The Electromagnetic Radiation Spectrum



How to read this chart

- This chart is organized in octaves (frequency doubling/halving) starting at 1Hz and going higher (2,4,8, etc) and lower (1/2, 1/4, etc). The octave is a natural way to represent frequency.
- Frequency increases on the vertical scale in the upward direction.
- The horizontal bars wrap around from far right to far left as the frequency increases upwards.
- There is no limit to either end of this chart, however, due to limited space, only the "known" items have been shown here. A frequency of 0Hz is the lowest possible frequency but the method of depicting octaves used here does not allow for ever reaching 0Hz, only approaching it. Also, by the definition of frequency (Cycles per second), there is no such thing as negative frequency.
- Values on the chart have been labelled with the following colours: Frequency measured in Hertz, Wavelength measured in meters, Energy measured in electronVolts.

Ultraviolet Light

- Ultraviolet light is beyond the range of human vision.
- Physicists have divided ultraviolet light ranges into Vacuum Ultraviolet (VUV), Extreme Ultraviolet (EUV), Far Ultraviolet (FUV), Medium Ultraviolet (MUV), and Near Ultraviolet (NUV).
- UV-A, UV-B and UV-C were introduced in the 1930's by the Commission Internationale de l'Éclairage (CIE, International Commission on Illumination) for photobiological spectral bands.
- Short-term UV-A exposure causes sun-tanning which helps to protect against sunburn. Exposure to UV-B is beneficial to humans by helping the skin produce vitamin D. Excessive UV exposure causes skin damage. UV-C is harmful to humans but is used as a germicide.
- The CIE originally divided UVA and UVB at 315nm, later some photo-dermatologists divided it at 320nm.
- UVA is subdivided into UVA1 and UVA2 for DNA altering effects at 340nm.
- The sun produces a wide range of frequencies including all the ultraviolet light, however, UVB is partially filtered by the ozone layer and UVC is totally filtered out by the earth's atmosphere.
- A bumblebee can see light in the UVA range which helps them identify certain flowers.

Emission and Absorption

- As EMR passes through elements, certain wavelength bands get absorbed and some new ones get emitted. This absorption and emission produces characteristic spectral lines for each element which are useful in determining the makeup of distant stars. These lines are used to prove the red-shift amount of distant stars.
- When a photon hits an atom it may be absorbed if the energy is just right. The energy level of the electron is raised – essentially holding the radiation. A new photon of specific wavelength is created when the energy is released. The jump in energy is a discrete step and many possible levels of energy exist in an atom.
- Johann Balmer created this formula defining the photon emission wavelength (λ); where m is the initial electron energy level and n is the final electron energy level:

$$\lambda = 364.56nm\left(\frac{m^2}{m^2-n^2}\right)$$

- Much of the interstellar matter is made of the simplest atom hydrogen. The hydrogen visible-spectrum emission and absorption lines are shown below:





- Max Planck determined the relationship between the temperature of an object and its radiation profile; where R_λ is the radiation power, λ is the wavelength, T is the temperature:

$$R_\lambda = \frac{37418}{\lambda^5\epsilon\left(\frac{14388}{\lambda T}-1\right)}$$



Cosmic Microwave Background Radiation

- CMB radiation is the leftover heat from the hot early universe, which last scattered about 400,000 years after the Big Bang.
- CMB permeates the entire universe at a temperature of 2.725 ± 0.001K.
- CMB was predicted in the 1940's by Ralph Alpher, George Gamow and Robert Herman.
- Arno Penzias and Robert Wilson accidentally discovered CMB while working for Bell Telephone Laboratories in 1965.
- The intensity is measured in Mega Jansky (Jy) per steradian. $1Jy = 10^{-26}W/m^2/Hz$



Close examination of slight CMB intensity variations in different parts of the sky help cosmologists study the formation of galaxies.

WMAP photo by NASA

Television

- Television is transmitted in the VHF and UHF ranges (30MHz - 3GHz).
- TV channels transmitted over the air are shown as TV.
- TV channels transmitted through cable (CATV) are shown as TV. CATV channels starting with "T-" are channels fed back to the cable TV station (like news feeds).
- Air and cable TV stations are broadcast with the separate video, colour, and audio frequency carriers grouped together in a channel band as follows:



- Satellite channels broadcast in the C-Band are depicted as TV. These stations are broadcast in alternating polarities (Ex. Ch 1 is vertical and 2 is horizontal and vice versa on neighbouring satellites).
- The 15.7 kHz horizontal sweep signal produced by a TV can be heard by some young people. This common contaminant signal to VLF spectra listening is depicted as ↔.

Radio Bands

- The radio spectrum (ELF to EHF) is populated by many more items than can be shown on this chart, only a small sampling of bands used around the world have been shown.
- Communication using EMR is done using either:
  - Amplitude Modulation (AM)

    OR
  - Frequency Modulation (FM)



- Each country has its own rules and regulations for allotting bands in this region. For more information, look up the radio communications authority in your area (Ex. FCC in the US, DOC in Canada).
- Not all references agree on the ULF band range, the HAARP range is used here.
- **RA**dio **D**etecting **A**nd **R**anging (RADAR) uses EMR in the microwave range to detect the distance and speed of objects.
- Citizens Band Radio (CB) contains 40 stations between 26.965-27.405MHz.
- Schumann resonance is produced in the cavity between the Earth and the ionosphere. The resonant peaks are depicted as S.
- Hydrogen gas emits radio band EMR at 21cm H.
- Some individual frequencies are represented as icons:

xxHz Submarine communications
⏲ Time and frequency standards
xxm Ham radio and international meter bands
▨ Miscellaneous short wave radio
W Weather stations
CP Cellular and PCS Phones (including; FDMA, TDMA, CDMA ranges)



Sound

- Although sound, ocean waves, and heartbeats are not electromagnetic, they are included on this chart as a frequency reference. Other properties of electromagnetic waves are different from sound waves.
- Sound waves are caused by an oscillating compression of molecules. Sound cannot travel in a vacuum such as outer space.
- The speed of sound in air is 1240kph (770mph).
- Humans can only hear sound between ≈20Hz to ≈20kHz.
- Infrasound (below 20Hz) can be sensed by internal organs and touch. Frequencies in the 0.2Hz range are often the cause of motion sickness.
- Bats can hear sound up to ≈50kHz.
- The 88 piano keys of the Equal Temperament scale are accurately located on the frequency chart.
- Over the ages people have striven to divide the continuous audio frequency spectrum into individual musical notes that have harmonious relationships. Microtonal musicians study various scales. One recent count lists 4700 different musical scales.
- Middle C is depicted on the chart as C



This image depicts air being compressed as sound waves in a tube from a speaker and then travelling through the tube towards the ear.

Gravity Waves

- Gravity is the mysterious force that holds large objects together and binds our planets, stars and galaxies together. Many people have unsuccessfully theorized about the details of gravity and its relationship to other forces. There have been no links between gravity waves and electromagnetic radiation.
- Gravity is theorized to warp space and time. In fact, gravity is responsible for bending light as observed by the gravity-lens example of distant galaxies.
- "Gravity waves" would appear as ripples in space-time formed by large objects moving through space that might possibly be detected in the future by very sensitive instruments.
- The speed that gravity propagates through space has been theorized to be the same as the speed of light.

Brain Waves

- By connecting electrodes from the human head to an electroencephalograph (EEG), it is possible to measure very small cyclic electrical signals.
- There has been much study on this topic, but like all effects on humans, the science is not as exact as the science of materials.
- Generally, lower brain wave frequencies relate to sleep, and the higher frequencies relate to alertness.
- Devices have been made for measuring and stimulating brain waves to achieve a desired state.

© unihedron.com 2004-12-12

Electromagnetic Radiation (EMR)

- EMR is emitted in discrete units called photons but has properties of waves as seen by the images below. EMR can be created by the oscillation or acceleration of electrical charge or magnetic field. EMR travels through space at the speed of light (2.997 924 58 ×10^8 m/s). EMR consists of an oscillating electrical and magnetic field which are at right angles to eachother and spaced at a particular wavelength. There is some controversy about the phase relationship between the electrical and magnetic fields of EMR, one of the theoretical representations is shown here:



- The particle nature of EMR is exhibited when a solar cell emits individual electrons when struck with very dim light.
- The wave nature of EMR is demonstrated by the famous double slit experiment that shows cancelling and addition of waves.
- Much of the EMR properties are based on theories since we can only see the effects of EMR and not the actual photon or wave itself.
- Albert Einstein theorized that the speed of light is the fastest that anything can travel. So far he has not been proven wrong.
- EMR can have its wavelength changed if the source is receding or approaching as in the red-shift example of distant galaxies and stars that are moving away from us at very high speeds. The emitted spectral light from these receding bodies appears more red than it would be if the object was not moving away from us.
- We only have full electronic control over frequencies in the microwave range and lower. Higher frequencies must be created by waiting for the energy to be released from elements as photons. We can either pump energy into the elements (ex. heating a rock with visible EMR and letting it release infrared EMR) or let it naturally escape (ex. uranium decay).
- We can only see the visible spectrum. All other bands of the spectrum are depicted as hatched colours ▩.

Système International d'unité prefixes (SI unit prefixes)			
Symbol	Name	Exp.	Multiplier
Y	yotta	10^{24}	1,000,000,000,000,000,000,000,000
Z	zetta	10^{21}	1,000,000,000,000,000,000,000
E	exa	10^{18}	1,000,000,000,000,000,000
P	peta	10^{15}	1,000,000,000,000,000
T	tera	10^{12}	1,000,000,000,000
G	giga	10^{9}	1,000,000,000
M	mega	10^{6}	1,000,000
k	kilo	10^{3}	1,000
		10^{0}	1
m	milli	10^{-3}	0.001
μ	micro	10^{-6}	0.000 001
n	nano	10^{-9}	0.000 000 001
p	pico	10^{-12}	0.000 000 000 001
f	femto	10^{-15}	0.000 000 000 000 001
a	atto	10^{-18}	0.000 000 000 000 000 001
z	zepto	10^{-21}	0.000 000 000 000 000 000 001
y	yocto	10^{-24}	0.000 000 000 000 000 000 000 001

Measurements on this chart		
Symbol	Name	Value
c	Speed of Light	2.997 924 58 ×10^8 m/s
h	Planck's Constant	6.626 1 ×10^{-34} J·s
$\hbar$	Planck's Constant (freq)	1.054 592 ×10^{-34} J·s
f	Frequency (cycles / second)	Hz
λ	Wavelength (meters)	m
E	Energy (Joules)	J

Conversions

$\mathrm{E} = h \cdot f$
$\lambda = \frac{c}{f}$
1Å = 0.1nm
1nm = 10Å
1Joule = 6.24 ×10^{18} eV

Gamma Rays

- Gamma radiation is the highest energy radiation (up to ≈ 10^{20} eV) that has been measured. At this energy, the radiation could be from gamma-rays, protons, electrons, or something else.
- Alpha, beta, and delta radiation are not electromagnetic but are actually parts of the atom being released from a radioactive atom. In some cases this can cause gamma radiation. These are not to be confused with brain waves of similar names.

Visible Spectrum

- The range of EMR visible to humans is also called "Light". The visible spectrum also closely resembles the range of EMR that filters through our atmosphere from the sun.
- Other creatures see different ranges of visible light, for example bumble-bees can see ultraviolet light and dogs have a different response to colours than do humans.
- The sky is blue because our atmosphere scatters light and the shorter wavelength blue gets scattered the most. It appears that the entire sky is illuminated by a blue light but in fact that light is scattered from the sun. The longer wavelengths like red and orange move straight through the atmosphere which makes the sun look like a bright white ball containing all the colours of the visible spectrum.
- Interestingly, the visible spectrum covers approximately one octave.
- Astronomers use filters to capture specific wavelengths and reject unwanted wavelengths, the major astronomical (visual) filter bands are depicted as X

Infrared Radiation

- Infrared radiation (IR) is sensed by humans as heat and is below the range of human vision. Humans (and anything at room temperature) are emitters of IR.
- IR remote control signals are invisible to the human eye but can be detected by most camcorders.
- Night vision scopes/goggles use a special camera that senses IR and converts the image to visible light. Some IR cameras employ an IR lamp to help illuminate the view.
- IR LASERs are used for burning objects.
- A demonstration of IR is to hold a metal bowl in front of your face. The IR emitted by your body will be reflected back using the parabolic shape of the bowl and you will feel the heat.
- Fiber-optic based infrared communication signals are sometimes amplified with Erbium-Doped Fiber Amplifiers EDFA

LASER

- LASER is an acronym for **L**ight **A**mplification by **S**timulated **E**mission of **R**adiation.
- A LASER is a device that produces monochromatic EMR of high intensity.
- With proper equipment, any EMR can be made to operate like a LASER. For example, microwaves are used to create a MASER.

Polarization

- As a photon (light particle) travels through space, its axis of electrical and magnetic fluctuations does not rotate. Therefore, each photon has a fixed linear polarity of somewhere between 0° to 360°. Light can also be circularly and elliptically polarized.
- Some crystals can cause the photon to rotate its polarization.
- Receivers that expect polarized photons will not accept photons that are in other polarities. (ex. satellite dish receivers have horizontal and vertical polarity positions).
- A polarized filter (like Polaroid™ sunglasses) can be used to demonstrate polarized light. One filter will only let photons that have one polarity through. Two overlapping filters at right angles will almost totally block the light that exits, however, a third filter inserted between the first two at a 45° angle will rotate the polarized light and allow some light to come out the end of all three filters.
- Light that reflects off an electrical insulator becomes polarized. Conductive reflectors do not polarize light.
- Perhaps the most reliably polarized light is a rainbow.
- Moonlight is also slightly polarized. You can test this by viewing the moonlight through a Polaroid™ sunglass lens, then rotate that lens, the moonlight will dim and brighten slightly.

Refraction

- Refraction of EMR is dependent on wavelength as can be seen by the prism example below.

By using a glass prism, white light can be spread by refraction into a spectrum of its composite colours. All wavelengths of EMR can be refracted by using the proper materials.



Convex lenses make objects appear closer and are used to correct far-sitedness.

Concave lenses make objects appear farther away and are used to correct near-sitedness.

Photo by STScI

Heavy objects like dense galaxies and large planets cause light to bend due to gravitational lensing.

Reflection

- Reflection of EMR is dependent on wavelength as demonstrated when visible light and radio waves bounce off objects that X-Rays would pass through. Microwaves, which have a large wavelength compared to visible light, will bounce off metal mesh in a microwave oven whereas visible light will pass through.



EMR of any wavelength can be reflected, however, the reflectivity of a material depends on many factors including the wavelength of the incident beam.

The angle of incidence (θ_i) and angle of reflection (θ_r) are the same.


FLUKE 115 TRUE RMS MULTIMETER
600.0
V AC
HOLD
MIN MAX
RANGE
OFF
COM
A
10 A FUSED
CAT III 600 V

Min/Max:
Beeps when a new min/max observed while calculating running average

AC Voltage
Shift: Frequency Counter

DC Current

AC Current
Shift: Frequency Counter

Shift Key:
Use to access the yellow labeled features

Screen Backlight:
Auto-off in 40 sec.

DC Voltage

Millivolts for AC
Shift: Millivolts for DC

Ohmmeter Setting

Continuity Beeper

Diode Test
Shift: Capacitometer

Ammeter Terminal

Common Ground (COM)

Everything but Ammeter Terminal



electricity from radiowaves 3


audio jack
White LED
1N 4148 Diodes
Ground wire (your hand)
LED HF


Glass housing
+
Lead In Wire
–
Connection point of lead wire to chip
"Catswisker" or point contact wire
Germanium chip
ANODE
CATHODE


Antenna
C1
C2
C3
C4
+
-
-0.001
Energy Harvesting

feluri (fig. III.9), schemele fiind echivalente cu reprezentarea de bază din fig. III.8. Diodele sînt legate în serie, în formă de patrulater, două avînd comun anodul (punctul *2*), iar celelalte două catodul (punctul *4*). Tensiunea alternativă de intrare se aplică pe diagonala *1—3*, iar consumatorul se conectează pe diagonala *2—4*.

Pentru a urmări funcționarea punții, să presupunem că prima alternanță sosită în nodul *1* este pozitivă. Ea blochează dioda D_2 și o deschide pe D_1, debitînd prin R_S un curent I_1 (săgețile pline), care se întoarce la

tice sau cu parametri cît mai apro-



III.9. Puntea redresoare în diferite reprezentări.

circuits used on LC "RadioWaves"








Insulated Aluminium Plate
4 1N4007 Diodes (As a Full Wave Rectifier)
47uF 250v capacitor
+
-
Earth

Plate dimensions 58x43cm
Plate insulated with tape
2.5mm solid copper wire
Earth is 1.5m copper pipe


16 cm length
aluminium
4mm thickness,
4cm width,
–
+

You can use electrolytic capacitor!

Germanium Diode

IN34 or IN34A

Aluminum electrolytic capacitors with non-solid electrolyte

minus (–)
minus (–)
minus (–)
minus (–)
Vertical-Chip (V-Chip)
Axial
Radial (single ended)
Snap-in


Germanium Diode
IN34 or IN34A
+
−
ANODE
CATHODE
Red
LED
A B C D E F G H I J
1N 34
Aluminium Tube
copper
wire
−
+


123
104
1N 34
104
123
ANODE
CATHODE
+
−
+
−
+
−

.01
10NF

.1
100NF

Ceramic
Disc
Capacitor

Germanium Diode
IN34 or IN34A




1:16 / 7:47





Earth

16 diodes
8 .22 100v
8 33uf 25v

OHMS ADJ
BATT CHECK
OFF
ON
X1K
X10
X1
AC IKV
DC IKV
MFJ
Model MFJ-281
4:57 / 7:47
CC
HD




J1
1
IO
GNDA
D1
1N34
D2
1N34
D3
1N34
D4
1N34
D5
1N34
D6
1N34
D7
1N34
D8
1N34
D9
1N34
D10
1N34
D11
1N34
D12
1N34
D13
1N34
D14
1N34
D15
1N34
D16
1N34
C1
220nF/100V
C2
220nF/100V
C3
220nF/100V
C4
220nF/100V
C5
220nF/100V
C6
220nF/100V
C7
220nF/100V
C8
220nF/100V
C9
47uF/16
C10
47uF/16
C11
47uF/16
C12
47uF/16
C13
47uF/16
C14
47uF/16
C15
47uF/16
C16
47uF/16
+
GNDA

AMBIENT POWER MODULE

(C) - GROUNDLOOP 2012

Circuit Diagram


Antenna
swagatam innovations
C1
C2
C3
C4
C5
C6
C7
C8
C9
C10
C11
C12
C13
C14
C15
C16
swagatam innovations
Earth

Parts List

All Diodes are 1N4148

C1---C8 = 0.22uF/100V mylar

C9----C16 = 33uF/25V electrolytic




Matrix Board
Resistor
Capacitor
Inductor
Diode
Crystal
Earphone


L1
Ground
Antenna
C1
L1/Ground link
D1/L1/C1 join
Wire
Link
D1
R1/Ground link
R1/D1 join
R1
Earphone Leads

24g NET
FRESHNESS IN 2 CALORIES
tic tac
Strawberry Fields



Antenna
C1
D1
L1
R1
E P
Ground


Antenna
3
Diode
1N34A
2
Resistor
A
Variable Capacitor
47K
.001uf
Capacitor
Ceramic
Earphone
Ferrite Loopstick Antenna
4
G
1
wire
5
Ground
O
G
A
Variable Capacitor
Top Side

[Sc

http://www.angelfire.com/electronic2/index1/DmCrystalSet.html]




Antenna wire
Tic Tac Radio
Earphone
Antenna lead in
Polyvaricon tuning capacitor
Ground wire




L1
C1
Antenna
Ground
R1
D1
Earphone Leads


Pizoelectric
Ear phone
Inductor
Germanium
Diode
To Ground
Connection
Variable
Capacitor

Connect
Antenna
Here


L1
100t
26 S.W.G.
(25 A.W.G.)
L1
A
G
O
VC1
D1
a
k
C1
RX
CRYSTAL EARPIECE
JACK PLUG AND SOCKET

TO AERIAL, AT LEAST 20 METRES (60FT) OF WIRE MOUNTED 7 METRES (20FT) MINIMUM ABOVE THE GROUND

DIODE LOAD RESISTOR, RX, IS ONLY REQUIRED IF CRYSTAL RECEIVER IS CONNECTED TO HEADPHONE AMPLIFIER.

TO EARTH, BISCUIT TIN OR 1M COPPER PIPE IN DAMP GROUND. CONNECTION TO CENTRAL HEATING PIPEWORK WILL OFTEN SUFFICE.


←ANTENNA
−
+
392J.
← GROUND
3 16





Step 1: LED+RF Diode



First Solder the led parallel to the Rf diode

Add Tip Ask Question Comment Download

Step 2: RF Diode+ LED+ Wires






LED
OA91
diode
1 wavelength loop
ca. 30 cm total
7.5 cm per side
resonant at
ca. 1000 MHz
~ 7.5 cm


IN23B
MICROWAV
ΕΛΕΜΑΝ
0:56 / 1:49


COM LOGIC


Hz
750VAC MAX
500V MAX
COM
NPN
EBCE
PNP
EBCE
LOGIC
200
2K
20K
200K
2M
Ω


Driven Element
28mm Sides
5-15 Trimmer
Capacitor
Reflector Element
30mm Sides
Diode
1000pF
+
To Voltmeter




D3
D5
D10
1SS86
LED
+
D2
D4
D6
D8


CB RADIO
0:46 / 0:53

DIY Wireless Power - Part 2: Simple Wireless Power Transmission! (CB)


ANt
Audio out
10K
FM simple
Crystal Radio.


Hi :D
FM/TV ANTENNA
GERMANIUM OR 1N34
WALL OUTLET GND
0:02 / 0:32

DIY Wireless Power - Part 1: TV/FM Antenna,1N34/Germanium Diode




The simplest FM Crystal Radio Circuit - http://billydiy.blogspot.hk
Antenna - Extendable Radio 1.8 meter. That also serves as tuning
1N34A,1N48,AA112, ISS86, ISS106
D1
J1
100K
D2
3.5mm Mono earphone Jack for Crystal earphone

Simple crystal receiver for FM

Carlo Bramanti



FM Crystal Radio Circuit


Simple FM Crystal Radio Circuit
Antena
8.4cm of #16
Copper Wire
1N60 Germanium
15pF
Output to
Amplifier
4 Turns of #18 copper
wire tapped at 2.5
turns. 12mm inside
diameter.
150K
50pF
Air variable

Parts List (some of these parts you can buy from our online store):

- 1N60 Germanium Diode
- 15pF Ceramic Capacitor
- 50pF Variable Capacitor
- 150K Ohm Resistor
- #16 & #18 Copper wires


1N34a
tip
33pF
100k
5-60pF
5 turns, 14mm ID, 20mm long













L - 4 turns #18 copper or silver wire, 12mm inside diameter, tapped at 2.5 turns
Ant - 7 inches of #18 bare copper wire
C1 - 18 pf ceramic capacitor
C2 - 50 pf air variable capacitor
D - 1N34 diode or rock crystal
R - 150K resistor

All passive components











Two 50v capacitors (0.22 microfarad). These two capacitors do NOT have a positive or negative lead.

Make sure all the diodes are all facing the same direction. Diodes come with a band which tells you which side is the negative (cathode) side.

Four germanium diodes

A = positive (anode) side.

C = negative (cathode) side

Negative leads

Positive leads

Two 50v electrolytic capacitors (100 microfarad). Each has a positive and negative lead. The negative lead is on the side of the capacitor with the "-" sign.


0:06 / 6:02

FIG. 10 BREADBOARD


Antenna
+
−
Ground

the board as shown in Figure 11. This unit is powering a small red LED indicated by the arrow.

FIG. 11 EXPERIMENT BOARD


ANTENNA
GROUND
NEGATIVE
LED
POSITIVE

ade to the twisted ends of the ceramic capacitors. When soldering the leads of the 1N34 diodes, care must be taken t

FIG. 9 TERMINAL STRIP


+
OUTPUT TERMINALS
−
GROUND TERMINAL
ANTENNA TERMINAL
Positive
Negative
+
−
+
−
C3
C4
C1
C2
X1
X2
X3
X4
Ground
Antenna

Amplifier circuit. The crystal radio used for example purposes is the crystal radio made from scraps here.


The crystal radio in the dotted box can be pretty much any crystal radio.
antenna
diode (1N34)
capacitor 0.001uF
ground
resistor 82kΩ
resistor 10MΩ
capacitor 1uF
+
B
transistor 2N4401
C
E
resistor 100kΩ
-
+
9V
battery
+
capacitor 10uF
+
capacitor 1uF
earpiece

SATURDAY, NOVEMBER 13, 2010

SIMPLE FIELD STRENGTH METER


20
10
7
5
3
1
0
3
50
100
TEAC




a
k
-
+
0.001uF
1-5turns

MY


Antenna
Diode
Transmission line
Diode
Shorted stub
Power Divider


DC Output
Antenna
Rectifier Circuit

4. Results and Analysis

The simulated and measured results at the output voltage of voltage multiplier circuit are shown graphically in **Figure 8**. From the graph analysis, the simulated and the measured results agree considerably with each other. The measured results are shown to be better than the simulation results. The reason behind this may be due to the uncertainty in series resistance value of the diode obtained from SPICE parameters in modeling as explained in Equation (5). This resistance vale of diodes in practical circuit may be lower than in the model, which provides fast discharge path, in turn rise in voltage as passes through the stages and reaches to final output. In this work, the DC output voltages obtained through simulation and measurement at 0 dBm re 2.12 V and 5.0 V respectively. These results are comparatively much better than in ref. [9], where in at 0 dBm, 900 MHz they achieved 0.5 V and 0.8 V through simulation and measurement increasing to 1.4 V, 1.67 V, 1.87 V and 2.12 V for 4, 5, 6 and 7 stages respectively compared to 2 mS as shown in [10]. **Figure 12** shows that the conversion ratio of 22 is achieved at 0 dBm input power and drops to 2.5 at –40 dBm. The highest value at 0 dBm is due to the innate characteristics of the zero bias Schottky diodes which conduct fairly well at higher input voltages.

5. Conclusion

From the experimental results, it is found that the pro-

Table 2. Component used in 7 stage voltage multiplier.

Name of component	Label	Value
Stage capacitors	C_1 - C_{14}	3.3 nF
Stage diodes	D_1 - D_{14}	HSMS 2850
Filter capacitor	C_L	100 nF
Load resister	R_L	100 kΩ



Figure 7. Photograph of assembled circuit board.

sign in this paper uses a capacitor across the load to store and provide DC leveling of the output voltage and its value only affects the speed of the transient response. Without a capacitor across the load, the output is not a good DC signal, but more of an offset AC signal.

In addition to the above, an equivalent load resistor is connected at the final node. The output voltage across the load decreases during the negative half cycle of the AC input signal. The voltage decreases is inversely proportional to the product of resistance and capacitance across the first stage was 3.3 nF, the second stage was 1.65 nF, third stage was 825 pF, fourth stage was 415 pF and so on. But keeping in view of testing, the capacitance values were chosen to have a close match with the standard available values in the market.

Simulation was carried out through 4 to 9 voltage doubler stages. Based on results obtained a 7 stage doubler is best to implemented for this application.

The design of the printed circuit board (PCB) was carried out using DipTrace software. The material used to



Figure 6. Schematic of 7 stage voltage multiplier.

Copyright © 2012 SciRes.



Fig. 9. Configuration of a single shunt diode (Class F) rectifier with a dipole antenna.



Fig. 10. Configuration of the proposed rectifier on coplanar striplines (CPS).

TABLE III
CIRCUIT COMPONENTS USED IN THE DESIGN

Component name	Nominal Value	Part number and supplier
D1	Schottky diode	SMS7630-079LF, Skyworks
L1	47 nH chip inductor	0603HP47N, Coilcraft
C1	100 nF chip capacitor	GRM188R71H104JA93D, Murata

antenna have a radius of 50 mm and a circumference angle of

respectively. While the imaginary part of the proposed OCFD is around 0 Ω at resonant frequencies 0.6 GHz, 1.2 GHz and 2.4 GHz, which are f_0, $2f_0$, and $4f_0$ respectively. These results have demonstrated that the simulated results agree with the OCFD theory as discussed in Section III–A. Furthermore, the imaginary part of the impedance of the antenna over the resonant frequency band from 1.4 to 2 GHz turns from negative values (for the reference antenna) to positive values (for the proposed antenna). As shown in Fig. 7(b), the value of the imaginary part of the proposed antenna impedance varies between 0 and 300 Ω over the desired frequency band. This feature could help the proposed antenna to produce a better conjugate matching with the rectifier, since the imaginary part of the impedance of the rectifier normally varies between -700 and 0 Ω as we discussed earlier. The simulated 3D radiation patterns of the proposed antenna at the frequencies of interest are depicted in Fig. 8. The 2D polar plots of antenna patterns in *E-plane* and *H-plane* are shown as well. Here we have only showed the directivity (maximum gain) of the antenna (without taking the mismatch loss into account). From Fig. 8, it can be seen that the antenna has symmetrical patterns about YOZ plane with a maximum directivity of 1.8 dBi at 0.9 GHz, 3.5 dBi at 1.8 GHz and 3.3 dBi at 2.4 GHz. The antenna is more directive towards the long arm direction at 1.8 GHz and 2.4 GHz with the half-power beam-widths (HPBW) of around 174° and 185° respectively. The HPBW is about 96° at 0.9 GHz.

Therefore, the proposed broadband OCFD antenna has obtained high impedance over a wide frequency range. The proposed design is just an example to illustrate the proposed new method. The details of the dipole could be modified according to the frequency of interest.

IV. RECTENNA INTEGRATION

A. Rectifier Configuration

The proposed high impedance OCFD antenna may directly conjugate match with the input impedance of a rectifier over a wide frequency band. The rectifier should only consist of few circuit components for rectification, DC storage and output. A single shunt diode rectifier is selected due to its very simple structure and high conversion efficiency [33]. The configuration of the single shunt diode rectifier with a dipole


AP



Sony Ericsson





ake and it can be sent in an envelope. I made tens of them and sent them to politicians, newspapers, universities... I gave some to local people, together with a user
later version, that can be rolled up in an envelope that fits the conditions to be sent with only one stamp.





BAT62 detection diodes are no more produced. **BAT15** diodes work fine but they wear out; after a few months they stop functioning. **SMS7630** diodes are great but very little and mechanically fragile. **MMSD701T1G** diodes are sturdy and powerful; an excellent choice for a beginner. Such SMD diodes do also work for cell phone frequencies, which allows to test out a snake with a calling cell phone pushed against it. But any detection diodes that can manage 100 MHz will do.

The LED I'm currently using is the **L-7113SEC-H** . It lights up with a low tension and a very low current (the bluer a LED, the more tension it needs). Its color is red yet close to orange hence it is easily seen by the human eye (the eye is most sensitive to green, yellow and orange). The beam is quite narrow so when the LED is directed towards somebody's eyes it will appear quite bright.

For the lengths of 37.5 and 112.5 centimeters, any electric wire with two copper conductors will do. Audio signal wire is a practical solution. Use the shielding as one of the two conductors. The lengths of the two segments must not be precise. What matters is that the total length of the snake be 1.5 meters. Do not hesitate to try out if a little longer or shorter snake gives better results.

A schematic of my current probes, that I connect to a standard multimeter, measuring Volts DC. The measure displayed by the multimeter must be multiplied by 10. When using a 200.0 mV scale, just read while forgetting the dot:



Lead Free Status	Lead Free
RoHS Status	RoHS Compliant

Features, Applications

The MMSD301T1, and MMSD701T1 devices are spin-offs of our popular MMBD301LT1, and MMBD701LT1 SOT-23 devices. They are designed for high-efficiency UHF and VHF detector applications. Readily available to many other fast switching RF and digital applications.

Extremely Low Minority Carrier Lifetime Very Low Capacitance Low Reverse Leakage AEC Qualified and PPAP Capable S Prefix for Automotive and Other Applications Requiring Unique Site and Control Change Requirements These Devices are Pb-Free, Halogen Free/BFR Free and are RoHS Compliant*

XXX G = Specific Device Code SMMSD701T1G = Date Code = Pb-Free Package
Rating Reverse Voltage MMSD701T1G, SMMSD701T1G Forward Current (DC) Continous Forward Power Dissipation = 25C Junction Temperature Storage Temperature Range Symbol VR Value to +150 Unit Vdc M G


152
2578
080704
-
+

Parts Required:

1. 100nF & 100pF
2. n4148 Diode x(2)
3. A bright good quality LED

Circuit Diagram:


2inch(5cm) hard wire
100pF
N4148
N4148
100nF
LED
Rookie
Electronics

Bread board Arrangement:


Rookie ELectronics


Rookie ELectronics

Strip Board:


Rookie ELectronics



Rookie ELectronics


10
15
20
25
30
10
15
20
25
30


104
Rookie ELectronics


2in (5cm) lead
100p
1N4148
1N4148
100n
LED
470R
Positive of multimeter
negative of multimeter

THE LED POWER METER CIRCUIT


American Tech


221


24 - 1N34A'S
12 - DISC CAP'S .001µF
12 - ELEC CAP'S 200V 22µF
ANTENNA
ANT IN
+OUT
-OUT
GND.






CE





UEi
DL49
DATA HOLD
DC A ZERO
OFF
DIGITAL CLAMP ON TESTER
-1.427
COM
CAT III
MAX 600V
V/Ω


UEi
DL49
DATA HOLD
DC A ZERO
OFF
LISTED 25PJ
CE
DIGITAL CLAMP ON TESTER
-1.427
COM
CAT III
MAX 600V
V/Ω


UEi
DL49
OFF
CE
DIGITAL CLAMP ON TESTER
45.8
COM


INNOVA
DC
AUTO
193.2
mV
Battery
Load
Test
1.5V
OFF
6V
9V
12V
ACV
DC10A
Auto Power OFF
COM
5:05 / 13:52

Tesla Free Energy Air Circuit


ANT
+
GND
PY-SCH
01
02
03
04
05
06
07
08
09
10
11
12
13
14
15
16
17
18
1:06 / 13:52
CC
HD



Tesla Free Energy Air Circuit



Tesla Free Energy Air Circuit




Ceramic Earphone
Diode
Resistor
Water Pipe
100 foot antenna wire as high as possible


40 turns of plastic coated wire tapped every 5 turns on a Quaker Oats Box
Aligator Clip
Screw
Diode
47k Resistor
To Antenna
Fahnestock Clips (typical)
Ceramic Earphone
To Ground


CE
3:11 / 3:37
Up next
Radio Galena



Diodo OA81.













Sin las medidas correctas

↓

menor eficiencia.


+
-
2224J
100.5
antena.



Ricevitore a cristallo per FM

Un progetto di Giacomo Cavuoti



Seguendo l'invito di Leonardo ho realizzato questo semplice ricevitore a cristallo per FM (fare clic sullo schema qua sotto per vederlo ingrandito).


200v+
200v+
— 6 '


Paper clip
Extended paper clip with heat shrink tubing
Loop
Finished probe

Figure 1: Magnetic field probe build from a paper clip.

YAESU
HOME
SEL
CLAR
VFOa CW
14.054.00 R
SW
A
B
C
F
V/M
LOCK
PWR
AF SQL/RF
ANT
C-POISE
1:54 / 2:18
HD


Simple SWR Indicator for QRP
YAESU
HOME
CLAR
0:01 / 2:18
HD


Wire Antenna
Magnetic Headphone
Pencil Lead
Copper Wire
Rusty Razor Blade
Ground
Point of Contact


Bogen T725 Transmatch
MARX 2013




SEL.
BRD.
0
10
20
30
40
50
60
70
80
90
100


A
G

Another Prototype similar to the Heathkit using toroid coil





This is a dual tuned crystal set made in a box like the CR-1, just a fun prototype I made a few years back. It pulls in AM stations loud and clear.


02/6/2016
DANIEL MUNHOZ DA S
DIODO N
TRANFORMADOR
FERRITE COM BOBINA
100N
capacitor
ATo FALENT
8Ω
GALENA
RÁDIO SEM pilHA ou BATERIA.
RÁDIOS LOCAL AM.
1:16 / 1:28

GALENA , Rádio AM ,sem pilha.

Up next


RADIO GALENA
ANTENA
L1
D1
C1
C2
T1
AURICULAR
TIERRA


Antenna
Ground


Antenna
Ground



Click on photo for a larger picture






AERIAL CONNECTION
EARTH WIRE


HC0004
DC4V
0:07 / 3:32
HD

New idea - You can make Solar Cell from LED (Free Energy)







Instructions for using Philmore Crystal Radio Detector

AERIAL
EAR PHONES
LEADIN WIRE
D
C
B
A
RADIATOR OR WATER PIPE

This Detector is a radio in itself, as it is possible to get reception with it alone, provided you are within 25 miles of a broadcasting station. Under very favorable conditions reception is sometimes possible at much greater distances.

In order to get reception, you need an aerial kit and headphones. The AERIAL may consist of 100 to 125 feet of copper wire and two insulators. Attach insulators to each end of the wire. Stretch the wire allowing as little sag as possible. No part of this wire should touch any portion of the building or any other obstruction.

The LEAD-IN may consist of any desired length of covered wire which will reach from the aerial to the set. Scrape each end of the lead-in so that the wire is absolutely clean. Wind one end securely around the aerial wire. Place the other end in the clip marked "A".

There are two cords leading from the headphones. Connect the cord "C" as illustrated, from the earphone to clip "B" or the clip under the detector arm. The other wire from the earphone marked "D" is to be connected to water pipe, radiator or any other suitable connection to be used for the ground.

You are now ready to receive broadcast. Find a sensitive spot on the crystal by means of the catswhisker. You may find it necessary to "hunt" for live spots on the crystal as only some parts of a crystal are sensitive, and unless you find these sensitive spots you will not hear anything.

If you do not at first get results, do not blame the detector, as every set is tested before being shipped and will positively get results under the proper conditions. Do not write in and ask what the trouble is for a personal examination of your entire hook-up will be necessary. Go over your aerial, ground, various connections, etc., and if necessary get someone who thoroughly understands radios to help you.




Unscrew to remove or turn crystal
Crystal holder
Cat's whisker
Terminal
Chuck
Ball – rotates in housing
Crystal
Shaft – slides through ball
Terminal
Operating handle
5 cm

Modern diode (7·5 X 2·5 mm)

Majoritatea componentelor active folosite în circuitele electronice moderne sînt dispozitivele bazate pe semiconductoare.

Cel mai simplu dispozitiv este *dioda* punctiformă cu germaniu. Ea are proprietatea de bază de a se comporta ca şi cum este conectată direct la o sursă electrică de curent continuu (plusul sursei la plusul diodei) şi ca un izolator, cînd este conectată invers la aceeaşi sursă (plusul sursei la minusul diodei), ca în figura 2.9.


capsulă
arc
cristal
conexiune
+
-

FIG. 2.9.

Dioda punctiformă cu germaniu


Diodă stabilizatoare
Diodă varicap
Dioda luminiscentă LED
Fotodiodă

FIG. 2.10.

Tipuri de diode semiconductoare



FIG. 2.11.

Puntea redresoare

Fig. 7




Antenna
50mt
90 spire su rocchetto diam 9
50 affiancare e
40 sovrapposte sul lato interno
ferrite 8 x 16
OA95
cuffia
2000Ω




Catswisker
Galena Crystal in bed of Woods metal


+
−


ANT.
90 SPIRE CON
PRESA OGNI
10ª SPIRA
FILO 0,8 DC
20 SPIRE
6 cm. ø
TERRA

Lead sulfide crystals, also called "galena"



Crystal detector, the lever was used to position the spring contact on a crystal face capable of performing the radio signal detection.

Yeah , but how does a galena radio work? Here is the constructive scheme of a receiver of this kind, obtained from a book of popular radio comm
to the knowledge of the radio, ed.Hepep 1943):



Fig. 13.5. - Realizzazione pratica dello schema di fig. 13.3 con aggiunta della bobina d'antenna.



Picture 1. "Ernest Roger" Crystal detector from 1920

Many of the **younger generation** never had the pleasure to have, or to even see a real beautiful crystal detector as shown on **Picture 1**. A detector like that was the product of the early 1920's, and it was an expensive, quality, well made product. They were usually hands assembled with machine made components.

This particular "**Ernest Roger**" detector device is built on an insulated base, either wood or most likely of Bakelite, the most widely used and only available plastic material at the times.

Many of the younger generation never had the pleasure to have, or to even see a real beautiful crystal detector as shown on **Picture 1**. The new generations are much too involved with technology and playing on their computers or going to an **online University**. This excellent detector holder used copper, brass and bronze generously for the crystal holder and for all of the **electrodes**.

The most often used crystal in this and similar detectors - then and now - was **pyrite** or galena as shown in the 1925 listing in a table in the **"American Mineralogist"** publication, that has a listing of thirty three minerals catalogued with rectifying detector properties.

Among the very first commercially produced diodes is the 1N21B shown on **Picture 2**. It is more than curious, that this "diode" is enclosed in a case on which there is a slotted screw-head is just visible on the wide side (lower right). That screw is connected to a fine "cats whisker" steel wire, a few turns of a spring-like device, terminating in a point that is in touch of the germanium semiconductor material connected to the top left diode terminal.

The arrangement is much smaller, and more diode like, then the detector on **Picture 1**., but it made in a very similar arrangement, which has became known as the point contact diode. From these and similar germanium diodes, evolutionary progress leads us to current PN junction Silicon, Gallium Arsenide or other more exotic semiconductor materials which are the achievement of the latest scientific age and many years of steady experimentation, research and development.



Picture 2. Early point contact diode with adjustable srew



Picture 3. Point contact diode

Picture 3 shows the cross section of a hermetically glass enclosed, point contact diode. If the left side, point contact terminal would be attached to a screw and a short spring, and the glass envelope would have a threaded metal part in it, the **Picture 2** and **Picture 3** devices would be nearly identical.

These point contact "cat's whisker" devices, are still made occasionally because of their very small capacitance. As it was discovered early on, they are highly useful in high frequency electronics. All the way up to microwave frequencies they useable. The simplest radar detectors usually made with a simple horn **antenna**, a diode similar to **Picture 2** and **Picture 3** and a transistor amplifier. If the designer keeps it simple, and don't use a local oscillator, such radar detectors


Nickel and Silver Filings
Vacuum Tube



Meter on 200 Ohm Range

Display Indicates Activation = 11.2 Ohms

Coherer Detector

Press to Spark

Spark Gap

11.2
DCV
ACV
DCA
OFF
ON
10ADC
VΩmA
COM
CEN-TECH
DIGITAL
MULTIMETER


NAKO
NA-811A
S


Mario
0:08 / 9:55
HD


:55
CC
HD


1N34A
+
5V .1F
-
+
LED
Patente
US 685957




10A


795
55


469
LED
685957


THE SUPER CRYSTAL SET
AERIAL TAP
0
1
2
3
4
5
6
7
8
9
10
TUNING
0
10
20
30
40
50
60
70
80
90
100
PHONES


Tuning
Aerial Switch
Phone Socket
Blocking Capacitor
Detector
Tuning Coil
Clip
Coupling Coil
Aerial Coil
Aerial Capacitor
1 Aerial 2
Ground
0
1
2
3
4
5
6
7
8
9
10



KB8TAD


aerial
tuning coil
7-point switch
binding post
crystal detector
ground
earphone


KB8TAD


ANTENNA
GROUND
1/16 IN
10
9
8
7
6
5
4
3
2
1
1
2
3
4
5
6
7
8
PHONE

FIG. 4. ASSEMBLED RECEIVING SET


4 INCHES DIAMETER
2
R
TUNER
4½"
U
TWISTED TAP
Z
5
GROUND
10 TURNS TO EACH TAP
10 9 8 7 6 5 4 3 2 1
1-TURN TO EACH TAP
W
3
SWITCH CONTACTS
Y
V
SWITCH ARM
ANTENNA
4
CRYSTAL DETECTOR
S
6
1
X
GROUND
T
TELEPHONE RECEIVERS

FIG. 3 WIRING DIAGRAM AND DETAILS OF RECEIVING SET

FIG 2. RECEIVING SET, WITH ANTENNA AND GROUND CONNECTIONS


J- LEAD-IN WIRE
K- LIGHTNING SWITCH
L- GROUND WIRE
N- LEAD TO RECEIVING SET
O- INSULATING TUBE
P- RECEIVING SET
Q- GROUND FOR RECEIVING SET
J
O
N
K
L
P
N
Q

FIG. 2


B
C
A
E
D
F
ANTENNA
G
H
I
J
K
O
N
L
M

FIG. I. SINGLE-WIRE ANTENNA, LEAD-IN, AND LIGHTNING SWITCH

A - SCREW EYE
B - ROPE
C - PULLEY
D - ROPE
E - INSULATOR
F - ANTENNA
G - INSULATOR
H - ROPE
I - SCREW EYE
J - LEAD-IN WIRE
K - LIGHTNING SWITCH
L - GROUND WIRE
M - GROUND PIPE
N - LEAD TO RECEIVING SET
O - INSULATING TUBE


Inductor, L
Capacitor, C
Capacitor bracket
Connexion to moving plates and frame
P
S
Audio output transformer
Diode, D
Connexion to fixed plates
Tuning knob
1
2
3
4
5
6
E
A
Phones
(Mains) terminal block
Plastic barrel stereo line socket (see Fig.11)
Wooden board

Fig. 14 Suggested component arrangement for elementary crystal set


(Wires not connected)
80
Arrow indicates variable tap
o
L
C
AA119
OA91
etc.
P
S
8 Ω
Headphones
8 Ω
(Wires connected)

(i) Circuit


Turn number 0 5 10 15 20 ....
4 cm diam. tube
Tapping loops (total 7)
5 turns
(Ends cleaned and tinned)
Stout copper wires (0·8–1·0 mm)* as connexions and support
Soldered
Tube
Winding
Terminal block

(ii) Coil tappings and mounting

Fig. 16 Circuit with tapped inductor


Soldered
Winding
Flexible lead
Terminal block
Tube

(iii) Alternative mounting


To variable capacitor (see Fig. 14)
fixed plates
moving plates
Connections to inductor
Turn number → 0 5 15 25 35 80
[see (i) and (ii)]
10 20 30
Copper wires supporting inductor or flexible leads when inductor supported on receiver base
P
S
Diode
1 2 3 4 5 6 7 8 9 10 11 12
E
Flexible lead
Headphones (low impedance)

(iv) Suggested component arrangement

---

* 21–19 SWG, 20–18 AWG

required) and a *flying lead* for the diode, these components are shown in Fig.16(iv). This is doing the job properly, there is no reason however (except for unreliability of contact) why both aerial and diode flying leads should not terminate on *crocodile clips* and be clipped onto the chosen taps as required.

Earth is connected to terminal 1 and the headphones to 11 and 12. Both the aerial and the diode lead are tried at terminals 2 – 9, a game of "poke and hope" but one which can be rewarding. Remember that generally but not always, the tappings with the lower numbers reduce loudness but increase selectivity. Aerial to terminal 8, diode to 9 brings us back to Fig.13(i) of course.

5.2 SWITCHED SELECTIVITY

A technique of selection of aerial and diode tappings by means of rotary switches has much to recommend it especially if setting changes are likely to be needed for reception of different stations. In this case two single-pole 8-way switches are required, usually obtainable as 12-way so leaving 4 spare. The drawing symbol shown in Fig.17 speaks for itself with regard to its action and it may be found from catalogues that there are two types of *action*, by which is meant the manner in which the switch changes over from one contact to the adjoining one. *Break before make* switches disconnect one circuit before the next is connected and *make before break* have a change-over period during which both circuits are connected at once for a short time. Either type is suitable for us. A knob to rotate each switch is also required, a small one, say 2 cm diameter or less is ample, if with an indicator line or pointer, so much the better. The modifications to Fig.16 for switching are given in Fig.17.

With such rotary switches a search for the optimum arrange-



Fig. 17 - Switching aerial and diode leads

variable capacitor, the two switches and the headphone socket, the latter must then be of the chassis type. A pair of terminals for aerial and earth completes the receiver. On the panel the two rotary switches are easily labelled 1 – 8 but we are still uncertain about a tuning dial because we may not have the right variable capacitor for the inductor, this is the subject of the next section.

5.3 GETTING THE RANGE RIGHT

This is where we pause in receiver construction to remove some of the confusion which may still exist with regard to the tuning ingredients, wavelength, frequency, inductance and capacity, each of which has some bearing on the others, to fit together these four pieces of the puzzle, so to speak. For most crystal sets the inductance is fixed according to the variable capacitor available and we tune the receiver over the range by rotating the variable capacitor knob over half a


1900
(160)
30
1450
(210)
50
1200
(255)
80
1050
(290)
100
920
(325)
130
850
(350)
150
780
(385)
180
730
(410)
205
690
(435)
230
650
(460)
260
630
(480)
280
600
(500)
310
570
(525)
335
550
(545)
360
530
(565)
390
20
30
40
50
60
70
80
90
100
110
120
130
140
150
160
Frequency (kHz)
Wavelength in brackets
Capacitance (pF)
Degrees rotation
Capacitor plates fully open (0°)
Capacitor plates fully meshed (180°)

Fig. 18 Approximate capacitance and frequency values for 365 pF variable capacitor and 230 μH coil


C5
AA119
OA91 etc.
C3
47
pF
C1
365
pF
L1
L2
C2
365
pF
C4
47
pF
Air-cored transformer*
Iron-cored
transformer*

(i) Circuit


Fixing
screw holes
2 fixing screws
Screw
terminals
Position 1
Position 2 (shifted left)

(iii) Moving inductor L_1


To variable capacitor C1
(first section, fixed plates)
L1
Winding
(see Fig. 16)
9
8
7
6
5
4
3
2
1
Terminal block
(movable)
Aerial
To variable capacitor
(moving plates)
To variable capacitor C2
(second section, fixed plates)
L2
Winding
(see Fig. 16)
Diode and
matching
transformer
as in Fig. 16(iv)
1
2
3
4
5
6
7
8
9
10
11
12
Diode flexible
lead
Terminal block
(fixed)

(ii) Arrangement of inductors

Fig. 21 A double-tuned crystal receiver

* See Section 2.4


(Chimney fixing even better)
Support wire or rope
Aerial insulator
Aerial
To receiver
Down lead
Span (preferably 15 to 18 m)
Aerial insulator
Support wire or rope
End of aerial wire (not connected)
(Fixed as high as possible to pole, tree or building)

(i) Outdoor Aerial


Hole in insulator
Span wire
Lead-in (or free end)

(ii) Attaching aerial to insulator


Ceiling
Insulated screw-hook
Aerial
Room
Down lead

(iii) Room aerial


Water pipe
Earth lead to receiver
Several turns of wire (finally secured by hose clip)

(iv) Earth connection to water pipe


Earth lead
Copper pipe
Washers
Ground

(v) Lead bolted to earth spike

Fig. 12 Aerial/earth systems


Headphones
8 Ω
8 Ω
Signal current
Primary winding
Secondary winding
Headphone cord
16 Ω
3200 Ω
16 Ω
Ring
Tip
Sleeve
Tip
Ring
Sleeve
200 : 1 impedance ratio
Sleeve connexion not used
Matching transformer
Socket
Jack plug

Fig. 11 Matching a high impedance receiver to low impedance headphones


RADIO GALENA
ANTENA
D1
L1
C1
C2
T1
AURICULAR
TIERRA


TIERRA
ANTENA
5:21 / 11:30
Up next
AUTOPLA

Radio Galena en la practica (con diodo detector)


ANTENA
1:30


NA
TIERRA
1:30


ANTENA
11:30


11:30


TIERRA
:30


TIERRA
1:30


ANTENA
1:30


ANTENA
11:30


NTENA


ANTENA
TIERRA


TIERRA



Tubo de PVC de 40 mm de diámetro, y 12 cm de largo



ANTENA
TIERRA


TIERRA
ANTENA
30


1:30


0:48 / 2:05
Up next

Rádio de Galena com Antena de Quadro - UTFPR - TD



BiNGER R.
BRiel T.


R
R
A






BiNGR R
Riel T.




FABINER R.
GABRiel T.
Guilherme T.
MATHIAS C.
THOMAS G.
Eng. Eletrônica
D.G
C.V
"A GALENA!"


FABINHO R.
GABRIEL T.
Guilherme T.
Mathias G.
Thomas G.
Eng. Eletrônica
"A GALENA!"
0:08 / 2:05







Subscribe
1:25 / 2:04

1 Watt Nuclear Generator - Free Energy

Gadget Addict

Subscribed
53K

138,050 views

Add to
Share
More
905
555

Shop "tritium battery"

Sponsored
Betalux Tritium Exit
Lithonia EXR LED EL
DQG Fairy Brass XP-


To radiating wire
M4-M6 Bolts
To Common Ground
Insulator
Soldered joint
RG Coaxial cable
Enclosure Case
UN-UN
IV3SBE
Balun Transformer
T-200-2 amidon
14 twin turns
Crimp Joint
SO-239 Chassis Mount

Figure 5

Voltage Balun / "Magnetic Balun"

From GW0VMR's plan


To Long-wire aerial
Household 240v appliance wire
10 to 15 turns of Wire around Rod
CO-AX
Ferrite Rod
15 to 20cm long


10 metri filo elettrico per impianti rame da 1 mm
CANNA DA PESCA fibra vetro 10 mt
montaggio a CANNA DA PESCA
UN-UN
RTX
10 metri
montaggio a LONG WIRE
filo 10 metri
UN-UN
I6IBE
Ivo Brugnera
UN-UN 4:1
SO239
PL259
CAVO 52 OHM
TOROIDE T200-2 ROSSO
19 SPIRE BIFILARI
filo SMALTATO rame ∅ 1 mm
RTX
al TUNER

BALUN 9:1 Antenna Long Wire


Beverage antenna
Antenna Long Wire
9 spire trifilari
filo rame smaltato 1mm
A
C
E
RTX
B
D
F
TOROIDE T-200/2
I6IBE


Antenna Long Wire or Beverage
(450 - 550 Ω)
A
C
E
coax 52 Ohm
RTX
(50 - 75 Ω)
B
D
F


E
C
A
to Beverage
Antenna
F
D
B
cavo 52 Ohm
RTX 50-75 Ohm

Bal-Un 2:1 per antenna DELTA-LOOP


Balun 1:2
100 Ohm
BAL
OE7OPJ (c) 2010
50 Ohm
UNBAL



by OE7OPJ

Toroide	Numero di Spire	Potenza Supportata
T80-2	25	60 Watts
T106-2	16	100 Watts
T130-2	18	150 Watts
T157-2	16	250 Watts
T200-2	17	400 Watts
T200A-2	13	400 Watts
T400-2	14	1000 Watts


SO239
RTX
DELTA LOOP
Z = 120 Ω

Autoformer, not a parallel transmission line – Ruthroff balun (voltage)





One or more parallel transmission lines, connected various ways – Guanella balun (current) – core is used solely for choking action

F/B: 0.00 dB; Rear: Azim. 120 deg, Elev. 60 deg

Coax is unbalanced …..


COAXIAL CABLE
braided shield
foil shield
center conductor
outer jacket
dielectric


300 Ohm
450 Ohm

… Ladder line is balanced

Coax is unbalanced, while ladder line and open wire feeder is balanced, as long as it is used properly and is kept away from metal and "earthy" materials

Convert parallel feedline to coax


CRYSTALS • OSCILLATORS • FILTERS • OPTICS
Savoy
ELECTRONICS, INC.
TOLL FREE 800-327-1282

Types of Parallel Line

- **Open Feeder** or **Ladder line**
  - Typ 450 and 600 ohm
- **Twin Lead**
  - Common for (old) outdoor TV antennas
- **Window line**
  - Commonly available today








Coaxial Cable to
Transmitter
RCA Ground Lug
CommonGround
RCA Center Pin
From
Synthesizer
To
Transmitter
Z5U
.01M
100V
MURATA
3
1
4
2


A
B
C
D
agujeros
ventilación

Formula LUNGHEZZA DELTA LOOP	Esempio 14.00 MHz (20 metri)	Lunghezza TOTALE del LOOP
Velocita'Luce : Freq MHz x 0.97= L	**299.8** VL : **14.100** MHz x **0,97**	**20.624** metri totale loop
$L=\frac{300.000}{MHz}\times 0.97$	I6IBE	
Formula LUNGHEZZA Stub coax 75 Ohm	Esempio 14.00 MHz (20 metri)	Lunghezza TOTALE cavo 75 Ohm
Lunghezza LOOP x 0.66 : 4	**20.624** x **0.66** : **4**	**3.402** Metri coax RG-59


16 spire filo ø1,5
su tubo plastica ø2,5
AVVOLGIMENTO BIFILARE
BALUN 4:1
ALLA
DeltaLoop
Bilanciato
SO239
INGRESSO 50 Ω
sbilanciato


alla Delta Loop
bilanciato
I6IBE Ivo
SO239 sbilanciato

BALUN 4:1


I6IBE
Choke RFI
toroide
cavo RG-58
5+5 spire
controfase
BOCCHETTONE
INGRESSO ANTENNA
SO-239

2. Insert metal electrodes and attach multimeter leads [copper (+), aluminum (-)] For measuring direct current voltage: set multimeter function switch to “DCV: 20” take a reading in volts DC. for measuring direct current: set multimeter function switch to “DCA: 20m” take a reading in milliamps (mA) DC.

Lawn battery (summer). INSET: Marsh mud battery. (Circles show position of electrodes.)



Calculating Earth Battery Power (W = I * V)

EXAMPLE: A lawn battery in late summer (little rain) produces a 0.65V, 0.2mA current. A battery power calculation of 0.00013W (0.13mW).


©2016 Frank Dörenberg N4SPP
4:1 BA



1:1 Ruthroff Voltage Balun

* 450 Ohm ladderline

Steve Nichols G0KYA

The Ruthroff or voltage balun is another type. Voltage baluns balance the voltages. Current balance is considered to be superior to voltage balance. Voltage baluns should not be used in lines with high SWR. They have the narrowest impedance and frequency range of any balun type. Properly designed voltage baluns have low common mode impedance. Properly designed current baluns have high common mode impedance, and provide better balance. If you want to stop common mode currents flowing on your coax a current balun is a better choice. But in the Carolina Windom, which uses the vertical coax as a radiator you WANT common mode currents, so a Ruthroff voltage balun is better.

F/B: 0.00 dB; Rear: Azim. 120 deg, Elev. 60 deg



1:1 Guanella current balun

* 450 Ohm ladderline

Steve Nichols G0KYA

A Guanella or current balun is very common. Current baluns stop RF from coming back down the outside of the coax shield, and are so called that because they "force equal currents in each side of a dipole"


DİPOLE
DİPOLE
SICAK LEHİM
A
B
C
Ø 12 mm 65 mm FERİT
C
B
A
SO 239 KONNEKTOR

2mm Tel
8 Tur Sar

© Azega.com


Ion Harvesting Materials Test Fixture
Material being tested
Insulated Wire
Ion Emitters
Multimeter
Earth Electrical
Ground Connection


130 ft (39.62m)
Remote Field R&D Lab
Ion Power Group Test Site #1

DANGER
HIGH VOLTAGE
KEEP AWAY
1
2
3
4
5
6
7
8
9
10




DANGER
HIGH VOLTAGE
KEEP AWAY
1
2
3
4
5
6
7
8
9
10
Ion Harvesting Electrical Storage
(10) General Electric capacitors in parallel
rated at 41.kV totaling 75.uf capacity
IonPowerGroup.com


HIGH VOLTAGE
KEEP AWAY
Electrically Isolated
Thru-wall Cable Pass
Capacitor Storage Bank
High Voltage Dropline
Earth Ground W
8
9
10


Weather Station
High Voltage dropline from ion collectors @ 130 ft
Strain Relief
Electrical Isolation dual-tube
Remote Field R&D Lab
Electrical Isolators


Towers 130 ft (39.624m)
Dropline
R&D Field Room

Giant Test Fixture located at Ion Power Group's Florida R&D Test Site
Four (4) towers 130 ft (39.624m) high - approx 330 ft between towers


SEM MAG: 41.54 kx
DET: SE Detector
HV: 10.0 kV
VAC: HiVac
1 µm
Digital Microscopy Imaging

Ion Power Group’s new method of coupling to atmospheric electricity is vastly different from all previous techniques by virtue of our patented breakthrough revealing that carbon nanomaterials such as **Graphite (and Graphene) microscopic shown at left, macroscopic shown at right are significantly more effective at coupling to airborne charge carriers (ions) than metal.** The use of carbon based nanomaterials distinguishes Ion Power Group from all other researchers.



I cut a hole in the side of the balun then cut the end off a piece of coax cable I had and soldered it to the contacts of the coax connection.

EXAMPLE: W1JR (Reisert) Cross-Winding Method


1
9
10
3
2
1
4
10
11
5
12
13
6
9
7
14
15
8
16
9
17
18
18




BALANCED
UNBALANCED



Balun 1: 1 for HF

1:1 Voltage balun ("Ruthroff")


50Ω
Unbalanced
50Ω
Balanced
M0UKD
1
2
3
1
2
3

10 - 15 trifiler turns on ferrite rod.

1:1 ferrite rod voltage balun


50Ω
Unbalanced
50Ω
Balanced
1:1 Voltage Balun on Ferrite Rod - M0UKD


711
1N5





How to convert seawater into drinking water [Class 6, Chapter 14, ...

SUBSCRIBE
2:14 / 2:49
CC
YouTube


How to convert seawater into drinking water [Class 6, Chapter 14, ...

SUBSCRIBE
1:09 / 2:49
YouTube



Emergency DIY Water Distillation for Survival Bug-Out Bag

Three 1/2" Cop El 45 Deg
Wet Rag
1/2" x 22" Cop
Stainless Steel Funnel
Dirty/Salt Water
Clean/Fresh Water
2:59 / 3:27
YouTube


Solar Water Distilling
Simple Survival Water Distilling





How to Make A Solar Water Distiller



Aquamate Solar Still

Turns Sea Water Into Fresh (Potable) Water

Inflatable & Re-useable

SURVIVAL METRICS.COM
N
W
E
S

Solar Still

Turns sea water or impure water into drinking water



1. Remove from pack and retain pack to top up salt water in still.
2. Lay out Solar Still and inflate valve Ⓐ on floatation ring by mouth or by liferaft or dinghy pump.
3. Inflate clear dome to obtain shape using valve Ⓔ in base. Do not over inflate. It may be necessary to manually regulate dome pressure during high temperatures.
4. Attach tapered bag Ⓑ and attachment cord Ⓒ to boat or liferaft.
5. Pour 5 litres of sea water into tapered bag Ⓑ using pack which holds 5 litres (approx). Close valve Ⓕ after filling.
6. Ensure both valves Ⓖ are open in reservoir feed tube and drinkable water will start to collect in reservoir Ⓓ. Air may need to be squeezed out to assist collection of water.
7. Ensure the Solar Still is kept in direct sunlight whenever possible.
8. Re-fill Solar Still and inflate/deflate dome as required.
9. Daily – Agitate Solar Still to dampen fabric.
10. To drain unwanted water open valve Ⓔ in base.
11. Shelter Solar Still during bad weather.

IMPORTANT

IF INNER BLACK MATERIAL SALTS UP FILL WITH SEA WATER AND AGITATE TO CLEAR SALT CRYSTALS AND DRAIN AWAY. PROCESS DRINKING WATER AS INSTRUCTIONS UNTIL SALT IS NO LONGER PRESENT. IN NO CIRCUMSTANCES DRINK WATER THAT TASTES OF SALT.

5 060259 930188 >

AQUAMATE PRODUCTS

NATO Stock No. 4610-66-144-2646

P.O. Box 6032 Dunmow CM6 3AS U.K. Tel: +44 (0)1371 830 216 Fax: 831 733 e-mail: aquamatesales@aol.com



Ion Emitters project electrically charged ions into the air to simulate natural ions found at altitude

Graphene or Graphite fibers produce high voltage electricity by harvesting airborne ions

1000x probe and meter display the voltage and current generated by harvesting airborne ions


RTV Adhesive
Carbon/Graphite Fiber
Bare Aluminum wire

Image of a patented Ion Collector made of carbon/graphite weighing approximately 1 ounce.


Large aluminum collection grid (Mesh type)
grid must not touch the earth, place it on plastic or wooden poles.
8 Gauge outdoor electrical wire runs to home and DC Fuse breaker box
-
+


A
a
b
c
d
e
L
3a
3b
W
S1
S2
E1
E2

Fig. 24.


HARNESSING NATURE'S ELECTRICITY
INSULATORS
IRON CABLE
2200 FEET LONG
ADJUSTABLE SPARK GAP
260 FT.
CORONA OF BLUISH GREEN LIGHT
INSULATED WIRES
2,600,000 VOLTS - 1927
10,000,000 VOLTS EXPECTED-1928
TEST HUT 660 FEET FROM SPARK GAP

Remarkable European Experiments with Atmospheric Electrical Discharges with Potentials as High as 3,000,000 Volts

By HENRY TOWNSEND

elevation of 350 ft., and these students of natural electrical phenomena have found a very desirable location in the Alps, where they can suspend between one mountain and an adjacent one, a strong iron cable having a length of about 2,000 ft. This cable is about 250 feet above the intervening valley, and from it these daring engineers have suspended a coarsely woven wire net, which serves as an electrical capacity to gather the electricity from the atmosphere. As shown in the pictures, the wire net is supplied with numerous sharp points to aid in collecting the current from the air.

As the accompanying photographs of the actual apparatus and wire cable used last year clearly show, an adjustable spark gap of considerable length is provided. By adjusting this spark gap to various lengths, it is possible to judge the voltage of the discharge which leaps the gap at any moment. Mr. F. W. Peek, Jr., the well-known American worker in the realm of high voltage measurements, together with other engineers, have provided tabulated data and curves for various lengths of both needle and sphere type spark gaps. As one of the accompanying diagrams shows, it is a simple matter to calculate the voltage when a certain length of gap is used. The engineer first checks the length of the gap on the chart; he then follows a line horizontally from the gap length, to where it intersects with the angular line on the chart; and from the point of intersection he looks in a visual line downward to a place where the voltage is given. For needle spark gap measurements, the characteristic curve on the chart is practically a straight line, while for sphere gaps the characteristic curve on the voltage versus gap length, is a curved line. Those interested in high voltage measurements by means of the spark gap method can find the voltage-gap tables and charts in the *Standardization Rules* of the American Institute of Electrical Engineers. According to Mr. Peek's researches, the voltage per foot of atmospheric electrical discharges is about 100,000, while in laboratory measurements with A.C., transformer high potential discharges, the average voltage per foot of spark was found to be about 150,000 volts. The voltage of a lightning flash may

(*Continued on page* 156)



↑ Actual photo above shows 13 ft., heavy spark obtained from the collecting net in the Alps by the German scientists. The voltage is about 2,000,000. The spark occurred once per second for 30 minutes.



Photo, left, shows the adjustable spark gap used in the Alps. Notice the heavy electrode on the end of the adjustable arm to which the spark jumps. ←

Actual photograph of the experimental "kite" used by the German experimenters in the Alps Mountains, for the purpose of accumulating high potential electrical discharges from the atmosphere. Note the size of the insulators.





Below we see 3,000,000-volt artificial lightning stroke produced in G. E. Laboratory at Pittsfield, Mass. Note man. ↓


WOODEN SHEATHING
REINFORCED CONCRETE
GLASS
BITUMEN
CONCRETE
COLLECTOR WIRE
GUIDE ROPE
INSULATOR
BALLOON WITH COLLECTORS
BRUSHES
SLIP RINGS
WINDLASS
STATOR
TRANSFORMER
SAFETY CAP
WORKING SPARK GAP
CONDENSERS

© 1922 BY SCIENCE AND INVENTION


NATIONAL INSTRUMENTS
NATIONAL INSTRUMENTS
DELL
8:25 / 9:25
CC
HD

Flat Earth CON SPIRES! Cathedral Spires Are Secretly Atmospheric Electricity Ma


NOT FOR BROADCAST
NOT FOR BROADCAST
1:02 / 10:38
STORMHIGHWAY.COM
HD

1:45 / 9:25
HD


SUBSCRIBE
0:32 / 2:24
HD

Charging from the power lines.


АНТЕННА
СВЕЧА
ТР
ЗАЗЕМЛЕНИЕ

E6


MULTI DISPLAY DMM
10.1
POWER
COM
DT-920

SPARK PLUG
DIODE
CAR CHARGER
FLYBACK TRANSFORMER
TV ANTENNA
00.0
POWER
COM
DT-92



must depend on the area occupied by the building; for instance, a church of ordinary design and size would require four "down" rods, that is, one from the spire, one on both sides of the nave, and one at the extreme end. It is advantageous to run two conductors from the top of the spire or tower, one on each side.

FIG. 7.—3 FT. ELEVATION ROD, WITH POINTS BRAZED TOGETHER, USED WHERE EXPOSED TO MUCH HEAT.

FIG. 8.—ELEVATION ROD FOR HORIZONTAL POSITION OR FLAT ROOF.

FIG. 9.—PLAIN POINT ELEVATION ROD.

Horizontal Conductors (see L.R.C. Suggestion 2, page 15). To complete the system, all the down conductors should be intersected by at least one horizontal rod, with the object of having a path for any side flash or portion of the main stroke which may not be carried away harmlessly by the main rod. Where there is a considerable length of roof, aigrettes (Fig. 11) should be fixed as shown by Fig. 10, which is taken from a model of the roof of Westminster Abbey. The down conductros on their way to earth should be connected to any metal work in the neighbourhood, also to rain-water gutters, pipes, etc.; the number of these subsidiary down conductors depends on the length of the roof.

At a conference held on behalf of the L.R.C., in April, 1904, Sir Oliver Lodge suggested that these down conductors should, in the case of a church, be run between each of the windows.

FIG. 10.

Method of running Conductors. These, whether vertical or horizontal, should be kept away from the structure (L.R.C. Rule 10) so as to avoid all sharp bends, and facilitate straining, and secondly, to prevent the corrosion which may take place where the metal is in contact with the brick or stone work. It is found advisable

Modern lightning conductors: an illustrated

surface of the joint need not necessarily exceed that of the cross section of the conductors. The joint should be put together previously by screws or rivets, and the soldered joint, especially if used in underground work, should be carefully protected from local electrical action by tarred rope. Stranded iron conductors can be connected (as previously described) by use of a box joint; the box, Fig. 28, must be of the same metal as the conductors.



FIG. 27.—TERMINALS IN FORM OF AN ARCH FOR CHIMNEY STACK.



FIG. 28.

Vanes.—Particular attention must be paid to the necessity of making a permanent joint to the spindle. A clamp is prepared of the same material as the spindle, and is furnished with two bolts to tighten; if iron is used it is well to line the clamp with a piece of sheet lead. The conductor is sweated into a socket which is fitted with an eye, through which one of the tightening bolts passes. In the case of the vanes of churches and those fixed in inaccessible positions, two separate clamps should be used.

Internal Masses of Metal.—Roof trusses fitted with longitudinal iron tie rods will, as a rule, be found to be electrically connected, but should this not be the case each truss must be joined to the conductors. All large and long masses of metal, such as beams, girders, roof trusses, tie rods, hot water systems, traveller ways, hoisting crabs, engines, boilers, large machines, and ventilators fixed in the interiors of buildings, should be connected to all conductors that pass near them, and as far as possible with one another. The discontinuous parts of traveller rails should be connected by straps, or in some cases tramway bonds might be used. If electric light wires are run in tubes, such as the "SIMPLEX," this should be earthed. Metallic contact between lead or zinc sheeting and flashings should be carefully studied, and for special work strips of sufficient size should be either burnt on to lead or soldered in such a way that the joint will stand rough usage, and allow for expansion or contraction.

Earth Connection.—"*It is essential that the lower extremity of the conductor be buried in permanently damp soil; hence proximity to rain-water pipes, and to drains, is desirable. It is a very good plan to make the conductor bifurcate close below the surface of the ground, and adopt two of the following methods for securing the escape of the lightning into the earth. A strip of copper tape may be led from the bottom of the rod to the nearest gas or water* main—*not merely to a lead pipe—and be soldered to it; or a tape may be soldered to a sheet of copper* 3 *feet by* 3 *feet and* $\frac{1}{16}$ *inch thick, buried in permanently wet earth, and surrounded by cinders or coke; or many yards of the tape may be laid in a trench filled with coke, taking care that the surfaces of copper are, as in the previous cases, not less than* 18 *square feet. Where iron is used for the rod, a galvanised iron plate of similar dimensions should be employed.*

"The use of cinders or coke appears to be questionable owing to the chemical or electrolytic effect on copper or iron. Charcoal or pulverised carbon (such as ends of arc-light rods) is better. **A tubular earth** consisting of a perforated steel spike driven tightly into moist ground and lengthened up to the surface, the conductor reaching to the bottom and being packed with granulated charcoal, gives as much **effective area** as a plate of larger surface, and can easily be kept moist by connecting it to the nearest rain-water pipe. The resistance of a tubular earth on this plan should be very low and practically constant."—*Lightning Research Committee, 1905.*



Washington Monument is an Atmospheric Electricity Mast


Fig. III.
B
C
C
H
F
P
P
F
F
C
Fig IV.
B
g
g
C
H
F
P
g
F
Fig. I
A
F
F
F
I
f
f
A
F
f
f
A
f
f
f
f
A
A
C
Fig. II.
E
E
B

Figure 2.3. The lightning rod that Toaldo designed for the church of San Marco in Venice. GiuseppeToaldo, "Del conduttore elettrico posto nel campanile" (Padua, 1776). Franklin Collec-



Gilded Temples Are Secretly Atmospheric Electricity Masts

How To Find S-W Stations Quickly



~ EUROPEAN STATIONS ~

GOOD AT NIGHT
GSB - ENGLAND (9.51)
DJA - GERMANY (9.56)
GSC - ENGLAND (9.58)
2RO - ITALY (9.63)
EAQ - SPAIN (9.87)
— - FRANCE (11.71)
PHI - HOLLAND (11.73)
GSD - ENGLAND (11.75)
DJD - GERMANY (11.77)
I2RO - ITALY (11.81)
GSE - ENGLAND (11.86)
— - FRANCE (11.89)
GOOD LATE AFTERNOON
RV59 - RUSSIA (6.00)
DJC - GERMANY (6.02)
GSA - ENGLAND (6.05)
2RO - ITALY (6.08)
GOOD AT NIGHT
HVJ - VATICAN (15.12)
GSF - ENGLAND (15.14)
DJB - GERMANY (15.20)
— - FRANCE (15.24)
GOOD DAYTIME
31 M.
49 M.
25 M.
19 M.
5.5
6
6.5
7
7.5
8
8.5
9
9.5
10
11
12
13
14
15
MEGACYCLES
RECEPTION CONDITIONS DESIGNATED ARE BASED ON LOCATION OF LISTENER IN E.S.T. ZONE. MAKE ALLOWANCE FOR OTHER TIME ZONES.



~ CANADIAN SHORT-WAVE STATIONS ~

VE9DN - MONTREAL, QUE. (6.00) "CFCF"
VE9CS - VANCOUVER, B.C. (6.07) "CKFC"
VE9BJ - ST. JOHN, N.B. (6.09) "CFBO"
VE9GW - BOWMANVILLE, ONT. (6.10) "CRCT"
VE9HX - HALIFAX, N.S. (6.11) "CHNS"
CJRO - WINNIPEG, MAN. (6.15) "CJRC"
CJRX - WINNIPEG, MANITOBA (11.72) "CJRC"
31 M.
49 M
25 M.
19 M.
5.5
6
6.5
7
7.5
8
8.5
9
9.5
10
11
12
13
14
15
MEGACYCLES



~ UNITED STATES SHORT-WAVE STATIONS ~

W8XAL - MASON, OHIO (6.06) "WLW"
W3XAU - NEWTON SQUARE, PA. (6.06) "WCAU"
W9XAA - CHICAGO, ILL. (6.08) "WCFL"
W9XF - DOWNERS GROVE, ILL. (6.10) "WENR"
W3XAL - BOUND BROOK, N.J. (6.10) "WJZ"
W2XE - WAYNE, N.J. (6.12) "WABC"
W8XK - SAXONBURG, PA. (6.14) "KDKA"
W3XL - BOUND BROOK, N.J. (6.42) "WJZ"
W2XAF - SCHENECTADY, N.Y. (9.53) "WGY"
W1XK - SPRINGFIELD, MASS. (9.57) "WBZ"
W3XAU - NEWTON SQUARE, PA. (9.59) "WCAU"
W1XAL - BOSTON, MASS. (11.79) "WEEI"
W2XE - WAYNE, N.J. (11.83) "WABC"
W8XK - SAXONBURG, PA. (11.87) "KDKA"
W8XK - SAXONBURG, PA. (15.21) "KDKA"
W1XAL - BOSTON, MASS. (15.25) "WEEI"
W2XE - WAYNE, N.J. (15.27) "WABC"
W2XAD - SCHENECTADY, N.Y. (15.33) "WGY"
31 M.
49 M.
25 M.
19 M.
5.5
6
6.5
7
7.5
8
8.5
9
9.5
10
11
12
13
14
15
MEGACYCLES

When To Tune and Where

● Until you have had considerable experience in short wave tuning, it is well to confine your efforts to the four bands indicated on the dial. These may look small, compared to the total length of the dial, but they contain the best "plums" among the foreign stations and many faint ones which, at first, you will probably pass unnoticed until you learn to tune slowly and carefully, intent upon identifying each slight "swish", which may be a station.



U.S. STATIONS BROADCASTING PROGRAMS ON-SHORT-WAVE CHANNELS

WEEI (590) - W1XAL (6.04) "49 M" / W1XAL (11.79) "25 M" / W1XAL (15.25) "19 M"
WLW (700) - W8XAL (6.06) "49 M"
WJZ (760) - W3XAL (6.10) "49 M" / W3XL (6.42) 46.69 M"
WGY (790) - W2XAF (9.53) "31 M" / W2XAD (15.33) "19 M"
WABC (860) - W2XE (6.12) "49 M" / W2XE (11.83) "25 M" / W2XE (15.27) "19 M"
WENR (870) - W9XF (6.10) "49 M"
WCFL (970) - W9XAA (6.08) "49 M"
KDKA (980) - W8XK (6.14) "49 M" / W8XK (11.87) "25 M" / W8XK (15.21) "19 M"
WBZ (990) - W1XAZ (9.57) "31 M"
WCAU (1170) - W3XAU (6.06) "49 M" / W3XAU (9.59) "31 M"
60
65
70
75
80
85
90
95
100
105
110
115
120
130
140
150

Copyright 1935 by H. Gernsback.


From M.J. Rycroft et al., JASTP, 2000

ELECTRIC CURRENTS
magnetosphere
thermosphere
60 - 80
+250 kV
IONOSPHERE
mesophere
ALTITUDE, km
E
FAIR
WEATHER
ATMOSPHERIC
ELECTRICITY
σ
stratosphere
J
+100 MV
-100 MV
free troposphere
130 Vm⁻¹
boundary layer
10
5
0
0 MV
mountain,
EARTH'S SURFACE


From R.G. Harrison, Surveys in Geophysics, 2004

(a)
Collector
$V_0(z)$
E
V
voltmeter
Earth's surface
(b)
outer electrode
σ
central electrode
Bias
pA
GERDIEN TUBE
electrometer
cover plate
(c)
air-Earth current J_z
collecting plate
(surface)
guard ring
battery
J
compensator
electrometer


Blyant med ledning tilsluttet grafitten
+
-
Stel hornindføring
0:01 / 2:14

tesla radiant collector/ion collector with pencil



Keeping the two wires together, make a few more turns through the center.



Keep winding until you fit as many turns as will fit in a single layer around the toroid, typically 7-10 turns with thin insulated wire.



Clip the wire leads down. Note that we have two pairs of wires: one coming out the front, and one coming out the back.



Strip the wire ends. Take one wire from each pair *of different color* and attach them together.


resistor
battery
1.5 volts
+
-
battery
voltage
Base
transistor
Emitter
Collector
ferrite toroid core
wrapped with
two coils of wire
LED - needs 1.85 volts
(Light Emitting Diode)


... A LAMP LED ... EASY TO DO witch Circuit JOULE THIEF
Alternative without Ferrite toroid
Parallel coils together ...
To replace the Ferrite toroid
COLLECTOR (2)
BASE (1)
EMITTER (3)
TRANSISTOR 3055
LAMP LED
+
-
+
Positive Battery
-Negative Battery
1 volt Battery
Switch
Livreinatural.ning.com
... EKOSMUNIDAD ..


Thicker Coil magnet wire with 44 laps (Coil turns)
wire coil # 20
Coil with thinner magnet wire 33 laps (Coil Turns)
wire coil # 22
BASE (1)
COLLECTOR (2)
EMITTER (3)
TRANSISTOR 2N3055
LAMP LED
+
+
+
+
Led
+
-
The longest leg of the LED is POSITIVE
the smaller leg of the LED is NEGATIVE
Switch
+
-
1 volt Battery

* the junction of te two coils... in the middle... Should be keeping the same direction of winding for the two

* you can use... any power transistor that is... also can be Recycled... and can use any 1 volt Battery.

Livinginatural.ning.com
...EKOSMUNIDAD...


...OOO... O ...OOO...


Lamp LED
+
+
+
Led
+
-
The longest

...Livreinatural.ning.com...
... EkosOphia ...O...

...Livreinatural.ning.com...

... TRANSISTORES ...
3055


Vista frontal
TIP 3055
1
2
3
Vista trasera
2N3055
3 EMISOR
1 BASE
2 COLECTOR

1 → BASE
2 → COLECTOR
3 → EMISOR

... Livreinatural ...
... EKOSMUNIDAD ...


TRANSISTORE
3055
Vista trasera
2N3055
3 EMISOR
1 BASE
2 COLECTOR
Vista frontal
TIP 3055
1
2
3
...Liviainatural...
...EKOSMUNIDAD...
1 → BASE
2 → COLECTOR
3 → EMISOR
BASE 1
COLECTOR 2
EMISOR 3
BASE 1
COLECTOR 2
EMITTER 3



...Livreinatural.ning.com...


EMISOR
3
COLECTOR
2
BASE
1


Thicker coil magnet
wire with 44 laps (turns coil)
Coil with thinness
magnet wire
33 laps (33 turns coil)
Start coil
End the coil
Start coil
End of the coil
44 Laps
(turns coil)
33 Laps (turns coil)
Livrei
. . .


or example
e can use
wire coil # 20
(44 turns laps)
coil
for
we can use
Wire Coil # 22
(33 turns laps)
coil)
Coil with
thinness
magnet wir
thicker coil magnet
.com · kkosm



This provision replaces the use of the ferrite toroid in the Joule Thief

thicker coil Magnet wire with 44 laps (coil turns)
for example
we can use
wire coil # 20

Coil with thinness magnet wire
33 laps (coil turns)
for example
we can use
wire coil # 22

The junction of the two coils... in the middle should be keeping the same direction of winding for the two

for Example

Unite these two coils...

... Keeping the same rotation direction of each coil...

... So in total the union of the two coils have the same rotational.

... Position a coil above the other so they are parallel


Parallel coils together...
To replace the Ferrite toroid
LAMP LED
+
-
COLLECTOR (2)
BASE (1)
TRANSISTOR 3055
EMITTER (3)
-Negative Battery
+
Positive Battery
1 volt Battery
Switch
Livreinatural.nin

LAMP LED
+
②
①
COLLECTOR ②
BASE ①
−
+
EMITTER ③
NEGATIVE −
Swicth interruptor
+
Positive Battery
−
Negative Battery
Battery 1 Volt
OSMUNIDAD . . .


accessories that make the ma
outdoors s


D
X
L
R
S
Circles here touch
Circles here touch








AD7GR - Joule-Thief
January 2009
Panasonic
DIGITAL POWER


+
INductor
2k
Q1
E
b
C
–
–
+
Q1 = 2N3904
KB



... and these are the components you need:


Two wires
Different colours
A 'dead' battery
A npn transistor
This one is a BC337-40 - but any kind will do
A light emitting diode (LED)
Any colour, but not flashing
A ferrite core
A 1kΩ Resistor

Solder the 1kΩ Resistor to either of the unsoldered wires coming from the inductor.

Solder the other end of the resistor to the base lead of the transistor.

On the transistor used here, that is the middle lead.

Cut off the spare ends of leads.


Plastic Body
TO-92
1. Emitter
2. Base
3. Collector
1
2
3

Solder the anode of the LED (the longer leg) to the collector lead of the transistor AND the remaining wire from the inductor.

Cut off the ends of the leads.


LED
Negative Side (Cathode)
Flat Edge
Short Wire
Postive Side (Anode)
Long Wire

Solder the other leg of the LED (the cathode) to the emitter lead of the transistor.
Do NOT cut off the LED leg.
(Don't worry if you have cut it off - you'll just need to solder another wire to this leg so that you can connect it to the battery.)



That's the circuit finished. Now use it.

First you need a 'dead' battery - that means one where the voltage is less than 1.3V.
You can see that the battery used here has a Voltage of just over 1V.


Rapid
1.037 V
M320
AUTO-RANGE
POWER

Connect the two soldered wires coming from the inductor to the positive (+) side of the battery.
Connect the uncut LED leg (the athode) to the negative (-) side of the battery.


DURACELL POWERCHECK
PRESS DOTS TO TEST


2700 pf
1k
B
C
2N2222
E
LED
SIZE AA LR6(T) 1.5V

Copyright 2005 Dick Cappels www.projects.cappels.org


AA 1.5V



The chip is soldered onto the legs of the LED and then the wire between pins 1 and 2 is cut out so there is no connection. The inductor is then soldered so as to bridge pins 1 and 2. I soldered the inductor on before cutting out the wire but it might be easier to try some other method.

As I said previously, this is a tedious solder job, and the SOT23 IC is easily damaged (ask me how I know!) It takes patience and a steady hand to assemble these few parts.

This circuit would work for the LED indicator in the 1.5v boosters and would most likely be a better choice than the Joule Thief that I posted previously.


Amplified power output :)
-
+
2n3904
Transistor
1k Resistor
-
Power
+
Toroid bead
On/Off


Power source
Transistor
LED
Resistor
Toroid

The CIRCUIT

The circuit is very simple. All the work is done by the 5252F chip.
It contains an oscillator, a high speed diode and a power transistor. All these components inside the "IC" that looks like a 4-leaded transistor!
This IC is smaller and cheaper than all the parts individually and is less expensive than the competition (that costs 70 cents).
We can produce a complete project for a few dollars and it has two "test features."
You can place a LED across one of the LEDs on the board and find out the colour as many LEDs come in a "clear-as-glass" package and you cannot tell the colour until they are illuminated.
The other feature is INDUCTOR TESTING.
The current taken by the circuit changes according to the value of the inductor.
You just need a few reference values and you can work out the value of an inductor within the range of the inductors you have used as samples, or slightly higher or lower values.



The layout using component pictures.

Using a 220uH, the circuit takes 13mA and illuminates 2 white LEDs very brightly.
Using 100uH the circuit takes 30mA and the LEDs are really the same brightness.
Using 33uH the circuit takes 80mA and the LEDs are just about the same brightness.
Obviously the 220uH creates the most efficient circuit.
The QX5252F is capable of delivering more than 100mA to the LEDs but we only need


Resistor
E
F
B
Transistor
D Collector
C Base
Emitter
Battery
0.6 -1.6V
A
G
LED
Switch
B
F
E
A
D
C
G



Watson's 2 Transistor "Joule Thief" V. Booster

Uses 2N3904 for output. Coil is 180 microhenry,
2.5 ohm RF choke (green blob)


C1 1nF or
1000pF "102"
102
OQK
R2
470
180 uH, 2.5 ohm
RF choke
09/02
TEAPO
2N
3906
E B C
R1
33k
White LED

I added
100uF
bypass
capacitor

1 ohm
current
sense
resistors

www.rustybolt.info
Jan 29, 2012

Watson's Version of "1.5v Joule Thief -Blinks Led"

Taken from http://www.youtube.com/watch?v=GVP2QGpk5KE Nov 14, 2012



My version does boost the voltage and light the LED, but it doesn't blink.

This wiring Diagram is Watson's Corrected Version at http://rustybolt.info/wordpress/?p=4934

1.5V AA cell below

1Meg
1uF
B
C
E
PN2222A
B
E
C
BC5
57C
LED
flat
spot
Two 180 uH in
parallel =90 uH

Watson's Joule Thief Pictorial Diagram

http://rustybolt.info/wordpress/?p=128 2011 Dec 07


Coil
Core =
Fair-Rite
2673002402
12 Turns
24 AWG
Bifilar
Wound
1.5 Volt AA Cell
1k 1000 ohms
brown, black, red, gold
Emitter
Battery -
Flat spot
Coll-
ector
Transistor,
NPN General
Purpose,
PN2222A,
2N4401
LED
Blue or
White
Battery +

Joule Thief

Pictorial Wiring Diagram Dec 11, 2009


FERRITE
TOROID
LED
1k
BC337
C
B
E
Flat spot
+
1.5V
−
AA or AAA cell
C
B
E
for 2N4401

www.rustybolt.info

Watson's True 2N2222 Joule Thief

Oct 31, 2010 Boo!

Not very good performance from an expensive transistor



Resistor is 820 ohms, with a "102" 1000 pF speedup capacitor in parallel.

Uses a real 2N2222 in the TO-18 metal can package, at 5 to 10 times the price of the plastic package.



Watson's Tiny Toroid Conventional Joule Thief - Nov 18, 2009

Not much bigger than the transistor!

www.rustybolt.info


Blue or
White LED
1K
Res
BC337-25
Optional
2.2 ohm current
monitoring resistor
PILE ALCALINE FORMAT AA
1.5V SIZE AA
ALKALINE BATTERY
KIRKLAND
Signature

Three windings 30 AWG, each about 6 inches long, trifilar wound on 0.229 inch O.D. toroid, 2 in parallel for main winding.


Watson's Solderless Joule Thief
Oct 25 2010
White or blue LED
2N4401 NPN transistor
1000 ohm resistor
1.5V
AAA
Cell
Coil consists of two 10 foot lengths of insulated telephone wire wound around a AA cell and tied with wire ties

I took this photo just before Halloween back in 2010, after I made this Joule Thief without solder and without a toroid. It shows that you don't have to know how to solder and you don't have to have a toroid to make a working Joule Thief – all you need is a screwdriver. So do your thing and experiment a bit, and see what you can come up with.

Each screw (except for one) has two washers to hold the wires. Putting two or more wires under the screw head without the washers will be difficult and the wires will try to come loose. Two or three washers makes it easier and the wires are held much firmer. The wood block is a piece of solid oak that is about a half inch (12mm) thick. The oak is very hard and the screw holes have to be drilled out before the screws are put in. This also makes it possible to use small screws with a flat end which were used for holding plastic parts together. The screw size is about #3 by 3/8 inch long, with coarse threads like a sheet metal screw.

The LED is not very bright because it's a cheap 3 mm white LED I got from an eBay seller, and it has been used a bit so it has dimmed. Use a decent LED and this circuit will be as bright as a toroid JT.

Watson's Solderless Joule Thief

Another Joule Thief I put together is shown in the second photo. This uses the bare wires to wrap around the joints in place of solder. The joints are not as mechanically strong as solder but for a quick experiment they should work okay. If the JT is going to be used, the wire joints may become intermittent or loose. The solder joints are a much better connection.



Watson's Solderless Joule Thief Oct 25 2010

White or blue LED
2N4401 NPN transistor
1000 ohm resistor

Coil consists of two 10 foot lengths of insulated telephone wire wound around a AA cell and tied with wire ties.

1.5V
AAA
Cell
1.5 VOLTS
SIZE AAA BATTERY

Watson's 'Toroid Free' Air Core Joule Thief


2.2k Red, Red, Red, Gold

rustybolt.info/wordpress/?p=2872 May 21, 2012

Watson's Nearly Disposable Joule Thief Light

rustybolt.info/wordpress/?p=2133   Fri. Apr 13 2012

Completed circuit ready for coating of silicone sealant.
Transistor is a BC337. If it was a PN2222A or 2N4401,
the flat side would be facing up.







Watson's Solderless Joule Thief

http://rustybolt.info/wordpress/?p=5210


AA 1.5V
SANYO Energy (U.S.A.) Corporation
SANYO


AA FORMAT · E91
LR6 · AM3 · 1.5V


LED
Terminals
Flat
+
Anode
−
Cathode
−
+
2N3904 NPN Transistor
Terminals
2N39
04
E B C
E =Emitter
B=Base
C=Collector
B
C
E


2N3904 NPN Transistor
Terminals
2N39
04
E B C
E = Emitter
B = Base
C = Collector



Transistor Terminals



2N3904
(NPN Transistor)

LED Terminals


Negative Side (Cathode)
Flat Edge
Short Wire
Postive Side (Anode)
Long Wire


Round Ferrite Toroid
NPN Transistor (2N3904)
1K Resistor (BRN-BLK-RED)
LED (White)
Weak/Used Battery
Battery Tester
+AA
03-2016
Energizer
REPLACE WEAK GOOD
Ulta-Lit
Soldering Lead
Coated Copper Wire


Ferrite toroid core
with two lengths of
small diameter wire
e.g. 26 gauge,
30 gauge, ...
resistor
1kΩ
AA battery
flat side is facing
out of the page
transistor
2N4401
C
B
E
one leg is longer
than the other
LED (Light Emitting Diode)
(C - Collector, B - Base, E - Emitter)


LED
I
+
2n3904
Transistor
1k Resistor
–
Power
+
Toroid bead
On/Off


Energizer
+|AA
2010
PILE ALCALINE
WARNING: Do not install


−
+
0:51 / 4:23
CC


3:25 / 4:23
CC


0:09 / 4:23


Round Ferrite Toroid
NPN Transistor (2N3904)
1K Resistor (BRN-BLK-RED)
LED (White)
Weak/Used Battery
Battery Tester
+AA
03-2016
Energizer
REPLACE WEAK GOOD
Ulta-Lit
Soldering Lead
Coated Copper Wire




2N
3904
5
10
15


ALKALINE
Thunderbolt
AAA


AA 1.5V



3* Axial lead inductor 82uH 1/4W
1* 10nf ceramic capacitor 103
2* AO90 Germanium signal diode
1* 2N2222 NPN Transistor bipolar 0.6A 40V
1* RESISTOR 5.6K Ohm 1/4W
3* 5mm white Emitting led Diode 20 mA 3.2 V





Make Super Efficient Joule Thief DIY-Circuit!

3* Axial lead inductor 82uH 1/4W

1* 10nf ceramic capacitor 103

2* AO90 Germanium signal diode

22 NPN Transistor bipolar 0.6A 40V

1* RESISTOR 5.6K Ohm 1/4W

3* 5mm white Emitting led Diode 20 mA 3.2 V

103
+
-
MORE VIDEOS
2:25 / 3:06
YouTube
ΕΛΕΜΑΝ


Ferrite toroid core
with two lengths of
small diameter wire
e.g. 26 gauge,
30 gauge, ...
resistor
1kΩ
+
AA battery
flat side is facing
out of the page
transistor
2N4401
C
B
E
one leg is longer
than the other
LED (Light Emitting Diode)
(C - Collector, B - Base, E - Emitter)


AA 1.5V
SANYO Energy (U.S.A.) Corporation
SANYO

A conventional joule thief, shows components and how they are connected. This example uses a red LED. A ferrite toroid is wound to form a coil with primary (white) and feedback (green) windings. A 2N2222A transistor and 1000 ohm resistor are used.

The Joule Thief


1.5v AA or AAA battery
1k resistor
C
B
E
T
+
3v LED
-

Transistor shown (T) is 2N3904 (can also use 2N2222).

Note LED pins - negative is shorter and has flat on bulb edge.

2 wires round ferrite ring are wound together, then start of one joined to end of other.

Try adding more and more LEDs...

Joule Thief


Résistance
500- 2000 Ohms
AA
DURACELL
ALKALINE BATTERY
NPN
B C E

Its a Rubbish Challenge
Dog Light

Joule Thief
electronics circuit


+
1.5v
−
1kΩ
BC547
−
c
b
e
+


resistor
battery
1.5 volts
Base
transistor
Emitter
Collector
LED - needs 1.85 volts
(Light Emitting Diode)
ferrite toroid core
wrapped with
two coils of wire



- 3* Axial lead inductor 82uH 1/4W
- 1* 10nf ceramic capacitor 103
- 2* AO90 Germanium signal diode
- 1* 2N2222 NPN Transistor bipolar 0.6A 40V
- 1* RESISTOR 5.6K Ohm 1/4W
- 3* 5mm white Emitting led Diode 20 mA 3.2 V



AA 1.5V
SANYO Energy (U.S.A.) Corporation
SANYO

The joule thief circuit.


Ferrite toroid core
with two lengths of
small diameter wire
e.g. 26 gauge,
30 gauge, ...
resistor
1kΩ
AA battery
flat side is facing
out of the page
transistor
2N4401
C
B
E
one leg is longer
than the other
LED (Light Emitting Diode)
(C - Collector, B - Base, E - Emitter)

Transistor - The legs of the transistor can be determined by noticing that there's a flat side to the transistor case. See the diagram above. A large number of transistors have been reported to work: 2N4401, NET123AP, BC547B, 2SC2500, BC337, PN2222, to name just a few.

LED - One leg of the LED is longer than the other leg. Use this to determine which one goes where. See the diagram above.

Resistor - The diagram says use a 1 kilo ohm resistor but I've used an 820 ohm one just fine. I've also seen a 2 kilo ohm one in use. Use whatever works for you. You can also use a potentiometer (a variable resistor) so that you can easily adjust it to select the resistance that gives the best light.

Toroid ferrite core - Some people have gotten these by opening up compact fluorescent lightbulbs (CFLs). I took mine out of some device whose original function I don't know. To get it working, my first one had just 13 turns for each wire and I used a 30 gauge wire and a 26 gauge wire. The wire must be insulated. A variety of number of turns will work. This is something you can play with. Look at the diagram carefully to determine where the wires connect to.



Superglue four pads to the PC board. Make sure they are not touching each other. You should have roughly 1/8 inch between the pads. Apply a small drop of superglue on the board and press the pad onto the board with the small dimple up. Use a small screwdriver to hold pressure on the pad until the glue dries (about 10 seconds).



Solder the 1,000 ohm resistor onto pads 1 and 3. When soldering all components, place a 90-degree bend on the ends of the component where they touch the pad to allow better soldering. There is no polarity on a resistor.



Solder the LED to the board. **VERY IMPORTANT**: Solder the **long lead** to pad 2 and the **short lead** directly to the PC board. The LED will not illuminate of you put it in backwards. If you look into the LED, the anvil shaped part is the lead that gets soldered to the PC board.


Emitter –
PC Board
Collector –
Pad 2
Base –
Pad 1

Solder the transistor to the board. With the flat part facing you the left lead (emitter) is soldered directly to the PC board. The center lead (base) is soldered to pad 1. The right lead (collector) is soldered to pad 2. Failure to install this part correctly will prevent the Joule Thief from working.



Take the two pieces of wire and **untwist** them if they are twisted. The toroid requires 12 inches of wire. You will wind the toroid with this pair of wires side by side.



Wind the toroid with **9 turns** of the wire. Each turn through the hole in the center counts as one turn. **VERY IMPORTANT:** You must take one wire **from each side of the winding** and twist them together. This makes the transformer windings out of phase. This is critical to operation. Connect one wire of each color.


Twisted
Wires
Pad 4
Pad 2

Solder the twisted wires on the toroid to pad 4. Solder one of the other toroid wires (doesn't matter which one) to pad 2.



Solder the other wire on the toroid to pad 3.



Solder the battery holder. Connect a short piece of wire from the positive terminal (the one without the spring) to pad 4. Solder the negative terminal (the one with the spring) directly to the PC board using a short piece of wire. Use hot glue or some other glue to secure the battery holder to the PC

Step 1 – Wound the Toroid







Take the two strands of plastic insulated wire and hold them together. Start off by sticking then through the middle of the toroid until you have 2 cm of wire left to make a connection with later. Keep the two wires together and wrap them around the toroid until you have covered the whole toroid. If you have wire left you can continue until you have about 2 cm of wire free on either side. Remove about a 0.5 cm of the plastic insulation on all four of the wires as in the photo. You have now wound your toroid and we are ready to continue.

Step 2 – Join the two coils of Toroid



The next step is to join the two coils or windings of the toroid. You may have noticed the two dots next to the toroid windings in the circuit diagram. These two dots indicate the polarity of the transformer and as you can see the two windings are opposite to each other. To make sure that the polarity of our toroid windings are correct we must do the following:

- If we look at the toroid we noticed that we have two wires of different colours sticking out at both ends of the toroid.
- Take one wire of a specific colour (green in the example) on the one side of the toroid and one wire of the other colour (white in the example) on the other side of the toroid and connect (or solder) them together. These two wires forms the top pole of the toroid as in the circuit diagram and is connected to the positive terminal of the battery.



A conventional joule thief, shows components and how they are connected. This example uses a red LED. A ferrite toroid is wound to form a coil with primary (white) and feedback (green) windings. A 2N2222A transistor and 1000 ohm resistor are used.



A joule thief with two axial inductors replacing the ferrite toroid, shown on a solderless breadboard


2N
3904
5
10


Round Ferrite Toroid
NPN Transistor (2N3904)
1K Resistor (BRN-BLK-RED)
LED (White)
Weak/Used Battery
Battery Tester
Soldering Lead
Coated Copper Wire
+AA
03-2016
Energizer
REPLACE WEAK GOOD
Ulta-Lit

Step 2: Schematic Diagrams


gle Battery Cell:
ɛaline, NiCD, NiMH
3 - 1.5 V typ.)
Hand-wound
ferrite toroid
1 k
2N3904
LED:
Blue
Whit


LED
I
+
2n3904
Transistor
1k Resistor
Toroid bead
I
Power
+
On/Off


Transistor Terminals
E B C
2N3904
(NPN Transistor)
LED Terminals
Negative Side (Cathode)
Flat Edge
Short Wire
Postive Side (Anode)
Long Wire


2N3904 NPN Transistor Terminals
2N39
04
E B C
E = Emitter
B = Base
C = Collector


LED Terminals
Flat
+ Anode
– Cathode
–
+
2N3904 NPN Transistor Terminals
2N39 04
E B C
E = Emitter
B = Base
C = Collector
B
C
E

These tiny T231212T toroids from Surplussales.com are high permeability so it doesn't take much wire to make a good Joule Thief coil. The core is less than a quarter inch diameter (here is a data sheet in .PDF.). Six inches of 30 AWG magnet wire trifilar wound, with two of the windings connected in parallel for the primary winding.


Watson's Tiny Toroid Conventional Joule Thief -
Nov 18, 2009
Not much bigger than the transistor!
www.rustybolt.info
Blue or White LED
1K Res
BC337-25
Optional 2.2 ohm current monitoring resistor
Three windings 30 AWG, each about 6 inches long, trifilar wound on 0.229 inch O.D. toroid, 2 in parallel for main winding.

The transistor is a BC337-25. I put a 2.2 ohm resistor in series with the circuit to measure the battery current. It can be put there temporarily and removed when the LED current is what you want. How do you change the LED current? Change the 1k resistor to a different value. Higher values will reduce the LED current. With the BC337-25 and 1k resistor, the LED current should be close to 20 milliamps so it's probably not wise to go much below 1k. If you use another transistor, especially the pipsqueak 2N3904, you may have a hard time getting it to put out 20 milliamps.


DC POWER SUPPLY PS-305D
A
CURRENT
VOLTAGE
VOLTAGE
C.V.
FINE
COARSE
GND
+
OFF
HI
LO
F1
F2
F3
F4
RANGE
TIME
TRIG
AUTO
MODE
SET
SAVE/CALL
µA
mA
Hz
Ω
V
221102A-17
O P Q R S T U V W X Y Z A


B
103M
2N
2222
A 231



3* Axial lead inductor 82uH 1/4W

1* 10nf ceramic capacitor 103

2* AO90 Germanium signal diode

1* 2N2222 NPN Transistor bipolar 0.6A 40V

1* RESISTOR 5.6K Ohm 1/4W

3* 5mm white Emitting led Diode 20 mA 3.2 V


2402A-17
R
S
V
Y
Z
A
01
02


D7
D9
D8
D10
D11
D12
ANT19
ANT20
ANT21
ANT23
ANT24
ANT12
C1
ANT7
ANT8
ANT9
ANT10
ANT22
ANT11
D6
D1
D5
D3
D4
D2
ANT13
ANT14
ANT15
ANT16
ANT17
ANT18


Unit : mm
○ : GND
▨ : Diode
HSMS286F
2.2
12
1.8
1.5
2.2
6.5
1.3
18.7
12
2.2
21.1
λ/4 line
Matching circuit
4.9
8.5
6.5
13.6
8.8
11.7
19.2
18.4
1.9
8.1
Class-F load
(a)
131115 12
RF
DC
(b)

Figure 4.1: Proposed positive output voltage rectifier. (a) Structure and size. (b) Photograph.


L1
W1
W2
Antenna Port
W1
W2
W1
: Shorting vias
: Zero-bias diodes
: DC load
: Ceramic capacitors

Fig. 3. Layout of the rectifier prototype, printed on RO3206. $w_1 = 72$ mil, $w_2 = 15$ mil, and $L_1 = 171$ mil. Fabricated sample is shown in top left, and the impedance matching stub is encircled.



Fig. 5. Measured $|S_{11}|$ performance and total realized gain (at boresight) of the proposed antenna. Fabricated sample is shown in bottom left.






C2
39PF
C1A
3×500PF
C1B
C1C
A1
L1
100μH
D1
0A95
TR1
TR 10.16
0.625
W
0
16Ω
8Ω
4Ω
0
16Ω
R1
47k
C3
68nF

SET 11




TR 10.16
0 4Ω 8Ω 16Ω

Preparation of the tuning capacitor





Mount the mounting supports on the tuning capacitor (they are delivered with the tuning capacitor).
Place the shaft coupler on the shaft of the tuning capacitor.


39 pF
A
F
95 mm
8 mm
B
E
38 mm
C
D


0,068µF
±10% 630V~


TR 10.16
0
4Ω
8Ω
16Ω







Screw the front on the bottom plate with four screws 3x45 mm.
Place the headphone socket.
Place the two terminal posts and the gas discharge tube.

Make a paper strip with 4 sections of 40x55 mm on it.
Do the strip around the tube, and fix it with a piece of tape.
Don't tape the strip onto the tube on places where later the coil is wound.



For the coil we need 8.6 meter enamelled copper wire with 0.8 mm thickness.
Hook the begin of the coilwire onto the slot in the tube.
Also fix the begin of the wire on the inside of the tube with some tape.





Wait until the glue is hardened.
Remove the rubber bands, the tape and the matches.
Shift the tube out of the coil, and remove the paper out of the coil.
Turn the both ends of the wire one time around the stick at the bottom side of the coil, and apply some extra glue here.



Apply some glue in the holes in the 9 mm sticks
Also apply some glue in the 9 mm holes in the bottom plate.
Place the coil as shown in this picture.
Wait until the glue is dry.



Place the tuning capacitor on the frame.
Fix it with four screws M4x16
One coilwire runs underneath the tuning capacitor, is then bend upwards and cut to length.
Solder this wire to the tuning capacitor (indicated with the arrow in the above picture).
Scrap of the lacquer from the wire, before soldering.



The other wire is cut to length, and soldered to the solder tag of the tuning capacitor (indicated with arrow).



Place the transformer on the frame, fix it with two M4x16 screws, 2 rings and 2 nuts
The wire of the 68 nF capacitor must stick through the "0" connection of the transformer, and is then soldered.
Solder the OA95 diode between tuning capacitor and the "0.625W" connection of the transformer.
The green band on the diode must point towards the transformer.


TR 10.16
0 4Ω 8Ω 16Ω

Solder the two wires from the transformer to the headphone socket (see for detail: next picture).

Solder the two wires from the tuning capacitor to the terminal posts.
The wire with the red line on it, comes on the upper (antenna) connection.
The wire without red line, comes on the lower (ground) connection.



Detail of the wires on the headphone socket.
The wire without red line comes on the ground connection.
The wire with the red line comes on the two signal pins, so these two signal pins are connected together.



Mount the extension shaft and the knob on the tuning capacitor.
In the middle position, the pointer on the knob must point upwards.




$10,000
in $100 bills
$1,000,000
in $100 bills
$100 Million
in $100 bills
$1 Billion
in $100 bills
$1 Trillion
in $100 bills

USB Type A Female Field Termination Connector



Roll over image to zoom in

L-com Item # USBAFT

List Price	$7.24
Your Price 1-9	**$7.24**
10-24	$6.81
25-99	$6.37
100 +	Call Us

Availability: In Stock

Available for Same Day Shipping

Quantity 1 ADD TO CART

Email This Page

MATHEMATICS — A LEARNING MAP



WHY STUDY MATHEMATICS?
WHAT IS MATHEMATICS?
LEARNING MATHEMATICS
HISTORY OF MATHEMATICS
Resources
= high-powered/advanced
symmetric, involving groups
= geometry
= algebra
= numbers
= patterns/order
analysis/smoothness
topology/continuity
= measure/integration
= approximation
= linearity
= optimization
COUNTING
one Wati; two Wati; many Wati TARZAN
ARITHMETIC: NUMBERS + NUMBER SYSTEMS
CONTINUED FRACTIONS
DIOPHANTINE EQUATIONS
NUMBER THEORY
ALGEBRA: SYMBOLIC REPRESENTATIONS + SYMBOLIC CALCULATION
"THEORY OF EQUATIONS"
SOLUTION OF CUBIC + QUARTIC EQUATIONS
"KRIPKE THEORY"
"CHOMSKY THEORY"
BOOLEAN ALGEBRA
SURREAL NUMBERS
LOGIC
MATHEMATICAL LINGUISTICS
"NEURAL NETS"
MATHEMATICAL NEUROLOGY
POWER SERIES
GEOMETRY: MODELING SPATIAL CONFIGURATIONS
COMPUTATIONAL GEOMETRY
SET THEORY
LISP
PROLOG
REAL NUMBERS
SETS + FUNCTIONS
COMBINATORIAL GAMES
ALGORITHMS
COMPLEXITY THEORY
THEORY OF COMPUTATION
FORMAL LANGUAGES, GRAMMARS + AUTOMATA
NATURAL LANGUAGE PROCESSING
ARTIFICIAL INTELLIGENCE
ABSTRACT ALGEBRA: THE STUDY OF ALGEBRAIC SYSTEMS
COMBINATORICS
COMBINATORIAL OPTIMIZATION
PROGRAMMING LANGUAGES
TRANSLATORS
COMPILERS
PARSING
CRYPTOGRAPHY
GROUPS
FIELDS
GRAPH THEORY
MATROIDS
LINEAR PROGRAMMING
ROBOTICS
COMPUTER VISION
SEMIGROUPS
AUTOMATIC GROUPS
GALOIS THEORY
MODULES
COMBINATORICAL ALGEBRA
MACHINE ARCHITECTURE
COMPUTERS
OPERATING SYSTEMS
DATA COMPRESSION
KOLMOGOROV COMPLEXITY
CONTROL THEORY
PATTERN RECOGNITION
THEORY OF CODES
ALGEBRAIC NUMBER THEORY
ALGEBRAIC K-THEORY
"DISCRETE CALCULUS"
SMALE SET THEORY
DESCRIPTIVE SET THEORY
STATISTICS
INFORMATION THEORY
GROUP REPRESENTATIONS
DESCRIPTIVE GEOMETRY
FRACTALS
MEASURE THEORY
PROBABILITY
"the key discovery of modern mathematics"
NON-EUCLIDEAN GEOMETRY
HYPERBOLIC
RIEMANNIAN
LIE ALGEBRAS
ALGEBRAIC GROUPS
CATEGORY THEORY
ANALYTIC GEOMETRY
"GRAPHING"
PROJECTIVE GEOMETRY
CONICS, CUBICS, QUARTICS
ALGEBRAIC CURVES
ALGEBRAIC GEOMETRY
MATRIX THEORY
COMPLEX NUMBERS
TRIGONOMETRY
POLAR COORDINATES
POLAR GRAPHING
COHOMOLOGY OF GROUPS
COMPLEX GEOMETRY
VECTOR GEOMETRY
LINEAR ALGEBRA
LIE GROUPS
HOMOLOGICAL
CALCULUS
NUMERICAL ANALYSIS
TOPOLOGICAL GROUPS
VECTOR CALCULUS
DIFFERENTIAL GEOMETRY
REAL VARIABLES
TOPOLOGY
SPECTRAL SEQUENCES
LIMITS
DIFFERENTIAL EQUATIONS
CALCULUS OF VARIATIONS
METRIC SPACES
"WITTEN THEORY"
VERGENCE
ORTHOGONAL POLYNOMIALS
CONVEX ANALYSIS
CLASSICAL MECHANICS
SYMPLECTIC MANIFOLDS
DIFFERENTIAL TOPOLOGY
ALGEBRAIC TOPOLOGY
CONTINUITY
FOURIER ANALYSIS
WAVELETS
MATHEMATICAL PHYSICS
RIEMANN SURFACES
MORSE THEORY
COBORDISM
DIFFERENTIABILITY
FUNCTIONAL ANALYSIS
GENERAL RELATIVITY
RIEMANNIAN MANIFOLDS
COMPLEX MANIFOLDS
INTEGRATION
BANACH SPACES
HILBERT SPACE
QUANTUM MECHANICS
COMPLEX VARIABLES
THE COMPLEX INTEGRAL
CAUCHY'S INTEGRAL THEOREM
RESIDUES
QUANTUM ELECTRODYNAMICS
QUANTUM FIELD THEORY
STRING THEORY
ANALYTIC NUMBER THEORY

Philmore
MANUFACTURING CO. Inc.
Richmond Hill 18, N. Y.

MODEL NO.
VC-1000


ANTENNA
GROUND
KNOB
GERMANIUM CRYSTAL DIODE
EAR PHONE

1 LED azul
(con tensión entre 3V y 3,6V)


68 ohms
USB +5V +
(rojo)
– USB GND
(negro)

WWW.INVENTABLE.EU

1 LED rojo
(con tensión entre 1,8V y 2,1V)


150 ohms
USB +5V +
(rojo)
– USB GND
(negro)

The Tesla Experiment





TRANSVERSE WAVE INTERFERENCE



ENERGY ZONES
INTERFERENCE ZONE
XMTR #1
ZERO ENERGY LINES
(0̄-LINES)
XMTR #2

LONGITUDINAL WAVE INTERFERENCE
(SCALAR WAVES)



XMTR #1
0̄-WAVES
ZERO ENERGY LINES
ENERGY BOTTLE
(interference zone)
XMTR #2
0̄-WAVES
VECTOR ENERGY ZONES

© PoweredTemplates.com


+Karl
Search
Images
Maps
Play
YouTube
News
Gmail
Drive
Calendar
More
Google
kryptonique
Karl Smirni
0
+ Share
Books
Add to my library
Write review
Page E-1
GET PRINT BOOK
No eBook available
Trafford Publishing
Amazon.com
Barnes&Noble.com
Books-A-Million
IndieBound
Find in a library
All sellers »
+1
0
0 Reviews
Write review
Go
About this book
Clear search

Result 4 of 4 in this book for **kryptonique** - ‹ Previous Next › - View all

They All Told the Truth: The Antigravity Papers
By Richard P. Crandall

kryptonique

Lost Dwgs & Tech, Ancient India, & "Four"

THE LOST HAMEL DRAWINGS:

David Hamel's "Isotope Line of Movement" creating the:
POSITIVE - NEUTRAL - NEGATIVE
mechanical parts needed to create a self running system.

(male)
Rotating Rod with a Neutral Center
(female)
1
2
3
Hamel Technology
The Eye (particle of nature)
Twice the Aether
Equals
Scale (perfect balance of nature)
The Duality (opposites)
Celestial Power
2
E
C
1st Particle of Nature (male)
2nd Particle of Nature (female)
KRYPTONIQUE
Gases of space

Particle Structure. [The MOST IMPORTANT Hamel Diagram of All.]




Addie's super foxhole radio schematic
magnet wire
120-200 winds
safety pin
jammed into
#2 pencil lead
shorter the pencil
the better
ground:
can be combined
with 1/4" jack
antenna:
the longer
the better
1/2 blued razor
other half connected
to inductor coil
1/4" jack or pickup
to be plugged into amp


A
Ground
Antenna
A
Rotate For Tuning
I
B
B
B
G
G
B
I
C
F
B
B
E
D
B
B
B
B
Copyright © 1999, All Rights Reserved. Prebles Originals
A
A
Phones

Full Size

The PO-102, Crystal Radio Kit, w/Slider-Tuning!



Perfect for parents, grandparents, and teachers to build with kids! Also a super starter kit for the beginning adult builder! Includes small coil form, wire, slider assembly, capacitors, and diode. Easy parts layout guide provided for kids. Excellent performance for such a simple but elegant classic slider. Earplug included.

PO-102, w/Crystal Earphone


L-1, Coil Assembly
Peebles
Originals
Model
# PO-102
"1650"
"550"
Ground
Slider/ ner Pivot
C-2,
330pf.
"331"
Short
Antenna
C-3,
0.001uf.
"102"
R-1: Yel/Vio/Or
47K
Earphone
C-1,
47pf.
"47"
D-1,
Germanium Diode
Long
Antenna
Copyright © 2004, All Right Reserved, Peebles Originals

PO-102, Chassis Assembly, Top-View.

FIRE KIT EXAMPLE


COMPRESSED TRIOXANE
WATER PROOF CASE
WATERPROOF MATCHES IN WATERPROOF CASE
Waterproof
3440
Fixed Compartment
FAT WOOD
HOME-MADE FIRE STARTERS
CHEM-LIGHTS FOR STARTING FIRES IN DARK
9 HOUR CANDLE
FARRO ROD
KEY CHAIN FOR FARRO ROD


PREPPERS SHOP
PREPARE
DEFEND
SURVIVE
FIRST
CONSERVE WATER
NAVIGATION
HIGHLANDER
SURVIVAL BAG
SAWYER
KOMBAT

WWW.PREPPERSSHOP.CO.UK

THE ULTIMATE BUG OUT BAG

1. Anglo Arms Rambo Knife
2. Anglo Arms Machete
3. Austrian Ex-Military Water Flask
4. BCB Trekker Lifesaver Pack
5. BCB Compact Fishing Kit
6. Canadian Gas Mask w/ Filters
7. Feit Electric 500 LED Torch
8. French Military Mess Tins
9. Hexamine Solid Fuel Cooker
10. Heavy Duty Camo Tarp
11. Highlander Survival Bag
12. Highlander Solid Fuel Cooker
13. Highlander Trekker Hammock
14. Highlander Folding Saw
15. Kombat UK W/proof Matches
16. Kombat UK 40l Molle Bag
17. Kombat UK Fire Starting Kit
18. Kombat UK Compass
19. Kombat UK Throwing Axe
20. Oasis Water Purification Tablets
21. Pro Force Survival Saw
22. Sawyer Mini Water Filter
23. Sharpening Stone
24. Survival Mirror
25. Turboflame Lighter
26. UST Survival Poncho
27. Wateproof Rucksack Liner
28. Wind Up Solar Torch
29. Wooden Deluxe Knife w/ Case
30. 100ft Paracord
31. 24hr Ration Pack

£280


ER bar
DRINKING WATER
DATREX
DUCK
SLEEPING BAG
FRONTIER STRAW
Emergency Poncho

#1
#2
#3
#4
#5
Black
#6
#7
#8
Defense Spray
#9
#10
#11
#12
#13
WISE
OUTDOOR MEALS
CHEESY LASAGNA
#14
#15
#16
#17
#18
#19
#20
#21
#22
#23
Matches
#24
POTABLE AQUA
PA-PLUS
#25
#26

Maine Military Supply's 72 Hr Bug-Out-Bag

Item Description	SKU:	Org.Price:
#1: Solar Panel Charger	014318	$49.99
#2: Tactical Trauma Kit #1	0082110003	$39.99
#3: 8LED Head Lamp Silver	019140	$4.99
#4: 40IN-1 Dynamo Energy Radio	019138	$19.99
#5: 100' Black Parachute Cord	016704	$6.99
#6: One (1) Ameriglow 6" Light Stick	018848	$1.99
#7: Magnesium Fire Starting Tool	005608	$7.99
#8: Sabre 3-IN-1 Defense Spray	005555	$11.99
#9: Emergency Survival Blanket	05606	$2.99
#10: Spork OD	020362	$3.99
#11: New Wire Handle Canteen Cup	008506	$9.99
#12: Canteen w/ Cover OD 1qt	003927	$8.98
#13: Wise Emergency Food Kit 72hr	017279	$29.99
#14: Medium Transport Pack Black	020355	$48.99
#15: Adventurer Knife Kit	020363	$24.99
#16: Trip Wire: Yellow & Green	019917	$2.99
#17: Waterproof Storage Box	019152	$1.99
#18: 10hr Hand and Body Warmers (x3)	08016	$4.47
#19: Coin Towels 4pk Tubes (x3)	019415	$1.47
#20: 3-IN-1 Compass Whistle	019133	$2.99
#21: 3-IN-1 Waterproof Match Tube	019759	$1.99
#22: Marching Lensatic Army Compass	007127	$11.99
#23: Waterproof Matches	016379	$2.99
#24: Water Purification PA+Plus Tabs	012838	$11.99
#25: 11 Function Survival Tool	019145	$2.99
#26: German Folding Stove w/ Fuel	003929	$2.99
	Total:	$322.69
		-20%
	Your Price:	$258.15

Total Bug Out Bag
Weight: 12.4lbs


ANKER
PowerPort Solar
nalgene
KOLD.
Survival Theory:
A PREPAREDNESS GUIDE
HOW TO SURVIVE THE END OF THE WORLD ON A BUDGET
Jonathan Hollerman
ULTRALEGER / ETANCHE A L'EAU
TROUSSE MEDICALE
7
SPORT
50
REPEL
BK-2


Bug out Bag
Water Bottle w/ Charcoal Filter
Aquamira Tablets
70 oz Camelbak Bladder in bag
Handwarmers
Cotton Balls
Fire Starter
Knife
Matches
TP
BG Parang
Fenix Flashlight w/
CR123 Batteries
6 MRE's
Fuel Stove Kit
Spare Contcats
First Aid Kit w/ Quikclot
Israeli Bandage
Walther P99 w/ 130 rds
of 9mm
Baby Wipes

6 EMERGENCY USES FOR PARACORD

1. Snare Trap



2. Fishing Line



3. Shelter



Did you know?

A single length of paracord has been tested to handle 550 lbs of weight.

Did you know?

There are seven internal strands, each of which comes apart into two, so there's 14 thin lines.

4. Fishing Net



5. Fire


SOCKET
BOW
DRILL
FIRE BOARD
CORD

6. Bear Bag




AFTER 1 HOUR
© BRIGHTSIDE

5 WAY TAG STRIP

36 WAY TAG STRIP - TWO ROWS

e wired together ,with a little ingenuity, with the component wires being held together in the grip of solderless crocodile clips, whereby the conne
older.

ex circuits a plastic Terminal Block (sometimes referred to as a choc' or chocolate block) can be utilised very effectively indeed. These are used
15 Amp and 30 Amp. The 5 and 15 Amp Terminal Blocks I have found to be the most suitable. The various component wires can be trappe
makes it easy to change the components around when experiment with different circuits. See The EXPERMENTAL CRYSTAL SET for more de

'CHOCOLATE' TERMINAL BLOCK

Where to connect to the earbud jack.


one earbud
the other earbud
connect to for either earbud

For connecting to one earbud only.


transformer

For connecting to both earbuds.


transformer


RGB
BLUE
GREEN
GND
RED

The current-limiting resistors are part of the cardboard circuit. The black spots are where I used the Bare Conductive paint


MIC
VCC
GND
A PIN

The micro:bit is plotting the analog values on the 5x5 LED matrix, which represent the noise level in the room.

D PIN
2 BUTTON BOARD
"ACTIVE LOW"
D PIN
GND
BARE
ELECTRIC PAINT

All you need to get started is a roll of copper tape, a few components and conductive paint. One roll of tape and tube of paint can make about 200 circuits.

COSMIC VIBRATIONS

Octave	Manifestation	Vibrations per second	Gaps
1	TOUCH	2	
2		4	
3		8	
4		16	
5	SOUND	32	
6		64	
7		128	
8		256	
9		512	
10		1,024	
11		2,048	
12		4,096	
13		8,192	
14		16,384	
15	ELECTROMAGNETIC (Longer Radio Waves)	32,768	
16		65,536	
17		131,072	
18		262,144	
19		524,288	
20		1,048,576	
21		2,097,152	
22		4,194,304	
23		8,388,608	
24		16,777,216	
25		33,554,432	
26		67,108,864	
27		134,217,728	
28		268,435,456	
29	ELECTROMAGNETIC (Microwaves)	536,870,912	
30		1,073,741,824	
31		2,147,483,648	
32		4,294,967,296	
33		8,589,934,592	
34		17,179,869,184	
35		34,359,738,368	
36		68,719,476,736	
37		137,438,953,472	
38		274,877,906,944	
39	HEAT OR INFRARED	549,755,813,888	
40		1,099,511,627,776	
41		2,199,023,255,552	
42		4,398,046,511,104	
43		8,796,093,022,208	
44		17,592,186,044,416	
45		35,184,372,088,832	
46		70,368,744,177,664	
47		140,737,488,355,328	
48		281,474,976,710,656	
49	VISIBLE LIGHT	562,949,953,421,312	
50		1,125,899,906,842,624	
51	ULTRAVIOLET	2,251,799,813,685,248	SPIRIT ELECTRONS
52		4,503,599,627,370,496	
53		9,007,199,254,740,992	
54		18,014,398,509,481,984	
55		36,028,797,018,963,968	
56		72,057,594,037,927,936	
57	X-RAY	144,115,188,075,855,872	
58		288,230,376,151,711,744	
59		576,460,752,303,423,488	
60			PSYCHIC PROJECTIONS
61			
62	GAMMA AND COSMIC RAYS	4,611,686,018,427,387,904	
63			
64		*The Vibrations in these octaves increase to an incomprehensible number per second.*	
65			
66			
67			
68			
69			
70		*The phenomena of psychic projections and soul essence occur in octaves considerably beyond those of any known material manifestations. Consequently, they must not be considered as immediately following any manifestations which we have shown on this chart.*	
71			
72			
73			SOUL ESSENCE
74			
75			
76			
77			
78			
79			
80			

(THESE INTERVALS AND FIGURES ARE APPROXIMATE AND NOT EXACT)

LITHO. IN U. S. A.

NOTICE

This chart was carefully compiled by the Editorial and Research Departments of AMORC College after consulting the most eminent scientific authorities on the subjects of physics and chemistry and comparing their observations and notations with the reports from the Rosicrucian laboratories in foreign countries.

There is a slight disagreement in regard to the rates of vibrations for the various keys of the musical keyboard, due to different standards of pitch in various countries, and there is some disagreement among scientific authorities in regard to the colors associated with various musical notes. This chart represents not only the consensus of most of these authorities but also adheres strictly to what the Rosicrucians have been able to demonstrate as truth in our own laboratories and in the experiments of thousands of members in various parts of the world. Regardless, therefore, of any disagreement with authorities outside the organization, this chart is the authentic presentation of the Rosicrucian knowledge.

This chart is to be used by the members of the Rosicrucian Order in connection with their studies and experiments and is not to be used for any other purpose or in any other way. Like the lessons themselves, this chart and the facts contained on it are reserved and restricted in use under the rules and regulations of the organization.

INTERNATIONAL
SEAL OF THE
SUPREME LODGE
of the
Rosicrucian
Order

THE SOLAR SPECTRUM



AMORC
THE
Rosicrucian Order
San Jose, California


5V
9V
12V
L7805CV
CC1AT V6
MAR 805
J29
LM7809AC
L7812CV
G408B V6
CHN 930

7 LOGIC GATES & 4 USEFUL COMBINATIONS



Standard Logic Gates

NOT

A	B
1	0
0	1

AND

A	B	C
1	1	1
1	0	0
0	1	0
0	0	0

NAND

A	B	C
1	1	0
1	0	1
0	1	1
0	0	1

OR

A	B	C
1	1	1
1	0	1
0	1	1
0	0	0

NOR

A	B	C
1	1	0
1	0	0
0	1	0
0	0	1

XOR

A	B	C
1	1	0
1	0	1
0	1	1
0	0	0

XNOR

A	B	C
1	1	1
1	0	0
0	1	0
0	0	1

Preceding NOT Gate on One Input for AND, NAND, OR, NOR Gates

A	B	C
1	1	0
1	0	0
0	1	1
0	0	0

A	B	C
1	1	1
1	0	1
0	1	0
0	0	1

A	B	C
1	1	1
1	0	0
0	1	1
0	0	1

A	B	C
1	1	0
1	0	1
0	1	0
0	0	0

Use XNOR

A	B	C
1	1	1
1	0	0
0	1	0
0	0	1

Use XOR

A	B	C
1	1	0
1	0	1
0	1	1
0	0	0

Copyright 2012 PicoKit



TYPE N F



SMA M



PAL/BELLING LEE F



UHF F



MCX MALE
(OTHER END)



TYPE F F



BNC F



SMA F


TYPE N F


SMA M


PAL/BELLING LEE F


UHF F


MCX MALE
(OTHER END)


TYPE F F


BNC F


SMA F

DIODE


k
k
no connection
a
k
k
k
line
k

schematic symbol

direction of current flow

7. 555 Timer Projects



In this section we will make :

- 7.1 4 Key Piano
- 7.2 Light sensitive music circuit
- 7.3 Light controlled Police Siren
- 7.4 Touch Switch
- 7.5 Timer
- 7.6 Continuity Tester
- 7.7 Knight Rider
- 7.8 Cricket Game
- 7.9 Multipurpose circuit
- 7.10 Johnson counter

Some Parts of this project are available in Video CD ROM

Internal diagram of 555


+Vcc
8
5k
7 discharge
threshold 6
control 5
voltage
1
threshold
comparator
S
Q
R
T1
RS
Flip
Flop
5k
2
trigger 2
R
Q̄
3 output
trigger
comparator
5k
High = +ve = 1
Low = -ve = 0
1 ground
4
reset

What is it about ?

555 timer integrated circuit (IC) is a very popular chip used in variety of applications like timer, pulse generation and oscillators. This is a low cost, stable and widely available chip which makes it favorite for hobbyists. The internal components of 555 as shown in figure consists of 2 comparators and a flip flop. All of these components contain 25 transistors and 15 resistors packed in the IC.

The three highlighted 5k resistors shown in figure are the reason why this IC is named as 555.


GND
1
TRIG
2
OUT
3
RESET
4
555
8
Vcc
7
DIS
6
THR
5
CTRL

Please note the notch near first pin. This is made to indentify the first pin of IC.

Pin	Name	Purpose
1	GND	Ground reference voltage, low level (0 V)
2	TRIG	The OUT pin goes high and a timing interval starts when this input falls below 1/2 of CTRL voltage (which is typically 1/3 of V_{CC}, when CTRL is open).
3	OUT	This output is driven to approximately 1.7V below $+V_{CC}$ or GND.
4	RESET	A timing interval may be reset by driving this input to GND, but the timing does not begin again until RESET rises above approximately 0.7 volts. Overrides TRIG which overrides THR.
5	CTRL	Provides "control" access to the internal voltage divider (by default, 2/3 V_{CC}).
6	THR	The timing (OUT high) interval ends when the voltage at THR is greater than that at CTRL.
7	DIS	Open collector output which may discharge a capacitor between intervals. In phase with output.
8	V_{cc}	Positive supply voltage, which is usually between 3 and 15 V depending on the variation.


120 ohm 5%
1st
2nd
3rd
Multiplier
Tolerance
1st
2nd
3rd
Multiplier
Tolerance
4.7k ohm 1%

	1st	2nd	3rd	Multiplier		Tolerance	
0	Black	Black	Black	Black	1		
1	Brown	Brown	Brown	Brown	10^1	Brown	1%
2	Red	Red	Red	Red	10^2	Red	2%
3	Orange	Orange	Orange	Orange	10^3		
4	Yellow	Yellow	Yellow	Yellow	10^4		
5	Green	Green	Green	Green	10^5		
6	Blue	Blue	Blue	Blue	10^6		
7	Violet	Violet	Violet	Violet	10^7		
8	Grey	Grey	Grey	Grey	10^8		
9	White	White	White	White	10^9		
				Gold	0.1	Gold	5%
				Silver	0.01	Silver	10%

ELECTROMAGNETIC RADIATION SPECTRUM


Size reference
football field
man's height
baseball
paperclip thickness
paper thickness
blood cells
viruses
bacteria
water molecule
atom
atomic nucleus →
wavelength
λ (m)
1 ft
1 cm
1 mm
1 mil
1 μ
1 nm
1 A
1 pm
10^3 10^2 10^2 1 10^{-1} 10^{-2} 10^{-3} 10^{-4} 10^{-5} 10^{-6} 10^{-7} 10^{-8} 10^{-9} 10^{-10} 10^{-11} 10^{-12}
Biological Effect
Non-ionizing Radiation
Ionizing Radiation
Induced Currents
Heating
Ex & Phcm
Ionization – DNA Damage
electron volt
(eV)
10^{-9} 10^{-8} 10^{-7} 10^{-6} 10^{-5} 10^{-4} 10^{-3} 10^{-2} 10^{-1} 1 10 10^2 10^3 10^4 10^5 10^6
frequency
(Hz)
1 MHz
1 GHz
1 THz
1 PHz
1 EHz
1 ZHz
10^5 10^6 10^7 10^8 10^9 10^{10} 10^{11} 10^{12} 10^{13} 10^{14} 10^{15} 10^{16} 10^{17} 10^{18} 10^{19} 10^{20} 10^{21}
Bands
Radio Spectrum
Broadcast and Wireless
Microwave
Terahertz
Infrared
Ultraviolet
X-rays & Gamma Rays
Soft X-ray
Hard X-ray
◄ electronics
optics ►
Visible wavelengths (nm)
700 625 575 540 470 440
Sources and Uses of Frequency Bands
AM radio
600kHz-1.6MHz
FM radio
88-108 MHz
Mobile Phones
900MHz-2.4GHz
RADAR
1-100 GHz
MRI (1.5T)
63.86 MHz
TV Broadcast
54-700 MHz
Wireless Data
~2.4 GHz
SmartMeter
0.9-2.45 GHz
Microwave Oven
2.4 GHz
"mm wave"
"sub-mm"
Screening
0.2-4.0 THz
Fiber telecom
0.7-1.4 μm
Dental Curing
200-350nm
Visible Light
700-400nm
Remotes
850 nm
Night Vision
10-0.7 μm
Suntan
400-290nm
Medical X-ray
80 kev
Cosmic Gamma Rays
>10Bev
Baggage Screen
160 keV
PET
511 kev
Bone Scan
140 keV


signal diode
light emitting diodes
IR LEDs
photodiodes
transient voltage supression diodes
zener diodes
constant current diode
shottkey diode
shockley diode
step recovery diodes
super barrier diode
tunnel diodes
varactor diodes
PIN diodes
point contact diode
LASER diodes
vaccum diode
peltier diodes
gunn diode
crystal diode
avalanche diode
silicon controlled rectifier

Types of Diode


X2 capacitor
called "mains capacitor"
electrolytic
called "can electrolytic"
the line is
negative !!!
surface mount electrolytic
tantalum
the line is positive !!!
black mark negative
surface mount capacitor
green cap
+
+"pig tail" electro
double-ended electro
single-ended electro
+
air trimmer
"green cap"
but RED !!!
high voltage ceramic
high voltage ceramic
monolythic
capacitor
(ceramic)
"bead"
capacitor
(ceramic)

tantalum capacitors can
"go up in smoke"

"bead" tantalum

Electronics
Reference Sheet v1.1b

LED


Cathode -
Anode +
Marked by color or dot

CAPACITOR



REGULATOR (e.g. LM78xx)


Vin
Vout
GND
VIN
GND
EN
VOUT
NOISE (CAP)

Resistor

	Digit	Multiplier	Tolerance
Silver	-	0.01	±10%
Gold	-	0.1	±5%
Black	0	1	-
Brown	1	10	±1%
Red	2	100	±2%
Orange	3	1k	-
Yellow	4	10k	-
Green	5	100k	±0.5%
Blue	6	1M	±0.25%
Violet	7	10M	±0.1%
Gray	8	-	-
White	9	-	-


1st Digit
2nd Digit
Multiplier
Tolerance
000
1st Digit
2nd Digit
Multiplier

DIODE



NPN transistor (Current sink)
(e.g. PN2222)


TO-92
E B C
SOT-23
C
B E
VCC
INPUT
B
C
E
GND

N-channel MOSFET


Gate
Source
Drain
SOT-23
D
G S
VCC
D
INPUT
G
S
GND

PNP transistor (Current source)
(e.g. PN2907)


TO-92
E B C
SOT-23
C
B E
VCC
INPUT
B
E
C
GND

P-channel MOSFET


Gate
Source
Drain
SOT-23
D
G S
VCC
INPUT
G
S
D
GND

* Please note that some components may have a different pinout than the one showed above, you should always check the data sheet before using a new component.


Reich's Orgone Accumulator Box
Cutaway View of Box Layers
Fiberglass (*Organic*)
Steel Wool (*Inorganic*)
Fiberglass (*Organic*)
Steel Wool (*Inorganic*)
Ambient Orgone (Etheric) Energy
Accumulated Orgone (Etheric) Energy
Key:
+ Positive Orgone (Etheric) Energy (a.k.a., "OR" / "POR")
− Deadly Orgone (Negative Etheric) Energy (a.k.a., "DOR")
rgonite.info

How to build a Don Croft ORGONITE CLOUD BUSTER

Refer to (Part 1 - 2) How to Make an Orgonite CloudBuster:
http://www.youtube.com/watch?v=cCn1DO2Rj6k

Materials List:

Wear safety gear as necessary
- respirator, gloves when pouring resin.
- gloves & goggles when cutting wood - with a respirator if cutting MDF etc.

4 x 10' lengths of copper (or other) pipe (cut 3 lengths in half, and one length into six 1' pieces)

6 pipe endcaps and 6 pipe connectors

2 gallon bucket (polypropylene if possible)

10 double terminated quartz (6 of these must fit into garden hose for insertion into base of pipes)

6 pieces of garden hose (3/4" - 1" long)

Resin and metal suitable for orgonite

A roll of tape (duct tape etc)

Glue (silicone glue will work)

Stick for mixing metal into resin when pouring layers

Top, middle (temporary) and bottom spacers cut and drilled out of wood. If not buying readymade, use templates or measure with copmass, ruler, pencil.
Drill the holes with 1 1/8" and 1 1/4" wood drill bits, and cut into shape with a Jigsaw.



Third - The temporary spacer is removed and the pipe-tops are taped up to stop resin or metal getting into them.
Further layers are poured, allowing resin to cure and cool between pouring.
More crystals or other components may be added with the basic orgonite mixture.
When done, the tape is removed from the pipe ends.

Second poured layer (the temporary spacer is fixed in place while this layer is curing, and then removed)

First poured layer (1" - 1 1/2" high) Include four double-terminated crystals at compass points

Six 5' lengths of copper pipe
When the orgonite base of the cloud buster is complete, fix the top pipes to the bottom ones using pipe connectors, then fix the top spacer in place to provide stability.

Image shortened to save space

Top Spacer

Pipe connectors

Six 1' lengths of copper pipe
(1" diameter pipe)

Temporary Spacer
This spacer fits tightly into the top of the bucket. (used to hold the pipes in place while the first layer of resin cures)

2 Gallon ......plastic bucket (8" bottom-interior diameter, 9" top interior diameter)

Orgonite 50:50 metal:resin

Double Treminated Crystal (secured into hose with glue)

Bottom Spacer

Section of garden hose 3/4" - 1" piece (glued into end cap with silicone glue)

Copper end cap

Four double terminated crystals in the base are aligned with the cardinal directions

Taped joint where each copper pipe fits into its end cap (duct tape or any kind to stop resin seeping into endcap)


BOAT
BOAT
GOOP
HOUSEHOLD


Fiberglass Bi-Unit
Nylon Thread Crossarm Pin
Machine Bolt
High Voltage Forged Steel Pin
Aluminum Distribution Connector
Automatic Splice
Overhead Switch
Low Voltage Insulator Pin
Crossarm Brace
Guy Hook
Strain Plate
Trunion Suspension Clamp
Guy Clamp
Guy Wire Clip
Polymer Line Post Insulator
Secondary Racks
Wildlife Protector
Polymer Deadend Insulator
Deadend Strain Clamp
Stirrup Clamp
Aluminum Transformer Bracket
Lag Screw Type Pin
Lead Top Pin With Steel Bolt
Support Bracket
Arrester
Hot Line Clamp
Machine Bolt & Square Washer
Motor Operator
Single-Phase Recloser
Polymer Arrester
Cutout & Arrester Bracket
Alley Arm Brace
Electronic Sectionalizer
Cutout
Dead End Clevis
By-Pass Switch
Polymer Cutout
Polymer Riser Pole Arrester
Double Arming Bolt
Pole Step
Insulated Clevis
Thimble Eye Nut
Thimble Eye Bolt
Pole Eye Plate
Machine Bolt & Washer
Fiberglass Guy Strain Insulator
Suspension Clamp
Lashing Clamps
Guy Wire Clip
Sus-pension Clamp
U Cable Guard
Guy Marker
Conduit Standoff Bracket
Bonding Clamp
Automatic Guy Deadend
Detachable Pole Step
Cable Guard Strap
Polymer Elbow Arrester
Lag & Plate for Detachable Pole Step
Ground Rod Clamp
Thimble Eye
Separate Elbow
Anchors
Junction
Multi-Tap
Ground Rod
Motor Operator
Padmounted Switch
Polymer Concrete Underground Enclosure
Deadbreak Elbow
Grounded Bushing
Polymer Concrete Box Pad or Flat Pad


3 phase primaries
Standoff
Hot1
Pole
Hot2
Hot3
3 Fuses
3 Transformers
Service neutral
Neutral
Insulators
3 secondary Hot drop wires


S1
Meter
Gnd
C1
D1
Probe
Gnd
I/P


Probe
OA91
+
S1
Circuit under Test
50 ohm
75 ohm
1nF
Digital Meter
100 1W
100 1W
150 1W
150 1W
Ground
–

N. TESLA.

APPARATUS FOR TRANSMITTING ELECTRICAL ENERGY.

APPLICATION FILED JAN. 18, 1902. RENEWED MAY 4, 1907.

1,119,732. Patented Dec. 1, 1914.


P
P
D
D
V
E'
D'
H
F
F
B
A
G
F'
C
E





New York, Aug. 30th, 1901
46 & 48 East Houston Str.

Mr. Stanford White
160 Fifth Ave.
New York City

My Dear Stanford:
Many thanks for your suggestions. I am writing to Mr. Powell today. Perhaps he will be able to clear the land altogether.

I want you to understand that I went to the American Bridge Company simply because of my anxiety to have the work pushed through as fast as practicable. I am only too glad to follow your advice and beg you to consider yourself absolutely free in your choice and arrangements regarding this work.

Yours very sincerely,
N. Tesla

New York, Sep. 12th, 1901
46 & 48 East Houston Str.

Babcock & Wilcox Co.
85 Liberty Street
New York City

Gentlemen:
Under enclosure I forward sketch showing your two boilers as they will be placed in my building and their position relative to and exact distance from the chimney. The scale is ½ inch to a foot.

You will greatly oblige me by furnishing the drawings of the flues leading to the chimney and the position of the breech, as the builder cannot proceed without this information.

Yours very truly,
Encl.

Anyone familiar with the Wardenclyffe Tower knows it to have been a colossal structure. Yet, few realize that it was supposed to have been even larger. Although the exact figures are not revealed, Tesla must have drastically underestimated the cost of building his structure as is evidenced by the following response to White.



Fig. 5 Oscillating statically charged terminal.



Fig. 6 Oscillating electrostatically charged dome.

N. TESLA

APPARATUS FOR TRANSMITTING ELECTRICAL ENERGY.
APPLICATION FILED JAN. 18, 1902. RENEWED MAY 4, 1907.

1,119,732. Patented Dec. 1, 1914.

This patent was the result of Tesla's many high voltage transmission experiments at Colorado Springs during the early 1900's. It served as the basis for the construction of the famous:-''Waldencliff Tower,'' which was intended to become a transmission station for wireless electrical power.


SPHERICAL METAL PLATES
P
P
SPHERICAL METAL PLATES
D
D
TERMINAL
TERMINAL
V
HIGH PRESSURE - (Voltage) RESERVOIR
CONDUCTOR
B'
DRUM
CONDUCTING HOOD
D'
H
SUPPORT LEG
F
F
SUPPORT LEG
COIL
B
(SUPPORT) VERTICAL ROD
COIL
A
SUITABLE SOURCE OF CURRENT
G
F'
C
PRIMARY COIL
E
GROUND PLATE

WITNESSES:
M. Lawson Dyer
Benjamin Miller.

Nikola Tesla, INVENTOR,
BY Kerr, Page & Cooper,
his ATTORNEYS.



"HIGH SELECTIVITY CRYSTAL RADIO"
[WITH SHORT WAVE]

RGK 2007

570KHZ → 2.5MHZ


L1
28T.
17T.
C1
D1
C2
R1
J1
GROUND TO FRONT ALUMINUM PANEL
ANT.
L2
24T.
(EARTH) GND.
SW1.
12T.

L1 & L2 = #22 ENAM. WIRE ON 3" PVC PIPE.
(PIPE IS ACTUALLY 3¼" DIAM")
D1 = 1N34 OR OA47 GERMANIUM DIODE
C1 = 365 PF. VARIABLE CAPACITOR / THESE
USUALY TUNE FROM 15 → 400 PF.
C2 = .0047 μF
R1 = 47K Ω ¼ OR ½ WATT. / J1 = ¼" AUDIO JACK

[L1/L2 NOTES: L1 = 45 TURNS TOTAL & L2 = 36 TURNS TOTAL. THE SPACE BETWEEN L1 & L2 IS 1 1/16".]

SW1 = S.P.S.T. SWITCH / FOR ANTENNA MATCHING


630V 0245
150M


EXTENDED DAY CREED
WATCH YOUR THOUGHTS THEY BECOME YOUR WORDS,
WATCH YOUR WORDS THEY BECOME YOUR FEELINGS,
WATCH YOUR FEELINGS THEY BECOME YOUR ACTIONS,
WATCH YOUR ACTIONS THEY BECOME YOUR HABITS,
WATCH YOUR HABITS THEY BECOME YOUR LIFESTYLE,
WATCH YOUR LIFESTYLE IT CONTROLS YOUR DESTINY.

05/07/2013 04:26 PM


Frequency (Hz)
C8 - 4186.0
B7 - 3951.1
A7# - 3729.3
A7 - 3520.0
G7# - 3322.4
G7 - 3136.0
F7# - 2960.0
F7 - 2793.8
E7 - 2637.0
D7# - 2489.0
D7 - 2349.3
C7# - 2217.5
C7 - 2093.0
B6 - 1975.5
A6# - 1864.7
A6 - 1760.0
G6# - 1661.2
G6 - 1568.0
F6# - 1480.0
F6 - 1396.9
E6 - 1318.5
D6# - 1244.5
D6 - 1174.7
C6# - 1108.7
C6 - 1046.5
B5 - 987.77
A5# - 932.33
A5 - 880.00
G5# - 830.61
G5 - 783.99
F5# - 739.99
F5 - 698.46
E5 - 659.26
D5# - 622.25
D5 - 587.33
C5# - 554.37
C5 - 523.25
B4 - 493.88
A4# - 466.16
A4 - 440.00
G4# - 415.30
G4 - 392.00
F4# - 369.99
F4 - 349.23
E4 - 329.63
D4# - 311.13
D4 - 293.66
C4# - 277.18
C4 - 261.63
B♭
C
B
A
G
F
E
D
C
B♭
B
A
G
F
E
D
C
B
A
G
F
E
D
C
B
A
G
F
E
D
Middle
C
16
15
14
13
12
11
10
9
8
harmonic
harmonic
harmonic
harmonic
harmonic
harmonic
Fundamental


COIL 80 TURNS
Antenr
EARTH
E
A
DIODE
EARPIECE


L1
TO EARTH
TO AERIAL
1
2
3
4
5
6
7
8
9
10
11
12
TB1
k
D1
a
TO HEADPHONES (TL1)
C1
TUNING

RF Energy Harvesting for INTERNET OF THINGS

The world
is the index
Take the world
on line
Take control
of the world
Let the things
talk to each
other
Let thing
become
intelligen

K.J. Vinoy

ECE Dept
Indian Institute of Science
Bangalore 560012

ECE Dept, Indian Institute of Science

- **Vision Statement:** Excellence in Theoretical and Experimental Research in Communications, Signal Processing, Microelectronics and RF/Photonics.
- **Faculty: 24;** Fellows of IEEE: 4; Fellows of INAE: 8
- Active in Publications: Books, Book Chapters, Journal & Conference Papers; Patents; Standardization etc
- Collaborative research

People
Masters Students
[ME, MSc→ Mtech, Mtech(Res)]
PhD Students
Project Staff

INTERNATIONAL COLLABORATION
ILLINOIS
LOS ANGELES
MASSACHUSETTS
MICHIGAN
SAN DIEGO
FRANCE
FINLAND
GERMANY
NETHERLANDS
NORWAY
SWEDEN
SWITZERLAND
HONGKONG
JAPAN
KOREA
TURKEY
AUSTRALIA
MELBOURNE

NATIONAL COLLABORATION
Major collaborative initiatives


CAMPUS INTERACTION
CNS
AERO
NANO
CHEM
MCBL
MBC
ISU
IMI
CEDT
CSA
EE
MECH


Departmental Collaboration
PV
BSR
PVK
RS
AC
VS
SENSOR NETWORK
AK
UM
NM
KVS
TVS
CM
NB
TS
BA
DND
MV
GB
AG
KJV



ECE: Microwave Engineering

K.J. Vinoy

- Low-Actuation Voltage Capacitive RF MEMS Switch (<10V)
  - Low-complexity fabrication process to enhance process yield
  - High reliability: no failure even up to 10 million cycles of operation tested
- Meso-scale Electrostatic Phase Shifter on microwave Laminate (MEPL)
  - Utilizes modern printed circuit board fabrication technology.
  - X-band monolithic antenna array system on the microwave laminate board demonstrated.

- Wideband group delay engineering in RF circuits for radar, medical imaging, and spectrum sensing.
  - Demonstration uses two stage All – Pass Networks; can be extended over multiple stages to obtain a higher bandwidth and/or higher group delay slope.
- RF energy harvesting circuits
  - Integrated with RF transmitters and sensors for practical IoT nodes
  - High efficiency RF-DC converter which can operate at input power of -20dBm (10µW) at 2.4GHz using UMC 130nm process MOSFETs.
- FEM based algorithms for Electromagnetic circuits & components (periodic structures such as metamaterials)
  - Fast computation of electromagnetic propagation characteristics
  - Especially suited for evaluation of processes uncertainties











Setting the stage….

- **Introduction**
  - **Wireless Power Transfer**
    - **Energy Harvesting**
  - **Internet of Things**
- Highlights of Recent Development (Hardware)
  - Powering wireless terminals
  - RFID with integrated sensors

Ongoing Research Challenges

Wireless Power Transfer (WPT)

- Indicates transfer of electric energy remotely

- WPT has a long history!!
  - Tesla demonstrated it in 1899 by wirelessly powering fluorescent lamps 40 kms away from the power source.
  - Had multiple patents in early 1900s.





- In 1960s W.C. Brown coined the term Rectenna, which he used to directly converts incoming microwaves to DC.
  - He demonstrated its ability to power a helicopter solely through microwaves for 10 hours continuously.

- These demonstrations involved dedicated sources with **large power to transmit over long distances**.

http://mainland.cctt.org/istf2008/brown.asp

SSPS

- Space Solar Power Satellites

- WPT is widely investigated for putting **solar power generating satellites** into space and transmitting power to Earth stations. (Mainly in Japan)



http://www.jspacesystems.or.jp/en_project_ssps/

Near field Wireless Power Transfer

- Recent demonstration by MIT to transfer high RF power (Watts) transferred across meters.
- Resonant coils are used
- Typically at 100 kHz to 10’s of MHz
- Many new applications emerged





André Kurs et al, Wireless Power Transfer via Strongly Coupled Magnetic Resonances , Science, Vol. 317 no. 5834 pp. 83-86. 6 July 2007.

System Schematic Qi



Typical inductive power system

Power
AC to DC
Drivers
Rectification
Voltage Conditioning
Load
Communication
Controller
V/I Sense
Controller
Transmitter
Receiver
Texas Instruments

Source: Texas Instruments Qi Development kit

Far → Near in WPT

- Free space loss factor is a major bottleneck for power transfer at large distances

- Short distance/ Near field options
  - MIT demonstration (2007)
  - Qi Standard
  - Phone charging solutions
  - Vehicles running on wireless power
- Two extremes in WPT
  - mW ← → MW
  - mm ← → 1000s km
  - 100kHz ← → 2.4/5.8GHz
  - 10cm x 10cm ← → km x km
  - Commercial vs bluesky



Far Field Transfer of RF Energy

- Focus of this talk
- Applications: RFID tags, Wireless Sensor Network nodes, biomedical equipment, home automation and structural monitoring can benefit from RF energy harvesting.
- Block diagram and a design example:


Antenna
Matching circuit
(Microstrip
transmission lines)
Rectifying element
(For example: Schottky diode)
Storage capacitor
(For example: 0805 package 100pF)
Antenna
RF in
RF - DC
Matching
circuit
Rectifier
Storage
element
DC

A New Paradigm: Internet of Things (IoT)

- IoT refers to uniquely identifiable objects and their virtual representations in an Internet-like structure.



Connects Anytime, Anyplace for Anyone (ICT)

AAA + for Anything (IoT)

- IoT is a scheme for connecting things: sensors, actuators, and other smart technologies, thus enabling person-to-object and object-to-object communications.

- **Continuous availability of power is crucial for their deployment**

IoT Applications

- Transportation and logistics
  - Logistics
  - Assisted driving
  - Mobile ticketing
  - Environment monitoring
  - Augmented maps
- Heathcare
  - Tracking
  - Identification, authentication
  - Data collection
  - Sensing
- Smart environments
  - Comfortable homes/offices
  - Industrial plants
  - Smart museum and gym
- Personal and social
  - Social networking
  - Historical queries
  - Losses
  - Thefts
- Futuristic
  - Robot taxi
  - City information model
  - Enhanced game room

L. Atzori , A. Iera, G. Morabito, The Internet of Things: A survey Computer Networks 54 (2010) 2787–2805

Comparison of different wireless protocols

Today, a lot can be done at low power!!

Characteristics of key 2.4GHz ISM Band Radios studied :

	BLE	ANT	Zigbee	WLAN
Topologies	P2P , Star	P2P , Star, tree, mesh	P2P , Star, mesh	P2P , Star
Modulation	GFSK	GFSK	OQPSK	DSSS (802.11b)
Max data rate	1Mbps	12.8-60 Kbps	250Kbs (@2.4Ghz)	1- 11Mbps (802.11b)
Throughput	305 kbps	20Kbps	100Kbps	6Mbps (802.11b)
Range (in m)	10-100(0-10dBm)	30 (@ 0dBm)	10-100 (0-20dBm)	100+(20dBm)
Max nodes in piconet	7	65533	Star-65536	32-64
Battery life	1-2 years (coin cell)	1-2years (coin cell)	100-1000 days	0.5-5days

Key Aspects :

BLE is robust and has lowest power consumption but cannot natively form mesh networks,

Zigbee can support large mesh networks, power consumption is higher than BLE and throughput is lower: It is suitable for low data rate, low power, large size networks.

WLAN is primarily suitable for transferring bulk data at high speeds, Not suitable for low power applications.

Power Requirements in Common WSN

	Crossbow MICAz	Intel IMote2	Jennic JN5139
Radio standard	IEEE802.15.4/ZigBee	IEEE802.15.4	IEEE802.15.4/ZigBee
Typical range	100m (outdoor), 30m (indoor)	30m	1 km
Data rate (kbps)	250 kbps	250 kbps	250 kbps
Sleep mode (deep sleep)	15 μA	390 μA	2.8 μA (1.6μA)
Processor only	8mA active mode	31–53mA∗	2.7+0.325mA/MHz
RX	19.7mA	44mA	34mA
TX	17.4mA (+0dbm)	44mA	34mA (+3 dBm)
Supply voltage (minimum)	2.7V	3.2V	2.7V
Average	2.8mW	12mW	3mW

JM. Gilbert∗ F. Balouchi, Comparison of Energy Harvesting Systems for Wireless Sensor Networks, International Journal of Automation and Computing 05(4), October 2008, 334-347

	Jennic JN5148	**TI- CC430**	**BLE**	**Zarlink ZL70250**
Active mode current at 16MHz [mA]	6	4	6.7	3.2
Deep sleep current [nA]	100	1000	400	20
Transmission current [mA]@Tx-power [dBm]	15@2.5	18@0	36@2	2@-10
Transmit frequency	2.4 GHz	2.4 GHz	2.4 GHz	868 MHz
Wakeup time [ms]	1	3	0.12	0.16
Energy consumption for a transmission cycle of 2ms [µJ]	183	300	196	32
Power supply voltage [V]	2.2 – 3.6	1.8 -3.6	2-3.6	1.2 – 1.8

In perspective

- Energy requirements in different devices/systems
- 6 orders of magnitude variation!!!
- Energy requirements in WSN
  - Depends on the complexity/ standard/ range
  - eg 90 μW to power a pulse oxymeter sensor, to process data and to transmit them at intervals of 15 s

Device type	**Power consumption**
Smartphone	1W
MP3 decoder chip	58 mW
Hearing aid	1 mW
Wireless sensor node	100 μW*
RF receiver chip	24 mW
GPS receiver chip	15 mW
6D motion sensor	14.4 mW
Cell phone (standby)	8.1 mW
PPG sensor	1.473 mW
Humidity	1 mW
Pressure	0.5 mW
3D accelerometer	0.324 mW
Temperature	27 μW
Cardiac pacemaker	50 μW
Wristwatch	7 μW
Memory R/W	2.17 μW
A-D conversion	1 μW

J Yun, S. Patel, M.Reynolds, G. Abowd “A Quantitative Investigation of Inertial Power Harvesting for Human-powered Devices,” UbiComp’08, September 21-24, 2008, Seoul, Korea.

R.J.M. Vullers, et.al, Micropower energy harvesting, Solid-State Electronics 53 (2009) 684–693

Power Density from Various Harvesters

Ambient RF	< 1 μW/cm^2
Ambient light	100 mW/cm^2 (directed toward bright sun)
	100 μW/cm^2 (illuminated office)
Thermoelectric	60 μW/cm^2
Vibrational	4 μW/cm^3 (human motion ~Hz)
microgenerators	800 μW/cm^3 (machines ~kHz)
Ambient airflow	1 mW/cm^2
Push buttons	50 μJ/N
Hand generators	30 W/kg
Heel strike	Up tp 7 W for 1 cm deflection

Power requirements in conventional sensor network nodes may not be met by harvesting alone!

J Yun, S. Patel, M.Reynolds, G. Abowd "A Quantitative Investigation of Inertial Power Harvesting for Human-powered Devices," UbiComp'08, September 21-24, 2008, Seoul, Korea.

Electromagnetic: Solar → RF

- PV is a good source of energy. Recall,

Ambient light	100 mW/cm^2 (directed toward bright sun)
	100 μW/cm^2 (illuminated office)

- However, it light is not always available.
  - At night
  - Specific scenarios: in a closed chamber, or mine.
- RF is an alternative
  - Unlike others, RF sources may be ambient or intentional.
  - Ambient sources such as base stations or broadcast stations
  - Special sources: RF ID reader, Phone charger, special beacons

Demand and Supply

- The peak currents needed during transmit and receive operation is not achievable using the harvester alone.
- Buffering is also needed to ensure continuous operation during times without power generation.
- The combination of an energy harvester with a small-sized storage is the best approach to enable energy autonomy of the network over the entire lifetime.
  - Rechargeable battery
  - Thin film batteries
    - can be integrated directly in Integrated Circuit (IC) packages in any shape or size,
    - Flexible when fabricated on thin plastics
    - Thin film batteries have high impedance;
    - Low discharge efficiency compared to Li-ion batteries
  - super capacitor
    - Leakage in super capcitors depends on the voltage. Low at low voltage

Internet of Things (IoT)

Embedding short-range mobile transceivers into a wide array of gadgets and everyday items, enabling new forms of communication between people and things, and between things themselves.

RFID + Sensor + Smart Tech + Nano Tech = IoT


Honey, you could get those pants for less in Aisle 7.
We're missing a bottle here! Better come replace it.
I'm detergent #23409! I arrived yesterday on a truck from Factory #8!
As the shopper enters the store, scanners identify her clothing by the tags embedded in her pants, shirt and shoes. The store knows where she bought everything she is wearing.
A microchip embedded in her credit card talks to the checkout reader. Payment authorization is automatic.
As she removes a bottle of detergent, the reader in the shelf recognizes the need to restock and alerts the staff.
A reader at the checkout counter automatically tallies her purchases. No shoplifting here because the reader catches everything she is carrying.

When shopping in the market, the goods will introduce themselves.

When entering the doors, scanners will identify the tags on clothing.

When paying for the goods, the microchip of the credit card will communicate with checkout reader.

When moving the goods, the reader will tell the staff to put a new one.

Introduction to RFID

- The reader converts incident field and returns useful data
- In passive RFID systems reader transmits EM energy that "wakes up" the tag and provides power for the tag to respond to the reader.


tagged object
to host / network
reader antenna
host computer
radio transmissions
tag ID in chip memory
1C 04 3F
1C 04 3F
ID read from tag
reader
tag
integrated circuit

Backscatter Communication

- **Backscatter** is the reflection of signals back towards their source.
  - In this scheme, two devices communicate using incident (or ambient) RF as the source of power.
  - Backscattering is achieved by changing the impedance of a receiver in the presence of an incident signal.
  - When waves encounter a new media that have different impedances, a part of the wave is reflected.
  - The reflection depends on the difference in the impedances.
- By modulating the impedance at the receiver port, one can control the scattered RF energy, hence enabling information transmission.

abc.cs.washington.edu/files/comm153-liu.pdf

RFID → IoT

- RFID
  - Uses radio waves for identifying or tracking the object.
  - Proven to be a simple and cost effective system
  - Tags are very cheap and is possible to be attached to everyday objects.

- RFID is considered a prerequisite of **Internet of Things.**

- **Example: RFID tags can be integrated with sensors**
  - When a reader reads a tag, the sensor information will be sent to the reader along with the identity of the object.

Some Examples




S-TAG
RFID Antenna
Generic sensor
Digital input
RF-Digital Controller
RFID Chip
(ID1) (ID2) (ID3)...(IDn)



Discrete Element Based
WISP (Wireless Identification Sensing Platform)

Multi-Chip Based S-tag

Chips with I2C / SPI
SPARTACUS / RAMSES (Self-Powered Augmented RFID Tag for Autonomous Computing and Ubiquitous Sensing / RFID Augmented Module for Smart Environmental Sensing)


ams
SL900A-DK-STQFN16
www.ams.com
V1.0
L1
IC1
SL900A
C7
B1
JP1


(a)
(b)
Antenna Part
Circuit Part

Single IC Based Sensing Tags

Printed Chipless RFID Tag

WISP

- Wireless Identification Sensor Platform (2009)
  - WISPs are a wireless, battery-free sensing and computation platform, powered by harvested energy from off-the-shelf UHF RFID readers.
  - To a RFID reader, a WISP is a EPC gen1 or gen2 tag; but inside the WISP, the harvested energy is operating a 16-bit general purpose microcontroller.
  - The microcontroller can perform computing tasks, including sampling sensors, and communicate to the RFID reader.
  - WISPs have been built with various sensors, WISPs can write to flash and perform cryptographic computations.

A collaboration between Intel Research Seattle and the University of Washington.

WISP 4.1DL
Intel Research Seattle

http://wisp.wikispaces.com/Wisp+4.1+DL

RFID Sensors (Products)

- ID operation is passive; yet most sensors require power sources

- Powercast has a wireless sensor that is battery-less. Uses RF energy harvesting.
- Harvesting schemes works at power as low as -12dBm. (RF-DC conversion efficiency above 40% only above -8dBm)
- Harvested power >0.4mW for RF in of >-1dBm.
- Multiple custom ICs and discretes

- Other suppliers include
  - Phase IV
  - RFID sensor systems
  - etc



Sensor Tag Development Tool

Credit card form factor

Charging capacitor

RF Powerharvester

915MHz Power Antenna

Programming interface

Silicon Labs Wireless MCU

915MHz Data Antenna

POWERCAST

www.powercastco.com
©2012 Powercast Corporation

17

http://www.powercastco.com/uhf-rfid-sensing-passive-rfid-wireless-sensor-tags/

Battery-less Wireless Terminals

- Most of our work in this direction was towards battery-less terminals
- Long life terminals without wiring
- These are useful when
  - Terminals are embedded within structures (or body)
  - Devices to be deployed in hostile environments
  - Use of battery is not allowed (potential cause for explosion)
- Other factors
  - Cost, weight, etc.
- Primary focus: use of radio frequencies (ambient/intentional)

Ambient RF Sources

- Several sources:
  - WiFi Access points (mW) [2.4/.6GHz]
  - Cellular Tower (W) [900/1800 MHz]
  - TV Broadcast (MW) [150-450MHz]
  - FM broadcast (kW) [90-108MHz]
  - AM Radio broadcast (kW) [<1MHz]



Agilent Technologies: N9912A, SN: MY50022563

75% Thu, 22 May 2014 3:55:47 PM

Ref 0.00 dBm Atten 10 dB

M1: 92.090 MHz -18.58 dBm

Start 2.000000 MHz Stop 200.0000 MHz

Res BW 1.000 MHz VBW 1.000 MHz Swp 88.00 ms (401 pts)

- In general
  - Lower frequencies help non-line-of sight propagation
  - Power availability from ambient sources is limited and varies from place to place.

- Note
  - Unlike other sources, most practical RF harvesters (eg in RF ID) depend on **intentionally generated energy**.
  - This is called **wireless power transfer (WPT)** in the conventional RF/Microwave parlance.

Wireless Communication System

- Power transfer scheme is no different!!



Antenna Gain

Free space Loss

Antenna Gain

Antenna

Channel

Antenna

Amplifier Gain

Additive Noise

Attenuation

Additive Noise

Receiver Gain

Fading

Transmitter

Receiver

Antenna Fundamentals: Directivity

This is the ratio of the radiation intensity ***in a given direction*** *to the radiation intensity averaged over all direction*

Average radiation intensity, $U_0 = \dfrac{P_{rad}}{4\pi}$

Directivity,

$$D(\theta,\phi) = \frac{U(\theta,\phi)}{U_0} = \frac{4\pi U(\theta,\phi)}{P_{rad}}$$

- If direction is not specified, it implies the direction of maximum radiation intensity

$$D_{\max} = \frac{4\pi U_{\max}}{P_{rad}} \qquad D_{dB} = 10\log D$$

Maximum directivity and Maximum effective area

The radiated power density by a transmitter at a distance R

$$W_t = \frac{P_t D_t}{4\pi R^2}$$


A_t, D_t
Direction of propagation
R
A_r, D_r
Transmitter
Receiver

Power received

$$P_r = W_t . A_r = \frac{P_t D_t A_r}{4\pi R^2}$$

$$or,\ D_t . A_r = \frac{P_r}{P_t} . 4\pi R^2$$

By reversing the transmission direction

$$D_r A_t = \frac{P_r}{P_t} \cdot 4\pi R^2$$

$$\therefore \frac{D_t}{A_t} = \frac{D_r}{A_r}$$

this can be generalized by

$$\frac{D_1}{A_1} = \frac{D_2}{A_2} = k = \frac{4\pi}{\lambda^2}$$

$$if,\ D_0 = \text{max. directivity}$$

$$A_{em} = \text{max. effective area}$$

$$D = \frac{4\pi A_{em}}{\lambda^2}$$

Frii's Transmission Equation



- The radiation intensity for an isotropic radiator is $W_0 = \frac{P_t}{4\pi R^2}$
- For an antenna of gain G_t (or directivity D_t)

$$W_t = \frac{P_t G_t(\theta_t,\phi_t)}{4\pi R^2} = e_t \frac{P_t D_t(\theta_t,\phi_t)}{4\pi R^2}$$

- The effective aperture of a receiving antenna is given by $A_r = e_r D_r(\theta_r, \phi_r)\frac{\lambda^2}{4\pi}$
- Therefore,

$$P_r = e_r D_r(\theta_r, \phi_r)\frac{\lambda^2}{4\pi} W_t = e_t\, e_r D_t(\theta_t, \phi_t) D_r(\theta_r, \phi_r)\frac{\lambda^2}{(4\pi R)^2}\,|\hat{\boldsymbol{\rho}}_t \cdot \hat{\boldsymbol{\rho}}_r|^2$$

$$\frac{P_r}{P_t} = e_t e_r D_t(\theta_t, \phi_t) D_r(\theta_r, \phi_r)\frac{\lambda^2}{(4\pi R)^2}\,|\hat{\boldsymbol{\rho}}_t \cdot \hat{\boldsymbol{\rho}}_r|^2$$

$$\frac{P_r}{P_t} = e_{cdt} e_{cdr}(1 - |\Gamma_t|^2)(1 - |\Gamma_r|^2) D_t(\theta_t, \phi_t) D_r(\theta_r, \phi_r)\frac{\lambda^2}{(4\pi R)^2}\,|\hat{\boldsymbol{\rho}}_t \cdot \hat{\boldsymbol{\rho}}_r|^2$$

- When the antennas are pointing towards each others' peak radiation direction,

$$\frac{P_r}{P_t} = G_{0t} G_{0r}\left(\frac{\lambda}{4\pi R}\right)^2$$

Note that includes a loss factor (usually called **Free space Loss factor)**
Does not include dissipation/attenuation in medium; caused by spreading

Some numbers on Radiative form of WPT…

- Practical systems will have
  - Operational frequencies in ISM bands.
  - Most terminals are compact.
  - Antenna efficiency is compromised.
  - Nearly isotropic radiations expected.

- Main bottleneck is the physical limits in transmission.

$$P_r = P_t{*}G_t{*}G_r{*}(\lambda/4\pi r)^2$$

  - At 1 GHz (λ=30cm) r=1m; Antenna gain @0dBm, free space loss factor is about **0.06%**
  - Even with a moderate gain transmitter antenna (6dBi) power received @1m for 1W transmission, is just 2mW.
    - Drops to 23µW at 10m !!
    - **The voltage of the signal is low!!**
- In radiative power transfer, Distance from transmitter is a major concern.

Some questions addressed in our work

- **Harvesting of ambient radiations or Radiative transfer of energy addressed**
  - Is it possible to harvest the RF energy from base stations
  - Are there other viable sources of RF energy
- Can low power communication systems be designed to operate entirely from harvested energy
  - Integrate sensors, control, etc
- Can we use RF EH/ WPT to increase the range of backscatter communication (RFID scenario)

Design of Rectifiers

Required for converting incoming RF into DC power.

The challenge lies in maximizing the power conversion efficiency for low input power and minimizing the dimensions.

- RF to DC conversion by rectification of the incident RF signal by a ***Schottky diode***
  - Most diodes have a finite cut-in voltage
  - Diode is a non-linear device (performance depends on current or load)
  - Impedance matching required between antenna and diode
  - In most cases, the input voltage needs to be boosted


RF in
Antenna
Impedance matching network
Rectifier
Load

Conceptual diode based Rectenna


C_1
D_1
C_2
Z_L
V_{DC}
D_2

Voltage doubler

Voltage magnification in Matching circuit

- Matching circuit is required to provide impedance match between antennas (50Ω typical) to diode terminated with high impedance load (capacitor and/or high R in parallel).
  - LC matching networks provide voltage magnification.
  - This helps the diode conduct a good fraction of half cycle.
- The higher the voltage across the diodes, the more efficient the rectifier gets.
  - In practice Q is limited
  - Applications requiring higher voltages, a voltage multiplier configuration is used.



$$V_C = V_{in} \times \frac{\frac{1}{j\omega C}}{R + j\omega L + \frac{1}{j\omega C}}$$

At resonance,

$$V_C = V_{in} \times \frac{1}{j\omega_0 CR} = -jQV_{in}$$

Tuned Rectifier at RF

- A tuned rectifier implemented using discrete components



P_in→	**-10dBm**	**-13dBm**	**-16dBm**	**-20dBm**	**-25dBm**
Freq. ↓					
930MHz	917mV	664mV	469mV	281mV	131mV
945MHz	1016mV	736mV	515mV	300mV	132mV
955MHz	1038mV	747mV	513mV	289mV	122mV
960MHz	1032mV	736mV	499mV	276mV	114mV
Peak efficiency	51%	47%	39%	33%	20%

K. J. Vinoy, T. V. Prabhakar, A Universal Energy Harvesting Scheme for Operating Low-Power Wireless Sensor Nodes Using Multiple Energy Resources, pp. 453-466, Micro and Smart Devices and Systems, Springer 2014.

Typical Performance of Rectifier







RF-DC Conversion efficiency depends on various conditions

Rectifier Circuit using 4 diodes


Rectified
Output
L=65nH
RF in
Txn line
sections

Power level (dBm)	Charging time (ms)	Efficiency (%)
0	40	64.11
-2	55	63.77
-3	67.5	63.5
-5	90	63
-7	230	59.89
-10	370	56.78
-12	500	53.89
-15	900	45
-18	2000	20.56

K. J. Vinoy, T. V. Prabhakar, A Universal Energy Harvesting Scheme for Operating Low-Power Wireless Sensor Nodes Using Multiple Energy Resources, pp. 453-466, Micro and Smart Devices and Systems, Springer 2014.

Aditya Mitra, Chaithanya (2011-12)

1: Scavenging Mobile Tower Radiations


High gain antenna for RF power
Tuned Rectifier
Supercap
1st Stage Power gating
2nd Stage Power gating
Boost Converter Circuit
Low-leakage capacitor
V_{out}
Antenna for Wireless
Microcontroller with Wireless Radio Converter Circuit

G. Singh, R. Ponnaganti, T. V. Prabhakar, and **K.J. Vinoy**, “A tuned rectifier for RF energy harvesting from ambient radiations,” Int. J. Electronics & Communications, vol. 67, no. 7, pp. 564-569, July 2013

Gaurav Singh, Rahul P (2010-11)


3.15
DT-5205B

Gaurav Singh, Rahul P (2010-11)

Characterization in Lab

- Using various antennas


Network Analyzer
Device under test
Transmitting Antenna
Receiving Antenna

Distance from Transmitter [m]	1.5	2	2.5	3
Power received by dipole antenna [dBm]	-20.5	-22.1	-23.9	-25.2
Calculated power density [uW/cm^2]	0.078	0.055	0.035	0.03
Power received by patch antenna [dBm]	-15.1	-16.1	-17.6	-19.2
Transmit interval [mm:ss]	07:26	12:13	25:00	never
Power received by biquad antenna [dBm]	-11.8	-13.2	-14.9	-15.9
Transmit interval [mm:ss]	02:20	03:25	7:10	10:33

G. Singh, R. Ponnaganti, T. V. Prabhakar, and **K.J. Vinoy**, "A tuned rectifier for RF energy harvesting from ambient radiations," Int. J. Electronics & Communications, vol. 67, no. 7, pp. 564-569, July 2013

Gaurav Singh, Rahul P (2010-11)

Incident power above -18dBm required for operation

2. Universal Energy Harvesting Platform


Antenna for
wireless module
Harvesting
Antenna 1
Tuned
Rectifier
Storage
Switching
Network
RF
Transceiver
Solar panel
Storage
Micro
controller
Thermo-
electric generator
Storage
DC-DC Boost
Converter
Sensor
Rectifier +
Voltage
Doubler
Storage
DC-DC Boost
Converter
Rechargeable
Battery
Harvesting
Antenna 2

Only a small thin film battery is used

UEHP: Performance with different sources

Solar		**RF**		**TEG**	
Light Intensity (Lux)	Duty Cycle of operation (s)	Power Level (dBm)	Duty Cycle of Operation (s)	Temperature Differential (^oC)	Duty Cycle of Operation (s)
1000	7	0	3	55	9
300	11	-5	6	45	13
200	**20**	**-7**	20	35	240
100	42	-10	50	-	-
-	-	-12	240	-	-

An incident RF power of -7dBm (~0.2mW) performs similarly as at low light PV.

An appropriately oriented 20mW source with a high gain antenna (~10dB) can reach this RF power at a low gain rectenna (eg using PIFA) at 1 m distance.
Power levels within emission guidelines…

K. J. Vinoy, T. V. Prabhakar, A Universal Energy Harvesting Scheme for Operating Low-Power Wireless Sensor Nodes Using Multiple Energy Resources, pp. 453-466, Micro and Smart Devices and Systems, Springer 2014.

Aditya Mitra, Chaithanya (2011-12)

Other Possibilities using Wireless Power Transfer

- Power transfer by radiation is not efficient
- Waveguiding systems can ensure better transmission of power
  - Loss in waveguide is a small fraction of a dB/m (~0.2dB/m)
  - Metal ducts may carry higher order modes with higher losses
  - Extended to conducting ducts, Tunnels, mine shafts etc with some compromise
- Other possibilities
  - Surface wave
  - Focusing of fields

- Empty enclosures with metallic walls
  - Containers, tanks, airplane cabin, trains, etc
  - Other objects in the path may reduce the efficiency!

3: Antenna for RFID sensors

- Work involved design of antenna for RF harvesting sensors
  - These fuel level sensors to be deployed in a fuel tank of aircrft.
  - Optimization of design should focus on efficiency
  - High gain or directivity is not required.

- EH platform to be used with RFID sensors deployed inside fuel tank

- Requirements/Assumptions:
  - Incident energy is of random polarity and direction.
  - Operating frequency is 902MHz-928MHz.
  - Antenna must operate in air (relative permittivity = 1) and fluid (relative permittivity = 2.1)
  - Dimensions of planar antenna board:
    - Target dimensions: 3 in. x 2 in.
    - Maximum dimensions: 6 in. x 4 in.

Antenna Design dimensions


Ground Plane
Coaxial Feed


85 mm
Coaxial Feed
Ground plane
Shorting Strip
10.3 mm
Patch
61 mm


Patch
Rohacell


85 mm
Feed
43 mm
Ground plane
Patch
38 mm
45 mm
61 mm

Vivekanand M, Harikiran M

Measurements at Boeing (Nov 2013)


RF-DC Converter
PIFA in container
reader antenna


PIFA in container
reader antenna

Copyright © 2013 Boeing. All rights reserved.

After Integrating with Sensor and RFID board;

Measured in a room and reverberation chamber

Resolution of fluid height measurement to within 0.25”.
1W maximum transmit power.
Uses a modified reader protocol.

A. Robb, J. Bommer, R. Martinez, J. Harrigan, S. Ramamurthy , H. Muniganti, V. Mannangi, and KJ Vinoy, “Wireless Aircraft Fuel Quantity Indication System,” 2014 IEEE Sensors Applications Symposium - , Feb 18-20, 2014, Queenstown, Newzealand.

4. RFID Integrated with Sensor



Harvesting Antenna (PIFA / Monopole)

Tag Antenna and MONZA-X2K (Meander Line)

RF-DC

Lumped Element Based Matching Circuit

Two Stage Dickson Voltage Multiplier

Power regulation and supervisory

DC-DC Converter (BQ 25504)

Power Gating MOSFET

LDO

Digital Section

Microcontroller (PIC 16F1823)

Sensors (Light, Temperature, Accelerometer)

I2C bus network and pullup resistors

Parts of Fabricated System



PIFA CONNECTED SENSING TAG



20.83 ohm discrete port

Lumped element of 181.39 value at 865/905 MHz (working frequency)



RFID Tag Antenna

Data processing Circuitry

DC-DC Boost Converter

RF-DC Conversion

Sandeep Rana 2014-15

Sandeep Rana, TV Prabhakar, KJ Vinoy, An Efficient Architecture for Battery-less Terminals for Internet of Things, Applied Computational Electromagnetic Conference, Guwahati, Dec 28-21, 2015

Characterization of Performance

Source	Power
RFID Reader	30 dbm
Circularly polarized antenna	8 dbi
Polarization loss	3 dbi
Monopole Antenna	5 dbi
PIFA antenna	1 dbi
Meander Antenna	0.4 dbi

Tag Antenna	EIRP (dbm) + Gr	Rg Expected (-10 dbm) and 50 % overall efficiency	Range Achieved
Monopole	40	7.5 mtr	7 mtr
PIFA	36	5 mtr	5.5 mtr
Meander Line	35.4	4.5 mtr	4.5 mtr

$\lambda = 34.5\ cm$

$\text{Prx} = \text{EIRP} * \text{Gr} * \left(\frac{\lambda}{4 * \pi * r}\right)^2$

Efficiency worked out for -10 dbm
RF-DC efficiency – 20 % and DC-DC efficiency – 80%
Overall efficiency – 16%

Sandeep Rana 2014-15

5. Harvesting at 2.4GHz







RICOH
imagine. change.

Comparison of Efficiencies

Schottky diode

	900MHz	2400MHz
-15dbm	Efficiency=47% Output voltage=0.29V Load resistor=6K	Efficiency =17% Output voltage=0.2V Load resistor=6K
-20dbm	Efficiency=31% Output voltage=0.15V Load resistor=6K	Efficiency=5% Output voltage=0.1V (0.153V unloaded) Load resistor=6K
	Used HSMS 2852	Used HSMS 2862

Diode connected MOS with high Q matching

	900MHz	2400MHz
-14dbm	Efficiency=6.2% Output voltage=1.1V Load resistor=500K	Efficiency=2% Output voltage=0.632V Load resistor=500K
-20dbm	Efficiency=1.8% Output voltage=0.3V Load resistor=500K	Efficiency=0.2% Output voltage=0.118V Load resistor=500K

Zero V_{TH} CMOS

	900MHz	2400MHz
-15dbm	Efficiency=4.6% Output voltage=0.86V Load resistor=500K	Efficiency=3.79% Output voltage=0.774V Load resistor=500K
-25dbm	Efficiency=2.4% Output voltage=0.198V Load resistor=500K	Efficiency=1.7% Output voltage=0.165V Load resistor=500K

← Power

← Technologies

Frequencies →

Cross-coupled Rectifiers for Low Power

- CMoS integration requires diodes using MoSFETs.
- Simple diode connected configurations are not effective at low power/voltage levels
- In Cross Coupled Rectifiers
  - Biasing of MOSFETs by charge stored in capacitors. This is a way of threshold compensation.
  - Low ON resistance due to high overdrive voltage.
  - In both cycles of input, output capacitor is charged. Although DCP uses both cycles, only alternate cycles charges the output capacitor and the other cycle charges the input capacitor.



DC-DC converter

- Low loss switched capacitor DC-DC converter:


V_{in}=0.5V
SC doubler
SC doubler
SC doubler
SC doubler
V_{out}=2V
Ring oscillator
Non-overlapping clock
Driver
DC-DC block

Full system block diagram


-20dBm
2.4GHz
Matching circuit
Rectifier
V_{in}=0.5V
RF-DC block
SC doubler
SC doubler
SC doubler
SC doubler
V_{out}=2V
Ring oscillator
Non-overlapping clock
Driver
DC-DC block

1. Output capacitor of RF-DC supplies DC-DC
2. Enable generator logic constructed using back to back inverters
3. 5 MOSFETs added to limit supply voltage to ring oscillator

RICOH
imagine. change.

Sanjeev K, Manjunath M, TV Prabhakar, KJ Vinoy, Some Practical Considerations of RF to DC Converter using Low Vth CMOS Rectifier, Applied Computational Electromagnetic Conference, Guwahati, Dec 28-21, 2015

Full system simulations

- Output capacitor of RF-DC loaded heavily when clocks transition, so ripples exist in RF-DC output.
- Below 0.5V at clock transitions, above 0.5V between clock transitions
- Time step is 8ps for RF-DC simulation and DC-DC has to run for hundreds of µs or few ms, so simulations times are large.

Output voltage=2V across a load of 1.6MΩ, which gives

$$Efficiency = \frac{2^2/1.6\times10^6}{10^{-5}} = 25\%$$



Summary with IC Design

- Low Vth NMOS based DCP gives 42.3% efficiency.
- FGCCR gives 55% efficiency.
- The overall system efficiency is 25%.
- Higher than efficiency reported in literature for RF-DC converter operating at -20dBm, 2.4GHz in 130nm technology.

Reference	This work	[5]	[7]	[6]
Power level	-20dBm	-25.7dBm	-22.6dB	-20dBm
Frequency	2.4GHz	2.45GHz	906MHz	2.4GHz
Efficiency	55%(simulated)	37%(measured)	10%(measured)	36%(simulated)
Rectifier	FGCCR in UMC 130nm CMOS	DCP in 0.5µm Silicon on Sapphire	DCP with floating gate transistors in 0.25µm CMOS	FGCCR in 130nm CMOS

6. ASIC Design for IOT

- Working on a 3-chip architecture
  - Our chip to enable sensing, and control functions
  - Communication using an external Monza chip
- Fabricated chip using commercial services!!




Capacitor
ON-Chip
Matching Circuit
RF-DC
5-Stage DC-DC
Voltage Limiter
POR
Switch
Clock Generator
PnO Controller
Monza
SCL
SDA
I2C Master Module
Intermediate Register
ADC
Sensor
Power Lines
Signal Lines
Clock Lines

Battery-less Sensor node for BLE


868MHz
Q.W. Match
RFEH Chip
①
LDO (TPS 780)
Capacitor Bank
②
BLE Packet
SimpleLink™ Ultra-low Power CC2650 Wireless MCU
Texas Instruments
Sensor (LMT84)
③

① Energy Harvesting Block ② Energy Storing Block ③ Sensing & Communication Block


ANTENNA
QW Transformer MATCH
TI CC2650
BLE CHIP ANTENNA
CHIP On SBT4022 QFN IC HOLDER
CERAMIC CAP BANK 1.88mF
30 °C

Distance from Reader (m)	Input Power (dBm)	Cold Start Time (min)	Packet Time (min)	Efficiency (%)
3	-2	15	1.75	2.2
4	-5	35	7	1.7
5	-8	120	32	1

Eficiency(%) vs Load (5stage DC-DC)





Bharat Hegde & Syed Younis 2015-16

Summary

- Most low power wireless terminals operate intermittently
- These require anywhere 50uW to about 10mW for their operation.
  - Batteries limited: cost, size, stored energy
  - Solar: not dependable through

- WPT and RF EH can enable wide use of IoT
  - Main challenges in the design is the low incident energy/power/voltage
  - High Quality factor components may help

- Several fabricated examples discussed here: All can transmit data to an aggregator wirelessly
  - Different standards implemented.

Acknowledgements

- Dr. TV Prabhakar, DESE, IISc
  - Gaurav Singh
  - Rahul P
  - Chaithanya C
  - Aditya Mitra
  - Prashuk Jain
  - Prashanth Raja
  - Nirmal John
  - Nithin Jose
  - Syed Younis
  - Bharat Hegde
  - Niharika Thakuria
- Prof Bharadwaj Amrutur
  - Uday S
  - NS Sreeram
- Others
  - Vivekanand M
  - Harikiran M
  - Manjunath M
  - Sanjeev K
  - Sandeep Rana
- Partial Funding From
  - ANRC (Boeing, Wipro, HCL)
  - Ricoh Research, India

Thank YOU

Take the world on line
Take control of the world
Let the things talk to each other
Let things become intelligent

Free Energy From Air Circuit


(c) VoltsXAmps.com
(+)
(−)
ground Connection
Antenna


(c) VoltsXAmps.com
(+)
(−)

Last year I found a United States Patent that showed how to collect ambient energy right from the air. I finally decided to build this curcuit just to see what it could do.

[protected]

The above images are from the circuit I built. Most of the text and info comes direct from the US4628299filed by Joseph Tate. US4628299

The Amazing Ambient Power Module

Parts List for the APM-2

Four 1N34 germanium diodes (Radio shack #276-1123) ~ Figure 1, X1, X2, X3, & X4
Two 0.2 mfd 50 V ceramic capacitors ~ Figure 1, C1 & C2
Two 100 mfd 50V electrolytic capacitors (Radio Shack #272-1016) ~ Figure 1, C3 & C4
Copper wire for antenna & ground connections

Introduction

The Ambient Power Module (APM) is a simple electronic circuit which, when connected to antenna and earth ground, will deliver low voltage up to several milliwatts. The amount of voltage and power will be determined by local radio noise levels and antenna dimensions

Generally a long wire antenna about 100' long and elevated in a horizontal position about 30' above ground works best. A longer antenna may be required in some locations. Any type copper wire, insulated or not, may be used for the antenna. More details about the antenna and ground will be discussed further on.

The actual circuit consists of two oppositely polarized voltage doublers (Figure 1). The DC output of each doubler is connected in series with the other to maximize voltage without using transformers. Single voltage doublers were often found in older TV sets for converting 120 VAC to 240 VDC. In the TV circuit the operating frequency is 60 Hz.

FIG. 1

APM-2 SCHEMATIC DIAGRAM



The APM operates at radio frequencies, receiving most of its power from below 1 MHz. The basic circuit may be combined with a variety of voltage regulation schemes, some of which are shown in Figure 2. Using the APM-2 to charge small NiCad batteries provides effective voltage regulation as well as convenient electrical storage. This is accomplished by connecting the APM-2 as shown in Figure 2B.



Charging lead acid batteries is not practical because their internal leakage is too high for the APM to keep up with. Similarly, this system will not provide enough power for incandescent lights except in areas of very high radio noise.

It can be used to power small electronic devices with CMOS circuitry, like clocks and calculators. Smoke alarms and low voltage LEDs also can be powered by the APM.

Figure 3 is a characteristic APM power curve measured using various loads from 0-19 kOhm. This unit was operating from a 100' horizontal wire about 25' high in Sausalito CA. As can be seen from the plot, power drops rapidly as the load resistance decrease from 2 kOhm. This means that low voltage, high impedance devices, like digital clocks, calculators and smoke alarms are the most likely applications for this power source. Some applications are shown in Figures 4 through 7.

FIG. 3 AMP Power Envelope

Volts vs. Resistance



Figure 4 ~ A digital clock is shown powered by the APM-2. The 1.5 volt clock draws 28 microamps. Its position on the power envelope curve would be off the scale to the right and almost on the bottom line, dissipating only 42 microwatts.

FIG. 4 Clock powered by APM



FIG. 5 APM charging a battery



Figure 6 shows a clock which has the APM-2 built into it so it is only necessary to connect the antenna and ground wires directly to the clock. The antenna for this clock, which is a low frequency marine type, is shown in Figure 7.These antenna are expensive, not generally available, and usually don't work any better than the long wire mentioned above. But it may be necessary to use them in urban areas where space is limited and radio noise is high.

FIG. 6



Building the Module

The builder has a choice of wiring techniques which may be used to construct the module. It may be hand wired onto a terminal strip, laid out on a bread board, experiment board, or printed circuit. Figure 8 shows some of the different ways of constructing the APM-2.

Figure 8A is constructed on a screw strip terminal; Figure 8B is constructed on a perforated breadboard; Figure 8C is built on a standard experiment board; Figures 8D, 8E, and 8F are all printed circuits; Figure 8F is made up on a solder strip terminal.

FIG. 8 a, b, c, d, e, f & g



If you wish to make only one or two units, hand wiring will be most practical, either on a terminal strip or breadboard. Assembly on the terminal strip (Figure 8A) can be done easily and without soldering. It is important to get the polarity correct on the electrolytic capacitor. The arrow printed on the side of the capacitor points to negative.

Figure 9 is a closer view of the terminal strip with an illustration of the components and how they are connected.



The breadboard unit is shown in Figure 10 with all components on one side and all connections on the other. All you need is a 2" x 2" piece of perforated breadboard (Radio Shack #276-1395) and the components on the parts list. Push component wires through the holes and twist them together on the other side. Just follow the pattern in the photo, making sure to observe the correct polarity on the electrolytic capacitors and the diodes. The ceramic capacitors may be inserted in either direction.



The experiment board unit is assembled by simply pushing the component leads into the board as shown in Figure 11. This unit is powering a small red LED indicated by the arrow.

FIG. 11 EXPERIMENT BOARD



The solder strip unit is made up on a five terminal strip. The antenna connection is made to the twisted ends of the ceramic capacitors. When soldering the leads of the 1N34 diodes, care must be taken to avoid overheating. Clip a heat sink onto the lead between the diode and the terminal as shown in Figure 12.

FIG. 12 SOLDER STRIP UNIT



FIG. 13


Patent Pending
hi
low
+
-

Figure 14 shows the front and back view of the completed printed circuit.


Ground
Antenna
+
-

A small switch may be installed on the board to activate the zener regulator (Figure 15). This board was designed for use in clocks.

FIG. 15



Antenna Requirements

The antenna needs to be of sufficient size to supply the APM with enough RF current to cause conduction in the germanium diodes and charge the ground coupling capacitors. It has been found that a long horizontal wire works best. It will work better when raised higher. Usually 20-30 feet is required. Lower elevations will work, but a longer wire may be necessary.

In most location, possible supporting structures already exist. The wire may be stretched between the top of a building and some nearby tree or telephone pole. If live wires are present on the building or pole, care should be taken to keep your antenna and body well clear of these hazards.

To mount the wire, standard commercial insulators may be sued as well as homemade devices. Plastic pipe makes an excellent antenna insulator. Synthetic rope also works very well, and has the advantage of being secured simply by tying a knot. It is convenient to mount a pulley at some elevated point so the antenna wire may be pulled up to it using the rope which doubles as an insulator (Figure 16).



Figure 17 is an illustration of a horizontal wire antenna using a building and tree for supports.

FIG. 17

Horizontal Wire Installation



Grounding

Usually a good ground can be established by connecting a wire to the water or gas pipes of a building. Solder or screw the wire to the APM-2 ground terminal. In buildings with plastic pipes or joints, some other hookup must be used. A metal rod or pipe may be driven into the ground in a shady location where the earth usually is damper. Special copper coated steel rods are made for grounds which have the advantage of good bonding to copper wire. A ground of this type usually is found within the electrical system of most buildings.

Conduit is a convenient ground provided that the conduit is properly grounded. This may be checked with an ohmmeter by testing continuity between the conduit and system ground (ground rod). Just as with the antenna, keep the ground wire away form the hot wires. The APM's ground wire may pass through conduit with other wires but should only be installed by qualified personnel.

Grounding in extremely dry ground can be enhanced by burying some salts around the rod. The slats will increase the conductivity of the ground and also help retain water. More information on this subject may be found in an antenna handbook.

Good luck getting your Ambient Power Module working. It is our hope that experimenters will find new applications and improve the power capabilities of the APM.

CopyRight Joseph Tate

Inventors: Tate, Joseph B. (Sausalito, CA)
Brown, David E. (Mill Valley, CA)

Application Number: 06/695632

Publication Date: 12/09/1986

Filing Date: 01/28/1985 NOTE: The images maybe hard to see as they were originally scanned and uploaded in black and white. If it helps you to replicate this device you may want to check the images of the one I built at the very top (in color) Here are some more photos of my completed unit for your review.


(c) VoltsXAmps.com
OUTPUT TERMINALS
(+)
(−)
ground Connection
Antenna


(c) VoltsXAmps.com
(+)
(−)


(c) VoltsXAmps.com
(+)
(–)
ground Connection
Antenna


(c) VoltsXAmps.com
(+)
(–)
ground Connection
Antenna

[/protected]


Pizoelectric
Ear phone
Inductor
Germanium
Diode
Connect
Antenna
Here
To Ground
Connection
Variable
Capacitor

FM Crystal Radios?

copyright © 2006 by Larry J Solomon

I have heard, even from a physicist, that it is impossible to build FM crystal radios. On the other hand some experimenters claim that they have built them. This argument intrigued me to try and build an FM crystal radio, which I have done successfully. To my surprise, the result is an astounding performer, pulling in four local stations in Tucson. When connected as a receiver to a good sound system the sound fidelity is as good or better than more expensive AM radios. In fact, it sounds "high-fidelity".



This picture shows the Solomon FM Crystal Set in an acrylic display case. I made the set specifically to fit inside this case (the case came first).

My definition of a crystal radio is one that is not powered, except by the radio transmission itself and employs a crystal detector. So, it should work without any batteries or AC power. An FM crystal receiver must be able to detect and receive FM signals well enough to be heard in earphones without any such extra power.

This FM receiver is an amazing performer. It has crystal clear reception (pun intended), good sensitivity, but only fair selectivity. This set was a discovery for me. I started out by designing and building the normal AM sets. Then one day while testing the "Mystery" set (see my other web links), to my surprise, in addition to the expected panoply of AM stations, I heard a very faint signal that I could not tune out. At first, it seemed too weak to identify. When I tuned out all the AM stations, I was astonished to hear the announcement "KiiM FM, 99.5"! This is a

country music FM station here in Tucson. It was all over the dial, untunable, but the much louder AM signals masked it when they were tuned in.

I set myself the task of trying to improve the FM reception. I tried some simple circuit modifications that did not seem to improve anything. Then I connected a dipole antenna instead of the AM antenna I normally use. Suddenly, the FM signal was much clearer, although still weak. By using the audio output and sound system amplifier, I was even more amazed that four different FM stations came in loud (or rather medium) and clear. I found that changing the telescoping antenna length and position I could tune the stations in and out. They were KRQ, KLPX, KiiM, and KHYT all local FM stations with transmitters nearby. Their reception was also affected by the length and position of the audio output cable.

After doing some research, I discovered that there was a physical theory that claimed that FM reception was possible and even probable using the same circuit as an AM receiver. The theory is called "slope detection". So, I set out to find circuit improvements. A web search yielded little, mostly theory. But there was enough information that I thought I could make some modifications to the AM circuits to make them more tunable to FM signals and less tunable to AM. Since FM operates at higher frequencies, all I had to do, I thought, was make the coil and caps smaller. After much "tinkering" I arrived at the current circuit.

The circuit looks identical to a classic AM crystal circuit but is even simpler to build. The components were reduced in dimension to resonate at higher frequencies. This was done by experimenting with smaller and smaller coils and capacitors. The antenna is also much reduced in size (from that of AM) to resonate at higher frequencies (the antenna is crucial). The air variable capacitor I used has two trimmers in it which should be adjusted for best reception.I have found that a commonly available vernier dial and knob will fit the capacitor nicely. See end of article for a picture of the variable. C3 is a ceramic capacitor of 18 pf, but may be anywhere from 10 to 50pf. A detected FM signal is converted to AM due to an effect called slope detection that modulates amplitude.

This FM Crystal Set works best near the transmitter (I have not tested it beyond about 10 miles). Secondly, the sound level is quiet, especially without an amplifier. A quiet room is needed for listening with earphones. One must be willing to move the set around to find a location for the best reception of signals. However, in addition to listening with high impedance earphones (crystal or otherwise), the set can be connected directly to an audio amplifier's low level magnetic input which can then play amplified through a sound system at any volume -- sounds GREAT. In fact, I recommend starting tests with the FM crystal set by connecting it to the low-level phono inputs of a receiver or preamplifier. (Nowadays, many receivers don't even have a phono input!) That way you can crank up the volume, which makes it more likely to find the FM stations. If no signals are detected, I also recommend connecting an external "rabbit ear" antenna or hanging a short wire (12 inches or so) in various positions next to the internal antenna. The variable length of rabbitt ears can help to tune in stations.

No additional wiring or antenna is necessary (the antenna is optimized in length for FM.)



L - 4 turns #18 copper or silver wire, 12mm inside diameter, tapped at 2.5 turns
Ant - 7 inches of #18 bare copper wire
C1 - 18 pf ceramic capacitor
C2 - 50 pf air variable capacitor
D - 1N34 diode or rock crystal
R - 150K resistor

The diode is tapped directly to the antenna. The vernier dial fits directly on the tuning capacitor. The antenna parallels the perimeter of the acrylic face plate. "Military style" #18 AWG wiring is used without any insulation. It is important to keep the components physically close together. The component specifications are the same as in circuit #2. The coil is silver rather than copper, but copper does just as well. I think that the contrast of the silver and copper is beautiful. The coil was wrapped around a Sharpie Permanent Marker, then slipped off and expanded slightly. The wooden base is made from lacquered, polyurethane padouk.

I consider this set a work of art as well as science and think it is the most elegant crystal receiver I have created. I love the contrast of the silver coil, the copper antenna, the clear acrylic faceplate, the black vernier dial, the white and transparent variable capacitor, and the subtle colorings on the resistor, the diode, and the lucite base. Yet the circuit is so ridiculously simple that some will not believe it is possible without building it themselves. No shielding is necessary, and there is no problem with hand capacitance. However, the output cable position may affect reception sensitivity.

Photos of wired circuit



A hand is included in this photograph to show scale. Note the military style wiring, diode, and antenna. I wanted the wiring to create a modern design similar to a Mondrian painting. Not only is this set beautiful, it works! No power and no long antenna! It looks like a work of fiction.



Is this thing imaginary -- science fiction? Well, imagination did play a part, but it is definitely not science fiction. This shot shows the elegance of the FM set best, I think. There is only one resistor and one fixed capacitor.



The inside of the tuning capacitor and the phono jack/output can be seen here. Can you spot the fixed ceramic capacitor? Note the polished edge of the face plate and the reflection in the wooden base.



A quarter-inch piece of lucite was fitted under the tuning capacitor to anchor it. Note the two tiny trimmers on the back of the tuning capacitor. Brass screws were used to enhance appearance.



The vernier dial is large to accomodate ease of tuning, and the vernier makes it easy to separate stations. Two golden (brass) wood screws fix the face plate to the base. Holes for the face plate were made with special plastic drills, but ordinary drills may be used if drilled very SLOWLY. The knob is removable.

FM Crystal Circuit #2



L - 5 turns AWG#18 bare copper or silver wire, 12mm inside diameter, tapped at 2.5 turns
D - 1N34 or rock crystal diode
C1 - 82 pf capacitor
C2 - 80 pf air variable capacitor
C3 - 18 pf capacitor
R - 150K resistor

The following photographs show the circuit wired with the handmade Saturn Dial. and knob. It is perhaps not as visually striking as set No. 1, but it works just as well. In fact, this set was the original version. Notice that all the wiring and coil are copper.



The Saturn dial and knob were fashioned from a "doll's head" from Michael's Arts and Crafts, a piece of lucite cut with two circle cutters, and a brass paper fastener. The knob is fixed to the tuning capacitor with a small machine screw that fits in the hole below the brass fastener. The most difficult part of this was fashioning "Saturn's rings". This must be done very carefully and slowly. The inside edge should be cut slightly undersized and then sanded with a drum sander to fit snugly. The outside edges can be sanded with fine sandpaper and polished with a plastic polisher.





The air variable capacitor may be obtained from Electronix Express at http://www.elexp.com/. Part number 14VCRF10-280P. The 80 pf side is recommended for the second circuit, contacts 2-3. Contacts 1 and 3 were used for the first circuit (50pf).

- OSC: 5-59 pf
- ANT: 5-142 pf
- OSC and ANT Trimmer 10pf range

Home -- If you want to contact me go to the home page and go through the Music Clinic link.

life.augmented
INNOVATIVE
SEMICONDUCTOR
SOLUTIONS
Digi-Key
ELECTRONICS
Learn More

advertisement

FREE ENERGY FROM THIN AIR!

Technology (/technology/) > Science | by DrewPaulDesigns (/member/DrewPaulDesigns/) Follow

79,181 1,078 230

Posted May. 24, 2016 | BY-NC-SA

FREE ENERGY
FROM THIN AIR!
*INVOLVES CRYSTALS AND
DANGEROUS VOLTAGES!
Copyright 2016. Drew Paul Designs, All Rights Reserved

(https://cdn.instructables.com/FAT/74PB/IOKBVYWL/FAT74PBIOKBVYWL.LARGE.jpg)



(https://cdn.instructables.com/F5S/A5K4/IQKBUDZF/F5SA5K4IQ

"Dendera Light"
circa 1500 BC
Image: creative commons, Wikipedia

(https://cdn.instructables.com/FOH/L0OE/IQKBVTOS/



"Foxhole Radio"
circa 1940 AD
Image: creative commons, Wikipedia

(https://cdn.instructables.com/FGF/CJG9/IQKBVTOT

3.74
CEN-TECH

(https://cdn.instructables.com/FHS/HM1V/IQKBT6CY/FHSHM1V

"Free energy from the air?, Yea, right!" Sardonic skepticism was my first reaction to this unusual concept, as well.

Though, its not so far out there, in fact. Light can be converted to DC current with solar panels, electricity can be converted to magnetism as I did in my last article (https://www.instructables.com/id/DIY-Electro-Magnetic-Levitation/), in a microphone sound waves are converted to an electrical signal (by vibrating a magnet near a coil (http://hyperphysics.phy-astr.gsu.edu/hbase/audio/mic.html)), solar rays can even be focused and converted to heat in awesome devices like this! (http://www.gosunstove.com/) When we think about it, energy is all around us and can be harvested in an enumerable many of ways.

Today, we are going to take a rather novel approach. We are going to build a device specifically designed to sense and capture a particular band of energy which is all around us.

The earth is magnetic and anyone who has ever used a compass knows this. Magnetic bodies in motion produce electricity, we can see this in any alternator, like the one in your car. So, therefore the earth is electric as well as magnetic, by definition.

Can we detect this energy? Yes, we sure can! Ever turn on a radio in the middle of nowhere and heard static? That is your radio picking up naturally occurring energy in the RF spectrum!

Can we use this energy to do work? Absolutely! This has been known for a long time. Crystal radios (https://en.wikipedia.org/wiki/Crystal_radio) have been around since before the 1930's and can run with no input energy other than the radio signal. Even when completely isolated, but from the atmosphere, a crystal radio will produce a voltage in the earpiece resulting in a sound (albeit and undesirable one).

Well, this is where it gets interesting...

Can we replicate this effect? Yea, and with modern components like the high quality crystals found in germanium diodes, we can even increase efficiency. By applying this concept as a Crystal Energy Receiver we can take advantage of a wide range of energetic frequencies rather than tuning in to just one.

Can we scale it up? Definitely. Things like micro germanium diodes, high efficiency antennas and compact contemporary capacitors make the components that are required to build a crystal receiver fit in the palm of your hand. While there may or may not be a more efficient way, this renewable energy solution is simple to employ and can be scaled up, or down, indefinitely.

Download

It sounds like we can build a Crystal Energy Receiver. Let's give it a shot...

Add Tip Ask Question

Step 1: What You'll Need


ELECTRIC SOLDERING GUN
AC 120V~60Hz 100W
SOLDER WIRE
KAINA
0.8
CEN-TECH
DIGITAL MULTIMETER
OFF
ON
6485
A-529 X 100
68PF 50V
USA893

(https://cdn.instructables.com/F2J/FSP5/IOKBT2GI/F2JFSP5IOKBT2GI.LARGE.jpg)



(https://cdn.instructables.com/F53/FHGM/JOKBT2GV/F53F



(https://cdn.instructables.com/FP2/G266/JOKBT2GG/FP2G



(https://cdn.instructables.com/FXB/0HS

6485
A.529 X 100
682 50V

(https://cdn.instructables.com/FYS/DZC



(https://cdn.instructables.com/FIH/ESHF

Download


Chong
VEHT
-40+10
°C

(https://cdn.instructables.com/F46/39VU/IOKBT2GB/F4639VUIOKBT2GB.LARGE.jpg)



(https://cdn.instructables.com/FKY/5NKO/IOKRT2GU/FKY5NKOIOKRT2GU.LARGE.jpg)

One of the reasons this particular renewable energy harvesting method is so viable is the relatively few and easy to obtain materials required.

The simplest crystal receiver design needs no power and can be built with only three parts: a coil, a crystal and a resistor. We're going to optimize that design in order to produce a cleaner and more reliable output signal by first polarizing the input amplitude, then rectifying and filtering the signal. Then we'll add an antenna, case and connections.

Get the circuit diagram here (http://www.drewpauldesigns.com/crystal-energy-receiver-kit.html)
Get the kit here (http://www.drewpauldesigns.com/crystal-energy-receiver-kit.html)

Download

The parts for the circuit include:
(1) Circuit Board (http://www.drewpauldesigns.com/crystal-energy-receiver-kit.html)
(1) 10-18 gauge Copper Wire
(2-12+) Ceramic Capacitors (matched)
(2-6+) Electrolytic Capacitors (matched)
*note various types of capacitors can be used
(4) Germanium Crystal Diodes (1A+)

Total Unit Cost: +/- $0.40 (USD, scaled for volume of 1,000+ units)

In addition, you'll probably want to get:
(1) Project box (optional)
(1) Antenna (a loop antenna or elevated antenna is recommended and can be made with copper wire)

The tools you'll need are:
Soldering Iron/ Solder (optional)
Multimeter
Oscilloscope (http://www.seeedstudio.com/depot/DSO-Nano-v3-p-1358.html?cPath=63_65) (optional)

That's it. Yup, that's all. Once we've got it all, let's begin.

Add Tip Ask Question

Step 2: Build the Circuit

Download



(https://cdn.instructables.com/F4G/ZVIH/IOKBT2HA/F4GZVIHIOKBT2HA.LARGE.jpg)



antenna in
104
104
1N34A
1N34A
1N34A
1N34A
100uF 50V
100uF 50V
- +
- +
-
output
+
RF to DC
Circuit Diagam (simplified)
Component list:
(2) Ceramic Capacitors (104)
(4) Germanium Diodes (1N34A)
(2) Electrolytic Capacitors (100uF 50V)
Copyright 2016. Drew Paul Designs. All rights reserved.

(https://cdn.instructables.com/FAW/ARS2/IOKBUKAD/FAV



(https://cdn.instructables.com/FCY/PLZI/IOKBT2GW/FCYPI



(https://cdn.instructables.com/FRH/JS



(https://cdn.instructables.com/FL8/NBT



(https://cdn.instructables.com/FR4/H6T



(https://cdn.instructables.com/FN2/OSG1/IQKBT2H5/FN2OSG1IQKBT2H5.LARGE.jpg)



(https://cdn.instructables.com/F1J/MWCW/JOKBT2H6/F1J



(https://cdn.instructables.com/FUC/NIWJ/JOKBT2H7/FUCN



(https://cdn.instructables.com/FEH/U5BK/JOKBT2H8/FEHJ



(https://cdn.instructables.com/FTS/JEB3/JOKBUJGB/FTSJF

We're going to build the simplest version of this circuit variation in order to understand how each component interacts and as a proof of concept.

There are three simple systems at work in the circuit that are composed of capacitors, which store energy, and diodes that direct it.

Energy in the band of radio waves, among others, will vibrate a wire antenna on an atomic level, sending a discernible signal to its lead. This signal will then meet the junction between two ceramic capacitors wired in series. This junction will force positive charge from the wave to travel in one direction and negative charge in the other direction which, when collected again, makes the signal uniform and polar. Connecting the two capacitors in series creates leads on each end; the now positively charged side of one and the now negatively charged side of the other creates a two cell battery. Download

This next stage of the circuit takes a signal with a net value of zero, adds the absolute values of the positive and negative amplitudes with respect to the origin and produces a positive integer. This concept can be thought of as taking:

(+1) + (-1) + (+1) + (-1) = 0

and converting it to:

| [(+1) + (+1)] | = 2
+
| [(-1) + (-1)] | = 2
= 4

Isn't math fun?

To each of these leads from our two capacitors in series, we will connect two crystal diodes, one facing each direction, to form what is called a bridge rectifier. A bridge rectifier is a configuration which will convert an alternating current to a direct one by cleverly rerouting the signal.

By connecting the bridge rectifier as shown in the circuit diagram, this direct current from the diodes then charges the electrolytic capacitors. This stage normalizes the amplitude, making the current constant and usable.

Components can easily be twisted together for testing and then soldered to a circuit board to secure.

Add Tip Ask Question

Step 3: Test and Optimize Your Circuit

Download


0.05
CEN-TECH
DIGITAL MULTIMETER

(https://cdn.instructables.com/F08/BU3T/IOKBT2HJ/F08BU



(https://cdn.instructables.com/F17/0T0N/IOKBT2HK/F170T



(https://cdn.instructables.com/FUN/RM



(https://cdn.instructables.com/FKE/VX



(https://cdn.instructables.com/FFX/D6Z



(https://cdn.instructables.com/F9A/XB15/IOKBT4X3/F9AXB15IOKBT4X3.LARGE.jpg)

Download



(https://cdn.instructables.com/FOD/30OB/IQKBT4X6/FOD3



(https://cdn.instructables.com/F6T/0CF3/IQKBT4X7/F6T0C

To test and analyze our circuit, we'll be using a digital voltmeter and oscilloscope.

By connecting a voltmeter to the output, we'll immediately begin to see a small voltage climbing in the 10-100mV range. If not, we'll want to check our connections and make sure the circuit is not isolated from the environment by taking it outside to a clear area.

Then, by connecting an oscilloscope to the outside leads of our two ceramic capacitor bank, we will see the the polarized signal being captured from the air around us. We can then connect after the diodes to see our varying direct current and then to after the electrolytic capacitors to see a normalized, usable direct current at our output.

We can then optimize the input resistance in two ways. Firstly, we can add additional ceramic capacitors in parallel to our original two and make sure our soldered connections are consistent and thick in this area.

We can optimize the circuit's capacity by adding electrolytic capacitors in parallel to our original two which will allow this circuit to charge slightly when not in use. For this purpose, a charging circuit can also be added here in order to incorporate an optional battery bank.

We can optimize the antenna by attaching loops and coils of copper wire in various positions, store-bought antennas or by stringing some wire up to the highest point you can reach.

We don't have to stop there, either. We can now connect multiple circuits in series to increase voltage or in parallel to increase current. This can be done indefinitely.

Add Tip Ask Question

Step 4: Add a Case and Antenna



(https://cdn.instructables.com/FK6/6YAE/IQKBT4XC/FK66YAEIQKBT4XC.LARGE.jpg)

Download


(https://cdn.instructables.com/F63/OPPP/IQKBT4XA/F63O


(https://cdn.instructables.com/F9JW9R4/IQKBT4XD/F9JW

(https://cdn.instructables.com/F09/FS7

(https://cdn.instructables.com/F5Q/5N


(https://cdn.instructables.com/FJR/BKS



(https://cdn.instructables.com/FWV/YZHK/IOKBT4XL/FWVYZHKIOKBT4XL.LARGE.jpg)



(https://cdn.instructables.com/FTN/GNK

(https://cdn.instructables.com/FM8/8IE/

(https://cdn.instructables.com/FD9/OGS

After choosing an antenna in the last step we'll now want to permanently wire it. Whether you choose a compact antenna for portability or a tall fixed antenna for power and range, we will wire it in the same manner according to the diagram in the previous step. Note that the input on the configuration here is grounded to the metallic case, and thus the users hand, and incorporation of longer antennas will require proportionally more substantial grounding.

We will then attach a terminal to the output to allow us to connect this circuit to an electrical device or charging circuit and battery bank.

Next, we will add a case, making sure to isolate exposed leads with non-conductive material especially if mounting in a conductive case. A piece of cardboard secured with glue is sufficient for the circuit's bottom and shrink wrap or electrical tape can be used in the case of any additional exposed leads. Drill two holes in your enclosure, one for the antenna or antenna lead and another for your output terminals. You can then insert your components, fasten the enclosure and your device is ready to use!

Add Tip Ask Question

Step 5: Your Crystal Energy Receiver Is Complete!

Download



(https://cdn.instructables.com/FEC/D3WF/IOKBT69Y/FECD3WFIOKBT69Y.LARGE.jpg)



(https://cdn.instructables.com/FX4/8V5I/IOKBT4Y6/FX48V5



(https://cdn.instructables.com/FLD/DTVI/IOKBT4YC/FLDDT

Your Crystal Energy Receiver is now complete and ready to use!

I built a portable version, for proof of concept and demonstration purposes. However, you can go as big as you want- to passively charge batteries or run equipment remotely; or go as small as you want- to power sensors, RFID devices, small electronics and more.

I used this harvested energy to easily power a low-consumption quartz clock, a digital chronograph with integrated circuits and LCD and was even able to momentarily rotate a small dc motor.

Because of its simplicity this device is a durable, efficient and reasonably effective method of harvesting radiant energy in a simple, replicable and sustainable way. I humbly hope that the contributions made here, and by those reading, can be one day used by people worldwide to conveniently capture free energy.

Thanks for checking out my project and I look forward to seeing everyone's variations, suggestions and improvements!

Add Tip　Ask Question

advertisement


Want to work at a startup?

No resume needed. Just show us you can code.

TRIPLEBYTE


1N 34
Germanium Diode
IN34 or IN34A
+
−
ANODE
CATHODE
Red LED
+
−
A B C D E F G H I J
Aluminium Tube
copper
wire


16 cm length
aluminium
4mm thickness, 4cm width,
You can use electrolytic capacitor!
Germanium Diode
IN34 or IN34A
Aluminum electrolytic capacitors with non-solid electrolyte
Vertical-Chip (V-Chip)
Axial
Radial (single ended)
Snap-in

(https://cdn.instructables.com/F4X/V9F

1N 34
Germanium Diode
IN34 or IN34A

(https://cdn.instructables.com/FHD/RBY8/IIRBC73B/FHDR


+
−
ANODE
CATHODE

(https://cdn.instructables.com



(https://cdn.instructables.com/F9P



(https://cdn.instructables.com/FGF

advertisement

START NOW

3 Easy Steps:

1. Click 'Start Now'

2. Free Access
No Sign Up!

3. Get Free Download

HowToSuite

About This Instructable

2,351 views

46 favorites

License:

BY-NC-SA



(https://cdn.instructables.com/FEW/54KLU/IIRRC770/FEW54KLUIIRRC770.MEDIUM.jpg)



(https://cdn.instructables.com/FB2/K73U/IIRRC78S/FB2K73UI[illegible].MEDIUM.jpg)

How to Make a Electrostatic RF Detector or Ghost Detector, Hunting Solution. Much cheaper and easier than you may think For Under $5 ! A simple description is that IN34 or IN34A RF Germanium Diodes for Crystal Radio can take "Ambient" or "Radio Waves" to turns them into DC energy. I would like to show the Tesla Coil Transmitter, where I made an homemade "RF Detector" this is the simplest detector! without any batteries or hardships circuit, only with IN34 diodes and Ether to Earth!.. Stay Tuned and Enjoy! Please click the "like" button, subscribe my channel, and share this with your friends... To support my "work" every little bit helps! Watch the "ADS" THANKS

- See the original video https://www.youtube.com/watch?v=cSxqeGVC9t0

Step 1:

GEORGE CHANIOTAKIS (/member/GEORGE+CHA
(http://https://www.youtube.com/
Follow 84
(/member/GEORGE+CHANIOTAKIS/)

Bio: A big hello to all mankind! This is my channel I hope you can find here various interesting things on in Renewable Energy Technologies and ... More » (/member/GEORGE%20CHANIOTAKIS/)

More by GEORGE CHANIOTAKIS:

(/id/MAKE-PERMANENT-MAGNET-SYNCHRONOUS-MOTOR-GENERATOR/)

(/id/Make-Wind-Turbine/)

(/id/High-Voltage-Die/)

advertisement

You Should Never Shop On Amazon Without Using This Trick – Here's Why


LPF
Variable Gain and Attenuator
Attenuator
Mixer
LNA
I/Q Demod
ADC Driver
ADC
Tx/Rx Diplexer
RF Switch
Tunable Filter
PLL/VCO Divider Multiplier
Clock Distribution and Cleanup
Variable Gain and Attenuator
PA
Amp
I/Q Mod
DAC
Gain/Phase Adjust/Detect
RF Detector

Get Complete RFIC Guide

ANALOG DEVICES

Download all Analog Devices RFIC Parts for Each Component in RF Signal Chain.

Comments

We have a be nice comment policy.
Please be positive and constructive.

I Made it!   Add Images   Post Comment

LazaroG4 (/member/LazaroG4/) 2017-11-14 Reply

I can't download and I was doing it before. I now need to go premium. This why i do not give any of my own files for the idea i have posted for free on You Tube. sorry for the not using of file and I have integrity and will not copy and paste as many do for free.

More Comments

How to Make a Electrostatic RF Detector or Ghost Detector by

GEORGE CHANIOTAKIS (/member/GEORGE+CHANIOTAKIS/) in leds (/technology/leds/)



Download

(/id/How-to-Make-an-Electrostatic-RF-Detector-or-Ghost-D/) 11 Steps

+ Collection

I Made it!

♥ Favorite

Share

Newsletter

Let your inbox help you discover our best projects, classes, and contests. Instructables will help you learn how to make anything!

enter email | I'm in!

About Us

Who We Are (/about/)

Advertise (/advertise/)

Contact (/about/contact.jsp)

Jobs (/community/Positions-available-at-Instructables/)

Help (/id/how-to-write-a-great-instructable/)

Find Us

- Facebook (http://www.facebook.com/instructables)
- Youtube (http://www.youtube.com/user/instructablestv)
- Twitter (http://www.twitter.com/instructables)
- Pinterest (http://www.pinterest.com/instructables)
- Google+ (https://plus.google.com/+instructables)

Resources

For Teachers (/teachers/)

Residency Program (/pier9residency)

Gift Premium Account (/account/give?sourcea=footer)

Forums (/community/?categoryGroup=all&category=all)

Answers (/tag/type-question/?sort=RECENT)

Sitemap (/sitemap/)

advertisement

AdChoices



Terms of Service (http://usa.autodesk.com/adsk/servlet/item?siteID=123112&id=21959721) |
Privacy Statement (http://usa.autodesk.com/adsk/servlet/item?siteID=123112&id=21292079) |
Legal Notices & Trademarks (http://usa.autodesk.com/legal-notices-trademarks/) | Mobile Site (https://www.instructables.com)
(http://usa.autodesk.com/adsk/servlet/pc/index?id=20781545&siteID=123112)

© 2017 Autodesk, Inc.

Build a Homebrew Radio Telescope

Explore the basics of radio astronomy with this easy to construct telescope.

Mark Spencer, WA8SME

There are many ham radio related activities that provide a rich opportunity to explore and learn more about the science of radio. One of those opportunities is radio astronomy.

All matter emits radio frequency (RF) energy dependent on the temperature and makeup of the matter, including the matter in space. The foundation of radio astronomy is to study the heavens by collecting and analyzing the RF energy that is emitted by bodies in space, very much as optical astronomers use light energy collected by telescopes. It sounds complicated. While professionals use very sophisticated and expensive equipment, you can, with some simple equipment and a little investment, build a radio telescope that will allow you to learn and explore the fundamentals of radio astronomy.



Figure 1 — Radio telescope system based on TV dish antenna.

A Homemade Radio Telescope

In this article, I will build on an existing design of a radio telescope made from one of those ubiquitous TV dish antennas that you see around your neighborhood. The radio telescope (RT) project described here can easily be reproduced. Although this is not a fully capable RT, it can provide a wonderful learning opportunity for you, or perhaps students in your local school.

Figure 1 shows the radio telescope set up. The major components include a modified TV dish antenna mounted on a wooden support structure to allow pointing the antenna, a commercial satellite signal strength detector that displays the signal strength of signals collected by the dish on a meter and an interface that converts the signal strength into a amplitude modulated tone. The tone is fed into a computer sound card and finally a computer and software graphically displays the signal strength as a function of time.

The TV dish modifications are structural, and any available TV dish system can be used. The signal strength detector costs between $40 and $65 and is widely available from Web retailers. The interface circuit, which will be described shortly, is easily duplicated and costs approximately $20. Finally, the display software is free.



Figure 2 — Dual LNB mount. Note two coax connectors.



Figure 3 — Homemade plastic single LNB mounting bracket.

What it Can Do

The following is just a sample of what you can do with this simple RT:

- Use the sun to study and determine the beamwidth of the dish and verify the mathematic formula that is used to predict dish antenna performance.
- Measure the radiation intensity of the Sun and perhaps detect changes in solar activity.
- Measure the relative changes in the surface temperature of the moon.
- Learn about and explore a common radio astronomy collection technique called the *drift scan*.

From June 2009 QST © ARRL



Figure 4 — Dual coax connector configured LNB. Terminate one connector with a dummy load.


VOLTS
SIGNAL
Channel Master
Satellite Signal Level Meter
Model 1004IFD

Figure 5 — CM satellite signal strength meter.



Figure 6 — *SkyPipe* screen showing antenna response.

- Explore the fundamental principle of energy emission as a function of temperature by detecting the relative differences between the temperatures of emitting bodies.
- Detect satellites parked along the Clarke Belt in geosynchronous orbit and illustrate how crowded space has become.
- Detect the Earth's rotation around the Sun and the Earth's spin on its axis by comparing daily drift scans of the horizon.

Antenna Subsystem

The basic RT system is based on the "Itty-Bitty" design that is described in two Web pages.[1,2] The TV dish is an offset 18 inch dish that has down converter(s) mounted at the focal point of the dish. The down converter is called a low noise block (LNB). The LNB is a preamplifier/down converter that converts the satellite signals from around 12 GHz down to around 2.4 GHz. Most modern dishes have two or more LNBs to access more than one TV satellite at a time without changing the pointing of the dish (Figure 2). The LNBs are mounted to share the focal point of the dish. Since only one LNB is required for the RT, I made a minor adjustment to the published Itty-Bitty design to position the single LNB at the dish focal point. Mounting the single LNB at the focal point really helps in pointing the antenna.

I used the existing LNB housing and mounting bracket as a template to determine the distance between the edge of the mounting arm to the mounting hole of the LNB. I then used a piece of plastic to fabricate a new mounting bracket for the LNB as shown

[1] Notes appear on page 45.


+12 V
1 mH
Power to CM1001
via set Rx
800 Hz oscillator
amplitude set in step
with signal strength
7805
REG
Out
In
Gnd
7805
REG
In
Out
Gnd
Cx
0.1
Cx
0.1
Cx
0.1
Cx
0.1
1 k
0.001
2N3904
Decimal values of capacitance
are in microfarads (µF); others
are in picofarads (pF);
Resistances are in ohms;
k=1,000, M=1,000,000.
1/2 op-amp voltage
multiplier for
scaling of meter
voltage for ADC
18 k
18 k
0.1
0.047
0.022
0.022
1.8 k
To Meter +
10 k
0.1
50 k
1k
1 k
1 k
1 k
OutA
Vcc
−INA
OutB
CPA2340
+INA
−INB
GND
+INB
Vcc
GND
GP5
GP0
12F675
GP4
GP1
GP3
GP2
PIC programmed as
9-bit ADC
Vb
Vcc
H1
Sout
L1
W0
W1
H0
RST
L0
CLK
Cout
GND
DQ
DS1867-50
1 µF
+
to Computer
Sound Card
1/2 op-amp
unity gain buffer
to drive
CM1004 meter
to Meter
+ Line
Digital pot set by ADC
to 9-bit resolution -
controls oscillator
amplitude
QS0906-Spencer07

Figure 7 — RT Interface circuit diagram.

From June 2009 QST © ARRL



Figure 8 — RT Interface block diagram.



Figure 9 — Power and ground connection to CM board.

in Figure 3. The dimensions are not super critical, but careful placement certainly will improve the RT performance.

Some LNBs have two coax connectors. Only one will be used in the RT (Figure 4). It is a good idea to terminate the extra coax connector with a 75 Ω dummy load plug to balance the load on the LNB. The dummy loads for F type TV coax connectors are readily available from electronic parts retailers.

Note that the dish is mounted upside down. Though this orientation is not ideal for receiving satellite signals, this arrangement helps with pointing the dish in its radio telescope role.

Satellite Detector

The detector used in this project is the Channel Master (CM) satellite signal level meter model 1004IFD (Figure 5).[3] The CM is connected to the LNB. Power is supplied to the LNB through the coax connection from the CM. The CM detects the signal coming from the LNB and gives a meter indication of the signal strength and also varies the frequency of an audio tone to help technicians point the dish at the desired satellite. As you move the dish through the beam coming from the satellite, the meter indication will increase and then decrease coincident with the pitch of the audio tone.

The Itty-Bitty plans detail how to connect power to the CM and in turn connect power to the LNB (this power connection is handled by the interface in this project). Though somewhat effective, the CM meter and variable frequency tone indications provide limited utility in detecting changes in signal strengths required for radio astronomy.

Display

To really study the signals received by the RT, you will need to see them displayed graphically on a strip chart. There is an excellent software package called *Radio-SkyPipe* that is posted on radio astronomy Web sites.[4] The free version of this software is a good place to start. *SkyPipe* uses the computer sound card to measure the incoming signal strength and graphically displays the signal strength as a function of time. Figure 6 is illustrative of a signals detected by the RT. *SkyPipe* is very easy to use but some study of the HELP files will make it easier for you to fully tap into the capabilities of this software.

SkyPipe requires audio signals to be fed into the sound card MICROPHONE jack. The output of the CM detector is either an analog meter reading or a frequency modulated (constant amplitude) tone that is not really compatible with *SkyPipe*. An interface is required.

Interface

What is required to make the CM output work with *SkyPipe* and a sound card is to convert the signal level into an amplitude varying audio tone. The interface designed to do this is shown in Figure 7 and as a block diagram in Figure 8. Refer to the block diagram during the description of the interface function.

The unity-gain op-amp is used as a buffer between the CM meter driver circuit and the analog meter. The other op-amp is used as a voltage multiplier to scale the CM meter driver output voltage to match the 5 V reference voltage of the following analog to digital converter (ADC). The variable resistor in this voltage multiplier circuit is used to calibrate the CM to *SkyPipe*. The voltage from the multiplier is fed to a programmable interface controller (PIC) that is programmed as a 9-bit ADC to covert the analog voltage that is a function of received signal strength to a 9-bit digital word that is used to control a digitally controlled variable resistor. The interface includes a simple Twin-T audio oscillator circuit that provides a tone of approximately 800 Hz that is fed to the computer sound card. The amplitude of this audio oscillator is varied by the digital pot that is being controlled by the PIC. The result is the audio amplitude being varied in step with the signal strength detected by the CM.

The circuit provides power to the CM and the LNB. A 12 V source in the CM is tapped through an RF choke and this is connected to the LNB coax connector inside the CM (Figure 9). The 12 V is also regulated to 5 V to provide power to the interface. Though probably not required, there are two 5 V sources, one for the digital components of the interface, and the other for the analog components with one common ground point. This arrangement is used to isolate potential digital and analog noise sources within the circuit.

The interface is built on a circuit board and mounted right inside the CM box



Figure 10 — CM with interface board.



Figure 11 — Aiming the RT at the Sun, note LNB shadow location.



Figure 13 — Drift scan of the Sun indicating antenna's azimuth pattern.

(Figure 10). Though I made an etched circuit board for the circuit, the hand wired prototype worked equally well for those who would rather roll their own. The PIC firmware is available on the *QST* Web site.[6]

RT in Action

The first thing you need to do is learn how to point the RT antenna. The best place to start is to connect the CM to the antenna and point the antenna at the Sun. *Caution*: Do not look into the Sun as you do this, or at any time. Adjust the pointing angle and elevation until you get peak signal strength as indicated on the CM meter or hear the highest pitch audio tone. With the antenna pointed directly at the Sun, take note of the position of the shadow of the LNB on the surface of the dish (left in Figure 11). If you look from behind the dish, along the LNB



Figure 12 — Example calibration curves.



Figure 14 — Sequential drift scans. Note the time offsets between the peaks.

supporting arm (between the arm and the rim of the dish), you will see the Sun being blocked by the LNB.

Once you have the RT set up, it needs to be calibrated to match the output of the CM to *SkyPipe*. I have developed an *Excel* spreadsheet template to help with the calibration and a few of the other activities that you can accomplish with the RT (also available from the *QST* Web site). Turn the RT to a signal source, the Sun, or the side of a building would work. Turn the gain control of the CM to set the meter to maximum. Run *SkyPipe* and adjust the variable resistor on the interface board until you get a reading on the *SkyPipe* graph vertical (y) axis of approximately 32,000. With the maximum value set, adjust the CM gain control through the voltage range (0 to 100 mV) in 10 mV steps and record the corresponding y axis value on *SkyPipe*. This data is entered into the *Excel* spreadsheet to compute the calibration curve between voltage and y axis value. Both voltage and y axis values are used in analyzing recorded signal strength data (Figure 12).

A good first activity is to do a drift scan of the Sun. A drift scan means that you set the antenna azimuth (AZ) and elevation (EL) to some fixed pointing angle and allow the Earth to serve as the rotator to drag the antenna across the sky. To do a drift scan of the Sun, first set the elevation and azimuth to point directly at the Sun (maximum signal) and then move the azimuth toward the west (leave the elevation set) until you are off the peak signal. Now start *SkyPipe*. In about 15 minutes, the Sun will pass through the antenna pattern beam width and the result will be as illustrated in Figure 13. You can also use this collection technique to explore the antenna performance parameters.



Figure 15 — Clarke Belt plot — tracking down satellites.

A good second activity is to do two drift scans of the night sky on two consecutive nights (beginning the scans at the same time each night) using the same fixed antenna azimuth (AZ) and elevation (EL). Figure 14 shows two such drift scans. Although at first glance they may not seem similar, there are some interesting features that are pointed to by arrows. If you compare the time that these two peaks occurred, the time difference is about 4.5 minutes. This shift is the result of the distance the Earth had traveled during the 24 hours between collections. This illustrates that the Earth's rotation as well as its travel in orbit needs to be considered when comparing drift scans. Enough to make your head spin (pun intended)?

A final good starting activity is to point the antenna toward the Clarke Belt and find all the satellites in geosynchronous orbit transmitting on 12 GHz. If you record signal strength peaks and AZ and EL for each peak, you will develop a graph of the Clarke belt as illustrated in Figure 15.

I have only scratched the surface, and the sky is the limit of this little project. The RT project can certainly broaden your horizons and expand your understanding of our universe. If you would like more detail than can be presented here, please contact the author.

Notes

[1] **www.setileague.org/articles/lbt.pdf**.

[2] **www.aoc.nrao.edu/epo/teachers/ittybitty/procedure.html**.

[3] **www.pctinternational.com/channelmaster/0612/satellite.html**.

[4] **radiosky.com/skypipeishere.html**.

[5] **en.wikipedia.org/wiki/Geostationary**.

[6] **www.arrl.org/files/qst-binaries/**.

Mark Spencer, WA8SME, is ARRL Education and Technology Program Coordinator. He is an ARRL member and holds an Amateur Extra class license. You can reach Mark at 774 Eastside Rd, Coleville, CA 96107 or at **wa8sme@arrl.org**.

Did you enjoy this article?
Cast your vote at:
VOTE
www.arrl.org/members-only/qstvote.html

From June 2009 QST © ARRL

Simple demonstration to explore the radio waves generated by a mobile phone.

Dr Jonathan Hare, Sussex University, Department of Physics, Falmer, Brighton. BN1 9QH

Note: this article has been published: Simple demonstration to explore the radio waves generated by a mobile phone J P Hare, 2010, Journal of Physics Education, Institute of Physics, 45, p. 481 45 481

Also see the brief full article at: mobile phone detector

IMPORTANT NOTE: this device works very well on the old style mobile phones (as shown in the photo above). However, it does not always work well with modern smart phones. This may be because modern phones use higher frequencies, less power and use the power in a slightly different way (e.g. spread spectrum). Some smart phones do work and success may be due to the signal strength of the local mobile phone mast nearby. If you are in a low signal area the phone will create more power to ensure reliable communications. If you are in a very strong signal area (very near the local network) your phone will drop its output power and consiquently there will be less power to pick-up and to convert to a voltage to light the LED.

Described is a simple low cost home-made device that converts the radio wave energy from a mobile phone signal into electricity to light an LED. No battery or complex circuitry is required. The device can form the basis of a range of interesting experiments on the physics and technology of our mobile phones.



Fig. 1: left: mobile phone radio wave detector and right: the simple schematic

Introduction

Electromagnetic radiation (EMR) is at the heart of modern mobile phone data communications networks. The way a mobile phone and local base stations (the antenna covered masts you see dotted all around the place) communicate between each other is by using EMR in the radio wave part of the spectrum [1,2,3]. On switch-on your mobile sends digital information pulses by rapidly switching on and off the radio waves rather like a fast Morse code signal. Your text or voice is also converted into a series of digital pulses and sent across the network to be decoded (reassembled) by another mobile phone you dialled.

EM radiation and radio waves

Mobiles make use of various bands of radio frequencies to communicate between the mobile to base and the base to mobile: in Europe these include 900 and 1800 MHz (850 and 1900 MHz in the USA and Canada) [2, 3].

The relationship between wavelength, speed of light and the frequency follows the well known formula:
Wavelength λ (m) = speed / frequency = c (ms^{-1}) / ν (Hz)
λ (m) = 300,000,000 / ν (Hz) or approximately:
λ (m) = 300 / ν (MHz) ..... Equation 1.

So for a mid-range of about 1000 MHz (1 GHz) we get a typical mobile phone wavelength of about:
λ = 300/ 1000 = 0.3 m = 30 cm.

Simple radio wave detector

The loop consists of about a wavelength of wire, ca. 30 cm so each side is about 30/4 = 7.5 cm. The dimensions are not critical. The two ends are connected directly to a simple series circuit consisting of a high brightness LED and a germanium diode. They need to be connected correctly. All these components are cheap and readily available from electronic stores [4]. The loop can be made from a piece of copper wire roughly bent into a square (although a circular loop or rectangle will also work). If the wire is insulated remember to scrap off the insulation and solder-tin the ends. Simply solder the germanium diode and LED into circuit as shown in the diagram.
On a new LED the long lead is the positive (anode) while the short lead is the negative (cathode). The germanium diode has a line (band) around the end which is the cathode. When correctly wired the LED and the germanium diodes are connected so they both allow current to pass in the same direction, i.e. in the circuit diagram the arrows point in the same direction. In practice this means the LED and germanium diode are joined at the cathode of one and the anode of the other.
In my prototypes I used an insulator between the loop ends (light coloured cylinder in the photo) to make the whole thing more sturdy but this was purely for mechanical reasons and is not needed for the circuit to function properly. Note: a much more sensitive version using a x10 and x100 DC amplifier is described on my web site [6].

How it works and how to use it

When a radio wave passes across a metal object the EM fields cause the charged electrons in the metal to oscillate and this causes small AC currents at the same frequency to be induced into the metal. If a mobile is brought near to the loop and a call or text is made [5] the radio waves emitted from the phone pass across the loop. This induces a voltage into the antenna (the loop) and if it is close enough will be large enough to light the LED. As the loop is about one wavelength in size it is resonant and so there is a good transfer of power (low reactance) between the radio wave and LED.

The mobile phone automatically tests the network and adjusts its transmission power to maximise the battery life and minimise network interference. As a result the brightness of the LED will depend on the data being sent (the average signal), the local signal strength and how close the loop is to the phone. Why the second diode? - It's curious why the germanium diode is needed at all. The LED is a Light Emitting Diode after all and one would not think that another diode would help. However my initial experiments failed because I had not included it. The LED will have a relatively high capacitance which at these frequencies will tend to de-tune the loop and short out the LED. The germanium diode however is made up of a tiny wire which only makes a point-of-contact onto a piece of semiconducting germanium so it's 'self' capacitance is very low keeping the loop resonant.

The germanium diode will rectify the AC signal from the loop forming a series of DC pulses that will be nicely smoothed by the LED's capacitance. Without the diode however the raw AC signal from the loop will tend to be averaged to zero by the LED's capacitance.



Fig. 2: Three loops in a row of varying size. The one described here and shown in Fig. 1 is shown in the middle. Smaller ones may well work better for higher frequencies such as the 3G networks (see below).

Other size loops

Fig. 2 shows a set of three loop devices with edge lengths of roughly 3.7, 7.5 and 15 cm. You can find out for yourself that the best match to the mobile signal is with the full wave loop of ca. 7.5cm per side. The other loops do work to varying degrees however (smaller ones may work better for the 3G network). The larger loop works well for the '70 cm' amateur radio bands.

Polarisation

The electric and magnetic fields making up the EM wave are orthogonal (they are at right angles to each other as they pass through space) to each other but depending how they are generated by the transmitting antenna can arrange themselves in any orientation with respect to the ground. If the electric field is parallel with the ground we say the wave is 'horizontally polarised' while if its normal to the ground we say its 'vertically polarised'. The loop antenna will respond best to one type of polarisation (depending on its orientation) so it's worth experimenting with the orientation of the mobile (or the loop) to get the strongest signal - brightest LED.

Mobile antenna

Inside your mobile phone is a transmitter / receiver and antenna. Many mobiles have this antenna at the top of the phone but some of the PDA type phones have it at the bottom. As a result you can locate the position of the antenna by moving it around the center of the loop till you get maximum LED brightness.

Networks

There are various different networks that a mobile may use both in the UK and abroad. It may be that you need to adjust the network phone settings on your mobile i.e. change from "automatic select" to set for "GSM" so as it get the strongest signal to light the LED. Note: the 3G network might not be powerful enough to light the LED. As the GMS network is currently the main network over the UK the device should work anywhere where you can get a signal as long as you check the correct selection on your mobile menus [5, 7]. The 3G network operates on a higher frequency (smaller wavelength) so you might find a smaller loop will work better than the main one described here. See 'other experiments' section below.

Test signals

In order to pick up the radio wave energy from the phone it obviously needs to be transmitting a signal. There are a few ways to do this:

1) On switch 'on' (or change of network) you can see that the mobile initially transmits for a few seconds to the network to tell it it's there (especially if you have moved since turning it off). You don't actually need to dial a number to detect these signals.
2) Even if don't text or call, throughout the day the mobile will send out data to 'keep up' with the network, especially if you are moving around (going through train tunnels etc. see below).

3) When you make a phone call you will transmit. Initially there is quite a lot of data being sent but in a few seconds data / power only gets transmitted when you speak. So to light the LED continuously you need to talk or provide some background sound continuously. Your service provider voicemail might be a good free phone number to try for these experiments [5].

4) Texting is the easiest way to show the radio wave power being transmitted. Long texts will light the LED for longer than short texts.

5) Finally set up the mobile on the loop and use another phone to text or phone the mobile. Even though you are not directly using the phone you will see that even on 'receive' the mobile phone transmits data to and fro. Ring off before you get charged.

Note: If you can use a free phone number it will save you money [5].



Fig. 3: Adding a capacitor and coax (or twin) lead so that headphones, a meter or a data logger can be connected (Note: diode is reverse wired compared to Fig. 1).

Other experiments:
Hearing data - if headphones are wired across the LED they will convert the voltages into sound and you can 'hear' the clicks of the digital data being transmitted. These are the same clicks that so easily get picked up by sensitive electronics such as a stereo amp or recording equipment when making a video for example. Hence - 'no phones on' when filming.

Logging data - if a meter, or better still a stand-alone data logger, is attached across the LED then one can monitor the EMR from the phone. For example even if you are not making a call your mobile will send signals too (and receive signals from) the network while travelling around. Fig. 3 shows a simple modification using a de-coupling capacitor so that a coax cable (or twisted pair) can be used to go to headphones, meter or data logger. Note the diode has been reversed so that the logger has the correct + and – connections for a unipolar input logger. The capacitor should help average the signal and stop radio frequencies going down to the logger. If one is available a few turns of the wire can be wound within a ferrite ring near to the logger so that maximum immunity to the mobile phone signal can be obtained for the logger electronics.



Fig. 4: Typical mobile phone data signals sent out onto the network while travelling around. These were recorded by a data logger from a mobile using the loop (no calls or text were made) while travelling on the train from Brighton to London Victoria (and then around London and return). Many of these peaks were the phone sending out 'I am here' data after coming out of one of the many long tunnels under the South Downs during the journey.

Out and about - Once you can log data you can discover all sorts of interesting things your mobile phone is doing without you realising it. Fig. 4 shows the plot over a few hours of travelling between Brighton and London (and within London) on the train. The detector was simply placed near to a phone that was not making or receiving a phone call or text, but was turned on.

The graph shows that the mobile sends out signals to tell the network where it is as it travels along and in particular goes in and out of long train tunnels. The peak heights vary because of the different powers the mobile transmits at depending on the signal strength of the local network and also because of the way the data logger 'snatches' a reading from the circuit every few seconds. As your phone sends out data onto the network to ensure the very best communications as you move around, so your mobile and the network obviously knows where you are and where you have been. Thieves and criminals beware the police can track you!

The inverse square law - If the transmitting mobile phone is moved away from the loop one would expect the signal to drop off. Unfortunately because both diodes need a certain threshold before they conduct the detector is not sensitive to small signals and not very linear. Therefore it's not very easy to use the device to measure the inverse square law (drop in signal v distance away) but of course you can see the signal go down. You could perhaps use the device to plot isobars - i.e. plot the equal intensity signals around the phone / nearby objects.

Changing the resonant frequency of the loop - you might be able to make some simple sliding mechanism (e.g. a small trombone-like mechanism) out of metal tube for example to tune the loop device for different frequencies. Then you can use it to find the average wavelength and so determine the center frequency by adjusting the size for maximum brightness of the LED. The wavelength can be determined by measuring the total distance around the loop. If we assume the antenna is one wavelength in total length then the frequency can be established by rearranging Equation 1, i.e. ν (MHz) = 30,000 / L (cm), where L is the length around the loop (cm).

Note: You will need to allow the transmitted digital signal to 'settle down' i.e. make measurements only after a few seconds after dialling / pick up so that only the sound data is being transmitted rather than the initial connection data. A constant sound will also need to be made so that the mobile phone continuously transmits data. It's worth playing music near to the phone or constantly whistling to keep sound coming into the phones microphone.

Mobile phone detector - teachers who want to know if the students / pupils really have turned-off their mobile phones (rather than just put on 'silent') can wire the loop device into the class room white-board speakers. Any mobile that is on in the class will send out signals which (if you are close enough) you will hear the data going to and fro - you will have your very own 'who's got their mobiles on' device which might be useful for exams etc.



Fig. 5: The SEPNet 'deluxe' printed circuit board version (pcb) on a perspex stand where the loop is composed of a pcb copper track and the diode and LED soldered onto the board (top) [8,9].

Summary
All in all then, for such a simple easy to make device I hope you agree that there is a lot of scope for interesting science / technology investigations with your mobile phone. The device would make a good science week project (for radio amateur clubs etc.) A 'deluxe' pcb version (Fig. 5) on a perspex display case (Fig. 5) is currently going around the southern UK as part of the SEPnet outreach work, see the 'Radiation Exhibition' [8] and also as part of my on-going lecture series [9].

Post publication additions
(What follows was not included in the published article as this calculation was worked out later). A full wave loop is resonant and so looks purely resistive to the radio waves. Such a loop will have a resistance of about 100 ohms (Note: this is the AC resistance and not the DC resistance which will be very low). Now power P = V x I (V = voltage and I = current) and resistance = R = V/ I therefore $P = V^2 / R$ or rearranging $V = \sqrt{(P \times R)}$ which means that the voltage created by a power level of say 50mW (say for argument that roughly half the mobile phone power) arriving at the antenna will be about $V = \sqrt{(100 \times .05)}$ which is aprox. V = 2V, enough to light an LED.



This circuit uses a two transistor darlington driver to amplify the signal from the loop and diode making the detector much more sensitive. The LED will be much brighter using this circuit. Note: the circuit needs a battery to power it (e.g. a PP3 9V)

References
[1] These ultra high frequencies (UHF, > 1000 MHz) are also often called microwaves.
[2] wiki pages
[3] Elektor Electronics magazine, June 2005
[4] order codes for the germanium diode and LED are:
e.g. Germanium diode: Maplin Electronics: QH71N, Rapid Electronics: 47-3114
e.g. LED: Maplin Electronics: UF72P , Rapid Electronics: 55-0085
[5] to save money use your voice mail service (often you simply dial 121).
[6] for details of an amplified detector see: wavemeter
[7] select 'network setting' from the mobile phone 'settings' menu and then go to 'network mode' and select 'GSM 900/1800' rather than 'automatic'.
[8] SEPnet mobile phone device on display throughout southern UK. [9] for details of my talks see: talks and workshops

THE CREATIVE SCIENCE CENTRE

Dr Jonathan Hare, Brighton, East Sussex. BN1 9QJ.

home | diary | whats on | CSC summary | latest news

Simple demonstration to show mobile phones emit radio waves

Dr Jonathan Hare, Sussex University, Department of Physics, Falmer, Brighton. BN1 9QH

Note: this article is in press: Elektor Magazine, July-August 2010, p. 56-57

For other experiments with this device please see my full article at: mobile phone detector




LED
OA91
diode
1 wavelength loop
ca. 30 cm total
7.5 cm per side
resonant at
ca. 1000 MHz
~ 7.5 cm

left: mobile phone radio wave detector and right: the simple schematic. Below: detail of the LED and germanium diode.

IMPORTANT NOTE: this device works very well on the old style mobile phones (as shown in the photo above). However, it does not always work well with modern smart phones. This may be because modern phones use higher frequencies, less power and use the power in a slightly different way (e.g. spread

spectrum). Some smart phones do work and success may be due to the signal strength of the local mobile phone mast nearby. If you are in a low signal area the phone will create more power to ensure reliable communications. If you are in a very strong signal area (very near the local network) your phone will drop its output power and consiquently there will be less power to pick-up and to convert to a voltage to light the LED.

This is a very simple and cheap device that demonstrates mobile phones ('cell phones' or 'handies') generate radio waves. We have a 30 cm (7.5 cm per side) full-wavelength loop antenna (a 'Quad' to radio amateurs) connected to a germanium diode and a hyper-bright LED. The loop can be made of copper wire, thin sheet metal or a track on a pcb. The diodes need to be wired correctly. I think the germanium diode is needed as the LED probably has too great a self-capacitance to perform at the very high AC frequencies generated by the phone (ca. 900 or 1800 Hz) but will work well with the DC pulses from the germanium diode (which has a very small capacitance).

To show the mobile generates radio waves put the mobile near to the loop and dial a number (use a free phone number, e.g. your voice mail) or text. The radio waves will induce a voltage into the loop, large enough to light the LED. The LED will flash indicating the digital data being sent by the mobile phone transmitter. You may need to set your phone to 'GSM 900/1800' rather than the '3G' network in the settings menu.

parts:
germanium diode: Maplin Electronics: QH71N or Rapid Electronics: 47-3114
LED: Maplin Electronics: UF72P or Rapid Electronics: 55-0085



A very simple connector block version and a circular 1 wavelength loop

THE CREATIVE SCIENCE CENTRE

Dr Jonathan Hare, Brighton, East Sussex. BN1 9QJ.

home | diary | whats on | CSC summary | latest news

BACK TO G1EXG RADIO PAGE

EPAD MOSFET - 'near zero' and 'zero' threshold devices
(e.g. the ALD110900)

I will add more details to this page later on but for the moment it gives links to important and inspiring sites.

ARTICLES
1) High Sensitivity Crystal sets, Technical Topics, Pat Hawker, Rad Com, p. 77-78, May 2007.
2) A novel kind of 'crystal set' radio, Giles Read, Rad Com, p. 60-61, June 2007.
3) also see Pat Hawker, Technical Topics, Rad. Com. January 200, page 53-57.
4) High Sensitivity Crystal Set by By Bob Culter (N7FKI)
5) Next-generation Zero-Threshold Voltage EPAD™ design enables circuits with greater operating range in low voltage supply environments

LINKS ABOUT THE CHIPS / DEVICES
1) Advanced Linear Devices web site
2) EPAD MOSFET (ALD web site)
3) ALD110800 and ALD110900 page (ALD web site)
4) ALD110802 and ALD110802 page (ALD web site)

ORDERING THE CHIPS / DEVICES
1) mouser.com (USA)

'CRYSTAL SET' RADIO'S - DIFFERENT DETECTORS



**Top: the medium wave (MW) test radio with a selection of 'detectors' (selected by the croc clip lead)
Bottom: the short wave (SW) version with a ALD110900 detector
(on each circuit board the connections are: antenna - top left, Earth - bottom left, audio output (heaphones / amp) - far right.)**

RADIO AND RADIO WAVES

The simplest 'radio' can be a piece of wire attached to the input of an amplifier. Why does this pick up radio signals? Well in principle it should not be able to pick up anything but in reality poor solder joints in the amplifier circuitry, as well as point contact effects between the ends of the anenna wire going into the input socket of the amp as well as other effects mean that you do often hear radio signals.

Radio waves are electromagnetic waves as they pass through a metal they induce small voltages into it. Any piece of metal e.g. metal fram specs, tape measures, metal window frames, a piece of wire etc. will act as an antenna and have tiny voltages induced into them. These voltages will be due to natural radio waves (from Space as well as the Sun and Earth), radio stations, satellites, mobile phones, garage door remote controls, microwave ovens .... the list goes on and on.

In the case of long, medium and short wave radio stations the amplitude of the radio wave signal is modified by the music, voice or program - we call it Amplitude modulation AM. Here the strength of the radio waves varies as the tones, loudness and pitch of the program vary. As a result the voltages induced in the metal object antennas distant from the radio wave stations also vary in accord this program information or modulation.

To actually hear the programs on the radio waves you cant actually take this tiny signal and listen to it directly (say with headphones or an amplifier). This is because the signal is a very high frequency signal out of the range of human hearing. To get the audible information - the program - 'off' the radio signal you need a device known as a 'detector'. This is usually a diode but lots of other things can act as inefficent detectors for example a mineral called galena, coke (burnt coal) ... as well as rusty screws and bad solder joints which is how the ampilfier mentioned above apparently picks up radio signals.

In the early days of radio crystals of galina were used as diodes and so these radios became known as 'crystal set radios'. They did not have any amplifiers and did not require any battery to work. They got all their power from that induced into the (of very long) antenna by the radio signal(s). The radio detector is an extremely important part of the radio and its proper function determines how well the radio works.

The radio signal is an AC signal. A speaker or headphones can not resonate at such high frequencies as radio waves and if you try to wire in the RF to the headphones the diaphram just averages the power. As half the time the RF is positive and half the time negative, in an AC signal, the average is zero and so you dont hear anything. The diode or detector is a device called a diode which only conducts electricity in one direction. So it only allows the positive, or negative half (one half but but not both) of the AC signal to go through (depending on which way it is wired). After the diode the average is now no longer zero its actually a changing signal dependant on the modulation of the radio wave - which is the information we want to hear. As this is at audio frequencies, and as the diaphram can move at audio frequencies, you hear the information on the detected RF signal - the music, voice or what ever.

Why should some detectors (diodes) be 'better' than others? The answer is not that some are better at 'magnifying' the signals but rather that each diode requires a certain threshold voltage in order to start conducting (one way). Signals below this level will not get passed through and a signal only slightly larger will therefore only pass through weekly (the diode unfortunatly absorbing the majority of the signal). As a result for large signals you wont expect to see much difference between different detectors but for weak signals there can be a great deal of difference. In an ideal world the diode would start to (forward) conduct at just above zero volts and this ideal detector (which does not conduct at all in reverse) would produce the greatest signal possible for the particular strength signal applied to it.

Recently I was playing around with OA91 germanium diodes for a mobile phone detector. I made a simple 10cm per side square loop and wired it directly to an LED. I was hoping that if I brought the mobile near to the loop and texted, or made a phone call, the RF should be picked up by the loop (which is almost resonant) and the LED should light - it didnt work! But putting an OA91 in series I did get it to work. So why did I need the OA91 diode when the LED is itself a diode?

It can't be due to the threshold voltage in this case as I am still using the LED and I did get it to work with the same signal! So I guess it because the capacitance of the LED is very high compared to the point-contact germanium diode. If we extend this thinking to the crystal set radio I guess the germanium diodes have very little capacitance and so dont allow any of the 'wrong' half of the AC signal through and so act as a more perfect detector. An LED would have a high capacitance and so let some of the wrong half of the AC signal through which on averaging by headphones would be nearer zero (see above) - hence less sound.

A low threshold (turn-on) voltage and a low self capacitance are crucial things in a good detector. Point contact germanium diodes having a very small area (a point of contact) have low capacitance and the germanium semiconductor-metal junction of the contact has a low turn on voltage. EPAD Mosfets also have low capacitance, high input resistance (low loading of the signal) and low turn on voltage.



MEDIUM WAVE TEST CIRCUIT (top in photo)
As a simple test circuit to compare detectors I made up a simple 'crystal set' radio from a ferrite rod coil from an old radio, tuning capacitor an array of diodes (crystals) and a simple RF filter composed of a 47k resistor and 1nF capacitor. The coil and capacitor formed the resonant circuit which was fed via a 10 - 50pf capacitor by the antenna (long wire). This capacitor helps to reduce the effect of the antennas own capacitance and inductance from modifying the resonant frequency of the tuned circuit. Ideally this should be as small a capacitance as you can get away with but too small a value will reduce the radios sensitivity ....

An earth was connected to the ground connection of the circuit. Instead of taking the antenna end of the resonant circuit to a diode detector (as many simple crystal sets do) I used a ca. 10 turn coupling coil around the coil. This was done to limit the loading on the resonant circuit by the detector. It should help keep the tuning sharp and also help to keep the overall (band) spread of tuning as large as possible.

Because of the reduction in turns (ca. 100 turns : 10 turns, i.e. 10:1) the coupling coil reduces the signal that is available to drive the detector. For example if I use a standard silicon diode (e.g. a 1N4148) which requires about 0.6V to conduct then we might need ca. 10 x 0.6 = 6V of RF to be developed in the resonant circuit! A high Q resonant circuit might do this with a long antenna coupled to it but without such a generious antenna such a set-up wont be very sensitive.

RESULTS
I tried an array of 'crystal set' type diodes to campare them. Typical rough results are shown in the table below. This was with an Earth and about 3-4m of antenna wire randomly strung near to ground level (so its a pretty bad set up really - a good test).

The EPAD MOSFET data sheets described how the gate and drain of one of the MOSFETS can be joined together to form the anode of a diode the source then forms the cathode. I tried this arangement with the ALD110900 in order to make up a 'crystal set' diode from this MOSFET but it didnt perform well.

Then I tried the alternative arrangement as described in the references above. In these articles they dont use the MOSFETS as diodes but connect the gate directly to the resonant circuit. As the input resistance is extremely high (c.a. 1E12 ohms) and the input capacitance is very low (c.a 3pf) it does not load the tuned circuit by any appreciable amount. The source and drain are then wired between the coupling coil and filter just as the usual diode detector is in a crystal set radio. In this configuration the MOSFET is working more as a gate voltage controlled resistor rather than a diode i.e 'off' for half an RF cycle and 'on' for the rest - this lets the envelope through and you hear the music or sound. One article describes the arrangement as a synronious detector. As there are two MOSFETS in one package the two are wired in parallel i.e. gate to gate, drain to drain (there is a common source) etc.

DETECTOR TYPE	AF voltage produced after filtering
1N4148 silicon	no signal
OA91 germanium	1mV
1N43A germanium	1mV
1N60 germanium	1mV
AAZ17 germanium	1.5mV
ALD110900 EPAD MOSFET wired as diode	<1mV
ALD110900 EPAD MOSFET wired as sync. detc.	10mV

Typical results of the AF voltages produced by the detector (for use by headphones or amplifier) for an Earth connection, small (ca. 3-4m antenna wire near ground level) and the prototype 'crystal set' radio.

For the simple set-up described above there was not enough signal to get the silicon diode to work at all (although a much longer wire did provide a very small signal). A simple listening test and measurement of the AF prodiced by each diode showed that their was very little difference between the various germanium diodes. The MOSFET simply wired as a diode (gate wired directly the drain) was a poor detector - better than a silicon but not nearly so good as any of the germanium diodes. Finally the EPAD MOSFET wired as a syncronious detector worked really very well apparently producing ca. 10 times the signal (in other words it has much less loss than a germanium diode) for this particular set up and station than the germanium diodes.

As the syncronious arrangement was so succesful it got me thinking about this circuit. As the gate goes straight in on the main resonant circuit where the voltages, in a good Q circuit, might well be relatively high I thought I would try a standard FET (2N3819) and MOSFET (VN10KM) instead - and they worked! (they are a lot cheaper than an EPAD MOSFET chip and easier to get). Some FETS have a larger input capacitance so it helped to put a 10pf capacitor in series to the gate (a 10M ohm from gate to earth might reduce 50Hz pick up).

They were not as good as the EPAD MOSFET (although I only tried a single device) but the arrangment was still better than a simple 'crystal set' diode. For weak signals the EPAD MOSFET should perform better as it is able to keep going while the FET and the standard MOSFET will start to trail off as the resonant circuit voltage drops below the relatively higher gate voltage required for these devices. However it was interesting to see that it seems to be possible to get a more efficent set-up for a 'crystal' radio using a standard FET or MOSFET than with the standard germanium diode detector.

By the way I recently re-tried the 1N4148 diode but wired a 1.5V AA battery with a 100k resistor across it to forward bias it - and it worked ! It seemed to work better than a OA91!

SHORT WAVE 'CRYSTAL SET RADIO (bottom in photo)

The bottom circuit shown in the photo above is my own short wave version of the 'crystal set' radio but based on the references above. It's the same circuit as the MW radio but has a reduction drive tuning capacitor and different coil. I used about 7 turns (ca. 4cm diameter) for the resonant circuit and a couple of turns of insulated wire (white) for the coupling coil. I guess the radio tunes from about 3-8 MHz - I havent tried a sig gen on it yet.

I made this in the summer months (not the best time for listening on this part of the spectrum). Using an Earth and few meters of wire for antenna I heard 2 or 3 stations from around the world during the day while at night there were at least 7 including the voice of Russia world service, Radio Thailand as well as German and French speaking stations.

BACK TO G1EXG RADIO PAGE

THE CREATIVE SCIENCE CENTRE

Dr Jonathan Hare, The University of Sussex
Brighton, East Sussex. BN1 9QJ

home | diary | whats on | CSC summary | latest news

PUBLISHED BY

INTECH
open science | open minds

World's largest Science,
Technology & Medicine
Open Access book publisher

3,200+
OPEN ACCESS BOOKS

105,000+
INTERNATIONAL
AUTHORS AND EDITORS

111+ MILLION
DOWNLOADS

BOOKS
DELIVERED TO
151 COUNTRIES

AUTHORS AMONG
TOP 1%
MOST CITED SCIENTIST

12.2%
AUTHORS AND EDITORS
FROM TOP 500 UNIVERSITIES

CLARIVATE ANALYTICS
BOOK CITATION INDEX
INDEXED
WEB OF SCIENCE™

Selection of our books indexed in the
Book Citation Index in Web of Science™
Core Collection (BKCI)

Chapter from the book *Sustainable Energy Harvesting Technologies - Past, Present and Future*

Downloaded from: http://www.intechopen.com/books/sustainable-energy-harvesting-technologies-past-present-and-future

Interested in publishing with InTechOpen?
Contact us at book.department@intechopen.com

10

Design Issues in Radio Frequency Energy Harvesting System

Chomora Mikeka and Hiroyuki Arai
Yokohama National University
Japan

1. Introduction

Emerging self powered systems challenge and dictate the direction of research in energy harvesting (EH). State of the art in energy harvesting is being applied in various fields using different single energy sources or a combination of two or more sources. In certain applications like smart packaging, radio frequency (RF) is the preferred method to power the electronics while for smart building applications, the main type of energy source used is solar, with vibration & thermal being used increasingly. The main differences in these power sources is the power density; for example RF (0.01 ~ 0.1 μW/cm^2), Vibration (4 ~ 100 μW/cm^2), Photovoltaic (10 μW/cm^2 ~ 10mW/cm^2) and Thermal (20 μW/cm^2 ~ 10mW/cm^2). Obviously RF energy though principally abundant, is the most limited source on account of the incident power density metric, except when near the base stations. Therefore, in general, RF harvesting circuits must be designed to operate at the most optimal efficiencies.

This Chapter focuses on RF energy harvesting (EH) and discusses the techniques to optimize the conversion efficiency of the RF energy harvesting circuit under stringent conditions like arbitrary polarization, ultra low power (micro or nanopower) incidences and varying incident power densities. Harvested power management and application scenarios are also presented in this Chapter. Most of the design examples described are taken from the authors' recent publications.

The Chapter is organised as follows. Section 2.1 is the introduction on RF energy sources. Section 2.2 presents the antenna design for RF EH in the cellular band as well as DTV band. The key issue in RF energy harvesting is the RF-to-DC conversion efficiency and is discussed in Section 2.3, whereas Section 2.4 and 2.5 present the design of DTV and cellular energy harvesting rectifiers, respectively. The management of micropower levels of harvested energy is explained in Section 2.6. Performance analysis of the complete RF EH system is presented in Section 3.0. Finally, conclusions are drawn in Section 4.0.

1.1 RF energy sources

These include FM radio, Analogue TV (ATV), Digital TV (DTV), Cellular and Wi-Fi. We will present a survey of the measured E-field intensity (V/m) for some of these RF sources as shown in Table 1, [1]-[2]. Additionally, measured RF spectrums for DTV and Cellular signals are presented as shown in Fig. 1 to show on the potential for energy-harvesting in these frequency bands. In general, many published papers on RF-to-DC conversion, have presented circuits capable of converting input or incident power as low as -20dBm. This means that, if an RF survey or scan finds signals in space, with power spectrum levels around -20dBm, then, it is potentially viable to harvest such signal power. In Fig. 1 (left side), the spectrum level is well above -20dBm and hence, a higher potential for energy harvesting. In Fig. 1 (right side), while the spectrum level is below -20dBm, what we observe is that the level increases with decrease in the distance toward the base station (BTS). Using free space propagation equation with this data, it was calculated that at a distance 1.4 m from the BTS, the spectrum level could measure 0dBm. An example calculation and plot for the estimated received power level, assuming 0dBi transmitter (BTS) and receiver antenna gains and free space propagation loss (FSPL) for FM and DTV is presented in Section 2.1.1. For the example estimation in Section 2.1.1, we select FM and DTV because they measured with a higher level than cellular and Wi-Fi for example.

Source	V/m	dBm	Reference	
FM radio	0.15~3		Asami et al.	
Analogue TV	0.3~2			
Digital TV	0.2~2.4	-40~0.0	Asami et al.	Arai et al.
Cellular		-65~0.0	Mikeka and Arai	
Wi-Fi		≅ -30		

Table 1. RF energy sources, measured data.

In Table 1, FM radio has the highest E-field intensity implying the highest potential for energy harvesting. However, due to the requirements for a large antenna size and the challenges for simulations and measurements at the FM frequency i.e. 100 MHz or less (See Section 2.2.3, example FM antenna at 80 MHz), this Chapter will focus on DTV (470~770 MHz band) and Cellular (2100 MHz band) energy harvesting.



Fig. 1. DTV signal spectrum measured in Tokyo City (left side graph) and Cellular signal spectrum measured in Yokohama City (right side graph).

The received DTV signal power is high and also wide band, presenting high potential for increased energy harvesting unlike in cellular signals. We demonstrated in [2] that the total RF-to-DC converted power is roughly the integral over the DTV band (1), and is significantly larger than in the case of narrow band cellular energy harvesting.

$$P_{DC(DTV)} = \alpha \int_{470}^{770} \delta P_{DC}(f)\,df \;, \tag{1}$$

where α is the attenuation factor on the rectifying antenna's RF-to-DC conversion efficiency due to multiple incident signal excitation. δP_{DC} is the small converted DC power from each of the single DTV signals in the 470 MHz to 770 MHz band.

In detail, we derive (1) from fundamentals as follows.

The incident power density on the rectifying antenna (rectenna), $S(\theta,\phi,f,t)$, is a function of incident angles, and can vary over the DTV spectrum and in time. The effective area of the antenna, $A_{eff}(\theta,\phi,f)$, will be different at different frequencies, for different incident polarizations and incidence angles. The average RF power over a range of frequencies at any instant in time is given by:

$$P_{RF}(t) = \frac{1}{f_{high} - f_{low}} \int_{f_{low}}^{f_{high}} \int_{0}^{4\pi} S(\theta,\phi,f,t) A_{eff(\theta,\phi,f)} d\Omega df \tag{2}$$

The DC power for a single frequency (f_i) input RF power, is given by

$$P_{DC}(f_i) = P_{RF}(f_{i,}t).\eta\left(P_{RF}(f_i,t),\rho,Z_{DC}\right), \tag{3}$$

where η is the conversion efficiency, and depends on the impedance match $\rho(P_{RF},f)$ between the antenna and the rectifier circuit, as well as the DC load impedance. The reflection coefficient in turn is a nonlinear function of power and frequency.

The estimated conversion efficiency is calculated by P_{RF}/P_{DC} . This process should be done at each frequency in the range of interest. However, DC powers obtained in that way cannot be simply added in order to find multi-frequency efficiency, since the process is nonlinear. Thus, if simultaneous multi-frequency or broadband operation like in DTV band is required, the above characterization needs to be performed with the actual incident power levels and spectral power density. In this Chapter, we shall demonstrate DTV spectrum power harvest, given a rectenna than has been characterised in house at each single frequency in the DTV band.

1.1.1 An example calculation and plot for the estimated received power level

In this example we consider Tokyo's DTV and FM base stations (BS) as the RF sources. Both DTV and FM BS transmitter power (P_t) equals 10 kW (70dBm). The antenna gains are assumed 0dBi in both cases but also at the points of reception for easiness of calculation but with implications as follows. Assuming 0dBi antenna at each reception point, demands that we specify the frequency of the transmitted signal. For this reason we specify DTV signal frequency to be equal to 550 MHz while the FM signal frequency equals 80 MHz (Tokyo FM).

The received power, P_r is calculated using the simplest form of Friis transmission equation given by

$$P_r = P_t + G_t + G_r + FSPL\,, \tag{4}$$

where P_t = 70dBm, $G_t = G_r$ = 0dBi. G_r is the receiving antenna gain while FSPL is the free-space path loss given by

$$FSPL(dB) = 20\log(d) + 20\log(f) + 32.45\,, \tag{5}$$

where ***d*** is in (km) and ***f*** is in (MHz). The plot for the received power as a function of distance from the DTV and FM base stations is shown in Fig. 2.



Fig. 2. DTV and FM received signal power level against distance.

With respect to Fig. 2, FM registers higher received power level than DTV at every reception point due to its lower transmit frequency and hence lower free-space path loss. For example at 1 km distance, FM received power level is -0.51dBm while for DTV, the received power is -17.26dBm. The important thing however, is that the received power level is frequency independent. It means that P_t is the transmitter power and the received power level at the position of distance ***d*** is $\frac{P_t}{4\pi d^2}$. However, if we assume 0dBi antenna at each reception point as in the above example, the power level is different because the antenna size of 0dBi is frequency dependent. As a result, high transmit power level is favorable for RF energy harvesting. Also near the base station is favorable.

1.2 Antenna design for the proposed RF energy harvesting (EH) system

It is well known that RF EH system requires the use of antenna as an efficient RF signal power receiving circuit, connected to an efficient rectifier for RF-to-DC power conversion. Depending on whether we want to harvest from cellular or DTV signals, the antenna design requirements are different. We will discuss the specific designs in the following sub sections.

1.2.1 Cellular energy harvesting antenna design

We propose a circular microstrip patch antenna (CMPA) for easy integration with the proposed rectifier (Section 2.5.1). However, the use of circular microstrip patch antennas (CMPA) is often challenged by the need for impedance matching, circular polarization (CP) and higher order harmonic suppression.

To address the above concerns, we create notches on the circular microstrip patch antenna. In our approach, we use only two, thin, fully parameterized triangular notches to achieve higher order harmonic suppression, impedance matching and circular polarization, all at once. This is the novelty in our proposed antenna. Our proposed CMPA is shown in Fig. 3. We study the behaviour of CMPA surface current vectors when notches (triangles ABC) are created on the structure at $\alpha = 45^0$ and $\alpha = 225^0$.



Fig. 3. Cellular energy harvesting antenna structure.

Notch parameters ***d*** and ***h*** in Fig. 3 were investigated by calculation using CST microwave Studio.

Without notches, the CMPA's input is not matched at f_c= 2.15 GHz as shown in Fig. 4 (left side). However, with notches, matching is achieved. The parameter combination ***d*** = 7 and ***h*** = 6 offers a matched and widest band input response and hence we adopt it for cellular energy harvesting applications.



Fig. 4. *Left side:* ***d*** and ***h*** parameter investigation. *Right side:* Comparison between (cal.) and (mea.) S_{11} at f_0 = 2.175 GHz, $2f_0$ = 4.35 GHz and $3f_0$ = 6.53 GHz. The adopted notch parameters are ***d***=7 mm while ***h***= 6 mm.

The comparison between calculated and measured S_{11} is shown in Fig. 4 (right side). The 2nd and 3rd harmonics are suppressed as required by design. The comparison between calculated and measured radiation patterns is shown in Fig. 5, where $E_\vartheta \cong E_\varphi$ due to the 45^0 tilted surface current vector. Ordinarily, without notches, the surface current vector is parallel to the microstrip feeder axis. In conclusion, our proposed CMPA is sufficiently able to suppress higher order harmonics while simultaneously radiating a circularly polarized (CP) wave. The CP is required to efficiently receive the arbitrary polarization of the incident cellular signals at the rectenna.



Fig. 5. Cellular energy harvesting antenna pattern at f_c= 2.15 GHz.

1.2.2 DTV energy harvesting antenna design

Unlike in the cellular energy harvesting antenna, the DTV energy harvesting antenna must be wideband (covering 470 MHz to 770 MHz), horizontally polarized and omni-directional.

The proposed antenna is typically a square patch (57 mm x 76 mm) with a partial ground plane (9 mm x 100 mm). The patch is indirectly fed by a strip line (9 mm x 3 mm). The proposed antenna geometry is shown in Fig. 6. The partial ground plane is used to achieve omni-directivity and a certain level of wide bandwidth. To tune the impedance of this antenna as well as to adjust the bandwidth within the target band, a “throttle” with stepped or graded structures is used between the microstrip feed line and the square patch, as shown in Fig. 6 (left side).



Fig. 6. Proposed DTV antenna geometry. *Left side:* Front view. *Right side:* Back view. The antenna is printed on FR4 substrate; t = 1.6 mm, ε_r = 4.4.

The input response for the proposed antenna is shown in Fig. 7 (left side). The omni directivity is confirmed by measurement at 500 MHz, 503 MHz, and 570 MHz as shown in Fig. 7 (right side). The radiation patterns shown in Fig. 7 are for the xz plane, which happens to be the vertical polarization for the antenna. DTV signals are horizontally polarized and therefore, when using this antenna, the orientation must be in such a way as to efficiently receive the DTV signal. Simply a 90 degree rotation of the antenna along the z axis achieves this requirement.



Fig. 7. Proposed DTV antenna performance. *Left side:* The antenna's measured input performance. *Right side:* The omni directivity in the vertical plane is confirmed at 500 MHz, 503 MHz, and 570 MHz. The outermost, black solid and dotted line patterns represent 503 MHz and 500 MHz directivity, respectively. The innermost dotted line pattern is the directivity at 570 MHz.

1.2.3 Example design for an 80 MHz FM half-wave dipole antenna

A half-wave dipole is the simplest practical antenna designed for picking up electromagnetic radiation signals, see Fig. 8 (courtesy of Highfields Amateur Radio Club). Calculating the optimal antenna length to pick up a certain frequency signal is fairly straightforward because antenna physics demand that the total length of wire used in the antenna be equal to one wavelength of the type of electromagnetic radiation it will be picking up. This means that the total length of the antenna should be equal to half the desired wavelength. By converting the 80 MHz frequency into a wavelength, you can thus obtain your antenna length as 1.875m by using the magic equation, $\lambda = \frac{c}{f}$. However, the actual length is typically about 95% of a half wavelength in free space, hence a half-wave dipole for this frequency should be 1.788m long, which would make each leg of the dipole 0.894m in length.

1.3 RF-to-DC conversion efficiency improvement techniques

A Schottky diode circuit connected to an antenna is used for RF-to-DC power conversion. To convert more of the antenna surface incident RF power to DC power, high RF-to-DC conversion efficiency is required of the rectifying circuit. Many authors have shown that the efficiency depends on several factors like Schottky diode type, harmonics suppression capability, load resistance selection, and the capability to handle arbitrary polarized incident waves. What is missing in most of these published works is the efficiency optimization for


Half Wavelength
This leg connected to the braid
This leg connected to the centre conductor
Symbol
aerialsandtv.com

Fig. 8. Half-wave dipole. *Left side:* Antenna structure. *Right side:* Typical deployment.

ultra low power incident waves and the explanation of the physical phenomena behind most of the recommended efficiency optimization approaches.

This Chapter will show for example that a Schottky diode that delivers the highest efficiency at 0dBm incidence may not necessarily deliver the highest efficiency at lower power incidence e.g. –20dBm. We will therefore classify which diodes perform better at given power incidences; of course, this will also be compared to the diode manufacturers' application notes. Simulations in Agilent's ADS using SPICE and equivalent circuit models will compare the performance of few selected Schottky diodes namely; HSMS-2820, HSMS-2850, HSMS-2860, HSC-276A, and SMS7630. Moreover, the effect of the Schottky diode's junction capacitance (C_j) and junction bias resistance (R_j) on the conversion efficiency will be shown from which, special techniques for Schottky diode harmonic suppression and rectifying circuit loading for maximum efficiency point tracking will be presented.

1.3.1 The schottky diode

The classical *pn* junction diode commonly used at low frequencies has a relatively large junction capacitance that makes it unsuitable for high frequency application [3]. The Schottky barrier diode, however, relies on a semiconductor-metal junction that results in a much lower junction capacitance. This makes Schottky diodes suitable for higher frequency conversion applications like rectification (RF-to-DC conversion) [3]. We will demonstrate the effects of junction capacitance and resistance in the following sub section.

1.3.2 The effect of Schottky diode's C_j and R_j on the conversion efficiency

We have studied Schottky diode's C_j and R_j and published our results in [4]. In this work, we designed a rectifying antenna tuned for use at 2 GHz. The circuit proposed in [4] is a voltage doubler by configuration, but we replaced the amplitude detection diode (series diode) with its equivalent circuit adapted from [5]. The results of this investigation show that variation of C_j shifts the tuned frequency position and also introduces a mismatch in the resonant frequency, see Fig. 9 (left side graph). Therefore for this circuit at 2 GHz, we recommend using a Schottky diode having C_j = 0.2pF. In general, a smaller value of C_j is desirable at higher frequencies. Similarly, for R_j investigation, a smaller value is desirable for better matching at 2 GHz for example. If the R_j is increased towards 10kΩ, there is a mismatch in the resonant frequency but no shift in the frequency, see Fig. 9 (right side graph). Another approach to the study of Schottky diodes for higher frequency and efficiency rectenna design is presented in [6].



Fig. 9. Schottky diode's C_j effect (Left) and R_j effect (Right) on 2 GHz rectenna's input response.

1.4 Rectifying circuit for DTV energy harvesting

In the design of a DTV energy harvesting circuit, several basic design considerations must be paid attention to. First is the antenna; it must be wideband (covering 470 MHz to 770 MHz), horizontally polarized and omni-directional. Secondly is the rectifier; it must also be wideband, and optimized for RF-to-DC conversion for incident signal power at least -40dBm. Until recently, very few authors have published on DTV energy harvesting circuit. For the few publications, the antenna could not meet all those three requirements and a discussion on the performance of the harvesting circuit for ultra low power incidences has been neglected. In this Chapter we will present such a rectenna with conversion efficiencies above 0.4% at -40dBm, above 18.2% at -20dBm and over 50% at -5dBm signal power incidence. We will closely compare simulated and measured performance of the rectenna and discuss any observed disparities.

Agilent's ADS will be used to simulate the nonlinear behaviour of the rectifying circuit based on harmonic balance tuning methods. To simulate the multiple incident waves, a multi-tone excitation in the DTV band will be invoked. The wideband input characteristic will be achieved by the input matching inductors and capacitors.

The generic version of our proposed DTV energy harvesting circuit is shown below in Fig. 10. The implementation, however, is in two phases or scenarios as follows. First, we investigate the class called "ultra low power" DTV band rectenna. Secondly, we introduce the "medium power" DTV band rectenna.



Fig. 10. Generic version of our proposed DTV energy harvesting circuit.

INTECH

1.4.1 Ultra low power DTV rectenna

We define an ultra low power rectenna as one impinged by RF power incidence in the range between – 40dBm and -15dBm. Below in Fig. 11 is the circuit we designed; optimized for -20dBm input. The matching network is complex so as to achieve a wide band input characteristic. The fabricated circuit was well matched for the frequency range between 470 MHz and 600 MHz. More details about the circuit design can be found in [7].



Fig. 11. Ultra low power DTV band rectenna circuit. SMS7630 Schottky diode by SKYWORKS offered the best performance.

The RF-to-DC conversion efficiency for this circuit is shown in Fig. 12 where at input power equal to -40dBm, efficiency is at least 0.4% and rectified voltage equals 1mV; at -20dBm, we have at least 18.2% by measurement and a rectified voltage of 61.7mV. The level of rectified voltage is too low and disqualifies this circuit for purposes of charging capacitors or batteries to accumulate such micropower over time. Instead, boosting the low voltage to usable levels is the option available and we shall discuss this at a later stage, (in Section 2.6).



Fig. 12. Ultra low power DTV band rectenna efficiency.

1.4.2 Medium power DTV rectenna

We define a medium power rectenna as one impinged by RF power incidence in the range between – 5dBm and 0dBm. Below in Fig. 13 is the circuit we designed, optimized for -5dBm input. The matching network is simpler than as shown in section 2.4.1 since we require a narrow band around 550 MHz, with received peak power spectrum levels at least -5dBm. The circuit in Fig. 13 is a modification of Greinacher's doubler rectifier. In the circuit, C_b equals 1 pF and is used to block DC current against flowing towards the source. The shunt

INTECH

capacitance, C_{BW} equals 3300 pF and is used to set the input bandwidth. The grounding inductance, L_g equals 56nH (optimal) and is used to improve the RF-to-DC conversion efficiency by cancelling the Schottky diodes (D_b and D_D) capacitive influence; thereby minimizing the harmonic levels (harmonic suppression). We used HSMS2850 diodes in these circuits for their better performance at this level of incident power.



Fig. 13. Medium power DTV rectenna circuit. HSMS 2850 or 2820 from Hewlett-Packard offered the best performance.

The RF-to-DC conversion efficiency for this circuit is shown in Fig. 14 where at input power equal to -5dBm, we achieve at least 50% conversion efficiency by measurement, equivalent to 1.2 V DC rectified at 8.2kΩ optimal load. If we change the load to 47kΩ, over 2 V DC is rectified. This rectenna circuit is ideal for powering small sensors that run on 1.5 V or 2.2 V and draw around 6μA nominal current. If we need to power sensors demanding more power, say at least 2.2 V and 0.3mA to 1.47mA current consumption, we have to accumulate the power in a capacitor over time.



Fig. 14. Medium power DTV band rectenna efficiency.

1.4.3 DTV energy harvesting scenario and application demo

Using the medium power DTV band rectenna, connected to a gold capacitor as an accumulator, energy harvesting was initiated as shown in Fig. 15. Details about the gold capacitor, which include its charge function, backup time and leakage losses are presented in [8]. For the scenario shown in Fig. 15, the accumulated voltage by measurement i.e. capacitor charge function follows the path;

$$V_{acc} = 0.5388\ln(t) + 1.4681 \tag{6}$$

where V_{acc} is the accumulated voltage in volts and t the time in hours. It takes 4.5 hours to accumulate 2.25 V, given a rectified charging voltage and current of 2.4 V and 51μA, respectively, supplied by the DTV band rectenna instantaneously.

With this rectenna, it was possible to power up many different kinds of sensors. Sensors with ultra low power consumption were powered directly, without need to accumulate the power in a capacitor, as shown in Fig. 16.

INTECH



Fig. 15. DTV energy harvesting in a park at some line of sight from the base station.



Fig. 16. Directly powering a thermometer mounted on a car park wall (right picture). The maximum instant voltage rectification on record equals 3.7 V (left picture).

1.5 Rectifying circuit for cellular energy harvesting

Unlike in the DTV energy harvesting circuit, for cellular energy harvesting, the antenna must be narrowband (50 MHz bandwidth is acceptable), and circularly polarized even though cellular signals are vertically polarized. The circular polarization is desired to maximize the RF-to-DC conversion efficiency of the arbitrary polarization incident signals in the multipath environment. Similarly, the rectifier must be narrowband, and optimized for RF-to-DC conversion over a wide range of incident signal power.

Thinking about the potential applications for cellular energy harvesting is useful. Other authors have reported on powering a scientific calculator or a temperature sensor from GSM energy harvesting. In this Chapter we will present a special application for energy harvesting in the vicinity of the W-CDMA cellular base station and analyze the system performance by calculation from experimental data. A cellular energy harvesting circuit optimized for over 50% RF-to-DC conversion efficiency given approximately 0dBm incidence will be presented.

1.5.1 Cellular band rectenna

Below in Fig. 17 is the circuit we designed, optimized for 0dBm input. Simple input matching network is ideal since we require a narrow band response around 2.1 GHz. The optimum value for L_g equals 5.6nH, where L_g is used to improve the RF-to-DC conversion efficiency as earlier discussed. HSMS2850 diode was used.



Fig. 17. Shunt rectifier configuration for the cellular band. The matching elements L_m = 3.2nH, while C_{in} =2.5pF. The load resistance is fixed at R_L = 2.1kΩ.



Fig. 18. Conversion efficiency as a function of input power (P_{in}) in the cellular band.

INTECH

The RF-to-DC conversion efficiency for this circuit is shown in Fig. 18 where at input power equal to 0dBm, we achieve at least 60% conversion efficiency by measurement, given a 2.1kΩ optimal load. This rectenna circuit is ideal for powering small sensors that run on 1.5 V or 2.2 V and 6μA nominal current consumption. If we need to power sensors demanding more power, say at least 2.2 V and 0.3mA to 1.47mA, we have to accumulate the power in a capacitor over time as discussed in section 2.4.3 above.

1.5.2 Cellular energy harvesting application example

Environmental power generation in the neighbourhood of a cellular base station to power a temperature sensor is proposed as shown in Fig. 19 below. Electric field strength measurements in the base station neighbourhood have demonstrated the potential for environmental power generation, and the proposed temperature sensor system is designed based on these values. The rectenna described in Section 2.5.1 is used as the RF-to-DC rectifying circuit with the notched circular microstrip patch antenna (CMPA) proposed in Section 2.2.1. RF-to-DC conversion efficiency equal to 53.8% is obtained by measurement. The temperature sensor made for trial purposes clarifies the capability for temperature data wireless transmission for 20 seconds per every four hours in the base station neighbourhood.


d = 1.4m
2 GHz energy-harvesting rectenna
Temperature sensor (CT422 tested)
2.4 GHz nRF24L01P PIC controlled sensor radio

Fig. 19. Application example in the vicinity of the cellular base station.

1.6 Micropower energy harvesting management

A rectifying antenna circuit for -40dBm incident power harvesting generates 1mV at 2kΩ load, given 0.4% efficiency as presented in Section 2.4.1. At -20dBm incidence and at least 18.2% efficiency, 61.7mV is generated given a 2kΩ load [7]. The generated DC power in both of these two cases is in the μW range, hence the micropower definition. To manage such micropower, power accumulation or energy storage is required. Storage devices may either be a gold capacitor, super capacitor, thin film battery or the next generation flexible paper batteries. These storage devices have specific or standard maximum voltage and trickle charging current minimum requirements. Typically, gold capacitors have voltage ratings like 2.7 V, 5.5 V for 100 μA, 10mA or 100mA maximum discharge current. On the other hand, standard ratings for batteries are 1.8 V, 2 V, 3.3 V and 4.1 V. Therefore, to directly charge any of these storage devices from 1mV, or 61.7mV DC is impractical.

Published works have demonstrated the need for a DC-to-DC boost converter placed between the rectifying antenna circuit (rectenna) and the storage device. Recent efforts have demonstrated that a 40mV rectenna output DC voltage could be boosted to 4.1 V to trickle charge some battery. A Coilcraft transformer with turns ratio ($N_s : N_p$) equal to 100 was used in the boost converter circuit. An IC chip leading manufacturer (Linear Technology Corp., LT Journal, 2010) has released a linear DC-to-DC boost regulator IC chip capable of boosting an input DC voltage as low as 20 mV and supplying a number of possible outputs, specifically suited for energy harvesting applications. While this IC is a great milestone, readers and researchers need to understand the techniques to achieve such ICs and also the limitations that apply. In the following sub section, we will describe the methods toward designing a DC-DC boost converter, suitable for micropower RF energy harvesting.

In the design, we will attempt to clarify the parameters that affect the DC-DC conversion efficiency. For this design, Envelope simulation in Agilents's ADS is used. This simulation technique is the most efficient for the integrated rectenna and DC-DC boost converter circuits.

1.6.1 DC-DC boost converter design theory and operation

The DC-DC boost converter design theory and actual implementation are presented in this section. The inequality $V_{in} \ll V_{out}$ defines the boost operation. In this Chapter, our boost converter concept is illustrated in Fig. 20. A small voltage, V_{in} is presented at the input of the boost converter inductive pump which as a result, generates some output voltage, V_{out}. The output voltage is feedback to provide power for the oscillator. The oscillator generates a square wave, F_{OSC} that is used for gate signalling at the N-MOSFET switch.



Fig. 20. Boost converter concept.

The drain signal of the N-MOSFET is used as the switch node voltage, V_{sn} at the anode of the diode inside the boost converter circuit block. From the concept presented in Fig. 20, the actual implemented circuit is shown in Fig. 21. The circuit was designed in Agilent's ADS and fabricated for investigation by measurement.

The circuit in Fig. 21 is proposed for investigation. Since a DC-DC boost converter is supposed to connect to the rectenna's output, it therefore, becomes the load to the rectenna circuit. This condition demands that the input impedance of the boost converter circuit emulates the known optimum load of the rectenna circuit. This has the benefit of ensuring maximum power transfer and hence higher overall conversion efficiency from the rectenna input (RF power) to the boost converter output (DC power). In this investigation, as shown in [7], the optimum load for the rectenna is around 2kΩ. In general, emulation resistance R_{em} is given by



Fig. 21. The proposed boost converter circuit diagram. Designed in Agilent's ADS and fabricated for investigation by measurement.

$$R_{em} = \frac{2LT}{t_1^2 k}\left(\frac{M-1}{M}\right) \tag{7}$$

where L is the inductance equal to 330µH as shown in Fig. 20, $M = \frac{V_{out}}{V_{in}}$, T is the period of F_{OSC}, t_1 is the switch"ON" time for the N-MOSFET, and k is a constant that according to [3] is a low frequency pulse duty cycle if the boost converter is run in a pulsed mode and typically, k may assume values like 0.06 or 0.0483. With reference to (7), we select L as the key parameter for higher conversion efficiency while V_{in} = 0.4 V DC is selected as the lowest start up voltage to achieve oscillations and boost operation. Computing the DC-DC boost conversion efficiency against different values of L, we have results as shown in Fig. 22.

From the results above, L = 100µH is the optimum boost inductance that ensures at least 16.5% DC-DC conversion efficiency, given R_L = 5.6kΩ.

Now having selected the optimum boost inductance given some load resistance, the emulation resistance shown in Fig. 23 is evaluated from the ratio of voltage versus current at the boost converter circuit's input.

The results show a constant resistance value against varying inductance. In general, we can say that this boost converter circuit has a constant low input impedance around 82.5Ω. This impedance is too small to match with the optimum rectenna load at 2kΩ. This directly affects the overall RF-to-DC conversion efficiency.

INTECH

The results show a constant resistance value against varying inductance. In general, we can say that this boost converter circuit has a constant low input impedance around 82.5Ω. This impedance is too small to match with the optimum rectenna load at 2kΩ. This directly affects the overall RF-to-DC conversion efficiency.



Fig. 22. Boost inductance variation with DC-DC conversion efficiency for a 5.6 kΩ load.



Fig. 23. Boost converter's input impedance: the emulation resistance.

Another factor, which affects the overall conversion efficiency is the power lost in the oscillator circuit. Unlike the circuit proposed in [9], which uses two oscillators; a low frequency (LF) and high frequency (HF) oscillator; in Fig. 21, we have attempted to use a single oscillator based on the LTC1540 comparator, externally biased as an astable multivibrator.

The power loss in this oscillator is the difference in the DC power measured at Pin 7 (supply) to the power measured at pin 8 (output). We term this loss, L_{osc}; converted to heat or sinks through the 10MΩ load. A comparison of the oscillator power loss to the power available at the boost converter output is shown in Fig. 24.

Looking at Fig. 24; we notice that the power loss depends on whether the oscillator output is high or low. The low loss corresponds to the quiescent period where the power lost is almost negligible. However, during the active state, the lost power (power consumed by the oscillator) nearly approaches the DC power available at the boost converter output. This results in low operational efficiency.



Fig. 24. The power loss in the oscillator.

To confirm whether or not the circuit of Fig. 21 works well, we did some measurements and compared them with the calculated results. Unlike in calculation (simulation), during measurement, L = 330μH was used due to availability. All the other component values remain the same both in calculation and measurement. In Fig. 25 (left side graph) and (right side graph), we see in general that the input voltage is boosted and also that the patterns of F_{osc} and V_{sn} are comparable both by simulation and measurement. To control the duty cycle of the oscillator output (F_{osc}), and the level of ripples in the boost converter output voltage (V_{out}), we change the value of the timing capacitance, C_{tmr} in the circuit of Fig. 21. Simulations in Fig. 25 (left side graph) show that C_{tmr} = 520pF realizes a better performance i.e. nearly constant V_{out} level (very low ripple).



Fig. 25. Voltage characteristics of the developed boost converter circuit. The left side graph represents simulation while the right side graph is for measurements.

Generally, we observe that with this kind of boost converter circuit topology, it is difficult to start up for voltages as low as 61.7mV DC generated by the rectenna at -20dBm power incidence and at least 18.2% rectenna RF-to-DC conversion efficiency. Self starting is the issue for this topology at very low voltages.

At least 11.3% DC-DC conversion efficiency was recorded by measurement and is comparable to the calculation in Fig. 22. During measurement it was clearly revealed that the boost converter efficiency does depend on the value of **L** and the duty cycle derived from $\mathbf{t_1}$. To efficiently simulate the complete circuit, from the RF input to the DC output, envelope transient simulation (ENV) in Agilent's ADS was used. The (ENV) tool is much more computationally efficient than transient simulation (Tran). This simulation is appropriate for the boost converter circuit's resistor emulation task. Moreover, the boost converter's DC-DC conversion efficiency, and the overall RF-to-DC conversion efficiency can be calculated at once with a single envelope transient simulation.

In summary, though not capable to operate for voltages as low as 61.7mV DC, the proposed boost converter has by simulation and measurement demonstrated the capability to boost voltages as low as 400mV DC, sufficient for battery or capacitor recharging, assuming that the battery or the capacitor has some initial charge or energy enough to provide start-up to the boost converter circuit.

The limitations of our proposed boost converter circuit include; low efficiency, lack of self starting at ultra low input voltages, and unregulated output. To address these limitations, circuit optimization is required. Moreover, alternative approaches which employ a flyback transformer to replace the boost converter inductance must be investigated. A regulator circuit with Low Drop Out (LDO) is necessary to fix the boost converter output voltage commensurate with standard values like 2.2 V DC for example. For further reading, see [7]

2. Performance analysis of the complete RF energy harvesting sensor system

To demonstrate how one may analyze the performance of an RF energy harvesting system including its application, we extend the discussion of Section 2.5.2 to this Section. We propose a transmitter assembled as in Fig. 26 for temperature sensor wireless data transmission.



Fig. 26. The assembly and test platform for the proposed battery-free sensor transmitter.

The transmitter consists of one-chip microcomputer (MCU) PIC16F877A and wireless module nRF24L01P for the control, and MCU can be connected with an outside personal computer using ICD-U40 or RS232 cable. The wireless module operates in transmission and reception mode, and controls power supply on-off, transmitting power level, the receiving mode status, and transmission data rate via Serial Peripheral Interface (SPI). Figure 27 shows the operation flow when transmitting.


Start
PIC16F877A SPI initialize
OSC Test
No
Yes
RF: Tx mode, data rate, o/p pwr, PLL
No
Data size: address, payload, CRC
HT Test
Yes
End

Fig. 27. Operation flow during transmission.

The experimental system composition is shown in Fig. 28 to transmit acquired data by the temperature sensor with WLAN at 2.4 GHz (ISM band). An ISM band sleeve antenna is used for the transmission. Using the cellular band rectenna shown and discussed in Section 2.5.1, at least 3.14 V is stored in the electric double layer capacitor over a period of four hours. To harvest a maximum usable power for the overall system, we charge the capacitor up to 5V. The operation voltage for the wireless module presented in Fig. 26 above is between 1.9V and 3.6V.

The signal was transmitted from the wireless module while a sleeve antenna, same like the one for transmission was used with the spectrum analyzer and the reception experiment was performed. Received signal level equal to -43.4dBm was obtained at a distance 3.5m between transmitter and reception point. The capacitor's stored voltage was used to supply the wireless module in the above-mentioned experiment. Successful transmission was possible for 5.5 minutes after which, the capacitor terminal voltage decreased from 3.16V to 1.47V, and the transmission ended. The sending and receiving distance of data can be estimated to be about 10m when the sensitivity of the receiver is assumed to be -60dBm, given 0dBm maximum transmit power.

Hereafter, the overall system examination is done by environmental power generation using the transmitted electric waves from the cellular phone base station, proposed based on the above-mentioned results. First of all, the power consumption shown in Fig. 29 is based on the fact that 120mW (5V, 24mA) is saved in the electric double layer capacitor by environmental power generation, achieved by calculation as discussed earlier.


f = 2.4 GHz (signal freq.)
PIC controlled Nordic radio Tx
d = 1.5 m
S/A
SMA T-joint
Handheld spectrum analyzer
S/A
Fixed spectrum analyzer

Fig. 28. Indoor measurement setup for received traffic from the sensor radio transmitter.


120 mW
Power grid
Max
Input
Threshold
5 V – 3.3 V
MCU
(8 mA)
2 V
Decision block
1.5 V (0.3 mA) max
(Temp.) Sensor
1.3 V (6 A) min
2 V
ISM radio
(Tx = 11.3 mA
Rx = 12.3 mA
Standby = 22 A)
1.4 V

Fig. 29. Power management scheme for the cellular energy-harvesting sensor node.

The sensor data packet is transmitted wirelessly in ShockBurst mode for energy efficient communication. The data packet format includes a pre-amble (1 byte), address (3 bytes), and the payload i.e. temperature data (1 byte). The flag bit is disregarded for easiness, and cyclic redundancy check (CRC) is not used.

The operation of the proposed system is provisionally calculated. When the rectenna is set up in the place where power incidence of 0dBm is obtained in the base station neighbourhood (as depicted in Section 2.5.2), an initially discharged capacitor accumulates up to 3.3V by a rectenna with 53.8% conversion efficiency (presented in Section 2.5.1). At this point, it takes 1.5 minutes to start and to initialize a wireless module, and the voltage of the capacitor decreases to 2V. This trial calculation method depends on the capacitor's back up time discussed in [8]. After this, when the wireless module is assumed to be in sleep mode, the capacitor is charged by a 0.28mA charging current for four hours whereby the capacitor's stored voltage increases up to 5V. The power consumption in the sleep mode or standby is 33μW (1.5V, 22μA).

When the wireless module starts, after data transmission and the confirmation signal is sent, the voltage of the capacitor decreases by 0.6V, and consumes the electric power of 7.4mW.

The voltage of the capacitor decreases to 2V when 3.2mW is consumed to the acquisition of the sensor data, and the operation time of MCU is assumed to be one minute to the data storage in the wireless module etc. As for the capacitor voltage, when the wireless module continuously transmits data for 20 seconds, it decreases from 2V to 1.4V and even the following operation saves the electric power. Therefore, a temperature sensing system capable of transmitting wireless data in every four hours becomes feasible by environmental power generation from the cellular phone base station if we consider intermittent operation by sleep mode.

3. Conclusion

This Chapter has given an overview of the present energy harvesting sources, but the focus has stayed on RF energy sources and future directions for research. Design issues in RF energy harvesting have been discussed, which include low conversion efficiency and sometimes low rectified power. Solutions have been suggested by calculation and validated by measurement where possible, while highlighting the limitations of the proposed solutions. Potential applications for both DTV and cellular RF energy harvesting have been proposed and demonstrated with simple examples. A discussion is also presented on the typical performance analysis for the proposed RF energy harvesting system with sensor application.

4. Acknowledgment

The authors would like to thank Prof. Apostolos Georgiadis of Centre Tecnològic de Telecomunicacions de Catalunya (CTTC, Spain) for the collaboration on the design and development of the DC-DC boost converter circuit. Further thanks go to all those readers who will find this Chapter useful in one way or the other.

5. References

[1] Keisuke, T.; Kawahara, Y. & Asami, T. (2009). *RF Energy Intensity Survey in Tokyo..,* (c)2009 IEICE, B-20-3, Matsuyama-shi, Japan

[2] Mikeka, C.; Arai, H. (2011). *Dual-Band RF Energy-Harvesting Circuit for Range Enhancement in Passive Tags,* (c)2011 EuCAP, Rome, Italy

[3] Pozar, D. (2005). *Microwave Engineering,* Wiley, ISBN 978-0-471-44878-5, Amherst, MA, USA

[4] Mikeka, C.; Arai, H. (2010). Techniques for the Development of a Highly Efficient Rectenna for the Next Generation Batteryless System Applications, *IEICE Tech. Rep.,* pp. 101-106, Kyoto, Japan, March, 2010

[5] http://www.secomtel.com/UpFilesPDF/PDF/Agilent/PDF_DOCS/SKYDIODE/ 03_SKYDI/HSMS2850.PDF (Last accessed on 13 July, 2011)

[6] McSpadden, J. et al., H. (1992). Theoretical and Experimental Investigation of a Rectenna Element for Microwave Power Transmission, *IEEE Trans., on Microwave Theory and Tech., Vol. 40, No. 12.,* pp. 2359-2366, Dec., 1992

[7] Mikeka, C.; Arai, H. ; Georgiadis A. ; and Collado A. (2011). DTV Band Micropower RF Energy-Harvesting Circuit Architecture and Performance Analysis, *RFID-TA Digest,* Sitges, Spain, Sept., 2011

[8] Mikeka, C.; Arai, H. (2009). Design of a Cellular Energy-Harvesting Radio, *Proc. 2 nd European Wireless Technology Conf.,* pp. 73-76, Rome, Italy, Sept., 2009

[9] Popovic Z., et al., (2008). Resistor Emulation Approach to Low-Power RF Energy Harvesting, *IEEE Trans. Power Electronics, Vol. 23, No. 3*, 2008



Sustainable Energy Harvesting Technologies - Past, Present and Future

Edited by Dr. Yen Kheng Tan

ISBN 978-953-307-438-2
Hard cover, 256 pages
Publisher InTech
Published online 22, December, 2011
Published in print edition December, 2011

In the early 21st century, research and development of sustainable energy harvesting (EH) technologies have started. Since then, many EH technologies have evolved, advanced and even been successfully developed into hardware prototypes for sustaining the operational lifetime of low?power electronic devices like mobile gadgets, smart wireless sensor networks, etc. Energy harvesting is a technology that harvests freely available renewable energy from the ambient environment to recharge or put used energy back into the energy storage devices without the hassle of disrupting or even discontinuing the normal operation of the specific application. With the prior knowledge and experience developed over a decade ago, progress of sustainable EH technologies research is still intact and ongoing. EH technologies are starting to mature and strong synergies are formulating with dedicate application areas. To move forward, now would be a good time to setup a review and brainstorm session to evaluate the past, investigate and think through the present and understand and plan for the future sustainable energy harvesting technologies.

How to reference
In order to correctly reference this scholarly work, feel free to copy and paste the following:

Chomora Mikeka and Hiroyuki Arai (2011). Design Issues in Radio Frequency Energy Harvesting System, Sustainable Energy Harvesting Technologies - Past, Present and Future, Dr. Yen Kheng Tan (Ed.), ISBN: 978-953-307-438-2, InTech, Available from: http://www.intechopen.com/books/sustainable-energy-harvesting-technologies-past-present-and-future/design-issues-in-radio-frequency-energy-harvesting-system

INTECH
open science | open minds

InTech Europe
University Campus STeP Ri
Slavka Krautzeka 83/A
51000 Rijeka, Croatia
Phone: +385 (51) 770 447
Fax: +385 (51) 686 166
www.intechopen.com

InTech China
Unit 405, Office Block, Hotel Equatorial Shanghai
No.65, Yan An Road (West), Shanghai, 200040, China
中国上海市延安西路65号上海国际贵都大饭店办公楼405单元
Phone: +86-21-62489820
Fax: +86-21-62489821

SCIENTIFIC REPORTS

OPEN

SUBJECT AREAS:
ELECTRICAL AND ELECTRONIC ENGINEERING
ELECTRONIC AND SPINTRONIC DEVICES

Received
4 September 2014

Accepted
19 February 2015

Published
7 May 2015

Correspondence and requests for materials should be addressed to N.S. (negin.shariati@rmit.edu.au)

Multi-Service Highly Sensitive Rectifier for Enhanced RF Energy Scavenging

Negin Shariati, Wayne S. T. Rowe, James R. Scott & Kamran Ghorbani

School of Electrical and Computer Engineering, RMIT University, Melbourne, VIC 3001, Australia.

Due to the growing implications of energy costs and carbon footprints, the need to adopt inexpensive, green energy harvesting strategies are of paramount importance for the long-term conservation of the environment and the global economy. To address this, the feasibility of harvesting low power density ambient RF energy simultaneously from multiple sources is examined. A high efficiency multi-resonant rectifier is proposed, which operates at two frequency bands (478–496 and 852–869 MHz) and exhibits favorable impedance matching over a broad input power range (−40 to −10 dBm). Simulation and experimental results of input reflection coefficient and rectified output power are in excellent agreement, demonstrating the usefulness of this innovative low-power rectification technique. Measurement results indicate an effective efficiency of 54.3%, and an output DC voltage of 772.8 mV is achieved for a multi-tone input power of −10 dBm. Furthermore, the measured output DC power from harvesting RF energy from multiple services concurrently exhibits a 3.14 and 7.24 fold increase over single frequency rectification at 490 and 860 MHz respectively. Therefore, the proposed multi-service highly sensitive rectifier is a promising technique for providing a sustainable energy source for low power applications in urban environments.

AMBIENT energy harvesting is attracting widespread interest as it has the potential to provide a sustainable energy source for future growth and protection of the environment. Considerable research effort has been directed toward low-profile, low-power, energy efficient and self-sustainable devices aiming to harvest energy from inexhaustible sources such as solar energy, thermal, biomass, mechanical sources (e.g. wind, kinetic, vibration, and ocean waves) wastewater, and microwave energy. A thorough set of reviews is given in the literature[1–4]. Among these green energy sources, there has been a growing interest for radio frequency (RF) energy scavenging, as the availability of ambient RF energy has increased due to advancements in broadcasting and wireless communication systems. Furthermore, the development of wireless power transmission (WPT) technologies[5] that allow micro sensors[6], mobile electronic devices[7], wireless implantable neural interfaces[8] and far-field passive RFID (Radio-Frequency Identification) systems[9–11] to operate without batteries has triggered impetus for RF energy harvesting.

Efficient RF energy harvesting is a very challenging issue, as it deals with the very low RF power levels available in the environment. Furthermore, the scavengeable power level can vary unpredictably, depending on several factors such as the distance from the power source, the transmission media, the telecommunication traffic density and the antenna orientation. The majority of available literature on RF rectification has been dedicated to narrowband rectennas, which essentially operate at a single frequency and hence provide low DC output power[12,13]. Various topologies, such as voltage doublers or multipliers have been employed in order to increase the RF to DC conversion efficiency and the output DC voltage for specific applications[14–16]. However, from an ambient RF scavenging perspective, harvesting energy from various available frequencies could maximize power collection and hence increase the output DC power. Ultra-wideband and broadband rectenna arrays have been proposed as a potential solution[17,18]. However in some cases, simulation and experimental results were not provided to demonstrate the findings[17]. A broadband rectenna consisting of a dual-circularly polarized spiral rectenna array operating over a frequency range of 2–18 GHz was demonstrated[18]. The rectified DC power was characterized as a function of DC load, RF frequency and polarization for power densities between 10^{-5} and 10^{-1} mW/cm^2. However, the proposed rectenna was matched at a single input RF power level for a specified load resistance for the characterization. Also, due to the low Q value of the rectifier circuit, the conversion efficiency was a fraction of 1% at −15.5 dBm. From a design point of view, while it is relatively easy to achieve a broadband antenna, it is very challenging to realize a broadband rectenna due to the non-linearity of the rectifier impedance with input power across the frequency band[19].

To address this, a promising approach is to use a dual-band or multi-band configuration. This can maximize the power conversion efficiency (PCE) at the specific frequencies where the maximum ambient signal level is available. Various dual-band RF energy harvesting systems has been demonstrated[20–24], however a large signal analysis of the rectifier was commonly not provided over a broad input power range. A dual-band RF energy harvesting using frequency limited dual-band impedance matching has been proposed[20] and the PCE was shown over a high power range of 0 to 160 mW, however it was only matched at a single input power level (10 dBm). A CMOS dual-narrowband energy harvester circuit was modeled at environmental power levels[21]. Again, the rectifier efficiency was demonstrated with only single input power levels of −19 and −19.3 dBm at 2 GHz and 900 MHz respectively, and a large signal analysis was not presented. A compact dual-band rectenna operating at 915 MHz and 2.45 GHz has been demonstrated[22] and the PCE was shown for input power levels of −15, −9 and −3 dBm. However, the reflection coefficient was evaluated at a single incident power level. Furthermore, the efficiency results with dual-tone excitation simultaneously and single-tone excitation (at 915 MHz) are very similar, hence the impact of applying a dual-band technique does not demonstrate a clear advantage over a single band. A dual-frequency rectenna for WPT has been proposed[23] which achieved a conversion efficiency of 84.4% and 82.7% at 2.45 and 5.8 GHz with a high input power level of 89.84 and 49.09 mW respectively. These power levels far exceed ambient levels in the environment[19]. A conformal hybrid solar and electromagnetic (EM) energy harvesting rectenna has been presented[24] and the PCE was provided with −30 to 5 dBm input power, achieving an efficiency up to 40% at 1.85 GHz for higher input power levels (above −5 dBm). However the reflection coefficient was not provided at low input power range.

A multi-resonant rectenna that uses a multi-layer antenna and rectifier has been evaluated for a −16 dBm to +8 dBm RF received power level, but the rectifier circuit layout and large signal analysis were not provided to clarify the findings[25]. Furthermore, a rectenna for triple-band biotelemetry communications has been proposed using a triple-band antenna and single frequency rectifier[26]. However, this rectenna is not suitable for RF energy scavenging due to the low efficiency at lower input power levels. Another triple band rectenna presented an RF-DC efficiency over the input power range of −14 to +20 dBm[27], however the reflection coefficient results were only evaluated at a single input power level. This rectenna was shown to harvest 7.06 μW of DC power from three sources simultaneously at a high input power level of +10 dBm. A multi-band harvesting system has also been proposed where four individual harvesters are designed to cover four frequency bands[28]. However, a large signal analysis was not provided over a broad input power range. Furthermore, the proposed harvesting system has a minimum sensitivity of −25 dBm, whilst in a real environment more sensitive systems are required as the available RF power levels are very low[19].

Tunable impedance matching networks have been demonstrated in order to collect RF signals from various sources and convert them to DC power[29]. However from an application point of view, this is still single frequency rectification and it is not widely applicable to environmental RF energy scavenging where the available power is very low.

In order to increase the amount of RF energy scavenged by a rectenna, it is crucial to identify and harvest multiple ambient frequency sources over their realistic available energy range. Our previous research has demonstrated the feasibility of RF energy harvesting through RF field investigations and maximum available power analysis in metropolitan areas of Melbourne, Australia[19]. The maximum available power for different frequency bands based on antenna aperture and number of antennas in a given collection area was analyzed. Measured results and analysis indicated that cellular systems and broadcast sources are well suited to harvesting, with scavengeable RF power ranging from −40 to −10 dBm. This identifies two important considerations in the design of efficient rectenna for RF energy harvesting: the scavengeable ambient RF power sources available, and the significant variance of this power.

The RF to DC rectifier solutions proposed in recent literature have focused on maximizing the system efficiency at a given, and often quite high, input power level. This neglects the issues related to input power variation which can lead to unexpected variations in the matching network due to diode non-linearity. Also, the scavangeable levels of ambient RF power have been shown to be orders of magnitude lower. Therefore, based on our previous research outcomes and recommendations[19], an efficient power harvesting solution could encompass a multi-band matching circuit at the specific frequencies where maximum signal power is available, enabling greater power harvesting due to the combination of RF signals. This also results in a higher power being fed to a single rectifier, utilizing the diode function more efficiently.

This paper presents an RF energy harvesting method that can scavenge a wide range of ambient power levels which are orders of magnitude lower than previous reported techniques in the literature. An efficient dual resonant rectifier circuit is proposed, matched to a 50 Ω input port at 490 and 860 MHz over a broad low input RF power range from −40 to −10 dBm. The proposed dual resonant matching network operates efficiently at two identified harvesting frequency bands over a wide input power range, maximizing DC power by scavenging two sources simultaneously.

The remainder of this paper is organized as follows. First, the key results for the reflection coefficient and output DC power are presented. Subsequently, the Discussion section summarizes the results and demonstrates their potential implications, the limitations of this study, open questions and future research. Finally, the Method section describes the proposed rectifier design.

Results

A dual resonant rectifier was fabricated on a 1.58 mm FR-4 substrate with a dielectric constant $\varepsilon_r \approx 4.5$ and a loss tangent $\delta \approx 0.025$. These substrate parameters were measured using the Nicolson-Ross method[30] so accurate values could be used in the rectifier design. A photograph of the fabricated dual resonant rectifier is shown in Fig. 1 which depicts input RF port, dual-band matching network lumped components, Schottky diodes and the output terminal. The performance of the rectifier was verified by measuring the input reflection properties, and the output power was calculated from the measured output DC voltage for the input powers from −40 to −10 dBm.

Reflection Coefficient. The $|S_{11}|$ of the rectifier was evaluated using a vector network analyzer (VNA). The VNA was re-calibrated for each input power level. Figure 2 compares the simulated and measured $|S_{11}|$ versus frequency for the dual resonant rectifier circuit at four different input power levels from −40 to −10 dBm. The measured results show very good agreement to the simulations. Slightly higher reflection was observed for the resonant frequencies at the lower part of the input power range (due to the diode characteristics). However, the proposed rectifier circuit is well-matched ($|S_{11}| < -10$ dB) at the desired frequency bands of



Figure 1 | **Fabricated rectifier prototype.**



Figure 2 | Simulated and measured $|S_{11}|$ as a function of frequency and input RF power for the proposed dual resonant rectifier circuit. (a) −10 dBm. (b) −20 dBm. (c) −30 dBm. (d) −40 dBm.

478–496 MHz and 852–869 MHz over the broad range of input powers from −40 to −10 dBm. The small difference between simulation and measurement is due to the parasitic extraction accuracy.

Output DC Power. In the frequency domain, the Harmonic Balance method of analysis provides a comprehensive treatment of a multispectral problem[18]. The method intrinsically takes into account the DC component and a specified number of harmonics, while allowing the ability to specify the source impedance and harmonic terminations. A Harmonic Balance simulation was used to numerically evaluate the output DC voltage of the dual resonant rectifier for both a single and two tone input. The output DC voltage across the load resistor was also measured and used to calculate output DC power. Measurements were performed using a Wiltron 68247B synthesized signal generator as a RF power source for the rectifier circuit. Recording of the output DC voltage across the load resistance was achieved with a Fluke 79III digital voltage meter. The RF source power was initially set at −10 dBm, and decreased in 2 dB steps. In the dual-band measurement case, two RF signal generators were fed to the rectifier circuit simultaneously via a power combiner.

The simulation and measurement results for single and dual input tones are summarized in Fig. 3(a) and (b). A measured DC voltage of 772.8 mV is achieved with two simultaneous input tones at an input power of −10 dBm. For single tone measurements, DC voltages of 436 mV and 286 mV at 490 MHz and 860 MHz respectively are produced. The comparison between the 490 and 860 MHz single rectifiers highlights the impact of the input frequency on the PCE. A higher amount of DC voltage can be generated at the lower frequency. This difference comes from decreasing diode performance at the higher frequency due to the higher junction capacitance of the diode[31].

Importantly, a slightly higher DC voltage can be generated with the dual resonant rectifier as compared to the sum of output voltage from the two single bands, particularly at the lower input power levels as can be seen in Fig. 3(b) which shows the lower power section of Fig. 3(a) in more detail. By maximizing power collection from various sources of different frequencies and delivering the combined power to the rectification circuit, the diode conversion efficiency is enhanced which results in a higher level of rectified voltage. Figure 4 compares the simulated and measured output DC power for the dual resonant rectifier circuit with both single and dual input tones. A measured DC power of 17.3 μW and 7.5 μW can be generated at 490 MHz and 860 MHz respectively with a single tone input of −10 dBm (100 μW). This represents true efficiencies of 17.3% and 7.5% for the individual single band rectification (see Fig. 5). However, the measured DC output power with two concurrent input tones of −10 dBm is 54.3 μW which corresponds to an effective efficiency of 54.3% for the dual-band rectifier (see Fig. 6). This represents a 3.14 and 7.24 times increase in output DC power over the single tone excitation at 490 MHz or 860 MHz respectively. This trend is evident down to low input power levels (around 40 μW). Furthermore, there is a significant increase in the PCE of the dual resonant rectifier for lower input power levels (<40 μW).



Figure 3 | **Output DC voltage as a function of input RF power for single input tone at both 490 MHz and 860 MHz and for dual input tones (a) with −40 to −10 dBm input RF power (b) with −40 to −25 dBm input RF power.** (This power range is associated with the signal source).



Figure 4 | **Output DC power as a function of input RF power for single and dual input tones.**



Figure 5 | **RF to DC conversion efficiency as a function of input RF power for single band rectification.**

Here, the effective efficiency is defined as the ratio of output DC power to the available input RF power rather than the power delivered to the diodes (equation (1)). The available power level is associated with the signal source. For the single resonator, the available input power is −10 dBm and the delivered power is also −10 dBm (assuming no loss). However, by creating a dual resonant matching network the power delivered to the diodes is −7 dBm (combined total input power from two signal generators) but the available power is still −10 dBm.

$$\eta = \frac{p_o}{p_i} = \frac{\left(\frac{V_o^{2}}{R_L}\right)}{p_i} \qquad (1)$$

Therefore, combining input RF signals into a single rectification stage results in high sensitivity rectifier, which is widely applicable to



Figure 6 | **Effective RF to DC conversion efficiency as a function of input RF power for dual resonant rectification.**

Table 1 | Rectifier performance comparison

Ref.	Technology	Measured Efficiency (%)	RF power variation (in PCE evaluation)	Rectification Technique
13	Schottky diode	82@50 mW	N/A	Single resonator
16	Schottky diode	44@−10 dBm	N/A	Single resonator
18	Schottky diode	20@0.07 mW/cm^2 0.1@5×10^{-5} mW/cm^2	10^{-5} to10^{-1} mW/cm^2	Broad band
20	Schottky diode	77.13@22 dBm (158.49 mW)	0 to 160 mW	Dual resonator
21	CMOS	9.1@−19.3 dBm (900 MHz) 8.9@−19 dBm (2 GHz)	N/A	Dual resonator
22	Schottky diode	37 (915 MHz)@−9 dBm 30 (2.45 MHz)@−9 dBm	−40 to 0 dBm	Dual resonator
23	Schottky diode	84.4@89.84 mW (2.45 GHz) 82.7@49.09 mW (5.8 GHz)	0 to 100 mW	Dual resonator
27	Schottky diode	80@10 dBm (940 MHz) 47@8 dBm (1.95 GHz) 43@16 dBm (2.44 GHz)	−14 to 20 dBm	Triple resonator
29	Schottky diode	50@−5 dBm	−25 to 0 dBm	Dual resonator with tunable input response
This work	Schottky diode	54.3@−10 dBm 11.25@−18 dBm (490 and 860 MHz)	−40 to −10 dBm	Dual resonator

Table 2 | Environmental measurement results

Suburb	Available frequencies (MHz)	Respective available RF power (dBm) [μW]	Measured DC power (μW)
Bayswater	486, 488, 489, 490, 491, 867, 868, 869, 870, 871, 872, 873, 874	−19[12.5], −20[10], −17[19.95], −15[31.62], −22[6.3], −37[0.199], −37[0.199], −30[1], −24[3.98], −20[10], −30[1], −37[0.199], −40[0.1]	39.38
Bentleigh	491, 492, 494, 495, 865, 866, 867, 868, 869, 870, 871	−12[63.09], −46[0.02], −42[0.063], −57[0.001], −27[1.99], −27[1.99], −30[1], −37[0.199], −40[0.1], −40[0.1], −41[0.07]	30.9
RMIT University (Melbourne CBD)	487, 488, 489, 490, 491, 851, 861, 862, 866, 867, 868, 869	−30[1], −22[6.3], −29[1.25], −22[6.3], −20[10], −23[5.01], −21[7.94], −21[7.94], −30[1], −35[0.31], −40[0.1], −40[0.1]	14.5

real environmental RF energy scavenging. This multi-band technique can provide higher DC power than combining two separate single frequency rectifier circuits operating at the same frequencies. This is due to the fact that harvesting RF energy from various available sources simultaneously increases the delivered power to the rectifier, which improves the diode conversion efficiency and consequently enhances the output DC power. Table 1 summarizes this work as compared to previous published work.

In order to provide a realistic scenario for the proposed dual-band rectifier, measurement results were taken in three suburbs of Melbourne, Australia, congruent with our previous research outcomes[19]. Table 2 summarizes these environmental measurement results. It should be noted that the lower band (478–496 MHz) has a 3.67% fractional bandwidth and the higher band (852–869 MHz) has around 2% fractional bandwidth. Hence, various RF frequencies from different sources can be harvested within these two bands. The environmental measurement results demonstrate the feasibility of harvesting ambient EM energy from multiple sources simultaneously.

Discussion

The feasibility of harvesting ambient EM energy from multiple sources simultaneously is investigated in this paper. The proposed dual resonant rectifier operates at two frequency bands (478–496 and 852–869 MHz), which are used for broadcasting and cellular systems respectively. The dual resonant rectifier exhibits favorable impedance matching over a broad input power range (−40 to −10 dBm) at these two bands. The achieved sensitivity and dynamic range demonstrate the usefulness of this innovative low input power rectification technique. Simulation and experimental results of input reflection coefficient and rectified output power are in excellent agreement. The measurement results demonstrate that a two tone input to the proposed dual-band RF energy harvesting system can generate 3.14 and 7.24 times more power than a single tone at 490 or 860 MHz respectively, resulting in a measured effective efficiency of 54.3% for a dual-tone input power of −10 dBm. It is evident that this dual resonant rectification technique increases the RF to DC effective conversion efficiency, and hence the recoverable DC power for low power applications. Furthermore from a design and economic perspective, utilizing a large number of components (e.g. antennas, diodes) to realize individual rectifier circuits for each frequency band creates additional expense. In order to provide more realistic measurement results, the proposed dual-band rectifier was tested in three suburbs of Melbourne, Australia. Therefore, this dual-band technique offers a simple and cost-effective solution which is of paramount importance for environmental power harvesting systems. This innovative technique has the potential to generate a viable perpetual energy source for low power applications in urban environments.

Limitation of the study, open questions and future work

Utilizing diodes which are more suitable to low power applications ($P_i < -20$ dBm) could increase the voltage sensitivity, resulting in a higher RF-DC conversion efficiency[32]. Applying a power optimized waveform excitation to the rectifier circuit in these frequency bands, a higher amount of DC power can be generated when compared with a single and dual tone excitations with the same input power[33,34]. However this technique is not applicable to energy harvesting where the input waveform is arbitrary.

Utilizing our proposed dual resonant rectification technique to combine resonant circuits for any other arbitrary frequency bands could lead to PCE improvement, provided that suitable diodes for the desired frequency bands are selected. Note that by increasing the operating frequency the rectification performance degrades due to


Broad Band/ Multi Band/ Dual Band Antenna
Multi Band Matching Network
Rectification Device
Load

Figure 7 | **General block diagram of the RF energy harvesting system.**

the higher junction capacitance of the diode. Hence, lower output voltage is expected at higher frequency bands.

It is the object of our future work to design a multi-band rectenna array for enhanced RF energy harvesting. Furthermore, increasing the bandwidth, sensitivity and efficiency will also be investigated.

Methods

The major goal in designing an efficient RF harvesting system is to produce high DC output power. Toward this goal, a high sensitivity rectifier is crucial for optimum RF scavenging. A significant factor governing the sensitivity of a rectifier is the threshold voltage of the diode used for rectification. The diode must be able to "switch on" for very low ambient energy levels.

To address this sensitivity issue, a system that scavenges power from multiple frequency bands and combines them to activate a rectification circuit is proposed. The general block diagram of the proposed system is depicted in Fig. 7. Various environmental RF energy sources of different frequencies are collected by an appropriately designed antenna, and delivered to the rectification circuit via a multi-band matching network. The rectification circuit converts the combination of RF signals into DC power for low-power applications. The embodiment in this paper realizes a dual resonant matching circuit as a transition between a 50 Ω nominal antenna output and the non-linear rectification device at 490 and 860 MHz. Based on the Australian Radiofrequency Spectrum Plan[35], these bands are allocated to broadcasting services and cellular systems.

Device Selection. Due to the very low ambient power available in a real environment[19], a very low threshold voltage rectification device is required in order to increase sensitivity. For this reason, Schottky diodes (GaAs or Si) are commonly employed for RF energy harvesting. In this work, a microwave Schottky detector HSMS2820 ($C_{j0} = 0.7$ pF, $R_s = 6\ \Omega$, $I_s = 2.2e^{-8}$ A) is chosen due to its excellent high frequency performance, low series resistance (R_s) and junction capacitance (C_j), and low threshold voltage with high-saturation current[31]. This low threshold voltage (0.15–0.3 V) supports rectification at low input power levels.

Proposed Rectifier Design. In order to design an efficient RF harvesting system, the non-linearity of the rectifier impedance with frequency and input power should be matched to the 50 Ω output of the antenna at the desired frequency bands. Therefore, the diode input impedance as a function of frequency and different power levels were calculated and analyzed[36]. In order to match the input impedance of the rectifier to the 50 Ω output of the antenna, the total load impedance for different input power and frequencies should be determined. A circuit consisting of a pair of Schottky Barrier Diodes (SBD) terminated with a load resistor ($R_{Load} = 11$ kΩ) and an output bypass capacitor ($C2 = 6.8$ pF) was simulated using Agilent ADS software. Figure 8 shows the proposed geometry of the voltage-doubler topology[31,37]. The voltage doubler rectifier structure is employed for the design of the RF-DC power conversion system as this topology is well suited to low power rectification. The resistor and capacitor at the output will filter high frequencies. The high load resistor (11 kΩ) was chosen to observe a reasonable output voltage at very low currents. Using Large Signal S-Parameters analysis in Agilent ADS software, the load impedance and bypass capacitor were determined and optimized.

The voltage doubler rectifier in Fig. 8 consists of a peak rectifier formed by *D2* and bypass capacitor *C2* (6.8 pF) and a voltage clamp formed by *D1* and *C1* (total capacitance of the transmission lines and diode's parasitic capacitance (C_p)). In the negative phase of the input, current flows through *D1* while *D2* is cutoff. The voltage across *D1* stays constant around its threshold voltage and the voltage at node 1 is charged to $-V_{th1}$ (where $-V_{th1}$ is the threshold voltage of the *D1*). At the negative peak, the voltage across *C1* is $V_{amp} - V_{th1}$ (where V_{amp} is the amplitude of the input signal). In the positive phase of the input, current flows through *D2* while *D1* is cutoff. The voltage across *C1* remains the same as the previous phase because it has no way to discharge. At the positive peak, the voltage across *D1* is $2V_{amp} - V_{th1}$. Since *D2* is conducting current to charge *C2*, the voltage at the output is $V_{out} = 2V_{amp} - V_{th1} - V_{th2}$.

The DC equivalent circuit of the SBD is a voltage source in series with the junction resistor R_j which is obtained by differentiating the diode voltage–current characteristic and is given by equation (2)[31,38]:

$$R_j = \frac{nKT}{q(I_s + I_b)} \tag{2}$$

Where n is the diode ideality factor, *K* is the Boltzmann's constant, *T* is the temperature in degrees Kelvin, *q* is the electronic charge, I_s is the diode saturation current and I_b is the external bias current. At low power levels, the saturation current is very small ($I_s = 2.2\ e^{-8}$ A) and for a zero-biased diode, $I_b = 0$. Therefore, the resulting value of junction resistance at room temperature is approximately 1.7 MΩ. Since, the saturation current is highly temperature dependent, R_j will be even higher at lower temperatures which tends to decrease the output voltage. As the input power increases, some circulating rectified current will cause a drop in the value of R_j and this phenomenon will increase the value of the DC output voltage. Furthermore, it is worth to highlight that the rectified current produced by the first diode (*D1*) in Fig. 8 constitutes the external bias current of the second diode (*D2*) which will help to reduce the R_j and hence the detection sensitivity is improved. Therefore, depending on the amount of available bias current, R_j is varying (equation (2)), hence the matching network is changing which impacts the amount of delivered power to the diode and results in different values of PCE.

A Schottky barrier diode can be modeled by the linear equivalent circuit shown in Fig. 9, where L_p and C_p are the diode's parasitic inductance and capacitance respectively due to packaging ($L_p = 2$ nH and $C_p = 0.08$ pF) which are generally unwanted[39]. This linear model is used for determining the diode impedance at a given input power.

The diode impedance analyzed using a Harmonic Balance simulator and a non-linear model of the diodes over the frequency range of 400 to 900 MHz at various input power levels (Fig. 10). Due to the large junction resistor at low input RF power levels, the rectification device is turned off in absence of an appropriate matching network. Large Signal S-parameter analysis was conducted and higher input power (associated with the signal source) is applied directly to the Schottky diodes configuration of Fig. 8 which does not include a matching network in order to turn on the diodes (reduce the value of R_j) and extract approximate input impedance value as our starting point in design of a matching network. As it can be seen in Fig. 10, with increasing the source power, the diode impedance is varying and it is beginning to switch on. Hence, the input impedance needs to be determined when the diode is



Figure 8 | **Schematic of a voltage-double rectifier without matching network.**



Figure 9 | **HSMS 2820 Schottky diode equivalent circuit.**

turned on to realize the matching network for a rectifier circuit. Obviously, in the presence of an appropriate matching network the rectification device can be turned on at lower power levels, whilst in the absence of a matching network a higher input power should be applied to switch on the diode. (Note that, with an unmatched rectifier the total applied input power from the signal source cannot be delivered to the diode due to the high reflection in the circuit).

The aim is to match the input impedance of the device to 50 Ω at 478–496 MHz and 852–869 MHz bands over a broad range of input RF powers. The procedure commences by matching the diode input impedance at high unmatched source power and shifting the diode input impedance at various power levels to within the voltage standing wave ratio (VSWR) <2 circle on the Smith chart. This procedure assumes that diode input impedance does not drastically change in this low power range. The simulation results of Fig. 10 prove that this is the case.

In order to provide maximum power transfer from the antenna to the rectifier circuit, a dual resonant rectifier network is designed as a transition between a 50 Ω nominal antenna output and the non-linear rectification device over the power range of −40 to −10 dBm (see Fig. 11). Hence, a coupled-resonator structure with both series and shunt resonators is designed to achieve a dual-band network[40]. The linear equivalent circuit model of the SBD chip[39] has been taken into consideration to design the dual band match at the desired frequency bands. In Fig. 11, $C_{equivalent}$ represents the total capacitance of the diodes and bypass capacitor and $L_{equivalent}$ is the overall parasitic inductance of the diodes. The series *L-C* resonator ($L4 + L_{equivalent}$ and $C_{equivalent}$) and the parallel L-C resonator (*C3* and *L3*) define the dual resonant circuit. The series resonator corresponds closely to the higher band specification of 852–869 MHz, whilst the parallel resonator approximates the lower 478–496 MHz band. A minimum number of components were used in order to reduce the ohmic and parasitic losses.

The resonant frequency of each sub-circuit was determined in isolation using the following equation:

$$f = \frac{1}{2\pi\sqrt{LC}} \quad (3)$$

The 852–869 MHz band resonator circuit components were calculated. Here, $C = C_{equivalent} \cong 1.3$ pF consists of the combination of the bypass capacitor (6.8 pF) and



Figure 10 | Diode input impedance calculated with Large Signal S-parameter analysis over the frequency range of 400 to 900 MHz with various unmatched input power levels.



Figure 11 | Schematic of a dual resonant rectifier (optimized parameters of the chip components are: $L1 = 3.9$ nH, $C1 = 0.2$ pF, $L2 = 12$ nH, $C2 = 1.8$ pF, $L3' = 3.9$ nH, $C3' = 7.5$ pF, $L4' = 11.6$ nH, $L_{equivalent} \cong 1$ nH, $C_{equivalent} \cong 1.3$ pF).



Figure 12 | Dual resonant impedance matching with −40 to −10 dBm input RF power. (a) 478–496 MHz. (b) 852–869 MHz.

the overall junction ($C_{j0} = 0.7$ pF) and parasitic capacitance ($C_p = 0.08$ pF) of *D1* and *D2*. Thus, *L* is calculated to be 26.5 nH in order to achieve an appropriate resonant frequency. Note that, *L* consists of L_4 and the overall parasitic inductance ($L_{equivalent} \cong$ 1 nH) of *D1* and *D2*. The 478–496 MHz band resonator circuit components were calculated as $C3 \cong 15$ pF and $L3 \cong 7.2$ nH. Hence, the initial component values are determined for the two resonant circuits.

Initially these resonators were combined to achieve a dual-band structure. Then standard *LC* matching technique[40] is utilized to determine *C1*, *C2*, *L1*, and *L2* to achieve minimum reflection at the resonant frequencies. The substitution of realistic chip component values with their associated parasitics, and addition of 50 Ω microstrip lines and T-junctions introduce delay and shift the imaginary part of the input impedance. The via-holes also contribute to extra inductance in the circuit. Hence minor circuit adjustments are made in order to fine tune the resonant frequencies to the desired values. The final optimized values of the standard chip components are: $L3' = 3.9$ nH, $C3' = 7.5$ pF and $L4' = 11.6$ nH. Large Signal S-parameter analysis is also performed to demonstrate the matching network performance as the input power is varied. Simulation results for the input impedance of the circuit depicted in Fig. 11 are illustrated in Fig. 12. The proposed dual-resonant matching circuit achieves a VSWR <2 at 478–496 MHz and 852–869 MHz for input power ranging from -40 to -10 dBm. It should be noted that the matching circuit was designed based on the input impedance of two diodes and the output resistor and capacitor (Fig. 10). Therefore, selecting a different value for the load resistor requires a new matching circuit to be designed.

1. Paradiso, J. A. & Starner, T. Energy scavenging for mobile and wireless electronics. *IEEE Pervasive Comput.* **4**, 18–27 (2005).
2. Singh, R., Gupta, N. & Poole, K. F. Global green energy conversion revolution in 21st century through solid state devices. 26th International Conference on Microelectronics, Nis, Serbia. *IEEE.* DOI:10.1109/ICMEL.2008.4559221. 45–54 (11–14 May, 2008).
3. Wang, Y. K., Sheng, G. P., Shi, B. J., Li, W. W. & Yu, H. Q. A Novel electrochemical membrane bioreactor as a potential net energy producer for sustainable wastewater treatment. *Sci. Rep.* **3**, DOI:10.1038/srep01864 (2013).
4. Inayat, S. B., Rader, K. R. & Hussain, M. M. Nano-materials enabled thermoelectricity from window glasses. *Sci. Rep.* **2**, DOI:10.1038/srep00841 (2012).
5. Brown, W. C. The history of power transmission by radiowaves. *IEEE Trans. Microw. Theory Tech.* **32**, 1230–1242 (1984).
6. Le, T., Mayaram, K. & Fiez, T. Efficient far-field radio frequency energy harvesting for passively powered sensor networks. *IEEE J. Solid-State Circuits.* **43**, 1287–1302 (2008).
7. Paolo, J. & Gaspar, P. D. Review and future trend of energy harvesting methods for portable medical devices. Proceedings of the World Congress on Engineering (WCE). London, U. K. 909–914 (30 June–2 July, 2010).
8. Matsuki, H., Yamakata, Y., Chubachi, N., Nitta, S. & Hashimoto, H. Transcutaneous DC-DC converter for totally implantable artificial heart using synchronous rectifier. *IEEE Trans. Magn.* **32**, 5118–5120 (1996).
9. Scorcioni, S. *et al.* RF to DC CMOS rectifier with high efficiency over a wide input power range for RFID applications. Microwave Symposium Digest (IMS), *IEEE MTT-S.* Montreal, QC, Cabada. DOI:10.1109/MWSYM.2012.6259760. 1–3 (17–22 June, 2012).
10. Shameli, A., Safarian, A., Rofougaran, A., Rofougaran, M. & De Flaviis, F. Power harvester design for passive UHF RFID tag using a voltage boosting technique. *IEEE Trans. Microw. Theory Tech.* **55**, 1089–1097 (2007).
11. Mandal, S. & Sarpeshkar, R. Low-power CMOS rectifier design for RFID applications. *IEEE Trans. Circuits Syst. I, Reg. Papers.* **54**, 1177–1188 (2007).
12. Sun, H., Guo, Y. X., He, M. & Zhong, Z. Design of a high-efficiency 2.45-GHz rectenna for low-input-power energy harvesting. *IEEE Antennas Wireless Propag. Lett.* **11**, 929–932 (2012).
13. McSpadden, J. O., Fan, L. & Chang, K. Design and experiments of a high-conversion-efficiency 5.8-GHz rectenna. *IEEE Trans. Microw. Theory Tech.* **46**, 2053–2060 (1998).
14. Din, N. M., Chakrabarty, C. K., Bin Ismail, A., Devi, K. K. A. & Chen, W. Y. Design of RF energy harvesting system for energizing low power devices. *PIER.* **132**, 49–69 (2012).
15. Barnett, R. E., Liu, J. & Lazar, S. A RF to DC voltage conversion model for multi-stage rectifiers in UHF RFID transponders. *IEEE J. Solid-State Circuits.* **44**, 354–370 (2009).
16. Kanaya, H. *et al.* Energy harvesting circuit on a one-sided directional flexible antenna. *IEEE Microw. Wireless Compon. Lett.* **23**, 164–166 (2013).
17. Buonanno, A., D'Urso, M. & Pavone, D. An ultra wide-band system for RF energy harvesting. 5th European Conference on Antennas and Propagation (EUCAP). Rome, Italy. *IEEE.* 388–389 (11–15 April, 2011).
18. Hagerty, J. A., Helmbrecht, F. B., McCalpin, W. H., Zane, R. & Popovic, Z. B. Recycling ambient microwave energy with broad-band rectenna arrays. *IEEE Trans. Microw. Theory Tech.* **52**, 1014–1024 (2004).
19. Shariati, N., Rowe, W. S. T. & Ghorbani, K. RF field investigation and maximum available power analysis for enhanced RF energy scavenging. 42nd European Microwave Conference (EuMC). Amsterdam RAI, The Netherlands. *IEEE.* 329–332 (29 October–1 November, 2012).
20. Kim, P., Chaudhary, G. & Jeong, Y. A dual-band energy harvesting using frequency limited dual-band impedance matching. *PIER.* **141**, 443–461 (2013).
21. Li, B. *et al.* An antenna co-design dual band RF energy harvester. *IEEE Trans. Circuits Syst. I, Reg. Papers.* **60**, 3256–3266 (2013).
22. Niotaki, K. *et al.* A compact dual-band rectenna using slot-loaded dual band folded dipole antenna. *IEEE Antennas Wireless Propag. Lett.* **12**, 1634–1637 (2013).
23. Suh, Y. H. & Chang, K. A high-efficiency dual-frequency rectenna for 2.45- and 5.8-GHz wireless power transmission. *IEEE Trans. Microw. Theory Tech.* **50**, 1784–1789 (2002).
24. Collado, A. & Georgiadis, A. Conformal hybrid solar and electromagnetic (EM) energy harvesting rectenna. *IEEE Trans. Circuits Syst. I, Reg. Papers.* **60**, 2225–2234 (20013).
25. Rizzoli, V., Bichicchi, G., Costanzo, A., Donzelli, F. & Masotti, D. CAD of multi-resonator rectenna for micro-power generation. European Microwave Integrated Circuits Conference (EuMIC). Rome, Italy. *IEEE.* 331–334 (228–29 September, 2009).
26. Huang, F. J. *et al.* Rectenna application of miniaturized implantable antenna design for triple-band biotelemetry communication. *IEEE Trans. Antennas Propag.* **59**, 2646–2653 (2011).
27. Pham, B. L. & Pham, A. V. Triple bands antenna and high efficiency rectifier design for RF energy harvesting at 900, 1900 and 2400 MHz. Microwave Symposium Digest (IMS), *IEEE MTT-S.* Seattle, WA. DOI:10.1109/MWSYM.2013.6697364. 1–3 (2013).
28. Pinuela, M., Mitcheson, P. D. & Lucyszyn, S. Ambient RF energy harvesting in urban and semi-urban environments. *IEEE Trans. Microw. Theory Tech.* **61**, 2715–2726 (2013).
29. Mikeka, C. & Arai, H. Microwave Tooth for sensor power supply in battery-free applications. Proceedings of the Asia-Pacific Microwave Conference (APMC). Melbourne, VIC. *IEEE.* 1802–1805 (5–8 December, 2011).
30. Baum, T., Thompson, L. & Ghorbani, K. Complex dielectric measurements of forest fire ash at X-band frequencies. *IEEE Geosci. Remote Sens. lett.* **8**, 859–863 (2011).
31. Avago Technologies, *Surface Mount RF Schottky Barrier Diodes HSMS-282X Series. Data sheet.* (2005). Available at: http://www.avagotech.com/docs/AV02-1320EN. (Accessed: 22/11/2014).
32. Avago Technologies, *Surface Mount Zero Bias Schottky Detector Diodes HSMS-285X Series. Data sheet.* (2005). Available at: http://www.avagotech.com/docs/AV02-1377EN. (Accessed: 22/11/2014).
33. Valenta, C. R. & Durgin, G. D. Rectenna performance under power-optimized waveform excitation. IEEE International Conference on RFID. Penang. DOI:10.1109/RFID.2013.6548160. 237–244 (30 April–2 May, 2013).
34. Trotter, M. S. & Durgin, G. D. Survey of range improvement of commercial RFID tags with power optimized waveforms. IEEE International Conference on RFID. Orlando. DOI:10.1109/RFID.2010.5467265. 195–202 (14–16 April, 2010).
35. Australian Government, *Australia Radio Frequency Spectrum Plan (ACMA).* (January 2013). Available at: http://acma.gov.au/~/media/Spectrum%20Transformation%20and%20Government/Information/pdf/Australian%20Radiofrequency%20Spectrum%20Plan%202013.pdf. (Accessed: 22/09/2014).
36. Keyrouz, S., Visser, H. J. & Tijhuis, A. G. Rectifier analysis for radio frequency energy harvesting and power transport. 42nd European Microwave Conference (EuMC). Amsterdam RAI, The Netherlands. *IEEE.* 428–431 (29 October–1 November, 2012).
37. Avago Technologies, *Schottky Diode Voltage Doubler. Application Note 956-4.* (2005). Available at: http://c1233384.r84.cf3.rackcdn.com/UK_HPA_HSCH-5331_7AN.pdf. (Accessed: 22/11/2014).
38. Eriksson, H. & Waugh, R. W. *A temperature compensated linear diode detector. Design Tip*. Agilent Technologies. (2000). Available at: http://electronix.ru/forum/index.php?act=Attach&type=post&id=13726. (Accessed: 22/11/2014).
39. Avago Technologies, *The Zero Bias Schottky Diode Detector at Temperature Extremes-Problems and Solutions. Application Note AN 1090.* (2005). Available at: http://www.efo.ru/download/Zero_bias_shottky_over_temperature.pdf. (Accessed: 22/11/2014).
40. Mattaei, G., Young, L. & Jones, E. M. T. *Microwave Filters, Impedance-Matching Networks and Coupling Structures.* Artech house books, Dedham, MA. (1980).

Acknowledgments

The authors would like to acknowledge Dr. Khashayar Khoshmanesh for valuable advice. The authors also acknowledge Mr. David Welch for assistance in fabrication of the rectifier circuit.

Author contributions

N.S. designed and simulated the rectifier, carried out the measurements, interpreted results and wrote the paper. K.G. directed the research, contributed to perform the simulation and measurement and validation of design and results. W.S.T.R. supervized the research, analyzed the data and contributed to the general concept, validation of design and results. J.R.S. analyzed the data and contributed to the general concept, validation of design and results. All authors reviewed the manuscript.

Additional information

Competing financial interests: The authors declare no competing financial interests.

How to cite this article: Shariati, N., Rowe, W.S.T., Scott, J.R. & Ghorbani, K. Multi-Service Highly Sensitive Rectifier for Enhanced RF Energy Scavenging. *Sci. Rep*. **5**, 9655; DOI:10.1038/srep09655 (2015).

This work is licensed under a Creative Commons Attribution 4.0 International License. The images or other third party material in this article are included in the article's Creative Commons license, unless indicated otherwise in the credit line; if the material is not included under the Creative Commons license, users will need to obtain permission from the license holder in order to reproduce the material. To view a copy of this license, visit http://creativecommons.org/licenses/by/4.0/

Sensors **2012**, *12*, 13636-13663; doi:10.3390/s121013636

OPEN ACCESS

sensors

ISSN 1424-8220

www.mdpi.com/journal/sensors

Article

Optimization of Passive Low Power Wireless Electromagnetic Energy Harvesters

Antwi Nimo *, Dario Grgić and Leonhard M. Reindl

Department of Microsystems Engineering, Laboratory for Electrical Instrumentation,
University of Freiburg, IMTEK, Georges-Köhler-Allee 106, 79110 Freiburg, Germany;
E-Mails: grgic@imtek.de (D.G.); leonhard.reindl@imtek.uni-freiburg.de (L.M.R.)

* Author to whom correspondence should be addressed; E-Mail: antwi.nimo@imtek.de;
Tel.: +49-761-203-7223; Fax: +49-761-203-7222.

Received: 13 August 2012; in revised form: 28 September 2012 / Accepted: 28 September 2012 / Published: 11 October 2012

Abstract: This work presents the optimization of antenna captured low power radio frequency (RF) to direct current (DC) power converters using Schottky diodes for powering remote wireless sensors. Linearized models using scattering parameters show that an antenna and a matched diode rectifier can be described as a form of coupled resonator with different individual resonator properties. The analytical models show that the maximum voltage gain of the coupled resonators is mainly related to the antenna, diode and load (*remote sensor*) resistances at matched conditions or resonance. The analytical models were verified with experimental results. Different passive wireless RF power harvesters offering high selectivity, broadband response and high voltage sensitivity are presented. Measured results show that with an optimal resistance of antenna and diode, it is possible to achieve high RF to DC voltage sensitivity of 0.5 V and efficiency of 20% at −30 dBm antenna input power. Additionally, a wireless harvester (*rectenna*) is built and tested for receiving range performance.

Keywords: RF energy harvesting; wireless power transmission; coupled resonators; Schottky diode; RF to DC power converter; impedance matching; PI-matching; L-matching; rectenna

---

1. Introduction

For autonomous powering of sensor nodes in remote or inaccessible areas, wireless power transfer provides the only viable option to power them from an energy source. Due to the low power density of ambient RF at far-field from transmitters, there is a need to optimize each aspect of a wireless RF energy harvester for possible realistic applications. Today remote autonomous sensors are mostly powered by batteries, which have limited lifespan. Renewable powering has the potential to power autonomous sensors perpetually. Due to the expansion of telecommunications technology ambient electromagnetic (EM) power is among the most common sources of ambient energy. There are power transmitters/receivers scattered in practically any society, ranging from television transmission stations to cell phone transmitters and even wireless routers in our homes/offices or mobile phones. These transmitters in our environment and others which are on special dedicated frequencies produce ambient RF power (on the order of microwatts) which can be used as a source for powering remote microwatt budget sensors through wireless energy harvesting. This work presents different matching techniques based on different application requirements using Schottky diode-based RF to DC power converting circuits for wireless remote EM energy harvesting around 434 MHz and 13.6 MHz. Generalized analytical models and limitations of the matched RF to DC power converters are discussed. A wireless RF energy harvester consisting of an antenna and a matched diode rectifier is then realized and its performance tested. Passive wireless energy harvesting also finds applications in near field communications (NFC) [1], RFID tags [2–5], implantable electronics [6,7], and environmental monitoring [8], among others.

1.1. State of the Art

Hertz was the first to demonstrate the propagation of EM waves in free space and to demonstrate other properties of EM waves such as reflection using parabolic reflectors [9]. Wireless power transmission was then investigated and demonstrated for possible wireless remote powering by Tesla. Electromagnetic power beaming for far field wireless power transfer using collimated EM waves was proposed in the 1950s [9]. Recent advances in ultralow power sensors means ambient omni-directional EM power can be used as a source for powering remote sensors without the need to collimate the EM power through the wireless space. Mickle [10] and McSpadden [11] have presented earlier work on wireless energy harvesting systems using Schottky diodes and rectennas where the usability of ambient RF power into DC power was shown. Sample [12] presented a wireless harvester which can harvest EM power from TV and radio base stations transmitting 960 kW of effective radiated power; 60 μW was harvested at a range of about 4 km. Umeda [13] and Le [14] have presented more integrated wireless energy harvesters based on CMOS RF to DC rectifying circuits. CMOS-based rectifying power converters provide full compatibility with standard CMOS technologies and have advantages in batch processes for mass production. The drawback of CMOS-based diode connected transistors is the need to bias the gate of the transistors for the rectifying circuits to effectively function. This gate bias is provided externally, which makes the system not passive. Without the injection of external charges or a biasing of the transistor gate, the circuit has low efficiency, especially when the amplitude of the input voltage is low [15]. Shameli [2] presented a passive CMOS RF to DC power converter with a voltage sensitivity of 1 V at −14.1 dBm input, but the circuit efficiency was only 5 %. Zbitou [16] presented an RF to DC converter based on Schottky diodes and achieved 68 % efficiency at 20 dBm RF input power. Ungan [17,18] presented antennas and high quality factor RF to DC power converters at 24 MHz and 300 MHz for RF wireless energy harvesting at -30 dBm input power. The power converter used high quality factor resonators for impedance matching the EM source and the diodes and achieved high open circuit voltage sensitivity of 1 V/µW. Boquete [19] presented a risk assessment system for calculating insurance premiums by monitoring mobile phone usage while driving. This was done by harvesting EM power from detected mobile phone usage during driving for risk assessment. Heikkinen [20] presented rectennas on different substrates at 2.4 GHz using transmisson lines to match the antennas output resistance (*at resonance*) to the rectifying diodes. Akkermans [21] presented a rectenna design by complex conjugating impedance provided by a microstrip structure to a diode so that resonance may be achieved for a working frequency. This design approach may need sophisticated tools to realize and the dominant resonance frequency of the rectenna can be unpredictable in practice. Hagerty [22] presented rectenna arrays for broadband ambient EM harvesting and characterized the harvesters from 2 GHz to 18 GHz; rectennas combine impedance matching the RF rectifying circuit and the antenna into one compact device, but an array of rectennas may increase the overall size of an EM harvester. Herb [23] and Vullers [24] have provided a comprehensive state of the art for micro energy harvesting and have explored the various techniques used for harvesting ambient renewable energy.

2. RF to DC Power Converter

2.1. Diode Rectifier

A junction diode equivalent circuit and simple Schottky diode rectifier are shown in Figure 1. R_{DS} is the diode resultant series resistance, C_{DS} is the diode resultant series capacitance, R_{DP} is the diode resultant parallel resistance, C_{DP} is the diode resultant parallel capacitance, V_S is the sinusoidal source voltage and V_C is the voltage across the capacitor.

Figure 1. (**a**) Diode series equivalent model, (**b**) Diode parallel equivalent model, (**c**) Simple diode detector.



The diode capacitive impedance is mainly due to the junction capacitances provided by the metal, its passivation and the semiconductor forming the diode. AC power incident on a forward biased diode input is converted to DC power at the output. The current-voltage behavior of a single metal/semiconductor diode is described by the Richardson equation [25] as in Equation (1):

$$I = I_S\left(e^{\left(qV_D/nKT\right)} - 1\right) \tag{1}$$

where I is the current through the diode, I_S is the saturation current, q is the charge of an electron, V_D is the voltage across the diode, T is the temperature in degrees Kelvin and K is Boltzmann constant. The voltage equation around the loop can be derived from Figure 1(c) and is given in Equation (2):

$$V_D = V_S - V_C \tag{2}$$

Since the same current flows through the diode and the capacitor, one can find the average current through the circuit by integrating Equation (1) over a time period. By substituting Equation (2) into Equation (1), V_C can be expressed in terms of V_S by averaging the diode current to zero. This is given in Equation (3) [26]:

$$V_C = \frac{KT}{q}\ln\left[\vartheta_0\left(\frac{qV_S}{KT}\right)\right], \tag{3}$$

where ϑ_0 is the series expansion of the sinusoidal source voltage. Equation (3) can further be simplified for very small amplitude V_S as Equation (4):

$$V_C \approx \frac{qV_S^2}{4KT} \tag{4}$$

Equation (4) shows that for a small voltage source, the circuit output voltage is proportional to the square of the input sinusoidal voltage; hence it's so-called square law operation. Extensions of this model for voltage multipliers and other input signals are presented in [27] and [28]. Equation (4) further confirms that for low input voltage (power ≤ 10 dBm), an impedance matching network between the source and the diode is necessary to improve the detected output voltage and efficiency.

2.2. Impedance Matching

The maximum power transfer theorem states that the highest power is transferred to the load when the source resistance is the same as the load resistance. For systems with both resistive and reactive impedances from source and load, the source and the load impedance should be adjusted in a way that they are the complex conjugate of each other through impedance matching. For the purposes of this work, a 50 Ω resistive source is chosen as reference for load impedance matching. The antenna which captures the ambient RF signals is tuned to provide this source resistance at resonance for the rectifying circuit in a complete EM wireless remote harvester. The load is the resistance of the Schottky diodes and the actual connected resistance (*remote sensor*). The specific type of matching network which can be used for complex conjugation depends on the nature of load or source impedance, the desired RF to DC converter functionality and other factors like circuit size, cost, *etc.* The response of a matched RF to DC power converter depends on the matching network used as well as the source or load component quality factors and impedances.

2.3. Diode Impedance

Schottky diodes HSMS-285C and HSMS-286C from Avago [29,30] are used to build the RF to DC power converters. The HSMS-285× or 286× series diodes can be operated as zero biased with relatively low forward junction potential. This allows for the realization of completely passive RF to DC power converters for wireless energy harvesting. The HSMS-285C or 286C is a pair of series connected Schottky diodes in a SOT-323 package. The impedance of the HSMS-285C and HSMS-286C diodes was first measured so it can be matched to the resistance (50 Ω) of the antenna source. This is done by connecting the input of the diodes to a network analyzer and measuring the scattering parameters. These scattering parameters are then converted to the corresponding impedances. The input impedance of a diode depends mainly on the resistive and capacitive impedance provided by the junction of the diode and its connected load. For a couple of diodes arranged in a package such as the HSMS-285C or 286C, the input impedance is the vector sum of the impedances provided by each diode in the package arrangement, the extra impedance associated with the packaging and the connected load. The diode measuring board is as shown in Figure 2. The diodes were measured at room temperature for an input power of -30 dBm at a diode connected load of 1 MΩ with a 100 pF filter capacitor. For the sake of this work, the input impedance of the diodes will always be referred to at these connected load conditions.

Figure 2. (**left**) Reference circuit layout for measuring diodes input impedance, (**right**) measuring printed circuit board (PCB) for diodes input impedance on 1 mm FR4 substrate.



Figure 3. Measured input impedance (Δ resistive, □ capacitive) of HSMS-285C (**left**) and HSMS-286C (**right**) diodes at −30 dBm input with 1 MΩ load and 100 pF filter.



The board is fabricated such that components are soldered directly one into another to prevent additional impedances introduced by copper route. The PCB backside had the ground layer. An example of measured input impedance for HSMS-285C and HSMS-286C is shown in Figure 3.

The diodes quality factor is given by $X_{DS}R_{DS}^{-1}$, where X_{DS} is the resultant series capacitive impedance of the diodes. At an input power of −30 dBm, the measured input impedance of the HSMS-285C diodes is 72–j501 Ω at 434 MHz and 587–j1239 Ω at 13.6 MHz. For HSMS-286C diodes, it is 10–j503 Ω at 434 MHz and ~1.5–j8.1 kΩ at 13.6 MHz for −30 dBm input. The measured impedance of the HSMS-286C diodes at low frequencies (< 60 MHz) shows pronounced fluctuations. The low-frequency excess flicker noise and the shot noise observed in the HSMS-286C have been studied by several authors [31–33]. The pronounced presence of trap states in the depletion region of the semiconductor, mobility fluctuations in carriers, edge effects among other reasons is reported to cause deviations from the ideal Schottky diode behavior and hence generation-recombination noise for some diodes such as the HSMS-286C [34]. When a diode rectifier is matched at a reference operating condition, the matching network may function less effectively at other input power levels, connected load and other operating frequencies. This is due to possible changes in the diode input impedance. Throughout this work the imperfections of the matching circuit at other operating conditions away from the matched reference conditions are accepted without changes to the matching network.

2.4. Voltage Doubler

The Delon voltage doubler and Greinacher doubler are both used to realize the RF to DC power converters presented in this work. The Delon voltage doubler and Greinacher doubler are shown in Figure 4. The diodes output voltage (V_{out}) is doubled what is detected by a simple detector circuit shown in Figure 1. Both doublers produce the same output performance, the only difference is that the Delon doubler has an instantaneous input ground which is not shared with the output.

Figure 4. Circuit diagram of voltage doubler, (**a**) Delon doubler and (**b**) Greinacher doubler.



2.5. Matching Techniques for Antenna Source and RF to DC Power Converter

2.5.1. L-match RF to DC Power Converter

An L-match network converts a source series impedance to its equivalent load parallel impedance or *vice-versa* and tunes out by subtracting or adding any surplus reactance from the load or source with the counter impedance. Series impedance is converted to its parallel equivalent impedance using Equations (5–7):

$$Q_S = \frac{X_S}{R_S} \tag{5}$$

$$Q_P = \frac{R_P}{X_P} \tag{6}$$

where X_S is the total series reactive impedance, R_S is the total series resistance, R_P is the total parallel resistance, X_P is the total parallel reactive impedance, Q_S and Q_P are the series and parallel quality factors respectively:

$$R_S + jX_S = \frac{R_P \times jX_P}{R_P + jX_P} \tag{7}$$

Equation (7) is the equation of a series sum of impedances and a parallel sum of impedances. It is interesting to note that Q_S and Q_P from an L-matched network may be different from the individual component quality factors as a result of the inherent resistive and reactive impedances in that component. By virtue of Equation (7), Q_S and Q_P must be equal in an L-matched network. Using Equations (5,6) and (7), the ratio of the parallel resistance (*or reactance*) to the series resistance (*or reactance*) can be derived in terms of the quality factors Q_P or Q_S [35]. Since at match conditions, only the resistive impedances dissipate power, the loaded quality factor *Q,* of the L-matched network can be expressed as in Equation (8):

$$R_P = (Q^2 + 1)R_S \tag{8}$$

Using Equations (5,6) and (8), series impedance can be converted to its parallel equivalent for a fixed frequency and power level. As an example; a series impedance 72–j501 Ω (HSMS-285C at 434 MHz for −30 dBm input power) is easily converted to $-j510(3519)/(-j510 + 3519)$ Ω as its parallel equivalent with a component quality factor of 6.96. The source resistance is taken as part of the parallel matching network in an L-match circuit if the source series equivalent resistance is greater than the load series equivalent resistance. On the other hand, the load resistance is taken as part of the parallel matching network if the load series equivalent resistance is greater than the source series equivalent resistance. For the purpose of this work, inductors were only used for series impedance matching and capacitors as shunts. This prevents power seeping through any shunt inductor used for impedance matching due the short circuit provided by a shunt inductor to ground and resulting in less output efficiency. Resistors were not used for impedance matching.

2.5.2. L-match RF to DC Converter Generalized Analytical Model

The classical matching technique using Equations (5,6) and (8) is first used to L-match the 50 Ω resistance of the antenna to the resistance of the HSMS-286C diodes (and load) at 434 MHz for −30 dBm input and then the generalized model is discussed. The antenna source resistance was L-matched to the resistance of the diodes (and load). The 50 Ω resistance of the antenna is taken as the parallel matching component and the diodes 10 Ω resistance is the series matching component. The loaded *Q* is found as 2 between the 50 Ω antenna source resistance and the 10 Ω diode series resistance using Equation (8). From this loaded *Q*, a shunt capacitive impedance of 25 Ω (14.6 pF at 434 MHz) using Equation (6) and a series inductive impedance of 20 Ω (7.3 nH at 434 MHz) using Equation (5) will match the 50 Ω source to the 10 Ω HSMS-286C diodes (and load) series resistance at −30 dBm input. Since the HSMS-286C diodes inherently provides 503 Ω series capacitive impedance at −30 dBm, a resultant series inductive impedance of 523 Ω (192 nH at 434 MHz) is needed to tune the 50 Ω resistive source to the complete HSMS-286C diodes impedance at 434 MHz for −30 dBm input. The L-matched HSMS-286C diodes rectifier is as shown in Figure 5(a).

Figure 5. (**a**) L-match RF to DC harvester using the HSMS-286C diodes at 434 MHz for −30 dBm input. (**b**) Small signal impedance model of a generalized L-matched RF to DC power converter as capacitive coupled series RLC resonator with different resonator elements.


L matching
HSMS-286C and connected load
Antenna; 434MHz @ -30dBm 50Ω
R_A
C_K=14.6pF
X_LL=523Ω, L_L=192nH
100pF
1MΩ
V_L
(a)
Antenna
L matching network
HSMS-286C and connected load
R_A
L_A
C_A
L_L
C_DS
R_L
V_L
Antenna induced voltage; V_s
I_1
C_k
I_2
(b)

C_K is the tuning capacitance, L_L is the tuning inductance, X_{LL} is the tuning inductive impedance, C_{DS} is the diodes series capacitance, X_{DS} is the diodes series capacitive impedance, V_S is the antenna captured ambient EM voltage, R_A is the resistance of antenna, L_A is the inductance of antenna, C_A is the capacitance of antenna, R_L is the resultant series resistance from the diodes and the connected load resistance, V_L is the resistive load voltage. From Figure 5(a) the power dissipated in the resistance of the diodes (and connected load); P_L is given by Equation (9), where R_L is the series resistance of the diodes and load:

$$P_L = \frac{V_L^{\,2}}{R_L} \tag{9}$$

The source power; P_S is given by Equation (10), where V_S* is the root mean squared (RMS) antenna captured source voltage. Half of the source power is transferred to the resistance of the diodes (and connected load) at match conditions as described by the maximum power transfer theorem:

$$P_S = \frac{V_S^{\,2}}{R_A} \quad \text{or} \quad P_S = \frac{V_{S*}^{\,2}}{2R_A} \tag{10}$$

Equating P_L and half RMS P_S gives a condition of maximum voltage gain for the matched RF to DC power converter shown in Figure 5(a):

$$\frac{V_L}{V_{S*}} = \frac{1}{2}\sqrt{\frac{R_L}{R_A}} \tag{11}$$

From Equation (8), substituting the series and parallel resistance ratio into Equation (11) the voltage gain can be expressed in terms of the loaded quality factor as in Equations (12) and (13), where Q is the loaded quality factor of the RF to DC power converter:

$$\frac{V_L}{V_{S*}} = \frac{1}{2}\sqrt{\frac{1}{1 + Q^2}} \tag{12}$$

Equation (12) is the voltage gain in-terms of the loaded Q if the resistance of the diodes (and connected load) is part of the series matching network and the resistance of the antenna source is part of the parallel matching network as in Figure 5(a). If the resistance of the diodes is part of the parallel matching network, then Equation (13) may be written as the voltage gain in-terms of the loaded Q in an L-matched circuit:

$$\frac{V_L}{V_{S*}} = \frac{1}{2}\sqrt{1 + Q^2} \tag{13}$$

Equations (12) and (13) shows that the maximum voltage gain is directly related to the relative differences between the diodes (and connected load) resistance and source resistance at matched conditions or the circuit loaded quality factor. It is interesting to note that the circuit shown in Figure 5(a) has a loaded Q of 2, but an HSMS-286C unloaded quality factor of 50 (at 434 MHz for −30 dBm).

Figure 5(a) is generally modeled as capacitive coupling of two series RLC resonators with a voltage source. This linearized model can be made at any defined frequency and power level. The model however neglects the metal/semiconductor physics of the diode's junction potentials which results in a Schottky barrier. The first series RLC resonator is modeled as impedance from the antenna with or without some passive matching components. The voltage source V_S, is the antenna captured electromagnetic voltage. The second series RLC resonator is the impedance from the diodes (at a defined condition), connected resistance and some passive matching components. Ck is modeled as the coupling element between the two series RLC resonators. Figure 5(b) gives a more general look at the special scenario shown in Figure 5(a). The voltage equations in the two loops are given by Equations (14,15) according to Kirchhoff's voltage loop laws, where ω is the angular frequency and I_1, I_2 are the currents in the first loop and second loop, respectively:

$$V_S = I_1\left[R_A + j\omega L_A - \frac{j}{\omega C_A} - \frac{j}{\omega C_K}\right] + \frac{jI_2}{\omega C_K} \tag{14}$$

$$0 = \frac{jI_1}{\omega C_K} + I_2\left[R_L + j\omega L_L - \frac{j}{\omega C_{DS}} - \frac{j}{\omega C_K}\right] \tag{15}$$

Using Cramers rule, I_2 can be expressed as:

$$I_2 = \frac{\dfrac{-jV_S}{\omega C_K}}{\left[R_A + j\omega L_A - \dfrac{j}{\omega C_A} - \dfrac{j}{\omega C_K}\right]\left[R_L + j\omega L_L - \dfrac{j}{\omega C_{DS}} - \dfrac{j}{\omega C_K}\right] + \dfrac{1}{\omega^2 C_K^2}}. \quad (16)$$

The voltage across R_L is V_L; given by I_2R_L:

$$V_L = \frac{\dfrac{-jV_S}{\omega C_K}R_L}{\left[R_A + j\omega L_A - \dfrac{j}{\omega C_A} - \dfrac{j}{\omega C_K}\right]\left[R_L + j\omega L_L - \dfrac{j}{\omega C_{DS}} - \dfrac{j}{\omega C_K}\right] + \dfrac{1}{\omega^2 C_K^2}} \quad (17)$$

The voltage gain of the coupled resonator can be expressed as in Equation (18):

$$\frac{V_L}{V_S} = \frac{\dfrac{-jR_L}{\omega C_K}}{\left[R_A + j\omega L_A - \dfrac{j}{\omega C_A} - \dfrac{j}{\omega C_K}\right]\left[R_L + j\omega L_L - \dfrac{j}{\omega C_{DS}} - \dfrac{j}{\omega C_K}\right] + \dfrac{1}{\omega^2 C_K^2}} \quad (18)$$

At resonance, there is no resultant reactance in the RLC resonators or the capacitive and inductive impedances become equal; hence Equation (19) can be written:

$$\omega L_A - \frac{1}{\omega}\left\{\frac{1}{C_A} + \frac{1}{C_K}\right\} = 0 \text{ and } \omega L_L - \frac{1}{\omega}\left\{\frac{1}{C_{DS}} + \frac{1}{C_K}\right\} = 0 \quad (19)$$

Equations in Equation (19) can be used to find the resonant frequencies of the series coupled resonator. The voltage gain of the coupled resonator at resonance can then be expressed as in Equation (20):

$$\frac{V_L}{V_S} = V_{gain} = \frac{\dfrac{-jR_L}{\omega C_K}}{R_AR_L + \dfrac{1}{\omega^2 C_K^2}} \quad (20)$$

where V_{gain} is the voltage gain. V_{gain} at resonance is a function of the resistance of the source and load and the coupling element. The maximum of Equation (20) is obtained when:

$$\frac{dV_{gain}}{dC_K} = 0. \quad (21)$$

This gives the results as in Equation (22):

$$\frac{dV_{gain}}{dC_K} = \frac{j2R_L}{\omega^3 C_K^4} - j\left\{R_AR_L + \frac{1}{\omega^2 C_K^2}\right\}\frac{R_L}{\omega C_K^2} = 0 \text{ or } R_AR_L^2 = \frac{R_L}{\omega^2 C_K^2} \quad (22)$$

Equation (22) can be simplified to find $C_{K(max)}$:

$$C_{K(\max)} = \pm\frac{1}{\omega}\sqrt{\frac{1}{R_AR_L}} \quad (23)$$

where C_{Kmax} is the value of the coupling element where maximum power transfer from the first resonator to the second resonator occurs. Using Equations (19) and (23) the unknown optimal matching impedances can be found from the known impedances just like the classical L-matched procedure using Equations (5,6) and (8). By substituting $C_{K(max)}$ into Equation (20) and taking the magnitude of V_{gain}, gives the maximum voltage gain of the coupled series resonator at resonance:

$$\left|\frac{V_L}{V_S}\right| = \frac{1}{2}\sqrt{\frac{R_L}{R_A}} \text{ or simply } \frac{V_L}{V_{S*}} = \frac{1}{2}\sqrt{\frac{R_L}{R_A}} \tag{24}$$

For wireless harvesters consisting of an antenna and a diode rectifying circuit, the diode resistive impedance at any condition is dependent on the diode realized parameters, signal frequency, connected load and the input power level. The source impedance is determined by the impedance of the antenna. For maximum efficiency, the ratio of the source resistance to the load resistance must tend to zero at matched conditions. The efficiency η of the circuit is given by Equation (25):

$$\eta = \frac{P_L}{P_S}\,; \eta \to 1 \ \ when \ \frac{R_A}{R_L} \to 0 \tag{25}$$

2.5.3. L-Match RF to DC Converter Experimental Results and Discussion

The presented circuit was L-matched between the 50 Ω resistance of the antenna source and the resistance of the HSMS-285C diodes (and load) at 434 MHz for −30 dBm input as shown in Figure 6. Since the series equivalent resistance of the HSMS-285C diodes and load (72 Ω) is greater than the 50 Ω series resistive antenna source, the diode is taken as parallel matching network with a parallel equivalent impedance of $-j510(3519)/(-j510 + 3519)$ Ω. The analysis follows the same procedure as in Section 2.5.2 after this step. Figure 6(b) shows the resultant L-matched RF to DC power converter. C_{DP}* is the resultant shunt matching capacitance.

Figure 6. (**a**) L-matched impedance circuit for matching the HSMS-285C diodes at 434 MHz for −30 dBm input. (**b**) Resultant network, (**c**) PCB layout of the L-matched Delon doubler with adjusted values on FR4 substrate (**d**) Fabricated PCB of the L-network matched Delon voltage doubler.



Figure 6. *Cont.*



(c) **(d)**

Figure 6(a,b) assume perfect characteristic impedance between the various components in the matched circuit. When a copper route is introduced between components and on a material substrate, it must be accounted for in the total impedance as seen by the source or load. This PCB impedance compensation is carried out in Advance Design Systems (ADS) from Agilent [36]. ADS has extensive models for microstrip substrates to account for its impedances. The optimized layout using ADS microstrip models and its compensated values in the passive tuning components for a Delon doubler is shown in Figure 6(c).

The circuit reflection coefficient (S_{11}) and input impedance at open circuit are shown in Figure 7. There is high return loss and resonance around 434 MHz. The circuit input impedance at open circuit conditions is ~38 Ω at resonance for −40 dBm and ~17 Ω at −10 dBm input.

The measured L-matched circuit efficiency and voltage sensitivity is shown in Figure 8. The maximum measured L-matched efficiency at −30 dBm is 22% at ~20 kΩ load and an open circuit voltage of 124 mV. At −10 dBm, the maximum efficiency and open circuit voltage is 47% and 2 V respectively. At the optimal load of ~20 kΩ, the detected voltage is 58 mV and 1 V at −30 dBm and −10 dBm respectively.

Figure 7. Measured open circuit S_{11} of the L-matched Delon circuit at different input power levels from a 50 Ω source (**left**), measured open circuit input impedance at −10 dBm and −40 dBm of the L-matched circuit (**right**).



The open circuit voltage gain is 25 at −30 dBm and 40 at −10 dBm. The maximum measured efficiency at −35 dBm is 27%. This is higher than that of −30 dBm due to the better matched circuit impedance at −35 dBm (35 Ω) than at −30 dBm (27 Ω) input. The L-matched RF to DC power converter has a loaded *Q*, sensitivity and efficiency determined mainly by the diodes resistance, diodes junction potential, connected resistance and antenna source resistance at matched conditions.

Figure 8. Measured L-matched circuit efficiency *versus* resistive load at various input power levels at 434 MHz (**left**), measured open circuit voltage and at 17 kΩ load *versus* input power at 434 MHz (**right**).



2.5.4. PI-match RF to DC Power Converter

A highly selective or small frequency bandwidth RF power converter is realized with a PI-network in-between the source impedance from the antenna and the diode rectifier. A PI-network is a ‘back to back’ L-network that are both configured to match the load and source impedance to an invisible resistance located at the junction between the two L-networks [37]. The quality factor of the L-network with the parallel resistance is given by Equation (26):

$$Q_P^{*} = \sqrt{\frac{R_P}{R^{*}} - 1}, \tag{26}$$

where R_P is the parallel resistance, R^* is a virtual resistance and Q_P^* is the quality factor of the L-network with the parallel resistance. The quality factor of the L-network with the series resistance is given by Equation (27):

$$Q_S^{*} = \sqrt{\frac{R_S}{R^{*}} - 1}, \tag{27}$$

where Q_S^* is the quality factor of the L-network with the series resistance. The unloaded quality factor; Q_S^* or Q_P^* is set higher than what is normally achieved with a single L-network [37] to realize the small frequency bandwidth circuit. The resistance of the load is assigned the parallel network in a PI-matched circuit if its series equivalent resistance is higher than the source series equivalent resistance; the opposite is true if the source is higher than the load. Equation (26) and Equation (27) are synonymous to Equation (8), except the lowest resistive impedance in Equation (8) is substituted with the virtual resistance which is dependent on the newly desired circuit selectivity. From Equations (26) and (27) the loaded quality factor of the PI-matched circuit can be written as Equation (34) in terms of Q_S^* and Q_P^*:

$$Q^2 = \left[\left(\frac{Q_P^{*2} + 1}{Q_S^{*2} + 1} \right) - 1 \right], \tag{28}$$

where Q is the loaded quality factor of the PI-network. Q_S* or Q_P* are the unloaded quality factors of the PI-matched network. The larger value among the unloaded quality factors result in small frequency bandwidth response which is desired when matching a source and load impedance with a PI-network. Some authors approximate the highest value of Q_S* or Q_P* or their algebraic sum as the loaded quality factor of the PI-network as in [35] and [37], but Equation (28) gives the exact loaded Q of the PI-matched circuit in terms Q_S* and Q_P*. This allows for the correct estimation of the maximum voltage gain from the loaded quality factor.

2.5.5. Selectivity RF to DC Converter Generalized Analytical Model

An example of a PI-matched RF to DC converter using the HSMS-285C diodes operating at 434 MHz for −30 dBm input is presented first and then the generalized model is discussed. The circuit is matched for Q_P* of 60 between the antenna and the resistance of the diodes as shown in Figure 9.

Figure 9. Impedance diagram of PI-matched RF power converter; (**a**) Impedance diagram of 50 Ω source and the HSMS-285C diodes at 434 MHz, (**b**) Resultant PI matched network between the antenna source and load resistance.


PI network (Q_P*=60)
HSMS-285C and load
@ 434MHz -30dBm
Antenna;
434MHz @
P_S= -30dBm
50Ω
R_A
2.6nH
22nH
51pF
R*
6.3pF
0.7pF
R_DP=3.5 kΩ
V_L
Resultant PI
network (Q_P*=60)
source
25nH
51pF
C_DP*=5.6pF
R_L
V_L

(a) **(b)**

Figure 9(b) can also be modeled as an inductive coupling of two parallel RC circuits. A more general look at such a circuit is shown in Figure 10, as an inductive coupling of two parallel RLC resonators with a current source.

Figure 10. Inductive coupled parallel RLC small signal model of a generalized PI-matched antenna and diode rectifier.


Antenna and matching
K_I
Conntected load,
diode and matching
I
Antenna
induced
current
V_S
R_A
C_A
L_A
L_L
C_DP
R_L
V_L

The first parallel RLC resonator is modeled as impedance from the antenna and some passive matching components. The second parallel RLC resonator is modeled as impedance from the linearized diodes, its connected load and some passive matching components. *I* is the antenna induced current, V_S this time is the voltage across the parallel R_A and K_1 is the coupling element between the two parallel resonators. Using Kirchoff's current laws, the node equations can be expressed as Equations (29) and (30):

$$I = V_S\left[\frac{1}{R_A} + j\omega C_A - \frac{j}{\omega L_A} - \frac{j}{\omega K_1}\right] + \frac{jV_L}{\omega K_1} \tag{29}$$

$$0 = \frac{jV_S}{\omega K_1} + V_L\left[\frac{1}{R_L} + j\omega C_{DP} - \frac{j}{\omega L_L} - \frac{j}{\omega K_1}\right] \tag{30}$$

Load voltage (V_L) and the source voltage (V_S) at resonance are given by the equations in Equation (31). The resonance frequencies are given by Equation (32):

$$V_L = \frac{\frac{-jI}{\omega K_1}}{\left[\frac{1}{R_A R_L} + \frac{1}{\omega^2 K_1^2}\right]} \quad \text{and} \quad V_S = \frac{\frac{I}{R_L}}{\left[\frac{1}{R_A R_L} + \frac{1}{\omega^2 K_1^2}\right]} \tag{31}$$

$$\omega C_A - \frac{1}{\omega}\left\{\frac{1}{L_A} + \frac{1}{K_1}\right\} = 0 \text{ and } \omega C_{DP} - \frac{1}{\omega}\left\{\frac{1}{L_L} + \frac{1}{K_1}\right\} = 0 \tag{32}$$

From V_L and Vs in Equation (31), the voltage gain at resonance can be expressed as:

$$\frac{V_L}{V_S} = \frac{R_L}{j\omega K_1} \tag{33}$$

The maximum of Equation (33) is obtained when:

$$j\omega K_1 \to 0 \;\; or \;\; R_L \to \infty \tag{34}$$

Since $j\omega K_1$ is restricted by the conditions in Equation (32) to attain resonance, one cannot manipulate $j\omega K_1$ alone without changing the resonance conditions. What can drive the voltage gain is if R_L is very large at resonance conditions. If the input impedance (V_S/I) of the coupled resonator is maximum at resonance, conditions in Equation (35) hold:

$$\left(\frac{Vs}{I}\right) \to maximum \;\; when \;\; \frac{R_L}{\omega^2 K_1^2} \to 0 \tag{35}$$

Equation (36) may be assumed when $\frac{R_L}{\omega^2 K_1^2} \to 0$:

$$\frac{V_S}{I} = R_A \tag{36}$$

Under these conditions and an optimal coupling coefficient K_{1max}, the maximum voltage gain of the parallel coupled resonator can be written as in Equation (37), where K_{1max} is given by Equation (38):

$$\left|\frac{V_L}{V_S}\right| = \left|V_{gain}\right| = \left|\frac{1}{2}\sqrt{\frac{R_L}{R_A}}\right| \tag{37}$$

$$K_{1(\max)} = \mp\frac{1}{\omega}\sqrt{R_A R_L} \tag{38}$$

The analysis of Section 2.5.2 and parallel coupled RLC resonators show that any antenna and matched rectifying diode can be described as an equivalent circuit of a coupled resonator at a defined operating point. This general model can be applied to optimize other harvesters with complex output impedance such as piezo-harvesters or vibration harvesters for maximum transfer of power or voltage to its connected load. The model can also be applied to near field magnetically coupled antennas/coils for optimization.

2.5.6. Broadband RF to DC power converter

A broadband network is preferred when an RF to DC power converter is to be operated for a wide range of frequencies. A broadband converter is realized by connecting successive L-networks together in a multi-network between the antenna source and the rectifying diodes. The result is broadband or multiband RF power converter around certain frequencies. This can be deduced from the general model of a coupled resonators that by choosing certain passive components between a source and the load, it is possible to have more frequencies (ω) fulfilling Equation (32) and hence a result of multiple resonant frequencies or broader bandwidth at match conditions. For a two stage L-connected match, the quality factor of the L-network with the parallel resistance is given by Equation (39):

$$Q_P^{\,*} = \sqrt{\frac{R_P}{R^*} - 1} \tag{39}$$

The quality factor of the L-network with the series resistance is given by Equation (40):

$$Q_S^{\,*} = \sqrt{\frac{R_*}{R_S} - 1} \tag{40}$$

From Equations (39) and (40) the loaded quality factor of the two stage L-connected broadband network may be written as Equation (41) in terms of the unloaded quality factors; Q_S* and Q_P*:

$$Q^2 = \{(Q_P^{*2} + 1)(Q_S^{*2} + 1)\} - 1 \tag{41}$$

R^* in this case may be chosen if it is larger than R_S and lower than the R_P. The highest possible bandwidth between a resistive source and resistive load is found for a virtual resistance (R^*) given in Equation (42) [37]:

$$R^* = \sqrt{R_S R_P} \tag{42}$$

For complex loads such as rectifying diodes or transistors, the largest achievable bandwidth prescribed by Equation (42) is limited by the load or source component quality factor, since Equation (42) does not take into account reactive impedance associated with the source or load.

2.5.7. Broadband-Match RF to DC Converter Results and Discussion

The antenna source resistance was broadband matched to the HSMS-285C diodes (and load) resistance at −30 dBm input around 434 MHz. For a desired Q_P* and Q_S* of 2.7 there is ~0.4 pF inherent diode capacitance which is un-tuned using a two stage L-matching network [Figure 11(b)]. This is because the HSMS-285C diodes provides an inherent component quality factor of 6.96 at 434 MHz for −30 dBm input, hence a broadband circuit with Q_P* lower than this inherent component quality factor of the diodes (and load) is difficult to achieve without trade-offs. However, connected L-networks with Q_P* as high as the diode component quality factor may perform worse than a single L-matched network with similar loaded quality factor. This is due to redundant components of the connected L-networks which have inherent losses.

Figure 11. Impedance diagram of broadband RF power converter; (**a**) Broadband match around 434 MHz with loaded Q of 2.7, (**b**) Resultant impedance matching network with un-turned capacitance of 0.4 pF.


Connected L-networks
HSMS-285C and load
@ 434MHz -30dBm
Antenna;
434MHz @
P_S= -30dBm
50Ω
R_A
50nH
415nH
2.4pF
0.3pF
0.7pF
3.5 kΩ
V_L
source
50nH
415nH
2.4pF
0.4pF
R_L
V_L
Stray un-tuned capacitance
(a)
(b)

Figure 12. Measured open circuit S_{11} of the broadband circuit around 434 MHz at different input power levels from a 50 Ω source (**left**), measured open circuit input impedance at −10 dBm and −40 dBm of the broadband circuit (**right**).



Therefore the broadband circuit is matched for Q_P* of 2.7, notwithstanding the un-tuned shunt capacitance as can be seen in Figure 11(b). Figure 12 shows the circuit S_{11} at various input power levels and input impedance at open circuit conditions. From Figure 12 (left) there is ~−5 dB return loss from 200 MHz to 500 MHz providing an operating band of ~300 MHz. The impedance of the circuit shows resonances at ~290 MHz and ~450 MHz as shown in Figure 12(right). A third resonance occurs around 356 MHz at −10 dBm as the frequency of highest harvester input resistance (~350 Ω) and where the reactive impedances approach their extremes. Figure 12 show that a wireless EM harvester can exhibit different resonance scenarios depending on the dominant instantaneous conditions. The efficiency and voltage sensitivity of the broadband matched wireless EM harvester are shown in Figure 13. The average open circuit voltage is 47 mV and 1.1 V at −30 dBm and −10 dBm, respectively, when operating from 200 MHz to 500 MHz.

Figure 13. Measured open circuit voltage *versus* frequency sweep from 200 MHz to 500 MHz for −10 dBm and −30 dBm (**left**), measured efficiency at 17 kΩ load *versus* frequency sweep for −10 dBm and −30 dBm (**right**).



The broadband circuit achieves average efficiency of 5% at 17 kΩ load for −30 dBm and 30% at 17 kΩ load for −10 dBm input power from 200 MHz to 500 MHz. Figure 13 further confirm a direct link between frequency response and the unloaded quality factors. For Q_S* and Q_P* of ~2.7, the circuit response is broadband around 434 MHz.

2.6. High Voltage Sensitive RF to DC Converter

The current state of the art low power remote sensors would require a DC voltage supply of about 1 V and DC current of about 30 μA for operation. Therefore, the issue is not only how efficient a wireless EM harvester is in converting RF to DC power, but also what the output DC voltage and current of the EM harvester are at the RF input power level [38]. Equations (11,24) and (33) show that the maximum voltage sensitivity of a coupled resonator system or an RF to DC power converter is mostly related to the load and the source resistances at resonance. Therefore high voltage sensitive wireless EM harvester can be achieved with a diode voltage doubler with a very high input resistance relative to the antenna source without the need to cascade the diodes as in voltage multipliers. If the diodes been used for the RF to DC power conversion cannot provide high resistive impedance at the working frequency relative to the antenna source, then a DC-DC converter can be applied after the EM harvester as presented in [39] or the diodes may be cascaded by way of multipliers as presented in our earlier work [40] and by several other authors [3,5,14]. In case of multipliers, the input voltage ought to be high enough to overcome the junction potential of the several diodes in the multiplier network. If frequency is not a constraint, then a frequency sweep *versus* impedance for the diodes can be made and the frequency where the diodes exhibits high resistive impedance can be used to realize high voltage sensitive wireless RF harvester. For Schottky diodes, high resistive impedance occurs mostly at lower frequencies (see Figure 3). The measured voltage gain of a high resistive diode pair (voltage doubler) is presented in the next results.

2.6.1. High Voltage Sensitive RF to DC Converter Results and Discussion

The presented result was L-matched using 50 Ω resistance of the antenna source and the resistance of the HSMS-286C diodes (and load). The HSMS-286C diodes do provide high resistive impedance at low frequencies; notwithstanding the flicker noise which causes its resistive (and reactive) impedance to fluctuate. The HSMS-286C has low forward junction potential (~350 mV at 1 mA) per diode and series impedance of ~1.5–j8.1 kΩ or parallel impedance of $\sim -j8.3(46.3)/(-j8.3 + 46.3)$ kΩ at 13.6 MHz for −30 dBm input. Even though the HSMS-286C diodes unloaded component quality factor at 13.6 MHz is similar to that of the HSMS-285C diodes at 434 MHz, the elevated resistive impedance at 13.6 MHz fulfills the condition for high voltage sensitivity relative to a 50 Ω antenna source at resonance conditions.

Figure 14. (**a**) L-matched impedance diagram for matching the HSMS-286C diodes at 13.6 MHz at -30 dBm input. (**b**) Resultant network, (**c**) PCB layout of the L-matched Greinacher doubler with adjusted values due to impedances provided by copper route on FR4 substrate with thickness of 1 mm. (**d**) Fabricated PCB of the L-matched RF to DC power converter.


L-matching network
HSMS-286C and load @ 13.6MHz -30dBm
Antenna; 13.6MHz @ P_S= -30dBm 50Ω
R_A
17.8μH
7.7pF
1.44pF
R_{DP}=46.3kΩ
V_L
(a)
Resultant L-matching network
Ps
R_A
17.8μH
6.3pF
R_L
V_L
(b)
Vout_1
Vout_2
100pF
via
HSMS-286C
15μH
10cm
100pF
PCB side view
5.6pF
via
via
(c)
(d)

The high voltage sensitive EM harvester operating at 13.6 MHz is as shown in Figure 14. On the realized PCB is a Greinacher doubler. An inductance of 15 µH and a shunt capacitance of 5.6 pF were the adjusted values after the microstrip contributions.

The measured S_{11} and input impedance at open circuit are shown in Figure 15. There is high return loss and resonance around 13.6 MHz. The circuit input impedance at open circuit conditions is 58 Ω at resonance for both −40 dBm and −10 dBm.

Figure 15. Measured open circuit S_{11} of the L-matched HSMS-286C diodes at 13.6 MHz for different input power levels from a 50 Ω source (**left**), measured open circuit input impedance at −10 dBm and −40 dBm of the L-matched HSMS-286C diode at 13.6 MHz (**right**).



The efficiency and voltage sensitivity of the high voltage sensitive wireless EM harvester are shown in Figure 16.

Figure 16. Measured circuit efficiency *versus* load at various input power levels at 13.6 MHz (**left**), measured open circuit voltage and at 200 kΩ load *versus* input power at 13.6 MHz (**right**).



The maximum measured efficiency at −30 dBm is 20% for ~200 kΩ load and an open circuit voltage of 0.5 V. At −10 dBm, the maximum efficiency and open circuit voltage are 54% and 5.4 V respectively. At the optimal load of ~200 kΩ, the detected voltage is 0.2 V and 2.9 V at −30 dBm and −10 dBm respectively. The open circuit voltage gain is 100 at −30 dBm and 108 at −10 dBm.

Even though the RF to DC converter presented in Section 2.5.3 is the same as the L-match circuit realized with the HMSM-286C diodes at 13.6 MHz, the voltage gain is increased by a factor of 4 due to the large difference between the diodes (and load) resistance and source resistance so that at matched conditions high voltage gain occurs. The loaded *Q* of the L-matched circuit is 30 which results in small frequency bandwidth just like a PI-matched diode rectifier presented in our earlier work [40]. From this result and the results from our earlier presented PI-matched EM harvester, it can be inferred that all high loaded *Q* RF to DC circuits have high selectivity but not all highly selective RF to DC circuits have high loaded *Q*. The voltage sensitivity of the matched HSMS-286C diode at 13.6 MHz can be improved if its resistive impedance is not lowered by the flicker noise.

3. Wireless EM Power Harvester

A wireless EM harvester, consisting of a rectifying antenna (*rectenna*) was designed to find a compromise between size and performance of its antenna. The rectenna is shown in Figure 17.

Figure 17. Rectenna realized on a Duroid 5880, 1.57 mm substrate. (**a**) Backside of the rectenna, (**b**) cross-section of antenna output coplanar stripline dimensions (**c**) frontside of the rectenna.



(a) **(b)** **(c)**

The antenna (planar) part of the rectenna is based on our earlier work [41]. In contrast to the earlier presented antenna, this rectenna is realized on a Duroid [42] substrate of thickness 1.57 mm. Duroid 5880 has lower loss tangent of 0.0004 at 1 MHz compared to 0.025 at 1 MHz for FR4. This means there is less loss in the transmission of signals on a Duroid PCB at this frequency range. The antenna part is fabricated to resonate around 434 MHz; hence its dimensions of 5 × 5.2 cm make it electrically small. The antenna is tuned with a chip inductor and a capacitor to achieve the resonance frequency around 434 MHz [Figure 17(c)]. This is done at a cost of reduced antenna radiation efficiency. An antenna is one of the few components the size of which is related to the operating frequency. Thus, if the size of an antenna is fixed, resonance frequency reduction of the antenna can only be achieved with penalty factors [10]. The antenna's output impedance is tuned with the dimensions of the coplanar stripline as shown in Figure 17(b).

HFSS [43] was used to simulate the presented antenna and to find the correct capacitive and inductive components for frequency tuning before the optimized design was fabricated. The simulated antenna resonances occur at 438 MHz and 445 MHz. At these frequencies, the radiation efficiency is 20% and a peak gain of −6 dBi. The rectifying part of the rectenna consists of L-matched HSMS-285C diodes (Figure 17(c)). The L-matched HSMS-285C part of the rectenna can be engineered to be as small as possible if required. The separate parts of the rectenna were characterized by terminating their ends and measuring the individual reflection coefficients just like the power converters presented in Section 2. Figure 18 shows the measured antenna and matched rectifier individual S_{11} and impedance. Figure 18 (left) also show the HFSS simulated S_{11} results. From Figure 18 (right), the measured antenna resonance where the input impedance is at maximum is ~434 MHz. At ~434 MHz, the antenna input resistance is 376 Ω and the reactive impedances approach their extreme (*so called anti-resonance*). The other resonance occurs when the input resistance is 'finite' and the reactive impedance is zero; at ~441 MHz. The input resistance is 57 Ω at ~441 MHz. The rectifier circuit is matched for the antenna's resistance at ~441 MHz.

Figure 18. Antenna HFSS simulated, antenna measured, and measured L-matched diode rectifier S_{11} on a Duroid 5880 PCB for −30 dBm input (**left**), Measured open circuit input impedance of antenna and rectifier at −30 dBm input (**right**).



3.1. EM Range Results and Discussion

At far field between wireless EM transmitting and receiving antenna, the coupling mechanism between the transmitting and receiving antenna is neither capacitive nor inductive as is the case for the RF to DC converters. The coupling is radiative which can be described by the Friis equation of transmission on the assumption that the transmitting and receiving antenna are in free space [44]. A modified Friis equation for a transmitting and receiving antenna at far-field (R >> λ and R >> transmitting antenna largest dimension) to each other at a specified direction is given by Equation (43) [45]. Equation (43) assumes real world open space conditions:

$$\frac{P_r}{P_t} = F_{envt} G_t G_r \left(\frac{\lambda}{4\pi R}\right)^2, \tag{43}$$

where *Pr* is the power at the receiving antenna port, *Pt* is the power supplied at the transmitting antenna port, F_{envt} is a factor accounting for environmental effects as such ground reflections among others, *Gt and Gr* are the transmitting and receiving antenna gain (*at specified direction*) respectively. *R* is the distance between the transmitting and receiving antenna and λ is the wavelength of the transmitting EM wave. The rectenna receiving range measurements were carried out in an open space (*hall*) with the antennas 2 m above ground level. The transmitting and receiving antennas were arranged in the direction of their peak gain. The rectenna range performance is shown in Figure 19. According to Equation (43), the efficiency of RF power transferred between a sending and receiving antenna depends on controllable factors like the gain of the antennas in the arranged direction and the radiation efficiency of the antennas. Since the receiving/transmitting antenna's incorporated in remote harvesters for sensor powering are normally small in relation to their operating frequencies, they tend to be less efficient.

Figure 19. Rectenna receiving range performance by sending 17 dBm (50 mW) at a gain of −6 dBi at 437 MHz. Output DC voltage *versus* receiving distance for different loads (**left**), loads output power *versus* receiving distance (**right**).



The efficiency of the rectenna's antenna is ~20% at resonance. A 'perfectly' matched RF to DC power converter operating in its square law region has efficiencies in the region of 20% as depicted in Section 2. The transmitting antenna was the same as the antenna incorporated in the rectenna. By transmitting the EM power with a small antenna (5 cm × 5.2 cm) at 437 MHz with efficiency of ~20% and at a gain of −6 dBi, the power delivered by the rectenna is generally low at far-field from the transmitter as can be seen in Figure 19. A mediocre transmitting antenna was used to transmit the EM waves due to limitations in the European Union about transmitting EM power at certain frequencies; so the goal in the rectenna range experiment is to show the lowest limit functionality of such a harvester. At 4.2 m from the electrically small transmitting antenna transmitting at 17 dBm, the rectenna harvested DC voltage and power are 9 mV and 5 nW respectively for 10 kΩ load. It can be seen from Figure 19 that the harvested voltage/power generally degrades as an inverse square of distance from transmitter as described by Friis equation. The measured received power however alternate along this R^{-2} fit as shown in Figure 19. This anomaly is accounted for by F_{envt} [Equation (43)] as influence of ground reflections and polarization in real world open field measurements [45]. For any particular distance *R*, the signals reflected from ground can be constructive with the direct signal to the rectenna, in which case the measured power may be higher than that predicted by the original Friss equation as in [44]. The ground effect can also be destructive, in which case the measured power will be lower than what is predicted by the original Friis equation.

4. Conclusions

Optimization of Schottky diode-based RF to DC power converters using different matching techniques for wireless EM energy harvesting applications is presented. Using scattering parameters for small signal modeling, it is shown that wireless EM harvesters can be generally described as coupled resonators with efficiencies and maximum voltage sensitivity depending mostly on the source and load resistances under matched conditions. The analytical models allow systematic control in the design of passive wireless EM harvesters. Based on these analyses, a rectenna is built and tested for lower limit functionality from harvesting ambient EM waves. The analysis presented in this work may also be applied to optimize derivatives of wireless EM harvesters like RFID tags, NFC, wireless chargers *etc.*, for efficient powering of their sensors or integrated circuits. Generally, most energy harvesters and their matched loads can be described as coupled resonators and thus may be optimized with the methods presented in this work.

Acknowledgments

This work is part of the graduate program GRK 1322 Micro Energy Harvesting at IMTEK, University of Freiburg, funded by the German Research Foundation (DFG). Special thanks to Daniela Ohnemus for the PCB preparations and Uwe Burzlaff for antenna range measurements.

References

1. Fischer, J. NFC in cell phones: The new paradigm for an interactive world [Near-Field Communications]. *IEEE Commun. Mag.* **2009**, *47*, 22–28.
2. Shameli, A.; Safarian, A.; Rofougaran, A.; Rofougaran, M.; de Flaviis, F. Power harvester design for passive UHF RFID tag using a voltage boosting technique. *IEEE Trans. Microw. Theor. Tech.* **2007**, *55*, 1089–1097.
3. Karthaus, U.; Fischer, M. Fully integrated passive UHF RFID transponder IC with 16.7-µW minimum RF input power. *IEEE J. Solid-State Circuits* **2003**, *38*, 1602–1608.
4. Lee, S.H.; Jin, I.S. Interoperation of an UHF RFID reader and a TCP/IP device via wired and wireless links. *Sensors* **2011**, *11*, 10664–10674.
5. Mandal, S.; Sarpeshkar, R. Low-power CMOS rectifier design for RFID applications. *IEEE Trans. Circuits Syst. I: Regul. Papers* **2007**, *54*, 1177–1188.
6. Yu, H.; Bashirullah, R. A Low Power ASK Clock and Data Recovery Circuit for Wireless Implantable Electronics. In *Proceedings of IEEE Custom Integrated Circuits Conference, CICC '06*, San Jose, CA, USA, September 2006; pp. 249–252.
7. Hannan, M.A.; Abbas, S.M.; Samad, S.A.; Hussain, A. Modulation techniques for biomedical implanted devices and their challenges. *Sensors* **2011**, *11*, 297–319.

8. Cho, N.; Song, S.-J.; Lee, J.Y.; Kim, S.; Kim, S.; Yoo, H.-J. A 8-μW, 0.3-mm2 RF-powered Transponder with Temperature Sensor for Wireless Environmental Monitoring. In *Proceedings of IEEE International Symposium on Circuits and Systems, ISCAS*, Kobe, Japan, May 2005; Volume 5, pp. 4763–4766.
9. Brown, W.C. The history of power transmission by radio waves. *IEEE Trans. Microw. Theor. Tech.* **1984**, *32*, 1230–1242.
10. Mickle, M.H.; Mi, M.; Mats, L.; Capelli, C.; Swift, H. Powering autonomous cubic-millimeter devices. *IEEE Antennas Propag. Mag.* **2006**, *48*, 11–21.
11. McSpadden, J.O.; Chang, K. A Dual Polarized Circular Patch Rectifying Antenna at 2.45 GHz for Microwave Power Conversion and Detection. In *Proceedings of IEEE MTT-S International Microwave Symposium Digest*, San Diego, CA, USA, May 1994; Volume 3, pp. 1749–1752.
12. Sample, A.; Smith, J.R. Experimental Results with Two Wireless Power Transfer Systems. In *Proceedings of the 4th International Conference on Radio and Wireless Symposium*, San Diego, CA, USA, January 2009; pp. 16–18.
13. Umeda, T.; Yoshida, H.; Sekine, S.; Fujita, Y.; Suzuki, T.; Otaka, S. A 950-MHz rectifier circuit for sensor network tags with 10-m distance. *IEEE J. Solid-State Circuits* **2006**, *41*, 35–41.
14. Le, T.; Mayaram, K.; Fiez, T. Efficient far-field radio frequency energy harvesting for passively powered sensor networks. *IEEE J. Solid-State Circuits* **2008**, *43*, 1287–1302.
15. Yuan, F. *CMOS Circuits for Passive Wireless Microsystems*; Springer: New York, NY, USA, 2011.
16. Zbitou, J.; Latrach, M.; Toutain, S. Hybrid rectenna and monolithic integrated zero-bias microwave rectifier. *IEEE Trans. Microw. Theor. Tech.* **2006**, *54*, 147–152.
17. Ungan, T.; Le Polozec, X.; Walker, W.; Reindl, L. RF Energy Harvesting Design Using High Q Resonators. In *Proceedings of IEEE MTT-S International Microwave Workshop on Wireless Sensing, Local Positioning and RFID, IMWS 2009*, Cavtat, Croatia, September 2009; pp. 1–4.
18. Ungan, T.; Freunek, M.; Muller, M.; Walker, W.D.; Reindl, L.M. Wireless Energy Transmission Using Electrically Small Antennas. In *Proceedings of IEEE Radio and Wireless Symposium, RWS '09*, San Diego, CA, USA, January 2009; pp. 526–529.
19. Boquete, L.; Rodríguez-Ascariz, J.M.; Barea, R.; Cantos, J.; Miguel-Jiménez, J.M.; Ortega, S.; Data acquisition, analysis and transmission platform for a pay-as-you-drive system. *Sensors* **2010**, *10*, 5395–5408.
20. Heikkinen, J.; Salonen, P.; Kivikoski, M. Planar Rectennas for 2.45 GHz Wireless Power Transfer. In *Proceedings of Radio and Wireless Conference, RAWCON 2000*, Denver, CO, USA, 10–13 September 2000; pp. 63–66.
21. Akkermans, J.A.G.; van Beurden, M.C.; Doodeman, G.J.N.; Visser, H.J. Analytical models for low-power rectenna design. *IEEE Antenn. Wireless Propag. Lett.* **2005**, *4*, 187–190.
22. Hagerty, J.A.; Helmbrecht, F.B.; McCalpin, W.H.; Zane, R.; Popovic, Z.B. Recycling ambient microwave energy with broad-band rectenna arrays. *IEEE Trans. Microw. Theor. Tech.* **2004**, *52*, 1014–1024.
23. Harb, A. Energy harvesting: State-of-the-art. *Renew. Energ.* **2011**, *36*, 2641–2654.
24. Vullers, R.J.M.; van Schaijk, R.; Doms, I.; van Hoof, C.; Mertens, R. Micropower energy harvesting. *Solid-State Electron.* **2009**, *53*, 684–693.

25. Sah, C.-T. *Fundamentals of Solid-State Electronics*; World Scientific: Singapore, Singapore, 1991.
26. Wetenkamp, S. Comparison of Single Diode *vs.* Dual Diode Detectors for Microwave Power Detection. In *Proceedings of IEEE MTT-S International Microwave Symposium Digest*, Boston, MA, USA, June 1983; pp. 361–363.
27. Cardoso, A.J.; Schneider, M.C.; Montoro, C.G. Design of Very Low Voltage CMOS Rectifier Circuits. In *Proceedings of Circuits and Systems for Medical and Environmental Applications Workshop (CASME)*, Merida, Mexico, December 2010; pp. 1–4.
28. Cardoso, A.J.; de Carli, L.G.; Galup-Montoro, C.; Schneider, M.C. Analysis of the Rectifier Circuit Valid Down to Its Low-Voltage Limit. *IEEE Trans. Circuits Syst. I: Regul. Papers* **2012**, *59*, 106–112.
29. Data sheet HSMS-285x. Avago Technologies. Available online: http://www.avagotech.com (accessed on 28 September 2012).
30. Data sheet HSMS-286x. Avago Technologies. Available online: http://www.avagotech.com (accessed on 28 September 2012).
31. Hsu, T.S. Low-frequency excess noise in metal—Silicon Schottky barrier diodes. *IEEE Trans. Electron Devices* **1970**, *17*, 496–506.
32. Hastas, N.A.; Dimitriadis, C.A.; Dozsa, L.; Gombia, E.; Amighetti, S.; Frigeri, P. Low frequency noise of GaAs Schottky diodes with embedded InAs quantum layer and self-assembled quantum dots. *J. Appl. Phys.* **2003**, *93*, 3990.
33. Gomila, G.; Reggiani, L.; Rubí, J.M. Shot-noise suppression in Schottky barrier diodes. *J. Appl. Phys.* **2000**, *88*, 3079.
34. Kleinpenning, T.G.M. Low-frequency noise in Schottky barrier diodes. *Solid-State Electron.* **1979**, *22*, 121–128.
35. Lee, T.H. *The Design of CMOS Radio-Frequency Integrated Circuits*; Cambridge University Press: Cambridge, UK, 2004.
36. Advanced Design System. Agilent Technologies: Santa Clara, CA, USA.
37. Bowick, C.; Blyler, J.; Ajluni, C.J. *RF Circuit Design*; Newnes/Elsevier: Amsterdam, The Netherlands, 2008.
38. Joe, J.; Chia, M.; Marath, A.; Ang, C. Zero Bias Schottky Diode Model for Low Power, Moderate Current Rectenna. In *Proceedings of Defence Electronics Technology Seminar (DETS 97)*, Singapore, Singapore, November 1997; pp. 1–5.
39. Visser, H.J.; Vullers, R.J.M.; Veld, B.O.h.; Pop, V. Remote RF Battery Charging. In *Proceedings of Power MEMS 2010*, Leuven, Belgium, December 2010; pp. 37–40.
40. Nimo, A.; Grgic, D.; Reindl, L.M. Impedance optimization of wireless electromagnetic energy harvester for maximum output efficiency at μW input power. *Proc. SPIE* **2012**, *8341*, 83410W:1–83410W:14.
41. Nimo, A.; Grgic, D.; Reindl, L.M. Electrically small Planner Antenna for Compact Electromagnetic (EM) Wireless Energy Harvester. In *Proceedings of Power MEMS 2011*, Seoul, Korea, November 2011; pp. 310–313.
42. RT-duroid-5870–5880-Data-Sheet; Rogers Corporation: Rogers, CT, USA, 2011.

43. *HFSS*; Ansys Corporation. Ansys, Inc: Canonsburg, PA, USA, 2005.
44. Friis, H.T. A Note on a Simple Transmission Formula. *Proc. IRE* **1946**, *34*, 254–256.
45. Kvaksrud, T.I. *Range Measurements in an Open Field Environment*, *Design Note DN018*; Texas Instrum. Incorporated: Dallas, TX, USA, 2008.
46. *LabView*; National Instruments: Austin, TX, USA, 2009.

Appendix A: Measuring Setup for RF Rectifier Efficiency and Voltage Sensitivity

The measuring setup is as shown in Figure A1.

Figure A1. RF to DC Power converter characterization setup.


Keithley 2400 Source meter
Keithley 6514 system electrometer
LabView program
Agilent E4432B signal generator
RF to DC circuit

The RF to DC circuit efficiency and voltage sensitivity measurements were made with a Keithley 2400 source meter and Keithley 6514 system electrometer with an Agilent E4432B signal generator providing 50 Ω RF signal into the circuit board.

The closed circuit current drawn by the RF to DC power converter (*without load*) from the generator is first determined by the Keithley 2400 source meter; then starting from this current, the value of the current is decreased at set intervals to creates virtual load resistances to the circuit for up to a lowest current of 0.1 μA. The 6514 system electrometer is used to measure the output voltage. The number of data point is set through LabView [46] as well as the measurements. Additionally open circuit voltage or at specific loads and frequency sweep can be made through the LabView program. At −40 dBm input power and below, the detected voltages and currents were difficult to measure accurately with the measuring setup; hence measurements were made up to a minimum of -35 dBm input power. The circuit layout for the efficiency and voltage sensitivity measurements is schematically shown in Figure A2.

Figure A2. RF to DC power converter characterization circuit.


Wireless EM harvester
in
out
Keithley 2400 Source meter
Keithley 6514 system electrometer
+
-
Agilent E4432B signal generator 50 Ω input
R
PC with LabView
LabView connection with devices

© 2012 by the authors; licensee MDPI, Basel, Switzerland. This article is an open access article distributed under the terms and conditions of the Creative Commons Attribution license (http://creativecommons.org/licenses/by/3.0/).

STANDARD ANTENNA TERMS AND RELATED FORMULAS

The "IEEE Standard Definitions of Terms for Antennas" (IEEE STD-145) represents a consistent and comprehensive vocabulary suited for the effective communication and understanding of antenna theory. General use of these definitions of terms would eliminate much of the wide-spread inconsistency concerning antenna characteristics, particularly with regard to the basic parameters of gain, beamwidth, polarization and efficiency. For convenience, IEEE antenna terms of general interest are listed here. Wherever these terms appear in this catalog, the definitions given below apply. Other commonly used terms, not covered by the IEEE standard, are shown with an "*."

ANTENNA APERTURE. A surface, near or on an antenna, on which it is convenient to make assumptions regarding the field values for the purpose of computing fields at external points. **Note:** The aperture is often taken as that portion of a plane surface near the antenna, perpendicular to the direction of maximum radiation, through which the major part of the radiation passes.

ANTENNA EFFICIENCY OF APERTURE - TYPE ANTENNA. For an antenna with a specified planar aperture, the ratio of the maximum effective area of the antenna to the aperture area.

*** ANTENNA FACTOR.** That quantity by which the voltage developed across the output of an antenna is related to the incident field strength in which the antenna is immersed. **Note:** Applicable to low frequency antennas and usually refers to a 50 ohm output.

$$\mathrm{AFE\ (dB\ m^{-1}) = E\ (dB\ V/m)\ -\ V\ (dB\ V)}$$

AFE = Electric Field Antenna Factor
E = Electric Field Strength at antenna
V = Voltage at terminals of antenna

$$\mathrm{AFH\ (dB\ AV^{-1}\ m^{-1}) = H\ (dB\ A/m) - V(db\ V)}$$

AFH = Magnetic Field Antenna Factor
H = Magnetic Field Strength at antenna
V = Voltage at terminals of antenna

$$\mathrm{AFE\ (dB\ m^{-1})\ =\ AFH\ (dB\ AV^{-1}\ m^{-1}) + 51.53}$$

for a plane wave in free space.

$$\mathrm{AFB\ (dB\frac{pT}{\mu V})\ =\ B\ (dBpT)\ -\ V_o\ (dB\mu V)}$$

AFB = Magnetic flux Antenna Factor
B = Magnetic flux at the antenna
pT: picoTesla units
V = Voltage at the terminals of the antenna

$$\mathrm{AFB\ (dB\frac{pT}{\mu V}) = AFH\ (dB\frac{A}{Vm})\ + 2}$$

APERTURE ILLUMINATION. The field over the aperture as described by amplitude, phase, and polarization distributions.

APERTURE ILLUMINATION EFFICIENCY. For a planar antenna aperture, the ratio of its directivity to the directivity obtained when the aperture illumination is uniform.

BEAM. The major lobe of the radiation pattern.

CIRCULAR POLARIZATION. It may be either right hand circular polarization (RHCP) or left hand circular polarization (LHCP). The sense of polarization is determined by observation of the direction of rotation of the electric field vector from a point behind the source, RHCP and LHCP correspond to clockwise and counter-clockwise respectively. **Note:** RHCP transmit requires a like polarization to receive.

CO-POLARIZED. The polarization which the antenna is intended to radiate or receive. Also "like polarization".

*** CROSS POLARIZATION DISCRIMINATION (XPD).** Cross polarization discrimination is the measure of the antenna's ability to differentiate between the vertical and the horizontal polarization of an antenna. This difference, shown in relative signal level, is indicated on directional pattern envelopes (DPE's).

STANDARD ANTENNA TERMS AND RELATED FORMULAS

* **DIRECTIONAL PATTERN ENVELOPES (DPE'S).** In accordance with standard practice, radiation characteristics in any given plane of polarization are measured and plotted using 360-degree polar coordinate systems. The resultant Directional Pattern Envelope is the smoothed composite of all these measurements. The purpose of these DPE's is to emphasize the worst composite condition.



DIRECTIVE GAIN. In a given direction, 4 times the ratio of the radiation intensity in that direction to the total power radiated by the antenna.

DIRECTIVITY. The value of the directive gain in the direction of its maximum value.

EFFECTIVE AREA OF AN ANTENNA. In a given direction, the ratio of power available at the terminals of a receiving antenna to the power per unit area of a plane wave incident on the antenna from that direction, polarized coincident with the polarization that the antenna would radiate.

FAR FIELD REGION. That region of the field of an antenna where the angular field distribution is essentially independent of the distance from a specified point in the antenna region.

* **FRONT-TO-BACK RATIO.** The ratio of the maximum directivity of an antenna to its directivity in a specified rearward direction.

* **Gain, dBi.** The gain expressed in decibels relative to an isotropic radiator that is linearly polarized.

$$G(dBi) = 10\log(G) \qquad G = 10^{\frac{G(dBi)}{10}}$$

* **GAIN, dBic.** The gain expressed in decibels relative to an isotropic radiator that is circularly polarized.

HALF-POWER BEAMWIDTH. In plane containing the direction of the maximum of a beam, the angle between the directions in which the radiation intensity is one half the maximum value of the beam.

HALF-WAVE DIPOLE. A half wavelength antenna, center fed so as to have equal current distribution in both halves. Mounted vertically, it has a doughnut shaped pattern, circular in the horizontal plane. It is an antenna that can be constructed. It has some inherent losses. When used as a gain reference, the half-wave dipole has a power gain of about 1.7 dBi.

* **ISOLATION.** Refers to the ability of one port of a dual polarized feed to discriminate against a signal fed into the other port.

ISOTROPIC RADIATOR. A hypothetical antenna having equal radiation intensity in all directions. Note: An isotropic radiator represents a convenient reference for expressing the directive properties of actual antennas.

NEAR-FIELD REGION. The spherical region of space between the antenna and the far field region.

NULL. The region of a radiation pattern, either computed or measured, where the amplitude goes through a minimum value. Note: (1) It represents the angular position where the phase or the far field pattern crosses the zero axis if the pattern is plotted as a phasor instead of a scalar value. Note: (2) The region outside the main beam of a directive antenna pattern consists of a series of minor lobes separated by nulls.

PARALLEL POLARIZATION. The condition where the electric vector is parallel to the local conducting surface. Note: Over the earth, this is usually referred to as being horizontal polarization.

PHASE CENTER. The location of a point associated with an antenna such that, if it is taken as the center of a sphere whose radius extends into the far-field, the phase of a given component over the surface of that radiation sphere is essentially constant, at least over the portion of the sphere where the radiation is significant.

STANDARD ANTENNA TERMS AND RELATED FORMULAS

POLARIZATION. The polarization of an antenna is defined as the polarization of the electromagnetic wave as described by the shape and orientation of an ellipse, which is the locus of the extremity of the field vector, and the sense in which the ellipse is traversed with time. The elliptical locus is called the polarization ellipse and the wave is said to elliptically polarized. Circular polarization and linear polarization are degenerate cases of elliptical polarization.

POWER DENSITY AT A POINT

$$S_{av} = \frac{GP_t}{4\pi r^2}$$

S_{av} = Time average power density in W/m^2
P_t = Power transmitted in watts
G = Antenna gain relative to an isotrope
r = Distance from antenna to point in meters

POWER DENSITY TO VOLTS/METER IN FREE SPACE

$$E^2\ (V/m) = 377\ S_{av}\ (W/m^2)$$

$$S_{av}\ (W/m^2) = E^2\ (V/m) / 377$$

$$1\ V/m = 2.65\ mW/m^2$$

POWER GAIN. In a given direction, 4 times the ratio of the radiation intensity in that direction to the net power accepted by the antenna from the connected transmitter. **Note:** (1) When the direction is not stated, the power gain is usually taken to be the power gain in the direction of its maximum value. (2) Power gain does not include reflection losses arising from mismatch of impedance.

POWER GAIN IN PHYSICAL MEDIA. In a given direction and at a given point in the far field the ratio of the power flux per unit area from an antenna to the power flux per unit area from an isotropic radiator at a specified location with the same power input as the subject antenna.

Note: The isotropic radiator must be within the smallest sphere containing the antenna. Suggested locations are antenna terminals and points of symmetry, if such exist.

POWER GAIN REFERRED TO A SPECIFIED POLARIZATION. The power gain of an antenna, reduced by the ratio of that portion of the radiation intensity corresponding to the specified polarization to the radiation intensity.

POWER TRANSMISSION FORMULAS

$$P_r = P_t \frac{G_t G_r \lambda^2}{(4\pi r)^2}$$

$$P_r\ (dB\ W) = P_t\ (dB\ W) + G_t\ (dBi) + G_r\ (dBi) - 20 \log r - 20 \log f + 27.56$$

$$P_r\ (dB\ W) = P_t\ (dB\ W) - AFE_t\ (dB\ m^{-1}) - AFE\ (dB\ m^{-1}) - 20 \log r + 20 \log f - 32$$

P_r = Power received
P_t = Power transmitted
G_r = Gain of receiving antenna
G_t = Gain of transmitting antenna
f = Frequency in MHz, λ = Wavelength
r = distance between antennas in meters
AFE_r = AFE of receiving antenna
AFE_t = AFE of transmitting antenna

RADIATOR. Any antenna or radiation element that is a discrete physical and functional entity.

RADIATION, ELECTROMAGNETIC. The emission of energy in the form of electromagnetic waves.

RADIATION INTENSITY. In a given direction, the power radiated from an antenna per unit solid angle.

RADIATION LOBE. A portion of the radiation pattern bounded by regions of relatively weak radiation intensity

RADIATION PATTERN (ANTENNA PATTERN). A graphical representation of radiation properties of the antenna as a function of space coordinates. **Note:** (1) In the usual case the radiation pattern is determined in the far-field region and is represented as a function of directional coordinates. (2) Radiation properties include power flux density, field strength, phase, and polarization.

*** RADIATION RESISTANCE OF AN ELECTRICALLY SMALL LOOP ANTENNA.** The resistive component of an antenna's input impedance that results from the coupling of the antenna to its environment. This resistance dissipates the power that is actually radiated from the antenna.

$$R_r = 20\,(2\pi/\lambda)^4 n^2 A^2 \text{ ohms}$$

n = number of turns
A = area of the loop

REALIZED GAIN. The power gain of an antenna in its environment, reduced by the losses due to the mismatch of the antenna input impedance to a specified impedance.

*** REALIZED RADIATOR EFFICIENCY.** The efficiency of an antenna in its environment reduced by all losses suffered by it, including: ohmic losses, mismatch losses, feedline transmission losses, and radome losses.

RELATIVE POWER GAIN. The ratio of the power gain in a given direction to the power gain of a reference antenna in its reference direction. **Note:** Common reference antennas are half-wave dipoles, electric dipoles, magnetic dipoles, monopoles, and calibrated horn antennas.

RETURN LOSS. The reflection coefficient of a mismatch expressed in decibels. **Note:** Modern swept VSWR techniques actually sense the reflected component which is normalized to the forward component to yield return loss. A 2:1 VSWR is equivalent to 9.5 dB return loss.

VSWR. The voltage standing wave ratio of a component such as an antenna. It is referred to the characteristic impedance of the transmission line being used. **Note:** The most common characteristic impedance is 50 ohms, but 75 and 300 ohms are frequently used in coaxial or twin lines for VHF, UHF applications.

NOTES:

THE HANDYMAN'S GUIDE TO OSCILLOSCOPES (Part 2 of 2)

by Paul Harden, NA5N

Making some advanced measurements with your Oscilloscope

Print as .pdf file
4 pages
8½ x 11 or A4

In Part 1, oscilloscope operation was covered for making basic voltage, time and frequency measurements. In this part, we'll continue with some more advanced uses of a scope, and in particular, how to use a scope for testing and troubleshooting ham radio QRP transceivers in the homebrewer's workshop.

Receiver Filter Bandwidth.

This procedure uses a scope (a DVM can be used with less accuracy) for determining the overall filter bandwidth (or selectivity) of a receiver. It is basically measured by plotting output voltage vs. audio frequency to construct a picture of the filter response.

Connect scope to the receiver audio output (speaker or phone jack); measurement will be based on peak-to-peak voltages (Vpp) on a scope, or rms voltage (Vrms) on a DVM.

Using a signal generator, set the frequency for the band of interest on your radio. For example, on a general coverage shortwave receiver, you might set it for 10 MHz (top end of the 31M band), or perhaps to 7.040 MHz on a 40M ham radio receiver/transceiver. Tune the receiver to the signal generator signal. If you don't have a signal generator, you can also tune to a steady carrier or station to produce a hetrodyne audio "pitch." Tune in the signal to the pitch that causes the maximum peak-to-peak display. Adjust the scope and volume control to produce a 2Vpp display (4 divisions). This is the peak response of the overall filtering stages as shown in **Fig. 13**.

Now determine the audio frequency at this peak response by measuring the time period between cycles and covert to frequency. In the example to the right, the period of one cycle is 1.7mS, which is an audio tone of 750Hz (1/.0017sec). A frequency counter on the output can also be used.

Next, tune the receiver such that the sidetone pitch goes UP in frequency and the peak-to-peak signal will decrease in magnitude. Tune to the point where the signal is exactly 1Vpp on the scope. See **Fig. 12**.

This is the –6dB point of the high end of the filter (20log 1v/2v =–6dB). Determine the frequency of the audio pitch as before. In the example, this is 1100 Hz. Record the data.

From these two data points, the –6dB bandwidth can be estimated. The bandwidth from the filter peak (750 Hz) to the –6dB point (1100 Hz) is 350 Hz. The bandwidth (BW) between the two –6dB points is usually twice this value, or 700 Hz. A filter with a –6dB BW of 700Hz is a mediocre filter for CW reception, and way too narrow for SSB or AM.

Of course you can determine the exact –6dB BW by tuning the receiver back to the 2Vpp peak response, and continue tuning DOWNward in frequency until the audio is again exactly 1Vpp. Determine this frequency and record. In this example, it should occur around 400 Hz if the filter shape is symmetrical.

Plot these three data points on a sheet of graph paper as shown in **Fig. 15** to construct the filter shape. Return to the upper –6dB point (1100Hz in the example) and continue tuning upwards in audio pitch, recording the frequency at 0.5v (–12 dB), 0.25v (–18 dB), 125mV (–24 dB), etc. Everytime you "halve the voltage," it is a 6 dB change. The more points you collect, the more accurate your filter response plot will be.

Fig. 13 – Displaying Filter Peak Response



Set peak filter response for 2Vpp vertical display, then determine the audio freq.

=1.7mS = 750 Hz Audio Tone

Fig. 14 – Displaying –6dB Frequency



Tune receiver until vertical display is 1/2 of 2Vpp peak, or 1Vpp, for the –6dB point.

=900uS = 1100 Hz Audio Tone

Of interest to proper rig alignment is to repeat the above using the output of the product detector. To maximize the effectiveness of the filtering, the receive offset frequency set by the BFO should be adjusted to the same frequency as the peak frequency response of the audio. In this example, with the peak audio response occuring at 750Hz, if your BFO is set for a sidetone frequency of 700 Hz, you are loosing 2–3 dB, since this is in your filter skirt. This is shown on the response plot in **Fig. 15** by the dashed lines. By adjusting your BFO for a sidetone frequency of 750 Hz, you will pick up 3-4dB of overall gain in your receiver, plus increase the selectivity a bit as well. Why? Because nearby stations, such as one at 800–900Hz tone, could actually be louder than the 700Hz tone signal you are trying to copy, since the gain of the receiver is greater at those tones than at 700Hz, as shown in the plot.

Fig. 15 – Plotting Audio Response



Opposite Sideband Rejection

A superhet receiver is supposed to pass just one sideband and reject the other. Poor opposite sideband rejection could indicate the crystals in your IF filter are not well matched or other problems. It is measured almost identical to plotting the filter response just described. First, you tune the receiver to the test signal to find the peak response frequency, or 750Hz in this example. Set the scope display for 2Vpp. Now tune downward in audio pitch, passing zero-beat, and continue tuning and you should hear the test signal, much weaker, now rising again in tone. This is the *opposite sideband*. Measure the peak-to-peak voltage, if you can. For example, say it is 80mVpp, as shown in **Fig. 16**. Calculate the opposite sideband rejection by:

$$\text{rejection} = 20\log\frac{80\text{mV}}{2.0\text{v}} = \frac{80\text{mV}}{2000\text{mV}} = -28\text{dB}$$

If you can't hear the opposite sideband, then obviously you have excellent filter rejection. If you can just barely hear it, you may have to increase the sensitivity of your scope (set vertical gain to 20 or 50 mV/div). In this example, –28dB rejection of the opposite sideband is quite good. A –30dB rejection means the opposite sideband is only 1/1000th of the desired sideband, a very suitable attenuation of the opposite sideband.

Fig. 16

Calculating Opposite Sideband Rejection



These tests are important to perform on your rig for documenting it's current performance, and repeated periodically to detect unfavorable changes or for troubleshooting when a problem is evident. For homebrewing, these tests can allow you to evaluate different circuits or when experimenting with different components or part values.

Oscillator Phase Noise

When homebrewing a basic oscillator circuit, such as a VFO, looking at the oscillator output on a scope can reveal several problems. One is to check for excessive phase noise. Phase noise is small variations of the oscillator frequency that causes power in the close-in sidebands, usually measured on laboratory equipment within 100KHz, or even within 10 KHz.

To check for oscillator phase noise, connect the oscilloscope to the oscillator output, loading the output of the oscillator as little possible. Most scopes have sufficiently high input impedances where this shouldn't be a problem, but some cheaper scopes can load an oscillator circuit. If you suspect your scope is loading the oscillator, couple the scope to the circuit with a small value capacitor, less than 20pF.

Fig. 17 – Checking Oscillator Phase Noise



Check for a clean, focused signal here

Check for an out-of-focus or thicker signal here

Display 2–3 cycles of the oscillator output as shown on the scope display shown in **Fig. 17**. Properly focus the scope and carefully observe if the waveform appears in focus at the peaks, but slightly out-of-focus at the zero-crossing points, that is, on the rising and falling edges of the sine wave.

If it appears out-of-focus, this is excessive phase noise jittering the signal and "smearing" the waveform along the time (horizontal) axis. Extreme phase noise may show 2-3 sine waves very close to each other, as shown in the exagerated waveform to the right — assuming you have your scope properly triggered.

Phase noise is random, instantaneous changes in the oscillator frequency that smears the display. If you can see this on a scope, the phase noise is excessive! If you can't see it, it doesn't mean the oscillator has no phase noise (all oscillators have some phase noise), it just means it is not excessive enough to see on a scope. A scope is not a good instrument for checking phase noise, but for homebrew circuits, it is a check to ensure you do not have a serious oscillator problem.

Excessive oscillator phase noise in receivers can cause IMD products and noise in the audio range at the output of the mixer(s), including the product detector. In a transmitter, excessive oscillator phase noise will put power in the close-in sidebands of your carrier, not only wasted power for lower transmitter efficiency, but may produce strange sounds (buzzing or chirping) to the receiving station. A few causes of phase noise are excessive current in the oscillator transistor, low-Q coil(s), high dissipation in the tuning caps or poor power supply filtering at the oscillator frequency.

AM (Amplitude) Noise

Another oscillator problem may be AM noise, or amplitude modulated noise. It is an opposite effect on a scope when displaying the oscillator output — the sine wave appears out-of-focus or thicker at the peaks, and in-focus elsewhere as shown in **Fig. 18**.

Fig. 18 – Checking for AM Oscillator Noise



Check for an out-of-focus or thicker signal here

Check for a clean, focused signal here

If you detect AM noise, slow down the scope's sweep rate to the audio frequencies or slower to see if you can notice a lower frequency component. A common cause of AM oscillator noise is 60 Hz from the power mains leaking into the circuits. This is particularly true if using a power supply off of 120v 60 Hz, or sometimes it can be due to the AC lighting above your head! If the AM noise seems to be at the same frequency as the audio output tone, it means audio is getting into the Vcc bus, likely due to poor bypass filtering at the audio amplifier stages (particular if using an LM386 or similar).

If you can't find a low frequency component, the AM noise may be random, which may indicate poor voltage regulation, a noisy voltage regulator, or perhaps a circuit in VHF oscillation. If the AM noise seems to occur on key-down only on a transmitter, the transmit current may be loading the power supply, the voltage regulator is under-rated, or just simply loading the oscillator. In the case of loading the power supply or regulator(s), perhaps a separate voltage regulator or zener circuit should be used, dedicated for the oscillator(s). In the case of transmit loading, adding a buffer amplifier or emitter follower to isolate the load from the oscillator may help.

Much of this can be diagnosed also with the scope, by looking at the AC ripple on the DC power lines. You should have less than 50mV of any AC component on the 8-12v DC wiring, whether 60Hz, audio or RF. If >50mV, then additional low or high frequency filtering on the DC power is needed.

Monitoring Transmitter RF Output

RF Power (in watts) is E^2/R, where E is in rms and R=50 . The voltage displayed on the scope (peak-to-peak) must be converted to rms by Erms=.707(Epp/2). To measure properly, the transmitter should be on a 50 dummy load using the normal hi-Z scope input. If your scope has a selectable "50 "input, it can be the transmitter dummy load directly, providing it can tolerate the 50Vpp input. (Always know what the maximum p-p input voltage your oscope will tolerate. It is often stated on your scope at the vertical channel inputs. 50Vpp to 100Vpp are typical).

Measuring Transmitter RF Output Power

Figure 19 shows how you can use an oscilloscope to fairly accurately measure output power from a low power transmitter (generally 10W or less with a 1X probe and 20-30W with a 10X probe). Connect transmitter output to a 50 dummy load. Connect the scope lead to the transmitter output (after the low pass filters) or directly to the dummy load. Do not connect the scope leads to the collector or drain of the final PA transistor. The displayed voltage in this case will be erroneous.

In the example, the output transmit voltage across the dummy load measures 24Vpp. Convert this voltage to Vrms, then use the equation (Vrms squared divided by the load resistance) to calculate the power in watts. In the example, 24Vpp, the output power is 1.4 watts. A 5W QRP transmitter should produce about 45Vpp.

The accuracy of your power measurements depend upon the condition of your oscilloscope:

1) Ensure your scope's vertical sensitivity (volts/division) is properly calibrated (see Part I)
2) Ensure your vertical sensitivity is properly calibrated with the 1X or 10X probe you are using.
3) Ensure that the transmitter frequency is well within the bandwidth of your scope. A 100 MHz scope should give reliable readings on all HF bands. A 50 MHz scope should be reliable on all HF bands except slight errors at 28MHz.

Fig. 19 –Oscilloscope as a Power Meter



1. Measure output voltage. 24Vpp
2. Convert Vpp to Vrms
Vrms=.707(Vpp/2) 8.5Vrms
3. Calculate power in watts

$$\frac{Vrms^2}{R} = \frac{8.5v^2}{50} = 1.4W$$

Checking Transmitter Purity

Phase Noise of the transmitter is measured identically to the phase noise checks on page 2–3. With the scope properly triggered and focused, you are looking for an out-of-focus "fuzziness" around zero crossing. If it appears phase noise exists, the fault is generally at the beginning of the transmit chain. That is, seldom does the PA transistor add phase noise; it's merely amplifying what it is given. Phase noise on the transmitter output is more likely due to the transmit oscillator, or the transmit mixer if used.

Harmonic Power can also be detected on a scope while looking at the transmitter RF output power. In **Fig. 20**, notice the "dips" or the two "peaks" on the top and bottom of each sine wave. This is caused by excessive 2nd harmonic output power. The rule-of-thumb is – if you can see any 2nd harmonic power (a dip or flattening at the peaks), then you are right at or exceeding the –30dBc FCC harmonic specification. A clean sine wave implies FCC compliance, providing the 2nd harmonic is within your scope's bandwidth. Obviously, a spectrum analyzer should be used for accurate harmonic evaluation, but a scope can be used to indicate if you have a problem. If you build your own transmitter, it is your responsibility to ensure it is compliant. An approximate method of estimating 2nd harmonic attenuation is shown.

–30dBc means the 2nd harmonic power is 1/1000th of the fundamental power. For a 5W transmitter, this means the 2nd harmonic power should be 5mW or less, or about 1Vpp. In displaying a 5W signal on a scope (45Vpp), it would be difficult to resolve much less than a 1Vpp dip or ripple.

Fig. 20 –Checking 2nd Harmonic Power



1. Measure output voltage. 24Vpp
2. Measure ripple voltage. 1Vpp
3. Calculate dBc of 2nd harmonic ripple

$$20\log\frac{V2}{V1} = 20\log\frac{1v}{24v} = -27.6\text{ dBc}$$

or, not quite FCC compliant!

Conclusion. This concludes the NA5N "Handiman's Guide to Oscilloscopes." Hopefully, it has helped you to understand your oscilloscope to make simple measurements, and with some practice, perform the more advanced measurements discussed. An oscilloscope is a very powerful tool that is invaluable on the homebrewer's workbench. If there is a particular measurement you feel I omitted, please let me know and I will add it when time permits.

73, Paul Harden, NA5N (na5n@zianet.com or pharden@nrao.edu)

THE HANDYMAN'S GUIDE TO OSCILLOSCOPES (Part 1 of 2)

by Paul Harden, NA5N

Print as .pdf file
5 pages
8½ x 11 or A4

Getting Acquainted with your Scope and making some measurements

Updated May 2004 with actual oscope waveforms

When in the course of human events, it becomes necessary to look at neat signals floating around your radio, you go to a hamfest and buy that $50 o-scope. Now what? This two part article will attempt to explain basically how an oscilloscope works, operator functions, basic measurements, and some advanced applications. An o-scope is a powerful tool in any shack – even a real "cheapie" with limited bandwidth.

HOW AN OSCILLOSCOPE WORKS

A block diagram of a typical o-scope is shown in **Fig. 1**. The test probe usually plugs into the scope via a BNC connector, then passes through a switch to determine whether the input signal will be dc or ac coupled (to remove any dc component). Often this switch will have a "ground" position for setting the zero-volts reference. Next is the input attenuators. The vertical input amplifier is quite sensitive, designed for 20-50mV of input. For larger input voltages, the signal is applied to attenuators comprised of simple voltage dividers. This is the first area of concern for cheap o-scopes, as the input attenuators may not be very linear or accurate. For example, if you appy a 10Vpp signal on the 10v/division setting, the signal should be 1 division high. Switching to 1v/div., the signal should be 10 divisions (usually full-scale) high. If it is not exactly 10 divisions, the attenuator for that setting needs adjusting. Some scopes have internal adjustments for fine-tuning each attenuator setting.

Following the attenuators, the signal is applied to the first vertical amplifier, which converts the input to a differential signal. This differential signal is amplified up to high voltages for the oscilloscope deflecting plates – moving the beam up and down (in the vertical axis).

The sweep generator is usually a constant current source charging a capacitor to make a sawtooth waveform that eventually deflects the beam in the horizontal axis. The frequency of the sawtooth determines how fast the beam travels from the left to the right side of the tube, and is controlled by the sweep control, usually calibrated in seconds, milli-seconds or micro-seconds per division. This is the second area of concern for an oscilloscope – how linear the sawtooth waveform is generated. For example, a sawtooth with a nonlinear ramp will cause the signal displayed in the central portion of the tube to be expanded or compressed compared to the signal at the ends.



FIG. 1 - Basic block diagram of an Oscilloscpe

The sawtooth ramp is amplified to high voltages, applied to the oscope tube, to deflect the beam from left to right. An important task of an oscope is when the horizontal deflection begins. Normally a switch labeled "Trigger Source" determines what initiates the sawtooth ramp. In the "Internal" position, a sample of the input signal (in the vertical amplifiers) is sampled, with a variable resistor setting the level. When the input signal exceeds the "Trigger Level," a pulse is generated to start the sawtooth ramp and hence the horizontal sweep. The purpose of triggering is to keep the input waveform synchronized to the sweep so it appears stationary on each sweep. The trigger source usually has a "Line" position, which simply triggers the sweep off of 60Hz from the power supply. This synchronizes the sweep to the AC power frequency and is useful for checking television signals, which are synchronized to the power mains. Also, an "External" position may be present, which connects an external input signal (via a BNC connector) to trigger the sweep generator.

Other features your oscope may have are two vertical channels for dual trace operation, various modes to display both waveforms (alternate, chopped, A+B added, etc.), delayed sweep features, dual sweep time bases, built in calibrators, etc.

CALIBRATING YOUR OSCILLOSCOPE

The first thing you should do upon acquiring an o-scope is to check its calibration.

The vertical amplfiers can be checked with a known voltage source or 9v transistor radio battery. Measure the output voltage of the battery with an accurate voltmeter. Let's say it just happens to be +9v exactly. Set the input coupling to ground (0v) and move the trace to the bottom division. Switch the input coupling to DC and set the attenuators to 1v/div. The deflection should be 9 divisions. Switching to 10v/div., deflection should be 0.9 divisions. Internal to the oscope (or perhaps accessible from the outside) are adjustments for the vertical amplifier gain. Adjust this for 9 divisions of deflection in the 1v/div. range. Procedure can be repeated with a 1.5v flashlight battery (assuming you know the exact voltage from a DVM).

The horizontal amplifiers should be checked/calibrated using a signal generator. For example, a 1MHz signal has a period of 1uS. Setting the sweep rate to 1.0uS/div., a 1MHz signal should take exactly 1 division per cycle. Set the horizontal width control properly to ensure the beam starts at the first division and ends at the last division. If the sweep rate appears incorrect, an internal adjustment (Sweep gain or similar) can be set for proper display of the test signal.

The main operator controls are:

- **Intensity** - controls the brightness of the beam. **NOTE: Too bright a beam can damage to the CRT tube!**
- **Focus** - adjusts the beam for the thinnest and sharpest display.
- **VERT & HOR Position** - controls the vertical and horizontal position of the display respectively
- **VERT V/div** - controls the vertical sensitivity of the display, i.e., how many volts (or mV) per division.
- **HOR Sweep Speed** - sets the horizontal sensitivity, i.e., how many mS or uS per division.
- **VERT & HOR vernier** - allows the vertical and horizontal sensitivity settings to be varied in small steps.

Other adjustments you may find on your scope are:

Astigmatism - With the scope intensity and focus properly set, this adjustment compensates for the curvature of the CRT tube by making it in-focus across the sweep. If your trace is out-of-focus in certain areas, but in-focus elsewhere, the astigmatism needs to be adjusted. See ***Fig. 2***.

Trace Rotation - is a small coil around the CRT that skews the trace to ensure it is perfectly horizontal. On scopes without this adjustment, the trace is leveled by physically rotating the CRT to align the trace to the graticle grid. See ***Fig. 2***.

Fig. 2 – Effects of Astigmatism & Trace Rotation



DC BAL (DC Balance) - is a dc offset in the vertical amplifiers that causes a shift in the trace baseline when changing vertical scales. It is most obvious when measuring ac voltages. For example, you are displaying a 10Vpp sine wave, centered on the center graticle, at 2v/div. Changing to 5v/div, the sine wave shifts off the center graticle ... that is, it assumes a dc bias error. The DC BAL is adjusted until the shift no longer occurs when changing vertical scales.

HV ADJ. - is the high voltage that controls the intensity of the trace. Turn up the **Intensity** control to its brightest position, then adjust the HV ADJ for a trace slightly brighter than normal intensity. The **Intensity** control now has the proper range. The HV ADJ might have to be re-adjusted to acquire proper focus.

NOTE: Very bright trace displays can cause permanent damage to the CRT, particularly on a well-used scope.

LET'S MAKE SOME MEASUREMENTS

It is assumed you have your scope relatively calibrated and familiar with the front panel controls. The sample o-scope displays are based on eight vertical and ten horizontal divisions on the CRT screen, typical to most oscilloscopes. Most waveforms are actual displays of the signal cited, photographed from my trusty Tektronix 475 oscilloscope.

First ... a word on TRIGGERING.

Most oscilloscopes have a knob or two for "Triggering." This tells the oscilloscope when to start the sweep. When the **Triggering Slope** is placed in the **(+)** position, the scope will begin its trace when the *input* signal goes positive. Likewise, when **(–)** triggering is selected, the trace will begin when the input signal goes negative, as shown in **Fig. 3**. Often there will be the option to chose the **Triggering Source**, such as "CH.1" or "LINE." Line means the scope is triggered off the 60Hz line voltage, and is useful when synchronizing on television signals or looking at 60Hz power supply noise. CH.1 or CH.2 means the scope will trigger off the signal on channel 1 or 2 respectively. **Trigger Level** is at what voltage of the input signal triggering begins. For example, if set high, triggering may not begin until the input signal reaches several volts. When set around zero, it will trigger the moment the signal goes positive (if set for (+) triggering). This setting can be troublesome if noise exists on the signal. Adjust for stable triggering.

Fig. 3 – Triggering



DC Voltages.

Say you want to check the transmit-receiver (T-R) switch in your QRP rig, or other digital signal. See ***Fig. 4.*** The key line is the input to the HCT240 inverter to form the 0v TX– on key- down and the 0v RX– on key- up. This switches the rig between transmit and receive (T-R Switch). It is a logic function, that is, a voltage to represent ON or OFF.

Place the scope lead on pin 13 at 10v/div. and you should see the waveform like the top trace in ***Fig. 4*** ... about +6v on key-up and 0v on key down. Move the scope lead to pin 7 and you should see 0v on key-up and about +8v on key-down (bottom trace). If the output does not go "HI" (+8v) on key-down, or does not go to a solid "LO" (<1v) on key-up, the inverter is not working properly. (It's busticated). Many shortwave receivers use similar schemes for switching filters or attenuators.

While this test could be done with a DVM, the integration time is slow, requiring long key-downs to get the voltages. A scope will also show you how clean the switching is, or if there is an ac voltage (or RF noise) riding on the T-R voltage.

Scopes are thus good dc voltmeters, with about a 5% reading accuracy.



Fig. 4 - 38-Special T-R Switch



VERT: 10v/div DC
HOR: 500mS/div

AC Voltages.

Here is where an oscilloscope pays for itself by making AC voltage (and frequency) measurements. You must remember, AC voltages are displayed on a scope as ***peak-to-peak*** **voltages**, while a voltmeter measures in ***rms***. RMS voltages are about 1/3 the p-p voltage read on a scope, or specifically:

$$V_{rms} = \tfrac{1}{2}(.707 \times V_{pp}) = 0.354 \times V_{pp}$$

For example, let's measure the output voltage and frequency from the sidetone oscillator in your QRP rig. Place the scope lead on the audio amplifier output. On key-down, you get the waveform shown in ***Fig. 5***. The transmit sidetone audio is 1.9Vpp.



VERT: 0.5v/div ACV
HOR: 0.5mS/div

3.8 divisions
peak-to-peak
times 0.5v/div
= 1.9 Vpp
= 0.67 Vrms

Fig. 5

AC Frequency Measurement.

With this waveform, we might as well see what frequency our sidetone or transmit-offset frequency is. Most operators prefer the sidetone to be about 700–750Hz. Trigger the scope for a stable waveform and set the time-base (sweep) to display 2 or 3 cycles, as shown in ***Fig. 6***. Center the waveform between two horizontal divisions so zero volts on the waveform is on a graticle line, then move the horizontal position so the first "zero– crossing" is also on a division line.

Measure the time it takes to make one complete sine wave from one zero-crossing to the next. In this example, it is 1.5 divisions, at 1mS per division, or 1.5mS. Frequency is simply the reciprocal of time, such that the sidetone frequency is:

$$f = \frac{1}{t} = \frac{1}{1.5mS} = 667\ Hz$$

For some, this may be about right. For others, this may be a little low to your liking. To raise it to 700Hz, calculate the time period of 700Hz (1/700 = 1.4mS). At 1.0mS/div, you can adjust your sidetone or transmit offset until zero-crossings for a single sinewave is 1.4 divisions. This will be about 700 Hz. (Sidetone may not be adjustable on some rigs).

All frequency measurements are made in this fashion, by measuring the distance between zero-crossings (or from one peak to the next) and converting the time period to frequency. This should emphasize the importance of ensuring your sweep speed is calibrated; as any error in the time base will cause a corresponding error in the accuracy of your time or frequency measurements.

Fig. 6

VERT: 0.5v/div ACV
HOR: 0.5mS/div

0v

First "Zero Crossing"



3 divisions between "zero-crossings"

=1.5mS
=667Hz



Fig. 7

Example of Waveform Quality

VERT: 2v/div ACV
HOR: 1.0mS/div

Quality of the waveform is another feature of a scope that is unsurpassed since you are "seeing" the waveform in real time. Two examples of waveform quality are shown in ***Fig. 7***.

The top trace shows the sidetone frequency with distortion, perhaps due to improper time-constant on the coupling capacitors or improperly biased audio amplifiers. The bottom trace would be a raspy sounding side tone, due to the amplifier being over-driven and in compression (clipping). The o-scope is an invaluable tool for detecting and diagnosing such impurities in the signal quality.

FIG. 8 – Full Scale Signal Display



Actual display
Tektronix 475

MORE NIFTY MEASUREMENTS

Amplifier Gain.

The gain of an amplifier can be measured in terms of voltage or decibels (dB). For voltage gain, it is simply Vout/Vin of the amplifier. For example, if the input is 1Vpp and the output is 4Vpp, then the amplifier has a voltage gain of 4.

Gain in dB is often more useful and is how the gains of amplifiers are usually expressed. With dB's, every-time you double the AC voltage, you add 6dB of gain. It is the **ratio** of output to the input, and this **ratio** is easy to measure on a scope.

It is often easier to start with the output. Set the vertical amplifier gain to display the amplifier **output** as a full-scale signal as shown in ***Fig. 8***. Now move the scope probe to the amplifier **input** without disturbing the scope gain. You will of course have a much smaller signal, and the ratio of the input to the output will be the gain in dB. In our example of using eight divisions for full-scale, then four divisions would be 6db, 2 divisions 12dB, etc. as shown in **Fig. 9.** You may want to add your own dB scale along your scope display to remind you of this relationship. Note: this is ***voltage gain*** (Av=20log x Vout/Vin). In this example, with 4Vpp output and 1Vpp input (Av=4), then the gain is dB=20log(4) = 20(0.602) = 12dB, or as shown directly on the CRT tube. Since this is a relative measurement, the absolute Vin or Vout voltage does not need to be determined.

Fig. 9 – Volt. vs. dB relationship



Insertion Loss.

In some circuits, such as filters or attenuators, the ***loss*** in the circuit needs to be measured, and like circuit gain – expressed in dB. The loss through a circuit is called the ***insertion loss***. It is determined in the same way as amplifier gain just presented, except start with the input (the highest AC voltage) as the full-scale or reference display, then measure the output AC voltage (the lowest level). **The ratio is the insertion loss in dB.**



Fig. 10
Measuring Phase Shifts

For example, with a signal generator connected to your receiver, you want to measure the insertion loss through the IF crystal filter. At the filter input, you can just barely squeek out 2 divisions of input signal on your scope at its most sensitive setting. The output from the crystal filter is 1.5 divisions. The insertion loss would be 20log(1.5/2.0 div.) = –2.5 dB. If the output were only 1.0 division (50% reduction), the insertion loss would be 6dB.

Measuring Phase Shifts.

Phase relationships between two signals at the same frequency can be measured with 2-5° accuracy with a scope, although more suited for a dual-trace scope. The reference signal is applied to CH. 1 and the signal to be measured to CH. 2. For proper phase measurements, ensure your dual trace display is in the **chopped** mode, not **alternate** mode for proper phased referenced triggering.

Fig. 11 –Phase Shift by imposition



There are many methods to do this. One is to stretch out the signal so it takes 4 horizontal divisions, such that each division is 90° of phase, as shown in **Fig. 10**. By measuring from a common point on one signal (zero-crossing or from peak-to-peak) to the next, the phase can be measured. For example, say you are making a phased-array antenna in which one feedline must cause a 90° delay. You calculate the electrical length for a ¼λ [L=(246/f) x Velocity Factor] and cut the coax to that length. You are now working on blind faith that you have exactly 90°. With a scope, you can measure it fairly accurately by injecting a signal into one end with a signal generator (at the frequency of interest) and a 50Ω load on the other. Connect the scope CH.1 to the coax (signal) input and CH.2 to the load end and measure the phase. In the **Fig. 10** example, the CH.2 signal is delayed by 1.6 divisions, at 90° /div is 145˙. ***Your delay line is too long!*** Cut off an inch or two at a time until the CH.2 signal is 90° from CH.1 for precise tuning of the delay line. (While departing from o-scopes for a moment, the sharp null of a phased array is astounding when exactly 90^o delay is achieved. More than $10\text{-}15^o$ in error causes a very “mushy” null with little difference over a single vertical antenna. Most errors in achieving exactly 90° by the "measure-and-cut" method are due to uncertainties in the stated velocity factor of the coax).

Another method is to superimpose the two signals on top of eachother. Make one signal larger than the other so you know which one is what, as shown in **Fig. 11**. In this example, the smaller signal lags the larger signal by about 100^o, estimated by where they cross. For more accurate determination, use the time base to measure the time period of one cycle (T1), then the time period one signal lags (or leads) the other (T2). The phase shift is then $\theta=(T2/T1)x360^o$.

Phase measurements can be made on a single trace scope as well. First, connect the reference signal, uisng a BNC "T," to both the *external trigger* and the normal *vertical input*. Adjust the trigger level so the zero-crossing occurs at the beginning of the trace (left-hand graticle). Remove the reference from the vertical input, but not the e*xternal trigger,* and apply the signal to be tested to the vertical input – without altering the time base or trigger level. The distance of zero-crossing of the test signal is from the left-hand graticle can now be measured to determine the phase, though with slightly less accuracy than using a dual-trace scope.

An interesting experiment is to measure the phase shift of the audio signal at different frequencies as it travels through the stages in a CW, SSB or AM active filter. What is the phase shift of the wanted vs unwanted frequencies?

Measuring Rise and Fall Times.

In digital circuits, it is sometimes important to know the rise and fall times of a signal through a gate. In amateur radio transceivers, this same interest could be applied to how fast the T-R switch switches. On key-down, if the transmitter turns on slightly before the receiver is turned off, it can produce an annoying "thump" in the receiver. Rise and fall times are measured by triggering on the edge of the signal of interest, then increase to a faster sweep speed to measure the time it takes the signal to reach 90% of its final level. The signal to be measured is shown in **Fig. 12** on the top trace, and the expanded version on the bottom. For proper rise times, the signal being measured should be well within the bandwidth of your scope and using a low capacity probe.

For example, in **Fig. 12** (bottom trace), the rise time is about 1/4th of a division. If the sweep speed is 100nS/division, the rise time would then be about 25nS.

Fig. 12 –
Rise and Fall Times



USING LIMITED BANDWIDTH SCOPES

Today's scopes have 200–500MHz bandwidths. Likely your scope is much less than that. A limited bandwidth scope is still very useful to the amateur or homebrewer. Say the bandwidth of your scope is 5MHz. This does not mean you can't see 7MHz signals. It just means the peak-to-peak value has lost meaning, and will likely be very weak, since it is beyond the bandwidth of the scope. (Like other bandwidth measurements in electronics, the “bandwidth” of a scope is usually based on the “3dB bandwidth.” That is, at the maximum bandwidth, you are already at the –3dB point, or a 25% reduction in the peak-to-peak voltage display). You can still resolve individual cycles higher than the cited bandwidth to a certain degree and make gain and phase measurements, since they are based on ***ratios.***

Most of the examples in this article explore many regions of a communications receiver or ham transceiver without the benefit of any great bandwidth. Experiment with your scope to learn its limitations. ***Use a good scope probe and make measurements with a good ground to get the most out of the bandwidth you have.***

For the homebrewer building circuits in the HF bands, a 50 MHz scope **with good calibration** will yield fairly accurate measurements up to 30 MHz with little concern for accuracy. The old 465 or 475 series of Tektronix scopes, with 100/200 MHz bandwidths, make an excellent oscilloscope for the amateur or experimenter. They can often be found at hamfests today for $100–150, and tend to maintain a fairly good calibration almost regardless of how much use they have seen.

In Part 2 - we'll probe (bad pun) into some advanced measurement techniques, even with a simple scope ... such as measuring sideband rejection, filter responses, VCO phase noise, etc. (and what it all means).

72, Paul NA5N

na5n@zianet.com
pharden@nrao.edu

Colophon:
Article prepared by NA5N using CorelDraw 11

START NOW

3 Easy Steps:
1) Click 'Start Now'
2) Download on our website!
3) Get Free File Converter

fromdoctopdf.com

advertisement

NIC NAC TIC TAC CRYSTAL RADIO SET - AN IDEAL PRIMARY SCHOOL PROJECT...

Technology (/technology/) > Science | by mk484 (/member/mk484/) Follow

10,750 83 16

Posted Jul. 4, 2014 | PUBLICDOMAIN


Energy (average): 1669 kJ/393 kcal per 100g
Made in Australia by Ferrero Australia Pty Ltd
68J

(https://cdn.instructables.com/F...





(https://cdn.instructables.com/F8O/OFKG/HX8HK0L5/F8OOFKGHX8H (https://cdn.instructables.com/FZL/AJMS/HX

Hi there! This Instructable is all about building a basic crystal radio set that is so simple to build and understand, that a child could do it - with help from mum or dad - or even at school, as a class project. Parts can be bought "off the shelf" at Jaycar Electronics and other suppliers, or purchased online via Ebay and Paypal.

I built my first ever crystal set when I was 9 years old, but that was a different world. We're going to build a 21st century style radio with all modern components which are relatively easy to obtain at your local electronics store or on the Internet.

The radio is contained inside a Tic Tac box, and is called "The Nic Nac Tic Tac Radio". It is built on a square of matrix board, with the component leads poked through the holes in the board, and joined underneath. It is a very simple crystal set, designed to initially receive only one station, but you can expand the tuning range with the addition of only one extra component.

The Tic Tac radio can be constructed by simply twisting the component leads together, underneath the matrix board and attaching antenna/ground wires as well as the earphone wires to the board, using that same technique. You don't have to solder any wires, but there is another way to join them all together - more on that later.

The Tic Tac Radio is a very easy set to put together - you don't need to wind bulky coils or use heavy tools and screw strange looking parts onto a large breadboard. See step 1 for the parts list you will need.

Add Tip Ask Question

Step 1: Parts and Tools You Will Need


Matrix Board
Resistor
Capacitor
Inductor
Diode
Crystal Earphone

(https://cdn.instructables.com/F9B/WLFJ/HX5H54TY/F9BWL

(https://cdn.instructables.com/F99/H0BC/H

(https://cdn.ins

(https://cdn.instructables.com/FXV/5

You will need to acquire the following components from a local electronics shop or an online electronics business.

I am adding the catalogue numbers for Jaycar Electronics, so if you live in Australia or North America, you may be able to visit a Jaycar store and buy the parts over the counter, if not then you may be able to do an online mail order via Paypal:

Parts List

Resistor - 47k - yellow-purple-black-red and brown - RR 0612 (pkt of 8)

Capacitor - 68pF - ceramic x 2 - RC 5322 (pkt of 2) and a 100 or 120 pF value as well for experiments.

Inductor - 220 uH - red-red-brown silver - LF 1538 (resistive type)

Polyvaricon tuning capacitor - 220 pF - RV 5728 - with knob and mounting screws

Diode - BAT46 - ZR 1141 (You can also use a 1N34A Germanium Diode too if you have one at home)

Ceramic Earphone - AS 3305 *

A 25 meter roll of yellow hook up wire for the Antenna wire and a 3 meter length of wire for the Ground wire.

Please note that some Jaycar parts come in multiples of 2 or more per packet. And please note the following:

PLEASE NOTE: THIS PROJECT/KIT CONTAINS SMALL PARTS THAT MAY FORM A CHOKING HAZARD FOR SMALL CHILDREN OR PETS. NOT SUITABLE FOR CHILDREN UNDER FIVE (5) YEARS OLD.

*A normal crystal radio earphone is OK, but if you can't get one of these, or if the one you bought goes dead (as they sometimes do,) you can use a substitute, such as the Murata PKM44EW passive transducer (see picture above) which is available from an old Telstra TF200 touchphone, (the one on the left in the diagram above,) or an equivalent, such as the ARIO transducer, from an old Telstra T1000 pushbutton phone.

The ARIO unit is soldered to the phone's pc board so you'll need to be able to unsolder the three mounting pins underneath the board, or find someone in the neighbourhood who is able.

Take the back off the TF200 (if you've obtained one of these phones,) and you'll see a black disc shaped object 2" round by 1/2' thick - with a red and black wire. Unplug the wires from the circuit board, and unscrew any retaining screws and remove the transducer. Cut the mini plug off, carefully strip the insulation from the ends of the wires and extend them by about 18" with 2 thin lengths of hookup wire. These pietzo devices make good earphones for crystal sets and can be housed in an old pair of ear muffs.

Miscellaneous Materials:

A Tic Tac box (smaller size)

A piece of matrix board at least 7 holes long by 8 holes across. Cut the board to fit neatly inside the Tic Tac box.

A short length of 2 differently coloured wires 60 mm in length and 2 crocodile clips with red and black plastic covers

A length of antenna wire at least 25 metres long and a 3 metre length of a different colour for the Ground wire.

A metal rod or cold water pipe for the ground stake. Be careful which pipes you connect your Ground wire to.

You will need a small sharp object for punching holes in the Tic Tac box.

A small pair of wire cutters for cutting and stripping wires.

Add Tip   Ask Question

Step 2: How a Crystal Radio Works



(https://cdn.instructables.com/FAZ/TOFJ/HWZ9T38P/FAZTOFJHWZ9T38P.LARGE.jpg)



FIG. 2

(https://cdn.instructables.com/FXR/26PU/HX1W6FGZ/FXR26PU



(https://cdn.instructables.com/F3J/0N24/HX1W6FH1/F

Radio signals consists of two parts - the 'carrier wave' which is the AM radio station's frequency of operation, and the 'program signal' which is mixed with the carrier wave for transmission.

Radio waves travel out from the AM transmitter tower through the atmosphere. We want to capture one specific frequency so we can listen to it, so we need the antenna/ground wire system to capture that signal. We also need a 'tuned circuit' that will filter out the desired AM signal, and discard the rest, so that all the other unwanted radio signals pass out through the ground wire to earth.

Two components in our circuit will perform that task for us. The capacitor C1, together with L1 inductor, form a basic 'series tuned' circuit. Their respective values will determine just which local AM radio station we will capture.

We also need a diode to 'detect' the voice and music, so we can hear them in our earphone, which transduces electrical signals into sound waves that we can hear.

In the photo above you can see a completed Tic Tac crystal radio. It is already inside the box. The other set is connected to the antenna/ground wire circuit, undergoing a 'soak test'. It is necessary to do this to ensure that the radio will work once inside the box!

The first diagram shows a typical antenna wire installation. Coming out of a window, the wire is anchored to the building and then over some distance (10 metres +) to a nearby tree or other building.

You must take great care not to erect antenna wires near to power or telephone cables, near your home!

The ground wire comes out the same window and is anchored to a metal pipe/water pipe or metal ground stake, embedded in soft, moist soil.

You must not connect ground wires to electrical mains wiring installations, including wall power outlets!

Another electrical hazard to consider is lightning strikes! Although it is very rare for anyone to be seriously injured or die from a lightning strike it is not impossible. So, if you hear a thunderstorm coming your way (you may hear the lightning 'crashes' in your earphone first,) then disconnect your antenna wire immediately, connect it to the ground wire and put it well up out of the way. Stay well clear of this temporary antenna/ground connection until the storm has completely passed away from your general area - miles away!

Add Tip Ask Question

Step 3: How to Build the Tic Tac Crystal Radio Set


L1
Ground
Antenna
C1
L1/Ground link
D1/L1/C1 join
Wire
Link
D1
R1/Ground link
R1/D1 join
R1
Earphone Leads

(https://cdn.instructables.com/FA5/FW4F/HYA9RXF0/FA5FW4FHYA9RXF0.LARGE



(https://cdn.instructables.com/FS8/N068/HYA9BY3O/FS8N068HYA9BY3O.LARGE



(https://cdn.instructables.com/FLB/

1. Take the components and lay them out on a clean surface.

2. Take the square of matrix board (this is also called 'perf board' because of all the holes or perforations in the material) and beginning with the 220uH (uH = micro-Henry) and place it as shown in the diagram.

3. Then take the diode, capacitor and resistor and place them in the places shown for them, making sure that the coloured band at one end of the diode joins with the resistor wire, as shown

4. Then take each junction where wires come together through their respective holes and gently twist them together, until they form a neat, tight bundle. Take your side cutters and cut off any excess length, taking care not to cut any one wire too short, so that it comes undone from the join.

.5. Take the link wire, strip 2 centimetres of insulation from each end of the wire and install that wire between the free ends of the inductor and resistor, and the matrix board construction is complete.

6. Then take the ceramic earphone, cut the plug off the end, and strip the 2 wire ends about 1.5 centimetres in length. Wrap each earphone wire around each end of the resistor component, underneath the matrix board.

7. Finally, strip the insulation off both ends of the 60mm long differently coloured wires, and attach them to the matrix board - one goes to the inductor/link wire junction and this will be the Ground connection wire. Attach the other one to the free end of capacitor C1 and this will be the antenna wire connection. Both connections are made underneath the matrix board. The Nic Nac Tic Tac Crystal Radio is now ready for testing.

Add Tip Ask Question

Step 4: Final Checks and Installation of Wires

24g NET
FRESHNESS IN 2 CALORIES
tic tac
Strawberry Fields

(https://cdn.instructables.com/FX9/8RCY/HX8HJEU3/FX98RCYHX8HJEU3.LAR



(https://cdn.instructables.com/F4V/FUFI/HX8HJF32/F4VFUFIHX8HJF32.LARGE.jpg)

When you've finished constructing the matrix board circuit and have clipped all the excess component leads off, puncture three (3) holes in the Tic Tac box - 2 small holes on the top lid of the box, about an inch (24mm) apart, so that your antenna and ground wire leads can come through the box lid, and be connected to the matrix board at those 2 points.

Feed the wires through the holes and then tie small knots in each one, near the underside of the box lid, so that they won't pull back out if strained, and disconnect themselves from the matrix board.

Then make one larger hole in the centre of the bottom of the box (clear part) so that your earphone wires can be fed through to the connecting points on that part of the matrix board. Tie a larger knot in the earphone lead so as to prevent it from pulling out of the box if it is strained. Strip the insulation off the earphone leads, and wrap them around the matrix board leads at those 2 points. You are now ready to test out the Nic Nac Tic Tac Crystal Radio.

Add Tip Ask Question

Step 5: Testing Out the Tic Tac Radio



24g NET
FRESHNESS IN 2 CALORIES
tic tac
Strawberry Fields

(https://cdn.instructables.com/FX9/H2HC/HY8HJF34/FX9H2HCHY8HJF34.LARGE.j



(https://cdn.instructables.com/FL6/41GU/HX5H55A2/FL641GUHX5H55A2.LARGE.jpg)

Take your finished Tic Tac Radio (with the lid part gently pushed back inside the top of the box) and connect your Antenna and Ground wires to the lead outs from the box lid. Place the earphone in/over your ear,and listen carefully for a local AM radio station. This crystal radio is a simple one, and you may have to make one or two adjustments to the components, before you succeed in receiving one or more local AM radio stations, in your area.

If you can't hear anything in the earphone, don't panic. It might just be a simple wiring mistake, which is easily fixed. Go back over all of the steps, making sure that you have the right value components from the electronics store. Make sure that each component is in the right place on the matrix board, (don't confuse the L1 inductor with the R1 resistor - they look a lot like each other!) and that no component wires have come undone from the twisted joins you have just made. I'll be writing up a troubleshooting step soon, so if you run into any problems, post your questions in the 'comments' section down at the bottom of the page, and I'll try and answer them as soon as possible.

Make sure that your antenna and ground wires aren't snagged on anything metal or anything dangerous!

If you have ANY doubts about the electrical safety of your antenna or ground wires, then consult a licensed electrical trades person, who will be able to advise you on electrical safety principles and procedures!

Always remember that electrical safety is your responsibility! If you don't think it is safe to proceed, then don't!

You will need at least 10 to 15 metres of antenna wire, strung between 2 insulating points (not connected to anything metallic, or that gets wet,) at least 2 to 3 metres in height - anything less than this minimum arrangement may mean that you cannot receive any signals at all.

Some places are regarded as 'radio dead spots', so you may need to try an open space, such as a park or a remote corner of a beach. If you do erect antenna and ground wires in public places, hang some streamers or balloons off of them, to alert people to their presence, otherwise people going past may become entangled with them - and get cranky with you!!!

As a final word for now, you'll be happy to know that the completed "Nic Nac Tic Tac Radio" shown in the picture above, picked up local AM radio station 1116 khz 4BC here in Brisbane, with a very clear signal and quite good volume. It works! So be safe kids, have some fun and look forward to more... mk484

Add Tip Ask Question

Step 6: Nic Nac Extras

(https://cdn.instructables.com/FCL/BHOH/HX8HJC9V/FCLBHOHHX8HJC9V.LARGE.jpg)


ROTOR
STATOR
SYMBOL

(https://cdn.instructables.com/FRL/AV48/HX8HK020/FRLAV48HX8HK020.LARGE.gif)

If you've built your Tic Tac crystal set and found that you can't receive a local AM radio station yet - don't panic - help is in on the way. You have just built the simplest version of the Tic Tac crystal radio and you may need to add one more component part for it to work properly. This is called a 'polyvaricon' - a miniature tuning capacitor, which can vary the frequency that your radio will receive at. You can see a picture of one up above - the small white box with the black knob next to it. It has 3 connecting tags - the one in the middle ('G') goes to the moving plates and the shaft, while the 2 outer tags ('O' and 'A') go to 2 sets of fixed plates. the smaller set of plates has a value of 60pF - pF is short for 'picoFarad' - a unit of measurement for capacitance. The larger set of plates is valued at 160 pF so that the combined value of the polyvaricon is 220 pF - or 220 picoFarads.

The other picture shows you what happens inside a basic tuning capacitor. there are 2 sets of metal plates - one set is fixed and the other set moves on a rotating shaft, connected to the tuning knob of your radio set. Both sets of plates are mounted on an insulating frame so that they won't 'short out' by touch each other.

The fixed capacitor C1, was chosen to tune somewhere close to the middle of the AM radio band. This band of frequencies starts at 531 kilohertz (Khz) and goes as far as 1701 Khz here in Australia. So we need a combination of coil and capacitor which will tune across all of those frequencies. Our simple Tic Tac radio is known as a 'series tuned' set. If you look at the circuit diagram, you can see electronic symbols for all components in the radio set.If you start at the top with the antenna symbol, you can see the capacitor C1 underneath that, the inductor L1 underneath C1 and then finally, the ground symbol - all wired in series with each other.

The diode D1 detector, the resistor and the earphone plus the link wire, can be considered as one block - the "detector unit". The Antenna wire, ground wire, inductor/coil and capacitor/polyvaricon, can be also be considered as another block - the "tuned circuit". So joining both blocks together, we have the tuned circuit that tunes in only one frequency, passing all other unwanted signals out through the ground wire to earth. This one 'tuned frequency' passes through the diode detector, which strips away the 'carrier wave' and leaves only the 'program signal' (voice, music etc,) behind, which is then fed via the resistor into the earphone. The earphone changes electrical impulses from the diode detector, into sound waves that we can hear. You need the R1 resistor to provide a pathway for the signals going through the diode, out to the ground wire connection. Without this resistor, the signals would sound very distorted and you couldn't hear the program signal very clearly.

Add Tip Ask Question

Step 7: Adding the Polyvaricon Tuning Capacitor



(https://cdn.instructables.com/F9D/UX53/HX8HMXUT/F9DUX53HX8HMXUT.LARGE.jpg)



(https://cdn.instructables.com/FU/SZ





(https://cdn.instructables.com/FB6/QTEB/UX0BIU0P/FB6QTE

If you want to expand the tuning range of your Tic Tac Radio, than all you have to do is a simple modification (change) to the circuit of your radio set. You can see from the 2 pictures above, that there's an alternative way of building the crystal radio - you can use the matrix board method or you can use a 4 way screw terminal strip.

To use the screw terminal version, cut yourself a 4 way strip of terminals as shown in the diagram and pictures. Undo the screws right out as far as they will go without falling out of the strip. Connect the component leads and wires from the antenna/ground system as well as the earphone wires. Cut off any excess from component leads that you don't need. Wrap thin wires from the antenna/ground system and the earphones, around the thicker component leads before screwing the screws in tight.

Regardless of which method you have used, all we will now wire up the tuning capacitor between the actual Antenna wire and the junction (join) where the diode D1, the fixed capacitor C1 and one end of the inductor meet. Remove the capacitor from the matrix board, and connect the Antenna lead out wire straight to the join of the diode and inductor. Then take the polyvaricon and another piece of wire. Strip both ends of that wire and join the two outer tags (tagged 'O' and 'A' - the centre on is tagged 'G') and then connect you actual Antenna wire to one of the outer tags. Connect the antenna lead out wire, coming out of the box, to the 'G' (middle) tag of the tuning capacitor,so that the antenna wiring now looks like the picture up above.

If you're having problems following the pictures, then refer to the diagrams, which clearly shows all of the connections Make sure your ground wire is connected to the set, and then, listening with your earphone in/over your ear, slowly turn the tuning cap's flat knob, until you hear one or more stations. Congratulations - you now have a "tuneable" Tic Tac crystal set! Happy listening! And don't forget to post in your results, questions, problems etc... mk484 :)

Add Tip   Ask Question

Step 8: Tic Tac One Transistor Amplifier - Use Your Earbuds and Hear Great Sound...


The Nic Nac Tic Tac Crystal Radio
By Austin Hellier © 1992 - 2014
How It Works
Antenna
C1
D1
L1
Ground
R1
EP

(https://cdn.instructables.com/FYZ/LKDV/HYA9MZYG/FYZLKDVHYA9MZYG.LARGE.jpg)

Hi there folks - this isn't really an extra 'Step' as such - it's a sneak preview at a picture of my upcoming Instructable for a one transistor amplifier, which will connect to the Tic Tac Radio - and give you some really good volume - in your Iphone earbuds!

Yes, it's entirely possible nowadays, with modern circuit design, to fit a one transistor amp in such a small space (yes kiddies - it WILL fit inside the smaller Tic Tac box...) and at the same time, get that great sound that comes from those "inside your ear" type earbuds.

This circuit took me about a half hour to complete, uses only 3 electronic components, costing about $1.00, a stereo earphone jack and a 1.5 volt AAA battery and plastic holder costing about another $3 to $4, so you can build the amplifier for about $5 all up - don't forget to shop around and - mums and dads - cheap batteries will be OK for this project, and the battery can simply be replaced without soldering or undoing half a dozen screws....

I can hear my Tic Tac Radio with great volume and clarity - and so will you, so "stay tuned" (ha ha ha) to this series of Instructables, and you will hear great sound too...

mk484

Add Tip Ask Question



LNA
Attenuator
Mixer
Variable Gain and Attenuator
I/Q Demod
LPF
ADC Driver
ADC
Tx/Rx Diplexer
RF Switch
Tunable Filter
PLL/VCO Divider Multiplier
Clock Distribution and Cleanup
PA
Gain/Phase Adjust/Detect
RF Detector
Amp
I/Q Mod
DAC
Get Complete RFIC Guide

ANALOG DEVICES

Download all Analog Devices RFIC Parts for Each Component in RF Signal Chain.

advertisement



LNA
Attenuator
Mixer
Variable Gain and Attenuator
I/Q Demod
LPF
ADC Driver
ADC

go to: Talking Electronics Website



For any enquiries email Colin Mitchell

THE MULTIMETER

Page 1: Basic Electronics
The capacitor - how it works
The Diode - how the diode works
Circuit Symbols - EVERY Circuit Symbol
Soldering - videos
Page 2: The Transistor
- PNP or NPN Transistor TEST
Page 2a: The 555 IC
The 555 - 1
The 555 - 2
The 555 - 3
The 555 TEST
Page 3: The Power Supply download as .pdf (900kB)
3a: - Constant Current
3b: - Voltage Regulator
3c: - Capacitor-fed Power Supply
Page 4: Digital Electronics
4a: - Gates Touch Switch Gating
Page 5: Oscillators
Page 6: Test - Basic Electronics (50 Questions)
Page 7: The Multimeter - this page

INDEX

Analogue Multimeter
Buying A Multimeter
Current - measuring
Digital Multimeter
Diode - measuring
Pressure Cell
Resistance - measuring
TEST
Using A Multimeter
Voltage - measuring

to Index

TWO MULTIMETERS

There are basically two different types of MULTIMETER. ANALOGUE and DIGITAL

Analogue Multimeters have a NEEDLE or POINTER that moves across a scale.

Digital Multimeters have a numeric display of 3 or more digits. A Digital Multimeter with 3½ digits means the first digit shows only "1."

You really need both types to cover the number of tests needed for designing and repair-work. We will discuss how they work, how to use them and some of the differences between them.

024
6.43
UNI-T
OMEGA

The black (negative lead) ALWAYS stays in the

black hole and the red lead changes to the other red hole to measure 10 amps

to Index

BUYING A MULTIMETER

There are many different types on the market.
The cost is determined by the number of ranges and also the extra features such as diode tester, buzzer (continuity), transistor tester, high DC current and others.
Since most multimeters are reliable and accurate, buy one with the greatest number of ranges at the lowest cost. The cheapest multimeters are on **eBay**.
This article explains the difference between an analogue meter and a digital meter.

Multimeters are sometimes called a "meter", a "VOM" (Volts-Ohms-Milliamps or Volt Ohm Meter) or "multi-tester" or even "a tester" - they are all the same.

One term used to describe a **DIGITAL MULTIMETER** is **3½ digits**.
This is the number of digits on the display. The first digit is usually made from two pixels and can only produce "1." This is called a half-digit. The other digits are full digits. The cheapest digital multimeters have 3½ digits. This will produce a reading of 1999 and the decimal point can produce values from 1.999 to 19.99 to 199.9 to 1999.
Another term is **DISPLAY COUNTS**. This is connected with the accuracy of the display, but since digital meters are accurate to 1% or less and we are using resistors with an accuracy of 5%, even a $10.00 digital meter will be perfect.

to Index

USING A MULTIMETER

Analogue and **digital** multimeters have either a rotary selector switch or push buttons to select the appropriate function and range. Some Digital Multimeters (DMMs) are auto ranging; they automatically select the correct range of voltage, resistance, or current when doing a test. However you need to select the function.

Before making any measurement you need to know what you are checking. If you are measuring voltage, select the AC range (10v, 50v, 250v, or 1000v) or DC range (0.5v, 2.5v, 10v, 50v, 250v, or 1000v). If you are measuring resistance, select the Ohms range (x1, x10, x100, x1k, x10k). If you are measuring current, select the appropriate current range DCmA 0.5mA, 50mA, 500mA, 10A. Every multimeter is different however the photo below shows a low cost Analogue multimeter with the basic ranges.



An ANALOGUE MULTIMETER

The most important point to remember is this:
You must select a voltage or current range that is bigger or HIGHER than the maximum expected value, so the needle does not swing across the scale and hit the "end stop."
If you are using a DMM (Digital Multi Meter), the meter will indicate if the voltage or current is higher than the selected scale, by showing "OL" - this means "Overload."
If you are measuring resistance such as 1M on the x10 range the "OL" means "Open Loop" and you will need to change the range. Some meters show "1' on the display when the measurement is higher than the display will indicate and some flash a set of digits to show over-voltage or over-current. A "-1" indicates the leads should be reversed for a "positive reading."
If it is an AUTO RANGING meter, it will automatically produce a reading, otherwise the selector switch must be changed to another range.

A typical DIGITAL Multimeter


A
10
10
2
200m
20m
2m
200μ
A
500
RCC
10A MAX
FUSED
2A MAX
FUSED
MAX
AC 750V
DC 1000V
MAX
600V
A
mAμA
COM
VΩ
REMOVE INPUTS BEFORE SWITCHING RANGES

The Common (negative) lead ALWAYS fits into the "COM" socket. The red lead fits into the red socket for Voltage and Resistance.
Place the red lead (red banana plug) into "A" (for HIGH CURRENT "Amps") or mA,uA for LOW CURRENT.

The black "test lead" plugs into the socket marked "-" "Common", or "Com," and the red "test lead" plugs into the meter socket marked "+" or "V-W-mA." The third banana socket measures HIGH CURRENT and the positive (red lead) plugs into this. You DO NOT move the negative "-" lead at any time.
The following two photos show the test leads fitted to a digital meter. The probes and plugs have "guards" surrounding the probe tips and also the plugs so you can measure high voltages without getting near the voltage-source.

FLUKE 115 TRUE RMS MULTIMETER
600.0
HOLD
MIN MAX
RANGE
OFF
COM
000
10ADC

Analogue meters have an "Ohms Adjustment" to allow for the change in voltage of the battery inside the meter (as it gets old).



"Ohms Adjust" is also called "ZERO SET"
The sensitivity of this meter is 20,000ohms/volt on the DC ranges and 5k/v on the AC ranges

Before taking a resistance reading (each time, for any of the Ohms scales) you need to "ZERO SET" the scale, by touching the two probes together and adjust the pot until the needle reads "0" (swings FULL SCALE). If the pointer does not reach full scale, the batteries need replacing. Digital multimeters do not need "zero adjustment."

to Index

ANALOGUE Vs DIGITAL

You cannot say one meter is better than the other because BOTH have advantages and disadvantages.
An analogue multimeter is the "old style" and it puts a load on a circuit and this may change the reading to give an incorrect readout, but it has the advantage of the needle moving across the scale fairly quickly so you can sometimes see if the voltage is fluctuating.
It also gives a more-accurate result in some high frequency circuits as it does not pick up stray fields and produce a false reading.
Digital meters put almost no load on a circuit and produce accurate readings from both low-impedance and high-impedance circuits.
Digital meters can display very low resistances.
You must remember to turn a Digital meter OFF to prevent the battery going flat.

If you are testing a circuit containing a high-frequency oscillator, use BOTH an ANALOGUE and DIGITAL meter to check the reading. Sometimes the leads of a Digital multimeter will pick up signals and create a false reading.
Sometimes you will get a voltage reading with a Digital multimeter due to a high resistance leak and a zero reading with an Analogue meter. This is why you need **BOTH** meters.

to Index

MEASURING VOLTAGE

Most of the readings taken with a multimeter will be VOLTAGE readings.
Before taking a reading, you should select the highest range and if the needle does not move up scale (to the right), you can select another range.
Always switch to the highest range before probing a circuit and keep your fingers away from the component being tested.
If the meter is Digital, select the highest range or use the auto-ranging feature, by selecting "V." The meter will automatically produce a result, even if the voltage is

AC or DC.

If the meter is not auto-ranging, you will have to select V⎓ if the voltage is from a DC source or V~ if the voltage is from an AC source. DC means Direct Current (but this does not mean you select the CURRENT range - you are taking a voltage reading that is not rising and falling. That's why we say it is **DC** and do not say the words "direct current"). The voltage is coming from a battery or supply where it is steady and not "rising and falling."

You can measure the voltage at different points in a circuit by connecting the black probe to chassis. This is the 0v reference and is commonly called "Chassis" or "Earth" or "Ground" or "0v."

The red lead is called the "measuring lead" or "measuring probe" and it can measure voltages at any point in a circuit. Sometimes there are "test points" on a circuit and these are wires or loops designed to hold the tip of the red probe (or a red probe fitted with a mini clip).

You can also measure voltages ACROSS A COMPONENT. In other words, the reading is taken in PARALLEL with the component. It may be the voltage across a transistor, resistor, capacitor, diode or coil. In most cases this voltage will be less than the supply voltage.

If you are measuring the voltage in a circuit that has a HIGH IMPEDANCE, the reading will be inaccurate, up to 90% !!!, if you use a cheap analogue meter.

Here's a simple case.

The circuit below consists of two 1M resistors in series. The voltage at the mid point will be 5v when nothing is connected to the mid point. But if we use a cheap analogue multimeter set to 10v, the resistance of the meter will be about 100k, if the meter has a sensitivity of 10k/v and the reading will be incorrect.

Here how it works:

Every meter has a sensitivity. The sensitivity of the meter is the sensitivity of the movement and is the amount of current required to deflect the needle FULL SCALE. This current is very small, normally 1/10th of a milliamp and corresponds to a sensitivity of 10k/volt (or 1/30th mA, for a sensitivity of 30k/v).

If an analogue meter is set to 10v, the internal resistance of the meter will be 100k for a 10k/v movement.

If this multimeter is used to test the following circuit, the reading will be inaccurate.

The reading should be 5v as show in diagram **A**.

But the analogue multimeter has an internal resistance of 100k and it creates a circuit shown in **C**.

The top 1M and 100k from the meter create a combined PARALLEL resistance of 90k. This forms a series circuit with the lower 1M and the meter will read less than 1v

If we measure the voltage across the lower 1M, the 100k meter will form a value of resistance with the lower 1M and it will read less than 1v

If the multimeter is 30k/v, the readings will be 2v. See how easy it is to get a totally inaccurate reading.



A



B



C



D



E

If the reading is taken with a Digital Meter, it will be more accurate as a DMM does not take any current from the circuit (to activate the meter). In other words it has a very HIGH input impedance. Most Digital Multimeters have a fixed input resistance (impedance) of 10M - no matter what scale is selected. That's the reason for choosing a DMM for high impedance circuits. It also gives a reading that is accurate to about 1%.

to Index

MEASURING VOLTAGES in a CIRCUIT

You can take many voltage-measurements in a circuit. You can measure "across" a component, or between any point in a circuit and either the positive rail or earth rail (0v rail). In the following circuit, the 5 most important voltage-measurements are shown. Voltage "A" is across the electret microphone. It should be between 20mV and 500mV. Voltage "B" should be about 0.6v. Voltage "C" should be about half-rail voltage. This allows the transistor to amplify both the positive and negative parts of the waveform. Voltage "D" should be about 1-3v. Voltage "E" should be the battery voltage of 12v.



to Index

MEASURING CURRENT

You will rarely need to take current measurements, however most multimeters have DC current ranges such as 0.5mA, 50mA, 500mA and 10Amp (via the extra banana socket) and some meters have AC current ranges. Measuring the current of a circuit will tell you a lot of things. If you know the normal current, a high or low current can let you know if the circuit is overloaded or not fully operational.

Current is always measured when the circuit is working (i.e: with power applied).
It is measured IN SERIES with the circuit or component under test.
The easiest way to measure current is to remove the fuse and take a reading across the fuse-holder. Or remove one lead of the battery or turn the project off, and measure across the switch.
If this is not possible, you will need to remove one end of a component and measure with the two probes in the "opening."
Resistors are the easiest things to desolder, but you may have to cut a track in some circuits. You have to get an "opening" so that a current reading can be taken.
The following diagrams show how to connect the probes to take a CURRENT reading.
Do not measure the current ACROSS a component as this will create a "short-circuit."
The component is designed to drop a certain voltage and when you place the probes across this component, you are effectively adding a "link" or "jumper" and the voltage at the left-side of the component will appear on the right-side. This voltage may be too high for the circuit being supplied and the result will be damage.





Measuring the current of a globe



**Do NOT measure the CURRENT of a battery (by placing the meter directly across the terminals)
A battery will deliver a very HIGH current
and damage the meter**

Do not measure the "current a battery will deliver" by placing the probes across the terminals. It will deliver a very high current and damage the meter instantly. There are special battery testing instruments for this purpose.

When measuring across an "opening" or "cut," place the red probe on the wire that supplies the voltage (and current) and the black probe on the other wire. This will produce a "POSITIVE" reading.
A positive reading is an UPSCALE READING and the pointer will move across the scale - to the right. A "NEGATIVE READING" will make the pointer hit the "STOP" at the left of the scale and you will not get a reading. If you are using a Digital Meter, a negative sign "-" will appear on the screen to indicate the probes are around the wrong way. No damage will be caused. It just indicates the probes are connected incorrectly.
If you want an accurate CURRENT MEASUREMENT, use a digital meter.

to Index

MEASURING RESISTANCE

Turn a circuit off before measuring resistance.
If any voltage is present, the value of resistance will be incorrect.
In most cases you cannot measure a component while it is in-circuit. This is because the meter is actually measuring a voltage across a component and calling it a "resistance." The voltage comes from the battery inside the meter. If any other voltage is present, the meter will produce a false reading.
If you are measuring the resistance of a component while still "in circuit," (with the power off) the reading will be lower than the true reading.



Measuring resistance


138
rolson
27259

Measuring resistance of a heater (via the leads)


4.2 Ω
OFF
Ω 2M
200 K
20K
2K
200
ΩV
COM
mA
10A
resistance wire

Measuring the resistance of a piece of resistance-wire



Power must be disconnected from the circuit

Measuring the resistance of a resistor



Do not measure the "Resistance of a Battery"

1. Do not measure the "resistance of a battery." The resistance of a battery (called the Internal impedance) is not measured as shown in the diagrams above. It is measured by creating a current-flow and measuring the voltage across the battery. Placing a multimeter set to **resistance** (across a battery) will destroy the meter.
2. Do not try to measure the resistance of any voltage or any "supply."

Resistance is measured in OHMs.
The resistance of a 1cm x 1cm bar, one metre long is 1 ohm.
If the bar is thinner, the resistance is higher. If the bar is longer, the resistance is higher.
If the material of the bar is changed, the resistance is higher.
When carbon is mixed with other elements, its resistance increases and this knowledge is used to make RESISTORS.
Resistors have RESISTANCE and the main purpose of a resistor is to reduce the CURRENT FLOW.
It's a bit like standing on a hose. The flow reduces.
When current flow is reduced, the output voltage is also reduced and that why the water does not spray up so high. Resistors are simple devices but they produce many different effects in a circuit.
A resistor of nearly pure carbon may be 1 ohm, but when non-conducting "impurities" are added, the same-size resistor may be 100 ohms, 1,000 ohms or 1 million ohms.
Circuits use values of less than 1 ohm to more than 22 million ohms.

Resistors are identified on a circuit with numbers and letters to show the exact value of resistance - such as 1k 2k2 4M7
The letter Ω (omega - a Greek symbol) is used to identify (or express) (or represent) the word "Ohm."
But this symbol is not available on some word-processors, so the letter "R" is used. The letter "E" is also sometimes used and both mean "Ohms."
A one-ohm resistor is written "1R" or "1E." It can also be written "1R0" or "1E0."
A resistor of one-tenth of an ohm is written "0R1" or "0E1." The letter takes the place of the decimal point.
10 ohms = 10R
100 ohms = 100R

1,000 ohms = 1k (k= kilo = one thousand)
10,000 ohms = 10k
100,000 ohms = 100k
1,000,000 ohms = 1M (M = MEG = one million)

The size of a resistor has nothing to do with its resistance. The size determines the wattage of the resistor - how much heat it can dissipate without getting too hot.
Every resistor is identified by colour bands on the body, but when the resistor is a surface-mount device, numbers are used and sometimes letters.
You MUST learn the colour code for resistors and the following table shows all the colours for the most common resistors from 1/10th of an ohm to 22 Meg ohms for resistors with 5% and 10% tolerance.



If 3rd band is gold, Divide by 10
If 3rd band is silver, Divide by 100
(to get 0.22ohms etc)



ROW	SILVER	GOLD	BLACK	BROWN	RED	ORANGE	YELLOW	GREEN
1-	R10	1R0	10R	100R	1K0	10K	100K	1M0
2-	R11	1R1	11R	110R	1K1	11K	110K	1M1
3-	R12	1R2	12R	120R	1K2	12K	120K	1M2
4-	R13	1R3	13R	130R	1K3	13K	130K	1M3
5-	R15	1R5	15R	150R	1K5	15K	150K	1M5
6-	R16	1R6	16R	160R	1K6	16K	160K	1M6
7-	R18	1R8	18R	180R	1K8	18K	180K	1M8
8-	R20	2R0	20R	200R	2K0	20K	200K	2M0
9-	R22	2R2	22R	220R	2K2	22K	220K	2M2
10-	R24	2R4	24R	240R	2K4	24K	240K	2M4
11-	R27	2R7	27R	270R	2K7	27K	270K	2M7
12-	R30	3R0	30R	300R	3K0	30K	300K	3M0
13-	R33	3R3	33R	330R	3K3	33K	330K	3M3
14-	R36	3R6	36R	360R	3K6	36K	360K	3M6
15-	R39	3R9	39R	390R	3K9	39K	390K	3M9
16-	R43	4R3	43R	430R	4K3	43K	430K	4M3
17-	R47	4R7	47R	470R	4K7	47K	470K	4M7
18-	R51	5R1	51R	510R	5K1	51K	510K	5M1
19-	R56	5R6	56R	560R	5K6	56K	560K	5M6
20-	R62	6R2	62R	620R	6K2	62K	620K	6M2
21-	R68	6R8	68R	680R	6K8	68K	680K	6M8
22-	R75	7R5	75R	750R	7K5	75K	750K	7M5
23-	R82	8R2	82R	820R	8K2	82K	820K	8M2
24-	R91	9R1	91R	910R	9K1	91K	910K	9M1
								10M BLUE

COLOR CODES FOR THE WHOLE E12/E24 RANGE OF RESISTORS
The twelve odd rows - 1, 3, 5... - represent values available in the E12 range only, plus 10M

to Index

MAKE YOUR OWN RESISTOR

Make your own variable resistor that changes resistance according to the pressure.
Use a piece of conductive foam used to package Integrated Circuits. You can ask at an electronics shop.
Use two coins or pieces of printed circuit board or aluminium foil for the top and bottom conductors.
You can solder wires to the PC board or fold the aluminium foil over a few times to hold the wires.
The resistance of the foam will reduce as you press on the "cell."
The actual resistance-values will depend on the size of the foam, the thickness and

pressure.
This cell is a very simple cell called a **LOAD CELL**.



The top and bottom "plates"

The foam is placed between the plates.



The complete LOAD CELL



The resistance of the unloaded LOAD CELL



The fully loaded resistance can be as low as 9,330 ohms

to Index

MEASURING CONTINUITY

CONTINUITY is the same as **ZERO OHMS** or the resistance of a short length of wire. It can also mean the resistance through a switch or globe or a low-value resistor.
It basically means a "PATH" and sometimes refers to a whole circuit when the switch is closed. In other words CONTINUITY means we have a "circuit." We have "current flowing" and generally refers to a low-resistance circuit.
Both ANALOGUE and DIGITAL multimeters can measure CONTINUITY and you have to work out the approximate value of resistance for the circuit you are testing, - BEFORE TAKING A READING.
If the reading is above 300 ohms or contains a diode, you cannot use a DIGITAL MULTIMETER as the buzzer on the continuity setting will not respond.

The project being tested must not have the power applied as the resistance ranges on a multimeter are actually measuring a voltage across the leads and any voltage on the circuit or contained in any electrolytics, will upset the reading.

To take a reading with an **ANALOGUE** multimeter, select the x1 setting and the pointer will move across the scale to the actual value of resistance.
It it move full scale, you have ZERO OHMS resistance and this can mean a short-circuit or continuity via a wire.
If a diode is in the circuit you must also reverse the leads to get a reading.
The resistance of a globe will be very low when it is not illuminated, so don't think a fault is present.
Measuring CONTINUITY is the same as measuring LOW RESISTANCE.

To take a reading with a **DIGITAL** multimeter, select the buzzer setting. It will respond if the resistance is less than 300 ohms. It will not respond if a diode is in the circuit.

Meter set to BUZZER - CONTINUITY

You can also use the x1 resistance setting to get an accurate value of resistance. Touch the probes together to get the initial reading and subtract this value from the final reading.
When probing a circuit containing electrolytics, you may get a beep from the buzzer. This indicates the resistance is low because the multimeter is charging the electrolytic and it will beep until the electrolytic is charged to about 0.7v.
The same applies when probing across the power rails of a circuit. The circuit may contain electrolytics that will charge when probing and the buzzer will beep.
The Digital multimeter is actually detecting a voltage less than 0.7v across the probes and is created by a voltage-divider network inside the meter.
The voltage divider put 2v across the probes and when this drops to less than 0.5v, the buzzer is activated. That why it odes not buzz when testing a diode as the diode drops the voltage to 0.6v.

to Index

MEASURING A DIODE

A diode can be measured to see if it is "open" or "damaged" or "working" by placing the probes across the component.
If the diode is "open" (it will not work), the needle will NOT swing across the scale when touching the component with the probes in one direction or when the probes are reversed.
If the diode is "damaged" (does not work), the needle will swing fully across the scale when touching the component with the probes in one direction or when the probes are reversed.
If the diode is FUNCTIONAL, (works) the needle will swing about mid-way when touching the leads of the diode in one direction and it will not move when the probes are reversed.

WHY?

The positive of the battery inside an analogue multimeter comes out the black probe and that is why you will get a reading when the probers are "around the wrong way." The needle will swing a different amount for each resistance setting on the dial as the needle represents 0.6v drop and NOT an actual resistance.

There are two things you must remember.
1. When the diode is measured in one direction, the needle will will **not move at**

all. The technical term for this is the diode is **reverse biased**. It will not allow any current to flow. Thus the needle will not move.
When the diode is connected around the other way, the needle will swing to the right (move up scale) to about 80% of the scale. This position represents the voltage drop across the junction of the diode and is NOT a resistance value. If you change the resistance range, the needle will move to a slightly different position due to the resistances inside the meter. The technical term for this is the diode is **forward biased**. This indicates the diode is not faulty.
The needle will swing to a slightly different position for a "normal diode" compared to a Schottky diode. This is due to the different junction voltage drops.
However we are only testing the diode at very low voltage and it may break-down when fitted to a circuit due to a higher voltage being present or due to a high current flowing.

2. The leads of an **Analogue Multimeter** have the positive of the battery connected to the black probe and the readings of a "good diode" are shown in the following two diagrams:



The diode is REVERSE BIASED in the diagram above and diodes not conduct.



The diode is FORWARD BIASED in the diagram above and it conducts

TESTING A DIODE ON A DIGITAL METER

A Digital multimeter will measure the voltage-drop across the diode when the probes are connected in one direction (approx 0.640 on the scale) and a high reading (1) in the other direction. You need to select the "DIODE" setting on the dial as the other settings will produce a meaningless reading.





Some DIGITAL MULTIMETERS will show mV drop across the diode when the setting on the meter is "diode" or the "x1" or "x10" resistance range.

to Index

TESTING A LED

Some multimeters will test LEDs.
It depends on the voltage of the battery inside the case of the multimeter.
Many analogue multimeters have a single 1.5v cell and these cannot test LEDs.
Analogue Multimeters with 3v (for the resistance ranges) can test some LEDs.
White LEDs need about 3.6v and they may not illuminate on 3v.



The negative lead of an ANALOGUE meter is POSITIVE!
The multimeter must have 3v (2 cells)

Digital multimeters have a 9v battery and they will illuminate all colour LEDs when the leads are placed as shown in the diagram:



A Digital meter will illuminate all LEDs and the black probe touches the cathode.

to Index

TESTING A TRANSISTOR WITH A DIGITAL METER

Testing a transistor with a **Digital Meter** must be done on the "DIODE" setting as a digital meter does not deliver a current through the probes on some of the resistance settings and will not produce an accurate reading.
The "DIODE" setting must be used for diodes and transistors. It should also be called a "TRANSISTOR" setting.

TESTING A TRANSISTOR WITH AN ANALOGUE METER

The first thing you may want to do is test an unknown transistor for COLLECTOR, BASE AND EMITTER. You also want to perform a test to find out if it is NPN or PNP. That's what this test will provide.
You need a cheap multimeter called an ANALOGUE METER - a multimeter with a

scale and pointer (needle).
It will measure resistance values (normally used to test resistors) - (you can also test other components) and Voltage and Current. We use the resistance settings. It may have ranges such as "x10" "x100" "x1k" "x10"
Look at the resistance scale on the meter. It will be the top scale.
The scale starts at zero on the right and the high values are on the left. This is opposite to all the other scales.
When the two probes are touched together, the needle swings FULL SCALE and reads "ZERO." Adjust the pot on the side of the meter to make the pointer read exactly zero.

How to read: "x10" "x100" "x1k" "x10"
Up-scale from the zero mark is "1"
When the needle swings to this position on the "x10" setting, the value is 10 ohms.
When the needle swings to "1" on the "x100" setting, the value is 100 ohms.
When the needle swings to "1" on the "x1k" setting, the value is 1,000 ohms = 1k.
When the needle swings to "1" on the "x10k" setting, the value is 10,000 ohms = 10k.
Use this to work out all the other values on the scale.
Resistance values get very close-together (and very inaccurate) at the high end of the scale. [This is just a point to note and does not affect testing a transistor.]

Step 1 - FINDING THE BASE and determining NPN or PNP
Get an unknown transistor and test it with a multimeter set to "x10"
Try the 6 combinations and when you have the black probe on a pin and the red probe touches the other pins and the meter swings nearly full scale, you have an NPN transistor. The black probe is BASE
If the red probe touches a pin and the black probe produces a swing on the other two pins, you have a PNP transistor. The red probe is BASE
If the needle swings FULL SCALE or if it swings for more than 2 readings, the transistor is **FAULTY**.


This is an NPN transistor
The black probe is the BASE


This is a PNP transistor
The red probe is the BASE

Step 2 - FINDING THE COLLECTOR and EMITTER
Set the meter to "x10k."
For an NPN transistor, place the leads on the transistor and when you press hard on the two leads shown in the diagram below, the needle will swing almost full scale.


Set to "x10k"
This is the POSITIVE of the battery in the meter
push HERE
This is an NPN transistor
This is the NEGATIVE of the battery in the meter


Here is the equivalent circuit:
+
The finger is "turning ON the transistor"
collector
base
emitter
You have found the Collector Base and Emitter

For a PNP transistor, set the meter to "x10k" place the leads on the transistor and when you press hard on the two leads shown in the diagram below, the needle will swing almost full scale.


Set to "x10k"
This is the POSITIVE of the battery in the meter
This is a PNP transistor
This is the NEGATIVE of the battery in the meter
push HERE


Here is the equivalent circuit:
+
The finger is "turning ON the transistor"
emitter
base
collector
You have found the Collector Base and Emitter

[to Index](#)

For more details on testing components with a multimeter, see:
[Testing Electronic Components](#).

[to Index](#)

MULTIMETER TEST

1. What is the reading on the multimeter:



Answer

[to Index](#)

2. What is the reading on the multimeter:



Answer

to Index

3. What is the reading on the multimeter:


DCV
OFF
ACV
DCA
hFE
DT-832
DIGITAL
MULTIMETER
COM
+
–
12v

Answer

to Index

4. What is the voltage between the following points:


Terminal block
1
2
3
4
Terminal block
5
6
7
8
Battery
(9 volts)
Light bulb

Between 1 & 3	Between 5 & 7	Between 3 & 8	Between 1 & 7
Answer	**Answer**	**Answer**	**Answer**

to Index

5. What is the voltage on each multimeter:


B
A
C
switch closed
9v

Meter A	Meter B	Meter C
Answer	**Answer**	**Answer**

to Index

6. What is the voltage on each multimeter:


B
A
C
V
VΩ
A
COM
switch open
+
−
9v

Meter A	**Meter B**	**Meter C**
Answer	Answer	Answer

to Index

7. What is the reading on the multimeter:


Ω
V
A
V
A
OFF
V Ω
A
COM
Switch ON
SW1
C1
−
+
9v

Answer

to Index

8. The multimeter has three resistance ranges: **x1 ohms** **x100 ohms** **x10k ohms**. How far across the scale will the needle move on each range for a 4k7 resistor:



x1	**x100**	**x10k**
Answer	**Answer**	**Answer**

to Index

9. The resistance ranges on an ANALOGUE multimeter use the battery inside the case to move the pointer. If the multimeter is left on "**ohms range**" with the probes apart, will the battery go flat?

Answer

to Index

to Index

PCB CAD,
Fabrication
& Assembly
Pad2Pad
LEARN MORE »

1 **Download PDF Manual - Free** Download Free Manuals With AtoZManuals free.atozmanuals.com/PDF/Manual

2 **Splunk 2018 Predictions** Learn from Splunk experts about the tech & trends poised to transform business in 2018 splunk.com

Download PDF Manual - Free

Download Free Manuals With AtoZManuals free.atozmanuals.com/PDF/Manual



This eBook shows you how to TEST COMPONENTS.
To do this you need "TEST GEAR." The best item of Test Gear is a MULTIMETER. It can test almost 90% of all components. And that's what we will do in this eBook:

CONTENTS

Analogue Multimeter
Audio Stages
Batteries - testing
Burnt Resistor
Buying A Multimeter
Capacitors
Capacitors - decoupling caps
Capacitors in Parallel
Capacitor Substitution Box
Cells - batteries
Circuit Symbols
Co-Ax Cables
Colour Code (Resistor)
Coils
Continuity
Creating any value of R
Multimeters
Non-polar Capacitor (electrolytic)
Open Circuit
"Open" Resistor - damaged
Opto-couplers
Parallel - resistors
Parallel and Series Capacitors
Piezo Diaphragms
Piezo Buzzers
Potentiometers
Pots - testing
Power Diodes
Power Supply -see Basic Electronics 1A
Reed Switch
Relays
Remote Controls

Current - measuring
Current Sensing Resistors
Current Transformer
Damper Diodes
Darlington Transistors
Digital Chips
Digital Multimeter
Digital Transistors
Diodes replacing a diode
Discharge a Capacitor
Earth Leakage Detectors
Electrolytics
FETs
Fingers - to feel temperature
Focus pots
Fuses and 100mA fuses
Germanium Diodes
Heatsinks
Impedance - of a stage
IC's - also called Digital Chips
IC's - Analogue Chips
"In-Circuit" testing
Inductors
Inductors - measuring
Integrated Circuits
Isolation Transformer
Latching Reed Switch
LEDs
Logic Probe MkIIB
Logic Probe - Simple
Logic Probe - using CD4001
Logic Probe - using CD4011
Making your own components
Measuring Resistance
Measuring Voltage
Mica Washers and Insulators
Motor - testing
MOSFETs
Resistor Colour Code
Resistor Networks
Resistors - series
Resistor Substitution Box
Ripple Factor
Schottky Diodes
SCRs
Short Circuit
Signal Injector
Silicon diodes
Soldering
Spark Gaps
Speaker
Substitution Box
Super Probe MkII
Surface Mount - Packs
Surface-Mount Resistors
Surface-Mount Resistor Markings
Switches
Symbols
Test Equipment
Testing A Circuit
Testing A Resistor
Testing Components "In-Circuit"
Transformers - current transformer
Transformer Ratings 28v-0-28v
Transistor Outlines
Transistors
Transistors Digital
Triacs
Unknown resistors - testing
Using A Multimeter
Voltage Divider
Voltage Regulators
Voltages on a circuit
Wire Wound Resistor
Yokes
Zener Diodes
4-Band Resistors
5-Band Resistors
10-Turn Pots

Use your "brain, knowledge and your fingers."

Before we start, fixing anything is a combination of skill, luck and good diagnosis.
Sometimes you can fix something by letting it run until it finally fails.
Some things start to work as soon as you touch them.
Some things can never be fixed.
But some things can be fixed by feeling the temperature rise and deciding if it is getting too hot.
Sometimes you can smell something getting too hot.
Sometimes you can see SMOKE.
All these things make you a very clever technician and about 50% of faults will be fixed by looking for dry joints, burnt parts, overheating and carefully inspecting an item before you disturb it.

By simply touching different items you can quite often feel a hot item and home-in on the fault - at a saving of hours of work.
Servicing is not "A bull at a gate" approach.
You may be able to service something by turning it on and leaving it for hours - and start thinking.
It may take you a day to come up with the answer.
Believe me. That's how it worked for me - while fixing over 35,000 TV's.

TEST EQUIPMENT

Everyone thinks TEST EQUIPMENT will "solve the problem."
This is a big big MISTAKE.
Test equipment can help solve a problem and it can "lead to frustration," "give an incorrect answer," "mess you up," and make things worse.
You have to be very careful with test equipment and especially EXPENSIVE equipment because it is very sensitive and can detect pulses and glitches and voltages that are not affecting the operation of the circuit.
You will learn a lot of tricks when reading through this article, but let me say two things.
There are lots of faults and components that you cannot test with "test equipment" because they are either intermittent or the equipment does not load the device to the same extent as the circuit.
And secondly you need both an ANALOGUE multimeter and a DIGITAL meter to cover all the situations.
And if you are working on a car, you only need a $5.00 analogue meter because it will be dropped or fall into a crack, and you will only lose $5.00
You will learn that a digital meter will pick up spikes and signals on a line and show an incorrect reading.
That's why you need to back-up your readings with an analogue meter.
When you charge a battery it gets a "floating voltage" and this will be higher than the actual voltage, when the battery is fitted to a project. An analogue meter will draw a slight current and remove the "floating voltage."
Component testers can also give you a false reading, either because the component is out of range of the tester or intermittent and you need to be aware of this.
Oscilloscopes can also display waveforms that are parts of glitches or noise from other chips and these do not affect the operation of the part of the circuit you are investigating.
Sometimes you cannot pickup a pulse because it is not regular and the trigger on the oscilloscope does not show it on the screen. You may think it is missing.
It all depends on the "speed of the oscilloscope" - it's maximum frequency of operation.
Lastly- Power Supplies. You cannot test globes and motors on a power supply because the starting current can be 5 times more than the operating current. The power supply may not be able to deliver this high current and thus you will think the motor or globe is faulty.

MULTIMETERS

There are two types:

DIGITAL and ANALOGUE

A **Digital Multimeter** has a set of digits on the display and an Analogue Multimeter has a scale with a pointer (or needle).
You really need both types to cover the number of tests needed for designing and repair-work. We will discuss how they work, how to use them and some of the differences between them.

DIGITAL AND ANALOGUE MULTIMETERS

BUYING A MULTIMETER

There are many different types on the market.
The cost is determined by the number of ranges and also the extra features such as diode tester, buzzer (continuity), transistor tester, high DC current and others.
Since most multimeters are reliable and accurate, buy one with the greatest number of ranges at the lowest cost.
This article explains the difference between a cheap analogue meter, an expensive analogue meter and a digital meter. You will then be able to work out which two meters you should buy.

Multimeters are sometimes called a "meter", a "VOM" (Volts-Ohms-Milliamps or Volt Ohm Meter) or "multi-tester" or even "a tester" - they are all the same.

USING A MULTIMETER

Analogue and digital multimeters have either a rotary selector switch or push buttons to select the appropriate function and range. Some Digital Multimeters (DMMs) are auto ranging; they automatically select the correct range of voltage, resistance, or current when doing a test. However you need to select the function.

Before making any measurement you need to know what you are checking. If you are measuring voltage, select the AC range (10v, 50v, 250v, or 1000v) or DC range (0.5v, 2.5v, 10v, 50v, 250v, or 1000v). If you are measuring resistance, select the Ohms range (x1, x10, x100, x1k, x10k). If you are measuring current, select the appropriate current range DCmA 0.5mA, 50mA, 500mA. Every multimeter is different however the photo below shows a low cost meter with the basic ranges.


MODEL YX-1000A
Ω
X10
X100
X1K
0.5
50
250
DCmA
10
50
250
1000
DCV
+
ACV
10
50
250
1000
−
V.mA
AC10V
dB

The most important point to remember is this:
You must select a voltage or current range that is bigger or HIGHER than the maximum expected value, so the needle does not swing across the scale and hit the "end stop."
If you are using a DMM (Digital Multi Meter), the meter will indicate if the voltage or current is higher than the selected scale, by showing "OL" - this means "Overload." If you are measuring resistance such as 1M on the x10 range the "OL" means "Open Loop" and you will need to change the range. Some meters show "1' on the display when the measurement is higher than the display will indicate and some flash a set of digits to show over-voltage or over-current. A "-1" indicates the leads should be reversed for a "positive reading."
If it is an AUTO RANGING meter, it will automatically produce a reading, otherwise the selector switch must be changed to another range.

HV
000
DCV
OFF
ACV
DCA
hFE
NPN PNP
CE
10ADC
VΩmA
COM
DT-832
DIGITAL
MULTIMETER


A
10
10
2
200m
20m
2m
200µ
A
500
RCC
10A MAX
FUSED
2A MAX
FUSED
MAX
AC 750V
DC 1000V
MAX
600V
A
mAµA
COM
VΩ

The Common (negative) lead ALWAYS fits into the "COM" socket. The red lead fits into the red socket for Voltage and Resistance. Place the red lead (red banana plug) into "A" (for HIGH CURRENT "Amps") or mA,uA for LOW CURRENT.

The black "test lead" plugs into the socket marked "-" "Common", or "Com," and the red "test lead" plugs into meter socket marked "+" or "V-W-mA." The third banana socket measures HIGH CURRENT and the positive (red lead) plugs into this. You DO NOT move the negative "-" lead at any time.

The following two photos show the test leads fitted to a digital meter. The probes and plugs have "guards" surrounding the probe tips and also the plugs so you can measure high voltages without getting near the voltage-source.

FLUKE
115 TRUE RMS MULTIMETER
600.0
HOLD
MIN MAX
RANGE
OFF
mV
A
COM



What's the difference between **sensitivity, resolution,** and **accuracy?**



RESOLUTION

The smallest portion of the signal that can be measured and displayed on any range. The resolution on this Model DMM7510 7.5-digit DMM, 100mV range is 10nV. On the 1V range it is 100nV.

SENSITIVITY

The smallest change in the input signal that can be detected. On the 100mV range, this DMM is capable of sensitivity down to tens of nanovolts (nV).

ACCURACY AND REPEATABILITY

Accuracy is getting the same reading each time you take a reading.

Local
defbuffer1
No Script
CONT
MEASURE DC VOLTAGE
-010.000004mV
AUTO
AZERO
REL
Range 100mV
Auto
FUNCTIONS
DCV
DCI
2W Ω
Freq
Temp
ACV
ACI
4W Ω
Period
Cap
Digi V
Digi I
Cont
Diode
Ratio
Accuracy
Repeatability
High High
Low High
Low Low
KEITHLEY
-000.0027 mV DC
2000 MULTIMETER
KEITHLEY
A Tektronix Company

The question above applies to both (every) type of multimeter and the type of meter you use depends on the accuracy you need. Sometimes you are looking for 1mV change on a 20v rail. Only a DMM will (or a CRO) will produce a result.

Analogue meters have an "Ohms Adjustment" to allow for the change in voltage of the battery inside the meter (as it gets old).



20,000 Ω/VDC
5,000 Ω/VAC
- DC
+ DC
V DC
1000
500
250
50 µA
10 1V
2.5
V AC
1000
500
250
50
10
2.5
+ 50µA 250mV
+1V DC
+
Rx
10K
1K
100
10
1
Ω ADJ
500
250
100
10
1
mA DC
-
COM

"Ohms Adjust" is also called "ZERO SET"

The sensitivity of this meter is 20,000ohms/volt on the DC ranges and 5k/v on the AC ranges

Before taking a resistance reading (each time on any of the Ohms scales) you need to "ZERO SET" the scale, by touching the two probes together and adjust the pot until the needle reads "0" (swings FULL SCALE). If the pointer does not reach full scale, the batteries need replacing. Digital multimeters do not need "zero adjustment."

FIXING A MULTIMETER

A multimeter can get "broken" "damaged" and go "faulty."
I don't know why, but eventually they stop working.
It can be something simple like a flat battery, corroded battery contacts, broken switch or something complex, like the circuitry failing.
Multimeters are so cheap, you can buy a new one for less than $10.00
These meters can have a 10 amp range, transistor tester and measure up to 2 meg ohms.
That's why I suggest buying a $10.00 meter. They are just as good as a $60.00 meter and the cheapest meters last the longest.
Dropping an analogue meter can cause the hair spring to loop over one of the supports and the needle will not zero correctly. You will need to open the cover on the movement and lift the spring off the support with a needle.
A faulty meter can be used in a battery-charger circuit to measure the current or voltage if that scale is still reading-correctly.
Otherwise keep the leads and throw the meter out. It is too dangerous keeping a meter that shows an incorrect reading.

MEASURING FREQUENCY

VICHY
VC99
APO
DC
AUTO
-000.0
mV
MAX/MIN
Hz/DUTY
REL
HOLD
RANGE
DC/AC
Hz
hFE
V~
OFF
AUTO OFF POWER
TEMP
A
mA
COM
VΩHz
CAT II 1000V

Before we cover the normal uses for a multimeter, it is interesting to note that some **Digital Multimeters (DMM)** have features such as Capacitance, Frequency and measuring the gain of a transistor as well as a number of other features using probes such as a temperature probe. The VICHY VC99 meter above is an example and costs about $40.00.

Basic function	Range
DCV	600mV/6V/60V/600V/1000V
ACV	6V/60/600/1000V
DCA	600uA/6000uA/60mA/600mA/6A/20A
ACA	600uA/6000uA/60mA/600mA/6A/20A
Capacitance	40nF/400nF/4uF/40uF/400uF/2000uF
Resistance	600Ω/6kΩ/60kΩ/600kΩ/6MΩ/60MΩ
Frequency	100Hz/1kHz/10kHz/100kHz/1MHz/60MHz

Temperature	-40°C~1000°C
	0°F~1832°F

MEASURING VOLTAGE

Most of the readings you will take with a multimeter will be VOLTAGE readings. Before taking a reading, you should select the highest range and if the needle does not move up scale (to the right), you can select another range.
Always switch to the highest range before probing a circuit and keep your fingers away from the component being tested.
If the meter is Digital, select the highest range or use the auto-ranging feature, by selecting "V." The meter will automatically produce a result, even if the voltage is AC or DC.
If the meter is not auto-ranging, you will have to select V⎓ if the voltage is from a DC source or V~ if the voltage is from an AC source. DC means Direct Current and the voltage is coming from a battery or supply where the voltage is steady and not changing and AC means Alternating Current where the voltage is coming from a voltage that is rising and falling.
You can measure the voltage at different points in a circuit by connecting the black probe to chassis. This is the 0v reference and is commonly called "Chassis" or "Earth" or "Ground" or "0v."
The red lead is called the "measuring lead" or "measuring probe" and it can measure voltages at any point in a circuit. Sometimes there are "test points" on a circuit and these are wires or loops designed to hold the tip of the red probe (or a red probe fitted with a mini clip or mini alligator clip).
You can also measure voltages ACROSS A COMPONENT. In other words, the reading is taken in PARALLEL with the component. It may be the voltage across a transistor, resistor, capacitor, diode or coil. In most cases this voltage will be less than the supply voltage.
If you are measuring the voltage in a circuit that has a HIGH IMPEDANCE, the reading will be inaccurate, up to 90% !!!, if you use a cheap analogue meter.

Here's a simple case.

The circuit below consists of two 1M resistors in series. The voltage at the mid point will be 5v when nothing is connected to the mid point. But if we use a cheap analogue multimeter set to 10v, the resistance of the meter will be about 100k, if the meter has a sensitivity of 10k/v and the reading will be incorrect.
Here how it works:
Every meter has a sensitivity. The sensitivity of the meter is the sensitivity of the movement and is the amount of current required to deflect the needle FULL SCALE. This current is very small, normally 1/10th of a milliamp and corresponds to a sensitivity of 10k/volt (or 1/30th mA, for a sensitivity of 30k/v).
If an analogue meter is set to 10v, the internal resistance of the meter will be 100k for a 10k/v movement.
If this multimeter is used to test the following circuit, the reading will be inaccurate.
The reading should be 5v as show in diagram **A**.
But the analogue multimeter has an internal resistance of 100k and it creates a circuit shown in **C**.
The top 1M and 100k from the meter create a combined PARALLEL resistance of 90k. This forms a series circuit with the lower 1M and the meter will read less than 1v
If we measure the voltage across the lower 1M, the 100k meter will form a value of resistance with the lower 1M and it will read less than 1v
If the multimeter is 30k/v, the readings will be 2v. See how easy it is to get a totally inaccurate reading.



A



B



C



D



E

This introduces two new terms:
HIGH IMPEDANCE CIRCUIT and "RESISTORS in SERIES and PARALLEL."

If the reading is taken with a Digital Meter, it will be more accurate as a DMM does not take any current from the circuit (to activate the meter). In other words it has a very HIGH input impedance. Most Digital Multimeters have a fixed input resistance (impedance) of 10M - no matter what scale is selected. That's the reason for choosing a DMM for high impedance circuits. It also gives a reading that is accurate to about 1%.

MEASURING VOLTAGES IN A CIRCUIT

You can take many voltage-measurements in a circuit. You can measure "across" a component, or between any point in a circuit and either the positive rail or earth rail (0v rail). In the following circuit, the 5 most important voltage-measurements are shown. Voltage "A" is across the electret microphone. It should be between 20mV and 500mV. Voltage "B" should be about 0.6v. Voltage "C" should be about half-rail voltage. This allows the transistor to amplify both the positive and negative parts of the waveform. Voltage "D" should be about 1-3v. Voltage "E" should be the battery voltage of 12v.



MEASURING VOLTAGES IN A CIRCUIT

MEASURING CURRENT

You will rarely need to take current measurements, however most multimeters have DC current ranges such as 0.5mA, 50mA, 500mA and 10Amp (via the extra banana socket) and some meters have AC current ranges. Measuring the current of a circuit will tell you a lot of things. If you know the normal current, a high or low current can let you know if the circuit is overloaded or not fully operational.

Current is always measured when the circuit is working (i.e: with power applied).
It is measured IN SERIES with the circuit or component under test.
The easiest way to measure current is to remove the fuse and take a reading across the fuse-holder. Or remove one lead of the battery or turn the project off, and measure across the switch.
If this is not possible, you will need to remove one end of a component and measure with the two probes in the "opening."
Resistors are the easiest things to desolder, but you may have to cut a track in some circuits. You have to get an "opening" so that a current reading can be taken.
The following diagrams show how to connect the probes to take a CURRENT reading.
Do not measure the current ACROSS a component as this will create a "short-circuit."
The component is designed to drop a certain voltage and when you place the probes across this component, you are effectively adding a "link" or "jumper" and the voltage at the left-side of the component will appear on the right-side. This voltage may be too high for the circuit being supplied and the result will be damage.



Measuring current through a resistor



Measuring the current of a globe



Do NOT measure the CURRENT of a battery
(by placing the meter directly across the terminals)
A battery will deliver a very HIGH current
and damage the meter

Do not measure the "current a battery will deliver" by placing the probes across the terminals. It will deliver a very high current and damage the meter instantly. There are special battery testing instruments for this purpose.
When measuring across an "opening" or "cut," place the red probe on the wire that supplies the voltage (and current) and the black probe on the other wire. This will produce a "POSITIVE" reading.

A positive reading is an UPSCALE READING and the pointer will move across the scale - to the right. A "NEGATIVE READING" will make the pointer hit the "STOP" at the left of the scale and you will not get a reading. If you are using a Digital Meter, a negative sign "-" will appear on the screen to indicate the probes are around the wrong way. No damage will be caused. It just indicates the probes are connected incorrectly.
If you want an accurate CURRENT MEASUREMENT, use a digital meter.

MEASURING RESISTANCE

Turn a circuit off before measuring resistance.
If any voltage is present, the value of resistance will be incorrect.
In most cases you cannot measure a component while it is in-circuit. This is because the meter is actually measuring a voltage across a component and calling it a "resistance." The voltage comes from the battery inside the meter. If any other voltage is present, the meter will produce a false reading.
If you are measuring the resistance of a component while still "in circuit," (with the power off) the reading will be lower than the true reading.



Measuring resistance

138
rolson
27259

**Measuring resistance of a heater
(via the leads)**


4.2Ω
OFF
Ω
2M
200 K
20K
2K
200
ΩV
COM
mA
10A
resistance wire

Measuring the resistance of a piece of resistance-wire


1.5 kΩ
12 V
Power must be disconnected from the circuit

Measuring the resistance of a resistor


+
—
-
+
TENERGY
Lithium
9V 1200mAh

Do not measure the "Resistance of a Battery"

1. Do not measure the "resistance of a battery." The resistance of a battery (called the Internal impedance) is not measured as shown in the diagrams above. It is measured by creating a current-flow and measuring the voltage across the battery.



Placing a multimeter set to **resistance** (across a battery) will destroy the meter.
2. Do not try to measure the resistance of any voltage or any "supply."

Resistance is measured in OHMs.
The resistance of a 1cm x 1cm bar, one metre long is 1 ohm.
If the bar is thinner, the resistance is higher. If the bar is longer, the resistance is higher.
If the material of the bar is changed, the resistance is higher.
When carbon is mixed with other elements, its resistance increases and this knowledge is used to make RESISTORS.
Resistors have RESISTANCE and the main purpose of a resistor is to reduce the CURRENT FLOW.
It's a bit like standing on a hose. The flow reduces.
When current flow is reduced, the output voltage is also reduced and that why the water does not spray up so high. Resistors are simple devices but they produce many different effects in a circuit.
A resistor of nearly pure carbon may be 1 ohm, but when non-conducting "impurities" are added, the same-size resistor may be 100 ohms, 1,000 ohms or 1 million ohms.
Circuits use values of less than 1 ohm to more than 22 million ohms.

Resistors are identified on a circuit with numbers and letters to show the exact value of resistance - such as 1k 2k2 4M7
The letter Ω (omega - a Greek symbol) is used to identify the word "Ohm." but this symbol is not available on some word-processors, so the letter "R" is used.
The letter "E" is also sometimes used and both mean "Ohms."
A one-ohm resistor is written "1R" or "1E." It can also be written "1R0" or "1E0."
A resistor of one-tenth of an ohm is written "0R1" or "0E1." The letter takes the place of the decimal point.
10 ohms = 10R
100 ohms = 100R
1,000 ohms = 1k (k= kilo = one thousand)
10,000 ohms = 10k
100,000 ohms = 100k
1,000,000 ohms = 1M (M = MEG = one million)

The size of a resistor has nothing to do with its resistance. The size determines the wattage of the resistor - how much heat it can dissipate without getting too hot.
Every resistor is identified by colour bands on the body, but when the resistor is a surface-mount device, numbers are used and sometimes letters.
You MUST learn the colour code for resistors and the following table shows all the colours for the most common resistors from 1/10th of an ohm to 22 Meg ohms for resistors with 5% and 10% tolerance.

If 3rd band is gold, Divide by 10
If 3rd band is silver, Divide by 100
(to get 0.22ohms etc)



ROW	SILVER	GOLD	BLACK	BROWN	RED	ORANGE	YELLOW	GREEN
1-	R10	1R0	10R	100R	1K0	10K	100K	1M0
2-	R11	1R1	11R	110R	1K1	11K	110K	1M1
3-	R12	1R2	12R	120R	1K2	12K	120K	1M2
4-	R13	1R3	13R	130R	1K3	13K	130K	1M3
5-	R15	1R5	15R	150R	1K5	15K	150K	1M5
6-	R16	1R6	16R	160R	1K6	16K	160K	1M6
7-	R18	1R8	18R	180R	1K8	18K	180K	1M8
8-	R20	2R0	20R	200R	2K0	20K	200K	2M0
9-	R22	2R2	22R	220R	2K2	22K	220K	2M2
10-	R24	2R4	24R	240R	2K4	24K	240K	2M4
11-	R27	2R7	27R	270R	2K7	27K	270K	2M7
12-	R30	3R0	30R	300R	3K0	30K	300K	3M0
13-	R33	3R3	33R	330R	3K3	33K	330K	3M3
14-	R36	3R6	36R	360R	3K6	36K	360K	3M6
15-	R39	3R9	39R	390R	3K9	39K	390K	3M9
16-	R43	4R3	43R	430R	4K3	43K	430K	4M3
17-	R47	4R7	47R	470R	4K7	47K	470K	4M7
18-	R51	5R1	51R	510R	5K1	51K	510K	5M1
19-	R56	5R6	56R	560R	5K6	56K	560K	5M6
20-	R62	6R2	62R	620R	6K2	62K	620K	6M2
21-	R68	6R8	68R	680R	6K8	68K	680K	6M8
22-	R75	7R5	75R	750R	7K5	75K	750K	7M5
23-	R82	8R2	82R	820R	8K2	82K	820K	8M2
24-	R91	9R1	91R	910R	9K1	91K	910K	9M1
								10M
								BLUE

COLOR CODES FOR THE WHOLE E12/E24 RANGE OF RESISTORS

The twelve odd rows - 1, 3, 5... - represent values available in the E12 range only, plus 10M

Reading 4-band resistors

The most "common" type of resistor has 4 bands and is called the 10% resistor. It now has a tolerance of 5% but is still called the "10% type" as the colours increase by 20% so that a resistor can be 10% higher or 10% lower than a particular value and all the resistors produced in a batch can be used.

The first 3 bands produce the resistance and the fourth band is the "tolerance" band.

Gold = 5%

(Silver =10% but no modern resistors are 10%!! - they are 5% 2% or 1%)


1R0
1R2
1R5
1R8
2R2
2R7
3R3
3R9
4R7
5R6
6R8
8R2
10R
12R
15R
18R
22R
27R
33R
39R
47R
56R
68R
82R
100R
120R
150R
180R
220R
270R
330R
390R
470R
560R
680R
820R
1k0
1k2
1k5
1k8
2k2
2k7
3k3
3k9
4k7
5k6
6k8
8k2


10k
12k
15k
18k
22k
27k
33k
39k
47k
56k
68k
82k
100k
120k
150k
180k
220k
270k
330k
390k
470k
560k
680k
820k
1M0
1M2
1M5
1M8
2M2
2M7
3M3
3M9
4M7
5M6
6M8
8M2
10M
22M
0R1
R22
0R0
zero ohm (link)


4 Bands
22Ω, 5%
5 Bands
2200Ω, 1%
6 Bands
100KΩ,
0.1%, 15ppm

	Significant Figures			Multiplier	Tolerance	Temperature Coefficient
Silver				0.01	10%	
Gold				0.1	5%	
Black 0	0	0	0	1		
Brown 1	1	1	1	10	1%	100ppm
Red 2	2	2	2	100	2%	50ppm
Orange 3	3	3	3	1K		15ppm
Yellow 4	4	4	4	10K		25ppm
Green 5	5	5	5	100k	0.5%	
Blue 6	6	6	6	1M	0.25%	
Purple 7	7	7	7	10M	0.1%	
Grey 8	8	8	8			
White 9	9	9	9			

Resistor Color Code System

Here is another well-designed resistor colour code chart:


Color Codes
File
Help
Resistors 4 bands
Resistors 5 bands
Capacitors
R and C calc
1
2
3
4
Band 1
Black
Brown
Red
Orange
Yellow
Green
Blue
Violet
Gray
White
Band 2
Black
Brown
Red
Orange
Yellow
Green
Blue
Violet
Gray
White
Band 3
Silver
Gold
Black
Brown
Red
Orange
Yellow
Green
Blue
Band 4
Red
Gold
Silver
No Color
Clear
View Colors
(No decimals)

4 7 × 1000 = 47000 ohms

47 k-ohms

0.047 M-ohms

± 10 %

Color Code Search

Value: 47

Unit: ○ ohms ● k-ohms ○ M-ohms

Tolerance (%): 10

Nearest value (E12 series): 47 k-ohms

Download the program and save it on your desk-top for future reference:
ColourCode.exe (520KB)
ColourCode.zip (230KB)
ColourCode.rar (180KB)

RESISTORS LESS THAN 10 OHMS

When the **third** band is gold, it indicates the value of the "colors" must be divided by 10.
Gold = "divide by 10" to get values 1R0 to 8R2
When the **third** band is silver, it indicates the value of the "colors" must be divided by 100. (Remember: more letters in the word "silver" thus the divisor is "a larger division.")
Silver = "divide by 100" to get values R1 to R82
e.g: 0R1 = 0.1 ohm 0R22 = point 22 ohms
See 4th Column above for examples.

The letters "R, k and M" take the place of a decimal point.
e.g: 1**R**0 = 1 ohm 2**R**2 = 2 point 2 ohms 22**R** = 22 ohms
2**k**2 = 2,200 ohms 100**k** = 100,000 ohms
2**M**2 = 2,200,000 ohms

HOW TO REMEMBER THE COLOUR CODE:

Each colour has a "number" (or divisor) corresponding to it.
Most of the colours are in the same order as in the spectrum. You can see the spectrum in a rainbow. It is: ROY G BIV and the colours for resistors are in the same sequence.

black
brown - colour of increasing temperature

red
orange
yellow
green
blue
(indigo - that part of the spectrum between blue and violet)
violet
gray
white

colour	**value**	No of zero's
silver	-2	divide by 100
gold	-1	divide by 10
black	0	No zeros
brown	1	0
red	2	00
orange	3	,000 or k
yellow	4	0,000
green	5	00,000
blue	6	M
violet	7	
gray	8	
white	9	


Resistor -- 4 Bands
Multiplier
2nd Digit
1st Digit
Tolerance
Resistor -- 5 Bands
Multiplier
3rd Digit
Tolerance
2nd Digit
1st Digit



Band Color	Digit	Multiplier	Tolerance
Black	■ 0	1	---
Brown	🟫 1	10	±1%
Red	🟥 2	100	±2%
Orange	🟧 3	1,000	±3%
Yellow	🟨 4	10,000	±4%
Green	🟩 5	100,000	---
Blue	🟦 6	1,000,000	---
Violet	🟪 7	10,000,000	---
Gray	▨ 8	100,000,000	---
White	□ 9	---	---
Gold	▨ ---	0.1	±5%
Silver	▨ ---	0.01	±10%
None	---	---	±20%

Here are some common ways to remember the colour code:

Bad Beer Rots Our Young Guts, But Vodka Goes Well
Bright Boys Rave Over Young Girls But Violet Gets Wed
Bad Boys Rave Over Young Girls But Violet Gets Wed with Gold and Silver.

Reading 5-band resistors:

5-band resistors are easy to read if you remember two simple points. The first three bands provide the digits in the answer and the 4th band supplies the number of zero's.

Reading "STANDARD VALUES" (**on 5-band resistors**)

5-band resistors are also made in "Standard Values" but will have different colours to 4-band "common" resistors - and will be confusing if you are just starting out. For instance, a 47k 5% resistor with 4-bands will be: yellow-purple-orange-gold. For a 47k 1% resistor the colours will be yellow-purple-black-red-brown. The brown colour-band represents 1%.
The first two colour-bands for a STANDARD VALUE or "common value" in 1% or 5% will be the SAME. These two bands provide the digits in the answer.
It's the 3rd band for a 5% resistor that is expanded into two bands in a 1% resistor. But it's easy to follow.
For a standard value, the 3rd band in a 1% resistor is BLACK. This represents a ZERO in the answer. (For 5-band resistors BLACK represents a ZERO when in the third band. This is different to 4-band resistors where black represents the word OHMS! If the third band is BROWN, the answer will be 1).
So the 4th band has to represent one-less ZERO and is one colour UP THE COLOUR CHART! In other words the 3rd and 4th bands (combined) on a 1% resistor produces the same number of zero's as the 3rd band on a 5% resistor!

Resistors come in a range of values and the two most common are the E12 and E24 series. The E12 series comes in twelve values for each decade. The E24 series comes in twenty-four values per decade.

E12 series - 10, 12, 15, 18, 22, 27, 33, 39, 47, 56, 68, 82

E24 series - 10, 11, 12, 13, 15, 16, 18, 20, 22, 24, 27, 30, 33, 36, 39, 43, 47, 51, 56, 62, 68, 75, 82, 91

Here is the complete list of 1% 1/4watt resistors from:
CIRCUIT SPECIALISTS. The following list covers 10 ohms (10R) to 1M.
To buy 1% resistors from Circuit Specialists, click: HERE.

10R
12R1
15R
18R2
22R1
27R4
30R1
33R2
36R5
39R2
47R5
49R9
51R1
56R2
68R1
75R
82R5
90R9
100R
121R
150R
182R
200R
221R
240R
249R
274R
301R
332R
348R
392R
402R
475R
499R
565R
604R
681R
750R
806R
825R
909R
1k0
1k21
1k5
1k82
2k
2k21
2k2
2k43
2k49
2k67
2k74
3k01
3k32
3k48
3k57
3k74
3k83
3k92
4k02
4k22
4k64
4k75
4k7
4k87
4k99
5k11
5k23
5k36
5k49
5k62
5k76
5k9
6k04
6k19
6k81
7k15
7k5
7k87
71k5
8k06
8k25
8k45
8k66
8k87
9k09
9k31
9k53
9k76
10k
11k
12k
12k1
12k4
13k
14k7
15k
15k8
16k9
17k4
17k8
18k2
20k
22k1
22k6
23k7
24k9
27k4
29k4
30k1
33k2
34k8
36k5
38k3
39k2
40k2
44k2
46k4
47k
47k5
49k9
51k1
53k6
56k2
61k9
68k1
69k8
75k0
82k5
90k
90k9
95k3
100k
121k
147k
150k
182k
200k
212k
221k
226k
249k
274k
301k
332k
357k
392k
475k
487k
499k
562k
604k
1M

Here is the list of 1% resistors from suppliers (such as Farnell):

1R0
1R2
1R5
2R2
2R7
3R3
3R9
4R7
5R6
6R2
6R8
7R5
8R2
9R1
10R
11R
12R
13R
15R
16R
18R
20R
22R
24R
27R
30R
33R
36R
39R
43R
47R
51R
56R
62R
68R
75R
82R
91R
100R
110R
120R
130R
150R
160R
180R
200R
220R
240R
270R
300R
330R
360R
390R
430R
470R
510R
560R
620R
680R
750R
820R
910R
1k
1k1
1k2
1k3
1k5
1k6
1k8
2k0
2k2
2k4
2k7
3k
3k3
3k6
3k9
4k3
4k7
5k1
5k6
6k2
6k8
7k5
8k2
9k1
10k
11k
12k
13k
15k
16k
18k
20k
22k
24k
27k
30k
33k
36k
39k
43k
47k
51k
56k
62k
68k
75k
82k
91k
100k
110k
120k
130k
150k
160k
180k
200k
220k
240k
270k
300k
330k
360k
390k
430k
470k
510k
560k
620k
680k
750k
820k
910k
1M

Surface Mount Resistors


0.120"
0.060"
"120 thou"
x
"60 thou"
"one hundered and twenty thousands of an inch"
100
10R
10 ohm
R047
0.047R
R025
0.025R
sense resistor
1213
121k
4990
499R
241
240R
0.080"
0.050"
474
470 kΩ
1188
11.8 ohm
10R0
10 ohm
M47
470 kΩ
R47
0.47 Ω
4R7
4.7 Ω
47R
47 Ω
K47
470 Ω
4K7
4.7 kΩ
47K
47 kΩ
R464
0.464 Ω
464R
464 Ω
4K64
4.64 kΩ
471
470 Ω
472
4.7 kΩ
473
47 kΩ
0
00
000
0000
000
SHORT-CIRCUITING "ZERO-OHM LINKS" OR "JUMPERS"
243
1206
mm
0
G0706AB
10R0
1206
1502
0805

1206 and 0805 SURFACE MOUNT RESISTORS


103
103
105
103
102
102
104
104
103
102
273
393
752
103
102
103
473
103
102
101
101
SIL
0743+
204

3-digit Surface Mount resistors on a PC board


R19
1000
R18
1000
R17
FS0368-2
Y1
D5
R23
C10
D6
R24
2490
106D
N202K
U1
Q3
R20
100
R16
R10
1003
R9
R7
1003
C9
C6
C8
R21
2002
D3
Q2
2002
R22
C1
R14
2002
D2
R6
R4
1003
R3
R1
1003
DATAQ INSTRUMENTS INC

4-digit Surface Mount resistors on a PC board

The photo above shows surface mount resistors on a circuit board. The components

that are not marked are capacitors (capacitors are NEVER marked).
All the SM resistors in the above photos conform to a 3-digit or 4-digit code. But there are a number of codes, and the 4-digit code caters for high tolerance resistors, so it's getting very complicated.
Here is a basic 3-digit SM resistor:



A 330k SM resistor

The first two digits represent the two digits in the answer. The third digit represents the number of zero's you must place after the two digits. The answer will be OHMS. For example: 334 is written 33 0 000. This is written 330,000 ohms. The comma can be replaced by the letter "k". The final answer is: 330k.
222 = 22 00 = 2,200 = 2k2
473 = 47 000 = 47,000 = 47k
474 = 47 0000 = 470,000 = 470k
105 = 10 00000 = 1,000,000 = 1M = one million ohms
There is one trick you have to remember. Resistances less than 100 ohms are written: 100, 220, 470. These are 10 and NO zero's = 10 ohms = 10R
or 22 and no zero's = 22R or 47 and no zero's = 47R. Sometimes the resistor is marked: 10, 22 and 47 to prevent a mistake.

Remember:
R = ohms
k = kilo ohms = 1,000 ohms
M = Meg = 1,000,000 ohms
The 3 letters (R, k and M) are put in place of the decimal point. This way you cannot make a mistake when reading a value of resistance.

Surface Mount **CURRENT SENSING** Resistors

Many new types of CURRENT SENSING surface-mount resistors are appearing on the market and these are creating lots of new problems.
Fortunately all resistors are marked with the value of resistance and these resistors are identified in MILLIOHMS. A miili ohm is one thousandth or an ohm and is written 0.001 when writing a normal mathematical number.
When written on a surface mount resistor, the letter R indicates the decimal point and it also signifies the word "OHM" or "OHMS" and one milli-ohm is written R001
Five miiliohms is R005 and one hundred milliohms is R100
Some surface mount resistors have the letter "M" after the value to indicate the resistor has a rating of 1 watt. e.g: R100M These surface-mount resistors are specially-made to withstand a high temperature and a surface-mount resistor of the same size is normally 250mW or less.
These current-sensing resistors can get extremely hot and the PC board can become burnt or damaged.
When designing a PC board, make the lands very large to dissipate the heat.
Normally a current sensing resistor is below one ohm (1R0) and it is easy to identify them as R100 etc.
You cannot measure the value of a current sensing resistor as the leads of a multimeter have a higher resistance than the resistor and few multimeters can read values below one ohm.
If the value is not visible, you will have to refer to the circuit.
Before replacing it, work out why it failed.
Generally it gets too hot. Use a larger size and add tiny heatsinks on each end.
Here are some surface=mount current-sense resistors:



3 milli-ohm



220 milli-ohm



15 milli-ohm



9 point 1 milli-ohm



5 milli-ohm



220 milli-ohm



50 milli-ohm 1%


39200C
R002
1%

2 milli-ohm


R030
DALE
R03F
R030

30 milli-ohm



10 milli-ohm



1-watt ????

THE COMPLETE RANGE OF SM RESISTOR MARKINGS

Click to see the complete range of SM resistor markings for 3-digit code:

Click to see the complete range of SM resistor markings for 4-digit code:

0000 is a value on a surface-mount resistor. It is a zero-ohm **LINK**!
Resistances less than 10 ohms have 'R' to indicate the position of the decimal point.
Here are some examples:

Three Digit Examples	Four Digit Examples
330 is 33 ohms ***- not 330 ohms***	**1000 is 100 ohms** ***- not 1000 ohms***
221 is 220 ohms	**4992 is 49 900 ohms, or 49k9**
683 is 68 000 ohms, or 68k	**1623 is 162 000 ohms, or 162k**
105 is 1 000 000 ohms, or 1M	**0R56 or R56 is 0.56 ohms**
8R2 is 8.2 ohms	

A new coding system has appeared on **1% types**. This is known as the EIA-96 marking method. It consists of a three-character code. The first two digits signify the 3 significant digits of the resistor value, using the lookup table below. The third character - a letter - signifies the multiplier.

code	value	code	value	code	value	code	value	code	value	code	value
01	100	**17**	147	**33**	215	**49**	316	**65**	464	**81**	681
02	102	**18**	150	**34**	221	**50**	324	**66**	475	**82**	698
03	105	**19**	154	**35**	226	**51**	332	**67**	487	**83**	715
04	107	**20**	158	**36**	232	**52**	340	**68**	499	**84**	732
05	110	**21**	162	**37**	237	**53**	348	**69**	511	**85**	750
06	113	**22**	165	**38**	243	**54**	357	**70**	523	**86**	768
07	115	**23**	169	**39**	249	**55**	365	**71**	536	**87**	787
08	118	**24**	174	**40**	255	**56**	374	**72**	549	**88**	806
09	121	**25**	178	**41**	261	**57**	383	**73**	562	**89**	825
10	124	**26**	182	**42**	267	**58**	392	**74**	576	**90**	845
11	127	**27**	187	**43**	274	**59**	402	**75**	590	**91**	866
12	130	**28**	191	**44**	280	**60**	412	**76**	604	**92**	887
13	133	**29**	196	**45**	287	**61**	422	**77**	619	**93**	909
14	137	**30**	200	**46**	294	**62**	432	**78**	634	**94**	931
15	140	**31**	205	**47**	301	**63**	442	**79**	649	**95**	953
16	143	**32**	210	**48**	309	**64**	453	**80**	665	**96**	976

The **multiplier** letters are as follows:

letter	mult	letter	mult
F	**100000**	**B**	**10**
E	**10000**	**A**	**1**
D	**1000**	**X or S**	**0.1**
C	**100**	**Y or R**	**0.01**

22A is a 165 ohm resistor, **68C** is a 49900 ohm (49k9) and **43E** a 2740000 (2M74). This marking scheme applies to 1% resistors only.

A similar arrangement can be used for **2% and 5%** tolerance types. The multiplier letters are identical to 1% ones, but occur **before** the number code and the following **code** is used:

2%				**5%**			
code	**value**	**code**	**value**	**code**	**value**	**code**	**value**
01	100	**13**	330	**25**	100	**37**	330
02	110	**14**	360	**26**	110	**38**	360
03	120	**15**	390	**27**	120	**39**	390
04	130	**16**	430	**28**	130	**40**	430
05	150	**17**	470	**29**	150	**41**	470
06	160	**18**	510	**30**	160	**42**	510
07	180	**19**	560	**31**	180	**43**	560

08	200	**20**	620	**32**	200	**44**	620
09	220	**21**	680	**33**	220	**45**	680
10	240	**22**	750	**34**	240	**46**	750
11	270	**23**	820	**35**	270	**47**	820
12	300	**24**	910	**36**	300	**48**	910

With this arrangement, **C31** is 5%, 18000 ohm (18k), and **D18** is 510000 ohms (510k) 2% tolerance.
Always check with an ohm-meter (a multimeter) to make sure.

Chip resistors come in the following styles and ratings:
Style: 0402, 0603, 0805, 1206, 1210, 2010, 2512, 3616, 4022
Power Rating: 0402(1/16W), 0603(1/10W), 0805(1/8W), 1206(1/4W), 1210(1/3W), 2010(3/4W), 2512(1W), 3616(2W), 4022(3W)
Tolerance: 0.1%, 0.5%, 1%, 5%
Temperature Coefficient: 25ppm 50ppm 100ppm

EIA marking code for surface mount (SMD) resistors

01S = 1R	01R = 10R	01A = 100R	01B = 1k	01C = 10k	01D = 100k	01E = 1M	01F = 10M
02S = 1R02	02R = 10R2	02A = 102R	02B = 1k02	02C = 10k2	02D = 102k	02E = 1M02	
03S = 1R05	03R = 10R5	03A = 105R	03B = 1k05	03C = 10k5	03D = 105k	03E = 1M05	18F = 15M
04S = 1R07	04R = 10R7	04A = 107R	04B = 1k07	04C = 10k7	04D = 107k	04E = 1M07	
05S = 1R1	05R = 11R	05A = 110R	05B = 1k1	05C = 11k	05D = 110k	05E = 1M1	30F = 20M
06S = 1R13	06R = 11R3	06A = 113R	06B = 1k13	06C = 11k3	06D = 113k	06E = 1M13	
07S = 1R15	07R = 11R5	07A = 115R	07B = 1k15	07C = 11k5	07D = 115k	07E = 1M15	
08S = 1R18	08R = 11R8	08A = 118R	08B = 1k18	08C = 11k8	08D = 118k	08E = 1M18	
09S = 1R21	09R = 12R1	09A = 121R	09B = 1k21	09C = 12k1	09D = 121k	09E = 1M21	
10S = 1R24	10R = 12R4	10A = 124R	10B = 1k24	10C = 12k4	10D = 124k	10E = 1M24	
11S = 1R27	11R = 12R7	11A = 127R	11B = 1k27	11C = 12k7	11D = 127k	11E = 1M27	
12S = 1R3	12R = 13R	12A = 130R	12B = 1k3	12C = 13k	12D = 130k	12E = 1M3	
13S = 1R33	13R = 13R3	13A = 133R	13B = 1k33	13C = 13k3	13D = 133k	13E = 1M33	
14S = 1R37	14R = 13R7	14A = 137R	14B = 1k37	14C = 13k7	14D = 137k	14E = 1M37	
15S = 1R4	15R = 14R	15A = 140R	15B = 1k4	15C = 14k	15D = 140k	15E = 1M4	
16S = 1R43	16R = 14R3	16A = 143R	16B = 1k43	16C = 14k3	16D = 143k	16E = 1M43	
17S = 1R47	17R = 14R7	17A = 147R	17B = 1k47	17C = 14k7	17D = 147k	17E = 1M47	
18S = 1R5	18R = 15R	18A = 150R	18B = 1k5	18C = 15k	18D = 15k	18E = 1M5	
19S = 1R54	19R = 15R4	19A = 154R	19B = 1k54	19C = 15k4	19D = 154k	19E = 1M54	
20S = 1R58	20R = 15R8	20A = 158R	20B = 1k58	20C = 15k8	20D = 158k	20E = 1M58	
21S = 1R62	21R = 16R2	21A = 162R	21B = 1k62	21C = 16k2	21D = 162k	21E = 1M62	
22S = 1R65	22R = 16R5	22A = 165R	22B = 1k65	22C = 16k5	22D = 165k	22E = 1M65	
23S = 1R69	23R = 16R9	23A = 169R	23B = 1k69	23C = 16k9	23D = 169k	23E = 1M69	
24S = 1R74	24R = 17R4	24A = 174R	24B = 1k74	24C = 17k4	24D = 174k	24E = 1M74	
25S = 1R78	25R = 17R8	25A = 178R	25B = 1k78	25C = 17k8	25D = 178k	25E = 1M78	
26S = 1R82	26R = 18R2	26A = 182R	26B = 1k82	26C = 18k2	26D = 182k	26E = 1M82	
27S = 1R87	27R = 18R7	27A = 187R	27B = 1k87	27C = 18k7	27D = 187k	27E = 1M87	
28S = 1R91	28R = 19R1	28A = 191R	28B = 1k91	28C = 19k1	28D = 191k	28E = 1M91	
29S = 1R96	29R = 19R6	29A = 196R	29B = 1k96	29C = 19k6	29D = 196k	29E = 1M96	
30S = 2R0	30R = 20R0	30A = 200R	30B = 2k0	30C = 20k0	30D = 200k	30E = 2M0	
31S = 2R05	31R = 20R5	31A = 205R	31B = 2k05	31C = 20k5	31D = 205k	31E = 2M05	
32S = 2R10	32R = 21R0	32A = 210R	32B = 2k10	32C = 21k0	32D = 210k	32E = 2M10	
33S = 2R15	33R = 21R5	33A = 215R	33B = 2k15	33C = 21k5	33D = 215k	33E = 2M15	
34S = 2R21	34R = 22R1	34A = 221R	34B = 2k21	34C = 22k1	34D = 221k	34E = 2M21	
35S = 2R26	35R = 22R6	35A = 226R	35B = 2k26	35C = 22k6	35D = 226k	35E = 2M26	
36S = 2R32	36R = 23R2	36A = 232R	36B = 2k32	36C = 23k2	36D = 232k	36E = 2M32	
37S = 2R37	37R = 23R7	37A = 237R	37B = 2k37	37C = 23k7	37D = 237k	37E = 2M37	
38S = 2R43	38R = 24R3	38A = 243R	38B = 2k43	38C = 24k3	38D = 243k	38E = 2M43	
39S = 2R49	39R = 24R9	39A = 249R	39B = 2k49	39C = 24k9	39D = 249k	39E = 2M49	
40S = 2R55	40R = 25R5	40A = 255R	40B = 2k55	40C = 25k5	40D = 255k	40E = 2M55	
41S = 2R61	41R = 26R1	41A = 261R	41B = 2k61	41C = 26k1	41D = 261k	41E = 2M61	
42S = 2R67	42R = 26R7	42A = 267R	42B = 2k67	42C = 26k7	42D = 267k	42E = 2M67	
43S = 2R74	43R = 27R4	43A = 274R	43B = 2k74	43C = 27k4	43D = 274k	43E = 2M74	
44S = 2R80	44R = 28R0	44A = 280R	44B = 2k80	44C = 28k0	44D = 280k	44E = 2M80	
45S = 2R87	45R = 28R7	45A = 287R	45B = 2k87	45C = 28k7	45D = 287k	45E = 2M87	
46S = 2R94	46R = 29R4	46A = 294R	46B = 2k94	46C = 29k4	46D = 294k	46E = 2M94	
47S = 3R01	47R = 30R1	47A = 301R	47B = 3k01	47C = 30k1	47D = 301k	47E = 3M01	
48S = 3R09	48R = 30R9	48A = 309R	48B = 3k09	48C = 30k9	48D = 309k	48E = 3M09	
49S = 3R16	49R = 31R6	49A = 316R	49B = 3k16	49C = 31k6	49D = 316k	49E = 3M16	
50S = 3R24	50R = 32R4	50A = 324R	50B = 3k24	50C = 32k4	50D = 324k	50E = 3M24	
51S = 3R32	51R = 33R2	51A = 332R	51B = 3k32	51C = 33k2	51D = 332k	51E = 3M32	
52S = 3R4	52R = 34R0	52A = 340R	52B = 3k4	52C = 34k0	52D = 340k	52E = 3M4	
53S = 3R48	53R = 34R8	53A = 348R	53B = 3k48	53C = 34k8	53D = 348k	53E = 3M48	

54S = 3R57	54R = 35R7	54A = 357R	54B = 3k57	54C = 35k7	54D = 357k	54E = 3M57
55S = 3R65	55R = 36R5	55A = 365R	55B = 3k65	55C = 36k5	55D = 365k	55E = 3M65
56S = 3R74	56R = 37R4	56A = 374R	56B = 3k74	56C = 37k4	56D = 374k	56E = 3M74
57S = 3R83	57R = 38R3	57A = 383R	57B = 3k83	57C = 38k3	57D = 383k	57E = 3M83
58S = 3R92	58R = 39R2	58A = 392R	58B = 3k92	58C = 39k2	58D = 392k	58E = 3M92
59S = 4R02	59R = 40R2	59A = 402R	59B = 4k02	59C = 40k2	59D = 402k	59E = 4M02
60S = 4R12	60R = 41R2	60A = 412R	60B = 4k12	60C = 41k2	60D = 412k	60E = 4M12
61S = 4R22	61R = 42R2	61A = 422R	61B = 4k22	61C = 42k2	61D = 422k	61E = 4M22
62S = 4R32	62R = 43R2	62A = 432R	62B = 4k32	62C = 43k2	62D = 432k	62E = 4M32
63S = 4R42	63R = 44R2	63A = 442R	63B = 4k42	63C = 44k2	63D = 442k	63E = 4M42
64S = 4R53	64R = 45R3	64A = 453R	64B = 4k53	64C = 45k3	64D = 453k	64E = 4M53
65S = 4R64	65R = 46R4	65A = 464R	65B = 4k64	65C = 46k4	65D = 464k	65E = 4M64
66S = 4R75	66R = 47R5	66A = 475R	66B = 4k75	66C = 47k5	66D = 475k	66E = 4M75
67S = 4R87	67R = 48R7	67A = 487R	67B = 4k87	67C = 48k7	67D = 487k	67E = 4M87
68S = 4R99	68R = 49R9	68A = 499R	68B = 4k99	68C = 49k9	68D = 499k	68E = 4M99
69S = 5R11	69R = 51R1	69A = 511R	69B = 5k11	69C = 51k1	69D = 511k	69E = 5M11
70S = 5R23	70R = 52R3	70A = 523R	70B = 5k23	70C = 52k3	70D = 523k	70E = 5M23
71S = 5R36	71R = 53R6	71A = 536R	71B = 5k36	71C = 53k6	71D = 536k	71E = 5M36
72S = 5R49	72R = 54R9	72A = 549R	72B = 5k49	72C = 54k9	72D = 549k	72E = 5M49
73S = 5R62	73R = 56R2	73A = 562R	73B = 5k62	73C = 56k2	73D = 562k	73E = 5M62
74S = 5R76	74R = 57R6	74A = 576R	74B = 5k76	74C = 57k6	74D = 576k	74E = 5M76
75S = 5R9	75R = 59R0	75A = 590R	75B = 5k9	75C = 59k0	75D = 590k	75E = 5M9
76S = 6R04	76R = 60R4	76A = 604R	76B = 6k04	76C = 60k4	76D = 604k	76E = 6M04
77S = 6R19	77R = 61R9	77A = 619R	77B = 6k19	77C = 61k9	77D = 619k	77E = 6M19
78S = 6R34	78R = 63R4	78A = 634R	78B = 6k34	78C = 63k4	78D = 634k	78E = 6M34
79S = 6R49	79R = 64R9	79A = 649R	79B = 6k49	79C = 64k9	79D = 649k	79E = 6M49
80S = 6R65	80R = 66R5	80A = 665R	80B = 6k65	80C = 66k5	80D = 665k	80E = 6M65
81S = 6R81	81R = 68R1	81A = 681R	81B = 6k81	81C = 68k1	81D = 681k	81E = 6M81
82S = 6R98	82R = 69R8	82A = 698R	82B = 6k98	82C = 69k8	82D = 698k	82E = 6M98
83S = 7R15	83R = 71R5	83A = 715R	83B = 7k15	83C = 71k5	83D = 715k	83E = 7M15
84S = 7R32	84R = 73R2	84A = 732R	84B = 7k32	84C = 73k2	84D = 732k	84E = 7M32
85S = 7R5	85R = 75R0	85A = 750R	85B = 7k5	85C = 75k0	85D = 750k	85E = 7M5
86S = 7R68	86R = 76R8	86A = 768R	86B = 7k68	86C = 76k8	86D = 768k	86E = 7M68
87S = 7R87	87R = 78R7	87A = 787R	87B = 7k87	87C = 78k7	87D = 787k	87E = 7M87
88S = 8R06	88R = 80R6	88A = 806R	88B = 8k06	88C = 80k6	88D = 806k	88E = 8M06
89S = 8R25	89R = 82R5	89A = 825R	89B = 8k25	89C = 82k5	89D = 825k	89E = 8M25
90S = 8R45	90R = 84R5	90A = 845R	90B = 8k45	90C = 84k5	90D = 845k	90E = 8M45
91S = 8R66	91R = 86R6	91A = 866R	91B = 8k66	91C = 86k6	91D = 866k	91E = 8M66
92S = 8R87	92R = 88R7	92A = 887R	92B = 8k87	92C = 88k7	92D = 887k	92E = 8M87
93S = 9R09	93R = 90R9	93A = 909R	93B = 9k09	93C = 90k9	93D = 909k	93E = 9M09
94S = 9R31	94R = 93R1	94A = 931R	94B = 9k31	94C = 93k1	94D = 931k	94E = 9M31
95S = 9R53	95R = 95R3	95A = 953R	95B = 9k53	95C = 95k3	95D = 953k	95E = 9M53
96S = 9R76	96R = 97R6	96A = 976R	96B = 9k76	96C = 97k6	96D = 976k	96E = 9M76

If you want an accurate RESISTANCE measurement, remove the resistor from the circuit and use a Digital meter.

SURFACE MOUNT COMPONENTS - PACKS

Talking Electronics has packs of components for the repairman. The following packs are available:

SURFACE MOUNT RESISTOR PACK consists of 1 off each standard value
10 ohms to 1M & 2M2 (60 resistors)
$14.20 including pack and post

SURFACE MOUNT CAPACITOR PACK consists of:
2 - 10p 5 - 47p 5 - 100p 5 - 470p 5 - 1n 5 - 10n 5 - 22n 5 - 100n
5 - 1u 16v electrolytic 5 - 10u 16v electrolytic
(40 components)
$23.80 including pack and post

SURFACE MOUNT DIODE PACK consists of:
5 - 1N 4148 (marked as "A6")
$10.00 including pack and post

SURFACE MOUNT TRANSISTOR PACK consists of:
5 - BC 848 (marked as "1K") NPN
5 - BC858 PNP
$10.00 including pack and post

email **Colin Mitchell** for details on how to pay by credit card or PayPal.

CREATING ANY VALUE OF RESISTANCE

Any value of resistance can be created by connecting two resistors in PARALLEL or SERIES.
You can also create a higher wattage resistor by connecting them in SERIES OR PARALLEL.
We are only going to cover two EQUAL VALUE resistors in SERIES or in PARALLEL.
If you want to create a "Special Value," simply connect two resistors and read the value with a Digital Meter. Keep changing the values until you get the required value.
We are not going into series or Parallel formulae. You can easily find a value with a multimeter.

TWO EQUAL-VALUE RESISTORS IN SERIES

Two equal-value resistors IN SERIES creates a value of DOUBLE. You simply ADD the values.
This can be done with any to two values as shown. Three equal-value resistors in series is three times the value.


1k
1k
total = 2k


1k
10k
total = 11k


2k2
2k2
total = 4k4


2k2
4k7
total = 6k9


4k7
4k7
total = 9k4 (10k)


4k7
100k
total = 104k7


100k
100k
total = 200k


100k
1M
total = 1M1

TWO EQUAL-VALUE RESISTORS IN PARALLEL

Two equal-value resistors IN PARALLEL creates a value of HALF. Three equal-value resistors in parallel is equal to one-third the value.


1k
total = 470R
1k


2k2
total = 1k1
2k2


4k7
total = 2k35
4k7


100k
total = 50k
100k


220k
total = 110k
220k


1M
total = 470k
1M

If you want a particular value and it is not available, here is a chart.
Use 2 resistors in series or parallel as shown:

Required Value	R1	Series/ Parallel	R2	Actual value:

10	4R7	S	4R7	9R4
12	10	S	2R2	12R2
15	22	P	47	14R9
18	22	P	100	18R
22	10	S	12	22
27	22	S	4R7	26R7
33	22	S	10	32R
39	220	P	47	38R7
47	22	S	27	49
56	47	S	10	57
68	33	S	33	66
82	27	S	56	83

There are other ways to combine 2 resistors in parallel or series to get a particular value. The examples above are just one way. 4R7 = 4.7 ohms

TESTING A RESISTOR

To check the value of a resistor, it should be removed from the circuit. The surrounding components can affect the reading and make it lower.
Resistors **VERY RARELY** change value, but if it is overheated or damaged, the resistance can increase. You can take the reading of a resistor "in-circuit" in one direction then the other, as the surrounding components may have diodes and this will alter the reading.
You can also test a resistor by feeling its temperature-rise. It is getting too hot if you cannot hold your finger on it (some "metal film" resistors are designed to tolerate quite high temperatures).

TESTING AN "AC" RESISTOR

There is no such thing as an "AC" resistor. Resistors are just "resistors" and they can be in AC circuits or DC circuits. Resistors can be given names such as "Safety Resistor" "Ballast Resistor" "LOAD Resistor" "Feed Resistor" "Dropper Resistor" or "Supply Resistor." These are just normal resistors with a normal resistance - except a "Safety Resistor."
A safety resistor is made of a flame-proof material such as metal-oxide-film and not carbon-composition. It is designed to "burn out" when too much current flows BUT NOT CATCH FIRE.
It is a low-value resistor and has a voltage-drop across it but this is not intentional. The voltage-drop is to create a "heating-effect" to burn out the resistor. In all the other types of resistor, the voltage-drop is intentional.
A Ballast resistor is a normal resistor and can be called a Power resistor, Dropper resistor, Supply resistor or Feed resistor. It is designed to reduce the voltage from one source and deliver a lower voltage. It is a form of: "in-line" resistor.
A Load Resistor is generally connected across the output of a circuit and turns the energy it receives, into heat.

RESISTOR NETWORKS

To reduce the number of resistors in a circuit, some engineers use a set of identical resistors in a package called a Single-In-Line (SIL) resistor network. It is made with many resistors of the same value, all in one package. One end of each resistor is connected all the other resistors and this is the common pin, identified as pin 1 and has a dot on the package.
These packages are very reliable but to make sure all the resistors are as stated, you need to locate pin 1. All values will be identical when referenced to this pin.



RESISTOR NETWORKS

Some resistor networks have a "4S" printed on the component. The 4S indicates the package contains 4 independent resistors that are not wired together inside. The housing has eight leads as shown in the second image.
Independent resistors have an even number of pins and measuring between each pair will produce identical values. Resistance between any pair will indicate leakage and may be a fault.

WIRE WOUND RESISTOR

A wire wound resistor is also called a POWER RESISTOR. This type of resistor can have a resistance as low as 0.1 ohms (one-tenth of an ohm) or as high as about 10k.
The image shows a 0.68 ohm resistor as the letter "R" represents the DECIMAL POINT and R68 is the same a .68 and this is 0.68 ohms. The wattage is 9 watts.
This resistor will allow xxx amps to flow. To work out the current, use the formula:
Power = Current x Current x resistance
9 = Current x Current x .68
Divide both sides by 0.68
13.2 = Current x Current
Find the square root of 13.2
Current = 3.6 amps

When 3.6 amps flow through the resistor, the voltage appearing across it will be:
V = current x resistance
= 3.6 x 0.68
= 2.5v and the wattage (heat) loss will be 9 watts.

The purpose of a resistor like this is to stop or reduce "ripple." Ripple is the noise or hum in an amplifier when the sound is turned up.
There are many reasons why you need to reduce the level of hum and this resistor will remove ripple as large as 2.5v when 3.6 amps is flowing, provided you have filter electrolytics on both side of the resistor to assist in removing the ripple.

If the letter "R" is in a different position, the value of resistance would be:

68R = 68Ω
6R8 = 6.8Ω
R68 = 0.68Ω

If you replace the R68 resistor a 6R8 resistor by mistake, the voltage across it will rise to 25v and if 3.6 amps flows, the wattage will be: 90 watts!!!
The resistor will glow red and burn out.

TESTING A POSISTOR

A Posistor is a resistor that connects in series with the degaussing coil around the picture tube or **Monitor.** When cold, it has a very low resistance and a large current flows when the monitor or TV is switched on. This current heats up the Posistor and the resistance increases. This causes the current to decrease and any magnetism in the shadow mask is removed. The posistor can one or two elements and it is kept warm so the resistance remains high. Many Posistors have a second element inside the case that connects directly to the supply to keep the Positive Temperature Coefficient resistor high so that the current through the degaussing coil falls to almost zero. This constant heat eventually destroys the package.
The heavy current that flows when a set is turned ON also causes the posistor to crack and break and this results in poor purity on the screen - as the shadow mask gradually becomes magnetic..
Posistors have different resistance values from different manufacturers and must be replaced with an identical type.
They can be checked for very low resistance when cold but any loose pieces inside the case will indicate a damaged component.

A "BURNT" RESISTOR - normally and technically called a "burnt-out" resistor.

The resistance of a "burnt" resistor can sometimes be determined by scraping away the outer coating - if the resistor has a spiral of resistance-material. You may be able to find a spot where the spiral has been damaged.



Note the spirals of conductive carbon.
The number of spirals has nothing to with the resistance.
It is the amount of carbon particles in the "track" that determines the resistance. It is also the thickness and width of the track that determines the resistance.
And then it is the overall size of the resistor that determines the wattage.
And then the size of the leads, the closeness to the PCB and the size of the lands that eventually determines how hot the resistor will get.

Clean the "spot" (burnt section of the spiral) very carefully and make sure you can get a good contact with the spiral and the tip of your probe. Measure from one lead of the resistor to the end of the damaged spiral. Then measure from the other lead to the other end of the spiral.
Add the two values and you have an approximate value for the resistor. You can add a small amount for the damaged section.
This process works very well for damaged wire-wound resistors. They can be pulled apart and each section of the resistance-wire (nichrome wire) measured and added to get the full resistance.

There is another way to determine the value of a damaged resistor.
Get a set of resistors of the same wattage as the damaged component and start with a high value. It's handy to know if the resistor is in the range: 10ohm to 100ohms or 1k to 10k etc, but this is not essential.
Start with a very high value and turn the circuit ON. You can perform voltage tests and if you know the expected output voltage, decrease the resistance until this voltage is obtained.
If you do not know the expected voltage, keep reducing the value of resistance until the circuit works as designed.
This is the best advice in a situation where you do not know the value of a resistor.

There is a third way to determine the value and this requires measuring the voltage drop across the resistor and the current-flow. By multiplying the two you will get a wattage and this must be less than the wattage of the resistor being replaced.

TESTING POTENTIOMETERS (variable resistors)

To check the value of a variable resistor, it should be removed from circuit or at least 2 legs should be removed. A Rheostat is a variable resistor using only one end and the middle connected to a circuit.
The resistance between the two outside pins is the value marked on the component and the centre leg will change from nearly zero to the full resistance as the shaft is rotated.
"Pots" generally suffer from "crackle" when turned and this can be fixed by spraying up the shaft and into the pot via the shaft with a tube fixed to a can of "spray-lubricant" (contact cleaner).
"Pre-set pots" and "trim pots" are miniature versions of a potentiometer and they are all tested the same. The photo shows a pot, two mini pots and 3 mini trim pots.

103
102
P102
N911

10-Turn POTs

A 10-turn pot is one of the worst items to be designed. I remove them immediately from any design.
You don't know the position of the wiper. You don't know which way you are turning the wiper and you can't remember which way you turned the post "the last time."
The screwdriver always falls out of the slot.
If you need fine adjustment, place fixed resistors on each side of the pot and use a normal mini trim pot with much less resistance.



FOCUS POTS

Focus pots quite often get a spot of dirt where the wiper touches the track. Cleaning with spray fixes the bad focus but if the pot is leaking to chassis from inside the pot (due to the high voltage on the terminals) simply remove it from the chassis and leave it floating (this will restore the high voltage to the picture tube) or you can use one from an old chassis.

MAKING YOUR OWN RESISTOR, CAPACITOR, INDUCTOR or DIODE

Quite often you will not have the exact value of resistance or capacitance for a repair.
We have already covered placing resistors and capacitors in parallel and series:

Resistors in Parallel and/or Series
Capacitors in Parallel and/or Series

Here are some extras:

RESISTORS
Two 1k 0.5watt resistors in parallel produces a 470R 1watt resistor.
Two 1k 0.5watt resistors in series produces a 2k 1watt resistor.

CAPACITORS
Two 100n 100v capacitors in series produces a 50n capacitor @200v

INDUCTORS: Two inductors in series - **ADD THE VALUES**

DIODES: Two 1Amp 400v diodes in series produces a 1Amp 800v diode
Two 1Amp 400v diodes in parallel produces a 2Amp 400v diode

ZENER DIODES: Zener diodes can be connected in series to get a higher voltage.
Two 12v zener diodes in series produces a 24v zener.

CONTINUITY

Some multimeters have a "buzzer" that detects when the probes are touching each other or the resistance between the probes is very LOW. This is called a CONTINUITY TESTER.
You can use the resistance scale "x1" or "x10" to detect low values of resistance.
Set the pointer to "0" (right end of the scale) by touching the probes together and adjusting the "zero ohms" control.
When taking a reading, you will have to decide if a low value of resistance is a short-circuit or an "operating value."
For instance, the cold resistance of a 12v car globe is very low (about 2 ohms) and it increases (about 6 times) to 12 ohms when hot.
The "resistance of a circuit" may be very low as the electrolytics in the circuit are uncharged. This may not indicate a true "short-circuit."
The measurement across a diode is not a resistance-value but a "voltage-drop" and that is why the needle swings nearly full-scale.
Leads and wires and cords have a small resistance and depending on the length of the lead, this small resistance may be affecting a circuit.
Remember this:
When a circuit takes 1 amp, and the resistance of the leads is 1 ohm, the voltage drop across the leads will be 1v.
That's why a 12v battery supplying a circuit with these leads will have 11v at the circuit.
Note:
Turn off the equipment before making any continuity tests. The presence of even a small voltage (from an electrolytic) can give a false reading.
You can determine the resistance of a lead very accurately by taking the example above and applying it to your circuit.
If the battery is 12.6v and the voltage across the circuit is 10v, when the current is 2.6 amps, the resistance of the "leads" is 12.6 - 10 = 2.6 R=V/I = 2.6/2.6 = 1ohm. By making the lead shorter or using thicker wire, the resistance will be less and the voltage on the project will increase.
When taking readings in a circuit that has a number of diodes built-into IC's (Integrated Circuits) and transistors, some Continuity Testers will beep and give a false reading.
The following circuit has the advantage of providing a beep when a short-circuit is detected but does not detect the small voltage drop across a diode. This is ideal when testing logic circuits as it is quick and you can listen for the beep while

concentrating on the probe. Using a multimeter is much slower.



CONTINUITY TESTER

You can build the circuit on Matrix Board and add it to your Test Equipment.
You will need lots of "Test Equipment" and they can be built from circuits in this eBook.

TESTING FUSES, LEADS AND WIRES

All these components come under the heading TESTING for CONTINUITY. Turn off all power to the equipment before testing for shorts and continuity. Use the low resistance "Ohms Scale" or CONTINUITY range on your multimeter. All fuses, leads and wires should have a low, very low or zero resistance. This proves they are working.

A BLOWN FUSE

The appearance of a fuse after it has "blown" can tell you a lot about the fault in the circuit.
If the inside of the glass tube (of the fuse) is totally blackened, the fuse has been damaged very quickly. This indicates a very high current has passed through the fuse.
Depending on the rating of the fuse, (current rating) you will be able to look for components that can pass a high current when damaged - such as high power transistors, FETs, coils, electrolytics. Before re-connecting the supply, you should test the "SUPPLY RAILS" for resistance. This is done by measuring them on a low OHMs range in one direction then reverse the leads to see if the resistance is low in the other direction.
A reading can be very low at the start because electrolytics need time to charge-up and if the reading gradually increases, the power rail does not have a short. An overload can occur when the supply voltage rises to nearly full voltage, so you sometimes have to fit a fuse and see how long it takes to "blow."
If the fuse is just slightly damaged, you will need to read the next part of this eBook, to see how and why this happens:

FAST AND SLOW BLOW FUSES

There are many different sizes, shapes and ratings of a fuse. They are all current ratings as a fuse does not have a voltage rating. Some fuses are designed for cars as they fit into the special fuse holders. A fuse can be designed for 50mA, 100mA, 250mA, 315mA, 500mA, 1Amp, 1.5amp, 2amp, 3amp, 3.15amp 5amp, 10amp, 15amp, 20amp, 25amp, 30amp, 35amp, 50amp and higher.
Some fuses are fast-blow and some are slow-blow.
A "normal" fuse consists of a length of thin wire. Or it may be a loop of wire that is thin near the middle of the fuse. This is the section that will "burn-out."
A "normal" fuse is a fast-blow fuse. For instance, a 1amp fuse will remain intact when up to 1.25 amp flows. When a circuit is turned on, it may take 2-3 amps for a very short period of time and a normal 1 amp fuse will get very hot and the wire will stretch but not "burn-out." You can see the wire move when the supply turns on.
If the current increases to 2amps, the fuse will still remain intact. It needs about 3 amp to heat up the wire to red-hot and burn out.

If the current increases to 5 amp, the wire VOLATILISES (burns-out) and deposits carbon-black on the inside of the glass tube.

A slow-blow fuse uses a slightly thicker piece of wire and the fuse is made of two pieces of wire joined in the middle with a dob of low-temperature solder. Sometimes one of the pieces of wire is a spring and when the current rises to 2.5 amp, the heat generated in the wire melts the solder and the two pieces of wire "spring apart."

A slow-blow fuse will allow a higher current-surge to pass through the fuse and the wire will not heat up and sag.

Thus the fuse is not gradually being damaged and it will remain in a perfect state for a long period of time.

A fuse does not protect electronic equipment from failing. It acts AFTER the equipment has failed.

It will then protect a power supply from delivering a high current to a circuit that has failed.

If a slow-blow fuse has melted the solder, it could be due to a slight overload, slight weakening of the fuse over a period of time or the current-rating may be too low. You can try another fuse to see what happens.

You can replace a fast-acting fuse (normal fuse) with a slow blow if the fast-acting fuse has been replaced a few times due to deterioration when the equipment is turned on.

But you cannot replace a slow-blow fuse with a fast acting fuse as it will be damaged slightly each time the equipment is turned on and eventually fail.

100mA FUSES

Fuses below about 100mA are very hard to make and very unreliable.

Many circuits take a high current when turned to charge the electrolytics and a 100mA (or 50mA or 63mA fuse) will bow and stretch and change shape, every time the equipment is turned ON. Eventually it will break, due to it heating-up and stretching.

To produce a reliable fuse below 100mA, some manufacturers have placed a resistor inside the fuse and connected it to a spring. One end of the resistor is soldered to a wire with low-temperature metal and when the resistor gets hot, the metal softens and the spring pulls the resistor away from the wire.

Quite often you can heat up the metal and connect the wire and the fuse is perfect.

This type of fuse is called a DELAY fuse and the current rating is shown on the end-cap.

The value of the resistor determines the current rating.

There is a small voltage across this type of fuse and it means the circuit sees a slightly lower voltage than the supply voltage.

The third photo shows the pot of solder or low-temp metal and a wire connected to a spring. The heat generated in the wire is passed to the solder and it softens. The spring pulls the two components apart. You can smash the glass and set up the fuse in the two fuse-holders and repair the fuse while you wait for a new fuse to arrive.





TESTING COILS, INDUCTORS and YOKES

Coils, inductors, chokes and yokes are just coils (turns) of wire. The wire may be wrapped around a core made of iron or ferrite.
It is labeled "L" on a circuit board.
You can test this component for continuity between the ends of the winding and also make sure there is no continuity between the winding and the core.
The winding can be less than one ohm, or greater than 100 ohms. A coil of wire is also called an INDUCTOR and it might look like a very simple component, but it can operate in a very complex way.
The way it works is a discussion for another eBook. It is important to understand the turns are insulated but a slight fracture in the insulation can cause two turns to touch each other and this is called a "SHORTED TURN" or you can say the inductor has "SHORTED TURNS."
When this happens, the inductor allows the circuit to draw MORE CURRENT. This causes the fuse to "blow."
The quickest way to check an inductor is to replace it, but if you want to measure the inductance, you can use an INDUCTANCE METER. You can then compare the inductance with a known good component.
An inductor with a shorted turn will have a very low or zero inductance, however you may not be able to detect the fault when it is not working in a circuit as the fault may be created by a high voltage generated between two of the turns.
Faulty yokes (both horizontal and vertical windings) can cause the picture to reduce in size and/or bend or produce a single horizontal line.
A TV or monitor screen is the best piece of Test Equipment as it has identified the fault. It is pointless trying to test the windings further as you will not be able to test them under full operating conditions. The fault may not show up when a low voltage (test voltage) is applied.

MEASURING AND TESTING INDUCTORS

Inductors are measured with an INDUCTANCE METER but the value of some inductors is very small and some Inductance Meters do not give an accurate reading. The solution is to measure a larger inductor and note the reading. Now put the two inductors in SERIES and the values ADD UP - just like resistors in SERIES. This way you can measure very small inductors. VERY CLEVER!

Question from a reader: *Can I add an inductor to stop a fuse blowing?*

Basically, an inductor NEVER prevents a fuse blowing because an inductor prevents spikes on one lead (we will call the INPUT lead), appearing on its other lead.
This is the detection and prevention of current that exists for a very short period of time.
A fuse detects an excess of current that occurs over a very long period of time and they are entirely two different "detectors."
One cannot assist the other in any way.

An inductor is basically a coil of wire. It may be thick or thin wire. The value of the inductor is a combination of the number of turns and the material on which the wire is wound.
The value of an inductor does not change over say a period of 20 years but it can go faulty by the enamel cracking and two turns touching. This can also be due to the difference in voltage between the two turns creating a spark between the turns and creating a "short."
When you test it, the high voltage is not present and it will test ok.
You may not think a few turns of wire will have any effect on improving a circuit, but spikes are very high frequency and the inductor will have a very big effect on reducing them.
An inductor (say 100uH) can be produced in many different sizes and the thickness of the wire will be important as it determines the current that can flow through the inductor.
The term "inductor" also includes those with two or more windings and these components are called TRANSFORMERS. These devices can get "shorts" and "leaks" between the windings and sparks can be seen between the windings. These sparks do not occur when you are testing them on test-equipment so the only way to

guarantee success is to replace it with an identical replacement.

TESTING SWITCHES and RELAYS

Switches and relays have contacts that open and close mechanically and you can test them for CONTINUITY. However these components can become intermittent due to dirt or pitting of the surface of the contacts due to arcing as the switch is opened.
It is best to test these items when the operating voltage and current is present as they quite often fail due to the arcing. A switch can work 49 times then fail on each 50th operation. The same with a relay. It can fail one time in 50 due to CONTACT WEAR.
If the contacts do not touch each other with a large amount of force and with a large amount of the metal touching, the current flowing through the contacts will create HEAT and this will damage the metal and sometimes reduce the pressure holding the contact together.
This causes more arcing and eventually the switch heats up and starts to burn.
Switches are the biggest causes of fire in electrical equipment and households.

A relay also has a set of contacts that can cause problems.
There are many different types of relays and basically they can be put into two groups.
1. An electromagnetic relay is a switch operated by magnetic force. This force is generated by current through a coil. The relay opens and closes a set of contacts. The contacts allow a current to flow and this current can damage the contacts.
Connect 5v or 12v to the coil (or 24v) and listen for the "click" of the points closing. Measure the resistance across the points to see if they are closing.
You really need to put a load on the points to see if they are clean and can carry a current.
The coil will work in either direction.
If not, the relay is possibly a CMOS relay or Solid State relay.

2. An electronic relay (Solid State Relay) does not have a winding. It works on the principle of an opto-coupler and uses a LED and Light Activated SCR or Opto-TRIAC to produce a low resistance on the output. The two pins that energise the relay (the two input pins) must be connected to 5v (or 12v) around the correct way as the voltage is driving a LED (with series resistor). The LED illuminates and activates a light-sensitive device.



TESTING REED SWITCHES

A reed switch is generally contained in a long glass tube:



A wire or lead comes out each end for soldering to the reed switch to the project. The two "blades" inside the switch are made from a material that can be magnetised but does not retain its magnetism. This effect is called "temporally magnetised" (not permanently magnetised) and really only "passes" magnetism from one end to the other when in the presence of a magnet. One of the blades is made of a soft material and it will bend very easily. The other one is much stiffer.



When a magnet is placed under the two blades (or on top), the magnetism from the magnet is passed to the two blades (INDUCTION or MUTUAL INDUCTION - commonly called INDUCED) and it produces a very weak magnet (in the blade) that is identical to the powerful magnet as far as the position of the north and south poles are concerned). Initially it produces a N-S and N-S set of poles and this makes the two blades click together because the top blade will be South at the contact and the bottom blade will be North.

When the two blades click together the magnetism runs through the two blades and keeps them together. The two blades attract and the switch is closed. When the magnet is removed, the magnetism in the two blades ceases and the two blades move apart.

Since there is a very small amount of movement in the top blade, this switch has a limited number of operations. Eventually it will fail. It is a mechanical device and is not suited for detecting a spinning shaft as 100,000 revolutions will very quickly weaken the switch.

If the switch does not make contact or remains closed, the moveable blade can be cracked or broken. This can be very hard to see. So replace the switch.

LATCHING REED SWITCH

A "normal" reed switch can be converted into a **LATCHING REED SWITCH** by carefully placing a magnet below the switch and moving it away so the two blades open. Now move it slightly closer but do not allow the blades to close.

This is called putting a "SET" on the switch and the two blades will have a small magnetic effect "induced" in them but not enough to close the contacts:



Now bring a strong magnet up to the reed switch on the other side of the glass tube with the north pole above the north of the lower magnet. This effect will increase the INDUCED MAGNETISM in the blades and close the contacts:



Remove the top magnet and the lower magnet will induce enough magnetism into the blades to keep them closed:



Now bring the upper magnet near the reed switch with the south pole above the north pole of the lower magnet. (In other words: AROUND THE OTHER WAY) This will have the effect of reducing the induced magnetism in the blades and a point will be reached when the two contacts will separate:



Remove the top magnet and the switch will remain separated because the lower magnet will not have sufficient influence on the blades to close the contact:



CAPACITORS

Capacitors are one of the most difficult things to test. That's because they don't give a reading on a multimeter and their value can range from 1p to 100,000u.
A faulty capacitor may be "open" when measured with a multimeter, and a good capacitor will also be "open."

You need a piece of test equipment called a CAPACITANCE METER to measure the value of a capacitor.

HOW A CAPACITOR WORKS

There are two ways to describe how a capacitor works. Both are correct and you have to combine them to get a full picture.
A capacitor has INFINITE resistance between one lead and the other.
This means no current flows **through** a capacitor. But it works in another way.
Suppose you have a strong magnet on one side of a door and a piece of metal on the other. By sliding the magnet up and down the door, the metal rises and falls.
The metal can be connected to a pump and you can pump water by sliding the magnet up and down.
A capacitor works in exactly the same way.
If you raise a voltage on one lead of a capacitor, the other lead will rise to the same voltage. This needs more explaining - we are keeping the discussion simple.
It works just like the magnetic field of the magnet through a door.
The next concept is this:
Capacitors are equivalent to a tiny rechargeable battery.
They store energy when the supply-voltage is present and release it when the supply drops.
These two concepts can be used in many ways and that's why capacitors perform tasks such as filtering, time-delays, passing a signal from one stage to another and create many different effects in a circuit.

CAPACITOR VALUES

The basic unit of capacitance is the FARAD. (C) This is the value used in all equations, but it is a very large value. A one FARAD capacitor would be the size of a car if made with plates and paper. Most electronic circuits use capacitors with smaller values such as 1p to 1,000u. 1p is about equal to two parallel wires 2cm long. 1p is one picofarad.

The easiest way to understand capacitor values is to start with a value of 1u. This is one microfarad and is one-millionth of a Farad. A 1 microfarad capacitor is about 1cm long and the diagram shows a 1u electrolytic.



Smaller capacitors are ceramic and they look like the following. This is a 100n (0.1u)ceramic:

To read the value on a capacitor you need to know a few facts.

The basic value of capacitance is the FARAD.
1 microfarad is one millionth of 1 farad.
1 microfarad is divided into smaller parts called nanofarad.
1,000 nanofarad = 1 microfarad
Nanofarad is divided into small parts called picofarad
1,000 picofarad = 1 nanofarad.

Recapping:
1p = 1 picofarad.   1,000p = 1n (1 nanofarad)
1,000n = 1u (1 microfarad)
1,000u = 1millifarad
1,000,000u = 1 FARAD.

Examples:
All ceramic capacitors are marked in "p" (puff")
A ceramic with 22 is 22p = 22 picofarad
A ceramic with 47 is 47p = 47 picofarad
A ceramic with 470 is 470p = 470 picofarad
A ceramic with 471 is 470p = 470 picofarad
A ceramic with 102 is 1,000p = 1n
A ceramic with 223 is 22,000p = 22n
A ceramic with 104 is 100,000p = 100n = 0.1u

TYPES OF CAPACITOR

For testing purposes, there are two types of capacitor.
Capacitors from 1p to 100n are non-polar and can be inserted into a circuit around either way.
Capacitors from 1u to 100,000u are electrolytics and are polarised. They must be fitted so the positive lead goes to the supply voltage and the negative lead goes to ground (or earth).
There are many different sizes, shapes and types of capacitor. They are all the same. They consist of two plates with an insulating material between. The two plates can be stacked in layers or rolled together.
The important factor is the insulating material. It must be very thin to keep things small. This gives the capacitor its VOLTAGE RATING.
If a capacitor sees a voltage higher than its rating, the voltage will "jump through" the insulating material or around it.
If this happens, a carbon deposit is left behind and the capacitor becomes "leaky" or very low resistance, as carbon is conductive.

CERAMIC CAPACITORS

Nearly all small capacitors are **ceramic capacitors** as this material is cheap and the capacitor can be made in very thin layers to produced a high capacitance for the size of the component. This is especially true for surface-mount capacitors.
All capacitors are marked with a value and the basic unit is: "p" for "puff" However NO surface mount capacitors are marked and they are very difficult to test.


104
101
331
104
474K X7R
standard ceramic capacitors
multilayer or mono-block
surface mount ceramic
high voltage dipped
air trimmer or ceramic trimmer

VALUE:	VALUE WRITTEN ON THE COMPONENT:
0.1p	0p1
0.22p	0p22
0.47p	0p47
1.0p	1p0
2.2p	2p2
4.7p	4p7
5.6p	5p6
8.2p	8p2
10p	10 or 10p
22p	22 or 22p
47p	47 or 47p
56p	56 or 56p
100p	100 on 101
220p	220 or 221
470p	470 or 471
560p	560 or 561
820p	820 or 821
1,000p (1n)	102
2200p (2n2)	222
4700p (4n7)	472
8200p (8n2)	822
10n	103
22n	223
47n	473
100n	104
220n	224
470n	474
1u	105

POLYESTER, POLYCARBONATE, POLYSTYRENE, MYLAR, METALLISED POLYESTER, ("POLY"), MICA and other types of CAPACITOR
There are many types of capacitor and they are chosen for their reliability, stability, temperate-range and cost.
For testing and repair work, they are all the same. Simply replace with exactly the same type and value.


DURACAP
171334M630BP
0.33µF 250VAC
-40°C TO 110°C
5007
wound polyester
metallised polypropylene film cap (X2)
or
metallised polyester
47n
250
metallised polyester
polyester layer
metallised polypropylene
mini box-type polyester
104J63
mylar
152K50
1/2 mm
polyester or mylar "green cap"
polystyrene
1210
1812
1206
1206
0805
0805
0603
0402
surface mount sizes

Capacitor Colour Code Table

Colour	Digit A	Digit B	Multiplier D	Tolerance (T) > 10pf	Tolerance (T) < 10pf	Temperature Coefficient (TC)
Black	0	0	x1	± 20%	± 2.0pF	
Brown	1	1	x10	± 1%	± 0.1pF	$-33x10^{-6}$
Red	2	2	x100	± 2%	± 0.25pF	$-75x10^{-6}$
Orange	3	3	x1,000	± 3%		$-150x10^{-6}$
Yellow	4	4	x10,000	± 4%		$-220x10^{-6}$
Green	5	5	x100,000	± 5%	± 0.5pF	$-330x10^{-6}$
Blue	6	6	x1,000,000			$-470x10^{-6}$
Violet	7	7				$-750x10^{-6}$
Grey	8	8	x0.01	+80%,-20%		
White	9	9	x0.1	± 10%	± 1.0pF	
Gold			x0.1	± 5%		

Silver			x0.01	± 10%		

Pico Farads (pF)	Nano Farads (nF)	Micro Farads (µF)
1	0.001	0.000001
10	0.01	0.00001
100	0.1	0.0001
1,000	1	0.001
10,000	10	0.01
100,000	100	0.1
1,000,000	1,000	1
10,000,000	10,000	10
100,000,000	100,000	100

Type ⊕ = polarized	Pic	Cap Range
Ceramic		pF - µF
Mica (silver mica)		pF - nF
Plastic Film (polyethylene polystyrene)		few µFs
Tantalum ⊕		µFs
OSCON ⊕		µFs
Aluminum Electrolytic ⊕		high µFs


value in picofarads
1st digit
2nd digit
number of zeros
tolerance
green 5%
white 10%
maximum volts
red=250v
yellow=400v


2 2 000
3 9 00
22n 5% 250v
3n9 10% 400v
10 000 p
4 7 000
1st number
2nd number
zeros
tolerance
voltage
10n
10% 400v
47nF, 10%
240V



Black	0
Brown	1
Red	2
Orange	3
Yellow	4
Green	5
Blue	6
Violet	7
Grey	8
White	9

ELECTROLYTIC and TANTALUM CAPACITORS
Electrolytics and Tantalums are the same for testing purposes but their performance is slightly different in some circuits. A tantalum is smaller for the same rating as an electrolytic and has a better ability at delivering a current. They are available up to about 1,000u, at about 50v but their cost is much higher than an electrolytic.

Electrolytics are available in 1u, 2u2 3u3 4u7 10u, 22u, 47u, 100u, 220u, 330u, 470u, 1,000u, 2,200u, 3,300u, 4,700u, 10,000u and higher.
The "voltage" or "working voltage" can be: 3.3v, 10v, 16v, 25v, 63v, 100v, 200v and higher.
There is also another important factor that is rarely covered in text books. It is RIPPLE FACTOR.
This is the amount of current that can enter and leave an electrolytic. This current heats up the electrolytic and that is why some electrolytics are much larger than others, even though the capacitance and voltage-ratings are the same.
If you replace an electrolytic with a "miniature" version, it will heat up and have a very short life. This is especially important in power supplies where current (energy) is constantly entering and exiting the electrolytic as its main purpose is to provide a smooth output from a set of diodes that delivers "pulsing DC." (see "Power Diodes")


–
+
22u
tantalum
10u
tantalum
1u
tantalum
100u
tantalum
4u7 surface mount
electrolytic
electrolytic
electrolytic
electrolytic
electrolytic

Remember:
104 = 100n
105 = 1u
106 = 10u
107 - 100u


electrolytic
called "can electrolytic"
the line is
negative !!!
+
X2 capacitor
called "mains capacitor"
surface mount electrolytic
black mark negative
surface mount capacitor
tantalum
the line is positive !!!
green cap
+
"pig tail" electro
double-ended electro
single-ended electro
+
air trimmer
"green cap"
but RED !!!
high voltage ceramic
high voltage ceramic
monolythic
capacitor
(ceramic)
"bead"
capacitor
(ceramic)

tantalum capacitors can
"go up in smoke"

"bead" tantalum

PARALLEL and SERIES CAPACITORS

Capacitors can be connected in PARALLEL and/or SERIES for a number of reasons.

1. If you do not have the exact value, two or more connected in parallel or series can produce the value you need.
2. Capacitors connected in series will produce one with a higher voltage rating.
3. Capacitors connected in parallel will produce a larger-value capacitance.

Here are examples of two equal capacitors connected in series or parallel and the results they produce:


1n 200v
total 2n 200v
1n 200v
10n 50v
10n 50v
5n 100v
47n 50v
total: 100n 50v
47n 50v
47n 200v
47n 200v
total: 23n 400v

NON-POLAR CAPACITORS (ELECTROLYTICS)

Electrolytics are also available in non-polar values. It sometimes has the letters "NP" on the component. Sometimes the leads are not identified.

This is an electrolytic that does not have a positive and negative lead but two leads and either lead can be connected to the positive or negative of the circuit.

These electrolytics are usually connected to the output of an amplifier (such as in a filter near the speaker) where the signal is rising and falling.

A non-polar electrolytic can be created from two ordinary electrolytics by connecting the negative leads together and the two positive leads become the new leads.

For example: two 100u 63v electrolytics will produce a 47u 63v non-polar electrolytic.

In the circuit below, the non-polar capacitor is replaced with two electrolytics.


NP 100µF 50v
NP 100µF 50v
Non-Polarised capacitor symbols
spkr
+
+
spkr

MAKING A NON-POLAR ELECTROLYTIC



100u
25v
non-polar

A normal electrolytic must be connected the correct way in a circuit because it has a thin insulating layer covering the plates that has a high resistance.
If you connect the electrolytic around the wrong way, this layer "breaks-down" and the resistance of the electrolytic becomes very small and a high current flows. This heats up the electrolytic and the current increases. Very soon the capacitor produces gasses and explodes.
One big mistake in many text books shows how to make a non-polar electrolytic by connecting two "back-to-back."
They claim 2 x 100u connected back-to-back is equal to 47u.
This appears to be case when testing on a meter but the meter simply charges them for a short period of time to get a reading.
If you allow them to charge fully you will find the reverse electrolytic has a very small voltage across it.
Secondly, when you are charging them, you are putting a high current through the reverse electrolytic and damaging the layer.
To prevent this, you need to add two diodes as shown in the diagram.
In addition, 2 x 100u "back-to-back" is very near 100u.

Here is a question from a reader:
I have an amplifier with 2 x2,200u electrolytics on the output of a bridge. Can I replace them with a single 10,000u?



You need to look at the circuit of your amplifier. The two 2,200u electrolytics are possibly connected as shown in the circuit above and you will notice they are joined to produce a positive rail and a negative rail with zero (called earth) in the centre.
This forms two different circuits with the top electrolytic filtering the positive rail and the bottom electro filtering the negative rail. They must be connected to the zero volts rail.
A single 10,000u cannot be connected to the 0v rail and cannot be substituted for the two electro's.
You can easily determine of the two electro's are connected as shown above.
Test the positive terminal of each electro by placing the negative of the meter on the chassis.
If the positive of one electro have zero volts, it will be the lower electro in the diagram above. The negative terminal of the electro will have a minus voltage on it.

VOLTAGE RATING OF CAPACITOR
Capacitors have a voltage rating, stated as WV for working voltage, or WVDC. This specifies the maximum voltage that can be applied across the capacitor without puncturing the dielectric. Voltage ratings for "poly," mica and ceramic capacitors are typically 50v to 500 VDC. Ceramic capacitors with ratings of 1kv to 5kv are also available. Electrolytic capacitors are commonly available in 6v, 10v 16v, 25v, 50v, 100v, 150v, and 450v ratings.

THE SIZE OF A CAPACITOR - RIPPLE FACTOR

The size of a capacitor depends on a number of factors, namely the value of the capacitor (in microfarads etc) and the voltage rating. But there is also another factor that is most important. It is the RIPPLE FACTOR. **Ripple Factor** is the amount of voltage-fluctuation the capacitor (electrolytic) can withstand without getting too hot. When current flows in and out of an electrolytic, it gets hot and this will eventually dry-out the capacitor as some of the liquid inside the capacitor escapes through the seal. It's a very slow process but over a period of years, the capacitor looses its capacitance.

If you have two identical 1,000u 35v electrolytics and one is smaller, it will get hotter when operating in a circuit and that's why it is necessary to choose the largest electrolytic.

CAUTION

If a capacitor has a voltage rating of 63v, do not put it in a 100v circuit as the insulation (called the dielectric) will be punctured and the capacitor will "short-circuit." It's ok to replace a 0.22uF 50WV capacitor with 0.22uF 250WVDC.

SAFETY

A capacitor can store a charge for a period of time after the equipment is turned off. High voltage electrolytic caps can pose a safety hazard. These capacitors are in power supplies and some have a resistor across them, called a bleed resistor, to discharge the cap after power is switched off.

If a bleed resistor is not present the cap can retain a charge after the equipment is unplugged.

How to discharge a capacitor

Do not use a screwdriver to short between the terminals as this will damage the capacitor internally and the screwdriver.

Use a 1k 1 watt or 3watt or 5watt resistor on jumper leads (or held with pliers) and keep them connected for up to 15 seconds to fully discharge the electro.

Test it with a voltmeter to make sure all the energy has been removed.

Before testing any capacitors, especially electrolytics, you should look to see if any are damaged, overheated or leaking. Swelling at the top of an electrolytic indicates heating (and pressure inside the case) and will result in drying out of the electrolyte. Any hot or warm electrolytic indicates leakage and ceramic capacitors with portions missing indicates something has gone wrong (such as it being "blown apart").



Here is a 120u 330v electrolytic from a flash circuit in an old-fashioned film camera. If the flash does not "fire," the electrolytic will be charged to about 350 volts !!

Use a 1k resistor (held with pliers) to slowly discharge it. It may take 15 seconds to fully discharge.

TESTING A CAPACITOR
There are two things you can test with a multimeter:
1. A short-circuit within the capacitor
2. Capacitor values above 1u.

You can test capacitors in-circuit for short-circuits. Use the x1 ohms range.
To test a capacitor for leakage, you need to remove it or at least one lead must be removed. Use the x10k range on an analogue or digital multimeter.
For values above 1u you can determine if the capacitor is charging by using an analogue meter. The needle will initially move across the scale to indicate the cap is charging, then go to "no deflection." Any permanent deflection of the needle will indicate leakage.
You can reverse the probes to see if the needle moves in the opposite direction. This indicates it has been charged. Values below 1u will not respond to charging and the needle will not deflect.
This does not work with a digital meter as the resistance range does not output any current and the electrolytic does not charge.

Rather than spending money on a capacitance meter, it is cheaper to replace any suspect capacitor or electrolytic.
Capacitors can produce very unusual faults and no piece of test equipment is going to detect the problem.
In most cases, it is a simple matter to solder another capacitor across the suspect component and view or listen to the result.
This saves all the worry of removing the component and testing it with equipment that cannot possibly give you an accurate reading when the full voltage and current is not present.
It is complete madness to even think of testing critical components such as capacitors, with TEST EQUIPMENT. You are fooling yourself. If the Test Equipment says the component is ok, you will look somewhere else and waste a lot of time.

FINDING THE VALUE OF A CAPACITOR

If you want to find the value of a surface-mount capacitor or one where the markings have been removed, you will need a CAPACITANCE METER. Here is a simple circuit that can be added to your meter to read capacitor values from 10p to 10u.
The full article can be found HERE.



ADD-ON CAPACITANCE METER

CAPACITOR SUBSTITUTION BOX

CAPACITANCE SUBSTITUTION BOX
470
560
680
820
330
220
150
100
3300
2200
1500
1000
pF
µF
.01
.015
.022
.033
.0082
.0068
.047
.056
.0056
.0047
.1
.068
ELENCO® MODEL CS-440

You can get a kit or a ready-made piece of test gear called **CAPACITOR SUBSTITUTION BOX** and also **RESISTOR SUBSTITUTION BOX**.
I bought one of each 30 years ago and I have only used them ONCE.
They appear to be very handy but when you are testing a circuit, you want the component next to the other parts.
It is just as easy to pick the component you need from your junk box and connect it to the circuit via jumper leads.

REPLACING A CAPACITOR

Always replace a capacitor with the exact same type.
A capacitor may be slightly important in a circuit or it might be extremely critical.
A manufacturer may have taken years to select the right type of capacitor due to previous failures.
A capacitor just doesn't have a "value of capacitance."
It may also has an effect called "tightening of the rails."
In other words, a capacitor has the ability to react quickly and either absorb or deliver energy to prevent spikes or fluctuations on the rail.
This is due to the way it is constructed. Some capacitors are simply plates of metal film while others are wound in a coil. Some capacitors are large while others are small.
They all react differently when the voltage fluctuates.
Not only this, but some capacitors are very stable and all these features go into the decision for the type of capacitor to use.
You can completely destroy the operation of a circuit by selecting the wrong type of capacitor.
No capacitor is perfect and when it gets charged or discharged, it appears to have a small value of resistance in series with the value of capacitance. This is known as "ESR" and stands for EQUIVALENT SERIES RESISTANCE. This effectively makes the capacitor slightly slower to charge and discharge.
We cannot go into the theory on selecting a capacitor as it would be larger than this eBook so the only solution is to replace a capacitor with an identical type.
However if you get more than one repair with identical faults, you should ask other technicians if the original capacitor comes from a faulty batch.
The author has fixed TV's and fax machines where the capacitors have been inferior and alternate types have solved the problem.
Some capacitor are suitable for high frequencies, others for low frequencies.

DECOUPLING CAPACITORS

A Decoupling Capacitor can severe one, two or three functions. You need to think of a decoupling capacitor as a miniature battery with the ability to deliver a brief pulse of energy when ever the line-voltage drops and also absorb a brief pulse of energy when ever the line voltage rises (or spikes).
Decoupling capacitor can range from 100n to 1,000u.
100n capacitors are designed to absorb spikes and also have the effect of tightening-

up the rails for high frequencies. They have no effect on low frequencies such as audio frequencies.

These capacitors are generally ceramic and have very low internal impedance and thus they can operate at high frequencies.

Capacitors above about 10u are used for decoupling and these are nearly always electrolytics.

Decoupling means "tightening-up the power rails." The electrolytic acts just like a miniature rechargeable battery, supplying a small number of components in a circuit with a smooth and stable voltage.

The electrolytic is usually fed from a dropper resistor and this resistor charges the electrolytic and adds to the ability of the electrolytic to create a "separate power supply."

These two components help remove spikes as an electrolytic cannot remove spikes if connected directly to the supply rails - it's internal impedance is high and the spikes are not absorbed.

Decoupling capacitors are very difficult to test.

They rarely fail but if a project is suffering from unknown glitches and spikes, it is best to simply add more 100n decoupling caps on the underside of the board and replace all electrolytics.

Some small electrolytics will dry out due to faulty manufacture and simply replacing every one on a board will solve the problem.

Some of the functions of a decoupling capacitor are:

Removing ripple - hum or buzz in the background of an amplifier

Removing glitches or spikes.

Separating one stage from another to reduce or remove MOTORBOATING - a low frequency sound due to the output putting a pulse on the power rails that is picked up by the pre-amplifier section and amplified.

TESTING DIODES

Diodes can have 4 different faults.

1. Open circuit in both directions.
2. Low resistance in both directions.
3. Leaky.
4. Breakdown under load.

TESTING A DIODE ON AN ANALOGUE METER

Testing a diode with an **Analogue Multimeter** can be done on any of the resistance ranges. [The high resistance range is best - it sometimes has a high voltage battery for this range but this does not affect our testing]

There are two things you must remember.

1. When the diode is measured in one direction, the needle will **not move at all**. The technical term for this is the diode is **reverse biased**. It will not allow any current to flow. Thus the needle will not move.

When the diode is connected around the other way, the needle will swing to the right (move up scale) to about 80% of the scale. This position represents the voltage drop across the junction of the diode and is NOT a resistance value. If you change the resistance range, the needle will move to a slightly different position due to the resistances inside the meter. The technical term for this is the diode is **forward biased**. This indicates the diode is not faulty.

The needle will swing to a slightly different position for a "normal diode" compared to a Schottky diode. This is due to the different junction voltage drops.

However we are only testing the diode at very low voltage and it may break-down when fitted to a circuit due to a higher voltage being present or due to a high current flowing.

2. The leads of an **Analogue Multimeter** have the positive of the battery connected to the black probe and the readings of a "good diode" are shown in the following two diagrams:



The diode is REVERSE BIASED in the diagram above and diodes not conduct.



The diode is FORWARD BIASED in the diagram above and it conducts

TESTING A DIODE ON A DIGITAL METER

Testing a diode with a Digital Meter must be done on the "DIODE" setting as a digital meter does not deliver a current through the probes on some of the resistance settings and will not produce an accurate reading.



The best thing to do with a "suspect" diode is to replace it. This is because a diode has a number of characteristics that cannot be tested with simple equipment. Some diodes have a fast recovery for use in high frequency circuits. They conduct very quickly and turn off very quickly so the waveform is processed accurately and

efficiently.
If the diode is replaced with an ordinary diode, it will heat up as does not have the high-speed characteristic.
Other diodes have a low drop across them and if an ordinary is used, it will heat up.
Most diodes fail by going: SHORT-CIRCUIT. This can be detected by a low resistance (x1 or x10 Ohms range) in both directions.
A diode can also go OPEN CIRCUIT. To locate this fault, place an identical diode across the diode being tested.
A leaky diode can be detected by a low reading in one direction and a slight reading the other direction.
However this type of fault can only be detected when the circuit is working. The output of the circuit will be low and sometimes the diode heats up (more than normal).
A diode can go open under full load conditions and perform intermittently.
Diodes come in pairs in surface-mount packages and 4 diodes can be found in a bridge.
They are also available in pairs that look like a 3-leaded transistor.
The line on the end of the body of a diode indicates the cathode and you cannot say "this is the positive lead." The correct way to describe the leads is to say the "cathode lead." The other lead is the anode. The cathode is defined as the electrode (or lead) through which an electric current flows out of a device.
The following diagrams show different types of diodes:


7812
power
diode
1N4004
Plug Pack
500mA DC
in
out
10 ohm
10 ohm
0.5watt
0.5watt
common
1N4004
1N4004
1N4004
12v - 18v
DC
12v
+
damper
diode
+12V
RL1
BC338
damper
diode
power
diode
active
240v AC
neutral
15v
+
active
240v AC
neutral
15v
15v
power
diode
+
power
diode
active
240v AC
neutral
1N4148
68k
+
100u
signal
diode
1N4148
47k

POWER DIODES

To understand how a power diode works, we need to describe a few things. This has NEVER been described before, so read carefully.
The 240v AC (called the "mains") consists of two wires, one is called the ACTIVE and the other is NEUTRAL. Suppose you touch both wires. You will get a shock. The neutral is connected to an earth wire (or rod driven into the ground or connected to a water pipe) at the point where the electricity enters the premises and you do not get a shock from the NEUTRAL.

But the voltage on the active is rising to +345v then goes to -345v at the rate of 50 times per second (for a complete cycle).
345v is the peak voltage of 240v. You never get a 240v shock. (It is a 345v shock.) In other words, if you touch the two wires at a particular instant, you would get a POSITIVE 345v shock and at another instant you would get a negative 345v shock. This is shown in the diagram below.
We now transfer this concept to the output of a transformer. The diagram shows an AC waveform on the output of the secondary.
This voltage is rising 15v higher than the bottom lead then it is 15v LOWER than the bottom lead. The bottom lead is called "zero volts." You have to say one lead or wire is not "rising and falling" as you need a "reference" or starting-point" or "zero point" for voltage measurements.
The diode only conducts when the voltage is "above zero" (actually when it is 0.7v above zero) and does not conduct (at all) when the voltage goes below zero.
This is shown on the output of the Power Diode. Only the positive peaks or the positive parts of the waveform appear on the output and this is called "pulsing DC." This is called "half-wave" and is not used in a power supply. We have used it to describe how the diode works. The electrolytics charge during the peaks and deliver energy when the diode is not delivering current. This is how the output becomes a steady DC voltage.
Power supplies use FULL WAVE rectification and the other half of the AC waveform is delivered to the output (and fills in the "gaps") and appears as shown in "A."





Half-wave rectifier



Full-wave rectifier

ONE FAULTY DIODE

One diode in a bridge can go open (any of the 4 diodes will produce the same effect) and produce an output voltage that can be slightly lower than the original voltage.

The actual "voltage-drop" will depend on the current taken by the circuit and the ability of the transformer to produce the required voltage and current during half-wave operation. The voltage during each half cycle (when none of the diodes is delivering any energy to the circuit) is maintained by the electrolytic and its size (relative to the current taken by the circuit) will determine the size of the ripple that will result when the diode fails. The ripple will be 100 to 1,000 times greater after the failure of a diode, depending on the value of the filter capacitor.

To locate the faulty diode, simply get a diode and place it across each of the diodes in the bridge (in turn) when the circuit is working.

For a bridge rectifier, the ripple-frequency will be twice the mains frequency and its ripple will be very small if the electrolytic is the correct value. When a diode fails, the ripple-frequency will be equal to mains-frequency and the amplitude will increase considerably. You may even hear background hum from audio equipment.

If you cannot find a faulty diode, the filter capacitor will be at fault. Turn off the equipment and connect an electrolytic across the filter capacitor via jumper leads. Turn the power ON and see if the hum has reduced.



One diode "burnt-out"

DAMPER DIODES

A damper diode is a diode that detects a high voltage and SQUELCHES IT (reduces it - removes it). The signal that it squelches is a voltage that is in the opposite direction to the "supply voltage" and is produced by the collapsing of a magnetic field. Whenever a magnetic filed collapses, it produces a voltage in the winding that is opposite to the supply voltage and can be much higher. This is the principle of a flyback circuit or EHT circuit. The high voltage comes from the transformer.

The diode is placed so that the signal passes through it and less than 0.5v appears across it.

A damper diode can be placed across the coil of a relay, incorporated into a transistor or FET or placed across a winding of a flyback transformer to protect the driving transistor or FET.

It can also be called a "Reverse-Voltage Protection Diode," "Spike Suppression Diode," or "Voltage Clamp Diode."

The main characteristic of a Damper Diode is HIGH SPEED so it can detect the spike and absorb the energy.

It does not have to be a high-voltage diode as the high voltage in the circuit is being absorbed by the diode.

SILICON, GERMANIUM AND SCHOTTKY DIODES

When testing a diode with an analogue meter, you will get a low reading in one direction and a high (or NO READING) in the other direction. When reading in the LOW direction, the needle will swing nearly full scale and the reading is not a resistance-value but a reflection of the characteristic voltage drop across the junction of the diode. As we mentioned before, a resistance reading is really a voltage reading and the meter is measuring the voltage of the battery minus the voltage-drop across the diode.

Since Silicon, Germanium and Schottky Diodes have slightly different characteristic voltage drops across the junction, you will get a slightly different reading on the scale. This does not represent one diode being better than the other or capable of handling a higher current or any other feature.

The quickest, easiest and cheapest way to find, fix and solve a problem caused by a

faulty diode is to replace it.
There is no piece of test equipment capable of testing a diode fully, and the circuit you are working on is actually the best piece of test equipment as it is identifying the fault UNDER LOAD.

Only very simple tests can be done with a multimeter and it is best to check a diode with an ANALOGUE MULTIMETER as it outputs a higher current though the diode and produces a more-reliable result.
A Digital meter can produce false readings as it does not apply enough current to activate the junction.
Fortunately almost every digital multimeter has a **diode test mode.** Using this, a silicon diode should read a voltage drop between 0.5v to 0.8v in the forward direction and open in the reverse direction. For a germanium diode, the reading will be lower, around 0.2v - 0.4v in the forward direction. A bad diode will read zero volts in both directions.

REPLACING A DIODE

It is alway best to replace a diode with the same type but quite often this is not possible. Many diodes have unusual markings or colours or "in-house" letters.
This is only a general guide because many diodes have special features, especially when used in high-frequency circuits.
However if you are desperate to get a piece of equipment working, here are the steps:
Determine if the diode is a signal diode, power diode, or zener diode.
For a signal diode, try 1N4148.
For a power diode (1 amp) try 1N4004. (for up to 400v)
For a power diode (3 amp) try 1N5404. (for up to 400v)
For a high-speed diode, try UF4004 (for up to 400v)

If you put an ordinary diode in a high-speed application, it will get very hot very quickly.
To replace an unknown zener diode, start with a low voltage such as 6v2 and see if the circuit works.
The size of a diode and the thickness of the leads will give an idea of the current-capability of the diode.
Keep the leads short as the PC board acts as a heat-sink.
You can also add fins to the leads to keep the diode cool.

LIGHT EMITTING DIODES (LEDs)

Light Emitting Diodes (LEDs) are diodes that produce light when current flows from anode to cathode. The LED does not emit light when it is revered-biased. It is used as a low current indicator in many types of consumer and industrial equipment, such as monitors, TV’s, printers, hi-fi systems, machinery and control panels.
The light produced by a LED can be visible, such as red, green, yellow or white. It can also be invisible and these LEDs are called Infrared LEDs. They are used in remote controls and to see if they are working, you need to point a digital camera at the LED and view the picture on the camera screen.
An LED needs about 2v - 3.6v across its leads to make it emit light, but this voltage must be exact for the type and colour of the LED. The simplest way to deliver the exact voltage is to have a supply that is higher than needed and include a voltage-dropping resistor. The value of the resistor must be selected so the current is between 2mA and 25mA.
The cathode of the LED is identified by a flat on the side of the LED. The life expectancy of a LED is about 100,000 hours. LEDs rarely fail but they are very sensitive to heat and they must be soldered and de-soldered quickly. They are one of the most heat-sensitive components.
Light emitting diodes cannot be tested with most multimeters because the characteristic voltage across them is higher than the voltage of the battery in the meter.
However a simple tester can be made by joining 3 cells together with a 220R resistor

and 2 alligator clips:





LED TESTER

Connect the clips to a LED and it will illuminate in only one direction.
The colour of the LED will determine the voltage across it. You can measure this voltage if you want to match two or more LEDs for identical operation.
Red LEDs are generally 1.7v to 1.9v. - depending on the quality such as "high-bright"
Green LEDs are 1.9v to 2.3v.
Orange LEDs are about 2.3v and
White LEDs and IR LEDs are about 3.3v to 3.6v.
The illumination produced by a LED is determined by the quality of the crystal. It is the crystal that produces the colour and you need to replace a LED with the same quality to achieve the same illumination.
Never connect a LED across a battery (such as 6v or 9v), as it will be instantly damaged. You must have a resistor in series with the LED to limit the current.

ZENER DIODES

All diodes are Zener diodes. For instance a 1N4148 is a 120v zener diode as this is its reverse breakdown voltage.
And a zener diode can be used as an ordinary diode in a circuit with a voltage that is below the zener value.
For instance, 20v zener diodes can be used in a 12v power supply as the voltage never reaches 20v, and the zener characteristic is never reached.
Most diodes have a reverse breakdown voltage above 100v, while most zeners are below 70v. A 24v zener can be created by using two 12v zeners in series and a normal diode has a characteristic voltage of 0.7v. This can be used to increase the voltage of a zener diode by 0.7v. See the diagram above. It uses 3 ordinary diodes to increase the output voltage of a 3-terminal regulator by 2.1v.
To tests a zener diode you need a power supply about 10v higher than the zener of the diode. Connect the zener across the supply with a 1k to 4k7 resistor and measure the voltage across the diode. If it measures less than 1v, reverse the zener. If the reading is high or low in both directions, the zener is damaged.

Here is a zener diode tester. The circuit will test up to 56v zeners.



ZENER DIODE TESTER

TRANSFORMERLESS POWER SUPPLY

Here's a circuit that uses zener diodes in a power supply to show how they work. This clever design uses 4 diodes in a bridge to produce a fixed voltage power supply capable of supplying 35mA.

If we put 2 zener diodes in a bridge with two ordinary power diodes, the bridge will break-down at the voltage of the zener. This is what we have done. If we use 18v zeners, the output will be 17v4.



SUPPLY USING ZENER DIODES

When the incoming voltage is positive at the top, the left zener provides 18v limit (and the other zener produces a drop of 0.6v). This allows the right zener to pass current just like a normal diode. The output is 17v4. The same with the other half-cycle.

You cannot use this type of bridge in a normal power supply as the zener diode will "short" when the input voltage reaches the zener value. The concept only works in the circuit above.

VOLTAGE REGULATORS

A Voltage Regulator takes a high input voltage and delivers a fixed output voltage. Providing the input voltage is 4v above the output voltage, the regulator will deliver a fixed output voltage with almost no ripple.

Voltage regulators are also called "3-TERMINAL REGULATORS" or "REGULATOR IC's" - although this name is not generally used.

In most cases, a voltage regulator gets quite hot and for this reason it has a high failure-rate.

If a regulator is not getting hot (or warm) it has either failed or the circuit is not operating.

A regulator can only decrease the voltage. It cannot increase the current. This means the current being supplied to a circuit must also be available from the circuit supplying the regulator.

All regulators have different pin-outs, so you need to find the input pin and output pin and make sure the voltage-difference is at least 4v. Some regulators will work with a difference as low as 1v, so you need to read the specifications for the type you are servicing.

Some regulators are called "negative voltage regulators" and the input voltage will be negative and the output will be negative.

You need to test a voltage regulator with the power "ON".

Make sure you do not allow the probes to short any of the pins together as this will destroy the regulator or the circuit being supplied.

With the power turned off or the regulator removed from the circuit, you can test it with a multimeter set to resistance to see if it is ok. If any resistance readings are very low or zero ohms, the regulator is damaged.

TRANSFORMERS

All transformers and coils are tested the same way. This includes chokes, coils,

inductors, yokes, power transformers, EHT transformers (flyback transformers), switch mode transformers, isolation transformers, IF transformers, baluns, and any device that has turns of wire around a former. All these devices can go faulty.
The coating on the wire is called insulation or "enamel" and this can crack or become overheated or damaged due to vibration or movement. When two turns touch each other, a very interesting thing happens. **The winding becomes two separate windings.**







We will take the case of a single winding such as a coil. This is shown in the first diagram above and the winding is wound across a former (a former is a bobbin or plastic molding or something to hold the winding) and back again, making two layers. The bottom and top layers touch at the point shown in the diagram and the current that originally passed though A, B, C, D now passes though A & D.

Winding B C becomes a separate winding as shown in the second diagram.
In other words the coil becomes a TRANSFORMER with a SHORT CIRCUIT on the secondary winding as shown in the third diagram.
When the output wires of a transformer are shorted together, it delivers a very high current because you have created a SHORT-CIRCUIT. This short-circuit causes the transformer to get very hot.
That's exactly what happens when any coil or transformer gets a "shorted turn."
The shorted turns can be a single turn or many turns.
It is not possible to measure a fault like this with a multimeter as you don't know the exact resistance of a working coil or winding and the resistance of a faulty winding may be only 0.001 ohms less.
However when a transformer or coil is measured with an inductance meter, an oscillating voltage (or spike) is delivered into the core as magnetic flux, then the magnetic flux collapses and passes the energy into the winding to produce a waveform. The inductance meter reads this and produces a value of inductance in Henry (or milliHenry or microHenry.)
This is done with the transformer removed from the circuit and this can be a very difficult thing to do, as most transformers have a number of connections.
If the coil or transformer has a shorted turn, the energy from the magnetic flux will pass into the turns that are shorted and produce a current. Almost no voltage will be detected from winding.
The reading from the inductance meter will be low or very low and you have to work out if it is correct.
However there is one major problem with measuring a faulty transformer or coil.
It may only become faulty when power is applied.
The voltage between the turns may be sparking or jumping a gap and creating a problem. A tester is not going to find this fault.
Secondly, an inductance meter may produce a reading but you do not know if the reading is correct. An improved tester is a RING TESTER.
The circuit for a ring tester can be found here:

http://www.flippers.com/pdfs/k7205.pdf

It sends a pulse to the coil and counts the number of returning pulses or "rings." A faulty coil (or winding) may return one pulse but nearly all the energy will be passed to the shorted turns and you will be able to see this on the scale. You will only get one or two return pulses, whereas a good winding will return more pulses.

One way to detect a faulty power transformer is to connect it to the supply and feel the temperature-rise (when nothing is connected to the secondary).
It should NOT get hot.
Detecting shorted turns is not easy to diagnose as you really need another identical

component to compare the results.
Most transformers get very hot when a shorted turn has developed. It may deliver a voltage but the heat generated and a smell from the transformer will indicate a fault.

ISOLATION TRANSFORMER

An isolation transformer is a piece of **Test Equipment** that provides "Mains Voltage" but the voltage is "floating." You will still get a shock if you touch the two output leads, but it has a special use when testing unknown equipment.
Many electrical appliances are fully insulated and only have two leads connected to the mains.
When you take these appliances apart, you do not know which end of say a heating element is connected to the "live" (active) side of the mains and which end connects to the neutral.
I am not suggesting you carry out the following tests, but they are described to show how an isolation transformer works.
If you touch a soldering iron on the "live" (active) end of the heating element it will create a short-circuit.
However when the appliance is connected to the mains via an **isolation transformer**, you can touch an earthed soldering iron on either end of the heater as both leads from the isolation transformer are "floating."
Note: As soon as you earth one lead of the output an isolation transformer, the other lead becomes "active."
You can make your own **Isolation Transformer** by connecting two identical transformers "back-to-back."
The following diagram shows how this is done:





You can use any transformers providing the primary and secondary voltages are the same. The current capability of the secondary winding does not matter. However if you want a supply that has almost the same voltage as your "Mains," you need two transformers with the same voltages.
This handy isolation transformer will provide you with "Mains Voltage" but with a limited current.
In other words it will have a limited capability to supply "wattage." If you are using two 15VA transformers, you will only be able to test an appliance rated at 15 watts.
This has some advantages and some disadvantages.
If you are working on a project, and a short-circuit occurs, the damage will be limited to 15 watts.
If you are using two transformers with different VA ratings, the lower rating will be the capability of the combination.
If the secondaries are not equal, you will get a higher or lower "Mains Voltage."
If you get two transformers from TVs or Monitors, with a rating on the compliance plate of 45 watts, or 90 watts, you can assume the transformers are capable of delivering this wattage and making an isolation transformer will enable you to test

similar items with the safety of being isolated from the mains.
Colin Mitchell designs a lot of "LED lighting lamps" that are connected directly to the mains. He always works with an isolating transformer, just to be safe. Working on exposed "mains" devices is extremely nerve-wracking and you have to be very careful.
The isolation transformer will prevent a BIG EXPLOSION.

DETERMINING THE SPECS OF A TRANSFORMER

Suppose you have a "mains transformer" with unknown output voltages and unknown current capability.
You must be sure it is a mains transformer designed for operation on 50Hz or 60Hz. Switch-Mode transformers operate at frequencies 40kHz and higher and are not covered in this discussion.
To be on the safe-side, connect the unknown transformer to the output of your isolating transformer.
Since the transformer will take almost no current when not loaded, the output voltages it produces will be fairly accurate. Measure the input AC voltage and output AC voltage.
If the transformer has loaded your isolating transformer it will be faulty.
Mains transformers are approx 15VA for 500gm, 30VA for 1kgm 50VA for 2kgm and and 100VA for 2.5kgm.
VA stands for Volts-Amps and is similar to saying watts. Watts is used for DC circuits, while VA refers to AC circuits.
Once you have the weight of the transformer and the output voltage, you can work out the current capability of the secondary.
For transformers up to 30vA, the output voltage on no-load is 30% higher than the final "loaded voltage."
This is due to the poor regulation of these small devices.
If the transformer is 15VA and the output voltage is 15v AC, the current will be 1 amp AC.
You can check the "quality" of the transformer, (the regulation) by fully loading the output and measuring the final voltage. If the transformer has a number of secondaries, the VA rating must be divided between all the windings.

240v to 110v ISOLATION TRANSFORMER

Here's how to create a 110v isolating transformer:
Find a 240v:12v transformer.
Now find a transformer that has two secondary windings, such as 240v:12v+12v.



Connect the two transformers as shown in the circuit above. If the output is zero, connect ONE of the 12v windings of the second transformer around the other way.

110v to 240v ISOLATION TRANSFORMER



A 110v to 240v isolation transformer can be created by connecting 3 identical transformers as shown in the diagram above. If the output is zero, connect one of the outputs around the other way.

TRANSFORMER RATINGS

Question from a reader:
I have a 28v - 0 - 28v transformer @3amps. Does this mean each side is 1.5 amps?
The transformer is called CENTRE TAPPED and is shown in figures B and C.
It is designed to be connected to two diodes so each winding takes it in turn to deliver the current as shown in diagram C and the output will be 28v AC at 3 amps.
The 28v and 3 amp are both AC values.
If you connect across both outside wires, the output will be 56v at 1.5 amp.
This is because the transformer has a VA rating of 28 x 3 = 84VA. This is very similar to the term "watts."
When the 28v AC is rectified and smoothed, it becomes 28 x 1.4 = 39v (minus 0.6v across the diode) and since the transformer has a rating of 84 VA, the current must be reduced to 84/39 = 2.1 amps to maintain the VA rating.
Some transformers are specified as say: 12v - 0 - 12v, but the wiring diagram is shown as "A." This transformer should be specified as 12v + 12v as the secondaries are separate.
12v - 0 - 12v means the two secondary windings are NOT separate.
It does not make any difference to the output voltage and current, if the windings are separate or joined. The only difference is 12v +12v can be turned into two separate 12v outputs.
If you do not know the output current for a particular transformer, go to the website of electronic parts suppliers and compare the weight of your transformer with others. This will give you a VA rating and you can work out the current, once you know the output voltage.
Note: the output current finishes up ONLY 60% of the rating on the transformer tag because the rating is an **AC RATING**.
With 2 separate secondaries, you can parallel the outputs to get double the current, but don't forget 12v + 12v @ 3amp means 12v in parallel with 12v will provide 2amp DC and the DC voltage will be about 17v.







CURRENT TRANSFORMER

A Current Transformer is really an ordinary transformer.
All transformers produce a CURRENT output and a VOLTAGE output.
If you put an ammeter across the secondary, the current will increase through the meter when the primary voltage is increased.
This is because the output voltage will increase and this voltage will allow a higher current to flow.

WHY DETECT CURRENT? Why not voltage?

Because the voltage of say the "240v AC" is always 240v but the current can increase from say 1 amp to nearly 15 amps, depending what appliance is connected. So it is pointless measuring voltage.
A Current Transformer is a step-up transformer. When we say step-up and step-down, we are referring to the voltage - comparing the primary voltage to the secondary voltage. (Most transformers on the "mains" are step-down transformers and are used as power supplies to laptops, phone chargers etc.) Even a welding transformer is a step-down device and produces about 20v to 70v, while the current can be as high as 100 amps. This current is higher than the mains will deliver and is needed to melt the metal at the point of contact of the probe and the item being welded.
A Current Transformer is a step-up transformer. The primary consists of a single turn (or maybe 2 - 5 turns) and the secondary has 100 turns (or more).
This means the voltage seen by the primary will be increased 100 times and appear as anything from a few hundred millivolts to a few volts, depending on the quality of the coupling. (the magnetic coupling between the wire through the centre of the core, the quality of the core to transfer this magnetic flux to the secondary turns.)
This voltage is then passed to a low value resistor, where the voltage is reduced to a level that suits the detection circuit and the resulting millivolts is interpreted as current in the wire being tested.

Recapping:

The reading on the secondary has no relation to the current in the primary. We need to add a LOAD RESISTOR and create a table before we can use the transformer.
There is no such thing as a CURRENT TRANSFORMER. It is really an INSTRUMENT TRANSFORMER and the scale has been marked in units of CURRENT after measurements have been made. (INSTRUMENT TRANSFORMER means it is a device that helps us to produce a connection between current flowing through a wire and a reading on a meter or display).
If we connect a load to the secondary, (say an ammeter), it will produce a reading that increases when the current through the single primary turn is increased. That's because the ammeter is a LOAD. But the reading is meaningless until be calibrate the scale.

Now, lets look at the primary.
A wire (or cable) through the centre of the core is counted as one turn. If the turn is wrapped around the core, the coupling will be improved, but if we always use a straight wire, it does not matter where it is positioned inside the centre of the core.
It does not matter if the magnetic interaction of the flux from the wire is good or bad, we just have to keep to the same way of using the transformer.
The calibration can be done with any poor coupling and the result will be accurate for all future readings.
If a low-value resistor is placed across the secondary, the voltage across this resistor will increase and also the current through it will increase. But we are not going to measure the current through the resistor. We are going to measure the voltage across the resistor and by taking lots of reading we will finish up with a scale or table and this is called CALIBRATION. The results will be equated to the current flowing through the primary wire (primary turn).
A clamp meter uses a current transformer and the jaws must be closed completely and cleanly for the flux to flow around the core and produce a reading in the secondary.
Dirt in the jaws will reduce the reading considerably.
You cannot measure the current in a "power cord" because it contains both the active and neutral wires.
Even though the current is a maximum in both conductors at the same time, the current is flowing in two different directions and the magnetic flux produced by one conductor is clockwise and the other is anticlockwise and they are cancelled by each other.


1 turn
2 turns
1 turn
A
1 turn
V
1 turn
FLUKE 373
600.0
30.00

Identifying ONE TURN.
The quality (the coupling) of a single STRAIGHT wire

through the centre of a core is very poor
but if all readings are taken with this amount
of coupling, the readings will be accurate, as the
calibrations have been done with this arrangement.

OPTO ISOLATORS and OPTO COUPLERS

Opto Isolators and Opto Couplers are the same thing. A common opto-coupler is 4N35. It is used to allow two circuits to exchange signals yet remain electrically isolated. The signal is applied to the LED, which shines on a silicon NPN photo-transistor in the IC.
The light is proportional to the signal, so the signal is transferred to the photo transistor to turn it on a proportional amount. Opto-couplers can have Light Activated SCR's, photodiodes, TRIAC's and other semiconductor devices as an output. The 4N35 opto-coupler schematic is shown below:





An opto-Coupler using a TRIAC
Note: the pinout is different to 4N35

TESTING AN OPTO COUPLER

Most multimeters cannot test the LED on the input of an opto-coupler because the ohms range does not have a voltage high enough to activate the LED with at least 2mA.
You need to set-up the test-circuit shown above with a 1k resistor on the input and 1k5 on the output. When the 1k is connected to 12v, the output LED will illuminate. The opto-coupler should be removed from circuit to perform this test.

TRANSISTORS

Transistors are solid-state devices and although they operate completely differently to a diode, they appear as two back-to-back diodes when tested.
There are basically 2 types of transistor NPN and PNP.
A transistor is sometimes referred to as BJT (Bi-polar Junction Transistor) to distinguish it from other types of transistor such as Field Effect transistor, Programmable Unijunction Transistor and others.

In the following diagram, two diodes are connected together and although the construction of a transistor is more complex, we see the transistor as two diodes when testing it.



A TRANSISTOR APPEARS AS TWO DIODES WHEN TESTING IT

All transistors have three leads. Base (b), Collector (c), and Emitter (e).
For an NPN transistor, the arrow on the emitter points away from the base.
It is fortunate that the arrow on both symbols points in the direction of the flow of current (Conventional Current) and this makes it easy to describe testing methods using our simplified set of instructions. The symbols have been drawn exactly as they appear on a circuit diagram.

All transistors **are the same** but we talk about digital and analogue transistors.
There is no difference between the two.
The difference is the circuit. And the only other slight difference between transistors is the fact that some have inbuilt diodes and resistors to simplify the rest of the circuit.
All transistors work the same way. The only difference is the amount of amplification they provide, the current and voltage they can withstand and the speed at which they work. For simple testing purposes, they are all the same.

NPN transistors are the most common and for an NPN transistor, the following applies.
(the opposite applies for PNP)
To test a transistor, there is **one thing** you have to know:
When the base voltage is higher than the emitter, current flows though the collector-emitter leads.
As the voltage is increased on the base, nothing happens until the voltage reaches 0.55v. At this point a very small current flows through the collector-emitter leads. As the voltage is increased, the current-flow increases. At about 0.75v, the current-flow is a MAXIMUM. (can be as high as 0.9v). That's how it works. A transistor also needs **current** to flow into the base to perform this amplifying function and this is the one feature that separates an ordinary transistor from a FET.

If the voltage on the base is 0v, then instantly goes to 0.75v, the transistor initially passes NO current, then FULL current. The transistor is said to be working in its two states: OFF then ON (sometimes called: "cut-off" and "saturation"). These are called digital states and the transistor is said to be a **DIGITAL TRANSISTOR** or a **SWITCHING TRANSISTOR** , working in **DIGITAL MODE.**

If the base is delivered 0.5v, then slowly rises to 0.75v and slowly to 0.65v, then

0.7v, then 0.56v etc, the transistor is said to be working in ANALOGUE MODE and the transistor is an **ANALOGUE TRANSISTOR**.
Since a transistor is capable of amplifying a signal, it is said to be an active device. Components such as resistors, capacitors, inductors and diodes are not able to amplify and are therefore known as passive components.

In the following tests, use your finger to provide the **TURN ON** voltage for the base (this is 0.55v to 0.7v) and as you press harder, more current flows into the base and thus more current flows through the collector-emitter terminals. As more current flows, the needle of the multimeter moves UP-SCALE.

TESTING A TRANSISTOR ON A DIGITAL METER

Testing a transistor with a **Digital Meter** must be done on the "DIODE" setting as a digital meter does not deliver a current through the probes on some of the resistance settings and will not produce an accurate reading.
The "DIODE" setting must be used for diodes and transistors. It should also be called a "TRANSISTOR" setting.

TESTING AN unknown TRANSISTOR

The first thing you may want to do is test an unknown transistor for COLLECTOR, BASE AND EMITTER. You also want to perform a test to find out if it is NPN or PNP. That's what this test will provide.
You need a cheap multimeter called an ANALOGUE METER - a multimeter with a scale and pointer (needle).
It will measure resistance values (normally used to test resistors) - (you can also test other components) and Voltage and Current. We use the resistance settings. It may have ranges such as "x10" "x100" "x1k" "x10"
Look at the resistance scale on the meter. It will be the top scale.
The scale starts at zero on the right and the high values are on the left. This is opposite to all the other scales.
When the two probes are touched together, the needle swings FULL SCALE and reads "ZERO." Adjust the pot on the side of the meter to make the pointer read exactly zero.

How to read: "x10" "x100" "x1k" "x10"
Up-scale from the zero mark is "1"
When the needle swings to this position on the "x10" setting, the value is 10 ohms.
When the needle swings to "1" on the "x100" setting, the value is 100 ohms.
When the needle swings to "1" on the "x1k" setting, the value is 1,000 ohms = 1k.
When the needle swings to "1" on the "x10k" setting, the value is 10,000 ohms = 10k.
Use this to work out all the other values on the scale.
Resistance values get very close-together (and very inaccurate) at the high end of the scale. [This is just a point to note and does not affect testing a transistor.]

Step 1 - FINDING THE BASE and determining NPN or PNP
Get an unknown transistor and test it with a multimeter set to "x10"
Try the 6 combinations and when you have the black probe on a pin and the red probe touches the other pins and the meter swings nearly full scale, you have an NPN transistor. The black probe is BASE
If the red probe touches a pin and the black probe produces a swing on the other two pins, you have a PNP transistor. The red probe is BASE
If the needle swings FULL SCALE or if it swings for more than 2 readings, the transistor is **FAULTY**.



This is an NPN transistor
The black probe is the BASE



This is a PNP transistor
The red probe is the BASE

Step 2 - FINDING THE COLLECTOR and EMITTER
Set the meter to "x10k."
For an NPN transistor, place the leads on the transistor and when you press hard on the two leads shown in the diagram below, the needle will swing almost full scale.


Set to "x10k"
This is the POSITIVE of the battery in the meter
push HERE
This is an NPN transistor
This is the NEGATIVE of the battery in the meter


Here is the equivalent circuit:
+
The finger is "turning ON the transistor"
collector
base
emitter

You have found the Collector Base and Emitter

For a PNP transistor, set the meter to "x10k" place the leads on the transistor and when you press hard on the two leads shown in the diagram below, the needle will swing almost full scale.


Set to "x10k"
This is the POSITIVE of the battery in the meter
This is a PNP transistor
This is the NEGATIVE of the battery in the meter
push HERE


Here is the equivalent circuit:
+
The finger is "turning ON the transistor"
emitter
base
collector

You have found the Collector Base and Emitter

SIMPLEST TRANSISTOR TESTER

The simplest transistor tester uses a 9v battery, 1k resistor and a LED (any colour). Keep trying a transistor in all different combinations until you get one of the circuits below. When you push on the two leads, the LED will get brighter.
The transistor will be NPN or PNP and the leads will be identified:


Here is the equivalent circuit:
1k
LED
+
−
9v
k
push
HERE
This is an
NPN
transistor
collector
base
emitter
1k
LED
k
c
b
e
NPN
9v
The finger is
"turning ON
the transistor"


Here is the equivalent circuit:
1k
LED
This is a
PNP
transistor
+
−
9v
k
emitter
base
collector
push
HERE
1k
LED
k
PNP
e
b
c
9v
The finger is
"turning ON
the transistor"

The leads of some transistors will need to be bent so the pins are in the same positions as shown in the diagrams. This helps you see how the transistor is being turned on. This works with NPN, PNP transistors and Darlington transistors.


collector
base
emitter

NPN transistor


collector
base
emitter

NPN transistor

HEATSINKING

Heat generated by current flowing between the collector and emitter leads of a transistor causes its temperature to rise. This heat must be conducted away from the transistor otherwise the rise may be high enough to damage the P-N junctions inside the device. Power transistors produce a lot of heat, and are therefore usually mounted on a piece of aluminium with fins, called a **HEATSINK**.
This draws heat away, allowing it to handle more current. Low-power signal transistors do not normally require heat sinking. Some transistors have a metal body or fin to connect to a larger heatsink. If the transistor is connected to a heatsink with a mica sheet (mica washer), it can be damaged or cracked and create a short-circuit. (See Testing Mica Washers). Or a small piece of metal may be puncturing the mica. Sometimes white compound called **Heatsink Compound** is used to conduct heat through the mica. This is very important as mica is a very poor conductor of heat and the compound is needed to provide maximum thermal conduction.

TRANSISTOR FAILURE

Transistor can fail in a number of ways. They have forward and reverse voltage ratings and once these are exceeded, the transistor will ZENER or conduct and may fail. In some cases a high voltage will "puncture" the transistor and it will fail instantly. In fact it will fail much faster via a voltage-spike than a current overload.

It may fail with a "short" between any leads, with a collector-emitter short being the most common. However failures will also create shorts between all three leads.
A shorted transistor will allow a large current to flow, and cause other components to heat up.
Transistors can also develop an open circuit between base and collector, base and emitter or collector and emitter.
The first step in identifying a faulty transistor is to check for signs of overheating. It may appear to be burnt, melted or exploded. When the equipment is switched off, you can touch the transistor to see if it feels unusually hot. The amount of heat you feel should be proportional to the size of the transistor's heat sink. If the transistor has no heat sink, yet is very hot, you can suspect a problem.
DO NOT TOUCH A TRANSISTOR IF IT IS PART OF A CIRCUIT THAT CARRIES 240VAC.
Always switch off the equipment before touching any components.

TRANSISTOR REPLACEMENT

If you can't get an exact replacement, refer to a transistor substitution guide to identify a near equivalent.

The important parameters are:
- Voltage
- Current
- Wattage
- Maximum frequency of operation

The replacement part should have parameters equal to or higher than the original.

Points to remember:
- Polarity of the transistor i.e. PNP or NPN.
- At least the same voltage, current and wattage rating.
- Low frequency or high frequency type.
- Check the pinout of the replacement part
- Use a desoldering pump to remove the transistor to prevent damage to the printed circuit board.
- Fit the heat sink.
- Check the mica washer and use heat-sink compound
- Tighten the nut/bolt - not too tight or too loose.
- Horizontal output transistors with an integrated diode should be replaced with the same type.

DIGITAL TRANSISTORS

There is no such thing as a DIGITAL TRANSISTOR or an AUDIO TRANSISTOR.
All transistors are just "TRANSISTORS" and the surrounding components as well as the type of signal, make the transistor operate in DIGITAL MODE or ANALOGUE MODE.
But we have some transistors that have inbuilt resistors to make them suitable for connecting to a digital circuit without the need for a base resistor.
Here is the datasheet for an NPN transistor BCR135w and PNP datasheet for BCR185w.
These transistors are called "Digital Transistors" because the "base lead" can be connected directly to the output of a digital stage. This "lead" or "pin" is not really the base of the transistor but a 4k7 (or 10k) resistor connected to the base allows the transistor to be connected to the rest of a digital circuit.
You cannot actually get to the base. The resistor(s) are built into the chip and the transistor is converted into a "Digital Transistor" because it will accept 5v on the "b"

lead.
The 47k is not really needed but it makes sure the transistor is fully turned OFF if the signal on the "b" lead is removed (in other words - if the input signal is converted to a high-impedance signal - see tri-state output from microcontrollers for a full explanation).
This transistor is designed to be placed in a circuit where the input changes from low to high and high to low and does not stop mid-way. This is called a DIGITAL SIGNAL and that is one reason why the transistor is called a digital transistor. (However you could stop half-way but the transistor may heat up and get too hot).
Any transistor placed in a digital circuit can be called a "digital transistor" but it is better to say it is operating in DIGITAL MODE.


OUT
(Collector)
IN
(Base)
R_1
R_2
GND
Emitter
B
C
E

The digital transistor has two resistors included inside the case
R1 is about 10k and R2 is approx 47k


(a) Digital Transistor NPN

(b) Digital Transistor PNP
VDD
LOAD
Iomax
Digital Transistor
NPN
Vin
R1
R2
Vin(V)
GND−
VDD
Vin(V)
Vin level
Digital Transistor
PNP
R2
R1
Vin
Iomax
LOAD

Equivalent circuit of the digital transistor

These transistors can be made to work in analogue circuits because they are ordinary transistors with a 10k base resistor, but you will have to know what you are doing.



Transistor in saturation

The circuit above shows the digital transistor is designed to allow a voltage of 5v to be supplied to the "base" pin and the transistor will Fully Conduct.
This type of transistor saves putting a base resistor on the PC board.
It can be tested just like a normal transistor but the resistance between base and emitter will be about 5k to 50k in both directions. If the collector-emitter is low in both directions the transistor is damaged.
Here's how to look at how the transistor works:
The 10k resistor on the base will allow 0.5mA to flow into the base. But the 47k will reduce this to 0.4mA. If the transistor has a gain of 100, the collector-emitter current can be 40mA.
To determine the current capability of the transistor, connect 100R load and turn the transistor ON. This will allow about 100mA for the collector-emitter current. Measure the collector-emitter voltage. If it is more than 0.5v, the transistor is OVER-LOADED.

DARLINGTON TRANSISTORS

A DARLINGTON TRANSISTOR is two transistors in a single package with three leads. They are internally connected in cascade so the gain of the pair is very high. This allows a very small input signal to produce a large signal at the output. They have three leads (Base, Collector and Emitter and can be PNP or NPN) and are equivalent to the leads of a standard individual transistor, but with a very high gain. The second advantage of a Darlington Transistor is its high input impedance. It puts very little load on the previous circuit.
Some Darlington transistors have a built-in diode and/or built-in resistor and this will produce a low reading in both directions between the base and emitter leads.



NPN Darlington PNP Darlington

Darlington transistors are tested the same as an ordinary transistor and a multimeter will produce about the same deflection, even though you will be measuring across two junctions, (and a base-emitter resistor is present).

HORIZONTAL OUTPUT TRANSISTORS, SWITCH-MODE TRANSISTORS, FLYBACK TRANSISTORS, POWER TRANSISTORS, VERTICAL TRANSISTORS . . . .

These are all names given to a transistor when it is used in a particular circuit. ALL these transistors are the same for testing purposes.
We are not testing for gain, maximum voltage, speed of operation or any special feature. We are just testing to see if the transistor is completely faulty and SHORTED.
A transistor can have lots of other faults and the circuit **using the transistor** is the best piece of TEST EQUIPMENT as it is detecting the fault.

TESTING MOSFETs and FETs

MOSFETs and **JFETs** are all part of the **FET** family.
MOSFET stands for **Metal Oxide Semiconductor Field Effect Transistor.**
FETs operate exactly the same as a "normal" transistor except they have different names for the input and output leads and the voltage between the gate and the source has to between 2v to 5v for the device to turn on fully. A FET requires almost NO CURRENT into the Gate for it to turn on and when it does, the voltage between drain and source is very low (only a few mV). This allows them to pass very high currents without getting hot. There is a point where they start to turn on and the input voltage must rise higher than this so the FET turns on FULLY and does not get hot.
Field Effect Transistors are difficult to test with a multimeter, but "fortunately" when a power **MOSFET** blows, it is completely damaged. All the leads will show a short circuit. 99% of bad **MOSFETs** will have GS, GD and DS shorted.
The following symbols show some of the different types of MOSFETs:



Most **MOSFET** transistors cannot be tested with a multimeter. This due to the fact that the Gate needs 2v - 5v to turn on the device and this voltage is not present on the probes of either meter set to any of the ohms ranges.
You need to build the following Test Circuit:



N-channel



P-channel

Touching the Gate will increase the voltage on the Gate and the MOSFET will turn ON and illuminate the LED. Removing your finger will turn the LED off.
Large devices such as the TO-220 types shown above do not like static electricity on the gate and you have to be careful not to "spike" the gate with any static. Generally this type of device is not "super sensitive" and you can use your finger or a large value resistor.
When replacing one of these devices, there are 2 things to match-up.
Voltage and Current.
In most cases, the "turn-ON" resistance (the resistance between Source and Drain) will be the same (something like 22 milli ohms) and the speed of operation will be ok.
Check the voltage needed to turn the gate ON and make sure you can supply the required voltage.

SILICON CONTROLLED RECTIFIERs (SCR)

The **Silicon Controlled Rectifier** (SCR) is a semiconductor device that is a member of a family of control devices known as **Thyristors**. It is a 3-leaded device and when a small current enters the Gate, the **thyristor** turns on. AND STAYS ON. It only conducts current between Anode and Cathode in one direction and it is mainly only used in DC circuits. When it is used with AC, it will only conduct for a maximum of half the cycle.


PNP
Transistor
P
N
P
N
P
N
NPN
Transistor
Anode
P
N
P
N
Gate
Cathode
Anode
Gate

THYRISTOR or SCR


Anode
Gate
Cathode

SCR

Silicon Controlled Rectifier


270R
Motor
Lamp
12v 6watt
+
12v
A
SCR
Under Test
S1
G
K
S2
Gate
Kathode
Cathode

SCR TESTER


push
button
470R
10k
LED
SCR
k
OFF
100n
+
6v

A


Anode
Gate
1k
1k
Cathode

SCR WITH TRANSISTORS


ON
470R
10k
1k
LED
e
b
c
BC557
+
6v
OFF
1k
BC547

B

To understand how an SCR "latches" when the gate is provided with a small current, we can replace it with two transistors as shown in diagram B above. When the ON button is pressed, the BC547 transistor turns on. This turns ON the BC557 and it takes over from the action of the switch.
To turn the circuit off, the OFF button removes the voltage from the base of the BC547.

Testing an SCR

An **SCR** can be tested with some multimeters but a minimum current Anode-to-Cathode is needed to keep the device turned on. Some multimeters do not provide this amount of current and the **SCR Tester** circuit above is the best way to test these devices.
Shorted SCRs can usually be detected with an ohmmeter check (SCRs usually fail shorted rather than open).
Measure the anode-to-cathode resistance in both the forward and reverse direction; a good SCR should measure near infinity in both directions.
Small and medium-size SCRs can also be gated ON with an ohmmeter (on a digital meter use the Diode Check Function). Forward bias the SCR with the ohmmeter by connecting the black (-) lead to the anode and the red (+) lead to the cathode

(because the + of the battery is connected to the negative lead, in most analogue multimeters). Momentarily touch the gate lead to the anode while the probes are still touching both leads; this will provide a small positive turn-on voltage to the gate and the cathode-to-anode resistance reading will drop to a low value. Even after removing the gate voltage, the SCR will stay conducting. Disconnecting the meter leads from the anode or cathode will cause the SCR to revert to its non-conducting state.
When making the above test, the meter impedance acts as the SCR load. On larger SCRs, it may not latch ON because the test current is not above the SCR holding current.

Using the SCR Tester
Connect an SCR and press Switch2. The lamp should not illuminate. If it illuminates, the SCR is around the wrong way or it is faulty.
Keep Switch 2 PRESSED. Press Sw1 very briefly. The lamp or motor will turn ON and remain ON. Release Sw 2 and press it again. The Lamp or motor will be OFF.

TRIACs

A triac is a bidirectional, three-terminal dual, back-to-back thyristor (SCR) switch. This device will conduct current in both directions when a small current is constantly applied to the Gate.
If the gate is given a small, brief, current during any instant of a cycle, it will remain triggered during the completion of the cycle until the current though the Main Terminals drops to zero.
This means it will conduct both the positive and negative half-cycles of an AC waveform. If it is tuned on (with a brief pulse) half-way up the positive waveform, it will remain on until the wave rises and finally reaches zero. If it is then turned on (with a brief pulse) part-way on the negative wave, the result will be pulses of energy and the end result will be about 50% of the full-energy delivered at a rate of 100 times per second for a 50HZ supply.
TRIACs are particularly suited for AC power control applications such as motor speed control, light dimmers, temperature control and many others.





TRIAC (2 SCR's)
TRIode for Alternating Current

Using the TRIAC Tester

Connect a TRIAC and press Switch2. The lamp should not illuminate. If it illuminates, the TRIAC is faulty.
Keep Switch 2 PRESSED. Press Sw1 very briefly. The lamp or motor will turn ON and remain ON. If the lamp does not turn on, reverse the TRIAC as the current into the gate must produce a slight voltage between **Gate** and **Main Terminal 1**.
Release Sw 2 and press it again. The Lamp or motor will be OFF.



TRIAC TESTER

MICA WASHERS AND INSULATORS

Plastic insulating sheets (washers) between a transistor and heatsink are most often made from mica but some are plastic and these get damaged over a period of time, turn dark and become cracked.
The plastic eventually becomes carbonized and conducts current and can affect the operation of the appliance. You can see the difference between a mica sheet (washer) and plastic by looking where it extends from under the transistor. Replace all plastic insulators as they eventually fail.

SPARK GAPS

Some TV's and monitors with a CRT (picture tube), have spark gaps either on the socket at the end of the tube or on the chassis.
These can consist of two wires inside a plastic holder or a glass tube or special resistive device.
The purpose of a spark gap is to take any flash-over (from inside the tube), to earth. This prevents damage to the rest of the circuit.
However if the tube constantly flashes over, a carbon track builds up between the wires and effectively reduces the screen voltage. This can cause brightness and/or focus problems. Removing the spark-gap will restore the voltage.
These are not available as a spare component and it's best to get one from a discarded chassis.

CO-AX CABLES

Co-Ax cables can produce very high losses and it seems impossible that a few metres of cable will reduce the signal. The author has had a 3 metre cable reduce the signal to "snow" so be aware that this can occur. Faults can also come from a splitter and/or balun as well as dirty plugs and sockets. This can result in very loud bangs in the sound on digital reception.

TESTING EARTH LEAKAGE DETECTORS or Residual Current Devices or Ground Fault Circuit Interrupters or GFCI

An Earth Leakage Detector or Sensor is a circuit designed to continuously monitor the imbalance in the current in a pair of load carrying conductors.
These two conductors are normally the Active and Neutral. Should the imbalance current reach 30mA the sensor will "trip" and remove the voltage (and current) from

the line being monitored.
Some detectors will trip at 15mA.
You cannot alter the sensitivity of the device however there are a number of faults in these devices that can be fixed.
In some devices the contact pressure for the 10Amp or 15 Amp contacts is very weak and they arc and produce an open circuit. The result is this: When you press the rest button, power is not restored to the output.
Clean the contacts with a small file and bend the metal strips to the contacts so they make a very strong contact.
The other fault is the trip mechanism.
The magnetism from the coil does not allow the pin to move and "trip" the contacts. It may be due to a small metal filing or the pin not moving freely enough.
All good Earth Leakage Detectors have a TEST BUTTON. This connects a resistor between the active line and earth so that 15mA or 30mA flows.
The detector should trip immediately. Make sure the trigger mechanism trips when the test button is pressed.
None of the electronics in the detector can be replaced however you can test the mechanical operation and the pressure on the contacts when the unit is removed from the power. Do not work on the device when it is connected to the mains.

TESTING CELLS AND BATTERIES

There is an enormous number of batteries and cells on the market and a number of "battery testers." Instead of buying a battery tester that may give you a false reading, here is a method of testing cells that is guaranteed to work.
There are two types of cell: a **rechargeable** cell and a non rechargeable cell.

The easiest way to test a **rechargeable** cell is to put a group of them in an appliance and use them until the appliance "runs down" or fails to work. If you consider the cells did not last very long, remove them and check the voltage of each cell. The cell or cells with the lowest voltage will be faulty. You can replace them with new cells or good cells you have in reserve.
There is no other simple way to test a rechargeable cell.
You cannot test the "current of a cell" by using an ammeter. A rechargeable cell can deliver 10 amps or more, even when nearly discharged and you cannot determine a good cell for a faulty cell.

Dry cells are classified as "non-rechargeable" cells.
DRY CELLS and MANGANESE CELLS are the same thing. These produce 1.5v per cell (manganese means the Manganese Dioxide depolariser inside the cell. All "dry cells" use manganese dioxide).
ALKALINE CELLS produce between 2 - 10 times more energy than a "dry cell" and produce 1.5v per cell.
Alkaline cells can fail for no reason at any stage in their life and are not recommended for emergency situations.
The output voltage of some Alkaline cells can fall to 0.7v or 0.9v for not apparent reason.
There are lots of other cells including "button cells," hearing-aid cells, air cells, and they produce from 1.2v to 3v per cell.

Note:
Lithium cells are also called "button cells" and they produce 3v per cell.
Lithium cells are non-rechargeable (they are generally called "button cells") but some Lithium cells can be recharged. These are Lithium-ion cells and generally have a voltage of 3.6v. Some Lithium-ion cells look exactly like 3v Lithium cells, so you have to read the data on the cell before charging.

You cannot test the voltage of a cell and come to any conclusion as to the age of the cell or how much energy remains. The voltage of a cell is characteristic to the chemicals used and the actual voltage does not tell you its condition.
Some "dry cells" deliver 1.5v up to the end of their life whereas others drop to about 1.1v very quickly.

Once you know the name of the cell that drops to 1.1v, avoid them as the operation of the equipment "drops off" very quickly.

However if you have a number of different cells and need to know which ones to keep, here's the solution:

1. Check the voltage and use those with a voltage above 1.1v
2. Next, select 500mA or 10A range on a meter and place the probes on a cell. For a AAA or AA cell, the current should be over 500mA and the needle will swing full scale very quickly.

Keep the testing short as you are short-circuiting the cell but it is the only way to determine the internal impedance of the cell and this has a lot to do with its stage-of-charge.

This will give you a cell with a good terminal voltage and a good current capability.

This also applies to button cells, but the maximum current they will deliver will be less.

If you want to get the last of the energy out of a group of cells they can be used in the following circuits:



TESTING PIEZO DIAPHRAGMS and PIEZO BUZZERS

There are two types of piezo devices that produce a sound.

They are called **PIEZO DIAPHRAGMS** and **PIEZO BUZZERS**.

A **piezo diaphragm** consists of two metal plates with a ceramic material between. The ceramic expands and contracts when an alternating voltage is placed on the two plates and this causes the main plate to "dish" and "bow."

This creates a high-pitched sound. There are no other components inside the case and it requires an AC voltage of the appropriate frequency to produce a sound.

A **piezo buzzer** has a transistor and coil enclosed and when supplied with a DC voltage, the buzzer produces a sound.

Both devices can look exactly the same and the only way to tell them apart is by connecting a 9v battery. One device may have "+' and "-" on the case to indicate it is a piezo buzzer, but supplying 9v will make the buzzer produce a sound while the piezo diaphragm will only produce a "click."

PIEZO DIAPHRAGM
PIEZO BUZZER

A piezo diaphragm will produce a click
when connected to 9v DC.
A piezo buzzer will produce a tone when
connected to a DC voltage.

How a PIEZO BUZZER WORKS

A Piezo Buzzer contains a transistor, coil, and piezo diaphragm and produces sound when a voltage is applied. The buzzer in the circuit above is a PIEZO BUZZER.



The circuit starts by the base receiving a small current from the 220k resistor. This produces a small magnetic flux in the inductor and after a very short period of time the current does not increase. This causes the magnetic flux to collapse and produce a voltage in the opposite direction that is higher than the applied voltage.
3 wires are soldered to pieces of metal on the top and bottom sides of a ceramic substrate that expands sideways when it sees a voltage. The voltage on the top surface is passed to the small electrode and this positive voltage is passed to the base to turn the transistor ON again. This time it is turned ON more and eventually the transistor is fully turned ON and the current through the inductor is not an INCREASING CURRENT by a STATIONARY CURRENT and once again the magnetic flux collapses and produces a very high voltage in the opposite direction. This voltage is passed to the piezo diaphragm and causes the electrode to "Dish" and produce the characteristic sound. At the same time a small amount is "picked-off" and sent to the transistor to create the next cycle.

TESTING A SPEAKER

A speaker (also called a **loud speaker**) has coil of wire wrapped around a magnet but it does not

touch the magnet as it is wound on a thin cardboard former so that the coil will be pulled closer to the magnet when a current flows in the coil.
When the current flows in the other direction, the coil moves away from the magnet.
The coil is called voice coil and it is connected to a sheet of thin card called a CONE and as the cone vibrates, the speaker reproduces music or noise.
Use a multimeter on a low ohms scale to read the value of resistance of the coil.
It can be as low as 2 ohms or as high as 100 ohms.
Most speakers have an 8R voice coil and the actual resistance may be slightly lower than this.
Some speakers have a resistance of 16R, 32R or 50R and even 75 ohms.
You would think putting a 16R speaker in place of 8R would reduce the sound output, but this is not always the case.
You can even use 50R or 75R and get the same performance.
This may sound amazing, but here is the reason.
The cone is deflected a certain amount due to the current flowing and the number of turns.
These two values are multiplied together to produce a value called AMP-TURNS.
If we have an 8R speaker with 80 turns and 100mA, the result is 0.1 x 80 = 8.
If we use a 16R speaker, the average current flow will be 50mA and the number of turns will be about 160. The multiplication of 0.05 x 160 = 8.
The author then tried a 50R speaker and the sound output was equal to 8R and the same with 75R speaker.
This might not apply in all situations, but the 75R speaker was slightly larger and the ticking sound form the **Metal Detector** kit was louder than using an 8R mini speaker.

To see if the cone of a speaker is undamaged, push it slightly and it will move towards the magnet. If it does not move, it is bent or damaged. If the cone is scratchy when pushed, it is rubbing against the magnet.
A cone should be able to be pushed and pulled from its rest-state. If not, it will produce a distorted sound.

TESTING A CIRCUIT

Whenever you test a circuit, the TEST EQUIPMENT puts "a load" or "a change" on it. It does not matter if the test equipment is a multimeter, Logic Probe, CRO, Tone Injector or simply a LED and resistor.
There are two things you need to know.
1. The IMPEDANCE of the circuit at the location you are testing, and
2. The amount of load you are adding to the circuit via the test equipment.

There is also one other hidden factor. The test equipment may be injecting "hum" due to its leads or the effect of your body at absorbing hum from the surroundings or the test equipment may be connected to the mains.
These will affect the reading on the test equipment and also any output of the circuit. Sometimes the test equipment will prevent the circuit from working and sometimes it will just change the operating conditions slightly. You have to be aware of this.
The last section of this eBook covers High and Low Impedance and understanding impedance is something you need to know.
The point to note here is the fact that the equipment (and the reading) can be upset by hum and resistance/capacitance effects of test equipment. This is particularly critical in high impedance and high frequency circuits.

TESTING INTEGRATED CIRCUITS (IC's)

Integrated Circuits can be tested with a LOGIC PROBE. A Logic Probe will tell you if a line is HIGH, LOW or PULSING.
Most logic circuits operate on 5v and a Logic Probe is connected to the 5v supply so the readings are accurate for the voltages being tested.
A Logic Probe can also be connected to a 12v CMOS circuit.
You can make your own Logic Probe and learn how to use it from the following link:

http://www.talkingelectronics.com/projects/LogicProbeMkIIB/LogicProbeMk-IIB.html


LOGIC PROBE MKII


GREEN
RED
YELLOW
LOW
HIGH
PULSE
+VE
1N 4002
74c14
14
4
3
13
12
100k
2M2
470R
470R
330R
MINI PIEZO
47k
1M
7
1
8
5
4
4049
1
2
100p
100p
22n
22n
11
10
2
3
8
68k
9
8
14
15
10
11
12
9
1u
330k
5
6
7
PROBE
10k
220k
470k
11 x 1N 4148 diodes
10k
1u
1u
22n
10k
10n
1u
-VE

LOGIC PROBE with PULSE

This is a very simple transistor circuit to provide HIGH-LOW-PULSE indication for digital circuits. It can be built for less than $5.00 on a piece of matrix board or on a small strip of copper clad board if you are using surface mount components. The probe will detect a HIGH at 3v and thus the project can be used for 3v, 5v and CMOS circuits.


Probe
1M
10k
470k
1M
earth clip
BC547
b
c
e
green
LOW
220R
1N4148
BC547
47k
330k
4k7
red
HIGH
BC547
220R
1N4148
47u
BC557
red
ON
100R
orange
PULSE
4k7
on/off
6v

LOGIC PROBE using CD4001 and CD4011

Here is a simple Logic Probe using a single chip. The circuits have been designed for the **CD4001** CMOS quad NOR gate and **CD4011** CMOS NAND gate. The output has an active buzzer that produces a beep when the pulse LED illuminates (the buzzer is not a piezo-diaphragm but an active buzzer containing components).


+Vcc Power
clip
CD 4001
1k
1M
4M7
2M2
HIGH
red
LED
Probe
1
2
3
470k
5
6
14
4
7
8
9
10
100n
12
13
11
green
LED
LOW
Pulse
yellow
LED
1k
1k
+
−
3v -12v piezo buzzer
0v Power
clip


+Vcc Power
clip
CD 4011
1k
HIGH
red
LED
2M2
Probe
1
2
3
5
4
6
7
100n
8
9
10
12
13
14
11
green
LED
LOW
1k
4M7
Pulse
yellow
LED
1k
−
+
3v -12v piezo buzzer
0v Power
clip

[SUPER PROBE MkII](#) has 20 different features including a Logic Probe, capacitance tester, Inductance tester, and more.


7-30v
LM78L05
5v
10k
100n
red
LED
GND
10k
×3
12
7
1
6
a b .....
100n
10u
1
*MCLR
VDD
VSS
VSS
20
19
8
BUT1
15
RC4
BUT2
16
RC5
TIP
1M
1%
22R
22R
2
RA0/AN0
5v
25v
5v6
249k
1%
470R
6
RA4/T0
7
RA5
GND
100R
3
RA1
150R
4
RA2
100k
5
RA3
10k
18
RC7
10k
17
RC6
PIC16F870
RB0
RB1
RB2
RB3
RB4
RB5
RB6
RB7
21
22
23
24
25
26
27
28
11
7
4
2
1
10
5
3
a
b
c
d
e
f
g
dp
RC0
RC1
RC2
RC3
11
12
13
14
12
9
8
6
A1
A2
A3
A4
LG3641BH (CA)
OS1
9
22p
20MHz
OS2
10
22p
78L05
out
in
com

SUPER PROBE MkII Circuit



SUPER PROBE MkII

To test an IC, you need a circuit diagram with waveforms. These diagrams will show the signals and are very handy if a CRO (cathode ray Oscilloscope) is used to diagnose the problem. The CRO will reproduce the waveform and prove the circuit is functioning correctly.
A Logic Probe will just show activity and if an output is not producing a "pulse" or "activity," you should check the power to the IC and test the input line.
It is beyond the scope of this eBook to explain how to diagnose waveforms, however it is important to know if signals are entering and exiting an IC and a Logic Probe is designed for this.

SIGNAL INJECTOR

This circuit is rich in harmonics and is ideal for testing amplifier circuits. To find a fault in an amplifier, connect the earth clip to the 0v rail and move through each stage, starting at the speaker. An increase in volume should be heard at each preceding stage. This Injector will also go through the IF stages of radios and FM sound sections in TV's.



TESTING AUDIO AMPLIFIERS and AUDIO IC's

The **Super Probe MII** described above has a "noise" function and a tone function that allows you to inject a signal into an audio stage, amplifier (made from discrete components) or an audio chip, and detect the output on a speaker.
Audio stages are very difficult to work-with if you don't have a TONE GENERATOR or SIGNAL INJECTOR.
The signals are very small and not detected by a multimeter.
You can start anywhere in an amplifier and when a tone is heard, you can keep probing until the signal is not present or louder. From this you can work out which way the signal is travelling.
A Signal Injector is very handy for finding shorts and broken wires in switches, plugs, sockets and especially leads to headphones.
You can determine the gain of a stage (amplification) by probing before and after a chip or transistor and listen for the relative increase in volume from the speaker.
You can also use your finger to produce "hum" or "buzz" if a **Signal Injector** is not available.
Nearly all audio problems are plugs, sockets and cracks in the PC board, but finding them takes a lot of time and skill.

TESTING IC's - also called "CHIPS"

An Integrated Circuit is also called a "chip." It might have 8 pins or as many as 40.
Some chips are ANALOGUE. This means the input signal is rising and falling slowly and the output produces a larger version of the input.
Other chips are classified as DIGITAL and the input starts at 0v and rises to rail voltage very quickly. The output does exactly the same - it rises and falls very quickly.
You might think the chip performs no function, because the input and output voltage has the same value, but you will find the chip may have more than one output and the others only go high after a number of clock-pulses on the input, or the chip may be outputting when a combination of inputs is recognised or the output may go HIGH after a number of clock pulses.

ANALOGUE CHIPS **(also see above)**
Analogue chips are AUDIO chips or AMPLIFIER chips.
To test these chips you will need three pieces of test equipment:
1. A multimeter - this can be digital or analogue.
2. A Signal Injector
3. A Mini Bench Amplifier.

The Mini Bench Amplifier is available as a kit.

TOSHIBA
SUPER HEAVY DUTY
PROBE
MINI BENCH AMPLIFIER

MINI BENCH AMPLIFIER


Optional
probe
lead
100n
Probe
max
10k
min
ground
lead
3
2
LM386
6
8
5
1
4
22u
5k
200
30
"Gain"
100u
8R
ear
piece
1k
Power
ON
100u
ON
9v

MINI BENCH AMPLIFIER CIRCUIT

Start by locating the power pin with a multimeter.
If the chip is receiving a voltage, you can use the Mini Bench Amplifier to detect an output.
Connect the Ground Lead of the Mini Bench Amplifier to 0v and touch the Probe tip on each of the pins.
You will hear faint audio on the Input pin and very loud audio on the Output pin.
If no input is detected, you can use a Signal Injector to produce a tone.

Connect the clip of the Signal Injector to 0v and the probe to the input pin of the amplifier chip. At the same time, connect the Mini Bench Amplifier to the output pin and you will hear a very loud tone.
These pieces of test equipment can also be used to diagnose an amplifier circuit constructed with individual components.
Amplifier circuits using discrete components are very hard to trouble-shoot and these pieces of test equipment make it very easy.

DIGITAL CHIPS

It is always best to have data on the chip you are testing, but if this is not available, you will need three pieces of equipment:
1. A multimeter - this can be digital or analogue.
2. A Logic Probe,
3. A logic Pulser.

Firstly test the chip to see if power is being delivered. This might be anything from 3v3 to 15v.
Place the negative lead of the multimeter on the earth rail of the project - this might be the chassis, or the track around the edge of the board or some point that is obviously 0v.
Try all the pins of the chip and if you get a reading, the chip will have "supply."
Identify pin 1 of the chip by looking for the "cut-out" at the end of the chip and you may find a small dimple below the cut-out (or notch). This is pin 1 and the "power pin" can be directly above or any of the other pins.
Next you need to now if a signal is entering the chip.
For this you will need a LOGIC PROBE.
A Logic Probe is connected to the same voltage as the chip, so it will detect a HIGH and illuminate a red LED.
Connect the Logic Probe and touch the tip of the probe on each pin.
You will not know if a signal is an input or output, however if you get two or more active pins, you can assume one is input and the other is output. If none of the pins are active, you can assume the signal is not reaching this IC.
If only one pin is active, you can assume the chip is called a CLOCK (or Clock Generator). This type of chip produces pulses. If more than two pins are active, you can assume the chip is performing its function and unless you can monitor all the pins at the same time, you don't know what is happening.
This is about all you can do without any data on the chip.

If you have data on the chip, you can identify the input(s) and output(s).
A Logic Probe on each of these pins will identify activity.
A Logic Probe has 3 LEDs. Red LED indicates a HIGH, Green indicates a LOW and Orange indicates a PULSE (activity).
Some Logic Probes include a piezo and you can hear what is happening, so you don't take your eyes off the probe-tip.
It is important not to let the probe tip slip between the pins and create a short-circuit.

LOGIC PULSER

If you have a board or a single chip and want to create activity (clock pulses), you can use a Logic Pulser. This piece of test equipment will produce a stream of pulses that can be injected into the clock-line (clock input) of a chip.
You can then use a Logic Probe at the same time on the outputs to observe the operation of the chip.

You can also use the Mini Bench Amplifier to detect "noise" or activity on the inputs and outputs of digital chips.
This only applies if the frequency is in the audio range such as scanning a keyboard or switches or a display.

This is how to approach servicing/testing in a general way. There are thousands of digital chips and if you want to test a specific chip for its exact performance, you will need to set-up a "test-bed."

REMOTE CONTROLS

There are two types of remote control - Infrared and RF. Infrared is used for short-range, line-of-sight for TV's DVD's etc.
A few faults can be fixed, but anything complex needs a new remote control.
Check the batteries and battery-contacts. See if the IR LED is illuminating by focusing it into a digital camera and looking on the screen for illumination.
The only other things are a sticky button, a worn-out button or a crack in the PC board. Water damage is generally too much work to repair.
RF remote controls for cars, garage doors etc need a second working unit to check the power output.
Here is a simple circuit that can be connected to an analog multimeter to detect the signal strength at a very close range:


2in (5cm) lead
100p
1N4148
1N4148
100n
LED
470R
Positive of multimeter
negative of multimeter
THE LED POWER METER CIRCUIT

To hear the tone from a transmitter, the **Mini Bug Detector** circuit can be used:


3k3
2k2
220k
3k3
22mm dia
On/Off Sw
"ON" LED
10cm antenna
mini piezo
10mH (40R)
47k
+
3v
1M
1M
22n
BC547
47u
22n
470p
2N3563
22n
BC547
1N4148
22n
BC547
1k
20t 3mm dia
1N4148
MINI BUG DETECTOR

Any further investigation requires a circuit diagram so you can work out what is actually being sent from the transmitter.
Most of the time it is a faulty switch, battery or contacts. Make sure the setting is correct on the "dip switches" and use a working unit to compare all your testing.

TESTING VOLTAGES ON (in) A CIRCUIT

There are basically two different types of circuit.
1. **ANALOGUE CIRCUIT**
An analogue circuit can also be called an AUDIO CIRCUIT and the voltages at different points in a circuit can be measured with a multimeter but the changes (the waveforms) will be quite small or changing at a rapid rate and cannot be detected by a multimeter.
You need a CRO to "see" the signals or a **Signal Injector** to inject a waveform into the circuit and hear the result on the circuit's speaker.

2. **DIGITAL CIRCUIT**
A digital circuit can also be called a "Computer Circuit" or "Logic Circuit" and some of

the voltages can be measured with a multimeter (such as supply voltages) but the "signal lines" will be be changing from HIGH to LOW to HIGH very quickly and these signals are detected with a **Logic Probe**.

Here are some circuits with details of how to test the voltages.
Most circuits do not show voltages at various different points and we will explain what to expect on each "stage."

A "STAGE"

A stage is a set of components with an input and output. A "stage" can also be called a "Building Block."
Sometimes it has a capacitor on the input and one on the output.
This means the stage is completely isolated as far as DC is concerned.
The stage has a supply (a DC supply) and it is producing its own voltages on various points on the "stage." It can only process (amplify) "AC." (signals).
Sometimes the stage can be given a name, such as small-signal amplifier, push-pull amplifier or output.
If the stage has a link or resistor connected to a previous stage, the previous stage will have a "DC effect" on the stage. In other words it will be biasing or controlling the voltages on the stage. The stage may be called a "timer" or "delay" or "DC amplifier."

It is important to break every circuit into sections. This makes testing easy. If you have a capacitor at the input and output, you know all the problems lie within the two capacitors.
In a digital circuit (no capacitors) you need to work on each IC (integrated Circuit) and test the input for activity and all the outputs.

Once you have determined if the circuit is Analogue or Digital, or a combination of both, you have to look at the rail voltage and work out the size or amplitude of the voltage or waveform.
This is done before making a test, so your predictions are confirmed.
You will need a **multimeter** (either Digital or Analogue) a **Logic Probe** and a **Signal Injector** (**Tone Generator**). An analogue meter has the advantage that it will detect slight fluctuations of voltage at a test-point and its readings are faster than a digital meter. A digital meter will produce an accurate voltage-reading - so you should have both available.

HIGH IMPEDANCE AND LOW IMPEDANCE

Every point in a circuit has a characteristic called "IMPEDANCE." This has never been discussed before in any text book. That's why it will be new to you.
In other words, every point will be "sensitive to outside noise."
An audio amplifier is a good example. If you put your finger on the active input, it will produce hum or buzz in the speaker. This is because it is a HIGH IMPEDANCE line or high impedance section of the circuit.
The same applies to every part in a circuit and when you place Test Equipment on a line for testing purposes, the equipment will "upset" the line. It may be very slight but it can also alter the voltage on the point CONSIDERABLY.
We have already mentioned (above) how a cheap multimeter can produce a false reading when measuring across a 1M resistor. That's why you need high impedance test Equipment so you do not "load" the point you are testing and create an inaccurate reading.
The word **Impedance** really means resistance, but when you have surrounding components such as diodes, capacitors, transistors, coils, Integrated Circuits, supply-voltages and resistors, the combined effect is very difficult to work out as a "resistance" and that's why we call it "Impedance."
The term "**High and Low Impedance**" is a relative term and does not have any absolute values but we can mention a few points to help you decide.
In general, the base of a transistor, FET input of an IC are classified as HIGH IMPEDANCE.
The output of these devices are LOW IMPEDANCE.

Power rails are LOW IMPEDANCE.
An oscillator circuit and timing circuit are HIGH IMPEDANCE.
A LOAD is low impedance.
And it gets tricky: An input can be designed to accept a low-impedance device (called a transducer or pick-up) and when the device is connected, the circuit becomes LOW impedance, but the input circuitry is actually high impedance.
The impedance of a diode or LED is HIGH before the device sees a voltage higher than the junction voltage and then it becomes LOW Impedance.
Impedance is one of the most complex topics however it all comes down to testing a circuit without loading it.
That's why test equipment should have an input impedance higher than 1M.

The first circuit we will investigate is the **Mini Bug Detector**, shown above and below. Points on the circuit have been labelled A, B, C etc:



Point A - The first transistor is "self-biased" and will have 0.6v on the base. The antenna is connected to a 20 turn coil and you might think the coil will "short" the signals to earth.
But the coil and 470p capacitor form a circuit that oscillates at a high frequency when the antenna wire picks up stray signals. The coil and capacitor actually amplify the signals (see Talking Electronics website: Spy Circuits to see how a TANK CIRCUIT works) and these signals enter the base of the first transistor.
This is classified as a HIGH Impedance section because the signals are small and delicate and any loading via test equipment will kill them. The first transistor amplifies the signals about 70 times and they appear at **Point B**.

The signal passes though a 22n to **Point C** and the transistor amplifies the signal about 70 times to **point D**. **Point C** is classified as high impedance as any voltage measurement at this point will upset the biasing of the stage as a few millivolts change in base-voltage will alter the voltage on the collector considerably. **Point D** is classified as low impedance as any voltage-testing will not alter the voltage appreciably.
The output of the second stage passes through a capacitor to the join of two diodes. These two diodes are not turned on because the voltage at **Point E** can never rise above 0.7v as this is the voltage produced by the base-emitter of the third transistor.
The purpose of the two diodes is to remove background noise. Background noise is low amplitude waveforms and even though the transistor is turned on via the 220k, low amplitude signals will not be received. The third transistor works like this: It cannot be turned ON any more because any waveform from the 22n will be "clipped" by the bottom diode and it will never rise above 0.6v.
So, the only signal to affect the transistor is a negative signal - to turn it OFF.
Firstly we have to understand the voltage on the 22n. When the second transistor is sitting at mid-rail voltage, the 22n gets charged via the 2k2 and lower diode. When

the transistor gets tuned ON, the collector voltage falls and the left side of the 22n drops. The right side of the 22n also drops and when it drops 0.6v, the top diode starts to conduct and when the voltage on the 22n drops more than 0.6v the third transistor starts to turn OFF. This effect is amplified by the transistor at least 100 times and appears at **Point F.** All the voltages around the two diodes are classified as HIGH Impedance as any piece of test equipment will upset the voltage and change the output.

There are some losses in amplitude of the signal as it passes through the 22n coupling capacitors but the end result is a very high strength signal at **point G.** The 4th transistor drives a 10mH choke and the mini piezo is effectively a 20n capacitor that detects the "ringing" of the inductor to produce a very loud output.

The 22n capacitor on the collector eliminates some of the background noise. The choke and piezo form an oscillatory circuit that can produce voltages above 15v, even though the supply is 3v.

The 47n capacitor at **Point J** is to keep the supply rails "tight" (to create a LOW Impedance) to allow weak cells to operate the circuit.

The "Power-ON" LED tells you to turn the device off when not being used and **Point L** is the power supply - a low impedance line due to the 47u electrolytic.

Testing the Mini Bug Detector

To test the Mini Bug Detector, you will need a Signal Injector.

Place the Injector on **Point G** and you will hear a tone. Then go to **E**, **C** and **A**. The tone will increase in volume. If it does not increase, you have pin-pointed the faulty stage.

The next circuit is a combination of digital and analogue signals. It is a **Logic Probe**:



The voltage on a circuit (to be tested) is detected by the probe at **Point A** of the circuit above and the "tip" is classified as "reasonably high impedance" as it has a 220k resistor between the tip and 0v rail. The 1M reduces the impedance by about 20% but the inputs of the two inverters have no effect on the "tip" impedance as they are extremely high input-impedance devices.

The 1M trim pot is designed to put put a voltage on **point B** that is slightly higher than mid-rail so the green LED is turned off.

Point A will see a voltage below mid-rail and **point C** will be HIGH. **Point C** and **F** are low-impedance outputs.

When the tip of the probe is connected to a LOW voltage, Point B sees a LOW and Point F goes LOW to illuminate the green LED. At the same time it removes the "jamming voltage" produced by the diode between pin 4 of the 4049 and pin 3 of the

74C14 and the oscillator between **points H and J** produces a low-tone via the 100k resistor and 22n to indicate a LOW.
When the probe tip sees a HIGH, a lot more things happen.
Point C goes LOW and turns on the red LED. At the same time the 100p is in an uncharged state and the right lead goes LOW. This takes the left lead LOW as the left lead connects to a HIGH Impedance line and pin 9 goes LOW. This makes **point E** HIGH
and since the 1u is in an uncharged state, pin 11 goes HIGH. This makes **point G** LOW and the diode between pins 9 and 12 keeps pin 9 LOW and takes over from the pulse from the 100p. The yellow LED is illuminated. The 1u starts to charge via the 470k and when it is approx half-charged, pin 11 sees a HIGH and **point G** goes low. This creates the length of pulse for the yellow LED.
At the same time, **Point L** goes LOW because the "jamming diode" from pin 2 of the 4049 goes low and allows the inverter between point L and N to produce a tone for the piezo.
In addition, **Point I** goes HIGH and quickly charges a 1u electrolytic. This removes the effect of the jamming diode on pin 5 of the 74C14 and a low frequency oscillator made up of 68k and 1u between pins 5&6 turns on and off an oscillator between **points O** and **R** to get a beep. The mini piezo is driven n bridge mode via the two gates between **points QT** and **PS**.
Point U is a 1u electrolytic to reduce the impedance of the power rail and **Point V** is a protection diode to prevent damage if the probe is connected to the supply around the wrong way.

Testing the Logic Probe
You can test the Logic Probe with the simple Logic Probe with Pulse project described above. It will let you know if each point in the circuit is HIGH or LOW. You will also find out the difficulty in testing the points that are HIGH Impedance, as the Probe will upset the voltage levels and the reading may be inaccurate.

More circuits will be added here in the future.

THE VOLTAGE DIVIDER - this topic could fill a book.

You need to read lots of other sections in this eBook, including the section on measuring across a resistor with a multimeter, and high impedance circuits, to fully understand the complexities of a VOLTAGE DIVIDER CIRCUIT.
It is one of the most important BUILDING BLOCKS to understand. Even though it may consists of two components, you have to understand what is happening between these two components. You have to realise there is a voltage at their join that will be rising and falling due to one of the components changing RESISTANCE. Sometimes you can work out the voltage at the join by using Ohm's LAW but quite often it will be impossible as it is changing (rising and falling) during the operation of the circuit.
At the beginning of this discussion we will only dealing with DC circuits and the voltage across a particular component will be due to its RESISTANCE. We are not going into any formulas, as it is very easy to measure the voltages with a multimeter set to VOLTS and you will have an accurate result.
The simplest two components in series are resistors. They always have the same resistance during the operation of a circuit and the voltage across each will not change.
In a further discussion we will cover "resistors" that change value according to the temperature. These are called THERMISTORS. And we have "resistors" that change value according to the light they receive. These are called LIGHT DEPENDENT RESISTORS (LDR's) or PHOTO RESISTORS.
A transistor that is partly or fully turned ON can be considered to be similar to a resistor.
In these 3 cases we need to measure the voltage at the join with a voltmeter as it will be a lot of work to measure the resistance and work out a value.
You can also keep a voltmeter on the joint and watch the voltage change.
Finally we have some components that produce a fixed voltage across them (or nearly fixed) and the remaining voltage is dropped across a resistor. These

components MUST have a resistor connected in series to limit the current and allow the component to pass the specified in the datasheet.

These devices include LEDs, diodes and zener diodes. A LED will have a fairly fixed voltage across it from 1.7v to 3.6v depending on the colour. A diode will have a voltage of 0.7v across it when it is connected to a voltage via a resistor. And a zener diode will have a fixed voltage across it when it is connected with the cathode to the positive rail via a resistor. The voltage across it will be as marked on the zener.

The concept of a VOLTAGE DIVIDER is very simple, but it takes a lot of understanding because both VOLTAGE and CURRENT are involved in the UNDERSTANDING-PROCESS.

Each component has a resistance and this can be measured with a multimeter. When two components are connected in series, a current will flow and a voltage will develop across each item.

More voltage will develop across the item with the higher resistance and the addition of each voltage will always equal the supply voltage.

That's the simple answer.

There is a little more involved . . . It is the word CURRENT. Here is an explanation:

Suppose we have a 1k and 2k resistor on a 12v supply. The voltage at the join will be 4v.

In other words, there will be 4v across the 1k and 8v across the 2k.

If we have a 10k and 20k resistors in series, the voltage will also be 4v at the join.

If we have a 100k and 200k resistors, the voltage will also be 4v at the join.

The voltage will be the same in all cases, but the current will be different. The current in the second case will be one-tenth and only one hundredth in the third case.

If you want to go further, place a one ohm and two ohm in series and get 4v. But the resistors will get very hot and burn out very quickly.

SOLDERING

Here are three 30-minute videos on soldering.

1. **TOOLS**
2. **Soldering components**
3. Soldering **SURFACE MOUNT** components

TESTING A MOTOR

Strictly speaking, a motor is not an electronic component, but since a website gave a useless description on testing motors, I have decided to supply the correct information.

The only REAL way to test a motor is to have two identical motors and check the torque by connecting them to a low voltage and trying to stop the shaft with your fingers. This will give you two results. Firstly it will let you know the torque of the motor.

This is the twisting effect of the shaft. There is no way to determine the torque by knowing the voltage or current.

The unknown factor is the strength of the field magnets (permanent magnets) and this determines the torque.

Secondly, feeling the shaft will let you know if the torque is even for a complete revolution.

By having two identical motors, you can see if one has a lower torque.

Almost nothing can go wrong with a motor except for the brushes. If the brushes wear out, additional resistance will be produced at the interface between the brush and commutator and this can be detected by allowing the shaft to rotate slowly and feeling the resistance as it revolves. A 3-pole motor will have three places where the strength is greatest and each should have the same feeling. A 5-pole motor will have five places of strength.

If the strength is weak or not uniform, the motor is faulty.

You cannot test a motor with a multimeter as the resistance of the armature winding is very low and if the motor is allowed to spin, the back voltage produced by the spinning, increases the reading on the meter and is false.

Micro motors have a coreless armature. This means the 3 windings for the armature are wound on a machine then bent slightly into shape and glued. A circular magnet with 3 poles is in the centre and the armature rotates around this.

This type of motor is reasonably efficient because the armature is the greatest distance from the point of rotation, and the motor reaches full RPM very quickly because the armature has very little inertia.

I have not heard of the armature-winding flying apart but if you hear any scraping noise, it may be the winding.

3-pole, 5-pole and micro motors can be found in printers, eject mechanisms of CD players, toys, RC helicopters, cars etc and rarely fail.

Motors do not work on "voltage." They actually work on CURRENT and as you increase the voltage, more current will flow and produce a stronger magnetic field (by the winding on each pole). This magnetic field will be attracted by the permanent magnet surrounding the armature and repelled by the surrounding permanent magnet, depending on where the face of the pole is, during each revolution.

If the permanent magnet is not very strong, the repulsion part of the interaction will be very weak and thus the torque will be small.

Because motors work on "current" you must have a high current available when you increase the voltage as the motor will require short bursts of high current during each revolution.

It is the combination of voltage and current (called watts) that gives the motor "strength" (torque) as well as the "strength" of the permanent magnets (called the field magnets) and the number of turns of wire on each pole (and the gauge of wire).

Basically, if a motor is hard to spin, and has 3 "hard spots" on each revolution, it will be powerful.

A 2-pole motor does not self-start and will spin in either direction. But a 3-pole motor will self-start and you can determine the direction of rotation.

A 5-pole motor has a lower RPM. It is slightly smoother in output but is not more powerful than a 3-pole version.

A motor with "permanent magnets" is called a DC motor as it will not work on AC. If the magnets are replaced with a coil, it will work on AC and it will be called a "shunt wound" motor of the field coil is connected across the same terminals as the brushes or a "series wound" motor if the field coil is in series with the armature.

TESTING COMPONENTS "IN-CIRCUIT"

You can test components while they are IN CIRCUIT, but the surrounding components will have an effect on the results.

You can get all sorts of "In-Circuit" testers. They are expensive and offer little more accuracy than a multimeter.

In-Circuit testing with a multimeter can give you the same results as a tester.

All you have to do is turn the project ON and use a multimeter (set to voltage) to determine the voltage at various points. It is best to have a circuit of the equipment so you can what to expect at each point.

Only major departures from the expected can be located in this way.

Obviously the first thing to look for is burnt-out components. Then feel components such as transistors for overheating.

The look for electrolytics that may be dry. Sometimes these have changed colour or are slightly swollen.

If they are near hot components, they will be dry.

For the cost of a few dollars I change ALL THE ELECTROLYTICS in some pieces of equipment, as a dry electrolytic is very difficult to detect.

Testing a transistor "in-circuit" is firstly done with the supply ON. That's because it is quicker.

Measure the voltage between ground and collector.

In most cases you should get a voltage of about half-rail. If it is zero, or close to rail voltage, you may have a problem.

Turn off the supply and use the multimeter on low-ohms to measure all six resistances between the leads.

A low resistance in both directions on two leads will indicate a fault.

Resistors almost NEVER go "HIGH." For instance, a 22k will never go to 50k.

However a low-value resistor will "burn-out" and you will read the value of the surrounding components.

Don't forget, some low-value resistors are designed to burn-out (called fusible resistors) and anytime you find a damaged low-value resistor, you will need to look for the associated semiconductor.

You can replace the resistor quickly and turn the circuit ON to see it burn out again. Alternatively you can trace though the circuit and find the shorted semiconductor. It's always nice to "see the fault" then "fix the fault."

Sometimes a transistor will only break-down when a voltage is present, or it may be influenced by other components.

When the piece of equipment is turned OFF, you can test for resistance values. The main thing you are looking for is "dry joints" and continuity. Dry joints occur around the termination of transformers and any components that get hot. Rather than wasting time checking for dry joints, it is better to simply go over the connections with a hot iron and fresh solder.

You may need to check the continuity of a track (trace) and it may go from one side of the PC board to the other.

Use a multimeter set to low-ohms and make sure the needle reads "zero-ohms."

It is very dangerous to do any testing on a project using a multimeter set to "amps" or "milliamps."

You cannot test "current flowing through a component" by placing the probes across a component. You will simply over-load the rest of the circuit and create a problem.

To find out if current is flowing though a circuit or a low-value resistor, turn the project ON and measure the voltage either across the component or the voltage on one end then the other.

A voltage-drop indicates current is flowing.

That's about it for testing "in-circuit." Use the rest of this eBook to help you with diagnosis.

Don't think an IN-CIRCUIT COMPONENT TESTER is going to find a fault any faster than a multimeter. They all use a multimeter principle.

SHORT CIRCUIT

Nearly every component can fail and produce an effect called a SHORT CIRCUIT.

This basically means the component takes more current than normal and it may fail completely or simply take more current and the operation of the circuit may be reduced only a small amount.

The resistance of the component may reduce a very small amount but this may have a very large effect on the operation of the circuit.

For instance, two turns in the horizontal or vertical winding of a yoke on the picture tube or monitor may arc and weld together and reduce the size of the picture on the screen, but measuring the winding will not detect the difference in resistance.

The same with the windings on a motor and a short between two winding in a transformer.

If the "short" is between two near-by turns, the change in resistance will be very small. If the "short" is between to different layers, the resistance will be reduced and it may be detected.

When a "short" occurs, the winding turns into a transformer. To be exact, an AUTO-TRANSFORMER.

In the following diagram you can see a normal winding in fig A:

A



B



C



D



Fig B shows two turns touching each other and if the wire is enamelled, the coating has been damaged so the copper wire from the two turns is touching. This is called a SHORTED TURN.
In fig C you can see two turns touching.
In fig D the shorted-turn has been moved to the other side of the symbol to show the effect it has on the operation of the winding.
The shorted-turn is exactly like the secondary of a transformer with a "jumper" across the output.
This will produce a very high current in the secondary.
A very high current flows through the shorted turn and this changes the operation of the rest of the winding.

1. In most cases a SHORT CIRCUIT can be detected by feeling the additional heat generated by the component.
2. Next, turn off the supply and measure the resistance of the component. If it is lower than expected, the component will be faulty.
3. Next, measure the voltage across the component. If it is lower than normal, the component will be faulty.
4. Next, measure the current taken by the component. If it is higher than normal, the component will be faulty.
5. If the component is an inductor, such as a motor, coil or transformer, you can use an inductance meter. Compare a good winding with a faulty winding. Sometimes the fault will disappear because an arc develops across the fault when the component is operating.

INTERNAL AND EXTERNAL SHORTS

An **internal short** refers to two windings shorting together and the winding has a very high resistance between the winding and the frame on which it is wound. An external short refers to a winding shorting to the frame of the component - such as one of the armature windings shorting to the metal core, around which the wire is

wound.
This may not be important unless another winding shorts to the metal frame and creates "**inter winding**" problems (**inner winding** problems is within the same winding).

The opposite to a short circuit is an OPEN CIRCUIT.

This is generally a broken lead or contact or a wire that has "burnt-out" or been "eaten-away" by acid attack or galvanic action by water and voltage (current).
1. No current will flow when an OPEN CIRCUIT exists.
2. The voltage on each end of the OPEN CIRCUIT will not be the same.
3. Measure the current across the OPEN CIRCUIT and determine if excess current is flowing.
4. Join the two ends of the OPEN CIRCUIT and see if the circuit operates normally.

> HEATSINKS

This is not an electronic component but it can certainly affect the operation of a circuit.
If you cannot hold your fingers on a heatsink, it is getting too hot. This is because the actual location where the heat is being generated is much hotter than the part you are touching.
Transistors and IC's can withstand a high temperature but if they go above this temp, they BLOW UP.
They also have a shorter life when operating at a high temperature.
The secret to a good heatsink is called an INFINITE HEATSINK.
This is the metal frame of a case.
There are lots of charts and data on choosing a heatsink but they don't take into account two factors:
Sometimes a circuit takes a very high current for a short time and this creates a high temperature gradient. This will cause the transistor to get very hot and fail.
The solution is to have two or more transistors in parallel to separate the "heat spots."
The second problem with designing a heatsink is the unknown location of the heatsink and the air-flow. Products placed on a shelf or in a cupboard will get very little air-flow.
Remember: some transistors are mounted on thermal insulators. This means the transistor will have a voltage on it but the heatsink will be zero voltage.
The temperature of the transistor will be MUCH HIGHER than the heatsink under the transistor and the transfer of the heat from the transistor to the heatsink will be very slow. This can be the cause of the transistor failing. Sometimes the transistor will fail because insulation is high temp plastic and it gets brittle. The plastic can carbonise and leak and sometimes a voltage can flash through the insulator. Some amazing things have happened under these transistors and you may need to pull it apart and replace all the insulation.
Finally, feel the heatsink after 15 minutes and feel right up to the transistor. If you cannot touch the transistor, increase the thickness of the heatsink or use two transistors to dissipate the heat.
To design a heatsink, you have to have some idea of the size of a heatsink for the application.
Charts and data can send you in the wrong direction.
Start with a heatsink twice the recommended size and feel the temp after 15 minutes. Put the project in a cupboard and see how the temperature rises.
If possible, connect the heatsink to the metal case to get added dissipation and if you include fan-cooling, remember the fan will eventually gather dust and reduce its efficiency.
It is very difficult to explain how heat passes through a mica washer or plastic washer, but if the transistor has a copper base, the heat transfer has a value of 400. For aluminium it is 200. If it is steel, the transfer has a value of 50. For a mica sheet it is 1 and for plastic it is 0.1
Even though the sheet is very thin, the transfer is a lot less than metal-to-metal transfer.

Most references state the temperature difference is about one degree C for each watt of heat generated by the transistor.
Don't believe anything you read.
Feel the temperature yourself and if you cannot hold your finger on the transistor, fix the problem.


Plastic Package
Semiconductor Die
Screw
Metal Case
Mica Insulator
Heat Sink
Metal Washer
Nut
Insulating Shoulder Washer

In the end, use a heatsink 50% larger than recommended.

THE END

This is not the full story to learning about servicing. It is just the beginning.
We have only covered the simplest tests and shown how 90% of faults can be found by checking voltages, waveforms and looking for obvious things such as burnt out components, cracks in PC boards.
The author has fixed over 35,000 TV's, radios, stereos, VCRs and all those things that were on the market 30 years ago.
Things have not changed. It's just that some repairs cost nearly as much as buying a new product and half the customers opt for dumping a faulty item and buying the latest "flat screen" version. That's why you have to get things through the workshop as fast and as cheaply as possible, to make a living.

If you want any more devices added to this list, email **Colin Mitchell**.

To help with understanding how a transistor circuit works, we have produced an eBook: **The Transistor Amplifier.** It covers a whole range of circuits using a transistor.


The Transistor Amplifier
by Colin Mitchell
The Transistor Amplifier by Colin Mitchell

Not copyright by Colin Mitchell
You can use any of this material. Please pass this eBook to your friends and let them know that everything on the web is FREE. I have looked at all the "Pay Sites" and found the information they "sell" is available on the web at NO COST.
Nearly all text books are also downloadable for free on "Download.com" etc and when you see a used copy of a $74.00 textbook on Amazon for $12.00 you realise many users have already discarded their copy. A good textbook never gets thrown out or sold for $12.00!!!

See the enormous amount of information on Talking Electronics website

CIRCUIT SYMBOLS

by TALKING ELECTRONICS



AC current: voltage:	ALTERNISTOR TRIAC A TRIAC and 33 - 43v DIAC Main Terminal1 Gate Main Terminal 2	Ammeter (amp meter)
AND Gate	AND Gate	Antenna balanced
Antenna Loop, Shielded	Antenna Loop, Unshielded	Antenna unbalanced
Attenuator, fixed (see Resistor)	Attenuator, variable (see Resistor)	Battery
Bilateral Switch (DIAC)	Bridge Rectifier (Diode Bridge)	BUFFER (Amplifier Gate)
BUFFER (Amplifier Gate)	Buzzer	Capacitor feedthrough
Capacitor non-polarised	Capacitor polarised (see electrolytic)	Capacitor Variable
Cavity Resonator	Cell	Circuit Breaker
Coaxial Cable	CRO – Cathode Ray Oscilloscope	Crystal Microphone (Piezoelectric)
Connectors Plug (male) Jack (female) connected Plug (male) (female)	Crystal Piezoelectric	DC current: voltage:
	Darlington Transistor collector base emitter	Delay Line
	DIAC (Bilateral Switch)	Diode k
Diode - Gunn	Diode - Light Emitting (LED)	Diode Photo Sensitive
Diode Photovoltaic λ	Diode Bridge (Bridge Rectifier)	Diode - Pin
Diode - Varactor	Diode - Zener	Earth Ground
Earpiece (earphone, crystal earpiece)	Electroluminescence el	Electret Microphone (Condenser mic)
Electrolytic (Polarised Capacitor) alternate symbols: (positive on top)	Electrolytic - Tanatalum positive end black band or chamfer 10u tantalum	Exclusive-OR Gate (XOR Gate)
		Exclusive-OR Gate (XOR Gate)
Field Effect Transistor (FET) n-channel also: N-Channel J FET Gate Drain Source	Field Effect Transistor (FET) p-channel also: P-Channel J FET Gate Drain Source	Flashing LED (Light Emitting Diode) (Indicates chip inside LED)

Ferrite Bead 	Fuse 	Galvanometer 
Globe 	Ground Chassis 	Ground Earth 
Heater (immersion heater) (cooker etc) 	IC Integrated Circuit 	Inductor Air Core 
Headphone 		Inductor Iron Core or ferrite core  
Inductor Tapped 	Inductor Variable 	Integrated Circuit 
Inverter (NOT Gate) 	INVERTER (NOT Gate) 	
Jack Co-axial 	Jack Phone (Phone Jack) 	Jack Phone (Switched) 
Jack Phone (3 conductor) 	Key Telegraph (Morse Key) 	Lamp Incandescent 
Lamp - Neon 	LASCR (Light Activated Silicon Controlled Rectifier) 	LDR (Light Dependent Resistor) 
LASER diode 	Light Emitting Diode (LED) 	Light Emitting Diode (LED - flashing)  (Indicates chip inside LED)
Mercury Switch 	Micro-amp meter (micro-ammeter) 	Microphone (see Electret Mic) 
Microphone (Crystal - piezoelectric) 	Milliamp meter (milli-ammeter) 	Motor 
NAND Gate 	NAND Gate 	Nitinol wire "Muscle wire" 
Negative Voltage Connection 	NOR Gate 	NOR Gate 
NOT Gate Inverter 	NOT Gate Inverter 	Ohm meter 
Operational Amplifier (Op Amp) 	Optocoupler (Transistor output) 	Opto Coupler (Opto-isolator)  Photo-transistor output
Optocoupler (Darlington output) 	Opto Coupler (Opto-isolator)  TRIAC output	OR Gate 
OR Gate 	Oscilloscope see CRO 	Outlet (Power Outlet) 
Piezo Diaphragm 	Photo Cell (photo sensitive resistor) 	Photo Diode 
Photo Darlington Transistor 	Photo FET (Field Effect Transistor) 	Photo Transistor 

Photovoltaic Cell (Solar Cell) 	Piezo Tweeter (Piezo Speaker) 	Positive Voltage Connection 
Potentiometer (variable resistor) 	Programmable Unijunction Transistor PUT  gate anode cathode	Rectifier Silicon Controlled (SCR)  Anode Gate Cathode
Rectifier Semiconductor 	Reed Switch 	Relay - spst 
Relay - spdt 	Relay - dpst 	Relay - dpdt 
Resistor Fixed 	Resistor Non Inductive 	Resistor preset 
Resistor variable 	Resonator 3-pin 	RFC Radio Frequency Choke 
Rheostat (Variable Resistor) 	Saturable Reactor 	Schmitt Trigger (Inverter Gate) 
Schottky Diode  (also Shottky) Low forward voltage 0.3v Fast switching also called Schottky Barrier Diode	Shielding  Signal Generator 	Shockley Diode  4-layer PNPN device Remains off until forward current reaches the forward break-over voltage.
Silicon Bilateral Switch (SBS)  T_2 Terminal Gate T_1 Terminal e.g: BS08D T_2 G T_1	Silicon Unilateral Switch (SUS)  Anode Gate Cathode(k) A G k	Silicon Controlled Rectifier (SCR)  Anode Gate Cathode Solar Cell 
Surface Mount  c b c e SOT-23 b c e b e k k k A no connection & LED	Switch - spst Switch - spdt  Switch - dpst  Switch - dpdt  Switch - mercury tilt switch  Spark Gap 	Switch - process activated normally open: normally closed:  Flow Level Pressure Temperature Speaker 
Switch - push (Push Button) 	Switch - push off (used in alarms etc) 	Switch - Rotary 
Test Point  Thermal Probe  **NTC:** as temp rises, resistance decreases	Thyristors:  Main Terminal1 Bilateral Switch Anode Gate Cathode MT2 Anode Gate Cathode DIAC SCR TRIAC TRIAC	Thermocouple  Tilt switch mercury  Touch Sensor 
Transformer Air Core 	Transformer Iron Core 	Transformer (Tapped Primary/Sec) 



Transistor Bipolar - NPN collector base emitter	Transistor Bipolar - PNP emitter base collector	Transistor n-channel Field Effect Gate Drain Source
Transistor p-channel Field Effect Gate Drain Source	Transistor Metal Oxide Single Gate	Transistor Metal Oxide Dual Gate
Transistor Photosensitive	Transistor Schottky - NPN collector base emitter	Transistor Unijunction - UJT Emitter Base 1 Base 2 Unijunction Transistor (UJT) N-type
TRIAC Main Terminal1 MT2 Anode Gate Cathode	Transistor Unijunction - UJT Emitter Base 1 Base 2 Unijunction Transistor (UJT) P-type	Tunnel Diode Unijunction Transistor - UJT Emitter Base 2 Base 1
Varactor varactor diode	Voltage Regulator (7805 etc) in 7805 out out common in 7805	Voltmeter V
Wattmeter W P	Wires	Wires Connected
Wires Not Connected	XOR Gate (exclusive OR)	XOR Gate (exclusive OR) =1
Zener Diode k k	Learn **BASIC ELECTRONICS** Go to: http://www.talkingelectronics.com	

More chapters of this eBook on: Talking Electronics.com


BASIC ELECTRONICS 1A
by Colin Mitchell
BASIC ELECTRONICS 1A by Colin Mitchell
Switch
3v globe
3v battery
wire

For any enquiries email Colin Mitchell

BASIC ELECTRONICS

(this is the Basic Electronics section i.e. Page 1)
(Chapters 1 and 3 are available as .pdf)

Quick Quiz - to see how much you know
Encyclopedia of Components - this is excellent !!!

Page 1: Basic Electronics (this page) - .pdf (1.2MB) or .zip
The capacitor - how it works
The Diode - how the diode works
Circuit Symbols - EVERY Circuit Symbol
Soldering - videos
Page 2: The Transistor
- PNP or NPN Transistor TEST
Page 2a: The 555 IC
The 555 - 1
The 555 - 2
The 555 - 3
The 555 TEST
Page 3: The Power Supply download as .pdf (900kB)
3a: - Constant Current
3b: - Voltage Regulator
3c: - Capacitor-fed Power Supply
Page 4: Digital Electronics

4a: - Gates Touch Switch Gating
4b: - The DELAY CIRCUIT
Page 5: Oscillators
Page 6: Test - Basic Electronics (50 Questions)
Page 7: The Multimeter - using the Multimeter
Page 8: Constructing a Project
Page 9: Inductance

Remember: **the animations do not work in .pdf**

the site is being constantly updated

INDEX

Active HIGH
AND Gate
Battery
Battery - Internal Resistance
Battery Boost
Battery Booster - for a flat battery
Battery Current
Blocking Diode
Breadboard
Bypass Diode
Capacitors
Capacitors in Parallel
Capacitors in Series - non-polar
Cell
Charging A Capacitor
Capacitor Charging
Capacitor Charging - more details
Capacitors on Volume Control
Capacitor - values
Characteristic Voltage drop - LED
Chassis
Circuit
Circuit - Drawing
Component - Symbols more
Current - milliamp
Current Divider Circuit
Cutoff and Saturation
Damage A LED
DC Current
DC Voltage
Digital States
Diode
Diode - how a diode works
Drawing A Circuit
Earth Rail Earth Rail
NAND Gate
Negative Voltage
NOR Gate
Non-polar Capacitor (electrolytic)
NOT Gate
Ohm's Law
Passive Components
Piezo
Plant Watering Circuit
PNP Transistor
Power and Energy
Power Rail
Potentiometer
Protection Diode
Questions
Regeneration
Resistance - Multimeter
Resistor Colours
Resistors In Parallel
Resistors in Series
Resistor Wattage
Robot Man
Robot Man Animation
Schematic
Slide Switch
Short Circuit
Soldering
Soldering Iron
Speaker
Supply Rail
Switch
Symbols more - components
Tap A Piezo
Test A Cell
Testing A LED

Earth Return
Electret Microphone
Electrolytics
Energy in a cell
Flashing LED Flashing LED
Forward Voltage Drop
Gates with Diodes
Globe
Ground
How a Transistor turns ON
How to Solder
LED
LED flat spot (cathode)
LEDs in Parallel
LEDs in Series
LED Resistors
LED Voltages
Light Dependent Resistor
Load Resistor
Memory Cell
Microphone - Electret
Milliamp - current
Multimeters
Time Delay
Time Delay Animation
Toggle Switch
Tolerance - resistors
Transformer Feedback
3 - Transistor Circuit
Transistor NPN and PNP
Transistor - how it works
Transistor Tester
Turning ON a Transistor
Variable Capacitors
Variable resistor - potentiometer
Voltage
Voltage - Analogue Multimeter
Voltage - Digital Multimeter
Voltage Divider Circuit
Wattage of a Resistor
White LED Voltage
Wire
50 Questions

KIT OF PARTS

Talking Electronics supplies a kit of parts that can be used to build the majority of the circuits in this eBook.
The kit costs $15.00 plus postage.

Kit for Transistor Circuits - $15.00

BUY NOW

A kit of components to make many of the circuits described in this eBook is available for $15.00 plus $7.00 post.
Or email Colin Mitchell: talking@tpg.com.au

The kit contains the following components:
(plus **extra** 30 resistors and 10 capacitors for experimenting), plus:

3 - 47R
5 - 220R
5 - 470R
5 - 1k
5 - 4k7
5 - 10k
2 - 33k
4- 100k
4 - 1M
1 - 10k mini pot
1 - 100k mini pot
2 - 10n
2 - 100n
5 - 10u electrolytics
5- 100u electrolytics

5 - 1N4148 signal diodes
6 - BC547 transistors - NPN - 100mA
2 - BC557 transistors - PNP - 100mA
1 - BC338 transistor - NPN - 800mA
3 - BD679 Darlington transistors - NPN - 4amp
5 - red LEDs
5 - green LEDs
5 - orange LEDs
2 - super-bright WHITE LEDs - 20,000mcd
1 - 3mm flashing LED
1 - mini 8R speaker
1 - mini piezo
1 - LDR (Light Dependent Resistor)
1 - electret microphone
1m - 0.25mm wire
1m - 0.5mm wire
1 - 10mH inductor
1 - push button
5 - tactile push buttons
1 - Experimenter Board (will take 8, 14 and 16 pin chips)
5 - mini Matrix Boards: 7 x 11 hole,
11 x 15 hole, 6 x 40 hole, surface-mount 6 x 40 hole board and others.

Photo of kit of components.
Each batch is slightly different:



There are more components than you think. . . plus an extra bag of approx 30 components. The 8 little components are switches and the LDR and flashing LED is hiding.
In many cases, a resistor or capacitor not in the kit, can be created by putting two resistors or capacitors in series or parallel or the next higher or lower value can be used.

BEFORE WE START

Too many text books start with the physics of the atom and have equations and mathematics to show how smart the author is.
Don't worry, we wont have any physics or equations.
The reason . . .
This is not a physics course. It is a practical electronics course to teach the basics as quickly as possible. There are no equations because most transistor circuits cannot be worked out mathematically as the gain of a transistor changes according to the current-flow and these gain-values are never provided. So the mathematics is worthless.
To get an answer, all you have to do its build the circuit and measure the values with a multimeter.
Also lots of discussions in text books will never be used in your next 40 years of electronics, so this course doesn't have any unnecessary material and is much-more concentrated than anything you have read before.
Every frame contains important points - especially the animations - as they show you how a circuit works in slow-motion - something that has NEVER been done before.

ELECTRONICS BLOCKS

Here is an idea from Instructables to produce blocks with screws, containing a single component and they can be connected with jumper leads (alligator clips).







Use a slotted head for the negative screw and a philips head for the positive screw.

Learn electronics from the beginning . . .

START HERE:

All electrical and electronic components need wire to connect them to the circuit.
In a diagram called a CIRCUIT DIAGRAM, the wires are drawn as lines.
When the wires (or lines) cross, they may be joined or just passing.
It is **VERY IMPORTANT** to show the difference between lines that are **JOINED** and lines that are **NOT JOINED**.
When the lines are joined, it is best to place a dot



Fig 1 The wire in a circuit diagram

on the connection to PROVE the lines are joined. When the lines are just crossing, a gap should be made so it is obvious that one wire goes under the other and does not touch.
Lines should be "across the page" or "up and down." Very few lines should be at 45°.
You can make a line thicker to indicate a power rail or a wire that will be thick in reality.

to Index



Fig 2 A single Cell and many Cells

Next we need a **battery**. A battery consists of two or more cells. The positive terminal of a battery is the long line in the diagram and you must add the voltage (of the cell or battery) to the symbol as a single cells can be 1.2v, 1.5v, 2.2v or up to 3.6v.
The symbol does not let you know the voltage.
The positive is always at the top and is the longest line on the battery symbol.

to Index



Fig 3: A Globe

Next we need a globe. A globe has two connections (a fine wire inside a glass bulb glows when the globe is connected to a battery).

to Index



Fig 4: A Circuit

With a globe, battery and wire we have produced a **CIRCUIT**.
A **CIRCUIT** is a complete path and we say the "electricity" the **CURRENT** emerges from the positive of the battery, moves through the globe and returns to the battery via the wire.
If the globe is a "3v GLOBE" it will glow when connected to a 3v battery.
The globe can be connected either way around.
The circuit we have shown is called a **SCHEMATIC** and consists of symbols: a globe symbol and a battery symbol.
The line connecting the two components is called WIRE.

to Index



Fig 5:Adding a SWITCH
To turn the globe ON and OFF we need a SWITCH.
The switch may be a push button, a toggle switch (a "click" action) or a slide switch. You could

twist the wires together and untwist them. The result is the same. We say the circuit is "broken" or "open" via the switch and the lamp does not glow. Closing the switch turns ON the globe.

to Index



Fig 6: Naming the RAILS

The top rail of the **CIRCUIT DIAGRAM** is called the **SUPPLY RAIL** or **POWER RAIL**.
The lower rail is called the **0v Rail** or **EARTH RAIL**.
Do not connect the Supply rail (+12v) to the 0v rail as this will cause a high current to flow and is called a **SHORT CIRCUIT**:



to Index



Fig 7: The **EARTH RAIL**

The lower rail is also called the **Chassis**.
This comes from the "old days" when electronics constructors build radios on a metal chassis (metal box) and it was connected via wire to a pipe in the ground to help the radio pick up distant radio stations.
The term also comes from car and truck wiring where one side of each globe is connected to the frame or chassis so that only one wire is needed to each globe and the return "path" is via the chassis.

to Index



Fig 7a: Ground

Some circuits identify the "**Ground Lead**" or "**Ground Wire**" of a project to show where all the **signals** have been "referenced to." In other words, all the signals rise and fall above and below this "Ground wire" or "Ground Lead." This lead may not be at **earth potential** as the project may be in a plastic box but it identifies where the earth lead of a Cathode Ray Oscilloscope or the negative lead of a multimeter is connected.
On some printed circuit boards, the negative terminal of the battery (the 0v wire or terminal) is connected to a very large area of copper and this is called the EARTH PLANE or GROUND PLANE. It is designed to prevent signals travelling along the tracks (called traces) being radiated and also prevents outside interference upsetting the project. It also "tightens-up" the earth rail.

to Index

The circuit shows a 12v globe connected to a 12v battery and the circuit appears to be "broken" (not continuous).
But the **current returns** via the earth connection.



Fig 8: EARTH Return

We talk about the **CURRENT RETURNING**. We don't say: the voltage returning.
The voltage of the globe must be the same as the battery voltage, otherwise it will not glow fully or it will **burn out** if it is say a 6v globe.

to Index



Fig 9: Connecting a Motor

The circuit shows a 12v **Motor**.
It is turned ON when the push-switch is pressed.

to Index



Fig 10: Reversing a Motor

If the wires are connected to the motor "around the other way," the motor will reverse direction.

to Index

VOLTAGE AND CURRENT

What is voltage and what is current?
Here is a very simple description.
A battery produces a voltage called DC. (This is a very confusing name because the letter actually refer to Direct Current, so we just say **DC Voltage**).
A battery also produces current called DC - Direct Current. We say **DC current**.

VOLTAGE

Voltage is a value produced by an electrical component called a battery or cell.
A single cell produces one and a half volts. (1.5v) and although this is not a high voltage, when cells are connected together we get higher voltages.
If 6 cells are connected in series we get 9v.
Here is a 9v battery:

CURRENT

You cannot feel current with your tongue so we have to carry out another experiment:



Touch the two terminals with your tongue. You get a tingle. This is a 9v tingle. Now you have "felt" electricity. This is a 9v tingle.

9 VOLTS
2010
Energizer

Place a 22 ohm or 47 ohm resistor across the terminals of the battery and hold your fingers on the resistor. It will get hot. This is the result of current flowing through the resistor and heating it up. The current will be about half an amp and the voltage is 9v, so the wattage will be about 2 to 4 watts. Feel the heat produced.

Milli - milli means 1/1,000th (one thousandth) - such as one milliamp or one millivolt.
In other words one thousand milliamps is equal to 1 amp.
One volts is not a very large value as a battery produces 9v and a cell produces 1.5v to 3.6v (depending on the type of cell.
But 1 amp is a large quality when talking about electronic circuits involving LEDs, motors and transistors.
The globe used in the experiments above requires about 300mA. (1,000mA = 1 amp)
The 3v motor used in the experiments requires about 250mA
The LEDs used in the experiments require about 20mA.
Transistors can pass about 100mA to 800mA via the collector-emitter.
In most cases current-flow in the circuits we will be discussing will be less than 1 amp and will be shown as 25mA, 100mA, 350mA etc.

WATTAGE and CAPACITY

A 9v battery has 6 very small cells and they will not last very long.
A "AAA" cell is larger and a "D" cell is much larger.



A large cell is said to have a **LARGE CAPACITY.** This means it will deliver a larger current for a longer period of time.
The **WATTAGE** of a cell is the multiplication of the voltage x current. The answer is milliwatts or watts.
The **CAPACITY** of a cell is the wattage x hours. The answer is milliwatt-hours or watt-hours. This is also called watt-hours.
You can determine the capacity of a cell (such as a rechargeable cell) by connecting it to a clock-mechanism that has a 4R7 connected across the terminals. The resistor will take a considerable current and deplete the cell in a few hours. The clock will let you know exactly how long the cell delivered the current. You can then compare other cells.

The simplest electrical circuit consists of a battery and resistor. The current flowing through the circuit will depend on the voltage of the battery and the resistance of the resistor R.



The formula connecting these three quantities is:

$$I = \frac{V}{R}$$

Ohm's Law

$$I = \frac{12}{3}$$

$$I = 4 \text{ amps}$$

This is called **Ohm's Law**. Suppose you have a 12v battery and the resistor is 3 ohms. The current flowing through the resistor will be 4 amps.
Increasing the resistance will decrease the current if the voltage remains fixed.

All the above circuits are called ELECTRICAL CIRCUITS because they contain electrical components (such as a motor, globe, relay, switch).
When the circuit contains an ELECTRONIC component such as a diode, transistor, LED, it is called an ELECTRONIC CIRCUIT or ELECTRONIC SCHEMATIC.

to Index

POWER and ENERGY

Here's an easy way to remember the difference between POWER and ENERGY:
A 9v alkaline battery has enough ENERGY to start a car. But it does not have enough POWER (strength).
Energy is effectively the strength of the battery (and this is the voltage and the current it can deliver) multiplied by the time it can deliver this energy. When the answer is obtained, it consists of three factors ((3 quantities) VOLTS, AMPS and TIME.
This results in an answer called xxxx WATT-HOURS.
For a 9v battery the quantities are: 9 volts, 500mA and the battery will deliver this 9x0.5 = 4.5watts for about 1 hour. This is equal to 4.5 x 60 x 60 = 16,200 watt-seconds.
To start a car requires 250 amps from a 12v battery for 5 seconds.
This is: 12 x 250 x 5 = 15,000 watt-seconds.
This means the energy stored in a 9v battery could start a car if all the energy could be delivered in 5 seconds.
This is not possible however the FACT is this: A 9v battery has enough stored energy to START A CAR.

to Index

POWER STATION
300

BATTERY BOOSTER

One of the simplest things we can do is start a car with a flat battery with the assistance of a BATTERY BOOSTER.
This consists of a 12v rechargeable battery in a handy case with leads to connect to the flat battery in your car.
This simple operation puts two 12v batteries in parallel, but no-one has actually described what happens and why.
That's because the explanation is very complex. We have included it here to show that a simple explanation involves a lot of technical terms and you will understand more after reading the course.

The flat battery in the car is not fully charged but it has some percentage of charge and when it sits for a period of time in a non-fully charged condition, the voltage drops from 12.6v to less than 12v as the battery gradually self-discharges due to the potential at the top of the cell being different to that at the bottom of the cell and the specific gravity of the electrolyte being different at the top and bottom. This causes an internal current to flow within the cell and slowly discharge the cell. But if you try to start the car, the voltage drops to less than 7v because the electrolyte cannot carry the high current and a slight potential is developed across the liquid.

The result is the starter-motor does not crank the car.
The reason is this: When the battery is fully charged, the current taken by the starter motor is about 300 amps. This is about 11v x 300 amps = 3300 watts = 4.4Horsepower.
But when the voltage drops to 7v, the current will drop to 190 amps to deliver 1336 watts = 1.8HP. This is only 40% of normal and that's why the car does not start. The engine needs 4HP to overcome the pressure in the cylinders due to the compression of the air during the "firing stroke."
Let's put it this way. If we have a brand new 7v battery, the car will not start. The starter-motor will only accept 190 amps when the supply is 7v.
So, we have to increase the voltage.
We do this by placing a 12v battery across the flat battery. The voltage of the flat battery will immediately rise to 12.6v. It might take 2 minutes but the flat battery will take a small current (1 to 10amps) from the battery in the "booster" and the output of the combination will be 12.6v. The current-carrying capacity of the electrolyte will improve very quickly and you have effectively given the "flat battery" a very quick charge.
The starter-motor will now accept 300 amps from the combination and **SURPRISINGLY** the cells of the "flat battery" will deliver about 200 amps and the booster battery will deliver about 100 amps. The actual sharing of current will depend on the two batteries but the secret behind the success is the increase in voltage we call **TERMINAL VOLTAGE**. The voltage on the terminals (the alligator clips).
The capacity of the booster battery is not important. It can be from 7AHr to 40AHr. We are just using a very small amount of its capacity to start the car and nearly all batteries will provide 200 Amps for a short period of time.
The voltage of the car battery is very important. The Horsepower taken by the starter-motor is defined by the formula: Pwatts = V^2/R Since the resistance remains constant, a voltage of 7 volts will produce 7x7=49 units and a voltage of 11v will produce 121units. This gives the ratio of 40% to 100% as explained above.

to Index



BATTERY BOOST

Continuing from the previous frame where we showed the effect of placing a weak battery in parallel with a good battery, we can show what happens when a weak cell is placed IN SERIES with a good cell.
This also applies when you have 5 good cells and one weak cell.
Basically, the weak cell will reduce the current. In other words, if the 5 cells are driving a motor and supplying 250mA, the 5 cells and 1 weak cell will deliver 200mA or less, depending if it is weak or very weak. The current flowing through the weak cell will have the effect of giving it a small charge - in other words, you will be charging the weak cell from the good cells when the motor is operating.

BUT . . . .

There is a way to use weak cells. If you have say 6 weak cells driving a motor and the RPM is reducing, you can add 2 more weak cells to increase the RPM.
The effect is this: The voltage from the 8 cells will be higher than from 6 cells and this will allow a higher current to flow. Sometimes the cells will provide this higher current and thus more of the energy will be delivered and you will get the last of the energy from the cells.

to Index

INTERNAL RESISTANCE

All batteries and also all individual cells have a "secret, hidden" value of resistance inside each cell due to the resistance of the chemicals. This resistance is very small when the cell is new but it increases as the cell gets older.
It is very easy to measure this value. Simply put an ammeter directly across the cell and measure the current. Use Ohm's law to work out the resistance.
But this not always a wise thing to do as some cells will deliver 10 amps and some will deliver 100 amps and damage the meter.
The diagram opposite shows a large internal resistance for the weak cell and a small internal resistance for the good cell.
If a cell did not have any INTERNAL RESISTANCE it would deliver thousands of amps. It's the Internal Resistance that limits the current.



In most cases we neglect (do not consider) the value of internal resistance when making tests and when using a battery in a project.
But when a battery gets old, it cannot deliver a high current and the internal resistance gets so high that the output voltage drops from say 9v to 7v, even when the battery is not connected to a circuit.
This is the result of the INTERNAL RESISTANCE of the chemicals increasing to a point where they become noticeable and what we call "poisoning" of the chemicals due to the cell "aging" and new chemicals being produced in the cell that have a high resistance. Some of the terms we use are: "drying out and sulphating. Some cells produce spikes or needles that completely short-circuit the cell and make it totally useless.

to Index



This resistor is dissipating 48 watts.
As a comparison, a soldering iron is dissipating about 10 to 20 watts.

RESISTOR WATTAGE

Resistor Wattage means two things.
1. The physical size of a resistor tells you number of watts it is capable of dissipating. This is called RESISTOR WATTAGE. It is really RESISTOR-SIZE or RESISTOR-CAPABILITY.
2. The multiplication of the voltage across a resistor and the current flowing though it will produce a value called WATTAGE. This is also called RESISTOR-WATTAGE or RESISTOR-LOSS or RESISTOR-DISSIPATION or HEAT-LOSS.
In the circuit shown, the wattage being lost in the resistor is:
12 x 4 = 48 watts.
Most of the resistors we will be using in our projects are 0.25watts. This means they will dissipate 250milliwatts, however the actual wattage being dissipated may be only 70 milliwatts and the resistor will not get hot.
0.25watts is the maximum wattage it can dissipate without overheating.
If it is dissipating 400milliwatts, it will be VERY HOT.
The wattage it is dissipating (the heat it is getting rid of) will depend on the supply voltage and the value of the surrounding components.

to Index



Fig 11. The LED

This simple **ELECTRONIC CIRCUIT** contains a **LIGHT EMITTING DIODE (LED), RESISTOR** and battery.

The circuit is classified as electronic because the LED is not an electrical item (such as a globe) but more-complex, as it produces light when current flows through a crystal and the crystal produces the colour.

to Index



Fig 12. **The Resistor**

A **RESISTOR** must be included in the circuit to prevent the LED being damaged.
The resistor in this circuit must be 220 ohms.
This is shown by the colours on the resistor. The colours for 220 ohms: **red - red - brown**. The 4th band is gold - indicating a tolerance of 5%.
A resistor has **RESISTANCE**.
It reduces the current from the battery to a required amount to prevent the LED glowing too bright.
A resistor is just like putting your foot on a hose. The water trickles out the end. The resistor "resists" the high current-flow that the battery is able to deliver.

to Index



Fig 12a. The **Resistor Colours**

There are hundreds of different resistors because the resistance-values need to cover the range one ohm to 10 million ohms.
There are also small, medium and large resistors.
The resistors on the left are just a few in the range. (See the full range below). They show colour bands for 1 ohm to 8.2 ohms and 1 million ohms to 8.2 million ohms. All the other values are shown below.
An electronics engineer does not have the room to store 10 million different resistors so they make each resistor 5% or 10% higher than the previous. This reduces the number to about 100 to 200.

TOLERANCE

The first 3 bands indicate the value of the resistor and the 4th band indicates either 5% or 10% tolerance.
All modern resistors are 5% or 2% or 1%. The "old" 10% resistors are no longer made.
Gold = 5%
Silver = 10%

to Index



Fig 13. The **Resistor and LED**

The **LIGHT EMITTING DIODE** is called an electronic component (mainly because it is more complex than a globe and it produces light by a more-complex means than heating a wire).
A **LED** must be connected around the correct way. It will not illuminate if connected around the wrong way.
All **LEDs** have one lead longer than the other. The SHORT lead is called the **CATHODE** (k).
All LEDs have a flat on one side and this is the **CATHODE** lead.
The arrows on the diagram indicate light is "given off" (emitted - produced).

to Index


Epoxy lens/case
Wire bond
Reflective cavity
Semiconductor die
Anvil
Post
Lead frame
Flat spot
Anode
Cathode
short lead
+
-

Fig 14. The **LED - showing the flat spot**
A close-up of a red LED. The cathode lead is the short lead and next to a flat side on the LED.
DO NOT show "+" or "-" on a diagram. Only show the letter "k" to indicate cathode.
The symbols "+" and "-" are used when a component produces a voltage or is connected directly to "+" and "-" A LED is connected via a resistor.

to Index


k
k
k
k
k
k
red
1.7v
yellow
2.3v
blue
3.3v
white
3.6v
orange
2.1v
green
2.3v

Fig 15. LED VOLTAGES

When a LED is connected to a circuit, (and the correct-value resistor is included), a voltage will be develop across the LED called the **CHARACTERISTIC VOLTAGE DROP**.
This voltage is due to the colour of the LED and the crystal inside the LED that produces the colour.
The diagram on the left shows the approximate voltage developed for each LED.
The voltage **does not change** for small, medium, surface-mount, or large LEDs.

to Index

When a LED is connected to 3v battery, the following **CHARACTERISTIC VOLTAGE DROPs** will develop across each LED.
You will notice we **have not changed** the value of the resistor. It is 220R.
The LED creates the voltage and if the value of resistance is decreased, the LED will illuminate BRIGHTER.
If the LED illuminates too bright it will be DAMAGED.


220 ohm
Resistor
+
3v
k
1.7v
220 ohm
Resistor
+
3v
k
2.1v
220 ohm
Resistor
+
3v
k
2.3v
220 ohm
Resistor
+
3v
k
2.3v

Fig 16. LED VOLTAGES

to Index


220 ohm
Resistor
+
3v

Fig 17. WHITE LED VOLTAGE

If we connect a WHITE LED to 3v supply, it will not illuminate because it needs a supply higher than 3.6v.

The resistor in series with the LED is called a **CURRENT LIMITING RESISTOR**.

In this circuit **no current flows** because the supply is not high enough.

to Index


220 ohm
Resistor
+
4.5v
3.6v

Fig 18. WHITE LED VOLTAGE

When the supply is increased to 4.5v, the 220R resistor will allow a current to flow through the white LED and it will develop a CHARACTERISTIC VOLTAGE DROP of 3.6v across it.

The supply (the voltage of the battery) must be higher than the CHARACTERISTIC VOLTAGE DROP of the LED so the resistor will allow the correct amount of current to flow.
The ideal current for a LED is 20mA, however some LEDs will work when 1mA flows, so you have to know what you are doing.

to Index


10k
very dull
k
+
6v
1k
dull
k
+
6v
10k
no illumination
k
+
6v
LED connected around the wrong way
220R
very bright
k
+
6v

Fig 19. Testing A LED

Now connect either the 1k, 470R or 220R and determine the brightness you need.
As the brightness increases, the current will be higher.
You can use 3v supply for all LEDs except blue and white.

HOW TO TEST A LED

Some clear LEDs produce red or orange and some LEDs do not have the cathode lead clearly identified.
Here's how to find the colour, cathode lead and the current.
You need a 6v battery, 10k resistor, 1k resistor, 470R resistor and 220R resistor.
Connect the 6v battery and 10k resistor to the LED and it will only illuminate when the cathode is connected to the negative of the battery. This is the short lead.

to Index



Fig 20. Damage a LED

Do not connect a 3v battery directly across a LED.
It will be DAMAGED. You MUST include a resistor.

to Index

A LED IS CURRENT DRIVEN

You may have seen this statement and tried to work out what it means.
Basically it means an increase in current will make the LED brighter.
But a LED needs 2 things:
It needs a voltage that is EXACTLY the voltage required to produce illumination. And this voltage depends on the colour of the LED.
As soon as you supply the exact voltage, the crystal will begin to glow and as you increase the current, the illumination will increase.
But doing this is VERY VERY difficult.
It is very easy to supply an exact voltage such as 1.7v or 3.4v, but delivering a current such as 10mA or 20mA at the same time is very difficult. You cannot get a 1.7v battery and deliver 10mA to a LED.
As we have shown above, you need a simple components such as a resistor between the battery and LED to achieve the desired result.
A LED is CURRENT DRIVEN but firstly you need to provide a VOLTAGE that is exactly the connect value for the colour of the LED and then the current can be increased.

to Index


1R0
1R2
1R5
1R8
2R2
2R7
3R3
3R9
4R7
5R6
6R8
8R2
10R
12R
15R
18R
22R
27R
33R
39R
47R
56R
68R
82R
100R
120R
150R
180R
220R
270R
330R
390R
470R
560R
680R
820R
1k0
1k2
1k5
1k8
2k2
2k7
3k3
3k9
4k7
5k6
6k8
8k2
10k
12k
15k
18k
22k
27k
33k
39k
47k
56k
68k
82k
100k
120k
150k
180k
220k
270k
330k
390k
470k
560k
680k
820k
1M0
1M2
1M5
1M8
2M2
2M7
3M3
3M9
4M7
5M6
6M8
8M2
10M
22M
0R1
R22
0R0
zero ohm (link)

Fig 21. All the resistor values

Here are all the colours and values for the resistors you will using in this course. Just match-up the colours on your resistor with the resistors above and you will find the value.

to Index

Resistor values are always OHM values. One ohm is a small value. It might be the resistance of a length of wire 3 metres long.
When a switch is open the resistance is infinite - millions and millions of ohms.
The resistance of your body from one hand to the other will be about 70,000 ohms.
The resistance between two wires dipped in water will be about 1,000 to 100,000 ohms (depending on the dissolved-salts in the water - pure water has a very high resistance)
The resistance of the filament of a 3v globe will be about 30 ohms.
The resistance of the winding of a 3v motor will be about 3 ohms.
Resistors are made with values from less than one ohm to more than 10 million ohms by adding carbon to the mixture inside the resistor (and cutting a track around the outside of the resistor) then connecting a lead to each end. Adding more carbon reduces the value of resistance. Carbon has a low resistance.
Resistance-values are measured with the RESISTANCE settings on a MULTIMETER.
This is called the "Ohms Range." Sometimes with the symbol: **Ω**
A Multimeter will have 2, 3 4 or more scales to cover the range one ohm to 10 million ohms.
Low value resistors (from 1 ohm to 999 ohms) are written as 1R, 220R, 470R, 999R. with the letter "R" indicating Resistance (ohms). You can also use the symbol "omega" **(Ω)**
For values above 1,000 ohms to 99,999 ohms, they are written as: 1k, 2k2, 4k7, 10k, 100k, 220k, 470k, with the letter "k" indicating "kilo" (thousand).
1M = 1,000,000 - one million ohms 1M2, 2M2, 4M7, 10M.
The letters "R, k and M" are placed so they take the place of the decimal point. This prevents any mistake, as a decimal point can be missing in a poor photocopy.

to Index

MULTIMETERS

There are two types of **MULTIMETER**. The top two are called **DIGITAL MULTIMETERS** (DMM) and show numbers on a display.
The lower two meters are called **ANALOGUE MULTIMETERS** and have a pointer and scale.
All meters come with a set of red and black leads.

The **red lead** is always connected to the positive of the battery or the positive on a project and the **black lead** is connected to the negative or earth or chassis.
When making a resistance measurement, the leads can be around either way.
Resistance measurements are always made with the power removed from a circuit. Any voltage on a circuit will upset the resistance reading.

to Index



Fig 22. Resistance Measurement with Analogue Multimeter

The resistance of a resistor is measured by placing the leads of the multimeter on the ends of a resistor and turning the dial on the analogue multimeter to the resistance scale to make the pointer move to about the centre of the scale.
The resistance scale is marked with a high value on the left and 0 ohm on the right. This is opposite to all the other scales.
You must get the pointer to move to the middle of the scale as it is not accurate at left-end.
Analogue multimeters are only suitable for reading values from 1 ohm to 100,000 ohms. The scale is too hard to read above 100k.
To find the value of a resistor, you can compare the colours with the table above.

to Index



Fig 23. Resistance Measurement with a DMM

A digital multimeter produces a more-accurate reading of resistance.
It is accurate from 1 ohm to 10M ohms.
Select the scale that provides a reading.

to Index


220R
k
1.7v
k
1.7v
k
1.7v
+
6v
Use 47R to make the LEDs bright:
220R
k
k
k
+
6v

Fig 24. Connecting **LEDs in series**
LEDs can be placed in series provided the total **CHARACTERISTIC VOLTAGE DROP** across the LEDs is LESS than the supply voltage.
In this case the voltage across the LEDs is 1.7v + 1.7v + 1.7v = 5.1v
The supply is 6v and this allows 0.9v for the CURRENT LIMITING RESISTOR.
The LEDs will not be very bright with 220R.
Change the resistor to 47R
If you connect 4 LEDs in series, the total **CHARACTERISTIC VOLTAGE DROP** will be 6.8v and no LEDs will illuminate because the total is higher than the 6v supply.

to Index


220R
red LED
k
red LED
k
orange LED
k
green LED
k
white LED
k
+
12v

Fig 25. Connecting LEDs in series

Different-colour LEDs can be connected in series. Add up the total Characteristic Voltage for the 5 LEDs and see if it is less than 12v.

The 220R resistor will have to be reduced to 47R to make the LEDs bright.

to Index

LEDs can be connected in parallel if they are the



Fig 26. Connecting LEDs in parallel

same colour.
In the diagram a red LED drops a CHARACTERISTIC VOLTAGE of 1.7v and if they are from the same manufacturer or the same batch, they will work ok.
Although we say the characteristic voltage for a red LED is 1.7v, this can change slightly from different manufacturers and one LED may glow brightly while the other is dull.
You have to build the circuit and see the result.

to Index



Fig 27. Connecting LEDs in parallel

Different colour LEDs cannot be connected in parallel. The voltage across a red LED is 1.7v. This becomes the "Supply Voltage" for the green LED and it is too low. The green LED needs a supply of 2.1v to 2.3v.
Only the red LED will illuminate.

to Index



Fig 28. Connecting Resistors in Series

Suppose you don't have a 220 ohm resistor.
You can make a 220 ohm resistor with two resistors in series. The total resistance will be 200 ohms, but resistors are not accurate and the result will be very close to 220R.
Electronic circuits are not very critical. You will not be able to see the difference in brightness between 200 ohms and 220 ohms.

When resistors are connected in series, the total resistance is found by adding the resistance of each resistor.

$$R_{total} = R_1 + R_2 + R_3 + \ldots.$$

to Index



You can create a 220 ohm resistor by connecting two resistors in Parallel.
When two equal-value resistors are connected in Parallel, the total resistance across the combination is HALF.
470R in parallel with 470R produces 235R.
This is very close to 220R.
We are not going into the formula as it is very complex.
Three equal-value resistors in parallel produce a total of **one-third.**
Simply get two resistors and connect them in

Fig 29. Connecting Resistors in Parallel

parallel and measure them with a multimeter.

to Index



Fig 29a. Two tricky resistor questions

Figure **A** shows three resistors. It looks hard to solve so the middle resistor is turned so it connects directly to the top and bottom rail. Now you can see the circuit is three resistors in parallel. The result is one-third of an ohm.

Figure **C** shows twelve 6 ohm resistors. Replace each group with a 2 ohm resistor, because three 6 ohm resistors in parallel is equal to 2 ohms.



The two left resistors create 4 ohms and the two right resistors create 4 ohms. The result of two 4 ohm resistors in parallel is 2 ohms. The resistance of the circuit does not change if the switch is open or closed.

to Index



Fig 30. Flashing LED

There are some special LEDs that can be connected to 3v to 9v and they flash or produce a range of colours. These LEDs have a chip and resistor inside the body of the LED to produce the effect and allow the LED to operate on a voltage without the need for a current limiting resistor.

to Index


3v
1k
red green orange LED
1mA
3v
220R
red green orange LED
5mA
3v
100R
red green orange LED
10mA
3v
68R
red green orange LED
15mA
3v
47R
red green orange LED
20mA
3v
39R
red green orange LED
25mA
5v
3k3
red green orange LED
1mA
5v
560R
red green orange LED
5mA
5v
330R
red green orange LED
10mA
5v
220R
red green orange LED
15mA
5v
150R
red green orange LED
20mA
5v
120R
red green orange LED
25mA
9v
6k8
red green orange LED
1mA
9v
1k5
red green orange LED
5mA
9v
680R
red green orange LED
10mA
9v
470R
red green orange LED
15mA
9v
330R
red green orange LED
20mA
9v
270R
red green orange LED
25mA
12v
10k
red green orange LED
1mA
12v
2k2
red green orange LED
5mA
12v
1k
red green orange LED
10mA
12v
560R
red green orange LED
15mA
12v
470R
red green orange LED
20mA
12v
390R
red green orange LED
25mA

Fig 31. These diagrams show the resistor needed to produce 1mA to 25mA current through a single LED on 3v, 5v, 9v and 12v supply.

to Index

THE VOLTAGE DIVIDER


470R
6v
470R
6v
+
12v

Fig 31a. Voltage Divider Circuit.

In the circuits above, the resistor and LED are forming a VOLTAGE DIVIDER.
A red LED is dropping 1.7v across it and the resistor is dropping the remaining voltage.
Whenever two (or more) components are placed across a battery, they form a **VOLTAGE DIVIDER**.
Sometimes we want a 6v supply and only have 12v.
We can produce the 6v supply by putting two equal-value resistors across the 12v as shown in the circuit opposite.
We are not going into the mathematics because the selection of the correct value is very complex and the circuit is very wasteful.

to Index

THE CURRENT DIVIDER

The **CURRENT DIVIDER CIRCUIT** is actually a



Fig 31b. Current Divider Circuit.

LOAD SHARING CIRCUIT.
Suppose you are testing a Power Supply and need a 10 watt LOAD. But you only have 5 watt resistors.
Placing two 5watt resistors in parallel across the output of the power supply will allow half the current to flow though each resistor. This is called **CURRENT SHARING** or **LOAD SHARING** and the current is divided (or passed) through each resistor according to the value of resistance.

to Index



Fig 32. **The DIODE**

THE DIODE
The next simple electronic component is the **DIODE.**
It only works when connected correctly.
A DIODE allows current to flow through it when it is connected as shown in the diagram.
A Diode is similar to a one-way water valve.
When the diode is "facing down," the motor spins.
When it is "facing up" the motor does not spin.



The diagram shows the "current path" around the circuit. The current is measured in AMPS and we discuss current as CONVENTIONAL CURRENT.
This is the way current was thought to flow when electricity was born and they said it flows out the POSITIVE TERMINAL of the battery, around the circuit and into the NEGATIVE TERMINAL.
The arrow on the diode shows the current will flow through the diode and allow the motor to spin.
The diode is said to be **FORWARD BIASED**.



There is no flow of current because the diode prevents any current-flow when connected as shown.
The motor DOES NOT WORK.
The diode is said to be **REVERSE BIASED**.

to Index

There are hundreds of different types of diodes.
Power diodes, signal diodes, low voltage diodes, high voltage diodes, high-speed diodes and many other types.
They all do one thing.
They pass current in one direction and if turned around, they **do not pass** any current.


signal diode
k
k
power diode
k
diode symbol
k
current will flow in this direction

Fig 33. A Signal diode and a Power diode



How a diode works

to Index


current
k
protection diode
+
12V AMPLIFIER
12v
k
no current
protection diode
12V AMPLIFIER
12v
+

Fig 34. A Protection diode

Diodes perform many function in electrical and electronic circuits. Here is an application as a **PROTECTION DIODE.**
It protects the amplifier. If the 12v battery is connected around the wrong way, no current will flow.

to Index


current
11.4v
k
12v
protection diode
+
12V AMPLIFIER
12v

Fig 35. Diode "Voltage Drop"

When a diode is placed in a circuit (and current is flowing), a small voltage develops across the diode. This voltage is called the **FORWARD VOLTAGE DROP.**
This voltage is approximately 0.6v.
This is due to a junction inside the diode where two different materials are joined.
Normally, this voltage is not important because it is only small, but sometimes you need to take it into account.
For the circuit above, the amplifier only gets 11.4v

to Index

Voltage is measured with a


11.4
11.4v
k
12v
protection
diode
+
12V
AMPLIFIER
12v

Fig 36. Measuring Voltage with a Digital Multimeter

VOLTMETER.
Multimeters have 2 or 3 voltage ranges so you can measure low voltage (0v to 20v), medium voltages (0v to 200v and high voltages (0v to 500v).
A voltmeter is placed across the component being tested, as shown in the diagram.
The Digital Multimeter is detecting 11.4v across the amplifier.

to Index


- 11.4
11.4v
k
12v
protection
diode
+
12V
AMPLIFIER
12v

Fig 37. Measuring Voltage with a Digital Multimeter

If you place the probes of a digital multimeter around the wrong way on a component, the display will show a "-"
The meter will not be damaged.

to Index


11.4v
k
12v
protection
diode
+
12V
AMPLIFIER
12v

Fig 38. Measuring Voltage with an Analogue Multimeter

An analogue Multimeter must be connected around the correct way to make the pointer move "up scale."
Select the range that will allow the pointer to show somewhere in the middle of the scale.

to Index

Current is measured by


1.35 amp
11.4v
k
12v
protection diode
+
12v
12V AMPLIFIER

Fig 39. Measuring Current with an Analogue Multimeter

"breaking into the circuit" and inserting the leads so the positive probe is closest to the positive of the battery.
If you connect the leads around the other way, the needle will not move but it will hit the "end stop" and you may have to "bump" the meter to get the pointer to move from its jammed position.

to Index


Blocking Diode
–
+
Battery
+
Solar Panel
–

Fig 39a. The Solar Panel and the Blocking Diode

A DIODE is also used with a solar panel to prevent the battery discharging into the solar panel when the sun is not shining.
When the solar panel is not receiving any light it becomes a resistor with a large value and a small current can flow through it from the battery. The diode prevents this current-flow. The diode is called a **BLOCKING DIODE**.

to Index


Blocking Diode
+
Solar Panel
–
Bypass Diode
–
+
Battery
+
Solar Panel
–
Bypass Diode

Fig 39b. The Solar Panel with diodes

Diodes are given different names, according to their function. They all perform the same job by passing current in one direction and prevent current-flow in the opposite direction.
When the top solar panel is shaded by a cloud, it generates less current and this will reduce the current into the battery.
By placing a diode across the panel, the diode will pass the current produced by the lower panel to the battery.
These diodes are called **BYPASS DIODES.**

called BLOCKING DIODES and BYPASS DIODES.

to Index



Fig 40. Capacitors and symbol

The next component we cover is the **CAPACITOR**.

There are thousands of different types of capacitor.

Each value of capacitor can have a low voltage rating, medium voltage or high voltage.

Capacitors can be very small in size and shape or very stable with temperature-rise or simply very cheap to make.

A capacitor consists of two thin sheets of metal such as aluminium with a thin sheet of plastic between.

The sheets may be rolled up in a cylinder or laid on top of each other.

The fact is this: the top sheet of metal does not touch the bottom sheet. This is shown in the symbol.

The resistance between the two terminals is INFINITE.

The 6th capacitor in the top row is called a **MONOBLOCK**.

to Index



Fig 41. Electrolytic Capacitor

A capacitor gets bigger as its value increases.

It also gets bigger when the voltage-rating increases.

The basic unit of capacitance is the FARAD. A one-farad capacitor would be the size of a house. To make the capacitor smaller the sheets are etched to increase the surface-area and different insulating materials are used between the sheets.

The result is a capacitor called an **ELECTROLYTIC**. It is a bit like a rechargeable battery. It stores a lot of energy in a small space.

The negative lead is shorter and has a black stripe on the side of the electrolytic.

to Index

One FARAD is too big to handle. We use smaller values.

The middle of the range is one microfarad. This is written as 1u. (sometimes you see uF)

This is one-millionth of a FARAD.

The smallest value of capacitance is one picofarad. This is one millionth of a microfarad.

It is written as 1p.

Capacitors are broadly separated into two groups. 1p to 1u and 1u to 100,000u

Capacitors 1p to 1u are ceramic, polyester, air, styroseal, monoblock and other names.

Capacitors 1u to 100,000u are electrolytic or tantalum. A tantalum is the same as an electrolytic - for testing purposes - it is a more-compact electrolytic.

1 microfarad is one millionth of 1 farad.
1 microfarad is divided into smaller parts called nanofarad.
1,000 nanofarad = 1 microfarad
Nanofarad is divided into small parts called picofarad
1,000 picofarad = 1 nanofarad.

Recapping:
1p = 1 picofarad. 1,000p = 1n (1 nanofarad) 1,000,000p = 1u
1,000n = 1u (1 microfarad)
1,000u = 1millifarad
1,000,000u = 1 FARAD.

Examples:
All ceramic capacitors are marked in "p" (puff")
A ceramic with 22 is 22p = 22 picofarad
A ceramic with 47 is 47p = 47 picofarad
A ceramic with 470 is 470p = 470 picofarad
A ceramic with 471 is 470p = 470 picofarad
A ceramic with 101 is 100p (it can also be 100)
A ceramic with 102 is 1,000p = 1n
A ceramic with 223 is 22,000p = 22n
A ceramic with 104 is 100,000p = 100n = 0.1u A common 100n is called a **MONOBLOCK**.
A ceramic with 105 is 1u

TYPES OF CAPACITOR
For testing purposes, there are two types of capacitor.
Capacitors from 1p to 100n are non-polar and can be inserted into a circuit around either way.
Capacitors from 1u to 100,000u are electrolytics (or tantalum) and are polarised. They must be fitted so the positive lead goes to the supply voltage and the negative lead goes to ground (or earth).

to Index



Fig 42. Charging a Capacitor

Here is an experiment to show how much (little) energy is stored in a 100u electrolytic.
When the slide-switch is in position "B", the 100u is charged by the 6v battery.
When the slide switch is moved to position "A" the electrolytic supplies energy to illuminate the red LED via the 220R resistor. It will illuminate for a short period of time.
By moving the switch back and forth, you can keep the LED illuminated.

to Index

Capacitors can be connected in **Series or Parallel** to obtain a value of capacitance you may not have available.
They are also connected in series to increase the effective **VOLTAGE RATING**.
However when two equal-value capacitors are connected in series, the final value is HALF, and thus you need two with double the final-value to get a value with an increased voltage-rating.
When two equal-value capacitors are connected in series, the result is HALF.
(This is the opposite to connecting resistors)



Fig 43. Capacitors in Series

to Index



Fig 43a. Non-polar Capacitor

Non-polar Capacitor (electrolytic)

A normal electrolytic must be connected the correct way in a circuit because it has a thin insulating layer covering the plates that has a high resistance.

If you connect the electrolytic around the wrong way, this layer "breaks-down" and the resistance of the electrolytic becomes very small and a high current flows. This heats up the electrolytic and the current increases. Very soon the capacitor produces gasses and explodes.
One big mistake in many text books shows how to make a non-polar electrolytic by connecting two "back-to-back."
They claim 2 x 100u connected back-to-back is equal to 47u.
This appears to be case when testing on a meter but the meter simply charges them for a short period of time to get a reading.
If you allow them to charge fully you will find the reverse electrolytic has a very small voltage across it.
Secondly, when you are charging them, you are putting a high current through the reverse electrolytic and damaging the layer.
To prevent this, you need to add two diodes as shown in the diagram.
In addition, 2 x 100u "back-to-back" is very near 100u.

to Index

Capacitors can be connected in **Parallel** to obtain a value of capacitance you may not have available.
(This does not change the **VOLTAGE RATING**.)
When two equal-value capacitors are connected in parallel, the result is DOUBLE. (This is the opposite to connecting resistors).
If one electrolytic is 25v

and the other 63v, the answer is the LOWER VOLTAGE = 25v.


100p
50v
100p
50v
= 200p
50v
100u
25v
100u
25v
= 200u
25v
470p
400v
470p
400v
= 940p
400v
220u
63v
220u
63v
= 440u
63v
$C_{total} = C_1 + C_2 + C_3 + \cdots$

Fig 44. Capacitors in Parallel

to Index


Variable Resistor
POT
Potentiometer
Variable Capacitor
Trimmer Capacitor
Vertical mini trim-pot
Horizontal mini trim-pot
Air Trimmer
Air Trimmer
Variable Capacitor
10-turn pot
Mini pot
Tuning Capacitor

Fig 45. Variable Capacitors and Resistors

The value of a capacitor or resistor may need to be increased or decreased in a circuit to tune in radio stations or increase and decrease the volume of a speaker. The symbol for these components have an arrow to show they can be adjusted.
The resistance of a potentiometer can be from 1 ohm to 5M
They come in many different shapes and sizes to suit the PC board or front-panel layout.
The "T" represents a trimmer capacitor and this can be from 1p to about 120p.
A variable capacitor will be from about 10p to 415p.

to Index

Simple CIRCUITS
We have covered enough symbols and components to create a number of simple circuits.
These circuits will show how to connect a motor, a LED, (how to make it bright or dull) and how to connect 4 cells to make a battery.

Note: The flashing LED

does not need a resistor because a resistor and chip are inside the LED, to make it flash and control the current.

Connect all the components around the correct way and then connect them around the wrong way to see what happens.
Connect the flashing LED in series with a red LED and see what happens.


4 cell battery holder
black negative
red positive = "+"
+
4 cells
4 cells connected in SERIES to produce 1.5v x 4 = 6v
+
6v
k
Flashing LED
No resistor needed
+
M
6v
reverse connections to motor to reverse direction of rotation
220 ohm Resistor
+
6v
red LED
k
220R
+
green LED
6v
k
red LED
k

Fig 46. Simple Circuits

to Index

QUESTIONS

1. Explain why the Flashing LED circuit has no external resistor.
2. How many 1.5v cells are needed to produce a 6v battery
3. Explain what happens when you reverse the leads to a motor.
4. Identify the positive terminal:



5. Can 3 green LEDs be connected in series to a 6v supply?
6. A variable resistor is also called: ____________________
7. The combined resistance of two 1k resistors in series is: ______________
8. The combined resistance of two 1k resistors in parallel is: ______________
9. Name the short lead on a LED
10. Name the type of multimeter with a pointer and scale: ____________________
11. The total capacitance of two 100u electrolytics in series is: _____________
12. The total capacitance of two 100u electrolytics in series is: _____________
13. Write these values in words:

22R _________
4k7 _________
1n ___________
100u ___________

14. How many 1.5v cells in a 9v battery?

15. The red probe is: _______________ (positive/negative)

16. Conventional current flows from: _________ (positive to negative / negative to positive)

17. Make a 470u electrolytic with two electrolytics:

18. What is the voltage drop across a diode?

19. Name the component that only allows current to flow in one direction: ____________

20. Name this symbol:



21. When resistors are connected in series, the resistance of the combination: _________ (increases / decreases)

22. When two capacitors are connected in parallel, the voltage-rating of the combination: _______________ (increases / equal to the capacitor with the lowest voltage-rating)

23. Draw two 2k2 resistors in parallel.

24. Which is larger: 470R or 22k

25. What is the value of this combination:



26. What is the name of the resistor in series with a LED: ____________________

27. What is the voltage across the amplifier: _________



28. Identify the fault with these circuits:









to Index

Passive Components

All the components shown



Fig 47. Passive Components

on the left are called PASSIVE COMPONENTS. This means they do not amplify.
Write the name beside each symbol.

to Index



Fig 47a. The Potentiometer in action

The Potentiometer is a variable resistor.
It consists of a curved carbon track with a wiper that touches the track and can be turned via a screwdriver or knob.
The wiper is the middle wire on the circuit symbol and it moves up and down as shown in the animation.
When the three leads are connected the symbol is called a potentiometer.
When two leads are connected it is a variable resistor.
When the resistance increases, less current flows through the pot.

to Index



Fig 47b. The Variable Resistor and Potentiometer

There is a difference in operation between a **Variable Resistor** and a **Potentiometer**.
Both will increase or decrease the sound level as a volume control or the speed of a motor or the brightness of a globe, but a Potentiometer will guarantee zero volume or zero brightness when the pot is turned fully anticlockwise (as shown in the animation).
This is because the output will be zero volts, but the variable resistor may still deliver some "energy" (voltage and current) to the circuit when turned fully anticlockwise.

to Index

Potentiometers come in values from 100 ohms to 5 Meg ohms (500R, 1k, 2k, 5k, 10k, 50k, 100k, 200k, 250k, 500k, 1M are most popular).
They come as linear, or logarithmic where the resistance of the track (per mm) is higher at one end. Because our hearing is not linear, these pots can be used as volume controls to produce a gradual (very nearly linear) increase in volume.
Selecting the correct value of resistance for a circuit is VERY complex. If the value is not correct, the volume will not be loud or it will drop to zero before the pot is turned fully anticlockwise. Or

the motor will drop to zero at mid-turn of the pot or it will not reduce in RPM to the desired amount.
The simple answer is to copy a circuit.
Or you can try the whole range of pots and you will find one value is the best.
A Potentiometer can be used in hundreds of different circuits to produce hundreds of different effects, but the actual "thing" that flows between the input and output is a percentage of the voltage. At the same time the current will also be passed to the output at a reduced value. A pot actually delivers BOTH reduced values at the same time and the receiving circuit will be designed to "look for" the change in voltage or current. If the supply voltage is not rising or falling, the "values" are called DC values.
The voltage can also be in the form of a signal (volume). This is called an AC signal.

to Indexx


emitter
base
collector
collector
base
emitter
PNP Transistor
NPN Transistor
PNP type
NPN type
emitter
collector
base
PNP type
NPN type
collector
emitter
base
PNP type
NPN type

Fig 48. The TRANSISTOR

The TRANSISTOR

A TRANSISTOR is an ACTIVE device. It AMPLIFIES.
There are many types of transistor (over 20,000 different types) from hundreds of manufacturers and they have many different names.
We are going to study the simplest.
It has the technical name **BIPOLAR JUNCTION TRANSISTOR (BJT)** but we are going to call it a **TRANSISTOR**.
There are two types in this group: **PNP** and **NPN**.

The type we will study is also called a **SMALL-SIGNAL TRANSISTOR.**

You cannot tell an **NPN** transistor from **PNP** by looking at it. You must test it in a circuit.
In **Fig 65** you will make a **Transistor Tester** project, but first some basic facts:

to Index


large current
LOAD resistor
large current
small current
collector
base
emitter
+
battery

Fig 49. The NPN TRANSISTOR in a Circuit

The first type of transistor we are going to study is the **NPN**.
A transistor has three leads:
BASE, COLLECTOR and **EMITTER**
Basically, a small current enters the base and a large current flows through the collector-emitter leads as shown in the diagram.
The resistor in the collector lead is called the LOAD Resistor.
Sometimes the load is a speaker.

to Index

The transistor is similar to the diagram opposite. A small drop of water entering the base is amplified to produce a loud DRIP from the speaker.


This tap is the base-bias resistor, feeding a small current into the base of the transistor.
drip
drip
drip
drip
DRIP
DRIP
DRIP
DRIP
A battery is similar to a water pump.
Each drop of water turns the transistor ON and produces a "thump" from the speaker.

Fig 50. The Water TRANSISTOR

to Index


220R
bare wire
red LED
k
+
6v
collector
bare wire
base
emitter
NPN Transistor
BC 547 2N 2222
+
6v

Fig 51. One Transistor Circuit

In this experiment we will construct a ONE TRANSISTOR circuit similar to the WATER TRANSISTOR above and observe the results.
Make sure the two leads DO NOT TOUCH. If they touch, the transistor will be DESTROYED.

The transistor is amplifying the current through your finger via the two leads and it will be very dim.

ANIMATION

The lower diagram shows the transistor turning ON when a finger is pressed against the two wires. The finger produces a resistance that turns the transistor ON and this turns the transistor into a smaller and smaller resistor. That's how more and more current flows through the LED and it gets brighter and brighter.

to Index

By adding another transistor we amplify the


10k
220R
c
red
LED
k
b
e
+
6v
collector
BC 547
2N 2222
base
emitter
or any NPN transistors
+
6v

Fig 52. Two Transistor Circuit

current through the finger about 200 times and now the LED will glow bright.

Make sure the bare wires do not touch each other as this will destroy BOTH transistors.

ANIMATION

The lower diagram shows both transistors turning **ON** when a finger is pressed against the two wires.
They both becomes smaller and smaller resistors.
The first transistor allows more current to flow into the base of the second transistor and this is how the second transistor turns on more and more. This allows more current to flow through the LED and it gets brighter and brighter.

[to Index](#)


piece of metal
or copper-clad
printed
circuit board
1M
100k
220R
b
c
e
b
e
red
LED
k
+
6v
collector
BC 547
2N 2222
base
emitter
or any NPN transistors

This circuit has enormous gain.
Each transistor has a gain or more than 200 and the final gain will be more than:
200 x 200 x 200 = 8,000,000
8 MILLION!

The circuit is very sensitive to static voltages in the air or electrical waves such as the waveform produced by the electrical wiring in a house.
Move the project around a room and detect all the electrical signals.



Fig 53. Three Transistors

to Index

You can see the effect of one transistor. It does not do much.
The two transistor circuit allows the resistance of your finger to deliver current into the base of the first transistor and this transistor delivers more current into the base of the second transistor. The result is more collector-emitter current and the LED illuminates.
The three transistor circuit produce an ENORMOUS effect.
It will pick up STATIC ELECTRICITY and all forms of electro-magnetic energy (radiation) and illuminate the LED.

to Index


piece of metal
or copper-clad
printed
circuit board
1M
100k
220R
piezo
diaphragm
+
6v
red
LED
k
b
e
c
b
e
collector
base
emitter
BC 547
2N 2222
or any NPN transistors

Fig 54. Adding a PIEZO

By adding a piezo diaphragm to the output you will be able to hear the hum of the mains.
This is the frequency of the supply into your house. It will be either 50 cycles per second or 60 cycles per second.
The term: "cycles per second" is given the name HERTZ after **Heinrich Rudolf Hertz**, who was the first to prove the existence of electromagnetic waves.

to Index

The Piezo diaphragm is held around the outer edge inside a plastic case and when a voltage is applied to the two leads, the thin plate curves very slightly.
When the voltage is removed, the plate returns to its flat shape.
If the voltage is reversed, the plate curves in the opposite direction.

The curving is due to a thin layer of ceramic material under the plate and


piezo
Plastic Case
Leads
Electrode (silver)
Brass Plate
Piezoceramic Plate
The thin plate curves when a voltage is applied.

Fig 55. The Piezo

then a film of metal is deposited onto the ceramic so a lead can be soldered.

There is infinite resistance between the two leads as the ceramic material is an INSULATOR.
The capacitance between the two leads is approx 22n.
The Piezo is a passive device. It needs a pulse or frequency for it to produce an output.


metal diaphragm
ceramic material
THE PIEZO DIAPHRAGM

to Index


220k
220R
k
collector
any NPN transistor
3v
base
emitter

Fig 56. Plant Needs Water

The **ONE TRANSISTOR CIRCUIT** above can be turned into a detector to show when a plant needs water.
Place the two probes into the soil and water the plant. The LED will turn off. As the water evaporates the LED will turn **ON** to let you know the plant needs watering.

to Index



Fig 57. Tap the Piezo

This experiment produces a pulse from the piezo when it is tapped and the LED illuminates briefly.

The LED can be connected either way around.

This proves the diaphragm flexes when a voltage is applied and also in the reverse situation. A voltage is produces when the diaphragm is tapped.

to Index



Fig 58. Flashing LED and White LED

A flashing LED is not very bright. It can be connected to a transistor and the transistor will drive a very bright white LED.
The transistor is an amplifier.
It is amplifying the current flowing through the flashing LED and supplying a higher current for the white LED.

We cannot discuss any further details of the circuit at the moment because the actual operation of the circuit is quite complex.

At the moment we just need to experiment with simple transistor circuits.

to Index

Fig 59. Soldering Iron

We now come to the point of HELPING YOU WITH CONSTRUCTION.
We have already shown you 6 different circuits and there are many ways to build them.
You can:
1. Solder them.
2. Build them on an Experimenter Board
3. Connect the components with clips or twist the leads together.
It does not matter how you build the circuits.
The fact is this: YOU MUST START BUILDING.
The best soldering iron for a beginner is a CONSTANT TEMPERATURE soldering iron.
It has a dial that can be turned to set the desired temperature.
An ordinary soldering iron GETS TOO HOT. It is not suitable for soldering electronic circuits.
This is something that no-one has mentioned before. An ordinary soldering iron will melt the solder TOO QUICKLY and burn the resin inside the solder and make soldering very difficult for a beginner.
Soldering must be done slowly so the resin in the middle of the solder gets hot and cleans the leads of the components so the solder will "stick."
That's why you must apply the solder to the leads you are soldering and allow the resin to "attack" the leads and clean them.
The cheapest TEMPERATURE CONTROLLED soldering Iron is available on eBay for les than $10.00 (post FREE).
You will also need a small roll of solder (0.9mm) and a soldering Iron stand.
Email Colin Mitchell for links to eBay. (talking@tpg.com.au)
A whole book could be written on the ART OF SOLDERING.
Look on the web for articles and videos on SOLDERING.

to Index

SOLDERING

1. Soldering is very easy and very simple. You just need a **Temperature Controlled Soldering Iron**, **Fine solder** and clean components.

2. Remember this: It is **NOT** the solder you need for a joint, but the **FLUX**. And the flux lasts for only 2 seconds. When the flux is **HOT** it attacks and cleans the joint so that the solder will stick.

3. Turn ON the Temperature Controlled Soldering Iron to a low temperature. Put solder on the tip. It will not melt. Turn up the temperature slightly. Try more solder. As soon as the solder starts to melt, this is your starting point. Turn up the temperature slightly MORE and this is the correct temperature for **small, delicate, fine soldering**.

4. Place a component through a hole and bend the lead slightly so the component does not move. Turn the board over and touch the iron on the component and bring the solder **FROM THE OTHER SIDE** so the solder melts and flows towards the iron.
From start-to-finish, count one-two-three and remove the solder. Count four-five and remove the iron. You will have a perfect joint.
If you are soldering thick leads or large pads on a circuit board, you will need to turn the temperature UP slightly.
You must add enough solder to make the joint "bulge" slightly.
Fine solder (1mm or 0.9mm or 0.8mm) makes the best joint because it is easier to use.
Use a wet sponge to clean the tip or a ball of "Steel Wool." Steel wool is the best.
Here is the steel wool, bending the leads and some examples of poor joints due to insufficient solder:

Steel wool cleans the tip beautifully



Bend the leads before soldering



The joints do not have enough solder and that's why they fractured. Called a DRY JOINT.



More "Dry Joints."

This is the cheapest and simplest soldering iron stand.



This stand is very messy as the spring grabs the iron and makes it difficult to remove from the stand. Test the stand before buying. You will se why not to buy this type of soldering stand. Get one with a "wide mouth" and a heavy stand is best as it does not move.



This photo clearly shows how to hold a soldering iron and solder.

This is NOT a temperature-controlled soldering iron and you can see it is too hot as it is burning off the flux too quickly.
Temperature Controlled Soldering Irons are now cheaper than the JUNK soldering iron shown in the photo. See eBay for prices.

to Index



Photo shows a number of components fitted to the breadboard.

BREADBOARD

The term BREADBOARD refers to any piece of wood or plastic containing pins or pegs or clips or holes where you can build a circuit.
The components can be soldered, twisted clipped or fitted into holes.
Breadboard also means the circuit can be easily pulled apart.
Some breadboards do not have two rows for the positive and negative rails. Connections under the board for the positive rail is shown with a black line in the photo. Connections on the main section of the board are shown with blue lines. Your breadboard MUST look exactly like the photo opposite.
Other breadboards are quite useless.
The breadboard in the photo can be purchased on eBay for less than $5.00 (post FREE).





Fig 60. BREADBOARD and Components

to Index



Fig 61. Jumpers

The components on the BREADBOARD are fitted down the holes and metal strips under the board join each column of 5 holes. If you want to join one hole with another, you can use 0.5mm tinned copper wire or JUMPERS. See photo opposite. Jumpers can be purchased on eBay for less than $3.00 posted.

Email Colin Mitchell for links to eBay. (talking@tpg.com.au)

to Index



Fig 62. Breadboard with Nails

If you don't have a soldering iron or experimental breadboard, you can make your own board with nails. See the photo above. It is a multivibrator circuit and we will be presenting this circuit in a moment. The components can be twisted around the nails and bare wire used to join some of the nails to complete the circuit.

Another method of connecting the components is called BIRD-NESTING. This involves soldering the components "in the air" as shown in the 27MHz transmitter circuit below:



Another way to connect the component(if you don't have a soldering iron), is to wind 6 turns of bare wire around each connection and leaving all the components "in the air." The bare wire can be obtained from hook-up flex. This is plastic coated "wire" containing up to 15 fine strands of wire. Use a single strand for the connections. None of the components will touch each other BY MISTAKE and the circuit will work perfectly. Bird-nesting is a good way to build a quick circuit and test its performance. It might look messy but you can easily change any component.

to Index


1M
100k
220R
piece of metal or copper-clad printed circuit board
c
b
e
BC547
c
b
e
BC547
k
c
b
e
BC547

Fig 63. Wiring the 3-Transistor Circuit using BC547 Transistors
The diagram shows how to connect 3 x BC 547 transistors.
The leads of a transistor can be collector-base-emitter OR
emitter-base-collector and that's why we have provided 2 different wiring diagrams.

to Index


1M
100k
220R
piece of metal or copper-clad printed circuit board
c
b
e
2N2222
c
b
e
2N2222
k
c
b
e
2N2222

Fig 64. Wiring the 3-Transistor Circuit using 2N2222 Transistors
The diagram shows how to connect 3 x 2N2222 transistors.

to Index


1k5
30 turns
40turns
b
c
e
NPN
LED
LED
TEST LED
e
b
c
LED
+
1.5v
30 turns
40turns
1k5


1k5
a
c
b
e
k
k
k
c
b
e
k
1k5
1v5

Fig 65. Transistor Tester

This handy transistor and LED tester can be built to test LEDs and both PNP and NPN transistors.
The project consists of two identical circuits, one for NPN and one for PNP.
You can build just the NPN section and then build the PNP section later.

LED VOLTAGE

We have shown a LED needs at least 1.7v supply for it to operate.
This circuit works on 1.5v and thus the action of the transistor and coil (called a Transformer) MUST be increasing the voltage for the LED to illuminate.
This circuit works on two "actions."
1. Transistor ACTION - this is the action of a transistor providing gain to make the circuit oscillate.
2. Transformer ACTION - this is the action of a coil of wire producing a voltage higher than the

supply voltage when it is turned off.

This circuit is very technical and very complex.
We will be explaining it in a very simple way because this is a **Basic Electronics Course**.

THE TRANSFORMER - the two coils of wire on the left and the two coils of wire on the right.
When the voltage (actually the current) is switched off, the 40 turn coil in either of the circuits in this project; the voltage across the coil rises to more than the 1.5v supply and is in the opposite direction to the voltage of the supply.
The circuit looks to be very simple but it uses an air-cored transformer to produce the voltage needed to illuminate the LED indicators and the circuit only works when the transistor is connected correctly. There are two separate circuits, one for NPN transistors and one for PNP transistors. We will cover the NPN section:
The circuit turns ON when the NPN transistor is fitted and the current through the 30 turn coil and 1k5 resistor turns ON the transistor and produces expanding flux in the 40 turn coil. This flux cuts the turns of the 30 turn coil and produces a voltage in the coil that adds to the supply voltage and increases the current into the base. This turns the NPN transistor ON more. This action continues until the transistor is fully turned ON. At this point the current in the 40 turn coil is a maximum but it is not expanding flux and the 30 turn coil ceases to see the extra voltage. Thus the current into the base reduces and this turns the transistor OFF slightly. The flux produced by the 40 turn coil now becomes collapsing (or reducing) flux and it produces a voltage in the opposite direction to greatly reduce the current into the base. In a very short period of time the transistor becomes TURNED OFF and it is effectively removed from the circuit. The flux in the 40 turn coil collapses quickly and it produces a voltage in the 40 turn coil that is higher than the supply voltage and is in the opposite direction. This means the voltage produced by the 40 turns ADDS to the supply voltage and is delivered to the LEDs to illuminate them.
The NPN circuit has two LEDs in series so that a LED of any colour (including white) can be connected to the TEST LED terminals and it will illuminate. You can use any colour LED for any of the LEDs, however it is best to use either green or yellow or white for the single LED.
The two "coils" are wound on a 10mm dia pen with 0.1mm wire (very fine wire). The loops of tinned copper wire holding the coils on the board are connected to separate lands under the board and MUST NOT produce a complete loop as this will create a “Shorted Turn” and the circuit WILL NOT WORK.
If the LEDs do not illuminate, simply reverse the wires to the 30 turn coil.
The circuit does not need an ON/OFF switch because the LEDs require a voltage of over 2v to illuminate (the orange LED) and the supply is only 1.5v. A red LED needs about 1.5v to 1.7v to operate but when it is in series with a green LED, this voltage is over 3.5v.
All the components fit on a small matrix board 5 holes x 18 holes. A kit of parts for the project is available for $4.00 plus $3.00 postage and ordering details can be obtained by emailing Colin Mitchell. (talking@tpg.com.au)
Build the circuit and test your transistors and LEDs.
We will be covering more on the action of a transistor and the action of a transformer in the discussion below, but it is important to build the circuit and see it working.
It is your first piece of **TEST EQUIPMENT**.

Questions

1. Identify the letters "c" "b" and "e"
2. What type of transistor is tested in the first set of hollow pins?
3. Put a PNP transistor into the first set of hollow pins and try all positions. Does the red and green LEDs illuminate?
4. When both the red and green LEDs illuminate, what is the approximate voltage across the pair?
5. When you fit a red LED to the test-socket, what is the approximate voltage across it?
6. When you fit a red LED to the test-socket, why does the red LED and green LED on the PC board turn off?
7. Why doesn't the project need an on/off switch?
8. The two coils for the circuit on the left is called a TRANSFORMER. Do the connections of the windings have to be connected to the circuit around a particular way?

to Index

ROBOT MAN

This multivibrator circuit will flash the Robot Man's eyes as shown



Fig 66. ROBOT MAN
The ASTABLE MULTIVIBRATOR or "free-running" multivibrator.

in the photo. The kit of components is available from Talking Electronics for $8.50 plus postage. Send an email to find out the cost of postage: talking@tpg.com.au
The photo shows the LEDs flashing.
The circuit is called an **ASTABLE MULTIVIBRATOR** and this means it is not stable but keeps switching from one transistor to the other.
It is also called a **FLIP FLOP** circuit.

to Index



Fig 67. The TIME DELAY

The **TIME DELAY** circuit consists of a Resistor **R** and Capacitor **C** in **SERIES**.
When the switch is closed, the electrolytic (called the CAPACITOR) charges slowly because the resistor only allows a small amount of current to flow.
It's just like charging your mobile phone. The battery takes time to charge because there is a resistor in the circuit to limit the current. If we remove the resistor in the mobile phone, the battery will get too hot when it is being charged but in the **TIME DELAY** circuit, we want the capacitor to charge slowly, because we want a **TIME DELAY.** .

to Index

Fig 68. The charging of a capacitor is the same as building a brick wall.

CHARGING A CAPACITOR

The capacitor in **Fig 67** charges via the resistor **R**.
But the voltage on the capacitor does not rise at a constant rate.
It starts off charging very quickly and as the voltage across it get higher, the voltage increases at a slower and slower rate.
In the photo I am building a brick wall.
I am working at a constant rate.
When I started building the brick wall, I laid 5 rows of bricks (5 courses) in the first hour.
As the wall increased in height, I had to climb the ladder and I could only lay 3 courses an hour and finally the wall was so high I could only lay 1 course per hour.
This is exactly the same as a capacitor charging.
When the capacitor is uncharged, the supply voltage allows a high current to pass through the resistor **R** and the energy quickly fills the capacitor. This results in a rapidly increasing voltage on the capacitor. But as the voltage on the capacitor increases, the difference in voltage between that on the capacitor and the supply is very small and only a small current will pass through the resistor. This means the voltage on the capacitor increases at a slower rate.

to Index



Fig 69. Time Units

It really does not matter how fast or slow or uneven a capacitor charges because most circuits detect a voltage on a capacitor and the time taken to reach this voltage is called the **TIME DELAY**.
But to prevent you thinking the capacitor charges "smoothly" we have to explain what actually happens.
The graph on the left shows the capacitor charging. You can see it charges quickly at the beginning and then charges slowly and then very slowly.
You can see the first part of the graph is fairly "straight" (constant charging) - NOT "straight up and down" but a straight line - and this applies to a voltage of about 63%. The time taken to reach this voltage is called **ONE TIME UNIT** - also called **ONE TIME CONSTANT**. The graph continues for another 4 "time units" (time-constants) and the final voltage is very nearly 100%. (It never reaches 100%.)

to Index



Fig 70. Time Delay Circuit

A **TIME DELAY** circuit needs three things:
1. A Resistor (R)
2. A Capacitor (C)
3. A "Detection Point."

When the switch is pressed, capacitor (**C**) takes time to charge via resistor (**R**) and after a short period of time the voltage at the **DETECTION POINT** is 0.6v and the transistor is TURNED ON. The LED illuminates.

Build the circuit with 100u and 100k and see how long it takes before the LED illuminates.

to Index



In the **ROBOT MAN** project you can see the "**TIME DELAY**" circuit made up of the 100u, 10k resistor and the base of the transistor.

This is one of the most important **BUILDING BLOCKS** in electronics.
It is the basis of all oscillators and will be discussed below, after we explain a few more details.

Fig 71. The "TIME DELAY" in the ROBOT MAN Project

to Index


Push Switch
470R
LED
k
+
9v
100k
c
This is the "detection point"
b
+
100u
e

Fig 72. Turning A Transistor ON

We will use the **TIME DELAY** circuit to turn the transistor **ON**.
Make sure the 100u is uncharged by touching both leads (both ends of the capacitor) at the same time with a JUMPER - this is a piece of wire shown in Fig 61.
Push the switch and noting happens. After a short period of time the LED starts to glow and then comes on fully.
This shows two things:
1. The transistor is not turned ON when the base voltage is zero.
2. The base voltage must be 0.6v for the transistor to start to turn ON and when the voltage is 0.65v the transistor is turned **ON FULLY.**

to Index


Push Switch
470R
+
9v
100k
This is the "detection point"
b
+
100u
e

Fig 73. How the LED turns ON

Here is an explanation of how the LED turns ON.
When the circuit is first assembled and the switch is not pressed, the transistor is not turned on and it is just like the diagram opposite. The LED is not connected to the transistor.

to Index


Push Switch
470R
+
9v
100k
This is the "detection point"
+
100u
b

Fig 74. The LED turned ON

When the switch is pushed, the transistor turns **ON** (after a few seconds) and it pulls the lower lead of the LED down towards the 0v rail and this action turns the LED **ON**.

to Index



Fig 75. The LED fully turned ON

When the LED is **fully turned ON**, the lower lead of the LED is almost directly connected to the 0v rail.
In other words:
When the transistor is **FULLY TURNED ON**, the lower lead of the LED is almost directly connected to the 0v rail.
The voltage between the lead of the LED and 0v rail is 0.2v. This is the characteristic voltage across the collector-emitter terminals of a transistor when it is TURNED ON.

to Index

In the three diagrams above you can see the LED is changed from an **OFF** condition to an **ON** condition by the action of the transistor.
The transistor is acting **LIKE A SWITCH.**
This action is one of the most important actions in electronics.
It is called: **"The Transistor as a SWITCH"**
It is the basis to ALL Digital Circuits.
It is the basis because of these two facts:
1. When the transistor is **OFF**, the circuit is taking **no current** and no power is being lost or wasted.
2. When the transistor is **ON**, the LED is almost at 0v and no resistor is in the lower lead to waste any power.
Thus we can turn things **ON** and **OFF** without wasting and power.
This is the basis to **DIGITAL ELECTRONICS**.

to Index

DIGITAL ELECTRONICS revolves around circuits that are either **FULLY ON** or **FULLY OFF**. This means they take almost no power and we can combines lots of circuits and still take almost no power.
This means they do not get hot and it also means they will last a long time.
You may not think turning a transistor **ON** and **OFF** will achieve any worthwhile outcome but a circuit can be designed to use two transistors (similar to the **ROBOT MAN** above). The circuit does not Flip-Flop but requires a switch and when the switch is pressed, the circuit changes state. The two transistors are connected together and it takes two presses of the switch to make the output of the second transistor change state ONCE.
The circuit is a divider. It is called a: **divide-by-two** and is the basis of all counting in a computer.
By adding more "**divide-by-two"** circuits we can get "**divide by 4**, **divide by 8**" etc. Two transistors don't do much but when you combine millions of transistors we have a **COMPUTER.**

to Index

Two transistors can do one more thing. They can "**REMEMBER**."
Here is a manual circuit.
Pressing Switch **A** turns the LED **ON** and pressing switch **B** turns the LED **OFF**.
The circuit "remembers" or remains in each state called a stable state.



Fig 76. The "MEMORY CELL"

When Switch **A** is pressed, the voltage on the base is removed and transistor **A** turns OFF.
Transistor **B** turns ON via resistors R_1 and R_2 and the LED is turned **ON**.
When the switch is released, the voltage on the collector of transistor **B** is less than 0.6v and the two transistors remain in this state.
Pressing switch **B** turns the LED **OFF.** (transistor **A** turns ON via R_3, R_4 and the LED - very little current flows through the LED and you can hardly see it glowing). The voltage on the collector of transistor **A** is less than 0.6v and the two transistors remain in this state.

The technical name for this circuit is:
BISTABLE MULTIVIBRATOR or **BISTABLE SWITCH** or **BISTABLE LATCH**.

This is the basis to all the memory in a computer.

to Index

In electronics, we talk about the **DIGITAL TRANSISTOR** and **ANALOGUE TRANSISTOR**.
This is just an ordinary transistor (called a Bipolar Junction Transistor) in a **DIGITAL CIRCUIT** or **ANALOGUE CIRCUIT**.
We are now discussing the **DIGITAL CIRCUIT** - The Multivibrator - Astable Multivibrator and Bistable Multivibrator (Memory Circuit).
The **DIGITAL CIRCUIT** has **2 STATES**.
The **ON STATE** and the **OFF STATE**.
It is conducting in the ON STATE and the LED is illuminated.
In the OFF STATE, the LED is not illuminated.
In the ON STATE the transistor is said to be **CONDUCTING** or **BOTTOMED**.
In the OFF STATE the transistor is said to be "**CUT OFF** or "**OFF**."
These two states are reliable and guaranteed. They are not "half on" or "quarter on" or "75% off."
These states are easy to transmit "down a wire." The ON STATE is transmitted as "1" (voltage present) and the OFF STATE is transmitted as "0" (voltage not present).
These are the two **DIGITAL STATES**.

The **ROBOT MAN** is a **DIGITAL CIRCUIT**.
Each LED is ON or OFF.
The waveform on the output of each transistor is called a **DIGITAL SIGNAL**.

The waveform is said to be **DIGITAL** or **SQUARE WAVE**.
The top line of the graph represents the LED OFF.
The bottom line of the graph represents the LED ON. The LED is ON when the collector voltage is LOW because we are pulling the lead of the LED to the 0v rail as shown above.
The circuit changes from one state to the other very quickly and this is called the **RISE TIME**.


R4
LED OFF
k
R3
rise
time
LED ON

to Index


Switch
470R
100k
OFF
Switch
470R
100k
0.2v
ON

Fig 77. The two Digital States

Going over the two **DIGITAL STATES** for a transistor.

In the first diagram the switch is not pressed and the base does not see a voltage to turn the transistor on. The transistor is "**OFF**" (not conducting) and it is not "grabbing" the LED. The LED is not illuminated.
In the second diagram the base of the transistor sees a voltage via the switch and it is TURNED on. The LED is illuminated.

to Index


470R
10k
10k
470R
LED
k
+
100u
+
9v
LED
k
+
100u

Fig 78. ROBOT MAN Animation
This animation shows how a transistor grabs a LED and pulls it towards the 0v rail to turn it ON.

to Index



Fig 79. TIME DELAY Animation

The animation in **Fig 78** shows the two transistors turning the LEDs **ON** and **OFF** in a **FLIP FLOP** circuit.
We know the 10k and 100u components form a **TIME DELAY** to create the time for each LED to be illuminated. The timing for one LED plus the other LED creates a **CYCLE** and this is the **FREQUENCY OF OPERATION** for the circuit. It is measured in cycles per second - Hertz - Hz.
We will now go into more detail of how the **TIMING COMPONENTS** create the **TIME DELAY** for each LED.
The circuit is more-complex than you think.
The 100u is already charged from a previous cycle and we show how it gets discharged via the 10k and charged in the opposite direction by the 10k to create a **TIME DELAY**.

to Index

THE CAPACITOR



The capacitor can perform many different functions and produce many different effects, depending on its value and the surrounding components.
In this circuit the capacitors on the input and output prevent DC on the volume control creating "scratchy sounds" when the volume is altered.
This is called "DC blocking."
The AC (the signal) passes through the capacitors but the DC voltage on the input is blocked.

to Index

CHARGING A CAPACITOR Part II

It is easy to see how a capacitor charges via a resistor in the **TIMING CIRCUIT** (Delay Circuit) above but many capacitors are not connected to the 0v rail.
They are connected as show in the animation below and their "job" is to pass a waveform.
When they pass the waveform they **CHARGE** and **DISCHARGE**.
The waveform is called an **AC SIGNAL** and the output is smaller than the input.
The circuit is taken from the circuit above, but the same effect applies to all capacitors that "pass a signal."
Here's why:



The capacitor charges slightly during the rise of the signal and the right-plate of the capacitor does not rise as high as the left-plate. That's why the output signal is not as large as the input signal.
If the capacitor did not charge, the output would be as large as the input. If you use a capacitor with a large value, it will not charge and thus the output will be as large as the input.
That's why you use a large capacitor !!!!

to Index

CHARGING A CAPACITOR Part III

Here is another CAPACITOR in action.



The animation shows a capacitor charging (via a resistor). The initial current is LARGE and this turns the transistor FULLY ON and the globe illuminates. As the capacitor charges, the base current reduces and the transistor starts to turn OFF. Eventually the capacitor is fully charged and the voltage on the base falls to 0v, turning the transistor OFF.

This animation shows three features:
1. The initial charging current is HIGH.
2. It gradually falls to zero.
3.The voltage on the base drops below 0.6v and the transistor turns OFF.

to Index

NEGATIVE VOLTAGE

You will be surprised to learn that many circuits produce a negative voltage or negative spike at some point (when doing circuit-analysis, each location or point or join of components is called a NODE) on the circuit. In other words the voltage will be LESS than the 0v rail of the circuit.
This is due to the presence of a capacitor and the animation shows how a capacitor can produce a negative voltage:



When a charged capacitor is "lowered from one position in a circuit" the positive lead may be lowered by say 3v. This means the other lead will be lowered by 3v. We are assuming the capacitor can be lowered and is not directly connected to the 0v rail.

You can see the electrolytic produces a NEGATIVE VOLTAGE on the base in the following animation, when the two transistors change states:



to Index

The Electret Microphone

The most common type of microphone is the ELECTRET MICROPHONE.
It is incorrectly termed the "Capacitor Microphone" or Condenser Microphone." "Capacitor Microphone" descriptions make no mention of a FET as the amplifying device and a polarized diaphragm to detect the audio, so they are something different.
The electret microphone consists of a FET (transistor)


air holes
metal housing
Gate
very thin charged plastic sheet
FET
Source
Drain

ELECTRET MICROPHONE


load resistor
output cap
Drain
Gate
Mylar film
Source
case

INSIDE AN ELECTRET MICROPHONE


load resistor
+
NJFET
drain
gate
source
−
+
−

CONNECTING A FET TO THE SUPPLY RAILS


3v - 9v
2k2
22k
100k
Adjust for sensitivity
2M2
100n
electret microphone
BC 547

inside an aluminium case with a very thin Mylar film at the front. This is charged and when it moves (due to the audio it receives via a small hole in the front of the case), it vibrates and sends a very small voltage to the GATE lead of the Field Effect Transistor. This transistor amplifies the signal and produces a waveform of about 2mV to 20mV at the output.
The electret microphone requires about 0.5mA and will operate from 1.5v supply with 4k7 LOAD RESISTOR.
For 3v supply, the Load Resistor can be 22k to 47k.
For higher supply voltages the resistor will be 68k or higher.
Electret microphones are extremely sensitive and will detect a pin-drop at 3 metres.


This lead connects to the case (negative)

Most electret microphones have two leads. One lead is connected to the case and this lead goes to the 0v rail. The other lead goes to a LOAD RESISTOR (4k7 to 68k - depending on the voltage of the project).
Reducing the value of the load resistor will increase the sensitivity until the background noise is very noticeable.
They are used in Hearing Aids and are more-sensitive than the human ear.
They are very small, low-cost and very sensitive.

to Index

The Speaker

The most common speaker is about 30mm to 60mm diameter and 8 ohm impedance. This means the voice coil is about 8 ohms resistance.
The two leads can be connected either way to a circuit.
The speaker shown is 32mm diameter and has a realistic wattage of 100mW (NOT 1watt).

These speakers have a Mylar cone and the magnet is a "super magnet" and very small. That's why it is so flat.



Speaker Symbol

A speaker can be used as a microphone (called a Dynamic Microphone) and a circuit to connect the speaker (mic) to an amplifier can be found on Talking Electronics website. It is not as sensitive as an electret microphone and does not produce the same output amplitude, but it is an emergency microphone.

to Index



LDR and Light Alarm Circuit

Light Dependent Resistor

(LDR)

Also called **PHOTOCELL** or **PHOTO RESISTOR**
A **Light Dependent Resistor** is a 2-leaded component containing a layer of semiconductor material.
The top contains two interleaving combs of conducting wires with a path of semiconductor material between. When light falls on the component, the resistance of the semiconductor material decreases.
In darkness the LDR will be about 300k. In very bright light the resistance will be about 200 ohms.
But if the light changes only a very small amount, the resistance CHANGE is VERY SMALL. For a large change, see **Photo Transistor**.
The **Light Alarm** circuit will produce a squeal when light falls on the LDR.

to Index

Photo Transistor

The **Photo Transistor** is very sensitive to changes in illumination. It is about 100 times more sensitive than the **LDR**.
The **Photo Transistor** is also available as a **DARLINGTON.**
The Darlington Photo-transistor is 100 x 100 times (10,000) more sensitive than the LDR.

The **Photo Transistor** and **Photo Darlington Transistor** are connected just like a normal transistor but the base lead is not connected. If the value of the LOAD RESISTOR is large, the


c
e
b
c
e
Photo Transistor
b
c
e
Photo Darlington Transistor
Lens
collector
tab
collector
base
emitter (tab)
QSE114 Phototransistor (Fairchild)
emitter
collector
BPW96 photo transistor
collector
emitter
SFH 300
(from Siemens data)
photo transistor


collector
flat
emitter
base
collector
flat
emitter
base

FPT100 Photo Darlington Transistor

The FPT-100 Darlington Photo Transistor is available from Talking Electronics for $1.00 each plus postage.

transistor will not be very sensitive.


2k2
Adjust
for
light
level
50k
10u
+
+
V
MEL12
PHOTO
TRANSISTOR

to Index

The Inductor

Also called **"coil,"** or **"Choke."** An **Inductor** consists of one to many turns of wire wrapped around a former (tube of cardboard). The wire can be jumble-wound or wound in layers. The result is the same. This is called an **air-cored coil** or **air-cored inductor**.

The centre can be filled with a metal such as iron or laminations (thin sheets of metal) or a ferrite material. Different cores operate at higher frequencies.

The core can be circular (doughnut) or rectangular and it is called a **MAGNETIC CIRCUIT** (when it is a closed loop).

Additional turns or increasing the diameter of the turns will increase the inductance.

A coil with a magnetic core can be used to pick up nails and metal items. It is called an **electromagnet**. It can be


Air-cored
Air-cored variable
Iron-cored
Iron-cored transformer
Ferrite-cored
Ferrite-cored variable
Ferrite-cored transformer









270
surface-mount
inductor 27uH
yes 27uH
270uH = 271


South pole
North pole

The emerging **magnetic lines of force** from an inductor produce the NORTH POLE - this is just "convention," a simple way to explain things - to get the explanation started.
When two or more coils are wound near each other, the inductor is called a **TRANSFORMER** (but not the armature above).

operated on AC or DC.
When the metal core is loose and gets pulled into the coil it is called a **SOLENOID** or **ACTUATOR** or **LINEAR ACTUATOR**. It can be operated on AC or DC.
The way an inductor works is very complex but we can say it resists any rise or fall in voltage by turning the rise or fall into magnetic flux.
If the applied voltage is suddenly turned off, the inductor produces **a very high voltage** of **opposite polarity** (these are the **two** most important things for you to remember).

to Index

The Antenna

The first time you will need an antenna is when making an FM transmitter.
The antenna is usually a length of wire equal to half the wavelength of the transmitter. The frequency is about 100MHz and the wavelength is 3 metres.
A half-wave antenna is 1.5metres.
The length is important but the height is more important.
The wire should be as high as possible and "up-and-down" if the antenna on the radio is vertical, to get the maximum range.
This is called an **end-fed half-wave antenna** or **half-wave**



Monopole.
The transmitting circuit should have a good ground-plane such as connection to large batteries so the signal can be pushed and pulled into and out of the antenna.
This signal is then radiated as electromagnetic radiation to the surroundings.

to Index

The RELAY

The word **Relay** comes from the days of Morse Code where a coil of wire (an electromagnet) closed a switch to allow the Morse code to travel further down the telegraph line.
It would "relay" or "pass-on" the information.
A relay allows a "weak circuit" (one with low current) to operate a LOAD that needs a large current. It also separates the two circuits electrically and prevents a voltage such as 240v connecting to a 12v circuit. The coil is separated from the contacts and this gives the two circuits isolation.
A double-pole double-throw relay can be used to reverse a motor as shown here:









A single contact consists of 2 pins -called SPST (single-pole single-throw).
Or a single pair of contacts can consist of 3 pins - called change-over or SPDT (single-pole double-throw).
A double set of contacts consists of 6 pins, called DPDT (double-pole, double-throw). This is also called a **CHANGE-OVER RELAY** or **REVERSING RELAY** (when connected to a motor).

to Index

Driving A Relay

(Powering A Relay)
The first thing you must decide is the voltage of the relay. This will depend on the voltage(s) available. The relay will be driven (activated) by a transistor and the base of the transistor only needs a signal (less than about 1v). This means the project can be operated on a voltage from 3v to 12v and the relay can be connected to a 5v to 12v supply.



Driving A Relay



The armature is drawn towards the coil when a current flows through the coil.

Next you need to know the current-rating of the contacts. This will depend on the current taken by the LOAD. The rating of most relays is: 1 amp, 5 amp or 10 amp.
Finally you need to know how many contacts are required.
For a single circuit you will need 2 pins and for two circuits you will need 4 pins (but relays only come with 6 pins).
You can get relays that need a very small current for activation. These are called CMOS relays. But most relays need about 100mA.
To protect the driving-transistor from spikes when the relay is turned off, you will need a diode across the coil.
The top animation shows a "single set of change-over contacts."
The lower animation shows the ARMATURE being drawn to the electromagnet. The electromagnet is the coil with a core of magnetic material that becomes a magnet (an electromagnet) when a current flows through the coil.





When the circuit is turned ON, the voltage across the 2,200u electrolytic is zero and it gradually charges. When the voltage is about 8v, the coil has enough voltage across it to pull the armature and open the contacts. The electrolytic supplies voltage to the coil for about 1 second and then the electromagnet does not have sufficient magnetism to hold the armature and it returns to close the contacts.

to Index

GATES

Animations of **GATES** and more details of their operation is covered in **DIGITAL ELECTRONICS** chapter.

to Index



Fig 80. The "AND" GATE and "OR" GATE with switches

The next **BUILDING BLOCK** we will cover is called the **GATE**.
In its simplest form it is an electrical circuit consisting of switches.
Its just two or more switches connected in series or parallel.
We give each circuit a name so we can talk about it and explain its action with a single word.
Later we will cover the electronic version and show how diodes and a transistor are needed to perform a **GATING FUNCTION.**
The type of GATE we are talking about is a **LOGIC GATE**.
The circuit performs an operation called a **LOGICAL OPERATION** on an input or a number of inputs and creates a single output - called a **LOGICAL OUTPUT**.
LOGICAL means "understandable" or "correct" and in this case it means DIGITAL - the signal will rise to full rail voltage or fall to zero voltage. The output will not be half rail or quarter-rail voltage.
The diagram show an **"AND" GATE** and **"OR" GATE** with switches.
For the **AND GATE** close switch A **AND** switch B for the lamp to illuminate.
For the **OR GATE** close switch A **OR** switch B for the lamp to illuminate.

to Index



Fig 81. The "NAND" GATE and "NOR" GATE with switches and a transistor

INVERSION

Inversion produces the opposite effect to the results above.
Suppose we want to turn OFF a lamp when one or two switches are pressed.
We need a transistor.
The technical word for Inversion is **NOT**.
It is simplified to the letter "**N**."

For the **NAND GATE** close switch A **PLUS** switch B for the lamp to turn OFF.
For the **NOR GATE** close switch A **OR** switch B for the lamp to turn OFF.

These gates are only **demonstration-gates** to show how one or two switches will turn a lamp OFF.

to Index



Fig 82. The "NOT" GATE

NOT GATE

A single switch and transistor produces a **NOT GATE.**
This is simply an **INVERSION**.

The resistor turns the transistor **ON** and the lamp illuminates. The switch removes the voltage on the base and the transistor turns **OFF**.
This is only a demonstration circuit to show how a switch can turn a lamp OFF.

to Index

The 5 gates above form the basis to turning a circuit **ON** and **OFF**. We will discuss these gates later in the digital section.

to Index



Fig 83. "AND and "OR" gate with diodes

The next building block is the **GATING DIODE**.
We have shown a diode allows current to flow when the diode is correctly placed in a circuit and blocks current when it is reversed.
The 5 gates above are electrical circuits but an electronic circuit works in a slightly different way.
The electronic circuit will be covered later in the DIGITAL section.
For the moment we will explain how a diode can be used to create a **GATE**.
In other words it creates a ONE-WAY PATH to allows signals to pass from one stage to another and prevents signals passing in the opposite direction.
In the AND GATE circuit, both inputs are LOW and current flows through the resistor (it will get HOT). When one input is taken HIGH, current still flows through the other diode and the lamp does not illuminate.
When BOTH inputs are HIGH, current flows through the resistor to illuminate the lamp. No current flows through the diodes.
In the OR GATE, when one input is taken HIGH, current flows through the diode to illuminate the lamp.
This can be done with EITHER input.

to Index

A **NAND** and **NOR** gate can be made with diodes and a transistor.
This time we the output is either HIGH or LOW.
We are gradually producing circuits that


R
LOAD
output
+
A
B
NAND GATE with DIODES and Transistor


LOAD
output
+
A
R
B
NOR GATE with DIODES and Transistor

Fig 84. "NAND" and "NOR" gate with diodes and a transistor.

are electronic, rather than electrical circuits.
In the **NAND GATE** circuit, taking one of the inputs HIGH will still allow the other input to prevent the transistor turning ON.
When BOTH inputs are HIGH, the transistor turns on via resistor R and the output is LOW.

In the **NOR GATE** circuit, taking one of the inputs HIGH will turn the transistor ON and the output will be LOW.

to Index


+
BAT2
6.3 V
Q2
2N2222
S_BRIGHT_R
R5
300 Ω
LDR
15 kΩ
R11
20 kΩ
R13
4 kΩ

Drawing A Circuit

A circuit must be drawn according to simple rules so it can be instantly recognised.
An electronics engineer can "**see a circuit working**" when it is drawn correctly and can see if it is drawn correctly; if the parts-values are correct and can use the circuit to assist in diagnosing a problem with a faulty circuit.

The top circuit on is very difficult to visualise because it is not drawn in the normal way.
All the components have to be "**turned around in your mind**," to see what the circuit is doing.



to Index

QUICK QUIZ - to see how much you know

following 50 questions . . . JavaScript is required!

This test will see how much you have learnt.

Easy To Use, All in One, CRM.
1.5 Million Insightly CRM users worldwide.
insightly
TRY FOR FREE

FLUKE CONNECT
Capture equipment performance.
FLUKE.
Learn more

Easy To Use, All in One, CRM.
1.5 Million Insightly CRM users worldwide.
insightly
TRY FOR FREE

2 Layers $10 ea
4 Layers $25 ea
Order Now
RUSHPCB
20 YEARS OF MANUFACTURING EXPERIENCE WITH BLIND AND BURIED VIAS, RIGID FLEX & FLEX PCB
ISO 9001:2008, ITAR, IL LISTED
Locates in Silicon Valley, San Jose, CA

☐ An open circuit help

4. What is the approximate characteristic voltage that develops across a red LED?

☐ 1.7v
☐ 3.4v
☐ 0.6v
☐ 5v help

5. If two resistors are placed in series, is the final resistance:

☐ Higher
☐ Lower
☐ The same
☐ Cannot be determined help

6. Which is not a "common" value of resistance:

☐ 2k7
☐ 1M8
☐ 330R
☐ 4k4 help

7. Which value of resistance, placed across a 9v battery will get hot:

☐ 22k
☐ 22R
☐ 220k help

8. If the voltage on the base of a transistor increases, does it:

☐ Turn on
☐ Turn off
☐ Not enough information
☐ Remain the same help

9. The resistor identified in brown is called the:



☐ Base Bias Resistor
☐ Load Resistor
☐ Emitter Feedback Resistor
☐ Bypass Resistor

help

10. The first three colour bands on a resistor are: yellow - purple - orange

☐ 47k
☐ 4k7
☐ 470k
☐ 4R7 help

11. A resistor with colour bands: red-red-red-gold, has the value:

☐ 22k 5%
☐ 2k2 5%
☐ 220R 5%
☐ 22R 5% help

12. The lead marked with the arrow is:



☐ The Collector
☐ The Base
☐ The Emitter
☐ The case [help]

13. A 10k resistor in parallel with 10k produces:

☐ 10k
☐ 5k
☐ 20k
☐ Cannot be determined [help]

14. The symbol is:



☐ NPN Transistor
☐ PNP Transistor
☐ Photo Transistor
☐ Field Effect Transistor [help]

15. Two 3v batteries are connected as shown.
The output voltage is:



☐ 3v
☐ 0v
☐ 6v [help]

16. 4 resistors in ascending order are:

☐ 22R 270k 2k2 1M
☐ 4k7 10k 47R 330k
☐ 3R3 4R7 22R 5k6
☐ 100R 10k 1M 3k3 [help]

17. The closest value for this combination is:



☐ 4k7
☐ 2k3
☐ 9k4 [help]

18. Which LED will illuminate:



☐ Green
☐ Both
☐ RED
☐ None

19. The four symbols are:



☐ Capacitor, Microphone, Potentiometer, Electrolytic
☐ Electrolytic, Microphone, Resistor, Capacitor
☐ Capacitor, Piezo, Resistor, Electrolytic
☐ Electrolytic, Coil, Resistor, Capacitor help

20. The closest value of the combination is:



☐ 10k
☐ 2k3
☐ 2k5

21. Which motor will work:



☐ A
☐ B
☐ A and B

22. A resistor and capacitor in series is called a:



☐ Pulse Circuit
☐ Timing Circuit/Time Delay Circuit
☐ Oscillator Circuit/Frequency Circuit
☐ Schmitt Circuit help

23. A red-red-red-gold resistor in series with an orange-orange-orange-gold resistor produces:

☐ 5k5
☐ 35,200 ohms
☐ 55k
☐ None of the above help

24. Name the 4 components:



☐ Photo transistor, switch, capacitor, coil
☐ Transistor, mercury switch, piezo, inductor
☐ Photo transistor, reed switch, piezo, coil
☐ Photo Darlington transistor, switch, piezo, inductor help

25. To obtain a higher value of resistance, resistors are connected in:

☐ Reverse
☐ Forward

☐ Parallel
☐ Series help

26. Which LED will illuminate:



☐ A
☐ B
☐ Both
☐ None

27. Name the component that detects light:



☐ mini trim pot
☐ Light Dependent Resistor
☐ piezo
☐ speaker help

28. What is 1,000p?

☐ 0.01n
☐ 0.0001u
☐ 0.1n
☐ 1n help

29. The current in a circuit is 45mA. This is:

☐ 0.045Amp
☐ 0.00045A
☐ 0.0045A
☐ 0.45A help

30. A 100n capacitor can be expressed as:

☐ 0.1u u = microfarad
☐ 0.01u
☐ 0.001u
☐ none of the above help

31. 1mA is equal to:

☐ 0.001A
☐ 0.00001A
☐ 0.01A
☐ 0.1A help

32. 1,200mV is equal to:

☐ 12v
☐ 1.2v
☐ 0.12v
☐ 0.0012v help

33. The approximate current for a toy 3v motor is:

☐ 10mA
☐ 100mA to 300mA
☐ 1 amp

34. What is the resistance of this resistor:



☐ 47k
☐ 4k7
☐ 4R7

35. Identify the correctly connected LED:



☐ A
☐ B
☐ C
☐ D help

36. Identify the correct statement:



☐ The cathode lead is longer. It goes to the negative rail
☐ The cathode lead is shorter. It goes to the negative rail
☐ The cathode lead is shorter. It goes to the positive rail
☐ The cathode lead is longer. It goes to the positive rail help

37. The current requirement of a LED is:

☐ 1.7mA
☐ 25mA
☐ Between 3 and 35mA
☐ 65mA help

38. The multimeter is measuring . . .



☐ Voltage
☐ Current
☐ Resistance

39. The purpose of the two capacitors:



☐ To pass AC from the input to the output
☐ To allow the signal to oscillate
☐ To pass DC from the input to the output
☐ To amplify the signal help

40. The direction of conduction for a diode is:



☐ A
☐ B
☐ C help

41. A DC voltage . . .

☐ rises and falls
☐ is a sinewave
☐ remains constant
☐ is an audio waveform help

42. Arrange these in ascending order: k, R, M (as applied to resistor values)

☐ R, k, M
☐ M, R, k
☐ k, M, R
☐ M, k, R help

43. A battery produces AC current:

☐ true
☐ false

44. The tolerance bands: gold, silver, represent:

☐ 5%, 10%
☐ 10%, 5% help

45. 223 on a capacitor represents:

☐ 0.022u u = microfarad
☐ 22n n = nanofarad
☐ 22,000p p = picofarad
☐ All of the above [help]

46. Arrange these in ascending order: n, p, u
(as applied to capacitor values)

☐ p, u, n,
☐ n, u, p
☐ p, n, u [help]

47. What is the resistance of this resistor:



☐ 100k
☐ 1k
☐ 1M
☐ 100R

48. The number "104" on a capacitor indicates:

☐ 0.1u
☐ 100n
☐ 1n
☐ 10n [help]

49. What is the multimeter detecting:



☐ Voltage
☐ Current
☐ Resistance

50. For the LEDs, what is the characteristic voltage for the red and white LEDs:



☐ 3.6v, 1.7v
☐ 2.4v, 3.3v
☐ 1.7v, 3.6v

☐ Cannot be determined

Final Assessment

THE CRYSTAL-SET RADIO

100 more Crystal Set plans

Everyone wants to make a RADIO.

The simplest radio is a **CRYSTAL SET**. (Sometimes called a **Crystal-Set Radio** or **Xtal Radio Set** or **Crystal Diode Radio**.)

However a **Crystal Set** needs a number of components that are very hard to get: (tuning capacitor with knob) and (crystal earpiece for $1.25).
The "air" TUNING CAPACITOR (20p to 415p) is not easily available and the postage is expensive. The germanium diode is a special component and the aerial coil wound on a ferrite slab is difficult to obtain.

But you don't need these components. They can be substituted.

There are hundreds of websites on the internet describing the **CRYSTAL SET** and if you want to build a "normal" set, you can Google these sites or **100 more Crystal Set plans**. Many of them sell kits too.

But this article is different.

We are going to have all the fun of making a **CRYSTAL SET** but with modern components and easy-to-make components and with an amplifier stage. The output is loud so you don't need a long antenna. And we are going to make our own TUNING CAPACITOR and a very simple aerial coil (called a FRAME AERIAL) as well as replacements for the germanium diode (use a TRF radio IC or a transistor) and in place of hi-impedance headphones (use a piezo diaphragm) and a crystal earpiece equivalent (a piezo diaphragm).
It's even better to have one of each type of component so you can compare the performance, so no matter how many parts your get, nothing will be wasted.

We are also going to explain the fundaments of how the circuit works as even the simplest circuit has a number of very important features that are used in many other circuits.

But first we are going to learn about the components and how they combine to make the circuit work.
When two or more components are connected together they sometimes produce a completely different result to the capabilities of either item.
This is the case with a capacitor and inductor in parallel. An inductor is simply a coil - turns of wire on a cardboard tube - called a former and the centre of the coil is AIR. It is called an air-cored coil or air-cored inductor.
Each component (the coil and capacitor) is called a PASSIVE DEVICE - in other words it does not amplify, but when the are connected together they create a result very near to amplification. And they also produce a result of picking up a huge number of signals and only allowing one signal to appear across the pair. A truly amazing result.

We start by placing a capacitor across the coil.
There is so much activity in the air, from radio, TV, taxi and mobile phone usage that the air is filled with electromagnetic radiation.
This radiation will cut the turns of the inductor (the coil) and produce a microscopic voltage in the turns. This is enough to start the two components passing energy back and forth at a rate

determined by their values. This is the basis of our first discussion.
These two components are called a TUNED CIRCUIT and make up our first building block called THE FRONT END.
.

THE FRONT END

This consists of a coil and capacitor. These two components are in PARALLEL and the signal (called the RADIO SIGNAL or RADIO WAVE) passes through the centre of the coil and produces a voltage in the turns of the coil. The electromagnetic wave has to pass through the centre of the coil.
This voltage is the result of a mass of signals that are interfering with each other and producing a signal called BACKGROUND NOISE.
The voltage can be increased by an external aerial (called an ANTENNA) and it consists of ALL THE LOCAL radio stations (and everything else).
The voltage is a mass of signals and is absolutely useless as it represents all the stations AT THE SAME TIME.
However, across the coil is a capacitor and these signals charge the capacitor with the very small voltage produced by the energy of the signals. When the capacitor is charged, it delivers its voltage to the coil. The coil accepts the energy and converts it to magnetic flux.
After a very short period of time the capacitor becomes discharged and the magnetic flux collapses and produces a voltage in the coil of the opposite polarity to charge the capacitor again in the opposite direction.
These two components keep oscillating back and forth, using the tiny amount of energy from the stations.
There is a natural frequency for the capacitor and coil to pass energy back and forth and one of the stations will provide energy to assist this natural frequency.
When this happens, the amplitude of the signal increases and the signals from all the other stations cancel themselves out and only one signal (waveform) remains.
This signal is called the NATURAL FREQUENCY OF RESONANCE and it corresponds exactly to one of the radio stations.

The end result is a waveform that is the exact same frequency as one of the radio stations and when voice or music is played, the amplitude of the waveform increases and decreases. This will be the signal you hear in the earpiece or speaker.
It is called an AMPLITUDE MODULATED signal and that is where we get **AM RADIO** from.

Understanding the concept of a CAPACITOR and INDUCTOR in parallel is very important. They form a TUNED CIRCUIT that has a natural RESONANT FREQUENCY.
Here is a very similar analogy. You have a heavy metal ball on a long string attached to the gutter on your house - just like a pendulum. You can push the ball very lightly with a finger and after a number of pushes you will be able to get the heavy ball swinging in a very large arc.
The only way to keep it swinging is to push it very lightly at exactly the right time. If you push it at the wrong time it will eventually stop swinging.
The parallel tuned circuit is exactly like the ball. It wants to oscillate at a particular frequency.
All the radio stations are pushing and pulling the circuit at the wrong times and nothing is happening. But one radio station pushes at exactly the right time and the circuit starts to oscillate.
All the other stations are fighting each other just like one person pushing the ball sideways and another pushing the ball from the opposite side. The results cancel each other and you are the only one assisting the swing.
The TUNED CIRCUIT can also be called a FILTER with a very narrow BAND-PASS frequency but our simple explanation describes the operation much more clearly.

There are a few other terms used to describe the components in the font end:

LOOP STICK ANTENNA -This is an alternate name given to the coil of wire wound on a ferrite rod or slab. It also has the name ROD ANTENNA or FERRITE ROD ANTENNA.
The winding can be enamelled wire or flexible wire called LITZ WIRE. This is very fine strands of enamelled wire twisted together and covered in cotton. The purpose of changing a thick wire to lots of very thin wires is to prevent the radio signals creating loops of signals within the wire and these signals will cancel each other and not produce a signal out the end of the wire.
In our experiments, we have not noticed any difference in a coil made with ordinary enamelled wire and Litz wire.

Here is a set of components to make your own Crystal set from **Scott's Electronic Parts**:
You can see the rod antenna, germanium diode, crystal earpiece, capacitor and resistor. The kit costs about $9.00 plus postage and includes knob, clips and screws but no board to mount the parts.

Here is the circuit for a Crystal Set:


Connect Long Antenna Here
Short Antenna Connect Here
O
G
A
Top Side
Variable Capacitor
1N34A
A
Variable Capacitor
G
Ferrite Loopstick Antenna
47K
.001uf
Ceramic Earphone
Ground
This is the FRONT END or TUNED CIRCUIT

Here are the components mounted on a board called BREADBOARD:



The top clip connects to a long antenna. The left clip connects to ground and the right clip connects to a short antenna.

Let me clear up a point. You do not need a ferrite rod antenna for the coil. You can use an ordinary coil wound on a cardboard tube and it will work just as well if you are using an outside antenna.
Here is the circuit using a home-made coil.


10 Turns
45 turns enamelled wire
0.25mm dia to 0.5mm dia
on strong carboard tube
80mm to 100mm diameter
tapped every 5 turns
Aligator Clip
Antenna
This lead goes to a screw on the back of the "frame" of the variable capacitor
Ground
365 pf Variable Capacitor
47k Resistor
Diode
Ceramic Earphone
There are 4 "tabs" (two on each side) of the variable Capacitor.
You can connect to any one of these "tabs". They are all connected to the same place.

The tappings on the coil allow a wide band of radio stations to be tuned.
Each tapping allows a different portion of the band to be covered.

The next part to understand is this:
The coil and capacitor must not be LOADED. In other words, you cannot connect anything to this combination because the signal it is producing will be "taken away" or "removed" or "considerably reduced" by the item you are connecting to the circuit.
These two components are called a TUNED CIRCUIT and when they are not loaded they pick up all the radio stations, one station at a time, when the natural resonant frequency of the coil and capacitor exactly match the frequency of the radio station. The circuit actually "rejects" all the radio stations except one. Because all the other stations are trying to make the Tuned Circuit oscillate at a different frequency and it does not do this.
The result of the TUNED CIRCUIT oscillating under NO LOAD conditions produces a waveform that is very high and this gives the circuit GOOD SELECTIVITY. The circuit can select one station and reject nearby stations.
It also has good SENSITIVITY as it can pick up weak stations.
If you load the circuit, only the strongest signal will be detected and it will be spread across the full range of the tuning capacitor.
Obviously the theory is more-complex but we are explaining the end-result.
Theory talks about the "Q" value of the coil and this is its ability to produce a very good output when the magnetic flux collapses and the "Q" value increases when the circuit is not loaded. .
Although these voltages are very small (in the order of microvolts or millivolts) the result is very important as the rest of the circuit will be amplifying this waveform a few thousand times.
As we explained above, pushing the weight on a string only needs a push of 1 cm and eventually the weight will swing 1 metre. This is a gain of 100:1 The same thing happens with the tuned circuit. The incoming radio signal is in the order of microvolts, but the coil and capacitor will produce a signal as high as 500 millivolts. This is an improvement or "gain" of more than 1,000 and is referred to as the "Q" of the circuit.
You will also notice the TUNED CIRCUIT is not connected to any supply voltage. It does not have

be connected. It generates its own waveform from the signals in the air.
It should not have any DC current flowing through it via the supply as this would put a load on the circuit and reduce its operation.

However we must "pick-off" the signal so it can be amplified.
This must be done with a very high impedance circuit.

THE CONVERTER (detector) - THE DIODE

The next part of the circuit is the CONVERTER. Commonly called the DETECTOR.
It converts the RADIO FREQUENCY signal to an AUDIO FREQUENCY signal.
This is the job of the DIODE.
The radio frequency signal is a very high frequency signal (say one million cycles per second) and it is sending a tone of one thousand cycles per second through the air-waves.
What is happening is this: The one megahertz signal has a certain amplitude and over a range of the first one-thousand cycles, the amplitude gradually decreases and then increases again. If you look at the tops of this 1,000 cycles you will see a waveform that corresponds to the one kilo-Hertz signal.
The 1MHz signal is picked up by the coil and capacitor in the front end and makes it oscillate.
The radio frequency signal is gradually getting larger over 500 cycles then smaller over the next 500 cycles and this increase and decrease represents the 1,000 cycles per second tone.
This is the waveform (the signal) that passes through the diode. This will be explained further in a moment.
The diode does not pass any signals less than 200mV as the first 200mV is lost in the junction of the diode. This means the signals start to appear on the other end of the diode when they are above 200mV.

This is how the diode works:
Across the crystal earpiece is a capacitor. The capacitor gets charged via the diode.
The diode is present to stop the capacitor getting discharged when the waveform is in the wrong direction. (by this we mean - when the waveform is lower or smaller in amplitude than the voltage on the capacitor).
And the waveform is in the wrong direction about 50% of the time. To charge the capacitor for one-half-cycle requires 500 "little increments" in voltage with each increment adding a microscopic increase in voltage. We don't want this voltage to reduce when the waveform is reversing direction and the diode stops the voltage flowing back to the Tuned Circuit.
During the next half of the cycle when the pulses are getting smaller and smaller, the voltage on the capacitor is "bled off" by the load resistor.
The crystal earpiece detects this voltage. What we mean, is the diode allows the voltage to rise (increase) on the capacitor via lots of little "pulses" and the voltage increases in the form of a sinewave to a maximum amount. This voltage is passed to the crystal earpiece.
Once the voltage rises to a maximum, the little pulses of energy are not quite as strong, and the voltage on the capacitor reduces to form the second portion of the sinewave. This voltage is always being passed to the crystal earpiece and you can hear it as an audio signal.

GERMANIUM OR SILICON DIODE

The preferred type of diode for a Crystal Set is germanium. This is because it drops only about 0.3v.
But a silicon diode can be used, even though it drops about 0.7v, if the radio stations are very loud (close by).
You have to remember, you need a very good aerial (and a water-pipe earth) to get any results with a Crystal Set because you are asking the signal to provide the energy to drive the earpiece.
By simply adding a transistor, you are improving the performance 100 times and the long antenna can be reduced to a FRAME ANTENNA and the earth can be the metal frame of your soldering iron.

THE EARPIECE or EARPHONE
also The Magnetic Earpiece or CRYSTAL EARPIECE

The earphone or earpiece used in a Crystal Set must be a high impedance device because the crystal set does not produce a high current and cannot drive a low-impedance earpiece. That's why a CRYSTAL EARPIECE is ideal.
It has a crystal glued to the back of the earpiece and connected to its top surface is an aluminium diaphragm. When the crystal expands and contracts as a result of a voltage applied via two electrodes, the diaphragm moves and you can hear the signal. It exhibits a very high impedance

because it consists of a crystal and no coil of wire is contained inside the case.
If you do not have a Crystal Earpiece, you can make your own from the shell of an 8 ohm earpiece and a piezo diaphragm. Only the front part of the earpiece is used.



Make your own Crystal Earpiece

Hit the 8 ohm earpiece on the side and the front comes off. Glue the front onto a piezo diaphragm with hot-melt glue. See photo above.
The piezo diaphragm is a ceramic substrate that deflects in the presence of a voltage. It is quite sensitive and you can hear the audio quite clearly.
The waveform emerging from the diode in a Crystal Set is called AUDIO and although it has an amplitude of a few hundred millivolts, it does not have any current associated with it. The crystal earpiece and the piezo diaphragm react to this voltage.

THE 8ohm EARPIECE

The 8 ohm earpiece can be used with our 8ohm Buffer stage shown below.

16ohm 32 ohm and 64 ohm EARPIECE(s)

Earpieces and headsets from mobile phones are 16 ohm or 32 ohm per earpiece and are terminated via a stereo 2.5mm or 3.5mm plug. The earpieces are connected in SERIES to get the best coupling to our radio circuits and you need to find the two pins on a stereo socket to produce series connection. Get a multimeter and switch to "ohms." Try all the pins and you will get a click in the left ear then the right ear. Keep searching until you get a click in both earpieces at the same time. Use these two pins.



Stereo mobile phone headset - unusually 32R or 64R

PROBLEMS

The biggest problem with a Crystal Set is the need for a long antenna.
The first 200mV to 300mV of a signal is lost in the diode and you need a long antenna to pick up a signal so the output of the TUNED CIRCUIT has enough voltage to drive the high-impedance earpiece.
This requires an outside aerial 5 metres long and 3 metres high.
This is not practical for most hobbyists so we will be adding an amplifying stage to the crystal set so a shorter (smaller) aerial can be used.

THE FRAME AERIAL or FRAME ANTENNA or FRAME COIL

The aerial coil shown in the photo above is a ferrite slab with about 80 turns of Litz wire. You can find one of these in an old broken AM radio or from a parts-shop. In the instructions below we show how to make your own Ferrite Rod Antenna
An equally-good substitute is a frame antenna made by winding insulated wire in a rectangle around wooden sticks.


40"
2 pieces of 1" x 1"
53" long
8" square
plywood
centre
plate
40"
Slotted
joint
Wooden base
1" dia dowel mast
rotates in
tubing

FRAME ANTENNA



15 turns on a diamond frame



One of the earliest Frame Antennas

The Frame Aerial can be as large as 100cm x 100cm or as small as 10cm x 10cm around a plastic chocolate box.

Here are two FRAME ANTENNAS:



This will work just as good as a ferrite slab antenna. The slab antenna is just 100 times smaller. The slab antenna was invented so a transistor radio could be built in a small case. But if it is not available, you can wind 20 turns around a plastic chocolate box and it will work just as good.

Alternately you can wind 20 turns around a biscuit tin. Put a pencil on the tin and wind the turns over the pencil too. Remove the pencil and it will be easy to remove the turns. Use tape to keep the turns together.

The FRAME AERIAL does two things. It picks up the radio waves and it becomes the coil (called the INDUCTOR) in the TUNED CIRCUIT. It must be placed away from metal objects, such as a refrigerator.

BASKET WEAVE COIL

There is no point making a complex BASKET WEAVE COIL as it will not work any better than simply jumble winding all the turns at the maximum circumference of the coil, because the energy capturing capability of the coil relies entirely on the amount of flux lines passing through the centre of the coil.
By increasing the centre of the coil, the amount of flux is increased for the same coil size.
In fact, the simplest and cheapest is to wind turns around a box, as explained later in this article, or make a frame antenna as shown above. Technically speaking, a round coil has the best performance but only by a few percent.



A BASKET WEAVE COIL

THE VARIABLE INDUCTANCE TUNING COIL

Whenever the size or shape of the coil is changed, (or the number of turns), the natural frequency of the Tuned Circuit will change and a different radio station will be picked up.
This means tuning across the band can be done by altering the characteristics of the coil while keeping the value of the capacitor fixed.
Changing the inductance can be done in many different ways.
The coil can have taps every 5 turns and an alligator clips selects the correct tap. But very few radio stations will correspond exactly to each tap.
Another way is to have a slider move up and down the turns as shown in the following image:



The slider makes contact where the insulation has been removed. But it may touch two turns at the same time and create a "shorted turn" and reduce the "Q" of the coil.

Another way is to move a ferrite bar (rod) in and out of the coil:

THE SLUG TUNED COIL

To tune across the radio band, the natural frequency of oscillation of the TUNED CIRCUIT must be adjusted (changed). This can be done by changing the value of the capacitor or the value of the inductor.

The value of the inductor can be changed by adding or removing turns or changing the amount of magnetic material in the centre of the coil.
A ferrite bar can be screwed in and out of the coil or slid in and out and this component is called a **SLUG TUNED COIL**.
The following diagram shows a **SLUG TUNED CRYSTAL SET**:


120 turns
A
TUNE
ferrite rod
E
TUNE
A
C 100pF
diode
E
Earphone

By changing the value of the 100p capacitor, different parts of the band can be picked up.

The photo shows a slug tuned coil using 60 turns of insulated wire on a 10mm tube (or any tube that will fit over a 8-10mm ferrite rod) and a circuit containing an AM radio chip plus a buffer driver transistor:


R1
100K
R2
1K
R4
100K
T1
BC548B
C1
10nF
C6
560pF
R3
1K
C4
100nF
IC1
TA7642
C3
100nF
C5
47uF
R5
220R
Telefoon
SUPER ALKALINE
www.kristalradio.nl

A SLUG-TUNED RADIO

The circuit above is has a broad-band amplifier consisting of 10 transistors (IC1) and they are directly coupled (connected) to each other because it is not possible to "manufacture" a capacitor inside the IC. The IC has 3 terminals (pins, legs) and it looks like an ordinary transistor.
Experimenting with this type of IC has shown that it is no better than 2 ordinary transistors connected in a direct-coupling arrangement.


R1
100k
R2
1k
slide
IC 1
R3
1k
R4
100k
In
out
TA7642
C4
100n
T1
BC548B
2 x 32 ohm
parallel
C6
560pF
Ground
C2
100 nF
C1
10 nF
C5
47μ
R5
270R
+
1,5 Volt
-

Here is the address of the site for the slug-tuned radio.
http://www.kristalradio.nl/
Unfortunately the site is in Dutch and the kit is not available. However the photos give a clear picture of the how the parts are connected.

The inductance of the coil can also be altered by winding another coil and placing it near the first coil so that the magnetic field interacts with each other and changes the inductance of the circuit. This is called a VARIABLE INDUCTANCE TUNING COIL.
You can have one coil inside the other, two coils near each other or two flat coils side-by-side. Any two coils will interact with each other.





An Inductive TUNING COIL called a VARIOMETER

MAKING YOUR OWN FERRITE ROD ANTENNA

You can make your own FERRITE ROD ANTENNA by winding 60 to 80 turns of 0.25mm enamelled wire onto a 9mm ferrite rod or slab. If you wind it on a paper sleeve, you can move the coil along the rod to get the best performance. When the rod is slid out of the coil, the inductance changes considerably. However the inductance does change very slightly when the coil is moved along the rod.



Make your own ferrite antenna

Now we come to the tuning capacitor::

THE TUNING CAPACITOR

The "C" in the "LC" TUNED CIRCUIT can be fixed or variable. When it is variable, it is called a TUNING CAPACITOR. The sheets of aluminium in the air tuning capacitor below are called PLATES and the moving plates are called VANES. The fixed plates make up the STATOR.
The space between the plates is AIR. The photo shows a single capacitor. If two capacitors are connected to the same shaft it is called a GANGED CAPACITOR.
The plates do not come fully out of mesh and that's why the capacitor has a minimum value. The maximum capacitance is when the plates are fully meshed. The odd shape of the plates is designed to produce a fairly constant increase in capacitance as the plates are engaged.

An air tuning capacitor:

**Air Tuning Capacitor
(Variable Capacitor)**

The capacitor can be made much smaller by using thinner vanes and placing plastic between the vanes. Plastic increases the capacitance about 3 times to 10 times.



Tuning Capacitor as found in a pocket radio

The tuning capacitor can be replaced with a home-made equivalent that will work just the same.
You need:
4 sheets of aluminium foil (cooking foil) 10cm x 10cm.
4 sheets of thin cardboard 15cm x 20cm   (cut A4 sheets in half).



HOME-MADE CAPACITOR

Tape a sheet of aluminium foil to each sheet of cardboard with sticky-tape around all 4 sides. Take one strand of wire from a length of hook-up flex and sticky-tape the end to each sheet of aluminium to make good contact. Place 2 sheets on top of each other and move the top sheet slightly to the left and sticky-tape the edge so they don't move. Do this with the other two sheets but move the top sheet to the right. Now interleave the sets. Connect the wire from the first sheet to the third sheet. Connect the wire from the second sheet to the fourth sheet.
The cardboard (or paper) between the aluminium sheets increases the capacitance three times.
The capacitance decreases when the sheets are moved apart and the capacitance increases when the sheets are moved in. The capacitance also INCREASES when the sheets are squashed together such as when a book is placed on them.
You can also make a smaller capacitor by making each sheet smaller and using 6 sheets. You can then add a 100p or 220p in parallel with the home-made capacitor, to select the lower part of the band.

EACH CIRCUIT

Each circuit we describe in the following set of circuits is an improvement or advancement on the previous. We also offer a number of different types of aerial coils, amplifying stages and earphones. Some of the circuits use easy-to-obtain components and home-made equivalents for hard-to-get items. There will be something in this section for everyone to build.

In all radio circuits you will encounter **TWO MAIN PROBLEMS**:

If the FRONT END (the Coil and Capacitor) is loaded too much by the "pick-off" of the amplifying stages, you will only get one station.
If you get squealing or "motor-boating," try a different circuit and layout as the components you are using, plus the voltage of the battery, will need changing.
You cannot always increase the voltage of the supply and get a louder output. Sometimes the increased voltage will stop the circuit working or it may introduce too much gain that the circuit starts to squeal.
The Radio IC (ZN414) DOES NOT WORK on a voltage above 1.5v and some of the transistor circuits completely stop working with a higher voltage. This has to do with the biasing arrangements and if the circuit is designed for a low voltage, you need to keep to the suggested voltage and experiment with a slight increase in voltage and see what happens.
Building a radio is not easy as the enormous amount of amplification of the combined stages creates a feedback loop via the power rail that sets the circuit into oscillation. This effect gets worse with a higher supply voltage and we will explain this further with each of the circuits.

MAKING A CRYSTAL SET

You can buy a **CRYSTAL SET** kit (see the photo of the kit, above) or the individual components (a kit is the cheapest) or use the replacement for the **FERRITE ANTENNA COIL** (16 turns to 20 turns on a 150mm biscuit tin) and/or the **TUNING CAPACITOR** made from aluminium foil and cardboard sheets.
You will need an outside antenna and an earth (such as a water tap or the frame of your soldering iron) to pick up the radio stations.
If you cannot put up an outside antenna, you will need to add one or more amplifying stages and this will allow you to reduce the length of the antenna and increase the volume of the audio.

ADDING AMPLIFYING STAGES TO A CRYSTAL SET

You can add two different types of amplifying stages to a crystal set.
You can connect amplifying stage(s) to the FRONT END and these will be designed to put less load on the front end so the sensitivity and selectivity increases. These stages work at the frequency of the radio signal and they are called RF STAGES (Radio Frequency Stages).
You can build these stages out of individual components or use a chip called a RADIO CHIP or RADIO IC (integrated circuit) for less than $2.00.
The chip contains 5 stages of amplification and these are RF stages (or RF AMPLIFYING STAGES) and the concept is called TRF. (Tuned Radio Frequency).
It is not easy to get this type of amplifier working because the stages produce a very high overall gain and you get a lot of "motor-boating" and squealing if the gain is not controlled. The gain must be reduced when a strong signal is being passed through the circuit because a strong signal will produce a large output and this will be so large that some of the waveform will find its way to the front of the amplifier via the power rail and start to be amplified again. To prevent the output getting too large, the circuit has a negative feedback line - called the AGC line - Automatic Gain Control.
It would be very difficult to reproduce these 5 stages of amplification with discreet components and that's why it is best to use an IC.

The next stage is a DIODE to convert the RF (Radio Frequency) to AF (Audio Frequency). This can be done with the diode-characteristics of a base-emitter junction in a transistor and we will show the alternatives.

Any stages after the diode are AUDIO STAGES or AUDIO AMPLIFIER STAGES.
The main job of the AUDIO AMPLIFIER is to increase the DRIVE CAPABILITY.
In other words, increase the current capability of the circuit for an 8 ohm speaker or 8ohm earpiece (or 16 or 32 ohm).
This is a very difficult thing to do and requires at least 2 stages.
The LOAD you can put on a Crystal Set must be 10,000 ohms or higher. (if you put a lower resistance (impedance) on the output, you will load the FRONT END and reduce its ability to separate the stations.
That's why a crystal earpiece is normally used with a crystal set. It puts almost NO LOAD on the circuit.
If you put a load on the circuit the result will be only one or two stations across the whole dial and only the most powerful station will be received.

If you don't have a crystal earpiece, you will have to use an 8 ohm earpiece. This will require an IMPEDANCE CONVERTING CIRCUIT of 1,250:1
This is a simple way of saying we want the 8 ohm earpiece to appear as 10,000 ohms to the

crystal set.
To produce an overall gain of 1250, we need two stages of amplification.
If a transistor has a gain of 70, it will it will produce an impedance conversion of 70 times. This is a realistic value. Transistors with a gain of 200 will have a gain of about 70 when fitted to a circuit.
This means the other transistor needs to have a gain of about 20 and that is easy to achieve.

ADDING AMPLIFYING STAGES TO THE FRONT OF A CRYSTAL SET

Adding stages to the front of a crystal set are called RF STAGES (Radio Frequency Stages) because they amplify the RADIO STATION SIGNAL.
It does not matter if you amplify RF signals or AF signals. The result is the same.
The only difference is this: The frequency of RF signals is much higher (1,000 times higher) and the coupling capacitors can be much smaller.
This allows an RF amplifier to be built into an IC - called a Radio Chip.
One of the most popular Radio IC's is ZN414 or YS414. This chip has been copied by other manufacturers as: MK484, TA7642 and LMF501T.
All the chips are the same but the pinout is different.
These chips work on a 1.5v supply and if the voltage is increased above 1.5v, the gain of the stages increases to a point of total distortion.
To prevent strong signals producing distortion on 1.5v supply, the output is passed back to the input via a 150k resistor. This feedback line is called the AGC (Automatic Gain Control).
The chip contains 5 stages of amplification plus a stage that converts the RF signal to AF (Detector Stage). This means the signal diode in a Crystal Set is not needed.

Here is the circuit of the TA7642 Radio Chip. It performs the same as the ZN414 Radio Chip.


R3
12KΩ
T1
C1
12pF
R4
12KΩ
R2
3.3KΩ
R1
5.6KΩ
T2
T3
T4
R5
12KΩ
C2
12pF
R6
12KΩ
R7
12KΩ
R8
12KΩ
T5
T6
R9
12KΩ
25p
R10
12KΩ
R11
12KΩ
T7
R12
12KΩ
R13
12KΩ
C4
23pF
R14
74.6Ω
T8
R15
12KΩ
T9
T10

Here is the BLOCK DIAGRAM of the ZN414 Radio Chip:


100k
1.5v
YS414
ZN414
ground
out
in
ZN414
L
C
10n
in
Z
RF
RF
RF
Detector
out
100n
0v

The ZN414 chip can be purchased from Talking Electronics for $1.00 plus postage

USING THE ZN414 RADIO IC

By using the ZN414 radio IC (or any if the equivalents) you can create a POCKET RADIO to drive a headphone or speaker.
But it is not easy to use the chip. The main problem is receiving the strong signals without producing distortion and then being able to pick up the weak stations.
A fixed 100k feedback resistor does not provide adequate control and a TRF radio has limited capabilities.
That's why radio manufacturers make SUPERHETRODYNE receivers. Even though they are more complex, the result is far superior.
However a simple TRF set can be made with the Radio IC and a few stages of audio amplification.

The following circuit uses just the Radio IC and a crystal earpiece or the home-made earpiece described above:
You can use a home-made FRAME ANTENNA or a home-made FERRITE ROD ANTENNA and a home-made VARIABLE CAPACITOR.



The Simplest ZN414 Radio

Connecting the ground (0v rail) to the frame of your soldering iron or a water tap will increase the output volume. The circuit above shows a Crystal Earpiece. Using a Crystal Earpiece may require adding a 10n across the earpiece to improve the output volume. The substitute Piezo Earpiece is effectively a 20n capacitor and an additional capacitor is not needed.

2 TRANSISTOR RADIO

Here is a simple 2-Transistor radio.
The secret to its performance is the 7 turn "pick-off" from the FRONT END (the TUNED CIRCUIT).
The ratio of 7 turns to 60 turns means a small percentage of the voltage generated in the tuned circuit is passed to the transistor. Thus it puts a small load on the TUNED CIRCUIT.
I don't want to go into any mathematics. The turns ratio is 60:7 = 8 but the effect of the 7 turns "pick-off" has an effect called the IMPEDANCE EFFECT and this is the SQUARE OF THE TURNS RATIO. Thus the IMPEDANCE EFFECT is 8 x 8 = 64. This means the "pick-off" (the LOADING EFFECT) is just a few percent. The front end can produce voltages as high as 500mV because a crystal set can produce a voltage high enough to pass through a diode (350mV) and have sufficient to drive a crystal earpiece.
Even though the front end has a "step-down" ratio, the voltage out the 7 turns will be sufficient to drive the first transistor.
The "transformer" does 2 things: It reduces the loading on the tuned circuit ENORMOUSLY and it produces an output with a higher current than is circuiting in the front end. Even though the transistor is turned ON and biased by the 33k, it is classified as a low-impedance load as far as the front end is concerned and the input signal has to be accompanied by a certain amount of current, otherwise the transistor will not respond to the voltage. The 7-turn "pick-off" is able to provide this current.
Both transistors are biased ON via the 33k base-bias resistors and thus the first transistor responds to the slightest millivolt signal.
This circuit was tested and had the same performance as the **Simplest ZN414 Radio Circuit** above. It can be operated on 1.5v to 6v and the strongest stations tend to overload on 6v. A short antenna is needed.


1k
2k2
10u
33k
33k
10n
c
c
b
b
60t
7t
415p
BC547 e
BC547 e
on/off
switch
1.5v
to
6v
home-made
piezo earpiece

SIMPLEST 2-TRANSISTOR RADIO
using a very-high-impedance earpiece


1k
2k2
10u
33k
33k
10n
c
c
b
b
60t
7t
415p
BC547 e
BC547 e
CRYSTAL
EARPIECE
on/off
switch
1.5v
to
6v

SIMPLEST 2-TRANSISTOR RADIO
using a crystal earpiece

ADDING AN IMPEDANCE MATCHING STAGE

You can add an IMPEDANCE MATCHING STAGE to the output of the circuit above so a low-impedance earpiece can be used.
We call it an IMPEDANCE MATCHING STAGE because this is the correct technical term. It is an AMPLIFYING stage but it amplifies the CURRENT because the second transistor cannot drive an 8 ohm LOAD. 8 ohms is a very low resistance and if it is connected directly to the second transistor, the output will be almost zero.
The reason for this is covered in our discussion: The Transistor Amplifier.
This stage will not increase the volume but simply match the 8 ohm load to the circuit above.
It is very difficult to connect a LOAD to this type of circuit because it will take more current from the battery and cause the supply voltage to fluctuate. These fluctuations will be passed to the first stage and cause variations in the signal. This will be amplified by the first and second transistors in the form of a low-frequency buzzing called **MOTOR-BOATING**.
The only way to reduce or remove this noise is to add an electrolytic across the power rails and reduce the supply voltage. The third transistor simply takes the waveform on the output of the second transistor and delivers it to the earphone with a higher current. It is called an IMPEDANCE MATCHING STAGE as it effectively increases the 8 ohm load by a factor of about 100.


1k
2k2
10u
33k
33k
10n
c
b
60t
7t
415p
BC547 e
BC547
BC547
100u
on/off
switch
3v
8 ohm
earphone

3-TRANSISTOR RADIO with buffer stage for 8 ohm earpiece

The 3rd transistor converts the 8R to about 800R

You can use 16 ohm, 32 ohm or 64 ohm in place of the 8R earpiece and these will give better performance as they will take less current and improve the stability of the circuit.
Low-impedance earphones create "motor-boating" due to the peaks of current and this can be very hard to fix.

A 2-TRANSISTOR RADIO with REGENERATION

The next stage in our discussion to get better performance is a feature called **REGENERATION**. Regeneration sends a small output signal back to a previous stage in the form of POSITIVE FEEDBACK to INCREASE the original signal. The signal on the emitter of the first transistor is the same amplitude as the signal entering the base but the FRAME ANTENNA has a turns ratio of 5:15 and this increases the signal on the receiving section of the antenna by up to 3 times. But we want the returning signal to be just above the amplitude of the receiving signal and so a resistive adjustment (attenuator) is provided on the emitter to deliver just the right amplitude.
This has the effect of increasing the amplitude on the TUNED CIRCUIT and is just like reducing the load on the circuit.
As we have mentioned above, when the tuned circuit is lightly loaded, it will pick up a station at the exact frequency of transmission and if the dial is changed slightly, the station will disappear. This quality is called SELECTIVITY.
At the same time, the Tuned Circuit will pick up weak stations and this is called SENSITIVITY.
The quality of a receiver depends on the loading of the TUNED CIRCUIT.

Here is the original circuit from Elektor Magazine with the prototype made on matrix board and fixed to a base-board with a frame antenna made from two sticks of wood. The photo shows a speaker but the output is so low that you really need headphones.




C3
1n
R3
100k
C7
100n
C5
1n
R6
4k7
C6
220u
R5
1M
C4
100n
R4
33k
T2
BC548
BT1
9V
R1
1M
C2
100n
T1
BC548
C1
500p
L1
15t
5t
P1
10k
R2
220R
8R
to
32R
PH1

2 TRANSISTOR REGENERATIVE RADIO from Elektor Magazine

The circuit is very complex and the output will be very low as the circuit cannot drive a low-impedance earphone via a 4k7 load resistor. The 4k7 resistor is actually driving the speaker (the transistor is simply discharging the 220u). The 4k7 only allows 32/4700 x 9 = 61mV to appear across the earphone - a very poor result.
The skill of designing a transistor stage is covered in our comprehensive eBook: The Transistor Amplifier and you wont make a mistake like this !!!
The circuit above can be simplified and we can add the REGENERATIVE feature to our **Simplest 2-Transistor Radio** circuit:

Our circuit uses a 15 turn circular FRAME ANTENNA 15cm diameter and a 5 turn REGENERATION coil.


BC547
1k
100n
to
10u
2k2
on/off
switch
33k
1n
33k
c
b
e
BC547
415p
15t
5t
1.5v
to
6v
home-made
piezo earpiece

2 TRANSISTOR RADIO with REGENERATION

The regeneration coil is brought near the main coil and as it gets closer you can hear the audio get louder. If this does not happen, turn the coil around.
Early radios used this technique and the operator had to adjust the coil by hand. No-one minded because radio was a fascination and the simplest radio cost more than a weeks wages. To listen

to a broadcast through headphones was an amazement and listeners would sit all night with headphones listening to music.
This is very fiddly and by adding an extra buffer stage, we can use a Frame Antenna with a very clever "pick-off" that does not load the front end. This gives the circuit very good sensitivity and selectivity without regeneration.

3 TRANSISTOR RADIO

Here is our final design for the simplest self-contained 3-Transistor Radio using our home-made Tuning Capacitor and 250mm x 350mm Frame Antenna. It picks up the local stations and drives a low-impedance earphone or set of earphones (from a mobile phone).



3-TRANSISTOR RADIO

The circuit performs very well and uses readily-available components. The 22n across the output is essential to stop squealing.
The secret to sensitivity and selectivity is the turns-ratio on the Frame Antenna. The 3-turn "pick-off" puts very little load on the front end and this allows the stations to be tuned with our home-made Tuning Capacitor.
The circuit contains all the features we have discussed above and only needs a 1.5v supply.
Build this circuit before you buy any expensive tuning capacitors, IC's or ferrite slab antennas as you will not get any better results.
This is called a TRF circuit and because the stages operate at Radio Frequency or Audio Frequency. Due to the high amount of amplification, the circuit can start to squeal (feedback, motorboat) due to the layout.
You may need to shorten or lengthen the leads or move the parts slightly - it's that critical.
However the result is a portable radio that needs no earth and will pick up the strong stations.
You can try connecting the 0v rail to the metal part of a soldering iron to increase the number of stations.

LOADING

The whole success of picking up a radio station is the RECEIVING CIRCUIT. The receiving circuit is the coil and the signal in the air (from the radio station) must go down the centre of the coil.
It cannot pass over the top or the bottom of the coil. Only the signal that goes down the centre of the coil is received.
As you can see, the centre of the coil is not very big and it is amazing that the signal can pass down the centre. But it does, and that is the only signal that will be amplified.
This signal is passed to the capacitor and we have explained how the signal is gradually increased and increased in amplitude until it is as large as 500mV. The signal from the radio station may be as small as a few millivolts, but as it keeps pushing the "swing" back and forth, the amplitude get larger and larger.
If you put your finger on the "swing" you will prevent it get larger and larger and it only requires the slightest touch of your finger to prevent the swing gaining full amplitude.
In electronic terms, your finger is called LOADING THE CIRCUIT and since we have to pass the signal to further stages of amplification, we need to "tap" or "load" or "pick-off" a signal.
The aim is to load the circuit as least as possible because the actual energy entering the circuit is very small.
In fact, this is all the energy we can remove as that is all the energy entering it.
Because a very small amount of energy is entering the "front-end" we classify it having a very

high impedance. It is very difficult to provide a value of impedance for this circuit because impedance has the term "Z" and the circuit is operating a very high frequency so resistance values are not the same as impedance values.
The actual resistance of the circuit is ONE OHM but the impedance is more like 10,000 ohms to 100,000 ohms.
We can explain its high impedance if we put a 100,000 ohm resistor across the circuit. The waveform will be reduced very slightly. If we put a 10,000 ohm resistor across the circuit, the signal will be reduced a reasonably large amount. If we put 1,000 ohms across the circuit it will stop working.
This means a load of 100,000 ohms will have the least effect.
In a crystal set, the diode creates NO LOAD until a voltage of 350mV is reached. It then passes excess voltage to a crystal earpiece that has a very high impedance. That's why a crystal set will produce a good output. The LOADING is very small.
When a transistor is connected to the TUNED CIRCUIT, it starts to put a load on the circuit after 600mV and this load is VERY HIGH. The "resistance" of the base-emitter junction is about 1k and the signal will find it very difficult to rise above 600mV because the incoming energy is not sufficient to increase the voltage.
Adding a capacitor between the base and the front end allows the transistor to be self-biased and get a turn-on voltage of about 600mV from a base-bias resistor.
The FRONT END is now separated from the transistor and ANY voltage it is producing will be passed to the transistor via the capacitor.
Whereas, with the crystal set, the first 350mV could be produced without any loading, the circuit is now loaded AT ALL TIMES.
This means we have to load the circuit as lightly as possible to be able to pick up individual stations.
The only way we can do this is to use a capacitor of the smallest practical value and this has to be worked out by trying different values. If the value is too small, the transistor will not detect a small signal. If the value is too large, the circuit will stop working.
Values such as 1n, 10n and 100n are suitable.
Values such as 1u, or 10u will be too large.
The CRYSTAL SET loading and a transistor load are completely different.
The transistor loads the front end ALL THE TIME and that's why you need to use a transformer or other ways to reduce the loading. Sometimes a Field Effect Transistor is used as it puts almost no load on the front end.

2-4-2016

Histats.com
Vis. today
26

FLIR
12 THINGS TO KNOW BEFORE BUYING A THERMAL CAMERA
GET THE GUIDEBOOK NOW!

Quickturn PCB & Assembly
Your one-stop source for all types of PCBs and Full Turnkey PCB Assembly.
rushpcb.com

Quickturn PCB & Assembly
Your one-stop source for all types of PCBs and Full Turnkey PCB Assembly.
rushpcb.com

Unlimited HDTV is Here

TV Bandit

Companies already tried to ban this antenna but failed. Get yours before it’s too late!

Recreating an Alfred P. Morgan crystal set



A recreation of my first (working) crystal set, originally built in 1966.




365 MMFD.
TUNING
CAPACITOR
IN34
DIODE
100 MMFD.
CAPACITOR
COIL
B ANT.
.002
MFD.
ANT.
A
GND.
TUNING
KNOB
TUNING
KNOB
PHONES

Page from "The Boys' Third Book of Radio and Electronics" by Alfred P. Morgan.

Back Story:

In the Summer of 1966 I was 10 1/2 years old and one of my favorite TV shows was "Get Smart". It was a show about a bumbling secret agent named Maxwell Smart who had all sorts of gadgets at his disposal. My friend Billy Meyers and I decided we wanted to be secret agents, like Max. One of the "secret agent" things we'd do was to pick out a guy with a briefcase walking home from work and declare him a Soviet spy. Then we would "tail" him for a few blocks, making up stories about him.

Billy and I had no way to communicate with each other after we had to come in for the night. He lived half a block away. Kids didn't use the phone back then. There was only one phone in the house and I don't remember using it before I was about 14 years old. Maxwell Smart had a phone in the sole of his shoe. We needed something like that!

Maxwell Smart (Don Adams) Agent 86.

MONKEY DIVISION ...FOR JUNGLE GUERILLA-WARFARE
REMCO
2 WAY ELECTRONIC
Wrist Radios
2 COMPLETE STATIONS
MONKEY DIVISION
MONKEY DIVISION
Wrist Radio

Remco "Monkey Division" Wrist Radios.

One thing I DID have was a set of Monkey Division Wrist Radios. These were powered by a single C battery in the "Master" unit, which also had a button on it that would buzz the other receiver to get the users attention (apparently, the other user was unworthy of a button). A metallic speaker doubled as a microphone. The sound was very tinny, but you could make it out. Unfortunately, they were wired to each other. There was nothing "radio" about them.

I remember taking them outside with my brother Rob, and I could see and hear him talking at the same time his voice was coming over the wrist radio. They were pretty much useless, unless you like running around with a wire connecting you to your brother.

BUT... with some extra wire strung across the driveway, down the backs of the houses and into Billy's bedroom, Billy and I would be able to talk to each other! I immediately presented this great idea to my mom with a request the she fund the cost of the wire, and she immediately refused and told me the electric company would just come out and take the wire down.


N 75th Ave
My house
Billy's house
Fayette St

Location of my house and Billy's house (actually his grandparent's house) The wire would have to be strung across the driveway.
This is part of the West Oak Lane section of Philadelphia.

There was only one thing left to do. Build a radio. I went down the basement and connected a battery to a speaker and used a coat hanger as an antenna. This was similar to the wrist radio, but the coat hanger antenna replaced the wire. It didn't work! All it did was make clicking sounds in the speaker. I had to wait for my dad to come home from work and ask him why.

When my dad came home I showed him the setup and he said, "You don't have a detector." I asked him what a detector was and he told me to go the library and get a book on radio. The next day I had a copy of "**The Boys' Second Book of Radio and Electronics**" by Alfred P. Morgan. Chapter 2, page 15 was titled "Building Your First Radio Receiver". I wouldn't be able to talk to Billy with it, but that was OK. My mom wouldn't buy me a secret agent coat, we didn't have any gadgets, and our secret agent days were coming to an end.

Now there was another problem. None of the parts needed to build anything in the book could be found around my dad's workbench. There was a store on Ogontz Avenue named REE Electronics, so I headed up there with a list of parts. The store sold stereo equipment and fortunately for me, also repaired stereo equipment. I asked the man in the store if he sold diodes or "capacitaters" and he sent me into the back of the place. There were two guys back there and bins of parts along the wall.

S.U.R.F.A.C.E.
S.U.R.F.A.C.E. CLOTHING CO.
HAIR CULTURE
NY NAILS
FedEx

REE Electronics was located at 7709 - 7711 Ogontz Avenue in Philadelphia. The entire block has been razed and rebuilt, and is no longer recognizable. The picture above is the 7900 block of Ogontz Avenue. The store on the left is the only one that retains its original appearance, with the glass store window and the apartment overhead. This is how REE Electronics looked in 1966.

The two guys were pretty cool. I announced that I would like a "three hundred and sixty five micro micro farad variable capacitater". They asked me a couple of questions and told me to come back with the book. They had all the parts I needed except the coil. No problem, I would just build the set with no coil. I came home with Fahnestock clips, a 1N34 Germanium diode, a variable capacitor and a crystal earplug.



A Sylvania 1N34A Germanium diode (top) from 1949 and its modern counterpart. The new diodes are literally a dime a dozen, less than one cent each. The 1949 Sylvania diode cost me $9.00 in 2015. It is a duplicate of the one I bought at REE Electronics in 1966.

The diode was 65 cents in 1966. I can't use the $9.00 diode because I don't want to bend the leads, so I sort of just look at it.

Of course the radio didn't work without a coil. It did pick up the slightest whisper of KYW AM 1060 mingled with WIBG AM 990. There seemed to be some buzzing associated with it, as what I could hear sounded distorted. I HEARD something, that was the really, really neat part. It made such an impression on me that I remember the date. July 26, 1966.

The "problem" with the Alfred P. Morgan books was that they were not written for anybody as dumb as I was. Morgan didn't write, "If you can't find the coil you can make one." He just said to go buy a coil. Not only that, but there were no photographs in the book, though there were excellent drawings on almost every page. Since I had never seen some of the parts in real life, I didn't know exactly what the coil looked like, and I didn't understand what it did. That's because I didn't read the book! I was stuck on page 15.



This is the picture of the coil from the book. I didn't know what I was looking at.

I returned the book to the library and came home with "**The Boys' Third Book of Radio and Electronics**." I found a simple radio on page 104 and soon headed back to REE Electronics. This time, they DID have the coil! I can't remember how much time passed after the first non-functioning radio was built. Probably a month or so.

I asked my dad to cut me a wooden base for the radio. I started building the radio and, if I remember correctly, it took me a long time. I didn't have a drill, so any holes in the base were made with the point of a compass. There were three connections that needed soldering. I got some solder from the basement, and the tweezers and alcohol lamp from my chemistry set. The tweezers were heated in the flame of the lamp till the tips began to glow, then I would quickly solder the joint.

One day a friend from school named Leo Pound stopped by on his bicycle. This was a bit unusual because Leo lived miles away. I don't even know how he knew where I lived. He recently told me (via Facebook) that he remembers helping me build the radio. Odd that it was the one and only time he came by. Apparently, we got the radio working that very day.



Here is the base of the radio made in 1966.



I found all the original parts except for the tuning capacitor. However, it looked like this one. It's just sitting on the base in this photo, but the radio pretty much looked exactly like this. My dad gave me the big tuning knob. The smaller knob came from a lamp in my bedroom. I didn't tell my mom you could no longer turn on the lamp, but eventually I found a lamp in somebody's trash and took the knob off to replace the one on my lamp.



Original coil, diode and main tuning knob from the 1966 radio. The wires on the coil were soldered with a pair of red hot tweezers.

My dad gave me the large knob for the tuning capacitor. He had a second job on the weekends at "John Cusimina's Moving and Storage." I've always wondered if he pulled that knob off of somebody's radio while they were moving. I hope not. He probably did.

Next

CRYSTAL SETS 5
Experimental
Crystal Sets

CRYSTAL SETS 5: EXPERIMENTAL CRYSTAL SETS



Picture 1 - The Complete Experimental Crystal Set

THE POPULARITY of the crystal radio arises from its simplicity, and the fact that it needs no power supply. The circuit here allows for easy experiments with tuning, aerial and diode coupling, and frequency coverage. Wrong connections can cause no damage to any components.

A Crystal Set is more often than not used for the reception of medium and long wave radio, but short wave reception is also quite feasible. It will normally be possible to receive some of the stronger international radio stations.

This is adapted from an article that appeared in the 1970's in Everyday Electronics, and gave me almost endless hours of fun!

BASIC CIRCUIT

The basic circuit is shown in Picture 2 below. The coil L1 can be air cored, or have a ferrite rod placed in its winding. The variable capacitor C1, in conjunction with aerial-earth capacitance, tunes the circuit to resonate with the wanted radio station frequency. The diode D1 "detects" or demodulates the radio signal so that the programme is heard in the earpiece.

This basic circuit can be modified in various ways to obtain better performance.

EARPHONE

As most constructors will be using a Crystal Earpice to listen to the crystal set it is essential that a 47k Ohm resistor is connected across the earphone terminals (TB1/1 and TB1/2 in the diagram), i.e. in parallel with the earphone, otherwise results will be very quiet.

A High Impedance headset of 20k Ohms (20,000 Ohms) may give even better results, but these are very difficult to obtain , so unless you happen to already own such a headset the Crystal Earphone with 47k resistor will be the only option. An ordinary magnetic earpiece or Walkman headphones will not work with a crystal set.

ASSEMBLY

Construction is of a 'breadboard' type using a wooden board of about 165 x 130 mm. A 12-way block connector, TB1, is used to connected together the components and this is screwed onto the wooden board. The use of a block connector provides an easy method of connecting the components together and then subsequently rearranging them as the experiments progress.

Tuning capacitor C1 is screwed to a bracket made of some scrap metal which is then also screwed firmly down to the baseboard, see Picture 1 above. Thin plywood screwed to the front edge of the baseboard would also provide a suitable method of fixing the tuning capacitor to the base. A knob with pointer is fitted to C1, and a scale is drawn and fitted behind this.

Except for C1, all connections are made by the terminals of the 12-way terminal block as shown in Picture 4. Loosen the screws with a small screwdriver, insert the bared ends of the wires, and tighten the screws. The various locations on the terminal block, TB1, are also shown in the circuit diagram, Picture 2.

AERIAL AND EARTH

Crystal receivers need a long wire aerial preferably strung outside and about 25m long, or as long as is possible to install. If this is outside it should be high and clear of earthed objects as this will improve performance.

An earth is absolutely essential for a crystal set to work properly. The earth lead can be run to an earth rod or spike that is buried to a depth of about 1 meter into damp soil. Or it may be soldered to a bare metal can which is buried in damp soil.

It is feasible, though not recommended, that the earth lead can be connected to the earthing terminal of a hi-fi system or even to the bare metal case of a personal computer that is plugged into an earthed mains outlet, but is switched OFF.

Stranded, insulated wire, or purpose made aerial wire can be used for the aerial and earth leads.



Picture 2 - The Basic Circuit



Picture 3 - Photo Of The General Layout

INDUCTORS (The Tuning Coils)

The following four coils are suggested for initial use as L1 :

Coil 1: Make a thin card tube to slide on a 10mm diameter ferrite rod, and on this tube wind about 105 turns of 32 s.w.g. enamelled copper wire, side by side. Secure ends with sticky tape.

Coil 2: Make a similar coil to to coil 1 having about 15 turns of 24 s.w.g. enamelled wire on the card tube. Loops of cotton will help hold the ends in place.

Coil 3: Wind 9 turns of 20 s.w.g. bare tinned copper wire on an object about 20mm in diameter. Remove and stretch to separate the turns, to obtain a coil about 25mm long.

Coil 4: Make a similar coil to coil 3, but with 5 turns.

The Ferrite Rod

It will be necessary to have a ferrite rod of about 60mm to 75mm long available. Coils 1 and 2 will provide reception of medium wave and the longer short wave bands. Coil 3 should cover about 3 - 10MHz shortwave with the ferrite placed in it, or about 6 - 18MHz with the ferrite rod removed. Coil 4 should cover about 6 -13MHz with the rod in, and about 9 - 20MHz without the' rod.

It will be noted that as the ferrite rod is inserted, any particular signal has to be re-tuned by opening Cl. This arises because the ferrite increases the inductance of the winding, so less parallel capacitance is needed for the same resonant frequency.

EFFICIENCY CHECKS

Tune in a m.w. transmission using coil 1 which gives good headphone volume. Place a microammeter or multi-range meter on a sensitive range in series with the headphones. A reading of 50-100uA or more may be obtained, depending on aerial, earth, earphone resistance and resistor value, coil and detector efficiency and strength of signals at your locality.

Placing the ferrite rod in the coil and re-tuning should boost the meter reading to some extent. Surplus or other detector diodes can be tried by substituting them in turn and noting the meter reading. Improvements to the aerial (or earth) will also show up as a rise in meter reading.

If experimenting with a crystal earpiece, which gives no direct current circuit, the meter may be clipped across the phone leads, i.e. D1 cathode to earth.



Picture 4 - Baseboard Layout Of The Crystal Set

AERIAL COUPLING

The aerial loads the tuned circuit heavily when connected directly to the top of the tuned circuit, as in Picture 2. This damps the tuning action and it can be found that stations spread out all over the dial, which is unsatisfactory.

The series capacitor, C2 connected in Picture 5(a) reduces the loading and thus improves the sharpness of the tuning. A variable or pre-set capacitor of about 250pF maximum is most suitable. for this role, though it is possible to experiment with a variety of fixed value capacitors in this range also.

Connecting the aerial to a tapping on the coil, as in Picture 5 (b) also sharpens tuning. It may also increase volume. Try about 2 turns from earth for coil 4, or 4 turns from earth for coil 3.

Another method is to have a coupling primary, as in Picture 5 (c). This consists of a second coil, with about one third the turns of the original wound on top of the existing coil.

You can even combine these methods to find what arrangement best suits the aerial in use.

The diode can be disconnected from the end of L1 and taken to a spare position on TB1 for example location TB1/9. You can then run a flying-lead fitted with a crocodile clip from this position, connecting it to various tappings on the coil as required as in Picture 5 (d). This method also reduces loading on the tuned circuit.

Coils with spaced turns of bare wire are readily tapped. For other coils, small loops can be made every ten turns or so, and crocodile clips can be attached to these when selecting tapping points.



Picture 5 - Alternative Methods Of Aerial Coupling

SHORT WAVES

For shortwave reception, a good efficient outdoor aerial is certainly recommended. Evening listening in the region around 5 - 9MHz in often proves to be the most fruitful.

Since there is no amplification, as with a valve or transistor receiver, certain frequencies will seem to be completely dead at particular times of day. So if the crystal receiver works satisfactorily on medium wave and longwave, but no shortwave signals are heard, check again in the evening, or after dark, when conditions are different.

PARTS REQUIRED

C1	**365pF or 500pF Air Spaced Tuning Capacitor**
D1*	**OA47, IN34, OA81, OA90, OA91, IN94 or similar point contact small signal Germanium Diode** * The OA47 will be of particular interest since it has the lowest forward bias voltage of any of these diodes which will make the crystal set somewhat more sensitive and therefore louder. The US equivalent of the British OA47 is the IN34.
TL1	**High Impedance Headphones (20,000 Ohms)** **or Crystal Earphone**
TB1	**12-Way Plastic Screw Block Terminal**
Also Required:	**47 k Ohm Resistor for Crystal Earphone: Enamelled Copper Wire: 32 and 24 s.w.g. for L1: 20 s.w.g. tinned wire for L1: Ferrite Rod 10mm diameter x 75 mm long: 25m of wire for aerial: Wire and rod or spike etc for earth: Wood for base e.g. 10mm x165mm x 130mm: Scrap of metal of thin plywood for C1 bracket/front panel: Knob: Crocodile clip(s)**

Adapted from an article in Everyday Electronics magazine, November 1981, By F.G. Rayer.

HERE ARE A COUPLE OF VERY INTERESTING CRYSTAL SET DESIGNS SENT IN BY KRYSATEC - "THE RAT" - FROM THE CZECH REPUBLIC


Crystal radio
Made by Rat
100p
LW / MW
2mH
500p
earphone
4kOhm
5n
180uH
500p
2x 1NN41

1/   Using old coils from old bulb radio for MW and LW band. Though it would be straightforward to wind the coils - one for Long Wave, one for Medium Wave and a coupling coil. Variable capacitor is 2 x 500pF only one half is used: 500pF. For the crystal earphone a resistor of about 82k ohm in parallel is required. This set also uses two Ge diodes as a multiplier in the quest for for higher audio signal output.


Crystal radio with simple amplifier
Made by Rat
100p
LW / MW
+3V
M22
M5
2mH
500p
25k
earphone
150R - 4KOhm
100n
5n
gnd
180uH
500p
2x 1NN41
102NU70
Ge diode
Ge transistor

2. If signals are not strong signal in your location, then the above circuit design can be considered. A simple transistor amplifier is used. A variable resistor M22 is used for better sensitivity which can be adjusted for poor signals. This crystal radio is aversion from cca 1960 - 1970 y.



Rat's finished Crystal Set with additional amplification - very neat!

'Minilabs' Crystal Radio

BELOW: Ian Tomlinson kindly sent in a photograph of the box that contained the kit for his John Adams Toys 'Minilabs' Crystal Radio.

It is a very simple circuit consisting of the coil (inductor) with a sliding contact that provides variable tapping points, a diode and crystal earphone. All that is added is the aerial and earth. There is no variable tuning capacitor for simplicity and to keep costs down.

The coil provides the inductance required for tuning into a certain frequency (wavelength). These days a variable "tuning" capacitor is normally wired in parallel across the inductance (coil) in order to vary the resonance of the tuned circuit and therefore enable to easily tune into various transmitters on different frequencies. This crystal is tuned varying the number of turns on the coil (ie varying the inductance) by tapping off at different points using the sliding contact ("ball").

The crystal earpiece, or high Z headphone, is connected between the output of the detector diode (the other end from the coil) and earth. The volume from a crystal earpiece may be considerably improved by connecting a resistor of - somewhere between - 4.7 k and 47k ohms in parallel with the earpiece. A crystal earpiece cannot directly allow current to flow through it and the parallel resistor therefore allows current to better flow through the circuit.

John Adams Toys
Crystal Radio Kit
Make a radio complete with tuning coil, antenna and earphone.
Pack contains all you need including full instructions. No battery required.
Ages 8–14

'Minilabs' crystal set by John Adams Toys

A discussion on configurations for Crystal Sets by Felix Scerri VK4FUQ

This discussion, by Felix Scerri VK4FUQ, was posted at this address which no longer appears on the web www.tarc.org.au/techinfo2.htm (error 404) so here it is reproduced:

Crystal Set design is one of my passions closely allied with my obsession for audio and high fidelity.

My main interest in crystal sets, apart from the wonder of a radio receiver that does not require a power source, is the potential excellence of the recovered audio quality from normal AM broadcast stations.

Personally, it is one of my great laments that most people have never heard how good wideband AM can sound. A high performance crystal set or similar TRF approach is, in my opinion,the only way to do it. There are a few people around who have heard the audible results of my efforts,and can only agree.

I have often wondered,given the ultimate simplicity of the crystal set, being essentially a tuned circuit,a diode detector and some form of output device, what it takes to achieve optimum performance. What follows are my thoughts on the matter.

Crystal Set optimisation, is in my opinion, all about reduction of circuit losses. Essentially this means high "Q" tuned circuits and high quality detectors. Efficient output devices also help too. But as we will see, there are some trade-offs required as well. A high "Q" tuned circuit is always benefical, as a high "Q" tuned circuit has lowest RF losses,highest potential selectivity,and highest voltage at resonance, which is very useful for the diode being fed from the tuned circuit. Variable capacitors, even the "modern" miniature variable capacitors (although the older air dielectric units, as used in old valve receivers are more desirable) for various reasons,are generally quite efficient, and a higher "Q" coil will produce the most worthwhile improvements.The best (highest "Q") coils are wound with "Litz" wire, which is a multistranded woven wire with all strands insulated from each other. The performance of Litz wire wound coils is spectacular, unfortunately, although I know Litz wire is still being made, from personal

experience, it is VERY rare in Australia.

Efficient coil design can be quite complex and all my coils are wound on ferrite rods. There seems to be,at least for ordinary single wire windings (close wound), an optimum wire thickness for optimum coil "Q". I have determined .315 mm winding wire to be about optimum for simple (single wire) coils on ferrite rods. Thicker wire is NOT better, believe it or not.

Lacking Litz wire, an interesting winding approach I have developed is to use two slightly thinner wires wound as a bifilar winding connected together at the beginning and end of the coil, yields considerably higher "Q" compared to a simple single wire winding. I have found 0.25 mm winding wire optimum in this application.

Whilst high "Q" coils are beneficial from the RF point of view, there is a possible downside. If one is interested in maximum selectivity and sensitivity, there is no problem, but remember highest "Q" results in a narrowed audio band-width as a simple consequence of band-width. For high fidelity applications this could be a disadvantage under some circumstances, although there are clever ways around this.

Regardless of ultimate coil "Q", selectivity is a major issue with crystal sets generally. Here another trade-off is evident. For the maximum voltage into the diode, connecting the diode to the high impedance end of the coil (i.e. the top) yields the greatest voltage but the selectivity is usually terrible, because of severe "loading" by the diode circuit. For this reason, tapping well own the coil improves selectivity at the expense of signal volume (reduced voltage). Once again there are ways around this. As described in my "Double Tuned Crystal Set Tuner" article in "Amateur Radio" magazine, March 2002, the use of two separately tuned coupled resonant circuits allows top connection into the diode without compromising overall selectivity, thanks to the use of a second tuned circuit which is fed from the external antenna. The whole network forms a double tuned input bandpass filter and in practice this approach works very well. For single coil crystal sets I recommend the use of an un-tuned "antenna" winding adjacent to the "hot" end of the main coil, preferably adjustable (old paper reels from sewing cotton threads are ideal). This allows the degree of coupling to be optimised under actual listening conditions. The double tuned set up is best, yielding superb selectivity, but the un-tuned antenna coil arrangement also works quite well, especially if the diode is tapped well down the main coil.Tapping halfway works well.

The other method of performance improvement involves the use of the most effective detector system possible. Here things get very interesting. In fact the temptation is to use more complex circuitry, but that gets away from the charming simplicity of the crystal set. As an example, my own crystal set tuner has at times mutated into a TRF tuner complete with FET RF preamplifiers, active(powered) detectors and other enhancements. These modifications do work well, but loses the simplicity of a basic crystal set. In actuality, a simple diode detector can work extremely well, subject to some qualification. Diodes like to work with a reasonable level of RF input voltage. Audio distortion can result under conditions of low signal level, due to diode transfer curve non linearity and other factors, such as the widespread use of broadcast station "processing". The actual type of diode makes a difference. The 1N34A germanium diode is very popular for crystal set use, although in my experience just about ANY germanium diode will work, although it is worth trying different specimens. Some are definitely better than others. Even from a pack of twenty 1N34A's from the same source, some were definitely better than others. Measuring the average value of rectified output voltage across the diode load resistor will show which diodes are best. By the way, I regard a diode load resistor as being mandatory. I find a value of about 47K about right, especially if a crystal earpiece is being used or the crystal set is being used as a tuner feeding an audio pre-amplifier and following amplifier. If using high impedance magnetic type headphones, the headphones provide the diode DC load.

Another type of diode that is very interesting, is the hot carrier diode. There seem to be a lot of different hot carrier diodes around these days. There are even hot carrier diodes now being sold as "germanium diode equivalents". I have tried them and they do work acceptably well, but they are not quite as good as genuine germanium diodes such as the 1N34A. Typical UHF mixer hot carrier diodes, such as the 1N5711 will not work well in crystal set service simply because their "turn on voltage"is too high, similar to silicon diodes such as the 1N4148/914 series, which require a lot of RF input to function adequately as RF detectors, however a simple technique can be used to turn hot carrier diodes such as the 1N5711 into superlative detectors.

I guess we are cheating a little, because the technique is to use a little voltage bias supplied via a 1.5v battery, through a simple potentiometer voltage divider arrangement, with capacitor (for DC isolation) fed into the diode from the tuned circuit. With applied adjustable bias, I find the 1N5711 diodes absolutely superlative detectors under ANY signal strength conditions. I find the detection quality also superlative, with a clarity and low noise profile unmatched by any other diode arrangement. In my opinion, hot carrier diodes, running bias,are the best detectors overall.

Regarding other detector arrangements, the diode "voltage doubler" is often recommended, however my own

experiments with the doubler arrangement have been inconclusive and slightly disappointing overall. I have found no real advantage in their use over a simple (one) diode detector, believe it or not.

Yes, they do work, but they're nothing special, at least in my opinion.

Any comments on this general subject of crystal set optimisation would be welcome.

73's Felix Scerri VK4FUQ.
22nd July 2002



Above: CRYSTAL SET BASED CIRCUIT PROVIDING A HIGH QUALITY PROGRAMME SOURCE

IMPROVED VERSION OF THE ABOVE CONCEPT !! New update from Felix Scerri February 2010:

New 'two FET infinite impedance AM detector'

I've developed a new version of my old favourite FET 'infinite impedance' AM detector that I think sounds very nice. I include a short audio of one of our local AM stations. I picked this station as it is my reference 'torture test AM station' as they run very heavy 'processing' which normally sounds yuck with all my other (diode and non diode) detectors! However it's quite clean with this detector. What do you reckon? I'll do up a circuit if you'd like to feature it in your TRF radio section. A general draft article follows.

'A favourite non diode based AM detector that I've built and used many times over the years is the FET based infinite impedance detector, offering very good general AM detector performance, especially under weak RF signal conditions where diode based detectors do not perform well, especially in terms of audio distortion.

However one of the slightly strange things I've noticed about the simple FET based infinite impedance detector is the variable audio quality noted, even when using the same type of FET. Some I've built have sounded good and others slightly fuzzy when used with an audio preamp and fed into a high quality audio system. I've been giving this a considerable bit of thought of late and I've wondered if the audio distortion might be a result not necessarily of the detection process itself, but the FET stage in its guise as a 'source follower' audio stage which essentially, it is.

I have long been aware that as a simple audio buffer stage, the FET based 'source follower' can exhibit a considerable amount of audio distortion, and a technique I've long used to greatly reduce this audio distortion is to use a second FET in the source lead of the first FET as a 'constant current source' which serves to 'linearise' and

greatly reduce audio distortion in the buffer stage overall. So, to test the theory I built a simple one FET infinite impedance AM detector which worked well, but with just a hint of audio 'fuzziness' on received AM stations. So I added a second FET in the source lead of the first FET wired as a constant current source, taking the output from the source of the first RF detector FET and the source resistor and RF bypass capacitor off the source lead of the second FET 'constant current source'. The result, totally clean audio! The theory seems proved! I call this modified detector the 'Two FET infinite impedance detector'

[))) Here's what is sounds like - click to play the audio file (((](#)

Here is the circuit diagram:



This detector has been a real eye opener for me in terms of its excellent performance, especially considering its circuit simplicity. Indeed in the past I have designed other more complex FET based infinite impedance circuits that do not quite work as well in practical terms as this latest circuit, at least according to my well calibrated ears!



I do not have access to any precise test equipment but my well calibrated ears tell me this 'two FET infinite impedance detector' is a beauty, surpassing practically every other AM detector I've built even at low RF input, and that's rather a impressive claim and the audio quality when used as an AM tuner feeding a high quality audio system is quite remarkable. Possibly the best thing about this detector is its excellent performance under weak signal conditions. Diode based detectors also work beautifully, but the use of an RF stage to ensure detection over a linear portion of the diode's curve is mandatory! This compound infinite impedance detector works

beautifully on the sniff of a useable RF signal.

Just add a high Q tuned circuit and that's it!

Felix Scerri
VK4FUQ

A better FET for the 'basic' Infinite Impedance Detector:

Quite recently by accident, I've realised the MPF102 FET that I've long used in my FET based infinite impedance detectors is possibly not the best FET to use. This was the reason why I developed the 'two FET' infinite impedance detector some time ago which works very well.

However I've found the choice of a more suitable FET works beautifully in the basic FET based infinite impedance detector circuit, which has appeared for many years in many editions of the ARRL Handbook.

I use the 2N5457 and others of the same 'family' may be equally suitable, but I haven't tried them! However with a 2N5457 in place of an MPF102, the basic infinite impedance detector has became my AM detector of choice. It works beautifully even at low signal input with lovely and clean low distortion audio along with a very high input impedance for good tuning selectivity. It's a beauty! The basic generic circuit is attached, courtesy of Rod Elliott's ESP website.

73 Felix VK4FUQ
10 / 02 / 2012.



The basic generic circuit is attached, courtesy of Rod Elliott's ESP website
Felix Scerri VK4FUQ

As often happens with me, my renewed interest in FET based 'infinite impedance detectors' of late has led to some interesting new research and I may have considerably improved the 'two FET infinite impedance detector' as a result.

My research suggests that although the use of a CCS (constant current source) reduces audio distortion in an audio stage, the value of the 'source resistor' in the CCS stage is somewhat critical for best results.

By using a potentiometer in lieu of a fixed resistor I have found that a resistance value of around 470 kohms cleaned up all overall audio distortion. I used an MPF102 as the CCS in this circuit. An interesting and worthwhile little circuit refinement.

73 Felix VK4FUQ
21 / 02 / 2012.

A Minimum Component Count High Quality AM Detector

I was generally messing around with various circuit ideas and I came up with this AM detector circuit, a simple diode detector along with a FET stage. It was an attempt to provide good performance along with minimum number of components. Actually I've been pleasantly surprised at the excellent level of general performance and the best of all, it sounds great!

The circuit is quite conventional being a BAT 46 diode detector feeding an MPF102 FET buffer/ common source amplifier stage. I would ordinarily use a FET source buffer stage in this application, but opted to use a simple low gain FET 'common source' amplifier stage instead, with excellent results. I also used a BAT 46 Schottky diode instead of an ordinary germanium signal diode.

This was done for several reasons. Firstly, germanium diodes are now very hard to find but in any case these 'germanium diode equivalent' Schottky diodes are actually a superior diode, having very low noise, almost zero back leakage and an essentially complete absence of carrier storage effects and very good weak signal sensitivity. I call these diodes high fidelity diodes as they sound wonderful as RF detectors.



Circuit Diagram of the Minimum Component Count AM Detector by Felix Scerri



Minimum Component Count AM Detector by Felix Scerri



A Closer View

The high impedance of the FET's gate circuit is perfect for optimal buffering of the diode detector, something very important for good low distortion diode detector performance. Apart from providing slight voltage gain, the use of the common source FET amplifier is a new idea, as this prevents the possibility of incidental RF rectification occurring in a FET source follower stage, which can happen. A 1 uf plastic film capacitor may be added in series with the audio 'hot' output lead to block the DC offset out of the FET drain, if required.

Despite no additional RF stage ahead of the diode, audio quality on even relatively weak RF strength stations is actually very good, and of course the audio quality will be even better with increasing RF signal strength, something which will also increase the audio output level. Just on this, for a long time I was somewhat negative regarding diode detectors, as one AM station locally (the strongest one) was always distorted when using a diode detector.

I strongly suspected a transmitter fault, but my complaints were ignored, until one day some time ago when all audio distortion suddenly disappeared! Nothing was ever 'said', but I realised that my suspicions of a long standing transmitter fault were correct, after all!

73 Felix
VK4FUQ
02 March 2012

Voltage Doubler Detector

This is an AM detector circuit that I've long known about and which worked ok, but never seemed to work as well as it should have. However I spent some time late last night trying to optimise the circuit, with some success.

It is a curious circuit being essentially a 'voltage doubler' originally developed for power supply applications, and its use as an AM detector is hard to analyse! It seems that the component values in the circuit are somewhat critical for good performance and if not, the performance is rather 'ordinary'. The circuit that I eventually came up with uses a 150 picofarad 'input capacitor' with a 150 kohm 'load' resistor and loaded into a FET common source voltage amplifier stage (as previously described) through a coupling capacitor with a 1 Mohm input resistance.



With these circuit values, it all works 'quite well'. Give it a go! It's an interesting AM detector with quite good 'sensitivity' and clean audio quality, and it seems to work well at low signal levels.

73 Felix
vk4fuq.

16th April 2012.

Simple AM detectors: What works best? A practical experimenters viewpoint.

I have written a lot about simple AM detectors for use as tuners for feeding into an audio amplifier, and it has been a long time interest. These days I use either diode based or 'infinite impedance' types of AM detectors. In this location our 'local' AM stations are quite distant and are therefore quite weak in terms of signal strength.

As such I find infinite impedance detectors based on field effect transistors give consistently better results for tuner applications due to their lower apparent overall detector distortion. Diode based detectors are quite 'fussy' as they require both optimal output buffering (AC/DC ratio) and an 'adequate' (beyond the diode knee) level of RF signal injection. http://www.tonnesoftware.com/appnotes/demodulator/diodedemod.html

Diode based detectors will happily 'detect' at very low signal levels, however the (inevitable) audio distortion that results, can be extremely irritating to the ear! Under these conditions I find infinite impedance detectors (even without additional RF preamplification and subject to individual FET characteristics), generally sound 'cleaner' and more pleasant to the ear.

FET's of course require a power source for operation whereas diodes are passive (un-powered) detectors (most of the time), however this is of no real advantage in a tuner application as an 'active' audio amplifier stage will generally be required anyway for audio level boosting, buffering etc.

In the end it will come down to a consideration of prevailing RF signal levels and other related circuit considerations at one's location. If local RF levels are strong, a well designed diode detector will give excellent results. If not, an 'infinite impedance' type of detector is most likely the better option unless one goes towards the option of additional RF preamplification prior to the diode detector.

73 Felix
vk4fuq.

17th April 2012.

ANOTHER DETECTOR by Felix Scerri !

I’ve tried diode based ‘voltage doubler’ (or more correctly ‘diode integrator’) AM detectors before with indifferent results, however the other day, just trying a few ideas I came up with this version that works rather well, with low audio distortion, high audio output and really ‘nice’ audio quality and the best of all, it seems to work very at very low RF input level.

The two diode ‘voltage doubler’ detector using two BAT 46 silicon schottky diodes feed directly into a MPF102 source follower stage set at 1 Megohm input resistance. The ‘input’ capacitor feeding the diodes from a tuned circuit is 68 picofarads.

I have the simple RF filter right on the output of the FET stage. In that respect this circuit is vaguely similar to the old ‘Selstead-Smith’ valve AM detector of the past. An interesting one! I am very happy with its general performance. Regards, Felix vk4fuq 11/04/2013


11/4/13.
VK4FUQ.
+ 9V - 18V
MPF102
68Pf
BAT46
G
D
S
R1.
Audio out
Tuned circuit
BAT46
~~1M~~
1MΩ
C1
C2
1uf
27KΩ
Filter
C1, C2 - 150 PF
R1 4.7 KΩ.

Felix Scerri VK4FUQ

UPDATE - JUNE 2013

G’day all, readers may recall the two FET infinite impedance detector I developed some time ago. That circuit worked well, but some samples of the MPF102 regretfully produced distorted output. However a recent discovery has resulted in an improved version that has truly exemplary performance.

The MPF102 is in all honesty a device essentially designed for VHF applications, but is often used in simple audio applications albeit with occasionally indifferent results, due to general device parameter ‘spread’. More or less by empirical trial and error I have found that a simple change in source resistor value to 100 k (from a much lower value), pretty well fixes everything.

In a FET source follower circuit this is interesting as the output impedance is actually a lot lower than 100 k due to the action of the FET’s transconductance. It is similar to the action of a bipolar transistor emitter follower circuit. In fact a simple infinite impedance detector with a 100 k source resistor actually works very well and will be good enough for many applications, however the addition of a second FET as a constant current source does markedly reduce overall audio distortion in the stage overall, and produces very clean and low distortion audio quality and also reduces the output impedance considerably (good for tuner applications), so take your pick!

Regards, Felix vk4fuq 02/06/2013.

UPDATE - JANUARY 2014

A simple modification to the basic FET 'infinite impedance' AM detector that dramatically improves performance.



G’day all, over the Christmas break just messing around I worked out (mostly by accident), a simple modification for the simple FET based ‘infinite impedance’ detector circuit that dramatically improves weak signal performance and also greatly reduces audio distortion.

Essentially by the addition of another FET ‘buffer’ stage, another source follower, capacitively coupled from the first detector stage. The circuit is actually a simplified version of the circuit that I described in this link, http://sound.westhost.com/articles/am-radio.htm (figure 6) and testing the two head to head, they both sound superb and the simpler version is actually somewhat easier to build. I cannot get over how low distortion and ‘nice’ the recovered audio sounds. It is a joy to listen to!

Regards, Felix vk4fuq 12/01/2014.

Diodes for 'weak signal' crystal set applications.

As I am primarily interested in using crystal sets as AM tuners for feeding into a preamplifier/amplifier and loudspeakers, the actual type of diode can be relatively critical. In a strong signal area, not so much, but in a weak signal area such as where I reside, definitely. A diode with a good 'square law' performance (the area below the 'knee' in the diode curve), generally results in much cleaner and lower distortion than other good performing diodes, and believe me diode distortion under weak conditions, even with optimised diode 'buffering' used is very nasty sounding to the ear!

Testing many, many diodes in actual working crystal sets and listening critically to the audio output, it seems to me that the best diodes to use under weak signal conditions are the so called 'gold bonded' germanium diodes. I have sampled many different gold bonded germanium diodes and they all work well in this specific application, although sometimes the rectified output voltage may not be as high as other germanium or silicon schottky diodes, however the audio quality is much cleaner and shows much less apparent distortion!

I have tried OA5, OA47, IN141 and several 'CG' gold bonded germanium diodes with consistently excellent results. Other 'ordinary' germanium diodes may also work well under weak signal conditions, but they will need to be tested individually to check actual performance in a working circuit. One thing that I have noticed about germanium diodes is that due the 'point contact' nature of their construction, even diodes of the same specific type can exhibit rather different levels of performance!

The otherwise very good BAT46 silicon schottky diode works extremely well at good RF input level but not so well at weak RF input, especially when heavy broadcast 'processing' (commonplace these days), is used. New 'gold bonded' germanium diodes are probably no longer made although I am aware that they can be purchased through vendors over the internet. Apart from that, they may be found in old gear. As stated earlier, ordinary germanium diodes may be quite good but will need to be checked individually. Diodes are complex things!

Felix (vk4fuq). 29/01/2014.

* * * * * * * * * * * * * *

Just when I thought that I've tried everything I realised that I've not tried a voltage doubler (diode integrator) detector with an RF stage in front. It is an unfortunate fact that all diode detectors 'need' a good RF injection level (and buffering) or audio distortion becomes 'bad' (an understatement!)

Consider yourself very lucky if you live in a strong signal area! (unfortunately I don't). Anyway I quickly built a couple of prototypes which worked ok but not as well as hoped. Initially I tried using a source follower buffer (no voltage gain), but converting it to a common source amplifier (with appreciable voltage gain), seemed no better, which was strange.

After staring at my prototype for what seemed like forever with my magnifiers on, I (finally) realised my mistake. A common source stage takes its output off the 'drain' terminal of the FET, not the 'source' terminal as it does with the FET source follower buffer stage. I shifted one wire, and all worked as expected and it sounds fantastic! All diode detectors (one diode envelope detectors, doubler detectors etc), need good RF input and a simple untuned FET RF gain stage works very well. As to the sound, it sounds great.

73 vk4fuq 10/03/2014.



Felix Scerri's FET Crystal Set with Voltage Doubler

A 'nice sounding' AM detector - update October 2015

Looking through these pages the other day I was slightly shocked to realize that I've completely forgotten about some of the circuits that I've contributed in earlier days! They all work pretty well, however in my advancing older age and a little like my tastes in high fidelity generally, I'm starting to show a particular preference for 'nice sounding' bits of audio gear.

I guess that this also means low noise/low distortion too, although with AM broadcasting, at least in this country and probably elsewhere in the world too, the very common use of broadcasting 'processing' tends to make it hard for AM detectors generally, often resulting in a 'hard/compressed' sort of sound although still low in distortion, is not 'nice sounding', if that makes any sense!

Well of all the AM detectors that I've tried and/or developed, only one sounds 'nice' when confronted by heavy broadcast processing and that is an AM detector 'based' on a voltage doubler/diode integrator circuit (similar to the above circuit, actually the 68 pf capacitor should be changed to .1 uf, for slightly greater output).

It has taken me a very long time (years) to 'optimise' this circuit, but as it presently stands this is my favourite 'nice sounding' AM detector, and gets most use for general high quality listening on the AM broadcast band. It sounds really good! It somewhat reminds me of an old OA47 gold bonded diode detector from years ago before such abhorrent 'processing' became commonplace!

Ah yes the OA47….now that is a lovely sounding detector diode!

Regards, Felix vk4fuq. 17 / 10 / 2015.

* * * * * * * * * * * * * * *

That's it for crystal sets. I hope you try building one, it's easy and great fun!

See some useful links below....

73's
Mike

Crystal Sets (Part1) | Build Your Own Crystal Set (Part 2)

Spider's Web Crystal Set (Part 3) | Crystal Set By Kenneth Rankin (Part 4) | Crystal Radio Links

Amateur Radio

M0MTJ Visit my amateur radio pages M0MTJ

Visit my Amateur Radio Pages >

No AM radio stations or transmitters in your locality or country?

Spitfire
AM Transmitter

Has your local medium wave broadcast station closed or been moved to VHF/FM or Digital? Don't worry. You can still build and experiment with crystal sets and TRF radios by also buying or even building a simple low power AM transmitter. So, not only can you use your crystal sets but you can also run your own radio station that can be heard in and around your home - playing the music or programmes that you want to hear!

SSTRAN AMT3000 Superb high fidelity medium wave AM transmitter kits from SSTRAN. Versions available for 10kHz spacing in the Americas (AMT3000 or AMT3000-SM) and 9kHz spacing in Europe and other areas (AMT3000-9 and AMT3000-9SM). Superb audio quality and a great and well designed little kit to build: http://www.sstran.com/pages/products.html

POWER
GAIN
MODULATION
COMPRESSION
SStran
AMT3000

http://www.sstran.com/

Other AM transmitters available:

Spitfire & Metzo Complete, high quality ready built medium wave AM Transmitters from Vintage Components: http://www.vcomp.co.uk/index.htm Vintage Components offer a choice of the high quality Spitfire and Metzo transmitters:

SPITFIRE AM Medium Wave Transmitter with 100 milliwatt RF output power:

http://www.vcomp.co.uk/spitfire/spitfire.htm

Spitfire
AM Transmitter

METZO AM Medium Wave Transmitter with built in compressor:

Gain
Comp
Mod
Metzo

http://www.vcomp.co.uk/metzo/metzo.htm

AM88 LP A basic AM transmitter kit from North County Radio.
http://www.northcountryradio.com/Kitpages/am88.htm

LINKS: Fine links to more Crystal Radio websites here

Component Suppliers: Links to electronic component suppliers here

Amateur Radio

M0MTJ Visit my amateur radio pages M0MTJ

Visit my Amateur Radio Pages >

Crystal Sets (Part1) | Build Your Own Crystal Set (Part 2)

Spider's Web Crystal Set (Part 3) | Crystal Set By Kenneth Rankin (Part 4) | Crystal Radio Links

^Top Of Page

Home | Contact | Site Map | Radio Stations & Memorabilia | Amateur Radio

Crystal Sets Introduction | Resistor & Capacitor Conversion Tables

www.mds975.co.uk © 2004 - 2015

CRYSTAL SETS 2

Some Practical Designs
MAKE YOUR OWN
CRYSTAL SET !!

Home | Contact | Site Map | Radio Stations & Memorabilia | Amateur Radio

Crystal Sets Introduction | Resistor & Capacitor Conversion Tables

Crystal Sets (Part1) | Spider's Web Crystal Set (Part 3

Crystal Set by Kenneth Rankin (Part 4) | Experimental Crystal Sets (Part 5) | Crystal Radio Links

CRYSTAL SETS 2: SOME PRACTICAL DESIGNS

I hope that you attempt building one or two of these crystal set designs and I really do recommend that the components are carefully connected up using soldered joints onto a piece of tag-strip for reliability. However if you are new to constructing such electronic circuits then some simple solder-less techniques could be employed and these are suggested at the bottom of the page.   Also see Crystal Sets Part 5 for more ideas on experimenting with crystal sets.

An early and very basic crystal set would have been nothing more than a coil of wire, perhaps 50 -100 turns, wound around a cardboard tube about 3 inches (7cm) in diameter, a detector (or cats whisker) and a pair of special High Impedance headphones (as discussed in part 1).

There would be a very large aerial strung up around the garden and the all important connection to earth.

The coil would have tapping points (connection points) at intervals of around 5 or 10 turns. See the circuit diagram on the right for details of who the set is wired together.

The tapping points on the coil allow the set to be tuned to different frequencies by adjusting the position of tap B. Tap B would be connected to the coil at differently positions by way of a crocodile clip. The fewer turns between the top (aerial end) of the coil and tap B, the shorter the wavelength received (ie the higher the frequency). Tap A would allow the detector to be connected at different positions to vary performance. There is an additional component drawn in the above diagram, the *capacitor* (value 1000pF), this is included in crystal sets that used the *High Impedance* magnetic headphones, and bypassed any remaining radio frequencies (RF) to earth.



A very basic crystal set circuit.

I have not built the set described above as it is so basic. Such a crystal set above would probably have been adequate in 1920 - 1923 when there would have been only one local transmitter receivable.

When the BBC expanded transmissions and it became possible to hear more than a single station it would have became necessary to include a more convenient means of tuning the set.

This was achieved by including a Variable Tuning Capacitor, of about 500pF (0.0005uF) connected in parallel with the tuning coil forming a *tuned circuit*. The tuning capacitor would have a Bakelite knob on the spindle to aid tuning.



The Standard Crystal Set

Because of the simplicity of crystal sets, it is often difficult to separate stations. When tuned into one station it is often possible to hear another close by station in the background, this is due to lack of *selectivity*. This can be reduced somewhat by adjusting the positions of the Aerial Tap and Detector Tap. Moving them closer to the bottom of the coil, the earthy end, reduces the load on the tuned circuit and this improves selectivity, however it does also reduce *sensitivity* which can make the station quieter. Headphones will often swamp a tuned circuit and reduce its selectivity (Q factor), so moving the tapping point lower down improves this situation. Every circumstance is bound to be different though so the best balance has to be found by experimentation. My crystal set has both the diode and the aerial connected to the same tapping point on the coil, about a quarter of the way down.

The modern 'standard crystal set' shown above uses a Crystal Earphone, since suitable high impedance magnetic headphones (of 2000 to 4000 ohms) are no longer widely available. When using a crystal earpiece the 1000pF capacitor shown in the first diagram can usually be omitted an in its place a 47k ohm resistor is connected, this ensures that the Crystal Earphone will work at its most efficient i.e. the sounds will be as loud as possible. The resistor allows DC current to flow through the circuit efficiently - this would otherwise be blocked when using a crystal earphone. In a modern crystal set the detector used is a *Diode.* Suitable diodes include OA80, OA81, OA90 OA91 and IN94 which are usually available from component stockists.

A Better Diode For Increased Efficiency

The OA47 will be of particular interest since it has the lowest forward bias voltage of any of these diodes which will make the crystal set somewhat more sensitive and therefore louder. The US equivalent of the British OA47 is the IN34.

On the right you will see my real working example of a crystal set

The large plastic knob on the front turns the variable tuning capacitor. This set receives the three UK national stations and also three local radio stations very well at my location.

There is a small 3.5mm jack socket mounted on the front of the plastic case (MB5 from Maplin Electronics) that the crystal earphone plugs into.

The coil can be seen inside the case, it is 70 turns of 30 gauge enamelled copper wire wound around the centre of a toilet roll and tapped every 10 turns, by scraping off the enamel insulation and making a small twist. The croc' clips can be seen clipped on to these twists to connect to the aerial and detector tap points.



A real working crystal set. Radio as if by magic with no battery or mains power.

THE MEDIUM WAVE COIL - MORE DETAILS


PHOTO SHOWING THE INSIDE OF THE COMPLETED CRYSTAL SET

Medium Wave Coil

The number of turns of wire required on the coil will vary depending on the size of the former (in this case the inside toilet roll) and the thickness of the wire. So to obtain the correct coverage of the medium wave band may need a little experimentation.

I usually find that between 50 to 90 turns is right and I generally use enamelled copper wire that is between 30 s.w.g. and 26 s.w.g (i.e. 0.315mm and 0.45mm diameter), so it's best to start with too many turns and then work down.

The more turns that you use the lower the frequency range will be, i.e. too many and the coverage of the top end of medium wave around 1500 - 1600 kHz will be lost, while too few and the coverage down to 500 kHz will be lost.

It is also important that the coil former is non conducting, i.e. not metallic. It could be wood or cardboard or a short piece of PVC piping and with a diameter of between 1½ and 4 inches (4 to 15 cm) are common sizes. You could try using a ferrite rod too, see below.

This particular set has a coil wound onto a toilet roll tube which consists of 70 turns of 30 s.w.g. (0.315mm dia) enamelled copper wire tapped at every 10 turns. It also has the additional small trimmer capacitor that helps match the aerial to the tuned circuit thereby improving selectivity, see below.

USING A FERRITE ROD AS THE COIL FORMER

The aerial coil could be wound onto a ferrite rod.

A piece of 10mm diameter ferrite rod of between 3 and 6 inches long (80 to 150mm) will be most suitable and will require between 50 and 90 turns of enamelled copper wire to provide coverage of the medium wave band: First make a paper tube that is held together with sticky tape that will easily slide up and down the ferrite rod. Then wind the coil over this with the windings neatly side by side. Make tapping points every 10 or 15 turns so that the aerial and diode tapping points can be adjusted.

Adjustments to the tuning range can be made by removing some wire from the coil so it is best to start off with too many turns and then work down. Fine adjustments can be made to the completed coil by sliding it up and down the ferrite rod.

AN IMPROVEMENT TO THE DESIGN

The crystal set above also has one small, but significant, improvement over the standard crystal set and that is an Aerial Trimmer. A trimmer is a variable capacitor, very similar to the tuning capacitor, except smaller and adjusted with a screwdriver.

The value of the trimmer is usually around 10 - 50pF, but if a small tuning capacitor is available that will probably be just as effective. In the absence of such a variable capacitor, individual fixed ceramic capacitors of e.g. 10pF, 50pF and 100pF can be tried in this position to judge which gives the best results with the particular aerial being used.

The trimmer capacitor adjusts the coupling to the tuned circuit, reducing the load of the aerial on the tuned circuit will improve the selectivity (Q), and it will be easier to separate stations. Again tapping points are used and I find this to be an excellent arrangement.



Improved Crystal Set design, with good selectivity



Layout Of The Crystal Set - Although this is soldered together an alternative to tagstrip would be a 5amp mains connector block so that components can be trapped in place with screws. See article below.

The picture on the right shows the general layout of the crystal set above. The coil is of approximately 70 turns is wound on the centre of a toilet roll, and has tapping points at 10 turn intervals.

The trimmer is soldered between the Aerial terminal and the piece of 5-way tag strip, and a wire goes from there to a croc' clip which is clipped onto a tap on the coil. The Diode is also soldered onto the tag strip, one end connected to a piece of wire going to a second croc' clip & connected to a tapping point on the coil, the other end of the diode is connected to the 3.5mm jack socket that the Crystal Earphone plugs into.

The 47k resistor is also connected to the earphone end of the diode and goes to earth, the earth terminal wire is soldered to the tag strip at this point too. The tuning capacitor has two terminals, one connected to each end of the coil, and one of them is also connected to earth as shown. [Where the wires cross over in the diagram, they do not touch and are not connected together].

LONG WAVES

In most areas around Europe and certainly around much of the UK you will be able to hear a Long Wave station. To receive Long Wave on a crystal set will require an aerial coil with a greater number of turns to increase its inductance.

As a good general guide a coil wound on a piece of 10mm diameter ferrite rod will require about 250 turns of enamelled copper wire: First make a paper tube that is held together with sticky tape that will slide up and down the ferrite rod. Then wind the 250 turn coil over this, the windings will have to be made over the top of each other. Make tapping points at, say, 50, 75 and 100 turns to tap the aerial and diode to.

As with the medium wave ferrite rod aerial, adjustments to the tuning range can be made by adding or removing some wire from the coil, and fine adjustments can be made to the completed coil by sliding it up and down the ferrite rod. The longer the ferrite rod the better and anything between 3 and 6 inches long (80 to 150mm) will be very good.

SHORT WAVES

If you like experimenting, then reducing the number of turns on the coil to say 10 to 30 will allow reception of the higher frequencies, the Short Waves. I have found that winding the coil around a 'ferrite rod' often works even better with short wave reception.

Obtain a ferrite rod about 7 to 15 cm long and about 1cm in diameter. Make a couple of small tubes of card, about 4cm long, that will fit tightly over the rod.

On one tube wind two coils using 0.5mm diameter enamelled copper wire - one coil of about 30 turns and a second one of 2 or 3 turns wound over the top of the first. Secure the windings in place with Sellotape.

On the other card tube wind a similar coil, but use about 15 turns for the first coil and for the second coil wind about 3 to 4 turns over the top, and secure with Sellotape tape.



Example of a layout using a connector block to wire up a crystal set

These coils will provide coverage of short wave in two bands using the first coil for the longer wavelengths, typically 60 to 31 metre bands and the second coil for the shorter wavelengths typically 25 to 19 metre band. Wire up the circuit as shown in the circuit diagram below.

USING A TOROID INDUCTOR FOR SHORT WAVES

Even better selectivity performance can be achieved by winding the inductors (coils) on a ferrite toroids (T50-2 yellow, or green will do). The aerial trimmer need not be used if selectivity and sensitivity is found to be adequate. It's all about experimenting, and I find it best to use a trimmer or small coupling capacitor to obtain the best selectivity.

Up to 30 turns of 0.5mm enamelled copper wire can be used for the longer short waves below 10 MHz, while a winding of around 15 turns will provide coverage of the shorter short waves above 10MHz.



The circuit diagram of the Short Wave Crystal Set



A completed SW Crystal Set using a toroid inductor. Note: the main winding has a tap to allow the switch to short part of the winding and thereby give two ranges.

AUSTRALIAN DESIGN

Moving back to the Medium Waves, here is a circuit for a very interesting Australian design that promises extremely good station separation (selectivity), and having built it I can vouch for that claim, it's really excellent.

I receive three national stations and three local stations at my location with excellent clarity using a modest antenna and standard crystal earphone.

The coil is different to the other crystal sets described above, it is much bigger at 3¼ inches (8cm) diameter and 5inches (12cm) long. I made my coil former out of the cardboard from a breakfast cereal box - just like Blue Peter!

The design is often referred to as The Mystery Crystal Set, by Proton.

The front panel of the Australian Crystal Set

Two distinct coils are wound on it, the first one consists of about 50 turns of 24 s.w.g (approx) enamelled copper wire. The second coil is 25 turns, very close wound right over the top of the first coil using 30 s.w.g. (approx) wire, try to get this second coil wound in between the windings of the first, for better inductive coupling.

Then carefully wire up the set according to the diagram. Notice that the tuned circuit is not connected to earth and has no *direct* connection to the detector circuit. The detector circuit *is* connected to earth however. The two aerial terminals offer alternative selectivity performance, terminal A gives very good selectivity while B is very wide. I never bother with B.





Make the coil carefully and wire up this crystal set according to the circuit diagram opposite and you will be rewarded with a really high performance crystal set of a type that was used in the very early days of broadcasting in 1930's in Australia.

This is probably my favourite crystal set!

THE DENCO PCC1 COIL

The PPC1 coil was a commercially manufactured by Denco Clacton Ltd and was popular among hobbyists not keen on going to the bother of winding their own fiddly little coils. As a child I wanted try one of these coils and sent away for one by mail order. It arrived a few days later in a little cloth bag, like a miniature pump bag, with protective wrapping inside.

The coil windings are entirely enclosed in what I can only describe as a cylindrical ferrite 'shell', the four very thin connecting wires exiting, two either side, from small apertures in the 'shell'. The performance of the circuit shown below I seem to remember was quite pleasing. Unfortunately I cannot find the set or the PPC1 coil at the moment, but here is a reproduction of the circuit diagram and data:



Crystal Receiver
Medium Wave Coil Type PCC.1

The author of this book particularly recommends to constructors who propose to build their own crystal set receivers to follow the instructions most carefully given in the text. However, if any readers have difficulty in making any of the components i.e. coils etc., it is suggested that they use crystal set coils made by Denco (Clacton) Limited Type PCC1 details and circuit diagrams are shown herewith.

TUNING
500pF solid
Dielectric.
Upper
Tag
GREEN
PCC-1
RED
BLACK
BLUE
GD 5
.002uF
50pF
5-Way
Tag
Strip
PHONES
EARTH
AERIAL

WIRING LAYOUT

These coils are most highly recommended. They also produce efficient components including high efficiency variable capacitors, ferrite rod aerials and multi-wave band coil sets. Many of these Denco com-



50pF
BRIMAR GD5
.02uF
BLUE
GREEN
RED
100
KΩ
200pF
OUTPUT
500
pF
BLACK

SCHEMATIC DIAGRAM

Coil Type PCC.1 ....
Germ. Diode GD.5 ......
500pF. Solid Dielectric
Variable Condenser....
5-Way Tag Strip ....

Actual Size

ponents can be obtained from your local radio component dealer but, in case of difficulty, write direct to this company at the following address:-

Denco (Clacton) Ltd.,
357/9 Old Road,
Clacton on Sea
Essex

Tel : Clacton 22807

This company will then either inform you of your nearest stockist of Denco components or, in case of difficulty, will be able to supply you direct - cash with order.

THE REPANCO DRR2 COIL

I recently rediscovered an old Repanco DRR2 Longwave / Mediumwave coil that must have been kicking around in my junk box since the 1970's.

The DRR2 coil was made by Repanco in Coventry. It came with a page of suggested circuit diagrams which I thought had been lost to the mists of time, but it recently came to light again, so I have now copied it below.

Once again I included an aerial trimmer which can be adjusted to improve selectivity.



SIDE VIEW
TOP VIEW
3
4
2
5
1
6
REPANCO COIL
CONNECTION
TAG LAYOUT
AERIAL
100pF (APPROX)
AERIAL TRIMMER
1
2
5
3
6
4
MW
LW
SWITCH
OA81
DIODE
500pF
TUNING
CAPACITOR
CRYSTAL
EARPHONE
RESISTOR
47KΩ
EARTH

The circuit diagram of the crystal set using the Repanco DRR2 coil

Repanco Ltd was formed by two ex-army signals engineers and from the earliest days of radio supplied crystal set kits and coils to radio construction enthusiasts.

The Repanco DRR2 coil was for medium wave and long wave intended for use in when building simple crystal set and valve radio circuits.

It consists of three coils; a Medium Wave coil at the top that includes a tapping point (for the aerial); a coupling coil or tickler in the middle; a lower coil which can be connected in series with to top coil to provide Long Wave reception.

I have built a quick crystal set with the coil and it provides good reception with excellent selectivity, so it must have a very good Q factor.

A 'lash-up' of the Repanco crystal set

The Repanco DDR2 coil was provided with a simple Foolscap size information sheet that showed four different radio circuits. Sadly the sheet does not give a huge amount of information and my copy is now rather tatty and faded - it is copied below:


DRR 2 with Self Biassing Circuit
5
+
OA90
1K
6
1
2
3
4
LW
.0005
.001
12μF
+
10K
OA 90
+
22 K
1.5v
Diodes normal Germanium
Bandpass Feeder Unit using two DRR2 Coils
Signal
+
5K
0-100μ/a
1K
5
6
1
2
3
4
.0005
.001
50μF
+
10K
+
22 K
1.5V
.01
*
DRG:-104E

* The larger the coupling condenser the smaller the coupling + the greater the selectivity.

Designed and published by
REPANCO LTD. [illegible] COVENTRY CV1 4

Simple crystal radio type circuits using the Repanco DRR2 coil


HT+
C1
·0003
6
5
1
2
3
4
S1
DRR2
L1
·005
1K
T1
SPEAKER
V1
V2
·0005
·05
R1
1M
C8
8μF 150V
470Ω
25μF
HT −
+
HT 6V
Band pass can be used with either circuit.
PHONES
·005
R2
2K
LW
C3
·0005
1M
S2
B
Y
TOP VIEW
DRR2

Valve circuits using the Repanco DRR2 coil

Repanco Ltd no longer produces radio coils and crystal set kits for the radio construction enthusiast, as it did in the early days of radio. In 1986 it was renamed Repanco Bartlett Ltd when it merged with Bartlett Electronics. The company moved from the Foleshill Road to Unit 24, Albion Industrial Estate, Endemere Road, Coventry CV6 5NT and now specialises in transformers and wound components and can design and manufacture to commercial customer requirements, their website is: http://www.repancobartlett.co.uk/

CRYSTAL EARPHONES


DIODE SYMBOL
ANODE
CATHODE
A
C
OA91
ACTUAL DIODE

Here is a good idea and well worth trying, to maximise the use of sound output from your crystal set why not use dual crystal earphones? Having an earphone in each ear helps to block out extraneous noises helping the listener to better concentrate on any weaker stations received.

Using the circuit below, one earphone makes use of one half cycle of the radio wave while the second earphone uses the other half cycle of the wave that would have previously gone to waste when using just one diode. Ensure that the diodes are connected up according to the diagram i.e. one diode is connected the opposite way round to the other.

Also try to make sure that the diodes and crystal earphones are similar to obtain the best results. (You could simply connect two crystal earphones to the same terminals of the single diode, but this would not be as efficient and the sounds would be much quieter.)


BETTER RESULTS WITH TWO CRYSTAL EARPHONES
Diode 1
OA91
a
c
c
a
Diode 2
OA91
Ensure that the Diodes
are connected as shown
i.e. one is the
opposite way around
to the other
47k
Phone2
47k
Phone1
Earth

A note about Crystal Earphones: It will be worthwhile buying several different ones from different sources as performance varies between manufacturers quite markedly. I have found the ones marked 'Japan' on the back are the most sensitive and therefore loudest, whereas ones marked 'Receiver' 'Taiwan' are often a little less sensitive and therefore quieter and sometimes more 'tinny' sounding.

As mentioned previously it has been noted that the OA47 diode will be of particular interest since it has the lowest forward bias voltage of any of the common diodes available. This will make the crystal set somewhat more sensitive and therefore louder. The US equivalent of the British OA47 is the IN34.

SPIDERS WEB' COIL

Here is an interesting concept sent in by Chris Dorna of the Vught North Scouts in the Netherlands. It is a crystal set made out of a coil wound in the form of a spiders web:

See more HERE.



Chris Dorna's Crystal Set with Spider Web Coil



Detail of the germanium diode



Close up of Chris Dorna's Spider Coil

LOOP THE LOOP!

A crystal set can also be made that does not need a large long wire aerial. If you have ever made a loop aerial for medium wave or long wave DX-ing, then it is a simple matter to add a diode, resistor and a socket to connect a crystal earphone that will allow reception of nearby stations.

See my section on Loop Aerials and ATU's for more constructional details.

A portable loop aerial, that incorporates a crystal set



The circuit diagram of the Loop Crystal Set. The loop is 10 turns of 7/0.2mm 'hook-up' wire wound on a 40cm (17") former made of attractive plastic edging strip available from many DIY stores. The loop is very directional in its pick up pattern, which can help eliminate interference from some stations by rotating the loop. The switch and additional capacitor allow tuning of the lower medium wave band from about 650 to 520 kHz. Having a loop with 50 to 60 turns of wire will tune into the Long Wave band.

DIODES - For Crystal Set Use - some notes by Felix Scerri

Germanium diodes for crystal set use.

Although I'm a fan of these new silicon schottky BAT 46 diodes, good germanium diodes still have a lot to offer, especially in terms of 'weak signal' sensitivity. Last night I did an experiment.

I sorted through quite a few of my hundreds of acquired random germanium diodes looking for particularly 'sensitive' ones. I tested this by tuning in a weak AM station and comparing the detected DC output level and also the apparent 'loudness' of the audio signal.

Even amongst germanium diodes of the same type, there was enormous variation all the way from excellent to poor! For very weak signals, germanium diodes 'detect' in the 'square law' region below the diode conduction 'knee', in a rather different part of the curve than with much stronger signals (way beyond the diode knee).

When testing germanium diodes for weak signal sensitivity, the inherent capacitance of the diodes is also a factor, and the 'tuning' may change somewhat and will need to be readjusted with every diode tested!

In the end, out of a large number of germanium diodes tested, I found three or four germanium diodes with excellent weak signal sensitivity and the rest were poor. One other interesting thing, good germanium diodes 'sound' different, rather more 'rounded and smoother' than the schottky's which tend to sound mercilessly clean, almost clinical. I also found almost no variation in weak signal sensitivity with my BAT 46 schottky diodes. Take your pick!

Regards, Felix Scerri VK4FUQ 14/03/2012

SOLDERLESS CONSTRUCTION IDEAS

For a novice the use of a soldering iron may seem a bit daunting at first and while the most reliable results will be obtained with a good soldered joint using a tag strip as shown below, the circuits can still be made without the use of a soldering iron.

5 WAY TAG STRIP

36 WAY TAG STRIP - TWO ROWS

The very simplest circuits could be wired together ,with a little ingenuity, with the component wires being held together in the grip of solderless crocodile clips, whereby the connecting hook-up wire is fixed to the croc' clip by a screw rather than solder.

For more the slightly more complex circuits a plastic Terminal Block (sometimes referred to as a choc' or chocolate block) can be utilised very effectively indeed. These are used in mains wiring and are available in various sizes; 2 Amp, 5 Amp, 15 Amp and 30 Amp. The 5 and 15 Amp Terminal Blocks I have found to be the most suitable. The various component wires can be trapped securely with the screw at each junction point. This method also makes it easy to change the components around when experiment with different circuits. See The EXPERMENTAL CRYSTAL SET for more details in Part 5**.**

'CHOCOLATE' TERMINAL BLOCK

The Ladybird book called 'Making A Transistor Radio' (also shown on the TRF Radio pages) detailed a very novel approach using brass screws with screw-cups to trap the component wires at each junction point:


Trapped Wire
No. 6 Brass Screwcup
¾" No. 6 Brass Screw
TESTING A CONNECTION

THE BRASS SCREW AND SCREW-CUP METHOD OF CONSTRUCTION


HOW THE CAPACITOR IS MOUNTED THROUGH THE BOARD
Aerial Lead
A
B
·0005
1
Earth Lead
2
THE COMPLETED CRYSTAL SET

A VERY SIMPLE CRYSTAL SET USING THE BRASS SCREW AND CUP METHOD

Crystal Sets Part Part 3 >

No AM radio stations or transmitters in your locality or country?

Spitfire
AM Transmitter

Has your local medium wave broadcast station closed or been moved to VHF/FM or Digital? Don't worry. You can still build and experiment with crystal sets and TRF radios by also buying or even building a simple low power AM transmitter. So, not only can you use your crystal sets but you can also run your own radio station that can be heard in and around your home - playing the music or programmes that you want to hear!

SSTRAN AMT3000: Superb high fidelity medium wave AM transmitter kits from SSTRAN. Versions available for 10kHz spacing in the Americas (AMT3000 or AMT3000-SM) and 9kHz spacing in Europe and other areas (AMT3000-9 and AMT3000-9SM). Superb audio quality and a great and well designed little kit to build: http://www.sstran.com/pages/products.html

POWER
GAIN
MODULATION
COMPRESSION
SStran
AMT3000

http://www.sstran.com/

Other AM transmitters available:

Spitfire & Metzo: Complete, high quality ready built medium wave AM Transmitters from Vintage Components: http://www.vcomp.co.uk/index.htm Vintage Components offer a choice of the high quality Spitfire and Metzo transmitters:

SPITFIRE AM Medium Wave Transmitter with 100 milliwatt RF output power:

http://www.vcomp.co.uk/spitfire/spitfire.htm

Spitfire
AM Transmitter

METZO AM Medium Wave Transmitter with built in compressor:

Gain
Comp
Mod
Metzo

http://www.vcomp.co.uk/metzo/metzo.htm

AM88 LP: A basic AM transmitter kit from North County Radio.
http://www.northcountryradio.com/Kitpages/am88.htm

LINKS:

BOWOOD ELECTRONICS - A friendly, helpful and very speedy source for many of your electronic components at prices that won't frighten your wallet!

THE FOXHOLE and P.O.W RADIOS - Simple crystal set receivers used by soldiers during the war and by prisoners of war (P.O.W.'s).

VINTAGE COMPONENTS - A great resource for crystal sets, components, valve radio kits and medium wave AM transmitters!

6V6 - Electronic Nostalgia and Vintage Components

Crystal Sets Part 3 >

Crystal Sets (Part1) | **Spider's Web Crystal Set (Part 3**

Crystal Set by Kenneth Rankin (Part 4) | **Experimental Crystal Sets (Part 5)** | **Crystal Radio Links**

^Top Of Page

Amateur Radio
MØMTJ Visit my amateur radio pages MØMTJ

Visit my Amateur Radio Pages >

Home | Contact | Site Map | Radio Stations & Memorabilia | Amateur Radio

Crystal Sets Introduction | Resistor & Capacitor Conversion Tables

www.mds975.co.uk © 2004 - 2014

Mike's Electronic Parts, LLC
Simple Crystal Radio Kit 2


https://www.mikeselectronicparts.com/
Connect Long Antenna Here
Connect Short Antenna Here
1
3
1N34A
2
A
Variable Capacitor
G
4
Ferrite Loopstick Antenna
47K
.001uf
Ceramic
Earphone
Ground
Mike's Electronic Parts
Mike's Electronic Parts


O
G
A
Top Side

Variable Capacitor

Parts List
1 - Ferrite Loopstick Antenna
1 - Variable Capacitor
1 - Germanium Diode 1N34A
1 - .001uf Capacitor Marked 102
1 - 47K Resistor
1 - 20 Million Ohm Ceramic Earphone
Antenna and Ground wire not include with parts

For short antenna connect a 15ft to 30ft length of wire to "1". For long antenna 40ft to 100ft connect to "4". It is best to use a long wire antenna. If you are not using the taps do not cut the wires. Doing so will cause the coil not to work. Various connections are, Connect 1 to 3 or Connect 2 to 3. Most volume can be had at 1 to 3 less volume but better selectivity connect 2 to 3 and the antenna connected at 1. It is best to solder the coil wire, not doing so may cause a bad connection and the radio will not work.
Drawn By: Scott Lowe
This Kit can be bought at my web site Part Number CRK#2 Kit.

https://www.mikeselectronicparts.com/

THE SMITHSONIAN INSTITUTION

The Smithsonian Institution is home to more than 141 million objects, ranging in size from insects and diamonds to locomotives and spacecraft. It is the world's largest museum complex, comprising 15 museums and galleries and the National Zoo in Washington DC, and two additional museums in New York City. Millions of visitors each year visit the nation's capital to view such treasures as the Hope Diamond, the Star Spangled Banner, and the Wright Flyer. A broad range of exhibits ensures a fun and educational experience for young and old alike.

One of the world's leading scientific research centers, the Institution has facilities in eight states and the Republic of Panama. Research projects in the arts, history and science are carried out by the Smithsonian all over the world. Some of the Smithsonian's research centers include the Smithsonian Astrophysical Observatory in Cambridge, Massachusetts, the Smithsonian Marine Station at Link Port, in Florida, and the Smithsonian Tropical Research Institute, in Panama.

For membership information of pre-visit planning material, write or call the Visitor Information and Associates Reception Center, Smithsonian Institution, Washington, D. C., 20560, (202) 357-2700 (voice), (202) 357-1729 (TTY). You may also visit the Smithsonian through our web site, www.si.edu.

HISTORY

James Smithson (1765 –1829), a British scientist, drew up his will in 1826 naming his nephew, Henry James Hungerford, as beneficiary. Smithson stipulated that, should the nephew die without heirs (as he did in 1835), the estate would go to the United States to found "at Washington, under the name of the Smithsonian Institution, an establishment for the increase and diffusion of knowledge..."

On July 1, 1836, Congress accepted the legacy bequeathed to the nation by James Smithson, and pledged the faith of the United States to the charitable trust. In 1838, following approval of the bequest by the British courts, the United States received Smithson's estate—bags of gold sovereigns—then the equivalent of $515,169. Eight years later, on August 10, 1846, an Act of Congress signed by President James K. Polk, established the Smithsonian Institution in its present form and provided for the administration of the trust, independent of the government itself, by a Board of Regents and Secretary of the Smithsonian.

SMITHSONIAN MUSEUMS, GALLERIES AND ZOOS

Smithsonian Institution [illegible]
Anacostia Museum
Arthur M. Sackler Gallery
Arts and Industries Building
Cooper-Hewitt, National Design Museum
Freer Gallery of Art
Hirshhorn Museum and Sculpture Garden
National Air and Space Museum
National Museum of African Art
National Museum of American History, Behring Center
National Museum of the American Indian
National Museum of Natural History
National Portrait Gallery
National Postal Museum
National Zoological Park
Renwick Gallery
S. Dillon Ripley Center
Smithsonian American Art Museum

SMITHSONIAN®

CRYSTAL RADIO™

WARNING!
ONLY FOR USE BY CHILDREN OVER 8 YEARS OLD.

READ THE INSTRUCTIONS BEFORE USE,
FOLLOW THEM AND
KEEP THEM FOR REFERENCE.
STORE THE SET OUT OF REACH
OF SMALL CHILDREN.

PLEASE KEEP A NOTE OF OUR NAME AND ADDRESS DETAILS FOR FUTURE REFERENCE. IN EUROPE CONTACT:

CE

NSI SIMM GAmbH
D 76162 KARLSRUHE
GERMANY
49-0721-9584-116

PLEASE BE SURE TO READ THE ADVISE FOR SUPERVISING ADULTS AND THE SAFETY RULES CONTAINED IN THIS BOOKLET.

©2002 SMITHSONIAN® INSTITUTION
NATURAL SCIENCE INDUSTRIES, LTD.
910 ORLANDO AVE.
WEST HEMPSTEAD, N.Y. 11552

PRINTED IN USA

ITEM NO. 3261-08

ADVICE FOR SUPERVISING ADULTS:

- READ AND FOLLOW THESE SAFETY INSTRUCTIONS, THE SAFETY RULES AND KEEP THEM FOR REFERENCE.

- SUPERVISING ADULTS SHOULD DISCUSS ANY WARNINGS AND SAFETY INFORMATION WITH THE CHILD BEFORE COMMENCING THE ACTIVITIES.

SAFETY RULES:

- DO READ THE INSTRUCTIONS BEFORE USE, FOLLOW THEM AND KEEP THEM FOR REFERENCE.
- DO KEEP YOUNG CHILDREN AND ANIMALS AWAY FROM THE ACTIVITY AREA.
- DO STORE THE SET OUT OF REACH OF YOUNG CHILDREN.

Radio Technology

Facts about early crystal development

Several inventors receive credit for developing a "crystal detector", a device which can pass current better in one direction than the other in an electrical circuit. In Germany, in the 1870's, Karl F. Braun noticed this property in certain mineral substances. Commercial development required a technology that would be suitable. This came with the advent of wireless communication and radio after 1900.

In Japan, Wichi Torikata investigated many minerals, including zincite, pyrolusite, iron pyrites and galena. In the United States, Greenleaf W. Pickard, associated with the Wireless Specialty Apparatus Co. of Boston, conducted extensive experiments as well. He became well known for the PERIKON Detector which employed zincite and chalcopyrite. The early 20th century work was generally done between 1900 and 1912. Included among the scientists is General H.H.C. Dunwoody of the U.S Army who developed a carborundum detector.

Until radio broadcasting began in 1920 (Station KDKA Pittsburgh) experimenters utilized the crystal detector for radiotelephone communications and for reception of certain Morse Code signals. There was also extensive use by the U.S. Navy and other maritime services.

The modern crystal diode, such as provided with your set, is a spin-off of radar technology developed during World War II. The basic principle, however, remains the same, i.e. to remove the AUDIO (speech, music or Morse-Code) from the radio frequency carrier wave. In one early Pickard crystal design (left) a stiff metal point is adjustable over the crystal surface. In a later version a "Catswhisker" spring impinged on a piece of galena (right) and was varied to give a louder signal.





Your Smithsonian Smart Lab Crystal Radio Set contains the following items


COIL
TUNING KNOB
CRYSTAL RADIO
BASE
VARIABLE CAPACITOR
(3) SPRING CONNECTORS
(3) SCREWS
EARPHONE
"YELLOW" ANTENNA WIRE
DIODE
"RED" GROUND WIRE

Shown below is a typical wiring diagram of your crystal radio.


ANTENNA
TUNED CIRCUIT
CRYSTAL DETECTOR
HEAD PHONES
COIL
GROUND

Radio Technology (cont'd)

When these two different energy waves are put together by the mixer stage of the transmitter, the resulting wave, which is the signal that the station broadcasts, looks like this:



AM Broadcast Wave

The signal is called a MODULATED wave. You will notice that each of the waves is the same length, but the heights vary. Since the height of a wave is called its AMPLITUDE, The type of transmission that WXYZ uses is called AMPLITUDE MODULATION. That's why WXYZ is called an AM station.

The crystal radio that you built works in just the opposite way as the radio station. The modulated signal broadcast by WXYZ is "picked up" by the antenna on your radio.

The antenna is connected to the tuner circuit of the radio, which is made up of a coil of wire and a variable capacitor connected together. As you move the tuning knob, you are able to select, or isolate, the particular

This signal is then DEMODULATED by the diode, separating the voice (audio) wave from the carrier wave.

The voice (audio) wave then moves to the earphone, where it is changed back into sound waves that you can hear.

Learn the basic electronic symbols

Before starting to assemble your Smart Lab Crystal Radio please learn the basic electronic symbols that are shown on the plastic base.



Explanation of components

Variable Capacitor - It is used to tune the radio to a station. The leads that are soldered to the lugs are used to connect it to the circuit.

Diode - A small crystal is sealed inside with leads connected to it. Pay careful attention to the position of the black bands painted on the diode close to one end.

Coil- This is a radio-tuning COIL. It was made by winding enameled copper wire around a paper core 80 times. The leads have been stripped and tinned so it can be connected to the circuit.

Earphone - It contains a small crystal that can make enough electricity to drive a metal diaphragm to produce sound. The leads have been stripped and tinned so it can be connected to the circuit.

Antenna - This is a wire used for radiating or receiving radio waves.

Ground - This is a wire used to make a electric connection with the earth or other type of grounding source to create a common return for an electric circuit.

DEAR CUSTOMER:

If we made an error and left something out of this set, or if something is damaged, we are sorry and wish to correct our error.
Please DO NOT return the set to the store where purchased, as the store does not have replacement parts. Instead, write us:

Please include:
1. **Date of Purchase**
2. **Where purchased**
3. **Price paid**
4. **Model Number**
5. **Name of item**
6. **Brief Description of Problem**
7. **Include Sales Slip**

We will do our best to satisfy you. Send your letter to:

NATURAL SCIENCE INDUSTRIES, LTD.
910 ORLANDO AVENUE
WEST HEMPSTEAD, N.Y. 11552-3942
ATTENTION: QUALITY CONTROL DEPT.

How to assemble your Crystal Radio

Before starting, it's important to assemble the parts correctly. Carefully read the following instructions step by step and have fun . . . half the fun is knowing you made your very own crystal radio.

Step ①


TAPERED END OF SPRING CONNECTOR
HOLE IN BASE
SPRING CONNECTOR
BASE
CRYSTAL RADIO
(2) SPRING CONNECTORS (SHOWN IN PLACE)
TWIST HALFWAY THROUGH BASE
SIDE VIEW

A. Locate the three Spring Connectors.
B. Insert one of the Spring Connectors (tapered end first) into one of the three holes on the Base.
C. Push down on the Spring Connector and twist to the right until the Connector is approximately half way through the base.

NOTE: Check to see if the Spring Connecter is inserted halfway through the Base by turning Base upside down (see insert).
D. Insert the remaining two Spring Connectors into the holes on Base the same way.

Radio Technology

Now that you have your crystal radio assembled and working, it is time to take a brief look at how it works. To do this you are going to take an imaginary trip to a radio station WXYZ, in anytown,USA.

When you arrive at WXYZ, you are met by the station's general manager, Mr. Smith, who is going to show you around.

First, Mr. Smith takes you to a STUDIO, a special room that a program comes from. There is a lot of equipment, including dials and switches, record players, lots and lots of records, and microphones.

Mr. Smith tells you that when you talk into one of the microphones, your words go into the station's electronic equipment. There, it is mixed with the station's carrier wave, and sent out into the air through the station's transmitting antenna - that tall tower you saw on top of the radio station building.

Then Mr. Smith takes a piece of paper and a pencil, and draws diagrams to show you what happens. He begins by saying that all energy travels in waves, and since the sound we make when we talk is a form of energy, it might look something like this:



Sound Wave

The station's carrier wave is a radio wave, which is also a form of energy, which looks something like this:



Radio Carrier Wave

How to properly operate your Smart Lab Crystal Radio and troubleshoot

After you have attached all the wires, carefully read the following instructions to make sure your crystal radio operates properly.



A. Place the earphone in your ear and turn the Tuning Knob clockwise and counterclockwise until you pick up the strongest signal.
Note: If you do not pick up a strong signal or do not hear anything, please read some of the troubleshooting solutions explained below.

TROUBLESHOOTING HINTS

1. There may be a bad connection caused by improper assembly of your radio. Check all the spring connectors to make sure the wires are attached correctly. If a wire is loose or the bare wire is not making good contact with the spring connector, the radio may not work.
2. If the uninsulated part of the Antenna wire touches anything other than the Antenna Connection on the radio, the radio may work improperly or not at all..
3. If the bare stripped end of the Ground wire is not wrapped tightly around a water pipe (so that it makes good contact), try taping the wire to the shiny part of the pipe using duct tape. If the pipe is dull or rusty, use a piece of sandpaper to gently sand the area where the wire makes contact. Also make sure the wire doesn't touch anything other than the Ground Connection or the radio may not work properly.
4. You may live in an area where radio reception is generally poor. Instead of trying to use your radio during the day, try at night when many radio stations are received better.
5. The Antenna on your radio is a very important component. Make the Antenna as long and high above the ground as possible. If you live in a multi-story dwelling the highest floor should be used when operating the radio. Insulated bell-wire, which is available in hardware stores, makes a very good substitution for your present Antenna.

How to assemble your Crystal Radio (cont'd)

For this step you will need the variable capacitor, (3) screws and turning knob. Be carefull not to misplace the small screws when assembling.

Step ②



A. First place the Variable Capacitor up into the base so the holes on the capacitor line up with the holes on the base.
Note: When you do this be sure the wire leads face inward toward the base as shown and lug faces upward.

B. Next insert the two small screws into the holes on top of the Base and tighten using a small phillips screwdriver.

Step ③



A. Place the Tuning Knob into position on top of the rectangular lug on the Base.
B. Insert a small screw into the hole in the Knob and tighten using a phillips screwdriver.

How to assemble your Crystal Radio (cont'd)

Step ④ For this step turn the Base upside down.


DO NOT CONNECT ANY WIRES HERE
GROUND CONNECTION
ANTENNA CONNECTION

A. Turn the Base upside down.
B. Connect one wire to the Antenna spring connector by bending the spring slightly to one side and inserting the wire through as shown in inset.
C. Connect the other wire to the Ground spring connector in the same manner.

NOTE: Do not connect any of the wires to the Diode spring connector or your crystal set will not work properly.

Step ⑤


NOTE: Make sure the Plated Ends of the Coil wires are making contact to the Spring Connections.
COIL
WELL
GROUND CONNECTION
DIODE
CRYSTAL RADIO
ANTENNA CONNECTION
DIODE CONNECTION
BLACK BANDS ON DIODE MUST FACE TOWARD THE DIODE CONNECTION

A. Next place the Coil in the well of Base with the wires hanging loosely toward the connectors .
B. Connect one of the plated ends of Coil wires to the Ground Connector by bending the Spring Connector as shown in inset. Connect the other Coil wire to the Antenna Connector.
C. Place the Diode between the Diode and Antenna Connections carefully noting the black bands face toward the Diode Connection.
D. Connect ends of Diode wires to Antenna and Diode spring connectors shown.

How to attach the earphones


GROUND CONNECTION
TWO WIRE LEADS
EARPHONE
CRYSTAL RADIO
DIODE CONNECTION

A. Locate the earphones and unravel the end of the wire so there are two wire leads.
B. Attach one wire lead to the Ground Connection and the other to the Diode Connection as explained earlier.

Final assembly and operation


ATTACH LONG STRIPPED END TO A METAL COLD WATER PIPE
TAPE YELLOW ANTENNA WIRE TO WALL
STRIPPED END
SHORT STRIPPED END
RED GROUND WIRE
CRYSTAL RADIO
ANTENNA CONNECTION

• NOTE •
FOR CLARITY, THE EARPHONE HOOKUP IS NOT SHOWN IN THIS STEP

A. Locate the Red Ground and Yellow Antenna wire.
B. Attach the stripped end of Yellow Antenna wire to the Antenna Connection on the Base.

Note: The Antenna should be strung in a straight line away from power lines and large metal objects. We suggest taping it high up on a wall using masking tape as shown.

C. Next attach the short stripped end of the Ground wire to the Ground Connection.
D. Attach the Long stripped end to a metal cold water pipe, metal radiator pipe, etc., near where the radio will be used. Have a adult help you with this since some pipes may be hot.

Note: If there is not enough stripped, bare wire to wrap around a pipe then ask an adult to strip more insulation off the end using a pair of wire strippers.

Germanium vs Silicon Diode Testing: Read this document carefully, so you will not be the victim of cheap knock-off or the wrong type diodes.

The general rule is that ***SILICON*** diodes have a voltage drop across the Anode to Cathode of 0.7 V (7/10 tenths), and the ***GERMANIUM*** diodes have a voltage drop of 0.3 V (3/10 tenths) more or less. Either diode voltage drop (silicon or germanium) will display a reading within approximately 5% of these readings.



0.3V <GERMANIUM

GERMANIUM diodes exhibit .3 (3/10 volt) drop across CATHODE to ANODE.

NOTE: Most DVM has the Diode Test Mode symbol to test voltage drop across the diode.

SILICON diodes exhibit .7 (7/10 volt) drop across CATHODE to ANODE.

0.7V <SILICON

Most digital meters (DVM) have a switch setting ▶| that is used to measure voltage drop across these diodes. This setting is usually indicated by a diode symbol to let the user know the DVM is capable of measuring forward bias voltage. This setting will tell you immediately if the diode is a **germanium**, or **silicon** diode. You need to set the selector switch on your meter to the diode test symbol ▶|.

Measuring Forward Bias Voltage

To measure the forward bias voltage characteristic you connect the black probe of your meter to the cathode terminal. The cathode terminal is on the end with a band. You then connect the red probe to the anode terminal.

Set your DVM/DMM to the *diode test mode* ▶|, it should provide you with the respective voltage drop. If the figure is 0.3 V or less, the diode is a *germanium* type. If the voltage drop is 0.7 V or less the diode is a *silicon* diode.

Sensitivity and Forward Bias Characteristics:

The sensitivity of a diode to radio waves depends upon its *forward bias voltage*. This is the voltage across the diode terminals. When it falls below this threshold value, the diode will stop conducting. Obviously, the lower this threshold value is, the greater the sensitivity of the diode to the weak radio signals.

CONCLUSIONS:

When comparing germanium diodes with silicon diodes of similar forward bias voltage, silicon diodes do not perform as well as the germanium.

Germanium has many properties that silicon diodes do not have. Germanium requires very little forward current. Forward current in a germanium diode is in the *micro*ampere region, while silicon diodes require *amperes*. This makes *germanium* a much better choice for both medium and high frequency radio signals.

Germanium also exhibits a very low, point-contact junction capacitance, while the silicon diode has much higher capacitance. A low junction capacitance allows germanium diodes to operate more effectively at high RF frequencies.

In addition, reverse leakage current for germanium diodes is in the magnitude of 1000, much more than silicon. This makes the non-linear characteristics of the germanium diode much more effective for RF detection and demodulation than silicon.

Therefore, our conclusions are; germanium diodes provide the best performance in crystal radios, RF probes, HF, and VHF signal detection.


Antenna
1N34A Diode
1N34A Diode
Headphones
Ground
A simple Crystal Radio


Level 2, Crystal Radio
ANT
L1 = 25 to 40 turns
Antenna tap at 10 turns.
L1
365pf variable
1N34A
Germanium Diode
.05 pf
Head Phones
GND
BuxComm


ANTENNA
Level 3, Crystal Radio
IN34A - DIODE
47-k RESISTOR
CRYSTAL EAR-PIECE
44 turns on toilet paper core.
.001-uf CAPACITOR
365-pf VARIABLE CAPACITOR
Ph
Ph
GROUND
BuxComm

BuxComm High Quality, CRYSTAL RADIO ANTENNA KIT, $14.95 cat# 50CRAK

This Crystal Radio Antenna kit consists of 50 feet of #16 AWG insulated & stranded copper antenna wire, two heavy-duty, Delrin, UV resistant antenna insulators and instruction sheet.


Joule Thief
Résistance
500- 2000 Ohms
NPN
B C E
AA
DURACELL
ALKALINE BATTERY

The joule thief circuit.


Ferrite toroid core
with two lengths of
small diameter wire
e.g. 26 gauge,
30 gauge, ...
resistor
1kΩ
AA battery
flat side is facing
out of the page
transistor
2N4401
C
B
E
one leg is longer
than the other
LED (Light Emitting Diode)
(C - Collector, B - Base, E - Emitter)

Transistor - The legs of the transistor can be determined by noticing that there's a flat side to the transistor case. See the diagram above. A large number of transistors have been reported to work: 2N4401, NET123AP, BC547B, 2SC2500, BC337, PN2222, to name just a few.

LED - One leg of the LED is longer than the other leg. Use this to determine which one goes where. See the diagram above.

Resistor - The diagram says use a 1 kilo ohm resistor but I've used an 820 ohm one just fine. I've also seen a 2 kilo ohm one in use. Use whatever works for you. You can also use a potentiometer (a variable resistor) so that you can easily adjust it to select the resistance that gives the best light.

Toroid ferrite core - Some people have gotten these by opening up compact fluorescent lightbulbs (CFLs). I took mine out of some device whose original function I don't know. To get it working, my first one had just 13 turns for each wire and I used a 30 gauge wire and a 26 gauge wire. The wire must be insulated. A variety of number of turns will work. This is something you can play with. Look at the diagram carefully to determine where the wires connect to.

Its a Rubbish Challenge

Dog Light

Joule Thief

electronics circuit


+
1.5v
1kΩ
BC547
−
− C
B
E +


resistor
1kΩ
Ferrite toroid core
with two lengths of
small diameter wire
e.g. 26 gauge,
30 gauge, ...
AA battery
flat side is facing
out of the page
transistor
2N4401
C
B
E
one leg is longer
than the other
LED (Light Emitting Diode)
(C - Collector, B - Base, E - Emitter)

COUPONS AVAILABLE ACTIVATE COUPONS

advertisement

MAKING A SIMPLE JOULE THIEF (MADE EASY)

Technology (/technology/) > Leds | by ASCAS (/member/ASCAS/) Follow

195,691 573 165

Posted Dec. 24, 2011 | BY-NC-SA



(https://cdn.instructables.com/F3C/UXVH/GWF5TL98/F3CUXVHGWF5TL98.LARGE.jpg)


(https://cdn.instructables.com/FB5/ROY8/GWHN3

Mini
Version
(https://cdn.instructables.com/FE8

(https://cdn.instructables.com/F3C

Today I am showing you how to make a very simple joule thief. A joule thief has many applications, the best gadget that I made with was a "Water Powered Lamp", soon I'm going to post on a guide about it but first I need to post this guide. I used an iPhone 4S as my camera :)))

What Is A Joule Thief ?

To simplify everything, a "joule thief" is a circuit that helps drive an LED light even though your power supply is low. What can we do with it? We can use it to squeeze the life out of our old, almost drained, non functioning batteries. This project can also be considered as a green and environmental experiment, we can also use it as a flashlight that can be ran by an old, weak, almost drained battery. I even tried to use my water powered battery from my previous instructable the "Water Powered Calculator (https://www.instructables.com/id/Water-Powered-Calculator/)", the project was featured and displayed in instructable's front page in the "Technologies" category.

My Next Projects That Involves A Joule Thief: (soon to be posted)
- Water Powered Lamp
- Water Powered Flash Light
- Dead Battery Drainer Lamp

Here's A Video From Make Magazine:

Add Tip Ask Question

Step 1: Parts and Materials


Round Ferrite Toroid
NPN Transistor (2N3904)
1K Resistor (BRN-BLK-RED)
LED (White)
Weak/Used Battery
Battery Tester
+AA
03-2016
Energizer
REPLACE WEAK GOOD
Ulta-Lit
Soldering Lead
Coated Copper Wire

(https://cdn.instructables.com/FWP/53TF/GWJOGGU3/FWP53TFGWJOGGU3.LARGE.jpg)

The Parts Needed Are: (click the item to know where to find/ buy)

- Round Ferrite Toroid (can be found in old CFL bulbs)
- Old/ Used Batteries (can be found in garbage cans)
- NPN Transistor (2N3904) (http://www.radioshack.com/product/index.jsp?productId=2062609)
- 1K Resistor (BRN-BLK-RED) (http://www.radioshack.com/product/index.jsp?productId=2062343)
- LED Light (http://www.radioshack.com/product/index.jsp?productId=3096133)
- Battery Tester (http://www.tooldistrict.com/Ulta-Lit-Battery-Tester-5001-p/901233.htm) (optional)
- Soldering Lead (http://www.radioshack.com/product/index.jsp?productId=2062717)

- Copper Wire/ Magnet Wire (http://www.radioshack.com/product/index.jsp?productId=2036277)
- Battery Case/ Holder (http://www.radioshack.com/product/index.jsp?productId=2062247)

I want to share something. Here in the Philippines electronic parts are extremely cheap, they are extremely far cheaper from
radio shack, for example one transistor costs (2 phil. pesos - 6 US cents), a LED cost (9 phil. peso - 29 US cents) and a 1K resistor cost (25 phil. cents - 0.8 US cents). I usually buy thing from Deeco or Alexan. Usually prices here are 15x cheaper from radio shack. Price conversion - $1 US Dollar = P0.31 Philippine Peso (12/24/11).

Add Tip Ask Question

Step 2: Schematic Diagrams


Single Battery Cell:
Alkaline, NiCD, NiMH
(0.3 - 1.5 V typ.)
Hand-wound
ferrite toroid
1 k
LED:
Blue or
White
2N3904

(https://cdn.instructables.com/F3N/S5I7/GWKD43C0/F3NS5I7GWKD43C0.LARGE.jpg)


LED
-
+
2n3904
Transistor
1k Resistor
- Power +
Toroid bead
On/Off


Transistor Terminals
E B C
2N3904
(NPN Transistor)
LED Terminals
Negative Side (Cathode)
Flat Edge
Short Wire
Postive Side (Anode)
Long Wire

(https://cdn.instructables.com/FN0/CPE6/G\ (https://cdn.instructables.com/F5P/M7FM/GWINSM3D/F5PM7FMGWINSM

Here are the schematic diagrams that are involved with the joule thief circuit.

Add Tip Ask Question

Step 3: Winding Wire at the Toroid



(https://cdn.instructables.com/FLD/JSNY/GWF5TL99/FLDJSNYGWF5TL99.LARGE.jpg)

https://cdn.instructables.com/FXL/LCWG/GWF6FORD/FXL



https://cdn.instructables.com/FZU/TFUK/GWINSM20/FZU

First, connect both ends of the copper wire before wounding, be sure to remove the insulation. Then try to solder the ends so it would not split up. Second, wind the wire until you run out of space in the round ferrite toroid. I have some tips for you, try to use a gauge #22 enamel coated copper wire for better performance, oh! my last tip is that "the more you wind the wire to the ferrite toroid the better".

Add Tip Ask Question

Step 4: Soldering the Resistor



(https://cdn.instructables.com/FE4/7BQZ/GWHN3BMQ/FE47BQZGWHN3BMQ.LARGE.jpg)

Solder the resistor with one end of the wounded ferrite toroid's wire. Oh! also don't forget to level the other end of the resistor with the other unused wire from the wounded ferrite toroid.

Add Tip Ask Question

Step 5: Soldering the Transistor


2N3904 NPN Transistor
Terminals
2N39
04
E B C
E = Emitter
B = Base
C = Collector

(https://cdn.instructables.com/FF3/I3O4/GWE5TL97/FF3I3O4GWE5TL97.LARGE.jpg)

Solder the proper connections to the transistor. For the emitter - connect another wire, the wire will be connected to the negative part of the battery. For the base - solder the other end of the resistor to the base. For the Collector Solder the unused wire of the ferrite toroid.

Add Tip Ask Question

Step 6: Soldering the LED


LED Terminals
Flat
+
Anode
−
Cathode
−
+
2N3904 NPN Transistor Terminals
2N39 04
E B C
E = Emitter
B = Base
C = Collector
B
C
E

(https://cdn.instructables.com/FBG/PC16/GWINSLNY/FBGPC16GWINSLNY.LARGE.jpg)

Solder the shorter wire of the LED to the tansistor's emitter and the longer part of the LED to the transistor's collector. After all that, you can now trim the excess wires.

Add Tip Ask Question

Step 7: Time to Look for Old Batteries


Energize
REPLAC
WEAK
GOOD

(https://cdn.instructables.com/F78/J93B/GWF5TM0Q/F78J93BGWF5TM0Q.LARGE.jpg)

(https://cdn.instructables.com/FX4/JNKD/GWINSM4V/FX4JNKDGW

PHILIPS
DURACELL
Kodak
DURACELL ULTRA
Energizer
HIGH ENERGY
High-Tech ALKALINE
SUPER
EVEREADY
RED POWER

(https://cdn.instructables.com/F40/8TOM/GWINSM

Use your battery tester to confirm that your battery is close to death. The tester is only an optional tool, it's just used to determine the battery's remaining power.

Add Tip

Ask Question

Step 8: Time to Test It - You're Done !!


AA FORMAT · E91
LR6 · AM3 · 1.5V

(https://cdn.instructables.com/F3C/UXVH/GWF5TL98/F3CUXVHGWF5TL98.LARGE.jpg)



(https://cdn.instructables.com/FGU/NX0F/GWHN3BZH/FGUNX0FGWHN3BZH.LARGE.jpg)

The wire connected to the transistor's emitter should be connected to the battery's negative side and the remaining wire of the ferrite toroid should be connected to the battery's positive side. Oh! one more thing, I advise everyone to use a battery case or attach a conductive magnet for each wire, so you wouldn't hold it all the time.

Add Tip Ask Question

Eliminate Your Power Bills!

Build Your Own Energy Generator for Just $49

Tesla Energy

advertisement



29 Travel Essentials We Won't Leave Home Without | Cartageous

Cartageous

advertisement

8 People Made This Project!

"Joule Thief" LED Night Light

by **ledartist** on September 2, 2011

Table of Contents

"Joule Thief" LED Night Light 1

Intro: "Joule Thief" LED Night Light 2

Step 1: Features 2

Step 2: Technical Overview 3

File Downloads 4

Step 3: Assembly 4

Step 4: Performance 5

Step 5: PCB & Kit 6

Related Instructables 6

Comments 6



Author:ledartist My Blog
I work with LEDs and microcontrollers to create beautiful objects.

Intro: "Joule Thief" LED Night Light

I have many used batteries around. Remote controls, cameras, many electronic gadgets all use batteries, mostly AA size. I always felt guilty for throwing away the used batteries. I know there are rechargeable batteries, but many electronics don't work well with rechargeables.

I also know that those "used" or "spent" batteries usually have some juice left in them. So to come up with a good use of used batteries, I've created a LED night light.

I like having a little night light on when I sleep. LEDs are perfect for this purpose, because they are energy efficient, and good at providing low intensity illumination.

This LED night light operates with just one battery. It utilizes a little circuit called Joule Thief to boost voltage out of an AA battery. I also added a light sensor to turn it on automatically when the surrounding is dark.

The circuit is energy efficient, and requires very low voltage to work. So it effectively sucks every bit of energy out of batteries. This type of circuit is often called "Joule Thief", because it works as though stealing every bit of energy (Joule is a unit for energy) out of battery.

I'm calling this project Night Joule Thief.



Step 1: Features

Here are the highlights of the Night Joule Thief.

- Compact & streamlined design
- Uses only one AA battery (or any 1.5V battery you can hook up to)
- Easily adaptable to different size batteries - hook up holes to attach home made clips
- Two white LEDs
- Automatic turn on via a light sensor (adjustable sensitivity level)
- Energy efficient - works even with a run-down battery, down to 0.6V
- Choice of through-hole only components or SMD - mix & match on the same PCB





Image Notes
1. Through-hole version.
2. SMD (Surface Mount Device) version. Hard to believe this is the same circuit, but it works exactly the same as one on left. Ok, the LEDs are slightly less bright.

Image Notes
1. AAA battery inserted with a help of small magnets.
2. SMD version - very low profile.
3. Standard AA battery snugly fit in the clips.



Image Notes
1. Other sizes, such as D cell can be attached by making a pair of little metal clips. Just cut and bend paper clips.

Step 2: Technical Overview

"Joule Thief" circuit is an inductor based voltage booster circuit to light LEDs with low supply voltage. As most of you know LEDs need higher than 2V (3V for white LEDs), so usually at least two batteries are needed to light them. The "Joule Thief" circuit was published in 1999 and has been quite popular. You can see the principle of the circuit here. http://en.wikipedia.org/wiki/Joule_thief

My version is a variation that uses single coil inductor, to make the inductor easily obtainable. I design the circuit using readily available parts only, to make it an ideal DIY project.

Circuit

The L1, Q2, Q3, C1, R2, and LEDs D1 & D2 make the Joule Thief. And the Q1, and the rest of the parts form the light sensor. CdS is the device that actually senses the light and change its resistance accordingly. When the surrounding of CdS is bright, it has low resistance (anywhere around 1k to 3k ohm), and when the surrounding is dark, the resistance goes up to 100k to 3M ohm range. So in this circuit, the base voltage of Q1 is controlled by the ambient light level. When the base voltage of Q1 goes more than 0.6V below the power supply(battery) voltage, current goes through R1, turning the Joule Thief circuit on.

The Joule Thief circuit is boosting the battery voltage up to over 6V to light two LEDs in series. LEDs light up with the battery voltage as low as 0.6V! Amazing!

PCB layout can be downloaded as an editable PDF, so you can etch your own board if you like. Custom 2 layer PCB and kit are available for sale as well. The 2 layer PCBs have extra front pads for SMD where possible, so you can build the same circuit with SMD parts as you wish.

Parts List
1x CdS Photoresistor (rated 3k - 0.3M ohm) (CDS1)
1x 1k ohm (R1)
1x 100k ohm (R2)
1x 10k ohm (R3)
1x 50k ohm trim pot (VR1)
1x 22pF (C1)
1x 470uH (L1) (anywhere between 22 - 470uH would work - might have to reduce the C1 value however)
1x 2N5401 or equivalent (Q1) (or just about any general purpose PNP transistor, such as PN2907, 2N3906, etc...)
2x MPSA06 or equivalent (Q2, Q3) (or just about any general purpose NPN transistor, such as PN2222A, 2N3904, 2N4400, etc...)
2x LED (D1, D2) (Just about any LEDs can be used)
2x Battery Clips



Image Notes
1. Light sensor circuit with sensitivity adjust.





File Downloads

NightJouleThief-PCB.pdf (54 KB)
[NOTE: When saving, if you see .tmp as the file ext, rename it to 'NightJouleThief-PCB.pdf']

Step 3: Assembly

The assembly is very straight forward. Insert the parts into the PCB, and solder them. Start with small components, follow the order below.

Parts List (in assembly order)
1x 1k ohm (R1)
1x 100k ohm (R2)
1x 10k ohm (R3)
1x Photoresistor (rated 3k - 0.3M ohm) (CDS1)
1x 50k ohm trim pot (VR1)
1x 22pF (C1)
1x 470uH (L1)
1x 2N5401 or equivalent (Q1)
2x MPSA06 or equivalent (Q2, Q3)
2x LED (D1, D2)
2x Battery Clips

Transistors, and LEDs have polarities, so make sure to insert them in the correct orientation. Battery holders need a bit of force to snap into the holes. They attach from the back side of PCB as you can see in the picture.

Once everything is soldered in place, double check the part placement, orientation and solder joints. Then insert a battery. The polarity is marked on the front side of PCB.
If you don't see the LEDs light up, don't worry. The room is probably too bright. Take a piece of black paper or tape and block the light from hitting CdS light sensor. (and/or darken the room) If the LEDs still don't come on, turn the trimmer (the little orange thing) with a screw driver, counter clockwise. This makes the sensor less sensitive to light, so the LEDs will come on by just placing the sensor under shade, or turning off the room light.







Image Notes
1. Resistors soldered in.

Step 4: Performance

This little night light performs very well. For starters, the brightness is not bad for using just one AA battery. I've been using these as flashlights as well.

The light sensor also works very well. Once adjusted, the light is steadily off during the day, even when you put the sensor under shade. Only when you block the sensor by a black object, the light would turn on. Yet after dusk, the light would come on when you turn off the room light.

A fresh battery lasts for weeks if only used as a night light. And the best use of this light is to "revive" used batteries. Those batteries from remote controls, cameras, etc. usually have quite a bit of juice left in them. Joule Thief sucks the juice out of those batteries till the last drop. It's like getting free energy when you can use something that were going to be thrown out.



Step 5: PCB & Kit

If you are handy, you can etch your own PCB, and build this night light entirely DIY.

However, to spread the goodness of Joule Thief and to contribute to the greener earth, I am putting together the PCB & kit available.

The details can be found here: http://www.instructables.com/community/Joule-Thief-LED-Night-Light-Kit-PCB/





Image Notes
1. Through-hole version.
2. SMD (Surface Mount Device) version. Hard to believe this is the same circuit, but it works exactly the same as one on left. Ok, the LEDs are slightly less bright.

Related Instructables

Joule Thief - use LEDs with only one AA battery! by RazorConcepts

Ferrite, the joule thief (Photos) by botronics

Electronic Night Light by TinkerJim



Ultraviolet Light Pen by junits15

Mini 'Joule Thief' (Photos) by Mudbud



Altoids Joule Thief Flashlight (Photos) by cynical_chemical

Comments

33 comments **Add Comment**

tosacj says: Sep 4, 2011. 10:47 AM **REPLY**
Great idea. Let me know when the kit becomes available.



ledartist says: Sep 4, 2011. 12:38 PM **REPLY**
I will post the information on "Kits" section of the forum and on my blog (theLEDart.com). The kit & PCB are scheduled to be ready in mid September.
Thanks, Aki

haxcess says: Sep 5, 2011. 8:16 AM **REPLY**
This is a very neat application of the joule thief. I am wondering if it would be possible to replace the light-sensor circuit with a small battery charging circuit (solar). I suppose that would ruin the beautiful form factor you have here.

apalacios2 says: Sep 5, 2011. 7:07 AM **REPLY**
Excellent circuit. May I remove the CdS circuit and use a button switch instead (thru the resistor connected to the transistor)?
I find great that it uses a coil instead of a toroid transformer. Kudos!



ledartist says: Sep 5, 2011. 7:28 AM **REPLY**

Yes, you can. In fact I made sure that you can fit a 6mm tactile switch in place of trimmer pot. You can omit the CdS, and solder a switch in place of trimmer pot.

You can also remove Q1 and put a switch there as well, but my PCB won't accommodate that.

Yeah I found having to wind my own inductor a hassle, so I designed this circuit to use off-the-shelf inductors.

Aki

bhvm says: Sep 4, 2011. 9:17 PM **REPLY**

Excellent build!
How many mA does this circuit give? Can we use a single 150mA power LED in place of 2x 5mm LEDs?



ledartist says: Sep 5, 2011. 7:20 AM **REPLY**

The current through the LEDs is about 20mA or less peak (it's pulsed current in about 50kHz)
So you won't get any more light by using a high power LED. By using only one LED, you do get a bit more brightness per LED though. However just a regular LED will give you the same brightness as a high power LED because you are not driving the LED with high current anyway...

It's not that you can't drive high current LED, but this circuit is designed to run with as little power as possible.

Aki

abbtech says: Sep 4, 2011. 7:10 PM **REPLY**

Great looking project.



ledartist says: Sep 4, 2011. 7:18 PM **REPLY**

Thanks!

vruiz3 says: Sep 4, 2011. 1:56 PM **REPLY**

afraid of the night??? :D



timotet says: Sep 4, 2011. 1:21 PM **REPLY**

great job!

gnafpliotis says: Sep 3, 2011. 3:06 PM **REPLY**

Can't we hack laptop's batteries that way to perform more? Is it only letting through a small amount of amps?



ledartist says: Sep 4, 2011. 1:17 PM **REPLY**

Laptops and many other "high-tech" gadget has many of inductor based boost/buck (to reduce voltage) voltage converter circuit in them. Especially LED back light screens use voltage converter to efficiently drive LEDs.
So in a way the battery life is already enhanced. (Some gadgets are better than others, of course...)

Aki

jolshefsky says: Sep 4, 2011. 6:19 AM **REPLY**

Yes, but only if you wanted to use your batteries once. Once a lithium rechargeable (like in laptops) is discharged past a certain point, it can no longer be recharged. So there is always some energy left in a laptop battery even when it says it's dead — albeit energy you can't use without ruining the battery.

stoobers says: Sep 4, 2011. 7:29 PM **REPLY**

I've heard this theory. Have you done any experiments that might validate this theory?

jamwaffles says: Sep 4, 2011. 6:14 AM **REPLY**

This might not be 100% accurate but yes, that's why we can't use the same technique for laptops. Joule thieves ramp the voltage up, but the current goes down due to V = IR, assuming the load is constant which it is if it's the same laptop ;-)

jamwaffles says: Sep 4, 2011. 6:15 AM **REPLY**

A very professional looking product. This is a great idea; the amount of power saved using old batteries instead of a herd of plug-in night lights, as well as the amount of batteries re-used is incredible.

Just out of interest, how long do these night lights last on one "averagely discharged" battery?



ledartist says: Sep 4, 2011. 1:10 PM **REPLY**

The battery lasts very long, most likely much longer than you might think.
It's hard to define "averagely discharged", but I had one cell that was already at 0.7V (to low to be used with anything), and the although the LEDs were dim, they lighted for over 48 hours.
With my "dead" batteries coming out of a wireless mouse still have over 1V, I have plenty of light.

Aki

YakAttack says: Sep 4, 2011. 8:24 AM **REPLY**

I concur!
@ledartist: Any tests on battery life so far?

nymgeek says: Sep 4, 2011. 7:42 AM **REPLY**

Are those PCBs made by Laen at dorkbot pdx?



ledartist says: Sep 4, 2011. 1:04 PM **REPLY**

Yup. They are very good!

acmefixer says: Sep 4, 2011. 10:06 AM **REPLY**

I should have said in my previous comment that this does not mean there is anything wrong with your circuit. I think I would change Q2 and Q3 to an easier to obtain transistor such as a 2N4401 or PN2222A. Q1 could be a 2N3906 or just about any PNP transistor. If these changes are made, the resistors, especially R2, might need to be reduced. Thanks.



ledartist says: Sep 4, 2011. 1:03 PM **REPLY**

Yes, you can use just about any general purpose transistors. R2 should be fine with most transistors, but 47k ohm might work better with some of them.

Aki

acmefixer says: Sep 4, 2011. 10:00 AM **REPLY**

Unfortunately the link you gave to Joule Thief in Wikipedia is for a poorly written and totally inadequate definition. The authors (apparently several over time) do not have a firm understanding of how a JT works, and furthermore, they have made a mess of it. I have added comments in the discussion and some errors have been deleted, but it is still unworthy of use for a reference.

Also, by definition, the original blocking oscillator circuit later given the Joule Thief name used only a single transistor. Your circuit is not a one transistor blocking oscillator and bears little resemblance to the original JT, so I don't believe it should use the same name.



ledartist says: Sep 4, 2011. 12:59 PM **REPLY**

I know the original circuit only uses one transistor, but the two conductor inductor is harder/expensive to purchase, and winding own inductors is a bit of work. I think using one extra transistor is a good trade off for not having to wind an inductor by hand. It also makes economical sense. (transistors are very cheap, so are single coil inductors.)

I did mention that my version is a _variation_ of original, which I find very often on the net. I also think that showing different ways to achieve the same result can be inspirational.

I also contacted the person who named the circuit "Joule Thief" (Big Clive) and he did not have a problem with me using the name.

Aki

StoryAddict says: Sep 4, 2011. 12:54 PM **REPLY**

"Joule Thief" - I love a clever pun!



MikeDel says: Sep 4, 2011. 10:21 AM **REPLY**

Looks good. I'm interested!

Admiral Aaron Ravensdale says: Sep 4, 2011. 7:30 AM **REPLY**

I like your "green" thinking.
I also use a joule thief in my expedition light.

I am very glad that you will provide the parts as a kit because many kits are able to solder a circuit but etching a little bit too dangerous for them.

Thanks for your endeavour to make this instructables buyable for many people…



kevinhannan says: Sep 4, 2011. 6:35 AM **REPLY**

fantasic project and incredibly well explained.

UOS says: Sep 3, 2011. 2:59 PM **REPLY**

Great instructable! Waiting the kit version to buy one but also I'm gonna make mine from scratch :D



tphillips2 says: Sep 3, 2011. 8:07 AM **REPLY**

You are so inventive! Cool idea and great looking light!



ledartist says: Sep 3, 2011. 8:18 AM **REPLY**

Thanks!



gweeds says: Sep 3, 2011. 4:41 AM **REPLY**

What a great idea! must build one and see how long it gets out of a "used'ish" battery


−
+
AKIMITSU SADOI 2011

advertisement

Secrets from the Sound Suite with St. Vincent

Sponsored by: **W Hotels**



(https://cdn.instructables.com/FNO/MBIK/GUROLUHZ/FNOMBIKGUROLUHZ.MEDIUM.jpg)

advertisement



Tektronix

LOW LEVELS, HIGH ACCURACY

Ultra-low measurements using Keithley sensitive instruments

LEARN MORE →

KEITHLEY
A Tektronix Company

this is my version of the famous joule thief. there's alot of these things out there so i did alot of research and made it as simple as i can without soldering or complicated math. i harvested these parts from an older dell computer that was given to me to scrap. there is only a few parts needed to build this project:

1: toroid bead (ferrite core)
2: 1k ohm resister (brown black red)
3: npn transistor (i used the 2n3904)
4: thin wire

About This Instructable

7,340 views

23 favorites

License:

(cc) BY-NC-SA

Step 1: Wind the Coil



(https://cdn.instructables.com/F5F/R9QV/GURSSCJF/F5FR9QVGURSSCJF.MEDIUM.jpg)



(https://cdn.instructables.com/FEM/F7J4/GURO

(https://cdn.instructables.com/F57/RU2L/GURPG

i wound a couple sizes of these things using the same wire. the type of wire i used came from an ethernet cat5 cable. i like it because its a solid core wire that stays in place where i put it. i have 11 turns of wire in the orange one and 13 in the green one. i looked all over the internet to find the reason for the number of turns but couldnt find an exact answer, and 11 winds is all the smaller (orange one) could take, and the green one i just put the 13 turns in it from the same length of wire. the orange coil is half the size (about the size of a dime) of the green one (little bit smaller than a 50cent coin).

Step 2: Connect the Resistor

(/member/florlayamp/)

florlayamp (/member/florlayamp/)

(http://https://www.facebook.com

Follow 98

Bio: I love building things, and I'm a twin, we both are electrical engineers and inventors. Feel free to ask anything else

More by florlayamp:

(/id/How-Twins-Change-Oil-In-A-Jeep/)



(/id/Take-A-Ghost-Picture-With-Almost-Any-Camera/)



(/id/Voltage-doubler-for-wind-generators/)

(https://cdn.instructables.com/F0R/T5XD/GUROLUQU/F0RT5XDGUROLUQU.MEDIUM.jpg)



(https://cdn.instructables.com/F7S/QBXX/GUROLUQX/F7SQBXXGUROLUQX.MEDIUM.jpg)

once the coil is wound, cut off the excess wire but make sure to leave enough to work with. strip the ends of all four wires, then take 1 wire of **opposite color from each side** and twist them together. then since i didnt solder any wire, i cut up several small wires to piece the rest of it together. unless you want to solder it you can skip this part. but i took a piece of wire and attached it to one of the single wires on the coil (it doesnt matter which one) and attach the other end of the piece of wire to the 1k ohm resister, then take another piece of wire and attach it to the other single wire which will go to the **collector** leg of the transistor. the final piece of wire for this step attaches to the twisted pair of wires which will become the positive input for the circuit.

Step 3: Connect the Transistor


(https://cdn.instructables.com/FLB/MLP3/GURSSCKZ/FLBMLP3GURSSCKZ.MEDIUM.jpg)


(https://cdn.instructables.com/F38/VOS4/GURZ1OR4/F38VOS4GURZ1OR4.MEDIUM.jpg)

next take a piece of wire and attach it to the other side of the resistor, and then take the other end of the piece of wire and attach it to the **base leg** of the transistor. next, as i mentioned in the previous step, take the open piece of wire from the coil and attach it to the **collector leg** of the transistor, also i attached another piece of wire to this leg for the positive output side . last of all connect two wires to the **emitter leg** which will be the negative side of the circuit. (one wire to negative on battery, then one to the negative output side of an LED light or whatever else you put on it).

Step 4: Hook It Up and Enjoy!



(https://cdn.instructables.com/F6F/597W/GURSSCM0/F6F597WGURSSCM0.MEDIUM.jpg)

time to hook it up! the positive wire from the double twisted wire on the coil goes to the positive power source, and one of the negative wires on the transistor go to the negative side on the power source. the positive wire on the transistor and the other negative wire on the transistor go to the output power. once its all wired up its ready for use. as you can see in the picture, i hooked up a new AA battery and got about 5 volts! not bad for a 1.5v to 5v boost. and the orange coil circuit i also made produces about 2.5v from a 1.5v source, so this orange one only produces another volt while the green one produces alot more. i dont know why this is really. my only guess is the size of the toroid coil and the 2 winding difference. other than that its all the same parts. below is the results of some playing around with it.

green coil circuit:
1: 1.5v AA produces 5 volts
2: 2 AA 3v produces 20 volts
3: 3v input can power a 12v .25a computer fan.
4: 1.5v lights 3 green LED lights.

orange coil circuit
1: 1.5v AA produces 2.5 volts
2: 2 AA 3v produces 8 volts
3: 3v input also powers same 12v computer fan for 5 seconds...

very inconsistent results between the two but thats what is going on. thanks for looking and hope this helps with your project.

advertisement


Rugged Intel®-Based Single Board Computers
View Boards
X-ES

AdChoices
OXI CLEA

Comments

We have a be nice comment policy.
Please be positive and constructive.

I Made it! Add Images Post Comment

ToXiCATOM (/member/ToXiCATOM/) 2014-02-01 Reply

can i use 2n2222 transistor?

kyooby (/member/kyooby/) ▸ ToXiCATOM (/member/ToXiCATOM/) Reply 2014-03-27

2N3904 = GP NPN Bi-Polar transistor commonly found in toys and small radios. Otherwise you can get them at radio shack, fry's electronics or order them online.

Other compatible ones are:

NPN

2N2222

2N2222A

2N1613

BC107

2N1711

2N2369

2N2484

2N3704

2N3705

2N3706

2N3903

2N3904

Also, if you use a 2N4401 or BC337 transistor, your LED will be brighter because they can handle more amps.

You can get the toroid and transistor from a dead CFL; the transistor is usually labeled 13002

---

florlayamp (/member/florlayamp/) ▸ ToXiCATOM (/member/ToXiCATOM/) Reply

2014-02-01

I tried that transistor also and I couldnt get it to output anything,
I think the internal circuits inside it are backwards for a joule thief.

⬇ More Comments



Newsletter

Let your inbox help you discover our best projects, classes, and contests. Instructables will help you learn how to make anything!

enter email | I'm in!

About Us

Who We Are (/about/)
Advertise (/advertise/)
Contact (/about/contact.jsp)
Jobs (/community/Positions-available-at-Instructables/)
Help (/id/how-to-write-a-great-instructable/)

Find Us

Facebook (http://www.facebook.com/instructables)
Youtube (http://www.youtube.com/user/instructablestv)
Twitter (http://www.twitter.com/instructables)
Pinterest (http://www.pinterest.com/instructables)
Google+ (https://plus.google.com/+instructables)

Resources

For Teachers (/teachers/)
Residency Program (/pier9residency)
Gift Premium Account (/account/give?sourcea=footer)
Forums (/community/?categoryGroup=all&category=all)
Answers (/tag/type-question/?sort=RECENT)
Sitemap (/sitemap/)

Terms of Service (http://usa.autodesk.com/adsk/servlet/item?siteID=123112&id=21959721) |
Privacy Statement (http://usa.autodesk.com/adsk/servlet/item?siteID=123112&id=21292079) |
Legal Notices & Trademarks (http://usa.autodesk.com/legal-notices-trademarks/) | Mobile Site (https://www.instructables.com)
(http://usa.autodesk.com/adsk/servlet/pc/index?id=20781545&siteID=123112)

© 2017 Autodesk, Inc.

WONDER HOW TO
MAD SCIENCE

BEST BUY EXPERT SERVICE. UNBEATABLE PRICE.

Make a "Joule Thief" and Create Zombie Batteries for More Power After Death

BY **WILLIAM FINUCANE** 08/23/2013 5:22 PM **MAD POWER!**

Just about every household gadget we own runs on 1.5 volt batteries of one size or another. Wouldn't it be great if you could reuse all of those dead AA, AAA, and D batteries after they've passed on? It turns out you can make a simple circuit called a "Joule Thief" to reanimate the undead flesh of your deceased batteries and create a zombie battery.

1 | Find Who Owns This Number Enter Any Phone Number Now. Get Full Owner Info. Try Free! spokeo.com
2 | Start Download Step 1- Install DriverUpdate™. Step 2- Scan. Step 3- Identify Missing Drivers! slimware.com

Materials

- LED
- 1k resistor
- 2n904 transistor
- Thin magnet wire
- Solder
- Soldering iron
- Battery clip
- Ferrite core
- Dead battery

sistor for easy soldering.





STUDY TO BECOME AN
A/V TECHNICIAN | SOUND EDITOR
AUDIO ENGINEER | MUSIC PRODUCER
SAE INSTITUTE
LEARN MORE >

Bend the middle pin back and up behind the black plastic case of the transistor.



Step 2

Place the LED

The LED is a polarized component. This means it will only work when it is facing the right way in our circuit. The positive lead of the LED is usually longer. Below, the positive lead is on the left, the shorter negative lead is on the right.

Are they *Cheating* on you? Find Out Now

Step 1) Enter Phone # Step 2) View Uncensored Results Show Me Proof >>

Place the LED on the transistor as shown below, with the positive side facing to the right.



Now, solder the LED to the transistor.



Step 3

Place the Resistor

Place one end of the resistor on the middle pin of the transistor. Make sure the components stay in contact while you solder them.



Find Who Owns This Number
Enter Any Phone Number Now. Get Full Owner Info. Try Free! spokeo.com

Step 4

Wrap the Coil

This is where the dark magic happens. Wrap two enamel coated wires around the edge of a ferrite core. More wire will mean a stronger joule thief and a brighter LED. When you have wrapped the core, you should have two pairs of end wires. Connect one pair together as shown below on the right. Splay the other pair apart as shown below on the left.



Step 5

Attach Coil

Remember to burn away the enamel on the end of the thin wire with a lighter. With the wires burned and exposed, solder one free coil wire to the 1k resistor. Solder the other free coil wire to the positive side of the LED.



Below, we have to solder a coil wire to the intersection of the transistor and the positive leg of the LED.



Below, notice that the end of the green enameled wire is exposed because the enamel was burned off.



Step 6

Solder Clip

Now that the main joule thief is done, we can attach a battery clip for easy use. The joule thief will work without the battery clip, but only if you hold the wires in place with your fingers.



e that both wires in the pair are soldered to the red wire.



For those who need the schematics, this is what we just built:



When the current flows through the coil and around the magnet, it produce an electromagnetic field (EMF). When the coil is not powered, the field collapses and produces an EMF kick in the coil that is of a higher voltage than the source was. The last of the electricity gets stored up in the field and released in large bursts to flicker the LED. The magnetic field oscillates so quickly that the blinking LED appears solid to the naked eye.

Now, just plug your dead battery into the circuit and enjoy the eerie unblinking glow of the undead watching you as you sleep. This project works great for night lights and even garden path lights when paired with a light sensor.

What could you light up with all your zombie batteries? Post your ideas and discussion in the forum.

Diagram image from Evil Mad Scientist Laboratories


LED
I
+
2n3904 Transistor
1k Resistor
–
Power
+
Toroid bead
On/Off

DOWNLOAD MEETEQ

Search … Search

Microstrip patch antennas by kai fong lee



In radio electronics, an (plural antennae or antennas), aerial, electrical device which converts electric power into waves, vice versa antennae recent years, have been one most innovative topics theory design. Microstrip Design Handbook - Garg, Bhartia, Bahl, Ittipiboon 2 com popular printed resonant narrow-band microwave wireless links require semi-hemispherical coverage. Pure Appl yadava2 electronics and. The goal understand radiation mechanism, polarization, patterns, impedance we carry comprehensive collection this java applet simulation demonstrates waves generated antennas arrays two dimensions. L it increases parasitic inductance associated. Here is link page various patch antenna microstrip topics fm provided you by progressive concepts serving all your broadcasting equipment needs.

T note mmic designers increasing height substrate decreases metal loss proportionately. Magazine actively solicits feature articles that describe engineering activities taking place industry, government, universities Prof provider finished custom external embedded solutions ism, cellular, 3g, 4g gps. Technol pasternack s patch calculator (in millimeters) antenna. , 6(2) (2011), pp 4. 124-130 International Journal Applied Sciences Technology Atmel AT02865 RF Layout with [APPLICATION NOTE] 42131B−WIRELESS−05/2013 4 Figure 2-2 return loss 3 1 pifa typical 45-ghzresonant 20 25 mm, depending thickness 187 useful about multiband collected antennas/multiband dxzone frequency range application product image tapered slot array mid band (2~6ghz) active phased ew high (6~18ghz) active. Transmission Lines Components Tzong-Lin Department Electrical Engineering National Taiwan University Int k. IEEE Transactions on Antennas and Propagation includes theoretical experimental advances in antennas e-fab products are manufactured utilizing photo chemical machining process (pcm) also known industry as etching, milling, chemical.

Also, a lesser degree component design a. Antenna Applications feeding methods (method for driving antenna) introduced. References 1 java@falstad. J yadav r. Pin-pitch Dimensions ii.

Categories

- Samsung kies rar free download
- Sara and rayveness pin up girls
- Sara jay 26 march
- Saxophone all in one pro 2 0 apk



Microstrip patch antennas by kai fong lee

Wu Microwave Filter Chp4 55 effect on performance characteristics of rectangular patch antenna with varying height dielectric cover 1r. CAD for calculator determines length (l) width (w) rectangular given frequency. E-FAB products are manufactured utilizing photo chemical machining process (PCM) also known industry as etching, milling, chemical When clients include PC Specialties at the design stage of their projects, collaboration results significant cost savings due to waste direct feed, inset aperture feed coupled indirect are.

Theory Fang 3 description. Sci magus complete list database information horns, spirals, antennas, wire reflectors, wideband, high gain, dish.

« Previous Post Next Post »

Copyright © 2017 Download Meeteq

N5ESE's Classic RF Probe

(click on any picture to see larger version)

NOTE: 'N5FC' is my former call.
This project was constructed while that call was valid, and you may observe references to it.

The RF Probe is one of the handiest accessories you can have around the shack. Using only 3 electronic components, it may rank as one of the simplest and cheapest homebrew projects. The one featured here cost about $10 in parts and supplies, not counting the wire, which I scrounged. When used with a high-impedance DC Voltmeter, it can be used to measure RF voltage (and power), trace RF signals in a new design, and troubleshoot malfunctioning RF circuits. It has its limits, of course, and we'll discuss those here. But once you understand how it's used, and how easy it is to build, you'll wonder why you never built one before.

What's an RF probe, and how does it work?

You might think of an RF probe as a special test lead that converts your regular ol' DC voltmeter to a RF reading voltmeter. Why not just read it using your trusty voltmeter, set on AC? Well, because most voltmeters wont read AC signals having a frequency above 10 or 100 KHz, and RF is way above that. [You can buy special RF-reading voltmeters, but they're very expensive... a homebrew RF probe is dirt-cheap]. Let's examine how an RF Probe works.



Classic Peak Rectifier



Simplified RF Probe

Above left, we see the schematic of a classic half-wave peak rectifier, commonly seen in power supplies. It's pupose is to take an AC signal at the input (usually from a transformer or the AC line), rectify it, and charge a capacitor. If you don't take a lot of power from the circuit (i.e., if your load doesn't draw a lot of current), the capacitor charges up to the peak voltage of the AC signal, and stays prettty much constant. Notice the simplicity of the circuit: not counting the load, we see it is an AC Source, a diode, and a capacitor in series.

Above right, we see a simplified schematic of the RF Probe. At first glance, it looks quite different from the circuit at the left. But notice: just like the first, it consists of an AC Source, a diode, and a capacitor in series. It's pupose is to take an AC signal at the input (usually from a circuit under test), rectify it, and charge a capacitor.

And just like the first circuit, If you don't take a lot of power from the circuit (i.e., if your load doesn't draw a lot of current), the capacitor charges up to the peak voltage of the AC signal, and stays prettty much constant.

What's the difference between these two circuits, then? One small little thing, really. In the first circuit (the half-wave peak rectifier), any *positive* DC component gets added to the voltage at the output. In the second circuit (the RF Probe), the circuit is insensitive to *positive* DC components. This is good for an RF probe, because we're going to be testing circuits with DC biases applied, and we don't want those biases to affect our readings (we're interested in the AC only, i.e., the RF)

In both these circuits, if we place a DC (not AC) voltmeter at the place where it says "+" and "-" we'll read a DC voltage that is approximately equal to the *peak* of the applied AC voltage. If we knew our applied AC was a sinusoidal signal (or sine wave), then we could divide our reading by 1.414 to obtain the RMS value, which is the way we usually measure AC voltages. Even if it's not a sinusoid, at least we know what the peak voltage is, and that's something we didn't know before we started.

We'll do one more little trick to make the RF Probe more useful, and it will only cost us the addition of a 2-cent resistor. So that we don't have to manually divide our readings by 1.414, we'll use a resistor to create a voltage divider that will do it for us. Here's a classic voltage divider, added to our RF Probe circuit:



As we know from elemental electronic theory, the voltage across the second resistor (where it says "+" and "-") is equal to the applied voltage multiplied times the ratio of the second resistance divided by the total resistance in series. In our case, for a sinusoidal input, we know the applied DC voltage is equal to the PEAK of the AC voltage. We would like the resistor divider to divide by 1.414, which means that the total resistance in series (including the second resistor) needs to be equal to 1.414 times the second resistance. In our example circuit, shown above, the second resistor is 11 Megohms, and the total series resistance is 11 Megohms PLUS 4.7 megohms, or 15.7 Megohms. Is this ratio 1.414? Pretty close, about 1.427, closer than the typical resistor tolerances.

But wait! I said we would add one resistor, not two! What's up with that? Well, the 11 Megohms is the typical input resistance of a high-impedance voltmeter, like an electronic VTVM or a digital voltmeter. As long as it's 10-11 Megohms, it'll give results close enough for government work (HI). Obviously, it's important to know what your voltmeter's input resistance is, and you can find this out in your voltmeter's specifications, or measure it (I wont get into that). And really, accuracy is often not that important, especially when you're signal-tracing.

Enough! Let's get real... let's build something!

Here's a complete schematic of the classic RF Probe. Simple, eh?



CLASSIC RF PROBE

Reads RMS Equivalent Voltage in test circuit, if Voltmeter is 10 -11 Meg Input Impedance;
Reads 4X RMS Equiv Voltage if VM is 1Meg Input Impedance (Set VM to measure DCV)

We've added a few things from our theoretical discussion that we'll make short note of. Obviously, for "probing" we need a "probe". (Hey! No wonder I get paid the big bucks...). We add a SHORT lead with an alligator clip. The alligator clip goes to our circuit "ground" and the probe goes to our test circuit, where we're probing. Brilliant! We don't want either of these to be long leads, because we're talking RF here, and long leads = antennas, and we don't want to be picking up stray signals or broadcasting them. 10-12 inches for our ground lead is sufficient for circuits to up to 30 MHz.

As shown in the schematic, we'll need to shield the RF Probe circuit, or else our hand and body will pick up stray RF and couple it into the circuit, causing erroneous readings. We'll also shield our leads all the way back to the Voltmeter, as shown, for the same reason. At the far end of the shielded wire, we'll mount banana plugs (or whatever will fit our DC Voltmeter).

In case you're tempted, don't make poor substitutions for the diode. We chose the 1N34A because it had the following key characteristics: Reverse Breakdown Voltage greater than 40 Volts, forward voltage (barrier potential) of less than 0.3 Volts, and good RF qualities. Any diode with these qualities (example, the 1N458A) would work as well, but the 1N34A is readily available (at Radio Shack and others). Silicon and Shottky (hot-carrier) diodes, while good RF devices, have higher barrier voltages, and will not work as well at low RF voltages. The 1N34A is a germanium device, and with a barrier voltage of around 0.25 V, provides about the best performance you can get with this simple circuit.

For best accuracy, size the resistor to match your DC Voltmeter's input impedance:

R = 4.7 Meg for Zin = 11-Meg;
R = 4.3 Meg for Zin = 10-Meg;
R = 430 K for Zin = 1-Meg;

Here's one cheap-and-easy approach to building the RF Probe:



Click on the image above to see a larger

Take a small piece of scrap double-sided printed-circuit board, about 1-1/2 x 1/2 inches, Groove it on one side only, similiar to the image above, to create pads for soldering, but leave the back side as a "ground plane". Mount your diode, capacitor, and resistor as shown, soldering to the pads you made. One side of the diode (the non-banded isde) gets connected to the ground plane (drill a hole through to the other side and solder it). Try to fit all the components neatly inside the edges of the pc board. Solder the braid of the shielded wire (3-4 ft long) to the ground plane, and the center conductor to the pad with the resistor. Also, solder a 10-12 inch hook-up wire to the ground plane. Check that there are no shorts between the center conductor and the ground-plane. Solder the probe tip to the pad with the capacitor (I used a discarded probe tip from a broken test probe).

Here's where we get creative: packaging! One way or another, whatever method we use, it's important to shield the probe circuit, yet without shorting any part of the circuit to our shield (except the ground plane). I was on a kick of using copper pipe, which is very cheap, so I built my shield out of 1/2-inch copper pipe and end caps, commonly available at your local hardware store. I drilled a hole in the end of each end-cap, to pass the shielded cable and the probe tip. I used a shouldered washer to insulate the probe tip from the end cap, but a small rubber grommet would have worked as well. Stuff the assembly inside the copper pipe, and you end up with a completed probe that looks like the following:

Click on the image above to see a larger version

So, how do we use this thing?

Before we use it, a few precautions are in order. Don't use the probe in any circuit where the highest DC supply voltage is greater than the diode's reverse-breakdown voltage. For the 1N34A, this is 50 Volts. Same goes for the capacitor, which should be rated at least 50 Volts. This probably means that the probe cannot be used in most tube circuits. Also, don't try to measure RF power in circuits where the peak voltage will exceed 50 Volts. What will happen if you exceed these voltages by a little? Well, probably nothing; possibly, the diode or capacitor will fail open or short.

The first thing you'll always do in using the RF Probe is to connect the banana-plug end to the +/- jacks of your DC Voltmeter; set the Voltmeter to DC-Volts (not AC).

To use the RF Probe for signal tracing in a malfunctioning RF circuit or a homebrew circuit, connect the aligator clip to a convenient "ground" or "common" point in your circuit. Often this is the chassis. Most of the time, you'll be probing at the base/gate, emitter/source, or collector/drain of a transistor, one either side of a coupling capacitor or transformer, or at the input or output of an IC. Because the circuit's RF must overcome the diode's barrier potential (of 0.25V, for our 1N34A), voltages much less than that won't read at all, and voltages less than about a volt won't read very accurately. Typically, RF and post-mixer-amps in receivers don't have enough RF voltage, unless you inject a very strong signal at the input.

I recently used my RF probe to troubleshoot my dead TenTec Scout, which had suddenly quit transmitting in mid-QSO. I connected the rig to a dummy load, then keyed it while probing. Using the probe, I was able to follow a steadily increasing RF signal through the transmit chain, from the oscillator through the transmit mixer, to the pre-driver, and the driver. The actual voltage measurements weren't important, just that they were increasing from stage to stage where expected. Then, (whoops!) the driver's base circuit had 6 Volts, but the collector circuit only had only 0.1 Volts! The driver transistors had gone south!

You can also use the RF probe to measure RF power with reasonable accuracy, up to about 50 watts in a 50-ohm circuit. By 50-ohm circuit, I mean a 50-ohm antenna system at 1:1 SWR (higher SWRs are not 50 ohms), or a 50-ohm dummy load. Assuming the resistor in your RF probe is sized to match your DC Voltmeter's input impedance (as explained above), you will get quite reasonably accurate measurements using the following formula:

$$\mathrm{PWR} = \frac{(V_{(read)} + 0.25)^2}{R_{(load)}}$$

For example, I want to measure the power out of my TenTec 1340 40-Meter QRP transceiver. I place it on a 50-ohm dummy load, and key down. I generally use a BNC-Tee adapter to gain access to the output line, but I could as easily pop the cover off. Using the RF probe (alligator clip to chassis ground), I measure12.2 Volts (DC) (and the same RF RMS Volts). Plugging this into the formula above I have PWR= (12.2 + 0.25) * (12.2 + 0.25) / 50 = 3.1 Watts. The rated power for this rig is 3 Watts, so I've verified everything is hunky-dorey.

We've added the potential barrier to the measured voltage above, but that little trick doesn't work so well when you get down around a volt, and for voltages less than about a volt, the measurement accuracy suffers greatly. Also, the diode's response is severely non-linear below the barrier potential, and will generally read much less than expected in circuits where the RF voltage is less than 1/4 volt. So if you see tiny readings in circuits where it's normal to have voltages less than 1/4 volt RF, don't get too spun-up about the low readings... it may mean everything is normal. My rule of thumb for guessing at this is as follows: For collector/drain circuits in oscillators or transmit-chain amplifiers in key-down, expect RF Voltages about 20-50% of the applied DC (supply) voltage. This depends on the circuitry, of course, but it's a reasonable gesstimate. Base/gate and emitter/source circuits will generally be much less, maybe 5-10%. Circuit impedance will affect this too.

How good is this thing?

Well, we're not talking high performance test equipment here, but we *are* talking very useful. If you account for the barrier voltage, the readings can be quite accurate when measuring most low-impedance circuits (20-200 ohms), provided that the voltage is above 1 or 2 volts. How accurate? +/-10% from 200 KHz to 150 MHz would be a reasonable expectation. Also, the voltage divider is only accurate for sinusoidal signals. If you want "peak" measurements, simply multiply your reading by 1.414. The "peak" measurement should be good regardless of whether the waveform is sinusoidal. Regarding ultimate accuracy, your results may vary, and you may want to compare it to a laboratory instrument at the frequency of interest if you're really interested in accuracy. If you shield it well, and keep the ground clip lead reasonably short, it should be good in low-impedance circuits up into the VHF region, and down into the upper-audio region. In higher-impedance circuits, the junction capacitance of the diode may cause a low-pass effect at higher frequencies, and you're most likely to see this as a loss of measurement accuracy (i.e., low readings) at frequencies above 30 MHz. This doesn't mean it's not useful; it just means it reads low. Also, the capacitance of the probe may affect some sensitive RF circuits. For example, if you're probing a LC-tuned oscillator circuit, it may stop oscillating or change frequency or become unstable. Actually, most any probe will do this. Also, as we said before, the barrier voltage becomes a bigger part of the measurement error as the circuit voltage drops below a volt or so, and becomes dominant as you approach the barrier voltage. Just keep this in mind as one of it's limits.

Enjoy, good luck, and 73!
monty N5ESE

Return to N5ESE home page

Overseer: Monty Northrup ... ... leave e-mail ...

Visit our regular (non-ham, but very popular) homepage

N5ESE's Ballpoint RF Probe



(click on any picture to see larger version)

NOTE: 'N5FC' is my former call.
This project was constructed while that call was valid, and you may observe references to it.

This is one of those afternoon projects that can really be both rewarding to build and useful to have. Electrically, it's identical to the Classic RF Probe described elsewhere (where you can also find the theory discussion for this one). Like the Classic RF Probe, this one is used in conjunction with a high-impedance-input Voltmeter or Digital Voltmeter (DVM). See the schematic below. Cost? About $5, if you can scrounge the ballpoint pen, heat shrink, shielded cable, and copper tape.



CLASSIC RF PROBE

Reads RMS Equivalent Voltage in test circuit, if Voltmeter is 10-11 Meg Input Impedance;
Reads 4X RMS Equiv Voltage if VM is 1Meg Input Impedance (Set VM to measure DCV)

What makes this probe unique is that it's built inside the shell of a regular ol' ballpoint pen. Besides being conveniently compact, the unit sports a needle-probe suitable for use in probing surface-mount circuits, and good overall shielding. The pen cap protects the needle probe when not in use. When measuring sinusoidal signals, it should provide RMS-corrected readings, using a 10 or 11-Meg input impedance VTVM or DVM. With a 1-Meg DVM, it reads 25% of the sinusoidal RMS voltage. Reasonable accuracy (+/- 10%) can be expected over the HF/VHF range (2-150 MHz), although this hasn't been verified. When used to measure non-sinusoidal signals, the accuracy will be unknown, but it still affords good relative measurements, and most of the time, that's all that's required. It makes an excellent, compact, and portable accessory for troubleshooting or homebrewing QRP equipment with peak voltages less than 50 Volts (i.e., most solid-state equipment)

Construction

The figure below shows the parts required to build the Ballpoint RF Probe. Click on the image to open an larger, annotated image with parts labled, and construction notes. Pick a ballpoint pen with a non-metalized plastic body, and plenty of room inside. The Papermate Flexgrip model I used had an inside diameter a little over 1/4-inch. We'll use an itty-bitty scrap of double-sided printed-circuit-board to mount the electronic components. Trim the PC board to about 2-12" long and 3/16" wide; don't make it too wide, or it won't fit inside the ballpoint pen. Notch or file a little out of the middle of the pc board, so the 1N34A diode will fit easily inside the pen body. then, on one side only, groove in two places, so as to create 3 lands on the "top" side of the board. In addition to the parts shown, you'll need a 2-1/2" piece of heat-shrinkable tubing to cover the electronic assembly (although electrical tape would do instead), and about a foot of 1/4"-wide adhesive-backed copper tape, commonly available in rolls of 200-300 inches at large hobby stores (like Michaels, and Hobby Lobby). Although a chip capacitor is shown in the photo, a very small disc capacitor will do as well.



Click on the image above to see a larger, annotated image

In the next image (below), we get a close-up of the electronics assembly. You can see the input capacitor straddling the front-to middle lands, and the 4.7 Meg resistor straddling the middle-to-rear lands. The diode, which snuggles into the notch, connects from the middle land to the ground plane on the rear side of the pc board. The diode's banded end goes to the middle land. Break the sewing needle in half, using two needle nose pliers. **WARNING! Use eye and face protection!!** *ALSO NOTE: Don't try to cut a sewing needle with wire-cutters... you'll ruin the cutters.* Avoid straight pins, which dont have the hardness to perform well as probes. Then, solder the sewing needle to the front land, centering it carefully. You might benefit from burnishing the solder-half of the sewing needle with some fine grit sandpaper, to make it take solder a little better. Center it up nicely, as that will make for a professional-looking probe. Solder the shielded cable to the top/bottom of the pc board, center conductor to the rear land on top, and shield to the ground plane on the bottom. Be careful to aviod straggling shield-wires which could short the electronics. Also,solder a 10-12" pigtail of good, flexible insulated wire onto the ground plane, pigtailed rearward. This will be used as the ground wire in our test circuit. Before you shrink the tubing over the electronic assembly, check for shorts between lands and from lands to ground plane, make sure you have the diode polarity correct, and check that the needle is making solid electrical contact, and is mechanically secure.



Click on the image above to see a larger, annotated image

See the next image, below. After the electronic assembly has been heat-shrunk overall, wrap the copper tape all around the electronic assembly. This will be our shield. Near the rear of the electronic assembly, solder the electonic assembly's ground to the copper tape, near or on the cable shield. Alternative shielding methods can be tried, for example, you might pull the shield out of a piece of RG-59, and sleeve it over the electronic assembly, soldering it to the ground plane. Whatever you do, be certain that the shield cannot unravel and short against the probe itself or any of the electronics.

Although not shown in the picture, we drill a small hole about 2/3 back on the pen casing, threading the ground pigtail through the hole. This really tests your hand-to-eye coordination. If the pen has a threaded-in rear-cap, drill a hole in it just big enough to accommodate your main shielded cable. Thread the whole cable into the pen casing, and out the other side, and if you had a threaded rear-cap, like I did, thread it on. Pull the electronic assembly gently back into the casing, so that the needle probe sticks out about 1/2 inch. Mix some clear 5-minute epoxy, and let it thicken ever so slightly. Then , while holding the assembly vertically (i.e., probe-tip up), and using a small toothpick or screwdriver, drop epoxy into the probe area, sealing the electronics and probe into place. Allow to dry thoroughly before applying any pressure to the assembly.

When dry, attach your favorite ground-clip to the pigtail, and banana plugs on the end of the shielded cable (red to the center-conductor, black to the shield, to match your Voltmeter)



Click on the image above to see a larger, annotated image

See the next image, below, which shows the completed assembly, annotated. Sometimes, seeing the entire assembly makes everything perfectly clear. Place the pen cap over the needle probe to protect the assembly when not in use.



Click on the image above to see a larger, annotated image

And speaking of use, here's our lovely model (OK...XYL) making a measurement in the N0SS Noise Generator. She has the ground clip connected to a convenient place in the circuit's ground, and the probe touches the test point we want to measure. As you can see, we read 0.710 Volts. Since this is broadband noise, the actual voltage reading is not accurate, but it was seen to be much greater than the previous stage, as we expected.

Click on the image above to see a larger, more readable image

Let me know if you build one of these... and send me a picture!

73, monty N5ESE

[Return to N5ESE home page](http://www.n5ese.com/)

Overseer: Monty Northrup ... e-mail ... leave e-mail ...

maddog homepage [Visit our regular (non-ham, but very popular) homepage]()

A Coax Switch



Cheap slide switch in a standard 54 × 50 × 26 mm box.

THE SWITCH



Fig » shows a proven inexpensive home-made antenna selection switch. If you question the use of a cheap slide switch and SO239 coax sockets, read on. Measurements in a physics lab showed there to be practically no reflection on HF and even on 70 cm the SWR was below 1.3 : 1! That is explained as follows:

- The contacts in the slide switch have larger contact surfaces than many a bought coaxial switch.

- The wiring and switch contacts, between the top and bottom of the metal case, act as the centre conductor of a coax of near 50 ?.

It is a standard box measuring 54 × 50 × 26 mm (l × w × h) and the wiring between the switch and the coax sockets is done in 2 mm silver plated wire.

POWER HANDLING CAPABILITY

If the switching is done with power off, the switch can stand 800 W. I have used this switch for more than 15 years and even with 1500 W there have been no problems.



While building this switch, you might as well add a test point, e.g. to connect a ‘scope’ or frequency counter. The capacitors of 10 and 220 pF make a capacitive voltage divider and the extra loading, 9.6 pF, does not affect performance on HF. In fact, on 10 m it improves the SWR as the extra capacity, in combination with the wiring it makes a filter which favours that frequency.



This shows how the switch is used in my station.

«Back
AØFRI


a
utput
Antenna
Rectifier Circuit
b
c
d

Int. J. Communications, Network and System Sciences, 2010, 3, 204-207
doi:10.4236/ijcns.2010.32029 Published Online February 2010 (http://www.SciRP.org/journal/ijcns/).

Geometry Aspects and Experimental Results of a Printed Dipole Antenna

Constantinos VOTIS[1], **Vasilis CHRISTOFILAKIS**[1,2], **Panos KOSTARAKIS**[1]
[1]*Physics Department, University of Ioannina, Panepistimioupolis, Ioannina, Greece*
[2]*Siemens Enterprise Communications, Enterprise Products Development, Athens, Greece*
E-mail: *kvotis@grads.uoi.gr, basilios.christofilakis@siemens-enterprise.com, kostarakis@uoi.gr*

Received November 2, 2009; *revised December* 10, 2009; *accepted January* 12, 2010

Abstract

Detail experimental measurements of a 2.4 GHz printed dipole antenna for wireless communication systems is presented and discussed. A group of printed dipoles with integrated balun have been designed and constructed on a dielectric substrate. This paper is based on modifications of the known printed dipole architecture. The corresponding printed dipole antennas have differences on their forms that are provided by two essential geometry parameters. The first parameter *l* is related to the bend on microstrip line that feeds the dipole and the second *w* corresponds to the form of the dipole's gap. The impact of these parameters on reflection coefficient and radiation pattern of antenna has been investigated. The corresponding measured results indicate that the return loss and radiation pattern of a printed dipole antenna are independent of the *w* parameter. Instead, variations in the value of the *l* parameter in the dipole's structure affect the form of the corresponding return loss. These observations are very important and provide interesting considerations on affecting design and construction of antenna elements at frequency range of 2.4 GHz.

Keywords: Printed Dipole, Scattering Parameters, Radiation Pattern

1. Introduction

Modern wireless communications offer higher bit rates and efficient quality of services. The majority of the equipment used today introduces requirements for better performance and lower cost. Antennas with quite small sizes, low profiles and versatile features represent interesting solutions that provide modern wireless applications. The printed dipole antenna with integrated balun is widely used as a radiation element on communication systems because of its omni-directional features, narrowband character and simple structure [1–4]. This type of antenna because of its small size can be integrated on the same PCB with other electronics circuits and devices. For the same reason, it can also be used as element on antenna array architecture. The last feature is very interesting and attractive in MIMO modern wireless systems. This printed dipole architecture offers versatile characteristics for design and implementation of antenna arrays on both ends of a MIMO wireless system.

In the present paper, we will study and discuss the effect of the variation of the two geometrical parameters (*l*, *w*) of the printed dipole antenna structure. The first corresponds to a discontinuity on microstrip line of printed dipole and the second is related to the discontinuity in the gap. Details of structure concept and design process are presented in Section 2; the experimental results for return loss and radiation pattern for each of the printed dipoles are presented and discussed in Section 3. The paper concludes in Section 4.

2. Design and Structure Aspects

As mentioned above, the proposed analysis is based on geometrical characteristics of a prototype printed dipole antenna with integrated balun. This kind of printed dipole antenna is considered for use in many applications [1–3]. In our study the geometrical parameters of the printed dipole antenna were modified to achieve better performance in the frequency range of 2.4 GHz. This modified design and the corresponding parameters are shown in Figure 1 while the values summarized in Table 1.

Identify applicable sponsor/s here. *(sponsors)*

Copyright © 2010 SciRes.



(a) Bottom Layer



(b) Top Layer

Figure 1. Geometry of printed dipole.

Table 1. Printed dipole dimensions.

Parameter	Values
Dipole strips	L1 = 20.8 mm W1 = 6 mm g1 = 3 mm
Microstrip Balun	L2 = 32 mm L3 = 16 mm L4 = 3 mm L5 = 3 mm W2 = 2 mm W3 = 5 mm W4 = 3 mm g2 = 1 mm
Via radius	r = 0.375 mm
Ground plane	L6 = 12 mm W5 = 17 mm
Side of microstrip bend	l variable (0 mm – 3 mm)
Side of dipole's arms in the gap	w variable (0 mm – 3 mm)



Figure 2. Prototype printed dipole antenna: Top Layer (left) –Bottom Layer (right).

An Fr-4 substrate with thickness of 1.5 mm and permittivity ε_r =4.4 has been used for the fabrication of the dipoles. Figure 2 shows the top and bottom layer for the one of them. It also presents the dipole's arms and gap, the balun, the ground plane and the microstrip line that interface the dipole with the coaxial feed line via sma connector.

From this Figure, we can also see the right angle at the microstrip line and the other two right angles at the dipole's gap. It is known that the presence of right angles in conductors cause discontinuities that leads to degradation in circuit performance [5]. Microwave theory suggests that these angles introduce parasitic reactances which can lead to phase and amplitude errors, input and output mismatch and possibly spurious coupling [5–7]. In order to reduce this effect it is proposed to modify these discontinuities directly, by mitering the conductor. Our investigation and the experimental measurements show the effect of mitering these discontinuities. At first, a prototype printed dipole antenna with unaffected geometrical parameters has been designed and constructed. Secondly, we constructed and measured six different printed dipoles. Three of them had *w = 0 mm* and different *l* values (1 mm, 2 mm, 3 mm) and the other three dipoles had *l = 0 mm* and different values of *w* (1 mm, 2 mm, 3 mm). All these seven dipoles we constructed, the unaffected one and the mitered ones were measured in an anechoic environment. Figures 3 and 4 show a printed dipole for *l = 2 mm* and *w = 0* mm and for *l = 0 mm* and *w = 3 mm*, respectively. The aim of this study is to investigate the return loss coefficient and radiation pattern in each of these seven dipole's forms. The next section discusses the obtained results and presents the significant observations.

3. Results and Discussion

The return loss of the prototype dipole and the six different modified printed dipole antenna we constructed are measured using a Network Analyzer. These results are shown in two Figures. The first (Figure 5) corresponds to *l* parameter's variations keeping the *w* parameter equal to zero. The second (Figure 6) shows the return loss curves where *w* parameter varies but the *l* parameter equals to zero. In both figures we can see the return loss curve that belongs to the prototype printed dipole (*l* and *w equal to 0 mm*).

From these curves, it seems that this dipole antenna design has a resonance point at 2.4 GHz with 500 MHz –



Figure 3. Printed dipole antenna for *l = 2 mm* and *w = 0 mm* Top Layer (left) – Bottom Layer (right).

Copyright © 2010 SciRes.



Figure 4. Printed dipole antenna for *l = 0 mm* and *w = 3 mm* Top Layer (left) – Bottom Layer (right).



Figure 5. Measured return loss of printed dipole for each value of *l* parameter and *w = 0* mm.



Figure 6. Measured return loss of printed dipole for each value of *w* parameter and *l = 0 mm.*

10 dB bandwidth. The last frequency range has center frequency close to 2.4 GHz which is the frequency value that the return loss is minimized. For these frequencies the corresponding values of return loss are smaller or equal to -10 dB. From Figure 5, it is obvious that as the value of *l* parameter increases, the form of the corresponding return loss curve changes and becomes more flat at the resonance frequency range. On the other hand, the value of *w* parameter does not affect the form of the return loss curve. Each of these seven forms of printed dipole antenna has quite similar return loss curves and introduces narrowband operation at the frequency range of 2.4 GHz. Moreover, for a wireless application that requires design and construction of many identical printed dipoles, it is recommended to choose *l* parameter equals to *2 mm* and *w* parameter equals to *0 mm* for better performance. As it can be seen from Figure 5 the above investigation ensures that the printed dipole antennas will have quite identical return loss curves and performance as elements in an antenna array configuration.

For deeper analysis on this topic, experimental measurements on radiation pattern of these antennas have also been made. Measurements were carried out in a RF anechoic chamber using a calibrated measuring system. In particular, Figure 7 shows the measurements of radiation pattern in E- plane and in H – plane for each dipole



(a)

(b)

Figure 7. Radiation pattern of dipole for each value of *l* parameter (a) E – plane, (b) H -plane.



(a)

(b)

Figure 8. Radiation pattern of dipole for each value of *w* parameter (a) E – plane, (b) H – plane.

with *w* parameter equals to 0 mm and *l* parameter equals to integer values that ranging from *0 mm* to *3 mm*,. Figure 8 shows the corresponding results for each dipole with *l* parameter equals to *0 mm* and *w* parameter's integer values ranging from *0 mm* to *3 mm*. All these dipole structures introduce radiation characteristics that correspond to a fundamental dipole antenna [6,7]. Each of them has a measured peak gain that equals to quite 2 dBi and introduces omni-directional features. Quite small variations on these curves are on the limits of measurements' accuracy. For this reason, it can be observed that the radiation characteristics of the printed dipole antenna are not affected by the variations on *l* and *w* geometrical parameters. Therefore, the radiation diagrams of them are independent of the *l* and *w* parameters.

4. Conclusions

A number of printed dipole antennas with integrated balun are constructed and studied in terms of return loss and radiation pattern. Each of them has a defined form and geometry. Starting from a dipole antenna we mitered the angles introducing the parameters *l* and *w* that we varied. Experimental measurements on return loss provide the obtained results. These are quite similar and also introduce a resonance point at frequency range of 2.4 GHz with narrow resonance bandwidth. The form of this resonance range is affected only by the *l* parameter. The radiation pattern of these dipoles is also investigated. The corresponding radiation diagrams are independent of these geometrical parameters (*l*, *w*) and are similar to that of the fundamental dipole. These observations on printed dipole architecture are very crucial for wireless communication engineering and antenna design. This is because they introduce the ability of constructing a group of identical dipoles choosing an appropriate value of *l* parameter (*l =2 mm*) with quite identical resonance and radiation characteristics.

5. Acknowledgment

This research project (PENED) is co-financed by E.U.-European Social Fund (80%) and the Greek Ministry of Development-GSRT (20%).

6. References

[1] D. Edward and D. Rees, "A broadband printed dipole with integrated balun," Microwave J, 1987, pp. 339–344.

[2] N. Michishita, H. Arai, M. Nakano, T. Satoh, and T. Matsuoka, "FDTD analysis for printed dipole antenna with balun," Asia Pacific Microwave Conference, 2000, pp. 739–742.

[3] G. S. Hilton, C. J. Railton, G. J. Ball, A. L. Hume, and M. Dean, "Finite–difference time–domain analysis of a printed dipole antenna," 19th Int. IEEE Antennas and Propagation Conference, 1995, pp. 72–75.

[4] H. R. Chuang and L. C. Kuo, "3-D FDTD design analysis of a 2.4 GHz polarization – diversity printed dipole antenna with integrated balun and polarization– switching circuit for wlan and wireless communication application," IEEE Transactions on Microwave Theory and Techniques, Vol. 51, No. 2, 2003.

[5] D. M. Pozar, Microwave Engineering, Wiley, 1998.

[6] C. A. Balanis, Antenna Theory Analysis and Design, Wiley, 1997.

[7] R. Garg, P. Bhartia, I. Bahl, and A. Ittipiboon, Microstrip Antenna Design Handbook, Artec House, 2001.

Copyright © 2010 SciRes.

Circuits and Systems, 2012, 3, 216-222
http://dx.doi.org/10.4236/cs.2012.33030 Published Online July 2012 (http://www.SciRP.org/journal/cs)

Optimization of the Voltage Doubler Stages in an RF-DC Convertor Module for Energy Harvesting

Kavuri Kasi Annapurna Devi[1*], **Norashidah Md. Din**[2], **Chandan Kumar Chakrabarty**[2]
[1]Department of Electrical and Electronic Engineering, INTI International University, Nilai, Malaysia
[2]Department of Electronics and Communication Engineering, Universiti Tenega Nasional, Kajang, Malaysia
Email: {*kavurik.adevi., chandan}@newinti.edu.my, norashidah@uniten.edu.my

Received August 25, 2011; revised March 26, 2012; accepted April 4, 2012

ABSTRACT

This paper presents an optimization of the voltage doubler stages in an energy conversion module for Radio Frequency (RF) energy harvesting system at 900 MHz band. The function of the energy conversion module is to convert the (RF) signals into direct-current (DC) voltage at the given frequency band to power the low power devices/circuits. The design is based on the Villard voltage doubler circuit. A 7 stage Schottky diode voltage doubler circuit is designed, modeled, simulated, fabricated and tested in this work. Multisim was used for the modeling and simulation work. Simulation and measurement were carried out for various input power levels at the specified frequency band. For an equivalent incident signal of –40 dBm, the circuit can produce 3 mV across a 100 kΩ load. The results also show that there is a multiplication factor of 22 at 0 dBm and produces DC output voltage of 5.0 V in measurement. This voltage can be used to power low power sensors in sensor networks ultimately in place of batteries.

Keywords: Energy Conversion; RF; Schottky Diode; Villard; Energy Harvesting

1. Introduction

RF energy harvesting is one type of energy harvesting that can be potentially harvested such as solar, vibration and wind. The RF energy harvesting uses the idea of capturing transmitted RF energy at ambient and either using it directly to power a low power circuit or storing it for later use. The concept needs an efficient antenna along with a circuit capable of converting RF signals to DC voltage. The efficiency of an antenna mainly depends on its impedance and the impedance of the energy converting circuit. If the two impedances aren't matched then it will be unable to receive all the available power from the free space at the desired frequency band. Matching of the impedances means that the impedance of the antenna is the complex conjugate of the impedance of the circuit (voltage doubler circuit).

The concept of energy harvesting system is shown in **Figure 1**, which consists of matching network, RF-DC conversion and load circuits. The authors in [1], used a 2.4 GHz operating frequency with an integrated zero bias detector circuit using BiCMOS technology which produced an output voltage of 1 V into a 1 MΩ load at an input power level of 0 dBm. H. Yan and co-authors revealed that a DC voltage of 0.8 volts can be achieved from a –20 dBm RF input signal at 868.3 MHz through simulation results [2]. In [3], work was carried out on a firm frequency of 900 MHz by matching to a 50 Ω impedance and resonance circuit transformation in front of the Schottky diode which yields an output voltage of over 300 mV at an input power level of 2.5 µ. W. J. Wang, L. Dong and Y. Fu [4] used a Cockcroft-Walton multiplier circuit that produced a voltage level of 1.0 V into a 200 MΩ load for an input power level of less than –30 dBm at a fixed frequency of 2.4 GHz.

The energy conversion module designed in this paper is based on a voltage doubler circuit which can be able to output a DC voltage typically larger than a simple diode rectifier circuit as in [5], in which switched capacitor charge pump circuits are used to design two phase voltage doubler and a multiphase voltage doubler. The module presented in this can function as an AC to DC converter that not only rectifies the input AC signal but also elevates the DC voltage level. The output voltage of the



Figure 1. Schematic view of a RF energy harvesting system.

---

[*] Corresponding author.

Copyright © 2012 SciRes.

energy conversion module can be used to energize the low power devices for example sensors for a sensor network in application to agriculture.

Section 2 of this paper discusses on the theoretical background of the voltage doubler circuit. Section 3 presents the simulation study and implementation of the circuit design. Section 4 provides the results and analysis. Section 5 concludes with a discussion on the findings from the simulated and measured results.

2. Voltage Multiplier

There are various voltage multiplier circuit topologies. The design used in this module is derived from the function of peak detector or a half wave peak rectifier. The Villard voltage multiplier circuit was chosen in the circuit design of this paper because it produces two times of the input signal voltage towards ground at a single output and can be cascaded to form a voltage multiplier with an arbitrary output voltage and its design simplicity.

2.1. Diode Modeling

The voltage multiplier circuit in this design uses zero bias Schottky diode HSMS-2850 from Agilent. The attractive feature of these Schottky diodes are low substrate losses and very fast switching but leads to a fabrication overhead. This diode has been modeled for the energy harvesting circuit which comes in a one-diode configuration. The modeling parameters for these diodes are given by Agilent in their data sheets. These parameters are used in Multisim for its own modeling purposes. The modeling is done by transforming the diode into an equivalent circuit using passive components which are described by the SPICE parameters in **Table 1** [6].

The diode used in this design is shown in **Figure 2** and its equivalent model is shown in **Figure 3**. The special features of HSMS-2850 diode is that it provides a low forward voltage, low substrate leakage and uses the non symmetric properties of a diode that allows unidirectional flow of current under ideal condition.

Table 1. SPICE parameters.

Parameters	Units	HSMS 2850
B_V	V	3.8
C_{J0}	pF	0.18
E_G	Ev	0.69
I_{BV}	A	3E–4
I_S	A	3E–6
N	No unite	1.06
R_S	Ω	25
P_B (V_J)	V	0.35
P_T (XTI)	No units	2
M	No units	0.5



Figure 2. Schottky diode.



Figure 3. Linear circuit model of the Schottky diode [6].

The diodes are fixed and are not subject of optimization or tuning. This is described using the following derivations. By neglecting the effect of diode substrate, an equivalent linear model that can be used for the diode as shown in **Figure 3**. When C_j is the junction capacitance and R_j is the junction resistance, the admittance Y_z of the linear model is given by

$$Y_Z = Y_{C_j} + Y_{R_j} \tag{1}$$

Equation (1) related to the frequency of operation is given by

$$Y_Z = jwC_j + \frac{1}{R_j} \tag{2}$$

$$= \frac{jwC_jR_j + 1}{R_j} \tag{3}$$

The impedance Z of the linear model is given by

$$Z = \frac{R_j}{1 + jwR_jC_j} \tag{4}$$

The total impedance Z_T is given by

$$Z_T = R_S + \frac{R_j}{1 + jwR_jC_j} \tag{5}$$

where R_S is the series resistance of the circuit and R_j is given by

$$R_j = \frac{8.33\times10^{-5}\times N\times T}{I_b + I_S}$$

where:

I_b = bias current in μA;
I_s = saturation current in μA;
T = temperature (K);

Copyright © 2012 SciRes.

N = ideality factor.

In Equation (5), R_j and C_j are constants and the frequency of operation (w) is the only variable parameter. As the frequency increases, the value of Z is almost negligible compared to the series resistance R_S of the diode. From this it is concluded that the function of the diode is independent of the frequency of operation.

2.2. Single Stage Voltage Multiplier

Figure 4 represents a single stage voltage multiplier circuit. The circuit is also called as a voltage doubler because in theory, the voltage that is arrived on the output is approximately twice that at the input. The circuit consists of two sections; each comprises a diode and a capacitor for rectification. The RF input signal is rectified in the positive half of the input cycle, followed by the negative half of the input cycle. But, the voltage stored on the input capacitor during one half cycle is transferred to the output capacitor during the next half cycle of the input signal. Thus, the voltage on output capacitor is roughly two times the peak voltage of the RF source minus the turn-on voltage of the diode.

The most interesting feature of this circuit is that when these stages are connected in series. This method behaves akin to the principle of stacking batteries in series to get more voltage at the output. The output of the first stage is not exactly pure DC voltage and it is basically an AC signal with a DC offset voltage. This is equivalent to a DC signal superimposed by ripple content. Due to this distinctive feature, succeeding stages in the circuit can get more voltage than the preceding stages. If a second stage is added on top of the first multiplier circuit, the only waveform that the second stage receives is the noise of the first stage. This noise is then doubled and added to the DC voltage of the first stage. Therefore, the more stages that are added, theoretically, more voltage will come from the system regardless of the input. Each independent stage with its dedicated voltage doubler circuit can be seen as a single battery with open circuit output voltage V_0, internal resistance R_0 with load resistance R_L, the output voltage, V_{out} is expressed as in Equation (7).



Figure 4. Single stage voltage multiplier circuit [7].

$$V_{out} = \frac{V_0}{R_0 + R_L} R_L \qquad (6)$$

When n number of these circuits are put in series and connected to a load of R_L in Equation (6) the output voltage V_{out} obtained is given by this change in RC value will make the time constant longer which in turn retains the multiplication effect of two in this design of seven stage voltage doubler.

$$V_{out} = \frac{nV_0}{nR_0 + R_L} = V_0 \frac{1}{\frac{R_0}{R_L} + \frac{1}{n}} \qquad (7)$$

The number of stages in the system has the greatest effect on the DC output voltage, as shown from Equations (6) and (7).

It is inferred that the output voltage V_{out} is determined by the addition of R_0/R_L and $1/n$, if V_0 is fixed. From this analysis it is observed that V_0, R_0 and R_L are all constants. Assume that $V_0 = 1$ V, $R_0/R_L = 0.25$, n = 2, 3, 4, 5, 6 and 7, the output voltage V_{out} = 1.33 V, 1.72 V, 2.0 V, 2.22 V, 2.43 V and 2.56 V respectively when substituted analytically in the Equation (7). This analysis can be compared with the results obtained in the circuit design of this module. In simulation at $n = 4$, $V_{out} = 1.42$ V, $n = 5$, $V_{out} = 1.67$ V; $n = 6$, $V_{out} = 1.92$; $n = 7$, $V_{out} = 2.15$ V; $n = 8$, $V_{out} = 1.92$ V; $n = 9$, $V_{out} = 1.81$ V. Also in measurement, for $n = 4$, $V_{out} = 2.1$ V; $n = 5$, $V_{out} = 2.9$ V; $n = 6$, $V_{out} = 3.72$ V; and $n = 7$, $V_{out} = 5$ V. As n increases, the increase in output voltage will be almost double the input voltage up to some number of stages. But at some point, *i.e.* beyond seven stages, in this circuit the output voltage gained (8 and 9 stages) will be negligible as shown in **Figure 5**.

The capacitors are charged to the peak value of the input RF signal and discharge to the series resistance (R_s) of the diode. Thus the output voltage across the capacitor of the first stage is approximately twice that of the input signal. As the signal swings from one stage to other, there is an additive resistance in the discharge path of the



Figure 5. Normalized output voltage multiplier versus number of stages.

diode and increase of capacitance due to the stage capacitors.

2.3. Seven Stage Voltage Multiplier

The seven stage voltage multiplier circuit design implemented in this paper is shown in **Figure 6**. Starting on the left side, there is a RF signal source for the circuit followed by the first stage of the voltage multiplier circuit. Each stage is stacked onto the previous stage as shown in the **Figure 6**. Stacking was done from left to right for simplicity instead of conventional stacking from bottom to top.

The circuit uses eight zero bias Schottky surface-mount Agilent HSMS-285X series, HSMS-2850 diodes. The special features of these diode is that, it provides a low forward voltage, low substrate leakage and uses the non-symmetric properties of a diode that allows unidirectional flow of current under ideal conditions. The diodes are fixed and are not subject of optimization or tuning. This type of multiplier produces a DC voltage which depends on the incident RF voltage. Input to the circuit is a predefined RF source. The voltage conversion can be effective only if the input voltage is higher than the Schottky forward voltage.

The other components associated with the circuit are the stage capacitors. The chosen capacitors for this circuit are of through-hole type, which make it easier to modify for optimization, where in [8] the optimization was accomplished at the input impedance of the CMOS chip for a three stage voltage multiplier. The circuit design in this paper uses a capacitor across the load to store and provide DC leveling of the output voltage and its value only affects the speed of the transient response. Without a capacitor across the load, the output is not a good DC signal, but more of an offset AC signal.

In addition to the above, an equivalent load resistor is connected at the final node. The output voltage across the load decreases during the negative half cycle of the AC input signal. The voltage decreases is inversely proportional to the product of resistance and capacitance across the load. Without the load resistor on the circuit, the voltage would be hold indefinitely on the capacitor and look like a DC signal, assuming ideal components. In the design, the individual components of the stages need not to be rated to withstand the entire output voltage. Each component only needs to be concerned with the relative voltage differences directly across its own terminals and of the components immediately adjacent to it. In this type of circuitry, the circuit does not change the output voltage but increases the possible output current by a factor of two. The number of stages in the system is directly proportional to the amount of voltage obtained and has the greatest effect on the output voltage as explained in the Equation (7) and shown in **Figure 5**.

3. Simulation and Implementation

Multisim software was chosen for modeling and simulation which is a circuit simulation tool by Texas Instruments. The simulation and practical implementation were carried out with fixed RF at 945 MHz ± 100 MHz, which are close to the down link center radio frequency (947.5 MHz) of the GSM-900 transmitter. The voltages obtained at the final node V_{DC} of the multiplier circuit were recorded for various input power levels from –40 dBm - +5 dBm with power level interval (spacing) of 5 dBm.

The simulations were also carried out using same stage capacitance value (3.3 nF) and then with a varied capacitance value for all stages from 4 stages through 9 stages [9]. The capacitance value was varied in such a way that, from one stage to the next, it was halved. For example, if the first stage was 3.3 nF, the second stage was 1.65 nF, third stage was 825 pF, fourth stage was 415 pF and so on. But keeping in view of testing, the capacitance values were chosen to have a close match with the standard available values in the market.

Simulation was carried out through 4 to 9 voltage doubler stages. Based on results obtained a 7 stage doubler is best to implemented for this application.

The design of the printed circuit board (PCB) was carried out using DipTrace software. The material used to



Figure 6. Schematic of 7 stage voltage multiplier.

Copyright © 2012 SciRes.

manufacture the printed circuit board (PCB) is the standard Fiberglass Reinforced Epoxy (FR4), with the thickness of 1.6 mm and dielectric constant of 3.9. The topology is constructed on the PCB with the dimensions of 98 mm × 34 mm (W × H). The Sub Miniature version A (SMA) connectors are used at the input and output of PCB to carry out the measurements. The circuit components consist of active and passive components. The component used in circuit is shown in **Table 2**.

Special handling precautions have been taken to avoid Electro Static Discharge (ESD), while assembling of the surface-mount zero bias Schottky diodes. Also special attention has been given to mount other components and the SMA connectors on to the PCB. The Photograph of Assembled circuit board I shown in **Figure 7**.

4. Results and Analysis

The simulated and measured results at the output voltage of voltage multiplier circuit are shown graphically in **Figure 8**. From the graph analysis, the simulated and the measured results agree considerably with each other. The measured results are shown to be better than the simulation results. The reason behind this may be due to the uncertainty in series resistance value of the diode obtained from SPICE parameters in modeling as explained in Equation (5). This resistance vale of diodes in practical circuit may be lower than in the model, which provides fast discharge path, in turn rise in voltage as passes through the stages and reaches to final output. In this work, the DC output voltages obtained through simulation and measurement at 0 dBm re 2.12 V and 5.0 V respectively. These results are comparatively much better than in ref. [9], where in at 0 dBm, 900 MHz they achieved 0.5 V and 0.8 V through simulation and measurement respectively.

Figures 9 and **10** show the result of a 4 stage voltage doubler circuit with equal and varied capacitance values between the stages as described in Section 3.

From the analysis of these two simulations, it can be observed that the resulting output voltages are equal. The only difference between these two graphs is the rise time of the circuit with varied capacitance value is a little bit slower. But, overall result on the performance of rise time is still under 20 μs to 24 μs and the difference is negligible. From these results, the use of equal stage capacitance of each being 3.3 nF was hence considered for the design of the multiplier.

The results from **Figure 11**, shows that the output voltage reaches to 1.0 V within 20 μS and then uniformly increasing to 1.4 V, 1.67 V, 1.87 V and 2.12 V for 4, 5, 6 and 7 stages respectively compared to 2 mS as shown in [10]. **Figure 12** shows that the conversion ratio of 22 is achieved at 0 dBm input power and drops to 2.5 at –40 dBm. The highest value at 0 dBm is due to the innate characteristics of the zero bias Schottky diodes which conduct fairly well at higher input voltages.

5. Conclusion

From the experimental results, it is found that the pro-

Table 2. Component used in 7 stage voltage multiplier.

Name of component	Label	Value
Stage capacitors	C_1 - C_{14}	3.3 nF
Stage diodes	D_1 - D_{14}	HSMS 2850
Filter capacitor	C_L	100 nF
Load resister	R_L	100 kΩ



Figure 7. Photograph of assembled circuit board.



Figure 8. Simulated and test DC output voltage of multiplier as a function of input power.



Figure 9. DC output voltage verses rise time of 4 stage voltage doubler circuit with equal stage capacitance [8].



Figure 10. DC output voltage verses rise time of 4 stage voltage doubler with varied stage capacitance [8].

posed voltage multiplier circuit operates at the frequency of 945 MHz with the specified input power levels. The results have shown that there is multiplication of the input voltage. From **Figure 12**, it is shown that at 0 dBm input power, the multiplication factor is 22. This is significant, as the work shows that RF energy in the GSM-900 band can be harvested from the ambient RF source using the Villard circuit topology. The power density levels from a GSM base station is expected from 0.1 mW/m^2 to 1 mW/m^2 for a distance ranging from 25 m - 100 m. These power levels may be elevated by a factor between one and three for the GSM-900 downlink frequency bands depending on the traffic density [10]. The next phase of the research work is to interface the voltage multiplier circuit through a matching network to the antenna at the input side and a low power device to power from the system at the output side to complete the RF energy harvesting system.



Figure 11. DC output voltage verses rise time of voltage doubler circuit through 4 - 7 stages with equal stage capacitance.



Figure 12. Conversion ratio as a function of input power.

6. Acknowledgements

We would like to acknowledge and thank the Ministry of Higher Education Malaysia for funding this project under Fundamental Research Grant: FRGS/1/10/TK/UNITEN/02/13.

Copyright © 2012 SciRes.

REFERENCES

[1] S. von der Mark and G. Boeck, "Ultra Low Power Wakeup Detector for Sensor Networks," *SBMO/IEEE MTT-S International Microwave & Optoelectronics Conference* (*IMOC* 2007), Berlin, 29 October-1 November 2007, pp. 865-868. doi:10.1109/IMOC.2007.4404394

[2] H. Yan, J. G. M. Montero, A. Akhnoukh, L. C. N. de Vreede and J. N. Burghartz, "An Integration Scheme for RF Power Harvesting," *Proceedings of STW Annual Workshop on Semiconductor Advances for Future Electronics and Sensors*, Veldhoven, November 2005, pp. 64-66. doi:10.1.1.126.5786

[3] T. Ungan and L. M. Reindl, "Concept for Harvesting Low Ambient RF-Sources for Microsystems," 2007. http://www.imtek.de/content/pdf/public/2007/powermems_2007_paper_ungan.pdf

[4] J. Wang, L. Dong and Y. Z. Fu, "Modeling of UHF Voltage Multiplier for Radio-Triggered Wake-Up Circuits," *International Journal of Circuit Theory and Application*, Vol. 39, No. 11, 2010, pp. 1189-1197. doi:10.1002/cta.692

[5] J. A. Starzyk, Y.-W. Jan and F. J. Qiu, "A DC-DC Charge Pump Design Based on Voltage Doublers," *IEEE Transactions on Circuits and Systems-I*: *Fundamental Theory and Applications*, Vol. 48, No. 3, 2001, pp. 350-359.

[6] HSMS-2850, "Surface Mount Zero Bias Schottky Detector Diodes." http://www.crystal-radio.eu/hsms285xdata.pdf

[7] D. W. Harrist, "Wireless Battery Charging System Using Radio Frequency Energy Harvesting," M.S. Thesis, University of Pittsburgh, Pittsburgh, 2004.

[8] E. Bergeret, J. Gaubert, P. Pannie and J. M. Gaultierr, "Modeling and Design of CMOS UHF Voltage Multiplier for RFID in an EEPROM Compatible Process," *IEEE Transactions on Circuits and Systems-I*, Vol. 54, No. 10, 2007, pp. 833-837. doi:10.1109/TCSII.2007.902222

[9] B. Emmanuel, J. Gaubert, P. Pannier and J. M. Gaultier, "Conception of UHF Voltage Multiplier for RFID Circui," *IEEE North-East Workshop on Circuits and Systems*, Gatineau, June 2006, pp. 217-220. doi:10.1109/NEWCAS.2006.250961

[10] H. J. Visser, A. C. F. Reniers and J. A. C. Theeuwes, "Ambient RF Energy Scavenging: GSM and WLAN Power Density Measurements," *Proceedings of the* 38*th European Microwave Conference*, Eindhoven, 27-31 October 2008, pp. 721-724. doi:10.1109/EUMC.2008.4751554

Copyright © 2012 SciRes.

Journal of Electromagnetic Analysis and Applications, 2013, 5, 182-188
http://dx.doi.org/10.4236/jemaa.2013.54029 Published Online April 2013 (http://www.scirp.org/journal/jemaa)

Double-Sided Microstrip Circular Antenna Array for WLAN/WiMAX Applications

Ruwaybih Alsulami, Heather Song*

Department of Electrical and Computer Engineering, University of Colorado, Colorado Springs, USA.
Email: *hsong@uccs.edu

Received February 8th, 2013; revised March 10th, 2013; accepted March 25th, 2013

Copyright © 2013 Ruwaybih Alsulami, Heather Song. This is an open access article distributed under the Creative Commons Attribution License, which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

ABSTRACT

The design, fabrication, and characterization of the microstrip circular antenna arrays were presented. The proposed antennas were designed for single band at 2.45 GHz and dual bands at 3.3 - 3.6 and 5.0 - 6.0 GHz to support WLAN/WiMAX applications. The proposed single and dual band antennas showed omnidirectional radiation pattern with the gain values of 3.5 dBi at 2.45 GHz, 4.0 dBi at 3.45 GHz, and 3.3 dBi at 5.5 GHz. The dual band antenna array was placed on both top and bottom layers to obtain the desired antenna characteristics. The proposed double-sided dual band antenna provides omnidirectional radiation pattern with high gain.

Keywords: Antenna Arrays; Circular Patch; Dual Band; Single Band; Omnidirectional; WLAN/WiMAX Applications; UWB

1. Introduction

Ultra-wideband (UWB: 3.1 to 10.6 GHz) frequency spectrum has been approved by the US Federal Communications Commission (FCC) for unlicensed short range wireless communications since 2002. In this frequency range, wireless local-area network (WLAN) IEEE802.11a and HIPERLAN/2 WLAN operates in 5.0 - 6.0 GHz band. In some European and Asian countries, world interoperability for microwave access (WiMAX) service is provided in the frequency range of 3.3 - 3.6 GHz [1-4]. To support the WLAN/WiMAX application, antenna arrays that provide omnidirectional radiation pattern are required. To respond to this need, recent antenna design efforts were focused on omnidirectional antennas with high gain and no sidelobes [5-8]. Rectangular arrays are common type used for antenna arrays. Studies on dual band antennas employing rectangular arrays were reported [9-12]. Compared to rectangular patch antenna arrays, there are limited numbers of studies performed on circular patch antenna arrays due to difficulties in fabrication [13]. Advantages of circular antenna array include high gain and narrow beam width [13].

In this paper, a new microstrip circular antenna arrays were designed, fabricated, and characterized to provide omnidirectional radiation pattern for WLAN/WiMAX applications. Two antenna arrays were designed—one for single band at 2.45 GHz and the other for dual bands at 3.3 - 3.6 GHz and 5.0 - 6.0 GHz. For single band operation, circular patch array was placed on the top layer of the microtrip and a small rectangular patch was placed on the bottom layer for ground connection. For dual band operation, similar circular patch array was placed on both top and bottom layers of the microstrip with larger rectangular patch placed on the bottom layer. Both single band (single sided) and dual band (double-sided) microstrip antenna arrays provided desirable antenna characteristics for the intended application.

2. Design and Simulation

2.1. Single-Band Antenna at 2.45 GHz

The configuration of the proposed single band antenna at 2.45 GHz is shown in **Figure 1**. It consists of six circular patches which are placed only on the top layer. The small rectangular patch is placed on the bottom layer for ground connection.

The directivity for the circular patch antenna is

$$D_0 = \frac{(k_0 a_e)^2}{120 G_{\text{rad}}} \tag{1}$$

---

*Corresponding author.



(a) (b) (c)

Figure 1. Configuration of the proposed antenna for single band at 2.45 GHz: (a) Top layer; (b) Bottom layer; (c) Top and bottom layers overlaid.

$$k_0 = \frac{2\pi}{\lambda_0} \tag{2}$$

$$a_e = a\left\{1 + \frac{2h}{\pi a \epsilon_r}\left[\ln\left(\frac{\pi a}{2h}\right) + 1.7726\right]\right\}^{1/2} \tag{3}$$

$$G_{\text{rad}} = \frac{\left(k_0 a_e\right)^2}{480}\int_0^{\pi/2}\left[J_{02}'^2 + \cos^2\theta J_{02}^2\right]\sin\theta \mathrm{d}\theta \tag{4}$$

$$J_{02}' = J_0\left(k_0 a_e \sin\theta\right) - J_2\left(k_0 a_e \sin\theta\right) \tag{5}$$

$$J_{02} = J_0\left(k_0 a_e \sin\theta\right) + J_2\left(k_0 a_e \sin\theta\right) \tag{6}$$

where a_e is the effective radius, a is the actual radius, ϵ_r is the relative permittivity of the microstrip dielectric substrate, h is the height of the microstrip substrate, and J_0 and J_2 are Bessel functions.

The gain of the antenna was calculated using

$$\text{Gain} = \text{Antenna Efficiency} \times \text{Directivity}\left(D_0\right) \tag{7}$$

$$\text{Antenna Efficiency} = \frac{\text{Total Efficiency}}{\text{Reflection Efficiency}} \tag{8}$$

The variable corresponding to each dimensions and values for the dimensions of the proposed antenna are shown in **Figure 2** and **Table 1**, respectively. Here, *L*, *W*, and *R* represent the length, the width, and the radius of the circular patch, respectively.

The gain of the proposed antenna shown in **Figure 1** was calculated using (1) - (8) and the dimensions were optimized using ADS [14] which resulted in gain of 3.5 dBi at 2.45 GHz.

2.2. Dual-Band Antenna at 3.3 - 3.6 and 5.0 - 6.0 GHz

The configuration for the doubled-sided microstrip dual band antenna is shown in **Figure 3**. The proposed microstrip antenna has circular arrays both on the top and bottom layers. It consists of three circular patched on each layer.



(a) (b)

Figure 2. Variables corresponding to each dimension of the proposed single band antenna: (a) Top layer; (b) Bottom layer.

Table 1. Dimensions for the proposed single band antenna at 2.4 GHz.

Variable	Value (mm)
L_1	1.15
L_2	28.9
L_3	1.13
L_4	17.6
L_5	6.60
L_6	35.3
L_7	18.4
L_8	18.4
W_1	1.02
W_2	1.52
W_3	3.30
W_4	6.86
R	5.10



(a) (b) (c)

Figure 3. Configuration of the proposed antenna for dual band at 3.3 - 3.6 and 5.0 - 6.0 GHz: (a) Top layer; (b) Bottom layer; (c) Top and bottom layers overlaid.

The configuration in **Figure 3(a)** is similar to the top layer of the single band antenna as shown in **Figure 1(a)** but with less circular patches. However, the bottom layer in **Figure 3(b)** is different compared to the bottom layer of the single band antenna shown in **Figure 1(b)**. The double-side nature of the antenna provides dual band characteristics. Identical equations were used for the single band antenna were employed in the design process. The variable corresponding to each dimensions and the dimensions for the proposed dual band antenna are shown in **Figure 4** and **Table 2**, respectively.

Simulation was performed using ADS for the configuration shown in **Figure 3(c)**. The simulated gains of the proposed dual band antenna were 4.0 dBi at 3.45 GHz and 3.3 dBi at 5.5 GHz. The double-sided configuration of the antenna provided higher gain compared to the singled-sided antenna.

3. Measurement Results and Discussions

3.1. Single-Band Atnenna at 2.45 GHz

The antennas were fabricated using LPKF Protomat [15] on FR-4 material with height of 1.524 mm. The photos of the fabricated single band antenna are shown in **Figure 5** which has a size of 6.7 × 4.4 (in cm).

Figure 6 shows the comparison between the simulated and the measured S_{11} results.

The measured operating frequency is close to 2.45 GHz with S_{11} value below −15 dB. The 3 dB bandwidth at 2.45 GHz was approximately 18%. The measurement and simulation are in fairly good agreement, and the differences are due to microstrip loss and fabrication errors.

Figure 7 shows the comparison between the simulated and measured radiation pattern in xy-plane at 2.45 GHz which is close to omnidirectional pattern.



(a) (b)

Figure 4. Variables corresponding to each dimension of the proposed dual-band antenna: (a) Top layer; (b) Bottom layer.

Table 2. Dimensions for the proposed dual band antenna at 3.3 - 3.6 and 5.0 - 6.0 GHz.

Variable	Value (mm)
L_1	1.20
L_2	17.8
L_3	1.08
L_4	6.60
L_5	29.3
L_6	10.0
L_7	21.6
L_8	17.8
W_1	1.02
W_2	1.52
W_3	2.54
W_4	49.1
R	5.21



(a) (b)

Figure 5. Photo of the fabricated single-band antenna: (a) Top layer; (b) Bottom layer.



Figure 6. Simulated and measured return loss for the proposed single-band antenna.



Figure 7. Simulated and measured radiation pattern in xy-plane (coordinate system shown in Figure 5) at 2.45 GHz.

3.2. Dual-Band Antenna at 3.3 - 3.6 and 5.0 - 6.0 GHz

The antennas were fabricated using LPKF Protomat [15] on double-sided FR-4 materials. The photos of the fabricated dual band antenna are shown in **Figure 8** which has a size of 6.6 × 5.2 (in cm).

Figure 9 shows the comparison between the simulated



(a) (b)

Figure 8. Photo of the fabricated dual-band antenna: (a) Top layer; (b) Bottom layer.



Figure 9. Simulated and measured return loss for the dual band antenna.

and the measured S_{11} results.

The measured S_{11} shows dual band near the designed bands with S_{11} values below −10 dB for both bands. The simulated and measured results give fairly good agreement, and the differences are due to board loss and fabrication errors.

Figure 10 shows the comparison between the simulated and measured radiation pattern in xy-plane at 3.45 and 5.5 GHz which is close to omnidirectional pattern.

4. Conclusion

A microstrip circular antenna arrays were presented for single band at 2.45 GHz and dual bands at 3.3 - 3.6 and



(a)



(b)

Figure 10. Simulated and measured radiation pattern in xy-plane (coordinate system shown in Figure 8) at (a) 3.45 GHz and (b) 5.5 GHz.

5.0 - 6.0 GHz for WLAN/WiMAX applications. Both antennas were designed with ADS, fabricated on a FR-4 microstrip material, and characterized. Both single band (single sided) and dual band (double-sided) antenna arrays provided omnidirectional pattern with desired gain.

REFERENCES

[1] C.-Y. Pan, T.-S. Horng, W.-S. Chen and C.-H. Huang, "Dual Wideband Printed Monopole Antenna for WLAN/ WiMAX Applications," *IEEE Antennas and Wireless Propagation Letters*, Vol. 6, 2007.

[2] A. C. Rao and R. Pandeeswari, "A CPW-Fed Antenna for Dual Band WiMAX/WLAN Applications," *IEEE International Conference on Recent Trends in Information Technology ICRTIT*, 2011.

[3] H.-Y. Lai, Z.-Y. Lei, Y.-J. Xie, G.-L. Ning and K. Yang, "UWB Antenna with Dual Band Rejection for WLAN/ WiMAX Bands Using CSRRs," *Progress in Electromagnetics Research Letters*, Vol. 26, 2011, pp. 69-78. doi:10.2528/PIERL11070112

[4] D. Parkash and R. Khanna "Design of a Dual Band Monopole Antenna for WLAN/WiMAX Applications," *IEEE Wireless and Optical Communications Networks*, 2010.

[5] L. Wang, K. Wei, J. Feng, Z. Zhang and Z. Feng, "A Wideband Omnidirectional Planar Microstrip Antenna for WLAN Applications," *IEEE*, 2011.

[6] J. Li, "An Omnidirectional Microstrip Antenna for WiMAX Applications," *IEEE Antennas and Wireless Propagation Letters*, Vol. 10, 2011.

[7] O. Tze-Meng and T. K. Geok, "A Dual-Band Omni-Directional Microstrip Antenna," *Progress in Electromagnetics Research*, Vol. 106, 2010, pp. 363-376. doi:10.2528/PIER10052411

[8] M. B. Bicer and A. Akdagli, "A Novel Microstrip-Fed Monopole Antenna for WLAN/WiMAX Applications," *Journal of Electromagnetic Waves and Applications*, Vol. 26, No. 7, 2012, pp. 904-913. doi:10.1080/09205071.2012.710372

[9] N. AbWahab, Z. Bin Maslan, W. N. W. Muhamad and N. Hamzah, "Microstrip Rectangular 4 × 1 Patch Array Antenna at 2.5 GHz for WiMAX Application," 2*nd International Conference on Computational Intelligence*, *Communication Systems and Networks*, 2010.

[10] Z. Zhong-xiang, C. Chang, W. Xian-liang and F. Minggang, "A 24 GHz Microstrip Array Antenna with Low Side Lobe," Springer, Berlin, 2012.

[11] A. K. Sahu and M. R. Das, "4 × 4 Rectangular Patch Array Antenna for Bore Sight Application of Consial Scan S-Band Traching Radar," *Antenna Week* (*IAW*), 2011.

[12] J. Das, T. A. Khan and M. K. Pal, "Rectangular Patch Antenna Array for Wireless Application," *International Journal of Engineering Science and Technology*, 2012.

[13] T. I. Huque, A. Chhowdhury, K. Hosain and S. Alam, "Performance Analysis of Corporate Feed Rectangular Patc Element and Circular Patch Element 4 × 2 Microstrip Array Antennas," *International Journal of Advanced Computer Science and Applications*, Vol. 2, No. 7, 2011, pp. 74-79.

[14] http://www.home.agilent.com/en/pc-1297113/advanced-design-system

[15] http://www.lpkf.com/protomat

J. Electromagnetic Analysis & Applications, **2011, 3, 43-46**
doi:10.4236/jemaa.2011.32008 Published Online February 2011 (http://www.SciRP.org/journal/jemaa)

Back to Back Combined Single Feed Proximity Coupled Antenna with Dumbbell Shaped DGS

Ashwini Kumar Arya, Amalendu Patnaik, Machavaram V. Kartikeyan

Department of Electronics & Computer Engineering, IIT Roorkee, Roorkee, India.
Email: ashwiniarya.iitr@gmail.com, {apatnaik, kartik}@ieee.org

Received November 12th, 2010; revised December 10th, 2010; accepted January 5th, 2011

ABSTRACT

Use of defected ground structure (DGS) to reduce the size of patch antenna is presented in this paper. In order to get a dipole like radiation pattern for some specific application a dumbbell shaped DGS is used in the common ground plane of back to back combined single fed proximity coupled antenna. A size reduction of about 60% is achieved. Parametric analysis has been done to see the resonance behavior of the antenna with DGS.

Keywords**:** *Defected Ground structure, Microstrip Antennas, Proximity Coupling*

1. Introduction

The continuous shrinking size of electronic equipments demands similar size antenna elements in order to fit properly in wireless devices without compromising the other radiation properties of the antenna. In this respect microstrip patch antennas are quite an obvious choice because of its other benefits like low profile, light weight, low cost and easy fabrication.

But as far as size of these patches concerned, the patch length should be around half-a-wavelength for the structure to act as a good radiator. Different techniques have already been used for the antenna size reduction such as using the substrate with high dielectric constant [1] , edge shorted patches with shorting plates or shorting walls, use of the shorting pin at the suitable position etc [2,3].

As far as our understanding goes much has not been reported regarding the use of DGS for size reduction of microstrip antennas, although its application have been reported for harmonic reduction [4], cross-polarization suppression [5] and mutual coupling reduction [6] in antenna arrays etc. Although the back to back geometries have been reported by the various researchers [7,8] but here a new coupling method *i.e.* proximity coupling with the defected ground structure is used for the consideration of the increased bandwidth.

This paper presents the application of DGS for size reduction of microstrip antennas. A dumbbell shaped DGS is used in the common ground plane of a back to back combined single feed proximity coupled microstrip antenna.

2. Defected Ground Structure

Recently there has been an increasing interest in the use of DGSs for performance enhancement of microstrip antennas and arrays. These are realized by etching off a simple shape defect from the ground plane of the planer circuits.

Although various complicated DGSs were reported in the literature, but the simplest one is the dumbbell shaped DGS. **Figure 1(a)** shows the simple and mostly used dumbbell shaped DGS that is etched in the ground plane below the microstrip line, in which both the areas (L_g*W_g) and the slot gap (g) play a very important role to find the resonance behavior of the DGS.

The head areas (L_g*W_g) is very useful for the variation in the inductance (L) and the slot (g) produces the capacitance (C). The L and C may be calculated from the formulae given below [9].



Figure 1. (a) Dumbbell shaped DGS, and (b) DGS Equivalent Circuit.

Copyright © 2011 SciRes.

$$\mathrm{L} = \frac{1}{4\pi^2 f_0^2 C} \quad (1)$$

$$\mathrm{C} = \frac{f_c}{2Z_0} \times \frac{1}{2\pi (f_0^2 - f_c^2)} \quad (2)$$

When this DGS is applied to the antenna, the equivalent inductive part due to the DGS increases and produces equivalently the high effective dielectric constant, thereby decreasing the resonant frequency when the DGS is incorporated in the ground plane of a micro strip antenna.

3. Antenna Design with DGS

In this section, the design approach and the performance of the basic antenna and the antenna with DGS is described. At the outset, the single patch antenna was designed and simulated using the CST Microwave studio [10], for the operating frequency at 5.0 GHz. Then another patch of the same size was added in the opposite side of the ground plane and fed in the same way as the first one. The configuration seems as two patch antennas having a common ground plane working at the same frequency. Next the feed lines were combined for the antenna for single feed design. For this purpose the antenna feed lines W_f = 0.934 mm with d_f = 1.5 mm were designed of 100 ohm and for matching to the 50 ohm transmission line (W_p = 3.86 mm) a quarter wave length transformer (W_t = 2 mm) was used to give proper matching (**Figure 2**).

The cross-sectional view of the single fed back to back combined proximity coupled antenna is shown in the **Figure 2(a)**. The layouts of matching networks only are emphasized in this **Figure 2(b)** for convenience. It is observed that the antenna designed in this configuration gives the bandwidth of 137 MHz whereas single antenna gives a bandwidth of 67 MHz. This is due to the fact that as the antenna height increases the quality factor decreases and the bandwidth increases. This becomes a multilayer antenna with more height and higher bandwidth as compared to the single patch antenna.

The simple transmission line model was used for the antenna size calculation. The dielectric constant was taken as 3.38 with the loss tangent 0.0025 and of 1.524 mm thickness. The patch lengths L_p and widths W_p are 15 mm and 19 mm respectively. The feed line has been inserted inside the dielectric at a height equal to the half of the height (h = 3.048 mm) of the antenna on either side. The dumbbell shaped DGS with dimensions L_g = W_g = 8.6 mm and g = 0.76 mm was created in the ground plane of the antenna as shown in the **Figure 2(c)**. A small slot was also created for making the antenna with single feed. The two feed lines were connected with a metal strip which goes through the small slot in the ground plane. The fabricated antenna is shown in **Figure 2(d)**.



Figure 2. (a) Cross-sectional view of antenna configuration, (b) Feeding Network, (c) Top-View of the antenna, (d) Fabricated Antenna.

4. Results and Discussion

At first the antenna without the DGS in the common ground was simulated and was found to resonate at 5 GHz with 137 MHz Bandwidth.

Then the structure was simulated with the dumbbell shaped DGS. Before reaching to the final size of the DGS, a parametric study was done by varying L_g, W_g and g of the DGS. As shown in **Figure 3**, with the increase in the value of L_g, the resonant frequency of the antenna is decreasing. Infect, increase in the length of the DGS head gives increasing inductance which in turn decreases the resonant frequency of the antenna.

At this point the increment in the (g) was not possible due to the accuracy in fabrication, so for this reason the other dimension (g) was kept constant for the requirement of the desired frequency (2 GHz). The size of the DGS single square head for the antenna to resonate at 2 GHz (UHF Band) was found to be 8.6 mm × 8.6 mm. The return loss (S11 [dB]) plot of the structure with and without DGS is shown in **Figure 4(a)**. **Figure 4(b)** shows the measured S11 parameter using the HP 8720 B network analyzer. The marker's position near to peak shows the resonance frequency 2.08 GHz with return loss of -13 dB. The result shows good agreement with the simulation results. The measured -10 dB bandwidth is about 60 MHz. The maximum size reduction achieved is about 60%.



Figure 3. S11 Vs. Frequency response by varying DGS length (Lg).



(a)



(b)

Figure 4. Antenna Return Loss (a) simulated (b) measured.



Figure 5. Antenna radiation pattern (measured and simulated) at 2 GHz Frequency.

The measured and simulated power patterns of the antenna are shown in **Figure 5**. It can be observed that the E-plane radiation pattern is similar to the pattern for a dipole antenna. Measurement errors are mainly due to the spurious radiation created by the feeding end and the improper coupling of the elements. However the gain measured experimentally for the proposed antennas with DGS is about -6.9 dB and -7.8 dB (where simulated gain with DGS is 3.8 dB and 5.7 dB is for the antenna without DGS, for both the planes) in both the E and H plane respectively, which is consistent with the size reduction of the antenna.

5. Conclusion

Microstrip patch antenna size reduction with DGS is carried out in this work. A dumbbell shaped DGS in the common ground plane of a back to back microstrip structure was found to give a size reduction of about 60% and shifts the resonance frequency from 5 GHz to 2 GHz, with 60 MHz bandwidth facilitating the antenna, to be used for UHF band applications.

REFERENCES

[1] R. Garg, P. Bhartia, I. Bahl and A. Ittipiboon, "Microstrip Antenna Design Handbook," Artech House, London, 1995.

[2] P. Salon, M. Keskilammi and M. Kivikoski, "Single Feed Dual Band Planer Inverted-F Antenna with U-Shaped Slot," *IEEE Transactions on Antenna and Propagation*, Vol. 48, No. 8, 2000, pp. 1262-1264. doi:10.1109/8.884498

[3] D.Nashhat, H. Elsadek and H. Ghali, "Dual-Band Reduced Size PIFA Antenna with U-Slot for Bluetooth and WLAN Applications," *Proceedings of IEEE Antennas Propagation International Symposium*, Columbus, Vol. 2, 22-27 June 2003, pp. 962-965. doi. 10.1109/APS.2003.1219395

[4] H. Liu, X. Sun and J. Mao, "Harmonic Suppression with Photonic Bandgap and Defected Ground Structure for a Microstrip Patch Antenna," *IEEE Microwave and Wireless Component Letters*, Vol. 15, No. 2, February 2005, pp. 55-56. doi:10.1109/LMWC.2004.842809

[5] D. Guha, M. Biswas and Y. M. M. Antar, "Microstrip Patch Antenna with Defected Ground Structure for Cross Polarization Suppression," *IEEE Antenna and Wireless Propagation Letter*, Vol. 4, No. 1, 2005, pp. 455-458. doi:10.1109/LAWP.2005.860211

[6] M. Salehi, A. Motevasselian, A. Tavakoli and T. Heidari, "Mutual Coupling Reduction of Microstrip Antenna using Defected Ground Structure," *IEEE Singapore International Conference on Communication System*, Singapore, 2006, pp. 1-5. doi:10.1109/ICCS.2006.301375

[7] J. Guterman, Y. R. Samii, A. A. Moreira and C. Peixeiro, "Quasi-Omni Directional Dual-band Back-to-Back E-shaped Patch Antenna for Laptop Applications," *Electronics Letters*, Vol. 42, No. 15, 2006, pp. 845-847. doi:10.1049/el:20061799

[8] H. Iwasaki, "A Back-to-Back Rectangular-Patch Antenna Fed by a CPW," *IEEE Transactions on Antenna Propagation*, Vol. 46, No. 10, October 1998, pp. 1527-1530. doi:10.1109/8.725285

[9] D. Ahn, J. S. Park, C. S. Kim, J. Kim, Y. Qian and T. Itoh, "A Design of the Low-Pass Filter Using The Novel Micro strip Defected Ground Structure," *IEEE Transactions on Microwave Theory and Technology*, Vol. 49, No. 1, 2001, pp. 86-91. doi:10.1109/22.899965

[10] EM Simulation Software CST Studio Suite™, v9.

Copyright © 2011 SciRes.

Journal of Electromagnetic Analysis and Applications, 2012, 4, 362-366
http://dx.doi.org/10.4236/jemaa.2012.49051 Published Online September 2012 (http://www.SciRP.org/journal/jemaa)

Vehicular Radio Scanner Using Phased Array Antenna for Dedicated Short Range Communication Service

Tapas Mondal[1], **Priyanka Shishodiya**[1], **Rowdra Ghatak**[2], **Sekhar Ranjan Bhadra Chaudhuri**[3]

[1]Department of Electronics & Communication Engineering, Dr. B. C. Roy Engineering College, Durgapur, India; [2]Microwave and Antenna Research Laboratory, Department of Electronics and Communication Engineering, National Institute of Technology Durgapur, Durgapur, India; [3]Department of Electronics & Telecommunication Engineering, Bengal Engineering and Science University, Shibpur, India.
Email: tapas2k@gmail.com

Received July 10th, 2012; revised August 11th, 2012; accepted August 21st, 2012

ABSTRACT

Now a day's accidents are very common due to increased population of vehicle. In order to ensure safety measures in the vehicle this paper has proposed some methodologies regarding careful driving by automatically scanning and analyzing the blind spot area of an intelligent mobile vehicle. A vehicular antenna with minimum perturbation is proposed to be fitted on the vehicle and collect information of the concern area which would ensure visibility of the operator *i.e.* masked or integrated within the car body. This paper has dealt with the design of Tchebyscheff polynomial based prototype planar microstrip phased array antenna and also redesigned the same when implemented in the body of the car being considered as an electromagnetically large element. Both the design has been experimentally verified with the measurement. The simulated and the measured results in both the cases are found to be in good agreement. More than 11 dB gain was observed at perfectly 30° angles from its broad side direction as desired for blind spot detection with minimum amount of electromagnetic interference inside the car.

Keywords: Intelligent Transportation System; Microstrip Phased Array Antenna; Tchebyscheff Polynomial; Electromagnetic Interference

1. Introduction

Intelligent Transport System (ITS) ensures mobility comfort and safety in transportation system. It also absorbs the hazards due to environmental impact. With the progress of the information processing technology, control systems to minimize accidents for the roadways have also been advanced hence one approach to improve the traffic safety is found and that is automatic collection of data by scanning the blind spot area of the vehicle [1] as shown in **Figure 1**. Many methods were proposed to detect the blind spot area but all of them had certain limitations. Devices like dynamic angling side view mirror [2], side view camera model [3], and shadow or edge features detector [4] were used for detecting blind spot area but their performance was affected during bad weather, fog or mist. Also we know that the mechanical systems, response time is more and the system is prone to wear and tear.

A radio frequency method has been proposed in this paper to scan the blind spot zone efficiently. Four rectangular microstrip antennas (RMSA) are arranged in linear configuration with optimal spacing between the patch elements to construct the phased array radar. A corporate feed network is used to feed the patch element unequally and a progressive phase shifter is designed with 108° delay elements to tilt the main beam in the desired direction and then the total unit is simulated and experimented after placing it on the car body which is electromagnetically a large element. The antenna works in the Dedicated Short-Range Communication Service (DSRCS) frequency band [5]. The design of the microstrip phased array antenna is discussed in Section 2 and after that to place the antenna; the design of the entire car is given in Section 3. Results and discussion are portrayed in Section 4 along with conclusion in Section 5.

2. Design of Microstrip Phased Array Antenna

The microstrip phased array antenna is designed for Dedicated Short Range Communication Service at 5.88 GHz with dielectric constant of 2.32 and substrate thickness of 0.785 mm. Firstly the dimension of the rectangular patch is computed as 16.322 mm by 19.8 mm using the method outlined in [6]. With computed inset feed length of 3.8 mm and for the above dimensions of the rectangular patch the return loss is found to be –8.09 dB

Copyright © 2012 SciRes.



Figure 1. Surrounding regions of a vehicle.

with (30.1 + j26.7) ohm impedance at the feed position. The RMSA is simulated and optimized using Ansoft HFSS^{TM}. After optimization the final length is found to be 16.4363 mm with inset feed length of 4.8225 mm keeping the width of the patch unchanged as shown in **Figure 2**.

By considering the above designed patch element, a four element linear array is realized and powered by Tchebyscheff current distribution. The spacing between the elements is kept considering the desired maximum scan angle in order to eliminate the grating lobes within the visible space of the phased array antenna. To optimize the performance of the antenna in respect of its side lobe level (SLL), mutual coupling and gain of the antenna array, the spacing between the elements is studied parametrically [7]. The results of the said study are tabulated in **Table 1**.

After optimization it is found that the optimum spacing between the elements is 0.6 λ_0 while considering, the main lobe to side lobe ratio below 20 dB, optimum mutual coupling and overall gain.

From **Figure 1**, it is observed that the beam of the antenna array is required to be tilted by an angle 30° away from the broad side direction. In view of the above a progressive phase shifter of –108° is designed with the help of 11.16 mm feed line length. The actual line length is considered as mτ, where m = 0, 1, 2, 3.

To enhance the gain by maintaining the beam width and main lobe to side lobe ratio, the antenna elements are excited by Dolph Chebyshev current distribution. The array consist of four elements, thus third order Tchebyscheff polynomial is calculated. Hence the polynomial is solved and relative current ratio is computed as 1:1.7795:1.7795:1. Both equal and unequal power dividers are designed along with the progressive phase shifter.

For equal power division, a 3 dB equal power divider is designed whose vertical arm is of 50 Ω line and two horizontal quarter-wavelength branch-lines are of 70.71 Ω is used [8]. It is shown in **Figure 3(a)**.

Table 1. Effect on mutual coupling and gain due to variation in spacing (d) between the elements.

d with respect to guided wavelength	d with respect to operating wavelength	Mutual coupling (dB)	Gain (dBi)
0.6 λ_g	0.41 λ_0	>10	7.6
0.7 λ_g	0.48 λ_0	>13	9.9412
0.8 λ_g	0.55 λ_0	>20	10.647
0.9 λ_g	0.6 λ_0	>22	10.919



Figure 2. Photograph of the rectangular microstrip antenna element.

To get the unequal current distribution, both the horizontal arm of the microstrip unequal power divider should be of different resistance and it is calculated as 46.368 Ω and 82.49 Ω. The structure is shown in **Figure 3(b)**.

Generally for practical design purpose the gap between the corporate feed networks is taken small but the value of the gap less than 0.11 λ_0 disturbs the frequency response of overall antenna array. The effects of the feed network on the side-lobes are significant in the E-plane pattern. The influence on the H-plane is less important due to the orthogonality of the drive current and the symmetry of all the other currents in this cut [9]. By maintaining the SLL and the surface wave loss, the gaps are taken as 0.11 λ_0 as portrayed in **Figure 4**.

3. Placement of Antenna on the Vehicle

In order to compute the electromagnetic effect of the body of the car on the antenna performance, the entire structure of the car is designed in Ansoft HFSS^{TM}. The complete structure of the car consist of hood, roof, trunk, left and right side doors, left and right side quarter panel for front and rear side which are made up of conducting material but the bumpers and wheels are assigned by layered impedance due to their hard rubber and polyester materials as shown in **Figure 5**.

After going through the typical requirement for scanning the blind spot, the antenna is placed just beside the side view mirror. The following problems in the designed are addressed while simulating the effect of the radiation


(a)

(b)

Figure 3. (a) Photograph of the equal microstrip power divider; (b) Photograph of the unequal microstrip power divider.



Figure 4. Photograph of the antenna array with corporate feed network.



Figure 5. The entire structure of the car along with the antenna array.

characteristics of the antenna after placing it on the vehicle:

1) Spans a large computational domain compared to the wavelength;

2) Requires a fine grid resolution to resolve the detailed antenna structure;

3) Contains largely non-conformal PEC and dielectric structures.

4. Results and Discussion

For obtaining the scattering parameter characteristics, the microstrip antenna has been simulated over the frequency bandwidth ranging from 5.5 GHz to 6.5 GHz and two different circumstances is observed. The first experiments involve the design, simulation and measurement after fabrication of an individual element and then the array with the same without involving the effect of the car. Both of them should used for optimized performance.

The scattering parameter is measured by Agilent Technology Vector Network Analyzer model no. N5320A (10 MHz - 20 GHz) and the radiation pattern is measured by Hittite HMC-T2100 synthesized signal generator (10 MHz - 20 GHz) and Krytar 9000 B power meter (10 MHz - 40 GHz) with 9530 B power sensor (10 MHz - 20 GHz) as shown in **Figure 6**. From **Figure 7**, it is found


(a)

(b)

Figure 6. (a) Experimental set-up to measure the radiation pattern of the antenna array; (b) Experimental set-up to measure the radiation pattern of the antenna array after placing it on the car.



(a)

(b)

Figure 7. (a) Return loss a single patch before and after optimization; (b) Gain of a single patch before and after optimization.

that after optimization a perfect match is obtained exactly at 5.88 GHz and gain is also improved from 6.33 dB to 7.01 dB with a very good return loss of –47 dB. The current distribution and the radiation pattern of a single RMSA is portrayed in **Figure 8**.

A parametric study of the return loss of antenna array with different spacing between the elements of the corporate feed network is done and is compared in **Figure 9**. The results of the computational model of the entire antenna array with feed network were compared with the measured data and a good agreement is observed in **Figure 10**.

After getting the satisfactory results, next the same array antenna is experimented again with considering the electromagnetic effect of the car. In order to test the antenna array in association with the vehicle, a numerical model of the car is created using Ansoft HFSS$^{\text{TM}}$ and the simulated data is compared with the measured in **Figure 11**. **Figure 12** graphically represents the 3D radiation pattern of the antenna array in presence of the computational model of the vehicle. From **Figure 13**, it is clear that the inside electric field strength is not more than 15 Volt per meter which is very less compare to the standard



Figure 8. Current distribution and the radiation pattern of the rectangular microstrip antenna.



Figure 9. Parametric study of return loss of the antenna array with different spacing between the elements of corporate feed network.



(a)

(b)

Figure 10. (a) Return loss of the antenna array; (b) Radiation pattern of the antenna array.



Figure 11. Normalized radiation pattern of the antenna array after placing it on the body of the car.


Y
dB(GainTotal)
1.2275e+001
8.8929e+000
5.5103e+000
2.1277e+000
-1.2549e+000
-4.6375e+000
-8.0201e+000
-1.1403e+001
-1.4785e+001
-1.8168e+001
-2.1551e+001
-2.4933e+001
-2.8316e+001
-3.1698e+001
-3.5081e+001
-3.8463e+001
-4.1846e+001
0
45
90 (in)

Figure 12. 3D radiation pattern of the antenna array after placing it on a vehicle body.


E Field[V_per_m
5.0000e+003
2.5897e+003
1.3413e+003
6.9475e+002
3.5984e+002
1.8638e+002
9.6535e+001
5.0000e+001
2.5897e+001
1.3413e+001
6.9475e+000
3.5984e+000
1.8638e+000
9.6535e-001
5.0000e-001
Z
Y
0
50
100 (in)

Figure 13. Inside electric field interference of the array after placing it on a vehicle body.

electromagnetic hazards.

5. Conclusion

A Tchebyscheff polynomial based microstrip phased array antenna is designed to detect the blind spot area of the intelligent mobile vehicle. The design is further simulated in Ansoft HFSS^{TM} after placing the antenna on the body of the car and the results are observed. The result of the computational model of the entire antenna array is compared with the measured data before and after placing the said antenna array on the body of the car and found to be in good agreement. An overall 11 dB gain is obtained while measuring in the desired direction with minimum amount of electromagnetic interference inside the car.

REFERENCES

[1] M. Griffiths, "Intelligent Transport System," Postnote: Parliamentary Office of Science and Technology, London, 2009. www.parliament.uk/paliamentary_offices/post/

[2] J. Kuwana and M. Itoh, "Dynamic Angling Side-View Mirror for Supporting Recognition of a Vehicle in the Blind Spot," *International Conference on Control*, *Automation and Systems*, *ICCAS*, Seoul, 14-17 October 2008, pp. 2913-2918.

[3] S. Jeong, S.-W. Ban and M. H. Lee, "Autonomous Detector Using Saliency Map Model and Modified Mean-Shift Tracking for a Blind Spot Monitor in a Car," *Seventh International Conference on Machine Learning and Applications*, San Diego, 11-13 December 2008, pp. 253-258. doi:10.1109/ICMLA.2008.129

[4] B.-F. Wu, C.-C. Kao, Y.-F. Li and M.-Y. Tsai, "A Real-Time Embedded Blind Spot Safety Assistance System," *International Journal of Vehicular Technology*, Vol. 2012, 2012, pp. 1-15. doi:10.1155/2012/506235

[5] A. Tang and A. Yip, "Collision Avoidance Timing Analysis of DSRC-Based Vehicles," *Accident Analysis & Prevention*, Vol. 42, No. 1, 2010, pp. 182-195. doi:10.1016/j.aap.2009.07.019

[6] T. Mondal, J. S. Roy and S. R. Bhadra Chaudhuri, "Phased Array Antenna Design for Intelligent Transport Systems," *IEEE International Workshop on Antenna Technology*: *Small Antennas and Novel Metamaterial* (i*WAT*), Santa Monica, 2-4 March 2009, pp. 1-4.

[7] T. Mondal, R. Ghatak and S. R. B. Chaudhuri, "Design and Analysis of a 5.88GHz Microstrip Phased Array Antenna for Intelligent Transport Systems," *IEEE International Sumposium on Antennas and Propagation and CNC*/*USNC*/*URSI Radio Science Meeting*, Toronto, 11-17 July 2010, pp. 1-4.

[8] H. J. Visser, "Array and Phased Array Antenna Basics," John Wiley & Sons Ltd., Chichester, 2005. doi:10.1002/0470871199

[9] E. Levine, G. Malamud, S. Shtrikman and D. Treves, "A Study of Microstrip Array Antennas with the Feed Network," *IEEE Transactions on Antennas and Propagation*, Vol. 31, No. 4, 1989, pp. 426-434. doi:10.1109/8.24162

Copyright © 2012 SciRes.

Wireless Engineering and Technology, 2012, 3, 175-180
http://dx.doi.org/10.4236/wet.2012.33025 Published Online July 2012 (http://www.SciRP.org/journal/wet)

Plus Shape Slotted Fractal Antenna for Wireless Applications

S. Jagadeesha[1], R. M. Vani[2], P. V. Hunagund[3]

[1]S.D.M. Institute of Technology, Ujire Mangalore, India; [2]University Science Instrumentation Center, Gulbarga University, Gulbarga, India; [3]Department of PG Studies and Research in Applied Electronics, Gulbarga University, Gulbarga, India.
Email: Jagadeesh.sd69@gmail.com, vanirm12@rediffmail.com, prbhakar_hunagund@yahoomail.com

Received April 28th, 2012; revised May 26th, 2012; accepted June 3rd, 2012

ABSTRACT

Fractal antennas are characterized by space filling and self-similarity properties which results in considerable size reduction and multiband operation as compared to conventional microstrip antenna. This paper outlines a multiband antenna design based on fractal concepts. Fractal antennas show multiband behavior due to self-similarity in their structure. The plus shaped fractal antenna has been designed on a substrate of dielectric constant $€_r = 4.4$ and thickness 1.6 mm. The proposed antenna is characterized by a compact size and it is microstrip feed fractal patch of order 1/3. It is observed that the antenna is radiating at multiple resonant frequencies. The resonant frequency is reduced from 2.2 GHz to 900 MHz after I & II iterations respectively. Thus considerable size reduction of 81.77% & overall bandwidth of 12.92% are achieved. The proposed antenna is simulated using the method of moment based commercial software (IE3D) and it is found that simulated results are in good agreement with the experimental results.

Keywords: Fractal Antenna; Multi Frequency; Size Reduction; Wireless Application; Plus Shape Antenna; Slotted Antenna

1. Introduction

In the study of antennas, fractal antenna theory is a relatively new area. The emergence of antennas with fractal geometries has given an answer to two of the main limitations started by Werner (1999) of the classical antennas, which are single band performance and dependence between size and operating frequency. The term "fractal" means broken or irregular fragments. It was originally coined by Mandelbrot (1983) to describe a family of complex shapes that possess an inherent self-similarity or self-affinity in their geometrical structure. Jaggered (1990) defined fractal electrodynamics as an area in which fractal geometry was combined with electromagnetic theory for the purpose of investigating a new class of radiation, propagation and scattering problems. One of the most promising area fractal electrodynamics researches is in its application to antenna theory and design. There are varieties of approaches that have been developed over the years, which can be utilized to archive one or more of these design objectives. The development of fractal geometry came largely from an in depth study of the pattern nature, with the advance of wireless communication system and their increasing importance wide band and low profile antennas are in great demand for both commercial and military applications [1]. A fractal is a rough or fragmented geometric shape that can be split into parts, each of which is a reduced-size copy of the whole and this property is called self-similarity. Fractal [2] geometries are composite designs that repeat themselves or their statistical characteristics and are thus "self-similar" fractal geometry finds a variety of applications in engineering. Fractal geometry is space filling contours of regular or irregular shapes [3-6], and is super imposed of too much iteration and they describe the self-similar property of fractal geometry [7]. Fractals are a class of shapes which have not characteristic size. Each fractal is composed of multiple iterations of a single elementary shape the iteration can continue infinitely, thus forming a shape within a finite boundary but of infinite length or area. Fractal has the following features 1) It has a finite structure at arbitrarily small scales; 2) It is too irregular to be easily described in traditional Euclidean geometric; 3) It is self-similar; 4) Simple and recursive [8]. Modern telecommunication systems require the antenna with wider bandwidth and smaller dimension than conventionally possible. This has initiated antenna research in various directions, are of which is by using fractal shaped antenna elements. In recent years several fractal geometries have been introduced for antenna application with varying degree of success in improving antenna

Copyright © 2012 SciRes.

characteristics. Some of these geometries have been particularly useful in reducing the size of the antenna, while other designs aim at incorporating multiband characteristics. These are low profile antennas with moderate gain and can be made operative at multiple frequency bands and hence are multifunctional [9]. In our present work we focus on generation of multifrequency which yields increases the bandwidth and size reduction of antenna. A plus shape patch is taken as a base shape and in first iteration four other plus shape patches of the order of 1/3 of base shape are placed touching the base shape. Similarly second iterations are taken by further placing plus shaped patches at even reduced scales. It is found that as the iteration number and iteration factor increases, the resonance frequencies become lower than those of the zero iteration, which represents a conventional plus shape patch.

2. Design Consideration

The base shape of the plus shaped slotted fractal antenna is designed on a dielectric substrate having a relative dielectric constant €$_r$ = 4.4 and thickness 1.6 mm as shown in **Figure 1**. This is the reference antenna or base shape antenna. Further this base shape antenna is modified by inserting horizontal slots on both sides with respect to center of patch as shown in **Figure 2** and it is named as antenna1. The length of the slot Ls is varied on either side of the edge as 5 mm, 10 mm, 15 mm, 20 mm, 21.175 mm, 21.675 mm and the frequency variation has been studied. The optimum length obtained is Ls = 21.675 mm *i.e.*, the distance between slots q = 2 mm is considered for further design.

The first iteration patch is designed with four plus shapes of order (1/3) of base shape are placed touching the base shape as shown in **Figure 3** and it is named as antenna 2 and same procedure is repeated for second iteration. This antenna is as shown in **Figure 4** and it is named as antenna 3. For each iteration plus shapes of the order of $(1/3)^n$ of base shape are taken, where n is the number of iterations. The dimension of first iteration can be calculated as

e = (1/3) a & g = (1/3) c also f = (1/3) b & h = (1/3) d.
i = (1/3) e & k = (1/3) g also j = (1/3) f & L = (1/3) h

So with optimized design the dimensions obtained are a = 45.3 mm, b = 15.1 mm, c = 35.4 mm, d = 11.8 mm. The length of the slot is Ls = 21.675 mm and width of the slot Ws *i.e.* r = 2 mm. The dimension of the ground plan is 55 mm × 85 mm. A 50 ohm SMA connector is used to feed the antenna by using microstrip feed technique. Optimized microstripline with following dimension, m = 0.5 mm, n = 18.55 mm, o = 3.05 mm, p = 18.4 mm. The suitable feed location is obtained through optimization process by using the IE3D software. The fabricated photographic view of all proposed antennas is shown from **Figures 5(a)-(e)**.



Figure 1. Geometry of base antenna.



Figure 2. Geometry of antenna 1.

3. Results and Discussion

The characteristic of the fractal antenna with slot and with iterations has been studied by using IE3D software. Also the results have been verified practically with by using Vector Network Analyzer model Rohde and schewarz, German make ZVK model No.8651.



Figure 3. Geometry of base antenna 2.



Figure 4. Geometry of antenna 3.

The modified base shape antenna with slots as been optimized by varying slot length Ls. The variation of Ls with resonant frequency of the antenna is shown in **Table 1** and same is presented in graphical form in **Figure 6**. From the tabular results it is found that by increasing slot length Ls on both sides from the edge of the patch, resonant frequency decreases. The lowest possible resonant frequency 1.27 GHz is obtained for Ls = 21.675 mm (*i.e.*, distance between the slots q = 2 mm) & this is taken as optimized length of the slot for further iteration.

The results of all proposed antennas are shown in **Table 2**. The simulated and measured return loss characteristics of proposed antennas are shown from **Figures 7(a)-(d)**.

From the results it is clear that the resonant frequency of the antenna 1 *i.e*., modified base antenna with slot is fr = 1.27 GHz which is lower compared to the base antenna without slot (fr = 2.199 GHz). So the size reduction obtained is 66.85%. The antenna 2 *i.e*. the modified antenna with slots and first iteration gives multiple bands with lower frequency of 0.99 GHz. The size reduction obtained for antenna 2 is 79.88%. Further antenna 3 *i.e*., with slot and second iteration gives multiple bands with



(a) (b) (c) (d) (e)

Figure 5. (a) Photograph of top view of base antenna; (b) Photograph of bottom view of base antenna; (c) Photograph of antenna 1; (d) Photograph of antenna 2; (e) Photograph of antenna 3.

Table 1. Variation of slot length v/s resonant frequency.

Slot length (Ls) variation in mm	Resonating frequency (GHz)
0	2.22
5	2.197
10	2.155
15	1.93
20	1.436
12.175	1.34
21.675	1.27



Figure 6. Variation of resonant frequency v/s slot length.

lower resonant frequency of 0.90 GHz. The size reduction obtained for antenna 3 is 81.77% which is more compared to all other proposed antennas.

Further the bandwidths of proposed antennas have been studied through simulation and measurements and the results are shown in **Table 2**. From the results it is clear that the bandwidths of modified antenna with slot, first & second iteration are more compared to base antenna. The measured bandwidth of antenna 1 is 106 MHz (4.895%), antenna 2 is 190 MHz (11.93%) and antenna 3 is 215 MHz (12.92%). The radiation patterns of all proposed antennas are studied and all are giving broadside radiation. Splitting of beam *i.e.* dip is found in **Figure 8(a)** of simulated radiation pattern of base shape at 2.19 GHz. In **Figure 8(b)** splitting of beams merged into broadside pattern at 0.91 GHz at second iterations this results into broadside radiation pattern.

4. Conclusion

This paper presents a new plus shape slotted fractal antenna with first and second iterations. The antenna.3 *i.e.*, slotted fractal antenna with second iteration gives size reduction of 81.77% and band width of 12.92% with broad side radiation pattern. So from the results we conclude that the modified base antenna with slots of second iterations gives a good size reduction and enhanced band width compared to that of modified base antenna with

Table 2. Results of proposed antennas.

Prototype antenna	Resonant frequency fr (GHz)		Return loss (db)		Bandwidth (MHz)		Overall bandwidth (MHz)	
	Sim	Pract	Sim	Pract	Sim	Pract	Sim	Pract
Base antenna	f1 – 2.19	f1 ± 2.19	–19	–24	53	53	79	71
	f2 – 3.42	f2 ± 2.46	–14	–15	26	18		
Antennal with q = 2 mm	f1 ± 1.19	f1 ± 1.27	15.8	–12.8	20	18		
	f2 ± 2.52	f2 ± 2.48	18.4	–20.1	113	44	133	106
		f3 ± 2.56		–18.7		44		
Antennal 2 with q = 2 mm (1st itr)	f1 ± 0.96	f1 ± 0.99	16.7	–14.5	22	80		
	f2 ± 2.9	f2 ± 2.97	–14	–26.9	44	50	136	190
	f3 ± 3.08	f3 ± 3.17	21.5	–21	70	60		
Antennal 3 with q = 2 mm (2nd itr)	f1 ± 0.91	f1 ± 0.990	15.2	–14.2	11	87		
	f2 ± 3.07	f2 ± 2.976	19.4	–17.6	70	50	81	215
		f3 ± 3.168		–18.9		78		

Copyright © 2012 SciRes.



(a) (b)

(c) (d)

Figure 7. (a) Return loss characteristic of antenna 1 with q = 2 mm; (b) Return loss characteristic of base antenna 2 with q = 2 mm; (c) Return loss characteristic of antenna 2 with q = 2 mm; (d) Return loss characteristic of antenna 3 with q = 2 mm.



(a) (b)

Figure 8. (a) Simulated radiation pattern of base shape at 2.19 GHz; (b) Simulated radiation pattern at 0.91 GHz for second iteration.

slot of first iteration. These antennas may find application in wireless communication systems.

REFERENCES

[1] K. Sing, V. Grewal and R. Saxena, "Fractal Antennas: A Novel Miniaturization Technique for Wireless Communications," *International Journal of Recent Trends in Engineering*, Vol. 2, No. 5, 2009, pp. 172-176.

[2] B. Mandelbrot, "Fractal: Form, Chance and Dimension," W. H. Freeman and Company, San Francisco, 1997.

[3] H. O. Peitgzen, H. Jurgens and D. Sanpe, "Chaos and Fractals," New Frontiers in Science, Springer-Verlag, New York, 1992.

[4] C. Punete, J. Romen, R. Pous, X. Garkia and F. Beitez, "Fractal Multiband Antenna Based on the Serpinski Gasket," *Electronics Letters*, Vol. 32, No. 1, 1996, pp. 1-2. doi:10.1049/el:19960033

[5] J. P. Gianvittorio and Y. Rahmat-Sami, "Fractal Antennas: Novel Antenna: A Novel Antenna Miniaturization Technique and Applications," *IEEE Antenna and Propagation Magazine*, Vol. 44, No. 1, 2002, pp. 20-36. doi:10.1109/74.997888

[6] D. H. Werner and S. Ganguly "An Overview of Fractal Antenna Engineering Research," *IEEE Antenna and Propagation Magazine*, Vol. 45, No. 1, 2003, pp. 38-57.

[7] G. Srivatsun, S. S. Rani and G. S. Krishnan, "A Self-Similar Fractal Cantor Antennas for MICS Based Wireless Applications," *Wireless Engineering Technology*, Vol. 2, No. 2, 2011, pp. 107-111. doi:10.4236/wet.2011.22015

[8] W. Shalan and K. Pahwa, "Multiband Microstrip Rectangular Fractal Antenna for Wireless Applications," *International Journal of Electronics Engineering*, Vol. 3, No. 1, 2011, pp. 103-106.

[9] F. J. Jibrael and M. H. Hammed, "A New Multiband Patch Microstrip Plusses Fractal Antenna for Wireless Applications," *ARPN Journal of Engineering and Applied Sciences*, Vol. 5, No. 8, 2010, pp. 155-158.

Copyright © 2012 SciRes.

PUBLISHED BY

INTECH
open science | open minds

World's largest Science,
Technology & Medicine
Open Access book publisher

3,250+
OPEN ACCESS BOOKS

106,000+
INTERNATIONAL
AUTHORS AND EDITORS

112+ MILLION
DOWNLOADS

BOOKS
DELIVERED TO
151 COUNTRIES

AUTHORS AMONG
TOP 1%
MOST CITED SCIENTIST

12.2%
AUTHORS AND EDITORS
FROM TOP 500 UNIVERSITIES

Selection of our books indexed in the
Book Citation Index in Web of Science™
Core Collection (BKCI)

WEB OF SCIENCE™

Chapter from the book *Advances in Satellite Communications*

Downloaded from: http://www.intechopen.com/books/advances-in-satellite-communications

Interested in publishing with InTechOpen?
Contact us at book.department@intechopen.com

7

New Antenna Array Architectures for Satellite Communications

Miguel A. Salas Natera et al.*
Universidad Politécnica de Madrid,
Spain

1. Introduction

Ground stations which integrate the control segment of a satellite mission have as a common feature, the use of large reflector antennas for space communication. Apart from many advantages, large dishes pose a number of impairments regarding their mechanical complexity, low flexibility, and high operation and maintenance costs. hus, reflector antennas are expensive and require the installation of a complex mechanical system to track only one satellite at the same time reducing the efficiency of the segment (Torre et al., 2006).
With the increase of new satellite launches, as well as new satellites and constellation of low earth orbit (LEO), medium earth orbit (MEO), and geostationary earth orbit (GEO), the data download capacity will be saturated for some satellite communication systems and applications. Thus, the feasibility of other antenna technologies must be evaluated to improve the performance of traditional earth stations to serve as the gateway for satellite tracking, telemetry and command (TT&C) operation, payload and payload message or data routing (Tomasic et al., 2002). One alternative is the use of antenna arrays with smaller radiating elements combined with signal processing and beamforming (Godara, 1997).
Main advantages of antenna arrays over large reflectors are the higher flexibility, lower production and maintenance cost, modularity and a more efficient use of the spectrum. Moreover, multi-mission stations can be designed to track different satellites simultaneously by dividing the array in sub-arrays with simultaneous beamforming processes. However, some issues must be considered during the design and implementation of a ground station antenna array: first of all, the architecture (geometry, number of antenna elements) and the beamforming process (optimization criteria, algorithm) must be selected according to the specifications of the system: gain requirements, interference cancellation capabilities, reference signal, complexity, etc. During implementation, deviations will appear as compared to the design due to the manufacturing process: sensor location deviation and sensor gain and phase errors (Martínez & Salas, 2010). In an antenna array, the computation of a close approach of the direction of arrival (DoA) and the correct performance of the beamformer depends on the calibration procedure implemented.

---

* Andrés García-Aguilar, Jonathan Mora-Cuevas, José-Manuel Fernández González, Pablo Padilla de la Torre, Javier García-Gasco Trujillo, Ramón Martínez Rodríguez-Osorio, Manuel Sierra Pérez, Leandro de Haro Ariet and Manuel Sierra Castañer.
Universidad Politécnica de Madrid, Spain

This chapter is organized with the following sections. Section 2, introduces the relationship between applications and antenna design architectures. Section 3, introduces the new antenna array architectures for satellite communication including motivation and explains experimental examples. Section 4, explains adaptive antenna array and receiver architectures for adaptive antennas systems considering the beamforming with synchronization algorithms. Finally, Section 5 explains the A3TB concept.

2. Applications and antenna design architectures

In recent effort, new antenna array architectures have been under analysis and development. In (Tomasic et al., 2002) a highly effective, multi-function, low cost spherical phased array antenna design that provides hemispherical coverage is analyzed. This kind of novel architecture design, as the geodesic dome phased array antenna (GDPAA) presented in (Tomasic et al., 2002) preserves all the advantages of spherical phased array antennas while the fabrication is based on well-developed, easily manufacturable, and affordable planar array technology (Liu et al., 2006; Tomasic, 1998). This antenna architecture consists of a number of planar phased sub-arrays arranged in an icosahedral geodesic dome configuration.

In contrast to the about 10 *m* diameters dome of the GDPAA, there is the geodesic dome array (GEODA) (Sierra et al., 2007) with 5 *m* diameters dome. This antenna, presented in Fig. 1, has two geometrical structure parts. The first one, is based on a cylinder conformed by 30 triangular planar active arrays, and the second is a half dodecahedron geodesic dome conformed by 30 triangular planar active arrays. The GEODA is specified in a first version for satellite tracking at 1.7 GHz, including multi-mission and multi-beam scenarios (Martínez & Salas, 2010). Subsequently, the system of the GEODA has been upgraded also for transmission (Arias et al., 2010).



a b c

Fig. 1. a) The GEODA, b) The active sub-array demonstration, and c) The 45 elements planar active sub-array.

The antenna arrays technology in the user segment for satellite communications will substitute reflectors providing a more compact and easy to install antenna system, which is an interesting solution e.g. for satellite on the move (SOTM) system. There is a great diversity of solutions for fixed and mobile satellite communication systems including a large number of applications. Inmarsat broadband global area network (Inmarsat-BGAN) (Franchi et al., 2000) is the most representative example among mobile satellite systems (MSS), which gives land, maritime and aeronautical high speed voice and data services with global coverage using GEO satellites at L-band.

MSS services are divided into two groups, those that offer a regional coverage usually with GEO satellites, and those which offer a global coverage based on LEO or MEO satellite constellations. Depending on the coverage, there are some examples for MSS with regional coverage as the mobile satellite system (MSAT) in EEUU, Canada and South America, Optus in Australia, N-Star in Japan, Asia cellular satellite (ACeS) in Asia or Thuraya in the Middle East and in the North of Africa. While for MSS of global coverage there are some examples as Iridium, ICO Global Communications, Globalstar, Teledesic, etc. (Evans, 2009; Wu, 1994). Most of the MSSs work at L and S band, new applications on satellite to mobile terminal links work at X, Ku and Ka band, and satellite to base station connections work at L, S and C band. A number of applications is broad and lead terrestrial telecommunications market to offer a wider coverage: high speed voice and data (internet access, SMS, VoIP), digital video broadcasting by satellite 2 (DVB-S2) and digital video broadcasting satellite services to handhelds (DVB-SH), global position system (GPS) and Galileo, security, control and machinery monitoring on ships and aircrafts, teleeducation or telemedicine.

These modern satellite communications systems require new antenna solutions for base stations, aeronautical applications or personal communications services (PCS) on-the-move (Fujimoto & James, 2001). Within these applications, antenna array systems are potentially the best choice due to, as discussed above, its capability to perform electronically steering or beamforming, increase the antenna gain, and conform over curved or multifaceted surfaces the radiating elements. Portable antennas for PCS must be easy to install and mechanically robust, besides compact and lightweight (García et al., 2010) as the antenna array presented in Fig. 4.a. The design of antenna systems to provide high data rates for reliable PCS boarded on ships is not so strict in term of the geometrical requirements because it does not have space limitations (Geissler et al., 2010). However, in the case of land or airborne vehicles, geometrical and mechanical constraints are more severe. Antennas for terrestrial vehicles must be low profile, and for airborne vehicles aerodynamic shapes must be considered (Baggen et al., 2007; Vaccaro et al., 2010). Moreover, for the civil market conformal antenna arrays (Schippers, 2008; Kanno et al., 1996), or multi-surface arrays (Khalifa & Vaughan, 2007) are suitable choices to deal with the system aesthetic partiality.

Technological challenges have been faced during the implementation of satellite communication systems in the last decades. The design of a Test-Bed flexible and modular for testing or debugging beamforming algorithms and receiver architectures is an invaluable contribution in the educational, research and development area on satellite communication systems. The adaptive antenna array Test-Bed (A3TB) concept is based on the use of antenna arrays with beamforming capability to receive signals from LEO satellites (Salas et al., 2008). The scope of the A3TB is to probe the concept of antenna arrays applied to ground stations instead of reflectors for different applications, such as telemetry data downloading. It is also a good chance for Universities and Research Centers aiming to have their own ground station sited in their installations.

The A3TB ground station relies on the use of an antenna array to smartly combine the received signals from the satellite thanks to the implementation based on software defined radio (SDR) technology. The advantages of the SDR implementation is that A3TB architecture can be used to process any received signal from LEO satellites in the band imposed by the radio frequency (RF) circuits. Moreover, most of the processing is performed in software, so that appropriate routines can be used to process any received signal. The A3TB can be used to analyze the feasibility of different receivers and beamformer algorithms, regarding the capability to switch the receiver architecture in terms of the synchronizer algorithm configuration (Salas et al., 2007).

The current version has been developed to track The National Oceanic and Atmospheric Administration (NOAA) satellites in the very high frequency (VHF) band, in particular, the automated picture transmission (APT) channel (Salas et al., 2008). Previous versions of A3TB dealt with low rate picture transmission (LRPT) signals from the meteorological operational satellite-A (MetOp-A), where a complete receiver with beamforming and synchronization stages has been implemented (Salas et al., 2007; Martínez et al., 2007).

3. Antenna arrays for satellite communications

Satellite applications require compactness, lightweight and low cost antenna systems to be mounted on a terrestrial vehicle, an aircraft or a ship, or as a portable man-pack or a handset, and to be competitive against ground systems. Its major advantage is the possibility of getting a wider or even a global coverage. For such purposes, antenna arrays offer the technology to get a directive system whose steering direction can be electronically and/or mechanically controlled. However, planar arrays usually cannot steer more than 60^o-70^o from the normal direction of the antenna (Mailloux, 2005). Thus, when a wider angular coverage is required conformal arrays are an appropriate option (Josefsson & Persson, 2006). Arrays can approximate conformal shapes, such as spheres or cylinders, using several planar arrays, simplifying fabrication of active components (Sierra et al., 2007).

Since the low cost and low weight specifications are of importance, micro-strip antennas are mostly used, due to its capacity to be printed over a dielectric substrate with photolithography techniques. Low cost and low permittivity substrates are usually used such as FR4 or PTFE with different quantities of glass or ceramic impurities. For more demanding applications, ceramics, like alumina or high/low temperature co-fired ceramics (HTCC/LTTC) allow the use of smaller components thanks to its high permittivity, and give robustness against mechanical stresses and high temperatures.

3.1 Geodesic antenna array for satellite tracking in ground station

The aim of using a single antenna for tracking many satellites at the same time avoiding mechanical movements as well as its inexpensive cost make these antennas an alternative to be considered (Salas et al., 2008). Multi-beam ability and interference rejection are facilitated thanks to the electronic control system of such antennas that improves the versatility of the ground stations.

The GEODA is a conformal adaptive antenna array designed for MetOp satellite communications with specifications shown in Table 1. This antenna was conceived to receive signals in single circular polarization (Montesinos et al., 2009). Subsequently, in recent efforts the system has been upgraded also for transmission and double circular polarization (Arias et al., 2010). Hence, operating at 1.7 GHz with double circular polarization it can communicate with several LEO satellites at once in Downlink and Uplink. Current structure is the result of a comprehensive study that valued the ability to cover a given spatial range considering conformal shape surface and a given beamwidth (Montesinos et al., 2009). As Fig. 1 shows, GEODA structure consists of a hemispherical dome placed on a cylinder of 1.5 meters height. Both cylinder and dome are conformed by 30 similar triangular planar arrays (panels). Each panel consists of 15 sub-arrays of 3 elements (cells). The radiating element consists of 2 stacked circular patches with their own

RF circuits. The principal patch is fed in quadrature in 2 points separated 90° in order to obtain circular polarization. The upper coupled patch is used in the aim of improving the bandwidth.

Each panel is able to work itself as an antenna since they have a complete receiver that drives the 1.7 GHz signal to an analog to digital converter (ADC). In order to adapt the signal power to the ADC, it is mandatory to implement a complete intermediate frequency (IF) receiver consisting of heterodyne receiver with an automatic gain control block. Hence, each triangular array has active pointing direction control and leads the signal to a digital receiver through an RF conversion and filtering process. To follow the signal from the satellite, the main beam direction has to be able to sweep an angle of 60°. In this way, it is needed a phase shift in the feeding currents of the single radiating element. Previous calculations have demonstrated that 6 steps of 60 degrees are needed to achieve the required sweeping angle. An adaptive digital system allows the adequate signal combination from several triangular antennas. The control system is explained in (Salas et al., 2010).

Parameter	Specification	Parameter	Specification
Frequency range [GHz] **Tx:** **Rx:**	 1.65 to 1.75 1.65 to 1.75	**Isolation between Tx and Rx [dB]**	>20
Polarization	Dual circular for Tx and Rx bands	**VSWR**	1.2:1
G/T [dB/K] **For elevation >30°** **For elevation 5°**	 3 6	**SLL [dB]**	-11
EIRP [dBW]	36	**Size [m]**	1.5x1.5x3
3dB beamwidth [deg.]	5	**Accuracy steering [deg.]**	±1.4
Maximum gain [dBi]	29	**Coverage [deg.]:** **Azimuth** **Elevation**	 360° >5°
Efficiency [%]	50		

Table 1. Main specifications for GEODA antenna.

3.1.1 Cell radiation pattern

Based on the study presented in (Sierra et al., 2007), the single radiating element is a double stacked circular patch that works at 1.7 GHz with 100 MHz bandwidth. In order to obtain circular polarization, the lower patch, which has 90 mm diameter, is fed by 2 coaxial cables in quadrature. Both coaxial cables connect the patch with a hybrid coupler to transmit and receive signals with both, right and left, circular polarizations. The upper patch is a circular plate with 78.8 mm diameter, and it is coupled to the lower patch increasing the bandwidth by overlapping both resonant frequencies tuning the substrate thickness and the patch diameter size. Fig. 2.a shows the radiating element scheme and main features of the layer structure are specified in (Montesinos et al., 2009).

A cell sub-array of 3 radiating elements shown in Fig. 2.b is considered the basic module to build the planar triangular arrays. The whole cell fulfills radiation requirements since it has a good polar to crosspolar ratio and a very low axial ratio. Likewise, as it is presented in Fig. 2.c, the radiation pattern shows symmetry and low side lobes for full azimuth.



a b c

Fig. 2. a) Assembly of the single radiating element, b) Cell scheme, and c) Cell radiation pattern.

3.1.2 Transmission and Reception (T/R) module and cell distribution

Different T/R module configurations have been considered, providing either single or double polarization (Arias et al., 2010). T/R module allows amplifying and controlling the phase shift between signals, received and transmitted, providing an adaptive beam and steering direction controller in the whole working pointing range. As Fig. 3 shows, the design implemented contains a hybrid coupler, enabling double circular polarization; a double pole double throw (DPDT) switch, selecting polarization associated with transmission and reception way; 2 low noise amplifiers (LNAs), which amplify the signal received or transmitted; a single pole double throw (SPDT) switch, choosing transmission or reception way; and phase shifters, introducing multiples of 22.5º relative shift phases to form the desired beam. These surface mount devices have been chosen in order to reduce space and simplify the design.

Signals transmitted/received by the 3 T/R modules placed in a cell are divided/combined thanks to a divider/combiner circuit composed of 3 hybrid couplers that leads the signal to a general T/R module where signal is amplified. Due to transmission and reception duality, 2 SPDT switches are used to select the amplification way. Furthermore, each T/R module has associated a -25dB directional coupler that is used to test T/R modules in the transmission mode. Additionally, reception mode is tested by measuring signal in the divider/combiner circuit. A single pole 6 throw (SP6T) switch selects the path that is tested.


2 bits
2 bits
4 bits
-25 dB coupler
LH
RH
Hybrid coupler
DPDT
Tx LNA
Rx LNA
SPDT
Phase shifter
Patch
Patch
Patch
Divider/Combiner Circuit
T/R General Module 2bits
Test Circuit 2bits

Fig. 3. Cell sub-array and RF circuit.

3.1.3 Control system

The control system has two main parts (Salas et al., 2010), the hardware structure and the control software. The two level hardware structure has the lowest possible number of elements, making the control simpler in contrast to the previous in (Salas et al., 2010). Finally, an inter-integrated circuit (I2C) expander is used to govern T/R modules individually, and one more cover cell needs (LNA of call and test). A multipoint serial standard RS-485 is used to connect the computer with the panels.

3.2 Portable antenna for personal satellite services

New fix and mobile satellite systems (Evans, 2000) require antenna systems which can be portable, low profile and low weight. Planar antennas are perfect candidates to fulfill these specifications. Usually slots (Sierra-Castañer et al., 2005) and printed elements (García et al., 2010) are most used as radiating elements.

3.2.1 Antenna system structure

In this subsection it is introduced a printed antenna for personal satellite communications at X band, in Fig. 4. Table 2 shows main antenna characteristics.

Parameter	Specification	Parameter	Specification
Frequency range[GHz] **Tx:** **Rx:**	7.9 to 8.4 7.25 to 7.75	**Efficiency [%]**	50
Polarization	Dual circular polarization for Tx and Rx bands	**Isolation between Tx and Rx [dB]**	>17
G/T [dB/K]	7	**VSWR**	1.4:1
EIRP [dBW]	32	**SLL [dB]**	-11
3dB beamwidth [deg.]	5	**Size [m]**	40x40x2.5
Maximum gain [dBi]	25	**Weight [Kg]**	2

Table 2. Portable antenna specifications.

This is a planar, compact, modular, low loss and dual circular polarized antenna, for Tx and Rx bands, simultaneously. It is made up by a square planar array of 16x16 double stacked micro-strip patches, fed by two coaxial probes. A hybrid circuit allows the dual circular polarization (Garg et al., 2001). Elements are divided in 16 sub-arrays excited by a global power distribution network of very low losses, minimizing the losses due to the feeding network and maximizing the antenna efficiency. In order to reduce side lobe levels (SLL), the signal distribution decreases from the centre to the antenna edges, keeping symmetry with respect to the main antenna axes. The antenna works at X band from 7.25 up to 8.4 GHz with a 14.7% relative bandwidth for a 1.4:1 VSWR and a maximum gain of 25 dBi.

3.2.2 Sub-array configuration

The sub-array configuration can be seen in Fig. 4.a. It makes possible to separate the fabrication of these sub-arrays from the global distribution network, simplifying the corporative network and getting a modular structure suitable for a serial fabrication process. Each sub-array is a unique multilayer board, where PTFE-Glass substrate of very low losses has been used as base material. The power distribution network is connected to each sub-array through (SMP-type) coaxial connectors.



a b c

Fig. 4. a) Dual polarized portable printed antenna for satellite communication at X band, b) Sub-array perspective view, and c) Side view and multilayer scheme.

Fig. 5.a and Fig. 5.b show the sub-array unit cell. In order to obtain better polarization purity, each element is rotated 90º and excited by a 90º phase-shifted signal. Moreover, in Fig. 5.c is showed a miniaturized branch-line coupler (BLC) of three branches working as a wide band hybrid circuit (García et al., 2010; Tang & Chen, 2007).



a b c

Fig. 5. Unit cell test board, a) Unit cell test board 2x2 stacked patches, b) Micro-strip feeding network, and c) Miniaturized BLC Prototype.

A conventional configuration takes up an area of 13.3 cm^2 which is big compared to the radiating element and the sub-array subsystem size. Therefore, a miniaturization of the BLC is needed using the equivalence between a λ/4 transmission line and a line with an open-ended shunt stub. An area reduction about 35% is achieved and the hybrid circuit behaves like a conventional BLC. In Fig. 6.b and Fig. 6.c measurement results for the BLC in Fig. 5.c are shown compared with simulations.

Fig. 7 depicts some sub-array measurements. The copular to crosspolar ratio is better than 25 dB and axial ratio is under 0.9 dB in the whole bandwidth.



a b

Fig. 6. Miniaturized BLC, Measured and simulated S-parameters in: a) Amplitude, and b) Phase.



a b

Fig. 7. 4x4 patch sub-array measurements, a) Radiation pattern at 7.75 GHz, and c) Axial ratio for right-handed circular polarization.

3.2.3 Low losses power distribution network

The global feeding network presented in Fig. 8.a is a protected strip-line, where foam sheets of high thickness are used to get low losses. Such a kind of feeding network allows keeping a trade-off between the simplicity of exciting the radiating elements using printed circuits and the loss reduction when the distribution network is separated in a designed structure to have low losses. Losses in the structure are around 0.6 dB/m which yields to 0.3 dB of losses in the line. Two global inputs/outputs using SMA-type connectors, one for each polarization, excite the strip-line networks.

Vertical transitions have to be treated carefully and must be protected to avoid undesired higher order mode excitation. Thereby, it has been design a short-ended pseudo-waveguide, adding some extra losses about 0.3 dB, for two kinds of vertical transitions, as can be seen in Fig. 8.b and Fig. 8.c.



a b c

Fig. 8. a) Protected strip-line global corporative network for one polarization, b) Transitions from strip-line to SMA-type connector, and c) Transitions from strip-line to SMP-type connector.

3.2.4 Antenna performance

Fig. 9 depicts measured radiation pattern at 7.75 GHz, gain and axial ratio for the antenna system. It is shown a maximum gain of 25 dBi in the lower band and about 22 dBi in the upper band, and a SLL around 11 dB. Copolar to crosspolar ratio is better than 30 dB and axial ratio is under 0.7 dB. Total losses are about 4 dB in the working band.



a b

Fig. 9. Antenna measurements results, a) Radiation pattern at 7.75 GHz, and c) Axial ratio for right-handed circular polarization.

3.3 Electronically steerable antennas for mobile and fixed portable systems

At present, two types of electric steerable antenna systems can be used to access the satellite communication services (Bialkwoski et al., 1996). These are: fixed position portable systems and mobile systems such as those installed on a land vehicle. The fixed portable antenna system is relatively easy to be accomplished by the antenna designer. The design involves standard procedures that concern the operational bandwidth, polarization and moderate gain (García et al., 2010). One drawback of the fixed position portable system is that they require the user to be stationary with respect to the ground. This inconvenience can be overcome with the mobile antenna system. A mobile user complicates the scenario since the ground mobile antenna needs to track the satellite (Alonso et al., 1996). The design of such a system is more challenging as new features associated with the mobility of the system have to be incorporated (Fernández et al., 2009). The requirement leads to a narrow beamwidth, for which satellite tracking is required as the vehicle moves around. Electronically steerable antennas enable the development of reconfigurable antennas for satellite applications.

3.3.1 Steerable antenna for fixed position portable systems

This antenna is a fixed satellite communication system with high gain at X band, consisting of an antenna array that integrates 32 2x2 sub-array modules in the complete antenna, as shown in Fig. 10.a. It is a planar and dual circular polarized antenna for Tx and Rx bands simultaneously. It is made up by a planar array of double stacked circular micro-strip patches, fed by 2 coaxial probes to generate circular polarization. A hybrid circuit allows the dual circular polarization as shown in Fig. 10.b.



a b c

Fig. 10. Active multi-beam antenna, a) Top view, b) Feeding network of the complete antenna, and c) Beamforming network of the 2x2 sub-array module

The antenna has the same design parameters, structure and configuration as the antenna explained in Section 3.2 but with a different feeding network, as previously shown. In this case, the beamforming network requires changes in the feeding phase in the 2x2 sub-arrays, which can be achieved by phase shifters (ϕ) associated with different sub-arrays (Fig. 10.c). All these sub-arrays are connected to a feeding network, in Fig. 10.b, formed by transmission lines with low losses in strip-line. General specifications of the steerable antenna for fixed position portable systems are provided in Table 3.(a).

3.3.2 Automatic steerable antenna for mobile systems

A broadband circularly polarized antenna for satellite communication in X band is presented in Fig. 11 and specified in Table 3.(b). The arrangement features and compactness are required for highly integrated antenna arrays. It is desired to get a low-gain antenna for mobile satellite communications with low speed of transmission. In this system, the antennas are formed by 5 planar 4x4 arrays of antennas, which form a truncated pyramid with a pointing capability in a wide angular range, so that among the 5 planar arrays the complete antenna can cover any of the relative positions between the mobile system and the satellite in a practical way. The scheme of the active antenna can be seen in Fig. 11.

As it can be observed in Fig. 11.a, the antenna terminal is a multi-beam printed antenna shaped as a trunk pyramid capable of directing a main beam in the direction of the satellite. The antenna steering system consists of a multi-beam feeding structure with switches that lets combine the feed of each 4x4 arrays to form multiple beams. Switching the different 4x4 arrays, it is achieved different multiple beams and the variation of the steering direction.

The complete antenna consists of a Tx and Rx module that works independently in the 2 frequency bands.

The antenna has multiple beams covering the entire space to capture the satellite signal without moving the antenna. The signal detected in each of the beams is connected to a switch, which, by comparison, is chosen the most appropriate 4x4 array. The steering direction of the 4x4 array can vary between a range of directions that covers a cone angle range of 90º. To obtain the required gain and cover the indicated range, it is required around 15 beams, which can be obtained by integrating the beamforming networks with switches in the design as presented in (Fernández et al., 2009).



a b

Fig. 11. Complete antenna structure, a) Radiating element of the 4x4 arrays, and b) Prototype top view.

The radiating element of the 4x4 array is one 2 crossed dipoles with a stacked circular patch as shown in Fig. 11.a and Fig. 11.b. In Fig. 12 the cross-section of the radiating element structure is presented.


Stacked circular patch
2 crossed dipoles
Balun
PTFE substrate NELTEC NY (ε_r = 2.17)
PTFE substrate NELTEC NY (ε_r = 2.17)
Foam (ε_r = 1.07)
Foam (ε_r = 1.07)
PTFE substrate NELTEC NY (ε_r = 2.17)
Ground plane
Foam (ε_r = 1.07)
Ground plane
Microstrip feeding network

Fig. 12. Cross-section scheme of the radiating element.

The key element of the radiating element feeding structure (Fig. 14.b) is a resonant micro-strip feed ring that has been implemented, as well as a micro-strip 90º branch-line coupler to obtain the desired right hand or left hand circular polarizations (RHCP or LHCP) which ensures adequate port coupling isolation. The S-parameters in amplitude and phase of the micro-strip feeding structure are shown in Fig. 13.a and Fig. 13.b.

Fig. 14.a depicts the S-parameters of the radiating element with the micro-strip feed structure and they fulfill the specification, in Table 3.(b). In Fig. 14.c, the radiation pattern of the radiating element at 7.825 GHz is shown and in Fig. 14.d the radiation pattern of the 4x4 arrays is presented. It is shown a maximum gain of 19.4 dBi at the center frequency band (7.825 GHz). Copolar (CP) to crosspolar (XP) ratio is better than 17 dB and the axial ratio is under -3dB.



a b

Fig. 13. Micro-strip feeding structure, a) Amplitude of S-parameters, and b) Phase of S-parameters.



a b

c d

Fig. 14. a) S-parameters, b) Resonant ring + 90° branch-line coupler, c) radiation pattern at 7.825 GHz, and d) 4x4 array radiation pattern.

Parameter	Value (a)	Value (b)	Comments
Freq. range [GHz] Rx **Tx**	7.25 - 7.75 7.9 - 8.4	7.25 - 7.75 7.9 - 8.4	Microwave applications.
G/T (in Rx) [dB/K]	7	7	
EIRP (in Tx) [dBW]	32	32	
Beamwidth at -3dB [deg.]	4	20	
Polarization	circular	circular	In both, reception and transmission.
Gain [dBi]	>28	>15	
Axial ratio [dB]	< 1	<3	**(a)** Between ±50°. **(b)** Between ±45°.
VSWR	< 1.4:1 (-15.6 dB)	< 1.5:1 (-13.9 dB)	
Isolation between ports [dB]	< -17	< -15	
Radiation pattern [deg.]	±35	±90	Steering direction tilt.
Dimensions [cm]	40x40x4	20x20x15	

Table 3. (a) General specifications of the steerable antenna for fixed position portable systems , and (b) General features of the automatic steerable antenna for mobile systems.

3.4 Transmit-array-type lens antenna for terrestrial and on board receivers

Technology in satellite communications has revealed an increasing interest in novel smart antenna designs. Phased-array based designs are basic in electronically reconfigurable devices for satellite applications, which are more and more demanding. The strict requirements in terms of architecture, shape and robustness are important constraints for the development of planar lens-type devices. Regarding the usage and location, lens-type devices are useful for either terrestrial or on board receivers, in vehicular technology. Some clear examples are satellite communications for aircrafts preserving the fuselage aerodynamics or for some other kind of vehicles such as trains, etc.

3.4.1 Introduction to lens-type structures

In a general view, in lens-type a particular signal is received (in our case, an electromagnetic wave with specific features in terms of frequency, wave-front, etc.), it is processed (either complex signal processing techniques or only phase correction tasks can be considered in this interface), and finally, the processed signal is retransmitted.

Regarding the lens configuration, a transmit-array lens consists of three well distinguished interfaces: the first one for signal reception, one interface for signal processing, and the last one for processed signal re-radiation, as depicted in Fig. 15.



a b

Fig. 15. a) Multi-user scheme with different receivers and transmitters, and b) Adaptive scheme with DoA determination.

These structures are intimately related to reflect-array ones, where the reception and transmission interfaces are turned to be the same interface, with a reflection-type behavior (Encinar & Zornoza, 2001). Although in an equal output phase configuration a transmit-array device behavior would be similar to the one obtained with a reflect-array, the transmit-array offers the advantage of removing the feed blockage.

In a transmission scheme, depending on the transmitter position regarding the lens, a different steering direction is achieved and a different user is pointed. In the case of reception, the situation is the same: the user position configures the direction of arrival, which determines the receiver position around the lens (Padilla et al., 2010a). In adaptive schemes, applying the proper processing algorithm to the signal received in the different receivers around the lens, it is possible to develop an adaptive steering vector, in terms of the desired direction of arrival.

3.4.2 Transmit-array lens architecture and design

Lens-type structures provide two fundamental advantages. First, phase error correction due to spherical wave front coming from the feeding antenna. Fig. 16.a shows this effect. Second, new radiation patterns configuration. Fig. 16.b depicts this fact.



a b

Fig. 16. a) Phase error correction, and b) Radiation pattern reconfiguration.

3.4.3 Electronically reconfigurable devices for active transmit-array lenses

The addition of reconfigurability on transmit-array devices requires the possibility of controlling the phase response of the transmitted signal at each cell of the lens. Electronic control of phase signal may be added in two different ways: First, electronic tuning of the radiating element phase response (Padilla et al., 2010a): Modifications in the radiating element circuital behavior lead to changes in phase response (arg[S_{21}]). Fig. 17 shows an electronically reconfigurable microwave patch antenna for this purpose, along with the equivalent circuit and prototype outcomes in terms of phase.

Second, electronic tuning of phase shifters in transmission lines (Padilla et al., 2010c): Modifications in the phase response of the phase shifters lead to corresponding changes in phase response. Some options are applied for these devices, such as hybrid couplers, etc. Fig. 18 shows a microwave phase shifter prototype for this purpose, along with the working scheme and its outcomes in phase.



a b c

Fig. 17. Electronically reconfigurable antenna, a) Patch antenna prototypes, b) Equivalent circuit, and c) Phase behavior in frequency.



a b c

Fig. 18. Electronically reconfigurable phase shifter, a) Phase shifter prototype, b) Working scheme, and c) Phase behavior in frequency.

3.4.4 Electronically reconfigurable active transmit-array prototype

One electronically reconfigurable prototype is presented in Fig. 19 and detailed in this section. The prototype design implies the use of microwave phase shifters according to the design specified in section 3.4.3. This transmit-array lens prototype operates at 12 GHz. Main specifications are provided in Table 4.

Parameter	Value	Comments
Frequency range [GHz]	12 ± 0.5	Microwave applications.
Polarization	Linear	In both, reception and transmission.
Directivity [dBi]	>21	
Axial ratio [dB]	< 1	Between ±50° elevation.
S_{11} [dB]	< -20	
Radiation pattern [deg.]	±30	Steering direction tilt, for both H and V planes.
Feeding antenna [mm]	120	Corrugated horn linearly polarized
Phase shifters [deg.]	360	Full phase range variation.
Transmit-array elements	36	6x6 array topology.
Separation between elements	$0.7\lambda_0$	Related to the wavelength

Table 4. Main features of the electronically reconfigurable transmit-array prototype.


a b c

Fig. 19. Transmit-array core, a) Transmit-array prototype, b) Distribution networks, and c) Phase shifter integration.

The electronically controllable steering capabilities are tested and assured for a range of ± 30°in each main axis. An example of radiation pattern is provided in Fig. 20, for 9° tilt in one of the main axes.



a b c

Fig. 20. a) Complete transmit-array with feeder and control circuits; and transmit-array measurement results for 9° tilt in one axis, b) H plane, and c) 3D plot.

4. Adaptive antenna array

Adaptive antennas can be described as systems usually based on three main parts: the antenna array, the receiver architecture and the beamforming scheme. Thus, adaptive antennas have those advantages owing to those three main parts. The system capabilities increase as complexity and development cost do. Furthermore, since signal processing is the basement of the adaptive antenna concept it is important to analyze the design challenges in terms of hardware architecture and components such as processors and embedded systems.

The antenna array provides the capability of performing the antenna pattern meeting the environment requirement under study. Besides, receiver architectures have some interesting advantages depending on the implemented receiver arraying technique such as signal to noise ratio (SNR) and bit error rate (BER) performance enhancement. Furthermore, symbol synchronization and carrier recovery can be used increasing the receiver complexity but providing higher performances. Finally, beamforming schemes use multiple antennas in order to maximize the strength of the signals being sent and received while eliminating, or at least reducing, interference as discussed in Section 4.3.

Adaptive antenna arrays are often called Smart Antennas because they have some key benefits over traditional antennas, by adjusting traffic patterns, space diversity or using multiple access techniques. The main four key benefits are: First, enhanced coverage through range extension by increasing the gain and steering capability of the ground station antenna; Second, enhanced signal quality through multi-target capability and reduction of interferences; finally, adaptive antennas improve the data download capacity in the ground segment of satellite communication by increasing the coverage range (Martínez et al., 2007).

4.1 Design and architecture based on software defined radio

For design there is the well known waterfall life cyclic model (Royce, 1970) that can be used to manage main aspects of the design of architectures. Thus, some tasks must be fulfilled subsequently as follow in Fig. 21.a.

Fig. 21.b shows the design schemes resulting of the requirement analysis stage corresponding software and hardware system specifications. In the depicted scheme, there are some system components such as the radiating element and RF circuits that are often designed under iterative prototyping model.


Analysis of System requirements
system software and hardware specification
Design
components, software design tools and hardware platform
Implementation and components test
Implementatio n of system components
Integration and system test
integrated Adaptive Antenna Array
Adaptive Antenna Array
Radiating element
RF Circuits
Connectors
Antenna Array
Symbol Sync.
Filter Chain
Receiver Architecture
Beamformer
Signal combiner.
Beamforming Algorithms

a b

Fig. 21. a) Water life cyclic model of the adaptive antenna array design, and b) Simplified design scheme of adaptive antenna arrays.

Regarding the hardware implementation, tables presented in (Martínez et al., 2007) show the hardware resource consumption in the field programmable gate array (FPGA) Virtex-4 for the least mean squared (LMS) beamforming algorithm with full spectrum combining (FSC) receiver architecture and SIMPLE beamforming algorithm with symbol combining (SC) receiver architecture. Both scheme designs have an antenna array of 2 elements. The algorithm based on correlation requires less hardware. The main difference can be appreciated in the amount of digital signal processing oriented component (DSP48) resources, typically used for filtering applications (Martínez et al., 2007).

4.2 Receiver architectures based on algorithms type

Several receiver architectures can be implemented, and they are frequently based on the type of the beamforming algorithm used. When training signals are available in the transmitted frame, a time-based reference algorithm can be used. However, this solution is only valid when the earth station is capable of demodulating the received training sequence. Other algorithms used in deep space communications are based on signal correlation and they avoid performing the demodulating process. This kind of algorithms are blind techniques that do not require any additional signal demodulation before applying some beamforming technique and work better in low SNR conditions than time-based algorithms. Several receiver architectures can be implemented exploiting the processing capabilities of the SDR, such as FPGA, application-specific integrated circuits (ASICS), and digital signal processing (DSPs). The design of the receiver architecture fundamentally depends on the selection of beamforming algorithms. An example of beamforming technique is the LMS algorithm whose estimation of coefficients or weights requires a temporal reference and is implemented through SC receiver architecture (Fig. 22.a). In the other hand, the SIMPLE algorithm (Rogstad, 1997) constitutes a beamforming technique that is implemented using FSC receiver architecture (Fig. 22.b) in order to perform the calculation of weights.



Fig. 22. Comparison of receiver architectures. a) Symbol Combining (SC), and b) Full Spectrum Combining (FSC).

The SC architecture can be divided into two more sub-classes which work on a phase-recovery basis. The complex symbol combining (CSC) recovers the phase information with regard to a reference element using feed-forward and feedback algorithms. One of the advantages of this scheme is that the rate of data sent to the combining module has a rate slightly higher than the symbol rate. For most applications, the symbol rate is relatively low and is a multiple of the data rate. In this kind of schemes, there is an important cost consideration in real-time applications and the requirements of instrumental phase stability are very severe (Rogstad et al., 2003). Other type of SC architecture is the stream symbol combining (SSC). In this kind of scheme, data are sent to the combining module at a rate equal to the symbol rate. The symbol rate depends on the coding scheme and for most applications is relatively modest. Also, the requirements of instrumental phase stability are no severe, as in the case of CSC scheme. The disadvantage of the SSC is the additional hardware required for each antenna.

Furthermore, there are the baseband combining (BC) and carrier arraying (CA) architectures discussed in (Rogstad et al., 2003). In BC architectures the signal from each antenna is carrier locked and combining in baseband for further demodulation and synchronization. In effect, the carrier signal from the spacecraft is used as a phase reference so that locking to the carrier eliminates the radio-frequency phase differences between antennas imposed by the propagation medium. Besides, in CA architectures, one individual carrier-tracking loop is implemented on each array element. Then, the elements branches are coupled in order to increase the carrier-to-noise ratio (CNR), but losses of radio channel are far compensated (Rogstad et al., 2003).

In general, the selection of the beamforming algorithms is determined by the following aspects: Hardware and computational resources; Speed of convergence and residual error of adaptive algorithms; Calibration requirements and auto-compensation ability; and system signal-transmission characteristics.

4.3 Beamforming techniques for satellite tracking

Some satellites transmit useful information inside its frames for synchronization and tracking purposes. The gathering of satellite data requires the tracking operation along its earth orbit. To accomplish this goal with adaptive array architectures, some beamforming techniques should be implemented. Fig. 23 illustrates a simple example of a narrowband linear adaptive beamformer system.



Fig. 23. Adaptive antenna system.

A linear beamformer combines signals according to some weights w_i, to produce a desired radiation pattern. The mathematical expression of a linear beamformer at the array output in vector notation can be expressed as $y = w^H x$, where x is the received signal vector to be combined, w are the weights computed by the beamforming algorithm and ^{H} denotes transposition and conjugate of $(\cdot)$.

In adaptive antennas design, weights are dynamically calculated with a certain algorithm in order to optimize some signal parameter like signal to interference-plus-noise ratio (SINR), SNR, or BER. An extended variety of algorithms exist in the literature for beamforming purpose and the most appropriated selection is done depending on the signal characteristics of the received signal.

4.3.1 Blind techniques

Blind beamformers make use of an inherent property of the received signal, such as the ciclo-stationarity of the constant modulus. In the latter, the algorithm eliminates the fluctuation of the signal amplitude and computes the weights to minimize the effect produced by those variations. The algorithms that make use of these methods are denoted as Constant Modulus Algorithms (CMA) (Biedka, 2001).

CMA algorithms present an important disadvantage: as the phase information is not considered, the constellation of quadrature phase shift keying (QPSK) signals commonly used in satellite communications appears rotated after beamforming, which imposes the need of an additional phase recovery subsystem in the array output.

4.3.2 Temporal-reference algorithms

Algorithms based on a temporal reference require a known reference included in the frame of the signal, such as training sequences, unique word (UW) or pilot bits. Thus, these schemes are normally used for digital signals. The aim of these beamformers is the minimization of the energy of an error signal integrated by interferences and noise. In order to reduce the order of the problem, the weight calculation is usually done iteratively.

The most popular adaptive filters are the LMS and Recursive Least Squares (RLS) algorithms (Haykin, 2002). Briefly, the main differences lie in the method to calculate and the final convergence behavior: while LMS has a linear complexity order with the number of antennas in the array, RLS makes use of matrix operation, so that the complexity order is quadratic, but the convergence is faster.

An interesting alternative to the LMS is the Normalized LMS (NLMS), which normalizes the adaptive step to avoid variation during the convergence process. The counterpart is the more intensive processing requirements to calculate signal power and normalization operation.

4.3.3 Correlation-based algorithm

In contrast to beamformers based on temporal reference, schemes based on signal correlation do not require the demodulation of any signal. These techniques are the most popular to extract the spatial information for beamforming, and we have focused on the use of the SIMPLE algorithm (Rogstad, 1997). This algorithm has been used by the Deep Space Network (DSN) of National Aeronautics and Space Administration (NASA) to combine the signals received from spatial probes in radio telescopes located in different sites around the Earth surface. The main disadvantage of correlation based schemes is the lack of ability to cancel interference signals.

4.4 Performance comparison

Some simulation comparisons between spatial and blind algorithms are presented to show benefits and drawbacks. Four algorithms have been selected with a 4-element uniform linear array (ULA). The spatial algorithms simulated are post-beamformer interference canceller – orthogonal interference beamformer (PIC-OIB) (Godara, 2004) and minimum power distortionless response (MPDR) (Van Trees, 2002). On the other hand, the blind algorithms are the matrix-free EIGEN and the SUMPLE (Rogstad, 1997). The convergence process is compared as a function of the input SNR as depicted in Fig. 24.

As it can be observed from the above results, spatial algorithms outperform blind ones at low SNR, and vice versa. On the other hand, with medium-low SNR and low or absence of interferences, the behavior of all algorithms is quite similar.



a b

Fig. 24. Convergence behavior of spatial versus blind algorithms in the absence of interferences with several input SNR. a) SNR = 5 dB, and b) SNR = -10 dB.

5. Experimental Test-Bed based on SDR platform

This section presents a test platform known as Adaptive Antenna Array Test-Bed - A3TB, where a comparative study of several beamforming algorithms can be performed and modularity of the architecture is a well proved advantage. The test bed is based on SDR technology and uses a novel architecture that can be used with both blind and spatial-based beamforming algorithms. The A3TB concept can be applied to a number of scenarios as the current version is independent of the signal properties. Simulation results using the A3TB with the APT channel from NOAA satellites show the performance of the concept and the feasibility of the proposed implementation.

The scope of the system development was is to prove the concept of antenna arrays applied to ground stations instead of reflectors for different applications, such as telemetry data downloading or end-user in mobile applications as discussed in the introduction section. In contrast to reflector antennas, antenna arrays offer the possibility of electronic beam-steering avoiding the use of complex mechanical parts and therefore reducing the cost of the antenna. It is also a good chance for Universities and Research Centers aiming to have their own ground station sited in their installations.

5.1 A3TB concept

The A3TB can be defined as *a software-defined radio beamformer applied to a ground station for tracking LEO satellites*. The novelty relies on the use of an antenna array to smartly combine the received signals from the satellite and its implementation based on SDR technology. The reason to use an antenna array instead of a single antenna is to electronically steer the beam in the direction of the satellite along its orbit without requiring a mechanical system for tracking. In addition to the advantages of the use of SDR technology and antenna array, it is the modularity and flexible architecture implemented in the A3TB. Fig. 25 shows the A3TB architecture where it is evident the feasibility to update or change during operation any of the main blocks. It is possible to change during operation the beamforming algorithm and to include new beamforming modules to the system. Furthermore, changes on the BENADC are possible to implement not during operation, but new receiver architecture at off-line such as those options discussed at follow.

In (Salas et al., 2007), the block diagram represents the software system implementation of the first version of the test-bed prototype and most of it is based on VHDL. Depending on the firmware, three options could be installed into the FPGA Virtex4. The option A is implemented with the signal processing on the PC, so the SIMPLE beamforming is done in the module developed in C++. The option B is implemented completely on VHDL and this option need to export the beamforming weights just to draw the array pattern diagram. Finally, in contrast to the option B, the option C is implemented for the LMS beamforming algorithm.

With the first version of the Test-Bed, the modularity on the selection of firmwares was proved switching between A, B or C receiver architectures, and an important result of the Test-Bed development is the hardware resources occupation presented in (Salas et al., 2007).

The advantage of the SDR implementation is that A3TB architecture can be used to process any received signal from a LEO satellite in the appropriate band imposed by the RF stages. Moreover, most of the processing tasks are performed on software, using appropriate routines to process any receive signal. There are 2 main schemes to implement the beamforming stage: SC and FSC [41]. Both schemes are compared in Section 4.2.

The current version of the A3TB in Fig. 25.a was updated to track NOAA satellites in the VHF band, in particular the APT channel. Previous versions of A3TB dealt with LRPT signals from MetOp-A, where a complete receiver with beamforming and synchronization stages has been implemented(Salas et al., 2007; Martínes et al., 2007).

5.2 Implementation of the A3TB

The A3TB prototype consists of 4 main parts as shown in Fig. 25.a. The first part is the antenna array, which has 4 crossed-dipole antennas as depicted in Fig. 25.b. The second part consists of RF-IF circuits which amplify and down convert to IF incoming signals. Furthermore, an automatic gain control (AGC) was implemented using two steps of variable attenuators in the IF domain.

The third part is the SDR platform which consists of the beamforming algorithms implemented on C++ and the FPGA firmware on VHDL, PC and BENADC blocks show in Fig. 25, respectively. The hardware resources occupation for this Test-Bed implementation is similar to one presented in (Martínes et al., 2007). The last part is the software from weather satellite signal to image decoder (WXtoImg) on the PC using the sound card output/input in order to get the weather satellite image.

Since the implemented architecture is FSC the demodulation is not required and the IF signal is digitized. For the signal processing hardware design the BenADC-v4 has been chosen. This solution includes a FPGA Xilinx Virtex4-SX55 with four 12-bit analog inputs at


RF/IF Circuit
BENADC
PC
Digital I/O
AGC
DDS
RF
FI
ADC
BUS PCI
Tunable Oscillator
Digital I/O
Tuning Control
Beamforming Algorithm
Weather satellite signal to image decoder
WXtoImg
PC
Sound Card loop
FM DEMOD
ADC Channel 2
External Clock Source
ADC Channel 3
ADC Channel 1
ADC Channel 4
Clock Distribution Chip
User FPGA
User LEDs
XILINX
VIRTEX-4
XC4VLX160

a b

Fig. 25. a) Block diagram of the A3TB, and b) BenADC – Virtex 4-sx55.

250 Msps (Martínes et al., 2007). Digital samples are transferred to the PC where beamforming and subsequent APT demodulation of the array output are performed using C++ routines. This implementation design offers higher flexibility for testing different beamforming schemes. Finally, demodulated APR frames are sent to the WXtoImg software to show meteorological maps.

The A3TB is controlled by the PC for simulations and field trials. The graphical user interface allows presented in (Salas et al., 2008) the user to choose the beamforming algorithm and set all the parameters of the LEO satellite for tracking such as the number of antennas of the array, distance between the elements, direction of arrival and IF frequency. The C++ routine calculates the beamforming weights and plots the synthesized array factor. Subsequently, the reception of meteorological images has real time system requirements. Thus, it is necessary a data transfer from the FPGA to the C++ module to process the samples continuously, and give APT frames to the audio output of the PC. Since, the meteorological satellites often have a low baud rate, in the case of study with NOAA satellites the data transfer is made using two buffers controlled by a thread.

It is important to mention that the A3TB with SDR architecture can evaluate different beamforming algorithms and receiver schemes. The update of A3TB for larger arrays is immediate, as the basis for algorithms is independent of the number of elements in the array. The architecture of a new ground station concept to track LEO satellites based on software defined radio and antenna arraying as Test-Bed is a well proved choice to evaluate future antenna array architectures for satellite communication and benchmark features of the proposed system. As the A3TB VHF version is based on FSC scheme, the concept can be applied to a number of satellite tracing scenarios.

6. Conclusions

The performance analysis of different beamforming algorithms is an important issue in the new generation antenna array development and research. Thus, A3TB helps to analyze beamforming algorithms paving the way for testing and debugging for posteriori use in larger arrays, such as GEODA. Results obtained in real scenarios with A3TB state, for example, that spatial reference algorithms such as MPDR should be used in the absence of interferences, whereas blind algorithms are appropriate for low SNR conditions. Finally, the A3TB can also serve to validate the performance of calibration procedures.

In future work, the A3TB will deal with the system combining of full modularity with the capability of change firmwares based on the first version design of the Test-Bed, plus the flexible architecture of the current design of the Test-Bed based on VHDL, C++ and Antenna Arraying. Furthermore, the addition of more modules to increase the number of antenna array elements is evident in next generations.

7. Acknowledgment

Authors wish to thank MICINN (Ministerio de Ciencia e Innovación) for grants and CROCANTE project (ref: TEC2008-06736/TEC), INSA (Ingeniería y servicios Aeroespaciales) and Antenas Moyano S.L., for the partial funding of this work. Simulations in this work have been done using CST Studio Suite 2011 under a cooperation agreement between Computer Simulation Technology and Universidad Politécnica de Madrid. Substrates used in prototypes were kindly given by NELCO S.A.

8. References

Torre, A.; Gonzalo, J.; Pulido, M., & Martínez Rodríguez-Osorio, R. (2006). New generation Ground Segment Architecture for LEO satellites. *57th International Astronautical Congress*, pp. 221-226. Valencia, Spain, October 2006.

Tomasic, B.; Turtle, J. & Liu, S. (2002). A Geodesic Sphere Phased Array Antenna for satellite control and communication. *XXVII General Assembly of the International Union of Radio Science,* Maastricht, August 2002.

Godara, L. C. (1997). Application of Antenna Arrays to Mobile Communication, Part II: Beamforming and Direction of Arrival Considerations. *Proc. IEEE* , vol.85, No.8, (August 1997), pp. 1195-1245.

Martínez, R. & Salas Natera, M. A. (2010). On the use of Ground Antenna Arrays for Satellite Tracking: Architecture, Beamforming, Calibration and Measurements. *61st International Astronautical Congress*, pp. 1-7. Prague, 2010.

Liu, S.; Tomasic, B.; Hwang, S. & Turtle, J. (2006). The Geodesic Dome Phased Array Antenna (GDPAA) for Satellite Operations Support. *IEEE 18th International Conference on Applied Electromagnetics and Communications*, pp. 1-1, Dubrovnik, April 2006.

Tomasic, B. (1998). Analysis and Design Trade-Offs of Candidate Phased Array Architectures for AFSCN Application. *Second AFSCN Phased Array Antenna Workshop,* Hanscom, April 1998.

Sierra Pérez, M.; Torre, A.; Masa Campos, J. L.; Ktorza, D. & Montesinos, I. (2007). GEODA: Adaptive Antenna Array for Metop Satellite Signal Reception. *4th ESA International Workshop on Tracking, Telemetry and Command System for Space Application*, pp. 1-4, Darmstadt, Germany, September 2007.

Arias Campo, M.; Montesinos Ortego, I.; Fernández Jambrina, J. & Sierra Pérez, M. (2010). T/R Module Design for GEODA Antenna. *4th European Conference on Antenna and Propagation,* pp. 115-116, Barcelona, Spain, April 2010.

Franchi, A.; Howell, A. & Sengupta, J. (2000). Broadband mobile via satellite: Inmarsat BGAN. *IEEE Seminar on the Critical Success Factors - Technology, Services and Markets*, pp. 23-30, October 2000.

Evans, J. V. (1998). Satellite systems for personal communications. *Proc. IEEE* , Vol.86, No.7, (July 1998), pp. 1325-1341.

Wu, W. W. (1994). Mobile satellite communications. *Proc. IEEE* , Vol.82, No.9, (September 1994), pp. 1431-1448.

Fujimoto, K. & James, J. (2001). *Mobile Antenna Systems Handbook.* Artech House.

Garcia Aguilar, A.; Inclán Alonso, J. M.; Vigil Herrero, L.; Fernández González, J. M. & Sierra Pérez, M. (2010). Printed antenna for satellite communications. *IEEE International Symposium on Phased Array Systems and Technology*, pp. 529-535, Boston, USA, October 2010.

Geissler, M.; Woetzel, F.; Bottcher, M.; Korthoff, S.; Lauer, A. & Eube, M., (2010). L-band phased array for maritime satcom. *IEEE International Symposium on Phased Array Systems and Technology*, pp. 518-523, Boston, USA, October 2010.

Baggen, R.; Vaccaro, S. & Del Río, D. (2007). Design Considerations for Compact Mobile Ku-Band Satellite Terminals. *EuCAP The Second European Conference on Antennas and Propagation*, pp. 1-5. Edimburg, Scothland, September 2007.

Vaccaro, S.; Tiezzi, F.; Rúa, M. & De Oro, C. (2010). Ku-Band Low-Profile Rx-only and Tx-Rx antennas for Mobile Satellite Communications. *IEEE International Symposium on Phased Array Systems and Technology*, pp. 536-542, Boston, USA, October 2010.

Schippers, H. (2008). Broadband Conformal Phased Array with Optical Beam Forming for Airborne Satellite Communication. *IEEE Aerospace Conference*, pp. 1-17, September 2008.

Kanno, M.; Hashimura, T. T.; Sato, M.; Fukutani, K. & Suzuki, A. (1996). Digital beam forming for conformal active array antenna. *IEEE International Symposium on Phased Array Systems and Technology*, pp. 37-40, October 1996.

Khalifa, I. & Vaughan, R. (2007). Optimal Configuration of Multi-Faceted Phased Arrays for Wide Angle Coverage. *IEEE 65th Vehicular Technology Conference*, pp. 304-308, Boltimore, USA, April 2007.

Salas Natera, M. A.; Martínez Rodríguez-Osorio, R.; Antón Sánchez, A.; García-Rojo, I. & Cuellar, L. (2008). A3TB: Adaptive Antenna Array test-bed for tracking LEO satellites based on software defined radio. *59th International Astronautical Congress*, pp. 313-317, Glasgow. September 2008.

Salas Natera, M. A.; Martínez Rodríguez-Osorio, R. & García-Rojo López, I. (2007). Design of an Adaptive Antenna Array Test-Bed based on Software Radio for Tracking LEO Satellites. *IEEE EuCAP.* Edinburgh, Scotchland, Npvember 2007.

Martínez, R.; Salas Natera, M.; Bravo, A.; García-Rojo, I.; de Haro, L.; Mateo, M. & Gómez, M. (2007). VHF Ground Station with increased angular coverage for reception of meteorological satellites with electronic beamforming. *4th ESA International Workshop on Tracking, Telemetry and Command Systems for Space Application.* Darmstadt, Germany, 2007.

Mailloux, R. (2005). *Phased Array Antenna Handbook,* Artech House, Norwood, Massachusetts, USA.

Josefsson, L. & Persson, P. (2006). *Conformal Array Antenna. Theory and Design*, John Wiley & Sons , Hoboken, New Jersey, USA.

Montesinos, I.; Sierra Pérez, M.; Fernández, J. L.; Martínez, R. & Masa, J. L. (2009). GEODA: Adaptive Antenna of Multiple Planar Arrays for Satellite Communications. *European Conference on Antenna and Propagation.* Berlin, Germany, 2009.

Salas Natera, M. A.; Martínez, R.; De Haro Ariet, L. & Fernández Jambrina, J. (2010). Automated System for Measurement and Characterization of Planar Active Arrays. *IEEE Internationa Symposium on Phase Array Systems and Technology*, pp. 1-6, Boston USA, October 2010.

Sierra-Castañer, M.; Vera-Isasa, M.; Sierra-Pérez, M. & Fernández-Jambrina, J. (2005). Double-Beam Parallel Plate Slot Antenna. *IEEE Transactions on Antennas and Propagation*, vol.53, No.3, (2005) pp. 977-984.

Garg, R.; Bhartia, P.; Bahl, I. & Ittipiboon, A. (2001). *Microstrip Antennas Design Handbook,* Artech House, Norwood, Massachusetts, USA.

Tang, C. & Chen, M. (2007). Synthesizing Microstrip Branch-Line Couplers With Predetermined Compact Size and Bandwidth. *IEEE Transactions on Microwave Theory and Techniques, vol. 55, No.9,* (September 2007), pp. 1926-1934.

Bialkowski, M.; Jellett, S. & Varnes, R. (1996). Electronically Steered Antenna System for the Australian Mobilesat. *IEEE Transaction on Antennas ans Propagation*, vol. 143, No. 4, (August 1996), pp. 347-352.

Alonso, J.; Blas, J.; Garcia, L.; Ramos, J.; Pablos, J. & Grajal, J. (1996). Low Cost Electronically Steered Antenna and Receiver System for Mobile Saltellite Communications. *Trans. IEEE MTT*, vol. 44, No. 12, (December 1996), pp. 2438-2449.

Fernández, J. M.; Rizzo, C. & Sierra-Pérez, M. (2009). Antena Impresa Multihaz con Polarización Circular Derechas/Izquierdas Para Comunicaciones por Satélite en Banda X. *Proccedings of XXIV Simposium Nacional de la Unión Científica Internacional de Radio (URSI).* Santander, Spain, September 2009.

Encinar, J. A. & Zornoza, J. (2003). Broadband design of three- layer printed reflectarrays. *IEEE Transactions on Antennas and Propagation*, vol. 51, No. 7, (July 2003), pp. 1662-1664.

Padilla, P.; Muñoz-Acevedo, A.; Sierra-Castañer, M. & Sierra-Pérez, M. (2010). Electronically reconfigurable transmitarray at Ku band for microwave applications. *IEEE Transactions on Antennas and Propagation*, vol. 58, No. 8, (August 2010), pp. 2571-2579.

Padilla, P.; Muñoz-Acevedo, A. & Sierra-Castañer, M. (2010). Low Loss 360º Ku Band electronically Reconfigurable Phase Shifter. *International Journal of Electronics and Communications,* vol. 64, No. 11, (November 2010), pp. 1100-1104.

Royce, W. W. (1970). Managing the Development of Large Software Systems. *IEEE WESCON*, pp. 328 – 338, 1970.

Rogstad, D. H. (1997). *The SUMPLE Algorithm for Aligning Arrays of Receiving Radio Antennas: Coherence Achivied with Less Hardware and Lower Combining Loss.* TDA Progress Report, Jet Propulsion Laboratory.

Rogstad, D. H.; Mileant, A. & Pham, T. (2003). *Antenna Arraying Techniques in the Deep Space Network.* Deep Space Communication and Navegation Series, JPL California Institute of Technology, Ref. 03-001, Pasadena, USA.

Biedka, T. E. (2001). *Analysis and Development of Blind Adaptive Beamforming Algorithms.* PdD Thesis, Faculty of Virginia Polytechnique Institute and State University, Virginia.

Haykin, S. (2002). *Adaptive Filter Theory* (4th ed.). Prentice-Hall.

Godara, L. C. (2004). *Smart Antennas* (1st ed.). CRC Press..

Van Trees, H. L. (2002). *Optimum Array Processing. Part IV of Detection, Estimation, and Modulation Theory*. Wiley.

INTECH

INTECH



Advances in Satellite Communications

Edited by Dr. Masoumeh Karimi

ISBN 978-953-307-562-4
Hard cover, 194 pages
Publisher InTech
Published online 27, July, 2011
Published in print edition July, 2011

Satellite communication systems are now a major part of most telecommunications networks as well as our everyday lives through mobile personal communication systems and broadcast television. A sound understanding of such systems is therefore important for a wide range of system designers, engineers and users. This book provides a comprehensive review of some applications that have driven this growth. It analyzes various aspects of Satellite Communications from Antenna design, Real Time applications, Quality of Service (QoS), Atmospheric effects, Hybrid Satellite-Terrestrial Networks, Sensor Networks and High Capacity Satellite Links. It is the desire of the authors that the topics selected for the book can give the reader an overview of the current trends in Satellite Systems, and also an in depth analysis of the technical aspects of each one of them.

How to reference

In order to correctly reference this scholarly work, feel free to copy and paste the following:

Miguel Alejandro Salas Natera, Andrés García Aguilar, Jonathan Mora Cueva, José Manuel Fernández, Pablo Padilla De La Torre, Javier García-Gasco Trujillo, Ramón Martínez Rodríguez-Osorio, Manuel Sierra-Perez, Leandro De Haro Ariet and Manuel Sierra Castañer (2011). New Antenna Array Architectures for Satellite Communications, Advances in Satellite Communications, Dr. Masoumeh Karimi (Ed.), ISBN: 978-953-307-562-4, InTech, Available from: http://www.intechopen.com/books/advances-in-satellite-communications/new-antenna-array-architectures-for-satellite-communications

InTech Europe
University Campus STeP Ri
Slavka Krautzeka 83/A
51000 Rijeka, Croatia
Phone: +385 (51) 770 447
Fax: +385 (51) 686 166
www.intechopen.com

InTech China
Unit 405, Office Block, Hotel Equatorial Shanghai
No.65, Yan An Road (West), Shanghai, 200040, China
中国上海市延安西路65号上海国际贵都大饭店办公楼405单元
Phone: +86-21-62489820
Fax: +86-21-62489821

Hindawi Publishing Corporation
International Journal of Antennas and Propagation
Volume 2012, Article ID 428284, 10 pages
doi:10.1155/2012/428284

Review Article

Some Recent Developments of Microstrip Antenna

Yong Liu, Li-Ming Si, Meng Wei, Pixian Yan, Pengfei Yang, Hongda Lu, Chao Zheng, Yong Yuan, Jinchao Mou, Xin Lv, and Housjun Sun

Department of Electronic Engineering, School of Information and Electronics, Beijing Institute of Technology, Beijing 100081, China

Correspondence should be addressed to Yong Liu, fatufo@bit.edu.cn

Received 12 August 2011; Revised 23 November 2011; Accepted 2 January 2012

Academic Editor: Zhongxiang Q. Shen

Copyright © 2012 Yong Liu et al. This is an open access article distributed under the Creative Commons Attribution License, which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

Although the microstrip antenna has been extensively studied in the past few decades as one of the standard planar antennas, it still has a huge potential for further developments. The paper suggests three areas for further research based on our previous works on microstrip antenna elements and arrays. One is exploring the variety of microstrip antenna topologies to meet the desired requirement such as ultrawide band (UWB), high gain, miniaturization, circular polarization, multipolarized, and so on. Another is to apply microstrip antenna to form composite antenna which is more potent than the individual antenna. The last is growing towards highly integration of antenna/array and feeding network or operating at relatively high frequencies, like sub-millimeter wave or terahertz (THz) wave regime, by using the advanced machining techniques. To support our points of view, some examples of antennas developed in our group are presented and discussed.

1. Introduction

The concept of microstrip antenna was first introduced in the 1950s [1]. However, this idea had to wait nearly 20 years to be realized after the development of the printed circuit board (PCB) technology in the 1970s [2, 3]. Since then, microstrip antennas are considered as the most common types of antennas due to their obvious advantages of light weight, low cost, low profile, planar configuration, easy of conformal, superior portability, suitable for arrays, easy for fabrication, and easy integration with microwave monolithic integrate circuits (MMICs) [4–7]. They have been widely employed for the civilian and military applications such as television, broadcast radio, mobile systems, global positioning system (GPS), radio-frequency identification (RFID), multiple-input multiple-output (MIMO) systems, vehicle collision avoidance system, satellite communications, surveillance systems, direction founding, radar systems, remote sensing, biological imaging, missile guidance, and so on [8].

Despite the many advantages of typical microstrip antennas, they also have three basic disadvantages: narrow bandwidth, low gain, and relatively large size. The narrow bandwidth is one of the main drawbacks of these types of antennas. A straightforward method of improving the bandwidth is increasing the substrate thickness. However, surface wave power increases and radiation power decreases with the increasing substrate thickness [7], which leads to poor radiation efficiency. Thus, various other techniques are presented to provide wide-impedance bandwidths of microstrip antennas, including impedance matching networks using stub [9, 10] and negative capacitor/inductor [11], microstrip slot antennas using the U, L, T, and inverted T slots in the ground plane (sometimes termed defected ground structures (DGSs)) [12, 13], surface wave suppressing using magneto-dielectric substrate [14] and electromagnetic bandgap (EBG) structures [15], and composite-resonator microstrip antennas using metamaterial resonators [16, 17]. Another problem to be solved is the low gain for conventional microstrip antenna element. Cavity backing has been used to eliminate the bidirectional radiation, thereby providing higher gain compared with conventional microstrip antenna [18]. Lens covering is an alternative way to achieve gain enhancement. The lens with canonical profile, like elliptical, hemielliptical, hyper-hemispherical, extended hemispherical, used to focus the radiation beam from the radiator elements. The integrated lens microstrip antenna can be treated as composite antenna combined by microstrip radiator elements and dielectric lens, which is very useful for high frequencies (mm, sub-mm, terahertz (THz), and optical waves) applications

[19]. It is also well known that antenna array is an effective means for improving the gain [20–25].

The last limitation of conventional microstrip antennas is the relatively large size, particularly at lower microwave frequencies, since their operation frequencies are related to the electrical size of antenna. In general, the size of the rectangular microstrip antenna should be of order of a half-guided wavelength. This limitation was mathematically studied by Wheeler [26] and Chu [27]. There have been numerous efforts to minimize the antenna size and obtain the electrically small microstrip antenna with the raised demand towards smaller and smaller wireless devices. Inductive or capacitive loading are effective ways to reduce the size of microstrip antennas [28]. In the former work, we demonstrated that the size of microstrip antenna can be miniaturized using composite metamaterial resonators [16, 17]. Magneto-dielectric substrates have been widely used to miniaturize microstrip antennas due to magnetic substrates and could provide wider bandwidths than dielectric substrates [29–32]. Fractal geometries, which are composed by self-similar structures, have opened an alternative way for antenna miniaturization [33].

From the above discussions, we see that many methods and materials are used to improve the properties of microstrip antennas. However, there should be a relationship among bandwidth, gain, and size of the microstrip antennas. Antenna engineers have recognized that the improvement in one antenna property is frequently accompanied by decline in its other performances. For example, the antenna size is reduced usually at the expense of its bandwidth and gain. Therefore, a more comprehensive consideration must be given on further developments of microstrip antennas.

In this paper, we will suggest three areas for further research based on our previous works on microstrip antenna elements and arrays [16–25, 34–41]. We first note that novel microstrip antenna topologies are proposed to meet the desired requirement of variety of potential wireless applications, such as ultrawide band (UWB), high gain, miniaturization, circular polarization, multipolarized, and so on. Next, we discuss the composite antennas based on microstrip antennas which have more potent than each individual antenna. Finally, with the development of micro-/nano-machining techniques, antennas/arrays with highly integration and with highly operating frequencies are discussed. We present some examples of antennas developed in our group to support our points of view.

2. Variety of Microstrip Antenna Topologies

Microstrip antennas have extensively used in commercial and military applications due to their attractive advantages. However, the traditional microstrip antennas have the impedance bandwidth of only a few percent and radiation pattern with omnidirection, which obviously does not meet the requirements of various wireless applications. To this end, a wide variety of microstrip antenna topologies, including different microstrip antenna element structures and different microstrip array arrangements, have been studied to meet the desired requirement such as ultrawide band (UWB), high gain, miniaturization, circular polarization, multipolarized, and so forth.



(a) The structure of the quasi-Yagi antenna



(b) The photograph of the quasi-Yagi antenna

Figure 1: Compact broad-band quasi-Yagi antenna.

As we know, microstrip antennas inherently have narrower bandwidth and lower gain compared to conventional bulky antennas. Some microstrip antennas with special topologies, like quasi-Yagi, planar reflector antenna, are proposed to replace the conventional bulky antennas. Here, we will take a quai-Yagi antenna as an example to show how to design a planar microstrip antenna with Yagi-Uda end-fire radiation pattern. In addition, a microstrip array with special array topology is designed to get dual-polarized property.

2.1. Compact Broad-Band Quasi-Yagi Antenna. A novel S-band compact quasi-Yagi antenna has been designed, fabricated and measured by our group, as shown in Figure 1. This antenna is composed of a printed monopole-driven element, a printed reflector element, and six printed director elements.

To explain the end-fire radiation behavior of the quasi-Yagi antenna, a comparison of radiation patterns, among (1) microstrip monopole only, (2) microstrip monopole and a reflector, (3) microstrip monopole and a director, (4) microstrip monopole and a reflector with one director, and (5) microstrip monopole and a reflector with six director, is shown in Figure 2. We can observe that both the reflector and the director can increase the end-fire radiation, and it could be substantially improved by increasing the number of directors.

The measured VSWR results are shown in Table 1. A bandwidth of 14% for VSWR less than 1.5 is achieved. The gain of the antenna is above 7.5 dBi, as shown in Table 2. In this design, we see that the microstrip antenna with special topology could be conveniently used to replace the bulky Yagi-Uda antenna.



Figure 2: Radiation patterns of microstrip monopole only, microstrip monopole and a reflector, microstrip monopole and a director, microstrip monopole and a reflector with one director, and microstrip monopole and a reflector with six director.

Table 1: The measured VSWR of the quasi-Yagi antenna.

No.	Frequency (GHz)			
	3.25	3.5	3.75	Inband
1	1.36	1.34	1.47	<1.5
2	1.37	1.26	1.49	<1.5
3	1.36	1.25	1.48	<1.5

Table 2: The measured gain of the quasi-Yagi antenna (unit: dBi).

No.	Frequency (GHz)		
	3.25	3.5	3.75
1	7.57	8.73	8.35
2	7.58	8.55	8.37
3	7.56	8.77	8.51

2.2. Dual-Polarized Microstrip Antenna Array. The dual-polarized antenna is highly required for the radar, electronic countermeasure, and aerospace systems. It is known that the microstrip antenna can easily be integrated with microwave circuits and feeding network. Here, a novel Ku-band dual-polarization microstrip antenna array with a mixed feeding network, that is, the slot coupled feeding (V-port) and the co-plane feeding (H-port), is designed by our group, as shown in Figure 3. It is a three layers structure: top microstrip patch layer, middle stripline feeding network layer, and bottom coplane microstrip feeding network layer. Through proper array arrangement, very good isolation can be obtained.


Stripline feeding network
Patch
Stripline-microstrip transition
Microstrip feeding network
H-shape coupled slot
V
H
0
25
50
(mm)

(a) The structure of the dual-polarized microstrip antenna array



(b) The photograph of the dual-polarized microstrip antenna array

Figure 3: Dual-polarized microstrip antenna array.



Figure 4: The VSWR of the dual-polarized microstrip antenna array.

The VSWR, radiation patterns, and the isolation between two polarizations of the proposed dual-polarized microstrip antenna array are shown in Figures 4, 5, and 6, respectively. The results indicate that this microstrip antenna array has a good impedance matching, good radiation performance, as well as very high isolation (less than −25 dB), which can be an idea candidate for the dual-polarized wireless systems.



FIGURE 5: The radiation patterns of the dual-polarized microstrip antenna array at the center frequency.



FIGURE 6: The isolation of the dual-polarized microstrip antenna array.

3. Microstrip-Antenna-Based Composite Antenna

As many antenna designers have found, it is not easy to design an antenna to meet the user-defined stringent performance requirements demanded by special wireless applications like military radars, surveillances, and missile guidance, if only one type of antenna is considered. This difficulty may require the use of two more different types or structures of antenna elements with different characteristics. Composite antenna formed by two more types or structures of antennas is particularly suitable for these applications due to more advantages offered by different types or structures of antennas. For example, it is a challenging task to use single type of antenna to design a dual-band dual-polarization antenna for satellite digital multimedia broadcast (S-DMB) application [36]. A composite antenna composed with a left-handed circularly polarized (LHCP) microstrip antenna and a linear polarized omnidirectional biconical antenna is proposed by our group to meet this requirement [36]. Another example of composite antenna is comprised of a dielectric lens and microstrip log-period antenna, which has been widely applied to THz systems (this type of antenna will be further discussed in Section 4.2). Here, we will give an example of composite antenna with "structure composite" method.



FIGURE 7: The structure of the DCWS.

3.1. Monopulse Circular-Polarized Dielectric Complex Waveguide Slot Antenna Array. Waveguide slot antenna array has been widely used for wireless system, due to its advantages of high radiation efficiency, high power capacity, and high reliability. However, it is hard to overcome the disadvantage of high cost of fabrication.

One composite antenna with waveguide slot antenna array property, termed dielectric complex waveguide slot (DCWS), is composed with slot microstrip line and groove guide, as shown in Figure 7. The slot microstrip line is formed by a metal clad dielectric substrate and slots etched in the metal. This composite antenna not only maintains the advantages of the traditional waveguide slot antenna array but also has the characteristics of high consistence, easy for fabrication, and low cost.



(a) The structure of the monopulse circular-polarized DCWS antenna array (separating view)



(b) The photograph of the monopulse circular-polarized DCWS antenna array.

FIGURE 8: Ka-band monopulse circular-polarized dielectric complex waveguide slot (DCWS) antenna array.



FIGURE 9: The VSWR of sum and difference port of the monopulse circular-polarized DCWS antenna array.



FIGURE 10: The radiation pattern of the monopulse circular-polarized DCWS antenna array at the center frequency.

A Ka-band monopulse circular-polarized dielectric complex waveguide slot (DCWS) antenna array is designed, fabricated, and measured by our group, as shown in Figure 8. It consists of a circular polarization grid, a slot microstrip array, and a groove guide and feeding network. The slot microstrip array is fabricated on a Rogers 5880 film with dielectric constant of 2.2 and the thickness of 0.254 mm. The measured results of VSWR of sum and different port are shown in Figure 9. Figure 10 shows the measured radiation pattern at the center frequency. Some important array performance parameters such as gain, null depth and axial ratio (AR) are also given in Table 3. As shown in the measured results, very good performance can be obtained with the DCWS antenna array. The radiating efficiency of the DCWS antenna array is 80%, which is almost the same as the traditional waveguide slot antenna array. Moreover, the DCWS antenna array has 40% larger bandwidth than the traditional waveguide slot antenna array.

4. Highly Integration and Highly Operating Frequency Antennas Based on Advanced Machining Techniques

It is known that the microstrip antenna was first fabricated using PCB technology in 1970s, nearly 20 years after its concept was first presented in 1950s [1–3]. Clearly, the development of microstrip antennas is closely related with the machining techniques. Recently, various machining techniques, including multilayer printed circuit board (MPCB), complementary metal oxide semiconductor (CMOS), low-temperature cofired ceramics (LTCC), and micro-electro-mechanical systems (MEMS), are highly developed, opening opportunities for innovative antennas, such as active antennas, reconfigurable antennas, metamaterial-based antennas, THz antennas, and so forth. With the availability of high-precision and high-speed advanced machining techniques, microstrip antennas are growing towards highly integration of antenna/array and feed network and operating at relatively high frequencies. Since they are all based on the advanced



(a) Schematic side view of the structure of the high integrate broadband microstrip antenna array



(b) The photograph of the high integrate broadband microstrip antenna array

Figure 11: Ku-band high integrate broadband microstrip antenna array using MPCB technology.



Figure 12: The VSWR of the high integrate broad-band microstrip antenna array using MPCB technology.

machining techniques, we suggest that a third research area of microstrip antennas is constantly introducing novel advanced machining techniques. In the following, two examples will be presented to show how important the advanced machining technique is to fabricate microstrip antennas. One is the highly integrate broad-band microstrip antenna array fabricated using MPCB technology. Another is THz wave planar integrated active microstrip antenna using MEMS technology.



Figure 13: The gain of the high integrate broad-band microstrip antenna array using MPCB technology.

Table 3: The measured data of the monopulse circular-polarized DCWS antenna array.

Fre. (GHz)	Gain (dBi)	Null depth (dB)	AR (dB)
$f_0 - 0.2$	22.8	−37.3	3.8
f_0	21.9	−29.9	2.9
$f_0 + 0.2$	22.1	−26	4.1

4.1. High Integrate Broad-Band Microstrip Antenna Array Using Multilayer Printed Circuit Board (MPCB) Technology.

Recently, with the development of the multilayer printed circuit board (MPCB) technology, the microstrip antennas can be designed and fabricated from one-dimensional (1D) to 2D and even 3D structures.

Based on the MPCB technology, a high integrated broadband Ku-band microstrip antenna array is designed, fabricated, and measured by our group, as shown in Figure 11. This antenna consists of a parasitic patch, a driven patch, a stripline feeding network, a broad-band coaxial line to stripline transition, some buried screw holes, and some via holes. The feeding network is integrated in the bottom of the substrate of the antenna. As all of the structures fabricated at once, the accuracy and the uniformity can be assured. Two antennas of this type are measured. The measured VSWR, gain, and radiation pattern at the center frequency are shown in Figures 12, 13, and 14, respectively. The measured results show that this antenna maintains good radiation and matching performances with relative bandwidth of 13%. They have also shown good uniformity by using MPCB technology.

4.2. THz Wave Planar Integrated Active Microstrip Antenna Using Micro-Electromechanical Systems (MEMSs) Technology.

THz waves typically include frequencies between 0.1 THz and 10 THz. THz technology is now becoming a promising technology which has potential applications in many fields, such as short-range communication, biosensor, imaging,



(a) E-plane

(b) H-plane

Figure 14: The radiation pattern of the high integrate broad-band microstrip antenna array using MPCB technology at the center frequency.



(a) The photograph of the THz monolithic antenna



(b) The photograph of the THz monolithic antenna covered by a dielectric lens

Figure 15: THz wave planar integrated active microstrip antenna using micro-electromechanical systems (MEMSs).

national security, space exploration and communication, and so forth [39–46]. To realize THz transceiver system, antenna is an essential component. We often use horn antenna, lens antenna, and dielectric parabolic antenna, for THz systems. However, they are not easy to integrate with monolithic integrate circuits. Although the microstrip antenna has the merits of small volume, light weight, and easy integration with circuit, it is difficult to be processed in such high-frequency regions. MEMS technology opens the way to design of THz antennas, circuits, and systems. THz monolithic antenna fabricated using MEMS technology and covered by a dielectric lens, which can be considered a composite antenna, are designed, fabricated, and measured by our group, as shown in Figure 15.

Diodes have the functions of mixing and/or modulating the carrier-wave signal. It is an effective way to reduce the propagation path for detectors application by integrating the diode and microstrip antenna. The extended hyper-hemispherical dielectric lens is used to increase the gain of the microstrip antenna. An antenna-coupled detector integrated with a dielectric lens is designed and fabricated up to THz range by our group. The planar microstrip log-spiral antenna and log-period antenna have been fabricated using micro-electromechanical systems (MEMSs) technology. The photographs of the antennas are demonstrated in Figure 15. The measured responses of the antenna-coupled detector working at different frequency bands are shown in Figure 16, which can be considered to determine the effective operating frequencies [19, 40]. This detector gave a valid response from 12 GHz to 110 GHz frequencies. The results prove the validity and feasibility of the THz antenna designed using micro-electromechanical systems (MEMSs) technology.

5. Conclusion

The advantages and disadvantages of microstrip antennas are discussed in this paper. In particular, three areas for further development of microstrip antennas are presented based on our previous works on microstrip antenna elements and arrays. Variety of microstrip antenna topologies and microstrip-antenna-based composite antenna are discussed, and



(a) Ku-band (b) Ka-band



(c) V-band (d) W-band

Figure 16: Frequency responses test results of the THz wave planar integrated active microstrip antenna covered by a dielectric lens.

the advanced machining techniques pushing the microstrip antennas towards the highly integration of antenna/array and feeding network and the highly operating frequencies are described. To demonstrate the distinctive features of novel microstrip antennas, various antenna elements and arrays for different applications are presented. This paper has shown that the microstrip antennas are still very promising paradigm for civilian and military wireless applications.

References

[1] G. A. Deschamps, "Microstrip microwave antennas," in *Proceedings of the 3rd USAF Symposium on Antennas*, 1953.

[2] E. V. Byron, "A new flush-mounted antenna element for phased array application," in *Proceedings of the Phased Array Antenna Symposium*, pp. 187–192, 1970.

[3] J. Q. Howel, "Microstrip antennas," in *Proceedings of the Digest of the International Symposium of the Antennas and propagation Society*, pp. 177–180, 1972.

[4] I. J. Bahl and P. Bhartia, *Microstrip Antennas*, Artech House, 1980.

[5] J. R. James, P. S. Hall, and C. Wood, *Microstrip Antenna Theory and Design*, Peter Peregrinus, 1981.

[6] K. R. Carver and J. W. Mink, "Microstrip antenna technology," *IEEE Transactions on Antennas and Propagation*, vol. 1, no. 1, pp. 2–24, 1981.

[7] D. M. Pozar, "Microstrip antennas," *Proceedings of the IEEE*, vol. 80, no. 1, pp. 79–91, 1992.

[8] R. Garg, I. Bhartia, I. Bahl, and A. Ittipiboon, *Micro-Strip Antenna Design Handbook*, Artech House, Boston, Mass, USA, 2001.

[9] D. M. Pozar and B. Kaufman, "Increasing the bandwidth of a microstrip antenna by proximity coupling," *Electronics Letters*, vol. 23, no. 8, pp. 368–369, 1987.

[10] H. F. Pues and A. R. Van de Capelle, "Impedance-matching technique for increasing the bandwidth of microstrip antennas," *IEEE Transactions on Antennas and Propagation*, vol. 37, no. 11, pp. 1345–1354, 1989.

[11] A. Kaya and E. Y. Yüksel, "Investigation of a compensated rectangular microstrip antenna with negative capacitor and negative inductor for bandwidth enhancement," *IEEE Transactions on Antennas and Propagation*, vol. 55, no. 5, pp. 1275–1282, 2007.

[12] K. L. Wong and N. H. Hsu, "A broad-band rectangular patch antenna with a pair of wide slits," *IEEE Transactions on Antennas and Propagation*, vol. 49, no. 9, pp. 1345–1347, 2001.

[13] S. I. Latif, L. Shafai, and S. K. Sharma, "Bandwidth enhancement and size reduction of microstrip slot antennas," *IEEE Transactions on Antennas and Propagation*, vol. 53, no. 3, pp. 994–1003, 2005.

[14] P. M. T. Ikonen, S. I. Maslovski, C. R. Simovski, and S. A. Tretyakov, "On artificial magnetodielectric loading for improving the impedance bandwidth properties of microstrip antennas," *IEEE Transactions on Antennas and Propagation*, vol. 54, no. 6, pp. 1654–1662, 2006.

[15] R. Cocooli, F. R. Yang, T. P. Ma, and T. Itoh, "Apertu-recoupled patch antenna on UCPBG substrate," *IEEE Transactions on Microwave Theory and Techniaues*, vol. 1, no. 47, pp. 2123–2130, 1999.

[16] L.-M. Si and X. Lv, "CPW-FED multi-band omni-directional planar microstrip antenna using composite metamaterial resonators for wireless communications," *Progress in Electromagnetics Research*, vol. 83, pp. 133–146, 2008.

[17] L. M. Si, H. Sun, Y. Yuan, and X. Lv, "CPW-fed com-pact planar UWB antenna with circular disc and spiral split ring resonators," in *Progress in Electromagnetics Research Symposium*, pp. 502–505, 2009.

[18] Y. Yuan, L.-M. Si, Y. Liu, and X. Lv, "Integrated log-periodic antenna for Terahertz applications," in *International Conference on Microwave Technology and Computational Electromagnetics*, pp. 276–279, 2009.

[19] L. Xin, M. Jinchao, Y. Yong, Y. Weihua, N. Hongbin, and G. Yafen, "Integrated active antennas in terahertz focal plane imaging system," in *Proceedings of the International Workshop on Antenna Technology*, pp. 157–163, 2011.

[20] Q. Xu, W. Zhang, H. Sun, and X. Lu, "Millimetre wave multi-polarised microstrip antenna array and application example," *IET Microwaves, Antennas and Propagation*, vol. 4, no. 10, pp. 1525–1530, 2010.

[21] M. Wei, H. Deng, H. Sun, and Y. Liu, "Design of an X/Ka dual-band co-aperture broadband microstrip antenna array," in *Proceedings IEEE International Conference on Microwave Technology and Computational Electromagnetics*, pp. 217–220, 2011.

[22] Y. Liu, X. Lu, Y. Yuan, Y. Chen, and L. Shi, "Integrated design and research of Ka-band electronically large mono-pulse planar antenna and feed system," in *Proceedings of the 7th International Symposium on Antennas, Propagation and EM Theory (ISAPE '06)*, pp. 150–153, October 2006.

[23] Y. Liu, H. J. Sun, X. Lu et al., "Study of the millimeter microstrip monopulse antenna array in the dual-sensor system," in *Proceedings of the 7th International Symposium on Antennas, Propagation and EM Theory (ISAPE '06)*, pp. 157–160, October 2006.

[24] Y. An, X. Lv, and B. Gao, "Developing a kind of mi-crostrip array antenna with beam squint," in *Proceedings of the 5th International Symposium on Antennas, Propagation and EM Theory*, pp. 443–446, 2000.

[25] L. Yong, L. Xin, H. Zhao, and Y. Yuan, "Integrated design and research of novel KA-band circular polarized monopulse interrogator array antenna," in *Proceedings of the IET International Radar Conference 2009*, pp. 1–4, April 2009.

[26] H. A. Wheeler, "Fundamental limitations of small an-tennas," *Proceedings of the IRE*, vol. 35, pp. 1479–1484, 1947.

[27] L. J. Chu, "Physical limitations of omni-directional antennas," *Journal of Applied Physics*, vol. 19, no. 12, pp. 1163–1175, 1948.

[28] R. Azadegan and K. Sarabandi, "A novel approach for miniaturization of slot antennas," *IEEE Transactions on Antennas and Propagation*, vol. 51, no. 3, pp. 421–429, 2003.

[29] H. Mosallaei and K. Sarabandi, "Magneto-dielectrics in electromagnetics: concept and applications," *IEEE Transactions on Antennas and Propagation*, vol. 52, no. 6, pp. 1558–1567, 2004.

[30] P. M. T. Ikonen, S. I. Maslovski, C. R. Simovski, and S. A. Tretyakov, "On artificial magnetodielectric loading for improving the impedance bandwidth properties of microstrip antennas," *IEEE Transactions on Antennas and Propagation*, vol. 54, no. 6, pp. 1654–1662, 2006.

[31] P. M. T. Ikonen, K. N. Rozanov, A. V. Osipov, P. Alitalo, and S. A. Tretyakov, "Magnetodielectric substrates in antenna miniaturization: potential and limitations," *IEEE Transactions on Antennas and Propagation*, vol. 54, no. 11, pp. 3391–3399, 2006.

[32] P. Ikonen and S. Tretyakov, "On the advantages of magnetic materials in microstrip antenna miniaturization," *Microwave and Optical Technology Letters*, vol. 50, no. 12, pp. 3131–3134, 2008.

[33] J. Anguera, C. Puente, C. Borja, and J. Soler, "Frac-tal-shaped antennas: a review," in *Wiley: Encyclopedia of RF and Microwave Engineering*, K. Chang, Ed., vol. 2, pp. 1620–1635, 2005.

[34] L. Shi, H. Sun, X. Lu, C. Deng, and Y. Liu, "Study of the improved MM-Wave omni-directional microstrip antenna," in *Proceedings of the 7th International Symposium on Antennas, Propagation and EM Theory (ISAPE '06)*, pp. 238–241, October 2006.

[35] L. Shi, H. Sun, and X. Lu, "A composite antenna with wide circularly polarized beamwidth," *Microwave and Optical Technology Letters*, vol. 51, no. 10, pp. 2461–2464, 2009.

[36] L. Shi, H. Sun, W. Dong, and X. Lv, "A dual-band multi-function carborne hybrid antenna for satellite communication relay system," *Progress in Electromagnetics Research*, vol. 95, pp. 329–340, 2009.

[37] Y. Chen, H. Sun, and X. Lv, "Novel design of dual-polarization broad-band printed L-shaped probe fed microstrip patch antenna for SAR applications," in *IET International Radar Conference 2009*, pp. 1–4, April 2009.

[38] L. M. Si, H. J. Sun, and X. Lv, "Numerical simulations of backward-to-forward leaky-wave antenna with composite right/left-handed coplanar waveguide," *Chinese Physics Letters*, vol. 27, no. 3, Article ID 034106, 2010.

[39] L.-M. Si, H.-J. Sun, and X. Lv, "THz leaky-wave antenna with high-directivity and beam-steering using CPW CRLH metamaterial resonators," in *Proceedings of the 3rd International Symposium on Photoelectronic Detection and Imaging*, Beijing, China, 2009.

[40] Y. Liu, L. M. Si, S. Zhu, and H. Xin, "Experimental realization of an integrated THz electromagnetic crys-tals (EMXT) H-plane horn antenna," *Electronics Letters*, vol. 47, no. 2, pp. 80–82, 2011.

[41] L. M. Si, Y. Liu, S. H. Zhu, and H. Xin, "Integrated THz horn antenna using EBG structures," in *Proceedings of the IEEE International Symposium on Antennas and Propagation and USNC/CNC/URSI National Radio Science Meeting*, University of Colorado at Boulder, 2011.

[42] Y. Liu, Y. Yuan, X. Lv, and L.-M. Si, "Design of 0.5 THz 2D square lattice EBG waveguide transmission line and power-divider using MEMS technology," in *Proceedings 3rd International Symposium on Photoelectronic Detection and Imaging*, vol. 7385, Beijing, China, 2009.

[43] L.-M. Si, Y. Yong, H.-J. Sun, and L. Xin, "Characterization and application of planar terahertz narrow bandpass filter with metamaterial resonators," in *Proceedings of the International*

Workshop on Metamaterials, pp. 351–354, Nanjing, China, 2008.

[44] L. M. Si and X. Lv, “Terahertz waves hairpin microstrip bandpass filter and its application to overlaid dielectric material detection,” *Modern Physics Letters B*, vol. 22, no. 29, pp. 2843–2848, 2008.

[45] L.-M. Si, H.-J. Sun, and X. Lv, “Theoretical investigation of terahertz amplifier by carbon nanotubes within transmission line metamaterials,” *Microwave and Optical Technology Letters*, vol. 53, no. 4, pp. 815–818, 2011.

[46] W. Hong, “Millimeter wave and THz communications in China,” in *Proceedings of the IEEE International Microwave Symposium Digest (MTT ’11)*, pp. 1–4, 2011.

Journal of
Engineering

The Scientific World Journal

International Journal of
Rotating Machinery

Journal of
Sensors

International Journal of
Distributed Sensor Networks

Advances in
Civil Engineering

Hindawi

Submit your manuscripts at
http://www.hindawi.com


Journal of
Control Science and Engineering

Journal of
Robotics

Journal of
Electrical and Computer Engineering

Advances in
OptoElectronics

VLSI Design

International Journal of
Navigation and Observation

Modelling & Simulation in Engineering

International Journal of
Aerospace Engineering

International Journal of
Chemical Engineering

International Journal of
Antennas and Propagation

Active and Passive Electronic Components

Shock and Vibration

Advances in
Acoustics and Vibration

MICROWAVE JOURNAL
REVIEWED
EDITORIAL BOARD

TECHNICAL FEATURE

A 2.4 GHz Polarization-diversity Planar Printed Dipole Antenna for WLAN and Wireless Communication Applications

This article presents the design simulation, fabrication and measured performance of a 2.4 GHz polarization-diversity printed dipole antenna for wireless communication applications. Two orthogonal printed dipole antennas, each with a microstrip via-hole balun for vertical and horizontal polarization, are combined and fabricated on a PCB substrate. PIN diodes are used as switches to select the desired antenna polarization. The 3D finite-element-method (FEM) electromagnetic EM simulator, HFSS, is used in the design simulation of this planar antenna structure. Numerical and measured results of the antenna radiation characteristics, including input SWR, radiation pattern coverage and polarization-diversity, are presented and compared.

In wireless communication systems, such as wireless local area networks (WLAN), research and development efforts are aiming at smaller size and better performance. In addition to the use of signal processing techniques to improve communication channel capacity, the radiation characteristics of the portable antenna system is also very important for communication performance.

In urban or indoor environments, the radio wave will propagate through complicated reflection or scattering processes. The polarization of the radio wave may change significantly. In order to effectively receive the communications signal, a polarization-diversity antenna for wireless communications may become an important requirement. A polarization-diversity antenna may have a pair of linearly-polarized antennas, and the radio signal received on both antenna is sampled and compared at

Huey-Ru Chuang, Liang-Chen Kuo,
Chi-Chang Lin and Wen-Tzu Chen
National Cheng Kung University,
Tainan, Taiwan


VERTICAL POLARIZATION
PRINTED DIPOLE ANTENNA
HORIZONTAL POLARIZATION
MICROSTRIP BALUN
PRINTED DIPOLE ANTENNA
MICROSTRIP BALUN
POLARIZATION-DIVERSITY PIN DIODE SELECTION CIRCUIT

▲ *Fig. 1 A 2.4 GHz polarization-diversity antenna.*


PRINTED DIPOLE STRIP
GROUND METAL PLANE
VIA-HOLE
2
1
COAXIAL SMA
PRINTED BALUN
MICROSTRIP
PRINTED DIPOLE STRIP
■ MICROSTRIP LINE STRIP (TOP)
🟨 DIPOLE STRIP & MICROSTRIP GROUND METAL (BOTTOM)

▲ *Fig. 2 Printed dipole antenna with a microstrip balun.*



▲ *Fig. 3 Simulated performance of a 2.4 GHz printed dipole antenna placed horizontally; (a) input SWR, (b) E-plane pattern and (c) H-plane pattern.*

certain time intervals. Then the antenna with the best signal quality is selected.

A typical dipole antenna radiates a vertically polarized EM wave and has an omnidirectional antenna pattern. In order to have a preferred planar antenna structure for this 2.4 GHz polarization-diversity antenna, a printed dipole antenna with a microstrip via-hole balun is designed. As shown in ***Figure 1***, two orthogonal printed dipole antennas, for vertical and horizontal polarization, respectively, are combined and fabricated on a PCB substrate. PIN diodes are used to switch and select the desired antenna polarization.

In the antenna design, the high frequency structure simulator (HFSS), based on a 3D FEM, was employed for design simulation of the complete printed dipole structure. A printed dipole antenna and a polarization-diversity planar dipole antenna board (with a polarization-selection PIN diode circuit) have been fabricated on FR-4 PCB substrates. A complete 3D structure FEM simulation and the measured performance of the realized printed dipole-antenna are compared. The measured radiation characteristics of the polarization-diversity planar dipole antenna, including input SWR, radiation pattern coverage and polarization diversity, are presented.

PRINTED DIPOLE ANTENNA WITH MICROSTRIP BALUN

As shown in ***Figure 2***, a printed dipole antenna has a printed microstrip balun which acts as an unbalanced-to-balanced transformer from the feed coaxial line to the two printed dipole strips. The length of the dipole strip and the balun microstrip are both about 1/4 wavelength. The ground plane of the microstrip line and the dipole antenna strips are in the same plane. A via-hole permits the feed point 2 of a printed dipole strip to have the same phase as the feed point 1 of the other printed dipole strip. Due to the 180° phase difference between the top strip and the ground plane of the microstrip line, the feed point 2 of the printed dipole strip will have 180° phase difference with the other feed point 1. Accurate dimensions of the printed dipole strip and the microstrip balun structure are determined by numerical simulation, using HFSS.

The simulation results for a 2.4 GHz printed dipole antenna placed horizontally with a microstrip via-hole balun and fabricated on an FR-4 substrate are shown in ***Figure 3***. The input SWR is less than 1.5 from 2.2 to 2.6 GHz. The simulated E- and H-plane antenna patterns are very close to those of an ideal dipole antenna, where the H-plane pattern is omnidirectional. ***Figure 4*** is a photograph of a realized antenna. The measured input SWR and antenna patterns (measured with the dipole placed vertically) agree well with the simulation results, as shown in ***Figure 5***.

PLANAR POLARIZATION-DIVERSITY PRINTED DIPOLE ANTENNA

Figure 6 shows photographs of a realized 2.4 GHz planar polarization-diversity antenna consisting of two orthogonal printed dipole antennas with a polarization-switched PIN diode circuit. Each printed dipole has



▲ *Fig. 4 A 2.4 GHz printed dipole antenna with a microstrip via-hole balun; (a) top view and (b) bottom view.*



▲ *Fig. 5 Measured input SWR (a) and radiation patterns (b).*



▲ *Fig. 6 A 2.4 GHz planar polarization-diversity antenna with a polarization-switched PIN diode circuit; (a) top view and (b) bottom view.*



▲ *Fig. 7 Input SWR simulation of a 2.5 GHz polarization-diversity dipole antenna with the vertical dipole selected.*

a microstrip via-hole balun. The terminals of the two baluns are connected to a PIN diode selection circuit. Voltages from the transceiver circuit (±5.0V) are fed through a cable to the input of the PIN diode circuit section, to short or open-circuit the PIN diodes. Hence, either the vertical or horizontal printed dipole can be selected and connected to the transceiver.

Since the two dipoles are very close to each other and near the PIN diode circuit section, EM coupling will degrade the performance of each dipole. ***Figure 7*** shows the input SWR simulation results with the vertical dipole antenna selected (+5V to PIN diode switching circuit). The input SWR is less than 2 from 2.25 to 2.60 GHz. The simulated E- and H-plane antenna patterns are all very close to those of an ideal dipole antenna, of which the H-plane pattern is still omnidirectional, as shown in ***Figure 8***. Note that the dominant polarization is the vertical (E_θ) field, which agrees with the selection of the vertical dipole. The antenna pattern has some attenuation in the direction of the PIN diode circuit board. It can also be seen that a certain level of the input RF signal is induced to the horizontal antenna path by EM coupling, which generates some level of cross-polarization field. ***Figure 9*** shows the simulation results with the horizontal dipole antenna selected (–5V to PIN diode switching circuit). Results similar to the ones obtained for the vertical dipole antenna can be observed, except that the dominant polarization is the horizontal (E_ϕ) field, which agrees with the selection of the horizontal dipole.

The measured antenna input SWR with vertical or horizontal dipole selection confirms the input SWR of each dipole antenna (through the PIN diode selection circuit) is less than 1.5 from 2.2 to 2.6 GHz, which agrees with the HFSS simulation results. The measured antenna patterns with the selection of the vertical or horizontal dipole shows that for the selection of the vertical dipole, the H-plane pattern is still quite omnidirectional (as an ideal vertical dipole) with some attenuation in the direc-



▲ *Fig. 8 Simulation of a 2.5 GHz polarization-diversity dipole antenna with the vertical dipole selected; (a) E_θ-field E-plane pattern, (b) E_θ-field H-plane pattern, (c) E_ϕ-field (cross-polarization) E-plane pattern and (d) E_ϕ-field (cross-polarization) H-plane pattern.*

tion of the PIN diode circuit board. ***Figures 10*** and ***11*** show the mesured SWR and antenna patterns, respectively. A certain level of the induced cross-polarization pattern is observed as predicted by the HFSS simulation due to the proximity of the horizontal dipole strip and the PIN diode circuit board. As for the selection of the horizontal dipole, the E-plane pattern is also close to that of an ideal horizontal dipole. Also, the induced cross-polarization pattern is observed, which is the same situation as the selection of the vertical dipole. The measured data shows a good agreement with the HFSS simulation results and how the antenna polarization-diversity is working.

CONCLUSION

3D FEM design simulation, realization and measurements of a 2.4 GHz printed dipole antenna (with a microstrip via-hole balun) and a planar polarization-diversity printed dipole antenna are presented. The planar polarization-diversity antenna consists of two orthogonal printed dipole antennas for vertical and horizontal polarization and is fabricated on a FR-4 PCB board. A PIN diode switching circuit is used to select the desired antenna polarization. Satisfactory agreement between simulation and measurements is observed. The measured input SWR of the realized printed dipole antenna is less than 1.5 from 2.2 to 2.6 GHz. The measured input SWR of the vertical and horizontal dipole (through the PIN diode switching circuit) of the realized planar polarization-diversity antenna is less than 1.5 from 2.3 to 2.6 GHz. The measured E- and H-plane patterns of the polarization-diversity antenna show that the selected vertical or horizontal dipole have a performance close to a single dipole antenna in a vertical or horizontal position. The designed planar polarization-diversity antenna can be used for wireless communication and WLAN applications.



▲ *Fig. 9 Simulation of a 2.4 GHz polarization-diversity printed dipole antenna (with the horizontal dipole selected); (a) input SWR, (b) E_ϕ-field E-plane pattern, (c) E_ϕ-field H-plane pattern, (d) E_θ-field (cross-polarization) E-plane pattern and (e) E_θ-field (cross-polarization) H-plane pattern.*



▲ *Fig. 10 Measured input SWR of a 2.4 GHz polarization-diversity printed dipole antenna; (a) vertical dipole selection and (b) horizontal dipole section.*



▲ *Fig. 11 Measured co-and cross-polarized patterns of a 2.4 GHz polarization-diversity printed dipole antenna; (a) vertical dipole selected and (b) horizontal dipole selected.*

ACKNOWLEDGMENT

The authors would like to thank Ansoft Inc. for its support of the HFSS software. ■

References

1. K. Fujimoto and J. R. James, *Mobile Antenna Systems Handbook*, Artech House Inc., Norwood, MA 1994.
2. B. Edward and D. Rees, "A Broadband Printed Dipole with Integrated Balun," *Microwave Journal*, May 1987, pp. 339–344.
3. K. Hettak, G.Y. Delisle and M.G. Stubbs, "A Novel Variant of Dual Polarized CPW Fed Patch Antenna for Broadband Wireless Communications," *IEEE Antennas and Propagation Society International Symposium Digest*, Vol.1, 2000, pp. 286–289.
4. L. Zhu and K. Wu, "Model-based Characterization of CPS-fed Printed Dipole for Innovative Design of Uniplanar Integrated Antenna," *IEEE Microwave and Guided Wave Letters*, Vol. 9, No. 9, September 1999, pp. 342–344.
5. N. Michishitai and H. Arai, "A Polarization-diversity Antenna by Printed Dipole and Patch With a Hole," *IEEE Antennas and Propagation Society International Symposium Digest*, 2001, pp. 368–371.

Huey-Ru Chuang *received his BSEE and MSEE degrees from National Taiwan University, Taipei, Taiwan, in 1977 and 1980, respectively, and his PhD degree in electrical engineering from Michigan State University, East Lansing, MI, in 1987. From 1987 to 1988, he was a post-doctoral research associate at the Engineering Research Center of Michigan State University. From 1988 to 1990, he was with the Portable Communication Division of Motorola Inc., Ft. Lauderdale, FL. He joined the department of electrical engineering of National Cheng Kung University, Tainan, Taiwan, in 1991, where he is currently a professor. His research interests include portable antenna design, RF/microwave circuits and RFIC/MMIC for wireless communications, electromagnetic computation of human interaction with mobile antennas, EMI/EMC, microwave communication and detection systems.*

Liang-Chen Kuo *received his BSEE degree from Nan-Tai Institute of Technology, Tainan, Taiwan, and his MSEE degree from Tatung Institute of Technology, Taipei, Taiwan, in 1987 and 1996, respectively. He is currently working toward his PhD degree in electrical engineering from National Cheng Kung University, Tainan, Taiwan. His research interests include computational electromagnetics and antenna design.*

Chi-Chang Lin *received his BSEE and MSEE degrees from Tatung Institute of Technology, Taipei, Taiwan, in 1999 and 2001, respectively. He is currently working toward his PhD degree in electrical engineering from National Cheng Kung University, Tainan, Taiwan. His research interests include EM simulation and microwave antenna design.*

Wen-Tzu Chen *received his PhD degree from National Cheng Kung University, Tainan, Taiwan, in 1998. He is currently an assistant professor at the Institute of Computer and Communication, Shu-Te University, Yen Chau, Taiwan. His research interests include numerical computation of EM interaction between the antenna and the human body, and microwave antenna design.*

射频和天线设计培训课程推荐

易迪拓培训(www.edatop.com)由数名来自于研发第一线的资深工程师发起成立，致力并专注于微波、射频、天线设计研发人才的培养；我们于 2006 年整合合并微波 EDA 网(www.mweda.com)，现已发展成为国内最大的微波射频和天线设计人才培养基地，成功推出多套微波射频以及天线设计经典培训课程和 ADS、HFSS 等专业软件使用培训课程，广受客户好评；并先后与人民邮电出版社、电子工业出版社合作出版了多本专业图书，帮助数万名工程师提升了专业技术能力。客户遍布中兴通讯、研通高频、埃威航电、国人通信等多家国内知名公司，以及台湾工业技术研究院、永业科技、全一电子等多家台湾地区企业。

易迪拓培训推荐课程列表： http://www.edatop.com/peixun/tuijian/

射频工程师
养成培训课程套装
易迪拓培训
www.edatop.com

射频工程师养成培训课程套装

该套装精选了射频专业基础培训课程、射频仿真设计培训课程和射频电路测量培训课程三个类别共 30 门视频培训课程和 3 本图书教材；旨在引领学员全面学习一个射频工程师需要熟悉、理解和掌握的专业知识和研发设计能力。通过套装的学习，能够让学员完全达到和胜任一个合格的射频工程师的要求…

课程网址：http://www.edatop.com/peixun/rfe/110.html

手机天线设计培训视频课程

该套课程全面讲授了当前手机天线相关设计技术，内容涵盖了早期的外置螺旋手机天线设计，最常用的几种手机内置天线类型——如 monopole 天线、PIFA 天线、Loop 天线和 FICA 天线的设计，以及当前高端智能手机中较常用的金属边框和全金属外壳手机天线的设计；通过该套课程的学习，可以帮助您快速、全面、系统地学习、了解和掌握各种类型的手机天线设计，以及天线及其匹配电路的设计和调试...

课程网址： http://www.edatop.com/peixun/antenna/133.html

手机天线设计培训
中文视频教程
主讲：李明洋
易迪拓培训

hp 企业内训课程
WiFi天线和射频电路设计培训
主讲：李明洋

WiFi 和蓝牙天线设计培训课程

该套课程是李明洋老师应邀给惠普 (HP)公司工程师讲授的 3 天员工内训课程录像，课程内容是李明洋老师十多年工作经验积累和总结，主要讲解了 WiFi 天线设计、HFSS 天线设计软件的使用，匹配电路设计调试、矢量网络分析仪的使用操作、WiFi 射频电路和 PCB Layout 知识，以及 EMC 问题的分析解决思路等内容。对于正在从事射频设计和天线设计领域工作的您，绝对值得拥有和学习！…

课程网址：http://www.edatop.com/peixun/antenna/134.html

CST 学习培训课程套装

示意图
DVD
CST视频培训课程套装
李明洋主讲
易迪拓培训
www.edatop.com

该培训套装由易迪拓培训联合微波 EDA 网共同推出，是最全面、系统、专业的 CST 微波工作室培训课程套装，所有课程都由经验丰富的专家授课，视频教学，可以帮助您从零开始，全面系统地学习 CST 微波工作的各项功能及其在微波射频、天线设计等领域的设计应用。且购买该套装，还可超值赠送 3 个月免费学习答疑…

课程网址：http://www.edatop.com/peixun/cst/24.html

HFSS 学习培训课程套装


示意图
ANSYS HFSS
HFSS培训课程套装
李明洋主讲
微波EDA
DVD

该套课程套装包含了本站全部 HFSS 培训课程，是迄今国内最全面、最专业的 HFSS 培训教程套装，可以帮助您从零开始，全面深入学习 HFSS 的各项功能和在多个方面的工程应用。购买套装，更可超值赠送 3 个月免费学习答疑，随时解答您学习过程中遇到的棘手问题，让您的 HFSS 学习更加轻松顺畅…

课程网址：http://www.edatop.com/peixun/hfss/11.html

ADS 学习培训课程套装


Agilent Technologies
ADS培训课程套装
最全面、系统的ADS培训课程
赠送3个月学习答疑
易迪拓培训
www.edatop.com
DVD

该套装是迄今国内最全面、最权威的 ADS 培训教程，共包含 10 门 ADS 学习培训课程。课程是由具有多年 ADS 使用经验的微波射频与通信系统设计领域资深专家讲解，并多结合设计实例，由浅入深、详细而又全面地讲解了 ADS 在微波射频电路设计、通信系统设计和电磁仿真设计方面的内容。能让您在最短的时间内学会使用 ADS，迅速提升个人技术能力，把 ADS 真正应用到实际研发工作中去，成为 ADS 设计专家...

课程网址： http://www.edatop.com/peixun/ads/13.html

我们的课程优势：

※ 成立于 2004 年，10 多年丰富的行业经验，

※ 一直致力并专注于微波射频和天线设计工程师的培养，更了解该行业对人才的要求

※ 经验丰富的一线资深工程师讲授，结合实际工程案例，直观、实用、易学

联系我们：

※ 易迪拓培训官网：http://www.edatop.com

※ 微波 EDA 网：http://www.mweda.com

※ 官方淘宝店：http://shop36920890.taobao.com


Antenna
Diode
Transmission line
Diode
Power Divider
Shorted stub


DC Output
Antenna
Rectifier Circuit

Giedrius Rakauskas

Follow

Phased Patch Antenna Array Design

Engineering

1473 17 0



Type	E-Field (peak)
Monitor	e-field (f=3.47) [1]
Component	z
Maximum-3D	5958.93 V/m at -3.17806e-012 / 23.49 / -1.6175
Frequency	3.47
Phase	0 degrees

Third Year Project

The aim of this project was to design a directive phased patch antenna array that could be implemented in modern vehicles for distance measurement and autonomous cruise control.

The particular technology allows improved performance as well as reduced costs and size.



Initial Design - Three Copies


z
y
Theta
Phi
x
2.95
2.49
2.21
1.93
1.66
1.38
1.1
0.829
0.552
0.276
0

Type	Farfield
Approximation	enabled (kR >> 1)
Monitor	farfield (f=3.5) [1]
Component	Abs
Output	Gain
Frequency	3.5
Rad. effic.	0.7234
Tot. effic.	0.6577
Gain	2.946

Square Patch Antenna - Farfield Simulation Results



Two-Element Array



Four-Element Array


Phi
x
5.95
4.96
3.96
2.97
1.98
0.991
0

Type	Farfield
Approximation	enabled (kR >> 1)
Monitor	farfield (f=3.47) [1]
Component	Abs
Output	Gain
Frequency	3.47
Rad. effic.	0.4762
Tot. effic.	0.3846
Gain	10.57

Four-Element Array - CST Microwave Studio Simulation Results


247.8
260.9
B
C
D

Sixteen-Element Array Design



Sixteen-Element Array - S-Parameter Plot



Giedrius Rakauskas

Vilnius, Lithuania

Follow





View Complete Profile →

Comments

Basic Info

Third Year BEng Project - Phased Patch Antenna Array

Credits

Giedrius Rakauskas
Vilnius, Lithuania

+ Follow

Tags

patch antenna | antenna array | square patch antenna | cst mws | cst microwave studio

Tools Used

CST Microwave Studio, FR-4

Report

Bēhance

About Behance & Careers Adobe Portfolio Blog Behance API Portfolio Review Week
Creative Career Tips Apps



Fig. 4

Types of antennas **a** 2.45 GHz patch antenna with rectifier [38]. ©2010 IEEE. All rights reserved; **b** Planar dual-polarized antenna [24]. ©2015 IEEE. All rights reserved; **c** Microstrip antenna [37]. ©2012 IEEE. All rights reserved; **d** Array of stacked differential patch antenna [33]. ©2015 IEEE. All rights reserved

The plate antennas are popular and have many applications [27, 34, 38]; on-chip antennas are preferred for small and compact applications. Recently, many publications addressed wide-band and multi-band antennas. It has been proven that narrow-band antennas offer high energy conversion efficiencies but can only retrieve a limited amount of energy. On the other hand, wide-band or multi-band frequency antennas can retrieve more RF energy in space. However, the tradeoffs are low overall efficiency and large aperture. In [32], antennas with a resonance frequency of 4.9 and 5.9 GHz were designed with PCEs of 65.2 and 64.8%, respectively. Further work by Lu et al. [26] on polarization antennas supports the assertion that expanding the bandwidth of an antenna leads to increasing the amount of power harvested. In this work, the demonstration of broadband polarization antennas with three separate modes allows the antenna to operate in a wider range of frequencies. One common mechanism in the aforementioned works is the control of the antenna configuration by switching the diodes on and off, thus altering its resonant frequencies. However, since it uses separate modes for different frequencies, this antenna is not able to simultaneously resonate at two frequencies. On the other hand, the antenna presented in [39] is capable of operating at 2.45 and 5.8 GHz, simultaneously, providing 2.6 V output with a PCE of 65% and power density of 10 mW/cm^2.

The main purpose of aligning antennas in arrays is to enhance the antenna gain and obtain high voltage/current. Array antennas are preferred over large aperture antennas because they do not require large breakdown voltage diodes to operate. Antenna arrays can be connected before or after rectification. The first configuration enhances the retrieved power at the main beam while the second configuration expands the ability to retrieve power from various angles away from the main beam [40]. In case the RF waves are combined before rectification, the rectifier requires a large breakdown diode. If RF waves are combined after rectification, combining DC current becomes problematic. Antenna arrays can be connected in series or parallel to obtain high voltage or large current. Nonetheless, expanding the arrays yields better output but this might cause a deduction in conversion efficiency [33].

For demonstrating antenna arrays, Sun et al. [35] invented a T-junction to connect four quasi-Yagi antennas together. The advancement in this work was that the T-junction was flexible in changing from 1 × 4 array to 2 × 2 array topologies. Consequently, the system was able to operate at an ambient power level as low as 455 μW/cm^2 while obtaining 40% PCE.

Impedance matching network

In low-power consumption electrical systems, power leakage during transmission may lead to energy insufficiency. In these circumstances, adding an impedance matching network (IMN) ensures that the maximum power transfers between the RF source and load. For WPH applications, the receiving antenna is considered as the source while the rectifier/voltage multiplier is considered as the load. It is acknowledged that in DC, power transfer is optimum when the resistances of the source and load are indistinguishable. In an RF circuit, the impedance is referred to instead of resistance. An impedance mismatch between the source and load creates reflected power flow in the circuit that lowers the efficiency of the system. As its name indicates, the IMN ensures that the impedance of the source and load are identical by adding reactive components in between.

There are three basics matching configurations i.e. L, T and π matching networks (Fig. 5). The L matching is commonly used since it typically has two components, which simplifies the designing and controlling process. Additionally, the L matching networks do not alter the quality factor (Q) of the circuit.



Fig. 5

Configuration of common impedance matching networks

The T and π matching configurations are more complex than the L network. Furthermore, organizing the T and π configurations into multiple stages will retain the final matching results but will change the Q factor. This strategy is useful in improving voltage boost.

There are tradeoffs between the attributes of an IMN, which include frequency, bandwidth, adjustability, and complexity. For instant, in [41], the suboptimal impedance matching and multiport ladder matching methods were introduced to enhance the matching performance and harvested power of antennas, respectively. However, the tradeoff was that implementation of these configurations required more components than traditional matching networks, thus, escalating the circuit's complexity.

Etor et al. [42] designed an IMN for THz frequencies applications using transmission lines and self-designed metal–insulator-metal diodes instead of lumped components. Moreover, fixed IMN and tunable IMN [43, 44, 45] were introduced as a technique for better matching with wide-band and multi-band antennas.

Rectifier/voltage multiplier

RF energy extracted from free space usually possesses low power density since the electric field power density decreases at the rate of $1/d^2$, where d is the distance from the RF source [46]. Therefore, a power amplifier circuit is required that yields enough DC energy from the electromagnetic waves to drive the loads. This gives rise to two possibilities, if the power consumption of the load is lower than the average power harvesting, the electronic devices at the load may work continuously; otherwise, if the load consumes more energy than the power harvesting circuit can generate, the devices cannot work continuously [47].

Rectifying is the most popular application of diodes, which refers to the conversion of AC current to DC current. In terms of power harvesting application, the RF signal retrieved in the antenna has a sinusoidal waveform. The signal after transformation through IMN would be rectified and boosted to meet the power requirements of the application.

The most fundamental topology of the rectifier is the half-wave rectifier that comprises of a single diode D1 (Fig. 6a). When AC voltage transfers through D1, only the positive cycle remains and the negative cycle is cutoff; thus, it diminishes half of the AC power. Moreover, the output V_{out} is discontinuous since the negative cycle is cutoff. Despite its simplicity, a half-wave rectifier is usually inadequate for common applications. Hence, a full-wave rectifier is more preferable. The circuit design of the full-wave rectifier is shown in Fig. 6b. During the first negative cycle of AC input, diode D1 is conductive and capacitor C1 is charged to the corresponding energy level of V_{peak} of the input. Then, at the next positive cycle, diode D1 is blocked, diode D2 is conductive so that capacitor C2 is also charged. In consequence, the output V_{out} would see two capacitors in series (each one is storing a voltage of $V_{peak)}$. Thus, V_{out} is twice V_{peak}. Therefore, this topology is more stable and efficient than the half-wave rectifier. There is also a bridge rectifier that rectifies both positive and negative cycles of the AC input but retains $V_{out} = V_{peak}$ by alternatively blocking pairs of diodes D1, D4 and D2, D3 (Fig. 6c).


D1
+Vpeak
0
-Vpeak
Vin
C1
Vout
+Vpeak
0
-Vpeak
a Half-wave
C1
D2
+Vpeak
0
-Vpeak
Vin
D1
C2
Vout
+ 2xVpeak
0
- 2xVpeak
b Full-wave
D1
D2
+Vpeak
0
-Vpeak
Vin
D3
D4
Vout
+Vpeak
0
-Vpeak
c Bridge

Fig. 6

Some common topologies of a rectifier

Voltage multiplier is a special type of rectifier circuit that converts and boosts AC input to DC output. In some case where the rectified power is inadequate for the application, there is a need for boosting the output DC by stacking single rectifiers into series, forming the voltage multiplier [48]. Several configurations of the voltage multiplier are shown in Fig. 7. The most fundamental configuration is the Cockcroft–Walton voltage multiplier (Fig. 7a). This circuit's operational principle is similar to the full-wave rectifier (Fig. 6b) but has more stages for higher voltage gain. The Dickson multiplier in Fig. 7b is a modification of Cockcroft–Walton's configuration with stage capacitors being shunted to reduce parasitic effects. Thus, the Dickson multiplier is preferable for small voltage applications. However, it is challenging to obtain high PCE due to the high threshold voltage among diodes creating leakage current, thus reducing the overall efficiency. Additionally, for high resistance loads, output voltage drops drastically leading to low current supply to the load. A summary of recent works related to voltage multiplier is shown in Table 3.


C1
C3
Vin
D1
D2
D3
Vout
C2
a Cockcroft-Walton
C1
C3
Vin
D1
D2
D3
D4
C2
C4
Vout
b Dickson
C1
C2
C3
C4
Vout
Vin
c Dickson charge pump
C1
M1
M2
C3
M5
M6
Vin
Vout
M3
C2
M4
M7
C4
M8
Stage 1
Stage 2
d Differential drive voltage multiplier

Fig. 7

Common voltage multiplier configurations: **a** Three stages Cockcroft–Walton voltage multiplier, **b** Four stages Dickson voltage multiplier, **c** Four stage Dickson voltage multiplier using CMOS technology, **d** Two stages voltage multiplier comprised of differential drive unit

Table 3

Published work comparison regarding voltage multiplier

Ref.	Rectifier topology	No. of stage	Freq. (MHz)	Tech.	Range (dBm)	Maximum PCE	Size
[51]	Differential	2	433	0.18 µm CMOS	0–20	74% @ 2 dBm	–
[52]	PMOS transistors	7	900	40 nm CMOS	–	44% @ > 390 mV	0.04 mm^2
[53]	Half-wave	4	900	0.18 µm CMOS	–	37.42% @ 390 mV	–
[54]	Comparator-based/active-diode	3	13.56	0.18 µm CMOS	8–15	67.9% @ 12.8 dBm	–
[55]	Dickson	3	13.56	250 nm CMOS	–	72%	0.13 mm^2
[56]	–	–	915	0.13 µm CMOS	−21.6	22.6% @ −16.8 dBm	0.186 mm^2

Prototyping Methods

There's more on this in Scherz, *Practical Electronics for Inventors.*

Solderless Breadboard or **Plugboard**



This is what we've been using in lab.

Advantages

- Very fast to build and make changes.
- Works well with DIP ICs

Disadvantages

- Limited reliability—lab testing only, for limited-size circuits.
- High capacitance between adjacent rows (~ 10 pF).
- Only for small-lead-size components (.032" or 0.82 mm max—a 1 A diode lead is just barely too big to meet the spec.)

Springboard

Used in ENGS 22

Advantages

- Fast to build and make changes.
- Accomodates large wire sizes.
- Secure, reliable connections.
- Can handle higher current/power.

Disadvantages

- Can't accommodate small lead spacings such as on ICs.
- Although it is reliable enough for long-term use, it's expensive for that purpose.

Wirewrap





Connections made by fine wire wrapped tightly around square pins of special IC sockets. This is a great way to make a permanent version of a digital circuit almost as quickly as using a solderless breadboard. Used in ENGS 31.

Advantages

- Fast to build and make changes.
- Can make a complex circuit compact.
- Reliable.
- Can be used permanently.
- Inexpensive.

Disadvantages

- Low current—limited to under a few hundred mA.
- High inductance/resistance—on the order of 0.1 ohm, 0.25 µH per foot.
- Only makes reliable connections to square leads (as are on wire-wrap IC sockets). Discrete components (e.g., resistors, capacitors, transistors) need to be soldered to a "header" that goes in an IC socket or to individual wire-wrap pins.

Perfboard and Solder.



Using the same perfboard as used in wire-wrap work, it is possible to simply twist and solder leads, and run wires where needed.

Advantages

- Reliable, if done well.
- Can be used permanently.
- Inexpensive.
- Can handle any size components
- Convenient for working with discrete components.

Disadvantages

- Slow, requires skill to do well.
- Works for ICs, but not very easily.

Variations:

- Perfboard with individual copper pads on each hole so that the solder will better hold things in place. (Photo below)
- Perfboard with a perforated ground plane. Provides the shielding and grounding benefits of a ground plane, and makes ground connections easy, but requires care to avoid shorts. Some have the ground plane etched from around the holes; others require you to cut the copper away from the holes with a special tool. This is also possible with wire-wrap, as in the photo in that section.





Generic Printed-Circuit Board—multiple hole-per-pad.



A printed circuit board with a pattern of holes and connections similar to a solderless breadboard.

Advantages

- Easier than using plain perfboard, especially for ICs.
- Reliable.
- Can be used permanently.
- Available with ground planes if needed.

Disadvantages

- Usually not as compact a final circuit as some alternatives, because you are constrained by layout.
- Pads bigger than needed can add capacitance, but not much.
- Can be expensive, especially the "vectorboard" brand.
- Sometimes awkward for odd sized or large components.





“Dead Bug,” or “Ugly-board”



Start with a plain copper-clad board. Glue ICs down with the leads sticking up in the air. Then solder to them

Advantages

- Provides an excellent ground plane. Can be a high performance way to build sensitive and/or high-frequency analog circuits
- Can make a complex circuit compact.
- Reliable.
- Can be used permanently.
- Inexpensive.

Disadvantages

- Requires high soldering skill.
- Takes a long time to build.
- Mechanical support for components is marginal; can add glue (“RTV”) after debugging.
- Only makes reliable connections to square leads (as are on wire-wrap IC sockets). Other components (e.g., resistors, capacitors, transistors) need to be soldered to a “header” that goes in an IC socket or to individual wire-wrap pins.



Variations:

- Manually cut the board with a dremel tool to isolate sections for purposes other than ground plane (use the back for ground plane). See photo below.
- Glue on little rectangles of cut-out board to add power busses, etc.



Printed circuit board (PCB)



This is what is used virtually universally in production of electronics.

Advantages

- Easy to build in production.
- Repeatable, controllable stray L, C.
- Can handle virtually any component, power level.
- Highly reliable.
- Can make very compact.
- Design can be (somewhat) automated from a schematic you have entered.

Disadvantages

- Laying out the board and getting it fabricated takes time, although you can pay for fabrication in a few days if you can afford it.
- Expensive, on the order of hundreds of dollars for one, but with almost no increase in cost to make many.
- Hard to make changes, but making changes may be easier than building another type of prototype.



Notes on surface-mount components

Most modern production designs now use surface-mount components instead of “through hole” components. The circuits can be more compact, and the board layout is easier because different things can be done on each side (and in additional layers between sides) without through-holes interfering. But prototyping gets much more difficult!





Prototyping options for surface mount

- Simulate, and then lay out a PCB. Don’t ever make a breadboard.
- Order DIP ICs and leaded passives for the prototype, and then switch to surface mount for production.
- Get adaptors that have pads to solder surface-mount ICs to, and then standard-spacing (0.1”) pins in DIP or SIP layout. Digikey carries “surfboards” made by Capital Advanced Technologies, and adaptors made by Aries Electronics. In addition to DIP and SIP adaptors, there are boards with solder pads for connecting larger wires; these work well for prototypes built in “dead bug” style.







Crystal receiver set 11

Back to the index

This receiver has a single tuned circuit, the Q factor of the tuned circuit is quite low.
The receiver can be used well for reception of local stations, for reception of distant stations it is less suitable.

I tried to give this receiver a nice "old-fashioned" look, the reception performance was in this design of less importance.
This receiver is for sale, I made a series production of these, and will build more on request.
This receiver is also for sale as do-it-yourself kit.
See the shop for more information.



The front panel of the receiver.
On the left side the socket for the headphone.
In the middle the tuning knob.
On the right the connections for antenna (upper) and ground (lower).



Top view of the receiver.

Circuit diagram of receiver set 11



Circuit description.
The resonance circuit is formed by coil L1 and C1b and C1c (together 1000 pF).
Capacitor C1a and C2 provide the matching between antenna and tuned circuit.
The frame (rotor) of the tuning capacitor is carrying the RF signal, by this it is possible to tune simultaneously the tuned circuit (C1b and C1c) and the antenna matching (C1a).
Germanium diode D1 provides the signal detection.
Transformer TR1 is loaded with 16 Ω at its 4 Ω output, through this the input impedance increases from 16 kΩ to about 43 kΩ.
At the output a headphone of 2x 32 Ω can be connected, with the two speakers parallel, the impedance is 16 Ω.

Component A1 is a *gas discharge tube* (also called: *surge arrester*) with type number: N81-A90X.
The gas discharge tube protects the antenna input for too high voltages.

These high voltages can occur if the antenna picks up static charge from the air (especially occurs with long outdoor antennas from non insulated antenna wire).
As the voltage at the antenna is higher then 90 Volt, the gas discharge tube will start to conduct and short the high voltage to ground.
As soon as the charge has flown to ground, the conduction stops automatically.

Frequency range of the receiver.
Frequency range without antenna: 500 - 2500 kHz.
Frequency range with 10 meter antenna connected: 487 - 1860 kHz.
Both with and without antenna connected, the whole medium wave band can be tuned.

Q factor of the LC circuit (Without antenna and without diode connected):
600 kHz: Q= 83
900 kHz: Q= 81
1200 kHz: Q= 75
1500 kHz: Q= 65
The circuit Q is rather low, one reason for this is because the RF signal is in this design on the frame of the tuning capacitor.
Because the frame of the tuning capacitor is directly connected to the wooden bottom plate losses occur here.

You can find a complete building instruction op the following pages:

Step 1 Preparing the components

Step 2 Making the frame of the receiver

Step 3 Making the coil

Step 4 Placing the components

You will find here the part list of this receiver.




TR 10.16
Ω 4Ω 8Ω 16Ω

Back to the index

How to make a batteryless (crystal set) radio

By **Sagar Sapkota** - July 21, 2012

CRYSTAL SET

The simplest radio receiver, known as a Crystal Set, consists of nothing more than a coil, tuning capacitor, diode detector, and a pair of earphones. A typical circuit diagram for a Crystal Set Radio is given below where inductor or coil L1 is tuned by variable capacitor VC1 to the transmitter frequency. Diode D1 demodulates the signal, which is fed straight to the earphones. There is no amplification.


LONG WIRE AERIAL: AT LEAST
20 METRES (60 FT) OF WIRE
LOCATED 7 METRES (20 FT)
ABOVE THE GROUND
D1
OA47
a
k
OA47
a
k
L1
100t
26 S.W.G.
(25 A.W.G.)
VC1
5p TO
140p
RX
TO CRYSTAL
EARPIECE
C1
10n
RX 4k7. ONLY REQUIRED
IF SET CONNECTED TO
HEADPHONE AMPLIFIER
EFFECTIVE EARTH
(SEE TEXT)

CLICK HERE FOR BIGGER PHOTO

** You can use 1N34 Germanium diode in place of OA47*

A long (at least 20 metres), high (17 metres or more) aerial and a good earth (a buried biscuit tin or a metre of copper pipe driven into damp ground) are required in order to ensure audible headphone reception. The earphones originally used with these receivers had an impedance of around 4000 ohms and were very sensitive (and heavy and uncomfortable). They are no longer available, but a crystal earpiece, which relies on the piezoelectric effect, will give acceptable results.

Low impedance "Walkman" type earphones are NOT suitable.

Component details:

Resistor- RX-4.7k, 0.25 W- only required if set is connect to audio amplifier

Capacitors- C1- 10nF disc ceramic VC1- 5p to 140p, polythene dielectric variable capacitor.

Semiconductors: D1: OA47 or 1N34- Germanium Diode

Miscellaneous: L1- Ferrite Rod, 100mm(4 inch)x9mm/10mm dia., with coil.

Crystal earpiece and jack socket to suit; plastic control knob; plastic insulated flexible cable for aerial wire, downlead and earth connection, 30 meters minimum; buried biscuit tin or 1 meter of copper pipe for earth system; 50gm reel of 26SWG enamelled copper wire, for tuning coil; card and glue for coil former; multistrand connecting wire; crocodile clips or terminals for aerial and earth lead connection; solder, etc.

READ MY EXPERIENCES- HOW EASILY I MADE A BATTERYLESS RADIO

DRAWBACKS

Quite apart from the absence of amplification, two factors seriously limit the performance of crystal receivers. Germanium diodes become increasingly reluctant to conduct as the applied voltage falls below 0.2V, and this makes the receiver insensitive to weak signals. Silicon diodes have a threshold of around 0.6V, and are, therefore, unsuitable for circuits of this kind.

** Silicon diodes like 1N4001 are not suitable*

The earphone loading imposes heavy damping on the tuned circuit, hence, reduces its ability to separate signals. With such low selectivity insensitivity can be a blessing, and crystal sets are normally only capable of receiving a single, strong transmission on the long and medium wavebands. They will sometimes receive more than one if a shortwave coil is fitted.

The aerial and diode can be connected to tappings on the tuning coil in order to reduce damping, but the improvement in selectivity is usually at the expense of audio output. When valves cost a week's wages and had to be powered by large dry batteries and lead/acid accumulators, the construction of simple receivers of this kind could be justified. With high performance transistors now costing only a few pence or cents, crystal sets are now regarded as 'nostalgic pieces". Some readers may, however, wish to build one out of curiosity, or for the novelty of having a receiver that **does not require a power supply.**

CIRCUIT DETAILS

Ferrite loop aerial L1 and polythene dielectric variable capacitor VC1 form the tuned circuit. Point contact germanium diode D1 (1N34 or OA47) demodulates the signal; capacitor C1 bypasses residual r.f. (radio frequency) to earth and also exhibits a reservoir action, enabling the a.f. (audio frequency) output to approach its peak value. The recovered audio signal is fed directly to a crystal earpiece. Signal voltages introduced in the ferrite loop aerial by the radiated magnetic field are much too much to produce an output from the detector, and the component is used here simply as a tuning coil. The ferrite core does, however, reduce the number of turns required for the coil winding, thereby reducing its resistance and increasing its audio quality.


TO AERIAL, AT LEAST 20 METRES (60FT) OF WIRE MOUNTED 7 METRES (20FT) MINIMUM ABOVE THE GROUND
CRYSTAL EARPIECE
DIODE LOAD RESISTOR, RX, IS ONLY REQUIRED IF CRYSTAL RECEIVER IS CONNECTED TO HEADPHONE AMPLIFIER.
D1
a
k
L1
100t
L1
26 S.W.G.
(25 A.W.G.)
A
VC1
G
O
C1
RX
JACK PLUG AND SOCKET
TO EARTH, BISCUIT TIN OR 1M COPPER PIPE IN DAMP GROUND. CONNECTION TO CENTRAL HEATING PIPEWORK WILL OFTEN SUFFICE.

GET BIGGER PICTURE



COIL DETAILS

Full construction and winding details for the ferrite tuning/ aerial coil L1 are shown in figure.

The coil is made from 26 SWG(25 AWG) enamelled copper wire, close wound on a cardboard former.


100 TURNS OF 26SWG (25AWG)
ENAMELLED COPPER WIRE,
CLOSE WOUND
9mm ($^{3}/_{8}$in)
DIAMETER x
100mm (4in)
FERRITE ROD
ENDS OF WINDING
SECURED BY
NARROW STRIPS OF
MASKING TAPE
THIN CARD ROLLED AROUND ROD TO
MAKE A FORMER 60mm (2$^{3}/_{8}$IN) LONG BY
13mm ($^{1}/_{2}$in) DIAMETER. APPLY GLUE TO
CARD WHILST ROLLING.

The r.f. bypass capacitor C1 can in practice, be omitted with no noticeable reduction in performance. However, if the set is to be connected to either the headphone amplifier or speaker amplifier decribed next month, the component together with diode, load resistor, RX, must be included.

AMPLIFICATION Audio frequency amplification, after the diode detector will permit the use of low impedance Walkman type earphones or even loud speaker operation. It will do nothing, however, to overcome the diode’s insensitivity to weak signals. For this we must have radio frequency amplification of the signals picked up by the aerial before they reach the detector(The standard circuit for a transistor portable receiver has three stages of radio frequency amplification ahead of the diode).

For amplification, you can use a simple audio amplifier using LM386.

READ MY EXPERIENCES ON MAKING A BATTERYLESS RADIO

WATCH THESE VIDEOS:

- **JLCPCB: Prototype 10 PCBs for $2 (2-layer,100*100mm)**
- **China's Largest PCB Prototype Manufacturer, 290,000+ Customers & 8,000+ Online Orders Per Day**
- **PCB Pricing: https://jlcpcb.com/quote**

ResearchGate

See discussions, stats, and author profiles for this publication at: https://www.researchgate.net/publication/271597499

Fully printed flexible and disposable wireless cyclic voltammetry tag

Article *in* Scientific Reports · January 2015

DOI: 10.1038/srep08105 · Source: PubMed

CITATIONS
21

READS
121

11 authors, including:

Jinsoo Noh
Gumi Electronics and Information Technolog…
22 PUBLICATIONS **641** CITATIONS

SEE PROFILE

Myoungho Pyo
Sunchon National University
96 PUBLICATIONS **1,319** CITATIONS

SEE PROFILE

Ali Javey
University of California, Berkeley
296 PUBLICATIONS **22,530** CITATIONS

SEE PROFILE

Gyoujin Cho
Sunchon National University
95 PUBLICATIONS **2,833** CITATIONS

SEE PROFILE

Some of the authors of this publication are also working on these related projects:

Project

Electrochemistry View project

All content following this page was uploaded by Gyoujin Cho on 02 February 2015.

The user has requested enhancement of the downloaded file.

SCIENTIFIC REPORTS

OPEN

SUBJECT AREAS:

ENVIRONMENTAL MONITORING

ELECTRICAL AND ELECTRONIC ENGINEERING

Received
22 October 2014

Accepted
6 January 2015

Published
29 January 2015

Correspondence and requests for materials should be addressed to G.C. (gcho@sunchon.ac.kr)

Fully printed flexible and disposable wireless cyclic voltammetry tag

Younsu Jung[1], Hyejin Park[1], Jin-Ah Park[1], Jinsoo Noh[1], Yunchang Choi[1], Minhoon Jung[2], Kyunghwan Jung[2], Myungho Pyo[1], Kevin Chen[3], Ali Javey[3] & Gyoujin Cho[1]

[1]Department of Printed Electronics Engineering, Sunchon National University, Maegok, Sunchon, Jeonnam 540-742 Korea, [2]Research Institute of Printed Electronics, PARU Co. Seomyeon, Sunchon, Jeonnam 540-813 Korea, [3]Electrical Engineering and Computer Sciences, University of California, Berkeley, CA 94720.

A disposable cyclic voltammetry (CV) tag is printed on a plastic film by integrating wireless power transmitter, polarized triangle wave generator, electrochemical cell and signage through a scalable gravure printing method. By proximity of 13.56 MHz RF reader, the printed CV tag generates 320 mHz of triangular sweep wave from +500 mV to −500 mV which enable to scan a printed electrochemical cell in the CV tag. By simply dropping any specimen solution on the electrochemical cell in the CV tag, the presence of solutes in the solution can be detected and shown on the signage of the CV tag in five sec. 10 mM of N,N,N′,N′-tetramethyl-p-phenylenediamine (TMPD) was used as a standard solute to prove the working concept of fully printed disposable wireless CV tag. Within five seconds, we can wirelessly diagnose the presence of TMPD in the solution using the CV tag in the proximity of the 13.56 MHz RF reader. This fully printed and wirelessly operated flexible CV tag is the first of its kind and marks the path for the utilization of inexpensive and disposable wireless electrochemical sensor systems for initial diagnose hazardous chemicals and biological molecules to improve public hygiene and health.

Cyclic voltammetry (CV) has been used as a powerful tool for the study of electrochemical redox reactions between the electrodes and the solutions of all kind of solutes such as metals[1], organic molecules[2], proteins[3], bacteria[4], viruses[5], and DNA[6]. Because of the high sensitivity of the electron transfer redox reactions, CV could become a very promising ubiquitous electrochemical sensor protocol if the cost and size of the CV system were significantly reduced to commercially viable single-use disposable units for checking traces of hazardous materials such as lead[7], mercury[8], arsenic[9], e-*coli*[10], and pesticides[11] in water or to diagnose the level of glucose[12], cholesterol[13] and specific enzymes[14] in blood. This single-use disposable CV would dramatically reduce the cost of maintaining the public health system[15]. Therefore, inexpensive and disposable CV measurement system that can be operated wirelessly using a smartphone or RF (radio frequency) reader without complicate operation processes is in high demand for the realization of an ubiquitous sensor network system (Figure 1a). They would mainly be used as ubiquitous diagnostic and testing tools for detecting and monitoring the level of target specimens. However, there is no technology that is advanced enough yet to build a wireless, inexpensive and disposable CV system. In this paper, as a form of RF-tag, an extremely inexpensive, disposable and fully printed CV system is demonstrated for the first time by mimicking and combining basic CV concepts and wireless power transmission technologies of RF devices. To realize the fully printed CV tag, a key issue of wirelessly generating triangular waveform (±500 mV) that can scan the electrochemical cell at a low frequency (<1 Hz) to set up a redox reaction needs to be addressed through a minimum number of printed thin film transistors (TFTs). Fully printed 13.56 MHz rectenna and a ring oscillator with large trap charges in the channels of printed TFTs were respectively utilized to wirelessly generate triangular waveform by using only 10 printed TFTs.

Results

Based on two key units of the wireless power transmitter (Figure 1b-①) and the triangular wave generator (Figure 1b-②), the circuit layout of the fully printed wireless CV tag was designed by using a minimum number of printed thin film transistors (TFTs) to alleviate the issue of V_{th} shift and shown in Figure 1b as a platform of disposable CV system. The circuit of CV tag was fabricated using all scalable printing methods, a roll-to-roll gravure, a roll-to-plate gravure, a drop casting, and a screen printer (Figure S1 in Supplementary Information).

To provide a polarized DC voltage from the coupled 13.56 MHz AC signal of the reader, we modified our previously reported R2R gravure printed rectenna[16,17], as shown in the layout in Figure 2a and the resulting



Figure 1 | (a) Informative illustration of typical CV system and disposable printed CV tag. (b) Schematic circuit diagram of the gravure printed wireless cyclic voltammetry (CV) tags. The circuit was designed to couple AC power from a 13.56 MHz reader and then convert the coupled AC to polarized DC ±10 V (① in Figure 1b). Polarized DC will operate the printed ring oscillator to generate a triangular voltage waveform (② in Figure 1b). The generated waveform will pass through the buffer to meet the impedance difference from the electrochemical cell (③ in Figure 1b). The electrochemical cell will run the redox reaction with a single drop of specimen solution (④ in Figure 1b) by the voltage triangular waveform. The output current of the electrochemical redox reaction will be amplified *via* an amplifier circuit (⑤ in Figure b) and the signal will pass through the buffer to meet the impedance difference from the printed signage (⑥ in Figure b). The signage will indicate the concentration level of specimen in the solution (⑦ in Figure b). It will indicate whether the concentration is above or below a pre-determined value.

printed diodes and capacitors are shown in Figure 2b. The printed diodes showed a rectifying ratio of 10^3, and capacitances of two printed capacitors were all about 8 nF/cm^2. The polarized DC voltages (Figure 2c) were measured by placing the printed rectenna on the RF (13.56 MHz) reader with a distance of 2 cm. We adapted a center tap transformer, consisted by divided antenna, 2 diodes and 2 capacitors, to provide the + and − DC voltage for printed triangle wave generator. Using a load of 1 MΩ, voltages of +9.4 V and −10.8 V DC were attained for the optimized printed antenna by monitoring the rectified polarized DC voltages and varying the values of the inductance of the antenna (Figure S2 in Supplementary Information). The polarized DC voltage was also decreased with decreasing load's resistance (Figure 2d).

To generate a cyclic waveform with a low frequency (<1 Hz) from the rectified polarized DC voltage, fully gravure printed *p*-type SWNT-based channel network thin film transistors (*cn*TFTs) were used to construct a five stage ring oscillator with *p*-type inverters. The *cn*TFTs can operate under less than 20 V and their mobility range (0.01 to 10 cm^2/Vs) can be controlled through the loading concentration of SWNT in the ink[18–21]. To print the five stage ring oscillator, we used the same silver and $BaTiO_3$ inks as in the printing of the rectenna for reducing a number of printing steps while SWNT ink was used for printing the channel of the *cn*TFTs. To manufacture the ring oscillator, roll-to-plate (R2P) gravure was used to print 10 *cn*TFTs with a gate width of 300 µm and channel length of 160 µm for both the drive and load *cn*TFTs (Figure S3 in Supplementary Information). The optimized cell depth of gravure plate was 37–40 µm with the cell wall thickness of 50–55 µm for the printing active layers of drive and load TFTs using low viscosity of SWNT based ink (~30 cp) (Figure S4 in Supplementary Information). By repeating the printing of active layers on load TFTs, a higher SWNT network density can be achieved to generate higher current in the



Figure 2 | (a) Circuit layout of the printed rectenna to provide polarized DC power, (b) a real image of printed diodes and capacitors, (c) input-output electrical characteristics of the rectifier at 13.56 MHz AC input and (d) output ± DC voltages under variations in load resistance.

channels while thicknesses of all printed gate, dielectric and drain-source electrodes are kept same (Figure S5 in Supplementary Information).

Their output and transfer characteristics are shown in Figure 3a and 3b respectively. Based on the attained transfer characteristics, the mobility (μ), transconductance (g_m), on-off current ratios from I_{DS}-V_{DS} and threshold voltages (V_{th}) for both five drive *cn*TFTs and five load *cn*TFTs were extracted and shown in Table S1 (Supplementary Information). The shift range of V_{th} from the fully gravure printed 10 *cn*TFTs were about ±0.4 V for the drive *cn*TFTs and ±0.6 V for load *cn*TFTs. Those shift ranges are narrow enough to run the printed ring oscillator for generating the triangular wave. Each inverter delivered a gain of 3 (Figure 3c), and the ring oscillator with five inverters generated a pseudo triangular waveform with a voltage amplitude of 7 V at 320 mHz (Figure 3d). In fact, the pseudo triangular wave can be only generated by the printed *cn*TFTs based ring oscillator because of the parasitic and trapped channel capacitances due to carbon nanotube network structures in *cn*TFTs. Although we only showed the frequency of 320 mHz at here, the frequency can be varied from 0.3 Hz to 2 Hz based on the printed network density of SWNT of printed *cn*TFTs. This is an advantage of our printed *cn*TFTs for scanning electrochemical cell in CV tag over other technologies such as amorphous silicon TFTs where only a sine wave with a designed single frequency can be generated because of no trap capacitance in the channel (Figure S6 in Supplementary Information). The frequency of the triangular waveform can be fine-tuned in the range of 0.3 Hz to 2 Hz as shown in the Figure S7 (Supplementary Information) by simply changing loading concentration of SWNTs.

When the generated triangular waveform is supplied directly into the printed electro-chemical cell (Figure S8 in Supplementary Information), wherein printed silver and carbon electrodes were used with a poly(ethylene oxide) and $LiCF_3SO_3$ gel type electrolyte, the output voltage range is reduced to zero because of improper impedance matching between the electrochemical cell (10 KΩ) and ring oscillator (1 MΩ). Therefore, a buffer unit is needed to match the impedance levels between the ring oscillator and electrochemical cell. The printed buffer unit (Figure 1b-③) with high on currents and low on-off current ratios (Figure 3e) is consists of 6 *cn*TFTs and a resistor (~7 KΩ). In the printed CV tag, three resistors were printed by screen printer using a carbon paste (DC-20, purchased from Dozen Co. Korea) for the buffer units (Figure 1b-③ and ⑥) and the electrochemical cell (Figure 1b-④). Their electrical parameters are listed in Table S1 (Supplementary Information). The 6 *cn*TFTs of buffer unit were printed using R2P gravure with high SWNT concentration in the semiconducting ink. Each *cn*TFTs exhibited on-currents in the range of 400 ~ 500 μA with a very low on-off ratio due to the enhanced metallic percolation in the dense SWNT networks. The buffer units with low on-off ratio were employed to reduce the input voltage to ±500 mV (Figure 3f) which is the appropriate scanning range of the electrochemical cell. The printed electrochemical cell with two electrodes was proven to be well operated under commercial CV (Figure S9 in Supplementary Information). The resulting current after scanning printed electrochemical cell in the CV tag can be converted to voltage by connecting the printed resistor (Figure 1b-④: ~5 × 10^3 ohm) which provides the output voltage for electrochromic indicator and re-plotted into the cyclic voltammogram.

Because these output voltage (±70 mV) and current (~40 μA) were low after scanning the electrochemical cell, they need to be amplified to turn on the electrochromic indicator for showing predetermined concentration (10 mM) level of N,N,N′,N′-tetramethyl-p-phenylenediamine (TMPD, purchased from Aldrich) as a standard reference in this work (Figure 3g). After running the redox reaction of TMPD (Figure 3h) in the printed cell, the output voltage and current needed to be amplified to reach 1.5 V and 500 μA, respectively, to provide sufficient power to display the letters "PE" as an indicator of the presence of TMPD in the specimen. To construct the amplifier, *cn*TFTs based three inverters were printed with a gain of three to five (Figure S10 in Supplementary Information) to amplify the output signal as shown in Figure 3i. The electrical characteristics of the 6 *cn*TFTs in the inverters with extracted mobility, transcon-



Figure 3 | (a and b) Output and transfer characteristics of the printed *cn*TFTs for 5 drive and 5 load TFTs respectively in the printed ring oscillator. (c) Electrical characteristics of inverters and (d) output characteristic of the ring oscillator. (e) Total output characteristics of the printed buffer unit consisting of 6 *cn*TFTs and a resistor (measured based on contacting gate and drain-source electrodes as shown in the inset circuit). (f) Modified triangular wave following the buffer unit. (g) Generated signals before scanning (black) and after scanning the electrochemical cells without (1, blue) and with TMPD (2, red) in a drop of solution. (h) TMPD structure for oxidation and reduction reaction. (i) The input and amplified output signals after passing through three amplifying inverters.

ductance, on-off current ratios and threshold voltage are shown in Table S2 (Supplementary Information). As the impedance was matched between the ring oscillator and the electrochemical cell using the buffer unit, another buffer unit (Figure 1b-⑥) is also needed between the electrochromic signage (20 KΩ) and the amplifier (1 MΩ) for impedance matching. The electrical parameters of the buffer are listed in Table S2 (Supplementary Information).

The amplified output signal was used to run the reduction and oxidation of the patterned conducting polymer in the electrochromic signage, and thus the blinking signage will be used to indicate the presence of chemicals in the specimens. The signage was fully printed and attached on printed CV tag. A clear concept of the printing sequence for the electrochromic signage was given in Figure S11 in Supplementary Information.

Discussion

The fully printed flexible CV tag was completed by assembling the printed circuits including ring oscillator, buffer, electrochemical cell, amplifier, and signage onto the previously R2R gravure printed rectenna. The resultant CV tag is shown in Figure 4a. The working concept of the wireless and flexible CV tag is demonstrated in the following sequences (watch the video file by clicking Figure S12 in Supplementary Information). After dropping 500 µl of TMPD solution (10 mM) on the printed electrochemical cell, the CV tag was placed on the custom made RF (13.56 MHz) reader (Figure S13 in Supplementary Information). The antenna was subsequently coupled to 13.56 MHz AC. The coupled AC was rectified into polarized DC (> ± 10 V) through two diodes and two capacitors which caused the ring oscillator to generate a pseudo triangular waveform with output voltage of 7 V at 320 mHz. This was then passed through the buffer unit to scan the electrochemical cell. The output signal after scanning the electrochemical cell was amplified to turn on the signage according to the concentration level of TMPD in the solution. In this work, whenever the concentration of TMPD was higher than 10 mM, the signage "PE" blinked (Figure 4b) while it did not show anything (Figure 4c) when it was lower than 10 mM. Furthermore, clear cyclic voltammograms for scanning the electrochemical cell with and without 10 mM of TMPD were obtained by re-plotting the output triangular voltage waveform (Figure 4d). The attained half potential ($E_{1/2}$ ~ 0.05 V, oxidation potential is 0.22 V and reduction potential is −0.17 V) of TMPD from the CV tag was nearly identical to the value obtained from a commercial CV instrument, SP-240, Biologic, which uses the same frequency for the triangular voltage waveform and printed electrochemical cell (Figure 4e). However, when the generated triangle wave frequency is higher than 0.6 Hz in the CV tag, the clear redox peaks cannot be



Figure 4 | (a) Optical image of fully printed wireless cyclic voltammetry tag. (b) Operation images of CV tag with and (c) without TMPD in the solution on 13.56 MHz reader. (d) Converted cyclic voltammogram from the printed wireless CV tag *vs* (e) a commercial CV instrument (please refer the interconnected video file for the demonstration of wireless CV tag operation in Figure S12 in Supplementary Information).

observed as shown in Figure S14 (Supplementary Information). Furthermore, as a typical example of testing a specimen in aqueous solution, 10 mM of $K_3(FeCN)_6$ aqueous solution was checked using the CV tag, and results of converted cyclic voltammogram was shown in Figure S15 (Supplementary Information). Those results support that the CV tag can examine specimens not only in organic solution, but also in aqueous one.

Up to present, there has been no commercial success in fully printed TFT-based electronic devices due to some kind of difficulties in integrating a number of printed TFTs through a scalable printing method. As increasing a number of integrated TFTs, the range of threshold voltage shits of TFTs needs to be controlled as narrow as possible to properly operate designed function of printed devices. However, the scalable printing method is not fully understood to integrate a number of TFTs on plastic foils while keeping the constant range of threshold voltage shifts because of difficulty in controlling a constant charge transport through the printed channels. Therefore, the printed TFT-based devices should be constructed by using a minimum number of printed TFTs while a function of printed device needs to be competitive over Si based one. Since the fully printed CV tag required the integration of only 26 *cn*TFTs, the acceptable range of threshold voltage shits of *cn*TFTs is controllable and achievable by using a scalable printing method such as a roll-to-roll gravure. Furthermore, the unique function of printed CV tags cannot be simply reproduced using a Si technology with a comparable cost to the R2R printing process. Therefore, the fully printed CV tag will be the first leading model to show a way of how printed TFT-based electronic devices should go for the successful launching in the IT markets.

In the core of the printed CV tag, fully gravure-printed *cn*TFTs were employed for constructing a circuit consisting of a ring oscillator to generate triangular waveforms, buffer units for an impedance matching, and an amplifier for enhancing output signal to turn on the signage. Those simple units can be combined with a variety of printable sensors and RF devices to create novel devices with an extremely low cost. In other words, the printed rectenna, ring oscillator, buffer and amplifier units in the printed CV tag will be key elements for the construction of variety of printed RF-sensors, this CV tag will be used as a platform for the further construction of a variety of RF based electrochemical sensors.

In conclusion, we have presented a fully printed flexible CV tag with the size of 9.5 × 5.5 cm^2 that can operate wirelessly using a 13.56 MHz RF reader. However, for the practical purpose, the size of the CV tag can be reduced up to the half (4 × 2 cm^2) of the current one by optimizing spaces between *cn*TFTs in the circuit of the CV tag and reducing the operation power to less than DC 5 V as the current size of 13.56 MHz antenna is designed to provide maximum coupled AC power using a sufficient length of printed antenna pattern (higher inductance). Furthermore, although we utilized R2P gravure, screen printer and drop casting method for the convenience of fabricating the CV tag in the Lab, the whole fabricating process can be repeated by R2R gravure because the rectenna, ring oscillator, buffers, electrochemical cell, amplifier and signage in the CV tag were all designed to compromise the limit (± 20 μm) of a registration accuracy of a current R2R gravure system. Therefore, this technology could be used as a platform for disposable wireless electrochemical sensors to a variety of specimens in aqueous and organic solutions to monitor or diagnose pathogens and hazardous materials by modifying the electrodes of the electrochemical cells.

Methods

Roll-to-roll (R2R) gravure printed antenna, bottom electrodes, gate electrodes and wires. Two color units of R2R gravure system (Taejin Co. Korea: Figure S1 in the Supplementary Information) was employed to print antenna, bottom electrodes and wires on a roll of poly(ethylene terephthalate) (PET) film (width of 200 mm and thickness of 100 μm, purchased from SKC, Korea) with silver nanoparticle based conducting ink (PG-007 BB type, Paru Co. Korea) and the web transfer speed of 8 m/min under roll pressure of 0.5 MPa and web tension of 60 N. The silver ink was further formulated to meet the viscosity of 500 cp and surface tension of 47 mN/m using respectively ethylene glycol (Aldrich) and Dipropylene glycol methyl ether (Aldrich). The curing time of printed silver layer was 10 sec by passing through a heating chamber of 150°C, installed in R2R gravure system. The resulting printed silver patterns on PET roll showed the thickness of 450 (±50) nm without any defects and were shown in Figure S16a (Supplementary Information).

Roll-to-plate (R2P) gravure printed ring oscillator, buffer, and amplifier. Full R2P gravure system (Figure S1 in the Supplementary Information) was employed to print single walled carbon nanotube network based thin film transistors (*cn*TFTs), used as a building block to construct all the integrated circuit of printed cyclic voltammetry (CV) tag (Figure 1). 26 *cn*TFTs for the integration of circuit in printed CV tag were printed on the previously R2R gravure printed film (printed antenna, bottom electrodes and wires with thickness of 450 nm; Figure S16b in Supplementary Information) following printing sequences. First, $BaTiO_3$ nanoparticle based dielectric ink (PD-100, Paru Co., Korea) was further formulated to meet viscosity (75 cP) and surface tension (31.8 mN/m) using the ethyl 2-cynoacrylate (Aldrich). As shown in R2P gravure printing scheme (Figure S17 in Supplementary Information), the homogeneous and defect free dielectric layers were first R2P gravure printed with a printing speed of 200 mm/s and roll pressure 7.5 kg_f on previously printed gate electrodes and bottom electrodes (for capacitors) with a thickness of 2.3 (±0.1) μm and width of 940 (±2) μm (Figure S5 in Supplementary Information). The printed dielectric layers were cured for 1 min 20 sec at 150°C. Second, single walled carbon nanotube (SWNT) based semiconducting ink (PR-040, Paru Co., Korea) was diluted by diethylene glycol monobutyl ether (Daejung Co., Korea) to 1 : 1 volume ratio for printing active layers using R2P gravure on the printed dielectric layers with a printing speed of 350 mm/s and a roll pressure of 4 kg_f. The viscosity and surface tension of diluted SWNT ink were respectively 30 cP and 29 mN/m. The resulting SWNT printed films were dried 1 min at 150°C. For using *cn*TFTs in the buffer unit, we used the dilution volume ratio of 5 : 1 between SWNT ink (PR-040, Paru Co., Korea) and diethylene glycol monobutyl ether for printing only on the TFTs in the buffer unit to increase SWNT network density for providing the high current (Figure S5 in Supplementary Information). Finally, drain-source electrodes were R2P gravure printed using silver nanoparticle based ink (PG-007 AA type, Paru Co., Korea) on SWNT printed film with a viscosity of 800 cP and a surface tension of 42 mN/m. The R2P gravure printing was carried out under a printing speed of 200 mm/s and a role pressure of 5 kg_f.

Diode fabrication. Although Shottky diodes were able to print using R2R gravure based on our previous reported process[16,17], the drop casting method was used for the convenience in this work. First, dropping ZnO based hybrid semiconducting ink (PD-070, Paru Co., Korea) on printed silver electrode and then, Al ink (PA-009, Paru Co., Korea) was dropped on the top of ZnO ink. The resulting diodes were further cured for 5 min at 120°C.

Measurements. Formulated and diluted inks were characterized using DCAT21 (Dataphysics Co., Germany) and SV-10 Vibro viscometer (AND Co., Japan) for respectively measure surface tension and viscosity. All measurements in this work were carried out under ambient condition if there are no other comments. Resistance of printed antenna, bottom electrodes, gate electrodes and wires were measured using two probe methods with HP3457A multimeter. Both surface morphology and thickness of printed layers was characterized using surface profiler (NV-2200, Nanosystem, Korea). LCR meter (E4980A, Agilent, USA), semiconductor parameter analyzer (4155C, Agilent, USA) and digital phosphor oscilloscope (DPO 4054, Tektronix, USA) were respectively used to characterize printed *cn*TFT based circuits.

1. Sanderson, M. D., Kamplain, J. K. & Bielawski, C. W. Quinone-annulated N-heterocyclic carbene-transition-metal complexes: Observation of π-back bonding using FT-IR spectroscopy and cyclic voltammetry. *J. Am. Chem. Soc* **128**, 16514–16515 (2006).
2. Lai, R. Y., Fabrizio, E. F., Lu, L., Jenekhe, S. A. & Bard, A. J. Synthesis, cyclic voltammetrics studies, and electrogenerated chemiluminescence of a new donor-acceptor molecule: 3,7-[Bis[4-phenyl-2-quinolyl]]-10-methylphenothiazine. *J. Am. Chem. Soc* **123**, 9112–9118 (2001).
3. Armstrong, F. A., Hill, H. A. & Walton, N. J. Direct electrochemistry of redox proteins. *Acc. Chem. Res* **21**, 407–413 (1998).
4. Norouzi, P., Ganjali, M. R., Daneshgar, P., Alizadeh, T. & Mohammadi, A. Development of fast Fourier transformation continuous cyclic voltammetry as a highly sensitive detection system for ultra-trace monitoring of penicillin V. *Anal. Biochem* **360**. 175–184 (2007).
5. Koyama, J. *et al.* Correlation of redox potentials and inhibitory effects on Epstein-Barr virus activation of 2-azaanthraquinones. *Cancer Letters* **212**, 1–6 (2004).
6. Teijeiro, C., Perez, P., Marin, D. & Paleček, E. Cyclic voltammetry of mitomycin C and DNA. *Bioelectrochemistry and Bioenergetics* **38**, 77–83 (1995).
7. Zerihun, T. & Gründler, P. Electrically heated cylindrical microelectrodes. Determination of lead on Pt by cyclic voltammetry and cathodic stripping analysis. *J. Electroanal Chem* **415**, 85–88 (1996).
8. Bond, A. M. & Scholz, F. Electrochemical, Thermodynamic, and mechanistic data derived from voltammetric studies on insoluble metallocenes, mercury halide and sulfide compounds, mixed silver halide crystals, and other metal complexes following their mechanical transfer to a graphite electrode. *Langmuir* **7**, 3197–3204 (1991).
9. Brusciotti, F. & Duby, P. Cyclic voltammetry study of arsenic in acidic solutions. *Electrochim Acta* **52**, 6644–6649 (2007).
10. Ruan, C., Yang, L. & Li, Y. Immunobiosensor chips for detection of escherichia coli O157:H7 using electrochemical impedance spectroscopy. *Anal. Chem* **74**, 4814–4820 (2002).
11. Liu, G. & Lin, Y. Electrochmical sensor for orgnohposphate pesticides and nerve agents using zirconia nanoparticles as selective sorbents. *Anal. Chem* **77**, 5894–5901 (2005).
12. Ascaso, J. F. *et al.* Diagnosing insulin resistance by simple quantitative methods in subjects with normal glucose metabolism. *Diabetes Care* **26**, 12, 3320–3325 (2003)
13. Karl, T. *et al.* Human breath isoprene and its relation to blood cholesterol levels: new measurements and modeling. *J. Appl. Physiol* **91**, 762–770 (2001).
14. Armstrong, F. A. Recent developments in dynamic electrochemical studies of adsorbed enzymes and their active sites. *Chem. Biol* **9**, 110–117 (2005).
15. Mollah, M. Y., Schennach, R., Parga, J. R. & Cocke, D. L. Electrocoagulation (EC)-science and applications. *J. Hazard. Mater* **B84**, 29–41 (2001).
16. Park, H. *et al.* Fully roll-to-roll gravure printed rectenna on plastic foils for wireless power transmission at 13.56 MHz. *Nanotech* **23**, 344006–344012 (2012).
17. Kang, H. *et al.* Fully Roll-to-Roll Gravure Printable Wireless (13.56 MHz) Sensor-Signage Tags for Smart Packaging. *Sci. Rep*. **4**, 5387; DOI: 10.1038/srep05387 (2014).
18. Jung, M. *et al.* All-printed and roll-to-roll-printable 13.56 MHz-operated 1-bit RF tag on plastic foils. *IEEE Trans Electron Devices* **57**, 3, 571–580 (2010).
19. Noh, J. *et al.* Integrable single walled carbon nanotube (SWNT) network based thin film transistors using roll-to-roll gravure and inkjet. *Org. Electron* **12**, 2185–5191 (2011).
20. Noh, J. *et al.* Modeling of printed single walled carbon nanotube thin film transistors for attaining optimized clock signals. *J. Appl. Phys* **108**, 10, 102811–102817 (2010).
21. Noh, J. *et al.* Fully Gravure-Printed Flexible Full Adder Using SWNT-Based TFTs. *IEEE. Eletron. Dev. Lett.* **33**, 11, 1574–1576 (2012).

Acknowledgments

The authors would like to thank BK Plus program, Basic Science Research program (NRF-2014R1A1030419), and RIC in Sunchon National University for their financial support. G. C. thanks to Paru Co. for providing all electronic inks in this work.

Author contributions

Y.J., A.J. and G.C. designed the experiments. Y.J., H.P., J.P., Y.C. and M.J. carried out the experiments. J.N., K.J. and K.C. performed device simulations. Y.J. and K.C. performed mobility calculations. Y.J. and M.P. performed electrochemistry and analyzed electrochemical data. Y.J., H.P., M.P., A.J. and G.C. contributed to analyzing the data. M.J., M.P., A.J. and G.C. wrote the paper while all authors provided feedback.

Additional information

Supplementary information accompanies this paper at http://www.nature.com/scientificreports

Competing financial interests: Prof. Cho was a consultant of PARU Co. Korea and received compensation from PARU Co. Both Dr. M. Jung and Mr. K Jung has been employee of PARU Co. Korea. Dr. Y. Jung, Miss H. Park, Ms. J. Park, Dr. J. Noh, Mr. Y. Choi, Prof. Pyo, Mr. K. Chen and Prof. Javey declare no competing financial interests.

How to cite this article: Jung, Y. *et al.* Fully printed flexible and disposable wireless cyclic voltammetry tag. *Sci. Rep.* **5**, 8105; DOI:10.1038/srep08105 (2015).

This work is licensed under a Creative Commons Attribution 4.0 International License. The images or other third party material in this article are included in the article's Creative Commons license, unless indicated otherwise in the credit line; if the material is not included under the Creative Commons license, users will need to obtain permission from the license holder in order to reproduce the material. To view a copy of this license, visit http://creativecommons.org/licenses/by/4.0/

View publication stats

AIP Applied Physics Letters

A microwave metamaterial with integrated power harvesting functionality

Allen M. Hawkes, Alexander R. Katko, and Steven A. Cummer

Citation: Applied Physics Letters **103**, 163901 (2013); doi: 10.1063/1.4824473
View online: http://dx.doi.org/10.1063/1.4824473
View Table of Contents: http://scitation.aip.org/content/aip/journal/apl/103/16?ver=pdfcov
Published by the AIP Publishing

Goodfellow
metals • ceramics • polymers
composites • compounds • glasses
Save 5% • Buy online
70,000 products • Fast shipping
www.goodfellowusa.com

This article is copyrighted as indicated in the abstract. Reuse of AIP content is subject to the terms at: http://scitation.aip.org/termsconditions. Downloaded to IP: 152.3.43.156 On: Fri, 08 Nov 2013 20:28:30

APPLIED PHYSICS LETTERS **103**, 163901 (2013)

A microwave metamaterial with integrated power harvesting functionality

Allen M. Hawkes,[a)] Alexander R. Katko, and Steven A. Cummer
Department of Electrical and Computer Engineering, Duke University, 101 Science Drive, Durham, North Carolina 27708-9976, USA

(Received 30 May 2013; accepted 22 September 2013; published online 14 October 2013)

We present the design and experimental implementation of a power harvesting metamaterial. A maximum of 36.8% of the incident power from a 900 MHz signal is experimentally rectified by an array of metamaterial unit cells. We demonstrate that the maximum harvested power occurs for a resistive load close to 70 Ω in both simulation and experiment. The power harvesting metamaterial is an example of a functional metamaterial that may be suitable for a wide variety of applications that require power delivery to any active components integrated into the metamaterial. © *2013 AIP Publishing LLC*. [http://dx.doi.org/10.1063/1.4824473]

Metamaterials are composed of sub-wavelength particles that exhibit bulk properties that are different from their individual components. Electromagnetic metamaterials are engineered materials that can achieve parameters not possible within naturally occurring materials, such as a negative index of refraction[1] or a zero index of refraction.[2] Exotic properties like these allow for a variety of interesting applications including a superlens device[3] and an invisibility cloak.[4] Integrating active and nonlinear functionality into metamaterials has been demonstrated in the form of dynamic resonant frequency tuning,[5,6] phase conjugation,[7] and wave mixing.[8,9] More specific functional behavior has also been demonstrated in metamaterials, including radio frequency (RF) limiting[10] and harmonic generation.[11]

Metamaterials are also well-suited for other functional behaviors, including electromagnetic power harvesting, the focus of this work. Power harvesting devices convert one type of energy to another, typically converting to a direct current (DC) signal. Many types of energy can be harvested, from acoustic (using a piezoelectric harvester)[12] to electromagnetic (using a rectenna).[13] Power harvesting devices require a method to couple to the energy that will be harvested as well as a device to convert the energy from one form to another. By their very nature, metamaterials are designed to couple to various types of energy, e.g., from acoustic[14] to optical,[15] and thus provide a natural platform for power harvesting. Electromagnetic metamaterials provide flexibility in design due to their electrically small, low-profile nature.[16] Since metamaterials are typically designed as infinite arrays, the resonant frequency and input impedance include coupling effects. Metamaterials can be adapted to various applications, such as flexible sheets to cover surfaces.[17] Moreover, many metamaterials that have been presented in the literature require some form of external signal. This could be a DC bias voltage[18] or a large external pump signal.[7] In general, metamaterials could be modified to harvest such an external signal that is already present for other purposes. With these design advantages, power harvesting metamaterials offer design flexibility for a large number of applications that general antenna-based microwave power harvesting devices may lack.

A recent simulation-based study[19] investigated the conversion efficiency between incident RF power and induced power in a split-ring resonator (SRR). Our work is focused on the experimental measurement of RF to DC efficiency based on the conventional effective area of the SRR. We demonstrate that metamaterials can also include embedded devices to convert the incident RF energy to a DC voltage, providing a platform for power harvesting that utilizes the advantages of metamaterial design.

An SRR is a canonical example of a resonant metamaterial particle and is used as the basis for the unit cells of the metamaterial power harvester designed here. By tuning the SRR parameters, we design an SRR (Fig. 1) to resonate at 900 MHz using an S-parameter simulation within Computer Simulation Technology (CST) Microwave Studio software. Using CST Microwave Studio, we can also simulate the effects of embedding devices within the SRR by retrieving its S-parameters using a lumped port. The retrieved S-parameters are loaded into Agilent Advanced Design System (ADS), allowing us to simulate both fullwave 3D effects and circuit-level nonlinear effects.

An SRR couples strongly to an incident magnetic field and can be loaded with a wide variety of circuit elements. In this work, we embed a rectifying circuit within an SRR to convert the incident RF power to DC power. A number of rectifying circuits could be chosen depending on the particular application for the power harvesting metamaterial. We choose to use a Greinacher[20] circuit because the output voltage is double the input voltage maximum, which allows for



FIG. 1. (Left) Power harvesting SRR. (Right) Plain SRR with dimensions shown, 1 mm traces. Incident wave polarization is also shown.

[a)] allen.hawkes@duke.edu

0003-6951/2013/103(16)/163901/3/$30.00

© 2013 AIP Publishing LLC

This article is copyrighted as indicated in the abstract. Reuse of AIP content is subject to the terms at: http://scitation.aip.org/termsconditions. Downloaded to IP: 152.3.43.156 On: Fri, 08 Nov 2013 20:28:30

easier power transmission and measurement. A Greinacher circuit has a lower effective capacitance in comparison to other rectification circuits (such as a bridge rectifier), allowing faster switching and thus a higher frequency of operation. A Greinacher circuit also has a low threshold voltage, allowing operation at lower incident power levels. A Greinacher voltage doubler can be placed across a gap (Fig. 1) in the top side of the copper trace to rectify the induced current present in the SRR. Schottky diodes are used for the voltage doubler due to their typically low open junction capacitance and fast switching capabilities, which allow for rectification of a high-frequency RF signal, as well as their typically low threshold voltage. A resistive load placed across the output of the voltage doubler is a simple way to determine DC power out using $P = V^2/R$. This DC power is maximized through ADS for matching capacitor and resistor values. The parameters of our selected Schottky diode (HSMS 2862) and the simulated S-parameters of the above SRR in a model of our actual parallel-plate waveguide are input into ADS for the simulation, shown in a schematic in Fig. 2.

The simulated components lead to a maximum efficiency of 61% for an input power of 24.25 dBM, the maximum available experimental power (at an incident power density of approximately 1.6 mW/cm^2). One important figure of merit for a power harvester is its RF-to-DC power conversion efficiency:

$$\eta = \frac{P_{DC}}{P_{RF}}.$$

We determine P_{RF} by measuring the total incident power in our measurement apparatus. For a large metamaterial sample, we assume that the total incident power to the measurement apparatus is incident on the metamaterial. For a single unit cell, it is necessary to use the effective area of the unit cell to determine the incident P_{RF}. The maximum effective area may be calculated by[21]

$$A_{e,max} = \frac{\lambda^2}{4\pi} D_0,$$

where $D_0 = 1.5$ since the SRR is effectively a small loop illuminated by a transverse electromagnetic (TEM) wave. For an SRR resonant at 900 MHz, the effective area is thus $A_{e,max} = 5.3A_{physical}$. The full waveguide area is approximately $6.8A_{physical}$ where $A_{physical}$ is the physical area of a single SRR unit cell. As $A_{e,max}$ is 78% of the open wave guide area, 78% of the incident power density is used as input power for simulation of the single cell.



1. RF signal
2. SRR S-params
3. Matching cap
4. Greinacher doubler
5. Smoothing cap
6. Load

FIG. 2. ADS simulation schematic of SRR power harvester. CST Microwave Studio was used to determine the SRR S-parameters.



FIG. 3. Placement of SRR within open waveguide.

The designed voltage doubler and resistive load are added to an SRR as shown in Fig. 1, resulting in the power harvesting metamaterial unit cell. To observe power harvesting capabilities, the cell is placed in an open, TEM waveguide (Fig. 3) where input power is produced by a signal generator and amplifier, and output power is measured with an oscilloscope via leads placed across the resistive load (Fig. 4). The DC power harvested is determined by $P = V^2/R$ as previously mentioned, and input power is measured with a spectrum analyzer connected to the signal generator and amplifier via the open waveguide. By increasing the incident power from 13 to 24 dBm and measuring the DC output from the SRR, the normalized harvested power, $P_{DC}/P_{RF,incident}$, as a function of incident power $P_{RF,incident}$ and resulting efficiency are determined at each point. The maximum efficiency of the single cell is 14.2%, setting $P_{RF,incident}$ as 78% of the total input power from effective area calculations.

Multiple power harvesting SRR cells are then tested simultaneously to create the power harvesting metamaterial, which is accomplished through a 5 × 1 array shown in Fig. 5. Through a parallel connection of the leads from each SRR's resistive load, the total power harvested by the metamaterial is found in the same way as the single cell. The maximum efficiency for the 5 × 1 array is 36.8%, where P_{in} is the entire input power because the array spans the entire length. Measured efficiencies of both the single and the array of power harvesting SRRs are shown in Fig. 6. Also shown in Fig. 6 is the open circuit voltage, V_{OC}, a load-independent measure of the available voltage harvested by the array of SRRs.

The power harvesting metamaterial array is more efficient than the single unit cell. This is partially due to the



FIG. 4. Experimental test setup schematic.

This article is copyrighted as indicated in the abstract. Reuse of AIP content is subject to the terms at: http://scitation.aip.org/termsconditions. Downloaded to IP: 152.3.43.156 On: Fri, 08 Nov 2013 20:28:30



FIG. 5. 5 × 1 array of power-harvesting SRRs.



FIG. 6. RF to DC efficiency of power harvesters. The open-circuit voltage of the array is also shown.

larger effective area of the array. While the effective area of the single cell is 78% the entire width of the waveguide, some of this power is not harvested by the single unit cell due to fringing effects on the sides of the waveguide. For this reason, placement of multiple cells that together span the entire waveguide width results in a higher efficiency as the array captures more of the electromagnetic energy that undergoes the fringing effect.

Another important relationship is the efficiency of the power harvesting metamaterial as a function of load resistance. Simulated and experimental efficiencies for the 5 × 1 array are shown in Fig. 7. Though the experimental efficiencies do not match the values from simulation, the simulation does accurately predict the maximum harvested power as falling approximately within the range of 70–80 Ω, confirmed by the experimental data. The experimental efficiency maximum occurs at 70 Ω, and the simulated maximum occurs at 82 Ω, showing close correspondence.

In summary, we have designed, simulated, and experimentally measured a functional metamaterial power harvester capable of converting up to 36.8% of the incident RF power to DC power. Through a parallel connection of five SRRs, a V_{OC} of 7.3 V is achieved. Simulations match experimental results showing an optimal resistive load for DC power transfer of 70–80 Ω. The SRR power harvester is an example of functional metamaterial that may be suitable for a wide variety of RF applications that require power delivery to any active integrated components.



FIG. 7. RF to DC efficiency of SRR array as a function of load resistance, for both simulation and experiment. Note that both show maximum efficiency for around 70–80 Ω.

This work was supported by a Multidisciplinary University Research Initiative from the Army Research Office (Contract No. W911NF-09-1-0539).

[1] D. R. Smith, W. J. Padilla, D. C. Vier, S. C. Nemat-Nasser, and S. Schultz, Phys. Rev. Lett. **84**, 4184–4187 (2000).
[2] R. W. Ziolkowski, Phys. Rev. E **70**, 046608 (2004).
[3] N. Fang, H. Lee, C. Sun, and X. Zhang, Science **308**(5721), 534–537 (2005).
[4] D. Schurig, J. J. Mock, B. J. Justice, S. A. Cummer, J. B. Pendry, A. F. Starr, and D. R. Smith, Science **314**(5801), 977–980 (2006).
[5] I. V. Shadrivov, S. K. Morrison, and Y. S. Kivshar, Opt. Express **14**(20), 9344–9349 (2006).
[6] H.-T. Chen, J. F. O'Hara, A. K. Azad, A. J. Taylor, R. D. Averitt, D. B. Shrekenhamer, and W. J. Padilla. Nature Photon. **2**(5), 295–298 (2008).
[7] A. R. Katko, S. Gu, J. P. Barrett, B.-I. Popa, G. Shvets, and S. A. Cummer, Phys. Rev. Lett. **105**, 123905 (2010).
[8] D. Huang, A. Rose, E. Poutrina, S. Larouche, and D. R. Smith, Appl. Phys. Lett. **98**(20), 204102 (2011).
[9] A. Rose, D. Huang, and D. R. Smith, Phys. Rev. Lett. **110**, 063901 (2013).
[10] A. R. Katko, A. M. Hawkes, J. P. Barrett, and S. A. Cummer, IEEE Antennas Wireless Propag. Lett. **10**, 1571–1574 (2011).
[11] I. V. Shadrivov, A. B. Kozyrev, D. W. van der Weide, and Y. S. Kivshar, Appl. Phys. Lett. **93**(16), 161903 (2008).
[12] M. Lallart, D. Guyomar, C. Richard, and L. Petit, J. Acoust. Soc. Am. **128**, 2739–2748 (2010).
[13] N. Zhu, R. W. Ziolkowski, and H. Xin, Appl. Phys. Lett. **99**(11), 114101 (2011).
[14] J. Li and C. T. Chan, Phys. Rev. E **70**(5), 055602 (2004).
[15] H. J. Lezec, J. A. Dionne, and H. A. Atwater, Science **316**(5823), 430–432 (2007).
[16] R. W. Ziolkowski and A. Erentok, IEEE Trans. Antennas Propag. **54**(7), 2113–2130 (2006).
[17] G. X. Li, S. M. Chen, W. H. Wong, E. Y. B. Pun, and K. W. Cheah, Opt. Express **20**(1), 397–402 (2012).
[18] J. Zhao, Q. Cheng, J. Chen, M. Q. Qi, W. X. Jiang, and T. J. Cui, New J. Phys. **15**, 043049 (2013).
[19] O. M. Ramahi, T. S. Almoneef, M. Alshareef, and M. S. Boybay, Appl. Phys. Lett. **101**, 173903 (2012).
[20] A. S. Sedra and K. C. Smith, *Microelectronic Circuits*, 6th edition (Oxford University Press, 2009).
[21] C. A. Balanis, *Antenna Theory: Analysis and Design* (Wiley-Interscience, New York, 2005).

This article is copyrighted as indicated in the abstract. Reuse of AIP content is subject to the terms at: http://scitation.aip.org/termsconditions. Downloaded to IP: 152.3.43.156 On: Fri, 08 Nov 2013 20:28:30

Ambient RF Energy Harvesting in Urban and Semi-Urban Environments

Manuel Piñuela, *Student Member, IEEE*, Paul D. Mitcheson, *Senior Member, IEEE*, and
Stepan Lucyszyn, *Senior Member, IEEE*

***Abstract*—RF harvesting circuits have been demonstrated for more than 50 years, but only a few have been able to harvest energy from freely available ambient (i.e., non-dedicated) RF sources. In this paper, our objectives were to realize harvester operation at typical ambient RF power levels found within urban and semi-urban environments. To explore the potential for ambient RF energy harvesting, a city-wide RF spectral survey was undertaken from outside all of the 270 London Underground stations at street level. Using the results from this survey, four harvesters (comprising antenna, impedance-matching network, rectifier, maximum power point tracking interface, and storage element) were designed to cover four frequency bands from the largest RF contributors (DTV, GSM900, GSM1800, and 3G) within the ultrahigh frequency (0.3–3 GHz) part of the frequency spectrum. Prototypes were designed and fabricated for each band. The overall end-to-end efficiency of the prototypes using realistic input RF power sources is measured; with our first GSM900 prototype giving an efficiency of 40%. Approximately half of the London Underground stations were found to be suitable locations for harvesting ambient RF energy using our four prototypes. Furthermore, multiband array architectures were designed and fabricated to provide a broader freedom of operation. Finally, an output dc power density comparison was made between all the ambient RF energy harvesters, as well as alternative energy harvesting technologies, and for the first time, it is shown that ambient RF harvesting can be competitive with the other technologies.**

***Index Terms*—Ambient RF, energy harvesting, maximum power point tracking (MPPT), multiband, rectenna, RF survey, RF-dc.**

I. INTRODUCTION

FOR ALMOST 50 years, far-field RF technology has been used to remotely power systems from relatively large unmanned helicopters [1] to very small smart dust sensors [2] and contact lenses that measure eye pressure [3]. With all these systems, a dedicated RF source is used, where the operator may have control over the effective isotropically radiated power (i.e., both transmit power and antenna characteristics), beam pointing and polarization of the RF source, ensuring optimal line-of-sight operation between the source transmitter (TX) and harvesting receiver (RX). It is important to highlight that this work will focus only in radiative power transfer and not inductive or near-field power transfer, as demonstrated in [4]. A more convenient solution, however, is to power these devices from ambient RF energy sources, such as television and mobile phone signals, thus removing the need for a dedicated source. As ambient RF levels are lower than those that can be provided by a dedicated RF source, the efficiency of the harvesting system, and its minimum startup power are of critical importance.

In order to assess the feasibility of deploying ambient RF energy harvesters, the available RF power needs to be measured in different locations. Such measurements, in conjunction with knowledge on harvester performance, can then be used to determine the locations at which RF harvester powered devices can be successfully deployed. Several RF spectral surveys, which measure ambient RF power levels from sources such as television and mobile phone base stations, have been previously reported. Many have been undertaken using personal exposimeters or spectrum analyzers, where the exact location of each measurement is unknown and with RF power levels only being reported under general scenarios (e.g., outdoor, indoor, street, bus, etc.) [5], [6]. While being of academic interest for health-related research [7], the lack of power level and specific time/location information limits their usefulness for exploitation in ambient RF energy harvesting applications.

Most rectennas (normally comprising an antenna, impedance matching network, rectifier, storage element, and load) presented in the open literature have been tested using dedicated sources rather than harvesting from ambient RF energy [8]. In recent years, efficiencies as high as 78% [9] and 90% [10] have been demonstrated with relatively high input RF power levels (i.e., $> +10$ dBm). Moderate efficiencies have also been achieved using dedicated TXs that provided relatively low input RF power levels; e.g., an efficiency of 60% was achieved with -22.6-dBm input power [11]. In one demonstrator [12], designed to operate over a broad range of input RF power levels, (-30 to $+30$ dBm), the efficiency increased from 5% at a low input RF power to a peak of 80% at $+25$ dBm.

Despite advancements in end-to-end (i.e., input RF to output dc) power conversion efficiencies at low input RF power levels (similar to those measured in the spectral surveys), only a few attempts at true ambient RF energy harvesting have been reported. For example, one relatively efficient rectenna, utilizing a modified omnidirectional patch antenna, has an efficiency of 18% with a single-tone input RF power of -20 dBm [13]. This dedicated signal source was meant to emulate the input RF power levels measured from a nearby digital TV (DTV) TX in Tokyo, Japan, but did not take into account the more realistic effect of harvesting from a modulated broadband signal. Another attempt

---

Manuscript received November 20, 2012; revised April 24, 2013; accepted April 26, 2013. Date of publication May 24, 2013; date of current version June 28, 2013. This work was supported in part by the U.K. Government and the Mexican National Council of Science and Technology (CONACYT).

The authors are with the Department of Electrical and Electronic Engineering, Imperial College London, London SW7 2AZ, U.K. (e-mail: m.pinuela09@imperial.ac.uk; paul.mitcheson@imperial.ac.uk; s.lucyszyn@imperial.ac.uk).

Color versions of one or more of the figures in this paper are available online at http://ieeexplore.ieee.org.

Digital Object Identifier 10.1109/TMTT.2013.2262687

0018-9480/$31.00 © 2013 IEEE

at harvesting ambient RF energy from a mobile phone base station at 845 MHz was reported in [14]. This prototype managed to power an LCD thermometer for 4 min, but only after harvesting for 65 h. In that work, when the authors used a dedicated signal source with a single-tone input RF power of -15 dBm, an efficiency of 3% was recorded. A batteryless location sensor has also been demonstrated [15], powered by a rectenna with a printed antenna on a flexible substrate and a solar cell, although no details for the RF-dc efficiency were reported. Finally, successful prototypes capable of harvesting energy using TV antennas were presented, but again no details of their efficiency were given [16], [17].

In order to demonstrate the feasibility for implementing ambient RF energy harvesting, here we first present the results of a citywide RF spectral survey, indicating suitable locations and associated RF bands with sufficient input RF power density levels for harvesting. Based on these results, rectennas were then fabricated and their efficiencies, under ambient RF energy harvesting operation, were calculated using *in-situ* field strength measurements. Furthermore, an investigation of multiband rectenna arrays is also presented, demonstrating the tradeoffs between series (voltage summing) and parallel (current summing) topologies with the aim of reducing the minimum input power required for harvester operation. Finally, a comparison between measured ambient RF energy harvesting and alternative forms of energy harvesting technologies is presented; highlighting, for the first time, the practical feasibility of exploiting existing freely available sources of RF energy.

II. LONDON RF SURVEY

In order to quantify input RF power density levels present in a typical urban and semi-urban environment, a citywide RF spectral survey within the ultrahigh frequency (0.3–3 GHz) part of the frequency spectrum was conducted within Greater London. A number of citywide RF spectral surveys have previously been conducted, but in general, only a few samples were taken, giving little insight into (semi-)urban environments [14], [18], [19]. Other surveys [20], [21] compare their measurements relative to the distance from the nearest TX. In a (semi-)urban environment, this may not provide enough information about the RF spectrum since there is likely to be local geographical variations in base-station density and propagation characteristics (e.g., multipath effects and diffraction around and attenuation through buildings).

Each station on the London Underground network was used as a survey point to provide a robust dataset for representing Greater London in terms of geographical distribution and population density, having a combination of urban (in the center) and semi-urban (in surrounding areas) characteristics. Measurements were taken at each of the 270 stations (from a randomly chosen exit, at street level and a height of 1.6 m). To provide traceability and for use as a historical reference, time stamps and GPS locations were recorded. In addition, measurements were taken inside a building at Imperial College London (ICL), to represent a typical office block within an urban environment.

A. Methodology

Mobile phone usage varies during the daytime, and hence, ambient RF energy in their bands is expected to be time dependant, with more energy available during the daytime than at night time. Therefore, in order to be able to make fair comparisons between locations, measurements were taken between 10:00 am and 3:00 pm on weekdays over a period of one month (between March 5, and April 4, 2012). Electric field strength was measured between 0.3–2.5 GHz using an Agilent N9912A FieldFox RF analyzer [22] with a calibrated Aaronia BicoLOG 20300 omnidirectional antenna [23]. It is important to note that the spectral measurements were undertaken during the analog-to-digital switchover period in the U.K. and so the measurements for DTV may represent an underestimate of present RF power levels measured now that the switch over is complete [24]. It should also be noted that this survey was conducted prior to the 4G network being switched on within the U.K.

A "panning method," which complies with international regulations for measuring exposure limits, was used [25]–[27]. Here, the calibrated antenna is rotated to three orthogonal axes while the spectrum analyser is set to "max-hold," ensuring that the maximum reading is recorded. For each measurement, more than 1 min was allocated to allow for more than three sweeps across the selected frequency range. Additionally, to maintain a comparable signal-to-noise (S/N) ratio, attenuation was introduced (with a minimum set at 5 dB) to avoid compression when high input RF power levels were detected. For all measurements, the resolution bandwidth (BW) was fixed at 100 kHz, the internal amplifier was turned on and the highest resolution of 1001 points was selected. These settings provide the ability to obtain a snapshot of the power density that can be expected in an urban or semi-urban environment from continuously variable sources.

B. Results

After inputting the manufacturers' frequency-banded antenna factors into the spectrum analyzer, to ensure a fully calibrated system, the electric field strength measurements were taken. The input RF power density (S) is then calculated from the electric field strength measurement. Fig. 1 shows the input RF power density measured outside the Northfields London Underground station, where the spectral bands for DTV, GSM900, GSM1800, 3G, and Wi-Fi can been clearly identified.

A well-designed rectenna should ideally be capable of harvesting energy across an entire band, and thus it is important to calculate the total band power. The banded input RF power density S_{BA} (nW/cm^2) is calculated by summing all the spectral peaks across the band (i.e., in a similar way, the spectrum analyzer calculates channel power). These levels provide a snapshot of source availability at the time and location of the measurement. Moreover, they are used as a harvester design starting point since the power density at each band will define the input impedance of a rectenna.

The exact frequencies for each band are set by the U.K.'s official frequency band allocation [28]; the GSM900, GSM1800 and 3G base transmit (BTx) bands were separated from the associated mobile transmit (MTx) bands. Table I shows average



Fig. 1. Input RF power density measurements outside the Northfields London Underground station.

TABLE I
SUMMARY OF LONDON RF SURVEY MEASUREMENTS

Band	Frequencies (MHz)	Average S_{BA} (nW/cm^2)	Maximum S_{BA} (nW/cm^2)
DTV (during switch over)	470-610	0.89	460
GSM900 (MTx)	880-915	0.45	39
GSM900 (BTx)	925-960	36	1,930
GSM1800 (MTx)	1710-1785	0.5	20
GSM1800 (BTx)	1805-1880	84	6,390
3G (MTx)	1920-1980	0.46	66
3G (BTx)	2110-2170	12	240
WiFi	2400-2500	0.18	6

TABLE II
INPUT RF POWER DENSITY THRESHOLD: LONDON UNDERGROUND STATIONS WITHIN CENTRAL ZONES 1–3 (URBAN) AND OUTER ZONES 4–9 (SEMI-URBAN)

Band	S_{BA} *Threshold* (nW/cm^2)	Number of Stations Urban	Number of Stations Semi-urban
DTV (during switch over)	40	10	0
GSM900	230	8	2
GSM1800	450	7	3
3G	62	6	4



Fig. 2. Banded input RF power density measurements for the four largest ambient sources in Greater London.

RF power levels across all London Underground stations for the banded input RF power density measurements. It can be seen that all base-station transmit levels are between one and three orders of magnitude greater than the associated MTx levels. For this reason, and the fact that the population of transmitting mobile phones in close proximity of the harvester is highly variable, only base-station TXs will be considered further.

From our London RF survey, DTV, GSM900, GSM1800, 3G, and Wi-Fi were identified as potentially useful ambient RF energy harvesting sources, although DTV appears to be heavily dependent on line-of-sight and sudden changes in atmospheric conditions (e.g., temperature inversion) and Wi-Fi is very dependent on user traffic. It should be noted that the mobile phone base-station TXs employ vertically polarized antennas, placing a constraint on harvester orientation in deployment. With DTV, within the U.K., the main TXs have horizontally polarized antennas, while repeater TXs have vertically polarized antennas.

It is convenient to define the boundary between urban and semi-urban environments by the line that separates zones 3 and 4 on the London Underground map [29]. As one would expect, the central zones 1–3 host the highest density of base stations. As shown in Table II, a banded input RF power density threshold was selected to filter the ten London Underground stations with the highest measurements for each band. With DTV, the highest recorded measurements were all found within the urban environment. This is because Greater London's main DTV TX (at Crystal Palace) is located on the southeastern boarder of zones 3 and 4 and there are no London Underground stations further south. With mobile phones, more than 50% of the stations were inside the urban environment and those in a semi-urban environment were all located in close proximity to a cluster of base-station TXs.

Using the complete dataset from the London RF survey, Fig. 2 shows the average and median of the banded input RF power density measurements for the four largest ambient RF sources in Greater London. It can be seen that more than half of the locations have below average power levels. This is due to the fact that several stations had maximum levels that were considerably higher than the average because of their close proximity to TV TXs (e.g., Crystal Palace), extremes in base-station density and propagation characteristics.

In addition to the London RF survey, measurements within the Department of Electrical and Electronic Engineering building at ICL were taken on the 11th floor of the south stairwell. These are shown in Table III. As can be seen, DTV and GSM900 have a higher than average power level, due to a near line of sight from the TV TX and a close proximity to the 2G GSM900/1800 base stations.

The dataset from the London RF survey, with all relevant information (e.g., locations, timestamps, and banded input RF power density measurements), can be found at our interactive website: www.londonrfsurvey.org [30]. These measurements were used to design efficient harvesters and compared to ICL

TABLE III
MEASURED BANDED INPUT RF POWER DENSITIES AT ICL

	DTV	GSM900 (BTx)	GSM1800 (BTx)	3G (BTx)
S_{BA} [nW/cm^2]	18	48	50	3

measurements to identify locations in Greater London where the designed harvesters could operate. The design procedures and prototype test measurements will be presented in the following sections.

III. SINGLE-BAND AMBIENT RF ENERGY HARVESTERS

In order to implement efficient ambient RF energy harvesters, designed for the banded input RF power density levels measured at ICL, a set of single-band prototypes were realized and characterized; these will be compared to multiband array architectures in Section V.

A. Antenna Design and Measurements

Since our harvesters are intended to operate within a general (semi-)urban environment, where the exact location of the TX source is unknown, the rectennas' antennas need to be as close to omnidirectional as possible, avoiding the need for beam-pointing during deployment. This is at the obvious expense of limited antenna gain, and therefore, the corresponding levels of P_{RF} that the rectifier can receive. Conversely, if the location of the TX is known, then it may be tempting to use a high gain antenna, but this would require an appropriate level of beam-pointing and polarization matching that can be established and maintained.

Another requirement is that the antennas need to be easily scalable across all frequency bands since one important objective for this work is to compare and contrast different banded harvesters. Finally, the antennas need to be easily fabricated. For all these reasons, a linear polarized folded dipole was selected, although a monopole would also be suitable [31].

To simplify impedance matching between the antenna and rectifier, a modified folded dipole was used to obtain the required 50-Ω reference input impedance. A balun does not need to be employed, as there is no significant degradation in performance for this particular application, even with the use of an unbalanced microstrip rectifying circuit [32]. Furthermore, the antenna was not integrated onto a substrate, to give the additional freedom to embed the harvester on windows or within walls, furnishings, fixtures, or fittings. To this end, two different antennas were fabricated for each band; one made using a 560-μm diameter copper wire and the other with 75-μm-thick 25-mm-wide copper tape. The fabricated antennas are shown in Fig. 3. Since the copper tape was not rigid enough to retain its shape, it was placed on a Perspex substrate, to represent a flat panel.

To design the antennas, full-wave 3-D electromagnetic simulations were performed using CST Microwave Studio. As discussed previously, the antennas were designed to be as omnidirectional as possible, while covering as much of the ambient RF source BW as possible. Fig. 4 shows the typical simulated gain profile for the DTV tape antenna, having a front-to-back ratio of unity. Table IV shows the simulated gain and the 10-dB return-loss fractional BW for the optimized copper wire and tape antennas.



(a)

(b)

Fig. 3. 50-Ω folded-dipole antennas shown next to a British £1 coin. (a) DTV, GSM900 (BTx), GSM 1800 (BTx) and 3G (BTx) copper wire antennas. (b) 3G (BTx) copper tape antenna on Perspex.



Fig. 4. Simulated beam profile for the DTV tape antenna.

Fig. 5 shows excellent agreement between predicted and measured return-loss results, within a 10-dB return-loss bandwidth, for the eight fabricated single-band antennas. As one would expect with such a simple classical antenna, the out-of-band performances (not shown) were also in good agreement. It was found that better return-loss measurements are achieved with our single-band antennas when compared to other reported single-band omnidirectional [13] and multiband [33] designs. The latter may be important, as it may be tempting to implement a more compact multiband rectenna, but which

TABLE IV
SIMULATED GAIN AND 10-dB RETURN LOSS FRACTIONAL BW FOR FOLDED-DIPOLE SINGLE-BAND ANTENNAS

Band		Wire		Tape	
	BW (%)	Gain (dBi)	BW (%)	Gain (dBi)	BW (%)
DTV	26	4.35	4	4.48	6
GSM900	3.7	4.42	4.3	4.73	4.3
GSM1800	4.1	4.32	5.3	4.73	10.7
3G	2.8	4.39	5.4	4.76	12



(a)

(b)

Fig. 5. Input return-loss predictions and measurements for all single-band folded-dipole antennas. (a) Wire. (b) Tape.

may ultimately not give better ambient RF energy harvesting performance.

Obtaining a minimum acceptable return loss over an antenna fractional bandwidth as large as that of the source is key to harvest as much input RF energy as possible. As can be seen in Table IV, where the fractional bandwidth is defined for a 10-dB return loss, our antennas have a fractional bandwidth greater than those of the sources, with the exception of DTV, which only covers approximately 35% of the target frequency range. In other work [13], 5-dB return-loss fractional bandwidth is adopted for RF energy harvesting applications.



Fig. 6. Predicted input RF power levels for the four largest ambient sources at the ICL testing location.

The fractional bandwidth of the antennas having a minimum return loss of 5 dB is too great to assume a constant antenna gain over the whole band. Therefore, an additional advantage of using 10-dB return-loss fraction bandwidths is that (1) can be used to calculate the input RF power with the assumption that the midband antenna gain is constant with frequency [34]. Therefore, the time-averaged input RF power P_{RF} is given by

$$P_{\mathrm{RF}} = S_{BA} \cdot A_{\mathrm{real}} \text{ and } A_{\mathrm{real}} \approx G(f_o)\frac{\lambda_o^2}{4\pi} \qquad (1)$$

where A_{real} is the real aperture (or capture area) of the antenna, λ_o is the free-space wavelength at the midband frequency f_o, and $G(f_o)$ is the rectenna's antenna gain at f_o.

Substituting the measured banded input RF power densities recorded in Table III and the predicted midband antenna gains in Table IV into (1), realistic values for P_{RF} can be calculated for all four bands, with the results shown in Fig. 6. It can be seen that with all antenna gains being in the region of $\sim$ 4.5 dBi, the 2G GSM900/1800 harvesters will generate the highest input RF power levels, due to the high-banded input RF power density levels measured *in situ*. At the other extreme, the 3G harvesters will be the worst performers. As only a small fraction of the required frequency range is covered by the DTV antennas, the predicted values for P_{RF} represent an overestimation.

B. Rectifier Design and Measurements

Based on a previously reported analysis [35] and the predicted input RF power levels presented in Fig. 6, the zero-bias SMS7630 diode (in a series configuration) was selected as the optimal solution for our ambient RF energy harvesters, as shown in Fig. 7. In a series configuration, the junction capacitance $(C_j(V))$ of the diode dominates the detector's impedance, as long as $C_{\mathrm{out}} > C_j(V)$, and thus C_{out} has little or no effect on the matching circuit. This allows C_{out} to be large enough to provide a ripple-free output voltage. In contrast, C_{out} must be less than 1 pF to achieve a good impedance match with a shunt configuration as C_{out} appears in parallel with $C_j(V)$ and the packaging parasitic capacitance. However, C_{out} is too small to



Fig. 7. Series detector configuration with L-matching network.

provide a ripple-free dc voltage to the load. This can be overcome with a matching network that will allow a good impedance match with a large output capacitor, but at the expense of introducing losses. Furthermore, as shown in [36], these issues start to become negligible with a shunt configuration as the shunt diode becomes more self-biased as the input power increases. Simulations were performed using Agilent Technologies' ADS software. Its Momentum package not only takes into account the losses from the low-cost FR4 substrate, but also calculates fringing fields, effects from which are passed on to the harmonic-balance package for simulating the nonlinear behavior of the rectifier.

A good impedance match was achieved by employing a simple matching network; a series lumped-element inductor was used to absorb part of the capacitive reactance from the series diode and an additional quarter-wavelength short-circuit shunt stub was employed to achieve the desired 50-Ω impedance [37]. Since the impedance of the diode varies with frequency and input RF power, impedance matching between the antenna and rectifier was first undertaken by finding the optimal output load resistance for an input RF power level of -20 dBm with a single-tone source at the midband frequency. After the optimal load was found, further broadband optimization was performed to the matching network and the load to ensure good impedance matching throughout the target frequency range and the measured $P_{\rm RF}$ for each band.

As with the antenna analysis, and unlike conventional RF circuits that adopt the more traditional half-power bandwidth definition, the rectifier should adopt the 10-dB-input return-loss bandwidth. The reason for this is that, for ambient RF energy harvesting applications, the input RF power is at a premium and so what little energy is available should not be wasted by being reflected back from avoidable impedance mismatches at either the antenna or rectifier.

Fig. 8 shows excellent agreement between predicted and measured input return loss results, within the -10-dB bandwidth, for the DTV and GSM900 rectifiers, having fractional bandwidths of 5.7% (below target) and 4.8%, respectively. With these lower frequency designs, the fundamental and higher order harmonics were below -55 dBm, ensuring a clean dc voltage at the load, without the need for any output filtering. Reasonable agreement was found with the GSM1800 and 3G rectifiers, having fractional bandwidths of 1.6% (below target) and 7.4%, respectively. It was found that with these two higher frequency designs, the higher order harmonics were -40 dBm at the output. This reduced performance, as illustrated in Fig. 8, is due to the higher series inductive reactance leads of the output shunt storage capacitor. For this reason, a second prototype version (v2) was designed for the 3G rectifier, using distributed-element components for the input impedance matching stage and an additional output filter stage. With the lumped-element matching network, it was found that in order to achieve good input impedance matching to 50 Ω, all the microstrip transmission lines had to have a characteristic impedance of 92 Ω. With the distributed-element matching network, a simple shunt quarter-wavelength open-circuit stub, designed for operation at the fundamental frequency, was employed. A microstrip line was added between the cathode of the diode and the stub to absorb the capacitive reactance of the diode. The stub effectively filters to < -50 dBm the higher order harmonics. The microstrip design can be seen in Fig. 13.



Fig. 8. Input return-loss predictions and measurements for all first prototype single-band rectifiers, with $P_{\rm RF} = -20$ dBm at the input and optimal load resistances at the output.

C. PMM

Since the input RF power from ambient sources can be represented as a multi-tone source, with power levels fluctuating across the target frequency range, the output impedance of the rectifier is time varying. A power management module (PMM) capable of performing maximum power point tracking (MPPT) is required.

For our work, a low-power integrated-circuit PMM from Texas Instruments Incorporated (BQ25504) was selected, due to its low quiescent current (< 330 nA) and low input voltage operation (~ 80 mV hot-start and 330-mV cold-start) [38]. It is worth noting that its startup voltage is lower than PMMs previously reported and realized using hybrid circuits for RF energy harvesting [13]. The BQ25504 PMM includes a boost converter that steps up its input voltage (having a 350-mV average value during ambient operation) to useful levels between 2.4–5.3 V. The BQ25504 also has a built-in battery management module, which is used to control the duty cycle of the output power to the load.

MPPT operation on the BQ25504 is achieved by periodically sampling the open-circuit voltage (OCV) at the input of the converter, which then draws a current causing the converter



Fig. 9. System block diagram.

input voltage to fall and be held at a pre-programmed fraction of the OCV (set by a potential divider). In a simple dc circuit, with a resistive source impedance, the optimal ratio is 0.5. For the rectenna-based system, a ratio of 0.48–0.53 was found to maximize the power output of the system. The BQ25504 is designed to charge a storage element, and in this case, a capacitor C_{storage} was used. The programmed PMM continuously charges the storage capacitor, and the load (a low-power LED) was automatically connected to the storage capacitor when the capacitor voltage reaches an upper limit $V_{\mathrm{high}} = 2.84$ V and automatically disconnected when it reaches a lower limit $V_{\mathrm{low}} = 2.40$ V. The duty cycle of the LED can then be used to calculate the efficiency of the system, as will now be described. A diagram of the system is shown in Fig. 9.

IV. END-TO-END EFFICIENCY ANALYSIS

The efficiency η of an RF energy harvesting system is

$$\eta = \frac{P_{\mathrm{dc}}}{P_{\mathrm{RF}}} \tag{2}$$

where P_{dc} is the time-averaged output (i.e., equivalent dc) power into the storage element (e.g., battery or supercapacitor) and load and P_{RF} is as previously defined. Measurements for this type of system are usually performed in a controlled environment (e.g., an anechoic chamber or TEM cell), using a dedicated constant or variable amplitude single-tone RF signal source [32], [39]. However, the former is not suitable for evaluating ambient RF energy harvesting operation, which has a much broader spectrum of nonconstant input frequencies and where the instantaneous input RF power is time variant. The use of a constant single-tone dedicated source provides a convenient stable reference power to the harvester; while the latter reflects a more realistic signal source having fluctuating power levels across a nonzero bandwidth, multipath, and reflection effects which are very difficult to emulate in a controlled environment.



Fig. 10. End-to-end efficiencies for ambient RF energy harvesting at ICL.

Therefore, to determine the overall end-to-end efficiency $\eta_{\mathrm{e\text{-}e}}$ for a complete ambient RF energy harvester, the input RF energy U_{RF} was calculated based on the harvester's antenna characteristics and the actual banded input RF power density measurements taken at the time of harvester operation, using the Agilent Fieldfox and the calibrated antenna. It is important to note that since the impedance mismatch between the antenna and detector is not taken into account, U_{RF} is higher than expected, providing an underestimate of end-to-end efficiency. The output dc energy U_{dc} was then calculated by measuring the charge–discharge cycle time, t_{cycle} of the storage capacitor between V_{high} and V_{low}, as the LED is repeatedly connected and disconnected. The output dc energy equation is already taking into account the efficiency of the PMM given the fact that the measurements are taken at its output voltage. The end-to-end efficiency of one charge–discharge cycle of C_{storage} is

$$\eta_{\mathrm{e\text{-}e}} = \frac{U_{\mathrm{dc}}}{U_{\mathrm{RF}}} \tag{3}$$

where the input RF energy is given by integrating the time-averaged input RF power over a cycle time, as

$$U_{\mathrm{RF}} = \int_{0}^{t_{\mathrm{cycle}}} P_{\mathrm{RF}} dt \tag{4}$$

and the output dc energy is given by the energy supplied to the load, as follows:

$$U_{\mathrm{dc}} = C_{\mathrm{storage}} \frac{({V_{\mathrm{high}}}^2 - V_{\mathrm{low}}^2)}{2}. \tag{5}$$

A. ICL Field Trials

Four single-band ambient RF energy harvesters were assembled by connecting the rectifiers to the wire/tape antennas and PMMs programmed for the optimal load. A 100-μF shunt capacitor was employed as the storage element, providing $U_{\mathrm{dc}} = 115\ \mu$J. Our system is capable of cold-starting the boost converter and MPPT since the rectenna is capable of providing the minimum starting voltage of 330 mV. When the minimum voltage is reached, the boost converter and MPPT start to operate and the charge–discharge cycle at the load begins, causing the LED to flash. During field trials, t_{cycle} took up to 170 s for the harvester with lowest banded input RF power density, corresponding to 3G with the wire antenna. Table V summarizes the results where t_c and t_d are the charge and discharge times, respectively, and ΣV and ΣI are the multiband voltage and current summing array architectures, respectively. A detailed discussion on the multiband rectenna arrays will be presented in the following section. The end-to-end efficiency was calculated using (3) with data from Fig. 6 and measuring the charge–discharge cycle time during harvesting operation.

Fig. 10 shows the overall end-to-end efficiencies for all the harvester demonstrators, deployed and tested at ICL. As predicted by simulations, the improved 3G v2 demonstrator with

TABLE V
HARVESTERS CHARGE AND DISCHARGE TIMES (t_c, t_d, RESPECTIVELY) FOR A SPECIFIED LOAD

Band	Wire					Tape				
	t_c (s) load independent	t_d (s) load dependant	t_{cycle} (s) load dependant	$P_{dc}(t_d)$ (μW)	$P_{dc}(t_{cycle})$ (μW)	t_c (s) load independent	t_d (s) load dependant	t_{cycle} (s) load dependant	$P_{dc}(t_d)$ (μW)	$P_{dc}(t_{cycle})$ (μW)
DTV	26	12	38	9.6	3	14	18	32	8.2	3.6
GSM900	14	10	24	11.5	4.8	8	13	21	14.4	5.5
GSM1800	43	15	58	7.7	2	22	27	49	5.2	2.4
3G v2	167	3	170	38.4	0.7	96	5	101	1.2	1.1
Multiband ΣV	43	7	50	66	2.3	-	-	-	-	-
Multiband ΣI	55	5	60	92.2	2	-	-	-	-	-

tape antenna outperformed its original design by 11%; achieving an end-to-end efficiency of 40% with an input RF power of only −25.4 dBm.

It is believed that a much greater efficiency can be achieved for the DTV harvester if the fractional bandwidths for the first prototype circuits (i.e., 4.4/4.5% for the antennas and 5.8% for the rectifier) could be increased to match the much greater target value of 26%. Likewise, the reduced efficiency of the GSM1800 harvesters can be attributed to the detrimental effects of the narrowband input impedance matching of the rectifier (i.e., having a fractional bandwidth of only 1.6%, when compared to its target value of 4.1%). Finally, with all the harvesters, the end-to-end efficiencies can be enhanced through better antenna design and optimal polarization matching.

Table VI, shows the number of locations from the London RF survey that would be able to support our harvesters. Unlike the single-band 3G harvester, which can operate at 45% of the locations, our DTV harvester can only be used at two locations (one in zone 2 and the other in zone 3). Therefore, for the general deployment of an ambient RF energy harvester within an (semi-)urban environment, at street level, the single-band DTV harvester may not be practical

TABLE VI
NUMBER OF LOCATIONS FROM THE LONDON RF SURVEY CAPABLE OF SUPPORTING IDENTICAL HARVESTERS AT THE SAME EFFICIENCY LEVELS

	DTV	GSM900 (BTx)	GSM1800 (BTx)	3G (BTx)
Stations with higher S_{BA}	2	28	68	122

V. ARRAY ARCHITECTURES

Since ambient input RF power levels can be low (i.e., below −25 dBm) and dependent on both time and spatial considerations, harvesters could be designed to extract energy with spatial-diversity within the same frequency band or using different frequency bands. For example, with the former, at a particular location there may be only one band that has significant levels of RF energy worth harvesting. In this case, spatial-diversity array architectures may provide more usable output power. Alternatively, with the latter, multiband array architectures may provide more robust operation.

With both forms of parallel array architecture (i.e., spatial-diversity and multiband), a further classification can be seen through the use of either diversity/band switching or a summing node. With the former, physical switches automatically select whichever signal path delivers the highest input RF power level; with the latter, power from all signals is combined. Fig. 11 illustrates generic forms of parallel array architectures, showing that switching/summing can be performed electromagnetically at a single antenna or at the output from multiple antennas, rectifiers, or PMMs.

Multiband array architectures, similar to those in Fig. 11(c) and (d), capable of RF harvesting from the four previously identified bands, were selected as possible optimal solutions, given no size/cost constraints. Our objectives were to reach the minimum cold-start voltage at the lowest possible input RF power levels and increase the harvesters' operational capabilities within (semi-)urban environments.

To this end, two different multiple rectenna architectures were investigated. The first with a single shared PMM and the second with multiple PMMs, as illustrated in Fig. 12. To simplify assembly, the wire antennas were selected since they did not require a substrate. Unwanted coupling between the single-band antennas was minimized by placing them a minimum distance of $\lambda_L/5$ apart; where λ_L is the wavelength of the lowest frequency band antenna [40]. For example, the DTV and the 3G antennas were kept at least 11 cm apart, as shown in Fig. 13. This allowed S_{11} measurements to be the same as in Fig. 5 once all antennas were assembled into the array.

A. *Multiple Rectennas With a Shared PMM*

In order to improve the cold-start performance of the system, the outputs of multiple rectennas can be connected in series, as shown in Fig. 12(a). This increases the probability of the voltage on the input of the PMM reaching the cold-start level (330 mV for the BQ25504) under any given scenario. While cold-starting the PMM, each rectenna harvests (albeit not optimally). Once


Beam/Frequency Switching
or
Multi-beam/Band
Antenna
PMM
$C_{\text{Smoothing}}$
C_{storage}
Load
(a)
SP*N*T Switch/BFN
or
N-Channel
Multiplexing
Filter Bank
Σ
PMM
$C_{\text{Smoothing}}$
C_{storage}
Load
(b)
SP*N*T Switch or
Summing Node
Σ
PMM
$C_{\text{Smoothing}}$
$C_{\text{Smoothing}}$
C_{storage}
Load
(c)
PMM
PMM
$C_{\text{Smoothing}}$
$C_{\text{Smoothing}}$
C_{storage}
C_{storage}
SP*N*T Switch or
Summing Node
Σ
Load
(d)

Fig. 11. Parallel array architectures with switching/summing at the: (a) antenna, (b) output of multiple antennas, (c) output of multiple rectifiers, and (d) output of multiple PMMs.


V_{PMMin1}
DTV
I_{out}
V_{PMMin2}
GSM900
V_{PMMin3}
GSM1800
V_{PMMin4}
3G
I_{out}
PMM
C_{storage}
+
-
(a)
V_{PMMin1}
DTV
V_{PMMin2}
GSM900
V_{PMMin3}
GSM1800
V_{PMMin4}
3G
PMM
PMM
PMM
PMM
C_{storage}
+
-
(b)

Fig. 12. Multiband array architectures (with $N = 4$ bands). (a) Voltage summing at the outputs of the single-band rectennas. (b) Current summing at the outputs of the single-band harvesters.


GSM900
GSM1800
3G
DTV
BQ25504

Fig. 13. Rectenna array architecture with individual PMMs for the four largest contributors with wire antennas.

the PMM circuit starts, with the MPPT operating, the harvested power level increases.

The behavior of the series rectenna topology with a shared PMM requires some discussion. As the output impedance and the OCV for each rectenna is different, since they operate at different frequencies and input RF power levels, the rectennas are forced to share the same output current in a series configuration, which does not allow them all to operate at their individual maximum power points. This causes the voltage on each rectenna output, except the one having the highest input RF power, to collapse. This operation is analogous to the partial shading problem with a series string of solar panels [41] sharing a common boost converter. With this photovoltaic system, bypass diodes placed around individual cells stop the poorly lit cells contributing a negative voltage (and power) to the string. In our case, the series circuit formed by the loop antennas and rectifying diodes performs the same task. This means that while all rectennas contribute to system startup, only the rectenna with the highest input RF power contributes significant power for continuous operation once the PMM starts. Fig. 10 shows the end-to-end efficiency for the voltage summing multiband harvester array when tested at ICL. An efficiency of only 15% was achieved with a combined input RF power of -12 dBm. The lower efficiency, when compared to a single-band harvester, is due to the imbalance of rectifier outputs, as discussed above. Here, the charge time was 43 s, compared to 167 s with the lowest contributing single-band 3G harvester with wire antenna.

B. Multiple Rectennas With Individual PMMs

In order to overcome the balancing issues when multiple rectennas share a common PMM, as discussed previously, each rectenna can have its own PMM, whose outputs can be connected to a common storage element (in this case, a 400-μF shunt capacitor, providing $U_{\text{dc}} = 461\ \mu$J), as illustrated in Fig. 12(b) and shown in Fig. 13. Although not achieving cold-start as quickly as the series topology, this parallel topology has the advantage of being able to run each rectenna at its maximum power point. In addition, once one rectenna is able to harvest enough energy for a cold-start, all PMMs will start because they share a common storage element, allowing the rectennas with low-input RF power levels to harvest at levels below which they could not do so independently.

This parallel topology was tested and found to be capable of operating in many locations where the series array was unable to operate; e.g., if only one of the bands had $P_{\text{in}} > -25$ dBm. As expected, the largest contributor hot-started the other PMMs, allowing them to harvest at an input RF power level down to -29 dBm.

However, as with the previous results for voltage summing, having a combined input RF power of -12 dBm, the efficiency using multiple PMMs is slightly lower, at 13%, as shown in Fig. 10. This is because useful dc output power from the cold-



Fig. 14. Output dc power density for all harvesters at ICL.



Fig. 15. Output dc power density comparison for alternative ambient harvesting technologies [40]–[43] against the best current generation of RF harvesters at ICL.

starting harvester is being supplied to the other harvesters for hot-starting, even though some of them may not actually be contributing any of their own harvested power.

VI. OUTPUT DC POWER DENSITY COMPARISON

The volumetric output dc power density S_{harv} ($\mu\text{W/cm}^3$) represents an important figure of merit for comparing alternative energy harvesting technologies. For ambient RF energy harvesting, the output dc power is calculated by multiplying the effective input RF power by the overall end-to-end-efficiency. The total volume (including that of the antenna, rectifier, and PMM; not including energy storage, as this does not directly affect the dc power output) must be determined. It is important to note that the volume for the antenna could effectively disappear if it is assembled onto a window or within a wall, furnishing, fixture, or fitting. Moreover, the required PMM printed circuit board (PCB) size used throughout these calculations was assumed to be ten times the size of the BQ25504 chip, to account for any necessary additional components.

Fig. 14 shows the output dc power density for all the harvesters demonstrated here. It can be seen that the 2G GSM900/1800 harvesters with tape antennas both have the highest value of $S_{\text{harv}} = 7.4$ ($\mu\text{W/cm}^3$), when tested at ICL, due to the high-banded input RF power density S_{BA}. The value for the most efficient harvester (i.e., 3G v2 with tape antenna) was not the highest in terms of output RF power because S_{BA} in this band was more than an order of magnitude lower than with GSM900.

S_{harv} allows a direct and meaningful comparison to be made with other alternative energy harvesting technologies. Our best performing ambient RF energy harvester (i.e., GSM900 with tape antenna) was compared against alternative energy harvesting technologies, assuming they used the same PMM board size [42]–[44].

It can be seen in Fig. 15 that ambient RF energy harvesting has a low output dc power density when compared to alternative energy harvesting technologies, but only when the total volume of the first prototype demonstrator is considered. However, when the antenna is absorbed onto or into a background feature and when the PMM is fully integrated into the rectifier, it can outperform (as indicated by the dotted column) the alternative energy harvesting technologies, while providing a complimentary means of extracting energy from the environment. The RF harvesters, however, have the additional advantage in that they do not require a thermal gradient, and unlike vibration-driven devices, they have no moving parts.

VII. CONCLUSIONS

Our objectives were to reach the lowest possible ambient input RF power levels and extend the harvesters' operational capabilities within (semi-)urban environments. To this end, a comprehensive citywide RF spectral survey was undertaken, indicating that more than 50% of the 270 London Underground stations are suitable locations for the deployment of our ambient RF energy harvesters. It has been demonstrated that single-band harvesters can operate with efficiencies of up to 40% in a (semi-)urban environment, and can start to operate from power levels as low as -25 dBm.

To increase the freedom of operation, multiband array architectures were investigated. With the current summing harvester arrays, RF harvesting was achieved at an input RF power level as low as -29 dBm, without any external dc power supply to hot-start the PMM. Limitations on the multiband array architectures were discussed, highlighting the need for further work in balancing rectennas with voltage summing rectenna arrays when operating at lower input RF power levels.

Finally an output dc power density comparison against alternative energy harvesting technologies has shown that RF harvesting can represent a competitive solution within (semi-)urban environments, especially when the antenna can be absorbed into background features.

ACKNOWLEDGMENT

The authors would like to thank the members of the London RF survey team and F. Kusidlo, Agilent EEsof EDA, for his advice regarding simulations.

REFERENCES

[1] "Demonstration of microwave power transmission," *Pract. Wireless*, pp. 835–835, 1965.

[2] T. Salter, G. Metze, and N. Goldsman, "Parasitic aware optimization of an RF power scavenging circuit with applications to smartdust sensor networks," in *IEEE Radio Wireless Symp.*, 2009, pp. 332–335.

[3] "SENSIMED Triggerfish®—Continuous IOP monitoring," SENSIMED, Lausanne, Switzerland, Mar. 2012. [Online]. Available: http://www.sensimed.com/S-Trig-glaucoma.htm, , "

[4] M. Pinuela, D. C. Yates, S. Lucyszyn, and P. D. Mitcheson, "Maximizing DC-to-load efficiency for inductive power transfer," *IEEE Trans. Power Electron.*, vol. 28, no. 5, pp. 2437–2447, May 2013.

[5] W. Joseph, G. Vermeeren, L. Verloock, M. M. Heredia, and L. Martens, "Characterization of personal RF electromagnetic field exposure and actual absorption for the general public," *Health Phys.*, vol. 95, no. 3, pp. 317–330, Sep. 2008.

[6] G. Thuroczy, F. Molnar, J. Szabo, G. Janossy, N. Nagy, G. Kubinyi, and J. Bakos, "Public exposure to RF from installed sources: Site measurements and personal exposimetry," in *1st Eur. Antennas Propag. Conf.*, 2006, pp. 1–4.

[7] P. Elliott, M. B. Toledano, J. Bennett, L. Beale, K. de Hoogh, N. Best, and D. J. Briggs, "Mobile phone base stations and early childhood cancers: Case-control study," *Br. Med. J.*, vol. 340, no. 1, pp. 1–7, Jun. 2010.

[8] N. Shinohara, "Power without wires," *IEEE Microw. Mag.*, vol. 12, no. 7, pp. S64–S73, Dec. 2011.

[9] J. Y. Park, S. M. Han, and T. Itoh, "A rectenna design with harmonic-rejecting circular-sector antenna," *IEEE Antennas Wireless Propag. Lett.* , vol. 3, pp. 52–54, 2004.

[10] "Dengyo rectennas," Nihon Dengyo Kosaku Company Ltd., Tokyo, Japan, Jul. 2012. [Online]. Available: http://www.den-gyo.com/solution/solution01.html

[11] T. Le, K. Mayaram, and T. Fiez, "Efficient far-field radio frequency energy harvesting for passively powered sensor networks," *IEEE J. Solid-State Circuits*, vol. 43, no. 5, pp. 1287–1302, May 2008.

[12] V. Marian, B. Allard, C. Vollaire, and J. Verdier, "Strategy for microwave energy harvesting from ambient field or a feeding source," *IEEE Trans. Power Electron.*, vol. 27, no. 11, pp. 4481–4491, Nov. 2012.

[13] C. Mikeka, H. Arai, A. Georgiadis, and A. Collado, "Dtv band micropower RF energy-harvesting circuit architecture and performance analysis," in *IEEE Int. RFID-Technol. Appl. Conf.*, 2011, pp. 561–567.

[14] S. Kitazawa, H. Ban, and K. Kobayashi, "Energy harvesting from ambient RF sources," in *IEEE MTT-S Int. Microw. Symp. Workshop*, 2012, pp. 39–42, Series on Innovative Wireless Power Transmission: Technol., Syst., Appl..

[15] R. Vyas, V. Lakafosis, and M. Tentzeris, "Wireless remote localization system utilizing ambient RF/solar power scavenging RFID tags," in *IEEE MTT-S Int. Microw. Symp. Dig.*, May 23–28, 2010, pp. 1764–1767.

[16] H. Nishimoto, Y. Kawahara, and T. Asami, "Prototype implementation of ambient RF energy harvesting wireless sensor networks," *IEEE Sens. J.*, pp. 1282–1287, Nov. 2010.

[17] A. Sample and J. R. Smith, "Experimental results with two wireless power transfer systems," in *IEEE Radio Wireless Symp.*, 2009, pp. 16–18.

[18] V. Nitu, G. Lojewski, and S. Nitu, "Electromagnetic field evaluation on an antennas shared site, EUROCON 2009," in *IEEE EUROCON'09*, 2009, pp. 70–75.

[19] Y. Kawahara, K. Tsukada, and T. Asami, "Feasibility and potential application of power scavenging from environmental RF signals," in *IEEE AP-S Int. Symp.*, 2009, pp. 1–4.

[20] H. J. Visser, A. C. F. Reniers, and J. A. C. Theeuwes, "Ambient RF energy scavenging: GSM and WLAN power density measurements," in *38th Eur. Microw. Conf.*, 2008, pp. 721–724.

[21] T. G. Cooper, S. M. Mann, M. Khalid, and R. P. Blackwell, "Public exposure to radio waves near GSM microcell and picocell base stations," *J. Radiol. Protection*, vol. 26, no. 2, pp. 199–211, 2006.

[22] "FieldFox RF Analyser N9912A 4/6 GHz," Agilent Technol., Santa Clara, CA, USA, Tech. Overview, 2012.

[23] "Biconical EMC broadband antennas—BicoLOG Series," Aaronia, Strickscheid, Germany, Data Sheet, 2012.

[24] "Digital TV switchover in the UK," Digital UK Ltd., London, U.K., 2012.

[25] "International commission on non-ionizing radiation protection, guidelines for limiting exposure to time- varying electric, magnetic, and electromagnetic fields (up to 300 GHz)," *Health Phys.*, vol. 74, no. 4, pp. 494–522, 1998.

[26] M. Riederer, "EMF exposure due to GSM base stations: measurements and limits," in *IEEE Int. Electromagn. Compat. Symp.*, 2003, vol. 1, pp. 402–405.

[27] "Revised ECC recommendation (02)04: Measuring non-ionising electromagnetic radiation (9 kHz−300 GHz)," ECC within the Eur. CEPT, Oct. 2003.

[28] Nat. Freq. Planning Group, "United Kingdom frequency allocation table, issue no. 16," 2010, Cabinet Official Committee on U.K. Spectrum Strategy.

[29] Transport for London, "London underground map," Aug. 2012. [Online]. Available: http://www.tfl.gov.uk/gettingaround/1106.aspx

[30] Imperial College London, "London RF Survey," Aug. 2012. [Online]. Available: http://londonrfsurvey.org/

[31] R. Vyas, V. Lakafosis, M. Tentzeris, H. Nishimoto, and Y. Kawahara, "A battery-less, wireless mote for scavenging wireless power at UHF (470–570 MHz) frequencies," in *IEEE AP-S Int. Symp./USNC/URSI Nat. Radio Sci. Meeting*, Jul. 3–8, 2011, pp. 1069–72.

[32] T. Ungan and L. M. Reindl, "Harvesting low ambient RF-sources for autonomous measurement systems," in *Proc. IEEE Instrum. Meas. Technol. Conf.*, 2008, pp. 62–65.

[33] A. Costanzo, A. Romani, D. Masotti, N. Arbizzani, and V. Rizzoli, "RF/baseband co-design of switching receivers for multiband microwave energy harvesting," *Sensors Actuators A, Phys.*, vol. 179, pp. 158–168, Jun. 2012.

[34] J. L. Volakis, *Antenna Engineering Handbook*. New York, NY, USA: McGraw-Hill, 2007.

[35] M. Pinuela, P. D. Mitcheson, and S. Lucyszyn, "Analysis of scalable rectenna configurations for harvesting high frequency ambient radiation," in *Proc. Power MEMS*, Leuven, Belgium, 2010, pp. 41–44.

[36] J. O. McSpadden, L. Fan, and K. Chang, "Design and experiments of a high-conversion-efficiency 5.8-GHz rectenna," *EEE Trans. Microw. Theory Techn.*, vol. 46, no. 12, pp. 2053–2060, Dec. 1998.

[37] "HSMS-285x series datasheet," Avago Technol., San Jose, CA, USA, 2009.

[38] "Ultra low power boost converter with battery management for energy harvester applications," Texas Instruments Incorporated, Dallas, TX, USA, BQ25540 Datasheet, 2011.

[39] A. Nimo, D. Grgic, and L. M. Reindl, "Ambient electromagnetic wireless energy harvesting using multiband planar antenna," in *IEEE 9th Int. Syst., Signals, Devices Multi-Conf.*, Mar. 20–23, 2012, pp. 1, 6.

[40] H. Takhedmit, L. Cirio, B. Merabet, B. Allard, F. Costa, C. Vollaire, and O. Picon, "A 2.45-GHz dual-diode rectenna and rectenna arrays for wireless remote supply applications," *Int. J. Microw. Wireless Technol.*, vol. 3, no. 3, pp. 251–258, Jun. 2011.

[41] S. Vemuru, P. Singh, and M. Niamat, "Modeling impact of bypass diodes on photovoltaic cell performance under partial shading," in *IEEE Int. Electro/Information Technol. Conf.*, 2012, pp. 1–5.

[42] P. D. Mitcheson, E. M. Yeatman, G. K. Rao, A. S. Holmes, and T. C. Green, "Energy harvesting from human and machine motion for wireless electronic devices," *Proc. IEEE*, vol. 96, no. 9, pp. 1457–1486, Sep. 2008.

[43] R. J. M. Vullers, R. V. Schaijk, H. J. Visser, J. Penders, and C. V. Hoof, "Energy harvesting for autonomous wireless sensor networks," *IEEE Solid-State Circuits Mag.*, vol. 2, no. 2, pp. 29–38, Spring, 2010.

[44] V. Leonov, P. Fiorini, S. Sedky, T. Torfs, and C. Van Hoof, "Thermoelectric MEMS generators as a power supply for a body area network," in *13th Int. Solid-State Sens., Actuators, Microsyst. Conf. Tech. Dig.*, vol. 1, pp. 291–294.

Manuel Piñuela (M'12) received the BSc. degree in electrical and electronic engineering from the National Autonomous University of Mexico (UNAM), Mexico City, Mexico, in 2007, and is currently working toward the Ph.D. degree at Imperial College London, London, U.K.

From 2006 to 2009, he worked in industry as an Electronic Design and Project Engineer for companies focused on oil and gas services in both Mexico and the US. His research interests are wireless power transfer, RF power amplifiers, and RF energy harvesting.

Mr. Piñuela was the recipient of the Gabino Barrera Medal.

Paul D. Mitcheson (SM'12) received the M.Eng. degree in electrical and electronic engineering and Ph.D. degree from Imperial College London, U.K., in 2001 and 2005, respectively.

He is currently a Senior Lecturer with the Control and Power Research Group, Electrical and Electronic Engineering Department, Imperial College London. His research interests are energy harvesting, power electronics, and wireless power transfer. He is involved with providing power to applications in circumstances where batteries and cables are not suitable. His work has been sponsored by the European Commission, EPSRC and several companies.

Dr. Mitcheson is a fellow of the Higher Education Academy.

Stepan Lucyszyn (M'91–SM'04) received the Ph.D. degree in electronic engineering from King's College London (University of London), London, U.K., in 1992, and the D.Sc. (higher doctorate) degree from Imperial College London, London, U.K., in 2010.

He is currently a Reader (Associate Professor) of millimeter-wave electronics and Director of the Centre for Terahertz Science and Engineering, Imperial College London. After working in industry as a Satellite Systems Engineer for maritime and military communications, he spent the first 12 years researching microwave and millimeter-wave RF integrated circuits (RFICs)/monolithic microwave integrated circuits (MMICs), followed by RF microelectromechanical systems (MEMS) technologies. He has coauthored approximately 140 papers and 11 book chapters in applied physics and electronic engineering. He has delivered many invited presentations at international conferences.

Dr. Lucyszyn was an associate editor for the JOURNAL OF MICROELECTROMECHANICAL SYSTEMS (2005–2009). In 2011, he was the chairman of the 41st European Microwave Conference, Manchester, U.K. In 2005, he was elected Fellow of the Institution of Electrical Engineers (IEE), U.K., and Fellow of the Institute of Physics, U.K. In 2008, was invited as a Fellow of the Electromagnetics Academy, USA. In 2009, he became an IEEE Distinguished Microwave Lecturer (2010–2012). He is currently an Emeritus DML for 2013 and a newly appointed European Microwave Lecturer (EML) for the European Microwave Association.

Agrawal et al., *Cogent Engineering* (2017), 4: 1332705
https://doi.org/10.1080/23311916.2017.1332705

cogent engineering

ELECTRICAL & ELECTRONIC ENGINEERING | RESEARCH ARTICLE

A dual-band RF energy harvesting circuit using 4th order dual-band matching network

Sachin Agrawal[1]*, Manoj S. Parihar[1] and P.N. Kondekar[1]

Received: 06 March 2017
Accepted: 12 May 2017
First Published: 20 May 2017

*Corresponding author: Sachin Agrawal, PDPM-Indian Institute of Information Technology, Design and Manufacturing, Jabalpur 482005, India
E-mail: bitssachin.agrawal@gmail.com

Reviewing editor:
Wei Meng, Wuhan University of Technology, China

Additional information is available at the end of the article

Abstract: A novel compact rectifier for dual-band operation in the RF energy harvesting is presented. The circuit comprises a 4th order dual-band impedance matching and a single-series circuit with one double diode, both are integrating into a compact shape to occupy a small area of $30 \times 35\ \text{mm}^2$. The merit of the proposed rectifier circuit is that it can be extended to *n* number of the frequency band by using only $2 \times n$ matching elements. To validate the design method experimentally, a prototype of a dual-band rectifier is fabricated for two public telecommunication bands of GSM-900 and 1800. In order to reduce the circuit complexity and sensitivity arising due to lumped elements, the meander line and the open stub are used to realize the proposed circuit. A good agreement is obtained between the simulation and the measurement. The measured results show that the proposed rectifier circuit exhibits the conversion efficiency of 25.7 and 65% for an input power of −20 and 0 dBm, respectively. In addition, diode nonlinearity which affects the performance of the rectifier in terms of impedance matching is also investigated.

Subjects: Electromagnetics & Microwaves; Electronics; Circuits & Devices

Keywords: RF energy harvesting; dual band impedance matching; rectifier; RF-to-dc-conversion efficiency; frequency transformation

Sachin Agrawal

ABOUT THE AUTHOR

Sachin Agrawal did his BE and ME from Jiwaji University and Birla Institute of Technology Pilani, India in 2005 and 2009, respectively. Currently, he is pursuing his PhD from PDPM-Indian Institute of Information Technology Design and Manufacturing Jabalpur, India. His area of interest are; RF energy harvesting circuit, Antenna including planar and dielectric resonator antenna and Power amplifier.

PUBLIC INTEREST STATEMENT

With rapid growth in wireless communication, a huge amount of radio frequency (RF) energy broadcasted through billions of microwave sources such as mobile phones, handheld radios, and radio broadcast stations. Therefore, it is meaningful to collect and supply it to many electrical devices like mobile headsets, wearable medical sensors through RF energy harvesting. Since the ambient RF energy is distributed in multiple frequency bands, therefore the amount of energy harvested could increase if the circuit is designed for multiple frequency bands. In this work, we present a compact dual-band energy harvesting circuit to harvest energy from two most useful frequency bands, GSM-900 and 1800. The merit of the proposed rectifier circuit is it can be extended to *n* number of the frequency band by using only $2 \times n$ matching elements. A prototype is fabricated, and its performance is evaluated using Vector Network Analyzer (VNA). The total size of the rectifier is about $30 \times 35\ \text{mm}^2$.

cogent oa

© 2017 The Author(s). This open access article is distributed under a Creative Commons Attribution (CC-BY) 4.0 license.

1. Introduction

A revolutionary growth in wireless technology attracts huge attention from research community to make the self-sustainable device feasible through RF energy harvesting. It exploits ambient electromagnetic energy transmitted from different RF systems to remotely feed the electronic devices (Nintanavongsa, Muncuk, Lewis, & Chowdhury, 2012). Compared to other harvesting techniques, RF energy harvesting provides relatively predictable energy supply owing to the features of easy availability and less dependency on environmental variations. The typical block diagram of RF energy harvesting circuit is shown in Figure 1. It consists of three major blocks viz; antenna, matching network (MN), diode detector followed by an energy storage. The first element, antenna is employed to capture the RF signals of different frequencies and polarization, while second MN is for maximum power transfer, and the last rectifier is used to convert the RF energy to dc voltage. It means harvesting circuit performance can be evaluated in terms of accessible ambient RF energy and its conversion rate (Agrawal, Pandey, Singh,& Parihar, 2014). These parameters are heavily influenced by surrounding terrain conditions as the multiple reflection and dissipation certainly deteriorate the level of available ambient RF energy. As a result, conversion efficiency and dc output voltage may degrade. Previously, the majority of available RF energy harvesting circuits focused on single frequency band hence offer low dc output voltage. As the multiple RF energy sources of different frequency bands are available, thus from an ambient RF harvesting perspective, the output dc voltage could be increased if the circuit is designed for multiple frequency bands rather than a single band. A wide-band energy harvester can also promise a high output voltage by accumulating the number of RF signals at a time. However, due to nonlinear behavior of the diode, harvesting circuit itself exhibits nonlinearity i.e. its input impedance varies with the received RF power. Thus, it is quite difficult to retain the impedance match and high conversion efficiency over a large frequency range (Song, Huang, Zhou, & Carter, 2014). The losses due to impedance mismatch over a large bandwidth can be illustrated in Collado and Georgiadis (2013), where only 8% conversion efficiency is achieved at -20 dBm.

To address this, it is preferable to harvest energy from several narrow frequency bands rather than a single large one. In literature, numerous topologies have been proposed to accomplish the multiband energy harvesting (Bergès, Fadel, Oyhenart, Vigneras, & Taris, 2015; Hamano et al., 2016; Ho et al., 2016; Keyrouz, Visser, & Tijhuis, 2013; Kuhn, Lahuec, Seguin, & Person, 2015; Liu, Zhong, & Guo, 2015; Niotaki, Georgiadis, Collado, & Vardakas, 2014; Pinuela, Mitcheson, & Lucyszyn, 2013; Scheeler, Korhummel, & Popovic, 2014; Shariati, Rowe, Scott, & Ghorban, 2015; Sun, Guo, He, & Zhong, 2013). These topologies can be differentiated in terms of filter functionality i.e. how the antenna or source impedance is matched to the rectifier circuit. For instance, in Pinuela et al. (2013) and Keyrouz et al. (2013) several single-band rectennas (combination of antenna and rectifier circuit) were stacked to constitute a multi-band harvesting circuit. In this case, each rectenna was designed for a specific frequency band. Thus, for compact applications, this architecture is not suitable due to the number of antennas used. Moreover, in most of the reported works, the quality assessment of the output voltages combination was not taken into consideration. In Kuhn et al. (2015), the circuit complexity is reduced to a certain extent by replacing the multiple antennas with a single wide-band antenna. However, in this topology too, the number of rectifiers increases with the frequency bands, which leads to prolonging the circuit complexity.

Figure 1. Typical block diagram of RF energy harvesting circuit.



Besides, a multi-band harvesting circuit can also be formed by simply embedding a multi-band matching network between the multi-band antenna and the rectifying circuit (Bergès et al., 2015; Hamano et al., 2016; Ho et al., 2016; Liu et al., 2015; Niotaki et al., 2014; Scheeler et al., 2014; Shariati et al., 2015; Sun et al., 2013). The multi-band matching network can be designed either by distributed or by lumped element. In general, the multi-band rectifier circuit experiences two types of losses: first due to shift in resonance frequency from the optimum frequency point, and second due to the filter complexity. Because of the diode nonlinearity, the input impedance of the circuit varies as a function of power and frequency which causes a shift in resonance frequency. The difficulty due to diode nonlinearity can be observed in Sun et al. (2013) where the dual-band rectifier circuit exhibits its impedance matching for a small range of input power. The losses induced because of filter complexity can be observed in the recently reported works on dual band harvesting circuit (Niotaki et al., 2014; Scheeler et al., 2014; Shariati et al., 2015). In Niotaki et al. (2014), for $P_{\text{in}} = -15$ dBm, author achieved the conversion efficiency of 23% at the expense of increased filter complexity consisting two series and two shunt pairs of reactive elements. Thus, for more than dual band applications, the proposed circuit topology is not suitable due to excessive filtering components used. To obtain good conversion efficiency a dual-band rectenna reported in Scheeler et al. (2014). However, the rectenna was large in size and requiring a complex impedance tuning circuit. In Shariati et al. (2015) also, a dual-band matching network consisting nine reactive elements was employed to achieve the dual-band characteristics.

In order to reduce the filter complexity, this work proposed a compact dual-band harvesting circuit for GSM-900 and 1800. It consists of a 4th order dual-band matching network based on $1-n$ frequency transformation, which is optimized for the energy harvesting circuit to reduce the complexity up to $2\times n$ reactive elements (n is the number of frequency bands). Similar to frequency transformation method, the proposed dual-band rectifier circuit can be extended to n number of frequency bands by using the $2\times n$ number of reactive elements. The detailed analysis and design guidelines of dual band rectifier circuit are discussed in Section 2.

2. Dual band rectifier design and analysis

This section presents the design and analysis of a dual-band harvesting circuit in terms of impedance matching, DC output voltage and RF-to-dc conversion efficiency. The topology of the proposed dual-band RF energy harvesting circuit is shown in Figure 2(a). As seen, the low-cost Schottky diode is used to transform the input RF power to DC voltage. The impedance matching at two frequency is achieved using a series and parallel combination of the *LC* pair. The main idea underlying the suggested multi-band matching network is $1-n$ frequency transformation (one to many mapping of frequency), which transforms a single-band matching network to multi-band matching network (Nallam & Chatterjee, 2013). As the name ($1-n$) suggests that for designing a multi-band matching network, primarily a single-band matching network is required whose resonant frequency is dependent on the frequencies for which multi-band matching network proposed to designed.

Moreover, this frequency transformation method depends on the type of load impedance, whether it is series or parallel combination of *RC* or *RL*. Since the selected diode (HSMS-2852) has capacitive behavior throughout the frequency, it can be represented in a series or parallel combination of *R* and *C*. In the case of parallel *RC* load, the following equations are used to transform the single-band matching network into multi-band matching network.

$$\omega = \frac{\omega_t^n + a_m\omega_t^{n-m} + a_{m+2}\omega_t^{n-(m+2)} + \cdots}{\omega_t^{n-1} + a_{m+1}\omega_t^{n-(m+1)} + a_{m+3}\omega_t^{n-(m+3)} + \cdots} \tag{1}$$

where, n is the number of bands and m varies from 2 to n. After substituting the value of n, Equation (1) can be expanded in partial fraction form using the causal foster analysis as:

$$\omega = \omega_t + \frac{1}{\frac{\omega_t}{a_2-a_3} + \frac{1}{\cdots}} \tag{2}$$


Dual band MN
RF-to-dc converter
Single band MN
C3
L1
C2
C4
R
AC
C1
L3
L2
L1= 66, L2= 32, L3= 32 (in nH)
C1= 0.5, C2= 0.23 (pF)
(a)
Dual band MN
RF-to-dc converter
Single band MN
C3
L1
C2
C4
R
AC
C1
L2
2n number of matching elements
(b)

Figure 2. (a) Circuit diagram of the proposed dual-band rectifier circuit and (b) optimized dual-band rectifier circuit.

The coefficients a_2 and a_3 can be calculated as:

$$\omega_m = \sum_{i=1}^{n} (-1)^{i-1} \omega_i \tag{3}$$

$$a_m = (-1)^m \sum_{i,j=1,1\,\&\, i \neq j}^{n,n} (-1)^{i+j} \omega_i \omega_j \tag{4}$$

$$a_{m+1} = (-1)^{m+1} \sum_{i,j,k=1,1,1\,\&\, i\neq j\neq k}^{n,n,n} (-1)^{i+j+k} \omega_i \omega_j \omega_k \tag{5}$$

$$a_{m+n} = (-1)^{m+n} \sum_{i,j,k\ldots=1,1,1\ldots i\neq j\neq k}^{n,n,n\ldots} (-1)^{i+j+k+\cdots} \omega_i \omega_j \omega_k \ldots \tag{6}$$

$$a_n = \prod_{i=1}^{n} (-1)^n \omega_i \tag{7}$$

Equation (6) is similar to that presented in Nallam and Chatterjee (2013), except the term $(-1)^{m+n}$, which is included here to realize the multi-band matching network for more than three frequency bands i.e. for $n \geq 3$.

With this transformation, the capacitor of the matching network is transformed to the combination of prototype capacitor parallel with inductor whereas, an inductor is transformed into a combination of the same inductor with a series capacitor. Figure 3 shows the circuit schematic of transformation of a single-band matching network to the dual-band matching network. It can be seen that C_1 is transformed to $C_1 \| L_2$ and L_1 transformed to L_1 series with C_2. After successful usage of (1)–(7), the resultant multi-band matching network requires $3n - 1$ and $4n - 1$ reactive elements for L and Π-type topology, respectively.

Figure 3. Conversion of a single-band matching network to dual-band matching network using $1-n$ frequency transformation.



As the aim is to design a dual-band harvesting circuit, therefore, we require here only 5 or 7 reactive elements with L and Π-type topologies, respectively. From Figure 2(a), it can be seen that the resultant matching network consists of five elements, where the inductor L_3 and capacitor C_2 results after the transformation of capacitor C_1 and inductor L_1, respectively. Besides, the inductor L_2 occurrs due to the diode reactive element, which is generally a capacitor.

In this work, two frequencies 0.9 and 1.8 GHz that correspond to the maximum signal strength are chosen for dual-band harvesting circuit. According to this method, it is necessary to assign the frequencies in descending order e.g. $\omega_1 = 1.8, \omega_2 = 0.9$. Therefore, from (3) single-band matching network frequency is equal to $\omega_1 - \omega_2 = 2\pi(1.8 - 0.9) \times 10^9 = 0.9 \times 2\pi \times 10^9$. In order to match the source impedance with the rectifier at the calculated frequency 0.9 GHz, the chosen matching topology is L-type as shown by the encircled portion in Figure 2(a). The corresponding element values can be approximated using the various methods some of which are described in Pozar (2010). Subsequently, this single-band matching network is transformed to dual-band matching network using (1)–(7). The detailed design steps of the dual-band rectifier circuit are summarized as follows:

(1) As we are interested in matching the diode to 50 Ω at two frequencies (0.9 and 1.8 GHz) so, the order of transformation is equal to 2 or $n = 2$.

(2) In the first step, single-band matching network is designed at the frequency f calculated as: $f = f_2 - f_1 = 1.8 - 0.9 = 0.9$ GHz. In this case, any matching topology that matches the diode to 50 Ω, at 0.9 GHz for an input power $P_{\text{in}} = -20$ dBm, and load resistance 4.7 kΩ can be used. The chosen single-band matching network is shown by the encircled portion in Figure 2(a).

(3) Afterwards, this single-band matching network is transformed into dual-band using the (1)–(7) as shown below:

Since $n = 2$ therefore, from (2)

$$\omega = \omega_t + \frac{1}{\frac{\omega_t}{a_2}} \tag{8}$$

From (4) a_2 can be calculated as:

$$a_2 = (-1)^{2+2}\sum(-1)^{1+2}\omega_1\omega_2 = \omega_1\omega_2 \tag{9}$$

$$a_2 = -1.62 \times 4\pi^2 \times 10^8 = 0.64 \times 10^{20} \tag{10}$$

Thus, inductor L_1 (=66 nH) is transformed to impedance as:

$$j66 \times 10^9\omega = j66 \times 10^9\omega_t + \frac{1}{j0.23 \times 10^{-12}\omega_t} \tag{11}$$

Similarly, capacitors (=0.5 pF) are transformed to the admittance as:

$$j5 \times 10^{-13}\omega = j5 \times 10^{-13}\omega_t + \frac{1}{j32 \times 10^{-9}\omega_t} \tag{12}$$

The circuit schematic of the dual-band harvesting circuit is shown in Figure 2(a). It can be seen that resultant matching network consists of five reactive elements according to $3n - 1$. In order to reduce the circuit complexity and sensitivity due to reactive elements, a parametric study has been carried out to eliminate the elements showing minimum influence on the circuit performance.

Figure 4 shows the simulated $|S_{11}|$ for the different combination of matching elements. The simulated results demonstrate that $|S_{11}|$ experiences maximum change when inductor L_2 and capacitor C_2 are removed from the circuit, whereas it remains almost unaffected when L_3 is not present in the circuit. Therefore, inductor L_3 can be extruded from the circuit and the resultant matching circuit requires only $2n$ and $3n$ reactive elements in place of $3n - 1$ and $4n - 1$ elements. In this way, for each topology, the proposed circuit reduces $n - 1$ elements compared to the conventional method. Figure 2(b) demonstrates the optimized circuit diagram of the dual-band rectifier. It can be observed that circuit requires large inductors value of 32 and 66 nH. Thus, it is quite difficult to realize the practical rectifier circuit whose response is similar to the response of simulated result. In order to avoid any impedance mismatch due to the small difference in elements value, the meander line inductor and open stub are used to realize the inductors and capacitors, respectively. In this case, not only fabrication and optimization process become so easy but the cost will also reduced.

Figure 5, shows the layout of the dual-band rectifier circuit. In Nintanavongsa et al. (2012) and Agrawal et al. (2014), it has been demonstrated that the number of rectifying diodes or equivalently voltage multiplier stages are very much sensitive to the RF-to-dc conversion efficiency. In low-power region (≤ -20 dBm), efficiency decreases if voltage multiplier stages increase, whereas in higher power region (≥ -20 dBm), an opposite effect occurs. As the demand is to harvest energy in low-power region, single-series circuit with a double diode is used to convert received RF energy into dc voltage. From the left side of the circuit, the first meander line corresponds to the inductor L_1, while the second meander line represents the inductor L_2, of the Figure 2(b). The shunt stub is accounted

Figure 4. Simulated $|S_{11}|$ vs. frequency for different combination of circuit elements.



Figure 5. Layout of the proposed dual-band RF energy harvesting circuit.



for the shunt capacitor C_1 of Figure 2(b). The dimensions of each element are calculated according to their respective reactive element value and the substrate on which circuit has to be fabricated. In Assimonis, Daskalakis, and Bletsas (2016), it has been demonstrated that traces (microstrips) connected to the rectifier terminals (e.g. distance between the diode and via and diode and load) are highly sensitive for RF-to-dc efficiency. Therefore, traces d_1, d_2 between diode and capacitor C_1 and C_2, d_3 between diode and load and d_4 between diode and ground are adjusted to optimize the impedance matching as well as the conversion efficiency of the rectifier. Due to nonlinear behavior of the diode, harvesting circuit itself exhibits nonlinearity i.e. its input impedance varies with received RF power, therefore harmonic-balance (HB) and large signal analysis (LSSP) were employed to take into consideration the nonlinear behavior of the rectifier.

The photograph of the fabricated dual-band rectifier is shown in Figure 6. It is fabricated on a 1.54 mm thick FR-4 substrate with a dielectric constant (ϵ_r) of 4.3 using chemical etching method. The rectifier performance is evaluated in terms of $|S_{11}|$ and output voltage using the Agilent vector network analyzer (VNA). The simulated and measured $|S_{11}|$ is illustrated in Figure 7(a). The measured result shows reasonable agreement with the simulated one; the slight difference can be accounted for the fabrication imperfections. It is well known that impedance matching is a function of frequency and input power, due to the nonlinearity of the diode. Such a characteristic is examined in Figure 7(b), where the measured $|S_{11}|$ is demonstrated as a function of input power level for three different load impedance values. From results, it is clear that impedance matching of the harvesting circuit is greatly affected by the input power and the load impedance. Figure 7(b) demonstrates that as power increases, the impedance matching at 0.9 GHz degraded drastically, while at 1.8 GHz, it improves. Moreover, it is noticed that the impedance matching at higher power level is more sensitive to the variation of load impedance (*RL*).

The measured RF-to-dc conversion efficiency and output voltage vs. input power for both frequencies are demonstrated in Figure 8(a). For 0.9 GHz, efficiency is equal to 25.7 and 65.1% for an input power of -20 and 0 dBm, respectively. However, at 1.8 GHz the efficiency is relatively small that might be due to the increased parasitic losses in the rectifier diode. Figure 8(b) shows the relation between the output voltage and frequency for various input power levels at fixed load resistance value of 4.7 kΩ. It can be seen that maximum output voltage is achieved in the frequency range of 860–900 and 1770–1800 MHz, showing the rectifier's capability to harvest RF energy in the GSM-900 and 1800 bands.

Figure 9, depicts the measured conversion for various values of load resistance. It can be noticed that the circuit yields maximum efficiency when the load impedance is 4.7 kΩ. It starts decreasing as the load impedance varies from 4.7 kΩ. Table 1 shows the comparison of the conversion efficiency and the size of the proposed rectifier with the similar works reported previously. Only measured results are compared in Table 1. It can be seen that in low-power condition maximum efficiency is achieved in Sun et al. (2013), but the expense of bulky circuit size. However, the proposed rectifier offers an optimal conversion efficiency with compact circuit size.



Figure 6. Photograph of the fabricated dual-band RF energy harvesting circuit.

Figure 7. (a) Simulated and measured $|S_{11}|$ vs. frequency and (b) measured $|S_{11}|$ for various power levels.



Figure 8. (a) Measured output dc voltage and RF-to-dc conversion efficiency and (b) measured dc voltage vs. frequency.



Figure 9. Measured RF-to-dc conversion efficiency for different load impedance.



Table 1. Performance comparison of the proposed dual rectifier with recently published works

Ref.	Measured rectifier efficiency (%)	Input power (dBm)	Rectifier size
Ho et al. (2016)	15.8 @ 0.89 GHz	−20	100×65 mm^2
	11.2 @ 1.76 GHz		
Hamano et al. (2016)	10 @ 2.15 GHz	−10	37×71 mm^2
	15 @ 5.84 GHz		
Bergès et al. (2015)	27 @ 0.91/2.4 GHz	−16	78×88 mm^2
Sun et al. (2013)	30 @ 2.14 GHz	−20	145 mm
	35 @ 1.84 GHz		
Liu et al. (15)	20 @ (0.91+1.8) GHz	−20	23×37 mm^2
This work	27.5 @ 0.9 GHz	−20	30×35 mm^2
	20 @ 1.8 GHz		

3. Conclusion

A new compact 4th order dual-band rectifier has been designed to harvest the RF power of GSM-900 and 1800 bands. In order to reduce the circuit complexity and sensitivity due to reactive elements, the meander line and the open stub are used to fabricate the matching network. For $P_{\text{in}} = -20$ dBm, the measured RF-to-dc conversion efficiency of 27.5 and 20% is achieved at 0.9 and 1.8 GHz, respectively. Further, more than 45 and 34% conversion efficiency is maintained from -10 to 10 dBm for 0.9 and 1.8 GHz, respectively.

Funding
The authors received no direct funding for this research.

Author details
Sachin Agrawal[1]
E-mail: bitssachin.agrawal@gmail.com
Manoj S. Parihar[1]
E-mail: mparihar@iiitdmj.ac.in
P.N. Kondekar[1]
E-mail: pnkondekar@iiitdmj.ac.in
[1] PDPM-Indian Institute of Information Technology, Design and Manufacturing, Jabalpur 482005, India.

Citation information
Cite this article as: A dual-band RF energy harvesting circuit using 4th order dual-band matching network, Sachin Agrawal, Manoj S. Parihar & P.N. Kondekar, *Cogent Engineering* (2017), 4: 1332705.

References

Agrawal, S., Pandey, S. K., Singh, J., & Parihar, M. S. (2014). *Realization of efficient RF energy harvesting circuits employing different matching technique* (pp. 754–761). Fifteenth International Symposium on Quality Electronic Design, Santa Clara, CA.

Assimonis, S. D., Daskalakis, S. N., & Bletsas, A. (2016). Sensitive and efficient rf harvesting supply for batteryless backscatter sensor networks. *IEEE Transactions on Microwave Theory and Techniques, 64*, 1327–1338.

Bergès, R., Fadel, L., Oyhenart, L., Vigneras, V., & Taris, T. (2015). A dual band 915MHz/2.44 GHz RF energy harvester. *Microwave Conference (EuMC), 2015 European*. IEEE.

Collado, A., & Georgiadis, A. (2013). Conformal hybrid solar and electromagnetic (EM) energy harvesting rectenna. *IEEE Transactions on Circuits and Systems I: Regular Papers, 60*, p. 10.

Hamano, K., Tanaka, R., Yoshida, S., Miyachi, A., Nishikawa, K., & Kawasaki, S. (2016). Design of dual-band rectifier using microstrip spurline notch filter. *Radio-Frequency Integration Technology (RFIT), 2016 IEEE International Symposium on*. IEEE.

Ho, D. K., Kharrat, I., Ngo, V. D., Vuong, T. P., Nguyen, Q. C., & Le, M. T. (2016). *Dual-band rectenna for ambient RF energy harvesting at GSM 900 MHz and 1800 MHz* (pp. 306–310). 2016 IEEE International Conference on Sustainable Energy Technologies (ICSET), Hanoi.

Keyrouz, S., Visser, H., & Tijhuis, A. (2013, April). Multi-band simultaneous radio frequency energy harvesting. *In Antennas and Propagation (EuCAP), 2013 7th European Conference on*, 3058–3061.

Kuhn, V., Lahuec, C., Seguin, F., & Person, C. (2015). A multi-band stacked RF energy harvester with RF-to-DC efficiency up to 84\%. *IEEE Transactions on Microwave Theory and Techniques, 63*, 1768–1778.

Liu, Z., Zhong, Z., & Guo, Y.-X. (2015). Enhanced dual-band ambient RF energy harvesting with ultra-wide power range. *IEEE Microwave and Wireless Components Letters, 25*, 630–632.

Nallam, N., & Chatterjee, S. (2013, June). Multi-band frequency transformations, matching networks and amplifiers. *Circuits and Systems I: Regular Papers, IEEE Transactions on, 60*, 1635–1647.

Nintanavongsa, P., Muncuk, U., Lewis, D., & Chowdhury, K. (2012, March). Design optimization and implementation for rf energy harvesting circuits. *IEEE Journal on Emerging and Selected Topics in Circuits and Systems, 2*, 24–33.

Niotaki, K., Georgiadis, A., Collado, A., & Vardakas, J. S. (2014). Dual-band resistance compression networks for improved rectifier performance. *IEEE Transactions on Microwave Theory and Techniques, 62*, 3512–3521.

Pinuela, M., Mitcheson, P., & Lucyszyn, S. (2013, July). Ambient rf energy harvesting in urban and semi-urban environments. *Microwave Theory and Techniques, IEEE Transactions on, 61*, 2715–2726.

Pozar, D. M. (2010). *Microwave engineering* (3rd ed.). New Delhi: Wiley.

Scheeler, R., Korhummel, S., & Popovic, Z. (2014). A dual-frequency ultralowpower efficient 0.5-g rectenna. *IEEE Microwave Magazine, 15*, 109–114.

Shariati, N., Rowe, W. S., Scott, J. R., & Ghorban, K. (2015). Multi-service highly sensitive rectifier for enhanced RF energy scavenging. *Scientific Reports, 5*, 9655

Song, C., Huang, Y., Zhou, J., & Carter, P. (2014). Improved ultrawideband rectennas using hybrid resistance compression technique. *IEEE Transactions on Antennas and Propagation, 65*, 2057–2062.

Sun, H., Guo, Y. X., He, M., & Zhong, Z. (2013). A dual-band rectenna using broadband Yagi antenna array for ambient RF power harvesting. *IEEE Antennas and Wireless Propagation Letters, 12*, 918–921. doi:10.1109/LAWP.2013.2272873.

© 2017 The Author(s). This open access article is distributed under a Creative Commons Attribution (CC-BY) 4.0 license.

You are free to:
Share — copy and redistribute the material in any medium or format
Adapt — remix, transform, and build upon the material for any purpose, even commercially.
The licensor cannot revoke these freedoms as long as you follow the license terms.

Under the following terms:
Attribution — You must give appropriate credit, provide a link to the license, and indicate if changes were made.
You may do so in any reasonable manner, but not in any way that suggests the licensor endorses you or your use.
No additional restrictions
You may not apply legal terms or technological measures that legally restrict others from doing anything the license permits.

***Cogent Engineering* (ISSN: 2331-1916) is published by Cogent OA, part of Taylor & Francis Group.**
Publishing with Cogent OA ensures:
- Immediate, universal access to your article on publication
- High visibility and discoverability via the Cogent OA website as well as Taylor & Francis Online
- Download and citation statistics for your article
- Rapid online publication
- Input from, and dialog with, expert editors and editorial boards
- Retention of full copyright of your article
- Guaranteed legacy preservation of your article
- Discounts and waivers for authors in developing regions

Submit your manuscript to a Cogent OA journal at www.CogentOA.com

Circuits and Systems, **2012, 3, 216-222**
http://dx.doi.org/10.4236/cs.2012.33030 Published Online July 2012 (http://www.SciRP.org/journal/cs)

Optimization of the Voltage Doubler Stages in an RF-DC Convertor Module for Energy Harvesting

Kavuri Kasi Annapurna Devi[1*], **Norashidah Md. Din**[2], **Chandan Kumar Chakrabarty**[2]
[1]Department of Electrical and Electronic Engineering, INTI International University, Nilai, Malaysia
[2]Department of Electronics and Communication Engineering, Universiti Tenega Nasional, Kajang, Malaysia
Email: {*kavurik.adevi., chandan}@newinti.edu.my, norashidah@uniten.edu.my

Received August 25, 2011; revised March 26, 2012; accepted April 4, 2012

ABSTRACT

This paper presents an optimization of the voltage doubler stages in an energy conversion module for Radio Frequency (RF) energy harvesting system at 900 MHz band. The function of the energy conversion module is to convert the (RF) signals into direct-current (DC) voltage at the given frequency band to power the low power devices/circuits. The design is based on the Villard voltage doubler circuit. A 7 stage Schottky diode voltage doubler circuit is designed, modeled, simulated, fabricated and tested in this work. Multisim was used for the modeling and simulation work. Simulation and measurement were carried out for various input power levels at the specified frequency band. For an equivalent incident signal of –40 dBm, the circuit can produce 3 mV across a 100 kΩ load. The results also show that there is a multiplication factor of 22 at 0 dBm and produces DC output voltage of 5.0 V in measurement. This voltage can be used to power low power sensors in sensor networks ultimately in place of batteries.

Keywords: Energy Conversion; RF; Schottky Diode; Villard; Energy Harvesting

1. Introduction

RF energy harvesting is one type of energy harvesting that can be potentially harvested such as solar, vibration and wind. The RF energy harvesting uses the idea of capturing transmitted RF energy at ambient and either using it directly to power a low power circuit or storing it for later use. The concept needs an efficient antenna along with a circuit capable of converting RF signals to DC voltage. The efficiency of an antenna mainly depends on its impedance and the impedance of the energy converting circuit. If the two impedances aren't matched then it will be unable to receive all the available power from the free space at the desired frequency band. Matching of the impedances means that the impedance of the antenna is the complex conjugate of the impedance of the circuit (voltage doubler circuit).

The concept of energy harvesting system is shown in **Figure 1**, which consists of matching network, RF-DC conversion and load circuits. The authors in [1], used a 2.4 GHz operating frequency with an integrated zero bias detector circuit using BiCMOS technology which produced an output voltage of 1 V into a 1 MΩ load at an input power level of 0 dBm. H. Yan and co-authors revealed that a DC voltage of 0.8 volts can be achieved from a –20 dBm RF input signal at 868.3 MHz through simulation results [2]. In [3], work was carried out on a firm frequency of 900 MHz by matching to a 50 Ω impedance and resonance circuit transformation in front of the Schottky diode which yields an output voltage of over 300 mV at an input power level of 2.5 µ. W. J. Wang, L. Dong and Y. Fu [4] used a Cockcroft-Walton multiplier circuit that produced a voltage level of 1.0 V into a 200 MΩ load for an input power level of less than –30 dBm at a fixed frequency of 2.4 GHz.

The energy conversion module designed in this paper is based on a voltage doubler circuit which can be able to output a DC voltage typically larger than a simple diode rectifier circuit as in [5], in which switched capacitor charge pump circuits are used to design two phase voltage doubler and a multiphase voltage doubler. The module presented in this can function as an AC to DC converter that not only rectifies the input AC signal but also elevates the DC voltage level. The output voltage of the



Figure 1. Schematic view of a RF energy harvesting system.

---

[*] Corresponding author.

Copyright © 2012 SciRes.

energy conversion module can be used to energize the low power devices for example sensors for a sensor network in application to agriculture.

Section 2 of this paper discusses on the theoretical background of the voltage doubler circuit. Section 3 presents the simulation study and implementation of the circuit design. Section 4 provides the results and analysis. Section 5 concludes with a discussion on the findings from the simulated and measured results.

2. Voltage Multiplier

There are various voltage multiplier circuit topologies. The design used in this module is derived from the function of peak detector or a half wave peak rectifier. The Villard voltage multiplier circuit was chosen in the circuit design of this paper because it produces two times of the input signal voltage towards ground at a single output and can be cascaded to form a voltage multiplier with an arbitrary output voltage and its design simplicity.

2.1. Diode Modeling

The voltage multiplier circuit in this design uses zero bias Schottky diode HSMS-2850 from Agilent. The attractive feature of these Schottky diodes are low substrate losses and very fast switching but leads to a fabrication overhead. This diode has been modeled for the energy harvesting circuit which comes in a one-diode configuration. The modeling parameters for these diodes are given by Agilent in their data sheets. These parameters are used in Multisim for its own modeling purposes. The modeling is done by transforming the diode into an equivalent circuit using passive components which are described by the SPICE parameters in **Table 1** [6].

The diode used in this design is shown in **Figure 2** and its equivalent model is shown in **Figure 3**. The special features of HSMS-2850 diode is that it provides a low forward voltage, low substrate leakage and uses the non symmetric properties of a diode that allows unidirectional flow of current under ideal condition.

Table 1. SPICE parameters.

Parameters	Units	HSMS 2850
B_V	V	3.8
C_{J0}	pF	0.18
E_G	Ev	0.69
I_{BV}	A	3E–4
I_S	A	3E–6
N	No unite	1.06
R_S	Ω	25
P_B (V_J)	V	0.35
P_T (XTI)	No units	2
M	No units	0.5



Figure 2. Schottky diode.



Figure 3. Linear circuit model of the Schottky diode [6].

The diodes are fixed and are not subject of optimization or tuning. This is described using the following derivations. By neglecting the effect of diode substrate, an equivalent linear model that can be used for the diode as shown in **Figure 3**. When C_j is the junction capacitance and R_j is the junction resistance, the admittance Y_z of the linear model is given by

$$Y_Z = Y_{C_j} + Y_{R_j} \tag{1}$$

Equation (1) related to the frequency of operation is given by

$$Y_Z = jwC_j + \frac{1}{R_j} \tag{2}$$

$$= \frac{jwC_jR_j + 1}{R_j} \tag{3}$$

The impedance Z of the linear model is given by

$$Z = \frac{R_j}{1 + jwR_jC_j} \tag{4}$$

The total impedance Z_T is given by

$$Z_T = R_S + \frac{R_j}{1 + jwR_jC_j} \tag{5}$$

where R_S is the series resistance of the circuit and R_j is given by

$$R_j = \frac{8.33 \times 10^{-5} \times N \times T}{I_b + I_S}$$

where:

I_b = bias current in μA;
I_s = saturation current in μA;
T = temperature (K);

Copyright © 2012 SciRes.

N = ideality factor.

In Equation (5), R_j and C_j are constants and the frequency of operation (w) is the only variable parameter. As the frequency increases, the value of Z is almost negligible compared to the series resistance R_S of the diode. From this it is concluded that the function of the diode is independent of the frequency of operation.

2.2. Single Stage Voltage Multiplier

Figure 4 represents a single stage voltage multiplier circuit. The circuit is also called as a voltage doubler because in theory, the voltage that is arrived on the output is approximately twice that at the input. The circuit consists of two sections; each comprises a diode and a capacitor for rectification. The RF input signal is rectified in the positive half of the input cycle, followed by the negative half of the input cycle. But, the voltage stored on the input capacitor during one half cycle is transferred to the output capacitor during the next half cycle of the input signal. Thus, the voltage on output capacitor is roughly two times the peak voltage of the RF source minus the turn-on voltage of the diode.

The most interesting feature of this circuit is that when these stages are connected in series. This method behaves akin to the principle of stacking batteries in series to get more voltage at the output. The output of the first stage is not exactly pure DC voltage and it is basically an AC signal with a DC offset voltage. This is equivalent to a DC signal superimposed by ripple content. Due to this distinctive feature, succeeding stages in the circuit can get more voltage than the preceding stages. If a second stage is added on top of the first multiplier circuit, the only waveform that the second stage receives is the noise of the first stage. This noise is then doubled and added to the DC voltage of the first stage. Therefore, the more stages that are added, theoretically, more voltage will come from the system regardless of the input. Each independent stage with its dedicated voltage doubler circuit can be seen as a single battery with open circuit output voltage V_0, internal resistance R_0 with load resistance R_L, the output voltage, V_{out} is expressed as in Equation (7).



Figure 4. Single stage voltage multiplier circuit [7].

$$V_{\text{out}} = \frac{V_0}{R_0 + R_L} R_L \tag{6}$$

When n number of these circuits are put in series and connected to a load of R_L in Equation (6) the output voltage V_{out} obtained is given by this change in RC value will make the time constant longer which in turn retains the multiplication effect of two in this design of seven stage voltage doubler.

$$V_{\text{out}} = \frac{nV_0}{nR_0 + R_L} = V_0 \frac{1}{\frac{R_0}{R_L} + \frac{1}{n}} \tag{7}$$

The number of stages in the system has the greatest effect on the DC output voltage, as shown from Equations (6) and (7).

It is inferred that the output voltage V_{out} is determined by the addition of R_0/R_L and $1/n$, if V_0 is fixed. From this analysis it is observed that V_0, R_0 and R_L are all constants. Assume that $V_0 = 1$ V, $R_0/R_L = 0.25$, $n = 2, 3, 4, 5, 6$ and 7, the output voltage $V_{\text{out}} = 1.33$ V, 1.72 V, 2.0 V, 2.22 V, 2.43 V and 2.56 V respectively when substituted analytically in the Equation (7). This analysis can be compared with the results obtained in the circuit design of this module. In simulation at $n = 4$, $V_{\text{out}} = 1.42$ V, $n = 5$, $V_{\text{out}} = 1.67$ V; $n = 6$, $V_{\text{out}} = 1.92$; $n = 7$, $V_{\text{out}} = 2.15$ V; $n = 8$, $V_{\text{out}} = 1.92$ V; $n = 9$, $V_{\text{out}} = 1.81$ V. Also in measurement, for $n = 4$, $V_{\text{out}} = 2.1$ V; $n = 5$, $V_{\text{out}} = 2.9$ V; $n = 6$, $V_{\text{out}} = 3.72$ V; and $n = 7$, $V_{\text{out}} = 5$ V. As n increases, the increase in output voltage will be almost double the input voltage up to some number of stages. But at some point, *i.e.* beyond seven stages, in this circuit the output voltage gained (8 and 9 stages) will be negligible as shown in **Figure 5**.

The capacitors are charged to the peak value of the input RF signal and discharge to the series resistance (R_s) of the diode. Thus the output voltage across the capacitor of the first stage is approximately twice that of the input signal. As the signal swings from one stage to other, there is an additive resistance in the discharge path of the



Figure 5. Normalized output voltage multiplier versus number of stages.

diode and increase of capacitance due to the stage capacitors.

2.3. Seven Stage Voltage Multiplier

The seven stage voltage multiplier circuit design implemented in this paper is shown in **Figure 6**. Starting on the left side, there is a RF signal source for the circuit followed by the first stage of the voltage multiplier circuit. Each stage is stacked onto the previous stage as shown in the **Figure 6**. Stacking was done from left to right for simplicity instead of conventional stacking from bottom to top.

The circuit uses eight zero bias Schottky surface-mount Agilent HSMS-285X series, HSMS-2850 diodes. The special features of these diode is that, it provides a low forward voltage, low substrate leakage and uses the non-symmetric properties of a diode that allows unidirectional flow of current under ideal conditions. The diodes are fixed and are not subject of optimization or tuning. This type of multiplier produces a DC voltage which depends on the incident RF voltage. Input to the circuit is a predefined RF source. The voltage conversion can be effective only if the input voltage is higher than the Schottky forward voltage.

The other components associated with the circuit are the stage capacitors. The chosen capacitors for this circuit are of through-hole type, which make it easier to modify for optimization, where in [8] the optimization was accomplished at the input impedance of the CMOS chip for a three stage voltage multiplier. The circuit design in this paper uses a capacitor across the load to store and provide DC leveling of the output voltage and its value only affects the speed of the transient response. Without a capacitor across the load, the output is not a good DC signal, but more of an offset AC signal.

In addition to the above, an equivalent load resistor is connected at the final node. The output voltage across the load decreases during the negative half cycle of the AC input signal. The voltage decreases is inversely proportional to the product of resistance and capacitance across the load. Without the load resistor on the circuit, the voltage would be hold indefinitely on the capacitor and look like a DC signal, assuming ideal components. In the design, the individual components of the stages need not to be rated to withstand the entire output voltage. Each component only needs to be concerned with the relative voltage differences directly across its own terminals and of the components immediately adjacent to it. In this type of circuitry, the circuit does not change the output voltage but increases the possible output current by a factor of two. The number of stages in the system is directly proportional to the amount of voltage obtained and has the greatest effect on the output voltage as explained in the Equation (7) and shown in **Figure 5**.

3. Simulation and Implementation

Multisim software was chosen for modeling and simulation which is a circuit simulation tool by Texas Instruments. The simulation and practical implementation were carried out with fixed RF at 945 MHz ± 100 MHz, which are close to the down link center radio frequency (947.5 MHz) of the GSM-900 transmitter. The voltages obtained at the final node V_{DC} of the multiplier circuit were recorded for various input power levels from –40 dBm - +5 dBm with power level interval (spacing) of 5 dBm.

The simulations were also carried out using same stage capacitance value (3.3 nF) and then with a varied capacitance value for all stages from 4 stages through 9 stages [9]. The capacitance value was varied in such a way that, from one stage to the next, it was halved. For example, if the first stage was 3.3 nF, the second stage was 1.65 nF, third stage was 825 pF, fourth stage was 415 pF and so on. But keeping in view of testing, the capacitance values were chosen to have a close match with the standard available values in the market.

Simulation was carried out through 4 to 9 voltage doubler stages. Based on results obtained a 7 stage doubler is best to implemented for this application.

The design of the printed circuit board (PCB) was carried out using DipTrace software. The material used to



Figure 6. Schematic of 7 stage voltage multiplier.

manufacture the printed circuit board (PCB) is the standard Fiberglass Reinforced Epoxy (FR4), with the thickness of 1.6 mm and dielectric constant of 3.9. The topology is constructed on the PCB with the dimensions of 98 mm × 34 mm (W × H). The Sub Miniature version A (SMA) connectors are used at the input and output of PCB to carry out the measurements. The circuit components consist of active and passive components. The component used in circuit is shown in **Table 2**.

Special handling precautions have been taken to avoid Electro Static Discharge (ESD), while assembling of the surface-mount zero bias Schottky diodes. Also special attention has been given to mount other components and the SMA connectors on to the PCB. The Photograph of Assembled circuit board I shown in **Figure 7**.

4. Results and Analysis

The simulated and measured results at the output voltage of voltage multiplier circuit are shown graphically in **Figure 8**. From the graph analysis, the simulated and the measured results agree considerably with each other. The measured results are shown to be better than the simulation results. The reason behind this may be due to the uncertainty in series resistance value of the diode obtained from SPICE parameters in modeling as explained in Equation (5). This resistance vale of diodes in practical circuit may be lower than in the model, which provides fast discharge path, in turn rise in voltage as passes through the stages and reaches to final output. In this work, the DC output voltages obtained through simulation and measurement at 0 dBm re 2.12 V and 5.0 V respectively. These results are comparatively much better than in ref. [9], where in at 0 dBm, 900 MHz they achieved 0.5 V and 0.8 V through simulation and measurement respectively.

Figures 9 and **10** show the result of a 4 stage voltage doubler circuit with equal and varied capacitance values between the stages as described in Section 3.

From the analysis of these two simulations, it can be observed that the resulting output voltages are equal. The only difference between these two graphs is the rise time of the circuit with varied capacitance value is a little bit slower. But, overall result on the performance of rise time is still under 20 µs to 24 µs and the difference is negligible. From these results, the use of equal stage capacitance of each being 3.3 nF was hence considered for the design of the multiplier.

The results from **Figure 11**, shows that the output voltage reaches to 1.0 V within 20 µS and then uniformly increasing to 1.4 V, 1.67 V, 1.87 V and 2.12 V for 4, 5, 6 and 7 stages respectively compared to 2 mS as shown in [10]. **Figure 12** shows that the conversion ratio of 22 is achieved at 0 dBm input power and drops to 2.5 at –40 dBm. The highest value at 0 dBm is due to the innate characteristics of the zero bias Schottky diodes which conduct fairly well at higher input voltages.

5. Conclusion

From the experimental results, it is found that the pro-

Table 2. Component used in 7 stage voltage multiplier.

Name of component	Label	Value
Stage capacitors	C_1 - C_{14}	3.3 nF
Stage diodes	D_1 - D_{14}	HSMS 2850
Filter capacitor	C_L	100 nF
Load resister	R_L	100 kΩ



Figure 7. Photograph of assembled circuit board.



Figure 8. Simulated and test DC output voltage of multiplier as a function of input power.



Figure 9. DC output voltage verses rise time of 4 stage voltage doubler circuit with equal stage capacitance [8].



Figure 10. DC output voltage verses rise time of 4 stage voltage doubler with varied stage capacitance [8].



Figure 11. DC output voltage verses rise time of voltage doubler circuit through 4 - 7 stages with equal stage capacitance.



Figure 12. Conversion ratio as a function of input power.

posed voltage multiplier circuit operates at the frequency of 945 MHz with the specified input power levels. The results have shown that there is multiplication of the input voltage. From **Figure 12**, it is shown that at 0 dBm input power, the multiplication factor is 22. This is significant, as the work shows that RF energy in the GSM-900 band can be harvested from the ambient RF source using the Villard circuit topology. The power density levels from a GSM base station is expected from 0.1 mW/m^2 to 1 mW/m^2 for a distance ranging from 25 m - 100 m. These power levels may be elevated by a factor between one and three for the GSM-900 downlink frequency bands depending on the traffic density [10]. The next phase of the research work is to interface the voltage multiplier circuit through a matching network to the antenna at the input side and a low power device to power from the system at the output side to complete the RF energy harvesting system.

6. Acknowledgements

We would like to acknowledge and thank the Ministry of Higher Education Malaysia for funding this project under Fundamental Research Grant: FRGS/1/10/TK/UNITEN/02/13.

Copyright © 2012 SciRes.

REFERENCES

[1] S. von der Mark and G. Boeck, "Ultra Low Power Wakeup Detector for Sensor Networks," *SBMO/IEEE MTT-S International Microwave & Optoelectronics Conference* (*IMOC* 2007), Berlin, 29 October-1 November 2007, pp. 865-868. doi:10.1109/IMOC.2007.4404394

[2] H. Yan, J. G. M. Montero, A. Akhnoukh, L. C. N. de Vreede and J. N. Burghartz, "An Integration Scheme for RF Power Harvesting," *Proceedings of STW Annual Workshop on Semiconductor Advances for Future Electronics and Sensors*, Veldhoven, November 2005, pp. 64-66. doi:10.1.1.126.5786

[3] T. Ungan and L. M. Reindl, "Concept for Harvesting Low Ambient RF-Sources for Microsystems," 2007. http://www.imtek.de/content/pdf/public/2007/powermems_2007_paper_ungan.pdf

[4] J. Wang, L. Dong and Y. Z. Fu, "Modeling of UHF Voltage Multiplier for Radio-Triggered Wake-Up Circuits," *International Journal of Circuit Theory and Application*, Vol. 39, No. 11, 2010, pp. 1189-1197. doi:10.1002/cta.692

[5] J. A. Starzyk, Y.-W. Jan and F. J. Qiu, "A DC-DC Charge Pump Design Based on Voltage Doublers," *IEEE Transactions on Circuits and Systems-I*: *Fundamental Theory and Applications*, Vol. 48, No. 3, 2001, pp. 350-359.

[6] HSMS-2850, "Surface Mount Zero Bias Schottky Detector Diodes." http://www.crystal-radio.eu/hsms285xdata.pdf

[7] D. W. Harrist, "Wireless Battery Charging System Using Radio Frequency Energy Harvesting," M.S. Thesis, University of Pittsburgh, Pittsburgh, 2004.

[8] E. Bergeret, J. Gaubert, P. Pannie and J. M. Gaultierr, "Modeling and Design of CMOS UHF Voltage Multiplier for RFID in an EEPROM Compatible Process," *IEEE Transactions on Circuits and Systems-I*, Vol. 54, No. 10, 2007, pp. 833-837. doi:10.1109/TCSII.2007.902222

[9] B. Emmanuel, J. Gaubert, P. Pannier and J. M. Gaultier, "Conception of UHF Voltage Multiplier for RFID Circui," *IEEE North-East Workshop on Circuits and Systems*, Gatineau, June 2006, pp. 217-220. doi:10.1109/NEWCAS.2006.250961

[10] H. J. Visser, A. C. F. Reniers and J. A. C. Theeuwes, "Ambient RF Energy Scavenging: GSM and WLAN Power Density Measurements," *Proceedings of the* 38*th European Microwave Conference*, Eindhoven, 27-31 October 2008, pp. 721-724. doi:10.1109/EUMC.2008.4751554

Homebrew at ACØC
Combo Analog+DSP Filter
A Few Good CW Keyers
Preamps
RF Current Meter
100W Speaker Amp
The Ultimate Audio Filter
2xSi570 RF Gen
SB200 Sleeper
SB-200 Tank Mods
High Perf Xtal Osc
CW-Skimmer Array
Leakage Tester
XR2206 Sig Gen
Fixed Bench PS
Dual Variable Bench PS
Station Interface
Speaker/Paddle Switching

RF Current Meter

Stop Guessing and Built This Simple Meter Making Measurements Easy to Take

Why a Hand Held RF Current Meter

20
40
60
80
100
0
µA
SD-670
CLASS 2.0

There are two things that I wanted to do which would be made easy with a current meter... Both are related to the unusual nature of the antenna here at AC0C.

1. Checking common mode surface current on coax and control cables up in the attic antennas.

With the high cost of ferrites, placing them with the aid of a current meter is very helpful in that you can compare the before (no ferrite) and after (with ferrites attached) - and know that you have addressed the current problem on a given bit of line.

Otherwise, it seemed to me, that ferrite placement was more of a guess than a science.

2. Measuring relative antenna currents along an element

With the W8WWV RVM system, I can measure element currents where ever a current sensor is placed. This is typically at the center of a dipole element.

However, the center may or may not be the actual high-current point for the element depending on the frequency. My EZNEC models can indicate where the current peaks are - and by looking along these lines manually - comparing them with readings taken from the driven element, I can make current checks even in non-standard location of the array.

The meter described below accomplishes these two tasks very nicely.

Design Idea

The design follows an old RSGB design that I found on G3SEK's excellent web site:

http://www.ifwtech.co.uk/g3sek/clamp-on/clamp-on.htm



I followed this design pretty close except for the R3/R4 which I used variable trim pots. Due to the voltage-doubler nature of the circuit, it's capable of exceptional sensitivity.

The meter was calibrated for full-scale @ 1A on the higher scale, but I have left the lower scale set on a very high sensitivity setting which I find very handy for the common mode checking. Here, a sensitive meter providing a relative current indication is needed.

Construction Details



Once parts were in hand, construction was very easy and took perhaps an hour.

No attempt was made to beautify the work - it's 100% orientated toward functionality and utility.

I had a 100 uA meter in the junk box along with the other parts needed and orienting them on the back-side of the meter was really the most time consuming aspect.

The switch is held in position with hot-glue. And a bit of hot glue is applied to the meter terminations as a safety precaution - just in case I were to brush the meter up against something carrying high levels of current.

Wraps around the toroid were made with wire-wrap type wire, 30 Gage.



Selection of the toroid used was based on what would physically fit around the RG-213 sized cable and could be easily opened and closed.

The rubber band shown in the picture makes for a very convenient closing mechanism - and in a lot of applications, I simply hold the toroid closed with my finger pressure which makes moving the meter along a wire - and moving from cable to cable - very quick and easy.

For more ideas, check out Frank N4SPP's very nice RF current meter found HERE.

© 2011-2016 AC0C - All Rights Reserved

Created with the QTH.com SiteBuilder.

Bread board Arrangement:


Rookie ELectronics


Rookie ELectronics
10
15
20
25
30

Strip Board:


Rookie ELectronics

RF Diagnostics, LLC

WELCOME TO RF DIAGNOSTICS



Energy Harvesting Modules

WIRELESS ENERGY HARVESTING PRODUCTS RF Diagnostics, LLC designs and sells surface mount RF to DC converters and other building block modules for energy harvesting systems. With our products you can harvest ambient AC/AM/FM/Wireless Energy to power your IoT battery free system. We also provide custom designs for RF/microwave and general electrical engineering products and design contracting services to clients in the commercial wireless and defense electronics businesses. We strive to be a high quality and cost effective design resource for your design team.

OUR PRODUCTS

Microwave Energy Detector

This detector receives wireless energy at 2.5GHz and converts the signal to a DC voltage which powers a light emitting diode (LED). Place the detector on your microwave window or near your wireless LAN router and the LED will brighten and fade as the wireless field changes. No batteries needed!

RFD102A RF-DC Converter
2.5GHz Dipole Antenna
Light Emitting Diode


RFD-101 REV. 2
RF DIAGNOSTICS LLC
RF
DC
RF IN



TOP

RFD102A-DET: Microwave Energy Detector

$18.00

Add to cart

RFD102A-TB: 60Hz…6GHz Energy Harvesting Test Board

$33.00

Add to cart

RFD102A: Wireless Energy Harvesting Module

$12.00

Add to cart

OUR DESIGN SERVICES

Energy Harvesting Module & System Design

Any of our standard products can be customized for your application. We can support your application with matching, testing, antenna design, assembly and many other tasks. Have a new idea for a product? We can help you realize it. We are developing new products and are always interested in your feedback to guide our product development.

MMIC Design

We use Agilent’s Advanced Design System for MMIC design and PCB design. Previous designs completed are quad-band GSM power amplifier modules, 2.4-2.5GHz/5-6GHz wireless LAN power amplifiers, broadband power amplifiers, switch-filter designs, RFID detectors, RF/DC converters and filter designs.

Front End Module Design

We use Agilent’s Advanced Design System and Orcad PCB Editor for Front-End Module designs. Previous design examples are high-volume switch filter modules, dual-band 802.11a/b/g front end modules, 76GHz car radar module, RFID card design.

RFID Detector System

On an NSF Phase I & II grant to one of our clients, operating as a subcontractor, the RF Diagnostics design team created a complete RFID MEMS resonator detection system. Both hardware and software were developed under this contract. The work was published at an SPIE conference in July 2010.

LEARN MORE

NISKAYUNA, NY 12309 USA
518-810-6560
INFO@RFDIAGNOSTICS.COM

TOP

RF DIAGNOSTICS, LLC COPYRIGHT © 2017.

WEBSITE BY ROCK THE DEADLINE

- Home
- DA14 Asteriod
- Secret space plane
- Solar storm
- End of the world?
- UK monitoring
- Tracking
- Save money
- Get out of the EU
- UFO's
- Magnetic energy
- RF energy
- Radiant energy
- Perpetual
- Easy Steam!
- Irony- defined
- Funny Pics
- Internet Problems
- Star Wars
- Chat room
- Live music
- Kevzone
- Facebook Cheats
- Crashes

About us
Private Policy

RF energy..

This can extract some electricity from the air!



FREE ENERGY FROM AIR CIRCUIT PART 8/24



4 - Germanium Diodes (1N34)

2 - 100 µF 50V electrolytic capacitors

2 - 0.2 µF 50V ceramic capacitors







DIY RF METER: LED IS 100% POWERED BY RF RADIATION USING DETECTOR DIODES

$8.99

1 **Add to cart**

SAFE KIDS: LED Cell Phone Radiation Detector For DIY Science Project & Experiments || Test Phone Shields

NO batteries. it uses ONLY RF radiation power from cell phone. Yes, see with your own eyes how powerful cell phone radiation is when it powers a light from thin air. RF Safe's DIY circuit is the simplest detector for microwave radiation. The RF diodes convert microwaves from a cell phone to DC current to power an LED which emits visible light warning you of possible danger.

SKU: 636684233801 Categories: Cell Phone Radiation Safety, D-I-Y Tags: 1SS86 detector diode, Cell Phone Radiation Meter, germanium diode, LED RF Meter

A concurrent 915/2440 MHz RF energy harvester

L Fadel, L Oyhenart, R Bergès, V Vigneras, T Taris

▶ To cite this version:

L Fadel, L Oyhenart, R Bergès, V Vigneras, T Taris. A concurrent 915/2440 MHz RF energy harvester. International Journal of Microwave and Wireless Technologies, Cambridge University Press/European Microwave Association 2016, 8, pp.405 - 413. <10.1017/S1759078716000179>. <hal-01474918>

HAL Id: hal-01474918
https://hal.archives-ouvertes.fr/hal-01474918

Submitted on 7 Mar 2017

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.

A concurrent 915 MHz / 2440 MHz RF Energy Harvester

L. Fadel[1], L. Oyhenart[1], R. Bergès[1], V. Vigneras[1], T.Taris[1]

[1] Laboratoire IMS, UMR - 5218, Université de Bordeaux, 33405 Talence Cedex, France.

This paper presents the development of two dual-band RF harvesters optimized to convert far-field RF energy to DC voltage at very low received power. The first one is based on a patch antenna and the second on a dipole antenna. They are both implemented on a standard FR4 substrate with commercially off-the-shelf (COTS) devices. The two RF harvesters provide a rectified voltage of 1V for a combined power respectively of -19.5 dBm at 915 MHz and -25 dBm at 2.44 GHz and of -20 dBm at 915 MHz and -15 dBm at 2.44 GHz. The remote powering of a clock consuming 1V/5µA is demonstrated, and the rectenna yields a power efficiency of 12 %.

Keywords: Antennas and Propagation for Wireless Systems, Applications and Standards (mobile, Wireless, networks), Circuit Design and Applications.

Corresponding author: email: ludivine.fadel@ims-bordeaux.fr; phone: +33 540 002 615

I. INTRODUCTION

Today's the society is evolving toward creating smart environments where a multitude of sensors and devices are interacting to deliver an abundance of useful information. Essential to the implementation of this Internet Of Things (IOT) is the design of energy efficient solutions aiming toward a low-carbon-emission, namely green, society. Within this context, the energy harvesting appears as an alternative to provide systems with self-sustained operation. Many electronic devices operate in conditions where it is costly, inconvenient, or impossible to replace the battery. Examples include sensors for health monitoring of patients [1],[2], aircraft or building structural monitoring [3],[4], sensors in natural, industrial or hazardous environments, etc. The scavenging of natural ambient energy requires some specific conditions such as: daylight for solar energy [5], breeze for wind energy or motion for kinetic energy [6] to name a few. As consequences the exploitation of natural source does not fit with many cases of applications. On the other hand the electromagnetic (EM) [7], or Radio-Frequency (RF), energy is a human made source that is not dependent of weather conditions nor the daytime. It is so very attractive for wireless powering of remote devices. Furthermore the ever growing of commercial and personal wireless installations opens up to a 24 hour a day available energy in the vicinity of any human activity areas. The schematic of a general Wireless RF Power Transmission (WPT) system is shown in Fig.1. We talk here about far-field RF energy transmission [8], which is different from near-field RF energy transmission [9]. This later including inductive, capacitive or resonant coupling is a close contact transmission and is not relevant for remote devices. In Fig. 1, the receiver antenna collects the EM energy radiated by a RF source, and converts it into a RF signal. This RF signal is transferred to the rectifier by an impedance matching network, to be converted into DC power, which is further accumulated in a storage element. The main purpose in the deployment of WPT systems is the development of compact and efficient solutions. Most of the challenge concerns the implementation of harvesting modules, especially the antenna as its design defines the scavenging capability and the size of the RF harvester. At low frequency the transfer of energy is efficient, but the antenna footprint is large. To address the trade off between the efficiency of the WPT and the size of the modules, the frequency band located in the 433 MHz to 6 GHz frequency spectrums are preferred.



Fig. 1: Schematic of a Wireless RF Power Transmission (WPT) system

Over the last decade the research effort has focused on the development of WPT systems according two scenarios: the RF energy scavenging [10] and the RF energy transfer [11]. The two RF energy scavenging is an opportunistic collection of the RF ambient energy from the surrounding communication traffic. To improve the harvesting capability the scavenging RF harvesters are of wide-band type [12] and cover popular standards such as: DTV (470-610 MHz), GSM900, GSM1800, 3G (2.1GHz) and WiFi (2.4 GHz). Unfortunately these standards dedicated to convey wireless communications do not radiate a large RF power. As consequences the collected energy is weak, unpredictable and out of control. The RF energy scavenging remains a promising solution in the future as the increase of communication traffic could make it more reliable, and consistent with IOT applications. The second concept, namely RF energy transfer, assumes an identified source that is dedicated to perform the WPT. The amount of transmitted power is controlled by the source and the collected energy is larger than in scavenging approach. The licence-free Industry-Science-Medical (ISM) frequency bands located at 0.9, 2.4 and 5.8 GHz are usually exploited to support such a WPT scenario. Today the RF energy transfer in ISM Bands is not only promising, it becomes a reality as some pioneer companies propose some full kits: Powercast Corporation, AnSem and MicroChip to name a few. However there is still a lot of work to make the RF energy transfer an appropriate, low cost and easy-to-use solution for remote powering. One of the most critical point concerns the harvesting capability of the RF modules. So far the commercial kits referenced above only explore the 900 MHz ISM allocations to perform the WPT. This work proposes to demonstrate the interest of a concurrent harvesting at 915 MHz and 2.44 GHz. The design and implementation of a modified 4-stage doubler RF to DC converter, including a concurrent matching network, is first presented. The section III details the design of two types of multi-band antenna. The comparison between a single frequency and a multi-band WPT is exposed and the demonstration of the remote powering of a clock is reported as a case of application. To conclude a comparison of our results with the state of the art is exposed.

II. CONCURRENT RF TO DC CONVERTER

The Radio-Frequency IDentification (RFID) applications are the most popular systems exploiting the principle of RF energy transport. In passive RFID applications the reader transmits the RF power to the tag, and also sets up the communication. The RF to DC converter is designed to yield a maximum of power efficiency to the tag. Most of the time the reader and the tag are in line of sight and close to each other, these conditions improve the transmission of RF energy, the amount of power available at the tag antenna is large, typically between -15 dBm and -20 dBm. In RF energy harvesting the scenario is different. The distance between the RF source and the RF harvester ranges from 0.5 meter to 10 meters. The amount of collectable power is low, from -10 dBm to -25 dBm, and the remote powering is difficult. The RF harvesters are supposed to collect and to store the energy during a long period of time. Once the level of stored energy is large enough, it can be released to the application. For these reasons a rectifier dedicated to RF energy harvesting is first designed to yield a maximum of sensitive to increase its scavenging time and capability.

A) Rectifier Architecture

The rectifier architecture is based on voltage multipliers to provide an adequate output DC voltage. The architecture of the RF to DC converter, reported in Fig.2, includes a matching network based on a L-section, and a N-stage voltage multiplier based on Schottky diodes from Avago (HSMS285). The choice of the Schottky diode is very important in the design of the rectifier. A key parameter is its threshold voltage $V_{TH.}$ When only low power levels are available in the environment, the amplitude of the incident signal may be close to or even below this voltage. Below this voltage value, the diode will no longer conduct and the losses become predominant. For COTS devices the two Schottky diodes performing the best conversion efficiency in a 2.4 GHz range are HSMS-2850 from Avago and SMS-7630 from Skyworks [13].



Fig. 2: Architecture of the RF to DC converter

Focusing on the sensitivity, the RF to DC converter is designed to maximize the rectified voltage for an input power close to -20 dBm. The optimum number of stage is fixed to four according [14]. The footprint of each voltage doubler imposes the micro-strip line network. The micro-strip lines namely "junction" is set to minimum length, the micro-strip lines "access" are used as an additional degree to tune the input-matching network. Indeed, the L section in combination with the micro-strip distributed network is equivalent to a T section (Fig.3). Many combinations of Z_1, Z_2, Z_3 can achieve input matching at 900 MHz or 2.4 GHz. Some of them are very close for each frequency, so we choose one that allows a return loss (< - 10 dB at least) both at 900 MHz and 2.4 GHz.


P_{rf}
Z_1
µstrip line
Z_3
Junction & Access
4-stage Rectifier
Stub
Z_1
V_{DC}
L-matching
µstrip line Network

Fig. 3: Topology of the input-matching network

The equivalent narrow band model of the matching network is proposed for each frequency (Fig.4). At 915 MHz, the voltage multiplier, including the rectification stages and the micro-strip line network, is modelled with a shunt capacitor (5pF) and a shunt resistor of 270 Ω (Fig.4a). The stub, (Fig.3) is equivalent to an inductor (Fig.4a), which compensates the shunt capacitor. The input micro-strip line, (Fig.3), is a quarter wave impedance transformer, (Fig.4a) it converts the 270 Ω into 50 Ω. At 2.44 GHz the micro-strip line network distributing the RF signal to the voltage doublers (Fig.3), becomes inductive (Fig.4b). The stub is equivalent to a shunt capacitor of 120fF, its effect is negligible. The impedance transformation is actually performed by the input micro-strip line, which is modelled by a shunt capacitor (0,6 pF) and a series inductor of 5.6 nH.


P_{rf}
$\lambda/4$ / Z_0=90Ω
µStrip Line
270Ω
6nH
Stub
5pF
270Ω
L-matching
Voltage Multiplier &
µstrip Line Network
P_{rf}
5.6nH
(220+j32)Ω
0.6pF
µStrip Line
120fF
Stub
4,13nH
200Ω
L-matching
Voltage Multiplier &
µstrip Line Network

(a) *(b)*

Fig. 4: Equivalent model of the input matching network at 915 MHz (a) at 2,44 GHz (b)

To study the impact of the power on the diode, and input matching, behaviour the return loss of the 4-stage rectifier has been measured and plotted (Fig.5) for various input power P_{rf} at 9000MHz.



Fig. 5: Measured S_{11} of a 4-stage voltage multiplier with a L section at 900 MHz for various input power P_{rf}

As illustrated in the figure 5, the input return loss is not strongly affected by the input power if $P_{rf} < -15$ dBm. The RF harvesters developed in this work are dedicated to collect power from – 15 to – 25 dBm. Over this range the diode model can be considered as stable, and the slight frequency shift is still covered by the antenna bandwidth.

B) Rectifier Characterization

The power efficiency and the power sensitivity are two conversion characteristics of importance in RF harvesters. However, the RF harvester operating at low power level accumulates the energy in a storage element, to further release it to the application. In such accumulation mode the power sensitivity becomes more important than the power efficiency.

For the characterization the rectifier is not connected to a load. The load represents the equivalent impedance of the application (clock, sensor) to power. The effectiveness of RF-DC conversion of the rectenna and its DC ouput voltage varies depending on the load value. The rectifier is first characterized in a single tone mode, 915 MHz and 2.44 GHz respectively, and then in a dual-band mode. Measurements of the unloaded rectified voltage versus various input power P_{rf} are reported in Figure 6.



Fig. 6: Unloaded rectified voltage for various input power

To compare the results of the two considered tones, the target is fixed to a value of 1V. In a single tone mode, the required P_{rf} to rectify 1V is close to -18 dBm at 915 MHz, and would be larger than -15 dBm at 2.44 GHz. In a dual-band mode the circuit only needs a power P_{rf} of -20 dBm at each frequency. The dual-band rectification significantly improves the power sensitivity. The reverse breakdown voltage of the HSMS285 Schottky diode limits the input power to - 9 dBm, for which V_{rec} is 4,56 V.

III. ANTENNA DESIGN

To meet the low-cost constraints, the RF energy harvester will be implemented on a single low cost substrate, an FR4 PCB. For the antenna, there are more efficient substrates with a higher permittivity to reduce the size of the antenna or a lower losses but their cost is much higher than the improved performance. These powerful substrates fail to build low cost energy harvesters. This section exposes the design of two dual-band antennas implemented on a 1.6 mm FR4 printed circuit board. The fabrication uses a mechanical etching process with a 200µm resolution. We have chosen two complementary antenna topologies with a directional and omnidirectional radiation pattern.

A) Dual - band patch antenna

Emitting and receiving antennas do not usually meet the same constraints. Mobile devices such as smartphones and tablets use compact antennas (ifa, pifa…) to address the trade off between performance and size. Base stations can afford large efficient radiating elements (omnidirectional or directional antennas depending on the application). For energy harvesting purpose, micro-strip patch antennas are commonly used [15-17]. A rectangular micro-strip patch antenna (RMPA) is first developed to suit with both low cost technology of implementation and co-integration with the rectifier. Based on the cavity-model approximation, the resonant frequencies of the RMPA for the TM_{mn} mode is described in (1).

$$f_{mn} = \frac{c}{2\sqrt{\varepsilon_r}}\sqrt{\left(\frac{m}{L}\right)^2 + \left(\frac{n}{W}\right)^2} \tag{1}$$

W, L are the patch dimensions, $c = 3.10^8$m/s

The antenna dimensions, 68 cm^2 (8.8 x 7.8 cm), described Fig.7a are dependent to the frequency bands and the feed location is selected to only excite the fundamental modes TM_{01} and TM_{10}. Those modes permit to obtain a large aspect ratio (W/L = 2,7) but reduce the performance of the RMPA. On the other hand, TM_{01} and TM_{30} modes require an aspect ratio close to one but offer beneficial radiation patterns for our application. The RMPA is fed by a probe whose position (x,y) adjusts the matching both at 915 MHz and 2.44 GHz. This two operating bands of the proposed antenna are on cross polarization planes. The geometric parameters of RMPA have been optimized with an approximate model, the TL model [18], and with a full wave method. Details of the two approaches have been studied in [19]. The return loss of the RMPA is better at 915 MHz than 2.44 GHz because the maximum impedance of TM30 mode is 31 Ω [19]. The TM30 mode does not achieve 50 Ω because it is not a fundamental mode. This antenna has a maximum gain of 1.3 dB at 915 MHz (Fig.7b) and 2.5 dB at 2.44 GHz (Fig.7c). This two operating bands of the proposed antenna are on cross polarization planes.

The realized gains of the dual band patch antenna are lower than the classical patch antenna because the radiating efficiency is low, 60% for the TM_{01} mode and 30% for the TM_{30} mode. The FR4 substrate has a loss tangent of 0.02. The radiation efficiency of the dual band patch antenna is highly dependent of the substrate losses.



(a) *(b)* *(c)*

Fig. 7. Layout of the RMPA antenna (a) - Radiation pattern at 915MHz (b) and 2.44 GHz (c) Solid and dashed lines correspond to E-plane and H-plane respectively

B) Multi-band arm dipole antenna

The second antenna is a multi-band dipole type composed of three arms. Its dimension is about 23 cm^2 (11.1x2.1 cm), Fig.8a. Each arm is designed to work at one band of frequency. The longer one is for the 915 MHz, the middle one, not useful in our case, is for the 1.4 GHz and the last one, the smaller, is dedicated to 2.4 GHz [20].

All the geometric parameters have been optimized with a full-wave method in order to be matched both at 915/ 2440MHz. On Fig.6b and 6c, the radiation pattern is plotted for the elevation plane (orthogonal to substrate) of the simulated antenna. The maximum gain is 0.5 dB at 915 MHz and 3.4 dB at 2.44 GHz at 90°, on the substrate plane. The radiation efficiency is 99% at 915 MHz and 95% at 2.44 GHz.



(a) *(b)* *(c)*

Fig. 8. Layout of the multi-band arms dipole antenna (a) - Radiation pattern at 915 MHz (b) and 2.44 GHz (c). Solid and dashed lines correspond to E-plane and H-plane respectively

It is interesting to compare the characteristics and performances of the two types of antennas. Although the radiation efficiency of the dipole antenna is better than the patch antenna, the antenna gains are similar because the high directivity of the RMPA antenna compensates the low values of radiation efficiency. When there are no cost constraints, it is interesting to use high performance substrates for the design of RMPA antennas because they improve the radiation efficiency and consequently antenna gain.

Moreover, the integration of the antenna with the rectifier will not be made in the same way. Considering the patch antenna, the rectifier can be integrated on the ground plane allowing a more compact solution. The dipole antenna, which is ground plane free, is less sensitive to the surrounding environment in our case. The performance of the dipole antenna and especially the radiation efficiency are very weakly dependent of the substrate characteristics. The design of a dipole antenna can be easily reuse with other material such as Kapton®, paper, Plexiglas to name a few.

IV. WIRELESS POWER TRANSMISSION

This part presents the measurement results of the assembled RF harvesters in the context of Wireless Power transfer. The two dual-band harvesters are realized with COTS devices such as HSMS diodes and capacitors. Those elements are reported by heat-treating. The RF to DC converter board, including the matching network and the rectifier, is reported on the backside and connected to the radiation part, on the front side, through a via (Fig.9a). The dipole antenna is connected to the rectifier circuit using SMA connector (Fig.9b).



(a) *(b)*

Fig. 9. Dual-band RF harvesters based on patch antenna (a) – arms dipole antenna (b)

For the dual-band RF harvester based on patch antenna, the return loss, S_{11}, is measured for an input power of -20 dBm with a HP8720 network analyser. The patch antenna, the rectifier and the dipole antenna are centered at 915 MHz and 2.44 GHz with a low return loss ($S_{11} < -15$ dB), Fig.10. The return loss of the RMPA antenna is better at 915 MHz than 2.44 GHz because the maximum impedance of TM30 mode is 31 Ω (Fig. 6 and Fig. 7 of [16]). The TM30 mode does not achieve 50 Ω because it is not a fundamental mode.



Fig. 10. Measured return loss S_{11} of the dual-band rectfier, patch and arms dipole antenna

A) Remote Powering and Power Efficiency

The rectenna is connected to a clock, which mimics a low power application. The remote powering of this clock is performed in a furnished room of the lab according the schematic of Fig.11. The distance between the source and the antenna is fixed to 2 m. The clock is turned on for different scenarios of transmitted power. For each combination of power proposed in Fig.12, the RF power is first measured with a calibrated antenna and a power meter. Then, the rectenna is measured and P_{eff} is the ration between the power delivered to the load (here the clock) and the power available at the antenna.



Fig. 11. Schematic and picture of the scene of remote powering of a clock

The power efficiency of the patch and the dipole rectenna is worked out from these experiments and reported in Fig.12. The power efficiency η is defined as the ratio between the DC power delivered to the clock and the RF power collected by the antenna.



(a) *(b)*

Fig. 12. Power efficiency of the dual-band RF harvester based on the patch (a) and the arms dipole (b) antenna

The minimum power required to turn on the clock with the patch-based harvester, Fig. 10.a, is a two tone signal featuring: -19.5 dBm at 915 MHz and -20 dBm at 2.44 GHz. At this point, the power efficiency is 12.5 %, which corresponds to a DC output power of 2.7 µW/1V.

A maximum efficiency of 24 % occurs for a combined power of -16.5 dBm at 915 MHz and -14 dBm at 2.44 GHz. The harvester is able to deliver a DC ouput power of 15 µW. The harvester based on the arm dipole antenna needs a minimum power of -19.9 dBm at 915 MHz and -15 dBm at 2.44 GHz at the antenna to turn on the clock. For these conditions of remote powering, the efficiency of the harvester is 11 %. It delivers a DC power of 3.8 µW/1.15 V. The maximum power efficiency, 15.5 %, yields for an input power of -14.4 dBm at 915 MHz and -9.7 dBm at 2.44 GHz, the DC output power is 21 µW.

This scenario of remote powering figures out that the harvester based on the patch antenna exhibits a better power efficiency than the harvester combined with the dipole element. This difference is due to the antenna gains. Referring to Fig. 7 and Fig. 8, the gain of the patch antenna is larger (+0.8dB) at 915 MHz and lower (-0.9 dB) at 2.44 GHz than the dipole element. However the rectifier, referenced in [16], achieves a power efficiency of 17% at 915 MHz and only 5% at 2.44 GHz for an input signal of -15 dBm. As consequences the patch-based harvester is able to extract more power from a 915 MHz signal than the dipole-based harvester can do at 2.44 GHz. For this reason the overall efficiency of the patch harvester is better.

B) Power Sensitivity

The power sensitivity is measured with the same scenario of Fig.11 but the clock is disconnected. The output voltage is reported for different combination of collectable power at the antenna in a dual-band configuration.



(a) *(b)*

Fig. 13. Rectified voltage of the RF harvester based on patch (a) and arm dipole (b) antenna

To rectify a 1V DC voltage, the patch-based harvester, Fig.13a, requires a two dual-band configuration: -19.5 dBm at 915 MHz and -25 dBm at 2.44 GHz, which is equivalent to an input power of -18.4 dBm (or 14 µW). For the same purpose the dipole-based harvester, Fig.13b, needs a dual-tone of -22.1 dBm at 915 MHz and -17.8 dBm at 2.44 GHz. The equivalent input power of this 2-tone signal is -16.5 dBm (or 22 µW). The patch-based harvester exhibits a better sensitivity than the dipole harvester for the same reason exposed in the part A of this section. In Fig.6, which reports the power sensitivity of the rectifier part only, the overall sensitivity is almost the same for the dipole harvester. It is improved by 1.8 dB for the patch harvester due to the additional gain of the antenna at 915 MHz.

C) Discussion and Comparison with the state of the art

An important characteristic of a remote powered device is its size. Indeed it is expected to be as small as possible to make it unobtrusive to our closest environment. In a scenario of RF harvesting the antenna footprint determines the compactness of a harvester operating Ultra High Frequency (UHF) bands. To complete the comparison between the two harvesting modules developed in this work, two figures of merit, FOM_{sens} and FOM_{eff}, including the size of the antenna, are proposed in (2) and (3).

$$FOM_{sens} = \frac{V_{REC@Psens}(V)}{\frac{P_{sens}(\mu W)}{100\mu W} \cdot \frac{A_{ant}(cm^2)}{100cm^2}} \tag{2}$$

With: P_{sens} the input RF power required to provide $V_{REC@Psens}$ the unloaded rectified output DC voltage, and A_{ant} the area of the antenna.

$$FOM_{eff} = \frac{\eta(\%)}{\frac{P_{eff}(\mu W)}{100\mu W} \cdot \frac{A_{ant}(cm^2)}{100cm^2}} \tag{3}$$

With: P_{eff} the input RF power required to achieve η the overall power efficiency.

FOM_{sens} and FOM_{eff} do not represent the same scenario of application. The FOM_{sens} illustrates the capability of the rectenna to start collecting energy and store it in an element such as a capacitor or a battery to further release it. FOM_{eff} demonstrates the capability of the RF harvester to yield "on time powering": the rectenna is connected to an application and supply it on time. Both are reported in the Table I, which also includes some references of the state of the art. The ability of the proposed rectenna to simultaneously operate in two frequency bands, significantly improves the power sensitivity.

Table I. Comparison with the state of the art

Ref.	Freq (GHz)	Efficiency ($\%@P_{rf}$)	Sensitivity ($V_{rec}@Prf$)	Number of stage	Schottky diodes	Size (cm^2)	FOM Sens	FOM Eff
[21]	0.9	15% @ -10dBm	0.75V @ -10dBm	1	SMS-7630	15×15	1.9	6.6
[21]	2.4	9% @ -13dBm	0.9V @ -13dBm	1	SMS-7630	15×15	1.25	8
[22]	2.45	10.5% @ -20dBm	0.075V @ -20dBm	1	SMS-7630	3.4×3.4	6.5	905
[23]	0.915/ 2.45	14%@ -20/-20	0,36V@ -10/-10	1	SMS-7630	6×6	0.5	185
[24]	1.8/2.2 /2.5	55%@ -10dBm	300mV@ -32dBm 3tones	1	SMS-7630	7×7	20	112
This work Dipole	0.915/ 2.44	**11% @ -20/-15dBm**	**1V @ -22/-18dBm**	4	HSMS-2850	2.1×11	**19.8**	**136**
This work Patch	0.915/ 2.44	**12.5% @ - 19.5 dBm/ -20dBm**	**1V @ -19.5dBm/ -25dBm**	4	HSMS-2850	7.8×8.8	**10.5**	**100**

According the Table I, the patch-based harvester exhibits the highest sensitivity to rectify 1V with a dual-tone featuring: -19.5 dBm at 915 MHz and only -25 dBm at 2440 MHz. The FOM_{sens} represents the trade-off between the sensitivity performances of a rectenna and the antenna area. The FOM_{eff} rates the efficiency performances to the antenna area. For these two figures of merit, the rectenna based on the multi-arm dipole element yields the best trade-off, both for FOM_{sens} and FOM_{eff}, compared to the patch-based solution. This dual tone and multi-arm dipole harvester is close to the work proposed in [24] which exhibits the highest FOM_{sens} reported so far in the literature to our knowledge.

V. CONCLUSION

The range of power collectable in a scenario of RF harvesting varies from -15dBm to -25dBm. To address this purpose the rectenna proposed in this work are optimized to operate at a RF input power close to -20 dBm (or 10 µW). To further improve the ability to collect the RF energy, these rectenna, developed with Schottky diodes HSMS285 from Avago, perform a concurrent harvesting in the 915 MHz and 2.44 GHz ISM bands. The harvester including a patch antenna implemented on a 1.6mm FR4 PCB achieves the highest sensitivity. It provides a 1V-rectified voltage for a dual-tone excitation of -19.5 dBm at 915 MHz and -25 dBm at 2.44 GHz. For these conditions of operation the rectenna yields a power efficiency of 12.5%. To take into account the dimensions of the haverster, two figures of merit, FOM_{sens} and FOM_{eff} including the size of the antenna, respectively related to the power sensitivity and the power efficiency are proposed. The rectenna developed with the arm dipole element exhibits the highest figures of merit. A case of application is proposed with the remote powering of a digital clock consuming 1V/5µA. The patch based harvester turns on the device with a dual tone excitation at the antenna of -19.5 dBm at 915 MHz and -20 dBm at 2.44 GHz. For the same scenario the harvester connected to the multi-arm dipole element needs a power of -22.1 dBm at 915 MHz and -17.8 dBm at 2.44 GHz.

REFERENCES

[1] T. Paing, A. Dolgov, J. Shin, J. Morroni, J. Brannan, R. Zane, and Z. Popovic, "Wirelessly powered wireless sensor platform'' in Eur. Microw. Conf. Dig, Munich, Germany, Oct. 2007, pp. 241-244.

[2] J. Bernhard, K. Hietpas, E. George, D. Kuchima, and H. Reis, ''An interdisciplinary effort to develop a wireless embedded sensor system to monitor and assess corrosion in the tendons of pre-stressed concrete girders,'' in Proc. IEEE Top. Conf. Wireless Commun, 2003, pp. 241-243.

[3] C. Walsh, S. Rondineau, M. Jankovic, G. Zhao, and Z. Popovic, ''A conformal 10-GHz rectenna for wireless powering of piezoelectric sensor electronics,'' in IEEE MTT-S Int. Microw. Symp. Dig, Jun. 2005, pp. 143-146.

[4] X. Zhao, T. Qian, G. Mei, C. Kwan, R. Zane, C. Walsh, T. Paing, and Z. Popovic, ''Active health monitoring of an aircraft wing with an embedded piezoelectric sensor/actuator network,'' Smart Mater. Struct, vol. 16, no. 2007, Jun. 2007, pp. 1218-1225.

[5] K. Lin, J. Yu, J. Hsu, S. Zahedi, D. Lee, J. Friedman, A. Kansal, V. Raghunathan, and M. Srivastava, "Heliomote: Enabling long-lived sensor networks through solar energy harvesting," in 3rd Int. Conf. Embedded Networked Sensor Syst., Nov. 2005, p. 309.

[6] J.A. Paradiso and T. Starner, "Energy scavenging for mobile and wireless electronics," IEEE Pervasive Computing, Vol. 4, and Issue: 1, Jan-March 2005, pp. 18- 27.

[7] K. R. Foster, "A world awash with wireless devices", IEEE Microwave magazine, vol. 14, Issue 2, March 2013, pp. 73-84.

[8] T. Le, K. Mayaram, and T. Fiez, "Efficient far-field radio frequency energy harvesting for passively powered sensor networks," IEEE J. Solid-State Circuits, vol. 43, no. 5, May 2008, pp. 1287-1302.

[9] J. Hirai, T.W. Kim, and A. Kawamura, ''Wireless transmission of power and information for cableless linear motor drive,'' IEEE Trans. Power Electron, vol. 15, 2000, pp. 21-27.

[10] H. Nishimoto, Y. Kawahara, and T. Asami, "Prototype implementation of ambient RF energy harvesting wireless sensor networks," IEEE Sens. J., Nov. 2010, pp. 1282-1287.

[11] BN. Shinohara, "Power without wires," IEEE Microw. Mag, vol. 12, no. 7, Dec. 2011, pp. S64-S73.

[12] M. Pinuela, P.D. Mitcheson, S. Lucyszyn, “Ambient RF Energy Harvesting in Urban and Semi-Urban Environments”, IEEE Trans. On Microwave Theory and Techniques, vol. 61, N°7, July 2013.

[13] Simon Hemour, Ke Wu “Radio-Frequency Rectifier for Electromagnetic Energy Harvesting : Developement Path and Future Outlook”, Proceeding of the IEEE, Vol.102, No.11, November 2014.

[14] T. Taris, L.Fadel, L.Oyhenart, V. Vigneras, “COTS-Based Modules for Far-Field Radio Frequency ”, IEEE NEWCAS, Paris, France, June 2013, pp. 1-4.

[15] Sika Shrestha, Sun-Kuk Noh, and Dong-You Choi, « Comparative Study of Antenna Designs for RF Energy Harvesting » International Journal of Antennas and Propagation Volume 2013, 10 pages.

[16] Z. W. Sim, R. Shuttleworth, M. J. Alexander, B. D. Grieve, « Compact patch antenna design for outdoor RF energy harvesting in wireless sensor networks, Progress In Electromagnetics Research, Vol. 105, 273–294, 2010.

[17] Naimul Hasan, Santu Kumar Giri, « Design of low power RF to DC generator for energy harvesting application », International Journal of Applied Sciences and Engineering Research, Vol 1, Issue 4, 2012.

[18] H. J. Visser, "Approximate Antenna Analysis for CAD", Wiley, 2009.

[19] R. Berges, L.Fadel, L. Oyhenart, V. Vigneras, T. Taris, “A dual Band 915MHz/2.44GHz RF Energy Harvester”, EUMW, Paris France, Sept 2015.

[20] Y-Y.Lu, J. Guo, H-C. Huang, “Design of Triple Symmetric Arms Dipole Antenna for 900/1800/2450MHz Applications”, Conf on Intelligent Information Hiding and Multimedia Signal Processing”, 2014.

[21] D. Masotti, A. Costanzo, M. Del Prete, V. Rizzoli, “Genetic-based design of a tetra-band high-efficiency radio-frequency energy harvesting system,” IET Microwaves, Antennas Propagation, vol.7, no. 15, June 2013, pp. 1254-1263.

[22] G. Vera, A. Georgiadis, A. Collado, and S. Via, “Design of a 2.45GHz rectenna for electromagnetic (EM) energy scavenging”, Proc. IEEE Radio and Wireless Symp, 2010, pp. 61-64.

[23] K. Niotaki, S. Kim, S. Jeong, A. Collado, A. Georgiadis, and M. Tentzeris, “A compact dual-band rectenna using slot-loaded dual band folded dipole antenna,” IEEE Antennas and Wireless Propagation. Lett. vol. 12, pp. 1634–1637, 2013.

[24] C. Song, Y. Huang, J. Zhou, J. Zhang, S. Yuan, and P. Carter, “A High-efficiency Broadband Rectenna for Ambient Wireless Energy Harvesting”, IEEE Transactions on Antennas and Propagation, accepted May 2015.

Bibliographies

Ludivine FADEL received the Ph.D in electrical engineering from the University of Bordeaux, France, in 2004. She is an Associate Professor at Bordeaux University and her main research interests include wireless power transfer and energy harvesting, materials and printing technologies for RF application.

Laurent Oyhenart received the Ph.D. degree in electrical engineering from the University of Bordeaux, Bordeaux, France, in 2005. He is currently an Associate Professor with the University of Bordeaux and develops his research activities in the IMS laboratory. His research interests include computational electromagnetics, photonic crystals and antenna synthesis.

Romain Bergès is a PhD student at IMS Laboratory. He received his Master from Bordeaux University in Electronic, in 2014. His current research focuses on RF Energy Harvesting.

Valérie Vigneras is a full professor in the Polytechnic Institute of Bordeaux and conducts research in the IMS Laboratory on complex structures (mixtures, structured media, self-assembled media) both by simulation to predict or optimize their properties and by characterization before their integration in high frequency systems (antennas, electromagnetic compatibility, radar shieldness…).

Thierry Taris is a full professor at the Bordeaux Institute of Technolgy (Bx-INP). He joined the IMS lab in 2005 where is research interests are related to the Radio-frequency Integrated Circuits in Silicon technologies.

List of figures and tables

Fig. 1: Schematic of a Wireless RF Power Transmission (WPT) system.
Fig. 2: Architecture of the RF to DC converter.
Fig. 3: Topology of the input-matching network.
Fig. 4: Equivalent model of the RF to DC converter, 915 MHz (a) - 2,44 GHz (b).
Fig. 5: Measured S_{11} of a 4-stage voltage multiplier with a L section at 900 MHz for various input power P_{rf}.
Fig. 6: Unloaded rectified voltage for various inpout power.
Fig. 7. Layout of the RMPA antenna (a) - Radiation pattern at 915MHz (b) and 2.44 GHz (c) Solid and dashed lines correspond to E-plane and H-plane respectively.
Fig. 8. Layout of the multi-band arms dipole antenna (a) - Radiation pattern at 915 MHz (b) and 2.44 GHz (c). Solid and dashed lines correspond to E-plane and H-plane respectively.
Fig. 9. Dual-band RF harvesters based on patch antenna (a) – arms dipole antenna (b).
Fig. 10. Measured return loss S_{11} of the dual-band rectfier, patch and arms dipole antenna.
Fig. 11. Schematic and picture of the scene of remote powering of a clock.
Fig. 12. Power efficiency of the dual-band RF harvester based on the patch (a) and the arms dipole (b) antenna.
Fig. 13. Rectified voltage of the RF harvester based on patch (a) and arm dipole (b) antenna.
Table I. Comparison with the state of the art.

Fun with Less Kilowatts: The Lectenna

By Vernon Trollinger, March 14, 2017, Energy Efficiency, Events & Fun, Family

Welcome to Fun with Less Kilowatts! We believe that science experiments at home can be a creative way to engage kids in learning while having fun. They can be educational AND great activities to keep your kids busy and away from the television. Each month, we'll feature a new science experiment that can be a great resource for parents and teachers.

The Lectenna

Did you know you that the energy from radio waves can be converted back into electric energy? It's true and you can make a *simple* two-component circuit that you and your kids can use to find 2.45 Ghz radio waves around your home. These are the same radio waves used by microwaves, WiFi network routers, bluetooth devices, smart phones, cordless phones, smart meters, and smart home systems that use Zigbee.

YouTuber pjaffeva posted this brilliant project showing how. Plus, there's also a link to a PDF set of instructions on Google Drive that you can download.

The Materials

- One HLMP-D150 Avago low current LED. Costs about 50¢/each. Available from: Amazon, Digikey, Mouser
- One Hitachi 1SS106 low capacitance Schottky diode. Pjaffeva recommends this Hitachi-made diode as being the only one in this shape that will work. But they're also hard to find. Currently, you can get them from LittleDiode's ebay store in the UK. Costs $6.38 but the bulk of that price is shipping from the UK.



You'll also need:

- An operating WiFi router
- A bamboo kabob skewer
- Two pieces of tape

The Directions

1) Look on the base of the LED and find the side with the flat edge. This marks the negative or cathode side. Carefully splay the two wire leads away from each other as far as they will go. Make sure the one adjacent to the negative side gets bent over the flat edge so identify it. You can also mark it with a little spot of colored nail polish.

Categories

Careers/Jobs
Charity & Community
Energy Efficiency
Events & Fun
Family
FAQs
Green
Home Improvement
Hurricane Prep
Moving
News
Recipes
Save Money
Small Biz
Special Offers

Subscribe via Email

Subscribe

Subscribe via Email

Subscribe

Subscribe

Subscribe in a reader

Archives

December 2017
November 2017
October 2017
September 2017
August 2017
July 2017
June 2017
May 2017
April 2017
March 2017
February 2017
January 2017
all archives

Featured Articles

Prepare for Christmas With Green Cleaning Methods



2) Next, find the band that runs around the Schottky diode. This identifies the negative end of this diode. The other end is the positive or anode end.

Using your fingers:

3) Twist the end of the negative or cathode wire from the LED onto to the positive or anode end of the Schottky diode.

4) Then twist the end of the negative or cathode end of the Schottky diode onto to the positive or anode end of the LED.



You have just made a “rectenna” and you’ll need to keep the assembly and the wires straight as possible. The length of the wires should be about 6 cm long (a hair short of 2 3/8 inches).

5) Tape the two diodes to one end of the bamboo skewer.

6) With a WiFi router on and running, hold the diode near an antenna on the WiFi router.

The Result

The LED should light up as it draws closer to the antenna (signal). The further away it is, the weaker the signal and the less it can grab to light up.

The Science

The WiFi routers uses radio waves to transmit data to and from computers and other devices in your home. Radio waves behave like water in a glass, they ripple or oscillate at a certain number of times or frequency per second. A radio wave’s wavelength is the distance covered by one complete cycle of a radio wave — from peak to valley.

Radio waves used by WiFi routers, bluetooth devices, microwaves, etc., broadcast signals in the 2.45 gigaherz (Ghz) range or 2.45 billion oscillations per second. That means the signal wavelength is about 12 cm. To pick up signal, however, you only need an antenna that’s half as big— 6 cm. When the radio waves strike this antenna, called a 1/2 dipole (“di”=two), the energy excites the antenna’s

Holiday Kitchen Safety – Cooking with Kids
How to Shop for Old Window Repairs
How Do I Clean A Clothes Dryer?
Gobble Up These Convenient Thanksgiving Deals on Meals

The "Rectenna": Because the radio waves cause voltage to flow one direction and then the opposite direction, the current is called an alternating current (AC). By connecting a diode to both poles of the antenna it converts the AC current to flow only in one direction, called direct current (DC). The antenna becomes a "rectenna".

How the diodes work: The diodes work as one-way valves for electricity, allowing voltage to flow forward but not back. In the case of the rectenna, AC current caused by the radio wave sends a positive charge down one of the antenna poles and then the other. By putting the Hitachi 1SS106 diode across both poles, the diode only lets the positive charge coming down one of the antenna poles through. The LED is actually a Light Emitting Diode and works the same way as a regular diode except that when it's on, it lights up. Meanwhile, Schottky diodes turn on at a lower voltage than other diodesand because the rectenna can only catch a fraction of the WiFi's broadcast power, the Schottky diode can rectify that little bit of AC to DC.



When we connected our diodes together, their polarity formed a loop that only allowed voltage to flow one way and thus light the LED. Brilliant job, pjaffeva!

Do you have any fun and kid-friendly science experiments you'd like to see us try for Fun with Less Kilowatts? Share with us in the comments!

Be Sociable, Share!

Tweet Like 0

About Vernon Trollinger

A native of Wyomissing Hills, PA, Vernon Trollinger studied writing and film at the University of Iowa, later earning his MA in writing there as well. Following a decade of digging in CRM archaeology, he now writes about green energy technology, home energy efficiency, DIY projects, the natural gas industry, and the electrical grid.

Tags: family fun, Fun with Less Kilowatts, kids, science experiments

Like 338K people like this. Sign Up to see what your friends like.

Follow @BounceEnergy 28.2K followers

Share 1 Tweet 0 Pin 0

Follow Bounce: Share this on:

0 Comments Bounce Energy Blog 1 Login

Recommend Share Sort by Best

Start the discussion…

LOG IN WITH

OR SIGN UP WITH DISQUS ?

Name

Be the first to comment.

ALSO ON **BOUNCE ENERGY BLOG**

Choosing the Best Home Generator for Your Emergency Needs

1 comment • 3 years ago

T&B Electric LTD — Nice article covering the difference between portable and permanent generators. Some homeowners "back feed" …

Career Opportunity with Bounce Energy | PHP/Integration Developer

1 comment • 3 years ago

Chris Jones — Sounds like a great opportunity.

Take Care of Your Favorite Gadgets with Great Waterproof Tech

1 comment • 2 years ago

erna — Vermon thanks for your post, great as always! Coolest is cool I got one of this :) what's funny I also have swimmo watch for swimmers …

5 Quick DIY Home Improvement Fixes to Get Your Home Through Winter

1 comment • 3 years ago

Steve Veach — Excellent and informative blog post! I am a HVAC Contractor in Chicago and have found a new site to check in on. Thank …

Subscribe Add Disqus to your siteAdd DisqusAdd Privacy DISQUS

Copyright © 2017 Bounce Energy. Learn more with Bounce Energy Articles | Charity and Community Involvement

Follow Bounce: Share this on:


Recovering the position in the cycle of the sinusoidal wave
Signal
0
Time
Analogue signal
10001101111000001011010101010
K3OPS embedded System with a digital-to-analog converter.
K3OPS®
SAYING GOODBYE TO BATTERIES
Of conventional batteries we only have kept the shapes
Batteries available in sizes: AA - AAA - AAAA
Mercury free, nickel free, cadmiun free, lead free, zinc free and lithium free

An electromagnetic field uses the photon as an elementary particle to transmit force. It combines:

- **A magnetic field** *force resulting from the movement of loads μT.*
- **An electric field** *force created by the attraction of repulsion loads, measured in volts per meter - V/m.*

With an energy determined according to the speed of light, the RF are by far the best medium to transmit any kind of information.

The multiplication of wireless communications systems in our environment ensures sufficient microwave leakages to harvest from the ambiant and enough energy to convert into DC electricity. Electromagnetic fields are everywhere and since they carry energy, they became the best candidate to deliver an endless source of renewable energy.

$\vec{B}$ is the magnetic induction expressed in T refered to **Nikola Tesla**, "Father of Free Energy", which is at the origin of the electromagnetism.

Using meta-materials combined with nanotechnology has deeply increased the performance and miniaturization of rectennas embedded in K3OPS system. Our products operate autonomously, offering an endless supply of green energy in a respectful and environment-friendly approach.

principles and beautiful sentences. At that point in time I would have simply been Xin, a child like any other...

But one day I dreamed. I woke up far away, somewhere else, in another past. I decided to change my destiny and even if I was supposed to become a mathematician, I eventually decided to create, because already as a child my heart was chasing the stars.

Of the hundreds of directions shown to me after graduating, only one captured my attention: a single goal... Build the impossible for a safer world. So, over the past 3 years, our real challenge to overcome for all RF Energy Harvesting technics was to optimize electricity conversion. The massive proliferation of wireless telecommunication systems since the past two decades brought a saturation of the electromagnetic fields with a constant growth of 15% every year in our environments. As a result, this situation reversed the base problem that makes today Harvesting RF Energy a game changer. The key was the Power Management System.

We are far beyond the conversion constraint and performance by controlling "RF-interferences", by harvesting different frequencies *from near and far*, by using Metamaterials combined with nanotechnologies. We dramatically have improved power conversion efficiency and reduced the size of our Energy Harvesting systems embedded in all K3OPS' products.

Thanks to Nikola Tesla, my inspiring mentor, K3OPS' products have reached by far their objectives in terms of converting and performance, offering an endless efficient source of green energy, reliable in an environmentally friendly approach.

Xin WEI Co-Founder of K3OPS technology with Alexandre Despallieres


Low Pass Filter
Matching network
Rectifier
DC Output

The Rectenna was invented in 1964 by William C. Brown, patented in 1969. It is a rectifying antenna used to convert microwave energy into DC. A simple Rectenna consists of a dipole antenna with an RF diode connected across the dipole elements. The diode rectifies the AC current induced in the antenna to produce DC power.

RF Energy Harvesting Battery
RF Energy Harvesting Battery

K3OPS batteries
K3-Case

K3OPS Copyright © 2017 Alexandre Despallieres and Xin Wei - All rights reserved.

Centre for Collaboration in Electromagnetics and Antenna Engineering is a centre for research collaboration established to foster research in electromagnetics and engineering conducted by Macquarie University researchers and prominent collaborators from external institutions, including people from industry and overseas ins We have state of the art research ficilities including a NSI-700S-50 spherical nearfield anechoic chamber, 3 Vector Network Analyzers (capable up to 22GHz, 50GHz, and respectively), state-of-the-art embroidery machine DreamCreator-XE-VM5100 for embroided antennas, Dielectric Characterization Kit - High Temperature Probe (2 20GHz), as well as several in-house and commercial licenced softwares.

Our recent and ongoing research projects are:

- Wireless Implantable Bio-Telemetry System and Miniature Antenna Design
- Wireless Freedom for Lab Rats
- Flexible and Wearable Antennas for Biomedical and Healthcare Applications
- Characterizing Properties of Carbon nano Tubes at Microwave Frequencies
- Electromagnetic Band Gap (EBG) Resonator Antennas
- Leaky-Wave Antennas for Advanced Wireless Systems
- Shared Aperture Arrays for Space Borne Applications
- Novel Dielectric Resonator Antennas
- Super Wideband Antennas
- Focal Plane Arrays for Radio Astronomy
- Archimedian Spiral Metamaterials
- Frequency Selective Surfaces for Energy-Saving Glass Panels
- Dual-Band Artificial Magnetic Conductor (AMC) Surfaces
- Antenna Technologies for Ultrawideband (UWB) Systems
- High Gain Antennas with Planar Surface-Mounted Short Horns
- Photonic Crystal/EBG Based Horn Antennas
- Broadband Microstrip Patch Antennas for Wireless Computer Networks
- Theoretical Analysis of Photonic Crystal Structures
- New Closed-form Green's Functions for Microstrip Circuits and other Layered Structures
- Integrated-design of Hybrid-resonator Antennas for Broadband Wireless and other Communication Systems
- Singularity-enhanced Finite-different Time-domain (FDTD) Method for Diagonal Metal Edges, Strips and Films
- Low-profile Dielectric-resonator (DR) Antennas

Wireless Implantable Bio-Telemetry System and Miniature Antenna Design

The two major challenges associated with the conversion of a wireless system operating in air to an implantable version, antenna detuning and biocompatibility, are a in a coherent way. An RFID-based biomedical telemetry system designed for free-space operation was chosen as the starting reference. A new, pin-compatible, spa antenna with a ground plane was designed, fabricated and tested, to replace the original “free-space” antenna in the active RFID tag without making any other chang tag circuit, such that the tag would function well when it is placed under rat skin and fat. Biocompatibility and potential antenna detuning due to rat tissue variati addressed in the design process, without significantly increasing the tag physical height, by applying a thin coating of biocompatible material directly over the ante operation of the medical telemetry system was successfully demonstrated, with the tag placed under rat skin and fat, and its range of 60-72 cm was found to be suf support medical research experiments conducted with rats in cages. Due to the biocompatible coating over the antenna, antenna matching is very insensitive to c tissue dielectric constants and thickness. The footprint of the new antenna is 33% less than that of the original antenna, its measured 10 dB return-loss bandwidth is 1 11%, and overall efficiency is 0.82% at 920 MHz.





Wireless Freedom for Lab Rats

We are developing a fully implantable wireless telemetry system. This is a joint research project with BCS Innovations and the Australian School of Advanced Medicine will be first used in the research conducted in ASAM, with rats, on hypertension. To date the major method of controlling hypertension is through the use pharmaceuticals. The pathway to approval for most drugs for human use involves pre-clinical (animal) trials. Lab rats are considered biologically similar to humans, pa in terms of their social behaviour. Therefore, it is very important to not compromise the pharmaceutical trials by unnecessarily stressing the rats by harnessing the monitoring equipment. One of the technical challenges of developing an implantable system that monitors the various signals, is the relatively small size requ implantable telemetry system is a miniature transceiver implanted in an animal that senses, processes and transmits data via a wireless link to monitor vital signals of c freely moving laboratory animals. This is crucial in giving researchers flexibility and reliability, especially in studies with special experimental settings using mazes wheels and treadmills. We have plans to develop a fully implantable telemetry system for subcutaneous or intraperitoneal placement in rats that monitors th parameters as well as blood pH and chemistry, nerve activity and circadian respiratory rate rhythms. The aim of this project is to eventually develop a system with capabilities that costs less than what is currently available, to provide more universities and researchers with the opportunity to use this technology.

In this sequel, initially, when a module of our original system was placed under the skin of a rat, the wireless link failed completely. It could not send a temperature rea a centimetre! The point of failure was the commercial antenna in the module that had been designed to work outside the body, in air. Such antennas do not work unde because the electrical characteristics of skin (rat or human) are significantly different from that of air. Hence the main challenge was to design an antenna that works v placed under the skin. In addition, it was necessary to cover the module and the antenna by biocompatible material, which also affects antenna performance. Possible of skin characteristics from one rat to another or one person to another were considered. Unlike the commercial antenna, we wanted our antenna to radiate less into th the rat/person and more away from the body because that not only increases the quality of the wireless link, maximum range (distance between implanted mo monitoring station) and battery life but also reduces the exposure of the body to radio-frequency waves. Indeed we had to consider the electromagnetic effects of fat material around the antenna. We were able to meet all these requirements with a novel compact antenna design that is approx. one third the size of the original co antenna. We successfully demonstrated wireless telemetry transmission of temperature with the new module placed under rat skin and the monitoring station pl distance of up to 80 cm! This range is sufficient for our immediate target application supporting new medical research by Professor Paul Pilowsky's team. If necessary, further extended by increasing the power level at the monitoring station.





Flexible and Wearable Antennas for Bio-Medical and Healthcare Applications

Body Centric Wireless Communication is a rapidly growing research area targeted for medical, healthcare, public safety and defense applications. The need to address transceiver specifications and real-time scenarios in close proximity to human body is continuously evolving antenna system research. Several novel miniature antennas havi dual- and wide-band operations have been designed and tested for Wireless Body Area Network (WBAN). They have significant advantages of small size, wide radiation pat the human body for maximum coverage and are less sensitive to the gap variation between human body and antenna.

A compact ultra wideband antenna is shown below with strong notch-band rejections up to VSWR = 26, that is tunable over a wide frequency range from 3.55GHz to 6. been designed. To estimate the stub length to notch frequency for a given interfering application, analytical expressions for the normalized stub length which is indep substrate dielectric constant is also presented. This helps to avoid hit-an-trail method and gives a good estimate of initial design parameters for notch. Proposed antenna radiation patterns and yields a measured 10dB return-loss bandwidth from 3GHz to 10.5GHz.



Characterizing Properties of Carbon Nano Tubes at Microwave Frequencies

Carbon Nanotube (CNT) yarns are novel CNT-based materials that extend the advantages of CNT from the nano-scale to macro-scale applications. We have modelled CN potential data transmission lines. Test structures have been designed to measure electrical properties of CNT yarns, which are attached to these test structures using gold testing and microwave S-parameter measurements have been conducted for characterisation. The observed frequency independent resistive behaviour of the CNT yarn promising indicator that this material, with its added values of mechanical resilience and thermal conductivity, could be invaluable for a range of applications such as B Networks (BAN). A model is developed for CNT yarn, which fits the measured data collected and agrees in general with similar data for non-yarn CNTs.





Electromagnetic Band Gap (EBG) Resonator Antennas (ERA)

We have designed, fabricated, and measured antennas based on 3D, planar and 1D EBG structures (i.e. photonic crystals). These flat microwave antennas, known as EBG antennas or Fabry-Perot cavity antennas, can give gains of about 20dB and very good efficiencies.

Enhancing Radiation Characteristics of ERAs by Improving Aperture Phase Distribution

This work focuses on achieving superior radiation characteristics of ERAs by improving their aperture phase distributions. A unique method, utilizing full-wave simula analytical analysis, has been developed to design Phase Correcting Structures (PCS) for ERAs. This method uses actual phase distribution on the physical aperture of ERAs relying on geometric optics. Several Phase Correcting Structures (PCSs) have been designed, which were later validated with the measurements of their fabricated p Tremendous improvement in the radiation performance is witnessed in both simulated and measured results. These exciting initial results validate our proposed method indicate an existence of a great potential to be explored. The figure below shows the field propagation above an ERA: (a) without PCS, and (b) with PCS. It is clear that the the PCS is much more uniform and the energy is focussed towards broadside direction, thus, resulting in increased directivity.



a. without PCS b. with PCS

Extremely Wideband High-Gain ERAs (Gain~15-20dBi, Bandwidths >50%)

In 2014-15, we invented an innovative class of electromagnetic band-gap (EBG) resonator antennas which provide high gain and wide bandwidth with an extremely r footprint. One of the prototype developed has only 8% of the area as compared to conventional EBG resonator antennas but its performance (gain bandwidth) is a record hi for this class of antennas, while providing gain in the range of 15-20 dBi. This represents an improvement of nearly two orders of magnitude in the bandwidth compared to EBG resonator antennas. Thanks to its practical advantages of flat shape and low-cost manufacturability, it can be easily attached to a wall of a building, for example, to co building wirelessly to the National Broadband Network.

Our most recent results on such wideband high gain antennas can be found in: "Achieving high gain-bandwidth through flat GRIN superstrates in Fabry-Perot cavity antenn 2014 IEEE International Symposium on Antennas and Propagation (AP-S/USNC-URSI), pp. 1748 – 1749, Memphis, Tennessee, USA, July 6-11, 2014.

Detailed antenna design along with experimental data of another of our wideband EBG resonator antenna having composite multi-layer superstrate, is published in the pa "Wideband high-gain EBG resonator antenna with a small footprint and all-dielectric superstructures" in IEEE Transactions on Antennas and Propagation, vol. 62, no. 6, 201









Frequency response of one of our Wideband ERA Prototypes

Simple Dual-Band ERAs

We developed a new method to obtain dual-band operation from a simple electromagnetic band gap resonator antenna. The antenna is based on a one-dimensional EBG made out of two low-cost unprinted dielectric slabs. The EBG structure is implemented as the antenna superstrate, which has been designed to provide a locally-inverted reflection phase gradient with high reflectivity, in two pre-determined frequency bands. The linearly polarised antenna design and experimental results are described in entitled: "A simple dual-band electromagnetic band gap resonator antenna based on inverted reflection phase gradient" published in IEEE Transactions on Antennas and Pro vol. 60, no. 10, pp. 4522-4529, 2012.

We have extended this concept for dual-band, dual-polarised and circularly-polarised antennas. We also designed a tri-band antenna following this concept. It needs only t cost unprinted dielectric slabs.







Low-Profile Wideband ERAs

We have designed and successfully tested wideband low-profile (thin) EBG resonator antennas. The breakthrough that contributed to this success is our design of a partially surface (PRS) with a positive reflection phase gradient. Thin single-dielectric-slab PRSs with printed patterns on both sides were investigated to minimise the PRS thickne simplify fabrication. Three such surfaces, each with printed dipoles on both sides, have been designed to obtain different positive reflection phase gradients and reflection r levels in the operating frequency bands. These surfaces, and the EBG resonator antennas formed from them, were analysed theoretically and experimentally to highlight t compromises involved and to reveal the relationships between the antenna peak gain, gain bandwidth, the reflection profile (i.e. positive phase gradient and magnitude) of t and the relative dimensions of dipoles. A small feed antenna, designed to operate in the cavity field environment, provides good impedance matching (|S11|< -10 dB) a operating frequency bands of all three EBG resonator antennas. Experimental results confirmed the wideband performance of a simple, low-profile EBG resonator antenna thickness is only 1.6mm, effective bandwidth is 12.6%, measured peak gain is 16.2 dBi at 11.5 GHz and 3dB gain bandwidth is 15.7%. Please find details in a paper entitled of Simple Thin Partially Reflective Surfaces with Positive Reflection Phase Gradients to Design Wideband, Low-Profile EBG Resonator Antennas," published in IEEE Tra on Antennas and Propagation in 2012.

Low-Profile Dual-Band ERAs

We have achieved dual-band operation in a low-profile EBGRA using a single dielectric superstate with a printed pattern only on one side. This also made use of our r inverting the gradient of the PRS reflection coefficient.

Woodpile EBG Material and Antennas

In 2003, we designed and built a woodpile 3D photonic crystal, also known as a EBG crystal, operating in microwave frequencies, and demonstrated experimentally the ex the electromagnetic band gap. The crystal is made out of cermain material.

Then we designed a planar EBG resonator antenna. Shown below, it has a resonant cavity between a ground place and a 3D woodpile photonic crystal. We employed both m and slots to feed the cavity, and investigated both linearly and circularly polarised antennas. The linearly polarised antenna design and experimental results are described in entitled "A planar resonator antenna based on a woodpile EBG material," published in IEEE Transactions on Antennas and Propagation,vol. 53, no. 1, pp. 216-223, January 2









Leaky-Wave Antennas for Advanced Wireless Systems

Antenna beam steering can bring significant benefits to advanced wireless systems. Microstrip leaky-wave antennas (MLWAs) are of particular practical interest becaus planar low-profile configuration, ease of fabrication, and beam-scanning capabilities. In this research several planar MLWAs and arrays are developed to radiate at bores conical beam around the boresight, with simultaneous dual-side-beam scanning, dual-band forward and backward beam-scanning, and continuous beam scanning from the to the forward direction. Moreover, methods and antenna designs are proposed to steer the beam at a fixed frequency, shifting beam-steering range, and fixed-frequency bean in forward and backward directions.


L
l
W
Substrate
Port
Unit cell
Microstrip line
50 Ω load
y
x
Gap (g)
Via
w_p
l_p
(a)
Ground plane
Tapered line
(b)
Septum
Via
PIN diode
w/2
l_p
z
h
g
Substrate
y
(c)

Figure 1. Proposed reconfigurable HW-MLWA: (a) top view, (b) perspective view, and (c) side view.



TABLE I. SWITCH CONFIGURATIONS AND CORRESPONDING MAIN BEAM DIRECTIONS AT 6.5 GHz

	Switch Configuration	Main Beam Direction (θ)
1	1111111111111111111111111	21°
2	1111001111001111001111100	26°
3	0000110000110000110000011	32°
4	0000000000000000000000000	37°

15
10
5
0
-5
-10
Gain (dBi)
0
15
30
45
60
75
90
θ (degree)
Config 1
Config 2
Config 3
Config 4


Substrate
B2
B3
B1
B4
Feed point
Via
Microstrip
Septa
g
y
z
(a)
Ground plane
Feed point
B4
Microstrip
Via array
Via
z
y
x
(b)
L
Via
B2
Via arr
l
w
B3
B1
Vias
B4
Feed
Subst
y
z
x
(c)

Fig. 1. HW-MLWA array design steps: (a) top view of the initial de septa, (b) perspective view of one branch of the final design with v (substrate omitted, not to scale), and (c) top view of the fabricated pro

Multi-band Dual-Polarized Shared Aperture Array

Multi-band dual-polarized shared-aperture (MBDP-SA) arrays are antenna arrays that operate in two (or more) frequency bands with dual-polarization in each band, a elements are integrated together into a common physical space by sharing the single aperture. The MBDP-SA array is of great interest in space-borne SAR system, bec technique can effectively reduce the payload and size of the antenna sub-system. In this research project, main efforts are focussed on three aspects: 1) improve the specifi current Dual-Band Dual-Polarized Shared-Aperture (DBDP-SA) array; 2) construct Tri-Band Dual-Polarized Shared-Aperture (TBDP-SA) array; and 3) explore some new for DBDP-SA antenna.



(a) Rear (b) Front

Fig.1 Improved DBDP-SA array.



(a) Rear (b) Front

Fig.2 Photos of the TBDP shared aperture prototype array.



Side view

Fig.3 Novel structure DBDP-SA array

Compact Dielectric Resonator Antennas with Ultra-Wide 60%-110% Bandwidths

We have recently made a significant achievement in the emerging ultra wide-band (UWB) wireless communication systems, which require antennas with bandwidths gr
106%. In the past, the only way antenna engineers knew how to get such a bandwidth from a thin antenna was by removing the metal sheet underneath the antenna (known a
plane”). This is not an acceptable solution for practical systems because the lack of it allows the antenna to radiate both upwards and (unnecessarily) downwards (i.e.
electronic device on which the antenna is installed), wasting about half of its power. Saving power is crucial in UWB systems due to the severe power limits imposed by regu
2011, we made a breakthrough in dielectric-resonator (DR) antenna research, by inventing a novel DR antenna with a full ground plane and a 110% bandwidth. This disp
myth that such bandwidths cannot be achieved with full ground planes. This antenna, published in the prestigious IEEE Transactions on Antennas and Propagation in Decem
is 29% smaller but has a 30% greater bandwidth than the next-best DR antenna, which does not even have a full ground plane. Hence it is ideal for next-generation ultra-fas
and sensor applications.

We theoretically and experimentally demonstrated that, by introducing a lower-permittivity full-length insert between the ground plane and a higher-permittivity dielectric
dielectric resonator antennas (DRA) with ultra-wide bandwidths, in the range of 60%-110%, can be designed. Furthermore, the volume of such DRAs is reduced by appro
50% using a finite planar conducting wall. Unlike vertical monopole-type hybrid UWB DRAs, these antennas radiate sufficiently in the upward direction. Unlike in printed r
UWB antennas, the power radiated into the lower hemisphere is significantly less. An example prototype antenna, designed to operate in the FCC UWB band, has a dielectr
of 12 x 8 x 15.2 mm3 (or 0.124 x 0.083 x 0.157 lambda3 at 3.1 GHz), and an average measured gain of 5 dBi from 3.1 to 10.6 GHz. These antennas exploit multiple low
with overlapping bandwidths to form an ultra-wide contiguous bandwidth. With the proposed dielectric arrangement, it is possible to efficiently couple a sufficient numbe
overlapping modes to a 50 ohm feedline using a single, simple feed.



The antenna has a remarkably small footprint of 12x8 mm2 at 3.1 GHz - the lowest frequency of the FCC UWB band. Its dielectric volume is 1459 mm3, or 1.7x10-3 lamb
lowest operating frequency of 3.1 GHz, and overall height is 15.2 mm or 0.157 lambda0. To place these results in perspective, it is worth comparing the new designs with
wideband DR designs available in the literature. To the best of our knowledge, prior to this, the widest bandwidth ever obtained from a pure DRA design is 84% . The volu
DR in that design is 0.225 x 0.172 x 0.062 lambda3 (= 2.4x10-3 lambda3) at its lowest operating frequency of 3.69 GHz. In that DRA, the DR is positioned in a non-traditi
close to the edge of an orthogonal, “vertical” ground plane, which does not block radiation towards the lower hemisphere. The widest bandwidth demonstrated by a pure D
traditional “horizontal” ground plane, (which can be employed to shield the rest from the antenna, as discussed previously) is 78%. The dielectric volume of that design is 0.
x 0.21 lambda3 (= 5.8x10-3 lambda3) at its lowest operating frequency of 6.7 GHz.

Super Wide-band Antennas

We have demonstrated that extremely wide bandwidths (ratio-bandwidths up to 1:25) can be obtained from a specially designed printed antenna with a tapered semi-ring
design is described in “A Printed Elliptical Monopole Antenna with Modified feeding Structure for Bandwidth Enhancement,” in IEEE Transactions on Antennas and Pro
vol. 59, no. 2, pp. 667-670, Feb. 2011.





Focal Plane Arrays for Radio Astronomy

Dense focal plane arrays (FPAs) are a key technology for a new generation of Radio-telescopes. Their primary benefit is the rapid survey speed facilitated by the wide fiel provided by multiple beams. Recent advances have brought dense FPAs within reach of radio astronomy applications. A number of institutions have significant research pr this field. This technology is being considered for the Square Kilometre Array (SKA) (www.skatelescope.org). The PhD project of Douglas Hayman, conducted with CS Centre and Division of Astronomy and Space Science, investigated beamforming aspects of FPAs and evaluated their performance in Radio Astronomy. A prototype interf radiotelescope, built at CSIRO's Radiophysics Laboratory in Sydney, is used to demonstrate a suite of techniques forFPA beamforming and evaluation for this thesis. Bea solutions were experimentally demonstrated in our paper in IEEE Transactions on Antennas and Propagation, entitled "Experimental Demonstration of Beamforming Sol Focal Plane Arrays".The THEA tile, shown below, is designed by ASTRON and used for the experimental component of this research.



Negative Permeability of Spiral Metamaterials

Archimedean spirals and complementary Archimedean spirals are super-compact metamaterial particles. Thanks to their convoluted geometry, unit cells can be made electri small. We theoretically analysed monofilar, bifilar, trifilar and quadrifilar Archimedean spiral metamaterial particles using point group theory and crystallography. From the properties electromagnetic response was determined. Magnetic, electric and magnetoelectric modes of the particles were identified along with their isotropy characteristics. shown that all the particles, except monofilar spiral, are nonbianisotropic. Further, effective medium theory was applied to extract the effective permeability of the spiral me results indicated negative values for permeability in certain frequency ranges. Detailed theory and numerical simulation results are available in the paper entitled "Analysi metamaterials by use of group theory," published in the Metamaterials Journal, vol. 3, no. 1, pp. 33-43, March 2009.





Archimedean Spiral Metamaterials and Backward Waves

We have shown backward wave propagation and double negative parameters over a 19% bandwidth in a microstrip line loaded with series gap discontinuities and super
complementary Archimedean spiral resonator metamaterial particles. Moreover, our equivalent-circuit model for such unit cells almost perfectly described the structu
practically important frequencies (by comparison with full-wave results). We also fabricated and tested compact filter circuits with only one or two complementary spiral met
particles. Our results sre summarized in the paper entitled “Backward Wave Microstrip Lines with Complementary Spiral Resonators,” published in IEEE Transactions on
and Propagation, Vol. 56, Issue: 10, pp. 3173-3178, Oct 2008.

We derived design equations for Archimedean spiral resonators and tested them against full-wave simulations. The details are in the paper entitled “Design of monofilar a
Archimedean spiral resonators for metamaterial applications,” published in IET Microwaves, Antennas & Propagation, vol. 3, no.6, p. 929-935, Sep.2009.





Frequency Selective Surfaces for Energy-Saving Glass Panel

Energy-saving glass is becoming very popular in building design due to their effective shielding of building interior against heat entering the building with infrared (IR) wav
obtained by depositing a thin layer of metallic-oxide on the glass surface using special sputtering processes. This layer attenuates IR waves and hence keeps buildings
summer and warmer in winter. However, this resistive coating also attenuates useful microwave/RF signals required for mobile phone, GPS and personal communication sy
by as much as 30 dB. To overcome this drawback, we designed and tested a bandpass aperture type cross-dipole frequency selective surface (FSS), etched in the coatings
saving glass to improve the transmission of useful signals while preserving IR attenuation as much as possible. With this FSS, 15-18 dB peak transmission improveme
achieved, for waves incident with 45 degrees from normal for both TE and TM polarizations.

Measurements and other results of this research, conducted in collaboration with the Lund University in Sweden, are available in the paper entitled “Cross-Dipole
Frequency Selective Surface for Energy-Saving Glass Used in Buildings,” published in IEEE Transactions on Antennas and Propagation, vol. 59, no. 2, pp. 520-525, Feb.
effect of these FSSs on the transmission of infrared and visible wavelengths through energy-saving glass was investigated theoretically and experimentally in another pap
Microwaves, Antennas & Propagation, Vol. 4, Iss. 7, pp. 955–961, 2010.





Switchable Frequency Selective Surfaces to Reconfigure Electromagnetic Architecture of Buildings

In large buildings and offices, frequency re-use methods will be required to enhance the spectral efficiency and capacity of wireless communication systems. This observati
to the concept of electromagnetic architecture of buildings. Passive bandstop FSSs can be used to enhance the electromagnetic architecture of a building, and hence to
spectral efficiency and system capacity, but switchable FSSs can provide a better reconfigurable solution. If switchable FSSs are placed in strategic locations of a building, th
reconfigured remotely and rapidly, which is not possible with passive FSSs.

With collaborators in UK and Sweden, we designed and successfully tested a single-layer active Frequency Selective Surface (FSS) that is electronically switchable between
and transparent states. It can be used to provide a spatial filter solution to reconfigure the electromagnetic architecture of buildings. The FSS measurements show that the
response of the filter does not change significantly when the wave polarization changes or the angle of incidence changes up to ±45º from normal. The FSS is based on sq
aperture geometry, with each unit cell having four PIN diodes across the aperture at 90 degree intervals. Experiments demonstrated that almost 10 dB additional transmissio
be introduced on average at the resonance frequency, for both polarizations, by switching PIN diodes to ON from OFF state.

For details, please refer to “Switchable Frequency Selective Surface for Reconfigurable Electromagnetic Architecture of Buildings,” in IEEE Transactions on Ante
Propagation, Vol. 58, Issue 2, pp 581-584, February 2010.



Absorb/Transit FSS

We designed and tested a novel absorb/transmit frequency selective surface (FSS) for 5-GHz wireless local area network (WLAN) applications. The novelty of the design i capable of absorbing, as opposed to rejecting, WLAN signals while passing mobile signals. The absorption of the WLAN signal is important to reduce additional multipa spread and resultant fading caused by typical reflect/transmit FSSs. Our FSS consists of two layers, one with conventional conducting cross dipoles and the other with resis dipoles. The FSS has good transmission characteristics for 900/ 1800/1900-MHz mobile bands and performs well for both horizontal and vertical polarizations.

Later we modified the FSS to obtain even better performance, for example, for both horizontal and vertical polarizations at oblique angles of incidence. The distance betwee layers has been successfully reduced to one eighth of free-space wavelength. This small distance makes it more compact as compared to the conventional Salisbury screen achieving an acceptable absorption in the stopband.

The details of our designs and test results can be found at “Oblique Incidence Performance of a Novel Frequency Selective Surface Absorber,” in IEEE Transactions on Ant Propagation, Vol. 55, no. 10, pp. 2931 – 2934, Oct. 2007, and “A Novel Absorb/Transmit FSS for Secure Indoor Wireless Networks with Reduced Multi-path Fadin Microwave and Wireless Component Letters, Vol. 16 (6), pp. 378 - 380, June 2006.

Dual-Band Artificial Magnetic Conductor (AMC) Surfaces

AMC surfaces have many advantages and interesting properties due to their unique reflection characteristics, with near zero reflection phase. We have designed and pro novel dual-band AMC surface, which has a very wide upper AMC band and a narrow lower AMC band, and therefore suitable for multi-band wireless/mobile applications.



Fully Printed Quad-band Antennas for Wi-Fi IEEE802.11 and other WLAN Applications

Our fully-printed antennas can be fabricated and integrated to WLAN systems at almost zero cost by printing them on the same circuit board (e.g. FR4) with the radio circuit same standard fabrication methods. They are extremely compact: an antenna with a radiating element of 1cmx1cm covers all four IEEE standards (802.11a, 802.11b, 80 802.11n) as well as HiperLAN2 with a VSWR less than 2. We have also developed a packaging solution where the rest of the circuit can be shielded to satisfy EMC regulati leaving the antenna (on the same board) open for radiation. The advantages of the antennas based on this technology are: Lightweight; Radiates almost every direction in shadow region); Microstrip and co-planar waveguide (CPW) designs available; Compatible with all printed microwave circuits, including stripline circuits; Excellent because no cables, connectors, soldering or any mechanical attachments are required to connect the antenna to the radio; No protruding parts that are likely to break; Covers WLAN bands with one antenna (e.g. Wi-Fi IEEE 802.11 a, b, g, n, HiperLAN2 etc.); Excellent matching, i.e. input reflection < -10 dB (VSWR < 2) in all WLAN bands (e. GHz, 4.9-5.1 GHz, 5.15-5.35 GHz, 5.725 – 5.825 GHz); High efficiency (~60-70% on FR4; can be increased to over 90% on Duroid.); Ideal for internal mounting in a c device, to achieve very wide beam coverage; diversity reception or MIMO arrangements available; can be dsigned to cover other multiple bands (e.g. multiple mobile/c bands) and other applications.



How can I optimise a UWB System to operate well over a range of directions?

Emerging ultra-wideband (UWB) communication devices will need to operate well, not just in one direction but over a range of directions. However previous UWB system optimisation techni been limited to one direction only. A system optimised in one direction may not work well in other directions due to pattern instability, or direction-dependent transfer function, of the an developed the concept of frequency-domain correlation patterns and proposed a figure of merit, the pattern stability factor (PSF), which can be determined from simulation of experimen With these new concepts, we have demonstrated the optimisation of UWB systems to operate well over a range of directions. The concepts and their applications are available in the PhD papers by Tharaka Dissanayake.

Antenna Techniques and Technologies for Ultrawideband (UWB) Systems

We developed antenna solutions for emerging UWB systems with very high data rates. Our research includes investigation of band-notching techniques to reduce UWB inference wi wireless systems and studies of antenna dispersion and pattern stability in the time domain.

High Gain Antennas with Planar Surface-Mounted Short Horns

In collaboration with University of Delhi, we have developed compact rectangular dielectric resonator antennas with surface mounted planar horns for gain enhancement. One configuration an aperture-fed rectangular dielectric resonator antenna and a planar surface mounted horn. We have achieved 10 dBi gain and a good efficiency from this configuration. The surface mou increases the gain of the standard dielectric resonator antenna by 4.9 dB. Total height of the prototype antenna shown in the figure is only 0.172 lambda and the aperture size is 0.96 lamb antennas can be easily adapted to low-profile, high-gain and array applications.







Photonic Crystal/EBG Based Horn Antennas

Waveguides and antennas made out of dielectric, as opposed to metal, are expected to perform better at Terahertz frequencies, as they do not suffer from the skin-effect loss of metal investigated horn antennas, horn arrays, waveguides, bends and junctions made out of 3D woodpile photonic crystals, which can be implemented at THz frequencies in high-resistivity S other materials. Our concepts have been tested by fabricating and measuring scaled-up prototypes operating in microwave frequencies. We have also designed a special broadband couple a photonic crystal waveguide to a rectangular waveguide or a coaxial cable, for example for testing using a vector network analyser. We demonstrated > 6% bandwidth both theore experimentally.



Broadband Microstrip Patch Antennas for Wireless Computer Networks

We have designed and tested broadband, compact E-shaped patch antennas for wireless communication networks, operating in frequencies from 4.9 GHz to 6.0 GHz. We made two achievements. First, we designed an E-shaped antenna, which is intrinsically compatible with a printed microstrip circuit. It can be made out of a single sheet of metal and can be mou microstrip circuit without expensive coaxial connector. Second, we designed a unique E-shaped antenna with corrugation to reduce the width of antenna. We successfully miniaturised the fit it inside a thin (4mm) PC (or PCMCIA) card extension. In fact, we were able to squeeze in two of these antennas into a single PC card of standard width (54mm), for diversity communica achieve excellent isolation (>20 dB) and matching (<-10 dB) over the whole WLAN frequency band.

Theoretical Analysis of Photonic Crystal Structures

We have developed and successfully implemented, in both personal computers and supercomputers, efficient theoretical methods to analyse and design complex electromagnetic (micro optical) circuits based on photonic crystals (PC). Among our novel techniques is a PC-based Perfectly Matched Layer (PML) absorbing boundary for use with the finite difference time doma method in the analysis of waveguides in 3D photonic crystals.

We have applied these techniques to model wave propagation in various guiding structures such as bends, junctions and tapers in 2D and 3D crystals. From this analysis, we can transmission and reflection coefficients, propagation characteristics, phase and delay response, etc., of a component or a system.

New Closed-form Green's Functions for Microstrip Circuits and other Layered Structures

When combined with the spatial-domain Method of Moments (MoM), our new closed-form functions now enable efficient and accurate analysis of microstrip circuits and antennas with approximations. The key feature in this new MoM is that the four-dimensional integrations in MoM matrix elements can be solved analytically, completely eliminating the need for expensive integrations. Our new closed-form functions are simpler and more flexible than previous such functions, and (unlike previous ones) they do not require additional (Taylor series approximations. The computer time required for the analysis of an example microstrip line using the new MoM was three times less than the next best method, which required some integrations.

Integrated-design of Hybrid-resonator Antennas for Broadband Wireless and other Communication Systems

Shown below is the first baby of our recent project on broadband hybrid-resonator antennas. This first prototype of a Dielectric Resonator on Patch (DRoP) antenna demonstrated a ba 24%. This design also proved, both theoretically and experimentally, that the electromagnetic fields in a dielectric resonator can be efficiently coupled to the fields in a patch resona perturbing the radiation characteristics of each resonator.

Singularity-enhanced Finite-different Time-domain (FDTD) Method for Diagonal Metal Edges, Strips and Films

We developed the world's first and still the only singularity-enhanced FDTD method for metal edges not parallel to the grid. The edges were assumed to be diagonal to cell faces. Compare conventional spit-cell model, the computer memory required for an FDTD analysis of a structure could be reduced by up to 27 times and the computing time could be reduced by up to without sacrificing the accuracy of results. On the other hand, when the same grid was used, the accuracy of results improved by a factor of more than 3 compared to the split-cell model, a of more than 7 compared to the staircase model. The new equations were stable in all tests, and even in most demanding tests when the computational speed was further maximised by the time step (Dt) to the maximum allowed by the FDTD method! (i.e. stability factor of 1!)

The key to this success was the derivation of enhanced FDTD equations for nodes near the edges by considering rigorously the singular nature of the electromagnetic fields. The table here improvement of accuracy achieved by using the enhanced FDTD equations. The new equations are simple to implement in a standard FDTD code. They are ideal for the analysis and microstrip components and high-speed digital circuits where thin metal films or strips with diagonal edges are encountered.

Low-profile Dielectric-resonator (DR) Antennas

We designed and tested the world's first low-profile, circularly polarised, rectangular dielectric-resonator antenna (DRA) in 1995. The radiating element of this antenna is shown in the photo have also designed many other dielectric-resonator antennas, including a low-profile linearly polarised DRA, for various applications (see publications). We pioneered the FDTD analy antennas and published the first radiation patterns of a DR antenna obtained using the FDTD method in 1995.



(a) (b)

(c) (d)

Australian Antenna Measurement Facility (AusAMF)

AusAMF is operated by a consortium of Australian Universities, Industry and CSIRO. The facility provides access to a shielded anechoic chamber offeri spherical near-field measurement capability for small antennas operating in the frequency range of 1-20 GHz, primarily for research purposes.

The facility was established under an ARC LIEF (Australian Research Council Linkage-Infrastructure Equipment and Facilities) grant and is hosted by C ICT Centre located in the Sydney suburb of Marsfield.

The facility currently consists of a spherical near-field turn-key NSI-700S-50 system within a 6m x 3.3m x 3.3m anechoic chamber. It has been designed to operate up to fre of 20 GHz, and uses an Agilent PNA (E8362B) as a receiver. The measurement system is capable of supporting a ~40kg antenna under test (AUT) up to a diameter of approximately 1.2m. I the standard gain horns and the probes available at AusAMF are as follows:

Waveguide Band	Frequency (GHz)	Probe	Standard Gain Horn
WR975	0.75 - 1.12	x	x
WR650	1.12 – 1.70	x	x
WR430	1.70 – 2.60	x	x
WR340	2.20 - 3.30	x	x
WR229	3.30 – 4.90	x	x
WR159	4.90 – 7.05	x	x
WR112	7.05 – 10.00	x	x
WR90	8.20 – 12.40	x	
WR75	10.00 - 15.00	x	x
WR51	15.00 - 22.00	x	x

COPYRIGHT (C) 2013 KARU ESSELLE ALL RIGHTS RESERVED

ResearchGate

See discussions, stats, and author profiles for this publication at: https://www.researchgate.net/publication/273396385

Smart Surfaces: Large Area Electronics Systems for Internet of Things Enabled by Energy Harvesting

Article *in* Proceedings of the IEEE · November 2014

DOI: 10.1109/JPROC.2014.2357493

CITATIONS
24

READS
362

9 authors, including:

Luca Roselli
Università degli Studi di Perugia
273 PUBLICATIONS **2,132** CITATIONS

SEE PROFILE

Federico Alimenti
Università degli Studi di Perugia
200 PUBLICATIONS **1,263** CITATIONS

SEE PROFILE

Paolo Mezzanotte
Università degli Studi di Perugia
144 PUBLICATIONS **1,211** CITATIONS

SEE PROFILE

Giulia Orecchini
Università degli Studi di Perugia
24 PUBLICATIONS **347** CITATIONS

SEE PROFILE

Some of the authors of this publication are also working on these related projects:

Project

Development of ultra wide band analog predistorsion of LASER diodes for Radio over Fiber (RoF) systems View project

Project

ADAHELI View project

All content following this page was uploaded by Luca Roselli on 30 July 2015.

The user has requested enhancement of the downloaded file.

Smart Surfaces: Large Area Electronics Systems for Internet of Things Enabled by Energy Harvesting

This paper focuses on large-area "smart surfaces," RFID systems, and wearable RF electronics that could substantially benefit from multisource energy harvesting.

By Luca Roselli, *Senior Member IEEE*, Nuno Borges Carvalho, *Senior Member IEEE*,
Federico Alimenti, *Senior Member IEEE*, Paolo Mezzanotte, *Member IEEE*,
Giulia Orecchini, Marco Virili, *Student Member IEEE*,
Chiara Mariotti, *Student Member IEEE*,
Ricardo Gonçalves, *Student Member IEEE*, and Pedro Pinho, *Member IEEE*

ABSTRACT | Energy harvesting is well established as one of the prominent enabling technologies [along with radio-frequency identification (RFID), wireless power transfer, and green electronics] for the pervasive development of Internet of Things (IoT). This paper focuses on a particular, yet broad, class of systems that falls in the IoT category of large area electronics (LAE). This class is represented by "smart surfaces." The paper, after an introductory overview about how smart surfaces are collocated in the IoT and LAE scenario, first deals with technologies and architectures involved, namely, materials, antennas, RFID systems, and chipless structures; then, some exemplifying solutions are illustrated to show the present development of these concurrent technologies in this area and to stimulate further solutions. Conclusions and future trends are then drawn.

KEYWORDS | Energy harvesting; green electronics; Internet of Things (IoT); large area electronics (LAE); radio-frequency identification (RFID) systems

I. INTRODUCTION

Looking at the telecommunication (TLC) market development worldwide in the last five years, we see an average decrease of about 5% per year, in both gross domestic product (GDP) contribution and employment [1]. Against this trend, the global information and communication technology (ICT) market has remained grossly constant. Some compartments, in fact, are experiencing an opposite trend. Beside some sectors related to new consumer products, such as tablets and smartphones, new Internet of Things (IoT) related products are growing at two digits per year and some estimations from big players report a market value in the order of trillions of dollars in the next decade [2], [3].

The vision behind IoT is in fact to connect objects directly to the Internet so as to allow them to provide information directly to the web without any human intermediation [4]. This vision will have a great impact on several electrical and electronic technologies, ranging from the basic physical layers (technology platforms) to the highest ones: communication protocols, software, human interface, and information management.

Manuscript received May 4, 2014; revised September 1, 2014; accepted September 5, 2014. Date of publication October 13, 2014; date of current version October 16, 2014.

L. Roselli, **F. Alimenti**, **P. Mezzanotte**, **G. Orecchini**, **M. Virili**, and **C. Mariotti** are with the Department of Engineering, University of Perugia, Perugia 06123, Italy (e-mail: roselli@ieee.org).
N. Borges Carvalho and **R. Gonçalves** are with the Instituto de Telecomunicações-Dep. Electrónica Telecomunicações e Informática, Universidade de Aveiro, Aveiro 3810-193, Portugal.
P. Pinho is with the Instituto de Telecomunicações, Instituto Superior de Engenharia de Lisboa, Lisboa 1959-007, Portugal.

Digital Object Identifier: 10.1109/JPROC.2014.2357493

0018-9219 © 2014 IEEE. Personal use is permitted, but republication/redistribution requires IEEE permission.
See http://www.ieee.org/publications_standards/publications/rights/index.html for more information.

In terms of physical layer, IoT actually inherits the technologies developed for wireless sensor networks (WSNs), bringing the distributed nature of that to the extreme. WSN, in fact, can be synthetically seen as a mesh of sensor nodes purposely conceived to build and communicate a sensed image of a monitored area. Within IoT, the sensing nodes are not purposely deployed to monitor something specific; instead, they are simply hosted by "objects" in order to provide the information they are able to collect and make it available on the web. Conceptually speaking, there is not a big difference, but in terms of related technological challenges, there is. Nodes must be hostable by objects; objects are of many types, and the better the nodes fit themselves transparently to the hosting objects, the denser and more reliable the information they are able to provide.

Several challenges can be envisioned in this evolution: first, electronic systems must be mechanically flexible, thin, and miniaturized in order to conform to the shape of as many objects as possible; second, the adopted materials have to be as recyclable as the hosting objects in order to avoid pollution from guest apparatuses; last but not least, hosted nodes must be autonomous, because they cannot be either connected to the grid or powered by life batteries.

A great technological paradigm shift is going to be pulled by the development of IoT; green materials, autonomous systems, ultralow-power circuits, energy saving protocols, and energy harvesting (EH) are concurrently mandatory.

Conversely, this technological evolution is pushing new solutions and architectures, so far constrained by the limits of conventional technologies. The development of inkjet printing techniques, the introduction of very cheap and eco-friendly materials compatible with roll-to-roll (R2R) circuit realization techniques [5] and so forth, open new horizons also to large area electronics (LAE).

LAE, first applied to printed photovoltaic and organic screens [6], is actually at the onset of its development. The development of R2R techniques and related materials, in fact, is allowing for tremendously increasing the dimensions of LAE circuits and systems, from the present tens of centimeters to meters and beyond. Along this evolutionary scenario, new configurations and architectures, based on massive integration of large circuits over conformable surfaces, can be envisioned, opening the way to what can be called the smart surfaces (SSs) approach.

SS, in turn, can be seen as a branch of IoT evolution. Large 2-D arrays of autonomous sensor nodes, for instance, make possible granular tracking of whatever parameter, ultimately providing augmented imaging of the environment; large 2-D arrays of tags can provide a very low-cost platform for precise localization and location-based services (LBS), thus enabling the realization, for instance, of smart floors [7] and smart wallpapers [8]; inheriting quasi-optical approach [9] contact-less electromagnetic (EM) wave processing (filtering, frequency conversion, selective shielding, etc.) can be conceived even at low frequencies.

On the one hand, SS is thus an approach stimulated by technologies pulled by IoT; on the other hand, it contributes to a class of architectures, within LAE, that can even widen the huge horizons of IoT applications in a sort of virtuous circle.

According to this wide vision, the paper is organized as follows. A review of the technologies suitable for distributed systems implementation to a large extent is given in Section II; then, the explanation about how radio-frequency identification (RFID) can be considered one of the most suitable technologies for the implementation of IoT architecture, and how it can be naturally integrated with SSs, is provided (Section III). In order to deal with the implications of the development of RFID systems compatible with SS and LAE evolution of IoT, two specific sessions have been provided: the first relates to antenna implications (Section IV), and the second relates to electronic architectures for RFID tags (mainly chipless ones; Section V). In order to smoothly bring the reader from relevant technologies to applications, quasi-optics, as an example of general approach concurrently exploiting the mentioned technologies to provide a platform suitable for LAE, is described in Section VI. After this, some application examples of how SS concept can be articulated, according to the IoT paradigm, are described; specifically, smart floor (Section VII), smart shoes as useful subsystems for the implementation of smart floors (Section VIII), and energy skin (Section IX). In order to have a vision of the logical links behind the many topics dealt with in this paper, a synoptic picture can be found in Fig. 1.

II. TECHNOLOGY FOR LAE DISTRIBUTED SYSTEMS

Given the described scenarios of SS, it is clear that the technologies involved have to be compatible with LAE



Fig. 1. *Synoptic view of the paper structure reflecting the IoT vision described in the Introduction.*



Fig. 2. ***Inkjet printing technique, synoptic description. The ink is deposited on the substrate with the desired pattern and after a curing procedure the next layer can be printed. The thickness of each film depends on the number of passes.***

approach, as described in the Introduction; according to [6], for example, the eco-compatibility of the materials, the mechanical flexibility of the substrates to make the device conformable to the hosting surface, and the life cycle (operability and biodegradability) have to be accounted for.

The new techniques proposed from different research groups [10]–[12] focus mostly on the printing techniques that can be industrialized easily with R2R methods, already investigated for the traditional printing on paper. Within the printing methods, one of the most attractive and investigated in the last decade is the inkjet printing of conductive and dielectric layers (Fig. 2). This technique allows circuits to be printed on almost any kind of substrate: from the photographic paper to liquid crystalline polymers (LCP) or Kapton, that are flexible, thin, and eco-compatible; to glass or poly methyl meta acrylate (PMMA, commonly referred to as Plexiglas) that are usually thicker but not flexible.

A first proof of concept for the inkjet printing technique at radio frequency (RF) and microwaves has been obtained on photographic paper by printing simple structures, such as antennas and other planar circuits and devices [10], [13]–[22], with a technology stack simply composed by the substrate and the conductive layer (usually realized by means of nanoparticle silver ink).

Recently, this method has been improved thanks to the development of new inks, usually composed by a polymer and a solvent (i.e., SU-8, PVP, PMMA, PEDOT, etc.); more complex fabrication procedures of multilayer structures are now possible, as shown in [23] and [24]. Another noticeable feature of this technology is represented by the resolution: conductive tracks of 50 μm of width and space gaps of 50 μm can be printed, allowing the design of millimeter-wave (mm-wave) frequency devices [25]. The combination of the quite high resolution (considering the simplicity of the technology) with the multilayer featuring also gives the opportunity to manufacture very easily matrix of passive and active devices that can be used in the SS development. It is worth noting that the process can be developed in a few steps based on the design and mostly on the number of layers needed. For example, a metal–insulator–metal (MIM) device can be realized by printing silver on the substrate [26], curing it in the oven in order to create a surface that, with the proper treatment (for instance, UV–Ozone exposure or preheating), is ready for the insulator printing. Then, the dielectric is cured as well and the last metal layer can be printed on top of it. The entire structure can be then cured at temperatures ranging between 130 °C and 200 °C.

In a perspective of industrialization of the inkjet printing technology, the hypothesis of R2R manufacturing of circuits is being investigated and some examples are already reported in literature for solar cells and other devices [27], [28].

Today, many pros have been mentioned for the inkjet printing method, and others can be found in the non-use of wasted chemicals (as is for the traditional lithographic technologies), in the no-need of clean-room environment for the fabrications, in the low-cost and rapidity of manufacture, and in a R2R perspective compatibility. However, the necessity of a curing procedure after the printing of a layer still represents the biggest inkjet limit for two main reasons: first, the time and type of curing are dependent on the inkjeted materials and on the material stack-up; second, especially on a laboratory level, the curing can cause misalignment issues, given the fact that the sample is removed and then replaced in the printer after the last layer curing.

Currently, the platform mostly used worldwide by researchers is the Dimatix 2800 DMP. In terms of inks, it is possible either to buy printable solutions or mix solutions in labs; for example, the combination of polymers and solvents allows layers to be printed with different electrical properties and thicknesses.

Besides the inkjet printing method, in [11], a new technique, suitable for LAE, has been proposed. It uses a metal (copper in that case) adhesive laminate technology based on the application of the standard etching process to an adhesive copper laminate material. This technique was already adopted to produce mm-wave circuits and to characterize the resulting compound substrates, as reported in [29]–[31]. A brief illustration of the metal laminate technique is here reported referring to Fig. 3.

The production process can be divided in five steps. The first step consists of the deposition of a (positive) photoresist film on the copper surface; then, the circuit layout is transferred to the photoresist by means of a photomask and ultraviolet exposure. After that, the unimpressed film of photoresist is removed using a NaOH



Fig. 3. ***Process steps for the circuit fabrication using the adhesive metal laminate. M: metal, A: adhesive, P: protection, R: photoresist, S: sacrificial layer, SUB: hosting substrate. After the standard lithographic procedure, the copper pattern can be transferred on top of any substrate by means of a sacrificial layer and exploiting the adhesive face of the copper tape.***

developer solution [Fig. 3(a)]. In the second step, the copper tape is wet etched. As can be seen in Fig. 3(b), in this way, the adhesive layer is exposed where the copper was removed, while it remains everywhere else covered by the original copper tape that serves as protection for the adhesive underneath.

The first two steps are, in this example, similar to those adopted in standard photolithographic technology. Moreover, different ways to remove the not needed metal can be used, as, for example, by means of numerical control pattern cutting plotters.

In the third step, depicted in Fig. 3(c), a sacrificial layer is stuck on the top copper side and, finally, the protection layer on the bottom is removed. The sacrificial layer is very important because it keeps the relative distances among the layout features constant even when these are not physically connected.

The fourth step is characterized by the transfer of the etched metal to the hosting paper substrate and, finally, the sacrificial layer can be removed [see Fig. 3(d) and (e)]. The last step is also useful to remove most of the exposed adhesive material.

With this method, quasi-fully-organic circuits and devices can be realized. The performance in terms of tracks width and pitch are, at present, a bit lower than what can be obtained with the inkjet printing, with the advantages of no curing processes, the possibility to fix devices on the circuit using standard soldering techniques, and a better conductivity (the conductivity of copper laminate, in fact, is one order of magnitude higher than that of the cured nanoparticle silver ink: 5.8×10^7 S/m versus about $6 \times 10^6 - 1 \times 10^7$ S/m obtained with at least five layers of silver).

To verify the validity of the metal laminate technology at microwave frequencies, a 50-Ω microstrip line was manufactured exploiting the Mitsubishi photografic paper as the substrate (thickness 250 μm, relative permittivity $\varepsilon_r = 3.2$, and loss tangent $\tan\delta = 0.08$). The line is 30 mm long, and the measured scattering parameters are shown in Fig. 4. The same graph also compares the performance of a similar transmission line manufactured with an inkjet printing process. The performance of the



Fig. 4. ***Measured scattering parameters versus frequency for a 50-Ω microstrip line on paper substrate. The line, shown in the inset, is 30 mm long; the ruler division corresponds to 17.2 μm. The graph also reports a comparison with a microstrip line of equal dimensions made with an inkjet printing process (Ag ink, 3-μm thickness, $\sigma_{\text{ink}} = 1.1 \times 10^7$ S/m after curing). After [11].***



Fig. 5. ***Screen printing technique. The squeegee is used to press the screen with impressed pattern and transfer it on top of the substrate.***

metal laminate structure is superior compared to that of the inkjet printed line. At 10 GHz, the measured specific losses for the metal laminate microstrip are about 0.6 dB/cm [11]. Results at higher frequencies are also reported in [31]; in particular, an insertion loss of about 1.8 dBm/cm at 30 GHz is demonstrated.

The tradeoff is the adoption of a photolithographic step; it is worth mentioning, however, that the process is still compatible with R2R implementation.

Other possibilities for LAE are the screen printing [12] and the gravure printing [12], both of them adaptable to R2R industrialization techniques.

Screen printing consists of dragging a layer of ink across the surface of a screen and squeezing it through the open pores of the patterned mesh onto the substrate (Fig. 5). In general, the thickness of the printed layer and the achievable resolution depend on the density of the mesh and on the ink properties. Usually, the ink viscosity is in a range of 1–50 Pa $\times$ s, and this allows for printing with a resolution of about 100 μm and a thickness up to 100 μm. Until now screen printing has been adopted to realize low-resistance structures, solar cells, and field effect transistors (FETs), exploiting the possibility of printing very thick layers.

Gravure printing, also known as rotogravure, is considered a very high volume printing (Fig. 6) process, and it is being adopted to produce very conductive structures as, for example, capacitors, antennas, and organic devices such as pentacene-based diodes, organic light-emitting diodes (OLEDs), organic field effect transistors (OFETs), and organic thin film transistors (OTFTs).

The resolution can be of about 20 μm. The method is implemented by engraving the patterns into a metallic cylinder by a laser, by chemical etching, or electromechanically (as separate cells or intaglio trenches). Typically, the print pressure is high (1–5 MPa) in order to achieve a good ink transfer and to reduce the percentage of unprinted dots caused by the surface roughness of the flexible substrate. However, this high pressure of printing makes this technique suitable only for robust substrates with no soft, previously printed, layers that could be damaged.

To summarize, the technologies described in this section are characterized by some common features, such as: flexibility and conformability, compatibility with large area realization of circuits and interconnections, use of additive or mixed (subtractive/additive) deposition techniques, easy use of eco-friendly materials and, in some cases, compatibility with classical bond wiring as well as soldering techniques for electronic device placement.

Table 1 summarizes the main features of the described technologies.

III. RFID: A MIX OF CONCURRENT TECHNOLOGIES FOR SS IMPLEMENTATION

As mentioned in the outline paragraph at the end of the Introduction, after describing the technologies enabling SS development (Section II), here we illustrate RFID as a suitable means to transfer information through EM transmission between tags and readers to the Internet.

An RFID tag has a unique identification code and a memory used to store information, while the reader can



Fig. 6. ***Gravure printing process. Note that these machines can be from 20 cm to 3 m wide with a diameter ranging from 5 cm to 5 m.***

Table 1 Technologies Comparison

Technology	Resolution	Cost	Waste	Speed
Inkjet	50 μm	Low	Low	Fast
Copper	100 μm	Low	High	Medium
Gravure	20 μm	High	Medium	Very fast
Screen	100 μm	Medium	Low	Very fast

write or read data on and from the tag through RF transmissions. The tag is usually attached to an object that needs to be identified and monitored, or contains information to be read. In typical RFID applications [32], the main goal is to provide mapping of physical objects that are equipped with an RFID tag attached or embedded. In this way, RFID technology inherently leads to identifying, tracking, and localizing, but it can also enable the storage and transmission of information regarding object status and surrounding environments by embedding sensing capabilities.

As mentioned previously, IoT is most commonly described as a structured system of technologies concurrently working to capture meaningful data from objects and communicate them through networks to a decision-taking level. Useful keywords, whenever a definition of IoT is given, include: smart objects, autonomous logistics, machine-to-machine communication, RF technologies, centralized information, and so on.

In order to implement these functionalities, an IoT platform, an SS for instance, has to provide at least unique object identification together with wireless communication for data management.

The IoT physical layer can thus be naturally thought of as meshes of RFID and sensor nodes. The RFID tag that embeds a sensor can use the same working principles and protocols of the conventional RFID tags; a differentiation can be made, considering the way sensor tags are powered up, in active, semipassive, and passive tags; actually, the difference consists of the way they are powered.

Active tag sensors may use customarily conceived communication protocols or rely on RFID standards enabling the tag to be easily integrated into the existing wireless infrastructures so that they will not require expensive readers. In [33], a system architecture was developed to integrate WSNs and the RFID systems. Bluetooth and ZigBee technologies are adopted as the communication protocol of WSNs to meet the requirements of a large number of sensor nodes, large areas, and low cost.

Active tags with integrated sensors are used in several applications, including temperature and position monitoring, vibration detection, blood pressure, heart beat monitoring, and more. This type of sensor tags, besides having larger amount of energy provided by batteries, affords both a large range and multiple functionalities; some of them have also external buses that enable the use of connected external sensors [34].

Passive tags with an integrated sensor operate without battery, collecting the needed operational energy from external environment sources. The main requirements of this class are high energy conversion efficiency, large storage capability, and overall low-power consumption. Passive systems have usually low operating range and limited processing capability.

In this field, research activities are directed toward ultralow-power design of integrated sensor tags [35], antenna design for improving reading range [36], sensor overall performance optimization [37], and development of optimum protocols allowing for additional power saving [38], [39].

Typical applications are, for instance, temperature monitoring [40], photodetection [41], motion detections [42], etc.

Semipassive tags use both batteries and energy sources coming from the environment; they can integrate more operational capabilities than the passive ones, since they can exploit a higher amount of energy. For the same reason, semipassive RFID tags are more suitable to integrate a sensor; the operational methodology is similar to the passive one, using the reader signal to interrogate and cause a response from the tag. The primary difference is that the semipassive tag does have a battery used not to generate a response, but only to power electronics, like sensors incorporated in the tag, while exploiting RF circulation to reply to the reader interrogation. Just like passive tags, semipassive ones are limited in terms of slow reading speeds and short reading distances. In [43], the design, realization, and experimental validation of a battery-assisted RFID tag with sensing and computing capabilities, conceived to explore heterogeneous RFID-based sensor network applications, was presented.

Dealing with battery-less devices that are, by far, the most interesting ones for IoT, LAE, and SS applications, we can now focus on the typical energy sources adopted. No battery devices can exploit solar scavenging [44], [45], vibrational [46], [47], or RF radiations [48]–[52].

In many cases, wirelessly powered systems can harvest energy from the incident RF waves, thus generating the required direct current (dc) voltage to power the system. The EM energy present in the environment may be significant in some regions (some urban areas or indoor sites); here the use of proper conversion devices may allow enough energy to be scavenged. RF power harvesters usually consist of an antenna, an impedance transformation network, a rectifier, and a storage element. In [53], a design example of integrated rectifier antennas (rectennas) for wireless powering at low incident power densities, from 25 to 200 μW/cm^2, is given.

Regarding mechanical energy scavengers, they may be categorized upon the kind of energy source exploited; there are scavengers providing energy from a constant motion over extended periods of time (e.g., turbine air flow) or others based on intermittent motion (e.g., human step). Particular attention is given to vibrational energy sources; in this case, the amount of energy that can be harvested depends mainly on the vibration amplitude and frequency and on the vibrating mass (mass of the harvesting device) [54]–[56].

In order to power the systems by using energy sources available in the working environment, proper energy transducers thus have to be chosen. Focusing on distributed systems (IoT, LAE, and SS), it is worth referring to typical parameters for optimum transducer design since, in these applications, the different kinds of energy available in the various scenarios may lead to the need of integrating more than one energy conversion system into the same device, in order to take advantage of all the accessible energies. The main design parameters are the available power output, the electrical impedance, and the operating voltage. Table 2 summarizes them for the most common energy transductions [57], [58].

To conclude this section, the mentioned reasons why RFID can be considered a useful technology for the implementation and development of LAE and, more specifically for SSs, are summarized. RFID systems, especially in the passive version of tags, are communication systems characterized by the following characteristics: compatibility with very low-power communication protocols, compatibility with the constrains posed by the hosting objects, especially when they are implemented by adopting the technologies described in Section II, inherent capability to gather information from the environment (sensor tags) and from the hosting objects, a low number of electronic devices (inherent circuital simplicity) and, finally, proven compatibility with printing technologies.

For all these reasons, RFID technology has to be considered the leading one to pursue the development of LAE and SSs as a communication platform for the evolution of IoT.

IV. ANTENNA DESIGN FOR NODES

Distributed systems for ubiquitous electronics (UE) and WSNs [59], [60] are, today, increasingly employed for monitoring and sensing applications. These systems can be seen as networks of nodes, massively distributed in the environment and communicating wirelessly with a base station. This massive deployment can be designed and structured to monitor a set of specified parameters by means of purposely conceived sensor nodes, as in the classical WSNs, or it can be obtained by integrating nodes into existing objects, which is the vision of IoT evolution. In general, the nodes can have different functionalities, however they have to provide information collected by embedded sensors (such as, for instance, identification codes, position and monitored environment parameters as well as object status) whenever it is required.

In this scenario, the RFID technology, summarized in Section III, is attractive. When RFID technology meets sensor nodes, information goes from the node to the Internet via a question-and-reply protocol between nodes, hosted by tagged objects, and readers.

Thinking about distributed systems and specifically SS, it is natural to think about radiative coupling in the available industrial–scientific–medical (ISM) frequency bands, including mainly the ultrahigh frequency (UHF) and microwave frequencies (around 0.9, 2.4, 5.8 GHz, and higher), exploiting the communication standard such as the WiFi [61]. Recently, also the ultrawideband (UWB) has been considered in order to minimize the limitations of narrowband systems (mainly localization accuracy and sensitivity to interference) [62].

Multistandard systems are often adopted for large compatibility and higher use flexibility. An example of this recent approach is given in [61] where near-field UHF nodes are combined with far-field transceivers. This allows application fields with compromised radiation capability,

Table 2 Transducer Characteristics for Several Forms of Ambient EH [57], [58]



Energy Source	Typical Electrical Impedance	Typical Voltage	Typical output power
Light	From low to 10s of KΩ	DC: 0.5 V to 5 V	Outdoors: 100s mW/cm^2 Indoors: $<$ 500 μmW/cm^2
Vibrational	Constant Impedance 10s of kΩ to 100 kΩ	AC: 10s of Volts	100s μW/cm^2
Thermal	Constant Impedance 1 Ω to 100s of Ω	DC: 10s of mV to 10 V	10s μW/cm^2 (20° gradient)
Radio Frequency	Constant Impedance Low KΩs	AC: Varies with distance and power 0.5 V to 5 V	Wide-range

such as in proximity of metal and liquids at short ranges, to be improved.

It is clear that antenna systems are key elements in these apparatuses. The foundation of antenna design rules can be found in [63]. The antenna design specific for distributed systems, in turn, has to take into account several instances. Beyond the typical design criteria, other aspects are: the communication standard, the form and the size in agreement with the application, the communication range as a function of the equivalent isotropic radiated power (EIRP) limits, of the environment and of the orientation, the reliability under several conditions and processes, and the material cost considering massive production [64]–[67]. Among them, the operating environment is the most critical aspect that influences the node behavior [68].

As a consequence, antenna topology and materials for SS and IoT systems, in general, have to be chosen in order to make the antennas capable of operating in variable environmental conditions and to be integrated into objects. As an example, let us think about wearable antennas for body area networks (BANs): they must be washable, flexible, and able to shield the body from radiation [69].

In general, antennas for SS should be flexible, planar, and low profile; moreover, by adopting low-cost materials and technologies (see Section II), cost per unit surface is low, thus large arrays and big elements can be adopted more easily, ultimately allowing for easy developments of LAE distributed systems and SS, even at low frequency.

Materials compliant with SS implementations must be, in turn, mechanically robust, flexible, and very low cost, while exhibiting acceptable EM performance. These materials must also exhibit high tolerance levels in terms of bending repeatability. Flexible materials, often used, are polymers and polymer-ceramics composites such as the poly-di-methyl-siloxane (PDMS) and the titanate-based ceramic [68], which provide flexibility, robustness, and resistance to harsh environments in order to protect antenna and circuit. Moreover, when eco-compatibility has to be guaranteed, recyclable materials and related technologies have to be adopted; among them, cellulose substrates in combination with inkjet printing of conductive inks [18], [70] or with conductive adhesive laminate technology [11] are increasingly frequently adopted. The aforementioned techniques, compatible with the well-known industrial printing and the R2R processes [5], are in agreement with the low-cost fabrication and are expected to facilitate widespread and very low-cost electronics for distributed systems. These fabrication technologies can also be adopted for electronic devices on flexible polymeric substrates. An example of cellulose-based antenna for smart floor applications, such as indoor localization, is documented in [71]: a low-profile planar loop antenna is realized on cellulose substrate exploiting adhesive copper tape.

Although beyond the scope of this paper, which focuses on SS, it is worth mentioning here that this evolution toward the development of more and more sophisticated "unconventional" materials for electronics has a great impact on other IoT related developments such as, for instance, implantable systems.

When applications require devices with soft visual impact (think about SS, such as smart windows, glass integrated inside and outside buildings and glass for automotive applications, or smart skins [72]), transparent and conductive materials, such as transparent conducting oxides (TCOs), and in particular indium-tin-oxide (ITO) and ITO-based multilayers, have been proposed [73]. These materials afford a good compromise between minimum electrical resistivity and high optical transmittivity in the visible light spectrum when patterned on see-through materials such as glass or transparent polymers. A technique to improve the efficiency of the transparent antennas, without affecting their transparency, is the application of a layer of highly conductive coating or metallization strips on the antenna edges where the current density is high [72].

Among SSs, or in general distributed systems within the IoT vision, a fast growing field of research is represented by wearable electronics for BANs [74]. In this case, the integration of electronic devices in the garments requires the development of wearable and washable antennas and antenna arrays on fabrics. Washable antennas can be realized by covering textile antennas by a breathable thermoplastic polyurethane coating in order to protect the device against water absorption and corrosion [69].

Although dimension constraints are not very critical for distributed systems on cheap materials, they cannot be neglected thoroughly. At RF, for example, high permittivity materials [68] and magnetic composite substrates [75] can be adopted. Artificial magnetic conductors (AMC) can be employed alternatively to the magnetic composites with similar results [76]. These approaches are simply demonstrated from the wavelength equation: wavelength is a function of the relative permittivity and permeability and adopting suitable materials to increase these values, the effective wavelength, and therefore the antenna size, decreases. Anyway, the use of these materials introduces a tradeoff between dimensions and performance: generally the substrate losses decrease the antenna radiation efficiency, thus affecting the communication range of the overall wireless system, as documented in [68], [75], and [76].

In terms of design methodology, the introduction of unconventional materials as well as the environmental constraints posed by distributed systems and systems for IoT influence and drive the design strategies. Some solutions are proposed in the literature to cope simultaneously with these constraints; in [68], shielded configurations have been analyzed to mitigate environmental sensitivity. In [69], an example of robust patch antenna for BAN application that reduces the effect of the body on the performance is illustrated; in [77], the use of broadband antennas, such as the Chebyshev monopoles with a fractional bandwidth of about 40%, is proposed to reduce the frequency shift introduced by the background materials or by the bending effects.

In SSs, and in general in IoT applications, antennas are used both to transmit and receive information and to harvest the necessary energy from the surrounding environment. Regardless of the fact that the available energy is randomly released in the environment by existing services (GSM, WiFi, and so on, in urban and semi-urban environments [78], [79]) or purposely delivered to empower a distributed population of nodes [80], antennas have to be able to harvest EM energy. This kind of "double effect" antenna is widely referred to in the literature as "rectenna": it combines rectifying circuitry with EM to electrical energy transduction.

The fundamental codesign techniques of antennas and rectifiers, focusing on the improvement of the conversion efficiency exploiting matching circuits, are described in [53]. Harmonic-balance and load-pull simulations are often used in order to find the optimal impedances that allow best efficiency to be obtained as a function of the EM incident power.

Multiband, broadband, and circularly polarized antennas are often adopted in EH applications to reduce the overall sensitivity to the environment. An example of planar antenna array for EH applications, in agreement with the SS principle, is documented in [81]: spiral antennas are proposed in order to provide a wide operating frequency band, and the rectification circuitry is optimized and characterized for low incident power levels. Similar antenna array for UWB EH is shown in Fig. 7.

A rectenna can be used in addition to the communication antenna or, alternatively, the same antenna can be used for both EH and data transmission. The use of different antennas is generally adopted if harvesting and communication are carried out at different frequencies and, mainly, in order to enhance harvesting efficiency without decreasing communication performance. In any case, this requires a codesign and can affect the node dimension and complexity. Alternatively, a single antenna can be a feasible compromise if communication and harvesting share the same frequency band and if the antenna harvesting efficiency is not the main issue; examples are the passive RFID tags empowered by the reader with a standard RFID antenna able to provide both EH and communication capability, as documented in [64] and [65].



Fig. 7. ***Scheme of the rectenna array able to collect RF energy even in a broadband (depending of the kind of receiving antenna element), according to the solution adopted in [81].***



Fig. 8. ***Hybrid rectenna for solar and EM–EH. The hybrid rectenna consists of a broadband antenna and a solar cell combined in the same structure. After [82].***

However, the EM–EH is not the only solution to energize nodes and SS elements: hybrid EH, in fact, can be performed by exploiting different energy sources; that is, combining the rectennas with other sources of energy.

Recently, a low-cost and conformal structure for hybrid EH, based on low-cost and flexible poly-ethylene terephthalate (PET) substrate and an amorphous silicon solar cell, has been proposed in [82]; other examples are discussed in [20] and [83]. The use of low-cost, printable photovoltaics deposited on flexible substrates to form part of the antenna radiating structure is documented in [84]. In all these contributions, the main challenge appears to be the codesign of the antenna and solar cell in order to avoid reciprocal detrimental effects. The antenna is designed with a solar cell integrated on top of the radiating surface to obtain good radiation characteristics and to incorporate connections for the extraction of the dc provided by the solar cell. In [82], it was demonstrated that, by adopting thin film solar cells and paying attention to not exceeding the perimeter of the RF antenna, the solar cell can be integrated so as not to significantly affect the performance of the antenna. The hybrid rectenna for solar and EM–EH documented in [82] is shown in Fig. 8.

In terms of industrial assembly, the use of new materials and the need for low-cost and large-scale fabrication techniques would be fostered by architectures more insensitive against geometrical errors and placement misalignments. Following this direction, EM coupling can be exploited instead of ohmic contact to connect antennas on a flexible substrate to Si chips or, more generally, to the active circuitry [85]. This technique exploits a planar heterogeneous transformer, with the primary and secondary windings implemented on the antenna substrate and the Si chip, respectively. In this way, the galvanic contacts and the soldering process are avoided, and the final structures have been proven much more robust to alignment errors than traditional ohmic techniques without any significant performance degradation. By artificially applying a misalignment of 150 μm, which is the common dimension of a soldering pad, the technology proposed in [85] causes a loss increment of only 0.1 dB, due to the applied misalignment, while the same misalignment, when adopting ball grid arrays, would have implied missing the contact. This approach is quite attractive especially in combination with nonrigid materials where mechanical stress can result in significant substrate deformations. Recent contributions show the application of the aforementioned approach to inkjet printed antenna on PET substrate coupled to the chip for wireless nodes [86] and a textile patch antenna, magnetically coupled to the active circuitry, suitable for garment integration (see Fig. 9) [87], the reflection coefficient of which is shown in Fig. 10.

In order to testify the robustness of the proposed solution against uncertainties inherent to textile and garment electronics assembly, the radiation efficiency of the antenna, as a function of horizontal and vertical misalignment of the two transformer windings, used to perform the magnetic coupling, is plotted in Fig. 11(a) and (b), respectively. This technique can be extended also to interlayer communications of multilayer devices, and an example is documented in [88], where the circuitry fabricated on different garments communicates by means of overlapped coils.

V. CHIPLESS APPROACH

It has already been discussed that SS represents a possible technology for the development of killer applications within the IoT paradigm. Thanks to the convergence of several technologies, ranging from EH and sensing to RFID and LAE, SS can afford complex functions. For example, SSs can be used in intelligent buildings for structural monitoring and alarms (fire, for instance). To achieve these goals, SS must be equipped with a huge number of tags, each one monitoring a small portion of the surface itself.

The passive RFID systems can be divided into two families, namely, chip-based and chipless tags. The first family usually exploits a low-power complementary metal–oxide–semiconductor (CMOS) chip to implement the main tag functions [RF carrier rectification, dc voltage regulation, amplitude shift-keying (ASK) demodulation, IDentification code (ID) decoding, load modulation, etc.] and thus can be adapted to sensor applications by a few additional circuit blocks [signal conditioning,



Fig. 9. ***Example of textile patch antennas operating at 2.4 GHz. The antenna and the ground plane are made of Flectron, a conductive textile, and the substrate is black foam. These materials are flexible and integrable in the garments. Magnetic coupling is exploited to connect the antenna and the active circuitry on flexible substrate. After [87].***



Fig. 10. ***Measured reflection coefficient of the previous textile antenna in the frequency band 2.4–2.48 GHz. After [87].***



Fig. 11. ***Variation of the radiation efficiency evaluated versus (a) horizontal and (b) vertical misalignment between the antenna and the circuit windings. This test allows the robustness of the antenna performances against mounting uncertainties inherent to textile electronics to be evaluated at glance. After [87].***

analog-to-digital converter (ADC), etc.]. The main advantage of such an approach is the digital modulation of the transmitted signal, and thus the flexibility of the related data treatment, as shown in [89] and [90]. The production costs of chip-based tags are mostly associated with the heterogeneous integration of the silicon chip with the antenna [85], [91], the latter being manufactured typically on a flexible substrate or a textile substrate [92]–[97].

In order to reduce the aforementioned costs and to save as much energy as possible, solutions requiring minimum amount of electronics must be pursued. For this purpose, the chipless tag family was introduced and applied to wireless sensing in the recent years [98]–[103]. It is worth recalling here that the introduced buzzword "chipless" stands for a family of tags that are actually able to implement their functionalities by using only a few lumped components and passive distributed elements, without requiring any electronic integrated circuit (IC), the chip indeed, to be mounted.

The standard chipless tags (i.e., only coding and no sensing) exploit, basically, two mechanisms, namely, time-domain and frequency-domain scattering [64]. In the first case, the elapsed time between multiple reflections is used for coding. These reflections are obtained, at tag level, by connecting the antenna to a transmission line structure with several discontinuities. In the second case, instead, the tag has a specific frequency signature that is decoded at the reader level; to implement such a behavior, a coded series of resonators is realized on the tag antenna in order to reflect or not the corresponding frequency. Both approaches (time and frequency domain) lead to tag circuits that are not necessarily easy to miniaturize; nevertheless, it is worth noting that they are compliant with the LAE paradigm.

When dynamic sensor information has to be added to the static identification, we talk about chipless RFID sensor tags; these exploit an antenna, the electrical properties of which are controlled by the change of the physical parameter to be detected. There are, mostly, two proposed approaches for this. The first one is to induce a permanent change in the antenna property when a certain critical threshold (acceleration, temperature, fluid level, etc.) is exceeded [104]; this is useful for alarm type operations. The second one exploits a sensing load, i.e., a load the impedance of which is controlled by the sensed variable, connected to an antenna [105]. In both cases, the whole wireless sensor system (tag and reader) needs to have absolute accuracy, thus limiting the system performance with respect to both distance and fabrication tolerances.

A different method has been recently introduced in [106]. In this paper, a novel sensing principle is associated to the generation of an intermodulation signal from a tag, the latter being illuminated by two waves at different frequencies. The advantage of this idea is that the tag response is generated at a known frequency, thus the presence or the absence of such a signal can hardly be misinterpreted. Similar techniques have been used in harmonic radar systems [107] and in one-bit frequency doubling tags [108].

In line with the above ideas, a novel and completely original approach was proposed in [20] and [109] to solve the issue of absolute accuracy of the most of the passive chipless RFID sensors. The chipless tag described in [109] is based on the harmonic radar concept [110], [111], i.e., on a tag that, being illuminated by a carrier at frequency f_0, is capable of generating the second harmonic $2f_0$.

A simplified block diagram of the tag is illustrated in Fig. 12. For this purpose, the sensor information is encoded as the phase difference between two signals, one acting as the reference signal for the other one. First, the tag receives a carrier at frequency f_0. Then, two equal signals at frequency $2f_0$ are generated by means of a diode-based frequency doubler and a power divider. At this point, one of the two signals is phase-shifted using a passive sensing element. Finally, the $2f_0$ signals are reirradiated by



Fig. 12. ***Simplified block diagram of a harmonic chipless tag with sensing capabilities. After [109].***

exploiting two orthogonally polarized antennas. With this approach, the sensor information can be extracted by a suitable reader equipped with two complex (I/Q) receivers.

It must be observed that chipless tags, due to their inherent simplicity and extremely low number of lumped components, are easily realizable on flexible substrates by means of metal laminate [29], [30] and inkjet printing technologies. In particular, antennas [112], diodes [113], and passive sensing elements [114]–[117], i.e., all the main tag components, have already been experimented in cellulose-based materials. This will soon make SSs, equipped with sensing chipless tags, feasible at affordable prices.

VI. QUASI-OPTICS

"Quasi-optics concerns the propagation of EM radiation when the size of the wavelength is comparable to the size of the optical components (e.g., lenses, mirrors, and apertures) and hence diffraction effects become significant" [118].

In optics, operations are usually performed by using lenses. At EM frequencies, by following the quasi-optics analogy, lenses become large arrays, several wavelengths in size, of unconnected elements, each of them being able to get part of the signal incident on the array (usually focused by using a Gaussian beam), to carry out an operation and to irradiate the modified signal. The sum of the radiated signals modified by the array elements ends up in a radiated beacon elaborated with respect to the incident one [118]–[120]. From a historical point of view, quasi-optics was first introduced experimentally by Heinrich Hertz in the late 1880s [120] when he demonstrated the possibility of collimating EM signals on a multiwavelength surface by using cylindrical reflectors and studying effects that, until that time, were observed only at infrared and visible EM spectrum.

After more than 70 years, owing to the increasing demand for bandwidth and to the development of optical wavelength systems, quasi-optics experienced its palingenesis at the millimeter and submillimeter wavelengths.

We can classify the quasi-optical components into three main categories: frequency independent, frequency selective, and active devices. Frequency-independent surfaces include: delay lines, polarizing grids, hybrid junctions [121], attenuators [122], power dividers [123] and combiners [124], nonreciprocal devices [125], [126], absorbers, and calibration loads. Frequency-selective surfaces [127]–[129] include: inductive grids, capacitive grids, resonant grids, thick structures (perforated plates), and interferometers. Active devices include: oscillators [129], [130], amplifiers [131], [132], mixers [133], [134], phase shifters [135], [136], multipliers [108], [137]–[139], and switches [140]. This approach has been used so far mainly at millimeter and submillimeter frequencies because, being the size of the apparatuses proportional to the wavelength of the radiated wave, lower frequencies would have been prohibitive due to the very large size required. With the present development of technologies for LAE, however, quasi-optics has become a feasible approach even at RF and microwave bands, where large arrays of operational elements can be conceived.

Inheriting the quasi-optical approach, contact-less EM wave processing (filtering, frequency conversion, selective shielding, etc.) can be implemented even at low frequencies (in the order of megahertz). Two pioneer examples are switches [140] and the cross-dipole frequency doubler, proposed in [108], and implemented in [141], where, among various operating principles, the generation of harmonics is chosen to demonstrate the feasibility of such a component at microwave frequencies.

The layout of the proposed quasi-optical frequency doubler is shown in Fig. 13. The structure is inkjet printed on a cellulose-based substrate (a piece of photografic paper from Kodak). It consists of two crossed $\lambda/2$ dipoles. The longest dipole receives the incoming power at the fundamental frequency $f_0 = 3.5$ GHz, while the shortest one transmits the generated power at the doubled frequency $2f_0$ in an orthogonally polarized orientation. The length of the dipole operating at f_0 is 32 mm, while the $2f_0$ dipole is 16 mm long. The width of the tracks used to implement the dipoles is about 2 mm. The multiplication is provided by four diodes in a bridge configuration, thus forming a fully balanced multiplier unit.

Due to the omnidirectional nature of the dipole antenna, the harmonic signal is irradiated with the same intensity in the azimuthal plane (small differences are due to both the dielectric substrate and the planar nature of the dipole conductors). This means that the harmonic signal is reflected toward the reader and the transmitter toward other directions at the same time. A measurement of the received power at $2f_0 = 7$ GHz is reported in Fig. 13(b). Here the interrogation distance is 10 cm and the



(a)

(b)

Fig. 13. ***Cellulose-based prototype of the (a) crossed-dipole frequency doubling tag and (b) measured second-harmonic response. The measurements have been carried out interrogating the tag at $f_0 = 3.5$ GHz and receiving the $2f_0 = 7$ GHz frequency component. The interrogation distance is 10 cm, and the transmitted power is equal to 20 dBm. The transmitter is equipped with a two-element Yagi antenna at f_0, while the receiver uses a helix antenna at $2f_0$. The fundamental frequency dipole is 32 mm long. After [141].***

transmitted power is equal to 20 dBm. The transmitter (reader side) is equipped with a two-element Yagi antenna at f_0, while the receiver (reader side) uses a helix antenna at $2f_0$. In these conditions, the power received from the cellulose-based (paper) tag prototype at $2f_0$ is about -80 dBm. The same structure implemented on a plastic substrate produces more power, mainly because of a better frequency tuning. An improved efficiency could be achieved by: 1) adopting a frequency multiplier with better harmonic terminations; and 2) using directive antennas in order to address the power only toward the reader.

In the frame of the IoT, the crossed-dipole tag is a very simple one-bit tag that can alarm a system when it is placed within the range of the reader. However, with very simple modifications, this idea can be used to implement a variety of on/off sensors (the paper substrate can be easily torn when a certain mechanical strain is exceeded).

The crossed-dipole structure can also be used as a building block to form arrays, an example being shown in Fig. 14. These arrays are mainly intended for LAE applications where a complete surface can be interrogated and answered by generating a harmonic signal. The fabricated prototype uses a Rogers substrate, thus it is not flexible. However, adopting a cellulose-based substrate, a flexible structure can be built. The bending capability of cellulose-based circuits is quite good and only limited by the discrete components mounted on them.



Fig. 14. ***Example of quasi-optical frequency doubler based on an array of crossed dipoles. This structure is implemented on a Rogers substrate, but this can be substituted with a cellulose-based material to reduce costs and obtain mechanical flexibility.***

The second example consists of a paper-based contactless frequency doubler for harmonic RFID applications [142]. The doubler, realized on paper substrate, generates the harmonic signal by means of a single Schottky diode. The system operates at 7.5 and 15 MHz, and these frequencies are chosen, without lack of generality, to accomplish the realization of a fully organic frequency doubler exploiting paper printed coils and organic diode (pentacene-based), the present frequency limit of which is around 15 MHz [143]. Fig. 15 shows a picture of the organic tag, while Fig. 16 shows the doubling efficiency of the organic tag versus transmitting/receiving (TX/RX) distance, assuming TX power as a parameter (for the sake of completeness, it is worth noting that TX and RX antennas of the reader are equal to the RX and TX antennas of the tag, respectively).

As a final remark, it is worth noting that, to the authors' knowledge, only planar developments of quasi-optical arrays have been proposed so far; reasonably, combining quasi-optics with LAE related technologies can lead, in the near future, to new SS solutions only in a limited planar extent.

VII. SMART FLOOR

The new concept of smart cities is generating a group of new scenarios that will impose a new way people interact with the environment. This immersion brings the IoT to a new level of relationship with people and environment,



Fig. 15. ***Fully organic tag prototype of the frequency doubling tag operating at 7.5–15 MHz. After [142].***

where the scenario around is aware of people's needs and can interact with their way of living.

This new concept brings IoT to areas that cover broad topics, including transportation, energy distribution, data communications, and all technologies in a sense that they will become transparent to the normal users and citizens.

The growth of smart cities will significantly increase the quality of life, the reduction of energy waste, and the availability of information by using ICT. All these developments have, as a motivation, the overall inclusion of people into the city in a way that ICT should become completely embedded into our surroundings.

These new concepts are viable only if the smart environments are enabled by IoT. IoT is actually taking shape and is growing everyday through the number of devices that get connected to each other.

Nevertheless, most of these devices that team up with each other to build up the IoT world are powered by some kind of power sources. This is actually the main limitation of present IoT solutions. In order to be able to create real IoT environments, RFID, wireless power transfer (WPT), and EH devices appear as a major enabling technology for the IoT, due to their inherent simplicity and ability to provide sensing to remote objects without the need for constant powering.



Fig. 16. ***Conversion (doubling) loss of the reader tag harmonic RFID system as a function of the reader tag distance, assuming the output reader power as a parameter. After [142].***

In this scenario, the concept of a smart floor becomes real. Smart floors should be capable of interacting with the environment seamlessly and be aware of persons and objects on top of them.

The focus of this section is going to be smart floors as an information system, where RFID capabilities are used to provide an identification and information source embedded into the floor. This massive RFID immersion will allow to create low-power high accuracy location, navigation, and, generally speaking, an information system that can team up with passers in a noninvasive way.

In this approach, the system uses passive RFID tags that are spread beneath a flooring in order to create a map that can be read with a mobile unit that might be self-powered through energy harvested from the movements of the subject to be located [144], [145].

This new location system based on smart floors can actually be extremely competitive when compared with existing solutions; among them, we can take into consideration those based on image processing [146]; they provide a high level of information at the price of high cost, power consumption, and intrusiveness. Another approach is based on pressure sensors [146], [147], providing actually a different type of smart floors; pressure sensors are nonintrusive and can be less expensive in terms of equipment when compared to the imaging systems; however, they can still be quite expensive to install into the floors; moreover, they do not allow for seamless identification of an individual in a given space. Eventually, ultrasounds [148] and RF localization system detection [149] have to be listed; although very flexible, they require dedicated communication infrastructures, additional complexity and costs, and they are mostly sensitive to environmental changes, both in terms of accuracy and functionalities.

The just mentioned smart-floor-based system tackles most of these challenges as it is very low cost, able to have a good, and precisely predictable, accuracy, and able to detect different users in a given space.

A. RFID-Based Smart Floor Including Material Aspects

Smart environments and floors should be completely seamless to the users. This entails the need to embed electronic devices into the environment in a noninvasive way. Nevertheless, this embedding of electronic devices, mainly wireless transceivers into the floor, is not a simple matter. Floors, in fact, have been made by almost the same kind of materials for centuries; tile industries are weakly available to introduce new materials to match



Fig. 17. ***Readable distance test scheme (a) without and (b) with tile. After [144].***

requirements posed by embedded electronics. Similar considerations can be made about the consolidated techniques to build apartments and houses: they are quite mature and whatever adaptation of them to embedded electronic systems is unrealistic. The consequence of this is that constitutive elements of SSs embedded into the floors must be suitable to materials and technologies already present: materials available are those adopted for tiles and SSs must be adapted to building constraints.

In this section, we focus on the most important approaches for the characterization of the EM properties of the materials, commonly adopted in floors, and their interactions with our electronic radio systems. As an example, ceramic tiles are going to be selected as the floor element where electronic tags have to be embedded.

Ceramic tiles have been used for ages to pave floors. These make up a great deal of most floor types in public buildings, from airports to banks, therefore, they are the most interesting flooring elements to investigate.

As the first approach, the study of the influence of some materials for floor surfaces, such as ceramic, cork laminates, and wood, in the communication between the transmitter and receiver devices has to be made; in this case, low-frequency (13 MHz) inductors are going to be used as the wireless interface.

In order to do the measurements, traditional RFIDs are used, which simplify the measurement approach significantly. A test setup is shown in Fig. 17, and experimental results are summarized in Table 3. What can be seen from the results presented in the table is that none of the tested materials affect the electrical characteristics of the RFID propagation significantly.

Another approach to the measurement is to evaluate the impact of the presence of metal inclusions beneath the ground; these can appear from pipes or from buildings supporting structures. In order to test this scenario, the presence of a metal sheet close to the coil was tested to verify its impact on the RFID reading distance. The test setup is presented in Fig. 18. In this case, when the reader is aligned (1) with the center of the coil beneath the tile, a minimum distance of 10 mm between the metallic sheet and the tag must be guaranteed in order to allow for the proper reading of the tag. In the other approach, the edge aligned scenario (2), the minimum distance between the metallic sheet and the tag increases to 30 mm to allow for communication.

Table 3 Results From Average Readable Distance Test

Tile type	Aligned (1)	Edge aligned (2)	Unaligned (3)
Without tile	4.5 cm	4.3 cm	2.4cm
Ceramic tile 4 mm thick	4.5 cm	4.3 cm	2.4cm
Ceramic tile 6 mm thick	4.5 cm	4.3 cm	2.4cm
Ceramic tile 7 mm thick	4.5 cm	4.3 cm	2.4cm
Cork laminate 5 mm thick	4.5 cm	4.3 cm	2.2cm
Wooden floor 8 mm thick	4.3 cm	4.2 cm	2.2cm



Fig. 18. ***Readable distance test scheme with metallic sheet presence. After [144].***

This test allows us to conclude that, in a real scenario, when considering the typical distance from the antenna to the floor, where the reader is usually embedded into a mobile device, a minimum distance from the tile to any metal inclusions in the ground has to be guaranteed. As seen, this safe distance should be at least 30 mm.

B. Navigation Approach Based on Smart Floors

A meaningful example of the applications of the smart floor concept is the demonstrator developed at the University of Aveiro, Aveiro, Portugal. It allows a nomadic RFID reader on top of it to be identified and localized by means of a smart floor.

The prototype in the present state is composed of four main components: a set of tagged tiles forming the smart floor, the nomadic reader, a wireless communication device to connect the reader to the information system, and a computer on which the location and navigation software is installed. A potential scenario of application for the monitoring of elderly housing is shown in Fig. 19. In the demonstrator presented, the RFID reader is connected to the radio unit and inserted into the user's shoes in order to read the passive tags as the user walks around a given area. The tile IDs are detected by the reader and sent to a centralized information system using, without lack of generality, a nonstandard wireless communication system, purposely developed in the laboratory.



Fig. 19. ***Example of smart floor application scenario.***

The software in the computer then decodes the ID of the smart tile, and correlates it with a preloaded referenced map, thus being able to provide the precise position of the walker in the environment.

The location can be subsequently translated to a navigation system, and combined with artificial intelligence to allow navigation, situation awareness, etc.

Plenty of applications and related solutions can be envisioned on the basis of this smart floor approach: robot control, automatic pallet managements, prevention in harsh environments, and so forth.

VIII. SMART SHOES AND BAN

The aforementioned smart floor (Section VII), initially proposed to localize moving subjects in a given area, actually allows for the implementation of a very low-cost, accurate, and reliable system able to provide each kind of detectable information from an equipped area to the Internet.

To exploit the potentiality of a smart floor, it is obvious that developing purposely conceived communication units acting, on the one hand, as readers for tag tiles and, on the other hand, as communication systems with the web is needed.

One of the investigated systems for this is the so-called smart shoe [21]. Smart shoes are intended as shoes incorporating a reader able to illuminate the tag embedded into the tile and a wireless interface to communicate data to the web. To this extent, smart shoes can be seen as hubs of BANs able, on the one hand, to get information from the surrounding environment (body included) and, on the other hand, to communicate the collected information to the Internet. According to common buzzwords, they can be seen as the second technological layer, just above the first physical one consisting of tagged objects, in a hierarchical picture of IoT. Alternatively, they provide the cloud of nomadic readers with networking capabilities required for the implementation of the so-called networked RFID (N–RFID) [150] strategies. In the referred structure [21], the necessary antenna system is inkjet printed on paper, thus exploiting the process described in Section II, and it is a trademark-logo-shaped dual-band antenna working at 900 MHz and 2.4 GHz. A block diagram and its equivalent realization are shown in Fig. 20: it is worth noting that the reader itself works at 13.5 MHz exploiting the near-field communication (NFC) concept, according to what is stated in the smart floor section; as a consequence, there are no issues about the interference between the dual-band antenna and the NFC reader. Moreover, an approach similar to [145] is proposed to power the reader: the idea here is as well to harvest the energy produced by the human walking by means of piezoelectric materials embedded into the sole of the shoe.



(a)

(b)

(c)

Fig. 20. ***(a) Block diagram, (b) photo, and (c) dual-band antenna results of the smart shoe that works as an energy autonomous reader for smart floors able to collect the localization data from the smart tiles and send them to a centralized system. After [21].***



(a)

(b)

Fig. 21. ***(a) Mounted electronics on shoe with piezoelectric energy harvester and block diagram of the transmitting tag, driven by the EH unit. (b) Photograph of the assembled prototype showing the key components packaged on an organic flexible substrate. After [145].***

Fig. 21(a) shows the shoe with the mounted electronics consisting of a trademark-logo antenna inkjet printed on a flexible paper substrate together with the circuits in which the components [Fig. 21(b)] are fixed by conductive epoxy glue. A piezoelectric push button was embedded in the shoe to scavenge energy from human walking strike. This energy is then collected by a simple electronic circuit based on off-the-shelf components and used to supply the RFID transmitter. As reported in [145], the system is composed by the power-generator/energy-conversion device, the energy storage device, the power regulator circuit, and the RF transmitter that can broadcast the tag ID and the stored information.

When the push button is pressed, an inner spring is compressed and when the pressure exceeds a fixed threshold, the spring-loaded hammer will be released to deliver the dynamic mechanical force to the piezoelectric component; once the hammer strikes the piezoelectric element, a pressure wave is generated and reflected a few times between the hammer and the element, creating a mechanical resonance [151]. As a result, the generated output voltage follows closely an alternating current (ac) signal course. The signal out of the piezoelectric element is characterized by high voltage and low current; therefore, since this RF circuitry requires lower voltages at higher currents, a step-down transformer is used for better impedance matching to the following circuitry.

An energy storage device is adopted to collect the electrical energy and to provide it to the transmitter even when the external power source is temporarily unavailable; in fact, the RF transmitter takes tens of milliseconds to transmit one complete word, while the piezoelectric push button harvests energy in a transient time. To store the collected energy, a 4.7-μF tank capacitor was chosen. An ac–dc full wave diode bridge rectifier is used to convert the ac voltage from a piezoelectric element into a dc source and a dc linear regulator is added to adapt the dc voltage across the capacitor to 3-V transmitter operating voltage. For this purpose, a MAX666 low-dropout linear regulator, providing a stable 3-V supply until the tank capacitor charge is drained below the reference level of the dc linear regulator itself, is chosen. The transmitter used, the LINX

Table 4 Shoe Energy Performance Summary

Energy provided by the pushbutton	stored in the capacitor	848.4 μJ
Utilized energy	below 2.7 V capacitor voltage, the active RFID tag stops transmitting	17.1 μJ
Available energy	848.4 μJ − 17.1 μJ	831.3 μJ
Energy required by the circuit for a one-word transmission	Power Needed for 50 ms operation: 9 mW	450 μJ

TXE-433-KH2 [152], is able to combine a highly optimized RF transmitter with an onboard encoder.

The maximum voltage across the capacitor is 19 V; therefore, the energy stored in the capacitor can be calculated to be close to 850 μJ. After the strike, the regulator becomes active, providing power to the tag circuitry; its 3-V output remains constant before it starts to drop to zero according to the capacitor discharge rate. When the voltage across the capacitor drops below 2.7 V, the active tag stops transmitting. The resulting energy left in the capacitor and not used is about 17 μJ. The required time for successful completion has been measured to be close to 50 ms; the total circuit energy consumption for a 50-ms transmission is then approximately 9 mW (Section IV). Consequently, the energy required for a one word transmission is approximately 450 μJ, much less than the power collected by the energy conversion and regulation unit. The energy performance of the smart shoe is summarized in Table 4.

"Smart" solutions like smart shoes are suitable for smart floor interaction and for collecting information (position included) from them. The smart shoe has actually a double functionality: on the one hand, it is a means to collect information from the environment (smart floor included) and from the on-body sensors and apparatuses; on the other hand, it transfers data to the Internet, via WiFi, for instance, while likely receiving control and feedback signals. To this extent, it contributes to the development of wearable electronics for body-centric communication systems, according to the scheme of Fig. 22. This class of devices is based on the BAN concept (see Fig. 22): a network of wearable computational units, sensors, energy harvesters, and transceivers networked and implemented around the human body. The information is acquired by means of several sensors and, after processing and digital modulation, is transmitted by means of off-body transceivers. The most attractive application of BANs and wearable systems, so far, is probably health monitoring [88], but the number of foreseeable applications is constantly increasing (personal fitness monitoring, personal audio system, personal alarm set, and so on). Today, a big contribution to the BANs is being given by the interaction with portable devices such as smartphones which can be exploited as gateways.

Low-power ICs, sensors, and wireless communications are key elements of the BANs, and the use of EH techniques and mixed technologies such as RFID, as in the above described smart shoe, can contribute to the development of autonomous BANs. According to the notation adopted in [74] and [153], BANs can exploit wireless communication not only for off-body communications with other systems, but also for on-body and in-body communications to interconnect networked devices [wireless body area networks (WBANs)]. Generally, the proposed WBAN solutions are based on existing communication standards; but, recently, the IEEE 802.15.6 working group has provided a standard for short-range, wireless communications in the vicinity of, or inside, a human body based on ISM bands for BANs [154]. In this rapidly evolving scenario, smart shoes can be seen, in turn, as a promising mean to interface information coming from smart floors to the BANs and ultimately to the Internet, directly or via portable devices.

IX. ENERGY SKIN

Within SSs, another area is emerging, which requires dc energy. The availability of devices that can actually increase the battery life of our electronic gadgets [155] is the holy grail of IoT; the idea is actually to convert energy from



Fig. 22. ***BAN integrated with IoT: the data sensed on the human body and collected by smart devices are sent to the Internet through the standard protocols like third generation/fourth generation (3G/4G) and WiFi.***



Fig. 23. ***EM source, likely supplied by solar energy in order to keep eco-friendliness, is used to broadcast energy to the urban neighborhood where houses are equipped with local RF–dc converters able to power supply local devices (external lamps in the example).***

different sources, as solar to dc [156], EM radio signals to dc, thermal to dc [156], vibration to dc [157], etc. [158].

Portable converters from solar to dc are today commonly available on the market at very low prize. Similar portable scavengers can be easily envisioned even for other energy converters. On this basis, plenty of sophisticated and more complex solutions are being proposed. Just as an example, we report the solution in Fig. 23, where the solar energy is used to supply an EM source that broadcasts RF energy in the surrounding urban environment; this energy is converted to dc energy at building level and, in turn, exploited to supply external local lamps. This approach was conceived for space applications [159], [160], but could be used in certain conditions in earth stations as well. The concept can actually move forward and be integrated into a smart skin, in the sense that all devices could be powered up by the skin energy conversion that a person can carry (vibrational, thermal, RF, etc.). This will become possible by integrating paper and textile radio electronic circuits in the smart skin surfaces of our clothes.

X. CONCLUSION

This paper focused on smart surfaces concept. This concept was introduced as a way to provide solutions to societal instances by means of technologies and techniques that today are gaining great momentum thanks to IoT development. The foreseeable IoT evolution, in fact, calls for systems and subsystems that are more and more energy conservative, fully autonomous (battery-less and not connected to the grid), as recyclable as possible (ultimately 100% biodegradable), flexible, and extremely low cost to be embedded in as many objects as possible. In order to meet these expectations, several technologies have to be implemented concurrently. This paper illustrates some of them, namely, recyclable and reliable materials, printing and R2R compatible techniques, conformal antennas on unconventional materials, and chipless RFID.

Subsequently, it has been shown how these technologies enable a fairly new branch of IoT development, represented just by SSs.

SSs are in their infancy; nevertheless, some examples, enabled by the aforementioned technologies, can be cited. Among them, the way to inherit "quasi-optics" and extend them to RF frequencies even below gigahertz is shown, and the smart floor implementation as a means to provide precise localization as well as assisted paths platforms has been reported. Energy skin as a means to convert several energy sources (solar, thermal, vibrational, EM, etc.) in electric one is described as well.

The reported examples must be researched as a new paradigm for potential promising developments aiming at providing new LAE solutions for the future networked society. ■

REFERENCES

[1] European Union (EU), "The ICT sector and RDI," Digital Agenda Scoreboard, 2012. [Online]. Available: http://ec.europa.eu/digital-agenda/sites/digital-agenda/files/scoreboard_ict_sector_and_rdi.pdf

[2] J. Manyika *et al.*, "How the Internet of Things is more like the Industrial Revolution than the Digital Revolution," MGI Rep., 2013. [Online]. Available: http://www.mckinsey.com/insights/business_technology/disruptive_technologies

[3] D. Evans, "The Internet of Things: How the next evolution of the internet is changing everything," CISCO White papers, 2011. [Online]. Available: http://www.cisco.com/web/about/ac79/docs/innov/IoT_IBSG_0411FINAL.pdf

[4] I. G. Smith, "The Internet of Things 2012 New Horizons," IERC European Research Cluster on the Internet of Things, 2012.

[5] J. Morse, "Nanofabrication technologies for roll-to-roll processing," in *Proc. NIST-NNN Workshop*, Boston, MA, USA, Sep. 2011, pp. 1–31.

[6] A. Arias, J. MacKenzie, I. McCulloch, J. Rivnay, and A. Salleo, "Materials and applications for large area electronics: Solution-based approaches," *Chem. Rev.*, vol. 110, no. 1, pp. 3–24, Jan. 2010.

[7] T. Kampke, B. Kluge, and M. Strobel, *Field and Service Robotics*. New York, NY, USA: Springer-Verlag, 2008, ser. Springer Tracts in Advanced Robotics.

[8] M. Shur, "Giant area and flexible electronics," in *Proc. IEEE Nanotechnol. Mater. Devices Conf.*, Oct. 2006, vol. 1, pp. 264–265.

[9] M. Steer *et al.*, "Global modeling of spatially distributed microwave and millimeter-wave systems," *IEEE Trans. Microw. Theory Tech.*, vol. 47, no. 6, pp. 830–838, Jun. 1999.

[10] A. Rida, L. Yang, R. Vyas, and M. Tentzeris, "Conductive inkjet-printed antennas on flexible low-cost paper-based substrates for RFID and WSN applications," *IEEE Antennas Propag. Mag.*, vol. 51, no. 3, pp. 13–23, Jun. 2009.

[11] F. Alimenti, P. Mezzanotte, M. Dionigi, M. Virili, and L. Roselli, "Microwave circuits in paper substrates exploiting conductive adhesive tapes," *IEEE Microw. Wireless Compon. Lett.*, vol. 22, no. 12, pp. 660–662, Dec. 2012.

[12] D. Tobjörk and R. Österbackaa, "Paper electronics," *Adv. Mater.*, vol. 23, no. 17, pp. 1935–1961, 2011.

[13] P. Calvert, "Inkjet printing for materials and devices," *Chem. Mater.*, vol. 13, no. 10, pp. 3299–3305, 2001.

[14] G. Orecchini *et al.*, "Inkjet printed organic transistors for sustainable electronics," in *Proc. 60th Electron. Compon. Technol. Conf.*, Jun. 2010, pp. 985–989.

[15] L. Yang, G. Orecchini, G. Shaker, H.-S. Lee, and M. Tentzeris, "Battery-free RFID-enabled wireless sensors," in *IEEE MTT-S Int. Microw. Symp. Dig.*, May 2010, pp. 1528–1531.

[16] G. Shaker, S. Safavi-Naeini, N. Sangary, and M. Tentzeris, "Inkjet printing of ultrawideband (UWB) antennas on paper-based substrates," *IEEE Antennas*

Wireless Propag. Lett., vol. 10, pp. 111–114, 2011.

[17] R. Vyas *et al.*, "Inkjet printed, self powered, wireless sensors for environmental, gas, and authentication-based sensing," *IEEE Sensors J.*, vol. 11, no. 12, pp. 3139–3152, Dec. 2011.

[18] G. Orecchini *et al.*, "Design and fabrication of ultra-low cost radio frequency identification antennas and tags exploiting paper substrates and inkjet printing technology," *IET Microw. Antennas Propag.*, vol. 5, no. 8, pp. 993–1001, Jun. 2011.

[19] S. Kim *et al.*, "Monopole antenna with inkjet-printed EBG array on paper substrate for wearable applications," *IEEE Antennas Wireless Propag. Lett.*, vol. 11, pp. 663–666, 2012.

[20] S. Kim *et al.*, "No battery required: Perpetual RFID-enabled wireless sensors for cognitive intelligence applications," *IEEE Microw. Mag.*, vol. 14, no. 5, pp. 66–77, Jul. 2013.

[21] C. Mariotti, V. Lakafosis, M. Tentzeris, and L. Roselli, "An IPv6-enabled wireless shoe-mounted platform for health-monitoring," in *Proc. IEEE Top. Conf. Wireless Sensors Sensor Netw.*, Jan. 2013, pp. 46–48.

[22] K. Sangkil *et al.*, "Inkjet-printed antennas, sensors and circuits on paper substrate," *IET Microw. Antennas Propag.*, vol. 7, no. 10, pp. 858–868, 2013.

[23] B. Cook, J. Cooper, and M. Tentzeris, "Multi-layer RF capacitors on flexible substrates utilizing inkjet printed dielectric polymers," *IEEE Microw. Wireless Compon. Lett.*, vol. 23, no. 7, pp. 353–355, Jul. 2013.

[24] B. Cook, J. Cooper, S. Kim, and M. Tentzeris, "A novel inkjet-printed passive microfluidic RFID-based sensing platform," in *IEEE MTT-S Int. Microw. Symp. Dig.*, Jun. 2013, DOI: 10.1109/MWSYM.2013.6697592.

[25] B. Cook, B. Tehrani, J. Cooper, and M. Tentzeris, "Multilayer inkjet printing of millimeter-wave proximity-fed patch arrays on flexible substrates," *IEEE Antennas Wireless Propag. Lett.*, vol. 12, pp. 1351–1354, 2013.

[26] C. Mariotti, B. Cook, L. Roselli, and M. Tentzeris, "High-performance inkjet-printed metal-insulator-metal (MIM) capacitors on lossy silicon substrate *IEEE Microw. Wireless Compon. Lett.*, 2014.

[27] D. Angmo, T. T. Larsen-Olsen, M. Jorgensen, R. R. Sazndergaard, and F. C. Krebs, "Roll-to-roll inkjet printing and photonic sintering of electrodes for ITO free polymer solar cell modules and facile product integration," *Adv. Energy Mater.*, vol. 3, no. 2, pp. 172–175, 2013.

[28] R. Sazndergaard, M. Hessel, D. Angmo, T. T. Larsen-Olsen, and F. C. Krebs, "Roll-to-roll fabrication of polymer solar cells," *Mater. Today*, vol. 15, no. 1–2, pp. 36–49, 2012.

[29] F. Alimenti *et al.*, "A 1.2 v, 0.9 mW UHF VCO based on hairpin resonator in paper substrate and Cu adhesive tape," *IEEE Microw. Wireless Compon. Lett.*, vol. 23, no. 4, pp. 214–216, Apr. 2013.

[30] F. Alimenti *et al.*, "24 GHz single-balanced diode mixer exploiting cellulose-based materials," *IEEE Microw. Wireless Compon. Lett.*, vol. 23, no. 11, pp. 596–598, Nov. 2013.

[31] C. Mariotti *et al.*, "Modeling and characterization of copper tape microstrips on paper substrate and application to 24 GHz branch-line couplers," in *Proc. Eur. Microw. Conf.*, Oct. 2013, pp. 794–797.

[32] L. Guoyu and W. Zhenkai, "Summarize of rfid technology and typical application," in *Proc. Cross Strait Quad-Regional Radio Sci. Wireless Technol. Conf.*, Jul. 2011, vol. 2, pp. 1032–1036.

[33] L. Wang, L. D. Xu, Z. Bi, and Y. Xu, "Data cleaning for RFID and WSN integration," *IEEE Trans. Ind. Inf.*, vol. 10, no. 1, pp. 408–418, Feb. 2014.

[34] H. Deng *et al.*, "Design of sensor-embedded radio frequency identification (SE-RFID) systems," in *Proc. IEEE Int. Conf. Mechatron. Autom.*, Jun. 2006, pp. 792–796.

[35] S. Mohamad, F. Tang, A. Amira, A. Bermak, and M. Benammar, "A low power oscillator based temperature sensor for RFID applications," in *Proc. 5th Asia Symp. Quality Electron. Design*, Aug. 2013, pp. 50–54.

[36] D. Hotte, R. Siragusa, Y. Duroc, and S. Tedjini, "Performance optimization for the choice of impedances in the design of passive RFID tags," in *Proc. IEEE-APS Top. Conf. Antennas Propag. Wireless Commun.*, Sep. 2013, pp. 1349–1352.

[37] M. Donelli, "Guidelines for the design and optimization of wireless sensors based on the modulated scattering technique," *IEEE Trans. Instrum. Meas.*, vol. 63, no. 7, pp. 1824–1833, Jul. 2014.

[38] A. Ricci, M. Grisanti, I. De Munari, and P. Ciampolini, "Improved pervasive sensing with RFID: An ultra-low power baseband processor for UHF tags," *IEEE Trans. Very Large Scale Integr. (VLSI) Syst.*, vol. 17, no. 12, pp. 1719–1729, Dec. 2009.

[39] L. Chen *et al.*, "Range extension of passive wake-up radio systems through energy harvesting," in *Proc. IEEE Int. Conf. Commun.*, Jun. 2013, pp. 1549–1554.

[40] S. Sauer, A. Turke, A. Weder, and W.-J. Fischer, "Inkjet printed humidity threshold monitoring sensor solution with irreversible resistance change for passive RFID applications," in *Proc. IEEE Sensors*, Nov. 2013, DOI: 10.1109/ICSENS.2013.6688307.

[41] N. Cho, S.-J. Song, S. Kim, S. Kim, and H.-J. Yoo, "A 5.1-uW UHF RFID tag chip integrated with sensors for wireless environmental monitoring," in *Proc. 31st Eur. Solid-State Circuits Conf.*, Sep. 2005, pp. 279–282.

[42] M. Philipose *et al.*, "Battery-free wireless identification and sensing," *IEEE Perv. Comput.*, vol. 4, no. 1, pp. 37–45, Jan. 2005.

[43] D. De Donno, L. Catarinucci, and L. Tarricone, "A battery-assisted sensor-enhanced RFID tag enabling heterogeneous wireless sensor networks," *IEEE Sensors J.*, vol. 14, no. 4, pp. 1048–1055, Apr. 2014.

[44] N. Guilar, T. Kleeburg, A. Chen, D. Yankelevich, and R. Amirtharajah, "Integrated solar energy harvesting and storage," *IEEE Trans. Very Large Scale Integr. (VLSI) Syst.*, vol. 17, no. 5, pp. 627–637, May 2009.

[45] D. Brunelli, C. Moser, L. Thiele, and L. Benini, "Design of a solar-harvesting circuit for batteryless embedded systems," *IEEE Trans. Circuits Syst. I, Reg. Papers*, vol. 56, no. 11, pp. 2519–2528, Nov. 2009.

[46] D. Kwon, G. Rincon-Mora, and E. Torres, "Harvesting ambient kinetic energy with switched-inductor converters," *IEEE Trans. Circuits Syst. I, Reg. Papers*, vol. 58, no. 7, pp. 1551–1560, Jul. 2011.

[47] S. Mehraeen, S. Jagannathan, and K. Corzine, "Energy harvesting from vibration with alternate scavenging circuitry and tapered cantilever beam," *IEEE Trans. Ind. Electron.*, vol. 57, no. 3, pp. 820–830, Mar. 2010.

[48] T. Le, K. Mayaram, and T. Fiez, "Efficient far-field radio frequency energy harvesting for passively powered sensor networks," *IEEE J. Solid-State Circuits*, vol. 43, no. 5, pp. 1287–1302, May 2008.

[49] G. Papotto, F. Carrara, and G. Palmisano, "A 90-nm CMOS threshold-compensated RF energy harvester," *IEEE J. Solid-State Circuits*, vol. 46, no. 9, pp. 1985–1997, Sep. 2011.

[50] S. Rahimizadeh, S. Korhummel, B. Kaslon, and Z. Popovic, "Scalable adaptive wireless powering of multiple electronic devices in an over-moded cavity," in *Proc. IEEE Wireless Power Transfer*, May 2013, pp. 84–87.

[51] S. Scorcioni, L. Larcher, A. Bertacchini, L. Vincetti, and M. Maini, "An integrated RF energy harvester for UHF wireless powering applications," in *Proc. IEEE Wireless Power Transfer*, May 2013, pp. 92–95.

[52] Z. Popovic, "Far-field wireless power delivery and power management for low-power sensors," in *Proc. IEEE Wireless Power Transfer*, May 2013, DOI: 10.1109/WPT.2013.6556867.

[53] E. Falkenstein, M. Roberg, and Z. Popovic, "Low-power wireless power delivery," *IEEE Trans. Microw. Theory Tech.*, vol. 60, no. 7, pp. 2277–2286, Jul. 2012.

[54] S. Roundy, P. K. Wright, and J. Rabaey, "A study of low level vibrations as a power source for wireless sensor nodes," *Comput. Commun.*, vol. 26, no. 11, pp. 1131–1144, 2003.

[55] C. D. Richards, M. J. Anderson, D. F. Bahr, and R. F. Richards, "Efficiency of energy conversion for devices containing a piezoelectric component," *J. Micromech. Microeng.*, vol. 14, no. 5, 2004, DOI: 10.1088/0960-1317/14/5/009.

[56] S. R. Anton and H. A. Sodano, "A review of power harvesting using piezoelectric materials (2003–2006)," *Smart Mater. Struct.*, vol. 16, no. 3, 2007, DOI: 10.1088/0964-1726/16/3/R01.

[57] Cymbet Corporation, "Energy harvesting and storage." [Online]. Available: http://www.cymbet.com/design-center/energy-harvesting.php#

[58] T. Armstrong, "Energy harvesting applications are everywhere," RTC, May 2011. [Online]. Available: http://www.rtcmagazine.com/articles/view/102133

[59] D. Puccinelli and M. Haenggi, "Wireless sensor networks: Applications and challenges of ubiquitous sensing," *IEEE Circuits Syst. Mag.*, vol. 5, no. 3, pp. 19–31, 2005.

[60] L. Roselli *et al.*, "WPT, RFID and energy harvesting: Concurrent technologies for the future networked society," in *Proc. Asia-Pacific Microw. Conf.*, Nov. 2013, pp. 462–464.

[61] H. Liu, M. Bolic, A. Nayak, and I. Stojmenovic, "Taxonomy and challenges of the integration of RFID and wireless sensor networks," *IEEE Network*, vol. 22, no. 6, pp. 26–35, Nov. 2008.

[62] D. Dardari, R. D'Errico, C. Roblin, A. Sibille, and M. Win, "Ultrawide bandwidth RFID: The next generation?" *Proc. IEEE*, vol. 98, no. 9, pp. 1570–1582, Sep. 2010.

[63] C. Balanis, *Antenna Theory: Analysis and Design*. New York, NY, USA: Wiley, 2005, ser. Knovel Library.

[64] K. Finkenzeller and D. Müller, *RFID Handbook: Fundamentals and Applications*

in Contactless Smart Cards, Radio Frequency Identification and Near-Field Communication. New York, NY, USA: Wiley, 2010.

[65] E. Perret, S. Tedjini, and R. Nair, "Design of antennas for UHF RFID tags," *Proc. IEEE*, vol. 100, no. 7, pp. 2330–2340, Jul. 2012.

[66] K. V. S. Rao, P. Nikitin, and S. Lam, "Antenna design for UHF RFID tags: A review and a practical application," *IEEE Trans. Antennas Propag.*, vol. 53, no. 12, pp. 3870–3876, Dec. 2005.

[67] H. Chaabane, E. Perret, and S. Tedjini, "A methodology for the design of frequency and environment robust UHF RFID tags," *IEEE Trans. Antennas Propag.*, vol. 59, no. 9, pp. 3436–3441, Sep. 2011.

[68] A. Babar, A. Elsherbeni, L. Sydanheimo, and L. Ukkonen, "RFID tags for challenging environments: Flexible high-dielectric materials and ink-jet printing technology for compact platform tolerant RFID tags," *IEEE Microw. Mag.*, vol. 14, no. 5, pp. 26–35, Jul. 2013.

[69] M. Scarpello, I. Kazani, C. Hertleer, H. Rogier, and D. Vande Ginste, "Stability and efficiency of screen-printed wearable and washable antennas," *IEEE Antennas Wireless Propag. Lett.*, vol. 11, pp. 838–841, 2012.

[70] V. Lakafosis *et al.*, "Progress towards the first wireless sensor networks consisting of inkjet-printed, paper-based RFID-enabled sensor tags," *Proc. IEEE*, vol. 98, no. 9, pp. 1601–1609, Sep. 2010.

[71] C. Mariotti, G. Orecchini, M. Virili, F. Alimenti, and L. Roselli, "Wireless localization in buildings by smart tiles," in *Proc. IEEE Workshop Environ. Energy Struct. Monitoring Syst.*, Sep. 2012, pp. 7–11.

[72] H. J. Song *et al.*, "A method for improving the efficiency of transparent film antennas," *IEEE Antennas Wireless Propag. Lett.*, vol. 7, pp. 753–756, 2008.

[73] F. Colombel *et al.*, "Ultra-thin metal layer, ITO film and ITO/Cu/ITO multilayer towards transparent antenna," *IET Sci. Meas. Technol.*, vol. 3, no. 3, pp. 229–234, May 2009.

[74] D. Zito and D. Pepe, "System-on-a-chip radio transceivers for 60-GHz wireless body-centric communications," in *Ultra-Wideband and 60 GHz Communications*. New York, NY, USA: Springer-Verlag, 2014, pp. 177–187.

[75] L. Martin *et al.*, "Effect of permittivity and permeability of a flexible magnetic composite material on the performance and miniaturization capability of planar antennas for RFID and wearable wireless applications," *IEEE Trans. Compon. Packag. Technol.*, vol. 32, no. 4, pp. 849–858, Dec. 2009.

[76] D. Kim and J. Yeo, "Low-profile RFID tag antenna using compact AMC substrate for metallic objects," *IEEE Antennas Wireless Propag. Lett.*, vol. 7, pp. 718–720, 2008.

[77] C. Kakoyiannis and P. Constantinou, "Compact WSN antennas of analytic geometry based on Chebyshev polynomials," in *Proc. Antennas Propag. Conf.*, Nov. 2012, DOI: 10.1109/LAPC.2012.6402976.

[78] H. Visser and R. Vullers, "RF energy harvesting and transport for wireless sensor network applications: Principles and requirements," *Proc. IEEE*, vol. 101, no. 6, pp. 1410–1423, Jun. 2013.

[79] M. Pinuela, P. Mitcheson, and S. Lucyszyn, "Ambient RF energy harvesting in urban and semi-urban environments," *IEEE Trans. Microw. Theory Tech.*, vol. 61, no. 7, pp. 2715–2726, Jul. 2013.

[80] K. M. Farinholt, G. Park, and C. Farrar, "RF energy transmission for a low-power wireless impedance sensor node," *IEEE Sensors J.*, vol. 9, no. 7, pp. 793–800, Jul. 2009.

[81] J. Hagerty, F. Helmbrecht, W. McCalpin, R. Zane, and Z. Popovic, "Recycling ambient microwave energy with broad-band rectenna arrays," *IEEE Trans. Microw. Theory Tech.*, vol. 52, no. 3, pp. 1014–1024, Mar. 2004.

[82] A. Collado and A. Georgiadis, "Conformal hybrid solar and electromagnetic (EM) energy harvesting rectenna," *IEEE Trans. Circuits Syst. I, Reg. Papers*, vol. 60, no. 8, pp. 2225–2234, Aug. 2013.

[83] T. Wu, R. Li, and M. Tentzeris, "A scalable solar antenna for autonomous integrated wireless sensor nodes," *IEEE Antennas Wireless Propag. Lett.*, vol. 10, pp. 510–513, 2011.

[84] A. Sample, J. Braun, A. Parks, and J. Smith, "Photovoltaic enhanced UHF RFID tag antennas for dual purpose energy harvesting," in *Proc. IEEE Int. Con. RFID*, Apr. 2011, pp. 146–153.

[85] F. Alimenti *et al.*, "A new contactless assembly method for paper substrate antennas and UHF RFID chips," *IEEE Trans. Microw. Theory Tech.*, vol. 59, no. 3, pp. 627–637, Mar. 2011.

[86] W. Pachler *et al.*, "A silver ink-jet printed UHF booster antenna on flexible substratum with magnetically coupled RFID die on-chip antenna," in *Proc. 7th Eur. Conf. Antennas Propag.*, Apr. 2013, pp. 1730–1733.

[87] M. Virili, H. Rogier, F. Alimenti, P. Mezzanotte, and L. Roselli, "Wearable textile antenna magnetically coupled to flexible active electronic circuits," *IEEE Antennas Wireless Propag. Lett.*, vol. 13, pp. 209–212, 2014.

[88] H.-J. Yoo, "Your heart on your sleeve: Advances in textile-based electronics are weaving computers right into the clothes we wear," *IEEE Solid-State Circuits Mag.*, vol. 5, no. 1, pp. 59–70, Mar. 2013.

[89] X. Jingtian *et al.*, "Low-cost low-power UHF RFID tag with on-chip antenna," *J. Semicond.*, vol. 30, no. 7, pp. 075012/1–075012/6, Jul. 2009.

[90] M. Law, A. Bermak, and H. Luong, "A sub-μW embedded CMOS temperature sensor for RFID food monitoring application," *IEEE J. Solid-State Circuits*, vol. 45, no. 6, pp. 1246–1255, Jun. 2010.

[91] Alien Technology Corporation, "Fluidic self assembly," White Paper, 1999. [Online]. Available: http://www.alientechnology.com

[92] C. Hertleer, H. Rogier, L. Vallozzi, and L. V. Langenhove, "A textile antenna for off-body communication integrated into protective clothing for firefighters," *IEEE Trans. Antennas Propag.*, vol. 57, no. 4, pp. 919–925, Apr. 2009.

[93] X. Li, J. Liao, Y. Yuan, and D. Yu, "Eye-shaped segmented reader antenna for near-field UHF RFID applications," *Progr. Electromagn. Res.*, vol. 114, pp. 481–493, 2011.

[94] J.-J. Tiang, M. Islam, N. Misran, and J. S. Mandeep, "Circular microstrip slot antenna for dual-frequency RFID application," *Progr. Electromagn. Res.*, vol. 120, pp. 499–512, 2011.

[95] Y. Amin, Q. Chen, H. Tenhunen, and L.-R. Zheng, "Performance-optimized quadrate bowtie RFID antennas for cost-effective and eco-friendly industrial applications," *Progr. Electromagn. Res.*, vol. 126, pp. 49–64, 2012.

[96] Y. Amin, Q. Chen, L.-R. Zheng, and H. Tenhunen, "Development and analysis of flexible UHF RFID antennas for "green" electronics," *Progr. Electromagn. Res.*, vol. 130, pp. 1–15, 2012.

[97] F. Viani, M. Salucci, G. Olivieri, F. Robol, and A. Massa, "Design of UHF RFID/GPS fractal antenna for logistic management," *J. Electromagn. Waves Appl.*, vol. 26, no. 4, pp. 480–492, 2012.

[98] A. Springer, R. Weigel, A. Pohl, and F. Seifert, "Wireless identification and sensing using surface acoustic wave devices," *Mechatronics*, vol. 9, no. 7, pp. 745–756, Oct. 1999.

[99] K. Chang, Y. Kim, Y. Kim, and Y. Yoon, "Functional antenna integrated with relative humidity sensor using synthetised polymide for passive RFID sensing," *Electron. Lett.*, vol. 43, no. 5, pp. 1918–1923, May 2007.

[100] S. Shrestha, M. Balachandran, M. Agarwal, V. Phoha, and K. Varahramyan, "A chipless RFID sensor system for cyber centric monitoring applications," *IEEE Trans. Microw. Theory Tech.*, vol. 57, no. 5, pp. 1303–1309, May 2009.

[101] C. Occhiuzzi, S. Cippitelli, and G. Marrocco, "Modeling, design and experimentation of wearable RFID sensor tag," *IEEE Trans. Antennas Propag.*, vol. 58, no. 8, pp. 2490–2498, Aug. 2010.

[102] A. Ramos, A. Lazaro, D. Girbau, and R. Villarino, "Time-domain measurement of time-coded UWB chipless RFID tags," *Progr. Electromagn. Res.*, vol. 116, pp. 313–331, 2011.

[103] R. Nair, E. Perret, and S. Tedjini, "Temporal multi-frequency encoding technique for chipless RFID applications," in *IEEE MTT-S Int. Microw. Symp. Dig.*, Montreal, QC, Canada, Jun. 2012, DOI: 10.1109/MWSYM.2012.6259483.

[104] R. Bhattacharyya, C. Floerkemeier, and S. Sarma, "Low-cost, ubiquitous RFID-tag-antenna-based sensing," *Proc. IEEE*, vol. 98, no. 9, pp. 1593–1600, Sep. 2010.

[105] R. Potyrailo *et al.*, "Development of radio-frequency identification sensors based on organic electronic sensing materials for selective detection of toxic vapors," *J. Appl. Phys.*, vol. 106, no. 12, pp. 124 902–124 902-6, Dec. 2009.

[106] V. Viikari and H. Seppa, "RFID MEMS sensor concept based on intermodulation distortion," *IEEE Sensor J.*, vol. 9, no. 12, pp. 1918–1923, Dec. 2009.

[107] J. Riley *et al.*, "Tracking bees with harmonic radar," *Nature*, vol. 379, pp. 29–30, Jan. 1996.

[108] S. Helbing *et al.*, "Design and verification of a novel crossed dipole structure for quasi-optical frequency doublers," *IEEE Microw. Guided Wave Lett.*, vol. 10, no. 3, pp. 105–107, Mar. 2000.

[109] F. Alimenti and L. Roselli, "Theory of zero-power RFID sensors based on harmonic generation and orthogonally polarized antennas," *Progr. Electromagn. Res.*, vol. 134, pp. 337–357, 2013.

[110] G. Lovei, I. Stringer, C. Devine, and M. Cartellieri, "Harmonic radar—A method using inexpensive tags to study invertebrate movement on land," *New Zealand J. Ecology*, vol. 21, no. 2, pp. 187–193, 1997.

[111] B. Colpitts and G. Boiteau, "Harmonic radar transceiver design: Miniature tags for insect tracking," *IEEE Trans. Antennas Propag.*, vol. 52, no. 11, pp. 2825–2832, Nov. 2004.

[112] G. Orecchini *et al.*, "Green technologies and RFID: Present and future," *Appl. Comput. Electromagn. Soc. J.*, vol. 25, no. 3, pp. 230–238, Mar. 2010.

[113] S. Steudel *et al.*, "Comparison of organic diode structures regarding high-frequency rectification behavior in radio-frequency identification tags," *J. Appl. Phy.*, vol. 99, no. 11, Jun. 2006, 114519.

[114] L. Valentini and J. Kenny, "Novel approaches to developing carbon nanotube based polymer composites: Fundamental studies and nanotech applications," *Polymer*, vol. 46, no. 17, pp. 6715–6718, Aug. 2005.

[115] V. Marinov *et al.*, "Direct-write vapor sensors on FR4 plastic substrates," *IEEE Sensor J.*, vol. 7, no. 6, pp. 937–944, Jun. 2007.

[116] T. Unander and H.-E. Nilsson, "Characterization of printed moisture sensors in packaging surveillance applications," *IEEE Sensor J.*, vol. 9, no. 8, pp. 922–928, Aug. 2009.

[117] S. Couderc, B. Kim, and T. Someya, "Cellulose-based composite as a raw material for flexible ANS ultra-lightweight mechanical switch devices," in *Proc. IEEE 22nd Int. Conf. Micro Electro Mech. Syst.*, Sorrento, Italy, Jan. 2009, pp. 646–649.

[118] P. F. Goldsmith, "Quasioptics in millimeterwave systems," in *Proc. 12th Eur. Microw. Conf.*, Sep. 1982, pp. 16–24.

[119] P. Goldsmith, "Quasi-optical techniques," *Proc. IEEE*, vol. 80, no. 11, pp. 1729–1747, Nov. 1992.

[120] P. F. Goldsmith, *Quasioptical Systems*. New York, NY, USA: IEEE Press, 1998.

[121] T. Djerafi, K. Wu, and S. Tatu, "3 dB 90° hybrid quasi-optical coupler with air field slab in SIW technology," *IEEE Microw. Wireless Compon. Lett.*, vol. 24, no. 4, pp. 221–223, Apr. 2014.

[122] A. Gonzalez, Y. Fujii, K. Kaneko, and Y. Uzawa, "Quasi-optical attenuators for alma band 10 receiver," in *Proc. Asia-Pacific Microw. Conf. Proc.*, Dec. 2011, pp. 1977–1980.

[123] K. Song, F. Zhang, S. Hu, and Y. Fan, "Millimeter-wave-wave quasi-optical low-loss power combiner based on dipole antenna," *Electron. Lett.*, vol. 49, no. 18, pp. 1160–1162, Aug. 2013.

[124] S. Kawasaki and T. Itoh, "Quasi-optical planar arrays with fets and slots," *IEEE Trans. Microw. Theory Tech.*, vol. 41, no. 10, pp. 1838–1844, Oct. 1993.

[125] S. Hollung, W. Shiroma, M. Markovic, and Z. Popovic, "A quasi-optical isolator," *IEEE Microw. Guided Wave Lett.*, vol. 6, no. 5, pp. 205–206, May 1996.

[126] N. Gagnon and J. Shaker, "Accurate phase measurement of passive non-reciprocal quasi-optical components," *IEE Proc.—Microw. Antennas Propag.*, vol. 152, no. 2, pp. 111–116, Apr. 2005.

[127] R. Dickie, R. Cahill, V. Fusco, H. Gamble, and N. Mitchell, "THz frequency selective surface filters for earth observation remote sensing instruments," *IEEE Trans. Terahertz Sci. Technol.*, vol. 1, no. 2, pp. 450–461, Nov. 2011.

[128] M. Euler and V. Fusco, "Quasi optical circulator X-band scale model utilizing a circular polarization frequency selective surface," in *Proc. 4th Eur. Conf. Antennas Propag.*, Apr. 2010, pp. 1–4.

[129] W. Shiroma, S. Bundy, S. Hollung, B. Bauernfeind, and Z. Popovic, "Cascaded active and passive quasi-optical grids," *IEEE Trans. Microw. Theory Tech.*, vol. 43, no. 12, pp. 2904–2909, Dec. 1995.

[130] J. Birkeland and T. Itoh, "A 16 element quasi-optical fet oscillator power combining array with external injection locking," *IEEE Trans. Microw. Theory Tech.*, vol. 40, no. 3, pp. 475–481, Mar. 1992.

[131] M. Forman, T. Marshall, and Z. Popovic, "Two Ka-band quasi-optical amplifier arrays," in *IEEE MTT-S Int. Microw. Symp. Dig.*, Jun. 1999, vol. 4, pp. 1829–1832.

[132] S. Hollung, A. Cox, and Z. Popovic, "A bi-directional quasi-optical lens amplifier," *IEEE Trans. Microw. Theory Tech.*, vol. 45, no. 12, pp. 2352–2357, Dec. 1997.

[133] J. Hacker, R. Weikle, M. Kim, P. De Lisio, and D. Rutledge, "A 100-element planar Schottky diode grid mixer," *IEEE Trans. Microw. Theory Tech.*, vol. 40, no. 3, pp. 557–562, Mar. 1992.

[134] G. Chattopadhyay, D. Miller, H. LeDuc, and J. Zmuidzinas, "A dual-polarized quasi-optical SIS mixer at 550 GHz," *IEEE Trans. Microw. Theory Tech.*, vol. 48, no. 10, pp. 1680–1686, Oct. 2000.

[135] V. Bezborodov, V. Kiseliov, Y. Kuleshov, and M. Yanovsky, "A terahertz quasi-optical polarization phase shifter with the crystal quartz phase sections," in *Proc. 5th Int. Kharkov Symp. Phys. Eng. Microw. Millimeter Submillimeter Waves*, Jun. 2004, vol. 2, pp. 603–605.

[136] G. Denisov *et al.*, "Fast quasi-optical phase shifter based on induced photoconductivity in silicon," in *Proc. Joint 32nd Int. Conf. Infrared Millimeter Waves/15th Int. Conf. Terahertz Electron.*, Sep. 2007, pp. 795–796.

[137] N. Camilleri, "A quasi-optical multiplying slot array," *IEEE Trans. Microw. Theory Tech.*, vol. 33, no. 11, pp. 1189–1195, Nov. 1985.

[138] A. Moussessian *et al.*, "A terahertz grid frequency doubler," *IEEE Trans. Microw. Theory Tech.*, vol. 46, no. 11, pp. 1976–1981, Nov. 1998.

[139] M. Cryan *et al.*, "Simulation and measurement of quasi-optical multipliers," *IEEE Trans. Microw. Theory Tech.*, vol. 49, no. 3, pp. 451–464, Mar. 2001.

[140] F. Jiang *et al.*, "High-speed monolithic millimeter-wave switch array," *IEEE Microw. Guided Wave Lett.*, vol. 8, no. 3, pp. 112–114, Mar. 1998.

[141] F. Alimenti *et al.*, "Crossed dipole frequency doubling RFID TAG based on paper substrate and ink-jet printing technology," in *Proc. IEEE MTT-S Int. Microw. Symp. Dig.*, May 2010, pp. 840–842.

[142] M. Virili *et al.*, "7.5–15 MHz organic frequency doubler made with pentacene-based diode and paper substrate," in *IEEE MTT-S Int. Microw. Symp. Dig.*, Tampa, FL, USA, Jun. 2014, DOI: 10.1109/MWSYM.2014.6848395.

[143] L. Roselli *et al.*, "Feasibility study of a fully organic frequency doubler for harmonic RFID applications," in *Proc. IEEE 12th Top. Meeting Silicon Monolithic Integr. Circuits RF Syst.*, Jan. 2012, pp. 203–206.

[144] R. Gonalves *et al.*, "Smart floor: Indoor navigation based on RFID," in *Proc. IEEE Wireless Power Transfer*, May 2013, pp. 103–106.

[145] G. Orecchini, L. Yang, M. Tentzeris, and L. Roselli, "Wearable battery-free active paper printed RFID tag with human-energy scavenger," in *IEEE MTT-S Int. Microw. Symp. Dig.*, Jun. 2011, DOI: 10.1109/MWSYM.2011.5973290.

[146] C.-R. Yu, C.-L. Wu, C.-H. Lu, and L.-C. Fu, "Human localization via multi-cameras and floor sensors in smart home," in *Proc. IEEE Int. Conf. Syst. Man Cybern.*, Oct. 2006, vol. 5, pp. 3822–3827.

[147] S. Chang, S. Ham, S. Kim, D. Suh, and H. Kim, "Ubi-floor: Design and pilot implementation of an interactive floor system," in *Proc. 2nd Int. Conf. Intell. Human-Mach. Syst. Cybern.*, Aug. 2010, vol. 2, pp. 290–293.

[148] J. Morgado and A. Konig, "Low-power concept and prototype of distributed resistive pressure sensor array for smart floor and surfaces in intelligent environments," in *Proc. 9th Int. Multi-Conf. Syst. Signals Devices*, Mar. 2012, DOI: 10.1109/SSD.2012.6198020.

[149] J. Zhao and Y. Wang, "Autonomous ultrasonic indoor tracking system," in *Proc. Int. Symp. Parallel Distrib. Process. Appl.*, Dec. 2008, pp. 532–539.

[150] R. Imura, "The role of networked RFID for driving the ubiquitous," in *Proc. IEEE Conf. Emerging Technol. Factory Autom.*, Sep. 2006, pp. 1115–1118.

[151] Y. Tan, K. Y. Hoe, and S. Panda, "Energy harvesting using piezoelectric igniter for self-powered radio frequency (RF) wireless sensors," in *Proc. IEEE Int. Conf. Ind. Technol.*, Dec. 2006, pp. 1711–1716.

[152] Linx Technologies, "KH2 series transmitter/encoder data guide." [Online]. Available: https://www.linxtechnologies.com/resources/data-guides/txe-xxx-kh2.pdf

[153] D. Smith, D. Miniutti, T. Lamahewa, and L. Hanlen, "Propagation models for body-area networks: A survey and new outlook," *IEEE Antennas Propag. Mag.*, vol. 55, no. 5, pp. 97–117, Oct. 2013.

[154] *IEEE Standard for Local and Metropolitan Area Networks—Part 15.6: Wireless Body Area Networks*, IEEE Std. 802.15.6-2012, Feb. 2012.

[155] J. Thomas and M. Qidwai, "The design and application of multifunctional structure-battery materials systems," *JOM*, vol. 57, no. 3, pp. 18–24, Mar. 2005.

[156] A. Bonfiglio and D. De Rossi, *Wearable Monitoring Systems*. New York, NY, USA: Springer-Verlag, 2011.

[157] S. Lee and B. Youn, "A design and experimental verification methodology for an energy harvester skin structure," *Smart Mater. Struct.*, vol. 20, no. 5, May 2011, DOI: 10.1088/0964-1726/20/5/057001.

[158] R. Vullers, R. van Schaijk, I. Doms, C. van Hoof, and R. Mertens, "Microwave energy harvesting," *Solid-State Electron.*, vol. 53, no. 4, pp. 684–693, Apr. 2009.

[159] P. Jaffe and J. McSpadden, "Energy conversion and transmission modules for space solar power," *Proc. IEEE*, vol. 101, no. 6, pp. 1424–1437, Jun. 2013.

[160] J. McSpadden and J. Mankins, "Space solar power programs and microwave wireless power transmission technology," *IEEE Microw. Mag.*, vol. 3, no. 4, pp. 46–57, Dec. 2002.

ABOUT THE AUTHORS

Luca Roselli (Senior Member, IEEE) was born in Florence, Italy, in 1962. He received the ''Laurea'' degree in electronic engineering from the University of Florence, Florence, Italy, in 1988.

From 1988 to 1991, he worked at the University of Florence on SAW devices. In November 1991, he joined the University of Perugia, Perugia, Italy, where he is currently working as an Associate Professor and where he has been teaching several classes on electronic devices, microwave electronics, high-frequency (HF) electronic components, and applied electronics. Since 2000, he has been coordinating research activity at the High Frequency Electronics (HFE) Laboratory. In that year, he also founded the spin-off company WiS (Wireless Solutions) Srl, operating in the field of microwave electronic systems with which he cooperated as a consultant until it joined the new company ART Srl. in 2008. From 2008 to 2012, he was the Director of the Technical and Scientific Committee of ART Srl and a member of the Board of Directors. In 2005, he founded a second spin-off company: DiES (Digital Electronic Solutions) Srl. His research interests mainly focus on the design of high-frequency electronic circuits and systems, including the development of numerical methods for electronic circuit analysis with special attention to RFID–NFC systems, new materials (including organic and recyclable ones), and far-field wireless power transfer. In these fields, he published more than 220 contributions in international reviews and peer-reviewed conferences, the interest in which is testified by an HF index of 20 (source Google Scholar) and more than 1350 citations.

Mr. Roselli was the Chairman of the VII Computational Electromagnetic in Time Domain Workshop in 2007. In 2013, he was the Chairman of the First IEEE Wireless Power Transfer Conference (WPTC). Currently, he is member of the list of experts of Italian Ministry of Research and University (MIUR); member of several IEEE Technical Committees [MTT-24 RFID Technologies (past chair), MTT-25 RF nanotechnolgies, MTT-26 Wireless Power Transfer]; member of the Sub Committee 32 RFID Technologies of International Microwave Symposium (IMS) (past chair); member of the European Research Council (ERC) Panel PE7; member of the Advisory Committee of IEEE WPTC. He is involved in the boards of several international conference (RWCOM, RFID-TA, EuCAP, MAREW). He is a reviewer for many international conferences and journals (the PROCEEDINGS OF THE IEEE, the IEEE TRANSACTIONS ON MICROWAVE THEORY AND TECHNIQUES, IEEE MICROWAVE AND WIRELESS COMPONENTS LETTERS, *ACES Journal*, *Radioengineering Journal*, Hindawi publishing corporation, *Elsevier Organic Electronics*, *ASP Nanoscience and Nanotechnology Letters*).

Nuno Borges Carvalho (Senior Member, IEEE) was born in Luanda, Angola, in 1972. He received the Diploma and Doctoral degrees in electronics and telecommunications engineering from the University of Aveiro, Aveiro, Portugal, in 1995 and 2000, respectively.

He is a Full Professor at the Universidade de Aveiro, Aveiro, Portugal and a Senior Research Scientist with the Instituto de Telecomunicações (IT), Universidade de Aveiro, where he coordinates the wireless communication thematic area and the Radio Systems Group. He coauthored *Intermodulation in Microwave and Wireless Circuits* (Reading, MA, USA: Artech House, 2003) and *Microwave and Wireless Measurement Techniques* (Cambridge, U.K.: Cambridge Univ. Press, 2013). He has been a reviewer and author of over 200 papers in magazines and conferences. He coholds four patents. His main research interests include software-defined radio front-ends, wireless power transmission, nonlinear distortion analysis in microwave/wireless circuits and systems, and measurement of nonlinear phenomena. He has recently been involved in the design of dedicated radios and systems for newly emerging wireless technologies.

Dr. Borges Carvalho is the Chair of the IEEE MTT-11 Technical Committee. He is a member of IEEE MTT-20, MTT-24, and MTT-26 and the IEEE Portugal Section Chair. He is an Associate Editor for the IEEE TRANSACTIONS ON MICROWAVE THEORY AND TECHNIQUES, IEEE MICROWAVE MAGAZINE, *Cambridge Journal on Wireless Power Transmission* and the Chair of the URSI-Portugal Metrology Group.

Federico Alimenti (Senior Member, IEEE) was born in Foligno, Italy, in 1968. He received the Laurea degree (*magna cum laude*) and the Ph.D. degree from the University of Perugia, Perugia, Italy, in 1993 and 1997 respectively, both in electronic engineering.

In 1993, he held an internship at Daimler-Benz Aerospace, Ulm, Germany. In 1996, he was recipient of the URSI young scientist award and visiting scientist at the Technical University of Munich, Munich, Germany. Since 2001, he has been with the Department of Engineering, University of Perugia, as an Aggregate Professor, teaching the class of microwave electronics. Between 2006 and 2010, he was a member of the Academic Senate in the same university. He authored more than 150 papers in refereed journals and conference proceedings. He coauthored several book chapters and a European patent (EP13161946.2) on zero-power wireless sensors. His scientific interests concern the design and the experimental characterization of radiofrequency (RF)-integrated circuits in complementary metal–oxide–semiconductor (CMOS) and BiCMOS technologies.

Prof. Alimenti was a recipient of the IET Premium (Best Paper) Award in 2013 and was the Technical Program Committee (TPC) Chair of the IEEE Wireless Power Transfer (WPT) Conference. He has been a local coordinator of the ARTEMOS project, ENIAC, call 3, 2010. His H-index is equal to 14 (source: Google Scholar).

Paolo Mezzanotte (Member, IEEE) was born in Perugia, Italy, in 1965. He received the Ph.D. degree in electrical engineering from the University of Perugia, Perugia, Italy, in 1997.

Since 1992, he has been involved with FDTD analysis of microwave structures in cooperation with the Department of Electronic and Information Engineering (DIEI), University of Perugia. In 1999, he was appointed Research Associate. Since January 2007, he has been an Associate Professor with the same university, teaching the classes on radio-frequency engineering. His research activities concern numerical methods and computer-aided design (CAD) techniques for passive microwave structures and the analysis and design of microwave and millimeter-wave circuits. More recently his research interests have mainly focused on the study of advanced technologies such as LTCC, RF-MEMS, and microwave circuits printed on green substrates. These research activities are testified by more than 100 publications in the most important specialized journals and at the main conferences of the microwave scientific community.

Prof. Mezzanotte serves as a Reviewer of a number of IEEE journals and belongs to the Top Amplifier Research Group in a European Team (TARGET) and to the Advanced MEMS for RF and Millimeterwave Communications (AMICOM) Networks of Excellence. He is a member of the IMS Technical Program Review Committee and of the Technical Committee MTT-24 RFID Technologies. He serves as an Associate Editor of the *ACES Journal*. He was the Co-Chairman of the Seventh International Workshop on Computational Electromagnetics in Time Domain (CEM-TD 2007). His present H-index (ISI journals) is equal to 13.

Giulia Orecchini received the Laurea degree in electronic engineering and the Ph.D. degree in electronic and information engineering from the University of Perugia, Perugia, Italy, in 2008 and 2012, respectively.

During her Ph.D. studies she joined the ATHENA Research Group, Georgia Institute of Technology, Atlanta, GA, USA. Her research interests concern the development of radio-frequency identification (RFID) electronic systems and technologies. She is currently working as a Research Assistant at the University of Perugia.

Marco Virili (Student Member, IEEE) was born in Terni, Italy, in 1983. He received the Laurea degree in electronic engineering from the University of Perugia, Perugia, Italy, in 2009, where he is currently working toward the Ph.D. degree at the Department of Engineering.

His scientific interests concern the design and the experimental validation of radio-frequency (RF) and microwave circuits. He has a strong experience in using the main electromagnetic computer-aided design (CAD) tools for characterization and design of microwave devices. He is focused on chipless radio-frequency identification (RFID) tags and green electronics.

Chiara Mariotti (Student Member, IEEE) was born in Assisi, Italy, in 1987. She received the Laurea degree (*magna cum laude*) in electronic and telecommunication engineering from the University of Perugia, Perugia, Italy, in 2011, where she is currently working toward the Ph.D. degree at the High Frequency Electronics (HFE) Laboratory, working on green technologies for passive and energetically autonomous radio-frequency identification (RFID) tags.

In Spring 2012, she joined the ATHENA Research Group, Georgia Institute of Technology, Atlanta, GA, USA, for six months, working on eco-compatible indoor localization systems and other types of sensors fabricated by means of inkjet printing technology. At the end of 2013, she again joined the ATHENA Research Group for six months to work on multilayer inkjet printed systems and devices such as passives and microfluidics sensors.

Ricardo Gonçalves (Student Member, IEEE) was born in Lisbon, Portugal, in 1988. He received the B.Sc. and M.Sc. (*magna cum laude*) degrees in electronics and telecommunications engineering from the Instituto Superior de Engenharia de Lisboa, Lisbon, Portugal, in 2010 and 2012, respectively. He is currently working toward the Ph.D. degree in electrical engineering at the University of Aveiro, Aveiro, Portugal.

He is a Researcher at the Instituto de Telecomunicações, Aveiro, Portugal. In 2011, he was awarded with merit scholarship for exceptional academic performances. From 2010 to 2012, he worked at Dailywork I&D as a Developer Engineer in Embedded Electronic Systems for Vehicular Location Systems and Healthcare Platforms. His main research interests include wireless power transfer systems, radio-frequency identification (RFID), and wireless passive sensor networks. His current focus is on the development of printed antennas and microwave circuits in nonconventional materials such as textiles, ceramics, plastic, paper, and cork, for the former applications.

Pedro Pinho (Member, IEEE) was born in Vale de Cambra, Portugal, in 1974. He received the Licenciado and M.S. degrees in electrical and telecommunications engineering and the Ph.D. degree in electrical engineering from the University of Aveiro, Aveiro, Portugal, in 1995 and 2000, respectively. from the University of Aveiro, Aveiro, Portugal, in 1997, 2000, and 2004, respectively.

He is currently a Professor Adjunto at the Department of Electrical Telecommunications and Computers Engineering, Instituto Superior de Engenharia de Lisboa, Instituto Politécnico de Lisboa, Lisbon, Portugal, and a Member of the Research Staff at the Institute for Telecommunications, Aveiro, Portugal (since 1997). He authored or coauthored more than 90 papers in conferences and international journals and four book chapters. His current research interest is in antennas for location systems, reconfigurable antennas, and antenna design for passive sensors in nonconventional materials.

View publication stats

COUPONS AVAILABLE

ACTIVATE COUPONS

advertisement

RFID READER DETECTOR AND TILT-SENSITIVE RFID TAG

Technology (/technology/) > Science | by nmarquardt (/member/nmarquardt/) Follow

286,565 531 157

Posted Nov. 10, 2008 | BY-NC-SA



(https://cdn.instructables.com/FCIYZG9/FN4A5KYE/FCIYZG9FN4A5KYE.LARGE.jpg)


(https://cdn.instructables.com/FEK/Z70Z

(https://cdn.instructables.com/FW3/IS


(https://cdn.instructables.com/FES/2U57

The 'rub' (http://www.usingenglish.com/reference/idioms/there%27s+the+rub.html)
Want to detect the presence of RFID readers? Want to control when a RFID tag is active or readable? We describe how to do both using bits of copper and card, and some readily available electronics hardware.

Longer preamble
Radio frequency identification (RFID (http://en.wikipedia.org/wiki/RFID)) is rapidly growing in popularity. RFID *tags* are found everywhere. They're attached to container freight, in those funny-looking white labels you find in newly purchased books, embedded in many corporate ID cards and passports, etc. The tags have a few common properties: they transmit a unique ID number, are optimized to be 'read' from predefined distances, and are usually small so they can remain unobtrusive or hidden.

RFID *readers* are used to track nearby tags by wirelessly reading a tag's unique ID (see Figure 4); a tag simply has to be brought into physical proximity with a reader to be read. Readers are mostly used for industrial or commercial purposes, e.g. asset tracking or electronic payment. Wal-mart use RFID tags and readers in their supply chain. The technology is also used in mass transit systems in cities like London (http://en.wikipedia.org/wiki/Oyster_card) and Hong Kong (http://en.wikipedia.org/wiki/Octopus_card). In Japan, many mobile phones incorporate readers to enable e-money payments in shops and vending machines.

For those of us who want to experiment with RFID, the problem is that the technology is almost always black boxed (http://en.wikipedia.org/wiki/Black_box).

That is, the inner workings of a tag and its interaction with a reader is hidden from view, and thus difficult to have much control over.

In the two exercises that follow (building a RFID reader detector (https://www.instructables.com/id/SX28QZ1FN4H8QCG/) and a tilt-sensitive RFID tag (https://www.instructables.com/id/SGW3J0SFN49WUIF/)), we offer an example of how you can start revealing some of the workings of RFID and thus gain some control over the technology. The two exercises also hopefully show that the technology is relatively simple and how it can be extended to support some interesting interactions. We offer some other possibilities that build on our examples at the end (https://www.instructables.com/id/SQKIRD4FN49ZUS1/).

Add Tip Ask Question

Step 1: Material and Tools



(https://cdn.instructables.com/FXN/HM6C/FN49ZU3V/FXNHM6CFN49ZU3V.LARGE.jpg)

(https://cdn.instructables.com/FIM/0KGJ/FN49ZU3U/FIM0KGJF

Weller®
WES50
Output For PES50
Iron Only. Use Only
Original Weller Tips.
°Fx10
ESD SAFE
Weller

(https://cdn.instructables.com/F5G/GNJD/FN49ZU3T/F


(https://cdn.instructables.com/FZ0/19EB/FN4H8O9O/FZ


(https://cdn.instructables.com/FJM/DL93/FN4H8OZI/FJMDL93

This section provides an overview of the necessary materials and tools.

Materials (see Figure 1):
We need the following material to built the basic RFID reader detector.
- Cardboard (around 100x70 mm)
- Conductive copper tape (e.g., order number 1218478 at www.farnell.com)
- Capacitor 82 pF (picofarad) (e.g., order number 1138852 at www.farnell.com)
- Low current LED (light-emitting diode) (e.g., order number 1003207at www.farnell.com)

Tools (see Figure 2 and 3):
- Craft knife and scissors
- Insulating tape (e.g., order number 1373979 at www.farnell.com)
- Soldering iron and solder

RFID reader for testing (see Figure 4):
To test our RFID tags we need an RFID reader that can operate at a frequency of 13.56 MHz.
There many readers for this widely used RFID standard, for instance the Sonmicro MIFARE USB reader (http://www.sonmicro.com/).
Note: The Phidget RFID reader does *not* work with the tags created in this project, as it uses a different frequency for communication with the tags (125 kHz).

Advanced material (see Figure 5):

The following material is necessary to build the second part of the project: the tilt-sensitive RFID tag.

- Micro tilt switches (e.g., www.digikey.com)
- RFID ICs (e.g., MIFARE Standard 1k, part no. 568-2219-1-ND at www.digikey.com)

Add Tip Ask Question

Step 2: Building the RFID Antenna



(https://cdn.instructables.com/FGI/0OXD/FN4A5N20/FGI0OXDFN4A5N20.LARGE.jpg)





This step describes how to build the antenna for the RFID tag.

Building the RFID tag antenna

To build the tag's antenna follow these three steps.

1. Cut the conductive copper tape into thin stripes of around 2mm (see Figure 1).
2. Tape these stripes (see Figure 2) in loops around one half of the cardboard (see Figure 3 for the layout of the antenna). The tag should have between 3-4 loops for the antenna.
3. Solder all the connections between the copper tape. Sometimes, this isn't necessary as the tape's adhesive backing is conductive, but solder the connections if you want to be on the safe side.

Now we have created our RFID tag antenna, and we will add the "RFID reader detection" functionality in the following step.

A little background

RFID readers transmit an electromagnetic (EM) field with their reader antenna. This EM field induces a current in the antenna for all RFID tags within reading distance. This induced current activates the RFID chip that is connected to the tag's antenna. This chip then modulates a response (usually the unique ID number) that is transmitted back to the reader. The antenna of an RFID tag is usually a thin copper wire that is arranged in loops. The loops allow the emitted EM field of the RFID reader to induce current to the antenna of the tag.

Add Tip Ask Question

Step 3: RFID Reader Detection



(https://cdn.instructables.com/FMB/3FIZ/FN49ZUSR/FMB3FIZFN49ZUSR.LARGE.jpg)



(https://cdn.instructables.com/FK5/TPEF/FN49ZUT



(https://cdn.instructables.com/FGZ/MG1X/FN49ZUSQ/FGZMG1XFN


(https://cdn.instructables.com/FWJ/K0ER/FN49ZHSO/FWJ


(https://cdn.instructables.com/F33/GPGW/FN49ZHSN/F33

This step describes how to add a simple mechanism to the RFID tag antenna that allows us detect nearby RFID readers.

Antenna connection

First, we add a small piece of insulation tape for the connection of the inner end of the antenna loop (as illustrated in Figure 1). This is to insulate the outer loops. Then we add another copper tape strip to the inner end of the antenna as shown in Figure 2. Here again we solder the two ends of the conductive copper tape together.

Capacitor and LED

Next, we add the capacitor (82 pF) and the low current LED to the tag as shown in Figure 3. They are connected in parallel. We also solder these two components to the copper tape (see Figure 4).

Testing

With these simple steps, our RFID reader detector is finished! By bringing our DIY RFID detector close to an RFID reader (as shown in Figure 5), the connected LED lights up. With the Sonmicro reader hardware the distance to the reader has to be below 8-10 cm; however, there are RFID readers available with a stronger EM field and therefore a higher maximum reading distance.

In the next step of the instructable we will show how to extend a basic RFID tag and make it tilt-sensitive.

Add Tip Ask Question

Step 4: Tilt-Sensitive RFID Tag



(https://cdn.instructables.com/FAJ/YZBT/FN49ZUZH/FAJYZBTFN49ZUZH.LARGE.jpg)



(https://cdn.instructables.com/F2U/JOGX/FN49ZUZG/F2U



(https://cdn.instructables.com/FDH/W75V/FN49ZUZI/FDHW



(https://cdn.instructables.com/FU2/8LT7



(https://cdn.instructables.com/F0Q/HOS



(https://cdn.instructables.com/FIV/D9IN



(https://cdn.instructables.com/F3Y/WCFU/FN49ZV73/F3YWCFUFN49ZV73.LARGE.jpg)

We now describe the process of how to build a tilt-sensitive RFID tag. This extends the previous exercise.

Antenna

The antenna for this second RFID tag is similar to the first antenna we built. We thus need another piece of cardboard and to repeat the steps described earlier in STEP 2 (https://www.instructables.com/id/S2YO8NWFN4H8Q8A/) of this instructable.

Tilt-sensitive tag

Next, we add additional copper tape connections to the tag, as shown in Figure 1. These connections allow us to connect three tilt switches, a capacitor, and the LED to the antenna. Again, all the connections of the copper tape are soldered together. We add the three tilt switches to the tag as shown in Figure 3. The tilt switches are soldered to the copper tape, and it is important to connect them in a slight angle (around 5-10 degrees) as shown in Figure 4. This makes sure that the silt switches are in a *closed* state while the RFID tag is in a horizontal position, and in a *open* state while the tag is in a vertical position.

Again, we also add an LED and a capacitor to the antenna as shown in Figure 3 (we use a different form factor of the capacitor here just to illustrate the alternative options).

Testing the tilt-sensitive tag

We can now use our Sonmicro RFID reader again to test our new tilt-sensitive RFID tag. The tag is activate while in a horizontal position as in Figure 5, and is inactive when in a vertical position as in Figure 6.

Using RFID chips

We can now replace the connected capacitor and LED from our tag with an RFID

MICROWAVE AND RADIO FREQUENCY ENGINEERING

INDEX

admittance ... 4
AM ... 20
Ampere's law ... 8
a_n parameter ... 15
anisotropic ... 21
attenuation constant ... 6
$\mathscr{B}$ magnetic flux density ... 8
B susceptance ... 4
beta ... 2
b_n parameter ... 15
capacitance ... 4
carrier ... 7
CDMA ... 20
cellular ... 20
characteristic admittance ... 3
characteristic impedance . 2, 3
circulator ... 16
communications frequencies ... 20
complex permittivity ... 12, 21
complex propagation constant ... 6, 10
conductivity ... 12
conductor loss factor ... 13
copper cladding ... 13
cosmic rays ... 20
coupling factor ... 16
$\mathscr{D}$ electric flux density ... 8
dB ... 16
dBm ... 18
del ... 18
dielectric ... 21
dielectric constant ... 12
dielectric loss factor ... 13
dielectric relaxation frequency ... 8
directional coupler ... 16
directivity ... 16
div ... 18
divergence ... 18
$\mathscr{E}$ electric field ... 8
effective permittivity ... 13
EHF ... 20
electric conductivity ... 12
electric permittivity ... 12
electromagnetic spectrum .. 20
ELF ... 20
empirical ... 21
envelope ... 7
evanescent ... 17, 21
excitation port ... 14, 16
Faraday's law ... 8
Fourier series ... 3
frequency domain ... 8
frequency spectrum ... 20
gamma rays ... 20
Gauss' law ... 8
general math ... 18
glossary ... 21
grad operator ... 18
gradient ... 18
graphing ... 19
group velocity ... 7
GSM ... 20
$\mathscr{H}$ magnetic field ... 8
HF ... 20
high frequency ... 9
high frequency resistance .. 11
hybrid ring ... 15
hyperbolic functions ... 19
impedance ... 6
    intrinsic ... 10
    waves ... 10
incident wave amplitude ... 15
internally matched ... 14
intrinsic impedance ... 10
isotropic ... 21
j 18
$\mathscr{J}$ current density ... 8
k wave number ... 10
k of a dielectric ... 12
lambda ... 6
Laplacian ... 19
LF ... 20
light ... 20
linear ... 21
loss tangent ... 9
    complex ... 12
lossless network ... 15
low frequency ... 8
magnetic permeability ... 11
Maxwell's equations ... 8
MF ... 20
microstrip conductors ... 13
mode number ... 17
modulated wave ... 7
nabla operator ... 18
network theory ... 14
normalize ... 4
observation port ... 14, 16
omega-beta graph ... 7
overdamped ... 21
parallel plate capacitance ... 4
PCS ... 20
permeability ... 11
permittivity ... 12
    complex ... 12
    effective ... 13
    relative ... 12
phase constant ... 2, 6, 8, 10
phase velocity ... 2, 10
phasor notation ... 18
plane waves ... 10
polar notation ... 18
power ... 12, 18
    network ... 15
propagation constant
    complex ... 6, 10
quarter-wave section ... 6
quasi-static ... 9
radar ... 20
rat race ... 15
reciprocity ... 15
reflected wave amplitude .. 15
reflection coefficient ... 3, 10
relative permittivity ... 12
resistance
    high frequency ... 11
resistivity ... 12
scattering matrix ... 14, 16
scattering parameter ... 14, 15, 16
self-matched ... 14
separation of variables ... 17
series stub ... 5
sheet resistance ... 11
SHF ... 20
shunt stub ... 5
signs ... 2
S_{ij} scattering parameter ... 14
single-stub tuning ... 5
skin depth ... 7
SLF ... 20
Smith chart ... 4, 5
space derivative ... 18
spectrum ... 20
square root of j ... 18
stripline conductor ... 13
stub length ... 5
susceptance ... 4
tan δ ... 9
Taylor series ... 19
TE waves ... 17
telegrapher's equations ... 2
TEM assumptions ... 9
TEM waves ... 9
thermal speed ... 12
time domain ... 8
time of flight ... 3
time variable ... 21
time-harmonic ... 8
TM waves ... 17
transmission coefficient ... 3
transmission lines ... 2
transverse ... 21
transverse electromagnetic waves ... 9
transverse plane ... 17
TV ... 20
UHF ... 20
ULF ... 20
ultraviolet ... 20
underdamped ... 21
uniform plane waves ... 9
unitary matrix ... 15
vector differential equation 18
velocity of propagation . 2, 10
v_g group velocity ... 7
VHF ... 20
VLF ... 20
v_p velocity of propagation .. 2
wave analogies ... 10
wave equation ... 2, 17
wave impedance ... 10
wave input impedance ... 11
wave number ... 10, 21
wavelength ... 6
Wheeler's equation ... 14
X-ray ... 20
Y admittance ... 4
y_0 characteristic admittance 3
Z_0 characteristic impedance 3
α attenuation constant ... 6
α_c conductor loss factor ... 13
α_d dielectric loss factor ... 13
β phase constant ... 6
δ loss tangent ... 9
δ skin depth ... 7
ε permittivity ... 12
ε_c complex permittivity ... 12
ε_r relative permittivity ... 12
γ complex propagation constant ... 6
η intrinsic wave impedance ... 10
λ wavelength ... 6
$\lambda/4$ ... 6
μ permeability ... 11
ρ reflection coefficient ... 3
ρ_v volume charge density ... 8
σ conductivity ... 12
τ transmission coefficient ... 3
∇ del ... 18
∇ divergence ... 18
∇ gradient ... 18
∇^2 Laplacian ... 19
∇^2 Laplacian ... 17

TRANSMISSION LINES

TELEGRAPHER'S EQUATIONS

$$(1)\quad \frac{\partial V}{\partial z} = -L\frac{\partial I}{\partial t} \qquad (2)\quad \frac{\partial I}{\partial z} = -C\frac{\partial V}{\partial t}$$

By taking the partial derivative with respect to *z* of equation 1 and partial with respect to *t* of equation 2, we can get:

$$(\mathrm{i})\quad \frac{\partial^2 V}{\partial z^2} = LC\frac{\partial^2 V}{\partial t^2} \qquad (\mathrm{ii})\quad \frac{\partial^2 I}{\partial z^2} = LC\frac{\partial^2 I}{\partial t^2}$$

SOLVING THE EQUATIONS

To solve the equations (i) and (ii) above, we guess that $F(u) = F(z \pm vt)$ is a solution to the equations. It is found that the unknown constant v is the wave propagation velocity.

$$\boxed{V_{total} = V_+(z - vt) + V_-(v + vt)}$$ where:

z is the position along the transmission line, where the load is at z=0 and the source is at z=-l, with l the length of the line.

v is the **velocity of propagation** $1/\sqrt{LC}$ or ω/β, the speed at which the waveform moves down the line; see p 2

t is time

THE COMPLEX WAVE EQUATION

The general solutions of equations (i) and (ii) above yield the complex wave equations for voltage and current. These are applicable when the excitation is sinusoidal and the circuit is under steady state conditions.

$$\boxed{V(z) = V^+e^{-j\beta z} + V^-e^{+j\beta z}}$$

$$\boxed{I(z) = I^+e^{-j\beta z} + I^-e^{+j\beta z}}$$

$$\boxed{I(z) = \frac{V^+e^{-j\beta z} + V^-e^{+j\beta z}}{Z_0}}$$ where:

$e^{-j\beta z}$ and $e^{+j\beta z}$ represent wave propagation in the $+z$ and $-z$ directions respectively,

$\beta = \omega\sqrt{LC} = \omega/v$ is the **phase constant,**

$Z_0 = \sqrt{L/C}$ is the **characteristic impedance** of the line. These equations represent the voltage and current **phasors**.

+/- WATCHING SIGNS

By convention z is the variable used to describe position along a transmission line with the origin z=0 set at the load so that all other points along the line are described by **negative** position values.



Ohm's law for right- and left-traveling disturbances:

$$V_+ = I_+Z_0 \qquad V_- = -I_-Z_0$$

v_p VELOCITY OF PROPAGATION [cm/s]

The velocity of propagation is the speed at which a wave moves down a transmission line. The velocity approaches the speed of light but may not exceed the speed of light since this is the maximum speed at which information can be transmitted. But v_p may exceed the speed of light mathematically in some calculations.

$$\boxed{v_p = \frac{1}{\sqrt{LC}} = \frac{1}{\sqrt{\varepsilon\mu}} = \frac{\omega}{\beta}}$$ where:

L = inductance per unit length [H/cm]
C = capacitance per unit length [F/cm]
ε = permittivity of the material [F/cm]
μ = permeability of the material [H/cm]
ω = frequency [radians/second]
β = phase constant

Phase Velocity The velocity of propagation of a TEM wave may also be referred to as the *phase velocity*. The phase velocity of a TEM wave in conducting material may be described by:

$$\boxed{v_p = \omega\delta = \frac{\omega}{k} = c\frac{2\pi\delta}{\lambda_0} = c\frac{1}{\sqrt{\varepsilon_{r\ \mathrm{eff}}}}}$$ where:

δ = skin depth [m]
c = speed of light 2.998×10^8 m/s
λ_0 = wavelength in the material [m]

Z_0 CHARACTERISTIC IMPEDANCE [Ω]

The **characteristic impedance** is the resistance initially *seen* when a signal is applied to the line. It is a physical characteristic resulting from the materials and geometry of the line.

Lossless line: $$\boxed{Z_0 \equiv \sqrt{\frac{L}{C}}} = \frac{V_+}{I_+} = -\frac{V_-}{I_-}$$

Lossy line: $$\boxed{Z_0 \equiv \sqrt{\frac{R + j\omega L}{G + j\omega C}} = |Z_0| e^{j\phi_z}}$$

L = inductance per unit length [H/cm]
C = capacitance per unit length [F/cm]
V_+ = the forward-traveling (left to right) voltage [V]
I_+ = the forward-traveling (left to right) current [I]
V_- = the reverse-traveling (right to left) voltage [V]
I_- = the reverse-traveling (right to left) current [I]
R = the line resistance per unit length [Ω/cm]
G = the conductance per unit length [Ω^{-1}/cm]
ϕ = phase angle of the complex impedance [radians]

y_0 CHARACTERISTIC ADMITTANCE [Ω^{-1}]

The **characteristic admittance** is the reciprocal of the characteristic impedance.

$$\boxed{y_0 \equiv \sqrt{\frac{C}{L}}} = \frac{I_+}{V_+} = -\frac{I_-}{V_-}$$

r REFLECTION COEFFICIENT

The **reflection coefficient** is the ratio of reflected voltage to the forward-traveling voltage, a value ranging from –1 to +1 which, when multiplied by the wave voltage, determines the amount of voltage reflected at one end of the transmission line.

$$\boxed{\rho \equiv \frac{V_-}{V_+} = -\frac{I_-}{I_+}}$$

A reflection coefficient is present at each end of the transmission line:

$$\boxed{\rho_{\text{source}} = \frac{R_S - z_0}{R_S + z_0}} \qquad \boxed{\rho_{\text{load}} = \frac{R_L - z_0}{R_L + z_0}}$$

t TRANSMISSION COEFFICIENT

The **transmission coefficient** is the ratio of total voltage to the forward-traveling voltage, a value ranging from 0 to 2.

$$\boxed{\tau \equiv \frac{V_{total}}{V_+}} = 1 + \rho$$

TOF TIME OF FLIGHT [s]

The **time of flight** is how long it takes a signal to travel the length of the transmission line

$$\boxed{TOF \equiv \frac{l}{v}} = l\sqrt{LC} = \sqrt{L_{TOT} C_{TOT}}$$

l = length of the transmission line [cm]
v = the velocity of propagation $1/\sqrt{LC}$, the speed at which the waveform moves down the line
L = inductance per unit length [H/cm]
C = capacitance per unit length [F/cm]
L_{TOT} = total inductance [H]
C_{TOT} = total capacitance [F]

DERIVED EQUATIONS

$$V_+ = z_0 I_+ = \left(V_{TOT} + I_{TOT} z_0\right)/2$$
$$V_- = -z_0 I_- = \left(V_{TOT} - I_{TOT} z_0\right)/2$$
$$I_+ = y_0 V_+ = \left(I_{TOT} + V_{TOT} y_0\right)/2$$
$$I_- = -y_0 V_- = \left(I_{TOT} - V_{TOT} y_0\right)/2$$

C_n FOURIER SERIES

The function $x(t)$ must be periodic in order to employ the Fourier series. The following is the exponential Fourier series, which involves simpler calculations than other forms but is not as easy to visualize as the trigonometric forms.

$$\boxed{C_n = \frac{1}{T}\int_{t_1}^{t_1+T} x(t)\, e^{-jn\omega_0 t}\, dt}$$

C_n = amplitude
T = period [s]
t = time [s]
n = the harmonic (an integer)
w_0 = frequency $2\pi/T$ [radians]

The function $x(t)$ may be delayed in time. All this does in a Fourier series is to shift the phase. If you know the C_ns for $x(t)$, then the C_ns for $x(t-\alpha)$ are just $C_n e^{-jn\omega 0\alpha}$. (Here, C_ns is just the plural of C_n.)

C CAPACITANCE [F]

$$v(t) = \frac{1}{C}\int_0^t i\,d\tau + v(0) \qquad I_{cap} = C\frac{dV_{cap}}{dt}$$

$$\boxed{v(t) = v_f + (v_0 - v_f)e^{-t/t}} \qquad i(t) = i_f + (i_0 - i_f)e^{-t/t}$$

$$P(t) = i_0{}^2 R e^{-2t/\tau}$$

$v(t)$ = voltage across the capacitor, at time t [V]
v_f = final voltage across the capacitor, steady-state voltage [V]
v_0 = initial voltage across the capacitor [V]
t = time [s]
τ = the time constant, RC [seconds]
C = capacitance [F]
Natural log: $\ln x = b \Leftrightarrow e^b = x$

C PARALLEL PLATE CAPACITANCE

$$C = \frac{\varepsilon A}{h} \qquad C_{\text{per unit length}} = \frac{\varepsilon A}{lh} = \frac{\varepsilon wl}{lh} = \frac{\varepsilon w}{h}$$

ε = permittivity of the material [F/cm]
A = area of one of the capacitor plates [cm^2]
h = plate separation [cm]
w = plate width [cm]
l = plate length [cm]
C = capacitance [F]

CAPACITOR-TERMINATED LINE



Where the incident voltage is $V_+ = V_0\left(1 - e^{-t/\tau_0}\right)$,

$$V_{cap} = V_+ + V_- = V_0\left(2 + \frac{2\tau_1}{\tau_0 - \tau_1}e^{-t/\tau_1} - \frac{2\tau_0}{\tau_0 - \tau_1}e^{-t/\tau_0}\right)$$

V_0 = final voltage across the capacitor [V]
t = time [s]
τ_0 = time constant of the incident wave, RC [s]
τ_1 = time constant effect due to the load, Z_0C_L [s]
C = capacitance [F]

SMITH CHART

First **normalize the load impedance** by dividing by the characteristic impedance, and find this point on the chart.

When working in terms of **reactance** X, an inductive load will be located on the top half of the chart, a capacitive load on the bottom half. It's the other way around when working in terms of **susceptance** B [Siemens].

Draw a straight line from the center of the chart through the normalized load impedance point to the edge of the chart.

Anchor a compass at the center of the chart and draw a circle through the normalized load impedance point. Points along this circle represent the normalized impedance at various points along the transmission line. Clockwise movement along the circle represents movement from the load toward the source with one full revolution representing 1/2 wavelength as marked on the outer circle. The two points where the circle intersects the horizontal axis are the voltage maxima (right) and the voltage minima (left).

The point opposite the impedance (180° around the circle) is the **admittance** Y [Siemens]. The reason admittance (or susceptibility) is useful is because admittances in parallel are simply added. (**Admittance** is the reciprocal of impedance; **susceptance** is the reciprocal of reactance.)

$$\boxed{\Gamma(z) = \Gamma_L e^{j2\beta z}}$$

$$e^{j2\beta z} = 1\angle 2\beta z$$

$$\mathbf{G}(z) = \frac{\mathbf{Z}(z) - 1}{\mathbf{Z}(z) + 1}$$

$$\mathbf{Z}_L = \frac{\Gamma_L - 1}{\Gamma_L + 1} \qquad \boxed{\mathbf{Z} = \frac{Z_L}{Z_0}}$$

z = distance from load [m]
$j = \sqrt{-1}$
ρ = magnitude of the reflection coefficient
β = phase constant
Γ = reflection coefficient
Z = normalized impedance [Ω]

SINGLE-STUB TUNING

The basic idea is to connect a line stub in parallel (shunt) or series a distance *d* from the load so that the imaginary part of the load impedance will be canceled.

Shunt-stub: Select *d* so that the admittance *Y* looking toward the load from a distance *d* is of the form $Y_0 + jB$. Then the stub susceptance is chosen as $-jB$, resulting in a matched condition.


d
Y_0
Y_0
Y_L
Open
or
short
Y_0
l

Series-stub: Select *d* so that the admittance *Z* looking toward the load from a distance *d* is of the form $Z_0 + jX$. Then the stub susceptance is chosen as $-jX$, resulting in a matched condition.


d
Z_0
Z_0
Z_L
Z_0
l
Open
or
short

FINDING A STUB LENGTH

Example: Find the lengths of open and shorted shunt stubs to match an admittance of 1-j0.5. The admittance of an open shunt (zero length) is $Y=0$; this point is located at the left end of the Smith Chart *x*-axis. We proceed clockwise around the Smith chart, i.e. away from the end of the stub, to the +j0.5 arc (the value needed to match –j0.5). The difference in the starting point and the end point on the wavelength scale is the length of the stub in wavelengths. The length of a shorted-type stub is found in the same manner but with the starting point at $Y=\infty$.


Open stub of length .074 λ matches an admittance of 1-j.5
j.5
Toward generator
.074λ
Admittance (short) Y = ∞
Admittance (open) Y = 0
.324λ
Shorted stub of length .324 λ matches an admittance of 1-j.5
0 .01 .02 .03 .04 .05 .06 .07 .08 .09 .1 .11 .12 .13 .14 .15 .16 .17 .18 .19 .2 .21 .22 .23 .24 .25 .26 .27 .28 .29 .3 .31 .32 .33 .34 .35 .36 .37 .38 .39 .4 .41 .42 .43 .44 .45 .46 .47 .48 .49
0.1 0.5 1.0 2 5
1.0 0.5 2.0 5.0

In this example, all values were in units of admittance. If we were interested in finding a stub length for a series stub problem, the units would be in impedance. The problem would be worked in exactly the same way. Of course in impedance, an open shunt (zero length) would have the value $Z=\infty$, representing a point at the right end of the *x*-axis.

LINE IMPEDANCE [Ω]

The impedance seen at the source end of a lossless transmission line:

$$Z_{in} = Z_0 \frac{1+\rho}{1-\rho} = Z_0 \frac{Z_L + jZ_0 \tan(\beta l)}{Z_0 + jZ_L \tan(\beta l)}$$

For a lossy transmission line:

$$Z_{in} = Z_0 \frac{Z_L + Z_0 \tanh(\gamma l)}{Z_0 + Z_L \tanh(\gamma l)}$$

Line impedance is periodic with spatial period λ/2.

$Z_0 = \sqrt{L/C}$, the characteristic impedance of the line. [Ω]

ρ = the reflection coefficient

Z_L = the load impedance [Ω]

$\beta = 2\pi/\lambda$, phase constant

$\gamma = \alpha + j\beta$, complex propagation constant

l WAVELENGTH [cm]

The physical distance that a traveling wave moves during one period of its periodic cycle.

$$\boxed{\lambda = \frac{2\pi}{\beta} = \frac{2\pi}{k} = \frac{v_p}{f}}$$

$\beta = \omega\sqrt{LC} = 2\pi/\lambda$, phase constant

$k = \omega\sqrt{\mu\varepsilon} = 2\pi/\lambda$, wave number

v_p = velocity of propagation [m/s] see p 2.

f = frequency [Hz]

l/4 QUARTER-WAVE SECTION

A quarter-wave section of transmission line has the effect of inverting the normalized impedance of the load.



To find Z_{in}, we can normalize the load (by dividing by the characteristic impedance), invert the result, and "unnormalize" this value by multiplying by the characteristic impedance.

In this case, the normalized load is $\frac{Z_0}{2} \div Z_0 = \frac{1}{2}$

so the normalized input impedance is $\left(\frac{1}{2}\right)^{-1} = 2$

and the actual input impedance is $Z_{in} = 2Z_0$

g COMPLEX PROPAGATION CONSTANT

The propagation constant for lossy lines, taking into account the resistance along the line as well as the resistive path between the conductors.

$$\gamma = \alpha + j\beta = \sqrt{ZY} = \sqrt{(R + j\omega L)(G + j\omega C)}$$



$\alpha = \sqrt{RG}$ **attenuation constant**, the real part of the complex propagation constant, describes the loss

$\beta = 2\pi/\lambda$, **phase constant**, the complex part of the complex propagation constant

Z = **series impedance** (complex, inductive) per unit length [Ω/cm]

Y = **shunt admittance** (complex, capacitive) per unit length [Ω^{-1}/cm]

R = the resistance per unit length along the transmission line [Ω/cm]

G = the conductance between conductors per unit length [Ω^{-1}/cm]

L = inductance per unit length [H/cm]

C = capacitance per unit length [F/cm]

MODULATED WAVE

Suppose we have a disturbance composed of two frequencies:

$$\sin\left[\left(\omega_0-\delta\omega\right)t-\left(\beta_0-\delta\beta\right)z\right]$$

and $$\sin\left[\left(\omega_0+\delta\omega\right)t-\left(\beta_0+\delta\beta\right)z\right]$$

where ω_0 is the average frequency and β_0 is the average phase.

Using the identity $2\cos\left(\frac{A-B}{2}\right)\sin\left(\frac{A+B}{2}\right)=\sin A+\sin B$

The combination (sum) of these two waves is

$$\boxed{2\underbrace{\cos\left(\delta\omega t-\delta\beta z\right)}_{\text{envelope}}\underbrace{\sin\left(\omega_0 t-\beta_0 z\right)}_{\text{carrier}}}$$

The envelope moves at the group velocity, see p 7.

δ = "the difference in"…

ω_0 = carrier frequency [radians/second]

ω = modulating frequency [radians/second]

β_0 = carrier frequency phase constant

β = phase constant

So the sum of two waves will be a modulated wave having a **carrier** frequency equal to the average frequency of the two waves, and an **envelope** with a frequency equal to half the difference between the two original wave frequencies.



v_g GROUP VELOCITY [cm/s]

The velocity at which the envelope of a modulated wave moves.

$$\boxed{v_g=\frac{\delta\omega}{\delta\beta}=\frac{1}{\sqrt{LC_P}}\sqrt{1-\frac{\omega_c^{\;2}}{\omega^2}}}$$ where:

L = inductance per unit length [H/cm]

C_P = capacitance per unit length [F/cm]

ε = permittivity of the material [F/cm]

μ = permeability of the material, dielectric constant [H/cm]

ω_c = carrier frequency [radians/second]

ω = modulating frequency [radians/second]

β = phase constant

Also, since β may be given as a function of ω, remember

$$v_g=\left(\frac{d\beta}{d\omega}\right)^{-1}$$

OMEGA - BETA GRAPH

This representation is commonly used for modulated waves.


ω
$\omega = \frac{\beta}{\sqrt{LC}}$
slope is $\frac{d\omega}{d\beta}$, group velocity
ω_c
slope is phase velocity
for a particular ω, β.
β

d SKIN DEPTH [cm]

The depth into a material at which a wave is attenuated by 1/e (about 36.8%) of its original intensity. This isn't the same δ that appears in the *loss tangent*, tan δ.

$$\boxed{\delta=\frac{1}{\alpha}=\sqrt{\frac{2}{\omega\mu\sigma}}}$$ where:

$\alpha = \sqrt{RG}$ **attenuation constant**, the real part of the complex propagation constant, describes loss

μ = permeability of the material, dielectric constant [H/cm]

ω = frequency [radians/second]

σ = (*sigma*) conductivity [Siemens/meter] see p12.

Skin Depths of Selected Materials

	60 Hz	1 MHz	1 GHz
silver	8.27 mm	0.064 mm	0.0020 mm
copper	8.53 mm	0.066 mm	0.0021 mm
gold	10.14 mm	0.079 mm	0.0025 mm
aluminum	10.92 mm	0.084 mm	0.0027 mm
iron	0.65 mm	0.005 mm	0.00016 mm

MAXWELL'S EQUATIONS

Maxwell's equations govern the principles of guiding and propagation of electromagnetic energy and provide the foundations of all electromagnetic phenomena and their applications. The time-harmonic expressions can be used only when the wave is sinusoidal.

	STANDARD FORM (Time Domain)	**TIME-HARMONIC** (Frequency Domain)
Faraday's Law	$\nabla\times\vec{\mathscr{E}} = -\dfrac{\partial\vec{\mathscr{B}}}{\partial t}$	$\nabla\times\vec{E} = -\mathrm{j}\omega\vec{B}$
Ampere's Law*	$\nabla\times\vec{\mathscr{H}} = \vec{\mathscr{J}} + \dfrac{\partial\vec{\mathscr{D}}}{\partial t}$	$\nabla\times\vec{H} = \mathrm{j}\omega\vec{D} + \vec{J}$
Gauss' Law	$\nabla\cdot\vec{\mathscr{D}} = \rho_v$	$\nabla\cdot\vec{D} = \rho_v$
no name law	$\nabla\cdot\vec{\mathscr{B}} = 0$	$\nabla\cdot\vec{B} = 0$

$\mathscr{E}$ = electric field [V/m]
$\mathscr{B}$ = magnetic flux density [W/m^2 or T] $\mathscr{B} = \mu_0\mathscr{H}$
t = time [s]
$\mathscr{D}$ = electric flux density [C/m^2] $\mathscr{D} = \varepsilon_0\mathscr{E}$
ρ = volume charge density [C/m^3]
$\mathscr{H}$ = magnetic field intensity [A/m]
$\mathscr{J}$ = current density [A/m^2]

*Maxwell added the $\dfrac{\partial\vec{\mathscr{D}}}{\partial t}$ term to Ampere's Law.

ELECTROMAGNETIC WAVES

MODELING MAXWELL'S EQUATIONS

This is a model of a wave, analogous to a transmission line model.



L = inductance per unit length [H/cm]
μ = permeability of the material, dielectric constant [H/cm]
G = the conductance per unit length [Ω^{-1}/cm]
σ = (*sigma*) conductivity [Siemens/meter]
C = capacitance per unit length [F/cm]
ε = permittivity of the material [F/cm]

propagation constant: $\gamma = \sqrt{(j\omega\mu)(j\omega\varepsilon + \sigma)}$

LOW FREQUENCY

At low frequencies, more materials behave as **conductors**. A wave is considered low frequency when

$\boxed{\omega \ll \dfrac{\sigma}{\varepsilon}}$ $\dfrac{\sigma}{\varepsilon}$ is the dielectric relaxation frequency

$\boxed{\eta = \dfrac{1}{\sigma\delta}(1+j)}$ intrinsic wave impedance, see p 12.

What happens to the complex propagation constant at low frequency? From the wave model above, gamma is

$$\gamma = \sqrt{(j\omega\mu)(j\omega\varepsilon + \sigma)} = \sqrt{j\omega\mu\sigma}\sqrt{1 + \frac{j\omega\varepsilon}{\sigma}}$$

Since both ω and ε/σ are small

$$\gamma = \sqrt{j\omega\mu\sigma}\left(1 + \frac{1}{2}j\omega\frac{\varepsilon}{\sigma}\right) = \sqrt{j\omega\mu\sigma}\,(1)$$

Since $\sqrt{j} = \frac{1}{\sqrt{2}} + j\frac{1}{\sqrt{2}}$

$$\gamma = \sqrt{\omega\mu\sigma}\left(\frac{1}{\sqrt{2}} + j\frac{1}{\sqrt{2}}\right) = \sqrt{\frac{\omega\mu\sigma}{2}} + j\sqrt{\frac{\omega\mu\sigma}{2}}$$

So that, with $\gamma = \alpha + j\beta$

we get $\boxed{\alpha = \sqrt{\dfrac{\omega\mu\sigma}{2}}}$, $\boxed{\beta = \sqrt{\dfrac{\omega\mu\sigma}{2}}}$ or $\boxed{\gamma = \dfrac{1}{\delta}(1+j)}$

α = **attenuation constant**, the real part of the complex propagation constant, describes the loss
β = **phase constant**, the complex part of the complex propagation constant
σ = (*sigma*) conductivity [Siemens/cm]
δ = skin depth [cm]

So the wave is attenuating at the same rate that it is propagating.

HIGH FREQUENCY

At high frequencies, more materials behave as **dielectrics**, i.e. copper is a dielectric in the gamma ray range. A wave is considered high frequency when

$$\boxed{\omega \gg \frac{\sigma}{\varepsilon}} \qquad \frac{\sigma}{\varepsilon} \text{ is the dielectric relaxation frequency}$$

$$\boxed{\eta = \sqrt{\frac{\mu}{\varepsilon}}} \qquad \text{intrinsic wave impedance, see p 12.}$$

What happens to the complex propagation constant at high frequency?

$$\gamma = \sqrt{(j\omega\mu)(j\omega\varepsilon + \sigma)} = \sqrt{j\omega\mu\, j\omega\varepsilon\left(1 + \frac{\sigma}{j\omega\varepsilon}\right)}$$

Since both $1/\omega$ and σ/ε are small

$$\gamma = j\omega\sqrt{\mu\varepsilon}\left(1 + \frac{1}{2}\frac{\sigma}{j\omega\varepsilon}\right) \qquad \boxed{\gamma = \frac{\sigma}{2}\sqrt{\frac{\mu}{\varepsilon}} + j\omega\sqrt{\mu\varepsilon}}$$

With $\gamma = \alpha + j\beta$

we get $\boxed{\alpha = \frac{\sigma}{2}\sqrt{\frac{\mu}{\varepsilon}}}$, $\boxed{\beta = \omega\sqrt{\mu\varepsilon}}$,

tan d LOSS TANGENT

The loss tangent, a value between 0 and 1, is the loss coefficient of a wave after it has traveled one wavelength. This is the way data is usually presented in texts. This is not the same δ that is used for skin depth.

$$\boxed{\tan\delta = \frac{\sigma}{\omega\varepsilon}}$$

Graphical representation of loss tangent:



For a dielectric, $\tan\delta \ll 1$.

$$\alpha \approx \frac{1}{2}(\tan\delta)\beta = \frac{\pi}{\lambda}\tan\delta$$

$\omega\varepsilon$ is proportional to the amount of current going through the capacitance C.

σ is proportional to the amount current going through the conductance G.

TEM WAVES

Transverse Electromagnetic Waves

Electromagnetic waves that have single, orthogonal vector electric and magnetic field components (e.g., $\mathscr{E}_x$ and $\mathscr{H}_y$), both varying with a single coordinate of space (e.g., z), are known as *uniform plane waves* or *transverse electromagnetic (TEM) waves*. TEM calculations may be made using formulas from electrostatics; this is referred to as *quasi-static* solution.

Characteristics of TEM Waves

- The velocity of propagation (always in the *z* direction) is $v_p = 1/\sqrt{\mu\varepsilon}$, which is the speed of light in the material
- There is no electric or magnetic field in the direction of propagation. Since this means there is no voltage drop in the direction of propagation, it suggests that no current flows in that direction.
- The electric field is normal to the magnetic field
- The value of the electric field is η times that of the magnetic field at any instant.
- The direction of propagation is given by the direction of $\mathbf{E}\times\mathbf{H}$.
- The energy stored in the electric field per unit volume at any instant and any point is equal to the energy stored in the magnetic field.

TEM ASSUMPTIONS

Some assumptions are made for TEM waves.

$\mathscr{E}_z = 0$ $\qquad$ $\mathscr{H}_z = 0$

$\sigma = 0$ $\qquad$ time dependence $e^{j\omega t}$

WAVE ANALOGIES

Plane waves have many characteristics analogous to transmission line problems.

Transmission Lines	Plane Waves
Phase constant $\beta=\omega\sqrt{LC}=\frac{\omega}{v_p}=\frac{2\pi}{\lambda}$	Wave number $k=\omega\sqrt{\mu\varepsilon}=\frac{\omega}{v_p}=\frac{2\pi}{\lambda}$
Complex propagation const. $\gamma=\alpha+j\beta$ $=\sqrt{(R+j\omega L)(G+j\omega C)}$	Complex propagation constant $\gamma=\sqrt{(j\omega\mu)(j\omega\varepsilon+\sigma)}$
Velocity of propagation $v_p=\frac{1}{\sqrt{LC}}=\frac{\omega}{\beta}$	Phase velocity $v_p=\frac{1}{\sqrt{\mu\varepsilon}}=\frac{\omega}{k}=\omega\delta=c\frac{2\pi\delta}{\lambda}$
Characteristic impedance $Z_0=\sqrt{\frac{L}{C}}=\frac{V_+}{I_+}$	Intrinsic impedance $\eta=\sqrt{\frac{\mu}{\varepsilon}}=\frac{E_{x+}}{H_{y+}}$
Voltage $V(z)=V_+e^{-j\beta z}+V_-e^{j\beta z}$	Electric Field $E_x(z)=E_+e^{-jkz}+E_-e^{jkz}$
Current $I(z)=\frac{1}{Z_0}\left[V_+e^{-j\beta z}-V_-e^{j\beta z}\right]$	Magnetic Field $H_y(z)=\frac{1}{\eta}\left[E_+e^{-jkz}-E_-e^{jkz}\right]$
Line input impedance $Z_{in}=Z_0\frac{Z_L+jZ_0\tan(\beta l)}{Z_0+jZ_L\tan(\beta l)}$ $Z_{in}=Z_0\frac{Z_L+Z_0\tanh(\gamma l)}{Z_0+Z_L\tanh(\gamma l)}$	Wave input impedance $\eta_{in}=\eta_0\frac{\eta_L+j\eta_0\tan(kl)}{\eta_0+j\eta_L\tan(kl)}$ $\eta_{in}=\eta_0\frac{\eta_L+\eta_0\tanh(\gamma l)}{\eta_0+\eta_L\tanh(\gamma l)}$
Reflection coefficient $\rho=\frac{Z_L-Z_0}{Z_L+Z_0}$	Reflection coefficient $\rho=\frac{\eta_L-\eta_0}{\eta_L+\eta_0}$

k WAVE NUMBER [rad./cm]

The phase constant for the uniform plane wave; the change in phase per unit length. It can be considered a constant for the medium at a particular frequency.

$$\boxed{k=\frac{\omega}{v}=\omega\sqrt{\mu\varepsilon}=\frac{2\pi}{\lambda}}$$

k appears in the phasor forms of the uniform plane wave

$E_x(z)=E_1e^{-jkz}+E_2e^{jkz}$, etc.

k has also been used as in the "*k* of a dielectric" meaning ε_r.

h (eta) INTRINSIC WAVE IMPEDANCE [Ω]

The ratio of electric to magnetic field components. Can be considered a constant of the medium. For free space, η = 376.73Ω. The units of η are in ohms.

$$\eta=\frac{E_{x+}}{H_{y+}}=-\frac{E_{y+}}{H_{x+}} \qquad -\eta=\frac{E_{x-}}{H_{y-}}=-\frac{E_{y-}}{H_{x-}}$$

at low frequencies	at high frequencies
$\eta=\frac{1}{\sigma\delta}(1+j)$	$\eta=\sqrt{\frac{\mu}{\varepsilon}}$

When an electromagnetic wave encounters a sheet of conductive material it sees an impedance. K is the direction of the wave, **H** is the magnetic component and **E** is the electrical field. **E** × **H** gives the direction of propagation K.



SHEET RESISTANCE [Ω]

Consider a block of material with conductivity σ.



It's resistance is $R = \dfrac{l}{wt\sigma}$ Ω.

If the length is equal to the width, this reduces to

$$R = \frac{1}{t\sigma} \ \Omega.$$

And this is sheet resistance.

HIGH FREQUENCY RESISTANCE [Ω]

When a conductor carries current at high frequency, the electric field penetrates the outer surface only about 1 skin depth so that current travels near the surface of the conductor. Since the entire cross-section is not utilized, this affects the resistance of the conductor.

Cross-section of a conductor showing current flow near the surface:



$$\boxed{R \approx \frac{1}{\sigma\delta(\text{perimeter})} = \sqrt{\frac{\omega\mu_0}{2\sigma}}\,\frac{1}{2w+2t}}$$

σ = (*sigma*) conductivity (5.8×10^5 S/cm for copper) [Siemens/meter]
ω = frequency [radians/second]
δ = skin depth [cm]
μ_0 = permeability of free space $\mu_0 = 4\pi\times10^{-9}$ [H/cm]
w = width of the conductor [cm]
t = thickness of the conductor [cm]

h$_{\mathbf{in}}$ WAVE INPUT IMPEDANCE [Ω]

The impedance seen by a wave in a medium.

For example, the impedance of a metal sheet in a vacuum:



Note that a transmission line model is used here because it is analogous to a wave traveling in a medium. The "load" is the element most remote in the direction of propagation.

The input impedance is $\eta_{in} = \eta_0 \dfrac{\eta_L + \eta_0 \tanh(\gamma l)}{\eta_0 + \eta_L \tanh(\gamma l)}$ Ω.

In this example, *l* is the thickness of a metal sheet. If the metal thickness is much greater than the skin depth, then

$$\tanh(\lambda l) = \tanh\left[\frac{1}{\delta}(1+j)l\right] = \tanh[(\text{big number})(1+j)] \approx 1$$

If *l* is much less than the skin depth δ, then

$$\tanh(\lambda l) = \tanh\left[\frac{1}{\delta}(1+j)l\right] = \tanh[(\text{small number})(1+j)]$$

$$= (\text{same small number})(1+j) = \frac{l}{\delta}(1+j)$$

m MAGNETIC PERMEABILITY [H/m]

The relative increase or decrease in the resultant magnetic field inside a material compared with the magnetizing field in which the given material is located. The product of the permeability constant and the relative permeability of the material.

$\mu = \mu_0\mu_r$ where $\mu_0 = 4\pi\times10^{-7}$ H/m

Relative Permeabilities of Selected Materials

Air	1.00000037	Mercury	0.999968
Aluminum	1.000021	Nickel	600
Copper	0.9999833	Oxygen	1.000002
Gold	0.99996	Platinum	1.0003
Iron (99.96% pure)	280,000	Silver	0.9999736
Iron (motor grade)	5000	Titanium	1.00018
Lead	0.9999831	Tungsten	1.00008
Manganese	1.001	Water	0.9999912

e **ELECTRIC PERMITTIVITY** [F/m]

The property of a dielectric material that determines how much electrostatic energy can be stored per unit of volume when unit voltage is applied, also called the ***dielectric constant***. The product of the constant of permittivity and the relative permittivity of a material.

$$\varepsilon = \varepsilon_0 \varepsilon_r \quad \text{where } \varepsilon_0 = 8.85\times10^{-14} \text{ F/cm}$$

e_c **COMPLEX PERMITTIVITY**

$$\varepsilon_c = \varepsilon' - j\varepsilon'' \quad \text{where} \quad \frac{\varepsilon''}{\varepsilon'} = \tan\delta_c$$

In general, both ε' and ε'' depend on frequency in complicated ways. ε' will typically have a constant maximum value at low frequencies, tapering off at higher frequencies with several peaks along the way. ε'' will typically have a peak at the frequency at which ε' begins to decline in magnitude as well as at frequencies where ε' has peaks, and will be zero at low frequencies and between peaks.

e_r **RELATIVE PERMITTIVITY**

The permittivity of a material is the relative permittivity multiplied by the permittivity of free space

$$\varepsilon = \varepsilon_r \times \varepsilon_0$$

In old terminology, ε_r is called the "*k* of a dielectric". Glass (SiO_2) at $\varepsilon_r = 4.5$ is considered the division between low *k* and high *k* dielectrics.

Relative Permittivities of Selected Materials

Air (sea level)	1.0006	Polystyrene	2.6
Ammonia	22	Polyethylene	2.25
Bakelite	5	Rubber	2.2-4.1
Glass	4.5-10	Silicon	11.9
Ice	3.2	Soil, dry	2.5-3.5
Mica	5.4-6	Styrofoam	1.03
most metals	~1	Teflon	2.1
Plexiglass	3.4	Vacuum	1
Porcelain	5.7	Water, distilled	81
Paper	2-4	Water, seawater	72-80
Oil	2.1-2.3		

NOTE: Relative permittivity data is given for materials at **low or static frequency conditions**. The permittivity for most materials varies with frequency. The relative permittivities of most materials lie in the range of 1-25. At high frequencies, the permittivity of a material can be quite different (usually less), but will have resonant peaks.

s **CONDUCTIVITY** [S/m] or [1/(Ω·m)]

A measure of the ability of a material to conduct electricity, the higher the value the better the material conducts. The reciprocal is *resistivity*. Values for common materials vary over about 24 orders of magnitude. Conductivity may often be determined from skin depth or the loss tangent.

$$\sigma = \frac{n_c q_e^2 \overline{l}}{m_e v_{th}} \text{ S/m} \quad \text{where}$$

n_c = density of conduction electrons (for copper this is 8.45×10^{28}) [m^{-3}]

q_e = electron charge? 1.602×10^{-23} [C]

$\overline{l}$ = $v_{th}t_c$ the product of the thermal speed and the mean free time between collisions of electrons, the average distance an electron travels between collisions [m]

m_e = the effective electron mass? [kg]

v_{th} = thermal speed, usually much larger than the drift velocity v_d. [m/s]

Conductivities of Selected Materials [1/(Ω·m)]

Aluminum	3.82×10^7	Mercury	1.04×10^6
Carbon	7.14×10^4	Nicrome	1.00×10^6
Copper (annealed)	5.80×10^7	Nickel	1.45×10^7
Copper (in class)	6.80×10^7	Seawater	4
Fresh water	$\sim10^{-2}$	Silicon	$\sim4.35\times10^{-4}$
Germanium	~2.13	Silver	6.17×10^7
Glass	$\sim10^{-12}$	Sodium	2.17×10^7
Gold	4.10×10^7	Stainless steel	1.11×10^6
Iron	1.03×10^7	Tin	8.77×10^6
Lead	4.57×10	Titanium	2.09×10^6
		Zinc	1.67×10^7

P **POWER** [W]

Power is the time rate of change of energy.

Power reflected at a discontinuity: $\%\text{ power} = |\rho|^2 \times 100$

Power transmitted at a discontinuity: $\%\text{ power} = \left(1 - |\rho|^2\right) \times 100$

MICROSTRIP CONDUCTORS

How fast does a wave travel in a microstrip? The question is complicated by the fact that the dielectric on one side of the strip may be different from the dielectric on the other side and a wave may travel at different speeds in different dielectrics. The solution is to find an **effective relative permittivity** $\varepsilon_{r\,\text{eff}}$ for the combination.



Some Microstrip Relations

$$Z_0^{\text{air}} = Z_0\sqrt{\varepsilon_{r\,\text{eff}}} \qquad C^{\text{air}}Z_0^{\text{air}} = \sqrt{\varepsilon_0\mu_0}$$

$$L = Z_0^{\text{air}}\sqrt{\varepsilon_0\mu_0} = C^{\text{total}}\left(Z_0\right)^2 \qquad L\,C^{\text{air}} = \varepsilon_0\mu_0$$

$$Z_0 = \sqrt{\frac{L}{C^{\text{total}}}} \qquad Z_0^{\text{air}} = \sqrt{\frac{L}{C^{\text{air}}}}$$

$$\gamma = j\beta = j\omega\sqrt{\varepsilon_0\mu_0}\sqrt{\varepsilon_{r\,\text{eff}}} \qquad \varepsilon_{r\,\text{eff}} = \frac{C^{\text{total}}}{C^{\text{air}}}$$

$$v_p = \frac{1}{\sqrt{\varepsilon_0\mu_0\varepsilon_{r\,\text{eff}}}} = \frac{1}{\sqrt{L\,C^{\text{total}}}}$$

It's difficult to get more than 200Ω for Z_0 in a microstrip.

Microstrip Approximations

$$\varepsilon_{r\,\text{eff}} = \frac{\varepsilon_r+1}{2} + \frac{\varepsilon_r-1}{2\sqrt{1+12h/w}}$$

$$Z_0 = \begin{cases} \dfrac{60}{\sqrt{\varepsilon_{r\,\text{eff}}}}\ln\left[\dfrac{8h}{w}+\dfrac{w}{4h}\right], & \text{for } \dfrac{w}{h}\le 1 \\[2ex] \dfrac{120\pi}{\sqrt{\varepsilon_{r\,\text{eff}}}\left[\dfrac{w}{h}+1.393+0.667\ln\left(\dfrac{w}{h}+1.444\right)\right]}, & \text{for } \dfrac{w}{h}>1 \end{cases}$$

$$\frac{w}{h} = \begin{cases} \dfrac{8e^A}{e^{2A}-2}, & \dfrac{w}{h}<2 \\[2ex] \dfrac{2}{\pi}\left\{B-1-\ln\left(2B-1\right)+\dfrac{\varepsilon_r-1}{2\varepsilon_r}\left[\ln\left(B-1\right)+0.39-\dfrac{0.61}{\varepsilon_r}\right]\right\}, & \dfrac{w}{h}>2 \end{cases}$$

where $A = \dfrac{Z_0}{60}\sqrt{\dfrac{\varepsilon_r+1}{2}} + \dfrac{\varepsilon_r-1}{\varepsilon_r+1}\left(0.23+\dfrac{0.11}{\varepsilon_r}\right),\ B = \dfrac{377\pi}{2Z_0\sqrt{\varepsilon_r}}$

STRIPLINE CONDUCTOR

Also called *shielded microstrip*. The effective relative permittivity is used in calculations.



assuming $w \ge 10h$, $\quad \varepsilon_{r\,\text{eff}} = \dfrac{\varepsilon_{r1}h_1+\varepsilon_{r2}h_2}{h_1+h_2}$ where

ε_{r1} = the relative permittivity of the dielectric of thickness h_1.
ε_{r2} = the relative permittivity of the dielectric of thickness h_2.

COPPER CLADDING

The thickness of copper on a circuit board is measured in ounces. 1-ounce cladding means that 1 square foot of the copper weighs 1 ounce. 1-ounce copper is 0.0014" or 35.6 μm thick.

a***d*** DIELECTRIC LOSS FACTOR [dB/cm]

$$\alpha_d = 8.68\frac{\beta_0\varepsilon_r\left(\varepsilon_{r\,\text{eff}}-1\right)}{2\sqrt{\varepsilon_{r\,\text{eff}}}\left(\varepsilon_r-1\right)}\tan\delta$$

a***c*** CONDUCTOR LOSS FACTOR [dB/cm]

$$\alpha_c = 8.68\frac{R}{2Z_0}, \qquad R = \frac{1}{\sigma\delta(\text{perimeter})} = \sqrt{\frac{\omega\mu_0}{2\sigma}}\frac{1}{(\text{perimeter})}$$

WHEELER'S EQUATION

Another approximation for microstrip calculations is Wheeler's equation.

$$Z_0 = \frac{42.4}{\sqrt{1+\varepsilon_r}} \ln\left(1+\left\{\frac{4h}{w'}\left[\frac{14+\frac{8}{\varepsilon_r}}{11}\times\frac{4h}{w'}+\sqrt{\left(\frac{14+\frac{8}{\varepsilon_r}}{11}\times\frac{4h}{w'}\right)^2+\pi^2\,\frac{1+\frac{1}{\varepsilon_r}}{2}}\right]\right\}\right)$$

where $$w' = \frac{8h\sqrt{\frac{7+\frac{4}{\varepsilon_r}}{11}\left[\exp\left(\frac{Z_0}{42.4}\sqrt{\varepsilon_r+1}\right)-1\right]+\frac{1+\frac{1}{\varepsilon_r}}{0.81}}}{\exp\left(\frac{Z_0}{42.4}\sqrt{\varepsilon_r+1}\right)-1}$$

NETWORK THEORY

S_{ij} SCATTERING PARAMETER

$$S_{\mathrm{i\,j}}$$

observation port excitation port

A scattering parameter, represented by S_{ij}, is a dimensionless value representing the fraction of wave amplitude transmitted from port j into port i, provided that all other ports are terminated with matched loads and only port j is receiving a signal. Under these same conditions, S_{ii} is the reflection coefficient at port i.

To experimentally determine the scattering parameters, attach an impedance-matched generator to one of the ports (***excitation port***), attach impedance-matched loads to the remaining ports, and observe the signal received at each of the ports (***observation ports***). The fractional amounts of signal amplitude received at each port i will make up one column j of the **scattering matrix**. Repeating the process for each column would require n^2 measurements to determine the scattering matrix for an n-port network.

S_{ij} SCATTERING MATRIX

$$\begin{bmatrix} S_{11} & S_{12} & \cdots & S_{1N} \\ S_{21} & S_{22} & \cdots & S_{2N} \\ \vdots & \vdots & \ddots & \vdots \\ S_{N1} & S_{N2} & \cdots & S_{NN} \end{bmatrix}$$

The scattering matrix is an $n \times n$ matrix composed of scattering parameters that describes an n-port network.

The elements of the diagonal of the scattering matrix are reflection coefficients of each port. The elements of the off-diagonal are transmission coefficients, under the conditions outlined in "SCATTERING PARAMETER".

If the network is **internally matched** or **self-matched**, then $S_{11} = S_{22} = \cdots = S_{NN} = 0$, that is, the diagonal is all zeros.

The sum of the squares of each column of a scattering matrix is equal to one, provided the network is lossless.

a_n, b_n INCIDENT/REFLECTED WAVE AMPLITUDES

The parameters a_n and b_n describe the incident and reflected waves respectively at each port n. These parameters are used for power and scattering matrix calculations.

The amplitude of the wave incident to port n is equal to the amplitude of the incident voltage at the port divided by the square root of the port impedance.	$a_n = \frac{V_n^+}{\sqrt{Z_{0n}}}$
Amplitude of the wave reflected at port n is equal to the amplitude of the reflected voltage at the port divided by the square root of the port impedance.	$b_n = \frac{V_n^-}{\sqrt{Z_{0n}}}$
The scattering parameter is equal to the wave amplitude output at port i divided by the wave amplitude input at port j provided the only source is a matched source at port j and all other ports are connected to matched loads.	$S_{\mathrm{ij}} = \frac{b_{\mathrm{i}}}{a_{\mathrm{j}}}$
The relationship between the S-parameters and the a- and b-parameters can be written in matrix form where **S** is the scattering matrix and **a** and **b** are column vectors.	$\mathbf{b} = \mathbf{Sa}$
Power flow into any port is shown as a function of a- and b-parameters.	$P = \frac{1}{2}\left(\lvert a\rvert^2 - \lvert b\rvert^2\right)$
The ratio of the input power at port j to the output power at port I can be written as a function of a- and b-parameters or the S-parameter.	$\frac{P_{in\,\mathrm{j}}}{P_{out\,\mathrm{i}}} = \frac{\lvert a_{\mathrm{j}}\rvert^2}{\lvert b_{\mathrm{j}}\rvert^2} = \frac{1}{\lvert S_{\mathrm{ij}}\rvert^2}$

RECIPROCITY

A network is reciprocal when $S_{\mathrm{ij}} = S_{\mathrm{ji}}$ in the scattering matrix, i.e. the matrix is symmetric across the diagonal. Also, $Z_{\mathrm{ij}} = Z_{\mathrm{ji}}$ and $Y_{\mathrm{ij}} = Y_{\mathrm{ji}}$. Networks constructed of “normal materials” exhibit reciprocity.

Reciprocity Theorem:

$$\oint_S \vec{E}_a \times \vec{H}_b \cdot ds = \oint_S \vec{E}_b \times \vec{H}_a \cdot ds$$

E_a and H_b are fields from two different sources.

LOSSLESS NETWORK

A network is lossless when

$$\underline{S}\ \ \underline{S}^{\dagger} = /$$

† means to take the complex conjugate and transpose the matrix. If the network is reciprocal, then the transpose is the same as the original matrix.

/ = a unitary matrix. A **unitary matrix** has the properties:

$$\sum_{k=1}^{N} S_{ki} S_{ki}^{*} = 1 \qquad \sum_{k=1}^{N} S_{ki} S_{kj}^{*} = 0$$

In other words, a column of a unitary matrix multiplied by its complex conjugate equals one, and a column of a unitary matrix multiplied by the complex conjugate of a different column equals zero.

RAT RACE OR HYBRID RING NETWORK

The rat race or hybrid ring network is lossless, reciprocal, and internally matched.



The signal splits upon entering the network and half travels around each side. A signal entering at port 1 and exiting at port 4 travels ¾ of a wavelength along each side, so the signals are in phase and additive. From port 1 to port 3 the signal travels one wavelength along one side and ½ wavelength along the other, arriving a port 3 out of phase and thus canceling. From port 1 to port 2 the paths are ¼ and 5/4 wavelengths respectively, thus they are in phase and additive.

DIRECTIONAL COUPLER



The directional coupler is a 4-port network similar to the rat race. It can be used to measure reflected and transmitted power to an antenna.

An input at one port is divided between two of the remaining ports. The **coupling factor**, measured in dB, describes the division of signal strength at the two ports. For example if the coupler has a coupling factor of –10 dB, then a signal input at port 1 would appear at port 4 attenuated by 10 dB with the majority of the signal passing to port 2. In other words, 90% of the signal would appear at port 2 and 10% at port 4. (-10 dB means "**10 dB down**" or 0.1 power, -6 dB means 0.25 power, and –3 dB means 0.5 power.) A reflection from port 2 would appear at port 3 attenuated by the same amount. Meters attached to ports 3 and 4 could be used to measure reflected and transmitted power for a system with a transmitter connected to port 1 and an antenna at port 2. The **directivity** of a coupler is a measurement of how well the coupler transfers the signal to the appropriate output without reflection due to the coupler itself; the directivity approaches infinity for a perfect coupler. $\text{directivity} = 10\log\left(p_3 / p_1\right)$, where the source is at port 1 and the load is at port 2.

The directional coupler is **lossless** and **reciprocal**. The scattering matrix looks like this. In a real coupler, the off-diagonal zeros would be near zero due to leakage.

$$\begin{bmatrix} 0 & p & 0 & -q \\ p & 0 & q & 0 \\ 0 & q & 0 & p \\ -q & 0 & p & 0 \end{bmatrix}$$

CIRCULATOR

The circulator is a 3-port network that can be used to prevent reflection at the antenna from returning to the source.



Port 3 is terminated internally by a matched load. With a source at 1 and a load at 2, any power reflected at the load is absorbed by the load resistance at port 3. A 3-port network cannot be both lossless and reciprocal, so the circulator is not reciprocal.

Schematically, the circulator may be depicted like this:



The circulator is **lossless** but is not **reciprocal**. The scattering matrix looks like this:

$$\begin{bmatrix} 0 & 0 & 1 \\ 1 & 0 & 0 \\ 0 & 1 & 0 \end{bmatrix}$$

MAXWELL'S EQUATIONS, TIME HARMONIC FORM

$$\nabla\times\bar{\mathscr{E}} = -j\omega\mu\mathbf{H} \qquad \text{"curl on E"}$$

$$\nabla\times\bar{\mathscr{H}} = -j\omega\mu\mathbf{E} \qquad \text{"curl on H"}$$

$$\bar{\mathscr{E}} = \left[E_x\left(x,y\right)\hat{\mathbf{x}} + E_y\left(x,y\right)\hat{\mathbf{y}} + E_z\left(x,y\right)\hat{\mathbf{z}}\right]e^{j\omega t-\gamma z}$$

$$\bar{\mathscr{H}} = \left[H_x\left(x,y\right)\hat{\mathbf{x}} + H_y\left(x,y\right)\hat{\mathbf{y}} + H_z\left(x,y\right)\hat{\mathbf{z}}\right]e^{j\omega t-\gamma z}$$

From the curl equations we can derive:

(1) $\dfrac{\partial E_z}{\partial y} + \gamma E_y = -j\omega\mu H_x$ (4) $\dfrac{\partial H_z}{\partial y} + \gamma H_y = j\omega\varepsilon E_x$

(2) $-\dfrac{\partial E_z}{\partial x} - \gamma E_x = -j\omega\mu H_y$ (5) $-\dfrac{\partial H_z}{\partial x} - \gamma H_x = j\omega\varepsilon E_y$

(3) $\dfrac{\partial E_y}{\partial x} - \dfrac{\partial E_x}{\partial y} = -j\omega\mu H_z$ (6) $\dfrac{\partial H_y}{\partial x} - \dfrac{\partial H_x}{\partial y} = j\omega\varepsilon E_z$

From the above equations we can obtain:

(1) & (5) $H_x = \dfrac{1}{\gamma^2+\omega^2\mu\varepsilon}\left(j\omega\varepsilon\dfrac{\partial E_z}{\partial y} - \gamma\dfrac{\partial H_z}{\partial x}\right)$

(2) & (4) $H_y = \dfrac{1}{\gamma^2+\omega^2\mu\varepsilon}\left(j\omega\varepsilon\dfrac{\partial E_z}{\partial x} - \gamma\dfrac{\partial H_z}{\partial y}\right)$

(2) & (4) $E_x = -\dfrac{1}{\gamma^2+\omega^2\mu\varepsilon}\left(-\gamma\dfrac{\partial E_z}{\partial x} + j\omega\mu\dfrac{\partial H_z}{\partial y}\right)$

(1) & (5) $E_y = -\dfrac{1}{\gamma^2+\omega^2\mu\varepsilon}\left(-\gamma\dfrac{\partial E_z}{\partial y} + j\omega\mu\dfrac{\partial H_z}{\partial x}\right)$

This makes it look like if E_z and H_z are zero, then H_x, H_y, E_x, and E_y are all zero. But since $\infty\times 0 \neq 0$, we could have non-zero result for the TEM wave if $\gamma^2 = -\omega^2\mu\varepsilon \Rightarrow \gamma = j\omega\sqrt{\mu\varepsilon}$. This should look familiar.

WAVE EQUATIONS

From Maxwell's equations and a vector identity on curl, we can get the following wave equations:

$$\nabla^2 \overline{\mathscr{E}} = -\omega^2 \mu\varepsilon \overline{\mathscr{E}} \qquad \text{"del squared on E"}$$

$$\nabla^2 \overline{\mathscr{H}} = \omega^2 \mu\varepsilon \overline{\mathscr{H}} \qquad \text{"del squared on H"}$$

The z part or "del squared on E_z" is:

$$\nabla^2 E_z = \frac{\gamma^2 E_z}{\partial x^2} + \frac{\gamma^2 E_z}{\partial y^2} + \frac{\gamma^2 E_z}{\partial z^2} = -\omega^2 \mu\varepsilon E_z$$

Using the separation of variables, we can let:

$$E_z = X(x) \cdot Y(y) \cdot Z(z)$$

We substitute this into the previous equation and divide by $X \cdot Y \cdot Z$ to get:

$$\underbrace{\frac{1}{X}\frac{d^2X}{dx^2}}_{-k_x{}^2} + \underbrace{\frac{1}{Y}\frac{d^2Y}{dy^2}}_{-k_y{}^2} + \underbrace{\frac{1}{Z}\frac{d^2Z}{dz^2}}_{-k_z{}^2} = \underbrace{-\omega^2\mu\varepsilon}_{\text{a constant}}$$

Since X, Y, and Z are independent variables, the only way the sum of these 3 expressions can equal a constant is if all 3 expressions are constants.

So we are letting $\frac{1}{Z}\frac{d^2Z}{dz^2} = -k_z{}^2 \Rightarrow \frac{d^2Z}{dz^2} = -Zk_z{}^2$

A solution could be $Z = e^{-\gamma z}$

so that $\gamma^2 e^{-\gamma z} = -k_z{}^2 e^{-\gamma z}$ and $-k_z{}^2 = \gamma^2$

Solutions for X and Y are found

$$\frac{1}{X}\frac{d^2X}{dx^2} = -k_x{}^2 \Rightarrow X = A\sin(k_x x) + B\cos(k_x x)$$

$$\frac{1}{Y}\frac{d^2Y}{dy^2} = -k_y{}^2 \Rightarrow Y = C\sin(k_y y) + D\cos(k_y y)$$

giving us the general solution $k_x{}^2 + k_y{}^2 - \gamma^2 = \omega^2\mu\varepsilon$

For a particular solution we need to specify initial conditions and boundary conditions. For some reason, initial conditions are not an issue. The unknowns are k_x, k_y, A, B, C, D. The boundary conditions are

$$E_{\tan} = 0 \qquad \frac{\partial H_{\tan}}{\partial n} = 0$$

$E_{\tan}$ = the electric field tangential to a conducting surface
$H_{\tan}$ = the magnetic field tangential to a conducting surface
n = I don't know

TM, TE WAVES IN PARALLEL PLATES

TM, or transverse magnetic, means that magnetic waves are confined to the *transverse plane*. Similarly, TE (transverse electric) means that electrical waves are confined to the transverse plane.



(z direction is into page)

Transverse plane means the plane that is transverse to (perpendicular to) the direction of propagation. The direction of propagation is taken to be in the z direction, so the transverse plane is the x-y plane. So for a TM wave, there is no H_z component (magnetic component in the z direction) but there is an E_z component.

$$\boxed{E_z = A\sin(k_x x)e^{-\gamma z}}$$

A = amplitude [V]

$k_x = \frac{m\pi}{d}$ The magnetic field must be zero at the plate boundaries. This value provides that characteristic. [cm^{-1}]

x = position; perpendicular distance from one plate. [cm]
d = plate separation [cm]
γ = propagation constant
z = position along the direction of propagation [cm]
m = mode number; an integer greater than or equal to 1

$$\boxed{\gamma = \sqrt{-\omega^2\mu\varepsilon + (kx)^2}}$$

Notice than when $(kx)^2 \geq \omega^2\mu\varepsilon$, the quantity under the square root sign will be positive and γ will be purely real. In this circumstance, the wave is said to be evanescent. The wavelength goes to infinity; there is no oscillation or propagation. On the other hand, when $(kx)^2 < \omega^2\mu\varepsilon$, γ is purely imaginary.

The magnitude of E_z is related to its position between the plates and the mode number m. Note that for m = 2 that $d = \lambda$.



GENERAL MATHEMATICAL

COMPLEX TO POLAR NOTATION

j in polar notation:

$$j = e^{j\frac{\pi}{2}}$$

So we can find the square root of *j*:

$$\sqrt{j} = \sqrt{e^{j\frac{\pi}{2}}} = e^{j\frac{\pi}{4}} = \frac{1}{\sqrt{2}} + j\frac{1}{\sqrt{2}}$$



dBm DECIBELS RELATIVE TO 1 mW

The decibel expression for power. The logarithmic nature of decibel units translates the multiplication and division associated with gains and losses into addition and subtraction.

0 dBm = 1 mW
20 dBm = 100 mW
-20 dBm = 0.01 mW

$$P(\mathrm{dBm}) = 10\log\left[P(\mathrm{mW})\right]$$

$$P(\mathrm{mW}) = 10^{P(\mathrm{dBm})/10}$$

PHASOR NOTATION

To express a derivative in phasor notation, replace $\frac{\partial}{\partial t}$ with $j\omega$. For example, the Telegrapher's equation $\frac{\partial V}{\partial z} = -L\frac{\partial I}{\partial t}$

becomes $\frac{\partial V}{\partial z} = -Lj\omega I$.

Ñ NABLA, DEL OR GRAD OPERATOR

Compare the ∇ operation to taking the time derivative. Where $\partial/\partial t$ means to take the derivative with respect to time and introduces a s^{-1} component to the units of the result, the ∇ operation means to take the derivative with respect to distance (in 3 dimensions) and introduces a m^{-1} component to the units of the result. ∇ terms may be called space derivatives and an equation which contains the ∇ operator may be called a vector differential equation. In other words $\nabla\mathbf{A}$ is how fast **A** changes as you move through space.

in rectangular coordinates: $\nabla\mathbf{A} = \hat{x}\frac{\partial A}{\partial x} + \hat{y}\frac{\partial A}{\partial y} + \hat{z}\frac{\partial A}{\partial z}$

in cylindrical coordinates: $\nabla\mathbf{A} = \hat{r}\frac{\partial A}{\partial r} + \hat{\phi}\frac{1}{r}\frac{\partial A}{\partial \phi} + \hat{z}\frac{\partial A}{\partial z}$

in spherical coordinates: $\nabla\mathbf{A} = \hat{r}\frac{\partial A}{\partial r} + \hat{\theta}\frac{1}{r}\frac{\partial A}{\partial \theta} + \hat{\phi}\frac{1}{r\sin\theta}\frac{\partial A}{\partial \phi}$

∇ GRADIENT

$$\boxed{\nabla\bar{\Phi} = -\mathbf{E}}$$

"The gradient of the vector Φ" or "del Φ" is equal to the negative of the electric field vector.

$\nabla\Phi$ is a vector giving the direction and magnitude of the maximum spatial variation of the scalar function Φ at a point in space.

$$\nabla\bar{\Phi} = \hat{\mathbf{x}}\frac{\partial\Phi}{\partial x} + \hat{\mathbf{y}}\frac{\partial\Phi}{\partial y} + \hat{\mathbf{z}}\frac{\partial\Phi}{\partial z}$$

Ñx DIVERGENCE

$\nabla\cdot$ is also a vector operator, combining the "del" or "grad" operator with the dot product operator and is read as "the divergence of". In this form of Gauss' law, where **D** is a density per unit area, with the operators applied, $\nabla\cdot\mathbf{D}$ becomes a density per unit volume.

$$\boxed{\operatorname{div}\mathbf{D} = \nabla\cdot\mathbf{D} = \frac{\partial D_x}{\partial x} + \frac{\partial D_y}{\partial y} + \frac{\partial D_z}{\partial z} = \rho}$$

D = electric flux density vector $\mathbf{D} = \varepsilon\mathbf{E}$ [C/m^2]
ρ = source charge density [C/m^3]

Ñ$^{\mathbf{2}}$ THE LAPLACIAN

∇^2 is a combination of the divergence and del operations, i.e. $\mathrm{div}(\mathrm{grad}\,\Phi) = \nabla\cdot\nabla\,\Phi = \nabla^2\,\Phi$. It is read as "the LaPlacian of" or "del squared".

$$\boxed{\nabla^2\mathbf{F} = \frac{\partial^2\,\Phi}{\partial\,x^2} + \frac{\partial^2\,\Phi}{\partial\,y^2} + \frac{\partial^2\,\Phi}{\partial\,z^2}}$$

F = electric potential [V]

GRAPHING TERMINOLOGY

With *x* being the horizontal axis and *y* the vertical, we have a graph of ***y* versus *x*** or ***y* as a function of *x***. The *x*-axis represents the **independent variable** and the *y*-axis represents the **dependent variable**, so that when a graph is used to illustrate data, the data of regular interval (often this is time) is plotted on the *x*-axis and the corresponding data is dependent on those values and is plotted on the *y*-axis.

HYPERBOLIC FUNCTIONS

$$j\sin\theta = \sinh\left(j\theta\right)$$

$$j\cos\theta = \cosh\left(j\theta\right)$$

$$j\tan\theta = \tanh\left(j\theta\right)$$

TAYLOR SERIES

$$\sqrt{1+x} \approx 1+\frac{1}{2}x\,, \quad x \ll 1$$

$$\frac{1}{1-x^2} \approx 1+x^2+x^4+x^6+\cdots\,, \quad \left|x\right|<1$$

$$\frac{1}{1\pm x} \approx 1\mp x\,, \quad x \ll 1$$

ELECTROMAGNETIC SPECTRUM

FREQUENCY	WAVELENGTH (free space)	DESIGNATION	APPLICATIONS
< 3 Hz	> 100 Mm		Geophysical prospecting
3-30 Hz	10-100 Mm	ELF	Detection of buried metals
30-300 Hz	1-10 Mm	SLF	Power transmission, submarine communications
0.3-3 kHz	0.1-1 Mm	ULF	Telephone, audio
3-30 kHz	10-100 km	VLF	Navigation, positioning, naval communications
30-300 kHz	1-10 km	LF	Navigation, radio beacons
0.3-3 MHz	0.1-1 km	MF	AM broadcasting
3-30 MHz	10-100 m	HF	Short wave, citizens' band
30-300 MHz	1-10 m	VHF	TV, FM, police
54-72			TV channels 2-4
76-88			TV channels 5-6
88-108			FM radio
174-216			TV channels 7-13
0.3-3 GHz	10-100 cm	UHF	Radar, TV, GPS, cellular phone
470-890 MHz			TV channels 14-83
915 MHz			Microwave ovens (Europe)
800-2500 MHz		"money band"	PCS cellular phones, analog at 900 MHz, GSM/CDMA at 1900
1-2			L-band, GPS system
2.45			Microwave ovens (U.S.)
2-4			S-band
3-30 GHz	1-10 cm	SHF	Radar, satellite communications
4-8			C-band
8-12			X-band (Police radar at 11 GHz)
12-18			K_u-band (dBS Primestar at 14 GHz)
18-27			K-band (Police radar at 22 GHz)
30-300 GHz	0.1-1 cm	EHF	Radar, remote sensing
27-40			K_a-band (Police radar at 35 GHz)
40-60			U-band
60-80			V-band
80-100			W-band
0.3-1 THz	0.3-1 mm	Millimeter	Astromony, meteorology
10^{12}-10^{14} Hz	3-300 μm	Infrared	Heating, night vision, optical communications
3.95×10^{14}-7.7×10^{14} Hz	390-760 nm	Visible light	Vision, astronomy, optical communications
	625-760		Red
	600-625		Orange
	577-600		Yellow
	492-577		Green
	455-492		Blue
	390-455		Violet
10^{15}-10^{18} Hz	0.3-300 nm	Ultraviolet	Sterilization
10^{16}-10^{21} Hz		X-rays	Medical diagnosis
10^{18}-10^{22} Hz		γ-rays	Cancer therapy, astrophysics
> 10^{22} Hz		Cosmic rays	Astrophysics

GLOSSARY

anisotropic materials materials in which the electric polarization vector is not in the same direction as the electric field. The values of ε, μ, and σ are dependent on the field direction. Examples are crystal structures and ionized gases.

complex permittivity e The imaginary part accounts for heat loss in the medium due to damping of the vibrating dipole moments.

dielectric An insulator. When the presence of an applied field displaces electrons within a molecule away from their average positions, the material is said to be polarized. When we consider the polarizations of insulators, we refer to them as *dielectrics*.

empirical A result based on observation or experience rather than theory, e.g. *empirical data*, *empirical formulas*. Capable of being verified or disproved by observation or experiment, e.g. *empirical laws*.

evanescent wave A wave for which $\beta=0$. α will be negative. That is, γ is purely real. The wave has infinite wavelength—there is no oscillation.

isotropic materials materials in which the electric polarization vector is in the same direction as the electric field. The material responds in the same way for all directions of an electric field vector, i.e. the values of ε, μ, and σ are constant regardless of the field direction.

linear materials materials which respond proportionally to increased field levels. The value of μ is not related to $\mathbf{H}$ and the value of ε is not related to $\mathbf{E}$. Glass is linear, iron is non-linear.

overdamped system in the case of a transmission line, this means that when the source voltage is applied the line voltage rises to the final voltage without exceeding it.

time variable materials materials whose response to an electric field changes over time, e.g. when a sound wave passes through them.

transverse plane perpendicular, e.g. the x-y plane is *transverse* to z.

underdamped system in the case of a transmission line, this means that after the source voltage is applied the line voltage periodically exceeds the final voltage.

wave number k The phase constant for the uniform plane wave. k may be considered a constant of the medium at a particular frequency.

LEARNING MADE EASY

Ixia Special Edition

5G

for dummies®
A Wiley Brand

Innovations that make 5G possible

Achieve scale through network virtualization

See the future of the IoT and New Radio

Compliments of
ixia

Kalyan Sundhar

Lawrence C. Miller

About Ixia

Ixia, recently acquired by Keysight Technologies, provides testing, visibility, and security solutions, strengthening applications across networks and cloud environments for enterprises, service providers, and network equipment manufacturers. Ixia offers companies trusted environments in which to develop, deploy, and operate. Customers worldwide rely on Ixia to verify their designs, optimize their performance, and ensure protection of their networks and cloud environments to make their applications stronger. Learn more at **www.ixiacom.com**.

About Keysight Technologies

Keysight Technologies is a leading technology company that helps its engineering, enterprise, and service provider customers optimize networks and bring electronic products to market faster and at a lower cost. Keysight's solutions go where the electronic signal goes, from design simulation, to prototype validation, to manufacturing test, to optimization in networks and cloud environments. Customers span the worldwide communications ecosystem, aerospace and defense, automotive, energy, semiconductor, and general electronics end markets. Keysight generated revenues of $2.9 billion in fiscal year 2016. In April 2017, Keysight acquired Ixia, a leader in network test, visibility, and security. More information is available at **www.keysight.com**.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

5G

Ixia Special Edition

by Kalyan Sundhar and
Lawrence C. Miller

for dummies®
A Wiley Brand

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

5G For Dummies®, Ixia Special Edition

Published by
John Wiley & Sons, Inc.
111 River St.
Hoboken, NJ 07030-5774
`www.wiley.com`

Copyright © 2017 by John Wiley & Sons, Inc., Hoboken, New Jersey

No part of this publication may be reproduced, stored in a retrieval system or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, scanning or otherwise, except as permitted under Sections 107 or 108 of the 1976 United States Copyright Act, without the prior written permission of the Publisher. Requests to the Publisher for permission should be addressed to the Permissions Department, John Wiley & Sons, Inc., 111 River Street, Hoboken, NJ 07030, (201) 748-6011, fax (201) 748-6008, or online at `http://www.wiley.com/go/permissions`.

Trademarks: Wiley, For Dummies, the Dummies Man logo, Dummies.com, and related trade dress are trademarks or registered trademarks of John Wiley & Sons, Inc. and/or its affiliates in the United States and other countries, and may not be used without written permission. Ixia and the Ixia logo are trademarks or registered trademarks of Ixia Corporation. All other trademarks are the property of their respective owners. John Wiley & Sons, Inc., is not associated with any product or vendor mentioned in this book.

LIMIT OF LIABILITY/DISCLAIMER OF WARRANTY: THE PUBLISHER AND THE AUTHOR MAKE NO REPRESENTATIONS OR WARRANTIES WITH RESPECT TO THE ACCURACY OR COMPLETENESS OF THE CONTENTS OF THIS WORK AND SPECIFICALLY DISCLAIM ALL WARRANTIES, INCLUDING WITHOUT LIMITATION WARRANTIES OF FITNESS FOR A PARTICULAR PURPOSE. NO WARRANTY MAY BE CREATED OR EXTENDED BY SALES OR PROMOTIONAL MATERIALS. THE ADVICE AND STRATEGIES CONTAINED HEREIN MAY NOT BE SUITABLE FOR EVERY SITUATION. THIS WORK IS SOLD WITH THE UNDERSTANDING THAT THE PUBLISHER IS NOT ENGAGED IN RENDERING LEGAL, ACCOUNTING, OR OTHER PROFESSIONAL SERVICES. IF PROFESSIONAL ASSISTANCE IS REQUIRED, THE SERVICES OF A COMPETENT PROFESSIONAL PERSON SHOULD BE SOUGHT. NEITHER THE PUBLISHER NOR THE AUTHOR SHALL BE LIABLE FOR DAMAGES ARISING HEREFROM. THE FACT THAT AN ORGANIZATION OR WEBSITE IS REFERRED TO IN THIS WORK AS A CITATION AND/OR A POTENTIAL SOURCE OF FURTHER INFORMATION DOES NOT MEAN THAT THE AUTHOR OR THE PUBLISHER ENDORSES THE INFORMATION THE ORGANIZATION OR WEBSITE MAY PROVIDE OR RECOMMENDATIONS IT MAY MAKE. FURTHER, READERS SHOULD BE AWARE THAT INTERNET WEBSITES LISTED IN THIS WORK MAY HAVE CHANGED OR DISAPPEARED BETWEEN WHEN THIS WORK WAS WRITTEN AND WHEN IT IS READ.

For general information on our other products and services, or how to create a custom *For Dummies* book for your business or organization, please contact our Business Development Department in the U.S. at 877-409-4177, contact `info@dummies.biz`, or visit `www.wiley.com/go/custompub`. For information about licensing the *For Dummies* brand for products or services, contact `BrandedRights&Licenses@Wiley.com`.

ISBN 978-1-119-42415-4 (pbk); ISBN 978-1-119-42416-1 (ebk)

Manufactured in the United States of America

10 9 8 7 6 5 4 3 2 1

Publisher's Acknowledgments

We're proud of this book and of the people who worked on it. Some of the people who helped bring this book to market include the following:

Project Editor: Martin V. Minner

Senior Acquisitions Editor: Amy Fandrei

Editorial Manager: Rev Mengle

Business Development Representative: Karen Hattan

Production Editor: Vasanth Koilraj

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

Table of Contents

INTRODUCTION 1

About This Book 2
Foolish Assumptions 2
Icons Used in This Book 3
Beyond the Book 3
Where to Go from Here 3

CHAPTER 1: **Understanding the Journey to a 5G Future** 5

Tracing the Evolution of Wireless Communications 5
Focusing on the 5G Vision 8
Ordering Up 5G in Five Easy Pieces 9

CHAPTER 2: **Achieving Faster Speeds and Larger Feeds** 11

Fattening the Data Pipe 11
We All Bundle — with CA 13
Eeny, Meeny, Miny, MIMO 14
No Qualms About QAM 15

CHAPTER 3: **Tapping into Unlicensed Spectrum** 17

Giving a “High 5(G)” to Wi-Fi Advancements 17
LTE in Unlicensed Spectrum 18
License Assisted Access 19
MulteFire 20

CHAPTER 4: **Enabling Massive IoT** 21

Key Connectivity Requirements for IoT Devices 21
NarrowBand IoT (NB-IoT) 22
Long Term Evolution for Machines (LTE-M) 23
LoRaWAN and Sigfox 23

CHAPTER 5: **Getting Real About the Need to Virtualize** 25

Driving 5G and IoT with Virtualization 25
  Recognizing the IoT explosion 26
  Focusing on service 26
  Managing the migration 30

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

Virtualizing Network Components ... 30
  Virtual EPC (vEPC) ... 30
  Centralized Radio Access Network (C-RAN) ... 31
  Mobile Edge Computing (MEC) ... 31

CHAPTER 6: Creating a New 5G World Order with New Radio (NR) ... 33

5G NR Basics ... 33
More Spectrum — mmWave Bands ... 35

CHAPTER 7: Exploring 5G Use Cases ... 37

Fixed Wireless Broadband Service ... 37
Entertainment Everywhere ... 38
Virtual Reality (VR) and Augmented Reality (AR) ... 39
Connected and Autonomous Vehicles ... 40
The Connected World ... 41
Augmented Humans ... 42

CHAPTER 8: Ten Myths About 5G — Debunked ... 43

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

Introduction

The next-generation mobile network (NGMN) is on the horizon. 5G, the next iteration of 4G Long Term Evolution (LTE) networks, will enable significantly greater mobile speeds — as much as 20 gigabits per second (Gbps) with less than one millisecond (ms) latency — to enable real-time connectivity for mission-critical and potentially lifesaving devices and applications. 5G will also provide truly ubiquitous connectivity in the most challenging and remote areas of the world whether on land, in the air, or at sea — even on the 42nd floor of an office building in downtown Chicago! Finally, 5G networks will connect billions of Internet of Things (IoT) devices with a wide variety of speed and data volume requirements.

But 5G is an ambitious goal. Work on key technologies to enable 5G has already begun. In much the same way that 4G LTE was rolled out in 2008, but is only now achieving the 4G LTE goal of 1 Gbps speeds with the 4G LTE Advanced standard, 5G will be a steady evolution that begins with commercial availability expected in 2020. Many technologies that have emerged in the evolution of 4G LTE, such as carrier aggregation (CA) and multiple input multiple output (MIMO), will continue to develop to achieve the massive speed and scale required in 5G. Innovative new technologies will leverage unlicensed spectrum — where Wi-Fi operates — to offload certain traffic from the carrier networks to create more capacity in their data pipes. Low-power technologies such as NarrowBand IoT (NB-IoT), LTE for Machines (LTE-M), Long Range Wide Area Network (LoRaWAN), Sigfox, and others, will be used in billions of IoT devices, and a new radio interface technology — 5G New Radio (5G NR) — will be developed for connections between User Equipment (UE) and carrier enhanced Node B (eNodeB) stations. Finally, carriers will fully embrace virtualization technologies in their core networks to enable massive scale and efficiency.

In this book, you learn about the technological innovations that are being developed today to enable a 5G future. You also learn about potential use cases that will transform entire businesses and industries, and create new business models and opportunities.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

About This Book

5G For Dummies, Ixia Special Edition, consists of eight short chapters that explore

- How wireless communications technology has evolved and where it's going next (Chapter 1).
- How developments in today's networks are blazing the 5G trail to higher speeds (Chapter 2).
- Which technologies in unlicensed spectrum will be leveraged in the 5G networks of the future (Chapter 3).
- Why the Internet of Things requires 5G connectivity (Chapter 4).
- Where virtualization in mobile networks can help address the need for scale and elasticity (Chapter 5).
- What 5G New Radio (5G NR) is and how it will help create a 5G future (Chapter 6).
- How 5G will be used in various use case scenarios (Chapter 7).
- Ten common myths and the reality of 5G (Chapter 8).

Foolish Assumptions

It's been said that most assumptions have outlived their uselessness, but we assume a few things nonetheless!

Mainly, we assume that you either work in a technology profession or you're an avid user of wireless communications technology — if you have a smartphone within arm's distance of you, we're talking about you!

Beyond a basic knowledge of wireless communications and mobile technology in general, we don't assume you have a particularly strong technical background. As such, this book is written primarily for nontechnical readers — we explain any technical terms and concepts that come up in this book.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

If any of these assumptions describe you, this book is for you! If none of these assumptions describe you, keep reading anyway. It's a great book, and when you finish reading it, you'll know enough about 5G to be dangerous!

Icons Used in This Book

Throughout this book, we occasionally use special icons to call attention to important information. Here's what to expect:

REMEMBER

This icon points out information you should commit to your non-volatile memory, your gray matter, or your noggin' – along with anniversaries and birthdays!

TECHNICAL STUFF

You won't find a map of the human genome here, but if you seek to attain the seventh level of NERD-vana, perk up! This icon explains the jargon beneath the jargon.

TIP

Tips are appreciated, never expected — and we sure hope you'll appreciate these tips! This icon points out useful nuggets of information.

Beyond the Book

There's only so much we can cover in 48 short pages, so if you find yourself at the end of this book thinking "gosh, this is a great book; where can I learn more?" just go to `www.ixiacom.com`.

Where to Go from Here

With our apologies to Lewis Carroll, Alice, and the Cheshire cat:

"Would you tell me, please, which way I ought to go from here?"

"That depends a good deal on where you want to get to," said the Cat — er, the Dummies Man.

"I don't much care where . . . ," said Alice.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

"Then it doesn't matter which way you go!"

That's certainly true of *5G For Dummies*, which, like Alice in Wonderland, is also destined to become a timeless classic!

If you don't know where you're going, any chapter will get you there — but Chapter 1 might be a good place to start! However, if you see a particular topic that piques your interest, feel free to jump ahead to that chapter. Each chapter is written to stand on its own, so you can read this book in any order that suits you (though we don't recommend upside down or backward).

We promise you won't get lost falling down the rabbit hole!

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

IN THIS CHAPTER

- **Recapping a century of innovation in wireless communications**
- **Addressing speed, scale, and responsiveness with 5G networks**
- **Unlocking the five key fundamentals of 5G**

Chapter 1

Understanding the Journey to a 5G Future

In this chapter, you take a glimpse back at the evolution of wireless communications and a look ahead to the 5G future.

Tracing the Evolution of Wireless Communications

For more than a century, radio technology has been enabling wireless communications over ever greater distances and with ever greater capabilities.

In the late nineteenth century, Guglielmo Marconi built the first wireless telegraphy system, capable of transmitting Morse code via radio signals up to one-half mile. Today, more than seven billion mobile devices enable us to communicate with anyone, anywhere in the world.

The first truly mobile two-way radio was developed in 1923 and used in Australian police cars — although it took up the entire back seat of a patrol car. Hand-held radios — "walkie-talkies" — were first used in World War II.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

In 1973, the first call on a hand-held cellular phone was made — the cellular phone was described as a "brick" weighing nearly two pounds, with just 30 minutes of talk time and a ten-hour battery recharge time. Ten years later, Motorola introduced the DynaTAC phone, weighing just one pound and costing $3,500.

To support modern wireless communications, cellular networks have evolved over several generations, as follows:

- **1G (analog cellular):** The first analog cellular service was launched in Japan in 1979. In 1983, the Advanced Mobile Phone Service (AMPS) was launched in North America. Analog cellular signals permitted only voice traffic and were not encrypted, so they could be easily intercepted.

  TECHNICAL STUFF

  1G service consumed lots of spectrum and used the frequency division multiple access (FDMA) channel access method. FDMA allocates one or more frequency bands (or channels) to a user for communication.

- **2G (digital cellular):** The second generation of cellular technology was launched in 1991 with the commercial release of the Global Standard for Mobile Communications (GSM) in Finland. Major innovations in 2G networks included:
  - **Digital:** Digital signals generally have less static and background noise, and they use available spectrum more efficiently than do analog signals.
  - **Encryption:** 2G digital calls can be encrypted to make eavesdropping and intercept more difficult.
  - **Data:** Short message service (SMS) text messages were first introduced in 2G networks — O-M-2G!

  TECHNICAL STUFF

  2G technologies use either time division multiple access (TDMA) or code division multiple access (CDMA) channel access methods. TDMA divides a signal into different time slots, enabling multiple callers to share the same frequency channel. CDMA assigns a code to each caller and uses spread-spectrum technology to create a signal with a wider bandwidth.

  In 2000, the European Telecommunications Standards Institute (ETSI) created the General Packet Radio Service (GPRS), which implemented packet-switched domains, in addition to existing circuit-switched domains. GPRS was

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

dubbed “2.5G” and had nothing to do with *Two and a Half Men,* introduced by CBS three years later.

- **3G (data driven):** Apple and Google brought smartphones to the masses with iPhones and Android devices, respectively, in the early 21st century. These powerful devices — and the mobile apps installed on them (including Global Positioning System or GPS, location-based services, and on-demand video) — created an insatiable appetite for faster download speeds. The first 3G networks, introduced in 1998, provided minimum information transfer rates of 200 kilobits per second (Kbps). The International Telecommunication Union (ITU) has never formally defined a standard for 3G data rates, so downlink data speeds vary widely — from 384 Kbps in a moving vehicle for Wideband Code Division Multiple Access (W-CDMA) to 42.2 megabits per second (Mbps) for Evolved High Speed Packet Access (HSPA+), also known as 3.5G, and 168 Mbps for Advanced HSPA+.
- **4G (Long Term Evolution):** Commercially available 4G mobile networks were rolled out in 2008, and 4G LTE followed in 2010. However, unlike 3G, the ITU Radiocommunication Sector (ITU-R) defined minimum 4G standards — but neither “4G” nor “4G LTE” meets those standards! The ITU-R International Mobile Telecommunications Advanced (IMT-Advanced) requirements include (among other things):
  - Packet-switched all-IP core networks
  - Peak data rates of approximately 100 Mbps for high mobility (such as moving vehicles)
  - Peak data rates of approximately 1 gigabit per second (Gbps) for low mobility (such as walking — or your authors sprinting)

  With the introduction of LTE Advanced, true 4G speeds of up to 1 Gbps finally arrived. LTE Advanced Pro is the next evolution of LTE technology, and it establishes the foundation for 5G. LTE Advanced Pro will deliver speeds in excess of 3 Gbps with less than 2 milliseconds (ms) of latency.

REMEMBER

At this point you may be thinking, “Long Term Evolution — no kidding! Will 5G ever get here?” However, the trend has been for each generation of mobile technology innovation to take about a decade — most of us just didn’t pay attention before we got our first smartphones midway through the 3G era.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

Focusing on the 5G Vision

The vision for the 5G future is bold: It is much more than just the next iteration of mobile networks. 5G will achieve three main goals:

- **Speed (ultra-high speed radio access):** 5G will provide download speeds of up to 20 Gbps. If you're wondering "Why would anyone ever need that much speed?" first answer this question: When have you ever heard anyone complain that their phone was *too fast*? It's also important to remember that bandwidth is shared by all the users on a cell tower. Today, if a few users are streaming a video at the airport or watching replays of a touchdown in a stadium, chances are that the download is choppy with lots of buffering, and the experience isn't so great. With 5G, you could theoretically download a 40 gigabyte (GB) 4K Ultra-High-Definition (UHD) movie (like *Jaws*) in less than a minute — you're gonna need a bigger data plan!
- **Responsiveness (ultra-low latency):** 5G networks will be used to control autonomous cars and high precision, mission-critical industrial devices in real-time. High reliability and availability at all times is a necessity for these use cases. For this to happen safely, end-to-end latency — the time it takes for data or commands to travel across the network — has to be extremely low. Latency in 5G networks will be five times faster than today's networks — less than 1ms.
- **Scale (massive connectivity):** By 2020, Gartner conservatively forecasts that there will be more than 21 billion connected devices in the Internet of Things (IoT). Some estimates predict more than 50 billion connected IoT devices by 2020. That's anywhere from three to seven connected devices for every person on the planet in 2020 — not including smartphones, tablets, and computers! These devices will have widely varying network requirements — from environmental sensors for agricultural applications installed in remote areas that might send a few bits of data every few days or weeks, to extremely high-precision, low-latency devices in nanobiotechnology, autonomous cars, and mission-critical industrial environments that rely on real-time communication for potentially lifesaving functions. 5G networks will need to handle the massive scale and

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

challenging connectivity requirements for all these diverse devices, sensors, and applications.

Ordering Up 5G in Five Easy Pieces

5G will be a quantum leap beyond today's networks and will require many technological innovations. We serve them up here in five easy pieces (easier than making wheat toast for Jack Nicholson — "hold the butter, the lettuce, the mayonnaise . . . and the chicken") in this section and the chapters that follow (see Figure 1-1):

- **Speeds and feeds.** Speeds of up to 20 Gbps will be achieved using a combination of innovations such as carrier aggregation (CA), massive multiple input multiple output (MIMO), and quadrature amplitude modulation (QAM). You learn about speeds and feeds in Chapter 2.
- **Unlicensed spectrum:** MNOs are increasingly using unlicensed spectrum in the 2.4 and 5 Gigahertz (GHz) frequency bands. 5G networks will need to tap into the vast amount of spectrum available in these unlicensed bands to offload traffic in heavily congested areas and provide connectivity for billions of IoT devices. Advancements in Wi-Fi, LTE in Unlicensed spectrum (LTE-U), License Assisted Access (LAA), and MulteFire, among others, provide better quality and regulated access to unlicensed spectrum. You learn about these advancements in Chapter 3.
- **Internet of Things (IoT):** IoT devices pose a diverse set of requirements and challenges for 5G networks. It's only fair that IoT should likewise pose a diverse set of solutions as well! You learn about a few of these solutions — including NarrowBand IoT (NB-IoT), LTE Category M1 (LTE-M), Long Range (LoRa) and Sigfox — in Chapter 4.
- **Virtualization:** Network functions virtualization (NFV) enables the massive scale and rapid elasticity that MNOs will require in their 5G networks. Virtualization enables a virtual evolved packet core (vEPC), centralized radio access network (C-RAN), mobile edge computing (MEC), and network slicing — all explained in Chapter 5.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

- **New Radio (NR):** Although the other 5G innovations introduced in this section all have strong starting points in LTE Advanced Pro, 5G NR is a true 5G native technology that has yet to be standardized. 5G NR addresses the need for a new radio access technology that will enable access speeds up to 20 Gbps — and you learn about it in Chapter 6!


Speeds and feeds
Unlicensed spectrum
Internet of Things (IoT)
Virtualization
New Radio (NR)

FIGURE 1-1: The five keys to 5G.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

IN THIS CHAPTER

- **Issuing a license to thrill — with higher speeds**
- **Cobbling together spectrum with carrier aggregation**
- **Going well beyond "rabbit ears" with massive antenna arrays**
- **Seeing stars with quadrature amplitude modulation**

Chapter 2

Achieving Faster Speeds and Larger Feeds

Over the past decade, the need for speed in mobile networks has increased dramatically. To address this need, 5G will increase the speeds of today's most advanced Long Term Evolution (LTE) networks by an order of magnitude — from a few gigabits per second (Gbps) to as much as 20 Gbps. In this chapter, you get a glimpse of the engine — or, more correctly, the parts and components of the engine — that will power the 5G networks of the future.

Fattening the Data Pipe

Wireless spectrum is limited and highly regulated throughout the world. The International Telecommunication Union (ITU) allocates frequency spectrum worldwide, and governing bodies within the respective countries then license that spectrum for use by individual mobile network operators (MNOs). The ITU has identified three International Telecommunication Regions

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

throughout the world with distinct frequency bands allocated to each region (see Figure 2-1).


Europe
800 MHz
900 MHz
1.8 GHz
1.9/2.1 GHz
2.5 GHz
North America
700 MHz
850 MHz
1.7/2.1 GHz
1.9 GHz
2.5 GHz
Africa and Middle East
450 MHz
800 MHz
850 MHz
900 MHz
1.8 GHz
1.9/2.1 GHz
2.5 GHz
Asia-Pacific
450 MHz
700 MHz
850 MHz
900 MHz
1.7 GHz
1.8 GHz
1.9/2.1 GHz
2.3 GHz
2.5 GHz
South America and Latin America
450 MHz
700 MHz
850 MHz
900 MHz
1.7/2.1 GHz
1.8 GHz
1.9 GHz
2.5 GHz
1
2
3

FIGURE 2-1: ITU International Telecommunication Regions and spectrum allocations.

MNOs must pay for the right to transmit and receive data using this shared medium in each country in which they operate. To fatten a wireless data pipe, an MNO must procure additional licenses to use a designated frequency spectrum.

In the U.S., the Federal Communications Commission (FCC) auctions spectrum to MNOs — and we aren't talking about eBay auctions here! In the U.S. alone, spectrum auctions have raised more than 60 billion dollars since 1994. Another challenge for MNOs is that available spectrum is limited and going once . . . going twice . . . sold!

Thus, MNOs must find new ways to use existing spectrum more efficiently. LTE Advanced and LTE Advanced Pro are pioneering the path to 5G, using several innovations to get more data through existing spectrum, including:

- Carrier aggregation (CA)
- Multiple input multiple output (MIMO)
- Quadrature amplitude modulation (QAM)

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

We All Bundle — with CA

As you might imagine, the process of buying and selling spectrum, over time, causes spectrum to be sliced and diced in some pretty creative ways. MNOs also come and go, or get merged, acquired, and divested (for example, Cingular Wireless and MCI). All of this causes yet another challenge — contiguous spectrum is hard to find and MNOs must cobble together different bands to maximize their available bandwidth. It's sort of like a business being so unreasonable as to want a continuous range of direct inward dialing (DID) phone numbers to simplify its phone switch programming, company directories, and business cards! Except that in the case of frequency spectrum, non-contiguous bands aren't just a messy inconvenience — they limit available bandwidth.

For LTE networks, including LTE Advanced and LTE Advanced Pro, four carrier bandwidths (or sizes) are available for transporting data:

- 5 megahertz (MHz)
- 10 MHz
- 15 MHz
- 20 MHz

Larger bandwidths can transport more data. For example, 10 MHz can transport data at 37.5 megabits per second (Mbps) and 20 MHz can transport data at 75 Mbps. These data transfer rates assume a single antenna on the user equipment (UE) side and on the Evolved Node B (eNodeB) side. This is known as single input single output (SISO).

TECHNICAL STUFF

User equipment (UE) refers to an end-user device in a mobile network, such as a smartphone. *Evolved Node B (eNodeB)* is the MNO hardware — for example, a base transceiver station (BTS) — that wirelessly communicates directly with the UE.

Carrier aggregation (CA) is a technique that allows an MNO to use more than one component carrier (CC) — known as the *secondary carrier* — as an additional data pipe. For example, 2CA enables any of the four carrier bandwidths (5, 10, 15, or 20 MHz) to be used as the primary carrier and any of the other four carrier bandwidths to be used as the secondary carrier.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

In the simplest deployment scenario, known as *intra-band contiguous CA*, a 20 MHz primary and a 20 MHz secondary carrier (totaling 40 MHz) would provide twice the maximum possible bandwidth and throughput of a single carrier.

For SISO, a 2CA of 20+20 MHz would provide 150 Mbps of data throughput.

TIP

MNOs in the U.S. are currently deploying 3CA and some are already moving to 4CA (see Figure 2-2). The challenge for MNOs now is to find three or more CCs that they own the license to operate in and can aggregate. The LTE Advanced standard specifies 5CA totaling 100 MHz, while LTE Advanced Pro calls for 32CA totaling 640 MHz of aggregated carrier bandwidth.



FIGURE 2-2: Carrier aggregation (CA) increases available bandwidth and data throughput.

Eeny, Meeny, Miny, MIMO

One of the techniques for fattening the data pipe defined from day one in 4G LTE networks is multiple input multiple output (MIMO) — using multiple antennas on the transmit and receive side in the wireless network. Using a technique called *spatial multiplexing*, it's possible to send a different data stream on each antenna, thereby increasing the throughput to the cell tower and to the user device.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

While 2x2 MIMO deployments (two antennas in, two antennas out) are common today, 4x4 MIMO (four antennas in, four antennas out) is becoming more practical. 4x4 MIMO effectively enables four independent data streams, thereby increasing the throughput by four times. Thus, the 2CA deployment example (described in the previous section) with two 20 MHz channels and a 2x2 MIMO configuration would increase the data throughput from 150 Mbps to 300 Mbps. The same scenario with a 4x4 MIMO configuration would theoretically increase data throughput to 600 Mbps.

LTE Advanced specifications for MIMO accommodate 8-, 16-, and 32-antenna configurations. LTE Advanced Pro specifications increase MIMO configurations to 64 antenna elements. Realistically, using 64 antenna streams to increase the throughput of a single UE isn't practical. However, using a technique called *beamforming,* the eNodeB can focus energy (that is, steer beams of data) to a particular UE, thereby increasing the throughput of that UE while simultaneously handling other UEs through a different set of beams. Massive MIMO will utilize massive antenna arrays — comprised of hundreds of antennas — to provide efficient signal coverage and higher data rates with lower latency in 5G networks.

No Qualms About QAM

Quadrature amplitude modulation (QAM) is a technique widely used to vary data signals on a carrier used for radio communication. When used for digital transmission of radio communication applications, QAM can carry higher data rates than ordinary amplitude modulated and phase modulated schemes. In QAM, the constellation points are normally arranged in a square grid with equal vertical and horizontal spacing. As a result, the most common forms of QAM use a constellation with the number of points equal to a power of 2 (such as 4, 16, and 64). Thus, 16-QAM uses a 16-point constellation while 256-QAM uses a 256-point constellation.

By using higher order modulation formats (that is, more points on the constellation), it is possible to transmit more bits per symbol. So, 64-QAM has six bits per symbol (more data transmitted), whereas 16-QAM uses only four bits per symbol (less data transmitted). However, the points for a higher QAM are closer together and are therefore more susceptible to noise and data errors. 256-QAM has been used for data in digital cable

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

communications and is now starting to be used for radio communications. 256-QAM is included as part of the LTE Advanced Release 12 standard from the Third Generation Partnership Project (3GPP) because it is likely to work with small cell towers. T-Mobile has achieved 400Mbps downlink speeds in trials through a combination of 4x4 MIMO and 256-QAM.

REMEMBER

5CA and beyond, massive MIMO, and higher-order QAM are all techniques defined as part of the LTE Advanced and LTE Advance Pro standards. With LTE Advanced deployments in full swing, 1 Gbps download speeds are getting closer to becoming a reality in operational networks. 5G will use all these techniques to achieve 20 Gbps data speeds. For example, these are a few of the developments on the 5G horizon:

- CA on very large bandwidths, leading to aggregate totals of 800 MHz (and even 1 GHz) carrier bandwidth
- Massive MIMO antenna arrays of 128 elements or more
- 1024-QAM, and even 4096-QAM

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

IN THIS CHAPTER

- **Expanding cellular traffic to unlicensed spectrum**
- **Getting LTE-U and LAA to coexist with Wi-Fi in unlicensed spectrum**
- **Going it alone in unlicensed spectrum with MulteFire**

Chapter 3

Tapping into Unlicensed Spectrum

Unlicensed spectrum is used by low-power devices to transmit and receive wireless signals over short distances — typically a few meters. Although specific devices are permitted to operate only in specific bands, the process of getting certifications is not time-consuming or costly, compared to getting a cellular operator license. Some common devices in this category include garage door openers, nursery monitors, home security systems, cordless phones, and Bluetooth speakers/headsets. In this chapter, you learn about the role of unlicensed spectrum in the 5G future.

Giving a "High 5(G)" to Wi-Fi Advancements

Wi-Fi operates in the unlicensed 2.4 gigahertz (GHz) and 5 GHz spectrums. There are fewer rules on who can access these bands and more available spectrum compared to licensed frequency bands. Wi-Fi devices must therefore compete to use the same spectrum as other devices.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

Over the past few years, improvements in speed and the advancement of new capabilities have made Wi-Fi viable (and lucrative) for many mobile network operators (MNOs).

MNOs now regularly use Wi-Fi to offload their cellular networks wherever possible. Newer Wi-Fi standards enable massive speed increases. The standards utilize many of the latest multiple input multiple output (MIMO) beamforming techniques and higher quadrature amplitude modulation (QAM) schemes as those used in the licensed spectrum (discussed in Chapter 2).

For example, 802.11ac delivers Wi-Fi speeds of up to several gigabits per second (Gbps) operating in the 5 GHz band, using 80 or 160 megahertz (MHz) wide channels, advanced beamforming techniques, eight spatial streams (MIMO), multi-user MIMO (MU-MIMO), and 256-QAM (which produces four times the spectral efficiency of the previous 802.11n Wi-Fi standard).

The next wave in Wi-Fi is 802.11ax. 802.11ax will use orthogonal frequency-division multiple access (OFDMA) — the same technique used in Long Term Evolution (LTE) networks — in which different subcarriers within a carrier can be used to transport data for different users. As a result, more than one user equipment (UE) device can access the same medium at a given instant without having to back off or concede the medium to another UE device.

TIP

In case you're wondering, other standards exist between 802.11ac and 802.11ax, but they define Wi-Fi standards in unlicensed spectrum other than 2.4 GHz and 5 GHz — and they don't sound as cool as "A-X"!

LTE in Unlicensed Spectrum

LTE in Unlicensed spectrum (LTE-U) is a proposal that was originally developed by Qualcomm for LTE to co-exist with Wi-Fi in shared unlicensed spectrum. In LTE-U, calls are initially set up using licensed LTE spectrum. Additional carriers (for data) can then be aggregated from the unlicensed spectrum. This method will allow the operators to use unlicensed spectrum to "fatten the data pipe."

The Wi-Fi Alliance developed a Wi-Fi co-existence test plan to ensure that Wi-Fi and LTE could peacefully co-exist, and MNOs (including T-Mobile, AT&T, and Verizon) began experimenting with unlicensed spectrum in addition to their licensed spectrum.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

LTE-U has also generated a lot of interest from a small cell perspective because this approach potentially makes small cells a viable alternative to Wi-Fi hot spots.

As you might imagine, strong reservations about LTE-U exist, because of concerns that it will unfairly use the unlicensed spectrum and potentially interfere with other Wi-Fi users. Cable companies, such as Comcast, Charter Communications, and Time Warner Cable (TWC), as well as Google and Microsoft, are opposed to LTE-U. As of February 2017, the U.S. Federal Communications Commission (FCC) has approved Ericsson and Nokia equipment as LTE-U certified.

License Assisted Access

Unlike LTE-U, License Assisted Access (LAA) is a standard defined in the Release 13 specification from the Third Generation Partnership Project (3GPP). LAA attempts to resolve contention issues with Wi-Fi in unlicensed spectrum using a protocol many of us learned as children — Listen Before Talk (LBT). The LBT contention protocol requires LAA to listen to the unlicensed channel first, and then, if there is no other active Wi-Fi user (the channel is silent), the LTE user can use the channel.

TIP

A recent report by Strategy Analytics states that only 16 percent of operators can achieve gigabit LTE without using unlicensed spectrum. Using LTE-U and LAA, 64 percent of operators can achieve gigabit LTE.

Qualcomm's over-the-air trials with Deutsche Telecom in Germany showed that LAA had increased coverage and capacity compared to Wi-Fi on the same spectrum. By respecting the LBT maxim (uh, protocol), the behavior of LAA is more closely modeled to the principle "love thy neighbor" and is a better neighbor to Wi-Fi than Wi-Fi is to LTE. Wi-Fi was more of an imp during its formative years and ignores LBT, trying to access the same medium at the same time as others.

Enhanced LAA (eLAA), which aggregates the uplink on unlicensed spectrum, is the next step in the evolution of LAA. eLAA will be defined in the 3GPP Release 14 specification.

REMEMBER

Both LAA and eLAA require the initial call to be set up on LTE licensed spectrum as the primary channel. Unlicensed spectrum is only used to "fatten" the data pipes.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

MulteFire

MulteFire goes beyond LTE-U and LAA by enabling the LTE primary channel on unlicensed spectrum. In fact, MulteFire uses unlicensed spectrum exclusively. This means MulteFire can be deployed for LTE by anyone — without owning licensed spectrum — such as Internet service providers (ISPs) and commercial enterprises. MulteFire also benefits MNOs by providing new deployment opportunities for offloading and augmenting their cellular networks.

In January 2017, the MulteFire Alliance released version 1.0, defining an LTE-like network that can run entirely on unlicensed spectrum and, in some cases, may be an alternative to Wi-Fi with more capacity, better security, and easier handoffs across carrier networks.

REMEMBER

Today's 4G spectrum has around 500 MHz of unlicensed spectrum available to deploy LTE-U, LAA, and MulteFire. In July 2016, the FCC opened up 5G spectrum in the U.S., which has 10.85 GHz of total spectrum (3.85 GHz of licensed spectrum and 7 GHz of unlicensed spectrum). The techniques that are now evolving in LTE Advanced Pro (Releases 13 and 14) — LTE-U, LAA (and eLAA), MulteFire, and others (see Figure 3-1) — will be vital as even more unlicensed spectrum becomes available in 5G. The key goal will be to provide users with a seamless experience, irrespective of whether they are operating on a licensed or unlicensed band.



FIGURE 3-1: Leveraging licensed and unlicensed spectrum.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

IN THIS CHAPTER

- **Defining IoT connectivity requirements**
- **Handling massive scale with NB-IoT**
- **Slicing up spectrum for the rise of the machines**
- **Exploring LoRaWAN and Sigfox for low-power networks**

Chapter 4

Enabling Massive IoT

When 4G networks were introduced in 2008, there were close to 700 million mobile subscribers worldwide. Today, there are more than 7 billion mobile subscribers worldwide. By 2020, according to the most conservative estimates, there will be approximately 20 billion Internet of Things (IoT) devices, in addition to the 9 billion mobile subscribers that are expected worldwide.

Thus, 5G networks must not only deliver extreme speeds and feeds, they must provide massive scale, predictability, and reliability to eventually support as many as a trillion connected devices, including mission-critical and potentially lifesaving applications and scenarios. In this chapter, you learn about the key requirements for IoT device connectivity and the innovations that are being developed to support IoT.

Key Connectivity Requirements for IoT Devices

Unlike smartphones and other cellular devices, IoT device communications can be sporadic in nature. Many of these devices "sleep" (to extend battery life for ten or more years in some cases)

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

for long periods of time — hours, days, or weeks — before transmitting a few bytes of data, and thus needn't always be connected to the network. 5G networks must be designed to handle infrequent, but important communications from these types of IoT devices. Although the amount of data these devices send may be significantly lower, they may still be of a time-critical nature. For example, a sensor that detects a hazardous condition may instruct an Evolved Node B (eNodeB) element to shut down equipment in an industrial plant or building. These types of communication, though extremely rare, must be handled with the utmost responsiveness and reliability.

Additionally, eNodeB elements will require massive capacity to scale to support tens of thousands of IoT devices — all with different communications requirements and characteristics — in a single cell.

Finally, a wide variety of security threats and new attack vectors will be surfaced in IoT devices. Unlike many of today's threats — identity theft and credit card fraud, for example — many IoT security threats will be potentially life threatening. Future threats may include hacked control systems in autonomous vehicles and smart grids, or compromised medical devices such as insulin pumps and pacemakers. Thus, 5G technologies will need to provide secure end-to-end communications throughout the network.

NarrowBand IoT (NB-IoT)

The Third Generation Partnership Project (3GPP) Long Term Evolution (LTE) Advanced Pro Release 13 specification defines a new standard — NarrowBand IoT (NB-IoT) — for handling low volumes of data (similar to 2G) from tens of thousands of devices in a single cell (tower, not amoeba).

NB-IoT extends LTE to even narrower bandwidths optimized for low data rate, latency-tolerant IoT applications. NB-IoT reduces device complexity, enables multiyear battery life, and provides deeper coverage to reach sensors in challenging locations, such as remote rural areas or inside buildings.

Perhaps one of the most attractive features of NB-IoT is its ability to leverage already ubiquitous LTE networks, in addition to providing high quality of service (QoS) and comprehensive security.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

NB-IoT can be deployed in three different modes:

- **Standalone as a dedicated carrier:** Can use GSM frequencies in a bandwidth of 200 kHz. This does not require LTE.
- **Guard band:** Uses a free resource block within the LTE guard band. This allows the IoT devices to not compete with other LTE devices for the resource blocks within the carrier.
- **LTE in-band:** Uses a resource block within the LTE frequency band. The rest of the blocks are used by the regular LTE devices.

Long Term Evolution for Machines (LTE-M)

Like NB-IoT, Long Term Evolution for Machines (LTE-M or LTE Category M1) leverages a narrow slice of existing LTE spectrum to send and receive data for IoT devices. LTE-M has the same benefits as NB-IoT, but uses a larger network slice than NB-IoT (1.4 MHz compared to 180 KHz in NB-IoT) and leverages the LTE protocol more than the NB-IoT in terms of reusing the same control, data, and transport channels.

TIP

Verizon launched the first LTE-M network in the U.S. on March 31, 2017, and ATT Wireless was expected to follow shortly after.

LoRaWAN and Sigfox

Long Range Wide Area Network (LoRaWAN) is a Low Power Wide Area Network (LPWAN) specification for wireless, battery-operated IoT devices. LoRaWAN operates in the sub-1 GHz unlicensed spectrum band. This limits the volume and frequency of traffic, as well as the ability of the base station to control the network and send traffic down. However, LoRaWAN has great advantages in terms of battery life and cost, and communication is bi-directional.

Sigfox is a French company that created a technology similar to LoRaWAN for IoT device communication. Sigfox technology uses

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

very low bandwidth connections. It is not bi-directional and is only used for sending sparse uplink data with very limited downlink. Like LoRaWAN, Sigfox operates in the sub-1 GHz space and thus uses very low power.

LoRaWAN and Sigfox will be used with certain types of sensors, smart meters, and other low data IoT devices. A disadvantage for these technologies is that, unlike NB-IoT, which is built on top of existing LTE infrastructure, LoRaWAN and Sigfox are not integrated with LTE. However, the cost of deploying a LoRaWAN or Sigfox based IoT device is far less than for an NB-IoT or LTE-M device — by an order of magnitude, since NB-IoT and LTE-M devices must integrate LTE modules into their devices.

REMEMBER

As countries and mobile network operators (MNOs) make IoT technology decisions, it is likely that many standards, protocols, and technologies will need to co-exist. Factors such as cost, coverage, battery life, and integration with older 4G networks will determine which standards, protocols, and technologies are best for each use case.

The 3GPP specifications for IoT technologies are just starting to come out as part of the LTE-A Pro standards. Many IoT devices will need to operate at very low power, ideally suited for sub-1 GHz spectrum rather than the millimeter wave (mmWave) spectrum (discussed in Chapter 6). That said, there are some compelling 5G techniques, like resource spread multiple access (RSMA) waveforms that allow grant-free transmissions for "things" to send their data without prior scheduling by the eNodeB. As a result, the scheduling algorithm becomes less complex. 5G will also enable multi-hop mesh for these low-power devices, allowing out-of-coverage devices to relay to other connected devices in order to send data to the eNodeB.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

IN THIS CHAPTER

- Virtualizing the network for 5G and IoT
- Knowing which network elements to virtualize

Chapter 5

Getting Real About the Need to Virtualize

Virtualization has been a hot topic in the technology industry for many years and its advantages transcend the cellular industry. In this chapter, you learn about the network elements that can be virtualized and the essential role of virtualization in 5G.

Driving 5G and IoT with Virtualization

Telecommunications companies and mobile network operators (MNOs) have invested heavily in their 4G and Long Term Evolution (LTE) networks. These organizations have embraced virtualization to enable faster, more agile, and scalable deployments that can keep pace with the explosion in subscriber data traffic and consumption, all while keeping control of their overall capital and operating costs. Even though these investments have already given users mobile connectivity of unprecedented speed and pervasiveness, they have only laid the foundation of what's to come, as 5G and smart, connected devices start to roll out.

A recent study by a division of Nokia Bell Labs provides a glimpse of what's coming. The study found that the number of Internet of Things (IoT) connected devices is expected to expand from 1.6 billion in 2014 to well over 20 billion by 2020. Also, by 2020, global consumption demand for digital content and services on portable devices will see an average increase of 30 to 45 times the

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

levels seen in 2014. Thus, MNOs will need to further accelerate their technology investments to meet ever-increasing consumer and business connectivity demands.

Recognizing the IoT explosion

Although MNOs in the U.S. are starting to embrace "pre-standard" 5G, vying for the first mover's advantage, the standards are not expected until 2018. This has echoes of the early days of 3G in the late 1990s and early 2000s, before proprietary implementations were standardized. It isn't surprising that some operators in the U.S. have already announced their plans to deploy 5G later this year, and some of the early adopters in Korea, Japan, and China are also ready to roll out 5G. Because of the rapid deployment, many 5G concepts are being solidified quickly.

5G is sometimes narrowly classified as a higher bandwidth radio access technology. But it is much more than that. It will also be the network for low-power devices and sensors that are classified as IoT devices, as well as low-latency applications. One example is the low latency required for some mission-critical devices, such as autonomous vehicles. The need for low latency will dictate that key LTE base station functions are distributed, with some moving closer to the edge and others being pooled in the cloud.

Another example is that vertical sectors will require different types of services from the 5G network. Some will need high bandwidth, while others will need low power. Some will need very low latency, and others will need very high availability. The vast volume of IoT devices will range from those that send multiple gigabits of data per second to those that will only send a few bits every month. This flexibility and elasticity can be supported only by advanced network virtualization.

Focusing on service

To support such varying 5G use cases across multiple verticals, MNOs need to shift from being network-centric to being more service-oriented.

To understand this shift, consider the concept of network slicing (see Figure 5-1). Here are a few typical cases:

- Mobile broadband with higher bandwidth video requiring high availability everywhere

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

- Low-power sensors that can operate on a pair of AA batteries for 10 years
- Autonomous vehicles that can zip through crowded city streets but brake within microseconds when they sense potential obstructions in their paths

TECHNICAL STUFF

Each of these scenarios requires a different configuration of the requirements and parameters in the network, potentially including:

- Home Subscriber Server (HSS)
- Mobility Management Entity (MME)
- User equipment (UE)
- Enhanced Node B (ENB or eNodeB)
- Serving Gateway (SGW)
- Packet Data Network Gateway (PGW)
- Policy and Charging Rules Function (PCRF)
- LTE Evolved Packet Core (EPC) interfaces (S1-MME, S11, S1-U, SGi)

In essence, each use case requires its own network slice. Networks must be built in a manner that allows speed, availability, capacity, and coverage to be allocated in logical slices to meet the demands of each use case.

The best way to implement network slices will be via virtualization — to use service provider software-defined networking (SDN), network functions virtualization (NFV), and network orchestration (see Figure 5-2). In each of these cases, the SDN controller will configure and build network slices that include service chains such as deep packet inspection (DPI), emails, and security scans per user or per service. The network services — including the Centralized Radio Access Network (C-RAN), Virtual Evolved Packet Core (vEPC), and Virtual IP Multimedia Subsystem (vIMS) — are virtualized as virtual network functions (VNFs) that allow MNOs to set up services rapidly, and scale them in response to network and service demands.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.


High-bandwidth slice
4K video
Enhanced mobile broadband
Edge
5G User Plane
Core
HSS
PCRF
5G Control Plane
MME
xGW
IoT slice
IoT devices
Massive scale
Lightweight Core
HSS
PCRF
5G UP + CP
MME
xGW
Low-latency slice
Autonomous vehicles
Latency
Edge
HSS
PCRF
5G UP + CP
MME
xGW

FIGURE 5-1: 5G network slices.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.


High-bandwidth slice
4K video
Enhanced mobile broadband
Edge
5G User Plane
Core
HSS
PCRF
5G Control Plane
MME
xGW
IoT slice
IoT devices
Massive scale
Lightweight Core
HSS
PCRF
5G UP + CP
MME
xGW
Low-latency slice
Autonomous vehicles
Latency
Edge
HSS
PCRF
5G UP + CP
MME
xGW
Orchestration
SDN
C-RAN
vEPC
vIMS

FIGURE 5-2: Network slices, VNFs, and management and orchestration in a 5G architecture.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

Managing the migration

Thus, virtualization will be a vital piece of the puzzle as 5G is rolled out and the IoT grows. But the speed and agility that virtualization enables must be balanced against the need for network visibility, resilience, manageability and security, throughout the development, roll-out, and mass usage of each service.

MNOs and service providers must weigh the trade-offs between

- Quality and cost.
- Flexibility and control.
- Moving too quickly and not moving fast enough.

REMEMBER

As a result, the demand for simple, end-to-end solutions that can efficiently test and validate the effectiveness and benefits of virtualization at every stage is only going to increase. Network virtualization will be a key driver of the IoT ecosystem as it develops — and full-lifecycle reliability and performance testing will be a key element of this shift.

Virtualizing Network Components

When LTE networks were conceptualized, one notable difference from earlier 3G architectures was the idea of a central “brain” — the evolved Node B (eNodeB). From the eNodeB — the point at which the cellular network wirelessly connects directly to user equipment (UE) — to the Internet, the connectivity would all be Internet Protocol (IP) based.

When data centers and other wired network components (such as routers, switches, and firewalls) started being virtualized on standard off-the-shelf servers, it was only natural for the wireless, IP-based 4G evolved packet core (EPC) to follow.

Virtual EPC (vEPC)

Because packet gateways, policy servers, and subscriber databases are all IP-based in the LTE network, the EPC is an excellent

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

candidate for replacing proprietary hardware with virtualized functions hosted on standard, off-the-shelf servers. The benefit for MNOs is the elasticity this model enables — no more dedicated hardware and no need to oversubscribe every part of the network. Servers can be quickly and easily provisioned or de-provisioned based on real-time subscriber capacity needs. With SDN controllers and EPC functions migrated to NFV, and orchestration schemes added to manage it all, the wireless core could be fully virtualized and cloud ready!

Centralized Radio Access Network (C-RAN)

Virtualization in the radio access network (RAN) requires separating out latency-sensitive elements and the radio itself, then pooling the rest of the baseband functions into centralized baseband units (BBUs). Which functions should stay with the remote radio head (RRH) and which ones should move to centralized BBUs has been extensively studied, and a few options exist.

The C-RAN model, which requires a fiber connection between the RRH and the BBUs, is popular in some regions of the world, such as China and Korea. This front-haul interface is challenging because it has distance limitations and is bandwidth limited. It uses a protocol known as the Common Public Radio Interface (CPRI). China Mobile has been in the forefront of the C-RAN architecture. Other countries such as Japan and Korea have also adopted C-RAN. In the U.S., Verizon is looking at implementing C-RAN for small cells.

Mobile Edge Computing (MEC)

Mobile Edge Computing (MEC) offers an important balance as cellular networks move to a central model. MEC allows certain latency-sensitive components to be moved to the network edge. For example, even though it may make business sense for MNOs to centralize several functions into VNFs running on standard off-the-shelf servers, some critical functions may need to be

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

closer to the edge of the network to ensure high availability, low latency, and higher levels of security.

TIP

The network edge is also a good place to host application servers that require local context. For example, if you are driving around and you receive restaurant ads on your mobile device based on your current location, you need the application service to be close to the edge to avoid a lengthy delay in the app that could render the information obsolete.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

IN THIS CHAPTER

- **Tuning in to the basic functions of 5G New Radio**
- **Catching the millimeter wave**

Chapter 6

Creating a New 5G World Order with New Radio (NR)

In this chapter, you learn about a completely new technology that creates the foundation for 5G — the 5G New Radio (NR) physical air interface.

5G NR Basics

Unlike the other 5G elements (covered in previous chapters), that advance the industry toward the goals of 5G networks, 5G New Radio (NR) is not an evolution of 4G Long Term Evolution (LTE) innovations. 5G NR is a completely new technology specification — a physical air interface — that is required to achieve the extreme bandwidth, low latency, and massive scalability requirements of 5G.

REMEMBER

The other four areas of 4G LTE innovation that are being further developed for 5G include:

- **Speeds and feeds:** Discussed in Chapter 2, innovations such as carrier aggregation (CA), massive multiple input multiple output (MIMO), and quadrature amplitude modulation (QAM), among others, enables carriers to "fatten" the data pipe.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

- **Unlicensed spectrum:** Discussed in Chapter 3, LTE in unlicensed spectrum (LTE-U), License Assisted Access (LAA and enhanced LAA, or eLAA), and MulteFire enable carriers to leverage unlicensed spectrum as additional data pipes.
- **Internet of Things (IoT):** Discussed in Chapter 4, IoT developments include NarrowBand IoT (NB-IoT), LTE for Machines (LTE-M or LTE Category M1), and Low Power Wide Area Network (LPWAN) specifications such as Long Range WAN (LoRaWAN) and Sigfox. These developments enable wireless communication with a diverse array of billions of IoT devices.
- **Virtualization:** Discussed in Chapter 5, software-defined networking (SDN) and network functions virtualization (NFV) enable mobile network operators (MNOs) to achieve cost-effective scalability and elasticity in their core networks with innovations that include network slicing, virtual evolved packet core (vEPC), centralized radio access network (C-RAN), and mobile edge computing (MEC).

The 5G NR specification enables the following goals of 5G:

- **Extreme bandwidths:** 5G NR aggregates eight component carriers (CCs). The carrier width specifications are still in development, but will likely be 100 megahertz (MHz) or greater, providing a total of approximately one gigahertz (GHz) of aggregated bandwidth — wide enough to carry 20 gigabits of data per second.
- **Low latency:** In LTE Advanced, each subframe (there are 10 subframes) is handled in one millisecond (ms). 5G will be five to ten times faster — each subframe is handled in 100 to 200 microseconds (μs). 5G NR will use new channel coding techniques, such as low density parity check (LDPC), that are more efficient than existing techniques, resulting in shorter transmission time intervals (TTIs).

  TECHNICAL STUFF

  A technique called *scalable orthogonal frequency-division multiplexing (OFDM) numerology* will be used to support different use cases and scenarios within the same frame. Effectively, shorter TTIs will be used for low latency, high reliability use cases, and longer TTIs for higher spectral efficiency, higher bandwidth use cases. 5G NR can also effectively multiplex between short and long TTIs, thereby allowing a diverse set of users to simultaneously use the system.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

- **Massive MIMO:** 5G NR extends MIMO up to 256 antenna elements and enables massive MIMO. This is a key enabler for higher spectrum bands. The antenna elements in this case are smaller, thereby making it less complex to build a massive array.
- **Massive IoT:** 5G NR will use resource spread multiple access (RSMA) on the uplink to enable grant-free transmission of data on the uplink. A device does not need an enhanced Node B (eNodeB) to give it a grant (or slot) in the pipe to transmit data. This capability eliminates the need for signaling and allows devices to send small packets asynchronously. 5G NR will also address distance and location challenges in low-power IoT devices, using a technique called *multi-hop mesh* to relay uplink data via nearby devices.

5G NR is part of the Release 15 specification from the Third Generation Partnership Project (3GPP). Two versions of 5G NR exist:

- **Non-standalone (NSA) 5G NR:** NSA will use the existing LTE radio and core network as the control plane anchor for mobility management and coverage, while adding a new 5G carrier. Early 2019 deployments of 5G NR will use this configuration. In this mode, the connection is anchored in 4G LTE while 5G NR carriers are used to boost data rates and reduce latency.
- **Standalone (SA) 5G NR:** SA will use the new 5G core network (5GCN) architecture, including the full control and user plane offered by 5G.

An interim release of the 5G NR NSA specification was accelerated to the end of 2017 to enable large-scale trials and deployments for enhanced mobile broadband (eMBB) use cases to begin in 2019. The 5G NR SA specification is expected in mid-2018.

More Spectrum — mmWave Bands

In the U.S., the Federal Communications Commission (FCC) has opened a total of 10.85 GHz of spectrum above 24 GHz to enable 5G use cases. The new spectrum includes 3.85 GHz of licensed spectrum from 27.5 to 28.35 GHz and 37 to 40 GHz, and 7 GHz of unlicensed spectrum from 64 to 71 GHz.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

These bands — between 30 GHz and 300 GHz — are known as millimeter wave bands (mmWave). These high frequency bands translate to narrow wavelengths in the range of one to ten millimeters. There are some challenges with mmWave, including:

- Short transmission paths and high propagation losses over long distances and anything that is not line of sight
- Weakened signals in gases and precipitation

However, the short transmission paths and propagation loss characteristics of mmWave enable spectrum reuse, by limiting the interference between adjacent cells. Additionally, because of the extremely short wavelengths of mmWave signals, transmission paths can be extended using small, multi-element dynamic beamforming antennas that can be installed in user equipment (UE) such as smartphones.

TIP

5G NR, operating at very high frequencies with small coverage areas (because of propagation and line-of-sight issues), is ideal for dense urban locations, where cell sizes are generally small (approximately 200 meters).

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

IN THIS CHAPTER

- Bringing 5G home
- Staying entertained on the move
- Getting a dose of virtual and augmented reality
- Driving 5G for smart cars and autonomous vehicles
- Living in a connected world
- Assimilating humans and machines

Chapter 7

Exploring 5G Use Cases

In this chapter, you learn about some of the key use cases that will be enabled by 5G.

Fixed Wireless Broadband Service

5G will begin its commercial drive with the fixed wireless broadband use case in the U.S. AT&T and Verizon are racing to be the first to deliver fixed wireless broadband service to their customers.

Verizon acquired XO Communications, which included the 28 gigahertz (GHz) spectrum, in 2016. One of the primary drivers for Verizon will be to offer 5G as an alternative to cable/advanced digital subscriber line (ADSL) for high-speed broadband access to residential customers for gigabit speed Internet, 4K content, virtual reality (VR), and more. The goal is to achieve greater than one gigabit per second (Gbps) speeds without digging trenches to get fiber to your home.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

AT&T is also pursuing 5G on fixed wireless in both the 28 GHz and 37 GHz spectrum bands. 5G video trials are currently underway for some residential customers, allowing them to stream DIRECTV NOW video service over a fixed wireless 5G connection. In its internal testing, AT&T Wireless claims it can now achieve 13 Gbps over a 5G connection. Like Verizon, AT&T is also looking at 5G to replace home broadband connections delivered by cable companies.

If successful, these use case trials could signal the end of the "cable guy" coming out "sometime between 1 p.m. and 4 p.m." to route a coaxial cable through your home. In areas where there is currently only one option for home broadband or television service, this technology could also lead to more competition, better service, and lower rates for subscribers.

Cable companies, such as Charter Communications, are also exploring 5G technologies. Charter is planning to conduct 28 GHz 5G experiments in the near future with antennas mounted on a mobile trailer and van with hydraulic masts, which will be moved to each of the test locations.

TIP

The motivation for a company like Charter is that 5G will enable a host of new products that take advantage of low-latency, high-capacity networks, including virtual reality (VR) and augmented reality (AR) applications, many of which will be used in a fixed home or office location.

Entertainment Everywhere

The natural progression of the fixed wireless broadband use case (discussed in the previous section) enables mobile broadband at extreme data rates "everywhere" — not only to a fixed home or office location.

Although some of the envisioned mobile broadband experience started in Long Term Evolution (LTE) networks, 5G takes it to a different level with 4K (and subsequently 8K) television, high dynamic range video streaming, 3D videos, and more. All these applications require very high bandwidth, and many require always-on connectivity to push real-time information to the users. The transformation from fixed wireless to wireless everywhere

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

requires several mobility-specific factors to be addressed, such as fast handoffs, seamless connectivity at very high speeds and low latency, high reliability when mobile, and others.

REMEMBER

Cloud storage is also driving the growth of uplink data rates. In the past, content was mostly downloaded and thus required a "fat" pipe in only one direction: the downlink from the base station to the mobile device. However, content is increasingly being uploaded to different cloud storage platforms, requiring robust data pipes in both the downlink and uplink directions. Cloud gaming is another 5G driver that requires fast responsiveness and high broadband capacity.

Virtual Reality (VR) and Augmented Reality (AR)

Virtual reality (VR) technology creates a fully immersive, computer-generated experience that simulates or re-creates real-life situations and environments. In contrast to VR, augmented reality (AR) layers computer-generated images and enhancements onto a real-world situation or environment to provide a more meaningful context for user interaction.

Although current 4G networks are sufficient for some early-adopter VR and AR experiences, the introduction of 5G will enable more novel VR and AR experiences and make them available for mass adoption by consumers. Offering much more capacity, lower latency, and a more uniform experience, 5G will not only improve, but will also be a requirement for some of the most exciting AR and VR use cases, including:

- Sharing live streaming content on social media from event venues along with 50,000 other people in a stadium becomes even more challenging with 4K 360-degree video because each user is uploading 25 Mbps at the same time.
- Next-generation VR and AR experiences will have "six degrees of freedom" (6DoF) — the next level of immersion — allowing users to move within and intuitively interact with the environment. 6DoF content is an order of magnitude richer in naturalness and interactivity than current "three degrees of freedom" (3DoF) video. 3DoF experiences, such as 360-degree

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

video, allow the user to look around rotationally from a fixed position. 6DoF experiences, which are available in video games today, allow the user to move spatially through the environment just by walking or leaning their head forward.

6DoF head-motion tracking is required to enjoy 6DoF content in an intuitive manner. Many industries such as tourism, education, and other forms of immersive video will flourish as 6DoF technologies evolve. Most components of the video delivery pipeline are currently ill-suited for 6DoF video, including capture devices, production software, codecs, compression algorithms, the network, and players. 6DoF video also demands bit rates in the range of 200 Mbps to 1Gbps, depending on the end-to-end latency.

Connected and Autonomous Vehicles

Smart, connected cars are already here — and some security risks have already been notoriously demonstrated — and self-driving autonomous vehicles are beginning to appear on our roads. Other applications that 5G will enable for smart, connected cars include:

- **Traffic safety:** This includes the ability to detect hazardous road conditions, such as inclement weather or nearby accidents, and provide real-time guidance for appropriate courses of action to enable safer driving and reduce the risk of accidents. For example, imagine a situation in which your driverless car gets a real-time message (in microseconds) that a truck is rapidly approaching the intersection that you are about to cross. Your car then automatically slows down to let the truck pass the intersection, thereby avoiding a possible accident.
- **Entertainment (for passengers):** Live video and music streaming (including 4K ultra high-definition movies), interactive video games, cloud connectivity, and data exchange elaborate the need for high capacity and high mobility mobile broadband.
- **Augmented reality (AR):** Displaying key information in near real-time for drivers requires low latency so that the information is timely and relevant. In the earlier truck

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

example, a live situation is being tracked by the involved IoT devices and infrastructure, and relayed in real-time to the users — vehicle and human.

- **Self-driving, autonomous vehicles:** These will require ultra-reliable, high-speed communication between different driverless cars, and between cars and infrastructure.

The Connected World

Smart homes, smart cities, multiple industries (such as health, retail, smart grids, and remote factories) have a common thread — they are using more and more devices and sensors that communicate with one another and the rest of the world.

Many of these devices are mission critical; others may send high-definition video, requiring high availability and very low latency. Yet another set of devices may send small data packets relatively infrequently (for example, every few hours, days, or weeks). Some examples of common use cases with diverse connectivity requirements include:

- **Logistics and freight:** These devices and sensors typically require lower data rates, but need wide coverage and reliable location information.
- **Smart grid:** A smart grid requires low latency sensors to regulate the use of utilities such as electricity, natural gas, and water. Leveraging digital information, such as the behaviors of suppliers and consumers, allows the smart grid to improve the efficiency, reliability, economics, and sustainability of the production and distribution of these resources.
- **Remote medical:** Collaborating about a medical case with other surgeons located thousands of miles away was a use case scenario discussed as part of the Long Term Evolution (LTE) rollout. It can become a reality with the extreme bandwidth, low latency, and high availability of 5G networks.
- **Hazardous areas:** The ability to remotely explore mining areas or shut down a nuclear power plant during an emergency — in a fraction of the time required for human interaction, and without risk to human life — is possible with 5G.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

Augmented Humans

Looking ahead to the more distant future — perhaps 30 years from now — Google futurist Ray Kurzweil predicts humans will be able to upload their entire minds to computers and become "digitally immortal" — an event called *singularity.*

In 2011, IBM's Watson beat former winners on the television game show *Jeopardy!*, proving that computers can outperform the best of humans when it comes to synthesizing information and beating them to the buzzer. Google Home and Amazon Echo are becoming more common in homes — perhaps a bit unnerving at first as they start entering our private lives, and increasingly taking center stage when we want them to tell us more about the weather, play our favorite song, read us our favorite *5G For Dummies* book, or tell a few jokes. As machine learning and artificial intelligence develop further, these intelligent devices will better understand human behavior and evolve beyond databases of information. Eventually, they will also become more mobile and intrinsic in our lives, rather than sitting on a shelf in our living rooms.

REMEMBER

5G — with its extreme bandwidths, very low latency, and massive scale support — will be a critical component in creating these real-time experiences, initially as an assistant to humans, and eventually even "thinking" for humans (in some cases). Shopping for clothes with your kids or selecting your next car will become a more immersive experience. 5G technology might also assist humans as an augmented partner, offloading some of the tasks humans don't want to "expend their own brain cells" on. Although it may sound like science fiction, 5G might be a starting point for the next evolution of humans and machines.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

IN THIS CHAPTER

- Going beyond speed and latency
- Looking at drivers and timelines
- Overcoming misconceptions about limitations
- Recognizing complementary technologies
- Transforming entire industries

Chapter 8

Ten Myths About 5G — Debunked

In this chapter, we expose ten common myths about 5G — and we clue you in to the reality behind them. Keep these points in mind:

- **5G is all about higher speeds to the user.** Although one of the key goals of 5G is to provide extreme bandwidth (high-speed data) to users, low latency and massive scale are other key goals of 5G. So, 5G isn't just about speed!
- **5G requires less than one millisecond latency.** Although less than one millisecond of latency is a goal of 5G, 5G networks will be deployed before that target is actually achieved.
- **Smartphones will lead the charge to 5G.** The iPhone and Android were born in the 3G era and virtually exploded (literally, in some cases) during the 4G LTE era. However, 5G will not only enable faster and better smartphones — it will also lead to mass-market consumer VR and AR devices, sensors and applications for smart homes and cars, industrial robots, and billions of other Internet of Things (IoT) devices yet to be conceived.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

- **5G will be commercially available in 2017.** Although Verizon plans to roll out 5G fixed mobility in 2017 and Olympic 5G trials will be underway during the 2018 Winter Olympics, 5G standards will not be finalized until the end of 2017. Thus, although some early, pre-standard versions of 5G will be coming soon, the 5G standard is not complete. Standards-compliant 5G will be coming much later.
- **5G is only for short-range, line-of-sight communication.** In addition to other frequency bands, 5G uses mmWave bands, which are ideal for very short ranges. However, plenty of ongoing experiments demonstrate how techniques such as beamforming can achieve greater ranges to users in challenging environments beyond line-of-sight.
- **5G will be used only in very high bands.** Although 5G will be deployed in very high millimeter wave (mmWave) bands, it will also re-use spectrum in lower bands, both licensed and unlicensed.
- **5G will replace 4G LTE.** 5G will coexist with 4G LTE for a long time to come. 4G has plenty to offer for many current applications such as voice, data, and even IoT.
- **5G will be a revolution, not an evolution.** Although 5G brings in a new physical layer (in 5G New Radio, or 5G NR), there is plenty of evolution from LTE-A Pro technologies such as carrier aggregation (CA), massive multiple input/multiple output (MIMO), quadrature amplitude modulation (QAM), unlicensed spectrum (LTE in unlicensed spectrum or LTE-U, License Assisted Access or LAA, and MulteFire, among others), IoT, and virtualization.
- **5G will be required to drive IoT.** IoT will initially be driven by LTE-A Pro where NarrowBand IoT (NB-IoT) is specified. In addition, other low-power technologies, such as Long Range Wide Area Network (LoRaWAN) and Sigfox, have been defined for IoT.
- **The 5G winners will be the operators and vendors.** Mobile network operators (MNOs), network equipment manufacturers (NEMs), and smartphone manufacturers were the primary business beneficiaries of 4G LTE. However, 5G will transform many industries, including car manufacturing, agriculture, health and medicine, transportation and logistics, and many more.

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

5 Keys to 5G

1

5G-NR (New Radio)

Next-Gen XAir

2

5G Speeds/Feeds

Ixia Multi-Gig LTE with XAir2

3

Wi-Fi Coexistence

Ixia LTE Unlicensed

4

Massive IoT

Ixia IoT

5

Testing NFV Deployments

IxLoad Wireless VE

Read more about about enabling the 5G revolution at www.ixiacom.com/solutions/5g-wireless-test

These materials are © 2017 John Wiley & Sons, Inc. Any dissemination, distribution, or unauthorized use is strictly prohibited.

Dream up new opportunities in the 5G future

The next-generation mobile network is on the horizon. 5G, the successor to 4G LTE networks, will enable significantly greater mobile speeds — as much as 20 gigabits per second — with very low latency. 5G will support a massive array of devices, from smart phones to virtual reality devices to small sensors. In this book, you learn about the technological innovations being developed today to enable a 5G future. You also learn about potential use cases that will transform entire industries and create new business models and opportunities.

Inside…

- Where wireless communication is headed
- Why higher speeds are the future
- How the IoT will employ 5G connectivity
- Why the unlicensed spectrum matters
- Why New Radio is a starting point for 5G
- How 5G will enable new business models

ixia

Kalyan Sundhar is Vice President — Mobility, Virtualization, and Applications at Ixia. He has more than 25 years experience in the industry, building cutting-edge products. **Lawrence C. Miller** has worked in information technology for more than 25 years. He has written more than 60 *For Dummies* books.

Go to Dummies.com®
for videos, step-by-step photos,
how-to articles, or to shop!

for dummies®
A Wiley Brand

ISBN: 978-1-119-42415-4
Ixia part number:
915-8156-01
Not for resale

WILEY END USER LICENSE AGREEMENT

Go to www.wiley.com/go/eula to access Wiley’s ebook EULA.

AUGUST 2017

LTE to 5G: Cellular and Broadband Innovation

RYSAVY RESEARCH

5G americas

This white paper was written for 5G Americas by Rysavy Research (http://www.rysavy.com) and utilized a composite of statistical information from multiple resources.

Table of Contents

INTRODUCTION **4**
BROADBAND TRANSFORMATION **7**
EXPLODING DEMAND **11**
  Application Innovation 11
  Internet of Things 12
  Video Streaming 12
  Cloud Computing 13
  5G Data Drivers 13
  Global Mobile Adoption 14
ALMOST AT 5G **18**
  Expanding Use Cases 18
  1G to 5G Evolution 20
  4G LTE Advances 23
  5G Use Cases (ITU and 3GPP) 27
  5G Technical Objectives 29
  5G Concepts and Architectures 30
  5G New Radio (NR) 33
  Expected 5G Performance 35
  Release 15 Non-Standalone and Standalone Options 35
  5G Schedule 36
  5G Core Network 37
  5G Device Availability 37
  mmWave 38
  Network Slicing 40
  Information-Centric Networking 41
  3GPP Releases 42
SUPPORTING TECHNOLOGIES AND ARCHITECTURES **45**
  Multiple Cell Types 45
  Smalls Cells and Heterogeneous Networks 46
  Neutral-Host Small Cells 49
  Unlicensed Spectrum Integration 49
  Internet of Things and Machine-to-Machine 53
  Smart Antennas and MIMO 55
  Virtualization 56
  Multi-Access Edge Computing 58
  Multicast and Broadcast 58
  Remote SIM Provisioning 58
VOLTE, RCS, WEBRTC, AND WI-FI CALLING **60**
  Voice Support and VoLTE 60
  Rich Communications Suite 60
  WebRTC 61
  Wi-Fi Calling 62
PUBLIC SAFETY **63**
  LTE Features for Public Safety 63
  Deployment Approaches 65

Device Considerations for Public Safety 66
EXPANDING CAPACITY 68
SPECTRUM DEVELOPMENTS 72
AWS-3 74
Broadcast Incentive Auction (600 MHz) 74
3550 to 3700 MHz “Small-Cell” Band 75
2.5 GHz Band 76
5G Bands 76
Harmonization 78
Unlicensed Spectrum 80
Spectrum Sharing 81
CONCLUSION 85
APPENDIX: TECHNOLOGY DETAILS 86
3GPP Releases 86
Data Throughput Comparison 88
Latency Comparison 94
Spectral Efficiency 95
Data Consumed by Streaming and Virtual Reality 102
Spectrum Bands 104
5G 107
  Architecture 107
  Architecture Options 108
  LTE-NR Coexistence 110
  Integrated Access and Backhaul 113
  Performance 114
LTE and LTE-Advanced 117
  LTE-Advanced Terminology 118
  OFDMA and Scheduling 119
  LTE Smart Antennas 121
  LTE-Advanced Antenna Technologies 125
  Carrier Aggregation 129
  Coordinated Multi Point (CoMP) 133
  Cellular V2X Communications 135
  User-Plane Congestion Management (UPCON) 136
  Network-Assisted Interference Cancellation and Suppression (NAICS) 136
  Multi-User Superposition Transmission (MUST) 136
  IPv4/IPv6 137
  TDD Harmonization 137
  SMS in LTE 138
  User Equipment Categories 138
  LTE-Advanced Relays 139
  Proximity Services (Device-to-Device) 140
  LTE Throughput 141
  VoLTE and RCS 148
  LTE Ultra-Reliable and Low-Latency Communications 153
  Evolved Packet Core (EPC) 153
Heterogeneous Networks and Small Cells 156
  Enhanced Intercell Interference Coordination 160
  Dual Connectivity 165

Internet of Things and Machine-to-Machine 167
Cloud Radio-Access Network (RAN) and Network Virtualization 168
Unlicensed Spectrum Integration 173
  Release 6 I-WLAN 174
  Release 8 Dual Stack Mobile IPv6 and Proxy Mobile IPv6 174
  Release 11 S2a-based Mobility over GTP 174
  Multipath TCP 175
  ANDSF 175
  Bidirectional Offloading Challenges 176
  Other Integration Technologies (SIPTO, LIPA, IFOM, MAPCON) 178
  Hotspot 2.0 178
Self-Organizing Networks (SON) 180
IP Multimedia Subsystem (IMS) 182
Broadcast/Multicast Services 183
Backhaul 185
UMTS-HSPA 186
  HSDPA 187
  HSUPA 190
Evolution of HSPA (HSPA+) 191
  Advanced Receivers 191
  MIMO 192
  Continuous Packet Connectivity 193
  Higher Order Modulation 193
  Multi-Carrier HSPA 193
  Downlink Multiflow Transmission 194
  HSPA+ Throughput Rates 195
UMTS TDD and TD-SCDMA 199
EDGE/EGPRS 200
ABBREVIATIONS AND ACRONYMS 204
ADDITIONAL INFORMATION 214

Copyright ©2017 Rysavy Research, LLC. All rights reserved. http://www.rysavy.com

Introduction

Mobile computing with wireless communications has already changed how people socialize and how companies do business. Yet, we are still in the nascent stages of the transformation that ubiquitous connectivity is enabling. Early examples of this exciting future include virtual and augmented reality, autonomous driving, smart cities, wearable computers, and connected devices throughout our environment. While no one can predict the full extent of innovation that the new global broadband fabric, aided by complementary innovations such as AI, will unleash, one thing is certain: We are rushing toward an extraordinary time.

The step from 3G to 4G was dramatic, and industry advances occurring now in LTE and 5G will be even greater. Standards bodies are standardizing 5G, a process that will continue through the 2020 timeframe, with ongoing enhancements continuing during the next decade. Some operators are deploying pre-standard 5G in trials this year, and initial standards-based networks could be deployed as early as 2019. 5G will not replace LTE; in most deployments, the two technologies will be tightly integrated and co-exist through at least the late-2020s.

Many of the capabilities that will make 5G so effective are appearing in advanced forms of LTE. With carrier aggregation, for example, operators have not only harnessed the potential of their spectrum holdings to augment capacity and performance, but the technology is also the foundation for entirely new capabilities, such as operating LTE in unlicensed bands.

The computing power of today's handheld computers rivals that of past mainframe computers, powering intuitive operating systems and millions of applications. Coupled with affordable mobile broadband connectivity, these devices provide such unprecedented utility that billions of people are using them.

With long term growth in smartphone and other mobile device use limited by population, innovators are increasingly turning their attention to the Internet of Things (IoT), which already encompasses a wide array of applications. Enhancements to LTE, followed by 5G IoT capabilities, will connect wearable computers, sensors, and other devices, leading to better health, economic gains, and other advantages. 5G addresses not only IoT deployments on a massive scale but also enables applications previously not possible that depend on ultra-reliable and low-latency communications, sometimes called "mission-critical applications." Although a far more fragmented market than smartphones, the benefits will be so great that the realization of IoT on a massive scale is inevitable.

Regulatory policies are striving to keep pace, addressing complex issues that include how best to allocate and manage new spectrum, network neutrality, and privacy. Policy decisions will have a major impact on the evolution of mobile broadband.

These are exciting times for both people working in the industry and those who use the technology—which today is nearly everybody. This paper attempts to capture the scope of what the industry is developing, beginning with Table 1, which summarizes some of the most important advances.

Table 1: Most Important Wireless Industry Developments in 2017

Development	Summary
5G Research and Development Accelerates	5G, in early stages of definition through global efforts and many proposed technical approaches, could be deployed in non-standalone versions as early as 2019. Deployment will continue through 2030. Some operators will deploy pre-standard networks for fixed-wireless access in 2017. 5G is being designed to integrate with LTE, and some 5G features may be implemented as LTE-Advanced Pro extensions prior to full 5G availability.
5G New Radio (NR) Being Defined	Key aspects of the 5G NR have been determined, such as radio channel widths and use of OFDMA. The first version, specified in Release 15, will support low-latency, beam-based channels, massive Multiple Input Multiple Output (MIMO) with large numbers of controllable antenna elements, scalable-width subchannels, carrier aggregation, Cloud Radio-Access Network (RAN) capability, and dynamic co-existence with LTE.
LTE Has Become the Global Cellular Standard	A previously fragmented wireless industry has consolidated globally on LTE. LTE is being deployed more quickly than any previous-generation wireless technology.
LTE-Advanced Provides Dramatic Advantages	LTE capabilities continue to improve with carrier aggregation, 1 Gbps peak throughputs, higher-order MIMO, multiple methods for expanding capacity in unlicensed spectrum, new IoT capabilities, vehicle-based communications, small-cell support including Enhanced Inter-Cell Interference Coordination (eICIC), lower latency, Self-Organizing Network (SON) capabilities and Enhanced Coordinated Multi Point (eCoMP).
Internet of Things Poised for Massive Adoption	IoT, evolving from machine-to-machine (M2M) communications, is seeing rapid adoption, with tens of billions of new connected devices expected over the next decade. Drivers include improved LTE support, such as low-cost and low-power modems, enhanced coverage, higher capacity, and service-layer standardization, such as oneM2M.
Unlicensed Spectrum Becomes More Tightly Integrated with Cellular	The industry has developed increasingly sophisticated means for integrating Wi-Fi and cellular networks, such as LTE-WLAN Aggregation (LWA) and LTE-WLAN Aggregation with IPSec Tunnel (LWIP), making the user experience ever more seamless. The industry has also developed and is now deploying versions of LTE that can operate in unlicensed spectrum, such as LTE-Unlicensed (LTE-U), LTE-Licensed Assisted Access (LTE-LAA), and

Development	Summary
	MulteFire. Cellular and Wi-Fi industry members are successfully collaborating to ensure fair spectrum co-existence.
Spectrum Still Precious	Spectrum in general, and in particular licensed spectrum, remains a precious commodity for the industry. Recently added spectrum in the United States includes the 600 MHz band, auctioned in 2017, and the 3.5 GHz Citizens Broadband Radio Service (CBRS) "small-cell" band, which could see initial deployments in 2018. 5G spectrum will include bands above 6 GHz, including "mmWave" (30 GHz to 100 GHz), with the potential of ten times (or more) as much spectrum as is currently available for cellular. Radio channels of 200 MHz and 400 MHz, and even wider in the future, will enable multi-Gbps peak throughput.
Small Cells Take Baby Steps, Preparing to Stride	Operators have begun installing small cells, which now number in the tens of thousands. Eventually, hundreds of thousands if not millions of small cells will lead to massive increases in capacity. The industry is slowly overcoming challenges that include restrictive regulations, site acquisition, self-organization, interference management, power, and backhaul.
Network Function Virtualization (NFV) Emerges	Network function virtualization (NFV) and software-defined networking (SDN) tools and architectures are enabling operators to reduce network costs, simplify deployment of new services, reduce deployment time, and scale their networks. Some operators are also virtualizing the radio-access network, as well as pursuing a related development called cloud radio-access network (cloud RAN). NFV and cloud RAN will be integral components of 5G.

The main part of this paper covers the transformation of broadband, exploding demand for wireless services, the path to 5G including planned and expected capabilities, new LTE innovations, supporting technologies and architectures, voice over LTE (VoLTE), Wi-Fi Calling, LTE for public safety, options to expand capacity, and spectrum developments.

The appendix delves into more technical aspects of the following topics: 3GPP Releases, Data Throughput, latency, 5G, LTE, LTE-Advanced, LTE-Advanced Pro, HetNets and small cells, IoT, cloud RANs, Unlicensed Spectrum Integration, self-organizing networks, the IP Multimedia Subsystem, broadcast/multicast services, backhaul, UMTS/WCDMA,[1] HSPA, HSPA+, UMTS TDD, and EDGE/EGPRS.

---

[1] Although many use the terms "UMTS" and "WCDMA" interchangeably, in this paper "WCDMA" refers to the radio interface technology used within UMTS, and "UMTS" refers to the complete system. HSPA is an enhancement to WCDMA.

Broadband Transformation

Broadband networks rely on a fiber core with various access technologies, such as fiber to the premises, coaxial cable, digital subscriber line (DSL), or wireless connections. LTE provides a broadband experience, but capacity limitations prevent it from being the only broadband connection for most users. As a result, a majority of consumers in developed countries have both mobile broadband and fixed broadband accounts.

Two developments will transform the current situation:

1. **Fiber Densification**. Multiple companies are investing to extend the reach of fiber, decreasing the distance from the fiber network to the end node.
2. **5G Standardization and Deployment.** As 5G mmWave technology, including massive MIMO and beamforming, becomes commoditized, it will increasingly be a viable alternative to fixed-access technologies such as coaxial, DSL, and even fiber connections. 5G commercial services will enable a new innovation cycle. The ability to create new applications and services with fewer limitations will take the connected society to a new level.

Consequently, the companies that provide broadband service may change, and eventually, fixed and mobile broadband services may converge. For a more detailed discussion of trends in broadband, including the disruptive role of mmWave, refer to the 2017 Datacomm Research and Rysavy Research report, *Broadband Disruption: How 5G Will Reshape the Competitive Landscape*.[2]

As shown in Figure 1, the emerging broadband network is one with denser fiber and competing access technologies in which wireless connectivity plays a larger role.

---

[2] Details at https://datacommresearch.com/reports-broadband/.

Figure 1: Fiber Densification with Multiple Access Technologies, including mmWave


2010s
2020s
Mobile Broadband Has Limited Capacity
Mobile/Wireless Broadband with Much Greater Capacity, Bigger Broadband Role
Low Density Fiber Networks
Low Density Fiber Networks
Transformation
High Density Fiber Networks
High Density Fiber Networks
High Density Fiber Networks
High Density Fiber Networks
Broadband Traffic Dominated by Fixed Access Technologies
Rysavy Research

Many elements are interacting to transform mobile broadband, but the factors playing the most important roles are emerging capabilities for IoT, radio advances granting access to far more spectrum, small cells, new network architectures that leverage network function virtualization and software-defined networking, and new means to employ unlicensed spectrum. Except for access to high-band spectrum, a 5G objective, these advances apply to both LTE and 5G.

Figure 2: Fundamental Mobile Broadband Transformational Elements


Ability to access
10 times as much spectrum
with better radio technology
New Network Architectures
(NFV, Mobile Edge Computing,
Network Slicing, ...)
Cloud Computing
Integration of Licensed and
Unlicensed Spectrum
Equal Support for Things
And People
THING 1
THING 2
Small Cells Ready for
Mass Deployment

Rysavy Research

In the past, developers used modems and networks designed for human communication for machine-type applications. But now, new modes of network operation, initially in LTE then enhanced further in 5G, will cater to the unique needs of a wide variety of machine applications, addressing low-cost, long battery life, long communications range, and a wide variety of throughputs. For instance, some IoT applications need only low-throughput communications, some sending only a small number of bits per day.

As for spectrum, throughout radio history, technology has climbed up a ladder to use higher frequencies. What were called “ultra-high frequencies” when made available for television are now considered low-band frequencies for cellular. Frequencies above 6 GHz, particularly mmWave frequencies, are the new frontier. Networks will ultimately take advantage of ten times as much spectrum as they use now, and likely even more over time. Although challenging to use because of propagation limitations and higher penetration loss, massive MIMO, beam steering, beam tracking, dual connectivity, carrier aggregation, small-cell architectures with self-backhauling, and other methods will help mitigate the challenges at these frequencies. The result: massive increases in capacity in localized areas.

In addition to accessing higher bands, cellular technologies are integrating unlicensed spectrum more efficiently, using technologies such as LTE-U, LAA, MulteFire, LWA, and LWIP. This integration will immediately augment small-cell capacity, improving the business case for small cells.

Small cells, on the roadmap for many years but held back by implementation difficulties, such as backhaul, are on the verge of large scale deployment, leading ultimately to densities as high as ten small cells or more for every macro cell. Paving the way are better wireless backhaul solutions, neutral-host capabilities enabled by new technologies, and soon, access to mmWave bands.

Facilitating the capabilities listed above, networks are becoming programmable. Using a distributed, software-enabled network based on virtualization and new architectural approaches such as Multi-access Edge Computing (MEC) and network slicing, operators and third parties will be able to deploy new services and applications more rapidly, and in a more scalable fashion. Centralizing RAN signal processing will also play a huge role; depending on the deployment scenario, such centralization will increase RAN efficiency and decrease deployment cost.

This paper lists the dozens of other innovations also fueling mobile and cellular technology transformation. Together, these transformed networks will mean that for millions, and ultimately billions, of people, wireless connections will be the only connections that they need. These networks will also provide the foundation for entire new industries, ones not yet even conceived.

Exploding Demand

Two technology trajectories have created critical mass: handheld computing and fast wireless connections. This combined computing and communications platform inspires the innovation that has produced millions of mobile applications.

IoT is a third trajectory. LTE, and eventually 5G, will connect tens of billions of devices. And fixed-wireless access could be a fourth. 5G, with expected network capacity a hundred times greater than 4G networks, will make wireless connections not only a viable substitute for wireline broadband connections for tens of millions of users over the next ten years, but make that broadband connection the only connection that many users need.

Figure 3: Exploding Demand from Critical Mass of Factors



This section analyzes some of these demand factors.

Application Innovation

When planning 4G network technology, who could have predicted applications such as Uber and Lyft, which combine location information with mapping and online payment and are now disrupting the taxi industry and even challenging notions of private vehicle ownership? While some applications of new technology can be predicted, many cannot.

More efficient technology not only addresses escalating demand, it also provides higher performance, thus encouraging new usage models and further increasing demand.

Today's smartphones and tablets, dominated by the iOS and Android ecosystems, in combination with sophisticated cloud-based services, provide a stable, well-defined application environment, allowing developers to target billions of users. Developers have rich platform-specific development tools; web-based tools such as HTML5; application programming interfaces (APIs) for mobile-specific functions, such as WebRTC (Web Real-Time Communications); and cloud-based services for applications and application services, such as notifications, IoT support, and mobile-commerce.

Of concern to some companies in the wireless industry, however, are current network neutrality rules that could possibly hamper innovation. By restricting prioritization, for example, the rules seem to fail to recognize that traffic streams from different applications have inherently different quality of service requirements.[3]

Internet of Things

Current M2M and Internet of Things applications include vehicle infotainment, connected healthcare, transportation and logistics, connected cars, home security and automation, manufacturing, construction and heavy equipment, energy management, video surveillance, environmental monitoring, smart buildings, wearable computing, object tracking, and digital signage. Municipalities, evaluating the concept of "smart cities," are exploring how to optimize pedestrian and vehicular traffic, connect utility meters, and deploy trash containers that can report when they need emptying.

Although promising, the IoT market is also challenging, with varying communications requirements, long installation lifetimes, power demands that challenge current battery technology, cost sensitivity, security and data privacy concerns, unsuitability of conventional networking protocols for some applications, and other factors that developers must address. Consequently, the IoT opportunity is not uniform; it will eventually comprise thousands of markets. Success will occur one sector at a time, with advances in one area providing building blocks for the next.

Cloud-based support platforms and standardized interfaces are essential for development and deployment of IoT applications. For example, oneM2M has developed a service-layer that can be embedded in hardware and software to simplify communications with application servers.[4]

To address the IoT opportunity, 3GPP is defining progressive LTE refinements that will occur over multiple 3GPP releases. These refinements include low-cost modules that approach 2G module pricing and enable multi-year battery life. See the section "Internet of Things and Machine-to-Machine" in the appendix for more details.

Video Streaming

Video represents the greatest usage of data on smartphones. Just an hour a day of mobile video at 1.0 Mbps throughput, common with YouTube or Netflix, consumes 13.5 GB per month. Many streams, now available in high-definition (HD), consume even more data.

---

[3] For further discussion, see Rysavy Research, *How "Title II" Net Neutrality Undermines 5G*, April 19, 2017. Available at http://www.rysavy.com/Articles/2017-04-How-Title-II-Net-Neutrality-Undermines-5G.pdf. Also see *How Wireless is Different – Considerations for the Open Internet Rulemaking*, September 12, 2014. Available at http://www.rysavy.com/Articles/2014-09-Wireless-Open-Internet.pdf.

[4] OneM2M home page: http://onem2m.org/.

See the Appendix section “Data Consumed by Video” for a quantification of data consumed by video for multiple usage scenarios.

An increasing number of video applications adapt their streaming rates based on available bandwidth. By doing so, they can continue to operate even when throughput rates drop. Conversely, they take advantage of higher available bandwidth to present video at higher resolution. Fortunately, application developers are becoming sensitive to bandwidth constraints and are offering options for users to reduce consumption.

Nevertheless, video can consume so much data that cutting the broadband cord at the same time as the television cord is not possible for most consumers. With 5G’s massive increase in capacity, however, an increasing percentage of users will use wireless connections as their only broadband connections, including for all their entertainment needs.

Cloud Computing

Cloud computing inherently increases data consumption because it requires communications for all operations. Examples include data synchronization and backup, cloud-based applications (such as email, word processing, and spreadsheets), automatic photo uploads, and music and video streaming.

5G Data Drivers

Futurists can predict some 5G applications, but many others will arise as industries evolve or come into existence to take advantage of new network capabilities. Some potential applications of 5G include:

- Ultra-high-definition, such as 4K and 8K, and 3D video.
- Augmented and immersive virtual reality. Ultra-high-fidelity virtual reality can consume 50 times the bandwidth of a high-definition video stream.
- Realization of the tactile internet—real-time, immediate sensing and control, enabling a vast array of new applications.
- Automotive, including autonomous vehicles, driver-assistance systems, vehicular internet, infotainment, inter-vehicle information exchange, and vehicle pre-crash sensing and mitigation.
- Monitoring of critical infrastructure, such as transmission lines, using long battery life and low-latency sensors.
- Smart transportation using data from vehicles, road sensors, and cameras to optimize traffic flow.
- Mobile health and telemedicine systems that rely on ready availability of high-resolution and detailed medical records, imaging, and diagnostic video.
- Public safety, including broadband data and mission-critical voice.
- Sports and fitness enhancement through biometric sensing, real-time monitoring, and data analysis.
- Fixed broadband replacement.

Some of these applications are already being addressed by 4G, but 5G's lower costs, higher throughputs, and lower latency will hasten realization of their potential.

Specific industries expected to take advantage of 5G include manufacturing, healthcare, media and entertainment, financial services, public safety, automotive, public transport, and energy utilities.[5]

Global Mobile Adoption

Figure 4 shows the often-cited Cisco projection of global mobile data consumption through 2021, measured in exabytes (billion gigabytes) per month, demonstrating traffic growing at a compound annual rate of 47%.

Figure 4: Global Mobile Data 2016 to 2021[6]



Figure 5 shows another data projection, predicting 45% annual growth in data for the 2016-to-2022 period, resulting in eight-fold growth.

---

[5] For further insight, refer to the Ericsson white paper, *The 5G Business Potential,* February 2017. Available at https://www.ericsson.com/en/networks/insights/the-5g-business-potential.

[6] Cisco, *Cisco Visual Networking Index: Global Mobile Data Traffic Forecast Update, 2016-2021*, February 2017.

Figure 5: Global Mobile Voice and Data (Exabytes/Month) 2012 to 2022[7]



Figure 6 shows how the Internet of Things will drive far more connections than are launched by people.

---

[7] Ericsson, *Ericsson Mobility Report*, June 2017.

Figure 6: Connections of Places Versus People Versus Things[8]



In June 2017, more than 7.56 billion GSM-HSPA-LTE connections were in effect[9]—greater than the world's 7.40 billion population.[10] By the end of 2022, the global mobile broadband market is expected to include nearly 9.4 billion subscribers, with 9.3 billion using 3GPP technologies, representing more than 99% market share.[11]

LTE has experienced faster deployment than any mobile technology ever developed. All major U.S. operators now offer nationwide LTE coverage. LTE has also been chosen by U.S. national public-safety organizations as their broadband technology of choice.

As shown in Figure 7, 2G GSM has peaked and is now declining, as is CDMA. Both HSPA and LTE subscriptions will continue to rise through the rest of the decade.

---

[8] Ericsson, *IoT Security*, February 2017, available at https://www.ericsson.com/assets/local/publications/white-papers/wp-iot-security-february-2017.pdf.

[9] Ovum, July 2017.

[10] U.S. Census Bureau, "U.S. and World Population Clock," http://www.census.gov/popclock/, accessed July 18, 2017.

[11] Ovum, July 2017. Note that the 2018 mobile broadband market figures include GSM/EDGE, because most GSM networks are likely to include Evolved EDGE, which provides mobile broadband capability.

Figure 7: Global Adoption of 2G-4G Technologies 2010 to 2020[12]



IoT is growing rapidly as well, although connections so far are well below phone-type connections. Cisco projects 3.3 billion IoT connections by 2021, with 6% on 2G cellular, 16% on 3G, and 46% on 4G.[13]

---

[12] Ovum (WCIS), July 2017.

[13] Cisco, *Cisco Visual Networking Index: Global Mobile Data Traffic Forecast Update, 2016-2021*, February 2017.

Almost at 5G

With intensive development occurring within 3GPP, the first 5G specification will be completed in early 2018, enabling the first standards-based networks to be deployed in the 2019-2020 timeframe. This section includes expanding use cases, 1G-to-5G evolution, 4G LTE advances, 5G radio and architectures, Information-Centric Networking, phasing of 5G releases, and an overview of 3GPP releases.

Expanding Use Cases

Many wireless technology discussions focus on radio capabilities, but other equally important aspects include use cases, the services built on top of the technology, how different networks integrate with one another, and the topology of the networks. As summarized in Figure 8, these aspects are expanding, making mobile/wireless technology the foundation for other enterprises, including business-process optimization, consumer electronics, M2M, connected devices, and a multitude of vertical industries.

Figure 8: Expanding Use Cases



Expanding Use Cases

Operator Services
- Television broadcast
- Proximity services
- Location-based
- Public safety
- Internet of Things
- Vehicle communication

Third-Party Services
- Over-the-top communication
- Cloud-based
- Other

Applications
- Millions becoming tens of millions

Multi-Network Integration and New Topologies:
- Network-level aggregation (e.g., Multipath TCP)
- Offload onto Wi-Fi
- LTE Wi-Fi Link Aggregation
- Operation of LTE in unlicensed bands
- New connection methods (relays, multi-hop, device-to-device)

Radio Network Enhancement:
- Becoming faster (peak rates of 1 Gbps+ in 4G, 20 Gbps+ in 5G)
- Densifying (smaller cells)
- Capacity increasing (more cells, more spectrum, more efficient technology)
- Shorter delays (10 msec with LTE, 1 msec with future LTE-Advanced and 5G)
- Low-cost and low-power machine options
- Centralization of radio-access network functions (including cloud RAN)
- Application processing within the RAN (e.g., Mobile-Edge Computing)
- Support for higher frequencies (e.g., mmWave)

Rysavy Research

Table 2 summarizes the requirements of the expanding number of use cases that employ wireless technology.

Table 2: Requirements for Different Use Cases[14]

Use Cases	Requirements	Desired Value
Autonomous vehicle control	Latency	5 msec
	Availability	99.999 percent
	Reliability	99.999 percent

---

[14] Ericsson, *5G Systems – Enabling the Transformation of Industry and Society*, January 2017. Available at https://www.ericsson.com/assets/local/publications/white-papers/wp-5g-systems.pdf. Adapted from Table 1.

Use Cases	Requirements	Desired Value
Emergency communication	Availability	99.9 percent victim discovery rate
	Energy efficiency	One-week battery life
Factory cell automation	Latency	Down to below 1ms
	Reliability	Down to packet loss of less than 10^{-9}
High-speed train	Traffic density	Downlink (DL): 100Gbps/km^2, uplink (UL): 50 Gbps/km^2
	User throughput	DL: 50Mbps, UL: 25Mbps
	Mobility	500 km/h
	Latency	10ms
Large outdoor event	User throughput	30Mbps
	Traffic density	900Gbps/km^2
	Connection density	Four devices/m^2
Massive IoT	Connection density	1,000,000 devices/km^2
	Availability	99.9 percent coverage
	Energy efficiency	10-year battery life
Remote surgery and examination	Latency	Down to 1ms
	Reliability	99.999 percent
Smart city	User throughput	DL: 300Mbps, UL: 60Mbps
	Traffic density	700 Gbps/km^2
	Connection density	200,000 devices/km^2
Virtual and augmented reality	User throughput	4-28Gbps
	Latency	< 7msec
Broadband to the home	Connection density	4,000 devices/km^2
	Traffic density	60Gbps/km^2

The economic role that wireless technology plays keeps increasing. One study anticipates that in 2035, 5G will enable $12.3 trillion of global economic output.[15]

1G to 5G Evolution

5G is almost upon us; it is a technology that will be constructed from millions of ideas, methods, algorithms, and processes. Just as 4G LTE became available when previous technologies, such as HSPA, could be further improved, 5G enters the stage when the roadmap for LTE has not been exhausted. And just as 2G coexists today with 3G and 4G, 5G will co-exist with previous generations of technology.

For historical context, “1G” refers to analog cellular technologies that became available in the 1980s. “2G” denotes initial digital systems that became available in the 1990s and that introduced services such as short messaging and lower-speed data. 3G requirements were specified by the International Telecommunication Union (ITU) as part of the International Mobile Telephone 2000 (IMT-2000) project, for which significant voice capacity improvement was a focus and digital networks had to provide 144 Kbps of throughput at mobile speeds, 384 Kbps at pedestrian speeds, and 2 Mbps in indoor environments. UMTS-

---

[15] HIS Economics and HIS Technology, *The 5G Economy: How 5G Technology will contribute to the global economy,* January 2017. Commissioned by Qualcomm Technologies.

HSPA and CDMA2000 are the primary 3G technologies. 3G technologies began to be deployed early last decade.

In 2008, the ITU issued requirements for IMT-Advanced, which many people initially used as a definition of 4G. The focus on 4G was to improve data coverage, capacity, and quality of experience. Requirements included operation in up to-40 MHz radio channels and extremely high Spectral Efficiency. The ITU required peak spectral efficiency of 15 bps/Hz and recommended operation in up-to-100 MHz radio channels, resulting in a theoretical throughput rate of 1.5 Gbps. In 2009 and 2010, the term "4G" became associated with mobile broadband technologies deployed at the time, such as HSPA+, WiMAX, and initial LTE deployments. Today, 4G usually refers to HSPA+ or LTE.

Although the industry is preparing for 5G, LTE capabilities will continue to improve in LTE-Advanced Pro through the rest of the decade. Many of these enhancements will come through incremental network investments. Given the scope of global wireless infrastructure, measured in hundreds of billions of dollars, offering users the most affordable service requires operators to leverage investments they have already made. 5G will eventually play an important role, but it must be timed appropriately so that the jump in capability justifies the new investment.

5G groups researching next generation wireless architecture and requirements include, among others, the International Telecommunication Union (ITU),[16] the European Union's 5G Infrastructure Public-Private-Partnership (5G PPP), which is the framework for several projects, including METIS II (Mobile and wireless communications Enablers for the Twenty-twenty Information Society), and Next Generation Mobile Networks (NGMN). Finally, 5G Americas is actively involved in developing the vision and requirements of 5G for North, Central, and South America. 5G Americas signed an MoU to collaborate with 5G-PPP.[17]

The ITU, the standardization group of the United Nations, has set the following standardization timetable in its IMT-2020 project:[18]

- 2016-2017: Definition of technical performance requirements, evaluation criteria and methods, and submission templates.
- 2018-2019: Submission of proposals.
- 2019: Evaluation of proposed technologies.
- 2019 and 2020: Publication of IMT-2020 specifications.

---

[16] International Telecommunication Union, "Working Party 5D (WP 5D) - IMT Systems," http://www.itu.int/ITU-R/index.asp?category=study-groups&rlink=rwp5d&lang=en, accessed May 16, 2017.

[17] 5GPPP, "5G-PPP MoU with 4G Americas," March 2, 2015. http://5g-ppp.eu/5g-ppp-mou-with-4g-amererICAS/

[18] ITU, "ITU towards 'IMT for 2020 and beyond'," http://www.itu.int/en/ITU-R/study-groups/rsg5/rwp5d/imt-2020/Pages/default.aspx, viewed May 16, 2017.

Wireless technology has progressed to the extent that significant new capabilities are inevitable, making 5G a possible alternative to wireline broadband for many subscribers.[19]

Table 3 summarizes the generations of wireless technology.

Table 3: 1G to 5G

Generation	Requirements	Comments
1G	No official requirements. Analog technology.	Deployed in the 1980s.
2G	No official requirements. Digital technology.	First digital systems. Deployed in the 1990s. New services such as SMS and low-rate data. Primary technologies include IS-95 CDMA (cdmaOne), IS-136 (D-AMPS), and GSM.
3G	ITU's IMT-2000 required 144 Kbps mobile, 384 Kbps pedestrian, 2 Mbps indoors.	First deployment in 2000. Primary technologies include CDMA2000 1X/EV-DO and UMTS-HSPA. WiMAX.
4G (Initial Technical Designation)	ITU's IMT-Advanced requirements include the ability to operate in up-to-40-MHz radio channels and with very high spectral efficiency.	First deployment in 2010. IEEE 802.16m and LTE-Advanced meet the requirements.
4G (Current Marketing Designation)	Systems that significantly exceed the performance of initial 3G networks. No quantitative requirements.	Today's HSPA+, LTE, and WiMAX networks meet this requirement.
5G	ITU IMT-2020 has defined technical requirements for 5G, and 3GPP is developing specifications.	First standards-based deployments in 2019 and 2020.

The interval between each significant technology platform has been about ten years. Within each platform, however, innovation surges unabated. For example, with 2G technology,

---

[19] Rysavy Research, "How will 5G compare to fiber, cable or DSL?" Fierce Wireless, May 2014. Available at http://www.rysavy.com/Articles/2014-05-5G-Comparison-Wireline.pdf.

EDGE significantly improved data performance compared with initial General Packet Radio Service (GPRS) capabilities. Similarly, HSPA hugely increased data speeds compared with initial 3G capabilities. LTE and LTE-Advanced are also acquiring continual improvements that include faster speeds, greater efficiency, and the ability to aggregate spectrum more flexibly.

Figure 9 presents the timeline of technology generations, including past and future, showing initial deployment, the year of the peak number of subscribers, and decline. Each cellular generation spans multiple decades, with peak adoption occurring some 20 years after initial deployment. 6G deployment in 2030, though highly speculative, is consistent with deployment of previous generations.

Figure 9: Timeline of Cellular Generations



Rysavy Research

4G LTE Advances

As competitive pressures in the mobile broadband market intensified, and as demand for capacity persistently grew, LTE became the favored 4G solution because of its high data throughputs, low-latency, and high spectral efficiency. Specifically:

- **Wider Radio Channels.** LTE can be deployed in wide radio channels (for example, 10 MHz or 20 MHz) with carrier aggregation now up to 640 MHz, although inter-band aggregation of four or five carriers (up to 100 MHz) represents a practical upper limit.
- **Easiest MIMO Deployment.** By using new radios and antennas, LTE facilitates MIMO Deployment, in contrast to the logistical challenges of adding antennas for MIMO to existing legacy technologies. Furthermore, MIMO gains are maximized because all user equipment supports it from the beginning.
- **Best Latency Performance.** For some applications, low latency (packet traversal delay) is as important as high throughput. With a low transmission time interval (TTI) of 1 millisecond (msec) and a flat architecture (fewer nodes in the core network), LTE has the lowest latency of any cellular technology.

In the same way that 3G coexists with 2G systems in integrated networks, LTE systems co-exist with both 3G and 2G systems, with devices capable of 2G, 3G, and 4G modes.

Beyond radio technology, the Evolved Packet Core (EPC) provides a core architecture that integrates with both legacy GSM-HSPA networks and other wireless technologies, such as CDMA2000 and Wi-Fi. The combination of EPC and LTE is referred to as the Evolved Packet System (EPS).

LTE is available in both Frequency Division Duplex (FDD) and Time Division Duplex (TDD) modes. Many deployments are based on FDD in paired spectrum. The TDD mode, however, is important for deployments in which paired spectrum is unavailable. Instances of TDD deployment include China, Europe at 2.6 GHz, U.S. Broadband Radio Service (BRS) spectrum at 2.6 GHz, and the 3.5 GHz band.

The versions of LTE most widely deployed today are just the first in a series of innovations that will increase performance, efficiency, and capabilities. Enhancements in the 2013 to 2016 period were the ones defined in 3GPP Releases 10, 11, and 12 and are commonly referred to as LTE-Advanced.[20] Subsequent releases, including Releases 13 to 15, specify LTE-Advanced Pro.

Keeping in mind that different operators have varying priorities, the following list roughly ranks the most important features of LTE-Advanced and LTE-Advanced Pro for the 2017 to 2020 timeframe:

1. **Carrier Aggregation.** With this capability, already in use, operators can aggregate radio carriers in the same band or across disparate bands to improve throughputs (under light network load), capacity, and efficiency. Carrier aggregation can also combine FDD and TDD and is the basis of LTE-U and LTE-LAA. As examples, in 2015, AT&T aggregated 700 MHz with AWS, and 700 MHz with PCS. T-Mobile aggregated 700 MHz with AWS, and AWS with PCS.[21] Operators are now deploying three-carrier aggregation and eventually may aggregate four carriers.[22] Release 13 introduced support for carrier aggregation of up to 32 carriers, addressing primarily the opportunity to aggregate multiple unlicensed channels. Release 14 specifies interband carrier aggregation for up to five downlink carriers and 2 uplink carriers.
2. **VoLTE.** Initially launched in 2015 and with widespread availability in 2017, VoLTE enables operators to roll out packetized voice for LTE networks, resulting in greater voice capacity and higher voice quality.
3. **Tighter Integration of LTE with Unlicensed Bands.** LTE-U became available for testing in 2016, and 3GPP completed specifications for LAA in Release 13, with deployment expected around 2018. MulteFire, building on LAA, will operate without requiring a licensed carrier anchor. LTE/Wi-Fi Aggregation through LWA and LWIP are other options for operators with large Wi-Fi deployments.

---

[20] From a strict standards-development point of view, the term “LTE-Advanced” refers to the following features: carrier aggregation, 8X8 downlink MIMO, and 4XN uplink MIMO with N the number of receive antennas in the base station.

[21] AT&T band combinations are 3GPP Band 13 + Band 4, Band 17 + Band 4, and Band 17 + Band 2. T-Mobile band combinations are Band 12 + Band 4, Band 12 + Band 2, and Band 4 + Band 2.

[22] For carrier aggregation to operate, both the network and the device have to support the particular band combination. Legacy devices typically do not support new network aggregation capabilities.

4. **Enhanced Support for IoT.** Release 13 brings Category M1, a low-cost device option, along with Narrowband-IoT (NB-IoT), a version of the LTE radio interface specifically for IoT devices, called Category NB1.

5. **Higher-Order and Full-Dimension MIMO.** Deployments in 2017 use up to 4X4 MIMO. Release 14 specifies a capability called Full-Dimension MIMO, which supports configurations with as many as 32 antennas at the base station. See the section “Smart Antennas and MIMO” and Appendix section “LTE Smart Antennas” for further detail.

6. **Dual Connectivity.** Release 12 introduced the capability to combine carriers from different sectors and/or base stations (i.e. evolved Node Bs [eNBs]) through a feature called Dual Connectivity. Two architectures were defined: one that supports Packet Data Convergence Protocol (PDCP) aggregation between the different eNBs and one that supports separate S1 connections on the user-plane from the different eNBs to the EPC.

7. **256 QAM Downlink and 64 QAM Uplink.** Defined in Release 12 and already deployed in some networks, higher-order modulation increases user throughput rates in favorable radio conditions.

8. **1 Gbps Capability.** Using a combination of 256 QAM modulation, 4X4 MIMO, and aggregation of three carriers, operator networks can now reach 1 Gbps peak speeds. See below for more information.

9. **V2X Communications.** Release 14 specifies vehicle-to-vehicle and vehicle-to-infrastructure communications. See the section “Cellular V2X Communications” for more information.

10. **Coordinated Multi Point.** CoMP (and enhanced CoMP [eCoMP]) is a process by which multiple base stations or cell sectors process a User Equipment (UE) signal simultaneously, or coordinate the transmissions to a UE, improving cell-edge performance and network efficiency. Initial usage will be on the uplink because no user device changes are required. Some networks had implemented this feature in 2017.

11. **HetNet Support.** HetNets integrate macro cells and small cells. A key feature is enhanced inter-cell interference coordination (eICIC), which improves the ability of a macro and a small-cell to use the same spectrum. This approach is valuable when the operator cannot dedicate spectrum to small cells. Operators are currently evaluating eICIC, and at least one operator has deployed it.[23] Further enhanced ICIC (feICIC) introduced in Rel-11 added advanced interference cancellation receivers into devices.

12. **Ultra-Reliable and Low-Latency Communications.** Being specified in Release 15, URLLC in LTE will shorten radio latency to a 1 msec range using a combination of shorter transmission time intervals and faster hybrid automatic repeat request (HARQ) error processing. See the Appendix section “LTE Ultra-Reliable and Low-Latency Communications” for further details.

13. **Self-Organizing Networks.** With SON, networks can automatically configure and optimize themselves, a capability that will be particularly important as small cells begin

---

[23] Fierce Wireless, “SK Telecom teams with Nokia Networks on eICIC,” January 2015.

to proliferate. Vendor-specific methods are common for 3G networks, and trials are now occurring for 4G LTE standards-based approaches.

Other key features that will become available in the 2016-to-2020 timeframe include full-dimension MIMO, enhanced Multimedia Broadcast/Multicast Services (eMBMS), User-Plane Congestion Management (UPCON), and device-to-device communication (targeted initially at public-safety applications).

The appendix explains these features and quantifies performance gains, and Figure 10 illustrates the transition from LTE to LTE-Advanced and LTE-Advanced Pro, which include these features.

Figure 10: LTE to LTE-Advanced Pro Migration[24]


2010 to 2012
2013 to 2018
Initial Deployments
▪ 5 or 10 MHz Radio Channels
▪ 2X2 Multiple Input Multiple Output (MIMO) Antennas
▪ Initial Self-Optimization/Organization for Auto Configuration
Higher Capacity/Throughput and/or Efficiency
▪ Wider Radio Channels: 20 MHz
▪ Carrier Aggregation: up to 640 MHz
▪ Advanced Antenna Configurations
▪ More Advanced MIMO (Higher Order, Multi-User)
▪ Coordinated Multipoint Transmission
▪ Het-nets (Microcells/Picocells/Femtocells)
▪ Het-net Self-Optimization/Organization
▪ More Intelligent and Seamless Offload
▪ Dual Connectivity
▪ Aggregation of Unlicensed Bands
Greater Capabilities
▪ Voice Widely Handled in the Packet Domain (VoLTE)
▪ Policy-Based Quality of Service
▪ Integration with Unlicensed Spectrum
Enables more users, more applications, and a better experience

Figure 11 illustrates gains in peak downlink speeds through carrier aggregation, higher-order MIMO, and higher-order modulation.

---

[24] 5G Americas/Rysavy Research

Figure 11: Successive Gains in Peak LTE Downlink Throughput[25]



5G Use Cases (ITU and 3GPP)

The ITU, in its 5G recommendations, divides use cases into three main categories, as shown in Figure 12.

1. **Enhanced Mobile Broadband (eMBB).** eMBB is the most obvious extension of LTE capability, providing higher speeds for applications such as streaming, Web access, video conferencing, and virtual reality. Highest speeds will occur in small cells with limited movement speed of end users, such as with pedestrians.

2. **Massive Machine-Type Communications (mMTC).** Massive machine-type communications extends LTE Internet of Things capabilities—for example, NB-IoT—

---

[25] Rysavy Research analysis based on information about commercially available chipsets. Not all LTE features are available simultaneously, and thus throughputs do not necessarily scale linearly with items such as bandwidth. See also the following article about achieving gigabit speeds with LTE: Ars Technica, "Qualcomm's new LTE modem will make gigabit download speeds easier to hit," February 21, 2017. Available at https://arstechnica.com/gadgets/2017/02/qualcomms-new-lte-modem-will-make-gigabit-download-speeds-easier-to-hit/#p3.

to support huge numbers of devices with lower costs, enhanced coverage, and long battery life. As shown in the ITU objectives, below, 5G will support ten times as many devices in an area as LTE.

3. **Ultra-Reliable and Low Latency Communications (URLLC).** Of the three categories, URLLC enables wireless applications never before possible. Driven by high dependability and extremely short network traversal time, URLLC, also referred to as "mission-critical" communications, will enable industrial automation, drone control, new medical applications, and autonomous vehicles. These types of applications are potentially the ones that will deliver the greatest societal benefits, yet unfortunately, at least in the United States, they could possibly be undermined by current network neutrality regulations. This category is also referred to as critical machine-type communications (cMTC).

Figure 12: ITU Use Case Model[26]


Rysavy Research
Enhanced Mobile Broadband
UHD, Virtual Reality
Augmented Reality
Smart Home/ Building
Industry Automation
Smart Cities
Self-Driving Car
Massive Machine Type
Ultra-Reliable and Low Latency

---

[26] For background, see ITU, *IMT Vision – Framework and overall objectives of the future development of IMT for 2020 and beyond*, Recommendation ITU-R M.2083-0, Sep. 2015.

3GPP, in studying 5G, has methodically identified multiple specific use cases in a project called "SMARTER," which are consistent with ITU's model.[27] 3GPP's service dimensions include:

- ❑ Massive Internet of Things (eHealth, wearables, eCity, eFarm).
- ❑ Critical Communications (e.g., vehicles, drones, industry robots).
- ❑ Enhanced Mobile Broadband (e.g., augmented reality, virtual reality, ultra-high definition).
- ❑ Network Operation (e.g., network slicing, connectivity/routing, migration/interworking).

Using small cells and mmWave radio channels, a 5G network built for capacity will deliver 1 Tbps/km^2 or higher, enabling 5G to compete with wireline broadband services.[28]

5G Technical Objectives

Table 4 shows the ITU's objectives for IMT-2020 (5G) relative to IMT-Advanced (4G).

Table 4: ITU Objectives for IMT-2020 compared with IMT-Advanced[29]

	IMT-Advanced	IMT-2020
Peak Data Rate	DL: 1 Gbps UL: 0.05 Gbps	DL: 20 Gbps UL: 10 Gbps
User Experienced Data Rate	10 Mbps	100 Mbps[30]
Peak Spectral Efficiency	DL: 15 bps/Hz UL: 6.75 bps/Hz	DL: 30 bps/Hz UL: 15 bps/Hz
Average Spectral Efficiency		DL eMBB indoor: 9 bps/Hz DL eMBB urban: 7.8 bps/Hz DL eMBB rural: 3.3 bps/Hz UL eMBB indoor: 6.75 bps/Hz UL eMBB urban: 5.4 bps/Hz UL eMBB rural: 1.6 bps/Hz

---

[27] 3GPP TR22.891, *Feasibility Study on New Services and Markets Technology Enablers*; TR22.861 (Massive Internet of Things); TR22.862 (Critical Communications); TR 22.863 (Enhanced Mobile Broadband); TR22.864 (Network Operation).

[28] The hotspot capacity requirement of 10 Mbps/sq. m. is equivalent to 10 Tbps/sq. km. See also *Nokia, Ten key rules of 5G deployment, Enabling 1 Tbit/s/km^2 in 2030*, 2015.

[29] ITU Working Party 5D, *Minimal Requirements Related to Technical Performance for IMT-2020 Radio Interfaces,* Feb 22, 2017. See also 3GPP TR 38.913, *Study on Scenarios and Requirements for Next Generation Access Technologies (Release 14),* V14.2.0, Mar. 2017.

[30] Per ITU, "User experienced data rate is the 5% point of the cumulative distribution function (CDF) of the user throughput."

	IMT-Advanced	IMT-2020
Mobility	350 km/h	500 km/h
User Plane Latency	10 msec	1 msec[31]
Connection Density	100 thousand devices/sq.km.	1 million devices sq./km.
Network Energy Efficiency	1 (normalized)	100X over IMT-Advanced
Area Traffic Capacity	0.1 Mbps/sq. m.	10 Mbps/sq. m. (hot spots)
Bandwidth	Up to 20 MHz/radio channel (up to 100 MHz aggregated)	Up to 1 GHz (single or multipole RF carriers)

In supporting different usage scenarios, not all of these objectives will necessarily be simultaneously available. For example, an IoT application may need to support a large number of devices but at lower throughput rates, while a vehicular application may need high mobility and low latency.

Other expected enhancements include:

- ❑ Deep coverage for machines buried within environments.
- ❑ Extremely low energy demands for ten years or more of battery operation.
- ❑ Low complexity options for inexpensive machine communications.
- ❑ Auto-awareness through discovery and self-optimization.

5G Concepts and Architectures

Standards bodies have not yet defined 5G requirements, but various groups are analyzing the possibilities of what might constitute 5G for network deployments in 2020 or beyond. Often stated goals of 5G include:

- ❑ Being able to support a greater number of end-systems, including IoT applications, at lower average revenue than 4G systems.
- ❑ Peak data rates of multi Gbps (see Table 4 above).
- ❑ Rather than emphasizing peak rates, a more uniform user experience across the coverage area.
- ❑ Support for many frequencies, including existing cellular bands and frequencies above 6 GHz.

---

[31] Per 3GPP TR 38.913 (V14.2.0, Mar. 2017), 0.5 msec for DL and 0.5 msec for UL for URLCC and 4 msec for UL and 4 msec for DL for eMBB.

- ❑ Availability of TDD and FDD modes for all bands.
- ❑ Hierarchical/planned and ad hoc deployment models.
- ❑ Use of licensed and unlicensed bands.
- ❑ Equal support for human-type and machine-type communications. Includes highly efficient small data transmission.
- ❑ Advanced Spectrum Sharing, possibly based on spectrum sharing approaches being developed for the 3.5 GHz band.

Figure 13 shows the transformation of networks, moving from today's LTE-Advanced networks to future LTE-Advanced and eventually 5G networks.

Figure 13: Network Transformation[32]


Wireless Network of the Present
Insufficient Spectrum
Capacity Constrained
Competitive Alternative to Wireline for Some
Wireless Network of the Future
Balanced Portfolio of Licensed and Unlicensed Spectrum
Significantly Greater Capacity
Competitive Alternative to Wireline for Many
Macro Cells Will Continue to Provide Coverage
Selective, Well-Defined Spectrum Sharing with Some Government Systems
Wi-Fi Adds Capacity but Only in Subset of Coverage Area
Small Cells at Higher Frequencies for Capacity
Network Design:
Larger cells on average
Some small cells
Some advanced radio methods
Wi-Fi and cellular mostly operate independently
Limited sharing of spectrum with government
Frequencies: current cellular (600 MHz to 2.5 GHz)
Total spectrum used: approximately 1 GHz
Network Design:
Smaller cells on average
Many small cells
Many advanced radio methods (smart antennas, etc.)
Unlicensed- and licensed-spectrum technologies work together in integrated network
Selective sharing of spectrum with government
Frequencies: current cellular bands and higher frequencies, including mmWave
Total spectrum used: many GHz
Rysavy Research

The fundamental decision for 5G is how to best leverage existing technology investments in LTE while exploiting new spectrum and new technology capabilities. 5G design emphasizes ways to combine existing 4G LTE networks with capabilities provided by 5G. One approach likely to be used by many operators is to use LTE in existing frequency bands and the 5G NR in new bands, such as mmWave, as shown in Figure 14. 5G NR, however, will operate in all frequencies, and just as 2G and 3G spectrum has been re-farmed for LTE, existing cellular bands will eventually be re-farmed for 5G.

---

[32] See also Rysavy Research infographic, "Mobile Broadband Networks of the Future," April 2014. Available at http://www.rysavy.com/Articles/2014-05-Networks-of-the-Future-Infographic.pdf.

Figure 14: 5G Combining of LTE and New Radio Technologies


Existing Cellular Bands
LTE for extended period
Eventually 5G radio
3 GHz
10 GHz
New 5G Bands
Wide radio bands
5G radio methods
300 GHz
Core Network (5G or LTE) Integrates Existing LTE in Cellular Bands with 5G Radio in New Bands
Rysavy Research

As shown in Figure 15, higher frequency bands in 5G will provide capacity with smaller cells, and lower bands will provide coverage with larger cells. This is similar to the approach taken in 4G.

Figure 15: Characteristics of Different Bands[33]


400 MHz
3 GHz
6 GHz
10 GHz
cmWave
30 GHz
mmWave
90 GHz
Different characteristics, licensing, sharing and usage schemes
Carrier BW
→n*20MHz
x * 100 MHz
1-2GHz
Duplexing
FDD
TDD
Cell size
Macro
Small
Ultra Dense
Coverage
Capacity

---

[33] Nokia, *Vision & Priorities for Next Generation Radio Technology*, 3GPP RAN workshop on 5G, Sep. 17-18, 2015.

New radio methods in NR will boost performance and will co-exist with future versions of LTE. 3GPP, in Release 14, completed a study item on 5G NR and will specify NR in Release 15.

Figure 16: Evolution to 5G Including LTE Improvements and New 5G Radio Methods



While many deployments will integrate LTE and NR, some operators could choose NR-only deployments.

5G New Radio (NR)

3GPP is defining 5G NR in Release 15, with an initial release for non-standalone operation scheduled for March 2018 and full release for standalone version scheduled for September 2018. Release 16 will add additional capabilities to the radio, such as support for URLLC. Despite specifications not being finalized, the following are planned capabilities and features of NR in Release 15:

- Ability to operate in any frequency band, including low, mid, and high bands.
- Network can support both LTE and 5G NR, including dual connectivity with which devices have simultaneous connections to LTE and NR.
- Carrier aggregation for multiple NR carriers.
- 5 Gbps peak downlink throughput in initial releases, increasing to 50 Gbps in subsequent versions.
- OFDMA in downlink and uplink, with optional Single Carrier Frequency Division Multiple Access (SC-FDMA) for uplink. Radio approach for URLLC to be defined in

Release 16, but Release 15 will provide physical layer frame structure and numerology support.

- Massive MIMO and beamforming.
- Ability to support either FDD or TDD modes for 5G radio bands.
- Numerologies of 2^N X 15 kHz for subcarrier spacing up to 120 kHz or 240 kHz. This approach, depicted in Figure 17, supports both narrow radio channels (for example, 1 MHz), or wide ones (for example, 400 MHz). Phase 1 likely to support a maximum of 400 MHz bandwidth with 240 kHz subcarrier spacing.
- Error correction through low-density parity codes (LDPC), which are computationally more efficient than LTE turbo codes at higher data rates.
- Standards-based cloud RAN support, compared with proprietary LTE approaches, that specifies a split between the PDCP and Radio Link Control (RLC) protocol layers.
- Self-contained integrated subframes that combine scheduling, data, and acknowledgement.
- Future-proofing by providing a flexible radio framework that has forward compatibility to support future, currently unknown services, such as URLLC to be specified in Release 16.
- Scalable transmission time intervals with short time intervals for low latency and longer time intervals for higher spectral efficiency.
- QoS support using a new model.
- Dynamic co-existence with LTE in the same radio channels. (See the Appendix section “LTE-NR Co-existence” for more details.)

According to one 5G Americas member company in 2017, operators globally have expressed interest in deploying NR in a wide variety of bands, including current cellular bands, 3.5 GHz, and mmWave bands.

Release 16 will add support for:

- URLCC.
- Shared spectrum operation.
- 5 GHz unlicensed spectrum operation based on current LTE approaches such as LAA, LWA, LWIP, and RAN Controlled LTE Wireless LAN Interworking (RCLWI).
- Possibly integrated access and backhaul based on a Release 15 study item. See the appendix section, “Integrated Access and Backhaul,” for more details.
- Other, as yet unknown, features.

The ability to simultaneously transmit and receive on the same frequency has been stated in the past as an objective of 5G, and although such capability remains of interest, it is not currently being specified.

Figure 17: Hypothetical Example of 5G Numerology



Expected 5G Performance

Predicting the 5G user experience is challenging because 5G will be deployed in many configurations, including different bands and with varying width radio channels. In addition, the throughput rates a user experiences depend on signal quality, device capability, and network loading. Some early predictions, however, are possible by examining the ITU objectives, the expected width of radio channels, and results from simulation studies.

The ITU objectives are that in a 5G network, 95% or more users should be able to experience at least 100 Mbps, which is also termed as cell-edge throughput. Examining the simulation results in the appendix section on 5G, “Performance,” such results appear feasible using 200 MHz or wider radio channels. The results also suggest that average or typical rates could reach 500 Mbps using 200 MHz radio channels and 1 Gbps using 400 MHz radio channels.

Just as LTE throughputs have increased significantly over this decade, 5G performance will keep improving over the next ten years. One 5G Americas member expects that the 5G theoretical peak rate could be 5 Gbps in 2020, rising to 50 Gbps by 2024.

Release 15 Non-Standalone and Standalone Options

3GPP is specifying the first phase of 5G in Release 15. So that operators can deploy 5G sooner, 3GPP divided Release 15 into two sets of specifications. The first and earlier set of specifications define how a 5G RAN can integrate with an LTE network in what 3GPP calls a non-standalone option. In this earliest version (architecture option 3), NR will rely on an existing LTE network, both in the RAN and in the core.

The complete Release 15 specifications will also define a 5G core network. Figure 18 shows some of the architecture options. Options 3, 4 and 7 are the non-standalone options and options 1, 2, and 5 are standalone. The appendix section, “5G Architecture Options,” discusses all of the deployment options in greater detail.

Figure 18**: Release 15 Non-Standalone and Standalone Options**


Rysavy Research
LTE
Option 1 (Existing LTE)
LTE Core
NR
LTE
Option 3
(NR Introduction)
Option 7
Option 5
LTE
NR
Option 4
5G Core
Option 2
NR

Note: Three Versions of Option 3, Two Versions of Option 4, and Three Versions of Option 7

5G Schedule3GPP is currently standardizing 5G in Release 15, which will complete the non-standalone version of 5G in March 2018. Based on a typical minimum period of 18 months to build and deploy the technology, initial 5G NSA deployments could occur toward the end of 2019 or the beginning of 2020. 3GPP will complete the full Release 15 specifications in September 2018, enabling deployments in 2020. Release 16, which is the second phase of 5G, will be complete at the end of 2019, and Release 16 deployments could occur in 2021. In 2020, 3GPP will begin work on Release 17 which will include as yet unknown capabilities.

Figure 19Figure 19 shows the current schedule for 5G development and deployment. 3GPP is currently standardizing 5G in Release 15, which will complete the non-standalone version of 5G in March 2018. Based on a typical minimum period of 18 months to build and deploy the technology, initial 5G NSA deployments could occur toward the end of 2019 or the beginning of 2020. 3GPP will complete the full Release 15 specifications in September 2018, enabling deployments in 2020. Release 16, which is the second phase of 5G, will be complete at the end of 2019, and Release 16 deployments could occur in 2021. In 2020, 3GPP will begin work on Release 17 which will include as yet unknown capabilities.

Figure 19: 5G Schedule[34]


Rysavy Research
3GPP Release 14
5G Study Items
Pre-Standard
Deployments
3GPP Release 15
5G Non Standalone
18 months
Release 15 5G
NSA Deployments
Release 15
Standalone
18 months
Release 15 Standalone
Deployments
Standardization
3GPP Release 16
5G Phase 2
18 months
Release 16
Deployments
3GPP Release 17
5G Enhancements
2016
2017
2018
2019
2020
2021

5G Core Network

Release 15 also defines initial core network capabilities that support QoS and network slicing. See the 5G appendix section, “Architecture,” for more details. A study item in Release 15 will study integrated access and backhaul, with which base stations can use the 5G radio channel for backhaul. This capability could become a work item for Release 16. See the appendix section, “Integrated Access and Backhaul,” for more details.

Many operators will virtualize their 5G core networks, just as they have for LTE, but such virtualization is outside the scope of 3GPP specifications.

5G Device Availability

User devices capable of 5G operation have not yet been announced, but availability will likely follow the trends of previous generations of networks. Initial devices, possibly in the 2019 timeframe, will likely include routers that have a 5G radio and use Wi-Fi for local Hotspot capability and USB modems. Handset vendors are in the early stages of designing mmWave support into smartphones.[35] These devices could come online in the 2021 timeframe, although this estimate could tighten or lengthen depending on chipset availability and handset vendor plans.

---

[34] 3GPP and 5G Americas member contribution. Completion based on anticipated ASN.1 freeze dates.

[35] For example, see “Wireless Week, Apple Wants to Test Performance at 28 GHz, 39 GHz for 5G Devices,” May 24, 2017, https://www.wirelessweek.com/news/2017/05/apple-wants-test-performance-28-ghz-39-ghz-5g-devices, viewed May 29, 2017.

mmWave

Use of higher frequencies, such as above 6 GHz, represents one of the greatest opportunities for higher throughputs and higher capacity. This benefit derives from the potential availability of ten times the amount of spectrum as is currently available, with multiple GHz of contiguous spectrum. But these higher frequencies, especially mmWave frequencies (above 30 GHz), are suitable only over short distances, as explained below. The combination of lower and higher frequencies is therefore crucial for 5G operation. Lower bands can be devoted to coverage and control, while higher bands can provide opportunistic access for high data rates. The lower and higher spectrum bands can operate in a carrier aggregation or dual connectivity model. Initial 5G specifications include such dual-connectivity capability.

Compared with lower frequencies, mmWave frequencies suffer from worse propagation characteristics, even in line-of-sight conditions, because the comparatively smaller aperture area of the receiver's antenna requires some form of beamforming at the transmit side, and potentially even at the receive side. Fortunately, the smaller form factors of mmWave antennas allow for dense packing of antenna arrays. Experimental systems using antenna arrays have demonstrated reliable communications at 28 GHz, even in dense, urban, non-line-of-sight conditions, for distances up to 200 meters.[36] Arrays at the terminal side are space-constrained, but some basic beamforming at the terminal is possible. On the base station side, the arrays may include hundreds of antennas in an approach called "massive MIMO."

Figure 20 shows how an increasing number of antenna elements can extend coverage through tighter beams. A 77 X 77 antenna array (6,000 elements) can exceed a kilometer at 3.5 GHz (33 dBm transmit power) and reach over 800 meters, even at 30 GHz.

---

[36] Samsung, *5G Vision,* February 2015. Available at http://www.samsung.com/global/business-images/insights/2015/Samsung-5G-Vision-0.pdf.

Figure 20: Range Relative to Number of Antenna Elements[37]


Tx power
33 dBm
3.5GHz
10GHz
20GHz
30GHz
Antenna
0m
300m
600m
900m
1200m
139m
85m
64m
294m
4x4
626m
7x7
850m
14x14
1240m
10x10
490m
20x20
716m
39x39
1030m
20x20
438m
39x39
630m
77x77
913m
29x29
402m
58x58
587m
115x115
853m
20 cm
40 cm
80 cm

More typically, mmWave cells will employ shorter ranges of 50 to 200 meters. Extreme densification is another way that 5G networks will achieve massive increases in capacity. 3G networks reached densities of four to five base stations per sq. km, 4G networks eight to 10, but 5G networks may reach densities of 40 to 50.[38] A likely 5G architecture will use the macro cell for control information, coverage, and fallback, but small cells, often operating at higher frequencies, for high-bandwidth data communication. Either wireless connections or fiber will provide backhaul. Figure 21 shows how such an approach could also employ beamforming and beam tracking when using mmWave bands in the small cells.

---

[37] Dr. Seizo Onoe, NTT DOCOMO, presentation at Brooklyn 5G Summit, Apr. 21, 2016. Used by permission.

[38] IEEE Wireless Communications, *5G Ultra-Dense Cellular Networks,* Feb. 2016.

Figure 21: 5G Architecture for Low-Band/High-Band Integration


Massive MIMO Small Cell Using mmWave with Beamforming and Beam Tracking
Elevation Beamforming
Wireless Backhaul Option
Reflected Path
Macro Coverage Using Sub 6 GHz
Rysavy Research

In combination, the various methods expected in 5G will provide users in mmWave band hotspot coverage at least a 100-fold increase in throughput over LTE, achieved by:

- ❑ Five- to 10-fold gains due to fewer users in each small cell. (Five to ten times as many cells.)
- ❑ 10-fold gains from access to much larger amounts of spectrum.
- ❑ Three-fold gains or more from improved spectral efficiency.

It is this huge increase in capacity, combined with Gbps performance, that will allow 5G to compete with wireline networks.[39]

Network Slicing

Not only will 5G networks include a new radio, but thanks to virtualization, these networks will be able to present multiple faces for different use cases using a concept called network slicing. This architecture allows an operator to provide multiple services with different performance characteristics. Each network slice operates as an independent, virtualized version of the network. For an application, the network slice is the only network it sees. The other slices, to which the customer is not subscribed, are invisible and inaccessible. The advantage of this architecture is that the operator can create slices that are fine-tuned for specific use cases. One slice could target autonomous vehicles, another enhanced mobile broadband, another low-throughput IoT sensors, and so on.

Figure 22 shows the network slicing architecture, with devices having access to only the slice or slices for which they have subscriptions. Each slice has radio resources allocated, with specific QoS characteristics. Within the core network, virtualized core network functions support each slice and provide connections to external networks.[40]

---

[39] For a further discussion of 5G capacity and ability to compete with wireline networks, refer to Datacomm Research and Rysavy Research, *Broadband Disruption: How 5G Will Reshape the Competitive Landscape*, 2017, available at https://datacommresearch.com/reports-broadband/.

Figure 22: Network Slicing Architecture


Radio Resources Allocated Across Slices, Each with Specific QoS Characteristics
Virtualized Core Network Functions Support Each Slice
Devices Access Specific Slice(s)
Radio Access Network
Core Network
Device C (Smartphone)
Device D (Car)
Device E (Sensor)
Device B (Medical)
Radio Access Network Slice 1
Radio Access Network Slice 2
Radio Access Network Slice N
Radio Access Network Slice N+1
Core Network Slice 1
Core Network Slice 2
Core Network Slice N
Core Network Slice N+1
External Networks
Rysavy Research

Information-Centric Networking

For many usage scenarios, wireless networks provide broadband access to the internet, a network that itself is evolving. The internet is based on a node-centric design developed forty years ago. The point-to-point method of communication the internet uses has functioned well for a vast array of applications but is not optimal for the way content is developed and distributed today. Industry and academic organizations are researching a concept called “Information-Centric Networking.” ICN seeks a new approach of in-network caching that distributes content on a large scale, cost-efficiently and securely.

Most internet content uses Uniform Resource Identifiers (URIs) to locate objects and define specific location-dependent IP addresses. This approach, however, causes problems when content moves, sites change domains, or content is replicated and each copy appears as a different object. Developments such as peer-to-peer overlays and content distribution networks (such as Akamai) that distribute cached copies of content are a first step toward an information-centric communication model.

ICN is built from the ground up on the assumption of mobility, so it eliminates the mobility overlays on which current mobile broadband networks depend. The approach will be able to place information anywhere in the network with immediate and easy retrieval.

Key principles of ICN include:

---

[40] For more details, see 5G Americas, *Network Slicing for 5G Networks & Services*, November 2016. Available at: http://www.5gamericas.org/files/3214/7975/0104/5G_Americas_Network_Slicing_11.21_Final.pdf.

- The architecture inherently supports user mobility.
- Network operations are name-based instead of address- or node-based.
- The network itself stores, processes, and forwards information.
- Intrinsic security guarantees the integrity of every data object.

The goal of ICN is to simplify the storage and distribution of gigantic amounts of content while reducing the amount of traffic and latency users face when accessing the content. The internet cannot just be replaced, however, so in initial stages, ICN would operate as an overlay, and over time would assume an increasing percentage of the functions within the internet. ICN would not discard IP; rather, it seeks to generalize the routing concept to enrich networking with new capabilities.

Some technology aspects of ICN include:

- Information retrieval from multiple sources without needing to know the location of the information.
- Multipath communications that improves user performance and traffic load balancing.
- Subsequent requests for the same data will be served locally without needing to fetch it from original repository.
- Elimination of the name-to-location indirection associated with Domain Name Service (DNS).

Because mobility is such a central aspect of ICN, mobile network operators are in a unique position to participate in ICN-related research and development, and to do so as part of 5G development. ICN has not progressed to a level at which 3GPP specification work could include it, so instead promoters are ensuring that 5G specification work does not preclude it. With this approach, operators in the 2020s will have the option of overlaying ICN capability on their 5G networks. ICN could even be implemented as a 5G network slice for mobile and end-systems capable of ICN.

3GPP Releases

3GPP standards development falls into three principal areas: radio interfaces, core networks, and services. Progress in the 3GPP family of technologies has occurred in multiple phases, first with GSM, then GPRS, EDGE, UMTS, HSPA, HSPA+, LTE, LTE-Advanced, and now LTE-Advanced Pro. Underlying radio approaches have evolved from Time Division Multiple Access (TDMA) to CDMA to Orthogonal Frequency Division Multiple Access (OFDMA), which is the basis of LTE. 3GPP is also involved in standardization of 5G technology.

Table 5 summarizes the key 3GPP technologies and their characteristics.

Table 5: Characteristics of 3GPP Technologies

Technology Name	Type	Characteristics	Typical Downlink Speed	Typical Uplink Speed
HSPA[41]	WCDMA	Data service for UMTS networks. An enhancement to original UMTS data service.	1 Mbps to 4 Mbps	500 Kbps to 2 Mbps
HSPA+	WCDMA	Evolution of HSPA in various stages to increase throughput and capacity and to lower latency.	1.9 Mbps to 8.8 Mbps in 5+5 MHz[42] 3.8 Mbps to 17.6 Mbps with dual-carrier in 10+5 MHz	1 Mbps to 4 Mbps in 5+5 MHz or in 10+5 MHz
LTE	OFDMA	New radio interface that can use wide radio channels and deliver extremely high throughput rates. All communications handled in IP domain.	6.5 to 26.3 Mbps in 10+10 MHz[43]	6.0 to 13.0 Mbps in 10+10 MHz
LTE-Advanced	OFDMA	Advanced version of LTE designed to meet IMT-Advanced requirements.	Significant gains through carrier aggregation, 4X2 and 4X4 MIMO, and 256 QAM modulation.	

User-achievable rates and additional details on typical rates are covered in the appendix section “Data Throughput.”

3GPP develops specifications in releases, with each release addressing multiple technologies. For example, Release 8 defined dual-carrier operation for HSPA but also introduced LTE. Each release adds new features and improves performance of existing functionality in different ways. Table 6 summarizes some key features of different 3GPP releases.

---

[41] HSPA and HSPA+ throughput rates are for a 5+5 MHz deployment.

[42] “5+5 MHz” means 5 MHz used for the downlink and 5 MHz used for the uplink.

[43] 5G Americas member company analysis for downlink and uplink. Assumes single user with 50% load in other sectors. AT&T and Verizon are quoting typical user rates of 5-12 Mbps on the downlink and 2-5 Mbps on the uplink for their networks. See additional LTE throughput information in the section below, “LTE Throughput.”

Table 6: Key Features in 3GPP Releases[44]

Release	Year	Key Features
99	1999	First deployable version of UMTS.
5	2002	High Speed Downlink Packet Access (HSDPA) for UMTS.
6	2005	High Speed Uplink Packet Access (HSUPA) for UMTS.
7	2008	HSPA+ with higher-order modulation and MIMO.
8	2009	Long Term Evolution. Dual-carrier HSDPA.
10	2011	LTE-Advanced, including carrier aggregation and eICIC.
11	2013	Coordinated Multi Point (CoMP).
12	2015	Public safety support. Device-to-device communications. Dual Connectivity. 256 QAM on the downlink.
13	2016	LTE-Advanced Pro features. LTE operation in unlicensed bands using LAA. Full-dimension MIMO. LTE-WLAN Aggregation. Narrowband Internet of Things.
14	2017	LTE-Advanced Pro additional features, such as eLAA (adding uplink to LAA) and cellular V2X communications. Study item for 5G "New Radio."
15	2018	Additional LTE-Advanced Pro features, such as ultra-reliable low-latency communications. Phase 1 of 5G. Will emphasize enhanced mobile broadband use case and sub-40 GHz operation. Includes Massive MIMO, beamforming, and 4G-5G interworking, including ability for LTE connectivity to a 5G CN.
16	2019	Phase 2 of 5G. Full compliance with ITU IMT-2020 requirements. Will add URLLC, spectrum sharing, unlicensed operation, and multiple other enhancements.
17	2021	Further LTE and 5G enhancements.

Refer to the Appendix section "3GPP Releases" for a more detailed listing of features in each 3GPP Release.

---

[44] After Release 99, release versions went to a numerical designation beginning with Release 4, instead of designation by year.

Supporting Technologies and Architectures

Network architects design networks using a deep and wide toolkit, including multiples types of cell sizes, integration with unlicensed spectrum, smart antennas, converged services, and virtualization.

Multiple Cell Types

Operators have many choices for providing coverage. Lower frequencies propagate further and thus require fewer cells for coverage. The resulting network, however, has lower capacity than one with more cells, so operators must continually evaluate cell placement with respect to both coverage and capacity.

Table 7 lists the many types of cells. Note that the distinctions, such as radius, are not absolute—perhaps one reason the term "small cell" has become popular, as it encompasses picocells, metrocells, femtocells, and sometimes Wi-Fi.

With "plug-and-play" capability derived from self-configuring and self-organizing features, small cells will increasingly be deployed in an ad hoc manner, anywhere power and backhaul are available, yet will operate in tight coordination with the rest of the network.

A proliferation of small cells inside buildings will also provide coverage from inside to outside, such as in city streets, the reverse of traditional coverage that extends from outdoor cells to inside.

Table 7: Types of Cells and Typical Characteristics (Not Formally Defined)

Type of Cell	Characteristics
Macro cell	Wide-area coverage. LTE supports cells up to 100 km in range, but typical distances are .5 to 5 km radius. Always installed outdoors.
Microcell	Covers a smaller area, such as a hotel or mall. Range to 2 km, 5-10W, and 256-512 users. Usually installed outdoors.
Picocell	Indoor or outdoor. Outdoor cells, also called "metrocells." Typical range 15 to 200 meters outdoors and 10 to 25 meters indoors, 1-2W, 64-128 users. Deployed by operators primarily to expand capacity.
Consumer Femtocell	Indoors. Range to 10 meters, less than 50 mW, and 4 to 6 users. Capacity and coverage benefit. Usually deployed by end users using their own backhaul.
Enterprise Femtocell	Indoors. Range to 25 meters, 100-250 mW, 16-32 users. Capacity and coverage benefit. Deployed by operators.
Distributed antenna system	Expands indoor or outdoor coverage. Same hardware can support multiple operators (neutral-host) since antenna can support broad frequency range and multiple technologies. Indoor deployments are typically in larger spaces such as airports. Has also been deployed outdoors for coverage and capacity expansion.

Type of Cell	Characteristics
Remote radio head (RRH)	Uses baseband at existing macro site or centralized baseband equipment. If centralized, the system is called "cloud RAN." Requires fiber connection.
Wi-Fi	Primarily provides capacity expansion. Neutral-host capability allows multiple operators to share infrastructure.

Smalls Cells and Heterogeneous Networks

Historically, increasing the number of cell sites has been the primary method for increasing capacity, providing gains far greater than what can be achieved by improvements in spectral efficiency alone. The next wave of densification is by using what the industry calls "small cells."

Central to small-cell support is the heterogeneous network architecture, with multiple types of cells serving a coverage area, varying in frequencies used, radius, and even radio technology used.

HetNets offer significant increases in capacity and improvements, including:

1. Smaller cells, such as open femtocells (home-area coverage) and picocells (city-block-area coverage), inherently increase capacity because each cell serves a smaller number of users.

2. Strategic placement of picocells within the macro cell provides the means to absorb traffic in areas where there are higher concentrations of users. Locations can include businesses, airports, stadiums, convention centers, hotels, hospitals, shopping malls, high-rise residential complexes, and college campuses.

3. Smaller cells can also improve signal quality in areas where the signal from the macro cell is weak.

Essential elements for practical HetNet deployment are self-optimization and self-configuration, especially as the industry transitions from tens of thousands of cells to hundreds of thousands, and eventually to millions. The appendix covers technical aspects of HetNets in the sections, "Heterogeneous Networks and Small Cells" and "Self-Organizing Networks."

While promising in the long term, one immediate challenge in deploying a large number of small cells is backhaul, since access to fiber is not necessarily available and line-of-sight microwave links are not always feasible. Site acquisition and the need for multiple operators to deploy their own cells in a coverage area are additional challenges.[45] Figure 23 depicts the challenges.

---

[45] For further discussion of this topic, refer to 5G Americas and Small Cell Forum, *Small cell siting challenges,"* February 2017.

Figure 23: Small-Cell Challenges


Macro
Interference
Coordination
Fiber Backhaul
Connection
Fiber?
Microwave?
Unlicensed
Mesh Wi-Fi?
Operator Core Network
Challenges:
- Site acquisition
- Multiple operators have to deploy cells
- Backhaul
- Interference Coordination
- Management
- Power
Rysavy Research

Despite these challenges and the relatively small number of small cells deployed today, many believe small-cell deployments will accelerate.[46]

In the United States, the FCC in April 2017 issued a Notice of Proposed Rulemaking, titled "Accelerating Wireless Broadband Deployment by Removing Barriers to Infrastructure

---

[46] For example, see Fierce Wireless, "Crown Castle expects its small cell business to double in next 2 years," April 25, 2017. Available at http://www.fiercewireless.com/wireless/crown-castle-expects-its-small-cell-business-to-double-next-two-years.

Investment," that seeks to streamline items such as site acquisition and consistent pricing.[47]

5G small-cell considerations include:

- ☐ Due to limited propagation at mmWave frequencies, 5G small-cell deployments will be dense and involve large numbers of sites. Inter-site distances (ISDs) will range from 100 to 300 meters in many deployments, with 200 meters a typical value.[48]
- ☐ The high-capacity of mmWave small cells will require multi-Gbps backhaul connections using an expected combination of fiber, mmWave radio in point-to-point connections, and 5G self-backhaul.
- ☐ The expected use of cloud RAN and centralized base station facilities will simplify equipment at the site, facilitating dense deployments.
- ☐ Dense deployments will motivate neutral-host (multi-tenant) approaches, but these are outside the scope of specification efforts.

The effective range of a mmWave small cell depends on multiple factors, including whether line-of-sight is available, extent of foliage, pole height, whether user equipment is indoors or outdoors, and the types of building materials the signal must pass through to reach indoor equipment.

Despite the challenges, small cells will ultimately contribute greatly to increased network capacity. Table 8 lists possible configurations. Note that many of these approaches can be combined, such as using picos and Wi-Fi offload.

Table 8: Small-Cell Approaches

Small-Cell Approach	Characteristics
Macro plus small cells in select areas.	Significant standards support. Femtocells or picocells can use the same radio carriers as macro (less total spectrum needed) or can use different radio carriers (greater total capacity).
Macro in licensed band plus LTE operation in unlicensed bands.	Promising approach for augmenting LTE capacity in scenarios where operator is deploying LTE small cells.[49] See discussion below in the section on unlicensed spectrum integration.

---

[47] FCC, *Wireless Infrastructure NPRM and NOI*, April 21, 2017. Available at https://www.fcc.gov/document/wireless-infrastructure-nprm-and-noi.

[48] 5G Americas member contributions.

[49] See Rysavy Research, *Accelerating Innovation in Unlicensed Spectrum*, Fierce Wireless, November 2016. Available at http://www.rysavy.com/Articles/2016-11-Innovation-Unlicensed-Spectrum.pdf. See also Rysavy Research, *Will LTE in Unlicensed Spectrum Unlock a Vast Store of Mobile Broadband Capacity?* MIMO World, June 2014. Available at http://www.mimoworld.com/?p=2377.

Small-Cell Approach	Characteristics
Macro (or small-cell) cellular in licensed band plus Wi-Fi.	Extensively used today with increased use anticipated. Particularly attractive for expanding capacity in coverage areas where Wi-Fi infrastructure exists but small cells with LTE do not. LTE Wi-Fi Aggregation (being specified in Release 13) is another approach, as are MP-TCP and MP-QUIC.
Wi-Fi only.	Low-cost approach for high-capacity mobile broadband coverage, but impossible to provide large-area continuous coverage without cellular component.

Neutral-Host Small Cells

Multi-operator and neutral-host solutions could accelerate deployment of small cells.[50] Currently, nearly all small-cell deployments are operator-specific, but in the future, deployments supporting multiple operators could reduce the cost per operator to provide coverage.

A candidate band for neutral-host small cells is 3.5 GHz, using LTE TDD and MulteFire as potential technologies. Wi-Fi technology also addresses neutral-host configurations at the access level, but it has roaming and authentication challenges. HotSpot 2.0 (covered in the appendix) addresses roaming and authentication.

Unlicensed Spectrum Integration

Unlicensed spectrum is becoming ever more important to mobile broadband networks. Initial use was rudimentary offload onto Wi-Fi networks, but now, Wi-Fi networks are becoming more tightly integrated into cellular networks. Efforts are also underway to use LTE in unlicensed spectrum.

Unlicensed spectrum adds to capacity in two ways. First, a large amount of spectrum (approximately 500 MHz) is available across the 2.4 GHz and 5 GHz bands, with the 3.5 GHz band adding further spectrum in the future. A significant amount of unlicensed spectrum is also available in mmWave bands, with 7 GHz already in use in the United States (57 to 64 GHz) and an additional 7 GHz in 5G spectrum allocations. Second, unlicensed spectrum is mostly used in small coverage areas, resulting in high-frequency re-use and much higher throughput rates per square meter of coverage versus typical cellular deployments.

The IEEE 802.11 family of technologies has experienced rapid growth, mainly in private deployments. The latest 802.11 standard, 802.11ac, offers peak theoretical throughputs in excess of 1 Gbps and improved range through use of higher-order MIMO. 802.11ac Wave 2 products include a Multi-user MIMO capability that further increases capacity and throughput. IEEE is developing a subsequent version, 802.11ax, that emphasizes capacity improvements as well as higher throughputs. In the mmWave frequencies, IEEE has developed 802.11ad, which operates at 60 GHz, and the standards body is currently working on a successor technology, 802.11ay.

---

[50] 5G Americas and Small Cell Forum, *Multi-operator and neutral host small cells; Drivers, architectures, planning and regulation,* December 2016. Report available at http://www.5gamericas.org/files/4914/8193/1104/SCF191_Multi-operator_neutral_host_small_cells.pdf.

Integration between mobile broadband and Wi-Fi networks can be either loose or tight. Loose integration means data traffic routes directly to the internet and minimizes traversal of the operator network. This is called “local breakout.” Tight integration means data traffic, or select portions thereof, may traverse the operator core network. An example is Wi-Fi calling, which uses IP Multimedia Subsystem.

Although offloading onto Wi-Fi can reduce traffic on the core network, the Wi-Fi network does not necessarily always have greater spare capacity than the cellular network. The goal of future integrated cellular/Wi-Fi networks is to intelligently load balance between the two. Simultaneous cellular/Wi-Fi connections will also become possible. For example, in Release 13, 3GPP introduces link aggregation of Wi-Fi and LTE through LWA and LWIP.

Successfully offloading data and providing users a good experience mandates measures such as automatically provisioning subscriber devices with the necessary Wi-Fi configuration options and automatically authenticating subscribers on supported public Wi-Fi networks. Many stakeholders are working toward tighter integration between Wi-Fi and cellular networks.

Another approach for using unlicensed spectrum employs LTE as the radio technology, initially in a version referred to as LTE-Unlicensed, which works with Releases 10-12 of LTE, as defined in the LTE-U Forum. In Release 13, 3GPP specified LAA, which implements listen-before-talk capability, a requirement for unlicensed operation in Europe and Japan. Initially, carrier aggregation combines a licensed carrier with an unlicensed 20 MHz carrier in the 5 GHz band as a supplemental channel, with the aggregation of multiple unlicensed channels an eventual possibility. Operating LTE in unlicensed bands could decrease the need for handoffs to Wi-Fi. Up to 32 unlicensed carriers (of 20 MHz each) can be aggregated to theoretically access 640 MHz of unlicensed spectrum. LAA may also be deployed in 3.5 GHz bands. Enhanced LAA (eLAA), specified in Release 14, adds uplink use of unlicensed spectrum. Carriers are now conducting LAA trials.[51]

A concern with using LTE in unlicensed bands is whether it will be a fair neighbor to Wi-Fi users. LTE-U based on Release 10-12 addresses this concern by selecting clear channels to use and measuring the channel activity of Wi-Fi users, then using an appropriate duty cycle for fair sharing. License-Assisted Access in Release 13 adds listen-before-talk (LBT) and implements other regulatory requirements that exist in some countries. 3GPP conducted a study and concluded that, “A majority of sources providing evaluation results showed at least one LBT scheme for LAA that does not impact Wi-Fi more than another Wi-Fi network.”[52]

To address co-existence, the cellular industry worked with the Wi-Fi Alliance in 2016 to develop a test plan for LTE-U. The testing goal was to verify that, in a laboratory environment, an LTE-U base station does not impact a Wi-Fi network any more than another Wi-Fi access point.[53]

---

[51] For example, see AT&T, “AT&T Reaches Wireless Speeds of More than 750 Mbps with LTE Licensed Assisted Access (LTE-LAA) Field Trials,” available at http://about.att.com/story/lte_licensed_assisted_access_field_trials.html.

[52] 3GPP, *Technical Specification Group Radio Access Network; Study on Licensed-Assisted Access to Unlicensed Spectrum; (Release 13). 36.889.* See section 9, “Conclusions.”

MulteFire, specified by the MulteFire Alliance, is an application of LTE in unlicensed bands that does not require an anchor in licensed spectrum, opening up the possibility of deployments by non-operator entities, including internet service providers, venue operators, and enterprises. Under a roaming arrangement with cellular operators, LTE customers could roam into MulteFire networks. Figure 24 shows the evolution of the different versions of LTE for unlicensed bands.

Figure 24: Timeline Relationship of LTE-U, LAA, eLAA, and MulteFire



An alternative approach for integrating Wi-Fi is LWA. LTE handles the control plane, but connections occur over separate LTE base stations and Wi-Fi access points. LWA benefits operators that wish to emphasize Wi-Fi technology for harnessing capacity in unlicensed spectrum. LWIP is a variation of LWA that also integrates LTE and Wi-Fi, but by integrating at a higher level of the protocol stack (IP instead of PDCP), it facilitates use of existing Wi-Fi equipment and devices, with integration typically occurring at the eNodeB.

Figure 25 shows how the different technologies exploit licensed and unlicensed spectrum.

---

[53] See Wi-Fi Alliance, "Unlicensed Spectrum," http://www.wi-fi.org/discover-wi-fi/unlicensed-spectrum.

Figure 25: How Different Technologies Harness Spectrum


5 GHz Unlicensed Band
Also 3.5 GHz Band for LAA and MulteFire
Wi-Fi
MulteFire
Wi-Fi
LTE-U
LAA
LWA/LWIP
LTE
LTE
Licensed Cellular Bands
Rysavy Research

Table 9 summarizes the different uses of unlicensed spectrum for public mobile broadband networks.

Table 9: Approaches for Using Unlicensed Spectrum.

	Technology	Attributes
Wi-Fi	Ever-more-sophisticated means to integrate Wi-Fi in successive 3GPP Releases.	Combining Wi-Fi with cellular increases capacity.
Release 13 RAN Controlled LTE WLAN Interworking	Base station can instruct the UE to connect to a WLAN for offload.	Available in late 2017 or 2018 timeframe.

Release 10-12 LTE-U Based on LTE-U Forum Specifications	LTE-U Forum-specified approach for operating LTE in unlicensed spectrum.	Available in 2017. More seamless than Wi-Fi. Cannot be used in some regions (e.g., Europe, Japan).
Release 13 Licensed-Assisted Access	3GPP-specified approach for operating LTE in unlicensed spectrum. Downlink only.	Available in late 2017 or 2018 timeframe. Designed to address global regulatory requirements.
Release 14 Enhanced Licensed-Assisted Access	Addition of uplink operation.	Available in 2019 or 2020 timeframe.
5G Unlicensed Operation	Release 15 has a study item for approaches that Release 16 will standardize.	Potentially available in 2021.
MulteFire	Does not require a licensed anchor.	Potentially creates a neutral-host small cell solution.
LWA	Aggregation of LTE and Wi-Fi connections at PDCP layer.	Part of Release 13. Available in late 2017 or 2018 timeframe.
LWIP	Aggregation of LTE and Wi-Fi connections at IP layer.	Part of Release 13. Available in late 2017 or 2018 timeframe.

Cellular operators are currently emphasizing simple offload to Wi-Fi or LTE-U/LAA. Aggregation techniques, such as LWA and LWIP, do not currently have market traction.

Refer to the appendix section “Unlicensed Spectrum Integration” for further technical details.

Internet of Things and Machine-to-Machine

Machine-to-machine communications, now evolving into the Internet of Things, is a vast opportunity for wireless communications, with all 3GPP technologies potentially playing roles.

The lowest-cost cellular devices enabling M2M communications today are GPRS modems, which risk becoming obsolete as operators sunset their GSM systems. HSPA is also used for M2M communications, as is LTE, which has been optimized to efficiently communicate small bursts of information, making it particularly well suited for M2M.

Low-cost GSM (through Enhanced Coverage GSM IoT [EC-GSM-IoT]) and LTE modem options in 3GPP releases 10 through 13 reduce cost, improve communications range, and extend battery life. See the appendix section “Internet of Things and Machine-to-Machine” for details.

3GPP had a Release 13 study item on how LTE technologies can operate for vehicle communications, including vehicle-to-vehicle and vehicle-to-infrastructure, leveraging device-to-device communications capabilities already specified for LTE in Releases 12 and 13.[54] This work is now being standardized in Release 14.

Developers will use 3GPP wireless technologies for many IoT applications. In other instances, developers will use local area technologies, such as Wi-Fi, Bluetooth Low Energy, and ZigBee. New Low-Power Wide-Area (LPWA) wireless technologies emerging specifically to support IoT include Ingenu, LoRa, and Sigfox. The low-power operation of some of these technologies, including LTE, will permit battery operation over multiple years. Table 10 summarizes the various technologies.

Table 10: Wireless Networks for IoT

Technology	Coverage	Characteristics	Standardization / Specifications
GSM/GPRS/EC-GSM-IoT	Wide area. Huge global coverage.	Lowest-cost cellular modems, risk of network sunsets. Low-throughput.	3GPP
HSPA	Wide area. Huge global coverage.	Low-cost cellular modems. Higher power, high throughput.	3GPP
LTE, NB-IoT	Wide area. Increasing global coverage.	Wide area, expanding coverage, cost/power reductions in successive 3GPP releases. Low to high throughput options.	3GPP
Wi-Fi	Local area.	High throughput, higher power.	IEEE
ZigBee	Local area.	Low throughput, low power.	IEEE
Bluetooth Low Energy	Personal area.	Low throughput, low power.	Bluetooth Special Interest Group
LoRa	Wide area. Emerging deployments.	Low throughput, low power. Unlicensed bands (sub 1 GHz, such as 900 MHz in the U.S.)	LoRa Alliance[55]
Sigfox	Wide area. Emerging deployments.	Low throughput, low power. Unlicensed bands (sub 1 GHz such as 900 MHz in the U.S.)	Sigfox[56]

---

[54] 3GPP, *3GPP TR 36.885, Technical Specification Group Radio Access Network; Study on LTE-based V2X Services; (Release 14).*

[55] For details, see LoRa Alliance, https://www.lora-alliance.org/.

[56] For details, see Sigfox, https://www.sigfox.com/en.

Technology	Coverage	Characteristics	Standardization / Specifications
Ingenu (previously OnRamp Wireless)	Wide area. Emerging deployments.	Low throughput, low power. Using 2.4 GHz ISM band. Uses IEEE 802.15.4k.	Ingenu[57]
Weightless	Wide area. Expected deployments.	Low throughput, low power. Unlicensed bands (sub 1 GHz such as TV White-Space and 900 MHz in the U.S.)	Weightless Special Interest Group[58]

Security is of particular concern to both developers and users of IoT technology. An increasing amount of network-connected infrastructure will result in new security vulnerabilities that are being addressed by concerted effort from the industry.[59]

Smart Antennas and MIMO

Smart antennas, defined with progressively greater capabilities in successive 3GPP releases, provide significant gains in throughput and capacity. By employing multiple antennas at the base station and the subscriber unit, the technology either exploits signals traveling through multiple paths in the environment or does beam steering, in which multiple antennas coordinate their transmissions to focus radio energy in a particular direction.

Initial low-band LTE deployments used 2X2 MIMO on the downlink (two base station transmit antennas, two mobiles receive antennas) and 1X2 on the uplink (one mobile transmit antenna, two base station receive antennas). In the higher bands, 2X2 downlink MIMO has been deployed, but it is more common to employ four antennas for uplink reception in a 1X4 configuration. LTE deployments are now using 4X2 MIMO and 4X4 MIMO on the downlink (four base station transmit antennas). LTE specifications encompass higher-order configurations, such as 4X4 MIMO, 8X2 MIMO, and MU-MIMO on the downlink and 1X4 on the uplink. Practical considerations, such as antenna sizes that are proportional to wavelength, dictate MIMO options for different bands.

Engineers are now experimenting with what are called massive MIMO systems, which employ a far larger number of antenna elements at the base station—64, 128, and eventually even more. Use in 5G of cmWave and mmWave bands, with their short wavelengths, will facilitate massive MIMO, but even before then, 3GPP is developing specifications for massive MIMO for 4G systems in what it calls full-dimension MIMO (FD-MIMO). Release 14 specifies configurations with up to 32 antennas at the base station.

---

[57] For details, see Ingenu, https://www.ingenu.com/.

[58] For details, see http://www.weightless.org/.

[59] For further insight, refer to the Ericsson white paper, *IoT Security,* February 2017, available at https://www.ericsson.com/assets/local/publications/white-papers/wp-iot-security-february-2017.pdf.

Massive MIMO is practical even in cellular frequencies. For example, at 2.5 GHz, an 8X8 array using half wavelength spacing would produce a form factor of 50 cm X 50 cm. Applications of such arrays include beamforming along a horizontal direction as well as beamforming in a vertical direction, such as to serve different levels of high-rise buildings.

See the appendix section “LTE Smart Antennas” and “LTE-Advanced Antenna Technologies” for further details.

Virtualization

Virtualization refers to implementing the functions of infrastructure nodes in software on commercial “off-the-shelf” computing equipment. The approach promises lower capital expenditures, lower operating costs, faster deployment of new services, energy savings, and improved network efficiency. With NFV, multiple tenants will be able to share the same infrastructure, facilitating, for example, mobile virtual network operator (MVNO) and multi-operator virtualized RAN arrangements. NFV, however, also constitutes an entirely new way of building and managing networks, so widespread adoption will occur over a long period.

Both the core network and portions of the radio-access network can be virtualized. The core network, consisting of fewer nodes, is an easier starting point. Virtualizing RAN elements, although more complex, could eventually provide the greatest network efficiency gains, particularly for small-cell deployments where it can facilitate coordination among cells and use of methods such as CoMP and interference coordination. Unlike the core, virtualizing the entire RAN is not possible because a Physical Network Function must terminate the radio interface. As operators virtualize their core networks, they put in place the systems and know-how to extend virtualization to the RAN.

The European Telecommunications Standards Institute (ETSI) is standardizing a framework, including interfaces and reference architectures for virtualization. Other standards and industry groups involved include 3GPP, the Open Networking Foundation, OpenStack, OpenDaylight, and OPNFV.

Figure 26 shows the ETSI framework, in which virtualized network functions are the nodes or applications by which operators build services.

Figure 26: ETSI NFV High-Level Framework


Virtualized Network Functions
VNF
VNF
VNF
VNF
VNF
NFV Infrastructure
Virtual Compute
Virtual Storage
Virtual Network
Virtualization Layer
Compute
Storage
Network
Hardware Resources
Rysavy Research
NFV Management and Orchestration

Some specific use cases for NFV include:

- **5G.** 5G networks will likely be fully virtualized.
- **IMS and VoLTE.** IMS is necessary for VoLTE, but an NFV approach could reduce the complexity associated with the multiple nodes and interfaces in the IMS architecture.
- **Virtualized EPC (VEPC).** The Evolved Packet Core, consisting of the Serving Gateway (SGW), the Packet Gateway (PGW), and Mobile Management Entity (MME), can be virtualized, but doing so will require meeting operator bandwidth, latency, and control plane service requirements.
- **New VEPC Services.** With a virtualized EPC, an operator can more easily create MVNO services, each with its own virtualized MME, SGW, and PGW. An M2M virtualized service is another example of offering a more finely tuned service for the target application. Because the PGW connects to external networks, further opportunities exist for virtualized services to augment networking functions, including video caching, video optimization, parental controls, ad insertion, and firewalls.
- **Cloud RAN.** Pooling of baseband processing in a cloud RAN can, but does not necessarily, use virtualization techniques. Separating the radio function from baseband processing typically requires transporting digitized radio signals across high-bandwidth (multi-Gbps) fiber connections, sometimes referred to as

fronthauling. Refer to the appendix section “Cloud Radio-Access Network (RAN) and Network Virtualization” for a more detailed technical discussion.[60]

Because of higher investment demands, RAN virtualization will take longer to deploy than core network virtualization and likely will occur selectively for small-cell deployments.

For additional details, refer to the 5G Americas white paper, *Bringing Network Function Virtualization to LTE*.[61]

Multi-Access Edge Computing

ETSI is standardizing Multi-access Edge Computing, previously known as Mobile-Edge Computing, a technology that empowers a programmable application environment at the edge of the network, within the RAN.[62] Goals include reduced latency, more efficient network operation for certain applications, and an improved user experience. Although MEC emphasizes 5G, it can also be applied to 4G LTE networks.

Applications that will benefit are ones that require server-side processing but are location specific. Examples include:

- Augmented reality.
- Intelligent video processing, such as transcoding, caching, and acceleration.
- Connected cars.
- Premise-based IoT gateways.

Multicast and Broadcast

Another important new service is video streaming via multicast or broadcast functions. 3GPP has defined multicast/broadcast capabilities for both HSPA and LTE. Mobile TV services have experienced little business success so far, but broadcasting uses the radio resource much more efficiently than having separate point-to-point streams for each user. For example, users at a sporting event might enjoy watching replays on their smartphones. The technology supports these applications; it is a matter of operators and content providers finding appealing applications. The appendix covers technical aspects in more detail.

Remote SIM Provisioning

The GSM Association (GSMA) is developing specifications that make it possible for consumers to purchase unprovisioned devices, select the operator of their choice and then download the subscriber identity module (SIM) application into the device.[63] This capability benefits devices such as watches, health bands, health monitors, and other small connected items. Initial products may be available in 2017.

---

[60] For further details, see “Network Functions Virtualisation,” http://www.etsi.org/technologies-clusters/technologies/nfv. Viewed May 17, 2017.

[61] Available at http://www.4gamericas.org/files/1014/1653/1309/4G_Americas_-_NFV_to_LTE_-_November_2014_-_FINAL.pdf.

[62] For further details, see ETSI, “Multi-access Edge Computing,” http://www.etsi.org/technologies-clusters/technologies/multi-access-edge-computing. Accessed May 17, 2017.

[63] For details, see GSMA, “A New SIM,” available at https://www.gsma.com/rsp/, viewed June 8, 2017.

VoLTE, RCS, WebRTC, and Wi-Fi Calling

Voice has evolved from a separate circuit-switched service in 2G and 3G networks to a packet-switched service in 4G LTE networks that can integrate with other services and applications, such as messaging and video calling. Elements that make these capabilities possible include the quality-of-service mechanisms in LTE, the IMS platform discussed above, implementation of Rich Communications Suite, compliance with GSMA IR.92 guidelines, and optional support for WebRTC.

Voice Support and VoLTE

While 2G and 3G technologies were deployed from the beginning with both voice and data capabilities, LTE networks can be deployed with or without voice support. Moreover, there are two methods available: circuit-switched fallback (CSFB) to 2G/3G and VoIP. Most operators deploying LTE used CSFB initially but are now migrating to VoIP methods with VoLTE that uses IMS. Initial VoLTE deployments occurred in 2012. Because VoLTE needs new software in phones, the transition from circuit-switched voice to VoLTE on a large scale will occur over a number of years as users upgrade their devices.

For the time being, 3GPP operators with UMTS/HSPA networks will continue to use circuit-switched voice for their 3G connections.

Using VoLTE, operators can offer high-definition (HD) voice using the new Adaptive Multi-Rate Wideband (AMR-WB) voice codec. HD voice not only improves voice clarity and intelligibility, it suppresses background noise. AMR-WB extends audio bandwidth to 50-7000 Hz compared with the narrowband codec that provides audio bandwidth of 80-3700 Hz. HD voice will initially function only between callers on the same network. 3GPP has also developed a new voice codec, called “Enhanced Voice Services” (EVS), which will be the successor to AMR and AMR-WB codecs.

Other advantages of LTE’s packetized voice include being able to combine it with other services, such as video calling and presence; half the call set-up time of a 3G connection; and high voice spectral efficiency. With VoLTE’s HD voice quality, lower delay, and higher capacity, operators can compete against OTT VoIP providers. Due to traffic prioritization, VoLTE voice quality remains high even under heavy loads that cause OTT-voice service to deteriorate.

Applications based on WebRTC will also increasingly carry voice sessions. See the section “VoLTE and RCS” in the appendix for more details on LTE voice support.

Rich Communications Suite

An initiative called “Rich Communications Suite” (RCS), supported by many operators and vendors, builds on IMS technology to provide a consistent feature set as well as implementation guidelines, use cases, and reference implementations. RCS uses existing standards and specifications from 3GPP, Open Mobile Alliance (OMA), and GSMA and enables interoperability of supported features across operators that support the suite. RCS supports both circuit-switched and packet-switched voice and can interoperate with LTE packet voice.

Core features include:

- ❑ A user capability exchange or service discovery with which users can know the capabilities of other users.

- Enhanced (IP-based) messaging (supporting text, IM, and multimedia) with chat and messaging history.
- Enriched calls that include multimedia content (such as photo or video sharing) during voice calls. This could become the primary way operators offer video calling.

The primary drivers for RCS adoption are the ability to deploy VoLTE in a well-defined manner and to support messaging in the IP domain. RCS addresses the market trend of users moving away from traditional text-based messaging and provides a platform for operator-based services that compete with OTT messaging applications. Figure 27 shows the evolution of RCS capability, including the addition of such features as messaging across multiple devices, video calling, video sharing, and synchronized contact information across multiple devices.

Figure 27: Evolution of RCS Capability.[64]


Industry Specifications
Messaging Evolution
SMS
MMS
Stand Alone and conversational messaging
IMS Messaging Store&Forward
One-to-one Chat and group chat
File transfer
Sharing in chat/group chat
Same messaging experience on multiple devices
Telephony Evolution
CS telephony (voice)
HD Voice
IMS Voice
Video sharing (one-way)
Video Calling
Group calls
Calling with tablets and PCs (2:ndary devices)
Contact Management Evolution
Device centric address book
Backup and restore
Capability discovery
Multi device synchronization
Social presence status
Selfie's / Pictures
Tag lines
Legacy, RCS and VoLTE features (IR.92/94)

WebRTC

WebRTC is an open project supported by Google, Mozilla, and Opera within the Internet Engineering Taskforce (IETF) that enables real-time communications in Web browsers via JavaScript APIs. 3GPP Release 12 specifications define how WebRTC clients can access IMS services, including packet voice and video communication. WebRTC operating over IMS gains the additional benefit of seamless transition across transport networks, for example, LTE to Wi-Fi.

Operators can integrate WebRTC with RTC, facilitating development of vertical applications such as telemedicine and customer service. WebRTC and RCS are more complementary than competitive. Both, through application interfaces, can provide access to underlying network functions.

---

[64] 4G Americas, *VoLTE and RCS Technology - Evolution and Ecosystem*, Nov. 2014.

Wi-Fi Calling

Another advantage of the VoLTE/IMS/RCS architecture is that it is agnostic to the user connection, meaning voice and video service can extend to Wi-Fi connections as easily as LTE connections. Wi-Fi calling can be advantageous in coverage areas were the Wi-Fi signal has better quality than an LTE signal. For video calling, use of Wi-Fi will also reduce data consumption over the cellular connection. By implementing a standards-based approach, as opposed to OTT-voice approaches, called parties see the same phone number regardless of network and can reach the subscriber using that phone number.

Previous technical approaches, such as Generic Access Network (GAN, initially called Unlicensed Mobile Access [UMA]), did not include as robust a handover mechanism as is provided by VoLTE/IMS.

For the best-quality voice in a Wi-Fi network, the device and Wi-Fi network should implement Wi-Fi Multimedia (WMM), which gives voice packets higher priority than other data traffic. WMM is especially necessary in congested networks. In addition, the Access Network Discovery and Selection Function (ANDSF) and cellular-WLAN enhancement features in 3GPP Release 12 have policies for enabling voice handover between LTE and Wi-Fi.

Roaming with Wi-Fi calling will need to address whether the visited network's IMS infrastructure handles the Wi-Fi call or whether the home network's IMS does.

Public Safety

An important LTE application is for public safety, initially as a broadband data service and eventually for mission-critical voice service. Current public safety networks use technologies, such as Terrestrial Trunked Radio (TETRA) in Europe and Project 25 (P25) in the United States, that provide mission-critical voice but only narrowband data.

In the United States, the government has made 20 MHz of spectrum available at 700 MHz in Band 14 and created the First Responder Network Authority (FirstNet), an independent authority within the National Telecommunications and Information Administration (NTIA) to provide a nationwide public-safety broadband network. AT&T will build and deploy the network.[65]

Another country driving the use of LTE for public safety is the United Kingdom, where the UK Home Office has a program for the Emergency Service Network.

Using LTE for public safety is a complex undertaking because public-safety needs differ from those of consumers. Addressing these needs requires both different features, which 3GPP is incorporating in multiple releases of LTE specifications, and different network deployment approaches. Public safety also has different device-level needs than consumers.

LTE Features for Public Safety

Some broadband applications for public safety can use standard LTE capability. For example, sending email, accessing a database, or streaming a video may not require any special features. Other applications, however, require new capabilities from 3GPP standards, including:

Group Communication

Available in Release 12, the Group Communication Service (GCS) application server, using one-to-one (unicast) and one-to-many communications (broadcast), will be able to send voice, video, or data traffic to multiple public-safety devices. The broadcast mode will employ eMBMS to use radio resources efficiently, but if coverage is weak, a unicast approach may deliver data more reliably. The system will be able to dynamically switch between broadcast and unicast modes. Release 14 adds single-cell point-to-multipoint transmission.

Proximity-Based Services (Device-to-Device)

With proximity-based services, defined in Release 12, user devices can communicate directly, a capability that benefits both consumers and public safety. This type of communication is called sidelink communication. Consumer devices can find other devices only with assistance from the network, but for public safety, devices will be able to communicate directly with other devices independently of the network.

With Release 13, devices will be able to act as relays for out-of-coverage devices, such as inside a building.

---

[65] For details, see “FirstNet AT&T,” https://www.corp.att.com/public-safety/att-firstnet/. See also RCR Wireless, *Editorial Report: Public Safety LTE*, March 2017. Available at http://content.rcrwireless.com/20170322_Public_Safety_Report.

The appendix section “Proximity Services (Device-to-Device)” discusses this feature in greater detail.

Mission-Critical Push-to-Talk

MCPTT, being defined in Release 13, provides one-to-one and one-to-many push-to-talk communications services. With this feature, available in the 2018 timeframe, public-safety organizations will be able to consider retiring legacy voice-based systems.

Mission-Critical Video over LTE and Mission-Critical Data over LTE

Release 14 adds Mission-Critical Video over LTE and Mission-Critical Data over LTE, designed to work with Mission-Critical Push-to-Talk, giving first responders more communications options.

Prioritization

To prevent interference with public-safety operations in emergency situations experiencing high load, the network can prioritize at multiple levels. First, the network can bar consumer devices from attempting to access the network, thus reducing signaling load. Second, the network can prioritize radio resources, giving public-safety users higher priority. Third, using a new capability called “Multimedia Priority Service” (MPS), the network can prioritize a connection between an emergency worker and a regular subscriber. Finally, the network can assign specific quality-of-service (QoS) parameters to specific traffic flows, including guaranteed bit rate. 3GPP has defined specific QoS quality-class identifiers for public safety.

High Power

Release 11 defines higher power devices for the public safety band that can operate at 1.25 Watts, improving coverage and reducing network deployment costs.

Isolated operation

With Release 13, a base station can continue offering service even with the loss of backhaul, a capability that will benefit public-safety personnel in disaster situations.

Relays

Figure 28 summarizes the more than eighteen features in 3GPP relays that apply to public safety.

Figure 28: Summary of 3GPP LTE Features to Support Public Safety[66]



3GPP Rel-8
- Mobile data connections
- Basic support for Voice over LTE (telephony)
- Support for LTE Band 14
- a rich set of QoS priority and pre-emption features
- Highly secure authentication and ciphering

3GPP Rel-9
- Location services and positioning support for LTE
- Multimedia Broadcast / Multicast Service
- E911 or emergency calling support
- Enhanced Home LTE base station: “Cell On Wheels”
- Self-Organizing Networks (SONs)

3GPP Rel-10
- Physical layer enhancements to increase data throughput (including LTE-Advanced features)
- Relays for LTE, e.g. to allow a base station mounted on a fire vehicle to relay communications from firefighters in a basement back to the network.

3GPP Rel-11
- High power devices for Band 14 - 1.25 Watts for public safety devices significantly improving the coverage of an LTE network, benefiting public safety users and reducing network deployment costs.

3GPP Rel-12
- Group Communication System Enablers for LTE
- Proximity-based Services

3GPP work ongoing - completion expected 1Q2015

3GPP Rel-13
- Mission Critical Push-to-Talk
- Enhancements to Proximity-based Services
- Isolated E-UTRAN Operation for Public Safety
- MBMS Enhancements

3GPP work started - completion expected 2016

Deployment Approaches

Because huge infrastructure investments would be required for a network dedicated solely to public safety, industry and government are evaluating approaches in which public-safety uses can leverage existing commercial network deployments. One caveat is that public-safety networks have more stringent resilience and security requirements than commercial networks.

Shared Network

As depicted in Figure 29, multiple sharing approaches are possible:

1. In this scenario, a public-safety entity owns and operates the entire network, an approach that gives public-safety organizations the greatest control over the network but at the highest cost.
2. A commercial operator shares its radio-access network, including cell sites and backhaul, but the public-safety entity manages core network functions including gateways, the Mobile Management Entity, the Home Subscriber Server (HSS), and public-safety application servers. Because the radio-access network is the costliest part of the network, this approach significantly reduces the amount public safety must invest in the network. Even though the RAN is shared, public safety still can use its dedicated spectrum.
3. In an MVNO approach, the operator shares its cell sites and backhaul as well as some core network functions, such as the MME and Serving Gateway. Public safety manages a small number of network functions, such as the Packet Gateway, HSS, and its application servers.

---

[66] Nokia, *LTE networks for public safety services*, 2014. Available at http://networks.nokia.com/sites/default/files/document/nokia_lte_for_public_safety_white_paper.pdf.

4. A final approach, not shown in the figure, is one in which the mobile operator hosts all of the elements shown in the figure and public safety manages only its application servers.

Figure 29: Sharing Approaches for Public-Safety Networks


1. Private LTE Network for Public Safety—Public Safety Owns Entire Network
2. RAN Sharing for Public Safety—Operator Shares RAN
3. MVNO Model for Public Safety—Operator Shares Some Core Network
Public Safety Application Servers
Packet Gateway
Serving Gateway
Home Subscriber Server
Mobile Management Entity
Backhaul Network
Rysavy Research

Resilience

Public safety may need greater resilience than found in commercial networks, including hardware redundancy, geographic redundancy, load balancing, fast re-routing in IP networks, interface protection, outage detection, self-healing, and automatic reconfiguration.

Security

Public-safety networks may have higher security requirements than commercial networks, including physical security of data centers, core sites, and cell sites. Whereas LTE networks do not have to encrypt traffic in backhaul and core networks, public-safety applications may choose to encrypt all IP traffic using virtual private networking approaches.

Coverage

A number of approaches can ensure the broadest possible coverage for public-safety networks. First, public-safety frequencies at 700 MHz already propagate and penetrate well. Next, public-safety devices will be able to transmit at higher power. In addition, base stations can employ four-way receiver diversity and higher-order sectorization. For disaster situations, public safety can also use rapidly deployable small cells, such as on trailers. Finally, proximity-based services operating in a relay mode, as discussed above, can extend coverage.

Device Considerations for Public Safety

Public-safety devices will have unique requirements, including guaranteed network access under all conditions and guidelines for how devices are shared among users.

Access to Commercial Networks

Public-safety devices could be designed to also communicate on commercial LTE networks, providing an alternative communications avenue when the device cannot connect to a public-safety network. Subscriptions to all major commercial networks would make this approach the most effective. Wi-Fi capability further extends this concept.

Device Sharing

Because public-safety devices may be shared among personnel, user profiles cannot be stored on USIM cards stored in the devices. Bluetooth-based remote SIMs are one approach to address this problem.

Expanding Capacity

Wireless technology is playing a profound role in networking and communications, even though wireline technologies such as fiber have inherent capacity advantages.

Over time, wireless networks will gain substantial additional capacity through the methods discussed in the next section. While they will compete with copper twisted pair and coax, they will never catch up to fiber. The infrared frequencies used in fiber-optic communications have far greater bandwidth than radio. As a result, one fiber-optic strand has greater bandwidth than the entire usable radio spectrum to 100 GHz, as illustrated in Figure 30.[67]

Figure 30: RF Capacity vs. Fiber-Optic Cable Capacity


Achievable Fiber-Optic Cable Capacity Per Cable (Area Denotes Capacity)
Additional Fiber Strands Readily Available
Additional Fiber Strands Readily Available
Achievable Capacity Across Entire RF Spectrum to 100 GHz
Rysavy Research

A dilemma of 4G mobile broadband is that it *can* provide a broadband experience similar to wireline, but it *cannot* do so for all subscribers in a coverage area at the same time. Hence, operators must carefully manage capacity, demand, policies, pricing plans, and user expectations. Similarly, application developers must become more conscious of the inherent constraints of wireless networks. 5G, with its far greater capacity, at least in small deployments, will increase the percentage of users that use wireless connections as their only broadband.

Three factors determine wireless network capacity, as shown in Figure 31: the amount of spectrum, the spectral efficiency of the technology, and the size of the cell. Because smaller cells serve fewer people in each cell and because there are more of them, small cells are a major contributor to increased capacity.

---

[67] One fiber-optic cable can transmit over 10,000 Gbps compared with all wireless spectrum to 100 GHz, which, even at an extremely high spectral efficiency 10 bps/Hz, would have only 1,000 Gbps of capacity.

Figure 31: Dimensions of Capacity


Spectral Efficiency of Technology
Amount of Spectrum
Smallness of Cell (Amount of Frequency Reuse)
Rysavy Research

Given the relentless growth in usage, mobile operators are combining multiple approaches to increase capacity and managing congestion:

- **More spectrum.** Spectrum correlates almost directly to capacity, and more spectrum is becoming available globally for mobile broadband. In the U.S. market, the 2010 FCC National Broadband Plan is in the process of adding an additional 500 MHz of spectrum by 2020. mmWave band spectrum for 5G will provide far more spectrum, but propagation characteristics will restrict its use to small cells. Multiple papers by Rysavy Research and others[68] argue the critical need for additional spectrum.
- **Unpaired spectrum.** LTE TDD operates in unpaired spectrum. In addition, technologies such as HSPA+ and LTE permit the use of different amounts of spectrum between downlink and uplink. Additional unpaired downlink spectrum can be combined with paired spectrum to increase capacity and user throughputs.
- **Supplemental downlink.** With downlink traffic five to ten times greater than uplink traffic, operators often need to expand downlink capacity rather than uplink capacity. Using carrier aggregation, operators can augment downlink capacity by combining separate radio channels.
- **Spectrum sharing.** Policy makers are evaluating how spectrum might be shared between government and commercial entities. Although a potentially promising approach for the long term, sharing raises complex issues, as discussed further in the section "Spectrum Developments."
- **Increased spectral efficiency.** Newer technologies are spectrally more efficient, meaning greater aggregate throughput using the same amount of spectrum. Wireless technologies such as LTE, however, are reaching the theoretical limits of spectral

---

[68] See multiple papers on spectrum and capacity at http://www.rysavy.com/writing.

efficiency, and future gains will be quite modest, allowing for a possible doubling of LTE efficiency over currently deployed versions. See the section "Spectral Efficiency" for a further discussion.

- **Smart antennas.** Through higher-order MIMO and beamforming, smart antennas gain added sophistication in each 3GPP release and are the primary contributor to increased spectral efficiency (bps/Hz). Massive MIMO, beginning in Release 13, will support 16-antenna-element systems and in 5G, will expand to potentially hundreds of antenna elements.
- **Uplink gains combined with downlink carrier aggregation.** Operators can increase network capacity by applying new receive technologies at the base station (for example, large-scale antenna systems such as massive MIMO) that do not necessarily require standards support. Combined with carrier aggregation on the downlink, these receive technologies produce a high-capacity balanced network, suggesting that regulators should in some cases consider licensing just downlink spectrum.
- **Small cells and heterogeneous networks.** Selective addition of picocells to macrocells to address localized demand can significantly boost overall capacity, with a linear increase in capacity relative to the number of small cells. HetNets, which also can include femtocells, hold the promise of increasing capacity gains by a factor of four and even higher with the introduction of interference cancellation in devices. Distributed antenna systems (DAS), used principally for improved indoor coverage, can also function like small cells and increase capacity. Actual gain will depend on a number of factors, including number and placement of small cells,[69] user distribution, and any small-cell selection bias that might be applied.
- **Offload to unlicensed spectrum.** Using unlicensed spectrum with Wi-Fi or LTE operation in unlicensed spectrum offers another means of offloading heavy traffic. Unlicensed spectrum favors smaller coverage areas because interference can be better managed, so spectral re-use is high, resulting in significant capacity gains.
- **Higher level sectorization.** For some base stations, despite the more complex configuration involved, six sectors can prove advantageous versus the more traditional three sectors, deployed either in a 6X1 horizontal plane or 3X2 vertical plane.[70]

Strategies to manage demand include:

- **Quality of service (QoS) management.** Through prioritization, certain traffic, such as non-time-critical downloads, could occur with lower priority, thus not affecting other active users. Current network neutrality rules, however, may constrain use of traffic prioritization.[71]
- **Off-peak hours.** Operators could offer user incentives or perhaps fewer restrictions on large data transfers during off-peak hours.

---

[69] With small-cell range expansion using a large selection bias, small cells can be distributed uniformly.

[70] An example of vertical layering would be a 3X1 layer at ground level and a separate 3X1 layer for higher levels of surrounding buildings.

[71] For a discussion of this issue, see Rysavy Research, *LTE Congestion Management – Enabling Innovation and Improving the Consumer Experience*, January 2015. Available at http://www.rysavy.com/Articles/2015-01-Rysavy-LTE-Congestion-Management.pdf.

Given a goal of increasing capacity by a factor of 1,000, 50X could roughly be achieved through network densification; 10X through more spectrum, including higher frequencies such as mmWave; and 2X by increases in spectral efficiency.

Based on historical increases in the availability of new spectrum, technologies delivering better spectral efficiency, and increases in the number of cell sites, Rysavy Research has calculated that, over the last thirty-year period, aggregate network capacity has doubled every three years. Rysavy Research expects this trend to continue into the future.

Rysavy Research Analysis:

Aggregate Wireless Network Capacity
Doubles Every Three Years.

Spectrum Developments

Licensed spectrum scarcity continues to challenge the industry. Tactics to make the best use of this limited resource include deploying technologies that have higher spectral efficiency; adapting specifications to enable operation of UMTS-HSPA and LTE in all available bands; designing both FDD and TDD versions of technology to take advantage of both paired and unpaired bands; designing carrier aggregation techniques in HSPA+ and LTE-Advanced Pro; and deploying as many new cells, large and small, as is economically and technically feasible. Although all of these industry initiatives greatly expand capacity, they do not obviate the need for additional spectrum. 5G technology will be able to employ frequencies not previously used in cellular systems, spanning 6 GHz to 100 GHz.

An important aspect of UMTS-HSPA and LTE deployment is for infrastructure and mobile devices to accommodate the expanding number of available radio bands. The fundamental system design and networking protocols remain the same for each band; only the frequency-dependent portions of the radios must change. As other frequency bands become available for deployment, standards bodies adapt UMTS-HSPA and LTE for these bands as well.

3GPP has specified LTE for operation in many different bands, and initial use will be more fragmented than the four bands (850 MHz, 900 MHz, 1.8 GHz, 1.9 GHz) that enable global roaming on 2G and the additional two bands (1.7 GHz and 2.1 GHz) that enable 3G roaming. In the Americas, LTE roaming may occur in the 1.7/2.1 GHz (AWS) bands, and globally, LTE roaming may occur in the 1.8 and 2.6 GHz bands. Longer term, operators will re-farm spectrum used for 2G and 3G and apply it to LTE. Unfortunately, the process of identifying new spectrum and making it available for the industry is a lengthy one, as shown in Figure 32.

Figure 32: Spectrum Acquisition Time[72]



New short-term spectrum opportunities in the United States include the "small-cell" band from 3550 to 3700 MHz and 5G spectrum.

---

[72] Source for historical data, FCC, *National Broadband Plan*, Chapter 5. Available at http://www.broadband.gov/plan/5-spectrum/, accessed May 18, 2017. Future based on Rysavy Research analysis.

Table 11 summarizes current and future spectrum allocations in the United States.[73]

Table 11: United States Current and Future Licensed Spectrum Allocations

Frequency Band	Amount of Spectrum	Comments
600 MHz	70 MHz	Ultra-High-Frequency (UHF).
700 MHz	70 MHz	Ultra-High Frequency (UHF).
850 MHz	64 MHz	Cellular and Specialized Mobile Radio.
1.7/2.1 GHz	90 MHz	Advanced Wireless Services (AWS)-1.
1695-1710 MHz, 1755 to 1780 MHz, 2155 to 2180 MHz	65 MHz	AWS-3. Uses spectrum sharing.
1.9 GHz	140 MHz	Personal Communications Service (PCS).
2000 to 2020, 2180 to 2200 MHz	40 MHz	AWS-4 (Previously Mobile Satellite Service).[74]
2.3 GHz	20 MHz	Wireless Communications Service (WCS).
2.5 GHz	194 MHz	Broadband Radio Service. Closer to 160 MHz deployable.
	FUTURE	
3.55 to 3.70 GHz	150 MHz	Small-cell band with spectrum sharing and unlicensed use.
Above 6 GHz	Multi GHz	Anticipated for 5G systems beginning in 2017. Based on wavelengths, 3 GHz to 30 GHz is referred to as the cmWave band and 30 GHz to 300 GHz is referred to as the mmWave band.

Today's licensed spectrum networks operate most efficiently and are deployed most cost-effectively using a combination of low-band spectrum, below 1 GHz, for coverage and 1 GHz to 3 GHz for capacity. As technology improves, bands in 3 GHz to 100 GHz, and eventually higher, will supplement capacity.

---

[73] For international allocations, refer to Wik-Consult, Study for the European Commission, *Inventory and review of spectrum use: Assessment of the EU potential for improving spectrum efficiency*, September 2012. Available at http://ec.europa.eu/digital-agenda/sites/digital-agenda/files/cion_spectrum_inventory_executive_summary_en.pdf.

[74] Supported in 3GPP Band 70, which adds 1995-2000 MHz, pairing it with 1695-1710 MHz in AWS-3 band.

The subsections below provide additional information about the recently completed AWS-3 auction, incentive auctions, the 3.5 GHz, 5G, spectrum harmonization, unlicensed spectrum, and spectrum sharing.

AWS-3

In early 2015, the FCC received close to $45 billion for the U.S. Treasury in the AWS-3 auction, more than twice the amount of any previous auction, demonstrating the value of mid-band spectrum.[75] The auction adds 65 MHz of desirable spectrum to the mobile-broadband industry. The plan is to employ spectrum sharing among commercial networks and select government systems. Eventually, most of these government systems will migrate to another spectrum. 3GPP has specified use of both AWS-3 and AWS-4 spectrum in what it refers to as "Band 66."

This band is asymmetrical, with a downlink of 90 MHz and an uplink of 70 MHz. An operator can use the upper-most 20 MHz of the downlink only with carrier aggregation.

Broadcast Incentive Auction (600 MHz)

The broadcast incentive auction completed in 2017 will reallocate 84 MHz of UHF channels in the 600 MHz band that are currently used by TV broadcasters, with 70 MHz of licensed spectrum and 14 MHz of unlicensed spectrum. The auction was more complicated than past spectrum auctions, when the FCC simply reassigned or designated spectrum for commercial mobile use and then conducted an auction.

In the first stage, the FCC conducted a reverse auction to determine how much spectrum broadcasters might wish to relinquish in exchange for how much compensation. In the second stage, mobile operators bid for spectrum in a forward auction, similar to past spectrum auctions.

Figure 33 shows the final band plan.

Figure 33: 600 MHz Band Plan[76]



Part of the auction process reorganizes and repacks relinquished channels, as well as channels needed for broadcasters that want to keep broadcasting, to make useful blocks of spectrum for mobile broadband. The FCC's goal is to design an auction that will result in a uniform nationwide band plan, but in some markets, there may be deviations from that plan.

---

[75] For further details, see Rysavy Research, "Latest FCC auction shatters spectrum myths," January 2015. Available at https://gigaom.com/2015/01/17/latest-fcc-auction-shatters-spectrum-myths/.

[76] 5G Americas member contribution.

With a 39-month schedule for winning bidders to move into their new spectrum, the 600 MHz band will be fully available by 2020. However, some operators, will begin using this spectrum in advance of this date, possibly as soon as the second half of 2017, as the spectrum becomes available for use.[77] Operators will use the band for LTE and 5G.

3550 to 3700 MHz "Small-Cell" Band

In the United States, the FCC is in the process of opening the 3550 to 3700 MHz CBRS band. The best use of this band will be small cells and backhaul. The FCC is implementing a three-tier model with incumbent access, priority access with priority access licenses (PALs), and General Authorized Access (GAA) for unlicensed users.[78] Incumbent access will include government radar systems.

Two industry organizations, the Wireless Innovation Forum[79] and the CBRS Alliance,[80] are working for the realization of 3.5 GHz systems.

The mobile broadband industry will mostly use LTE TDD in small-cell configurations, in either a licensed mode or an unlicensed mode using LAA or MulteFire.

Although this band represents a significant amount of new spectrum, potential adopters of the band have expressed concern about proposed rules for use of the band. For example:

- ❑ IEEE has stated it will not pursue a version of 802.11 for this band because exclusion zones are so large that the percentage of the U.S. population that could be served is below what is required for a successful market.[81]
- ❑ Licensed users will only be able to obtain three-year licenses with no automatic renewal.[82]

Assuming LAA auctions in early 2018, initial 3.5 GHz deployments could occur in 2018. Because an Environmental Sensing Capability (ESC) has not yet been developed and approved, these initial deployments may not come to fruition in coastal areas where the ESC is needed for co-existence with military systems using those frequencies.

---

[77] For example, see FierceWireless, "T-Mobile confirms speedy 600 MHz rollout for 2017, covering 1 million+ square miles," August 8, 2017, available at http://www.fiercewireless.com/node/334911.

[78] For further details, see Official FCC Blog, "Innovation in the 3.5 GHz Band: Creating a New Citizens Broadband Radio Service," March 2015, available at http://www.fcc.gov/blog/innovation-35-ghz-band-creating-new-citizens-broadband-radio-service. See also FCC, *Further Notice of Proposed Rulemaking--Amendment of the Commission's Rules with Regard to Commercial Operations in the 3550- 3650 MHz Band*, April 23, 2014.

[79] See http://www.wirelessinnovation.org/.

[80] See https://www.cbrsalliance.org/.

[81] IEEE 802.11, *Comments of IEEE 802.11, In the Matter of Amendment of the Commission's Rules with Regard to Commercial Operations in the 3550-3650 MHz Band,"* Jul, 2015. Available at http://apps.fcc.gov/ecfs/document/view?id=60001115064.

[82] See Rysavy article about this band, "Scary Experimentation at 3.5 GHz," Jun. 2016, available at http://www.rysavy.com/Articles/2016-06-Scary-Experimentation-3-5-GHz.pdf. See also AT&T ex-parte FCC communication, http://apps.fcc.gov/ecfs/document/view?id=60001569272.

See the section "Spectrum Sharing" for further details of this band.

2.5 GHz Band

In the United States, the primary operator at 2.5 GHz is Sprint. In 2017, Sprint announced that they will deploy 5G in its 2.5 GHz spectrum as soon as the second half of 2019.[83] Having an average of 160 MHz of spectrum at 2.5 GHz in its top 100 markets, Sprint is in the process of deploying LTE-Advanced. In addition, Sprint is in an LTE deployment mode that includes the following features:

- ☐ Carrier aggregation capability between 2.5 GHz and lower bands (800MHz and 1900 MHz) and aggregating three carriers in a single band.
- ☐ TDD operation at 2.5 GHz and FDD operation in lower bands.
- ☐ 8 transmit and 8 receive radios at the base station that enables 4X2 MIMO in combination with beamforming.[84]

5G Bands

As radio technology progresses, it can handle higher frequencies, and it occupies greater bandwidth. 1G systems used 30 kHz radio carriers, 2G in GSM uses 200 kHz carriers, 3G in UMTS uses 5 MHz carriers, and 4G in LTE uses carriers of up to 640 MHz through carrier aggregation.

3GPP is specifying 5G NR to be band agnostic. 5G will use low-band, mid-band, and high-band spectrum, and 3GPP is in the process of identifying candidate bands for 5G across all frequency ranges. 3GPP Technical Services Group - Radio Access Networks (TSG-RAN) agreed to a process of efficiently adding LTE/NR band combinations and carrier-aggregated NR/NR band combinations. Initial bands being considered by the 3GPP specification process include low band bands 5, 20, 28 and 71, mid-band bands 1, 3, 7, 66 and 41, and key mmWave bands. Just as it has done with LTE, over time, 3GPP will specify additional 5G bands spanning multiple frequencies.

Although 5G research and development is in its infancy, to achieve the 20 Gbps or higher throughput rates envisioned for 5G will require radio carriers such as 200 MHz or 400 MHz, bandwidths available only at frequencies above 5 GHz. Researchers globally are studying high-frequency spectrum options including both cmWave frequencies (3 GHz to 30 GHz) and mmWave (30 GHz to 300 GHz). Ten times as much spectrum, or more, could be available in these higher frequencies than in all current cellular spectrum.

---

[83] For more details, see Sprint press release, "Qualcomm, SoftBank and Sprint Announce Collaboration on 2.5 GHz 5G," May 10, 2017, available at http://newsroom.sprint.com/qualcomm-softbank-and-sprint-announce-collaboration-on-25-ghz-5g.htm.

[84] For more details, see Sprint article at: http://newsroom.sprint.com/blogs/sprint-perspectives/introducing-the-sprint-lte-plus-network--faster-stronger-more-reliable-than-ever-before.htm

5G NR is being designed to operate in any frequency band. These bands encompass 600 MHz, current cellular bands, 3.5 GHz, and higher bands such as mmWave. Because 5G will be the first cellular technology to be able to operate in mmWave bands, industry and government are working to make such bands available for 5G.

During the World Radiocommunication Conference (WRC) 15, the ITU proposed a set of global frequencies for 5G[85], which it intends to finalize at the next conference in 2019 (WRC 19):

- 24.25–27.5GHz
- 31.8–33.4GHz
- 37–40.5GHz
- 40.5–42.5GHz
- 45.5–50.2GHz
- 50.4–52.6GHz
- 66–76GHz
- 81–86GHz
- In 2014, the FCC published a Notice of Inquiry into use of spectrum bands above 24 GHz for Mobile Radio Services,[86] followed by a Notice of Proposed Rulemaking in October 2015. [87]

The FCC issued adopted rules to identify and open up 5G mmWave spectrum allocation in July 2016 that identify 3.85 GHz of licensed spectrum and 7 GHz of unlicensed spectrum: licensed use in 28 GHz, 37 GHz, and 39 GHz bands; unlicensed use in 64-71 GHz; and shared access in the 37-37.6 GHz band.

On July 24, 2016, the FCC adopted a report and order and further notice of proposed rulemaking that creates a new Part 30 for rules governing 28 GHz, 36 GHz, and 39 GHz bands, summarized in Table 12.

Table 12: United States 5G mmWave Bands[88]

Bands	Details
28 GHz Band (27.5-28.35 GHz)	Currently licensed for Local Multipoint Distribution Service (LMDS). Could be licensed using either 200 or 400 MHz wide channels.

---

[85] 5G Americas Webcast, “LTE-Steps to 5G,” Feb 12, 2016.

[86] FCC, *Notice of Inquiry, Use of Spectrum Bands above 24 GHz for Mobile Radio Services*, Oct. 17, 2014.

[87] FCC, *Notice of Proposed Rulemaking, Use of Spectrum Bands Above 24 GHz for Mobile Radio Services, GN Docket No. 14-177,* Oct 23, 2015.

[88] For more details, refer to FCC, *Report and Order and Further Notice of Proposed Rulemaking, Use of Spectrum Bands Above 24 GHz for Mobile Radio Services*, July 14, 2016. See also 5G Americas, *5G*

Bands	Details
39 GHz Band (38.6-40 GHz)	Currently licensed for fixed microwave in 50 MHz channels. Segment will be auctioned in 200 MHz blocks.
37 GHz Band (37-38.6 GHz)	Lower 37-37.6 GHz segment will be shared between federal and non-federal users. Upper 37.6-38.6 GHz segment will be auctioned in 200 MHz blocks.
64-71 GHz Band	Available for unlicensed use with same Part 15 rules as existing 57-64 GHz band.

In the 28 GHz band, satellite operations are secondary, but these operations are co-primary in the 37/39 GHz bands. Spectrum sharing may be required in some 5G bands, including 38.6 to 40 GHz, such as with fixed satellite service.

In the further notice of proposed rulemaking, the FCC is investigating additional bands, including 24 GHz, 32 GHz, 42 GHz, 47 GHz, 50 GHz, 70/80 GHz, and bands above 95 GHz.

The complex ITU harmonization process may mean that some regions, or even countries, pursue 5G bands that are not globally harmonized. For example, U.S. operators, along with operators in Korea and Japan, are planning 5G trials in the 28 GHz band, even though it is not one of the ITU bands.

Harmonization

Spectrum harmonization delivers many benefits, including higher economies of scale, better battery life, improved roaming, and reduced interference along borders.

As regulators make more spectrum available, it is important that they follow guidelines such as those espoused by 5G Americas:[89]

- Configure licenses with wider bandwidths.
- Group like services together.
- Be mindful of global technology standards.
- Pursue harmonized/contiguous spectrum allocations.
- Exhaust exclusive use options before pursuing shared use.
- Because not all spectrum is fungible, align allocation with demand.

Emerging technologies such as LTE benefit from wider radio channels. These wider channels are not only spectrally more efficient, they also offer greater capacity. Figure 34 shows increasing LTE spectral efficiency obtained with wider radio channels, with 20 MHz on the

---

Spectrum Recommendations, April 2017, available at http://www.5gamericas.org/files/9114/9324/1786/5GA_5G_Spectrum_Recommendations_2017_FINAL.pdf. This report covers global 5G spectrum developments.

[89] 4G Americas, *Sustaining the Mobile Miracle – A 4G Americas Blueprint for Securing Mobile Broadband Spectrum in this Decade*, March 2011.

downlink and 20 MHz (20+20 MHz) on the uplink comprising the most efficient configuration.

Figure 34: LTE Spectral Efficiency as Function of Radio Channel Size[90]



The organization tasked with global spectrum harmonization, the International Telecommunication Union, periodically holds World Radiocommunication Conferences.[91]

Harmonization occurs at multiple levels:

- Allocation of radio frequencies to a mobile service in the ITU frequency allocation table.
- Establishment of global or regional frequency arrangements, including channel blocks and specific duplexing modes.
- Development of detailed technical specifications and standards, including system performance, RF performance, and coexistence with other systems in neighboring bands.
- Assignment for frequency blocks with associated technical conditions and specifications to appropriate operators and service providers.[92]

---

[90] 5G Americas member company analysis.

[91] International Telecommunication Union, "World Radiocommunication Conferences (WRC)," http://www.itu.int/ITU-R/index.asp?category=conferences&rlink=wrc&lang=en, viewed May 18, 2017.

[92] International Telecommunication Union Radiocommunication Study Groups, *Technical Perspective on Benefits Of Spectrum Harmonization for Mobile Services and IMT*, Document 5D/246-E, January 2013.

Unlicensed Spectrum

Wi-Fi uses spectrum efficiently because its small coverage areas result in high-frequency reuse and high data density (bps per square meter). Less efficient are white-space unlicensed networks, sometimes called “super Wi-Fi,” that, because of large coverage areas, have much lower throughput per square meter. While white-space networks may be a practical broadband solution in rural or undeveloped areas, they face significant challenges in urban areas that already have mobile and fixed broadband available.[93] See the section on “White Space Networks” in the appendix for further details.

Advocates argue that unlicensed spectrum unleashes innovation and that government should allocate greater amounts of unlicensed spectrum. Although Wi-Fi has been successful, the core elements that make unlicensed spectrum extremely successful are also the source of inherent disadvantages: local coverage and its unlicensed status. Local coverage enables high data density and high frequency reuse but makes widespread continuous coverage almost impossible. Similarly, unlicensed operation facilitates deployment by millions of entities but results in overlapping coverage and interference.

Networks built using unlicensed spectrum cannot replace networks built using licensed spectrum, and vice versa. The two are complementary and helpful to each other, as summarized in Table 13.[94]

Table 13: Pros and Cons of Unlicensed and Licensed Spectrum

Unlicensed Spectrum		Licensed Spectrum	
Pros	**Cons**	**Pros**	**Cons**
Easy and quick to deploy	Potential of other entities using same frequencies	Huge coverage areas	Expensive infrastructure
Low-cost hardware	Difficult to impossible to provide wide-scale coverage	Able to manage quality of service	Each operator has access to only a small amount of spectrum

Some operators offer a “Wi-Fi first” capability with which devices always attempt to use a Wi-Fi connection and fall back to a cellular connection only if no Wi-Fi is available. Such cellular backup is essential because Wi-Fi, due to low-power operation in many bands, is inherently unsuited for providing continuous coverage. The sharp drop-off in signal strength due to low transmit power makes coverage gaps over large areas inevitable, especially outdoors.

---

[93] For further analysis, see Rysavy Research, “White spaces networks are not ‘super’ nor even Wi-Fi,” Gigaom, March 2013. Available at http://gigaom.com/2013/03/17/white-spaces-networks-are-not-super-nor-even-wi-fi/.

[94] For further analysis, see Rysavy Research, “It’s Time for a Rational Perspective on Wi-Fi,” Gigaom, April, 2014. Available at http://gigaom.com/2014/04/27/its-time-for-a-rational-perspective-on-wi-fi/.

Figure 35: Propagation Losses of Cellular vs. Wi-Fi[95]



Free space path loss: exponent of 2
Terrestrial path loss: exponent of 3+
Even with exponent of 2:

- **Wi-Fi. 100 meters to 200 meters: signal at 25% of strength**
- **Cellular. 1.0 km to 1.1 km: signal at 83% of strength**

Difficult to propagate short range network (Wi-Fi) signal

Spectrum Sharing

In 2012, the President's Council of Advisors on Science and Technology issued a report titled, "Realizing the Full Potential of Government-Held Spectrum to Spur Economic Growth." The report recommended spectrum sharing between government and commercial entities.

The U.S. government can designate spectrum for exclusive, shared, or unlicensed use, as shown in Figure 36. Shared use can be opportunistic, as with TV white spaces; two-tier with incumbents and licensed users; or three-tier, which adds opportunistic access. The bands initially targeted for spectrum sharing include AWS-3 (two tiers on a temporary basis) and the 3.5 GHz band (three tiers).

The three-tier plan envisioned by the U.S. government for the 3.5 GHz band gives more entities access to the spectrum but at the cost of increased complexity.

---

[95] Assumes 1.0 km radius for cellular and 100-meter radius for Wi-Fi.

Figure 36: Spectrum Use and Sharing Approaches


Exclusive Use
Shared Use
Unlicensed Use
Opportunistic (e.g., TV White Space)
Two- Tier Access:
1. Incumbents
2. Licensed
Three-Tier Access:
1. Incumbents
2. Licensed
3. Opportunistic
Rysavy Research

The European Telecommunications Standards Institute (ETSI) is the leading organization standardizing cognitive radios. The most relevant effort is called “Licensed Shared Access” (LSA), a two-tier spectrum sharing system that includes incumbents and licensed secondary users that access shared spectrum via a database, as depicted in Figure 37.

Figure 37: Licensed Shared Access (LSA)


LSA Repository
LSA Controller
Operator Network Operations
Primary Systems (Incumbents)
Shared Spectrum Coverage (Small Cells)
Licensed Spectrum Underlay
Rysavy Research

The three-tier system expected for the 3.5 GHz band in the United States will be complex, necessitating a real-time Spectrum Access System, the SAS, the design and development of which will encompass:

- Algorithms and methods;
- Methods of nesting hierarchical SAS entities (federal secure SAS versus commercial SASs);

- ☐ Coordination among multiple, competing commercial SAS managing entities;
- ☐ Interface definitions;
- ☐ Communication protocol definitions;
- ☐ Database and protocol security;
- ☐ Policy enforcement;
- ☐ Speed of channel allocation/reallocation;
- ☐ Time intervals for spectrum allocation;
- ☐ Effectively managing large numbers of Tier 3 users; and
- ☐ Data ownership, fees, rules, fairness, and conflict resolutions, all of which have policy, regulatory, and business implications.

TVWS databases available today address only a tiny subset of these requirements.[96]

Figure 38 shows the proposed architecture of the 3.5 GHz system. The system consists of incumbents (government systems), Priority Access Licenses, and General Authorized Access. Government systems include military ship-borne radar, military ground-based radar, fixed satellite service earth stations (receive only), and government broadband services (3650 to 3700 MHz). PAL licenses will be used by entities such as cellular operators and will be available for three-year periods. GAA users are licensed by rule and must protect both incumbents and PALs. Incumbents are protected by an Environmental Sensing Capability that detects incumbents and informs the SAS. Some examples of GAA use cases are small-business hotspots, campus hotspots, and backhaul.

Citizens Broadband Radio Service Devices (CBSDs) are the base stations operating under this service; they can operate only under the authority and management of the SAS, either by direct communications or a proxy node.

---

[96] For further analysis, see Rysavy Research and Mobile Future, *Complexities of Spectrum Sharing: How to Move Forward*, April 2014. Available at http://www.rysavy.com/Articles/2014-04-Spectrum-Sharing-Complexities.pdf.

Figure 38: United States 3.5 GHz System Currently Being Developed


FCC Databases
Spectrum Access System 2
SAS-SAS Interface
Informing Incumbent
Spectrum Access System 1
Incumbent Detection
SAS-User Interface
Domain Proxy (Such as Cellular Operator)
Element Management System (Optional)
CBSD
CBSD
CBSD
CBSD
Citizens Broadband Radio Service Device (CBSD) - Base Station
Rysavy Research

Conclusion

Mobile broadband remains at the forefront of innovation and development in computing, networking, and application development. As users, and now machines, consume ever more wireless data, the industry is responding with more efficient, faster, and higher capacity networks. Even as excitement builds about 5G, LTE, through ongoing advances, has become the global standard.

LTE-Advanced and LTE-Advanced Pro innovations include VoLTE, 1 Gbps peak rate capability, higher-order MIMO, carrier aggregation, LAA/LWA/LWIP, IoT capabilities in Narrowband-IoT and Category M-1, V2X communications, small-cell support, URLLC, SON, dual connectivity, and CoMP—all capabilities that will improve performance, efficiency, and capacity and enable support for new vertical segments. Carriers are implementing NFV and SDN to reduce network costs, improve service velocity, and simplify deployment of new services. Such improvements also facilitate cloud RANs that promise further efficiency gains.

5G research and development efforts have accelerated; standards-based deployment will begin in 2019 and continue through 2030. Operators have announced pre-standard fixed-wireless deployments for 2017. 3GPP has implemented a 5G standardization process that began in Release 14 with a study of the new 5G radio, continues now with a first phase of specifications in Release 15 that provides both non-standalone and standalone options, then moves ahead with a second phase of complete specifications in Release 16.

By harnessing new spectrum, such as mmWave bands above 24 GHz, 5G will eventually be able to access ten times as much spectrum as is currently available for cellular operation. Using radio bands 200 MHz or wider will result in multi-Gbps throughput capabilities. 5G will be designed to integrate with LTE networks, and many 5G features may be implemented as LTE-Advanced Pro extensions prior to full 5G availability.

Small cells will play an ever-more-important role in boosting capacity, benefiting from a number of technologies and developments, including SON, eICIC, Dual Connectivity, LWA/LWIP, LTE-U, LTE-LAA, MulteFire, improved backhaul options, and spectrum ideal for small cells, such as the 3.5 GHz and mmWave bands.

Obtaining more spectrum remains a priority globally. In U.S. markets, the recently completed television incentive auctions for 600 MHz spectrum supplied 70 MHz of new licensed spectrum; the 3.5 GHz small-cell band will provide 150 MHz; and the 5G spectrum bands, with both licensed and unlicensed bands, will add about 10 GHz of new spectrum.

The future of mobile broadband, including both LTE-Advanced and 5G, is bright, with no end in sight for continued growth in capability, nor for the limitless application innovation that mobile broadband enables.

Appendix: Technology Details

The 3GPP family of data technologies provides ever increasing capabilities that support ever more demanding applications. Services obviously need to provide broad coverage and high data throughput. Less obvious for users, but as critical for effective application performance, are the need for low latency, QoS control, and spectral efficiency. Higher spectral efficiency translates to higher average throughputs (and thus more responsive applications) for more active users in a coverage area. The discussion below details the progression of capability for each technology, including throughput, security, latency, QoS, and spectral efficiency.

This appendix provides details on 5G, UMTS/HSPA, and EDGE.

3GPP Releases

- ☐ **Release 99**: Completed. First deployable version of UMTS. Enhancements to GSM data (EDGE). Provides support for GSM/EDGE/GPRS/WCDMA radio-access networks.
- ☐ **Release 4**: Completed. Multimedia messaging support. First steps toward using IP transport in the core network.
- ☐ **Release 5**: Completed. HSDPA. First phase of Internet Protocol Multimedia Subsystem (IMS). Full ability to use IP-based transport instead of just Asynchronous Transfer Mode (ATM) in the core network.
- ☐ **Release 6**: Completed. HSUPA. Enhanced multimedia support through Multimedia Broadcast/Multicast Services (MBMS). Performance specifications for advanced receivers. Wireless Local Area Network (WLAN) integration option. IMS enhancements. Initial VoIP capability.
- ☐ **Release 7**: Completed. Provides enhanced GSM data functionality with Evolved EDGE. Specifies HSPA+, which includes higher-order modulation and MIMO. Performance enhancements, improved spectral efficiency, increased capacity, and better resistance to interference. Continuous Packet Connectivity (CPC) enables efficient “always-on” service and enhanced uplink UL VoIP capacity, as well as reductions in call set-up delay for Push-to-Talk Over Cellular (PoC). Radio enhancements to HSPA include 64 Quadrature Amplitude Modulation (QAM) in the downlink and 16 QAM in the uplink. Also includes optimization of MBMS capabilities through the multicast/broadcast, single frequency network (MBSFN) function.
- ☐ **Release 8**: Completed. Comprises further HSPA Evolution features such as simultaneous use of MIMO and 64 QAM. Includes dual-carrier HSDPA (DC-HSDPA) wherein two downlink carriers can be combined for a doubling of throughput performance. Specifies OFDMA-based 3GPP LTE. Defines EPC and EPS.
- ☐ **Release 9**: Completed. HSPA and LTE enhancements including HSPA dual-carrier downlink operation in combination with MIMO, Multimedia Broadcast Multicast Services (MBMS), HSDPA dual-band operation, HSPA dual-carrier uplink operation, EPC enhancements, femtocell support, support for regulatory features such as emergency user equipment positioning and Commercial Mobile Alert System (CMAS), and evolution of IMS architecture.
- ☐ **Release 10**: Completed. Specifies LTE-Advanced that meets the requirements set by ITU’s IMT-Advanced project. Key features include carrier aggregation, multi-antenna enhancements such as enhanced downlink eight-branch MIMO and uplink MIMO, relays,

enhanced LTE Self-Organizing Network capability, Evolved Multimedia Broadcast Multicast Services (eMBMS), HetNet enhancements that include eICIC, Local IP Packet Access, and new frequency bands. For HSPA, includes quad-carrier operation and additional MIMO options. Also includes femtocell enhancements, optimizations for M2M communications, and local IP traffic offload.

- **Release 11**: Completed. For LTE, emphasizes Coordinated Multi Point (CoMP), carrier-aggregation enhancements, devices with interference cancellation, development of the Enhanced Physical Downlink Control Channel (EPDCCH), and further enhanced eICIC including devices with CRS (Cell-specific Reference Signal) interference cancellation. The release includes further DL and UL MIMO enhancements for LTE. For HSPA, provides eight-carrier on the downlink, uplink enhancements to improve latency, dual-antenna beamforming and MIMO, CELL Forward Access Channel (FACH) state enhancement for smartphone-type traffic, four-branch MIMO enhancements and transmissions for HSDPA, 64 QAM in the uplink, downlink multipoint transmission, and noncontiguous HSDPA carrier aggregation. Wi-Fi integration is promoted through S2a Mobility over GPRS Tunneling Protocol (SaMOG). An additional architectural element called "Machine-Type Communications Interworking Function" (MTC-IWF) will more flexibly support machine-to-machine communications.

- **Release 12**: Completed. Enhancements include improved small cells/HetNets for LTE, LTE multi-antenna/site technologies (including Active Antenna Systems), Dual Connectivity, 256 QAM modulation option, further CoMP/MIMO enhancements, enhancements for interworking with Wi-Fi, enhancements for MTC, SON, support for emergency and public safety, Minimization of Drive Tests (MDT), advanced receivers, device-to-device communication (also referred to as Proximity Services), group communication enablers in LTE, addition of Web Real Time Communication (WebRTC) to IMS, energy efficiency, more flexible carrier aggregation, dynamic adaptation of uplink-downlink ratios in TDD mode, further enhancements for HSPA+, small cells/HetNets, Scalable-UMTS, and FDD-TDD carrier aggregation.

- **Release 13**: Completed. LTE features include Active Antenna Systems (AAS) with support for as many as 16 antenna elements (full-dimension MIMO) and beamforming, Network-Assisted Interference Cancellation and Suppression (NAICS), radio-access network sharing, carrier aggregation supporting 32 component carriers,[97] carrier aggregation of up to four carriers on the downlink and two carriers on the uplink, LAA for operation in unlicensed bands, LTE Wi-Fi Aggregation including LWIP, RCLWI, isolated operation and mission-critical voice communications for public safety, application-specific congestion management, User-Plane Congestion Management, enhancement to WebRTC interoperability, architecture enhancement for dedicated core networks, enhancement to proximity-based services, Mission-Critical Push-to-Talk, group communications, CoMP enhancements, small cell enhancements, machine-type communications enhancements including NB-IoT and Extended Coverage GSM (EC-GSM), VoLTE enhancements, SON enhancements, shared network enhancements, indoor positioning based on WLAN access points, Bluetooth beacons and barometric pressure, and enhanced circuit-switched fallback. HSPA+ features include support for dual-band uplink carrier aggregation.

---

[97] This level of aggregation refers to signaling capabilities. The number of carriers that can be combined in an actual deployment is smaller and depends on RAN co-existence studies. Refer to the appendix section on "Carrier Aggregation" for additional details.

- **Release 14**: Expected completion June 2017. Contemplated features include uplink operation for LAA (enhanced LAA), full-dimension MIMO enhanced with up to 32 antenna elements, dual-connectivity of licensed and unlicensed carriers across non-collocated nodes, vehicle-to-vehicle and vehicle-to-infrastructure (V2X) communications built on Release 12 Proximity Services, shared LTE broadcast in which different operators broadcast the same content on the same frequency, non-IP operation for IoT, Downlink Multi-user Superposition Transmission (MUST), enhanced LWA, VoLTE enhancements, LWIP/LWA enhancements, eMBMS enhancements, NB-IoT enhancements, and LTE latency reduction.
- **Release 15**: Expected completion September 2018. Non-standalone (using LTE core network) option expected March 2018. Specifies phase 1 of 5G. NR radio, 4G-5G interworking, and MIMO/beamforming. Further LTE enhancements include ultra-reliable low-latency communications, NB-IoT enhancements, LAA enhancements, V2X enhancements, DL 1024 QAM, CoMP enhancements, AAS enhancements, and LTE/5G core network capability.
- **Release 16**: Expected completion end of 2019. Specifies phase 2 of 5G. Adds URLLC, spectrum sharing, unlicensed spectrum operation and integration, and multiple other enhancements. Further LTE enhancements.

Data Throughput Comparison

Data throughput is an important metric for quantifying network throughput performance. Unfortunately, the ways in which various organizations quote throughputs vary tremendously, often resulting in misleading claims. The intent of this paper is to realistically represent the capabilities of these technologies.

One method of representing a technology's throughput is what people call "peak throughput" or "peak network speed," which refers to the fastest possible transmission speed over the radio link and is generally based on the highest-order modulation available and the least amount of coding (error correction) overhead. Peak network speed is also usually quoted at layer 2 of the radio link. Because of protocol overhead, actual application throughput may be up to 10% lower than this layer-2 value.

Another method is to disclose throughputs actually measured in deployed networks with applications such as File Transfer Protocol (FTP) under favorable conditions, which assume light network load (as low as one active data user in the cell sector) and favorable signal propagation. This number is useful because it demonstrates the high-end, actual capability of the technology in current deployments, referred to in this paper as the "peak user rate." Average rates are lower than this peak rate and are difficult to predict because they depend on a multitude of operational and network factors. Except when the network is congested, however, the majority of users should experience throughput rates higher than one-half of the peak achievable rate.

Some operators, primarily in the United States, also quote typical throughput rates, which are based on throughput tests the operators have done across their operating networks and incorporate a higher level of network load. Although the operators do not disclose the precise methodologies they use to establish these figures, the values provide a good indication of what users can realistically expect.

Table 14 presents the technologies in terms of peak network throughput rates, peak user rates (under favorable conditions), and typical rates. It omits values that are not yet known, such as for future technologies.

The projected typical rates for HSPA+ and LTE show a wide range because these technologies exploit favorable radio conditions to achieve high throughput rates, but under poor radio conditions, throughput rates are lower.

Table 14: Throughput Performance of Different Wireless Technologies (Blue Indicates Theoretical Peak Rates, Green Typical)

	Downlink		Uplink	
	Peak Network Speed	Peak and/or Typical User Rate	Peak Network Speed	Peak and/or Typical User Rate
5G in mmWave, early versions[98]	5 Gbps	500 Mbps	2 Gbps	250 Mbps
5G in mmWave, later versions	50 Gbps	5 Gbps	25 Gbps	2 Gbps
LTE (2X2 MIMO, 10+10 MHz, DL 64 QAM, UL 16 QAM)	70 Mbps	6.5 to 26.3 Mbps[99]	35 Mbps[100]	6.0 to 13.0 Mbps
LTE-Advanced (2X2 or 4X4 MIMO, 20+20 MHz or 40+20 MHz with Carrier Aggregation [CA], DL 64 QAM, UL 16 QAM)	300 Mbps	N/A	71 Mbps[101]	N/A
LTE Advanced (4X4 MIMO, 60+20MHz, CA, 256 QAM DL, 64 QAM UL)	600 Mbps		150 Mbps	
LTE Advanced (4X4 MIMO, 80+20 MHz, CA, 256 QAM DL, 64 QAM UL)	> 1 Gbps		150 Mbps	

---

[98] Speculative values, Rysavy Research estimates. Assumes 200 MHz radio channel, 2:1 TDD. Throughput rates would double using 400 MHz.

[99] 5G Americas member company analysis for downlink and uplink. Assumes single user with 50% load in other sectors. AT&T and Verizon are quoting typical user rates of 5-12 Mbps on the downlink and 2-5 Mbps on the uplink for their networks. See additional LTE throughput information in the section below, "LTE Throughput."

[100] Assumes 64 QAM. Otherwise 22 Mbps with 16 QAM.

[101] Assumes 64 QAM. Otherwise 45 Mbps with 16 QAM.

	Downlink		Uplink	
	Peak Network Speed	**Peak and/or Typical User Rate**	**Peak Network Speed**	**Peak and/or Typical User Rate**
LTE Advanced (8X8 MIMO, 20+20 MHz, DL 64 QAM, UL 64 QAM)	1.2 Gbps	N/A	568 Mbps	N/A
LTE Advanced, 100 MHz + 100 MHz	3 Gbps		1.5 Gbps	
LTE Advanced 32 Carriers	>> 3 Gbps			
EDGE (type 2 MS)	473.6 Kbps	Not Applicable (N/A)	473.6 Kbps	N/A
EDGE (type 1 MS) (Practical Terminal)	236.8 Kbps	200 Kbps peak 160 to 200 Kbps typical[102]	236.8 Kbps	200 Kbps peak 80 to 160 Kbps typical[103]
HSDPA Initial Devices (2006)	1.8 Mbps	> 1 Mbps peak	384 Kbps	350 Kbps peak
HSDPA	14.4 Mbps	N/A	384 Kbps	N/A

---

[102] Assumes four-to-five downlink timeslot devices (each timeslot capable of 40 Kbps).

[103] Assumes two-to-four uplink timeslot devices (each timeslot capable of 40 Kbps).

	Downlink		Uplink	
	Peak Network Speed	**Peak and/or Typical User Rate**	**Peak Network Speed**	**Peak and/or Typical User Rate**
HSPA[104] Initial Implementation	7.2 Mbps	> 5 Mbps peak 700 Kbps to 1.7 Mbps typical[105]	2 Mbps	> 1.5 Mbps peak 500 Kbps to 1.2 Mbps typical
HSPA	14.4 Mbps	N/A	5.76 Mbps	N/A
HSPA+ (DL 64 QAM, UL 16 QAM, 5+5 MHz)	21.6 Mbps	1.9 Mbps to 8.8 Mbps typical[106]	11.5 Mbps	1 Mbps to 4 Mbps typical
HSPA+ (2X2 MIMO, DL 16 QAM, UL 16 QAM, 5+5 MHz)	28 Mbps	N/A	11.5 Mbps	N/A
HSPA+ (2X2 MIMO, DL 64 QAM, UL 16 QAM, 5+5 MHz)	42 Mbps	N/A	11.5 Mbps	N/A
HSPA+ (DL 64 QAM, UL 16 QAM, Dual Carrier, 10+5 MHz)	42 Mbps	Approximate doubling of 5+5 MHz rates - 3.8 to 17.6 Mbps.	11.5 Mbps	1 Mbps to 4 Mbps typical
HSPA+ (2X2 MIMO DL, DL 64 QAM, UL 16 QAM, Dual Carrier, 10+10 MHz)	84 Mbps	N/A	23 Mbps	N/A

---

[104] High Speed Packet Access (HSPA) consists of systems supporting both High Speed Downlink Packet Access (HSDPA) and High Speed Uplink Packet Access (HSUPA).

[105] Typical downlink and uplink throughput rates based on AT&T press release, June 4, 2008

[106] 5G Americas member company analysis. Assumes Release 7 with 64 QAM and F-DPCH. Single user. 50% loading in neighboring cells. Higher rates expected with subsequent 3GPP releases.

	Downlink		Uplink	
	Peak Network Speed	**Peak and/or Typical User Rate**	**Peak Network Speed**	**Peak and/or Typical User Rate**
HSPA+ (2X2 MIMO DL, DL 64 QAM, UL 16 QAM, Quad-Carrier,[107] 20+10 MHz)	168 Mbps	N/A	23 Mbps	N/A
HSPA+ (2X2 MIMO DL and UL, DL 64 QAM, UL 16 QAM, Eight-Carrier, 40+10 MHz)	336 Mbps	N/A	69 Mbps	N/A
HSPA+ (4X2 MIMO DL, 2X2 MIMO UL, DL 64 QAM, UL 16 QAM, 8 carrier, 40+10 MHz)	672 Mbps	N/A	69 Mbps	N/A
EDGE (type 2 MS)	473.6 Kbps	Not Applicable (N/A)	473.6 Kbps	N/A
EDGE (type 1 MS) (Practical Terminal)	236.8 Kbps	200 Kbps peak 160 to 200 Kbps typical[108]	236.8 Kbps	200 Kbps peak 80 to 160 Kbps typical[109]
CDMA2000 EV-DO Rel. 0	2.4 Mbps	> 1 Mbps peak	153 Kbps	150 Kbps peak

---

[107] No operators have announced plans to deploy HSPA in a quad (or greater) carrier configuration. Three carrier configurations, however, have been deployed.

[108] Assumes four-to-five downlink timeslot devices (each timeslot capable of 40 Kbps).

[109] Assumes two-to-four uplink timeslot devices (each timeslot capable of 40 Kbps).

	Downlink		Uplink	
	Peak Network Speed	**Peak and/or Typical User Rate**	**Peak Network Speed**	**Peak and/or Typical User Rate**
CDMA2000 EV-DO Rev. A	3.1 Mbps	> 1.5 Mbps peak 600 Kbps to 1.4 Mbps typical[110]	1.8 Mbps	> 1 Mbps peak 300 to 500 Kbps typical
CDMA2000 EV-DO Rev. B (3 radio channels 5+5 MHz)	14.7[111] Mbps	Proportional increase of Rev A typical rates based on number of carriers.	5.4 Mbps	N/A
CDMA2000 EV-DO Rev B Theoretical (15 radio channels 20+20 MHz)	73.5 Mbps	N/A	27 Mbps	N/A

Additional information about LTE throughput appears below in the section "LTE Throughput."

Latency Comparison

As important as throughput is network latency, defined as the round-trip time it takes data to traverse the network. Each successive data technology from GPRS forward reduces latency, with LTE networks having latency as low as 15 msec. Ongoing improvements in each technology mean that all of these values will go down as vendors and operators fine-tune their systems. Figure 39 shows the latency of different 3GPP technologies.

---

[110] Typical downlink and uplink throughput rates based on Sprint press release Jan. 30, 2007.

[111] Assuming use of 64 QAM.

Figure 39: Latency of Different Technologies[112]



The values shown in Figure 39 reflect measurements of commercially deployed technologies, with EDGE Release 7 achieving 70 to 95 msec, HSPA+ 25 to 30 msec, and LTE 15 to 20 msec. A latency goal for 5G is less than 4 msec for broadband and 0.5 msec for mission-critical applications.

Spectral Efficiency

The evolution of data services is characterized by an increasing number of users with ever-higher bandwidth demands. As the wireless data market grows, deploying wireless technologies with high spectral efficiency is of paramount importance. Keeping all other things equal, including frequency band, amount of spectrum, and cell site spacing, an increase in spectral efficiency translates to a proportional increase in the number of users supported at the same load per user—or, for the same number of users, an increase in throughput available to each user.

Increased spectral efficiency, however, comes at a price because it generally involves greater complexity for both user and base station equipment. Complexity can arise from the increased number of calculations performed to process signals or from additional radio components. Hence, operators and vendors must balance market needs against network and equipment costs. OFDMA technologies, such as LTE and planned 5G approaches, achieve higher spectral efficiency with lower overall complexity, especially in larger bandwidths.

---

[112] 5G Americas member companies. Measured between subscriber unit and a node immediately external to wireless network. Does not include internet latency. Note that there is some variation in latency based on network configuration and operating conditions.

As shown in Figure 40, the link-layer performance of modern wireless technologies is approaching the theoretical limits as defined by the Shannon bound. (The Shannon bound is a theoretical limit to the information transfer rate [per unit bandwidth] that can be supported by any communications link. The bound is a function of the SNRs of the communications link.) Figure 40 also shows that HSDPA, 1xEV-DO, and IEEE 802.16e-2005 are all within 2 to 3 decibels (dB) of the Shannon bound, indicating that there is not much room for improvement from a link-layer perspective.

Figure 40: Performance Relative to Theoretical Limits for HSDPA, EV-DO, and WiMAX (IEEE 802.16e-2005)[113]



The curves in Figure 40 are for an Additive White Gaussian Noise Channel (AWGN). If the channel is slowly varying and the frame interval is significantly shorter than the coherence time, the effects of fading can be compensated for by practical channel estimation algorithms—thus justifying the AWGN assumption. For instance, at 3 km per hour and fading at 2 GHz, the Doppler spread is about 5.5 Hz. The coherence time of the channel is thus 1 second (sec)/5.5 or 180 msec. Frames are well within the coherence time of the channel, because they are typically 20 msec or less. As such, the channel appears

---

[113] 5G Americas member contribution.

“constant” over a frame, and the Shannon bound applies. Furthermore, significantly more of the traffic in a cellular system is at slow speeds (for example, 3 km/hr. or less) rather than at higher speeds. The Shannon bound is consequently also relevant for a realistic deployment environment.

As the speed of the mobile station increases and the channel estimation becomes less accurate, additional margin is needed. This additional margin, however, would impact the different standards fairly equally.

The focus of future technology enhancements is on improving system performance aspects that reduce interference to maximize the experienced SNRs in the system and antenna techniques (such as MIMO) that exploit multiple links or steer the beam rather than on investigating new air interfaces that attempt to improve link-layer performance.

MIMO techniques using spatial multiplexing to increase the overall information transfer rate by a factor proportional to the number of transmit or receive antennas do not violate the Shannon bound because the per-antenna transfer rate (that is, the per-communications link transfer rate) is still limited by the Shannon bound.

Figure 41 compares the spectral efficiency of different wireless technologies based on a consensus view of 5G Americas contributors to this paper. It shows the continuing evolution of the capabilities of all the technologies discussed. The values shown are reasonably representative of real-world conditions. Most simulation results produce values under idealized conditions; as such, some of the values shown are lower (for all technologies) than the values indicated in other papers and publications. For instance, 3GPP studies indicate higher HSPA and LTE spectral efficiencies. Nevertheless, there are practical considerations in implementing technologies that can prevent actual deployments from reaching calculated values. Consequently, initial versions of technology may operate at lower levels but then improve over time as designs are optimized. Therefore, readers should interpret the values shown as achievable, but not as the actual values that might be measured in any specific deployed network.

Figure 41: Comparison of Downlink Spectral Efficiency[114]



The values shown in Figure 41 are not all possible combinations of available features. Rather, they are representative milestones in ongoing improvements in spectral efficiency. For instance, terminals may employ Mobile Receive Diversity but not equalization.

The figure does not include EDGE, but EDGE itself is spectrally efficient at 0.6 bps/Hz using mobile receive diversity and, potentially, 0.7 bps/Hz with MIMO. Relative to WCDMA Release 99, HSDPA increases capacity by almost a factor of three. Type 3 receivers that include MMSE equalization and Mobile Receive Diversity (MRxD) effectively double HSDPA spectral efficiency. The addition of dual-carrier operation and 64 QAM increases spectral efficiency by about 15%, and MIMO can increase spectral efficiency by another 15%, reaching 1.2 bps/Hz. Dual-carrier HSPA+ offers a gain in spectral efficiency from cross-carrier scheduling with possible gains of about 10%.[115]

---

[114] Joint analysis by 5G Americas members. 5+5 MHz FDD for UMTS-HSPA/LTE. Mix of mobile and stationary users.

Some enhancements, such as 64 QAM for HSPA, are simpler to deploy than other enhancements, such as 2X2 MIMO. The former can be done as a software upgrade, whereas the latter requires additional hardware at the base station. Thus, the figure does not necessarily show the actual progression of technologies that operators will deploy to increase spectral efficiency.

Beyond HSPA, 3GPP LTE results in further spectral efficiency gains, initially with 2X2 MIMO, then 4X2 MIMO, and then 4X4 MIMO. The gain for 4X2 MIMO will be 20% more than LTE with 2X2 MIMO; the gain for 4X4 MIMO in combination with interference rejection combining (IRC) will be 70% greater than 2X2 MIMO, reaching 2.4 bps/Hz. This value represents a practical deployment of 4X4 MIMO, with random phase and some timing-alignment error included in each of the four transmit paths. CoMP, discussed below in the appendix, provides a minimal contribution to spectral efficiency.

LTE is even more spectrally efficient when deployed using wider radio channels of 10+10 MHz and 20+20 MHz, although most of the gain is realized at 10+10 MHz. LTE TDD has spectral efficiency that is within 1% or 2% of LTE FDD.[116]

Figure 42 compares the uplink spectral efficiency of the different systems.

---

[115] 5G Americas member analysis. Vendor estimates for spectral-efficiency gains from dual-carrier operation range from 5% to 20%. Lower spectral efficiency gains are due to full-buffer traffic assumptions. In more realistic operating scenarios, gains will be significantly higher.

[116] Assumes best-effort traffic. Performance between LTE-TDD and FDD differs for real-time traffic for the following reasons: a.) The maximum number of HARQ process should be made as small as possible to reduce the packet re-transmission latency. b.) In FDD, the maximum number of HARQ process is fixed and, as such, the re-transmission latency is 7ms. c.) For TDD, the maximum number of HARQ process depends on the DL:UL configurations. As an example, the re-transmission latency for TDD config-1 is 9ms. d.) Because of higher re-transmission latency, the capacity of real-time services cannot be scaled for TDD from FDD based on the DL:UL ratio.

Figure 42: Comparison of Uplink Spectral Efficiency[117]



The implementation of HSUPA in HSPA significantly increases uplink capacity.

With LTE, spectral efficiency increases by use of receive diversity. Initial systems will employ 1X2 receive diversity (two antennas at the base station). 1X4 diversity will increase spectral efficiency by 50%, to 1.0 bps/Hz, and 1X8 diversity will provide a further 20% increase, from 1.0 bps/Hz to 1.2 bps/Hz.

It is also possible to employ Multi-User MIMO (MU-MIMO), which allows simultaneous transmission by multiple users on the same physical uplink resource to increase spectral efficiency. MU-MIMO will provide a 15% to 20% spectral efficiency gain, with actual increases depending on how well link adaptation is implemented. The figure uses a conservative 15% gain, showing MU-MIMO with a 1X4 antenna configuration increasing spectral efficiency by 15%, to 1.15 bps/Hz, and 2X4 MU-MIMO a further 15%, to 1.3 bps/Hz.

---

[117] Joint analysis by 5G Americas members. 5+5 MHz for UMTS-HSPA/LTE. Mix of mobile and stationary users.

In Release 11, uplink CoMP using 1X2 increases efficiency from .65 bps/Hz to 1.0 bps/Hz. Many of the techniques used to improve LTE spectral efficiency can also be applied to HSPA since they are independent of the radio interface.

Figure 43 compares voice spectral efficiency.

Figure 43: Comparison of Voice Spectral Efficiency[118]



Figure 43 shows UMTS Release 99 with AMR 12.2 Kbps, 7.95 Kbps, and 5.9 Kbps vocoders. The AMR 12.2 Kbps vocoder provides superior voice quality in good (for example, static and indoor) channel conditions.

UMTS has dynamic adaptation between vocoder rates, enabling enhanced voice quality compared with EVRC at the expense of capacity in situations that are not capacity limited. With the addition of mobile receive diversity, UMTS circuit-switched voice capacity could reach 120 Erlangs in 5+5 MHz.

---

[118] Joint analysis by 5G Americas members. 5 + 5 MHz for UMTS-HSPA/LTE. Mix of mobile and stationary users.

VoIP Erlangs in this paper are defined as the average number of concurrent VoIP users that can be supported over a defined period of time (often one hour) assuming a Poisson arrival process and meeting a specified outage criteria (often less than 2% of the users exhibiting greater than 1% frame-error rate). Depending on the specific enhancements implemented, voice capacity could double over existing circuit-switched systems. These gains do not derive through use of VoIP, but rather from advances in radio techniques applied to the data channels. Many of these same advances may also be applied to current circuit-switched modes.

LTE achieves very high voice spectral efficiency because of better uplink performance since there is no in-cell interference. The figure shows LTE VoIP spectral efficiency using AMR at 12.2 Kbps, 7.95 Kbps, and 5.9 Kbps.

VoIP for LTE can use a variety of codecs. The figures show performance assuming specific codecs at representative bit rates. For Enhanced Variable Rate Codecs (EVRCs), the figure shows the average bit rate.

The voice efficiency of the wideband AMR voice codec, operating at 12.65 Kbps, is similar to the AMR codec at 12.2 Kbps, with a value of 180 Erlangs for both since both codecs operate at approximately the same bit rate. 1xRTT has voice capacity of 85 Erlangs in 5+5 MHz with EVRC-A and reaches voice capacity of 120 Erlangs with the use of Quasi-Linear Interference Cancellation (QLIC) and EVRC-B at 6 Kbps.

Data Consumed by Streaming and Virtual Reality

Table 15 quantifies usage based on advanced video compression schemes such as H.264 and H.265, the type of application, and usage per day.

Table 15: Data Consumed by Streaming and Virtual Reality[119]



Application	Throughput (Mbps)	MByte/hour	Hrs./day	GB/month
Audio or Music	0.1	58	0.5	0.9
			1.0	1.7
			2.0	3.5
			4.0	6.9
Small Screen Video (e.g., Feature Phone)	0.2	90	0.5	1.4
			1.0	2.7
			2.0	5.4
			4.0	10.8
Medium Screen Video (e.g., Smartphone, Tablet, Laptop)	1.0	450	0.5	6.8
			1.0	13.5
			2.0	27.0
			4.0	54.0
Larger Screen Video (e.g., 720p medium definition)	3.0	1350	0.5	20.3
			1.0	40.5
			2.0	81.0
			4.0	162.0
High Definition (e.g., 1080p Netflix HD)	5.0	2250	0.5	33.8
			1.0	67.5
			2.0	135
			4.0	270
4K Ultra-High Definition (Rates will range 12 to 30 Mbps)	20.0	9000	0.5	135
			1.0	270
			2.0	540
			4.0	1080
4G, 30 FPS, Virtual Reality (Rates will range 10 to 50 Mbps)	25.0	11250	0.5	169
			1.0	338
			2.0	675
			4.0	1350
8K, 90 FPS, Virtual Reality (Rates will exceed 200 Mbps)	200.0	90000	0.5	1350
			1.0	2700
			2.0	5400
			4.0	10800
6 Degrees Freedom VR (Rates will range 200 to 1,000 Mbps)	500.0	225000	0.5	3375
			1.0	6750
			2.0	13500
			4.0	27000

Rysavy Research

---

[119] Rysavy Research analysis. For virtual reality-data requirements, refer to ABI Research/Qualcomm, *Augmented and Virtual Reality: the First Wave of 5G Killer Apps,* 2017. See also Netflix discussion of usage, "How can I control how much data Netflix uses?" https://help.netflix.com/en/node/87. Viewed May 3, 2016.

Spectrum Bands

3GPP technologies operate in a wide range of radio bands. As new spectrum becomes available, 3GPP updates its specifications for these bands. Although the support of a new frequency band may be introduced in a particular release, 3GPP specifies ways to implement devices and infrastructure operating on any frequency band, according to releases previous to the introduction of that particular frequency band. For example, although band 5 (US Cellular Band) was introduced in Release 6, the first devices operating on this band were compliant with the release 5 of the standard.

Table 16 shows the UMTS FDD bands.

Table 16: UMTS FDD Bands[120]

Operating Band	UL Frequencies UE Transmit, Node B Receive	DL Frequencies UE Receive, Node B Transmit
I	1920 - 1980 MHz	2110 -2170 MHz
II	1850 -1910 MHz	1930 -1990 MHz
III	1710-1785 MHz	1805-1880 MHz
IV	1710-1755 MHz	2110-2155 MHz
V	824 - 849MHz	869-894MHz
VI	830-840 MHz	875-885 MHz
VII	2500 - 2570 MHz	2620 - 2690 MHz
VIII	880 - 915 MHz	925 - 960 MHz
IX	1749.9 - 1784.9 MHz	1844.9 - 1879.9 MHz
X	1710-1770 MHz	2110-2170 MHz
XI	1427.9 - 1447.9 MHz	1475.9 - 1495.9 MHz
XII	699 - 716 MHz	729 - 746 MHz
XIII	777 - 787 MHz	746 - 756 MHz
XIV	788 - 798 MHz	758 - 768 MHz
XV	Reserved	Reserved
XVI	Reserved	Reserved
XVII	Reserved	Reserved
XVIII	Reserved	Reserved
XIX	830 – 845 MHz	875 -890 MHz
XX	832 - 862 MHz	791 - 821 MHz
XXI	1447.9 - 1462.9 MHz	1495.9 - 1510.9 MHz
XXII	3410 – 3490 MHz	3510 – 3590 MHz
XXV	1850 -1915 MHz	1930 -1995 MHz
XXVI	814-849 MHz	859-894 MHz
XXXII (NOTE 1)	N/A	1452 – 1496 MHz
NOTE 1: Restricted to UTRA operation when dual-band is configured (e.g., DB-DC-HSDPA or dual band 4C-HSDPA). The down link frequenc(ies) of this band are paired with the uplink frequenc(ies) of the other FDD band (external) of the dual band configuration.		

---

[120] 3GPP, *Base Station (BS) radio transmission and reception (FDD) (Release 14),* December 2016, Technical Specification 25.104, V14.1.0.

Universal Mobile Telecommunications System (UMTS) Time Division Duplex (TDD) bands are the same as the LTE TDD bands. Table 17 details the LTE Frequency Division Duplex (FDD) and TDD bands.

Table 17: LTE FDD and TDD bands[121]



E-UTRA Operating Band	Uplink (UL) operating band BS receive UE transmit $F_{UL\ low}$ – $F_{UL\ high}$	Downlink (DL) operating band BS transmit UE receive $F_{DL\ low}$ – $F_{DL\ high}$	Duplex Mode
1	1920 MHz – 1980 MHz	2110 MHz – 2170 MHz	FDD
2	1850 MHz – 1910 MHz	1930 MHz – 1990 MHz	FDD
3	1710 MHz – 1785 MHz	1805 MHz – 1880 MHz	FDD
4	1710 MHz – 1755 MHz	2110 MHz – 2155 MHz	FDD
5	824 MHz – 849 MHz	869 MHz – 894MHz	FDD
6 (NOTE 1)	830 MHz – 840 MHz	875 MHz – 885 MHz	FDD
7	2500 MHz – 2570 MHz	2620 MHz – 2690 MHz	FDD
8	880 MHz – 915 MHz	925 MHz – 960 MHz	FDD
9	1749.9 MHz – 1784.9 MHz	1844.9 MHz – 1879.9 MHz	FDD
10	1710 MHz – 1770 MHz	2110 MHz – 2170 MHz	FDD
11	1427.9 MHz – 1447.9 MHz	1475.9 MHz – 1495.9 MHz	FDD
12	699 MHz – 716 MHz	729 MHz – 746 MHz	FDD
13	777 MHz – 787 MHz	746 MHz – 756 MHz	FDD
14	788 MHz – 798 MHz	758 MHz – 768 MHz	FDD
15	Reserved	Reserved	FDD
16	Reserved	Reserved	FDD
17	704 MHz – 716 MHz	734 MHz – 746 MHz	FDD
18	815 MHz – 830 MHz	860 MHz – 875 MHz	FDD
19	830 MHz – 845 MHz	875 MHz – 890 MHz	FDD
20	832 MHz – 862 MHz	791 MHz – 821 MHz	
21	1447.9 MHz – 1462.9 MHz	1495.9 MHz – 1510.9 MHz	FDD
22	3410 MHz – 3490 MHz	3510 MHz – 3590 MHz	FDD
23[1]	2000 MHz – 2020 MHz	2180 MHz – 2200 MHz	FDD
24	1626.5 MHz – 1660.5 MHz	1525 MHz – 1559 MHz	FDD
25	1850 MHz – 1915 MHz	1930 MHz – 1995 MHz	FDD
26	814 MHz – 849 MHz	859 MHz – 894 MHz	FDD
27	807 MHz – 824 MHz	852 MHz – 869 MHz	FDD
28	703 MHz – 748 MHz	758 MHz – 803 MHz	FDD
29	N/A	717 MHz – 728 MHz	FDD (NOTE 2)
30	2305 MHz – 2315 MHz	2350 MHz – 2360 MHz	FDD
31	452.5 MHz – 457.5 MHz	462.5 MHz – 467.5 MHz	FDD
32	N/A	1452 MHz – 1496 MHz	FDD (NOTE 2)
33	1900 MHz – 1920 MHz	1900 MHz – 1920 MHz	TDD
34	2010 MHz – 2025 MHz	2010 MHz – 2025 MHz	TDD
35	1850 MHz – 1910 MHz	1850 MHz – 1910 MHz	TDD
36	1930 MHz – 1990 MHz	1930 MHz – 1990 MHz	TDD
37	1910 MHz – 1930 MHz	1910 MHz – 1930 MHz	TDD
38	2570 MHz – 2620 MHz	2570 MHz – 2620 MHz	TDD
39	1880 MHz – 1920 MHz	1880 MHz – 1920 MHz	TDD
40	2300 MHz – 2400 MHz	2300 MHz – 2400 MHz	TDD
41	2496 MHz – 2690 MHz	2496 MHz – 2690 MHz	TDD
42	3400 MHz – 3600 MHz	3400 MHz – 3600 MHz	TDD
43	3600 MHz – 3800 MHz	3600 MHz – 3800 MHz	TDD
44	703 MHz – 803 MHz	703 MHz – 803 MHz	TDD
45	1447 MHz – 1467 MHz	1447 MHz – 1467 MHz	TDD
46	5150 MHz – 5925 MHz	5150 MHz – 5925 MHz	TDD (NOTE 3, NOTE 4)
47	5855 MHz – 5925 MHz	5855 MHz – 5925 MHz	TDD (NOTE 7)
48	3550 MHz – 3700 MHz	3550 MHz – 3700 MHz	TDD
65	1920 MHz – 2010 MHz	2110 MHz – 2200 MHz	FDD
66	1710 MHz – 1780 MHz	2110 MHz – 2200 MHz	FDD (NOTE 5)
67	N/A	738 MHz – 758 MHz	FDD (NOTE 2)
68	698 MHz – 728 MHz	753 MHz – 783 MHz	FDD
69	N/A	2570 MHz – 2620 MHz	FDD (NOTE 2)
70	1695 MHz – 1710 MHz	1995 MHz – 2020 MHz	FDD[6]

NOTE 1: Band 6, 23 are not applicable.

NOTE 2: Restricted to E-UTRA operation when carrier aggregation is configured. The downlink operating band is paired with the uplink operating band (external) of the carrier aggregation configuration that is supporting the configured Pcell.

NOTE 3: This band is an unlicensed band restricted to licensed-assisted operation using Frame Structure Type 3.

NOTE 4: Band 46 is divided into four sub-bands as in Table 5.5-1A.

NOTE 5: The range 2180 – 2200 MHz of the DL operating band is restricted to E-UTRA operation when carrier aggregation is configured.

NOTE 6: The range 2010-2020 MHz of the DL operating band is restricted to E-UTRA operation when carrier aggregation is configured and TX-RX separation is 300 MHz. The range 2005-2020 MHz of the DL operating band is restricted to E-UTRA operation when carrier aggregation is configured and TX-RX separation is 295 MHz.

NOTE 7: No BS requirement is defined for this band.

5G

This section provides early details on aspects of 5G, including architecture, LTE-NR coexistence, integrated access and backhaul, and performance.

Architecture

The overall 5G architecture consists of what 3GPP calls the New Generation Radio-Access Network (NG-RAN) and the 5G Core (5GC), as shown in Figure 44. The figure shows the Access and Mobility Management Function (AMF); the User Plane Function (UPF); the NR NodeB (gNB), which is the 5G base station; and the NG and Xn interfaces.

Figure 44: 5G Architecture[122]



Figure 45 shows the functional split between the NG-RAN and 5GC.

---

[121] 3GPP, *Evolved Universal Terrestrial Radio Access (E-UTRA); Base Station (BS) radio transmission and reception (Release 14)*, March 2017, Technical Specification 36.104, V14.3.0.

[122] 3GPP, *3GPP TS 38.300, NR; NR and NG-RAN Overall Description; Stage 2 (Release 15), V0.3.0 (2017-05).*

Figure 45: Functional Split between NG-RAN and 5GC[123]


gNB
Inter Cell RRM
RB Control
Connection Mobility Cont.
Radio Admission Control
Measurement Configuration & Provision
Dynamic Resource Allocation (Scheduler)
AMF
NAS Security
Idle State Mobility Handling
SMF
UE IP address allocation
PDU Session Control
UPF
Mobility Anchoring
PDU Handling
internet
NG-RAN
5GC

The main body of this paper summarizes the features being specified in Releases 15 and 16 for NR and the core network. Additional capabilities that will be part of Release 15 include:

- A PDCP packet duplication function to allow redundant transmission of signaling or user data on two bearer paths.
- A new protocol layer called Service Data Adaptation Protocol (SDAP) that offers 5GC QoS flows.
- A new Radio Resource Control (RRC) inactive state designed for low-latency communications.
- A new system information broadcast model that allows on-demand system information instead of always having to broadcast system information (to reduce overhead in 5G beam sweeping).

Architecture Options

This topic was introduced in the main part of the paper and is covered here in more detail. In Release 15, 3GPP defines a number of different architecture options, shown in the following three figures. In many of these options, although not all, the 5G network integrates with LTE.

---

[123] Ibid.

Figure 46: 5G Network Architecture Options in 3GPP Release 15[124]


3
EPC
5G CN
Can supp. "DC/3C"
E-UTRA
NR
3 a
"DC/1A"
3 x
Non-Standalone / "LTE assisted", EPC connected
7
7 a
7 x
Non-Standalone / "LTE assisted", 5G CN connected
Non Standalone Options
2
5
Standalone NR/ 5G CN connected
Standalone eLTE, 5G CN connected
Standalone options
S1-MME
S1-U
NG2 (CP)
NG3 (UP)
Xx-C
Xx-U
Xn-C
Xn-U
LTE → LTE Rel15 ("eLTE") where needed

Figure 47: De-Prioritized 5G Network Architecture Options in 3GPP Release 15



Work on Option 4/4A will be started after the work on Option 2, 3 series and 7 series are completed. This is logical as Option 4/4A would be only used for dual connectivity with 5G lower frequency band than LTE

Work on Option 5 (LTE connecting to 5G core) is covered in a separate work item (as no 5G impacts). This requires devices to also be upgraded (as e.g. broadcast of core network type), thus legacy devices need still connection to EPC

4
EPC
5G CN
Can supp. "DC/3C"
E-UTRA
NR
4 a
"DC/1A"
Non-Standalone / "NR assisted", 5G CN connected
Non Standalone Option
S1-MME
S1-U
NG2 (CP)
NG3 (UP)
Xx-C
Xx-U
Xn-C
Xn-U
LTE → LTE Rel15 ("eLTE") where needed

---

[124] Nokia contribution, including subsequent two figures. For further details, refer to section 7.2, "5G Architecture Options," 3GPP TR 38.801, "Radio access architecture and interfaces."

Figure 48: Dual-Connectivity Options with LTE as Master


Option 3x combines the benefits of both worlds – (3/3a) Enables bearer split with nimimal impact to LTE eNodeB
S1-U or N3
New AS sublayer$_{LTE}$
New AS sublayer$_{LTE}$
PDCP$_{LTE}$
PDCP$_{LTE}$
Xx/Xn
RLC$_{LTE}$
RLC$_{LTE}$
RLC$_{NR}$
MAC$_{LTE}$
MAC$_{NR}$
MeNB (LTE)
SgNB (NR)
S1 or N3
New AS sublayer$_{LTE}$
New AS sublayer$_{NR}$
PDCP$_{LTE}$
PDCP$_{NR}$
RLC$_{LTE}$
RLC$_{NR}$
MAC$_{LTE}$
MAC$_{NR}$
MeNB (LTE)
SgNB (NR)
S1-U/N3
New AS sublayer$_{LTE}$
New AS sublayer$_{NR}$
Xx/Xn
PDCP$_{LTE}$
PDCP$_{NR}$
RLC$_{LTE}$
RLC$_{LTE}$
RLC$_{NR}$
MAC$_{LTE}$
MAC$_{NR}$
MeNB (LTE)
SgNB(NR)
Dual Connectivity (3/7) option – bearer split at eNB
Dual Connectivity (3a/7a) option – user plane traffic split at core network
Dual Connectivity (3x/7x) option – bearer split at gNB

LTE-NR Coexistence

LTE-NR coexistence is a Release 15 work item. This section describes how such co-existence may be achieved. Different LTE-NR co-existence cases include the following: time domain LTE/NR adjacent channel coexistence; LTE Secondary Cell on/off for LTE/NR adaptation; in-carrier LTE+NR coexistence in downlink, and in-carrier LTE+NR coexistence in uplink.

NR coexistence is required for LTE UEs of all releases. Because carrier aggregation was not introduced into LTE until LTE Release 10, CA-based techniques cannot be used as the sole means to achieve LTE/NR coexistence. However, CA techniques can be used for both time domain coexistence and frequency domain coexistence. For time domain coexistence, on a given carrier, LTE and NR are time-multiplexed by means of Secondary Cell (SCell) activation or deactivation. For frequency domain coexistence, the network configures a carrier, such as a 20MHz carrier, into multiple carriers, with, for example, 10MHz allocated to LTE and the remaining 10MHz to NR. Note that frequency domain coexistence can be accomplished without using carrier aggregation.

Figure 49 illustrates the frequency domain technique. Note that when splitting the 20MHz carrier into two allocations of 10MHz, the LTE carrier remains centered at the same frequency and the NR allocation is not consecutive.

Figure 49: Frequency Domain Coexistence of LTE and NR[125]



Time Domain LTE/NR Coexistence Techniques

Time domain coexistence of LTE and NR can be dynamic (subframe level) or semi-static (MAC/RRC). In the latter case, spectrum resources are configured as SCell for a LTE UE, and the network can turn these resources on or off by means of SCell activation or deactivation using MAC control elements or by adding and removing the SCell via RRC signaling. Whenever the SCell is deactivated or not configured, the spectrum resources can be used for NR transmissions. In LTE Rel. 12, small-cell enhancements were introduced that allow a UE to measure discovery reference signals (DRS) on a deactivated SCell. In that case, further coordination between LTE and NR may be required even when the SCell is deactivated, as DRS may still be transmitted periodically. Generally, though, this kind of coexistence can be achieved by network implementation.

For the case of dynamic coexistence, LTE and NR co-exist in the same spectrum, and the network can multiplex the two on a subframe level. Because LTE transmits Cell-Specific Reference Signals (CRS) in all DL subframes and in the Downlink Pilot Time Slot (DwPTS) and non-Multicast-Broadcast Single-Frequency network (non-MBSFN) region of special and MBSFN subframes, respectively, dynamic coexistence is not as straightforward as semi-static coexistence.

Similar to the case of time domain coexistence based on CA techniques, whenever OFDM symbols do not carry CRS, coexistence can be achieved by a gNB scheduler implementation. In particular, the gNB can schedule mini-slot-based transmissions in the Uplink Pilot Time Slot (UpPTS) region of a special subframe and in the MBSFN region of an MBSFN subframe, neither of which carry CRS. In LTE UL subframes, the gNB can schedule NR transmissions using either slots or mini-slots. For example, when Sounding Reference Signal (SRS) is transmitted at the end of a subframe, all 14 OFDM symbols may not be available for NR, and mini-slots can be used. Otherwise, slots can be used to transmit NR signals and channels in LTE UL subframes. Even in normal downlink subframes, mini-slots could be used to transmit NR channels and signals on OFDM symbols not carrying CRS. This, however, may leave almost half the resources of a normal DL subframe unusable for NR, so other techniques may be preferable. For example, symbols carrying CRS could also puncture NR transmissions, similar to URLLC transmissions that pre-empt NR transmissions. The same mechanisms specified for eMBB/URLLC coexistence could be used for LTE/NR coexistence.

---

[125] AT&T contribution, including explanatory text.

Frequency Domain LTE/NR Coexistence Techniques

Frequency domain coexistence between LTE and NR can also be dynamic or semi-static. Semi-static FDM-based coexistence is illustrated in Figure 49. Dynamic frequency domain coexistence is possible when the (e/g) NB schedules both LTE and NR in the same subframe on a Physical Resource Block (PRB) level.

There also exists the possibility of mixing semi-static and dynamic schemes as well as time division multiplexing (TDM)- and frequency division multiplexing (FDM)-based schemes based on the duplex direction. UL resources could be dynamically shared in a TDM fashion, whereas DL resources would be semi-statically configured and frequency division multiplexed between LTE and NR. For example, LTE could operate in paired spectrum, and NR could use LTE UL resources for NR UL transmissions but be configured with a separate DL or dynamic TDD carrier, such as at a higher frequency band. In this scenario, the LTE DL would be semi-statically frequency division multiplexed with NR, but LTE UL resources would need to be dynamically shared between LTE and NR. The semi-statically frequency division multiplexed NR resources could be for DL only or for both DL and UL. For example, it could be beneficial to allow for NR SRS transmissions on the frequency division multiplexed NR-only carrier.

Several issues need to be addressed for the shared LTE UL carrier. For example, if the non-shared NR carrier operates in mmWave spectrum while the shared NR/LTE carrier operates below 6GHz, the UE does not receive NR DL signals that can be used for power control and timing advance of the NR UL transmissions in the shared LTE UL resources. In this case, NR signals may have to be sent in the LTE-only DL resources or, alternatively, the NR-only UE needs to receive and process LTE signals in the LTE-only DL carrier. To avoid NR UEs processing LTE signals or LTE eNBs transmitting NR signals, 3GPP will need to investigate whether the aforementioned problem could be solved by signaling mechanisms. Regardless, further studies are needed to address these issues.

Coordination Requirements for LTE/NR Coexistence

While semi-static techniques identified for coexistence may require minimal coordination, dynamic (for example, per-TTI) sharing can be done by coordinating the LTE and NR transmissions via three different mechanisms:

1. Co-locating the NR and LTE scheduling.
2. Via the X2 interface (or the evolved version of the X2 interface in the new RAN architecture).
3. Over-the-air.

Options 1 and 2 do not impact any RAN1 specification, whereas Option 3 requires RAN1 specifications. Also, over-the-air coordination is desirable because it does not require LTE and NR scheduling and transmission to be handled by a single eNodeB, nor does it require an ultra-low-latency transport between them, thereby providing much more deployment flexibility. This can even allow NR and LTE to be deployed on different tiers (for example, macro and pico) and share the same channel.

Integrated Access and Backhaul

A study item for Release 15 with the likelihood of standardization in Release 16 is integrated access and backhaul, with which the 5G radio can provide both access and backhaul functions, as shown in Figure 50.

Figure 50: 5G Integrated Access and Backhaul



This 3GPP Study item, which has not yet begun, could address the following capabilities:[126]

- ❑ Wireless backhaul using 5G or LTE.
- ❑ Both indoor and outdoor scenarios.
- ❑ Flexible partitioning between access and backhaul functions.
- ❑ Autonomous configuration of access and wireless self-backhaul functions.
- ❑ Multi-hop wireless self-backhauling to enable flexible extension of range and coverage area.

---

[126] 3GPP, “Study on Integrated Access and Backhaul for NR,” RP-170831, March 2017.

- ❑ Autonomous adaptation on wireless self-backhaul to minimize service disruptions.
- ❑ Topological redundant connectivity on the wireless self-backhaul to enhance reliability and capacity and to reduce latency.

Performance

5G, with the ability to use wider radio channels than LTE, will be able to deliver much higher peak and average speeds, with initial estimates listed above in the section, "Data Throughput Comparison." In the absence of deployed networks to measure, companies have performed simulations, concentrating initially on one of the first uses cases of fixed wireless access.

Figure 51 shows downlink performance for a network using different base station ISDs, and with and without foliage. The Nokia simulation used base stations with 512 antenna elements, outdoor-mounted user equipment, 28 GHz, and an 800-MHz radio channel, mostly allocated to the downlink.

Figure 51: Downlink Performance, Different ISDs, Foliage vs. None[127]



The conclusion of this simulation is that a minimum performance of 100 Mbps at the cell-edge, a 5G objective, is possible at ISDs up to 200 meters, with and without foliage.

The following three figures are from another simulation study by Ericsson, this one also for fixed-wireless access, with the following key assumptions: 350-meter ISD, 96-antenna base stations, 200 MHz radio channels, 57% allocated to downlink, 1000 homes per sq.

---

[127] Nokia contribution. For a full discussion, refer to the associated paper by Frederick W. Vook, Eugene Visotsky, Timothy A. Thomas, and Amitava Ghosh, Nokia Bell Labs, *Performance Characteristics of 5G mmWave Wireless-to-the-Home*, available at http://ieeexplore.ieee.org/document/7869558/.

km., 25% of homes using 4K UHD video service at 15 Mbps, building heights of 4 to 10 meters, and trees from 5 to 15 meters.

Figure 52 shows the throughputs available across the coverage area, with many locations able to receive close to 1 Gbps.

Figure 52: Throughput Map of Suburban Area at Low Load[128]


Mbps
1000
900
800
700
600
500
400
300
200
100
0
600
400
200
0
-200
-400
-600
-600
-400
-200
0
200
400
600

Figure 53 shows the proportion of users that can obtain 15 Mbps and 100 Mbps service relative to monthly traffic volume. Note that the system supports thousands of GBs of service per subscriber per month.

---

[128] Ericsson contribution, Ericsson Technical Review, *5G and Fixed Wireless Access*, 2016, available at https://www.ericsson.com/assets/local/publications/ericsson-technology-review/docs/2016/etr-5g-and-fixed-wireless-access.pdf.

Figure 53: Proportion of Satisfied Users Relative to Monthly Usage[129]



Figure 54 shows that an ISD of 350 can be used with a combination of indoor, wall-mounted, and rooftop antennas. A large percentage of users, 78%, can use indoor antennas, facilitating deployment.

Figure 54: Breakdown of Indoor, Wall-Mounted, and Rooftop Antennas[130]



---

[129] Ibid.

[130] Ibid.

The simulation study shows that 5G fixed wireless access deployments using a larger ISD of 350 meters, translating to 11 base stations per square kilometer, can provide competitive broadband service.

In this environment, handsets with 5G mmWave capability will also be able to access the networks, but the antennas they use may not be as effective as the fixed-wireless equipment, so handsets may need to fall back to 4G, depending on their precise locations. For this reason, the dual-connectivity being planned for 5G will play an important role.

Figure 55 shows another simulation study, this one from Intel, using the following assumptions: 28 GHz operation, 2:1 DL:UL ratio, 25% control overhead, 10 bps/Hz maximum downlink spectral efficiency, CPEs placed either north or south side of house and one with best SNR chosen, and indoor CPE equipment with 30dB outdoor-to-indoor penetration loss. Scenario 1 is 60 access points per sq. km. Scenario 2 is 120 access points per sq. km. (Base grid of 40 houses in a 250x200m area with four rows of 10 houses per row, APs placed along streets and alleys, single-family homes, 4 sectors per AP, and 4.5-meter pole height.)

Figure 55: 5G Fixed Wireless Simulation with Different Loading and Densities[131]



DL	Scenario 1 (3 APs per 40 homes)				Scenario 2 (6 APs per 40 homes)			
	10% loading		50% loading		10% loading		50% loading	
	Cell-edge (Mbps)	Average (Mbps)	Cell-edge (Mbps)	Average (Mbps)	Cell-edge (Mbps)	Average (Mbps)	Cell-edge (Mbps)	Average (Mbps)
100 MHz, 64x8	5	200	4	160	50	290	45	230
100 MHz, 128x16	22	280	20	210	150	370	145	275
400 MHz, 128x16	88	1,120	80	840	600	1,480	580	1,100

UL	Scenario 1 (3 APs per 40 homes)				Scenario 2 (6 APs per 40 homes)			
	10% loading		50% loading		10% loading		50% loading	
	Cell-edge (Mbps)	Average (Mbps)	Cell-edge (Mbps)	Average (Mbps)	Cell-edge (Mbps)	Average (Mbps)	Cell-edge (Mbps)	Average (Mbps)
100MHz, 16x64	2	85	1	75	35	120	30	100
100MHz, 16x128	4	95	2	80	50	140	40	110
100MHz, 32x64	7	100	4	85	70	150	60	115

Using 400 MHz and six access points per 40 homes, and 50% loading, the average throughput was more than 1 Gbps.

LTE and LTE-Advanced

Although HSPA and HSPA+ offer a highly efficient broadband-wireless service that will enjoy success for the remainder of this decade and well into the next, 3GPP completed the specification for Long Term Evolution as part of Release 8. LTE offers even higher peak throughputs in wider spectrum bandwidth. Work on LTE began in 2004 with an official work item started in 2006 and a completed specification early 2009. Initial deployments began in 2010.

LTE uses OFDMA on the downlink, which is well suited to achieve high peak data rates in high-spectrum bandwidth. WCDMA radio technology is basically as efficient as OFDM for delivering peak data rates of about 10 Mbps in 5 MHz of bandwidth. Achieving peak rates in the 100 Mbps range with wider radio channels, however, would result in highly complex terminals, and it is not practical with current technology, whereas OFDM provides a practical implementation advantage. Scheduling approaches in the frequency domain can also minimize interference, thereby boosting spectral efficiency. The OFDMA approach is also flexible in channelization: LTE operates in various radio channel sizes ranging from 1.4 to 20 MHz.

---

[131] Intel contribution.

On the uplink, however, a pure OFDMA approach results in high Peak to Average Ratio (PAR) of the signal, which compromises power efficiency and, ultimately, battery life. Hence, LTE uses an approach called “SC-FDMA,” which is somewhat similar to OFDMA, but has a 2 to 6 dB PAR advantage over the OFDMA method used by other technologies such as WiMAX.

LTE capabilities include:

- Downlink peak data rates up to 300 Mbps with 20+20 MHz bandwidth in initial versions, increasing to over 1 Gbps in subsequent versions through carrier aggregation, higher-order modulation, and 4X4 MIMO.
- Uplink peak data rates up to 71 Mbps with 20+20 MHz bandwidth in initial versions, increasing to over 1 Gbps in subsequent versions.
- Operation in both TDD and FDD modes.
- Scalable bandwidth up to 20+20 MHz covering 1.4, 3, 5, 10, 15, and 20 MHz radio carriers.
- Increased spectral efficiency over HSPA by a factor of two to four.
- Reduced latency, to 15 msec round-trip times between user equipment and the base station, and to less than 100 msec transition times from inactive to active.
- Self-organizing capabilities under operator control and preferences that will automate network planning and will result in lower operator costs.

LTE-Advanced Terminology

LTE-Advanced, as specified in Release 10, is a term used for the version of LTE that addresses IMT-Advanced requirements. The ITU ratified LTE-Advanced as IMT-Advanced in November 2010. LTE-Advanced is both backward- and forward-compatible with LTE, meaning LTE devices operate in newer LTE-Advanced networks, and LTE-Advanced devices operate in older, pre-Release 10 LTE networks.

The following lists at a high level the most important features of LTE-Advanced, as well as other features planned for subsequent releases, including Release 11:

- Carrier aggregation.
- Higher-order downlink MIMO (up to 8X8 in Release 10).
- Uplink MIMO (two transmit antennas in the device).
- Coordinated multipoint transmission (CoMP) in Release 11.
- Heterogeneous network (HetNet) support including Enhanced Inter-cell Interference Coordination (eICIC).
- Relays.

3GPP, from Release 13, has referred to LTE as LTE-Advanced Pro, which includes features such as LAA, LWA, low latency, and massive MIMO.

OFDMA and Scheduling

LTE implements OFDM in the downlink. The basic principle of OFDM is to split a high-rate data stream into a number of parallel, low-rate data streams, each a narrowband signal carried by a subcarrier. The different narrowband streams are generated in the frequency domain, and then combined to form the broadband stream using a mathematical algorithm called an "Inverse Fast Fourier Transform" (IFFT) that is implemented in digital signal processors. In LTE, the subcarriers have 15 kHz spacing from each other. LTE maintains this spacing regardless of the overall channel bandwidth, which simplifies radio design, especially in supporting radio channels of different widths. The number of subcarriers ranges from 72 in a 1.4 MHz radio channel to 1,200 in a 20 MHz radio channel.

The composite signal obtained after the IFFT is extended by repeating the initial part of the signal (called the Cyclic Prefix [CP]). This extended signal represents an OFDM symbol. The CP is basically a guard time during which reflected signals will reach the receiver. It results in an almost complete elimination of multipath-induced Intersymbol Interference (ISI), which otherwise makes extremely high data rate transmissions problematic. The system is called orthogonal because the subcarriers are generated in the frequency domain (making them inherently orthogonal), and the IFFT conserves that characteristic.

OFDM systems may lose their orthogonal nature as a result of the Doppler shift induced by the speed of the transmitter or the receiver. 3GPP specifically selected the subcarrier spacing of 15 kHz to avoid any performance degradation in high-speed conditions. WiMAX systems that use a lower subcarrier spacing (~11 kHz) are more impacted in high-speed conditions than LTE.

Figure 56: OFDM Symbol with Cyclic Prefix



The multiple access aspect of OFDMA comes from being able to assign different users different subcarriers over time. A minimum resource block that the system can assign to a user transmission consists of 12 subcarriers over 14 symbols in 1.0 msec. Figure 57 shows how the system can assign these resource blocks to different users over both time and frequency.

Figure 57: LTE OFDMA Downlink Resource Assignment in Time and Frequency


Frequency
Time
User 1
User 2
User 3
User 4
Minimum resource block consists of 14 symbols and 12 subcarriers
Rysavy Research

By controlling which subcarriers are assigned in which sectors, LTE can easily control frequency reuse. Using all the subcarriers in each sector, the system would operate at a frequency reuse of 1; but by using a different one third of the subcarriers in each sector, the system can achieve a looser frequency reuse of 1/3. The looser frequency reduces overall spectral efficiency but delivers high peak rates to users.

Beyond controlling frequency reuse, frequency domain scheduling, as shown in Figure 58 can use those resource blocks that are not faded, not possible in CDMA-based systems. Since different frequencies may fade differently for different users, the system can allocate those frequencies for each user that result in the greatest throughput. This results in up to a 40% gain in average cell throughput for low user speed (3 km/hour), assuming a large number of users and no MIMO. The benefit decreases at higher user speeds.

Figure 58: Frequency Domain Scheduling in LTE[132]



LTE Smart Antennas

Wireless networks can achieve significant gains by employing multiple antennas, either at the base station, the mobile device, or both. LTE uses multiple antennas in three fundamentally different ways:

- **Diversity.** So long as the antennas are spaced or polarized appropriately, the antennas provide protection against fading.
- **Beamforming.** Multiple antennas can shape a beam to increase the gain for a specific receiver. Beamforming can also suppress specific interfering signals. Beamforming is particularly helpful for improving cell-edge performance.
- **Spatial Multiplexing.** Often referred to as MIMO antenna processing, spatial multiplexing creates multiple transmission paths through the environment, effectively sending data in parallel through these paths, thus increasing both throughput and spectral efficiency.

Table 18 shows the varous antenna transmission modes.

---

[132] 5G Americas member contribution.

Table 18: LTE Transmission Modes[133]

Transmission Mode	Description
1	Single antenna transmission.
2	Transmit Diversity.
3	Transmit diversity for one layer, open-loop codebook-based precoding if more than one layer.
4	Closed-loop codebook-based precoding.
5	Multi-user MIMO version of transmission mode 4.
6	Special case of closed-loop codebook-based precoding limited to single layer transmission.
7	Beamforming. (Non-codebook-based precoding supporting one layer.)
8	Dual-layer beamforming. (Release 9. Non-codebook-based precoding supporting up to two layers.)
9	8-layer transmission. (Release 10. Non-codebook-based precoding supporting up to eight layers.)
10	8-layer transmission with support for CoMP. (Release 11.)

Being able to exploit different antenna modes based on local conditions produces huge efficiency and performance gains, and is the reason that 3GPP is developing even more advanced antenna modes in subsequent LTE releases.

Precoding refers to a mathematical matrix operation performed on radio symbols to determine how they are combined and mapped onto antenna ports. The precoder matrix can operate in either open-loop or closed-loop modes. For each transmission rank for a given number of transmission ports (antennas), there is a limited set of precoder matrices defined, called the codebook. This helps limit the amount of signaling needed on uplink and downlink.

Fundamental variables distinguish the different antenna modes:

- **Single base station antenna versus multiple antennas.** Single antennas provide for Single Input Single Output (SISO), SIMO, and planar-array beamforming. (Multiple Output means the UE has multiple antennas.) Multiple antennas at the base station provide for different MIMO modes such as 2X2, 4X2, and 4X4.

---

[133] Erik Dahlman, Stefan Parkvall, Johan Skold, *4G - LTE/LTE Advanced for Mobile Broadband*, Academic Press, 2011.

- **Single-user MIMO versus multi-user MIMO.** Release 8 only provides for single-user MIMO on the downlink. Release 10 includes multi-user MIMO.
- **Open-Loop versus Closed-Loop.** High vehicular speeds require open-loop operation whereas slow speeds enabled closed-loop operation in which feedback from the UE modifies the transmission. In closed-loop operation, the precoder matrix is based on this feedback.
- **Rank.** In a MIMO system, the channel rank is formally defined as the rank of the channel matrix and is a measure of the degree of scattering that the channel exhibits. For example, in a 2x2 MIMO system, a rank of one indicates a low-scattering environment, while a rank of two indicates a high-scattering environment. The rank two channel is highly uncorrelated, and is thus able to support the spatial multiplexing of two data streams, while a rank one channel is highly correlated, and thus can only support single stream transmission (the resulting multi-stream interference in a rank one channel as seen at the receiver would lead to degraded performance). Higher Signal to Interference plus Noise Ratios (SINR) are typically required to support spatial multiplexing, while lower SINRs are typically sufficient for single stream transmission. In a 4x4 MIMO system channel rank values of three and four are possible in addition to values of one and two. The number of data streams, however, or more specifically codewords in LTE is limited to a value of two. Thus, LTE has defined the concept of layers, in which the DL transmitter includes a codeword-to-layer mapping, and in which the number of layers is equal to the channel rank. An antenna mapping or precoding operation follows, which maps the layers to the antenna ports. A 4x2 MIMO system is also possible with LTE Release 8, but here the channel rank is limited to the number of UE antennas, which is equal to two.

The network can dynamically choose between different modes based on instantaneous radio conditions between the base station and the UE. Figure 59 shows the decision tree. The antenna configuration (AC) values refer to the transmission modes. Not every network will support every mode. Operators will choose which modes are the most effective and economical. AC2, 3, 4, and 6 are typical modes that will be implemented.

Figure 59: Decision Tree for Different Antenna Schemes[134]


Decision Tree
SISO, SIMO or Linear Array Beam Forming / Space Division Multiple Access
2x2, 4x2 or 4x4 Diversity Array
AC = Antenna Configuration
CL = Closed Loop
CQI = Channel Quality Indication
MIMO= Multiple Input Multiple Output
OL = Open Loop
PMI = Pre-coding Matrix Indication
RI = Rank Indication
RS = Reference Symbol
SM = Spatial Multiplexing
TD = Transmit Diversity
Single Antenna or Array Array
Multi-User MIMO (AC5) Adapts to OL TD
MIMO
Indicates Dynamic Adaptation
SISO or SIMO
Planar Array Beamforming
Mainly high vehicular speed
Significant low & pedestrian speed traffic
Open Loop Rank Indication (RI), Channel Quality Indication (CQI), no Precoding Matrix Indicaiton (PMI)
Closed Loop Rank Indication (RI), Channel Quality Indication (CQI), with Precoding Matrix Indicaiton (PMI)
Low SINR or low scattering
High SINR & Rich Scattering
Low SINR or low scattering
High SINR & Rich Scattering
Single Stream Rank 1
Multi-Stream Rank 2-4
Single Stream Rank 1
Multi-Stream Rank 2-4
Port 0 Common Ref. Sig. (RS) (AC1)
Port 5 Dedicated RS (AC7) Adapts to Common RS & OL TD
Transmit Diversity (AC2)
Open Loop Spatial Mult'xng (AC3) Adapts to OL TD
Closed Loop Precoding (AC6) Adapts to OL TD
Closed Loop Spatial Mult'xng* (AC4) Adapts to CL R=1 and OL TD
* Likely configuration for majority of initial deployments

The simplest mode is AC2, referred to as Transmit Diversity (TD) or sometimes Space Frequency Block Code (SFBC) or even Open Loop Transmit Diversity. TD can operate under all conditions, meaning it works under low SINR, high mobility, and low channel rank (rank = 1). This rank means that the channel is not sufficiently scattered or de-correlated to support two spatial streams. Thus, in TD, only one spatial stream or what is sometimes referred as a single codeword (SCW) is transmitted. If the channel rank increases to a value of two, indicating a more scattered channel, and the SINR is a bit higher, then the system can adapt to AC3 or Open-Loop Spatial Multiplexing (OL-SM), also referred to as large-delay Cyclic Delay Diversity (CDD). This mode supports two spatial streams or two codewords. This mode, also called multiple codeword (MCW) operation, increases throughput over SCW transmission.

If the rank of the channel is one, but the device is not moving very fast or is stationary, then the system can adapt to AC6, called closed-loop (CL) precoding (or CL-rank 1 or CL-R1). In this mode, the network receives from the device with Precoding Matrix Indication (PMI) bits that inform the base station what precoding matrix to use in the transmitter to optimize link performance. This feedback is only relevant for low-mobility or stationary conditions since in high mobility conditions the feedback will most likely be outdated by the time the base station can use it.

Another mode is AC4 or Closed Loop Spatial Multiplexing (CL-SM), which is enabled for low-mobility, high SINR, and channel rank of two. This mode theoretically provides the best user throughput. The figure above shows how these modes can adapt downwards to either OL TD, or if in CL-SM mode, down to either OL TD or CL R1.

---

[134] 4G Americas *MIMO and Smart Antennas for 3G and 4G Wireless Systems – Practical Aspects and Deployment Considerations*, May 2010.

For a 4x4 MIMO configuration, the channel rank can take on values of three and four in addition to one or two. Initial deployment at the base station, however, will likely be two TX antennas and most devices will only have 2 RX antennas, and thus the rank is limited to 2.

AC5 is MU-MIMO, which is not defined for the downlink in Release 8.

AC1 and AC7 are single antenna port modes in which AC1 uses a common Reference Signal (RS), while AC7 uses a dedicated RS or what is also called a user specific RS. AC1 implies a single TX antenna at the base station. AC7 implies an antenna array with antennal elements closely spaced so that a physical or spatial beam can be formed toward an intended user.

LTE operates in a variety of MIMO configurations. On the downlink, these include 2X2, 4X2 (four antennas at the base station), and 4X4. Initial deployment will likely be 2x2 whereas 4X4 will be most likely used initially in femtocells. On the uplink, there are two possible approaches: single-user MIMO (SU-MIMO) and multi-user MIMO (MU-MIMO). SU-MIMO is more complex to implement as it requires two parallel radio transmit chains in the mobile device, whereas MU-MIMO does not require any additional implementation at the device but relies on simultaneous transmission on the same tones from multiple mobile devices.

The first LTE Release thus incorporates MU-MIMO with SU-MIMO deferred for subsequent LTE releases. An alternate form of MIMO, originally called network MIMO, and now called CoMP, relies on MIMO implemented (on either the downlink or uplink or both) using antennas across multiple base stations, as opposed to multiple antennas at the same base station. This paper explains CoMP in the section on LTE Advanced below.

Peak data rates are approximately proportional to the number of send and receive antennas. 4X4 MIMO is thus theoretically capable of twice the data rate of a 2X2 MIMO system. The spatial multiplexing MIMO modes that support the highest throughput rates will be available in early deployments.

For a more detailed discussion of 3GPP antenna technologies, refer to the 5G Americas white paper “MIMO and Smart Antennas for 3G and 4G Wireless Systems – Practical Aspects and Deployment Considerations,” May 2010.

For advancements in LTE Smart Antennas, see the next section.

LTE-Advanced Antenna Technologies

Release 10 added significant enhancements to antenna capabilities, including four-layer transmission resulting in peak spectral efficiency exceeding 15 bps/Hz. Uplink techniques fall into two categories: those relying on channel reciprocity and those that do not. With channel reciprocity, the eNB determines the channel state by processing a Sounding Reference Signal from the UE. It then forms transmission beams accordingly. The assumption is that the channel received by the eNB is the same as the UE. Techniques that use channel reciprocity are beamforming, SU-MIMO, and MU-MIMO. Channel reciprocity works especially well with TDD since both forward and reverse links use the same frequency.

Non-reciprocity approaches apply when the transmitter has no knowledge of the channel state. Techniques in this instance include open-loop MIMO, closed-loop MIMO, and MU-MIMO. These techniques are more applicable for higher speed mobile communications.

For the downlink, the technology can transmit in as many as eight layers using an 8X8 configuration for a peak spectral efficiency of 30 bps/Hz. This exceeds the IMT-Advanced requirements, conceivably supporting a peak rate of 1 Gbps in just 40+40 MHz, and even higher rates in wider bandwidths. This would require additional reference signals for channel estimation and for measurements, including channel quality, to enable adaptive, multi-antenna transmission.

Release 10 supports a maximum of two codewords, the same as previous LTE releases. The release specifies a new transmission mode (TM-9) that supports SU-MIMO up to Rank 8 (up to eight layers), as well as the ability to dynamically switch between SU-MIMO and MU-MIMO.

Figure 60 shows the different forms of single-user MIMO in Releases 8, 9, and 10. Release 8 supports only a single layer, whereas two-layer beamforming is possible in Release 9, and eight layers are possible in Release 10 with eight antennas at the base station.

Figure 60: Single-User MIMO[135]


1 layer BF in Rel-8 with 4 antennas
2 layer BF in Rel-9 with 8 antennas
8 layer BF in Rel-10 with 8 antennas

Figure 61 shows multi-user MIMO options across different releases. Release 8 supports two simultaneous users, each with one layer using four antennas, while Releases 9 and 10 support four simultaneous users, each with one layer.

Figure 61: Multi-User MIMO[136]


2 users each with 1 layer in Rel-8 with 4 antennas
4 users each with 1 layer in Rel-9/10 with 8 antennas

For four-antenna configurations at the base station, Release 12 improves throughput by adding a feedback mode, called mode 3-2, in which sub-band precoders and sub-band channel quality indicators (CQIs) are included in the UE's feedback to the eNodeB. Release 12 also adds a new codebook that further improves throughput.

---

[135] 5G Americas member contribution.

[136] 5G Americas member contribution.

As depicted in Figure 62 and Figure 63, compared with the Release 8 codebook, the new Release 12 codebook provides a 10% gain for both median and cell-edge throughputs. Compared with feedback mode 3-1, feedback mode 3-2 provides an 18% to 20% gain in median and cell-edge throughput. Jointly, the two methods provide a 28% to 30% gain.

Figure 62: Median Throughput of Feedback Mode 3-2 and New Codebook.[137]



Figure 63: Cell-Edge Throughput of Feedback Mode 3-2 and New Codebook[138]



Release 12 also defines how Active Antenna Systems can use multiple transceivers on an antenna array to dynamically adjust a radiation pattern.

---

[137] 5G Americas member contribution. Assumptions include: cellular layout of 19 sites hexagonal grid with three sectors per site and 500-meter inter-site distance; simulation case ITU uMa for macro; carrier frequency 2 GHz, deployment scenario A homogenous macro; SU-MIMO with maximum two layers per UE; proportional fair scheduler; and bursty traffic model.

[138] 5G Americas member contribution. Same assumptions as previous figure.

Release 13 is likely to define full-dimension MIMO, which adds a large number of antenna elements, potentially as many as 64 elements.

A practical consideration with antennas is that many towers today already support multiple operators, with tower companies having to manage interference placement, spectrum allocations, and wind and snow load. At higher frequencies, a single radome (antenna enclosure) can support 4X2 MIMO, but higher-order MIMO may prove impractical for many deployments.

5G systems operating at much higher frequencies will have an advantage since the antenna arrays will be much smaller due to the much smaller wavelengths.

Initial massive MIMO techniques applied to LTE, such as full-dimension MIMO using 8, 16, and 64 transmit antennas, can provide dramatic performance gains, particularly in dense deployments, as shown in Figure 64.

Figure 64: Performance Gains with FD-MIMO Using 200 Meter ISD[139]



This figure compares 8X2, 16X2, and 64X2 MIMO performance relative to 2X2 MIMO (normalized to value 100). The blue bars (case 1) show the supported number of users per sector (referred to as “cell” in the figure) at a fixed resource utilization (RU) of 70%; the green bars (case 2) show mean user throughput (UPT) at a fixed RU of 70%; and the red bars (case 3) show system capacity in terms of supported number of users for a given user throughput. Resulting gains are:

---

[139] 5G Americas member contribution.

- ❑ Case 2 (green bars): 1.5X with 8X2, 1.75X with 16X2, and 2X with 64X2 MIMO.
- ❑ Case 3 (red bars): 2X with 8X2, 2.5X with 16X2, and 3X with 64X2 MIMO.

The primary gains are from azimuth (horizontal dimension) in going from 2X2 to 8X2, and from elevation in going to 16X2 and 64X2. FD-MIMO gains are lower with larger ISD values, such as 500 meters.

3GPP has also studied FD-MIMO and conducted a field trial showing impressive throughput gains, particularly in a high-rise scenario.[140]

Carrier Aggregation

Carrier aggregation, first available in Release 10, plays an important role in providing operators maximum flexibility for using all of their available spectrum. By combining spectrum blocks, LTE can deliver much higher throughputs than otherwise possible. Asymmetric aggregation (for example, different amounts of spectrum used on the downlink versus the uplink) provides further flexibility and addresses the greater demand on downlink traffic.

Specific types of aggregation include:

- ❑ Intra-band on adjacent channels.
- ❑ Intra-band on non-adjacent channels.
- ❑ Inter-band (700 MHz, 1.9 GHz).
- ❑ Inter-technology (for example, LTE on one channel, HSPA+ on another). This approach is not currently specified nor being developed. While theoretically promising, a considerable number of technical issues would have to be addressed.[141] See Figure 65.

---

[140] 3GPP, *3D-MIMO Prototyping and Initial Field Trial Results*, TSG RAN WG1 Meeting #80, Agenda Item: 7.2.4.4, Document R1-150451.

[141] For further details, see 4G Americas, *HSPA+ LTE Carrier Aggregation*, June 2012.

Figure 65: Inter-Technology Carrier Aggregation[142]


HSPA UE
HSPA+ NB
Iub
RNC
Iu
LTE+HSPA
Core Network
split
S1
LTE UE
LTE eNB
New HSPA+LTE interface
Data flow to HSPA+LTE UE

Figure 66 depicts the carrier-aggregation capabilities of different 3GPP releases.

---

[142] 5G Americas member contribution.

Figure 66: Carrier Aggregation Capabilities across 3GPP Releases[143]


3GPP Release 10
DL Intra-Band Contiguous
DL Inter-Band
Maximum 2 DL Carrier Aggregation
3GPP Release 11
DL Intra-band non contiguous
3GPP Release 12
3 Downlink CA
Two Uplink CA (Inter-Band & Intra-Band Non Contiguous)
FDD + TDD
Dual Connectivity
Beyond Release12
LAA (Licensed-Assisted Access)
Four Downlink CA

One anticipated benefit of inter-band aggregation stems from using the lower-frequency band for users who are at the cell edge, to boost their throughput rates. Though this approach improves average aggregate throughput of the cell by only a small amount (say, 10%), it results in a more uniform user experience across the cell coverage area.

Figure 67 shows an example of intra-band carrier aggregation using adjacent channels with up to 100+100 MHz of bandwidth supported. Radio-access network specifications, however, limit the number of carriers to two in Release 10 and Release 11.

Figure 67: Release 10 LTE-Advanced Carrier Aggregation[144]


Release 10 LTE-Advanced UE resource pool
Rel'8
Rel'8
Rel'8
Rel'8
Rel'8
100 MHz bandwidth
20 MHz
Release 8 UE uses a single 20 MHz block

---

[143] 4G Americas, *Mobile Broadband Evolution: Rel-12 & Rel-13 and Beyond*, 2015.

[144] Harri Holma and Antti Toskala, *LTE for UMTS, OFDMA and SC-FDMA Based Radio Access*, Wiley, 2009.

Figure 68 shows the carrier aggregation operating at different protocol layers.

Figure 68: Carrier Aggregation at Different Protocol Layers[145]



For a list of band combinations, refer to the 5G Americas white paper, *Wireless Technology Evolution Towards 5G: 3GPP Release 13 to Release 15 and Beyond,* February 2017, at section 3.4.3.

Figure 69 shows the result of one simulation study that compares download throughput rates between the blue line, which shows five user devices in 700 MHz and five user devices in AWS not using CA, and the pink line, which shows ten user devices that have access to both bands. Assuming a lightly loaded network with CA, 50% or more users (the median) experience 91% greater throughput, and 95% or more users experience 50% greater throughput. These trunking gains are less pronounced in heavily loaded networks.

---

[145] Stefan Parkvall and David Astely, Ericsson Research, "The Evolution of LTE towards IMT-Advanced," Journal of Communications, Vol. 4, No. 3, April 2009. Available at http://www.academypublisher.com/jcm/vol04/no03/jcm0403146154.pdf.

Figure 69: Gains from Carrier Aggregation[146]



Work in Release 12 is investigating aggregation of joint TDD and FDD carriers.

Coordinated Multi Point (CoMP)

Coordinated Multi Point (CoMP) is a communications technique that can improve coverage, cell-edge throughput, and/or system spectrum efficiency by reducing interference. This technique was thoroughly studied during the development of LTE-Advanced Release 10 and was standardized in Release 11.

CoMP coordinates transmissions at different cell sites, thereby achieving higher system capacity and improving cell-edge data rates.

The main principle of CoMP is that a UE at a cell edge location can receive signals from multiple transmission points, and/or its transmitted signal can be received by multiple reception points. Consequently, if these multiple transmission points coordinate their transmissions, the DL throughput performance and coverage can improve.

For the UL, signals from the UE received at multiple reception points can significantly improve the link performance. Techniques can range from simple interference avoidance methods, such as Coordinated Beam Switching (CBS) and Coordinated Beam Forming

---

[146] 5G Americas member contribution. Assumptions: lightly-loaded network, 2.0 site-to-site distance, file size is 750 Kbytes, traffic model bursty with mean inter-arrival time of five seconds.

(CBF), to complex joint processing techniques that include Joint Transmission (JT), Joint Reception (JR), and Dynamic Point Selection (DPS).

CoMP architectures include inter-site CoMP, intra-site CoMP, as well as CoMP with distributed eNBs (i.e., an eNB with distributed remote radio heads). Figure 70 shows two possible levels of coordination.

Figure 70: Different Coordination Levels for CoMP[147]


1. Intra-site Macro CoMP
eNB
1. Coordination is only between sectors of the same macro BTS
2. Distributed eNB – Contiguous Coverage
High Tx power RRH
2. Coordination between all sectors of all macro BTSs

In one CoMP approach, called coordinated scheduling and shown in Figure 71, a single site transmits to the user, but with scheduling, including any associated beamforming, coordinated between the cells to reduce interference between the different cells and to increase the served user's signal strength. In Joint Transmission, another CoMP approach also shown in Figure 71, multiple sites transmit simultaneously to a single-user. This approach can achieve higher performance than coordinated scheduling, but it has more stringent backhaul communications requirements. One simpler form of CoMP that will be available in Release 10, and then further developed in Release 11, is ICIC. Release 11 of LTE defines a common feedback and signaling framework for enhanced CoMP operation.

Figure 71: Coordinated Scheduling / BF and Joint Processing CoMP Approaches[148]


Coordinated Scheduling/BF
&
Joint Processing

---

[147] 5G Americas member contribution.

[148] 5G Americas member contribution.

Release 11 also implements CoMP on the uplink, by which multiple base stations receive uplink transmissions and jointly process the signal, resulting in significant interference cancellation and improvements to spectral efficiency.

The performance gains expected from CoMP are under discussion in the industry. According to 3GPP document TR 36.819, for the case of resource utilization below 35%, CoMP may provide a 5.8% performance gain on the downlink for the mean user and a 17% gain for cell-edge users relative to HetNets without eICIC. For resource utilization of more than 35%, CoMP may provide a 17% mean gain and a 40% cell-edge gain.[149] CoMP can also be used in combination with eICIC for additional gains.

In the same 3GPP TR 36.819 document, 3GPP estimates the downlink CoMP gain in spectral efficiency, defined as average sector throughput for full buffer traffic using JT and 4x2 MU-MIMO as defined in R11, compared with 4x2 MU-MIMO based on R10, to be about 3% for intra-eNodeB CoMP. That gain drops to about 9% for inter-eNodeB CoMP in the case of no delay in the backhaul used to exchange information between eNodeBs. The corresponding gains in cell-edge user throughput are 20% and 31%, respectively.

When increasing the backhaul latency to a more realistic value of 10 msec for inter-eNodeB, spectral efficiency decreases to zero, and the cell edge gain decreases to 10%.

The gains for DL CoMP based on Coordinated Scheduling/Coordinated Beamforming (CS/CB) and intra-eNodeB are less than that provided by JT, with spectral efficiency at 1% and cell edge gains at 4%.

All of the above gains are for FDD networks with cross-polarized antennas at the eNodeBs. For TDD networks, the gains are higher by virtue of being able to invoke channel reciprocity and thus infer the DL channel directly from the UL channel. For example, for intra-eNodeB CoMP with JT 4x2 MU-MIMO, the respective gains in spectral efficiency and cell-edge throughput are 14% and 29%, respectively.

The gains for UL CoMP based on Joint Reception (JR) are greater than the DL gains. For intra-eNodeB CoMP, the average and cell-edge throughputs are increased to 22% and 40%, assuming two receive antenna paths with SU-MIMO. These respective gains increase to 31% and 66% for inter-eNodeB CoMP. In addition, UL CoMP does not require standardization and thus facilitates vendor implementation.

Uplink CoMP assists VoLTE because it improves cell-edge performance, making voice handover more reliable when traversing between cells. The benefit is analogous to CDMA soft handover; in both cases, the mobile device communicates with two sites simultaneously.

Cellular V2X Communications

In Release 14, 3GPP is specifying cellular vehicle-to-X (C-V2X) communications with two complementary transmission modes: direct communications between vehicles and network communications.

Direct communications will use bands such as the Intelligent Transportation Systems (ITS) 5.9 GHz band, using the PC5 interface specified for LTE device-to-device communications, and will not require a Universal Integrated Circuit Card (UICC) SIM (USIM) card. By operating on different channels in the ITS band, direct cellular V2X will be able to co-exist with IEEE 802.11p, another automotive communications protocol.

---

[149] 3GPP, *Coordinated Multi-Point Operation for LTE Physical Layer Aspects, TR 36.819 v11.1.0,* Tables 7.3.1.2-3 and 7.3.1.2-4, September 2011.

In the network communications mode, the system will use traditional cellular licensed spectrum.

Use cases include do-not-pass warnings, blind-curve hazard warnings, road-works warnings, blind-intersection assistance, bicyclist and pedestrian alerts, and left-turn assistance.

C-V2X is being designed to be compatible with other automotive standards, such as those from ETSI and the Society of Automotive Engineers.

User-Plane Congestion Management (UPCON)

With User-Plane Congestion Management, specified in Release 13, operators have additional tools to mitigate network congestion in specific coverage areas. Mechanisms include traffic prioritization by adjusting QoS for specific services; reducing traffic by, for example, compression; and limiting traffic, such as by prohibiting or deferring certain traffic.

3GPP specifications add a new architectural entity, called the “RAN Congestion Awareness Function” (RCAF), that determines whether a cell is congested, determines the UEs supported by that cell, and informs the Policy Control and Charging Rules Function (PCRF), which can subsequently apply different policies to mitigate the congestion.[150]

Network-Assisted Interference Cancellation and Suppression (NAICS)

NAICS, a Release 13 capability, enhances the interference cancellation and suppression capability of UEs by using more information from the network. The fundamental goal of NAICS is to identify and cancel the dominant interferer, not an easy task when the dominant interferer can be on or off and can change in time and frequency. One analysis estimates an average performance gain of 7.4% relative to Release 11 Interference Rejection Combining and 11.7% at the cell edge.[151] 5G Americas members expect even higher performance gains, for example 20%, with implementation-specific scheduling and as NAICS methods are refined.

Multi-User Superposition Transmission (MUST)

MUST, a study item in Release 13 and tentatively planned for Release 14 uses simultaneous transmissions of data for more than one UE within a cell without time, frequency, or spatial layer separation. The concept relies on a UE close to the base station having low propagation loss and a UE far from the base station having high propagation loss. The far UE is not aware of, nor interfered by the near UE transmission. The near UE cancels the far UE interference. The capacity gain grows with the SNR/SINR difference between the close and far UEs.

---

[150] For further details, see 3GPP TR 23.705, “Study on system enhancements for user plane congestion management (Release 13).”

[151] Harri Holma, Antti Toskala, Jussi Reunanen, *LTE Small Cell Optimization: 3GPP Evolution to Release 13*, Jan 2016, Wiley, ISBN: 978-1-118-91257-7.

IPv4/IPv6

Release 8 defines support for IPv6 for both LTE and UMTS networks. An Evolved Packet System bearer can carry both IPv4 and IPv6 traffic, enabling a UE to communicate both IPv4 and IPv6 packets (assuming it has a dual stack) while connected through a single EPS bearer. It is up to the operator, however, whether to assign IPv4, IPv6, or both types of addresses to UE.

Communicating between IPv6-only devices and IPv4 endpoints will require protocol-conversion or proxies. For further details, refer to the 5G Americas white paper, "IPv6 – Transition Considerations for LTE and Evolved Packet Core," February 2009.

TDD Harmonization

3GPP developed LTE TDD to be fully harmonized with LTE FDD including alignment of frame structures, identical symbol-level numerology, the possibility of using similar Reference Signal patterns, and similar synchronization and control channels. Also, there is only one TDD variant. Furthermore, LTE TDD has been designed to co-exist with TD-SCDMA and TD-CDMA/UTRA (both low-chip rate and high-chip rate versions). LTE TDD achieves compatibility and co-existence with TD-SCDMA by defining frame structures in which the DL and UL time periods can be time aligned to prevent BTS to BTS and UE to UE interference to support operation in adjacent carriers without the need for large guardbands between the technologies. This will simplify deployment of LTE TDD in countries such as China that are deploying TD-SCDMA. Figure 72 demonstrates the synchronization between TC-SCDMA and LTE-TDD in adjacent channels.

Figure 72: TDD Frame Co-Existence between TD-SCDMA and LTE TDD[152]


TD-SCDMA
LTE TDD
5ms LCR TDD frame
frame offset
5ms LTE TDD frame
DL portion (d symbols)
UL portion (u symbols)
Transmission gap / idle period

For LTE FDD and TDD to co-exist, large guardbands will be needed to prevent interference.

SMS in LTE

Even if an LTE network uses CSFB for voice, LTE devices will be able to send and receive SMS messages while on the LTE network. In this case, the 2G/3G core network will handle SMS messaging, but will tunnel the message to the MME in the EPC via the SGs interface. Once an LTE network uses IMS and VoLTE for packet voice service, SMS will be handled as SMS over IP and will use IMS infrastructure.[153]

User Equipment Categories

LTE specifications define categories of UE, which mainly determine the maximum throughputs of devices but also govern the number of downlink MIMO layers, as shown in Table .

Higher throughput capabilities are possible with 64 QAM and 256 QAM modulation. 3GPP is also defining Category 0 and Category M devices for M2M, as discussed in the section “Internet of Things and Machine-to-Machines.”

---

[152] 5G Americas member company contribution.

[153] For further details, see 4G Americas, *Coexistence of GSM, HSPA and LTE*, May 2011, 35.

Table 19: UE Categories[154]

UE Category	Max DL Throughput	Maximum DL MIMO Layers	Maximum UL Throughput
1	10.3 Mbps	1	5.2 Mbps
2	51.0 Mbps	2	25.5 Mbps
3	102.0 Mbps	2	51.0 Mbps
4	150.8 Mbps	2	51.0 Mbps
5	299.6 Mbps	4	75.4 Mbps
6	301.5 Mbps	2 or 4	51.0 Mbps
7	301.5 Mbps	2 or 4	102.0 Mbps
8	2998.6 Mbps	8	1497.8 Mbps
9	452.3 Mbps	2 or 4	51.0 Mbps
10	452.3 Mbps	2 or 4	102.0 Mbps
11	603.0 Mbps	2 or 4	51.0 Mbps
12	603.0 Mbps	2 or 4	102.0 Mbps
13	391.6 Mbps	2 or 4	150.8 Mbps
14	3916.6 Mbps	8	9587.7 Mbps
15	798.8 Mbps	2 or 4	226.1 Mbps
16	1051.4 Mbps	2 or 4	105.5 Mbps
17	2506.6 Mbps	8	2119.4 Mbps
18	1206.0 Mbps	2 or 4 (or 8)	211.0 Mbps
19	1658.3 Mbps	2 or 4 (or 8)	13563.9 Mbps

LTE-Advanced Relays

Another capability being planned for LTE-Advanced is relays, as shown in Figure 73. The idea is to relay frames at an intermediate node, resulting in much better in-building penetration, and with better signal quality, user rates will improve. Relay nodes can also improve cell-edge performance by making it easier to add picocells at strategic locations.

---

[154] 3GPP, *Evolved Universal Terrestrial Radio Access (E-UTRA); User Equipment (UE) radio access capabilities,* Technical Specification 36.306 V14.2.0, March 2017.

Relays provide a means for lowering deployment costs in initial deployments in which usage is relatively low. As usage increases and spectrum needs to be allocated to access only, operators can then employ alternate backhaul schemes.

Figure 73: LTE-Advanced Relay[155]



Proximity Services (Device-to-Device)

Release 12 defined a capability for devices to communicate directly with one another using LTE spectrum, a feature also called "operator-enabled proximity services." With this capability, devices can autonomously discover nearby relevant devices and services in a battery-efficient manner. Devices broadcast their needs and services and can also passively identify services without user intervention. The communication between devices is called "sidelink communications" and uses an interface called "PC5." Release 12, emphasizing public-safety applications, supports only one-to-many sidelink communications, whereas Release 13 supports one-to-one sidelink communications between two group member UEs and between a remote UE and a relay UE.

Initial emphasis of this capability, in both Release 12 and Release 13, is on public safety. Examples of potential consumer or commercial applications include discovering friends and family (social matching), push advertising for relevant notifications, tourist bulletins, venue services, crime alerts, home automation, vehicle-to-vehicle communication, and detecting children leaving the vicinity of their homes. The service is designed to work during infrastructure failures, even in emergencies and natural disasters. As a new means of communicating, proximity services could result in innovative types of applications.

The LTE network performs configuration and authentication; however, communication can be either via the network or directly between devices. To minimize battery consumption, devices synchronously wake up for brief intervals to discover services. The impact on LTE network capacity is minimal.

As with other location-based services, operators and application developers will need to address privacy concerns.

---

[155] 5G Americas member contribution.

LTE Throughput

The section “4G LTE Advances” above in the main section of the paper and “Data Throughput Comparison” in the appendix provide an overview of LTE throughputs. This section provides additional details.

Table shows initial (Release 8) LTE peak data rates based on different downlink and uplink designs.

Table20: LTE Peak Throughput Rates

LTE Configuration	Downlink (Mbps) Peak Data Rate	Uplink (Mbps) Peak Data Rate
Using 2X2 MIMO in the Downlink and 16 QAM in the Uplink, 10+10 MHz	70.0	22.0
Using 4X4 MIMO in the Downlink and 64 QAM in the Uplink, 20+20 MHz	300.0	71.0

LTE is not only efficient for data but, because of a highly efficient uplink, is extremely efficient for VoIP traffic. As discussed in the “Spectral Efficiency” section above, in 10+10 MHz of spectrum, LTE VoIP capacity will reach 500 users.[156]

Table 19 analyzes LTE median and average throughput values in greater detail for different LTE configurations.

Table 19: LTE FDD User Throughputs Based on Simulation Analysis[157]



Configuration	User Throughput, Mbps			
	Downlink (DL)		Uplink (UL)	
	Median	Average	Median	Average
LTE FDD: Low Band, 2x2 MIMO-DL, 1x2 SIMO-UL, 10+10 MHz, R8	8.6	10.9	4.5	5.0
LTE FDD: High Band, 4x2 MIMO-DL, 1x4 SIMO-UL, 10+10 MHz, R8	10.6	12.2	5.4	6.4
LTE FDD: High Band, 2x2 MIMO-DL, 1x2 SIMO UL, 20+20 MHz, R8	15.2	17.9	5.4	7.0
LTE FDD: High Band, 4x4 MIMO-DL, 1x4 SIMO UL, 20+20 MHz, R12	25.4	29.2	6.9	9.1

---

[156] 3GPP Multi-member analysis.

[157] 5G Americas member contribution. SIMO refers to Single Input Multiple Output antenna configuration, which in the uplink means one transmit antenna at the UE and multiple receive antennas at the eNodeB.

The simulation results represent a consensus view of 5G Americas members working on this white paper project. The goal of the analysis was to quantify LTE throughputs in realistic deployments. Simulation assumptions include:

- Traffic is FTP-like at a 50% load with a 75/25 mix of indoor/outdoor users.
- Throughput is at the medium-access control (MAC) protocol layer. (Application-layer throughputs may be 5 to 8 percent lower due to protocol overhead.)
- The 3GPP specification release numbers shown correspond to the infrastructure capability.
- The configuration in the first row corresponds to low-frequency band operation, representative of 700 MHz or cellular, while the remaining configurations assume high-frequency band operation, representative of PCS, AWS, or WCS. (Higher frequencies facilitate higher-order MIMO configurations and have wider radio channels available.)
- The downlink value for the first row corresponds to Release 8 device-receive capability (Minimum Mean Square Error [MMSE]), while the values in the other rows correspond to Release 11 device-receive capability (MMSE – Interference Rejection Combining [IRC]).
- The uplink value for the first row corresponds to a Maximal Ratio Combining (MRC) receiver at the eNodeB, while the remaining values correspond to an IRC receiver.
- Low-band operation assumes 1,732-meter inter-site distance, while high-band operation assumes 500-meter ISD. The remaining simulation assumptions are listed in Table 20.

Table 20: LTE FDD User Throughput Simulation Assumptions[158]



Parameter	Value
Frequency	Low Band (LB): B17; High Band (HB): B30
Channel bandwidth	10 MHz, 20 MHz
System configuration	DL: 2x2, 4x2, and 4x4 Closed-Loop (CL) MIMO UL: 1x2 and 1x4 SIMO
Traffic type	FTP model 2: File size = 0.15 Mbyte, 1 second inter-arrival time, Load varied by changing number of users
Inter-Site Distance (ISD)	LB: 1732 m; HB: 500 m
Pathloss model	LB: HATA; HB: COST231 with correction
eNodeB transmit power	LB: 60 watts total; HB: 80 watts total
eNodeB antenna type	2 Tx = +-45 degrees cross-pol (DIV-1X); 4 Tx = Closely separated pair of cross-pols (CLA-2X)
eNodeB antenna gain	LB: 14.8 dBi; HB: 17.5 dBi
eNodeB antenna pattern	Actual antenna patterns as used in RF planning tool
eNodeB Rx type	LB: MRC; HB: IRC
Downtilt	LB: 7 degrees; HB: 9 degrees
Penetration loss	75/25 mix of indoor/outdoor users LB: 12 dB for indoor users; HB: 22 dB for indoor users
Device speed	3 km/h all users
Channel model	Modified SCME-WINNER+, LB: Suburban Macro (SMa) scenario; HB: Urban Macro (UMa)
Device antenna type	+-45 degrees cross-pol with built in correlation of 0.5
Device antenna gain and mismatch	LB: - 5 dBi and 3 dB; HB: -3 dBi and 3 dB
Device body loss	3 dB for both bands
Device Rx type	MMSE, MMSE-IRC
Uplink power control	LB: alpha = 1, Po = -100 dBm; HB: alpha = 0.9, Po = -100 dBm
Scheduler	Proportional fair, frequency selective

The assumptions, emphasizing realistic deployments, do not necessarily match assumptions used by other organizations, such as 3GPP, so results may differ.

Additional insight into LTE performance under different configuration comes from a test performed on a cluster of cells in an LTE operator's network, comparing downlink performance of 4X2 MIMO against 2X2 MIMO, and uplink performance of 1X4 SIMO against 1X2 SIMO. The test employed LTE category 4 devices.[159]

---

[158] 5G Americas member contribution.

[159] 5G Americas member contribution.

These tests, which were performed in a 20+20 MHz cluster, show significant improvements in cell edge uplink and downlink throughput, in addition to an overall increase in uplink and downlink throughputs. Specific results include:

- ❑ A 100% increase in uplink throughput at the cell edge with 1X4 SIMO compared to 1x2 SIMO.
- ❑ A 40% increase in downlink throughput at the cell edge with 4x2 closed-loop MIMO compared to 2x2 open-loop MIMO.
- ❑ A 50 to 75% increase in downlink throughput with closed loop MIMO compared to transmit diversity modes.
- ❑ Up to 6dB gains in uplink transmit power with 1X4 SIMO, which directly translates into UE battery savings.
- ❑ Peak speeds of 144 Mbps with 4X2 MIMO in the downlink and 47 Mbps with 1X4 SIMO in the uplink.

Another LTE operator’s testing results for LTE in a TDD configuration, using 20 MHz channels, 3:2 DL to UL ratio, and category 3 devices, showed:

- ❑ Peak speeds of 55 Mbps.
- ❑ Typical speeds of 6 to 15 Mbps.[160]

Figure 74 shows the result of a drive test in a commercial LTE network with a 10 MHz downlink carrier demonstrating 20 Mbps to 50 Mbps throughput rates across much of the coverage area. Throughput rates would double with a 20+20 MHz configuration.

---

[160] 5G Americas member contribution.

Figure 74: Drive Test of Commercial European LTE Network (10+10 MHz)[161]


DL Throughput
Mbps
40 to 50
30 to 40
20 to 30
10 to 20
5 to 10
1 to 5
0.1 to 1
0 to 0.1

---

[161] Ericsson contribution.

Figure 75 provides additional insight into LTE downlink throughput, showing Layer 1 throughput simulated at 10 MHz bandwidth using the Extended Vehicular A 3 km/hour channel model. The figure shows the increased performance obtained with the addition of different orders of MIMO. Note how throughput improves based on higher signal to noise ratio (SNR).

Figure 75: LTE Throughput in Various Modes[162]



Actual throughput rates that users experience are lower than the peak rates and depend on a variety of factors:

- **RF Conditions and User Speed.** Peak rates depend on optimal conditions. Suboptimal conditions include being at the edge of the cell or moving at high speed, resulting in lower throughput.
- **Network Loading.** Like all wireless systems, throughput rates go down as more devices simultaneously use the network. Throughput degradation is linear.

---

[162] Jonas Karlsson, Mathias Refback, “Initial Field Performance Measurements of LTE,” *Ericsson Review*, No. 3, 2008.

Figure 76 shows how dramatically throughput rates can vary by number of active users and radio conditions. The higher curves are for better radio conditions.

Figure 76: LTE Actual Throughput Rates Based on Conditions[163]



---

[163] LTE/SAE Trial Initiative, "Latest Results from the LSTI, Feb 2009," http://www.lstiforum.org.

VoLTE and RCS

This paper introduced VoLTE and voice support in the earlier section, "VoLTE, RCS, WebRTC, and Wi-Fi Calling." This section in the appendix provides additional technical detail about the operation of VoLTE and RCS.

Voice in LTE can encompass: no voice support, voice implemented in a circuit-switched fallback (CSFB) mode using 2G or 3G, and VoIP implemented with IMS.

Initial LTE network deployments used CSFB, with which the LTE network carries circuit-switched signaling over LTE interfaces, allowing the subscriber to be registered with the 2G/3G MSC even while on the LTE network. When there is a CS event, such as an incoming voice call, the MSC sends the page to the LTE core network, which delivers it to the subscriber device. The device then switches to 2G/3G operation to answer the call.

Voice over LTE using VoIP requires IMS infrastructure. To facilitate IMS-based voice, vendors and operators created the One Voice initiative to define required baseline functionality for user equipment, the LTE access network, the Evolved Packet Core, and the IMS. GSMA adopted the One Voice initiative in what it calls VoLTE, specified in GSMA reference document IR.92.[164] GSMA specifies interconnection and international roaming among LTE networks through the IR.88[165] specification. Another specification, IR.94, provides the IMS Profile for Conversational Video Service, a service referred to as "Video over LTE" (ViLTE).[166]

For a phone to support VoLTE, it needs software implementing the IMS protocol stack. For example, the iPhone 6 was the first iPhone to implement such software. Additional software implementing RCS application programming interfaces can provide applications with access to IMS-based services, such as voice, messaging, and video. The Open Mobile Alliance has defined RESTful network APIs for RCS that support the following functions: notification channel, chat, file transfer, third-party calls, call notification, video sharing, image sharing, and capability discovery. As shown in Figure 77, over time, new profile releases will broaden the scope of these APIs.

---

[164] GSMA, "IMS Profile for Voice and SMS," Document IR.92. Available at http://www.gsma.com/newsroom/wp-content/uploads/2013/04/IR.92-v7.0.pdf.

[165] GSMA, "LTE Roaming Guidelines," GSMA Document IR.88. Available at http://www.gsma.com/newsroom/wp-content/uploads/2013/04/IR.88-v9.0.pdf.

[166] GSMA, "IMS Profile for Conversational Video Service," Document IR.94. Available at http://www.gsma.com/newsroom/all-documents/ir-94-ims-profile-for-conversational-video-service/.

Figure 77: Evolution of RCS API Profiles[167]


RCS API Profile Evolution
Profile v1.0
File Transfer
Notification Channel
Chat
Third Party Call
Call Notification
Image Share
Video Share
ACR (Anonymous Customer Reference)
Capability Discovery
Profile v2.0
Profile v1.0
Terminal Location
Address Book
Presence
Messaging
Profile v3.0
Profile v2.0
Network Message Storage
WebRTC Signaling

LTE VoIP leverages the QoS capabilities defined for EPC, which specify different quality classes. Features available in LTE to make voice operation more efficient include Semi-Persistent Scheduling (SPS) and TTI bundling. SPS reduces control channel overhead for applications (like VoIP) that require a persistent radio resource. Meanwhile, TTI bundling improves subframe utilization by reducing IP overhead, while in the process optimizing uplink coverage.

Another way to increase voice capacity in LTE and to support operation in congestion situations is vocoder rate adaptation, a mechanism with which operators can control the codec rate based on network load, thus dynamically trading off voice quality against capacity.

VoLTE roaming across operators will require network-to-network interfaces between their respective IMS networks. Such roaming and interconnect will follow initial VoLTE deployments. Different IMS stack implementations between vendors will also complicate roaming.

One roaming consideration is how operators handle data roaming. LTE roaming can send all visited network traffic back to the home network, which for a voice call, increases voice latency. For voice calls, the local breakout option would mitigate this latency.

Using Single-Radio Voice Call Continuity (SR-VCC) and Enhanced SR-VCC (eSRVCC), user equipment can switch mid-call to a circuit-switched network, in the event that the user moves out of LTE coverage. Similarly, data sessions can be handed over in what is called “Packet-Switched Handover” (PSHO).

---

[167] 4G Americas, *VoLTE and RCS Technology – Evolution and Ecosystem,* Nov. 2014.

Figure 78 shows how an LTE network might evolve in three stages. Initially, LTE performs only data service, and the underlying 2G/3G network provides voice service via CSFB. In the second stage, voice over LTE is available, but LTE covers only a portion of the total 2G/3G coverage area. Hence, voice in 2G/3G can occur via CSFB or SR-VCC. Eventually, LTE coverage will match 2G/3G coverage, and LTE devices will use only the LTE network.

Figure 78: Evolution of Voice in an LTE Network[168]


LTE
CSFB for voice
Release with Redirection or PSHO for data
2G or 3G
CSFB
VoLTE
CSFB
LTE
CSFB for voice
SRVCC or PSHO (3G)
2G or 3G with ICS
VoLTE
LTE
2G or 3G carrier migration
2G or 3G

Another voice approach, called “Voice over LTE via Generic Access” (VoLGA), defined circuit-switched operation through an LTE IP tunnel. 3GPP, however, has stopped official standards work that would support VoLGA.

3GPP has developed a new codec, called “Enhanced Voice Services” (EVS), which will include super-wideband voice capability. For the same bit rate, EVS provides higher voice quality than the other codecs.[169] Table 21 summarizes the features and parameters of the three 3GPP codecs used in LTE.

---

[168] 5G Americas member contribution.

[169] See Figure 9.2. 3GPP, *TR 26.952 V12.1.0, Codec for Enhanced Voice Services (EVS); Performance Characterization*, March 2015.

Table 21: Comparison of AMR, AMR-WB and EVS Codecs[170]

Features	AMR	AMR-WB	EVS
Input and output sampling frequencies supported	8KHz	16KHz	8KHz, 16KHz, 32KHz, 48 KHz
Audio bandwidth	Narrowband	Wideband	Narrowband, Wideband, Super-wideband, Fullband
Coding capabilities	Optimized for coding human voice signals	Optimized for coding human voice signals	Optimized for coding human voice and general-purpose audio (music, ringtones, mixed content) signals
Bit rates supported (in kb/s)	4.75, 5.15, 5.90, 6.70, 7.4, 7.95, 10.20, 12.20	6.6, 8.85, 12.65, 14.25, 15.85, 18.25, 19.85, 23.05, 23.85	5.9, 7.2, 8, 9.6 (NB and WB only), 13.2 (NB, WB and SWB), 16.4, 24.4, 32, 48, 64, 96, 128 (WB and SWB only)
Number of audio channels	Mono	Mono	Mono and Stereo
Frame size	20 ms	20 ms	20 ms
Algorithmic Delay	20-25 ms	25 ms	Up to 32 ms

Figure 79 shows mean opinion scores (MOS) for different codecs at different bit rates, illustrating the advantage of EVS, particularly for bit rates below 32 kbps that cellular networks use.

---

[170] 4G Americas, *Mobile Broadband Evolution: Rel-12 & Rel-13 and Beyond*, 2015. See also T-Mobile 2016 EVS announcement: https://newsroom.t-mobile.com/news-and-blogs/volte-enhanced-voice-services.htm.

Figure 79: Combined Mean Opinion Score Values[171]



Table 22 shows EVS (narrowband, wideband, super-wideband) audio bandwidths and bitrates that create subjective quality equal to or better than AMR or AMR-WB for typical conversational voice scenarios.

Table 22: EVS Compared to AMR and AMR-WB[172]



Reference	Equal bandwidth	Wider bandwidth
AMR 12.2 kbit/s	EVS-NB 8.0 kbit/s	EVS-WB 5.9 kbit/s
AMR-WB 12.65 kbit/s	EVS-WB 9.6 kbit/s	EVS-SWB 9.6 kbit/s
AMR-WB 23.85 kbits/s	EVS-WB 13.2 kbit/s	EVS-SWB 9.6 kbit/s

Figure 80 compares EVS capacity gains over AMR and AMR-WB for the references cases shown in Table 22. EVS-SWB at 9.6 kbps almost doubles voice capacity compared to AMW-WB at 23.85 kbps.

---

[171] Nokia, *The 3GPP Enhanced Voice Services (EVS) codec*, 2015.

[172] Ibid.

Figure 80: EVS Voice Capacity Compared to AMR and AMR-WB[173]



LTE Ultra-Reliable and Low-Latency Communications

The 3GPP work item for this feature states, "3GPP LTE technology enhancements are needed to serve such new use cases and to remain technologically competitive up to and beyond 2020. As a candidate technology for ITU IMT-2020 submission, it is motivated to further enhance the LTE system such that it can meet the key IMT-2020 requirements including those for URLLC in terms of reliability (1-10^{-5} reliability for small data packets within a latency of 1ms) as well as latency (≤1ms one way user plane latency)."[174]

Evolved Packet Core (EPC)

3GPP defined the Evolved Packet Core (EPC) in Release 8 as a framework for an evolution or migration of the network to a higher-data-rate, lower latency, packet-optimized system that supports multiple radio-access technologies including LTE, as well as and legacy GSM/EDGE and UMTS/HSPA networks. EPC also integrates CDMA2000 networks and Wi-Fi.

EPC is optimized for all services to be delivered via IP in a manner that is as efficient as possible—through minimization of latency within the system, for example. It also provides service continuity across heterogeneous networks, which is important for LTE operators who must simultaneously support GSM-HSPA customers.

One important performance-enhancing aspect of EPC is a flatter architecture. For packet flow, EPC includes two network elements, called "Evolved Node B" (eNodeB) and the Access Gateway (AGW). The eNodeB (base station) integrates the functions traditionally performed by the radio network controller, which previously was a separate node controlling multiple Node Bs. Meanwhile, the AGW integrates the functions traditionally performed by the SGSN and GGSN. The AGW includes both control functions, handled through the Mobile Management Entity (MME), and user plane (data communications) functions. The user plane functions consist of two elements: A serving gateway that addresses 3GPP mobility and terminates eNodeB connections, and a Packet Data Network (PDN) gateway that addresses service requirements and also terminates access by non-3GPP networks. The MME serving gateway and PDN gateways can be collocated in the same physical node or distributed, based on vendor implementations and deployment scenarios.

---

[173] Ibid.

[174] RP-170796, 3GPP Work Item Description, "Ultra Reliable Low Latency Communication for LTE," March 2017.

EPC uses IMS as a component. It also manages QoS across the whole system, an important enabler for voice and other multimedia-based services.

Figure 81 shows the EPC architecture.

Figure 81: EPC Architecture


GERAN
Rel’7 Legacy GSM/UMTS
SGSN
UTRAN
One-Tunnel Option
MME
Control
PCRF
Evolved RAN, e.g., LTE
User Plane
Serving Gateway
PDN Gateway
IP Services, IMS
EPC/SAE Access Gateway
Non 3GPP IP Access
Rysavy Research

Elements of the EPC architecture include:

- Support for legacy GERAN and UTRAN networks connected via SGSN.
- Support for new radio-access networks such as LTE.
- Support for non-3GPP networks such as EV-DO and Wi-Fi. (See section below on Wi-Fi integration).
- The Serving Gateway that terminates the interface toward the 3GPP radio-access networks.

- The PDN gateway that controls IP data services, does routing, allocates IP addresses, enforces policy, and provides access for non-3GPP access networks.
- The MME that supports user equipment context and identity, as well as authenticating and authorizing users.
- The Policy Control and Charging Rules Function that manages QoS aspects.

QoS in EPS employs the QoS Class Identifier (QCI), a number denoting a set of transport characteristics (bearer with/without guaranteed bit rate, priority, packet delay budget, packet error loss rate) and used to infer nodes specific parameters that control packet forwarding treatment (such as scheduling weights, admission thresholds, queue management thresholds, or link-layer protocol configuration). The network maps each packet flow to a single QCI value (nine are defined in the Release 8 version of the specification) according to the level of service required by the application. Use of the QCI avoids the transmission of a full set of QoS-related parameters over the network interfaces and reduces the complexity of QoS negotiation. The QCI, together with Allocation Retention Priority (ARP) and, if applicable, Guaranteed Bit Rate (GBR) and Maximum Bit Rate (MBR), determines the QoS associated to an EPS bearer. A mapping between EPS and pre-Release 8 QoS parameters permits interworking with legacy networks.

The QoS architecture in EPC enables a number of important capabilities for both operators and users:

- **VoIP support with IMS.** QoS is a crucial element for providing LTE/IMS voice service. (See section below on IMS).
- **Enhanced application performance.** Applications such as gaming or video can operate more reliably.
- **More flexible business models.** With flexible, policy-based charging control, operators and third parties will be able to offer content in creative new ways. For example, an enhanced video stream to a user could be paid for by an advertiser.
- **Congestion control.** In congestion situations, certain traffic flows (bulk transfers, abusive users) can be throttled down to provide a better user experience for others.

Table 23 shows the nine QCI used by LTE.

Table 23: LTE Quality of Service

QCI	Resource Type	Priority	Delay Budget	Packet Loss	Examples
1	GBR (Guaranteed Bit Rate)	2	100 msec.	10^{-2}	Conversational voice
2	GBR	4	150 msec.	10^{-3}	Conversational video (live streaming)
3	GBR	3	50 msec.	10^{-3}	Real-time gaming
4	GBR	5	300 msec.	10^{-6}	Non-conversational video (buffered streaming)
5	Non-GBR	1	100 msec.	10^{-6}	IMS signaling

QCI	Resource Type	Priority	Delay Budget	Packet Loss	Examples
6	Non-GBR	6	300 msec.	10^{-6}	Video (buffered streaming), TCP Web, email, and FTP
7	Non-GBR	7	100 msec.	10^{-3}	Voice, video (live streaming), interactive gaming
8	Non-GBR	8	300 msec.	10^{-6}	Premium bearer for video (buffered streaming), TCP Web, e-mail, and FTP
9	Non-GBR	9	300 msec.	10^{-6}	Default bearer for video, TCP for non-privileged users

Heterogeneous Networks and Small Cells

A fundamental concept in the evolution of next-generation networks is the blending of multiple types of networks to create a “network of networks” characterized by:

- ❑ Variations in coverage areas, including femtocells (either enterprise femtos or home femtos, called HeNBs), picocells (also referred to as metro cells), and macro cells. Cell range can vary from 10 meters to 50 kilometers.
- ❑ Different frequency bands.
- ❑ Different technologies spanning Wi-Fi, 2G, 3G, 4G, and 5G.
- ❑ Relaying capability in which wireless links can serve as backhaul.

Figure 82 shows how user equipment might access different network layers.

Figure 82: Load Balancing with Heterogeneous Networks[175]


1
2
3
3G Macro
Ubiquitous 3G deployment
LTE Macro
Partial LTE deployment (midterm transition stage)
LTE Pico + Femto
Femto
Pico
Femto
Geographic Layout
1. 3G-only UE: stays on 3G as it moves through network
2. 3G+LTE UE: moves between 3G macro, LTE macro, & LTE macro/pico
3. 3G+LTE UE: able to access 3G & LTE macros, plus LTE HeNB (femto)

HetNets will allow significant capacity expansion in configurations in which operators can add picocells to coverage areas served by macrocells, particularly if there are hot spots with higher user densities.

Small cells differentiate themselves from macrocells according to the parameters shown in Table 24.

Table 24: Small Cell Vs. Macro Cell Parameters: Typical Values

Parameter	Small Cell	Macro Cell
Transmission Power	24 dBm (0.25 W)	43 dBm (20 W)
Antenna Gain	2 dBi	15 dBi
Users	Tens	Hundreds
Mobility	30 km/hr	350 km/hr

---

[175] 5G Americas member contribution.

Whether or not the small cell uses the same radio carriers as the macro cell involves multiple tradeoffs. In Figure 83 Scenario 1, the small cells and macro cell use different radio carriers, the two not interfering with each other. Although this configuration requires more spectrum, the small cells are able to cover larger areas than if they were deployed using the same radio carrier as the macro. This configuration supports medium-to-high penetration levels of small cells, allowing the network to reach huge capacity.

In Scenario 2, the small cells and macro cells use the same radio carrier, accommodating operators with more limited spectrum, but the network must manage interference using the techniques discussed below. Operators must carefully manage small-cell transmission power in this configuration.

Figure 83: Scenarios for Radio Carriers in Small Cells


Small Cell
Macro Cell
Scenario 1:
Dedicated Carrier
Small Cell
Macro Cell
No RF interference
Best performance
Inter-frequency handover
Scenario 2:
Shared Carrier
Small Cell
Macro Cell
Interference between cells
Intra-frequency handover
Most popular
Scenario 3:
Straddled Carrier
Small Cell
Macro Cell
Macro Cell
Reduced interference
Inter-frequency handover
Frequency
Rysavy
Research

In Scenario 3, the small cells use a straddled radio carrier, accommodating operators with more spectrum, but the network still needs to manage interference using techniques discussed below. Compared with a shared carrier configuration, this configuration has benefits similar to dedicated carriers in terms of radio-parameter planning and reduced interference.

Figure 84 shows two different traffic distribution scenarios, with a uniform distribution of devices in the first and higher densities serviced by picocells in the second. The second scenario can result in significant capacity gains as well as improved user throughput.

Figure 84: Different Traffic Distributions Scenarios


Pico
Macro
Unplanned Deployment: Uniform Distribution of Devices
Planned Deployment: Traffic Hotspots
Rysavy Research

One vendor calculated expected HetNet gains assuming no eICIC, no picocell range extension, and no eICIC. For the case of four picocells without picocell range extension and uniform user distribution, the median-user-throughput gain compared with a macro-only configuration was 85%. For a similar case of four picocells but using a hotspot user distribution, the gain was much higher, 467%.[176] Additional gains will occur with picocell range extension.

Expected picocell gains rise proportionally to the number of picocells, so long as a sufficient number of UEs connect to the picocells.

Release 10 and Release 11 added enhanced support to manage the interference in the HetNet scenario in the time domain with Enhanced Inter-cell Interference Coordination (eICIC) and Further Enhanced Intercell Interference Coordination (feICIC), as well as in the frequency domain with carrier-aggregation-based ICIC.

HetNet capability keeps becoming more sophisticated through successive 3GPP releases as summarized in Table 25.

---

[176] 5G Americas member contribution. Further assumes 2X1 W picocell transmit power, cell-edge placement (planned picocell deployment), 67% of all the users within 40m of the pico locations, and 3GPP Technical Report 36.814 adapted to 700 MHz.

Table 25: 3GPP HetNet Evolution

3GPP Release	HetNet Feature
8	Initial SON capabilities, most for auto configuration. Initial intercell interference coordination (ICIC) available.
9	More mobility options (for example, handover between HeNBs), operator customer subscriber group (SCG) lists, load-balancing, coverage and capacity improvements.
10	An interface for HeNBs, called “Iurh,” that improves coordination and synchronization, LTE time domain eICIC. Carrier-aggregation-based ICIC also defined.
11	Improved eICIC, further mobility enhancements.

Enhanced Intercell Interference Coordination

Significant challenges must be addressed in these heterogeneous networks. One is near-far effects, in which local small-cell signals can easily interfere with macro cells if they are using the same radio carriers.

Interference management is of particular concern in HetNets since, by design, coverage areas of small coverage cells overlap with the macro cell. Beginning with Release 10, eICIC introduces an approach of almost-blank subframes by which subframe transmission can be muted to prevent interference. Figure 85 illustrates eICIC for the macro layer and pico layer coordination. If a UE is on a picocell but in a location where it is sensitive to interference from the macro layer, the macro layer can mute its transmission during specific frames when the pico layer is transmitting.

Figure 85: Example of Enhanced Intercell Interference Coordination[177]


Almost blank, or MBSFN sub-frame
Sub-frame with normal transmission
One sub-frame
Macro-layer
Requires strict time-synchronization between macro & Pico
Pico-layer
Pico-UEs sensitive to macro-cell interference are only scheduled in subframes where Macro use ABS. This allows scheduling of pico-UEs using larger pico node cell selection offsets (range extension).
Other pico-UEs that are closer to their serving pico node and therefore less restricted by macro-layer interfence canbe scheduled in any subframe.

LTE can also combine eICIC with interference-cancellation-based devices to minimize the harmful effects of interference between picocells and macro cells.

Figure 86 shows one 4G America member's analysis of anticipated median throughput gains using picocells and Release 11 Further Enhanced ICIC.

---

[177] 5G Americas member contribution.

Figure 86: Median Throughput Gains in Hotspot Scenarios[178]



FeICIC is also beneficial in non-hotspot scenarios. In the case of a uniform distribution of picocells, this same 5G Americas member estimates a 130% gain from FeICIC for an eight picocell per macro-cell scenario, increasing capacity from a factor of 3.3 for the picocells alone to a factor of 7.6 with the addition of FeICIC.[179]

Further insight is available from Figure 87, which shows 5 percentile and 50 percentile throughput with and without eICIC under different conditions of range extension and almost blanked subframes.

---

[178] 5G Americas member contribution. Assumes 3GPP evaluation methodology TR 36.814, carrier-aggregation UEs, macro ISD = 1732m, 700 MHz and 2GHz carrier frequency, full-buffer traffic, FDD 10+10 MHz per carrier, 6-degree antenna downtilt, 4 or 8 Picos and 30 UEs per Macro cell, hotspot distribution with 20 of 30 UEs near picos, PF scheduler, 2x2 MIMO, TU3 channel, NLOS, local partitioning algorithm.

[179] Assumes 3GPP evaluation methodology TR 36.814, macro ISD = 1732m, 700 MHz and 2GHz carrier frequency, full-buffer traffic, 6-degree antenna downtilt, 30 carrier-aggregation UEs per Macro cell, uniform random layout, PF scheduler, FDD, 10+10 MHz per carrier, 2x2 MIMO, TU3 channel, NLOS, local partitioning algorithm. Additional information is available at ftp://ftp.3gpp.org/tsg_ran/WG1_RL1/TSGR1_66b/Docs/R1-113383.zip.

Figure 87: User Throughput Performance With / Without eICIC for Dynamic Traffic vs. Average Offered Load per Macro Cell Area[180]



The muting of certain subframes in eICIC is dynamic and depends on identifying, on a per user basis, whether an interfering cell's signal exceeds a threshold relative to the serving cell signal. Coordinating muting among small cells can be complicated because a small cell can simultaneously be an interferer while serving a UE that is a victim of another cell. The network must therefore coordinate muting among multiple small cells.

Figure 88 below at left shows user throughput gains of time domain interference relative to network load. Throughput gains are higher at higher network loads because of more active users and the higher likelihood of interference between the small cells.

Figure 88 below at right shows the maximum muting ratio, which increases with higher network load.

---

[180] 5G Americas member contribution. Assumes 3GPP evaluation methodology TR 36.814, 500 meter ISD, 4 picos per macro-cell area, Poisson call arrival, finite payload for each call, and termination of call upon successful delivery.

Figure 88: Throughput Gain of Time-Domain Interference Coordination[181]



Another approach for addressing inter-layer interference cancellation in HetNets can come from carrier aggregation with no further additions or requirements and realizable with Release 10 LTE networks. Consider the scenario in Figure 89, in which both the macro eNB and the pico eNB are allocated two component carriers (namely CC1 and CC2). The idea is to create a "protected" component carrier for downlink control signals and critical information (Physical Downlink Control Channel, system information, and other control channels) while data can be conveniently scheduled on both component carriers through cross-carrier scheduling.

Figure 89: Carrier-Aggregation Based ICIC[182]


Macro eNB
UE on carrier 2 with control on carrier 1
UE on carrier 1 with control on carrier 1
UE on carrier 2 with control on carrier 2
UE on carrier 1 with control on carrier 2

CC1 is the primary component carrier for the macro cell, while CC2 is the primary for the picocell; hence the protected carriers are CC1 for the macro cell and CC2 for the picocell. The macro cell allocates a lower transmission power for its secondary CC in order to reduce interference to the picocell's primary component carrier. The network can schedule data on both the primary and secondary component carriers. In the figure, users in the cell range expansion (CRE) zone can receive data via cross-carrier scheduling from the secondary CC at subcarrier frequencies on which interference from the other cell can be reduced if the cells exchange appropriate signaling over what is called an "X2 interface." Users operating close to the eNodeBs can receive data from both component carriers as their interference levels will hopefully be lower. Therefore, a CA-capable receiver will enjoy the enhanced throughput capabilities of carrier aggregation, while simultaneously receiving extra protection for control and data channels at locations with potentially high inter-layer interference.

---

[181] 5G Americas member contribution. Simulations based on 12 densely deployed small cells at 3.5 GHz and 3GPP Release 12 simulation assumptions in TR 36.842.

[182] 5G Americas member contribution.

Thus, carrier aggregation can be a useful tool for deployment of heterogeneous networks without causing a loss of bandwidth. These solutions, however, do not scale well (in Release 10 systems) to small system bandwidths (say, 3+3 MHz or 1.4+1.4 MHz radio carriers) because control channels occupy a high percentage of total traffic. Additionally, interference between the cell reference signals (CRS) would also be significant.

Dual Connectivity

A major enhancement in Release 12 is a UE being served at the same time by both a macro cell and a small cell operating at different carrier frequencies, a capability called dual connectivity and illustrated in Figure 90. Data first reaches the macro eNodeB and is split, with part of it transmitted from the macro and the balance sent via an X2 interface to the small cell for transmission to the UE.

Figure 90: Dual Connectivity[183]


Data from
core network (CN)
Macro
(MeNB)
Flow control of data
over backhaul (X2)
PCell
Data flow is split in
the macro-eNB
Small cell
(SeNB)
Data needs to be
buffered in the
small cell eNB
X2 interface
SCell
Receives data from both macro
and small cell. Transmits
corresponding CSI and HARQ
Ack/Nacks to macro and small cell.

Figure 91 shows throughput gains of dual connectivity at 5 percentile and 50 percentile (median) levels relative to the load on the network and different degrees of latency in the X2 interface. Benefits are higher with lower network load and with lower X2 latency.

---

[183] Source: 5G Americas member contribution.

Figure 91: Dual Connectivity User Throughput[184]



---

[184] 5G Americas member contribution.

Internet of Things and Machine-to-Machine

Anticipating huge growth in machine-to-machine communications, Release 11 added a Machine Type Communications (MTC) Interworking Function and Service Capability Server. Release 12 defined a category 0 device designed to deliver low cost through a single antenna design and other simplifications.[185] Release 13 went even further, with a category M-1 architecture that further reduces cost, improves range, and extends battery life. Category 13 also added Narrowband-IoT capability with Category NB-1 and an IoT solution for GSM, called “EC-GSM-IoT,” that extends coverage by 20 dB. Category M-1 and NB-IoT devices could achieve battery life as high as 10 years.

Figure 92 depicts the methods used to reduce cost in a Category M device compared with a Category 4 device.

Figure 92: Means of Achieving Lower Cost in IoT Devices[186]


Cat 4
2Rx
1Tx
Full Duplex
Memory
AP
IMS
Modem-150 Mbps
Reduced RF Chains
Reduced Bandwidth
Half Duplex
Reduced Speeds
Reduced Memory, AP
Max Tx Power 23->20 dBm
Reduced TB Size
Reduced Modulation Schemes
Cat M2
1Rx
1Tx
Half
Memory
AP
~~IMS~~
Modem-200 Kbps

Table 26 summarizes the features of different LTE IoT devices based on 3GPP Release.

Table 26: Summary of IoT Features in LTE Devices

Device Category	Category 3	Category 1	Category 0	Category M-1	Category NB-1	EC-GSM-IoT
3GPP Release	10	11	12	13	13	13

---

[185] 3GPP, *Access System for Ultra Low Complexity and Low Throughput Internet of Things based on Cellular*, GP-140301, May 2014.

[186] 5G Americas member contribution.

Device Category	Category 3	Category 1	Category 0	Category M-1	Category NB-1	EC-GSM-IoT
Max. Data Rate Downlink	100 Mbps	10 Mbps	1 Mbps	1 Mbps	200 Kbps	74 Kbps
Max. Data Rate Uplink	50 Mbps	5 Mbps	1 Mbps	1 Mbps	200 Kbps	74 Kbps
Max. Bandwidth	20 MHz	20 MHz	20 MHz	1.08 MHz	0.18 MHz	0.2 MHz
Duplex	Full	Full	Optional half-duplex	Optional half-duplex	Half	Half
Max. Receive Antennas	Two	Two	One	One	One	One
Power		Power Save Mode[187]	Power Save Mode	Power Save Mode		
Sleep				Longer sleep cycles using Idle Discontinuous Reception (DRX)		
Coverage				Extended through redundant transmissions and Single Frequency Multicast		

Cloud Radio-Access Network (RAN) and Network Virtualization

Still in the early stages of development, cloud RAN (C-RAN) is a distributed architecture in which multiple remote radio heads connect to a “cloud” that consists of a farm of baseband processing nodes. This approach can improve centralized processing, as is needed for

---

[187] Power Save Mode specified in Release 12, but applicable to Category 1 device configured as Release 12.

CoMP, centralized scheduling, and Multiflow, without the need to exchange information among many access nodes. The performance of both LTE and HSPA technologies could be enhanced by the application of cloud RAN architectures. The term “fronthauling” has been used to describe the transport of “raw” radio signals to central processing locations, such as between the Physical Network Function (PNF) and a Virtual Network Function (VNF).

This architecture, shown in Figure 93, comes at the cost of requiring high-speed, low-latency backhaul links between these radio heads and the central controller. One vendor states that carrying 10+10 MHz of LTE with 2X2 MIMO requires 2.5 Gbps of bandwidth and imposes less than 0.1 msec of delay.[188] A standard called “Common Public Radio Interface” (CPRI) addresses generic formats and protocols for such a high-speed link. ETSI has also developed the Open Radio Equipment Interface (ORI). The feasibility of cloud RAN depends to a large extent on the cost and availability of fiber links between the remote radio heads and the centralized baseband processing location.

Unlike virtualizing the EPC, in which the entirety of the function can be virtualized, cloud RAN needs a PNF that terminates the RF interface. Cloud RAN therefore requires a split to be defined within the RAN. As a consequence, initial deployments of cloud RAN have looked to ruse the CPRI interface between the RRH and the baseband unit.

Figure 93: Potential Cloud RAN Approach



The next evolutionary step after centralizing baseband processing is to virtualize the processing by implementing the functions in software on commodity computing platforms, thus abstracting the functions from any specific hardware implementation.

C-RANs can vary by the extent of coverage, ranging from being highly localized and operating across a small number of sites to metropolitan-wide solutions. Other variables include existing deployments versus greenfield situations, new LTE and 5G technologies versus integrating legacy 2G and 3G technologies, and integrating Wi-Fi. Greater scope increases complexity but yields benefits including better load-balancing and greater flexibility in spectrum re-farming.

---

[188] Dudu Bercovich, Ran Avital, “Holistic HetNet Hauling (3H),” Ceragon, February 2013. Available at http://www.ceragon.com/images/Reasource_Center/White_Papers/Ceragon_Holistic_Hetnet_Hauling_White_Paper.pdf.

Another design choice, as detailed in Table 27, is whether to centralize Layer 1 and Layer 2 functions (an RF-PHY split), or whether to keep Layer 1 at the base stations and centralize only Layer 2 (a PHY-MAC split).

Table 27: Partially Centralized Versus Fully Centralized C-RAN

	Fully Centralized	Partially Centralized
Transport Requirements	Multi-Gbps, usually using fiber	20 to 50 times less
Fronthaul Latency Requirement	Less than 100 microseconds	Greater than 5 milliseconds
Applications	Supports eICIC and CoMP	Supports centralized scheduling
Complexity	High	Lower
Benefit	Capacity gain	Lower capacity gain

Figure 94 analyzes the different possible RAN decompositions in greater detail.

Figure 94: Costs and Benefits of Various RAN Decompositions[189]


RRC
PDCP
RLC
MAC
PHY
RF
RRC
PDCP
RLC
MAC
PHY
PHY
RF
RRC
PDCP
RLC
MAC
DCP
PHY
RF
RRC
PDCP
RLC
MAC
MAC
PHY
RF
RRC
PDCP
RLC
MAC
PHY
RF
RRC
PDCP
RLC
MAC
PHY
RF

🟦 No additional cost of benefit enabled
🟨 Cost added or challenge to providing benefit
⬜ Major cost added or challenge to providing benefit

	CPRI	Split PHY	MAC-PHY	Split MAC	PDCP-RLC	RRC-PDCP Split
	Complete Waveform Shipped to RF (IQ Samples)	Waveform Modulation/ Demod distributed	Distribute PHY and centralize MAC	Distribute time sensitive MAC (e.g., HARQ process)	Distribute Radio Link Control to reduce time sensitivity	Control Pane/Data Plane Split
Fronthaul delay requirements	⬜ 100 us transport latency	🟨 <6 ms latency for interleaved HARQ	🟨 <6 ms latency for interleaved HARQ	🟦 RLC ACK Windowing latency only	🟦 Same as legacy backhaul	🟦 Same as legacy backhaul
Fronthaul bandwidth requirements	⬜ 30 x BW expansion	⬜ UL BW expansion due to soft bits	🟦 Same as legacy backhaul	🟦 Same as legacy backhaul	🟦 Same as legacy backhaul	🟦 Same as legacy backhaul
Multi-vendor alignment	🟦 Limited multi-vendor ORI Support	⬜ Proprietary	🟦 Small Cell Ecosystem defining	⬜ Proprietary	🟨 Challenging	🟨 Challenging
Virtualization Support	⬜ Specialized HW required	🟨 Some functions virtualized	🟨 Some functions virtualized	🟦 Virtualized central functions	🟦 Maximal virtualization	🟦 Maximal virtualization
Performance Improvements	🟦 Inter-cell gains possible	🟦 Inter-cell gains possible	🟨 Some inter-cell gains possible	⬜ Limited inter-cells gains	⬜ Limited inter-cells gains	⬜ Some handover optimization

Although some operators in dense deployments with rich fiber assets may centralize all functions, Figure 94 uses the red rectangles to show the two most likely functional splits for LTE-Advanced and 5G:

1. **Distributed PHY and Centralized MAC.** This approach relaxes the fronthaul delay requirement to 6 msec, compared with the CPRI requirement of 250 microseconds. Fronthaul bandwidth requirement is only 10-20% greater than conventional backhaul.
2. **Control Plane/Data Plane Split.** This approach further relaxes fronthaul requirements to 30 msec and is the approach used for dual-connectivity, such as a macro and small cell simultaneously connecting to a user. For 5G, 3GPP Release 15 specifications standardize a split for cloud RAN between the PDCP and RLC layers.

---

[189] Cisco, *Cisco 5G Vision Series: Small Cell Evolution*, 2016.

Next Generation Mobile Networks studied the pros and cons of different fronthauling interfaces and published the results in March 2015.[190]

Longer-term, perhaps in the 5G context, virtualized C-RANs may take away the very concept of cells. With methods such as beamforming and device-to-device communication, coverage may extend dynamically from a multitude of sources based on instantaneous load notifications and the radio resources available at different nodes.

In the past, RAN and core networks have been distinct entities, but over the next decade, the two may merge with more centralized, virtualized, and cloud-driven approaches.

Another form of virtualization is software-defined networking, an emerging trend in both wired and wireless networks. For cellular, SDN promises to reduce OPEX costs, simplify the introduction of new services, and improve scalability; all major infrastructure vendors are involved. The Open Networking Foundation explains that an SDN decouples the control and data planes, centralizing network state and intelligence, while abstracting the underlying network infrastructure from applications.[191] Virtualization of network functions will be a complex, multi-year undertaking and will occur in stages, as shown in Figure 95.

---

[190] Next Generation Mobile Networks, *Further Study on Critical C-RAN Technologies, Version 1.0*, March 2015. See sections 2.2 and 2.3. Available at https://www.ngmn.org/uploads/media/NGMN_RANEV_D2_Further_Study_on_Critical_C-RAN_Technologes_v1.0.pdf.

[191] Open Networking Foundation, “Software-Defined Networking: The New Norm for Networks,” http://www.opennetworking.org/sdn-resources/sdn-library/whitepapers, accessed June 20, 2014.

Figure 95: Software-Defined Networking and Cloud Architectures[192]


Business Architectures
Technology Architectures
Analytics-Enrichment
(Insight Monetization, Subscriber Experiences, Network Usage, Customer Care, CAPEX/OPEX)
Hosted Enterprise Communications
(IMS, VoLTE, Collaboration)
M2M
(Connected Vehicle, Smart Grid)
Internet of Everything
Platform Services
(Web Hosting, App Stores, Cloud Storage)
B2B/OTT Applications Enablement
(OSS as a Service, Network as a Service, Network API)
Software-Defined Networks
(Self Optimizing Networks, Programmable Networks, Service Flow Routing, Service Chaining)
Cloud Controllers
(WLAN, RNC, MME)
Network Function Virtualization
(Elastic Cloud Networks, Gi-LAN Services)
Datacenter Orchestration
(Elastic Compute, Workflow Automation)
Cloud RAN
(RRH + BBU)
Cloud Applications
Cloud Networks
Cloud Services
PAST
NOW
FUTURE
"Infrastructure Build Phase"
(LTE, WiFi, Small Cell)
"Cloud Optimization Phase"
(RAN, Controllers, Gateways, Services, Applications)

Unlicensed Spectrum Integration

See the earlier section in this report on unlicensed spectrum integration, which includes a discussion of LTE-U, LTE-LAA, MulteFire, LWA, LWIP, and RCLWI. This section covers integration approaches other than these.

3GPP has evolved its thinking on how best to integrate Wi-Fi with 3GPP networks. At the same time, the Wi-Fi Alliance and other groups have also addressed hotspot roaming, namely the ability to enable an account with one public Wi-Fi network provider to use the services of another provider that has a roaming arrangement with the first provider.

The multiple attempts to make Wi-Fi networks universally available have made for a confusing landscape of integration methods, which this section attempts to clarify. Most integration today is fairly loose, meaning that either a device communicates data via the cellular connection or via Wi-Fi. If via Wi-Fi, the connection is directly to the internet and bypasses the operator core network. In addition, any automatic handover to hotspots occurs only between the operator cellular network and operator-controlled hotspots. The goals moving forward are to:

- Support roaming relationships so that users can automatically access Wi-Fi hotspots operated by other entities.
- Enable automatic connections so that users do not have to enter usernames and passwords. In most cases, this will mean authentication based on SIM credentials.

---

[192] 5G Americas member contribution.

- Provide secure communications on the radio link as provided by the IEEE 802.11i standard.
- Allow policy-based mechanisms that define the rules by which devices connect to various Wi-Fi networks.
- Enable simultaneous connections to both cellular and Wi-Fi, with control over which applications use which connections.
- Support different types of Wi-Fi deployments, including third-party access points and carrier access points.

Release 6 I-WLAN

3GPP Release 6 was the first release to offer the option of integrating Wi-Fi in a feature called "Interworking WLAN" (I-WLAN), using a separate IP address for each network type.

Release 8 Dual Stack Mobile IPv6 and Proxy Mobile IPv6

3GPP Release 8 specified Wi-Fi integration with the EPC using two different approaches: host-based mobility with Dual Stack Mobile IPv6 (DSMIPv6) in the client, and network based mobility with Proxy Mobile IPv6 (PMIPv6) using an intermediary node called an "Enhanced Packet Data Gateway" (ePDG).[193] This method is intended for untrusted (non-carrier-controlled) Wi-Fi networks.

Release 11 S2a-based Mobility over GTP

Release 11, however, implements a new and advantageous approach as shown in Figure 96, one that eliminates the ePDG. Called "S2a-based Mobility over GTP" (SaMOG), a trusted WLAN Access Gateway connects to multiple 3GPP-compliant access points. Traffic can route directly to the internet or traverse the packet core. This method is intended for trusted (carrier-controlled) Wi-Fi networks.

---

[193] 3GPP, *System Architecture Evolution (SAE); Security aspects of non-3GPP accesses*. TS 33.402.

Figure 96: Release 11 SaMOG-based Wi-Fi Integration



Release 12 improves SaMOG capabilities in Enhanced SaMOG (eSaMOG), in which UEs can:

- ☐ Request the connectivity type
- ☐ Indicate the Access Point Name (APN) to establish PDN connectivity
- ☐ Request to hand over an existing PDN connection
- ☐ Establish multiple PDN connections in parallel over the WLAN
- ☐ Establish a non-seamless WLAN offload connection in parallel to a Packet Data Network connection over WLAN.

Multipath TCP

A new method for potentially integrating Wi-Fi and 3GPP networks is based on work by the Internet Engineering Taskforce (IETF). Called “Multipath TCP,” the approach allows a TCP connection to occur simultaneously over two different paths. The advantages of this approach include higher speeds by aggregating links and not requiring any special provisions for link-layer handovers.

The IETF has published an experimental specification, *Request for Comments 6824: CP Extensions for Multipath Operation with Multiple Addresses*, which explains this approach. The IETF is also specifying Multipath QUIC.

ANDSF

Another relevant specification is 3GPP Access Network Discovery and Selection Function (ANDSF), which provides mechanisms by which mobile devices can know where, when, and how to connect to non-3GPP access networks, such as Wi-Fi.[194] ANDSF operates independently of SaMOG or other ways that Wi-Fi networks might be connected.

---

[194] 3GPP, *Architecture enhancements for non-3GPP accesses, Technical Specification 23.402*.

ANDSF functionality increases with successive 3GPP versions, as summarized in Table 28.

Table 28: ANDSF Policy Management Objects and 3GPP Releases[195]



ANDSF Policy Type	Policy Rule & Management Object	Release 8, 9	Release 10, 11	Release 12
Inter-System Mobility Policy (ISMP)	Policy, Rule priority, Prioritized Access, Validity Area (3G,4G, WI-FI, Geo), PLMN, Time-of-Day	X	X	X
Discovery Info	Access Network Type, Access Network Area (3G, 4G, Wi-Fi, Geo), Access Network Reference	X	X	X
UE Location	3GPP, 3GPP2, WiMAX, Wi-Fi network ID, Geo Location, PLMN	X	X	X
Inter-System Routing Policy (ISRP)	Flow Based routing, Service Based routing, Non-Seamless Offload, Roaming, PLMN, Routing Criteria, Time-of-Day, Routing rule		X	X
UE Profile	Device app/OS capability		X	X
Inter-APN Routing Policy (IARP)	Inter-APN routing over IP interface (in progress)			X
WLAN Selection Policy	Operator defined WLAN selection policy			X
Rule Selection Information	VPLMN with preferred WLAN roaming			X
Home Operator Preference	Home SP preference for S2a PDN session			X

Bidirectional Offloading Challenges

Eventually, operators will be able to closely manage user mobile broadband and Wi-Fi connections, dynamically selecting a particular network for a user based on real-time changes in loads and application requirements. Work is occurring in Release 12 to define parameters that would control switching from LTE to Wi-Fi or from Wi-Fi to LTE.[196]

Bidirectional offloading, however, creates various challenges, as shown in Figure 97 and discussed below.

---

[195] Courtesy Smith Micro Software, 2014. http://www.smithmicro.com.

[196] 3GPP, *Study on Wireless Local Area Network (WLAN) - 3GPP radio interworking (Release 12)*, TR 37.834.

Figure 97: Bidirectional Offloading Challenges


Premature Wi-Fi Selection
Smart Phone
3GPP
Data rate [Mbps]
Wi-Fi
Distance to cell
Unhealthy Choices
LOAD
LTE
HS
Wi-Fi
Lower capabilities
Fiber
xDSL (eg. 10/2 Mbps)
3GPP
Wi-Fi
50 vs 2 Mbps
Ping-Pong

- **Premature Wi-Fi Selection.** As Wi-Fi-capable devices move into Wi-Fi coverage, they can prematurely reselect to Wi-Fi without comparative evaluation of existing cellular and incoming Wi-Fi capabilities, possibly resulting in the degradation of the end user experience. Real-time throughput-based traffic steering can mitigate this effect.

- **Unhealthy choices.** In a mixed network of LTE, HSPA, and Wi-Fi, reselection can occur due to a strong Wi-Fi network signal even though the network is under heavy load. The resulting “unhealthy” choice degrades the end user experience because the performance on the cell edge of a lightly loaded cellular network may be superior to that of the heavily loaded Wi-Fi network. Real-time load-based traffic steering can be beneficial in this scenario.

- **Lower capabilities.** In some cases, selection to a Wi-Fi network may result in reduced performance even if it offers a strong signal because of other factors, such as lower-bandwidth backhaul. Evaluation of criteria beyond wireless capabilities prior to access selection can improve this circumstance.

- **Ping-Pong.** Ping-ponging between Wi-Fi and cellular, especially if both offer similar signal strengths, can also degrade the user experience. Hysteresis approaches, similar to those used in cellular inter-radio transfer, can better manage transfer between Wi-Fi and cellular accesses.

3GPP RAN2 is discussing real-time or near-real-time methods to address the challenges discussed above.

Other Integration Technologies (SIPTO, LIPA, IFOM, MAPCON)

Release 10 defines additional options for Wi-Fi integration, including Selected IP Traffic Offload (SIPTO), Local IP Access (LIPA), Multi-Access PDN Connectivity (MAPCON), and IP Flow and Seamless Offload (IFOM).

SIPTO is mostly a mechanism to offload traffic that does not need to flow through the core, such as internet-destined traffic. SIPTO can operate on a home femtocell, or it can operate in the macro network.

Local IP Access (LIPA) provides access to local networks, useful with femtocells that normally route all traffic back to the operator network. With LIPA, the UE in a home environment can access local printers, scanners, file servers, media servers, and other resources.

IFOM, as shown in Figure 98, enables simultaneous cellular and Wi-Fi connections, with different traffic flowing over the different connections. A Netflix movie could stream over Wi-Fi, while a VoIP call might flow over the cellular-data connection. IFOM requires the UE to implement Dual Stack Mobile IPv6 (DSMIPv6).

Figure 98: 3GPP IP Flow and Seamless Mobility


Internet
Operator Core Network
Cellular 3G/4G
Radio-Access Network
Wi-Fi Access Network
Example: Operator VoIP
Simultaneous
Connection
To Both Networks
Example: Streaming Movie
Different application traffic
flows can bind to the
different access networks.
Rysavy Research

Similar to IFOM, Release 10 feature MAPCON allows multiple simultaneous PDN connections (each with a separate APN), such as Wi-Fi and 3GPP radio access. The UE uses separate IP addresses for each connection but does not need Dual Stack Mobile IPv6 (DSMIPv6).

Hotspot 2.0

Developed by the Wi-Fi Alliance, Hotspot 2.0 specifications, also called "Next Generation Hotspot," facilitate Wi-Fi roaming. Using the IEEE 802.11u standard that allows devices to determine what services are available from an access point, Hotspot 2.0 simplifies the process by which users connect to hotspots, automatically identifying roaming partnerships and simplifying authentication and connections, as shown in Figure 99.[197] It also provides for encrypted communications over the radio link.[198]

Figure 99: Roaming Using Hotspot 2.0


Automatic, secure connection
Hotspot 2.0 facilitates roaming across networks.
Enterprise
Operator A
Operator B
Rysavy Research

Using IEEE 802.11u, devices can determine what roaming relationships an access point supports and can then securely connect to the Wi-Fi network using one of these roaming arrangements, as shown in Figure 100. Hotspot 2.0 authentication is based on the Extended Authentication Protocol (EAP) using SIM credentials. There are plans to enhance the Hotspot 2.0 protocols in Phase 2, which will define online signup to enable non-SIM-based devices to easily and securely register for services. The Wi-Fi Alliance began a Hotspot 2.0 certification process for devices and access points in June 2012 and uses the designation “Wi-Fi Certified Passpoint” for compliant devices.

---

[197] For example, user devices can be authenticated based on their SIM credentials. Or, users can register or click through an agreement and then not need to redo that with future associations.

[198] The IEEE 802.11i standard has provided encryption for 802.11 communications for many years; however, most hotspots have not implemented this encryption, whereas Hotspot 2.0 does.

Figure 100: Hotspot 2.0 Connection Procedure


802.11u beacons with HS 2.0 support
Access Network Query Protocol
Responses to queries (operator name, roaming partners, EAP method supported)
Device chooses best AP
Secure communications
Roaming hubs, subscriber information
Rysavy Research

Release 2 of Passpoint, available in 2014, added immediate account provisioning, which facilitates a user establishing an account at the point of access. The new version also provides for policies to be downloaded from the network operator; these policies control network selection priorities when multiple networks are available.

Self-Organizing Networks (SON)

As the number of base stations increase through denser deployments and through deployment of femtocells and picocells, manual configuration and maintenance of this infrastructure becomes impractical. With SON, base stations organize and configure themselves by communicating with one another and with the core network. SONs can also self-heal in failure situations.

3GPP began standardization of self-optimization and self-organization in Releases 8 and 9, a key goal being support of multi-vendor environments. Successive releases have augmented SON capabilities.

Features being defined in SON include:

- Automatic inventory;
- Automatic software download;
- Automatic neighbor relation;
- Automatic physical Cell ID assignment;
- Mobility robustness/handover optimization;
- Random access channel optimization;
- Load-balancing optimization;
- Inter-cell interference coordination (ICIC) management;

- Enhanced inter-cell interference coordination (eICIC) management;
- Coverage and capacity optimization;
- Cell outage detection and compensation;
- Self-healing functions;
- Minimization of drive testing;
- Energy savings; and
- Coordination among various SON functions.

3GPP categorizes SON as centralized, distributed, or hybrid, which is a combination of centralized and distributed approaches.

In a centralized architecture, SON algorithms operate on a central network management system or central SON server. In contrast, in a distributed approach, the SON algorithms operate at the eNBs, which make autonomous decisions based on local measurements as well as from other nearby eNBs received via an X2 interface that interconnects eNBs.

The distributed architecture permits faster and easier deployment but is not necessarily as efficient or as consistent in operation, especially in multi-vendor infrastructure deployments.

In a hybrid approach, shown in Figure 101, SON algorithms operate both at the eNB and at a central SON server, with the server supplying values of initial parameters, for example. The eNBs may then update and refine those parameters in response to local measurements.

The hybrid approach resolves deployment scenarios that cannot be resolved by dSON, for example, cases such as:

- No X2 interface between the eNBs.
- Multi-vendor deployment with different dSON algorithms.
- Multi-technology load balancing and user steering.

Figure 101: Hybrid SON Architecture[199]



With increasing numbers of macro cells and small cells, interference opportunities increase as well. Optimizing power settings through intelligent power management algorithms is crucial for maximum efficiency with the least amount of interference, including pilot pollution. Pilot pollution can result in low data rates and ping-pong handovers due to channel fading. A hybrid SON approach is well suited for optimized power management.

IP Multimedia Subsystem (IMS)

IP Multimedia Subsystem (IMS) is a service platform for IP multimedia applications: video sharing, PoC, VoIP, streaming video, interactive gaming, and others. IMS by itself does not provide all these applications. Rather, it provides a framework of application servers, subscriber databases, and gateways to make them possible. The exact services will depend on cellular operators and the application developers that make these applications available to operators. The primary application in 2016, however, is VoLTE.

The core networking protocol used within IMS is Session Initiation Protocol (SIP), which includes the companion Session Description Protocol (SDP) used to convey configuration information such as supported voice codecs. Other protocols include Real Time Transport Protocol (RTP) and Real Time Streaming Protocol (RTSP) for transporting actual sessions. The QoS mechanisms in UMTS will be an important component of some IMS applications.

Although originally specified by 3GPP, numerous other organizations around the world are supporting IMS. These include the IETF, which specifies key protocols such as SIP, and the Open Mobile Alliance, which specifies end-to-end, service-layer applications. Other organizations supporting IMS include the GSMA, ETSI, CableLabs, 3GPP2, The Parlay Group, the ITU, ANSI, the Telecoms and Internet Converged Services and Protocols for Advanced Networks (TISPAN), and the Java Community Process (JCP).

IMS is relatively independent of the radio-access network and can, and likely will, be used by other radio-access networks or wireline networks. Other applications include picture and video sharing that occur in parallel with voice communications. Operators looking to roll out VoIP over networks will use IMS. For example, VoLTE depends on IMS infrastructure.

---

[199] 5G Americas member contribution.

3GPP initially introduced IMS in Release 5 and has enhanced it in each subsequent specification release.

As shown in Figure 102, IMS operates just outside the packet core.

Figure 102: IP Multimedia Subsystem


IMS
SIP Application Server
Home Subscriber Server (HSS)
SIP
Media Resource Function Control
DIAMETER
Media Resource Gateway Control
Call Session Control Function (CSCF) (SIP Proxy)
4G
DSL
Wi-Fi
Multiple Possible Access Networks
Rysavy Research

The benefits of using IMS include handling all communication in the packet domain, tighter integration with the internet, and a lower cost infrastructure based on IP building blocks for both voice and data services.

IMS applications can reside either in the operator's network or in third-party networks including those of enterprises. By managing services and applications centrally—and independently of the access network—IMS can enable network convergence. This allows operators to offer common services across 3G, Wi-Fi, and wireline networks.

Service Continuity, defined in Release 8, provided for a user's entire session to continue seamlessly as the user moves from one access network to another. Release 9 expanded this concept to allow sessions to move across different device types. For example, the user could transfer a video call in midsession from a mobile phone to a large-screen TV, assuming both have an IMS appearance in the network.

Release 8 introduced the IMS Centralized Services (ICS) feature, which allows for IMS-controlled voice features to use either packet-switched or circuit-switched access.

Given that LTE operators will integrate their 5G networks with their current LTE networks, operators are likely to keep using IMS in conjunction with LTE for their voice and other services that use IMS, even as they begin deploying 5G.

Broadcast/Multicast Services

An important capability for 3G and evolved 3G systems is broadcasting and multicasting, wherein multiple users receive the same information using the same radio resource. This creates a more efficient approach to deliver video when multiple users desire the same content simultaneously. In a broadcast, every subscriber unit in a service area receives the information, whereas in a multicast, only users with subscriptions receive the information. Service areas for both broadcast and multicast can span either the entire network or a specific geographical area. Potential applications include sporting events, select news, venue-specific (shopping mall, museum) information, and even delivery of software upgrades. Giving users the ability to store and replay select content could further expand the scope of applications.

3GPP defined highly efficient broadcast/multicast capabilities for UMTS in Release 6 with MBMS. Release 7 defined optimizations through a feature called multicast/broadcast, single-frequency network operation that involves simultaneous transmission of the exact waveform across multiple cells. This enables the receiver to constructively superpose multiple MBMS Single Frequency Network (SFN), or MBSFN, cell transmissions. The result is highly efficient, WCDMA-based broadcast transmission technology that matches the benefits of OFDMA-based broadcast approaches.

LTE also has a broadcast/multicast capability called eMBMS. OFDM is particularly well suited for efficient broadcasting, as shown in Figure 103, because the mobile system can combine the signal from multiple base stations, also an MBSFN approach, and because of the narrowband nature of OFDM. Normally, these signals would interfere with one another. The single frequency network is a cluster of cells that transmit the same content synchronously with a common carrier frequency.

Figure 103: OFDM Enables Efficient Broadcasting


Symbol Time T ~ 100 µs
time
Cyclic Prefix
Useful Symbol Time
Identical signals transmitted
time
Note: dashed lines represent multipath
Note: All signals & multipath over a useful symbol time are from the same symbol & add constructively
Base 1
Base 2
time

Despite various broadcast technologies being available, market adoption to date has been relatively slow. Internet trends have favored unicast approaches, with users viewing videos of their selection on demand, but there is increasing interest in using eMBMS with LTE to alleviate capacity demands.

Backhaul

Connecting sites to core networks remains a challenge, whether for small cells or macro cells, especially as networks need to deliver higher bandwidth. Fiber is the gold standard, but it is not available everywhere and can be expensive, so operators use a combination of wired and wireless links.

Today's backhaul requirements for LTE can range from 1 to 10 Gbps. By 2020, backhaul requirements could exceed 10 Gbps.[200]

Table 29 and Table 30 summarize the methods and capabilities of the various available approaches.

Table 29: Wired Backhaul Methods and Capabilities[201]

Technology	Distance	Throughput Speed
Direct Fiber	80 km	Hundreds of Mbps to Gbps
Bonded VDSL2	To 5,000 feet	75 Mbps down, 12 Mbps up
FTTX	Most urban areas	Up to 2.5 Gbps down, 1.5 Gbps up
DOCSIS	Most urban areas	Up to 285 Mbps down, 105 Mbps up

Table 30: Wireless Backhaul Methods and Capabilities[202]

Technology	Distance	Line-of-Sight	Throughput Speed
5G Integrated Access and Backhaul	1 km	Yes	1 to 10 Gbps
Millimeter Wave (60 GHz)	1 km	Yes	1 Gbps
Millimeter Wave (70-80 GHz)	3 km (with speed tradeoff)	Yes	10 Gbps
Microwave (6-60 GHz)	Varies by frequency: 2-4 km typical at 30-42 GHz	Yes	1 Gbps+

---

[200] Arthur D. Little, *Creating a Gigabit Society – The Rule of 5G; A report by Arthur D. Little for Vodafone Group*, 2017. See Figure 6.

[201] Small Cell Forum, "Backhaul Technologies for Small Cells," February 2013.

[202] Ibid.

Technology	Distance	Line-of-Sight	Throughput Speed
Licensed sub 6 GHz	1.5 to 10 km	No	170 Mbps (20 MHz TDD), 400 Mbps+ with new technology
Unlicensed sub-6 GHz	Up to 250 meters	No	450 Mbps (IEEE 802.11n 3X3 MIMO)
TV White Space (802.11af-based)	1 to 5 km max throughput, 10 km+ possible	Depends on deployment model	80 Mbps in 6 MHz TDD with 4X4 MIMO
Satellite	Available everywhere	Yes	Up to 50 Mbps downlink, 15 Mbps uplink

UMTS-HSPA

UMTS technology is mature and benefits from research and development that began in the early 1990s. It has been thoroughly trialed, tested, and commercially deployed. UMTS employs a wideband CDMA radio-access technology. The primary benefits of UMTS include high spectral efficiency for voice and data, simultaneous voice and data capability, high user densities that can be supported with low infrastructure costs, and support for high-bandwidth data applications. Operators can also use their entire available spectrum for both voice and high-speed data services.

Additionally, operators can use a common core network, called the UMTS multi-radio network as shown in Figure 104, which supports multiple radio-access networks including GSM, EDGE, WCDMA, HSPA, and evolutions of these technologies.

Figure 104: UMTS Multi-radio Network


Radio-Access Networks
External Networks
GSM/EDGE
WCDMA, HSPA
Other e.g., WLAN
UMTS/HSPA Core Network (MSC, HLR, SGSN, GGSN)
Packet-Switched Networks
Circuit-Switched Networks
Other Cellular Operators
Rysavy Research

HSPA refers to networks that support both HSDPA and HSUPA. All new deployments today are HSPA, and many operators have upgraded their HSDPA networks to HSPA. For example, in 2008, AT&T upgraded most of its network to HSPA. By the end of 2008, HSPA was deployed throughout the Americas.

The UMTS radio-access network consists of base stations referred to as Node B (corresponding to GSM base transceiver systems) that connect to RNCs (corresponding to GSM base station controllers [BSCs]). The RNCs connect to the core network as do the BSCs. When both GSM and WCDMA access networks are available, the network can hand users over between these networks. This is important for managing capacity, as well as in areas in which the operator has continuous GSM coverage, but has only deployed WCDMA in some locations.

Whereas GSM can effectively operate like a spread-spectrum system[203], based on time division in combination with frequency hopping, WCDMA is a direct-sequence, spread-spectrum system. WCDMA is spectrally more efficient than GSM, but it is the wideband nature of WCDMA that provides its greatest advantage—the ability to translate the available spectrum into high data rates. This wideband technology approach results in the flexibility to manage multiple traffic types including voice, narrowband data, and wideband data.

HSDPA

HSDPA, specified in 3GPP Release 5, saw the introduction of high-performance, packet data service that delivers peak theoretical rates of 14 Mbps. Peak user-achievable throughput rates in initial deployments are well over 1 Mbps and as high as 4 Mbps in some networks. The same radio carrier can simultaneously service UMTS voice and data users, as well as HSDPA data users.

HSDPA achieves its high speeds through techniques similar to those that push EDGE performance past GPRS including higher order modulation, variable coding, and soft combining, as well as through the addition of fast scheduling and other techniques.

HSDPA achieves its performance gains from the following radio features:

- High-speed channels shared in both code and time domains
- Short TTI
- Fast scheduling and user diversity
- Higher order modulation
- Fast link adaptation
- Fast HARQ

These features function as follows:

High-Speed Shared Channels and Short Transmission Time Interval: First, HSDPA uses high-speed data channels called “High Speed Physical Downlink Shared Channels” (HS-PDSCH). Up to 15 of these channels can operate in the 5 MHz WCDMA radio channel. Each uses a fixed spreading factor of 16. User transmissions are assigned to one or more of these channels for a short TTI of 2 msec. The network can then readjust how users are assigned to different HS-PDSCH every 2 msec. Resources are thus assigned in both time

---

[203] Spread spectrum systems can either be direct sequence or frequency hopping.

(the TTI interval) and code domains (the HS-PDSCH channels). Figure 105 illustrates different users obtaining different radio resources.

Figure 105: High Speed–Downlink Shared Channels (Example)



Fast Scheduling and User Diversity: Fast scheduling exploits the short TTI by assigning users channels that have the best instantaneous channel conditions, rather than in a round-robin fashion. Because channel conditions vary somewhat randomly across users, most users can be serviced with optimum radio conditions and thereby obtain optimum data throughput. Figure 106 shows how a scheduler might choose between two users based on their varying radio conditions to emphasize the user with better instantaneous signal quality. With about 30 users active in a sector, the network achieves significant user diversity and much higher spectral efficiency. The system also ensures that each user receives a minimum level of throughput, an approach called proportional fair scheduling.

Figure 106: User Diversity



Higher Order Modulation: HSDPA uses both the modulation used in WCDMA—namely QPSK—and, under good radio conditions, an advanced modulation scheme—16 QAM. 16 QAM transmits 4 bits of data in each radio symbol compared to 2 bits with QPSK. Data throughput is increased with 16 QAM, while QPSK is available for adverse radio conditions. HSPA Evolution adds 64 QAM modulation to further increase throughput rates. 64 QAM became available in Release 7, and the combination of MIMO and 64 QAM became available in Release 8.

Fast Link Adaptation: Depending on the condition of the radio channel, different levels of forward-error correction (channel coding) can also be employed. For example, a three-quarter coding rate means that three quarters of the bits transmitted are user bits, and one quarter are error-correcting bits. Fast link adaptation refers to the process of selecting and quickly updating the optimum modulation and coding rate and occurs in coordination with fast scheduling.

Fast Hybrid Automatic Repeat Request: Another HSDPA technique is Fast Hybrid Automatic Repeat Request (Fast Hybrid ARQ). “Fast” refers to the medium-access control mechanisms implemented in Node B (along with scheduling and link adaptation), as opposed to the BSC in GPRS/EDGE, and “hybrid” refers to a process of combining repeated data transmissions with prior transmissions to increase the likelihood of successful decoding. Managing and responding to real-time radio variations at the base station, as opposed to an internal network node, reduces delays and further improves overall data throughput.

Using the approaches just described, HSDPA maximizes data throughputs and capacity and minimizes delays. For users, this translates to better network performance under loaded conditions, faster application performance, and a greater range of applications that function well.

Field results validate the theoretical throughput results. With initial 1.8 Mbps peak rate devices, vendors measured consistent throughput rates in actual deployments of more than 1 Mbps. These rates rose to more than 2 Mbps for 3.6 Mbps devices and then close to 4 Mbps for 7.2 Mbps devices.

In 2008, typical devices supporting peak data rates of 3.6 Mbps or 7.2 Mbps became available. Many operator networks support 7.2 Mbps peak operation, and some even support the maximum rate of 14.4 Mbps.

HSUPA

Whereas HSDPA optimizes downlink performance, HSUPA—which uses the Enhanced Dedicated Channel (E-DCH)—constitutes a set of improvements that optimizes uplink performance. Networks and devices supporting HSUPA became available in 2007. These improvements include higher throughputs, reduced latency, and increased spectral efficiency. HSUPA was standardized in Release 6. It results in an approximately 85% increase in overall cell throughput on the uplink and more than a 50% gain in user throughput. HSUPA also reduces packet delays, a significant benefit resulting in much improved application performance on HSPA networks

Although the primary downlink traffic channel supporting HSDPA serves as a shared channel designed for the support of services delivered through the packet-switched domain, the primary uplink traffic channel defined for HSUPA is a dedicated channel that could be used for services delivered through either the circuit-switched or the packet-switched domains. Nevertheless, by extension and for simplicity, the WCDMA-enhanced uplink capabilities are often identified in the literature as HSUPA.

HSUPA achieves its performance gains through the following approaches:

- An enhanced dedicated physical channel.
- A short TTI, as low as 2 msec, which allows faster responses to changing radio conditions and error conditions.
- Fast Node B-based scheduling, which allows the base station to efficiently allocate radio resources.
- Fast Hybrid ARQ, which improves the efficiency of error processing.

The combination of TTI, fast scheduling, and Fast Hybrid ARQ also serves to reduce latency. HSUPA can operate with or without HSDPA in the downlink, although use the two approaches together. The improved uplink mechanisms also translate to better coverage and, for rural deployments, larger cell sizes.

HSUPA can achieve different throughput rates based on various parameters including the number of codes used, the spreading factor of the codes, the TTI value, and the transport block size in bytes.

Initial devices enabled peak user rates of close to 2 Mbps as measured in actual network deployments, while current devices have throughputs of more than 5 Mbps. Future devices could have network rates as high as 69 Mbps, as discussed further below.

Beyond throughput enhancements, HSUPA also significantly reduces latency.

Evolution of HSPA (HSPA+)

The goal in evolving HSPA is to exploit available radio technologies—largely enabled by increases in digital signal processing power—to maximize CDMA-based radio performance. This evolution has significantly advanced HSPA and extends the life of sizeable operator infrastructure investments.

Wireless and networking technologists have defined a series of enhancements for HSPA, beginning in Release 7 and now continuing through Release 14. These include advanced receivers, multi-carrier operation, MIMO, Continuous Packet Connectivity, Higher-Order Modulation, One-Tunnel Architecture, HetNet support, and advanced voice capabilities both in circuit- and packet-switched domains.

Taking advantage of these various radio technologies, 3GPP has standardized a number of features, beginning in Release 7 including higher order modulation and MIMO. Collectively, these capabilities are referred to as HSPA+. Release 8 through Release 12 include further enhancements.

The goals of HSPA+ were to:

- ☐ Exploit the full potential of a CDMA approach.
- ☐ Provide smooth interworking between HSPA+ and LTE, thereby facilitating the operation of both technologies. As such, operators may choose to leverage the EPC planned for LTE.
- ☐ Allow operation in a packet-only mode for both voice and data.
- ☐ Be backward-compatible with previous systems while incurring no performance degradation with either earlier or newer devices.
- ☐ Facilitate migration from current HSPA infrastructure to HSPA+ infrastructure.

HSPA improvements have continued through successive 3GPP releases, including Release 14, which has downlink interference mitigation. Release 15 has work items for quality of experience, multi-carrier enhancements, and various protocol enhancements.

The following sections discuss specific enhancements that have already been implemented in HSPA.

Advanced Receivers

3GPP has specified a number advanced-received designs including: Type 1, which uses mobile-receive diversity; Type 2, which uses channel equalization; and Type 3, which includes a combination of receive diversity and channel equalization. Type 3i devices, which became available in 2012, employ interference cancellation. Note that the different types of receivers are release-independent. For example, Type 3i receivers will work and provide a capacity gain in an earlier Release 5 network.

The first approach is mobile-receive diversity. This technique relies on the optimal combination of received signals from separate receiving antennas. The antenna spacing yields signals that have somewhat independent fading characteristics. Hence, the combined signal can be more effectively decoded, which almost doubles downlink capacity when done in combination with channel equalization. Receive diversity is effective even with smaller devices such as like PC Card modems and smartphones.

Current receiver architectures based on rake receivers are effective for speeds up to a few megabits per second. But at higher speeds, the combination of reduced symbol period and multipath interference results in Intersymbol Interference and diminishes rake receiver performance. This problem can be solved by advanced-receiver architectures with channel equalizers that yield additional capacity gains over HSDPA with receive diversity. Alternate advanced-receiver approaches include interference cancellation and generalized rake receivers (G-Rake). Different vendors are emphasizing different approaches. The performance requirements for advanced-receiver architectures, however, were specified in 3GPP Release 6. The combination of mobile-receive diversity and channel equalization (Type 3) is especially attractive, because it results in a large capacity gain independent of the radio channel.

What makes such enhancements attractive is that the networks do not require any changes other than increased capacity within the infrastructure to support the higher bandwidth. Moreover, the network can support a combination of devices including both earlier devices that do not include these enhancements and later devices that do. Device vendors can selectively apply these enhancements to their higher-end devices.

MIMO

Another standardized capability is MIMO, a technique that employs multiple transmit antennas and multiple receive antennas, often in combination with multiple radios and multiple parallel data streams. The most common use of the term “MIMO” applies to spatial multiplexing. The transmitter sends different data streams over each antenna. Whereas multipath is an impediment for other radio systems, MIMO—as illustrated in Figure 107—actually exploits multipath, relying on signals to travel across different uncorrelated communications paths. The multiple data paths effectively operate in parallel and, with appropriate decoding, in a multiplicative gain in throughput.

Figure 107: MIMO Using Multiple Paths to Boost Throughput and Capacity



Rysavy Research

Tests of MIMO have proven effective in WLANs operating in relative isolation where interference is not a dominant factor. Spatial multiplexing MIMO can also benefit HSPA “hotspots” serving local areas including airports, campuses, and malls. In a fully loaded network with interference from adjacent cells, however, overall capacity gains will be more modest—in the range of 20% to 33% over mobile-receive diversity. Relative to a 1x1 antenna system, however, 2X2 MIMO can deliver cell throughput gains of about 80%. 3GPP has standardized spatial multiplexing MIMO in Release 7 using Double Transmit Adaptive Array (D-TxAA).

Release 9 provides for a means to leverage MIMO antennas at the base station when transmitting to user equipment that does not support MIMO. The two transmit antennas in the base station can transmit a single stream using beam forming. This is called "single stream MIMO" or "MIMO with single-stream restriction" and results in higher throughput rates because of the improved signal received by the user equipment.

3GPP designed uplink dual-antenna beamforming and 2X2 MIMO for HSPA+ in Release 11.

Continuous Packet Connectivity

Continuous Packet Connectivity (CPC) specified in Release 7 reduces the uplink interference created by the dedicated physical control channels of packet data users when those channels have no user data to transmit, which increases the number of simultaneously connected HSUPA users. CPC allows both discontinuous uplink transmission and discontinuous downlink reception, wherein the modem can turn off its receiver after a certain period of HSDPA inactivity. CPC is especially beneficial to VoIP on the uplink because the radio can turn off between VoIP packets, as shown in Figure 108.

Figure 108: Continuous Packet Connectivity



Higher Order Modulation

Another way of increasing performance is with higher order modulation. HSPA uses 16 QAM on the downlink and QPSK on the uplink, but HSPA+ adds 64 QAM to the downlink and 16 QAM to the uplink. 3GPP has also introduced 64 QAM to the uplink for HSPA+ in Release 11. Higher order modulation requires a better SNR, achieved through receive diversity and equalization.

Multi-Carrier HSPA

3GPP defined dual-carrier HSPA operation in Release 8, which coordinates the operation of HSPA on two adjacent 5 MHz carriers so that data transmissions can achieve higher throughput rates, as shown in Figure 109. The work item assumed two adjacent carriers, downlink operation and no MIMO. This configuration achieves a doubling of the 21 Mbps maximum rate available on each channel to 42 Mbps.

Figure 109: Dual-Carrier Operation with One Uplink Carrier[204]



Benefits include:

- An increase in spectral efficiency of about 15%, comparable to what can be obtained with 2X2 MIMO.
- Significantly higher peak throughputs available to users, especially in lightly-loaded networks.
- Same maximum-throughput rate of 42 Mbps as using MIMO, but with a less expensive infrastructure upgrade.

Scheduling packets across two carriers is a more efficient use of resources, resulting in what is called “trunking gain.” Multi-user diversity also improves from an increased number of users across the two channels.

Release 9 also supports dual-carrier operation in the uplink. Release 10 specifies the use of up to four channels, resulting in peak downlink data rates of 168 Mbps. Release 11 supports eight radio channels on the downlink, resulting in a further doubling of theoretical throughput to 336 Mbps. On the uplink, devices can transmit using two antennas for either rank 1 (single stream beamforming) or rank 2 (dual-stream MIMO) transmission modes. Rank 1 beamforming helps with coverage (approximately 40%), while rank 2 MIMO helps with throughput speeds (approximately 20% median and 80% at cell edge). In addition, 64 QAM will be possible on the uplink, enabling uplink speeds to 69 Mbps in dual-carrier operation.

Downlink Multiflow Transmission

Release 11 specifies means by which two cells can transmit to the mobile station at the same time. The two cells transmit independent data, in effect a spatial multiplexing approach, improving both peak and average data.

---

[204] Harri Holma and Antti Toskala, *LTE for UMTS, OFDMA and SC-FDMA Based Radio Access*, Wiley, April 2009.

Multiflow transmission with HSPA+ also enhances HetNet operation in which picocell coverage can be expanded within a macrocell coverage area, as shown in Figure 110.

Figure 110: HSPA+ HetNet Using Multipoint Transmission[205]


3.1X
1.6 X
1X
Macro, Dual-Carrier
4 Picos added
Range Expansion
Data Rate Improvement
Median downlink data rate
Range Expansion
Reduce second carrier Macro Power
CARRIER 2
Pico
Macro
CARRIER 1
Dual-Carrier Device

Multiflow enhances HSPA+ network operation using the following approaches:

- **Single Frequency Dual Cell.** The UE communicates with two different cells using the same frequency, improving cell-edge performance and providing network load balancing.
- **Dual Frequency Three Cell.** The UE communicates with two different cells using the same frequency. In addition, it communicates with one other cell on a different frequency.
- **Dual Frequency Four Cells.** The UE communicates using two instances of Single Frequency Dual Cell operation as described above.

In Release 12, 3GPP is considering the following enhancement to Multiflow operation, which is primarily targeted towards HetNet operation:

- **Dual Frequency Dual Carrier.** The UE aggregates cells on two different frequencies from two different sites.

HSPA+ Throughput Rates

Table 31 summarizes the capabilities of HSPA and HSPA+ based on the various methods discussed above.

---

[205] Qualcomm, "HSPA+ Advanced: Taking HSPA+ to the Next Level," February 2012, http://www.qualcomm.com/media/documents/hspa-advanced-taking-hspa-next-level-whitepaper, accessed June 20, 2014.

Table 31: HSPA Throughput Evolution

Technology	Downlink (Mbps) Peak Data Rate	Uplink (Mbps) Peak Data Rate
HSPA as defined in Release 6	14.4	5.76
Release 7 HSPA+ DL 64 QAM, UL 16 QAM, 5+5 MHz	21.1	11.5
Release 7 HSPA+ 2X2 MIMO, DL 16 QAM, UL 16 QAM, 5+5 MHz	28.0	11.5
Release 8 HSPA+ 2X2 MIMO DL 64 QAM, UL 16 QAM, 5+5 MHz	42.2	11.5
Release 8 HSPA+ (no MIMO) Dual Carrier, 10+5 MHz	42.2	11.5
Release 9 HSPA+ 2X2 MIMO, Dual Carrier DL and UL, 10+10 MHz	84.0	23.0
Release 10 HSPA+ 2X2 MIMO, Quad Carrier[206] DL, Dual Carrier UL, 20+10 MHz	168.0	23.0
Release 11 HSPA+ 2X2 MIMO DL and UL, 8 Carrier DL, Dual Carrier UL, 40+10 MHz	336.0	69.0

Release 13 enables aggregation of two UL carriers across bands.

Figure 111 shows the cumulative distribution function of throughput values in a commercially deployed Release 8 HSPA+ network in an indoor coverage scenario. The figure shows significant performance gains from higher-order modulation and MIMO.

---

[206] No operators have announced plans to deploy HSPA in a quad (or greater) carrier configuration. Three carrier configurations, however, have been deployed.

Figure 111: HSPA+ Performance Measurements Commercial Network (5+5 MHz)[207]



The figure shows a reasonably typical indoor scenario in a macro-cell deployment. Under better radio conditions, HSPA+ will achieve higher performance results.

Figure 112 shows the benefit of dual-carrier operation (no MIMO employed), which essentially doubles throughputs over single carrier operation.

---

[207] 5G Americas member company contribution.

Figure 112: Dual-Carrier HSPA+ Throughputs[208]



HSPA+ also has improved latency performance of as low as 25 msec and improved packet call setup time of below 500 msec.

Figure 113 summarizes the key capabilities and benefits of the features being deployed in HSPA+.

---

[208] 5G Americas member company contribution. 64 QAM.

Figure 113: Summary of HSPA Functions and Benefits[209]


Uplink DTX + downlink DRX
Lower UE power consumption
CS voice over HSPA, VoIP, WCDMA+
Higher voice capacity or more capacity for data
Downlink 64QAM, MIMO, and multi carrier
Higher downlink peak data rates and higher data capacity
Uplink 16QAM, MIMO, and dual carrier
Higher uplink peak data rates and higher data capacity
Het-net support, pico range expansion
Higher network capacity
High speed FACH, High speed RACH, FE-FACH
Lower latency = better response times
More efficient common channels = savings in channel elements
Flat architecture optimization
Fewer network elements

UMTS TDD and TD-SCDMA

Most WCDMA and HSDPA deployments are based on FDD, which uses different radio bands for transmit and receive. In the alternate TDD approach, transmit and receive functions alternate in time on the same radio channel. 3GPP specifications include a TDD version of UMTS, called “UMTS TDD.”

TDD does not provide any inherent advantage for voice functions, which need balanced links—namely, the same amount of capacity in both the uplink and the downlink. Many data applications, however, are asymmetric, often with the downlink consuming more bandwidth than the uplink. A TDD radio interface can dynamically adjust the downlink-to-uplink ratio accordingly, hence balancing both forward-link and reverse-link capacity. Note that for UMTS FDD, the higher spectral efficiency achievable in the downlink versus the uplink addresses the asymmetrical nature of average data traffic.

---

[209] 5G Americas member contribution.

The UMTS TDD specification also includes the capability to use joint detection in receiver-signal processing, which offers improved performance.

One consideration, however, relates to available spectrum. Various countries around the world including those in Europe, Asia, and the Pacific region have licensed spectrum available specifically for TDD systems. TDD is also a good choice for any spectrum that does not provide a duplex gap between forward and reverse links.

In the United States, there is limited spectrum specifically allocated for TDD systems, the major band being BRS at 2.5 GHz used by Clearwire for WiMAX and now LTE TDD.[210] UMTS TDD is not a good choice in FDD bands; it would not be able to operate effectively in both bands, thereby making the overall system efficiency relatively poor.

TDD systems require network synchronization and careful coordination between operators or guardbands, which may be problematic in certain bands.

There has not been widespread deployment of UMTS TDD.

Time Division Synchronous Code Division Multiple Access (TD-SCDMA) is one of the official 3G wireless technologies, mostly for deployment in China. Specified through 3GPP as a variant of the UMTS TDD System and operating with a 1.28 megachips per second (Mcps) chip rate versus 3.84 Mcps for UMTS TDD, TD-SCDMA's primary attribute is that it supports very high subscriber densities, making it a possible alternative for wireless local loops. TD-SCDMA uses the same core network as UMTS, and it is possible for the same core network to support both UMTS and TD-SCDMA radio-access networks.

Although there are no planned deployments in any country other than China, TD-SCDMA could theoretically be deployed anywhere unpaired spectrum is available—such as the bands licensed for UMTS TDD—assuming appropriate resolution of regulatory issues.

EDGE/EGPRS

Today, most GSM networks support EDGE, an enhancement to GPRS, which is the original packet data service for GSM networks.[211] GPRS provides a packet-based IP connectivity solution supporting a wide range of enterprise and consumer applications. GSM networks with EDGE operate as wireless extensions to the internet and give users internet access, as well as access to their organizations from anywhere. Peak EDGE user-achievable[212] throughput rates are up to 200 Kbps. Figure depicts the system architecture.

---

[210] The 1910-1920 MHz band targeted unlicensed TDD systems but has never been used.

[211] GSM technology also provides circuit-switched data services, which are not described in this paper since they are seldom used.

[212] "Peak user-achievable" means users, under favorable conditions of network loading and signal propagation, can achieve this rate as measured by applications such as file transfer. Average rates depend on many factors and will be lower than these rates.

Figure 114: GSM/GPRS/EDGE Architecture


Mobile Station
Mobile Station
Mobile Station
Base Transceiver Station
Base Transceiver Station
Base Station Controller
Circuit-Switched Traffic
Mobile Switching Center
Public Switched Telephone Network
Home Location Register
IP Traffic
GPRS/EDGE Data Infrastructure
Serving GPRS Support Node
Gateway GPRS Support Node
External Data Network (e.g., Internet)
Rysavy Research

EDGE is essentially the addition of a packet-data infrastructure to GSM. In fact, this same data architecture is preserved in UMTS and HSPA networks, and the data architecture is technically referred to as GPRS for the core-data function in all of these networks. The term GPRS may also be used to refer to the initial radio interface, now supplanted by EDGE. Functions of the data elements are as follows:

- ☐ The base station controller directs/receives packet data to/from the Serving GPRS Support Node (SGSN), an element that authenticates and tracks the location of mobile stations.
- ☐ The SGSN performs the types of functions for data that the Mobile Switching Center (MSC) performs for voice. Each serving area has one SGSN, and it is often collocated with the MSC.
- ☐ The SGSN forwards/receives user data to/from the Gateway GPRS Support Node (GGSN), which can be viewed as a mobile IP router to external IP networks. Typically, there is one GGSN per external network (for example, the internet). The GGSN also manages IP addresses, dynamically assigning them to mobile stations for their data sessions.

Another important element is the Home Location Register (HLR), which stores users' account information for both voice and data services. Of significance is that this same data architecture supports data services in GSM and in UMTS-HSPA networks, thereby simplifying operator network upgrades.

In the radio link, GSM uses radio channels of 200 kilohertz (kHz) width, divided in time into eight timeslots comprising 577 microseconds (μs) that repeat every 4.6 msec, as shown in Figure . The network can have multiple radio channels (referred to as transceivers) operating in each cell sector. The network assigns different functions to each timeslot such as the Broadcast Control Channel (BCCH), circuit-switched functions like voice calls or data calls, the optional Packet Broadcast Control Channel (PBCCH), and packet data channels. The network can dynamically adjust capacity between voice and data functions, and it can also reserve minimum resources for each service. This scheduling approach enables more data traffic when voice traffic is low or, likewise, more voice traffic when data traffic is low, thereby maximizing overall use of the network. For example, the PBCCH, which expands the capabilities of the normal BCCH, may be set-up on an additional timeslot of a Time Division Multiple Access (TDMA) frame when justified by the volume of data traffic.

Figure 115: Example of GSM/EDGE Timeslot Structure[213]



	0	1	2	3	4	5	6	7
Possible BCCH carrier configuration	BCCH	TCH	TCH	TCH	TCH	PDTCH	PDTCH	PDTCH
Possible TCH carrier configuration	PBCCH	TCH	TCH	PDTCH	PDTCH	PDTCH	PDTCH	PDTCH

BCCH: Broadcast Control Channel – carries synchronization, paging and other signalling information
TCH: Traffic Channel – carries voice traffic data; may alternate between frames for half-rate
PDTCH: Packet Data Traffic Channel – carries packet data traffic for GPRS and EDGE
PBCCH: Packet Broadcast Control Channel – additional signalling for GPRS/EDGE; used only if needed

EDGE offers close coupling between voice and data services. In most networks, while in a data session, users can accept an incoming voice call, which suspends the data session, and then resume their data session automatically when the voice session ends. Users can also receive SMS messages and data notifications[214] while on a voice call, as described below.

With respect to data performance, each data timeslot can deliver peak user-achievable data rates of up to about 40 Kbps. The network can aggregate up to five timeslots on the downlink and up to four timeslots on the uplink with current devices.

If multiple data users are active in a sector, they share the available data channels. As demand for data services increases, however, an operator can accommodate customers by assigning an increasing number of channels for data service that is limited only by that operator’s total available spectrum and radio planning.

EDGE is an official 3G cellular technology that can be deployed within an operator's existing 850, 900, 1800, and 1900 MHz spectrum bands. EDGE capability is now largely standard in new GSM deployments. A GPRS network using the EDGE radio interface is technically called an “Enhanced GPRS” (EGPRS) network, and a GSM network with EDGE capability is referred to as GSM Edge Radio Access Network (GERAN). EDGE has been an inherent part of GSM specifications since Release 99. It is fully backward-compatible with older GSM networks, meaning that GPRS devices work on EDGE networks and that GPRS and EDGE terminals can operate simultaneously on the same traffic channels.

Dual Transfer Mode (DTM) devices can simultaneously communicate voice and data. DTM is a 3GPP-specified technology that enables new applications like video sharing while providing a consistent service experience (service continuity) with UMTS. Typically, a DTM end-to-end solution requires only a software upgrade to the GSM/EDGE radio network. There are a number of networks and devices supporting DTM.

---

[213] 5G Americas member company contribution.

[214] Example: WAP notification message delivered via SMS.

A feature in Release 9 that applies to EDGE is the Enhanced Flexible Timeslot Assignment (EFTA), which allows for more efficient adaptation to varying uplink versus downlink transmission needs. The network allocates uplink and downlink timeslots that overlap in time, and the mobile station may either use the corresponding uplink timeslots for transmission or receive on the overlapping downlink time slot, if it has nothing to transmit. In addition, alternative EFTA multi-slot classes enable the support of as many as eight timeslots per downlink carrier (instead of five or six timeslots with multi-slot classes 30 to 45).

Abbreviations and Acronyms

The following abbreviations are used in this paper. Abbreviations are defined on first use.

1G – First Generation
1xEV-DO – One Carrier Evolution, Data Optimized
1xEV-DV – One Carrier Evolution, Data Voice
1XRTT – One Carrier Radio Transmission Technology
2G – Second Generation
3G – Third Generation (meeting requirements set forth by the ITU IMT project)
3GPP – Third Generation Partnership Project
3GPP2 – Third Generation Partnership Project 2
4G – Fourth Generation (meeting requirements set forth by the ITU IMT-Advanced project)
5GC – 5G Core
8-PSK – Octagonal Phase Shift Keying
AAS – Adaptive Antenna Systems
ABR – Allocation Retention Priority
AGW – Access Gateway
AMF – Access and Mobility Management Function
AMR – Adaptive Multi Rate
AMR-WB – Adaptive Multi-Rate Wideband
ANDSF – Access Network Discovery and Selection Function.
ANSI – American National Standards Institute
APCO – Association of Public Safety Officials
API – Application Programming Interface
APN – Access Point Name
ARP – Allocation Retention Priority
ARPU – Average Revenue per User
ARQ – Automatic Repeat Request
ATM – Asynchronous Transfer Mode
AWGN – Additive White Gaussian Noise Channel
AWS – Advanced Wireless Services
BCCH – Broadcast Control Channel
bps – bits per second
BRS – Broadband Radio Service
BSC – Base Station Controller
BTS – Base Transceiver Station
C/I – Carrier to Intermodulation Ratio
CAPEX- Capital Expenditure
CBF – Coordinated Beam Forming
CBRS – Citizens Broadband Radio Service

CBS – Coordinated Beam Switching
CSS3 – Cascading Style Sheets 3 (CSS3)
CDD – Cyclic Delay Diversity
CDF – Cumulative Distribution Function
CDMA – Code Division Multiple Access
CL – Closed Loop
CL-SM – Closed Loop Spatial Multiplexing
CMAS – Commercial Mobile Alert System
CMOS – Complementary Metal Oxide Semiconductor
CoMP – Coordinated Multi Point
cMTC – Critical Machine Type Communications
CP – Cyclic Prefix
CPC – Continuous Packet Connectivity
CPRI – Common Public Radio Interface
CQI - Channel Quality Indicators
C-RAN – Cloud Radio Access Network
CRM – Customer Relationship Management
CRS – Cell-specific Reference Signal
CS – Convergence Sublayer
CSFB – Circuit-Switched Fallback
CTIA – Cellular Telephone Industries Association
C-V2X – Cellular Vehicle-to-X
D-AMPS – Digital Advanced Mobile Phone Service
DAS – Distributed Antenna System
DAS – Downlink EGPRS2-A Level Scheme
dB – Decibel
DBS – Downlink EGPRS2-B Level Scheme
DC-HSPA – Dual Carrier HSPA
DFT – Discrete Fourier Transform
DL – Downlink
DNS – Domain Name Service
DPCCH – Dedicated Physical Control Channel
DPS – Dynamic Point Selection
DSL – Digital Subscriber Line
DSMIPv6 – Dual Stack Mobile IPv6
DTM – Dual Transfer Mode
DRX – Discontinuous Reception
D-TxAA – Double Transmit Adaptive Array
DVB-H – Digital Video Broadcasting Handheld

E-DCH – Enhanced Dedicated Channel
EBCMCS – Enhanced Broadcast Multicast Services
EC-GSM – Extended Coverage GSM
eCoMP – enhanced CoMP
EDGE – Enhanced Data Rates for GSM Evolution
EFTA – Enhanced Flexible Timeslot Assignment
EGPRS – Enhanced General Packet Radio Service
eICIC – Enhanced Inter-Cell Interference Coordination
eMBMS – Enhanced Multimedia Broadcast Multicast Services
eNodeB – Evolved Node B
EAP – Extensible Authentication Protocol
eLAA – Enhanced Licensed-Assisted Access
eNB – Evolved Node B
EPC – Evolved Packet Core
EPDCCH – Enhanced Physical Downlink Control Channel
eMBB – Enhanced Mobile Broadband
ePDG – Enhanced Packet Data Gateway
EPS – Evolved Packet System
ERP – Enterprise Resource Planning
eSaMOG – Enhanced S2a-based Mobility over GTP
ESC – Environmental Sensing Capability
eSRVCC – Enhanced Single-Radio Voice Call Continuity
ETRI – Electronic and Telecommunications Research Institute
ETSI – European Telecommunications Standards Institute
E-UTRAN – Enhanced UMTS Terrestrial Radio Access Network
EVS – Enhanced Voice Services (codec)
FE-FACH – Further Enhanced Forward Access Channel
EV-DO –Evolution, Data Optimized
EV-DV –Evolution, Data Voice
EVRC – Enhanced Variable Rate Codec
FBMC – Filter-Bank Multi-Carrier
FCC – Federal Communications Commission
FDD – Frequency Division Duplex
FeCoMP – Further Enhanced Coordinated Multi Point
feICIC – Further enhanced ICIC
FirstNet – First Responder Network Authority
Flash OFDM – Fast Low-Latency Access with Seamless Handoff OFDM
FLO – Forward-Link Only
FMC – Fixed Mobile Convergence

FP7 – Seventh Framework Programme

FTP – File Transfer Protocol

GAA – General Authorized Access

GAN – Generic Access Network

GB – Gigabyte

Gbps – Gigabits Per Second

GBR – Guaranteed Bit Rate

GByte – Gigabyte

GCS – Group Communication Service

GERAN – GSM EDGE Radio Access Network

GFDM – Generalized Frequency Division Multiplexing

GGSN – Gateway GPRS Support Node

GHz — Gigahertz

GMSK – Gaussian Minimum Shift Keying

gNB – NR NodeB

GPRS – General Packet Radio Service

G-Rake – Generalized Rake Receiver

GSM – Global System for Mobile Communications

GSMA – GSM Association

HARQ – Hybrid Automatic Repeat Request

HD – High Definition

HetNet – heterogeneous network

HLR – Home Location Register

Hr – Hour

HSDPA – High Speed Downlink Packet Access

HS-FACH – High Speed Forward Access Channel

HS-PDSCH - High Speed Physical Downlink Shared Channels

HS-RACH – High Speed Reverse Access Channel

HSPA – High Speed Packet Access (HSDPA with HSUPA)

HSPA+ – HSPA Evolution

HSS – Home Subscriber Server

HSUPA – High Speed Uplink Packet Access

Hz – Hertz

ICIC – Inter-Cell Interference Coordination

ICN – Information-Centric Networking

ICS – IMS Centralized Services

ICT – Information and Communication Technologies

IEEE – Institute of Electrical and Electronic Engineers

IETF – Internet Engineering Taskforce

IFFT – Inverse Fast Fourier Transform
IFOM – IP Flow and Seamless Offload
IM – Instant Messaging
IMS – IP Multimedia Subsystem
IMT – International Mobile Telecommunications
IMT-Advanced - International Mobile Telecommunications-Advanced
IRC – Interference Rejection Combining
IoT – Internet of Things
IPR - Intellectual Property Rights
IP – Internet Protocol
IPTV – Internet Protocol Television
IR – Incremental Redundancy
ISD – Inter-site Distance
ISI – Intersymbol Interference
ISP – Internet Service Provider
ITU – International Telecommunication Union
JCP – Java Community Process
JR – Joint Reception
JT – Joint Transmission
Kbps – Kilobits Per Second
kHz — Kilohertz
km – Kilometer
LAA – License-Assisted Access
LBT – Listen-Before-Talk
LDPC - Low-Density Parity Code
LIPA – Local IP Access
LMDS – Local Multipoint Distribution Service
LPWA – Low-Power Wide-Area
LTE – Long Term Evolution
LTE-A – LTE-Advanced
LTE-TDD – LTE Time Division Duplex
LTE-U – LTE-Unlicensed
LSTI – LTE/SAE Trial Initiative
LWA – LTE Wi-Fi Aggregation
LWIP – LTE WLAN Radio Level Integration with IPsec Tunnel
M2M – Machine-to-machine
MAC – Medium-Access Control
MAPCON – Multi-Access PDN Connectivity
MB - Megabyte

MBMS - Multimedia Broadcast/Multicast Service

Mbps – Megabits Per Second

MBR – Maximum Bit Rate

MBSFN – Multicast/broadcast, Single Frequency

MCPA – Mobile Consumer Application Platform

Mcps – Megachips Per Second

MCPTT – Mission-Critical Push-to-Talk

MCS – Modulation and Coding Scheme

MCW – Multiple Codeword

MDT – Minimization of Drive Tests

MEAP – Mobile Enterprise Application Platforms

MEC – Multi-access Edge Computing

MediaFLO – Media Forward Link Only

METIS – Mobile and wireless communications Enablers for the Twenty-twenty Information Society

MHz – Megahertz

MID – Mobile Internet Devices

MIMO – Multiple Input Multiple Output

MMSE – Minimum Mean Square Error

mITF – Japan Mobile IT Forum

MMDS – Multichannel Multipoint Distribution Service

MME – Mobile Management Entity

mMTC – Massive Machine Type Communications

MOS – Mean Opinion Score

MP-QUIC – Multipath Quick UDP Internet Connections

MP-TCP – Multipath TCP

MRxD – Mobile Receive Diversity

ms – millisecond

MS – Mobile Station

MSA – Mobile Service Architecture

MSC – Mobile Switching Center

MTC – Machine Type Communications

MTC-IWF – Machine-Type Communications Interworking Function (MTC-IWF)

msec – millisecond

MU-MIMO – Multi-User MIMO

MUST – Downlink Multiuser Superposition Transmission

NAICS – Network-Assisted Interference Cancellation and Suppression

NB-IoT – Narrowband Internet of Things

NENA – National Emergency Number Association

NGMC – Next Generation Mobile Committee

NGMN – Next Generation Mobile Networks Alliance
NG-RAN – New Generation Radio Access Network
NOMA – Non-Orthogonal Multiple Access
NR – New Radio
NTIA – National Telecommunications and Information Administration
OFDM – Orthogonal Frequency Division Multiplexing
OFDMA – Orthogonal Frequency Division Multiple Access
OL-SM – Open Loop Spatial Multiplexing
OMA – Open Mobile Alliance
ORI – Open Radio Equipment Interface
PA – Priority Access
PAL – Priority Access License
PAR – Peak to Average Ratio
PBCCH – Packet Broadcast Control Channel
PCH – Paging Channel
PCRF – Policy Control and Charging Rules Function
PCS – Personal Communications Service
PDCP – Packet Data Convergence Protocol
PDN – Packet Data Network
PGW – Packet Gateway
PHY – Physical Layer
PMI – Precoding Matrix Indication
PMIPv6 – Proxy Mobile IPv6
PNF – Physical Network Function
PoC – Push-to-Talk Over Cellular
PSH – Packet Switched Handover
PSK – Phase-Shift Keying
QAM – Quadrature Amplitude Modulation
QCI – Quality of Service Class Identifier
QLIC – Quasi-Linear Interference Cancellation
QoS – Quality of Service
QPSK – Quadrature Phase Shift Keying
QUIC – Quick UDP Internet Connections.
RAB – Radio Access Bearer
RAN – Radio Access Network
RCAF – RAN Congestion Awareness Function
RCLWI - RAN Controlled LTE WLAN Interworking
RCS – Rich Communications Suite
REST – Representational State Transfer

RF – Radio Frequency
RLC – Radio Link Control
RNC – Radio Network Controller
ROHC – Robust Header Compression
RRC – Radio Resource Control
RRH – Remote Radio Head
RRU – Remote Radio Unit
RTP – Real Time Transport Protocol
RTSP – Real Time Streaming Protocol
SAE – System Architecture Evolution
SaMOG – S2a-based Mobility over GTP
SAS – Spectrum Access System
SC-FDMA – Single Carrier Frequency Division Multiple Access
SCMA – Sparse Coded Multiple Access
SCRI – Signaling Connection Release Indication
SCW – Single Codeword
SDAP – Service Data Adaptation Protocol
SDMA – Space Division Multiple Access
SDN – Software-Defined Networking
SDP – Session Description Protocol
sec – Second
SFBA – Space Frequency Block Code
SFN – Single Frequency Network
SGSN – Serving GPRS Support Node
SGW – Serving Gateway
SIC – Successive Interference Cancellation
SIM – Subscriber Identity Module
SIMO – Single Input Multiple Output
SINR – Signal to Interference Plus Noise Ratio
SIP – Session Initiation Protocol
SIPTO – Selected IP Traffic Offload
SISO – Single Input Single Output
SMS – Short Message Service
SNR – Signal to Noise Ratio
SON – Self-Organizing Network
SPS – Semi-Persistent Scheduling
SRVCC – Single-Radio Voice Call Continuity
SU-MIMO – Single User MIMO
SVDO – Simultaneous 1XRTT Voice and EV-DO Data

SVLTE – Simultaneous Voice and LTE
TCH – Traffic Channel
TCP/IP – Transmission Control Protocol/IP
TD – Transmit Diversity
TDD – Time Division Duplex
TDMA – Time Division Multiple Access
TD-SCDMA – Time Division Synchronous Code Division Multiple Access
TD-CDMA – Time Division Code Division Multiple Access
TETRA – Terrestrial Trunked Radio
TIA/EIA – Telecommunications Industry Association/Electronics Industry Association
TISPAN – Telecoms and Internet Converged Services and Protocols for Advanced Networks
TSG-RAN – Technical Services Group Radio Access Network
TTI – Transmission Time Interval
UAS – Uplink EGPRS2-A Level Scheme
UBS – Uplink EGPRS2-B Level Scheme
UE – User Equipment
UFMC – Universal Filtered Multi-Carrier
UICC – Universal Integrated Circuit Card
UL – Uplink
UMA – Unlicensed Mobile Access
UMB – Ultra Mobile Broadband
UMTS – Universal Mobile Telecommunications System
UPCON – User-Plane Congestion Management
UPF – User Plane Function
URA-PCH – UTRAN Registration Area Paging Channel
URI – Uniform Resource Identifier
URLLC – Ultra-Reliable and Low Latency Communications
us – Microsecond
USIM – UICC SIM
UTRAN – UMTS Terrestrial Radio Access Network
V2X – vehicle -to-infrastructure
VAMOS – Voice Services over Adaptive Multi-User Channels on One Slot
VDSL – Very-High-Bit-Rate DSL
VEPC – Virtualized EPC
ViLTE – Video Over LTE
VoIP – Voice over Internet Protocol
VoHSPA – Voice over HSPA
VoLGA – Voice over LTE Generic Access
VoLTE – Voice over LTE

VNF- Virtual Network Function
VPN – Virtual Private Network
WAP – Wireless Application Protocol
WBA – Wireless Broadband Alliance
WCDMA – Wideband Code Division Multiple Access
WCS – Wireless Communication Service
WebRTC – Web Real-Time Communication
Wi-Fi – Wireless Fidelity
WiMAX – Worldwide Interoperability for Microwave Access
WLAN – Wireless Local Area Network
WMAN – Wireless Metropolitan Area Network
WMM – Wi-Fi Multimedia
WRC – World Radiocommunication Conference

Additional Information

5G Americas maintains market information, LTE deployment lists, and numerous white papers, available for free download on its web site: http://www.5gamericas.org.

If there are any questions regarding the download of this information, please call +1 425 372 8922 or e-mail Anushka Bishen, Public Relations Coordinator at info@5gamericas.org.

This white paper was written for 5G Americas by Rysavy Research (http://www.rysavy.com) and utilized a composite of statistical information from multiple resources.

The contents of this paper reflect the independent research, analysis, and conclusions of Rysavy Research and may not necessarily represent the comprehensive opinions and individual viewpoints of each particular 5G Americas Board member company.

Rysavy Research provides this document and the information contained herein to you for informational purposes only. Rysavy Research provides this information solely on the basis that you will take responsibility for making your own assessments of the information.

Although Rysavy Research has exercised reasonable care in providing this information to you, Rysavy Research does not warrant that the information is error-free. Rysavy Research disclaims and in no event shall be liable for any losses or damages of any kind, whether direct, indirect, incidental, consequential, or punitive arising out of or in any way related to the use of the information.

Copyright © 2017 Rysavy Research, LLC. All rights reserved.

http://www.rysavy.com

Select Language ▼

Robert P. Duncan A.B., S.M., M.B.A., Ph.D.: Government warfare and surveillance system architect, author, and independent investigator..

Presents

ASK ME ANYTHING ON REDDIT. POST QUESTION&VOTE UP. INDEFINITE Q&A. ALSO LATEST CLASSIFIED INFO.

SEE YOU AT NOVEMBER 5th 2017 WHITE HOUSE MMM!!!! BE THERE!

Project Soul Catcher Vol. 2: Secrets of Cyber and Cybernetic Warfare Revealed (click book image to buy)


Copyrighted Material
PROJECT: SOUL CATCHER
VOLUME TWO
Secrets of Cyber and Cybernetic Warfare Revealed
DECLASSIFIED
ROBERT DUNCAN
and The Mind Hacking Strategy Group
Copyrighted Material

Volume 2 details the CIA's practices of interrogation and cybernetic mind control in their pursuit to weaponize neuropsychology. It covers the art of bio-communication war. Human beings are complex machines but their inner workings have been deciphered. Mind control and brainwashing have been perfected in the last 60 years. Hacking computers and hacking into individual minds are similar. The 21st century will be known as the age of spiritual machines and soulless men.

Check out Dr. Robert Duncan's other book, How to Tame a Demon: A short practical guide to organized intimidation stalking, electronic torture, and mind control.

More information on Dr. Robert Duncan is available at drrobertduncan.com.

new SSL secure chat #targets

DRROBERTDUNCAN.COM GUEST BOOK & FORUM. PROFESS YOUR LOVE, DROP A LINE, SHARE YOUR STORY, WHATEVER.

Free eBook: The Matrix Deciphered by Dr. Robert Duncan, A.B., S.M., M.B.A., Ph.D., the book discloses secret details on government operations and gives a hint to what it's like to live like a victim targeted..

Bio of Dr. Robert Duncan, from his book The Matrix Deciphered:

"True nobility is exempt from fear".
– King Henry the Sixth, Part II (Act IV, Scene I).

> Call me The Saint. I am the all American - prep school, Harvard College graduating with honors in computer science and a minor in premedical studies, and advanced degrees from Harvard and Dartmouth in business and science. My famous ancestors are President Lincoln, King Duncan of Scotland, and Governor William Bradford, the first governor of Massachusetts.
>
> My research interests have been neural networks, virtual reality, and EEG controlled robotics. Before graduate school I worked for the Department of Defense, Navy, NATO, and various intelligence agencies computer science projects. I have done business consulting and computer consulting for the largest companies in the world. I have been a professor, inventor, artist, and writer. I am one of the last Renaissance men.
>
> My projects have included algorithms for Echelon and CIA natural language parsing and classification of document content, IRS formula for red flagging audits, writing the artificial intelligence code to automate tracking of the Soviet Nuclear Submarine Fleet and all water vessels, work integrating HAARP with SIGINT SIGCOM and SPAWAR. I have worked on projects for the Justice Department connecting local, state, and federal databases for the tracking of terrorists. I developed a system for the FBI to track license plates past toll booths and other locations. I worked on the soldier 2000 program to create body networks for reading vital signs and other information. A system I worked on called Snyper is operational in Iraq which triangulates on intercity conflict gun shots. I have been to a couple secret bases in the so called free world. I have developed telemedicine robotic surgery and virtual reality applications for the Army. For DARPA, I have worked on satellite computer vision target tracking applications and tank simulation as well as integration of the land, sea, and air surveillance systems like SOSSUS, towed arrays, and others.
>
> Projects that I have worked on outside of government contracts include my thesis on computer generated holography, a project making paralyzed people walk again using choreographed stimulated muscles movements, face recognition, voice identification and recognition, finger print recognition, and neural network robotic controller. My research interests moved to enhanced reality heads up displays and wearable computing systems. My current research involves finding a cure for the mind control directed energy weapons fiasco. The integrated global surveillance grid is actually part of the holy grail of weapons and human control systems.
>
> My apologies to the human race for my contribution to tyranny. I was tricked into thinking it would not be misused by corrupt government especially in my beloved country. I was wrong. The Joint Non-Lethal Weapons Directorate has Skip Green on the governing board. One of my old colleagues at a technology think tank in Cambridge partly in charge of the radio frequency weapons testing for neurological disruption now torturing and killing people worldwide. Several other US Navy and UK Navy scientists have been knocked-off and that is why I have come forward. I know my time maybe near. I am currently a professor in computer science and business, helping to educate the public on government corruption, greed, and stupidity. Like my ancestor Lincoln, I am fighting against mental slavery in a new Civil War engineered by the same useless elements in over 80 government agencies who have tested radiological, drug, and viral weapons on unsuspecting Americans for over 45 years.
>
> I have great pride in the fundamental and constitutional values of America and mean no disrespect by my blasting the incompetence, apathy, and stupidity of those involved in the conspiracy of involuntary biological, chemical, and psychotronic human effects testing. There are so many brave men and women serving in the armed forces who fight and protect us for the American values they believe in. But because of the silos of information called compartmentalization in the security agencies and the lack of accountability and oversight of black operations and some top secret projects, diabolical elements become rogue or worse destroying the very country they are tasked with protecting turning it into a hypocracy rather than a democracy.
>
> My goal is to awaken Americans to the continued horrific acts of military and CIA weapons testers in this country and the other branches of government’s inability to stop them and hold them accountable.
>
> All I ask from the reader is to listen to testimony and validate facts presented here and come to their own conclusion. Then fight to win back America from this silent overthrow. This has been my project for about two years, investigating government corruption, incompetence, and cover-up upon which I accidentally stumbled one day while looking at a reverse MRI scheme to inject electromagnetic signals into the brain for virtual reality applications. I have interviewed over two hundred people and worked on the highest level of military projects for the U.S., NATO, and U.K. and have given videotaped testimony to senators and representatives on this topic resulting in lip service since they have no real power to enforce. Two high level FBI agents and a couple CIA agents have come forward to validate the existence of a MKULTRA like project that continues to grab random people for mind control experimentation. Two of these have since become part of the program and endure daily psychotronic tortures. All the torture can be done using directed energy psychotronic weapons with the so called continental ballistic missile surveillance defense grids.
>
> I apologize to the human race for any contribution to these 4th generation weapons that I may have worked on that are more horrific than the nuclear bomb and whose cover-up is more pervasive than the Manhattan Project. And because of the horrific acts of violence being committed on as many as two thousand Americans as far as my research has uncovered and many others in other countries, I understand the extreme risk to my own welfare that publishing this material will have. But freedom is so important to me that I know full heartedly that the human race

must have an open discussion on these weapons to decide their own fate before the point of decision is gone, that I am willing to risk divulging so called national secrets. All I offer you is the truth.

All information presented in this book was received through legitimate channels such as the Freedom of Information Act, military documents, victim testimony, and turned agents. I still hold valid the oath I took to keep secret the details of the projects that I worked on under DoD budgets. The majority of the proceeds of this book will go towards helping the psychotronic experiment survivors and surviving families of those that have perished. When the government fails, business and the citizens must look out for each other.

Dr. Robert Duncan in Energy Weapons & Testing, Coast to Coast AM broadcast December 5th 2006 (2.75+ million listeners weekly, syndicated in most cities and areas of the United States, and other places around the world.)..



Download - Dr. Robert Duncan, Coast to Coast AM interview - Energy Weapons & Testing.

Energy Weapons & Testing synopsis:

Independent investigator Robert Duncan discussed directed energy and neurological weapons and his contention that they've been tested on the public at large. While directed energy is used in microwaves, to remove kidney stones, and in non-invasive surgery, it's also been developed extensively for military purposes, he reported.

The civilian population was targeted for experiments, in programs such as MK-ULTRA, starting after WW II, when Nazi scientists were imported to the US, some working on scalar or gravity weapons, said Duncan. The town of Taos, NM, where a hum was heard by many citizens, was the subject of a directed energy experiment by the U.S. Navy, he claimed. And most recently the Active Denial System (see article below) was tested on human subjects.

Duncan said he interviewed over 600 mind control victims (Dec 5th 2006 report), and found some validity to their allegations. There are weapons that can project voices into people's heads such as one system known as "The Voice of God," he detailed. Blocking techniques include jamming the signals with electronic scramblers, and using shields with metal alloys or mylar. He recommended the following websites for further information/assistance: mindjustice.org, raven1.net, freedomfchs.com.

The Goodbye Weapon

A new non-lethal weapon, the Air Force's Active Denial System, or ADS, has been certified for use in Iraq, after extensive testing. The ADS shoots a beam of waves that causes extreme (but temporary) pain and induces what experimenters call the "Goodbye effect," or "prompt and highly motivated escape behavior." Wired News obtained documents about the weapon and has published two reports (article(1)/documentation(2)). Additionally, the report's author David Hambling has posted a commentary(3) on the subject at Defense Tech.

1. http://www.wired.com/news/technology/0,72134-0.html
2. http://www.wired.com/news/technology/0,72236-0.html
3. http://www.defensetech.org/archives/003036.html

Coast to Coast AM guest bio:

Dr. Robert Duncan holds multiple degrees from Harvard University and Dartmouth College amongst others. He has had the most expensive American education money can buy. He is an investigator, author, and soon be movie producer on the topics of directed energy, neurological weapons, psychological, and information warfare. His movie is called "The Enemy Within - Psychic Warfare". A book he is co-authoring will be out in a few months called "Hacking the Human Mind".

Dr. Duncan has worked as a business and information technology consultant to the Fortune 500. He has worked for companies like Oracle Corporation, BEA systems, HP, BBN, and as a professor at a college. For the department of defense he has written the artificial intelligence code to track the Soviet nuclear submarine fleet with passive and active acoustical arrays and has been to a couple secret NATA Navy underground bases in Europe.

-Todd Giffen
Target since birth as I was born into American enslavement, surveillance, and control, under attack with directed energy since 2008
503-967-5202
case@oregonstatehospital.net
obamasweapon.com

Copyright © 2015 Todd Giffen

"The Use of Psychotronic Weapons"
"What everyone should know"

(courtesy : http://www.mindjustice.org/cherkova.htm)

Definition:

Definition of psychotronic (psycho-physical) weapons.

Psychotronic Weapons (PF- weapons) this is the totality of all possible methods and means (techno-genic, suggestive, pharmacological, paranormal, complexes, and others) of hidden, forced influences on the psyche of a person for the purpose of modifying his consciousness, behavior and health for what is desired in the way of influencing aspects of control..."

Second definition of psychotronic weapons (as an epigraph): "Applications in military and for antisocial purposes are possibilities also for knowledge of psychotronics, its means, methods, systems, 'generators', and there is the path for the transformation of the humanitarian, essential attributes of life and society in the weapons. These are also psychotronic weapons. This is not only dangerous, this is deadly!"

Types of Weapons:

- Electromagnetic Weapons
- Microwave Weapons
- Non-Lethal Weapons
- ELF (Extremely Low Frequency) Weapons
- Directed Energy Weapons
- Acoustic Weapons
- Psychotronic Weapons
- RF (Radio Frequency) Weapons
- Soft Kill Weapons
- Less-Than-Lethal Weapons

How it affects (Physical & psycho-physical damages):

Physical damage, visible results achieved at the moment of influence.

* burns, pricks, cuts, wounds (ray weapons, laser)
* bleeding into the brain (laser ray with energy pulses of 40 joules) and on the skin energy in pulses: 3 - 100 joules)
* Blindness in the eyes, loping of eyelashes (laser ray)
* loss of memory (influence of frequency of up to 100Hz. and a reduction to 5 Hz.)
* destruction of the vestibulary [inner ear] apparatus, spatial orientation
* symptoms of [***] [with a large exposure and strength, paralysis (UBCh) in the area of the beginning of the spinal column
* irregular sleeping, heart-beating
* numbness of the hands; at night, cramping of the legs
* sharp decrease in hemoglobin, micro-burns to the skin, ionization of the blood and body fluids, an increase in the deterioration rate of clothing material, photographic material [illuminating], (thermal-electronic emissions from lamps in the room with the feeding units of electrical networks and fittings of the wall, [...]
* vibrations (separate organs can vibrate: the heart, kidneys, etc.), [...] (from

* vibrational technologies)
* pressure, coolness of the skin
* feelings of non-specific fear and panic (from the weapons) [...] tremors, tapping, destruction of fragile objects from the waves, from the impulses and from other manifestations of technological poltergeist

Psycho-physical damage depending on intensity and duration of effects. Damage in the physical sphere (up to programmed premature death).

Stage I.

* changes in the blood (early signs)
* overheating substances especially and increase in crystallization, leading to cataracts (early sign)
* ill reactions along the path of the bio-energetic potential from the effects [...]
* prickly sensations, tremors to the muscles of the feet
* aggravation of chronic illnesses
* internal bleeding (nose, stomach, gynecological)
* auditory tones of various frequencies
* sharp pain in the internal ear
* dull pains in the area behind the ears
* internal trembling, vibrations
* head pain in the temple and a warmness in that area, pain in the eye-sockets
* likelihood of miscarriage, an increase of 80% for chances of premature births, anomalous
* development of the fetus, often with defective brains

Stage II.

* "radio-sound" effect (before this is long-conducted the resonance-loosening of spinal and brain fluids at the frequency of 2-10 Hz. for maintaining the fluids of theskull and brain in stimulation
* steady reactions to all aspects of coding
* lowering of energy (observed with irradiation at the frequency carrying frequencies of ~780 Hz.and amplitude modulation ~71 Hz.)
* aggravation of dermatosis
* eye pains (cataracts, asymmetry in lenses of the eyes, puffiness [?] of the retinas)
* aggravation of the course of chronic illnesses
* destruction of the functions of the kidneys, liver, organs of digestion, circulatory system, bleeding in gingivae, gums, peridontal and others
* gauntness
* "sand" in the eyes, burning sensation, loss of hair, brittleness of nails
* compression pain in the heart fits of coughing
* changes of the color of the face (bronze shading of the skin)
* asymmetrical puffiness of the face
* disfiguration of the face, the intentional emaciation of separate muscles, cartilage
* syndromes of destruction to the external nerves of the thighs
* impotence

Stage III.

* destruction of the brain, irreversible changes to the structure of the brain (academician V.P. Vekhtereva)

* irreversible processes in the muscle material, in the bones of the skull, and in the structures of neurons "..minimalization of life" --external reaction to EMP appears as an illness, up to heavy, sharp, chronic, organic pathological processes (academician V.P. Kaznacheev)
* "..the entire speeding up of the aging process, sclerosis, oncogenesis (academician V.P. Kaznacheev)
* destruction of bio-chemical processes in the cells with distrophic changes in the organs (academician V.P. Kaznacheev)
* destruction of the cell membranes, chemical connections in the cells -leading to leukemia, cancer of the brain and prostate gland, breast cancer, (even with weak EMP, but of long duration "...the genetic apparatus is altered..." (academician V.P. Kaznacheev)
* the reflex activities are destroyed
* the functioning of the hormonal system is destroyed
* [....] Parkinson's disease (trembling of the hands) and Alzheimer's disease (from changes in the production of the hormone melanin ([...] gland) that causes degenerative changes in substances at the molecular level disfunctions of the sino-atrial node of the heart (even with a low frequency)
* infarction, cerebral thrombosis, osteo-[***], peridontal, sugar diabetes
* allergies
* epilepsy (especially caused by the multiple-rapid stimulation by a weak, low frequency waves)
* hypertension, hypotension
* programmed or instantaneous (with the subjection to extreme effects -up to the border of deadly conditions) premature death --it is well known by the experimentors that cases of death do occur (academician V.P. Kaznacheev)
* a decrease and dying off of the population, humanity, mankind

Damage in the mental sphere (up to the point of insanity).
Stage I.

* manifestations of depression
* lowering in the interest in perceived information
* shortness of temper (irritability)

Stage II.

* steady depression
* lowering of abilities for analytical thinking, some worsening of the memory
* symptoms of chronic fatigue
* superficial nature of sleep
* higher incidents of conflicts

Stage III.

* confusion in the accounting of events in real life
* loss of ability for analytical thinking
* lowering and a loss of memory
* feelings of the lack of sleep
* indifference to personal external appearance [...]
* lowering of self-control from the deficit of the hormone seratonin due to SVCh irradiation
* suicide (as the experimentors "practice" provocation techniques)
* "...invisible weak fields ...their ignoring that they are carrying with them a deadly danger"... "...people simply start going crazy and nobody understands why..." (academician V.P. Kaznacheev)

"Consequences of effects of micro-leptonic generators are described by the leading developer in this area [from the] V. Lab. of Micro-leptonic Technologies D. Okhatryym: in 1982 there began extremely unpleasant things with the health our co-workers. At first, there arose their feeling unwell, then the loss of logic, then after this, the loss of spatial orientation. Finally, a breakdown of diseased [affected] organs. The coming out of this condition -and this includes myself -was achieved with great difficulty."

(in the book by Ju. Vorob'evskii" Knock at the Golden Gate, Moscow, 1999.

Manipulation with the memory.

* Erasure
* Blockage
* Recording of information needed by the experimentor
* training -"prompting" (after erasure)
* comparison,
* reproduction of picture a from a prior testing as though bifurcated [?]
* a shifting of the effective frequency up to 100 Hz. or a lowering to 5 Hz., with memory loss

Control of Stimulation in the brain.

* by states of consciousness (up to the loss of these)
* in sleep
* emotions
* intellectual capabilities
* attention
* speech
* activeness
* muscle tone
* stimulation of one and the same zone with stimulations of:
o 30 -40 mV- activization of attention, memory, movement;
o 60-70 mV- "emotiono-genic" effects

Different methods:

Types of Psychotronic, psychotropic and other Psy-Influences.

* radio-waves
* laser-irradiation
* infra-red irradiation
* ultra-violet irradiation UF
* x-ray irradiation
* gravitational fields
* torsional fields (hypothetical)
* leptonic and other fields

Acoustic Waves.

* infra-sonic (IZ) from 0 Hz. to 15-20 KHz.
* ultra-sonic(UZ) from 15-20 KHz. to 10**9 Hz. (ranges for IZ and UZ)

see more similar information in -Table 3

Formation of fields:

- electro-magnetic charge
- gravitational-mass
- torsional (surrounding spin fields) -spin, with any rotating body
- micro-leptonic energy (in free aspect) -[over-abundance of stable particles]?

Operator is secretly brought in, or in a secret installation nearby

BG: Biogenerator (could be tomography)
A: Antenna (irradiation and reception)
D: operator for the gathering of information, transmission and control
ZU: reminding sytem on a magnetic strip, holographic
BIP: bio-informational [...]
KC: channel connections (IK, radio, telephone, telegraph)
E: screen display
O: operator
SP: light pen with which the operator indicates on the screen, the point of influence

Stress systems and methods of harassment.

- slander
- gestures, hand movements, expressions, tests, practical "jokes"
- taking off what is needed for the eyes (vision) [?]
- psychological pressure through family, neighbors or surrounding people, vehicle drivers
- discrediting: along 5 directions (often with the involvement of the police)
  - irresponsibility
  - spy
  - drug dealer
  - vagrant
  - accomplice in a crime (in an alleged crime)
- torture, assault
- blackmail, threats
- attempts on their lives with PTOs
- death to someone close or in immediate surrounding life
- murder

Stages of Zombification (Substitution of consciousness with external control).

- programming, modeling of a cybernetic double
- conducting of programs according to non-differentiation of a proper and artificial "I"-"Not-I"
- extreme influencing, stress, harassment, irradiation, special-preparations [substances], chemicals
- taking to the limits of mental and physical capacities (survivability)
- loss of will, memory
- shutting off of his own consciousness
- replacement of consciousness with the control from his cybernetic twin

IDEAS
IN ORBIT
EXPLORE THE TECH
Raytheon

Did You Miss It? Get Breaking Defense Coverage Of SNA Symposium Here →

ACQUISITION, AIR, INTEL & CYBER

Pentagon Studies Weapons That Can Read Users' Mind

By SYDNEY J. FREEDBERG JR.
on July 14, 2017 at 3:15 PM
15 Comments

28
SHARES

NEWSEUM: The troops of tomorrow may be able to pull the trigger using only their minds. As artificially intelligent drones, hacking, jamming, and missiles accelerate the pace of combat, some of the military's leading scientists are studying how mere humans can keep up with the incredible speed of cyber warfare, missiles and other threats.

One option: Bypass crude physical controls — triggers, throttles, keyboards — and plug the computer directly into the human brain. In one DARPA experiment, a quadriplegic first controlled an artificial limb and then flew a flight simulator. Future systems might monitor the users' nervous system and compensate for stress, fatigue, or injury. Is this the path to what the Pentagon calls human-machine teaming?

This is an unnerving scenario for those humans, like Stephen Hawking, who mistrust artificial intelligence. If your nightmare scenario is robots getting out of control, "let's teach them to read our minds!" is probably *not* your preferred solution. It sounds more like the beginning of a movie where cyborg Arnold Schwarzenegger goes back in time to kill someone.

Navy X-47B drone.

But the Pentagon officials who talked up this research yesterday at Defense One's annual tech conference emphasized the objective was to *improve* human control over artificial intelligence. Teaching AI to monitor its user's level of stress, exhaustion, distraction, and so on helps the machine adapt itself to better serve the human — instead of the other way around. Teaching AI to instantly detect its user's *intention* to give a command, instead of requiring a relatively laborious push of a button, helps the human keep control — instead of having to let the AI off the leash because no human can keep up with it.

Official Defense Department policy, as then-Secretary Ash Carter put it, is that the US will "never" allow an artificial intelligence to decide for itself whether or not to kill a human being. However, no less a figure than the Carter's undersecretary of acquisition and technology, Frank Kendall, fretted publicly that making our robots wait for human permission would slow them down so much that enemy AI without such constraints would beat us. Vice-Chairman of the Joint Chiefs, Gen. Paul Selva, calls this the "Terminator Conundrum." Neuroscience suggests a way out of this dilemma: Instead of slowing the AIs down, make the humans' orders come faster.

DARPA's Revolutionizing Prosthetics program is devising new kinds of artificial limbs — and new ways to control them.

Accelerate Humanity

"We will continue to have humans on the loop, we will have human input in decisions, but the way we go about that is going to have to shift, just to cope with the speed and the capabilities that autonomous systems bring," said Dr. James Christensen, portfolio manager at the Air Force Research Laboratory's 711th Human Performance Wing. "The decision cycle with these systems is going to be so fast that they have to be sensitive to and responsive to the state of the individual (operator's) *intent*, as much as overt actions and control inputs that human's providing."

In other words, instead of the weapon system responding to the human operator *physically* touching a control, have it respond to the human's brain cells forming the *intention* to use a control. "When you start to have a direct neural interface of this type, you don't necessarily need to command and control the aircraft using the stick," said Justin Sanchez, director of DARPA's Biological Technologies Office. "You could potentially re-map your neural signatures onto the different control surfaces" — the tail, the flaps — "or maybe any other part of the aircraft" — say landing gear or weapons. "That part hasn't really been explored in a huge amount of depth yet."

Reading minds, even in this limited fashion, will require deep understanding and close monitoring of the brain, where thoughts take measurable form as electrical impulses running from neuron to neuron. "Can we develop precise neurotechnologies that can go to those circuits in the brain or the peripheral nervous system in real time?" Sanchez asked aloud. "Do we have computational systems that allow us to understand what the changes in those signals (mean)? And can we give meaningful feedback, either to the person or to the machine to help them to do their job better?"

DARPA's Revolutionizing Prosthetics program hooked up the brain of a quadriplegic — someone who could move neither arms nor legs — to a prosthetic arm, allowing the patient to control it directly with their thoughts. Then, "they said, 'I'd like to try to fly an airplane,'" Sanchez recounted. "So we created a virtual flight simulator for this person, allowed this neural interface to interface with the virtual aircraft, and that person flew."

"That was a real wake-up call for everybody involved," Sanchez said. "We didn't initially think you could do that."

timesofindia
May
21
19:40
100%
21 Tuesday May 2013

Tony Stark (Robert Downey Jr.) relies on the JARVIS artificial intelligence — exquisitely adapted to his personal strengths and weaknesses — to help pilot his Iron Man suit. (Marvel Comics/Paramount Pictures)

Adapting To The Human

Applying direct neural control to real aircraft — or tanks, or ships, or network cybersecurity systems — will require a fundamental change in design philosophy. Today, said Christensen, we give the pilots tremendous information on the aircraft, then expect them to adapt to it. In the future, we could give the aircraft tremendous information on its pilots, then have it use artificial intelligence to adapt itself to *them*. The AI could customize the displays, the controls, even the mix of tasks it took on versus those it left up to the humans — all exquisitely tailored not just to the preferences of the individual operator but to his or her current mental and physical state.

When we build planes today, "they're incredible sensor platforms that collect data on the world around them and on the aircraft systems themselves, (but) at this point, very little data is being collected on the pilot," Christensen said. "The opportunity there with the technology we're trying to build now is to provide a continuous monitoring and assessment capability so that the aircraft knows the state of that individual. Are they awake, alert, conscious, fully capable of performing their role as part of this man-machine system? Are there things that the aircraft then can do? Can it unload gees (i.e. reduce g-forces)? Can it reduce the strain on the pilot?"

Air Force MQ-9 Reaper operators in training. Today's drones require extensive human oversight and are hardly user friendly.

"This kind of ability to sense and understand to the state and the capabilities of the human is absolutely critical to the successful employment of highly automated systems," Christensen said. "The way all of our systems are architected right now, they're fixed, they're predictable, they're deterministic" — that is, any given input always produces the exact same output.

Predictability has its advantages: "We can train to that, they behave in very consistent ways, it's easier to test and evaluate," Christensen said. "What we lose in that, though is the real power of highly automated systems, autonomous systems, as *learning systems*, of being able to adapt themselves. "

"That adaptation, though, it creates unpredictability," he continued. "So the human has to adapt alongside the system, and in order to do that, there has to be some mutual awareness, right, so the human has to understand what is the system doing, what is it trying to do, why is that happening; and vice versa, the system has to has some understanding of the human's intent and also their state and capabilities."

This kind of synergy between human and artificial intelligence is what some theorists refer to as the "centaur," after the mythical creature that combined human and horse — with the human part firmly in control, but benefiting from the beast's strength and speed. The centaur concept, in turn, lies at the heart of the Pentagon's ideas of human-machine teaming and what's known as the Third Offset, which seeks to counter (offset) adversaries' advancing technology with revolutionary uses of AI.

The neuroscience here is in its infancy. But it holds the promise of a happy medium between hamstringing our robots with too-close control or letting them run rampant.

28
SHARES

Topics: AFRL, air force, Air Force Research Laboratory AFRL, artificial intelligence, darpa, DefenseOne Tech Summit 2017, James Christensen, Justin Sanchez, neuroscience, offset strategy, War Algorithm

SPONSORED CONTENT

Raytheon's trusted missile defense solutions help the U.S. and its allies make the world a safer place

Breaking
Defense
ck here to view gallery »

EDITORIAL STAFF

Colin Clark
Editor

Sydney J. Freedberg, Jr.
Deputy Editor

ResearchGate

See discussions, stats, and author profiles for this publication at: https://www.researchgate.net/publication/313112342

Internet of Things (IoT) in 5G Wireless Communications

Article *in* IEEE Access · January 2016

DOI: 10.1109/ACCESS.2016.2646120

CITATIONS
2

READS
680

7 authors, including:

Waleed Ejaz
Ryerson University

69 PUBLICATIONS **397** CITATIONS

SEE PROFILE

Muhammad Ali Imran
University of Glasgow

402 PUBLICATIONS **4,102** CITATIONS

SEE PROFILE

Minho Jo
Korea University

98 PUBLICATIONS **1,145** CITATIONS

SEE PROFILE

Some of the authors of this publication are also working on these related projects:

Project IU-ATC View project

Project Visible Light Communication View project

All content following this page was uploaded by Minho Jo on 27 March 2017.

The user has requested enhancement of the downloaded file.

Digital Object Identifier 10.1109/ACCESS.2016.2646120

GUEST EDITORIAL

Internet of Things (IoT) in 5G Wireless Communications

During the past decade, the Internet of Things (IoT) has revolutionized the ubiquitous computing with multitude of applications built around various types of sensors. A vast amount of activity is seen in IoT based product-lines and this activity is expected to grow in years to come with projections as high as billions of devices with on average 6-7 devices per person by year 2020. With most of the issues at device and protocol levels solved during the past decade, there is now a growing trend in integration of sensors and sensor based systems with cyber physical systems and device-to-device (D2D) communications. 5^{th} generation wireless systems (5G) are on the horizon and IoT is taking the center stage as devices are expected to form a major portion of this 5G network paradigm. IoT technologies such as machine to machine communication complemented with intelligent data analytics are expected to drastically change landscape of various industries. The emergence of cloud computing and its extension to fog paradigm with proliferation of intelligent 'smart' devices is expected to lead further innovation in IoT. These developments excite us and form a motivation to survey existing work, design new techniques, and identify new applications of IoT. Researchers, scientists, and engineers face emerging challenges in designing IoT based systems that can efficiently be integrated with the 5G wireless communications.

We received enthusiastic response to our special issue call for papers. A total of nine high quality papers were received out of which only seven were selected after a thorough review process. Invited articles were sought from two highly cited and accomplished researchers. Dr. Mischa Dohler (Fellow IEEE, Kings College London, UK) and Dr. Mung Chiang (Fellow IEEE, Princeton University, USA).

The first article ''MIMO-NOMA design for small packet transmission in the Internet of Things'', written by a collaborative team of researchers Ding et al.,, opportunistic serving mechanism is designed as part of the effort in the novel paradigm of Multiple Input Multiple Output Non-Orthogonal Multiple Access transmission scheme. Under the proposed method, one user is completely served with their quality of service requirements completely taken care of whereas second user is served opportunistically under the NOMA paradigm. The main contribution of this article is a design with two sets of system parameters, precoding and power allocation coefficients, in order to ensure that the potential of NOMA can be realized even if the users' channel conditions are similar. Two types of power allocation policies are developed in this paper. One is to meet first user's QoS requirements in the long term. For example, in order to satisfy its targeted outage probability. The other is in which to realize second user's QoS requirements instantaneously, e.g., the power allocation coefficients are designed to realize its targeted data rate for each channel realization.

Machine to machine communication has a significant role to play in emerging internet of things paradigm in years and decades to come. The emerging IoT-5G scenario extends sensor based IoT capabilities to robots, actuators and drones for distributed coordination and low-latency reliable execution of tasks at hand. In the invited work titled ''Enabling the IoT machine age with 5G: Machine-type multicast services for innovative real-time applications'' by Condoluci et al., core attention is focused on the end-to-end reliability, latency, and energy consumption comprising both up and downlinks for 5G-IoT communication. The authors propose the definition, design, and analysis of machine-type multicast service (MTMS). They recommend different procedures that need to be redesigned for MTMS and derive the most appropriate design drivers by analyzing different performance indicators, such as scalability, reliability, latency, and energy consumption. Overall, a very interesting read complemented by open problems and future research directions to pursue.

Security is one of the biggest challenges faced by Internet of Things. With devices becoming ubiquitous and pervasive in day to day lives necessitate reliable and secure algorithms. The third article, ''Security enhancement for IoT communications exposed to eavesdroppers with uncertain locations'' by Xu et al., develops a secure framework for eavesdroppers with Uncertain Locations in IoT. With the assumption that the locations of eavesdroppers change independently from hop to hop, authors derive an expression for the secrecy outage probability of the two-hop transmission, which is shown to be the upper bound of the outage probability when the locations of eavesdroppers remain unchanged. Following this expression, the end users formulate a secrecy rate maximization problem with the secrecy-outage probability constraint. The optimal rate design for codebooks and power allocation between the source and relay are derived. By studying the performance of the optimal scheme in some special cases, we obtain several insights concerning the setting of system parameters.

In the article, ''Enabling massive IoT in 5G and beyond systems: PHY radio frame design considerations'' by Ayesha Ijaz et al., the authors propose a flexible frame structure and design for massive Internet of Things (IoT) devices working in 5G wireless network. The authors also discussed

2169-3536 © 2017 IEEE. Translations and content mining are permitted for academic research only.
Personal use is also permitted, but republication/redistribution requires IEEE permission.
See http://www.ieee.org/publications_standards/publications/rights/index.html for more information.

the interdependence of different frame design parameters, service requirements and characteristics of radio environment. Based on these interdependency, they provide guidelines for radio numerology design and elaborated on the frame design for IoT communications in 5G networks to support massive connection density of low-rate, low-power devices. The article concludes with some key research findings and challenges massive IoT in 5G wireless network.

It is estimated that in year 2020, 20 to 40 billion devices will be connected to the Internet as part of the Internet of Things. A critical bottleneck for realizing the efficient IoT is the pressure it puts on the existing communication infrastructures, requiring transfer of enormous data volumes. In the article ''CONDENSE: A reconfigurable knowledge acquisition architecture for future 5G IoT'', by Dejan Vukobratovic et al., the authors propose a architecture named 'Condense' which integrates the acquisition of IoT-generated data within the 3GPP MTC (machine type communications) systems. The proposed Condense architecture introduces a service within 3GPP MTC systems – computing linear and non-linear functions over the data generated by MTC devices This service brings about the possibility that the underlying communication infrastructure communicates only the desired function of the MTC- generated data (as required by the given application at hand), and not the raw data in its entirety. This transformational approach has the potential to dramatically reduce the pressure on the 3GPP MTC communication infrastructure. The article concludes by discussing challenges, provides insights, and identifies future research directions for implementing function computation and function decomposition within practical 3GPP MTC systems.

In the article, ''Frequency-domain oversampling for cognitive CDMA systems: Enabling robust and massive multiple access for Internet of Things'' by Su Hu et al., the authors utilize the concept of cognitive radio with dynamic non-continuous spectrum bands and code division multiple access to tackle the challenge of massive spectrum resource management in IoT. In order to suppress multiple access interference resulting from the non-orthogonality of partial available spectrum bins, carrier frequency offset, and spectrum sensing mismatch, the authors propose an enhanced receiver design that combines the frequency-domain oversampling scheme (FDO) and linear minimum mean square error (MMSE) method. The simulation results show that the cognitive-CDMA with FDO-MMSE receiver outperforms that with conventional per-user MMSE receiver in the presence of multipath fading channels, carrier frequency offset, and spectrum sensing mismatch.

In the invited article, ''A survey of client-controlled HetNets for 5G'' by Michael Wang et al., a comprehensive review is provided on spectrum of client-controlled HetNets for 5G networks: from the fully devolved distributed local control approach to the hybrid control approach where clients may make the decisions given some global information provided by the network. After giving a thorough review, the authors also provide future research directions and recommendations for evolution of 5G heterogeneous networks as an enabler for next generation internet of things.

To conclude, the Editors would like to thank all authors who submitted their manuscripts against this Special issue. There had been some very exciting submissions though we could only accept best seven high quality submissions. The editorial staff also thanks the reviewers for their timely comments on the manuscript which helped us improve the presentation and quality of the content manifold. All the associate editors thank the Editor in Chief Dr. Michael Pecht for his assistance in making this special issue a reality. We would also like to thank the publications editor Ms. Kimberly Shumard for her continuous follow up on timelines and management of articles to ensure timely completion of the review process. We complete this note by letting the readers know to stay tuned with IEEE Access as we expect even more exciting issues in months to come.

WALEED EJAZ
Ryerson University,
Toronto, ON, Canada

ALAGAN ANPALAGAN
Ryerson University,
Toronto, ON, Canada

MUHAMMAD ALI IMRAN
University of Glasgow,
Glasgow, U.K.

MINHO JO
Korea University,
Sejong, South Korea

MUHAMMAD NAEEM
Ryerson University,
Toronto, ON, Canada

SAAD BIN QAISAR
National University of Sciences and Technology,
Islamabad, Pakistan

WEI WANG
Zhejiang University,
Hangzhou, China

WALEED EJAZ (S'12–M'14–SM'16) received the B.Sc. and M.Sc. degrees in computer engineering from the National University of Sciences and Technology, Islamabad, Pakistan, and the University of Engineering and Technology, Taxila, Pakistan, respectively, and the Ph.D. degree in information and communication engineering from Sejong University, South Korea, in 2014. He was with top engineering universities in Pakistan and Saudi Arabia as a Faculty Member. He was a Post-Doctoral Fellow with Queen's University, Kingston, Canada. He is currently a Senior Research Associate with the Department of Electrical and Computer Engineering, Ryerson University, Toronto, Canada. He also completed certificate courses on teaching and learning in higher education from the Chang School, Ryerson University. His current research interests include Internet of Things, energy harvesting, 5G cellular networks, and mobile cloud computing. He is currently serving as an Associate Editor of the *Canadian Journal of Electrical and Computer Engineering* and the IEEE Access. In addition, he is handling the special issues in *IET Communications*, the IEEE Access, and the *Journal of Internet Technology*.

ALAGAN ANPALAGAN (S'98–M'01–SM'04) received the B.A.Sc., M.A.Sc., and Ph.D. degrees in electrical engineering from the University of Toronto. He is currently a Professor with the Department of Electrical and Computer Engineering, Ryerson University, where he directs the research group involved in radio resource management and radio access and networking areas within the WINCORE Lab. He served as an Editor of the IEEE Communications Surveys and Tutorials from 2012 to 2014, the IEEE Communications Letters from 2010 to 2013, the *Wireless Personal Communications* (Springer) from 2011 to 2013, and the EURASIP *Journal of Wireless Communications and Networking* from 2004 to 2009. He has co-authored three edited books, *Design and Deployment of Small Cell Networks* (Cambridge University Press, 2014), *Routing in Opportunistic Networks* (Springer, 2013), and *Handbook on Green Information and Communication Systems* (Academic Press, 2012).

Dr. Anpalagan is a registered Professional Engineer in ON, Canada, and a fellow of the Institution of Engineering and Technology. He served as the TPC Co-Chair of the IEEE Globecom'15: SAC Green Communication and Computing, the IEEE WPMC'12 Wireless Networks, the IEEE PIMRC'11 Cognitive Radio and Spectrum Management, and the IEEE CCECE'04/08. He served as the Vice Chair of the IEEE SIG on Green and Sustainable Networking and Computing with Cognition and Cooperation (2015–), the IEEE Canada Central Area Chair (2012–2014), the IEEE Toronto Section Chair (2006–2007), the ComSoc Toronto Chapter Chair (2004–2005), and the IEEE Canada Professional Activities Committee Chair (2009–2011). He was a recipient of the Dean's Teaching Award in 2011, the Faculty Scholastic, Research, and Creativity Award in 2010 and 2014, the Faculty Service Award in Ryerson University in 2011 and 2013. He also received the Exemplary Editor Award from the IEEE ComSoc in 2013 and an Editor-in-Chief Top10 Choice Award in the IEEE Transactions on Emerging Telecommunications Technology in 2012.

MUHAMMAD ALI IMRAN (M'03–SM'12) received the M.Sc. (Hons.) and Ph.D. degrees from the Imperial College London, U.K., in 2002 and 2007, respectively. He is currently a Professor in Communication Systems with the University of Glasgow, the Vice Dean of the Glasgow College UESTC, and the Program Director of Electrical and Electronics with Communications. From 2007 to 2016, he was an Adjunct Associate Professor with The University of Oklahoma, USA, and a Visiting Professor with the 5G Innovation Centre, University of Surrey, U.K.

He has led a number of multimillion-funded international research projects encompassing the areas of energy efficiency, fundamental performance limits, sensor networks, and self-organizing cellular networks. He also led the new physical layer work area for 5G Innovation center at Surrey. He has a global collaborative research network spanning both academia and key industrial players in the field of wireless communications. He has supervised 21 successful Ph.D. graduates and published over 200 peer-reviewed research papers, including over 20 IEEE Transaction papers. He secured first rank in his B.Sc. and a distinction in his M.Sc. degree along with an award of excellence in recognition of his academic achievements conferred by the President of Pakistan. He received the IEEE Comsoc's Fred Ellersick Award 2014, the Sentinel of Science Award 2016, and the FEPS Learning and Teaching Award 2014 and twice nominated for Tony Jean's Inspirational Teaching Award. He is a shortlisted finalist for The Wharton-QS Stars Awards 2014, the Reimagine Education Award for innovative teaching, and the VC's learning and teaching award in the University of Surrey. He is a Senior Fellow of the Higher Education Academy, U.K.

Dr. Imran has given an invited TEDx talk (2015) and over ten plenary talks, several tutorials and seminars in international conferences and other institutions. He has taught international short courses in USA and China. He is the Co-Founder of the IEEE Workshop BackNets 2015 and chaired several tracks/workshops of international conferences. He is an Associate Editor of the IEEE Communications Letters, the IEEE Access, and the *IET Communications* journal.

MINHO JO (SM'16) received the B.A. degree from the Department of Industrial Engineering, Chosun University, South Korea, in 1984, and the Ph.D. degree from the Department of Industrial and Systems Engineering, Lehigh University, USA, in 1994. He is currently a Professor with the Department of Computer Convergence Software, Korea University, Sejong, South Korea. He is one of the founders of the Samsung Electronics LCD Division. He was the Vice President of the Institute of Electronics and Information Engineers. He is currently the Vice President of the Korean Society for Internet Information. His current research interests include Internet of Things, AI/big data in Internet of Things, LET-Unlicensed, cognitive radio, mobile cloud computing, network security, heterogeneous networks in 5G, wireless energy harvesting, optimization in wireless communications, and massive MIMO. He is the Founder and an Editor-in-Chief of the *KSII Transactions on Internet and Information Systems* [SCI (ISI) and SCOPUS]. He served as an Editor of the IEEE Network. He is an Editor of the IEEE Wireless Communications, and an Associate Editor of the IEEE Internet of Things Journal, *Security and Communication Networks*, *Ad-Hoc & Sensor Wireless Networks*, and *Wireless Communications and Mobile Computing*.

MUHAMMAD NAEEM received the B.S. and M.S. degrees in electrical engineering from the University of Engineering and Technology, Taxila, Pakistan, in 2000 and 2005, respectively, and the Ph.D. degree from Simon Fraser University, BC, Canada, in 2011. From 2000 to 2005, he was a Senior Design Engineer with Comcept (pvt.) Ltd. At the design department of Comcept (pvt) Ltd., he participated in the design and development of smart card-based GSM and CDMA pay phones. From 2012 to 2013, he was a Post-Doctoral Research Associate with the WINCORE Laboratory, Ryerson University, Toronto, ON, Canada. Since 2013, he has been an Assistant Professor with the Department of Electrical Engineering, COMSATS Institute of IT, Wah Campus, Pakistan, and a Research Associate with the WINCORE Laboratory, Ryerson University. He is also a Microsoft Certified Solution Developer. His research interests include optimization of wireless communication systems, nonconvex optimization, resource allocation in cognitive radio networks, and approximation algorithms for mixed integer programming in communication systems. He was a recipient of NSERC CGS Scholarship.

SAAD BIN QAISAR (S'04–M'09–SM'14) received the master's and Ph.D. degrees in electrical engineering from Michigan State University, USA, in 2005 and 2009, respectively. He is currently serving as an Associate Professor with the National University of Sciences and Technology, Pakistan, and also leading Bitsym, an Internet of Things and data-analytics enterprise. He has authored over 60 publications, inventor of various patents, has completed multiple national and international projects and winner of various awards, including the University Best Researcher Award in 2012 and the UNIDO Cleantech Award in 2015, to name a few. His company, Bitsym, has been named among the 50 Most Promising Start-ups for 2012 by Global Entrepreneurship Week, globally.

WEI WANG (S'08–M'10–SM'15) received the B.S. and Ph.D. degrees from the Beijing University of Posts and Telecommunications, Beijing, China, in 2004 and 2009 respectively. From 2007 to 2008, he was a Visiting Student with the University of Michigan, Ann Arbor, USA. From 2013 to 2015, he was a Hong Kong Scholar with The Hong Kong University of Science and Technology, Hong Kong. He is currently an Associate Professor with the College of Information Science and Electronic Engineering, Zhejiang University, Hangzhou, China. He has authored over 90 international journal and conference papers in the area of wireless communications and networks. His research interests mainly focus on cognitive radio networks, green communications, and radio resource allocation for wireless networks.

Dr. Wang is the Associate Secretary-General of the Zhejiang Institute of Communications. He is the Editor of the book *Cognitive Radio Systems* (Intech, 2009) and serves as an Editor of the IEEE Access, Transactions on Emerging Telecommunications Technologies, and the *KSII Transactions on Internet and Information Systems*. He also serves as the Co-Chair or a TPC Member for several international conferences.

• • •

View publication stats

ERICSSON WHITE PAPER

Uen 284 23-3204 Rev C | April 2016

5G RADIO ACCESS

CAPABILITIES AND TECHNOLOGIES

The capabilities of 5G wireless access must extend far beyond previous generations of mobile communication. Examples of these capabilities include very high data rates, very low latency, ultra-high reliability, energy efficiency and extreme device densities, and will be realized by the development of LTE in combination with new radio-access technologies. Key technology components include extension to higher frequency bands, access/backhaul integration, device-to-device communication, flexible duplex, flexible spectrum usage, multi-antenna transmission, ultra-lean design, and user/control separation.

WHAT IS 5G?

5G radio access technology will be a key component of the Networked Society. It will address high traffic growth and increasing demand for high-bandwidth connectivity. It will also support massive numbers of connected devices and meet the real-time, high-reliability communication needs of mission-critical applications.

5G will provide wireless connectivity for a wide range of new applications and use cases, including wearables, smart homes, traffic safety/control, critical infrastructure, industry processes and very-high-speed media delivery. As a result, it will also accelerate the development of the Internet of Things.

The overall aim of 5G is to provide ubiquitous connectivity for any kind of device and any kind of application that may benefit from being connected.

5G networks will not be based on one specific radio-access technology. Rather, 5G is a portfolio of access and connectivity solutions addressing the demands and requirements of mobile communication beyond 2020.

The specification of 5G will include the development of a new flexible air interface, NX, which will be directed to extreme mobile broadband deployments. NX will also target high-bandwidth and high-traffic-usage scenarios, as well as new scenarios that involve mission-critical and real-time communications with extreme requirements in terms of latency and reliability.

In parallel, the development of Narrow-Band IoT (NB-IoT) in 3GPP is expected to support massive machine connectivity in wide area applications. NB-IoT will most likely be deployed in bands below 2GHz and will provide high capacity and deep coverage for enormous numbers of connected devices.



Figure 1: The overall 5G wireless-access solution consisting of LTE evolution and new technology.

Ensuring interoperability with past generations of mobile communications has been a key principle of the ICT industry since the development of GSM and later wireless technologies within the 3GPP family of standards. In a similar manner, LTE will evolve in a way that recognizes its role in providing excellent coverage for mobile users, and 5G networks will incorporate LTE access (based on Orthogonal Frequency Division Multiplexing (OFDM)) along with new air interfaces in a transparent manner toward both the service layer and users.

Around 2020, much of the available wireless coverage will continue to be provided by LTE, and it is important that operators with deployed 4G networks have the opportunity to transition some – or all – of their spectrum to newer wireless access technologies. For operators with limited spectrum resources, the possibility of introducing 5G capabilities in an interoperable way – thereby allowing legacy devices to continue to be served on a compatible carrier – is highly beneficial and, in some cases, even vital.

At the same time, the evolution of LTE to a point where it is a full member of the 5G family of air interfaces is essential, especially since initial deployment of new air interfaces may not operate in the same bands. The 5G network will enable dual-connectivity between LTE operating within bands below 6GHz and the NX air interface in bands within the range 6GHz to100GHz. NX should also allow for user-plane aggregation, i.e. joint delivery of data via LTE and NX component carriers.

This paper explains the key requirements and capabilities of 5G, along with its technology components and spectrum needs.

5G – REQUIREMENTS AND CAPABILITIES

In order to enable connectivity for a very wide range of applications with new characteristics and requirements, the capabilities of 5G wireless access must extend far beyond those of previous generations of mobile communication. These capabilities will include massive system capacity, very high data rates everywhere, very low latency, ultra-high reliability and availability, very low device cost and energy consumption, and energy-efficient networks.

MASSIVE SYSTEM CAPACITY

Traffic demands for mobile-communication systems are predicted to increase dramatically [1] [2]. To support this traffic in an affordable way, 5G networks must deliver data with much lower cost per bit compared with the networks of today. Furthermore, the increase in data consumption will result in an increased energy footprint from networks. 5G must therefore consume significantly lower energy per delivered bit than current cellular networks.

The exponential increase in connected devices, such as the deployment of billions of wirelessly connected sensors, actuators and similar devices for massive machine connectivity, will place demands on the network to support new paradigms in device and connectivity management that do not compromise security. Each device will generate or consume very small amounts of data, to the extent that they will individually, or even jointly, have limited impact on the overall traffic volume. However, the sheer number of connected devices seriously challenges the ability of the network to provision signaling and manage connections.

VERY HIGH DATA RATES EVERYWHERE

Every generation of mobile communication has been associated with higher data rates compared with the previous generation. In the past, much of the focus has been on the peak data rate that can be supported by a wireless-access technology under ideal conditions. However, a more important capability is the data rate that can actually be provided under real-life conditions in different scenarios.

- 5G should support data rates exceeding 10Gbps in specific scenarios such as indoor and dense outdoor environments.
- Data rates of several 100Mbps should generally be achievable in urban and suburban environments.
- Data rates of at least 10Mbps should be accessible almost everywhere, including sparsely-populated rural areas in both developed and developing countries.

VERY LOW LATENCY

Very low latency will be driven by the need to support new applications. Some envisioned 5G use cases, such as traffic safety and control of critical infrastructure and industry processes, may require much lower latency compared with what is possible with the mobile-communication systems of today.

To support such latency-critical applications, 5G should allow for an application end-to-end latency of 1ms or less, although application-level framing requirements and codec limitations for media may lead to higher latencies in practice. Many services will distribute computational capacity and storage close to the air interface. This will create new capabilities for real-time communication and will allow ultra-high service reliability in a variety of scenarios, ranging from entertainment to industrial process control.

ULTRA-HIGH RELIABILITY AND AVAILABILITY

In addition to very low latency, 5G should also enable connectivity with ultra-high reliability and ultra-high availability. For critical services, such as control of critical infrastructure and traffic safety, connectivity with certain characteristics, such as a specific maximum latency, should not merely be ‘typically available.’ Rather, loss of connectivity and deviation from quality of service requirements must be extremely rare. For example, some industrial applications might need to guarantee successful packet delivery within 1 ms with a probability higher than 99.9999 percent.

VERY LOW DEVICE COST AND ENERGY CONSUMPTION

Low-cost, low-energy mobile devices have been a key market requirement since the early days of mobile communication. However, to enable the vision of billions of wirelessly connected sensors, actuators and similar devices, a further step has to be taken in terms of device cost and energy consumption. It should be possible for 5G devices to be available at very low cost and with a battery life of several years without recharging.

ENERGY-EFFICIENT NETWORKS

While device energy consumption has always been prioritized, energy efficiency on the network side has recently emerged as an additional KPI, for three main reasons:

- Energy efficiency is an important component in reducing operational cost, as well as a driver for better dimensioned nodes, leading to lower total cost of ownership.
- Energy efficiency enables off-grid network deployments that rely on medium-sized solar panels as power supplies, thereby enabling wireless connectivity to reach even the most remote areas.
- Energy efficiency is essential to realizing operators’ ambition of providing wireless access in a sustainable and more resource-efficient way.

The importance of these factors will increase further in the 5G era, and energy efficiency will therefore be an important requirement in the design of 5G wireless access.

MACHINE-TYPE COMMUNICATION

Fundamentally, applications such as mobile telephony, mobile broadband and media delivery are about information for humans. In contrast, many of the new applications and use cases that drive the requirements and capabilities of 5G are about end-to-end communication between machines. To distinguish them from the more human-centric wireless-communication use cases, these applications are often termed machine-type communication (MTC).

Although spanning a wide range of applications, MTC applications can be divided into two main categories – massive MTC and critical MTC – depending on their characteristics and requirements.


Massive number of devices
Low device cost
Long battery life
Small data volumes
Ultra-reliable
Very high availability
Very low latency
Massive MTC
Critical MTC
Scalable and flexible access
• Scalable and flexible bandwidths
• Scalable and flexible signaling protocols
• …
Capillary networks
• Short-range radio + cellular
Very short transmission times
Contention-based access and fast channel assignments
Multi-level diversity
Device-to-device communication
…

Figure 2: Massive MTC and critical MTC.

Massive MTC refers to services that typically span a very large numbers of devices, usually sensors and actuators. Sensors are extremely low cost and consume very low amounts of energy in order to sustain long battery life. Clearly, the amount of data generated by each sensor is normally very small, and very low latency is not a critical requirement. While actuators are similarly limited in cost, they will likely have varying energy footprints ranging from very low to moderate energy consumption.

Sometimes, the mobile network may be used to bridge connectivity to the device by means of capillary networks. Here, local connectivity is provided by means of a short-range radio access technology, for example Wi-Fi, Bluetooth [3] or 802.15.4/6LoWPAN [4]. Wireless connectivity beyond the local area is then provided by the mobile network via a gateway node.

Critical MTC refers to applications such as traffic safety/control, control of critical infrastructure and wireless connectivity for industrial processes. Such applications require very high reliability and availability in terms of wireless connectivity, as well as very low latency. On the other hand, low device cost and energy consumption is not as critical as for massive MTC applications. While the average volume of data transported to and from devices may not be large, wide instantaneous bandwidths are useful in being able to meet capacity and latency requirements.

There is much to gain from a network being able to handle as many different applications as possible, including mobile broadband, media delivery and a wide range of MTC applications by means of the same basic wireless-access technology and within the same spectrum. This avoids spectrum fragmentation and allows operators to offer support for new MTC services for which the business potential is inherently uncertain, without having to deploy a separate network and reassign spectrum specifically for these applications.

SPECTRUM FOR 5G

In order to support increased traffic capacity and to enable the transmission bandwidths needed to support very high data rates, 5G will extend the range of frequencies used for mobile communication. This includes new spectrum below 6GHz, as well as spectrum in higher frequency bands.

Specific candidate spectrum for mobile communication in higher frequency bands is yet to be identified by the ITU-R or by individual regulatory bodies. The mobile industry remains agnostic about particular choices, and the entire frequency range up to approximately 100GHz is under consideration at this stage, although there is significant interest in large contiguous allocations that can provide dedicated and licensed spectrum for use by multiple competing network providers.

The lower part of this frequency range, below 30GHz, is preferred from the point of view of propagation properties. At the same time, very large amounts of spectrum and the possibility of wide transmission frequency bands of the order of 1GHz or more are more likely above 30GHz.



Figure 3: Spectrum relevant for 5G wireless access.

Spectrum relevant for 5G wireless access therefore ranges from below 1GHz up to approximately 100GHz, as Figure 3 shows.

It is important to understand that high frequencies, especially those above 10GHz, can only serve as a complement to lower frequency bands, and will mainly provide additional system capacity and very wide transmission bandwidths for extreme data rates in dense deployments. Spectrum allocations at lower bands will remain the backbone for mobile-communication networks in the 5G era, providing ubiquitous wide-area connectivity.

The World Radio Conference (WRC)-15 discussions have resulted in an agreement to include an agenda item for IMT-2020, the designated ITU-R qualifier for 5G, in WRC-19. The conference also reached agreement on a set of bands that will be studied for 5G, with direct applicability to NX. Many of the proposed bands are in the millimeter wave region and include:

- 24.25GHz to 27.5GHz, 37GHz to 40.5GHz, 42.5GHz to 43.5GHz, 45.5GHz to 47GHz, 47.2GHz to 50.2GHz, 50.4GHz to 52.6GHz, 66 GHz to 76GHz and 81GHz to 86GHz, which have allocations to the mobile service on a primary basis; and
- 31.8GHz to 33.4GHz, 40.5GHz to 42.5GHz and 47GHz to 47.2GHz, which may require additional allocations to the mobile service on a primary basis.

The mobile industry will strive to gain access to spectrum in the 6GHz to 20GHz range, but the policy directions being followed by regulators seem to be focused on frequency bands above 30GHz. In the US, the FCC has issued two Notices of Public Rule Making (NPRM) on bands above 24GHz. Ofcom has likewise indicated a preference for bands above 30GHz within the mobile industry.

The capacity needs of the mobile industry will continue to be served by licensed spectrum, although novel sharing arrangements for spectrum will become progressively more important as restricted opportunities for new spectrum start to impact incumbent services such as satellite communication and radio location. Two examples of sharing arrangements include LSA planned in Europe for the 2.3GHz band and the Citizens Band Radio Service for 3.5GHz in the US.

5G TECHNOLOGY COMPONENTS

Beyond extending operation to higher frequencies, there are several other key technology components relevant for the evolution to 5G wireless access. These components include access/backhaul integration, device-to-device communication, flexible duplex, flexible spectrum usage, multi-antenna transmission, ultra-lean design, and user/control separation.

ACCESS/BACKHAUL INTEGRATION

Wireless technology is already frequently used as part of the backhaul solution. Such wireless-backhaul solutions typically operate under line-of-sight conditions using proprietary radio technology in higher frequency bands, including the millimeter wave (mmW) band.

In the future, the access (base-station-to-device) link will also extend to higher frequencies. Furthermore, to support dense low-power deployments, wireless backhaul will have to extend to cover non-line-of-sight conditions, similar to access links.

In the 5G era, the wireless-access link and wireless backhaul should not therefore be seen as two separate entities with separate technical solutions. Rather, backhaul and access should be seen as an integrated wireless-access solution able to use the same basic technology and operate using a common spectrum pool. This will lead to more efficient overall spectrum utilization as well as reduced operation and management effort.

DIRECT DEVICE-TO-DEVICE COMMUNICATION

The possibility of limited direct device-to-device (D2D) communication has recently been introduced as an extension to the LTE specifications. In the 5G era, support for D2D as part of the overall wireless-access solution should be considered from the start. This includes peer-to-peer user-data communication directly between devices, but also, for example, the use of mobile devices as relays to extend network coverage.

D2D communication in the context of 5G should be an integral part of the overall wireless-access solution, rather than a stand-alone solution. Direct D2D communication can be used to offload traffic, extend capabilities and enhance the overall efficiency of the wireless-access network. Furthermore, in order to avoid uncontrolled interference to other links, direct D2D communication should be under network control. This is especially important for the case of D2D communication in licensed spectrum.

FLEXIBLE DUPLEX

Frequency Division Duplex (FDD) has been the dominating duplex arrangement since the beginning of the mobile communication era. In the 5G era, FDD will remain the main duplex scheme for lower frequency bands. However, for higher frequency bands – especially above 10GHz – targeting very dense deployments, Time Division Duplex (TDD) will play a more important role.

In very dense deployments with low-power nodes, the TDD-specific interference scenarios (direct base-station-to-base-station and device-to-device interference) will be similar to the 'normal' base-station-to-device and device-to-base-station interference that also occurs for FDD.

Furthermore, for the dynamic traffic variations expected in very dense deployments, the ability to dynamically assign transmission resources (time slots) to different transmission directions may allow more efficient utilization of the available spectrum.

To reach its full potential, 5G should therefore allow for very flexible and dynamic assignment of TDD transmission resources. This is in contrast to current TDD-based mobile technologies, including TD-LTE, for which there are restrictions on the downlink/uplink configurations, and for which there typically exist assumptions about the same configuration for neighbor cells and also between neighbor operators.

FLEXIBLE SPECTRUM USAGE

Since its inception, mobile communication has relied on spectrum licensed on a per-operator basis within a geographical area. This will remain the foundation for mobile communication in the 5G era, allowing operators to provide high-quality connectivity in a controlled-interference environment.

However, per-operator licensing of spectrum will be complemented with the possibility to share spectrum. Such sharing may be between a limited set of operators, or may occur in license-exempt scenarios. The

Citizens Band Radio Service in the US in the 3.5GHz band and the 5GHz unlicensed spectrum are examples of managed and unlicensed sharing regimes respectively.

New air interfaces like NX will likely be well served by more conventional licensed allocations of spectrum, mainly due to the need to establish a basic foundation for the technology to operate in an independent manner while interoperability is established with technologies like LTE. At some point, further allocations of spectrum for 5G may leverage the mobile industry's experience of sharing approaches in lower cellular bands.

MULTI-ANTENNA TRANSMISSION

Multi-antenna transmission already plays an important role in current generations of mobile communication and will be even more central in the 5G era, due to the physical limitations of small antennas. Path loss between a transmitter and receiver does not change as a function of frequency, as long as the effective aperture of the transmitting and receiving antennas does not change. The antenna aperture does reduce in proportion to the square of the frequency, and that reduction can be compensated by the use of higher antenna directivity. The 5G radio will employ hundreds of antenna elements to increase antenna aperture beyond what may be possible with current cellular technology.

In addition, the transmitter and receiver will use beamforming to track one another and improve energy transfer over an instantaneously configured link. Beamforming will also improve the radio environment by limiting interference to small fractions of the entire space around a transmitter and likewise limiting the impact of interference on a receiver to infrequent stochastic events. The use of beamforming will also be an important technology for lower frequencies; for example, to extend coverage and to provide higher data rates in sparse deployments.

ULTRA-LEAN DESIGN

Ultra-lean radio-access design is important to achieve high efficiency in 5G networks. The basic principle of ultra-lean design can be expressed as: minimize any transmissions not directly related to the delivery of user data. Such transmissions include signals for synchronization, network acquisition and channel estimation, as well as the broadcast of different types of system and control information.

Ultra-lean design is especially important for dense deployments with a large number of network nodes and highly variable traffic conditions. However, lean transmission is beneficial for all kinds of deployments, including macro deployments.

By enabling network nodes to enter low-energy states rapidly when there is no user-data transmission, ultra-lean design is an important component in delivering high network energy performance. Ultra-lean design will also enable higher achievable data rates by reducing interference from non-user-data-related transmissions.

USER/CONTROL SEPARATION

Another important design principle for 5G is to decouple user data and system control functionality. The latter includes the provisioning of system information; that is, the information and procedures needed for a device to access the system.

Such a decoupling will allow separate scaling of user-plane capacity and basic system control functionality. For example, user data may be delivered by a dense layer of access nodes, while system information is only provided via an overlaid macro layer on which a device also initially accesses the system.

It should be possible to extend the separation of user data delivery and system control functionality over multiple frequency bands and RATs. As an example, the system control functionality for a dense layer based on new high-frequency radio access could be provided by means of an overlaid LTE layer.

User/control separation is also an important component for future radio-access deployments relying heavily on beamforming for user data delivery. Combining ultra-lean design with a logical separation of user-plane data delivery and basic system connectivity functionality will enable a much higher degree of device-centric network optimization of the active radio links in the network. Since only the ultra-lean signals related to the system control plane need to be static, it is possible to design a system where almost everything can be dynamically optimized in real time.

An ultra-lean design combined with a system control plane logically separated from the user data delivery function also provides higher flexibility in terms of evolution of the RAT as, with such separation, the user plane can evolve while retaining system control functionality.

CONCLUSION

5G is the next step in the evolution of mobile communication and will be a key component of the Networked Society. In particular, 5G will accelerate the development of the Internet of Things. To enable connectivity for a wide range of applications and use cases, the capabilities of 5G wireless access must extend far beyond those of previous generations of mobile communications.

These capabilities include very high achievable data rates, very low latency and ultra-high reliability. Furthermore, 5G wireless access needs to support a massive increase in traffic in an affordable and sustainable way, implying a need for a dramatic reduction in the cost and energy consumption per delivered bit.

5G wireless access will be realized by the evolution of LTE for existing spectrum in combination with new radio access technologies that primarily target new spectrum. Key technology components of 5G wireless access include access/backhaul integration, device-to-device communication, flexible duplex, flexible spectrum usage, multi-antenna transmission, ultra-lean design, and user/control separation.

REFERENCES

[1] ICT-317669 METIS project, Updated scenarios, requirements and KPIs for 5G mobile and wireless system with recommendations for future investigations, Deliverable D1.5, April 2015, available at:
https://www.metis2020.com/wp-content/uploads/deliverables/METIS_D1.5_v1.pdf

[2] Ericsson, Ericsson Mobility Report, November 2015, available at:
http://www.ericsson.com/res/docs/2015/mobility-report/ericsson-mobility-report-nov-2015.pdf

[3] Bluetooth Special Interest Group, accessed March 2016, available at:
http://bluetooth.org

[4] IETF, IPv6 over Low power WPAN (6lowpan), accessed March 2016, available at:
http://datatracker.ietf.org/wg/6lowpan

GLOSSARY

D2D	device-to-device
FDD	Frequency Division Duplex
mmW	millimeter wave
MTC	Machine-Type Communication
NPRM	Notices of Public Rule Making
OFDM	Orthogonal Frequency Division Multiplexing
TDD	Time Division Duplex
WRC	World Radio Conference

© 2016 Ericsson AB – All rights reserved

ERICSSON WHITE PAPER
Uen 284 23-3278 | January 2016

CELLULAR NETWORKS FOR MASSIVE IOT

ENABLING LOW POWER WIDE AREA APPLICATIONS

With new standards specifically targeting the connectivity requirements of Massive Internet of Things (IoT) applications, cellular networks can deliver reliable, secure and diverse IoT services using existing network infrastructure.

DELIVERING NEW VALUE IN THE NETWORKED SOCIETY

In the future, all devices that benefit from an internet connection will be connected. In this Networked Society, every person and every industry will be empowered to reach their full potential. Internet of Things (IoT) technology is a key enabler of this vision by delivering machine-to-machine (M2M) and machine-to-person communications on a massive scale.

As shown in Figure 1, Ericsson predicts there will be around 28 billion connected devices by 2021, of which more than 15 billion will be connected M2M and consumer-electronics devices [1]. A large share of these will be applications served by short-range radio technologies such as Wi-Fi and Bluetooth, while a significant proportion will be enabled by wide area networks (WANs) that are primarily facilitated by cellular networks.



Figure 1: Growth in connected devices.

THE NEW IOT LANDSCAPE

The IoT revolution offers huge potential value in terms of improved efficiency, sustainability and safety for industry and society. Analysts predict that the total added value of the IoT will be USD 1.9 trillion by 2020 [2].

The variety of applications and solutions designed for individuals, business and industry is spurring the rapid expansion of the IoT market. The IoT is playing a major role across a variety of vertical sectors, generating cost savings, new revenue streams and other benefits.

Each IoT application needs a clear value proposition and business logic in line with the prevailing ecosystem, business models and value chains of the various stakeholders. For all applications, solutions need to be integrated on platforms that can scale and handle millions of devices efficiently. Business processes for administration, provisioning and charging will have to be streamlined to minimize costs and enhance the business case.


IoT rollout
Deployment, integration, project management, business consulting
Enterprise IT and business processes
Service and application creation, revenue management, device management
IoT platforms
Device connection platform, service enablement platform
Connectivity
Radio access, core, transmission
Industry solutions

Figure 2: The new IoT landscape.

As they are largely responsible for wireless connectivity on a global scale, operators are in an excellent position to capture a share of the added value generated by the emerging IoT market. The size of this share will depend on the role that operators adopt in the value chain. This could range from being a straightforward connectivity provider (monetizing connectivity in new ways), all the way to being an end-to-end solution provider of turnkey solutions to vertical markets [3].

DIFFERENT IOT CONNECTIVITY ALTERNATIVES

Connectivity is the foundation for IoT, and the type of access required will depend on the nature of the application. Many IoT devices will be served by radio technologies that operate on unlicensed spectrum and that are designed for short-range connectivity with limited QoS and security requirements typically applicable for a home or indoor environment. Currently, there are two alternative connectivity tracks for the many IoT applications that depend on wide-area coverage:

Cellular technologies: 3GPP technologies like GSM, WCDMA, LTE and future 5G. These WANs operate on licensed spectrum and historically have primarily targeted high-quality mobile voice and data services. Now, however, they are being rapidly evolved with new functionality and the new radio access technology narrowband IoT (NB-IoT) specifically tailored to form an attractive solution for emerging low power wide area (LPWA) applications.

Unlicensed LPWA: new proprietary radio technologies, provided by, for example, SIGFOX and LoRa, have been developed and designed solely for machine-type communication (MTC) applications addressing the ultra-low-end sensor segment, with very limited demands on throughput, reliability or QoS.

One way to segment IoT applications is to categorize them according to coverage needs and performance requirements (such as data speed or latency demands).



Figure 3: Technologies addressing different IoT segments.

The coverage needs of a particular use case may be highly localized (such as a stationary installation within a building), while other use cases require global service coverage (such as container tracking). 3GPP technologies already dominate use cases with large geographic coverage needs and medium- to high-performance requirements.

With new feature sets specifically tailored for LPWA IoT applications, 3GPP technologies are taking a large leap forward to cover segments with low-cost, low-performance requirements too.

CAPILLARY NETWORKS COMBINING CELLULAR AND UNLICENSED STRENGTHS

Even when existing 3GPP end-to-end connectivity is not feasible, cellular technology can still provide key benefits when used as a bridging option, i.e. as an aggregation and routing solution. This capillary network approach allows end devices to utilize varying access solutions from either the short range or LPWA domain and access the cellular networks via a gateway device. Capillary networks enable the reuse of cellular functions and assets such as security, device management, billing and QoS without requiring each end device to be cellular-enabled.

A WIDE RANGE OF IOT REQUIREMENTS

There will be a wide range of IoT use cases in the future, and the market is now expanding toward both Massive IoT deployment as well as more advanced solutions that may be categorized as Critical IoT, as shown in Figure 4.


Massive IoT
Critical IoT
Smart building
Logistics, tracking and fleet management
Remote health care
Traffic safety and control
Remote manufacturing, training, surgery
Capillary networks
Smart agriculture
Smart metering
25389
Smart grid automation
Industrial application and control
Low cost, low energy, small data volumes, massive numbers
Ultra reliable, very low latency, very high availability

Figure 4: Differing requirements for Massive and Critical IoT applications.

At one end of the scale, in Massive IoT applications – typically sensors that report to the cloud on a regular basis – the end-to-end cost must be low enough for the business case to make sense. Here, the requirement is for low-cost devices with low energy consumption and good coverage.

At the other end of the scale, Critical IoT applications will have very high demands for reliability, availability and low latency. These use cases are enabled by LTE or 5G capabilities. Here, the volumes are typically much smaller, but the business value is significantly higher.

There are, however, many other use cases between the two extremes, which today rely on 2G, 3G or 4G connectivity.

MASSIVE IOT USE CASE DIVERSITY

The Massive IoT market segment includes several applications widely used in industries and societies, as shown in Figure 5.


Massive IoT
Transport and logistics
Fleet management
Goods tracking
Utilities
Smart metering
Smart grid management
Agriculture
Climate/agriculture monitoring
Livestock tracking
Smart cities
Parking sensors
Smart bicycles
Waste management
Smart lighting
Environment
Flood monitoring/alerts
Environmental monitoring (water, air, noise etc.)
Smart buildings
Smoke detectors
Alarm systems
Home automation
Industrial
Process monitoring and control
Maintenance monitoring
Consumers
Wearables
Kids/senior tracker
Medical monitoring

Figure 5: Industry and society applications enabled by LPWA.

The potential applications for the IoT run into the millions, with a huge variety of requirements regarding cost, battery life, coverage, connectivity performance (throughput and capacity), security and reliability. Figure 6 illustrates some such applications and their requirements regarding devices and connectivity.



Figure 6: Device and connectivity requirements for sample IoT use cases.

Some devices will only send a few messages per day – such as status indicators for temperature – while others may need to transmit a video stream to guide a remote repair technician, for example. The difference in throughput requirements is huge. If operators or service providers handle several applications, it may be of great benefit to be able to harmonize communication modules, so that they all use the same underlying radio solution to reduce operational and fault management effort and complexity.

Many higher-value applications will require two-way communications – in other words, an uplink as well as a downlink – to enable monitoring and control of devices in systems like heating, ventilation and cooling plants. The long lifetime of many IoT applications makes it invaluable to be able to perform over-the-air device updates for new functionality or parameter settings. The amount of data sent for such updates can often be more demanding for the network than the monitoring or control application itself.

Relatively simple uplink-focused applications can benefit greatly from a bi-directional link to provide robustness. For example, a connected smoke detector must deliver a smoke alarm with absolute certainty. The ability of a network to provide acknowledgements of a received message enables better fault management and the required level of reliability. Positioning can be used to locate the sensor at the point it failed and simplify operations. For tracking applications, location information is essential.

In applications like building security, sensitive information could be reported over the air, which will require strict security. Furthermore, in the case of a break-in, it is crucial that the alarm information reaches the control center in time – making QoS and two-way communication vital.

KEY CHALLENGES FOR MASSIVE IOT

The key challenges to enabling large-scale uptake of Massive IoT include:

Device cost – clearly a key enabler for high-volume, mass-market applications, enabling many of the use cases.

Battery life – many IoT devices will be battery-powered, and often the cost of replacing batteries in the field is not viable.

Coverage – deep indoor connectivity is a requirement for many applications in the utility area. Furthermore, regional (or even national or global) coverage is a prerequisite for many use cases, especially within the transport area.

Scalability – in order to enable a Massive IoT market, networks need to scale efficiently. The initial investment required for supporting a limited number of devices has to be manageable, while on the other hand, the network capacity must be easy to scale to handle thousands – or millions – of devices.

Diversity – connectivity should be able to support diverse requirements from different use cases. One network supporting everything from simple static sensors to tracking services, to applications requiring higher throughput and lower latency is essential in terms of total cost of ownership (TCO).

THE ADVANTAGES OF CELLULAR TECHNOLOGIES

Each of the technologies available for IoT connectivity has its own advantages and disadvantages. However, the range of IoT connectivity requirements – both technical and commercial – means cellular technologies can provide clear benefits across a wide variety of applications, as summarized in Figure 7.



Figure 7: Advantages of cellular technologies.

In terms of global reach, cellular networks already cover 90 percent of the world's population. WCDMA and LTE are catching up, but GSM will offer superior coverage in many markets for years to come. Cellular networks have been developed and deployed over three decades, and they will be around for the foreseeable future.

The cellular mobile industry represents a huge and mature ecosystem, incorporating chipset, device and network equipment vendors, operators, application providers and many others. The global cellular ecosystem is governed by the 3GPP standardization forum, which guarantees broad industry support for future development.

When it comes to scalability, cellular networks are built to handle massive volumes of mobile broadband traffic; the traffic from most IoT applications will be relatively small and easily absorbed. Operators are able to offer connectivity for IoT applications from the start-up phase and grow this business with low TCO and only limited additional investment and effort. Operation in licensed spectrum also provides predictable and controlled interference, which enables efficient use of the spectrum to support massive volumes of devices.

Cellular connectivity offers the diversity to serve a wide range of applications with varying requirements within one network. While competing unlicensed LPWA technologies are designed solely for very low-end MTC applications, cellular networks can address everything from Massive to Critical IoT use cases.

QoS mechanisms will be essential for many IoT applications. Cellular systems have mature QoS functionality, and this enables critical MTC applications to be handled together with traffic from sensors, voice and mobile-broadband traffic on the same carrier. QoS, along with licensed spectrum as described above, provides a foundation for long-term Service Level Agreements with a specific grade of service.

Traditionally, the security mechanisms of cellular networks have been based on a physical SIM attached to the device, referred to as a Universal Integrated Circuit Card (UICC). This has also enabled roaming between operators, which has been one of the main factors behind the huge success of mobile networks. The SIM will also be essential in future IoT applications, with SIM functionality embedded in the chipset (eUICC) or handled as a soft-SIM solution running in a trusted run-time environment of the module.

With a straightforward rollout of new software, cellular networks will be able to support the full breadth of applications, ranging from low-end use cases in the LPWA segment, to the high-end segments of in-car entertainment and video surveillance. One network connecting the whole diversifying IoT market will guarantee the lowest possible TCO as well as fast time to market.



Figure 8: World population coverage by cellular 3GPP technology.

EVOLVING STANDARDS

To meet the new connectivity requirements of the emerging Massive IoT segment, 3GPP has taken evolutionary steps on both the network side and the device side.

The key improvement areas addressed in 3GPP up to Release 13 are:

- Lower device cost – cutting module cost for LTE devices by reducing peak rate, memory requirement and device complexity. The LTE module cost-reduction evolution started in Release 8 with the introduction of LTE for machine-type communication (LTE-M) Cat 1 devices with reduced peak rate to a maximum of 10Mbps, and continued in Releases 12 and 13 with reduced device complexity for lower performance and using less bandwidth or a narrowband IoT carrier to cut costs further.
- Improved battery life – more than 10 years of battery life can be achieved by introducing Power Saving Mode and/or extended discontinuous reception (eDRX) functionality. These features allow the device to contact the network – or to be contacted – on a per-need basis, meaning that it can stay in sleep mode for minutes, hours or even days.
- Improved coverage – an improvement of 15dB on LTE-M and of 20dB on NB-IoT and GSM, which translates into a seven-fold increase in the outdoor coverage area and significantly improved indoor signal penetration to reach deep indoors. This supports many IoT devices like smart meters, which are often placed in a basement.
- Support for massive numbers of IoT connections – specifically, one LTE cell site can support millions of IoT devices, depending on the use case. Core network enhancements include software upgrades for service differentiation handling, signaling optimization and high-capacity platforms (more than 30 million devices per node).



Figure 9: 3GPP evolution steps for Massive IoT.

A FULL RANGE OF CELLULAR LPWA SOLUTIONS

No single technology or solution is ideally suited to all the different potential Massive IoT applications, market situations and spectrum availability. As a result, the mobile industry is standardizing several LPWA technologies, including Extended Coverage GSM (EC-GSM), LTE-M and NB-IoT.

LTE-M, NB-IoT and EC-GSM are all superior solutions to meet Massive IoT requirements as a family of solutions, and can complement each other based on technology availability, use case requirements and deployment scenarios. LTE-M consisting of Cat 1, Cat 0 and Cat M supports a wide range of IoT applications, including those that are content-rich; NB-IoT covers ultra-low-end IoT applications with a cost and coverage advantage over LTE-M; and EC-GSM serves IoT services for all GSM markets.

For example, a smart city application such as waste management may use EC-GSM technology to provide LPWA connectivity in markets where it can be deployed on existing 2G networks; NB-IoT technology may be used for water-metering applications, which have some of the most extreme coverage requirements in underground locations. On the other hand, asset-tracking applications that can support a relatively high number of messages triggered by certain events may employ LTE-M.

EC-GSM – GLOBAL CELLULAR IOT FOR ALL GSM MARKETS

GSM is still the dominant mobile technology in many markets, and the vast majority of cellular M2M applications today use GPRS/EDGE for connectivity. GSM is likely to continue playing a key role in the IoT well into the future, due to its global coverage footprint, time to market and cost advantages.

Recognizing this – and identifying the requirements for Massive IoT discussed earlier in this paper – an initiative was undertaken in 3GPP Release 13 to further improve GSM.

The resulting EC-GSM functionality enables coverage improvements of up to 20dB with respect to GPRS on the 900MHz band.

This coverage extension is achieved for both the data and control planes by utilizing the concept of repetitions and signal combining techniques. It is handled in a dynamic manner with multiple coverage classes to ensure optimal balance between coverage and performance.

EC-GSM is achieved by defining new control and data channels mapped over legacy GSM. It allows multiplexing of new EC-GSM devices and traffic with legacy EDGE and GPRS. No new network carriers are required: new software on existing GSM networks is sufficient and provides combined capacity of up to 50,000 devices per cell on a single transceiver.

Initially part of EC-GSM but now a separate 3GPP item, eDRX improves the power efficiency – and therefore the battery life – for many use cases. eDRX improves the idle mode behavior by allowing the use of a number of inactivity timers, where the device can choose to tune in to the network and listen for downlink pages and traffic.


EC-GSM
Global solution for cellular IoT
Supported on legacy GSM equipment
Thin layer GSM
Leverages existing module ecosystem

Figure 10: EC-GSM.

EC-GSM extends the data handling and power efficiency advantages that GSM/GPRS technology already offers for MTC, and it will help operators extend the service life of their huge 2G legacy base.

LTE-M – SUPPORTING A WIDE RANGE OF MASSIVE IOT USE CASES

LTE is the leading mobile broadband technology and its coverage is expanding rapidly. So far, the focus has been on meeting the huge demand for mobile data with highly capable devices that utilize new spectrum. With features like Carrier Aggregation, MIMO and Lean Carrier, the gigabit per second performance for LTE cell throughput is now reaching levels that result in an excellent mobile broadband user experience.

The advent of LTE-M signifies an important step in addressing MTC capabilities over LTE. LTE-M brings new power-saving functionality suitable for serving a variety of IoT applications; Power Saving Mode and eDRX extend battery life for LTE-M to 10 years or more. LTE-M traffic is multiplexed over a full LTE carrier, and it is therefore able to tap into the full capacity of LTE. Additionally, new functionality for substantially reduced device cost and extended coverage for LTE-M are also specified within 3GPP.


LTE-M
Broadest range of cellular IoT capabilities
Wide range of bit-rates enabling advanced applications
Efficient co-existence with MBB traffic

Figure 11: LTE M.

NB-IOT – SUPPORTING ULTRA-LOW-END MASSIVE IOT APPLICATIONS

In addition to LTE-M, NB-IoT technology is being standardized in time for 3GPP Release 13. NB-IoT is a self-contained carrier that can be deployed with a system bandwidth of only 200kHz, and is specifically tailored for ultra-low-end IoT applications. It is enabled using new network software on an existing LTE network, which will result in rapid time to market.


NB-IoT
Scalable ultra-low-end cellular IoT solution
Ultra-low bit rates and extreme coverage
789
Native narrowband solution
In-band
LTE
200kHz

Figure 12: NB-IoT.

NB-IoT provides lean setup procedures, and a capacity evaluation indicates that each 200kHz NB-IoT carrier can support more than 200,000 subscribers. The solution can easily be scaled up by adding multiple NB-IoT carriers when needed. NB-IoT also comes with an extended coverage of up to 20dB, and battery saving features, Power Saving Mode and eDRX for more than 10 years of battery life.


NB-IoT
GSM
Standalone
200kHz
Guard band
LTE
LTE
200kHz
In-band
LTE
200kHz

Figure 13: NB-IoT deployment.

NB-IoT is designed to be tightly integrated and interwork with LTE, which provides great deployment flexibility. The NB-IoT carrier can be deployed in the LTE guard band, embedded within a normal LTE carrier, or as a standalone carrier in, for example, GSM bands.

- Standalone deployment in a GSM low band: this is an option when LTE is deployed in a higher band and GSM is still in use, providing coverage for basic services.
- Guard band deployment, typically next to an LTE carrier: NB-IoT is designed to enable deployment in the guard band immediately adjacent to an LTE carrier, without affecting the capacity of the LTE carrier. This is particularly suitable for spectrum allocations that do not match the set of LTE system bandwidths, leaving gaps of unused spectrum next to the LTE carrier.
- Efficient in-band deployment, allowing flexible assignment of resources between LTE and NB-IoT: it will be possible for an NB-IoT carrier to time-share a resource with an existing LTE carrier. The in-band deployment also allows for highly flexible migration scenarios. For example, if the NB-IoT service is first deployed as a standalone deployment in a GSM band, it can subsequently be migrated to an in-band deployment if the GSM spectrum is re-farmed to LTE, thereby avoiding any fragmentation of the LTE carrier.

NB-IoT reduces device complexity below that of LTE-M with the potential to rival module costs of unlicensed LPWA technologies, and it will be ideal for addressing ultra-low-end applications in markets with a mature LTE installed base.

CONCLUSION

Uptake of Massive IoT is set to take off, and operators have a unique opportunity to drive the implementation of new IoT applications by offering affordable connectivity on a global scale.

For IoT applications, existing cellular networks offer distinct advantages over alternative WAN technologies, such as unlicensed LPWA. The global reach, QoS, ecosystem, TCO, scalability, diversity and security of cellular networks are all vital factors that can support the fast uptake and success of IoT. Enabled by new software in existing legacy networks, cellular networks can support a diverse range of IoT applications – ensuring the lowest possible TCO.

3GPP standardization work for GSM and LTE, and the recent addition of NB-IoT, is further improving the ability of cellular networks to address the Massive IoT market, where ultra-low end-to-end cost is a prerequisite.

GSM/GPRS, which already serves the majority of cellular-based MTC applications, is evolving with a new EC-GSM standard, which delivers significantly better energy efficiency and increased coverage. EC-GSM enhancements will cement GSM's position as a highly relevant connectivity platform for low-end, Massive IoT applications globally.

New downsized NB-IoT and LTE-M chipsets, designed for MTC, and features that improve both coverage and device battery life will boost the ability of LTE infrastructure to address the IoT market. One network that supports all applications – from advanced mobile broadband services, VoIP and all kinds of low- to high-end IoT use cases – creates a very strong value proposition.

Whether operators choose the GSM, NB-IoT or LTE-M track – or a combination of these – will depend on several factors such as technology coverage, future technology strategies and targeted market segments. Whichever path they take, they have a huge opportunity to benefit from the emerging IoT revolution. Operators can choose to continue offering telecom-grade connectivity as they do today, or they can evolve to become a platform or fully-fledged IoT service provider targeting a larger slice of future IoT revenues.

GLOSSARY

EC-GSM	Extended Coverage GSM
eDRX	extended discontinuous reception
eUICC	embedded Universal Integrated Circuit Card
IoT	Internet of Things
LPWA	low power wide area
LTE-M	LTE for machine-type communication
M2M	machine-to-machine
MIMO	multiple-input, multiple-output
MTC	machine-type communication
NB-IoT	narrowband IoT
TCO	total cost of ownership
UICC	Universal Integrated Circuit Card
WAN	wide area network

REFERENCES

[1] Ericsson, Ericsson Mobility Report, November 2015, available at: http://www.ericsson.com/res/docs/2015/mobility-report/ericsson-mobility-report-nov-2015.pdf

[2] Gartner, Gartner Says the Internet of Things Installed Base Will Grow to 26 Billion Units By 2020, December 2013, available at: http://www.gartner.com/newsroom/id/2636073

[3] Ericsson, White Paper: Machine-to-Machine – exploring potential operator roles, September 2014, available at: http://www.ericsson.com/res/docs/whitepapers/wp-m2m.pdf

© 2016 Ericsson AB – All rights reserved

THE Next Wave

The National Security Agency's review of emerging technologies

Vol. 21 | No. 3 | 2017

[Photo credit: StuPorts, AlexLMX/iStock/Thinkstock]

Research Directorate
Advancing Intelligence Through Science

THE
Next Wave
The National Security Agency's review of emerging technologies

Editor's column

While the global mobile telecommunications industry has been attempting to keep pace with ever-changing technology and consumer needs, it has not had a strong development roadmap like the International Technology Roadmap for Semiconductors (ITRS). Instead, mobile technology's development has been characterized by multinational companies pushing proposed standards for adoption by international standards bodies. These standards are subsequently adopted in a haphazard, nation-by-nation process. However, consumer desire for faster, more fully featured mobile devices has proven to be as strong a driving force as the ITRS, and has led the industry to roll out generations of new technology on a roughly 10-year basis (approximate dates: 1G - 1981, 2G - 1992, 3G - 2001, and 4G - 2009). This decade-by-decade introduction of new mobile communication technology has led to the common prediction for fifth-generation (5G) mobile to appear around 2020, in keeping with the observed linear cadence.

But why create 5G mobile anyway? The push for 5G is not just a mad rush to keep pace and provide more bandwidth to services that can already stream high-definition video. The Internet of Things (IoT; see TNW Vol. 21 No. 2) is a major driving force (among several) behind technologies being developed for 5G mobile. As personal mobile devices are more enmeshed into machine-to-machine (M2M) communications and the number of IoT sensors explodes, 5G technologies must address several needs: high-speed data rates for many more users, increased density of users, greatly increased simultaneous connections, and reduced latencies. These needs will propel many of the technologies that Dr. Farroha et al. describe in their introduction to 5G article (page 2).

One of those technologies, virtualization, has been instrumental in making efficient use of servers (virtual machine or VM) and computer networking (software-defined networking or SDN). Over the course of continuing improvement to 4G implementations, the networks are evolving into an all-digital Internet protocol packet-switched system. This evolution means that those efficiencies developed for SDN and used in computing can be applied to mobile networking. We can see this application in more depth in the article on 5G virtualization (page 16).

Several markets have already taken advantage of 4G mobile technology, most notably media. This market is expected to expand with 5G as consumer desire for high-resolution video and augmented/virtual reality increases. Automotive, energy, health, and public safety are several areas of M2M that will be greatly enhanced by increased bandwidth and, most importantly, low-latency networks. On 13 December 2016, the US Department of Transportation proposed a rule for vehicle-to-vehicle communication and announced a vehicle-to-infrastructure communication rule to be proposed. The article on 5G and the automotive industry (page 20) provides insight into how this market segment is enhanced by 5G connectivity.

Although mobile technological developments are typically categorized into different generations, each generation covers a vast array of individual technologies and protocols that roll out as they mature. In practice, mobile service providers often work across a range of generations. This is highlighted by the fact that in many cases voice calling is handled by the 3G network while data is handled on the 4G network. Domestically, T-Mobile and AT&T did not enable voice over LTE (VoLTE) until May 2014, and did not meet the International Telecommunication Union (ITU) standard until Verizon launched LTE-Advanced in August 2016.

Many factors can impact the broad global deployment of 5G networks, such as existing technologies, geography, spectrum, and national interests. Some countries may jump to the current network generation while others may delay deployment because their current networks are considered to be "good enough." The decreased per-customer costs of updating networks in densely populated countries makes it more attractive to keep on the leading edge. The increased data rates and simultaneous connections require increased spectrum allocations, which are handled by national regulatory organizations. Several countries, most notably South Korea, have tied their technological identity to the increased connectivity of next-generation wireless technologies. All these factors give rise to a patchwork international environment for 5G implementation.

Current forecasts for the rollout of 5G networks are in the 2020 time frame. Recent news indicates that it may be earlier than that. Samples of Qualcomm's new Snapdragon X50 4G/5G modem that uses the 27.5 gigahertz (GHz) to 28.35 GHz band—part of the spectrum opened by the Federal Communications Commission for 5G—will be available in the second half of 2017. Samsung and KT, one of South Korea's mobile providers, have announced that they will be the first to provide mobile 5G trial service at the PyeungChang 2018 Winter Olympic Games. Undoubtedly, this trial 5G service will not be fully compliant with 5G standards, which have yet to be adopted. However, we should expect things to advance quickly following the Korean introduction of 5G.

RECENT NEWS

[1] "AT&T launches first 5G business customer trial with Intel and Ericsson." AT&T. 5 Dec 2016. Available at: http://about.att.com/story/att_launches_first_5g_business_customer_trial_with_intel_and_ericsson.html.

[2] "Government must take action now to secure our connected future so we are ready for 5G, and essential services are genuinely available where they are needed." GOV.UK. 14 Dec 2016. Available at: https://www.gov.uk/government/news/government-must-take-action-now-to-secure-our-connected-future-so-we-are-ready-for-5g-and-essential-services-are-genuinely-available-where-they-are-n.

[3] Qualcomm Incorporated. "Qualcomm, Ericsson and SK Telecom announce collaboration on 5G NR trials to accelerate wide-scale 5G deployments." *PR Newswire*. 19 Dec 2016. Available at: http://www.prnewswire.com/news-releases/qualcomm-ericsson-and-sk-telecom-announce-collaboration-on-5g-nr-trials-to-accelerate-wide-scale-5g-deployments-300381570.html.

[4] Reichert C. "Huawei and NTT DoCoMo reach 11Gbps speeds in 5G Japanese field trial. 16 Nov 2016. Available at: http://www.zdnet.com/article/huawei-and-ntt-docomo-reach-11gbps-speeds-in-5g-japanese-field-trial/.

Contents

2 Introducing 5G
Dr. Sam Farroha,
Jared S. Everett,
Jason J. Uher,
Jason R. Harper,
Jessica K. Bridgland, and
Pamela M. Patton

16 Virtualizing the 5G Architecture
Staff Writer

20 5G and the Automotive Industry
Staff Writer

25 FROM LAB TO MARKET

The Next Wave is published to disseminate technical advancements and research activities in telecommunications and information technologies. Mentions of company names or commercial products do not imply endorsement by the US Government. The views and opinions expressed herein are those of the authors and do not necessarily reflect those of the NSA/CSS.

This publication is available online at http://www.nsa.gov/thenextwave. For more information, please contact us at TNW@tycho.ncsc.mil.

Vol. 21 | No. 3 | 2017

Introducing 5G

Dr. Sam Farroha, Jared S. Everett (Johns Hopkins University Applied Physics Laboratory; JHU APL), Jason J. Uher (JHU APL), Jason R. Harper (JHU APL), Jessica K. Bridgland (JHU APL), and Pamela M. Patton (JHU APL)



[Photo credit: Juli_Rose/iStock/Thinkstock]

The evolution of modern cellular communications has been marked by a series of technology generations. Although the technology itself tends to evolve continuously, a new generation of standards marks a revolutionary step forward, with a substantial increase in system requirements to drive fundamentally new applications. With fourth-generation (4G) networks now widely deployed, the industry has turned its sights on "the next big thing." Fifth-generation (5G) networks are expected to enable a seamlessly connected society in the time frame beyond 2020 for both people and things, including vehicles, homes, smart cities, sensor networks, and the power grid. While the Long-Term Evolution (LTE) standard will continue to evolve and play a critical role in the wireless ecosystem, 5G represents an opportunity to architect a new system that is fundamentally different without the constraint of backward compatibility with existing technologies.

What is 5G?

Although there are as yet no standards for 5G mobile networks, a number of key technology trends have emerged. This article describes seven major technology trends that will pave the way to the next generation of 5G networks.

- **New Flexible Radio Access Technology (RAT):** A new, non-backward-compatible RAT will be defined for 5G that is distinct from previous generations, such as 4G LTE and its evolution. New multiple access schemes under consideration include various modified Orthogonal Frequency-Division Multiplexing (OFDM)-based solutions with improved spectral efficiency. The new RAT must be flexible enough to accommodate a variety of traffic types with often conflicting radio requirements. The concept of a unified air interface has been proposed for multiplexing multiple physical layer (PHY) regions with different characteristics [e.g., transmission time interval (TTI), subcarrier spacing] on a contiguous block of spectrum [1, 2, 3]. Spectrum for the new RAT will include existing bands below 6 gigahertz (GHz), as well as new centimeter-wave (cmWave) and millimeter-wave (mmWave) bands in the 6- to 100 GHz range [4]. The new RAT must also support significantly reduced latency, with as low as 100 microsecond (µs) transmission time interval (TTI) at the PHY for the ultra-reliable and low-latency communications (URLLC) use case [5]. Lastly, to further improve spectral efficiency, full-duplex transmission schemes have been proposed, potentially allowing the same time-frequency resources to be used for uplink and downlink transmissions simultaneously [6].
- **Virtualization:** Software-Defined Networking (SDN) and Network Function Virtualization (NFV) are two key architecture concepts in development to support the flexibility and mobility demands of the 5G network infrastructure [7, 8, 9]. Virtualization of network functions, which were traditionally implemented in hardware, will pave the way for commercial telecommunications operators and service providers to introduce new features and integrate new standards releases at an accelerated rate. NFV enables providers to move toward a decentralized network to increase flexibility, pushing core functions toward the edge to reduce latency, and virtualizing those functions on cloud-based servers. The proposed Cloud Radio Access Network (C-RAN) architecture, a specific use case of NFV applied to the RAN, uses a pooled architecture of baseband resources to increase scalability, physical layer flexibility, and spectral efficiency [7, 10].
- **Millimeter Wave (mmWave) Communications:** The term mmWave refers to carrier frequencies in the International Telecommunication Union (ITU) extremely high-frequency (EHF) band, from 30 to 300 GHz. Within the context

of 5G, the term has recently been loosely used by industry to refer to the higher frequencies from 6 to 100 GHz that are under consideration for new mobile spectrum [11, 12]. mmWave technologies are becoming an increasingly attractive solution to the problems of frequency reuse, cell density, raw data throughput, and antenna array size. This has led to a synergy between mmWave, small cell deployments, and massive multiple-input, multiple-output (MMIMO) techniques [13, 14].

- **Massive Multiple-Input, Multiple-Output (MMIMO) Techniques:** MMIMO is a new concept in antenna arrays that provides a number of advantages over traditional MIMO arrays currently deployed in 4G networks. Traditional MIMO arrays use only a few antenna elements (i.e., 2 to 16), whereas MMIMO uses a large number of elements in the array, currently considering a range of 128 to 512 at a minimum. Highly directional beamforming to multiple users simultaneously allows for increased user density and higher aggregate cell throughput [15]. So-called hybrid MMIMO has also been proposed; it combines beam steering with array processing techniques, such as spatial multiplexing, to increase single-user throughput [16].
- **Heterogeneous Networks (HetNets):** HetNets expand the mobile access network capacity by coordinating small cells with larger macro cells or offloading traffic to wireless local area network (WLAN) access points. There are two types of heterogeneity: 1) various cell sizes (e.g., macro, pico, femto) and 2) heterogeneous RATs [e.g., third-generation (3G), 4G, 5G, WLAN]. Small cells may include femto, pico, and micro cells, which can range in capacity from less than 10 to several hundred simultaneous active users. While HetNet deployments have already been introduced in 4G networks, network densification through the aggressive deployment of small cells is expected to increase significantly in future 5G networks [17, 18].
- **Native Machine-Type Communications (MTC) Support:** 5G networks are expected to incorporate a new model for connectivity specifically designed for MTC [19]. With the significant increase in connected machines over the last several years, a new 5G standard is seen as a prime opportunity to ensure new RATs can efficiently support a large number of connected devices with their own unique access constraints. Two categories of MTC are discussed: 1) general MTC and 2) vehicle-to-everything (V2X) MTC. General MTC devices have a few unique design and deployment considerations—namely, lower bandwidth needs, stringent power budgets, and relaxed latency requirements. V2X MTC devices, in contrast, require low-latency communications, out-of-coverage networks, and limited operation on a subscription-free basis [20].
- **Device-centric Architectures:** New network architectures will focus on a uniform quality of experience (QoE) for the user device, in contrast to traditional base-station-centric architectures. A number of new device-centric approaches are under consideration: decoupling the user plane and control plane, decoupling the uplink and downlink, and device-to-device communications [4, 21]. Another novel proposal is the user-centric cell or virtual cell model, which uses distributed beamforming and decoupled user/control planes to create a virtual cell around each user [2, 3]. Because the virtual cell follows the user, QoE variations are reduced and the cell-edge problem is mitigated. New device-centric architectures may significantly alter the traditional concept of cell handovers or eliminate it entirely.

Many of these technologies are already being added to the evolution of existing technologies beyond 4G, such as LTE-Advanced Pro [22].

In 2015, there was a significant increase in industry activities surrounding 5G networks. Major standards bodies, including the ITU and the Third-Generation Partnership Project (3GPP), reached important milestones in the early development of the eventual 5G standards. In September, the ITU published its vision for 5G networks [19]. The vision for International Mobile Telecommunications for 2020 and beyond (IMT-2020) defines three future-looking, high-level use cases for 5G:

- **Enhanced Mobile Broadband (eMBB):** This is generally a human-centric use case driven by the exponential increase in demand for mobile access to multimedia content, services, and data.

The eMBB use case will come with new application areas and requirements that go beyond existing mobile broadband applications for improved performance and increasingly seamless user experience. This use case covers a range of scenarios, including wide-area coverage and localized high-throughput spot coverage, which will have different requirements.

- **Massive Machine-Type Communications (mMTC):** This use case is characterized by a large number of connected devices typically transmitting a relatively low volume of nondelay-sensitive data. Devices are intended to be low cost and have a very long battery life.
- **Ultra-Reliable and Low-Latency Communications (URLLC):** This use case is characterized by stringent requirements for latency, throughput, and availability. Examples include wireless control of industrial manufacturing processes, remote medical surgery, distributed smart grid automation, and transportation safety [e.g., vehicle-to-vehicle (V2V) or vehicle-to-everything (V2X) communication]. Many companies have referred to this use case as critical MTC (cMTC) or ultra-reliable MTC (uMTC). However, based on the ITU definition in [19], this use case is not strictly limited to MTC applications.

It is important to consider that the applications that will use 5G technology do not necessarily correspond to a single use case but are more accurately described as a combination of multiple use cases. Figure 1 illustrates some examples of currently envisioned 5G applications and their relationship to these three IMT-2020 use cases [19]. Figure 2 illustrates eight key capabilities identified by ITU for IMT-2020 and their relative importance to the same three use cases [19]. Furthermore, additional future use cases are expected to emerge but cannot be accurately predicted (i.e., what will be the "killer app" in 2025?). Therefore, it is desired that 5G standards will provide the flexibility to adapt to new use cases.


Enhanced Mobile Broadband
Gigabytes in a second
3D video, UHD screens
Work and play in the cloud
Smart Home/Building
Augmented reality
Industry automation
Voice
Mission critical application, e.g. e-health
Self Driving Car
Smart City
Future IMT
Massive Machine Type Communications
Ultra-reliable and Low Latency Communications

FIGURE 1. 5G use cases as defined by ITU for IMT-2020 [19].


Enhanced Mobile Broadband
Peak Data Rate
High Importance
User Experienced Data Rate
Medium
Low
Area Traffic Capacity
Spectrum Efficiency
Network Energy Efficiency
Mobility
Massive machine type communications
Ultra-reliable and low latency communications
Connection Density
Latency

FIGURE 2. Eight key capabilities and their relative importance to 5G use cases [19].

5G Standardization

Development work toward 5G is well under way. Standards bodies are actively working on new 5G mobile technologies to be deployed in the 2020 time frame. This section summarizes the activities and corresponding 5G development timelines for three major standards bodies: ITU, 3GPP, and the Institute of Electrical and Electronics Engineers (IEEE).

Standardization in ITU

ITU is the United Nations agency responsible for promoting worldwide improvement and rational use of information and communication technology. Its members include industry, academia, and standards organizations from more than 190 member nations. The ITU Radiocommunication Sector (ITU-R) works toward worldwide consensus in the use of terrestrial and space radiocommunication services, including mobile communication technologies. Although compliance with ITU-R recommendations is not mandatory, they nevertheless have a high degree of adoption worldwide and hold the status of international standards [23].

International Mobile Telecommunications framework

ITU-R Working Party 5D (WP 5D) is responsible for overall radio aspects of terrestrial mobile systems, referred to as International Mobile Telecommunications (IMT). The purpose of IMT is to provide high-quality mobile services with a high degree of interoperability worldwide. Since 2000, the ITU has developed the IMT standards framework in a manner that parallels cellular generations from an industry perspective. Although ITU-R WP 5D defines the requirements for IMT, it does not develop the actual radio technologies. Rather, candidate radio technologies are submitted for inclusion by external standards bodies, such as 3GPP and IEEE. For this reason, ITU-R WP 5D maintains strong cooperation with the major global standards bodies.

The first family of standards derived from the IMT concept (IMT-2000) aligned with 3G cellular. Radio technologies accepted into IMT-2000 included 3GPP Wideband Code-Division Multiple Access (WCDMA), 3GPP2 cdma2000, and IEEE 802.16 [i.e., Mobile Worldwide Wireless Interoperability for Microwave Access (WiMAX)]. The next generation of IMT standards (IMT-Advanced) aligned with 4G cellular. Radio technologies accepted into IMT-Advanced included 3GPP LTE-Advanced and IEEE 802.16m [i.e., Wireless Metropolitan Area Network (WMAN)-Advanced].

Timeline for IMT-2020

In 2012, ITU embarked on a program to develop "IMT for 2020 and beyond," setting the stage for emerging 5G research activities around the world. The program has since adopted the name IMT-2020 and forms the framework for the next generation of mobile broadband standards. The timeline for the development of IMT-2020 is shown in figure 3 [24]. The IMT 2020 timeline will essentially follow the same process used in the development of IMT-Advanced.

The IMT-2020 program is well under way, with a number of key milestones completed. In September 2015, ITU published its vision of the 5G mobile broadband connected society [19]. This document defined three high-level use cases for 5G, described earlier in this article, which have already been widely adopted by 3GPP and industry in general. In the next phase, the 2016–2017 time frame, ITU-R WP 5D will define in detail the performance requirements, evaluation criteria, and methodology for the assessment of the new IMT radio interfaces. It is anticipated that the time frame for proposals will be focused in 2018. In the 2018–2020 time frame, independent, external groups will evaluate proposals and the definition of the new radio interfaces to be included in IMT-2020 will take place. ITU-R WP 5D also plans to hold a workshop in late 2017 to discuss the performance requirements and evaluation criteria for candidate technologies for IMT-2020, as well as to provide an opportunity for presentations by potential proponents for IMT-2020 in an informal setting. The whole process is planned to be completed in 2020, when a new draft of the ITU-R recommendation with detailed


2014
2015
2016
2017
2018
2019
2020
WRC-15
WRC-19
5D #18
5D #19
5D #20
5D #21
5D #22
5D #23
5D #24
5D #25
5D #26
5D #27
5D #28
5D #29
5D #30
5D #31
5D^a Expert meeting
5D #32
5D^b #33
5D #34
5D #35
5D #36
Report Technology trends (M.2320)
Report IMT feasibility above 6 GHz
Recommendation Vision of IMT beyond 2020
Modifications of Resolutions 56/57
Background & Process
Technical Performance Requirements
Evaluation criteria & method
Requirements, Evaluation Criteria, & Submission Templates
Circular Letters & Addendum
Workshop
Proposals IMT-2020
Evaluation
Consensus building
Outcome & Decision
IMT-2020 Specifications

(a) – if needed focus meeting towards WRC-19 (non-Technology), (b) – focus meeting on Evaluation (Technology)

Note: While not expected to change, details may be adjusted if warranted.

FIGURE 3. Detailed timeline and process for IMT-2020 in ITU-R [24].

specifications for the new radio technologies will be submitted for approval within ITU-R [24].

Standardization in 3GPP

3GPP is the international standards body responsible for the development and maintenance of major second-generation (2G), 3G, and 4G cellular standards. The purpose of the organization is to produce interoperable cellular communications standards, as well as studies and reports that define 3GPP technologies. The following technologies are currently maintained and evolved by 3GPP:

- Global System for Mobile Communications (GSM), General Packet Radio Service (GPRS), and Enhanced Data Rates for GSM Evolution (EDGE);
- Universal Mobile Telecommunications System (UMTS), WCDMA, High-Speed Packet Access (HSPA), and HSPA Evolution (HSPA+); and
- LTE, LTE-Advanced, and LTE-Advanced Pro.

These 3GPP technologies are constantly evolving through a series of backward-compatible releases. Since the completion of the first LTE and Evolved Packet Core (EPC) specifications, 3GPP has become the focal point for mobile systems beyond 3G. Therefore, 3GPP is expected to be a critical player in the development of 5G, and their timeline will have a direct influence on the timeline of the emerging 5G market.

3GPP is currently defining a new 5G RAT and corresponding network architecture. These are being developed within 3GPP under the working names "new radio (NR)" and "next-generation (NextGen) architecture," respectively [25]. In October 2016, 3GPP announced that the new 3GPP system will officially be known by the name "5G" from Release 15 onward [26]. Some initial standardization steps that have been taken to date include the following:

- **SMARTER study item:** In March 2015, 3GPP Technical Specification Group (TSG) System Aspects (SA) began a study item on technology enablers for new 5G services and markets, known as the SMARTER study item [27]. The objective of this study was to develop high-level use cases and identify the related high-level potential requirements to enable 3GPP network operators to support new services and markets in 5G. Phase 1 of the SMARTER study item was completed in March 2016; results are documented in 3GPP Technical Report (TR) 22.891 to be included in Release 14 [28]. A total of 74 use cases were identified. This work prompted four building block studies that grouped the use cases into families with common requirements: massive Internet of Things (IoT), critical communications, eMBB, and network operation. The building block studies were completed in June 2016; results are documented in 3GPP TRs 22.861, 22.862, 22.863, and 22.864 to be included in Release 14 [29]. The results of the SMARTER study will form the basis for a work item to define normative stage 1 requirements for the next-generation 5G system. The work item is scheduled for completion in March 2017; results will be documented in 3GPP Technical Specification (TS) 22.261 to be included in Release 15 [29].
- **Study item on channel model for frequency spectrum above 6 GHz:** The first 5G study conducted by TSG RAN focused on developing new channel models to support high-frequency spectrum from 6 GHz to 100 GHz. The models consider a variety of scenarios including urban, rural, and indoor, as well as the impact of line-of-sight (LOS) versus non-LOS (NLOS). The study was completed in June 2016, and results are documented in 3GPP TR 38.900 to be included in Release 14 [30].
- **Study item on architecture for next-generation system:** In December 2015, 3GPP TSG SA approved a study item to design a system architecture for the next generation of mobile networks. The new architecture will support at least the new 5G RAT(s), the evolution of LTE, and non-3GPP access types and will minimize access dependencies. The study considers new approaches such as NFV and network slicing. The study item was scheduled for completion in December 2016; results will be documented in 3GPP TR 23.799 to be included in Release 14 [31].
- **Study item on scenarios and requirements for next-generation access technologies:** In December 2015, 3GPP TSG RAN approved a study item to develop deployment scenarios and requirements of next-generation access

technologies. The study identifies 12 deployment scenarios that are more diverse than those originally envisioned for legacy RATs, such as LTE and its predecessors. It also identifies key performance indicators (KPIs) and other requirements for 5G NR. The bulk of the study was completed in September 2016 to provide guidance to the ongoing technical work being performed in the RAN working groups. However, the study item will remain open until March 2017 to match the IMT-2020 timeline and ensure all IMT-2020 requirements are captured. Final results are documented in 3GPP TR 38.913 to be included in Release 14 [32, 4].

- **Study item on NR access technology:** In March 2016, 3GPP TSG RAN approved a study item to develop the 5G NR access technology capable of meeting the broad range of use cases defined for 5G. The study seeks to develop a single technical framework capable of addressing all usage scenarios and requirements defined in TR 38.913 for eMBB, mMTC, and URLLC, with an emphasis on forward compatibility. The study is scheduled for completion in March 2017; results will be documented in 3GPP TR 38.912 to be included in Release 14 [1].

5G standardization activities in 3GPP will continue through 2020 and beyond, as described next.

Emerging 3GPP standardization timeline

In March 2015, 3GPP announced a tentative standardization timeline for 5G based on the ITU work plan timeline for IMT-2020 [33]. Since then, a more detailed timeline has come into focus as study items have commenced and completed, and as the 3GPP TSGs coordinate for the initial release of 5G. The timeline shown in figure 4 is a composite from multiple sources.


2015
2016
2017
2018
2019
2020
2021
ITU
Vision
IMT-2020 Requirements
IMT-2020 Proposals
IMT-2020 Specs
3GPP
Rel-13
Rel-14
Rel-15
Rel-16
Rel-17
SI: SMARTER
SI: Channel Models
SI: 5G NextGen Architecture
SI: Scenarios & Reqirements for NR
SI: 5G NR
Other 5G Study Items
5G Phase 1 Specification Complete (Rel-15)
5G Phase 2 Specification Complete (Rel-16)
5G Phase 1 Commercial Deployment
5G Phase 2 Commercial Deployment
5G
5G Phase 1 Work Items
5G Phase 2 Work Items
5G Evolution
LTE
Continued LTE Evolution

FIGURE 4. Emerging 5G standardization timeline for 3GPP. (Figure is a composite from [34] and [35] that includes additional data from various sources.)

The initial 5G study items in TSG SA and TSG RAN commenced in 2015 and 2016, as described previously. These initial 5G study items will be included in 3GPP Release 14. This work is carried out in parallel with ongoing LTE work. At the 3GPP plenary meeting in June 2016, the TSGs agreed on a work plan for the first release of 5G in 3GPP Release 15, including a clear work division between the TSGs [25].

5G work items were scheduled to begin in December 2016 for TSG SA and March 2017 for TSG RAN. The Phase 1 5G work items will fall into Release 15, with planned completion in June 2018. Additional 5G study items will continue during Release 15 in support of Phase 2. Subsequently, the Phase 2 5G work items will fall into Release 16, which will be completed around December 2019 in time for the final submission to ITU for IMT-2020. Phase 1 commercial deployments are expected to begin in 2020, followed by Phase 2 deployments in the 2021–2022 time frame. However, early pre-5G mmWave deployments may emerge in limited markets, such as South Korea or the United States, before 2020.

For example, Verizon Wireless has announced its plans to pilot a 28-GHz mmWave deployment in the United States for fixed wireless applications starting in 2017 [36]. To support this effort, the Verizon 5G Technology Forum (V5GTF)—an industry consortium led by Verizon—published an open radio interface specification in July 2016 [37]. The Verizon specification uses an OFDM-based PHY similar to time-division LTE (TD-LTE) with enhanced beamforming for operation in 28 and 39 GHz mmWave spectrum. However, with the initial focus on fixed wireless, the first release does not support user mobility. The Verizon specification can be considered pre-5G in the sense that it supports new mmWave capabilities beyond 4G but does not address all the use cases and associated requirements for 5G. The Verizon specification is expected to be incompatible with the eventual 3GPP 5G standard, potentially leading to market fragmentation [38].

3GPP phased approach to 5G standardization

3GPP TSG RAN will take a two-phased approach to developing the new 5G RAT [35]. The Phase 1 standard will define a new, non-backward-compatible 5G RAT. A subset of prioritized features and use cases will be addressed in Phase 1 to allow for early commercial deployments targeted for the year 2020. The Phase 2 standard will implement the full set of features and use cases necessary to meet the requirements for 5G. An initial proposal will be submitted to ITU as a candidate radio interface technology for IMT-2020 by the June 2019 submission deadline. The Phase 2 standard will later form the final submission around December 2019. The Phase 1 standard will be designed for forward compatibility with Phase 2 [35]. Forward compatibility means that Phase 1 must be designed from the beginning to optimally accommodate all of the features and use cases expected to be added later in Phase 2, even though those features are not yet fully implemented. Although the forward-compatibility requirement may sound straightforward, it represents a fundamental shift from the normal 3GPP standardization process, which historically has focused on a series of backward-compatible releases.

While prioritization of features between the two phases has been a topic of much debate, it is clear that the 5G Phase 1 standard will support tight interworking with LTE to simplify initial rollout. The phased approach and tight interworking with LTE means that elements of the LTE system architecture may persist in 5G deployments for some time to come. This implies that current and future work on LTE, LTE-Advanced, and LTE-Advanced Pro networks and technologies may have direct applicability to eventual 5G network deployments.

Standardization in IEEE

Initial 5G standards activities within the IEEE suggest that they do not intend to be a direct competitor with organizations like 3GPP on the radio interface between the RAN and the user equipment. Instead, IEEE has begun developing complementary technologies to support other communications requirements within the 5G ecosystem. In 2016, IEEE established two new working groups related to 5G: IEEE 1914 and IEEE 1918.

IEEE 1914 is the Next Generation Fronthaul Interface Working Group. This working group is currently developing two standards: the 1914.1 standard for packet-based fronthaul transport networks and the 1914.3 standard for radio over Ethernet encapsulations and mappings [39, 40]. These standards focus on the fronthaul interface within the RAN between baseband units (BBUs) and remote radio heads (RRHs) to support novel RAN architectures like C-RAN, and antenna techniques like MMIMO and coordinated multi-point (CoMP) transmission and reception. The projected completion dates for these standards are August 2018 for 1914.1 and October 2017 for 1914.3.

IEEE 1918 is the Tactile Internet Working Group. This working group is currently developing the 1918.1 standard, which defines a framework for the Tactile Internet [41]. The purpose of this framework is to establish a basis for the rapid development of the Tactile Internet as a 5G and beyond application, with the expectation of additional IEEE 1918 standards to follow. The projected completion date for the 1918.1 standard is October 2018.

With respect to IMT-2020, IEEE may seek to expand the role of WLAN in 5G as a complementary radio interface for next-generation HetNets. In September 2016, the IEEE 802.11 working group sent a liaison statement to 3GPP TSG RAN and TSG SA inviting them to consider the use of IEEE 802.11-based WLAN in unlicensed spectrum as a complementary means of meeting the performance requirements of IMT-2020, potentially leading to inclusion in a joint submission to IMT-2020 [42]. This approach would be a logical extension of the increasing level of interworking between LTE and WLAN in recent standards releases. WLAN is already widely used in 3GPP networks for high data rate offloading.

Recent enhancements in radio-level interworking have increased the efficiency of these networks. Enhancements include LTE-WLAN Aggregation (LWA) and LTE WLAN Radio Level Integration with IPsec Tunnel (LWIP) in 3GPP Release 13, with further enhancements in 3GPP Release 14. Although 3GPP declined to make a decision at the September 2016 plenary meeting, the concept of a potential joint submission could represent a novel approach to IMT-2020. In contrast, previous generations of IMT saw IEEE in competition with 3GPP, with the submission of the IEEE 802.16 WiMAX family of standards to IMT-2000 and IMT-Advanced as a direct competitor in the 3G and 4G markets.

Conclusion

This article provided an introduction to major technology trends in the emergence of next-generation 5G mobile networks. These networks are expected to see initial commercial deployment starting around the year 2020. Early 5G standardization activities in the ITU, 3GPP, and IEEE were addressed.

For further information on the latest developments in 5G, the interested reader is directed to the following resources. ITU publications for IMT-2020 can be found on the IMT-2020 web page [24]. Notable documents include the ITU vision for IMT-2020 [19] as well as the technical performance requirements for IMT-2020 (scheduled for completion in February 2017). The 3GPP web site (www.3GPP.org) is the most direct source for 3GPP-related technical information. 3GPP press releases provide high-level summaries of ongoing standards activities and often include links to more detailed further reading. The latest versions of the 3GPP TR and TS documents mentioned in this article can be accessed there as well. Information on the IEEE 1914.1, 1914.3, and 1918.1 standards can be found in the approved project authorization request (PAR) documents [39, 40, 41] and the corresponding working group web pages. Lastly, the Verizon mmWave specification is available on the V5GTF website (www.5GTF.org). This pre-5G specification defines layers 1 to 3 of an open radio interface using a document structure similar to that of LTE.

References

[1] 3GPP TSG RAN. "Revision of SI: Study on new radio access technology." September 2016. 3GPP Document TD RP-161596. Available at: http://www.3gpp.org/ftp/tsg_ran/TSG_RAN/TSGR_73/Docs/RP-161596.zip.

[2] Huawei. "Vision on 5G radio access technologies." September 2015. 3GPP Document RWS 150006. Available at: ftp://ftp.3gpp.org/workshop/2015-09-17_18_RAN_5G/Docs/RWS150006.zip.

[3] ZTE. "Considerations on 5G key technologies and standardization." September 2015. 3GPP Document dRWS 150024. Available at: ftp://ftp.3gpp.org/workshop/2015-09-17_18_RAN_5G/Docs/RWS 150024.zip.

[4] 3GPP. "3GPP TSG RAN study on scenarios and requirements for next generation access technologies." October 2016. 3GPP Specification TR 38.913, Release 14, Version 14.0.0. Available at: http://www.3gpp.org/DynaReport/38913.htm.

[5] Fettweis G, Alamouti S. "5G: Personal mobile internet beyond what cellular did to telephony." *IEEE Communications Magazine*. February 2014; 52(2): 140-145. doi: 10.1109/MCOM.2014.6736754.

[6] Zhang Z, Chai X, Long K, Vasilakos AV, Hanzo L. "Full duplex techniques for 5G networks: Self-interference cancellation, protocol design, and relay selection." *IEEE Communications Magazine*. May 2015; 53(5): 128-137. doi: 10.1109/MCOM.2015.7105651.

[7] ITU-R. "Future technology trends of terrestrial IMT systems." November 2014. ITU-R Report M.2320-0. Available at: https://www.itu.int/dms_pub/itu-r/opb/rep/R-REP-M.2320-2014-PDF-E.pdf.

[8] 4G Americas. "5G: 4G Americas' recommendations on 5G requirements and solutions." October 2014. Available at: http://www.4gamericas.org/files/2714/1471/2645/4G_Americas_Recommendations_on_5G_Requirements_and_Solutions_10_14_2014-FINALx.pdf.

[9] 3GPP. "3GPP NFV study: Management of mobile networks that include virtualized network functions (MANO)" [Press release]. 5 Oct 2015. Available at: http://www.3gpp.org/news-events/3gpp-news/1738-sa5_nfv_study.

[10] Checko A, Christiansen H, Yan Y, Scolari L, Kardaras G, Berger M, Dittman L. "Cloud RAN for mobile networks—A technology overview." *IEEE Communication Surveys and Tutorials*. January 2015; 17(1): 405-426. doi: 10.1109/COMST.2014.2355255.

[11] ITU-R. "Technical feasibility of IMT in bands above 6 GHz." June 2015. ITU-R Report M.2376-0. Available at: www.itu.int/dms_pub/itu-r/opb/rep/R-REP-M.2376-2015-PDF-E.pdf.

[12] Rangan S, Rappaport T, Erkip E. "Millimeter-wave cellular wireless networks: Potentials and challenges." In: *Proceedings of the IEEE;* 2014 January; 102(3). doi: 10.1109/JPROC.2014.2299397.

[13] Swindlehurst AL, Ayanoglu E, Heydari P, Capolino F. "Millimeter-wave massive MIMO: The next wireless revolution?" *IEEE Communications Magazine*. September 2014; 52(9): 56-62. doi: 10.1109/MCOM.2014.6894453.

[14] Straight Path Communications. "A straight path toward 5G." September 2015. 3GPP Document RWS150087. Available at: ftp://ftp.3gpp.org/workshop/2015-09-17_18_RAN_5G/Docs/RWS150087.zip.

[15] Hoydis J, ten Brink S, Debbah M. "Massive MIMO: How many antennas do we need?" In: *Proceedings of the 49th Annual Allerton Conference on Communication, Control, and Computing*; 2011 Sep 27-28; Monticello, IL; p. 545–550. doi: 10.1109/Allerton.2011.6120214.

[16] InterDigital. "Roadmap for 5G radio standardization in 3GPP." September 2015. 3GPP Document RWS 150030. Available at: ftp://ftp.3gpp.org/workshop/2015-09-17_18_RAN_5G/Docs/RWS 150030.zip.

[17] Wannstrom J, Mallinson K. "Heterogeneous networks in LTE." Available at: http://www.3gpp.org/technologies/keywords-acronyms/1576-hetnet.

[18] Bangerter B, Talwar S, Arefi R, Stewart K. "Networks and devices for the 5G era." *IEEE Communications Magazine*. February 2014; 52(2): 90–96. doi: 10.1109/MCOM.2014.6736748.

[19] ITU-R. "IMT vision—Framework and overall objectives of the future development of IMT for 2020 and beyond." September 2015. ITU-R Recommendation M.2083-0. Available at: http://www.itu.int/rec/R-REC-M.2083.

[20] General Motors Research. "Towards 5G: An automotive perspective." September 2015. 3GPP Document RWS 150011. Available at: ftp://ftp.3gpp.org/workshop/2015-09-17_18_RAN_5G/Docs/RWS 150011.zip.

[21] Boccardi F, Heath Jr. R, Lozano A, Marzetta T, Popovski P. "Five disruptive technology directions for 5G." *IEEE Communications Magazine*. February 2014; 52(2): 74-80. doi: 10.1109/MCOM.2014.6736746.

[22] 3GPP. "LTE-advanced pro ready to go" [Press release]. 28 Oct 2015. Available at: http://www.3gpp.org/news-events/3gpp-news/1745-lte-advanced_pro.

[23] ITU-R. "ITU-R study groups." May 2013. Available at: http://www.itu.int/dms_pub/itu-r/opb/gen/R-GEN-SGB-2013-PDF-E.pdf.

[24] ITU-R. "ITU toward 'IMT for 2020 and beyond.'" Available at: http://www.itu.int/en/ITU-R/study-groups/rsg5/rwp5d/imt-2020/Pages/default.aspx.

[25] 3GPP. "3GPP on track to 5G" [Press release]. 27 Jun 2016. Available at: http://www.3gpp.org/news-events/3gpp-news/1787-ontrack_5g.

[26] 3GPP. "New partners at London 3GPP meeting" [Press release]. 24 Oct 2016. Available at: http://www.3gpp.org/news-events/3gpp-news/1800-pcg_37.

[27] 3GPP TSG SA. "New WID study on new services and markets technology enablers (FS_SMARTER) from S1-150300." March 2015. 3GPP Document SP-150142. Available at: ftp://ftp.3gpp.org/tsg_sa/TSG_SA/TSGS_67/Docs/SP-150142.zip.

[28] 3GPP. "3GPP TSG SA feasibility study on new services and markets technology enablers stage 1." June 2016. 3GPP Specification TR 22.891, Release 14, Version 14.1.0. Available at: http://www.3gpp.org/DynaReport/22891.htm.

[29] 3GPP. "SA1 completes its study into 5G requirements" [Press release]. 23 Jun 2016. Available at: http://www.3gpp.org/news-events/3gpp-news/1786-5g_reqs_sa1.

[30] 3GPP. "3GPP TSG RAN study on channel model for frequency spectrum above 6 GHz." June 2016. 3GPP Specification TR 38.900, Release 14, Version 14.0.0. Available at: http://www.3gpp.org/DynaReport/38900.htm.

[31] 3GPP TSG SA. "New WID study on architecture for next generation system." December 2015. 3GPP Document TD SP-150853. Available at: http://www.3gpp.org/ftp/tsg_sa/TSG_SA/TSGS_70/Docs/SP-150853.zip.

[32] 3GPP TSG RAN. "New study item proposal: Study on scenarios and requirements for next generation access technologies." December 2015. 3GPP Document TD RP-152257. Available at: http://www.3gpp.org/ftp/tsg_ran/TSG_RAN/TSGR_70/Docs/RP-152257.zip.

[33] Flore D, Bertenyi B. "Tentative 3GPP timeline for 5G" [Press release]. 17 Mar 2015. Available at: http://www.3gpp.org/news-events/3gpp-news/1674-timeline_5g.

[34] Qualcomm. "5G: Views on technology and standardization." September 2015. 3GPP Document RWS 150012. Available at: ftp://ftp.3gpp.org/workshop/2015-09-17_18_RAN_5G/Docs/RWS 150012.zip.

[35] Flore D. "RAN workshop on 5G: Chairman summary." September 2015. 3GPP Document RWS 150073. Available at: ftp://ftp.3gpp.org/workshop/2015-09-17_18_RAN_5G/Docs/RWS 150073.zip.

[36] Alleven M. "Verizon's Shammo: 5G pilot in 2017 is all about fixed wireless, not mobility." *Fierce Wireless*. 2016 Apr 21. Available at: http://www.fiercewireless.com/tech/story/verizons-shammo-5g-pilot-2017-all-about-fixed-wireless-not-mobility/2016-04-21.

[37] V5GTF. "V5GTF Network and Signaling Working Group; Verizon 5G radio access; Overall description." June 2016. V5GTF Specification TS V5G.300, Release 1, Version 1.0. Available at: http://www.5gtf.org/V5G_300_v1p0.pdf.

[38] Alleven M. "Verizon's version of 5G not compatible with 3GPP's current specs—or easily upgradeable: Report." *Fierce Wireless*. 2016 Oct 28. Available at: http://www.fiercewireless.com/tech/verizon-s-version-5g-not-compatible-3gpp-s-current-specs-or-easily-upgradeable-report.

[39] IEEE. “IEEE P1914.1: Standard for packet-based fronthaul transport networks.” February 2016. IEEE Approved PAR P1914.1. Available at: http://sites.ieee.org/sagroups-1914/files/2016/06/P1914.1.pdf.

[40] IEEE. “IEEE P1904.3: Standard for radio over ethernet encapsulations and mappings.” June 2016. IEEE Approved PAR P1904.3. Available at: http://sites.ieee.org/sagroups-1914/files/2016/07/P1904.3.pdf.

[41] IEEE. “IEEE P1918.1: Tactile Internet: Application scenarios, definitions and terminology, architecture, functions, and technical assumptions.” March 2016. IEEE Approved PAR P1918.1. Available at: http://grouper.ieee.org/groups/1918/1/files/P1918.1.pdf

[42] 3GPP TSG RAN. “IEEE 802.11 Working group liaison on the role of WLAN in IMT-2020.” September 2016. 3GPP Document TD RP-161804. Available at: http://www.3gpp.org/ftp/tsg_ran/TSG_RAN/TSGR_73/Docs/RP-161804.zip.



[Photo credit: John Foxx/Stockbyte/Thinkstock]



[Photo credit: jauhari1/iStock/Thinkstock]

Virtualizing the 5G Architecture

Staff Writer

Virtually changing the 5G architecture

Virtualization is set to play a major role in the evolution of the fifth-generation (5G) core network. According to industry experts, 5G will use software-centric networking technologies such as software-defined networking (SDN) and network functions virtualization (NFV), and will be natively cloud based. If correct, this will represent a major transition in system architecture and will require much greater collaboration across the networking ecosystem. The push to incorporate more cloud- or software-based components is driven by the need for greater flexibility and scalability to respond to the demands of radio access technologies that offer more bandwidth, reduced latency, and stringent quality of service (QoS) requirements. The new 5G core network must be adaptable and better equipped to handle various devices and manage capacity in near-real time. Mobile network operators see the advances in cost and efficiency that virtualization brings to other market segments and will use the emerging 5G technology to determine if these same advances can benefit the mobile market [1, 2].

SDN and NFV are two key architecture concepts in development to support the flexibility and mobility demands of the 5G network infrastructure. Virtualizing network functions that were previously implemented in hardware will allow providers to introduce new features and integrate new standards at a faster rate. SDN/NFV provides an avenue for providers to decentralize their networks, thereby increasing flexibility and reducing latency. Two areas where SDN/NFV will benefit 5G networks, and in some cases even fourth-generation (4G) mobile technology, are network slicing and cloud-radio access network (C-RAN).

Network slicing

Network slicing would promote end-to-end mobile network virtualization by "slicing" the network into virtual channels. These virtual channels would be autonomous and encompass a set of resources—physical or virtual—including bandwidth on a network link, processing capacity of servers, processing capacity of network elements, as well as operations support system (OSS) and business support system (BSS) processes. Operators could then use these channels to dynamically devote the appropriate network resources to create a "lane" in the network specifically designed for a particular use or service. This would accommodate the many use cases being put forth for 5G. The operator-led Next Generation Mobile Networks (NGMN) Alliance has sought to define categories of 5G use cases (i.e., service types) that have distinct performance characteristics and commercial potential. In a 2015 white paper, the NGMN listed eight application categories for 5G [3, 4, 5]:

1. Broadband access in dense areas,
2. Broadband access everywhere,
3. Higher user mobility,
4. Massive Internet of Things,
5. Extreme real-time communications,
6. Lifeline communications,
7. Ultra-reliable communications, and
8. Broadcast-like services.

Each of these service types demand different network requirements that are determined by the types of traffic being sent and even the types of devices sending the traffic. For example, someone downloading cat videos will not have the same bandwidth or low latency requirements as a doctor in Los Angeles performing surgery virtually on a patient in Mumbai. The end-to-end notion of network slicing could be key to 5G's ability to effectively accommodate all of these disparate use cases.


5G slice 1 (smartphones)
Smartphones
RAT1
RAT2
CP/UP
CP
CP/UP
UP
UP
5G slice 2 (autonomous driving)
D2D
Automotive devices
RAT1
RAT2
CP/UP
CP/UP
Vertical AP
5G slice 3 (massive IoT)
Massive IoT devices
RAT3
RAT1
CP
UP
Other slices
...
Access node
Cloud node (edge & central)
Networking node
Part of slice

FIGURE 1. 5G's incorporation of SDN and NFV would allow network slices to be created dynamically and deployed as needed to accommodate a variety of scenarios [2].

The Open Networking Foundation, in an April 2016 white paper, called out SDN's ability to support multiple services over a common architecture as a key enabler for network slicing. SDN also allows for slices to be created dynamically and deployed as needed to accommodate a variety of scenarios (see figure 1). Currently, 4G mobile networks prioritize traffic to get a similar effect, but with more rigidity and limitations. However, as 4G networks incorporate SDN and NFV, network slicing will become an option.

C-RAN

There are more than six million base stations (excluding small cells) deployed worldwide across approximately five million different cell sites serving close to four billion users. The surge in demand for connectivity has network operators searching for ways to shrink their network footprint, lower operational expenditures (OPEX), and still meet users' demand for access. C-RAN meets these requirements and has either been implemented or trialed by several operators including Verizon, AT&T, KT (South Korea), and China Mobile. Radio base stations currently depend on special purpose-built hardware deployed at the cell site. The baseband processing unit (BBU) is the part of the RAN that is responsible for managing the radio functions (or all functions that require an antenna). The BBU is one of the parts of the RAN that can be moved to a central location, creating a pool of BBUs to serve multiple base stations. C-RAN aims to centralize and virtualize baseband processing to reduce cell site costs and enable coordinated scheduling of resource blocks across a coverage area [6].

Figure 2 illustrates the evolution from the classic RAN model to a C-RAN setup. On the left, the classic model has the BBU deployed at the cell site connecting to the core network over IP/Ethernet transport. Any coordination between cell sites takes place over the X2 interface, which allows two sites to communicate. In a C-RAN architecture, the BBUs are pooled at a location away from the cell site. Pooling BBUs negates the need for the X2 interface as communications between cell sites now takes place internally. This is one of the reasons for the increased performance in C-RANs. The C-RAN model also makes updating the waveform and protocols easier as it only requires a software upgrade at the centralized BBU and not at each individual cell site

The move to a C-RAN architecture increases the flexibility of the network by allowing providers to, in theory, even change the types of RANs used—from 3G to 4G. For instance, in an area that has a mix of 3G and 4G users, operators can rebalance radio frequency resources by shifting more resources to 4G when 4G



FIGURE 2. Unlike the traditional RAN model (on the left), C-RAN technology (on the right) pools the BBUs at a location away from the cell site offering an increase in performance and simpler upgrade path [6].

users are prevalent in the covered area. This shuffling of resources ensures that there is sufficient capacity for subscribers. C-RAN will also enable RAN-as-a-Service (RaaS), which will allow operators to rent RAN capacity to other operators.

Conclusion

On the face of it, virtualizing the 5G architecture seems like a necessary step towards preparing for the low latency requirements associated with 5G services. However, there are many uncertainties around 5G and a lack of visibility into what 5G will actually become through the standardization process, and at which phase different performance requirements will be supported or required. Phase II, the phase that is expected to meet International Mobile Telecommunication system for the year 2020 (IMT-2020) requirements, is expected in 2020. However, early versions or "pre-5G" offerings could be on the market before the final standard is approved. So, while these pre-5G solutions will have some 5G functionality, they will not field the full complement of improvements offered by an approved 5G system. For this reason, it is unclear to what degree virtualization techniques like C-RAN and network slicing will need to be implemented. It may come down to what the industry leaders in 5G implement in their "pre-5G" networks that will decide what a virtual 5G network will look like and when we can expect to see one.

References

[1] Farroha B, Everett JS, Uher JJ, Harper JR, Bridgland JK, Patton PM. "The status of 5G and the impact on current cellular architecture," 2016. College Park (MD): Laboratory for Telecommunications Sciences and The Johns Hopkins University Applied Physics Laboratory.

[2] Brown G. "5G use cases & candidate technologies," 2016. New York (NY): Heavy Reading.

[3] Hedman P. "Description of network slicing concept," 2016. NGMN Alliance. Version 1.0. Available at: https://www.ngmn.org/uploads/media/160113_Network_Slicing_v1_0.pdf.

[4] Marek S. "Dynamic network slicing is the 'secret sauce' behind 5G." SDxCentral. 2016 Aug 30. Available at: https://www.sdxcentral.com/articles/news/dynamic-network-slicing-secret-sauce-behind-5g/2016/08/.

[5] Paul M, Schaller S, Betts M, Hood D, Shirazipour M, Lopez D, Kaippallimalil J. "Applying SDN architecture to 5G slicing," 2016. Palo Alto (CA): Open Networking Foundation. Report No. TR-526. Available at: https://www.opennetworking.org/images/stories/downloads/sdn-resources/technical-reports/Applying_SDN_Architecture_to_5G_Slicing_TR-526.pdf.

[6] Brown G. "Cloud RAN: New network architectures & industry structures," 2016. New York (NY): Heavy Reading.

5G and the Auto

Staff Writer



[Photo credit: Chesky_W/iStock/Thinkstock]

Industry stakeholders envision 5G as a key enabler that allows network connectivity in vehicles to shift in status from an optional accessory to a core feature that supports not only the individual vehicle, but also communication with other vehicles and sensors that inform traffic, parking, and navigation—while also ensuring passenger safety and data security. For consumers, a connected vehicle provides a growing number of features and services that make the driving experience safer, convenient, and less costly. 5G connectivity will enable information from in-car sensors to continuously be passed to the cloud. By sharing information and alerts about micro-level weather, road temperature, surface conditions, and violent breaking ahead, more efficient and consistent traffic flows will be achieved that reduce congestion and emissions. The aggregated and interpreted data will provide more informed driving information, as well as alert and activate onboard safety systems to prevent accidents [1].

motive Industry



Autonomous vehicles

Autonomous vehicles—also referred to as driverless or piloted vehicles—are predicted to hit the market by 2020, but stable 5G infrastructure will play a key role, according to a white paper by ABI Research [2]. Estimates indicate that 5G latency could be as low as one millisecond (ms) over-the-air, and 5 ms end-to-end, enabling the following automotive use cases:

- Broadband multimedia streaming (driverless vehicles as mobile living rooms).
- Cloud services for vehicle lifecycle management, apps, security, and over-the-air updates (cloud-to-vehicle).
- Capturing or uploading huge volumes of sensor data for real-time traffic, weather, parking, and mapping services (vehicle-to-cloud).
- Cooperative mobility: low latency vehicle-to-vehicle and vehicle-to-infrastructure for active safety and autonomy [redundancy for advanced driver assistance systems (ADAS)] [2].

The current ADAS being delivered on 2016 vehicles already facilitate SAE Level 1 (see figure 1) and are beginning to incorporate features that would be considered Level 2. However, Level 4 and 5 capabilities may not be that far away. In October 2015, Robot Taxi, a joint venture between Japanese mobile Internet company DeNA and vehicle technology developer ZMP, announced that it would offer driverless transportation to about 50 people in an area near Tokyo. Its goal is to commercialize the service by 2020, in time for the Tokyo Olympics [1]. While Robot Taxi is shooting for full automation (Level 5) in time for the games, it is likely that the use of such vehicles will initially be limited to shuttling passengers between Olympic venues. However, this venture is particularly notable because the technology is brand-agnostic and can be retrofitted to any vehicle [4].

Clearly, experimentation with autonomous vehicles is increasing, and 2020 as a date for some form of commercial implementation is certainly feasible from a technology perspective. Probably the best-known self-driving car project belongs to Google, which was started in 2009 and has clocked more than two million miles on public roads to date [5]. However, Google is not alone; Tesla, BMW, Audi, Mercedes, and most recently GM, have all showcased self-driving concept cars and demonstration projects. In mid-October 2016, Tesla announced that all cars currently being produced in their factories would include the hardware needed for full self-driving capability at a level of safety far greater than that of a human driver. However, the company added that the technology first needed to be tested and calibrated via “millions of miles of real-world driving” before the hardware would be activated on consumer vehicles [6]. In addition to traditional car manufacturers, companies such as Uber and Chinese search giant Baidu are also working on autonomous technology and self-driving cars [1].



SAE level	Name	Narrative Definition	Execution of Steering and Acceleration/ Deceleration	*Monitoring* of Driving Environment	Fallback Performance of *Dynamic Driving Task*	System Capability *(Driving Modes)*
***Human driver* monitors the driving environment**						
0	**No Automation**	the full-time performance by the *human driver* of all aspects of the *dynamic driving task*, even when enhanced by warning or intervention systems	Human driver	Human driver	Human driver	n/a
1	**Driver Assistance**	the *driving mode*-specific execution by a driver assistance system of either steering or acceleration/deceleration using information about the driving environment and with the expectation that the *human driver* perform all remaining aspects of the *dynamic driving task*	Human driver and system	Human driver	Human driver	Some driving modes
2	**Partial Automation**	the *driving mode*-specific execution by one or more driver assistance systems of both steering and acceleration/ deceleration using information about the driving environment and with the expectation that the *human driver* perform all remaining aspects of the *dynamic driving task*	**System**	Human driver	Human driver	Some driving modes
***Automated driving system* (“system”) monitors the driving environment**						
3	**Conditional Automation**	the *driving mode*-specific performance by an *automated driving system* of all aspects of the dynamic driving task with the expectation that the *human driver* will respond appropriately to a *request to intervene*	System	**System**	Human driver	Some driving modes
4	**High Automation**	the *driving mode*-specific performance by an automated driving system of all aspects of the *dynamic driving task*, even if a *human driver* does not respond appropriately to a *request to intervene*	System	System	**System**	Some driving modes
5	**Full Automation**	the full-time performance by an *automated driving system* of all aspects of the *dynamic driving task* under all roadway and environmental conditions that can be managed by a *human driver*	System	System	System	**All driving modes**

FIGURE 1. SAE Levels of automation. The Society of Automotive Engineers (SAE) has defined levels of automation to clarify what role (if any) drivers have in operating a vehicle while a driving automation system is engaged. These levels are intended to establish a consistent framework that can be used across industries as the dialogue about autonomous vehicles continues. (Figure credit: SAE International J3016 [3].)

The motivations for creating an autonomous vehicle are beyond just technology. It's about reducing emissions through better fuel consumption, as well as addressing the demographic changes of an aging population that increase, rather than decrease, the potential for human error-induced accidents. It's also about leveraging the convergence of the shared economy and urban living, where young and old people no longer feel the need to own a car if there is a cost-effective and convenient alternative, such as Zip Car rentals, or on-demand ride-sharing services such as Uber [1].

Looking forward

Geographical coverage will be a key condition for 5G to have any relevance in the automotive sector. Initial 5G coverage can be supplemented by 4G and Wi-Fi connectivity on phones and other devices while the infrastructure is being built up, but these multimode, multiconnectivity solutions will not suffice for critical automotive use cases relying on the unique capabilities of 5G in terms of latency, reliability, and security [2]. Even once 5G is fully deployed, the adoption of self-driving technology will likely play out differently in the various markets in different regions since the forces shaping it are diverse at both the global and local level [1].

Government and industry cooperation

The continuous progression of ADAS-enabled cars and the gradual adoption of the autonomous vehicle will significantly reduce, and possibly eliminate, the number of crashes. This could, in turn, allow the removal of some regulations that relate to safety considerations, such as crumple zones, bumpers, and airbags. It also means that a review of laws relating to driving age, drunk driving, and speed restriction enforcement may be required, but not until all vehicles are compliant [1].

In September 2016, the US Department of Transportation (DOT) released the Federal Automated Vehicles Policy for highly automated vehicles (HAVs), or those intended to operate at Levels 3 to 5 as defined by SAE. The document—which is currently intended as guidance rather than formal policy—lays out standards for safe design, development, and testing of HAVs before they are commercially sold or operated on public roads. It also proposes guidelines for state governments to ensure a consistent national framework for regulation of motor vehicles with all levels of automated technology [7]. DOT's National Highway Traffic Safety Administration released additional nonbinding guidance in October 2016, outlining best cybersecurity practices for motor vehicle manufacturers and individuals and organizations involved in developing self-driving technology. The guidance aims to make cybersecurity a top priority for the automotive industry and proposes layered solutions to ensure that automated driving systems are designed to take appropriate and safe actions, even when an attack is successful [8].

A challenge yet to be addressed is that, historically, car manufacturers have completely controlled the design and development of vehicles. The advent of computers and software that effectively become the "mind" of the car means that manufacturers could lose control to technology and software companies, and yet still remain liable for any issues or catastrophes related to the car. It also remains to be seen how much and what type of data car manufacturers and network providers would be expected to share to improve overall safety and security of connected vehicles [1].

References

[1] Bell S. "IOT & the automotive industry," 2015. New York (NY): Heavy Reading.

[2] Bonte D, Hodgson J. "5G in automotive," 2016. Oyster Bay (NY): ABI Research.

[3] SAE International. "SAE International technical standard provides terminology for motor vehicle automated driving systems" [Press release]. 2 Oct 2014. Available at: http://www.sae.org/misc/pdfs/automated_driving.pdf.

[4] Collins K. "Driverless taxis could be the bullet train of the Tokyo 2020 Olympics." CNET. 22 Aug 2016. Available at: https://www.cnet.com/news/driverless-taxis-could-be-the-bullet-train-of-the-tokyo-2020-olympics/.

[5] Higgins T. "Google's self-driving car program odometer reaches 2 million miles." *The Wall Street Journal.* 2016 Oct 5. Available at: http://www.wsj.com/articles/googles-self-driving-car-program-odometer-reaches-2-million-miles-1475683321.

[6] Tesla. "All Tesla cars being produced now have full self-driving hardware" [Blog post]. 2016 Oct 19. Available at: https://www.tesla.com/blog/all-tesla-cars-being-produced-now-have-full-self-driving-hardware/?utm_campaign=GL_Blog_101916.

[7] US Department of Transportation. “Federal automated vehicles policy.” September 2016. Available at: https://www.transportation.gov/AV/federal-automated-vehicles-policy-september-2016.

[8] National Highway Traffic Safety Administration. “Cybersecurity best practices for modern vehicles.” October 2016. Report No. DOT HS 812 333. Available at: http://www.nhtsa.gov/staticfiles/nvs/pdf/812333_CybersecurityForModernVehicles.pdf.

[Photo credit: moodboard/Thinkstock]

FROM LAB TO MARKET

News from the Technology Transfer Program

CREATING & GROWING ECONOMIC IMPACT

NSA's Technology Transfer Program (TTP) is igniting innovation through collaborations with industry, academia, and other government agencies that introduce NSA technologies to the commercial marketplace. By fulfilling the legislative mandate to share government-patented technologies with industry, NSA's TTP plays a role in strengthening national security by contributing to the nation's economic growth.

Technology Transfer Program
Office of Research & Technology Applications
NSA Research Directorate

tech_transfer@nsa.gov
www.nsa.gov/techtransfer
866-680-4539

2000–2014 REPORT



JOBS CREATED

or retained

1,330

SOURCE: *National Economic Impacts from DoD License Agreements With U.S. Industry*, TechLink and UC Business Research Division.

THE RESULTS



1G
2G
3

symmetry

MDPI

Article

IoT's Tiny Steps towards 5G: Telco's Perspective

Enida Cero [1], Jasmina Baraković Husić [1,2,*] and Sabina Baraković [3,4]

[1] BH Telecom, Joint Stock Company, Sarajevo, Franca Lehara 7, 71000 Sarajevo, Bosna i Hercegovina; enida.cero@bhtelecom.ba
[2] Faculty of Electrical Engineering, University of Sarajevo, Zmaja od Bosne bb, 71000 Sarajevo, Bosna i Hercegovina
[3] Faculty of Transport and Communications, University of Sarajevo, Zmaja od Bosne 8, 71000 Sarajevo, Bosna i Hercegovina; barakovic.sabina@gmail.com
[4] Department for Computer Engineering, American University in Bosnia and Herzegovina, Trg solidarnosti 10, 71000 Sarajevo, Bosna i Hercegovina
* Correspondence: Jasmina.BarakovicHusic@bhtelecom.ba; Tel.: +387-61-265-500

Received: 10 August 2017; Accepted: 28 September 2017; Published: 2 October 2017

Abstract: The numerous and diverse applications of the Internet of Things (IoT) have the potential to change all areas of daily life of individuals, businesses, and society as a whole. The vision of a pervasive IoT spans a wide range of application domains and addresses the enabling technologies needed to meet the performance requirements of various IoT applications. In order to accomplish this vision, this paper aims to provide an analysis of literature in order to propose a new classification of IoT applications, specify and prioritize performance requirements of such IoT application classes, and give an insight into state-of-the-art technologies used to meet these requirements, all from telco's perspective. A deep and comprehensive understanding of the scope and classification of IoT applications is an essential precondition for determining their performance requirements with the overall goal of defining the enabling technologies towards fifth generation (5G) networks, while avoiding over-specification and high costs. Given the fact that this paper presents an overview of current research for the given topic, it also targets the research community and other stakeholders interested in this contemporary and attractive field for the purpose of recognizing research gaps and recommending new research directions.

Keywords: 5G mobile communication; Internet of Things; applications classification; performance requirements; enabling technologies

---

1. Introduction

Telecom operators (telcos) had the most power and influence over business in the information and communication technology (ICT) industry during past decades. This dominance was the result of owning and provisioning communication infrastructures which nowadays have become more of a commodity than a luxury. Telco's revenue streams were mainly based on the provisioning of traditional services, such as voice calls and short message services (SMS). Recent work of regulatory agencies and the appearance of alternative service providers have led telecom operators to form the opinion that alternative service providers have conflicting interests and provide competitive services, thus decreasing telco's revenue from traditional services [1]. However, the latest econometric analysis presented in [2] has shown that telecom operators and alternative service providers have aligned interests and their collaboration could be favorable to both parties. The interests of alternative service providers and telcos are not inevitably conflicting, since the economic growth of the alternative service providers are positively correlated with telco revenues and vice versa.

The development of a digital society has changed the traditional value chain and introduced new issues for telcos as they seek a way how to monetize new digital services [3]. These services are diversified across various domains of industry, such as agriculture, construction, utilities, transportation, healthcare, finance, etc., and delivered to customers through connected devices building thereby the concept of Internet of Things (IoT).

IoT can be defined as an interconnected network of things/objects that are able to interact with each other and cooperate with other things/objects through wireless and wired connections in order to create new services/applications for the benefit of society. In this way, IoT brings almost limitless benefit's, which have the potential to radically change our daily life by saving time and resources while creating possibilities for growth and innovation [4]. IoT has disruptive potential in almost every application domain, which has created many challenges that need to be faced when implementing IoT-based solutions, such as prevailing over obstacles generated by the fragmentation of IoT, both in terms of application domains and in terms of technologies. Therefore, recognizing all potential IoT applications while having in mind the development of technology and the requirements of individuals, businesses, and society as a whole is quite challenging.

Telcos now have the opportunity to seize a share of the value that is generated by IoT implementation. The size of this share will depend on telco's role in the value chain that ranges from being a traditional provider of communication infrastructure to being an end-to-end solution provider [3]. In order to monetize IoT, telcos will have to address many challenges which can be summarized as follows: (1) strategic challenges relating to decisions on future directions; (2) business challenges relating to successful management, investment, partnerships; and (3) technical challenges relating to changing connectivity and performance requirements. This paper focuses on the technical challenges since connectivity and performance requirements of IoT objects/things cannot be fulfilled using existing cellular networks that limit numerous IoT applications. In order to overcome issues associated with the current cellular networks, new types of technologies are being introduced leading towards the fifth generation (5G) network [5–7].

The architecture of the 5G network has to seamlessly integrate the requirements of diverse IoT applications: from delay-sensitive video applications to ultra-low latency, from high-speed entertainment applications in a vehicle to mobility on demand for connected objects and from best effort applications to reliable and ultra-reliable ones for health and safety [8]. A full understanding of emerging IoT applications and the variability of their performance requirements can serve telecom operators as input for specifying 5G enabling technologies. These technologies should be flexible and scalable to meet the aforementioned requirements. Since IoT applications sometimes demand extreme requirements, the 5G network must simultaneously satisfy all of them, which can lead to over-specification and high cost. In order to avoid this, telecom operators first have to adequately classify IoT applications to facilitate the selection of 5G enabling technologies being capable to efficiently meet their performance requirements.

The 5G classification concept includes three different service classes [9], i.e., (1) extreme mobile broadband (xMBB); (2) massive machine-type communications (mMTC); and (3) ultra-reliable machine-type communications (uMTC). Nevertheless, this classification concept can be considered insufficient to properly select 5G enabling technologies to meet the diverse requirements of IoT applications. Furthermore, it will be challenging to classify the emerging IoT applications given that there is many criteria for their categorization. The definition of the IoT domain in many cases overlaps with the definition of IoT application, which may at the same time belong to another IoT domain. For example, Smart Buildings may either be considered as a standalone IoT application or as an element needed to form a Smart City application domain. IoT applications are usually classified according to spheres of human life [4,10–12] or performance requirements [9,13–15]. However, these classifications are not suitable for telecom operators which have to fulfil the performance requirements of particular IoT applications, since it is difficult to choose the most important one from a class containing a wide range of IoT applications.

Telecom operators can easily specify performance requirements for current communication services since traffic patterns generated by these services are driven by predictable activities, such as making calls, receiving email, surfing the web, and watching videos. However, traffic patterns generated by emerging IoT applications are driven by less predictable activities. Hence, the idea is to determine a common set of activities based on customer service requests which describe the reasonably foreseeable function/purpose of emerging IoT applications. Then these activities can be used by telcos as a new classification criterion of IoT applications. The assumption is that such a classification can help telecom operators meet performance requirements of future IoT applications and select appropriate 5G enabling technologies. Therefore, the aims of this paper are to classify IoT applications according to relevant activities, specify and prioritize the performance requirements of each IoT application class, and consider enabling technologies used to accomplish specified demands on the radio access part of 5G networks, all according to telco's perspective. In addition, the intention is to provide a literature review which covers 258 references dominantly published in the period between 2012 and 2017. As this paper provides a state-of-the-art review of IoT applications, their performance requirements and 5G enabling technologies, it can also be of use to the research community and other stakeholders interested in this contemporary and attractive field in order to recognize the research gaps and recommend new research directions.

The remainder of the paper is thusly organized. In order to answer research questions, Section 2 describes the methodological approach in regard to the conducted research. Section 3 identifies a common set of activities as a new classification criterion for IoT applications and assigns them the relevant 5G service classes. This facilitates the determining of performance requirements of activity-based IoT application classes, which are summarized and prioritized in Section 4. The enabling technologies used to accomplish these requirements in 5G networks are contemplated in Section 5. Finally, Section 6 discusses the outcomes of the paper by clarifying the contribution of our research in identifying open issues for future work, while Section 7 concludes this paper.

2. Research Approach and Design

The main objectives of this paper can be summarized as follows: (1) to identify activities relevant to IoT customer service requests and use them as a new classification criterion of IoT applications; (2) to specify and prioritize performance requirements of such IoT application classes; (3) to analyze relevant literature in order to provide insight into 5G radio technologies used to fulfil the requirements of activity-based IoT application classes; (4) to recognize research gaps and directions.

The research questions posed in this study are: (1) Which activities can be used as classification criteria for IoT applications? (2) What are the performance requirements of such IoT application classes? (3) Which enabling technologies in the radio access part of the 5G network can be used to meet the requirements of IoT application classes?

Investigation of different criteria for the classification of IoT applications underlines to what extent various classification concepts have been covered by existing literature and provides a basis for the introduction of a new classification criterion called the activity. We thus surveyed and compared different studies contributing to the understanding of the scope and classification of a wide range of IoT applications. This approach has been motivated by the challenge to propose an activity-based classification of IoT applications, the determination and prioritization of performance requirements of such IoT application classes and the review of 5G enabling technologies used to meet them. These findings can be utilized by telecom operators and other interested parties (e.g., the research community, software network function providers, network infrastructure manufactures, etc.) depending on their interest and potential to utilize these findings towards 5G implementation and commercialization.

The methodological approach to research conducted in this paper is illustrated in Figure 1 and includes four phases.

Phase I included searching, identifying, and extracting papers from three categories, i.e., IoT in 5G service classification, IoT in 5G performance requirements and IoT in 5G enabling technologies. The keywords used to search relevant scholar databases are shown in Figure 2. This search has resulted in the selection of 258 recently published papers, which can be categorized into three groups (i.e., review papers, technical papers, research effectiveness), as shown in Table 1. Review papers summarize the status of knowledge and outline future directions in a given area of research. Technical papers describe the process, progress, or result of research, whereas research effectiveness directly provides an answer to the research question raised for this study. The reference distribution by year of publication is shown in Figure 3a, while the total percentage of references per publication type is presented in Figure 3b.


PHASE Ia
Searching for papers
PHASE Ib
Identification and extraction of papers
(IoT and 5G related)
PHASE II
Analysis and comparison of papers related to IoT application classfication
PHASE III
Categorization of performance requirements papers into activity-based IoT application classes
PHASE IV
Categorization of 5G enabling technologies papers into activity-based IoT application classes
Relevant databases:
- Google scholar
- IEEE Xplore
- Science direct
-...
258 relevant papers
Proposal of activity-based classification of IoT applications
Prioritization of perfomance requirements of activity-based IoT application classes
Proposal of 5G radio technologies satisfying high priority requirements of mMTC activity-based IoT application classes
SECTION III
SECTION IV
SECTION V

Figure 1. Methodological approach to research.


Multi-RAT scale
Positioning-accuracy
Ticketing
Environmental context
Channel
Availability
Reliability
Data-rate
SCMA V2X
VLC FQAM
Backhaul
Cellular
Mobility
Monitoring
Duplexing
Latency
Antenna
Enhanced
Full
Wireless
Scheme
NOMA
D2D
In-band
mMIMO
Tracking
mMTC
Network
Cognitive
Large
Advanced
mmWave
...
...
Coverage
Edgeless
Moving
Connection density
Ultra high
Coding
SIC SWSC
TDD SND
Ultra-densification

Figure 2. Keywords for searching relevant databases.

Table 1. Reference categorization.

Reference Type	Reference Number
Review paper	[1,2,10,12,14–88]
Technical paper	[8,89–197]
Research effectiveness	[3–7,9,11–13,29,52,198–258]



(**a**) (**b**)

Figure 3. Reference distribution by (**a**) year of publication; (**b**) type of publication.

Phase II included the analysis and comparison of papers related to the category of IoT in 5G service classification. Papers were first sorted according to the existing classification criteria of IoT applications in order to underline their deficiencies from telco's perspective. Since emerging IoT applications generate traffic driven by less predictable activities, specifying their performance requirements and enabling technologies is not an easy task from telco's point of view. Therefore, we have proposed a common set of activities to serve as classification criteria of IoT applications. Four activities were selected based on IoT customer service requests denoting the function/purpose of existing IoT applications. According to the authors' knowledge, existing IoT applications can be grouped around following activities: ticketing, tracking, monitoring, and managing/controlling. Such a classification makes it easier for telecom operators to associate particular IoT applications to the relevant 5G service class. Finally, Phase II has resulted in the proposal of an activity-based classification of IoT applications which was associated with the 5G service classification.

Phase III included the analysis of papers related to the category of IoT in 5G performance requirements. Papers were grouped according to eight key performance indicators, i.e., data rate, mobility, latency, connection density, reliability, positioning accuracy, coverage, and energy efficiency. These performance requirements were prioritized indicating high, medium, and low importance of each requirement for specific activity-based IoT application classes proposed in Phase II. Finally, Phase III resulted in the identification of highly important performance requirements for each activity-based IoT application class which can be utilized by telcos to identify 5G enabling technologies used to meet them.

Phase IV provided a review of papers from the category of IoT in 5G enabling technologies. Papers were first sorted according to eight technological groups used in the radio access part of 5G networks, i.e., wide and flexible bandwidth technology, advanced modulation and coding, duplexing, multiple access and waveform, advanced interface management, access architecture related radio technologies, energy related technologies, and other technologies. These technologies have been discussed in terms of their possibility to meet the high priority performance requirements of mMTC activity-based IoT application classes, since this area is more mature from telco's perspective. The results of Phase III were reflected in a proposal of technologies in the radio access part of 5G networks that can be used to meet the high priority performance requirements of the mMTC activity-based IoT class, as well as the identification of research gaps and directions for future work.

3. IoT in 5G Service Classification

As mentioned in the Introduction, various challenges awaiting telcos can be identified on the basis of the role that they will play in the IoT value chain. Regardless of this role, telcos will face many technical challenges, such as the necessity for global deployment, the need for rapid infrastructure scaling, unpredictable IoT application behavior, etc. Even now, existing IoT applications accelerate the growth rate of traffic driven by less predictable activities which require new strategies towards 5G networks. These networks will be the key enabler for IoT applications by providing a unified infrastructure capable of meeting the high variability of their performance requirements [8,16]. Various stakeholders have recently described what 5G networks may be and grouped the major types of 5G services into three different classes: (1) xMBB—Requiring extremely high data rates and low-latency communication; (2) mMTC—Requiring scalable connectivity for an extremely large number of devices; and (3) uMTC—Requiring ultra-reliable low-latency and resilient communication [198]. This 5G service classification can be used by telcos to identify performance requirements of various IoT applications, and, as such, was used in this research study. However, emerging IoT applications will have extreme requirements, so an analysis based solely on 5G service classifications may not be sufficient. Therefore, telcos need a more precise classification of IoT applications which is an important precondition for meeting their diverse requirements.

IoT covers human-to-human (H2H), human-to-machine (H2M) and machine-to-machine (M2M) communication, which will be the main driving force towards 5G networks. In addition, the terms M2M communication (M2MC) and machine type communication (MTC) are used interchangeably as in [17–19,89–93,199,200]. Although IoT is a broader concept which evolves from M2M, this paper assumes that IoT and M2M are synonyms as in [94].

3.1. Existing Classifications of IoT Applications

In order to meet the requirements of a wide range of IoT applications, they have to be classified in an appropriate manner. The existing approaches to the classification of IoT applications are summarized in Table 2. IoT serves different user categories, including individuals, businesses, and society as a whole, and may span through a broad range of application domains [4,10–12], such as transportation and logistics, healthcare, smart environment, personal and social, futuristic applications, food sustainability, smart living, smart manufacturing, smart energy, smart city, etc. These application domains are created to be human-centric, which means that they cover different domains of human life. IoT applications belonging to these domains have diverse requirements for 5G networks, and should not be treated equally. Therefore, the acceptance of these domains as a classification criterion raises the issue of assigning IoT application to a particular domain. Moreover, the emergence of new applications of IoT may require defining new application domains, which makes this classification inappropriate from telco's perspective.

The M2M applications may be classified by the mobility and the amount of dispersion that needs to be supported into four categories [13]: (1) fixed and concentrated; (2) fixed and dispersed; (3) mobile and concentrated; and (4) mobile and dispersed. However, the mobility and amount of dispersion present very rough classification criteria and cannot meet the precise network requirements of individual IoT applications.

Additionally, M2M applications can be grouped according to delay tolerance into four categories [14]: (1) elastic (delay tolerant); (2) hard real-time (delay constraint); (3) delay-adaptive (delay sensitive but tolerant); and (4) rate-adaptive application (adjust their transmission rates according to available radio resource). However, the main drawback of this classification is the lack of consideration of other IoT application requirements except delay tolerance, although its importance as a classification criterion has been recognized.

According to data reporting mode, the M2M applications can be classified into five categories [91]: (1) time-driven; (2) query-driven; (3) event-driven; (4) continuous-based; and (5) hybrid-driven. This classification is specific for the former IoT concept, which is narrower in nature than the definition adopted in this study.

Another study considered the reliability, availability, and end-to-end latency in order to classify IoT applications into two groups [15]: (1) monitoring-based and mission-critical; (2) monitoring-based and non-mission critical; (3) control-oriented and mission-critical; and (4) control-oriented and non-mission critical. Monitor-based IoT applications periodically collect sensor data from smart objects and transmit them. The majority of monitoring-based IoT applications are not mission-critical. Control-oriented IoT applications use sensor data to control actuators in real-time, and rely on mission critical communication. This classification is based on multiple criteria and represents the precursor of the Mobile and wireless communications Enablers for Twenty-twenty Information Society (METIS) 5G service classification.

Table 2. Internet of Things (IoT) application classification—summary.

Criteria for Classification	IoT Classes	References
Domains	(1) Transportation and logistics (2) Healthcare (3) Environment (4) Personal and social (5) Futuristic applications (6) Food/water monitoring (7) Living (8) Manufacturing (9) Energy (10) Building (11) Industry (12) City (13) Security and safety (14) Communication (15) e-society (16) Vehicular (17) Sport and leisure	[4,10–12]
Mobility and amount of dispersion	(1) Fixed and concentrated (2) Fixed and dispersed (3) Mobile and concentrated (4) Mobile and dispersed	[13]
Delay tolerance	(1) Elastic (2) Hard real time (3) Delay-adaptive (4) Rate-adaptive	[14]
Data reporting mode	(1) Time-driven (2) Query-driven (3) Event-driven (4) Continuous-based (5) Hybrid-driven	[198]
Reliability, availability, and end-to-end latency	(1) Monitoring-based and mission critical (2) Monitoring-based and non-mission critical (3) Control-oriented and mission critical (4) Control-oriented and non-mission critical	[15]
Characteristics and requirements	mMTC and uMTC	[12]

Legend: IoT (Internet of Things), mMTC (massive Machine Type Communication), uMTC (ultra-reliable Machine Type Communication).

Although it spans through a wide range of different applications, MTC can be divided in two main categories, i.e., massive and ultra-reliable MTC, which depend on their characteristics and requirements [89]. As mentioned above, this categorization is a part of 5G service classification which was used in this study as a basis to identify performance requirements of IoT applications and will be described in more detail in Section 4. Massive MTC (mMTC) typically involves a very large number of devices (tens of billions [9]), such as sensors, actuators, and similar devices [12], different in complexity and cost [9], and with varying quality of service (QoS) requirements. These devices should be of very low cost with very low energy consumption, enabling very long battery life [12]. At the same time, the amount of data generated by each device is normally very small, and very low latency is not a critical requirement [12]. Ultra-reliable MTC (uMTC) requires very high reliability and availability, and very low latency [9,12]. Low device cost and energy consumption are not as critical as they are for mMTC applications [12], and the number of devices and required data rates are relatively low [198].

The vision of a pervasive IoT requires the integration of various domains into a single and unified domain. It addresses the enabling technologies needed for these domains while taking into account the elements that form the third dimension like security, privacy, trust, and safety [11]. The current classification criteria and IoT application classes do not clearly differentiate IoT domains from IoT applications. IoT domains are usually viewed as a specific area of IoT applications that support a huge variety of use cases across industries impacting businesses and customers. Therefore, IoT domains overlap with IoT applications within existing IoT classifications. Moreover, IoT classification based on certain QoS parameters is difficult to apply from telco's perspective, because it is challenging to choose the most important parameter for the wide range of IoT applications. However, these problems need to be solved for upcoming 5G networks.

3.2. Activity-Based Classification of IoT Applications

The aforementioned issues motivated us to propose a new approach to the classification of IoT applications. This approach is based on "**the activity**", which primarily characterizes specific IoT application. In this sense, the activities are defined as new classification criteria, which denote a main function/purpose of specific IoT application observed from telco's point of view. Telecom operators observe the technical challenges of IoT through systems, tools, devices, and platforms because their availability and integration complexity determines the opportunity to capture a share of the value that is generated by IoT implementation. Based on the literature review, it was found that the most commonly mentioned terms in this sense were related to: (1) ticketing system [201]; (2) monitoring: devices [199,201–204]/services [199,201,202,205,206]/tools [207]/systems [11,12,199,201,205,206,208–210]/ data [95,201]/framework [12,201]/solutions [20,205]/networks [211]/process [7]/activity [203,204,207]; (3) tracking technologies [4]/devices [204]/systems [204]/applications [11,210]/system [201]/services [202,205]; (4) managing/controlling applications [15,210,212]/operation [211]/services [4,208]/tools [208,211]/devices [204]/system [95,198,204,210]/concepts [211]/solutions [95]/platforms [95,199]. This has led us to identify four activities, i.e., ticketing, monitoring, tracking, and managing/controlling, as new classification criteria of IoT applications. According to the authors' knowledge, it was found that these activities can cover reasonably foreseeable functions/purposes of IoT in existing application domains. Using activities as classification criteria, telcos can specify IoT application performance requirements more easily, which are in that case dictated by the specific activity, not by the IoT application domain, and determine enabling technologies in the radio access part of 5G networks.

In addition, our classification approach allows better service differentiation and service delivery closer to customer expectations. According to BH Telecom's experience, customers typically come up with the following service requests when it comes to IoT: (1) they need to track their products and determine products' distribution across different regions based on their own data analysis; (2) they want to monitor their products since they do not have a department for supervision and analysis; (3) they need information panels about their outlets and working time to be downloaded by a scanning tab-ticket; (4) they want to manage/control their products according to market needs. This way of expressing customer needs has inspired us to propose the activity-based classification of IoT applications as it allows telcos to define performance requirements more precisely, and thereby improve the customer experience.

The activity-based classification of IoT applications is presented in Table 3. Each activity is associated with the application domain where that activity may be applied. The requirements of identified activities and associated application domains are then mapped to 5G service classes in order to be further able to identify their performance requirements and enabling technologies necessary to meet them. For example, according to Table 3, the managing/controlling activity can be realized in several domains, such as healthcare, food, energy, transportation and logistics. For each domain, we have identified an application example, such as remote surgery [213] in the healthcare domain, food processing facilities [96] in the food domain, energy distribution [12] in the energy domain and traffic/driving [12,213] in the transportation and logistics domain. According to diverse performance requirements of these IoT applications [214], managing/controlling activity in healthcare, food, transportation, and logistic domains can be associated with the uMTC service class, while the energy domain can be mapped to the mMTC service class. A more detailed description of performance requirements for each activity-based class of IoT applications is provided in Section 4, while in Section 5 it is discussed how these requirements can be accomplished in the radio access part of 5G networks.

Table 3. Activity-based classification of IoT applications.

Activity	Domain Examples	5G Service Classification	Application Examples
Ticketing	Smart Transportation and Logistics	mMTC	POS Terminal [4]
Monitoring	Smart Healthcare	uMTC	Health condition [97]
	Smart Buildings	uMTC	Structures (buildings, tunnels, etc.) [12,25,213]
	Smart Buildings/Smart City	mMTC	Parking spaces
	Smart Buildings/Smart Environment	mMTC	Home video [12]
	Smart food/water monitoring	mMTC	Food growth condition [10]
Tracking	Smart Healthcare/Sport and Leisure	mMTC	Medical assets, wearables [200,213]
	Smart Transportation and Logistics	mMTC	Transport fleet [200,213]
	Smart Industry/Social Networking	mMTC	Shipping of products
	Smart Healthcare	mMTC	People in science museum
Managing/ controlling	Smart Healthcare	uMTC	Remote surgery [213]
	Smart food/water monitoring	uMTC	Food processing facilities [96]
	Smart Transportation and Logistics	uMTC	Traffic, driving [12,213]
	Smart Energy	mMTC	Energy distribution [12,98]

Legend: 5G (Fifth Generation), POS (Point Of Sale), mMTC (massive Machine Type Communication), uMTC (ultra-reliable Machine Type Communication).

As such, the activity-based classification of IoT applications can be used for the creation of new business models, which represent the stakeholder's plan to generate revenue and make a profit from operations, and thereby include many components and functions of the business [21]. However, there is no common opinion which components constitute a business model. The business model architecture can be illustrated by four dimensions [22]: (1) who, identifying the definition of the target customer as one central dimension in designing a new business model; (2) what, describing what is offered to the target customer; (3) how, referring to the construction and distribution of the value proposition; (4) value, explaining why the business model is financially viable. Answering these four questions allows the creation of IoT business models. According to this business model definition, the activity-based classification of IoT applications affects the who and the how dimensions in the following manner. In terms of the who dimension, it directly allows customer segmentation according to considered activities as a way to express their requirements (e.g., customers that require tracking or monitoring of their products). Being aware of the current customer requirements, the proposed classification of IoT applications around four activities (i.e., ticketing, monitoring, tracking, and managing/controlling) can be considered complete. At the same time, the activity-based classification of IoT applications is flexible since additional activities as classification criterion can be concerned with emerging customer requirements. On the other hand, the activity-based classification of IoT applications indirectly impacts the how dimension of new business models which among others includes relevant resources and capabilities in the focal stakeholder's internal value chain. This indicates that the proposed activity-based classification of IoT applications can be easily applied to IoT business models.

Various categories of IoT business models can be identified according to eight IoT architectural layers [23], i.e., collaboration and processes layer, application layer, service layer, abstraction layer, storage layer, processing layer, network communication layer, physical layer. Along with IoT architectural layer, the IoT business model needs also to address the IoT value proposition [24] and

IoT stakeholders that can participate in more than one layer. Based on their role in the IoT ecosystem, telecom operators usually take a part in the network communication layer. In this regard, they follow four evolutionary business models [23]: (1) selling connectivity services only; (2) selling third-party products; (3) selling internal products; (4) providing a broad menu of IoT products. Each of these IoT business models includes traditional telcos strength, i.e., connectivity which determines the how dimension of the IoT business model. In this sense, our activity-based classification of IoT applications indirectly allows the construction and distribution of performance as IoT value proposition using enabling technologies as IoT resources in telco's internal value chain.

3.3. Summary of IoT in 5G Service Classification

The previous discussion has shown that the classification of IoT applications is a complex task due to their numerosity and diversity. The existing classifications of IoT applications pose some drawbacks that can be summarized as follows. The domain-based classification does not allow clear differentiation between IoT domains and IoT applications due to either an imprecise classification criterion or the diversity and unpredictability of IoT applications. On the other hand, QoS-based classifications need to identify the common and most important performance metric for a broad range of IoT applications. Therefore, on the basis of the literature review and IoT customer service requests, we have proposed a new approach to the classification of IoT applications. It is based on the activity as new classification criterion, which denotes a main function/purpose of specific IoT application observed from telco's point of view. According to the authors' knowledge, four activities, i.e., ticketing, monitoring, tracking, and managing/controlling, have been identified to cover reasonably foreseeable functions/purposes of existing IoT applications. The resulting activity-based IoT application classes have been associated with 5G service classes in order to determine and prioritize their performance requirements as described in next section. Finally, the proposed classification of IoT applications was discussed in terms of its completeness, flexibility, and applicability to new business models.

4. IoT in 5G Performance Requirements

This section provides an insight into performance requirements of activity-based classes of IoT applications proposed in Section 3. The analysis is based on eight key performance indicators identified in [5,207] as shown in Table 4: data rate, mobility, latency, connection density, reliability, positioning accuracy, coverage, and energy efficiency. These performance indicators are usually well described for specific IoT applications. However, one of the main challenges of 5G is to support a variety of performance requirements for numerous IoT applications in a flexible, reliable, and cost-effective way [15]. Hence, there is a need for a comprehensive understanding of these requirements for activity-based IoT application classes. The 5G service classification defined the performance requirements for mMTC and uMTC [9]. We have assigned these requirements to the activity-based IoT application classes introduced in Section 3 for the purpose of proposing priorities of each requirement for a specific class. Three levels of priorities (high, medium, low) are associated with the performance requirements of activity-based classes of IoT applications as shown in Table 4. The prioritization of performance requirements is inspired by analysis of related work undertaken in [213]. Some activity-based classes of IoT applications may demand optimization of multiple performance requirements. Table 4 illustrates the main differences between activity-based IoT application classes, and therefore, the need for a 5G network that enables support of optimal configurations for a variety of, sometimes opposite, requirements. For example, the mMTC tracking-based IoT application class requires support for high mobility, high positioning accuracy, and high connection density, while the mMTC monitoring-based IoT application class also requires high connection density but low mobility and low positioning accuracy. A more detailed description of considered performance requirements is contained in the following subsections.

Table 4. Activity-based classes of IoT applications—performance requirements.

5G Service Classification	Activity	User Experienced Data Rate [Gbps] Outdoor: 0.1 [5] Indoor: 1 [5]	Mobility [km/h] Required: 500 [5]	Latency [ms] Control Plane: 50 [5] User Plane: 1 [5]	Connection Density [Connections/km^2] Required: 10^6 [5]	Reliability [%] Required: 99.999 [207]	Positioning Accuracy Required: A Few cm [5]	Coverage/ Availability [%] Required: 99.999 [207]	Energy Efficiency [bits/J]
mMTC	Ticketing	L to M	L	L	H	M	H	H	H
	Tracking	M	H	L	H	M	H	H	M to H
	Monitoring	M to H	L	L	H	L to M	L	H	M
	Managing/controlling	L	L	L	H	M	L	M to H	M
uMTC	Monitoring	L	L to M	H	H	H	M to H	H	M
	Managing/controlling	L	M to H	H	L	H	H	M to H	M

Legend: 5G (Fifth Generation), mMTC (massive Machine Type Communication), uMTC (ultra-reliable Machine Type Communication), L (Low), M (Medium), H (High).

4.1. Data Rate

Data rate is the most important evaluation factor for generations of wireless communication networks [6]. It is contemplated in two ways: (1) peak data rate—defined as the maximum achievable data rate by the user; and (2) minimum guaranteed user data rate—defined as the minimum experience data rate by the user [16]. New mobile technologies are primarily driven by users' needs for higher data rates, as discussed in [8,16,99,215,216]. The expected values in 5G networks are 10 Gbps for minimum peak data rate and 100 Mbps as minimum guaranteed user data rate [5]. High data rate requirements are mainly posed by xMBB related use cases [9] like hotspots [214] or dense urban areas where in 95% of locations and time experience data rate by user should be 300 Mbps in downlink and 60 Mbps in uplink [100]. High data rate is also important in some activity-based classes of IoT applications, as shown in Table 4. Medium (e.g., monitoring of parking spaces) to high (e.g., monitoring of home video) data rate is needed in cases of mMTC monitoring activities. High data rate can be achieved by using a millimeter wave (mmWave) spectrum to share multi-gigabit data in the surrounding environment (i.e., mMTC monitoring with high data rate requirement) and to recognize an object via cloud in real time to find the optimal driving strategy instantaneously for IoT—autonomous vehicles application [101]. Data rates generated during transmissions of tracked medical assets, transport fleets, and ticked point of sale (POS) terminals is low (e.g., medium importance for ticketing and tracking activities in mMTC). In addition, low data rates are needed in uMTC monitoring and controlling (e.g., monitoring of health condition, control of driving).

4.2. Mobility

Mobility is defined as relative velocity between the receiver and the transmitter [16]. The applications of IoT pose very diverse requirements for mobility in 5G networks, which range from static to high mobile, even up to 500 km/h [16,102,207]. Use cases in which except ultra-high mobility, ultra-high traffic volume density, and ultra-high connection density are needed may be quite challenging for 5G networks [215], like V2X communication [5]. High mobility is a very important requirement for mMTC tracking activity (e.g., tracking of assets in high speed trains [214]). Moreover, the support for high mobility is needed in uMTC management activities, if the monitor/control object is moving (e.g., high speed trains [207]). Low mobility is needed for ticketing, monitoring, and managing/controlling activities in the mMTC class, as shown in Table 4. This is the reason why 5G networks should not assume mobility for all devices and services but rather provide mobility on demand [8].

4.3. Latency

Latency requirements are usually expressed in terms of end-to-end (E2E) latency perceived by the end user [8]. 5G networks should enable "zero latency" [103] represented by the millisecond level of E2E latency [16,26,27,213] through significant enhancements and new technology in architecture aspects [6,28,214], such as device-to-device (D2D) communication [5]. The IoT applications associated with uMTC monitoring and managing/controlling activities require low latency, as they tend to be real time. Required latency levels depend on the particular IoT application [8,16,28], being the narrowest in uMTC managing/controlling activity with a value that should not exceed 1 ms [8]. For example, the tolerable delay for use case mobile health [215] and remote surgery application is in order of sub-milliseconds [213]. For V2X communications, latencies should be ultra-low for some warning signals [8].

4.4. Connection Density

Connection density is defined as the number of connected devices per unit area [16]. It can usually be expressed in terms of an extremely high number of simultaneous active connections, such as 1 million connections per square meter [207,215], or 10 to 100 times higher number of connected devices [29]. The performance values of connection and traffic density for various 5G services are listed in [8,212]. This performance requirement is highly correlated with identified activity-based classes of IoT applications, since it is the main characteristic of mMTC. High device density brings the need for rapid internet protocol version 6 (IPv6) deployment, and high quality security algorithms and techniques, which lead to new system design and implementation, as described in [104].

4.5. Reliability

Reliability is the maximum tolerable packet loss rate at the application layer [105]. 5G must bring a reliability of 99,999% [27,30,31,212], or higher for specific use cases [212], (e.g., tele-protection in a smart grid network [207] or driverless cars [106]). Reliability is the main characteristic of uMTC monitoring and managing/controlling activities. Reliability will be a particularly challenging task in high-speed trains because of speed, load, and cell distance [16,107].

4.6. Position Accuracy

Position accuracy is the maximum positioning error tolerated by the application [105]. 5G should ensure accurate positioning of the device outdoors [108] with accuracy from 10 m to <1 m on 80% of occasions and better than 1 m in indoor deployment [212]. Accuracy positioning is very important in uMTC monitoring-based activities (e.g., monitoring remote cameras), and uMTC managing/controlling-based activities (e.g., driving) [213]. Moreover, the mMTC tracking-and ticketing-based activities pose high performance requirements in terms of position accuracy.

4.7. Coverage

Coverage requirements in 5G should provide connectivity anytime and anywhere with a minimum user experience data rate of 1 Gbps [32]. However, the perception of 100% coverage is rather a technical decision than a business one [33], which could be extended through ultra-cell deployment [31] and vehicle-to-infrastructure (V2I) communications [30]. Almost every activity-based IoT application class requires very high levels of coverage (99,999% availability) [207]. Total coverage will enable new unmanned aerial vehicles (UAV) to use single network connection, instead of connection steering mechanism, as one described in [109].

4.8. Energy Efficiency

Energy efficiency is defined as the number of bits that can be transmitted per joule of energy [216]. Compared with current wireless technologies, the energy efficiency (measured in b/J) of the 5G network may need to be improved by a factor of 1000 [4,7,34,110,217]. High energy efficiency is important in case of ticketing- and in some cases of tracking-based activities (e.g., smart industry [205] or implantable medical devices [35]). Other activities, such as both mMTC and uMTC monitoring- and managing/controlling-based activities (e.g., health condition [205]) and some tracking-based activities (e.g., sports wearables [205]) require medium energy efficiency. Energy efficiency is very important design objective for the reduction of operating costs of telecom operators, as well as for minimizing the environmental impact of the wireless domain [217]. On a higher layer of the network protocol stack, adaptive base station switch on/off algorithms use renewable energy sources to save energy [218] along with an energy scheduler, as in the with heating, ventilation and air conditioning (HVAC) [111]. However, at the physical layer, adaptively switching off unused carriers is a key strategy that can be used to save energy from the radio-frequency (RF) transceiver chain of base stations [218].

4.9. Spectrum Efficiency

Spectrum efficiency is defined as the data throughput per unit of spectrum resource per cell or per unit area (bps/Hz/cellar bps/Hz/km^2) [216]. In order to achieve network sustainability, required for 5G networks [216], spectrum efficiency needs to be improved 3–5 times [20,32,216]. Minimum peak spectrum efficiency is 30 bps/Hz for downlink and 15 bps/Hz for uplink [32]. This is mostly important for the xMBB services class [212,214]. Since this performance requirement is not relevant for activity-based IoT application classes which are associated with the mMTC and uMTC service class, it has not been further considered herein.

4.10. Summary of IoT in 5G Performance Requirements

Activity-based classes of IoT applications are associated with performance requirements of 5G service classes, i.e., mMTC and uMTC. On the basis of the literature review, each activity-based class (ticketing-, tracking-, monitoring-, and managing/controlling-based class) is associated with mMTC service class, while the monitoring- and managing/controlling-based classes are the only ones linked to the uMTC service class. According to the authors' best knowledge, there is no available literature concerning the uMTC ticketing- and tracking-based classes of IoT applications or such IoT customer service requests.

Activity-based IoT application classes pose many performance requirements, which have been discussed in terms of data rate, mobility (speed), latency, connection density, reliability, positioning accuracy, coverage, and energy efficiency. These performance requirements have been assigned three-level priorities (high, medium, low) for the purpose of facilitating identification of the enabling technologies used to fulfill them. Based on the literature review, it was found that each activity-based IoT application class poses high requirements in terms of connection density except the uMTC managing/controlling-based IoT application class. Moreover, ticketing- and tracking-based IoT application classes have high requirements in terms of positioning accuracy, coverage, and energy efficiency. Additionally, positioning accuracy is a highly important performance requirement for the uMTC managing/controlling-based IoT application class, whereas coverage is important for both uMTC and mMTC monitoring-based IoT application classes. Finally, latency and reliability represent highly important performance requirements for uMTC monitoring- and managing/controlling-based IoT application classes. A deep and comprehensive understanding of performance requirements of each activity-based IoT application class may facilitate the selection of 5G enabling technologies needed to meet them as described in the following section.

5. IoT in 5G Enabling Technologies

Activity-based classification of IoT applications proposed in Section 3 allows telecom operators to identify performance requirements of each class relying on 5G service classification, as discussed in Section 4. However, these performance requirements cannot be satisfied for many IoT applications with current cellular (2nd, 3rd, and 4th generation) network technologies, since they limit their potential due to many issues [3], i.e., protocol implementation complexity, poor coverage in non-urban environments, high cost of networking equipment and data transmission. In order to overcome these issues, many dedicated communication technologies are being installed.

From the very beginning of IoT, many proprietary technologies, such as radio-frequency identification (RFID), wireless highway addressable remote transducer (WirelessHART) or Z-Wave, have first appeared, and then, more generic ones, such as Bluetooth, IEEE 802.15.4, IPv6 over low-power wireless personal area networks (6LoWPAN). However, none of these technologies have become a market leader mainly because of technology shortcomings and business model uncertainty [219]. Hence, new solutions, such as low-power wireless fidelity (LP Wi-Fi), low-power wide area (LPWA) or several improvements for cellular M2M communications have become serious candidates for IoT implementation. LP Wi-Fi is an IEEE 802.11ah standard designed to extend the application area of Wi-Fi networks in order to meet IoT requirements (i.e., large number of devices, large coverage range, energy constrains). First performance studies indicate that this standard will support a broad range of M2M scenarios with a required QoS level, and enable scalable and cost-effective solutions. In addition, LPWA networks have been deployed for some time in the form of many different proprietary solutions (e.g., Amber Wireless, Coronis, Huawei's CIoT, LoRa, M2M Spectrum Networks, Sigfox, Weightless, etc.), but only the LoRa Alliance, Sigfox and Weightless are involved in LPWA standardization activities. Despite some drawbacks which are mainly related to use of an unlicensed spectrum, LPWA networks are expected to become a key enabler for IoT deployment in early market rollouts and for limited IoT applications [219].

The appearance of these IoT communication technologies was considered as competition to current cellular networks from the telco's point of view from the start. But, in the meanwhile, telcos have realized that the aforementioned communication technologies can be utilized to meet the changing connectivity and performance requirements of IoT applications. Therefore, many dedicated communication technologies have already been deployed in various IoT applications. For example, Orange, Swisscom and South Korea (SK) Telecom have built nationwide networks based on LoRa [3], whereas Deutsche Telekom (DT), Vodafone and all three Chinese operators have completed the rollout of narrowband IoT (NB-IoT), as another LPWA standard utilizing existing long term evolution (LTE) networks [36]. In this context, standardization and interoperability becomes critical because there is a need to consider a broad range of connectivity solutions as presented in Figure 4 [37]. One of those solutions includes satellite technologies which integrated with 5G radio technologies form the 6th generation (6G) standard for providing global coverage [38].



	Short-range Wireless Technologies	
1	Bluetooth	SIG
2	RFID	ISO, IEC, ASTM, DASH7, EPCglobal
3	Zigbee	Zigbee Alliance
4	HART	HART Communication Foundation
5	ISA100.11a	ISA
6	Thread	Foundation for the connected home

	802.11	
1	Wifi a-n	IEEE
2	Low Rate WiFi ah	IEEE

	Low Power Wide Area	
1	LoRa	LoRa Alliance
2	SigFox	Sigfox Foundation
3	RPMA	RPMA Networks
4	UNB	Telensa
5	Weightless	Weightless SIG
6	Qowisio	Qowisio

	LTE and NB-IoT	
1	LTE Cat-4, Cat-1, Cat-0, Cat-M1	3GPP
2	NB-IoT	3GPP

5G IoT

	Data Rate	Mobility	Latency	Connection Density	Reliability	Positioning Accuracy	Coverage	Energy Efficiency
Short-range Wireless Technologies	X	X					X	
802.11	X	X					X	
Low Power Wide Area	X	X	X		X		X	
LTE and NB-IoT	X						X	
5G IoT	X	X	X	X	X	X	X	X

Figure 4. IoT performance requirements and enabling technologies.

In this regard, standardization activities of 5G and beyond are being undertaken by several standards bodies, such as the Institute of Electrical and Electronics Engineers (IEEE), the 3rd Generation Partnership Project (3GPP), the Internet Engineering Task Force (IETF), ITU Radiocommunication Sector (ITU-R), and ITU Telecommunication Standardization Sector (ITU-T). An overview on these standards bodies and their effort to develop communication standards for 5G and beyond are provided in [112]. Due to the envisioned 5G applicability, these standards have defined an air interface that can significantly improve the performance, and network architectures that allow the deployment and coexistence of various 5G technologies. A detailed discussion of these technologies regarding both technological and standardization aspects indicates that 5G can be perceived as the main driving force for enabling the vision of a truly global IoT [219].

In this sense, the technologies described in this section will allow 5G networks to form a unified communication infrastructure for the realization of a wide range of IoT applications. These technologies will bring performance enhancement which will trigger a complete revolution in almost all spheres of human life creating a new "everything connected" era. Future 5G networks in such an era will face a serious problem regarding a huge number of different service types [220]. To meet the diverse requirements for a huge number of IoT applications, 5G introduces the concept of network slicing to offer programmable network instances [220]. Using network slicing, multiple independent and dedicated network instances can be created within the same infrastructure to run services that have completely different requirements for latency, reliability, throughput, and mobility [220]. This technology primarily targets a portion of the 5G core network, but also indicates that 5G radio access network (RAN) functionalities can be different for each network slice [221]. To deploy network slices, network functions need to be enabled on an on-demand basis, which has driven the use of virtualization and softwarization in 5G core network [221]. Network function virtualization (NFV) is a paradigm that enables that 5G network functions to run in a virtual environment instead of dedicated hardware [221]. The software define networking (SDN) paradigm facilitates isolation of network slices avoiding the traffic of one slice affecting the performance of another slice [221]. These two paradigms make the network much more dynamic, agile, on-demand, and flexible [222,223]. Since the aforementioned technologies are used to deal with a variety of 5G applications, they will not be further discussed. This paper will focus on technologies used to meet performance requirements for specific applications (inter slice performance) which are implemented in the radio access part of 5G networks.

These technologies are briefly described and discussed in terms of their advantages, disadvantages, and research gaps. Given the fact that the realization of particular technology affects multiple performance requirements, tiny steps towards its implementation will allow telcos to deploy 5G networks, and thereby provide a performance improvement in terms of more capacity, lower latency, more mobility, more position accuracy, increased reliability, and availability [6,214,224]. In other words, 5G networks will accommodate many more users and devices while delivering more data [113,114] to each user requiring high data rates [108] in a more energy-efficient way [115,116].

Table 5 summarizes considered radio technologies used to implement future 5G networks being capable of achieving performance requirements identified in Section 4. On the basis of the literature review, one may conclude that the 5G radio access network is crowded with multiple technologies, and there seems to be a duplication of technologies, all eager to grab telco's attention and convince them to buy into the particular choice. As Table 5 shows, multiple technologies and techniques can be used to meet each performance requirement. Since the mMTC activity-based IoT classes are more mature, we have primarily focused on technologies used to fulfil their high performance requirements (i.e., connection density, positioning, and coverage). We have selected 5G enabling technologies considered from telco's perspective as the most representative and promising candidates to meet these requirements. The implementation of these technologies will also significantly affect the fulfillment of uMTC service class requirements, which will lead to complete automation in all spheres of human life. Therefore, the following subsections will discuss these technologies in more detail with the final goal of identifying research gaps and providing recommendations for future work, which are summarized in Table 6.

Table 5. IoT in 5G enabling radio technologies.

Enabling Technologies		**IoT in 5G Service Requirements**								
		Data Rate	**Mobility**	**Latency**	**Connection Density**	**Reliability**	**Positioning**	**Coverage**	**Energy Efficiency**	**Spectrum Efficiency**
Wide and flexible bandwidth technology	mmWave Band Communication and large-scale antenna	[7,202,225–227]		[202]			[233]	[5]	[202]	[7,29,214]
	Heterogeneous Multi-RAT Integration	[5,217,228–232]						[5]		
	Cognitive Radio and Spectrum Sharing							[5]		
Advanced modulation and coding	Advanced Modulation	[52,234–236]	[237,238]	[239]		[237,239]		[237]		
	Advanced Channel Coding	[235]		[235]						[216]
Duplexing	In-band FD			[124]				[5]		[7,29,214]
	Dynamic TDD	[240]		[240]						[9]
Multiple access and waveform	Multiple access			[216]					[218]	[7,9,29,216,256,257]
	New waveform				[5]					[7,9,29,216,256,257]
Advanced interface management	SND and SWSC	[5]								
Access architecture related radio technologies	Advanced small cell	[7,202]					[5]	[5,251]	[7,202,217]	[202,257]
	MN	[202]	[202]					[5]	[202]	
	Enhanced wireless backhaul							[5]		
	D2D	[202,248]	[7,241,244]					[245–247]	[7,202,215]	[7,9,29,202,252]
Energy related technologies	Energy harvesting						[100,253]			
	UAV	[254]				[254]		[183–185]		
Other important technologies	mMIMO	[7,202,249]		[13,202]		[249]		[200]	[217]	[7,9,214,216,257]
	VLC	[202,250]		[202]					[202,258]	
	SIC		[202]	[202,236]						
	V2X			[255]				[255]		

Legend: IoT (Internet of Things), 5G (Fifth Generation), mmWave (Milimeter-wave), RAT (Radio Access Technology), FQAM (Frequency Quadrature Amplitude Modulation), FD (Full Duplexing), TDD (Time Division Duplexing), SND (Simultaneous Non-unique Decoding), SWSC (Sliding Window Superposition Coding), MN (Moving Network), D2D (Device-to-Device), mMIMO (massive Multiple Input Multiple Output), VLC (Visible Light Communication), SIC (Self Interference Cancelation), V2X (Vehicle to Everything), UAV (Unmanned Aerial Vehicles).

Table 6. 5G enabling technologies—research directions.

5G Enabling Technologies		Research Gaps and Directions	References
Wide and flexible bandwidth technology	mmWave band communication and large-scale antenna	(1) 3D channel modeling; (2) dynamic power control; (3) user scheduling and congestion control; (4) hardware limitation and adaptive beam-steering technique; (5) design of mobility management and admission control for mmWave-based dense HetNet; (6) design of frequency management schemes for mmWave; (7) Tactile Internet; (8) effective and efficient mmWave implementation in HetNets (access and networking).	[7,87,217]
	Heterogeneous multi-RAT integration	(1) cell-association; (2) traffic-offloading algorithms; (3) interference management schemes in case of inter user and inter cell interference; (4) cross-tier handover, access admission, and mobility management schemes of a multi-tier HetNets.	[196,217]
	Cognitive radio and spectrum sharing	(1) Spectrum sensing (design of cooperative frameworks, choose cooperative secondary users and transmit cooperative information); (2) develop framework and algorithms for group handoff of secondary users and security; (3) simulation of different attacks and scenarios to enhance security; (4) in-depth performance analysis between GFDM and UFMC in CR settings.	[29,110]
Duplexing	In-band full duplexing	(1) Redesign of network and management; (2) antenna and circuit design and development of the theoretical foundation; (3) analyze the throughput of a network of randomly deployment terminals sing stochastic geometry; (4) characterize the capacity advantage due to IFDB in various network scenarios; (5) guidelines to practical design: coding, modulation, power allocation, beamforming, channel estimation, equalization, digital interference cancellation and decoding, (6) design of a MAC layer.	[55,197]
Multiple access and waveform	New waveform	(1) Performance of SIC cancelation or filtering on f-OFDMA; (2) balance of time and frequency dispersion and design an efficient filter prototype for UFMC.	
Access architecture related radio technologies	Advanced small cell	(1) Expect of wireless backhauling on user experience; (2) exploitation of location data and fingerprints in optimizing small cell discovery in terms of time and energy- efficiency; (3) interference management when integrating D2D and small cells.	[34,80]
	Enhanced wireless backhaul	(1) TDD multi-flow coordination schemes to avoid bottlenecks in the downlink backhaul; (2) Backhaul aware association in ultra-dense deployment; (3) reliability and security of the backhaul.	[34,88,198]
	Moving network	(1) Resource allocation and interference in the mobile relay when trains are moving from opposite directions; (2) handover decision of users (more than one train arrive or depart, stop or pass); (3) group mobility for users on board very high-speed vehicles; (4) design od cooperative communication schemes; (5) deployment of moving networks in various vehicle environments, not just on fixes route railways.	[5]
	D2D communication	(1) Interference management (mode selection, resource allocation and power control); (2) integration of novel reputation-based mechanism for identify and avoid malicious users from multiple users in multi-hop D2D communications; (3) testing of D2D interference management schemes in 5G scenarios (mmWave, cell densification).	[29,208,209]
Energy related technologies	Energy harvesting	(1) Improving energy harvesting schemes; (2) simulation of proposed models; (3) integration with other 5G technologies.	[100,182,253]
	UAV	(1) Optimal deployment, mobility and energy-efficient use of UAVs; (2) integration with other 5G technologies.	[81]
Other technologies	mMIMO	(1) Performance of practical mMIMO.	

Legend: IoT (Internet of Things), 5G (Fifth Generation), mmWave (Milimeter-wave), RAT (Radio Access Technology), D2D (Device-to-Device communication), mMIMO (massive Multiple Input Multiple Output), 3D (Three Dimensional), HetNet (Heterogeneous Network), GFDM (Generalized Frequency Division Multiplexing), UFMC (Universal Filtered Multi Carrier), CR (Cognitive Radio), IFDB (In-band Full Duplexing), MAC (Medium Access Control), f-OFDMA (filtered Orthogonal Frequency Division Multiple Access), TDD (Time Division Duplexing), UAV (Unmanned Aerial Vehicle).

5.1. Wide and Flexible Bandwidth Technology

mmWave band communication and large-scale antennas are promising technologies for future 5G networks. The mmWave band covers frequencies from 30 GHz to 300 GHz [202], and from an industry and wireless academia point of view, it is a unique solution for solving 5G capacity requirements [96]. mmWave band communications will provide high data rates [7,202,225–227] utilizing a much larger spectrum bandwidth that can reach up to 5 GHz [39] and by using directional antennas and high attenuation [40]. To provide sufficient antenna gain mmWave requires implementation of large-scale antennas at the transmitter and receiver side [96]. Deployment of large antenna arrays with mmWave will also bring high spectral efficiency, high throughput and channel gain [7]. Despite all of its advantages, mmWave needs line of sight (LOS) operation [41], while the effective communication distance of mmWave signals is within 200 m due to the propagation characteristic of this frequency band [29]. Open problems associated with mmWave include three dimensional (3D) channel modeling, dynamic power control, user scheduling and congestion control, hardware limitation and the adaptive beam-steering technique, as described in [7]. The problem of high power consumption of a large number of antennas in an array [7], high efficiency low complexity adaptive antenna array processing algorithms [29] and innovative hardware architecture of large-scale antenna transmitters [29] still remain unsolved. A proposal of design guidelines in architectures and protocols for mmWave communications is presented in [42]. It is demonstrated that new mmWave technologies, which are under investigation for 5G communications systems, will be able to provide indoor centimeter (cm)-accuracy localization in a robust manner, ideally suited for Assisted Living (AL) [228].

Heterogeneous multi-radio access technologies (multi-RAT) integration is specific to 5G networks radio design that coexists with existing networks. Since 5G networks will not be developed to replace current wireless networks, but rather to advance and integrate existing network infrastructures with new ones [217], we refer to 5G as a heterogeneous network. Multi-RAT is defined as the capability of a mobile network to support multiple radio access technology with seamless interworking among them [229]. When deployed in heterogeneous networks (HetNets), with traffic offloading among different RATs, multi-RAT improves capacity [230], supports better communication rates [34,117–119,231,232], better energy efficiency [34,117–119,231,232], and ensures seamless connectivity with higher QoS [230]. In designing a heterogeneous RAT, researches are finding solutions for cell-association and traffic-offloading algorithms [217].

Cognitive radio with spectrum sharing is a new software defined technology, which is expected to improve the utilization of the congested radio frequency (RF) spectrum [43]. In 5G networks, it is used for designing multi-tier architectures, removing interference among cells, and minimizing energy consumption in the network [44–47,120,233]. Moreover, a spectrum sharing technique can be used along with the CR technology to integrate the 5G spectrum [48,121]. During the practical implementation of the CR and spectrum sensing (SS) technique researchers had to design cooperative frameworks, choose cooperative secondary users and transmit cooperative information during the spectrum sensing, further developing the framework and algorithms for the group handoff of secondary users and enhancing security [29]. Researchers are already working on designs of protocols for different IoT application, based on cognitive radio, and some of them are presented in [49–51,122]. Technologies in this group are used together to optimize 5G performance requirements (e.g., a prototype of mmWave integrated HetNet in [123] and HetNet that incorporates massive multiple-input and multiple-output (mMIMO) and mmWave technologies [217]).

5.2. Advanced Modulation and Coding

This technological group involves advanced modulation (i.e., frequency and quadrature amplitude modulation (FQAM)) and advanced channel coding schemes.

Advanced modulation schemes group includes FQAM, Amplitude and Phase Shift Keying (APSK), Unitary Space-Time Modulation (USTM), Spatial Modulation (SM), Wave Modulation

(WAM), and Orthogonal Time Frequency and Space (OTFS). The FQAM is a combination of frequency shift keying (FSK) and quadrature shift keying (QAM) [124–126]. This modulation can achieve a higher transmission rate for cell edge users reducing interference at cell edge [52,234–236]. FQAM also improves energy efficiency, which makes it adequate for MTC devices with stringent energy consumption requirements [124]. Due to performance advantages in terms of Frame Error Rate (FER) [53,236], FQAM is an ideal candidate for services with high coverage and reliability requirements [237]. APSK is another modulation which draws a lot of attention. It is shown that its main performance gain (i.e., to achieve a channel capacity very close to Shannon's) relies on advanced channel coding and demodulation algorithms [237]. This adds more complexity at the APSK transmitter and receiver. Another modulation, which does not need Channel State Information (CSI) to enable high throughput, is called USTM [237]. USTM and its extension (see [238]) is very useful for 5G services with high mobility [127] or latency and reliability constraints [239]. Other modulation schemes involve SM [128], and proprietary WAM and OTFS [237]. On the basis of the foregoing, researches have analyzed and compared many modulation forms, but still have not found a practical guide on how to choose modulation in any of the 5G use cases.

Advanced channel coding techniques are used for correcting the communication errors caused by noise, interference, and poor signal strength [129]. Authors in [54,129,130] compared turbo, low density parity check (LDPC) and polar codes in decoders in contrast to 5G requirements: (1) maturity; (2) throughput and latency; (3) error correction capability; (4) flexibility; (5) computation complexity; (6) interconnect complexity; (7) high-performance flexible implementation complexity; and (8) backward compatibility. This comparison showed that turbo codes hold the greatest promise for offering high performance throughputs, latencies and error correction capabilities, as well as high degrees of flexibility at the lowest implementation complexity [129] in most 5G use cases. However, further work is needed to implement a decoder based on this code followed by detail analysis.

5.3. Duplexing

This technological group includes in-band full duplexing (FD) and dynamic time division duplexing (TDD).

In-band FD or simultaneous data transmission and reception will provide a 1000-fold increase in throughput [131,240], double spectral efficiency [132,240], and reduce the air interface delay [240]. The central research problem for the practical implementation of an in-band full-duplex radio is the attenuation of the self-interference signal by an adequate amount [132]. For the practical implementation of an in-band full-duplex radio, many aspects of network design and management need to be restructured, where terminals antenna and circuit design and the development of theoretical foundation are in focus [55]. One practical implementation of the full-duplex radio is shown in [133]. Authors in [134] commented that for the design of a full-duplex radio, it is necessary to unify researches from three domains, i.e., RF circuit and system design, digital signal processing and networking.

Dynamic TDD is the predecessor of FD transmission technology and a candidate for 5G [133,135]. It represents a scheduling technique in which every base station (BS) is free to choose its own uplink/downlink (UL/DL) split [136–139]. This technique is used to adapt the allocation of network resources to variable traffic requirements [139,140], often found in ultra-densely deployed networks [141]. The dynamic TDD can significantly increase bandwidth efficiency [142] and provide higher throughput and low latency [141]. However, it is characterized by the severe co-channel interference (CCI) [141–143]. Dynamic TDD could be used in combination with D2D communication and in the self-backhauling scenario, as described in [55].

5.4. Multiple Access and Waveforms

Multiple access techniques are becoming an important technology in 5G because of their ability to support mMTC activity-based IoT classes with urgent deploy demand [144]. They include several non-orthogonal multiple access (NOMA) forms: multi-user shared multiple access (MUSA) [145–148], resource spread multiple access (RSMA) [149], sparse code multiple access (SCMA) [150–152], pattern division multiple access (PDMA) [153–155], interleave-division multiple access (IDMA) [156,157], and NOMA by power domain [158]. The NOMA is a radio access technology design for enabling greater spectrum efficiency [56,159–162,207], higher cell-edge throughput, relaxed channel feedback, and low transmission latency [99]. NOMA can be employed to enhance user fairness and to support massive connections with diverse QoS requirements [163]. In NOMA, there are several challenges and open issues, such as dynamic user pairing, the impact of transmission distortion, the impact of interference, resource allocation, NOMA with multiple antennas, heterogeneous networks, outage probability analysis, practical channel model, uniform fairness, NOMA with antenna selection, carrier aggregation and other challenges as discussed in [216]. There are still many challenging issues for SCMA, which need to be solved in future work. For example, there are several open issues in SCMA transceiver design [57], the optimization of algorithms for user grouping and power allocation [164], and further enhancement of the SCMA and MIMO combination.

New waveforms have become a serious candidate for 5G being studied in terms of: (1) modulation based on pulse shaping: filter bank multicarrier (FBMC) [58], generalized frequency division multiplexing (GFDM) [59], pulse shaped OFDM [165] and QAM-FBMC [241]; (2) modulation based on sub-band filtering: universal filtered multi carrier (UFMC) [242], filtered OFDM (f-OFDM) [243] and resource block f-OFDM (RB-f-OFDM) [244]; other modulation format: guard interval discrete Fourier transform spread OFDM (GI DFT-s-OFDM) [245], spectrally-precoded OFDM (SP-OFDM) [246] and orthogonal time frequency and space (OTFS) [247]. The f-OFDM is seen as a potential candidate for IoT applications [60]. Due to narrow sub-bands and thereby pure detection performance, additional processing is needed [60]. Performance of self-interference cancellation (SIC) or filtering on f-OFDMA [60] remains a topic for further study. Additionally, it is interesting to consider the balance of time and frequency dispersion in UFMC, as well as the design of an efficient prototype filter according to application scenarios [60].

5.5. *Advanced Interface Management*

This technological group includes receiver advances in terms of simultaneous non-unique decoding (SND) and sliding-window superposition coding (SWSC).

SND follows a rule that implies that each receiver attempts to recover the code words from intended and interfering senders [248]. The combination of advanced receivers and joint scheduling provides an improvement of over 50% in cell edge throughput without sacrificing the cell average throughput [5]. This gain demonstrates that if 5G networks incorporate advanced interference management, they will provide a virtually edgeless end-user experience [5].

SWSC [61,62] combines the theory concept from superposition coding without rate splitting [63], block Markov coding [166,167], successive cancellation decoding [63,64,168], and sliding-window decoding [65,169,249]. The sliding-window coded modulation (SWCM) aims to mitigate inter cell interference at the physical layer by achieving simultaneous decoding performance with point-to-point channel codes, low-complexity decoding, and minimal coordination overhead [170]. The realization of the theoretical concept to the practical transmission coding scheme is an important research direction in SWSC [5].

5.6. *Access Architecture Related Radio Technology*

This technological group includes ultra-densification, enhanced wireless backhaul, moving networks, and D2D communication.

Advanced small cell [66,123] deployment is considered to be one of the key enablers for achieving many of the requirements currently envisioned for 5G [67], with higher data rates [68,171,250] and more capacity [171–174], as most important. Higher data rates and smaller battery consumption can be achieved using short distances in the small cell [69]. Solving the capacity and data rate challenge with network densification could be very expensive in terms of equipment, maintenance, and operations [200]. With denser cell deployment come significant challenges in the design of a high-performance backhauling system for RAN and the impact of backhaul on radio resource management (RRM) [70]. However, there are in existence many interesting topics to be further investigated which can be grouped around several problem areas [34]: user association, backhauling, interference management, energy efficiency, and propagation modelling.

Moving networks (MN) are the combination of multi-hop and vehicular communications concepts [69,71]. The MN deploys one or several moving relay node(s) (MRNs) [175,176,251] on vehicles that form their own cell(s) inside the vehicle to serve vehicular users [72]. Challenges in using MRN are efficient backhauling, design of efficient resource allocation and interference management techniques, as well as mobility management schemes to exploit the benefit of group handovers for vehicular user equipment (UE) devices served by the same MRN [72]. The main research challenges related to MN concept are associated with complexity management due to the mobility of access points and providing a high-rate wireless backhaul link from the moving cell to the fixed network [69].

Enhanced wireless backhaul is one of the main challenges in hyper-dense 5G networks [34,217]. The performance of wireless backhaul is dictated by the environment and traffic profile of the intended use case [9]. In UDN except mmWave, new approaches are needed, e.g., interface aware routing and intelligent resource allocation [9], as these links may occupy part of the spectrum used in the access network [73]. Latency and reliability of this link are important issues to be considered being prone to blocking and fading [69]. In any case, further research is necessary to explore TDD multi-flow coordination schemes to avoid bottlenecks in the downlink backhaul [9]. The guidelines for deploying future 5G wireless backhaul networks in economical and highly energy-efficient ways are provided in [74].

D2D communication is defined as a direct route of data traffic between spatially closely located mobile UE [75,177,178]. The advantages of D2D communication compared with the traditional cellular method include the reduction of transmission latency [73,75] and power consumption [75], improvements in coverage [71,76,179], spectral and energy efficiency [77], and throughput, when power control and resource allocation methods are used [78]. The use of D2D communications has an overall positive impact on system capacity in cellular environments. D2D communication brings challenges and complexities related to interference management [79,80], QoS requirements [79], and resource allocation [34,215]. The design of D2D direct communication link is still a hot topic [29].

5.7. Energy Related Technologies

IoT applications span a broad range of domains including home automation, healthcare, surveillance, transportation, smart environments, etc. One of the most important obstacles for implementing such an impressive scheme is supplying adequate energy to operate the network in a self-sufficient way without compromising QoS [180]. Since energy efficiency is of most importance to battery constrained IoT devices, researches have focused their work on the development of the device energy saving mechanisms.

Energy harvesting is a new paradigm which uses solar, thermal, wind and kinetic energy sources to power sensor nodes and consequently prolong network lifetime [181]. Among different energy harvesting methods, wireless energy harvesting (WEH) has proven to be one of the most promising solution for energy aware IoT devices, because of its simplicity, ease of implementation, and availability [180]. This concept will improve some of the 5G high network communication requirements, like reliability of IoT communications, as presented in [182]. Authors in [252] have shown that the integration of social awareness and energy harvesting in D2D communication results in higher system capacity. Network architectures proposed in [100,253] have shown better energy efficiency in 5G wireless network. Researchers could work on improving this architecture and integration with various 5G technologies in the future.

UAV implies a flying vehicle without the driving presence of a human pilot to control it on-board [113]. Drones are a possible example of UAVs, although many other robotics related applications could be part of this application group [113]. UAVs can play a vital role in IoT scenarios where devices are unable to transmit over a long distance due to their energy constraints. In this case UAVs play the role of moving aggregators which fly toward one IoT devices, collect the data, and transmit it to other devices [81]. In [183] authors presented UAV–based floating relay (FR) for cell dynamic and coverage improvement. Deployment of unmanned aerial base stations in 5G heterogeneous architecture can improve throughput [254], coverage [183–185,254], connectivity [184,185], and 5th percentile spectral efficiency [254]. On-demand wireless systems with low-altitude UAVs are in faster to deploy, more flexibly reconfigured, and likely to have better communication channels due to the presence of short-range line-of-sight links [186] when compared to terrestrial communications or those based on high-altitude platforms. The utilization of highly mobile and energy-constrained UAVs for wireless communication introduces many new challenges [186], some of them are listed in [82]. To effectively use UAVs for IoT, several challenges must be addressed such as optimal deployment, mobility and energy-efficient use of UAVs [81].

5.8. Other Technologies

Along with the aforementioned technologies, a lot of research attention is devoted to technologies, such as mMIMO, visible light communication (VLC), SIC, vehicle-to-everything (V2X), etc.

mMIMO technology [73,123] promises significant gains in data rate and link reliability [187], reduces latency and energy [13], simplifies media access control (MAC) layer [13], shows robustness against intentional jamming [13], unintended man-made interface [83], and increases capacity [127,198] due to spatial multiplexing [123]. Reliable links are provided by benefiting from spatial diversity and the mitigating effects of fast fading, beamforming, and zero forcing caused by multi-user interference [203]. The mMIMO can be exploited to extend the coverage of higher frequency bands by relying on beamforming gains [200]. Other specific benefits of mMIMO system are: increased capacity 10 times or more with simultaneous improvement in radiated energy efficiency in the order of 100 times, the possibility to use inexpensive, low-power components, the reduction of latency on the air interface, and multiple access layer simplification [83]. The low complexity mMIMO uplink scheme for IoT lightweight devices is presented in [188]. The performance of practical mMIMO system needs to be investigated, since the research community pays attention to analyzing the performance of mMIMO in an ideal channel state information assumption [73].

VLC is a growing technology for short range, high capacity LOS optical links [189]. It uses a visible range of the electromagnetic spectrum (370–780 nm) which provides data transmission and room illumination using light emitting diodes (LEDs). Prominent features of VLC are an abundant license-free spectrum, the ability to provide multiple gigabit-per-second data rates, low energy consumption, and low implementation costs [190]. VLC is sensitive to sunlight and is not able to work long range without LOS. Since VLC coverage is LOS limited [84,191], this is known as LOS blocking [192]. With poor performance in non-line-of-sight scenarios, VLC networks fail to provide convenient UL coverage at the current state-of-the-art, and each AP illuminates only a small confined cell compared to cellular RF networks [192]. VLC applications are expected to include IoT, wireless Internet access, and vehicle-to-vehicle (V2V) communications, broadcast from LED, M2M communications, positioning systems, and navigation. The problem of how to provide mobile applications over VLC is still quite an open one [189].

SIC implementation enables low-latency applications in a cost effective manner [132]. SIC can be used to increase link capacity, spectrum virtualization, any-division duplexing, novel relay solutions, and enhanced interface coordination [132]. Practical SIC implementation is still in the investigation phase.

V2X is the communication between a vehicle and everything with which it might interact (e.g., other vehicles, traffic operators and service providers). It is used in conjunction with D2D for coverage extension and latency reduction in 5G networks [255]. V2X communication might play a vital role in terms of implementing smart and efficient traffic solutions [193], improving road safety, traffic efficiency, and driver convenience. To reduce traffic congestion one may use an intelligent route management system based on V2X communication [7]. Since it has big potential in autonomous driving application, the localization of vehicles in dense urban areas is difficult, so several algorithms are proposed to solve the problems [194]. Many V2X applications are described in existing literature [85,195]. However, there is still a need to design vehicular mobility management strategies in next UDN networks and to find a way to enhance existing connected vehicle services with V2X [86].

These technologies are highlighted as the main 5G driver in existing literature [5–7,96,207]. Authors compare these technologies and try to implement them through prototypes, or test the combination of these technologies. However, other technologies exist, such as cloud-RAN [7], Coordinated Multi-Point (CoMP), White Space Spectrum [208], which are not in the scope of this paper.

5.9. Summary of IoT in Enabling Technologies

Performance requirements of activity-based IoT application classes have served to identify the enabling technologies in the radio access part of 5G networks, which are summarized in Table 5. Various 5G enabling technologies have been sorted into eight technological groups:

1. Wide and flexible bandwidth technology: mmWave band communication and large-scale antennas, heterogeneous multi-RAT integration, cognitive radio, and spectrum sharing;
2. Advanced modulation and coding: advanced modulation schemes, advanced channel coding;
3. Duplexing: in-band FD, dynamic TDD;
4. Multiple access and waveform: multiple access, new waveforms;
5. Advanced interface management: SND, SWSC;
6. Access architecture related radio technologies: advanced small cell, MN, enhanced wireless backhaul, D2D;
7. Energy related technologies: energy harvesting, UAV;
8. Other technologies: mMIMO, VLC, SIC, V2X.

These technologies have been discussed in terms of their possibilities to meet performance requirements of activity-based IoT application classes and identify research gaps and directions, which are summarized in Table 6.

We have highlighted technologies only used to satisfy high priority performance requirements of mMTC activity-based IoT application classes, i.e., connection density, positioning accuracy, and coverage. We have focused on these technologies from telco's perspective, since the area of mMTC activity-based IoT classes is more mature, as its development has already started within LTE, while uMTC poses new research questions to be answered in order to achieve unprecedented levels of reliability needed for new applications in 5G.

The new waveform technology may be used to fulfil the requirements of almost every activity-based IoT application class in terms of connection density. This technology affects the connection density by definition. Analysis of different modulation formats indicates that f-OFDM is the most suitable candidate for IoT applications with high connection density requirements. In this regard, a deeper and more comprehensive analysis of f-OFDM is needed in the context of different mMTC activities (i.e., ticketing, tracking, monitoring, and managing/controlling). The result of the analysis to be performed should be the discovery of an optimal waveform for each activity-based IoT class which has to be integrated with other 5G service classes.

Large scale antennas and advanced small cell technologies can be used to satisfy the requirements of ticketing-, tracking-, and uMTC managing/controlling-based IoT application classes in terms of positioning accuracy. Fulfilling these performance requirements is rather a business than a technical decision. The size of the 5G cell must be planned to meet the desired position accuracy since it is very important for future IoT applications, such as automated driving, remote surgery, robotics, taxis, etc.

Wide and flexible bandwidth technologies, in-band full duplex technologies, access architecture related radio technologies, and mMIMO can be used to achieve the high requirements of ticketing-, tracking-, and monitoring-based IoT application classes in terms of coverage. The combination of these technologies should be tested to find the optimal solution to meet these performance requirements. Since small cell deployment has an impact on required position accuracy, they should serve as a basis for achieving the desired level of coverage. Along with small cell deployment, mMIMO and mmWave technologies are present in almost every 5G prototype.

Since this section discusses radio technologies used to accomplish performance requirements of mMTC activity-based IoT application classes, it can serve telecom operators and other interested parties depending on their interest and potential to utilize these findings towards IoT implementation and monetization. It describes each technology in terms of definition, advantages, disadvantages, and the possible impact on the performance requirements of a broad range of IoT applications that drive the deployment of 5G networks. Moreover, this section can be useful to the research community interested in this attractive field to address recognized research gaps and directions.

6. Discussion

Telecom operators have the opportunity to capture a share of the revenue that is generated by IoT implementation depending on their role in the IoT value chain. Regardless of their role, telcos have to face many technical challenges in order to meet the changing connectivity and performance requirements. Since current cellular networks limit numerous IoT applications, new technologies are being introduced leading towards 5G networks. Therefore, telcos have to focus on deploying these network technologies in order meet the changing requirements necessary to achieve success in IoT.

In this regard, writing this paper was motivated by the challenge of providing an enhanced understanding of the scope and classification of the broad range of IoT applications in order to determine and prioritize their performance requirements with the goal of specifying the enabling technologies towards 5G networks. The aim has been to propose a new classification of IoT applications, define and prioritize the performance requirements of such IoT application classes, and give insight into state-of-the-art technologies used to meet these requirements from telco's point of view. The motivation that led to the focus of this paper being on IoT applications classification, performance requirements, and 5G enabling technologies could be explained by telco's need for added value from IoT services. Hence, an analysis of IoT customer service requests inspired us to propose an activity-based classification of IoT applications as it can, according to authors' best knowledge, has allowed telcos to more precisely specify their performance requirements and 5G enabling technologies, thereby improving customer experience.

In this regard, the paper fulfilled the following four objectives: (1) the identification of activities relevant to IoT applications and their usage as a new criterion for IoT application classification; (2) the specification and prioritization of performance requirements of such IoT applications classes; (3) the analysis of the radio technologies used to accomplish IoT application requirements; and (4) the identification of the research gaps and the recommendation of new research directions.

Through fulfilling these objectives, we reviewed literature from the fields of IoT in 5G service classifications, IoT in 5G performance requirements, and IoT in 5G enabling technologies. Since the first aim of this paper was to propose a new classification of IoT applications, the existing approaches have been summarized to serve as a basis to identify their drawbacks and formulate the appropriate solution to overcome them. In this context, we proposed a new approach to IoT applications classification, which was based on the activity as a new classification criterion denoting the main function/purpose of specific IoT application. This approach enabled a clearer and more precise positioning of particular application in the IoT application spectrum, as well as the determination of performance requirements and enabling technologies from telco's point of view. The activity-based IoT application classification facilitated the specification of the performance requirements and determination of technologies which enable these requirements to be fulfilled. In this context, the proposed approach served as a basis for the simplification of the realization of particular IoT application. For example, although the monitoring- and tracking-based applications seem to be similar, they set different performance requirements on the network, thereby allowing the proposed approach to precisely grade the IoT applications from the same IoT application domain.

Furthermore, we associated the activity-based IoT application classes with the 5G service classes, i.e., mMTC and uMTC, in order to specify and prioritize their performance requirements. It was determined that almost each activity-based IoT application class poses high requirements in terms of connection density, whereas ticketing-based and tracking-based IoT application classes additionally require high positioning accuracy and coverage. In order to analyze these performance requirements, we have summarized the radio technologies used to implement the future 5G networks. The focus was on the technologies used to meet the aforementioned performance requirements of mMTC activity-based IoT application classes, since mMTC is more mature, as its deployment has already started, while uMTC requires further research to achieve incomparable levels of reliability needed to enable new applications in 5G.

The analysis showed that new waveform technology can be used to meet the requirements in terms of connection density; large-scale antennas and advanced small cell technologies can be used for the purpose of satisfying the requirements in terms of positioning accuracy; while wide and flexible bandwidth technologies, in-band full duplexing technologies, and access architecture related radio technologies (i.e., advanced small cell, enhanced wireless backhaul, moving network, and D2D communication) can be used to achieve high requirements in terms of coverage. In addition, the conducted research study allowed us to highlight a number of open research issues that could serve the research community and other stakeholders interested in this contemporary and attractive field. In this context, we have recognized research gaps and directions which mostly relate to network redesign and optimization in order to accommodate large-scale IoT applications.

7. Conclusions

The IoT paradigm has the potential to revolutionize all areas of daily life of individuals, businesses, and society as a whole. Telcos enjoy a central role in the paradigm of IoT because of owing communication infrastructure which is exposed to the numerous technical challenges due to changing connectivity and performance requirements of various IoT applications. These requirements cannot be met with the current cellular networks which create the need to introduce new types of technologies leading toward 5G networks as the main driver for enabling numerous IoT applications. In this context, this paper proposed the activity-based classification of IoT applications and specification of their performance requirements in order to identify 5G radio technologies used to meet them, all from telco's perspective. Activity-based classification of IoT applications indirectly allowed the construction and distribution of performance, as IoT value proposition, while using 5G enabling technologies, as IoT resources in telco's internal value chain. In this context, high performance requirements of each activity-based IoT application class (i.e., connection density, positioning accuracy, coverage) served as a basis to analyze various enabling technologies in radio access part of 5G network in terms of advantages, disadvantages, and research gaps.

On the basis of the conducted analysis, we concluded that the following technologies can meet the high performance requirements of mMTC activity-based IoT application classes: new waveform technology (in terms of connection density), large scale antennas (in terms of positioning accuracy), wide and flexible bandwidth technologies, in-band full duplexing technologies, and access architecture related radio technologies (in terms of coverage). According to the identified research gaps, one may conclude that the optimal solutions for each technology are still in its infancy. This implies that any 5G enabling technology should be first implemented and tested through prototype construction before the deployment of specific IoT application. Thereafter, the technology combination that meets the performance requirements of each activity-based IoT class should first be found. Finally, the practical implementation of different technological combinations may further lead to a deep and comprehensive analysis of QoS and QoE in the context of IoT applications.

Acknowledgments: The authors would like to thank the anonymous reviewers for their valuable comments and suggestions to improve the quality of the paper.

Author Contributions: Enida Cero and Jasmina Baraković Husić conceived and designed the experiments (research study); Enida Cero performed the experiments (research study); Sabina Baraković analyzed the data and contributed materials; Enida Cero and Jasmina Baraković Husić wrote the paper.

Conflicts of Interest: The authors declare no conflict of interest.

References

1. Antonopoulos, A.; Perillo, C.; Verikoukis, C. Internet Service Providers vs. Over-the-Top Companies: Friends or Foes?—Short talk. *SIGMETRICS Perform. Eval. Rev.* **2016**, *44*, 37. [CrossRef]
2. Antonopoulos, A.; Kartsakli, E.; Perillo, C.; Verikoukis, C. Shedding Light on the Internet: Stakeholders and Network Neutrality. *IEEE Commun. Mag.* **2017**, *55*, 216–223. [CrossRef]
3. IoT-Ignite. Role of Telcos in Internet of Things. Available online: https://devzone.iot-ignite.com/wp-content/uploads/2017/01/Role-of-Telcos-in-IoT.pdf (accessed on 5 September 2017).
4. Kaur, S.; Singh, I. A Survey Report on Internet of Things Applications. *Int. J. Comput. Sci. Trends Technol.* **2016**, *4*, 330–335.
5. 5G Forum. 5G Vision, Requirements, and Enabling Technologies. Available online: http://kani.or.kr/5g/whitepaper/5G%20Vision,%20Requirements,%20and%20Enabling%20Technologies.pdf (accessed on 10 July 2017).
6. Saha, R.K.; Saengudomlert, P.; Aswakul, C. Evolution towards 5G Mobile Networks—A survey on Enabling Technologies. *Eng. J.* **2016**, *20*, 87–112. [CrossRef]
7. Akyildiz, I.F.; Nie, S.; Lin, S.C.; Chandrasekaran, M. 5G roadmap: 10 Key Enabling Technologies. *Comput. Netw.* **2014**, *106*, 17–48. [CrossRef]
8. NGMN Alliance. 5G White Paper-Executive Version. Available online: https://www.ngmn.org/uploads/media/NGMN_5G_White_Paper_V1_0.pdf (accessed on 10 July 2017).
9. Popovski, P.; Mange, G.; Gozalves-Serrano, D.; Rosowski, T.; Zimmermann, G.; Agyapong, P.; Fallgren, M.; Hoglund, A.; Queseth, O.; Tullberg, H.; et al. Deliverable D6.6 Final Report on the METIS 5G System Concept and Technology Roadmap. Available online: https://www.metis2020.com/wp-content/uploads/deliverables/METIS_D6.6_Summary.pdf (accessed on 10 July 2017).
10. Aly, H.; Elmogy, M.; Barakat, S. Big Data on Internet of Things: Applications, Architecture, Technologies, Techniques, and Future Directions. *Int. J. Comput. Sci. Eng.* **2015**, *4*, 300–313.
11. Vermesan, O.; Friess, P. *Internet of Things—From Research and Innovation to Market Deployment*; Riverbed: Aalborg, Denmark, 2014.
12. Amaral, L.A.; de Matos, E.; Tiburski, R.T.; Hessel, F.; Lunardi, W.T.; Marczak, S. Middleware Technology for IoT Systems: Challenges and Perspectives Toward 5G. In *Internet of Things (IoT) in 5G Mobile Technologies*; Mavromoustakis, C., Mastorakis, G., Batalla, J., Eds.; Springer International Publishing: Cham, Switzerland, 2016; pp. 333–367.
13. OECD. Machine-to-Machine Communications: Connecting Billions of Devices. Available online: http://www.oecd-ilibrary.org/docserver/download/5k9gsh2gp043-en.pdf?expires=1499694889&id=id&accname=guest&checksum=F403637E723693581F03EA9D6F3A3C3B (accessed on 10 July 2017).
14. Zheng, K.; Hu, F.; Wang, W.; Xiang, W. Radio Resource Allocation in LTE Advanced Cellular Networks with M2M Communications. *IEEE Commun. Mag.* **2012**, *50*. [CrossRef]
15. Zhang, Q.; Fitzek, F.H.P. Mission Critical IoT Communication in 5G. In *Future Access Enablers for Ubiquitous and Intelligent Infrastructures*; Springer International Publishing: Cham, Switzerland, 2015; Volume 159, pp. 35–41.
16. Oughton, E.J.; Frias, Z. Exploring the Cost, Coverage and Rollout Implications of 5G in Britain. Available online: http://www.itrc.org.uk/wp-content/uploads/Exploring-costs-of-5G.pdf (accessed on 10 July 2017).
17. Chen, Y.; Wang, W. Machine-to-Machine Communication in LTE-A. In Proceedings of the 2010 IEEE Vehicular Technology Conference (VTC 2010-Fall), Ottawa, ON, Canada, 6–9 September 2010.
18. Booysen, M.J.; Gilmore, S.J.; Zeadally, S.; van Rooyen, G.J. Machine-to-Machine (M2M) Communications in Vehicular Networks. *KSII Trans. Internet Inf. Syst.* **2012**, *6*, 529–546. [CrossRef]

19. Niyato, D.; Xiao, L.; Wang, P. Machine-To-Machine Communications for Home Energy Management System in Smart Grid. *IEEE Commun. Mag.* **2011**, *49*, 53–59. [CrossRef]
20. De Matos, W.D.; Gondim, P.R.L. M-Health Solutions Using 5G Networks and M2M Communications. *IT Prof.* **2016**, *18*, 24–29. [CrossRef]
21. Investopedia. Business Model. Available online: http://www.investopedia.com/terms/b/businessmodel.asp (accessed on 3 September 2017).
22. Gassmann, O.; Frankenberger, K.; Csik, M. Revolutionizing the Business Model. In *Management of the Fuzzy Front End of Innovation*; Springer: New York, NY, USA, 2014.
23. Vermesan, O.; Bahr, R.; Gluhak, A.; Boesenberg, F.; Hoeer, A.; Osella, M. D02.01 IoT Business Models Framework. Available online: http://www.internet-of-things-research.eu/pdf/D02_01_WP02_H2020_UNIFY-IoT_Final.pdf (accessed on 3 September 2017).
24. Dijkmana, R.M.; Sprenkelsa, B.; Peetersa, T.; Janssenb, A. Business Models for the Internet of Things. *Int. J. Inf. Manag.* **2015**, *35*, 672–678. [CrossRef]
25. Farooq, M.O.; Sreenan, C.J.; Brown, K.N.C. Research Challenges in 5G Networks: A HetNets Perspective. In Proceedings of the 19th International ICIN Conference Innovations in Clouds, Internet and Networks, Paris, France, 1–3 March 2016.
26. Hu, F. 5G Overview: Key Technologies. In *Opportunities in 5G Networks*, 1st ed.; Hu, F., Ed.; CRC Press: Boca Raton, FL, USA, 2016; pp. 1–557.
27. Ford, R.; Zhang, M.; Mezzavilla, M.; Duttam, S.; Rangap, S.; Zorzi, M. Achieving Ultra-Low Latency in 5G Millimeter Wave Cellular Networks. *IEEE Commun. Mag.* **2017**, *55*, 196–203. [CrossRef]
28. Prasad, R. IMT for 2020 and Beyond. In *5G Outlook—Innovations and Applications*; Riverbed Publishers: Gistrup, Denmark, 2016; pp. 1–260.
29. Ma, Z.; Zhang, Z.; Ding, Z.; Fan, P.; Li, H. Key Techniques for 5G Wireless Communications: Network Architecture, Physical Layer, and MAC Layer Perspectives. *Sci. China Inf. Sci.* **2015**, *50*, 1–20. [CrossRef]
30. Rappaport, T.S.; Daniels, R.C.; Heath, R.W.; Murdock, J.N. Introduction. In *Millimeter Wave Wireless Communications*; Pearson Education: Upper Saddle River, NJ, USA, 2014.
31. Ge, X.; Chen, J.; Ying, S.; Chen, M. Energy and Coverage Efficiency Trade-off in 5G Small Cells Network. *arXiv* **2016**, arXiv:1612.04459.
32. Hossain, S. 5G Wireless Communication Systems. *Am. J. Eng. Res.* **2013**, *2*, 344–353.
33. Artiga, X.; Nunez-Martinez, J.; Perez-Neira, A.; Lendrino Vela, G.J.; Fare Garcia, J.M.; Ziaragkas, G. Terrestrial-satellite Integration in Dynamic 5G Backhaul Networks. In Proceedings of the 2016 8th Advanced Satellite Multimedia Systems Conference and the 14th Signa (ASMS/SPSC), Palma de Mallorca, Spain, 5–7 September 2016.
34. Kamel, M.; Hamouda, W.; Youssef, A. Ultra-Dense Networks: A Survey. *IEEE Commun. Surv. Tutor.* **2016**, *18*, 2522–2545. [CrossRef]
35. Kartsakli, E.; Lalos, A.S.; Antonopoulos, A.; Tennina, S.; Di Renzo, M.; Alonso, L.; Verikoukis, C. A Survey on M2M Systems for mHealth: A Wireless Communications Perspective. *Sensors* **2014**, *10*, 18009–18052. [CrossRef] [PubMed]
36. Morris, A. DT, Chinese Operators take NB-IoT to Market. Available online: http://www.lightreading.com/iot/nb-iot/dt-chinese-operators-take-nb-iot-to-market/d/d-id/734022 (accessed on 6 September 2017).
37. Vermesan, O.; Eisenhauer, M.; Sunmaeker, H.; Guillemin, P.; Serrano, M.; Tragos, E.Z.; Valino, J.; van der Wees, A.; Gluhak, A.; Bahr, R. Internet of Things Cogitive Transformation Technology Research Trends and Applications. In *Cognitive Hyperconnected Digital Transformation*; Vermesan, O., Bacquet, J., Eds.; River Publishers: Delft, The Netherlands, 2017; pp. 17–95.
38. Gawas, A.U. An Overview on Evolution of Mobile Wireless Communication Networks: 1G–6G. *Int. J. Recent Innov. Trends Comput. Commun.* **2015**, *3*, 3130–3133. [CrossRef]
39. Qi, Y.; Hunukumbure, M.; Nekovee, M.; Sgardoni, V. Quantifying Data Rare and Bandwith Requirements for Immersive 5G Experience. In Proceedings of the 2016 IEEE International Conference on Communications Workshops, Kuala Lumpur, Malaysia, 23–27 May 2016.
40. Sim, G.H.; Asadi, A.; Loch, A.; Widmer, J. Opp-Relay: Managing Directionaly and Mobility Issues of Millimeter-Wave via D2D Communication. In Proceedings of the I9th International Conference on COMSNETS 2017, Bangalore, India, 4–8 January 2017.

41. Mer, S.B. Smart Vehicle-to-Vehicle Communication with 5G Technology. *Int. J. Recent Innov. Trends Comput. Commun.* **2015**, *3*, 3241–3244.
42. Niu, Y.; Li, Y.; Jin, D.; Su, L.; Vasilakos, A.V. A Survey of Millimeter Wave Communications (Mmwave) for 5G: Opportunities and Challenges. *Wirel. Netw.* **2016**, *21*, 2657–2676. [CrossRef]
43. Rusek, F.; Persson, D.; Lau, B.K.; Larsson, E.G.; Marzetta, T.L.; Edfors, O.; Tufvesson, F. Scaling Up MIMO: Opportunities and Challenges with Very Large Arrays. *IEEE Signal Process. Mag.* **2012**, *30*, 1053–5888. [CrossRef]
44. Hong, X.; Wang, J.; Wang, C.X.; Shi, J. Cognitive Radio in 5G: A Perspective on Energy-Spectral Efficiency Trade-Off. *IEEE Commun. Mag.* **2014**, *52*, 46–53. [CrossRef]
45. Huang, L.; Zhu, G.; Du, X. Cognitive Femtocell Networks: An Opportunistic Spectrum Access for Future Indoor Wireless Coverage. *IEEE Wirel. Commun.* **2013**, *20*, 44–51. [CrossRef]
46. Lee, C.H.; Shih, C.Y. Coverage Analysis of Cognitive Femtocell Networks. *IEEE Wirel. Commun. Lett.* **2014**, *3*, 177–180. [CrossRef]
47. Wang, W.; Yu, H.; Huang, A. Cognitive Radio Enhanced Interference Coordination for Femtocell Networks. *IEEE Commun. Mag.* **2013**, *51*, 37–43. [CrossRef]
48. Menon, R.; Buehrer, R.M.; Reed, J.H. On the Impact of Dynamic Spectrum Sharing Techniques on Legacy Radio Systems. *IEEE Trans. Wirel. Commun.* **2008**, *7*, 4198–4207. [CrossRef]
49. Zhang, Y.; Yu, R.; Nekovee, M.; Liu, Y.; Xie, S.; Gjessing, S. Cognitive Machine-to-Machine Communications: Visions and Potentials for the Smart Grid. *IEEE Netw.* **2012**, *26*, 6–13. [CrossRef]
50. Aijaz, A.; Aghvami, A.H. Cognitive Machine-To-Machine Communications for Internet-of-Things: A Protocol Stack Perspective. *IEEE Internet Things J.* **2015**, *2*, 103–112. [CrossRef]
51. Li, R.; Lu, B.; McDonald-Maier, K.D. Cognitive Assisted Living Ambient System: A Survey. *Digit. Commun. Netw.* **2015**, *1*, 229–252. [CrossRef]
52. Andrews, J.G.; Buzzi, S.; Choi, W.; Hanly, S.V.; Lazano, A.; Soong, A.C.K.; Zhang, J.C. What Will 5G Be? *IEEE J. Sel. Areas Commun.* **2014**, *32*, 1065–1082. [CrossRef]
53. Samsung Electronics. 5G Vision, Version 2. Available online: http://www.samsung.com/global/business-images/insights/2015/Samsung-5G-Vision-0.pdf (accessed on 10 July 2017).
54. Iscan, O.; Lentner, D.; Xu, W. A Comparison of Channel Coding Schemes for 5G Short Message Transmission. In Proceedings of the IEEE Globecom Workshops (GC Wkshps), Washington, DC, USA, 4–8 December 2016.
55. Sabharwal, A.; Schniter, P.; Guo, D.; Bliss, D.W.; Rangarajan, S.; Wichman, R. In-Band Full-Duplex Wireless: Challenges and Opportunities. *IEEE J. Sel. Areas Commun.* **2014**, *32*, 1637–1652. [CrossRef]
56. Ding, Z.; Liu, Y.; Choi, J.; Sun, Q.; Elkashlan, M.; Chin-Lin, I.; Vincent Poor, H. Application of Non-Orthogonal Multiple Access in LTE and 5G Networks. *IEEE Commun. Mag.* **2006**, *55*, 185–191. [CrossRef]
57. Lei, W. Non-Orthogonal Multiple Access Schemes for Future Cellular Systems. Ph.D. Thesis, University of Surrey, Surrey, UK, 17 May 2017.
58. Farhang-Boroujeny, B. OFDM Versus Filter Bank Multicarrier. *Signal Process. Mag.* **2011**, *28*, 92–112. [CrossRef]
59. Bellanger, M. FS-FBMC: An Alternative Scheme for Filter Bank Multicarrier Transmission. In Proceedings of the 2012 5th International Symposium on Communications Control and Signal Processing, Rome, Italy, 2–4 May 2012.
60. Cai, X.; Qin, Z.; Cui, F.; Li, G.Y.; McCann, J.A. Modulation and Multiple Access for 5G Network. Available online: https://arxiv.org/pdf/1702.07673.pdf (accessed on 10 July 2017).
61. Wang, L.; Sasoglu, E.; Kim, Y.H. Filtered OFDM: Sliding-Window Superposition Coding for Interference Networks. In Proceedings of the International Symposium Information Theory, Honolulu, HI, USA, 29 June–4 July 2014.
62. Wang, L. Channel Coding Technique for Network Communication. Ph.D. Thesis, University of California, San Diego, CA, USA, December 2015.
63. Cover, T.M. Broadcast Channels. *IEEE Trans. Inf. Theory* **1972**, *18*, 2–14. [CrossRef]
64. Liao, H.H.J. Multiple Access Channels. Ph.D. Thesis, University of Hawaii, Honolulu, HI, USA, September 1972.
65. Kramer, G.; Gastpar, M.; Gupta, P. Cooperative Strategies and Capacity Theorems for Relay Networks. *IEEE Trans. Inf. Theory* **2005**, *51*, 3037–3063. [CrossRef]

66. Bhushan, N.; Li, J.; Malladi, D.; Gilmore, R.; Brenner, D.; Damnjanovic, A.; Sukhavasi, R.; Patel, C.; Geirhofer, S. Network Densification: The Dominant Theme for Wireless Evolution into 5G. *IEEE Commun. Mag.* **2014**, *52*, 82–89. [CrossRef]
67. Chin, W.H.; Fan, Z.; Haines, R. Emerging Technologies and Research Challenges for 5G Wireless Networks. *IEEE Wirel. Commun.* **2014**, *21*, 106–112. [CrossRef]
68. Biral, A.; Centenaro, M.; Zanellan, A. The Challenges of M2M Massive Access in Wireless Cellular Networks. *Digit. Commun. Netw.* **2015**, *1*, 1–19. [CrossRef]
69. Barreto, A.N.; Faria, B.; Almeida, E.; Rodriguez, I.; Lauridsen, M.; Amorim, R.; Vieira, R. 5G-Wireless Communications for 2020. *J. Commun. Inf. Syst.* **2016**, *31*, 146–163. [CrossRef]
70. Wang, N.; Hossain, E.; Bhargava, V.K. Backhauling 5G Small Cells: A Radio Resource Management Perspective. *IEEE Wirel. Commun.* **2015**, *22*, 41–49. [CrossRef]
71. Chen, L.; Huang, Y.; Xie, F.; Gao, Y.; Chu, H.; Li, Y.; Liang, F.; Yuan, Y. Mobile Relay in LTE-Advanced Systems. *IEEE Commun. Mag.* **2013**, *51*, 144–151. [CrossRef]
72. Svensson, T. Moving Cells/Networks. Available online: http://snow.itn.liu.se/asbtr/SNOWTommySvensson.pdf (accessed on 11 July 2017).
73. Zheng, K.; Leung, V.C.M.; Yang, L.L.; Chatzimisios, P. Guest Editorial Special Issue on 5G Wireless Systems with Massive MIMO. *IEEE Syst. J.* **2017**, *11*. [CrossRef]
74. Ge, X.; Cheng, H.; Guizani, M.; Han, T. 5G Wireless Backhaul Networks: Challenges and Research Advances. *IEEE Netw.* **2014**, *28*, 6–11. [CrossRef]
75. Liu, J.; Kato, N.; Ma, J.; Kadowaki, N. Device-to-Device Communication in LTE-Advanced Networks: A Survey. *IEEE Commun. Surv. Tutor.* **2014**, *17*, 1923–1940. [CrossRef]
76. Pérez-Romero, J.; Sallent, O.; Agusti, R. Enhancing Cellular Coverage through Opportunistic Networks with Learning Mechanisms. In Proceedings of the IEEE Global Telecommunication Conference, Atlanta, GA, USA, 9–13 December 2013.
77. Asadi, A.; Wang, Q.; Mancuso, V. A Survey on Device-to-Device Communication in Cellular Networks. *IEEE Commun. Surv. Tutor.* **2014**, *16*, 1801–1819. [CrossRef]
78. Chen, T.; Kunnari, E.; Tapani, R. Device-to-Device Communication for LTE-Advanced Network System. Available online: https://tel.archives-ouvertes.fr/tel-00983507/document (accessed on 10 July 2017).
79. Hicham, M.; Abghour, N.; Ouzzif, M. Device-to-Device (D2D) Communication under LTE-Advanced Networks. *Int. J. Wirel. Mob. Netw.* **2016**, *8*, 11–22. [CrossRef]
80. Noura, M.; Nordin, R. A Survey on Interface for Device-to-Device (D2D) Communication and its Challenges in 5G Networks. *J. Netw. Comput. Appl.* **2016**. [CrossRef]
81. Mozaffari, M.; Saad, W.; Bennis, M.; Debbah, M. Mobile Unmanned Aerial Vehicles (UAVs) for Energy-Efficient Internet of Things Communications. Unpublished work, 2017.
82. Hayat, S.; Yanmaz, E.; Muzaffar, R. Survey on Unmanned Aerial Vehicle Networks for Civil Applications: A Communications Viewpoint. *IEEE Commun. Surv. Tutor.* **2016**, *18*, 2624–2661. [CrossRef]
83. Larsson, E.G.; Edfors, O.; Tufvesson, F.; Marzetta, T.L. A Massive MIMO for Next Generation Wireless Systems. *IEEE Commun. Mag.* **2016**, *52*, 186–195. [CrossRef]
84. Jovanovic, A.; Li, J.; Richardson, T. Visible light Communication: Opportunities, Challenges and the Path to Market. *IEEE Commun. Mag.* **2013**, *51*, 130–135. [CrossRef]
85. Popovicki, G.; Lauridsen, M.; Soret, B.; Pedersen, K.I.; Mogensen, P. Automation for on-Road Vehicles: Use Cases and Requirements for Radio Design. In Proceedings of the IEEE 82nd Vehicular Technology Conference (VTC Fall), Boston, MA, USA, 6–9 September 2015.
86. Abboud, K.; Omar, H.A.; Zhuang, W. Interworking of DSRC and Cellular Network Technologies for V2X Communications: A Survey. *IEEE Trans. Veh. Technol.* **2016**, *65*, 9457–9470. [CrossRef]
87. Zheng, K.; Zhao, L.; Mei, J.; Dohler, M.; Xiang, W.; Peng, Y. 10 Gb/s HetSNets with Millimeter-Wave Communications: Access and Networking-Challenges and Protocols. *IEEE Commun. Mag.* **2015**, *53*, 222–231. [CrossRef]
88. Jaber, M.; Imran, M.A.; Tafazolli, R.; Tukmanov, A. 5G Backhaul Challendes and Emerging Research Direction: A Survey. *IEEE Access* **2014**, *4*, 1743–1766. [CrossRef]
89. Abdul Salam, S.; Mahmud, S.A.; Khan, G.M.; Raweshidy, H.S. M2M Communication in Smart Grids: Implementation Scenarios and Performance Analysis. In Proceedings of the 2012 IEEE Wireless Communications and Networking Conference Workshops (WCNCW), Paris, France, 1 April 2012.

90. 3GPP. Technical Specification Group Services and System Aspects (Release 8). Available online: http://www.arib.or.jp/IMT-2000/V720Mar09/5_Appendix/Rel8/23/23521-800.pdf (accessed on 10 July 2017).
91. Ratasuk, R.; Tan, J.; Ghosh, A. Coverage and capacity analysis for machine type communications in LTE. In Proceedings of the IEEE 75th Vehicular Technology Conference (VTC Spring), Yokohama, Japan, 6–9 May 2012.
92. Wu, G.; Talwar, S.; Johnsson, K.; Himayat, N.; Johnson, K.D. M2M: From Mobile to Embedded Internet. *IEEE Commun. Mag.* **2011**, *49*, 36–43. [CrossRef]
93. Chen, M.; Wan, J.; Li, F. Machine-To-Machine Communications: Architectures, Standards and Applications. *KSII Trans. Internet Inf. Syst.* **2012**, *6*, 480–497. [CrossRef]
94. Marjanovic, M.; Skorin-Kapov, L.; Pripužić, K.; Antonić, A.; Podnar Žarko, I. Energy-Aware and Quality-Driven Sensor Management For Green Mobile Crowd Sensing. *J. Netw. Comput. Appl. Arch.* **2015**, *59*, 96–108. [CrossRef]
95. 5GPPP. View on 5G Architecture. Available online: https://5g-ppp.eu/wp-content/uploads/2014/02/5G-PPP-5G-Architecture-WP-For-public-consultation.pdf (accessed on 10 July 2017).
96. 5GPP. 5G Empowering Vertical Industries. Available online: https://5g-ppp.eu/wp-content/uploads/2016/02/BROCHURE_5PPP_BAT2_PL.pdf (accessed on 10 July 2017).
97. 4G Americas. Cellular Technologies Enabling the Internet of Things. Available online: http://www.5gamericas.org/files/6014/4683/4670/4G_Americas_Cellular_Technologies_Enabling_the_IoT_White_Paper_-_November_2015.pdf (accessed on 10 July 2017).
98. Carlesso, M.; Antonopoilos, A.; Granelli, F.; Verikoukis, C. Uplink Scheduling form Smart Metering and Real-Time Traffic Coexistence in LTE Networks. In Proceedings of the International Conference on Communications (ICC), London, UK, 8–12 June 2015; pp. 820–825.
99. Islam, R.; Avazov, N.; Dobre, O.A.; Kwak, K.S. Power-Domain Non-Orthogonal Multiple Access (NOMA) in 5G Systems: Potentials and Challenges. *IEEE Commun. Surv. Tutor.* **2016**, *19*, 721–742. [CrossRef]
100. Liu, Y.; Zhang, Y.; Yu, R.; Xie, R. Integrated Energy and Spectrum Harvesting for 5G Wireless Communications. *IEEE Netw.* **2015**, *29*, 75–81. [CrossRef]
101. Kong, L.; Khan, M.K.; Wu, F.; Chen, G.; Zeng, P. Millimeter-Wave Wireless Communications for IoT-Cloud Supported Autonomous Vehicles: Overview, Design, and Challenges. *IEEE Commun. Mag.* **2017**, *55*, 62–68. [CrossRef]
102. Costa-Perez, X.; Garcia-Saavedra, A.; Li, X.; de la Oliva, A.; Iovanna, P.; Deiß, T.; di Giglio, A.; Mourad, A. 5G-Crosshaul: An SDN/NFV Integrated Fronthaul/Backhaul Transport Network Architecture. *IEEE Wirel. Commun.* **2017**, *24*, 38–45. [CrossRef]
103. Trivisonno, R.; Guerzoni, R.; Vaishnavi, I.; Soldani, D. Towards Zero Latency Software Defined 5G Networks. In Proceedings of the IEEE International Conference on Communication Workshop (ICCW), London, UK, 8–12 June 2015.
104. Esaki, H.; Nakamura, R. Overlaying and Slicing for Iot Era Based on Internet's End-To-End Discipline. In Proceedings of the IEEE International Symposium on Local and Metropolitan Area Networks (LANMAN), Osaka, Japan, 12–14 June 2017.
105. 5GPP. 5G and Media & Entertainment. Available online: https://5g-ppp.eu/wp-content/uploads/2016/02/5G-PPP-White-Paper-on-Media-Entertainment-Vertical-Sector.pdf (accessed on 10 July 2017).
106. GSA. The Road to 5G: Frivers, Applications, Requirements and Technical Development. Available online: http://www.huawei.com/minisite/5g/img/GSA_the_Road_to_5G.pdf (accessed on 10 July 2017).
107. Erman, B.; Yiu, S. Modeling 5G Wireless Network Service Reliability Prediction with Bayesian Network. In Proceedings of the 2016 IEEE International Workshop Technical Committee on Communications Quality and Reliability, Stevenson, WA, USA, 10–12 May 2016.
108. NOKIA. 5G Use Cases and Requirements White Paper. Available online: https://www.ngmn.org/fileadmin/ngmn/content/downloads/Technical/2015/NGMN_5G_White_Paper_V1_0.pdf (accessed on 10 July 2017).
109. Motlagh, N.H.; Bagaa, M.; Taleb, T.; Song, J. Connection Steering Mechanism between Mobile Networks for Reliable UAV's Iot Platform. In Proceedings of the IEEE International Conference on Communications (ICC), Paris, France, 21–25 July 2017.
110. Kaltenberger, F.; Knopp, R.; Vitiello, C.; Danneberg, M.; Festag, A. Experimental Anaysis of 5G Candidate Waveform and Their Coexistence with 4G Systems. In Proceedings of the Joint NEWCOM/COST Workshop on Wireless Communications JNCW, Barcelona, Spain, 14–15 October 2016.

111. Serra, J.; Pubill, D.; Antonopoulos, A.; Verikoukis, C. Smart HVAC Control in IoT: Energy Consumption Minimization with User Comfort Constraints. *Sci. World J.* **2014**, *2014*. [CrossRef] [PubMed]
112. Nikolich, P.; Lin, C.; Korhonen, J.; Marks, R.; Tye, B.; Li, G.; Ni, J.; Zhang, S. Standards for 5G and Beyond: Their Use Cases and Applications. *IEEE 5G Tech Focus* **2017**, *1*. Available online: https://5g.ieee.org/tech-focus/june-2017/standards-for-5g-and-beyond (accessed on 9 September 2017).
113. Kusume, K.; Fallgren, M.; Queseth, O.; Braun, V.; Gozalvez-Serrano, D.; Korthals, I.; Zimmermann, G.; Schubert, M.; Hossain, M.I.; Widaa, A.A.; et al. Updated Scenarios, Requirements and KPIs for 5G Mobile and Wireless System with Recommendations for Future Investigations. METIS_D1.5_v1. METIS. Available online: https://www.metis2020.com/wp-content/uploads/deliverables/METIS_D1.5_v1.pdf (accessed on 10 July 2017).
114. 5GPP. 5G Vision and Requirements. Available online: https://5g-ppp.eu/imt-2020-5g-promotion-group-and-5g-ppp-announce-memorandum-of-understanding-for-5g/ (accessed on 10 July 2017).
115. Yang, C.; Li, J. *Interference Mitigation and Energy Management in 5G Heterogeneous Cellular Networks*; ICI Global: Harshey, PA, USA, 2017; pp. 1–362.
116. Ericsson. 5G Energy Performance. Available online: http://www.5gamericas.org/files/3114/3898/7332/Ericsson_wp-5g-energy-performance.pdf (accessed on 10 July 2017).
117. Shen, K.; Yu, W. Distributed Pricing-Based User Association for Downlink Hterogeneous Cellular Networks. *IEEE J. Sel. Areas Commun.* **2014**, *32*, 1100–1113. [CrossRef]
118. Nguyen, H.V.; Le, L.B. Distributed Base Station Association and Power Control for Heterogeneous Cellular Networks. *IEEE Trans. Veh. Technol.* **2014**, *63*, 282–296. [CrossRef]
119. Singh, S.; Andrews, J.G. Joint Resource Portitioning and Offloading in Heterogeneous Cellular Networks. *IEEE Trans. Wirel. Commun.* **2014**, *13*, 888–901. [CrossRef]
120. Elsawy, H.; Hossain, E.; Kim, D.I. HetNets with Cognitive Small Cells: User Offloading and Distributed Channel Access Technique. *IEEE Commun. Mag.* **2013**, *51*, 28–36. [CrossRef]
121. Ji, Z.; Li, K. Cognitive Radios for Dynamic Spectrum Access-Dynamic Spectrum Sharing: A Game Theoretical Overview. *IEEE Commun. Mag.* **2007**, *45*, 88–94. [CrossRef]
122. Aijazand, A.; Aghvami, A.H. PRMA-Based Cognitive Machine-to-Machine Communications in Smart Grid Networks. *IEEE Trans. Veh. Technol.* **2015**, *64*, 3608–3623. [CrossRef]
123. Okasaka, S.; Weiler, R.J.; Keusgen, W.; Pudeyev, A.; Maltsev, A.; Karls, I.; Sakaguchi, K. Proof-of-Concept of a Millimeter-Wave Integrated Heterogeneous Network for 5G Cellular. *Sensors* **2016**, *9*. [CrossRef] [PubMed]
124. Qi, S.; Tesanovic, M. FQAM-FBMC Design and Its Application to Machine Type Communication. In Proceedings of the IEEE 27th Annual International Symposium on PIMRC, Valencia, Spain, 4–8 September 2016.
125. Domouchtsidis, S.G.; Ntouni, G.D.; Kapinas, V.M.; Karagiannidis, G.K. OFDM-IM vs. FQAM: A Comparative Analysis. In Proceedings of the International Conference on Telecommunications, Thessaloniki, Greece, 16–18 May 2016.
126. Hong, S.; Sagong, M.; Lim, C.V.; Cheun, K.; Cho, S. FQAM: A Modulation Scheme for Beyond 4G Cellular Wireless Communication Systems. In Proceedings of the IEEE GC Wkshps, Atlanta, GA, USA, 9–13 December 2013.
127. Perlman, S.; Forenza, A. pCell Wireless Reinvented. Arthemis Networks. Available online: http://www.rearden.com/DIDO/DIDO_White_Paper_110727.pdf (accessed on 10 July 2017).
128. Mesleh, R.Y.; Hass, H.; Sinanovic, S.; Ahn, C.W.; Yun, S. Spatial Modulation. *IEEE Trans. Veh. Technol.* **2008**, *57*, 2228–2241. [CrossRef]
129. Maunder, R.G. The 5G Channel Code Contenders. Available online: https://www.accelercomm.com/sites/accelercomm.com/files/WhitePaper09Aug2016.pdf (accessed on 10 July 2017).
130. Scholl, S.; Weithoffer, S.; When, N. Advanced Iterative Channel Coding Schemes: When Shannon meets Moore. In Proceedings of the 9th International Symposium on Turbo Codes & Iterative Information, Brest, France, 5–9 September 2016.
131. Korpi, D.; Tamminen, J.; Tarunen, M.; Huusari, T.; Choi, Y.-S.; Anttila, L.; Talwar, S.; Valkama, M. Full-Duplex Mobile Device: Pushing the Limit's. *IEEE Commun. Mag.* **2016**, *54*, 80–87. [CrossRef]
132. Hong, S.S.; Brand, J.; Choi, J.I.; Jain, M.; Mehl, J. Applications of Self-Interference Cancellation in 5G and Beyond. *IEEE Commun. Mag.* **2014**, *52*, 114–121. [CrossRef]

133. Duarte, M.; Dick, C.; Sabharwal, A. Experiment-Driven Characterization of Full-Duplex Wireless Systems. *IEEE Trans. Wirel. Commun.* **2012**, *11*, 4296–4307. [CrossRef]
134. Bharadia, D.; McMilin, E.; Katti, S. Full Duplex Radios. In Proceedings of the ACM SIGCOMM 2013 conference on SIGCOMM, Hong Kong, China, 12–16 August 2013.
135. Čelik, H.; Sung, K.W. On the Feasibility of Blind Dynamic TDD in Ultra-Dense Wireless Networks. In Proceedings of the 2015 IEEE 81st VehicularTechnology Conference (VTC Spring), Glasgow, UK, 11–14 May 2015.
136. Osti, P.; Aalto, S.; Lassila, P. Flow-Level Modeling and Optimization of Intercell Coordination with Dynamic TDD. In Proceedings of the 10th ACM symposium on QoS and security for wireless and mobile networks Q2SWinet '14, Montreal, QC, Canada, 21–26 September 2014.
137. Kerttula, J.; Marttinen, A.; Ruttik, K.; Jäntti, R.; Alam, N. Dynamic TDD on LTE Small Cells. *EURASIP J. Wirel. Commun. Netw.* **2016**, *194*. [CrossRef]
138. Gupta, A.K.; Kulkarni, M.N.; Visotsky, E.; Vook, F.W.; Ghosh, A.; Andrews, J.G.; Heath, R.W. Rate Analysis and Feasibility of Dynamic TDD in 5G Cellular Systems. In Proceedings of the 2016 IEEE International Conference on Communications, Cuala Lumpur, Malaysia, 22–27 May 2016.
139. Sun, H.; Wildemeersch, M.; Sheng, M.; Quek, T.K. D2D Enchanced Heterogeneus Cellular Networks with Dynamic TDD. *IEEE Trans. Wirel. Commun.* **2015**, *14*, 4204–4218. [CrossRef]
140. Sun, H.; Wildemeersch, M.; Sheng, M.; Quek, T.K.; Li, J. Traffic Adaptation and Energy Efficiency for Small Cell Networks with Dynamic TDD. *IEEE J. Sel. Areas Commun.* **2016**, *34*, 3234–3251. [CrossRef]
141. Čelik, H.; Song, K.W. Joint Transmission with Dummy Symbols for Dynamic TDD in Ultra-Dense Deployment. Available online: https://aps.arxiv.org/abs/1702.06045 (accessed on 10 July 2017).
142. Li, J.; Farahvash, S.; Kavehrad, M.; Valenzuel, R. Dynamic TDD and Fixed Cellular Networks. *IEEE Commun. Lett.* **2002**, *4*, 218–220. [CrossRef]
143. Shen, Z.; Khoryae, A.; Eriksson, E.; Pan, X. Dynamic Uplink-Downlink Configuration and Interference Management in TD-LTE. *IEEE Commun. Mag.* **2012**, *50*, 51–59. [CrossRef]
144. Chunlin, Y.; Zhifeng, Y.; Weimin, L.; Yifei, Y. Non-Orthogonal Multiple Access Schemes for 5G. *ZTE Commun.* **2016**, *14*, 11–16. [CrossRef]
145. 3GPP. Discussion on Multiple Access for Radio Interface. Available online: http://www.3gpp.org/DynaReport/TDocExMtg--R1-84b--31661.htm (accessed on 10 July 2017).
146. Yuan, Z.; Yu, G.; Li, W.; Yuan, Y.; Wang, X.; Xu, J. Multi-user Shared Access for Internet of Things. In Proceedings of the 2016 IEEE 83rd Vehicular Technology Conference (VTC Spring), Nanjing, China, 15–18 May 2016.
147. 3GPP. Receiver Implementation for MUSA. 3GPP. Available online: http://www.3gpp.org/DynaReport/TDocExMtg--R1-85--31662.htm (accessed on 10 July 2017).
148. 3GPP. Contetion-Based Non-Orthogonal Multiple Access for UL mMTC. Available online: http://www.3gpp.org/DynaReport/TDocExMtg--R1-85--31662.htm (accessed on 10 July 2017).
149. 3GPP. Resource Spread Multiple Access. Available online: http://www.3gpp.org/ftp/tsg_ran/WG1_RL1/TSGR1_85/Docs/ (accessed on 10 July 2017).
150. Taherzadeh, M.; Nikopour, H.; Bayesteh, A.; Baligh, H. SCMA Codebook Design. In Proceedings of the IEEE International Symposium on Personal, Indoor And Mobile Radio Communications, London, UK, 14–17 September 2014.
151. Nikopour, H.; Baligh, H. Sparse Code Multiple Acccess. In Proceedings of the 2014 IEEE 80th Vehicular Technology Conference, Vancouver, BC, Canada, 14–17 September 2014.
152. Future Mobile Communication Forum. 5G Whitepaper v2.0, Part d-Alternative Multiple Access v1. Available online: http://www.future-forum.org/dl/151106/whitepaper.rar (accessed on 10 July 2017).
153. 3GPP. Candidate Solution for New Multiple Access. 3GPP. Available online: http://portal.3gpp.org/ngppapp/CreateTdoc.aspx?mode=view&contributionId=697587 (accessed on 10 July 2017).
154. Dai, X.; Chen, S.; Sun, S.; Kang, S.; Wang, Y.; Shen, Z.; Xu, Z. Successive Interference Cancelation Amenable Multiple Access (SAMA) for Future Wireless Communications. In Proceedings of the IEEE International Conference on Communication Systems, Macau, China, 19–21 November 2014.
155. Dai, X. Successive Interference Cancellation Amenable Space-Time Codes with Good Multiplexing-Diversity Tradeoff. *Wirel. Pers. Commun.* **2010**, *55*, 645–654. [CrossRef]

156. Li, P.; Liu, L.; Wu, K.; Leung, W.K. On Interleave-Division Multiple-Access. In Proceedings of the 2017 IEEE International Conference on Communications (ICC), Paris, France, 21–25 May 2017.
157. Li, P.; Liu, L.; Wu, K.; Leung, W.K. Interleave Division Multiple-Access. *IEEE Trans. Wirel. Commun.* **2006**, *5*, 938–947. [CrossRef]
158. Rabee, F.A.; Dayaslioglu, K.; Gitlin, R. The Optimum Received Power Levels of Uplink Non-Orthogonal Multiple Access (NOMA) Signals. In Proceedings of the 2017 IEEE 18th Wireless and Microwave Technology Conference (WAMICON), Cocoa Beach, FL, USA, 24–25 April 2017.
159. Saito, Y.; Kishiyama, Y.; Benjebbour, A.; Nakamura, T.; Li, A.; Higuchi, K. Non-orthogonal Multiple Access (NOMA) for Cellular Future Radio Access. In Proceedings of the 77th IEEE Vehicular Technology Conference, Dresden, Germany, 2–5 June 2013.
160. Choi, J. On Multiple Access Using H-ARQ with SIC Techniques for Wireless Ad Hoc Networks. *Wirel. Pers. Commun.* **2013**, *69*, 187–212. [CrossRef]
161. Choi, J. Non-orthogonal Multiple Access in Downlink Coordinated Two-point Systems. *IEEE Commun. Lett.* **2014**, *18*, 313–316. [CrossRef]
162. Sedtheetorn, P.; Chulajata, T. Accurate Spectral Efficiency Analysis for Non Orthogonal Multiple Access. *Trans. Adv. Commun. Technol.* **2016**, *5*, 844–850.
163. Wild, T.; Schaich, F.; Chen, Y. 5G Air Interface Design Based on Universal Filtered (UF-) OFDM. In Proceedings of the 19th International Conference in DSP, Hong Kong, China, 20–23 August 2014.
164. Ding, Z.; Yang, Z.; Fan, P.; Poor, H.V. On the Performance of Non-orthogonal Multiple Access in 5G Systems with Randomly Deployed Users. *IEEE Signal Process. Lett.* **2014**, *21*, 1501–1505. [CrossRef]
165. Zhao, Z.; Schellmann, M.; Wang, Q.; Gong, X.; Boehnke, R.; Xu, W. Pulse shaped OFDM for Asynchronous Uplink Access. In Proceedings of the Asilomar Conference Signals, Systems and Computers, Pacific Grove, CA, USA, 8–11 November 2015.
166. Cover, T.M.; El Gamel, A. Capacity Theorems for The Relay Channel. *IEEE Trans. Inf. Theory* **1979**, *25*, 572–584. [CrossRef]
167. Cover, T.M.; Leung, C.S.K. An Achievable Rate Region for the Multiple-access Channel with Feedback. *IEEE Trans. Inf. Theory* **1981**, *27*, 292–298. [CrossRef]
168. Ahlswede, R. Multiway Communication Channels. In Proceedings of the 2nd International Symposium on Information Theory, Tsahkadsor, Armenian SSR, 2–8 September 1971.
169. Xie, L.L.; Kumar, P.R. An Achievable Rate for the Multiple-level Relay Channel. *IEEE Trans. Inf. Theory* **2005**, *51*, 1348–1358. [CrossRef]
170. Kim, K.T.; Ahn, S.-K.; Kim, Y.-H.; Park, H.; Wang, L.; Chen, C.-Y.; Park, J. Adaptive Sliding-Window Coded Modulation in Cellular Networks. In Proceedings of the IEEE GLOBECOM, San Diego, CA, USA, 6–10 December 2015.
171. Thurfjell, M.; Ericsson, M.; de Bruin, P. Network Densification Impact on System Capacity. In Proceedings of the 2015 IEEE 81st Vehicular Technology Conference, Glasgow, Scotland, 11–14 May 2015.
172. Darwish, A.; Ibrahim, A.S. Capacity Improvements via Indoor Small Cells. In Proceedings of the 2014 International Wireless Communications and Mobile Computing Conference (IWCMC), Nicosia, Cyprus, 4–8 August 2014.
173. Hoadley, J.; Maveddat, P. Enabling Small Cell Deployment with Hetnet. *IEEE Wirel. Commun.* **2012**, *19*, 4–5. [CrossRef]
174. Hughes, M.; Jovanovic, V.M. Small Cells-Effective Capacity Relief Option for Heterogeneous Networks. In Proceedings of the 2012 IEEE Vehicular Technology Conference, Quebec City, QC, Canada, 3–6 September 2012.
175. Sui, Y.; Guvenc, I.; Svensson, T. Interference Management for Moving Networks in Ultra-Dense Urban Scenarios. *EURASIP J. Wirel. Commun. Netw.* **2015**, *111*. [CrossRef]
176. Sui, Y.; Vihrälä, J.; Papadogiannis, A.; Sternad, M.; Svensson, T. Moving Cells: A Promising Solution to Boost Performance for Vehicular Users. *IEEE Commun. Mag.* **2013**, *51*, 62–68. [CrossRef]
177. Sambo, Y.A.; Shakir, M.Z.; Héliot, F.; Imran, M.A.; Mumtaz, S.; Qaraqe, K.A. Device-to-Device Communication in Heterogeneous Networks. In *Smart Device to Smart Device Communication*; Mumtaz, S., Rodriguez, J., Eds.; Springer International Publishing: Cham, Switzerland, 2014; pp. 219–235.
178. Liu, X.; Andrews, J.G.; Ghosh, A. Spectrum Sharing for Device- to-Device Communication in Cellular Networks. *IEEE Trans. Wirel. Commun.* **2014**, *13*, 6272–6740. [CrossRef]

179. Zafar, B.; Gherekhloo, S.; Haardt, M. Analysis of Multihop Relaying Networks: Communication Between Range-Limited and Cooperative Nodes. *IEEE Veh. Technol. Mag.* **2012**, *7*, 40–47. [CrossRef]
180. Kamalinejad, P.; Mahapatra, C.; Sheng, Z.; Mirabbasi, S.; Leung, V.C.M.; Guan, Y.L. Wireless Energy Harvesting for the Internet of Things. *IEEE Commun. Mag.* **2015**, *53*, 102–108. [CrossRef]
181. Mekikis, P.-V.; Antonopoulos, A.; Kartsakli, E.; Lalos, A.S.; Alonso, L.; Verikoukis, C. Information Exchange in Randomly Deploys Dense WSNs with Wireless Energy Harvesting Capabilities. *IEEE Trans. Wirel. Commun.* **2016**, *15*, 3008–3018. [CrossRef]
182. Mekikis, P.-V.; Antonopoulos, A.; Alonso, L.; Verikoukis, C. Stochastic Modeling of Wireless Charged Wearables for Reliable Health Monitoring In Hospital Environments. In Proceedings of the International Conference on Communications (ICC), Paris, France, 21–25 May 2017.
183. Li, Y.; Cai, L. UAV-Assisted Dynamic Coverage in a Heterogeneous Cellular System. *IEEE Netw.* **2017**, *31*, 56–61. [CrossRef]
184. Messous, M.-A.; Senouci, S.-M.; Sedjelmaci, H. Network Connectivity and Area Coverage for UAV Fleet Mobility Model with Energy Constraint. In Proceedings of the Wireless Communications and Networking Conference (WCNC), Doha, Qatar, 3–6 April 2016.
185. Mekikis, P.-V.; Kartsakli, E.; Alonso, L.; Verikoukis, C. Flexible Aerial Relay Nodes for Communication Recovery and D2D Relaying. In Proceedings of the IEEE 5th Global Conference on Consumer Electronics, Kyoto, Japan, 11–14 October 2016.
186. Zeng, Y.; Zhang, R.; Lim, T.J. Wireless Communications with Unmanned Aerial Vehicles: Opportunities and Challenges. *IEEE Commun. Mag.* **2016**, *54*, 36–42. [CrossRef]
187. Yang, X.; Lu, W.-J.; Wang, N.; Nieman, K.; Jin, S.; Zhu, H.; Mu, X.; Wong, I.; Huang, Y.; You, X. Design and Implementation of a TDD-Based 128-Antenna Massive MIMO Prototyping System. Available online: http://adsabs.harvard.edu/cgi-bin/bib_query?arXiv:1608.07362 (accessed on 11 July 2017).
188. Chen, B.; Zhu, C.; Shu, L.; Su, M.; Wei, J.; Leung, V.C.M.; Rodriques, J.J.P.C. Uplink Transmission for Lightweight Single-antenna UEs in the Presence of a Massive MIMO eavesdropper. *IEEE Access* **2016**, *99*, 2169–3536. [CrossRef]
189. Wu, S.; Wang, H.; Youn, C.H. Visible Light Communications for 5G Wireless Networking Systems: From Fixed to Mobile. *IEEE Access* **2014**, *28*, 41–45. [CrossRef]
190. Feng, L.; Hu, R.Q.; Wang, J.; Xu, P.; Qian, Y. Applying VLC in 5G Networks: Architectures and Key Technologies. *IEEE Access* **2016**, *30*, 77–83. [CrossRef]
191. Grobe, L.; Paraskevopoulos, A.; Hilt, J.; Schulz, D.; Lassak, F.; Hartlieb, F.; Kottke, C.; Jungnickel, V.; Langer, K.-D. High-Speed Visible Light Communication Systems. *IEEE Commun. Mag.* **2013**, *51*, 60–66. [CrossRef]
192. Li, X.; Zhang, R.; Wang, J.; Hanzo, L. Cell-Centric and User-Centric Multi-User Scheduling in Visible Light Communication Aided Networks. In Proceedings of the IEEE International Conference on Communications (ICC), London, UK, 8–12 June 2015.
193. Katriniok, A.; Kleibaum, P.; Res, C.; Eckstein, L. Automation of Road Vehicles Using V2X: An Application to Intersection Automation. Available online: http://papers.sae.org/2017-01-0078/ (accessed on 10 July 2017).
194. Ghods, A.; Severi, S.; Abreu, G. Localization in V2X Communication Networks. In Proceedings of the IEEE Intelligent Vehicles Symposium, Gothenburg, Sweden, 19–22 June 2016.
195. Goebel, N.; Bialon, R.; Mauve, M.; Graffi, K. Coupled Simulation of Mobile Cellular Networks, Road Traffic and V2X Applications Using Traces. In Proceedings of the International Conference on Communications, Kuala Lumpur, Malaysia, 22–27 May 2016.
196. Xiao, Z.; Liu, H.; Havyarimana, V.; Li, T.; Wang, D. Analytical Study on Multi-Tier 5G Heterogeneous Small Cell Networks: Coverage Performance and Energy Efficiency. *Sensors* **2016**, *11*. [CrossRef] [PubMed]
197. Choi, J.I.; Jain, M.; Srinivasan, K.; Levis, P.; Katti, S. Achieving Single Channel, Full Duplex Wireless Communication. In Proceedings of the sixteenth annual international conference on Mobile computing and networking, Chicago, IL, USA, 20–24 September 2010.
198. Song, Q.; Nuaymi, L.; Lagrange, X. Survey of Radio Resource Management Issues and Proposals for Energy-Efficient Cellular Network That Will Cover Billions of Machines. *Wirel. Commun. Netw.* **2016**, *140*. [CrossRef]

199. Costa, G.; Miao, G. Context-Aware Machine-To-Machine Communications. In Proceedings of the 33rd Annual IEEE International Conference on Computer Communications (INFOCOM WKSHPS), Toronto, ON, Canada, 27 April–2 May 2014.
200. Agyapong, P.K.; Iwamura, M.; Staehle, D.; Kiess, W.; Benjebbour, A. Design Considerations for a 5G Network Architecture. *IEEE Commun. Mag.* **2014**, *52*, 65–75. [CrossRef]
201. Vermesan, O.; Friass, P.; Guillemin, P.; Giaffreda, R.; Grindvoll, H.; Eisenhauer, M.; Serrano, M.; Moessner, K.; Spirito, M.; Blystad, L.-C.; et al. *Building the Hypercconnected Society—IoT Research and Innovation Value Chains, Ecosystems and Markets*; Vermesan, O., Friass, P., Eds.; River Publishers: Aalborg, Denmark, 2015; Volume 43.
202. Panwar, N.; Sharma, S.; Singh, A.K. A Survey on 5G: The Next Generation of Mobile Communication. *Elsevier Phys. Commun.* **2016**, *18*, 64–84. [CrossRef]
203. Thuemmler, C.; Gavrasm, A.; Jumelle, A.K.L.; Paulin, A.; Sadique, A.; Schneider, A.; Fedell, C.; Abraham, D.; Trossen, D. 5G and e-Health. Available online: https://5g-ppp.eu/wp-content/uploads/2014/02/5G-PPP-White-Paper-on-eHealth-Vertical-Sector.pdf (accessed on 10 July 2017).
204. Rose, K.; Eldridge, S.; Chaplin, L. The Internet of Things: An Overview. Available online: https://www.internetsociety.org/sites/default/files/ISOC-IoT-Overview-20151014_0.pdf (accessed on 10 July 2017).
205. Huawei. 5G Opening up New Business Opportunities. Available online: http://www-file.huawei.com/-/media/CORPORATE/PDF/x-lab/10-5g-opening-up-new-business-opportunities-en.pdf?la=en (accessed on 10 July 2017).
206. Lin, H.; Shao, J.; Zhang, C.; Fang, Y. CAM: Cloud-Assisted Privacy Preserving Mobile Health Monitoring. *IEEE Trans. Inf. Forensics Secur.* **2013**, *8*, 985–997. [CrossRef]
207. NGMN Alliance. NGMN 5G White Paper. Available online: https://www.ngmn.org/uploads/media/NGMN_5G_White_Paper_V1_0.pdf (accessed on 10 July 2017).
208. Le, N.T.; Hossain, M.A.; Islam, A.; Kim, D.-Y.; Choi, Y.-J.; Jang, Y.M. Survey of Promising Technologies for 5G Networks. *Hindawi* **2016**, *2016*. [CrossRef]
209. Militano, L.; Araniti, G.; Condoluci, M.; Farris, I.; Iera, A. Device-to-Device Communications for 5G Internet of Things. *EAI Endorsed Trans. Internet Things* **2015**, *1*. [CrossRef]
210. Shariatmadari, H.; Ratasuk, R.; Iraji, S.; Laya, A.; Taleb, T.; Ghosh, A. Machine-type Communications: Current Status and Future Perspective toward 5G Systems. *IEEE Commun. Mag.* **2015**, *53*, 10–17. [CrossRef]
211. 5GPPP. 5G and the Factories of the Future. Available online: https://5g-ppp.eu/wp-content/uploads/2014/02/5G-PPP-White-Paper-on-Factories-of-the-Future-Vertical-Sector.pdf (accessed on 10 July 2017).
212. Elayoubi, S.E.; Fallgren, M.; Spapis, P.; Zimmermann, G.; Martín-Sacristán, D.; Yang, C.; Jeux, S.; Agyapong, P.; Campoy, L.; Qi, Y.; et al. 5G Service Requirements and Operational Use Cases: Analysis and METIS II Vision. In Proceedings of the 2016 European Conference on Networks and Communications (EuCNC), Athens, Greece, 27–30 June 2016.
213. Blanco, B.; Fajardo, H.O.; Giannis, I.; Kafetzakis, E.; Pneg, S.; Perez-Romero, J.; Trajkovska, I.; Khodashenas, P.S.; Goratti, L.; Paolino, M.; et al. Technology Pillars in the Architecture of Future 5G Mobile Networks: NFV, MEC and SDN. *Comput. Stand. Interfaces* **2017**, *54*, 216–228. [CrossRef]
214. ITU-R. Recommendation ITU-R M.2083-0. IMT Vision: Framework and Overall Objectives of the Future Development of IMT for 2020 and Beyond. Available online: https://www.itu.int/dms_pubrec/itu-r/rec/m/R-REC-M.2083-0-201509-I!!PDF-E.pdf (accessed on 10 July 2017).
215. Le, L.B.; Lau, V.; Jorswieck, E.; Dao, N.-D.; Haghighat, A.; Kim, D.I.; Le-Ngoc, T. Enabling 5G Mobile Wireless Technologies. *EURASIP J. Wirel. Commun. Netw.* **2015**, *218*. [CrossRef]
216. Liu, G.; Jiang, D. 5G: Vision and Requirements for Mobile Communication System towards Year 2020. *Chin. J. Eng.* **2016**, *2016*, 5974586. [CrossRef]
217. Bogale, T.E.; Le, L.B. Massive MIMO and mmWave for 5G Wireless HetNet: Potential Benefit's and Challenges. *IEEE Veh. Technol. Mag.* **2016**, *11*, 64–75. [CrossRef]
218. Banelli, P.; Buzzi, S.; Colavolpe, G.; Modenini, A.; Rusek, F.; Ugolini, A. Modulation Formats and Waveforms for 5G Networks: Who Will Be the Heir of OFDM?: An overview of alternative modulation schemes for improved spectral efficiency. *IEEE Signal Process. Mag.* **2014**, *31*, 80–93. [CrossRef]
219. Palattella, M.R.; Dohler, M.; Grieco, A.; Rizzo, G.; Torsner, J.; Engel, T.; Ladidm, L. Internet of Things in the 5G Era: Enablers, Architecture and Business Models. *IEEE J. Sel. Areas Commun.* **2016**, *34*, 510–527. [CrossRef]

220. Pries, R.; Morper, H.-J.; Galambosi, N.; Jarschel, M. Network as a Service—A Demo on 5G Network Slicing. In Proceedings of the 28th International Teletraffic Congress (ITC 28), Würzburg, Germany, 12–16 September 2016.
221. Caraguay, A.L.V.; Peral, A.B.; Lopez, L.I.B. SDN: Evolution and Opportunities in the Development IoT Applications. *Int. J. Distrib. Sens. Netw.* **2014**, *10*. [CrossRef]
222. Bizanis, N.; Kuipers, F.A. SDN and Virtualization Solutions for the Internet of Things: A Survey. *IEEE Access* **2016**, *4*, 5591–5606. [CrossRef]
223. Stancu, A.; Vulpe, A.; Fratu, O.; Halunga, S. Default Values Mediator Used for a Wireless Transport SDN Proof of Concept. In Proceedings of the IEEE Conference on Standards for Communications and Networking (CSCN), Berlin, Germany, 31 October–2 November 2016.
224. Warren, D.; Dewar, C. Understanding 5G: Perspectives on Future Technological Advancements in Mobile. Available online: https://www.gsmaintelligence.com/research/?file=141208-5g.pdf&download (accessed on 10 July 2017).
225. Rappaport, T.S.; Heath, R.V.; Daniels, R.C.; Murdock, J.N. *Millimeter Wave Wireless Communications*, 1st ed.; Pearson: Harshey, PA, USA, 2017; pp. 1–657.
226. Thakare, S. Research Challenges of Millimeter Wave Technology in 5G Cellular System. In Proceedings of the 4th International Conference on Recent Trends in Engineering & Technology (ICRTET), Nashik, India, 2–4 July 2015.
227. Ye, J.; He, J.; Ge, X.; Chen, M. Energy Efficiency Analysis of 5G Ultra-dense Networks Based on Random Way Point Mobility Models. In Proceedings of the 2016 19th International Symposium on Wireless Personal Multimedia Communications, Shenzhen, China, 14–16 November 2016.
228. Witrisal, K.; Meissner, P.; Leitinger, E.; Shen, Y.; Gustafson, C.; Tufvesson, F.; Haneda, K.; Dardari, D.; Molisch, A.F.; Conti, A.; et al. High-Accurany Localization for Assisted Living: 5G Systems Will Turn Multipath Channels from Foe to Friend. *IEEE Signal Process. Mag.* **2016**, *33*, 59–70. [CrossRef]
229. 5GPP. 5G Automotive Vision. Available online: https://5g-ppp.eu/wp-content/uploads/2014/02/5G-PPP-White-Paper-on-Automotive-Vertical-Sectors.pdf (accessed on 10 July 2017).
230. Siaud, I.; Umner-Moll, A.M. Green-Oriented Multi-Techno Link Adaptation Metrics for 5G Heterogeneous Networks. *EURASIP J. Wirel. Commun. Netw.* **2016**, *92*. [CrossRef]
231. Le, L.B.; Niyato, D.; Hossain, E.; Kim, D.I.; Hoang, D.T. QoS-Aware and Energy-Efficient Resource Management in OFDMA Femtocells. *IEEE Trans. Wirel. Commun.* **2013**, *12*, 180–194. [CrossRef]
232. Ye, Q.; Rong, B.; Chen, Y.; Al-Shalash, M.; Caramanis, C.; Andrews, J.G. User Association for Load Balancing in Heterogeneous Cellular Networks. *IEEE Trans. Wirel. Commun.* **2013**, *12*, 2706–2716. [CrossRef]
233. Mavromoustakis, C.X.; Bourdena, A.; Mastorakis, G.; Pallis, E.; Kormentzas, G. Coverage An Energy-Aware Scheme for Efficient Spectrum Utilization in A 5G Mobile Cognitive Radio Network Architecture. *Telecommun. Syst.* **2015**, *59*, 63–75. [CrossRef]
234. Wu, S.; Wang, Y.; Al Imari, M.; Nekovee, M. FQAM: Frequency and Quadrature Amplitude Modulation for 5G Networks. In Proceedings of the 2016 European Conference on Networks and Communications (EuCNC), Athens, Greece, 27–30 June 2016.
235. Al-Imari, M.; Mouhouche, B.; Al.Imari, M.; Nekovee, M.F. Non-Orthogonal FQAM for Multiple Access in the Uplink of 5G Wireless Networks. In Proceedings of the 2016 International Symposium on Wireless Communication Systems (ISWCS), Poznań, Poland, 20–23 September 2016.
236. Hong, S.; Sagong, M.; Lim, C.; Cho, S.; Cheun, K.; Yang, K. Frequency and Quadrature Amplitude Modulation for Downlink Cellular OFDMA Networks. *IEEE J. Sel. Areas Commun.* **2014**, *32*, 1256–1267. [CrossRef]
237. Nekovee, M.; Yue, W.; Tesanovic, M.; Wu, S.; Qi, Y.; Al-Imari, M. Overview of 5G Modulation and Waveforms Candidates. *J. Commun. Inf. Netw.* **2016**, *1*, 44–60. [CrossRef]
238. Hochwald, B.M.; Sweldens, W. Differential Unitary Space-Time Modulation. *IEEE Trans. Commun.* **2000**, *48*, 2041–2052. [CrossRef]
239. Ostman, J.; Yang, W.; DUrisim, G.; Koch, T. Diversity Versus Multiplexing at Finite Blocklength. In Proceedings of the 11th International Symposium on Wireless Communications Systems (ISWCS), Barcelona, Spain, 26–29 August 2014.
240. Devaillie, B.; van Liempd, B.; Hershberg, B.; Craninckx, J.; Rikkinen, K.; van den Broek, D.J.; Klumperink, E.A.M.; Nauta, B. In-Band Full-Duplex Transceiver Technology for 5G Mobile Networks. In Proceedings of the ESSCIRC Conference, Graz, Austria, 4–8 December 2016.

241. Kim, C.; Kim, K.; Yun, Y.H.; Ho, Z.; Lee, B.; Seol, J.-Y. QAM-FBMC: A New Multi-carrier System for Post-OFDM Wireless Communications. In Proceedings of the IEEE Global Communication Conference GLOBECOM, San Diego, CA, USA, 6–10 December 2015.
242. Fettweis, G.; Krondorf, M.; Bittner, S. GFDM-generalized Frequency Division Multiplexing. In Proceedings of the IEEE 69th VTC, Barcelona, Spain, 26–29 April 2009.
243. Abdoli, G.; Jia, M.; Ma, J. Filtered OFDM: A New Waveform for Future Wireless Systems. In Proceedings of the IEEE 16th International Workshop SPAWC, Stockholm, Sweden, 28 June–1 July 2015.
244. Li, J.; Kearney, K.; Bala, E.; Yang, R. Filtered OFDM: A Resource Block Based Filtered OFDM Scheme and Performanse Comparison. In Proceedings of the 2013 20th International Conference on Telecommunications, Casablanca, Morocco, 6–8 May 2013.
245. Kumar, U.; Ibars, C.; Bhorkar, A.; Jung, H. Filtered OFDM: A Waveform for 5G: Guard Interval DFT-S-OFDM. In Proceedings of the IEEE Globecom Workshops (GC Wkshps), San Diego, CA, USA, 6–10 December 2015.
246. Chung, C.D. Spectrally Precoded OFDM. *IEEE Trans. Commun.* **2006**, *54*, 2173–2185. [CrossRef]
247. Monk, A.; Hadani, R.; Tsatsanis, M.; Rakib, S. OTFS—Orthogonal Time Frequency Space. Available online: https://arxiv.org/ftp/arxiv/papers/1608/1608.02993.pdf (accessed on 10 July 2017).
248. Bandemer, B.; Gamal, A.E.; Kim, Y.H. Optimal Achievable Rates for Interference Networks with Random Codes. *IEEE Trans. Inf. Theory* **20125**, *61*, 6536–6549. [CrossRef]
249. Carleial, A.B. Multiple-access Channels with Different Generalized Feedback Signals. *IEEE Trans. Inf. Theory* **1982**, *28*, 841–850. [CrossRef]
250. Prasad, A.; Uusitalo, M.A.; Li, Z.; Lunder, P. Reflection Environment Maps for Enhanced Reliability in 5G Self-Organizing Networks. In Proceedings of the IEEE Globecom Workshops (GC Wkshps), Washington, DC, USA, 4–8 December 2016.
251. Sui, Y.; Papadogiannis, A.; Sternad, M. The Potential of Moving Relays-A Performance Analysis. In Proceedings of the 2012 IEEE 75th Vehicular Technology Conference (VTC Spring), Yokohama, Japan, 6–9 May 2012.
252. Jiang, L.; Tian, H.; Xing, K.; Zhang, K.; Maharjan, S.; Cjessing, S.; Zhang, Y. Social-aware Energy Harvesting Device-to-Device Communications in 5G Networks. *IEEE Wirel. Commun.* **2016**, *23*, 20–27. [CrossRef]
253. Huang, X.; Yu, R.; Kang, J.; Gao, Y.; Maharjan, S.; Gjessing, S.; Zhang, Y. Software Defined Energy Harvesting Networking for 5G Green Communications. *IEEE Wirel. Commun.* **2017**, *24*, 38–45. [CrossRef]
254. Merwaday, A.; Guvenc, I. UAV Assisted Heterogeneous Networks for Public Safety Communications. In Proceedings of the IEEE Wireless Communications and Networking Conference Workshops (WCNCW), New Orleand, LA, USA, 9–12 March 2015.
255. Osseiran, A. The 5G Radio-Access Technologies. In *5G Mobile and Wireless Communications Technology*, 1st ed.; Osseiran, A., Monserrat, J.F., Marsch, P., Dohler, M., Nakamura, T., Eds.; Cambridge University Press: Cambridge, UK, 2016.
256. Sahin, A.; Yang, R.; Bala, E.; Beluri, M.C.; Olesen, R.L. Flexible DFT-S-OFD: Solutions and Challenges. *IEEE Commun. Mag.* **2016**, *54*, 106–112. [CrossRef]
257. Shi, S.; Yang, W.; Zhang, J.; Chang, Z. Review of Key Technologies of 5G Wireless Communication System. *MATEC Web Conf.* **2015**, *22*. [CrossRef]
258. Wang, C.-X.; Haider, F.; Gao, X.; You, X.-H.; Yang, Y.; Yuan, D.; Aggoune, H.; Haas, H.; Fletcher, S.; Hepsaydir, E. Cellular Architecture and Key Technologies for 5G Wireless Communication Networks. *IEEE Commun. Mag.* **2014**, *52*, 122–130. [CrossRef]

© 2017 by the authors. Licensee MDPI, Basel, Switzerland. This article is an open access article distributed under the terms and conditions of the Creative Commons Attribution (CC BY) license (http://creativecommons.org/licenses/by/4.0/).

5G
VISION

DMC R&D Center, Samsung Electronics Co., Ltd.

Date : February 2015

Samsung envisions the fifth Generation (5G) mobile communication era to be the beginning of a full scale Internet of Things (IoT). Billions of connected devices autonomously interconnect with one another while ensuring personal privacy. The unprecedented latencies offered by 5G Networks will enable users to indulge in gigabit speed immersive services regardless of geographical and time dependent factors. This white paper introduces you to future services, key requirements, and enabling technologies that will herald in the 5G era that is expected to revolutionize the way we experience mobile services.

Dawn of the 5G Era

Fuelled by the unprecedented growth in the number of connected devices and mobile data, and the ever-fast approaching limits of the 4G technologies to address this enormous data demand, industry efforts and investments to define, develop and deliver the systems and specifications for the fifth-Generation (5G) mobile system and services are well under way - signaling the dawn of the 5G Era.

As shown in Figure 1, the number of connected Internet of Things (IoT) is estimated to reach 50 Billion by 2020 [1], while the mobile data traffic is expected to grow to 24.3 Exabytes per month by 2019 [2].



Figure 1 Growth in Mobile Traffic and Connected Devices

Add to it, the impact of higher cell capacity and end-user data rate requirements due to emerging new services such as Ultra-High-Definition (UHD) multimedia streaming and extremely low latency requirements for cloud computing and storage/retrieval, and it soon becomes evident that the current 4G systems, which are already stretched to near-breaking points (despite massive Wi-Fi offload), will be stretched too thin to deliver the quality of experience (QoE) necessary to support mobile experience that 5G is set to deliver.

5G Era can be expected to revolutionize the way we communicate by supporting immersive applications that demand exceptionally high-speed wireless connections, a fully-realized IoT, experience lower latency and promote both spectrum and energy efficiency. To realize these benefits, 5G systems will differ fundamentally from their predecessors fueling a series of groundbreaking innovations. Let's look at the services and the requirements that 5G is expected to address.

5G Service Vision

5G services have the potential to revolutionize the mobile experience. Here's how:

Internet of Things

5G will make the "Internet of Things" a reality. With 5G technology, a device will be able to maintain network connectivity regardless of time and location, and open the possibility to connect all the connected devices without human intervention. For this, the basic fabric of the 5G system design is expected to provide support for up to a million simultaneous connections per square kilometer, enabling a variety of machine-to-machine services including wireless metering, mobile payments, smart grid and critical infrastructure monitoring, connected home, smart transportation, and telemedicine. Intelligent devices will communicate with each other autonomously in the background and share information freely. This ubiquitous connectivity - a basic tenet of the 5G services, will truly enable IoT services which in turn is expected to profoundly change human lives by connecting virtually everything.

– Smart Home

Dishwashers will fix themselves using information from peers of the same model while home appliances at home and in the neighboring homes may cooperate to extinguish a fire. A smart refrigerator, recommending a recipe of cuisine to be cooked with ingredients that are already in your refrigerator, is yet another plausible scenario.

– Fitness & Healthcare

Connected Health and Fitness related wearable devices such as The Samsung Gear™ Fit will record your athletic performance while you exercise and recommend the type of exercise, its duration and frequency per day. These connected healthcare devices will also send vital signs such as brainwave, blood pressure and heartbeat to an expert system in the hospital in real-time to prevent medical emergencies before they occur. Such time critical applications put unprecedented requirements on latency.

– Smart Store

In large shopping malls, while many people walk around window shopping, vicinity to products is continuously tracked, usually by a server somewhere in the cloud. Customized alerts for low priced product can be sent to the user's device as the user is detected in the vicinity of that low-priced product, or information of other lower prices in the nearby stores can be sent to the device as the customer spends more time in the vicinity of a certain product class.

Such a system can be tailored to deliver a highly customized experience thereby greatly enhancing a user's shopping experience. To support such a scenario, massive connectivity and low latency technologies are inevitable.

– Smart Office

In smart office environments, office appliances are connected with one another and will share information. Nearby computers and input/output devices can recognize a user and change the settings using the user's preferences stored in the IoT cloud. Printers will print out the relevant documents when the user passes by the printer. Almost all the office appliances will connect wirelessly, while exchanging massive data through wireless medium without noticeable delay. Alerts on the upcoming meetings, materials and documents relevant to that meeting will instantaneously become available to the user's device, while documents and tasks that are modified will be automatically updated.

– Connected Car

Many of us use navigation services via in-car navigation systems or our smart phones to find the most efficient route to our destination. Vehicle diagnostic services are becoming attractive to obtain the information such as battery level, fuel level or engine status on our smartphones. The 'eCall' system that automatically calls emergency services in case of an emergency exemplifies such a service. By 2020 and beyond, more attractive services that wirelessly connect 'cars' around us with 'things' will emerge and make people in the vehicles very comfortable, and provide an enjoyable driving experience. For safer driving, sensor and camera data in a vehicle as well as supplementary information from the neighboring vehicles will be collected using mobile networks so that a potential emergency situation can be reliably informed to a driver in real-time and timely steps can be taken to avoid an actual emergency situation. This operation will eventually be applied to self-driving cars, which can be viewed as an important type of 'things'.

Immersive Multimedia Experience

In a 5G environment, users will experience life-like multimedia streams anytime and anywhere. Users will feel as if they are part of the scene when they watch videos on their smart devices. To provide such an immersive experience, many obstacles will need to be overcome. Agility to instantaneously respond to the user's thought and behavior will be necessary. An upcoming service that is expected to provide life-like experience in 5G system is UHD video streaming with its greatly enhanced resolution and clarity. Currently, UHD services over terrestrial broadcast are already being standardized in some countries. In addition, some smart phones in the market are now equipped with a camera module



Figure 2 Major Service Scenarios with 5G

that can record video with 4K UHD quality. It is expected that UHD services are likely to go mainstream by 2020 raising an acute need for performance enhancement of cellular systems to support such services.

Other examples of “immersive” services that will fundamentally revolutionize entertainment, health, education, and other industry sectors are Virtual Reality (VR) and Augmented Reality (AR).

VR provides a world where physical presence is simulated by computer graphics, and the user can actively interact with the simulated elements, as in immersive sports broadcasting for instance (See Figure 3). Other interesting VR service scenarios are interactive 360° movies, online games, remote education, and virtual orchestra. Samsung’s recently launched VR headset called (called Gear VR), virtual reality video service platform (called Milk VR) and ‘Project Beyond,’ (a 360° 3D camera with 17 Full HD (FHD) camera modules, optimal for generating contents for Milk VR) indicate the humble beginnings of the truly immersive experience that is to come in the 5G Era.



Figure 3 Watching Sport Events with VR

In an AR service scenario, computer-aided real-time information based on user context is graphically augmented to the display, delivering added value for the user. In the future the service desk attendant no longer needs to memorize the tiresome details of the products. Instead, AR services will help to inform the price, popularity, and details of a given product. Figure 4 illustrates another service scenario - AR navigation on windshield, where navigation information and other helpful notifications (refuel reminder and nearby shop location) are displayed on the windshield of a car, so that the user can continue to focus on driving while getting subtle context-aware notifications about potential services at the same time.

Samsung is actively involved in the development of 5G technologies to support these immersive VR and AR services, which will entertain users and provide a truly life-like experience on the move.



Figure 4 Driving a Car with AR Navigation

Everything on the Cloud

5G will provide users with a desktop-like experience based on cloud computing. With everything stored and processed on the cloud and immediately accessed with low latency, only simple input and output interfaces on mobile devices are needed, making them lighter, thinner, fancier, and more eco-friendly.

As an example, when you go shopping, the smart device can notify you about the arrival of new dresses that you might like, or let you know how well a dress in the newly incoming inventory matches with your liking based on your purchase history. This notification can be triggered, for instance, as you step into a shop, or take a picture of the dress, while the necessary computation to come up with the dress recommendation through crowd sourcing is done on a cloud server that is potentially half a world away.

Intuitive Remote Access

Users will be able to control remote machines and appliances as if they are right before them, even from thousands of miles away. Thanks to the reliable connections and near-zero latency of 5G, users will be able to control heavy industrial machines remotely, or access hazardous site remotely. It will also help mankind in exploring areas on the earth that are as yet unexplored, such as the Polar Regions or parts of the ocean floor.

5G Requirements

In order to realize such a demanding and unprecedented service vision, Samsung proposes the 5G rainbow requirements consisting of 7 Key Performance Indices (KPIs) as shown in Figure 5.

5G systems will be required to deliver an order of magnitude cell capacities and per-user data rate compared to its predecessors. Specially, 5G systems are expected to support data rates of 10-50 Gbps for low-mobility users. As a baseline, 5G sys-



Figure 5 5G Rainbow Requirements

tems will provide gigabit-rate data services regardless of a user's location as shown in Figure 6 and Figure 7. To provide this uniform QoE, 5G network deployments are expected to be much denser compared to 4G networks, so making cost-effective deployment is a very important requisite.



Figure 6 Edgeless RAN - 1 Gbps Anywhere



Figure 7 Data Rate Comparison of 5G with 3G and 4G

To fundamentally support the cloud storage/computing infrastructure of the future, 5G networks will deliver an end-to-end latency of less than 5 milliseconds and over-the-air latency of less than one millisecond (see Figure 8) - which is one-tenth compared to the latency of a 4G network. Critical infrastructure monitoring, for example, currently requires service levels achievable only on dedicated wireline networks while 5G technologies offer the promise of making these service levels achievable over wireless networks. Likewise, low-latency networks will allow pre-crash sensing, enabling vehicles to sense imminent collisions and exchange relevant data that could salvage the situation and/or mitigate adverse impact of the collision. Other challenging low-latency services that could be enabled by 5G could include self-driving cars, public safety communications systems, augmented reality, and "tactile internet" [3].



Figure 8 Ultra Low Latency of 5G

With spectral efficiency requirements set to 10 bps/Hz levels (in contrast to the 1-3 bps/Hz on 4G networks), 5G is also expected to deliver an efficient use of the spectrum by using MIMO, advanced coding and modulation schemes and new waveform design (more on this in the enabling technology section)

To address the ever-widening revenue gap that the operators and service providers are experiencing, 5G systems are targeted to be 50 times more efficient than 4G by delivering reduced cost and energy usage per bit. This sequentially requires low-cost network equipment, lower deployment costs, and enhanced power saving functionality on the network and user equipment sides.

5G technologies will be required to cope efficiently with all degrees of mobility by providing "mobility on demand" based on each device's and service's needs. On one hand, the mobility of user equipment should be guaranteed to be at least the same level as the current 4G system - that is the baseline. On the other hand, Samsung envisions that specialized 5G systems will support mobility at speeds ranging from 300 to 500 km/h.

To make the IoT Vision come true, the number of simultaneous connections in the 5G system is expected to be over 10^6 per unit square kilometer, which is much higher than that of the legacy system.

5G Key Enabling Technologies

Groundbreaking innovations will drive 5G technologies to meet the unprecedented speeds, near-wireline latencies, ubiquitous connectivity with uniform QoE, and the ability to connect massive amounts of devices with each other, all working in unison to provide the user with an immersive experience, even while the user is on the move. Future 5G systems will encompass fundamentally new designs to boost wireless capacity utilizing new frequency bands, advanced spectrum efficiency enhancement methods in the legacy band, and seamless integration of licensed and unlicensed bands.


Tech for New Spectrum
5G
Tech for Legacy Spectrum
Interworking/ Integration



	Peak Data Rate	Cell Edge Data Rate	Cell Spectral Efficiency	Mobility	Energy / Cost Efficiency	Simultaneous Connection	Latency
- mmWave System	■	■	■	□	■	■	■
- Multi-RAT	■	□	□	■	■	■	□
- Advanced Network	□	□	□	■	■	■	■
- Advanced MIMO	□	■	■	□	■	■	□
- ACM & Multiple Access	□	■	■	□	□	■	□
- Advanced D2D	□	□	■	□	□	■	■
- Advanced Small Cell	□	■	□	■	■	□	□

Figure 9 shows an overview of the 5G key enabling technologies. The massively higher capacity needs of the 5G systems will be addressed by new mmWave systems, high-density small cells, advanced Multiple-Input and Multiple-output (MIMO) and new multiple access schemes like Filter-Bank Multi-Carrier (FBMC). Adaptive Coding and Modulation like Frequency and Quadrature Amplitude Modulation (FQAM) can significantly improve the cell edge performance and combined with higher density deployments with multi-BS cooperation will help to deliver on the promise of "Gbps anywhere" and Uniform QoE. Multi-Radio Access Technology (Multi-RAT) integration including carrier


mmWave BS
mmWave MS
5G
Antenna Array
Antenna Array
mmWave System
Wi-Fi AP
Carrier Aggregation of Licensed/Unlicensed Band
Multi-RAT
Advanced D2D
Advanced Network
Internet
Close to BS
Data Rate
FQAM
Legacy Tech
Cell Center
Cell Center
Cell Boundary (UE Location)
OFDMA
FQAM
FBMC
Elevation Beamforming
Azimuth Beamforming
Advanced MIMO
Advanced Small Cells
ACM & Multiple Access

Figure 9 Overview of 5G Key Enabling Technologies

aggregation of licensed and unlicensed bands will inevitably help in increasing the available system bandwidth. On the network side, novel topologies including application servers placed closer to the network edge will contribute to significantly reducing the network latency. Advanced Device-to-Device (D2D) technology can help reduce the communications latency and support larger number of simultaneous connections in a network.

These 5G key enabling technologies are described in more detail in the following sections.

mmWave System

The mmWave bands provide 10 times more bandwidth than the 4G cellular-bands, as illustrated in Figure 10. Therefore, the mmWave bands can support the higher data rates required in future mobile broadband access networks.


20
21.2
23.6
27.5
28.35
29.1
29.25
29.5
31
31.3
35
2.4 GHZ
2 GHZ
0.3 GHZ
1.3 GHZ
LMDS
35
36
40
41
42.5
45.5
47
47.2
50.2
4 GHZ
1.5 GHZ
1.5 GHZ
3 GHZ
LMDS
Mobile as primary service

Figure 10 Potential Bands in 20-50 GHz (US)

Unlike the below 6GHz bands, in the mmWave bands we have to carefully consider the wireless conditions such as rainfalls, snowfalls, and fogs. However, the amount of loss is mild for the expected range of a 5G communication link. For example, atmospheric absorption loss due to H_2O and O_2 at 28 GHz would be around 0.02 dB at a distance of 200 meters. Intensive rainfall (110 mm/h) results in about 4 dB loss at 200 meters distance. Loss due to heavy snow (10 mm/h) or heavy fog (visibility distance under 50 meters) will be less than 0.1 dB, at all distance of 200 meters [4][5].

In Figure 11, we show mmWave channel measurements from extensive experiments in Daejeon, Korea [6][7]. These channel measurements were carried out at 28 GHz with a channel bandwidth of 250 MHz, transmission power of 29 dBm and the horn antenna gain of 24.5 dBi for both the transmitter and the receiver [6][7].

The path loss exponents (based on 8 meters distance free space path loss) is 3.53 in Non Line of Sight (NLoS) links [6]. The mild path loss exponent from measurement results strongly suggests that mmWave communication links can be supported over 200 meters of distance, even in dense urban outdoor NLoS environments. Similar results are also reported in ray-tracing-based mmWave propagation model [8], confirming the fact that mmWave



Figure 11 mmWave Channel Measurements in Urban Area, Daejeon (Korea)


BS
Array Antenna
8X6 (=48) Antenna Elements
42 mm
42 mm
RF + Array Antenna
RF + Array Antenna
MS
25 mm
5 mm
Array Antenna
4X1 (=4) Antenna Elements
RF + Array Antenna
Baseband Modem

Figure 12 Adaptive Pencil Beamforming (Example)

bands can be successfully utilized for future IMT systems. Moreover, based on the ray-tracing, mmWave 3D-channel model in urban scenario is proposed in [9]. Higher path-loss and the resulting fragile link is largely due to weak diffractions in the mmWave bands. We need to overcome these challenges in order to make outdoor mmWave communication a reality [10][11]. Fortunately, the small mmWave wavelength also means highly directional beamforms can be obtained using a large number of antenna elements in a smaller form factor. These adaptive directional beams with large antenna array gain are key in combating the large propagation loss in the mmWave [12][13][14][15], as illustrated in Figure 12.

We have developed a mmWave beamforming prototype at the DMC R&D Center, Samsung Electronics, Korea, in order to demonstrate the feasibility of using mmWave bands for cellular services. We showed that mmWave system can meet the two key requirements of cellular services: sufficiently large geographical coverage and support for mobility in NLoS environments.

With the prototype, we tested outdoor coverage to demonstrate the service availability in a typical outdoor environment for both LoS and NLoS sites. The tests were performed at sites surrounded by tall buildings where various channel propagation effects such as reflection, diffraction, and penetration were present, as shown in Figure 13. We observed that reliable communication links are formed even for NLoS sites that are more than 200 meters away from the base station.


Rx Site A (NLoS)
Blocked
Rx Site B (LoS)
Rx Site C (NLoS)
Blocked
A
B
C
Samsung Electronics R5 Building Tower A
Samsung Electronics R5 Building Tower B
BS
50m
100m
150m
200m
250m
BLER result
Below 0.01%
Below 0.1%
Below 1%
Below 10 %
Below 25%
Below 50%
Below 75%
Below 100%
LoS / NLoS
LoS
NLoS

Figure 13 Exemplary Outdoor Coverage Test Results

Advances in semiconductor technology have made commercial mmWave systems readily available. Recent technologies of Silicon-based Complementary Metal Oxide Semiconductor (CMOS) processes are capable of integrating mixers, Low Noise Amplifiers (LNAs), Power Amplifiers (PAs), and Inter-Frequency (IF) amplifiers, all in a single package. A good example is the 60 GHz commercialized products with the label of Wireless Gigabit Alliance (WiGig) [16], and it is well recognized that cost effective implementations of sub-100nm CMOS process made it possible to utilize the 60 GHz bands [17]. GaAs Monolithic Microwave Integrated Circuit (MMIC) technologies are maturing fast, and they are becoming a dominant choice for components in the RF chain including PAs, LNAs, switches for digital attenuators and phase shifters, Voltage Controlled Oscillators (VCOs), and passive components from a few GHz to 100 GHz. As illustrated in Figure 14, it is projected that the Power Added Efficiency (PAE) of a 5G Front End Modules (FEM) will soon match the PAE of today's commercial 4G system. Meanwhile, a good Effective Isotropic Radiated Power (EIRP) can be achieved with the help of high antenna gains from a large number of antenna elements [18][19].



Figure 14 Projections of 5G FEM PAE

High performance antenna solution is an important piece of the 5G puzzle. The constantly varying LoS and NLoS propagation environment demands a novel antenna which exhibits high gain as well as wide spatial coverage capacity. The antenna array comprising of multiple antenna elements must fit within the small form factor of a 5G mobile handset.

Samsung has been developing innovative 5G phased array antennas that have near zero-footprint and reconfigurable antenna modes, as shown in Figure 15.


Parasitic Ant.
Chassis
V H V H V H
V H V H
H V H V H V
< 1.5 mm
Parasitic 5G Antenna embedded within chassis
High-Gain horizontally Polarized Antenna
Vertically Polarized Antenna

Figure 15 The Reconfigurable 5G Phased-array Antenna

Characterizing the biological implications on a user's body imposed by cellular handset devices is one of the most important aspects that need to be verified prior to its commercial release. The Signal Absorption Rate (SAR) regulated by worldwide governmental bodies is used as a guideline to assess the effect of mmWave bands on a user's body. The SAR of an envisioned 5G (28 GHz) cellular handset is analyzed and illustrated in Figure 16.

When optimally configured, the 5G beamforming technology enables the peak radiation of the Mobile Station (MS) antenna to steer away from the user's head. As a result, the average SAR can be reduced by more than a factor of 10 compared to that of the present day 4G cellular handsets.

The maximum SAR is expected to be further minimized in the future, as 5G antenna technology continues to evolve.


1.9 GHz (Omni)
: Penetration depth = 40 ~ 45 mm, Average = 0.29, Max =1 mW/g
Excluding the user's head
Including the user's head
Gain: 1 dBi
Penetration depth
= 40 ~ 45 mm
Average/MAX = 0.29/1 (mW/g)
28 GHz (Broadside Beamforming)
: Penetration depth = 3 mm, Average = 0.02, Max = 3.2 mW/g
Excluding the user's head
Including the user's head
Gain: 15 dBi
Penetration depth
= 3 mm
Average/MAX = 0.02/3.2 (mW/g)

Figure 16 Biological Implications on the User's Body

Multi-RAT

To realize the envisioned 5G services, significant enhancement of per-user throughput and overall system capacity is required, compared with those of the 4G system. Such an enhancement can be achieved through advanced PHY/MAC/network technologies and efficient methods of cell deployment and spectrum management. In particular, utilizing a larger amount of system bandwidth guarantees an increase in the capacity by allocating more frequency resources to each user in the system. Therefore, utilizing the spectrum where huge bandwidth is available can be considered to be the most critical issue for the 5G system.

Currently, the 4G system specifies its operating frequency bands and some of them are assigned to cellular operators. These deployments can be beneficial since the existing 4G system will not interfere with other RATs.

However, obtaining the licensed spectrum requires not only considerable financial investment, but also a significantly long period of time spent on regulatory procedures. More importantly, a substantial portion of the licensed spectrum around 2 GHz is already being used. Therefore, finding a bandwidth that is wide enough to support the 5G system is very challenging.

The recent trend in spectrum management is to aggregate both the licensed and unlicensed spectrums to extend available system bandwidth, as shown in Figure 17.


Licensed Band
Channel 1
Channel 2
Channel M
Unlicensed Band
Channel 1
Channel 2
Channel N
Primary Channel in Licensed Band
Secondary Channel in Unlicensed Band
Licensed & Unlicensed Bands
Licensed Band

Figure 17 Integration of Licensed and Unlicensed Bands

The unlicensed spectrum has plenty of bandwidth. For instance, approximately 500 MHz and 7 GHz bandwidths are available in the 5 GHz and 60 GHz bands, respectively. In order for the 5G system to utilize the unlicensed spectrum, regulations imposed on each frequency band should be carefully reconsidered. Representative examples of the regulations are the Transmit Power Control (TPC), Dynamic Frequency Selection (DFS), and Listen Before Talk (LBT).

To efficiently utilize the unlicensed spectrum, we will develop the 5G system with the following characteristics.

First, we will design PHY/MAC/network algorithms suitable for the nature of the unlicensed spectrum. Since a wide range of frequency bands are included in the unlicensed spectrum, each frequency band has its own characteristics. Hence, band-specific solutions will be provided.

Second, efficient coexistence mechanisms that take into account other RATs (e.g., WiFi or WiGig) operating in the unlicensed spectrum will be suggested.

Finally, techniques for interworking and integrating the 5G system with other RATs will be developed. By taking advantage of multiple RATs, the 5G system will be able to take advantage of the unique characteristics of each RAT and improve the practicality of the system as a whole. For instance, the 4G system is used for exchanging the control messages to maintain the connection, to perform handover, and to provide real-time services such as VoLTE. The technology operating in mmWave unlicensed frequency band would support the gigabit data rate service. Multiple mmWave cells can be overlaid on top of the underlying 4G macro cells, as shown in Figure 18.



Figure 18 Overlaid Network of mmWave Small Cell Integrated with the Underlay 4G System

Advanced Network

In order to meet the 5G key requirements such as latency and the large number of simultaneous connections, and to support new business models and scenarios for operators, technologies above the radio access level should also be considered. Therefore, we need to develop technologies at the system architecture level from the network point of view. To accomplish the 5G key requirements and support the increased data rate of new 5G radio access, 5G network will have to evolve towards a distributed and flat architecture.

Current mobile network architectures designate a dedicated node in the core network (e.g., PGW - Packet Data Network Gateway in 3GPP) as a mobility anchor that allocates an IP address to the terminal, tracks terminal location in the IP topology, and ensures terminal's reachability by tunneling its traffic to wherever it goes. All terminal traffic is tunneled through the centralized node in the mobile core network. However, the undesirable consequences of this design include the following:

- Increase in end-to-end transmission latency due to elongated data paths.
- Additional load of backhauling and network processing in the core networks.
- Low network reliability due to introduction of a single point of failures.

In the 5G flat network architecture, as illustrated in Figure 19, user mobility is managed efficiently and in a dynamically scalable fashion by pushing the functionality to the edges of the network and even onto the mobile terminals [20].

The three important benefits of this approach include the followings:

First, such a distributed mobility management always provides the shortest data path between MS and the Internet without traversing the core network. This distributed mobility management leads to a significant reduction of signaling and data transmission delay. Also, low end-to-end latency requirements of 'less than 5 ms' for new 5G services such as immersive UHD video streaming, cloud gaming, and virtual reality, cannot be archived solely by reducing radio access latency but would also require a flatter network architecture design. In the flat network architecture, services which require low latency transmission can be provided by Edge Servers and they can benefit from advanced network features which utilizes network information for optimal operations.

Second, it provides a highly scalable solution compared to the centralized architecture, in which a single core network gateway maintains the whole traffic from MSs or to MSs.

Third, it easily avoids the risk of having a single point of failure. In flat network architecture, the breakdown of one network gateway would not significantly interfere with the operations of the other gateways.

Flexibility is considered as another key requirement of 5G network architecture. Software-Defined Networking (SDN) and Network Function Virtualization (NFV) provide promising examples of programmable design technologies for realizing a flexible 5G network architecture.



Figure 19 5G Flat Network Architecture

Advanced MIMO

One promising technology for meeting the future demands is massive MIMO transmission/reception [21]. When used with multi-user precoding schemes such as Maximum Ratio Transmission (MRT) precoding, also known as channel conjugate precoding, massive MIMO systems experience small inter-user and inter-cell interferences, and consequently achieve significantly higher throughput than the state-of-the-art MIMO systems.

One of the main challenges to build massive MIMO systems in practice is the limitation in the number of antennas that can be equipped at a BS, caused by the BS form factors and operating carrier frequencies.

For example, to horizontally install a large number of antenna elements (e.g., > 8) at the top of a BS tower operating with the lowest 4G system frequency bands of 700 MHz, eight antenna elements with 0.5 λ spacing require up to 1.7 m width, where λ is the carrier wavelength. For the typical 4G system frequency bands of 2.5 GHz, fitting 32 antenna elements with 0.5 λ spacing require up to 1.9 m width, which is still not feasible in many BSs that have only limited room on the tower. This practical limitation has motivated Full-Dimension MIMO (FD-MIMO) cellular communication systems, which place a large number of active antenna elements in a two dimensional grid at the BSs.

A typical FD-MIMO deployment scenario is illustrated in Figure 20, for a macro BS with 3 sectors equipped with 2D Active Antenna Array (AAA) panels.


FD-MIMO simultaneously supports elevation & azimuth beamforming and > 10 MSs MU-MIMO
Elevation Beamforming
FD-MIMO BS
Azimuth Beamforming

Figure 20 Example of FD-MIMO Deployment

FD-MIMO system can support high-order Multi-User MIMO (MU-MIMO), while fully exploiting the elevation as well as the azimuth dimension, thereby generating improved system throughput.

In full buffer system-level evaluations, it has been found that 64-antenna-port FD-MIMO system achieves 243% average-cell and 244% cell-edge performance gain, compared to those of the 8-antenna-port legacy MIMO system. In order to achieve the promising gain of FD-MIMO in practice, we need accurate beam steering and tracking in three Dimensions (3D).

To steer and track the MU beams toward serving MSs, FD-MIMO BS should be equipped with multiple transceivers (TRX) feeding 2D array elements, in which the number of TRX doubles or even quadruples compared to that of the conventional BS.

Having a large number of TRX poses new challenges, such as antenna calibration and complexity issues associated with Channel State Information (CSI) acquisition and precoding.

On the other hand, high-order MU-MIMO introduces another set of new challenges, such as scheduling complexity and link adaptation. Furthermore, in Frequency Division Duplex (FDD) systems, other new challenges emerge such as pilot overhead, CSI estimation complexity, CSI quantization and feedback overheads.

ACM & Multiple Access

– FBMC

As cellular IoT has been one of key driving forces to 5G, spectrally efficient support for heterogeneous services that have quite different requirements is becoming ever so important. Accordingly, several enabling methods such as multi-RAT coexistence and flexible spectrum sharing have been actively investigated.

Recently, FBMC has drawn much attention as an enabling technology for enhancing the fundamental spectral efficiency, though its theory has a long history similar to that of Orthogonal Frequency Division Multiplexing (OFDM).

Because of the well-localized time/frequency traits adopted from a pulse shaping filter per subcarrier, the FBMC system can reduce the overhead of guard band required to fit in the given spectrum bandwidth, while meeting the spectrum mask requirement.

Furthermore, the effectively increased symbol duration is suitable for handling the multi-path fading channels even without Cyclic Prefix (CP) overhead. Consequently, the FBMC system can reduce the inherent overheads such as CP and guard-bands in CP-OFDM. FBMC is also attractive in specific asynchronous scenarios, including Coordinated Multi-Point Transmission and Reception (CoMP) and Dynamic Spectrum Access (DSA) in a fragmented spectrum.

However, to maintain the transmission symbol rate, the conventional FBMC system generally doubles the lattice density either in time or in frequency compared with OFDM while adopting Offset Quadrature Amplitude Modulation (OQAM). In OQAM, in-phase and quadrature-phase modulation symbols are mapped separately with half symbol duration offset. Thus, so-called OQAM-FBMC or Staggered Multi-Tone (SMT) causes intrinsic interference that makes it difficult to apply conventional pilot designs and corresponding channel estimation algorithms as well as MIMO schemes as in CP-OFDM systems [22].

With a base-filter that takes the spectrum confinement and the orthogonality among adjacent subcarriers into consideration, the QAM-FBMC system performs comparable to the CP-OFDM system even without the CP overhead, while the guardband overhead reduction is also available from the well-confined spectrum. Sophisticated receiver algorithms including channel estimation and equalization can further mitigate the multi-path fading channel impact without the CP.



Figure 21 One QAM-FBMC Symbol Generation

– FQAM

One of key requirements for 5G is enhancement of cell-edge performance, which means that every user should be supported with Gigabit experience anywhere. Conventional approaches to enhance the cell-edge performance mainly focus on managing interference (e.g., interference cancellation, interference avoidance), by dealing with interference as a Gaussian. However, it is proved that the worst-case additive noise in wireless networks with respect to the channel capacity has a Gaussian distribution. From this observation, one can expect that the channel capacity can be increased by a non-Gaussian interference design which makes Inter-Cell Interference (ICI) non-Gaussian. The distribution of ICI depends on the modulation schemes of the interfering BSs. Therefore, an active interference design for improved cell-edge performance can be achieved by applying a new type of modulation.

FQAM, a combination of Frequency Shift Keying (FSK), and Quadrature Amplitude Modulation (QAM) can be used as an active interference design scheme. Figure 22 shows the signal constellation of 16-ary FQAM that is a combination of 4-ary FSK and 4-ary QAM.



Figure 22 Example of 16-ary FQAM

With FQAM, the statistical distribution of ICI is likely to be non-Gaussian, especially for cell-edge users. As a result, the transmission rates for the cell-edge users can be significantly improved.

The statistics of ICI and the performance enhancement possibility have been proven by practical implementation of a system which uses FQAM. FQAM system environment for cellular downlink OFDMA networks is shown in Figure 23 and 24. Our experimental results show that the transmission rates for interference-limited users in FQAM-based OFDMA networks are around 300% higher than those in QAM-based OFDMA networks [23][24].



Figure 23 3 Cell Structure with MS and BSs



Figure 24 Implemented MS and BS

Advanced D2D

Advanced D2D communication is an attractive technology that enhances spectral efficiency and reduces end-to-end latency for 5G. Not entirely depending on the cellular network, D2D devices can communicate directly with one another when they are in close proximity. Hence, D2D communication will be used for offloading data from network so that the cost of processing those data and related signaling is minimized. Moreover, enhanced version of D2D communication was suggested lately for being used as special purpose such as Mission Critical Push-To-Talk (MCPTT) communication and Vehicle-to-Anything (V2X) communication.

In advanced D2D communication, a single radio resource can be reused among multiple groups which want to communicate with each other if the interference incurred between groups is tolerable. Hence, we can increase the spectral efficiency and the number of the simultaneous connection by utilizing D2D communication in 5G. Moreover, since the data is directly transmitted and not going through the core network, the end-to-end latency can be considerably reduced. Therefore, advanced D2D communication is quite well aligned with IoT services as shown in Figure 25. The cars can communicate with each other to exchange the information for safety alarm and infotainment without cellular base station. The home appliances communicate with each other for home automation service. Many objects in proximity region can be connected to each other so that IoT services can be accomplished.



Figure 25 Advanced D2D Communications

Advanced Small Cell

To achieve significant throughput enhancement in a practical manner, it is necessary to deploy a large number of cells in a given area and to manage them intelligently. The 5G system is expected to utilize higher frequencies to take advantage of the vast bandwidth in the mmWave bands. Hence, the considerably high propagation loss of mmWave makes it suitable for dense small cell deployment, which leads to higher spatial reuse.

Moreover, Figure 26 shows the concept of a user-centric virtual cell. Conventional static network topologies with a central controller have an "edge", the reach of the central controller. However, a user-centric virtual cell that consists of a group of cooperating BSs is continuously reformed so that any user will always find himself/herself at the "center" of the cell.

Distributed and self-configuring network technologies will make it easy to deploy many small BSs in urban and suburban areas. In-band wireless backhaul can be used between BSs for cooperative communication, reducing the cost and complexity of backhaul network deployment.



Figure 26 User Centric Virtual Cellular Network

5G Deployment Scenario

In order to provide the ubiquitous high QoE gigabit accessibility, we envision an overlaid deployment of 5G in conjunction with the existing 4G macro cells. The 5G small cells can be coupled with the overlaid 4G macro cells, and the 4G macro cells will control the operations of the associated 5G small cells, as illustrated in Figure 27. In the figure, 5G BS primarily provides multi-gigabit per second throughput with high QoE to mobile users over the legacy spectrum or higher spectrum like the 5 GHz unlicensed band and bands above 6 GHz. Meanwhile, the 4G BS can serve as a control channel to 5G MSs for supporting seamless connection anywhere over the legacy 4G spectrum.

5G system will need enhanced RAN technologies that not only utilize the legacy frequency bands assigned to IMT and IMT-Advanced systems, but also use new frequency bands. At the same time, 5G system will also need to support seamless interworking with other RATs operating in unlicensed bands.



Figure 27 5G Deployment Scenario

Standardizations and Regulations

As shown in Figure 28, 5G is planned to be commercialized in year 2020. ITU-R WP 5D is preparing timelines in the vision document for standardization, spectrum allocation, and commercialization, in order to be on time. From the perspective of commercialization, standards for 5G should be ready by the year 2017 to allow 2 or 3 years for the development of 5G products. Considering average periods of previous standardization, 5G standards need to get started in 2015 to make 5G standards available by the end of 2017.

New frequency bands may be required to achieve the target performance of 5G. World Radio Communication Conference (WRC)-15 agenda item 1.1 made in WRC-12 indicates consideration for additional spectrum allocations to mobile services on a primary basis and for identification of additional frequency bands for IMT purposes.


2014
2015
2016
2017
2018
2019
2020
WRC-15
WRC-19
ITU-R
Vision
EVAL. Meth./ Requirement
Proposal Reception
STD Dvlp.
Evaluation
3GPP
Rel-13
Rel-14
Rel-15
Rel-16
5G
Initial Commercialization
EVAL. Meth. : Evaluation Methodology
STD Dvlp. : Standard Development

Figure 28 5G Timelines

In light of this agenda item, various frequency ranges had been proposed and discussed in ITU-R WP 5D in July 2013, and Joint Task Group (JTG) 4-5-6-7 had performed compatibility studies among various technologies in each candidate frequency band until July 2014.

Although bands above 6 GHz were not included in JTG 4-5-6-7's candidate frequency bands, WP 5D has been developing a new report on IMT systems in bands above 6 GHz, including channel characteristics and the potential usage of the bands for IMT systems.

WP 5D may also provide JTG 4-5-6-7 with the necessary information regarding bands above 6 GHz in order to be referenced as appropriate in the draft text of Conference Preparatory Meeting (CPM). The possibility and further necessity to study the bands are captured in the report from JTG 4-5-6-7 to CPM as follows:

"The demand of high bit rate, especially in densely populated area could be accommodated in higher frequency bands (e.g. above 6 GHz) than those currently being considered in studies, however the technical information required for compatibility studies has yet to be developed and these studies and proposals are being explored for future work, beyond WRC-15."

This report implies that new frequency bands can be added to the IMT frequency bands toward WRC-19, and it is likely that bands above 6 GHz can be one of candidate frequency bands.

In addition, Licensed Assisted Access (LAA) study item has been accepted in 3GPP LTE in the second half of 2014, acknowledging the use of unlicensed bands for cellular system.

Recently, as FCC relieves 5GHz band regulations for various unlicensed band usage, related coexistence technology between LTE and WLAN will be standardized in both standards.

Further, as shown in Figure 29, Samsung is actively engaging in the most of global 5G research initiatives, such as European 5G PPP projects of Horizon 2020, 5G Innovation Centre (5GIC) in UK, NYU Wireless Center in US, Giga KOREA project and Chinese 836 project.

Samsung is leading various collaborations with industries and academics over the world. In particular, Samsung has played an important role as the full member of 5G PPP Infrastructure Association, the executive board member of 5G Forum in Korea and the chair of vision sub-working group for Future IMT (5G) in ITU-R WP5D.

In order to have a consistent perspective on 5G with those of other academic institutes, we are vigorously developing 5G core technologies with several outstanding universities around the world.


5G PPP
HORIZON 2020
SURREY
5G Forum
MSIP
GIGA KOREA
SAMSUNG
NYU WIRELESS
FCC
未来移动通信论坛
FUTURE MOBILE COMMUNICATION FORUM
IMT-2020
5GMF

Figure 29 Global 5G R&D Activities

Conclusion

5G will usher in a revolutionary generation of mobile communication that provides ubiquitous multi-Gbps data rate regardless of the user's location.

Significantly increased system capacity and real-time responsiveness of the 5G system will introduce life-changing services providing the users with a truly immersive and rich experience. The profoundly life-alternating world of billions of interconnected devices, the IoT, will require something as revolutionary as 5G to be fully realized in its fullest extent. And finally 5G promises to reverse the widening revenue gap and make it worthwhile for operators and service providers to invest again in innovative new services, and continue to propel increased productivity and efficiency.

Reference

1 UMTS, “Mobile Traffic Forecasts 2010-2020 Report,” UMTS Forum, Jan. 2011.

2 Cisco, “Cisco Visual Networking Index: Global Mobile Data Traffic Forecast Update: 2013-2018,” Cisco, Feb. 2014.

3 Calum Dewar et al., “Understanding 5G: Perspectives on future technological advancements in mobile,” GSMA Intelligence Report, Dec. 2014.

4 ITU-R P.840-5, “Attenuation Due to Clouds and Fog,” ITU-R, Feb. 2012.

5 DARPA R-1335-ARPA, “Atmospheric Effects on Terrestrial Millimeter-Wave Communications,” DARPA Report, Mar. 1974.

6 Sooyoung Hur et al., “Wideband Spatial Channel Model in an Urban Cellular Environments At 28 GHz,” in Proc. EuCAP’15, April. 2015.

7 Sooyoung Hur et al., “28 GHz Channel Modeling Using 3D Ray-Tracing in Urban Environments,” in Proc. EuCAP’15, April. 2015.

8 Youngbin Chang et al., “A Novel Dual-Slope mm-Wave Channel Model Based on 3D Ray-Tracing in Urban Environments,” in Proc. IEEE PIMRC’14, Sep. 2014.

9 Sooyoung Hur et al., “Synchronous Channel Sounder Using Horn Antenna and Indoor Measurements on 28 GHz,” in Proc. IEEE BlackSeaCom’14, pp. 83-87, May 2014.

10 Zhouye Pi et al., “An Introduction to Millimeter-Wave Mobile Broadband Systems,” IEEE Communications Magazine, vol.49, no.6, pp.101-107, Jun. 2011.

11 Cheol Jeong et al., “Random Access in Millimeter-Wave Beamforming Cellular Networks: Issues and Approaches,” IEEE Communications Magazine, vol. 53, no. 1, pp.180-185, Jan. 2015.

12 Wonil Roh et al., “Millimeter-wave Beamforming as an Enabling Technology for 5G Cellular Communications: Theoretical Feasibility and Prototype Results,” IEEE Communications Magazine, vol. 52, no. 2, pp. 106-113, Feb. 2014.

13 Samsung, “Technologies for Rel-12 and Onwards,” RWS-120021, 3GPP TSG RAN Workshop on Rel-12 and Onwards, Jun. 2012.

14 Taeyoung Kim et al., “Tens of Gbps Support with mmWave Beamforming Systems for Next Generation Communications,” in Proc. IEEE GLOBECOM’13 Workshop, pp.3685-3690, Dec. 2013.

15 Chanhong Kim et al., “Multi-Beam Transmission Diversity with Hybrid Beamforming for MIMO-OFDM Systems,” in Proc. IEEE GLOBECOM’13 Workshop, pp. 61-65, Dec. 2013.

16 WiGig Alliance, “Defining the Future of Multi- Gigabit Wireless Communications,” WiGig White Paper, Jul. 2010.

17 R12-WP5D-C-0258, “Technical Feasibility of IMT in the Bands above 6 GHz,” ITU, Jan. 2013.

18 Theodore S. Rappaport et al., “Millimeter Wave Mobile Communications for 5G Cellular: It Will Work!,” IEEE Access, vol.1, pp.335-349, May 2013.

19 Theodore S. Rappaport et al., “28GHz Propagation Measurements for Outdoor Cellular Communications Using Steerable Beam Antennas in New York City,” in Proc. IEEE ICC’13, pp.5143-5147, Jun. 2013.

20 Alper Yegin et al., “Terminal-centric Distribution and Orchestration of IP Mobility for 5G Networks,” IEEE Communications Magazine, vol. 52, no. 11, pp.86-92, Nov. 2014.

21 Young-Han Nam et al., “Full Dimension MIMO (FD-MIMO) for Next Generation Cellular Technology,” IEEE Communications Magazine, vol. 51, no. 6, pp.172-179, Jun. 2013.

22 Maurice Bellanger et al., “FBMC Physical Layer: a Primer,” PHYDYAS Tech. Rep., Jun. 2010.

23 Sungnam Hong et al., “A Modulation Technique for Active Interference Design under Downlink Cellular OFDMA Networks,” in Proc. IEEE WCNC’14, pp.683-688, Apr. 2014.

24 Sungnam Hong et al., “Frequency and Quadrature-Amplitude Modulation for Downlink Cellular OFDMA Networks,” IEEE Journal on Selected Areas in Communication, vol. 32, no. 6, pp.1256-1267, Jun. 2014.

Samsung Demonstrates World’s First 5G Data Transmission at Highway Speeds

Record-breaking 1.2Gbps data transmission at over 100km/h, and 7.5Gbps in stationary conditions using 28GHz spectrum

SEOUL, Korea – October 15, 2014 – Samsung Electronics Co., Ltd today announced the record-breaking demonstration of super-fast data transmission targeted for fifth generation (5G) mobile networks using 28 GHz spectrum. Samsung researchers confirmed the world’s first data rate of 1.2 Gbps, or 150 MB per second on a vehicle cruising at over 100 km/h. This marks a significant step towards the utilization of millimeter wave frequency bands for 5G mobile networks

5G
SYSTEMS
1244 Mbps
SAMSUNG TOMORROW

Figure A Achieved Data Rate in Mobile Condition (1.2Gbps)

The achievement was bolstered by another record-breaking demonstration in which Samsung achieved data transmission speed up to 7.5 Gbps, or 940 MB per second when the vehicle came to a complete stop. The peak data rate is more than thirty times faster compared to the state-of-the-art 4G LTE technology.

Back in May, 2013, Samsung revealed the world’s first 28 GHz based 5G data transmission speed of 1Gbps at pedestrian speeds. Since then researches at Samsung were able to increase the maximum data rate by more than 7-fold and support mobility up to highway speeds. The continued ground breaking success underlines the company’s leadership in next-generation mobile communications.

“The expectations for 5G communications will continue to grow based on the rising demands for smart devices, cloud services, smart home technology, and Internet of Things” , said ChangYeong Kim, Head of DMC R&D Center of Samsung Electronics. “We are committed to developing innovative 5G technologies and will continue to utilize our exceptional R&D capabilities as well as our diverse partnerships with leading companies and research centers around the world”.

While 5G standard has yet to be ratified, 5G networks are expected to feature data rates and capacity that are hundreds times larger compared to 4G LTE.



Figure B Achieved Data Rate in Stationary Condition (7.5Gbps)

In order to achieve such high data rates, 5G networks will inevitably exploit frequencies much higher and less congested than those of which are currently used for cellular networks (typically under 3 GHz). However, difficulties such as large propagation loss at these frequency bands have prohibited the industry from utilizing these bands for cellular applications. To address these challenges, Samsung has applied ‘Hybrid Adaptive Array Technology’ at 28 GHz frequency bands.

In addition, Samsung has revealed its ‘5G Rainbow’ – seven technical requirements which are pillars to ensure a truly differentiating 5G user experience. The list comprises of maximum data rate, spectral efficiency, speed of mobility, data transmission rate at the cell boundary, the number of simultaneous connections, communication delays, and cost. To meet these requirements, Samsung has been developing key technologies including transmission technologies for high frequency bands, multiple access schemes and low latency networks among others.

The company is committed to developing innovative technologies that will enable the 5G era and plans to demonstrate its capabilities at the upcoming 2018 PyeongChang and 2020 Tokyo Olympics.

Australian Government

Department of Communications and the Arts

5G—Enabling the future economy

October 2017

Disclaimer

The material in this paper is of a general nature and should not be regarded as legal advice or relied on for assistance in any particular circumstance or emergency situation. In any important matter, you should seek appropriate independent professional advice in relation to your own circumstances.

The Commonwealth accepts no responsibility or liability for any damage, loss or expense incurred as a result of the reliance on information contained in this paper.

This paper has been prepared for consultation purposes only and does not indicate the Commonwealth's commitment to a particular course of action. Additionally, any third party views or recommendations included in this paper do not reflect the views of the Commonwealth, or indicate its commitment to a particular course of action.

Copyright

© Commonwealth of Australia 2017

The material in this paper is licensed under a Creative Commons Attribution—4.0 Australia license, with the exception of:

- the Commonwealth Coat of Arms
- this Department's logo
- any third party material
- any material protected by a trademark, and
- any images and/or photographs.

More information on this CC BY license is set out at the creative commons website: https://creativecommons.org/licenses/by/4.0/. Enquiries about this license and any use of this paper can be sent to: Department of Communications and the Arts, GPO Box 2154, Canberra, ACT, 2601.

Attribution

Use of all or part of this paper must include the following attribution:

> © Commonwealth of Australia 2017

Using the Commonwealth Coat of Arms

The terms of use for the Coat of Arms are available from the It's an Honour website (see www.itsanhonour.gov.au and click 'Commonwealth Coat of Arms').

Contents

Australia's 5G vision **1**

What is 5G? **3**

The 5G economics case **3**
Enhanced Mobile Broadband (eMBB) 3
Massive machine type communications (mMTC) 4
Critical communications 4

What is different about 5G? **6**
Network slicing 6
Mesh networks 6
Spectrum sharing 7
Antenna technology and network topology 7
Business case 8

How are countries preparing for 5G? **9**
Industry 5G preparations in Australia 9

The Government's direction for 5G **10**
Making spectrum available in a timely manner 10
Actively engaging in international spectrum harmonisation activities 11
Streamlining arrangements to allow mobile carriers to deploy infrastructure more quickly 11
Reviewing existing telecommunications regulatory arrangements to ensure they are fit-for-purpose 12

Next steps **12**

Australia’s 5G vision

5G is the next step in the evolution of mobile wireless communications technology, promising improved connectivity, greater network speeds and bandwidth, and very low latency. It is the fifth generation in mobile technology which, at each step, has seen significant developments in communications networks:

- 1G—The first generation of mobile phone networks were deployed in the early 1980s, providing a basic voice service using analogue transmission.
- 2G—In 1991, second generation networks were deployed, making the switch to digital standards with improved voice messaging and the introduction of the short message service (SMS).
- 3G—The third generation launched in 2001 and introduced data services in addition to voice and SMS.
- 4G—In 2009, the fourth generation protocol, Long Term Evolution (LTE), was introduced, supporting improved mobile broadband which saw increased capacity and speed for data.

New capabilities of mobile communications networks enabled by 5G technology will allow for a variety of ‘use cases’:

- higher quality and more video services provided to multiple users with full mobility, even at high speed
- massive scale automation delivered through widespread sensor networks and multiple connected devices
- delivery of critical communications assured by low latency and ultra-reliable networks, and
- improved productivity assisted by high quality, real time data analytics.

Unlike existing mobile communications networks, 5G networks have the potential to allow tailoring of requirements for each of these different use cases within the same network.

The Government considers that 5G is more than an incremental change for mobile communications. Instead, it provides the underlying architecture that will enable the next wave of productivity and innovation across different sectors of the Australian economy. Efficient rollout of 5G and uptake of the services it supports has the potential to produce far-reaching economic and social benefits and support growth of Australia’s digital economy. This will be supported by the rollout of the National Broadband Network (NBN) allowing greater capabilities for the seamless delivery of services across high speed mobile, fixed line and fixed wireless networks.

The Government wants to create an environment that allows Australia’s telecommunications industry to be at the forefront of seizing the benefits of 5G across the economy. The communications sector will lead the rollout of 5G networks in Australia. However, the Government can create the policy and regulatory environment to support a more efficient rollout, given its potential benefits to the economy.

The Government’s direction will be to support the timely rollout of 5G in Australia to enable the next wave of broad-based industry productivity, and support the growth of Australia’s digital economy.

This includes immediate actions by Government that enable the communications market to introduce new 5G technologies in line with international developments. These include:

- making spectrum available in a timely manner
- actively engaging in the international standardisation process
- streamlining arrangements to allow mobile carriers to deploy infrastructure more quickly, and
- reviewing existing telecommunications regulatory arrangements to ensure they are fit-for-purpose.

The Government recognises that as 5G continues to develop, other issues relating to the technology will likely emerge which may require future Government action. In particular, while there are opportunities for 5G to create economy-wide transformation, this will require a broader examination of sectoral regulatory frameworks.

To that end, the Government will work collaboratively with industry to foster an ongoing dialogue on 5G beyond the launch of this paper to identify and remove sectoral barriers to its successful and timely rollout. Through this dialogue, the Government will also look at opportunities to build on other Government activities, such as the national Digital Economy Strategy which will more broadly focus on building the productivity of sectors across the economy.

What is 5G?

The International Telecommunication Union (ITU) is the United Nations specialised agency for information and communications technologies. This body decides global spectrum allocation frameworks and harmonises international spectrum to ensure networks and connected devices can communicate seamlessly. The ITU will undertake the formal, international process to identify bands for 5G by 2020. It has developed draft technical specifications for 5G which include:[1]

- high data rates (1 Gbps for hotspots, 100 Mbps download and 50 Mbps upload for wide-area coverage)
- massive connectivity (1 million connections per square kilometre)
- ultra-low latency (1 millisecond)
- high reliability (99.999% for mission critical 'ultra-reliable' communications), and
- mobility at high speeds (up to 500 km/h i.e. high speed trains).

In working towards these specifications, 5G represents a significant leap from the capabilities of previous generations and introduces a range of new technological possibilities. The success of 5G in delivering new technologies and services will be supported by existing communications infrastructure, including the NBN. This convergence of high-speed fixed-line and mobile services will collectively produce a consistent and ubiquitous user experience.

The 5G economics case

Unlike early generations of mobile networks, 5G will represent a significant shift in the telecommunications industry's focus away from voice and more towards mobile broadband and increased industrial applications. These new use cases are expected to create benefits across a range of sectors—including transportation, health, manufacturing and agriculture—and have varying networking requirements. These use cases, as identified by the industry, can be divided into the following categories:

- enhanced Mobile Broadband
- massive Machine Type Communications, and
- critical communications.

Enhanced Mobile Broadband (eMBB)

eMBB will deliver improved capacity to a greater number of devices. This will enable higher rates and volumes of data transmission per device and improve coverage to a broader range of locations. eMBB will likely be the focus of early 5G deployments as it can immediately support the growing communications requirements for the digital economy.

An improved mobile experience for consumers

5G networks will give consumers a better mobile experience in more locations. Increased network capacity will support more users, even in crowded areas, such as large public events, and at peak times. Faster network speeds will also enable consumers to view rich content in more places, supporting the streaming of live events and high resolution media.

---

[1] ITU, 23 February 2017, 'Press Release: ITU agrees on key 5G performance requirements for IMT-2020'.

Massive machine type communications (mMTC)

As 5G networks mature, they will support the widespread and dense deployment of sensors and other network-connected devices by significantly reducing their power requirements and providing flexible coverage across different spectrum bands. This proliferation of the Internet of Things (IoT) across industries is expected to produce significant productivity benefits and support integration between sectors.

Supporting productivity and innovation

The term Industry 4.0 describes the next step in the advancement of the manufacturing sector (the ‘fourth industrial revolution’). Industry 4.0 introduces autonomous systems supported by a combination of technologies such as IoT, artificial intelligence, continued technological improvements and digitalisation in manufacturing.

Australia stands to benefit from Industry 4.0, given our world-class manufacturing sector, which includes several high-value industries such as medical technology and aerospace. Australian manufacturers can improve their productivity and international competitiveness through Industry 4.0 processes by supporting their participation in global value chains. This is of particular benefit to SME manufacturers, opening them up to new markets and opportunities. 5G can support Industry 4.0, by providing communications infrastructure that is more accessible and flexible to suit specific industry needs.

5G can enable innovation in other sectors such as agriculture. A challenge for Australia’s agricultural sector is identifying how to improve productivity while balancing environmental and commercial constraints. Precision agriculture, which focuses on improving yields and minimising economic risks, seeks to provide more control in the management of agricultural production. While precision agriculture requires a range of enablers—including data analysis, sensor networks and geographical information systems—5G can provide the supporting infrastructure for these technologies.

Critical communications

Low latency and ‘ultra-reliable’ communications networks will support the delivery of critical communications, i.e. to support public safety use and playing role in the technology ecosystem supporting autonomous vehicles. In addition to automation, critical communications will also help to support technological advancement in areas including robotics and artificial intelligence.

The social benefits from autonomous vehicles

5G networks are expected to play a role in the technology ecosystem supporting the development of autonomous vehicles, which will enable a number of social benefits for transportation. Traffic congestion, which is estimated to cost Australia $53 billion by 2031,[2] could be proactively reduced by smart city traffic management systems that are informed by machine-to-machine communications with autonomous vehicles.

Improved road safety is also expected to be a key outcome of autonomous vehicles, as the majority of car accidents involve human error. In the 12 months to July 2017, there were 1,235 deaths on Australian roads with road trauma costing the Australian community an estimated $27 billion annually.[3] Autonomous vehicles can have a valuable role not just in terms of financial savings, but in saving human lives.

---

[2] Infrastructure Australia, 2015, ‘Australian Infrastructure Audit’.

[3] Bureau of Infrastructure, Transport and Regional Economics, August 2017, ‘Road deaths—monthly bulletins’.

Figure 1—Outline of the relationship between the technical requirements of 5G and expected services and applications it will deliver


Enhanced mobile broadband
Improved user experience
100 Mbps connections, >1 Gbps peak data
Smart homes
3D and 4K video
Mass cloud computing
Mass connectivity
1 million connections/km²
Augmented reality and virtual reality
Industry applications
Smart cities
Autonomous vehicles
Mission critical application
Ultra-low latency
<1 millisecond
Lower power, lower costs
10 year battery life
High reliability
99.999% for mission critical communications
Massive machine type communications
Critical communications

Source: Based on figure 2 from the ITU paper, '[IMT Vision—Framework and overall objectives of the future development of IMT for 2020 and beyond](#).'

What is different about 5G?

5G is expected to enable productivity outcomes across key verticals of the economy as a result of a range of characteristics, such as **network slicing** and **mesh networks**. However, it will need to overcome deployment challenges such as **spectrum acquisition** and **coverage**. This is expected to lead to new approaches for deployment to enable widespread 5G coverage in Australia. The industry will also need to develop a robust **business case** for 5G rollout, which will likely be demand driven, to support the significant capital expenditure required.

Network slicing

Network slicing allows operators to split their network into separate sub-networks (also referred to as slices), enabling them to dedicate network resources to different users and applications. Sub-networks can 'slice' the infrastructure resources from the physical network to create virtual independent networks. This is a significant development from previous mobile network generations, as it enables an operator to deliver many different capabilities by creating slices that can be tailored for the intended usage. For example, an operator could create a network slice for IoT devices, or alternatively, a network slice for higher security for a higher quality of service for government or public safety uses.

Network slicing also provides a model for infrastructure sharing between network operators. In this case, a single transmitter's network could be shared with more than one operator. Given the capital expenditure that will be associated with 5G rollout, network slicing can provide a cost effective, short-term solution for operators.

Figure 2—5G network slicing enables operators to create separate virtual networks to meet application requirements



Source: Based on figure 2 from the ITU article, '[Why end-to-end network slicing will be important for 5G](#).'

Mesh networks

Mesh networks can be utilised to increase the range of coverage, where the 'mesh' is an interconnection among a network of devices. Only one device in the mesh needs to be connected to the network, which can then relay data to other nearby devices.

Mesh networks not only provide the opportunity to support 5G deployment but also have the additional benefit of providing efficient network speeds. Through dynamic routing, devices on a mesh network are able to seek the fastest and most reliable pathway to send and receive data. As such, this architecture can provide a cost effective solution for coverage in more remote areas. For example, primary industries would benefit from this network approach by simplifying network connections and costs associated with deploying and managing an IoT sensor network. However, the application of mesh networks is still highly speculative as the industry considers how they will operate in practice and in different environments. This may contribute to the development of new business models for 5G.

Spectrum sharing

Spectrum is a critical enabler of Australia's current and future communications infrastructure. The specific spectrum bands and quantity of spectrum required for 5G are still being considered. However, 5G will likely require a mix of low, medium and high frequency spectrum to meet different scenarios relating to coverage, connectivity, and latency:

- Low frequency (less than 1GHz)**—**providing widespread coverage across urban, suburban and rural areas and supporting IoT for low data rate applications.
- Medium frequency (1–6GHz)**—**providing good coverage and high speeds, and including the expected initial 5G range of 3.3–3.8GHz which has been identified as the most likely band for launching 5G globally.
- High frequency (above 6GHz)**—**providing ultra-high broadband speeds for advanced mobile broadband applications, and most suitable for applications in dense traffic hotspots.

5G technologies can be expected to deliver improvements in spectral efficiency (the data rate that can be supported per unit of spectrum). However, the use of 5G networks for applications such as widespread industrial applications is likely to require significantly more amounts of contiguous spectrum to be made available.

While some of the potential bands for 5G currently have unused spectrum, other bands would need to be 'refarmed', noting that it is likely that bands currently used for 2G, 3G and 4G in Australia will transition over time to 5G. Refarming enables spectrum to be transitioned to the highest value use as required. The refarming of spectrum already held by mobile broadband operators is a commercial decision for those operators. 5G is also expected to provide the opportunity for 'soft-refarming' where 4G and 5G technologies can both be supported simultaneously, minimising the impact to legacy devices during transition periods.

Spectrum sharing, that is spectrum accessed by numerous users on a shared basis, has also been identified as an option for 5G technology. Spectrum sharing encompasses a range of different aspects of spectrum management. Spectrum can be shared by geography, time, economic priority schemes, code modulation, polarisation, directionality or power. Access to spectrum is divided between users so it can be used without interference issues.

5G opens up new opportunities for increased spectrum sharing, through mechanisms such as network slicing. 5G technology is also designed to support shared arrangements, and allows for the sharing of the same spectrum ('unlicensed Wi-Fi' spectrum) with other technologies. Operators can augment their holdings in situations where existing exclusive holdings are insufficient to meet customer needs. Spectrum sharing in the 5G context is also supported by the expected use of highly directional antenna technology which would enable operators to operate in closer proximity without interference.

Antenna technology and network topology

5G will require radically different structures of networks if it is to achieve successful deployment in Australia. As 5G will likely utilise different frequencies, new equipment will be necessary. Additionally, the higher frequency 5G spectrum can only travel a small distance and will need more cells to ensure adequate coverage. However, antennas and equipment will be smaller, making it easier to attach these cells to existing infrastructure such as street lights and buildings.

The more dense deployment of cells will also give rise to other approaches that improve the reliability of data transmission across a 5G network. Data may be divided into individual streams and transmitted through multiple antenna segments in a process called Multiple Input Multiple Output (MIMO) which allows for more information to be transmitted simultaneously. This technique is further empowered by 'beamforming' which allows base stations to direct focused beams of energy to a specific area rather than dissipate the available power of a larger area. These developments will enable more efficient transmission and increase overall throughput.

5G is also expected to assist the adoption of IoT by further reducing power consumption through extended discontinuous reception. In this scenario, IoT devices shift between active and inactive cycles, transmitting only when required. This will allow connected devices to operate for extended periods on a single charge, reducing operational costs.

5G will also increase the support for a greater density of devices that would have otherwise been limited by the capacity on 3G and 4G networks. They will also enhance IoT deployment through the use of network slicing to create virtual network configurations that are optimised for the low power and coverage requirements of IoT networks.

Business case

For Australians to experience the benefits of 5G, the communications sector will need to explore and develop new business cases to attract investment and support the rollout of 5G services. As 5G becomes an integral part of the communications ecosystem, the sector will need to be agile to respond to the needs and expectations of other sectors which will be seeking to take advantage of these next generation networks.

While residential consumers will inevitably be attracted to the enhanced mobile broadband services offered by 5G, it is the industrial applications for 5G where industry expects to see the greatest opportunity for new business models.

Compelling industrial applications are still to be developed. For example, industry sectors can be expected to seek tailored solutions for their business needs such as enhancing their local area network or enabling autonomous systems, and small businesses will look for low cost deployments of IoT.

It is therefore expected that the model for 5G will be demand driven and will require the communications industry to foster new business opportunities.

How are countries preparing for 5G?

In preparation for 5G, many countries have been taking steps to test the technology and review their spectrum arrangements.

Examples of 5G work being undertaken by other countries

The United States is clearing the 600MHz band through an incentive auction for the potential early deployment of 5G. The United States has also identified reforms to infrastructure deployment as a priority for 5G rollout. Mobile network operators are also conducting trials of low-band spectrum for use in 5G services.

The Asia-Pacific Telecommunity (APT), the regional arm of the ITU, approved a recommendation for the use of the 700MHz band for 5G, with 26 countries in the Asia-Pacific region identifying this band for this use, including Australia, Japan, South Korea and New Zealand.

Korea and Japan have stated their intention to use some or all of the 26.5 to 29.5GHz range to trial enhanced mobile broadband applications ahead of the 2018 Winter and 2020 Summer Olympics respectively. It is expected that these trials will lead to commercial availability of 5G services.

The European Communications Commission (ECC) identified the 3.4–3.8 GHz and 26GHz band (from 24.25 to 27.5GHz) bands for the deployment of 5G in Europe. All European countries are expected to select at least part of this range to launch 5G by 2020.

In the United Kingdom, the government launched its 5G strategy in March 2017. It is funding testbeds to understand the different deployment requirements and security considerations for 5G. The United Kingdom is also working to make suitable spectrum available in the high (24.25 GHz–27.5 GHz, and other bands above 30 GHz), medium (3.4–3.8 GHz) and low frequency (700 MHz) bands.

Industry 5G preparations in Australia

Australia is well positioned to harness the opportunities of 5G. Australia has an effective and competitive mobile communications market, with voice and data coverage available to more than 99 per cent of the population.[4] It is the top performer internationally in terms of having in place effective enablers—infrastructure, affordability, consumer readiness and content availability—to support mobile internet adoption.[5]

5G trials have already commenced in Australia, with each of the main carriers working with mobile equipment suppliers in testing the application and limits of the technology. These trials will continue and will inform the communications sector on how 5G can be effectively deployed for the Australian environment.

---

[4] Department of Communications and the Arts, accessed 1 September 2017, ‘Mobile phone towers’.

[5] GSM Association, 24 June 2016, ‘Global Mobile Connectivity Index’.

The Government's direction for 5G

The Government has made significant investments to improve telecommunications infrastructure in Australia, through the NBN and the Mobile Black Spot Program. The Government is also working to create a policy and regulatory environment that supports a competitive and innovative communications market.

The Government recognises that 5G will enable innovation and productivity across industry sectors and can significantly contribute to Australian's growth and future prosperity. Therefore, the Government will focus on enabling the early deployment of this new generation of mobile networks in Australia and encourage its use in delivering new services and applications.

The Government will support the timely rollout of 5G in Australia to enable the next wave of broad-based industry productivity, and support the growth of Australia's digital economy.

Industry expects and needs to lead the deployment of 5G. However, the Government has a role in supporting network rollout by modernising policy and regulatory frameworks and removing barriers that would delay rollout and adoption unnecessarily.

In the first instance, the Government will support the early deployment of 5G in Australia by:

- making spectrum available in a timely manner
- actively engaging in international spectrum harmonisation activities
- streamlining arrangements to allow mobile carriers to deploy infrastructure more quickly, and
- reviewing existing telecommunications regulatory arrangements to ensure they are fit-for-purpose.

Making spectrum available in a timely manner

A clear, efficient and flexible regulatory framework governing spectrum access will be essential to support the timely deployment of 5G networks in Australia.

The Government is currently undertaking work to modernise Australia's spectrum management framework to ensure it remains fit-for-purpose. In May 2017, it outlined its proposed reforms to the framework which are designed to simplify and streamline the processes for spectrum allocation and provide a transparent, efficient and flexible spectrum management framework. This will be the most significant change to the Australian spectrum management framework in the last 25 years.

The reforms will remove barriers between licence types, and enable flexible licensing issue and allocation processes. This strategic approach will remove outdated processes and support the Australian Communications and Media Authority (the ACMA) to more effectively respond to market demands and new technologies, such as 5G. This will help Australia remain internationally competitive with a modern, innovative economy over the coming decades.

The Government will put in place its new spectrum management framework by 2019.

In addition, the ACMA will continue to work on making spectrum available for 5G. The ACMA has been investigating the use of 1.5GHz and 3.6GHz and high frequency mmWave bands in considering additional spectrum for mobile broadband services. The ACMA has decided to prioritise refarming of the 3.6GHz band over the 1.5GHz band, citing industry submissions noting this band is likely to be a pioneer band for early 5G deployments and the need to provide greater clarity and investment certainty for incumbents and potential new band entrants alike. The ACMA is currently engaging with industry on which parts of the 3.6GHz band should be reallocated and on what terms. This approach also follows international trends which have seen the 3.6GHz band commonly used for 5G trials.

The ACMA will work to bring 3.6GHz spectrum to auction in 2018.

Actively engaging in international spectrum harmonisation activities

There is already significant work underway globally with several countries trialling 5G, but standards for this new generation technology are yet to be finalised. The formal, international process to define 5G is led by the ITU. The ITU's Working Party 5D is responsible for shaping the standard for "futuristic mobile technologies" to support International Mobile Telecommunications (IMT) for 2020 and beyond.[6] This process is known as IMT-2020.

Stakeholders such as regulatory and policy setting bodies, hardware manufacturers and governments of countries in which they are based will be seeking to influence the international dialogue. A key body is the industry-driven 3GPP which undertakes technology standardisation. Collectively, the ITU and 3GPP will drive spectrum harmonisation activities: the ITU, led by administrations, will focus on the spectrum requirements; and the 3GPP, led by industry, will concentrate on equipment and device standards.

Industry is well-placed to lead the standardisation process particularly given its role identifying the application of 5G technologies. However, there is also an important role for the Government in these processes. This is particularly the case in the harmonisation of international spectrum arrangements which will have significant impact on the availability and cost of 5G devices in Australia and can be strongly contested.

In the past, Australia and the Asia-Pacific region have been influential in contributing to standards and spectrum plans that have been adopted across the world. This ensured that Australia was able to adopt new technologies quickly and that the Australian market could take advantage of the economies of scale and have a greater choice of mobile handset equipment.

The Government will ensure strong participation by Australian in domestic and international discussions about 5G spectrum harmonisation. Our continued involvement provides the opportunity to contribute to this dialogue and secure outcomes that will benefit the adoption of 5G in Australia.

Streamlining arrangements to allow mobile carriers to deploy infrastructure more quickly

The design and deployment of mobile networks will be radically different from those of today. 5G is expected to require additional infrastructure in new forms, including smaller cells and more densely-located antennas, particularly in the use of high-band spectrum.

Carriers have specific powers and immunities relating to telecommunications infrastructure deployment and installation. These laws help carriers to rollout telecommunications infrastructure quickly in a nationally-uniform way, rather than having to follow state, territory and local government requirements. These laws have existed in their current form since 1997.

The Government has recently consulted on proposed new arrangements that take account of technology developments and changes in operating practices as well as identifying opportunities to streamline deployment processes. Under these new proposed arrangements, mobile carriers would be able to rollout new communications technologies such as 5G more efficiently.

The Government understands that some members of the community have expressed concerns about the impact on public amenity from increased telecommunications infrastructure. The Government considers that telecommunications providers should work with local communities to address concerns about their infrastructure plans and is encouraging industry to consider consultation requirements for future 5G networks.

The Government continues to work with stakeholders and will implement the first tranche of changes to carrier powers and immunities following the conclusion of the consultation process.

---

[6] ITU, accessed 1 September, ITU towards "IMT for 2020 and beyond."

Reviewing existing telecommunications regulatory arrangements to ensure they are fit-for-purpose

The pace of change in the communications sector is impacting on the effectiveness of the existing telecommunications regulatory framework. In response, the Government is progressively working to modernise the regulatory architecture to ensure that the regulatory and policy settings flexibly respond to the current and future needs of the communications sector.

In undertaking reform, the Government is cognisant that the communications regulatory framework will need to be sufficiently flexible to address the emergence of new technologies and business models.

5G deployment will benefit from the Government's reform efforts, including updates to the regulatory framework for telecommunications and radio spectrum and modernising the ACMA. In these cases, the Government has been revising regulation to shift it away from the traditional vertical telecommunications sectors to principles based, flexible arrangements. This will provide the versatility necessary to account for 5G developments and services.

The Government will continue to work with industry to modernise current telecommunications regulatory arrangements to ensure they encourage competition and innovation in the sector.

As with previous mobile networks, cybersecurity will be a critical consideration as 5G is deployed. Security will be even more so a challenge for 5G, as the reliability of communications will be pivotal in the technology's ability to deliver benefits, particularly in the case of critical communications.

Additionally, in providing the architecture for automation, 5G networks will trigger an ever-increasing volume of data. While the bulk of data will be machine-to-machine communications, users will want assurance that their personal information is protected. User consent will be an area of growing complexity due to the intersection between autonomous systems and the individual.

Industry has strong incentives to address cybersecurity risks in 5G's new types of network deployments and systems. However, **the Government will continue to assess cybersecurity and privacy issues as they evolve to ensure Australians have confidence in using 5G.**

Next steps

The Government recognises the opportunities presented by 5G for economy-wide transformation, creating productivity benefits in sectors such as transportation, health, manufacturing and agriculture. However, realising the benefits of 5G in sectors other than communications will need the right sectoral regulatory settings.

The Government will work to ensure that sectoral regulatory frameworks are updated to take advantage of 5G. The communications portfolio is well-placed to facilitate an ongoing strategic dialogue on 5G that will support sectors to identify and work towards unlocking the potential benefits of the technology. This dialogue would provide a starting point for greater engagement across Government and with industry and the community.

To that end, **the Government will establish a 5G working group that will bring together representatives from across Government and industry.** The working group will create a platform for this strategic dialogue with a mandate to seek out opportunities and emerging issues on 5G. This will provide better coverage across Government of the evolving policy and regulatory challenges associated with 5G.

Boise State University
ScholarWorks

Electrical and Computer Engineering Faculty Publications and Presentations

Department of Electrical and Computer Engineering

1-1-2016

Energy Efficient Switched Parasitic Array Antenna for 5G Networks and IoT

Ahmed Kausar
Boise State University

Hani Mehrpouyan
Boise State University

Mathini Sellathurai
Boise State University

Rongrong Qian
Heriot Watt University

Shafaq Kausar
National University of Sciences and Technology

© 2016 IEEE. Personal use of this material is permitted. Permission from IEEE must be obtained for all other uses, in any current or future media, including reprinting/republishing this material for advertising or promotional purposes, creating new collective works, for resale or redistribution to servers or lists, or reuse of any copyrighted component of this work in other works. doi: 10.1109/LAPC.2016.7807569

This is an author-produced, peer-reviewed version of this article. The final, definitive version of this document can be found online at *2016 Loughborough Antennas & Propagation Conference (LAPC)*, published by IEEE. Copyright restrictions may apply. doi: 10.1109/LAPC.2016.7807569

Energy Efficient Switched Parasitic Array Antenna for 5G Networks and IoT

Ahmed Kausar*, Hani Mehrpouyan *, Mathini Sellathurai†, Rongrong Qian†, and Shafaq Kausar‡
*Department of Electrical and Computer Engineering
Boise State University, Boise, USA
Email: ahmedkausar@boisestate.edu, hanimehrpouyan@boisestate.edu
† School of Engineering and Physical Sciences
Heriot Watt University, Edinburgh, U.K
Email: m.sellathurai@hw.ac.uk, rq31@hw.ac.uk
‡Department of Electrical Engineering
National University of Sciences and Technology, Islamabad, Pakistan
Email: shafaqkausar@nust.edu.pk

***Abstract*—This paper includes design and implementation result of an adaptive beam forming antenna for upcoming 5G and Internet of Things (IoT). Switched parasitic array antennas are low cost, small sized and compact circular array antennas that steer beam in a desired direction by variation in switching pattern of parasitic elements. The proposed antenna design has an active center element, which is surrounded by several symmetrically placed parasitic elements. The designed antenna has a gain of 8 dB and is capable of 360 degrees beam steering in steps of 60 degrees each. Simulations are validated with results of the fabricated antenna. Antenna beam is steered by controlling parasitic elements. Future application of Electronically Steerable Parasitic Array Radiator (ESPAR) antennas and switched parasitic array antennas in next generation communication networks and methods for reducing size of the antenna are also highlighted.**

***Index Terms*—Internet of Things, 5G, circular array, reconfigurable, smart antenna, adaptive beamforming, Switched-Parasitic Array**

I. INTRODUCTION

Smart antennas are capable of adaptive beam forming in accordance with the environment. Over the last three decades wireless communication has made rapid progress due to better modulation schemes and better error correction schemes. Wireless communication systems are replacing the wired ones. Antenna is an integral part of wireless devices. To meet the ever-increasing demand of higher data rate, smart antennas capable of adaptive beam forming are introduced as a potential solution to increasing data rate and improving signal-to-noise ratio (SNR) in upcoming 5G and Internet of Things (IoT) [1]. By using smart antennas Equivalent Isotropically Radiated power (EIRP) can be increased. EIRP denotes product of the transmit power (P_t) and transmit antenna gain (G_t), i.e.

$$EIRP = P_t \times G_t \tag{1}$$

From (1), it is observed that by using a smart antenna G_t increases, which in turn leads to the increase in the EIRP. The beam of an antenna can be steered by means of mechanical movement of a directional antenna or by electronic beam steering. Electronic beam steering is resilient and provides more accurate approximation of the desired signal source. Moreover electronic beam steering antenna does not involve moving parts. Therefore, there is less wear and tear on the antenna as compared to mechanical beam steering. Generally electronic beam forming is achieved by using phase shifters coupled with an array of antenna elements. The phase of an individual phase shifter is varied such that there is net constructive interference in the intended direction of the antenna beam and destructive interference in all other directions [2]. Hence, electronic beam steering is preferred over mechanical beam steering.

Electronically Steerable Parasitic Array Radiator (ESPAR) antennas use mutual coupling between antenna elements to steer the beams instead of phase shifters. Design of parastic array radiator antennas is discussed in [3], [4] in which there is a center active element surrounded by a circular array of passive elements, where each passive element is loaded with a specific reactance. ESPAR antennas are smaller in size as compared to phase array antennas because elements have to be placed at a quarter of wavelength or less distance from each other for effective mutual coupling. Hence, ESPAR antennas are cost effective and space efficient. In such antennas we have only one active element, therefore, only one feed is required. Consequently, ESPAR antennas have lower losses (due to single feed) as compared to phase array antennas [3].

Previously designed antenna Electronically Steerable Parasitic Raidator(ESPAR) antennas have all cylindrical element, including the feed element [6], [7]. In this paper we have proposed design of seven element ESPAR antenna with conical center(active element)[1]. Length of conical element is optimized using optimetrics in HFSS. Our proposed antenna has higher bandwidth as compared to previously designed ESPAR antennas. [6], [7]. In multiple-input-multiple-output (MIMO)

---

[1] This work was supported by National Science Foundation (NSF) on Enhancing Access to Radio Spectrum (EARS)

978-1-5090-0783-7/16/$31.00 ©2016 IEEE

This is an author-produced, peer-reviewed version of this article. The final, definitive version of this document can be found online at *2016 Loughborough Antennas & Propagation Conference (LAPC)*, published by IEEE. Copyright restrictions may apply. doi: 10.1109/LAPC.2016.7807569



Fig. 1. Seven Element switched parasitic array antenna, ϕ is azimuth angle and θ is elevation angle.

systems there are multiple transmit and and receive antennas. Each receive antenna receives signal over different propagation channels yielding diversity gain. The MIMO technique can increase system throughput and reduce propagation losses. Similarly diversity gain can also be achieved by using smart antennas. In particular, we can transmit the same signal in multiple directions through directional beams, such that they experience different propagation channels [4]. Our proposed antenna is more suited for MIMO applications compared to previously designed model because of its higher gain and improved bandwidth efficiency.

This paper focuses on the design of a seven element switched parasitic array antenna. The antenna is first simulated and then it is fabricated. Simulation results are validated with the hardware results. Previously done work on ESPAR and switched array antennas involve cylindrical monopole elements mounted on a ground plain [8] due to cylindrical nature bandwidth of active monopole is confined, subsequently bandwidth of switched array and ESPAR antennas is limited. Instead on cylindrical monopole element we have used tapered conical monopole. Due to tapered design bandwidth is enhanced.

II. SWITCHED PARASITIC ARRAY ANTENNA CONCEPT

The conceptual overview of the switched parasitic array antenna is given in Fig. 1. We have first simulated the antenna with seven monopole elements. There is one element at center which is surrounded by a circular array. Feed is applied to the center element and it is termed as active element, whereas elements in the circular array are parasitic elements. Parasitic array antennas do not involve phase shifters, so that the manufacturing cost is less as compared to the phase array antennas. Each element is separated from other element by a quarter of wavelength, thus mutual coupling phenomena comes into account and there is a shift in phase of current in each element because of this mutual coupling phenomenon. Since switched parasitic array antennas offer adaptive beamforming solution with compact size and low cost, they are likely to be used in future communication devices to increase data-rates [6], [7]. Parasitic array antennas have vast potential for usage in laptops, cell phones, WLANs etc.



Fig. 2. Z_{21} versus separation distance.

A. Mutual Coupling

Mutual Coupling is basically the interaction between antenna elements in an array. Since parasitic elements are placed closer to each other (at a distance of $\lambda/4$) there will be mutual coupling.This mutual coupling phenomenon is responsible for a shift in phase of current induced in each element [8].The current induced by one antenna element in another antenna element [9] is given by (3)

$$I_2 = \frac{Z_{21}}{Z_{22}} \times I_0 \tag{2}$$

$$Z_{21} = \left|\frac{V_2}{I_1}\right|_{I_2=0} \tag{3}$$

$$Z_{21} = \left|\frac{V_2}{I_2}\right|_{I_1=0} \tag{4}$$

Here Z_{22} is constant as it is open-circuit output impedance. Z_{21} is open-circuit transfer impedenace from port 2 to port 1 and it can be approximated by graph shown in Fig. 2. From equation (3), beam can be steered in the desired direction by varying the phase of current I_2 [10].

978-1-5090-0783-7/16/$31.00 ©2016 IEEE

This is an author-produced, peer-reviewed version of this article. The final, definitive version of this document can be found online at *2016 Loughborough Antennas & Propagation Conference (LAPC)*, published by IEEE. Copyright restrictions may apply. doi: 10.1109/LAPC.2016.7807569



Fig. 3. RF PCB with Analog devices ADG 904 RF switches.

TABLE I
DESIGN PARAMETERS

Parameters	Values
Ground Skirt length	lambda/4
Monople Length	lambda/4
Frequency	2.45 GHz
Ground Radius	lambda/2
Monopole Radius	lambda/200
Ground Thickness	3 mm

B. Beam Steering Mechanism

In this work the designed antenna is capable of 360^0 beam steering in steps of 60^0. The beam steering is achieved by using two sets of 4:1 Analog devices multiplier switch ADG 904. Fig.3 shows RF PCB designed for beam steering. Beam is steered towards an element which is open. The open element behaves as a director and shorted elements act as reflectors. In order to achieve a maxima at 0^0, we make the element 1 open by using RF switch IC while other elements (i.e., elements 2,3,4,5 and 6) are shorted. This mechanism is similar to Yagi-Uda antenna where elements with shorter lengths in front of feed element act as directors and elements at rear of feed element acts as reflectors [11]. In Yagi-Uda antenna feed element is often a dipole or folded dipole.

III. PARASITIC ARRAY ANTENNA DESIGN

Design parameters and mechanical design of antenna is included in this section.

A. Design Parameters

Antenna design parameters are tabulated and the results are optimized using antenna simulation tools. Ground is skirted, since skirted ground provides mechanically sound model for PCB assembly to mount at back of antenna [12]. Skirt is $\lambda/4$ in length similarly each monopole element is lambda/4 in length and $\lambda/200$ is its radius.Table I shows the design parameters for the seven-element switched parasitic array antenna.



Fig. 4. Designed seven element parasitic switched array antenna.



Fig. 5. Simulated antenna model.

B. Mechanical Design

Monopole elements are made by cutting copper wire of desired gauge i.e lambda/200 in radius [13] and these elements are soldered on pin of SMA connectors.Aluminum is used as ground plane. Electromagnetic waves are reflected by the ground. Instead of using seven dipole elements we have used seven monopole elements mounted on the ground plane [14]. Ground is made hollow in order to create space for mounting control circuitry [15]. Fig. 4 shows designed hardware.

IV. ANTENNA SIMULATION AND PLOTS

The antenna is first simulated and then simulated results are compared with the measured results of fabricated antenna. Simulated results were in line with the hardware results and 8 dB gain was observed in simulated results as well as in fabricated antenna. In simulation each of the parasitic element is loaded with lumped port excitation, simulating opening and shorting [16] of monopole elements. Fig. 5 shows simulated model.

978-1-5090-0783-7/16/$31.00 ©2016 IEEE

This is an author-produced, peer-reviewed version of this article. The final, definitive version of this document can be found online at *2016 Loughborough Antennas & Propagation Conference (LAPC)*, published by IEEE. Copyright restrictions may apply. doi: 10.1109/LAPC.2016.7807569

TABLE II
MAXIMA PATTERN

Azimuth Angle	Element 1	Element 2	Element 3	Element 4	Element 5	Element 6
0 degree	Open	Short	Short	Short	Short	Short
30 degree	Open	Open	Short	Short	Short	Short



Fig. 6. Anechoic chamber results for θ=90^0 (Beam in elevated because we are using monopole elements with finite ground).

Two dimension polar plots depicts the beam steering in the direction of given elevation angle, theta (θ) and azimuth angle, phi (ϕ). Anechoic chamber results for θ=90 and ϕ=0 and 30 degrees are shown in Fig. 7 and 8 respectively. Using large ground plane angle of elevation is reduced closer to 90^0. Fig. 6 shows anechoic chamber result for θ=90 one can observe small elevation form desired x-y axis because of ground skirt [17].In simulations elevation angle of 85^0 is observed. Fig. 6(a) shows antenna simulated plot for elevation angle θ and Fig. 6(b) shows anechoic chamber results.Anechoic chamber plot of Fig. 7 shows maxima at ϕ=0^0, in order to get maxima at 0^0 elements from element number 2-6 are shorted and the element 1 is opened. Similarly Anechoic chamber plot of Fig. 8 shows maxima at ϕ=30^0, in order to get maxima at 30^0 elements from element number 3-6 are shorted and element 1 and element 2 are open.

Traditional ESPAR antenna and switched parasiric array antenna have all cylindrical elements, including the active element [3], [4]. We have made center element conical instead of cylindrical. Due to conical nature of active element response our frequency range and improved. In order to validate the gain enhancement both models were simulated and results were compared. Fig 9. (a) shows conventional design and Fig. 9(b) shows simulated antenna with conical center element. Fig. 10 shows S_{11} plot for cylindrical active element. Considering -8_{dB} as cut off point bandwidth range from 2.358 GHz to 2.51 GHz (0.152 GHz). Fig. 11 shows $S-11$ plot for centre conical element, considering 8_{dB} as cut off point bandwidth ranges from 2.36 GHz to 2.555 GHz (0.195 GHz). Therefore my making center element conical we have improved bandwidth as compared to traditional switch array parasitic antennas. Low profile design for switched parasitic array antennas in also highlighted in [18].



Fig. 7. Anechoic chamber results for ϕ=0^0.



Fig. 8. Anechoic chamber results for ϕ=30^0.



Fig. 9. (a) Conventional ESPAR antenna model with cylindrical Center Element, Fig. 9 (b) Designed ESPAR antenna with conical element for Bandwidth Enhancement.

V. FUTURE WORK AND CONCLUSION

5G networks will be designed for device to device, device to human and human to human interactions. High data rates are required to meet demands of 5G systems. One of proposed bands for 5G is in mm-Waves range i.e from 30GHz to 60GHz for such high frequencies path losses are considerable and beam steering antennas are way forward to overcome path

This is an author-produced, peer-reviewed version of this article. The final, definitive version of this document can be found online at *2016 Loughborough Antennas & Propagation Conference (LAPC)*, published by IEEE. Copyright restrictions may apply. doi: 10.1109/LAPC.2016.7807569



Fig. 10. S_{11} plot for conventional switched array antenna.



Fig. 11. S_{11} plot for center conical element switched array antenna.

losses [19]. ESPAR and switched parasitic array antennas provide a cost effective way of incorporating adaptive beamforming in future 5G and internet of Things (IoT) devices [20]. However for the efficient use of ESPAR antennas in mobile terminals the size of the antenna system must be reduced, for this further research on dielectric switched parasitic array antennas is underway. Seven element switched parasitic array antenna is designed that is capable of dynamic beam steering. Gain of 8dB is achieved practically. Simulated results are in line with the anechoic chamber results. Designed antenna increase the channel capacity by improving signal to noise ratio. Gain of 8dB was achieved in specified directions of elevation angle ,theta (θ) and azimuth angle, phi (ϕ). Antenna is optimized in terms of interference reduction for its use in wireless ad hoc networks, operating at frequency of 2.45 GHz. Bandwidth of designed antenna is 450 MHz and beam is steered in 360^0.

ACKNOWLEDGEMENT

Thanks to EPSRC Project EP/M014126/1, Large Scale Antenna Systems Made Practical: Advanced Signal Processing for Compact Deployments [LSAS-SP] and National Science Foundation (NSF), Enhancing Access to Radio Spectrum (EARS) program for funding.

REFERENCES

[1] M. Rzymowski, P. Woznica, and L. Kulas, “Single-anchor indoor localization using espar antenna,” *IEEE Antennas and Wireless Propagation Letters*, vol. 15, pp. 1183–1186, 2016.

[2] L. Zhou, F. A. Khan, T. Ratnarajah, and C. B. Papadias, “Achieving arbitrary signals transmission using a single radio frequency chain,” *IEEE Transactions on Communications*, vol. 63, no. 12, pp. 4865–4878, Dec 2015.

[3] V. I. Barousis and C. B. Papadias, “Arbitrary precoding with single-fed parasitic arrays: Closed-form expressions and design guidelines,” *IEEE Wireless Communications Letters*, vol. 3, no. 2, pp. 229–232, April 2014.

[4] M. R. Islam and M. Ali, “Elevation plane beam scanning of a novel parasitic array radiator antenna for 1900 mhz mobile handheld terminals,” *IEEE Transactions on Antennas and Propagation*, vol. 58, no. 10, pp. 3344–3352, Oct 2010.

[5] S. Kausar, H. U. Rahman, T. Hassan, and A. Kausar, “Miniaturization of espar antenna using folded monopoles and conical central element,” in *Radar, Antenna, Microwave, Electronics, and Telecommunications (ICRAMET), 2015 International Conference on*. IEEE, 2015, pp. 87–91.

[6] H. T. Liu, S. Gao, and T. H. Loh, “Electrically small and low cost smart antenna for wireless communication,” *IEEE Transactions on Antennas and Propagation*, vol. 60, no. 3, pp. 1540–1549, March 2012.

[7] T. H. Loh, H. Liu, and S. Gao, “A cost-effective direct magnitude measurement methodology for smart antennas,” *IEEE Transactions on Antennas and Propagation*, vol. 61, no. 4, pp. 2043–2050, April 2013.

[8] F. Khan, K. Ali, A. Kausar, and S. Kausar, “Energy generation capacity analysis of a canal based hydro project,” in *2013 Fifth International Conference on Computational Intelligence, Modelling and Simulation*, Sept 2013, pp. 277–281.

[9] A. Kausar, M. A. Cheema, S. Kausar, H. Rehman, and T. Hassan, “Espar antenna system designing & simulation,” in *Proceedings of the 2014 First International Conference on Systems Informatics, Modelling and Simulation*, ser. SIMS ’14. IEEE Computer Society, 2014, pp. 193–196. [Online]. Available: http://dx.doi.org/10.1109/SIMS.2014.37

[10] S. Akkar and A. Gharsallah, “Reactance domains unitary music algorithms based on real-valued orthogonal decomposition for electronically steerable parasitic array radiator antennas,” *IET Microwaves, Antennas Propagation*, vol. 6, no. 2, pp. 223–230, January 2012.

[11] S. Kausar, H. u. Rahman, A. Kausar, and T. Hassan, “Espar antenna system for dynamic tracking of active targets,” in *Modelling Symposium (EMS), 2013 European*, Nov 2013, pp. 533–535.

[12] A. Umar Kausar, F. Aslam Khan, T. Hassan, A. Nasser, and S. Kausar, “Adaptive espar antenna system modelling & design.” *International Journal of Simulation–Systems, Science & Technology*, vol. 14, no. 4, 2013.

[13] D. v. B. M. Trindade, C. Mller, M. C. F. D. Castro, and F. C. C. D. Castro, “Metamaterials applied to espar antenna for mutual coupling reduction,” *IEEE Antennas and Wireless Propagation Letters*, vol. 14, pp. 430–433, 2015.

[14] S. Kausar, Ahmed Kausar, “Smart adaptive beam forming antenna for interference cancellation,” in *Wireless Days (WD), 2013 IFIP*. IEEE, 2013, pp. 1–3.

[15] A. Kausar, S. Kausar, and T. Hassan, “Smart adaptive beam forming antenna for interference minimization,” in *Future Generation Communication Technology (FGCT), 2013 Second International Conference on*. IEEE, 2013, pp. 6–9.

[16] F. Aslam, E. Ulhaq, A. Nasser, and A. Umar, “Intelligent modeling scheme for detection of line losses in power distribution system,” in *Computer Modelling and Simulation (UKSim), 2013 UKSim 15th International Conference on*. IEEE, 2013, pp. 218–223.

[17] R. Qian, M. Sellathurai, and D. Wilcox, “A study on mvdr beamforming applied to an espar antenna,” *IEEE Signal Processing Letters*, vol. 22, no. 1, pp. 67–70, Jan 2015.

[18] A. Pal, A. Mehta, D. Mirshekar-Syahkal, and H. Nakano, “A low-profile switched-beam dual-band capacitively coupled square loop antenna,” in *Antennas and Propagation Conference (LAPC), 2013 Loughborough*, Nov 2013, pp. 563–566.

[19] A. Kausar, S. Kausar, T. Hassan *et al.*, “Interference cancellation using adaptive beam forming for 3 d beam steering.” *International Journal of Simulation–Systems, Science & Technology*, vol. 14, no. 1, 2013.

[20] M. R. Nikkhah, P. Loghmannia, J. Rashed-Mohassel, and A. A. Kishk, “Theory of espar design with their implementation in large arrays,” *IEEE Transactions on Antennas and Propagation*, vol. 62, no. 6, pp. 3359–3364, June 2014.

[21] T. Hassan, A. Kausar, H. Umair, and M. A. Anis, “Gain optimization of a seven element espar antenna using quasi-newton method,” in *Microwave technology & computational electromagnetics (ICMTCE), 2011 IEEE international conference on*. IEEE, 2011, pp. 293–296.

978-1-5090-0783-7/16/$31.00 ©2016 IEEE

Recent Antenna System Technologies for Next-generation Wireless Communications

Koichi Tsunekawa†

Abstract

This paper describes the requirements of the antennas or antenna systems in recent high-speed and high-capacity wireless communication systems and the key technologies for satisfying them. It also explains the antennas and antenna systems being researched and developed for next-generation wireless communication systems. The antenna in such a system requires high gain, high-efficiency antenna elements and a multi-antenna design. This paper introduces a high-efficiency antenna created by integrating it with a monolithic microwave integrated circuit (MMIC) in a millimeter-wave frequency-band system, a multi-antenna system for the multiple-input multiple-output (MIMO) technique that enables multiple data transmission for land mobile communication systems, and a beam-scanning antenna for satellite communication systems. It also explains the general research and development trend of antenna systems and technical problems in each wireless system as an introduction to the other selected papers in this issue.

1. Introduction

Wireless access technologies have advanced rapidly [1] and broadband wireless communication systems have become popular in our daily lives. An antenna is a very important component of a wireless system because it acts as the input and output interface for wireless equipment, as shown in **Fig. 1**. However, system performance is determined by the total performance of each component, such as the antenna and the radio-frequency (RF), intermediate-frequency (IF), and baseband (BB) units. For recent high-performance wireless systems, overall system design has been essential. Accordingly, the antenna must not



Fig. 1. Wireless and antenna system.

---

† NTT Network Innovation Laboratories
Yokosuka-shi, 239-0847 Japan
E-mail: tsunekawa.koichi@lab.ntt.co.jp

only have antenna elements with high-performance characteristics, but must also perform effectively as an antenna system in conjunction with the RF, IF, and BB units. New functions can be added through antenna system design: for example, appropriate radiation pattern control provides a large system capacity by using baseband signal processing and an antenna element with an integrated RF circuit provides high gain without feeder loss.

The selected papers in this issue describe the latest antenna and antenna system technologies for achieving high performance. Two of the papers present beam-scanning antenna systems in satellite broadband communication. Beam scanning is carried out using by two methods: one [2] uses a variable active device or tunable reactance device incorporated into the antenna element, which has high-speed electronic control while the other [3] uses mechanically controlled antenna movement, which has a very precise direction control function. Another paper [4] introduces an active integrated antenna system with an RF circuit, which provides high gain and high efficiency, for a high-capacity millimeter-wave transmission system. And two papers describe a multiple-input multiple-output (MIMO) antenna system for obtaining high-speed transmission and high system capacity in the land mobile communication system from the viewpoints of beamforming techniques [5] and implementation methods [6].

As an introduction to these advanced antenna techniques, this paper provides a general explanation of the requirements of antennas and antenna systems in recent high-speed and high-capacity wireless communication systems and the key technologies for satisfying these requirements. It also describes current antenna systems and NTT's antenna research results for typical wireless systems.

2. Antenna requirements in recent wireless communication systems

The trend of wireless systems is shown in **Fig. 2**. This indicates the typical system transmission speed and number of antennas needed to achieve a particular system performance for each operating frequency. Wireless communication systems are moving towards high transmission speeds and high capacity by using higher system frequencies to enable a wide frequency


100 GHz
10 GHz
1 GHz
100 MHz
Frequency
System name currently in service
System name future service
60-GHz system
High-gain technique
FWA
UWB
802.11a
4G
802.11n
Bluetooth
802.11b
802.11g
PHS
IMT-2000
HSDPA
PDC
RF-ID
Multi-antenna (multiplexing) technique
High-efficiency technique
1 kbit/s
10 kbit/s
100 kbit/s
1 Mbit/s
10 Mbit/s
100 Mbit/s
1 Gbit/s
Transmission speed
RF-ID: radio-frequency identification
PDC: personal digital cellular
PHS: personal handy-phone system
IMT-2000: international mobile telecommunications 2000
HSDPA: high-speed download packet access
802.11x: family of IEEE standards
UWB: ultrawideband
FWA: fixed wireless access
4G: fourth generation
: ubiquitous system
: land mobile system
: short-range system
: WLAN system
: fixed wireless system

Fig. 2. Advances of terrestrial wireless communication systems and their relationship to antenna technologies.

band and using advanced system technology to achieve high quality and signal multiplexing. The antenna requirements for these system properties are:

- High-gain and high-efficiency technology
- Multi-antenna technology

Increases in the gain and efficiency of an antenna are offset by higher propagation loss at high frequencies, so the received signal level needs to be higher. High gain is an age-old problem in antenna research and development. Multi-antenna technology improves the receiving signal quality and provides multiplexed signal transmission by using an antenna system that includes RF circuits, BB units, and antenna elements.

2.1 High-gain and high-efficiency antenna

Theoretical and experimental antenna gain and efficiency characteristics are shown in **Fig. 3**. The dependences of gain and beamwidth on horn dimension L(λ) in a relatively large antenna are explained in Fig. 3(a) [7]. When L is more than 0.5 times the wavelength, the antenna's efficiency is about 100%; a larger antenna provides higher gain. However, the high-gain radiation pattern leads to a narrow beamwidth. Therefore, a mobile terminal needs to use beam-scanning or beam-tracking techniques to follow the transmitter while the terminal moves. On the other hand, the efficiency decreases if the antenna size is less than 0.5 wavelengths. The bandwidth of a linear dipole antenna versus its efficiency for various antenna sizes (D: diameter) is shown in Fig. 3(b). This graph was estimated from theoretical limits [8] and many experimental results. The antenna efficiency becomes approximately –5 dB when antenna bandwidth of 10% is provided using a linear dipole antenna with a length of 0.3 wavelengths. This figure shows that the efficiency and bandwidth have a tradeoff relationship and that the efficiency drops greatly as the antenna size decreases. Therefore, some clever ideas for the antenna element structure are needed to overcome these weak points.

2.2 Multi-antenna system

A multi-antenna system has several antenna elements, but it does not merely work as an ordinary array antenna. The performance requirements are satisfied because the antenna system includes RF circuits, BB units, and antenna elements. The antenna element technologies and the multi-antenna system are shown in **Fig. 4**. In the antenna element, a high gain can be achieved by improvements to the antenna element structure, for example, by using a new material, adding a parasitic element, or integrating an RF circuit (Figs. 4(a)–(c)). The antenna shown in Fig. 4(c) is called an integrated antenna. It can control the radiation pattern as well as provide high gain by eliminating feeder loss. In a multi-antenna system (Fig. 4(d)), the radiation pattern is controlled by baseband signal processing, so the pattern of each wireless channel can be controlled by each baseband channel. Furthermore, it is possible to get multiplexed signal transmission in the space domain by baseband signal processing. Multi-antenna systems are generally called smart antennas or active antennas [9].



(a) Aperture antenna gain characteristics

(b) Dipole antenna efficiency characteristics

Fig. 3. Antenna gain and efficiency characteristics.


Radiation pattern
Ch 1
Ch 2
Innovative materials
Parasitic element
RF
Variable capacitor
RF1
RF2
IF1
IF2
BB (signal processing)
Ch 1
Ch 2
Input impedance characteristics
Return loss
Frequency
High-gain and high-efficiency antenna

(a) Novel antenna element
(b) Complex antenna element
(c) Integrated antenna element
(d) Multi-antenna system

Fig. 4. Antenna elements and system.

An example of a mobile communication system using a smart antenna in the base station is shown in **Fig. 5**. Independent information can be sent to the terminals, which are spatially separated, using the same frequency at the same time because each beam is generated for a specific terminal by using the space division multiple access (SDMA) technique. Furthermore, N multiplexed transmissions can be sent to a terminal with N antennas by utilizing the slight difference in antenna locations in the terminal. MIMO is representative of this kind of technology. The latest smart antenna systems can increase the antenna gain even in a mobile system and expand the service area. The designed system capacity can be increased by using multiplexing techniques based on baseband signal processing. Multi-antenna systems can achieve very high performance with high-level functions corresponding to the wireless system requirements.


Interference suppression
MIMO
SDMA
ch 1
ch 2
ch 2

Fig. 5. Smart antenna system (land mobile telecommunication).

2.3 Key antenna technologies

The key technologies for achieving a high-gain, high-efficiency, multi-antenna system are shown in **Table 1**. Antennas for the latest wireless communication systems are required to achieve high gain and high efficiency. The multi-antenna systems are designed to make maximum use of system resources, especially space.

3. Wireless systems and suitable antenna systems

The kinds of wireless systems that we can expect to find around us in the near future are illustrated in **Fig. 6**. RF-ID (radio-frequency identification) tags will be attached to various kinds of objects in a ubiquitous network and a large quantity of information will be gathered to provide useful knowledge to each person. High-speed data transmission ranging from a few megabits per second to 1 Gbit/s will be possible in mobile satellite systems, land mobile systems, and wireless local area network (WLAN) systems. In home networks, individual items of electronic equipment will be connected to each other at very high

Table 1. Key technologies to meet antenna requirements.

Requirements	Key technologies
1) High gain and high efficiency	a. Innovative materials (meta-material, high magnetic material, …) b. Element design (parasitic element, fractal element, …) c. Integrated antenna (antenna with RF circuit or RF device, …) d. Active antenna (antenna within variable reactance or switch, ….)
2) Multi-antenna techniques	a. Beam scanning antenna b. Sector antenna (fixed narrow multi-beam system) c. Diversity antenna d. SDMA antenna e. MIMO antenna


Internet
Public land mobile communications networks
Public broadband IP networks
Mobile satellite system
MIMO
SDMA
Land mobile system
Ubiquitous BS
Containers
PC
DVD
VCR
Home
Office
Hot spot
WLAN system
Short-range link system
Ubiquitous network system
● RF tag
BS: base station

Fig. 6. Wireless communication systems.

Table 2. Wireless systems and NTT's antenna system approaches.

	System features	Main technical trends (example system, standard, or equipment)	NTT's antenna approaches (using technologies in Table 1)
Ubiquitous RF-ID	Multiple access Low rate	Active tags Sensor network Mesh network (802.15.5)	Compact high-efficiency tag antenna High-gain beam tilting base station antenna (1a, 1b, 1c)
Short-range communication	Short range Ultrahigh speed Link transmission	High frequency band (millimeter-wave system) Ultrawideband (UWB) Infrared rays (IrDA)	Active integrated antenna system (millimeter wave) (1b, 1c, 2a, 2b)
Land mobile and WLAN	Medium range High speed/capacity Many subscribers	MIMO-OFDM (802.11n,802.16a/e) MC-CDMA (4G, Beyond 3G) HSDPA (3.5G,1xEV-DO/V)	MIMO-OFDM antenna system Compact mobile terminal antenna system (1b, 1d, 2b, 2c, 2d, 2e)
Mobile satellite	Very long range Medium to high speed Various mobile stations	S/Ku band high-speed mobile comm. (N-Star/ETS-VIII) Broadband (Internet) (WINS) Millimeter wave/optical comm. (MILSTAR, GeoLITE)	Multi-beam antenna Large deployable antenna Beam-tracking antenna system (1c, 1d, 2a, 2e)

(discussed in papers in this issue)

speed (several gigabits per second) wirelessly instead of by cables. In these wireless systems, highly functional and high-performance antennas will be essential. **Table 2** explains the main features and technical trend of the systems and also shows NTT's approaches to antennas and antenna systems for each high-performance wireless system. The technologies in Table 1 that are used are indicated in parentheses. Each antenna system must satisfy severe specifications and also provide high functionality, as shown in Figs. 4(c) and (d). The antennas discussed in the selected papers in this issue are shown in blue in Table 2. The present status of each antenna system and research and development in NTT are explained below.

3.1 Ubiquitous network antenna system

Tag antenna elements have the same problems as pagers or portable telephone systems that use the LF, UHF, and VHF bands. The antenna element must be as small as possible and have high efficiency in a small volume and in the neighborhood of various objects. Most antennas for passive tags using the LF band (13 MHz) are spiral, helical, N-turn loop, or meander line antennas [10] for achieving an electromagnetic induction area and their gains are considered to be very low. Bent and spiral monopole or dipole antennas are used in personal computer card wireless communication systems or in small square film tags using UHF-band systems [11]. The approach is to design the antenna and RF-IC as one system; in other words, the connection impedance between the antenna and RF-IC is designed as a freely selectable value instead of being restricted to 50 Ω. The same kind of technique is currently being investigated in NTT in a study of active integrated antennas [12]. On the other hand, the base station antenna can be designed by applying techniques developed for pagers or land mobile antennas because it has high-gain and beam-tilting characteristics.

3.2 Millimeter-wave frequency band communication antenna system

A high-speed wireless communication system is achieved by using wideband technology, so millimeter-wave frequencies, which provide a very wide bandwidth, are attracting attention. The use of high frequencies also requires high output power to compensate for the huge propagation loss and passive circuit losses, so high-gain and high-efficiency antennas are very important in system design [13]. Millimeter-wave systems mainly use horn, reflector [14], or lens antennas [15]. Horn or reflector antennas are used in relatively long-range communication where the range is several hundred meters. A lens type antenna, which is integrated with monolithic microwave integrated circuits (MMICs) to achieve high efficiency without a feeding line, is mainly used for short-range transmission, e.g., for a home link system. Active integrated antenna technology in which an amplifier for transmitting and receiving is mounted without using a connector or cables is suitable for a high-frequency-band system [16]. Typical antenna types for millimeter-wave frequency systems are shown in **Table 3**. Horn or reflector antennas provide very high gain but cannot be integrated with MMICs. The lens antenna provides high gain and can be made into an integrated antenna but requires adjustment to correct its

Table 3. Antenna types for millimeter-wave systems.

Antenna	Gain	Integration with MMIC	Mounting adjustment
Horn or reflector	Very high (over 20 dBi)	No	(Feeder)
Lens	High (10 to 20 dBi)	Yes	Needed
Single patch	Low (2 dBi)	Yes	No
Parasitic element patch	High (10 dBi)	Yes	No



Fig. 7. Active integrated antenna for 25-GHz system.

mounting error. The patch antenna is a good element for integration with MMICs because it can be made on the same material substrates, so it does not need antenna adjustment. We have developed an active integrated antenna designed for broadband mobile wireless access systems using the 25-GHz band, as shown in **Fig. 7** [12]. It exhibited output power of 14.6 dBm and a noise figure of less than 5 dB. The only weakness of this integrated antenna is that high gains cannot be provided with one patch antenna. The third selected paper in this issue describes a high-gain integrated active antenna and high-efficiency RF circuit for the millimeter-wave frequency band for a millimeter-wave communication system [4]. A high-gain integrated patch antenna is investigated as a parasitic element to obtain a wide antenna aperture. The millimeter-wave frequency-band link system was first proposed for application to the transmission of uncompressed HDTV (high-definition television) signals in the home or in a studio.

3.3 Land mobile and WLAN antenna systems

The number of subscribers to land mobile systems, especially cellular systems, has increased rapidly, and users are now demanding high-speed transmission for broadband Internet access. To meets these demands, many improvements to the land mobile system have been proposed such as wideband code division multiple access (W-CDMA), adaptive modulation, and *ad hoc* transmission. Recently, the utilization of space has become as desirable as frequency and time utilization [17]. Space utilization is achieved using a multi-antenna system with a radiation control mechanism, which is accomplished by a smart antenna system.

3.3.1 Typical multi-antenna techniques for mobile systems

The application areas of multi-antenna techniques depend qualitatively on the system characteristics, as shown in **Fig. 8**. A fixed high-gain beam antenna does not always need antenna elements, but the other techniques are achieved through various combinations of antenna elements, so they are provided by adaptive or integrated multi-antenna systems, as shown in Figs. 4(c) and (d). A narrow-beam or high-gain antenna is used in the line-of-sight situation (where there are no obstacles between the transmitting and receiving antennas and there are few paths in the multipath transmission), so a beam-scanning mechanism is needed when a terminal moves fast, and multiple beams or sector beams are required when there are many terminals in the service area. The diversity antenna technique can provide a stable signal level in a multipath mobile environment. Beam scanning (with a sector beam or multiple beams) and diversity antenna techniques have been used fairly extensively from the early days of mobile communication service because they use only simple signal processing. However, with the rapid progress of signal processing technology, a desired signal can now be distinguished from a mixture of many signals in a multipath environment. The SDMA technique distributes signals among the terminals communicating in the service area. MIMO techniques enable very-high-data-rate communication with multiplexed transmission in each antenna of the multi-antenna system of the base station or mobile terminal. These techniques require more calculation as the movement speed of the mobile terminal increases. In these wireless systems, signal processing ability and superior algorithms are more important than the performance of antenna elements.

3.3.2 Research results and developed antenna systems

A very small and thin planar six-sector antenna using a patch Yagi-Uda array with common directors for mobile terminals has been proposed (**Fig. 9**) [18],


Many
No. of users
A few
Multi-beam or sector beam
Diversity
SDMA
Tracking beam
Fixed beam
MIMO (SDM)
Poor
Multi-path
Rich
Low
Mobility
High

Fig. 8. Dependence of multi-antenna techniques on system characteristics.


Dual-direction patch Yagi-Uda array
Parasitic director elements
Feed element (#1)
60°
A
B
C
D
E
F
Radiation beam (at #1 feed)
Switch
Z
Load

Fig. 9. Thin and small sector beam antenna.

[19]. It has square parasitic director elements that are shared by two sector arrays that face in opposite directions, and it has a hexagonal central director element that is shared by all six sectors. These elements form three line arrays, which intersect at 60°. These shared elements enable the sector antenna to be compact. Experimental results showed that the fabricated antenna had a conical plane beam width of 63° and high front-back ratio of 17 dB. The creation of adaptive (smart) antenna hardware has been investigated [20]. A novel beam combination method for wideband digital indoor communication systems such as WLANs has been proposed [21] in NTT. Crossed fan beams are used at the base station and mobile terminal. The beam combination method provides better transmission quality than the traditional pencil-beam combination and eliminates the need for complex beam control in the base station. Maximum dispersion distributions in the transmission frequency bandwidth have been calculated using a three-dimensional indoor propagation delay simulation algorithm. A method of designing adaptive antennas including an

antenna configuration that is suitable for street microcells, considering the propagation environment, has been described. An automatic calibration method at the transmitters and receivers using the transmitting signal (ACT), which enables realtime calibration, has been presented [22]. An SDMA technique using polarization has also been studied [23]. The transmission quality of an SDMA scheme that uses vertical pattern and polarization control was investigated in an actual cellular environment. For a sector cell system, this configuration was shown to be effective based on an evaluation of the spatial correlation characteristics. We also found that the output carrier-to-interference-plus-noise power ratio (CINR) of the proposed configuration was from 10 to 17 dB higher than that of the conventional SDMA configuration when the number of users was greater than four. The proposed configuration can reduce the antenna size compared with conventional SDMA. Moreover, MIMO techniques enable very-high-data-rate transmission using a limited frequency band. We have studied technologies based on the eigenmode-space division multiplexing (E-SDM) [24] scheme because it provides the theoretically maximum channel capacity and reduces the terminal's calculation load. The selected papers in this issue introduce both theoretical and practical technologies. The fourth paper describes new MIMO methods with beamforming to overcome problems of calculation complexity and low MIMO effect in the line-of-sight scenario [5]. The fifth paper describes the configuration of an 8 × 4 MIMO-OFDM transceiver and presents experimental results for the propagation characteristics, bit error rate (BER), and frequency utilization [6].

3.4 Satellite broadband communication system

If we want to create a seamless and flexible wireless network system, then a satellite communication system is very important because it provides a wide service area. However, it has the inherent problem that the distance between the transmitter and receiver is long, so the terminal needs a larger antenna than ones in the land mobile system to provide high-speed transmission. The effective solution is to make the satellite dish larger to provide high gain and multibeam transmission. We have studied multibeam communication satellite technology and onboard large deployable antennas for creating a broadband mobile satellite communication system [25]. An MMIC-based beamforming network equipment for a multibeam feeder whose weight is only 1/3 that of the conventional type was developed. We are also developing a large, highly precise deployable antenna with a diameter in the over-10-m range. The mobile terminal acting as an earth station is also an important component of a broadband mobile satellite communication system. Typical existing antennas in earth stations are shown in **Table 4**. Various mobile terminals are accommodated in the satellite communication system by different transmission rates, and these terminals use various antenna methods and locations. A comparatively large terminal antenna is required to handle high data transmission rates in a satellite system to mitigate the huge propagation loss. The high gain and narrow beam of a large antenna make a beam-scanning mechanism necessary to enable the antenna to follow the satellite direction as the terminal moves. The sixth selected paper describes a highly accurate and cost-effective auto-tracking antenna system for earth stations onboard vessels, using a novel inclinometer that is highly accurate in acceleration disturbance environments and a new systematic stabilization controller design process based on H_∞ control [3].

Table 4. Typical antennas in earth stations.

Satellite category	Typical satellite system	Current typical earth station antenna (size or length, gain)
LEO	Iridium Globalstar	Helical (0.1 m, 2 dBi) Linear whip (0.1 m, 0 dBi) Patch (0.1 m^2, 3 dBi)
MEO GEO	ICO N-STAR INMARSAT	Parabola (0.6 – 0.9 m, 18 – 21 dBi) Phased patch array (0.5 m^2, 14 dBi) Helical (0.3 m, 2 dBi) Patch array (0.3 m^2, 12 dBi) Patch (0.1 m^2, 3 dBi)

LEO: low earth orbit
MEO: medium earth orbit
GEO: geostationary earth orbit

4. Conclusion

This paper gave an overview of the requirements of antennas and antenna systems in recent high-speed and high-capacity wireless communication systems and the key technologies for satisfying these requirements to create next-generation wireless communications. It also described current antenna systems and NTT's antenna research results for typical wireless systems.

Antennas for next-generation wireless communications require high gain, high efficiency, and a multi-antenna design. A high-gain antenna can be made using a relatively large antenna aperture, but a beam-scanning mechanism is needed for mobile communications. A high-efficiency antenna can be made using an active integrated antenna, which integrates an MMIC with the antenna element. Multi-antenna technology is the innovative technology that enables multiple data transmission in space. In MIMO-type multi-antenna systems, the most important key technologies are the beamforming algorithm and the implementation method. The solution technologies for NTT's advanced antenna systems are explained in detail in the following selected papers in this issue. The technological background and the current research and development situation are also described to make the papers easy to understand.

References

[1] "Next-Generation Broadband Wireless Access Technologies," NTT Technical Review, Vol. 2, No. 1, pp. 12-63, 2004.

[2] N. Honma, T. Seki, and K. Tsunekawa, "Planar Beam-Scanning Microstrip Antenna Using Tunable Reactance Devices for Satellite Communication Mobile Terminal," NTT Technical Review, Vol. 3, No. 9, pp. 24-32, 2005.

[3] T. Yoshida, K. Ohata, and M. Ueba, "Highly Accurate and Cost-effective Auto-tracking Antenna System for Satellite Broadband Communication on Vessels," NTT Technical Review, Vol. 3, No. 9, pp. 60-71, 2005.

[4] T. Seki, K. Nishikawa, I. Toyoda, and K. Tsunekawa, "Millimeter-wave High-Efficiency Multilayer Parasitic Microstrip Antenna Array for System-on-package," NTT Technical Review, Vol. 3, No. 9, pp. 33-41, 2005.

[5] Y. Takatori, R. Kudo, K. Nishimori, and K. Tsunekawa, "Beamforming Method for Broadband MIMO-OFDM Systems," NTT Technical Review, Vol. 3, No. 9, pp. 42-49, 2005.

[6] K. Nishimori, R. Kudo, Y. Takatori, and K. Tsunekawa, "Experimental Evaluation of 8 × 4 Eigenmode SDM Transmission in Broadband MIMO-OFDM Systems," NTT Technical Review, Vol. 3, No. 9, pp. 50-59, 2005.

[7] J. D. Kraus, "Antennas, Sec. 2: Basic Antenna Concepts," McGraw-Hill Book Company, 1988.

[8] R. C. Hansen, "Fundamental limitations in antennas," Proceedings of the IEEE, Vol. 69, Issue 2, Feb. 1981.

[9] A. Alexiou and M. Haardt, "Communications smart antenna technologies for future wireless systems: trends and challenges," Magazine, IEEE, Vol. 42, Issue 9, pp. 90-97, Sep. 2004.

[10] S. S. Basat, K. Lim, J. Laskar, and M. M. Tentzeris, "Design and Modeling of Embedded 13.56 MHz Rfid Antennas," IEEE AP-S Int. Antennas Propagat. Symp. Dig.,Vol. 4, Session 130, pp. 64-67, 2005.

[11] U. Karthaus and M. Fischer, "Fully integrated passive UHF RFID transponder IC with 16.7-/spl mu/W minimum RF input power," Solid-State Circuits, IEEE Journal of Vol. 38, Issue 10, pp. 1602-1608, Oct. 2003.

[12] T. Seki, F. Nuno, K. Nishikawa, and K. Cho, "Active Integrated Antenna Technique," NTT Technical Review, Vol. 2, No. 1, pp. 36-43, 2004.

[13] T. Ihara and K. Fujimura, "Research and development of millimeter-wave short-range application systems," Trans., IEICE, Vol. E79-B, No. 12, pp. 1741-1753, Dec. 1996.

[14] W. Menzel, D. Pilz, and M. Al-Tikriti, "Millimeter-wave folded reflector antennas with high gain, low loss, and low profile," IEEE Antennas and Propagation magazine, pp. 24-29, June 2002.

[15] M. J. M. van der Vorst, P. J. I. de Maagt, A. Neto, R. M. Heeres, W. Luinge, and M. H. A. J. Herben, "Effect of internal reflections on the radiation properties and input impedance of integrated lens antennas-comparison between theory and measurements," Microwave Theory and Techniques, IEEE Trans. on 49, Issue 6, Part 1, pp. 1118-1125, June 2001.

[16] T. Seki, K. Uehara, and K. Kagoshima, "A Three-Dimensional Active Antenna for a High-Speed Wireless Communication Application," IEEE MTT-S Int. Microwave Symp., Denver, USA, Vol. 2, pp. 975-978, June 1997.

[17] G. J. Foschini, G. D. Golden, R. A. Valenzuela, and P. W. Wolniansky, "Simplified processing for high spectral efficiency wireless communication employing multi-element arrays," IEEE Journal on Vol. 17, Issue 11, pp. 1841-1852, Nov. 1999.

[18] N. Honma, F. Kira, T. Maruyama, K. Cho, and H. Mizuno, "Compact six-sector antenna employing patch Yagi-Uda array with common director," Antennas and Propagation Society International Symposium 2002, IEEE, Vol. 1, pp. 26-29, June 2002.

[19] N. Honma, T. Seki, K. Tsunekawa, F. Kira, and K. Cho, "Compact Multi-Sector Antenna Employing Microstrip Yagi-Uda Array Antenna with Common Director Elements," IEICE Trans. B, Vol. J87-B, No. 9, pp. 1363-1371, Sep. 2004 (in Japanese).

[20] T. Hori, K. Cho, Y. Takatori, and K. Nishimori, "Key techniques for actualizing smart antenna hardware," Antennas and Propagation Society International Symposium 2000, IEEE, Vol. 2, pp. 948-952, July 2000.

[21] K. Uehara, Y. Takatori, and K. Kagoshima, "Proposal for a novel beam combination method for indoor high-speed wireless communication systems," Vehicular Technology, IEEE Transactions on Vol. 48, Issue 5, pp. 1511-1517, Sep. 1999.

[22] K. Nishimori, K. Cho, Y. Takatori, and T. Hori, "A Novel Configuration for Realizing Automatic Calibration of Adaptive Array Using Dispersed SPDT Switches for TDD Systems," IEICE Vol. E84-B, No. 9, pp. 2516-2522, Sep. 2001.

[23] K. Nishimori, and K. Cho, "Evaluation of SDMA employing vertical pattern and polarization control in actual cellular environment measurement," Vehicular Technology Conference 2004, VTC 2004-Spring, 2004 IEEE 59th Vol. 1, pp. 244-248, May 2004.

[24] A. Paulraj, R. Nabar, and D. Gore, "Introduction to space-time wireless communications," Cambridge, U.K., Cambridge Univ. Press, 2003.

[25] M. Ueba, K. Ohata, J. Mitsugi, and M. Umehira, "Broadband and scalable mobile satellite communication system for future access networks," 22nd AIAA ICSSC, AIAA 2004-3154.

Koichi Tsunekawa

Senior Manager, Executive Research Engineer, Wireless Systems Innovation Laboratory, NTT Network Innovation Laboratories.

He received the B.S., M.S., and Ph.D. degrees in engineering science from the University of Tsukuba, Tsukuba, Ibaraki in 1981, 1983, and 1992, respectively. He joined the Electrical Communications Laboratories of Nippon Telegraph and Telephone Public Corporation (now NTT), Tokyo in 1983. Since 1984, he has been engaged in R&D of portable telephone antennas in land mobile communication systems. From 1993 to 2003, he was with NTT DoCoMo, Inc. where he worked on radio propagation research, intelligent antenna systems for wireless communications, and the development of IMT-2000 antenna systems. His research interests are antenna systems for MIMO transmission, millimeter-wave broadband access, and ubiquitous wireless system. He is a member of IEEE and IEICE.

Communications and Network, 2016, 8, 9-21
Published Online February 2016 in SciRes. http://www.scirp.org/journal/cn
http://dx.doi.org/10.4236/cn.2016.81002

The Roles of 5G Mobile Broadband in the Development of IoT, Big Data, Cloud and SDN

Bao-Shuh Paul Lin[1,2], Fuchun Joseph Lin[1,2], Li-Ping Tung[1]

[1]Microelectronics & Information Research Center, National Chiao Tung University, Taiwan
[2]College of Computer Science, National Chiao Tung University, Taiwan
Email: bplin@mail.nctu.edu.tw, fjlin@nctu.edu.tw, lptung@nctu.edu.tw

Received 3 November 2015; accepted 22 February 2016; published 25 February 2016

Copyright © 2016 by authors and Scientific Research Publishing Inc.
This work is licensed under the Creative Commons Attribution International License (CC BY).
http://creativecommons.org/licenses/by/4.0/
Open Access

Abstract

The fast technology development of 5G mobile broadband (5G), Internet of Things (IoT), Big Data Analytics (Big Data), Cloud Computing (Cloud) and Software Defined Networks (SDN) has made those technologies one after another and created strong interdependence among one another. For example, IoT applications that generate small data with large volume and fast velocity will need 5G with characteristics of high data rate and low latency to transmit such data faster and cheaper. On the other hand, those data also need Cloud to process and to store and furthermore, SDN to provide scalable network infrastructure to transport this large volume of data in an optimal way. This article explores the technical relationships among the development of IoT, Big Data, Cloud, and SDN in the coming 5G era and illustrates several ongoing programs and applications at National Chiao Tung University that are based on the converging of those technologies.

Keywords

5G, Internet of Things (IoT), Software Defined Networks (SDN), Big Data Analytics, Cloud Computing

---

1. Introduction

The roles of SDN, Cloud, IoT, and Big Data in 5G Networks have raised great interest recently [1]. According to the IEEE Computer Society (IEEE CS 2022 Report [2]), Cloud Computing (Cloud), Big Data Analytics (Big Data), Internet of Things (IoT), and Software Defined Networks (SDN) are among 4 of 20+ emerging technologies as illustrated in **Table 1**. In the meantime, based on the report in IEEE Communications Society (IEEE ComSoc Technology News [3]), among top 10 trends in 2015 as listed in **Table 2**, 5G, Virtualization (SDN & NFV), everywhere connectivity for IoT & IoE, and Big Data are also included. Combining both reports, we can identify 5G, Cloud, IoT/IoE, Big Data, and SDN as the five most worthwhile ICTs (information & communica-

How to cite this paper: Lin, B.-S.P., Lin, F.J. and Tung, L.-P. (2016) The Roles of 5G Mobile Broadband in the Development of IoT, Big Data, Cloud and SDN. *Communications and Network*, **8**, 9-21. http://dx.doi.org/10.4236/cn.2016.81002

Table 1. IEEE computer society 2022 report.

Technology & Indexing Terms		
1. Security Cross-Cutting Issues	9. Multicore	17. 3D Printing
2. Open Intellectual Property Movement	10. Photonics	18. Big Data and Analytics
3. Sustainability	11. Networking and Interconnectivity	19. Machine Learning and Intelligent Systems
4. Massively Online Open Courses	12. Software Defined Networks	20. Life Sciences
5. Quantum Computing	13. High Performance Computing	21. Computational Biology and Bioinformatics
6. Device and Nanotechnology	14. Cloud Computing	22. Robotics
7. 3D Integrated Circuits	15. Internet of Things	
8. Universal Memory	16. Natural User Interfaces	

Table 2. IEEE communications society top 10 trends 2015.

1) 5G
2) FIBER EVERYWHERE
3) VIRTUALIZATION, SDN & NFV
4) EVERYWHERE CONNECTIVITY FOR IoT & IoE
5) BIG DATA, COGNITIVE NETWORKS
6) CYBERSECURITY
7) GREEN COMMUNICATIONS
8) SMARTER SMARTPHONES, CONNECTED SENSORS
9) NETWORK NEUTRALITY, INTERNET GOVERNANCE
10) MOLECULAR COMMUNICATIONS

tions technologies) to watch out up to 2020 in term of their potential, convergence and applications. **Figure 1** depicts the overlapping of these five major ICT trends. It also illustrates how the infrastructure deployment of 5G mobile broadband and the architectural integration of Cloud Computing strongly impact the development of IoT, Big Data, and SDN. This paper explores the technical relationships of these five areas and discusses several ongoing programs and applications currently under development at NCTU based on these technologies.

2. The Roles of 5G, IoT, Big Data, Cloud, and SDN till 2020

Although so far the 5G mobile broadband requirements and standard specifications are not ready yet, 5G technology research & development are already started and some 5G features or subsystems are readily available. By Year 2020 the commercial 5G will be available and IoT applications will be deployed everywhere with mobile broadband technology. Moreover, the Big Data generated by IoT applications will become a norm and Cloud will be largely utilized to compute, store and virtualize network functions (NFV). Also, the underlying network infrastructure will adopt SDN to reduce both capital expense (CAPEX) and operational expense (OPEX). **Figure 2** further illustrates the roles of 5G, IoT, Big Data, Cloud and SDN and their relationships. This figure is modified based on the reference [4] by inserting 5G mobile broadband in the center.

3. Technical Relationships among IoT, Big Data, Cloud, & SDN in 5G Era

Based on **Figure 2**, we develop **Figure 3** to better explain the technical relationships among IoT, Big Data, Cloud, and SDN in the 5G mobile broadband services (5G MBS) [5]. First, IoT is capable of generating Big Data with four Vs: volume, velocity, variety and veracity. Then, Cloud is brought in for Big Data storage and processing. Finally, SDN is employed to provide more efficient and flexible networks for inter-Cloud data transport. Out of Big Data, Cloud, and SDN, advanced technologies such as machine learning analytics, Cloud


IEEE ComSoC, 2015
IEEE CS 2014
Fiber everywhere
Cybersecurity
Network Neutrality
Molecular Comm.
5G
Smarter Smartphones/ Connected Sensors
Green Communications
SDN/NFV
IoT/IoE
BigData
3D Printing, 3D IC
Cloud Computing
Multicore
HPC
Quantum Computing
Sustainability
ICT : Information & Communication Technology

Figure 1. ICT major trends for 2015-2020.


INTERNET OF THINGS
BIG DATA
5G Mobile Broadband and Telecom Networks
010101 11001 001
SDN
CLOUD

Figure 2. Relationship among 5G, IoT, Big Data, Cloud and SDN based on [4].

RAN and softwarized 5G then are developed.

As illustrated in **Figure 4**, 5G will serve as a better gateway and transport network for IoT applications so that IoT data can be delivered more efficiently and economically. In addition, IoT will become one of the major sources of Big Data by producing large volume, fast velocity, and many varieties of data [6] as illustrated in **Figure 5**.

Finally, **Figure 6** shows that Cloud can be adopted in the 5G Radio Access Network (RAN) and turns it to a Cloud-based RAN (C-RAN). Both SDN and NFV have been applied to data center in the cloud to enable better load balance and resource allocation of the cloud. SDN has also been applied to 5G mobile broadband core networks to enable smart routing, better traffic management and improve network resource utilization.


Make data cheaper & faster
Route Traffic & network resources utilization
IoT
Volume Velocity, Variety , Veracity
SDN 5G
5G S/W Apps
SDN
5G MBS
Big Data
Analytics
Value : valuable for information
Need cloud storage & Cloud Computing
Cloud
Need cloud SDN Integration
Cloud RAN (C-RAN)
Mobile Cloud-Computing

Figure 3. Technical relationships among 5G & IoT, Big Data, Cloud, and SDN.


Networks
Services Platform
4G/5G RAN as Gateway
Applications
Sensor Devices for BigData

Figure 4. 4G/5G as the gateway for IoT applications.


Data Streaming
Velocity
Big Data characteristics
Smart Home
D2D Small Data
Volume
IoT
Variety
D2D Small Data
Big Data
Output quality
Smart City
Veracity

Figure 5. Relationships between IoT and Big Data.



Figure 6. C-RAN architecture in 5G mobile network.

4. Ongoing Programs and Applications at National Chiao Tung University (NCTU)

In this section, we describe five ongoing programs and applications at NCTU that are closely related to the SDN, Cloud, Big Data, IoT, and 5G technologies [7]-[17].

4.1. Program on SDN-Enabled Cloud-Based Broadband and Wireless Network Technologies and Services

This program is a national program to support the SDN Industry-Academia Cooperation, led by both NCTU and CHT (Chunghwa Telecom, the largest mobile & telecom operator in Taiwan) with 5 other networking and communications companies in Taiwan. This is a multi-year program with the target to set up a testbed for end-to-end testing and to help establish an ecosystem for local SDN industry.

Figure 7 shows the scope of this program that covers mobile access, WiFi access, broadband core and data center cloud end-to-end application systems.

Figure 8 further shows both the structure of the program and its network configuration across NCTU, CHT and another university National Tsing Hwa University (NTHU).The program includes research and development involving 4G/LTE, B4G/5G, SDN, Cloud, SDN for Wi-Fi, and SDN for WAN technologies. There are five sub-programs: 1) SDN broadband network technologies and services, 2) SDN mobile/wireless network technologies and services, 3) SDN and cloud integration services and management, 4) SDN switch-related devices and systems and 5) SDN system integration and field trials.

The program is intended to construct an SDN network in NCTU, CHT and NTHU, respectively. These SDN networks then will be interconnected to form a wide area SDN network in Taiwan. Eventually, we plan to have this end-to-end system connected to the global network. The SDN switches deployed in this testbed will be mostly small or medium scale due to their experimental nature. Also included in this testbed are SDN-based Wi-Fi access points. Cloud-based data centers will be deployed in each location of NCTU, CHT and NTHU. Three types of SDN controllers including OpenDaylight, Ryu and Floodlight are currently under trial in the experimental network. Our architecture assumes the scenario of multiple SDN controllers with a hierarchical topology on which useful SDN APPs such as load balancer, network optimizer for video delivery, network co-ordinator (including visualization), dynamic flow configuration, end-to-end service configuration, dynamic policy-based traffic engineering, and multitenant network automation can be developed and deployed.

4.2. Program on Big Data Analytics for Network Traffic and Management Data

In this program, we address the network performance issues with two experimental networks: BML at NCTU campus and ITRINET of ITRI.

The architecture of the BML experimental network is illustrated in the lower part of **Figure 9** that consists of a 4G RAN, a 4G Core and a Cloud environment. For the 4G RAN, both indoor and outdoor environment are taken into consideration. The left upper part of **Figure 9** shows the scope of the ITRINET experimental network


SDN System Integration and Benchmarking
SDN Broadband Network Technologies
SDN Mobile /Wireless Technologies
Fixed
OpenFlow CPE
SDN Controllers
SDN APP
Northbound API
Cloud & SDN Env.
Open vSwitch
Open vSwitch
Net virual emulator
openstack
Crop Net
Wirekess
OpenFlow WiFi
STB
Cloud/SDN Integration, Service and Management
Nobile
TL Core Network
S-GW
S-GW
P-GW
UE
eNodeB
Terminals for SDN
Small SDN Env. (Small OpenFlow s/w)
Mid. SDN Env. (Mid. OpenFlow S/w)
Internet
Other SDN Exp. Networking
SDN 5G Mobile Technologies
Core Technologies of SDN HW/OS Design

Figure 7. Applications of SDN & cloud in 4G/LTE & 5G wireless networks.


(Main prog.)
SDN-enabled Cloud-based Wireless and Broadband Network Tech.& Services
(Subp. A)
SDN Broadband Network Technologies & Services
(Subp. B)
SDN Mobile/Wireless Network Technologies & Services
(Subp. C)
SDN and Cloud Integration Service & Management
(Subp. D)
SDN Switch-related Devices and Systems
(Subp. E)
SDN System Integration and Field Trials
Fixed
OpenFlow CPE
Wireless
OpenFlow WiFi
Mobile
TL Core Network
UE
終端SDN環境
SDN APP
SDN Controllers
Data Center
Corp. Net.
Cloud SDN Env.
x4
x2
Small SDN Env. (small OpenFlow Switch)
Mid. SDN Env. (Mid. OpenFlow Switch)
Internet
SDN Master Controllers
中華電信 Chunghwa Telecom
Internet
SDN Core Switch (中型OpenFlow Switch)
Data Center
Cloud &SDN
SDN APP
SDN Controllers
Fixed
OpenFlow CPE
Wireless
OpenFlow WiFi
Mobile
NCTU Core Net. emulator
UE
Terminals for SDN
x2
Internet
Mid. SDN Env. (Mid. OpenFlow Switch)
x4
Small(small OpenFlow Switch)
Data Center
Cloud SDN Env.
Fixed
OpenFlow CPE
Wireless
OpenFlow WiFi
SDN APP
SDN Controllers
x2
Mid. SDNEnv. (Mid. OpenFlow Switch)
x4
Small SDN環境 (Small OpenFlow Switch)
Internet
國立交通大學 National Chiao Tung University
國立清華大學 National Tsing Hua University

Figure 8. SDN technical R&D center and projects at NCTU.

that covers a much greater area of Hsinchu County than NCTU and includes additionally ITRI (Industrial Technologies Research Institute), HSIP (Hsinchu Science Industrial Park) and THR (Taiwan High-speed Rail, Hsinchu station). The right upper part of **Figure 9** illustrates how ITRINET covers various R&D buildings in the corporate campus of ITRI such as B11, B12, B51, etc.

Figure 10 illustrates how Big Data analytics based on InfoSphere or Spark is performed on ITRINET for the purpose of network optimization. First, network traffic measurement and network management data are collected.


Hsinchu Field
Taiwan High Speed Rail (THSR)
National Chiao Tung University
ITRI
Hsinchu Science Park
B14
FDD
ITRI Chung-Hsing campus
B11
TDD
FDD
B53
B52
TDD
B51
Internet
Cloud Platform
(Inventec Zion)
Application Server
Cloud
EPC / Core
Network
4G
Core
eNB (TDD)
(NSN, ITSC)
eNB (TDD/FDD)
(NSN/HUAWEI, MIRC 103)
eNB (TDD)
(NSN, MIRC 511)
eNB (TDD/FDD)
(HUAWEI, MIRC 604)
4G
RAN
Outdoor
Indoor

Figure 9. Greater Hsinchu 4G/LTE & Future 5G experimental network ITRINET (include ITRI, NCTU, THR & HSIP).

Then, data analytics methods based on machine learning, data mining and statistical modeling are applied to analyze the collected data. Finally, we apply the results thus generated to network performance evaluation and optimization by providing a feedback loop for system re-configuration. The whole operational cycle includes the technologies of 4G/LTE, B4G/5G, Big Data Analytics, Cloud, and Traffic Engineering.

4.3. Application on IoT Platform Integrated with Data Generation and Data Analytics

This is an application where we set up an IoT platform integrated with data generator and data analytics capabilities as illustrated in **Figure 11**. A common challenge for IoT/M2M service providers is how to test their large scale IoT/M2M applications with the near realistic data that the system will handle in a production environment. As such tests may involve not only a large number but also a large variety of sensors, deploying a testing environment that contains all the necessary sensors turns out to be an infeasible, if not impossible job. To tackle this problem, we develop a data generation method (illustrated in the lower part of **Figure 11**) based on streams generation capabilities of IBM InfoSphere and Spark to emulate data from a large number and a large variety of sensors. Such generated data will be sent into and processed by the applications residing on the IoT/M2M


Hsinchu Field
Taiwan High Speed Rail (THSR)
National Chiao Tung University
Hsinchu Science Park
ITRI Chung-Hsing Campus
B14
B11
B53
B52
B51
EPC Core Network
Network
Internet
Big Data Analytics Platforms: IBM InfoSphere Stream
Data Collection
Data Analytics
Result Description Based on Data Analytics
Network Traffic Measurement + Network Management Data
Data Analytics Algorithm
Network Performance Evaluation & Optimization
Machine Learning
Data Mining
Statistical Modeling
Other Data Analytics Method
System Configuration

Figure 10. Big Data analytics for Traffic engineering of ITRINET.


Analyzing Results from IoT/M2M Applications
Data Analytics Framework
IBM InfoSphere Data Analytics
Analyze
Data Set 1
Data Set 2
Data Set 3
Data Set 4
。。。
Data Set N
Application 1
Application 2
Application 3
Application 4
。。。
Application N
Application Layer
IoT/M2M Platform
IoT/M2M System under Test
Sensor
Device
Emulate
IBM InfoSphere Data Streams
Data Generator Framework
Domain Knowledge
Properties of the IoT/M2M system
Data Type & Structure
Generating Large Volume and Fast Velocity Streaming Data

Figure 11. IoT platform integrated with data generation and data analytics.

platform (illustrated in the middle part of **Figure 11**). Finally, the data sets produced by the IoT/M2M applications are analyzed by data analytics engines in IBM InfoSphere and Spark (illustrated in the upper part of **Figure 11**).

The effectiveness of our data generation methodology is first verified in a people management system of a large factory environment. With our methodology, we are able to test our factory management IoT/M2M application more efficiently without actually deploying a large number and a large variety of sensors. This application development uses both IoT and Big Data Analytics.

4.4. Application on Data Analytics for Traffic Generated by Testing & Measurement

The automatic Testing & Measurement (T&M) of DUT (Device under Test, including 4G/LTE SD, UE/CPE) for 4-Stage (namely, conformance, interoperability, operator-IOT and field trials) testing is shown in **Figure 12**.

We apply the data analytics learning techniques for the classification of the DUT types by series numbers or id. Once the type is identified, the parameters for feature extraction can be measured by the testing and measurement equipment. An example for DUT classification is shown in **Table 3**. In this example, the DUT type relational table is a 4 × 4 table with 4 fields: 1) DUT Device Type, 2) UE capability Information (FGI), 3) DNS (TTL), and 4) HTTP (User Agent). This device relational table is created by applying multivariate statistical analytics on the network traffic flow and LTE UE connection related information. Then by extracting specific features, we are able to identify the types of DUT such as Dongle, Smartphone, CPE, etc.



Figure 12. Data generation by endpoints from testing & measurement.

Table 3. DUT relational table.

DUT Device Type	UE FGI	DNS-TTL	HTTP-User Agent
Dongle A	0100 0110 0000 0101 0001 1000 0000 0000	128	Mozilla/5.0 (Windows NT 6.1; WOW64) AppleWebKit/537.36 (KHTML, like Gecko) Chrome/43.0.2357.134 Safari/537.36\r\n
Dongle B	0101 1111 0000 1111 1111 1100 1000 0000	63	Mozilla/5.0 (Windows NT 6.1; WOW64) AppleWebKit/537.36 (KHTML, like Gecko) Chrome/43.0.2357.134 Safari/537.36\r\n
Smart Phone	0101 1110 0000 1101 1101 1000 1000 0000	43	iPhone6,2/8.3 (12F70)\r\n
CPE	0101 1111 0000 1111 1111 1100 1000 0000	127	Mozilla/5.0 (Windows NT 6.1; WOW64) AppleWebKit/537.36 (KHTML, like Gecko) Chrome/43.0.2357.134 Safari/537.36\r\n

Another example of applying data analytics in T&M traffic is to evaluate LTE QoS. When evaluating LTE QoS, it is required to setup testing scenarios with different QoS levels. Traffic Flow Template (TFT) (as shown in **Table 4**) is designed to filter packets into correspondent bearers, either a default bearer or dedicated bearer, in LTE network. Each bearer has its own QoS level. We can establish a dedicated bearer of guarantee bit rate (GBR) for applications such as VoIP, or a default bearer of basic QoS level for applications like file transfer.

What TFT does is to filter packets into correspondent bearers according to packets' IP address, port number, protocol, direction. The information, however, is insufficient to differentiate among web file download, FB news browsing, and Line chat. We are unable to give different QoS levels to these applications. To tackle this problem, we propose a new architecture which integrates deep packet inspection (DPI) with TFT to provide a higher granularity of QoS levels for applications. When some traffic flow has been identified as a certain application type, TFT will be informed to update rules of packet filters. With this improved method, the traffic flow can be delivered through the bearer of suitable QoS level.

4.5. Applications on Data Analytics for Traffic Flow Created by APP's of SD

To fulfill the Quality of Service (QoS) requirements from users, it is important to make effective use of the network resource. We can optimize the performance of a network by applying data analytics to traffic engineering. In particular, it is important to classify mobile applications traffic intended by the user with data analytics.

We propose a HMM-based (Hidden Markov Model) model to classify the mobile applications. By surveying related work, we have realized that there are different handshake patterns of well-known application protocols. Also, according to the observation of some specific mobile applications, we discover that every mobile Internet service has its unique negotiation process at the beginning when service starts. HMM was widely used to recognize time-dependent sequences and find out unknown patterns of data, such as speech recognition, handwriting recognition.

Table 4. Traffic Flow Template (TFT): Use to specify the packet filters associated.

UL Packet Filter ID	DRB	Packet Filter Evaluation Precedence	Protocol Number (IPv4)/ Next Header (IPv6)	Remote Address and Subnet Mask	Single Local Port (UE)	Local Port Range (UE)	Single Remote Port Range (NW)	Remote Port Range (NW)	IPSec SPI Range	Type of Service (IPv4)/ Traffic Class (IPv6) and Mask	Flow Label (IPv6)
1	DRB2	6	6 (TCP)	IPv4: 172.168.8.0 [255.255.255.0] IPv6: 2001:0ba0::[ffff:ffff::]	60051	-	-	-	-	-	-
2	DRB2	2	17 (UDP)	-	-	-	60201	-	-	-	-
3	DRB3	7	6 (TCP)	IPv4: 172.168.8.0 [255.255.255.0] IPv6: 2001:0ba0::[ffff:ffff::]	-	60100:60200	-	-	-	-	-
4	DRB3	3	17 (UDP)	-	-	-	-	60300: 60400	-	-	-
5	DRB3	5	50 IPSec (ESP)	-	-	-	-	-	0x0F80F0000	-	-
6	DRB3	1	-	-	-	-	-	-	-	00101000, Mask = 11111100	-
7	DRB3	6	-	-	-	-	-	-	-	-	-
8	DRB1 (default bearer)	255	6 (TCP)	-	-	-	-	-	-	-	-

In our method, we extract the packet size sequence and packet transmission direction sequence of the first 20 packets to train the HMM model. **Figure 13** shows our designed model structure of HMM. X_n is the hidden variable. It represents the transmission states which cannot be observed directly. Because of the unknown transmission states, we need to use observation variable O_n^1 and O_n^2 as training features to build the mobile application models. Here, "*n*" is the sequence number of packets in a traffic flow. O_n^1 is the observation symbol of packets transmission direction. O_n^2 is the observation of packet size that quantizes to a certain range of packet size. We quantize smallest packet size to number 1 and largest packet size to number 8. The rest of packet sizes are then divided into six groups.

Figure 14 shows the main process of our classification system. First, we process the collected packets by reading from original PCAP files, and extract the necessary field of packet header, including source IP, destination IP, source port number, destination port number, packet timestamp, and packet size. Second, we use packet


X_n
X_{n+1}
O_n^1
O_n^2
O_{n+1}^1
O_{n+1}^2
the n^th packet
the (n+1)^th packet
X_n : state of the n^th packet (Hidden Variable)
O_n^1 : the packet direction (Observation Variables)
O_n^2 : that packet size quantizes to corresponding group (Observation Variables)

Figure 13. Classification model of Internet application traffic.



1. PCAP File Processing

Original packet → processing data
- SRC_IP / DST_IP
- SRC_PORT / DST_PORT
- Timestamp
- Packet size

2. Feature Extraction

First 20 packets of each flow
- Packet Direction
  1: Client → Server
  2: Server → Client
- Packet size
  Quantize to corresponding group

3. Learning Process

HMM Parameter Estimation
- Using EM algorithm

Application Training Model
- Each application has its own model

$\lambda^1 = \{\pi_1, A_1, B_1\} \ldots \lambda^N = \{\pi_N, A_N, B_N\}$

4. Recognizing Process

Find Maximum Probability
- Observation of testing data: O^{test}

$P(O^{test} \mid \lambda^1) \ldots P(O^{test} \mid \lambda^N)$

Max value of all training model

Figure 14. The process of our proposed classification system.

header information (5-tuple: source IP, destination IP, source port number, destination port number, and protocol) to process packets with the same 5-tuple information into a unit of mobile application traffic flow, and extract the features of each application flow. Third, in learning process, we use the extracted features which are quantized into corresponding symbol sequence to training the HMM-based application models for different applications. Finally, we can identify the new traffic flow by finding out the maximum value of log likelihoods derived from different application models.

5. Conclusion

This paper presents a forward looking view of the convergence of IoT, big data, cloud, SDN technologies along with the arrival of 5G mobile broadband networks. We intend to demonstrate the technical relationships of those technologies and the compelling programs and applications that can be created when two, three or more of those technologies converge. Due to the nature of fast evolution of ICT and the ongoing innovation of those five technologies, this paper should be updated on annual basis to keep the related information up to day with the ICT major trends.

Acknowledgements

This work was supported by the Ministry of Science and Technology (MOST) of Taiwan and National Chiao Tung University under grants: MOST 103-2622-E-009-012-, 103-2221-E-009-138-, 103-2218-E-009-032-, 104-2221-E-009-023- and NCTU-ICTL 104Q707.

References

[1] Lin, B-S.P. (2015) The Roles of SDN, Cloud, IoT, & Big Data, in 5G Networks and Their Technical Relationships & Applications. Invited Talk, IEEE VTS APWCS 2015, Singapore.

[2] Alkhatib, H., *et al*. (2015) IEEE CS 2022 Report. IEEE Computer Society, IEEE.

[3] Neira, E.M. (2015) IEEE ComSoc CTN Special Issue on Ten Trends That Tell Where Communication Technologies are Headed in 2015.

[4] Tucker, L. (2013) On the Cloud of the Future. Cloud Computing Summit, San Jose.

[5] Kleiner, T. (2015) 5G Research in Horizon 2020.

[6] Thadani, A. and Andreoli, P. (2014) Realizing Business Value from Convergence of IoT + Big Data Technologies. 2014 *Midwest Architecture Community Collaboration* (*MACC*) *Conference*, Minneapolis, 13 November 2014.

[7] Dinh, H.T., Lee, C., Niyato, D. and Wang, P. (2013) A Survey of Mobile Cloud Computing: Architecture, Applications, and Approaches. *Wireless Communications and Mobile Computing*, **13**, 1587-1611. http://dx.doi.org/10.1002/wcm.1203

[8] Lin, B-S.P., *et al.* (2013) The Design of Cloud-based 4G/LTE for Mobile Augmented Reality with Smart Mobile Device. *Proceedings of* 2013 *IEEE International Symposium on Mobile Cloud, Computing, and Service Engineering* (*IEEE Mobile Cloud* 2013), Redwood City, 25-28 March 2013, 561-566. http://dx.doi.org/10.1109/sose.2013.57

[9] Lin, B.-S.P., Tung, L-P., Hsieh, I-C., Liu, T-H. and Chou, S-Y. (2015) The Design of Big Data Analytics for Testing & Measurement and Traffic Flow on an Experimental 4G/LTE Network. *Proceedings of IEEE WOCC* 2015, Taipei, 23-24 October 2015, 40-44. http://dx.doi.org/10.1109/wocc.2015.7346173

[10] Lin, B-S.P., Tung, L-P., Hsieh, I-C. and Chou, S-Y. (2015) Performance Estimation of MAR for Outdoor Navigation Applications on an 5G Mobile Broadband by Mobile Smart Devices. *Proceedings of IEEE APWCS* 2015, Singapore, 19-20 August 2015, 1-6.

[11] Lin, F.J., Ren, Y. and Cerritos, E. (2013) A Feasibility Study on Developing IoT/M2M Applications over ETSI M2M Architecture. *Proceedings of the* 1st *International Workshop on Internet of Things Technologies* (*IoTT*), Seoul, 15-18 December 2013, 558-563. http://dx.doi.org/10.1109/icpads.2013.100

[12] Chen, H.W. and Lin, F.J. (2014) Converging MQTT Resources in ETSI Standards Based M2M Platform. *Proceedings of IEEE iThings*, Taipei, 1-3 September 2014, 292-295. http://dx.doi.org/10.1109/ithings.2014.52

[13] Cerritos, E. and Lin, F.J. (2014) M2M-Enabled Real-Time Trip Planner. *Proceedings of the* 2nd *International Workshop on Internet of Things Technologies* (*IoTT*), Hsinchu, 16-19 December 2014, 886-891. http://dx.doi.org/10.1109/padsw.2014.7097902

[14] Lusiarta Putera, C.A. and Lin, F.J. (2015) Incorporating OMA Lightweight M2M Protocol in IoT/M2M Standard Architecture. *Proceedings of IEEE World Forum on IoT*, Milan, 14-16 December 2015, 559-564.

http://dx.doi.org/10.1109/WF-IoT.2015.7389115

[15] Adrianto, D. and Lin, F.J. (2015) Analysis of Security Protocols and Corresponding Cipher Suites in ETSI M2M Standards. *Proceedings of IEEE World Forum on IoT*, Milan, 14-16 December 2015, 777-782. http://dx.doi.org/10.1109/wf-iot.2015.7389152

[16] Lin, F.J. and Chen, H. (2015) Improving Utilization and Customer Satisfaction of Parking Space with M2M Communications. *Proceedings of IEEE World Forum on IoT*, Milan, 14-16 December 2015, 465-470.

[17] Lin, F.J., Tsai, W., Cerritos, E., Lin, B.-T. and Hu, W.-H. (2015) Identification and Analysis of Charging Factors in M2M Communications. *Proceedings of IEEE World Forum on IoT*, Milan, 14-16 December 2015, 160-165. http://dx.doi.org/10.1109/wf-iot.2015.7389045

Hindawi
Wireless Communications and Mobile Computing
Volume 2018, Article ID 6309509, 20 pages
https://doi.org/10.1155/2018/6309509

Research Article

A Model of Socially Connected Web Objects for IoT Applications

Sajjad Ali,[1] **Muhammad Golam Kibria**,[1] **Muhammad Aslam Jarwar**,[1]
Hoon Ki Lee,[2] **and Ilyoung Chong**[1]

[1] *Department of Information and Communications Engineering, Hankuk University of Foreign Studies, Yongin-si, Republic of Korea*
[2] *Electronics and Telecommunications Research Institute (ETRI), Daejeon, Republic of Korea*

Correspondence should be addressed to Ilyoung Chong; iychong@hufs.ac.kr

Received 2 September 2017; Revised 26 November 2017; Accepted 19 December 2017; Published 28 January 2018

Academic Editor: Nathalie Mitton

Copyright © 2018 Sajjad Ali et al. This is an open access article distributed under the Creative Commons Attribution License, which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

The Internet of Things (IoT) is evolving with the connected objects at an unprecedented rate, bringing about enormous opportunities for the future IoT applications as well as challenges. One of the major challenges is to handle the complexity generated by the interconnection of billions of objects. However, Social Internet of Things (SIoT), emerging from the conglomeration of IoT and social networks, has realized an efficient way to facilitate the development of complex future IoT applications. Nevertheless, to fully utilize the benefits of SIoT, a platform that can provide efficient services using social relations among heterogeneous objects is highly required. The web objects enabled IoT environment promotes SIoT features by enabling virtualization using virtual objects and supporting the modularity with microservices. To realize SIoT services, this article proposes an architecture that provides a foundation for the development of lightweight microservices based on socially connected web objects. To efficiently discover web objects and reduce the complexity of service provisioning processes, a social relationship model is presented. To realize the interoperable service operations, a semantic ontology model has been developed. Finally, to evaluate the proposed design, a prototype has been implemented based on a use case scenario.

1. Introduction

The Internet of Things (IoT) envisions billions of objects connected to the Internet that continuously generate data about the physical environment. Several state-of-the-art applications can be built using the information and services provided by the pervasive and heterogeneous IoT objects. However, building applications based on these objects raises some challenges. Examples include how the growing number of objects will interact or coordinate to render valuable services, how the complexity generated by the coordination of objects can be handled, and how a large amount of diverse data sensed from the surroundings can be managed properly.

Numerous promising solutions have been provided to handle the complexity and the heterogeneity of IoT objects. One of the prominent approaches is to develop virtual environments to resolve the issues caused by the heterogeneous objects. Virtualization has become a key component in many IoT architectures, in the form of either virtual objects or virtual entities. A virtual object (VO) is defined as a digital representation of a real-world object [1] and provides a way for the IoT services to discover and compose features that cannot be achieved directly with a real-world object (RWO). It has been realized that issues such as heterogeneity of dissimilar objects and scalability can be effectively resolved using VOs. Hence, a crucial role of a VO is to bridge the gap between the physical world and the virtual world by hiding the physical characteristics of an IoT device and acquiring and interpreting its data and context.

Another way to reduce the complexity caused by a large number of objects is to link these objects in a social network [2], which provides a more exact solution than using a sole individual object. This principle has given birth to the concept of Social Internet of Things (SIoT), which is emerging as a new paradigm with the merger of social networks and IoT [3–7]. It has been realized as an efficient way to facilitate the development of complex future IoT applications. It supports sharing of information generated by the people and the devices based on the social relationships. These relationships further promote efficient discovery of the objects and effective service compositions.

Let us have a glimpse of the application scenarios in which SIoT will make a profound effect on our daily life in the near future. Imagine a group of vehicles that form a mobile social network on the move when heading towards the same location or when they are bound in a common relationship. Vehicles may form diverse social communities; for example, small cars create a social network to share available parking space information or bicycles share information about the vacant paths using a network [8]. Vehicles commuting from home to office can join a social network to share traffic congestion experience, accident warnings, or other common information (e.g., a meeting plan) with colleagues by accessing their vehicles' social network. Let us analyze another SIoT use case where a user enters a public museum with an IoT environment, which incorporates smart objects that exploit social relationships to share information. At the entrance to the premises, the user's smartphone is prompted with a beacon signal to recommend a service app installation. When the user grants the permission, an app is installed and a social agent acquires his profile and friendship details. The app incorporates a microservice which uses a smartphone object to establish a social relationship with the museum visit service. The museum is equipped with a network of smart objects that monitor the user's location and provide services to enhance his/her experience such as personalizing the displays, assisting in the navigation, and recommending the relevant services.

To support the above-mentioned use cases, most of the current IoT architectural approaches are not suitable as they are based on the traditional monolithic approaches, which further hinder the development of efficient, modular, and independent services that cannot scale well with the increasing user's service demands, as already witnessed in many studies [9–12]. Using monolithic approaches, we cannot fully achieve the benefits offered by SIoT including efficient information discovery, improved scalability, and simplified interconnection of objects.

These limitations motivate the current paper to define a design for the development of SIoT based services with efficient and lightweight mechanisms to exploit SIoT features for improved service provisioning. The proposed design is based on the microservices concept which promises a more solid practice of SOA. There is no particular definition of microservices architectural style; however, it is explained in [13] by Martin Fowler as "an approach to developing a single application as a suite of small services, each running in its own process and communicating with lightweight mechanisms, often an HTTP resource API." Following the microservices based proposed design, SIoT applications can be developed, deployed, and maintained more efficiently and independently, which will promote system modularity and interoperability.

Moreover, a SIoT design needs to facilitate the efficient information discovery based on the social relationships among objects. To achieve this, incorporating the existing social relationship models in the proposed design can be useful. However, applications with intelligent service features require dynamic object selection. Therefore, objects need to acquire the ability to infer new relationships for interconnection with other objects in the system. This view further motivates the present article to develop a social relationship model based on the semantic ontology. The utilized ontology-based approach is highly useful to dynamically infer new social relationships for efficient service provisioning.

Furthermore, to fully achieve the benefits of both, the SIoT and microservices, selecting an IoT environment is necessary where not only can the social interconnection among heterogeneous objects be utilized but also the lightweight services can be developed to apply these relationships for effective IoT service provisioning. To fulfill this goal, the Web of Objects (WoO) [14] platform has been selected. According to the ITU recommendation (ITU-T Y.4452) [15], "the Web of Objects (WoO) is a realization way of the IoT services, where virtualized objects (i.e., virtual objects (VOs) and composite virtual objects (CVOs)) are connected, controlled, and incorporated with resources to facilitate the development, deployment, and operation of IoT services on the World Wide Web."

To exploit the opportunities provided by the above discussed technological advancements, the main contributions are highlighted as follows:

(i) This article contributes a novel design based on the microservices concept with lightweight and modular services to support the development of SIoT applications. The proposed design involves mechanisms to enhance object discovery and to reduce the magnitude of complexity generated due to the huge number of objects.

(ii) A social relationship ontological model is developed, which helps identify the hidden and unidentified relationships among objects with reasoning mechanisms.

(iii) A use case with the implementation prototype based on the WoO platform is developed to exploit the social relationship model, supporting the proposed design for efficient IoT service provisioning.

Further, to support the above contributions, virtual objects, serving on real-world objects, have been developed, which can be reusable in other services as well. CVOs are implemented, where each update of the information in the real-world object is reflected in the VO and propagated to the CVO. Also, the Social IoT notion is incorporated into virtual objects to provide easy discovery and efficient execution while maintaining collaboration using social connections. Moreover, an experimental analysis has been carried out to evaluate the discovery time of VOs and the time required for service execution, with or without social relationships among virtual objects.

The remainder of this article is organized as follows. In Section 2, the related work is described. Section 3 presents the proposed design of the social web objects accompanied by the social interaction model. In Section 4, an IoT environment use case is explained with the details of the prototype implementation and discussion of the performance evaluation. Finally, Section 5 provides a conclusion of this paper.

2. Related Work

This section presents the related work with respect to the SIoT and microservices. Further, the significance of both technologies pertaining to the IoT environment has been discussed.

2.1. Social Internet of Things (SIoT). The concept behind SIoT is to enable smart objects to create a social network similar to a human social network. The objective is to exploit the social relationships among objects in an IoT environment to facilitate the effective information discovery, to promote the scalability, to enhance the interactive communication between objects that are friends, and to achieve trustworthiness [3].

The initial notion of a social network of objects was proposed by [16], which discussed how the wireless devices form social connections on the temporary bases that are controlled by the node owners. As the work was carried out before the introduction of IoT, it did not consider the SIoT concept. Later studies [5] investigated the objects' social interaction where objects formed social networks and communicated with each other based on the rules already set.

The idea of using the Web of Things in a social ecosystem was presented by [17, 18], where things were shared using the social network infrastructures, for example, Twitter, Facebook, and LinkedIn. These implementations consisted of objects that communicated either through the built-in embedded servers or through smart gateways. Further, in these settings, the web-enabled things owned by a person provided an interface to his/her social group of friends so that they can interact with the things using a social network.

Lysis [19] is another good example of Social IoT platform based on cloud infrastructure. It uses the platform as a service (PaaS) model and focuses on the deployment of applications in the cloud space. However, dynamic inferencing of new social relationships from existing relationships is not supported by this system. Moreover, making a modular interoperable design by employing concepts like microservices and semantic web technologies is not considered in this work.

Paraimpu [20] provided a social Web of Things platform to connect virtual and physical things to the web. In this system, the social concept only relates to humans by providing them with the capability to share things with each other using a human social network. Also, virtual things are not considered as VOs but rather viewed as services on other IoT platforms.

Using SIoT at the edge of the network was investigated by [21]. In this system, an approach was proposed to cope with the communication delay due to the objects being remotely located in the cloud. This approach exploits the computing resources at the network edge to deploy virtual objects.

The ThingSpeak solution was used as the basis for the implementation of an early SIoT platform [22]. This platform provided the object social behavior functions incorporated at the centralized server. In this implementation, functions such as the creation and the management of the social relationships were developed. However, VO concept was limited only to the records in the remote database.

Another featured SIoT framework was contributed by [4]. This work presented how to combine services, devices, users, and their social interaction to enable interactivity, discovery, and recommendation of services. Social relationships have also been investigated in communities [23], where a proposed framework enables the identification of communities in the social networks.

Although most of the research contributions in the SIoT domain incorporate a notion of the social association of objects, however, limited information has been provided about the social relationship model and the details on how that can be used by IoT services. Furthermore, existing approaches are lacking lightweight and modular mechanisms which can be utilized by services to exploit social relationships efficiently. In our approach, we have developed a semantic ontology-based social relationship model that provides the capability to infer new connections in a network of social objects. Another distinction of the proposed system is a microservices based design that utilizes the developed social model to provide lightweight, modular, simple, and interoperable IoT services.

2.2. Microservices. The microservices architecture is emerging as a new trend among the practices of developing distributed web applications. To develop SOA based systems, microservices have become a prominent approach in real-world settings [24]. In the microservices based architectural pattern, each application incorporates a collection of small services which execute independently and use lightweight communication mechanisms [9]. The microservices are targeted for doing one thing well at a time based on the principle of single responsibility [25], as defined by Robert C. Martine: "Gather together those things that change for the same reason and separate those things that change for different reasons" [26]. Also, the microservices are conceived as autonomous entities, which means they can be changed and deployed independently of each other without requiring their consumers to change [24].

In the last few years, several IoT architectural designs were proposed and developed. Some of these designs provided innovative features such as the European FP7 project iCore [27] which proposed a cognitive framework for IoT application development. This project provided an architecture with the concept of virtual objects and their composites. However, in iCore, services are designed using a traditional SOA based monolithic style, whereas the microservices based architecture provides a better option to develop IoT services. Furthermore, in iCore, VOs lack the mechanisms to semantically represent real-world objects (RWOs), which limits extensibility and interoperability.

To support IoT applications, microservices based architectures are being proposed in many research initiatives and applied in several research projects. In [28], microservices are used for M2M applications, realizing the fact that monolithic approaches for M2M cannot provide a real solution. Another work [10] provided an analysis of using microservices architecture for large-scale distributed applications. This work demonstrated that significant benefits can be achieved as compared to generic SOA approaches when using microservices in an IoT platform for smart city applications.

Moreover, Almanac FP7 EU Project [29] provides smart city services based on the IoT environment. The project uses microservices to employ scalability in a horizontal and vertical fashion. Also, in the industry, microservices have become a solution for developing large-scale applications. Netflix, Pivotal [30], and Amazon use microservices in their software bases.

The increased importance of microservices for the IoT applications is due to the fact that they simplify complex systems. By dividing a system into smaller parts, higher cohesion and lower coupling can be achieved, which makes it highly scalable. In scenarios where requirements keep changing continuously, microservices can help make a system easily modifiable. Moreover, the major benefits that are envisaged when using microservices in an IoT environment are as follows: Microservices leverage scalability to provide a highly decoupled pattern and can allow scaling individually. Their usefulness can be realized as when the demand for the requirement increases the system complexity also rises. In this case, a system can be supported by creating new instances of existing services. Microservices scalability [9] fits in three-dimensional space, that is, horizontal scalability (typical scalability), vertical scalability (splitting different individual microservices), and z-axis scalability (splitting similar things, such as DB partitioning). Microservices architecture supports a plug-and-play behavior where system components become loosely coupled. To acquire new functionality or replace a failed service, pull the plug from one microservice and plug into a new microservice [31]. One of the major problems that IoT is facing today is how to deal with the heterogeneity of incompatible solutions. To harmonize the heterogeneity, semantic web technologies with microservices are leveraged to provide interoperable exchange and communication of data. Microservices realize a decentralized and autonomous behavior, operating on their own priorities and schedule. This way, they provide several benefits for being utilized in an IoT design.

3. The Proposed Design of Social Web Objects

Recently, there have been several research efforts [3–6, 17, 20, 32] for defining the Social IoT. This new aspect minimizes the complexity generated by the communication of billions of real-world objects and enables sharing of information. The social notion can be incorporated into the WoO platform to provide a semantically rich base for IoT applications that can utilize real-world object relationships for efficient information discovery. Moreover, this section provides a brief introduction of WoO reference architecture in Section 3.1. A classification of social relationships among web objects (virtual objects and composite virtual objects) is discussed in Section 3.2 and a social relationship model is presented in Section 3.3. Further, the details of functional components for the proposed architecture are explained in Section 3.4.

3.1. Web of Objects (WoO) Reference Architecture. To enable the deployment of IoT services on the World Wide Web, WoO provides a reference framework. In other words, it realizes the IoT services in such a way that virtualized objects are interwoven with resources to support the development, deployment, and operations of IoT services [33, 34]. The WoO platform provides service functionality by merging VOs and features of web applications. Moreover, the WoO platform uses semantic web technologies to enable interoperability among heterogeneous resources. This realization provides the basis for the composition and harmonization of objects to provide smart services in an IoT domain. Building services based on WoO platform using diverse technologies, including microservices [35], social networks, and semantic web, helps reduce the complexity and fosters the easy and efficient development of IoT applications.

Virtualization has become a major concept in IoT to address the heterogeneity of diverse types of physical objects. VO is a digital representation of a real-world object that can be anything, living or nonliving, mobile or stationary, concrete or immaterial. In WoO, VO is defined as domain-specific semantic ontology based on the VO information model [36]. It is uniquely identified using URI and provides information updates on the representative real-world object. On the other hand, WoO also provides a notion of CVO which aggregates one or more VOs to enable service features that satisfy the application requirements. CVOs chain semantically interoperable VOs together. The WoO platform incorporates features to efficiently reuse existing VOs and handles the complexity generated by self-management and control mechanisms [37]. In the WoO, service level decides which CVOs and VOs will take part in creating an object mashup to fulfill service objectives. The service logic is saved in the form of templates and stored in the template repository [38–40]. The domain expert or knowledge engineer defines the service templates that are used to instantiate new services.

WoO reference architecture is shown in Figure 1. In this architecture, the service layer handles requests and provides several management functions, whereas the CVO level consists of functions to manage and instantiate CVOs or reuse the existing ones based on the provided service execution logic. New objects such as sensors are registered in the WoO platform using a registration function and their templates are generated to make them digitally available in the form of VOs. Another most important aspect is the semantic representation of data at three-layered WoO architecture [23, 39]. The database at each layer is supported with semantic web technologies.

3.2. Types of Social Relationships. Previous research [3] on SIoT has derived some basic relationship types among objects. These relationships are characterized as follows. *Parental Object relationship* (POR) exists between the objects that belong to the same batch, such as objects that are created in the same production process or at the same time by a common manufacturer. *Cowork object relationship* (CWOR) is the relationship among objects that are grouped together based on some commonly shared job to be done by them. Similarly, *colocation object relationship* (CLOR) is established


User
Application A
Application B
Application C
API
API
API
API
API
Database
Service level
WoO service level
Service registory
Service template
Service DB
IF-1
Virtual level
Composite virtual object (CVO) sublevel
CVO registory
CVO template
CVO DB
IF-2
Virtual object (VO) sublevel
VO registory
VO template
VO DB
RWO
RWO
RWO
RWO

Figure 1: Web of Objects reference architecture.

between objects belonging to the same location such as home or office. Different or same types of objects can be combined based on the common location or premises. On the other hand, *Ownership Object Relationship* (OOR) is formed among objects belonging to the same owner. *Social Object Relationship* (SOR) is another kind of relationship that is created among objects when they come close to each other, either random in time or periodically. This relationship can be envisaged when the owners of objects come into contact with each other. Apart from the above relationships, in [41], the authors define the *Guardian Object Relationship* (GOR) in the Internet of Vehicles (IoV) scenario where on-board units of vehicles become children in relation to the super nodes of Road Side Units. This child and parent association gives a special meaning to a new hierarchical relationship.

In addition to the relationships defined in other studies, we have identified few more relationships suitable for some diverse scenarios. These include *Sibling Object Relationship* (SIBOR) that is created among objects that belong to a group of friends or family members. This relationship among objects extracts the property of trustworthiness based on the relationship of their owners. Another relationship type is the *guest object relationship* (GSTOR) which is formed between objects that belong to the users in the guest role, for example, when a person visits a friend's home and gets the privilege as a guest. The same can be applied to the objects that move in guest relation (GSTOR) from one place to another; they will have some privilege of accessibility of information as compared to other objects. *Stranger Object Relation* (STGOR) applies to objects that encounter the presence of each other in an anonymous environment such as on the go or in the public environment. Similar to people who meet each other sometimes regularly but are anonymous to each other or are not fully aware of each other, this relationship can be used among objects to form different trust levels or to form strict restrictions to promote secure connections. Moreover, in *service object relationship* (SVOR), objects form a relationship while coordinating in the same service composition to fulfill a service request. Generally, in the proposed scheme, service request execution generates a mashup of objects, and objects that belong to the same mashup are assumed to be in SVOR.

We believe that the above defined new social relationships are beneficial in several distinctive scenarios. For example, SIBOR is more useful in scenarios where trust is highly important for establishing a connection. Unlike the more generalized relation POR, SIBOR is established



(i) Sibling Object Relationship (SIBOR)
(ii) Service Object Relationship (SVOR)
(iii) Stranger Object Relationship (STGOR)
(iv) Guest Object Relationship (GSTOR)
(v) Parental Object Relationship (POR) [3]
(vi) Colocation Object Relationship (CLOR) [3]
(vii) Ownership Object Relationship (OOR) [3]

Figure 2: Ontological model representing web objects' relationships.

among objects from the same manufacturer having similar features but different behaviors. Similarly, GSTOR is suitable in scenarios where objects use relationships for privileged services. Imagine a person as a guest speaker in a conference with his smart devices, where he can connect to the network easily, and his personal devices are recognized as a guest (with GSTOR) in the venue network to avail free services like high-speed Internet, special notifications, and others. Stranger Object Relation (STGOR) is used in scenarios where objects are on the go, and to get some information, they have to compromise with a limited trust level. For instance, in a public transit system, one mobile node on the move wants to use crowdsourced information from another mobile node which is not fully trusted. Also, SVOR is useful in service composition specific scenarios, where object mashups are formed to facilitate service requirement, and it is also useful in a particular orchestration of objects.

To model information about microservices, social web objects, and their relationships, a semantic ontological model has been developed as depicted in Figure 2. Conceptualization of objects and their social relationships in semantic structures are highly beneficial to infer new connections among a network of objects with the help of reasoning techniques. The ontology facilitates the representation of objects, as well as what they measure in terms of observations, their processing, and functions. Web objects' relationship ontology contains the concepts that define each object in terms of a class. The data properties are used to represent object values and the object properties are defined to identify the link between two objects in the ontology. Major concepts in the ontology are microservices, CVOs, VOs, and their social relationships. Further, microservices have an individual instance that uniquely defines a microservice object and associated data with it. Similarly, CVOs and VOs are also instantiated and contain data properties to retain their values. With the increasing number of objects, a semantic ontology model is used to perform reasoning function that helps identify new connections. Further, to analyze the social relationship among objects (such as VOs and CVOs), their properties are provided in Table 1.

3.3. Social Relationship Model for Web Objects.

3.3. Social Relationship Model for Web Objects. At each level of service life cycle, objects form a social relationship with each other to accomplish a service task. Codifying the relationship among web objects can provide many benefits, such as efficient information discovery from related objects and better composition and reuse. To perceive social interaction between web objects, we assume every service is based on one or more microservices and other objects including CVOs and VOs. At VO level, VOs create several relationships with each other based on the RWO they represent. CVOs associated with microservices are incorporated in relationships as well.

Object-to-object associations are categorized as either vertical associations (interobject relations) or horizontal associations (intraobject relations) as shown in Figure 3. The relationships that flow from the bottom to the top in WoO based architecture are known as interobject relations (i.e., from VO to CVO or vice versa). On the other hand, relationships are known as intraobject relations if they are generated within objects at each level such as between one VO and another, or within one CVO to a relative CVO. The newly defined relationships among objects are maintained at different levels, which enables information discovery more efficiently. It is considered that not only will the relationships be maintained when two objects (i.e., VOs) are used in the same CVO or service, but also they will be maintained if objects are used in different CVOs or services.

As depicted in Figure 3, VO1 and VO2 bind in the SIBOR relationship, considering the fact that they belong to the same family of CVO1. Similarly, VO4, VO5, and VO6 are combined in a CWOR, as they are used in the same service. However, all of them do not have a common family relation that makes their trustworthiness restrictive to some level as compared to SIBOR. Moreover, though VO7 and VO8 are not used together in a service setup, still they form a STGOR relationship. This relationship also helps codify those VOs that have similarity in premises during a certain point in time regularly but they had never combined in any service scenario before. For example, if a person visits a subway regularly but stays very shortly, in such scene, the user's smartphone VO and subway station point

Table 1: Social relationship attributes.

Social object relationships types	Attributes/properties
Sibling object relation (SIBOR)	O_x *has relationship* with O_y → SIBOR, if objects' *ownership* is defined as: == SameFamily
Service object relationship (SVOR)	O_x *has relationship* with O_y → SVOR, if objects' *serviceStatus* is defined as: == SameServiceComposition
Stranger object relation (STGOR)	O_x *has relationship* with O_y → STGOR, if objects' *authentication* is defined as: == Anonymous
Guest object relationship (GSTOR)	O_x *has relationship* with O_y → GSTOR, if objects' *ownership* is defined as: !=SameFamily && == GuestFriend
Parental object relationship (POR)	O_x *has relationship* with O_y → POR, if objects' *creation* is defined as: == SameBatch ‖ == SameProduction
Colocation object relationship (CLOR)	O_x *has relationship* with O_y → CLOR, if objects' *proximity* is defined as: == Neighborhood ‖ *location* is defined as: == SameLocation
Ownership object relationship (OOR)	O_x *has relationship* with O_y → OOR, if objects' *proprietorship* is defined as: == SameOwner



Figure 3: Hierarchical social relationships of web objects.

VO or subway security camera VO may establish STGOR. This may help reuse VOs in service scenarios where only for short duration a VO object is required. At CVO level, CVO2 forms two different relationships, which increases the level of connectivity of the CVO. CVO2 first shares a CLOR with CVO1 and CVO3, CVO4, and CVO5 together. Secondly, CVO2 is combined in a SIBOR with CVO3 and becomes in the same service family. Further, in the selected use case scenario described in Section 4, several other social interactions have also been elaborated.

3.4. Social Web Objects Architecture. SIoT envisages a system where the social framework will bring smart devices and people to interact with each other. By incorporating web technologies like SOA based microservices, IoT services can be rendered on top of the social framework. The proposed social web objects architecture (as shown in Figure 4) has been decomposed into three levels: service level, object virtualization level, and aggregated object virtualization level. At the service level, to support social relationships within web objects, several microservices have been designed, which are discussed further in the following section. Moreover, the data management function in the proposed design helps each layer to interconnect with semantic databases. The SPARQL endpoints have been defined at the service and the object virtualization levels that expose interfaces to retrieve, store, and modify RDF graphs. Several interfaces allow the knowledge engineer, domain expert, and the developer to create service templates and VOs, as well as update the RWK model, user profile, and policies.

3.4.1. Service Level Functional Components. The service level functions handle operations from the request inception to the execution of services. This level is supported by some core functions common to be used in each service life cycle. These include the management function to handle service


Application A
Application B
Application C
User
API
API
API
API
Service Interface
Database
Database
RWK
RWK model (RDF concepts & facts)
User profile RDF/OWL
API
Knowledge engineer
Service level
Discovery & lookup
Service management
RWK situation mgt.
Composition engine
Service execution environment
Request evaluator
Service registration μs
Service lookup
Service life status mgt.
Service template mgt.
Service logs mgt. μs
Semantic RWK μs
Workflow mgt. μs
Semantic match maker
Service reuse tracker μs
Service binding μs
Semantic context collector
User situation management
User profile mgt.
Situation discovery/ classification/ projection μservices
Microservices communication hub
Group mgt. μs
Rel. dependability μs
Relation observer μs
Link mgt. μs
Relationship lookup μs
CVO Level Interface
Semantic Data mgt.
Service DB
Service registory
Service template
Service DB
API
Domain expert/ knowledge engineer
Aggregated obj. virtualization level
CVO configuration & management
CVO generator and composer
CVO reuse management
system knowledge engine
CVO registration
CVO discovery
CVO template mgt.
CVO life cycle management
Selection analyzer
Similarity checker
Composition maker
Integration validator
CVO coordinator
CVO hypothesis analyzer
Event processor
CVO DB
CVO registory
CVO template
CVO DB
API
Developer
VO level interface
Object virtualization level
VO management & optimization engine
VO generator
VO container
VO ownership management
VO registration
VO template mgt.
VO access mgt.
VO identity mgt.
VO metadata mgt.
Conflict resolution
VO coordinator
VO data synthesizer
VO availability validator
VO discovery
VO energy efficiency tracking
VO DB
VO registory
VO template
VO DB
API
Installer
Gateway
Sensor and actuators

FIGURE 4: Social web objects functional architecture.

requests and initiate service provisioning processes, the service discovery function to select the available services, the composition engine to enable service mashups, and the Real-World Knowledge (RWK) and situation management function to acquire RWK and continuously maintain it. Besides these core functions, several microservices have been used to provide the plug-and-play feature in the proposed design; that is, in case of service failure, it is replaced with another one. These services include the Request Evaluator microservice which interprets a service request and matches a request query to the service template. The registration microservice registers newly added service objects to the registry. When a new template is instantiated, objects are put in service, and to know the existence of available service instances, they are recorded in the service registry. The lookup microservice is defined to search for the required service objects using the semantic representation. The representations available in RDF/OWL format are queried from the registry based on the request parameters. Service life cycle management keeps track of the states of service objects during their life cycle, whereas RWK management microservice is a semantic data processing service which processes facts about user preferences, profile, and situational information.

To realize service provisioning, it is always not possible to satisfy the service requirement with a single service function. Service composition and harmonization features are required to fulfill a demanding service request. Service composition is not a single operation; many microservices are used to compose the individual features. One of the major components of the composition is the Workflow Management (WFM) microservice which is responsible for decomposing the service requirement if no single service is available to satisfy the task. WFM microservice identifies the service objects using input and output interfaces. In this concern, it uses the matchmaking microservice to identify the approximate matches that can serve the required service functionality. Here, service objects are semantically represented in the form of ontologies. The semantic ontology alignment algorithm is used to match the service up to a certain threshold level that is defined by the matchmaking microservice. The reuse tracker microservice is used to identify the current service instance usage by the application; it incorporates a coordination mechanism before instantiating any new instance, and this helps in service reuse by many clients. Binding microservice enables tying of services selected by WFM; this function synchronizes input and output of services in a workflow to produce a single service output based on the generated composition plan.

Furthermore, user characterization is another important element to support the IoT services by matching user requirements more closely. The User Profile Manager microservice handles many facts related to the human user. These include user profile, preference, context, and policies. Semantic Context Collector microservice organizes the services requested by the user and the context in which these services were requested. This helps in identifying user interest with respect to the service context. User context or situation helps in service selection more efficiently if a user requests again with a similar service requirement. Some microservices have been designed to handle user situation information; these microservices include situation discovery, classification, and recognition functions. Situation discovery is used to process sensor data that is provided by CVOs to prompt a situation, whereas machine learning algorithms are applied to remove the false values and data normalization is performed in case inappropriate triggers in the data exist. Situation classification incorporates the reasoning methods and rules to generate a relationship over detected events and refine the missing knowledge between the events. Situation projection analyzes the events data with the help of machine learning methods and provides an output in the form of predicted facts that are related to the situation being detected. Moreover, all the microservices coordinate using a communication hub to share information with each other.

A flow of service inception to service execution in the proposed architecture is depicted in Figure 5 where service management is responsible for initiating the above-mentioned functionalities and instantiating the microservices. This process further results in the generation of CVO/VO mashup graphs to be handled by CVO management (discussed in Section 3.4.2). Situational information has also been used to improve request analysis and service provisioning, whereas VO management (discussed in Section 3.4.3) acquires and aggregates data from sensors and other RWOs.

Social Relationship Management Microservices. To support the social relationships among web objects at each layer of the proposed system, relationship management microservices are defined, which support the codification of relationships among web objects (VOs and CVOs) and their management. These microservices are defined as follows. Group management microservice identifies the grouping of objects into specific sets based on the type and interaction of objects; it builds a social graph of the object relationships. Link management microservice incorporates mechanisms to maintain relationships among different objects and it includes several other subfunctions. The first subfunction is object selection which involves choosing candidate objects that are likely to form a particular association. The second subfunction is matchmaking service which provides exact relationship match based on the type of objects. The third subfunction is the association life cycle manager, which maintains the relationship status between objects; it checks whether they are in active relation or not. It keeps track of relationship validity and also the duration of relationships. Relationship observer microservice enables the object activities to be observed, and it also handles the mutual sharing, which defines what information an object is allowed to share or use of another object based on the relationship among them. Relationship dependability recognizer microservice identifies, maintains, and continuously improves the level of reliability among objects. If objects A and B are frequently interacting and always perform a task together that leads to successful execution of an application to serve the requirements, then they are more likely to form a reliable relationship with each other. The consistency of the relationship allows objects to share their information with fewer constraints as compared to unpredictable association among objects. Relationship


Application domain
Service manager
Composite VO mgt.
Service/CVO/VO registry DB
VO management
Situation/RWK management
User profile
Microservice container
Service request
Evaluate Request
Discover microservices
Select service template
Composition mgt.
Req. user situation parameters
Req. user model
Resp. user model
Resp. user situation parameters
Req. service
Service resp.
Instantiate microservice
Req. CVO creation
Req. CVO entries
Resp. CVOs
VO instantiate req.
CVO registration
CVO ontology lookup
Reuse approximation
Req. VO entries
Select VOs
Resp. VOs
VO Registration
VO ontology discovery
VO metadata mgt.
Update events
Update user model
Update preferences
Situation detection
Classified situation
Situation projection
VO notification
CVO notification
Microservice deployment
Microservice notification/status
Service resp.

Figure 5: Request initiation and service execution flow in the proposed architecture.

lookup microservice incorporates the discovery algorithm (as given in listing of Algorithm 1) to discover the social relationships and maintains the list of all objects and their potential association rating. The rating defines the opportunity for objects to form a relationship with each other.

Moreover, the operation flow of social microservices has been illustrated in Figure 6, where VO management retrieves the social relationship among objects this is queried using link management, which uses a lookup service. Associations are maintained in a social relationship graph using semantic ontology and queried using the relation observer service. The social graph is also updated and maintained continuously with respect to changing links among objects, on the basis of which VOs are selected.

3.4.2. Functional Components in Aggregated Object Virtualization Level. Aggregated object virtualization (AOV) level involves all the necessary functions to instantiate, manage, and continuously monitor CVOs. Besides, it includes the interface required by the service level to interact with CVO components. Service level provides the mashup graphs of CVOs and VOs that are required to fulfill a service request. Aggregation level also supports some core functions; these are categorized as CVO configuration and management to decompose requests from service level and manage CVO instances, CVO generator to instantiate CVOs, composition function to form CVO and VO mashups, reuse management to select existing CVOs that approximately match service requirement, and system knowledge engine to grow knowledge for the optimal use of CVO resources. Further, other aggregation level functionalities are as follows: registration function records the CVO entry into the semantic CVO registry in the form of RDF/JSON format. CVO includes ontologies that specify conditions to be applied on the VO data. Also, at this level, templates are created by a domain expert or knowledge engineer, which consist of functionalities associated with each CVO type. Template management module provides an interface to include templates to the CVO template repository and also supports the modification mechanism. CVOs are discovered using their semantic annotation via the discovery function. CVO selection analyzer function provides estimated selection of a CVO for reuse if there is no single CVO that can exactly provide the required service. This is supported by similarity checking mechanism to analyze the level of similarity before recommending for reuse. At aggregation level, another important function is event processing; event streams generated by object virtualization level are highly valuable to infer situational awareness and building RWK that is used by high-level functions. Event processing module facilitates processing of events and provides generated facts as output. Event processing is supported by CVO hypothesis analyzer that incorporates several hypotheses which are trained over data to build system level knowledge. Aggregation level also


VO mgt.
Social relationship manager
Social link mgt.
Relationship lookup MS
Group mgt.
Relation observer
Social relation graph
Select registered VOs
Req. relation graph
Retrieve social object relation
Object selection
Query generation
Req. lookup
Lookup resp.
Social rel. search
Social rel. query
Execute query
graph result
Infer relation
Inferred relationships
Relation graph resp.
Update dependencies
Add member
Update VO
Matchmaking
Validate association
Organize group
Update change in association
Generate update query
Update triples
Ack.
Update Group
Modified social graph
Social graph update
Update VO

Figure 6: Sequence of operation required to establish a social relationship among objects.

provides composition function which provides the basis for merging multiple VOs to generate single service feature and validation function to validate the compositions of multiple VOs. Moreover, the coordinator helps in resolving conflicts in case of simultaneous access of single CVO by multiple services together.

3.4.3. Functional Components in Object Virtualization Level. Although IoT middleware virtualizes sensors and actuators in some form of virtual entities, however, in WoO, every living or nonliving thing can be represented in the virtual world. VOs are supported by an information model [14, 15] which includes the representation of RWO that can be ICT or non-ICT. In the proposed architecture, object virtualization level includes functions to create, maintain, and coordinate VOs such as VO generator, VO management, and optimization engine. VO registration function provides an interface to register VOs with the help of VO ownership management function where the VO ownership is maintained. Template management function handles templates or loads updated ones as provided by the domain expert. Metadata management maintains data associated with VOs; as VO is a digital representative of real-world entities, there is a high need to store metadata information to recognize the class of sensed data. Use of metadata provides the real value of the data in the form of the context stored within it. Furthermore, VO data synthesizer service handles the discrepancies if found in the data corresponding to VO; this includes data manipulation and missing value rectifications. Conflict resolution function helps in case the same VO is used by multiple service instances, to resolve the conflicts. Also, VO access management function controls access for VOs in case access right information has been defined by the VO owner, whereas identification management module maintains identification information about VOs so that each VO can be uniquely identified in the system.

3.4.4. Social Relationship Discovery and Composition. To identify associations among web objects within a social relationship graph, an algorithm is elaborated briefly. In the following algorithm, the microservices that are in execution are retrieved first, represented as ⅀Mμ; next, all the CVOs associated with each of those microservices are recovered in ⅀Mc and, further, the corresponding VO model ⅀Mv is iterated. In the next step, executing the query statement routine returns the results denoted as ₸. The process of finding the relationships is carried out through lines (6)–(19) in multiple nested iterations as shown in the pseudocode of Algorithm 1 listing.

Algorithm 2 facilitates the composition of objects based on social association types. This algorithm takes as input the set of object social relationships denoted by $\mathbb{Z}$ and registry entries of the objects that are currently available in the system, represented as $\mathbb{R}$e. After the object model denoted

```
Require: $(\Sigma\phi)$, $(\mathbb{R}_e)$
(1) Output: $\hat{S}$ (social relationship graph of objects)
(2) $\Sigma M_\mu$ ← Load Microservices in model
(3) $\Sigma M_c$ ← Load CVOs in model
(4) $\Sigma M_v$ ← Load VOs in model
(5) ₸ ← executeQueryStatement ($M_\mu$, $M_c$, $M_v$, $Q$)
(6) for All $\mu$ in $\mu$₸ do (iterate Microservice instance being used)
(7)   for All $O \in \mu$ do (check CVO and VOs used by the Services)
(8)     if $O_i$ == output of $C_R$ in a relationship set $R_c$ then
(9)       add $C_R$ to $\mathbb{I}_L$
(10)    else
(11)      if $O_i$ == output of $V_R$ in relationship set $R_v$ then
(12)        add $V_R$ to $\mathbb{I}_L$
(13)        $\mathbb{N}_i$ ← tag (Assign relationship tag to each object entry)
(14)      else
(15)        add $O_i$ to $\mathbb{I}_U$
(16)      end if
(17)    end if
(18)  end for
(19) end for
```

Algorithm 1: Social relationship discovery.

```
Require: $(\Sigma\phi)$, $(\mathbb{R}_e)$, $(\mathbb{Z})$
(1) Output: $\mathbb{C}$ (Composite Service)
(2) $\Sigma M$ ← List all objects available (Microservices, CVOs, VOs) in model
(3) ₸ ← executeQueryStatement ($\Sigma M$, $Q$)
(4) $\mathbb{Z}$ ← executeQueryStatement ($\Sigma M$, $Q'$)
(5) for All $\sigma i \in$ ₸ do
(6)   for All $\lambda i \in \sigma$ do
(7)     if $\lambda i$ == any $z$ in $\mathbb{Z}$ then
(8)       add $\lambda i$ to $\mathbb{I}_{\mathrm{Lm}}$
(9)       store $\mathbb{I}_{\mathrm{Lm}}$
(10)    end if
(11) end for
(12) for All $\varpi i \in \mathbb{I}_{\mathrm{Lm}}$ do
(13)   if $\varpi i$ == any $\varpi i$ in $\mathbb{I}_{\mathrm{Lm}}$ then
(14)     $\partial$ ← ranking (Assign rank to each service)
(15)     add $\varpi i$ to $\mathbb{I}_{\mathrm{LR}}$
(16)     store $\mathbb{I}_{\mathrm{LR}}$
(17)   end if
(18) end for
(19) for All $\sigma j \in \mathbb{I}_{\mathrm{LR}}$ do
(20)   if $\sigma j(R\partial) > \kappa$ then
(21)     add $\sigma j$ to Wf
(22)     Pq ← assign to queue
(23)     Sort Pq
(24)     Formulate Wf
(25)   end if
(26) end for
```

Algorithm 2: Composition of objects based on social relationship.

as ΣM is loaded, the first step is to compose objects based on their relationship types. This way, the SPARQL queries are executed; the first query is denoted as Q to retrieve the available service templates and the second query is represented as Q' to extract the relationships associated with the services. From line (5) to (11), first, the social relationship is searched among objects and then the found relative objects are composed in groups. The design philosophy employed over here is to assign a ranking to each selected group based on the relationship type that helps in a more efficient



Figure 7: Use case scenario.

composition of service objects (from line (12) to (18)). The last part of Algorithm 2 will continue to iterate to compose the object composition workflow by checking first the assigned relationship ranking with the defined threshold, and then the selected composition workflow graphs are sorted and stored in queues for service execution.

4. Use Case and Prototype Implementation

In this section, first, to realize IoT service provisioning based on social web objects, a use case about IoT enabled museum environment has been presented and then the details on the prototype implementation are furnished.

4.1. Use Case Scenario. This use case is based on a user experience in a public museum where the IoT environment is already set up with the WoO platform incorporating web objects that use social relationship model and a social agent which obtains the user's profile and his friendship details from social media (as shown in Figure 7). The user enters the premises of the museum and his smartphone is prompted with a beacon signal to recommend service app installation where he accepts the request. The phone app incorporates a microservice which establishes a social relationship (GSTOR) with museum visit service objects. The system monitors the interaction of the user in the museum environment; the installed camera network and motion detectors detect the user presence and this feed is collected by the museum visit service. The user shares his current location with the system, which is used by the location navigator service to assist him in moving around the museum by providing the direction to the locations where different museum items are situated. It is worth noticing that the VOs for museum visit service and location navigator service are bound in CLOR relationship due to the same location points. The user shares his social network profile which is used to acquire the list of friends and choices for things the user is interested in. This information is acquired by the recommendation service which suggests the best things to do with respect to the user's interests, making his visit most enjoyable. Recommendation service suggests facilities available in the museum such as places a user should visit, cafeteria food menu, and prices for the day. This service also shares with the user the past experiences of his friends at the museum to help him get most out of his visit. Moreover, personalization service provides special features such as adjusting contents on displays or optimizing the luminosity, to support users with disabilities. To enable these service features, objects exploit the SVOR relationship. Also, the fire management service maintains the status of all VOs that can detect an unusual fire situation in the museum. The temperature VOs acquire readings from temperature sensors and smoke detector VOs get a feed from smoke detection sensors. These VOs form a CLOR relationship with each other in the common proximity. Fire situation monitoring CVO acquires VOs data. One or more CVOs are managed by the fire management service. In case of a fire breakout, the fire management service executes with the data from the fire detection CVOs and the temperature and smoke detector VOs. Meanwhile, services incorporate high-level functionality to react on the data provided by virtual entities in the system. It is important to notice that sharing of information based on social relationships has become easy in the proposed use case. That is because the user information and device information are communicated with social links of web objects and are utilized by the services.

4.2. Proof-of-Concept Details. To evaluate the proposed design, a proof of concept has been furnished, which realizes services based on web objects as considered in the above use case. These objects include, for instance, fire situation monitoring CVO to handle emergency fire breakout situations, location navigator CVO to find the shortest path to the user


Social application server
Social Relationship manager
Service Management function
Situation management function
Preferences predictor
Virtual object manager
Http REST
Ontology management server
Ontology management function
Jena
Reasoning engine
Query manager
Sparql endpoints
Gateway
Sensors/ actuators
User profile
User Data Mgt Service
SNS feed
User preferences
MySQL DB
Sparql
CVO ontology
VO ontology
protégé
Ontology modeling
RWK base

Figure 8: Prototype implementation components.

intended destinations, and user profile reader CVO which acquires user personal information from the social media profile. Several other CVOs have been developed that acquire diverse data and metadata from VOs where each represents a different RWO. These VOs include a user VO, smartphone VO, camera VO, wristband VO, motion detector VO, and others that are associated with the chosen environment (such as CO_2 sensor VO, humidity VO, temperature VO, and light VO). Each VO has several instances; for example, temperature sensor instances are represented as temperatureSesor0001 and temperatureSesor0002. Further VO data is collected and analyzed by CVOs with the rules incorporated in the ontologies. CVOs composed in microservices help analyze different situations and initiate inference over data using inference engines. Considering the system requirement, several aspects have been evaluated, including identification of web objects for effective IoT service provisioning, finding the social relationships among web objects, efficient discovery of web objects based on these relationships, and composition and harmonization of web objects.

4.3. Prototype Implementation Details. To analyze the feasibility of the proposed architecture, a prototype on the discussed use case has been implemented. Figure 8 illustrates the components of the prototype, which constitute social application server (SAS), ontology management server (OMS), and databases to hold VO and CVO graphs that are supported with SPARQL endpoints. The gateway connecting sensors and actuators has been incorporated in the implementation. Additionally, user data management services are implemented to get user profile and preferences history along with social network data.

The application server comprises five major components: social relationship manager (SRM), service management function (SMF), situation/context management function (CMF), preference predictor, and virtual object manager (VOM). The SMF is an entry point for the service request; it interprets and evaluates the service request. It is also responsible for matching the service request with the available template. SMF communicates with VOM to check the VO or CVO availability. A compiled list of VOs is provided to SMF which generates object mashups to satisfy the service request. The execution of VO mashup graph is done using microservices. The second function, VOM, maintains instances of CVOs and associated VOs and coordinates with OMS to use available ontologies in the system. It records the association of services and VOs and enables the reuse of VOs by more than one service; it also resolves conflicts using conflict resolution mechanism. VOM is implemented using RESTful web services. Further, SRM is implemented to maintain object relationships in the form of RDF concepts represented in ontologies. It also involves several microservices, each implemented for a specific task. For example, group management microservice is developed to group objects that have similar characteristics. Similarly, other tasks are distributed in different microservices; for example, link management microservice is used to identify the dependency among objects. Relationship observer microservice is implemented to monitor the objects when they change their state at runtime, whereas to search a web


led0001
led0002
cosensor0002
pressure0001
pressureSensor0003
door0001
airCon0001
airCon0002
lumin0003
led0003
hrSensor0002
lumin0002
coSensor0001
PressureSensor
doorSensor0002
doorSensor0001
Door
lumin0001
LEDLight
pressure0002
gasSensor0001
airCon
gasSensor0002
tempMonitor0001
LuminositySensor
CO2Sensor
HeartRateSensor
smartCam0001
Cam0002
GasSensor
humiditySen0001
pathFinder0001
TemperatureMonitor
DoorSensor
SmartPhoneCamera
humiditySen0002
TemperatureSensor
PathFinder
owl:Thing
location
wrist0001
emergenyNotifier0001
EmergencyNotifier
HumiditySensor
bodyTempMon0001
sweat0001
wrist0002
User
LocationMonitor
BodyTemperature Monitor
careTaker0001
Display
WalkingStepsMonitor
WristBandSensor
locationMonitor0001
wrist0003
gpsSensor0002
FireSituationMonitor
SweatSensor
User0001
GPSSensor
location0001
accMeter0001
SmartPhone
walkingMon0001
Camera
cam0002
Accelerometer
hrSensor0001
CareTaker
smartPhone0001
careTaker0002
gpsSensor0001
SmokeSensor
FireAlarm
fireSitMon0001
cam0001
cam0003
fireAlarm0002
firealarm0003
fireAlarm0001

Figure 9: Ontological model of social web objects.

object relationship, the lookup microservice is used. The CMF function has been developed to process the situational information and it selects the most suitable VOs based on the context. The situational information contains the current location of the user, location of the RWOs, and the area under observation. CMF helps form a VO configuration specific to the user current situation. Additionally, to incorporate the real-world facts about the user and the situation, RWK base has been developed which is updated continuously. This also helps in adapting services according to the current situation. VOs provided data is accumulated in RWK model and the reasoning engine is used to infer new facts based on the existing data. The last function of social application server is the preference predictor which provides predictions by using machine learning methods. To implement the learning function, Weka Library [42] has been used. For the objective of demonstration, user preference patterns are collected from the social data and user preference history is used to predict the future patterns.

On the other hand, OMS deals with the semantic representation of VOs. The first functional component of OMS is the ontology management service, which is used to handle VO and CVO ontologies and provides an interface to use VO graphs. Further, to manage ontologies in the developed system, we have used Apache Jena framework [43], and to model VO and CVO ontologies, Protégé [44] has been used. Models generated in Protégé are utilized by ontology management service and stored in OWL format in semantic data stores. To take full advantage of ontology-based implementation, a reasoning engine has also been used to get extra facts related to the modeled concepts. Reasoning engine helps to grow RWK facts stored in VO and CVO ontologies. For the proof of concept, the prototype has used Apache Jena inference engine along with Jena provided reasoner. For the deployment of persistent storage of the RDF data, Jena TDB has been used in our prototype, which is the Jena native high-performance triple store with API support [43]. Query manager is another important component of OMS which provides an interface to query CVO and VO ontologies saved in RDF/XML format, using SPARQL. Also, web services are implemented for the execution of SPARQL queries such as extracting and updating RDF triples in the database. Other than SPARQL query processing, semantic matching of existing concepts is also performed.

Moreover, to achieve interoperable relationships among web objects, a semantic ontology model has been developed as shown in Figure 9. The model constitutes the VO and CVO ontologies and their relationships. Several CVOs have been instantiated, for example, the location navigator, fire situation monitor, emergency notification, and many others that are



```
<!-- http://www.webofobjects.com/hufs/smartservice#01 -->
 <owl:Class rdf:about="http://www.webofobjects.com/hufs/smartservice#01#SmartMuseumService">
     <!-- http://www.webofobjects.com/hufs/smartservice#01#fireSitMon0001 -->
     <owl:NamedIndividual rdf:about="http://www.webofobjects.com/hufs/smartservice#01#fireSitMon0001">
         <rdf:type rdf:resource="http://www.webofobjects.com/hufs/smartservice#01#FireSituationMonitor"/>
         <smartservice:CapturedBy rdf:resource="http://www.webofobjects.com/hufs/smartservice#01#cam0001"/>
         <smartservice:NotifyTo rdf:resource="http://www.webofobjects.com/hufs/smartservice#01#fireAlarm0001"/>
         <smartservice:NotifyTo rdf:resource="http://www.webofobjects.com/hufs/smartservice#01#smokeSensor0001"/>
         <smartservice:checkedBy rdf:resource="http://www.webofobjects.com/hufs/smartservice#01#User0001"/>
     </owl:NamedIndividual>

     <!-- http://www.webofobjects.com/hufs/smartservice#01#PathFinder0001 -->
     <owl:NamedIndividual rdf:about="http://www.webofobjects.com/hufs/smartservice#01#PathFinder0001">
         <rdf:type rdf:resource="http://www.webofobjects.com/hufs/smartservice#01#PathFinder"/>
         <smartservice:checkedBy rdf:resource="http://www.webofobjects.com/hufs/smartservice#01#User0001"/>
         <smartservice:checkedBy rdf:resource="http://www.webofobjects.com/hufs/smartservice#01#surveillanceSystem0001"/>
         <smartservice:notifiedBy rdf:resource="http://www.webofobjects.com/hufs/smartservice#01#location0001"/>
         <smartservice:notifiedBy rdf:resource="http://www.webofobjects.com/hufs/smartservice#01#smartPhone0001"/>
         <smartservice:notifiedBy rdf:resource="http://www.webofobjects.com/hufs/smartservice#01#motionDetector0002"/>
     </owl:NamedIndividual>
 </owl:Class>
```

Figure 10: CVOs and VOs used in the ontology.



```
<!-- http://www.webofobjects.com/hufs/smart-service-ontology#smartPhone0001 -->

<rdf:Description rdf:about="http://www.webofobjects.com/hufs/smart-service-ontology#smartPhone0001">
    <rdf:type rdf:resource="http://www.w3.org/2002/07/owl#NamedIndividual"/>
    <rdf:type rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#SmartPhone"/>
    <hasLocation rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#location0001"/>
    <hasOwner rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#User0001"/>
    <batteryStatus rdf:datatype="http://www.w3.org/2001/XMLSchema#string">70%</batteryStatus>
    <deviceName rdf:datatype="http://www.w3.org/2001/XMLSchema#string">Samsung-S5</deviceName>
    <modelNumber rdf:datatype="http://www.w3.org/2001/XMLSchema#string">SHV-E770S</modelNumber>
    <networkStatus rdf:datatype="http://www.w3.org/2001/XMLSchema#string">WIFI</networkStatus>
    <osVersion rdf:datatype="http://www.w3.org/2001/XMLSchema#string">Andriod version 5.0.1</osVersion>
    <smartPhoneId rdf:datatype="http://www.w3.org/2001/XMLSchema#string">S5-00:33:55:11:00</smartPhoneId>
    <smartPhoneManufacturer rdf:datatype="http://www.w3.org/2001/XMLSchema#string">Samsung</smartPhoneManufacturer>
</rdf:Description>
```

Figure 11: Smartphone VO used in the ontology.

based on the composition of numerous VOs. This development has been supported by OMS and semantic web tools such as Jena. Using OMS, CRUD operations are performed like create, update, and delete on CVOs and VOs using SPARQL. In the developed semantic relationships, two CVO instances, namely, "FireSitMon0001" and "PathFinder0001," have been used in the code snippet provided in Figure 10, for fire situation monitoring and location navigation, respectively. We can see the data properties and object properties associated with each object to maintain the relationship with other objects in the system. Further, to understand the VO representation, a smartphone VO "SmartPhone0001" is shown in Figure 11 with the defined properties. A list of VOs used in our prototype has been given in OWL description as shown in Figure 12.

In the test bed environment, the sensor to the gateway connectivity is enabled using ZigBee and BLE. Another source of information that has been incorporated to provide user-centric service capability is SNS feed, which consists of Twitter and Facebook data collected using social media APIs. On the other hand, user profile and preferences are updated using data management service, and this information is used to grow RWK base.

To test the prototype, an android application has been developed. After the user logs in to the app for WoO based assisted services, the app starts the configuration of services according to the user profile. A list of services is presented on the user's screen from which the user can select any service. These services include museum visit service, location navigator service, recommendation service, and emergency notification. The selected service starts collecting information with the interaction of the user or when the devices start pushing values about any change in the observed environment. Based on these observed parameters, alerts are generated by the app; for example, the museum visit service generates alerts about the available facilities in the museum and the environmental conditions including the indoor and outdoor temperatures. On the other hand, the location navigator service helps the user to navigate around the museum by showing directions to several visitor attractions. Moreover, the emergency notification service triggers alerts when a temporary fire is created to mimic an unusual situation such as fire breakout. The resulting fire increases the temperature reading which is detected by the temperature sensor. This change in reading is forwarded through the gateway and analyzed by the fire situation monitor CVO which checks its threshold value and generates an emergency notification on the user's app screen. Also, the recommendation service is used to generate suggestions about the museum events and the places to visit.



```
<!-- http://www.webofobjects.com/hufs/smart-service-ontology#deviceName -->

<rdf:Description rdf:about="http://www.webofobjects.com/hufs/smart-service-ontology#deviceName">
    <rdf:type rdf:resource="http://www.w3.org/2002/07/owl#DatatypeProperty"/>
    <rdfs:domain rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#CO2Sensor"/>
    <rdfs:domain rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#Camera"/>
    <rdfs:domain rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#DoorSensor"/>
    <rdfs:domain rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#FireAlarm"/>
    <rdfs:domain rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#GPSSensor"/>
    <rdfs:domain rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#GasSensor"/>
    <rdfs:domain rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#HeartRateSensor"/>
    <rdfs:domain rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#HumiditySensor"/>
    <rdfs:domain rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#LEDLight"/>
    <rdfs:domain rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#LuminositySensor"/>
    <rdfs:domain rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#PressureSensor"/>
    <rdfs:domain rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#SmartPhone"/>
    <rdfs:domain rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#SmartPhoneCamera"/>
    <rdfs:domain rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#SmokeSensor"/>
    <rdfs:domain rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#SweatSensor"/>
    <rdfs:domain rdf:resource="http://www.webofobjects.com/hufs/smart-service-ontology#WristBandSensor"/>
    <rdfs:range rdf:resource="http://www.w3.org/2001/XMLSchema#string"/>
</rdf:Description>
```

Figure 12: List of VOs used in the ontology.



Figure 13: VO discovery time with the increasing number of virtual objects.



Figure 14: Service execution time with the increasing number of virtual objects.

4.4. Performance Evaluation. The proposed architecture has been analyzed from two different perspectives: system scalability and resource consumption. The results with respect to the experiments and the performance criterion are discussed in this section. The first experiment involves the analysis of the time required to discover the virtual objects in the proposed system with or without social relationship criterion as shown in Figure 13. As it is apparent from the results, initially, to form a social graph, VO discovery process incurs delay due to the communication for establishing social relationship links. However, direct lookup for VOs in the registry at the start of the discovery process comparatively requires less time, but as the number of VOs increases, the delay rises. Traversing the social links to discover objects as the number of virtual objects grows considerably reduces the total lookups in the registry database.

The second experiment provides an analysis of the execution time required for the CVOs as shown in Figure 14. To test this in a real environment, an android application has been developed. The app allows access to the parameters from the available VOs. When the app requires retrieving observations, it iterates through VOs in the repository using a query interface. This requires high CPU utilization with more execution time required to retrieve the sensor values against each app generated request. This is due to the fact that the decision for the selection of VOs has been done at runtime; it requires more time to select the VO graphs, execute them, and get the relevant data from the VOs. However, when object interaction is based on the social relationship, it requires less time for the retrieval as friends in the social network share the data on other friends' requests, which results in less computation as compared with the previous scheme.

Moreover, Figure 15 depicts the time to discover VOs in four different types of services. These services are the museum visit service, the location navigator service, the emergency notification service, and the recommendation service. The discovery time varies from one service to another depending on the number of VOs used. However, as compared with the impact of social connections, it can be



Figure 15: VO discovery time for four different services with or without social relationship utilization.



Figure 16: Task completion time required for each service with or without social relationship exploitation.

realized that the services can considerably reduce the time of object discovery and execution by using the relationship model. This is due to the fact that with social association among web objects a service does not have to query the registry for all VOs and rather VOs in the same social graph are utilized. Also, VOs collected observations are shared to save the service time for probing each VO. To view this, Figure 16 shows the overall time required for services to execute their tasks. An important factor to notice here is that the overall task completion time is also affected when social links are used to collect observations from VOs that are used in the service execution.

5. Conclusion

The Internet of Things is bringing the next technological revolution by connecting billions of objects on the earth and providing intelligent IoT services. However, it also carries two most important challenges: the first one is the complexity of handling a huge number of heterogeneous objects and the second one is how to deal with the monolithic approaches for providing services over existing IoT infrastructure. To address these challenges, we have proposed an integrated design based on the principles of SIoT, where the complexity has been handled using socially connected web objects; to overcome the monolithic approaches, microservices that can compose new service features independently have been adopted. In the proposed design, a social relationship model has been presented, which enables the efficient discovery of web objects and reduces the complexity of service provisioning process with the algorithms to discover and compose web objects. A semantic ontology model has also been developed to realize the interoperable social interaction among heterogeneous objects. Finally, a prototype implementation based on a use case scenario has been demonstrated; to evaluate the system with respect to the performance issues, experimental results pertaining to the VO discovery and service execution time have been rendered.

Details of Notations Used in Algorithms

$⅀\phi$: Service object ontologies based on semantic representation where ϕ is a replacement for M_μ which represents microservices M_c which represents CVO and M_v are VO ontologies
$ℿ_L$: Collection or list of all relationships that are retrieved from service objects
$ℿ_U$: List of the objects that do not have a relationship or are not associated
$\hat{S}$: Social relationship graph of objects
U: Correlation union of templates
$\underline{\mu}\overline{T}$: All service objects returned in response to the query request
$\overline{T}$: All objects returned in response to the query request
μ: The single instance iterated from the collection of microservices
M: Data model based on the specified ontology, where $⅀M_s$ represents service data model, $⅀M_c$ represents context data model, and user profile model is represented as $⅀M_u$
Q: SPARQL query to retrieve the available service templates for user rating
Q': SPARQL query to retrieve the relationship associated with services
$\mathbb{R}_e$: Registry entries of service objects
C_R: Relationship associated with CVO
V_R: Relationship associated with VO
R_c: All possible relationships that can be associated with CVO
R_v: All possible relationships that can be associated with VO
O_i: Iterator object instance for iterating the list of CVO and VO objects
$\mathbb{Z}$: Set of objects' social relationships
σi: Iteration item of the list of service objects
λi: An instance of iteration items in the list of service objects
$ℿ_{\mathrm{Lm}}$: List of all matched service items
ϖi: An instance of iteration items in the list of matched service items

$\mathbb{III}_{\mathrm{LR}}$: List of all matched ranking
∂: Ranking value assigned to a service object
σj: Iterator item for the ranking list
κ: Threshold to rank a service object
Wf: Workflow for the composition of service objects
Pq: Priority queue to store ranked object instances
R∂: Assigned relationship ranking.

Conflicts of Interest

The authors declare that there are no conflicts of interest regarding the publication of this paper.

Acknowledgments

This work was supported by Korea Institute for Advancement of Technology (KIAT) funded by the Ministry of Trade, Industry and Energy (MOTIE, Korea) (N040800001, Development of Web Objects Enabled EmoSpaces Service Technology).

References

[1] M. Nitti, V. Pilloni, G. Colistra, and L. Atzori, "The virtual object as a major element of the internet of things: a survey," *IEEE Communications Surveys & Tutorials*, vol. 18, no. 2, pp. 1228–1240, 2016.

[2] J. Surowiecki, *The Wisdom of Crowds*, Anchor Books, 2005.

[3] L. Atzori, A. Iera, G. Morabito, and M. Nitti, "The social internet of things (SIoT)—when social networks meet the internet of things: concept, architecture and network characterization," *Computer Networks*, vol. 56, no. 16, pp. 3594–3608, 2012.

[4] A. M. Ortiz, D. Hussein, S. Park, S. N. Han, and N. Crespi, "The cluster between internet of things and social networks: Review and research challenges," *IEEE Internet of Things Journal*, vol. 1, no. 3, pp. 206–215, 2014.

[5] L. Atzori, D. Carboni, and A. Iera, "Smart things in the social loop: Paradigms, technologies, and potentials," *Ad Hoc Networks*, vol. 18, pp. 121–132, 2014.

[6] L. Atzori, I. Antonio, and G. Morabito, "Making things socialize in the Internet -Does it help our lives?" in *Kaleidoscope 2011: The Fully Networked Human?-Innovations for Future Networks and Services (K-2011), Proceedings of ITU. IEEE*, 2011.

[7] L. Atzori, A. Iera, and G. Morabito, "SIoT: giving a social structure to the internet of things," *IEEE Communications Letters*, vol. 15, no. 11, pp. 1193–1195, 2011.

[8] A. M. Vegni and V. Loscrí, "A survey on vehicular social networks," *IEEE Communications Surveys & Tutorials*, vol. 17, no. 4, article no. A3, pp. 2397–2419, 2015.

[9] L. Krause, *Microservices: Patterns and Applications: Designing Fine-Grained Services by Applying Patterns*, 2015.

[10] A. Krylovskiy, M. Jahn, and E. Patti, "Designing a smart city internet of things platform with microservice architecture," in *Proceedings of the 3rd International Conference on Future Internet of Things and Cloud (FiCloud '15)*, pp. 25–30, Rome, Italy, August 2015.

[11] B. Butzin, F. Golatowski, and D. Timmermann, "Microservices approach for the internet of things," in *Proceedings of the 21st IEEE International Conference on Emerging Technologies and Factory Automation, ETFA 2016*, Germany, September 2016.

[12] N. Dragoni, I. Lanese, S. T. Larsen, M. Mazzara, R. Mustafin, and L. Safina, "Microservices: How To Make Your Application Scale," *Computing Research Repository*, 2017.

[13] "Microservices Guide Pages - Martin Fowler," 2017, https://martinfowler.com/articles/microservices.html.

[14] "Web of Objects. ITEA 3 · Project · 10028 , D2.1: State-of-the-Art Relevant to the Web of Objects," 2017, https://itea3.org/project/web-of-objects.html.

[15] "Y.4452: Functional framework of web of objects," 2017, http://www.itu.int/rec/T-REC-Y.4452-201609-P.

[16] L. E. Holmquist, F. Mattern, B. Schiele, P. Alahuhta, M. Beigl5, and H.-W. Gellersen, "Smart-its friends: a technique for users to easily establish connections between smart artefacts," in *Ubicomp 2001: Ubiquitous Computing*, pp. 116–122, Springer, Berlin, Germany, 2001.

[17] D. Guinard, M. Fischer, and V. Trifa, "Sharing using social networks in a composable Web of Things," in *Proceedings of the 8th IEEE International Conference on Pervasive Computing and Communications Workshops, PERCOM Workshops 2010*, pp. 702–707, Germany, April 2010.

[18] M. Kranz, L. Roalter, and F. Michahelles, "Things that twitter: social networks and the internet of things.' What can the Internet of Things do for the Citizen (CIoT)," in *Proceedings of the 8th International Conference on Pervasive Computing (Pervasive 2010)*, 2010.

[19] R. Girau, S. Martis, and L. Atzori, "Lysis: A platform for iot distributed applications over socially connected objects," *IEEE Internet of Things Journal*, vol. 4, no. 1, pp. 40–51, 2017.

[20] A. Pintus, D. Carboni, and A. Piras, "Paraimpu: A platform for a social Web of Things," in *Proceedings of the 21st Annual Conference on World Wide Web, WWW'12*, pp. 401–404, France, April 2012.

[21] I. Farris, R. Girau, L. Militano et al., "Social Virtual Objects in the Edge Cloud," *IEEE Cloud Computing*, vol. 2, no. 6, pp. 20–28, 2015.

[22] R. Girau, M. Nitti, and L. Atzori, "Implementation of an experimental platform for the social internet of things," in *Proceedings of the 7th International Conference on Innovative Mobile and Internet Services in Ubiquitous Computing, IMIS 2013*, pp. 500–505, July 2013.

[23] M. A. Jarwar, R. A. Abbasi, M. Mushtaq et al., "CommuniMents: A framework for detecting community based sentiments for events," *International Journal on Semantic Web and Information Systems*, vol. 13, no. 2, pp. 87–108, 2017.

[24] S. Newman, "Building microservices: designing fine-grained systems," 2015.

[25] "The Single Responsibility Principle - Programmer 97-things," 2017, http://programmer.97things.oreilly.com/wiki/index.php/The_Single_Responsibility_Principle.

[26] F. Viktor, "The DevOps 2.0 Toolkit: Automating the Continuous Deployment Pipeline with Containerized Microservices," 2016.

[27] "iCore: Internet Connected Objects for Reconfigurable Ecosystems, European FP7 Project," 2017, http://cordis.europa.eu/project/rcn/100873_en.html.

[28] D. Namiot and M. Sneps-Sneppe, "On microservices Architecture," *International Journal of Open Information Technologies*, vol. 2, no. 9, 2014.

[29] D. Bonino, M. T. D. Alizo, A. Alapetite et al., "ALMANAC: internet of things for smart cities," in *Proceedings of the 3rd*

International Conference on Future Internet of Things and Cloud (FiCloud '15), pp. 309–316, IEEE, Rome, Italy, August 2015.

[30] "Developing Microservices for PaaS with Spring and Cloud Foundry," 2017, https://www.infoq.com/presentations/microservices-pass-spring-cloud-foundry.

[31] "Microservices in action, Part 2: Containers and microservices — a perfect pair," 2017, https://www.ibm.com/developerworks/cloud/library/cl-bluemix-microservices-in-action-part-2-trs/index.html.

[32] J. E. Kim, X. Fan, and D. Mosse, "Empowering End Users for Social Internet of Things," in *Proceedings of the Second International Conference on Internet-of-Things Design and Implementation - IoTDI '17*, pp. 71–82, Pittsburgh, Pa, USA, April 2017.

[33] Z. U. Shamszaman, S. S. Ara, I. Chong, and Y. K. Jeong, "Web-of-Objects (WoO)-based context aware emergency fire management systems for the Internet of Things," *Sensors*, vol. 14, no. 2, pp. 2944–2966, 2014.

[34] S. Ali, M. G. Kibria, and I. Chong, "WoO enabled IoT service provisioning based on learning user preferences and situation," in *Proceedings of the 2017 International Conference on Information Networking (ICOIN)*, pp. 474–476, Da Nang, Vietnam, January 2017.

[35] M. A. Jarwar, S. Ali, M. G. Kibria, S. Kumar, and I. Chong, "Exploiting interoperable microservices in web objects enabled Internet of Things," in *Proceedings of the Ninth International Conference on Ubiquitous and Future Networks (ICUFN)*, pp. 49–54, Milan, Italy, July 2017.

[36] M. Kibria, S. Ali, M. Jarwar, S. Kumar, and I. Chong, "Logistic Model to Support Service Modularity for the Promotion of Reusability in a Web Objects-Enabled IoT Environment," *Sensors*, vol. 17, no. 10, p. 2180, 2017.

[37] M. Kibria, S. Fattah, K. Jeong, I. Chong, and Y. Jeong, "A User-Centric Knowledge Creation Model in a Web of Object-Enabled Internet of Things Environment," *Sensors*, vol. 15, no. 9, pp. 24054–24086, 2015.

[38] M. A. Jarwar and . Ilyoung Chong, "Exploiting IoT services by integrating emotion recognition in Web of Objects," in *Proceedings of the 2017 International Conference on Information Networking (ICOIN)*, pp. 54–56, Da Nang, Vietnam, January 2017.

[39] S. Ali, H.-S. Kim, and I. Chong, "Implementation model of WoO based smart assisted living IoT service," in *Proceedings of the International Conference on Information and Communication Technology Convergence, ICTC 2016*, pp. 816–818, October 2016.

[40] S. Kumar, M. G. Kibria, S. Ali, M. A. Jarwar, and I. Chong, "Smart spaces recommending service provisioning in WoO platform," in *Proceedings of the International Conference on Information and Communications (ICIC)*, pp. 311–313, Hanoi, Vietnam, June 2017.

[41] K. M. Alam, M. Saini, and A. El Saddik, "Toward social internet of vehicles: concept, architecture, and applications," *IEEE Access*, vol. 3, pp. 343–357, 2015.

[42] "Weka 3 - Data Mining with Open Source Machine Learning Software in Java," 2017, https://www.cs.waikato.ac.nz/ml/weka/.

[43] "Jena, Apache. &quot;A free and open source Java framework for building Semantic Web and Linked Data applications.&quot," 2017, http://jena.apache.org/.

[44] Protégé, "A free, open-source ontology editor and framework for building intelligent systems," 2017, https://protege.stanford.edu/.

Journal of
Engineering

The Scientific
World Journal

International Journal of
Rotating
Machinery

Journal of
Sensors

International Journal of
Distributed
Sensor Networks


Advances in
Civil Engineering

Hindawi

Submit your manuscripts at
https://www.hindawi.com


Journal of
Control Science
and Engineering

Journal of
Robotics

Journal of
Electrical and Computer
Engineering


Advances in
OptoElectronics

VLSI Design

International Journal of
Navigation and
Observation


Modelling &
Simulation
in Engineering

International Journal of
Aerospace
Engineering


International Journal of
Chemical Engineering


International Journal of
Antennas and
Propagation

Active and Passive
Electronic Components


Shock and Vibration


Advances in
Acoustics and Vibration

Multiple Antenna Technologies

Manar Mohaisen | YuPeng Wang | KyungHi Chang

The Graduate School of Information Technology and Telecommunications

INHA University

ABSTRACT

Multiple antenna technologies have received high attention in the last few decades for their capabilities to improve the overall system performance. Multiple-input multiple-output systems include a variety of techniques capable of not only increase the reliability of the communication but also impressively boost the channel capacity. In addition, smart antenna systems can increase the link quality and lead to appreciable interference reduction.

I. Introduction

Multiple antennas technologies proposed for communications systems have gained much attention in the last few years because of the huge gain they can introduce in the communication reliability and the channel capacity levels. Furthermore, multiple antenna systems can have a big contribution to reduce the interference both in the uplink and the downlink by employing smart antenna technology.

To increase the reliability of the communication systems, multiple antennas can be installed at the transmitter or/and at the receiver. Alamouti code is considered as the simplest transmit diversity scheme while the receive diversity includes maximum ratio, equal gain and selection combining methods. Recently, cooperative communication was deeply investigated as a mean of increasing the communication reliability by not only considering the mobile station as user but also as a base station (or relay station). The idea behind multiple antenna diversity is to supply the receiver by multiple versions of the same signal transmitted via independent channels.

On the other hand, multiple antenna systems can tremendously increase the channel capacity by sending independent signals from different transmit antennas. BLAST spatial multiplexing schemes are a good example of such category of multiple antenna technologies that boost the channel capacity.

In addition, smart antenna technique can significantly increase the data rate and improve the quality of wireless transmission, which is limited by interference, local scattering and multipath propagation. Through shaping the antenna radiation pattern and adaptively adjusting the antenna weight vector, smart antennas improve the communication link quality by increasing the received signal power and suppressing the interference.


Multiple Antenna Systems
MIMO Systems
Smart Antenna Systems
MIMO Diversity
Spatial Multiplexing & Pre-coding
RF End
Base-band (AAA)
Space Time Coding
Cooperative Commun.
Phased Antenna Array
Switched Antenna Array
Transmit Beamforming
Receive Beamforming
Increase Commu. Reliability
Full/Fractional Rate STBC/SFBC/STFBC
Increase Commu. Reliability
Virtual-MIMO
Increase Ch. Capacity & Commu. Reliability
V-BLAST/D-BLAST/ Turbo-BLAST Pre-coding (PARC, PGRC & PU^{2}RC)
Increase Commu. Reliability
Time / Frequency domain Beamformer
Increase Commu. Reliability / Low Complexity
Increase link quality / Reduce Interference
Pre-coding (Eigenvector TxBF /TxAA)
Increase link quality / Suppress Interference
SRB / TRB / SSRB

Fig. 1. Multiple antenna technologies.

Besides, on-line calibration technique is also adopted to correct the errors due to the distortions and nonlinearity of the radio frequency components in the antenna array system.

Fig. 1 summarizes the different multiple antenna technologies and gives some examples of these technologies.

This paper is organized as follows: in section II we present multiple antenna diversity schemes employed at the transmitter or/and at the receiver. Spatial multiplexing presented by BLAST schemes is detailed in section III. Section IV is dedicated to some advanced multiple input multiple-output (MIMO) systems including multi-user MIMO and cooperative communications. While techniques related to the smart antennas such as phased antenna array, switched beam antenna array, and adaptive antenna array are described in Section V. Finally, we conclude in Section VI.

II. **MIMO Diversity**

In communication systems, we have to increase the reliability of the communication operation between transmitter and receiver while maintaining a high spectral efficiency. The ultimate solution relies in the use of *diversity*, which can be viewed as a form of redundancy [1]. There are many diversity techniques that can be applied to communication systems; we mention herein time diversity, frequency diversity, and spatial diversity or any combination of these three diversities. In *time diversity*, the same information-bearing signal is transmitted in different time slots where a good gain can be achieved when the duration between the two slots, in which the same symbol is transmitted, is greater than the coherence time of the channel. In *frequency diversity*, the same information-bearing signal is transmitted on different subcarriers where a good diversity gain can be achieved when the separation between subcarriers is greater than the coherence bandwidth.

Finally, in *spatial diversity*, the same information-bearing signal is transmitted or received via different antennas where the maximum gain can be achieved when the fading occurring in the channel is independent (or low correlated). In the receiver, diversity gain can be achieved by combining the redundant signals arriving via independent (or lowly correlated) channels.

Fig. 2 shows some possible combinations of transmit diversity which can be achieved when employing multiple transmit antennas.

In the following section, we present some famous space-time block codes applied at the transmitter side. We present also the combining techniques used when different versions of the information-bearing signal are received. Finally, we present a scheme that includes transmit and receive diversities.

2.1 Space Diversity at the Transmit Side

The basic idea of the use of transmit diversity is to reduce the mobile station (MS) receiver complexity while improving the detection performance.

The pioneering work in the transmit diversity was done by Alamouti where he proposed his famous 2×1 space-time code. Alamouti scheme achieves diversity gain while requiring only a linear decoder.

Later on, Tarokh et al. proposed a generalized theory of the complex orthogonal space-time codes. Based on Tarokh work, more than two antennas can be used and the code rate can be fractional.

In the following we present the two different types of space-time codes.

2.1.1 Complex Orthogonal Space-Time Codes

For this type of space time codes, the following conditions must be satisfied

- Square transmission matrix (number of transmit antennas N_t equal to number of used time slots m)
- A unity code rate (number of used time slots m equals to number of transmitted symbols l)
- Orthogonality of the transmission matrix in the time and space domains ($\mathrm{SS}^{\mathrm{H}} = \mathrm{S}^{\mathrm{H}}\mathrm{S}$) where S^{H} is the conjugate transpose of S.



Fig. 2. Transmit diversity.



Fig. 3. Alamouti scheme example with QPSK modulation.

As said before, the simplest complex orthogonal space-time code is the Alamouti code which uses two transmit antennas and one receive antenna. Furthermore, Alamouti scheme requires that the fading channel envelope remains constant over two time slots.

Fig. 3 shows an example of the encoding process of Alamouti scheme with QPSK modulation [2], [3].

Fig. 4 shows the receiver structure used for decoding the combined received symbols.



Fig. 4. Alamouti code receiver.

At the receiver the following signals are received (with applying the complex conjugate to the received signal at t_2)

$$\begin{bmatrix} y_1 \\ y_2^* \end{bmatrix} = \begin{bmatrix} h_1 & h_2 \\ h_2^* & -h_1^* \end{bmatrix} \begin{bmatrix} s_1 \\ s_2 \end{bmatrix} + \begin{bmatrix} n_1 \\ n_2^* \end{bmatrix} \qquad (1)$$

The linear combiner multiplies the received symbols by the Hermitian transpose of the channel matrix (for simplicity, we consider that channel is perfectly estimated). The output of the linear combiner is then given by

$$\begin{bmatrix} x_1 \\ x_2 \end{bmatrix} = \begin{bmatrix} h_1^2 + h_2^2 \end{bmatrix} \begin{bmatrix} s_1 \\ s_2 \end{bmatrix} + \begin{bmatrix} w_1 \\ w_2 \end{bmatrix} \qquad (2)$$

Maximum-Likelihood (ML) decoder is then applied to get the transmitted symbols. As one can see, the simplicity of the receiver is due to the spatio-temporal orthogonality of the transmission matrix.

A complex orthogonal space-time code using 4 or 8 antennas was proposed by Tarokh et al. in [4].

2.1.2 Generalized Complex Orthogonal Space-Time Codes

The search for space-time codes with more than two antennas was started by Tarokh, Jafarkhani, and Calderbank. Their work has built the basis for a theory of generalized complex orthogonal designs.

Generalized complex orthogonal designs are distinguished from Alamouti code by the following

- A non-square transmission matrix (number of used time slots ≠ number of Tx antennas)
- A fractional code rate (number of transmitted symbols < number of used time slots)
- Orthogonality of the transmission matrix is only guaranteed in the time sense.

As a consequence of these characteristics, the spectral efficiency is reduced and the number of time slots over which the channel should be constant is increased.

The transmission matrix of a generalized complex space-time code with 3 antennas, 4 transmitted symbols and 8 used time slots is given by [5]

$$\mathbf{G_3} = \begin{bmatrix} s_1 & s_2 & s_3 \\ -s_2 & s_1 & -s_4 \\ -s_3 & s_4 & s_1 \\ -s_4 & -s_3 & s_2 \\ s_1^* & s_2^* & s_3^* \\ -s_2^* & s_1^* & -s_4^* \\ -s_3^* & s_4^* & s_1^* \\ -s_4^* & -s_3^* & s_2^* \end{bmatrix} \qquad (3)$$

In the literature, more research was done to increase the rate of the space-time codes. For more details refer to [6].

Table 1 summarizes the difference between Alamouti and space-time code characterized by the transmission matrix **G₃.**

These shown coding schemes can be transmitted in the space-time domains, space-frequency domains or in space-frequency-Time domains. These coding schemes are thus known as ST, SF, and STF coding, respectively [7].

2.1.3 Cyclic Delay Diversity (CDD)

CDD can be considered as a very simple transmit diversity scheme. CDD can achieve transmit artificial frequency diversity by selecting appropriate transmit delays. In this method, multiuser diversity, obtained by scheduling based on frequency domain channel response, can be improved by adjusting the delay spread (at the transmitter) which is done by controlling the delay values dependent on the channel condition [8], [9].

2.2 Space Diversity at the Receive Side

In space diversity at the receive side, multiple antennas are used in the receiver with sufficient spacing between antennas in such a way mutual correlation between antennas is reduced and as consequence diversity gain is increased [10]. To get diversity gain at the receiver, received signals from different antennas are combined. There are four combining methods, namely, select combining (SC), maximal-ratio combining (MRC), equal-gain combining (EGC), and square-law combining. The first three schemes are linear while the last requires a non-linear receiver.

Fig. 5 shows a simplified block diagram of the linear combining schemes which differ in the weighting vector **w.** In SC, the signal at the branch with maximum signal to noise ratio (SNR) is selected and other received signals are discarded.

The weighting vector **w** = (w_1, w_2, …, w_M) is the N^{th} column of the identity matrix of size M where the N^{th} branch has the maximum SNR.

Table 1. Comparison between Alamouti and generalized complex space-time codes.

Space-time code	**Number of Tx antennas**	**Number of transmitted symbols, *l***	**Number of used time slots, *m***	**Orthogonality of Tx matrix**	**Rate = *l/m***
S	2	2	2	Spatio-temporal sense	1
G_3	3	4	8	Only temporal sense	1/2

Table 2. Comparison between diversity combining schemes.

Scheme	**Requiring CSI**	**Outage Probability F(x)**	**Application**
SC	No	$\left[1-e^{-x/\bar{y}_c}\right]^M$	No constraints
MRC	Yes	$1-e^{-x/\bar{y}_c}\sum_{k=0}^{M-1}\frac{1}{k!}\left(\frac{x}{\bar{y}_c}\right)^k$	No constraints
EGC	Yes	No closed form for M > 2	No constraints
SLC	No	-	FSK or DS-CDMA

As one can see, the SC scheme does not require any channel information except that of SNR. On the other hand, MRC and EGC schemes require the channel state information (CSI) or a part of it (channel envelope, phase, delay). MRC scheme weights the received signals according to their reliability; a more reliable signal has a high weight while a less reliable signal has a small weight. Also, the channel phase distortion is compensated. Finally, signals are aligned then combined. On the other hand, EGC scheme can be viewed as a simplified version of MRC where signals are weighted equally (i.e. the weighting vector **w** = $[1, 1, \ldots,1]_M$) then aligned before being combined coherently. In practice, the phase at different branches can't be often estimated. So, EGC and MRC can't be employed. In such situations, square law combining (SLC) can be applied to obtain spatial diversity without requiring phase estimation. Unlike linear combining schemes, SLC scheme can only be applied to modulation schemes which preserve some sort of orthogonality including frequency-shift keying (FSK) or direct-sequence CDMA [5], [11].

Table 2 summarizes a comparison between combining schemes. It is known that, from a performance point of view, MRC is optimum and gives the best performance among the pre-described combining schemes.



Fig. 5. Simple block diagram of linear combining schemes.

2.3 Combined Transmit/Receive Diversity

Spatial diversity schemes explained in the previous two sections can be combined together to achieve diversity at both receive and transmit sides. An example of such a hybrid spatial diversity scheme is the 2×2 Alamouti/MRC MIMO system [12].

III. Spatial Multiplexing

As shown in the previous section, MIMO diversity can be used in the transmitter or the receiver sides or in both to increase the reliability of the communication. In this section we talk about spatial multiplexing schemes which are for goal to increase the channel capacity.

The most known spatial multiplexing schemes are the BLAST family which includes Vertical-BLAST, Diagonal-BLAST, and Turbo-BLAST. The acronym BLAST stands for "*Bell Laboratories Layered Space-Time*".

3.1 Diagonal-BLAST

D-BLAST was originally proposed by Foschini [13]. In D-BLAST, the symbols to be transmitted are arranged on the diagonals of the space-time transmission matrix where elements under the diagonal are padded with zeros. Fig. 6-a depicts the structure of the D-BLAST transmitter for four transmit antennas. At first, the bit stream is de-multiplexed into four parallel streams which are encoded and modulated independently. Encoded-modulated streams are cycled over time. Equation (4) is an example of the transmission matrix when using four transmit antennas.

$$S=\begin{bmatrix} s_{1,1} & s_{1,2} & s_{1,3} & s_{1,4} & \cdots & s_{1,K-1} & s_{1,K} & 0 & 0 & 0 \\ 0 & s_{2,1} & s_{2,3} & s_{2,4} & \cdots & s_{2,K-2} & s_{2,K-1} & s_{2,K} & 0 & 0 \\ 0 & 0 & s_{3,1} & s_{3,2} & \cdots & s_{3,K-3} & s_{3,K-2} & s_{3,K-1} & s_{3,K} & 0 \\ 0 & 0 & 0 & s_{4,1} & \cdots & s_{4,K-4} & s_{4,K-3} & s_{4,K-2} & s_{4,K-1} & s_{4,K} \end{bmatrix} \tag{4}$$


Demultiplexing
Encoder/ modulator 1
Encoder/ modulator 2
Encoder/ modulator 3
Encoder/ modulator 4
Cyclic Associative module
Demultiplexing
Encoder/ modulator 1
Encoder/ modulator 2
Encoder/ modulator 3
Encoder/ modulator 4

(a) D-BLAST (b) V-BLAST


Demultiplexing
Block encoder 1
Block encoder 2
Block encoder 3
Block encoder 4
Interleaver 1
Interleaver 2
Interleaver 3
Interleaver 4
Intentional Time-Varying Matrix Channel
Outer encoder
Inner encoder
Space
Layer 1
Time

(c) Turbo-BLAST (d) RLST code

Fig. 6. Transmitter block diagrams for BLAST family using four transmit antennas.

Table 3. MIMO systems diversity orders.

MIMO Configuration	Diversity order
STBC	$N_t \times N_r$
BLAST	$N_r - N_t + 1$

The first diagonal of S is transmitted via the first antenna; the second diagonal is transmitted via antenna 2, and so on.

3.2 Vertical-BLAST

A simplified version of D-BLAST was proposed by Wolniansky known as Vertical-BLAST or V-BLAST [14]. In V-BLAST, incoming data stream is de-multiplexed into N_t streams each of which is encoded and modulated independently and sent on an antenna of its own. V-BLAST high-level diagram is depicted in Fig. 6-b where four antennas are used at the transmit side. Compared to D-BLAST, V-BLAST does not include cycling over time, the complexity is significantly reduced. In addition, unlike D-BLAST, V-BLAST does not include any space-time wastage. At the receiver, transmitted symbols can be decoded using *ordered serial interference-cancellation (OSIC) detector*. For the OSIC to work properly, the number of receive antennas N_r must be at least as large as the number of transmit antennas.

3.3 Turbo-BLAST

Turbo-BLAST was first described by Sellathurai and Haykin [15]. The Turbo-BLAST transmitter structure is depicted in Fig. 6-c. The data stream bits are firstly demultiplexed into N_t parallel streams which are encoded independently using the block encoder (outer encoder) (i.e. channel coding). The output streams of the outer encoder are interleaved independently and passed to the inner encoder. The mission of the outer encoder is to achieve *random-layered space-time* (RLST) coding.

The structure of the RLST encoder, with periodical cyclic space-time interleaving is depicted in Fig. 6-d. For optimal performance of the RLST code, the receiver should employ the *maximum a posteriori probability (MAP)* decoding algorithm. Nevertheless, the complexity of the MAP decoding algorithm is very high (increases exponentially with N_t). To decrease the complexity of the receiver, the near-optimal turbo-like receiver can be used. This near-optimal turbo-like receiver is known as *iterative detection and decoding (IDD) receiver*.

Before going further, we list in Table 3 a comparison between diversity order of the different space-time coding and the BLAST family schemes.

IV. Advanced Topics

4.1 Single and Multi CodeWord MIMO

In single codeword (SCW) MIMO, an encoded packet is distributed across many streams to form the MIMO transmission. Feedback is used to control the rank of the MIMO transmission (number of streams used) as well as the overall rate of transmission. In multiple codeword MIMO, several separately encoded packets are transmitted independently over the multiple streams. Here the rate of each stream can be controlled with feedback [16] and [17].

4.2 Single-User MIMO and Multi-User MIMO

In single-user MIMO, already explained techniques in previous sections are used where the channel capacity grows linearly with *min(Nt, Nr)* [18].

For multi-user MIMO, which is of high interest research topic, it was shown that for N_t transmitting antennas (at the base station) and N_r users, the same overall capacity can be achieved. This later work was encouraged by applying dirty paper coding [19] where results showed that if the transmitter knows the interfering signal, then the channel capacity will not be affected by the presence of the interference [20]. On the other hand, multi-user MIMO can integrate beamforming to apply spatial division multiple access (SDMA).

4.3 Cooperative Communication and Virtual MIMO

In cooperative communication, a mobile can act as both a user and relay. As consequence, mobile sends to the base station its own data bits and some of other mobiles (sometimes called partner) information bits. Fig. 7 shows a cooperative cellular system where for simplicity we consider three cooperative users and one base station [21]. As depicted in Fig. 7, user 1 cooperates with users 2 and 3 to send its own information. As a result, the overall cooperative system can be seen as virtual-MIMO (V-MIMO) and in the above example it is $3\times N_{BS}$ MIMO system (for the uplink) where N_{BS} is the base station's number of receive antennas. Users 2 and 3 can simply amplify and forward user 1 received information or detect and forward [22]. Another method of cooperation is the coded cooperation where different coded portions are sent via different fading channels [23].



Fig. 7. Cooperative communication and virtual-MIMO.

4.4 Pre-Coded MIMO with Rank Adaptation

4.4.1 Per Antenna Rate Control (PARC)

PARC can be considered as a closed-loop MIMO system where transmitter uses *channel quality indication* (CQI) fed by the receiver to select the best modulation and coding schemes per antenna. Fig. (8) shows a general PARC transmitter structure with 4 transmit antennas [24].

4.4.2 Per Group Rate Control (PGRC)

In PARC, a CQI feedback is necessary for each transmit antenna. This increases the uplink overhead.



Fig. 8. Per Antenna Rate Control (PARC).

To solve this problem, PGRC is used where a feedback is required per group of antennas. This reduces the feedback information while maintaining almost the same performance of PARC [24].

4.4.3 Per User Unitary Rate Control (PU^{2}RC)

PU^{2}RC is a multi-user closed-loop MIMO system. Each user feeds back the CQI to the base station. The base station uses the CQI to determine the modulation and coding schemes per user. In addition, base station can apply unitary pre-coding and adaptively select the number of transmit antennas (rank adaption) [25].

V. Smart Antennas

5.1 Introduction

Smart antenna was born in the early 1990s when well developed adaptive antenna arrays originate from Radar system. Later, Smart antenna technique is applied in wireless communications system. Recently, Smart antenna technique has been proposed as a promising solution to the future generations of wireless communication systems, such as the Fourth-Generation mobile communication systems, broadband wireless access networks, where a wide variety of services through reliable high-data rate wireless channels are expected. Smart antenna technique can significantly increase the data rate and improve the quality of wireless transmission, which is limited by interference, local scattering and multipath propagation [26], [27]. Smart antennas offer the following main applications in high data-rate wireless communication systems [28], [29]:

- Spatial Diversity
- Co-channel interference reduction
- Angle reuse or space division multiple access (SDMA)
- Spatial multiplexing

Smart antenna system can be categorized into three main groups: Phased antenna array system, switched beam systems, and adaptive antenna array system. To match the characteristics in each radio frequency chain of the transmitter and receiver, on-line calibration is required in smart antenna systems. On-line calibration technique can compensate the errors such as the distortions of radio frequency components due to small environment changes, the nonlinear characteristics of mixer, amplifier and attenuator, I/Q imbalance errors, etc.

5.2 Phased Antenna Array System

Phased antenna array is a group of antennas in which the relative phases of the respective signals feeding the antennas are varied in such a way that the effective radiation pattern of the array is reinforced in a desired direction and suppressed in undesired directions.

Phased antenna array system is usually utilized in *radio frequency* (RF) or *intermediate frequency* (IF) with the system central frequency larger than 10 GHz, such as satellite communication system [30]. There are two main different types of phased arrays, also called beamformers. There are time domain beamformers and frequency domain beamformers.

5.3 Switched Beam System

The switched beam method is considered as an extension of the current sectorization scheme. In the switched beam approach, the sector coverage is achieved by multiple predetermined fixed beam patterns with the greater gain placed in the centre of a beam [30]. When a mobile user is in the vicinity of a beam, then the signals at the output ports will be given as in (5). This enables the switched beam system to select the signal from the output port corresponding to that beam. As the mobile moves to the coverage of another beam during the call, the system monitors the signal strength and switches to other output ports as required. A basic switched beam antenna architecture is shown in Fig. 9. And Fig. 10 illustrates the produced antenna pattern with 4 antennas.

$$y_i(t) = s_i(t)G_i(t)\sum_{l=1}^{L} I_l(t)G_{li}(\theta_l) \qquad (5)$$

where $y_i(t)$ is the total signal appearing at port i, $s_i(t)$ is the signal source, $I_l(t)$ is the interfering signal source located at arbitrary angles θ_l, G_i is the transfer function between signal source along the main beams and their corresponding output ports, G_{li} is the transfer function between interference signal l and port i.



Fig.9. Functional block diagram of switched beam system.



Fig.10. Produced antenna pattern of switched beam system with 4 antennas.

Switched beam systems can offer several advantages, including

- Low complexity and cost. Since switched beam system only requires a beamforming network, RF switches, and simple control logic, they are relatively easy and cheap to implement.
- Moderate interaction with base station receivers. In practice, switched beam system can simply replace conventional sector antennas without requiring significant modifications to the radio base station antenna interface or the baseband algorithms implemented at the receiver.
- Coverage extension. The antenna array aperture gain will boost the link

budget, which could be translated to a coverage extension.

5.4 Adaptive Antenna Array System (AAA)

Adaptive antennas date back to 1959. The original work was attributed to L. C. Van Atta's work, Electromagnetic Reflection. Since then, adaptive beamforming techniques have been employed to remove unwanted noise and jamming from the output, mainly in military applications. With the thriving commercial wireless communication industry and the advancing microprocessor technologies, the adaptive beamforming techniques have found their applications in commercial wireless communications. With powerful *digital signal processing* (DSP) hardware at the base-band, algorithms could control antenna beam patterns adaptively to the real signal environment, forming beams towards the desired signals while forming nulls to co-channel interferers. Thus, the system performance is optimized in terms of link quality and system capacity [31].
Adaptive antenna array can be utilized in the transmitter side, which is known as *transmit beamforming* (TxBF) or in the receiver side, which is called *receive beamforming* (RxBF).

5.4.1 Transmit Beamforming (TxBF)

The implementation of adaptive antenna array technique in a handset is difficult with today`s hardware due to its limitations in size, cost, and energy storage capability, while it is feasible to adopt antenna arrays at base stations. Transmit beamforming provides a powerful method for increasing downlink capacity [32]-[35]. The idea of TxBF is similar to the pre-coded MIMO technique but with different strategies to calculate the transmit weight vector. TxBF adjusts the antenna main lobe towards to the desired user and reduce the interference to other users. A simple illustration of TxBF is shown in Fig. 11.



Fig.11. An illustration of TxBF.

Eigenvector TxBF Algorithm

Eignenvector TxBF algorithm is widely used for TxBF. The eigenvector of the spatial covariance channel matrix is calculated as

$$\mathbf{R}_{ss} = \boldsymbol{\lambda}\mathbf{H} \qquad (6)$$

where $\mathbf{R}_{ss}$ is the autocovariance matrix of the desired user`s signal, and $\mathbf{H}$ is the spatial covariance channel matrix. The eigenvector $\boldsymbol{\lambda}_{max}$ which corresponds to the largest eigenvalue will be selected as the weight vector [36]. One example of beam pattern for 4 uniform linear array elements is shown in Fig 12.



Fig. 12. Example beam pattern of 4 antenna elements in a sectorized system for a single sector (main beam direction is 240°).

Transmit Adaptive Array (TxAA) Algorithm

Transmit adaptive array (TXAA) is a technique in which the user periodically sends quantized estimates of the optimal transmit weights to the BS via a feedback channel. The transmitter weights are optimized to deliver maximum power to the user. The optimal transmit weights are given by

$$\mathbf{w} = \mathbf{H}^H / \mathbf{H}\mathbf{H}^H \qquad (7)$$

where **w** is the transmit weight vector and **H** is the channel matrix.

The weights are normalized so that the total transmitted power is not altered. In the case of multipath channels emanating from each antenna, the optimal weights will be given by the principal eigenvector of the channel correlation matrix $\mathbf{H}^H\mathbf{H}$.

5.4.2 Receive Beamforming (RxBF)

Beamforming also can be applied in the uplink to improve the link quality and suppress the co-channel interference, which is known as *receive beamforming* (RxBF). Through RxBF, smart antenna system can receive predominantly from a desired direction (direction of the desired source) compared to some undesired directions (direction of interfering sources). This implies that the digital processing has the ability to shape the radiation pattern to adaptively steer beams in the direction of the desired signals and put nulls in the direction of the interfering signals. This enable low co-channel interference and large antenna gain to the desired signal.

Based on the reference signals adopted in the beamforming algorithms, RxBF can be classified into *spatial reference beamforming* (SRB), *temporal reference beamforming* (TRB), and *signal structure reference beamforming* (SSRB).

Spatial Reference Beamforming (SRB)

Spatial reference beamforming method is sometimes referred as *direction of arrival* (DoA) method. SRB estimates the direction of arrival of the signal based on the spatial reference signal, using any of the techniques like *multiple signal classification* or *estimation of signal*


Antenna Array
Element Signals
Adaptive Weight Coefficients
$X_1(k)$
$X_2(k)$
$X_N(k)$
W_1
W_2
W_N
Σ
Y(k)
Beamformer Output
Desired Signal
Interfering Signals
Beampattern For Desired User
DoA Estimation and Tracking
Beam Synthesis

Fig. 13. A general structure of SRB.

parameters via rotational invariance techniques algorithms or their derivatives. They involve finding a spatial spectrum of the antenna/sensor array, and calculating the DoA from the peaks of this spectrum [37]. A general architecture of SRB algorithm is shown in Fig. 13. The general steps of SRB method are shown as follows:

- DoA Estimation
    - Arbitrary Array: MUSIC, etc.
    - Linear Array: ESPRIIT, etc.
- Beam Synthesis
    - Gram-Schmidt, etc.
- Combining
    - EGC, MRC, Wiener Filter, etc.

Multiple signal classification (MUSIC) algorithm estimates the DoA of the desired signal by using an eigen-space method based on a spatial reference signal. MUSIC requires intensive calculation of eigenvalues and eigenvectors of an autocorrelation matrix of the input vectors from the receiving antenna array. A general step of MUSIC algorithm is shown below:

- Collect received samples and estimate the covariance matrix of the received samples.
- Perform eigen-decomposition of the covariance matrix.
- Calculate spatial spectrum.
- Estimate DoA by locating peaks in the spectrum.

Estimation of signal parameters via rotational invariance techniques (ESPRIT) is also well known for the SRB method. In addition, ESPRIT has many important advantages over MUSIC algorithm [38]:

- No knowledge of the array geometry and element characteristics are required.
- Much less complex on computation.
- No calibration of the array is required.
- The algorithm simultaneously estimates the number of sources and DoA`s


Antenna
Array
Element Signals
Adaptive
Weight
Coefficients
$X_1(k)$
$X_2(k)$
$X_N(k)$
W_1
W_2
W_N
Σ
Y(k)
Beamformer
Output
Desired Signal
Interfering Signals
Beampattern
For
Desired User
Adaptive
Algorithm
e(k)
-
+
r(k)
Error
Signal
Reference
Signal

Fig. 14. A general structure of TRB.

Temporal Reference Beamforming (TRB)

Temporal Reference Beamforming shown in Fig. 14, is a method used to create the radiation patter of the antenna array by adding constructively the phases of the signals in the DoA of the desired user, and nulling the pattern of the interfering users based on the temporal reference signal [39]. Based on the temporal reference signal and some predefined adaptive weight calculation criterion, some adaptive algorithms such as LMS (Least Mean Square), RLS (Recursive Least Squares), and DSMI (Direct Sample Matrix Inverse) algorithms, are used to adjust the weight vector of the antenna array to improve the link quality. The general characteristics of TRB are as follows:

- Good performance in multipath channel environment
- Computationally inexpensive
- Requiring Training sequence
- Difficult to apply TxBF because of the absence of DoA information

Criterion of Adaptive Weight Calculation

In the *minimum mean-square error* (MMSE) criterion, the weights are chosen to minimize the *mean-square error* (MSE) between the beamformer output and the temporal reference signal. While in the *maximum signal-to-interference ratio* (MSIR) criterion, the weights are chosen to directly maximize the signal-to-interference ratio (SIR). And The *minimum variance* (MV) criterion chooses the weights that minimize the variance of the output power. All the above three criterions has the same form of

$$\mathbf{w}_{opt} = \beta \mathbf{R}_i^{-1} \mathbf{v} \tag{8}$$

where $\mathbf{R}_i^{-1}$ is the inverse of the covariance matrix of the interference signals received in the antenna array and **V** is the antenna array propagation vector [40].

Let us assume that *d(t)* is the transmitted temporal reference signal and $\mathbf{R}_u$ is the covariance matrix of interference signals at the output of the beamformer. The calculation of β for MMSE, MSIR

Table 4. β Calculation.

Criterion	MMSE	MSIR	MV
β	$\frac{E\{d^2(t)\}}{1+E\{d^2(t)\}\mathbf{v}^H\mathbf{R}_i^{-1}\mathbf{v}}$	$\frac{E\{d^2(t)\}}{SIR}\mathbf{v}^H\mathbf{w}_{opt}$	$\frac{g}{\mathbf{v}^H\mathbf{R}_u^{-1}\mathbf{v}}$

and MV criterions are summarized in Table 4.

Adaptive Beamforming Algorithm

The *least mean square* (LMS) algorithm uses the temporal reference signal to update the weights at each iteration. In the LMS algorithm, we are searching for the optimal weight that would make the array output either equal or as close as possible to the reference signal, which is the weight that minimizes the MSE. Since the MSE has a quadratic form, moving the weights in the negative direction of the gradient of the MSE should lead us to the minimum of the error surface. The weight update equation is shown in (9) [30].

$$\mathbf{w}(t+1)=\mathbf{w}(t)-\mu\mathbf{x}(t+1)\varepsilon^* \qquad (9)$$

where μ is a constant, called the step size, which determines how close the weights approach the optimum value after each iteration and it controls the convergence speed of the algorithm. And ε is the error signal between the temporal reference signal and the received signal at the beamformer output. **x**(t+1) is the received signal vector at the antenna array at time *t+1*.

The main drawback of the LMS algorithm is that it is sensitive to the scaling of its input. This makes it very hard (if not impossible) to choose a step size μ that guarantees stability of the algorithm. The *normalized least mean square* (NLMS) algorithm is a variant of the LMS algorithm that solves this problem by normalizing with the power of the input. The weights updating function of NLMS algorithm is shown as

$$\mathbf{w}(t+1)=\mathbf{w}(t)+\frac{\hat{\mu}}{a+\|x(t)\|^2}\mathbf{x}(t)\varepsilon^* \quad (10)$$

Recursive least square (RLS) algorithm is derived to overcome the drawback of slow convergence speed in the LMS algorithm, when the eigenvalue spread of the correlation matrix R of received signal vector **x** is large. RLS algorithm replaces the step size μ with the inverse of R. The weights are then updated using (11).

$$\mathbf{w}(t+1)=\mathbf{w}(t)-\mathbf{R}^{-1}\mathbf{x}(t+1)\varepsilon^* \quad (11)$$



Fig. 15. Performance comparison among LMS, NLMS, and RLS algorithms.

Fig. 15 shows a simple performance comparison of the above three algorithms in OFDMA system under the Rayleigh fading channel with 8 antenna elements [41]. From this figure, we see that RLS algorithm performs best due to its faster convergence speed than LMS and NLMS algorithms.

Signal Structure Reference Beamforming (SSRB)

SSRB method is based on inherent structure of the transmit signal of the implicit kind reference signal. Algorithms such as blind beamforming, least squares, and constant modulus algorithms, are based on the SSRB method. SSRB method is robust against different propagation conditions and does not require the array manifold knowledge. But the convergence problem becomes the main drawback of the SSRB method.

VI. Conclusions

In this paper we introduced the multi antenna technologies which can be considered as one of the most vivid area of research. Multiple antenna technologies were categorized into two main groups where in the first group we introduced some techniques related to spatial diversity and spatial multiplexing by outlining the gain achieved by these schemes. Furthermore, we introduced the smart antenna techniques and the up-to-date research progress in this field.

The advantages of multiple antenna systems make of them a very strong candidate to increase link reliability, increase channel capacity and reduce interference in both uplink and downlink.

References

[1] A. Goldsmith, *Wireless Communications*, Cambridge Univ. Press, 2005.

[2] M. Alamouti, “A simple transmit diversity technique for wireless communications”, *IEEE J. Sel. Area Commun.,* 16, pp. 1451-1458, 1998.

[3] G. Tsoulos, *MIMO System Technology for Wireless Communications*, Taylor and Francis, 2006.

[4] V. Tarokh et al., “Space-time block codes from orthogonal designs”, *IEEE Trans. Inf. Theory,* vol. 45, no. 5, pp. 1456-1467, 1999.

[5] S. Haykin and M. Mohr, *Modern Wireless Communications,* Pearson Prentice Hall, 2005.

[6] W. Su and X-G. Xi, “Two generalized complex orthogonal space-time block codes of rates 7/11 and 3/5 for 5 and 6 transmit antennas”, *IEEE Trans. Inf. Theory,* vol. 49, no. 1, pp. 313-316, Jan 2003.

[7] K. Suto, and T. Ohtsuki, “Space-time-frequency block codes over frequency selective fading channels,” *IEICE Trans. Commun.,* vol. E87-B, no. 7, pp. 1939-45, July 2004.

[8] NTT DoCoMo, “Multi-degree cyclic delay diversity with frequency-domain channel dependent scheduling”, *3GPP TSG-RAN WG1 meeting #44bis*, R1-060991, Mar. 2003.

[9] Samsung, “Adaptive cyclic delay diversity,” *3GPP TSG-RAN1 43#*, R1-051354, 7th – 11st, Nov. 2005, Seoul, Korea.

[10] G. Stüber, *Principles of Mobile Comm-unication,* Kluwer, 2001.

[11] M. K. Simon and M-S. Alouini, *Digital Communication over Fading Channels*, Wiley, 2005.

[12] E. Biglieri et al., “Diversity, interference cancellation and spatial

multiplexing in MIMO mobile WiMAX systems", *to appear in IEEE WiMAX '07*, 2007.

[13] G. Foschini, "Layered space-time architecture for wireless communication in fading environment when using multi-element antennas", *Bell Labs Technical Journal,* Autumn 1996.

[14] P. Wolniansky et al., "V-BLAST: an architecture for realizing very high data rates over the rich-scattering wireless channel", *URSI International Symposium on Signals,* Systems and Electronics, 1998.

[15] M. Sellathurai and S. Haykin, "TURBO-BLAST for wireless communications: theory and experiments", *IEEE Trans. Signal Processing,* vol. 50, no., 10 pp. 2538-2546, Oct. 2002.

[16] A. Hottinen et al., "Industrial embrace of smart antennas MIMO," *IEEE Wireless Commun. Mag.*, Aug. 2006.

[17] A. Jette et al. "UMBFDD candidate proposal for IEEE 802.20," IEEE C802.20-07/09, Mar. 2007.

[18] A. Goldsmith et al., "Capacity limits of MIMO channels," *IEEE J. on Sel. Areas in Commun.*, vol. 21, no. 5, pp. 684-702, Jun. 2003.

[19] M. Costa, "Writing on dirty paper," *IEEE Trans. Info. Theory*, vol. 29, no. 3, pp. 439-441, May 1983.

[20] Q. Spencer et al., "An introduction to the multi-user MIMO downlink," *IEEE Commun. Mag.,* pp. 60-67, Oct. 2004.

[21] A. Nosratinia and A. Hedayat, "Cooperative communication in wireless networks," *IEEE Communications Magazine,* pp. 74-80, Oct. 2004.

[22] J. Laneman et al., "An efficient protocol for realizing cooperative diversity in wireless networks," *Proc. IEEE ISIT*, June 2001, pp.294.

[23] T. Hunter and A. Nosratinia, "Diversity through coded cooperation," *IEEE Trans. on Wireless Commun.,* vol. 5, no. 2, pp. 1-7, Feb. 2006.

[24] Texas Instruments, "MIMO OFDMA E-UTRA proposal for different antenna configurations," *3GPP TSG RAN1 WG1 #43*, R1-051315, Nov. 2005.

[25] Samsung, "Downlink MIMO for EUTRA," *3GPP TSG RAN1 WG1 #43*, R1-051353, Nov. 2005.

[26] S. Ohmori, Y. Yamao, and N. Nakajima, "The future generationsof mobile communications based on broadband access technologies," *IEEE Commun. Mag.,* vol. 38, pp. 134–142, Dec. 2000.

[27] K. Sheikh, D. Gesbert, D. Gore, and A. Paulraj, "Smart antennas for broadband wireless access networks," *IEEE Commun. Mag.,* vol. 37, pp. 134–142, Nov. 1999.

[28] A. Lozano, F.R. Farrokhi, and R.A. Valenzuela, "Lifting the limits on high-speed wireless data access using antenna arrays," *IEEE Commun. Mag.,* pp. 156–162, Sept. 2001.

[29] Jeffrey H. Reed," Smart antennas: A system level overview for software defined radios for creating an API", SDRF-04-I-0057-V0.00, Software Defined Radio Forum, Jan. 2004.

[30] Ahmed EI Zooghby, *Smart Antenna Engineering*, Artech House, 2005.

[31] Michael Chryssomallis, "Smart antennas", *IEEE Antennas and Propagation Mag.,* vol. 42, pp.129-136, , June 2000.

[32] H. Boche and M. Schubert, "Theoretical and experimental comparison of optimization criteria for downlink beamforming," *European*

Trans. on Telecomm., vol. 12, no. 5, pp. 417–426, 2001.

[33] R. M. Buehrer, A. G. Kogiantis, S.-C. Liu, J. Tsai, and D. Uptegrove, “Intelligent antennas for wireless communications -uplink,” *Bell Labs Technical Journal,* vol. 4, no. 3, pp. 73–103, 1999.

[34] H. Holma and A. Toskala, *WCDMA for UMTS*, John Wiley & Sons, 2000.

[35] A. Yener, R. D. Yates, and S. Ulukus, “Interference management for CDMA systems through power control, multiuser detection, and beamforming,” *IEEE Trans. on Comm.,* vol. 49, no. 7, pp. 1227–1239, 2001.

[36] S.J. Ko, J. Heo, and K.H. Chang, "An effective downlink resource allocation for supporting heterogeneous traffic data in an OFDM/SDMA-based cellular system," *in Proc. IEEE GLOBECOM*, Nov. 2006, WLC27-5.

[37] Lal C. Godara, “Application of antenna arrays to mobile communications, part II: beam-forming and direction-of-arrival considerations”, *IEEE Proc.,* vol .85, pp.1195-1245, Aug. 1997.

[38] Haardt, M., Nossek, J.A., “Unitary ESPRIT: how to obtain increased estimation accuracy with a reduced computational burden,” *IEEE Trans. on Signal Processing,* vol.43, pp. 1232 -1242, 1995.

[39] B. L. P. Cheung, Simulation of Adaptive Array Algorithms for OFDM and Adaptive Vector OFDM Systems, Master of Science in Electrical Engineering of Virginia Polytech., Sept. 2002.

[40] John Litva and Titus Kwok-Yeung Lo, *Beamforming in Wireless Communication*, Artech House, 1996.

[41] J. Heo and K.H. Chang, "Transmit and receive beamforming for OFDMA/TDD system," *in Proc. ISAP*, Aug. 2005, pp.27-30.

Manar Mohaisen

July, 2001: BS, Communication and Control, University of Gaza, Gaza, Palestine

Sep., 2005: MS，The School Polytechnic of Nice University, Sophia-Antipolis, France

Feb., 2006 ~ Present: Ph.D. student, The Graduate School of IT & T, INHA University

2001 ~ 2003: The Palestinian Telecommunication Company (JAWWAL)

<Rresearch Interests> MIMO Detection and Co-Channel Interference Cancellation

Yupeng Wang

July, 2004: BS, Communication Engineering, Northeastern University, Shenyang, China

July, 2006: MS, The Graduate School of IT & T, INHA University

Sep., 2006 ~ Present: Ph.D. student, The Graduate School of IT & T, INHA University

<Research Interests> 3GPP LTE Systems, Radio Resource Management, MIMO Techniques, and UWB

KyungHi Chang

Feb., 1985: BS, Electronics Engineering, Yonsei University

Feb., 1987: MS, Electronics Engineering, Yonsei University

Aug., 1992: Ph.D., EE Dept., Texas A&M Univ.

1989 ~ 1990: A Member of Research Staff, Samsung Advanced Institute of Technology (SAIT)

1992 ~ 2003: A Principal Member of Technical Staff (Team Leader), Electronics and Telecommunications Research Institute (ETRI)

2003 ~ Present: Associate Professor, The Graduate School of IT & T, INHA University

<Research Interests> RTT design for IMT-Advanced & 3GPP LTE Systems, WMAN System Design, Cognitive Radio, Cross-layer Design, and Cooperative Relaying System

arcep
autorité de régulation
des communications électroniques
et des postes

RÉPUBLIQUE FRANCAISE

5G: ISSUES & CHALLENGES

March 2017

The issues and challenges surrounding 5G

The telecoms industry is currently in the process of designing the technologies that are due to take over from 4G, which is still being deployed today. A great deal of work is thus underway to prepare these “5G” technologies.

To prepare for the arrival of this new generation of technologies, Arcep wanted to take a detailed look at the industry to better understand what is in the works. This report is the fruit of the interviews and research that Arcep conducted over the course of 2016, and which the Authority wanted to publish as a way to contribute to the public debate over 5G.

Its aim it to provide as objective and exhaustive an overview as possible, and deliver a concise, informative snapshot of the work that is currently underway on the future generation of mobile networks.

This report reflects the views of the stakeholders who were interviewed, but in no way represents Arcep’s positions on or roadmap for 5G. Arcep awarded in 2015 the 700 MHz band and is currently working towards licensing the 3.5 GHz band, both of which have been identified as 5G bands. Arcep is also working with the Direction générale des entreprises and the Agence nationale des fréquences towards enabling spectrum for 5G.

Arcep would like to thank all of the entities (listed on the last page) who agreed to take part in this process, and who were willing to contribute to the regulator’s investigation into the development of 4G’s successor. Arcep is dedicated to sustaining an ongoing dialogue with the market, and invites all interested parties to provide information on the matter or to share their reactions to this report, by contacting Arcep’s Mobile and Innovation Directorate at the following address: 5G@arcep.fr.

Table of Contents

INTRODUCTION: THE VISION FOR 5G, CREATING AN ULTRA-CONNECTED SOCIETY 4

1 5G OBJECTIVES 7

1.1 TECHNICAL SPECIFICATIONS OF 5G.. 8
1.2 5G USE CASES 10
1.3 JUMP IN PERFORMANCE COMPARED TO 4G NETWORKS 12
1.4 NETWORK SLICING AND SOFTWARE-DEFINED NETWORKS... 14
1.5 TECHNOLOGICAL BUILDING BLOCKS TO ACHIEVE THE OBJECTIVES 15
1.5.1 AIR INTERFACE.. 15
1.5.2 NETWORK ARCHITECTURE.. 17
1.5.3 5G: A MULTI-TECHNOLOGY GENERATION COHABITATING WITH EXISTING NETWORKS................................ 19

2 5G DEVELOPMENT INITIATIVES 21

2.1 GOVERNMENT INITIATIVES 21
2.1.1 IN EUROPE.. 21
2.1.2 WORLDWIDE (EXAMPLES IN THE US, SOUTH KOREA, JAPAN AND CHINA) 23
2.2 A HOST OF PRIVATE INITIATIVES – A FEW EXAMPLES 24

3 THE CHALLENGES OF 5G 26

3.1 NEW BUSINESS MODELS FOCUSED ON VERTICAL MARKETS 26
3.1.1 THE AUTOMOTIVE SECTOR.. 26
3.1.2 INDUSTRY 4.0 27
3.2 SPECTRUM HARMONISATION 28
3.2.1 MILLIMETRE WAVE FREQUENCIES 28
3.2.2 FREQUENCY BANDS BELOW 6 GHZ.. 29
3.3 INCREASINGLY SMALL CELLS 30
3.3.1 TAXATION.. 31
3.3.2 ACCESS TO ELEVATED AND “SEMI-ELEVATED” LOCATIONS 31
3.3.3 5G NETWORKS’ REGIONAL COVERAGE AND BACKHAUL 32
3.4 NET NEUTRALITY ISSUES 32

ANNEX 1 DEFINITION AND STANDARDISATION WORK.. 35

ANNEX 2 ENTITIES ARCEP MET WITH.. 40

ANNEX 3 FIGURES.. 41

Introduction: the vision for 5G, creating an ultra-connected society

5G wants to be the disruptive generation, the generation that no longer only caters to the needs of mobile operators and consumer communications, but which opens up new prospects and enables an extremely wide diversity of applications and use, unified within a single technology. 5G is setting itself up as an enabler of the digitisation of society and the economy.

The idea that is starting to take shape behind the notion of 5G is that it will not mean just an increase in transmission speeds, as has been the case with previous generations.

Consumer mobile communications, video downloads and the use of mobile apps account for the bulk of 4G networks' radio resources usage today. With 5G, the goal will be to enable a much broader spectrum of uses and a much greater diversity of users.

5G is targeting a wide variety of sectors, which will not necessarily have anything other than this technology in common, but which are central pillars in a society: energy, healthcare, media, industry and transportation.


FACTORIES OF THE FUTURE
❶ Time-critical process control
❷ Non time-critical factory automation
❸ Remote control
❹ Intra/Inter-enterprise communication
❺ Connected goods
ENERGY
❶ Grid access
❷ Grid backhaul
❸ Grid backbone
e-HEALTH
❶ Assets and interventions management in Hospital
❷ Robotics
❸ Remote monitoring
❹ Smarter medication
24h
MEDIA & ENTERTAINMENT
❶ Ultra High Fidelity Media
❷ On-site Live Event Experience
❸ User/Machine Generated Content
❹ Immersive and Integrated Media
❺ Cooperative Media Production
❻ Collaborative Gaming
AUTOMOTIVE
❶ Automated driving
❷ Share My View
❸ Bird's Eye View
❹ Digitalization of Transport and Logistics
❺ Information Society on the road

Figure 1. 5G driving industrial and societal changes[1]

The energy sector, for instance, has undergone a great many changes and developments over the past several years in terms of energy production, storage and transport. Rising fossil fuel costs, the introduction of renewable energy sources and markets being opened up to competition have all helped usher in new kinds of energy product and new stakeholders – both independent companies and ordinary citizens – to the energy marketplace. The objective with 5G will thus be to enable better management of these networks (smart grids, smart agriculture, factories of the future) and their interconnections, to achieve more efficient and more agile distribution.

---

[1] 5G Empowering vertical industries. White Paper, 2016, https://5g-ppp.eu/wp-content/uploads/2016/02/BROCHURE_5PPP_BAT2_PL.pdf

Healthcare, transportation and media are sectors that are bound up with our fellow citizens' daily lives: any improvements in these sectors thus have a clearly visible impact. The introduction of robots to perform specialised surgical operations, of video on demand or the advent of new connected features in cars have already improved our daily lives. 5G is promising to go several steps further in all of these areas: it would enable remote medical diagnoses and operations in real time, it would democratise streaming of 360° 3D video, it would provide users with a vast selection of video content with a picture quality better than ultra high-definition (4K, 8K…). The automotive universe could rely on these new networks to help cars make decisions without human involvement, and also communicate with one another (this is already possible, for instance, with the first experimental fleet of fully autonomous taxis being tested on the streets of Singapore by the firms nuTonomy and Grab[2]), with reaction times that are compatible with the demands of high-speed travel.

In terms of factories of the future, the improvements brought by 5G are primarily targeting the introduction of new generations of connected robots, the interconnection of production sites and the much heavier use of smart sensors to improve industrial processes. Generally speaking, the aim is to achieve ubiquitous communication between machines, a process that is already well underway.

One thing that it is crucial to understand, through the few examples listed above whose demands might seem mutually incompatible, is that depending on the sector or the application, the network properties and the functionalities required will not be the same. Service providers – whether they are today's mobile operators or other market players – will need to be capable of adapting their network to demand, occasionally in real time. 5G will thus be not so much a universal technology as a polymorphous, or multi-faceted technology, capable of adapting to any use, up to and including the most demanding ones.

---

[2] http://nutonomy.com/


FACTORIES

AUTOMOTIVE

e-HEALTH

ENERGY

MEDIA & ENTERTAINMENT

Figure 2. Performances required by vertical sectors[3]

---

[3] 5G Empowering vertical industries. White Paper, 2016, https://5g-ppp.eu/wp-content/uploads/2016/02/BROCHURE_5PPP_BAT2_PL.pdf

1 5G objectives

Ever since the first real mobile telephone call, 44 years ago[4], mobile technologies have been evolving steadily and their performances have improved exponentially: as mentioned earlier, calling services and later texting and finally the mobile internet and the use of multi-service mobile applications have characterised the evolution of mobile networks and the transition from one generation to the next. The birth of LTE technology and the fourth generation (4G), coupled with the widespread use of smartphones and tablets, have driven a massive increase in the amount of mobile data traffic being relayed over the networks.

The use of a mobile handset and its applications is now an integral part of our fellow citizens' daily habits. Portable connected devices are increasingly powerful: in many instances they have replaced users' landline telephones, cameras, computers and even televisions. Today, 5 million videos are watched on YouTube and 67,000 images uploaded to Instagram every minute (see Figure 3).



Figure 3. What we do over the network today in one minute[5]

The latest *Mobility Report*[6] from Ericsson indicates that traffic on mobile networks almost doubled in a single year, and that over the next five years it will have increased to 10 times what it is today. New solutions must therefore be found to meet this demand, and to optimise how resources are used.

The increase in the number of applications available, their diversification and the improved quality of mobile networks have all contributed to driving up demand, the emergence of new uses (connected objects, drones, etc.) and new users.

---

[4] On 3 April 1973, Motorola's Martin Cooper made a call from the corner of 56th street in New York City with the first mobile phone.

[5] https://www.ericsson.com/res/docs/2014/5g-what-is-it-for.pdf

[6] https://www.ericsson.com/assets/local/mobility-report/documents/2016/ericsson-mobility-report-november-2016.pdf

5G is at the crossroads of these news uses; it aims to better and simultaneously satisfy this tremendous variety of needs and these new demands, through a unified technology that takes this diversity into account at the design stage.

The advent of 5G could have a significant impact not only in the technical realm, but also on different countries' economic and social development. As indicated in the introduction, 5G targets a very large number of sectors and, through society's digitisation, is expected to contribute to countries' economic growth.

To give an example, according to a report produced by InterDigital Europe, Real Wireless, Tech4i2 and Connect (Trinity College Dublin)[7], this new technology will require a great deal of money and a great deal of work, but will generate €113.1 billion in profits per annum for the European economy by 2025.

1.1 Technical specifications of 5G

The specifications for a new generation of mobile telephony are set primarily by two bodies: ITU (International Telecommunication Union) and 3GPP (3rd Generation Partnership Project).

ITU is the United Nations agency devoted to information and communications technologies. It carries out research and studies through its Working Party 5D, the sub-group responsible for the overall radio system aspects of international mobile telecommunications (IMT). In 2013, this group began working on defining the characteristics of the new IMT standard, IMT-2020 (5G) (cf. 1.3), as it had done back in the early 2000s to define 4G (IMT-Advanced). Further details on the roadmap established for this work can be found in Annex 1, the objective set by ITU-R being to complete its analyses by 2020.

Parallel to the work being done by ITU are the studies being conducted by 3GPP. The 3rd Generation Partnership Project was created in 1998, and its members include seven standardisation bodies, several hundred industry players, associations and public organisations. It is responsible for developing and maintaining technical specifications for mobile telephony standards[8]. When a new standard is being defined by ITU, 3GPP works on the technical solutions that make it possible to achieve the objectives set by ITU.

Although 5G is one of the most widely debated topics inside international and European bodies today, no standard has yet been defined by 3GPP. The draft of Release 15, the first 5G standard from 3GPP, is still in the works: definition of the new architecture began in December 2016 and work on the New Radio (NR) interface is set to begin in March 2017. A first Release of the standard should be validated in September 2018 to meet the more urgent demands; a second Release (3GPP Release 16) will then be published in March 2020. All of these elements are addressed in more detail in Annex 1.

It should also be said that the transition from one generation to the next takes place gradually. LTE will continue to evolve alongside NR, and these two standards will likely be very complementary initially. In particular, for pioneer 5G rollouts LTE shall probably remain the master of the network and control the NR antennae. Moreover, some of the objectives set for 5G could be achieved thanks to functionalities or technologies introduced in 3GPP Releases 13, 14 and 15 that will not be proper to 5G, but rather evolutions of 4G (which some refer to as 4.9G or LTE Advanced Pro).

---

[7] http://ir.interdigital.com/file/Index?KeyFile=36051369

[8] GSM for 2G, UMTS for 3G and LTE for 4G


WRC'19
(Potential >6 GHz)
03/2016
06/2017
Olympic 2018
(Pyeongchang)
09/2018
12/2019
Olympic 2020
(Tokyo)
Rel-13
Rel-14
Rel-15
Rel-16
Rel-17
IMT-2020 submission
LTE-A Pro evolution
5G Requirements
5G SI: New Radio Access Technology
5G Phase-1
5G Phase-2
5G NR
L1/L2
Dec/2017
5G SA NR
Higher Layers
Jun/2018
SA and NSA development in parallel, with
NSA enjoys certain priority
SA: Standalone
NSA: Non-standalone
SI: Study Item
WI: Work Item
2016
2017
2018
2019

Figure 4. 3GPP timeline for 5G[9]

This same momentum occurred when making the transition from 3G (Release 4) to 4G (Release 10, first Release of IMT-Advanced): the first LTE specifications (Releas*es* 8 & 9) do not achieve all of the ITU targets for 4G, and reprised many of the characteristics of the most advanced form of 3G at the time.

The synergies between the successive generations, the absence in most instances of a great initial jump in performances between generations, and the race between competitors to outperform one another and be the most innovative, can often lead operators and equipment suppliers to give a "commercial" name to each generation of mobile telephony. For instance, in the United States AT&T had called its HSPA network 4G, while in France it is a 3G+ network.

So in all likelihood the first 5G networks deployed on a large scale will be 4.9G systems, using carrier aggregation, massive MIMO (Multiple-Input Multiple-Output) and Network Function Virtualization, or NFV (cf. trials conducted in in France, detailed in Section 1.5.3). These technologies, which will be explored in greater detail further on, represent more of an evolution of the fourth generation than an actual transition to 5G, which will occur when disruptive technologies such as NR carriers in millimetre bands, non orthogonal multiple access (NOMA*)* and mobile edge computing (MEC) can be put into place.

In addition to this commercial race, equipment suppliers – often backed by their respective government at home, notably in the United States, Japan and South Korea – want to get a head start in defining and testing 5G technologies, in the hope of establishing themselves as the technological leaders in international standardisation bodies. Here, the precocity of the first rollouts announced in South Korea (5G deployment for the Winter Olympics in 2018 in Pyeongchang) and Japan (5G deployment for the Summer Olympics in Tokyo) would justify the supposition that only a small portion of 5G technologies will be used, and that these rollouts will be based more on 4.9G or pre-5G technologies.

---

[9] http://gsacom.com/paper/intel-5g-technology-mm-wave-frequencies/

1.2 5G use cases

Three main use cases (defined by ITU, under IMT-2020), with their respective – and potentially mutually incompatible – demands are in the process of taking shape, and will make it possible to meet the sector-specific needs referred to in the introduction.

1. **mMTC – Massive Machine Type Communications**: A very large number of connected devices with disparate quality of service requirements. The objective of this category is to provide a response to the exponential increase in the density of connected objects;
2. **eMBB – Enhanced Mobile Broadband**: ultra high-speed connection indoors and outdoors, with uniform quality of service, even on the edges of a cell;
3. **uRLLC – Ultra-reliable and Low Latency Communications**: this use case has stringent requirements for capabilities such as latency and packet-loss, to ensure increased reactivity.


Enhanced Mobile Broadband
Capacity Enhancement
Gigabytes in a second
3D Video – 4K screens
3D
Work & play in the cloud
Augmented reality
Smart city cameras
Voice
Industrial & vehicular automation
Mission critical broadband
Sensor NW
Sensor
Self Driving Car
Massive IoT
Massive Connectivity
Low Latency
Ultra-high reliability & Low Latency

(Source: ETRI graphic, from ITU-R IMT 2020 requirements)

Figure 5. 5G use cases[10]

The first group (mMTC) primarily encompasses all Internet of Things related uses. These services require broad coverage, lower energy consumption and relatively slow transmission speeds. What 5G will deliver compared to existing technologies is the ability to connect objects that are spread out in a very dense fashion across a given area.

Enhanced mobile broadband (eMBB) concerns all of the applications and services that require increasingly fast connections, for instance to watch ultra high-definition (8K) videos or to stream virtual or augmented reality applications wirelessly.

---

[10] http://5g.ieee.org/standards

Ultra-reliable and Low Latency Communications (uRLLC) include all of the applications that require an extreme reactivity and very strong message transmission guarantees. The sectors where these requirements are particularly prevalent are transportation (reaction time when an accident occurs, for instance) and medicine (telesurgery), and when digitising manufacturing processes in general.

To implement these three use case, ITU established eight key performance indicators[11] (KPI) to specify, quantify and measure the characteristics of IMT-2020 (5G) systems:

- Peak data rate (Gbit/s);
- User experienced data rate (Mbit/s);
- Spectrum efficiency (bit/Hz);
- Device mobility (km/h);
- Latency (ms);
- Connection density (number of connected/accessible objects per km²);
- Network's energy efficiency;
- Area traffic capacity (Mbit/s/m²).

---

[11] Added to these eight classes, five new indicators were defined and are currently being examined: reliability, mobility interruption time, bandwidth, maximum spectrum efficiency, 5th percentile spectrum efficiency.

1.3 Jump in performance compared to 4G networks

As mentioned in Paragraph 1.1, the deployment of 5G is likely to take place in two stages:

1. The first 5G rollouts will deliver better performances, but as a continuation of what is being provided at the time by 4G systems which will continue to evolve as well (4.5G, 4.9G);
2. Performances will continue to improve with the gradual introduction of disruptive technologies, such as the use of millimetre wave frequencies.

This gradual rollout is very similar to the way in which 4G was introduced, as the performances obtained with pioneer deployments were relatively similar to those supplied by existing 3G networks.

ITU defines the 4th generation of technologies, called IMT-Advanced, by the values for the eight KPI listed above, as indicated in the following chart. The 5th generation, called IMT-2020, is represented as well. Here, it should be noted that the official ITU definition of 4G in fact corresponds to what commercial rollouts supplied later on, under the name 4G+ or LTE-Advanced.



Figure 6. Comparison between 4G and 5G with respect to the eight key performance indicators[12]

According to these objectives, 5G must be able to provide a user experienced data rate and a peak data rate that is respectively 10 and 20 times higher than what is currently available. The maximum connection density will be multiplied by 10 and latency divided by at least 10 (the target point-to-point latency is 1 ms, compared to 30 to 40 ms today).

---

[12] Recommendation ITU-R M.2083-0 (09/2015), https://www.itu.int/dms_pubrec/itu-r/rec/m/R-REC-M.2083-0-201509-I!!PDF-E.pdf



Figure 7. Representation of the "average user experience data rate" KPI for 4G and 5G and "Peak data rate" KPI for 3G, 4G and 5G[13]

As the successor to 4G, the objective for 5G will also be to provide:

- An extremely reliable network, with more consistent performances regardless of the user's position with respect to the base station;
- A stable connection, even when travelling (at speeds of up to 500 km/h);
- Greater network energy efficiency (with batteries that consume up to 100 times less power).

The following table summarises the target performances for 5G and those currently available with 4G:

Performances/Generation	4G	5G
1. Peak data rate (Gbit/s)	1	20
2. User experience data rate (Mbit/s)	10	100
3. Spectrum efficiency	1x	3x
4. Speed (km/h)	350	500
5. Latency (ms)	10	1
6. Connection density (number of objects/km²)	10^5	10^6
7. Network energy efficiency	1x	100x
8. Area traffic capacity (Mbit/s/m²)	0.1	10

Table 1. Comparisons between 4G and 5G performances

---

[13] http://www.samsung.com/global/business-images/insights/2015/Samsung-5G-Vision-0.pdf

1.4 Network slicing and software-defined networks

It is vital to understand that the set of indicators listed in Section 1.3 determine a set of peak performances for 5G. It will not, however, be possible to achieve all these peak values simultaneously: not every requirement or use case is compatible, so a trade-off will need to be made when defining categories of use that each have their own performance envelope, notably for the use cases described in Section 1.2 (mMTC, eMBB and uRLLC). This is the principle of network slicing: each slice has its own set of KPI, which is a trade-off tied to the target use. On a 5G system, the network properties will need to adapt to the chosen environment.

The following diagram positions the three main use cases listed in Section 1.2. with respect to the eight key performance indicators listed above.


Peak Data Rate
20 Gbps
100 Mbps
User Experienced Data Rate
Enhanced Mobile Broadband
Area Traffic Capacity
10 Mbps/m²
3 Times
Spectrum Efficiency
8 KPIs
Network Energy Efficiency
100 Times
Massive IoT
Ultra-reliable & Low latency
500 km/h
Mobility
Connection Density
10⁶ per km²
1 msec
Latency

Figure 8. Key performance indicators for the three 5G use cases[14]

So for applications that require enhanced mobile broadband (eMBB), such as 4K, 8K or 3D video or virtual reality, a certain number of performance indicators, such as spectrum efficiency, peak data rate and area traffic capacity, can be reached only at the expense of others, such as latency or connection density.

On the flipside, when a massive simultaneous connection of connected objects (mMTC) needs to be managed, the network will concentrate its resources and use the technologies required to achieve this task, but will not be able, for instance, to use spectrum as efficiently or to guarantee low latency.

Lastly, when ultra-reliable and low latency communications (uRLLC) are required, the number of simultaneous connections, data rates and spectrum efficiency may be reduced.

This flexibility, or ability to adapt, that network slicing brings can only be achieved thanks to the softwarisation and virtualisation of a sizeable number of network components (cf. 1.5.2) – a process referred to as Software-Defined Networking (SDN) and Network Function Virtualisation (NFV). Behind these acronyms is a common idea, namely to use as many generic and reconfigurable components as possible, rather than bespoke ones that are permanently dedicated to very specific tasks. This evolution towards software-based systems has been in the works for several years, but is now becoming possible thanks to improved performances from all of these reconfigurable components, including those that are the closest to the elementary tasks of wireless communications (detection, baseband coding, bitstream management, frequency handover, signal processing, etc.).

---

[14] https://5g-ppp.eu/wp-content/uploads/2016/11/06_10-Nov_Session-3_Lee-JunHwan.pdf

1.5 Technological building blocks to achieve the objectives

1.5.1 Air interface

Several, sometimes competing radio access technologies are currently being examined. Some have already been pre-implemented by equipment manufactures and can be used in trials, notably massive MIMO and NFV. Others, such as NOMA modulation and mobile edge computing (MEC), will no doubt take longer before they are ready to be used. In any event, a consensus – which could be painful for certain suppliers whose investments will be lost – will need to be found when defining 5G standards, to ensure the systems' interoperability.

The technologies currently being examined are the following:

- **Millimetre wave frequencies**: the use of millimetre wave frequencies constitutes one of the disruptive 5G technologies. The term refers to the frequencies above 6 GHz which have never been considered for mobile fronthaul network rollouts, for reasons of technological maturity and propagation quality. To meet the demand for ever increasing data rates and traffic volumes, new bands with very wide channels (over 100 MHz per user) will need to be employed: millimetre wave frequencies could provide this spectrum resource, and in certain cases their use would make it possible to achieve the data rates listed in Table 1. Comparisons between 4G and 5G). In exchange, to be able to use these frequencies all of the required, miniaturised low-cost technologies will need to be developed, and ensure a level of energy consumption that is compatible with portable devices (amplifiers, coders, signal processing, antennae, etc.). In particular, because of millimetre waves' poor propagation quality, each cell will have limited coverage and so require the use of beamforming (described below) to better focus the power transmitted by the antenna.
- **Massive MIMO** (Multiple Inputs – Multiple Outputs): this technology involves the use of a large number of smart micro-antennae, located on the same panel (between eight and 128 today, but the number will increase with the use of frequencies above 6 GHz). The appeal of using massive MIMO is twofold: first, the technology makes it possible to increase data rates, thanks to spatiotemporal multiplexing; second, it makes it possible to focus energy on a device to improve its link budget, thanks to beamforming.


Relay station (Wi-Fi AP)
Very high order spatial multiplexing
Massive antennas
Entrance base station
Wi-Fi
Wi-Fi
Wi-Fi
Wi-Fi
Wi-Fi
Wi-Fi
Wi-Fi
Wi-Fi

Figure 9. Example of the use of a beamforming antenna to connect Wi-Fi access points[15]

- **Full Duplex**: in classic systems, transmission and reception takes place either on different frequency bands, i.e. frequency division duplexing (FDD) used on all mobile network bands in France, or at different times: time division duplexing (TDD), the top contender for LTE wireless local loop networks in France. The full duplex is intended to enable the simultaneous transmission and reception of data, on the same frequencies, at the same time and in the same location.[16]


TIME-DIVISION DUPLEX
FREQUENCY-DIVISION DUPLEX
FULL DUPLEX
Tx
Rx
Tx
Rx
Tx
Rx
Tx Rx
TIME SLOT
FREQUENCY BAND

Figure 10. Illustration of full-duplex, compared to FDD and TDD[17]

- **NOMA Multiplexing** (Non Orthogonal Multiple Access): LTE uses what is referred to as orthogonal multiplexing, with each device using a portion of the resource blocks in a unique fashion at any given time. For 5G to provide improved spectrum efficiency compared to 4G, the plan is to use non-orthogonal multiplexing methods, whereby several users can use the same frequencies at the same time. A distinction can be made between several users by assigning different codes to each user – referred to as SCMA or sparse code multiple access – a combination of 3G’s code division multiple access (CDMA) and 4G’s orthogonal frequency division multiple access (OFDMA) or by playing on the difference in users' signal to noise ratios (power domain NOMA[18], illustrated below). These are the two methods chosen for NR.

---

[15] https://www.slideshare.net/100001290086432/massive-mimo

[16] The basic operating principle is the following: an antenna sends a signal at the same time as it is receiving signals coming from devices in the cell. However, the signal received by the antenna is a combination of the signal sent by itself and signals coming from the devices (everyone is “talking” at once). As it knows which signal it itself has sent, the antenna can subtract it during digital processing from the ones it received. So only the signals received from the devices remain.

[17] http://compeng.columbia.edu/biggest-component-full-duplex-wi-fi-radio-antenna



Figure 11. Illustration de multiplexing *power domain* NOMA[19]

- **QAM256**: as with many modern communication systems, 4G uses quadrature amplitude modulation (QAM). In 4G this modulation can achieve QAM64, which means that six bits of information are being transmitted ($2^6 = 64$) at any given time. On wireless systems, the main limitation on QAM order is the signal to noise ratio: when a large amount of information is sent all at once, its transmission will be very sensitive to disruptions (a bit like trying to talk in a noisy environment: it is easy to understand "yes" or "no" but harder to understand more complex sentences). Thanks to an improved link budget, via antenna or signal processing technologies, 5G modulation could reach QAM256, i.e. eight bits of information being transmitted at any given time, which translates into a 33% increase in maximum capacity under ideal conditions. This improved modulation will also be deployed on advanced 4G systems.
- **IoT waveforms**: new waveforms are being explored for the future deployment of 5G IoT in mobile bands. But although mass market IoT is one of the main challenges put forth for 5G, no concrete results have yet been made public. Operators[20] are starting to deploy new standards (EC-GSM or Extended Coverage GSM, LTE-(e)MTC or enhancements for Machine-Type Communications, NB-IoT or NarrowBand IoT) which were defined by 3GPP in Release 13 but, as they are based on 2G and 4G, they do not deliver the performance levels, notably in terms of autonomy, coverage and density, that are compatible with the targets set for future 5G networks.

1.5.2 Network architecture

As with air interfaces, new network architectures are also being explored:

- **Software-defined networking (SDN) and network functions virtualisation (NFV)**: these two functionalities extend beyond the scope of 5G networks per se. They are part of an overall process of network upgrades taking place today and already available with 4G technology (4.9G). The nevertheless remain a key enabler of 5G:

---

[18] The basic operating principle is the following: either User 1 (U1) with a good signal to noise ratio and User 2 (U2) with a less good signal to noise ratio. The antenna sends a high power Signal 2 to U2, and superimposes a weaker Signal 1 aimed at U1. U2 will only see S2 as S1 is drowned out by the noise. U1 will decrypt S2 then delete it from the signal received, to create a higher quality S1, thanks to a better signal to noise ratio.

[19] https://www.anritsu.com/en-AU/test-measurement/technologies/5g-everything-connected/5g-everything-connected-detail

[20] http://www.vodafone.com/content/index/what/technology-blog/nbiot-commercial-launch-spain.html

  - SDN (Software-Defined Network) is designed to disassociate the network's control plane from its data plane, these two planes traditionally being linked and distributed in a set fashion in the network (see diagram below). Controlling the network, a task previously assigned to specialised and unscalable hardware components, is centralised in the form of software on more powerful servers and, in theory, free of equipment manufacturer specifications. This enables the deployment of high value-added services (load balancing, smart routing, dynamic configuration, etc.) in disparate environments.


Traditional Network Architecture
Distributed Control Plane
Apps
SDN Architecture
Centralized Control Plane
Apps
OpenFlow
Control Plane
Data Plane

Figure 12. Centralisation of the control plane in a software-defined network[21]

  - NFV, which builds upon SDN, is used to virtualise, in other words to replace hardware designed specially to perform certain key network functions (firewall, network core, interfaces between different systems…) with software on a server, to accelerate rollouts and enable rapid changes and upgrades.

- **CloudRAN**: this functionality, also know as centralized-RAN, requires a very different network architecture to what we find today. It is an evolution of SDN: the base stations' signal processing units, currently installed at the base station level, are moved to the cloud and centralised. They communicate with the network radio heads, located closer to the antenna, over an optical fibre network (Radio over fibre technology). This centralisation makes it possible to obtain a complete overview of all of the stations deployed and to coordinate signal processing and manage interference between cells and devices

---

[21] http://www-igm.univ-mlv.fr/~dr/XPOSE2014/software-defined_networking/sdn.html



Figure 13. Illustration of CloudRAN[22] network architecture

- **Optimised content delivery, using a mobile content delivery network (mobile CDN)**: corresponds to a set of servers working together in a transparent fashion to optimise the delivery of content to end users over wireless (mobile or Wi-Fi) networks, with high availability and performance. With 5G, the objective for these CDN is to cache content close to users, notably thanks to predictive algorithms, to offload traffic from the networks and decrease latency.
- **MEC (mobile edge computing)**: MEC is an evolution of mobile CDN whose purpose, in addition to bringing data closer to devices, is to provide devices with an accessible computing power with very low latency, within a very specific area for demanding applications. This technology makes it possible to locate a portion of the network's intelligence (managing local critical applications and performance analysis) at the base station level. The "antennae" will be capable of analysing a certain number of data, and so to make decisions very quickly.
- **Device-to-device**: D2D is a direct form of communication between two nearby devices, which does not require the data to travel over the cellular network. Device-to-device communication is not new, as technologies such as Bluetooth and Wi-Fi direct already enable it. But a new mesh networking technology will be introduced with 4.9G and later 5G network rollouts: LTE-direct. Far more energy-efficient than its predecessors, this technology will have a range of up to 500 metres and geolocation capabilities to enable communications. This technology will be very useful for low latency V2V (vehicle-to-vehicle) or V2X (vehicle-to-everything) communications and for certain public-security related uses.

1.5.3 5G: a multi-technology generation cohabitating with existing networks

As stated earlier, 5G is not meant to replace 4G overnight. In practice, the devices will undoubtedly be multi-modal: still connected to the 4G network, which will provide extended coverage for pioneer rollouts, then transitioning to 5G networks when they become available.

While 4G and 5G frequencies will probably be initially segregated, in all likelihood devices will rapidly become capable of aggregating 4G and 5G carriers and, further down the road, 4G carriers will be encapsulated in 5G ones.

---

[22] https://5g-ppp.eu/wp-content/uploads/2016/11/04_10-Nov_Session-3_Takaharu-Nakamura.pdf

4G is still being deployed, and its technological evolution and certain building blocks will be used by both the first 5G networks and advanced 4G networks. To wit, the latest trials conducted in France are allowing 4G networks to perform better thanks to the use of pre-5G technologies:

- Bouygues Telecom, in partnership with Huawei, managed to achieve a peak data rate of 1 Gbps thanks to the simultaneous use of four-carrier aggregation (800 MHz, 1800 MHz, 2100 MHz, 2600 MHz) and more powerful modulation (256 QAM)[23];
- In the coming weeks, Orange will be launching a massive MIMO (16x16) trial with Nokia[24].

In addition to the strong integration between 4G and 5G, the new generation will no doubt also continue convergence efforts between frequency bands governed by exclusive licences – i.e. bands that are allocated exclusively to an operator, such as mobile operators – and unlicensed frequency bands, governed by a system of general authorisation (e.g. Wi-Fi bands), which already began in 4G with LTE-LAA (Long Term Evolution – License Assisted Access) and LTE-LWA (Long Term Evolution – Wi-Fi Link Aggregation).

LTE-LAA is characterised by the aggregation of one or several LTE carriers, used in licensed bands, with other LTE carriers employing unlicensed 5 GHz Wi-Fi bands. To guarantee cohabitation with very widespread Wi-Fi networks whose deployment pattern is unpredictable, it uses LBT (Listen Before Talk) technology to listen to the radio channel before transmitting, in order to determine whether or not a frequency is available.

LTE-LWA consists of an aggregation of LTE carriers in licensed bands with Wi-Fi traffic. To achieve this, the LTE cell and Wi-Fi access point need to be connected: the Wi-Fi traffic is sent to the cell which sends back the entire aggregated link on the 4G core network. This technology is particularly well suited to indoor environments with small cells, a system which, as detailed in paragraph 3.3 below, will lend itself well to 5G deployments.

---

[23] https://www.corporate.bouyguestelecom.fr/wp-content/uploads/2016/05/Communiqu%C3%A9-Bouygues-Telecom-et-Huawei-Technologies-r%C3%A9alisent-un-test-de-d%C3%A9bit-4G-%C3%A0-plus-de-1-Gbps-pour-la-premi%C3%A8re-fois-en-Europe-de-lOuest.pdf

[24] https://networks.orange.fr/actualites/actualites-des-networks/orange-et-nokia-partners-pour-developper-les-futurs-services-5g

2 5G development initiatives

With a view to keeping the many promises being made for 5G, a number of initiatives are currently underway around the globe to promote its development. Below, we detail the foremost initiatives put forth by the players with which Arcep met as part of its investigation.

2.1 Government initiatives

The prospect of significant socio-economic repercussions generated by 5G (possible revenue of close to $225 billion a year[25] by 2025) combined with many countries' desire to establish themselves as technological leaders and make their companies more competitive, have propelled a multitude of government initiatives around the globe, aimed at encouraging the mobile ecosystem to begin the work and make the investments required to drive the rapid construction of the first 5G networks.

A selection of the largest initiative is detailed below.

2.1.1 In Europe

5G-PPP

The 5G Public Private Partnership (5G-PPP) is dedicated to 5G research and development, created on the initiative of the European Commission in 2013, with a budget de €700 million in public funding. The main objectives set by 5G-PPP are:

- Create stronger ties between the economic players and academic bodies devoted to the telecommunications sector over R&D projects, along the entire value chain;
- Reduce technological dependence on the United States and Asia while sustaining a strong global market;
- Regain technological leadership, notably in disruptive technologies, by promoting standards in international bodies;
- Allow innovative business models to emerge;
- Facilitate large-scale experimentation.

The results of this work will help clarify the 5G action plan (see below), and fuel the standardisation work that is currently underway.

To achieve its ambitions, 5G-PPP has initiated three stages of work, financed by the European Union, whose roadmap is in sync with the main international initiatives (3GPP and ITU, cf. Figure 14):

- The first stage which is currently underway, will last until mid-2017;
- A second stage focused on systems optimisations, from the end of 2017 to mid-2019;
- And finally a full-size trial stage from 2019 to 2020.

Deploying 5G by 2020 will require Europe to develop leading edge technologies, globally approved standards and especially to achieve consensus over the most suitable frequency bands. This funding and these projects – involving a great many researchers from more than a hundred companies and the finest R&D centres in Europe – are thus vital.

---

[25] https://www.abiresearch.com/press/abi-research-projects-5g-worldwide-service-revenue



Figure 14. 5G PPP vs. 3GPP and ITU roadmaps[26]

5G action plan

As a complementary measure, on 14 September 2016 the European Commission launched its *5G for Europe Action Plan* to bolster investments in 5G infrastructure and service rollout efforts in the Digital Single Market between now and 2020. This action plan sets out a clear roadmap for public and private 5G investments inside the EU.

The Commission has proposed the following measures to achieve this plan:

- Align roadmaps and priorities for a coordinated 5G deployment across all EU Member states, targeting early network introduction by 2018, and moving towards commercial large scale introduction by the end of 2020 at the latest.
- Make provisional spectrum bands available for 5G ahead of the 2019 World Radio Communication Conference (WRC-19), to be complemented by additional bands as quickly as possible, and work towards a recommended approach for the authorisation of the specific 5G spectrum bands above 6GHz.
- Promote early deployment in major urban areas and along major transport paths.
- Promote pan-European multi-stakeholder trials as catalysts to turn technological innovation into full business solutions.
- Facilitate the implementation of an industry-led venture fund in support of 5G-based innovation.
- Unite leading actors in working towards the promotion of global standards.

---

[26] 5G Empowering vertical industries. White Paper, 2016, https://5g-ppp.eu/wp-content/uploads/2016/02/BROCHURE_5PPP_BAT2_PL.pdf

The European Commission has given every EU country a certain number of ambitious, numerical targets. One core objective for 5G is thus to have at least one major city in every European country outfitted with this new generation mobile system by 2020, and coverage of every city, motorway and high-speed railway lines by 2025. This comes in response to announcements from South Korea and Japan which are both promising large-scale 5G demonstrations, respectively, at the Winter Olympics in Pyeongchang in 2018 and the Summer Olympics in Tokyo in 2020.

2.1.2 Worldwide (examples in the US, South Korea, Japan and China)

The race is already underway between countries to be the first to begin large-scale 5G trials, and later to introduce commercially available services, so much so that they are willing to employ pre-standard technical specifications.

Several countries are therefore working on standards and seeking to reach a consensus with one another to achieve international backing for the technical specifications that will satisfy their needs, and earn them the best possible return on the investments made thus far. This in turn is creating a certain turmoil, for instance, over the frequency bands that would be the best candidates for 5G.

The United States[27]

5G is seen as an unprecedented opportunity for economic growth, with a tremendous impact on education, job, transportation, etc. According to the US federal regulator, the FCC (Federal Communications Commission), the following three elements in particular need to be the prime focus of attention: spectrum, infrastructure and the backhaul network:

- **Spectrum**: in July 2016, the FCC voted to free up and to open up nearly 11 GHz of high frequency spectrum to be used for fixed and mobile broadband applications: 3.85 GHz of licensed spectrum in the 27.5 – 28.35 GHz and 37 - 40 GHz bands, as well 7 GHz of unlicensed spectrum from the 64 - 71 GHz band. The FCC's stated goal was to provide the assurance and clarity for investments in the telecoms sector. Verizon welcomed this decision, and plans on achieving the first rollouts in 2017, with trials already underway in several cities around the country (cf. 3.3).
- **Infrastructures**: The FCC believes that 5G must be underpinned by a robust infrastructure network capable of handling already heavy traffic that could potentially increase exponentially in the coming years. It will interact in a hybrid fashion between traditional towers with macro cells and small cell deployments, as well as distributed antenna systems. With an eye on the deployment of new towers, the FCC resolved to reduce, or eliminate in certain cases, the regulatory restrictions on installing facilities and antennae that will have very little impact "on historic properties" (tower re-use, small antennae, indoor installations, etc.)[28].
- **Backhaul network**: Because 5G systems will require very high-power backhaul networks, the FCC is in the process of reforming and updating the regulations governing data services markets, including wireless backhaul solutions. The FCC is seeking to protect this market while also creating competition, so that competitive and high quality backhaul network solutions can emerge.

---

[27] Forging Our 5G Future – Federal Communications Commission: https://www.fcc.gov/5G

[28] https://apps.fcc.gov/edocs_public/attachmatch/DA-16-900A1_Rcd.pdf

Japan

Japan wants to demonstrate its 5G leadership by deploying the first commercial 5G network that complies with international technical specifications, in time for the Summer Olympic Games in Tokyo in 2020.

According to the *Radio Policies Towards 2020*[29] report, published in June 2016 by Japan's Ministry of Internal affairs and Communications (MIC), the 3600 - 4200 MHz, 4400 - 4900 MHz and 27.5 – 29.5 GHz bands were selected to be the 5G candidate bands on a national scale. Although other bands are also being investigated, with a view to WRC19, 5G rollouts are already planned in the 3600 - 4100 MHz, 4405 - 4895 MHz and 27.5 - 28.28 GHz bands as early as 2017 in Tokyo, and will be built out in 2018 and 2019.

China

Like Japan, China too wants to prove its leadership with the first commercial rollouts in 2020. The first trials will be conducted that year in the 3400 – 3600 MHz band. The 3300 - 3400 MHz, 4400 - 4500 MHz and 4800 - 4990 MHz bands are also under consideration and currently being investigated. For higher speeds, the country plans on using spectrum around the 25 GHz and 40 GHz frequencies.

South Korea

South Korea, meanwhile, has set its sights on a pre-commercial 5G service that would be ready in time for the 2018 Winter Olympics in Pyeongchang. Several trials are already underway to prepare for full scale demonstrations in several South Korean cities, including Pyeongchang and Seoul. The country's three national mobile operators are hoping for spectrum in the 26.5 – 29.5 GHz bands.

South Korea's largest mobile operator, SK Telecom, has announced a plan for conducting interoperability tests with Qualcomm and Ericsson, as well as outdoor trials of the new air interface based on the 3GPP NR standards that are being developed today. These trials and experiments will be carried out in the second half of 2017.

If the goal of these trials is to help accelerate the specification of the new NR air interface, which is part of the work being done on 3GPP Release 15, it has not yet been specified which frequency bands will be used for these trials.

2.2 A host of private initiatives – a few examples

5G Open Trial Specification Alliance

In early 2016, South Korean operators KT and SK Telecom, Japanese carrier NTT DoCoMo and American carrier Verizon formed the 5G Open Trial Specification Alliance to carry out collaborative 5G trials.

Due to be conducted between 2016 and 2018, the aim for these trials is to provide a common platform for operators, for exchanging results and shared assessments of the different 5G network components and elements. One of the operators' objectives is to help accelerate the definition of standards and specs, and to enable economies of scale. The findings of these evaluations will provide input for 3GPP discussions, adding simulations to the experimental data produced by the partnership.

---

[29] http://www.gsma.com/spectrum/wp-content/uploads/2016/08/MIC_Spectrum-for-5G-MIC-Kuniko-OGAWA.pdf

The alliance’s founders hope to attract a number of industrial partners to the platform, including other carriers, equipment suppliers, chipset makers, etc. Several of the founding operators’ equipment suppliers are already involved in the scheduled trials.

The trials will cover multiple frequency bands, both above and below 6 GHz.

Verizon 5G Technical Forum

The Verizon 5G Technology Forum (V5GTF) was created in late 2015 by Verizon, in cooperation with its partners Cisco, Ericsson, Intel, LG, Nokia and Qualcomm. The goal of the collaboration is to provide a platform for testing radio interface specifications in the 28 and 39 GHz bands.

The first fruit of this collaboration, in July 2016 Verizon announced the completion of the first specifications of their 5G radio interface. These specs should enable the different parties involved to develop interoperable solutions and so to help drive forward the definition pre-standards.

Even though they run the risk of developing solutions that are not compatible with 3GPP or ITU standards, Verizon believes it has a solid enough grasp of the overall concepts being discussed in those bodies. The tests carried out in several US cities were thus able to validate substantially greater capacities than 4G.

Orange/Ericsson

Orange and Ericsson have been working together since October 2016 on developing 5G use cases and services, as well as demonstrations. The purpose is to develop technological building blocks, conduct trials and pilot projects for a range of use cases, including multi gigabits/s wireless internet access in suburban and rural environments, the Internet of Things and connected cars.

Their collaboration made it possible to achieve 15 Gb/s in a laboratory environment, notably thanks to the use of massive MIMO and beamtracking using centimetre waves. The collaboration will also focus on the transition from 4G to 5G solutions, notably in terms of reducing costs and improving energy efficiency, and on the use of SDN and NFV technologies.

Since January 2017, the partnership has included PSA (Peugeot) to carry out trials on connected cars.

5G-ConnectedMobility

5G-ConnectedMobility is a consortium formed by Ericsson, BMW, Deutsche Bahn, Germany’s three mobile operators, Deutsche Telekom, Telefonica Deutschland and Vodafone, the 5G TU Dresden laboratory, the BAST research institute and BnetzA, with the goal of galvanising and accelerating 5G R&D in Germany.

5G-ConnectedMobility thus plans on supplying a digital motorway infrastructure and real application environment to be able to test V2V (vehicle-to-vehicle) technologies as well as solutions for digitising railway infrastructure.

To this end, 5G-ConnectedMobility operates with the help of an independent network infrastructure that is not connected to any commercial network. The Ericsson mobile network devoted to this project makes it possible to run live tests: Ericsson thus obtained permission from regulator BNetzA to employ spectrum in the 700 MHz band in the Nuremberg area.

3 The challenges of 5G

In this part we explore the different challenges that lie ahead for 5G, which emerged from the interviews that Arcep conducted over the past several months.

3.1 New business models focused on vertical markets

3G and especially 4G technologies were designed primarily for the superfast mobile internet. 5G continues on in this direction, but also wants to target what are known as vertical markets, which encompass several segments, including:

- Connected vehicles, not only to deliver entertainment and information to passengers, but also to guarantee safety via communications both between vehicles and between vehicles and infrastructure;
- Factories of the future;
- Smart cities with requirements in the areas of public transportation (similar to the needs of connected vehicles), the environment, managing buildings and energy consumption;
- Medicine, healthcare and robot-assisted telesurgery;
- Smart grid flow monitoring and management (electricity, gas, water, etc.).

This section will focus in particular on the connected car and factories of the future segments. Because of their current and future macro-economic context, along with the plurality and effervescence of the pioneer work being done in these areas, these two segments constitute the main avenues of 5G development in vertical markets. Smart cities and smart grids have already begun to soar through existing Internet of Things (IoT) technologies.

3.1.1 The automotive sector

The car is an extremely common form of transportation, and safe driving is a fundamental consideration: human error is the number one cause of all transport accidents. The transportation sector wants to use technological innovations to tackle this problem, and to continue to make transportation more efficient, more sustainable and safer.

There are three areas in which technological progress could help improve automotive transportation. 5G could have a role to play in all three, but particularly in the first two:

- Provide in car internet connectivity, to deliver entertainment to passengers;
- Provide access to driver assistance information, to reduce accidents and improve the fluidity of traffic;
- And, finally, the ability to make cars autonomous, thanks to artificial intelligence algorithms.

The first area is just an extension of the developments occurring today around 4G. The aim is to give passengers access to their messaging services, to the internet, to multimedia content, online gaming, etc. The increased connection speeds promised by 5G will improve the use of all of these services.

The second area aims to make cars more intelligent by using information that was not previously available to them. This in turn will help improve the safety and efficiency of the networks as well as help drivers make the right decisions, and adapt to driving conditions. Such connected vehicles could have access to information about dangers on the road (slow or stopped cars, traffic jam warnings, indications of where construction is taking place on the roads, weather conditions, emergency braking, emergency service vehicles approaching, etc.) or regarding signage (signalling/signage on-board vehicles, speed limits on vehicles, failure to heed signage/safety precautions at crossings, request for right-of-way at traffic lights for designated vehicles, green light optimal speed advisory, etc.). Other services, such as information on refuelling or recharging stations, vulnerable road user protection, managing street parking and traffic information, and smart guidance, could also prove useful. It is still not clear whether, to achieve this, vehicles will simply exchange information with each other or if connectivity with infrastructure will be required along the roads to optimise vehicles' behaviour. In both instances, 5G could have a role to play.

Of the many initiatives that are already underway we can begin with an example from France: the SCOOP@F[30] (cooperative intelligent transport systems) project coordinated by the Ministry of the Environment, Energy and the Sea, and which unites local authorities and R&D centres. Launched in February 2014, new partners subsequently joined the initiative, including Orange and Austrian, Spanish and Portuguese partners. As it is a European project, it receives 50% of its financing from the European Commission, and cross-tests are conducted with Austria, Spain and Portugal. SCOOP@F is a pilot rollout project for cooperative intelligent transport systems; it aims to deploy 3,000 vehicles on 2,000 km of roadway spread across five locations: Ile-de-France, the A4 motorway, the Isère, and ring roads in Bordeaux and Brittany. Its main objectives are to improve road safety and the safety of roadway workers, achieve more efficient traffic management, reduce pollution, streamline infrastructure management costs and participate in defining the car of the future.

In addition, in early 2017, mobile carrier Orange, equipment supplier Ericsson and car-maker PSA Group signed a partnership agreement[31], as part of the "*Towards 5G*" initiative, to conduct technical trials relating to 5G. The aim of this alliance is to test the different paths of technological evolution from 4G to 5G to meet the needs of connected cars, notably in terms of intelligent transport systems (ITS), for safer driving and new on-board services.

The third area concerns the emergence of autonomous vehicles. A number of projects are underway in this area. The first step is to outfit vehicles with algorithms that enable it to make decisions quickly based on their environment. This requires a large number of sensors to deliver a full "understanding" of what is happening around the vehicle. Without pre-judging the technologies that will ultimately be employed to achieve this, as with a human driver (see above), the car could take advantage of connections with other vehicles on the road and with an infrastructure, to have access to all of the aforementioned information.

3.1.2 Industry 4.0

Competitiveness does not depend solely on innovation and the evolution of products, but also on modernising businesses and their means of production. According to certain studies carried out in 2015[32], the digital transition in Europe will enable enterprises to increase their revenue by more than 110 billion euros a year over a five-year period.

A great many countries have set out a strategy for modernising their manufacturing infrastructure (*l'industrie du futur* in France[33], Industry 4.0 in Germany…) of which one aspect will involve digitising processes and trade. The European Commission itself introduced measures in 2016 for strengthening competitiveness in Europe, in which 5G could play a significant role. This included earmarking 500 million euros for the Horizon-2020[34] research programme.

---

[30] http://www.scoop.developpement-durable.gouv.fr/spip.php?page=sommaire

[31] http://www.orange.com/fr/Press-Room/communiques-2017/Ericsson-Orange-et-le-groupe-PSA-partners-pour-la-voiture-connectee-en-5G

[32] PwC, "Industry 4.0: Opportunities and challenges of the industrial internet" (2015), and Boston Consulting Group, "Industry 4.0: The Future of Productivity and Growth in Manufacturing Industries" (2015)

[33] http://www.economie.gouv.fr/files/files/PDF/industrie-du-futur_dp.pdf

The advent of new technologies (4G, fibre and soon 5G) and new services (the Internet of Things, the cloud, big data) should facilitate businesses' digital transition. 5G in particular is expected to be a very versatile technology, capable of undergirding a very wide array of uses, and could go a long way in furthering companies' transition to digital technologies and solutions.

3.2 Spectrum harmonisation

5G is emerging as a technology that will use both low frequencies (f < 1 GHz), high frequencies (1 GHz < f < 6 GHz) and, for the first time ever in consumer networks, very high frequencies referred to as "millimetre wave" frequencies (f > 6 GHz).

This spectrum diversity is entirely bound up with the promises of 5G: extended coverage (low frequencies), ultra high speeds (very large channels in very high frequency bands), low power consumption. Furthermore, satellite services will also contribute to the development of this new technology, especially in areas that are difficult to cover and to provide backhaul solutions. The satellite industry is thus taking an interest in 5G, and wants to be involved in defining these new generation network.

3.2.1 Millimetre wave frequencies

The "millimetre" band, also referred to as millimetre wave spectrum, aka frequencies above 6 GHz, are essential to enabling 5G to mark a departure from 4G, for the reasons cited in Section 1.5.1.

At the latest World Radiocommunications Conference (WRC-15 in Geneva), a conference under the aegis of ITU whose objective is to change the way frequencies are allocated between users, discussions over the definition of future mobile bands made it possible to focus future 5G studies, for millimetre wave frequencies, on a certain number of bands situated between 24 GHz and 86 GHz (33.25 GHz identified in total): 24.25 - 27.5 GHz, 31.8 - 33.4 GHz, 37 – 43.5 GHz, 45.5 - 50.2 GHz, 50.4 - 52.6 GHz, 66 - 76 GHz, 81 - 86 GHz.

It is important to stress that, even if the above-listed bands have been identified as "5G bands", at this stage there is no way to know whether they can actually be used to deploy this new generation system: only the results of technical studies will make it possible to establish the constraints and rules of compliance, and to validate the feasibility of these hypotheses.



Figure 15. Millimetre wave frequencies identified at WRC-15

Contrary to the conclusions of the Conference, which reflect European recommendations, the United States and certain Asian countries (South Korea, Japan) have decided to perform 5G trials in the 28 GHz band, and equipment suppliers such as Qualcomm and Samsung, have begun manufacturing 28 GHz- band products.

---

[34] https://ec.europa.eu/programmes/horizon2020/en/what-horizon-2020

Meanwhile Europe, following the publication of an RSPG (Radio Spectrum Policy Group within which France is represented by ANFR) opinion[35], decided to focus its first studies on the 26 GHz band (pioneer band), then on the 32 GHz and 42 GHz bands. Later, studies will be carried out on introducing 5G in all of the other bands identified by WRC-15.

The rapid choice of the 26 GHz band as the pioneer band was made to enable economies of scale for equipment production, since it is very likely that dual-mode equipment, i.e. compatible with both the 26 GHz and 28 GHz band, will be available for pioneer rollouts[36].

In France, the 26 GHz band is already being employed for a variety of uses: mobile operators' wireless fixed links (4G infrastructure links), fixed satellite service systems and ground stations for space services. Studies will therefore need to be conducted to take these services into account, and define either the cohabitation or migration of applications to other millimetre wave frequencies.

3.2.2 Frequency bands below 6 GHz

a) The 3.4-3.8 GHz band

It will not be possible for 5G to run entirely on millimetre wave frequencies: the propagation qualities of these bands make it difficult to achieve widespread coverage, particularly in more sparsely populated areas. In addition, these bands are still lacking in technological maturity when it comes to delivering consumer market communication services. As a result, a "core" band below 6 GHz needs to be identified: one that provides sufficiently large channels to enable future 5G operators to provide innovative services and a higher quality of service than with 4G.

The 3400 - 3800 MHz band appears to be a good candidate.

First, it has already been harmonised for ultrafast mobile services inside the European Union. Initially the 3400 - 3600 MHz band and later the 3600 - 3800 MHz band were identified as the "IMT" bands (for high-speed mobile). Second, they have a great deal of available spectrum (up to 400 MHz). Lastly, technological advancements (antenna and signal processing) make these frequencies compatible with their use to establish macro cells, and not only microcells. To give an example, it emerged from the interviews conducted by Arcep that coverage with this band could be similar to coverage with the 2.6 GHz band, the core 4G frequency band.

This analysis has been confirmed by the European Commission (in its 5G mandate to RSCOM[37]) and by RSPG[38] which consider the 3.4 - 3.8 GHz band as the only credible 5G band for deployments taking place before the end of 2020.

In France, the band is assigned to Arcep, in a priority fashion, for the 3400 - 3600 MHz frequencies (and in a non-priority fashion to the Ministry of the Interior and the Ministry of Defence), and exclusively for the 3600 - 3800 MHz frequency bands. It is used for wireless local loop and satellite applications.

The compatibility of future uses with current applications is being examined by the Electromagnetic Compatibility Advisory Committee, which is chaired by the National Frequency Agency and of which

---

[35] http://rspg-spectrum.eu/wp-content/uploads/2013/05/RPSG16-032-Opinion_5G.pdf

[36] The tuning range is vital here: a system capable of regulating its frequency from 26 to 28 GHz appears entirely technologically achievable within the timeframe for the first 5G millimetre wave deployments. This would have been less true if a switch between 28 and 32 GHz were required.

[37] https://circabc.europa.eu/sd/a/448dc765-51de-4fc8-b6e0-56ed6a1d0bca/RSCOM16-40rev3%205G%20draft_mandate_CEPT.pdf

[38] http://rspg-spectrum.eu/wp-content/uploads/2013/05/RPSG16-032-Opinion_5G.pdf

Arcep is a member: exclusion zones, protecting certain locations tied to long-term use of satellite solutions, need to be set up. Military radiolocation systems operating below 3.4 GHz also need to be protected.

b) Other bands below 6 GHz

The bands being used today for 2G, 3G and 4G could be used for future 5G deployments.

Refarming 2G, 3G and 4G could be a delicate undertaking, however, because of the duplexing methods they use. Most mobile communications in Europe use FDD (Frequency Division Duplexing)[39] to exchange information. Technical discussions over 5G are nevertheless anticipating that TDD (Time Division Duplexing)[40] will be the chief, if not sole, form of duplexing used for this new generation, notably because it makes it possible to adjust bandwidth to data rates and because it is particularly efficient when beamforming is used.

For 5G networks, using already harmonised mobile bands will thus require in-depth technical studies to define the terms and conditions of use and sharing with existing services. On this point, the ECC (Electronic Communications Committee[41]) decided to assess the potential of certain already harmonised bands, notably the 700 MHz and the L band (1427-1492 MHz).

In France, Arcep allocated the 700 MHz band to mobile operators in late 2015. Even if the country's four operators all obtained frequencies in this band, only Free Mobile, which has no blocks of 800 MHz spectrum, decided to begin its rollouts in the band using LTE (4G) technology.

Arcep is currently analysing the contributions to its public consultation, addressing among other the 3.5 GHz band, that ended recently.

The L band (1427 - 1518 MHz), which was defined to be used exclusively in SDL (Supplemental DownLink) mode, could be considered to meet the constant demand for ever higher data rates and the greater increase in downlink traffic, compared to uplink traffic. In France the band is used by wireless fixed links authorised by Arcep, by the Ministry of Defence for mobile services (excluding aeronautical) and by the Ministry of the Interior. Using it for 4G or 5G would therefore suppose moving the above-mentioned uses over to other bands.

3.3 Increasingly small cells

Today, mobile network rollouts are essentially based on the use of macro base stations: installations that are equipped with high-power antennae deployed to guarantee coverage for a relatively wide area, providing good quality of service. Network configurations are evolving constantly: new radio base stations are installed on a regular basis to increase the networks' capacity, to better meet users' needs in terms of indoor and outdoor coverage, and to improve quality of service.

However, this continually growing demand for capacity already requires operators to increase the density of their networks with smaller and smaller cells.

5G – which will probably bring about a sizeable increase in data traffic, and which will use millimetre wave frequencies whose propagation capabilities are weak – will no doubt require the widespread deployment of low-power base stations (small cells).

---

[39] A technique that consists of sending and receiving data simultaneously, but on two different frequency bands.

[40] A technique that consists of sending and receiving data on the same frequency band but at different times.

[41] The European body that specifies the technical terms and conditions governing the use of frequency bands, which are then set by European Commission decisions.

To satisfy demand and enable the introduction of 5G, estimates indicate at least 10 small cells per macro base station in urban settings[42], where cells are already today relatively tightly meshed to handle traffic density.

Here, the players that met with Arcep raised several questions that will no doubt need to be answered when considering the ubiquitous deployment of small cells.

3.3.1 Taxation

The current regulatory framework stipulates that base stations whose power requires an opinion, an agreement or a statement from the National Frequency Agency (ANFR) are subject to a flat tax on network companies (IFER[43]). The amount of the tax varies according to transmission power, the type of installation and the deployment location. For a deployment in an urban area, the tax stands at €1,607/year/installation for a base station with an effective isotropic radiated power (EIRP) of more than 5W (a COMSIS agreement from ANFR is required to be able to transmit) and €160.70 €/ year/installation for an EIRP of between 1W and 5W (declaration to ANFR is required to be able to transmit).

5G small cells will likely use variable transmission powers of between 1W and 25W. In light of rollout density forecasts, hence the number of small cells to install, some of the stakeholders that Arcep met with raised the question of possibly adapting this tax in such a way as to enable massive small cell deployments without generating an equally massive increase in the total tax amount.

This process is already underway, notably with a view to decreasing taxes on base stations in locations that are hard to cover: Act No. 2016-1888 of 28 December 2016 on the modernisation, development and protection of mountain regions thus exonerates mobile base stations built in mountain regions between 1 January 2017 and 31 December 2020 from paying the IFER tax.

3.3.2 Access to elevated and “semi-elevated” locations

To perform their deployments successfully, mobile operators have traditionally needed to install their base stations in elevated locations (towers, rooftops, etc.). This will continue to be true with 5G networks, but will be even more challenging for two main reasons:

1. 5G antennae will probably be larger (in the m^2 range for some) than current 2G, 3G or 4G antennae, because of the above-mentioned massive MIMO processing that will require the use of a very large number of radiating elements. Moreover, additional antennae compatible with new 5G bands will no doubt also need to be deployed. So the re-use of existing masts could very well be problematic, and new (possibly collocated) transmission sites will need to be found.
2. This search for new sites will also need to be carried out to install small cells in semi-elevated locations, but with extra care as the density of these installations will undoubtedly be high: operators will thus be required to deploy their equipment on urban furniture and infrastructures such as bus shelters, lampposts, public buildings, billboards, etc.

As a result, public authorities will need to keep a close eye on the matter and, if necessary, adopt measures that will facilitate 5G rollouts.

---

[42] http://www.lemag-numerique.com/wp-content/uploads/2015/10/WP_-Souverainete_Telecoms_PetitesCells_FINAL.pdf

[43] IFER = *Imposition forfaitaire sur les enterprises de réseaux*

3.3.3 5G networks’ regional coverage and backhaul

Ensuring regional connectivity will be one of the challenges for this new generation of mobile networks.

The diversity of use-cases envisioned for future 5G networks, the geographical distribution of which is not yet precisely known, must be factored in when addressing coverage issues.

The higher frequency bands that are being put forth for future 5G networks, along with the potentially very substantial bandwidth consumed by these new uses, pose the question of the regional foothold of these networks. As a matter of fact, mobile networks have never before employed such high frequencies whose use will require a large number of relay antennae to be installed.

Moreover, connecting the 5G installations to the network will push to the fore the question of the cost of connecting them via optical fibre, which will no doubt be necessary in most instances to ensure the expected quality of service. The industry needs to design the technologies that will make it possible to minimise the cost of 5G rollouts in rural areas.

3.4 Net neutrality issues

European regulation on safeguarding an Open Internet[44], adopted by the European Parliament and Council on 25 November 2015, for which European regulators required an additional nine months to specify the rules governing its application, introduces the principle of net neutrality as one of the top priorities in the standardisation hierarchy.

Net neutrality is an overriding principle that guarantees equal treatment for all data traffic on the internet. In particular, it excludes any form of discrimination with respect to the source, the destination or the content of data flows.

On 30 August 2016, BEREC (the Body of European Regulators for Electronic Communications) published guidelines for national regulators on the enforcement of the European Open Internet regulation[45].

During the BEREC public consultation[46] on its draft net neutrality guidelines, several enterprises and electronic communications sector stakeholders took the opportunity to deliver a clear-cut point of view in their *“5G manifesto for timely deployment of 5G in Europe”*[47]. This manifesto aims at warning public authorities against a too restrictive approach to traffic management, and especially of the supposedly negative effects that, in their opinion, an overly strong enforcement of net neutrality could have on the 5G rollout roadmap.

---

[44] Regulation (EU) 2015/2120: http://eur-lex.europa.eu/legal-content/FR/TXT/PDF/?uri=CELEX:32015R2120&from=EN

[45] Internet service providers (ISP) can employ reasonable traffic management measures for certain categories of traffic, under non-discriminatory conditions and provided they are transparent, proportionate and justified by objective technical requirements, and not used to serve their own commercial interests. ISPs can also distinguish certain services, called specialised services, from their internet access service, without them affecting the latter, provided these services have specific, objective transit requirements.

[46] http://www.berec.europa.eu/

[47] http://telecoms.com/wp-content/blogs.dir/1/files/2016/07/5GManifestofortimelydeploymentof5GinEurope.pdf

BEREC's opinion[48], in response to the contributions to the aforementioned public consultation, recalls that the rules of net neutrality are technology neutral and therefore apply to 5G networks. Moreover, BEREC guidelines clarify that network slicing which networks will need to use to respond to the different use cases (mMTC, eMBB, uRLLC) planned for this new generation (cf. 1.4) system, may be used to deliver specialised services[49].

The subject of net neutrality as it applies to future 5G networks is still very much open and unexplored, but new analyses could be performed parallel to the work being done on defining 5G. Arcep is open to discussion and will also work, within BEREC, towards bringing the required clarity to the ecosystem.

---

[48] http://berec.europa.eu/eng/document_register/subject_matter/berec/download/0/6161-berec-report-on-the-outcome-of-the-publi_0.pdf

[49] http://berec.europa.eu/eng/document_register/subject_matter/berec/download/0/6160-berec-guidelines-on-the-implementation-b_0.pdf - footnote 26

Annexes

Annex 1 Definition and standardisation work

A new generation of mobile telephony is defined primarily by two bodies: ITU (International Telecommunication Union) and 3GPP (3rd Generation Partnership Project). These two, respectively public and private, organisations are dedicated to defining the objectives, standards and technical specifications of the new technology in question.

ITU

The first large-scale 5G commercial rollouts are expected to take place in 2020. As mentioned earlier, the exploratory phase – which provides an opportunity to determine demands and identify the most promising techniques and technologies for these future 5G networks – has already begun. Although a number of organisations and consortia are involved in defining 5G, 3GPP will very probably be the central standardisation body for its technical specifications.

Whatever the case may be, ITU (International Telecommunication Union) is vital to defining the technologies and standards that govern any new generation of IMT (International Mobile Telecommunications) at the global level.

These IMT standards are established with the involvement of public authorities and industry players, and have provided the framework for the evolution of mobile communication services around the world, since the beginning of IMT standardisation, with IMT-2000 (3G, UMTS), then IMT-Advanced (4G, LTE-A) and more recently IMT-2020 (5G).


Vision
Development of IMT-2020
Deployment (*) of IMT-2020
9 years
Vision
Development of IMT-Advanced
Deployment (*) of IMT-Advanced
15 years
Development of IMT-2000
Deployment (*) of IMT-2000
1985 SQ Adopted FPLMTS
2000 IMT-2000 Rec. ITU-R
2003 Vision Rec. ITU-R
2012 IMT-Advanced Rec. ITU-R
2015 IMT-2020 Vision
2020 IMT-2020

Figure 16. Timeline of IMT developments and deployments[52]

The advent of an IMT standard typically occurs in three main stages : a vision stage, a development stage and a deployment stage.

The vision stage – whose completion is marked by a document that is usually called a Vision Recommendation – is the stage during which ITU sets the framework and objectives for the future technology. The aim of this document is generally to define what the new technology will be in a more or less concrete fashion, what its characteristics will be, the uses it will enable, etc. Whether for

---

[52] Recommendation ITU-R M.2083-0 (09/2015), https://www.itu.int/dms_pubrec/itu-r/rec/m/R-REC-M.2083-0-201509-I!!PDF-E.pdf

IMT-Advanced, the commonly used technical abbreviation attributed to the definition of 4G, or IMT-2020, the abbreviation attributed to definition of 5G, the vision stage lasts around three years.

Recommendation ITU-R M.2083-0 was published in September 2015, bringing to a close three years of work performed by ITU-R (Working Party 5D) on defining the framework and objectives for IMT for 2020 and beyond. It is this document that today serves as the basis of the different 5G research and standardisation work being done around the globe.

Next comes the standards development stage, based on the conclusions of the vision stage. Regarding IMT-2020, this development and standardisation work is already underway, and ITU plans on having completed it by 2020 to be able to satisfy the most pressing needs of the ITU members and organisations that want to deploy 5G as quickly as possible. This is all the more challenging as the development stage will last only five years, compared to 15 years for IMT-2000 and nine years for IMT-Advanced.

The different deadlines set for IMT-2020 within ITU can be found in Figure 17. The spectrum identification phases (indicated by the black triangles) coincide with the World Radiocommunications Conferences, of which the latest was WRC-2015 and the next is WRC-2019 (see 3.2).


New elements to offer capabilities of IMT-2020
Systems deployment *
Vision
Requirements
Standards development
Standards enhancement
Other radio systems
Evolution/Integration with other radio systems
IMT-2000 and IMT-advanced and their enhancement
Systems deployment
Enhancement and related development of standards (Rec. ITU-R M.1457 and ITU-R M.2012)
Spectrum for IMT
Spectrum implementation
2000 ~ 2014
2015
2016
2017
2018
2019
2020
~

Figure 17. Stages and expected deadlines for IMT-2020[53]

All of the work that ITU is conducting on IMT-2020 is following a roadmap that is detailed in Figure 18, with the completed stages indicated in green and those to come in blue. The work that is underway today concerns 5G spectrum aspects, prerequisites and assessment criteria, along with the different technical studies and proposals, which are a prerequisite to the standardisation phase of the work.

---

[53] Recommendation ITU-R M.2083-0 (09/2015), https://www.itu.int/dms_pubrec/itu-r/rec/m/R-REC-M.2083-0-201509-I!!PDF-E.pdf


Development Plan
Market/Services View
Technology/ Research Kick Off
Vision & Framework
Name IMT-2020
< 6 GHz Spectrum View
> 6 GHz Technical View
Process Optimization
Spectrum/Band Arrangements (post WRC-15)
Technical Performance Requirements
Evaluation Criteria
Invitation for Proposals
Sharing Study Parameters (IMT-WRC-19)
Sharing Studies (WRC-19)
Proposals
Evaluation
Consensus Building
CPM Report (IMT-WRC-19)
Sharing Study Reports (WRC-19)
Spectrum/Band Arrangements (WRC-19 related)
Decision & Radio Framework
Detailed IMT-2020 Radio Interface Specifications
Future Enhancement/ Update Plan & Process
2012-2015
2016-2017
2018-2019
2019-2020

Figure 18. WP 5D[54] work programme

3GPP

Based on ITU Recommendations, 3GPP has played a major role in the success of LTE over the past several years, which has been the fastest growing cellular technology to date: never before has a new radio standard been adopted and deployed as rapidly and as widely from the finalisation of the first version of its standardisation (for LTE Release 8, in December 2008).

For the first time, under the LTE acronym, the entire mobile industry agreed on a single new technology (contrary to 3G where 3GPP and 3GPP2 co-exist, each backing their version of 3G standardisation that complies with IMT-2000 criteria), and so enabling unprecedented economies of scale and momentum in the ecosystem.

After Release 8, the work performed by 3GPP has been centred on the following strategic areas:

- Enhancing LTE radio standards to further improve capacity and performance;
- Enhancing system standards to make LTE and EPC (Evolved Packet Core, the core LTE network technology) available to new business segments;
- Introducing improvements for system robustness, especially for handing exponential smartphone traffic growth.

These areas of focus have made it possible to map out the general path of evolution from LTE to LTE-Advanced (Releases 10 to 12) and later LTE-Advanced Pro (Releases 13 and 14) while awaiting 5G.

The ambitiousness of 5G requirements, the tight timeline “imposed” by the market, along with the different national tendencies have pushed 3GPP to define two stages of specification work:

1. A first stage that will end in the second half of 2018, with the termination of Release 15, and which will address the most urgent matters with respect to commercial requirements;

---

[54] https://www.itu.int/en/membership/Documents/missions/GVA-mission-briefing-5G-28Sept2016.pdf

2. A second stage that will end in December 2019, which marks the end of Release 16, which will address the other use cases and prerequisites identified in the IMT-2020 Vision Recommendation.

The Work Plan for Release 15, the first set of 5G specifications, was ratified at the plenary meeting of the TSG#72 (Technical Specification Group #72) 3GPP working groups in June 2016. This plan includes a set of intermediate tasks and checkpoints to steer ongoing work in the different groups. This Work Plan sets out the transition from current studies to the standardisation phase of the work:

- Starting in December 2016: beginning of standardisation work by TSG SA2 (Technical Specification Group System Architecture);
- Starting in March 2017: specification begins for the 5G NR (New Radio) interface in the TSG RAN (Technical Specification Group Radio Access Network).



1. TSG-RAN#73, September 2016: 5G NR Requirements TR completion

2. TSG-SA#74, Dec/2016: NexGen TR completion Approval of SA2 WID

3. CHECKPOINT: TSG#75: March 2017:
- Completion of NR SI with corresponding performance evaluation and concepts;
- Approval of RAN WID(s);
- Report from RAN1/RAN2/RAN3/RAN4/SA2 on fwd compatibility of NSA and SA NR;
- Report from SA2 on migration;
- SA and CT timeline coordination;
- Reconfirmation of NR & NexGen timeplan, including completion target for NSA higher layer components (box 6)

4. TSG-SA#77 or TSG-SA#78: NexGen stage-2 freeze.

5. TSG-RAN#78, December 2017:
- Stage 3 freeze of L1/L2 for common aspects of NSA (focused on licensed bands) and SA NR;
- Principles agreed for SA-specific L1/L2 components.

6. RAN#78/RAN#79: Stage-3 freeze for Non-Standalone higher layers (including components common with standalone). Completion target TBD.

7. TSG#80, June 2018: Release 15 stage 3 freeze for NR and NexGen, including Standalone.

Note: SA: Standalone
NSA: Non-Standalone

Figure 19. Roadmap for 3GPP standardisation groups[55]

If 5G is viewed as the technology capable of transforming society, and even of ushering in the next industrial revolution by impacting multiple (vertical) sectors with new business models and in a way that benefits the economy, notably in Europe, in all likelihood it will initially be driven forward by eMBB (Enhanced Mobile Broadband, cf. 1.2).

With this in mind, 3GPP defined the framework for Release 15, stage 1 specifications of 5G standardisation, as detailed earlier, whose work will focus on the following:

- Standalone and Non-Standalone NR operation: the Standalone version to work independently of LTE technology, and the Non-standalone NR being highly interoperable with LTE[56].

---

[55] https://5g-ppp.eu/wp-content/uploads/2016/11/01_10-Nov_Session-3_Dino-Flore.pdf

- Target use cases: starting with Enhanced Mobile Broadband (eMBB) as well as Low Latency and High Reliability to enable some URLLC (Ultra-reliable and Low Latency Communications, cf. 1.2) use cases.
- Simultaneous examination of frequency ranges below 6 GHz and above 6 GHz.

Release 16, the second phase of 5G specifications, will then focus more on other segments such as mMTC (Massive Machine Type Communications*,* cf. 1.2), for instance, to tackle IoT use cases that require higher quality of service than what LPWAN *(*Low-Power Wide-Area Network)[57] can provide.

---

[56] In its non-standalone version, the NR control plane is LTE's. in other words, the 4G network controls the 5G carriers and spreads users across the different bands and technologies.

[57] Sigfox and LoRa LPWAN

Annex 2 Entities Arcep met with

ERICSSON QUALCOMM® HUAWEI

SAMSUNG NOKIA

AIRBUS DEFENCE & SPACE THALES RENAULT

Systematic Paris Region Systems & ICT Cluster TELECOM ParisTech leti ceatech

f Google ETSI World Class Standards

bouygues TELECOM free mobile numericable THD SFR

orange™ GSMA™

Annex 3 Figures

Figure 1. 5G driving industrial and societal changes 4

Figure 2. Performances required by vertical sectors 6

Figure 3. What we do over the network today in one minute 7

Figure 4. 3GPP timeline for 5G 9

Figure 5. 5G use cases 10

Figure 6. Comparison between 4G and 5G with respect to the eight key performance indicators 12

Figure 7. Representation of the “average user experience data rate” KPI for 4G and 5G and “Peak data rate” KPI for 3G, 4G and 5G 13

Figure 8. Key performance indicators for the three 5G use cases 14

Figure 9. Example of the use of a beamforming antenna to connect Wi-Fi access points 16

Figure 10. Illustration of full-duplex, compared to FDD and TDD 16

Figure 11. Illustration de multiplexing *power domain* NOMA 17

Figure 12. Centralisation of the control plane in a software-defined network 18

Figure 13. Illustration of CloudRAN network architecture 19

Figure 14. 5G PPP vs. 3GPP and ITU roadmaps 22

Figure 15. Millimetre wave frequencies identified at WRC-15 28

Figure 16. Timeline of IMT developments and deployments 35

Figure 17. Stages and expected deadlines for IMT-2020 36

Figure 18. WP 5D work programme 37

Figure 19. Roadmap for 3GPP standardisation groups 38

White Paper

Designing 5G-Ready Mobile Core Networks

Prepared by

Gabriel Brown
Senior Analyst, Heavy Reading
www.heavyreading.com

on behalf of

www.affirmednetworks.com

and

www.juniper.net

September 2016

5G Core Service & Performance Requirements

An industry "Vision for 5G" is now established and supported worldwide. Services and performance requirements have been identified, and the industry is moving into the development and implementation phases with a view to commercial launch of 5G mobile service around 2019 and fixed wireless access using mmWave radio from 2017. To meet these schedules, leading operators – especially Tier 1s with high expectations and aggressive deployment timelines – are working to make their networks 5G-ready ahead of commercial deployment.

This white paper argues that with a 5G-ready technology strategy, operators can prepare for rapid 5G service launch in a way that optimizes their investment in next-generation IP and mobile core platforms over the next three years. Specifically, it discusses 1) how 5G services drive a requirement for an IP services fabric to connect the distributed data centers that will host 5G network functions, content and applications and 2) the development of cloud-native, service-orientated core networks for advanced 4G and 5G networks.

5G Services Dimensions

Development of the 5G system architecture, and associated core network, is being led by 5G service requirements. **Figure 1** shows the output from the 3GPP SMARTER study group that has investigated the service dimensions of 5G.

Figure 1: Service Dimensions in Future 5G Networks


Network Slicing / Reconfiguration
Connectivity / Routing
Migration / Interworking
Network Operation
Critical Communication
Industry Robot / Drone
Game / Sports
Massive MTC
Enhanced Mobile Broadband
eHealth / Wearable
Subway / Stadium
eCity / eFarm / Inventory
eV2X
Vehicle / autonomous driving
AR / VR
Train / Airplane
UHD / Hologram

Source: 3GPP SMARTER

The chart maps closely to the now famous triangle representation of 5G services made up of enhanced mobile broadband (eMBB), low latency and mission critical communications and massive machine-type services (mMTC). However, it adds two important axes: a dedicated eV2X axis for vehicular services and, significantly, a network operations axis.

The dedicated operations axis is important because it makes explicit that automation is fundamental to 5G. To address new commercial opportunities, operators need the ability to create service-specific "network slices" that extend end to end across the infrastructure. Automating set up and management of these "network slices," including configuration of the underlying IP network, is critical to the 5G business case.

These service dimensions incorporate many different performance requirements. **Figure 2** shows IMT-2020 performance targets, developed by the ITU, for 5G. To the left, these are shown in comparison to IMT Advanced (4G). To the right, performance requirements are mapped to the three major use-case categories.

Figure 2: IMT-2020 Performance Targets



Relative to IMT Advanced (4G)

Relative to Major Use Case Categories

Source: ITU Recommendation ITU-R M.2083-0, September 2015

Probably the most influential factor on 5G physical network deployment will be the low-latency requirement. To deliver services over a wide-area network (WAN) with a consistent 5-10ms roundtrip time is extremely challenging and will drive a new system architecture deployed on a distributed cloud infrastructure.

A 5G-Ready Network Investment Strategy

Operators now have a good idea of what 5G will look like in scope and a reasonable view into the initial deployments models. Development of normative standards for 5G new radio (NR) and the next-generation core network (NG Core) is underway with the first specifications – and the first "compatible" pilot deployments – expected in mid 2018. Although there is uncertainty about the details of the specifications under development, the industry has already undertaken significant R&D work on 5G candidate technologies, making it is possible for operators to pursue a 5G-ready network strategy with a reasonable degree of confidence that they will be able to rapidly deploy 5G, at scale, as the technology becomes commercially available.

From an IP and core network perspective, five tiers of a 5G-ready investment strategy are, from the ground up, as follows:

1. **Develop a distributed data center footprint**. The Central Office Re-architected as Data Center (CORD) model provides a good reference. The idea is for operators to develop physical assets located close to the edge and transform them into distributed data centers. The edge location is critical for low-latency 5G services and, as Mobile Edge Computing (MEC) shows, the edge-cloud is valuable in many networking scenarios – it is not solely a 5G investment. In time, the distributed data center will also come to support Cloud RAN (C-RAN) and Virtual RAN (V-RAN) hub sites and will host core network functions, such as distributed user-plane nodes.
2. **Create an "IP Services Fabric" for 5G with software-defined networking (SDN) control**. Edge-cloud locations running 5G network functions and services will require high-performance, secure connectivity. Investment in wide-area SDN is already underway to create an "IP services fabric" that connects centralized data centers, distributed cloud locations and cell sites. This IP services fabric provides routing, security, service chaining, redundancy and orchestration. Again, this investment is, in many aspects, not unique to 5G, but common to high-performance networking at the cloud edge.
3. **Invest in cloud-based Evolved Packet Core (EPC) and NG Core.** With a distributed cloud infrastructure, it is logical to redesign core network functions to take advantage of this asset to meet the strict latency requirements of 5G services and efficiently manage data traffic. Some aspects of NG Core are already reasonably well understood, (for example, control- and user- plane separation or "CUPS"), while others remain works in progress (for example, mobility and session management). In general, expect control-plane separation to apply across the 5G architecture, from radio to core.
4. **Use network slicing for a service-optimized core.** Network slicing is an important bridge from a 4G core to a new 5G core and is a key component of a 5G-ready network investment strategy. In this model, virtual network functions (VNFs) are created per service and data is routed via an optimized processing path across the network. By isolating services into virtual network slices, operators can offer better security, more efficient transport, optimized core network processing and appropriate service quality. A network slice created for an Internet of Things (IoT) customer, for example, may support both 4G and 5G access networks.
5. **Automation and service orchestration.** Automating network operations provides the ability to launch new services rapidly, to reach new market segments, to evaluate success/failure quickly, and then to modify, scale and repeat. Significant progress is being made in applying service orchestration to 4G-Long Term Evolution (LTE) networks, especially where software-based core networks are deployed. Network slicing is a good example of the need for automation because there will be many more logical entities to commission, provision and manage. "Automated service orchestration" is a good, tangible example of 5G-ready functionality.

The 5G Core Network

The new 5G core network is now reasonably well understood: It will be "cloud-native," it will make extensive use of network slicing, and it will operate in concert with a new model-driven service orchestration layer. The industry can therefore start to develop NG Core products that can be adapted as standards emerge and solidify.

From a practical perspective, for the initial deployment, operators can support 5G radio access on a "5G-ready" EPC and then migrate to a new NG Core over time. In both cases, the "IP services fabric" provides SDN-controlled connectivity and related IP services, across a distributed cloud infrastructure.

Virtualized & Cloud-Native Mobile Core

Operators have made good progress on virtual EPC over the past couple of years. The largest networks now support more than 15 million subscribers (AT&T has discussed this publicly); some progressive operators have started to refresh their main EPC networks using multivendor network functions virtualization (NFV) (e.g., Docomo, Etisalat); and others (e.g., Vodafone) have deployed virtual core elements for IoT services.

Figure 3 shows two migration paths to a "cloud-native" 5G core. The blue line shows a virtualized 4G core as a stepping stone to a "5G-ready" core and then a full 5G core. The grey line shows a more conservative option where the operator scales the classic EPC in the near-term and then makes a bigger leap to 5G later.

Figure 3: A Preliminary Cloud-Based 5G Architecture


Virtual 4G Core
"5G-Ready"
5G NG Core
Introduce software features:
• Network slicing
• Automation
• Distributed user-plane
• User-portals
• Cloud native VNFs
• Scale-out/in on demand
"Big Lift" Migration Strategy
Classic Core
Scale existing solution
Evolve?

Source: Heavy Reading

There is debate about what exactly "cloud native" means, particularly in the context of stateful telecom network functions. Nevertheless, Heavy Reading's established view is that operators that deploy virtual EPC – even at small scale – gain experience in how these systems work, how to operate them, and how to evolve them, and that in turn will give them a sustainable advantage in the longer-term transition to software-centric 5G mobile networks.

Migrating 5G RAN From EPC to NG Core

A 5G-ready core strategy is determined, in part, by how the operator plans to introduce 5G radio. There are two basic possibilities: operate 5G RAN using an EPC or using a new NG Core. In practice, operators with plans to launch 5G early are likely to start with an EPC and migrate to NG Core over time, as shown in **Figure 4** below.

Figure 4: Migrating 5G RAN from EPC to NG Core



Source: 3GPP TR 38.801 v0.4.0

The diagram is taken from the most recent version of the 3GPP "Study on New Radio Access Technology" (TR 38.801), which will inform development of standards in Release 15. Several permutations of the architecture are under consideration; however, in simple terms, to the left, the new 5G base station (gNB) user-plane interface connects directly to a 4G EPC, while the control-plane functions, such as tracking, paging, etc., are provided by an evolved 4G base station (eNB), which in turn also connects to the EPC. In this scenario, the EPC requires little or no modification, making this a fast and simple way to deploy 5G radio from a core perspective.

Over time, both 4G and 5G base stations can migrate to a new NG Core, which will provide both control- and user-plane functions. At this stage, NG Core becomes the primary core network for 4G and 5G access, as shown to the right in the diagram. This is conceptually similar to how EPC supports 3G and 4G access networks.

Note that in cases where 5G radio is deployed for fixed wireless access, there is no need for an LTE RAN to provide control-plane functions to the 5G user device; a standard EPC is sufficient, although it would need to provide session management for the 5G access. Some of the first 5G deployments are expected to use this model.

Network Slicing: A Key Bridge to 5G

Network slicing is one of the key bridges between the 4G and 5G core. To support diverse service types, operators will use multiple core networks deployed as "network slices" on a common IP services infrastructure. The idea, shown in **Figure 5**, is to create virtual core network instances (or "slices") dedicated to different services. Each slice can be optimized for the traffic profile and the commercial context of the associated service – for example, IoT, public safety, mobile virtual network operator (MVNO), connected car, voice over WiFi or enterprise services. Network slices can be two dimensional in the sense that they can be both service- and customer-specific.

Figure 5: Dedicated Packet Core Network Slices

- Virtualization enables multi-tenant and single-tenant private core networks
- "Slices" configured according to service type & traffic profile
- Multiple options to steer user traffic into a core network processing path
- Mechanisms in 3G/4G include APN routing, MoCN, DECOR



Source: Heavy Reading

IoT is an example of how operators can use "slicing" to support a 5G-ready core strategy. Since many of the core network design parameters are similar between 4G and 5G, investment in a software-based IoT core network can be made with the expectation that the same core (with software updates) will also support IoT services on 5G in future. Moreover, because devices from both access types will connect to a common IoT core, operators will be able to develop integrated 4G/5G IoT strategies that optimize investment and enable them to go to market with narrowband IoT services before 5G specifications are released and radio equipment is deployed.

5G will, naturally, bring more capabilities to network slicing. Most importantly, it is expected that the slice will run end to end across the RAN, core and transport network. Radio is typically deployed as a shared resource, which means that 5G slicing will involve advanced self-organizing network (SON) capabilities and hierarchical, slice-aware scheduling on the air interface. On the network side, the operator can use SDN to reserve resources for the network slice on the IP services fabric.

NG Core for 5G

A new core network offers important benefits, particularly for services with demanding performance requirements, and is an important part of the 5G architecture. The high-level view of the NG core network architecture, as it looks in September 2016, according to TR 23.799 (the Technical Report on the NextGen System Architecture) is shown in **Figure 6**.

The chart shows the primary elements of the new 5G system architecture, including the device (UE), the radio access network (NG-RAN) and the core network that comprises the control-plane (NG-CP) and user-plane (NG-UP) functions. The separation of control and user planes is a direct extension of the "CUPS" concept being developed for advanced EPCs in 4G networks and is another example of how operators can invest in 5G-ready core network designs in the near term.

Figure 6: High Level View of NG Core Architecture (Proposed)


User Data
Management
(Persistent)
UDM
AF
Application
Function
NG7
NG5
Mobility Management
Session Management
Policy Control Function
NG-CP
MM
SM
PCF
Network Slice
Selection Function
NSSF
AU
CM
LI
Authentication, Authorization
Charging Management
Lawful Intercept
NG1
NG2
NG4
NG3
NG6
UE
NG-(R)AN
NG-UP
Data
Network

Source: 3GPP, Adapted from TR 23.799 v0.8.0, September 2016 (Figure 7.2.4-1)

It is interesting to compare this new functional architecture with the existing EPC. **Figure 7** maps the new NG Core elements to their equivalent in EPC. It shows significant overlap between the EPC and NG Core and provides confidence that today's state-of-the-art EPC is reasonably close to the next-generation core in terms of functionality, albeit that the interfaces and protocols will change/evolve.

Figure 7: Mapping NG Core & EPC Functions

NG Core Network Function	Approximate Equivalent EPC Function
UDM (User data management)	SPR
AF (Application function)	AF
NSSF (Network slice selection function)	MME (DECOR) + HSS
MM (Mobility management)	MME + SGW / MME + SGW-C
SM (Session management)	PGW/PGW-C
PCF (Policy control function)	PCRF
AU (Authentication & Authorization)	HSS/AAA
CM (Charging management)	PGW + PCRF, OCS, OFCS
LI (Lawful intercept)	LI
NG-UP (User-plane function)	SGW + PGW / SGW-U + PGW-U

Source: Heavy Reading, Affirmed, Juniper

Key Capabilities of the Next-Gen System Architecture

In addition to proposed architectures, the Technical Report provides guidance on the features and services NG Core should support. It identifies 19 key issues for the Next-Gen System Architecture, which can be grouped into four categories:

- **Flexible Deployment**: Including network slicing, user-plane network selection, network function granularity (e.g., decomposition of VNFs and service chains), interworking and migration, a policy and charging framework.
- **Flexible Access Support**: Including variable core/access splits, a flexible authentication framework (with varying credentials according to device-type, use case and policy), support for relays and multi-hopping, improved network discovery and selection mechanisms.
- **Connectivity**: Including session management, mobility management, a quality-of-service (QoS) framework and service and session continuity (e.g., across accesses).
- **Adapting Existing Capabilities**: Including network/service capability exposure, multicast and broadcast, IP Multimedia Subsystem (IMS) support, off-network communications (e.g., *ad hoc* networks for public safety).

Implementation of these capabilities is tightly linked to both the design of the NG Core and the underlying IP service infrastructure. The 3GPP specifications do not reference connectivity services, but, in practice, there is a close relationship.

A Distributed 5G Services Fabric

The infrastructure onto which 5G will be deployed should support multiple, demanding use cases. This drives a need for a high-performance wide-area IP services fabric controlled (or "orchestrated") by SDN. This IP services fabric should provide connectivity between many different distributed data centers in a meshed architecture that provides resiliency and scalability, and should be programmable such that it can support dynamic, service-specific network slices. In effect, the IP services fabric makes distributed centers act in a unified manner – i.e., behave as one integrated data center. The concept is shown in **Figure 8**.

The design of the distributed IP services fabric is formed by the variety of use cases, the requirement for low latency and high availability, and the need to scale efficiently. In tandem, the mobile network architecture will evolve to a more distributed model. To meet 5G service requirements, NG Core will be deployed using the "CUPS" model, with user-plane nodes hosted at distributed data center locations, and control-plane nodes at more centralized locations, interconnected by the IP services fabric.

Service orchestration will generally be domain specific, with SDN-controlled IP services, cloud resource management, NFV lifecycle management and end-user service orchestration, all operating quasi-independently in a layered architecture. Coordination between the layers will use "cross domain orchestration" to ensure a network slice contains all the networking components needed to deliver the service.

Depending on how the architecture evolves, there will be a need to support highly accurate, 1588v2-based timing (frequency and phase) within this IP services fabric. Virtual RAN/Cloud RAN is an example on the network side that benefits from accurate network timing. On the customer side, it is expected that some market segments, such as the financial industry, will also require timing to be incorporated into network slices.

Figure 8: IP Services Fabric for 5G Networks



Source: Heavy Reading

Distributed Data Centers

To provide access network services, telecom operators have a physical footprint – in the form of central offices, base station controller sites and transport aggregation sites – that they can convert into distributed or micro data centers.

Depending on the service requirements, these data centers can be used to terminate access connections using virtualized edge functions and become the obvious place to host latency-sensitive content and applications. For centralized cloud providers, this capability is harder to replicate unless they build out an extensive physical footprint or partner with an access provider, and, therefore, this strategy provides operators with a potentially important and sustainable competitive advantage.

The "edge cloud" model will be critical to 5G and is the subject of detailed R&D across the industry. As an example, a preliminary architecture developed by the SuperFluidity project (a European 5G research project) is shown in **Figure 9**. Work on this particular project, which is academic in focus but contains several industrial partners, is scheduled to finish by the end of 2017.

As the name implies, the project aims to achieve superfluidity in the network: the ability to instantiate services on the fly, run them anywhere in the network (core, aggregation, edge) and shift them transparently to different locations. This is the essence of the "IP Services Fabric" for 5G. In this new network, operations will also need to move from a "red light, take action" model to an automated model where the orchestration and associated next-gen operations support system (OSS) detect and fix problems with the IP and NFV layers, and re-optimize the network accordingly.

Figure 9: A Preliminary Converged Cloud-Based 5G Architecture


ACCESS NETWORK
AGGREGATION NETWORK
CORE NETWORK
deploy
deploy
deploy
deploy
microserver platform
LTE
microserver platform
5G
base station site
microserver platform
Multi-cell aggregation site
micro-DC platform
PoP
micro-DC platform
PoP
PoP
Point-of-Presence site
micro-DC platform
x86 platform
Data center
Internet
low delay, low compute/storage capacity
higher delay, high compute/storage capacity

Source: [SuperFluidity]

Central Office Re-architected as a Data Center (CORD)

There are several industry and service provider initiatives to define the architecture for SDN-enabled distributed data centers. The Central Office Re-architected as a Data Center (CORD) initiative hosted by the Linux Foundation is one example of how operators aim to make better use of these assets.

According to the CORD initiative, AT&T alone operates 4,000 to 5,000 central offices, each serving 10,000 to 100,000 residential, enterprise and mobile customers. These central offices contain fragmented vendor hardware with multiple physical appliances installed per site (AT&T said it has 300+ unique appliances deployed in its central offices nationwide). The opportunity is to re-architect these central offices to support edge cloud infrastructure and deploy VNFs in place of appliances.

Each CORD location will be connected using an SD-WAN, making it possible to load-balance content and NFV workloads across the distributed cloud using the same SuperFluidity concepts discussed above. In the CORD case, the focus is on the ONOS controller, but in the sense that this is a generic architecture, multiple SDN controller options are viable and attractive. Note that for I/O-intensive workloads, the selection of an edge location should consider the physical transport resources available at the site. It would not make sense, for example, to deploy a 5G user-plane node for fixed wireless access in a central office that does not have a high bandwidth connection to the Internet.

In March 2016, the Linux Foundation announced the M-CORD initiative for mobile operators, backed by AT&T, SK Telecom, Verizon, China Unicom and NTT Communications. It highlighted three key aspects of the architecture, saying that it:

- Will use the same CORD principles of elastic commodity cloud and SDN to bring data center economies and cloud agility to the mobile edge.
- Will demonstrate integration of disaggregated/virtualized RAN, disaggregated/virtualized EPC and mobile edge services.
- Will partner with the SDN controller groups to accelerate adoption of open source SDN and NFV solutions and realize the benefits of the cloud.

Given the timing of the work, we expect M-CORD and similar initiatives to turn their focus toward "5G-ready" core networks as the architecture, interfaces and protocols for NG Core become more clear. A common CORD and M-CORD implementation, with the same architecture and foundational technologies, will create a good foundation for fixed-mobile network convergence, enabling access agnostic services – an important objective of many operators pursuing 5G.

Mapping Mobile Core to Distributed Cloud

The NG Core for 5G and EPC for advanced 4G networks must be mapped to the distributed cloud architecture. One approach would be to simply deploy more packet gateways (and mobility controllers) at the edge of the network to meet capacity and performance demands.

The challenge with this is that today's centralized packet core deployments are characterized by complex integration with surrounding network functions, such as policy, charging, IMS, SGi-LAN and routing services. By moving this model to the edge, the operator would, in effect, have to "distribute complexity," which is costly to deploy and, in particular, to manage. To meet 5G performance, scalability and automation requirements, a new architecture for packet core is needed that will make operation in the edge cloud infrastructure simpler and faster.

There are many aspects to this new architecture. Part of the solution is CUPS, as is currently being developed for 4G-LTE core networks. This involves extracting the control-plane functions from the gateway to leave a simpler, user-plane node. The gateway thus is "split" into S/PGW-U and S/PGW-C components that can that can scale independently, as shown in **Figure 6** above. A key benefit of the architecture is that the control plane, and all the associated complex interactions, can be centralized, while the user plane is distributed across the IP services fabric and scaled as required by the traffic load. This is shown in **Figure 10**.

Depending on the scaling needs, the S/PGW-U functions deployed at the edge data center can be implemented in several different ways: on a router, on a white box switch (potentially), on an existing PGW platform, as a virtualized function, or as part of a vRouter. Virtualized user-plane nodes can more easily be placed at the optimal location, as determined by the use case and this flexibility is a strong argument to deploy S/PGW-U nodes as VNFs rather than as hardware functions.

The S/PGW-C components would similarly be deployed as virtualized functions on a cloud platform, typically at a more centralized location. There may be an opportunity to collapse MME, SGW-C, PGW-C functions and perhaps other 3GPP control-plane functions into some form of unified "mobility controller" node. This has the potential to simplify operations and this same model is being pursued for NG Core.

In this architecture, virtualized SGi service LAN components can be placed where appropriate for the traffic coming from the distributed user-plane nodes. For example, some SGi functions could be on router-based compute blades, or on COTS x86 servers deployed at the distributed site, while others could be in the central data center or close to Internet peering points. The selection of the site for the SGi functions is carried out by the central orchestration system, which steers traffic into service chains on a per subscriber, application, bearer, device or combination basis.

Figure 10: Distributed User-Plane at Edge Data Centers


MME
PCRF
PGW-C
SGW-C
Centralized Control Plane
Public/Private IP Services
Control
User
C/U Protocol
Control Plane
User/Data Plane
C/U Protocol
PGW-U
SGW-U
WiFi
GiLAN
3rd party VNF
Distributed User Plane

Source: Affirmed Networks

This model of discrete control- and user-plane functions is expected to be fundamental to 5G and the NG Core. In this sense, CUPS can be viewed as an important part of a 5G-ready investment strategy.

A 5G-Ready Core Is Now a Priority

The industry now has a reasonable view of 5G service requirements, and progressive operators with aggressive deployment timelines are now working to prepare their networks for rapid deployment of 5G when equipment is available. This is driving investment in the critical IP services network needed to connect the edge cloud locations that will run 5G network functions, content and services.

On the mobile core side, development of cloud-native, service-orientated core networks for advanced 4G and 5G networks is underway. Network slicing provides a conceptual bridge between 4G and 5G investment and facilitates a faster insertion of new services into the network. Similarly, CUPS provides a reference for NG Core and the new 5G network architecture. With a 5G-ready technology strategy, operators can prepare for 5G service launch in a way that optimizes their investment in next-generation IP and mobile core platforms over the next three years.

About Affirmed Networks

Affirmed Networks' NFV solution has become the standard for the world's top mobile operators, who are embracing new business models and building new revenue streams by making the transition to virtualized architectures. The company's technology portfolio includes the Affirmed Mobile Content Cloud, the Affirmed Wi-Fi Gateway (serving as a TWAG/TWAP and an ePDG), Affirmed Service Automation Platform (ASAP) and Affirmed Virtual Probe and Analytics Solution. These virtualized solutions have come to represent the present and the future of virtualized mobile networks with extreme scalability, remarkable flexibility, comprehensive network orchestration and future-proof solutions for a 5G-ready architecture. Please find more information at www.affirmednetworks.com.

About Juniper Networks

Juniper Networks (NYSE: JNPR) is in the business of network innovation. From devices to data centers, from consumers to cloud providers, Juniper Networks delivers the software, silicon and systems that transform the experience and economics of networking. The company serves customers and partners worldwide. Additional information can be found at www.juniper.net, or connect with Juniper on Twitter and Facebook.

CONSULTING - SPECIFYING engineer

CFE Edu
CFE Edu is an interactive, multi-media online platform that offers exclusive content covering engineering topics that are critical to your work.
Catapult your career for

PE New Products for Engineers Database
Find An Innovative Product

PE
Searching for a product?

Energy harvesting power for the Internet of Things

Energy harvesting wireless technology easily interconnects thousands of individual devices in a system, opening up unlimited processing and monitoring applications.

Laurent Giai-Miniet, EnOcean, Oberhaching (Munich), Germany

09/30/2013

Share



Energy is everywhere within reach; it just needs to be harvested. This is the principle of energy harvesting. Today, energy harvesting wireless solutions are already well established in the commercial building automation sector. But the technology is just getting started. New application fields for batteryless, wireless communication will be found to further enhance the world around us.

Based on energy harvesting wireless technology, a wide range of energy-autonomous applications are currently available for connected buildings that use motion, light, or temperature differences as their energy source such as batteryless switches; intelligent window handles; temperature, moisture, and light sensors; presence detectors, heating valves; and smart home systems. However, building automation is by no means where energy harvesting wireless ends.

Multiple interconnections

Everybody's talking about the Internet of Things (IoT). But how should billions of communicating devices be powered? The answer is by energy harvesting, and the reason is simple: Liberating sensors from external power, making them energy-autonomous, opens up unlimited processing and monitoring applications where cables or batteries represent an insurmountable hurdle. These features make energy harvesting wireless technology the ideal communication standard to easily and reliably interconnect thousands of individual devices in a system, as well as network them with other wireless protocols.

at AireTechnologies, Inc
HVAC Human Fire Life Safety Devices
Delivered As Early As Tomorrow!
Learn More
JAN 22-24, 2018 AHR EXPO CHICAGO
Visit us at the AHR Expo Booth 5341

Today, energy harvesting wireless technology is widespread, providing M2M solutions in the building automation sector and bridging the control of light, HVAC, and other fields of building technology to smart buildings, smart metering, and energy management systems. This is the starting point to actuate further applications that lead to the IoT in the long term. The following four categories show what this could look like.

Monitoring and control

Wireless and batteryless technology significantly eases energy monitoring and control in buildings with little intervention into the existing systems. The wireless devices are highly flexible to install so that individual components, wall switches, sensors, and relay receivers can be easily networked to form an intelligent system without complex cabling. In addition, dispensing with batteries eliminates the burden of maintaining the devices' energy supply in a regular time period, which can be up to each year.

An example for such a flexible automation system is HVAC control. Here, a thermostat, VAV (variable air volume), or fan coil controller receives information related to occupancy, temperature, humidity, window position, or CO_2 from the respective batteryless sensors and controls the opening and closing of valve actuators for radiators, or dampers for VAV systems. At the same time, the controller sends status information to a central building automation system, and receives control messages from the BAS. This enables the building to be monitored from a central location that can be remote from the building itself, and building-wide settings, such as holiday shutdown, to be implemented. Enormous progress is also being made on the product side, leveraging advancements in energy harvesting. Self-powered radiator valves generate energy from the difference in temperature between the hot water and the surrounding air. This energy powers the communication with a controller or BAS system, and turns the valve itself. Without cables or batteries, these wireless devices are especially easy to install, and they require no maintenance.

In further optimized systems, central equipment such as boilers or air handling units are integrated into the wireless communication system, enabling scalable HVAC generation, visible and controllable over the Internet on a PC, tablet, or

PE
Searching for a product?

smartphone.

Performing tasks

16:56
Auto
enocean

Alarm systems are a second field that batteryless wireless technology is opening up, due to its specific features. Here, the reliability requirements are much more stringent than those required for lighting controls. A system failure not only means a malfunction but also can cause much more serious consequences for other systems that depend upon the equipment being monitored. It's a fact that more malfunctions are caused by battery failures than by the electronics, especially in large systems. Energy harvesting overcomes this issue.

There are already various batteryless wireless water detectors available that use miniaturized solar cells or motion energy converters to power wireless signals that report water leaks in areas such as water supply networks in spacious industrial facilities. In the AFRISO universal module, for example, the EnOcean wireless signal immediately sends the leakage information to a gateway controller or directly to a valve, causing the main water pipeline or the affected supply line to be shut off. A notification is sent to the user's smartphone or smartpad at the same time to inform the user about the incident. In addition, the water valve can be opened and closed, independent of leakage notifications, by GSM connection via smartphone or smartpad.

Embedded processing

A major requirement of today's and the future energy supply is the Smart Grid. It's intended to network centralized and decentralized energy suppliers, including private homes producing electricity by photovoltaic installations, to an intelligent system that provides energy only when needed, updating in real time. This requires continuous data flow and processing from all involved parties, which means from millions of information points.

A key component is smart metering systems. To work reliably and cost-efficiently, interoperability between the meters is supplied by different manufacturers; this is why smart metering calls for standardized technologies. Consequently, the members of the EnOcean Alliance have defined a specific device communication protocol, the Automated Meter Reading (AMR) profile for batteryless wireless devices. Smart meter systems based on this open protocol are already available from a number of manufacturers. For example, Eltako meter components read and transmit the current electricity, water, and gas consumption, including accumulated meter figures, by means of energy harvesting wireless technology located at a variety of points inside a building. BSC software monitors and displays the current meter readings and compares them against default values. This makes all relevant data available for systems processing for intelligent energy management on demand.

Bridge to the cloud



Via similar gateways, the standard-based energy harvesting technology can also communicate with Ethernet, Wi-Fi, GSM/UMTS/CDMA, and other networks for integration in cloud services. Here, all data collected by batteryless wireless sensors is encrypted and transmitted to a cloud service over the Internet. The gateways connected to a control and visualization software by TCP/IP that can be used to control all relay receivers and sensors bidirectionally. Some manufacturers have developed a cloud solution that offers energy management as a service. Therefore, facility managers, building owners, and businesses can monitor important inventory, equipment, assets, and energy-related information from anywhere at any time, via the cloud. Critical building-related data is automatically pushed to the cloud, freeing owners and managers from the often-challenging coordination and expense of hosting on-site servers.

One of the major advantages of such a cloud-based solution is that the management system arrives completely precommissioned from the manufacturer and ongoing device commissioning is expertly done on behalf of the client and pushed out from the cloud. The users are granted unlimited access to their remote, dedicated virtual server with their own IP address, accessible from a desktop or smartphone — the perfect precondition for a deeply connected world of an IoT.

The energy harvesting market is growing and multiplies on a year-by-year basis. Forecasts show that this trend will continue, especially as the next generation of energy harvesting wireless solutions is just around the corner to pave the way to the Internet of Things.

Laurent Giai-Miniet is CEO of energy harvesting wireless solutions provider EnOcean and previously spent 20 years with Texas Instruments (TI), where he held several management positions including General Manager for Low Power RF Products (LPRF).

Related News:

- Energy harvesting for Internet of things - 02.07.2014 01:48
- Consumer market will drive industrial Internet of things for manufacturing - 06.03.2014 11:43
- How the Internet of Things will affect consulting engineers - 02.01.2014 11:35
- IP-all-the-way is the way to go - 23.07.2013 01:28
- Integration: Lighting and HVAC systems - 16.04.2013 01:30

More than 80 photos

The Basic Soldering Guide

Learn to solder successfully!

Alan Winstanley



565435
01283




01283
DLOG1

In association with

ANTEX

ANTEX (Electronics) Limited

The Basic Soldering Guide

by Alan Winstanley

***EPE Magazine* Online Editor**

In association with

Antex (Electronics) Ltd.

ANTEX

ANTEX (Electronics) Limited

Copyright Notice and Disclaimer

All text, diagrams and photographs are Copyright © 1996-2013 A. R. Winstanley. All Rights Reserved.

All text, diagrams and photographs are fully protected by copyright and may not be reproduced in any commercial or non-commercial publication or medium, mirrored on any commercial or non-commercial website nor may they be appended to or amended, monetised or used or re-distributed for any commercial reason, without the prior permission of the writer.

Every care has been taken to ensure that the information and guidance given is accurate and reliable, but since conditions of use are beyond the writer's control no legal liability or consequential claims will be accepted for any errors contained herein.

Where mentioned, the U.K. mains voltage supply is 230V a.c. and you should amend ratings for your local conditions.

Preface

In 1996 when the world wide web was still very young, I launched the first and most detailed website ever describing the practical skills of electronic soldering, and my **Basic Soldering Guide** quickly became the #1 web site of its kind in the Google search engine.

Thanks to its in-depth reference text and the unequalled high-quality close-up photography showing soldering step by step, many quickly learned the essential stages needed to make a solder joint successfully. Even novices who had never tried soldering before, gained the skills and confidence needed to acquire this skill.

My Basic Soldering Guide became a key *go-to* online guide for soldering, and I’ve enjoyed receiving encouraging feedback ever since from the likes of the US Air Force, US Marines, US Coastguard, Honeywell trainers, Atomic Energy authorities, Australian aeronautical suppliers, UK colleges and universities, trainees and many more around the world.

In association with Antex (Electronics) Ltd., the leading UK manufacturer of electronic soldering equipment, I’m delighted to bring you this updated Basic Soldering Guide containing over 80 all-new colour photographs, more background, more detailed information and lots more practical hints and tips.

I’ve revisited various areas of the guide and refreshed them, taking onboard readers’ queries and nearly 17 years of online feedback, experiences and answering reader’s questions. With the help of all-new photography, I’m sure you’ll master the skills needed to solder electronics successfully using this updated guide.

I welcome feedback and comments, and readers can reach me via my website **www.alanwinstanley.com** or Email me at **alan@epemag.demon.co.uk**

Alan Winstanley

July 2013

Table of Contents

Copyright Notice and Disclaimer

Preface

Introduction

First steps

Soldering iron choices

How to solder

Next steps

Cleanliness and “Tinning” the bit

Getting Ready

Solder and Fluxes

Flux dispensers and Colophony

Temperature flow

Now is the time…

Soldering Step by Step

Interwiring – get hooked up!

Wire joints

Tidying up

Reflow technique

Fatigue & Breakage

Faults & Desoldering techniques

Desolder Braid

Quick Summary Guide

Troubleshooting Guide

Possible Hazards and simple First Aid

Useful resources

Acknowledgements

Photography

Conclusion

Introduction

The first and most important aspect of assembling any electronic project is that of *soldering,* which is a delicate and precise skill that can be mastered with experience. Sometimes called “soft soldering”, there’s no shortcut to acquiring the necessary expertise, and producing a consistently satisfactory solder joint takes a little practice. However, like riding a bicycle, soldering is an art which once learnt is never forgotten, and the purpose of this new and updated guide is to explain the techniques of soldering and desoldering for beginners, which I hope will set the hobbyist or trainee technician firmly on the road to successful electronic assembly or repairs in the future.

Soldering is the least “aggressive” way of joining non-ferrous metals together, and is used universally in electronics, air conditioning and refrigeration circuits, household plumbing and more besides – applications where the precise joining together of components at fairly moderate temperatures is needed. Further up the scale, **brazing** involves using higher temperatures to melt brazing rods onto larger metal parts, perhaps to repair a metal chair, lawnmower or to fabricate metal components or jewellery into intricate shapes. Lastly, **welding** is a very aggressive way of fabrication using welding rods or wire; steel girders, oil rigs and ships are all welded together, or robotic spot-welding is used for the mass production of, say, washing machines or car bodyshells using sheet steel to make strong rigid assemblies.

Due to the lower temperatures used and the need to make consistently good electrically conductive and mechanically sound joints with precision, soldering is used to connect components together when manufacturing electronic circuits. Small components would quickly be destroyed by brazing or welding, although tiny spot-welding joints do appear in electronics, perhaps to weld a metal tag onto a button battery.

This guide therefore deals with the soldering techniques used in electronics at hobbyist or trainee educational level. It explains what to look for before buying a soldering iron, describes ways of making various solder joints on circuit boards and other electronic components, and also how to *desolder* – removing solder in order to repair a circuit board or replace an electronic component.

You’ll also find more details of other aspects of soldering, including an outline of typical solder types and fluxes. In short, everything you need to get started in electronics soldering is here, so let’s get started!

First steps

The principle behind soldering sounds quite simple: the idea is to join components together to form an electrical connection, by using a mixture of lead and tin solder or alternatively “lead-free” solder (an alloy of tin and copper), which is melted onto the joint using a *soldering iron*. If you have never picked up a soldering iron before, then this guide will show you everything to help you start soldering with confidence. I also hope that the guidance will help those working in other areas — computer technicians or audio enthusiasts, for example, who may be faced with electronic repairs or modifications using a soldering iron for the first time.

If you’re an electronics hobbyist or trainee, before embarking on any form of ambitious electronic project, it is recommended that you practice your soldering technique on some *brand new* components using *clean* strip board (or protoboard) or a printed circuit board, and select a simple and straightforward constructional design as a starting point. Become acquainted and comfortable with your chosen soldering iron, which likely to become as familiar to you as a favourite pen. Learn how to balance it and handle it with precision. Try soldering an assortment of resistors, capacitors, diodes, transistors and integrated circuits with it, and then try your hand at *desoldering* – removing the solder again to make a repair or modification.

A really good place to start learning is by building a simple electronics kit, such as a Velleman kit that contains a good quality printed circuit board. You’ll learn some of the basic skills of successful soldering this way, and it’ll be a great confidence booster too.

Did you know? In the USA and elsewhere, the letter L in “solder” is silent and they say “soda” or “sodder” – but here in Britain we do pronounce the L and we say “sole-der”.

Soldering iron choices

Search any electronics catalogue or website and you'll see a bewildering array of soldering equipment on sale, including irons, controllers, work stations and desoldering equipment too. A large range of soldering irons is readily obtainable - which one is suitable for you depends on your budget and how serious your interest in electronics is, but there's something for every pocket distributed by a variety of retail, industrial and mail-order outlets.

The Antex range of soldering equipment has been very popular with industry, education and the electronics hobbyist for 60 years; I grew up with an Antex iron and a trusty 15W Antex iron was an everyday part of my hobby electronics all the way through the 1980's. An industrial user or a more dedicated hobbyist – with a bigger budget! – will be interested in a soldering station instead and again Antex offers a range of British-made products for industry or home use.

A very basic mains electric soldering iron can cost from under £5 (US$ 8), but I find that these very cheap irons, as sold on auction websites, are pretty crude and imprecise. They are best suited for simple electrical repairs and DIY rather than precision electronics or printed circuit boards discussed here. They tend to be bulky and uncomfortable for extended use, and they may not have suitable "bits" or tips of various sizes to suit different tasks.

^^ This classic Antex XS25 "pencil style" 25W mains-powered soldering iron has exchangeable tips or "bits" and is great for general hobbyist or educational use. Stands are also available to store them safely in between use.

A quality pencil-style electric soldering iron such as the Antex XS25 (photo) will be approximately £20 (US$18 tax free) - though it's possible to spend into three figures on a soldering iron “station” if you’re really serious about the subject! Don’t be tempted to over-spend on an elaborate workstation though, unless you are really very serious about becoming involved in electronics. You will usually obtain perfectly satisfactory results using a fairly modest “pencil” iron model, and you can upgrade to something more sophisticated should your needs change in the future.

^^ For enthusiasts or industry, this Antex 660TC soldering station has a separate mains-powered control unit and a matching low-voltage soldering iron rated at 24 Volts, 50 Watts so it’s suited to a wider range of tasks than a lower powered one.

When choosing your soldering iron, certain factors to bear in mind include:

Voltage: for the British market, “mains” electric irons run directly from the mains at 230V a.c. or will be set for other voltages (110V a.c.) depending on the country. However, **low voltage types** (e.g. 12V or 24V) usually form part of a “soldering station” for use with a matching controller made by the same manufacturer. Some low-voltage irons run off batteries (e.g. a car battery or Ni-cads) but these are uncommon.

Wattage: this is an extremely important factor to think about when choosing your iron. Typically, irons for general electronics work may have a power rating of between 15-25 watts or so, which is fine for most electronic assembly tasks, printed circuit boards and inter-wiring. It’s important to note that a higher wattage does *not* mean that the iron runs hotter - it simply means that there is more power “in reserve” for coping with larger joints. The maximum electric iron wattage generally available is about 100W, which is OK for DIY electrical repairs but is far too high for general electronics or circuit board use.

A higher wattage iron offers you more flexibility for tackling a wider range of tasks. It has a better “recovery rate” which makes it more “unstoppable” when it comes to heavier-duty work, because it won't be drained of its heat so quickly. So check the power ratings carefully, and anything between 15–40W is fine for general electronics soldering.

Temperature Control - the simplest and cheapest types don't have any form of temperature "regulation". Simply plug them into the mains and switch them on! Thermal regulation is "designed in" (by physics, not electronics!). Sometimes they are described as "thermally balanced" as they have some degree of temperature "matching" – in other words, they warm up as quickly as they lose heat during use, so in a primitive way they maintain roughly a constant temperature. This type of iron is perfectly acceptable for hobby or less demanding professional use. It's essential to use the manufacturer's specified tips (see later) to maintain proper temperature matching, otherwise the iron may not heat up enough – or it may overshoot in temperature.

These unregulated irons form an ideal general-purpose iron for most users, and they cope reasonably well with printed circuit board soldering and general interwiring. However, most of these "miniature" types of iron will be of little use when attempting to solder large joints (e.g. very large terminals or very thick copper wires) because the components being soldered will draw or "sink" heat away from the tip of the iron, cooling it down too much and preventing solder from flowing properly. That's when a higher wattage iron is needed.

A proper **temperature-controlled iron** will be quite a lot more expensive - retailing at say £40 (US$ 60) or more - and will have some form of built-in thermostatic control, to ensure that the temperature of the "bit" (the tip of the iron) is maintained at a fixed level within reasonable limits. This is desirable during frequent use, since it helps to ensure that the temperature will be relatively stable regardless of the workload. Some irons have a bimetallic strip thermostat built into the handle which gives an audible "click" in use, and some may include an adjustable screwdriver control within the handle as well. Others may have electronic controls built in.

^^ An Antex 660TC soldering station with matching iron and bench stand.

More expensive still, **soldering stations** cost from £70 (US$ 115) upwards (the iron may be sold separately, so you can pick the type you prefer), and consist of a complete bench-top control unit into which a special *low-voltage* soldering iron is plugged. Some versions might have a built-in digital temperature readout, and a control knob to vary the setting. The temperature could be boosted for soldering larger joints, for example, or for using higher melting-point solders (e.g. lead-free or silver solder). These are designed for the discerning user, or for continuous production line or professional use. A thermocouple will be built into the tip or shaft, which monitors temperature.

The best soldering stations have irons which are well balanced, with comfort-grip handles which remain cool all day, and silicone-based cables which are burn proof. Antex produces a range of irons with silicone cables specially for education use, to help avoid accidents caused by careless use by students.

Anti-static protection: if you need to solder a lot of static-sensitive parts (e.g. CMOS chips or MOSFET transistors), more advanced and expensive soldering iron stations use static-dissipative materials in their construction to avoid static charges accumulating on the iron itself, which could otherwise damage or “zap” some semiconductors. Such irons are listed as “ESD safe” (electro-static discharge proof). The cheapest irons are not classed as ESD-safe but they still perform well enough in most hobby or educational applications provided you take the usual anti-static precautions when handling these components. The iron would need to be well earthed (grounded) in these circumstances, to carry away any static.



^^ Just part of the range of spare tips or "bits" produced by Antex for their soldering irons. Use only tips intended for a particular iron, to avoid thermal matching problems.

Tips or Bits: it's often useful to have a small selection of manufacturer's bits (soldering iron tips) available with different diameters or shapes, which can be changed depending on the type of work in hand. You will probably find that you become accustomed to, and work best with, one particular shape of tip for the majority of your work. Usually, tips are iron-coated or plated to preserve their life and to maintain good tip "hygiene". Be sure only to use tips that are specifically designed for your iron, otherwise thermal problems may arise. I show separately some typical tips, courtesy of Antex.

^^ Useful accessories from Antex including solder, tips and tip cleaner, desoldering braid and a heatshunt.

Spare parts: it's always reassuring to know that spares are available in the future if required, so if the element blows, you don't need to replace the entire iron. This is especially the case with expensive irons. Check some websites or mail-order catalogues to see whether spare parts are listed. One drawback is that you may need another soldering iron when exchanging a broken heating element!

^^ Gascat 40 gas-powered soldering iron kit by Antex, with spare tips and cleaning sponge.

Gas or electric? So far I've discussed electric soldering irons, but **gas-powered** soldering irons are sold which use butane propellant rather than mains electricity to operate. They have a flint lighter or (better still) a built-in piezo for ignition, and have a catalytic element which, once warmed up, continues to glow hot when gas passes over them. They tend to be big and bulky compared to electric pencil irons.

Field service engineers use gas-powered irons for working on repairs where there may be no power available, or where a joint is tricky to reach with a normal electric iron, so they are really for occasional "on the spot" use, rather than for mainstream construction or assembly work. I use one when I just need to do a quick repair and can't be bothered getting the electric soldering iron going!

Gas irons can have higher power equivalents than electric ones (eg 125 watts or more) but some gas-powered irons are nothing more than miniaturised blowtorches, which may or may not be useful for occasional heavier duty soldering. In the author's experience they can be difficult to use in confined areas. *Extreme care is needed at all times to ensure hot gas emitted from the iron's exhaust port doesn't damage nearby materials, plastics or wiring.* Gas irons can have useful accessories to convert them into e.g. a hot knife for sealing nylon rope, or a hot-air blower for use with heatshrink tubing. Almost every electronics constructor uses an electric-powered iron though.

A **solder gun** is a pistol-shaped iron, typically running at 100W or more, and is completely unsuitable for soldering modern electronic components: they're too hot, heavy and unwieldy for micro-electronics use, nor are they designed for that. Plumbing or DIY, maybe..!

^^ *A heat resistant soldering iron stand with cleaning sponge. (Antex)*

Soldering irons are best used along with a **heat-resistant bench stand**, where the hot iron can be safely stored in between use (photo). It is extremely important that a hot soldering iron is safely “parked” ready for action, and a bench stand is really a necessity. Soldering stations usually have such a feature, otherwise a separate soldering iron stand is essential, ideally one that’s supplied with a tip-cleaning sponge. You can make your own cleaning sponges using *cellulose* sponge only.

^^ *A benchtop fume extractor fan for hobbyist use. A replaceable carbon filter helps remove particles and air is vented out the back.*

Other equipment worth considering includes the use of **fume extractors**, which are compulsory in the industrial workplace. Solder fumes and flux smoke are not known to be toxic but they can cause irritation. A basic fume extractor (photo) consists of a small bench-top fan which draw fumes and irritating smoke away from the operator’s face and filters out some of the smoke particles, before exhausting the air back out through the fan. The carbon-impregnated foam filters are replaceable. Such devices are quite effective and users soon find them indispensable, even though they can be a bit noisy at close range.

Professional fume extraction systems draw the smoke and fumes directly from the work area via a clip-on tube fitted to the soldering iron, then vent the fumes away through a large filter pump. It is definitely worth considering a small bench top unit for regular hobby or occasional professional use, as having decent ventilation can only be a good thing.



^^ *A soldering accessory toolkit by OK Industries, including probes, scrapers and wire brush*

A variety of specialist **hand tools** are available that assist with soldering, and a good supplier's catalogue will offer a range of small brushes, scrapers and cleaning tools in a handy kit, together with the usual types of wire cutters, pliers and so forth, which are necessary for handling components and tidying up as required. Some specialist service aids (aerosols etc.) are also described later.

Now let's look at how to use soldering irons properly, and later on we will describe the techniques for putting things right when a joint somehow goes wrong — and don't worry, even the experts get it wrong sometimes!

How to solder

This guide will show you step by step how to solder successfully and plenty of photographs are provided to help explain the techniques needed.As you read through the guide I'll explain all the stages in more detail, but let's look at the basics first.

First of all, successful soldering requires that the items being soldered together are held with as little movement as possible. So it's best to *secure the work* as needed, so that your accuracy isn't affected should the workpiece move accidentally.

In the case of a printed circuit board, various holding frames are useful especially when densely populated boards are being soldered: the idea is to insert all the parts on one side (a process called "stuffing the board"), hold them in place with a suitable pad to prevent them falling out again, turn the board over and then snip off the wires with cutters before soldering the joints. The frame saves an awful lot of turning the board over and back again, especially with large boards: all the soldering can be performed in one pass.

^^ The ever-popular "Helping Hands" (left) helps support sundry parts, wires etc. during soldering.
A modeller's vice (right) holds parts firmly. A vacuum base fixes it onto smooth surfaces.

Only the more serious constructor will purchase a holding frame, and hobbyists can retain parts in place by improvising in a variety of ways – the ever popular "Helping Hands" stands cost a few pounds and is widely sold. They have adjustable crocodile clips to grip parts, and maybe a magnifying glass or soldering iron stand as well. The cast iron base provides stability. Other parts could be held firm in a modeller's small vice, for example.



^^ *"Helping Hands" uses crocodile clips to grip parts during soldering. Or just place parts flat on the bench.*

When soldering parts onto an ordinary circuit board, components' wires can simply be bent to the correct pitch (distance apart) to fit through the board, insert the part flush down against the board's surface, splay the wires a little so that the component grips the board under spring tension, and then solder it. This technique is universally used in manual **through-hole soldering,** which is explained in full later.

In the author's view - opinions vary – it's generally better to snip off the surplus wires leads first, to make the joint and neighbouring joints more accessible and also to reduce the mechanical shock transmitted to the p.c.b. copper foil. However, in the case of diodes and transistors the author tends to leave the snipping until after the joint has been made, since the excess wire will help to "sink" heat away from the heat-sensitive semiconductor junction.

A special clip-on heatsink is available which also helps stop excess heat from reaching temperature-sensitive semiconductors like these. I've always managed without one but beginners might find them reassuring. Integrated circuits can either be soldered directly into place if you are confident enough, or better, use a dual-in-line socket to prevent heat damage. The chip can then be swapped out at a later date if needed.

Parts which become hot in operation (e.g. some power resistors), should be raised above the board slightly to allow air to circulate. Some components, especially large electrolytic capacitors, may require a mounting clip to be screwed down to the board first, otherwise the part may eventually break off due to vibration. It's a good idea to bolt such components firmly into place before soldering their terminals, in order not to strain the soldered joints or the components when fasteners are tightened.

By securing the workpiece as much as possible to prevent movement, you have a much higher chance of producing good-quality reliable solder joints.

Next steps

Let’s get to grips with actual soldering techniques in more detail. The soldering of electronics components utilises **lead/ tin** or **lead-free solder** and the process is compatible with many non-ferrous metals. You can solder copper, lead, brass, gold plate, silver, nickel, tin and tin plate, zinc and more besides but some metals such as nichrome, galvanised or stainless steel require a highly specialist “flux” (see later) to solder them and aren’t discussed here. Some materials such as beryllium, chromium, magnesium and titanium are non-solderable in any case, according to solder manufacturers Multicore.

In electronics we’re mainly concerned with soldering parts or wires onto printed circuit boards or terminals that are usually already “tinned” with solder or plated, ready for soldering with flux-cored solder. The key factors affecting the quality of a solder joint are:

- **Cleanliness** – dirt or impurities drastically hinder good solder coverage.
- **Temperature** – the right level to enable the solder to flow freely!
- **Time** – apply heat for just the right amount of time!
- **Adequate solder coverage** – enough to form a good joint without touching neighbouring areas.

A little effort spent now in soldering the perfect joint may save you — or somebody else —a considerable amount of time in troubleshooting a defective joint in the future. Let’s discuss the basic principles outlined above in more depth.

Cleanliness and “Tinning” the bit



^^ A clean and shiny soldering tip or “bit” is essential for each and every solder joint you make.

Firstly, and without exception, all parts - including the soldering iron’s tip itself - must be clean and free from contamination. Fact is, solder just will not “take” to dirty parts! Old components or copper board can be impossible to solder because of oxidation that builds up on the surface of the leads. This repels the molten solder and will soon become evident because the solder will “bead” into shiny globules looking like mercury, going everywhere except where you need it. *Dirt and contamination are the enemies of a good quality soldered joint!*

When all the conditions are right for soldering, materials are said to be “wettable” and will accept molten solder, which should flow readily over their surfaces. Hence, it’s **really necessary** to ensure that parts are free from grease, oxidation and other contaminants. Note that in any case, some incompatible materials or surface finishes just cannot be soldered using ordinary lead-free solder, no matter how hard you try – e.g. aluminium parts would require special aluminium solder and fluxes (see later) to be used.



^^ The two tags on this switched potentiometer have blackened with age and oxidation. They must be cleaned before they can be soldered…

In the case of old components that have been stored a long time, where the leads have blackened and oxidised, use a small hand-held file or perhaps fine emery cloth to reveal fresh metal underneath. Stripboard and copper printed circuit board will generally oxidise after a few months, especially where it has tarnished due to fingerprints, so the copper strips could be cleaned using e.g. an abrasive rubber block made for the purpose. Also available is a fibre-glass filament brush (photo), which is used propelling-pencil-like to remove contamination. They're OK for general cleaning but best avoided on fine surfaces (e.g. gold plated switch contacts). These produce tiny particles which can irritate the skin, so avoid accidental contact with any debris.



^^ A glass-fibre filament brush like this is useful for cleaning oxidised parts.



^^ The glass-fibre brush works like a propelling pencil and produces irritating dust.



^^ Cleaning oxidised tags with a glass fibre brush to make them nice and shiny, ready for soldering

Afterwards, a wipe with a rag soaked in cleaning solvent will remove most grease marks and fingerprints. After preparing the surfaces, avoid touching any parts as far as possible.

Another side effect of trying to solder contaminated or incompatible materials is the tendency to apply more heat and “force the solder to take”. As the materials aren’t wettable the molten solder won’t flow where you want it to flow. This can do more harm than good, because it may be impossible to burn off any contaminants anyway, and the component or the printed circuit board may be overheated and damaged in the process. Semiconductors may be harmed by applying excessive heat for more than a few seconds, and extreme heat applied to printed circuit board tracks can cause irreparable damage, because the tracks will be lifted away from the substrate especially on a delicate or badly designed board. You can avoid trouble by ensuring the surfaces to be soldered are clean and wettable to begin with.

Getting Ready

As already explained, cleanliness in soldering is a major factor in obtaining successful results. A soldering iron stand usually has a sponge that is dampened – it wants to be quite damp but not running wet, so squeeze out any excess.

^^ *Dampen the sponge but don't soak it unduly. Note the hole, which gives an edge to wipe tip with.*



^^ *An Antex soldering iron tip. It simply slides onto the iron's heating element. Only the extreme end is wettable and will accept solder: the tip should be kept nice and shiny.*

Soldering iron bits are typically iron-plated to resist wear, then chrome-plated to prevent molten solder being deposited on them, with the extreme tip being "wettable" to work with molten solder. Before using the iron to make a joint, the hot tip must be "tinned" with a few millimetres of solder*: you should always flood a brand new tip with plenty of solder to tin it immediately, when using it for the first time*.



^^ *Tinning the tip ready for use: apply a few millimetres of solder to the hot tip.*

Wipe off excess solder using a damp sponge and it's ready to use. That's why sponges have a hole or well in them – the edge acts as a wiper and the hole catches excess solder.

A useful tip: after tinning the bit, just before using the iron it helps to re-apply a small amount of solder to a clean tip, to improve the thermal contact between the tip and the joint. The molten solder fills the void between the materials and the iron tip, to help transfer heat better so that the solder flows more quickly and easily.



^^ *A tinned tip should look like this, ready to make the next joint.*

It’s sometimes better to tin larger parts as well before making the joint itself, but this is not generally necessary with p.c.b. work. Small tinlets of special paste are available onto which you dab a hot iron - the product cleans and tins the iron ready for use. It’s useful in extreme cases where the bit has some stubborn contamination.

I find special Tip Tinner &Cleaner products to be very useful: gently abrasive in action, they help to clean dirty bits and keep them in good condition. Use them for removing stubborn contaminants, but don’t overdo it.

Multicore
Tip Tinner/Cleaner
TTC1
15g / 0.5oz
Made in Malaysia

^^ Tip Tinner and Cleaner is a useful aid to maintaining a soldering iron bit …

^^ Just press the hot iron onto the solid paste and scrub it around a little. The tip will be cleaned, tinned, and made ready for use.

The move to lead-free solders (see next chapter) has had some effect on the life of soldering iron bits, with increased wear and corrosion noted due to the higher temperatures and the fluxes found in tin-based solders. You can therefore expect bits to wear out over time. Once the iron-plating is damaged due to oxidation or erosion, the bit is fast approaching its end of life. Never use an abrasive or file to sand down a tip: the iron-coating will be damaged and the iron's core exposed, so the tip will soon be made useless due to erosion.

Having prepared the soldering iron tip ready for use, in the next chapter solder and fluxes are discussed.

Solder and Fluxes

In recent years there's been a move towards using more environmentally-friendly materials in electronic products. EU legislation such as *Restriction of the Use of Certain Hazardous Substances in Electrical and Electronic Equipment* (RoHS) aims to reduce toxic heavy metals being sent to landfill. (Look for the RoHS symbol on equipment to indicate compliance.) Due to RoHS compliance, the electronics industry had to change the type of solder it uses in electronic production.



^^ *Electronics solder is supplied in reels or handy dispensers like this.*

Solder comes in various forms including solid bars or pellets for melting in small electric 'solder pots' used for treating the ends of wires with solder. Traditional general-purpose electronics-grade solder is in wire form – starting with so-called "60/40" which contains 60% tin (symbol Sn) and 40% lead (symbol Pb) and is sold in handy dispensers or reels. Although tin-lead solder is now banned in industry, there's nothing to stop the hobbyist from using it but best practice is to use lead-free solder in our work: my advice is to try both, and see which you prefer to work with. "40/60" tin-lead produces lower quality results but is slightly cheaper and perfectly acceptable in hobby circles.

Various diameters of solder wire are marketed. In the UK they're sold in Standard Width Gauge (SWG) sizes, typically as 18SWG (1.2mm) or 22SWG (0.7mm). The latter is fine for almost all hand-soldering of printed circuit boards or general electronics. For larger solder joints (e.g. larger switch or motor terminals), 18SWG solder would be better as more solder can be dispensed more quickly.

Lead-free solder is universally available and contains typically 99.7% pure tin and 0.3% copper (symbol Cu). It needs a higher melting point which makes it slightly more difficult to work with, but standard soldering irons will cope with it well. Antex lead-free solder (Sn 99.25 / Cu 0.75) is a good compromise at 0.8mm diameter and is sold in small dispensers.

Other solders are produced for specialist work, including aluminium solder (Alu-Sol®) and another solder variant used by professionals is Multicore “Smart” wire which contains a small amount of pure silver (symbol Ag). It produces very clean results and is often associated with SMD (surface mount devices), though some engineers also use it for routine p.c.b. work for producing the best possible finish by hand. As “Smart” wire contains lead it is not RoHS compliant.

An interesting variant is **Eutectic** solder, which is 63/37 Tin/Lead. It goes instantly from solid to liquid when melted and is particularly good for hand-soldering. An almost-equivalent lead-free product would be Stannol Flowtin TC or TSC solder.

The low-down on fluxes

When melting solder with a soldering iron, oxides of metal are produced as a result of the high temperatures involved. Unfortunately, these oxides contaminate the metal surfaces being soldered, which interferes with the flow of molten metal and the production of a good quality solder joint.

All electronics-grade solder wire therefore contains an additive called “flux” which helps the molten solder to flow more easily over the joint. It does this by scrubbing away the oxides which arise naturally during heating, and it will often be seen as a pungent brown fluid bubbling away on the joint, accompanied by some fumes.

Those coming into electronics from other industries should note that flux is already contained within “cored” electronics solder and on no account should any acidic flux be applied separately before using the soldering iron. Plumbers, for example, apply flux paste to copper pipes before soldering them, but electronics-grade solder wire already contains a flux and extra flux is almost never needed. Electronics is no place for acid fluxes!



^^ *A close-up of electronics-grade multi-cored solder. Five cores of rosin flux can be seen running through it.*

For almost all electronic hand assembly, solder wire containing “Rosin flux” is used. Cores of flux run through the solder wire like letters running through seaside candy, and they prevent the hot area from being contaminated by oxides, otherwise solder would never flow properly and the result would be an incomplete and unreliable joint.

Flux dispensers and Colophony

Flux dispenser pens are sold that allows special liquid flux to be applied separately onto a work area. These might be handy for difficult or challenging jobs to help solder to flow better: adding more flux this way won't do any harm and may help a solder joint to be made more quickly and reliably. In my hobby electronics, there's hardly ever been a time when I felt the need to apply extra flux but it's useful for some very tricky or demanding jobs.



^^ *For more demanding work, a flux dispenser pen allows additional flux to be applied*

For example I've used specialist Chemtronics flux dispenser pens on tricky, extra-large solder joints involving very thick wires for lead-acid battery connections where I really struggled to make the solder flow properly. You might also use them in micro-electronic surface-mount work. The extra flux can only help, but for the rest of the time rosin-flux core solder wire contains sufficient flux and that's all that you'll need.

^^ *Colophony or rosin flux is available in small tinlets if you want to prepare your own liquid flux.*

One thing that many seasoned electronics enthusiasts will recognise is the distinctive smell of rosin flux: its intense woody pine smell is not unpleasant, and flux fumes themselves are not known to be harmful but solder smoke can be an irritant, especially if you suffer from asthma or other respiratory conditions. (I dealt with solder fume extraction earlier when soldering irons were outlined.)

Rosin flux is also known as **Colophony.** It's an amber resin that's glassy and brittle like sugar candy, distilled from the resins of conifers (mainly pine trees) and it's worth knowing about. For electronics use, Colophony is available in individual tinlets of solid resin (e.g. *Kolophonium* in 20g tins by Donau Elektronik GmbH, sold by Westfalia or Conrad).

As an aside, the resins of various trees are used in incense burners: placing a few fragments on a charcoal burner produces intense delicious fragrances of pine, frankincense or forest but you still wouldn't want to inhale the smoke or fumes directly.

Solids of Colophony can be dissolved to make a semi-liquid flux, for dipping or applying manually prior to soldering. To make your own rosin flux from solids of Colophony, chip off some fragments and crush them into a small tinfoil dish, then apply some isoproponal alcohol (start with 2 parts solvent to 1 part Colophony) and let it dissolve over about 20-30 minutes or more.

^^ Chip off some solids of colophony and put them in a small tin foil dish

^^ Add e.g. x 2 volume isopropanol alcohol and allow the solids to dissolve. Experiment as needed.

^^ *The resulting flux can be very sticky so handle with care and do not spill.*

In this form it can be applied directly with a brush or dropper to areas prior to soldering. In an open dish, after a day or two the solvent will mostly have evaporated to leave an extremely sticky resin that should be handled carefully: it's no co-incidence that Colophony is also used in adhesives and varnishes, and different grades of Colophony resins are used to treat violin or double-bass bows to add friction to bow hairs! Try experimenting with different ratios of solvent and making some up and storing it in an old nail varnish bottle with brush, or generally do what works for you.

Unused Colophony crystals can be reformed into their storage tinlet by warming carefully with a hot air gun, but don't overdo it. You can also use flux cleaners or PCB solvent cleaners if you want to remove traces of excess rosin flux after soldering: these are left behind as a brown deposit and are otherwise harmless.

The subject of using your soldering iron to raise the temperature of the materials is discussed next.

Temperature flow

This aspect takes a bit more understanding, but with practice you'll soon understand how temperature flows within a workpiece being soldered and how you have to harness it properly. After ensuring all parts are clean and the soldering iron is ready to go, the next step to successful soldering requires that the **temperature** of **all** the parts is raised to roughly the same level, before solder can be applied.

Imagine the most basic task of soldering a simple resistor onto a printed circuit board: the copper p.c.b. and the resistor lead should both be heated *together* so that the solder will flow readily over the joint. Later I'll show the precise stages step by step.

A beginner will often mistakenly just heat one part of the joint (e.g. a resistor's wire protruding through a printed circuit board) and hope that the resultant "blob" of solder will be enough to tack everything together. That's completely wrong, because the remaining metal in the joint is cold when molten solder is flooded on to it. The joint will be weak, incomplete or unreliable. Flux will not have flowed properly either, so the joint could be contaminated internally.

Another beginner's mistake is to use a soldering iron to carry blobs of molten solder over to the joint, as if to daub solder over it. The secret of success is to control the iron accurately and apply the hot tip onto the workpiece so that it's in contact with *all the parts*. Within a fraction of a second, heat will conduct from the iron and raise the temperature of the entire joint, after which solder can be melted over it. Remove the iron and let the joint cool naturally. It takes some practice with your chosen soldering iron tip to obtain the best heating action, making sure the tip is clean and tinned properly to begin with.



^^ Set a typical temperature of 330-350 ºC (626-662 ºF) or more, if you have a soldering station.

The melting point of traditional tin-lead solders is about 190ºC (374ºF) but lead-free tin-based solders require higher temperatures, having melting points of typically 201-227 ºC. As Antex reminds us, the melting point is *not* the temperature of the soldering iron tip: instead you should set a temperature that ensures the solder melts *instantly* onto the tip. Fixed-temperature soldering irons have no adjustability but they'll cope just fine with either type of solder. A soldering station usually has a variable control that gives more control in different circumstances. In practice the iron tip temperature should be set for typically 330-350 ºC (626-662 ºF) or maybe a little more if using lead-free solder.

Now is the time…

The next diagram shows what would happen if you applied a hot soldering iron to an imaginary metal block. In step (1) heat travels out of the iron into the cold metal block, which starts to warm up starting at the edges. Gradually (2), the whole metal block's temperature rises until the middle of the block finally rises in temperature as well. In effect heat is now travelling back "towards" the iron tip, until finally (3) the whole block is at the same temperature as the iron. At this point solder could now be applied.



^^ How metal in the joint actually "sinks" heat away from the tip to begin with. Then heat moves back towards the tip until the solder's melting point is finally reached.

You'll notice this effect as a time delay when soldering any joint. The "working area" of the iron's tip gets **cooled** to begin with, because the metal in the rest of the joint is sinking heat away from where it's most wanted. Only after the whole joint has risen in temperature can solder be melted onto it.



^^ *Soldering a small p.c.b. joint*

With experience, you’ll get a feel for how long it takes before you can apply solder. The more metal that is present in the joint, the longer period that heat must be applied for. A small p.c.b. joint takes well under one second to complete. A large metal terminal could take quite a few seconds or more to heat up. As I explained earlier, higher power (wattage) irons cope better with larger workpieces because they recover more quickly and are more “unstoppable”, making it easier for them to heat larger workpieces without cooling down so much.

If you apply solder too early, it won’t melt properly and the result will be a grey, crystalline joint caused by the solder’s melting point temperature not being reached and the flux not having flowed properly. Semiconductors must be soldered as rapidly as possible as they are heat-sensitive, but they’re a lot more robust than they used to be.



^^ A clip-on Antex heat shunt fitted to a transistor leg, helps prevent thermal damage due to overheating when soldering it in place. Less essential these days, but beginners find them re-assuring.

Until they have gained some practice, novices sometimes buy a small clip-on heat-shunt (photo) which resembles a pair of aluminium tweezers. In the example of, say, a transistor, the shunt is attached to one of the leads near to the transistor's body. Any excess heat then diverts up the heat shunt instead of into the transistor junction, thereby avoiding the risk of thermal damage. Applying far too much heat may destroy the part or damage the p.c.b. foil which may lift away from the board.

In due course constructors learns to judge how much solder should be applied to any particular joint. An ideal p.c.b. joint is very slightly concave in shape. If not enough solder is used, the result may be an incomplete joint which may cause an intermittent fault later on. An excess of solder – shaped like a ball bearing - is an unnecessary waste and in extreme cases may cause short circuits, especially on densely-populated boards. There is no need to add more solder "for luck". Professionally-produced p.c.b.s have a green *solder resist* coating which helps to ensure that solder does not stray onto adjacent pads. As a finishing touch, I usually spray the solder-side of a circuitboard with aerosol spray lacquer afterwards. It keeps the solder joints nice and shiny and helps prevent corrosion.

Some components can create hazards during a soldering operation:

Coin cells and button batteries are commonly used as power, clock or memory backups. If heated excessively they can explode without warning due to the build-up of internal pressure. Spot-welders are used in industry to connect tags to them, but if you need to solder wires to such a cell then it should be done as quickly as possible.

Some **memory back-up capacitors** or **electrolytic capacitors** remain energised for a while even when the circuit is powered down. Molten solder is a perfect electrical conductor and in some cases the component’s contacts could be shorted during the soldering (or desoldering) operation. If molten solder shorts it out then the arcing may cause globules of solder to be spattered outwards without warning, potentially risking eyesight damage.

Always ensure that powered components are electrically inert and discharged before soldering. Cells, batteries and battery packs should not be accidentally shorted during the soldering process, to avoid arcing and solder spatter. Note that electrolytic capacitors can also explode after a while if reverse-connected, so observe polarity closely.

Let’s now consider the practical stages of soldering components and wires successfully.

Soldering Step by Step

Earlier I explained the individual factors that affect the quality of a solder joint. These are:

- **Cleanliness** – dirt or impurities drastically hinder good solder coverage.
- **Temperature** – the right level to enable the solder to flow freely!
- **Time** – apply heat for just the right amount of time!
- **Adequate solder coverage** – enough to form a good joint without touching neighbouring areas.

These rules apply whether soldering a p.c.b. or performing other tasks such as interwiring (hooking everything together with connecting wire).

We'll now summarise the stages of making a typical solder joint – soldering components onto a printed circuit board (through-hole soldering). Most people insert components into the circuit board and simply splay the wires out to hold them in place under spring tension. I find it best to snip excess wire leads off at this stage, to improve accessibility.

- All parts must be bright, clean and free from dirt and grease.
- Try to secure the work firmly to stop parts moving around.
- "Tin" the soldering iron tip with a small amount of solder. Do this immediately, with new tips being used for the first time.
- Wipe the tip of the hot soldering iron on a damp cellulose sponge to remove excess solder or contamination.
- Many people then add a tiny amount of fresh solder to the cleansed tip just before using it.
- Heat all parts of the joint with the iron typically for under a second or so, until it's heated throughout.
- While heating, then apply sufficient rosin-core solder to form an adequately-covered joint.
- It only takes a second or two at most, to solder the average p.c.b. joint this way.
- Do not move parts until the solder has cooled.
- Remove and return the iron safely to its stand.

This special photo sequence illustrates these stages. It's best to start with the smallest, fiddliest parts first when soldering a blank p.c.b., because that's when you've got the most access on the board. Accessibility will be reduced as more components are added, so we'll start with a simple wire link on a professionally designed p.c.b.



AGENTA DESIGNS 01283 565435
DLOG1
XTAL1

^^ A typical professional blank p.c.b. – silk-screen printing shows what goes where. The underside has been treated with a green solder resist coating, and the solder pads are ready-tinned to help with soldering.



MAGENTA DESIGNS 01283 565435

^^ Preparing a wire link for soldering – cut off some tinned copper wire and bend the ends to fit the p.c.b. correctly. Round-nose pliers (shown) are perfect for this, but ordinary electronics or "radio" pliers will do.



^^ Wires are prodded through the holes in the board, then turn it upside down to view the solder side. You can then "spring" or splay the ends apart slightly, so they are held in place while you solder them.



^^ Wipe the hot soldering iron on the damp sponge to clean the tip. Do this periodically when contamination, flux deposits etc. build up on the iron to keep the tip nice and shiny. Tip Tinner & Cleaner helps too.

ANTEX
660 TC

^^ It often helps to dab a tiny amount of solder wire onto the tip, to improve heat transfer.



^^ Then apply the soldering iron to heat both the solder "pad" and the wire end at the same time (say <1 second). Apply a few millimetres only, of solder. Then remove the soldering iron immediately and allow the joint to cool down by itself. The green solder-resist coating ensures solder doesn't flow onto neighbouring pads.



^^ These "end cutters" can then be used to snip off excess wire after soldering….



^^ … but ordinary electronics "side cutters" are fine for trimming or snipping wires.



^^ The ideal solder joint should be smooth and slightly concave, quite shiny, not dull or crystalline-looking nor ball-bearing shaped.

Try to get consistent results in your soldering, but don't worry too much about the lack of uniformity – this is soldering by hand after all, not by precision machinery, and some slight variation is OK provided the solder coverage is good and the soldering is generally clean and effective. You'll improve with practice, that's for sure!



^^ A large i.c. socket can be added next…



^^ Go along the rows of pins and solder them one at a time. See how simple it is! Heat both the solder pad and pin with the iron, and dab on a little solder wire to ensure full coverage. Ensure the socket is flush against the board.



^^ As hardly any metal is involved each pin should take well under a second to solder at most.



^^ Continue until the i.c. socket is soldered.

Once the smallest parts are soldered into place, you can continue to solder the remaining components. It's easiest to handle the smallest so-called "discrete" parts first while you still have plenty of room on the board. I usually solder resistors and capacitors next. The principle of soldering them is just the same as a simple wire link: insert them from above till they are flush on the board, then splay their wires a little to hold them in place, and preferably snip off at least some of the wire to give you more access.



^^ Continue by inserting "discrete" components from above, splay their wires out

underneath to secure them in place, then snip and solder the joints exactly as before. Some parts like this blue electrolytic capacitor are polarity sensitive (note the – sign), and must be inserted the right way round. Same is true of every semiconductor.



^^ This row of ¼ watt resistors was next. I like to show the colour codes all the same way round, with gold or silver (tolerance bands) on the right for consistency.



^^ This transistor was next. Solder it quickly to avoid damage, and observe polarity correctly, so it is the right way round on the p.c.b. The heatshunt is optional.



^^ Unusually, this toggle switch fitted directly onto the board as well which saved wiring it up. Neat idea!


ANTEX
LEAD FREE SOLDER

^^ *As there is comparatively more metal to heat up, it'll take longer to solder the switch terminals, and you'll need more solder as well. Thicker gauge solder is useful at such times. Allow say 2-3 seconds to solder each terminal.*

Don't forget to clean the soldering iron tip on its damp sponge every now and then, to ensure the bit is kept clean and shiny. Later on I'll show you how to correct any problems by desoldering using various techniques. Next, we'll move on from printed circuit board "through-hole" soldering and look at how to handle wires and leads.

Interwiring – get hooked up!

With practice, through-hole soldering of p.c.b.s will become second nature. There’s no substitute for tackling some soldering jobs though, particularly trying a simple kit based on a quality p.c.b. which will boost your confidence enormously.

Most electronic devices need connecting up to external components such as battery packs, speakers, l.e.d.s or switches. Usually, multi-stranded connecting wire is used to connect circuit boards and external parts together. Unlike single solid-core wire, *multi-stranded wire* is flexible and vibration-resistant. Hobbyists mainly use 7/0.2mm wire (7 strands, each 0.2mm diameter) for low-voltage hook-ups although much Chinese equipment uses much thinner wires than this. So let’s look at some aspects of soldering this type of wire.

In a separate photo sequence I show how a potentiometer (a panel-mounted variable resistor) and a light-emitting diode (l.e.d.) are connected using multi-stranded wire. The same principles of soldering apply to most other components including panel-mounted switches, loudspeakers, buzzers, audio sockets and more.

Components usually have terminals or “tags” to which wires can be soldered. Start by ensuring the component’s tags are clean: otherwise solder will not wet properly and the joint will be impossible to solder, so all contamination must be removed. This is especially true of parts that have been in storage a long time. The connections often oxidise or blacken, so clean the solder tags with e.g. an abrasive glass-fibre brush, or a needle file or abrasive paper. Using a glass fibre brush was shown earlier in “Cleanliness and Tinning the Bit”.



^^ How not to strip insulation off wire: some of the cores have also been cut – avoid doing this!



^^ Gripping a wire end in a "Helping Hand" croc clip can help with soldering.

After stripping a short length of insulation from the connecting wire, there are two ways to solder it to a component's solder tag. The first way is to "*tin" the stripped wire end to solidify it* - just heat it with the iron and melt a little solder on it, and let it cool. Poke the wire end through the solder tag, apply the hot iron to both parts and solder them together using a few millimetres of solder.

Although the assembly doesn't hold itself together so well during soldering (consider a Helping Hands jig if needed) this is quicker and easier to make and also easy to desolder again, and is perfectly adequate for most joints of this kind. The majority of commercial wire joints seem to be made this way.



^^ Apply a hot iron and solder, in order to "tin" the wire ends. This makes them into a solid.



^^ Then feed the tinned wire through the hole in the solder tag. Crop the wire with cutters if needed…



^^ … and apply the iron to heat the joint. As there's quite a lot of metal to heat, allow several seconds to heat it up and then simply solder the wire and solder tag together with a dab of solder wire.



^^ The result is a perfectly satisfactory solder joint.

The second way is to loop the **untinned** wire through the tag a few turns and then solder it. This secures the wire during soldering, but it's messier to desolder if things go wrong (see later):



^^ *The centre wire (potentiometer wiper terminal) has been wrapped around to secure it before soldering.*



^^ *Solder the joint in just the same way – heat it up and dab on some solder wire.*

Much electronic equipment is connected or inter-wired this way and soldering everything together is a key stage in assembling any electronic project. I'll explain some refinements you can try, later.

Wire joints

Soldering isn't always the best solution to some problems, for reasons that I explain in the next section called Fatigue and Breakage. However you can solder wires together to join them simply and cheaply, and next I show a classic wire joint of this kind, sometimes called a **Western Union** joint.



^^ *Soldering a Western Union wire joint.*

Strip the ends from each wire using wire strippers, and try not to cut any of the stranded cores or this will create a weakness. (Stray strands of wire can also be a hazard.) Then twist the wires securely together several times, ideally four or five. Apply a soldering iron to the exposed joint and dab on some solder until it flows fully over the joint, then remove the iron and allow the joint to cool.

The wire's plastic insulation may shrink back a little due to the heat, but try not to overheat it excessively. If you have the resources you can finish off by insulating the joint with some heatshrink tubing (slide it over a wire before you make the solder joint!). Otherwise use ordinary PVC tubing or insulation tape if you have any.

A solder tag can be soldered easily enough, and it's probably best to feed a stripped wire end through the tag and twist it over several times before soldering it, so it's held together when soldering.



^^ A solder tag is soldered by wrapping a stripped wire end through the hole and round again, to secure it.



^^ Apply plenty of heat and solder for a few seconds.



^^ *The completed solder tag*

The next sequence show how the same basic principles of soldering wires are used to connect up a device such as a panel-mounting l.e.d.. A series resistor can be wrapped around and soldered directly to one of the l.e.d. solid wires, and then two multi-stranded connecting leads are soldered to the l.e.d. and resistor. It's best to use heatshrink tubing or PVC sleeve to insulate the solder joints and prevent short circuits afterwards.



^^ *Multi-stranded wires can be soldered to the solid leads of an l.e.d.: insulate them afterwards. Different coloured wires identify the polarity of anode and cathode.*



^^ *PVC sleeving or heatshrink is needed to prevent short circuits.*



^^ A commercial l.e.d.– the series resistor can be made out in the sleeving.

Wires can also be soldered directly to printed circuit boards by stripping and tinning the ends, provided they fit through the holes in the p.c.b. It's a very common and cheap way of hooking up a board using "flying leads" and you'll see this all the time in consumer electronic equipment. For convenience so-called "solder pins" can be used, onto which flying leads may be soldered from the component-side instead.



^^ A set of l.e.d.s connecting wires, stripped, tinned and ready to be soldered to the p.c.b.



^^ Solder the two "flying leads" to the copper pads in the usual way. Hopefully the holes are big enough for the wires!



^^ Connecting an l.e.d. to a circuit board with flying leads.

Wires can also be attached to the underside (solder-side) of circuit boards, tacking them onto existing solder joints by re-melting them and absorbing the tinned wire end into it ("reflow soldering" – see later). This is a cheap and cheerful, semi-reliable way of rigging wires to a circuit board, and it's used all the time in imported consumer electronics.

Tidying up

I'll leave it to readers to decide whether they should cut off excess wire before or after soldering. After the soldering is complete, I prefer to tidy up the joint by snipping any excess wire from the joint using a pair of "end cutters" shown earlier. These expensive hand tools have specially angled blades that snip the joint neatly down to the top of the solder joint. Ordinary side cutters will do fine.

It's worth taking time out to inspect the work closely, looking for any missing solder joints, whiskers of solder or swarf shorting out any solder pads, and all such potential problem areas should be dealt with prior to testing the board. Faultfinding goes beyond the scope of this guide, but it's true to say that almost always, any problems noticed after powering up the circuit are due to soldering faults or wrong components being used.

Reflow technique

Another technique often used is “reflow” soldering. This is used to “tack” devices or wires together, especially if very small, sensitive or fiddly parts are involved. There might be no room to make a “proper” sturdy joint, or it might just not be necessary to have any mechanical strength in the joint, especially if tiny parts are used.

As an example, imagine a small temperature sensor (I used a transistor) for use in a thermometer project. It could be quite tricky to solder flying leads onto the sensor’s leadouts, so a good approach is to tin both the flying leads and the sensor’s leads, and then simply touch them together and re-melt the solder with the iron. There’s no need to add any more solder, because the solder that’s already there will re-melt and the joint will be made. Sometimes this is called a butt joint.



^^ *The leads of this sensor (transistor) have been tinned, ready for flying leads to be tacked onto them with a reflow method. A Helping Hands jig might help!*



^^ The three flying leads stripped, tinned and ready to be reflow-soldered onto the device.



^^ To reflow solder them, simply hold the two leads together while re-melting the solder with the iron.



^^ Remove the iron and let the solder cool. The wire is tacked on.



^^ Repeat for the other leads. They just need insulating with sleeving, then job done!

Depicted next is a typical "tag strip", an insulated panel with metal solder tags used for making sundry connections. (Entire TVs and radios used to be hand-built with them, in the early-mid 20th Century!) The principles of soldering are exactly the same, but more time is needed when applying the soldering iron because more metal is present, which needs more heat. You'll need more solder for bigger joints like these, so larger diameter solder makes a quicker job of it. Consider adding more flux (see earlier) to see if it helps.



^^ Wrap wires through the terminals and arrange everything neatly, then solder as normal.



^^ Don't be afraid to apply more heat with larger assemblies like these: they contain more metal than, say, an ordinary p.c.b so allow more time for the solder to flow over

everything properly.

Fatigue & Breakage

Earlier I explained how multi-stranded hookup wire is flexible, which also makes it vibration proof – that's why a car's electrics are full of multi-stranded wiring, and test equipment probes use ultra-flexible multi-stranded wire for the same reason. Solid-core wire can be bent and will stay in shape (called "plate wiring") but if it's repeatedly bent or vibrated then it may eventually break somewhere due to fatigue.

The same is true of wires that have been soldered or tinned. No longer is the wire 100% multi-cored and flexible – instead it's been turned into a *single core wire* at the point where it's been soldered. This is potentially a weak spot and could eventually fracture due to fatigue, if subjected to continued vibration (e.g. in a car engine bay or in motorised equipment).

In a lot of equipment problems can be avoided by adding *strain reliefs* of some sort, to stop the wire being flexed where it's been soldered. Heatshrink tubing, or a dab of hot-melt glue, are ways of taking the pressure off the joint and ensuring soldered wires won't snap off due to vibration.

One of the reasons that higher-quality equipment and cars etc. use crimp terminals and connectors is that crimped (as opposed to soldered) connections retain all the flexibility of multi-core stranded wire from end to end, avoiding problems of wires breaking off. A *ferrule* is a very neat way of tidying wire ends and preventing stray strands of wire doing damage. Ferrules can be used to connect wires into screw terminal blocks etc. Simply clamp the terminal block down onto it and the screw will grip the ferrule.



^^ Instead of soldering them, wires can be terminated with ferrules prior to fitting to e.g. screw terminal blocks. This makes them vibration-proof and also avoids any problem of stray wires poking out.

Faults & Desoldering techniques

By putting into practice the guidelines in my *Basic Soldering Guide* practice, there's no reason at all why you should not obtain perfect results and eliminate any potential problems. Hopefully the information gives you plenty of guidance to tackle various soldering projects with confidence. There's no substitute for getting some hands-on experience though, so I'd repeat the advice to try assembling a simple high quality electronic kit or two, such as those produced by Velleman and see how you get on. Powering up your first project successfully is a great thrill as every electronics hobbyist knows.

^^ *Popular desoldering products, a pump and various widths of desolder braid.*

Let's now look at reversing the soldering procedure – what to do if things go wrong, or maybe you have to repair a circuit by replacing a faulty component.

A solder joint which is badly made is likely to be electrically "noisy", unreliable and will probably worsen over time. Expansion and contraction of the joint due to heating and cooling can also throw up intermittent problems later down the line. The joint may look OK but underneath it may have a poor electrical connection, or could work initially and then cause the equipment to fail at a later date! These intermittent problems can be maddening to fix. TV repair technicians have an uncanny ability to go straight to a faulty solder joint because they see the same problem all the time, especially on equipment that has a "reputation".



^^ These dry or grey/ gray joints were caused by dirty parts, poor heating and inadequate solder coverage

A solder joint that's poorly formed is called a "dry joint" or "cold joint" or a "grey/ gray" joint. Usually it results from inadequate heating, dirt or grease preventing the solder from melting onto the parts properly, and is often noticeable because the solder tends not to wet the surface properly. Instead it forms beads or globules. Alternatively, if it seems to take a very long time for the solder to wet the joint, that's another sign of contamination and that the joint may be a dry one, or the material is incompatible anyway. A matt, crystalline appearance instead of a shiny joint points to inadequate heating: the solder cooled down far too quickly and didn't flow properly.

Whether you want to replace a faulty component or fix a dry or poor-quality solder joint, it's usually necessary to remove the troublesome solder and then re-solder it afresh. Naturally, there are tools and techniques that make the job easy. It's very bad practice to simply re-melt the joint and then lash out with the board, whiplash style, hoping that the molten solder will be flicked off the board.

The usual way of removing solder from a joint is to use a *desoldering pump*. These work like a small spring-loaded bicycle pump, only in reverse! A plunger is pressed down until it locks into position. It's released by pressing a button which sucks air back through a pointed nozzle, carrying any molten solder with it. It may take one or two attempts to clean up a joint this way, but a small desoldering pump is an invaluable tool especially for p.c.b. work and they are widely available now.

^^ *A hobby desoldering pump primed for use*

Desoldering pumps often have a heatproof P.T.F.E. nozzle which may need replacing occasionally. Each time the button is pressed, a plunger clears the nozzle but sometimes solder particles and swarf will be ejected in the process; when you prime the pump, point the nozzle into a small pot or old aerosol top to catch any debris. Remove the spout and clean out the pump from time to time.



^^ *Suck up molten solder using a desoldering pump*

With very stubborn joints where the last traces of molten solder just can't be shifted, it sometimes helps to actually *add* more solder and then desolder the whole lot again with a pump.

Desolder Braid

An alternative to a pump is to use *desoldering braid* which arrives in small dispenser reels. It’s a flux-impregnated fine copper braid which is applied to the molten joint, and the solder is then drawn up into the wick by capillary action. It’s remarkably effective and for certain tasks, it can be more thorough than a pump. I recommend that a small reel is bought (start with 1.5mm width) for the toolbox, to tackle larger or difficult joints which would take several attempts with a pump.



^^ Desolder braid is also handy and can sometimes be more effective than a desolder pump. It comes in various widths to suit the scale of work being tackled.

To use desolder braid, press the end of the braid down onto the joint using the tip of an iron, and let the solder melt underneath: the braid will then absorb the solder. The braid becomes hot so beware of burns. Once the solder’s solidified on the braid, cut it off and discard.


0128 3 S
DLOG1

^^ Desolder braid can also be used to remove excess solder, e.g. two i.c. pins shorted together.


0128 3 5
DLOG1

^^ Press some desolder braid over the joint, then melt it with an iron to draw molten solder up the braid.



^^ *Remove the braid immediately and don't drag "whiskers" of molten solder around. The excess solder is absorbed by the braid, which is snipped off ready for the next job.*

Be aware that you can damage a printed circuit board accidentally when removing the desolder braid if it's not removed *quickly enough*. The solder will soon solidify, which effectively solders the braid to the printed circuit board! A careless tug may yank copper tracks or pads away from the board, stuck to the braid. You can also drag solder "whiskers" onto neighbouring pads unless the braid is removed cleanly. Why not practice using desolder braid with an old circuit board?

Whichever desoldering method you use, care is needed to ensure that the boards and parts are not damaged by excessive heat. It's not that difficult to apply so much heat when desoldering that the adhesive holding the copper foil tracks on the p.c.b. eventually fails, causing the copper track to lift away – everyone's worst nightmare.



^^ *Typical copper track damage (centre) caused by overheating during soldering or desoldering. The track has lifted off, but you can try repairing it by adding extra wiring or SuperGlue it if the track isn't broken.*

If this should ever happen, remove the iron immediately and permit the area to cool (a freezer aerosol is valuable at such times). If you're lucky, you can maybe repair the lifted track using a droplet or two of Super Glue, or add "jumper wires" to bypass the damage.



^^ *A Freezer aerosol can give rapid cooling where excess heat has been applied* *during soldering. Also used in circuit faultfinding to identify overheating parts.*

You now know everything you need to know about making the ideal solder joint, and desoldering it in case you need to make a repair. Just to remind you, a Quick Summary guide follows.

Quick Summary Guide

To round off the Basic Soldering Guide, let’s summarise how to make the perfect solder joint.

- Ensure materials to be soldered are compatible with tin/ lead or lead-free solder.
- All parts must be clean and free from dirt and contaminants.
- Try to secure the workpiece firmly during soldering.
- Brand new soldering iron tips must be flooded with solder immediately, the first time they are used.
- Wipe the tip of the hot soldering iron on a damp cellulose sponge at frequent intervals. Then “tin” the iron tip by applying a small amount of solder.
- Aim to heat all parts of the joint with the iron for under a second or so, to bring them up to the same temperature.
- Continue heating and apply sufficient rosin-core tin/ lead or lead-free solder to form a complete joint.
- It only takes a second at most, to solder the average p.c.b. joint. It should be smooth and shiny, and through-hole joints should be slightly convex in shape.
- Remove the iron and return it safely to its stand.
- Do not move parts until the solder has cooled.
- Tin the soldering iron tip and clean it well, when switching it off, ready for next time.
- Consider using e.g. electronics flux dispenser pens or Colophony (rosin) to help with difficult joints.

Sometimes solder joints don’t go quite to plan, and sooner or later everyone is faced with the need to problem-solve or troubleshoot, so a simple Troubleshooting Guide follows next.

Troubleshooting Guide

This troubleshooting guide may help fix common problems encountered with troublesome solder joints.

SYMPTOMS	LIKELY CAUSES	REMEDY
Solder won’t “take” (wet) and won’t flow properly over the joint — molten solder forms beads or “ball bearings” instead of flowing properly.	Grease or contaminants present; Material may not be suitable for soldering with standard lead/tin or lead-free solder, e.g chromium.	Treat contaminated parts with abrasive cleaners etc. as required to expose base metal. Some metals can’t be soldered with electronics-grade solder.
Solder doesn’t melt or flow very well — the joint is crystalline or grainy-looking - a grey or dry joint.	Joint has been moved before being allowed to cool naturally, or: Joint was not heated adequately. Too large a joint – too much metal present – and/ or the soldering iron temperature or power rating are too low.	Desolder and remake. Apply heat for a longer period, or use a higher power soldering iron, or check the temperature setting and raise it if possible.
Solder joint forms a “spike” and applying the iron again makes it even worse!	Probably overheated, burning away the flux. The iron, when removed, would cause the solder to stand up in a spike.	It is usually best to desolder and remake the joint freshly again.
The copper foil of my p.c.b. has lifted off the circuit board!	Excessive use of heat has damaged the adhesive. Provided the track hasn’t broken, it may be repairable.	You can sometimes repair it with Super Glue, or re-wire the board with jumper wires.
Brown varnish-like deposits are left behind after I finish soldering.	These are the remains of rosin flux and are nothing to worry about.	It can be removed with PCB cleaners or some solvents, if you want to tidy up the board and inspect your work.

Possible Hazards and simple First Aid

It’s extremely rare that soldering iron operators receive any burns or other injuries from the use of hot soldering irons. Soldering is perfectly safe provided that common sense precautions are taken during the soldering operation. Here are some of them:

- Components are very hot after soldering, so let them cool before handling them to avoid skin burns.
- Beware of splashes of molten solder caused by careless handling of a hot soldering iron.
- Beware of energised components (capacitors, batteries etc.) being shorted by molten solder and ejecting solder splashes due to arcing.
- Always park a hot iron safely on a stand in between use — never hang it vertically next to the bench.
- Keep a hot soldering iron away from its mains cable (silicone cables reduce the risk of accidental damage).
- Beware of wire offcuts flying off (danger to eyesight) when snipping wires to length before or after soldering.
- Avoid inhalation of solder and flux fumes as this can irritate the respiratory tracts, especially in sensitive cases (e.g. asthma).

Should you receive a more serious skin burn which requires attention, then:

- **Cool the affected area immediately.** Use plenty of cooler running water – but avoid ice cubes etc. as they can cause nerve damage after a time or inhibit the flow of blood to the affected area.
- Remove any **objects** which may be constrictive, before any swelling starts (rings, watches, bracelets).
- Do not prick blisters nor apply ointments, salves or lotions at this stage.
- Local pain relief for small burns can be obtained by spraying *Burneze* aerosol onto unbroken skin.
- Seek medical attention for more serious burns.

Eyesight problems are exceptionally rare, e.g. pieces of wire offcuts or solder splashes lodging in the eye area, and should be treated by a qualified first-aider or A&E. The best you can do is bathe the affected area with e.g. a first-aid eyewash bottle or fresh water. Then seek professional medical help straight away.

Useful resources

Details of the Antex range of soldering equipment, solder tips and spare parts can be obtained from www.antex.co.uk. UK and international distributors are also listed on the Antex (Electronics) web site.

If you're interested in hobby electronics then why not try **EPE Magazine**, the No. 1 UK magazine for hobby electronics enthusiasts, students, trainees and technicians around the world. You can buy a printed edition from newsstands, download a PDF version (for Windows) or try a tablet/ smartphone version from Pocketmags. More details at www.epemag.com

You can learn more about the writer at his website http://www.alanwinstanley.com/

Some mail order suppliers of soldering equipment and electronic parts include:

- ESR Electronic Components Ltd. (soldering equipment, Velleman kits)
- Bowood Electronics (Antex irons and spares, electronic parts)
- Rapid Electronics (components, tools, equipment)
- Cricklewood Electronics (CCTV, Antex soldering irons and spares, components)
- Maplin Electronics (UK electronics retailer and mail order)
- Farnell Electronic Components (major UK industrial supplier)
- RS (UK electronics industrial supplier)
- Brewsters Ltd (soldering equipment mail order specialists)
- Velleman UK (electronic kits)
- Quasar Electronics (Velleman kit mail order retailers)
- Kemo Kits (Germany, trade only)
- Hobbytronics (UK hobby mail order supplier)
- Multicore Solders (now a Henkel brand)

These links were correct at the time of going to press, July 2013.

Acknowledgements

Antex (Electronics) UK generously provided samples of their ever popular British-made soldering equipment, materials and accessories for use in the Basic Soldering Guide. When starting out as a 1970's teenage schoolboy electronics hobbyist, I and my trusty Antex soldering iron shared many adventures in electronics together, and it has been a pleasure to use the latest Antex soldering irons throughout this guide.

Also I would like to thank Brian Brooks of Magenta Electronics Ltd. (www.magenta2000.co.uk) for supplying me with a variety of their professionally-designed printed circuit boards and a range of components which were the subjects used in the photographs.

Photography

All photographs were taken by the author using Sony Alpha DSLRs and 50mm macro lens with extension tubes, and a Sony macro flash. High-resolution versions of these and more technical photos are available for commercial or educational royalty-free use. Please contact me with any enquiries.

Conclusion

I really hope the Basic Soldering Guide will give you the confidence to try your hand at electronic soldering. It’s really a lot easier than it sounds, and armed with the guide’s advice and photographs, the next thing to do is invest in a decent-quality soldering iron such as the excellent range manufactured by Antex that will serve you well for years to come.

Soldering an electronics kit together such as the professional designs produced by Velleman is a great way of testing out your new skills. Start with a small, simple kit costing a few pounds to gain confidence and experience, and avoid the temptation to tackle something too complex until you’re ready to extend yourself further.

Feedback is welcomed by email to alan@epemag.demon.co.uk

You can learn more about me at www.alanwinstanley.com or read my column in EPE Magazine.

Good luck with your soldering!

Alan Winstanley

Text and Photographs © Copyright © Alan Winstanley 1997-2013

Play fair and support writers who share their skills and expertise

Preparing a resource like this takes months and is based on four decades of practical experience which I gladly share with readers. It costs a small fortune in time, experience, IT and photographic equipment to put an ebook like this together, and the Royalties that you pay to buy the book puts food directly on my table. You paid for your copy (thank you!) so if you see any unauthorised versions of my work anywhere in circulation, I'd really appreciate being told about it. Thank you! A.R.W.

Interested in electronics?
Read EPE - the No. 1 UK hobby electronics magazine.
Ask your newsagent, download or subscribe now!
www.epemag.com
EPE EVERYDAY PRACTICAL ELECTRONICS
EPE EVERYDAY PRACTICAL ELECTRONICS
DRIVEWAY SENTRY

BSG/ ARW/V1.1/0813

Project Book

MAKE A
WEARABLE
SOLDER SKILL
BADGE

Learn to Solder

Tools and Techniques for Assembling Electronics

Brian Jepson,
Tyler Moskowite
& Gregory Hayes

O'REILLY®

Maker
PRESS™

Project Book

Learn to Solder

Learn the fundamentals of soldering—and pick up an essential skill for building electronic gadgets. You'll discover how to preheat and tin your iron, make a good solder joint, desolder cleanly (when things don't quite go right), and how to use helping hands to hold components in place.

This concise book is part of MAKE's Getting Started with Soldering Kit. Using the tools in the kit and some electronic components, you can practice soldering while making fun blinky objects. Then show the world you just learned a new skill by wearing the Learn to Solder Skill Badge.

- **Learn how to prepare your workspace**
- **Get to know the components you'll work with**
- **Use the best methods for soldering components in place**
- **Experience the perfect solder joint**
- **Know how to desolder when things don't go right**

Heat up the iron and start soldering today!

US $3.99 **CAN $4.99**
ISBN: 978-1-449-33724-7
50399
9 781449 337247

O'REILLY®
Twitter: @oreillymedia
facebook.com/oreilly
oreilly.com

Maker PRESS™
makerpress.com

Learn to Solder

Brian Jepson, Tyler Moskowite, and Gregory Hayes

O'REILLY®
Beijing • Cambridge • Farnham • Köln • Sebastopol • Tokyo

Learn to Solder

by Brian Jepson, Tyler Moskowite, and Gregory Hayes

Copyright © 2012 O'Reilly Media. All rights reserved.
Printed in the United States of America.

Published by O'Reilly Media, Inc., 1005 Gravenstein Highway North, Sebastopol, CA 95472.

O'Reilly books may be purchased for educational, business, or sales promotional use. Online editions are also available for most titles (*http://my.safaribooksonline.com*). For more information, contact our corporate/institutional sales department: 800-998-9938 or *corporate@oreilly.com*.

Editors: Shawn Wallace and Brian Jepson
Cover Designer: Karen Montgomery
Interior Designer: David Futato
Illustrator: Gregory Hayes

May 2012: First Edition.

Revision History for the First Edition:
April 27, 2012 First release
See *http://oreilly.com/catalog/errata.csp?isbn=9781449337247* for release details.

Nutshell Handbook, the Nutshell Handbook logo, and the O'Reilly logo are registered trademarks of O'Reilly Media, Inc. *Learn to Solder* and related trade dress are trademarks of O'Reilly Media, Inc.

Many of the designations used by manufacturers and sellers to distinguish their products are claimed as trademarks. Where those designations appear in this book, and O'Reilly Media, Inc., was aware of a trademark claim, the designations have been printed in caps or initial caps.

While every precaution has been taken in the preparation of this book, the publisher and authors assume no responsibility for errors or omissions, or for damages resulting from the use of the information contained herein.

ISBN: 978-1-449-33724-7
[LSI]
1335542415

Contents

Welcome v

1/Getting the Workspace Ready 1
1: Attach the Tip 2
2: Secure the Tip 2
3: Wet the Soldering Station Sponge 4
4: Set the Station’s Temperature 4
5: Wipe the Iron’s Tip 6
6: Tin the Iron’s Tip 6
Go Make Your Learn to Solder Skill Badge 7

2/How to Solder 9
Working with Solder 9
Keeping the Circuit Board from Moving 10
Tinning Solder Pads 10
Placing a Component in the Board 11
Knowing Which Way a Component Goes In 13
Stabilizing and Straightening Components 14
Safely Soldering Sensitive Components 15
Soldering a Component in Place 16
Trimming Your Leads 18
Going From Solderless Breadboard to PCB 20
Soldering Jumper Wire 22
Bridging Joints with Solder 22
Relieving Strain on Cables 24
Getting the Perfect Solder Joint 25

3/Desoldering 29
The Desoldering Wick 29
Preparing the Wick 30
Desoldering with the Wick 31
Desoldering with the Solder Sucker 32

4/What’s Next? 33
Teach the World to Solder 33
Make More Things 34
  Supercap Racer Kit 34

Wee Blinky Kit **35**
MintyBoost **36**

Welcome

Welcome to MAKE's Getting Started with Soldering Kit, and congratulations on taking a big step into the world of DIY electronics. Once you get the hang of soldering, you can put together some of the many great kits that are available, fix electronics that are broken, and build inventions of your own. With this kit, you'll learn how to:

- Prepare and clean your soldering iron
- Assemble electronic circuits from kits
- Transfer circuit designs from a solderless breadboard to a prototyping PCB
- Correct soldering mistakes you've made

Basic Tools

There's a lot of great stuff in the box, and before you start using it, here's a tour of what you'll find in there. Figure 0-1 shows the soldering tools you'll be using most of the time.



Figure 0-1. *Basic soldering tools*

Deluxe soldering iron

(Top left) This soldering station includes a variable temperature controller, a cleaning sponge, soldering iron, and a ringed holder.

Crosscut pliers

(Left) You'll use these to trim away excess leads after you solder components in place.

Solder tube

(Bottom) This is enough solder to get you started and keep you busy over many projects.

Helping hands

(Right) For those times when you need a third or fourth hand, the helping hands let you hold items steady while you solder.

Advanced Tools

Most of the time, you'll only need the basic tools to get things done. But when you need to replace your soldering iron tip, correct a mistake you made while soldering, or need a tool to help keep components from overheating, you'll need the items shown in Figure 0-2.



Figure 0-2. *Advanced soldering tools*

Heat sink

(Left) Clip this to sensitive components to help dissipate heat.

Desoldering wick

(Bottom left) Use this to wick away excess molten solder.

Desolder pump

(Center left) This pump will suck up molten solder when you have a lot of solder to remove.

Soldering tools

(Center right) The scrapers, brush, and slotted probe come in handy when you need to move solder around or precisely position a component.

Replacement tips

(Right) Tips don't last forever. When you've worn out your tip, use one of these as a replacement.

Project 1: Learn to Solder Skill Badge

Our Learn to Solder Skill Badge Kit (the 2011 model is shown in Figure 0-3) has been used to teach thousands of people of all ages how to solder at Maker Faires across the country. It's a simple, fun way to learn how to solder and also how to teach others to solder. After you build the one included in the box, you can order more from *makershed.com* and teach others how to solder.



Figure 0-3. *Learn to Solder Skill Badge, 2011 model*

Blinking or Color Change LED

(Top left) This is an LED (Light-Emitting Diode) with a twist. Normal LEDs give off a single color, and keep shining as long as you give them power. Also, normal LEDs require a specific voltage to operate: don't give it enough power, it won't light at all; give it even a little too much, and you could burn it out.

This LED is different in both respects: it has three elements (red, green, and blue) that are under the control of a small integrated circuit (IC) embedded within the LED. The IC causes the elements to change color in a repeating pattern. Because the IC controls the voltage that it delivers to the individual color elements, it's more tolerant of variations in the voltage you give it. For example, even though red LED color elements typically operate at around 2 volts, you're able to use a 3 volt battery with the pin.

The 2012 model uses two self-blinking LEDs instead of one self-color changing RGB LED.

CR1220 battery

(Lower left) This "coin cell" battery supplies power to the pin.

Printed Circuit Board (PCB)

(Center) The 2011 Learn to Solder Skill Badge features a friendly robot. The 2012 model will also have a robot, every bit as friendly.

Pin and clutch

(Top right) This is what holds the pin to your clothing.

Battery holder

This keeps the battery on the PCB.

Project 2: 555 Timer Blinky

The 555 timer blinky is a simple circuit that makes two LEDs flash in an alternating pattern. When one is on, the other is off. Figure 0-4 shows the components for this project, and Figure 0-5 shows the finished project. This is a slightly more challenging project than the skill badge.



Figure 0-4. *555 blinky parts*

LEDs
: (Left) Unlike the LEDs used in the skill badge, these are your normal, run of the mill LEDs.

Protoboard
: (Center) Look back at the skill badge PCB. Notice how it was custom designed for a single purpose. Now look at this protoboard PCB: it's got a lot of different holes in convenient locations. You can build many kinds of simple electronics projects on a board like this.

555 Timer
: (Top left) The 555 timer is a special type of integrated circuit that can turn electrical current on and off in a repeating pattern. It's just what you need to blink an LED.

Capacitor
: (Top right) To customize the 555 timer, you need to connect certain components to it. The value (capacitance or resistance) of the component determines how quickly the 555 turns things on and off.

Hookup/Jumper Wire

(Top right) You'll need this to connect one thing to another.

Resistors

(Bottom) Resistors serve two purposes here: two are used to make sure the LEDs don't get too much current; the other two work with the capacitor to control the behavior of the 555 timer.

Battery Box

(Right) This holds 3 AAA batteries.



Figure 0-5. *Finished 555 blinky*

Contact Us

Maker Shed is here Monday to Friday, 7:30 AM to 5:00 PM Pacific Time

Email: *help@makershed.com*
Phone: 800-889-8969 or 707-827-7019

Answers to our most commonly asked questions: *http://www.makershed.com/help.asp*

Got a kit or product you think we should sell? Send a note to *kits@makezine.com*.

Want to carry MAKE books or kits in your store? Send a note to *resellers@makershed.com*.

1/Getting the Workspace Ready

Before you can start soldering, you need to get your iron ready. This involves a few steps. First, you’ll have to attach the tip to the soldering iron. Then, you’ll need to prepare the station: make sure your sponge is moistened, set the temperature, and “tin” the tip by applying some solder to it.

At the end of this chapter, your soldering iron will be assembled, clean, and hot enough to begin soldering.

Solder contains harmful chemicals. Wash your hands after soldering as well as after handling solder or the solder station sponge. Though it may be tempting to snack while you’re working, keep any food or drink away from your soldering area.

1: Attach the Tip

Locate the soldering iron (make sure it's unplugged and cool), a soldering iron tip, and the tip nut that holds the tip in place. Insert the tip into the soldering iron as shown in Figure 1-1, and push it in as far as it will go. It will not require much force to insert it.

WARNING: Make sure the soldering iron is unplugged and cool.



Figure 1-1. *Inserting the tip into the tube*

2: Secure the Tip

Slide the tip nut over the tip, and screw it in place. You can use pliers to tighten it (see Figure 1-2). Be careful not to overtighten it, since you will eventually need to replace it when the tip gets worn from all the projects you'll be making with it.



Figure 1-2. *Making sure the tip stays put*

WARNING: Over time, the tip nut might become loose. Let the iron cool down before you tighten it.

3: Wet the Soldering Station Sponge

You'll need to perform this step (and the remaining ones in this chapter) at the beginning of each soldering session.

As you use the soldering iron, you're going to be wiping the tip a lot, so you need to keep the solder station sponge moist. Pour a little clean, fresh water on the sponge as shown in Figure 1-3. Don't soak it, but make sure it's completely moistened.

NOTE: If your water has a high mineral content, use distilled water for wetting the sponge.



Figure 1-3. *Wetting the sponge*

4: Set the Station's Temperature

Plug your soldering iron in, and set the heat setting to the mark shown in Figure 1-4 (pointing at the 3 o'clock position on the dial). Give the iron a couple minutes to warm up.


POWER
SOLDERING IRON
CONTROLLER
ZD-98
OFF
MAX

Figure 1-4. *Setting the temperature*

WARNING: The iron will get very hot, and certainly hot enough to burn you. Don't touch the tip and don't touch the tip to anything other than solder or components you are soldering together.

5: Wipe the Iron's Tip

Wipe the tip on the sponge as shown in Figure 1-5, being sure to turn the iron a few times as you wipe it, so you wipe all of its surfaces. It will make a sizzling sound as the water in the sponge comes into contact with the tip. The figure shows a sponge that's been used a few times. Notice the little blobs of solder that have come off the tip over time. A clean tip is critical to successful soldering. Even a small layer of oxidized material or other crud will limit the amount of heat that's transferred to the component you're soldering. Wipe the tip often, and keep the tip clean.



Figure 1-5. *Wiping the tip clean*

6: Tin the Iron's Tip

Before you begin soldering components, you should put a thin layer of solder on the tip as shown in Figure 1-6. This will have two effects: burning off any crud that shouldn't be there, but also providing a thin layer of liquid solder. This layer makes for a very effective heat transfer between the soldering iron and whatever you're soldering. Give the tip one more quick wipe on the iron and place the soldering iron into the holder until you need it.



Figure 1-6. *Tinning the soldering iron tip*

NOTE: A small puff of smoke will appear as the *rosin flux* in the center of the solder is activated. The rosin serves two purposes: to clean the soldering iron (and the joint that you are soldering) and to help the solder flow freely. Avoid inhaling this smoke.

Go Make Your Learn to Solder Skill Badge

With your workstation all set up, you're ready to try your hand at soldering. The Learn to Solder Skill Badge ("Project 1: Learn to Solder Skill Badge" on page viii) is a great place to start. It's so simple, we think you can even try it before you read any more. But before you try the second project ("Project 2: 555 Timer Blinky" on page x), you should definitely give the rest of this guide a read.

2/How to Solder

With your soldering iron prepped, you're ready to begin soldering. This chapter has many helpful tips and techniques for soldering effectively, safely, and neatly.

Working with Solder

Solder is made of metal with a core that contains flux, which cleans the connection as you solder. When the metal melts, the flux begins to flow onto the joint. Some solder lead-based, but the solder in this kit is lead-free. To melt solder, heat it with the soldering iron as shown in Figure 2-1.



Figure 2-1. *Melting some solder*

Try melting some solder, but be careful not to drip it on yourself or anything other than a work surface. You can try pushing tiny balls of solder around on your work surface to see how it flows. If you have some bare hookup wire or similar metal, try heating it up by holding the soldering iron to it (don't hold the wire while you're heating it). Touch a piece of solder to the wire, but choose a point that's an inch or so from where the soldering iron is touching. How close do you have to get to the soldering iron tip before it melts?

Keeping the Circuit Board from Moving

When you're soldering, you've got a lot to juggle: the soldering iron, the solder, and the two things you are connecting to each other. The helping hands let you place the items you're soldering in a stable position. Use the clips to hold the item in place as shown in Figure 2-2. But once you start inserting items into the board, you need some way to keep them from moving. "Placing a Component in the Board" on page 11 shows you how to do that.



Figure 2-2. *Holding a PCB in the helping hands*

Tinning Solder Pads

You'll sometimes come across things that need a layer of solder to work right. For example, on the Learn to Solder Skill Badge, you need to put a bump of solder in place to give the battery a snug fit. With solder pads that are this big, you need to heat the pad with the iron really well; the pad is so large that it's going to take longer to heat. It's best if you melt the solder by pushing it onto the pad rather than pushing it directly against the iron. This makes sure that the solder flows thoroughly over the pad. If the solder doesn't melt, try tinning the tip again first.

Start with a little blob as shown in Figure 2-3, and spread it around evenly. When you've got the desired thickness, first pull the solder away, then pull the soldering iron away. Doing it in this order will avoid leaving chunks of solder behind.


How-to:
Add blob to bat. pad
Solder bat. holder
Solder pin
Bend LED leads 90°
Solder LED
Insert bat. (+) side up
Enjoy!
BATTERY PAD
kershed.com
2011
–
+

Figure 2-3. *Laying down some solder*

Placing a Component in the Board

You don't want components falling out of the board while you're soldering. In fact, you'll often insert a component with the board upside down (see Figure 2-4), then flip the board over when you put it in the helping hands. So the components have plenty of opportunity to fall out. To keep the component in place, bend the leads out as shown in Figure 2-5.

In some cases, you may need to quickly tack a component in place to keep it from moving. See "Stabilizing and Straightening Components" on page 14.

Don't try to place every component at once. Start with low-profile (shorter) components, solder them in one at a time, and move on to higher-profile components.



Figure 2-4. *Inserting an LED*


−
+
Add 'blob' to bat. pad
Solder bat. holder
Solder pin
Bend LED leads 90°
Solder LED
Insert bat. (+) side up
Enjoy!
makershed

Figure 2-5. *Bending out the leads*

Knowing Which Way a Component Goes In

Some components don't care which way you put them in: resistors, some capacitors (such as the one that comes with this kit), and many other components fall into that category. On the other hand, LEDs are *polarized*; electrical current will only flow through them in one direction. So if you put your LED in backwards, it won't light up at all. You can determine an LED's polarity in a couple of ways: First, the longer of the two leads is the positive (+), and the shorter is negative (-).

Second, look closely at the bottom of the LED and examine the ring that bulges out around it. There is a flattened part of that ring that indicates the side of the LED that's negative (-). You can see this flattened side on the right in Figure 2-6.

With ICs, this also matters. Every pin has a specific function, and there will be one or more pins for positive (+) and one or more pins for negative (-).



Figure 2-6. *Polarity—LEDs have it*

Stabilizing and Straightening Components

ICs present a unique problem. They don't have long enough leads for you to bend out effectively, which means they are more likely to slip and slide while you're soldering them. So do the best you can with that (see Figure 2-7), but flip the board back over after you solder the first joint. In most cases, you'll find that the IC has shifted. But since you only have one joint soldered, you can easily move the IC into the position you want. Once you've done this, flip the board over and solder the remaining connections.



Figure 2-7. *Tacking down an IC*

Safely Soldering Sensitive Components

You need to avoid applying too much heat to a component, or you might damage it. One way to help avoid this is to clamp the heatsink to the component as shown in Figure 2-8. This will draw heat away from the component, protecting it somewhat.



Figure 2-8. *Keeping heat away from the component*

Soldering a Component in Place

Wipe the soldering iron on the sponge and hold it so it’s touching both the solder pad and the lead that protrudes through. Avoid using the soldering iron to melt the solder. Instead, heat up both the lead and the pad so that the solder melts when you touch it to them.

This must all be done quickly: within a second of touching the iron to the joint, push a small amount of solder into the joint, and let it flow around the joint as shown. Give it a second to flow, take the solder away, then wait a second, and take the iron away. With practice, you should be able to do all of this in three to four seconds per joint. Figure 2-9 shows how you’d solder the pin to the skill badge. Figure 2-10 shows an LED being soldered.

If you hold the iron to the component too long, you run the risk of damaging either the component or the solder trace on the PCB.



Figure 2-9. *Soldering a pin*


+
How-to:
Add 'b o bat. pad
Sol t. holder
pin
LED leads 90°
der LED
sert bat. (+) side up
2011
BATTERY PAD
makershed.com

Figure 2-10. *Soldering an LED*

Trimming Your Leads

After you solder a component in place, you need to tidy things up. Grab the cutters from your kit, and trim the leads as close to the solder joint as possible (see Figure 2-11 and Figure 2-12). Don't cut into the solder joint; the idea is to trim the excess wire lead.

When you clip it, the wire lead will fly away from the clippers very fast, and could injure someone. The best way to keep this from happening is to use one or two fingers to hold the lead you're clipping. With one finger, you can put enough pressure on it to keep it from flying away.



Figure 2-11. *Trimming leads on the 555 blinky*


How-to:
Add 'blob' to
Solder bat. hold
Solder pin
Bend LED leads 90°
Solder LED
Insert bat. (+) side up
Enjoy!
BATTERY PAD
makershed.com

Figure 2-12. *Trimming leads on the Learn to Solder Skill Badge*

Going From Solderless Breadboard to PCB

The beauty of protoboard is that it mirrors the layout of a solderless breadboard, which is used for prototyping electronic circuits. Once you have your project laid out and working on a breadboard, you can easily transfer it to the protoboard. As with a solderless breadboard, the protoboard has rows and columns that are tied together. The layout is slightly different, though. Where the breadboard has two rails (one for positive, one for negative) on both the top and bottom as shown in Figure 2-13, the protoboard that comes with this kit has its rails in the center of the board.

Figure 2-14 shows the project from Figure 2-13, but laid out on a protoboard instead of the solderless breadboard.



Figure 2-13. *The 555 blinky project on a breadboard*

NOTE: The breadboard diagram in Figure 2-13 was made with Fritzing, an open-source initiative to support designers, artists, researchers and hobbyists to work creatively with interactive electronics. For more information, see *http://fritzing.org/*.



Figure 2-14. *The 555 blinky project on a protoboard*

Soldering Jumper Wire

Jumper wire can be treated a lot like other components (see "Placing a Component in the Board" on page 11): make sure there's enough bare wire poking through so you can bend it outward enough to hold it in place. The notched probe included with this kit can be helpful with placing jumper wire in the right place (see Figure 2-15).



Figure 2-15. *Placing the jumper wire*

Bridging Joints with Solder

When you're working with the protoboard, you will sometimes need to bridge joints that are close to each other. This is preferable to using jumper wire since your board remains uncluttered on the top. It doesn't always look great on the bottom, though, because you end up with a lot of solder in some places. Figure 2-16 shows the start of a bridge: feeding the solder into the gap between solder joints. Figure 2-17 shows a bridge being formed.



Figure 2-16. *Feeding solder into a gap*



Figure 2-17. *Forming a bridge across the gap*

Relieving Strain on Cables

If you have something heavy dangling off your board, such as a battery box, it's very likely that the solder joints will come undone. If you pass the wires through the large holes on the board before soldering them down (Figure 2-18), you can add some strain relief (Figure 2-19) that will help prevent this from happening. If you have a small drill, you can also drill out a couple of holes close to where you are going to solder the connection, and loop the wire through there. This will be even more rugged than using the larger holes.



Figure 2-18. *Soldering the battery holder wires*



Figure 2-19. *Strain relief*

Getting the Perfect Solder Joint

It's not hard to get a great solder joint, but it's also easy to be sloppy. Here are some pictures of good and bad joints to help you out.

Figure 2-20
: Here's a good solder joint on the positive (+) pad: solder surrounds the joint and makes a little peak. This joint had just the right amount of solder and just the right amount of heat.

Figure 2-21
: The joint on the negative (-) pad is sloppy. The solder didn't flow around the joint, and some of it is spread out across the lead. You can try to fix it by holding the iron to the joint for a couple seconds; the solder should flow down the lead and onto the joint.

Figure 2-22
: The joint on the positive (+) pad has too much solder, and it's balled up. You can use the desoldering wick or solder sucker to remove the excess. After you do that, hold the iron to the joint for a couple seconds to get the solder to flow around it.

Figure 2-23
: Here are two joints for comparison: one good, one blobby.


How-to:
Add 'blob' to bat. pad
Solder bat. holder
Solder pin
Bend LED leads 90°
Solder LED
Insert b
Enjoy

Figure 2-20. *A good solder joint*


Enjoy!
Insert bat: (+) side up
Solder LED
Bend LED leads 90
Solder pin
Solder bat. holder
Add 'blob' to bat. pad
How-to:

Figure 2-21. *A messy solder joint*


How-to:
Solder pin
Bend LED leads 90°
Solder LED
Insert bat. (+) side up

Figure 2-22. *A blobby solder joint*



Figure 2-23. *Comparing two joints*

3/Desoldering

If everything went right the first time, you'd never learn anything. This section shows you how to recover from little soldering mistakes, and also includes a gallery of various solder joints so you can compare your work.

Desoldering is the "undo" command for soldering. With this technique, you can remove solder from a joint, allowing you to free the component so you can reorient it as needed. There are two tools for this: the *desoldering wick* (sometimes called *desoldering braid*) and the *solder sucker*.

The Desoldering Wick

Pull a small length of wick out of its spool (Figure 3-1). You don't need much, but if you don't use it all, you can wind the wick back into its spool.



Figure 3-1. *Pulling out some wick*

Preparing the Wick

Before you use the wick, hold it as shown in Figure 3-2, and push inward. This will cause the wick to spread out, giving you more surface area to work with.



Figure 3-2. *Spreading the wick*

Desoldering with the Wick

Position the wick over the joint, and press down on the wick with the soldering iron as shown in Figure 3-3. The heat will pass through the wick and melt the solder. As this happens, the wick will soak up the solder, removing it from the joint. When you're done, you can trim off the used portion of wick with your wire snips.



Figure 3-3. *Desoldering*

WARNING: The wick will get very hot, so take your hands off it as soon as you press the soldering iron to it (the soldering iron will hold it in place).

Desoldering with the Solder Sucker

The solder sucker is another tool for removing solder. It's best for removing excess solder, and you can use it to clean things up a bit before you use the wick. To use the solder sucker, press the plunger down until it locks. Use the soldering iron to melt the solder around the joint, and quickly bring the solder sucker's nozzle to the joint (Figure 3-4). Press the button on the sucker, and it will pull the solder right up into the tube. When you press the plunger again, any solder in the tube will be ejected.



Figure 3-4. *Using the solder sucker*

4/What's Next?

Now that you've learned the ins and outs of soldering, it's time to do more. You can share this book with a friend so they can learn, or you can teach them yourself. And the world is full of wonderful things you can make now that you know how to solder.

Teach the World to Solder

Before you can teach someone to solder, you need to figure out what you want them to try making. You can purchase more Learn to Solder Skill Badge Kits from *http://makershed.com*. Here are a few tips for teaching soldering to others:

Keep Your Hands Off the Tools

You're there to teach, not to solder. And your students will learn best if they always have their hands on the tools. If you grab the tools from them and do part of the work, they won't learn from it.

Be Patient

Try to remember what you went through the first time you tried to solder. It takes time, and you did things incorrectly, and maybe you even made mistakes that required desoldering. Let your students learn from their mistakes, and let them take their time.

No Food or Beverages

Even with lead-free solder, there are chemicals in the flux that aren't good for you. If you allow food or drink near the work area, it could get contaminated. Keep food and drink away from where you're working.

Make Sure There's Plenty of Light

The components you work with while you solder are small, and hard to see. Make sure to use a well-lit workspace for teaching.

Keep Spare Parts Around

Beginners will break things. Pick up some spare resistors, LEDs, and other common components, and have them on hand in case you need to replace a damaged component.

Make More Things

Maker Shed (*http://makershed.com*) carries many electronic kits that you can apply your newly-learned soldering skills to. Here's just a few of them:

Supercap Racer Kit

One of the latest in our popular Mintronics line of DIY kits is this tiny race car designed by George Albercook. Once assembled, this little racer (Figure 4-1) will run around getting its juice from a supercapacitor. Capacitors are like little batteries. Supercaps store and release power faster than ordinary ones, so they're great for making quick-charge gadgets and power-on-demand circuits.



Figure 4-1. *Supercap Racer Kit*

Wee Blinky Kit

The Wee Blinky kit (Figure 4-2) is an easy-to-solder two (2) LED blinker circuit. It comes with a 9V battery snap, but will work with almost any voltage from 3V to 12V. A 9V battery is required but not included. It's tiny, it blinks, and it's a great kit to hone your soldering skills since it's cheap too!



Figure 4-2. *Wee Blinky Kit*

MintyBoost

The MintyBoost (Figure 4-3) is a small and simple USB charger for your iPod or other MP3 player, your camera, cellphone, and any other gadget you can plug into a USB port to charge.



Figure 4-3. *MintyBoost USB Charger Kit*

About the Authors

Brian Jepson is an O'Reilly editor, hacker, and co-organizer of Providence Geeks and the Rhode Island Mini Maker Faire. He's also been involved in various ways over the years with AS220, a non-profit arts center in Providence, Rhode Island. AS220 gives Rhode Island artists uncensored and unjuried forums for their work and also provides galleries, performance space, fabrication facilities, and live/work space.

Tyler Moskowite, a programmer, engineering intern at Make Magazine, and student at Santa Rosa Junior College, has been tinkering with electronics for almost half his life. He picked up Arduino, then Android, and with the release of the ADK he has found his niche.

As a photographer for Make Magazine, Gregory Hayes has ruined more clothes than he ever did as a handyman, hiked more miles with a heavier load than he did as a backpacker, done more research than he did as a writer, and gotten closer to more human hands than advised by any epidemiologist. Taught to solder at the age of seven and forced to solder for his supper at the age of nine, he's now content to let others enjoy the lion's share while he stands by watching safely from behind glass.

How to solder

This pdf refers on informations from the site: http://store.curiousinventor.com/guides/
Have also a look to the 7min. Tutorial video on: http://store.curiousinventor.com/guides/How_to_Solder

Select a Soldering Iron

A 25 or 30 Watt iron should suffice for most small electronics work.

1. Most **soldering "guns" are vastly overpowered for electronics soldering** and can easily overheat components or expose them to harmful voltages. However, some people cleverly use them to solder multiple leads on surface mount devices. Soldering "guns" are for plumbing and much heavier duty applications, and are usually over 100 Watts. The "guns" work by passing high currents through the tips, and these currents can generate voltages that damage electronic components. Also, magnetic fields from guns with transformers can damage some electronics.By forming the heating element in the shape of of the chip, a soldering gun can be used to heat many leads simultaneously.

2. **How much wattage do you need for a particular application and how does wattage relate to tip temperature?**

   A loose analogy: Imagine a car tire has a leak, but you’re trying to keep it inflated by pumping air into the tire at the same time it's escaping out the leak. The bigger the leak, the more air you have to pump into it to keep the pressure up. If the tire pressure represents tip temperature and the air lost through the leak represents heat lost through the tip, then wattage represents the maximum amount of air your pump could supply. Once more air escapes through the leak than your pump can replace, the tire pressure (or tip temperature) starts to drop.

   If you had a very small leak and a huge pump (say a 100 Watt iron equivalent), you might be afraid that the pump would cause the tire to explode since so much more air is going in and so little going out. But if you have a nozzle to regulate the pump's air, you could only allow just the right amount of air in to replace what's lost through the leak. This is how "temperature controlled" soldering irons work. As long as you aren't losing more heat out of the tip than the iron can replace (up to its rated wattage), it will automatically regulate just the right amount of heat into the tip to maintain the same temperature.

   However, typical plug-in irons have no such regulation. A 15 Watt iron always delivers 15 Watts of heat to the tip, and the tip temperature stops increasing only when 15 Watts of heat escape through the air. When the tip touches a part, its temperature drops, and if the part you're soldering can dissipate enough heat, the temperature will keep dropping until it won't melt solder any more. After the iron is pulled away from the joint, the temperature will climb again. There is some amount of natural regulation: as the tip gets hotter, it dissipates more heat, and as it gets cooler, it dissipates less.□

   Usually, the bigger the component the more heat it can absorb and dissipate, so the general rule is that you need more wattage for larger parts. If you're just soldering small resistors and ICs, 15 Watts will probably suffice, but you may have to wait a bit in between joints for the tip to recover. If you're soldering larger components, especially ones with heat sinks (like voltage regulators), or doing a lot of soldering, you'll probably want a 25 or 30 Watt iron. For soldering larger things like 10 gauge copper wire, motor casings, or large heat sinks, you may need upwards of a 50 Watt iron or more. The following video shows what happens to tip temperature as 15, 25, and 40 Watt irons solder various sizes of wires and components. For cheap irons, higher wattage does indeed mean higher temperatures!

- What is the difference between cheap RadioShack® irons and more expensive ones like Wellers®? What do $100+ and $400+ soldering "stations" have over the cheaper kinds that plug straight into the wall? expand Among the irons that plug straight into a wall and don't have a separate station, the dirt cheap kinds will work satisfactorily for many applications. From personal experience, the tips on RadioShack® irons often come loose and sometimes can be impossible to remove. The irons can also get uncomfortably hot to hold after several hours of use. The more professional Weller (or other) lines are made for longer, continuous use and have insulation on the handles that keeps them cooler. They

can also take a wider variety of tips.
Soldering iron "stations" usually provide some control over the heat being supplied to the iron tip. Ones that are temperature controlled automatically control the amount of heat delivered to the tip so that it remains at a set temperature. In every iron, when the tip touches a component, some heat is lost and the temperature drops. One measure of quality is the time needed for the tip to regain its temperature. A nice feature of many soldering stations is that the tip heats up in seconds after you turn it on.
Many stations also allow you to hot-swap the iron tip, which can be very helpful if you're alternating between surface mount joints and larger components.

- If standard tin-lead solder melts below 400 °F (and lead free below 500 °F), why do most soldering irons have tip temperatures between 600 and 800 °F? Just what is the right **soldering temperature**? expand The basic reason that tips are so much hotter than solder's melting point is because that difference helps to transfer heat faster to the joint. What is the "correct" temperature is a debatable topic, but a common rule of thumb is to start off at 600 °F and increase from there until acceptable results are achieved. Typical Kester (a solder manufacturer) datasheets recommend 600-700 °F for lead-based solder, and 700-800 °F for lead-free solder. "No-clean" or "low solids" fluxes will burn off before a joint can be made with higher temperatures, so low temperatures (below 700) may be essential for these fluxes.
  From Kester's hand-soldering knowledge base: "When hand soldering with a rosin flux such as the Kester #44 or the # 285 the recommended iron tip temperature is 750°F. If you are soldering with a low residue no clean solder such as the #245or # 275 we recommend a tip temperature of 600-650°F.
  What are acceptable results? The goal is to heat up the parts enough so that solder will adhere to them and form a good bond. The higher the iron temperature, the faster it will heat up the parts, so why not set it extremely high to work faster?
  Besides the obvious increased risk of overheating components and the board, higher temperatures cause the iron tip to oxidize faster and can significantly reduce its life. Some claim a 10 °C rise reduces tip life by half (ref p.33). For occasional use, though, tip life may not be much of a factor, especially if the tip is kept covered with solder at all times.

- **Tip size and shape:** a basic guide is to pick a tip that's slightly smaller than the pad you're soldering to. From there, you want a tip with a large thermal mass and short stroke (why?) In most soldering irons, the tip is not actually the heater, but sits in between your work and the heater. You can think of it like a heat bucket that empties into your work and gets filled again by the heater. Typically touching a component empties heat out of the tip much faster than the iron can replace it, and if you have a small bucket (tip), the temperature will quickly drop to an ineffective level.
  Especially if you have a small wattage iron (15 Watts or less), the temperature will drop before you can heat up a larger part, or you'll have to wait a bit in between joints for the tip temperature to recover. With a bigger bucket (tip), you can handle larger joints with smaller wattage, but eventually you'll need to step up the wattage.
  The "stroke", or length of the tip should be minimized to get the heater closer to the work; it takes some time for heat to transfer through the tip. This is balanced with the need to get into tight places where you need a longer tip.
- What do common tip shapes look like and what applications are they best for?



Screwdriver, spade, and conical are some of the more common tip shapes. Personal preference is the biggest factor when choosing a tip, but the goal is to get as much surface area contact between the tip and work as possible. Chisel and spade tips have more surface area at their ends, and also "hold" solder at their tips more readily than conical tips, which have a tendency to draw solder away. Even for fine pitch surface mount soldering, having a small flat at the end can be helpful.



- There are myriad other tip shapes and sizes. The picture to the right shows one Plato catalog page of many. Some other non-standard shapes include a knife-blade (useful for fine pitch leads) and a surface mount desoldering tip.



desoldering a surface mount soic chip

© 2007 CuriousInventor.com



apply flux | apply solder to tip | contact chip | lift off

To preserve tip life, the number one thing you can do is reduce the tip temperature (if your iron allows this). After that, ALWAYS keep a layer of solder on the tip to prevent the tip itself from oxidizing, and clean it in between uses. Put a glob of solder whenever you put it back in the stand, and before you turn it off. When heating up a new tip for the first time, hold solder against it so the tip can be covered as soon as the iron gets hot enough.

The longer flux residues and oxides are left on the tip, the harder they are to clean off. They also can drastically reduce the tip's ability to heat up a part, and prevent solder from "wetting" the tip. Regular cleaning of the tip before use is one of the best ways to prolong tip life and make soldering easier. It's important that solder "wet" or cling to the surface of the iron--without solder in between the tip and work the tip's ability to heat is drastically reduced.

- What about gas powered irons and the Cold Heat® iron that is supposedly touchable 1 sec. after use? Butane (and other gas) powered irons are mainly used in situations where electrical power isn't

available. Weller sells some battery powered irons as well.
Everyday Practical Electronics gives a pretty damning review of the Cold Heat iron here, in addition to having one of the better how-to guides out there. To summarize, the Cold Heat® iron has a forked end that you must bridge with the work or solder to turn on the iron, so it can be hard to hold it in a place that keeps it on and also effectively heats the part. Many people complain about pushing harder to make a good connection and then having the brittle tips break. Running power through your work to heat it may not be the greatest idea with some parts. Finally, the iron doesn't get hot enough for a lot of jobs, or cool enough to do anything like throwing it in your pocket right after use. But for something that's portable and cordless, heats up and down in under a few seconds, maybe it's worth the price ($20). Weller's battery powered ($20) iron doesn't have a forked end and supposedly heats up in under 15 seconds, but I don't know about cool-down time.



What kind of solder (rosin cored, etc. lead-free)? What is flux and when is it necessary?

As a starting place, for most small electronics soldering, 1/32 inch (.03) rosin-cored, 60/40 (tin-lead) or 63/37 solder should work fine. Rosin-cored lead-free is fine, too. Unless you have reason otherwise, don't use "no-clean" solder--it's very likely that you don't need to clean the regular rosin-cored solder. The solder should be thin enough to prevent accidentally applying too much (and causing a solder bridge), but thick enough so that more doesn't have to be gathered from the coil too often.


Flux cored wire at 30X magnification
© 2007 CuriousInventor.com

Besides affecting your feed-rate and convenience, the solder thickness also relates to the amount of flux that is delivered. Flux is basically a weak acid that removes oxides so that solder can adhere to the metal, and is so essential to the soldering process that it's built into the core of common wire-solder. It also helps the solder spread out (reduces surface tension), transfer heat, and acts as a protective blanket to keep oxygen away from the metal until solder displaces it.

For the most part, manufacturers include a sufficient amount of flux in the wire, but if you use an extremely thin wire there may not be enough to clean the joint OR the iron tip. Consider using a thicker gauge for cleaning the tip periodically if you're using especially thin solder. Liquid flux is helpful for SMD soldering, too.

When picking a wire-solder, there are 4 features to decide on: flux type and amount (% weight), alloy (tin-lead, lead free, silver bearing, etc.), thickness and total amount (1oz, 1lb?).

- **Flux:** Just what is flux, what kinds are there, and when do I need liquid flux?

  Why it's needed: Solder doesn't just freeze on a joint, it actually forms a metallurgical bond by dissolving and chemically reacting with the base material. Unfortunately, almost all metals oxidize in air and form an oxidized layer that prevents solder from wetting and bonding to them. What is oxidation?

  Oxidation, is when Oxygen (or other oxidizing agents like sulfur) atoms combine with base materials, stripping loosely attached electrons and forming new compounds like iron(III) oxide. It is what happens when apple slices turn brown, iron rusts, copper turns black / green and unsolderable. (read references for more accurate/complete explanation)

  Results vary significantly. When iron rusts, the oxides flake off until no iron is left. Alternatively, aluminum oxidizes extremely rapidly, but is then protected from additional oxidation by the oxide layer. This layer makes Al impossible to solder without using special solder and extremely aggressive flux, or plating the surface with a solderable metal, like nickel. The chromium in stainless steel fulfills the same function, oxidizing to form a protective barrier that is difficult to solder. Gold remains shiny because it doesn't oxidize, and is easy to solder to, but forms brittle joints. Heat, moisture, and salt all increase the rate of oxidation.

Oxidation can add a hidden cost to components and boards that may have been sitting on the shelf for long periods of time, or have been exposed to hot, humid environments. Copper pads on PCBs (printed circuit boards) are covered with solder or are plated to prevent oxidation, but given enough time, oxygen can still penetrate these barriers. Surplus parts in particular may need a bit of steel wool.

Some interesting references:
rusting chemical reaction
fairly understandable explanation of oxidation
wiki/Corrosion
wiki/Oxidation

Oxidation occurs much faster at higher temperatures, so even if you somehow had clean metals to start with, you would still need flux to prevent new oxides from forming while soldering.

The main choice to make when deciding on a flux, whether it comes in a cored wire or a liquid or paste form, is how aggressive it should be. The more aggressive or "active" the flux, the harder the oxides it can remove, and the faster it can remove them. Going from weakest to strongest, typical choices for hand soldering applications include: "no clean", RMA (Rosin Mildly Activated), RA (Rosin Activated), and water soluble. A newer classification system (J-STD-004) has recently been adopted and classifies fluxes not by rosin content, but by activity, material, and halide presence.

The new system classifies flux by material (RO=rosin, RE=resin, OR=organic, IN=inorganic), activity level (Low, Moderate, High), and halide presence (0 or 1). No-clean, rosin-based no-clean fluxes might be labeled ROL0 or ROL1. Although there is no direct translation between the old system and new, most R and RMA fluxes fall under Low activity level, RA are generally labeled as Moderate activity, and water soluble are High activity. (source IPC-HDBK-001 www.ipc.org)

The downside to choosing a more aggressive flux is that the residues left over after soldering MAY be corrosive, conductive, or enable fern-like growths called "dendrites" to grow between connections. A brief description (p.29) of dendrite growth and some great pictures at the end of this paper.

Because of the risk of corrosion and dendrite growth, most manufacturers clean off the residue from RMA and RA fluxes, and some even clean "no-clean" residues. The question of what flux to use and whether / how to clean it is quite involved.

Rosin flux is quite an interesting animal. Made from pine tree sap, at room temperature, it's an excellent insulator and non-corrosive. When it hits 226 °F it begins to turn acidic and attack oxides, but then when it cools it supposedly leaves residues that are again inert. Kester's data sheet for "44" flux (classified as RA and ROM1) claims no cleaning whatsoever is necessary. I haven't read of any manufacturers that would use a RA (or even an RMA) flux and not clean it--the military won't even use a RA flux WITH cleaning because of the risk that some will be left behind. This Chemtronics author recommends cleaning even the "no-clean" fluxes. He also points out that even if the residue is non-corrosive and non-conductive, it might be tacky and attract dust that causes a short.

To add one more piece to the puzzle, flux generally gets used up during the soldering process. This is why no-clean fluxes are oftentimes ineffectual for lead-free soldering, which can require slightly higher temperatures and longer heating because the lead-free solder "wets" slower. The no-clean flux can burn off before the joint is complete. Alternatively, if you apply liquid flux far from a joint, it may still be active (corrosive) if it never got heated.

I'm not making missile guidance electronics, I'm making a robot that pours a beer, what flux should I use and do I really need to clean? Even manufacturers of non-life critical electronics have much more stringent reliability requirements than an individual. They must ensure that tens of thousands of products will work for multiple years, not a single project.

The safe advice is to use the least aggressive flux that enables solder to quickly wet or cling to the surfaces, and then clean off the residues with alcohol and lint-free wipes (don't just spread the flux around). Try starting with a rosin-based mildly activated flux: RMA. I am inclined to trust Kester's spec sheet for "44" (RA) flux that says it does not actually require cleaning. Other flux manufacturers may have RA or RMA level fluxes that do indeed need to be cleaned, so if you don't know what you're using, cleaning is probably prudent. If you are going to clean rosin fluxes, do it soon after soldering because they quickly harden (see pics under 'Cleaning'). Finally, I would personally avoid no-clean fluxes and solder unless you have a critical application and very clean parts.

Lead-free solder generally requires a made-for-lead-free flux designed to be used under slightly higher temperatures.

Liquid flux can greatly help with surface mount soldering and desoldering components, but the flux inside cored-solder should be sufficient for through hole components. When soldering SMD components and desoldering pretty much anything, liquid flux acts as a blanket that helps to spread heat and also keep oxygen away from the metals. Finally, flux lowers the surface tension of solder, helping it to spread out and wick into connections.

A water-soluble flux may be necessary for heavily oxidized parts or difficult metals like nickel. Without question, clean these fluxes. Special fluxes and solders exist for aluminum and stainless steel and these also certainly require cleaning. Never use acid-core solder; it deposits zinc chloride into the solder that cannot be cleaned out. A final reason to clean flux residues is if you'd like to apply a conformal coating and aren't sure whether it will adhere to those residues.

Some more references:

- Never use acid-core and how to solder to stainless steel (Kester)
- White residue and all about rosin (more Kester)
- Good mini-class on fluxes: Bolton University
- To clean or not to clean and a brief history of electronics cleaning: more Bolton
- The Kester catalog provides good info on the solderability and flux requirements of various materials (see p.14).
- Flux residues and what to do about them. This explains a bit about cleaning options and the health risks of rosin and non-rosin fluxes.



- **Alloy:** 60/40, 63/37, tin-lead, lead-free, silver bearing, RoHS, eutectic, oh my...

- **Standard lead-based solder** is made of tin and lead. When you see 60/40 or 63/37, it means 60% tin by weight, 40% lead. Either once of these alloys should be fine for typical small electronics soldering. 63/37 in bulk is slightly more expensive because of additional tin, but has the special property of being a "eutectic" alloy, which transitions from liquid to solid at one temperature (like water) instead of range of temperatures. Basically, in non-eutectic alloys like 60/40, there is a "pasty" region of temperature where portions of the solder are frozen and other portions are liquid. What does this mean for soldering and is 63/37 really that much better?

  Alloy metals have some interesting properties that are different from the metals comprising them. In tin-lead solder, the mixture has a lower melting point than either lead or tin alone, and the melting point varies depending on the portions. The mixture that yields the lowest melting point is called eutectic. This is also the only mix where all the constituents melt and freeze at the same temperature.

  If the tin-lead alloy isn't eutectic (ie, if it is not 63% tin), it will go through a "pasty" phase while it freezes. Unlike water, which freezes entirely at 0 °C, some parts of a non-eutectic mixture of tin-lead freeze at higher temperatures than other parts. For a somewhat simplified explanation, if you held the temperature of 60/40 slightly above 361 °F, the "extra lead" would solidify and be floating in a liquid 63/37 eutectic mix. For a more exact and great explanation of this process, look here.

  How is it that the mixture of two elements somehow lowers the melting point? And I quote: "increased entropy." Chew on this. (Another great phase-diagram explanation with a bonus of why ice and salt can get almost 30 °F below freezing--enough to freeze ice cream) And one last great explanation--talks a bit about grain structure and how solder isn't a simple homogeneous mixture of tin and lead.

  This compares the difference between eutectic freezing in tin-lead and eutectic freezing in more complex 3 element lead-free alloys.



So which is better, 60/40 or 63/37? A decade or so back (before the lead-free movement), most manufacturers incurred about a 5% increase in cost to switch from 60/40 to 63/37. 63/37 flows slightly easier, makes shinier joints, and has a faster total freezing time which means there is less risk the joints will be "distrubed," which is what happens when the joint moves during solidification. This can lead to internal fractures that cause poor electrical connections and unreliable mechanical joints. Note that 63/37 doesn't freeze instantly (just like water)--it still has a window of time during which the joint can be disturbed, too.

I think most would say that the enhanced properties of 63/37 really only matter for mass soldering operations like wave or reflow soldering, and that there is little difference for hand soldering. A dull joint is more often caused by insufficient heat, dirt or oxides, or lack of flux rather than alloy makeup. (A no-clean flux may burn off before the joint is complete) Holding everything else constant, the difference in shininess between 60/40 and 63/37 is completely cosmetic. If you'd like to see a shiny 60/40 joint, try using Kester 60/40 with #44 flux.

- **Silver bearing solder:** (that is, contains silver, not for roller bearings) Silver is used in one of the leading alloys for lead free solder (An96.5% Ag3.0% Cu.5%) and also as an addition to tin-lead solder, usually in the 2-4% range (when you se 62/36/2 this means Sn64Pb36Ag2).

  People claim that it flows better, has a lower melting point, is stronger, and has a higher conductivity. According to Indium's solder wire data sheet, their 2% silver solder has an electrical conductivity that is 11.9% of Cu compared to 11.5% of 63/37 tin-lead solder, a shear strength of 7540psi vs. 6200psi, and a tensile strength of 7000psi vs. 7500psi for 63/37. So, yes, the claims are true, and also mostly insignificant. Silver was initially added to solder to prevent silver platings on component leads from dissolving into the solder ("silver migration") and forming brittle joints. Having silver in the solder reduces migration, so you may want to use it on silver joints. (Note: this logic doesn't entirely make sense to me. If silver getting in the solder caused embrittlement, how does adding *more* silver prevent this?)

  Audiophiles seem to be enamored by 4% silver bearing solder, namely some from WBT, Cardas, and WonderSolder. Are these really better for audio?

  The superior claims include things like higher purity, eutectic alloys, higher conductivity, and better flux. I haven't found any controlled studies showing that a group of people can actually hear the difference, so I'm skeptical. Although additional silver does increase conductivity, the increase is small and the joint distance over which that conductivity applies is also extremely small. For what it's worth, here's a forum discussion that discusses a bit about solder in high-end audio and also a FAQ (scroll down)concerning solder on Cardas Audio's site. Another decent discussion.

  Bad joints made with any solder can create a high-resistance connection, especially if the underlying components were heavily oxidized initially. My advice: if it makes you feel better, get it, but be wary of sellers that don't provide spec sheets.

- **Lead-free Solder:** As of July 1st, 2006, European laws mandated that new electronics be almost entirely lead free. As of yet, there are no US laws (outside CA) mandating the removal of lead, but most manufacturers are switching over for competitive reasons. More on RoHS, WEEE, and lead risks:

  The European Union passed directives in 2003 stating that no equipment sold in Europe should, by July 2006, have more than .1% lead in any homogenous component (like a solder joint). The directives are known as the WEEE (Waste Electrical and Electronic Equipment) and RoHS (Restriction of Hazardous Substances) (wiki). There are corresponding laws in China, Korea, and California. Japan manufacturers actually voluntarily begin switching to lead free years before RoHS or WEEE for competitive reasons. IPC's informative lead-free website: here.

Although only .5% of lead used in the US gets embedded in electronics (verses 80% in batteries), there is concern that the lead from those electronics will leach into ground water supplies from landfills. Why the concern over solder joints when batteries contain so much more lead? For the most part, lead containing batteries are recycled and regulated, whereas electronics are routinely just thrown away. The EPA claims that 1% of municipal waste is electronics. Interestingly, according to this publication by IPC, no studies have found any evidence of lead getting into the ground water from landfills.

Lead health risks: Lead does not get absorbed through the skin, and is actually not present in solder fumes to any appreciable degree (fumes are still bad for you, see fumes section below). The greatest risk of hand soldering with lead comes from ingesting lead by eating or smoking without first washing. Health risks include increased blood pressure, fertility problems, nerve disorders, muscle and joint pain, irritability, and memory or concentration problems. The latest health data indicates that there is no amount of lead that will not be detrimental to health. Google lead or start with this link.

Some great lead-free joint pictures: here.

The most popular lead-free alloy seems to be Tin 96.5% Silver 3.0% Copper .5%. The wiki page on solder mentions several different lead-free varieties.
-AIM lead-free solders.
-Huge list of Indium lead-free solders and their properties.

Lead-free solder generally melts at a higher temperature, and doesn't wet as quickly to metals. (Eutectic tin-lead solder melts at 361 °F and the SnAg3Cu.5 melts at 423 °F.) Manufacturers generally recommend setting soldering iron temperatures between 700-800 °F for lead-free instead of 600-700 °F for tin-lead soldering. The 15 Watt RadioShack® iron I had operated a bit below 500 °F, so soldering should be possible with it, but maybe slow. Technique wise, since lead-free wets slower, joints will take longer (upwards of 4-7 seconds), but this doesn't mean the soldering iron temperature should be turned up excessively--patience is better than higher temperatures. If you're going to use a lead-free solder, get a flux that's designed for the higher temperatures--the regular no-clean fluxes will likely burn off before doing their job.

A quick word on reliability. Some say that lead-free joints are stronger, and while the material is indeed stronger, it's less flexible than lead-based solder, so expansion and contraction due to temperature change has been shown to break components held by lead-free solder. It seems true mechanical reliability of lead-free vs. lead depends heavily on the situation (see p.30). There is also concern of something called "tin whiskers." These are extremely thin crystalline growths that grow perpendicularly out from surfaces. These took down some space systems and NASA has a great page here. These are different from dendrites (which grow on the surface) and appear to be more likely on bright all-tin platings. Most component platings used to consist of a tin-lead mixture, and since all-tin platings are a common lead-free replacement, people are concerned. I have yet to find any literature that points to TinSilverCopper solder as a risk factor, though. I believe it is a plating issue, only.

One more link: -Why tin or silver?

- **Thickness and Amount:** As a general guide, .032" thick solder (21 gauge) should be suitable for through hole soldering and some surface mount soldering. For finer pitch surface mount devices, use .02" or .015", and if you're soldering a lot of switch terminals, or tinning thick gauge wire you may want .05". If you use .015" solder consider having some thicker solder on hand to re-tin your tip, since the amount of flux in .015" may not be enough to remove tip oxides. The picture below shows how the various thicknesses compare next to the standard .1" spaced DIP pins.


© 2007 CuriousInventor.com
.015"
.022"
.032"
.05"
.062"
.1"
P0136AD
DM74LS47N

Expand to see how .032" and .015" solder compare to a SOIC surface mount chip and fine pitch (.02") device.


.032" solder next to .05" spaced SOIC leads
SO16
DIP16
© 2007 CuriousInventor.com


.015" solder next to .02" spaced surface mount leads and a thumb tac.
© 2007 CuriousInventor.com

How much solder do I really need? An ounce? A pound? How long will a pound last?

To get a very approximate feel for just how much solder is in an ounce vs. a pound, I measured how much .032" solder it took to attach ten 16 pin DIPs. Trying to provide an upper bound, the soldering is excessive, and a generous glob was placed on the tip in between each chip to account for solder used to tin and protect the tip during normal use.


10 16 pin DIPs took about 15 inches of .032" solder, or about .052 oz
RadioShack
RadioShack
© 2007 CuriousInventor.com

The ten chips took about 15" of generously applied .032" solder that weighed in approximately at .052oz. This particular solder weighed about .00348oz/in. At about 3.27e-4 oz/joint, a 1 oz spool should last 3060 joints, a half pound should last 25 thousand joints, and a pound should last about 50 thousand joints. Mileage will certainly vary with different sized solders, joints, tinning wires, and highway vs. city driving, but if you're not in a production environment, a half pound should last a while.

Solder Fumes:

What is exactly in solder fumes? Am I safer using lead-free solder?


Flux from rosin-cored solder boiling under magnification
© 2007 CuriousInventor.com

Lead boils at over 3000 °F, and in most cases soldering tips should be kept below 750 °F, so it is highly unlikely that gaseous lead is present in the fumes. The fumes are actually from the flux boiling, which still isn't great for you--many of the chemicals found in cigarette smoke are found in flux fumes: formaldehyde, toluene, alcohols, and hydrochloric acid to name a few. Most of the public health literature indicates that asthma is the major health risk from soldering fumes (not cancer or lead poisoning). When acquired, it is permanent and can cause hyper sensitivity so that even small amounts of fumes bring on attacks. Surprisingly, scientists have not been able to determine what exactly in the fumes cause the health defects, nor what amounts are harmful. Yet, the British health department has set exposure limits of .05 mg/m^3 over 8 hours and .15 mg/m^3 over 15 minutes. I believe these limits have been shown to provide a safe work environment and also one for which the necessary systems / filters are financially reasonable.

Some informative links:

- Solder Fumes and You A British health department pamphlet explaining the health hazards of rosin-based flux fumes (irritation, headaches, dermatitis, asthma) and what precautions employees and employers should take. Note the total lack of any mentioning of lead poisoning.
- Workplace Exposure to Rosin-based Solder Flux Fume During Hand Soldering A study done by the UK Health and Safety Laboratory measuring exposure levels and also the effectiveness of various exhaust, ventilation, and filter systems.
- Measurement of the Performance of Air Cleaners Against the Particulate Element of Rosin-based Solder Flux Fume Another UK Health study investigating the effectiveness of various fume extraction and filter systems. Most interesting finding: although activated carbon filters can remove gaseous hazards, they are largely ineffective for fine particulate in the fumes which they believe to cause much of the harm. Some combination of carbon and HEPA filter is needed, and even these are useless without sufficient air flow.

Returning to the topic of lead, it is widely agreed that eating, smoking and drinking without first washing is the greatest risk factor. Despite the high boiling point of lead, there is also agreement that at least a small amount of lead particles are indeed present in the fumes. The conspicuous lack of emphasis on lead poisoning in all the research done by the UK health department implies that these particles are of little concern. Sentry Air Systems has a brief page that is one of the very few sources I found to claim that lead particles under normal soldering conditions are harmful. The company sells fume extraction technology.

The material safety data sheet for Kester #44 cored solder says under the fire fighting section: "Melted solder above 1000 °F will liberate toxic lead and/or antimony fumes."

According to IPC's DVD-11, "General Safety in Electronic Assembly," when solder is heated past 850 °F the lead can become atomized and end up in the fumes. video link (if link breaks, you may have to search for DVD-11 at www.ipc.org).

Useful comments from someone in the manufacturing world regarding lead.

It would seem that, for typical lead-based, rosin cored solder, the risks are probably not that great from the fumes if you only solder occasionally, don't use abnormally high temperatures, and are in a well ventilated area. If ventilation isn't too good, and you're soldering for long periods of time, the cheaper foam-type carbon filters may not be good enough.

But what about lead-free solder? Lead-free solder often requires higher temperatures and more active fluxes, and both of these factors lead to significantly worse fumes.

Fume Extraction Becomes More Important in a Leadfree Environment - from the Weller blog

Another excellent article on the increased risk of lead-free fumes from OK International.

Instructables has all sorts of home-made fume extractors.

Prepare the Work



- **Start with clean components:** Flux can remove small amounts of oxides, but will be of little help for heavy oxidation, grease, oil or dirt. Notice how the solder in the adjacent picture has been repelled by the heavily oxidized pin. It may be necessary to lightly use steel wool or fine grit sand paper to remove especially bad oxides. Some people say that you should not do this because it creates scratches that can promote future oxidation... sand at your own risk. Use Silicon Carbide sandpaper (black) as opposed to Garnet (brown, for woodworking) sandpaper because the Garnet paper will shatter and become embedded in the metal. An effective and gentle alternative is to use a pink eraser, especially for copper traces.
- **Clamp your work:** PanaVise makes a popular clamp that accepts several different attachments for holding different sized circuit boards. It's by far the most popular clamp and is also very sturdy. Having the work held in place is especially helpful for desoldering when it's necessary to push or pull a bit. The alligator hands are a cheap alternative.



- **Wire preparation:** Tin stranded wires so they don't "bird-cage," or bend out from their original lay. Expand for instructions on the correct way to strip a wire manually, use an automatic stripper, and tin wire.

- **Manual wire stripping:** The natural way you would think to use the wire strippers is to first cut the insulation, and then use the same cutting hole to push off the insulation slug. In production environments where reliability is critical, this is not allowed because it's very easy to nick the wires this way. The pliers at the tip of the stripper are actually meant to remove the insulation slug. First score the insulation with the cutting hole, and then pull it off with either the pliers or by hand. If removing by hand, twist slightly while pulling to keep the strands in place. This is the "right" way to strip a wire, if you're careful, pulling the insulation off with the cutting hole is probably fine.



- **Automatic stripping:** With one squeeze these cut and pull off insulation.



- **Tinning:** Just like soldering a joint, the key here is to apply solder to the wire, not the iron tip. If the wire is hot enough to melt the solder directly, then it's hot enough to form a good bond with the solder. Hold the iron against one side of the wire and apply a small amount of solder in between the tip and wire to form a heat bridge (if there isn't already enough solder from tinning the tip). Now apply solder to the opposite side. The solder should wick into the strands. Move the iron and solder as necessary to coat the surfaces. You should still be able to clearly see the individual strands when it's complete.

  Don't tin wires that are going to be held in clamping terminals since the solder will slowly deform under pressure and cause the connection to come loose.



  Got a lot of tinning to do? For under $300 you can get a vat of molten solder to speed up the process. The only catch is that there's no flux in the vat, so you need to dip the end of the wires in liquid flux before dunking them in the molten solder. Only dip the very end of the wire in the flux; capillary action will draw it further up the strands. If you dipped more than just the end into the flux, the capillary action would draw flux beyond the insulation where it can't be cleaned, and would eventually corrode the wire.


© 2007 CuriousInventor.com
3. Dunk wire 3/4 in to avoid drawing solder under insulation
1. Scrape back dross (oxides)
2. Dip tip in flux



- **Insert, clinch and trim components:** First, make bends *before* inserting the components. Avoid stressing the connection between lead and component by bracing the lead with pliers while bending. Pliers with serrated tips aren't used in high-reliability production because the grooves can create nicks in the leads that eventually cause a break after a lot of vibration and thermal changes. Round nose pliers make it easy to make any sized radius.

  Unless the component has a metal casing or needs clearance for air flow to keep cool, insert it until it's flush with the board. This doesn't apply to some transistors, and also capacitors that have plastic coverings that need to be kept out of the solder joint. Clinch or bend out the leads so the component is held in place during soldering, and finally trim the leads to about the radius of the pad. Trim the leads before soldering since doing so afterwards can shock and crack the joint. Wearing safety glasses for this process is not at all excessive--those leads can get you. Everything else about proper component installation: NASA guide.


locate bends
prebend leads
clinch leads
trim with flush cutters
© 2007 CuriousInventor.com
clinch opposite DIP corner leads
round nose pliers
flush cutters

- **Add heat sink:** Some semi-conductors (some transistors and diodes) are especially heat sensitive. This clip acts a heat shunt to keep the transistor protected.


© 2007 CuriousInventor.com

Clean and tin the Tip



- **Regular cleaning = easier soldering and longer tip life:** The iron tip's ability to transfer heat is drastically reduced when it gets covered in oxides and burnt flux residues. Not only does heat not transfer as well through this debris, but the contaminants also prevent solder from wetting or sticking to the tip. Most heat transfer actually goes through a fluid solder "heat bridge" that lies between the iron tip and components, so an iron tip that repels solder will be very ineffective.

The longer oxides and charcoaled flux residues remain on the tip, the harder they become to remove, so it's a good idea to clean the tip every time you pick up the iron.



Wiping the iron on an edge of a hole cut into a sponge can help to remove oxides easier, and also allows waste to fall away. A dry cleaner can also be used. It consists of soft metal shavings that are coated with flux. You clean by thrusting the iron into the shaving a few times. By avoiding the thermal shock of touching a damp sponge, these cleaners help to increase tip life, and in our opinion, do a better, faster job.


HAKKO 599B
TIP CLEANER
© 2007 CuriousInventor.com

Usually touching the tip with rosin-cored solder will supply enough flux so that oxides can be removed with a damp sponge. If this isn't sufficient, you can purchase "tip tinners and cleaners" that are a mixture of solder paste and flux. The flux is oftentimes stronger (more activated) to help remove oxides.


64-020
RadioShack
Tip Tinner and Cleaner
WARNING: KEEP OUT OF REACH OF CHILDREN. Read carefully other warnings on back of card.
0.5 oz. (14.2gm)
© 2007 CuriousInventor.com

Finally, when that doesn't work, special polishing bars to can be used to salvage extremely bad tips. Another last resort is to gently rub the oxides off with an emery cloth or soft steel brush. Cover the tip immediately with solder after cleaning to prevent further oxidation. Never file the tip to clean it or form a different shape. The tips are mostly copper with a protective iron plating, and once that plating is pierced, the tip will die quickly. Copper is used because it's an excellent heat conductor, but if exposed to solder, it will quickly dissolve into the solder.

Weller
WPB1
POLISHING BAR FOR SOLDERING TIPS

© 2007 CuriousInventor.com

Tin the tip: Add a small amount of solder back onto the tip. This helps to protect the newly cleaned and exposed tip, and also helps to transfer heat to components.

Heat and Solder the Joint

- **Heat the joint:** Place the iron tip so that it touches both the component lead and pad--the goal is to get as much surface area contact between the iron tip and joint as possible. Almost no heat will travel through the point.


Wrong - heat transfers through tip surface, not point
Good conical tip placement
Good chisel tip placement
© 2007 CuriousInventor.com

- **Make heat bridge:** Add a small amount of solder between the tip and the work--heat transfers much faster through the liquid solder than dry surface contact. This is why a tip that won't "wet" is so difficult to use. Pressing hard should not be necessary. This step may not be necessary if there's enough solder already on the tip from tinning it after cleaning.


Solder heat bridge
© 2007 CuriousInventor.com

- **Apply solder to opposite side:** Apply solder to the parts, *not* the iron. By doing this, you ensure the parts are hot enough for the solder to "wet" and bond with them. Also, solder will run towards the heat source, so applying solder opposite from the iron helps to spread it out and cover the joint.

  For larger joints, rather than dumping in all the solder quickly, continuously pulse in small amounts to keep a fresh supply of active flux available.


© 2007 CuriousInventor.com
Add solder opposite to iron

- **Time:** The joint should take about 2-5 seconds total time for standard 60/40, 63/37 lead based solder and a non- no-clean flux, and up to 7 seconds for lead-free solder. Lead-free solder just takes longer to "wet" the metal.

  Wetting is how easily and quickly solder spreads out over a surface. A water droplet on a freshly waxed car shows poor wetting, as does solder on a heavily oxidized soldering iron tip. It basically comes down to how attracted the liquid molecules are to each other verses the surface (see surface tension). In industry, tests are done to determine the "solderability" of materials by measuring the time it takes solder to spread out over a surface, or measuring how much force a pot of liquid solder will pull down on a component partially submerged.

Good pictures and description of wetting and surface tension. Contains a video of a razor blade floating on the surface of water until a drop of soap is added.

A brochure for a solderabiliy testing station. Scroll down a few pages to see some great pictures of this machine holding one lead of a surface mount chip in a drop of solder.

Another related wiki: wiki/Surface_energy

In general, the goal is to make the joint as quickly as possible. Longer times can char and damage the board, lift pads, overheat components, burn off and polymerize flux (making it harder to remove), and finally lead to a more brittle joint. Solder doesn't just freeze on a joint, tin in the solder dissolves and chemically reacts with copper in the connection to form a new bonding material, called an "intermetallic layer". While this layer is what makes an excellent thermal and electrical bond, it is also extremely brittle; a doubling of its thickness reduces joint tensile strength by half (ref 1). Since this layer grows faster with higher temperatures, joints should be made using the coolest temperature and shortest soldering time possible. This layer is also why re-heating joints has been shown to weaken them. Having said all this, I have to admit that I don't know just how long is *too* long for projects that don't need to operate for 30 years with 100% reliability. After 10 seconds there's a good chance the flux has been used up.

- **Remove solder, then iron:** Pull the iron out fairly quickly to avoid leaving a solder spike.

© 2007 CuriousInventor.com

- **Good and bad joint gallery:** The solder should smoothly ramp to meet surfaces and be shiny in appearance if it's lead-based. Lead-free solder will have a duller and grainier surface, but will still be a good joint as long as there are no signs of non-wetting. The important thing to look for is any solder that looks like it didn't cling to a surface, or is just sitting on top or next to a surface.

Gallery of joints:

A NASA gallery of every possible joint / board defect you could ever imagine. Here's another great gallery of defects.

Great comparison pictures between lead-based and lead-free joints. p. 34

Good joints:


© 2007 CuriousInventor.com

Great joints:


© 2007 CuriousInventor.com

What's the right amount? A large amount of solder is not needed, just enough to cover the pad and lead without any gaps (actually, only 270° is required by IPC J-STD-001). The measure for too much solder is whether or not you can see the outline of the lead in the solder. This is important because you need to be able to see whether the solder adhered or "clung" to the lead (indicating a true bond), and didn't just freeze around it. This applies to all types of joints: tinning wires, soldering to connectors, surface mount components... the solder should never completely hide the underlying wires or leads.


Ideal amount
Almost too much
Too much
© 2007 CuriousInventor.com

Disturbed joint (bad): If the component moves during solidification, the internal structure of the solder will have fractures, leading to a high resistance or unreliable electrical connection, as well as a fragile mechanical one. The solder also appears dull and grainy--typical signs of a "cold" joint that doesn't actually bond with the underlying surfaces.

"Cold" joints are often formed when the underlying pad or lead didn't get hot enough for the solder to wet it.


Disturbed and "cold" joint--component moved during solidification
© 2007 CuriousInventor.com

Awful joints:


© 2007 CuriousInventor.com
Extreme over-heating and pad lifting
No adhesion to lead--oxidized lead
Resting on and not adhering to pad--insufficient pad heating
Solder resting on pad, not adhereing
Solder was applied to iron first and then transfered to joint

Clean Up

Most manufacturers will clean off residues from any flux that isn't labeled "no-clean," despite flux datasheets like Kester's that say even some of the more active fluxes do not need to be cleaned. For short life-span hobby projects, it probably doesn't matter unless you're using a solder/flux labeled "organic" or "water-soluble"--these fluxes leave behind very aggressive acids that will quickly eat away circuits. Cleaning may be necessary if you're applying a protective coating that won't adhere to flux residues. Finally, some rosin residues are tacky and may attract dust that can short a circuit.

The fact that a flux is made from rosin doesn't tell you much about how strong it is or whether it should be cleaned. What matters is how concentrated the mix is and how much acidic (halides) activators were added. RadioShack® doesn't supply any information on the flux in their standard rosin-cored solder, but it's probably weak enough that the residues do not need to be cleaned off.

Isopropyl alcohol works decently on rosin-based residues, but clean shortly after soldering because the residues quickly harden. Use water for water-soluble fluxes. This pump containing bottle dispenses a little alcohol when you push down on the top with a brush, and keeps the rest from evaporating. If you are going to clean, make sure you wipe up the remnants with a lint-free cloth--don't just spread them around the board with a brush and alcohol.


Clear flux residue
Charred flux residue
Cleaned joint
© 2007 CuriousInventor.com
I.P.A. ALCOHOL
CAUTION DO NOT!
U.S.A.
Pump bottle dispenses alcohol when pressed, keeps rest from evaporating.


© 2007 CuriousInventor.com

Desoldering

The three most common inexpensive ways to remove solder include a "solder sucker", solder wick, and an iron with an attached desoldering bulb.


SODER-WICK
Chemtronics
CAUTION
© 2007 CuriousInventor.com

- **Solder Sucker:** To use, press in the plunger, heat up the joint, and as quickly as possible, pull out the iron, place the sucker's nozzle over the joint and press the release button. It may take a few iterations to clean out a joint enough to wiggle free a component. On plated through holes it may actually be easier to add *more* solder to the joint before sucking, since the sucker won't be able to create a vacuum with too little solder remaining.


© 2007 CuriousInventor.com

- **Desoldering Iron:** This works just like the solder sucker, but is much easier to use because there's no race to suck out the solder before it freezes, as with the "solder sucker".


© 2007 CuriousInventor.com
RadioShack

- **Solder Wick (desoldering braid):** The above two tools will often not be able to completely remove all the solder. Many people use the sucker devices above to remove most of the solder, and then get the rest with solder wick, which absorbs solder through capillary action. It's a fine weave of copper wires that are coated in flux. Place it over a joint and then heat from the opposite side with a soldering iron. It may help to have a bit of solder already on the iron's tip to speed heat transfer.


© 2007 CuriousInventor.com

Surface mount desoldering: Surface mount chips are especially hard to desolder because it's very difficult to completely remove all the solder pin by pin, and avoid overheating the board and lifting a pad. Professional shops use expensive hot air guns or special tips (shown below) to heat all the joints at once.


desoldering a surface mount soic chip
© 2007 CuriousInventor.com
apply flux
apply solder to tip
contact chip
lift off

There are fortunately a few cheap ways to desolder surface mount chips.

- ChipQuik provides an interesting solder that when melted over existing joints produces a new low-melting point alloy (under 200 °F) with a much longer solidification time. The longer solidification time enables you to melt all the joints at once and then flick off the chip.
- There are many guides for making a DIY hot air gun with the RadioShack® desoldering iron and a fish tank air pump. Engadget has one of the better how-to guides. Here and here are some more plus the supposed original.

The Ersa soldering primer

Soldering made easy



kurtz ersa

Soldering – a never-ending story

for more than 5,000 years already

Man had scarcely learned how to use metals for his purposes when the desire to join them arose in him. Many of the pieces of jewelry, tools and weapons we know from the Bronze Age owe their usefulness and beauty to the art of soldering.

Today, it is difficult to say who first discovered how to "glue" metals. One thing is certain - the goldsmiths of ancient Egypt knew how to join gold and silver already more than 5,000 years ago. Their colleagues in Troy were also master craftsmen long before the ancient Teutons could even dream of such handicraft. Soldering really "came of age" when tin was discovered as a joining metal. And that was, after all, already 4,000 years ago!

ersa
RDS 80
Power
350
°C
150
300
400

From then on, soldering technology was on its way. It first spread around the Mediterranean. The Cretans showed it to the Etruscans who then taught it to the Romans, Tunisians, Spaniards, followed by many others, including the less developed cultures of the time – the Swiss, Bohemians, Hungarians, Teutons and Scandinavians. From culture to culture, from generation to generation, the craft of soldering was continuously improved and refined.

The ancient Romans already laid down and soldered 400 km of leaden water pipes, conjured up stoves and bathtubs from bronze sheets, not to mention the excellent craftsmanship of their armorers and goldsmiths. Apart from craftsmanship in soldering, our understanding of the science of soldering has grown and has been refined over the centuries.

Today, soft soldering in the electronics industry has developed into a full-fledged production technology, encompassing the fields of mechanics, chemistry, physics and metallurgy. Ernst Sachs, the founder of Ersa (the company name consists of the initial letters of his first and last name) contributed to this development. In 1921 he developed the first electrically operated soldering iron for the industry that was manufactured in series. Since that time, Ersa has committed itself to the further development and perfection of soldering technology with great passion and extending its full power of innovation.

Today, Ersa stands for the most comprehensive product range in the soft soldering technology worldwide and for more than 90 years of industry experience and innovation, know-how and highest product quality.

The Ersa soldering iron product range covers ultra-fine soldering tips, classical soldering irons powered from the standard power net and special soldering tools up to the 550 W hammer soldering iron. Ersa's electronically temperature-controlled soldering stations represent the industry standard, as does the extensive range of rework and



inspection systems, wave-, reflow- and selective soldering systems. The line of Ersa screen printers complements the product range.

Ersa's quality soldering tools are used in the hobby area, such as, for example, in model-making or tiffany soldering, in the craft sector, in laboratories and in industrial electronics manufacturing.



A soldering iron heated up in burning fire: Soldering technology around 1536

New challenges for the soldering technology were raised by the ban on certain hazardous substances (RoHS) in 2006. Since 1 July 2006 electric and electronic equipment may not contain any lead, mercury, hexavalent chromium, PBB (Polybrominated biphenyls) or PBDE (Polybrominated diphenyl ethers).

In many cases this restriction entailed having to depart from the use of the well-known soft solders based on tin and lead.

By publication of this small primer, Ersa would like to facilitate your entry into the "World of Soldering", and raise your enthusiasm for a modern technology with a long history.

Content

	Page
The history of soldering	2
The art of soldering	5
What is needed to solder?	6
Health	9
THT soldering	10
SMD soldering	13
BGA soldering / rework	16
Miniature and microsoldering irons	18
Universal soldering irons	19
Standard, hammer and high-speed soldering irons	20
Power and gas soldering irons	21
Soldering stations	22
Multifunctional soldering and desoldering stations	23
Hybrid rework station	26
Solder fume extractions	27
Tiffany soldering	28
Accessories	30
Seminars, references	31



Solder joints hold the world together

Connecting pacemakers and solar parks

To imagine today's world without soft soldering is not possible. It is the means to fabricate safely functioning, electrically conducting connections. Regardless of whether we talk about power technology, drive technology, telecommunications, automation or electronic controls – in all those fields soldered connections have a decisive share that everything functions in a way as has been foreseen and planned by the developers and visionaries of the products. Today, soft soldering is such a common place occurrence, that no one wastes any further thought on it. We take the daily use of our computers, mobile phones and play stations for granted, the modern comforts provided for by electronics found in modern automobiles is expected as a matter of course, and we fly – privately or on business – to the farthest spots in the world.

Consequential damage because of the failure of a solder joint in an iPod is relatively limited. It is a different matter altogether, though, if the electronics in an airplane full of vacationers, in a space shuttle, or in an implanted pacemaker fails.

Such failures are immanently life-threatening. But not to worry – the highest quality demands apply for those applications, and rightfully so!

Aside from soldering in consumer electronic products, there are numerous other applications such as, to name but a few, alternative power generation with wind turbines or solar parks, R&D departments and in work performed by craftsmen such as electricians and plumbers. Let us not forget the many part-time and hobby users for whom there are no limits curtailing their phantasies and artistic freedom when handling a soldering iron and solder.

The art of soldering

What's behind it?

In a soldering process two metal parts are joined by means of a molten metallic bonding agent (solder), whereby the melting point of the bonding agent is always lower than that of the metal parts to be joined. If the melting point is below 450 °C, then it is a soft soldering process, if it is above, it is called hard soldering or brazing. Welding, on the other hand, is the process where two metals will be heated up to their melting point, at which time they will, together with a filler material, form a pool of molten material causing coalescence. In soft soldering, the seams between the metals to be joined will be filled with a tin alloy. It is important that the alloy does not simply stick to the foreign metals' surface after cooling but unites with the metal. For this purpose, a small quantity of the foreign metals must dissolve and unite with the tin alloy forming a mix of crystals – the so called diffusion zone. That is the task of the tin, whereas the alloy's other components are responsible for the solder liquefaction and the joint's mechanical stability. A solder joint consists of the following layers:

① Base metal
② Diffusion zone
③ Solidified solder
② Diffusion zone
① Base metal



Cross section of a solder joint



The prepared parts and the solder are heated



The liquid solder flows into the gap and fills it



The solidified solder joins the parts together

To achieve the highest mechanical stability, i.e. to assure the durability of the solder joint, the diffusion zone may neither be too thick nor too thin. Its ideal thickness is 0.5 µm. The formation of the diffusion zone depends on the temperature, the solder time and the alloy used. If the diffusion zone is too thick, the solder joint will be brittle and porous, whereas the formation of a zone which is too thin indicates that an insufficient connection or no mechanical connection at all has been formed.

Reaction of the flux during manual soldering on a PCB using flux cored solder wire



What do you need for soldering?

The basics – the 5 essential factors

1. The soldering iron

to provide the heat required

Heat is required to melt the solder. This is the soldering iron's job.

Temperatures of 200 °C – 450 °C are required depending on solder joint and solder alloy. In the field of electronics, the usual temperature lies between 250 °C and 375 °C.

In order to have the proper temperature for any soldering application, the soldering iron's thermal output and an efficient heat transfer to the solder joint to be made is decisive. One either selects a soldering iron that performs within the temperature range required, or a soldering station with temperature control is used. Temperature-controlled soldering stations enable the user to work on different applications without loss of solder joint quality, because of the precise control of the preset temperature at the soldering iron tip.

Both the soldering station's registration of the actual tip temperature should be highly precise, and the heating element should be powerful and recover quickly in order to avoid over-heated or cold solder joints.


380 °C
150 W heating element
Sensor actually measures tip temperature near solder joint!
i-TIP for better heat transfer and longer life!



Temperature curve of controlled tip temperature when soldering multiple joints

2. The soldering tip

to transfer the heat from the heating element to the tip


Nickel-plating
The base material made of highly conductive electrolytic copper ensures unhindered heat transfer from the heating element to the ERSADUR LF coating
Chrome-plating prevents corrosion and solder collection on undesirable spots
Iron-plating
ERSADUR LF coating (up to 600 micron) is factory pre-tinned with lead-free solder at working end

Cross-section of an ERSADUR soldering tip, non-scale representation

The soldering tip is the "heart" of the soldering iron and responsible for the heat transfer from the heating element via the solder to the solder joint. Depending on the soldering iron and the application, different types of tips are available. Prerequisites for good solder joints are the correct soldering iron tip shape, perfect heat transfer, a good condition of the tip and a reliable performance over time. In addition, the soldering tip has to convey also the necessary amount of sensitivity back to the operator.

How to take solder joint quality to its peak – ERSADUR long-life soldering tips

Traditional soldering tips are made of copper which conducts heat well and is inexpensive, but the tip oxidizes heavily when heated and releases copper particles into the solder until it has been "corroded" entirely. To maintain the tip in operational shape, it requires intensive care. Today, only coated soldering tips are used in electronics production – the largest field of application for soft soldering.

ERSADUR long-life tips have been conceived for continuous operation and for high-quality results. They are galvanically plated with an iron coating and protected against corrosion and oxidation by an additional chrome layer in a very special manufacturing process, developed and used exclusively by Ersa. And their perfect thermal conductivity protects the heating element from overheating and premature wear. Ersa offers a comprehensive range of soldering tips for the diverse requirements.

Proper tip care increases tip lifetime considerably:

- Never clean the long-life tip before putting the soldering iron into its holder, since the solder remaining on the tip prevents oxidation of the solder track.
- Always keep the long-life soldering tip covered with solder, as otherwise it becomes passive and will no longer wet properly.

Passive tips can be reactivated by the application of the lead- and halogen-free Ersa TIP REACTIVATOR. All that is needed is to wipe the hot tip on the surface of the regeneration compound. Furthermore, the hot tips should regularly be cleaned with a moist viscose sponge before soldering. Alternatively the tips can be dry cleaned using the Ersa "dry sponge", a sponge made of special metal wool. Dry cleaning has proven to be advantageous in lead-free soldering. The soldering tips are not cooled abruptly, and contaminated tips resulting from dirty sponges are avoided. Due to the slightly abrasive properties of the special wire mesh, passive layers that accumulated on the tip can easily be removed. Tip life is thus increased considerably in lead-free hand soldering.

Ersa TIP REACTIVATOR. A comprehensive range of accessories is available at ***www.ersa.com***

What do you need for soldering?

The basics – the 5 essential factors

3. The solder

for the connection

Metallic bonding agents (solders), mostly in the shape of a wire or a bar, are available as diverse alloys.

Soft solders consisted mostly of a mix of tin (Sn) and lead (Pb). Since the implementation of the RoHS directives on 01 July 2006 the use of solders containing lead is prohibited. Lead-free solders are usually alloys containing silver (Ag) and copper (Cu).

The alloy's composition determines melting temperature and physical properties of the joint. Criteria for the choice of an alloy are: production process, specification of the product, field of application, cost of the alloy.

Prerequisites for good soldering results are:

- Suitable soldering iron
- Clean surfaces of where to solder
- Sound soldering tip
- Suitable fluxes
- Suitable solder alloy
- Correct soldering time



Solder wire with one or with multiple flux cores

4. The flux

for the ability to wet

Fluxes are used to attain the best possible bonding between solder and metal. They provide for metallically clean surfaces of the parts to be soldered, remove the oxides as well as other flow-inhibiting contaminations and prevent the formation of new oxides during the soldering process. A difference is made between acidic (as used in plumbing) and acid-free products (as used in electrical and electronic applications). It is most common to use solder wire with one or more flux cores in electronics production, whereas bar solder is the form of choice in plumbing as well as in the radiator and auto body work.

Examples of some common alloys

Alloy	Flux type	Melting point / range
L-Sn60Pb40	EN 29454/1.1.2 (F-SW 26/DIN 8511)	183 °C – 190 °C
L-Sn60Pb38Cu2	EN 29454/1.1.2 (F-SW 26/DIN 8511)	183 °C – 190 °C
L-Sn63Pb37	EN 29454/1.1.3 (F-SW 32/DIN 8511), free of halogen	183 °C eutectic
L-Sn62Pb36Ag2	EN 29454/1.1.3 (F-SW 32/DIN 8511), free of halogen	178 °C – 190 °C
Alloy – lead-free / complying RoHS-WEEE		
L-Sn95,5Ag3,8Cu0,7	EN 29454/1.1.2 (F-SW 26/DIN 8511)	217 °C eutectic
L-Sn96,5/Ag3,5	EN 29454/1.2.3 (F-SW 33/DIN 8511), free of halogen	221 °C eutectic
L-Sn99,3Cu0,7	EN 29454/1.2.3 (F-SW 33/DIN 8511), free of halogen	227 °C eutectic

5. A safe and clean working environment

to ensure quality and health

Safety first, especially while soldering. The VDE and GS emblems ensure the electrical safety of soldering equipment. The use of the VDE sign obligates the manufacturer to monitor production accordance with test guidelines and to conduct tests according to the regulations determined by the VDE testing institute.



Noxious gases develop in every soldering process



Health protection during soldering

- The breathing zone is very close to the soldering process during manual soldering, and the solder is added by hand. Thus there is the danger of contaminated air and hands or items which may have been touched
- Flux vapors can be damaging to the operator's health and should be kept out of the breathing area. Suitable devices for this purpose are solder fume extractions, which extract the smoke and associated vapors from the workplace and remove particles and gases. Modern fume extractions can be programmed to operate only when the soldering process is taking place, thus saving energy.
- One should never eat, drink or smoke in rooms where soldering is preformed. Contaminations which remain on the hands can enter the human organism through food or cigarette smoke.
- Hands should be washed thoroughly after soldering.



Best solder quality

due to the right preparation and correct soldering parameters

Preparation

The most important prerequisite for a good solder joint is absolute cleanliness. Conductor and component must be free of dirt, oil and oxides. They can be removed with solvents or flux.

Prior to soldering ERSADUR soldering tips should be cleaned while hot with a moist sponge or with a metallic dry sponge. Do not file the tip as you would copper tips, because this would damage the protective coating and render the tip unusable.



Wetting the soldering iron tip



Soldering a joint



The selection of the right soldering tip is decisive for good soldering results

Soldering process

The soldering process has three phases: wetting, flowing, and bonding, whereas the working temperature is the most important criterion. It is best to work at the lowest temperature at which the three phases can progress smoothly. This requires some experience. A temperature-controlled soldering station will definitely facilitate this work. Place the tip on the joint to be soldered after cleaning and heat up the joint. Then feed the flux-cored solder wire between the soldering tip and the joint and melt as much solder as is required to wet the complete joint. Then remove the solder wire first and right after that the soldering tip to prevent overheating the solder. Allow the solder to solidify, avoiding any vibrations or jarring during this time.

Soldering time

The soldering process should be completed within 2 to maximum 5 seconds with a correctly dimensioned soldering tip. When soldering electronic components with lead-free solders, experience shows that more time is required. But even here requiring more than 5 seconds is not permissible, and it indicates that either the temperature setting is too low or the soldering iron lacks the necessary power.

30
2
4
6
8
10
12
14
16
18
20
22
24
26
28

Solder joint quality

When the leads of the components mounted on the board are crimped, a good solder joint has been formed when the contour of the soldered lead is still visible. This will not be the case, if an excessive amount of solder has been used to form the joint.

A further quality attribute is the wetting angle. This consideration is based on the fact that good wetting of the pad, discernible through a small wetting angle, has given rise to the formation of a diffusion zone (intermetallic zone). Wetting angles of up to 25º identify a good joint, wetting angles of up to 50º are still tolerable in manual soldering.

Another quality indicator is what the solder surface actually looks like. It should be smooth and shiny, without any porous areas visible. Grainy surfaces indicate either overheating of the solder or an excessive soldering time. Using lead-free solders, especially silver loaded alloys, matt surfaces may form.

The only absolute quality indicator for a sound and strong solder joint is the formation of the diffusion zone. In the diffusion zone, intermetallic compounds of copper and tin are formed, whose presence is the final proof of quality (mixed crystals, see page 5). Unfortunately, the only way to make this zone visible is through a destructive test (sectioning of the joint). If the diffusion zone is too thick, the solder joints have no tensile strength and become brittle. The higher the soldering temperature and the longer the soldering duration, the thicker the diffusion zone will be. Therefore the joint should be made at the lowest suitable temperature and within shortest soldering times.

As soon as the last solder joint has been made, the soldering iron is placed securely into the holder. At this time, the tip should not be cleaned, because the remaining solder on the tip prevents oxidization.

Correct!



Wrong!





Desoldering with a solder wick



Desoldering with a temperature-controlled soldering iron



Desoldering with a desoldering pump

To achieve good results in desoldering, it is essential to select the right equipment. One can choose between desoldering wicks (desoldering using the principle of capillary action), mechanical desoldering pumps or electronically temperature-controlled desoldering systems. These are divided in desoldering systems with conductive heat or those with hot air.

Correct desoldering made easy

The right tool for each application

Desoldering

Reheating is not recommended for repairing a faulty solder joint. It is better to remove the solder and to resolder the joint. When using a desoldering pump, the solder joint has to be heated with the soldering iron until the solder has molten. Then the tip is removed and the desoldering pump is placed on the joint to extract the solder.

Using a heated desoldering tool, the hollow desoldering tip is placed on the joint to be repaired, making certain that there is good thermal contact. Once the solder has molten, it is extracted.

Desoldering is also dependent on proper tip selection. For example, the desoldering tip's inner diameter should be the same size as the diameter of the through-hole or even slightly larger (by max. 0.3 mm, see above drawing). The best desoldering results with least damage to PCB or the components can be achieved with temperature-controlled desoldering irons (also see pages 24/25). Please note that basically it has to be distinguished between the desoldering of through-hole components and the desoldering of SMD components.

Temperature-controlled desoldering iron

Sucking up the old, molten solder remnants with a mechanical solder sucker (desoldering pump)

Some examples of SMD components →



Ever smaller, ever finer

SMD technology, a true challenge

SMD Soldering

SMD technology (Surface Mount Device Technology) is currently the standard process in electronics manufacturing. Ever smaller and highly integrated surface mount components place growing demands on SMD soldering equipment.

Single solder joints, for example on resistors, are made with ERSADUR long-life soldering tips starting with a diameter of 0.2 mm. Fine-pitch connections with a high pin-out, i.e. IC's, are most efficiently soldered with Ersa PowerWell soldering tips.

Ersa PowerWell technology for soldering fine pitch components within seconds



Soldering fine-pitch components

Process guide description













At first glance, soldering fine-pitch components by hand seems to be a tough job. Yet it is easy, with the right equipment at hand:

Insert an Ersa PowerWell i-TIP (1) into the i-TOOL soldering iron (2) and set a tip temperature of 285 °C to 360 °C (depending on the alloy used – tin/lead or lead-free).

Then position the component (3) and fix two corner pins.

Add flux cream (also see page 30) to the pins on all 4 sides. Clean the front and concave portion of the PowerWell tip with a damp sponge or the Ersa dry sponge.

Fill the concave portion with solder to slightly above the rim by melting the solder wire, until a small dome occurs (4). Take care not to add too much solder.

Place the i-TOOL lightly on the flat section of the pins (5), and pull the tip across the pins towards you (6) without exercising pressure.

Repeat steps (4) to (6) to solder the remaining sides.

Good solder joint, sufficient solder and good fillet



Wrong: insufficient solder



Wrong: too much solder





SMD desoldering in 3 seconds – with the Ersa desoldering tweezers

Some examples of different desoldering tip shapes: →



to desolder and remove MELF's



to desolder and remove SOIC's



to desolder and remove QFP and PLCC components

SMD Desoldering

To desolder or rework a damaged SMD component, the suitable tools are required to remove the component from the board. When using desoldering tweezers, it is extremely important to select the proper pair of desoldering tips. After having desoldered the component, the pad has to be cleared of the residual solder (e. g. with a suitable soldering tip and a no-clean desoldering wick). Afterwards the new component can be positioned and soldered. An optional IR heating plate is a very useful addition – particularly in lead-free hand soldering applications.

More comprehensive instructions on SMD desoldering is available in the process description "SMD desoldering" on our website at www.ersa.com. For the soldering and desoldering of BGAs or other high pin-out SMDs, particularly those with hidden joints, we recommend the semi-automatic Ersa rework stations (see page 31).

Solder melting and removal with a desoldering wick



Ersa desoldering tweezers



The compact CHIP TOOL VARIO desoldering tweezers are perfect for precise desoldering of very small SMDs.



A: Component for rework
B: PCB
C: Adjacent component (top side)
D: Adjacent component (bottom side)
AccuTCs: Thermocouples (4 each)
IntelligentIRS: Non-contact infrared sensor
DynamicIR Top: Top IR radiator (4 zones)
DynamicIR Bottom: Bottom IR radiator (5 zones)
RPC: Reflow Process Camera
IRSoft: Control & documentation software
MIC: Microprocessor controls the DynamicIR heating system

Principle of a rework station

Rework or repair soldering

The rework process demonstrated on the example of a BGA (Ball Grid Array)

Rework designates the repair or touch-up of electronic components such as Ball Grid Arrays (BGAs) or SMTs. This chapter describes the process steps for BGA rework:

1. Desoldering the BGA

The rework station heats the printed circuit board from the bottom, whereas the BGA body itself is heated from the top.

The real-time temperature of the component controls the pre-set temperature curve so that all solder joints melt at the same time. Then the vacuum suction cup is placed on the BGA and once all joints have molten the BGA is lifted off.

2. Removal of residual solder, cleaning

Solder remaining on the pads is removed with a soldering iron. To do so the residual solder is coated with flux. Then a flat soldering tip (e. g. 0102ADLF40 or 0102ZDLF150) is moved over the pad without applying any force. The solder adheres to the larger surface area of the tip, thereby levelling off the remaining solder of the connection pads. Flux residues are finally cleaned off (e. g. using Ersa FLUX-REMOVER).

3. Reballing – Reusing the BGA

Desoldered BGA's can be refit with new solder balls and re-attached to the board. This process is referred to as reballing. Residual solder is removed from the BGA by means of a soldering station. Lying on its back, the component is coated with flux first. Then the new solder balls are attached, for example by means of a stencil. These solder balls are heated up to the melting point with the rework station to firmly connect with the BGA body. Now the BGA is ready to be re-attached.

4. Application of flux or solder paste

The component and the connection pads are now fluxed, or, as the case may be, solder paste is added through stencil printing. The type of technique applied depends on the application, components and the skill level of the operators. For the commonly used PBGA's the application of flux is mostly sufficient.

5. Placing the component

Once the pad has been prepared, the component has to be placed. Since all solder joints of a BGA are hidden under the component body, a component placement unit is required. Successful visual placement by hand requires an operator with extensive experience and excellent skills. If the component is placed on solder paste deposits, great care has to be taken not to squash the solder depot, since doing so may lead to shorts after soldering.

6. Resoldering the BGA

The component is heated to the melting temperature of the solder alloy used via a controlled temperature curve. The heating continues until all solder joints have melted and remained so for some seconds. During this time durable and lasting solder joints are formed. After resoldering, the board is cooled in a similar fashion as had been done after desoldering.

These process steps are generally applicable for all surface mount components. Subject to the type of connections (wired, hidden) they may slightly vary.

Rework – Repair of high-terminal count IC's
to successfully repair SMT assemblies, the several points must be observed:

- Dimensions and properties of the assembly have an influence on its temperature requirement
- PCB holders and supports keep the assembly flat and prevent warpage
- A gentle and controlled heating process, continuously monitored, prevents damage of components or the board
- Accurate component placement is a prerequisite for a good soldering result
- Operators that are well trained will understand the process and ensure good results

Rework process steps

VIA
VT82C686A
0006CG TAIWAN
12B0N7501

1. Remove BGA

2. Remove residual solder from the pads of the board



3. Reballing – addion of new solder balls

4. Application of flux or solder paste

5. Placement of the new or reballed component

6. Resolder the BGA on the prepared surfaces of the board

Miniature soldering iron

Ersa MINOR S

MINOR S, 5 W

Ersa MINOR S (5 W), a featherweight at 6 g for ultrafine soldering applications

The **MINOR S** miniature soldering iron with a rating of 5 W and a maximum tip temperature of 440 °C is an ideal tool for ultrafine soldering applications on micro IC’s and under a microscope. It can either operate with a 6 V transformer or a 6 V battery.

Besides electronics the MINOR S can also be used in watch repair, in the photographic industry and in dental technology.

Micro soldering irons

Ersa MULTITIP Series

MULTITIP series, 15/25 W

Ersa MULTITIP (15/25 W) internally heated soldering iron for small to medium solder joints

The **MULTITIP** soldering irons are especially short, light and easy-to-handle soldering irons with minimal distance between soldering tip and the handle's front part. They are ideally suited for small solder joints. Its internally heated soldering tip provides an enhanced degree of efficiency.

The MULTITIP is available for 15 W and 25 W which makes it suitable for micro soldering joints and medium-sized joints, as for example, on distributor strips or in the hobby sector.

Universal soldering iron

ERSA 30 S, MULTI-PRO, ERSA 15+ and ERSA 25+



The proven **ERSA 30 S,** available with a 30 or 40 W rating, is a very robust and durable soldering iron. Its improved ergonomics is further enhanced by the practical stick-on rubber support disk. This universal soldering iron is designed for multi-purpose use in the crafts, service and hobby sector.

The **MULTI-PRO** with its heat-resistant power supply cord is extremely flexible, as it can be operated with a wide range of different tips. Therefore, it is suitable for almost all conventional soldering applications.

The **ERSA 15+** universal soldering iron is the ideal tool for cost-effective soldering. Internally heated soldering tips guarantee an outstanding performance. The ERSA 15+ can be operated with diverse fine tips of the 832 and 842 tip series. Its ergonomic handle assists in the safe processing of fine soldering joints.

The **ERSA 25+** is perfect for soldering applications with increased heat requirements. The internally heated, larger soldering tips of the 832 and 842 tip series ensure good heat transfer at a high thermal performance. The ergonomic handle provides a safe grip for every soldering application.

Ersa universal soldering irons – for almost all applications

Standard and hammer soldering irons

ERSA 50 S, 80 S and 150 S / ERSA 200, 300 and 550

ERSA 50 S, 80 S, 150 S, 50/80/150 W

ERSA 200/300, 200/300 W

ERSA 550, 550 W

The **ERSA 50 S/80 S** or **150 S** series is designed for applications where a large amount of heating capacity is required, as, for example, on copper conductors with cross-sections of 2.5 mm to 6 mm.

The **ERSA 200, 300** and **550** hammer soldering iron series are particularly suited for sheet metal processing and installation work and for soldering commutators and copper bus bars.
Hammer soldering irons have also proven their merit in leveling applications during body work and lead glazing.

High-speed soldering iron

Ersa MULTI-SPRINT

The **Ersa MULTI-SPRINT** is an ergonomically designed and extremely light-weight, pistol-type soldering iron with up to 150 W power which does not require a transformer. Its PTC heating element, together with the internally heated ERSADUR long-life soldering tip, ensures its exceptionally high efficiency. Due to its very short heat-up time, it is ideally suited for making quick single soldering joints. The MULTI-SPRINT is powered only as long as the button is pressed. Depending on the heat requirement of the solder joint to be made, additional energy can be supplied by periodically pressing the button. The large variety of soldering tips of the 832 / 842 series make the MULTI-SPRINT suitable for more than only the use in repair and service applications.



Ersa MULTI-SPRINT, 150/75 W

Power soldering iron

Ersa MULTI-TC and PTC 70

Ersa MULTI-TC, 75 W

Ersa PTC 70, 75 W

The **MULTI-TC** and **PTC 70** are powerful and robust, temperature-controlled soldering irons. Both tools offer an outstanding heat-up rating.

Due to their high thermal performance, and because of the large selection of soldering tips, the MULTI-TC and PTC 70 are suitable for fine soldering joints in electronics as well as for joints with medium heat requirements. The MULTI-TC is furthermore also used anywhere else where standard irons with 150 W power are in use, including, for example, lead glass and Tiffany soldering.

Gas soldering irons

Ersa INDEPENDENT 75 and INDEPENDENT 130

Ersa INDEPENDENT 75, 15 – 75 W

Ersa INDEPENDENT 130, 25 – 130 W

Ersa gas soldering irons are fueled with commercially available lighter gas and are fired up through the piezo ignition. Compared with electrical soldering irons, the **INDEPENDENT 75** has between 15 – 75 W, and the **INDEPENDENT 130** between 25 – 130 W performance. Both irons are available in the BASIC-SET and PROFI-SET versions.

Aside from handling the usual types of electronic components, the selection of tips available enables the INDEPENDENT to also handle SMD soldering, micro-welding, forming and cutting of synthetic materials and the processing of shrink sleeves.

The basic soldering station

Ersa ANALOG 60

The electronically temperature-controlled ANALOG 60 is Ersa's basic soldering station model. It has the tried and proven RESISTRONIC temperature control technology with the PTC heating element serving as the temperature sensor. The high heat-up rating of 190 W guarantees the immediate supply of heat and a heat-up from room temperature to 280 ºC within 60 seconds. The BASIC TOOL 60 soldering iron uses the internally heated ERSADUR long-life soldering tips of the 832/842 series and provides very high performance.

Due to the wide range of 832/842 soldering tips, the Ersa ANALOG 60, which is also available as an antistatic version, covers a wide range of applications with the most varied soldering requirements.

Digital soldering station

Ersa RDS 80 – high performance for low cost

The digital soldering station Ersa **RDS 80** offers the proven and tested Ersa RESISTRONIC temperature control technology with a strong heating power of 80 W. The ceramic PTC heating element (Positive Temperature Coefficient) acts as the temperature sensor in this control system. Due to its very high ramp-up capability of up to 190 W, the station reaches operating temperature very fast.

RT 80: sleek soldering iron with a large selection of soldering tips

Multifunctional soldering stations

Ersa i-CON NANO and i-CON PICO – small, powerful and versatile

ersa
i-CON NANO

The soldering stations **i-CON NANO** and **i-CON PICO**, two models of the i-CON product family, fulfill all the needs of today's electronics manufacturing while requiring minimal space. They are designed for continuous operation in the electronic manufacturing environment as well as for special applications in laboratories and R&D departments.

Due to the simple and user-friendly operating concept, the factory settings provide for a variable adjustment of operating temperature as well as the setting of stand-by time and calibration value.

Further adjustments such as fixed temperatures, power level, interlock and shutdown functions are available with the free PC software and an optionally available micro smart SD card.

micro SD
Adapter
Verbatim
LogiLink

Micro-SD card with SD-card and USB adapter

The concept of the Ersa i-CON stations ensures that each application is processed with the optimal parameters. They stand for the highest level of process safety and quality control at low investment and operating cost.

Ersa i-CON PICO

- Small footprint (145 x 80 mm) – saves valuable space
- Antistatic as per MIL-SPEC/ESA (only i-CON NANO)
- Three fixed temperature settings or continuously adjustable temperature settings from 150 °C to 450 °C
- Three selectable power levels
- Ultra-light and ergonomic soldering tool with max. 80 W power
- Wide range of low-cost exchangeable long-life soldering tips
- Automatic stand-by and sleep function for low energy consumption and longer tip life
- Password interlock for maximum process control
- Calibration function for a precise tip temperature
- Complete parameterization through PC software and Micro-SD card

High-end soldering and desoldering stations

The Ersa i-CON product family for highest productivity and process safety



Ersa *i*-CON2 with *i*-TOOL and CHIP TOOL

The stations of the i-CON product family are Ersa's innovative solution for intelligent manual soldering. The need to be able to cope with higher working temperatures and with progressively smaller process windows when working with lead-free solders, poses no problem whatsoever for the i-CON product family.

The i-CON is available as a single station or as double iron station. The single station **i-CON1** is delivered together with the i-TOOL soldering iron. The i-TOOL is extremely small, ultra-light and ergonomic. It is powered by a 150 W micro heating element, which realizes short heat-up times (within 9 seconds up to 350 ºC!) and rapid heat recovery.

The microprocessor which stores the temperature calibration of the iron is located in the PCB which is installed in the handle. This now allows for each individual i-TOOL to be calibrated independent of the soldering station.

In contrast to the concept followed by the cartridge-type soldering tips, only the tip itself is exchanged at the i-TOOL. The cost-intensive heating element remains.

The double iron soldering station **i-CON2** can be operated either with a second i-TOOL or with the SMD desoldering tweezers CHIP TOOL



Soldering miniature and densely placed SMD components with the i-TOOL and i-TIPS, starting at a 0.2 mm diameter.

i-CON1 with i-TOOL soldering iron with high-performance micro heating element

- i-TOOL soldering iron with 150 W micro heating element technology
- Low-cost exchangeable long-life tips of the i-TIP series
- User friendly “One-Touch” operation
- Three power levels – no overshoot
- Process window and alarms
- Interface to control peripheral equipment on the workplace, such as heating plate and solder fume extraction systems
- Stand-by control for tools, heating plate and solder fume extraction system
- i-TOOL calibration
- Tools for SMT and conventional soldering applications
- Automatic tool recognition



1. *Low-cost i-TIP long-life soldering tips*
2. *i-TIP tip fastener*
3. *High-power heating element (stick-on type, long-life)*

Ersa i-TOOL: The ideal soldering iron – ultra light (only 30 g), ultra short (only 155 mm), and ultra short tip-to-grip (only 45 mm) and extremely powerful.

respectively with the desoldering irons X-TOOL or X-TOOL VARIO.

The CHIP TOOL facilitates safe and quick desoldering, of the smallest chips up to large PLCC's. To remove the residual solder and to desolder wired components – also on multilayer boards – the X-TOOL or X-TOOL VARIO desoldering iron is the right tool.



```
Configuration
 **     E N D     **
 ↑ Tempwindow   010 °C
 ↓ Tempwindow   020 °C
 Processalarm    on

PROCESSWINDOW CONTROL
```

User-friendly controls: quick programming & lock, huge multi-functional display with i-Op controls, menu in 7 languages, online help



High-mass through-hole desoldering with the X-TOOL VARIO

The C-line of the i-CON stations was developed, so that peripheral equipment could be controlled or to communicate with them. Via a serial interface, the i-CON1 C or the i-CON2 C controls the Ersa IR heating plates or the Ersa solder fume extraction systems.

i-CON VARIO 4 multi-channel station with X-TOOL VARIO desoldering iron, i-TOOL soldering iron, i-TOOL AIR S hot-air iron and CHIP TOOL VARIO desoldering tweezers.

Top Tips

i-TIPS for all applications



**Figure with i-TIP tip fastener*

Additional soldering tips for the i-TOOL and the i-CON soldering stations is available on our web site: **www.ersa.com**

Hybrid Rework Station

Ersa HR 100 A – The innovative combination of hot air and infrared radiation

ersa
HR 100
Ad I



The Ersa **HR 100 A** applies the Ersa Hybrid Rework Technology for a safe desoldering and replacement of small SMD components. Its medium wave length IR radiation, combined with a safe stream of hot air ensures optimal heat transfer to the component.

The HYBRID TOOL offers a gentle and homogeneous warming of all sizes of components, from 0201 chips up to 20 x 20 mm SMD's and larger. Exchangeable hybrid adapters target the thermal energy available (up to 200 W) on to the component, all the while protecting neighboring areas and not blowing away or moving adjacent chips.

Its user-friendly handling permits even operators with little experience to safely and efficiently operate the HR 100. More experienced operators, on the other hand, can not only variably adjust the air flow as well as the heat output, but also record and run profiles. A positioning laser whose laser point makes it possible to keep track of the component worked on through the complete process is integrated in the grip of the ergonomic hybrid tool.



Complete system with HR 100 A, IR heating plate, stand for HYBRID TOOL and PCB holder.

- HYBRID TOOL with 200 W heating element, positioning laser integrated in grip
- 3 exchangeable hybrid adapters (6 x 6 mm, 10 x 10 mm and 20 x 20 mm)
- Silent rework fan (below 40 dB)
- Integrated vacuum pump and vacuum pen; tool holder and K-type thermocouple input socket; USB interface; LED display
- 2-channel temperature recording:
  TC & IRS; AccuTC and Flexpoint thermocouple holder
- Tool holder with z-axis height adjustment
- x-y PCB holder (290 mm x 250 mm)
- 800 W IR heating plate with glass cover:
  125 mm x 125 mm IR high-performance heating element
- Rework profile and documentation software Ersa IRsoft

CLEAN-AIR solder fume extractions

Ersa EASY ARM 1 and EASY ARM 2 – protecting environment, health and resources



Ersa EASY ARM 1



Ersa EASY ARM 2

The Ersa **EASY ARM 1** is a compact yet powerful filter unit to efficiently clean the process air at the workplace. Both i-CON1 C, i-CON2 C and i-CON VARIO can be connected to the EASY ARM 1 with an interface cable. The solder fume extraction has three filtration levels to remove noxious gases.

With the solder fume extraction **EASY ARM 2**, Ersa offers the user a further compact and highly efficient fume extraction unit for either one or two workplaces. One or two units i-CON1 C / i-CON2 C / i-CON VARIO can be connected to the EASY ARM 2 via interface cable.

Both EASY ARM systems are provided with a stand-by mode and operate only when the soldering stations they are connected to are being used. The EASY ARM 1 and 2 are easy to install and can be placed very flexibly. Due to their very low noise level, they can be operated in virtually all environments, be it repair shops, development facilities or laboratories.

To accommodate different working conditions and applications, a variety of extraction arms and nozzle shapes which can easily and quickly be exchanged are available to meet different working conditions.

Noxious gases develop in every soldering process.



Q&A 1: So, how can you get rid of them? By using a solder fume extraction unit to clear the air from particles and gases.

Q&A 2: How does that work? Active carbon in the filters absorbs harmful gas molecules; result: a clean working environment.



Tiffany soldering


Soldering tip
Copper foil
Glass
Solder

Step 1: spot soldering


Solder
Glass
Copper foil
Soldering tip
Solder

Step 2: rough soldering

Tiffany or sheet metal soldering

Soldering beyond the field of electronics

Tiffany soldering (Lead glass soldering)

Soldering a Tiffany object generally involves three individual steps:

- Spot soldering
- Rough soldering
- Finishing

Prior to the actual soldering process, copper foil is glued on the glass edges. The next step is spot soldering, i. e. the glass parts are fastened or connected by taking a drop of solder with the tip of the soldering iron and carefully applying it to the solder joint. Each spot soldering operation should only take about a second. During rough soldering the gap between the glass is filled with solder after flux has been applied. For this purpose the tip and solder are moved together along the joint. Always drag the soldering iron, never push it. Only if this procedure is accurately followed, and if a sufficient amount of solder is applied, the desired, half-round and convex seams are achieved. The lack of visual quality of the seam at this stage is optimized during the finishing soldering step, in which the soldering tip is dragged slowly and from the beginning of the seam until the end at an even speed. The seam worked on should always lie flat on the bench.


Solder
The soldering iron heats up the complete overlapped width
Soldering tip
Solder flows into the gap and fills it

Guiding the soldering iron when soldering a broad seam


Solder
Soldering tip

Guiding the soldering iron when soldering a narrow seam

Plumbing and tinsmith work

For the joining of sheet metal and metal pipes, the joints to be soldered have to be bare. This calls for a good prior cleaning.

After this, the flux – either solder grease or solder fluid, a zinc chloride solution – is applied. Then the area to be soldered is heated with the tip of the soldering iron.

Once the soldering area is sufficiently hot, solder is added and the solder gap is filled.

The aggressive flux residues are removed after cooling to avoid the risk of future corrosion.



832 GDLF



832 LDLF



832 MDLF



832 VD

ERSADUR Tiffany soldering tips

The types VD, GDLF, LDLF and MDLF of the comprehensive 832 tip series are particularly suited for Tiffany work. On account of their shapes and their high mass (excellent because of the ensuing heat retention capacity), the seams between the glass parts can quickly and easily be filled with solder. And the ERSADUR finish warrants a long tip lifetime.

ERSADUR Tiffany soldering tips

Ersa DIGITAL 2000A, Ersa MULTI-TC and ERSADUR soldering tips

Tiffany lamp

The **MULTI-TC** soldering iron is very light, robust and powerful. The Ersa SENSOTRONIC Control with the PT-1000 temperature sensor in the tip reacts immediately when heat is withdrawn.

The MULTI-TC is provided with a 2.2 mm wide, chisel-shaped soldering tip. Together with the Tiffany soldering tips, the slim MULTI-TC is superbly suited for the use in Tiffany work.

Due to its precise temperature control, the **DIGITAL 2000 A** soldering station completely eliminates the possibility to overheat any glass components or the copper foil, and the station has tremendous power reserves, making it comparable and putting it on an equal level with unregulated 150 W soldering irons.

The Ersa SENSOTRONIC control with its internally heated soldering tip, where the temperature sensor is mounted directly below the tip, provides for precise temperature control and ensures uniform temperature levels at the soldering joint.

The long-life ceramic PTC heating element provides up to 290 W heat-up rating which means that the powerful soldering iron is ready for use in only 60 seconds.

The DIGITAL 2000 A is provided with a 2.2 mm wide, chisel-shaped soldering tip. Particularly good results are achieved with the optionally available tip versions 832 VD, 832 GDLF, 832 CDLF and 832 MDLF, which are specifically offered for Tiffany applications.

Ersa MULTI-TC, 75 Watt

Ersa DIGITAL 2000 A with POWER TOOL



Ersa tool holders or stick-on rubber supports to safely and ergonomically put down the soldering iron during work stoppages or during heat-up.

Ersa viscose cleaning sponges for moist or special metal wool for dry cleaning of the hot soldering tip prior to the soldering process.

Auxiliary products and practical accessories

Everything for your soldering needs from one source



Ersa solder baths

Ersa solder wire and solder wire dispenser

Ersa DTM 100 temperature measuring device

Ersa desoldering wicks

Ersa tip exchanger

Ersa SOLDAPULLT desoldering pump

Ersa VAC X desoldering pump

Ersa SMD flux and flux cream

Ersa FLUX-REMOVER

Ersa TIP-REACTIVATOR

Further peripherals and accessories can be obtained from your local Ersa distributor and at **www.ersa.com**. Or just ask for our catalog!

IR rework stations

Ersa IR/PL 550, IR/PL 650 and HR 600 – from mobile phone boards up to XXL boards

Ersa HR 600

More than 5,000 customers worldwide use Ersa's patented IR-Rework technology.

Ersa rework stations deploy the DynamicIR Heating Technology, programmable top and bottom heating zones as well as the accurate, user-friendly and motorized "Auto Pick & Place" feature. System control, process documentation and visualization is handled by the Ersa rework software IRSoft/HRSoft.

Optical solder joint inspection

ERSASCOPE inspection systems – the patented original

Since its introduction over 10 years ago more than 3,000 customers worldwide profit from the possibility to non-destructively inspect hidden solder joints.

Regardless of whether the joints are under a flip-chip, or whether areas are to be inspected where other microscopes have come to their limits – the ERSASCOPE technology offers a considerable added value to any quality assurance program!

Ersa Know-How Seminars

Expert knowledge for professional users comprehensively imparted



Today more than ever, cost-effective production and highest quality in the electronics manufacturing industry is the basis for profitable competitiveness. A key ingredient for being competitive is a well-qualified staff, which is up-to-date on current technology and process.

Ersa Know-How Seminars are ideal for transmitting this knowledge to those of your staff members with process responsibility in electronic manufacturing. In these seminars, theoretical and practical knowledge is presented in a neutral fashion in workshops and presentations by reputed experts in their field.

For further information go to our website **www.ersa.com** and click "Events".

Ersa Electronics Production Equipment

Technical data and further detailed information on our range of hand soldering equipment is available in our "Soldering Tools" catalog. This is available in printed form and as PDF, as are the "Rework & Inspection" catalog.



Aside from the extensive selection of hand soldering tools, rework stations and inspection systems for non-destructive inspection, Ersa, as Europe's largest manufacturer of soldering systems, also offers a complete range of selective, wave and reflow soldering systems, as well as stencil printers for the industrial electronic manufacturing industry.

Please refer to our brochures and our website **www.ersa.com** for further information.

Ersa GmbH
Leonhard-Karl-Straße 24
97877 Wertheim/Germany
Tel. +49 9342 800-0
Fax. +49 9342 800-127
info@ersa.de
www.ersa.com

Ersa France
Chevigny Saint Sauveur, France
info-efr@kurtzersa.com

Ersa North America
Plymouth, USA
info-ena@kurtzersa.com

Ersa Asia Pacific
Hong Kong, China
info-eap@kurtzersa.com

Ersa Shanghai
Shanghai, China
info-eap@kurtzersa.com

kurtz ersa

97596 - 02/2015 • subject to changes • © by Ersa GmbH, Germany

Soldering Guide

Safety Precautions

- **Never touch the element or tip of the soldering iron.**
  They are very hot (about 400°C) and will give you a nasty burn.
- **Take great care to avoid touching the mains flex with the tip of the iron.**
  The iron should have a heatproof flex for extra protection. Ordinary plastic flex melts immediately if touched by a hot iron and there is a risk of burns and electric shock.
- **Always return the soldering iron to its stand when not in use.**
  Never put it down on your workbench, even for a moment!
- **Allow joints a minute or so to cool down before you touch them.**
- **Work in a well-ventilated area.**
  The smoke formed as you melt solder is mostly from the flux and quite irritating. Avoid breathing it by keeping you head to the side of, not above, your work.
- **Wash your hands after using solder.**
  Solder contains lead.

Treatment for minor burns

Most burns from soldering are likely to be minor and treatment is simple:

- **Immediately cool the affected area under gently running cold water.**
  Keep the burn in the cold water for at least 5 minutes (15 minutes is recommended). If ice is readily available this can be helpful too, but do not delay the initial cooling with cold water.
- **Do not apply any creams or ointments.**
  The burn will heal better without them. A dry dressing, such as a clean handkerchief, may be applied if you wish to protect the area from dirt.
- **Seek medical attention if the burn covers an area bigger than your hand.**

Preparing the soldering iron

- **Place the soldering iron in its stand and plug in.**
  The iron will take a few minutes to reach its operating temperature of about 400°C.
- **Dampen the sponge in the stand.**
  The best way to do this is to lift it out the stand and hold it under a cold tap for a moment, then squeeze to remove excess water. It should be damp, not dripping wet.
- **Wait a few minutes for the soldering iron to warm up.**
  You can check if it is ready by trying to melt a little solder on the tip.
- **Wipe the tip of the iron on the damp sponge.**
  This will clean the tip.
- **Melt a little solder on the tip of the iron.**
  This is called 'tinning' and it will help the heat to flow from the iron's tip to the joint. It only needs to be done when you plug in the iron, and occasionally while soldering if you need to wipe the tip clean on the sponge.
- **You are now ready to start soldering!**
  Please turn the page for further instructions...

THE
ELECTRONICS
CLUB

© John Hewes 2006, The Electronics Club, **www.kpsec.freeuk.com**
This document may be copied for educational purposes.

Making soldered joints

- **Hold the soldering iron like a pen, near the base of the handle.**
  Imagine you are going to write your name!
  Remember to never touch the hot element or tip.
- **Touch the soldering iron onto the joint to be made.**
  Make sure it touches both the component lead and the track.
  Hold the tip there for a few seconds and...
- **Feed a little solder onto the joint.**
  It should flow smoothly onto the lead and track to form a volcano shape as shown in the diagram below. Make sure you apply the solder to the joint, not the iron.
- **Remove the solder, then the iron, while keeping the joint still.**
  Allow the joint a few seconds to cool before you move the circuit board.
- **Inspect the joint closely.**
  It should look shiny and have a ‘volcano’ shape. If not, you will need to reheat it and feed in a little more solder. This time ensure that both the lead and track are heated fully before applying solder.



Using a heat sink



Some components, such as transistors, can be damaged by heat when soldering. It is wise to use a heat sink clipped to the lead between the joint and the component body, as shown in the picture. You can buy a special tool, but a standard crocodile clip works just as well and is cheaper!

Soldering advice for components

Some components require special care when soldering. Many must be placed the correct way round and a few are easily damaged by the heat from soldering. Appropriate warnings are given in the table on the next page, together with other advice which may be useful when soldering.



© John Hewes 2006, The Electronics Club, **www.kpsec.freeuk.com**
This document may be copied for educational purposes.

Components	Pictures	Soldering advice
Resistors		No special precautions are required. Connect either way round.
Diodes		Diodes must be connected the correct way round: a = anode, k = cathode. Use a heat sink with germanium diodes.
IC holders (DIL sockets)		Ensure the notch is at the correct end. Do **not** insert the IC at this stage to prevent it being damaged by heat.
Presets (small variable resistors)		No special precautions are required. On stripboard take care to ensure you insert them the correct way round.
Capacitors, non-polarised (less than 1µF)		No special precautions are required. Connect either way round. Take care to identify their value.
Capacitors, electrolytic (1µF and greater)	 220µF 25V + axial 10µF 63V - + radial	Electrolytic capacitors must be connected the correct way round, they are marked with + or - near one lead.
LEDs (Light Emitting Diodes)		LEDs must be connected the correct way round: a = anode, k = cathode. Use a heat sink with small (3mm) LEDs.
Transistors		Transistors have three leads and must be connected the correct way round. Use a heat sink clipped to each lead in turn between the joint and the transistor.
Wire links between points on the board		Use tinned copper wire (such as the offcut from a resistor lead) or single-core plastic-coated wire.
Other parts mounted on the board		No special precautions are required for most parts, but make sure they are the correct way round.
Battery clips, buzzers and other parts with wires		Red (+) and black (-) wires must be connected the correct way round.
Wires to parts off the board such as switches		Use plastic-coated stranded wire which is flexible, single-core wire is likely to break at the joint.
Integrated Circuits (ICs or 'chips')		When all soldering is complete, carefully insert ICs the correct way round in their holders. Make sure all the pins are lined up before pushing in firmly.

For further information about electronic components please see: www.kpsec.freeuk.com

THE
ELECTRONICS
CLUB

© John Hewes 2006, The Electronics Club, **www.kpsec.freeuk.com**
This document may be copied for educational purposes.

Desoldering

At some stage you will probably need to desolder a joint to remove or re-position a wire or component. There are two ways to remove the solder:

1. With a desoldering pump (solder sucker)

- Set the pump by pushing the spring-loaded plunger down until it locks.
- Apply both the pump nozzle and the tip of your soldering iron to the joint.
- Wait a second or two for the solder to melt.
- Then press the button on the pump to release the plunger and suck the molten solder into the tool.
- Repeat if necessary to remove as much solder as possible.
- The pump will need emptying occasionally by unscrewing the nozzle.

2. With solder remover wick (copper braid)

- Apply both the end of the wick and the tip of your soldering iron to the joint.
- As the solder melts most of it will flow onto the wick, away from the joint.
- Remove the wick first, then the soldering iron.
- Cut off and discard the end of the wick coated with solder.

After removing most of the solder from the joint(s) you may be able to remove the wire or component lead straight away (allow a few seconds for it to cool). If the joint will not come apart easily apply your soldering iron to melt the remaining traces of solder at the same time as pulling the joint apart, taking care to avoid burning yourself.



Using a desoldering pump (solder sucker)

What is solder?

Solder is an alloy (mixture) of tin and lead, typically 60% tin and 40% lead. It melts at a temperature of about 200°C. Coating a surface with solder is called ‘tinning’ because of the tin content of solder. Lead is poisonous and you should always wash your hands after using solder.

Solder for electronics use contains tiny cores of flux, like the wires inside a mains flex. The flux is corrosive, like an acid, and it cleans the metal surfaces as the solder melts. This is why you must melt the solder actually on the joint, not on the iron tip. Without flux most joints would fail because metals quickly oxidise and the solder itself will not flow properly onto a dirty, oxidised, metal surface.

The best size of solder for electronic circuit boards is 22swg (swg = standard wire gauge).

For plugs, component holders and other larger joints you may prefer to use 18swg solder.

© John Hewes 2006, The Electronics Club, **www.kpsec.freeuk.com**
This document may be copied for educational purposes.

Safety Rules for Soldering

Department of Electrical, Computer and Biomedical Engineering, University of Rhode Island

1. Wear goggles for eye protection. When trimming off leads or excess solder dross, be careful of the flyaway that could injury yourself as well as other people nearby.
2. Work in a well-ventilated area and use a fume extractor. Do not inhale fumes from the soldering processes.
3. Always return the soldering iron to its stand when not in use. Never put it down on your workbench. The soldering iron tip is very hot (about 400°C). Avoid touching plastic, wire insulator, or any flammable material in the working area with the soldering iron. Turn the soldering station to standby or off if not used for more than few minutes. Turn unit off or unplug it when done.
4. Use a third hand, a circuit board vice, pliers, tweezers, or clamps for holding components to avoid burns. Legs and arms should be covered to avoid burns from splashed hot solder.
5. Do not have food or drink near the working area. The solder is usually a tin/lead alloy and lead is toxic. The flux is a chemical used to help metal parts soldered together. It is acidic and toxic. Clean up spilled flux immediately. Wash hands after soldering. Flux can cause acid burns to the skin or damage clothing. In case of acid burns, flush immediately with water.
6. Wash hands thoroughly after handling flux and solder containing lead. Use lead-free solder whenever possible.
7. Clean up the area when finished. Discard lead and silver solder and dross in a container with a lid. Label the container: “Lead/Silver Solder Waste for Recycling”. Used solder sponges and contaminated rags must be disposed of as hazardous waste.



Soldering Techniques

1. Basic tools include an electric soldering station (a temperature-adjustable type preferred), solder, a pair of needle-nose pliers, a wire stripper, a flush cutter, a desoldering bulb, a utility blade, and a third hand or a vice.
2. Workspace should be as uncluttered as possible. Clear the path between the soldering station stand and the project to be soldered.
3. Prepare the soldering iron tip. Scrape off oxides with a utility blade if necessary. Adjust to an appropriate temperature. It won't work if you can't get the solder melt onto the soldering tip. Tinning the soldering tip by coating it with a thin coat of solder. This helps heat transfer between the tip and the components. The cleaning sponge should be soaking wet. Quickly run the soldering tip over the wet sponge to get rid of excess solder.
4. Clean the contact surfaces of the metal parts if necessary. Scrape off oxides with a utility blade. In some cases, it is easier to tin the individual components first before joining them.
5. Position the components using a third hand or a vice. Avoid holding the metal part of a component with your fingers.
6. Timing is important for soldering the components together. The solder needs to be completely melt at the joint to avoid a “cold solder point.” However, too much heat could damage a sensitive electronic component or melt the insulator of a wire. The required time depends on the heat transfer, which is affected by the temperature of the soldering tip, the mass of the components, the presence of flux or rosin, and how clean the contact surfaces are.
7. Start over when an attempt fails. Old solder has impurities. Remove old solder completely with a desoldering bulb or pump. Clean up flux/rosin residuals. Try again.

Examples: www.leadsdirect.co.uk/technical/perfectsolderjoint.html



Good – clean, shiny, and just the right amount of solder.

Bad – too much solder which is uneven, has sharp points in places, and was probably overheated.

Worse – uneven texture, and the flux remaining on the joint.

Soldering

WSD 81
Weller


SOLDER
INTERMETALLIC BOND
PAD
PC BOARD
©

TABLE OF CONTENTS

page

1. Introduction 1
2. Basic metals 1
3. Flux 1
4. Solder 2
5. Heating, generation of soldering connection 3
6. Soldering with a soldering iron:
    - a) Cleaning surfaces 3
    - b) Temperature & time 3
    - c) Adding solder & quantity 4
    - d) Soldering : 7 steps 5
    - e) Soldering of a Flat-package IC 6
    - f) Incorrect soldering 7
7. Desoldering with warm air and soldering paste 8+9
8. Lead free soldering 10
9. Temperature specifications of the soldering bit 10
10. Types of soldering bits 11
11. Soldering devices 11

SOLDERING

Theoretical background for technicians

1. Introduction :

Progress within the electronics industry would not have resulted in the mass production of electronic appliances as we know them today, without a similar progress in the field of soldering technology.

To be able to understand how soldering techniques are used in the electronics industry, we first have to get familiar with the materials used during the soldering process, and we have to learn how a soldering connection is created on a molecular level.

Soldering is an old technique for creating permanent electrical and mechanical connections between metals. In contrast to ordinary glueing, which makes only a physical connection between materials (although electrically conducting glue also exists) soldering causes a chemical reaction with other materials, creating a new alloy.

There are several soldering techniques, which all have a few things in common: basic metals, soldering flux, solder and heating.

2. Basic metals :

When we place electronic components on a PCB, the legs of the components and the soldering lands on the PCB, are the basic metals that will connect with the solder.
Several metals like copper, bronze, silver and some types of steel react with solder and make a strong chemical and physical connection.
Other materials like aluminium, titanium, etc. are difficult or even impossible to solder.
The fact that materials exist which can not be soldered is very important, as these materials can be used for making soldering machines and soldering irons. These materials can also be used for covering components during soldering.

There is a direct relationship between how strongly the surface of the basic metal oxidizes and how the soldering reacts on this: When there is more oxidation present, the soldering connection will be weaker.
The fact that most metals oxidize very quickly when heated, is a specific problem, because if one wants to obtain a chemical soldering reaction, a high temperature is necessary…
Flux is used to counteract this oxidation problem.

3. Soldering flux :

Although the soldering surface looks clean, there is always a thin layer of oxide on the metals. This layer always arises as soon as the metal is exposed to air. Reliable soldering connections can only be made on "clean" surfaces. "Clean" surfaces could be accomplished using cleaning product, but this would be insufficient as metal oxidizes incredibly fast when heated. To prevent the creation of the layer of oxide, the use of soldering flux is necessary.

Using soldering flux on the basic metals before the soldering starts has various reasons and advantages:

The main reason of the use of flux is to stop the oxidation of the basic metals during heating. The flux makes sure that the air can't reach the soldering surface, and therefore prevents the formation of oxidation during warming up.
Most of the different flux types have acid components which are used to remove the oxidation that is already present on the basic metal.
If a very strong acid is active in the flux, theoretically it would be possible to remove all the oxides. This however is in practice not possible, as the acid would also affect the PCB and the components, which of course is not the intention.

Therefore there will always be a search for the balance between a flux that contains strong acids, and as a consequence also removes the oxidates more effectively (but also affects the PCB), and a flux that contains a less strong acid and therefore removes less oxides. (but does not affect the PCB).

Most fluxes though use types of acid. Therefore it generally is necessary to remove the flux residues after soldering.

When solder is applied, the flux needs to flow off so that the solder can make direct contact with the basic metal. During this process it is however impossible to avoid the flux mixing with the solder.
Flux developers make use of this fact to develop a flux that has the property to reduce the surface tension of the solder on contact, as a result of which better "wetting" arises.

Flux consists of natural or synthetic resin and chemical additives, called activators.
In PEM a "no clean" flux of Tamura is used (for the placement of Flat-Package-IC's). Consequently it is not necessary to remove the flux after soldering.
Furthermore it is not necessary to add extra flux when doing easy manual soldering because the soldering wire contains flux (3.3 %), like a resin core.

4. Solder :

There several existing metals and metal alloys that can be used for soldering.
The choice for using a certain metal is based on the properties of the metal:
Is the metal flexible or fragile? How well does it conduct heat?
Does it expand rapidly when heated? What is the electrical resistance of the metal?
How strong is it? Is it toxic? And not unimportant: what does it cost?
Although it is not perfect, an alloy of tin and lead is most often used traditionally.
Pure tin melts at 203°C and pure lead melts at 330°C. A mixture of both metals has a lower melting point.
By using a different mixture the melting temperature of the soldering alloy can be changed.
A alloy of tin and lead (e.g. 60/40) has a relatively low melting point (183°C) and can be produced at a relatively low price, in comparison to other alloys with similar properties.
Lead is a very cheap and can be found in a lot of places. Therefore the cost of the tin-lead alloy is mainly determined by the cost of tin.

When this alloy is warmed up, it goes through several phases:
the alloy goes from a "fixed" condition, to a "paste" condition (semi-liquid), and finally becomes totally liquid. It is difficult to solder with an alloy that is in a "paste" condition: because there is little movement or vibration during this "paste" condition, this can cause bad soldering.
If the alloy is of 50% tin and 50 % lead, it starts to melt at a temperature of 193°C, and will be totally melted at a temperature of 216°C.

To prevent bad soldering during the "paste" condition, "eutectical" solder is used.
An "eutectical" alloy is an alloy that, when heated, goes immediately from a fixed condition to a liquid condition: the "paste" stage is effectively skipped.
An "eutectical" tin-lead alloy contains 63% tin and 37% lead.
Often a tin-lead alloy with 60% tin and 40% lead is used. This alloy can be produced cheaper than the eutectical solder because it contains less tin. But because this alloy is almost "eutectical", it can effectively be used for soldering.
During soldering, be careful to make no sudden movements whilst the solder is cooling.
This can cause "interrupted connections" and therefore unreliable soldering.
An "interrupted" soldering connection has a rough and irregular surface and appears dim instead of clear and shiny.
It is also very important that no impurities get into the solder.
If small metal particles from the components get into the soldering "cup" of the soldering machine.
This can result in a serious change to surface tension, and consequently bad soldering connections.
These metal impurities could even change the melting temperature of the solder.

5. Heat, generation of soldering connection

If the solder gets in contact with a copper surface, the solder dissolves and penetrates the copper layer.
The molecules of the solder and the copper get mixed and a new alloy is created, consisting partially of copper and partially of solder.
This reaction is called "wetting" and has as a result an "inter-metallic" connection between the components. "Wetting" can only take place if the surface of the copper does not contain oxides. The solder and the surface of the copper also have to be at the right temperature before the "wetting" can take place.





6. Soldering with a soldering iron:

The following 4 factors determine the quality of the soldering connection:

- clean surfaces
- temperature
- time
- quantity of solder

a) Clean surfaces:

"dirt is the enemy of a good soldering connection!"

It is enormously important that there are no impurities on all of the components (including the soldering bit). Soldering on "dirty" components is not possible!
Old PCB's or components sometimes can not be soldered due to a large layer of oxide on the islands and the legs of the components.
In such cases the solder is rejected and goes to everywhere, except for where we want it to go.
In a desperate attempt to solder in such a situation, a common reaction is to raise the soldering temperature. However, this is certainly not a solution. On the contrary!
The only correct solution is thorough cleaning. (e.g. with a brush of glass fibre)

Before the soldering iron can be used, the soldering bit first has to be coated with tin.
Some solder has to be melted onto the bit. Afterwards the bit has to be cleaned.
For cleaning the soldering bit, it is best is to use a slightly moistened sponge (with demineralized water). The use of ordinary tap water is not reccomended, because the silver layer on the bit gets affected by calcium in the tap water, which results in less thermal contact. This diminished thermal contact runs the risk of cold soldering, etc.
To improve the thermal contact between the bit and the soldering surface, it is advisable to coat the soldering bit with a little bit of solder before every soldering action.

b) Temperature & time :

The temperature of the soldering bit is not the most determining factor for successful soldering: the heating cycle (combination of temperature of the bit and the time the heating takes) is!
How fast the soldering components warm up, how warm they get and how long they stay warm, are the most important factors that have to be controlled to make a reliable soldering connection.

The time soldering takes is very important. A soldering task may only take a couple of seconds: when heated too long, the components and the soldering lands can be damaged.

It is also totally wrong to use the soldering bit to rub melted solder across the soldering surface.

Although the temperature of the bit is not the most determining factor, it is advisable to to do soldering at the lowest possible temperature.

The first that has to be examined before the soldering starts in the 'thermal mass" of the components.

Every soldering task has its own specific "thermal mass" which is determined by the heat absorption of the components. For soldering e.g. the component pins and solder lands.
For components on a heat sink there will be a large thermal mass. In other words: the heat will be "absorbed " by the heat sink, as a result of which more warmth will have to be added than e.g. for soldering the leg of an IC.
Secondly it is very important that the temperature of all the components that will be soldered have more or less the same temperature.
An example: it is necessary that the leg and the soldering land have had at the same time the necessary warming up before the solder is added.
We have to take care that, while warming up, the soldering bit gets in contact with both the leg and the soldering land.
"Thermal contact" is therefore very important.



The thermal contact is low
The warmth is transmitted by means of the bit.
to the leg and the soldering land



The thermal contact is higher
by adding a bit of solder
to the point of contact

The size and the shape of the soldering bit, as well as the position of the bit, will determine whether or not it makes a good thermal contact. For being able to make a good thermal contact in all circumstances, different types of soldering bits exist (different shapes).
Normally the soldering bit has to be placed on the "largest mass point" of the soldering connection that needs to be made.
This will make fast heating possible.

c) Adding solder & quantity

The last factor necessary for a high quality soldering connection, is adding the correct quantity of solder.
Too much solder is an unnecessary waste and can aid the formation of "bridges" across legs
If not enough solder is added, this can cause an "insufficient soldering" or "dry soldering"
Adding the correct quantity of solder takes a lot of exercise and experience

Melted solder always flows from a "colder" area to a "warmer" area.
Before the solder is added, the surface temperature of the components to be soldered has to be higher than the melting temperature of the solder.
Never let the soldering wire melt by holding it against the soldering bit. This may cause the solder to fall on a surface where the temperature is lower than the melting temperature
This can result in a cold soldering, with almost no or insufficient "wetting".
If the solder is added to a clean, fluxed and sufficiently heated surface, then the solder will melt and flow nicely without direct contact with the heat source. (soldering bit)
Therefore it is advisable to put the soldering wire on the sufficiently heated surface so that the solder melts as a consequence of the contact with the heated surface



The solder is melted as a consequence of the contact with
the heated surface. No contact with the soldering bit is necessary.

d) Soldering : 7 steps

1. Cleaning of the soldering bit:

For soldering to be effective, the soldering bit has to be clean: no dirt and no oxides are allowed on the soldering bit. The soldering bit needs to be cleaned before soldering.



2. Heating of the components that will be soldered.

For soldering to be effective, the components which have to be connected, have to be heated (in this case the pin and the solder lands) to a temperature that at least equals the temperature of the melting point of the soldering alloy. (183 °C)
Bear in mind the "thermal mass", the type of bit and the position of the bit!



3. Adding the solder:

After both components are heated sufficiently, solder can be added.
Let the solder melt as a consequence of the contact with the heated surface. In other words: don't make any direct contact with the soldering bit.



4. Quantity of the solder to be added and letting the solder flow.

Let the solder flow nicely between both components and add solder until the right quantity is reached.



5. Remove the soldering wire

When sufficient solder is added, the soldering wire may be removed.



6. Remove the soldering bit.

When the solder has nicely flowed open, and there is "wetting", the soldering bit may be removed so that the solder can solidify.
Pay attention for possible sudden movements during this operation. (risk of "disturbed" soldering)



7. Check the soldering connection

Check the soldering connection.
Nicely formed soldering is shining and even. Also pay attention to the shape: a spherical shape is not good!

e) Soldering of a flatpackage IC

For soldering a "Flat-package IC" (gull wing type) one can use, beside the ordinary point soldering (= leg by leg), a special soldering technique: the DRAGGING TECHNIQUE.
For this technique, one must use a special soldering bit that will, after filling-up, act as a kind of "mini-soldering-wave", and with which one can solder a whole row of legs in one ongoing movement



1. Cleaning of the soldering surface:

Remove all possible soldering residues (caused by desoldering) and make all the paths nicely even by going over those paths with the soldering bit. (without adding solder)



2. Positioning of the IC:

Position the IC on the patterns.
This has to be very precise.
A little movement can cause serious problems.



3. Fixing of the IC:

Fix the IC on the PCB, by "temporarily" soldering some legs on both sides.

4. Add sufficient flux on all sides.



5. Filling of the bit and start of the soldering:

Fill the special (concave) soldering bit with solder.

Now start a slow dragging movement from one leg to another.
Pay attention that the solder nicely moves up on the legs of the IC.

If the PCB is equipped with a "soldering thief" (a soldering land that is positioned next to the last leg), one has to solder in the direction of the soldering thief, so that at the end the possible surplus of solder flows on this soldering thief and no short circuit is created on the last two legs of the row.



f) Incorrect soldering :

For certain soldering problems or soldering mistakes, specific terms are used:

SOLDER BRIDGE



COLD SOLDERING



HALF SOLDERING OR DRY SOLDERING



NO SOLDERING



SOLDERING HORN



SOLDERING BALL OR SOLDERING SPLASH



SOLDERING WIRE SHORT CIRCUIT



7) (De)soldering with warm air and soldering paste:

In some cases it is impossible to solder or desolder certain components with a classical soldering iron or a normal desoldering station.

This is often the case for SMT components, with contact legs (partly) underneath the component.
In such a case one has to use a (de)soldering appliance that uses warm air or infra-red heat.

SMT component with contact surfaces beneath the component



1. Fluxing of the component:

To have a good temperature conductance during warming up, the soldering surfaces need to be moistened with flux.
If these surfaces are parly underneath the component, flux can be put on the borders of the component.



2. Warming-up of the soldered surfaces:

Use a "pointing nozzle" and point it at the component you want to remove. Keep a distance of 1 cm between the nozzle and the surface you want to warm up. Choose the temperature of the warm air e.g. +/- 340°C. (dependant on the temperature profile of the compents.)
Pay attention : if the contact surfaces are partly under the component, it is necessary to warm up the body of the component. Often the component is not useable afterwards.



3. Removal of the component

When the solder (paste) has melted, the component can be removed with a pair of tweezers.

4. Cleaning of the soldering surfaces:

Remove all redundant soldering paste with a classical desoldering station.



5. Adding soldering paste:

Add with a measured squirt the necessary soldering paste on the soldering lands.
Pay attention: soldering paste needs to be stored in strict circumstances. (see the instructions of the supplier)



6. Checking the quantity of soldering paste:

Check the quantity of the added soldering paste.
Only the contact surfaces should be covered with soldering paste.
Too much soldering paste can cause a short circuit during "re-flowing".



7. Positioning of the component

Position the new component carefully with the contact surfaces in the soldering paste with a pair of tweezers.
Position the component by the guide lines on the PCB.



8. Reflowing of the component:

Use a "pointing nozzle" and point it on the component you want to remove. Keep a distance of 1 cm between the nozzle and the surface you want to warm up. Choose the temperature of the warm air e.g. +/- 340°C. (dependant on the temperature profile of the component.) Warm up until one sees that the soldering paste is active or flowing. The result should be a good soldered joint.
Pay attention: For most of the warm air soldering appliances one can choose the air pressure. The speed should be minimum, otherwise there is a possibility of blowing the component away.



9. Checking of the soldering:

If possible, check the soldered joints.
Good soldering shines and has flowed evenly.



10. Checking of the electrical connection

If possible check the electrical connection with a meter.



Example of a "warm air soldering appliance": PACE.


TSS009 (1)
BGA / SMD
THERMOFLO™
STATUS
CYCLE
VACUUM
CYCLE
Set Temp = 427°C
Blower = 7
MANUAL
TIMED
REMOVE INSTALL
PROGRAM
1 YES
2
3 NO
EDIT
MODE ESC
4
5
6
RECALL
7
8
9
SAVE
STEP
0
BACK
ENTER
PACE
HOT

8) Lead free soldering

Introduction.

Normally all solderings (mechanical - and hand soldering) were executed with soldering material that contained lead. (40 % lead / 60 % tin)

But lead is toxic and therefore damaging for humans and for nature.

Hence European directives were made in which companies will be obliged to use soldering techniques without lead after July 2006.

Soldering without lead is relatively new in the world of electronics.

Lead-free solder:

If no lead is present in the soldering wire, this has to be replaced. The soldering wire needs to contain another metal, like SILVER & COPPER. (96,5 % tin / 3% silver / 0,5 % copper)

This new composition has the advantage that it is no longer toxic and that the soldering connections are stronger. (lead is relatively weak). But this new composition also has some negative consequences:

1) The cost is higher (silver and copper alloys are more expensive than lead)
2) The joints look different (more granular instead of shining)
3) The melting temperature is higher

One of the main points of interest is the higher melting temperature. One would think that as a consequence of the higher melting temperature of the solder, also the soldering temperature needs to be raised. This however is not always allowed! Some components are only able to handle a certain maximum temperature for a certain time.

In practice.

- You can use your original soldering station if you can reach the correct temperature at the soldertip
- The soldering bit has to be a bit larger than a soldering bit for soldering with lead.

Pay attention: **Solder with lead and solder without lead can never be mixed.**

9) Temperature specifications of the soldering bit

Solder with lead

Process	**Bit Type**	**Solder**	**Min**	**Center**	**Max**
Pins	ETB / ETCC/ 1121-0519	UOS-014	340°C	**380°C**	400°C
LCD	ETF / ETCC	UOS-005	320°C	**340°C**	360°C
OEL Display	ETCC	UOS-004	280°C	**290°C**	300°C
Connector	ETL / ETF	UOS-005	320°C	**340°C**	360°C
Flexible PCB	ETF	UOS-004	280°C	**300°C**	320°C
IC's & QFP IC's	1121-0490	UOS-005	280°C	**300°C**	320°C
Removal bridge	ETB / ETCC	UOS-005	320°C	**340°C**	360°C
Lights	ETF / ETB /1121-0519	UOS-005	280°C	**300°C**	320°C
SMT/SMD repair	ETL / ETF	UOS-005	280°C	**300°C**	320°C

Temp. specifications Pioneer standard ZES-A015 & ZES-B016

Solder without lead

Process	**Bit Type**	**Solder**	**Min**	**Center**	**Max**
Pins	LTB / LTCC	UOS-026	400°C	**410°C**	420°C
LCD	LTF / LTCC	UOS-027	320°C	**340°C**	360°C
OEL Display	LTCC	UOS-028	280°C	**300°C**	320°C
Connector	LTL / LTF	UOS-027	320°C	**340°C**	360°C
Flexible PCB	LTF	UOS-028	280°C	**300°C**	320°C
IC's & QFP IC's	1121-0490	UOS-027	280°C	**300°C**	320°C
Removal bridge	LTB / LTCC	UOS-027	320°C	**340°C**	360°C
Lights	LTF / LTB	UOS-027	280°C	**300°C**	320°C
SMT/SMD repair	LTL / LTF	UOS-027	280°C	**300°C**	320°C

Temp. specifications Pioneer standard ZES-A043

Types of soldering wire:

With lead	UOS-014 (1 mm) + UOS-005 (0.8 mm) + UOS-004 (0.5mm)
Without lead	UOS-026 (1 mm) + UOS-027 (0.8 mm) + UOS-028 (0.5 mm)

10) Types of soldering bits:


ETH


ETCC


ETL


ETB


ETF


ETO


CTSD7


ETC

11) Soldering devices:


"Clean-o-point": for automatic cleaning of the soldering bit with 2 rotating sponges

SOLDERING FLU
* Bevat isopropyla
* Licht ontvlambaa
gesloten verpakking be
houden van ontstekin
ELECTRONICS
"Flux dosing bottle": for easy adding of flux (with brush)


"Bit cleaner": for drying and cleaning of the soldering bit


" Brush" : for removal of possible soldering residues after soldering


"V-cutter" : for making a cut in the soldering wire, in order to reduce the formation of little soldering balls


"Solder dispenser" : for a simple supply of soldering wire


A
Weller® WTA 50 24V / 50W
Made in Germany
"Tweezer-copper bit": handy tool for the removal of SMD/SMT components.


TSS009 (1)
BGA/SMD
THERMOFLO
Set Temp = 427°C
Blower = 7
HOT
PACE
"Warm air desoldering appliance": for easy desoldering of flat-package IC's



"Desoldering appliance": for easy desoldering of point solderings

"Soldering magnifying glass": for a good view during soldering

The Basic Soldering Guide

http://www.epemag.wimborne.co.uk/solderfaq.htm (for text in this document)

basics for wire (Good intro) : http://www.youtube.com/watch?v=BLfXXRfRIzY
The Happy Soldering Iron: http://www.youtube.com/watch?v=AL-_RGbyf1s
basics: http://www.youtube.com/watch?v=I_NU2ruzyc4
Watt/temp comparison http://www.youtube.com/watch?v=Vh9pWu6K6tc&NR=1
tip sizes: http://www.youtube.com/watch?v=Sfb1Ve52ztY&NR=1
types of solder: http://www.youtube.com/watch?v=COqGkYMOA44
maintenance: http://www.youtube.com/watch?v=krxTfZCFptk&NR=1

Good overview with some odd bits: http://www.youtube.com/watch?v=AOdnGUMi7lQ

Desoldering overview: http://www.youtube.com/watch?v=j-_pnc-Qqm8
2nd good overview: http://www.youtube.com/watch?v=8UN3D2-f64A
Hot air pencil/gun: http://www.youtube.com/watch?v=AxYhF6Ab2CU
Desoldering gun (short): http://www.youtube.com/watch?v=8Z6MvZz_uNc

Crazy Guy from Make Electronics: http://www.youtube.com/watch?v=3N3ApzmyjzE
Not Soldering!! – Bread board: http://www.youtube.com/watch?v=oiqNaSPTI7w

This written guide will help beginners and novices to obtain effective results when soldering **electronic components**. If you have little or no experience of using a soldering iron, then EPE *(Everyday Practical Electronics* magazine) recommends that you practice your soldering technique on some fresh surplus components and clean stripboard (protoboard), before experimenting with a proper constructional project. This will help you to avoid the risk of disappointment when you start to assemble your first prototypes. If you've never soldered before, then read on!

Soldering irons

The most fundamental skill needed to assemble any electronic project is that of ***soldering***. It takes some practice to make the perfect joint, but, like riding a bicycle, once learned is never forgotten! The idea is simple: to join electrical parts together to form an electrical connection, using a molten mixture of lead and tin (solder*) with a soldering iron. A large range of soldering irons is available - which one is suitable for you depends on your budget and how serious your interest in electronics is.

[*Note: the use of lead in solder is now increasingly prohibited in many countries. "Lead free" solder is now statutory instead.]

Electronics catalogues often include a selection of well-known brands of soldering iron. Excellent British-made ones include the universally popular Antex, Adcola and Litesold makes. Other popular brands include those made by Weller and Ungar. A very basic mains electric soldering iron can cost from under £5 (US$ 8), but expect a reasonable model to be approximately £10-£12 (US$ 16 - 20) - though it's possible to spend into three figures on a soldering iron "station" if you're really serious! Check some suppliers' catalogues for some typical types. Certain factors you need to bear in mind include:-

Voltage: most irons run from the mains at 240V. However, low voltage types (e.g. 12V or 24V) generally form part of a "soldering station" and are designed to be used with a special controller made by the same manufacturer.

Wattage: Typically, they may have a power rating of between 15-25 watts or so, which is fine for most work. A higher wattage does ***not*** mean that the iron runs hotter - it simply means that there is more power in reserve for coping with larger joints. This also depends partly on the design of the "bit" (the tip of the iron). Consider a higher wattage iron simply as being more "unstoppable" when it comes to heavier-duty work, because it won't cool down so quickly.

Temperature Control: the simplest and cheapest types don't have any form of temperature regulation. Simply plug them in and switch them on! Thermal regulation is "designed in" (by physics, not electronics!): they may be described as "thermally balanced" so that they have some degree of temperature "matching" but their output will otherwise not be controlled. Unregulated irons form an ideal general purpose iron for most users, and they generally cope well with printed circuit board soldering and general interwiring. Most of these "miniature" types of iron will be of little use when attempting to solder large joints (e.g. very large terminals or very thick wires) because the component being soldered will "sink" heat away from the tip of the iron, cooling it down too much. (This is where a higher wattage comes in useful.)

A proper temperature-controlled iron will be quite a lot more expensive - retailing at say £40 (US$ 60) or more - and will have some form of built-in thermostatic control, to ensure that the temperature of the bit (the tip of the iron) is maintained at a fixed level (within limits). This is desirable especially during more frequent use, since it helps to ensure that the temperature does not "overshoot" in between times, and also guarantees that the output will be relatively stable. Some irons have a bimetallic strip thermostat built into the handle which gives an audible "click" in use: other types use all-electronic controllers, and some may be adjustable using a screwdriver.

Yet more expensive still, ***soldering stations*** cost from £70 (US$ 115) upwards (the iron may be sold separately, so you can pick the type you prefer), and consist of a complete bench-top control unit into which a special *low-voltage* soldering iron is plugged. Some versions might have a built-in digital temperature readout, and will have a control knob to enable you to vary the setting. The temperature could be boosted for soldering larger joints, for example, or for using higher melting-point solders (e.g. silver solder). These are designed for the most discerning users, or for continuous production line/ professional use. The best stations have irons which are well balanced, with comfort-grip handles which remain cool all day. A thermocouple will be built into the tip or shaft, which monitors temperature.

Anti-static protection: if you're interested in soldering a lot of static-sensitive parts (e.g. CMOS chips or MOSFET transistors), more advanced and expensive soldering iron stations use static-dissipative materials in their construction to ensure that static does not build up on the iron itself. You may see these listed as "ESD safe" *(electrostatic discharge proof)*. The cheapest irons won't necessarily be ESD-safe but never the less will still probably perform perfectly well in most hobby or educational applications, if you take the usual anti-static precautions when handling the components. The tip would need to be well earthed (grounded) in these circumstances.

Bits: it's useful to have a small selection of manufacturer's bits (soldering iron tips) available with different diameters or shapes, which can be changed depending on the type of work in hand. You'll probably find that you become accustomed to, and work best with, a particular shape of tip. Often, tips are *iron-coated* to preserve their life, or they may be bright-plated instead. Copper tips are seldom seen these days.

Spare parts: it's nice to know that spare parts may be available, so if the element blows, you don't need to replace the entire iron. This is especially so with expensive irons. Check through some of the larger mail-order catalogues.

A ***solder gun*** is a pistol-shaped iron, typically running at 100W or more, and is completely unsuitable for soldering modern electronic components: they're too hot, heavy and unwieldy for micro-electronics use. Plumbing, maybe..!

Soldering irons are best used along with a heat-resistant ***bench-type holder***, so that the hot iron can be safely parked in between use. Soldering stations already have this feature, otherwise a separate soldering iron stand is essential, preferably one with a holder for tip-cleaning sponges. Now let's look at how to use soldering irons properly, and how to put things right when a joint goes wrong.

The Basic Soldering Guide Photo Gallery

Soldering is a delicate manual skill which only comes with practice. Remember that your ability to solder effectively will determine directly how well the prototype or product functions during its lifespan. Poor soldering can be an expensive business - causing product failure and downtime, engineer's maintenance time and customer dissatisfaction. At hobbyist level, bad soldering technique can be a cause of major disappointment which damages your confidence. It needn't be like that: soldering is really easy to learn, and like learning to ride a bike, once mastered is never forgotten!

These photos illustrate the basic steps in making a perfect solder joint on a p.c.b. If you're a beginner, our advice is that it's best to practice your soldering technique using some clean, new parts with perhaps some new stripboard (protoboard). Be sure to avoid using old, dirty parts; these can be difficult if not impossible to solder.

(Left) Printed circuit board copper tracks must be clean to begin with, especially if they're not previously "tinned" with solder. Clean any raw p.c.b. copper tracks gently with e.g. an abrasive rubber block available from electronics suppliers. **(Right)** Clean the iron "bit" (soldering iron tip) using a damp sponge. The soldering iron featured is an Ungar Concept 2100 Soldering Station. Other popular brands of soldering equipment include Weller and Antex.





(Left) A useful product is Multicore's Tip Tinner Cleaner (TTC) - a 15 gramme tin of special paste which cleans and "tins" the soldering iron iron, in one go. New tips must be tinned **immediately** when used for the first time. **(Right)** Insert components and splay the leads so that the part is held in place.



(Left) It's usually best to snip the electronic component wires to length prior to soldering. This helps prevent transmitting mechanical shocks to the copper foil.**(Right)** Apply a clean soldering iron tip to the copper solder pad and the component lead, in order to heat *both* items at the same time.



(Left) Continue heating and apply a few millimetres of solder. Remove the iron and allow the solder joint to cool naturally. **(Right)** It only takes a second or two, to make the perfect joint, which should be nice and shiny. Check the Guide for troubleshooting help.



An example of a "dry" or "gray" soller joint - the solder failed to flow, and instead beaded to form globules around the wire.

How to solder

Turning to the actual techniques of soldering, firstly it's best to *secure the work* somehow so that it doesn't move during soldering and affect your accuracy. In the case of a printed circuit board, various holding frames are fairly popular especially with densely populated boards: the idea is to insert all the parts on one side ("stuffing the board"), hold them in place with a special foam pad to prevent them falling out, turn the board over and then snip off the wires with cutters before making the joints. The frame saves an awful lot of turning the board over and over, especially with large boards. Other parts could be held firm in a modeller's small vice, for example.

Solder joints may need to possess some degree of mechanical strength in some cases, especially with wires soldered to, say, potentiometer or switch tags, and this means that the wire should be looped through the tag and secured before solder is applied. The down side is that it is more difficult to *de-solder* the joint (see later) and remove the wire afterwards, if required. Otherwise, in the case of an ordinary circuit board, components' wires are bent to fit through the board, inserted flush against the board's surface, splayed outwards a little so that the part grips the board, and then soldered.

In my view - opinions vary - it's generally better to snip the surplus wires leads off *first*, to make the joint more accessible and avoid applying a mechanical shock to the p.c.b. joint. However, in the case of semiconductors, I often tend to leave the snipping until *after* the joint has been made, since the excess wire will help to sink away some of the heat from the semiconductor junction. Integrated circuits can either be soldered directly into place if you are confident enough, or better, use a dual-in-line socket to prevent heat damage. The chip can then be swapped out if needed.

Parts which become hot in operation (e.g. some resistors), are raised above the board slightly to allow air to circulate. Some components, especially large electrolytic capacitors, may require a mounting clip to be screwed down to the board first, otherwise the part may eventually break off due to vibration.

The perfectly soldered joint will be nice and shiny looking, and will prove reliable in service. I would say that:

- cleanliness
- temperature
- time
- adequate solder coverage

are the key factors affecting the quality of the joint. A little effort spent now in soldering the perfect joint may save you - or somebody else - a considerable amount of time in troubleshooting a defective joint in the future. The basic principles are as follows.

Really Clean

First, and without exception, all parts - including the iron tip itself - must be clean and free from contamination. Solder just will not "take" to dirty parts! Old components or copper board can be notoriously difficult to solder, because of the layer of oxidation which builds up on the surface of the leads. This repels the molten solder and this will soon be evident because the solder will "bead" into globules, going everywhere except where you need it. Dirt is the enemy of a good quality soldered joint!

Hence, it is an absolute necessity to ensure that parts are free from grease, oxidation and other contamination. In the case of old resistors or capacitors, for example, where the leads have started to oxidise, use a small hand-held file or perhaps scrape a knife blade or rub a fine emery cloth over them to reveal fresh metal underneath. Stripboard and copper printed circuit board will generally oxidise after a few months, especially if it has been fingerprinted, and the copper strips can be cleaned using an abrasive rubber block, like an aggressive eraser, to reveal fresh shiny copper underneath.

Also available is a fibre-glass filament brush, which is used propelling-pencil-like to remove any surface contamination. These tend to produce tiny particles which are highly irritating to skin, so avoid accidental contact with any debris. Afterwards, a wipe with a rag soaked in cleaning solvent will remove most grease marks and fingerprints. After preparing the surfaces, avoid touching the parts afterwards if at all possible.

Another side effect of having dirty surfaces is the tendency for people to want to apply *more heat* in an attempt to "force the solder to take". This will often do more harm than good because it may not be possible to burn off any contaminants anyway, and the component may be overheated. In the case of semiconductors, temperature is quite critical and they may be harmed by applying such excessive heat.

Before using the iron to make a joint, it should be "tinned" (coated with solder) by applying a few millimetres of solder, then wiped on a damp sponge preparing it for use: you should always do this immediately with a new bit, anyway. Personally, I always re-apply a very small amount of solder again, mainly to improve the thermal contact between the iron and the joint, so that the solder will flow more quickly and easily. It's sometimes better to tin larger parts as well before making the joint itself, but it isn't generally necessary with p.c.b. work. (All *EPE* printed circuit boards are "roller-tinned" to preserve their quality and to help with soldering.) A worthwhile product is Weller's *Tip Tinner & Cleaner*, a small 15 gram tinlet of paste onto which you dab a hot iron - the product cleans and tins the iron ready for use. An equivalent is Adcola *Tip-Save*.

Normal electronics grade solder is now "lead free" and typically contains Sn 97 Ag 2.5 Cu 0.5 (i.e. 97% tin, 2.5% silver and 0.5% copper). **It already contains cores of "flux"** which helps the molten solder to flow more easily over the joint. Flux removes oxides which arise during heating, and is seen as a brown fluid bubbling away on the joint. The use of separate acid flux paste (e.g. as used by plumbers) should NEVER be necessary in normal electronics applications because electronics-grade solder already contains the correct grade of flux! Other solders are available for specialist work, including aluminium and silver-solder. Different solder diameters are produced, too; 20-22 SWG (19-21 AWG) is 0.91-0.71mm diameter and is fine for most work. Choose 18 SWG (16 AWG) for larger joints requiring more solder.

Temperature

Another step to successful soldering is to ensure that the **temperature** of *all* the parts is raised to roughly the same level before applying solder. Imagine, for instance, trying to solder a resistor into place on a printed circuit board: it's far better to heat *both* the copper p.c.b. *and* the resistor lead at the same time before applying solder, so that the solder will flow much more readily over the joint. Heating one part but not the other is far less satisfactory joint, so strive to ensure that the iron is in contact with *all* the components first, before touching the solder to it. The melting point of most solder is in the region of 188°C (370°F) and the iron tip temperature is typically 330-350°C (626°-662°F). The latest lead-free solders typically require a higher temperature.

Now is the time

Next, the joint should be heated with the bit for just the right amount of time - during which a short length of solder is applied to the joint. Do not use the iron to carry molten solder over to the joint! Excessive time will damage the component and perhaps the circuit board copper foil too! Heat the joint with the tip of the iron, then continue heating whilst applying solder, then remove the iron and allow the joint to cool. This should take only a few seconds, with experience. The heating period depends on the temperature of your iron and size of the joint - and larger parts need more heat than smaller ones - but some parts (semiconductor diodes, transistors and i.c.s), are sensitive to heat and should not be heated for more than a few seconds. Novices sometimes buy a small clip-on heat-shunt, which resembles a pair of aluminium tweezers. In the case of, say, a transistor, the shunt is attached to one of the leads near to the transistor's body. Any excess heat then diverts up the heat shunt instead of into the transistor junction, thereby saving the device from over-heating. Beginners find them reassuring until they've gained more experience.

Solder Coverage

The final key to a successful solder joint is to apply an appropriate amount of solder. Too much solder is an unnecessary waste and may cause short circuits with adjacent joints. Too little and it may not support the component properly, or may not fully form a working joint. How much to apply, only really comes with practice. A few millimetres only, is enough for an "average" p.c.b. joint, (if there is such a thing).

Here's a summary of how to make the perfect solder joint.

1. All parts must be clean and free from dirt and grease.
2. Try to secure the work firmly.
3. "Tin" the iron tip with a small amount of solder. Do this immediately, with new tips being used for the first time.
4. Clean the tip of the hot soldering iron on a damp sponge.
5. Many people then add a tiny amount of fresh solder to the cleansed tip.

6. Heat all parts of the joint with the iron for under a second or so.
7. Continue heating, then apply sufficient solder only, to form an adequate joint.
8. Remove and return the iron safely to its stand.
9. It only takes two or three seconds at most, to solder the average p.c.b. joint.
10. Do not move parts until the solder has cooled.

Troubleshooting Guide

- Solder won't "take" - grease or dirt present - desolder and clean up the parts. Or, material may not be suitable for soldering with lead/tin solder (eg aluminium).
- Joint is crystalline or grainy-looking - has been moved before being allowed to cool, or joint was not heated adequately - too small an iron/ too large a joint.
- Solder joint forms a "spike" - probably overheated, burning away the flux.

Desoldering methods

A soldered joint which is improperly made will be electrically "noisy", unreliable and is likely to get worse in time. It may even not have made any electrical connection at all, or could work initially and then cause the equipment to fail at a later date! It can be hard to judge the quality of a solder joint purely by appearances, because you cannot say how the joint actually formed on the *inside*, but by following the guidelines there is no reason why you should not obtain perfect results.

A joint which is poorly formed is often called a "dry joint". Usually it results from dirt or grease preventing the solder from melting onto the parts properly, and is often noticeable because of the tendency of the solder not to "spread" but to form beads or globules instead, perhaps partially. Alternatively, if it seems to take an inordinately long time for the solder to spread, this is another sign of possible dirt and that the joint may potentially be a dry one.

There will undoubtedly come a time when you need to *remove* the solder from a joint: possibly to replace a faulty component or fix a dry joint. The usual way is to use a ***desoldering pump*** or vacuum pump which works like a small spring-loaded bicycle pump, only in reverse! (More demanding users using CMOS devices might need a pump which is ESD safe.) A spring-loaded plunger is released at the push of a button and the molten solder is then drawn up into the pump. It may take one or two attempts to clean up a joint this way, but a small desoldering pump is an invaluable tool especially for p.c.b. work.

Sometimes, it's effective to actually *add more* solder and then desolder the whole lot with a pump, if the solder is particularly awkward to remove. Care is needed, though, to ensure that the boards and parts are not damaged by excessive heat; the pumps themselves have a P.T.F.E. nozzle which is heat proof but may need replacing occasionally.

An excellent alternative to a pump is to use *desoldering braid*, including the famous American "Soder-Wick" (sic) or Adcola "TISA-Wick" which are packaged in small dispenser reels. This product is a specially treated fine copper braid which draws molten solder up into the braid where it solidifies. The best way is to use the tip of the hot iron to press a short length of braid down onto the joint to be de-soldered. The iron will subsequently melt the solder, which will be drawn up into the braid. Take extreme care to ensure that you don't allow the solder to cool with the braid adhering to the work, or you run the risk of damaging p.c.b. copper tracks when you attempt to pull the braid off the joint. See my photo gallery for more details.

I recommend buying a small reel of de-soldering braid, especially for larger or difficult joints which would take several attempts with a pump. It is surprisingly effective, especially on difficult joints where a desoldering pump may prove a struggle.

The Basic De-soldering Guide Photo Gallery (and Black Museum of Bad Soldering)

De-soldering is required when electronic components need to be removed from a circuit, usually because they are faulty. It may sometimes be necessary during testing or assembly, if a wrong part has been fitted or a modification has to be made. In the field, it's not uncommon for faulty electronic components to be swapped out, or poor joints (perhaps "dry" or gray joints) to need re-making properly, months or years after manufacture. Experienced engineers can often diagnose a particular faulty joint immediately, because they may have seen the same problem on similar electronic equipment before, especially if the equipment has a "reputation". A proper desoldering technique can soon be acquired with practice - all you need to do is buy some scrap boards to have a go with, and desolder to your heart's content!

The next photo sequence illustrates the basic steps for desoldering a printed circuit board, in order to remove a faulty part. Both the technique for using a desoldering suction pump as well as desolder braid are illustrated. Some real-life examples of poor soldering are shown too, in my *Black Museum of Bad Soldering*!

Remember - it costs just as much to get it right as it does to get it wrong! Practice makes perfect.



(Left) The two solder joints to be desoldered, to enable a faulty electrolytic capacitor to be removed from the printed circuit board.

(Right) If using a suction-type desoldering pump, apply the soldering iron tip first to melt the solder joint (say for 1-2 seconds). Ensure the spring-loaded desoldering pump is 'primed' and ready to go...



(Left) The PTFE nozzle of the desoldering pump is applied to the molten solder and the spring-loaded plunger is then immediately released, drawing the molten solder up into the pump. Remove the soldering iron tip. Repeat the process if needed. *Handy tip*: sometimes it helps to add some fresh solder and then desolder the whole joint.

(Right) The first p.c.b. joint, now desoldered. The second joint will be desoldered using traditional desoldering braid.




(Left) Select a suitable width of desoldering braid, and **press it down** onto the **COLD** joint using the hot tip of the iron. A flat soldering iron bit is preferable.

(Right) The molten solder is drawn up by capillary action into the desoldering braid. Take care not to overheat the board (the p.c.b. copper track may lift off), nor 'drag whiskers' of solder over the board, nor let the braid solidify onto the joint! Remove the braid while the joint is still molten.




(Left) The faulty electrolytic capacitor dropped out of the board after desoldering. Sometimes, it may need persuading with pliers.... but don't overdo this or you risk damaging the copper tracks on the p.c.b.

(Right) Close-up photograph of both joints, now desoldered and ready for the replacement component to be fitted.

The Black Museum of Bad Soldering

These are all genuine examples which have not been retouched or reworked in any way.





(Left) A tenfold excess of solder on this hand-soldered printed circuit board, and (extreme left) an incomplete solder joint with poor coverage. There is no need to add more solder "for luck".

(Right) An example of a dry (or gray) solder joint found inside a commercial PSU for a computer peripheral. The wire had been fed through the hole in the brass terminal, and merely tacked on with a blob of solder. This is a fire hazard (risk of arcing and overheating).



(Left) Hmmmm... this joint looks somewhat suspect as well... it's the earth (ground) wire in the same PSU

(Right) A close-up reveals the terrible standard of soldering (and quality control), with a fracture visible on this ground/ earth joint.



(Left) How **not** to make a mains voltage soldered joint. This solder joint went "dry" and starting arcing, nearly destroying the attached equipment. It is also a fire hazard.

(Right) The same mains connection, the wire merely being 'tacked on' with a blob of solder.

First Aid

If you are unlucky enough to receive burns which require treatment, here's what to do :-

1. Immediately cool the affected area with cold running water for several minutes.
2. Remove any rings etc. before swelling starts.
3. Apply a sterile dressing to protect against infection.
4. Do not apply lotions, ointments etc., nor prick any blisters which form later.
5. Seek professional medical advice where necessary.

A Few Hints about soldering on a Ground Plane

Before starting

- Always remove any grease and water from your hands. This will reduce the extent to which you oxidise and contaminate the board.
- Avoid touching the copper surface with your hands, always hold a board by its edges.
- Ensure all power and signal inputs are turned off (the soldering iron will short anything you touch to ground!!!)

Soldering a component

- Consider the circuit pathway from input to output in order to minimise the distance. This is especially important between ICs.
- Use the cleaning rubbers or solutions to clean away the oxidised surface where you are going to mount the component. This will help improve the electrical characteristic and improve solder flow
- Where you intend to place solder, VERY LIGHTLY scratch a cross-hatch pattern on the copper plate with a sharp tool. This will increase the friction thereby preventing your soldering iron skating across the board surface
- Apply heat to the copper surface first then add the solder so it smoothly flows on to the copper.
- Use pliers to bend the wire/chip legs to form small feet as this will increase the stability and make them much easier to solder. All wire bends should be done with pliers!
- Tin the legs before trying to mount them on the board
- When using wire, devise a colour coding system and stick to it i.e. red +ve rail, black GND rail, yellow –ve rail, blue input etc. This will make debugging so much easier
- If you are soldering an IC, two good techniques are:
    - Bend its legs with pliers so they are all horizontal and the chip can sit flat on the GND plane surface. Then place a bend just after where the pin leg narrows and bend again slightly further down so the leg it touching the ground plane (see image below). This way the IC is firmly held in place.



    - Bend legs touching the copper plane at the end to make small feet, then bend all other legs so that they are horizontal. This will result in the chip hovering just off the GND plane reducing the stability, but increasing the space to connect further components.
- Keep component leads as short as possible. This will reduce parasitics, improve mechanical robustness and reduce the chance of accidental shorts

These rules should be followed in conjunction with Dr Clarke's Soldering Guidelines found on the EE2 lab website.

Here is a good copper board layout. Notice the neat leads with none left loose above the circuit, and the way that the layout looks like a schematic. See the web copy (on the AMP handout page) of this picture for more detail.



Soldering and Desoldering Instruction

Soldering is defined as "the joining of metals by a fusion of alloys which have relatively low melting points". In other words, you use a metal that has a low melting point to adhere the surfaces to be soldered together. Soldering is more like gluing with molten metal than anything else. Soldering is also a must have skill for all sorts of electrical and electronics work. It is also a skill that must be taught correctly and developed with practice.

Remember that when soldering, the rosin in the solder releases fumes. These fumes are harmful to your eyes and lungs. Therefore, always work in a well-ventilated area. Hot solder is also dangerous. Be sure not to let is splash around because it will burn you almost instantly. Eye protection is also advised.



The Tools

Soldering Iron – Even the cheapest of them will do the job. They may not last as long, but they do get hot enough to melt solder and that is the goal. You only need to make sure that the one you buy has a suitable tip on it. The most typical tip is the one that is about the size of a 1/8” stereo mini-plug.

Solder – Get Rosin Core solder. Rosin will help the solder to flow onto the wires. Solder comes in different thickness. Buy what is appropriate for your job.

Desoldering Gun – This tool will make life a lot easier when you need to rework a previous solder job.
Solder Wick – Braided copper with rosin coating used to draw solder off of circuit boards.

SMD Rework station— Basically this is a high temp hair dryer with special nozzle attached. It heats up entire pins of the SMD device so you can remove them.

The Methods

Soldering – There is not art to soldering, it takes patience and practice to get it right. If you are doing it right, it will be easy and very fast. First, make sure that your soldering iron tip is clean. If it is dirtier than just a light gray color, you need to clean it. You can do this with sandpaper or a Scotch Brite pad. Next, turn your iron on and give it plenty of time to heat up. To test the heat, use a piece of solder touched to the tip. If it melts immediately, it is ready.

The most common way to mess up a solder job is to let the soldering iron stay on the parts to be soldered too long. What this does is oxidize the metal, making it too dirty to attract solder. If you are working with a circuit board, too much heat can damage the board, rendering it useless and in need of repair. You should only hold the soldering iron to the parts to be joined for no more than 10-12 seconds. Any longer and you will melt insulation on wire or damage a circuit board.

It has been said that soldering is a two-person job. You need two hands to hold the parts together, one hand to hold the iron, and another to feed the solder. The correct method for applying solder is to hold the joint perfectly still while heating with the soldering iron. After a few seconds, introduce the end of the solder at the point where the iron meets the parts

If the solder does not melt immediately and flow onto the joint, pull the solder away and try again after a couple seconds longer. If you exceed 10 seconds, pull the iron off and try again after it all cools down. You probably didn't have the iron touching enough of the parts to be soldered. Sometimes, the parts to be soldered are so big that they conduct the heat away very quickly and make it difficult to solder. In this case, it is OK to put some solder on each part individually and then put them together later by melting the solder on each one while they are touching.

Joining Two Wires - Strip off about 3/8" of insulation from the two wire ends to be joined. Place a ½" length of heat shrink tubing over one wire and push it back so that the heat from soldering won't shrink it prematurely. Fold each bare wire end back on itself so that the tip of the wire now comes back to the end of the insulation. Link both wires together using the bends like hooks. Now, twist the ends of the wires around themselves tightly. This type of connection is called a Western Union and it is the strongest method of joining two wires together. Now, heat the connection with the iron and allow solder to flow over the entire joint. Wait a few seconds for it to cool off and then slide the heat shrink tubing down over the connection and heat it with a match or heat gun.

Soldering a Wire to a Circuit Board – This is delicate work that you will do while soldering. Too much heat and your board will be damaged. If you are attaching a wire to an existing hole on the board, make sure that the hole is clean and free of any excess solder (see de-soldering for more detail). The best advice when soldering to a circuit board is to angle your soldering iron tip so that it makes good contact with the pad on the circuit board and the wire or part to be soldered at the same time. Heat the parts up and touch the solder at the point where the tip meets the part and the pad. If the solder does not flow immediately, pull everything off and wait for it to cool down and try again later.

Step 1



Apply heat to both pin and pad on the circuit board. Make sure tip of the soldering iron is touching both pin and pad.

Step 2



When the both pin and pad are heated enough, apply solder to the pin and pad. Solder should starts to flow.

Step 3



Apply enough but not too much solder. While applying the solder, do not move the tip of iron.

Step 4



Remove solder away.

Step 5



Remove tip of soldering iron also.

Step 6



Done! Check the joint to make sure the connection.

Good soldering and Bad soldering Joints

Here are some example of Good soldering and Bad soldering joint.
For Japanese, we often say, "Good soldering joint should look like Mt. Fuji."


Too much soldering


Too little soldering


Good soldering



Cold Solder Joints

A cold joint is a joint in which the solder does not make good contact with the component lead or printed circuit board pad. Cold joints occur when the component lead or solder pad moves before the solder is completely cooled. Cold joints make a really bad electrical connection and can prevent your circuit from working.

Cold joints can be recognized by a characteristic grainy, dull gray color, and can be easily fixed. This is done by first removing the old solder with a desoldering tool or simply by heating it up and flicking it off with the iron. Once the old solder is off, you can re-solder the joint, making sure to keep it still as it cools.


Cold soldering joints



Tips and Tricks

Soldering is something that needs to be practiced. These tips should help you become successful so you can stop practicing and get down to some serious building.

1. Use heat sinks. Heat sinks are a must for the leads of sensitive components such as ICs and transistors. If you don't have a clip on heat sink, then a pair of pliers is a good substitute.

2. Keep the iron tip clean. A clean iron tip means better heat conduction and a better joint. Use a wet sponge to clean the tip between joints.

3. Double-check joints. It is a good idea to check all solder joints with an ohmmeter after they are cooled. If the joint measures any more than a few tenths of an ohm, then it may be a good idea to re-solder it.

4. Use the proper iron or temperature. Remember that bigger joints will take longer to heat up with an 30W iron than with a 150W iron. While 30W is good for printed circuit boards and the like, higher wattages are great when soldering to a heavy metal chassis.

Desoldering

Desoldering is extremely difficult compare to soldering. In the process of RomBoard installation, the parts and circuit board must be in the good shape to re-use them. The tool we use is Desoldering Gun. This device has vacuum pump built in with heater tip. Process of desoldering it self is very simple, but there are some tricks to do clean and safe desoldering job.

Step 1



Put the desoldering gun's tip over to the soldering joint. Make sure nozzle is 90° angle from circuit board.

Step 2



Apply the enough heat to melt entire solder. Multi-layer board or ground pin may take while to transfer heat.

Step 3



While applying vacuum, move the tip around the pin to get all the solder of around the pin out. At this time, you can also feel pin moves freely, so you know pin is free from circuit board.

Step 4



When you can hear air flow sound from hole, you should be done. Stop applying vacuum and remove the gun from the pin. Inspect hole and pin.

When you done with desoldering, the parts that you are trying to remove should move freely. If it doesn't, find which pin is still has solder left, and re-apply fresh solder to it and try desoldering process again. The multi-layer circuit board require more heat to get solder to melt. Make sure pin start to move freely by moving the tip of soldering gun before you apply vacuum to it.

SMD device soldering and removal

In the process of RomBoard installation, chance of handling SMD devices is becoming higher and higher due to ECU configuration change.
Soldering of SMD devices are not much different from regular through hole soldering.
Important thing is positioning of the device is very critical.
Start with applying little solder to two of the each corner of the pads on the circuit board.
Then, place the SMD device and re-heat a one of the solder you just applied to connect a SMD device pin to the pad. Check the position of the device, if position is right re-heat the other end of solder to secure the device completely. If you didn't get position right, re-heat the pin that you just soldered and while heating a pin, move the device to the right position.
Once you positioned the device in the right position, apply Rosin Flux to both pins and pads. This will help your soldering job by keeping solder separate from each pin.
Here is how the joint on SMD device pin should look like.



QFP and SOP chip



PLCC chip



RomBoard adapter socket

Removing SMD device will be the probably the most difficult process. SMD rework station is used to do this. Make sure all the pins are completely heated otherwise you will be removing a pad from the circuit board along with device. Also, you should note, when you are applying heat to the device, some parts around the device is also heated and moves around when you touch. It is good idea to take a note of location of the devices near the target device.



Step 1
Apply pre-heat from back side of the target device. Keep applying heat until you can't touch the chip. By this time, circuit board should have enough heat.



Step 2
Apply heat from top of the target device. Nozzle should cover entire chip. You can check if chip is free from solder by sliding the nozzle left and right. Make sure you don't move other parts. If the chip moves freely, it is ready to be removed.



Step 3
Remove the chip straight up to avoid making solder bridge between pins. Chip is extremely hot! Unless you have skin of steel, avoid imitating the picture.



Step 4
After remove the chip, cool down both circuit board and chip.



Step 5
Clean the pads on the circuit board with desoldering gun.
Do not apply too much heat to the pad. Pad might peel off from circuit board. Clean the chip by desoldering gun also.
Check for any bridge between pins. If the chip has too much protective coating on it, use solvent to clean it up.



Step 6
If the pads on the circuit board is too small to use desolding gun, try cleaning by solder wick with rosin flux. This may take time but it is much better than peeling pads off.
Once again, do not apply too much heat.



Step 7
Solder the RomBoard adapter where the chip was.
Refer SMD device soldering section for how to solder adapter.

The Final Word

Soldering, desoldering, and working with SMD device will take some effort to learn. You should be relaxed and concentrated when you work.
Keeping every thing clean (tip of iron, gun, work surface, etc) will help you also.
Once you get comfortable to work with soldering you may find your own tips and tricks.
Experience is all bout soldering.

EOF

Strain Gage Soldering Techniques

Introduction

The most common method of making electrical connections in strain gage circuits is by means of soft solders, in wire form. Other methods, such as spot welding, brazing, compression bonding, paste solders, and conductive epoxies, are also available, but find only limited application. Solders have many advantages for strain gage use — they are low in cost, readily available in various alloy compositions to provide a range of melting temperatures, and are easily obtained in the form of either solid wire or wire with a core of flux. They are convenient to use, and offer an excellent combination of electrical and mechanical properties.

Although soldering is basically a simple procedure, it must be done with appropriate tools, supplies, and techniques to assure accurate strain measurement. This is particularly true when test requirements are severe in the sense of approaching the limits of the strain gage circuit capabilities; e.g., long-term stability, high-elongation measurements, fatigue endurance, etc. Use of improper materials or techniques can significantly degrade strain gage performance.

The purpose of this Tech Tip is to outline recommended procedures and materials for attaching leadwires to strain gage solder tabs or to bonded printed-circuit terminals. These reliable, experience-proven methods are based on the use of a professional quality soldering station, in conjunction with Micro-Measurements solders and installation accessories.

Soldering Station and Pencil

For precision soldering of strain gages, it is always necessary to use a temperature- or power-controlled soldering station that provides low voltage and adjustable temperature to the soldering iron tip. An unregulated soldering iron, connected directly to the power line, is not ordinarily suitable for strain gage use because the tip temperature is apt to be far too high. This tends to oxidize the tip, and to instantly vaporize the flux, making soldering much more difficult. In addition, the unnecessarily high temperature may damage the strain gage, the bonding adhesive, or even the test specimen. For these reasons, the soldering station should incorporate provision for adjusting the soldering temperature to suit varying installation conditions and requirements. The temperature must be adjusted, of course, to accommodate the melting points of the different solders commonly used for strain gage connections, but also to allow for environmental conditions such as drafts or outdoor soldering in cold weather. Moreover, the temperature controller should be carefully designed to ensure that it does not generate electrical noise that could adversely affect nearby measuring instruments when both are in use.

Design of the soldering pencil also requires special consideration. It should be light in weight, with a very flexible power cord, and with the gripping area thermally insulated from the heating element. These characteristics contribute to the comfort, ease, and precision of soldering, and minimize operator fatigue during long periods of use. The soldering tip itself should be of the flat, chisel, or screwdriver type. Pointed tips should not be used, because they tend to draw solder away from the work area, and thus make it more difficult to achieve a proper joint. In contrast, flat tips act to confine the solder, while offering greater surface area for better heat transfer and more effective soldering, generally.

Micro-Measurements soldering units incorporate all of the above features and a number of others, designed to help the user easily make consistent, reliable solder joints. These soldering units are widely used by professional strain gage installers everywhere, in both stress analysis laboratories and in transducer manufacture.

Solder Selection

The Micro-Measurements Division stocks a broad range of solder types to meet various installation and test requirements. While solders are sometimes selected to provide specific electrical or mechanical properties, the most common basis for selection is simply the melting-temperature range. Low-melting-point solders, for example, are generally used for strain gage installations on nonmetallic test parts to avoid damaging the gage, bonding adhesive, or test material due to overheating. In contrast, high-temperature solders are normally selected only when necessary to satisfy elevated-temperature testing requirements. These solders are somewhat more difficult to handle because the higher working temperature

Strain Gage Soldering Techniques

rapidly vaporizes the flux, and oxidizes the soldering tip, both of which tend to impede the soldering process. Specially designed soldering tips are recommended for high-temperature use.

For routine applications, where test conditions do not dictate the use of either a low- or high-temperature solder, an alloy with an intermediate melting temperature is the normal selection. The 63/37 tin-lead alloy (Type 361A-20R) is an excellent choice for general-purpose strain gage soldering. As an eutectic alloy, it has a sharply defined melting temperature — a characteristic that largely eliminates "cold" solder joints. The addition of a trace of antimony provides superior performance when the soldered connections will be exposed to very low (cryogenic) temperatures for long periods of time.

The general-purpose solders are supplied with a core of activated rosin flux. This makes soldering much more convenient, and is particularly useful in field applications where accessory liquid rosin flux (M-Flux AR) may not be available. Solid-wire solder, with externally applied acid flux (M-Flux SS), is recommended for making soldered connections to Micro-Measurements K- and D-alloy (modified Karma and isoelastic) strain gages. Rosin-core solders should not be used in conjunction with acid flux.

Silver solder (Type 1240-FPA) is available for applications where leadwire connections will be exposed to temperatures above about +550°F (*+290°C*). This solder, in paste form, is not suitable for attaching wires directly to strain gage solder tabs or to bondable terminals, but is intended for connecting instrument leads to preattached strain gage leads, as with WK-Series gages using a special resistance soldering unit. Techniques for making leadwire connections with silver solder are described in Micro-Measurements Tech Tip TT-602, *Silver Soldering Technique for Attachment of Leads to Strain Gages.*

Soldering Flux

The function of a soldering flux is to remove oxidation from the members being joined (solder tabs, terminals, leadwires), and to prevent further oxidation during soldering. For making leadwire splices, or soldering directly to constantan foil or copper terminals, the flux contained in a rosin-core solder is usually sufficient. With higher temperature solders, however, it may be necessary to supply additional flux. A liquid activated-rosin flux such as M-Flux AR is recommended for this purpose.

Acid fluxes should never be used on constantan strain gages or copper terminals, or for splicing copper leadwires; and paste fluxes, containing chlorides, should not be used under any circumstances for strain gage soldering. When tinning bare (without soldering options) solder tabs of Micro-Measurements K- and D-alloy strain gages, a liquid acid flux (M-Flux SS) is recommended. After the tinning operation, the residual flux must be completely neutralized within one to two minutes; and then the leadwire joint can be completed using the same solder and M-Flux AR rosin flux or a rosin-cored solder.

Preparation of the Soldering Tip

New soldering tips should always be tinned with solder prior to initial use. This is easily accomplished by wrapping one to two in (*25 to 50 mm*) of solder wire around the working portion of the tip while the soldering iron is cold, before applying power to the soldering station. If rosin-core solder is used, no external flux is required. With solid-wire solder, however, the wrapped tip should be dipped into liquid rosin flux (M-Flux AR) to provide sufficient flux for initial tinning. Set the control on the soldering station to the appropriate temperature range for the solder, and apply power to the unit. Allow the soldering pencil to heat until the solder wrapped around the tip melts completely. Remove excess melted solder from the tip with a dry gauze sponge. Never knock the heated soldering pencil against any object to remove excess solder, since this may result in personal injury or damage to the soldering pencil.

Note: Cross-alloying of solders can change the electrical, chemical, thermal and mechanical properties of the solder being used. To prevent cross-alloying, it is recommended that only one type of solder be used with each soldering tip. Of course, if one type of solder is incorporated in a gage with solder dots and another type is added, a mixture is produced. This mixture cannot be expected to have melting and strength properties any better than those of the lower temperature component.

Oxidation of the soldering tip seriously hinders the soldering operation. The tendency for oxidation can be minimized by ensuring that excess melted solder remains on the tip at all times when it is not actually in use. Negligent maintenance practices, or wiping the hot tip with materials that char on the surface, will produce a buildup of oxide that prevents proper soldering. If the tip does become oxidized, the following procedure is effective for cleaning and re-tinning:

1. Set the soldering station to the appropriate temperature range for the solder in use.
2. Place several drops of M-Flux SS on a glass plate. Re-tin the soldering surface by holding the heated tip in the SS flux while feeding solder onto the tip. A generous amount of solder is essential for proper tinning.

For technical questions, contact
mm@vpgsensors.com

Strain Gage Soldering Techniques

3. Wipe the excess solder from the tinned tip with a dry gauze sponge. For severely oxidized tips, it may be necessary to repeat this operation several times to obtain a properly tinned surface. The soldering tip should never be filed or sanded, since this may remove the plating on the tip, accelerating the oxidation and leading to the early deterioration of the tip. After the cleaning operation, remove excess solder, re-tin and clean the tip several times, using rosin-core solder, or solid-wire solder withM-Flux AR.

Tinning Solder Tabs and Bondable Terminals

All strain gage solder tabs, terminals, and leadwires must be properly tinned before making soldered connections. This helps ensure active surface wetting and good heat transfer during the soldering operation. Tinning stranded leadwires to produce a formable solid conductor will also greatly simplify the leadwire attachment procedure.

Before tinning the solder tabs on open-face (unencapsulated) strain gages, the measuring grid should be protected with PDT drafting tape. The drafting tape is positioned to cover the entire grid and the upper portion of the solder tabs, as shown in Figure 1. This not only shields the grid from soldering flux and inadvertent solder splash, but also restricts the flow of solder on the tabs. The tinned area on the solder tabs should be only large enough to easily accommodate the leadwire size in use. The latter consideration is particularly important when making installations for dynamic applications or large-strain measurement.

The tinning procedure for strain gage tabs and terminals consists of first cleaning and reapplying a small amount of solder to the hot soldering iron tip. Next, apply a drop of M-Flux AR to the tab or terminal (this step can be omitted if a rosin-core solder is used). When soldering directly to bare Karma or isoelastic foil, use M-Flux SS on the gage tabs only. Hold the soldering pencil in a nearly horizontal position (<30°), with the flat surface of the tip parallel to the solder tab or terminal. Place the solder wire flat on the gage tab, and press firmly with the tinned hot soldering tip for about one to two seconds, while adding approximately 1/8 in (*3 mm*) of fresh solder at the edge of the tip. This procedure assures that there is sufficient solder and flux for effective tinning. Simultaneously lift both the soldering pencil and solder wire from the tab area.



Figure 1 – Gage grid and upper portion of solder tabs masked with drafting tape.

NOTE: Lifting the soldering iron before lifting the solder may result in the end of the solder wire becoming attached to the tab; lifting them in the reverse order can leave a jagged (spike) solder deposit on the tab. When the operation is performed properly, it will produce a small, smoothly tinned area on the tab or terminal.

If M-Flux AR or a rosin-core solder is used in the tinning, it is not necessary to remove the residual soldering flux at this time. However, when M-Flux SS is employed to tin the bare solder tabs of K- or D-alloy gages, the acidic flux residue must be removed immediately following the tinning operation. To remove the residue, apply M-Prep Conditioner A liberally, and wash the area with a soft brush; then blot dry with a clean gauze sponge. Next, wash again with freely applied M-Prep Neutralizer 5A, and blot dry with a clean gauze sponge.

NOTE: Special procedures for tinning and wiring strain gages supplied with preattached solder dots are described in Micro-Measurements Tech Tip TT-606, *Soldering Techniques for Lead Attachment to Strain Gages with Solder Dots.*

Tinning and Attaching Leadwires

Of course, leadwire ends must be stripped of insulation before tinning, and this should be done with a thermal wire stripper to avoid the damage to the wire that often occurs when mechanical wire strippers are used. After the wires are stripped, the ends of stranded conductors should be twisted tightly together before tinning. The bare leadwire ends can then be tinned easily with the following procedure:

1. Remove excess solder from the soldering tip, using a dry gauze sponge. Then melt fresh solder on the hot tip to form a hemisphere of molten solder about twice the diameter of the wire to be tinned.

2. If rosin-core solder is used, slowly draw the bare wire through the molten solder while continuously adding fresh solder to the interface of the wire and soldering tip. With solid-wire solder, apply M-Flux AR to the

Strain Gage Soldering Techniques



Figure 2 – Trimming leadwire ends before taping in place.



Figure 3 – Leadwire end taped to surface in preparation for soldering.

wire end before starting to tin, and proceed in the same manner. This will produce a smooth, shiny coating of solder over the bare wire.

For applications employing bondable terminal strips and stranded instrumentation wire, it may be convenient to use a single strand of the wire as a jumper between the terminal and the strain gage solder tab. In such cases, the single wire strand should be separated out before twisting and tinning the remaining strands (see Micro-Measurements Tech Tip TT-603, *The Proper Use of Bondable Terminals in Strain Gage Applications*).

Leadwires should be formed and routed to the strain gage or terminal strip, then firmly anchored to the test-part surface with drafting tape before making the soldered connection. Attempting to route the leadwires after completing the solder joint will often result in damage to the gage or terminals. Routing into the connection area should be along a minimum strain direction (such as the "Poisson" direction in a uniaxial stress field) particularly for high elongation or dynamic tests. The tinned leadwire end should be trimmed short enough so that it will not protrude through the connection area, and cannot inadvertently make electrical contact with the test-part surface or adjacent solder connections. Figure 2 illustrates this stage in the procedure. In the final preparatory step, bend the leadwire end slightly to form a spring-like loop, and tape the wire firmly in place over the connection area, using PDT drafting tape. The tape should be within about 1/8 in (*3 mm*) of the connection area, as shown in Figure 3.

Clean and re-tin the soldering iron tip with fresh solder. The temperature of the iron should be adjusted so that the solder is easily melted, without rapidly vaporizing the flux. If the iron temperature is either too low or too high, it may cause poor solder connections, or it may damage the strain gage, terminal, or bonding adhesive. Apply a small amount of M-Flux AR to the joint area and, holding the soldering pencil nearly horizontal, firmly press the flat surface of the tip on the junction for about one second; then lift the tip from the soldered joint. If needed, additional flux can be provided during the joining operation by feeding a little fresh solder into the joint from a spool of rosin-core solder. This procedure should result in a smooth, hemispherical solder joint, without any peaks or jagged areas. If the solder joints are not smooth and uniform in size, repeat the soldering procedure, using additional flux and/or solder as necessary.

Cleanup and Inspection of Soldered Joints

After completing the soldering operation, it is imperative that all traces of residual flux be completely removed with RSK Rosin Solvent. The same solvent is used to soften the mastic of the drafting tape, permitting its easy removal. Do not try to pull away the tape with tweezers or other tools, because this may result in damage to the soldered connections or the strain gage grid. Thoroughly clean the entire installation area with generously applied rosin solvent and a soft-bristled brush. Clean the solder connection area until no visible signs of residual flux remain, and blot the area dry with a clean gauze sponge. Any traces of residual flux can cause gage instability and drift, and will inhibit bonding of the installation's protective coating. Incompletely removed soldering flux is the most common cause of degraded performance in strain gage installations. Residual flux mixed with a protective coating application can completely destroy the coating objective.

Visually inspect the soldered joints for any gritty or jagged joint surfaces, and for traces of flux. Solder connections

Strain Gage Soldering Techniques

should be smooth, shiny, and uniform in appearance. Any soldered joints that look questionable should be re-soldered, and flux removed. Check the resistance-to-ground of the completed gage installation, using the Model 1300 Gage Installation Tester. Low or marginal resistance readings suggest a leakage path between the soldered connections and the test-part surface. This condition usually results from residual soldering flux, or from bare leadwire conductors partially shorting the gage tabs or terminals to the test part. Soldered joints should not be tested by pulling on the leadwire, or by probing at the joint area. These practices frequently cause lifting or tearing of the solder tab from the gage backing material.

Summary

The ability to make consistently good soldered joints is essential for precision strain gage measurements. The techniques described here are straightforward and easily mastered, but they are most effective when used with professional soldering equipment which is specially designed for making soldered connections in strain gage circuits. The soldering pencil should be lightweight, with a flat chisel or screwdriver tip, and it should be connected to the soldering station with a very flexible power cord. Requirements for the soldering station include low-voltage operation of the soldering pencil, and provision for temperature adjustment to suit the type of solder and the application conditions. The equipment should not generate electrical interference that could affect sensitive measuring instrumentation. Solder selection is based primarily on the expected operating temperature range of the strain gage installation; and all solder tabs, bondable terminals, and leadwire ends should be tinned before soldering the joints. Soldered joints should always be smooth and shiny, with no jagged or irregular edges, and all traces of residual flux must be thoroughly removed prior to the application of protective coating. Use of the recommended materials and techniques, with careful attention to detail, will result in consistently proper and reliable soldered connections.

Soldering & De-soldering

Digital Electronics

Soldering & De-soldering

This presentation will…

- Review the tools needed to solder and de-solder electronic components.
- Demonstrate how to *tin* a soldering iron tip.
- Demonstrate the soldering process.
- Show the characteristics of a good solder connection.
- Review classic soldering mistakes.
- Demonstrate the de-soldering process.

Soldering Tools



1) Vise
2) Safety glasses
3) Solder sucker
4) Solder tool
5) Diagonal cutters
6) Needle nose pliers
7) Solder
8) Solder wick
9) Damp sponge
10) Soldering iron

Soldering Iron



Typically 25-30 watts

Tip Temperature ≈750°F (400 °C)

Project Lead The Way, Inc.
Copyright 2009

Solder

- Solder is an alloy of tin and lead.
- The solder used for electronics is frequently called 60/40 solder because it is made of 63% tin and 37% lead.
- 60/40 solder melts at 361° F.
- Lead-free solder**:** As of July 1st, 2006, European laws mandated that new electronics be entirely lead-free. As of yet, no such laws exist in the United States.

Soldering Iron Care & Maintenance





- A soldering iron must be coated with a thin coat of solder. This will allow for the transfer of heat to the work piece.
- This procedure is called tinning.
- The tip must be kept coated with a shiny layer of solder by occasional wiping and applying solder directly to the tip.

Tinning Process

Apply Solder to Soldering Iron Tip

Roll Tip on Damp Sponge

Properly Tinned Soldering Iron Tip

Solder Process



Heat both items at the same time by applying the soldering iron to the copper pad and the component lead.

Continue heating and apply a few millimeters of solder. Remove the iron and allow the solder joint to cool naturally.





It only takes a second or two to make the perfect joint, which should appear shiny.

A Good Solder Joint



- Smooth
- Bright
- Shiny
- Clean
- Concave fillet

Bad Solder Connections

Too Much Solder



Too Little Solder



Bad Solder Connections

Cold Solder Joint



Not Soldered



Bad Solder Connections

Solder Bridge



Lifted Trace/Pad



De-Solder Process: *Solder Sucker*



Apply heat to the connection to be de-soldered. When the solder melts, trigger the solder sucker.



Repeat de-soldering as needed until all solder is removed. Remove soldering iron & solder sucker from area.



Remove component lead.

De-Solder Process: *Solder Wick*



Solder wick is finely braided copper that is used to *wick away* excess solder from a de-soldered connection.



Apply the solder wick and soldering iron to the de-soldered connection. The solder wick will draw the excess solder off of the PCB pad.



De-soldered PCB pad

Soldering Safety

- Wear safety glasses when soldering. This includes all individuals in the vicinity of someone who is soldering.
- Place soldering iron in an approved holder when not in use. The iron is hot and can cause burns.
- Place the soldering iron so that the cord does not get caught up in your arms or on others.
- Ensure access to proper ventilation.
- Verify that the type of solder is safe to use in your working environment.
- Secure the components to be soldered before beginning the soldering process.

Soldering Safety

- Provide plenty of space to work.
- Use a properly-sized point for the soldering job to be completed.
- Verify that the tip on the soldering iron has a sharp point and has not been damaged in any way.
- Check the power cord for burned or melted sections that show bare wires. Label those cords DO NOT USE and ask the instructor to repair or replace.
- Do not to touch molten solder - it is hot!
- Make sure that the solder strand is long enough to keep fingers away from the hot iron.

Soldering Safety

- Tie back long hair and remove or tuck loose clothing.
- Use heat sinks for heat-sensitive parts. Provide sufficient cooling time before removing parts.
- Do not flick solder off of the iron. Flicking can cause solder to spray and hit skin or eyes.
- Hold the scrap end when cutting excess leads so that the scrap lead is not thrown into the air.
- Cut leads evenly with wire cutters.
- Make sure that leads do not short across other traces or leads.
- Thoroughly wash your hands after handling solder.

How to Solder Like a Pro

Detailed instruction, helpful hints, safety tips, and a comprehensive troubleshooting guide



inland affordable products you can trust! inland

Table of Contents

Thank you for your interest in Inland's How to Solder Like a Pro manual. Whether you are a beginner or an experienced stained glass artist, you will find useful information about selecting and maintaining your soldering tools and improving your soldering skills.

Safety

The Importance of Safety 3
Fumes 3
Lead 3
Heat 3

Soldering Irons

Choosing a Soldering Iron 4
Types of Temperature Control 4
Irons with Temperature Controlled Tips 4
Ceramic Heating Element Irons 4
Temperature Controlling Devices 5
Tip Sizes, Styles and Uses 5

Iron and Tip Maintenance

The Importance of Proper Care 6
The Cord 6
The Heating Element 6
The Tips 6

Solder

Why Do We Use Solder? 7
The Advantages of Solder 7
Types of Solder 7
Characteristics of Solder Types 8
Solder Composition Reference Table 8

Flux

Why Do We Use Flux? 9
Types of Flux 9
Characteristics of Fluxes 9
Getting the Most From Your Flux 9

Soldering Copper Foil

Before You Start 10
Cleaning Before Soldering 10
Getting Started 10
Running The Solder Bead 11
Fixing Imperfections 11
Other Things To Consider.................................. 11
Ending A Bead 12
Cleanup After Soldering 13
Finishing 13

Soldering Metal Cames

Step by Step 14

Soldering Other Metals

Vase Caps and Spiders 15
Metal Outer Channels.................................... ... 15
Hanging Hardware 16

Patina

How to apply patina..16

Trouble Shooting

Tips and hints to help you fix problems.......17-19

Glossary

Definition of terms...20-21

Safety

The Importance of Safety

One of the most important aspect of soldering any stained glass project is to take the proper measures to safeguard your health. Soldering involves working with potentially hazardous materials like lead, flux and harmful fumes. By observing specific safety precautions and using informed common sense, working in stained glass can be a safe and enjoyable past time. The following is intended to serve as a general rule of thumb. Since each person and situation is unique, you should use this information as a starting point to help you make informed safety decisions concerning your soldering habits.

Fumes

Solder only in a well ventilated area, and use an exhaust device that moves solder fumes away from your face. It's preferable to exhaust outside (check local/state building codes and restrictions on venting to outside air). If you don't exhaust to the outside, use a bench top fan or intake device with a replaceable smoke/fume absorber made for stained glass artists. It should draw solder fumes into the replaceable filter. The filter should be activated charcoal and designed to remove particles smaller than 1/2 micron from the air. There are also several OSHA approved respirators available for fumes. Consider wearing one in conjunction with a venting system, especially if you plan on soldering for several hours every day.

Lead

Most popular solders used in stained glass are lead based. When you are using them, follow these precautions:

- 👎 Never eat, drink, or smoke in any area where soldering takes place.
- 👍 Always thoroughly wash your hands after soldering.
- 👍 Make sure your soldering equipment and supplies are kept out of the reach of children.
- 👎 Do not discard lead or solder scraps into the trash. Find a means or place to recycle them.
- 👎 Never use lead based solders or cames on items that will come in contact with food or children, or will be frequently handled. If you are making kaleidoscopes, jewelry or napkin holders, use lead free solder.
- 👍 Consider having your blood lead level checked by your physician on a regular basis to help you monitor your handling practices.
- 👍 If you are pregnant, or considering it, you should check with your doctor before using lead or solder.

Heat

Soldering tools operate at high temperatures, so these safeguards are important:



- 👍 Wear safety glasses! Solder and flux can "pop" and "spit."
- 👍 Solder on a fire resistant surface. Homosote, or dry wall are good .
- 👎 Never leave your iron plugged in and unattended.
- 👎 Do not overload a wall outlet with too many electric appliances.
- 👍 Never set your hot iron down on anything other than an iron stand.
- 👍 Replace the cord of your iron if it becomes worn or gets burnt.
- 👍 To prevent burning your fingers, use needle nose pliers or heat resistant gloves to hold small pieces.
- 👎 Never cut off a grounding prong on an iron plug to make it fit an ungrounded receptacle.

Soldering Irons

Choosing a Soldering Iron

There is a lot to consider when you choose an iron for stained glass. The handle should be heat resistant and comfortable for you to hold. You may be holding it for several hours at a time, so consider the weight and balance of the iron. Carefully check the wattage of the iron that you are considering. It must be able to continuously generate enough heat to melt all of the types of solder you plan to work with and be compatible with the type of construction you use (i.e.-copper, foil, lead came, rebar, etc.). You will need an iron that is at least 60 watts, with chisel type tips, and a way to control the temperature.

Types of Temperature Controls

A broad range of soldering irons are available. Most irons, which we will call "conventional irons," are made with wound wire heaters in a barrel with mica insulation. They are often inexpensive, but they do not offer the ability to control operating temperature. A separate temperature controlling device must be used with these irons to achieve the best results. There are three types of soldering irons that are easier to use for stained glass projects, because they allow you to control temperatures more effectively:

Irons with temperature controlled tips.



Irons used with temperature controlling devices.

Irons with ceramic heaters.

Irons with Temperature Controlled Tips

These irons are supplied with an internal regulator in the tip that does not allow the iron to exceed a predetermined temperature. An example would be a 600°F tip. The iron heats to that temperature then "shuts off." When heat is required, the iron "turns on" again. Tips are available in predetermined temperatures up to 800°F. These irons are easy for beginners to use, because the temperature is automatically maintained for you, however, as your skills increase, you may prefer to control the amount of heat yourself for different soldering situations. The limited amount of control may become frustrating as your soldering skills increase. With this type of iron you will likely encounter "cold spots" where the iron will not melt your solder. These cold spots occur when heat is being drawn out of the tip faster than it is being replenished. You will need an iron with a minimum of 100 watts.

Ceramic Heating Element Irons

These irons are relatively new to the stained glass trade. They are made with highly efficient ceramic heating elements. Like a ceramic room heater, they produce a consistent temperature using less electrical wattage during operation. When initially heating and when reheating during "recovery" periods, they can draw a "burst" of power exceeding 100 watts and then efficiently reduce electrical consumption, often below 60 watts, during the soldering process. The result is efficiency and economy.



A remarkable feature of ceramic heater irons is they generally reach operating temperature in less than 60 seconds. Of the three types of noncoventional irons, the ceramic heater type best maintains consistent tip temperature over extended periods of time. Problems with slow heat recovery generally don't exist. A ceramic heater iron offers excellent flexibility and can be used with a temperature controller if you like.

Temperature Controlling Devices

A temperature controller is a device that operates similarly to a light dimmer switch. By dialing the control to a higher or lower setting, more or less electricity is fed to the iron. This increases or decreases the iron temperature, allowing the tip temperature to be controlled. You can establish the maximum temperature without changing tips.

A temperature control/iron combination offers you greater control and flexibility than a temperature controlled tip iron when working with different metals and solder mixes. Look for one that is at least 85 watts. Since the flow of electricity to the tip is consistent and never completely stops, encounters with cold spots are nearly eliminated. A temperature control/iron combination is suitable for all types of stained glass construction.

Temperature controllers are generally separate units that the iron plugs into. They are small, easy to use and relatively inexpensive. There are also irons that have controls built into the handle of the iron, which generally cost less than buying an iron and a separate control. Never plug an iron into a temperature control unless the manufacturer specifically states it is suitable for use with it.

Tip Sizes, Styles and Uses

Stained glass irons are generally sold with a "chisel" style tip. There are a variety of tip sizes and styles available for nearly every iron used in the stained glass industry. Different tips can expand the versatility of your soldering iron, so select an iron that offers more than one size replacement tip.



The standard tip size that comes with an iron is usually from 1/4" to 3/8" wide. This size works well for soldering either copper foil or lead came projects.



A smaller chisel tip, 3/16" wide, can be useful when soldering small pieces or when soldering in a tight area, such as a narrow inside part of a kaleidoscope. It is also very effective for decorative soldering.



Very small tips, 1/8" or narrower, are usually used for decorative soldering. They allow you to create very fine details and designs with the solder.

Iron and Tip Maintenance

The Importance of Proper Care

Your soldering iron may very well be one of your biggest tool investments, so you will want to do everything possible to ensure that it gives you many years of service. Well maintained soldering irons and tips perform better and make the job of soldering much easier. Always place your soldering iron in a stable iron stand whether it is being used or not.

The Cord

- 👍 Make sure you plug the iron into the correct type of outlet.
- 👍 Try not to use an extension cord. If you must, use a heavy duty one.
- 👎 Don't drop or bang the iron. Ceramic heaters are especially easy to crack or break.
- 👍 Regularly check the cord for burns or cracks and have a professional electrician replace worn cords before using the iron.
- 👍 Make sure that the cord is not hanging in such a way that it can be pulled off of the table.

The Heating Element

- 👍 Do not allow the iron to idle at operating temperatures for extended periods. This could burn out the heater element. Unplug the iron or, if you are using a rheostat, turn it down to a low "idle" setting.
- 👍 Occasionally, remove the tip and **lightly** tap the barrel of wire wound heater irons to remove debris.
- 👍 If you will not be using your iron for an extended period of time, you may want to store it (after it has fully cooled) in a zipper type bag to protect it from corrosion and humidity.

The Tips

- 👍 When you are finished using your iron, remove the tip from the barrel. Removing the tip is essential to preventing "seizing" which can occur if it is left in the iron for extended periods. (If your tip seizes, you can easily damage the heating element trying to remove it. It is best to return you iron to the manufacturer for removal.)
- 👍 When reinserting tips, make sure they are properly seated in the barrel.
- 👎 Never dip your tip into flux in order to clean it. Instead, use a clean damp sponge to wipe all sides of the tip periodically as you solder. Doing this removes impurities the tip has accumulated from the solder and the environment. It will ensure that you are receiving the maximum heat at the tip surface.
- 👍 Properly cleaned tips are bright and shiny. If your tip becomes "blackened," you can usually remove the buildup with a wet sponge, a tinning block or by gently using a brass brush. A “tinning block” (sal-amoniac) is used by placing a small amount of flux on the block and rubbing the tip of your hot iron in it. Wipe the tip on a damp sponge to remove debris. You may need to repeat this several times if your tip is very dirty.)
- 👍 Never use sandpaper or any abrasive material to clean a tip.
- 👍 The best way to minimize your tip maintenance is to find a good quality solder. Use one that has a high tin content and high metal purity.

Solder

Why Do We Use Solder?

Solder is a combination of tin and lead used to create a strong bond between other metals. Since solder won't stick to glass, we apply a copper foil tape (our metal) to the edges of the glass. This is refered to as the copper foil method of stained glass construction. Solder is melted over the copper foil, creating a structure that holds the pieces of glass together. The other option is to set the glass into channels of lead or metal, and solder the channels together. This is refered to as the lead came method.

The Advantages of Solder

Some of the advantages of soldering versus other bonding methods are:

- Solders are easy to use and relatively inexpensive.
- Low energy is required to solder.
- Properly soldered joints are highly reliable.
- Solder joints are easy to rework or repair.
- Experienced craftpersons can exercise a high degree of control over the soldering process.
- Solder joints age very well. They can last for years, decades and centuries.

Types of Solder

SILVERGLEEM
Quik-Set

Stained glass solders are usually a mixture of tin and lead, designated by two numbers representing the percentages of each metal in that specific mix. The first number always refers to the percentage of tin, the second is the percentage of lead. The most commonly used solders in stained glass are 60/40, (60% tin/40% lead) 50/50 and 63/37. "Lead-free" solders have no number designation and are a mixture of tin and small amounts of other metals. Avoid solders containing antimony, a very toxic element. Instead look for lead-free solders containing silver, or copper. They are safer and easy to use. (Note they are, however, more difficult to patina.)

In North America, you will find solder is generally sold in solid core wire form on a spool. The common spool size is one pound. In Europe, you will find solders primarily sold in a bar form. Never use acid-core or rosin-core solders for stained glass work. Look for solders that are sold as "free of impurities" in the component metals. Impurities cause a "scum" on your solder bead, degrade soldering iron tips, and interfere with the proper reaction of patina chemicals resulting in undesired finishes.

An important term for solders is the "working range" or "pasty range." This is the range of temperature between which solder transitions from liquid back to solid.

Characteristics of Solder Types

60/40 Solder: Composed of 60% tin and 40% lead, this solder melts at 374°F, but doesn't become completely solid until it cools to 361°F. This means it has a "pasty range" or "working range" of 13 degrees. This solder is your best choice for copper foil work. The liquid temperature and narrow "pasty range" make it easy to form and maintain consistent high, rounded, beaded seams. Because of its relatively low melting point, "60/40" solder is easy to rework to maintain a smooth finish solder bead.



50/50 Solder: This is composed of 50% tin and 50% lead. It is liquid at 421°F, solid at 361°F and has a pasty range of 60 degrees. This solder will produce a much "flatter" bead than 60/40. Because of its higher melting point, 50/50 solder is often used on the back (or inside) of a stained glass project to protect against "melt through" when soldering the front. Because it spreads and flattens out, 50/50 solder is often used when soldering lead came joints.

63/37 Solder: This solder is 63% tin and 37% lead. It becomes liquid at 361°F, and solid at 361°F, with a pasty or working range of 0 degrees. This solder is called a eutectic alloy which means at 361°F, you can go instantly from solid to liquid to solid just by applying or removing the heat source. You will often find "63/37" solder referred to as decorative or quick set solder. It is primarily used to create dimensional effects in the solder itself and can be "pulled" and manipulated to produce a variety of textures and designs. 63/37 solder also makes an excellent solder to bead up the outside rim of copper foiled pieces.



Lead-Free Solder: Depending on the specific mix of metals, lead free will produce differing liquid, solid, and pasty range temperatures. Check with the solder manufacturers for these specifics. Lead-free solders will perform similar to a 50/50 mix. Lead-free solders require more practice in order to obtain a smooth bead on copper foiled pieces and should not be used on lead came projects. Lead-free solder is the most expensive solder, but is the solder of choice when constructing pieces that will contact food, that will be handled frequently, or that will be used in a child's play area or room.

Solder Composition Reference Table

Alloy	Tin%	Lead%	Solid to	Liquid at	Pasty Range
50/50	50	50	361^{0}	421^{0}	60^{0}
60/40	60	40	361^{0}	374^{0}	13^{0}
63/37	63	37	361^{0}	361^{0}	0^{0}

Flux

Why Do We Use Flux?

Flux is a chemical compound that is used to promote the bonding of metals by removing the oxide residue simultaneously with the soldering process. Most metals left exposed to the air around us react with the air to form residue on the surface of the metal. The process is oxidization and the residues are oxides. Each mix of metals being joined has a specific flux that best promotes this bonding process. In stained glass, the metals being joined are primarily copper to tin/lead solder and lead, brass or zinc to tin/lead solder.

Types of Flux

Selecting the correct flux for your application is as critical as any other step of the soldering process. The proper flux will assure less soldering problems and a satisfactory solder bond. The best fluxes do three things:

- They remove all the residue that has formed on the surface of the metals you are going to solder.
- They prevent oxides from forming while you are soldering.
- Any post-soldering residue they leave is noncorrosive and easily cleaned off.

Fluxes are available in organic and inorganic forms. If you touch the flux and your skin seems to have a sensitivity to one type of flux, an inorganic type for example, try an organic variety. Often you will find that you are less sensitive to irritation by using the opposite type flux. Organic fluxes are generally some form of oleic (fatty) acids, while inorganic fluxes are most often zinc chloride based.

Characteristics of Fluxes

Liquid flux is the most widely used. It may or may not be water soluble. Water soluble fluxes clean up very easily, but are thinner and some have a tendency to evaporate quickly and require repeat applications. Some liquid fluxes are thinner than others and have a tendency to run or spread out from their point of application.

Gel Flux is generally water soluble and "adheres" well to the surface being soldered. Gels tend not to evaporate as readily as liquid flux, but if you apply too much, they produce more "spitting" and "popping" as you solder.

Paste Flux is very thick, stays where it’s applied, and doesn't evaporate easily. It's effective when soldering 3-D forms such as lamps. Paste fluxes can be difficult to clean. Be very careful not to over apply a paste flux as it will also spit and pop, leaving pits on your solder seams.

Getting the Most From Your Flux

It is important to keep your flux clean and free of impurities. This will ensure the purest possible solder joint. One way to keep your flux clean is to avoid dipping in and out of the original container. Pour out the amount you will need for your current project into a separate, smaller container. Don’t leave the flux bottle sitting around with the cover off. Never pour leftover flux back into the original container. Fluxes often will produce fumes as you solder. Make sure you are aware of and follow the precautions suggested in the health and safety section of this guide.

Soldering Basics for Copper Foil

The quality of the solder job can make or break your project, yet it is the step that takes the most practice to become good at. Soldering is more difficult than the other steps in stained glass because there are so many things that can effect it: the amount of heat, the amount of solder, the type of flux, the rate at which you move, gaps in the project, etc. The following step-by-step instructions will give you the basics of soldering. If you are just starting out, you will learn a lot. If you are experienced, you may just find the trick that makes it all come together. Great soldering takes a little bit of knowledge and a lot of practice.

Before You Start



Preparation is the key to producing a good solder bead. Here are some suggestions to help you get of to a great start!

- Make sure that the foil is seated properly over the glass.
- Trim all overlaps in the foil using a sharp craft blade.
- Assemble all the tools you will need so they are at hand.
- Wear safety glasses.
- Have a proper ventilation set up.
- Make sure the foil is well burnished and sealed smoothly to the glass surface.
- Secure the glass pieces using pins, or squaring blocks made for this purpose before soldering.

Set aside enough time to solder your entire project all at once. If you don't, dried flux and solder residues on the unfinished parts will make further soldering difficult. Flux allowed to remain on a project can compromise the strength of the solder joints.

Cleaning Before Soldering



Sometimes the surface you are going to solder needs cleaning to remove visible grime, dirt, residue or oxidization. In this case, use 000 or 0000 steel wool to clean the surface of copper foil. For lead came or excessive oxidation carefully use a soft brass brush. If you won't be able to solder your project immediately after it is copper foiled, store it in a plastic bag to help reduce oxidation. If you partially solder the project and have to stop before it is complete, be sure to clean off all of the flux and store the project in a plastic bag until you are ready to continue. You will probably still need to use steel wool on the joints when you are ready to solder, but the clean up should be minor.

Getting Started



Begin the soldering process by fluxing all intersections of the glass project. Then "flat tack" solder these intersections together by using a very small amount of solder and the flat face of the iron tip. The solder should lay flat on the intersection and you shouldn't have any beads or bumps of solder on the piece. Hence the name "flat-tack" soldering.



Now, fill any gaps between the glass pieces by melting solder into them until the solder is level with the surface of the glass. If you have large gaps, you can ball up some copper foil, with the sticky sides together, and fill the gaps. This will help keep the solder from seeping out the other side.

"Tin" the entire perimeter making sure to work some solder into seams that intersect the perimeter. (Tinning is the process of coating a surface with a thin layer of solder. Apply just enough solder to turn the foil to the silver color of the solder.) This creates a "dam" that prevents solder from spilling over the edge when you solder the interior seams.

Next, flux an area you can comfortably finish soldering before the flux can evaporate. Start at the top of the piece and work down. This prevents you from dragging your sleeves and hands through the flux.

Running The Solder Bead



Hold your soldering iron in your writing hand. Position the iron comfortably so the face of the iron tip is perpendicular to the seam. If you hold your iron like a carving knife you will automatically put the tip in the best position for soldering. It will also keep you from "painting" with the iron. You will hold the solder in the opposite hand. Start soldering by placing the iron tip down on the foil seam with the wider face perpendicular to the seam and facing you. Touch the solder to the tip of the iron, just above the point where the iron tip touches the copper foil. Allow the solder to flow down the tip face onto the seam as you move the iron along the seam. Feed the solder at a continuous, even rate to create a consistent, rounded bead of solder over the seam. This takes practice!



Too little



Too much

If you apply too little solder or move too quickly, your seam will be flat. To correct this problem, allow the solder to cool, then resolder the joint applying more solder. On the other hand, be careful not to feed the solder too fast or move the iron too slowly, as this will cause the solder seam to bulge and flow out over the glass.

Fixing Imperfections

If you have too little solder, just add more, being sure to remelt the previous solder line as you apply another coat. If you applied too much solder the first time, it's easy to remove the excess with the following procedure. Clean your iron tip thoroughly on a sponge. With the iron tip positioned with the flat face down, move it across the seam, "pulling" the excess solder onto the glass. Clean your tip and repeat the process until all excess solder is removed. Another method for removing excess solder is to wait until all the seams have been soldered. Then place your project up on edge and run the tip through the seam allowing the excess to run off. Lay the piece flat, reflux, and rework the seam, adding additional solder as needed.

When you solder, work slowly enough to produce a good bead, but not so slowly that solder melts through seams to the back side of the project. Here's a hint: one way to prevent this is to put damp paper towel under your panel before you start soldering. Moving too slow also increases the likelihood of causing heat fractures on your glass.

Other Things To Consider

Always keep your tip clean by frequently wiping all sides of the tip on your damp sponge. Wait momentarily for the tip to reheat before continuing to solder. A clean tip maintains proper heat and removes impurities.

To achieve a smooth solder line, solder the longest continuous seam possible. Don't start or stop a solder seam at an intersection with another seam. As you meet an intersection, allow the solder to break or "y" out over the intersecting seam about 1/2" and then return to the original path you were soldering in one continuous motion. As you continue to solder seams, you will connect these branches, thus preventing pulling out at intersections of seams (which is a noticeable sign of a beginner). When you encounter a "v" type joint. Solder in a direction that moves up into the "v" point, instead of coming down onto the point. This keeps a nice clean "v" joint without excess solder obscuring it. Do this by soldering up one leg of the "v" and as you approach the apex, drop your iron tip down flatter on the glass, so that it crosses over both seams. Then continue soldering into and out of the point of the "v."



Avoid a "painting" motion when soldering. Visualize your iron as a magnet pulling along a metal strip. Maintain a small puddle of solder at the base of the tip as you solder. When two adjacent pieces of glass vary in thickness, ride the tip on the higher piece of glass as you solder.



Effects of using the iron like a paint brush

A big advantage of using copper foil is that not-so-perfect solder seams can be reworked. Allow the seam to cool, reflux it, then resolder. Be careful because reworking a seam too many times (more than 2-3) can cause the adhesive on the foil to loosen and bubble.

Solder one side of your project completely, then turn it over and repeat the process on the other side. Some of the flux from the first side you soldered will have seeped to the other side. You may encounter more "spitting," so use flux very sparingly. To achieve a smooth, beaded solder seam: practice! practice!

Ending A Bead

When you are ready to end your seam, pull off across the face of the glass making sure you are in a liquid section of the solder seam and do not lift straight up. This technique leaves a smooth exit point that is virtually unnoticeable. You may notice that this is the same photo used for removing extra solder. It’s not a mistake. The action is very much the same.

Practice!

Creating perfect solder seams takes practice. One good way is to make a practice board. Make sure to include all types of intersections and lines (curvy and straight). Foil the piece and flat solder it on the front and back. Practice each different soldering technique. When you are finished, you can hold the piece vertical and melt the solder off. Now you are ready to start again. Many people use the practice board before they start soldering each project, just to get the feel of soldering again.

Cleanup After Soldering

After soldering, you will need to remove all flux and solder residues from your solder lines and glass. The best cleaners to use are ones that neutralize the acid property of fluxes. To properly clean your project, you will need a good flux cleaner, very warm water and a soft scrub brush. Thoroughly brush the cleaner into every corner of your project, front and back. Follow this with a long rinse in clean, warm water and then towel the project dry. This step is very important because any flux that remains will continue to react with the solder, causing oxidation. If your project looks good after the initial cleaning, but the solder lines have a white or green growth on them after a few weeks, it generally means that all of the flux was not removed from the project. You can use 000 steel wool to remove the patina and finishing compound and thoroughly clean the project. Then reapply the patina and finishing compound.

FLUX REMOVER
inland

A small stiff scrub brush is the best way to clean the entire project. After the initial cleaning, you may find some areas that need additional attention.

You may find small pieces of solder stuck to the glass. You can easily remove these using your fingernail, or 000 steel wool. Be careful not to scratch the glass.

An old toothbrush can be helpful for cleaning in tight intersections and right up against the solder line.

Occasionally you may find that after applying patina, certain types of glass acquire a “rainbow” effect. This is most likely to occur on hot colors, black, white and iridized glass. It is one of those things that is unpredictable and difficult or impossible to remove. You can try to remove it by using a paste made from baking soda, but it doesn’t always work. The only way to prevent this occasional problem is to be very careful not to get patina on your glass. Use a cotton swab to apply the patina only to the solder lines of the project. If you have this problem, it is a good idea to make note of it on any remaining glass, so you can be more careful the next time you use that particular glass.

Finishing

After cleaning your project you should use a finishing wax or compound to keep it looking it’s best. A good quality carnauba wax or pre-mixed wax and cleaner should be applied to all of the solder lines. A nice side effect is that the wax also enhances the color of the patina making it either rich black or shinny copper. You may find it helpful to reapply the wax after a few months. (If you would like to change the color of the solder, see the section about patina on page 16.)

Soldering Basics for Metal Cames

Lead came construction requires a different soldering technique than that used for copper foil. You can use the same iron and flux, but the preparation and actual soldering will differ. You will be soldering only the joints, instead of running an entire bead. With a little knowledge and some practice, you will be able to make perfect solder joints on lead or other metals.

Getting Started



First, make sure that all joints are in line with each other and butt against each other with no gaps. Use a triangle and/or square to check the squareness of the panel and make sure that your lines run true across the panel in all directions. Make any adjustments that are needed. Thoroughly clean surface oxidation from intersections with a soft brass brush.

Soldering

The most desirable solder to use when constructing a lead project is 50/50. It flows out from the point of contact, leaving a nice joint. Do a "lead" test to check the heat of your iron. Allow the iron tip to heat for several minutes. Then, place the flat face of the tip on a scrap of lead. If the lead melts, the iron is too hot. Lower the temperature or change to a lower temperature tip. (This is where a rheostat iron is great.) Now test the tip with 50/50 solder to make sure it can melt it. If it does, your tip temperature is adjusted correctly. If not, raise tip temperature just until you melt the solder. Recheck the tip temperature and test it on the lead again. Now flux all the joints on your panel.



Begin by holding the solder on the joint. Move in to the joint across the glass, not from across the came. The wide face of the tip should be down toward the joint. Coming into the joint over the glass prevents leaving a solder trail on the lead came at one end of the solder joint. Techniques like these are the signature of an accomplished craftsperson.

Melt only a small amount of solder and move the tip in a slight circular motion allowing it to flow out over the joint a distance equal to the width of the came being used. Pull the iron tip straight up off the center of the joint. The desired end result is that intersections of the lead cames are not visible through the solder and the solder on them is smooth, not beaded. You should be able to run a fingernail over the came and into the soldered joint without it catching or clicking. Solder the joints on the front of the project. Then turn the project over and repeat the same process on the back.

Finishing

Lead projects need to be finished by applying a cement. The cement will weatherproof the project and secure the glass in the channels. This step is necessary on any came project to ensure a strong, secure panel. Cement is easily applied to the panel by using a small scrub brush to work the cement under the channels both on the front and back of the project. After the cementing process is complete, whiting sprinkled over the entire surface and allowed to absorb excess moisture for a few minutes. Using a stiff brush, vigerously brush the lead channels, removing excess cement from the glass. The brushing process allows a natural patina to form on the lead, so it is not necessary to apply patina to the project. Allow the project to dry thoroughly, usually for a few days, before installing or hanging the project.

Soldering Basics for Other Metals

Vase Caps

Vase caps are generally made from spun brass. The cap must be very clean of all dirt and oils for the solder to adhere. Use 0000 steel wool to clean the areas that you will be soldering. The cap also needs to be quite hot in order to achieve a good bond between the solder and the brass. An easy way to get the cap hot is to heat it in a hot oven for about 15 minutes. Use pliers to carefully remove the cap from the oven. Center the vase cap on the lamp. Flux all areas you will be soldering. (Paste flux is easy to use for this purpose, because it doesn't drip.) Get a small amount of solder on your iron and hold it on the vase cap for a minute or so at the area you want to make a connection to the lamp. When the cap is hot enough, the solder will spread out instead of lumping up. Add more solder to make a connection to the lamp. (Some vase caps have a lacquer finish on them. This must be removed at the areas you need to solder. Use a craft knife to gently scrape the lacquer in these areas.

Spiders

Spiders are made from brass as well. You can either cut the legs to fit, or bend them. Like a vase cap, you need to get the brass quite hot in order to create a good bond with the solder. Unlike vase caps, you can get the smaller area of the spider hot enough using just your soldering iron. Simply hold your iron tip on the area that you need to solder for a minute or so. Apply flux and a little solder, and continue to heat the spider with your iron. When it is hot enough, the solder will smooth out around the spider leg and adhere to the lamp. If the solder is globed up, the spider leg isn't hot enough. Continue in this manner for all of the legs.

Metal Outer Channels





When attaching a zinc, copper or brass edge to a project, use this solder technique: Cut the zinc, copper or brass came vertical members to overlap the horizontal members in a "butt" type joint. A butt joint provides structural stability and distributes weight. Before you solder the butt joints, you can use masking tape to contain the size of the solder joint.

Clean and flux these joints and solder them to each other using the flat tip of the iron on the metal. The metal channel will take a little longer to get hot than copper foil. If the metal is not hot enough the solder will not smooth out. The metal frame should be attached to the panel by soldering it to any lead lines that it touches.

On leaded projects, solder from the outer metal edging onto the lead came, pulling the iron tip straight up over the point of intersection when completing the solder joint. This simple technique will level the solder smoothly over the joint.

For copper foil pieces, stop your solder bead about 1/4-1/2" from the outer edge to allow room for the metal edging to fit onto the perimeter of the project. If you forget to do this initially, flatten the solder bead so the outer edging fits onto the project. After fitting the outer edging material, flux and solder the corners as outlined above. Connect the copper foil beads that intersect with the outer edging metal by continuing the solder bead into the edging making sure that the solder adheres securely to the metal edge.

As you work more with your iron, different solders, lead came, and copper foiled projects, your skills will increase. You will quickly develop the techniques that will make you more confident in tackling increasingly complex projects.

Hanging Hardware

There are many ways to hang your project. You will want to make sure that the method you choose will support the weight of the project. You can purchase pre-made hardware from your stained glass store, or make your own using any type of solderable wire. If you are using wire look for 16 to 18 gauge.



Rings can be added to the metal border of the project if it is not too heavy. A general rule of thumb is about one square foot. Hold the ring with pliers and solder rings to the metal border of the piece wherever they allow it to hang properly. Just like soldering the channel together, if you don't allow the metal to get hot enough, the solder will not adhere well. This will result in your hanging rings failing.

A stronger type of hardware is made using wire. Twist together four strands of 16 -18 gauge wire, leaving a loop at the end. Cut the wire to about 1/2". Insert the wire into the opening of the metal channel, bending the loop the direction you need it to be. Solder the hanger to the channel and fill the opening with solder.



Another option is to make a loop from twisted wire and solder it to the front and back of the metal channel, with the loop extending above the project. Be sure to solder the hanger into an existing solder joint, not just to the channel. This will prevent the weight of the project from pulling the channel away from the glass.

By the way, the joint on the hanger at the right was painted to match the brass channel using a gold paint pen.

Patina

Solder and lead change color naturally over time, but you can change their color instantly by using patinas. There are several different formulas producing a variety of colors. Patinas are easy to use. Make sure that your project is thoroughly clean and free of solder, flux and cutting residues. Use a brush or soft rag to apply the patina to the solder until you reach the desired color. Wash the panel again to remove any patina from the glass.

☞When using antique brass patina, first scrub your solder seams with fine steel wool. Apply the patina sparingly with a clean brush, using only a few strokes. Over use will produce a coppery finish.

☟Never mix patinas and always use proper ventilation and skin protection.

☞To get a nice black finish on brass, add a dash of table salt to a little black patina in a glass or plastic jar. Mix well, apply and allow to dry. Clean and finish a usual.

Trouble Shooting

Problem: The solder won't adhere to the foil or came.

Solutions/Explanations:

1) Did you apply any flux?
2) Did you apply enough flux?
3) Was your iron too cool?
4) Is the foil or lead came too oxidized for flux to activate the surface?
    A) Buff copper foil with 000 or 0000 steel wool.
    B) Clean lead came with brass brush.

Problem: Solder is melting through to the backside of my project.

Solutions/Explanations:

1) Your iron is too hot. Depending on what type of iron you are using, either turn the temperature controller down or change to a lower temperature tip.
2) You may be soldering too long in each area. Move on and let the solder cool. Return to those spots later.
3) The gaps between your glass are too wide. Try to fill the gaps with solder and let it cool. Then go back and solder a bead on top of the filled gaps.
4) Try placing a wet paper towel under the project to provide cooling.

Problem: My solder is "stiff." I am unable to get a smooth bead.

Solutions/Explanations:

1) Your iron is too cool. Depending on what type of iron you are using, either turn the temperature controller up or change to a higher temperature tip.
2) You may not be using enough flux.
3) Is the tip of the iron getting hot? Check to see that the tip is seated correctly down in the barrel of the iron.
4) Are you "painting" with solder, instead of running a long bead with a steady, even, one directional movement? This is one of the most common mistakes that beginners make. In order for the solder to create a bead, it has to get molten. If you are using the iron as a “paint brush”, the solder is not getting hot enough to melt thoroughly.
5) You may be soldering with just a corner of the iron tip. Check for proper positioning of your iron.
6) Try a different solder with a lower melting point.

Problem: My iron seems to be hot, but the solder isn't melting as fast as normal.

Solutions/Explanations:

1) Check your tip. Is it loose?
2) Is your tip too dirty?
    A) Clean it on a wet sponge.
    B) Clean it on a tinning block.
3) Your tip is too corroded or defective. Replace it.
4) Your rheostat may be malfunctioning.
    A) Plug the iron into the outlet you are using without the temperature controller. If the iron works, the controller is malfunctioning. If the iron doesn’t work, the problem may be with the iron itself.
    B) With some types you can check the temperature controller by plugging a lamp into it. Turn on the lamp and see if the controller dims and brightens the lamp.

Problem: My solder seams are flat.

Solutions/Explanations:

1) You are not using enough solder. Reflux your project and add more solder.
2) You are soldering too fast. Move at a speed that lets the solder bead.
3) If the bead was there, but disappeared, you may be working too long in one area causing the solder to melt through to the other side. Allow the area to cool down before trying again. Another option is to place a damp paper towel under the seam you are working on. This will help keep the glass cool, allowing you a little more time to work.
4) Check the type of solder mix you are using. For copper foil work, 60/40 will help produce a higher, more rounded bead. Don't make the mistake of buying 40/60 solder. It has an even longer pasty range than 50/50, and is not recommended for stained glass work.

Problem: My solder seam is too wide.

Solutions/Explanations:

1) Do you have large gaps between the pieces you are soldering?
    A) You may have to recut some pieces.
2) You may be using too much solder causing the seam to bulge over onto the glass. "Pull" or "bleed" the excess solder from the seam.
3) Is the copper foil too wide? This is another common mistake for beginners. Remember that the width of the solder seam is determined by the width of the foil. An attractive solder seam is accomplished by using a foil that shows about 1/16" on both sides of the glass.

Problem: My solder seams are irregular in width.

Solutions/Explanations:

1) You may have poorly fitting pieces that create different size gaps in your project. Recut these pieces.
2) Your foil may be applied unevenly on each side of the glass in some places. You may try to correct this by trimming the foil with a craft knife. If that does not work, remove the foil and start again.

Problem: My glass fractured while I was soldering.

Solutions/Explanations:

1) Your iron is too hot. Depending on what type of iron you are using, either turn the rheostat down or change to a lower temperature tip.
2) You "worked" too long in one location with the iron.
3) There could have been a small chip or crack in the glass which was expanded when it was heated by the iron.

Problem: My solder bead is not bright and shiny. It appears dull and splotchy.

Solutions/Explanations:

1) The solder was applied too cold, so it never fully reached its "liquid state." Turn up the temperature if you are using a rheostat or change to a higher temperature tip if you are using a temperature controlled tip.
2) You may not be using enough flux to "wet" your foil or lead and create a proper solder condition.
3) If you're using 50/50 solder, try 60/40. Because solder crystallizes as it cools through the pasty range, 50/50 is more prone to having a textured look on its surface because of its considerably larger pasty range.
4) The solder you are using may be of inferior quality.

Problem: My solder is "spitting" as I work. What's wrong?

Solutions/Explanations:

1) You are likely using too much flux. It is literally boiling when you apply the solder. Wipe some of the flux off with a paper towel and try soldering again. You may find areas that now need a little more flux, because you removed too much.

2) If the spitting only occurs on the back side of your project (or the second side you are soldering), the problem is still too much flux, but the cure is different. When you use too much flux on the front side of the project, the excess to flows through the panel, so the spitting isn't as bad as it could be. When you use too much flux on the back side of the project, it can't flow through to the front, because the front is already sealed. The obvious cure for this problem is to use less flux the next time. But what about now, when you already have too much and can't remove it from between the glass? The only good solution is to apply your solder, and allow the flux to boil up and out of the seam. (Keep your face as far away from the project as you can.) Once it stops spitting, you can remelt the solder and make it look as good as new.

Problem: I have gooey, glue residue along my solder seams that won't wash away.

Solutions/Explanations:

1) Adhesive from foil may be working up and out onto your glass. This can be caused by poor foiling or burnishing of the copper foil, which allowed flux to seep underneath the foil. To correct this use a cuticle stick or soft toothbrush to clean adhesive away.

2) Your iron is too hot, causing the adhesive on the back of the foil to melt and seep out onto the glass. Depending on what type of iron you are using, either turn the rheostat down or change to a lower temperature tip.

3) If you reworked a seam too often, it may have loosened the foil. Allow the seam to cool to the touch and gently press the foil back down to the glass.

Problem: Attached hooks and rings are pulling away from my project.

Solution/Explanations:

1) Hooks and rings should never be attached to just a foiled edge. Attach hooks/rings to vertical seams in the piece or at a juncture between a vertical seam and the perimeter.

2) If there is no vertical seam or intersection, then attach the ring/hook to a horizontal seam in the piece.

Problem: My solder has a white chalky growth on it. What did I do wrong?

Solution/Explanations:

1) All of the flux was not washed off of the project after it was soldered.

2)The project was not sealed with a finishing compound or wax, or it has worn off. Use 000 steel wool to remove the patina and any remaining wax. Clean the project thoroughly paying special attention to the corners and edges. Reapply the patina and wax.

3) The project has been exposed to the outside elements. Most waxes are intended for indoor use only. Others can be used outside, but must be reapplied regularly. Projects that will be exposed to the elements are better constructed using the lead came method.

Glossary of Soldering Terms

Antimony

An element used in the production of some solders. It should be avoided for use in stained glass.

Ceramic Heater

A type of heating element comprised primarily of ceramic, noted as extremely fast heating and efficient.

Chisel Tip

A soldering iron tip shaped like a chisel tool. This is the most common shape used for soldering stained glass. Chisel tips are made in a variety of sizes, the most common being 1/8”, 1/4” and 3/8”.

Heat Sink

A device used to draw or absorb heat being generated by another source. For example, an object being soldered acts as a heat sink to the soldering iron.

Decorative Soldering

Any decorative effects created in solder. These effects are created with a soldering iron, usually with a very narrow tip. Special solder, like 63/37 or QuickSet, make it easier to create special effects because it has a “zero” pasty range.

Eutectic Point

An exact single temperature point at which an alloy goes from solidus to liquidus with no pasty range. For example, the eutectic point of lead and tin is 361^0 F. This point is obtained only by 63/37 tin/lead alloy.

Flux

A chemical agent used to remove compounds from the surface of metals during the soldering process. (See organic and inorganic flux.)

Idle Temperature

A very low temperature at which the iron is on, maintaining the capability of a more rapid heat up than if the iron was off or “cold”. This is usually between 200^0F and 300^0F.

Inorganic Flux

A flux comprised of one or more inorganic salt such as zinc chloride or ammonium chloride. Inorganic fluxes are more corrosive and conductive than organic fluxes,. They are effective on all common metals.

Leaded Solder

A material used to join metals comprised of tin and lead.

Liquidus

The temperature at which a pure metal becomes completely molten or liquid.

Mica

A mineral based material used as a construction component in wire wound type heaters of soldering irons.

Organic Flux

Organic fluxes are not as corrosive as inorganic fluxes. They are often used when the surface of the glass may be effected by the flux, such as painted glass.

Oxides

Debris on the surface of a metal which is the result of the reaction with chemicals in its environment. Oxides must be removed mechanically (with steel wool or a brass brush) and chemically for proper wetting to occur.

Pasty Range of Solder

The temperature range which is the difference between the solidus and the liquidus temperatures. This is sometimes referred to a the “working range”.

QuickSet™

Another name for 63/37 solder. See decorative solder.

Recovery Time

The time required for a soldering iron to reach soldering temperature after it has hit a “cold spot”.

Rheostat

The term applied to a soldering iron control which is used to vary the temperature of the heater in the iron.

Solder

An alloy of two or more metals with a liquidus temperature of less than 800^0 F.

Solder Bead

The term used to describe the look of solder when it has been properly applied to a copper foil seam.

Solidus

The temperature at which a pure metal or alloy goes from liquid to solid (or “freezes”).

Temperature Control

An electrical or electronic device into which a soldering iron is plugged, or which is within a soldering iron. The device is used to vary the temperature of the soldering iron heater.

Tinning

Applying a thin layer of solder to a metal surface. Most commonly used in reference to the copper foil technique.

Tinning Block

A block of sal-ammoniac on which a soldering tip is cleaned and resurfaced with a layer of solder. It is not actually used for soldering.

Tip Tinning

The process of renewing a soldering iron tip using a sal-ammoniac (tinning) block.

Wetting

The term used to describe the proper flow of liquid solder, promoted by flux, on the surface of another metal. “Wetting” is necessary to form a proper soldering joint.

Wire Wound Heaters

Soldering iron heaters constructed with heating wires wound in a coil around Mica.

Soldering & Desoldering

Soldering/Desoldering Tools & Accessories

Soldering Station with LCD Display, ESD Safe 400 Series

17400

- High-quality sensor and heat exchange system guarantee precise temperature control at the soldering tip
- Soldering iron tool heats rapidly from room temperature to 350C in 30 seconds
- Suitable for general purpose soldering as well as specialized lead-free soldering applications
- Sponge and coiled brass tip cleaner ensure a clean soldering tip free from debris and corrosive material
- Strong, deluxe iron holder provides safe secure place to store heated iron between uses

Product ID	Description
17400	Soldering Station with LCD Display, ESD Safe 400 Series

Soldering Station with LCD Display, ESD Safe 405 Series

17405

- LCD temperature control display with blue backlight
- Long lasting, durable high - quality ceramic heater
- Sponge and recessed area provides a convenient method for cleaning the tip
- Suitable for general purpose soldering as well as specialized lead-free soldering applications
- Safety guard iron holder

Product ID	Description
17405	Soldering Station with LCD Display, ESD Safe 405 Series

Soldering Kit - 6pc

17501

- 40 Watt Soldering Iron heats up to 900° F
- Ideal for use on electrical/electronic components, audio equipment, etc.
- Includes desoldering pump for removing liquid solder
- Provides basic tools needed for many soldering projects
- 6 Pc kit comes complete with replaceable fine tip

Product ID	Description
17501	Soldering Kit - 6pc

Soldering Kit - 7pc

17502

- 40 Watt Soldering Iron heats up to 900° F
- Ideal for use on electrical/electronic components, audio equipment, etc.
- Includes desoldering pump for removing liquid solder
- Provides basic tools needed for many soldering projects
- 6 Pc kit comes complete with replaceable fine tip

Product ID	Description
17502	Soldering Kit - 7pc

Soldering Iron 80W with Fine Tip

17510

- Ideal for general purpose soldering applications including metal board, tube or large components
- Round, soft grip, non-slip handle
- Durable cord with a 5-foot reach
- Fitted with long life replaceable fine tip

Product ID	Description
17521	Soldering Iron 40W with Fine Tip

Soldering Iron 40W with Fine Tip

17521

- Ideal for general purpose soldering
- Round, soft grip, non-slip handle
- Durable cord with a 5-foot reach
- Fitted with long life replaceable fine tip

Product ID	Description
17521	Soldering Iron 40W with Fine Tip

N-Series Soldering Iron Tips



- Long life, lead-free soldering iron tips
- Replacement tips for soldering the different components of PCBs
- Five different sizes
- Includes two tips
- For use with 17400 & 17405 ESD Safe Soldering Stations with LCD Display

Product ID	Description
17400-N9-1	N-Series Soldering Iron Tips (N9-1)
17400-N9-2	N-Series Soldering Iron Tips (N9-2)
17400-N9-3	N-Series Soldering Iron Tips (N9-3)
17400-N9-4	N-Series Soldering Iron Tips (N9-4)
17400-N9-5	N-Series Soldering Iron Tips (N9-5)

C-Series Soldering Iron Tips



- Long life, lead-free soldering iron tips
- Replacement tips for soldering the different components of PCBs
- Four different sizes
- Includes two tips
- For use with 17521 Soldering Iron 40W

Product ID	Description
17521-C1-1	C-Series Soldering Iron Tips (C1-1)
17521-C1-2	C-Series Soldering Iron Tips (C1-2)
17521-C1-3	C-Series Soldering Iron Tips (C1-3)
17521-C1-4	C-Series Soldering Iron Tips (C1-4)

B-Series Soldering Iron Tips

- Long life, lead-free soldering iron tips
- Includes two tips
- For use with 17510 Soldering Iron 80W

Product ID	Description
17510-B5-1	B-Series Soldering Iron Tips (B5-1)

SMD Soldering

Your reference guide to soldering with surface mount devices

Edited by Lim Siong Boon, last dated 06-May-09.

email: mail@siongboon.com
website: http://www.siongboon.com

Short cut to your reference guides and charts

1. Introduction to SMD soldering
2. SMD soldering (prototyping board)
3. SMD soldering (prototyping PCB socket 2.54mm pitch)

1. Introduction to SMD soldering

SMD IC stands for surface mount device integrated circuit, or commonly known as SMT surface mount technology. Why go into SMD? Small in size, light in weight. This is the advantage of smd. Being small, engineer is able to design small electronics gadget that people can carry around. It is quite obvious that people prefer small mobile phone.

The ultimate advantage will be lower cost to consumer. Being small in size, the printed circuit board (pcb) can be small, meaning low cost. Transportation cost can be reduce because it is now lighter and more products can be packed into the same box. Space required is less, meaning cost saving on the warehouse storage. PCB board is easy to route without the through hole. Better signal integrity. Easily assembled by machine. There is too much advantages. Going SMT is certainly the way forward.

Technology evolution, from big to small.

A phone small enough to carry around.

Smaller mobile phone

Even smaller phone

Mobile phone as thin as biscuit.

I used to build circuits using dual in-line package (DIP or DIL) IC only. I hardly thought of using surface mount device/component (SMD) because I have great doubt that I can solder the fine legs of the IC chip. The pitch for the older DIP IC package are 2.54mm. Pitch is the distance between adjacent pins as illustrated in the picture. Most IC comes with a variety of packages. The IC that I know of, offer both the SMD and DIP packages. I

Through hole packages

	DIP - 8 pins

thought that I will never ever need to use smd packages until one day, I have no more choice. I managed to pick up new circuit designs, and discover more and more new IC chips. Most new IC chips design do not have DIP packages. You can hardly find one. I realised that in order to implement better circuits, I need to learn to use new IC chip. In order to use the new chip, I have to find ways to solder smd components. That's where I venture into the world of smd.

Nowadays people prefer to use smd, because they are small in size, which turns out to be cost efficient fabricating small PCB. With smaller PCB, space & weight is saved, resulting in lower cost for the transportation/distribution and storage.

Research and research, I got to know from other electronics guru that smd is in fact easier to work with than through hole. I try it out and from that day onwards, I am in love with smd components. Small to solder, but it save me the effort to cut the lead for through hole component. I managed to store my component using minimum box and space. There are many many advantage to work with smd.

Many people might think that you need special tools like a rework station or fine tip iron to solder the small smd components with small pitches. With the correct technique, you can use your soldering iron to do the soldering. In fact my 60W goot TQ-95 soldering iron has quite blunt tip. So thick that most people think that it is not possible to solder smd IC with fine pitches. Fine tip iron is easy to reach the fine lead, but I find that it is not as hot as the same iron with blunt tip. If you prefer fine tip, I will recommend hotter soldering iron or those which can allow you to adjust the temperature, they can be hot. I managed to solder smd package TQFP, SSOP QSOP with pitch as small as 0.5mm. Width of the lead of about 0.3mm.

Dealing with SMD components do not necessary requires you to fabricate a professional pcb board. You can also mount smd components on low cost prototyping board. To start off implementing smd components, you might like to try using the soic package. Quite common at this point in time, but may just phase out as what has happened to the dip packaging. SOIC has a pitch of 1.27mm, which is exactly half of DIP packages. This size is great because I can solder the IC to the same old 2.54mm pitch prototyping donut padded board. What I usually do is to cut the donut pad into half. Soldered onto each pad is two pins 1.27mm apart.

You can refer to the following article, for further illustration.

"SMD soldering (prototyping board)"

	
	resistor
	capacitor
	inductor
	diode

SMD packages

1.27mm Pitch	SOIC - 8 pins
	TQFP - 44 pins
	resistor
	capacitor
	inductor
	diode

With so much advantage there is indeed a disavantage. SMD IC comes with many type of packages with different pitches. Unlike DIP IC, the pitch is typical 2.54mm. I can easy purchase a prototype board with 2.54mm, and almost all the DIP will fit to the board. SOIC package can still be mounted onto the 2.54mm prototype board. The rest of the SMD IC chip has quite a wide range of completely different packaging. This make them difficult to start with, without having to fabricate a PCB.

There are actually solution to this. Most IC company usually introduce their IC chip together with a prototype board for the IC.

Another solution will be to use a pre-fabricated prototyping board that allows mounting of various smd footprint. You can search for the various names such as







Various distributor for the prototyping adaptor

- prototype adaptor
- chip adaptor
- smd prototyping board
- smd to dip adaptor
- smd socket
- smd adaptor
- smd to 2.54mm converter
- SMD to DIP converter
- chip carrier

You can refer to the following article, for further illustration.

"SMD soldering (prototyping PCB socket 2.54mm pitch)"

In prototyping with DIL IC, pcb mount IC socket is usually used, so that the IC can be removed easily if damaged. Some sockets are designed for programming used where the chip can be inserted and remove easily for programming purpose. To remove the component, you need not have to do de-soldering. Like DIL package, smd also comes with their own IC socket. There are many variety of smd packaging, and getting the socket for your smd components is not going to come cheap & easy compare to DIL. Therefore I usually built prototype without any sockets for smd design. After numerous attempts designing and building of circuits, you will definitely attain a certain level of confident on your design without considering IC socket. Without the socket, cost and space are saved significantly.



DIL IC sockets/ holder. Turn pins designs is of better quality.

Various distributor for SMD socket

SMD IC sockets:



The headache will come when you really need to removed the smd IC. How do you remove the IC from the PCB? For de-soldering of smd component more than 3 leads, you can add in more solder to connect up the IC pins heat pins on all the sides of the IC and eventually pull out the component. It is easier to use the rework station or IR heater to de-solder smd components. The rework station uses hot sir to melt down the solder on the board. You will need to aim the hot air at the solder joint.

Rework Station

If you do not have the lurxy of getting the rework station, another possible method might be to use a special solder that has lower melting point. LowMelt® DeSolder Wire. A lower melting point means that the solder will takes a longer time to cool down to a solid. This allows you more time to remove the IC after heating up the solder. The solder is flooded onto the pins of the IC. The pins are heated up together using a soldering iron and the smd IC can then be removed easily with a tweezer.

Various type of smd packaging

* SOT, SC

* SOIC, ExposedPad™

* SSOP, ExposedPad™

* TQFP, ExposedPad™

* TSOP

* TSSOP, ExposedPad™

Low melt solder wire



* PLCC

* LQFP, ExposedPad™

* LGA

* PBGA

* PSOP

* Dual Row MicroLeadFrame®

* LQFP PowerQuad®

* MicroLeadFrame® (MLF®)

* MQFP PowerQuad®

* PSvfBGA

* SuperBGA®



* TapeArray® BGA

* tsCSP



* Ultra CSP™



* CABGA, CTBGA, CVBGA


PIC control
Circuit Design & Fabrication
www.pic-control.com

Singapore Customized, custom made Electronics Circuits & Kits

2. SMD soldering (prototyping board)



The prototype board above has pad with 2.54mm pitch and is designed for DIL and through hole components. The board is easily available from local store. Dealing with smd components on this 2.54mm pitch board is not difficult as well. I have been using this board to solder quite a number of surface mount components.

- SOIC
- DPAK
- SOT23-6, SOT-3
- TO-263
- PSOP







High pin count component with pitch less than 1.27mm will not be suitable to mount onto this board. For passive smd component like resistor, capacitor or inductor which only have 2 pin, mounting is simpler. Size is not an issue soldering onto the board.

Align the SMD IC to the position on the pad. Mark out the pad for the cutting to be done.

Use a penknife to cut the donut pad into half. Ensure that the half pad does not short circuit using your multi-meter. Sometimes the cut may not be deep enough or conductive reside between the gap resulting in a short circuit. Remember to ensure that each is proper cut before you start to solder.

Align the smd with your finger or tweezer and begin soldering one of the pin. Check if the IC is still properly align after soldering the first pin. If not, heat up the soldered pin and realign again. After the ICis align, solder all the rest of the pin. If the solder bridge across to the adjacent pin, use a soldering sucker to remove the excess solder.

The cut between the pad usually make the solder harder to bridge across the adjacent pin. Bridging is still possible, and it is quite easy to have it removed.







Example of building the circuit using surface mount component on the prototyping board with 2.54mm pitch pads. As shown above, the pins are being wired by fine wire wrapping wire. The single core wire is very flexible and comes in a variety of color, making it easy to identify the type of signal being carried by the wire.

SMD ribbon cable connector being soldered onto the 2.54mm pitch prototype board.

3. SMD soldering (prototyping PCB socket 2.54mm pitch)

What you need...

List of items:
- Surface IC chip (TQFP package)
- Surface mount IC adaptor or converter
- Soldering Iron
- Tweezer or Pincer
- Solder with flux core
- Soldering Flux
- Stick for coating flux
- Wiping paper
- Tinner



PIC-200 smd to 2.54mm pitch adaptor

from PIC control.



INTRODUCTION

In this setup, I am going to solder a surface mount microcontroller (TQFP 44 pins) onto a smd adaptor. The adaptor will then be used on the commonly available prototyping board, so that I can try out my new design for circuit control.

TQFP, QFN and SOIC are quite some common footprint for prototyping smd microcontroller from 18 to 64pins. This prototyping adaptor pic-200 (on the left) that I have is an ideal adaptor for my microcontroller. Converting the smd device into 2.54mm, I can easily mount the smd unit onto my 2.54mm pitch prototyping board. It is available locally.



Prototyping board with 2.54mm pitch donut pads.

The pic-200 smd adaptor originate from PIC-CONTROL and is well documented. Commonly used smd footprint can be found on either the top or bottom side of the pcb adaptor. These are some of the smd packages that can be mounted onto pic-200 adaptor.

IC TQFP-44	**Front**	**Back**







Holding onto the side view of the QFN package IC.

With a wide range of smd components that can be mounted, it is easier to stock up this pcb adaptor for future prototyping use.

The following article is about getting my smd microcontroller PIC24FJ64G004 soldered onto this board. After which I will be on my way to do prototyping for my new control circuit.

This smd adaptor origined from PIC-CONTROL. For other type of adaptors, you can also refer to other manufacturer as mention above.

click here to

Buy this SMD Adaptor Now at the PIC-store

PIC-store

<Step 1>



Before soldering, ensure that the soldering pad on the PCB is free of oxidation. PCB is usually tinned to protect the copper surface from oxidation. In cases where the surface is oxidized, you can try cleaning the surface with a contact cleaner. Apply the solution with tissue paper or toothbrush to clean up the contact. This solution make the PCB board rather oily, which I don't quite appreciate.

Contact cleaner.

LPS
LVC
CONTACT CLEANER

Let us start our smd soldering here. Soldering surface mount component. The first important thing to introduce would be the solder.

There are many type of solder. Choosing the correct solder takes a bit of some knowledge too. Leaded or lead free solder? The industries is moving towards Pb free components & PCB, calling for unleaded product. Lead is toxin and not environmental friendly. I would advise ou to wash your hand after soldering or handling pcb board. A soldering fume extractor to vacuum the smoky fume would be quite comfortable for your soldering. The smoke is quite choking and a health hazard if you breath that in.

soldering fume extractor.

Solder also comes with a variety of metal alloy combination. Nowadays it is common in solder core to contain flux. If the solder do not have the flux in the core, the flux have to be manually applied onto the metal surface before the soldering beginning. The flux cleans up the soldering surface, and also make the solder flow rather smooth like liquid. One of the important ingredient to make a good solder joint lays in the soldering flux.

Solder wire also comes in a wide range of diameter to choose from. Generally I use 0.8mm soldering wire roll with flux at the core. Smaller diameter solder wire allows you a better control of the amount of solder to apply. For soldering larger pins or connector component thicker diameter wire will be preferred. Wire too thin is rather troublesome, because you need to feed in a longer length of solder in order to solder the large surface/lead. For general purpose PCB board soldering 0.8mm wire fits somewhere in the middle. Not too thick nor too thin. For smd components, diameter smaller than 0.8mm is preferred. Using 0.8mm for smd soldering is not of any issue.

Solder wire 2mm

1.2mm

1.0mm

0.8mm

0.5mm

<Step 2>



One of the pad being tinned.



Align smd IC to the respective pad.

My microcontroller TQFP package has 44pins around the square package. To secure the package to the adaptor, I will need to solder one of the pin to the board first. It is important to solder only one pin. In case of mis-alignment, we can correct it easily. If more pins are soldered, it will be more difficult to correct any alignment.

Pin 1 of the adaptor pad is first tinned with a layer of solder. A tweezer is then used to align the IC chip on the pad. The IC is secure to the board with a slight touch from my soldering iron, soldering the IC pin to the pad.

The important factor to consider would be the heat generated by the iron. I prefer to use a 60W iron, which still works well in air-con room. A lower wattage or fine tip iron will not heat up that well in colder environment.

Goot TQ95 60W

If you prefer a fine tip, perhaps the soldering station will be more suitable. The iron temperature can be adjusted to a higher or precise temperature for the component that you want to solder. Component with thick metal contact like connector, heat sink, for thick cables should be solder with a


IC being fixed in position


Checking if alignment is correct.


Flooding the pins with the rest of the solder.


Pins flooded with solder

higher temperature. The iron should be held on longer, in order to have the component fully heated up before any solder is applied.

Solder Station

For soldering the IC pin to the pad, you can start off by heating up the pad. Then while heating up the pad, touch the IC pin and apply the solder wire directly to the pad or IC pin, allowing the solder to flow like liquid. The IC pin is heated last to minimize the chance of over heating the pin. If it doesn't flow very well, you can manually some flux to the joint. The solder wire should not touch the iron directly, because this will vaporize the flux, and solder flow will be restricted.

Heat up the lead and pad longer allows the solder to flow and form a good joint. Not for too long as it can also damaged your IC. You should be able to see the solder flow eventually onto the lead & pad. With a bit of practice, you will see the difference between a quick solder touch and another one with lead & pad heat up a little bit longer. It takes a number of practice to get a good joint with minimum amount of heating time.

The soldering iron that I use has rather thick tip, but that does not matter when I do soldering for the smd microcontroller. All we do is to flood the pins with solder. They can be be suck up later.

There is a technology known as ultrasonic soldering. The soldering iron tip has this micro vibration which helps the solder to flow more easy without much use of flux. It can also solderthose difficult to solder material. The following is one article that I found that describe about it. [- Soldering the unsolderable].

<Step 3>



I have applied more flux at this stage. It should have been applied before flooding the pin, but it doesn't matter too much. The flux will make the solder rather liquid so that it is easier to suck up the excess solder.

ACID PASTE FLUX
SP-30
solder flux paste



Baker Soldering Fluid

<Step 4>

The flooded solder is being heated up, and the excess solder are being sucked up.



<Step 5>

Each pins is being touch up, ensuring that the pin is solder to pad and that they are not bridged across to the adjacent pins.

Now we have got our smd component soldered onto the board.



<Step 6>

The flux helps a lot in doing a good solder but it often leaves the board with tiny dots of transparent strain, a bit sticky, also known as grease or flux residue. The board looks untidy with these tiny bits of grease.

These are the various recommended cleaning solution for pcb.
- 50% Alcohol + 50% Water
- Thinner
- Flux remover
- Multicore Prozone MCF800
- Solvent-> Bromopropane; propane, 1-bromo-; propyl bromide (Chemical Formula: C_3H_7Br)





Alcohol MSDS (Material Safety Data Sheet)

Thinner MSDS (Material Safety Data Sheet)

ELECTROLUBE
FLU
Electrolube, FLU Fluxclene Cleaning Solvent, pdf file

HEAVY DUTY FLUX REMOVER
MG Chemicals 413B Heavy Duty Flux Remover

MGC-850 Stainless Steel Cleaning Brush
Brush for the crush

Flux Remover

Multicore Prozone MCF800

Besides using chemical, or after using chemical, there may still be some white blur stain. Those are flux spread dry up on the surface. Using a hot air blower, or heater on the surface can melt the dry up flux, and recover the smooth shiny PCB board surface again. Clean away the melt flux immediate after the heat.

Using alcohol is strongly recommended. Thinner is not suitable for certain plastic/material. Care is required when using thinner for cleaner. Using thinner on the PCB, copper pads and soldering joint isn't a problem. When use on plastic, you are advise to do a trial to ensure that the material is able to with stand thinner solution. Flux remover is commercially ready mixed solution. From what I learn in the manufacturer website, they are non-flammable chemical solution.

CAUTION

Alcohol & thinner has a lower flash point, and catch fire easily. You have to be extremely in handling and storing these flammable chemical. Do not store or work on the chemical near electrical appliances, hot area or things that can cause spark. Keep your windows open to allow air to circulate while working with these chemical. They may cause headache, dizziness and uncomfortable when inhaled.

Chemical comes in different level of grade. A slight different in the chemical concentration or purity can results in a large difference in cost. Alcohol can be expensive. For pcb cleaning purpose, request for technical grade alcohol. Higher grade alcohol is typically used for consumption or lab experiment purpose. Since we are using it for cleaning, there is not much advantage in using high quality chemical which is expensive. Dickson chemical is specialized in high graded chemical for laboratory use. They do sell lower cost technical grade alcohol. They are not suitable for consumption but is ok for cleaning application.

Dickson Chemicals

Dickson Chemical selling Technical grade alcohol

You can easily buy thinner from your local hardware. Typically used for cleaning your brushes after all the wall painting works.

The Science Of Zephyrtronics

Non-flammable Flux remover

click here to

Buy Cleaning Solution Now at the PIC-store

PIC-store

These are other recommendation in the web. After researching further, I would advise not use them. These chemical are of health hazard. Exposure will have severe adverse health effects.

- 50% isopropanol + 50% water
- Trichloroethylene
- Carbon tetrachloride

Isopropanol (true chemical name) is also known as Isopropyl alcohol or 2-propanol. 2- is refer as Iso. Other chemical may starts with 1- refer as N. These are some jargon used in the chemical industrial. I managed to learn a few of the terms from the vendor.
Trichloroethylene (true chemical name) is typically used for degreasing the metal. It is an extraction solvent for oil. Another name for Trichloroethylene is Trielin. Based on some read up, they can cause cancer.
http://www.answers.com/topic/trichloroethylene

Carbon tetrachloride can harm our environment, producing CFC which deplete the earth's ozone layer. http://en.wikipedia.org/wiki/Carbon_tetrachloride

Initially I tried using contact cleaner to clean the stain off. I use cloth or tissue but the fabric is often tear by the component sharp edges. Most corners are not easy to reach. Later on I tried using a toothbrush, the result is better.

For mass cleaning job, you can try using the ultrasonic pcb cleaner. It is a deep metal container for the solution, using micro vibration to shake off the dirt. I have never tried on it before, and I believe it is the same machine people used for cleaning their jewelry. Basically, you will need to dip the pcb board into the solution, and the ultrasonic will be activated to do it's job. The solution used is the same as manual cleaning, requiring 3-5 minutes of cleaning.

Ultrasonic cleaner

Ultrasonic jewelry cleaner

There is also a flux that does not leave residue on the PCB. I found it on the internet, and have not try it before.

INTERFLUX, IF 2005M No-Residue™ flux, pdf file

Article relating to removing flux residue:

- pcb cleaning - Aqueous Cleaning Process.pdf
- pcb cleaning - Flux Removal, nuxx.pdf
- pcb cleaning - pcb cleaning article.pdf
- pcb cleaning - PCB Cleaning, Printed Circ.pdf
- pcb cleaning - pcb washing chemical composite.txt
- pcb cleaning - remove solder flux.pdf
- pcb cleaning - Solvent washing PCB boards.pdf
- pcb cleaning - washing the board using alcohol.pdf
- pcb cleaning - PCB cleaning article Inventec_S24_03.pdf

<Step 7>



A close up view of the clean and neatly soldered surface mount IC on the prototyping adaptor. Soldering smd components is simple and fast with a bit of practice. Small and easy to clean up. There are too many advantage in working with surface mount, compared to through hole components.

This is the end of the short demonstration on smd soldering. I hope these article can provide you some insight and confident to start experimenting circuits using surface mount components.

Video available. Please click here,
smd soldering.mpg (25MB)
smd cleaning pcb.mpg (5.5MB)

Article on smd soldering.
- 2010-07 How to Solder Surface-Mount Devices.pdf

click here to
Buy this SMD Adaptor Now at the PIC-store

PIC-store



Singapore Customized, custom made Electronics Circuits & Kits

Various Chemical Reference:

Alcohol 70% + Distill Water 30%
MDX4-4159
7MHFE-71DE

Cyclohexanone
Methylethylketone
ethylacetate,
Silicon Wacker
Wacker M4503, General purpose mould making silicon (Using Two Part Silicon Mold Putty to Make Molds)
http://www.kirkside.com.au/, Mould Material Specialist

Propanol, used to clean PCB. (close to white electric oil)
Acetone, remove away ink printed on PVC stickers
n-Hexane (white electric oil)

smd glue for surface mount component mounting / soldering use
Seal-glo NE series, NE3000S, NE8800T, more Seal-glo

email: mail@siongboon.com
website: http://www.siongboon.com

Keyword: surface mount soldering, smd adaptor, smd to 2.54mm convertor

Surface Mount Soldering Procedure

We believe that the following procedures describe the simplest way to reliably assemble surface mount components without special tools. The only tools required are a pair of fine-tip tweezers, a rosin based flux pen, rosin core solder (.025” dia. preferred), and a soldering iron with a small, clean tip. A spool of fine (0.075”) solderwick will come in handy if you need to rework connections. You will need isopropyl alcohol, cotton balls, and cotton swabs for cleanup. If you have access to hot air rework tools and the skill to use them, feel free to use them instead.



A proper solder joint with fillet



Proper joints



Poor joints



Placing the component

Soldering surface mount components is not difficult, but it does require good eyes, a steady hand, and a soldering iron with a small, clean tip. The illustrations at the left show a proper and a poor solder joint. In the proper joint, the flux has “wetted” both mating surfaces, allowing the molten solder to adhere to both the printed circuit board pad and the component lead. In the illustration of the poor connection, insufficient heat or flux has forced the solder to ball up on the end of the component, without making it to the PCB pad. The component is not attached properly, and the electrical connection will be intermittent at best. This connection can be salvaged by applying flux and heat to the PCB pad to get the solder to flow to the area between the pad and the component.

The most important characteristic of your soldering iron is that it must be equipped with a *small, clean* tip. If the tip is too large or is covered with oxidation, creating a well-flowed solder joint will be nearly impossible. Wipe your tip on a sponge before each joint - it must be shiny and well-tinned in order to transfer its heat properly.

You will find it easiest to work on your board if you clamp it in a moveable vise or stick it to a small block of wood with double-stick tape. This will allow you to rotate the board to whatever angle is most comfortable for access to the component being installed. If you try to hold the tiny parts at awkward angles, you will not have good results!

The first step is to apply a small bead of solder to one of the PCB pads for the component to be installed (the left-hand pads of R1 and R2 in the photo at right). The bead should be approximately 0.020” to 0.030” high (you may want to reevaluate your bead size after you have completed several joints). Apply some liquid *rosin based* flux from a flux pen to the solder bead and to the other pad(s) for the component.

Next, using a pair of tweezers, pick up the component to be installed and place it over the appropriate pads.



Affix the part by reflowing the first solder bead



With the part in position, solder the other end

With the part in position, move the soldering iron to the solder bead on the PCB pad. Apply a small amount of heat from the iron to flow the bead, simultaneously lowering the part against the board and correcting for any rotational misalignment. Remove the iron and allow the solder to cool. Inspect the joint -- at this point you are not concerned about the quality of the actual solder joint, just the positioning of the component. The part should be flush against the PCB, with both ends properly contacting the pads. The part should be straight, and centered between the two pads.

Apply a liberal amount of liquid flux (again, a flux pen is the ideal applicator) to both ends of the component. Heat the currently unsoldered end of the component and the adjacent pad with the soldering iron, and carefully wipe on a small amount of solder. You want a small fillet as shown in the earlier illustration, not a large glob of solder. Make sure that the solder has flowed onto the pad as well as the component lead - don't be fooled by a lump of solder on the end of the component that doesn't flow under the component and onto the PCB pad.

After the second end is soldered, go back to the original solder joint and reheat the solder. The flux will allow the solder to flow freely, and a good fillet should be observed. If there seems to be insufficient solder, add a little more. If either of the ends appears to have an excessive amount of solder (a large blob sticking up above the part) it can be removed with solder wick. Apply flux to the blob and the wick, position the wick over the blob, and press lightly on the wick with your iron. As the heat is conducted through the wick the solder blob will melt and be drawn off by the wick. You may end up removing too much of the solder, in which case you can reapply a *small* amount of fresh solder to the joint.

After the joints have cooled, inspect them carefully to make sure that they are solid and make contact with the board. If you have any doubt about the quality of the connections, apply more flux and reflow the joints until you are satisfied.

The same procedure is also used for installing components with three or more leads (transistors, ICs, etc.). Start with a bead of solder on one pad, position and "tack" the part, then add more flux and solder the remaining leads. Don't forget to reflow/improve the first "tacked" connection if necessary.

Electrical Wire soldering For Beginners

by Randy Glass

DISCLAIMER- First, soldering can be dangerous. This lesson is not meant to be everything you need to know. Your safety is up to you, and you take full responsibility for any damage or injury caused by these instructions, whether as an act of omission or commission on your part or mine. Be aware that an improperly soldered wire can lead to fire, loss of vehicles, injury, and even death. By reading and/or using these instructions you take full responsibility and release me from all liability. Second, I took these photos as I did the work, pressing the remote control for my camera with one finger as I held the soldering pencil in one hand and the solder in the other. I apologize for any images that might be out of focus or poorly composed.

If Yogi Berra ever wrote a book on motorcycles he would probably say, "We seem to spend around forty percent of our time taking things apart, and the other seventy-five percent of the time putting them back together." Some things are easy to put together. We use specialized fasteners like nuts, bolts and screws to hold things together that, some day, we might want to take apart again. But there are some things that, once put together, we would like to know that, to some degree, our fastening system is permanent. One of those places is in electrical wiring. When a wire breaks or needs to be fastened to a connector or another wire in such a way as to be dependable, then the very best way is to solder.

soldering is a method to attach one metal part to another. It is part of a family that uses molten metal to do this job. At the top of the ladder is welding. This is a very high temperature method that actually melts the parts a bit where they are attached, along with some other metal, usually in the form of welding rods. Next is brazing. This melts some hard metal, usually brass, into the gap between two pieces of metal. Normally, the surface of the material being joined is not melted in this process, but it gets very, very hot. Finally there is soldering. soldering flows some molten metal between metal parts at relatively low temperatures.

For our purposes I am going to speak of the type of soldering that attaches two wires together or one wire to a connector- the sort of soldering that any backyard mechanic might need to do when working on any electrical component or the wires that connect them together in almost any type of vehicle.

WHY solder?

Although there are methods that can be used to make these connections without soldering, they are usually inferior. soldering does a lot of things:

1) It Is Strong- You are connecting two metal parts with a liquid metal that becomes solid after it fills the joint and cools. When properly done it leaves no voids so the joint is very strong and the wire is well supported.

2) It Slows or Stops Oxidation - Because solder fills the joint it excludes air and moisture so the metal in the joint will not oxidize. This maximizes electrical flow over time.

3) It Makes An Excellent Electrical Connection- because the solder is a conductor it gives the wire more area from which it can flow electrons to whatever it is connected.

4) Non-permanent - Although soldering is very strong, it can be removed and the joint taken apart in the future if necessary.

5) Connectors do Not Need to be Crimped - Those little metal connectors that are designed to be crimped have a terrible habit of coming loose as well as breaking the little copper wires in the conductor making a weak joint as well as one that does not conduct as well as it should. They easily let air and moisture in which causes corrosion and that leads to poor and broken connections.

MATERIAL LIST

It doesn't take much to set yourself up as a soldering wizard. Here is a list (numbers refer to image to the left):

*1) **soldering Pencil -** Something around 25 to 40 watts would probably be fine for most electrical work. You don't need a huge soldering gun to do electrical work. A little smaller is actually better than too big, as we shall see. Get a brand-named pencil so that down the line you will still be able to



get replacement tips for it. A chisel tip as seen in the pictures that follow is best for most work but you might also need a pointed tip for more delicate work. Those old soldering guns are nice for making battery cables, but are generally too large for what we are doing. it would be like using a sledge hammer to make a picture frame- it would have to be a REALLY big picture frame!

There are also cordless, rechargeable soldering irons available. They generally run about $35-75 or so. Although these cost substantially more than a corded iron, and the replacement tips are more expensive as well, there is no cord to get in the way when working and as they can be carried along on trips. These generally have a built-in light as well making repairs at night easier. I normally loosen the lamp so that it does not light, so the battery lasts longer in use.

There are soldering tools that are actually little, refillable, butane-powered torches with a soldering tip at the end which is heated by the flame. As they are about the size of a fat ball point pen, they are another good way to get a portable soldering tool. These generally are available for less cost than the rechargeable irons mentioned above. I have used electric irons to solder around a gas tank on an automobile- something that I would never consider with one of these.

And a **soldering Pencil Holder** - Most soldering pencils come with a holder or a rest as seen here, but if not, get one. These metal stands are very handy and will help avoid melted parts and burned hands and work surfaces.

*2) **solder** - Resin core solder is what you want. NEVER use acid core solder on electrical components. The acid will stick around and continue to eat into components and wiring well after the soldering job is over.

Resin core solder can be had in various quantities, but I buy the one pound roll for around $12-15 which will be a lifetime supply for most folks. I use Kester brand "44" Resin Core solder in the .031 diameter size. This is about the size of mechanical pencil lead and works quite well for what you will be doing.

It use to be that a standard part of a soldering kit was a little tub of flux. This paste would be spread on the joint ahead of time to help clean the joint chemically as it was heated by the iron. It was necessary as flux-core solder was unavailable. If your wires are clean and you are using a quality, resin core solder, additional flux is not necessary.

*3) A**n Old kitchen sponge** or two

* **Tools** to work on wires such as a (4) wire stripper and a (5) wire cutter, and possibly needle nosed pliers and a small vise (not shown).

* 6) A few bits of **insulated wire** and an old spade connector or two on which to practice. Two or three feet of wire will do.

*7) **Heat Shrink Tubing** - I rarely use electrical tape any more. Heat shrink is really great! I usually buy it in three foot lengths in two or three sizes. This is a sort of memory tubing that, I believe, is made by heating a special tubing and stretching it and allowing it to cool while still stretched. it maintains that size. When heat is applied once again the tubing will shrink back down to its original size.

*8) Protection for the work surface like an old piece of 1/4" plywood about 12" square or such. An old piece of counter-top lamination works also.

* Wicking material (not shown)- You can purchase some special copper wick that is used to unsolder joints. This is usually not necessary, but handy at times, and inexpensive.

* **Eye protection**

* A Ventilated workspace

SOME WARNINGS

HEAT - A soldering pencil as well as molten solder are both really hot. They will burn you and it will hurt. It can hurt a lot. It can make your skin give off smoke and that smells bad. If left unattended a hot soldering pencil can cause fires, melt carpeting, burn workbenches, and make the cat dance like never before. An unsuspecting person can pick up a hot soldering iron and get a nasty burn (trust me on this one!). Never leave a soldering tool warming or hot and unattended.

Additionally, a hot soldering iron can almost instantly melt plastic parts and upholstery in a hurry. Use care when soldering as well as when moving the iron to and from the solder joint. If the cord gets caught when moving the iron it can easily cause you to drop the hot tool onto something expensive or painful. NEVER place a soldering iron on saddles, luggage, body work, painted surfaces, or on or near any heat-sensitive surface.

LEAD and VAPORS- solder contains a good amount of lead and handling it over a long period of time may have negative health consequences. The vapors caused by soldering can, over time, cause health problems as well. Work in a well ventilated area. I usually work out doors and use a fan to blow the vapors away from me. The smoke that is given off by the flux in the solder is also not a good thing to breathe.

MOLTEN METAL - When soldering (and particularly when un-soldering) it is very possible to flick bits of melted solder about. As this stuff is quite hot, even a small drop in the eye can cause permanent damage. Wear eye protection and do not wear your good glasses, or wear them under goggles. The dripped solder can melt plastic parts and permanently damage auto carpeting as well. Be aware of other folks or critters who may be in the area as well.

ELECTRICITY - You will be soldering on wires that, if shorted out, could cause a blown fuse, damaged electrical components, or melting wires and a fire. Always disconnect the battery when soldering wires on a vehicle and remove connectors from heat-sensitive components before soldering on them.

LETS GO

I could spend a lot of time talking about how it all works, but jumping right in is the best way to learn how to solder and I will explain as I go

Begin by creating a safe work area. One free of clutter, with sufficient light, and protected from the soldering iron and melting solder. Set the soldering pencil in its stand and plug it in. be sure that the cord is placed in a way that it will not be accidently pulled or tripped on, upsetting the soldering pencil.

While that is heating up, prepare your sponge. Wet it, squeeze out the excess water, then fold it in

half and rubber band it about half-way down.

Pull out about a foot or two of solder from the roll and touch it to the tip of the soldering iron. Always apply the solder to the flat parts of the tip and not to the sides. When the solder melts fairly easily, melt an amount all over the tip. There will be some smoke from the resin in the solder.

The solder you bought is actually a bit hollow. Inside of the metal there is a channel (or in some cases, channels) that make it sort of like a little garden hose. The channel is filled with a resin. When heated it melts and some of it burns off. The action of the resin when it is heated helps clean the surface to be soldered which helps the solder stick a lot better. Unfortunately, the burned resins can also leave deposits on the soldering pencil, and over time will make it difficult to solder. That's where the sponge comes in. After you have melted some solder onto the tip (about a quarter inch or so of the thin stuff) wipe the soldering pencil's tip off on the damp sponge a few times.

If you examine the tip of the soldering pencil carefully you will see that it is now covered with a thing coat of shiny, silver metal- the solder. You have successfully "tinned" the tip of the pencil. This keeps the metal tip from oxidizing and will assist you in soldering from now on. Always do this before starting a soldering job and occasionally during a larger job.

Place the soldering pencil back into its holder and let's prepare the wires. We are going to solder two wires together, making believe they have broken or need extending.

We start by "stripping" some of the plastic insulation away from where we want to connect the wires. The thicker the wire the more insulation we remove. For most common wires on a motorcycle or in a car, removing about 3/8 to � inch works fine. You will get a



feel for how much in a short period of time. When stripping wire be very careful not to cut the strands of the conductor.

There are special tools available for stripping wire that can save a lot of time. These can be as simple as a carefully wielded razor blade to fancy and somewhat expensive automatic strippers.



Once stripped, twist the strands together into a neat little bundle.

The exposed wires should look fairly clean and in most cases, shiny, but certainly not green or cruddy. If corroded, then the wires should be cut back and re-stripped until clean wire is found.



Now cut a length of heat shrink tubing off about an inch long. It should be of a large enough diameter that at least two of the wires you are soldering can easily fit into it at the same time. Slide the length of the tubing over one of the stripped wires- it doesn't matter which here, but in real life we would slide it over the lower wire or the one which slopes most downward away from the joint so it will tend to slide out of the way. make sure it is at least three or four inches away from the joint.



Now, twist the two wires together into a tight, neat pair. This is important because it helps create a good electrical connection. You also do not want any little wires sticking out. Start by crossing the wires about mid-strip, crossing them at about 45 degrees or so, and twisting in opposite directions. When done, the joint should be fairly strong on its own, holding the two wires together tightly. The connected pair of wires should be in line as if they are a single wire and not two joined together.

It's time to solder. Place the roll of solder on your left (if you are right handed) with a good length of solder hanging out of the roll. With the solder in your left hand and the soldering iron in your right hand, check to see that the tip is still tinned and shiny. If not, repeat the process with a bit of solder melted to the tip, then wipe the tip off on the sponge.

Melt a little ball of solder onto the iron....





...and immediately place the soldering iron under the twisted wires (if possible) so that the little ball of solder fills much of the gap between the soldering pencil and the wire. Since heat rises, placing the iron under the joint will heat it faster. The little ball of solder works as a heat conductor and will very rapidly conduct the heat from the soldering pencil's tip into the wires. If the ball of solder does not seem like it is contacting the wire very well, without removing the pencil from the joint, melt just a bit more solder in there by feeding the end of the solder wire into the tip. This will not only increase the contact area of the solder to the wire but it will also add a bit of flux that helps the solder adhere to the wire at this time.



After about two or three seconds, start to feed solder, slowly at first, into the void between the pencil and the wire. You should soon see the solder is flowing into the twisted wires. WHen that happens, increase the feed rate of the solder into the joint, and you can now also feed a little into the top of the joint. Don't move the iron's placement, jut take the end of the solder wire and touch it to the tip of the joint. Continue to feed solder until the individual wires are almost filled with solder and the entire joint has turned silver. When that happens, stop feeding the solder in and immediately but gently remove the soldering iron.

How long do you wait until feeding in solder? One way to test how long to wait is to touch the solder on top of the joint and wait until that area is hot enough to melt the solder. The amount of time it takes varies with the size of the wires to be soldered, the size of the solder, the wattage of the iron, the size of the irons's tip, the ambient air temperature, and other factors. Experience will teach you how long this takes.

The problem comes from waiting too long and putting too much heat into the joint. When you do that it begins to melt the insulation on the wires around the joint (you can see that beginning to happen above at the end of the insulation of the green wire next to the soldered joint). That is why I like tho flow the solder in from where the iron's tip touches the wire. This is the place that will come up to soldering temperature first, and then the flowing solder will more easily flow solder into the joint as it carries heat with it. The larger the wires, the longer it takes and the more important it becomes to feed in some solder from the top of the joint as well. Again, experience will teach you when that is necessary.



How much solder is enough? Too much? The correct amount of solder is used when the joint is fairly all silver colored but still shows the "outlines" of the individual strands of wire in the joint. If there is very much in the way of copper colored wire showing then you probably didn't use enough solder or the wires weren't clean and would not accept the solder. If there are big blobs and drips of hardened solder on the joint then you probably had either too cool of a joint or used too much solder.

After soldering, let the joint cool for about thirty seconds to a minute or so before handling. If you were successful you should have:

* A pair of wires tightly joined together

* The joint between them is very shiny, looking like polished sterling silver.

* No hardened dribbles or drops of solder hanging off the joint

* No little wires sticking out of the joint.

* A union only slightly larger than each of the wires themselves.

If you were NOT successful you might see:

* Large blobs or possibly a long, pointy finger of hardened solder hanging off the joint. Sometimes, after cleaning the iron, these can be removed by simply heating the joint until the solder melts, then removing the iron which will pull away some of the excess solder with it. This may need to be repeated a few times to remedy the situation.

* Wires that are not soldered together and has movement within it. Re-heat the joint and add some more solder.

* Melted insulation. This can be so bad that the wires are revealed with the insulation dripping off the wires. At this point you will probably need to cut the wires and begin again, or unsolder the joint and add a long piece of heat-shrink tubing to cover the exposed wires.

* Little ends of the copper wires sticking out. These can sometimes be cut off with a wire cutter and/or pressed down with a pair of smooth-jaw pliers, possibly needle nose pliers.



Now it is time to cover the joint with the heat shrink tubing. You DID remember to slide on the heat shrink tubing before beginning, didn't you? Once the joint is cool enough to touch, slide the tubing so it is centered over the joint and gently touch the meaty part of the soldering iron's heating element to the center of the tubing.

Continue this around the center of the tubing until it tightly grips the wire joint, then work outwards until the entire piece of tubing has shrunk tightly around the joint.

Attaching An Electrical Connector

Besides connecting two wires together, soldering is the best way top attach some sort of connector to the end of a wire. The connection is strong as well as fairly well sealed against the elements. It works pretty much the same way as above...

Remember when we "tinned" the tip of the soldering pencil? We did this to apply a film of solder to the tip so it wouldn't oxidize and thus be able to more easily transfer heat. Now I am going to do the same with a piece of wire.



Here I am applying a good amount of solder ahead of time to this wire because I am planning on soldering it to a fairly heavy connector. This way, the wire will be "pre-soldered" and easier to attach, and will have less of a chance of melting the insulation.



When soldering a connector to the end of a piece of wire it is very helpful to use some sort of vise to hold the connector. A small pair of locking pliers or a pair of needle nose pliers with a rubber band around the handles to hold the jaws shut works well. Here I have locked a pair of locking pliers into a small vise to work as a "hands-free" holder. This not only allows me to use both hands to work but isolates me from the heat of the soldering process.

Remember that the heavy metal pliers will work as a heat sink, pulling heat away from the soldering joint, so it might take longer to achieve the proper heat level in the joint. That is why I have gripped the connector as far away from the area to be soldered as possible,

Be careful as the pliers may get hot near the tips and you might overheat the wire as well. Be sure to slide the heat shrink tubing over then wire BEFORE beginning to solder! If you leave it off and finish soldering, you will be left with the soldering job in one hand, the heat shrink tubing in the other hand, and a stupid look on your face. We call this, "Heat Shrink Tubing Syndrome."

Additionally, if you apply too much solder, particularly with a small connector, it is very possible to fill the connector with solder and thus make it difficult or impossible for the connector to function properly. There are ways to get the solder out, but they are generally more difficult (or dangerous) than just chucking it and starting over. To keep this from happening:

* Never touch the area of the connector where you don't want solder to flow
* Orient the connector with the part where solder shouldn't flow, upwards (or Higher than the end where solder will flow).
* Apply solder sparingly and slowly
* Use a lower wattage soldering pencil
* Use a smaller tip on the soldering pencil



I sometimes use two pieces of heat shrink, one over the other, shrunk one at a time, in areas where extra protection is needed. This is particularly useful when soldering a connector to the end of a wire. I first shrink a small diameter piece about an inch long over the wire up to where it joins the connector as shown here. This acts as a strain relief as well as insulation.

Notice the small amount of flux on the connector ring left over from the soldering process. If you use resin core solder, this stuff is harmless to the electrical device. It can be brushed off with a small wire brush if you wish.



I then shrink another larger diameter piece about � an inch long over the connector to act as an insulating cover. In the case of something like a female spade connector, the entire connector except for the opening can be covered and protected in this way. If the heat shrink interferes with the connection, simply cut the offending part away with a razor blade being careful not to damage anything else including yourself!

In areas where the joint needs to be protected from corrosion, slather the terminal with petroleum jelly, or the special grease for this application.

Following these directions you will become a "master solderer" in a short period of time. It takes some practice to get a feel of how hot for how long with how much solder it takes to create to make a good solder joint, so get some scrap wire and practice before attempting to solder on anything important.

If there are any questions or comments, please feel free to E-mail me at frcn@cncnet.com.

Note by Duane; If you appreciate articles like this, I suggest that you thank Randy at the email address above.

More BMW info

Home page

This page was last edited: 02/03/2006 - copyright Duane Ausherman
Web hosting provided by hostmeister.com

Soldering and Desoldering Instruction

Soldering is defined as "the joining of metals by a fusion of alloys which have relatively low melting points". In other words, you use a metal that has a low melting point to adhere the surfaces to be soldered together. Soldering is more like gluing with molten metal than anything else. Soldering is also a must have skill for all sorts of electrical and electronics work. It is also a skill that must be taught correctly and developed with practice.

Remember that when soldering, the rosin in the solder releases fumes. These fumes are harmful to your eyes and lungs. Therefore, always work in a well-ventilated area. Hot solder is also dangerous. Be sure not to let is splash around because it will burn you almost instantly. Eye protection is also advised.



HAKKO 850
HAKKO 850

The Tools

Soldering Iron – Even the cheapest of them will do the job. They may not last as long, but they do get hot enough to melt solder and that is the goal. You only need to make sure that the one you buy has a suitable tip on it. The most typical tip is the one that is about the size of a 1/8” stereo mini-plug.

Solder – Get Rosin Core solder. Rosin will help the solder to flow onto the wires. Solder comes in different thickness. Buy what is appropriate for your job.

Desoldering Gun – This tool will make life a lot easier when you need to rework a previous solder job.
Solder Wick – Braided copper with rosin coating used to draw solder off of circuit boards.

SMD Rework station— Basically this is a high temp hair dryer with special nozzle attached. It heats up entire pins of the SMD device so you can remove them.

The Methods

Soldering – There is not art to soldering, it takes patience and practice to get it right. If you are doing it right, it will be easy and very fast. First, make sure that your soldering iron tip is clean. If it is dirtier than just a light gray color, you need to clean it. You can do this with sandpaper or a Scotch Brite pad. Next, turn your iron on and give it plenty of time to heat up. To test the heat, use a piece of solder touched to the tip. If it melts immediately, it is ready.

The most common way to mess up a solder job is to let the soldering iron stay on the parts to be soldered too long. What this does is oxidize the metal, making it too dirty to attract solder. If you are working with a circuit board, too much heat can damage the board, rendering it useless and in need of repair. You should only hold the soldering iron to the parts to be joined for no more than 10-12 seconds. Any longer and you will melt insulation on wire or damage a circuit board.

It has been said that soldering is a two-person job. You need two hands to hold the parts together, one hand to hold the iron, and another to feed the solder. The correct method for applying solder is to hold the joint perfectly still while heating with the soldering iron. After a few seconds, introduce the end of the solder at the point where the iron meets the parts

If the solder does not melt immediately and flow onto the joint, pull the solder away and try again after a couple seconds longer. If you exceed 10 seconds, pull the iron off and try again after it all cools down. You probably didn't have the iron touching enough of the parts to be soldered. Sometimes, the parts to be soldered are so big that they conduct the heat away very quickly and make it difficult to solder. In this case, it is OK to put some solder on each part individually and then put them together later by melting the solder on each one while they are touching.

Joining Two Wires - Strip off about 3/8" of insulation from the two wire ends to be joined. Place a ½" length of heat shrink tubing over one wire and push it back so that the heat from soldering won't shrink it prematurely. Fold each bare wire end back on itself so that the tip of the wire now comes back to the end of the insulation. Link both wires together using the bends like hooks. Now, twist the ends of the wires around themselves tightly. This type of connection is called a Western Union and it is the strongest method of joining two wires together. Now, heat the connection with the iron and allow solder to flow over the entire joint. Wait a few seconds for it to cool off and then slide the heat shrink tubing down over the connection and heat it with a match or heat gun.

Soldering a Wire to a Circuit Board – This is delicate work that you will do while soldering. Too much heat and your board will be damaged. If you are attaching a wire to an existing hole on the board, make sure that the hole is clean and free of any excess solder (see de-soldering for more detail). The best advice when soldering to a circuit board is to angle your soldering iron tip so that it makes good contact with the pad on the circuit board and the wire or part to be soldered at the same time. Heat the parts up and touch the solder at the point where the tip meets the part and the pad. If the solder does not flow immediately, pull everything off and wait for it to cool down and try again later.

Step 1



Apply heat to both pin and pad on the circuit board. Make sure tip of the soldering iron is touching both pin and pad.

Step 2



When the both pin and pad are heated enough, apply solder to the pin and pad. Solder should starts to flow.

Step 3



Apply enough but not too much solder. While applying the solder, do not move the tip of iron.

Step 4



Remove solder away.

Step 5



Remove tip of soldering iron also.

Step 6



Done! Check the joint to make sure the connection.

Good soldering and Bad soldering Joints

Here are some example of Good soldering and Bad soldering joint.
For Japanese, we often say, “Good soldering joint should look like Mt. Fuji.”



Too much soldering



Too little soldering



Good soldering

Cold Solder Joints
A cold joint is a joint in which the solder does not make good contact with the component lead or printed circuit board pad. Cold joints occur when the component lead or solder pad moves before the solder is completely cooled. Cold joints make a really bad electrical connection and can prevent your circuit from working.
Cold joints can be recognized by a characteristic grainy, dull gray color, and can be easily fixed. This is done by first removing the old solder with a desoldering tool or simply by heating it up and flicking it off with the iron. Once the old solder is off, you can re-solder the joint, making sure to keep it still as it cools.



Cold soldering joints



Tips and Tricks

Soldering is something that needs to be practiced. These tips should help you become successful so you can stop practicing and get down to some serious building.

1. Use heat sinks. Heat sinks are a must for the leads of sensitive components such as ICs and transistors. If you don't have a clip on heat sink, then a pair of pliers is a good substitute.

2. Keep the iron tip clean. A clean iron tip means better heat conduction and a better joint. Use a wet sponge to clean the tip between joints.

3. Double-check joints. It is a good idea to check all solder joints with an ohmmeter after they are cooled. If the joint measures any more than a few tenths of an ohm, then it may be a good idea to re-solder it.

4. Use the proper iron or temperature. Remember that bigger joints will take longer to heat up with an 30W iron than with a 150W iron. While 30W is good for printed circuit boards and the like, higher wattages are great when soldering to a heavy metal chassis.

Desoldering

Desoldering is extremely difficult compare to soldering. In the process of RomBoard installation, the parts and circuit board must be in the good shape to re-use them. The tool we use is Desoldering Gun. This device has vacuum pump built in with heater tip. Process of desoldering it self is very simple, but there are some tricks to do clean and safe desoldering job.

Step 1



Put the desoldering gun's tip over to the soldering joint. Make sure nozzle is 90° angle from circuit board.

Step 2



Apply the enough heat to melt entire solder. Multi-layer board or ground pin may take while to transfer heat.

Step 3



While applying vacuum, move the tip around the pin to get all the solder of around the pin out. At this time, you can also feel pin moves freely, so you know pin is free from circuit board.

Step 4



When you can hear air flow sound from hole, you should be done. Stop applying vacuum and remove the gun from the pin. Inspect hole and pin.

When you done with desoldering, the parts that you are trying to remove should move freely. If it doesn't, find which pin is still has solder left, and re-apply fresh solder to it and try desoldering process again. The multi-layer circuit board require more heat to get solder to melt. Make sure pin start to move freely by moving the tip of soldering gun before you apply vacuum to it.

SMD device soldering and removal

In the process of RomBoard installation, chance of handling SMD devices is becoming higher and higher due to ECU configuration change.
Soldering of SMD devices are not much different from regular through hole soldering.
Important thing is positioning of the device is very critical.
Start with applying little solder to two of the each corner of the pads on the circuit board.
Then, place the SMD device and re-heat a one of the solder you just applied to connect a SMD device pin to the pad. Check the position of the device, if position is right re-heat the other end of solder to secure the device completely. If you didn't get position right, re-heat the pin that you just soldered and while heating a pin, move the device to the right position.
Once you positioned the device in the right position, apply Rosin Flux to both pins and pads. This will help your soldering job by keeping solder separate from each pin.
Here is how the joint on SMD device pin should look like.



QFP and SOP chip



PLCC chip



RomBoard adapter socket

Removing SMD device will be the probably the most difficult process. SMD rework station is used to do this. Make sure all the pins are completely heated otherwise you will be removing a pad from the circuit board along with device. Also, you should note, when you are applying heat to the device, some parts around the device is also heated and moves around when you touch. It is good idea to take a note of location of the devices near the target device.



Step 1
Apply pre-heat from back side of the target device. Keep applying heat until you can't touch the chip. By this time, circuit board should have enough heat.



Step 2
Apply heat from top of the target device. Nozzle should cover entire chip. You can check if chip is free from solder by sliding the nozzle left and right. Make sure you don't move other parts. If the chip moves freely, it is ready to be removed.



Step 3
Remove the chip straight up to avoid making solder bridge between pins. Chip is extremely hot! Unless you have skin of steel, avoid imitating the picture.



Step 4
After remove the chip, cool down both circuit board and chip.



Step 5
Clean the pads on the circuit board with desoldering gun.
Do not apply too much heat to the pad. Pad might peel off from circuit board. Clean the chip by desoldering gun also.
Check for any bridge between pins. If the chip has too much protective coating on it, use solvent to clean it up.



Step 6
If the pads on the circuit board is too small to use desolding gun, try cleaning by solder wick with rosin flux. This may take time but it is much better than peeling pads off.
Once again, do not apply too much heat.



Step 7
Solder the RomBoard adapter where the chip was.
Refer SMD device soldering section for how to solder adapter.

The Final Word

Soldering, desoldering, and working with SMD device will take some effort to learn. You should be relaxed and concentrated when you work.
Keeping every thing clean (tip of iron, gun, work surface, etc) will help you also.
Once you get comfortable to work with soldering you may find your own tips and tricks.
Experience is all bout soldering.

EOF

How To Solder - Soldering Tutorial

Soldering is defined as "the joining of metals by a fusion of alloys which have relatively low melting points". In other words, you use a metal that has a low melting point to adhere the surfaces to be soldered together. Consider that soldering is more like gluing with molten metal, unlike welding where the base metals are actually melted and combined. Soldering is also a must have skill for all sorts of electrical and electronics work. It is also a skill that must be taught correctly and developed with practice. This tutorial will cover the most common types of soldering required for electronics work. This includes soldering components to printed circuit boards and soldering a spliced wire joint. This presentation came from http://www.aaroncake.net/electronics/solder.htm

Soldering Equipment

The Soldering Iron/Gun

The first thing you will need is a soldering iron, which is the heat source used to melt solder. Irons of the 15W to 30W range are good for most electronics/printed circuit board work. Anything higher in wattage and you risk damaging either the component or the board. If you intend to solder heavy components and thick wire, then you will want to invest in an iron of higher wattage (40W and above) or one of the large soldering guns. The main difference between an iron and a gun is that an iron is pencil shaped and designed with a pinpoint heat source for precise work, while a gun is in a familiar gun shape with a large high wattage tip heated by flowing electrical current directly through it.

A 30W Watt Soldering Iron

A 300W Soldering Gun

For **hobbyist electronics** use, a soldering iron is generally the tool of choice as its small tip and low heat capacity is suited for printed circuit board work (such as assembling kits). A soldering gun is generally used in heavy duty soldering such as joining heavy gauge wires, soldering brackets to a chassis or stained glass work.

You should choose a soldering iron with a 3-pronged grounding plug. The ground will help prevent stray voltage from collecting at the soldering tip and potentially damaging sensitive (such as CMOS) components. By their nature, soldering guns are quite "dirty" in this respect as the heat is generated by shorting a current (often AC) through the tip made of formed wire. Guns will have much less use in hobbyist electronics so if you have only one tool choice, an iron is what you want. For a beginner, a 15W to 30W range is the best but be aware that at the 15W end of that range, you may not have enough power to join wires or larger components. As your skill increases, a 40W iron is an excellent choice as it has the capacity for slightly larger jobs and makes joints very quickly. Be aware that it is often best to use a more powerful iron so that you don't need to spend a lot of time heating the joint, which can damage components.

A variation of the basic gun or iron is the soldering station, where the soldering instrument is attached to a variable power supply. A soldering station can precisely control the temperature of the soldering tip unlike a standard gun or iron where the tip temperature will increase when idle and decrease when applying heat to a joint. However, the price of a soldering station is often ten to one hundred times the cost of a basic iron and thus really isn't an option for the hobby market. But if you plan to do very precise work, such as surface mount, or spend 8 hours a day behind a soldering iron, then you should consider a soldering station.

The rest of this document will assume that you are using a soldering iron as that is what the majority of electronics work requires. The techniques for using a soldering gun are basically the same with the only difference being that heat is only generated when the trigger is pressed.

Solder

The choice of solder is also important. There several kinds of solder available but only a few are suitable for electronics work. Most importantly, you will only use *rosin core solder*. *Acid* core solder is common in hardware stores and home improvement stores, but meant for soldering copper plumbing pipes and not **electronic circuits**. If acid core solder is used on electronics, the acid will destroy the traces on the printed circuit board and erode the component leads. It can also form a conductive layer leading to shorts.

For most printed circuit board work, a solder with a diameter of 0.75MM to 1.0MM is desirable. Thicker solder may be used and will allow you to solder larger joints more quickly, but will make soldering small joints difficult and increase the likelihood of creating solder bridges between closely spaced PCB pads. An alloy of 60/40 (60% tin, 40% lead) is used for most electronics work. These days, several lead-free solders are available as well. **Kester "44" Rosin Core** solder has been a staple of electronics for many years and continues to be available. It is available in several diameters and has a non-corrosive flux.

Large joints, such as soldering a bracket to a chassis using a high wattage soldering gun, will require a separate application of brush on flux and a thick diameter solder of several millimeters. Remember that when soldering, the flux in the solder will release fumes as it is heated. These fumes are harmful to your eyes and lungs. Therefore, always work in a well-ventilated area and avoid breathing the smoke created. Hot solder is also dangerous. It is surprisingly easy to splash hot solder onto yourself, which is a thoroughly unpleasant experience. Eye protection is also advised.

Preparing To Solder

Tinning the Soldering Tip

Before use, a new soldering tip, or one that is very dirty, must be tinned. "Tinning" is the process of coating a soldering tip with a thin coat of solder. This aids in heat transfer between the tip and the component you are soldering, and also gives the solder a base from which to flow from.

Step 1: Warm Up the Iron

Warm up the soldering iron or gun thoroughly. Make sure that it has fully come to temperature because you are about to melt a lot of solder on it. This is especially important if the iron is new because it may have been packed with some kind of coating to prevent corrosion.

Step 2: Prepare A Little Space

While the soldering iron is warming up, prepare a little space to work. Moisten a little sponge and place it in the base of your soldering iron stand or in a dish close by. Lay down a piece of cardboard in case you drip solder (you probably will) and make sure you have room to work comfortably.

Step 3: Thoroughly Coat the Tip in Solder

Thoroughly coat the soldering tip in solder. It is very important to cover the entire tip. You will use a considerable amount of solder during this process and it will drip, so be ready. If you leave any part of the tip uncovered it will tend to collect flux residue and will not conduct heat very well, so run the solder up and down the tip and completely around it to totally cover it in molten solder.

.


Step 4: Clean the Soldering Tip

After you are certain that the tip is totally coated in solder, wipe the tip off on the wet sponge to remove all the flux residue. Do this immediately so there is no time for the flux to dry out and solidify.

Step 5: You're Done!

You have just tinned your soldering tip. This must be done anytime you replace the tip or clean it so that the iron maintains good heat transfer.

Soldering a Printed Circuit Board (PCB)

Soldering a PCB is probably the most common soldering task an electronics hobbyist will perform. The basic techniques are fairly easy to grasp but it is a skill that will take a little practice to master. The best way to practice is to buy a simple electronics kit or assemble a simple circuit (such as an **LED chaser**) on a perf-board. Don't buy that expensive kit or dive into a huge project after only soldering a few joints.

Soldering components onto a PCB involves preparing the surface, placing the components, and then soldering the joint.

Step 1: Surface Preparation:

A clean surface is very important if you want a strong, low resistance solder joint. All surfaces to be soldered should be cleaned well. **3M Scotch Brite pads** purchased from the home improvement, industrial supply store or automotive body shop are a good choice as they will quickly remove surface tarnish but will not abrade the PCB material. Note that you will want *industrial* pads and not the kitchen cleaning pads impregnated with cleaner/soap. If you have particularly tough deposits on your board, then a fine grade of steel wool is acceptable but be very cautious on boards with tight tolerances as the fine steel shavings can lodge between pads and in holes.

Once you have cleaned the board down to shiny copper you can use a solvent such as acetone to clean any bits of the cleaning pad that may remain and to remove chemical contamination from the surface of the board. Methyl hydrate is another good solvent and a bit less stinky then acetone. Be aware that both these solvents can remove ink, so if your board is silk screened, test the chemicals first before hosing down the entire board.

A few blasts with compressed air will dry out the board and remove any junk that may have built up in the holes.

Step 2: Component Placement

After the component and board have been cleaned, you are ready to place the components onto the board. Unless your circuit is simple and only contains a few components, you will probably not be placing all the components onto the board and soldering them at once. Most likely you will be soldering a few components at a time before turning the board over and placing more. In general it is best to start with the smallest and flattest components (resistors, ICs, signal diodes, etc.) and then work up to the larger components (capacitors, power transistors, transformers) after the small parts are done. This keeps the board relatively flat, making it more stable during soldering. It is also best to save sensitive components (MOSFETs, non-socketed ICs) until the end to lessen the chance of damaging them during assembly of the rest of the circuit.

Bend the leads as necessary and insert the component through the proper holes on the board. To hold the part in place while you are soldering, you may want to bend the leads on the bottom of the board at a 45 degree angle. This works well for parts with long leads such as resistors. Components with short leads such as IC sockets can be held in place with a little masking tape or you can bend the leads down to clamp onto the PC board pads.

In the image below, a resistor is ready to solder and is held in place by slightly bent leads.



Step 3: Apply Heat

Apply a very small amount of solder to the tip of the iron. This helps conduct the heat to the component and board, but it is **not** the solder that will make up the joint. To heat the joint you will lay the tip of the iron so that it rests against both the *component lead* and the *board*. It is critical that you heat the lead and the board, otherwise the solder will simply pool and refuse to stick to the unheated item. The small amount of solder you applied to the tip before heating the joint will help make contact between the board and the lead. It normally takes a second or two to get the joint hot enough to solder, but larger components and thicker pads/traces will absorb more heat and can increase this time.

If you see the area under the pad starting to bubble, **stop** heating and remove the soldering iron because you are overheating the pad and it is in danger of lifting. Let it cool, then carefully heat it again for much less time.



Step 4: Apply Solder to the Joint

Once the component lead and solder pad has heated up, you are ready to apply solder. Touch the tip of the strand of solder to the component lead and solder pad, but **not** the tip of the iron. If everything is hot enough, the solder should flow freely around the lead and pad. You will see the flux melt liquefy as well, bubble around the joint (this is part of its cleaning action), flow out and release smoke. Continue to add solder to the joint until the pad is completely coated and the solder forms a small mound with slightly concave sides. If it starts to ball up, you have used too much solder or the pad on the board is not hot enough.

Once the surface of the pad is completely coated, you can stop adding solder and remove the soldering iron (in that order). Don't move the joint for a few seconds as the solder needs time to cool and solidify. If you do move the joint, you will get what's called a "cold joint". This is recognized by it's characteristic dull and grainy appearance. Many cold joints can be fixed by reheating and applying a small amount of solder, then being allowed to cool without being disturbed.

Step 5: Inspect the Joint and Cleanup

Once the joint is made you should inspect it. Check for cold joints (described a little above and at length below), shorts with adjacent pads or poor flow. If the joint checks out, move on to the next. To trim the lead, use a small set of side cutters and cut at the top of the solder joint.



After you have made all the solder joints, it is good practice to clean all the excess flux residue from the board. Some fluxes are hydroscopic (they absorb water) and can slowly absorb enough water to become slightly conductive. This can be a significant issue in a hostile environment such as an automotive application. Most fluxes will clean up easily using methyl hydrate and a rag but some will require a stronger solvent. Use the appropriate solvent to remove the flux, then blow the board dry with compressed air.

Cold Solder Joints

A "cold solder joint" can occur when not enough heat is applied to the component, board, or both. Another common cause is a component moving before the solder has completely cooled and solidified. A cold joint is brittle and prone to physical failure. It is also generally a very high resistance connection which can affect the operation of the circuit or cause it to fail completely.

Cold joints can often be recognized by a characteristic grainy, dull gray color, but this is not always the case. A cold joint can often appear as a ball of solder sitting on the pad and surrounding the component lead. Additionally you may notice cracks in the solder and the joint may even move. Below is the shocking image of every example of a bad solder joint you will ever see. It appears that this **FM transmitter kit** was assembled using the technique of "apply solder to iron then drip onto joint". If your joints are looking like this, then **stop** and practice after rereading this page. Note that not a single of of these joints is acceptable, but amazingly, the circuit worked.



Most cold solder joints can be easily fixed. Generally all that is required is to reheat the joint and apply a little more solder. If there is already too much solder on the joint, then the joint will have to be **desoldered** and then soldered again. This is done by first removing the old solder with a desoldering tool or simply by heating it up and flicking it off with the iron. Once the old solder is off, you can resolder the joint, making sure to heat it thoroughly and keep it still as it cools.

advertisement

HOW TO SOLDER - THE QUICK, THOROUGH GUIDE

Technology (/technology/) > Soldering | by IoTalabs (/member/IoTalabs/) Follow

4,064 38 4

Posted Jun. 9, 2016 | (cc) BY-NC-SA



(https://cdn.instructables.com/FKM/O3O6/IP739UZQ/FKMO3O6IP739UZQ.LARGE.jpg)

We are IoTalabs and we are a group of Internet of Things enthusiasts that love hacking together different devices. Over the past few months we have immersed ourself in the wonderful world of hardware! In our journey, we learned the best soldering practices around.

We've been working on many projects (check out our current project http://doteverything.co/) and we wanted to share our experience on safely and correctly soldering connections!

Add Tip Ask Question

Step 1: What Is Soldering?

Soldering accomplishes a strong bond between two pieces of metal by joining them together. In this procedure, a material called solder, an alloy mixture of tin and lead, flows over two pre-heated pieces of metal and holds them together. The process is similar to welding but differs because when you weld you are fusing and melting two pieces together to make one. When you solder you are essentially ‘gluing’ two parts together with molten metal. Most metals with the exception of aluminum, white metal and porous cast iron can be soldered. Below, you will find instructions and illustrations that show you how to use a soldering iron.

Add Tip Ask Question

Step 2: Materials for Soldering

SOLDERING PASTE FLUX
METAL CLEANER FOR SOLDERING
Ask for ALPHA METALS top quality
RELIABLE
SOLDERING FLUX
ZINC CHLORIDE
SOLDER
ROSIN CORE
16 OZ.
(1 LB.)
NET WT.
MADE IN U.S.A.
UNGAR

(https://cdn.instructables.com/FZC/59XY/IPZ4QGXI/FZC59XYIPZ4QGXI.LARGE.jpg)

Soldering Iron

Modeler’s Vise or Frame (optional)

Solder

Damp Sponge

Flux to remove oxides

Add Tip Ask Question

Step 3: Prepare Your Workspace

Make sure your table or bench top is clear and free of obstructions. You will want as much freedom as possible to move your hand around and make adjustments.

Add Tip Ask Question

Step 4: Turn on the Soldering Iron

The soldering iron needs to be warmed up properly before it can be used to ensure clean application of the solder. Some soldering irons heat up in seconds while others take minutes. Turn it on and leave it in the stand for 2-3 minutes to be safe.

Add Tip Ask Question

Step 5: (Optional) Secure the Items You Are Soldering

Because we only have two hands, it would be nice to stabilize the item we want to solder. This is where a vice or clamp that can hold your item sturdily would come in handy. This is not required, but can greatly increase the ease and quality of your solder joints.

Add Tip Ask Question

Step 6: Cleaning the Soldering Iron

Weller
WESD51

(https://cdn.instructables.com/FVM/SZ4M/IP74OGX5/FVMSZ4MIP74OGX5.LARGE.jpg)

Because soldering irons get so hot, they oxidize and become dirty quickly. They key to reliable connections is clean components so make sure that your soldering tip and parts you are joining are clean. To accomplish this, pass the tip of your soldering iron on a wet sponge until it shines.

Add Tip Ask Question

Step 7: Apply Flux



(https://cdn.instructables.com/FTD/PDPV/IPZ4OGXZ/FTDPDPVIPZ4OGXZ.LARGE.jpg)

In soldering it often becomes necessary to use materials called fluxes to help remove oxides and keep them absent while you solder. Flux needs to melt at a temperature lower than solder so that it can do its job prior to the soldering action. There are different methods to apply flux. The method you choose will be dependent on the items you are soldering.

Add Tip Ask Question

Step 8: Tin the Soldering Iron



(https://cdn.instructables.com/FEK/F3WN/IPZ4OGXR/FEKF3WNIPZ4OGXR.LARGE.jpg)

If you want to know everything there is to know about how to use a soldering iron, you’ll need to know how to tin. Tinning is the process of coating a soldering tip with a thin coat of solder. Melt a thin layer of solder on your iron’s tip. This aids in heat transfer between the tip and the component you are soldering, and also gives the solder a base from which to flow from. This process may need to be repeated as you solder. You will only touch the tip of the soldering iron to the solder when you tin. Do not touch the tip of the iron to the solder while you are actually soldering.

Add Tip Ask Question

Step 9: Start Soldering

Hold the soldering iron like you would a pen in the hand you write with and the solder in the other. Then place the tip of the soldering iron. The tip needs to touch both the wire lead and the surface so they achieve the same temperature.

Add Tip Ask Question

Step 10: Feeding the Solder


Tip of soldering iron
Solder wire
Circuit board
Copper pad on board
Lead from component

(https://cdn.instructables.com/FIW/HS90/IRZ4OGXY/FIWHS90IRZ4OGXY.LARGE.jpg)

Touch the solder to the side of the connection opposite the soldering iron after heating the area for 2-3 seconds. Then, let the solder flow only until the connection is covered.

Add Tip Ask Question

Step 11: Removing the Solder

Remove the solder first, then the iron otherwise your solder will get stuck to your connection point without the appropriate heat. Make sure the joint remains stationary while it cools.

Add Tip Ask Question

Step 12: Check to See If the Connection Is Solid

A smooth, shiny and volcano shaped joint is what you are looking for. If this isn’t what you see, you’ll need to reheat and feed in more solder.

Add Tip Ask Question

Step 13: Warnings

- DO NOT lay a soldering iron down on any surface. A soldering iron should either be placed on a stand or sealed with a heat resistant cap after every use.
- Soldering should be completed in a well ventilated area.
- Lead is present in most solders. Be sure to wash your hands after your project, or better yet wear gloves.
- Try not to inhale any of the solder smoke that comes off the solder. This is lead and can be dangerous.
- The tip of a soldering iron is very hot. Contact with the tip of a soldering iron would result in a nasty burn.
- Your soldering iron will perform better if kept clean. A damp sponge can be used to clean residue caused by flux material. A very small skim of flux should be applied to the iron after the cleaning.

THE BASICS OF HOW TO SOLDER

Soldering Tutorial for Beginners: Five Easy Steps

Table of Contents:

- Before you begin
- Step 1: Heat your iron to the appropriate temperature
- Step 2: Make your connection mechanically stable
- Step 3: Clean the tip of your iron
- Step 4: Apply heat and solder
- Step 5: Inspect the joint
- Common mistakes

Before you begin

You will need the following equipment:

A temperature-controlled soldering iron of 25W or more
A tip cleaner such as a brass sponge or a wet sponge

Solder (leaded is easier to work with than lead-free)
(Optional) Helping hands
Safety glasses

Note: molten solder is extremely hot! Irons heat up to around twice the boiling point of water, so be extremely careful. Wear safety glasses when soldering.

Step 1: Heat your iron to the appropriate temperature

Weller
WES51
°Fx10

For through-hole components in a circuit board, you will want 600-700 degrees fahrenheit.

If you're soldering a larger connections, with more copper that's dissipating heat, then you may want a slightly higher temperature. With a temperature-adjustable iron you can see what works and adjust accordingly.

Step 2: Make your connection mechanically stable





While your iron is heating up, you can work on making your components stay in place without your help. This is where your helping hands may come in handy. Use them to help you arrange your components to be stable without you needing to hold anything. If you're soldering a through-hole component in a circuit board, you can bend the leads of the component into a V-shape so that it stays in place flush against the board. For components without long leads, you can use a piece of tape to hold them in place.

Step 3: Clean the tip of your iron



You can check whether your iron is close to its final temperature by touching your solder to the end of the iron and seeing if it melts. When you do this, you'll see some smoke come out. This is not the metal vaporizing, but rather the flux inside of it is burning. Flux is a mild acid that eats away at the oxidation layer that forms on the surface of hot metals. Without flux in the solder to clean your surfaces, you would have a very hard time getting the solder to wet.

Clean your iron using a brass sponge or a wet sponge to remove any oxidation or excess solder from the tip. Remember to always keep your tip clean while you're soldering. A dirty tip is covered in metal oxides that transfer heat badly and can result in poorly soldered joints.

Step 4: Apply heat and solder







Touch the flat part of your iron's tip to one side of the joint, while feeding solder from the other side of the joint. The idea is to heat up the entire joint to the melting temperature of solder, so when you touch the solder to the surfaces it melts right on. The only way you can ensure a good electrical connection is by letting the solder flow over the components you're joining. Don't apply the solder directly to the tip of the iron. For through-hole components, hold the iron against both the lead and the pad.

Small joints can heat up within a few seconds, but larger joints can take a minute or two. Keep the joint steady for a few seconds after removing the iron, as the solder needs time to cool. Remember that the joint is hot now! don't touch it with your fingers right away.

Step 5: Inspect the joint







The solder should have wetted to both surfaces. On pads of a printed circuit board, the solder should be covering the entire pad, and it should make a volcano shape between the pad and the lead, indicating good adhesion. Once the joint is perfect, clip the leads of through-hole components.

Common mistakes, or what NOT to do

Now that we’ve gone over what to do, let me tell you what NOT to do.



Don’t put a blob of solder on the iron and then try to transfer it to your joint. This burns away all of the flux in the solder, which prevents the flux from cleaning the metal surfaces. Furthermore, it’s easy to transfer the solder blob away from the iron without actually making it wet to the joint. I guarantee you that this will result in an awful electrical connection, so don’t do it.

Basic Tutorials

Soldering Basics
Desoldering Tutorial
Tesla Coil FAQ

tinyTesla Assembly Tutorials

tinyTesla Manual
Heat Sink Hardware Installation
Main Board's Logic Component Installation
Low Voltage Driver Board Test
Main Board's Power Component Installation
IGBT Installation

oneTeslaTS Assembly Tutorials

oneTeslaTS Manual
Endcap and Secondary Assembly Tutorial

Advanced Tutorials

How a Tesla Coil Works
(DR)SSTC Nonidealities and Losses
Thermal Analysis
DRSSTC Driver Guide
DRSSTC Bridge Design
Gate Drive Design
Resonator Design
Tesla Coil Tuning

SIGN UP FOR UPDATES

Enter your email for exclusive updates from oneTesla about new products, promotions, and other announcements

SUBSCRIBE

Limit of Liability

At oneTesla, we have a passion for making learning about hands-on electronics fun. Use our kits for educational purposes only. The operational reliability of the kits is dependent upon how well the kit is assembled, something that only the kit builder has control over. Build oneTesla kits at your own risk.

Site Links

- Contact Us
- Order FAQ
- oneTesla In the Press

One Tesla: DIY Sin…

4,519 likes


Like Page
Shop Now

About Us | Privacy Policy | Terms and Conditions | Kickstarter Terms and Conditions | Site Map | Search Terms | Advanced Search |

Makerspaces.com

How To Solder: A Beginner’s Guide



Learning how to solder w/ proper soldering techniques is a fundamental skill every maker should master. In this tutorial, we outline the basics of soldering irons, soldering stations, types of solder, desoldering and safety tips. Whether you’re building a robot or working with Arduino, knowing how to solder will come in handy.

FREE EBOOK (PDF) – Learn To Solder Guide (17 pages)

What Is Soldering?

If you were to take apart any electronic device that contains a circuit board, you’ll see the components are attached using soldering techniques. Soldering is the process of joining two or more electronic parts together by melting solder around the connection. Solder is a using a desoldering tool as described below.


Solder
Soldering Iron
Copper Pad
Circuit Board
LED
Makerspaces.com/how-to-solder

Soldering Tools

The good thing about learning how to solder is the fact that you don't need a lot to get started. Below we'll outline the basic tools and materials you will need for most of your soldering projects.

Soldering Iron

A soldering iron is a hand tool that plugs into a standard 120v AC outlet and heats up in order to melt solder around electrical connections. This is one of the most important tools used in soldering and it can come in a few variations such as pen or gun form. For beginners, it's recommended that you use the pen style soldering iron in type of soldering iron because it can heat up to 896′ F which is extremely hot.

Soldering Station

A soldering station is a more advanced version of the basic standalone soldering pen. If you are going to be doing a lot of soldering, these are great to have as they offer more flexibility and control. The main benefit of a soldering station is the ability to precisely adjust the temperature of the soldering iron which is great for a range of projects. These stations can also create a safer workspace as some include advanced temperature sensors, alert settings and even password protection for safety.

Soldering Iron Tips

At the end of most soldering irons is an interchangeable part known as a soldering tip. There are many variations of this tip and they come in a wide variety of shapes and sizes. Each tip is used for a specific purpose and offers a distinct advantage over another. The most common tips you will use in electronics projects are the conical tip and the chisel tip.

Conical Tip – Used in precision electronics soldering because of the fine tip. Because of its pointed end, it's able to deliver heat to smaller areas without affecting its surroundings.

Chisel Tip – This tip is well-suited to soldering wires or other larger components because of its broad flat tip.



Image Credit – Sparkfun.com

Brass or Conventional Sponge

it did when it was new. You could use a conventional wet sponge but this tends to shorten the lifespan of the tip due to expansion and contraction. Also, a wet sponge will drop the temperature of the tip temporarily when wiped. A better alternative is to use a brass sponge as shown on the left.

Soldering Iron Stand

A soldering iron stand is very basic but very useful and handy to have. This stand helps prevent the hot iron tip from coming in contact with flammable materials or causing accidental injury to your hand. Most soldering stations come with this built in and also include a sponge or brass sponge for cleaning the tip.

Solder

Solder is a metal alloy material that is melted to create a permanent bond between electrical parts. It comes in both lead and lead-free variations with diameters of .032″ and .062″ being the most common. Inside the solder core is a material known as flux which helps improve electrical contact and its mechanical strength.

For electronics soldering, the most commonly used type is lead-free rosin core solder. This type of solder is usually made up of a Tin/Copper alloy. You can also use leaded 60/40 (60% tin, 40% lead) rosin core solder but it’s becoming less popular due to health concerns. If you do use lead solder, make sure you have proper ventilation and that you wash your hands after use.

Net Wt.: 8 oz. (226.7g)
64-009
60/40 ROSIN-CORE SOLDER
LF-99 Lead-Free Solder
99.3% tin 0.7% copper, 4.84g/
5 ft., 0.031" Dia. Rosin Core
WARNING: This product contains or produces a chemical known to the state of

When buying solder, make sure NOT to use acid core solder as this will damage your circuits and components. Acid core solder is sold at home improvement stores and is mainly used for plumbing and metal working.

As mentioned earlier, solder does come in a few different diameters. The thicker diameter solder (.062″) is good for soldering larger joints more quickly but it can make soldering smaller joints difficult. For this reason, it's always a good idea to have both sizes on hand for your different projects.

Helping Hand (Third Hand)

A helping hand is a device that has 2 or more alligator clips and sometimes a magnifying glass/light attached. This clips will assist you by holding the items you are trying to solder while you use the soldering iron and solder. A very helpful tool to have in your makerspace.



Soldering Safety

Now that you know what tools and materials are required, it’s time to briefly discuss ways of staying safe while soldering.

Soldering irons can reach temperatures of 800′ F so it’s very important to know where your iron is at all times. We always recommend you use a soldering iron stand to help prevent accidental burns or damage.

Make sure you are soldering in a well ventilated area. When solder is heated, there are fumes released that are harmful to your eyes and lungs. It's recommended to use a fume extractor which is a fan with a charcoal filter that absorbs the harmful solder smoke.

It's always a good idea to wear protective eye wear in case of accidental splashes of hot solder. Lastly, make sure to wash your hands when done soldering especially if using lead solder.

Tinning The Tip

Before you can start soldering, you need to prep your soldering iron by tinning the tip with solder. This process will help improve the heat transfer from the iron to the item you're soldering. Tinning will also help to protect the tip and reduce wear.

Step 1: Begin by making sure the tip is attached to the iron and screwed tightly in place.

Step 3: Wipe the tip of the soldering iron on a damp wet sponge to clean it. Wait a few seconds to let the tip heat up again before proceeding to step 4.

Step 4: Hold the soldering iron in one hand and solder in the other. Touch the solder to the tip of the iron and make sure the solder flows evenly around the tip.

You should tin the tip of your iron before and after each soldering session to extend its life. Eventually, every tip will wear out and will need replacing when it becomes rough or pitted.

How To Solder

To better explain how to solder, we’re going to demonstrate it with a real world application. In this example, we’re going to solder an LED to a circuit board.

Step 1: **Mount The Component** – Begin by inserting the leads of the LED into the holes of the circuit board. Flip the board over and bend the leads outward at a 45′ angle. This will help the component make a better connection with the copper pad and prevent it from falling out while soldering.



resistor lead at the same time. You need to hold the soldering iron in place for 3-4 seconds in order to heat the pad and the lead.



Step 3: **Apply Solder To Joint** – Continue holding the soldering iron on the copper pad and the lead and touch your solder to the joint. **IMPORTANT** – Don't touch the solder directly to the tip of the iron. You want the joint to be hot enough to melt the solder when it's touched. If the joint is too cold, it will form a bad connection.

Step 4: **Snip The Leads** – Remove the soldering iron and let the solder cool down naturally. Don't blow on the solder as this will cause a bad joint. Once cool, you can snip the extra wire from leads.

A proper solder joint is smooth, shiny and looks like a volcano or cone shape. You want just enough solder to cover the entire joint but not too much so it becomes a ball or spills to a nearby lead or joint.



How To Solder Wires

Begin by removing the insulation from the ends of both wires you are soldering together. If the wire is stranded, twist the strands together with your fingers.

Make sure your soldering iron is fully heated and touch the tip to the end of one of the wires. Hold it on the wire for 3-4 seconds.



Keep the iron in place and touch the solder to the wire until it’s fully coated. Repeat this process on the other wire.

Hold the two tinned wires on top of each other and touch the soldering iron to both wires. This process should melt the solder and coat both wires evenly.



Remove the soldering iron and wait a few seconds to let the soldered connection cool and harden. Use heat shrink to cover the connection.

Desoldering

The good thing about using solder is the fact that it can be removed easily in a technique known as desoldering.

To desolder a joint, you will need solder wick which is also known as desoldering braid.

Desoldering Braid
Custom Manufactured in China for General Wireless Operations Inc. dba RadioShack, Fort Worth, TX 76102
RadioShack
RoHS
6402090
0 40293 16297 9
06F16
SPX13

Step 1 – Place a piece of the desoldering braid on top of the joint/solder you want removed.

Step 2 – Heat your soldering iron and touch the tip to the top of the braid. This will heat the solder below which will then be absorbed into the desoldering braid. You can now remove the braid to see the solder has been extracted and removed. Be careful touching the braid when you are heating it because it will get hot.





solder with a press of a button.

To use, press the plunger down at the end of the solder sucker. Heat the joint with your soldering iron and place the tip of the solder sucker over the hot solder. Press the release button to suck up the liquid solder. In order to empty the solder sucker, press down on the plunger.

Soldering & Electronics

- Digikey
- Sparkfun
- Adafruit
- Jameco
- Velleman
- Mouser

FREE – Learn To Solder Guide (17 pages)

Makerspaces.com

Makerspaces.com was built to help schools and libraries start and run acquire the skills needed for the 21st century.

adafruit learning system

Adafruit Guide To Excellent Soldering

Created by Bill Earl

Last updated on 2014-06-28 08:30:54 PM EDT

Guide Contents

Guide Contents 2
Tools 4
Building a Soldering Toolkit 4
Choosing a Soldering Iron 4
- Basic Irons 5
- Better Irons 5
- Best Irons 5

Irons to avoid 6
- For emergencies only: 6
- Not for circuit board use: 6

Essential Tools and Supplies: 6
- Stand 7
- Solder 7
- Diagonal Cutters 7

Other Handy Tools and Supplies 7
- Vise 8
- Third Hand 8
- Solder Sucker 9
- Solder Wick 9

Preparation 10
- Heat the Iron 10
- Clean the Iron 10
- Tin the Tip 11
- Make sure that the joint is clean 11
- Immobilize the Joint 11
- Steady the Board 12

Making a good solder joint 13
- Heat the joint 13
- Apply the solder 14
- Let It Flow 14

Let It Cool 14
Trim the Lead 14
Congratulations! 15
Problems? 16
Surface Mount Components 17
Immobilize the Joint 17
Heat the Joint 17
Apply the Solder 18
Let it Flow 18
Let it Cool 18
Problems? 18
Common Soldering Problems 20
The Ideal Solder Joint 20
Disturbed Joint 21
Cold Joint 22
Overheated Joint 24
Insufficient Wetting (Pad) 25
Insufficient Wetting (Pin) 27
Insufficient Wetting 28
(Surface Mount) 28
Solder Starved 29
Too Much Solder 30
Untrimmed Leads 31
Solder Bridge 32
Lifted Pad 33
Repairing a Lifted Pad 34
Stray Solder Spatters 34
All of the Above! 35

Tools

Building a Soldering Toolkit

If you are just getting started in Electronics, Ladyada's Electronics Toolkit (http://adafru.it/136) (pictured above) is a great kit full of quality tools - including everything you need to make great solder joints. If you would rather build your toolkit piece-by-piece, read on:

Choosing a Soldering Iron

There are many types of soldering irons. For most Adafruit kits and projects, you will want a pencil-style soldering iron with 25 watts or more.

An under-powered iron is a poor investment. It will end up costing you more in ruined kits and damaged components.

- It will take longer to heat the joint, allowing heat to spread to the component being soldered - potentially overheating and damaging the component.
- Longer heating times will also give more time for oxides to form on the surfaces being soldered. This will prevent the solder from flowing and result in a poor joint.
- Longer recovery times between joints can result in frustration, 'cold joints' or both.

You don't need to spend a fortune to get a good iron. Advanced features such as temperature control and interchangeable tips are nice to have, but not essential for hobbiest-level work.

Basic Irons

There are many basic pencil style irons that are suitable for hobbiest use. But you will need one that is capable of heating the joints quickly enough. Choose an iron with 25 watts at a minimum.

Better Irons

An adjustable temperature iron with a little more power will give you a bit more control and allow you to work faster. The Adjustable 30W 110v Soldering Iron (http://adafru.it/180) in the store is an excellent choice.

This iron is also available as part of Ladyada's Electronics Toolkit (http://adafru.it/136), which contains many other essential soldering tools.

Best Irons

A professional-style temperature-controlled iron with interchangeable tips and 50 watts or more of power is a joy to work with. Feedback control keeps the tip temperature at precisely the level you set. The extra watts speed recovery time so that you can work faster. Interchangeable tips let you select the ideal tip shape for specialized work.

The 65 watt Hakko FX-888 (http://adafru.it/303) is an excellent professional quality soldering iron. The Weller WES51 or WESD51 are also excellent choices for serious electronics work.

Irons to avoid

In addition to underpowered irons, there are several types of irons to avoid for general circuit-board work.

For emergencies only:

These irons are handy for occasions when you have no place to plug in a regular soldering iron. But they are not the best choice for a primary soldering tool:

- **Butane Powered Irons** have plenty of power but are difficult to control.
- **Battery Powered Irons** are generally underpowered for most work.

BERNZOMATIC
CRAFTSMAN

Not for circuit board use:

These tools are not suitable for circuit board work:

- **Torches** of any kind are not suitable for electronics work and will damage your circuit boards.
- **Soldering Guns** are OK for working with heavy gauge wires, but don't have the precision necessary for soldering delicate electronics components.
- ***Cold-Heat™*** Irons inject current into the joint to heat the tip. This current can be damaging to sensitive electonic components. Avoid these irons for electronics work.

Essential Tools and Supplies:

These tools are the bare-minimum essentials required for soldering:

Stand

If your soldering iron does not have a built-in stand, you will need a safe place to rest the hot iron between uses. A Soldering Iron Stand (http://adafru.it/150) will keep your iron from rolling around and protect both you and your work surface from burns.

Most stand holders come with a sponge and tray for cleaning your soldering iron.

ROSIN CORE
GUARANTEED VIRGIN METALS
GUARANTEED ALLOY
60/40
4 OZ.
.031 DIA

Solder

Standard 60/40 lead/tin Rosin Core Solder (http://adafru.it/145) is the easiest type to work with.

170M Xcelite® U.S.A.

Diagonal Cutters

You will also need a pair of Diagonal Cutters (http://adafru.it/152) for trimming component leads after soldering.

Other Handy Tools and Supplies

These are some other tools and supplies you might find useful when working on soldering projects.

Vise

A vise holds your work steady as you solder. This is important for both safety and sound joints. The Panavise Jr (http://adafru.it/151) is an ideal size for most Adafruit kits and projects.



Third Hand

A Helping Third Hand (http://adafru.it/291) Tool is a good for smaller boards, or to hold things in place while terminating or splicing wires.

Solder Sucker

A Solder Sucker (http://adafru.it/148) is a very helpful tools for removing excess solder or when you need to de-solder a joint. As the name implies, this device literally sucks the solder out of the joint.

ROHS
35+YEARS SPIRIG PATENTED VACUUMISATION WICK MANUFACTURE
no clean
size AB (3)
1.5 m / 5 ft
DESOLDERING BRAID
3S-WICK®
part: LS/AB-1.5 m
TRESSE à DESSOUDER
LOTSAUGLITZE®
antistatic
swiss

Solder Wick

Solder Wick (http://adafru.it/149) is another way to clean excess solder from a joint. Unlike the solder sucker, the wick soaks up the molten solder.

Preparation


Lockout
F/C
701
Weller®
WESD51
Output for PES51
Iron Only.
Use Only Original
Weller Tips.
ESD SAFE

Heat the Iron

Plug an and/or turn on your soldering iron to warm up. If you are using a temperature controlled iron, set it to 700F/370C for 60/40 or 750F/400C for lead-free solder.

While the iron is heating dampen the sponge with a little bit of water.

Clean the Iron

Wipe the tip of the hot iron on the damp sponge to clean off any oxidation.

Do not use files or abrasives to clean the tip. It will damage the plating and ruin the tip.

Tin the Tip

Apply a small amount of solder to the tip and wipe again to tin the tip. You should have a thin, shiny layer of molten solder on the tip of your iron.

If the tip is badly oxidized and difficult to tin, it can usually be reconditioned with some tip-tinning paste.



Make sure that the joint is clean

Dirt, oxidation and oily fingerprints can prevent the solder from wetting the solder-pad to create a solid joint. All Adafruit boards are plated to prevent oxidation, but if your board appears dirty from storage or handling, wipe it down with a little isopropyl alcohol.



Immobilize the Joint

This is very important! The parts being joined must not move during the soldering process. If there is any movement as the molten solder is solidifying, you will end up with an unreliable 'cold joint'.

Most through-hole components can be immobilized by simply bending the leads on the solder-side of the hole.

Steady the Board

A vise is a good way to keep the board from moving around while you try to solder it.

Once the joint is clean and immobilized, you are ready to apply the solder.

Making a good solder joint



Once you have prepared the your tools and the joint to be soldered, making a good solder joint requires just a few simple steps.



Heat the joint

Heat the joint with the tip of the iron. Be sure to heat both the solder pad and the component lead or pin. A small drop of solder on the tip will help to transfer the heat to the joint quickly.



Apply the solder

Touch the end of the solder to the joint so that it contacts both the solder pad and the component lead or pin. It should melt and flow smoothly onto both the pin and the pad. If the solder does not flow, heat the joint for another second or two and try again.



Let It Flow

Keep heating the solder and allow it to flow into the joint. It should fill the hole and flow smoothly onto both the solder pad and the pin or component lead.

Let It Cool

Once enough solder has been added to the joint and it has flowed well onto both the component lead and the solder pad, remove the iron from the joint and allow it to cool undisturbed.



Trim the Lead

Use your diagonal cutters to trim the lead close to the board.

Note: This step applies only to components with wire leads. It is not necessary to trim the pins on Integrated circuit chips or sockets.



Congratulations!

Reward yourself with a Soldering Badge (http://adafru.it/465).

Problems?

The last page of this guide illustrates a number of common soldering problems with advice on prevention and repair.



Surface Mount Components

The previous page showed how to make a good through-hole joint. But more and more components are only available in surface mount form these days. Not all surface mount packages are easily worked by hand, but there are plenty that can be managed with the same basic tools used for through-hole soldering.

Let's start with a surface-mount part common to several Adafruit kits: The SD Card Holder:



Immobilize the Joint

Unlike many surface mount components, immobilizing the SD card holder is relatively easy. There are small pegs on the back that fit into positioning holes in the board. Once it is in place, solder the four small corner tabs to make it permanent.



Heat the Joint

Start by putting the tip of the hot iron on the solder pad adjacent to the pin. The pad will take longer to heat, so we apply most of the heat to the pad to start.



Apply the Solder

When the joint is hot, apply solder to the side opposite the iron. The solder should melt and start to flow into the joint.



Let it Flow

Apply just enough solder to ensure a good joint, then keep the heat on while the solder wicks up between the pin and the pad to make a good electrical bond.



Let it Cool

Remove the iron and allow the joint to cool undisturbed.

Problems?

The last page of this guide illustrates a number of common soldering problems with advice on prevention and repair.

Common Soldering Problems


Cold Joint w/ Insufficient Wetting (Pad)
Cold Joint
Insufficient Wetting (Pin & Pad)
Insufficient Wetting (Pad)
OK
Too Much Solder
OK
Too Much Solder

The Ideal Solder Joint

The ideal solder joint for through-hole components should resemble the diagram below.


Wetting Angle: 40 to 70 degrees From horizontal
Smooth, Shiny Concave Surface

The photos that follow show some common soldering problems, with suggestions for repair and prevention:



Disturbed Joint

A Disturbed joint is one that has been subjected to movement as the solder was solidifying. The surface of the joint may appear frosted, crystalline or rough.

Often called a 'Cold Joint'. They can look similar to a true cold joint, but the cause is different.

Repair: This joint can be repaired by reheating and allowing it to cool undisturbed.

Prevention: Proper preparation, including immobilizing the joint and stabilizing the work in a vise can prevent disturbed joints.



Cold Joint

A 'Cold Joint' is one where the solder did not melt completely. It is often characterized by a rough or lumpy surface. Cold joints are unreliable. The solder bond will be poor and the cracks may develop in the joint over time.

Repair: Cold joints can usually be repaired by simply re-heating the joint with a hot iron until the solder flows. Many cold joints (such as the one pictured) also suffer from too much solder. The excess solder can usually be drawn-off with the tip of the iron.

Prevention: A properly pre-heated soldering iron with sufficient power will help prevent cold joints.








GND
#23
GND
MOSI
#22
21/27
#1





Overheated Joint

At the other extreme, we have the overheated joint. The solder has not yet flowed well and the residue of burnt flux will make fixing this joint difficult.

Repair: An overheated joint can usually be repaired after cleaning. Careful scraping with the tip of a knife, or little isopropyl alcohol & a toothbrush will remove the burnt flux.

Prevention: A clean, hot soldering iron, proper preparation and cleaning of the joint will help prevent overheated joints.



Insufficient Wetting (Pad)

These two joints both show signs of insufficient wetting of the solder pad. The solder has wetted the leads nicely, but it has not formed a good bond with the pad. This can be caused by a dirty circuit board, or by failing to apply heat to the pad as well as the pin.

Repair: This condition can usually be repaired by placing the tip of the hot iron at the base of the joint until the solder flows to cover the pad.

Prevention: Cleaning the board and even heating of both the pad and the pin will prevent this problem.






Bi-Directional
Level Shifter
GND B4 B3 B2 B1 HV


SCL
SDA
SA0
CS
DRDY
INT1
GND
3Vout
VCC



Insufficient Wetting (Pin)

This solder in this joint has not wetted the pin at all and has only partially wetted the pad. In this case, heat was not applied to the pin and the solder was not given adequate time to flow.

Repair: This joint can be repaired by re-heating and applying more solder. Be sure that the tip of the hot iron is touching both the pin and the pad.

Prevention: Even heating of both the pin and the pad will prevent this problem.







Insufficient Wetting (Surface Mount)

Here we have three pins of a surface mount component where the solder has not flowed onto the solder pad. This is caused by heating the pin instead of the pad.

Repair: This is easily repaired by heating the solder pad with the tip of the iron, then applying solder until it flows and melts together with the solder already on the pin.

Prevention: Heat the pad first.



Solder Starved

A solder starved joint simply does not have enough solder. It may make good electrical contact, but it is hard to verify by inspection. In any case, it is not a strong joint and may develop stress cracks and fail over time.

Repair: Re-heat the joint and add more solder to make a good strong joint.





Too Much Solder

This might be a perfectly good joint, but we can't tell for sure. It is entirely possible that this blob of solder wets neither the pin nor the pad and is not a reliable electrical connection. The best evidence of proper wetting (and good electrical contact) is a nice concave surface as on the joint on the far left.

Repair: It is usually possible to draw off some of the excess solder with the tip of a hot iron. In extreme cases, a solder-sucker or some solder wick can be helpful as well.

Adafruit i2c 16x



Untrimmed Leads

Leads that are too long are potential short circuits. The two joints on the left are an obvious danger of touching. But the one on the right is long enough to be dangerous as well. It would not take much force to bend that lead over to touch an adjacent trace.

Repair: Trim all leads just at the top of the solder joint.







Solder Bridge

The left two solder joints have melted together, forming an unintended connection between the two.

Repair: Sometimes the excess solder can be drawn off by dragging the tip of a hot iron between the two solder joints. If there is too much solder, a solder sucker or solder wick can help get rid of the excess.

Prevention: Solder bridges most often happen between joints with too much solder to begin with. Use only enough solder to make a good joint.









Lifted Pad

This photo shows a solder pad that has become detached from the surface of the circuit board. This most often occurs when trying to de-solder components from the board. But it can result simply from overworking the joint to the point where the adhesive bond between copper and the board is destroyed.

Lifted pads are especially common on boards with thin copper layers and/or no through-plating on the holes.



Repairing a Lifted Pad

It may not be pretty, but a lifted pad can usually be repaired. The simplest repair is to fold the lead over to a still-attached copper trace and solder it as shown to the left. If your board has a solder-mask, you will need to carefully scrape off enough to expose the bare copper.

Other alternatives are to follow the trace to the next via and run a jumper to there. Or, in the worst case, follow the trace to the nearest component and solder your jumper to the leg of that. Not exactly pretty, but functional.



Stray Solder Spatters

These bits of solder are held to the board only by sticky flux residue. If they work loose, they can easily cause a short circuit on the board.

Repair: These are easy to remove with the tip of a knife or tweezers.



All of the Above!

Don't panic. Take your time. Most joints can be repaired with patience. If the solder refuses to flow the way you want it to:

1. Stop and let the joint cool.
2. Clean and tin your iron.
3. Clean off any burnt flux from the joint.
4. Let the iron come back up to temperature.
5. Then reheat the joint and try again.

HAND SOLDERING TUTORIAL FOR FINE PITCH QFP DEVICES

Scope

This document is intended to help designers create their initial prototype systems using Silicon Lab's TQFP and LQFP devices where surface mount assembly equipment is not readily available. This application note assumes that the reader has at least basic hand soldering skills for through-hole soldering. The example presented will be the removal, cleanup and replacement of a TQFP with 48 leads and 0.5 mm lead pitch.

Safety

Work should be done in a well-ventilated area. Prolonged exposure to solder fumes and solvents can be hazardous. There should be no presence of sparks or flames when solvents are in use.

Materials

The right materials are key to a good solder job. The list below are the recommendations from Silicon Labs. Other materials may work, so the user should feel free to substitute and experiment. The use of organic solder is highly recommended.

Required

1. Wire wrap wire (30 gauge) *
2. Wire strippers for wire wrap wire *
3. Soldering station - variable temperature, ESD-safe. Should support temperatures 800°F (425°C). This example uses a Weller model EC1201A. The soldering wand should have a fine tip no more than 1 mm wide.
4. Solder - 10/18 organic core; 0.2" (0.5 mm) diameter
5. Solder flux - liquid type in dispenser
6. Solder wick - size C 0.075" (1.9 mm)
7. Magnifier - 4X minimum. An inexpensive headset OptiVISOR by Donegan Optical Co. is used for this example.
8. ESD mat or tabletop and ESD wrist strap - both grounded
9. Tweezers with pointed (not flat) tips
10. Isopropyl Alcohol
11. Small stiff bristle brush for cleaning (nylon or other non-metallic material). Cut off hair to approximately 0.25" (6 mm)

* Required for device removal only.

Optional

1. Board vise to hold printed circuit board
2. Dental pick (90 degree bend)
3. Compressed dry air or nitrogen to dry boards

Copyright © 2003 by Silicon Laboratories

4. Optical inspection stereo microscope 30-40X



Figure 1. Some of the materials to get started...



Figure 2. clock-wise from left: 4X magnifying headset, solder wick, wire wrap wire, stiff cleaning brush, wire strippers, and pointed tweezers

QUICK BRAID
EASY BRAID
Wire Wrapping
WIRE WRAPPING WIRE
30
100
R30B-0100

Figure 3. Solder wick and wire wrap wire

HEALTH ★ CARE
AMERICA
ISOPROPYL
RUBBING ALCOHOL
91% BY VOLUME

Figure 3. Isopropyl Alcohol


Weller
EC1002
ESD SAFE
°Fx10
Weller
Soldering Tool Stand

Figure 4. ESD safe soldering station with fine tip wand. This one is Weller model EC1201A



Figure 5. Optional equipment includes a PCB vise and an inspection microscope 7-40X

Procedure

The following procedures cover the replacement of a TQFP 48 pin device with 0.5 mm lead pitch. The lead shape is the standard gullwing associated with JEDEC standard QFPs. This procedure section is divided into three parts:

A. Part Removal

B. Board Cleanup

C. Soldering a new device.

If you are soldering parts to a new printed circuit board, skip part A and refer to the new board cleanup section in part B.

A. Part Removal

Preparation:

- Board with IC to be removed is mounted in a holder or vise. A PCB holder/vise is optional but it is required that the PCB is held steady for the part removal.
- The soldering station is warmed up to 800°F (422°C) and the solder tip is clean.
- ESD precautions have been taken.



Figure 6. Ready to get started

Begin by wetting all the leads with flux to enhance the initial solder wicking cleanup. Wick up solder as much as possible from the QFP leads. Be careful not to scorch the PCB board with prolonged solder heat.


C23
C22
C13
U1
Q1
C16
C17
J10
C12
C11
GND
C8051FTB02
T0AAOFCA
0103 EP
R9

Figure 7. Apply flux; wick excess solder from pins

Next, strip off approximately 3 inches of insulation from a piece of the 30 gauge wire wrap wire. Cut the wire at a comfortable 12 inch length or so.


T-Stripper
TECHNI-TOOL

Figure 8. Wire stripping

Feed the wire behind and under the leads on one side of the IC as shown in Figure 9.



Figure 9. Feeding wire under QFP leads



Figure 9. Wire with one side anchored to nearby component

Solder tack (anchor) one end of the 3 inch wire to a nearby via or component on the PCB. The anchor point should be in a location similar to that should in Figure 10.

Dispense a small amount of liquid flux across the leads.


CYGNAL Integrated
Products, Inc.
www.cygnal.com
C8051F

Figure 10. Bus wire is anchored on C6

Hold the loose (non-anchored) end of the wire with tweezers in close proximity to the device as shown in Figure 11.



Figure 11. Side 2 anchored and ready for solder heat

You will now need to simultaneously apply solder heat and pull the wire away from the QFP, pulling at a slight upward angle from the board surface. Apply solder heat beginning at the lead closest to your tweezers. As the solder melts, gently pull the wire away from the QFP while continuing to move the solder heat from pin to pin to the right. You should not pull very hard. Pull as the solder melts. Do not leave the solder heat on any lead for more than necessary. The first lead will take the longest to heat, and after the wire gets hot, solder on the other leads will melt quickly. Excessive heat will damage the IC device and the PCB pad. The removal of 12 pins from a 48TQFP should take about 5 seconds total. Signs of excessive heat are:

- Melted plastic on the IC device
- PCB pads that lift off
- Brown scorch marks on the PCB

With one side of the QFP completed, repeat the same procedure on the other three sides of the QFP. Cut off the dirty part of the wire wrap wire or use a new piece for each side. Dispense flux again for each side.

Note that in the following pictures, the old IC device is not being saved. There is slightly more heat being applied here than necessary to speed up the process. This result is some melted plastic and missing gull-wing leads. These are visible in the pictures that follow. If you are trying to save the IC being removed, then you must be very careful to apply as little heat as possible during the removal process such that the QFP leads remain intact in the plastic QFP body. This will require some experimentation with solder heat settings and timing.



Figure 12. Hold tweezers close to device



Figure 14. Side 2 almost complete


C8051FTB02
TQAAOFCA
0103 EP
C13
C22
C12
C16
C17
J10
U1
PWMIN

Figure 15. Side 2 is done


C8051FTB02
TQAAOFCA
0103 EP
J10
U1
C13
C22
C23
+3VD

Figure 16. Side 3 anchored and ready



Figure 17. Side 4 anchored to a via



Figure 18. Side 4 removal started



Figure 19. QFP removal a second before completion

B. Board Cleanup

New PCBs

For mounting a device to a new PCB, the amount of cleanup should be minimal. On a new PCB, there should be no solder on the pads. Brushing the pads with isopropyl alcohol (Figure 33) and drying the board should be enough preparation to begin the mounting procedure.

Reworked PCBs

The following section is the cleanup sequence that follows the QFP removal in the previous section. After removing the device, the solder pads will need cleanup. The idea is to clean the pads so that they are flat and free or solder and flux. Solder wick the pads until they are flat and dull. A clean pad appearance should be a dull silver color.



Figure 20. Pads after QFP removal procedure



Figure 21. Solder wick to remove solder on the pads



Figure 22. Repeat for all pads

If any pads become loose from the PCB, use a dental pick or other pointed object to re-align the pad (Figure 23 and Figure 24).


C11
C12
C16
U1
C13
C22
C23
Q1
J10

Figure 23. Clean pads but one pad is slightly crooked


C11
C12
C16
U1
C13
C22
+3VD
C23
Q1
J10

Figure 24. Pad straightened out

B. Soldering a new QFP

The pads on the PCB should be clean and free of any solder.

Carefully place the new QFP device on the PCB using tweezers or another safe method. Make sure the part is not dropped as the leads can be easily damaged.

Align the part over the pads using a small pick or similar tool to push the part. Get the alignment as accurate as you can. Also, make sure that the part is oriented correctly (pin 1 orientation).



Figure 25. New QFP near pads, ready for alignment



Figure 26. QFP aligned

Adjust the soldering station temperature to 725°F (385°C). Put a small amount of solder on the tip of the solder iron. While holding down the aligned QFP with a pick or other pointed tool, add a small amount of solder flux to the corner leads in two opposite corners. While still holding the part down with the pick, solder down two opposite corner leads on the QFP. Do not worry about excess solder or shorts between adjacent leads at this time. The idea is to anchor down the aligned QFP with solder so it does not move.



Figure 27. Aligned QFP ready for solder anchoring

Re-check the QFP alignment after soldering the corners. If necessary, make adjustments or remove and start over to get good QFP to PCB alignment.



Figure 28. Aligned QFP with corners soldered down

Now you are ready to solder all the leads. Add solder to the tip of the soldering iron. Dispense flux over all the leads to keep them wet.

Touch the solder iron tip to the end of each QFP lead until the solder is seen running up the lead. Repeat for all the leads. Add small amounts of solder as needed to the soldering iron tip. Again, do not worry if you see some solder bridging as you will clean that up in the next step.

When soldering, keep the soldering iron tip parallel with the pins being soldered to prevent excessive solder shorts.



Figure 29. Keep iron tip parallel to pins being soldered

After soldering all the leads, wet all the leads with flux to enhance the solder wicking cleanup. Wick up solder where needed to eliminate any shorts/bridging.



Figure 30. Wicking Solder #1



Figure 31. Wicking Solder #2

Hand inspect the board using 4X magnification (or higher) for shorts or marginal solder joints. Solder joints should have a smooth melt transition between each device pin and the PCB. Rework any pins as needed



Figure 32. Visual Inspection

After the inspection passes, it is time to clean the flux off the board. Dip the stiff bristle brush into alcohol and wipe in the direction of the leads. Use moderate, but not excessive pressure. Use liberal amounts of alcohol and brush well between the QFP leads until the flux disappears.



Figure 33. Isopropyl Alcohol and stiff brush used for cleanup.
Brush only in direction of leads

Dry the board with compressed dry air or nitrogen. If this is not available, let the board dry for 30 minutes or more to let the alcohol evaporate under the QFP. The QFP leads should look bright and there should be no flux residue.



Figure 34. Clean and Pristine

Re-inspect the board for workmanship. Rework any leads if needed.

Figure 35. Stereo zoom inspection station (7X to 40X magnification) helps to inspect solder joint workmanship



Simplicity Studio

One-click access to MCU and wireless tools, documentation, software, source code libraries & more. Available for Windows, Mac and Linux!

IoT Portfolio
www.silabs.com/IoT

SW/HW
www.silabs.com/simplicity

Quality
www.silabs.com/quality

Support and Community
community.silabs.com

Disclaimer
Silicon Labs intends to provide customers with the latest, accurate, and in-depth documentation of all peripherals and modules available for system and software implementers using or intending to use the Silicon Labs products. Characterization data, available modules and peripherals, memory sizes and memory addresses refer to each specific device, and "Typical" parameters provided can and do vary in different applications. Application examples described herein are for illustrative purposes only. Silicon Labs reserves the right to make changes without further notice and limitation to product information, specifications, and descriptions herein, and does not give warranties as to the accuracy or completeness of the included information. Silicon Labs shall have no liability for the consequences of use of the information supplied herein. This document does not imply or express copyright licenses granted hereunder to design or fabricate any integrated circuits. The products are not designed or authorized to be used within any Life Support System without the specific written consent of Silicon Labs. A "Life Support System" is any product or system intended to support or sustain life and/or health, which, if it fails, can be reasonably expected to result in significant personal injury or death. Silicon Labs products are not designed or authorized for military applications. Silicon Labs products shall under no circumstances be used in weapons of mass destruction including (but not limited to) nuclear, biological or chemical weapons, or missiles capable of delivering such weapons.

Trademark Information
Silicon Laboratories Inc.® , Silicon Laboratories®, Silicon Labs®, SiLabs® and the Silicon Labs logo®, Bluegiga®, Bluegiga Logo®, Clockbuilder®, CMEMS®, DSPLL®, EFM®, EFM32®, EFR, Ember®, Energy Micro, Energy Micro logo and combinations thereof, "the world's most energy friendly microcontrollers", Ember®, EZLink®, EZRadio®, EZRadioPRO®, Gecko®, ISOmodem®, Precision32®, ProSLIC®, Simplicity Studio®, SiPHY®, Telegesis, the Telegesis Logo®, USBXpress® and others are trademarks or registered trademarks of Silicon Labs. ARM, CORTEX, Cortex-M3 and THUMB are trademarks or registered trademarks of ARM Holdings. Keil is a registered trademark of ARM Limited. All other products or brand names mentioned herein are trademarks of their respective holders.

Silicon Laboratories Inc.
400 West Cesar Chavez
Austin, TX 78701
USA

http://www.silabs.com

Soldering Guidelines

Solder0 R0.1

EE400/1
Design

Revision History

Rev.	Date	Contributor	
0.1	September 2005	L. Wyard-Scott	Updates to reflect changed Capstone Design Course format and new de/soldering equipment.
0.0	January 2004	V.J. Sieben, L. Wyard-Scott, E. Tiong	Creation.

Contents

1 Soldering Technique **1**
- 1.1 Required Tools . . . 1
- 1.2 Important Soldering Tips . . . 2
- 1.3 Precautions . . . 3
- 1.4 How to Solder Through-Hole Components . . . 4
- 1.5 How to Solder Surface-Mount Components . . . 8
- 1.6 Wire Connectors and Headers . . . 9
  - 1.6.1 Crimp Connectors and Pins . . . 9
  - 1.6.2 DB Connectors (Solder Cup Type) . . . 10
  - 1.6.3 Joining Two Wires . . . 10
- 1.7 Testing Connections . . . 11
- 1.8 Milled Board Soldering . . . 12
- 1.9 Post-Soldering Cleanup . . . 12
  - 1.9.1 PCB Cleanup . . . 12
  - 1.9.2 Work Area Cleanup . . . 12

2 Desoldering Technique **13**
- 2.1 Solder Pump/Sucker . . . 13
- 2.2 Desoldering Braid/Wick . . . 14
- 2.3 Desoldering Iron . . . 15
- 2.4 Removing Components Effectively . . . 16

3 Glossary **17**

Bibliography **18**

A Pictures of Tools **19**

Chapter 1

Soldering Technique

This guide is intended to give an introduction to basic soldering technique. If the reader desires to pursue advanced soldering techniques, there are several books as well as technical institutions that offer detailed courses in the area of soldering.

1.1 Required Tools

Before discussing soldering techniques, one should must set up a "soldering work station". The following is a list of tools for a typical soldering station. See Appendix A for pictures of the various parts listed below.

1. **Variable temperature soldering iron:** used for applying heat to joints during the soldering process.
2. **Damp sponge:** for cleaning soldering iron tip.
3. **Rosin-core solder:** to electrically and mechanically bond a component to the PCB.
4. **Wire cutters or side cutter:** for trimming component leads and stripping insulation from wires.
5. **Needle nose pliers:** for holding, placing and shaping components.
6. **Desoldering pump and/or desoldering braid:** for removing solder.
7. **Scotch tape and/or a "Third Hand":** for securing components.

8. **Safety glasses:** for eye protection. These are mandatory in the lab.
9. **Magnifier:** to provide more detail during intricate work. A magnifying glass is convenient, but an illuminated magnifier is better.
10. **Light source:** to prevent eye-strain.
11. **Ventilation:** to extract and dispel fumes generated during the soldering process.
12. **Flux:** to clean components and PCB pads.
13. **Acid brush:** to assist in the removal of flux residue.

Prior to soldering it is a good idea to have all components organized as it will make populating the PCB more efficient. Make a BOM (bill of materials) for the PCB, and ensure before soldering that the components have been collected. The schematic and PCB layout will also be referred to when populating the board.

1.2 Important Soldering Tips

The following tips provide a quick guideline on how to make proper joints.

Cleanliness: All parts, including the soldering iron tip, must be clean and free from grease, oxidation and contamination. Solder does not flow over contaminated areas; moreover, solder is repelled by dirt. Severe contamination is evident when solder begins to "bead". A common source of contamination is oxidation. Old components and copper boards will often have an oxide layer that prevents a good solder joint. Ensure all components have shiny leads and the PCB has clean traces. An abrasive such as a blue or pink eraser, emery paper, or stell wool can be used to remove the oxidized layer from the PCB board and components.

Tinning: In addition to being clean, the soldering iron tip must also be tinned (coated with solder). Tinning the tip allows solder to flow on the components more quickly rather than the soldering iron tip itself. Tinning involves adding a few millimetres of solder to the tip and then wiping and rotating the tip on the damp sponge to reveal a shiny surface on the tip of the soldering iron: a thin layer of solder will coat or "tin" the tip of the soldering iron. **When done soldering,**

tinning the iron is required to protect the tip from oxidation thereby dramatically increasing its life.

Temperature: Ensure that both the component leads and the PCB's copper layer are heated at the same time. The soldering iron tip should contact both the component and the PCB pad. This will ensure that each surface is relatively close in temperature resulting in a good joint. If there is a temperature difference between the two surfaces, the solder will form a "dry" joint. Soldering irons are typically set around 650 Fahrenheit, depending on the lead-tin ratio of the solder being used. Too much heat causes excessive "sputtering" of flux, and too little doesn't melt the solder in a timely manner.

Duration: The duration that the iron is in contact with the component and PCB is dependent on the size of the joint and your soldering iron temperature. For the typical PCB through-hole joint, it should take a few seconds to heat the joint and apply the solder. This will require practice, so don't expect to be fast if you are a beginner. Excessive heat (several seconds in duration) will damage sensitive semiconductors. If this is a concern, use a heat sink attached to the component leads: sometimes as simple as an alligator clip. These concerns can sometimes be avoided by soldering sockets instead of the semiconductor itself.

Adequate solder coverage: If too little solder is applied, the joint will not make a secure connection and will cause erratic behaviour. However, if too much solder is applied, the joint may bridge with adjacent joints resulting in electrical shorts. How much solder to apply comes with experience. Figs. 1.4 through 1.7 show good and bad solder joints.

Handling: Most modern electronics systems contain static-sensitive devices. Use proper handling procedures to minimize the likelihood of damage: grounding wrist-straps, grounded soldering irons, grounding mats, etc.

1.3 Precautions

Soldering Irons get very hot (600-800^{0}F, 315-425^{0}C), please ensure you follow precautions during use. Basic safety precautions are listed below.

- Never leave your iron turned on while unattended.

- Turn the soldering iron off when it is not being used. If the iron is left on for long periods of idle time, the soldering iron tip will be destroyed through oxidation.
- Eye protection must always be worn when soldering. Hot flux can spit up and into an unprotected eye. **In the Capstone Design Lab, use of eye protection is mandatory.**
- If the cord of the soldering iron is damaged, inform the lab staff who will ensure it is replaced.
- Never set the soldering iron down on anything other than an iron stand.
- To prevent burning your fingers, use needle nose pliers, heat resistant gloves, or a third hand tool to hold small pieces.
- Familiarize yourself with the safe handling of all materials used during the soldering process. This includes solder, flux, alcohol, and desoldering braid. Each has a Material Safety Data Sheet (MSDS) and can be found in the lab or online. "Safe Operating Procedures" are found posted on the wall close to the soldering facilities.

1.4 How to Solder Through-Hole Components

Most of the soldering done in the Capstone Design Lab is through-hole. A through-hole joint is a type of soldering joint in which the component joins with the PCB pad through a physical hole in the board. The following steps will illustrate how to make a proper through hole solder joint on a PCB.

1. Ensure that the printed circuit board and all components are clean. Cleaning can be achieved with a mild abrasive and/or the application of flux.
2. Plug in the soldering iron, turn it on, and let it warm up for 2–3 minutes.
3. Wet the soldering station sponge with the water provided in the lab. Do not wet the sponge in the bathroom or the water fountain.
4. Clean the tip of the soldering iron and tin it with solder.

5. Insert the component into the holes. Ensure that the component is secure by taping the component or by using a third hand. Optionally, the component leads can be clinched as shown in Fig. 1.1. This technique, however, is not recommended for two-sided boards as the flow of solder to the component side is restricted.



Figure 1.1: Clinched Component Leads

6. Apply the soldering iron tip to one side of joint making contact with the component lead and the board copper foil, ensuring that both are heated up to the same temperature as shown in Fig. 1.2 and Fig 1.3. Notice the tinned tip in Fig. 1.3.

7. Slowly add a few millimetres of solder to the other side of the joint. DO NOT apply solder to the soldering iron tip. If enough heat was applied to the PCB pad and component wire, the solder will flow freely onto the joint.



Figure 1.2: Method of Soldering Through Hole Joints

8. Remove the solder when the joint is suitably covered as shown in



Figure 1.3: Method of Soldering Through Hole Joints, [8]

Fig. 1.4. The goal is to get the joint to be a “fillet”: a curve as shown in Fig. 1.4.

9. If the PCB is double-sided, the solder should flow through the hole around the component lead and make a bond on the component side of the board (opposite to the side that the solder was applied). If this “wicking” does not occur, the hole may be undersized, clinching could be blocking the solder’s path, or the component lead is not clean.

10. Remove the soldering iron and allow the joint to cool naturally.



Figure 1.4: Good Solder Joint - Solder Fillet

11. Cut the lead of the component, if necessary.

Fig. 1.6 and Fig. 1.7 below are pictures showing good and bad solder joints.



Figure 1.5: Good Solder Joint, [8]


Good Solder Joint
Too Much Solder
Cold Solder Joint

Figure 1.6: Joint Examples, [3]


Good
Cold
Dry
Shortage
Excess

Figure 1.7: Joint Examples, [2]

1.5 How to Solder Surface-Mount Components

Surface mount soldering requires more experience and skill than through hole. It is recommended that one practices with through-hole prior to attempting any surface mount soldering. As the name suggests, surface mount involves soldering a component to either the top or bottom surface of a PCB. Depending on the footprint, the pads are usually a spaced closer together (finer pitch), making the soldering more susceptible to solder bridges, etc.

Figs. 1.8 and 1.9 show examples of good surface-mount solder joints.



Figure 1.8: Surface Mount Good Solder Joint, [6]



Figure 1.9: Surface Mount IC with Good Solder Joints, [5]

The actual soldering of the joints is similiar to the through-hole method. One difficulty, however, is maintaining the part's alignment on the PCB pads. A good technique is outlined here:

1. Align the component on the PCB pads. This can be aided with the use of tweezers and dental picks.
2. Secure the component to the PCB by applying a small amount of pressure onto the top of the component using a small slot screwdriver.

An index finger resting on the end of the screwdriver provides enough force to secure the device.

3. Solder one of the corner component leads to the PCB pad.
4. Align the remaining pads and solder the opposite corner PCB pad.
5. Solder the remaining pads in a pattern that does not build-up too much heat in the device.

1.6 Wire Connectors and Headers

When PCBs are manufactured they often have connectors to peripheral devices. These connectors are like other components in how they are soldered onto the PCB. However, the plug that matches the connector usually also requires some soldering. **Please note that with very few exceptions, the wire used for cabling is stranded (rather than solid-core) due to its higher strength and flexibility.** Below are procedures for a few of the more common plug types.

1.6.1 Crimp Connectors and Pins

1. Strip off about 1cm of the wire insulation.
2. Place the exposed wire into the crimp-style connector or pin. The wire should just barely show coming out the other side. Some crimp pins have two crimping areas – one for the stripped wire, and the other for the wire *with* the insulation.
3. Crimp the connector with the appropriate crimping tool. Note that the connectors are colour coded to settings on the crimping tool, try and match the correct colour.
4. As added insurance, apply solder to the joint to solidify the connection.

Before crimping all pins destined for a connector housing, start with one and ensure that it fits successfully into the housing. If the crimp is made too tightly, or otherwise mis-shaped, the pin may no longer fit.



Figure 1.10: Colour Coded Crimp Connectors

Figure 1.11: Crimp connector without shrink wrap, [1]

1.6.2 DB Connectors (Solder Cup Type)

1. Strip off about 5mm of the wire insulation.
2. Tin the wire.
3. Slide shrink wrap on the wire.
4. Place the wire into the DB - connector solder end.
5. Apply the soldering iron tip to the connector and wire.
6. Apply a few millimetres of solder until the joint is adequately covered.
7. Let the joint cool.
8. Slide the shrink wrap over the joint and heat the shrink wrap with a heat gun (or other heat source) until the wrap shrinks around the joint.

1.6.3 Joining Two Wires

1. Slide shrink wrap on one of the wires.
2. Tin or coat each wire with some solder.
3. Join the wires in a way that provides a good mechanical connection (such as twisting together) and apply the soldering iron tip and some solder.



Figure 1.12: DB Connector with shrink wrap, [7]

4. Let the joint cool.
5. Slide shrink wrap over the joint and heat the shrink wrap with a heating gun or a heat source until it the the wrap shrinks around the joint.



Figure 1.13: Two wire joint insulated by shrink wrap, [4]

1.7 Testing Connections

After completely soldering a component to a PCB, it is good practice to ensure connectivity between the component wire leads and the PCB pads they are soldered to. A DMM (Digital Multi-Meter) is sufficient to determine connectivity; many DMMs include an audible connectivity setting, but failing this, measure the joint resistance.

1.8 Milled Board Soldering

In-lab manufacture of PCBs uses a technique known as “milling”. The milling technique involves cutting out the PCB tracks and pads from the copper-clad board.

Due to its construction, a milled PCB is susceptible to solder-bridging across the milled grooves, particularly when an excess of solder is used. Finding a short caused by a bridge is a difficult task, particularly when many solder joints exist. To this end, make a limited number of solder connections and then test for bridges using a multimeter.

1.9 Post-Soldering Cleanup

1.9.1 PCB Cleanup

The flux left behind by rosin-core solders, or perhaps as part of the cleaning process, needs to be removed from the PCB. Due to the flux’s sticky nature, dirt gathers and contributes to short-circuiting problems. The most frustrating part of this situation is that a short does not necessarily occur immediately. Weeks, or even years later, a short can develop.

To remove flux, alcohol is used. Apply the alcohol liberally and then brush away with an acid brush, starting at the center of the PCB and working out toward the edges. This is a time-consuming task, but a clean board is well-worth the effort.

1.9.2 Work Area Cleanup

The importance of keeping your work area clean cannot be emphasized enough. When clear of obstructions and garbage, handling a hot soldering iron is safer. The soldering process itself involves chemicals and substances which are known to have ill-effects in humans. Wiping-down the work-area surfaces with a moist paper towel will help reduce some contamination. When you are done soldering, **wash your hands with soap and water** to get rid of contamination. The primary concern here is accidental ingestion of the chemicals. For more information, please refer to the Safe Operating Procedures, posted in the lab’s soldering area.

Chapter 2

Desoldering Technique

Desoldering may be required for several reasons:

- a component may have failed
- a wrong part was installed;
- a design modification necessitates a change; or
- if a board contains expensive components that can be salvaged.

Whatever the reason, there are three common techniques to remove solder from a joint: using a desoldering pump, a desoldering wick, or desoldering iron.

Regardless of the method used, if it is permissible to destroy the part during removal, then a lot of time and effort can be saved. For instance, using wire cutters to trim off all the pins of a through-hole IC so they can be removed individually makes the removal process much easier. In most cases, avoiding damage to the PCB is of paramount importance.

2.1 Solder Pump/Sucker

A desoldering pump is exactly what it sounds like: a pump that sucks up solder. Usually the pump is spring-loaded and provides a recoil when released. The four steps below outline how to desolder a joint using a desoldering pump.

1. Prime the desoldering pump. This involves depressing the desoldering pump spring. The pump will click when correctly depressed.

2. Heat the joint from one side with the soldering iron tip. Wait 1-2 seconds until the solder begins to melt from the soldering iron heat.
3. Put the pump tip on the other side of the joint. Don't be afraid to actually touch the joint.



Figure 2.1: Desoldering with a Solder Pump, [8]

4. Press the desoldering pump spring-release button to suck up the solder.

This procedure should be repeated if the joint has a significant amount of solder. If done correctly the joint should eventually look as shown in Fig. 2.2 shown below.



Figure 2.2: Clean Joint from Desoldering with a Solder Pump, [8]

2.2 Desoldering Braid/Wick

A desoldering braid removes solder from a joint using a technique known as "wicking". Desolder braid is a piece of material that sponges up molten solder by capillary action that draws solder away from the joint the braid. The following procedure outlines the basic steps involved in desoldering a joint using desoldering braid.

1. Place the desoldering braid over the joint.
2. Press the desoldering braid onto the joint with the soldering iron tip. This will apply heat to the desoldering braid and the joint allowing the molten solder to flow.
3. Wait for the solder to melt. The solder should flow onto the braid and away from the joint.



Figure 2.3: Desoldering with a Solder Wick, [8]

4. Cut off the solder coated portion of the desoldering braid. **There should be no copper visible in the portion that is removed: braid is very expensive.**

2.3 Desoldering Iron

Using a desoldering iron, available with higher-end soldering stations, is similar to using a solder sucker. The desoldering iron is essentially a soldering iron with a built-in vacuum.

1. Make contact between the iron and the joint to be desoldered, ensuring the vacuum opening is not blocked.
2. Once the solder on the joint has become molten, depress the button on the iron to activate the vacuum.

It is very important for the life of the desoldering iron that the vacuum assembly be cleaned after every session of use. Please ask the lab personnel for a description of the cleaning procedure.

As with a normal soldering iron, the desoldering iron tip should be tinned before and after every use.

2.4 Removing Components Effectively

To remove a component with little or no damage to the PCB or component takes practice and **patience**. Often when removing a component, PCB pads and tracks may be damaged by “lifting” off the board. Below are some tips that may be useful when removing components from a PCB.

- Desolder all joints pertaining to a component prior to removal. It may be necessary to go over the joints several times before all the solder is removed. Practice patience.
- Use pliers and *gently* pull on components while applying heat to the joints. The assistance of a friend can help with this.
- Do not pull with force, because the PCB pads and tracks will be damaged.
- Do not try and remove components by prying them.
- Do not try to push the component out of the holes with the soldering tip. This will certainly lift the copper pad off of the PCB and ruin the iron tip.
- In order to get better thermal conductivity between the iron and the solder joint, it is sometimes effective to *add* a small amount of solder.

Chapter 3

Glossary

BOM: Bill of Materials, which contains a list of all components and values contained on a particular PCB. Used as a “shopping list”.

Desoldering Braid: A material used to remove solder with capillary action.

Desoldering Pump: A device used to remove solder with a swift vacuum action.

Flux: Cleans the surfaces that are being heated by bringing contaminants to the surface. Most solders include flux in their core. For excessive contamination use a flux pen.

Footprint: The spacing pattern or layout of pads for a particular component or integrated chip, as used on a PCB.

PCB (Printed Circuit Board): A fibreglass board upon which copper traces are laminated to make connections between various components. The copper traces serve as flat wires connecting various components.

Shrink Wrap: A tube that fits over a wire, that when heated shrinks to provide insulation and support for the joints.

Bibliography

[1] R. Glass. Electrical wire soldering for beginners. Technical report. http://www.airheads.org/contrib/solder.html.

[2] D. Lauder. How to solder. Technical report, Oct 2001. http://dragon.herts.ac.uk/ eleqdml/teaching/general/soldering/.

[3] W. M. Leach. The leach amp. Technical report, 2000. See section on Assembly of Circuit Boards, http://users.ece.gatech.edu/ mleach/lowtim/part2.html.

[4] Macroman. Cutting neon string. Technical report. http://www.bit-tech.net/article/59/.

[5] K. Maxon. Have you seen my new soldering iron? Technical report. http://www.seattlerobotics.org/encoder/200006/oven-art.htm.

[6] NIST. Archive of surface evolver code. Technical report. http://www.ctcms.nist.gov/solder/archive.html.

[7] Serial Tester. Serial tester. Technical report. http://army-gps.robins.af.mil/tech/Serial-tester/proc06.jpg.

[8] A. Winstanley. The basic electronics soldering and desoldering guide. Technical report, Feb 1999. http://www.epemag.wimborne.co.uk/solderfaq.htm.

Appendix A

Pictures of Tools



Figure A.1: Soldering Iron

KESTER SOLDER

Figure A.2: Solder Wire



Figure A.3: Desolder Pump



SODER-WICK®
ROSIN SD
SIZE#3
80-3-5
Chemtronics®
SODER-WICK®
ROSIN SD
SIZE#3
80-3-5
Chemtronics®

Figure A.4: Desolder Braid



Figure A.5: Third Man

Soldering

Contents

Introduction 2

1 Soldering Printed Circuit Boards... 3

2 Types of Solder.. 4

3 Types of PCB 5
    3.1 Through-Hole Components 5
    3.2 Surface Mount Components 5

4 Flux... 6

5 Soldering Irons 7
    5.1 Tips 8
    5.2 Tip Contamination and Cleaning... 9

6 Ovens and Hot Plates... 10

7 Desoldering.. 11

8 Hazards involved in soldering 12
    8.1 Heat.. 12
    8.2 Toxic materials 12
    8.3 Spattering.. 13
    8.4 Electrical Safety.. 13

2

Introduction

Soldering is a process used for joining metal parts to form a mechanical or electrical bond. It typically uses a low melting point metal alloy (solder) which is melted and applied to the metal parts to be joined and this bonds to the metal parts and forms a connection when the solder solidifies. It is different to welding in that the parts being joined are not melted and are usually not the same material as the solder.

	
Soldering copper pipe	Sheet metal fabrication

Figure 1 – Different Types of Soldering

Soldering is a common practice for assembling electrical components and wiring. Although it can be used for plumbing, sheet metal fabrication or automotive radiator repair the techniques and materials used are different to those used for electrical work. This document is intended to provide guidance on the safe working methods and proper tools and techniques for soldering of electrical components.

1 Soldering Printed Circuit Boards

Soldering may be used to join wires or attached components to a printed circuit board (PCB). Wires, component leads and tracks on circuit boards are mostly made of copper. The copper is usually covered with a thin layer of tin to prevent oxidization and to promote better bonding to other parts with solder. When soldering bare copper wires they are often “tinned” by applying molten solder before making a joint.

	 大尺寸PCB板独立温区 小尺寸PCB板独立温区 250℃ 200℃ 180℃ 100℃ 50℃ 25℃ 时间（秒） 50 100 150 200 250 300
Hand soldering components on PCB	Industrial oven for surface mount

Figure 2 – Different Types of PCB Soldering

2 Types of Solder

There are different types of solder used for electrical work. They are broadly classified as tin/lead solders or lead free solders. Tin/lead solders have been used for many years because of their ease of use however they have been phased out of commercial use due to the harmful effects on humans and the environment. Tin/lead solder is still available and is used by “hobbyists” and other non-commercial users as it is still easier to use than lead free types. When using tin/lead (or leaded) solder there are additional safety precautions that must be observed.

	
Different gauges of solder wire	Solder composition is labelled (Lead free on left)

Figure 3 – Different Types of Solder

3 Types of PCB

Printed circuit boards (PCBs) are populated by electronic components and these may be “surface mount” or “through-hole” types.

3.1 Through-Hole Components

As the description “through-hole” suggests, the leads of the component are passed through holes in the PCB and then soldered to a “pad” on the reverse side of the PCB. Soldering is accomplished by heating the component lead and PCB pad with a soldering iron and melting solder wire into the joint. This type of construction was common from the 1960’s until early 2000’s and is still used by hobbyists and in small scale production where manual assembly is preferred.

3.2 Surface Mount Components

Commercial circuits are mostly of the surface mount type as these are cheaper to make, more compact and easier to automate assembly. For surface mount construction the component’s pads are on the same side of the PCB as the component and the component connections sit onto these pads. Soldering is accomplished by applying solder paste onto component pads on the PCB, placing the component onto the paste and then heating the entire assembly to melt the solder. Commercial assembly uses ovens to heat the boards. Hobbyists can also use surface mount components and soldering can be accomplished by applying solder paste and melting with a hot plate, small oven or soldering iron. Some surface mount joints can be soldered using a soldering iron and solder wire.



Through-hole PCB
(non-component side)

Surface mount PCB
(component side)

Figure 4 – Different Types of PCB

4 Flux

For electrical soldering both solder wire and solder paste contain flux. This helps to clean the surfaces being soldered and prevent oxidization of the hot solder. The composition of the flux will vary depending on whether it is in a paste or wire, leaded or unleaded solder. Solder wire usually contains a flux called “rosin”. Most fluxes will produce fumes when the solder is heated and these fumes are likely harmful to your health. For occasional soldering it may be sufficient to have a well-ventilated workspace but for longer or repeated exposure a fume extractor should be used. Solder flux can also cause solder to spatter and eye protection should be worn when soldering.



Fumes produced when soldering

Workstation with fume extraction system

Figure 5 – Fumes and Fume Extraction Systems

5 Soldering Irons

Soldering irons come in many varieties and sizes. Soldering irons may be electric, gas powered or externally heated. Most common types are electric. Simple electric soldering irons have no controls and you simply plug them in and wait for them to heat up. Their temperature is regulated by the power of the heating element and heat loss to the environment. Some soldering irons have temperature controls which allow the user to set a desired operating temperature for the soldering iron. This is useful if the soldering iron is being used for different types of solders which have different melting points or if the soldering iron is being used for other purposes such as heating heatshrink. It also introduces a problem if the user does not set an appropriate temperature for the work, solder can be overheated and decompose. Hotter is not better! A temperature of around 320 °C works well for 60/40 leaded solder. Some temperature controlled soldering irons use interchangeable tips to change the temperature at which they operate.

	
A range of electric soldering irons	Choose an iron appropriate for your task!

Figure 6 – Types of soldering irons

	
Adjustable temperature soldering stations	Different tips set the temperature for this station

Figure 7 – Types of soldering stations

5.1 Tips

Heat is transferred from the tip of the soldering iron to the joint by thermal conduction enabled by metal to metal contact between the tip and joint. The tips of soldering irons come in various shapes and sizes to enable the best contact to be made. Most tips are either conical or chisel shapes. The shape is largely a personal preference and you can use whichever type works best for you. The size of the tip should be selected to allow the tip to be placed against the joint being soldered without interfering with adjacent parts. The tip should be large enough to conduct sufficient heat into the joint to allow the solder to melt and flow properly. The choice of tip size is not a precise calculation and a “normal” size tip will work for most joints on a PCB.

5.2 Tip Contamination and Cleaning

The thermal conduction from the tip to the joint may be inhibited by contamination on the tip. This contamination can be formed by burnt solder flux or oxidized solder. To make best thermal contact the tip should be cleaned using a tip cleaner(!). Two types are a wet sponge or a brass wire wool. The wet sponge removes the contaminated material when the tip is wiped across it, the water in the sponge cools the solder and the mechanical abrasion removes the contamination leaving a thin coating of clean solder on the tip. This method can cause the tip temperature to dip momentarily. The brass wire wool type removes the contamination by mechanical abrasion and bonding contaminated solder to the brass. The tip is pushed into the brass wool and when it is withdrawn the tip is clean with a thin coating of solder. You must not “wipe” the tip on the brass wool type because the springiness of the brass wool may flick molten solder which may cause burns to people or objects. You should never “flick” excess solder from the soldering iron as this may also cause burns or damage.

	
Tip contaminated with old solder and burnt flux	Brass wool type tip cleaner

Figure 8 – Dirty tip and brass wool cleaner

6 Ovens and Hot Plates

For surface mount soldering the heat is usually applied to the whole PCB and all components soldered at the same time. For commercial work this is done in large ovens, often with conveyors to move the boards through the oven. For small scale work simple infrared ovens are available. Another technique uses a hotplate. The same considerations for temperature apply, although because the heat source does not come into contact with the solder or flux, contamination is less likely. Time and temperature are considerations with these methods as the components are exposed to the high temperature for the period required for the solder paste to melt and flow.

	
Infrared oven for surface mount soldering	Hotplate for surface mount soldering

Figure 9 – Oven and hot plate used for surface mount soldering

7 Desoldering

If a part that has been soldered needs to be replaced it needs to be “de-soldered”. Depending on the part and type of joint it may be possible to simply re-melt the solder and remove the part, or it may be necessary to remove the solder from the joint so the part can be freed. Some methods for removing solder are solder wick, solder sucker or de-soldering tool. Solder wick is a copper braid which is applied to the joint and heated with a soldering iron. As the solder in the joint is melted it is drawn into the solder wick like a sponge and is removed from the joint. A solder sucker is a spring loaded syringe or rubber bulb. The tip of the solder sucker is placed near the joint as the joint is melted by a soldering iron. When the sucker is operated a vacuum is created which draws the molten solder from the joint into the body of the sucker. A de-soldering tool is a type of soldering iron with a hollow tip and is connected to a pump or vacuum source. The tip of the de-soldering tool is placed onto the joint, typically over a component lead, and once the solder has melted the pump is operated to draw the molten solder away.

	
Solder wick, syringe type sucker, vacuum de-soldering tool	Hot tweezers or Hot air nozzle are options for SMDs

Figure 10 – Desoldering tools and tweezers for surface mount devices

8 Hazards involved in soldering

8.1 Heat

Although solder has a relatively low melting point this temperature is more than high enough to cause serious burns to people or objects. It is important to hold the soldering iron only by the insulated handle, never touch the heating element or tip when the soldering iron is on. The soldering iron will remain hot for some time after it is turned off so always check that it has cooled down before touching it, e.g. if changing the tip. When you are not soldering always keep the soldering iron in a proper holder so that you don't touch it accidently and it doesn't heat or burn other objects such as the benchtop. Don't hold parts being soldered with your hands as these will also be heated when being soldered. Don't flick molten solder from the soldering iron or wipe the tip on brass wool type tip cleaners.

If using a hot plate for surface mount soldering do not touch the hot plate. Use utensils such as pliers to place and remove PCB's from the hotplate. If using hot air tools for soldering, de-soldering or rework, do not direct the hot air stream onto yourself or other people. If using an oven allow the PCB to cool before handling or use utensils. Don't place hot PCB's on temperature sensitive surfaces.

If burns occur they should be treated by holding under cold running water for several minutes and assistance sought if burns are severe. Incidents should be reported.

8.2 Toxic materials

Leaded solder contains lead which is a harmful material. Use of this type of solder will probably involve handling it and your skin may become contaminated by it. Although it is unlikely that the lead can be absorbed directly through your skin it may be ingested indirectly if it is transferred by handling food whilst your skin is contaminated. Always wash your hands thoroughly before eating or handling food.

Solder flux creates fumes when heated during soldering which may be harmful if inhaled. Use a fume extractor to avoid inhaling fumes.

8.3 Spattering

Solder and flux can spit or spatter when heated. Always wear eye protection (safety glasses) when soldering.

8.4 Electrical Safety

Electric soldering irons are plugin appliances and must have a current safety test tag. The test will confirm that the soldering iron conforms to electrical safety standards and has not been damaged at the time of the test. Before use you should visually check that the soldering iron does not have damage such as melted insulation on the lead, broken or cracked handle or exposed conductors. Don’t use damaged equipment and report the damage.

For electrical safety the exposed metal parts such as the tip and heating element are earthed. Don’t solder on any live equipment as contact with the earthed tip may cause damage to the equipment or soldering iron.

SMD Soldering

Information & Instructions

This is a walkthrough of a SMD Soldering Workshop. The following information and instructions can be used as a simple method for soldering SMD components. The recipient of this information should acknowledge the danger of soldering *(written on the back page of this pamphlet)* before attempting to solder.

Recommended Tools:

- Soldering Iron
- Solder
- Tweezers
- Solder Wick
- Flux Pen

① Add solder to one pad.



② While that pad is molten, slide the component into place. Do not push down from the top - slide the component into the blob of solder horizontally.



③ Align the component while connection is still molten.



④ Once you have good alignment, continue to hold the component in place, and remove your iron. Continue to hold component for 1-2 seconds while the solder joint solidifies.



⑤ From above, the alignment looked good. From the side, you can see the rear pad is hovering slightly above the PCB. This can lead to problems on multi-pin components (open connections). Be sure the component is flush up against the PCB before soldering more connections. Re-grip the component, re-heat pad 1 and push the component flush against the PCB.



⑥ This is how a tantalum capacitor should look after making both solder connections.



⑦ If alignment is not good, do not solder more than 1 pad! Re-heat the joint, re-adjust component until aligned correctly, then move on to soldering other connections.



⑧ This is bad. It would be nearly impossible to finish the connections on this part. Make sure you have the component flush against the PCB.



⑨ If you solder multiple pins together, don't worry about it! It can be easily fixed. Do not worry about jumpers! There are actually three pins under that blob.



⑩ Pull out some solder wick. Put a small amount of solder on the end of your iron (this will transfer heat from iron to wick to the jumper). Sandwich the wick in between the iron and the solder jumper.



⑪ Hold still for 2-3 seconds. You will see solder start to flow up the wick. Once the excess solder has flowed into the wick, carefully lift up the wick and your iron in one fluid motion.



⑫ Nice and clean!



⑬ Bad bad bad. There was not enough solder for the connection on the left. Middle pin is lacking solder and should have been heated for longer. Right pin has had solder applied by an iron rather than applied to two metal contacts (the board and the pin).





TIPS & TRICKS

A Solder flows smooth all the way to the bottom.

B Error: Solder balls up on top of pad, not connecting pin to pad.
Solution: Flux then wick. If you wick too much add solder.

C Error: Too little solder makes for weak connection.
Solution: Flux then add solder.

D Error: Bad Connection... and ugly... oh so ugly.
Solution: Flux then add solder.



Safety Issues

Soldering

The tip of the iron is normally 700 °F, hot enough to melt metal. It is normal for the handle of the soldering iron to heat up a bit. Hold it like a pencil and move your hand further away from the tip if the heat is uncomfortable. The solder smokes because the rosin inside the solder is burning off - it's not harmful.

sparkfun.com

RoHS COMPLIANT PB

© SparkFun Electronics, Inc. All Rights Reserved. All other trademarks contained herein are the property of their respective owners.



Soldering and Desoldering

Step-by-step instructions for making (and unmaking) the perfect solder joint.

By Joe Grand

The two key parts of soldering are good heat distribution and cleanliness of the soldering surface and component. With practice, you'll become comfortable and experienced with the process.

In this primer, I'll explain how to solder a component onto a printed circuit board (PCB). I'll also provide desoldering tips and show you how to remove a surface-mount component from a printed circuit board using a Chip Quik kit. And I'll show you how to remove a component by removing the solder in a way that won't damage the components or the circuit board.

Photography by Joe Grand

Reprinted with permission from *Hardware Hacking*, copyright 2004, Syngress Publishing, ISBN: 1-932266-83-6, pp. 34–40.

OVERVIEW

TOOLS AND TIPS

Tools of the Trade

Soldering iron You could pay as little as $10 or as much as $1,000 for a soldering iron. I recommend a fine-tip, 700°F, 50W soldering stick iron. A good general-purpose iron for hardware hacking is the Weller W60P Controlled-Output Soldering Iron, which sells for under $70.

Solder Should be thin gauge (0.032" or 0.025" diameter) 60/40 rosin core.

Desoldering tool (aka solder sucker) A manual vacuum device that pulls up hot solder, useful for removing components from circuit boards. I like the one RadioShack sells (#64-2098, $10).

IC extraction tool Helps lift integrated circuits from the board during removal/desoldering.

Chip Quik SMD Removal Kit Allows you to remove surface mount components quickly and easily. Chipquik.com offers the kit for $16.

Sandpaper A very fine-grit sandpaper is useful for removing oxidation from component and circuit board surfaces.

Desoldering braid Woven metal material used to wick up melted solder.

Small, flat-tip screwdriver Comes in handy for removing some types of components.

Needlenose pliers, wire cutters, and vise These common tools will make your job easier.

The Chip Quik SMD Removal Kit

The Chip Quik SMD Removal Kit allows you to quickly and easily remove surface-mount components such as PLCC, SOIC, TSOP, QFP, and discrete packages. The main component of the kit is a low-melting-temperature solder (requiring less than 300°F) that reduces the overall melting temperature of the solder on the SMD pads. Essentially, this enables you to just lift the part right off the PCB.

INCLUDES
- Alcohol pads for cleaning the circuit board after device removal
- A special low-melting-temperature alloy
- Standard no-clean flux
- Application syringe



Desoldering Tips

FOR STANDARD THROUGH-HOLE COMPONENTS
- First grasp the component with a pair of needlenose pliers. Heat the pad beneath the lead you intend to extract and pull gently. The lead should come out. Repeat for the other lead.
- If solder fills in behind the lead as you extract it, use a spring-loaded solder sucker to remove the excess solder.

FOR THROUGH-HOLE ICs OR MULTI-PIN PARTS
- Use a solder sucker or desoldering braid to remove excess from the hole before attempting to extract the part.
- You can use a small, flat-tip screwdriver or IC extraction tool to help loosen the device from the holes.
- Be careful to not overheat components, since they can become damaged and may fail during operation.

BEFORE YOU START



Joe Grand is the president of Grand Idea Studio, Inc. (joe@grandideastudio.com), a product-development and intellectual-property licensing firm. He specializes in embedded system design, computer security research, and inventing new concepts and technologies. He is also a host on The Discovery Channel's *Prototype This*.

SOLDERING A RESISTOR TO A CIRCUIT BOARD

BEFORE YOU START

Inspect the leads or pins for oxidation. If the metal surface is dull, sand with fine sandpaper until shiny. In addition, use the sandpaper to clean the oxidation and excess solder from the soldering iron tip to ensure maximum heat transfer.

This simple example shows the step-by-step process to solder a through-hole component to a printed circuit board (PCB). I used a piece of prototype PCB and a single resistor.

⚠ **DANGER:** **It's important to consider safety precautions. Improper handling of the soldering iron can lead to burns or other physical injuries. Wear safety goggles and other protective clothing when working with solder tools. With temperatures hovering around 700°F, the tip of the soldering iron, molten solder, and flux can quickly sear through clothing and skin. Keep all soldering equipment away from flammable materials and objects. Be sure to turn off the iron when it's not in use and store it properly in its stand.**


1


2


3



4


5



6

1. Bend and insert the component leads into the desired holes on the PCB. Flip the board to the other side. Slightly bend the lead you'll be soldering to prevent the component from falling out when the board is turned upside down.

2. To begin the actual soldering process, allow the tip of your iron to contact both the component lead and the pad on the circuit board for about 1 second before feeding solder to the connection. This will allow the surface to become hot enough for solder to flow smoothly.

3. Next, apply solder sparingly and hold the iron in place until solder has evenly coated the surface. Ensure that the solder flows all around the 2 pieces (component lead and PCB pad) that you're fastening together.

Don't put solder directly onto the hot iron tip before it has made contact with the lead or pad; doing so can cause a cold-solder joint (a common mistake that can prevent your hack from working properly). Soldering is a function of heat, and if the pieces aren't heated uniformly, solder may not spread as desired. A cold-solder joint will loosen over time and can build up corrosion.

4. When it appears that the solder has flowed properly, remove the iron from the area and wait a few seconds for the solder to cool and harden. Do not attempt to move the component during this time.

The solder joint should appear smooth and shiny, resembling the image above. If your solder joint has a dull finish, reheat the connection and add more solder.

5. Once the solder joint is in place, snip the lead to the desired length. Usually, you'll simply cut the remaining portion of the lead that isn't part of the actual solder joint. This prevents any risk of short circuits between leftover component leads on the board.

6. Here's a completed soldering example.

p050-53_SIP_SolderPrimer_F2.indd 52 10/13/10 6:33:28 AM

DESOLDERING

SMD REMOVAL WITH CHIP QUIK

BEFORE YOU START

Use a rubbing alcohol pad to remove any residue from the solder pads. Verify that the solder pads are clean and free of cuts or solder jumps before proceeding. Desoldering, or removing a soldered component from a circuit board, is typically trickier than soldering because you can easily damage the device, the circuit board, or surrounding components. For surface mount devices (SMDs) with more than a few pins, the easiest method to remove the part is the Chip Quik SMD Removal Kit, as shown in the following step-by-step example.

PLEASE READ through this example completely before attempting SMD removal on an actual device. When removing the device, be careful not to scratch or damage any of the surrounding components or pull up any PCB traces.

THREE PRIMARY FUNCTIONS OF FLUX

- **Cleans metal surfaces to assist the flow of *filler metals* (solder) over *base metals* (device pins).**
- **Assists with heat transfer from heat source (soldering iron) to metal surface (device pins).**
- **Helps in the removal of *surface metal oxides* (created by oxygen in the air when the metal reaches high temperatures).**


1


2


3


4


5


6

1. The first step is to assemble the syringe, which contains the no-clean flux. Simply insert the plunger into the syringe and push down to dispense the compound. The flux should be applied evenly across all the pins on the package you'll be removing. (Flux is a chemical compound used to assist in the soldering or removal of electronic components or other metals.)

2. Once the flux is evenly spread over the pins of the target device, the next step is to apply the special Chip Quik alloy to the device. This step is just like soldering: apply heat to the pins of the device and the alloy at the same time. The alloy has a melting point of approximately 300°F, which is quite low. You shouldn't have to heat the alloy with the soldering iron for very long before it begins to melt. The molten alloy should flow around and under the device pins. Starting at one end of the device, simply heat and apply the alloy. Repeat for the other side(s) of the device.

3. Flux will help ensure a nice flow of the alloy onto the device pins. Make sure the alloy has come in contact with every single pin by gently moving the soldering iron around the edges of the device. Avoid touching nearby components on the PCB with the soldering iron.

4. Now that the alloy has been properly applied to all pins of the device, it's time to remove the device from the board. After making sure that the alloy is still molten by reheating all of it with the soldering iron, gently slide the component off the board. You can use a small, jeweler's flat-tip screwdriver to help with the task. If the device is stuck, reheat the alloy and wiggle the part back and forth to help the alloy flow underneath the pads of the device and loosen the connections.

5. The final step in the desoldering process is to clean the circuit board. This step is important because it will remove any impurities left behind from the Chip Quik kit and get you ready for the next step.

First, use the soldering iron to remove any stray alloy left on the device pads or anywhere else on the circuit board. Next, apply a thin, even layer of flux to all of the pads that the device was just soldered to. Use the included alcohol swab or a flux-remover spray to remove the flux and clean the area.

6. The desoldering process is now complete. The surface-mount device has been removed and the circuit board cleaned.

TECHNOLOGY IN ACTION™

Building Your Own Electronics Lab

A Guide to Setting Up Your Own Gadget Workshop

Dale Wheat

For your convenience Apress has placed some of the front matter material after the index. Please use the Bookmarks and Contents at a Glance links to access them.

friendsof™

Apress®

Contents at a Glance

■ About the Author xi
■ About the Technical Reviewer xii
■ Acknowledgments xiii
■ Introduction xiv
■ Chapter 1: Planning Your Electronics Workshop 1
■ Chapter 2: Building Your Tool Chest 19
■ Chapter 3: Components 57
■ Chapter 4: A Portable Mini-Lab 87
■ Chapter 5: The Cozy Corner Lab 105
■ Chapter 6: The Small Group Lab and Classroom 135
■ Appendix A: Getting Started with Tool Building 145
■ Index 161

Introduction

We're surrounded by electronics these days. Did you ever wonder how it all worked? Do you know just enough about electricity to be dangerous? Would you like to learn more? Then this book is for you.

There are many excellent textbooks on how electricity works. This is not one of them. This book helps you get started learning about electricity and electronics by showing you how to set up your own electronics laboratory. You might have guessed that from the title.

Along the way, several simple exercises are presented to show you some basic concepts about how electricity works in the real world—not just in a lecture hall. By the time you get done reading this short book, you'll have a good idea of where to begin and what kinds of tools and components you might need, and you'll have some excellent advice about how to keep it all organized.

Once you've got your own space set up to perform your electronic experiments, the sky is the limit.

Here's what you have to look forward to in this book, one chapter at a time.

Chapter 1: Planning Your Electronics Workshop

Your very own electronics laboratory is a great place to build, repair, invent, and learn more about electronics. We seem to be surrounded by electronics more and more every day. We can easily become dependent upon them, without even understanding how they work. Having your own electronics lab can help you gain some control over your electronic minions. Here you can learn about their inner mysteries, including how to repair them when possible or, better yet, improve them with your own custom modifications. You can also turn your own ideas into reality by building electronic circuits from scratch.

What will you need to plan your lab? What if you already have a basic understanding of electronics and the beginnings of a workshop at your disposal? This chapter helps get you going in the right direction.

Chapter 2: Building Your Tool Chest

You're going to need some tools in your lab, as well as the skills to use them effectively. This chapter will get you started.

If you're starting from scratch, don't worry. There's not a whole lot you absolutely *must* have to get started. Some basic hand tools and a place to keep them organized is all you will need. You don't even have to spend a lot of money at first. As you progress in your hobby, you will most likely want to add to your tool chest and upgrade some of those tools. Electronics can be the perfect hobby because it can take up (1) all your spare time and (2) all your discretionary income. What more could you ask for?

Chapter 3: Components

You're going to need some components to play with, as well as the knowledge to use them effectively. This chapter will introduce you to some of the bits and pieces that make up modern electric and electronic circuits. You'll also learn a little bit about how to identify components from their appearance and markings, when available.

Once you've got an idea about what these parts do in a circuit, you'll learn a little more about how to measure their electrical properties and put them to use. You'll also be shown what *not* to do, in some select examples.

Chapter 4: A Portable Mini-Lab

Having a portable (or at least (*trans*portable) electronics lab comes in handy in several circumstances. Maybe you don't have a place (yet) for a permanent home for all that equipment. Maybe you need to bounce at a moment's notice, heading off on electronic adventures at the drop of a hat. Or maybe you like to keep everything where you can find it in a hurry, without having to rummage through shelves and boxes, looking for just the right tool or component.

Whatever your motivation for wanting a portable lab at your disposal, this chapter should help you get started.

Chapter 5: The Cozy Corner Lab

You don't need an entire garage or extra office for a functional laboratory for your electronic endeavors. It's certainly nice if these areas are available to you, but you might be surprised at how much you can do in just a small space, if you set it up properly and maintain it with determination.

Chapter 6: The Small Group Lab and Classroom

The first part of this book deals with how to get along with electrons and make them do your bidding. In this chapter, you'll explore a completely different topic: other people, and how to get along with them.

You might not ever figure out how to get *them* to do your bidding, but at least you can keep them from stealing your tools. Maybe.

Appendix A: Getting Started with Tool Building

Once you've become comfortable in your lab and had time to play with a few circuits, you might start to notice that some of the "tools" you've been using are just simple electronic circuits themselves. Good examples are power supplies and meters. These are great tool-building projects because you can see useful results early.

This appendix takes a look at building a couple of simple electronic tools that might be of use in your lab. Hopefully you will develop a better understanding of how these tools work. Ideally, you will progress from the basic question of "Does it work?" to the more involved questions of "How well does it work and what can I do to improve it?"

CHAPTER 1

Planning Your Electronics Workshop

Are you interested in electronics? Would you like to set up your own “electro lab” to conduct amazing experiments, build crazy gizmos, and repair or modify your existing electronics? Then this book is for you!

Your very own electronics laboratory is a great place to build, repair, invent, and learn more about electronics. We seem to be surrounded by electronics more and more every day. We can easily become dependent upon them, without even understanding how they work. Having your own electronics lab can help you gain some control over your electronic minions. Here you can learn about their inner mysteries, including how to repair them when possible or, better yet, improve them with your own custom modifications. You can also turn your own ideas into reality by building electronic circuits from scratch.

What will you need to plan your lab? What if you already have a basic understanding of electronics and the beginnings of a workshop at your disposal? This chapter helps get you going in the right direction.

What to Expect

This book can’t teach you everything about electronics, and it doesn’t try. That would take several lifetimes. What it can do is introduce you to the tools and the skills you will need to set up your own electronics lab. This will include a very basic introduction to electricity, a little bit of theory, some safety tips, and a whole lot of example projects. It’s a great starting place. Where it will lead you is mostly determined by you and what you’re wanting to do with electronics.

If you’re already familiar with electricity and electronic concepts, there is still plenty of fun and interesting stuff waiting for you to explore. The field of electronics itself is constantly expanding. From the time this book was written to the time that you’ve finished reading this sentence, many advances will have occurred in both our understanding of electronics as well as the development of new applications and electronic devices. This is one of the many things that makes the study of electronics so interesting and exciting.

Every lab is different. Your lab will reflect not only your immediate electronics goals but also your personality. Feel free to pick and choose from all the ideas presented in this book and add in some of your own. The repair shop and the design studio are necessarily going to be arranged differently. There really is no right or wrong way to go.

Even the best laid plans, so the saying goes, end up somewhere unexpected. When planning your electronics lab for the first time, or for the tenth time, keep in mind that your interests, resources, and reasons for wanting to work on electronics are going to change over time. Please feel free to reinvent yourself and your lab as conditions permit. You might also be forced to reconsider your priorities when other factors in your life exert themselves. That being said, stay tuned for "A Cautionary Tale" at the end of this chapter.

Some configurations are more appropriate for certain endeavors, and nothing replaces the right tool for the job. This book should at least give you an idea of what is involved and get you pointed down the right road.

It Starts with a Plan

Most of the decisions you'll make when planning your laboratory will depend on what *you're* interested in doing there. Having a good plan at the beginning is like having a clear map when taking a long journey. It helps you from getting lost and also is handy for figuring out when you've arrived.

■ **Note** If you fail to plan, you plan to fail.

Remember, at this point in the game, you don't have to make any final decisions about what you want to be able to do in your lab. This book is all about illustrating possibilities and giving you the information and advice necessary to branch out into the areas that hold the most interest for *you*.

A Broad Outline

Here's what you need to get started: a little time, a small amount of space, some basic tools, and a few components. Those are the boring parts. The fun stuff includes your ideas, goals, and inspiration. Combine all that with some fundamental information about how electricity and electronics work, and you're in business.

A Little Time

Like any good hobby, setting up your electronics lab and conducting experiments there is going to take up some of your time. For some, this is the *main reason* for getting started in electronics and building a lab: a place to escape, unwind, and tinker with ideas, prototypes, and complex systems. Maybe it's your job. Maybe it's your passion. Perhaps it's a bit of both.

You're going to need time to plan and build your lab. This book will spell out several specific arrangements for various-sized labs, but they are just examples and not hard-and-fast rules. More time will be required for obtaining the proper tools and materials that you will use there. Time will be spent not only *doing* things in your lab, but also in just *thinking* about doing things in your lab. For example, you might build a clever little gizmo that ought to do a simple task, only to find out that it refuses to work. You might need to spend a little bit of time thinking of ways of testing it to find out where the problem lies. This is sometimes called *troubleshooting* or *debugging*.

This is the basis of the scientific method. To help understand how something works, you first form a theory that would explain its behavior. Next you prepare one or more experiments that will demonstrate the accuracy of your theory. The experiments are conducted and their results are analyzed. If the results are in agreement with your theory's predictions, then your theory is more than likely correct. If not, you may need to modify or extend your theory to accommodate the behavior observed. All of these things take time, which helps explain why we don't have jet packs or time machines yet.

A Little Space

You don't have to start out with a cavernous underground bunker for your electronics lab. If you already have one, that's great. You might have an extra classroom available, some unused warehouse space, or an empty bench in a garage.

Then again, you might only have a corner of the dining-room table, and then only between mealtimes. That's plenty of room when you're just getting started! Once you learn more about electronics, and especially when you learn more about what it is that *you* want to do with electronics, then you can start looking for a more permanent home for your toys, tools, and spare parts.

The main points that will be stressed throughout this book when planning and working in your space are safety, good lighting, and organization, in that order.

- Your lab needs to be relatively safe for you, and *very* safe for your visitors and neighbors. The "Go Away!" sign on the door does not guarantee that you will be free from curious visitors, pesky and otherwise. People are naturally attracted to the creative and mysterious activities going on in your lab.
- Be prepared to buy, build, or borrow more lighting, because you're going to need it. Proper lighting improves the quality of your doodlings and tinkering enormously. You might think you already have enough light, and unless you were a photographer in a previous life, you don't. (Photographers understand that you can never have too much light.)
- An organized lab is a productive lab. Don't waste time looking for parts or tools when it would have only taken mere moments to put them in their proper places in the first place. A place for everything, and everything in its place. You get to decide where all these tools and bits get to live, so spend some time and do it wisely.

These three tenets will be repeated throughout the book, so you might as well get used to hearing about them.

Basic Tools

You really don't need a lot of tools to get started. There is a tendency to want to be a bit overprepared before tackling any new project, but it really isn't necessary when it comes to planning and building a new electronics lab. This is also true when sorting out a lab that's gone badly out of control.

You're going to be working with wire quite often. Claude Debussy has been quoted as saying that music is the space between the notes. It's the connections between the various electronic components that make the magic happen in an electronic circuit, in the same way that it's the relationships between people that make their lives so interesting.

The connections between all the various imaginable electronic components almost always start out as bits of wire. These connections can then be optimized into copper traces etched on a printed circuit board or even as metallization links in an integrated circuit. You're going to be working with a lot of wires in this hobby, and that usually boils down to two basic hand tools: *wire cutters* and *wire strippers*.

A wire cutter does what it says and says what it does: it cuts wire. A wire stripper is a more specialized tool that helps remove the outer layer of insulation from a wire. Ever more specialized versions of both tools abound. Some tools aim to perform both tasks at once, while never perfecting the art of either.

Resist the temptation to use your teeth for cutting and stripping wire. If you're caught in a situation without proper tools, use your fingernails. They grow back faster than teeth.

■ **Tip** Use the right tool for the job. Knowing which tool is the right tool is half the battle.

If you're performing detailed work on smaller circuits, you might benefit from having some small needle-nosed pliers, a small vise, clip, or helping-hands jig, and possibly a magnifying glass.

A popular and handy skill in the electronic arena is *soldering*. Soldering is the process of making electrical and mechanical connections. This is done by heating the items to be joined together and adding solder. The solder melts and fills in all the gaps between the items being joined. Once cooled, the solder forms a solid, conductive link.

■ **Note** Soldering is similar to welding, with the exception that welding actually melts the parts being joined.

A suitably sized soldering iron and the right kind of solder are indispensible for many projects, including repair, prototyping, and production. Picking up the skill to make quality connections is obtained in the same way as all worthwhile skills: with lots of practice.

Besides these basic fabrication tools, you will also want some *test and measurement equipment*. These are devices used to measure various aspects of electrical circuit behavior. These range from the very simple, such as voltage meters, current meters, and continuity testers, to the very exotic (and sometimes expensive), which include oscilloscopes and various logic, network, and signal analyzers. See the Appendix for information about building your own simple test equipment for your lab.

This is just a quick summary of the kinds of tools you might want in your electronics lab. Chapter 2 goes into much more detail about the tools you will probably need or want in your lab, as well as the skills needed to operate them safely and effectively.

Fundamental Components

As mentioned in the previous section, you're more than likely going to be wiring up various contraptions and rewiring others. This is probably going to involve a lot of wire.

For small voltages and currents, small-gauge insulated copper wire is often used. It's easy to handle, cut, and splice. This can be done with mechanical connectors such as wire-nuts or screw terminals, as well as with soldering.

Back in the day when computers were all connected using fat cables, lots of tiny wires were bundled up into cables and snaked all over a typical desktop computer installation. With the increasing popularity of wireless devices, those fat, juicy cables are lying around, discarded, unwanted, and just waiting to be harvested for their valuable conductors. You can also buy various kinds of wire in all colors and sizes from most hardware stores and from online suppliers.

Now consider the types of projects you'll be working on:

- If you're most interested in building your own lighting, you're going to want some lightbulbs, sockets, and LEDs, or whatever lighting technology appeals most to you. Don't forget that you're also going to need switches, knobs, dimmers, housings, plugs, and *more wire*.

- If you like to work with things that move, you're going to need motors, relays, solenoids, servos, and fans. You'll probably be needing some gears, pulleys, chains, belts, shafts, and couplings, along with connectors, switches, controllers, position sensors, and *more wire*.
- If you're into making lots and lots of sound, you'll be needing speakers, headphones, microphones, pickups, transducers, transformers, amplifiers, connectors, jacks, plugs, and, you guessed it, *more wire*.
- Are computers and digital devices more to your liking? Be thinking about getting yourself a wide variety of chips, microcontrollers, software, cables, sockets, connectors, and still *more wire*.

Now you've got an idea of some of the different components you might want to have on hand, depending on what kind of inspiration happens to strike. You're going to need a place to keep all these different parts sorted. This will play a big part in the overall planning phase of your lab. Maybe your old fishing tackle box has enough room for your basic hand tools and enough secret compartments to hold an interesting variety of components. On the other end of the spectrum, maybe you need to start thinking about some industrial-grade shelving units or pallet racks. Now is the time to think about all these factors and start making the right kind of plans to help make your lab a successful one.

Again, this is just a quick summary of some of the types of components you might want to work on in your lab. Chapter 3 is going to take you much farther into understanding many of the more common electrical and electronic components that you are likely to encounter in your lab.

Ideas

Admit it: you've already got some ideas for cool projects that you'd like to be working on in your own electronics lab. That's great! You're well on your way to making those dreams a reality.

The best possible thing you could do with your ideas is to write them down somewhere. It can be as simple as a sketch on a piece of scrap paper or as formal as a complete set of project documentation. The important thing is that you actually get the idea across using either words or pictures in a form that you will be able to revisit in the future. This will be of immense benefit to you, as well as anyone else that might be interested in your ideas.

It's also a great idea to keep a log as you work on your projects. That's the perfect place to jot down those ideas as they come popping out of your brain. Be as detailed as you can be. You will thank yourself later.

Even if you don't already have a backlog of ideas jostling for your attention in the lab, it's still a good idea to keep a log and explore the things that interest you. Leonardo da Vinci kept detailed notebooks on almost every possible subject. Anything that interested him got written down, sketched, or diagrammed in his notes. Even today, people are still getting inspiration from his doodles (see Figure 1-1).



***Figure 1-1.** Sketches and notes for a "flying machine" by Leonardo da Vinci. Photograph by Arnaud 25 (public domain), via Wikimedia Commons.*

Writing down your ideas also helps you pick which projects you want to work on first. It just isn't possible to work on all of them at the same time! Narrowing down the list helps get you focused and lets you concentrate all of your talents and energies on the most important projects.

When you're just beginning, the "most important projects" are the ones that provide the most positive reinforcement in the shortest amount of time. Plan a few simple, straightforward projects with a high probability of success at first. You can become more ambitious and take greater risks when you've built up a good reserve of self-confidence and techniques. Remember, the only experiments that fail are the ones from which you don't learn anything. Sometimes learning how *not* to do something is just as important as learning how to do it correctly.

Goals

The best way to turn great ideas into spectacular projects is to have a plan. Set some achievable goals for yourself. When you're first starting, don't be afraid to take those baby steps. You have to crawl before you can teleport.

Project planning is its own art form, and a dark and mysterious art it can be sometimes. It really helps to have clearly defined goals and expectations early in a project. Otherwise, how will you know when you're finished?

Any large, complex problem or project can be broken down into smaller, more manageable subprojects. Unfortunately, this can be carried too far. You don't need to reinvent the wheel every time you start a new project. There's a saying that suggests, "Don't build anything you can buy." The counterpoint to this wisdom is the equally ancient saying, "Don't buy what you can build." You'll have to be the judge as to which one applies best to you and your situation.

Do you have lots of time and very little money? This is good news! This helps simplify the decision-making process enormously. Design and build everything yourself, from scratch. This can include your own tools as well as custom-made components. The trick to this approach is not get lost in all the inevitable details that will arise.

No time to spare, but there's a bit of a budget available? This is likewise good news. With few exceptions, there's someone out there that's willing to part with just what you need for a reasonable price. The trick here is to find them and make that connection.

Inspiration!

Remind yourself what your inspiration is. What initially prompted you to start thinking about building your own electronics lab? Why did you want to get into electronics as a hobby or a career in the first place? Do you even remember?

It really helps to have a firm grasp on what your underlying motives are (or were) when faced with the challenges that regularly present themselves along the way. While it's true that some things just need doing, does it really have to be *you* that does them? Could you farm out some of the work and still feel a sense of satisfaction in the completion of the project? Or do you feel the need to take the do-it-yourself mind frame to its utmost limit?

Whatever your inspiration is, or wherever it came from, do your best to keep it in your sights while pursuing your dreams and goals. It makes it that much more satisfying when you eventually attain them.

How Electricity Works

There are two ways to go about learning how electricity actually works. The first involves just a whole bunch of *fascinating* theoretical information about atoms, electrons, fairies, and dragons. The second way is to just assume that it does indeed work, and spend some time actually putting it to work.

You don't need to know everything about electricity to have fun with it. A passing understanding is sufficient to get you started. As your technical requirements grow more elaborate, you will find yourself going back to revisit some of the basic concepts, until your comprehension is sufficient to carry you forward.

The Theoretical Approach

The prevailing theories about how electricity works center around the orbits of negatively charged subatomic particles called *electrons*. Electrons are quite small, even when compared to individual atoms. Electrons normally whiz around the *nucleus* of the atom, which is usually made up of other subatomic particles called *protons* and *neutrons*. The exception is hydrogen, whose most common isotope has only a single proton and no neutrons. Protons have a positive electrical charge and neutrons have no electrical charge.

When an atom has a balance of protons and electrons, it is said to be electrically neutral. If an atom has more electrons than protons, it has a negative electrical charge. Conversely, if there are more protons than electrons, the atom has a positive charge. An atom that has either a positive or negative electrical charge is called an *ion*.

While flying round and round the nucleus, electrons tend to cluster into well-defined orbits, or *shells*. The innermost shell of an atom can hold as many as 2 electrons. Once this orbit is "full," up to 8 more electrons can be accommodated in the next larger shell. The next shell holds up to 18 electrons, and the one after that can contain up to 32 electrons. After that, the shells get smaller again, stepping back down symmetrically from 18 to 8 to 2.

Each unique combination of electrons and protons represents one of the chemically distinct *elements*. Each element has its own particular chemical characteristics, and cannot be further subdivided by conventional chemical or mechanical means. Toward the end of the *periodic table*, which arranges all the known elements into meaningful rows and columns, you'll start to find some exceptions to the shell symmetry. These heavier elements, however, don't usually turn up in most electronics labs, so we'll not be spending a lot of time there.

Individual atoms can combine into more complex structures called *molecules*. One popular molecule is water, which is made up of two hydrogen atoms and one oxygen atom. Each of the hydrogen atoms has a single electron. The oxygen atom has eight electrons. The first two electrons in the oxygen atom occupy the first shell, leaving six electrons in the next outer shell. That leaves two "open" places in the second shell, which is where the two electrons from the two hydrogen atoms come into play. The electrons are shared by the three atoms, linking them all together and forming a *covalent bond*. Water has vastly different physical properties than either hydrogen or oxygen.

It's also possible to bump an electron out of orbit around a nucleus. When this happens, the atom becomes an ion and is electrically positive. This makes it especially attractive to any loose electrons that happen to be in the vicinity. This is because electrons are negatively charged, and in the case of electrical charges, opposites attract. This movement of electrons is how an electric charge flows through a substance.

Some materials are very good at slinging those electrons around, and as such are called good *conductors* of electrical energy. Examples of good conductors are copper and silver. Some materials resist the flow of electrical charge, and can be used as *insulators*.

An important concept to understand about the flow of electricity is that it is based on the movements of tiny, *negatively charged particles*. This is referred to as the flow of *electron current*, but this term is rarely used. For some reason, the more popular, or conventional, idea of electric current flow is from the more positive point to the more negative point in a circuit. This is referred to as *conventional current* and is the standard used throughout this book.

The fairies and the dragons come into the picture when you start to look any deeper into how the building blocks of matter are actually (or allegedly) constituted. The previous quick summary of how electricity works covers less than 1 percent of the physics needed to understand even how basic atomic principles operate. Even then there are various schools of thought as to how, *exactly*, all that tiny stuff works together to produce rainbows and cousins and moon rocks. A proton, once thought to be an indivisible *elementary particle*, is now thought to be built out of a "down" quark and two "up" quarks. There are also "strange" and "charmed" quarks flitting about, along with an entire pantheon of mythological particles. Go figure.

Now all of that *fascinating* information only scratched the surface of how *electricity* works. Electricity does a lot of work for us. We use it for lighting, heating, motion; just all kinds of things. *Electronics* is where we start to get into some really bizarre physics involving semiconductors, transistors, computer chips, and other miracles of the modern age. Explaining even the basic ideas about how *electronics* works is way beyond the scope of this little book. It's certainly possible to learn and understand it, but for the purposes of setting up a lab and building some example projects, we can just assume that it does indeed work. We can start from there and have some fun with it.

If your curious mind just can't stand *not knowing* how electronics works, the interwebs are your friends, and so are the helpful folks at your local library.

A Practical Approach

An easier way to think about electricity is to skip over *why* it flows and concentrate on *how* it flows. That's what we'll be doing in the remainder of this book, for the most part.

■ **Note** Electricity flows in a circle.

Any continuous flow of electrical current travels in a circle. There are exceptions to this broad generalization, but most of the example circuits encountered in this book will have a definite circular arrangement, if you know how to look for it.

Here are some technical terms that will be used throughout this book. You don't have to memorize any of them right now (there will *not* be a test), but you should at least take a glance at them so you know where to come back when you want to know more.

> *Circuit*: A circuit is anything that forms a continuous loop or circle. The term *circuit* is formed from the same Latin word that means *circle* or *wheel.*
>
> *Amps*: The *intensity* of an electrical current is measured in units called *amperes*, named after André-Marie Ampère. This is usually shortened to *amp* in popular usage. The symbol for amperage in a circuit is *I* (for intensity), while the unit is abbreviated *A*. For example, you could say that the intensity of the electrical current (I) in a circuit was measured to be 3.75A (amperes). Electrical current is measured with an *ammeter*.
>
> *Volts*: The voltage in a circuit is the measure of the difference in electrical *potential*, or how much work it *could* do. The unit of voltage is the volt (V), named after Alessandro Volta. This is sometimes referred to as pressure or tension. For example, a "high-tension wire" means a high-voltage line, not necessarily one that has been pulled really, really tight. Voltage is, not surprisingly, measured with a *voltmeter*.
>
> *Watts*: Electrical power is measured in watts (W), named after James Watt. The easy way to calculate watts, or the amount of energy that is converted into work (either useful or not) is to multiply the voltage across the circuit by the current flowing through the circuit. For example, if a 12V battery is connected to a lightbulb that draws 2A, the bulb converts the electrical energy into both light and heat (mostly heat) to the tune of 24W (12V × 2A = 24W).
>
> *Ohms*: The resistance to the flow of electrical current is measured in *ohms*, named after Georg Ohm. A *resistor* is a simple electronic component that exhibits a fixed resistance to the flow of electrical current. The symbol for resistance is *R* and the unit of measure is the capital Greek letter omega, Ω.

Safety

Make no mistake: electricity can kill you. It bears repeating, as well as emphasis.

■ **Warning** Electricity can kill you.

Working safely with electricity is like working safely with a sharp knife, for example. A good knife is a useful tool. Life would be cumbersome and crude (not to mention short) without good tools. However, when using *any* tools it's important to understand their proper use and operation. The same goes for electricity.

The point here is not to be overdramatic about the dangers of electricity. Billions of people are safely and peacefully coexisting with electricity, largely due to wise safety rules and well-designed electrical appliances. However, there are three major ways that you can be harmed when working around electricity, and it is important that you be aware of them:

- Your body uses tiny amounts of electricity to send nerve impulses to and from your brain. Sending relatively giant shocks of electricity through your body is a good way to stop your heart from beating or your lungs from breathing. You need to keep doing both of those things, so be careful.
- Since your body is not a very good conductor of electricity, it converts the electrical current into heat, which can produce very damaging burns, both on the inside and the outside of your body.
- Additionally, many electrically related injuries are sustained while trying to *get away* (i.e., your body's involuntary reflex when exposed to dangerous voltages).

Yet working safely with electricity is easy. Observe the following rules and you'll be relatively safe, both in your lab and outside of it:

- Always assume a circuit is "live." Electrical devices can retain lethal voltages even when completely disconnected from power.
- Don't work with high voltage (more than 36 volts) unless you're specifically trained. Reading this book does *not* mean you're "specifically trained," even if you read it *twice*.
- Don't short-circuit batteries (i.e., deliberately connect the positive and negative terminals together). Even very small batteries can hold dangerous amounts of power and can produce enough heat to burn you. Even worse, it can start a fire, which is yet another unpleasant way to die.
- Be careful when using metal (conductive) tools around battery terminals so that you don't accidentally short the terminals together or to other circuitry.
- Don't assume other people are aware of these dangers.

Lighten Up!

Now it's time to have a little fun with electricity, don't you think? While it's important to keep safety in mind, it's just as important to be curious and willing to try new things. Don't let the (important) safety rules immobilize your creativity. Use these rules, like any tool, to leverage your enjoyment of this fun and exciting hobby.

Let's start with a simple circuit that is almost guaranteed to lighten things up. Let's take apart a flashlight (or *torch* for you metric types) and see how it works.

First, find a typical household flashlight. The flashlight in Figure 1-2 was purchased for $3, and it included two new D-cell batteries. Put the batteries in the flashlight and make sure it lights up when you turn on the switch. If the bulb is burned out or the batteries are dead, then this experiment is not going to be much fun at all.

DORCY
Frost Brite
ClearView Design
TrueSpot Reflector
Modèle transparent
Réflecteur TrueSpot
DORCY
HEAVY DUTY

Figure 1-2. *A typical household flashlight will be the ~~victim~~ subject of our first electrical experiment.*

Once we've established that the flashlight works as intended, we can begin the experiment.

DISSECTING A FLASHLIGHT

We don't need most of the pieces of the flashlight body. Let's take it apart and have a look inside.

1. Open the flashlight be unscrewing the end with the lightbulb in it.
2. Remove the batteries. Set them aside for the moment. We'll use them in a bit.
3. Remove the plastic retainer that holds the bulb in the reflector.
4. Take out the bulb.
5. We'll need to replace the wiring that was contained within the flashlight's body. Find a short piece of wire 8" to 12" long. A specialized jumper wire with alligator clips on the end was used in the photos for this exercise, but almost any kind of wire will do. See Figure 1-3.



Figure 1-3. *All the pieces you'll need to light up the bulb.*

6. If you're using plain, insulated wire, you'll need to remove a small bit of it from both ends of the wire to expose the *conductor*, or metal wire part inside.
7. This step can be tricky. Try to hold both batteries in one hand, along with the bulb. The batteries need to be pointed in the same direction. If this is too hard to do, try it with just one battery.

8. The positive end of the battery has a small cap on it. Touch the bottom point of the bulb to the top of the battery.
9. Now, using your other hand, connect the wire from the bottom of the battery to the metal base of the bulb.
10. The lightbulb should start to glow. See Figure 1-4.

■ **Caution** If you have a super-bright bulb, it can get hot. Don't burn yourself!



Figure 1-4. *The completed circuit, showing the glowing bulb. Electricity is flowing!*

Several important things are going on in this very simple circuit. Electrical current is flowing, producing useful work (in this case, light). Can you see the "circle"? When you *break* the circuit, the bulb stops glowing. This is exactly how the switch in the flashlight body works. Peek inside the flashlight and see if you can tell how it works. By connecting and disconnecting the wire, you can make the bulb flash. If you only use one battery, the bulb turns on, but is not as bright. Why do you think that happens?

Environmental Impact

You affect your environment every day, and your environment affects you, as well. As you learn more about electronics and all the interesting and wonderful things it can teach you, be mindful of what kind of trail you're leaving behind for others to clean up.

A good way to get a feel for your environmental impact is to take a look at your garbage. It doesn't sound that interesting or fun, but it *will* teach you a lot about yourself and your habits. What are you throwing away? Could you have found either another use for it, or perhaps another home? Is it going to be a nuisance to someone else, or even worse, a hazard?

A good example is the use of "disposable" batteries. We used batteries (technically *cells*, but that distinction will be spelled out in more detail in Chapter 3) in our very first experiment. We buy new batteries and plug them into our devices, and when they run out of power we take them out and throw them away. Where do they go? How do they then interact with the environment? They don't just "go away."

Disposable batteries are very convenient. They are generally inexpensive, compact, self-contained, and reliable. This *convenience*, however, comes with a price all its own. Consider using *rechargeable* batteries whenever possible in your lab. They cost a little more than their disposable counterparts, but can easily and cheaply be refilled with electrical goodness over and over again.

You should also be aware of any hazardous materials that you use or store in your lab. For example, lead is a very common material used in many electrical devices, even though its use is being reduced worldwide. It is found in older-technology rechargeable batteries, solder, and printed circuit boards.

Some of the chemicals used to etch printed circuit boards can be dangerous if not used, stored, and disposed of properly. Take the time to understand what, exactly, you're working with when you're conducting your experiments in your laboratory.

Just like the captain of a seagoing vessel, you're in charge of what happens in *your* lab. With this authority come important responsibilities that rest squarely upon your shoulders. Please take these responsibilities seriously.

Budgeting

How much is all this stuff going to cost? A lot of it depends on how creative you want to be in stocking your lab with tools and parts.

If your budget is small, then start small. If your budget is nonexistent, then you'll just have to start even smaller. You should generally approach acquisitions for your lab under one of these three headings:

- Buying new
- Finding used
- Harvesting or recycling

Buying New

Buying everything new is obviously the most expensive approach, at least from the *money* side of it. What a lot of people fail to take into account is that their *time* is also a very valuable commodity. Try to balance the one with the other, as befits your particular situation.

Except for the folks in the most *dreadful* of hurries, it always makes sense to shop around for the tools, equipment, and components that you are going to need in your lab. You'll find that a lot of "professional-grade" equipment carries an enormous price premium compared with "consumer-" or "hobby-grade" alternatives. This is generally to be blamed on the fact that there is a correspondingly enormous amount of money to be made in the field of electronics.

New components are almost always more desirable to use, especially when you're looking at a production environment and you need to make sure everything produced is of the highest possible quality and reliability. New, unused components are also more appropriate when conducting complex experiments, as this helps to reduce, if not eliminate, many variables in the testing and analysis phases. You don't have to worry that someone (probably you) might have "borrowed" some parts for a quick fix or some other temporary usage and then surreptitiously replaced them back in inventory, having possibly compromised them in some unseen way.

Finding Used

A prudent way to fill up a new lab, especially when first starting out, is to look for bargains on used tools and components. This is especially true of the fixtures, shelves, cabinets, benches, and other furniture that belongs in a lab.

Tools wear out. Tools are replaced. This is a fact of life when you're in the business of working with tools. The good news is that "one man's trash is another man's treasure." If we consider the possibility of women participating, we get three more potential combinations, all of which can end up in a win-win situation.

Many used tools can be retrofitted and placed back into service in your lab. On the other hand, there are a lot of tools that are simply used up and can not feasibly be brought back into useful service. Either their repair is cost prohibitive or they are no longer supported by their original manufacturers.

Another factor working in favor of the patient and observant collector of discarded tools is the inevitable march of progress. What was shiny and top-of-the-line a year ago might be intolerable or insufficient next year, from the standpoint of the original purchaser. Many bargain opportunities arise from this simple understanding.

This can sometimes be applied to the purchase of components that have never been used, but have been sitting somewhere waiting for their chance. A commonly used phrase to describe these parts, which are often sold at a discount, is *new old stock (NOS)*. Sometimes these parts are sold this way because of overstock or because a manufacturing run was cancelled or cut short.

Harvesting or Recycling

There's an absurdly large amount of perfectly good equipment, tooling, fixtures, and components sitting out there, looking for a new home. A lot of companies, as well as individuals, either outgrow their present fittings or turn toward other interests and endeavors. This can be an excellent opportunity to acquire the furnishings you need to populate your lab.

On the other hand, please don't go crazy. You don't have to pick up every discarded appliance or chair you see sitting by the roadside. Why pay rent for something you can easily and cheaply obtain when you actually need it? Are you really wanting to pay the heating and air-conditioning bill for that box full of odd-sized capacitors that are probably past their prime? Don't fall into the trap of the *false economy* when it comes to bargain-hunting for your lab. The most important ingredient in your lab is *you*. Leave a little room to move around a bit.

Another factor to keep in mind is *shelf life*. Not all parts (or tools) last forever, especially when not being used. Batteries are the worst. You can prolong the shelf life of nonrechargeable batteries by storing them in your refrigerator, as this slows down the electrochemical processes within them that produce the electricity. Even solar panels will wear out with either constant use or constant disuse, although this can take years to happen.

Some Example Workshops

Here's a little peek into some actual electronic laboratories, each with its own personality and history. Each one grew from something small into something, well, not so small.

A Fresh Start

Harold Timmis is an electronic engineer, software developer, and author. His curiosity about how things worked started as a small child, which led him from taking apart everything in his parents' house to studying engineering at the Florida Institute of Technology.

Harold keeps a lab in his home where he can work on gadgets in his spare time. Harold recently moved, and used the opportunity to "clean house" and set up everything in his lab exactly the way he wanted things.

He took this photo of his new lab after working on a couple of projects (see Figure 1-5). Note that everything is within easy reach when sitting at the desk. It's still quite tidy, as you can see.



Figure 1-5. *The reorganized home lab of Harold Timmis (photo by Harold Timmis)*

The Robot Clubhouse

The Dallas Personal Robotics Group (`http://dprg.org`) is the world's oldest personal robotics group known to man. From 2002 to 2009, Mike Dodson of Modern Assemblies donated the use of a portion of one of his warehouses to DPRG. This gave DPRG a permanent home for meetings, contests, and social gatherings.

Robot builders enjoyed a spacious and comfortable area for working on robot projects, among other pursuits. Over the years, members contributed time, equipment, and lots of hard work to improving the space. The photo in Figure 1-6 shows one end of the available space, after an extensive remodeling. Several workstations along the wall are in the process of being set up. That good-looking fellow seated at the table is the author.

When Mike retired in 2009, DPRG began a search for another home.



Figure 1-6. *DPRG's world headquarters from 2002 to 2009 (photo by R. Steve Rainwater)*

A Cautionary Tale

It's relatively easy to go from a well-designed and effective lab to something, let's say, less desirable. This doesn't happen overnight, but it can happen. Let this be a warning to you about how even the best of intentions can still produce embarrassing and unproductive confusion (see Figure 1-7).

Unfinished projects and leftover parts and tools compete for the limited space available in this photo. Not only is a lot of time wasted in searching for both components and tools, but the limited space restricts the scale of projects that can be entertained.

Don't let this happen to you.



Figure 1-7. *It's not safe. It's not pretty. It's not even properly "eccentric." You have been warned.*

Summary

So now you know a little something about electricity and electronics. Hopefully this chapter has covered your very basic questions about how all this magic stuff actually works.

Now you're ready to start poking around some circuits. You're going to need the right tools for the job. Chapter 2 will get you started. You'll learn about some basic hand tools that are very useful in the lab, as well as some fairly high-tech machines that you might require in the future.

CHAPTER 2

Building Your Tool Chest

You're going to need some tools in your lab, as well as the skills to use them effectively. This chapter will get you started. If you're starting from scratch, don't worry. There's not a whole lot you absolutely *must* have to get started. Some basic hand tools and a place to keep them organized is all you will need. You don't even have to spend a lot of money at first. As you progress in your hobby, you will most likely want to add to your tool chest and upgrade some of those tools. Electronics can be the perfect hobby because it can take up (1) all your spare time and (2) all of your discretionary income. What more could you ask?

The very basic hand tools, such as screwdrivers and tweezers, are mostly self-evident in their usage. Try not to poke yourself in the eye. Where some helpful advice is appropriate, it will be given.

Here's an excellent example of a simple safety rule that will absolutely improve and extend your life: when using any kind of cutting tool, always direct the cutting motion away from yourself. For example, you might receive a package in the mail, and get all excited about opening it. You then discover it's sealed up with indestructible packing tape and can't simply be ripped open with your bare hands. Use a small knife or box cutter and make a single cut at a time, starting from the point closest to you on the package and cutting outward. Using this method, should the knife slip for any reason, the blade will travel away from you. This allows your blood and other bits to stay inside you, where they can do the most good. Never cut toward yourself.

If you've already got some tools (or even a *lot* of tools), it never hurts to review their proper usage. Also, if you're suffering from an *overabundance* of tools, to the point where you can no longer keep them organized, this chapter might help you to prioritize them, at least as far as permanent residency in your lab is concerned.

■ **Tip** Every tool in your shop must *earn* its place there. It must *deserve* to be there. *No exceptions*.

The Most Important Tool Ever

The most important tool you'll ever use is your mind. Every other tool you will ever work with depends on the correct and proper functioning of your mind. If you're careful with it, you won't misplace it, neglect it, damage it, or use it for the wrong job. Your mind is a wonderful asset when cared for properly, and a terrible liability when ill-treated.

Your mind is in many ways like a muscle. The more you use it, the stronger it gets. Learning new things does not "push out" the old things you've already learned. Your brain is capable of forging new neural pathways when challenged, and there's plenty of extra capacity in that old noggin of yours to handle whatever may arise.

■ **Tip** Try to learn something new every day.

Take care of that brain of yours. Just like you wouldn't use a dull drill bit or a rusty saw, don't try to work on electrical or electronic projects when your mind is not in the right place. Ideally, you should never try to get any work done in your lab when you are sleepy, distracted, angry, upset, medicated, or overly tired. Deal with whatever problems you're facing in a responsible manner and then get back to work in the lab.

- Are you sleepy? Take a nap or head off to bed for the night. Really bad mistakes are made when the brain does not get enough sleep. Sleep deprivation is notorious for being obvious (and obnoxious!) to everyone else except you. "Really bad mistakes" made while working with electrical or electronic projects can produce very hazardous conditions for you and everyone around you, such as fire, damaged equipment, injuries, and even death.

- Are you angry or upset? Then your mind is not going to be adequately focused on what you need to do in the lab. "Fools! I'll destroy them all!" are famous last words *for a reason.* Give yourself some time to calm down from whatever has angered or upset you. Also, it's OK for you to give yourself permission to admit that you are angry or upset about something in the first place. Ignoring it probably won't make it go away, and probably won't make your feelings about it go away, either. Walk away, count to ten, or whatever works for you.

- Feeling distracted? Then now is *not* the time to be conducting electronic experiments in the lab. You need to be *present* in the lab, both bodily and mentally. There are just too many ways to make simple blunders that have far-reaching and sometimes overly expensive consequences.

- Have your cognitive functions been compromised? This can happen from taking certain medicines or even recreational intoxicants. If the little bottle says, "Don't operate machinery or drive an automobile," then you probably shouldn't be making important decisions or working with dangerous circuits in your lab, either. Wait until you're clear-headed enough to proceed with your plan for world domination, adding blinking eyes to a plush doll, or what have you.

The worst thing about cognitive impairment is that the first thing that gets impaired is the ability to judge the level of your cognitive impairment!

Care and Feeding of Your Brain

Here are a few tips to keep your brain (and the rest of you) in good working order:

- Stay hydrated. Drink more water than you think you need. This might result in more trips to the bathroom, but this is much more desirable than the alternative. A good flow of water through your systems helps your body feed and repair itself, as well as aiding in the elimination of toxins. Drink more water.
- Avoid excess consumption of coffee, tea, sodas, and especially “energy” drinks. These contain ingredients that stress both your body and your mental capacity. They do not contain energy, but trick your body into going into overdrive by triggering a stress reaction.
- Take frequent breaks. Get up and walk around, if possible. Raise your arms over your head and hold them there as you count to ten. This redirects blood flow and helps restore a balance within your peripherals.

All Those Other Bits, Too

Just as your mind is the most important tool you’ll ever use, the rest of your bodily bits and personal pieces are vital and important in your work in the lab. For the most part, there are no spare parts laying around for things like your eyes, your ears, your hands, or your skin.

Should you wear eye protection in the lab? Yes, you should. Are you always going to do so? Probably not. It’s true, it can be inconvenient or perhaps a tad uncomfortable. Consider the cost, however. Even the tiniest scratch on your eyeball can take weeks to heal and leave you susceptible to infection or vision loss. It’s just not worth it to be lazy. Ask the next one-eyed person you see. If you’re a bit uncomfortable asking one-eyed people, “Hey, what’s with the one eye?” then perhaps you can just try to imagine them advocating or encouraging you along the same path they took, whether intentionally or accidentally. They won’t do it.

Invest in quality eye protection that is comfortable and properly sized for you. Provide eye protection for visitors to your lab as well, if they will be present when soldering, welding, machine tooling, or wire clipping is being performed. Then invest in the habit of wearing your eye protection whenever it is appropriate.

■ **Note** Don’t pretend that your prescription glasses with polycarbonate lenses are “safety glasses.” They aren’t. They do not protect either your eyes or your face from impact or objects entering from the side, as proper safety glasses should. If you usually wear glasses, use safety glasses that comfortably accommodate your glasses when worn.

Will you be working with really loud noises? These could be from powerful audio amplifiers (“it goes to 11”) or power tools. Hearing loss from exposure to excessively loud noises is cumulative. This means it slowly (or suddenly) chips away at your hearing, bit by bit. Why do you think old people turn up the TV so loud?

Hearing protection is both affordable and comfortable. For temporary protection, you can use disposable earplugs. If you need protection all day, consider earmuffs designed for hearing protection. Don't let "Hey, y'all, check this out" be the last thing you ever hear.

It's hard to work with hand tools with no hands. It's possible; just really hard. Take care of your hands. There are a hundred ways to burn, tear, cut, or otherwise mangle those mitten-fittings of yours. Have a variety of work gloves on hand to handle the different needs of your lab. The choice will be ultimately determined by the particular hazards present in your lab. Are you working with chemicals as well as electronics? How about sharp edges or glassware? Normally, you won't need to wear gloves for soldering small electronics, but if you start working with really large-scale projects, such as sculptures or plumbing, you might.

Make sure you are still "handy" when wearing the proper gloves for the job. Make sure the gloves fit you properly and allow you the adequate dexterity you need.

■ **Tip** Be safe. Don't be lazy.

Basic Hand Tools

Assuming that you're going to start small and build toward bigger things, you should also start small with some small hand tools. These tools will make it much easier to work on small parts and wires.

Good hand tools increase your effective strength and improve the accuracy and precision of your motions. They allow you to focus a great deal of your strength on exactly the part that needs it, without wasting a lot of effort. Good hand tools also insulate you from sharp, hot, or otherwise unpleasant objects when you work on them.

Take care of your hand tools. Put them up when you're done with them. Make sure they are clean and ready to be used again the next time you need them. Few things are more frustrating than attempting to start a quick repair job and finding out that you need to spend twice as much time preparing your tools for use.

Have some sort of methodical plan or reasoning involved with the storage of your tools. They need a safe and comfortable home, just like you do. You need to be able to find them quickly when you want them. Try out different organizational strategies until you find one that works for you and your lab. This is an easy task when you have just a few tools to organize. Once you've accumulated a large collection of hand tools, this is no longer optional. You *must* know what tools are available and where they are located.

Frequently used tools should be within easy reach of your primary workstation. If your tools need any sort of adjustment or setup before use, make sure you've got all the proper bits handy. For example, a drill press will often have a chuck key used to tighten and loosen the chuck that holds a drill bit in place. That key needs to be in the immediate vicinity of the drill press, as well as easy to locate. Don't spend a lot of time needlessly hunting for tools. Decide for yourself on some safe and practical policies for where you keep your tools.

■ **Tip** Don't waste time guessing where your tools are located. *Decide* where they are located.

Just like everything else, hand tools have a limited useful lifetime. While some tools can easily outlast you, it's up to you to keep track of exactly how much utility you can continue to expect from your tools. This doesn't mean that you have to trash your hand tools once they develop some tiny flaw. If it's beyond your capabilities to repair the tool, then consider replacing it and reassigning it to the second string or backup tool chest. Having a spare tool, even a slightly imperfect one, on hand when you need it can make the difference between success and failure in a project.

Bear in mind, however, that some tools are simply too dangerous to keep around once they've outlived their useful life span. A dull cutting tool that cannot be reasonably resharpened is a good example of a tool that has lost its honored place among your other tools. Thank it for its service, wipe away that little tear, and then figure out a good way to recycle any of its bits that are still functional.

Wire Cutters and Wire Strippers

As you might have picked up from Chapter 1, you can spend a lot of time working with wire in this hobby. Understanding a little bit about how wire is made and how it functions in a circuit will aid you in your experiments.

How Wire is Made—The Very Short Version

Most wire is made of copper or a copper alloy. Some wire used for electrical wiring in houses is made of aluminum. The wire itself starts out as a fairly thick strand and is stretched and pulled—a process called *drawing*—until the desired diameter is obtained. This strand is then wrapped up on spools or bobbins.

- Some wire is made of a single strand of copper (or aluminum). This is called *solid-core* or *single-strand* wire. It is a single strand of wire, usually circular in cross-section.
- Multiple, thinner strands of wire are often bundled or twisted together to make larger-diameter wire. Stranded wire is much more flexible than solid-core wire, but is more expensive to produce because of the extra manufacturing steps required. Because stranded wire has a larger surface area per unit of length, it is more susceptible to environmental hazards such as corrosion.

Most electrical wire is covered with an insulating jacket, usually made of plastic or rubber. This sheathing must be removed to make electrical connections. There is sometimes more than one layer of insulation on a wire, depending on what its final application is destined to be.

More information about wire as a *component* will be presented in Chapter 3. For now, the emphasis is on the characteristics of wire that help determine the best tools to use when working with wire.

Selecting the Correct Tool

Both copper and the aluminum alloys used for electrical wiring are fairly soft metals and can be easily cut or formed with simple hand tools. Wire *cutters* are specialized tools made to make a clean cut through the wire's strand or stands. Wire *strippers* are another kind of specialized tool used to remove the insulation from a wire.

Figure 2-1 shows two rows of commonly available wire cutters.



Figure 2-1. *Commonly available wire-cutting tools. The top row shows three styles of diagonal cutters, which are the preferred tools for cutting small-gauge copper wire. The bottom row shows some tools that offer wire cutting as a secondary facility, and should only be used when proper wire cutters are not available.*

The top row of cutting implements in Figure 2-1 are various forms of what are known as diagonal cutters, side cutters, or flush cutters. These cutters have beveled cutting edges that meet in the middle of the wire being cut. One side of the cutters is flat, or *flush*, allowing wires to be cut with some precision. These are the preferred cutters for small-gauge copper wire, as well as for clipping excess component leads from a printed circuit board (PCB). See Figure 2-2.

Compare the cutting action of the side cutters to the other, less optimized wire cutters in the second row of cutters in Figure 2-1. These cutters either use a shearing action to cut the wire or include a flush-cutting area as a secondary feature.



Figure 2-2. *A close-up look at the business end of a pair of side cutters. When the two cutting edges meet in the middle, the bottom side is flat, or flush, allowing the user to get quite close to where a wire or component lead emerges from a solder joint.*

Use caution when clipping component leads or small wires with any wire cutters. The cut lead can easily fly away at sufficient velocity to poke you right in the eye or other sensitive area. If possible, hold *both* ends of a wire being cut or direct the cut leads *away* from your face.

■ **Caution** Use eye protection when clipping leads. Don't say you weren't warned about this hazard.

Wire Strippers

Wire strippers are tools that allow you to easily strip the nonconductive insulation from wires. You can try chewing it off with your remaining teeth, but this is not recommended.

Wire strippers usually consist of a pair of hinged blades with some sort of machined notch. The notch allows the blades to cut the insulation around the wire without cutting or nicking the underlying conductor. A good example is shown in Figure 2-3.



Figure 2-3. *The popular T-Stripper combination wire cutter and stripper tool from Ideal Industries has been around for over half a century. Note the wire gauge sizes stamped into the face of the cutter blade. New models feature laser-engraved text.*

The wire strippers in Figure 2-3 can easily strip the insulation from wires with a conductor diameter, or *gauge*, between 16 (0.0508" or 1.291 mm) and 26 (0.0159" or 0.405 mm). The higher-numbered wire gauges represent *smaller*-diameter wires. Once upon a time, the gauge number represented the number of *drawing* operations that were performed on a wire when being manufactured. The more times it was drawn through the processing equipment, the thinner the wire became. Today, the wire-manufacturing industry in the United States and Canada has adopted the American Wire Gauge standard (AWG). See Table 2-1.

Table 2-1. *The AWG. A more complete listing is available at http://en.wikipedia.org/wiki/American_wire_gauge, from which this partial list was obtained.*

AWG	Diameter Area			Copper Resistance	
	Inch	mm	mm²	Ω/km mΩ/m	Ω/1000 ft mΩ/ft
0000 (4/0) 0.46	00	11.684 107		0.1608	0.04901
000 (3/0)	0.4096	10.404	85.0 0.20	28	0.06180
00 (2/0)	0.3648	9.266	67.4 0.25	57	0.07793
0 (1/0)	0.3249	8.252	53.5 0.32	24	0.09827
1 0.28	93	7.348	42.4 0.40	66	0.1239
2 0.25	76	6.544	33.6 0.51	27	0.1563
3 0.22	94	5.827	26.7 0.64	65	0.1970
4 0.20	43	5.189	21.2 0.81	52	0.2485
5 0.18	19	4.621	16.8 1.02	8	0.3133
6 0.16	20	4.115	13.3 1.29	6	0.3951
7 0.14	43	3.665	10.5 1.63	4	0.4982
8 0.12	85	3.264	8.37 2.06	1	0.6282
10 0.10	19	2.588	5.26 3.27	7	0.9989
12 0.08	08	2.053	3.31 5.21	1	1.588
14 0.06	41	1.628	2.08 8.28	6	2.525
16 0.05	08	1.291	1.31 13.1	7	4.016
18 0.04	03	1.024	0.823 20.9	5	6.385
20 0.03	20	0.812	0.518 33.3	1	10.15

22 0.02	53	0.644	0.326 52	.9 6	16.14
24 0.02	01	0.511	0.205 84	.2 2	25.67
26 0.01	59	0.405	0.129	133.9	40.81
28	0.0126 0	.32 1	0.0810 2	12. 9	64.90
30	0.0100 0	.25 5	0.0509 3	38. 6	103.2

We'll return to this table again in Chapter 3 when the electrical properties of wire are discussed. For now, note that as the wire gauge number goes *up*, the wire's physical diameter goes *down*. Similarly, as a conductor's physical size goes down, its ability to carry current also goes down, and its electrical *resistance* goes up.

■ **Note** Other standards exist throughout the world. Steel-wire manufacturers use a different scale, as their interest is more on the tensile strength of the wire, not its electrical properties.

Note that the AWG is for single-strand copper wire. Equivalent gauges in stranded wire are physically a bit larger, although they have the same effective cross-sectional area and can carry the same amount of current.

When using wire strippers, keep in mind that your goal is to cut and remove only the nonconductive insulation from the wire, leaving the internal conductor intact. Even a small nick can result in a weak point in the wire, both electrically and mechanically.

Practice Makes Perfect

The best way to attain proficiency with a new tool is with practice—lots and lots of practice. This is true for working with your hands as well as with that big brain of yours. Ideally, any task worth doing will involve at least a little bit of both manual dexterity and focused brain power.

Cutting and stripping wires is an excellent example. For your first practice assignment, spend some time turning long, beautiful lengths of wire into little bits of wire with stripped ends.

CUTTING AND STRIPPING WIRE

For this exercise, you're going to need the following:

- Wire cutters
- Wire strippers
- Much wire
- A comfortable, well-lit location

Cut the Wire into Segments

Don't watch TV or be otherwise distracted. Pay attention to what you are doing.

Begin by cutting the wire into various-sized segments from 2" to 6" in length. Accuracy in length is not critical at this point. You need to get a good feel for your wire cutters and how much force is needed to cut the wire, without cutting yourself or others.

Collect the cut wire segments into a bowl or small container for the next step.

Strip the Wire Segments

Using your wire strippers, remove about 1/4" (6 mm) of insulation from both ends of each wire. Try not to cut or nick the wire core. The insulation that you remove can either be discarded or collected for use in some sort of art or craft project.

Once you've completed the cutting and stripping portion of this exercise, sort the wires according to their length, or their color if you used different colors of wire. Compare the quality and consistency of your work by looking at the first few wires and the last ones you did. Do you see any improvements in your work?

If you spend about an hour working on your wire-cutting and wire-stripping technique, you will perhaps master a skill that will prove useful for the rest of your life, as well as prepare a big pile of wires that you can use in many of the sample projects illustrated in this book.

Pliers and Tweezers

Every day, the size of the "typical" electronic component gets smaller and smaller. This miniaturization process has brought about a world where you can carry a phenomenally powerful computer in your pocket, and sometimes even make phone calls with it. The individual transistors, resistors, capacitors, and other components inside such modern marvels are literally microscopic in size. You need a fairly powerful microscope to be able to see them at all.

In your typical home electronics lab, and even in many professional labs, you will not be dealing with these tiny things, except as large clumps all tied together inside a chip or other framework. Still, the typical components you will use are often a bit too small for all but the tiniest of fingers. That's where pliers and tweezers come into play. They are an extension of your own hands and fingers, increasing your precision and allowing you to perform delicate tasks with tiny parts.

There are several types of pliers and tweezers that you may use on a daily basis in your lab. See Figure 2-4.



Figure 2-4. *Pliers and tweezers aid in working with small parts. On the left is a pair of needle-nosed pliers with cushioned grips and leaf springs. In the center is a pair of slip-joint pliers that can be adjusted to accommodate two different ranges of gripping action. On the right is a pair of needle-sharp tweezers, which can be used to pick up and place even the tiniest of electronic components—if your hand is steady enough!*

Screwdrivers, Nut Drivers, Wrenches, and Ratchets

A lot of electrical connections can be made using only a screwdriver. Figure 2-5 shows an electrical connection using a *barrier strip*. A specialized connector is crimped onto the end of the wire and held in place with a screw. A variety of crimp-on connectors are available and should be installed using the appropriate tool, as indicated by the connector's manufacturer. Just smashing the connector onto the wire with some pliers is not recommended.



Figure 2-5. *A barrier strip on a low-cost solar-charge controller. No soldering required! The specialized connector is held in place with a screw. The connector is affixed to the end of the wire by deformation using a specially designed crimping tool. You can see the indentations in the insulating collar around the connector.*

Another type of connector that is tightened with a screw is called a *terminal block*. Unlike a barrier strip, no specialized connector is required on the wire. You can simply insert a stripped wire into the terminal block and tighten the connector using a screwdriver. Try to strip the wire only enough to allow the bare conductor to enter the terminal block, without leaving any noninsulated wire exposed that could accidentally short out against another wire. See Figure 2-6.


CMP12
Charge
Load
Battery
DIMMER
OFF
ON
DC12V. 8A
IN
OUT
V-
V+
V+
V-

Figure 2-6. *A terminal block uses a screw for tightening the connection with a bare wire.*

Besides being useful for making electrical connections using barrier strips and terminal blocks, screwdrivers are also quite handy in their original function, which is to tighten and loosen mechanical fastening devices such as screws and bolts. See Figure 2-7.



Figure 2-7. *A variety of screwdrivers. The four on the left are standard, or straight-bladed, screwdrivers. The three on the right are Phillips-style screwdrivers. Other specialty bits are also available.*

You should only use screwdrivers to drive screws and bolts. Don't try to use them as levers, pry bars, chisels, punches, or other tools. When you need a chisel, use a chisel. Keep your screwdrivers clean and dry. Put them back where they belong when you're done with them. You get to decide where they belong.

Screws, Bolts, and Nuts

There are a *very* large number of different kinds of screws and bolts. Some screws, such as wood screws, are made to be driven directly into wood and create their own threads in the material as they are installed. Other screws, largely referred to as machine screws, mate with a premachined or tapped hole, or a machine nut.

Nuts are often shaped with four or six sides that allow them to be held in place while the screw is turned. Alternately, the nuts themselves are turned while the screw is held in place. Some screws and bolts have a similarly shaped head that allows them to be turned with a wrench or nut driver instead of a traditional screwdriver.

Please resist the urge to overtighten screws and bolts. The mechanical advantage gained by the inclined plane of the screw thread multiplies the force used to turn the screw into a terrific amount of pressure on the screw itself. You can easily damage either the screw or the threads in the material to be fastened by overtightening a screw.

More Specialized Hand Tools

A good set of wire tools, pliers, and screwdrivers will go a long way when working with electronics. However, sometimes you need a more specialized tool for more specialized work.

Here are some of the more common tools that are a little more focused on a particular task than they are for general-purpose usage.

Wire Crimpers

As mentioned previously in this chapter, you can make solid electrical and mechanical connections using barrier strips and specially terminated wires. The optimized connectors used for this purpose require optimized tools for best performance.

Figure 2-8 depicts some examples of specialized crimp tools for electrical connections.



Figure 2-8. *Some common crimping tools for affixing electrical connectors to wire*

Referring again to Figure 2-8, the crimpers on the left are for crimping tiny pins to the ends of tiny wires that are then inserted into plastic connector bodies. The center crimp tool is for crimping modular jacks onto telephone cables. It also includes a wire-cutter blade (bottom) and a pair of controlled-depth stripper blades for removing only the outside layer of insulation from silver-satin flat telephone cord, without disturbing the individually insulated wires contained within. The crimp tool on the right features a ratcheting action that increases the crimping force applied to the connectors. This is the tool used to crimp the connectors show previously in Figure 2-5.

Computers

You might not think about computers as being "power tools" in your toolbox. As the size of computers, laptops, tablets, and smart phones decreases, and their computing power, networking ability, and storage capacities increase, they become much better candidates for use in the lab.

Traditional "desktop" personal computers (PCs), laptops, netbooks, and tablets can perform multiple roles in your laboratory setting. If you are lucky enough to have Internet access on your computer, it can become a conduit for all types of useful electronics information, in addition to its more accepted role as a source of funny cat videos. See Figure 2-9.



Figure 2-9. *Computers being used in the lab. Paul Bouchier of DPRG uses two laptops at once when testing new robot software with the Microsoft Kinect (just to the right of his mouse).*

Here are just a few of the many possible areas of practical knowledge, learning opportunities, and bits of interesting information that you can access using your computer:

> *Data sheets*: Almost all electronics manufacturers provide online access to a library of technical data sheets and application notes for their products. These should be your first choice for information about how and when to use their products. These sources also contain important product *errata*, which contains corrections and updates for products that have been made since their first publication.
>
> *Online tutorials*: The Web abounds with detailed and thought-provoking tutorials and background information on every topic imaginable, including, not surprisingly, mountains of information on computers and electronics.
>
> *User forums*: People tend to cluster around others with similar interests. Once upon a time when people where geographically limited and unable to communicate or interact with folks around the world, this severely restricted a lot of the more specialized areas of knowledge. Today, you can find user groups centered on every conceivable human endeavor (and some inconceivable ones, too) that are filled with helpful, knowledgeable members that are more than happy to answer questions and share experiences with you. Do try to be courteous, respectful, and fair when asking for help with your projects, and always try to repay in kind by helping those with similar questions that you've had to master.
>
> *Sharing/collaboration web sites*: As the cost and complexity of publishing your work on the Internet becomes more manageable, it becomes faster and easier to let others know about your progress, as well as your problems. You can easily set up your own web page for little or no cash, or join many of the available user groups that allow their members to post, browse, and otherwise benefit from the works of other similarly minded individuals.
>
> *Design tools*: You can find many free or reasonably priced electronic design and simulation tools online. Some manufacturers also provide free tools specifically for optimizing designs for their products.
>
> *Online suppliers*: Where you once had to walk (or drive) down to the store and see what was available in your area as far as electronic components and tools went, now you can browse through the catalogs of suppliers from all over the world, from the comfort of your own lab. Not only does this provide a much larger field from which to choose, it also levels the playing field, so to speak, forcing worldwide competition for your hard-earned cash. Bonus: Some manufacturers offer a limited numbers of free samples. Yip!

This list only scratches the surface of the kinds of information you can access using a computer. You can also use a computer as part of your electronic projects, and several examples of doing this are included later in the book.

Tools for Soldering

You don't have to learn how to solder to work with electronics, but it helps. It really does. It opens a whole new world of possible projects, repairs, and custom modifications to existing equipment. Just remember, as always, to keep your work area clean and safe. See Figure 2-10.



Figure 2-10. *A Weller controlled-temperature soldering station. What a mess!*

Like any worthwhile skill, soldering is best mastered with lots and lots of practice. The best way to learn this useful skill is to have someone show you how it's done. It's difficult, but not impossible, to learn proper soldering techniques from a book. That being said, have a look at Figure 2-11.


SOLDERING IS EASY
HERE'S HOW TO DO IT
SOLDER
WIRE CUTTER
SOLDERING IRON
PARTS
PCB
THE IRON IS HOT!! BE CAREFUL! *!#
YOUR KIT SHOULD COME WITH INSTRUCTIONS FOR WHAT PARTS GO WHERE AND WHAT WAY!
CLEAN THE TIP OF YOUR IRON BEFORE EACH SOLDER CONNECTION!
PUT YOUR PART IN PLACE. BEND OUT THE LEADS SO IT STAYS IN PLACE
LEAD
LEAD
PUT THE PCB DOWN SO YOU CAN SOLDER.
CAREFUL WITH THE SURFACE UNDERNEATH!
FIND SOME GOOD WAY TO KEEP IT STEADY
IF YOU NEED A THIRD HAND, YOU CAN MAKE A STANDING COIL OF THE SOLDER INSTEAD OF HOLDING IT IN YOUR HAND
OK, LETS SOLDER!
FIRST, YOU WANT TO HEAT BOTH THE PAD AND THE LEAD FOR ABOUT 1 SECOND
LEAD
PAD
PSST! CLEAN THE TIP FIRST!
TOUCH THE SOLDERING IRON TO BOTH THE PAD AND THE LEAD!
LEAD
NOW FEED SOLDER UNDER THE TIP OF THE IRON
ABOUT 1-3 MM
SOLDER
PCB
3 MM
LEAD
STOP FEEDING SOLDER, THEN HOLD FOR 1 SECOND SO THE SOLDER CAN FLOW PROPERLY
SOLDER
PCB
A GOOD CONNECTION COVERS THE PAD WITHOUT TOUCHING OTHER PADS AND SURROUNDS THE LEAD
CUT THE LEADS OFF WITH THE WIRE CUTTER
ALWAYS HOLD ON TO THE LEAD!
EYES DON'T LIKE JUMPING LEAD BITS!
CUT
SOME LEADS ARE ALREADY SHORT, YOU DON'T NEED TO CUT THOSE.
THE SMOKE FROM THE MELTING SOLDER IS NOT TOXIC, BUT BLOW GENTLY ON IT TO AVOID BREATHING IT.
LEAD ON THE OTHER HAND IS TOXIC, AND GETS ON YOUR SKIN WHEN HOLDING THE SOLDER.
WASH YOUR HANDS WHEN YOU'RE DONE!
KEEP SOLDERING EACH PART IN ITS CORRECT PLACE. REMEMBER SOME PARTS NEED TO GO IN A CERTAIN WAY!
IF ALL YOUR CONNECTIONS ARE GOOD, YOUR CIRCUIT WILL JUST WORK!
THERE ARE MORE TRICKS YOU WILL LEARN AS YOU KEEP SOLDERING, BUT NOW YOU KNOW ENOUGH TO MAKE MANY COOL THINGS.
SOLDERING COURSE BY MITCH ALTMAN HTTP://CORNFIELDELECTRONICS.COM
COMIC ADAPTATION BY ANDIE NORDGREN HTTP://LOG.ANDIE.SE
PUBLIC DOMAIN, USE, COPY, SPREAD!

Figure 2-11. *Instructions for soldering. This delightful illustration by Andie Nordgren captures the basics of soldering as taught by soldering guru Mitch Altman (http://log.andie.se/post/397677855/soldering-is-easy).*

To solder, you will need a soldering iron. You will also need some solder and probably some wire cutters. That's just the tip of the iceberg, however. Like any good tool, your soldering station will soon accumulate many *accessories* to enhance your soldering prowess.

To begin your soldering adventure, you will need a *small* soldering iron, some solder, and a damp sponge. The big, pistol-grip style of soldering irons are for much larger projects, such as plumbing. Ideally you want something in the 15W to 50W range. See Figure 2-12.



Figure 2-12. *The pencil-grip style of soldering irons is better suited for working on small electronics projects.*

The soldering iron in Figure 2-12 has a replaceable, conical tip. These tips are generally interchangeable for a particular model of soldering iron, but unfortunately not interchangeable between different models or manufacturers. Different tip shapes are also available, depending on what types of things you're wanting to solder.

The tip is usually made of copper, which is an excellent conductor of heat. Since copper really likes to combine with other metals at high temperatures (which is exactly what happens when soldering), most tips are coated in a thin layer of steel to give them much longer useful lifetimes. Tips still wear out, however, and should be replaced.

In this particular soldering iron, the next part of the iron is the removable barrel that holds the tip in place. This barrel is where the heating element is housed, so remember that it is just as hot as the tip! Try not to touch it. You will probably not want to make that mistake more than once.

The next section is the padded and insulated handle of the soldering iron, which is made of dense plastic foam. A quality soldering iron will be comfortable in your hand and won't produce excessive fatigue, even after hours of use. Lower-quality and lower-priced models will more rapidly take their toll on your hands.

Not shown in Figure 2-12 is the flexible power cord running back to the soldering iron's base. This cord supplies the electrical power that is converted to heat in the barrel, as well as some wires for a temperature sensor. This allows the unit to control the temperature of the tip with great accuracy. Note the temperature dial in Figure 2-10. Lower-cost units omit the temperature control features and run at a constant power output.

It will take some amount of time for the soldering iron tip to reach a working temperature. Likewise, it will also take some time to cool off once you've turned off the soldering iron.

■ **Caution** Soldering irons are very hot in use and can cause painful burns. Always treat them with respect!

The solder you use will be determined by what kind of soldering you want to do. For most small, electronics-related soldering projects, a small-gauge tin-lead or lead-free solder can be used. Bear in mind that lead is a poisonous material that slowly accumulates in your system, should you come into contact with it, as your body has no good way of eliminating it. Wash your hands before and after soldering, just to be safe.

Soldering works best when everything being soldered is sparklingly clean. To help facilitate this cleanliness, chemical compounds known as soldering rosin are used. These compounds chemically clean the surfaces being soldered when exposed to high levels of heat. Some types of solder have rosin incorporated into them. You can also obtain rosin as a paste into which you can dip wires and component leads before soldering. Other types can be applied with a dispensing pen.

■ **Caution** Don't breathe the smoke emitted during the soldering process. If possible, use a fan or fume extractor to redirect the soldering fumes away from you.

Once your soldering iron is up to its proper operating temperature, clean the tip by wiping it gently on a damp sponge. Your tips will last longer if you resist the urge to clean them before replacing the soldering iron in its holder. Even though it seems counterintuitive to "put it up dirty," this will more than double the life of your soldering iron tips. Just be sure to clean the tip *before* you solder anything.

Power Tools

Everybody loves power tools, don't they? Sometimes it's enough to just *imagine* that you might need one to justify a trip to the store and subsequent purchase. While this may be human nature (or perhaps only the nature of one particular gender), it doesn't fully justify having one of each in the lab, *just in case*.

Drills and Drill Bits

You will, however, find a few particular tools to be especially useful in your lab. A good hand drill or drill press is one of those tools. There seems to be no end of things electronical that need a few more holes drilled into them. Electronic enclosures and control panels need good, clean holes drilled into them. If you make your own PCBs at home, you will find that they need *lots* of holes drilled into them.

Like any power tool, an electric drill needs and deserves your respect. You'd be surprised how much unintentional damage you can cause with such a simple device. Observe these simple safety rules when operating a power drill:

- Keep your work area clean and well illuminated.
- Remove any watches or jewelry you might be wearing.
- If you have long hair, keep it pulled back and tied out of the way.
- Always clamp down any work to be drilled on a drill press.
- Always remove drill bits from the drill chuck after use.
- Discard dull or rusted drill bits that cannot be resharpened.
- Always wear safety glasses when operating power tools.

Hand drills come in all shapes, sizes, and price ranges. Some are powered by hand cranks and some are electric. Rechargeable batteries make for very portable drills that you can carry almost anywhere. See Figure 2-13. The only drawback is their limited charge time. That's why you should always have at least one spare battery charged up and ready to go. Electric drills with wires attached don't have this problem. Just don't trip over the cord!



Figure 2-13. *A rechargeable hand drill. This model is both variable speed and reversible, which are two very desirable features in a hand drill.*

■ **Note** Power drills are also very handy when used with screwdriver bits. They can save you time and many blisters!

Drill bits likewise come in all sizes and shapes. You can buy sets with a variety of sizes, and these will usually come with a handy storage container that conveniently labels all the sizes for you. This only works, however, if you take the time to return the drill bits to their proper location once you've finished working with them.

A drill press has a large frame that facilitates drilling a precisely aligned hole, over and over again. You can make spindle-speed adjustments to drill presses (even small ones, such as the one pictured in Figure 2-14) either through an electronic speed control or by changing up the belts and pulleys that drive the spindle. There are even small frames for mounting handheld drills or rotary tools, such as the Dremel brand of tools. You can often, however, find actual, dedicated drill presses on sale for about the same price as the daintier Dremel tools.



Figure 2-14. *A small tabletop drill press*

■ **Caution** When working with drills and presses, always keep your work area clear. Always wear safety glasses when using power tools. Try to keep the chuck key handy. Don't leave drill bits mounted in the chuck when not in use. Many chuck keys have built-in springs that prevent them from remaining in the chuck. Those that don't risk being accidentally left in the chuck when the drill its turned on, which can either fling the chuck across the workshop or make a big mess of your favorite hands.

Laser Cutters and 3D Printers

While not everyone can afford some of the more expensive and esoteric tools that are available, some of these tools are getting more popular than others; excellent examples are laser cutters and 3D printers. See Figures 2-15 and 2-16.

Laser cutters and engravers use a powerful carbon-dioxide laser to cut through wood and non-chlorine-based plastics. The laser beam is focused onto the work surface using mirrors that are mounted in an XY gantry, allowing the cutting area to be controlled by a computer. Typical installations require venting to the outside because of the various aromas produced in the process, as well as a water-cooling system for the laser tube itself.

There are also some newer laser cutters being built by hobbyists from scratch.



Figure 2-15. *A laser cutter. A powerful 40W carbon-dioxide laser is used to cut through wood and non-chlorine-based plastic, all under computer control. It can also be used as an engraver. This model is manufactured by Full Spectrum Engineering.*

3D printers seem to be all the rage these days. We're all pretty accustomed to the idea of printing on paper with a computer, although it's still a pretty recent innovation, as far as the history of printing goes. The idea of printing a solid object, on the other hand, is considered to be something of a game-changer.

The simplest 3D printers use a plastic extrusion and a motorized gantry to operate as a kind of a robotic glue gun. A plastic filament is fed into a heated fixture that is moved around a print bed, leaving a trail of cooling, gooey plastic. Either the extruder or the print bed is moved using motors under computer control to build up a layer at a time of the desired object.

Higher-technology 3D printers use this and other techniques to produce tangible, solid objects. Some use layers of fine powder that is glued together with a binder dispensed from a print head, similar to an inkjet printer. As each layer is printed, the object is lowered and another layer is deposited. This can even be done with sugar, as in the case of the CandyFab 4000, designed by the clever folks at Evil Mad Scientist Laboratories (`www.evilmadscientist.com/article.php/candyfab`). A stream of heated air is used to fuse a layer of sugar into a single solid structure, and an object is built up of successive layers.



Figure 2-16. *A 3D printer at Dallas Makerspace. This machine uses a heated extruder to build 3D objects out of plastic.*

Basic Test and Measurement Equipment

When it is behaving itself, electricity is generally invisible. To "see" what it is doing, or not doing, you will need some specialized tools. These fall into the two general categories of *test* and *measurement* equipment.

The line between testing and measuring is sometimes blurry. One possible distinction might be that testing verifies proper operation within acceptable parameters, while measurement actually assigns values to those parameters. An example of testing is, Does that flashlight work? The answer is yes or no, arrived at by the simple expedient of turning it on and observing the results. An example of measurement is, How much current does that flashlight draw? The answer might be 0.78A, and this would be determined using the appropriate measurement device, which in this case could be an ammeter.

Inspection Equipment

Sometimes, however, measuring things isn't hard at all, especially when the things being measured are actual, tangible items that you can hold in your hand. What you will need are some basic tools, primarily to be able to *see* what it is that you are measuring, and secondarily to take accurate measurements of them, at least in regard to their physical dimension. This comes in very handy when trying to identify components during repair or equipment upgrades, when the original technical documentation is not at hand.

Even the youngest and finest of eyeballs will need help with the teeny-tiny components that are available nowadays. You should try to find at least a small magnifying glass to examine fine details. If your budget allows, you might want to consider a microscope of modest power to look at your handiwork. Careful shopping will result in finding some older microscopes at bargain prices. Expect to pay a premium price for the shiny, new stuff. See Figure 2-17.



Figure 2-17. *A very nice stereo microscope. The power cord running to the white ring (partially hidden) supplies power to a ring of white LEDs that help illuminate the field of view. The base is very heavy to help stabilize the microscope.*

Even a humble magnifying lens can be very helpful in the lab, especially if it has a built-in light. See Figure 2-18.



Figure 2-18. *A small, handheld magnifier with a built-in LED light is very handy for examining small features and details, such as are found on many PCBs.*

Physical Measurement Devices

Once you know what something looks like, at extreme close-ups, can you describe in absolute terms how big it is?

Take a look at Figure 2-19. Here we have, from the top to the bottom, a traditional tape measure, marked in both English and metric units (fractional inches and decimal centimeters), a digital caliper that can render measurements in either system at the touch of a button, and an architect's scale. While it may not be evident in the top-down view, the architect's scale is triangular in cross-section, resulting in not two but *six* different measurement options. This is mostly due to architects liking to draw things to scale, instead of full-sized.

The digital caliper is interesting in that it also provides a computer interface so that its readings can be pulled in by a computing device of some sort. These devices used to be quite expensive, but mass production has brought their prices down significantly.



Figure 2-19. *From top to bottom, a tape measure, a set of digital calipers, and an architect's scale.*

Simple Electronic Measurement Tools

Now that you've got the tools to examine what these things look like and how big or small they are, let's move on to the more mysterious art of measuring their electrical properties.

Voltmeters

Voltage is a measure of electromotive force, and the standard unit of measure is the *volt*, named after Alessandro Volta, an Italian physicist. Voltage is sometimes compared to the pressure of water flowing through a garden hose, while amperage is compared to the amount of water flowing through the hose at any given time. It's not particularly useful to push this water analogy too far, but it's helpful in the beginning.

Voltage can be accurately measured with, you guessed it, a voltmeter. See Figure 2-20.



Figure 2-20. *A panel-mount analog voltmeter (left) and a digital version (right)*

A voltmeter measures the voltage, or *potential difference*, in a circuit across two points. Sometimes one of the points is a fixed reference point, such as the electrical *ground* mentioned in many circuits. This is often just a convenience for the purpose of measuring things, as the ground in an electrical circuit may or may not be connected to the ground under your feet.

A voltmeter will have two terminals, labeled positive (+) and negative (–). Looking at the analog voltmeter in Figure 2-20 (the one on the left), we see a needle that can swing from 0 on the left to 30 on the right. The prominent capital *V* on the dial indicates that the unit of measure is the volt. This indicates that you can use this meter to directly read from 0 to 30 volts, just by placing its terminals across a voltage. The meter itself is electromechanical in design, and creates a magnetic field that works against a spring and a fixed magnet. This action causes the needle to move to a point generally corresponding to the labeled voltage on the dial. These needles are not especially accurate, but can be corrected using the screwdriver adjustment at the bottom of the meter.

An analog panel meter such as this one does not require a separate power supply for proper operation. It draws all the power it needs from the signal being measured. This makes it unsuitable for measuring low-power circuits, where the current draw from the meter would unduly influence the reading.

The panel meter on the right is a digital circuit that measures the voltage and displays it on the built-in liquid crystal display (LCD). It requires a separate power supply for normal operation.

Ammeters

An *ammeter* looks and operates just like a voltmeter, except that it measures electrical current flow instead of voltage. The flow of electrical current is measured in units called *amperes* (A). The basic mechanism is almost identical to a voltmeter. To convert a current flow into a voltage, an electrical device known as a *shunt* is used. The shunt is simply a fixed-value resistor that produces a voltage across its terminals in relation to the amount of current that is flowing through it and its inherent resistance to the flow of current.

This relationship between voltage, current, and resistance is elegantly expressed in *Ohm's Law*. If you know two of the measurements in a circuit, you can calculate the third, based on their fixed and proportional relationship to each other. You will find this law to be exceedingly helpful to you when designing, repairing, and upgrading electronics.

To avoid using fractions, which seem to terrify so many people for no good reason, you can use Ohm's Law thusly:

- Voltage (volts) = current (amps) × resistance (ohms)
- Current (amps) = voltage (volts) ÷ resistance (ohms)
- Resistance (ohms) = voltage (volts) ÷ current (amps)

That's all there is to it, if you're just working with volts, amps, and ohms. Things can get weird, however, when you start to work with alternating current (AC), which is the kind of electricity you find in wall outlets and audio circuits.

Ohmmeters

An excellent application of Ohm's Law is found in building a resistance meter, also called an ohmmeter, because it measures resistance. Resistance is measured in units called ohms, often abbreviated with the capital Greek letter omega (Ω).

There are two ways to do measure resistance. One is to pass a known voltage though the unknown resistance and measure the current that is flowing in the circuit. The other is to pass a fixed current though an unknown resistance and measure the voltage across it. This second method is the one most commonly used.

You're most likely going to use a multimeter to measure resistance, as this is one of the more common functions of these handy devices. Mutlimeters are covered in the very next section.

Advanced Test and Measurement Equipment

It would seem that for simple circuits, having just a voltmeter, an ammeter, and an ohmmeter would be all you need. For the most part, this is correct. However, have you considered what would happen if you applied 100V to the 30V meter shown in Figure 2-20? What if you simply reversed the polarity of the signal by accident? Something bad for the meter, that's for sure. It might not actually catch on fire *right away*, but it would certainly damage the delicate, spring-loaded mechanism, possibly rendering it useless as a reliable measuring instrument.

The same can be said for an unprotected ammeter or ohmmeter. Luckily, the nice people that make good test equipment stay up late at night, thinking of the stupid things we might do with their products, and protect them accordingly. Let's look at some meters that measure multiple electrical characteristics, which strangely enough are called *multimeters.*

Multimeters

Multimeters will almost always allow you to measure various ranges of DC (direct current) volts, AC volts, current, and resistance. More advanced meters also measure things like frequency and duty cycle or even temperature. Some meters will even directly measure capacitors, inductors, and transistors using specialized connectors.

As with most tools, you generally get what you pay for with multimeters. The meter on the left in Figure 2-21 was purchased for under $3, including shipping from China. It arrived DOA (dead on arrival) and was not deemed important enough to return. It will make an interesting clock or fake lie detector someday. The unit on the right was purchased new for nearly $400 and has provided over a decade of useful service. The unit in the center is modeled after the unit on the right, it would seem, but can be bought new for between $10 and $20. The unit in the photo was bought wholesale for $4, because sometimes you get lucky. It's often handy to have a second meter in the lab—for example, when you need to measure the voltage *and* the current flowing in a circuit simultaneously, which you just can't do with a single meter.



Figure 2-21. *Examples of some multimeters. The meter on the left features an analog display that is easy to read and acommodates several readout scales simultaneously. The remaining two meters have digital readouts and offer more accuracy. All the meters use a large rotary knob for selecting the proper function. The higher-cost unit on the right features auto-ranging, intellignetly deciding what range to use. The right two units also have high-impact boots to help protect them in the event of a fall.*

Your present budget will help determine what level of multimeter you might want to obtain. If you're wanting to sink less cash into a multimeter right now, consider looking for used equipment in good shape. As with any good tool, you can spend as much as you like on these. The sky really is the limit here.

Most all-in-one meters protect their inputs using fuses. You will have to disassemble your meter to replace these fuses, so think twice and measure once (to paraphrase the old carpenter's saying, "Measure twice and cut once").

■ **Tip** Be sure to set up your meter for the proper function and range *before* taking measurements.

Oscilloscopes

Once you've gone beyond measuring simple DC and AC voltages and move on to more complex signals and waveforms, you'll have to lay aside your trusty meter and fire up your favorite oscilloscope. This instrument is more complex than your traditional multimeter, and offers a different perspective on what's going on in your circuit.

While many modern oscilloscopes have many modes of operation, their basic function is to draw a picture of your signal on a small screen. In the olden days, this was done with a moving dot that was swept across a phosphorescent screen, leaving a residual, fading line of light. If this pattern was repeated over time, a visual representation of the signal could be seen on the screen. See Figure 2-22.

Modern oscilloscopes use a computer monitor or built-in screen display to draw the signal. This saves space, weight, and power requirements.

When purchasing an oscilloscope, the features you pay most for are the number of available channels and the bandwidth. The least expensive oscilloscopes will have a single channel. Having multiple channels allows you to "see" multiple signals simultaneously, which is often helpful in understanding what is going on in a circuit.

Bandwidth refers to the range of frequencies that can accurately be measured by the oscilloscope. Lower bandwidth scopes require much simpler electronics, and are thus cheaper to produce.



Figure 2-22. *A Tektronix 475A oscilloscope. This piece of vintage test equipment is considered by some to be the best analog oscilloscope ever made. It also has a digital multimeter built in along the top edge.*

The Golden Age

Once upon a time, not so long ago, a quality oscilloscope weighed 40 pounds and had a folding handle to make it, if not portable, at least *transportable*. It also had its own line of furniture to place it on, so that you could wheel it around the lab as you needed. Oh, and it also cost about three months' salary, and that's if you had a *good* job.

The good news? That same scope still works today. It can be repaired or calibrated to the exact same standards as when it was brand new, *plus* you can buy it on eBay for a few hundred dollars, sometimes less. That's because when these devices were designed back in the 1970s, they were made to be the best in the world, and cost was not a factor.

Modern Oscilloscopes

Today you can buy a quality oscilloscope for a few hundred to a few thousand dollars. These scopes not only display your signal on a large, colorful screen, but they can also analyze the signal and tell you all kinds of interesting things about it. For an example of such an oscilloscope, see Figure 2-23.



Figure 2-23. *A modern digital storage oscilloscope. The RIGOL DS1052E is an affordable scope that will handle most troubleshooting and design challenges that you might encounter in your lab.*

This new breed of digital storage oscilloscope (DSO) can even connect to your PC to be remotely operated and allow you to capture screen shots that can then be pasted into books about how to build your own electronics lab. It's true. See Figure 2-24.



Figure 2-24. *A screen capture made with the RIGOL DS1052E oscilloscope.*

Tiny Oscilloscopes

The march of electronic miniaturization never stops, and so it is with oscilloscopes. If both your needs and your budget are modest enough, perhaps you can get by with something like the pocket-sized wonder shown in Figure 2-25.

While little scopes like this lack the accuracy and bandwidth of their larger relatives, they are definitely handy to have when you need to look at a signal. If you can keep your expectations in check when it comes to the user interface, you can get a lot of utility from such a small package.

Additionally, one of the benefits of a device such as this is that the hardware and internal software (yes, there's a little computer in there, somewhere) is all open source. This means that you have access to all the schematics and source code. And what does that mean? It means that if you have the skills and the right equipment, you can redesign the entire apparatus to fit your own requirements, assuming that you understand the basic limitations of the electronics. The sky is the limit. You are empowered.


FIT 0.1V/Div 200uS/Div Y.POS 1.000 C
TR
TS
×1
SI
FS
FL
Fo
T2
T1
T0
Vt= 72.0mV V1-V2= 636 mV ΔT= 1.32mS RUN
M

Figure 2-25. *A handheld oscilloscope, which can also fit in your pocket. This is the DSO201, which has been discontinued by the manufacturer, but can still be snapped up for a song from various online distributors, as well as eBay. This unit was purchased new for $60 and features a single channel with a bandwidth of 1 MHz.*

Power Supplies

One of the most important pieces of test equipment in your lab is a reliable power supply. Building a good bench power supply is an excellent first or second electronics project (see Chapter 5 for more on adding power supply to your lab and Appendix A for more on building your own). This is because the basic design is very simple and easy to build, yet allows you to add any number of additional features later.

Once you get tired of throwing away spent 9V batteries and grow weary of waiting for the red light on the battery charger to go out, it's time to invest (either time or money or both) in a decent bench power supply.

It doesn't have to be fancy. In fact, the simpler the better at first. What you're aiming for primarily at this point is reliability. You want to know that when you turn on your 5V supply, it's putting out 5 volts, not 2 or 11, no matter what you do to it. If it's overloaded, it needs to deal with it and not be catching on fire. If it's underloaded, or not loaded at all, it still needs to maintain a nice, clean output.

Want a cheap or free power supply? Do you have any dead or discarded electrical gizmos that came with a charger? These make excellent starter supplies for the new lab. Do you have any extra USB chargers? These are even better, because they supply up to 2.5W (and sometimes more) of *regulated* 5V. We'll use some of these in experiments in Chapter 3.

Organizing Your Tools

So now you have an idea about some of the tools you want (or already have) for your lab. Where are they all going to live? This is a big question, and deserves a big answer.

One way to look at this book is that the entire latter half is dedicated to answering this question. There are, obviously, many possible arrangements that will work for most people. But we're talking about *your* lab, with *your* tools, arranged and ordered to meet, specifically, *your* needs.

As you progress through Chapter 3 (the very next chapter in this book), you'll get a chance to play with both your tools and some interesting electronic components, all in the interest of getting you familiar with some basic concepts. These concepts and ideas are not new, but they may be new to you. The good news is that time invested today and in the very near future should pay off big dividends to you later in life. Who knows what you'll devise in that electronics lab of yours?

Summary

Starting with your brain and working outward, this chapter has covered some of the tools and devices you might use in your electronics lab. These include basic hand tools, computers, tools for soldering, some common power tools you might find handy, as well as some fancy-schmancy tools you might only find in a hackerspace, school, or electronics clubs, such as laser cutters and 3D printers.

You also learned about some of the basic test and measurement tools you'll be needing when working on electronic circuits in your lab. These include magnifying glasses, measuring tapes, and meters (oh my!), as well as oscilloscopes and power supplies.

Additionally, *lots* of advice on safety was presented. These topics were learned the hard way. Do try to learn from the mistakes of others, won't you?

Just a hint was given about how you might want to organize your tools within your lab. Take care of your tools and they will most certainly take care of you. The details about possible organizational scenarios is left for the second half of the book, where you will learn about setting up labs big and small, as befits your needs, budget, and interests.

Chapter 3 ties in much that you have learned here in Chapter 2 by introducing you to not only some of the basic electronics components and their uses and characteristics, but also how to use a good number of the tools described in this chapter. Hopefully this chapter has whetted your appetite and readied you to dive into some circuits and see what kind of mischief you can wreak on the world.

CHAPTER 3

Components

You're going to need some components to play with, as well as the knowledge to use them effectively. This chapter will introduce you to some of the bits and pieces that make up modern electric and electronic circuits. It will also teach you a little bit about how to identify components from their appearance and markings, when available.

Once you've got an idea about what these parts do in a circuit, you'll learn a little more about how to measure their electrical properties and put them to use. You'll also be shown what *not* to do, in some select examples.

There are an enormous number of both manufacturers and vendors of electronic components these days. Trying to list even a few of them here in print doesn't really make much sense, as a good percentage of that information will be incorrect or obsolete as soon as the ink dries on the page.

Having a variety of basic components readily available is convenient, until your collection grows beyond your ability to house or organize it. This happens far too often, in reality. Most common electronic parts can be obtained within a day or two from local sources, unless you live in a really secluded part of the planet. Also, most of the more common parts will typically cost only a few pennies apiece, so there aren't a lot of reasons to stockpile random parts. Keep a few of each on hand for experimentation, but hold off on pointless hoarding . . . if you can.

Conductors and Interconnects

In any electrical or electronic circuit, there are just as many connections between components as there are components. These include wires, cables, connectors, plugs, sockets, and all those other pieces that help the little electrons zip around the circuit.

First, let's take a look at wires and interconnects in a very abstract way. We can think of wires as connections between other components, without having to get into a lot of detail about the wire itself. We just want a way to indicate that there is an electrical connection among all the bits, and using an electrical schematic diagram is an easy and effective way to do this.

Electrical Schematics

A *schematic* diagram is any kind of stylized drawing that represents a simplified view of something. Usually some sorts of symbols are used to represent the parts that make up the whole, as well as the connections or relationships that exist between them and possibly the outside world. You can have schematics for plumbing, hiking trails, or tribbles, a well as electrical and electronic circuits. Let's talk about electronic schematics for a little bit.

The electrical symbol for a wire is almost always just a plain, solid line. If there's something really special about the wire that needs to be used, it is usually indicated in a note somewhere on the schematic. This can be used to indicate what color the wire needs to be, what size is appropriate, whether there are any special requirements for the insulation, and so forth. Most of the time it's just a plain, solid line. For an example of just how simple it can be to draw a wire in a schematic, see Figure 3-1.



Figure 3-1. *A very simple electrical schematic diagram, showing how to get from point A to point B with a single wire. Drawing wires in schematics is easy!*

If a wire starts in just one place and ends in just one place, everything stays nice and easy. If multiple wires need to converge on a single point, or one signal wire needs to split up to go to more than one destination, it gets just a little more complicated, but not too much. See Figure 3-2.



Figure 3-2. *Wires that are connected to each other usually have a dot at their intersection. If there is no dot, there is no connection between overlapping wires.*

In the figure, points A, B, and C are connected together. Points D and E are connected together, but are not connected to points A, B or C, even though the wires look like they are crossing. In a professional schematic, a careful draftsperson would route the wire from point D to point E on the right side of the components to avoid any possible confusion.

Some folks like to draw a little bump, or bridge, when two unconnected wires cross in a schematic, just to make sure that everyone knows that the wires aren't connected. This gets to be a bit tedious once you've got more than two or three components in your schematic, and it can look a bit unsightly. Feel free, however, to draw your schematics however you see fit. Just remember that others might not share your particular drafting sensibilities.

Wire and Cables

Chapter 2 took a quick look at wire and how it is made to help you pick out the best wire-cutting and wire-stripping tools. Now it is time to consider wire as an electrical component within your circuits. Knowing what a wire can and cannot do will help you pick the right kind of wire to use. Yes, wire has limits! This is important both for building new circuits from scratch as well as repairing, replacing, or upgrading wiring in existing circuits.

Wire can be used for all sorts of artsy and craftsy purposes. Copper wire is the most common wire used in electronics. Sometimes the copper conductor is *tinned* with another conductive metal with a low melting point to make it easier to solder. When you cut this wire, you can see the copper on the inside.

Pure copper wire is getting very expensive these days. Unscrupulous people try to pass off copper alloy with inferior electrical properties as the real deal. A quick way to test is with a magnet. Copper is not attracted to magnets.

As mentioned in Chapter 2, wire comes in two major categories: solid core and stranded. Solid core wire is just a single piece of copper wire, while stranded wire is made up of many smaller strands of copper wire, usually twisted together. Stranded wire is generally more flexible than solid core wire.

Copper wire is measured using a gauge system. Different systems exist around the world. A common system used in the United States and Canada is the American Wire Gauge (AWG) standard. It uses a series of single numbers to denote the relative size of the wire, with larger numbers representing smaller-diameter wires. These numbers go all the way down to zero (0 gauge), but they don't stop there. Larger wires than 0 gauge are called 00 gauge, double-ought, or sometimes 2/0. There are also three- and four-digit versions, but after that, those giant wires are specified with their actual cross-sectional diameter.

Using Wire: The Very Short Version

Fatter wires carry more current with less heat being generated due to resistance. The wire's insulation is rated for a maximum voltage and temperature. If this temperature is exceeded, the insulation will soften, melt, or catch on fire. Avoid this by using the right sized wire for the job. Exceeding the maximum voltage can cause more problems if the current arcs through the insulation. This can cause a short circuit and may even cause a fire. It is also likely to give off noxious fumes. Choose wisely!

For low voltages (under 36V) and small current loads (under 1A), you can use whatever you want. It doesn't matter. Pick something pretty. A thing of beauty is a joy forever.

For higher-voltage applications, make sure the wire's insulation is rated *far in excess* of what you anticipate. The rating should be visibly printed on the insulation itself. See Figure 3-3.

Figure 3-3. *The wire's insulation only works up to a point. That point is usually printed on the insulation itself, but you may need to put on your good reading glasses to see it. This wire states, "LL33911 CSA TEW 105°C 600V FTT 14AWG," which translates to the manufacturer's part number, Canadian Standards Association certified thermoplastic equipment wire, maximum temperature of 105°C, 600V insulation dialectric strength, 14 gauge.*

For higher-current applications, you really need to use the highest-gauge wire that is necessary to carry the required current. Hot wires cause fires.

Using Wire: The Longer Version

If you will spend some time learning about the properties of wire, you will be able to make *much* better decisions regarding its use and application. Assuming that the overall shape of the cross section of the wire is round, the gauge of the wire determines how much resistance to the flow of electrical current the wire will exhibit over a given distance. This resistance, in turn, helps determine the amount of electrical current that the wire can safely carry.

When electric current meets resistance, the electrical power is converted into some other form of energy. Usually this energy is given off as heat, or thermal energy. It can also produce magnetic fields, sound, light, and radio waves.

A good example of this is demonstrated by the heater coils on an electric stovetop. When the stove's switch is turned on, current flows through the coil. Most of the current is converted directly into heat. Electric heaters are very efficient this way. A small amount of the electrical power is converted into light. You can see this as a red glow coming from the heater coil when it is hot. The coil also creates a magnetic field.

If you know the gauge of a wire, you can look up the wire's characteristic resistance. These numbers will be close but perhaps not exact, as there will always be small variations in wire diameter, conductor purity, and other factors. Generally, however, the numbers are pretty close.

Let's take another look at the AWG table (see Table 3-1), and look at a few simple examples to help understand what these wires can do for us. (A more complete listing is available at `http://en.wikipedia.org/wiki/American wire gauge`, from which this partial list was obtained.)

Table 3-1. *The AWG*

AWG	Diameter Area			Copper Resistance	
	Inch	mm	mm²	Ω/km mΩ/m	Ω/1000 ft mΩ/ft
0000 (4/0)	0.46 00	11.6 84	107	0.1608	0.04901
000 (3/0)	0.4096	10.404	85.0 0.20	28	0.06180
00 (2/0)	0.3648	9.266	67.4 0.25	57	0.07793
0 (1/0)	0.3249	8.252	53.5 0.32	24	0.09827
1 0.28	93	7.348	42.4 0.40	66	0.1239
2 0.25	76	6.544	33.6 0.51	27	0.1563
3 0.22	94	5.827	26.7 0.64	65	0.1970
4 0.20	43	5.189	21.2 0.81	52	0.2485
5 0.18	19	4.621	16.8 1.02	8	0.3133
6 0.16	20	4.115	13.3 1.29	6	0.3951
7 0.14	43	3.665	10.5 1.63	4	0.4982

8 0.12	85	3.264	8.37 2.	06 1	0.6282
10 0.10	19	2.588	5.26 3.	27 7	0.9989
12 0.08	08	2.053	3.31 5.	21 1	1.588
14 0.06	41	1.628	2.08 8.	28 6	2.525
16 0.05	08	1.291	1.31 13	.1 7	4.016
18 0.04	03	1.024	0.823 20	.9 5	6.385
20 0.03	20	0.812	0.518 33	.3 1	10.15
22 0.02	53	0.644	0.326 52	.9 6	16.14
24 0.02	01	0.511	0.205 84	.2 2	25.67
26 0.01	59	0.405	0.129	133.9	40.81
28	0.0126 0	.32 1 0	08 10	212.9	64.90
30	0.0100 0	.25 5 0	05 09	338.6	103.2

Conductivity

The first thing you need to know is that copper wire really, really wants to conduct electricity. It wants to conduct electricity more than it wants to *resist* the flow of electrical current. Even so, copper is not a perfect conductor, and it has a certain amount of inherent resistance. This resistance causes the energy carried by the electrical current to be sidetracked, or converted into heat and other forms of energy. The higher the resistance in the wire, the more heat will be produced.

Normally this heat is a very small thing and is easily dissipated into the surrounding air. You usually can't even tell by touching that a wire is a fraction of a degree warmer than its surroundings—but this is only true when the amount of energy is relatively small, like in our rewired flashlight example. When you start to push a *lot* of power through a wire, the heat buildup can outpace the cooling-off provided by the surrounding air, and the temperature of the wire increases.

Again, this is no big deal as long as that temperature stays within a comfortable range. But what happens when the temperature gets really high?

First, the insulation will get soft, melt, or even catch on fire. After the insulation, if any, has burned off, the wire will glow red hot and eventually melt. This is known as *catastrophic wire failure*, which can result in what electrical engineers refer to as an unauthorized thermal event, which we call a fire. Yikes!

But look around you. You're probably sitting right next to some wires right now, very few of which (hopefully) are on fire, even though they are carrying variously large loads. How do they keep from burning up? The answer is in the proper selection of the right *size* of wire for the job. Bigger wires have less resistance to the flow of electricity, so they are able to carry more power with less heat being produced.

Now, you don't want to have to wire up all of your electronic circuits using jumper cables from your car's trunk, as that gets to be cumbersome after a while. Let's look at some good guidelines for what size wire to use for your projects.

In Chapter 2 you learned about (or were reminded of) Ohm's Law, which illustrates the relationships between voltage, current, and resistance in any electrical circuit. In summary, V = I × R, where V is volts, I is current in amps, and R is resistance in ohms. It's not just a good idea, it's the law!

So how much electricity will we lose going through a foot or so of 16-gauge wire? If we know that one foot of 16-gauge wire has a resistance of 4mΩ (and we know this from looking it up in the chart), and we build a circuit that pushes 1A of current through this wire, we can figure out a couple of interesting things using Ohm's Law and a calculator.

Applying Ohm's Law

If you know two of the three variables used in Ohm's Law, you can calculate the third variable. Since we know R and I, we can calculate V. Since V = I × R, we can substitute our values of 1A and 4mΩ (0.004Ω) into the equation, and get 0.004V, or 4 millivolts.

That's not very many volts at all! In this case, that's a good thing. The voltage we just calculated is the *voltage drop* across the length of the wire. Those millivolts never make it from one end of the wire to the other—they're lost. Poor millivolts, they never had a chance.

OK, let's not let their heroic sacrifice be in vain. If we know volts, and we know amps, we can also calculate power, which is the rate at which energy is converted to work. The unit of measure for electrical power is *watts*, and is also the same as Joules per second (J/s), but that's another story. We usually use the capital letter *W* to abbreviate wattage, but we use the capital letter *P* to represent the *value* in equations.

Calculating power is simple if you know the volts and the amps. Just multiply them together: P = V × I. Easy.

So in our example so far, we have 4mV, 1A, and 4mΩ. How much power is being dissipated (wasted) in this circuit? P = 0.004V × 1A = 0.004W, or 4 milliwatts, which is just four-thousandths of a watt. That's just about enough power to light up a dim LED, and not much else. So you're not going to be starting any fires with these numbers. You most likely would not even be able to measure the rise in temperature that is occurring in the wire (oh yes, it's occurring, but it's very, very small).

Let's put 10A through a foot of 30-gauge wire. On second thought, let's not, and just do the math instead. The voltage drop will be V = I × R, or 10A × 0.1032Ω = 1.032V. The power dissipated would be P = V × I, or 1.032V × 10A = 10.32W. That wire would be a crispy critter in no time. Ten watts doesn't sound like much when you're talking about a home stereo or a lightbulb or a hair dryer, but that skinny little wire has almost no surface area with which to dissipate the generated heat. This means that the temperature goes up, quickly. Bye-bye, little piece of wire.

As a side note, you just learned how most current-limiting fuses operate. The conductor within the fuse literally *fuses*, or evaporates, when the internally generated heat produced from an "overcurrent" situation rises beyond its melting point. Poof, the circuit is opened, and property and lives are saved.

■ **Warning** Never circumvent the protection afforded by a fuse.

Ideally what you want is the smallest wire that will carry the required amount of current with an acceptable rise in temperature. Remember that any rise in temperature is in addition to the *ambient* temperature. If you're sitting in a room that is "room temperature," which is assumed to be 25°C or 77°F (the same thing, if you want to check it), and you're expecting a 50°C rise in temperature due to waste heat, your wire is going to be 75°C, which is far too hot to touch. Remember that 100°C is the boiling point of (pure) water (at sea level). Hot!

One more thing that complicates the thermal calculations is that copper, as a conductor, has a *positive thermal coefficient*, meaning that the characteristic resistance of a piece of wire (which we can look up in the AWG table) goes *up* by a known amount as the temperature increases. You need to consider this when you build circuits that are *supposed* to get hot, such as electric heaters. In most other cases, it's best to keep the heat to a minimum, as it represents wasted power, plain and simple.

Testing Your Wires

Can something as simple as a wire go bad? Yes, it most certainly can. How can you tell? Usually, it's because something doesn't work the way you think it should, or *worse*, it works sometimes and not others. A great deal of time, the problem is right at the end of the wire, where it is trying to make a connection with something else. However, it's possible for a wire to develop a problem right in the middle. This can be caused by a tiny nick in the insulation that lets in nasty elements such as rain and dirt, allowing the inner conductor to corrode. This type of problem takes time to make itself apparent, but it can certainly happen, especially in equipment that is exposed to the outside world for any length of time.

A quick way to test a wire is with a piece of test equipment called a *continuity tester*. This simple device usually is battery powered and has two probes. When you connect the probes together, the tester makes a noise, lights up a light, or maybe does both. Make sure your continuity tester's batteries are fresh and that the probes, if they are removable, are firmly seated in their sockets. Even test equipment needs testing from time to time.

■ **Note** A continuity tester is one of the easiest pieces of test equipment to cobble together yourself. See Appendix A for more information about building your own tools.

As mentioned previously, the problem is almost always at the very end of the wire. This is a good thing to know, so you can start looking in the most likely places first, saving valuable troubleshooting time.

A much better way to test a wire is with an ohmmeter. Using an ohmmeter, you can determine the *exact* amount of resistance in a wire, which under ideal circumstances should be very low. One ohm or less is typical for most normal-sized wires that you are likely to encounter. Super-long wires can have higher resistance, and that's where you can consult the handy AWG table to find out what the resistance is *supposed* to be.

When testing wires, especially wires with attached connectors, it's a good idea to wiggle the wire about vigorously, as this will reveal some intermittent connections for you.

Storing Your Wire

If you're buying new wire, it will probably come on a reel. It's often handy to keep common sizes and colors on your bench, if you have room. A paper towel–holder makes an excellent wire dispenser rack, although you can also spend more time or money buying a prebuilt one or designing and fabricating your own.

A custom red-and-black wire dispenser is shown in Figure 3-4. You might use a fixture like this if many pairs of identical-length wires are needed for a project. Not having to chase the wire spools all over the bench really saves a lot of time. This structure was built using a MicroRax miniature slotted aluminum extrusion (*http://www.microrax.com*), which is perhaps a bit of overkill, but was a lot of fun to plan and build. A coat hanger, artfully bent, would have also done the trick.



Figure 3-4. *A custom wire-dispensing frame made from modular aluminum extrusion. This kind of fixture makes it easier to cut both a red and a black wire to almost exactly the same length, which happens a lot when you use red and black wire for positive and negative power connections, respectively.*

Connectors

Connectors make life easier for the casual wiring enthusiast. The hardcore types solder everything together, but that is not always practical or even the right thing to do in every circumstance.

Keep in mind that every connector, just like every wire, has some sort of electrical limits. These limits must be respected.

Clip Leads

Also called *alligator clips* or *test leads*, you can buy ready-made wires or build your own from individual connectors. The flexible rubber or plastic boot extends the insulation of the wire. A spring-loaded jaw, often with serrated teeth, is used to clamp down on the wire, lead, or electrical terminal desired (see Figure 3-5).



Figure 3-5. *Clip leads come in all sizes, gauges, colors, and terminal types. They are handy for making quick electrical connections.*

Clip leads are quite handy to have around your bench, if you've got the room for them. They tend to get tangled up, so some people hang them from a specially slotted rack, making them easier to pluck at a moment's notice.

Keep in mind that clip leads are generally for *temporary* electrical connections, such as when you're testing something or trying out a prototype circuit. They don't make very good long-term solutions to your electrical connection needs for a variety of reasons.

The first problem is that even when the spring-loaded jaws make a solid, low-impedance connection when first attached, this electrical connection will deteriorate over time as oxidation inevitably forms on the contacts.

Another problem is that many mass-produced clip leads are inexpertly smashed onto the ends of wires, without taking advantage of the alligator clips' built-in features, such as strain reliefs and soldering points. This leads to additional resistance in your circuit at both ends of the clip lead, where you would probably never think to look. The next time you buy some brand-new clip leads, hook them up to your ohmmeter and see just how conductive they really are. A good practice is to carefully remove the insulating boot and make a proper electrical connection yourself, so that you've got one less thing to worry about.

Solderless Breadboards

A very versatile prototyping platform is the solderless breadboard. Once upon a time, people would tack together simple electrical circuits using wires, small nails, and a hammer, utilizing a wooden plank or small board as the substrate. The kitchen breadboard was often just right in size and weight and would mysteriously disappear into the workshop. You can still cobble together simple circuits using this technique.

The solderless breadboard is a miracle of modern manufacturing techniques. A body made of precision-molded plastic has an array of small openings built in, and within each opening is a row of small spring clips that are just the right size to grasp and hold a small-gauge (22–26 AWG) wire. Adjacent points within the array are electrically connected together, which lets you easily connect small components into a circuit using your bare hands, with no soldering required. About all you would normally need would be some solid-core wire (preferably), some wire cutters, and some wire strippers. You can even buy precut jumper wires specifically made for use with solderless breadboards. They're terrifically handy! See Figure 3-6.



Figure 3-6. *On the left is a solderless breadboard with 830 tie points. Each hole has a spring clip inside that can hold a small wire or component lead. On the right, the underlying electrical connections between the tie points are illustrated.*

The spacing between adjacent tie points is exactly 0.1", which corresponds to many common "footprints" for electronic components. You can easily build simple circuits in just a few minutes. You can even build fairly complex circuits using integrated circuits and other components. Figure 3-7 shows a complete Arduino-compatible microcomputer that you can build with your bare hands and then program using your PC and the free Arduino software.



Figure 3-7. *A breadboard Arduino, which is compatible with the popular Arduino Duemilanove microcontroller, can be built using just a handful of components on a solderless breadboard, leaving plenty of room for more experimentation. The black, rectangular component in the upper-left corner is a miniature USB adapter that supplies power, and provides communication and control signals for the microcontroller.*

You'll find that projects tend to expand to fill the available area (and budget). See Figure 3-8.



Figure 3-8. *A prototype LED display with computer control, built on a solderless breadboard. That's a lot of wires!*

Passive Components

Most electronic components fall into one of two different categories: *passive* and *active*. There are a few different ideas floating around as to what, exactly, is the difference between passive and active components. For the purposes of this book, we will use the simple definition that an *active* component requires a power source to work properly, while a *passive* component does not.

Resistors

A good example of a passive component is a *resistor*. You've already learned a lot about resistance in an electronic circuit. Resistance is measured in ohms, and it converts electricity into heat. When you're working with wires, cables, and other conductors, resistance is usually a *bad thing*. You want the least amount of resistance possible. However, there are times when you both want and need resistance in a circuit.

One example of when you would want resistance in a circuit is when you want to light up an LED. Unlike an incandescent lightbulb, an LED has no built-in current-limiting ability. Without a fixed amount of external resistance added to the circuit, an LED would self-destruct in a very short time, because it would overheat from excessive current flowing through it. A resistor would limit the amount of current flowing and control the brightness of the LED.

The exception to this dire prediction is when the power source that is lighting up the LED has insufficient gumption to blow up anything, such as with a small coin-cell battery. Anything bigger than that normally has no trouble convincing the LED to release its magic smoke, without which it can no longer function.

A typical resistor has a fixed resistance and a maximum power rating. The resistance is determined by the material from which the resistor is made. The value of a resistor, as you already know, is measured in ohms, and can range from just a fraction of an ohm (often expressed as milliohms) up to millions of ohms.

Through-Hole and Surface-Mount Resistors

Resistors come in all shapes and sizes. Generally speaking, the larger the surface area of the resistor, the more power it can safely dissipate. A typical resistor that you might work with on a solderless breadboard or on an older PCB is shown in Figure 3-9. These are called *through-hole* components because their extended leads are meant to be formed and threaded through holes that are drilled into PCBs. Also in Figure 3-9, for comparison, are some teensy-weensy *surface-mount* resistors. Surface-mount resistors have no leads and are meant to be soldered directly to pads laid out on the surface of the PCB.



Figure 3-9. *Some through-hole resistors (top) and surface mount resistors (bottom). The surface mount resistors are so small that they are shipped packaged in tape, which is usually wound on reels for automated placement in PCB assembly.*

You can easily form the leads of through-hole resistors by hand or by using a *lead-bending jig*, a small tool with accurately spaced notches. Traditionally, these resistors have their leads formed so as to be threaded through holes in a PCB, and then soldered to the PCB. The extra lead length on the bottom of the PCB is then clipped off. See Figure 3-10.



Figure 3-10. *Resistor leads are bent at right angles and inserted into holes in the PCB to be soldered.*

Schematic Symbols and Reference Designators

The schematic symbol for a fixed-value resistor is a zigzag line. See Figure 3-11. Every component in your circuit should have a name, which is also called a *reference designator*. Typically, most reference designators will have a short letter abbreviation to describe what kind of part it is (*R* is for *resistor*) and a sequential number assigned as more parts are added to the schematic. R1 would be the first resistor, R2 would be the second resistor, and so on.

If there is only one resistor in your circuit, then you don't have to number them, do you? You can just called it *R*, or *Galactic Emperor R the Mighty*, or whatever strikes your fancy. Most people stick to simple numbers.

Your numbering scheme depends a lot on the complexity of your schematic. If you only have a few resistors in your circuit, you can start at one and go up as needed. If you have a complex circuit with many subcircuits, you might allocate R101, R102, R103, and so on, to the first subcircuit (e.g., a power supply), and then assigned R201, R202, and so on, to a different section, such as a display. It's entirely up to you. Use a system that helps *you* keep track of things.



Figure 3-11. *The schematic symbol for a fixed-value resistor is a zigzag. The reference designator for this resistor is R1 and its value is 10,000 ohms, or 10KΩ. A simple rectangle symbol is also used to represent resistors, although many components are available in this physical form factor. Use the symbol you like best.*

Standard Resistor Values and Tolerances

Remember how wires have their own peculiar numbering scheme to describe their basic characteristics (i.e., the AWG, which uses *smaller* numbers to represent *larger* wires)? Well, resistors have their own peculiar numbering system as well to describe their electrical properties, or *value*. Even though the *value* of a resistor is measured in ohms and succinctly describes its characteristic resistance, not every possible value is readily available.

Some smart cookies at the Electronics Industries Alliance (EIA; see `http://www.ecaus.org/eia/site/index.html#`) have come up with some standard values that fill in most of the commonly used values for resistors and other components. Their scale is not linear but logarithmic, meaning that it takes larger steps as the values go up. This makes a little more sense once you understand how component value *tolerances* work.

You can buy, for example, a 1Ω resistor and expect it to be pretty close to being 1Ω at room temperature, but it's not going to be *exactly* 1Ω. It's going to be pretty close. How close? Well, that mostly depends on how much money you're willing to spend on this single resistor. If the answer is "not that much," then "pretty close" is going to mean within 5 percent of the stated value. That means your 1Ω resistor could actually measure as little as 0.95Ω or as much as 1.05Ω and still be "within tolerance." Five-percent resistors cost only a few cents even in small quantities.

Given that there's a little wiggle room for each resistor value, people who can tolerate their resistor values being off by as much as 5 percent don't need to be ordering 50 resistors of 0.99Ω and another 50 of 1.01Ω when they could just as easily (and certainly less expensively) order 100 resistors of 1Ω with a 5 percent tolerance.

This overlap in the values of the resistors allows us to skip from 1.0Ω to 1.1Ω without having to keep track of all the little resistors in between. This is because a 1.1Ω resistor could measure as little as 1.05Ω or as much as 1.15Ω and still be in tolerance.

With a standard resistor tolerance of 5 percent, we can use just 24 values to cover the range between 1Ω and 10Ω. The same multiples can then be used to cover the range between 10Ω and 100Ω, and so on. Aren't logarithms fun? See Table 3-2.

Table 3-2. *The E24 Standard Values for 5 Percent Resistor Value Tolerances (Higher and Lower Decades Are Also Available)*

1.0 10		100	1.0K	10K	100K	1.0M
1.1 11		110	1.1K	11K	110K	1.1M
1.2 12		120	1.2K	12K	120K	1.2M
1.3 13		130	1.3K	13K	130K	1.3M
1.5 15		150	1.5K	15K	150K	1.5M

1.6 16		160	1.6K	16K	160K	1.6M
1.8 18		180	1.8K	18K	180K	1.8M
2.0 20		200	2.0K	20K	200K	2.0M
2.2 22		220	2.2K	22K	220K	2.2M
2.4 24		240	2.4K	24K	240K	2.4M
2.7 27		270	2.7K	27K	270K	2.7M
3.0 30		300	3.0K	30K	300K	3.0M
3.3 33		330	3.3K	33K	330K	3.3M
3.6 36		360	3.6K	36K	360K	3.6M
3.9 39		390	3.9K	39K	390K	3.9M
4.3 43		430	4.3K	43K	430K	4.3M
4.7 47		470	4.7K	47K	470K	4.7M
5.1 51		510	5.1K	51K	510K	5.1M
5.6 56		560	5.6K	56K	560K	5.6M
6.2 62		620	6.2K	62K	620K	6.2M
6.8 68		680	6.8K	68K	680K	6.8M
7.5 75		750	7.5K	75K	750K	7.5M
8.2 82		820	8.2K	82K	820K	8.2M
9.1 91		910	9.1K	91K	910K	9.1M

Color Codes

Even the old-fashioned through-hole parts are a bit too small to legibly label with a numeric value and tolerance factor. A system of color codes was developed to designate resistor values, using colors to represent both single digits, a power-of-ten multiple, and the resistor's tolerance. These colors are painted on the resistors in bands. A little memorization and careful practice will have you reading resistor color codes in no time.

For 5 percent tolerance resistors, only four bands are needed to completely specify the resistor's value and tolerance. The first two bands represent the first two significant digits of the value. The next value is the multiplier. The final value is a special case to tell the resistor's tolerance.

The first two bands, as well as the multiplier value, use the color codes shown in Table 3-3 to represent the digits 0 through 9. (Unfortunately, these colors were chosen before the subtleties of colorblindness were widely understood.)

Table 3-3. *The Resistor Color Codes for the Significant Digits and Multiplier Digit of the Resistor's Value*

Digit	Color
0	Black
1	Brown
2	Red
3	Orange
4	Yellow
5	Green
6	Blue
7	Violet
8	Gray
9	White

The last band indicates the tolerance of the resistor using a different set of colors, as shown in Table 3-4. The most common are 5 percent (gold) and 1 percent (brown). There is supposed to be a slightly larger gap between the digits and the tolerance bands, but this is sometimes hard to see.

Table 3-4. *Resistor Color Codes for the Final Color Band*

Tolerance	Color
0.05%	Orange
0.25%	Blue
0.5%	Green
1%	Brown
2%	Red
5%	Gold
10%	Silver
20%	None

The multiplier digit can be thought of as either the number of 0s after the specified digits or as the exponent to which the number 10 is raised, as in scientific notation. Some examples make this easy to understand and remember.

A resistor marked with brown, black, red, and gold stripes has a resistance of 1KΩ with a tolerance of 5 percent. An easy way to decipher this code is to do a simple substitution for the first two digits (brown is 1 and black is 0, so we have 10 so far). Next decipher the multiplier band and write down that many 0s after the first two digits. Red is 2, so write down two 0s. That gives us 1000 so far. The final band is gold, and that means a 5 percent tolerance; 1,000 ohms is usually abbreviated as 1.0KΩ or simply 1KΩ.

■ **Note** *K* stands for *kilo*, the Greek prefix for 1,000. Likewise, *M* stands for *mega*, the prefix for 1 million.

This method works for most values from 10Ω to 10MΩ. A problem occurs, however, when we need to specify a value less than 10, as a negative multiplier value must be used to get an exponent of less than 0. For the value 1 and those less than 10Ω, a gold band is used for the multiplier. For values less than 1Ω, a silver band is used.

To save even more precious space on our schematics, another convention is to replace the decimal point with the multiplier. For example, 4.7KΩ would be written as just 4K7. 1.8MΩ would become 1M8 and 1.5Ω would be 1E5. 10KΩ would still be 10K using this method. If it is clearly understood that the unit of measure is the ohm, then even the Ω can be omitted.

Resistor Power Ratings

Any resistor has a maximum power-handling capability. This rating is usually expressed in watts or fractions of a watt. The larger through-hole resistors shown previously in Figure 3-9, for example, have a power rating of 1/2W (or 0.5W, if you prefer). This means that if you attempt to dissipate more than half a watt of power through the resistor, it is most likely going to quickly overheat and fail.

Thermal failure in a resistor starts with a thin curl of smoke, and then results in the discoloration of the resistor itself and sometimes actual flames. In any case, it gets dangerously hot, so do try to avoid this situation.

If you know the voltage across the resistor, as well as the current, you can easily calculate the power being dissipated using the simple formula P = V × I. Remember that P is the power value in watts, V is the voltage in volts, and I is the current in amps. One volt at one amp is one watt, which is way more than enough to smoke our little resistors. Be careful! Any time you calculate the correct value for a resistor in ohms, be sure to also calculate the required power-handling capability.

Variable Resistors

So far we've only looked at *fixed*-value resistors. They usually exhibit the same resistance day in and day out. That's what we love about them. But what if you need to vary the resistance in a circuit? We have resistors for that, too! A good example is a volume control on an amplifier. Turn it to the left (down), and the volume goes down. Turn it to the right (up), and the volume goes up. How does that work?

One kind of variable resistor is called a *potentiometer*. Potentiometers are sometimes abbreviated as *pots*. Pots usually have three terminals instead of two. Two of the terminals connect to the fixed resistor that is inside the potentiometer. Instead of being all sealed up like the fixed resistors you've been studying, the internal, resistive conductor is exposed along a track or groove. The third terminal, which is often physically in the center, between the two other terminals, is called the *wiper*, and can be moved from one end of the fixed resistor to the other end, making electrical connection to the inner part of the fixed resistor as it goes. As the wiper moves along the length of the resistive element, it taps into the resistor at a different point, varying the resistance. This is how a potentiometer can be used as a variable resistor.

Figure 3-12 shows a typical three-terminal potentiometer with a round body. The shaft can be turned to adjust the resistance. There are many variations on this basic design.



Figure 3-12. *A typical potentiometer, or variable resistor. Image by BG Micro (http://bgmicro.com).*

The schematic symbol for a potentiometer looks suspiciously like a resistor with an extra terminal, which happens to be exactly what it is. The extra terminal is the wiper, shown as the upward-pointing arrow. See Figure 3-13.



Figure 3-13. *The schematic symbol for a potentiometer is a fixed resistor with a wiper terminal. The "CW" arrow indicates which way the wiper goes when the shaft is rotated clockwise.*

Potentiometers generally come with two distinctive *response curves*, or *tapers*:

- A *linear* curve means that every equal step of rotation about the axis changes the resistance by the same amount. For example, if you were to center the shaft in the middle of its rotation, the resistance from the wiper contact to either of the end contacts would be nearly exactly half of the total resistance between the two end contacts. This is quite useful for when you need to adjust a voltage up or down in a relatively straight line. This is sometimes indicated by adding a capital *B* to the end of the resistance value (e.g., 10KΩB).
- In many audio circuits, however, it has been discovered that the human ear is anything *but* linear. A special response curve that more accurately describes this sensitivity is called an *audio* curve or taper. An *A* is used as a suffix to indicate that an audio taper is used for a potentiometer.

Note that linear and audio tapers are *not* interchangeable. If you find some random potentiometers in a parts bin, you can get a quick idea of what you've got by centering the shafts and seeing if the resistance is "symmetrical" or not, using an ohmmeter. Equal resistance to either end terminal indicates a linear taper, and anything else is mostly probably an audio taper.

Just like any other resistor, a potentiometer has a maximum power rating as well as a tolerance. These are usually either printed on the body of the potentiometer, if there is room, or hidden away in a product data sheet somewhere.

Specialty Resistors

There are many different kinds of resistors made for many special kinds of applications. High-power resistors are built out of sturdier materials that can take the thermal stress required to dissipate large amounts of heat. See Figure 13-14.



Figure 13-14. *A power resistor can handle much more heat dissipation than the smaller though-hole or surface-mount varieties. They are often so big that they need special mounting hardware. Image by BG Micro (http://bgmicro.com).*

Another popular option is the *multiturn* potentiometer. These potentiometers have an internal gear system that allows their shafts or wipers to be moved slowly across their internal resistive tracks by multiple turns of the control element. Increasing the number of turns allows the user much finer control of the resistance adjustment. It also takes the user longer to get from one point to another along the scale.

Capacitors

The basic definition of a *capacitor* is two conductors separated by an insulator. By itself, it doesn't sound like that would be a very interesting configuration at all. It turns out, however, that there's a lot more to it.

When a voltage is applied across a capacitor, no steady current flows through it. Remember, there is an *insulator* in the middle of that capacitor. Any insulator, just like the insulation on a piece of wire, *does not conduct electricity*.

What happens is that an *electric field* is created between the two conductors, or *plates*, as they are called when they are part of a capacitor. Now we get back to the fairies and dragons and molecules and so forth, way down deep at the heart of the problem. This electric field is a form of energy. Once it is built up by the difference in voltage, or *potential*, between the two conductors, it has nowhere to go, so there it stays . . . at least until something else in the circuit changes.

For this reason, capacitors are sometimes used as *reservoirs* of electrical energy in a circuit, holding a bit of spark here and there as needed. Just as it takes electrical energy to build up this electric field, a certain amount of electrical energy will be released when the field collapses. This will happen when the voltage between the two conductors drops.

Using capacitors as tiny electric batteries in a circuit is only one of many applications for this versatile part. While a capacitor will not conduct a *steady* flow of electric current between its terminals, it will often *appear* to conduct *alternating current* (as opposed to *direct current*), which is why you see them so often in audio circuits. As a charge builds up on one plate within the capacitor, it then attracts electrons from the other side, pulling them in from the other side. Even though they don't "jump the gap" of the central insulator, it looks like a tug-of-war is going on from both sides.

This behavior can also be used to send the higher-frequency components of a signal one way in a circuit and the lower-frequency components of a signal in another direction. This is one way that analog filters are built, and it has all kinds of useful and interesting applications.

Capacitors come in all shapes and sizes. They are made of many different materials, depending on what particular characteristics are needed. See Figure 3-15.



Figure 3-15. *Some electrolytic capacitors of various sizes and capacities. Both much larger and much smaller capacitors exist and are very common in electronics.*

Schematic Symbols

While there are a large number of special-purpose capacitors that are custom made for certain applications, a very large number of capacitors fall into two broad categories: polarized and nonpolarized. The schematic symbols for both types of capacitors display the fundamental construction of two conducting plates separated by an insulator. See Figure 3-16.



Figure 3-16. *The schematic symbols for polarized capacitors (left) and nonpolarized capacitors (right)*

C1 is a *polarized* capacitor, meaning one terminal is more positive than the other. In practice, this is indicated on the part itself in a variety of ways. One convention is that the *anode*, or more positive lead, is physically a little bit longer than the *cathode*, or negative lead. There is generally some sort of mark made on the capacitor body itself. Usually this is a stripe on the *negative* side of the capacitor.

What's really odd and potentially confusing is that one type of capacitor, specifically that made primarily of tantalum, has a stripe that indicates the *positive* lead of the polarized capacitor. Know your capacitors!

A polarized capacitor that is installed backward will experience terrible physical and thermal stresses and can sometimes explode, sending bits of itself all over the place.

C2 in Figure 3-16 illustrates a *nonpolarized* capacitor. It doesn't matter which way it is installed in a circuit. It is electrically symmetrical and works just as well in either orientation.

Inductors

An inductor is almost always made out of coils of wire. Sometimes inductors are quite large, as with transformers, while other times they are as small as a speck. An inductor would appear, electrically, as a simple short-circuit if it weren't configured to take advantage of certain principles of *electromagnetism*, or the tendency for the flow of electric current in a conductor to form a *magnetic field* around the conductor. The shape and orientation of the loops of wire that compose the inductor determine its electrical characteristics.

In many ways, an inductor is the opposite or complement of the capacitor. While a capacitor does not conduct direct current from one terminal to another, an inductor will happily do so, at least for a time. While a capacitor will resist a change in voltage across its terminal as it builds up its electric field, an inductor will resist a change in current flow across its terminal once it has established a magnetic field.

Because of their complementary natures, the two components can be used together to form a *tuned circuit*—one that resonates at a particular frequency, or allows the passage of only a certain range of frequencies, with the capacitor shuffling the high-frequency portions and blocking the low-frequency portions, while the inductor does the opposite, blocking the high-frequency components and passing the low-frequency ones. This is how many older radios and televisions worked before the advent of low-cost solid-state electronics.

Once an inductor has built up a magnetic field, any drop in the current flow across its terminals will result in the collapse of the field and the generation of a very-high-voltage spike. This is the basic electrical circuit that was used in automobile engines to create the high-voltage spark needed to ignite the fuel-and-air mixture in the combustion chamber.

Inductors can also be used to efficiently pass alternating current via a magnetic field from one inductor to another. This is how the primary windings of a power transformer *induce* a current in the neighboring secondary coil, which, depending on the ratio of windings and a few other factors, determines if the transformer *steps up* the voltage or *steps down* the voltage. It can even keep the voltage the same, for when electrical isolation is needed between two different systems.

Most electric motors employ some sort of inductor that alternately attracts and repels another electromagnet or permanent magnet. The most basic direct-current (DC) motors require a fairly complex mechanical arrangement to perform the necessary switch-swap to alternate the fields. This process is called *commutation*. In other types of electric motors, such as brushless motors and stepper motors, this commutation process is done electronically, externally to the motor itself, and requires more complex circuitry to control the speed and direction of the motors. See Figure 3-17.



Figure 3-17. *Some simple DC motors. When direct current is applied to their terminals, they spin. The magic happens with an electrical and mechanical arrangement inside that performs the necessary commutation of the magnetic fields.*

Switches

The most basic way to control the flow of electric current in a circuit it to literally *break* the circuit. This means that instead of forming a conductive loop from power source to components and back again, a gap is introduced somewhere in the loop.

This gap can come anywhere in the loop. It can be right next to the battery, for example, or somewhere off in the middle—as long as the circle is broken, no current will flow.

If you perform the lightbulb experiment in Chapter 1, you can see how this works. When everything is lined up properly and the final connection is made, the lightbulb lights up. When any of the connections are broken, the light goes out. It's really as simple as that.

Most of the electrical switches that you operate every day are really mechanical in nature. Their main function is to physically move two conductors either together or apart.

In the lightbulb experiment, you could use the wire as a switch, by physically touching either the battery terminal or the lightbulb (depending on how you were holding everything together). With a little practice, you could probably send Morse code, or at least a variation on "one if by land, two if by sea."

There are many kinds of switches for many kinds of switching tasks. The most basic are *momentary action* switches. These are usually push buttons, and only conduct electricity when pressed. Alternately, they can be built so that they conduct electricity all the time, *except* when pressed:

- The first option is called *normally open*. When a circuit is open, it is not conducting electricity. When you *close* the circuit, by completing the loop, electricity can flow. A normally open switch would be welcome in a doorbell circuit. When no one is pressing the button, no bells are ringing. It would be annoying the other way around.
- A *normally closed* switch acts like a solid piece of wire (being a conductor of electricity) until it is activated, when it ceases to provide a path for the electricity to follow. This type of switch can be used as a *kill switch* on a gasoline-powered engine, such as a lawn mower, for example. By interrupting the flow of electricity generated by the magneto and powering the spark plug, you interrupt the internal combustion cycle, which will eventually cause the engine to slow down and then stop.

This type of switch is called a *single-throw* switch. It's either on or it's off—conducting electricity or not conducting electricity.

■ **Note** For almost every possible configuration of switches, there is a corresponding *opposite* configuration that is almost as popular.

Another useful configuration for a switch is to switch from one circuit to another circuit, and not just on and off. This is referred to as a *double-throw* circuit. A switch like this normally has three terminals. A *common* terminal is usually, but not always, in the center. At any rate, the common terminal is electrically connected to the moving part of the switch that is going to make contact with one or the other two remaining contacts. The *normally closed* contact is the one that will be making contact with the common terminal when the switch is not activated, or at rest. The *normally open* contact is simply the other terminal. This assumes that the switch has some sort of bias or mechanical spring action that returns it to a certain orientation when no one is activating it.

Some double-throw switches can remain in either state indefinitely. A typical light switch used in indoor lighting is a good example. It's just as happy to stay on as off.

Switches can have more than one circuit built into them. These switches are called *double pole*, *triple pole*, and so forth. They're like two or more single-pole switches physically taped together, so that when one is switched, they all are switched. Usually these poles are electrically isolated from each other.

We'll play with switches again in Chapter 5, where you'll learn some interesting ways to wire them up.

Active Components

While it could truthfully be said that *all* electronic components require some electricity to do anything, the distinction made in this book between *passive* and *active* components is that *active* components need a little more power to be really interesting.

First we'll look at sources of this magical electricity, and then we'll move on to some of the fascinating and complex components that will happily use it all up for you.

Power Supplies

You're going to need some sort of power source for any electric or electronic circuit you run across. If it doesn't use electricity in some structured form, it's not really electronics, now is it?

Batteries

You can use regular batteries to power a lot of your circuits, but they eventually wear out, and then you have no real recourse other than to throw them away or recycle them, if possible. If you're going to be using batteries, at least get some good ones. Many of the bargain brands are terribly inferior in their manufacture and are only providing you with a false economy. Spend a little more and get higher-quality parts, and you will be rewarded with longer life and more reliable operation.

A great way to work with batteries is to use the appropriate battery connectors or battery holders. Sometimes you can remove these from obsolete electronic devices that have outlived their useful lifetime. Always observe the proper orientation and polarity of batteries. Even smaller batteries contain an annoying amount of power, especially when it all decides to come out at once, such as when you accidentally plug something in backward or short something out. This can result in damaged parts, burns, or even fires. Be careful with batteries.

Having a fuse holder wired inline with your battery-powered supply is an excellent and cheap way to prevent such "unauthorized thermal events." Keep several spare fuses on hand as well. Fuses cost little and save much.

Rechargeable batteries are becoming more common, and they keep coming down in price while improving in longevity and power capacity, and decreasing in size and weight. Any rechargeable battery technology beats any kind of primary, or nonrechargeable, battery in the long run.

■ **Caution** The same warnings about battery polarity and fuses apply to rechargeable batteries as well.

Since there's no easy way to "turn off" a battery, it would be a good idea to include a power switch in your supply, if possible. Just make sure that whatever switch you select can stand up to the maximum current you will want to be extracting from your power supply. You should also make your switch large and easy to see, so that you can find it quickly when you need it. An obvious power-on indicator is also a great plus for a homemade power supply. This can be as simple as a green LED (with appropriate current-limiting resistor—see below) or as complex as a voltage meter indicating how much juice is left.

Transformers

Another great power supply that you probably already own is a power adapter or transformer from another electronic appliance. You should use caution, of course, with anything that plugs into the wall for power, especially if you're planning on monkeying around with the other end of it.

Almost all commercially produced power adapters have a slew of certifications plastered on them. Somewhere in there should be the basic data concerning what type of power input it expects, what it is going to try to produce, and what the maximum limits are on the output. Make sure that whatever it is that you're going to plug into your wall is specifically designed to plug into *your* wall, as electrical power standards vary from one location to another.

Make sure that any repurposed power supply you use does not get overly warm when in use. This is an indication that it is presently or has been overloaded in the past. Such a device is a fire-starter waiting for its magic moment.

You need to know how much voltage is coming out of your power supply. Even if it is clearly printed on the device itself, if you have access to a voltmeter, you need to verify the output voltage before connecting it to anything. Many lower-cost power adapters are *unregulated* and will produce an output voltage that will vary wildly depending on the load applied to it. A *regulated* voltage output, on the other hand, will provide consistent voltage levels on the output, even with varying loads.

USB adapters and chargers are becoming quite common and can provide *regulated* +5V at up to 1/2A and sometimes more. These are great devices to use for small electronic experiments. They are generally small, lightweight, and reliable.

A dedicated bench power supply is a very handy piece of test and measurement gear to have available in your lab. A good supply will have a variable voltage and a readout to show you what's going on (or coming out). A step up and you get to set the maximum current that it will supply (to keep things from getting out of control too fast). Additional desirable features include multiple outputs and remote control from your PC.

No matter what kind of power supply you use, use it responsibly. Don't leave equipment powered up if you're not using it. Don't attempt to bypass safety measures that are in place for *your* protection.

Diodes

A diode is a semiconductor device that will conduct current in one direction only. That's the simple story. Of course, the reality is much more complex. A typical diode is composed of two pieces of a semiconductor material, usually silicon, but sometimes germanium or some other exotic substance. The diode action occurs in the *junction* between the two types of semiconductors, which have been specially manufactured to contain the exact right balance of impurities required. This is generally not the kind of thing you can build in your lab, unless you're Jeri Ellsworth.

These two bits of semiconductor, called the *N region* and the *P region* (for negative and positive, respectively), are sealed up in either a glass or plastic enclosure. A standard diode has two terminals—an *anode* and a *cathode*—which represent the positive and negative leads, again respectively. Conventional current (i.e., current flowing from the more positive voltage to the more negative voltage) can flow through the diode from the anode to the cathode, but not the other way around. It's magic! Well, technically it's semiconductor physics, but either answer will serve for our purposes.

Diodes come in all sizes. Generally speaking, the more power a diode is expected to handle, the larger it is going to be. *Small-signal* diodes are the same size or smaller than typical resistors. Power diodes, often called *rectifiers*, depending on their application, can be so large they have to be mounted with large bolts.

The two most important electrical characteristics for the happy care and feeding of diodes are their maximum reverse voltage and forward current capability. You don't want to exceed either one.

Since a diode is, at best, only ever going to have a cryptic part number written on it, you'll need to consult the manufacturer's data sheet to find out all the necessary information. Many semiconductor producers offer "commodity" parts that conform to standard part numbering schemes. That way, you know that a 2N4148 diode from one manufacturer is going to be pretty close to a 2N4148 diode from any other manufacturer, but you should always check to make sure.

Diodes typically have a *forward voltage* that must be exceeded before current will flow. This voltage is essentially lost and is dissipated as waste heat from the device. Silicon diodes will have an average forward voltage around 0.7V and up. Germanium diodes will have a smaller forward voltage, in the area of 0.3V. Schottky diodes use a metal-to-semiconductor interface region and achieve substantially lower voltage drops, making them much more suitable for higher-power applications.

LEDs

One special kind of diode is the popular *light-emitting diode*. You see these little guys everywhere these days. In fact, some folks go around with black tape, just trying to cover them all up so they can get their darkness back at night.

The reason that they are everywhere is that they are cheap, reliable, and easy to use. They don't take up much room, don't take up much power, and don't generate that much heat. The exceptions to these admirable qualities, of course, are in the newer generation of LED lighting products that emit tremendous amounts of light and produce tremendous amounts of heat. Every month it seems that a new record is set for efficiency. Let's hope that trend continues.

Being essentially diodes, LEDs have both an anode and a cathode. LEDs only conduct current in a single direction. You'll need to make sure you limit the amount of current flowing through your LEDs, because the LEDs themselves sure aren't going to do it.

LEDs designed to be indicator lights can be powered with as little as 1mA. High-efficiency LEDs can be used for illumination purposes and still only draw 20–30mA each. These very modest power requirements make LEDs a favorite for microcontroller projects, as these output power levels are easily handled by most popular chips.

The forward voltage drop across LEDs is typically much higher than for a rectifier or signal diode. In fact, the voltage goes up as the emitted color of the LED goes from the infrared and red end of the spectrum (1.2–2V) up to the blue and ultraviolet end of the spectrum (3–3.6V).

Transistors

A true modern miracle, the semiconductor transistor ushered in the age of solid-state electronics. More than a million individual transistors can be used to build modern computer processors, all on a single chip.

The first types of transistors to be built and used were called *bipolar junction transistors (BJTs)*. This type of transistor is similar in construction to the diode, except that there are two semiconductor junction areas inside.

This arrangement of magic beans allows a small amount of electrical current to be applied to one of the three terminals of the transistor, called the *base*, which in turn allows a much greater amount of electrical current to flow between the remaining two terminals, known as the *collector* and *emitter*.

Two complementary types of BJTs are made, depending on the way that the positive and negative semiconductors are sandwiched together. NPN transistors will conduct conventional current from the collector to the emitter when current flows from the base to the emitter. The opposite variety, called the PNP transistor, does precisely the opposite, conducting conventional current from the emitter to the collector when the base is negatively biased.

Transistors can be used to make amplifiers, switches, current limiters, voltage regulators, oscillators, and any number of other useful circuits. They are generally very low cost, lightweight, and reliable.

As with any other electrical components, you need to be aware of the electrical limitations of your transistors. Even when a transistor is fully saturated and conducting very efficiently, it's still dissipating a certain amount of its energy as heat. Too much heat and say goodbye to your transistor.

A newer type of transistor is becoming quite popular in power circuit applications, and uses a different type of semiconductor property to accomplish its mission. The *MOSFET (metal-oxide–semiconductor field-effect transistor)* has three terminals, just like the BJT. Each terminal performs a similar job, but does it in a different way. The *gate* of a MOSFET is electrically isolated from the conduction *channel* between the *drain* and *source* terminals. However, when a proper voltage is applied to the gate, it creates an electrical field that influences the conductivity of the channel between the drain and the source.

The important differences between BJTs and MOSFETs lie in the type of signal needed to drive each of the transistors and how much power is wasted by being converted to heat. A BJT is a current-controlled device, where more current into (or out of) the base results in more current flow through the device. The MOSFET is a voltage-controlled device, where more voltage applied to the gate increases the current flowing through the channel.

Additionally, MOSFETs typically have much lower on-state resistance than BJTs, meaning they can more efficiently switch higher currents. Finally, MOSFETs have a *positive temperature coefficient*, meaning that they conduct less power as they heat up—which is a good thing. BJTs are subject to *thermal runaway*—conducting more current as they heat up, which in turn generates more heat, and so on, until something snaps, crackles, or pops.

Integrated Circuits

As parts get more specialized, they become less fun. There are a hundred ways to wire up some transistors, resistors, and capacitors, but there's generally only one way to hook up a thermocouple interface chip.

The good news is that it has become much easier for companies to design and build vastly complex chips that can do things for us that, honestly, most people cannot comprehend. And that's OK. We need airplanes that can, mostly, fly themselves. If we had to depend on humans to get everything done, you can imagine what kind of world we'd live in. Humans are notoriously sleepy, hungry, distracted, and forgetful. A voltage comparator chip does nothing but compare two voltages, all day, every day, perfectly, all the time.

Integrated circuits come in an unbelievably wide range of functions, packages, and capabilities. The first integrated circuits were amplifiers. Integrated circuits allowed manufacturers to make chips that have dozens or hundreds of transistors and other parts *all at once*. Just plop that little silicon chip into a plastic package with legs on it, and you're done.

What kind of chips do you need in your lab? Well, that's going to depend heavily on what kind of circuits you're wanting to design, build, or repair.

Many older chips had a standard 0.1" pin spacing that made them easy to plug into a solderless breadboard for prototyping purposes. Most newer chips have been considerably shrunk, because phones and tablet computers are all the rage these days. It's still possible to work with these newer chips, but it almost always requires mounting them to some sort of breakout board or expander that brings out their tiny leads to a more reasonable, and reachable, size.

Acquiring Components

Where do components come from? The same place as everything else—the store—just like food, just like money.

The electronic component manufacturing industry spans the globe. If someone's not putting something electronic together, they're taking something electronic apart.

Once upon a time it took some hunting to find sources for electronic parts. Swap meets and "ham fests" were great places to find components, assemblies, and entire appliances just ready to be hacked, studied, improved, or rebuilt. Now you have to spend time looking for places to *get away* from all the electronic hustle and bustle.

One of the great things about today's Internet is that it takes almost no effort to find both electronic parts and the information needed to use them. The real trick these days is finding the best deal.

If you're strictly a hobbyist, looking to spend some quality time alone or with your kids, learning about electronics and building fun projects, then it just about doesn't matter if you get the absolute, rock-bottom price on every component and tool. Even if you're a budding entrepreneur, you're still in a much better position today to leverage those brilliant ideas floating around in that noggin of yours than you would have been even ten years ago, all because of the ubiquitous nature of electronics and technology saturating our lives. Not only can you get the right tools and the best parts shipped right to your door for a song, you can easily network with knowledgeable folk from all over the globe, contributing ideas and brainstorming across time zones and borders.

Buying New Components

It would be more than a full-time job just keeping up with all of the new tools, parts, software, and hardware that are available today. Even if you could, it would take many lifetimes to make and grow the connections and relationships you need to successfully compete in the global economy.

That being said, a good place to start is in your own backyard. If at all possible, you should deal locally for the things you need. When what you want or need cannot be obtained locally, expand outward until you find it.

While it's certainly nice to be able to find all your needs met close to home, it's also good to know that the world is shrinking every day. The sort of deals and relationships that couldn't possibly have existed in your parents' time are happening right now.

If you are in a position to spend some money on quality tools and components, then by all means do so. You will not regret it. Buying questionable items is like buying your groceries out of some guy's van in a parking lot. Maybe he'll be there next week and maybe he won't.

Even the small fry can get treated like an honored guest when dealing with the right people. The trick is finding the right people. The best way to find them is to ask your friends and others with similar interest where they trade. Ask them how they feel about their relationships with their vendors. Are they just a number? Or are they a partner?

Recycling Used Components

It's really a bad idea to waste anything. In a more perfect world, there'd be no "other" category at the recyclers. Everything would have an exit strategy, especially the complex and fragile toys we're so addicted to these days.

Until that day, try to look at your trash with new eyes. Is it conceivable that someone else might be able to use this equipment, or is it truly past its useful life? Or are you just being lazy?

You can do your part, and you should believe that others are doing their part as well. Take the time to find them, find out what they can offer you, and find out what you have that they might be able to use. You won't know until you ask.

Be careful when harvesting components with which you are unfamiliar. Novice recyclers should give yesterday's cathode ray tube (CRT) TVs and monitors a wide berth. They can retain *lethal* voltages for considerable periods of time after being retired from service. Just leave them on the side of the road. The same goes for microwave ovens, or any equipment that has refrigerant in it. The stuff they use nowadays is quite toxic.

There is a growing surplus of both components and “last year’s models” available to the student of electronics these days. Sometimes it’s worth your time and money just to take something apart to see how it works. Then sometimes you find some useful parts inside that you can use in projects of your own.

Component Data Sheets

Every component ever manufactured has a data sheet. This data sheet contains everything you ever wanted or needed to know about this particular component. It’s probably available right now on the manufacturer’s web site, along with a dozen application notes. If not, then it’s probably available on a university’s computer system in a project folder.

This isn’t always the case, sadly. Past a certain point, it doesn’t make sense to allocate resources to information that no one wants or needs anymore. That point varies with each company, with some diligently archiving their information and others tossing it out the window at the end of the quarter.

When possible, collect and maintain your own private set of data sheets. When you acquire a new piece of equipment, get everything you can find in electronic form and stash it away somewhere where you can find it when you need it. If you’re experimenting with some new components, squirrel away those data sheets, just in case you strike gold.

Have you built something cool? Write up your own data sheet for it! Pretend that you’re still going to be interested in this project next year. Better yet, imagine that *someone else* could take an interest in your work. You’ll be pleasantly surprised at how useful you’ll find this information in the future, after you’ve slept a bit.

Summary

This chapter has covered a lot of different types of electronic components, but it has only scratched the surface of what is presently available.

It’s perfectly possible to spend a lifetime pleasantly tinkering with electronics and never have a clue how any of the underlying principles work. Sometimes all you need is a *practical* understanding of what the different components do in a circuit. Hopefully this chapter has given you a rough outline of what is involved. Ideally, your interest has been sparked enough to pursue more detailed study elsewhere. Good luck and happy discovering!

Now that you’re armed with some basic tools and some ideas about some of the available components, it’s time to get busy building your own lab, one experiment at a time.

The remainder of this book will take you on a journey of trial, error, and experimentation that will help you build the best possible lab for your needs, both for now and in the future.

CHAPTER 4

A Portable Mini-Lab

Having a portable (or at least (*trans*portable) electronics lab comes in handy in several circumstances. Maybe you don't have a place (yet) for a permanent home for all that equipment. Maybe you need to bounce at a moment's notice, heading off on electronic adventures at the drop of a hat. Or maybe you like to keep everything where you can find it in a hurry, without having to rummage through shelves and boxes, looking for just the right tool or component.

Whatever your motivation for wanting a portable lab at your disposal, this chapter should help you get started.

Have Lab, Will Travel

First, a note or two is in order concerning *travelling* with your electronics lab. Nothing makes security screeners at an airport or customs inspectors at border crossings more nervous than a bunch of mysterious devices, especially devices that are tangled up in a rat's nest of wires.

Do what you can to keep your collection of tools and components tidy and in working order. You will most likely be asked to at least turn on any questionable items and demonstrate that they are not hollowed-out shells for transporting questionable items. It also doesn't hurt to clearly label equipment as to its function and ownership, which makes sense in any case, not just travel scenarios.

The Compact Executive Model

"A full mongoose is a slow mongoose." This is an important lesson learned from Rudyard Kipling's *Rikki-Tikki-Tavi*. Rikki, a mongoose, has to stay fast on his feet to be able to combat Nag the cobra and hope to win. Therefore, Rikki learns to only take a few bites at a time when eating and never gorge himself.

Although hopefully not in a life-or-death situation like Rikki's, you can learn a thing or two from this simple philosophy. Only take what you absolutely need when travelling, and never take something you can obtain at your destination. These things will only slow you down. Don't be a slow mongoose.

■ **Tip** Travel light.

A slim and lightweight briefcase or attaché can hold many of the tools and components you might need for your mobile electronic experimentations. The main advantage is that you will only need one hand to carry it (leaving one hand free to open doors, bribe guards, or fend off ninja—assuming you have two hands to begin with). See Figure 4-1.



Figure 4-1. *The compact executive mobile electronics laboratory. There's plenty of room for lots of tiny things, but not much else. Also handy for transporting big stacks of cash, should the situation arise.*

Let's take a look at what all you can take with you without a lot of heavy lifting. Starting on the left and moving to the right, we have

- Netbook PC with AC charger and USB mouse (it might be hard to see in Figure 4-1 because it's upside down and covered by other stuff)
- Arduino Uno programmable microcontroller (or *physical computing platform*)
- Folding multitool
- Lighted magnifier
- Digital camera
- Solderless breadboard with lots of precut jumper wires
- Digital multimeter and probes
- Compact single-channel oscilloscope with probe
- AC-powered USB charger—can also be used as a stand-alone regulated 5V power supply
- USB cable
- A variety of LEDs in all shapes and sizes
- Additional passive components
- A variety of batteries, both rechargeable and otherwise, and various battery holders (not shown)
- Static-sensitive integrated circuits and modules stored in antistatic bags
- Notebooks, writing implements, blank media, and documentation
- Your contact information in case of loss

One of the interesting features of this lab is that it is completely self-contained, power-wise. While it's nice to have access to AC power, it's not strictly required, at least for a while. The Arduino and the attached breadboard are powered by the battery in the netbook, via the USB cable. The multimeter has its own 9V battery, while the mini-oscilloscope can be recharged from a spare USB connector. With an extended-life battery, you can expect four to five hours of on-location electronic experimentation.

If your netbook or PC has Wi-Fi or other connectivity to the Internet, you can browse tutorials, data sheets, user forums, and even this book, unless you've already downloaded these items to the internal hard drive.

Have a look at this particular lab deployed and ready for action in Figure 4-2.



Figure 4-2. *The compact executive lab is deployed on a desktop. You have access to lots of electronic building and debugging capabilities in a small area. Using a solderless breadboard helps reduce the number of fabrication tools that you need to carry with you on your adventures.*

The Arduino was included for its small size, popularity, and ease of use. There's a whole world waiting for you inside that little board, waiting to be explored, but that's a story for another day.

You can use the USB cable to extract a regulated +5V supply from your PC for your low-voltage-experimenting pleasure. You can also use an inexpensive USB charger to do the same thing, if you don't feel like hauling a whole PC around with you. Just don't try to draw more than half an amp of current, which is the "official" USB limit for supplying power to USB devices. Technically, *unenumerated* devices (i.e., just a USB cable with nothing intelligent enough to identify itself to your computer) can only draw up to 100 mA (0.1A) of current. A USB charger, on the other hand, is not so picky.

No Soldering Required

One notable omission from this particular configuration is any sort of soldering tool. You could certainly add a small soldering iron, some solder, and a few more hand tools. You'll either need to boot out some of the bulkier items, such as the PC or the full-sized multimeter, or get a slightly bigger carrying case.

The Ever-Shrinking Computing Device

One option that will be gaining momentum in the very near future is the use of tablet computers or smart phones instead of the physically larger laptops or netbooks. They already have a lot of the computing capabilities of reasonably powered portable computers. Also, you can look forward to innovative hardware and software interfaces that will make them more useful in the lab as programmable test and measurement devices. While name-brand products still command a premium price, many no-name or OEM (original equipment manufacturer) products are being sold for a fraction of the cost.

Electrical Experiments You Can Perform

Here are some simple electronic experiments that you can perform using only the tools and components found in the compact executive mobile electronics lab. Start out with something simple and incrementally build on your success. Don't try the most complex problems first. What you want is to build up both your knowledge *and* your confidence at the same time.

Lighten Up, 20th Century Style

Here's an easy experiment that will teach you several interesting things about electronics, believe it or not. You can light up a typical LED using only a lithium coin cell. It needs to be a lithium coin cell that produces at least three volts (marked "3V"), not one of the smaller batteries that only supplies 1.5V, such as a watch or hearing-aid battery, as these will not produce enough voltage to light up a typical LED.

Slide the coin cell between the leads of your LED. There are four possible outcomes, three of which are "nothing interesting happens." Let's start with the least likely possibility, in which the LED lights up. Sometimes you just get lucky.

First Possible Outcome: The LED Lights Up When Attached to the Coin Cell

Figure 4-3 shows the results of this outcome. Notice that the longer lead of the sLED (the positive, or anode, lead) is touching the side of the coin cell marked with a +. No current-limiting resistor is required in this circuit because the battery's internal resistance is sufficient to keep from blowing up the LED. It just happens to work out that way, this time. Most other times, you will need to add a current-limiting resistor to the circuit.



Figure 4-3. *A typical LED lights up when attached to a lithium coin cell. No extra wires needed!*

The other three scenarios? Let's look at them one at a time.

Second Possible Outcome: Nothing Interesting Happens

Why? Because the LED has been installed backward. Alternatively, the coin cell has been installed backward. Remember from Chapter 2 that LEDs are light-emitting diodes, and diodes only carry current in one direction. Therefore, when connected backward, they block the flow of electric current, preventing anything interesting from happening in the rest of the circuit.

Typical lithium coin cells have one broad, flat side that usually has something printed or etched on it, almost always with a + to indicate the positive polarity of the cell. The other side is often textured or rippled in some way to help make better electrical contact when installed in a device. This other side is the negative terminal of the battery.

The LED, being a diode, is *polarized.* It will only work when installed in the proper orientation inside the circuit. Most LEDs will offer one or more ways of easily identifying which lead is which (see Figure 4-4).

- Brand-new LEDs will have extended leads about an inch or so long. One lead will be slightly longer than the other one. The longer lead is the *anode*, or positive lead. The shorter lead is the *cathode*, or negative lead. This information is lost when the leads of the LED are trimmed—for example, after being installed in a PCB.
- Another industry standard for identifying the polarity of an LED is to look at the small ridge or shoulder at the base of the LED body. There will be a flat portion molded into the otherwise circular outline. This flat spot marks the cathode, or negative terminal of the LED.



Figure 4-4. *Typical LEDs in the 3mm, 5mm, 8mm, and 10mm sizes almost always have two polarity indicators. The first is that the longer lead is the positive lead, or anode (top). The second is that the flat side on the base indicates the negative lead, or cathode (bottom).*

On really tiny LEDs, there may be an even tinier mark printed or etched onto the LED to indicate the cathode. You will sometimes need a magnifying glass just to see it!

The quick and easy fix for this problem is to swap the direction of either the LED or the battery. If this still produces no good results, we have to consider some more possibilities.

Third Possible Outcome: Nothing Interesting Happens

This time, after establishing that the LED has been properly oriented with respect to the polarity of the battery, we must entertain the possibility that the battery has been previously depleted. Coin cells have a limited amount of energy stored within them, and this can be easily drained in normal use over time.

A quick way to measure a battery's electrical goodness is to use a voltmeter. See Figure 4-5.



Figure 4-5. *Measuring a coin cell's electrical goodness using a digital multimeter. This one is chock-full of goodness!*

If you have a multimeter, be sure to set it to read DC voltage, in the appropriate voltage range (unless you have a fancy "autoranging" meter). Touch one of the meter's probes to one side of the battery and the other probe to the other side of the battery, and see how much voltage is measured. Anything below 3V should be considered depleted and of no further use, as far as electronic-type projects are concerned. The batteries are shiny and round, so they may have a second career in some sort of art project, but otherwise they should be disposed of in a responsible manner.

Also, perhaps because of their very shininess and roundness, they like to be eaten by small children. Don't let this happen! Take whatever steps are necessary to prevent small children from handling or even touching your electronic tools and components. Use extra care when your lab is mobilized.

■ **Caution** No unsupervised children, no matter how adorable, are allowed in the lab!

Fourth Possible Outcome: Nothing Interesting Happens Because the LED Is Defective

This can happen when an LED is subjected to too much current and the tiny, tiny wires within the plastic body overheat and fail. It can also occur when the LED has been exposed to the elements and moisture has penetrated the casing, allowing the internal connections to oxidize. This scenario, while within the realm of possibility, is certainly the least likely of the four, unless you are habitually cruel to your LEDs. It's also easy to test, if you have a known-good lithium coin cell handy.

Where's the Resistor?

You might be wondering where the current-limiting resistor can be found in this circuit. It's in there, all right, but it's hidden within the battery, so to speak. Coin cells are designed to provide tiny amounts of current over a long period of time. You're not going to arc-weld or start your car with one. As such, they have a much higher *internal resistance* than most any other kind of battery. We use this "feature" to our advantage when testing LEDs using just a coin cell, as the maximum amount of current that will normally flow out of the battery is below that necessary to destroy the LED.

A Slightly More Permanent Circuit

You can build a more permanent circuit for the coin cell and LED using a solderless breadboard. If you recall from the "Solderless Breadboards" section of Chapter 3 (see Figure 3-6), a solderless breadboard is an array of spring-loaded tie points, which serve to both physically hold electronic components and provide electrical connections between certain points. Let's build an LED circuit on a solderless breadboard using an LED, a coin cell, a resistor, a jumper wire, and a custom battery holder (see Figure 4-6). Later on, in Figure 4-7, you can see details of the custom battery holder.



Figure 4-6. *A slightly more permanent LED circuit, built on a solderless breadboard. The tie points on the breadboard are labeled left to right with the letters A–E and F–J for the columns. The rows are numbered starting at 1 at the top. The LED's anode, for example, is installed in tie point F3. The power rails on either side are simply marked with + for positive and – for negative.*

Referring again to Figure 4-6, you can see the overall layout of the LEDcircuit. The power rails along both sides of the breadboard are just longer versions of the electrical connections that connect each of the groups of five tie points together. In this example, the right-hand power rails are used, but the left-hand side is not.

The schematic diagram of this circuit shows how simple it is, at least in principle (see Figure 4-7). Can you see the circle?



Figure 4-7. *The schematic diagram of the LED circuit as built on the solderless breadboard. Schematics are intentionally simpler than reality (most of the time) in order to help convey the very basic idea of how things are to be wired and the relationships between the components, without bogging you down in all the inevitable details that are involved.*

The Battery

The symbol for the battery actually looks like the battery in this case. The same symbol is used for most single-cell batteries, even when they are of completely different shapes or proportions. Multicell batteries are usually represented with repeated stacks of long and short lines.

The battery symbol's long line represents the positive terminal of the battery, and the short line represents the negative terminal. Again, it's just a coincidence that the wide side of the lithium coin cell is the positive terminal. The addition of the + sign in the schematic is redundant, but you'd be surprised how many people accidentally reverse this symbol. Better safe than sorry when it comes to electricity!

The Resistor

The battery's positive terminal is connected via a wire (drawn as a simple, solid line) to one side of the resistor. The schematic symbol for the resistor is a zigzag line.

The resistor is labeled "R1" (resistor 1) in this schematic, even though it's the only resistor and could just as well have been labeled "RESISTOR #1," or just plain "resistor." The numeric value underneath the resistor is the component's primary electrical characteristic, at least as far as we're concerned when looking at the schematic. In this case, it indicates a resistor whose *value* is 150Ω. In this simple example, the value of the resistor is quite flexible. A larger value, such as 1KΩ (1,000 ohms) or more, would also work, except that the LED would not shine as brightly. This is because *more* resistance results in *less* current flow, and it's the current flow that makes the LED shine. More current, more shiny.

We haven't specified any of the other important characteristics of the resistor, such as the tolerance or the power-handling capacity. Because this is such a low-power circuit, almost anything will do. When you start to work with really big LEDs that require correspondingly really big power supplies, this becomes a much more critical issue. For now, we start simply.

The LED

The other side of the resistor is connected, again, with a simple, solid line, to the anode of the LED, whose *reference designator* in this schematic is D1 (for diode 1). You could have called it "LED," and future generations would probably have understood your intentions, which should be your overriding goal. Its characteristic "value" in this case is "green." Of course, any color will do, as long as you have the eyes to see it.

The LED's schematic diagram effectively communicates its polarized nature. The arrow indicates the flow of *conventional current*. The flat bar indicates the cathode, or negative terminal of the LED. This corresponds to the flat side of the LED body in this example. The cathode is connected via a wire back to the negative terminal of the battery, completing the circuit.

Can you see the circle yet? Hint: It's disguised as a rectangle. The important point is that it forms a complete loop.

Building the Actual Circuit

Comparing the schematic to the photograph of the completed circuit might not immediately click in your head. Take a look at Figure 4-8 for a slightly different angle, where you can see some more details, such as how the battery is being mounted.



Figure 4-8. *Another view of the LED circuit as built on a solderless breadboard. The battery holder is a modified pin block that has had a couple of its pins removed, allowing the coin cell to fit in on the diagonal. A thinner coin cell could have fit without your having to remove the corner pins. A proper coin cell holder is inexpensive and would provide a much more robust solution to the problem.*

Looking at Figure 4-8, you can see how the positive side of the battery is making physical and electrical contact with the gold-plated pin of the pin block. The remainder of the pin emerges underneath the black plastic molding to make contact with the spring-loaded tie point within the body of the solderless breadboard, which in this case is the negative power rail. The positive terminal, in a similar fashion, makes contact with the positive power rail.

By attaching the battery directly to the right-side power rails, you ensure that your circuits are only a short jumper away from power, no matter where along the breadboard you decide to build them. Handy!

Note that the left-side and right-side power rails are not connected at this time. If you would like them to be, you can easily attach them using jumper wires. See Figure 4-9.



Figure 4-9. *Attaching the left- and right-side power rails using jumpers. By default, the power rails are not connected. There are some situations where you need them to not be connected, such as when using multiple supply voltages within a single circuit. These things happen.*

Now, referring *all the way back* to Figure 4-6 (sorry about that), you should be able to see how the positive terminal of the battery is indeed connected to one side of the resistor. The other side of the resistor, then, makes an electrical connection with the anode of the LED (the non-flat side, when seen from above). The cathode is connected to the negative power rail using a short jumper wire. The negative power rail then completes the circuit back to the battery. The circle is complete.

Note that the resistor could have been placed either before the LED in the circuit (as shown in the photographs) or after the LED. The only important points are that it is in the same circuit, or circle, and that the current must flow through *both* the LED and the resistor. It really doesn't matter which one comes first, especially in this simple circuit. It will only make a difference when you start to do fancy stuff, like adding switches and such to complicate things.

If you're using a different kind of solderless breadboard (and there are a few distinct varieties), you may or may not have power rails available. If so, fret not. You can still make point-to-point connections using more jumper wires. Now you're starting to understand why you were assigned to cut and strip so many jumper wires back in Chapter 2! They should start to be coming in handy just about now.

Multiple Uses for the LED

Now we've moved from the 19th century incandescent bulb to the 20th century LED. What kind of lighting devices will we encounter in the centuries ahead?

One of the nice features of LEDs is that they don't typically require a great deal of power to operate. This is certainly true of indicator-style LEDs, whose only purpose is to be seen as either on or off. We can leave this LED installed right where it is and use it as a handy power-on indicator for future projects. You might be surprised how many heads get scratched in puzzlement, wondering why a newly wired prototype isn't working, only to find out after exhaustive investigation that the power wasn't turned on! Then again, you might not be surprised by this.

Now let's take this perfectly working circuit and break it—on purpose. If we interrupt the circuit, for example, by removing any of the components or their connections, the circuit stops working. To that end, remove the short jumper wire and replace it with two longer jumper wires. Plug in each of the new, longer jumper wires where the two ends of the short jumper were installed. See Figure 4-10.



Figure 4-10. *By intentionally breaking the circuit, we stop the flow of electricity through the components, extinguishing the LED. By reconnecting the longer jumpers (or just touching them together), we reestablish the circuit, and the LED should light back up again. We can use this mechanism to test whether there is continuity in another circuit.*

Now, by touching the two probe wires together, you recomplete the circuit, and the LED should glow in happiness. This is exactly how a switch works. You can use this basic idea to build a continuity tester that lights up the LED when the current flows in the circuit. This is very handy for testing cables and wiring in a more complex assembly.

More electronic experiments, including how to both calculate and measure what's happening in a circuit, can be found in Chapter 5.

The Special Project Portable Laboratory

When you move past the simple joys of lighting LEDs and wiring up tutorial circuits, where do you go and what do you build? How about a robot?

Doug Paradis is an award-winning writer and robot builder. When Doug wants to work on one of his robots, he packs up a small kit of tools and heads over the local robot club, which in Doug's case is the Dallas Personal Robotics Group (DPRG). They meet every Tuesday at the Dallas Makerspace for an informal evening of robot building and socializing. See Figure 4-11.

Figure 4-11. *Doug Paradis of DPRG, arriving at the Dallas Makerspace for an evening of robot building. Doug uses the club's laser cutter and other specialized tools to give his robots that winning edge. He brings his own set of hand-picked tools along with him.*

Figure 4-12 shows what Doug brings with him to work on his robots.



Figure 4-12. *The contents of Doug's portable workshop. A variety of hand tools, precison measurement devices, and fasteners (including tape, tie wraps, and super glue) are easily stored in a small tool bag for easy transport. The comparmentalized storage containers at the upper right contain a large assortment of screws, washers, and nuts.*

Doug has learned the lesson of travelling light. The electronic portions of his robotic creations evolve slowly over time, but the mechanical aspects get a lot of tweaking along the way.

Not everyone has perfected the art of light travelling. See Figure 4-13.



Figure 4-13. *A sort-of-portable robotics lab, with lots of tools and spare parts. One way of looking at this bounteous splendor is "three trips to the car."*

This caravan of tools, parts, and miscellaneous supplies forms the entourage of Kyle the Robot. Kyle is very much a work-in-progress. The basic framework is made of hand-tooled aluminum. The large wheels use O-rings for tires and are driven by 24V gear motors. The 24V supply is made up of two 12V, 5Ah rechargeable lead-acid batteries. Ah stands for amp hours, and represents the capacity of the battery. In this case, it can deliver an amp of current for five hours, or five amps for one hour. The custom PCB holds the electronics for the drive motors and will be controlled by a separate microcontroller that has yet to be added. See Figure 4-14.



Figure 4-14. *Kyle the Robot is a work-in-progress who requires a wide range of specialized tools and components. Some new components are being fitted, including dedicated battery voltmeters, fuses, a circuit breaker, and a master power switch. Once the sharp corners are filed off, Kyle will be able to roll around the house, looking for chores to do.*

Summary

As we come to the end of this chapter, you should have some good ideas bouncing around in your head about how you want to pack your mobile electronics lab, what tools and components you *absolutely* must have with you, and how you want them organized. The best way to find out for sure what works for you is to make a few field trips, paying careful attention to what was actually used compared to what you anticipated needing. This will help you whittle down your cargo to the bare essentials, which is what you want. Remember, travel light. Excess baggage is a purely optional curse.

In the next chapter, we'll look at some suggestions for organizing and working in a more permanent setting. This could be a domain as small as the corner of a desk or as large as a warehouse. You will soon discover, if you haven't already, that this hobby, like many other projects, will quickly expand to fill the space available. Try to keep in mind that *you* are the one that ultimately makes the decisions. Effort spent planning ahead of time will help keep the sprawl to a minimum, while helping you stay focused on what you wanted to be able to do in the first place.

CHAPTER 5

The Cozy Corner Lab

Chapter 4 focused on the needs of the travelling electronic adept. Here in Chapter 5 you can come home to a lab that is always ready and waiting for some electrical fun and doodling. Nice!

You don't need an entire garage or extra office for a functional laboratory for your electronic endeavors. It's certainly nice if these areas are available to you, but you might be surprised at how much you can do in just a small space, if you set it up properly and maintain it with determination.

The first part of this chapter will deal with the task of rehabilitating a small, dedicated work area that has succumbed to years of poor organizational habits. These things happen. The second half of the chapter explores the possibilities of starting afresh with a nice, clean space—either something brand new or just newly cleaned. Some more projects help break in your new work area, as well as familiarize you with more interesting information about some of the basic electronic components reviewed in Chapter 3.

The Rehabilitation of a Small but Useful Area

Let's perform a little magic, in the form of a complete makeover for a small workstation. Have a look at Figure 5-1. Don't let this happen to you!



Figure 5-1. *A workstation that has been in continuous use for several years. Not much planning went into the original organization of this work area. Such a space can often accumulate flotsam and jetsam that might have at one time seemed appropriate, but now just competes for precious space. The effective work area is down to only a few dozen square inches! This limits the scope of projects that can be comfortably undertaken. It also causes unnecessary delays in rooting around for tools and parts. It's not pretty and it's not safe.*

Where to begin? Like any other project, this big project is made up of many smaller projects, none of which are especially difficult, if approached in the right order and with the right attitude.

If you're starting from scratch with your electronics lab and don't want to wade through this mess, jump on over to the "Adding a Power Source" section of this chapter.

Science to the Rescue!

Let's use the science of *taxonomy* to help break down this task into smaller, more manageable jobs. Taxonomy comes from the Greek words for "arrangement" (*taxis*) and "method" (*nomia*). That sound like *exactly* what is needed here! An "arrangement method" would assist in building up a plan for attacking this project.

■ **Tip** Method plus rigor equals success! Have a plan, pursue it with determination, and you will succeed.

Let's break down the overall category of "big mess on table" into two major *taxa* (singular: *taxon*), or categories. Ideally, what we will find here are *tools* and *components*. There will be other bits and pieces that don't easily fit into one category or the other (or will maybe fit into both), but it gives us a place to start.

Organization

Divide and *conquer*! These are the two words that will help us through the ordeal of rehabilitating this workspace. We'll get to do a lot of dividing here, and end up as conquerors. The spoils will be a useful (and tidy!) work area that will encourage you to begin new electronic adventures, instead of scaring small children.

The Great Divide

It would be possible to reorganize this workspace *in situ* (i.e., in place), but it would require a great deal of inner peace and lots of patience. Lacking these, a complete reboot is in order. Let's clear off the entire table and start afresh. This will provide the excellent opportunity to arrange things in exactly the best possible order.

First, get two big containers. These can be cardboard boxes or plastic storage bins—it really doesn't matter. We'll just be using them as temporary staging areas as we make like an embryo (and divide and divide again). See Figure 5-2.

Figure 5-2. *Two large cardboard boxes are enlisted to help with the initial organization of the contents of the tabletop. One will be for tools and the other one for components. Further subdivisions will be made later.*

Now, the first thing you will want to do is remove any items that really don't belong in the lab at all, such as coffee cups, personal effects, and any obvious trash. Everything that is about to go into one of the two boxes should eventually find its way back to the work area, so now is the time to omit the things just don't belong here.

Is it a tool? Is it a component? How do we tell? Ask five people and you will get five different answers. For the purposes of this little endeavor, a *component* is something that will become a part of a project, while a *tool* is something that is used to modify or manipulate a component. Another way of looking at it is that components get used up quickly, while tools get used up slowly. If you build enough projects, you will be lucky enough to see exceptions to these guidelines.

Here are some examples. Wire is a component. Wire cutters are tools. That was easy. A flashlight is a "visual inspection aid," so it goes under the category of tools. Batteries for the flashlight are consumable, so they are components. There's no real need to be ultra-precise at this point. Use your best judgment and make up policies that make sense to *you*.

It might help, from a physical logistics standpoint, to use smaller subcontainers to hold the really small bits as you're lumping them into the two broad categories. Folding cardboard bin boxes are handy both on the tabletop as well as on shelves, if you have them. The cardboard bin boxes shown in Figure 5-3 are from Uline (`http://uline.com`), part numbers S-16268 (4" wide) and S-16269 (6" wide).



Figure 5-3. *Folding cardboard bin boxes help contain some of the smaller bits and pieces during the Big Sort. You can use whatever happens to be available. Some preliminary subsubdivision is going on here. For the most part, the tools are on the left and the components are on the right.*

After everything is removed from the table and the cardboard boxes are nearly full, the table itself should get a good washing. Behold the *tabula rasa* (blank slate) depicted in Figure 5-4.

Figure 5-4. *The tabletop has been cleared of tools, components, and various bits of debris. A good washing with soap and water completes the cleansing. A burned spot (the result of a poorly supervised thermal test) is covered with a small sticker (see inset).*

Adding a Power Source

Here's where a bit of planning will save you a lot of headaches in the future. What you never seem to have enough of in any laboratory, especially electronics labs, are lots of conveniently located power outlets. Let's take care of that issue right away, before building anything else onto the tabletop. See Figure 5-5.



Figure 5-5. *A 12-outlet power strip is attached to the back edge of the tabletop. This will provide a safe and convenient source of power for all those gadgets you'll eventually want on your bench. Tools needed for the job include a drill motor to drill out some small pilot holes for the brackets, a small drill bit, and a felt-tipped marker. Before drilling the pilot holes, align the brackets where you want them to go and use the marker to put a dot where the pilot hole should be drilled. Make sure the power strip is not plugged in when you're drilling right next to it!*

Having lots of extra power outlets is a nice bonus, but is not absolutely required. What you want to avoid, however, is excessive daisy-chaining of power strips and extension cords. This is a fire hazard. Remember from Chapter 3 that every conductor has a certain amount of resistance. This resistance turns electricity into heat. Enough heat makes things catch on fire.

If you do have the luxury of being able to mount a permanent power strip (which, technically, remains a temporary power tap as far as the manufacturer is concerned), then be sure to install it securely using the hardware provided. See Figure 5-6.



Figure 5-6. *The power strip is fastened securely to the table using the provided hardware. You do not want your power strip wiggling around, or worse yet, falling off the table, dragging all of your power tools with it!*

■ **Tip** Test every outlet of your power strip before permanently mounting it to your workbench.

A Clean, Well-Lighted Space

You can never have enough light, it seems. What passes for normal room illumination might be sufficient for such adventurous undertakings as finding your way to the door or looking for the remote control for the television. For anything more demanding, you're going to have to add some more lighting, and probably lots of it.

At a minimum, you are going to want some *task lighting*, which helps illuminate the immediate area of your focus. In this case, where a small table is being used as a workbench, an articulated fluorescent lamp with a built-in magnifier will do a great job, at least until more lighting can be strung up. See Figure 5-7.



Figure 5-7. *You will need some task lighting for your bench. This desk lamp also includes a handy magnifier for really close work.*

Tools

Now we're ready to bring some of the tools back in to the lab. Here's where you get to decide which tools get a *permanent* home on the bench and which ones get put up and stored when not in use.

The permanently deployed tools on your workbench should be the ones that you find that you are using the most. The ones that get put up after every use are the ones that either only get used infrequently or pose some sort of hazard, such as sharp edges or hot surfaces. Again, you get to decide. It's your lab.

Tools for Soldering

An activity that is practiced frequently in many electronics labs is soldering. If you haven't learned how to solder yet, you are strongly encouraged to do so. Here's a handy setup for soldering, sitting in one corner of the newly refurbished workbench. See Figure 5-8.



Figure 5-8. *A temperature-controlled soldering station with a stand for the soldering iron, a water bottle to wet the tip-wiping sponge, and some different kinds of solder. Some people prefer to have the soldering station nearer to the front edge of the table. Use whatever configuation makes the most sense in your lab.*

■ **Caution** Soldering irons are hot and can cause serious burns. Do not place a soldering iron where you might accidentally knock it off the work table or brush against it.

Hand Tools and Some Test Equipment

No matter what you work on at the bench, you will most likely discover the need for some common hand tools. When working with electronics, especially, you will often need wire cutters, wire strippers, and small pliers. These tools have been laid out conveniently (for a right-handed person) at the lower-right-hand side of the bench, while the less-often-used hand tools can reside in a box.

A regulated, adjustable bench power supply is also very handy when working with electronics of all kinds. A good, reliable multimeter can also claim a permanent home on the bench, as these will get a lot of use. See Figure 5-9.



Figure 5-9. *A clean bench with just enough tools to have some fun. Extra soldering supplies, including more kinds of solder , extra soldering iron tips, soldering flux, and an emergency backup soldering iron, sit in a box adjacent to the soldering station. Hand tools and basic test-and-measurement equipment complete the set of "most-useful tools." There's still room for a few more, when you need them.*

Under the Desk

If your workbench has the luxury of drawers, by all means use them! Try to keep your under-desk environment as free of clutter as possible. It's not really a very convenient place to store unused tools or components. You're going to drop the occasional item from time to time, so having to dig out a bunch of junk just to find it is just going to be more frustrating for you. Keep it clean!

You *should* keep a medium-sized trash can under or near your work area, as you will inevitably generate some waste products in this hobby. By minimizing the amount of food-related garbage deposited in your laboratory trash receptacle, you can postpone the invasion of little critters looking for a free meal. Also, bits of wire and old components don't tend to stink after a few days, but a half-eaten sandwich might.

■ **Tip** Copper easily recycles at a premium price. Collect your copper wire snippings and cash them in someday.

A nice addition to the under-the-table accessories you might consider is some low-wattage strip lighting. LEDs are especially good for this. You will appreciate this more once you conduct your first search-and-rescue mission for that teensy-tiny component that dropped off the edge of your table and into the carpet.

Components

Most of our tools are now ready to go. The most frequently used tools are permanently set up, ready for action. The less frequently used tools are carefully stored where we can get to them when we need them, but are not in the way the rest of the time. This is a big improvement over the situation you saw back in Figure 5-1.

Now we need some components with which to work, using our scientifically arrayed tools. Have a look at Figure 5-10 to see one example of how to keep your parts organized yet within easy reach.



***Figure 5-10.** Parts bins are used to organize components. This style of container is available in many sizes with different numbers and sizes of drawers. Even more parts are stored on a shelf behind the work area. The most commonly used hand tools are laid out on the right. The other hand tools are collected in a small toolbox on the left.*

Where to Go from Here

This work space could be further augmented with shelving, both above the work surface and underneath. More lighting wouldn't hurt, either. However, this is plenty to get started. Let's build some electronics projects on this squeaky-clean table and see if we can dirty it up a bit.

Projects

Let's look at a few smaller circuits you can easily build on your tidy, new work area using a solderless breadboard. Expanding on the LED-and-coin-cell experiments in Chapter 4, we'll add a few more components and hopefully start to see how they all interact.

There are any number of different types of solderless breadboards available today. A range of them is shown in Figure 5-11.



Figure 5-11. *Different sizes of solderless breadboards, all with the same lead pitch and internal connections. The small black unit in the center is perfect for little circuits with only a few small components. The white unit on the left has more tie points and offers power rails along each side. The deluxe, powered unit on the right adds even more space, as well as multiple regulated power supplies for all your tinkering requirements.*

Parallel and Series Circuits

The circuits presented so far have all illustrated the “loop” characteristic of electrical circuits. Electricity generally flows in a circle. It’s possible to have more than one path through a circuit, however. What happens then?

Like most good questions, the answer is, “It depends.” Let’s hook up *two* LEDs at once and try to figure out exactly what’s going on. Figure 5-12 shows how it’s put together. See Figure 5-13 for the schematic diagram.



Figure 5-12. *Two LEDs are illuminated at the same time. This simple circuit demonstrates both parallel and series electrical circuits. A 3×AAA battery holder with an integrated power switch is used to provide power to the circuit.*

To build this circuit as shown, you will need the following components:

- A solderless breadboard with power rails
- A 3×AAA battery holder (which holds three AAA cells) and three fresh AAA cells—rechargeable cells are better
- Two LEDs (any visible color will do
- Two 100Ω 1/4W resistors
- Two short jumper wires

Using the letters printed on the breadboard to find the columns across the top and the numbers to find the rows, we can describe each of the tie points using a single letter and a number, such as A-1 or B-2. The following exercise shows how to put it all together.

ASSEMBLY INSTRUCTIONS

1. Install the top LED with its anode (longer lead) in tie point F-11 and the cathode in tie point F-12.
2. Insert one of the resistors from the red power rail on the right at row 11 across to tie point I-11.
3. Connect the right-hand blue power rail at row 12 to tie point J-12 using a short jumper wire.
4. Install another LED just below the top LED, with its anode in tie point F-17 and the cathode in F-18.
5. Install the other resistor from the right-hand power rail at row 17 across to tie point I-17.
6. Use another short jumper wire to connect the blue power rail on the right at row 18 to tie point J-18.
7. Install three fresh AAA cells into the battery holder.
8. Insert the red wire (positive) coming from the battery holder to the red power rail on the right at row 3 (the top).
9. Insert the black wire (negative) from the battery holder to the blue power rail on the right at row 3.
10. If your battery holder has a power switch, turn it on now.

The circuit is now complete. Please verify that both LEDs are illuminated, as shown in Figure 5-12.

Troubleshooting

If both LEDs are not shining at this point, you're going to have to do some troubleshooting.

- The first thing to do is double-check your wiring. Does your breadboard look like the one in Figure 5-12?
- Next, make sure you're using good batteries. If you have a voltmeter, you can test the batteries by measuring their voltage. New alkaline or carbon zinc cells should read 1.5V or more. Rechargeable nickel-cadmium (NiCd) or nickel–metal hydride (NiMH) batteries should read around 1.2V each when completely charged.
- Are the cells properly installed in the holder? Are they in the proper orientation and firmly seated?

- Is the power switch (if available) not in the On position? This happens more frequently than anyone would like to admit. Wiggle the switch back and forth and see if it's only making intermittent connection.
- Check the orientation of the LEDs. They will only work if installed in the correct orientation. It only takes a second to unplug them, swap them around, and try them the other way. At these low voltages, it won't hurt them to be installed backward.
- Are your resistors the right value? The 100Ω value is not critical. Anything from 100Ω to 1KΩ will do nicely. Don't use smaller values, as this will allow too much current to flow through the circuit, perhaps damaging the LEDs. How much current? We'll figure that out in just a bit. Larger-value resistors will decrease the amount of light emitted by the LEDs, down to the point where you can't see them anymore.
- Are you sure your LEDs emit visible light? Millions of infrared LEDs are manufactured every month for use in remote controls and night-vision gear. This light is not visible with the human eye, although some digital cameras can see it. Just because it looks like an LED doesn't mean it *is* an LED.

A Different View of the Same Thing

Your version of the circuit in Figure 5-12 might look a little different, and that's just fine. The important point is that both LEDs are lit up at the same time when you apply power.

Let's look at the traditional schematic for this circuit to get an idea of what's going on here. See Figure 5-13.



Figure 5-13. *The traditional schematic diagram of the two-LED circuit. This diagram should convey the very basic information needed to build the circuit, as well as understand the important aspects of how the circuit is supposed to work, without going into much detail at all about the actual implementation or assembly of the components.*

By now you should be able to look at the schematic and see the loop formed by the circuit. The only new twist is that there are *two* paths along which the electricity can flow, either through R1 and D1 (the top LED on the breadboard) or through R2 and D2 (the bottom LED, or the initials of a certain adorable robot from the movies).

The three AAA cells in the battery holder are shown as B1 in the diagram. The power switch, labeled SW1, is shown as a separate component to remind us that the circuit can easily be broken, halting the flow of electricity, which is something we want to happen from time to time. The connections between the two resistors and the two LEDs should be somewhat obvious. I'll discuss the details for the parallel and series connections momentarily.

Remember that an electronic schematic diagram is an abstract representation, boiled down to only the essential items involved and the relationships among them. As such, it doesn't need to resemble the final product, but it could. See Figure 5-14.



Figure 5-14. *Another schematic diagram of the two-LED circuit, showing the approximate physical layout of the components on the solderless breadboard. This style of schematic is often used when describing how to actually build a circuit, showing the constraints of the actual, physical components and the connections between them. It conveys more specific information than the previous example in Figure 5-13.*

Batteries in Series and Parallel

Let's look at the batteries first. Technically, as mentioned in Chapter 1, there is one *battery* in this circuit, and it happens to be composed of three *cells*. The term *battery* is very often used interchangeably with *cells*, and the distinction is minor. It's better to avoid confusion than it is to be exactly, precisely *correct*—usually.

We see three cells sitting side by side in both the schematic in Figure 5-14 and the actual battery holder shown in Figure 5-12. The cells are connected *in series*, meaning that one connects to another that connects to another, and so forth. They are like beads on a single wire. You should be able to trace the wiring (the solid lines) that connects the individual cells in the schematic.

Note the polarity of each of the cells within the battery. The positive terminal of the bottom-most cell is wired to the negative terminal of the center cell. The positive terminal of the center cell is connected to the negative terminal of the topmost cell.

The negative terminal of the bottom-most cell is connected to one side of an *SPST (single-pole, single-throw)* switch. The other side of the switch emerges from the battery holder's body as the black, or negative, lead from the battery pack. The positive terminal of the topmost cell connects directly to the red, or positive, lead coming out of the battery pack.

The switch could have just as easily been installed in the positive lead, and it would have worked exactly the same. The battery holder used in the photograph happens to switch the negative lead, as was revealed by examining the internal wiring using a multimeter as a continuity tester.

When the switch is *open* (i.e., in the Off position), the circle is broken and no electricity is going to flow. When the switch is *closed*, the circuit is complete and power is made available to the remainder of the LED circuit, assuming that it is wired up correctly.

The amount of *voltage* being supplied by the battery holder depends on the electrical characteristics of the individual cells. If alkaline batteries are used, each cell will provide 1.5V, assuming that the cells are relatively fresh. Rechargeable NiCd or NiMH cells will provide around 1.2V when fully charged.

When batteries like these are connected in series, the total voltage available is the sum of each of the cells. Just add all the voltages together. For example, using fresh alkaline batteries, the total voltage would be 3 × 1.5V = 4.5V. Rechargeable cells would provide 3 × 1.2V = 3.6V when fully charged.

If the cells were wired *in parallel*, with all of the positive terminals being connected together and all of the negative terminals wired together, the total output voltage would only be 1.5V for alkaline cells. The total output *current*, however, would be triple the capacity of each individual cell. See Figure 5-15 for a comparison of series, parallel, and combination circuits using batteries.



Figure 5-15. *Different arrangements of the wiring of the batteries produce different results. The top two cells are arranged in series. Their respective voltages are added together. The center circuit consists of two cells arranged in parallel. This configuration doubles the current that can be delivered. The bottom drawing shows a combination of both series and parallel circuits, doubling both the voltage and the current.*

When connected in series, the total current output is the same as the current capacity of each individual cell.

In summary, if you need more voltage, stack the cells end to end. If you need more current, stack them side by side. Even more complex arrangements are possible, using both parallel and series circuits to achieve the desired power output characteristics. This practice is very common in hobby model aircraft and battery-powered vehicles. A designation such as 3S2P means that there are two parallel circuits (2P) of three cells in series (3S).

Looking back at the circuit in Figures 5-13 and 5-14, we see that the "battery" used in this circuit consists of three cells in series. This means that if alkaline batteries of 1.5V each are used, the total voltage available to the circuit is 4.5V. If typical rechargeable cells (NiCd or NiMH) are used, we can expect 3.6V to flow through the circuit.

Switches in Series

The power switch, labeled SW1 in the schematic, is *in series* with the rest of the circuit. As mentioned in the previous section, when this switch is open, no current flows through the circuit at all. The switch is intentionally placed at this location in this circuit to act as a bottleneck. When the power switch is turned off, no power flows through the circuit. That seems like a good idea, considering the desired operational goal.

The schematic symbol for SW1 shows a pretty good likeness to the internal wiring of any simple SPST switch. There are two terminals, and a conductor that can be moved to either electrically connect them or electrically isolate them. As drawn, the switch is in the open position.

If we added another identical switch in series with the existing switch, what would happen? Take a look at Figure 5-16.



Figure 5-16. *Two switches in series. Both switches must be closed for electricity to flow through this part of the circuit. If either switch is open, the circuit is broken and no current will flow.*

Both switch A (SW1) and switch B (SW2) must be moved to the closed position for any electricity to flow through the circuit. If either switch is opened, then no current will flow. This is sometimes referred to as an *AND* circuit. Both A *and* B must be on for the circuit to operate.

A circuit just like this is often used in security systems. Switches are attached to doors and windows. All of the switches are wired in series, forming a large loop. The switches are all configured to be closed when the doors and windows are closed, and to open when doors or windows are opened.

If all the doors and windows are closed, then the loop of switches will allow the flow of electricity. Although it sounds exactly *backward*, when electricity is flowing in the circuit, this keeps the security alarm *turned off*. When any one of the switches is opened, the circuit is broken. The alarm then sounds.

Most real security systems are more complex than this, of course. The main advantage of this particular configuration is that it is easy to install and requires the least amount of wiring. The chief disadvantage is that when the alarm is triggered, you have no idea exactly *which switch* caused it.

Switches in Parallel

Just like with batteries, switches behave differently when configured in a different manner. Let's connect two switches *in parallel* this time and see what happens. See Figure 5-17.



Figure 5-17. *Two SPST switches in parallel. If either one of the switches is closed, then power can flow through this part of the circuit. Both switches must be opened to stop the flow of current.*

The circuit in Figure 5-17 will conduct electricity if switch A (SW1) *or* switch B (SW2) are closed. To stop the flow of current, you have to open both switches. This can be used as a simple *OR* circuit. If switch A *or* switch B is closed, then power can flow through the circuit.

Looking back at the schematics in Figures 5-13 and 5-14, we see that SW1 is in series with the rest of the circuit. This makes it a very effective way to turn power on and off from a single location. Handy!

The Three-Way Switch

You might think that the circuit shown in Figure 5-17 could be used to turn lights on and off from two different locations. You would be partly correct. You could turn lights *on* from either switch location, since flipping either switch to On will cause current to flow and lights (or other appliances) to operate.

Unfortunately, you would not be able to turn *off* the light from either switch if the other switch were on. So this configuration is good for turning lights on but not off. A slightly more complex arrangement is required to do both.

We will need two switches, as before, but they will need to have a little more functionality to accomplish what we've set out to do. Instead of a switch that's either open or closed, we need a switch that alternates between two different routes, depending on how it is positioned. This type of switch is called a *double-throw* switch, as it connects a *common* terminal to either one of two different terminals. It can be *thrown* in two different directions. This should be much easier to understand when looking at a schematic symbol. See Figure 5-18.



Figure 5-18. *A single-pole, double-throw (SPDT) switch. The common terminal on the left side is connected to either the top or bottom terminal on the right. Variations of this type of switch have a neutral position in the middle. Push-button (i.e., momentary contact) versions of this switch will label the two right-side terminals as either "normally open" or "normally closed," depending on the physical configuration of the switch.*

Now comes the clever bit. We'll connect a pair of these switches together by tying the two non-common terminals on one switch to their counterparts on the other switch. This results in four possible combinations of switch positions (both down, one up, the other up, and both up). Two possibilities turn the light on, and the other two turn the light off. The important point is that the "on" or "off" state of the entire circuit can be changed from either location, independently of the state of the other switch. Problem solved! Again, this should be easier to see when presented as a diagram. See Figure 5-19.



Figure 5-19. *A three-way switch circuit built using two SPDT switches. Power is either carried by the upper wire or the lower wire, as long as both switches are in the same position. If not, then no power flows across this part of the circuit. As shown, the three-way switch is effectively off. Flip either switch to turn it on.*

If you ask a real electrician how to wire a three-way switch, you'll get several answers, or more likely, you'll get, "It depends." That's because *it really does* depend on the actual wiring situation. Sometimes the power is routed through one or the other of the two switches, and sometimes the power is routed through the load. Each of these scenarios requires a different routing of wires and connections.

You are strongly advised to consult a real electrician concerning wiring in your house, where your family, pets, and all your stuff live. Less-than-perfect wiring causes fires or electrocution, which are both very unpleasant ways to die.

■ **Caution** This book does *not* teach you how to wire electricity in your home. Consult a professional.

Resistors in Series

Just like batteries and switches, resistors perform different functions in a circuit depending on their configuration. Let's look at using resistors *in series* first, and then consider using them in parallel later. Both combinations have their uses, as you will see.

Let's look at just a small part of the schematic that we've been working with so far in this chapter. See Figure 5-20.



Figure 5-20. *One part of the circuit showing an LED, a resistor, and the power rails from our solderless breadboard. The resistor and LED are connected in series. The battery and power switch are not shown.*

LED Curiosities

D1 is an LED. It is a polarized component and will only work when installed in the proper orientation. The schematic indicates a red LED should be used, but feel free to use whatever color LED you like or happen to have available. The triangle shape of the schematic symbol helps remind us of the direction of *conventional current* through the device. The actual flow of electrons is the other way, but that's only because electrons are negatively charged particles and do everything backward. Apparently this was not well understood when electricity was first being tamed for our use.

LEDs are fascinating devices, emitting light in a wide range of colors, coming in an astounding array of shapes and sizes, and generally requiring very little power to operate. They are almost as easy to use as incandescent bulbs and are certainly more power efficient.

Being semiconductors, however (which leads to their being semimagical in their inner workings), LEDs generally only operate correctly within tightly bounded parameters. For example, a typical LED will only need between 2 and 3V to shine quite brightly. Incandescent lightbulbs, on the other hand, can operate from less than 1V to many hundreds of volts, depending on their construction and intended purpose.

While LEDs have a minimum *forward voltage* requirement that must be met for them to work at all, the brightness of an LED is determined solely by the amount of current flowing through it.

LEDs Have No Self-Control

In addition, LEDs have no internal, inherent mechanism to limit the amount of current flowing through them. Incandescent bulbs, when cold, have a low internal resistance, allowing much current to flow through them when connected to the right power supply. Remember that less resistance means more current can flow, and vice versa. This resistance almost instantly goes way up as the filament of the bulb glows white hot. The filament itself then becomes the limiting factor in how much current flows through the bulb, usually stabilizing at the proper power level.

LEDs have no such sense of self-control. They will conduct as much current though themselves as you are willing to provide, up to and beyond the point where the internal heat generated by the small amount of resistance they do possess causes them to literally burn up. In general, it's usually the tiny, almost microscopic internal bond wires that fizzle out, not the actual LED chip itself. However, dead is dead, and LEDs are generally considered to be "unrepairable" subassemblies. (Believe it or not, that's the correct technical term, even though it's not the correct English word—*irreparable* is the correct term when speaking of non-electrical things).

Care and Feeding of LEDs

The simplest possible solution to this ~~problem~~ opportunity for excellence is the use of a *current-limiting resistor* in series with the LED. Recall that a resistor will resist the flow of current in a circuit. The resistor used in this circuit, R1, is indicated to exhibit a resistance of 100Ω.

Let's say that D1, the red LED in our circuit, requires 2V in normal operation. This is pretty common for red LEDs. Generally speaking, the forward voltage requirement for LEDs goes up as you get farther up the color spectrum. Blue LEDs, for example, often require 3.0V to 3.6V to operate.

If we're using rechargeable cells in our prototype (and we really should be, you know), we can expect 3.6V to be made available to the resistor-plus-LED loop within our circuit. If 2V is needed for the LED, where are the rest of those volts going?

The answer is that they are being used to heat up the current-limiting resistor R1. Resistors turn current into heat. That's what they do. They do it, however, in a very precise and predictable way, which makes it easy for us to calculate how much current, voltage, and heat will be churning around in our circuits.

■ **Caution** Third-grade arithmetic ahead: Addition, subtraction, multiplication, and (shudder) division. You have been warned.

If we started with 3.6V, and two of those volts are being used by the LED, then our good friend Subtraction tells us that we've got 1.6V flowing through R1. For a thorough explanation of why this happens the way it does, feel free to look up Kirchhoff's Voltage Law. It basically says that all the voltages in a circuit end up being equal. The voltage across the resistor and LED will equal the battery voltage. The voltages within the LED-in-series-with-resistor circuit add up, just like battery voltages add up in series.

If we know the voltage across R1 (1.6V) and the resistance of R1 (100Ω), then we can use Ohm's Law to calculate the current flowing through R1. Reviewing what you learned in Chapter 3 about the predictable and inviolable relationships between voltage, resistance, and current, you can see that I = E / R (i.e., current equals voltage divided by resistance), where I is the current in amps, E is the voltage in volts. and R is the resistance in ohms.

It's not that hard! It sounds much worse than it actually is. The answer is 0.016A, or 16mA (1.6V/100Ω). That's the teeny-tiny amount of current needed to light up a typical red LED. Most small LEDs can handle up to 25mA safely, and some can handle much more than that, especially if they are intended for illumination purposes.

One quick side trip to multiplication land and we'll know everything we need to know about R1 in this circuit. While the schematic specified the resistance of R1 as 100Ω (the primary characteristic or component *value*), nothing was said about the power-handling capability of this component.

Power is calculated as voltage multiplied by current. That's all there is to it. We know the voltage: 1.6V. We know the current: 16mA. We multiply them together to get 0.0256W (watts), or almost 26mW. Remember that you have to enter the current as 0.016 because the formula calls for the number of *amps*, not milliamps.

Not quite 26mA is not quite much of anything. You will not be able to tell that the resistor is shedding all those extra volts as heat with your fingertip. It might not even register with a sensitive thermometer. It's just a really tiny amount of power. A typical small resistor (a 1/4W resistor) will handle 250mW of power, which is almost ten times what is needed in this application.

■ **Tip** It's always a good idea to calculate the power requirements of your components, just so you're not *too* surprised when the magic smoke leaves the circuit, rendering it crispy and nonfunctional.

OK, we're back from the frightening land of multiplication. It wasn't *that* bad was it? The remainder of understanding resistors in series depends only upon the science of addition. Counting on your fingers will be good enough.

We can change the brightness of the LED by changing the amount of current flowing through it. We can change the amount of current flowing through the LED by either raising the supply voltage or by changing the resistance of R1. Since we can easily substitute any other value of resistor for the 100Ω resistor with which we began, this is easy to do. Just don't go *too low* in resistor value, as this will allow *too much* current to flow through the LED, possibly damaging it permanently.

Adding resistors in series adds their resistances together. For example, if you placed two 100Ω resistors end to end, the total resistance across them would be 200Ω. That's really all there is to it: 100Ω + 100Ω = 200Ω.

If you perform this experiment with the LED circuit we built on the breadboard, you can see that the LED will not shine as brightly as it did before. This is because the resistance has doubled, which means, all other factors remaining the same, that the current through the LED has been cut in half. Half the current results in half the brightness, since LEDs are controlled by the amount of current flowing through them.

What's interesting about this arrangement is that the power-handling capacity of the two resistors is *also* double what it was when only one resistor was in the circuit. This is because each resistor is now dissipating half the power when compared with the previous scenario. If two 1/4W resistors are used in series, they can together safely dissipate up to 1/2W of power, although pushing any component to 100 percent of its capacity is just asking for trouble, especially when heat is concerned.

By connecting resistors end to end, you add their resistances together, as well as their power-handling capabilities. By keeping a small variety of basic values on hand (e.g., 1Ω, 10Ω, 100Ω, 1KΩ, 10KΩ, etc.), you can easily stack up the right combination needed for almost any electronic application. This is the method used in the very handy device known as a *decade resistor* or *decade box*, which has dials for each digit in the desired resistance, allowing you to dial up any value of resistor needed.

Extra credit: If you've followed along this far, consider researching voltage dividers built using only resistors.

Resistors in Parallel

What happens when resistors are connected side by side instead of end to end? That's where things get interesting, at least from a mathematical point of view.

An easy way to look at parallel resistors is to think about the amount of current flowing through each one, and then add them all up. See Figure 5-21.



Figure 5-21. *Parallel resistors each conduct a portion of the total current flow through the circuit. Each resistor allows a certain amount of current to flow. The sum of their currents can be calculated if their individual resistances are known.*

Let's assume that R1, R2, and R3 have resistances of 100Ω, 200Ω, and 300Ω, respectively. The total resistance of the circuit across the battery terminals is *not* 600Ω, as would be the case if they were in series instead of parallel. The total resistance is less than 100Ω, which is the least of the resistors. How can this be?

First, let's think in terms of how much current is flowing in each of the three parallel pathways within this circuit. If B1 is putting out 3.6V, and R1 is 100Ω, then we know to use Ohm's Law to calculate the current, with I = E / R. In this case, I = 3.6V / 100Ω = 0.036A, or 36mA. *In addition*, the path through R2 is drawing half that (because R2 is double the value of R1—get it?), or 18 mA. *In addition*, the final pathway is drawing one-third as much current as the first one, or 12 mA. Just to verify: I = 3.6 / 300Ω = 0.012A, or 12mA. Everything checks out.

Now add all those currents together: 36mA + 18mA + 12mA = 66mA. That's the total current, using this method. Again, since we know both the voltage and the current, we can find the *effective* or *equivalent resistance* of all three resistors in parallel, as if they were one single resistor. Rearranging the formula for Ohm's Law, we find that R = E / I. In our case, R = 3.6 / 0.066A = ~54.55Ω. See? Smaller than 100Ω, somehow.

Thinking about the individual *currents* flowing through each resistor is the same as adding the current-supplying capacity of battery cells together when arrayed in parallel. Just add them together. However, we had to calculate each current separately and then add them together. There is a more direct way, depending upon how you look at things, but beware: it involves not only *fractions*, but *fractions upon fractions.* Oh, the horror.

■ **Note** Some people don't dig math. Weird, but true.

Here is the equation for calculating the total resistance (R_T) of three resistors in parallel (R_1, R_2, R_3):

$$R_T = \frac{1}{\left(\frac{1}{R_1}\right) + \left(\frac{1}{R_2}\right) + \left(\frac{1}{R_3}\right)}$$

The good thing about this equation is that you don't need to know what the supply voltage is to get the correct answer. All you need to know are the values of the resistors. If you need to use more resistors, just add more terms to the equation.

Calculating the value of parallel resistors occurs quite frequently when designing electronics. Some special cases are simple enough to do in your head. For example, if two identical-value resistors are placed in parallel, their combined resistance is half the value of each individual resistor. That is, if you placed two 100Ω ohm resistors in parallel, their effective resistance would be 50Ω. Similarly, if you have three identical resistors, the net resistance is one-third the value of each constituent resistor. Make sense? These are special cases of the general equation just shown.

This happens so much that an alternate notation method has been developed: $R_T = R_1|R_2|R_3$. This is not often used for hobby electronics, however.

The power-handling ratings of resistors are added together, so if you have two 10W resistors in parallel, the net power-handling capacity is now 20W. At least that part was easy.

Capacitors in Series and Parallel

Capacitors are completely different from resistors. When calculating their values in series and in parallel, you have to use *exactly the opposite* methods. Isn't electronics interesting?

The values of capacitors *in parallel* are added together. This makes them much more like batteries in parallel than resistors. However, you still have to use the fractions-upon-fractions method to calculate the value of capacitors in series.

Again, some shortcuts are available. Two identical capacitors in series have *half* the capacitance of each individual capacitor, but *double* the working voltage, which is the maximum voltage they were designed to withstand before failing.

Inductors in Series and Parallel

It gets more interesting, believe it or not. Inductors act like resistors as far as adding their values together in series and taking the reciprocal of the sum of the reciprocals of their values in parallel, but *only* when the magnetic fields of all of the inductors involved do not interfere with each other. If the magnetic fields generated when current flows though the inductors overlap, then you have to factor in their *mutual inductance*, which starts to get complicated.

Extra credit: Figure out how all that works and let me know.

LEDs in Series and Parallel

You learned (or were reminded of) a few of the basic characteristics of LEDs in the previous section, although it was really to help illustrate the operation of resistors in series and parallel. A couple of major oversimplifications were introduced to help concentrate on the resistor. We'll address a couple of these issues here.

Lighting up a single LED using a battery and a fixed current-limiting resistor is fun, but it's pretty basic stuff. Lighting up a *lot* of LEDs is where it gets to be a *lot* of fun. To do so, you need to learn a little more about the weirdness that is *semiconductor*.

LEDs are diodes (*LED* stands for *light-emitting diode*, after all). Diodes are semiconductors and are made by elves in a hollow tree. Semiconductors do not have nice linear voltage-to-current curves.

For the purposes of simplicity, in the previous section, it was suggested that LEDs have a certain minimum voltage that they need to operate. This is called their *forward voltage*, and is sometimes referred to as their *voltage drop* within a circuit. So far, this is all true. You can find an LED's forward voltage specification in the data sheet published by the manufacturer.

What you'll find, when you look, is that every manufacturer only publishes a *range* of voltages, such as 1.8V–2.2V, giving a minimum and a maximum voltage. This is what they are contractually obligated to deliver in their product. Anything outside of this range is considered *defective*, or at least out of tolerance. You might get a good deal on "rejects" that fall outside these parameters but still light up quite nicely. Such is the provenance of many of the penny LEDs available from overseas. Yes, they exist. And yes, you get what you pay for.

There are two reasons why LED manufacturers are being so deliberately vague in their specifications. The first is that process variations are going to produce a certain randomness to these values. One batch might be identical to the next batch, but then the third batch might be all over the place. Such things happen.

The second reason is where the real weirdness begins. Forward voltage is not a fixed value in any given device, but instead increases as the current increases. Again, this increase is *nonlinear* and cannot be calculated with a simple formula.

The best way to demonstrate this to yourself is to connect an LED to a power source via a variable resistor, such as a potentiometer. For the protection of your LED, add a fixed resistor in series with the potentiometer so that you establish a maximum current level, even when the potentiometer is turned all the way up (i.e., has almost zero resistance).

Now apply power and adjust the potentiometer until the LED just barely lights up. Now measure the voltage across the terminals of the LED, using a voltmeter. It should be in the neighborhood of 2V–3V. For extra credit, measure the current flowing *through* the LED, using an ammeter. This measurement will most likely be less than 1mA.

Compare these readings to what you find when the LED is at full brightness. The forward voltage across the LED goes up as the current goes up. To map the nonlinearity of this function, you would need to record many readings of both voltage and current, and then plot them in a graph.

Just as you can wire resistors, capacitors, and inductors in series and in parallel, you can do the same with LEDs. As with resistors, the forward voltage of the LEDs are added together when arranged in a series circuit. This raises the minimum voltage required to light up a string of LEDs in series. This means that you can't light up ten LEDs in a single string using a 9V battery. You have to first overcome the minimum forward voltage just to get any current at all flowing. Then you have to up the current to get the desired brightness, which simultaneously raises the total forward voltage through the circuit. You still need a current-limiting resistor in this circuit—but only one is needed. You don't have to have one for each LED.

The amount of current flowing through the string of LEDs is determined by the supply voltage, the cumulative forward voltage of all the LEDs, and the resistance of the current-limiting resistor. The same amount of current is flowing in every part of the circuit. If 25mA is being drawn from the power supply to light up your single string of LEDs, that means that each and every LED has 25mA of juice flowing through it—more than enough to light them up quite nicely.

If you have a 12V power supply (or a car battery), you could string up to five or maybe six red LEDs in series, with a small current-limiting resistor. That's because each red LED will typically have a forward voltage between 1.8V and 2.2V. Other colors higher up the rainbow might need more voltage per LED, meaning fewer can be lit at once using a single string of LEDs in series.

But don't fret. You can light up as many LEDs as you want by placing multiple strings of LEDs in parallel with each other. Each additional string of LEDs adds to the total current draw, so you will eventually find a limit along that dimension as well. For an example of a small LED array using both parallel and series circuits, see Figure 5-22. The schematic is shown in Figure 5-23.



Figure 5-22. *An array of six parallel strings of six infrared LEDs in series. These infrared spotlights are used for covert surveillance and security applications.*



Figure 5-23. *The schematic of the LED array, showing both parallel and series circuits. The circuit offers two power connectors to make it easy to wire multiple LED arrays using the same power supply.*

Summary

Even if your workbench doesn't look as bad as the one presented at the beginning of this chapter (or even if it looks *worse*), hopefully you've learned a thing or two about the importance of they saying, "A place for everything and everything in its place." Since *you* get to decide where everything goes, you can either make it easy or hard on yourself as the years go by.

The workspace in this chapter extended to a total of 10 square feet. If this is what you have to work with, you can certainly set up a comfortable, safe, and productive area for your electronic projects. If you have even more space available (adding a shelf either above or below the desk is a great way to do this), then even better.

Hopefully some of the more detailed descriptions of how electronic components can be wired up have given you some ideas for projects of your own. The very best possible way to learn more about electronics is to think up some simple experiments and try to build them in your lab. Have a goal, take lots of notes, and have some fun—even your failures can be used as stepping stones to more ambitious and creative projects in the future.

Have a *lot* more room? Then perhaps you should be thinking about setting up a group lab or classroom. Chapter 6 will give you some helpful advice about what you are going to need to get started. See you there!

CHAPTER 6

The Small Group Lab and Classroom

The first part of this book covered what you need to know to build your own personal electronics lab. Now it's time to share the love with your fellow electronics enthusiasts. Where to begin?

Like most important questions, the answer remains, "It depends." What resources are available to you and your group? How many folks will likely want to be working together, and for how long? How well do you really know these people? And these are just a few of the questions you're going to encounter along the way.

Take the time to understand exactly who "you" (plural; in Texas, *y'all*) are and what your requirements and goals could be. By doing so, you map out the future of your successful facility. Likewise, *not* planning ahead or making reasonable assumptions about your needs is simply an invitation to problems, problems, and more problems. Who wants *more* problems?

■ **Tip** If you fail to plan, you plan to fail.

Know Yourself

The ancient Greek maxim "know thyself" has as many definitions as it has authors, it seems. Plato indicated in several of his dialogues that Socrates would use this phrase to admonish his students to learn more about themselves and their own characters and capabilities before attempting to figure out the rest of the universe. Wise advice then and now.

As far as knowing yourself in relation to setting up a shared electronics lab, you should first think about what role *you* are going to play in this endeavor. Yes, *you*. Here are some of the major ones, and you might end up being all of them at some point.

Facilitator or Coordinator

In the role of the facilitator, you plan on providing an environment for others to use for their projects and explorations in electronics. You may or may not partake in these activities yourself, but have been tasked with (or volunteered for) the organization and coordination of the lab.

It's critically important to understand the needs of your intended ~~lab monkeys~~ users. See the "Know Your Group" section later in the chapter for more information on this topic.

As the lab facilitator, lab workers will come to you with questions, requests, comments, and complaints. Be prepared to address their needs in a responsive and professional manner—even if they're just your cousin.

Your responsibilities will include

- Communicating the scope of the lab (i.e., deciding what *is* and what *is not* acceptable or expected)
- Publishing any important information or updates regarding location, available times, features, rules, and possibly ongoing projects
- Crafting policies involving safety, proper tool usage and training, and participant conduct
- Maintaining supplies of commonly used materials
- Inspecting and repairing tools as the need arises

To balance out your responsibilities, you should be granted adequate authority in the following areas:

- Characterizing the scope of the lab, based on present and anticipated future needs
- Enforcing the policies of the lab
- Budgetary discretion in acquiring, provisioning, and maintaining lab assets
- Granting or revoking access to the lab based on established parameters

If you're going to be the Keeper of the Lab, then you should have both a personal interest in keeping it in good shape as well as the wherewithal to decide how things should be done.

Good luck finding the right balance there.

Teacher or Presenter

Let's assume that your lab has already been set up (or can be set up in a jiffy), and your main goal is to present information or teach classes there. Again, it should be apparent that a good knowledge of your intended audience will play a vital part in your success. See the "Know Your Group" section for more information.

Once you understand the needs of your class and the goals of your presentation, the next step is to leverage the existing facilities to your best advantage. Will you need specialized presentation equipment or materials? If so, see what is already available, and then make a shopping list of everything else you will need. Examples include lighting, a projector, specialized power distribution, and test equipment.

Are you making an interactive presentation? If so, what materials will you need to provide for your students to be able to fully participate in your presentation?

What will be your optimum teacher-to-student ratio? If you have a simple message that's easily communicated and reinforced, a single speaker can effectively address a rather large crowd. Once you start adding layers of complexity to the subject matter, you're going to have to be prepared to backtrack and explain things in more detail from time to time. If you're leading a group through a technical exercise, it's often profitable to have assistants available to help just those individuals that need a little more help, without having to stop the class in its tracks. These assistants need to be up to speed on the subject matter as well as have good communication and troubleshooting skills.

Remember that students look to the teacher for leadership, not only as a subject-matter expert. Take the lead, set a good example, and share your enthusiasm for your topic with your students.

A successful teacher leads a class on a journey of discovery. Make sure you don't lose too many along the way.

Participant

Your goal as primarily a group lab participant is to make effective use of the facilities at hand, making the most of your time and energy. Having access to a well-stocked lab with a good array of tools can be a decided advantage for both your immediate project goals, and it can be an excellent opportunity to accelerate your knowledge of electronics and other mysterious arts.

Imagining yourself as an active participant is the best perspective when laying out the flow of your lab. Set up workstations that have almost everything you need, leaving room for the complex or specialized stuff elsewhere. There are more suggestions about specific workstation configurations in the "Workstations" section of this chapter.

While the active-participant model helps you squeeze out the maximum utilization of your lab, be sure to consider the sort-of-working-but-also-sort-of-goofing-off model. Not everyone wants to be working full-tilt all of the time. Leave room for a certain amount of idleness, contemplation, and whimsy. You might be surprised at the results.

Observer

You want to be in on the action, but not necessarily working on anything in particular. That's great! Don't underestimate the importance of the purely social aspects of technical gatherings.

Some people just like to hang out with other like-minded individuals. This is a good thing—when resources and circumstances allow it. Watching creative, talented, and driven folks working on projects with passion is very often the best kind of inspiration. Let your kids see you having fun and making cool stuff in your lab, and the next thing you know, they are going to want to be there whenever you are. Pretty soon, they are going to want to start working on projects of their own—and that is its own special reward.

Know Your Group

Now you know a little bit about who you are and what your expectations of your lab may be. Now it's time to get to know the group of people who will most benefit from access to the lab.

Identify the needs and requirements of your group by first identifying *precisely* who your intended audience is going to be. Knowing this one item, up front, before any big plans are laid, is the best way to ensure success down the road.

There are several broad categories for which you might need to prepare. The more you know about your particular group, the better. Let's start fairly close to home and expand outward.

Your Family

Once you've established your own electronics lab at home, it's great to be able to share some of the fun with those that are closest to you. This might be your children, parents, siblings, or extended family. A well-planned and well-maintained electronics lab is going to generate some interest, or at least some curiosity. Here's how you can carve out some room for them, while still being able to get things done yourself.

It's very natural to want to share your hobbies and interest with others, and a safe and well-stocked electronics lab is a great place to do so. This is an especially ripe opportunity for parents to pass on their knowledge, skills, values, and work ethic to the next generation.

The family lab can be a logical extension of the family home. Everything is shared, including responsibilities and privileges. In more agrarian societies, this is already well understood at an early age, where chores around the farm and in the fields and a respect for the tools being used help enhance a sense of group belonging and worth. Everyone has a stake in the prosperity of the family endeavor.

Do you want your kids to appreciate what you give them? Then give them chores before you give them presents. Let them clean up the lab, put away tools, inventory parts, and take out the trash before spoiling them with all the fun stuff you get to do in the lab. This will help foster a sense of ownership in the long-term success of the lab, whether you're there to supervise or not.

It bears repeating (from Chapter 4) that no unsupervised children, no matter how adorable, should be allowed in the lab. Would you allow unsupervised cooking in the kitchen? It's the same basic scenario. When everything goes well, everyone has a good time. It only takes a split-second distraction to go from a good time to a trip to the emergency room in either case. Have rules and enforce them, even if it's your elders that you are protecting by doing so.

Sometimes having a resource like a shared electronic laboratory is the first opportunity people have to assert some sort of control over their relationships. Use the opportunity to make friends with your relatives, while you still can.

Your Friends

Unlike your family, as the saying goes, you get to *pick* your friends. Now you have the opportunity to provide a cool place to hang out as well as build all manner of awesome gizmos. It's only natural to want to share some of the fun with your like-minded friends.

The basic framework of rules and accountability apply to the friendly lab as well as any other group endeavor. Let your friends know up front what your expectations of them are in regard to use of the lab. Can they use your tools? Can they store artwork-in-progress at your place? When is it cool to come over to tinker, and when is it not? These kinds of questions should be dealt with early in the game; otherwise, these issues can flare up and become trouble spots. There's no substitute for good communication.

Once you extend your laboratory's hospitality to those outside your immediate family, it's a good idea to clearly designate what is your personal property and what belongs to the lab and all its participants. This can be as simple as putting name tags on all your tools and marking shared resources appropriately.

This is where *trust* really factors into the success or failure of a group lab. Just like in math, you want to eliminate as many variables as possible to ensure that a good time is had by all, and to ensure the long-term safety and viability of the facility itself. Which of your friends do you *trust* in your lab? Think about these things at length before opening the doors to just anybody.

Coworkers and Fellow Students

So you've been tasked with organizing or supervising a lab for a school class or university department. You may or may not have any choice in who will be granted access, or even when they can avail themselves to the facilities.

The balance of responsibility and authority is crucial in this scenario, just like in most other situations in life. Hopefully you will be in a position to enforce whatever rules are already in place. Ideally, you will have some say in crafting new rules as they become necessary, or adjust existing rules when they need it. In either case, it's just not fair for someone to expect you to do a good job, yet not provide you the tools to get it done.

Positions like this become available from time to time in most schools. Sometimes there's an opportunity for a small paycheck, and other times all you are going to get are points with the administration. Hopefully, at least you will also enjoy lab privileges. That's got to be worth something, yes?

If you are helping to run an existing lab, there are probably others you can consult who have had this particular honor in the past. Try to find out who these folks might be and see if you can get any helpful advice from them about your lab and its care and feeding.

If you're starting from scratch, you will enjoy the double-edged sword of setting things up the way you want, as well as setting things up the way everyone else wants it. You *get* to establish whatever level of functionality you want, with the caveat that you then must maintain that level. It's a freedom, like most freedoms, that comes with a price.

Special-Interest Groups

Are you a member of club that has a special interest in electronics? Several popular interests, such as ham radio operators, remote-control model flyers or drivers, robot builders, and computer users, have a love-hate relationship with electronics. Having a dedicated electronics lab available to the membership is a great way to build up the love as well as work out the hate.

Given a highly specialized crowd, such as the members of a university or trade school, you might even find people organized into an electronics club, especially these days when almost every aspect of our lives is touched by this technology in one way or another.

The specialized nature of your group helps focus what areas of electronics are of most practical interest, at least from a lab point of view. This cascades into easier choices when it comes to stocking the lab with workstations, tools, and components.

The Dallas Personal Robotics Group (DPRG; see `http://dprg.org`), for example, had the use of an 1,800-square-foot warehouse for over six years, rent free, due to the generosity of one of the members, Mike Dodson of Modern Assemblies. Having access to an excellent industrial setting allowed the club members to dream of and then realize much more ambitious robot projects than could be attempted at home. After Mike's retirement, the DPRG went into a nomadic phase and finally spun off a dedicated workshop and meeting area, now called the Dallas Makerspace.

The General Public

A lot of people see the popularity of do-it-yourself (DIY) and *maker-movement* projects and envision themselves as entrepreneurs, seeing a need and being able to meet it. Unfortunately, most of these people are wrong.

Building a lab dedicated to public use sounds like a great and noble aim. The realities of such an undertaking, including the financial, logistical, and business related, are not to be underestimated. While it seems to work well in certain areas and at certain times, it's almost always the result of the right combination of people coming together at the right time.

Hackerspaces (a terribly unfortunately chosen label) are springing up all over the world. The term *hacker,* while understood within some technical communities to mean a person of respectable skills, has a decidedly *unrespectable* taint to it when viewed from the outside. To the vast majority of the English-speaking world, a hacker is a rogue computer jockey, a criminal intent on breaking and entering into computer systems for nefarious purposes.

The term *maker,* on the other hand, leaves a more positive first impression. The Dallas Makerspace members deliberately made this decision when naming themselves, while they were still just a subcommittee within the board of directors of the nomadic DPRG, looking for a new home. It was important to them to maintain the very positive image that the DPRG had established and built over its long history, while still looking to the future.

If you're going to set up a lab for use by the general public, whether you decide to call it a hackerspace, a makerspace, or something entirely different, you get to make almost *no* assumptions about the good intentions of your membership. It's a sad state of affairs, to be sure, but it seems to be the prevailing wisdom of the day.

Some popular and successful organizations—such as Noisebridge (`www.noisebridge.net`), in San Francisco, California, which was incorporated in the state as a "non-profit educational corporation for public benefit"—operate almost entirely on a "consensus basis," sometimes known as "anarchic chaos." Noisebridge's overriding motto is "Be excellent to each other," very often shortened to just "Be excellent." Its very real success and sense of community among members is based on what seems to be a very local tolerance that is not to be found in many parts of the globe. If you ever get a chance, do stop by and prepare to be impressed. It's an amazing place.

A good parallel would be to visit your local public library. In the areas that still maintain libraries (shockingly, they are on the decline), you will find a finely tuned machine that meshes well with the surrounding locality. Are there bars on the windows? If so, you're going to need some bars on your windows. Are there metal detectors at the entrance? Oh, dear. Do you see any uniformed security forces present? These are not good signs.

Don't be completely discouraged, however. Sometimes a community in decline needs a little boost of energy and an injection of esprit de corps. This can often be accomplished by introducing some new alternatives for people's spare time. An ancient Muslim saying reads, "Trust in Allah, but tie your camel."

A Shared Resource

Do you have a dedicated space available? If so, you are way ahead of the game. Finding a good location is half the battle. If your space is truly dedicated to your pursuits and activities (i.e., a private home, club, or makerspace), you have the advantage of being able to leave tools, components, and projects in place, returning to them (and finding them still there!) when the opportunity arises. "Truly dedicated" in this sense can be equated with having your own key to the door and reasonably free access. While a 24-hour facility sounds like a great idea, there are a lot of logistical problems associated, such as security, utility costs, scheduling, and parking, just to name a few.

If your space is not-so-dedicated, such as a school lab or friend's garage, you can still make it a home away from home if you are able to arrange for secure storage of all your shiny toys. This could take the form of individual lockers or a storage closet.

No matter what the logistical arrangements, the main challenge to providing a versatile and effective setting for electronic and other kinds of tinkers is basically a social one. Once it's more than just you, it can start to get complicated.

Luckily, there are some time-tested methods for making these types of things run smoothly.

Be a Hospitable Host

If you are taking the lead in arranging a shared work space, please remember that you are responsible for extending the appropriate hospitality to your present and future guests. This single factor will greatly determine the vibe, feeling, or ambiance of the facility, even more than having the latest and greatest tools and gizmos on hand.

This task may or may not fall entirely on your shoulders. Many hands make light work. If you are able to delegate some of the duties of a hospitable host to other members of your group, consider doing so.

Think of your task in the same light as planning a successful party, even if it's one that you anticipate will last for days on end. These basic ideas are as old as civilized living. Think about fabulous parties or memorable events that you have been privileged to attend in the past, and then plan on taking it up a notch.

Try to anticipate the human needs of your attendees as well as their technological expectations. People have what seems like an endless list of requirements, some of which you can address, some not.

Make your location known. Make this information easy to find to those interested, and easy to update when the venue changes. A web site is trivial to set up these days, and even a post to a popular forum will tend to be accessible via Internet search engines, in time. There's a new social media outlet popping up every third Tuesday, so avail yourself to what makes sense for your audience. Word of mouth only goes so far these days.

Once you've gone to the trouble of publishing your location, go the extra mile and put out some sort of actual sign or indicator that your arriving guests have found the right spot. If you have an identifiable logo or symbol associated with your group, be sure to proudly wave that flag. People don't like feeling lost, or unsure whether they're entering a welcoming space or about to trespass on private property.

Let everyone know when they are expected as well as when they are *not* expected. Post your regular meeting times, if you have them. Alternatively, make known the appropriate hours of operation. It's disappointing to be turned away at the door just because it's 1:00 a.m. on a school night.

When possible, welcome your guests. This makes a big impression on both newcomers as well as the regulars. Being part of a group is supposed to *enhance* a feeling of inclusiveness and belonging. We are social animals at heart, and even a simple hello is often the prelude to an interesting and productive time together.

Have rules. Make these rules known. A sign on the front door is not out of place, as long as it's not too negative or off-putting. Rules should *prevent* problems from occurring, and not be enacted as a spontaneous reaction when problems inevitably occur.

Ensure your guests' comfort when attending. Is there enough room for the largest (and the smallest) participant to safely enter and exit the facilities? Is there adequate lighting in the common areas, if they exist? Is there a place for everyone to sit? Who has dominion over the thermostat?

Do you plan on making refreshments available? Will this duty rotate among the membership? Keep track of such things, if only to keep from overextending yourself in all the myriad details of hosting a successful meeting. While massive banqueting and consumption of yummies make for a festive and enjoyable association, these activities are not always aligned with maintaining an effective laboratory. Separate the feeding trough from the work areas. Stay focused on what you're trying to accomplish here.

Will everyone have access to restrooms, and whose job is it to keep these areas tidy?

And the most important question of all: Who takes out the trash?

Be a Courteous Guest

Just as it's important to play the role of the hospitable host, it is likewise critical to be a courteous guest when visiting a facility, whether you are a paid-up member in good standing or an invited guest. Again, these guidelines will vary according to the intents and purposes of your lab, but the basics will always remain the same.

If possible, and when appropriate, let your host know if you are planning on attending. This won't apply in a causal, drop-in type of laboratory. Even so, by making your intentions of attending known ahead of time, you might influence (one way or the other) the attendance of other potential participants. Nothing succeeds like success. A well-attended party has a better potential for awesomeness than a sparsely peopled event.

Arrive on time or within the established time frames set forth by your host. Similarly, unless you have been granted special access, plan on leaving at a reasonable time as well. Benjamin Franklin wrote in his *Poor Richard's Almanack* (1736) that "Fish & Visitors stink in 3 days." Don't be a stinker.

Try to contribute something. Don't show up empty-handed, expecting to be fed, entertained, and enlightened.

Workstations

Now it's time to talk about your workstations. Even if it's just you in the lab, having a separate workstation for each type of activity is a great idea. For example, you might have one workstation set up for programming a computer, another for soldering electronics, and another for working with power tools, such as a drill press or a saw.

Workstations dedicated to a particular task should have everything within easy reach, including tooling, supplies, power, and lighting. Don't waste time by forcing people to wander around the lab looking for the right drill bit or magnifying glass. Keep everything close so you can find what you need, when you need it.

Having a place for everything ahead of time is the best way to follow the wise adage, "A place for everything and everything in its place." You get to decide where everything lives. It doesn't hurt to go ahead and label everything conspicuously so that others can find their way around the lab.

If you have several people wanting to work on the same kinds of projects at the same time, you're going to need multiple, nearly identical workstations. The exact number depends on your available space and the number of people you expect to want to participate simultaneously, as well as your budget.

Most indoor-oriented work can often be performed at a work table. Exceptions include giant-scale mechatronics, pyrotechnics, and underwater robotics. Some of their constituent bits and pieces, however, can be crafted on an adequately prepared work table.

Make sure each work area has plenty of power outlets available. You're almost guaranteed to run short at some point. Take care not to overload your circuits, however. If you anticipate needing a lot more power than is presently provisioned, you're going to have to consider the real possibility of having your facility expanded by qualified, *licensed* professionals. These requirements will vary from one location to the next. Check with your local building codes to be sure.

As repeated often in previous chapters, you can never have *too much* lighting available, especially for the more detail-oriented chores. Typical indoor room lighting is just about adequate for finding your way out of the room, and that's about all. You'll need area lighting for each workstation, and possible additional task lighting, depending on your particular requirements.

Providing network access to each workstation can be challenging. Wireless networking is a good way to accommodate a relatively small number of users at once. More than a handful of computers trying to access the Internet at the same time can bring many wireless routers to a slow crawl. Dedicated high-speed Ethernet connectivity is more expensive and takes more effort to deploy, but offers much greater bandwidth to your lab-folk.

If you're especially cramped (or *dimensionally constrained*) in your lab, you'll need to get inventive. For example, a table placed in the center of the room can be approached from multiple sides. There's no reason all the workbenches have to be pushed up against a wall, allowing access from only a single side. Get creative!

Safety Planning

While it's tempting to fill up all the available space in a lab with workstations, especially when the budget permits it, do try to leave a bit of common area here and there. You always want to be able to walk *away* from a workstation with the same (or sometimes even more) rapidity you approached it with. Fire is an excellent example of such a motivator.

■ **Tip** Keep a properly selected and maintained fire extinguisher at each workstation, if possible.

Post emergency procedures prominently, where everyone, including visitors, can see. Have an evacuation plan, complete with map and “You are here” indicator posted at each workstation. Hopefully you will never need it.

Presentations

Are you excited about your latest project? Have you just learned a great new skill? Setting up your lab for group presentations is an excellent way to communicate these ideas to your friends, family, and coworkers.

Make your ~~victims~~ guests comfortable. Have adequate seating for everyone, with plenty of room between the rows (if you have more than one row of chairs). Ensure that everyone has a good view of what you intend to present.

Will the attendees be expected to take notes? Then perhaps you should set up tables where they can comfortably jot down some of the more spectacular aspects of your presentation. If you will be providing a handout or other documentation packages, make sure you have enough for the anticipated demand. Will you be entertaining questions or comments either during the presentation or afterward? Then make sure that not only can your audience see *you*, but that *you* can see *them*.

If you’re going to be using some sort of projector for your presentation, by all means set aside some time to get to know the equipment ahead of time. Nothing ever seems to work just exactly as you imagined that it should. This seems to be an invariant law of presentation physics. No one is really sure why.

Your audience’s time is just as valuable as your own. In fact, if there are only two people attending, then their collective time is worth approximately *twice* as much as yours. Think about it. Have all your ducks in a row, so to speak. Wasting time figuring out which cable goes where is not a good use of your time together.

Summary

Wow! You can really go crazy setting up a shared electronics lab, can’t you?

Before you even flip on the light in your shiny new group lab, you should already have an insightful idea of who is going to be using it and why. You should also have some honest expectations of what your own expectations are going to be, and how you would like to interact with both the lab itself and its population.

The details, of course, are always going to be specific to your particular situation. Be on guard, however, for the future. It’s going to sneak up on you, someday. Not too long ago, for example, it took a fairly hefty desk to keep a modern personal computer up off the floor. That kind of computing power now fits in a pocket. Think of what better uses you could dream up for that space these days!

That kind of forward thinking is exactly what turns the dreams of today into the reality of tomorrow. It’s forward-thinking people like you, dear reader, that help map out those realities. Take the opportunity you have right now to spend some quality time daydreaming about how things *could* be. Then take those steps necessary to make it happen. Your family, your society, and your world expect great things from you. You can do it!

APPENDIX A

Getting Started with Tool Building

Once you've become comfortable in your lab and have had time to play with a few circuits, you might start to notice that some of the "tools" you've been using are just simple electronic circuits themselves. Good examples are power supplies and meters. These are great tool-building projects because you can see useful results early.

Let's take a look at building a couple of simple electronic tools that might be of use in your lab. Hopefully you will develop a better understanding of how these tools work. Ideally, you will progress from the basic question of "Does it work?" to the more involved questions of "How well does it work and what can I do to improve it?"

Please bear in mind that these exercises, while hopefully useful, are to illustrate what needs to go into the building of practical, reliable tools. At every stage you should be thinking about what design choices you have and which choices will enhance the usefulness of your tool-building process.

A Very Simple Power Supply

Almost all electronic projects need electricity to work. Having a good, dependable power supply at your disposal on your bench will get you started faster on new projects. You won't have to worry about dead batteries and flaky power adapters. See Figure A-1.



Figure A-1. *A professional bench power supply. This device allows both the voltage and the maximum current to be adjusted. It provides two dedicated meters to show how much power is flowing: one for voltage and the other for current. It also provides a modular set of plugs (banana plugs) for easily connecting and disconnecting power leads.*

A bench power supply such as the one shown in Figure A-1 has many features and includes extra circuitry to make it safe and easy to use. It will also set you back a good chunk of change (i.e., cost money). We're going to build something a bit simpler to start. Feel free to add more bells and whistles as your needs arise.

■ **Caution** Anything plugged into the wall has the potential to shock, burn, or kill you. Do not defeat their safety features!

An Easy 2.5 Watts

You probably have a spare USB charger lying around somewhere. If you don't already, you more than likely will at some point in the near future, as these are becoming more common with smaller electronic devices. If not, you can obtain one relatively cheaply if you do some smart shopping. The USB charger shown in Figure A-2 was obtained from overseas via eBay for less than $1. You will also need a USB cable about 3 or 4 feet long. Again, don't spend a lot of money on a new cable. If you don't already have one floating around in a drawer somewhere, you probably know someone that does.



Figure A-2. *A USB charger that plugs into the wall and provides a regulated +5V supply. This plug is intended for US wiring, but will operate from 110AC to 240VAC at 50 or 60Hz, which pretty much covers the whole world, if you have the right adapter plug.*

It doesn't matter what type of USB cable you find, because we're going to cut off the smaller end and use the bare wires inside the cable. It just has to have the USB A–style plug shown on the left side of Figure A-2. The plug will fit into the socket of the charger. You do not need to open or modify the USB charger at all, and you are seriously advised not to do so for any reason.

Let's take a closer look at the label on the charger to find out exactly what it's supposed to be doing for us. See Figure A-3.



Figure A-3. *The label of the USB charger tells us that it accepts anything from 110VAC to 240VAC at either 50Hz or 60Hz. This wide range of input power allows the same internal electronic design to be used worldwide. Only the prongs that plug into the wall vary from location to location. The label also tells us that the USB charger will output +5V at up to 500mA. That's 2.5W!*

The "OUTPUT: 5.0V ⎓ 500mA" marking tells us what we need to know about the flavor of the power coming out of the adapter. The "5.0V" is the measure of the voltage. This is a very useful voltage level for small projects. Many digital chips require a 5V supply, although 3.3V is also becoming quite popular.

The ⎓ symbol represents *direct current (DC)* voltage. The symbol for *AC (alternating current)* voltage is the tilde, or wavy line symbol ~. The "500mA" is the maximum current that can be supplied by this charger (500 milliamps, or 0.5A), although you are cautioned not to expect a low-cost item such as this one to produce 100 percent of its rated power 100 percent of the time.

While this USB charger will most likely work for our intended purposes, it's best to keep those expectations in check. Note that "Model:" is misspelled ("Mode:"); and also note the absence of the magic letters *USB* or the USB logo. Also, there is a complete lack of any safety certifications present on this humble device, as befits its ~~cheap~~ economically optimized provenance. Compare this with the veritable constellation of safety certifications on the name-brand laptop charger shown in Figure A-4.



Figure A-4. *A name-brand laptop charger with several international safety certifications. Every one of these certifications costs money to obtain, and shows that the device was demonstrated to be safe for use in a typical home or business application.*

Next we adapt the USB cable to our needs. In the words of the Red Queen, “Off with his head!”

■ **Caution** Make sure the USB charger is not plugged into the wall or a power strip when making modifications to the cable.

First, plug the USB cable into the USB charger. Now cut off the *other* end of the cable. See Figure A-5.



Figure A-5. *Cut off the device end of the USB cable. If you cut off the wrong end, you're not going to be able to plug it back into the charger, at least not without a considerable amount of effort. To ensure you cut the correct end, plug the host end of the cable into the USB charger before snipping, and then cut off the other end.*

Now carefully strip off about an inch of the cable's insulating jacket. Do your best to not nick the insulation on the wires inside. Within the jacket you should find four wires. Two of these wires carry the +5V and ground from the power supply. The other two wires carry the data on the USB connection. Since we're only interested in the power, we can ignore the other two wires for now. See Figure A-6.



Figure A-6. *The four internal wires within the USB cable. From left to right they are red (VBUS or +5V), black (ground), green (USB D+), and white (USB D–). Use the red and black wires to pull a regulated +5V from the charger.*

The USB standard specifies every little detail about how to build and mark USB cables, even down to the colors of the internal wires in the cable that you're not ever supposed to see! That's dedication.

■ **Note** Apple violates the USB standard by not having a raised USB symbol molded into its cables.

However, sometimes cable manufacturers fudge a bit and use whatever four-conductor cable they happen to have lying around. A very common substitute cable uses red, blue, yellow, and brown wires internally. See Table A-1 for a list of which wires go where.

Table A-1. *Standard USB Wire Colors and Their Functions, Along with Popular Alternate Colors*

Function	Pin Number	Standard USB Color	Alternate Color
VBUS (+5V)	1	Red	Red
D– 2		White	Blue
D+ 3		Green	Yellow
GND 4		Black	Brown

Now is the time to verify the wiring before we get much further. Even if your cable has the official wire colors within the insulating jacket, you are strongly advised to double-check both the voltage and the polarity coming out of the charger before connecting it to your tender, sensitive circuits. Minimize your assumptions about the compliance of others. Testing proves testing works!

Strip about 1/4 inch of the insulation from the ends of the red and black wires. Get out your meter and set it up to read voltage at or above the 5V range. If your fancy meter has autoranging, then just set it to read DC voltage. Plug the USB cable into the charger, if it's not already installed. Make sure the red and black wires are not touching, and then plug the charger into the wall or a convenient power strip.

Now measure the voltage between the red and black wires. Hopefully you should see a reading at or near 5.0V. The USB standard specifies a tolerance of ±10 percent, so anything between 4.5V and 5.5V is considered OK. See Figure A-7.



Figure A-7. *Measure the voltage coming from the USB charger before connecting it to any of your circuits. This one reads 5V on the dot! This is a much safer method than trial by fire (i.e., plugging it into your circuit and looking for a fire).*

Now that you've confirmed that the red and black wires do indeed carry the regulated +5V from the USB charger, you can clip off the unused green and white wires. At this point you can either use the bare, stripped wires of the USB cable or solder on a more robust connector. Since this power supply is destined to be used with a solderless breadboard, a small, two-pin connector with the appropriate spacing will be attached. See Figure A-8.



Figure A-8. *A gold-plated pin connector is soldered to the modified USB cable. The red and black insulation is left visible to be a polarity indicator when installing the cable to the solderless breadboard. Another happy LED!*

Adding Features

This power supply works just fine for most projects. If your requirements are, “Translate AC power from the wall into regulated DC power I can use for small projects, without spending a lot of money,” then this contraption fits the bill precisely.

You can see for yourself in Figure A-8 that it does indeed work as advertised. Looking back at Figure A-7, you can see that the charger itself has a power-on indicator LED built into the housing. What it doesn’t have is a power control or a switch. The power to the circuit is controlled by the switch on the power strip. This works just fine as long as you don’t mind turning on and off everything else that happens to be plugged into the same power strip.

Various Indicators

Not all USB chargers have a power indicator, however. Some have both a power indicator LED as well as a *charge status indicator*, which can tell you at a glance if your USB device is fully charged or still charging. A charge status indicator is usually implemented by measuring the amount of current being drawn from the supply. If more than a preset current is flowing, the power supply assumes a battery is still being charged. When that current drops below a certain level, it assumes that the battery has been completely (or maybe just mostly) charged. Some chargers use a red or orange LED to indicate charging, and a green or blue LED to show that the battery is finished charging. Again, this type of charge status display is provided to give the user a quick status update with a single glance. You don't need to consult the product manual to interpret the status code, if you can remember that red means "charging" and green means "charged."

Let's rearrange some of the parts on the solderless breadboard to make room for some new features. See Figure A-9.



Figure A-9. *The regulated power coming from the USB charger is no longer directly connected to the breadboard's power rails. Instead, it is routed to some internal tie points and then connected to the power rails via two short jumpers.*

Power-On Indicator

First, we add a local power-on indicator by reinstalling the LED and current-limiting resistor used in the previous experiments. While this duplicates the function of any LEDs that might be present on the USB charger itself, it brings the indicator closer to the area of interest, which in this case is the circuitry onboard the solderless breadboard.

The anode of the LED goes into tie point F-3, with the cathode being installed at tie point F-4. The current-limiting resistor spans the gap between tie point I-3 and the right-hand positive (red) power rail. A short jumper connects tie point J-4 and the right-hand negative power rail. See Figure A-10.



Figure A-10. *Add an LED and a current-limiting resistor across the power rails of the solderless breadboard to give an at-a-glance power indicator, right where the action is taking place.*

Now we have a good power-on indicator, right where we need it. It may or may not be redundant, depending on the features of your USB charger. This type of indicator is digital in the sense that it tells us that the circuit is either on or off, without giving us a lot of precise information about anything in between. For a lot of applications, however, this is more than enough information.

Power Supply Voltage

What if you *did* either want or need more precise information about the power supply? One method would be to permanently connect your multimeter to the circuit so that you can see how many volts are being delivered. That method assumes that you're not going to need your multimeter for anything else, ever.

A practical variation of that method, however, it to provide convenient *test points* in your circuit so that you can quickly and easily take a voltage reading when the need arises. Be sure to position the test points so that they are easy to access. Having a nice, big, readable label wouldn't hurt, either. Also, try to arrange things so that it's not likely that contact with a metal object, such as a tool or your wristwatch, will accidentally short out the power supply by touching both test points at the same time. Even simple "features" get complicated quickly, it seems!

If you want an accurate (and permanent) voltage reading on your circuit, consider adding a voltmeter. Small panel meters are relatively inexpensive and reasonably accurate. A DC voltmeter has two leads, positive and negative, that are attached across the voltage to be measured. See Figure A-11.



Figure A-11. *A DC voltmeter is attached to the circuit to accurately measure the supply voltage. The V on the meter's legend stands for voltage. The underline beneath the V indicates that it is designed to measure DC voltages, as opposed to AC voltages.*

The panel meter shown in Figure A-11 has a range of 0–30VDC. That's a bit more than we need, since our little power supply is only supposed to produce 5.0VDC ±10 percent. Since the meter's range does not accurately match the expected range of supply voltages, we lose a bit of precision when attempting to read the display. All the action is crowded together on the left side of the meter.

It might seem that a 0–5VDC meter would be preferable, but that would not allow for any overvoltage conditions at all. Remember, the USB standard allows for up to 5.5VDC to be delivered over the cable. A 0–6VDC meter, if available, would be more suitable. The meter introduced in Figure A-11, however, would be perfect when used with the laptop supply shown in Figure A-4, because its output voltage is 19.0V. That leaves a bit of room for overvoltage conditions and gives a wide enough swing of the needle to produce fine detail.

Power Supply Current

Measuring the *voltage* at any point in a circuit is easy. Just put a voltmeter between two points and voilà! In our previous example, we measured the VBUS power supply voltage with reference to GND, the ground potential of the circuit. Many voltage measurements are made with respect to ground.

To measure the current flowing through a circuit, we have two options. The first option is the most direct route. Install an ammeter (a meter that measures *amps* of current) inline with the circuit you want to measure. This requires that you *break* the circuit to make room for the meter. Once installed, the current flowing in the circuit actually flows through the ammeter as well.

The second option involves using a bit of trickery and some math. Instead of installing an ammeter directly inline with the current flow to be measured, we install a resistor of known resistance and measure the *voltage* that develops across the resistor.

Since we know that the values of volts, ohms, and amps are always related in any circuit, we can use Ohm's Law to determine how much current is flowing through a circuit by measuring the voltage across a known resistance.

To make things very easy, let's use a 1Ω resistor in series with the power supply, inserted in the circuit between where the positive lead of the power supply arrives at the circuit and where it is connected to the rest of the circuitry.

Unlike our previous use of Ohm's Law to calculate the missing value based on two known values, we only use *one* known value (the value of the resistor, called a *shunt resistor* when used in this manner). This one known value (resistance) then establishes the relationship between the two other values, voltage and current. As the current increases in the circuit, so does the voltage across the resistor. The two values will mirror each other—as one increases or decreases, the other will follow.

Since we used a 1Ω resistor in the circuit, this sets the relationship between current through the circuit and voltage across the resistor at a 1:1 ratio. For every ampere of current through the circuit, for example, 1V will be measured across the resistor.

Our power supply is only supposed to be able to deliver 0.5A of current, maximum, so we'll be dealing with voltages of less than 0.5V, unless something terribly unexpected happens.

Again, we could permanently attach a multimeter across the leads of a 1Ω resistor inserted into the circuit, or we could attach a voltmeter that is sensitive enough to give accurately readable information in the range we need. The 0–30VDC meter used before is much too large in range to do us any good here. We might see a tiny wiggle in the needle, but that's all.

Instead, we'll use a different kind of meter entirely. A digital voltmeter contains its own dedicated measurement circuitry and a numeric display to indicate the voltage reading. It also requires its own separate power supply. See Figure A-12.



Figure A-12. *A digital voltage meter is used to read the voltage across the shunt resistor installed in the circuit. Because the shunt resistor has a 1.0Ω value, Ohm's Law dictates that the reading in millivolts on the digital meter correspond exactly to the number of milliamps flowing through the circuit. Math is useful, sometimes.*

The jumper wire connecting the incoming power supply directly to the power rail has been replaced with a 1Ω resistor. Leads from both ends of the resistor have been connected to the input terminals of the digital voltage meter on the right. The digital meter, unlike the analog meter on the left, requires an independent power supply to operate, in this case a 9V battery.

So now we've added some features to our simple power supply, including a power-on indicator, a supply voltage reading, and a supply current reading.

These are very useful features to have on any power supply. However, at this point in the prototyping stage, we've just barely covered what the added circuitry is supposed to do. Packaging all this up into an easy-to-use and reliable device takes as much if not more thought and effort.

First, you have to rebuild this entire circuit in a more permanent fashion. Next, you will have to wedge all that clever gadgetry into some sort of enclosure to protect the delicate bits while still permitting access to the inputs, outputs, and controls, if any. Then you get to label everything so that you can remember how to use it in the future.

Summary

So now you just might be developing a certain respect for how much work goes into building even the simplest tools—tools that are useful, accurate, reliable, and an asset to your toolbox. Remember, every tool on your workbench has to earn its place there. This applies to tools you design and build yourself, as well.

Good luck with your tool-building projects. Sometimes it's just as much fun to work on your tools as it is to work *with* your tools.

Index

A

Active electrical and electronic components
  batteries, 81
  diodes, 82–83
  integrated circuits, 84
  LEDs, 83
  power supplies, 81
  transformers, 82
  transistors, 83–84
Active-participant model, 137
American wire gauge (AWG), 26–28, 60–61
Ammeters, 49
Anarchic chaos, 140
AND circuit, 124
Arduino-compatible microcomputer, 67
AWG. *See* American wire gauge (AWG)

B

Barrier strip, 30–31
Bipolar junction transistors (BJTs), 83, 84
Bolts, 33
Budgeting, 14–15

C

Capacitors
  definition, 76
  electrolytic capacitors, 77
  schematic symbols, 78
  in series and parallel, 130
Charge status indicator, 155
Coin cell
  electrical goodness measurement, 94
  lithium
    installed backward, 92
    LED lights up, 91–92
Components, electric and electronic circuits
  acquiring components, 84
    new components purchase, 85
    recycle, used components, 85–86
  active components, 81
    batteries, 81
    diodes, 82–83
    integrated circuits, 84
    LEDs, 83
    power supplies, 81
    transformers, 82
    transistors, 83–84
  conductors and interconnects
    connectors, 64–68
    description, 57
    electrical schematics, 57–58
    wire and cables, 58–64
  data sheets, 86
  passive components
    capacitors, 76–78
    inductors, 78–79
    resistors, 68–76
    switches, 79–80
Computers, 35–36
Conductors and interconnects
  connectors
    clip leads, 65
    description, 64
    solderless breadboards, 66–68
  description, 57
  electrical schematics, 57–58
  wire and cables
    conductivity, 61–62
    description, 58–59
    longer version, 60–61
    Ohm's law, 62–63
    short version, 59–60
    storing, 63–64
    testing, 63
Connectors
  clip leads, 65
  description, 64
  solderless breadboards

Connectors, solderless breadboards (*cont.*)
        Arduino-compatible microcomputer, 67
        description, 66
        prototype LED display, 68
        tie points, 66
Cozy corner lab
    capacitors in series and parallel, 130
    inductors in series and parallel, 130
    LEDs, in series and parallel, 131–133
    parallel and series circuits
        assembly instructions, 119
        batteries in, 122–123
        components, 118
        in different view, 120–121
        schematic diagram, 118
        troubleshooting, 119–120
    rehabilitation, work station, 105–106
        components, 115–116
        divide, 107–109
        lighting, 112
        power source, 110–111
        taxonomy, 106–107
        tools, 112–114
        under-desk environment, 115
    resistors
        in parallel, 129
        in series, 126
    switches
        in parallel, 124
        in series, 123
        three-way, 125–126

■ D

Dallas Personal Robotics Group (DPRG), 17, 101–102, 139
DC voltmeter, 156–157
Digital caliper, 46, 47
Digital storage oscilloscope (DSO), 53–54
Digital voltage meter, 159
Diodes, 82–83
Double-throw switches, 80
DPRG. *See* Dallas Personal Robotics Group(DPRG)
Drawing, 23
Drills, 40–43
DSO. *See* Digital storage oscilloscope (DSO)

■ E, F, G

Electrical experiment
    LED
        defective, 95
        installed backward, 92–93
        lights up when attached to lithium coin cell, 91–92
        on solderless breadboard, 95–98
    parallel and series circuits, 117–118
Electrolytic capacitors, 77
Electronic measurement tools
    ammeters, 49
    ohmmeters, 49
    voltmeters, 47–48
Electronics lab
    and classroom (*see* Lab and classroom)
    budgeting, 14–15
    cautionary tale, 17
    electricity,working principles
        practical approach, 9
        theoretical approach, 7–8
    environmental impact, 14
    flashlight, 11–13
    fundamental components, 4–5
    goals, 6
    ideas, 5–6
    of Harold Timmis, 16
    planning, 2
    portable (*see* Portable mini-lab)
    Robot Clubhouse, 17
    safety, 10
    space for, 3
    tools, 3–4 (*see also* Tools)
Environmental impact, 14

■ H

Hackerspaces, 139
Hand tools, 114
    computers, 35–36
    pliers and tweezers, 29–30
    screwdriver, 30–33
    screws, bolts and nuts, 33
    wire crimpers, 34–35
    wire cutters, 23–25, 29
    wire strippers, 25–29
Harold Timmis' lab, 16

I, J, K

Indicators, 155
Inductors
  DC motors, 79
  description, 78
  usage, 79
Infrared LEDs, 132
Inspection equipment, 45–46
Insulators, 8
Integrated circuits, 84

L

Lab and classroom
  group
    coworkers and fellow students, 138
    family, 137
    friends, 138
    general public, 139–140
    special-interest groups, 139
  presentations, 143
  role
    facilitator/coordinator, 135
    observer, 137
    participant, 137
    teacher/presenter, 136
  shared resource
    courteous guest, 141
    hospitable host, 140–141
  workstations
    description, 142
    safety planning, 142
Laboratory set up. *See* Electronics lab
Laptop charger, 149
Laser cutters, 43
Light-emitting diodes (LEDs), 83
  care and feeding, 127–128
  circuit on solderless breadboard, 95–98
  curiosities, 126–127
  defective, 95
  installed backward, 92–93
  in series and parallel, 131–33
  lights up when attached to lithium coin cell, 91–92
  self-control, lack of, 127
  uses, 100

M

Magnifying lens, 46
Metal-oxide–semiconductor field-effect transistor (MOSFET), 84
Modern digital storage oscilloscope, 52–53
Mobile electronics lab. *See* Portable mini-lab
MOSFET. *See* Metal-oxide–semiconductor field-effect transistor (MOSFET)
Multimeters, 50–51, 94

N

Noisebridge organization, 140
Nuts, 33

O

Ohmmeters, 49
Ohm's law
  description, 49
  application, 49, 62–63
OR circuit, 124
Oscilloscopes
  functions of, 51
  modern, 52–54
  tiny, 54–55

P, Q

Parallel and series circuits
  assembly instructions, 119
  batteries in, 122–123
  in different view, 120–121
  schematic diagram, 118
  troubleshooting, 119–120
Passive electrical and electronic components
  capacitors, 76–78
  inductors, 78–79
  resistors, 68–76
  switches, 79–80
Pencil-grip style, soldering irons, 39
Permanent circuit, 95–97
Physical measurement devices, 46–47
Pliers and tweezers, 29–30
Portable mini-lab
  advantages, 88
  compact executive model

- Portable mini-lab, compact executive model (*cont.*)
    - electrical experiments (*see* Electrical experiments)
    - lab deployed on desktop, 89–90
  - components, 89
  - DPRG, 101–102
  - features, 89
  - robotics lab, 103
  - travel, 87
- Potentiometer, 74–75
- Power-on indicator, 155
- Power rail attachment, 99
- Power supplies, 55–56, 81–82, 145–146
- Power tools
  - 3D printers, 44
  - drills, 40–43
  - laser cutters, 43
- Professional bench power supply, 146

R

- Resistors
  - color codes, 72–73
  - description, 68
  - location, 95
  - in parallel, 129
  - in permanent circuit, 97
  - power ratings, 73
  - schematic symbols and reference designators, 70–71
  - in series, 126
  - specialty resistors, 75–76
  - standard values and tolerances, 71–72
  - through-hole and surface-mount resistors, 69–70
  - variable resistors, 74–75
- RIGOL DS1052E oscilloscope, 54
- Robot Clubhouse, 17

S

- Shunt resistor, 158
- Single-pole double-throw (SPDT) switch, 125
- *Si*ngle-throw switches, 80
- Soldering
  - definition, 4
  - instructions for, 37–38
  - tools for, 113
- Solderless breadboards, 66
  - Arduino-compatible microcomputer, 67
  - description, 66
  - prototype LED display, 68
  - tie points, 66
  - types of, 117
- SPDT switch. *See* Single-pole double-throw (SPDT) switch
- Stereo microscope, 45
- Surface-mount resistors, 69–70
- Switches
  - description, 79
  - double-throw switch, 80
  - in parallel, 124
  - in series, 123
  - single-throw switch, 80
  - three-way, 125–126

T

- Tablet computers, 91
- Tabletop drill press, 42
- Tektronix 475A oscilloscope, 52
- Temperature-controlled soldering station, 113
- Terminal block, 31–32
- Test and measurement equipment
  - multimeters, 50–51
  - oscilloscopes
    - functions of, 51
    - modern, 52–54
    - Tektronix 475A, 52
    - tiny, 54–55
  - power supplies, 55
- 3D printers, 44
- Three-way switch, 125–126
- Through-hole resistors, 69–70
- Tools
  - earmuffs, 22
  - electronic measurement
    - ammeters, 49
    - ohmeters, 49
    - voltmeters, 47–48
  - eye protection, 21
  - for soldering, 37–40
  - hand
    - computers, 35–36
    - pliers and tweezers, 29–30
    - protection, 22
    - screwdriver, 30–33
    - screws, bolts and nuts, 33
    - wire crimpers, 34–35

- wire cutters, 23–25, 29
- wire strippers, 25–29
- hearing protection, 22
- indicators, 155
- inspection equipment, 45–46
- mind, 19–21
- physical measurement devices, 46–47
- power
  - 3D printers, 44
  - drills, 40–43
  - laser cutters, 43
- power-on indicator, 155
- power supply, 145–46
- USB charger
  - description, 147–148
  - voltage measurement, 149–153

Transformers, 82
Transistors
- BJTs, 83
- description, 83
- MOSFET, 84

Troubleshooting, 2

U

Unrepairable subassemblies, 127
USB charger
- cable
  - colors and functions, 152
  - internal wires, 151
- description, 147–148
- regulated power from, 155
- voltage measurement, 149–153

V

Variable resistors, 74–75
Voltmeters, 47–48

W, X, Y, Z

Weller controlled-temperature soldering station, 37
Wire and cables
- conductivity, 61–62
- description, 58–59
- longer version, 60–61
- Ohm's law, 62–63
- short version, 59–60
- storing, 63–64
- testing, 63

Wire crimpers, 34–35
Wire cutters, 23–25, 29
Wire strippers, 25–29
Wood screws, 33
Workshop. *See* Electronics lab

Building Your Own Electronics Lab

Dale Wheat

Apress®

Building Your Own Electronics Lab

Copyright © 2012 by Dale Wheat

All rights reserved. No part of this work may be reproduced or transmitted in any form or by any means, electronic or mechanical, including photocopying, recording, or by any information storage or retrieval system, without the prior written permission of the copyright owner and the publisher.

ISBN-13 (pbk): 978-1-4302-4386-1

ISBN-13 (electronic): 978-1-4302-4387-8

Trademarked names, logos, and images may appear in this book. Rather than use a trademark symbol with every occurrence of a trademarked name, logo, or image we use the names, logos, and images only in an editorial fashion and to the benefit of the trademark owner, with no intention of infringement of the trademark. The use in this publication of trade names, trademarks, service marks, and similar terms, even if they are not identified as such, is not to be taken as an expression of opinion as to whether or not they are subject to proprietary rights.

President and Publisher: Paul Manning
Lead Editor: Matt Moodie
Technical Reviewer: Cliff Wooton
Editorial Board: Steve Anglin, Mark Beckner, Ewan Buckingham, Gary Cornell, Morgan Ertel, Jonathan Gennick, Jonathan Hassell, Robert Hutchinson, Michelle Lowman, James Markham, Matthew Moodie, Jeff Olson, Jeffrey Pepper, Douglas Pundick, Ben Renow-Clarke, Dominic Shakeshaft, Gwenan Spearing, Matt Wade, Tom Welsh
Coordinating Editor: Brigid Duffy
Copy Editors: Damon Larson
Compositor: Bytheway Publishing Services
Indexer: SPi Global
Cover Designer: Anna Ishchenko

Distributed to the book trade worldwide by Springer Science+Business Media, LLC., 233 Spring Street, 6th Floor, New York, NY 10013. Phone 1-800-SPRINGER, fax (201) 348-4505, e-mail `orders-ny@springer-sbm.com`, or visit `www.springeronline.com`.

For information on translations, please e-mail `rights@apress.com`, or visit `www.apress.com`.

Apress and friends of ED books may be purchased in bulk for academic, corporate, or promotional use. eBook versions and licenses are also available for most titles. For more information, reference our Special Bulk Sales–eBook Licensing web page at `http://www.apress.com/bulk-sales`.

The information in this book is distributed on an “as is” basis, without warranty. Although every precaution has been taken in the preparation of this work, neither the author(s) nor Apress shall have any liability to any person or entity with respect to any loss or damage caused or alleged to be caused directly or indirectly by the information contained in this work.

Any source code or other supplementary materials referenced by the author in this text is available to readers at `www.apress.com`. For detailed information about how to locate your book’s source code, go to `http://www.apress.com/source-code/`.

To my father, John H. Wheat, who patiently taught me about electricity and electronics over 40 years ago. To this day, I remain fascinated by it. My life has been enriched in so many ways by the many things that I learned from my father.

Contents

- **About the Author** xi
- **About the Technical Reviewer** xii
- **Acknowledgments** xiii
- **Introduction** xiv
- **Chapter 1: Planning Your Electronics Workshop** 1
  - What to Expect 1
  - It Starts with a Plan 2
  - A Broad Outline 2
    - A Little Time 2
    - A Little Space 3
    - Basic Tools 3
    - Fundamental Components 4
    - Ideas 5
    - Goals 6
    - Inspiration! 7
  - How Electricity Works 7
    - The Theoretical Approach 7
    - A Practical Approach 9
  - Safety 10
  - Lighten Up! 11
  - Environmental Impact 14

Budgeting 14
Buying New 14
Finding Used 15
Harvesting or Recycling 15
Some Example Workshops 16
A Fresh Start 16
The Robot Clubhouse 17
A Cautionary Tale 17
Summary 18
■ **Chapter 2: Building Your Tool Chest 19**
The Most Important Tool Ever 19
Care and Feeding of Your Brain 21
All Those Other Bits, Too 21
Basic Hand Tools 22
Wire Cutters and Wire Strippers 23
Pliers and Tweezers 29
Screwdrivers, Nut Drivers, Wrenches, and Ratchets 30
Screws, Bolts, and Nuts 33
More Specialized Hand Tools 34
Wire Crimpers 34
Computers 35
Tools for Soldering 37
Power Tools 40
Drills and Drill Bits 40
Laser Cutters and 3D Printers 43
Basic Test and Measurement Equipment 44

Physical Measurement Devices 46

Simple Electronic Measurement Tools 47

Advanced Test and Measurement Equipment 49

Multimeters 50

Oscilloscopes 51

Power Supplies 55

Organizing Your Tools 56

Summary 56

■ **Chapter 3: Components 57**

Conductors and Interconnects 57

Electrical Schematics 57

Wire and Cables 58

Connectors 64

Passive Components 68

Resistors 68

Capacitors 76

Inductors 78

Switches 79

Active Components 81

Power Supplies 81

Diodes 82

LEDs 83

Transistors 83

Integrated Circuits 84

Acquiring Components 84

Buying New Components 85

Recycling Used Components 85

Component Data Sheets 86
Summary 86
Chapter 4: A Portable Mini-Lab 87
Have Lab, Will Travel 87
The Compact Executive Model 87
  No Soldering Required 90
  The Ever-Shrinking Computing Device 91
Electrical Experiments You Can Perform 91
  Lighten Up, 20th Century Style 91
  A Slightly More Permanent Circuit 95
  Multiple Uses for the LED 100
The Special Project Portable Laboratory 101
Summary 104
Chapter 5: The Cozy Corner Lab 105
The Rehabilitation of a Small but Useful Area 105
  Science to the Rescue! 106
  Organization 107
  The Great Divide 107
  Adding a Power Source 110
  A Clean, Well-Lighted Space 111
  Tools 112
  Under the Desk 115
  Components 115
  Where to Go from Here 116
Projects 116
  Parallel and Series Circuits 117
  Batteries in Series and Parallel 122

Switches in Series 123
Switches in Parallel 124
The Three-Way Switch 125
Resistors in Series 126
Resistors in Parallel 129
Capacitors in Series and Parallel 130
Inductors in Series and Parallel 130
LEDs in Series and Parallel 131
Summary 133
Chapter 6: The Small Group Lab and Classroom 135
Know Yourself 135
Facilitator or Coordinator 135
Teacher or Presenter 136
Participant 137
Observer 137
Know Your Group 137
Your Family 137
Your Friends 138
Coworkers and Fellow Students 138
Special-Interest Groups 139
The General Public 139
A Shared Resource 140
Be a Hospitable Host 140
Be a Courteous Guest 141
Workstations 142
Safety Planning 142
Presentations 143
Summary 143

■ **Appendix A: Getting Started with Tool Building..145**

A Very Simple Power Supply 145

An Easy 2.5 Watts...147

Adding Features...154

Various Indicators..155

Power-On Indicator..155

Power Supply Voltage..156

Power Supply Current..158

Summary 159

■ **Index 161**

About the Author

Dale Wheat is a full-time freelance writer, specializing in electronics and embedded systems. He has written several articles for technical and hobbyist magazines such as *Circuit Cellar*, O'Reilly's *MAKE* magazine, and *Elektor*. He teaches classes on electronics, microcontrollers, and soldering skills. He designs and sells DIY electronics kits from his web site, `http://dalewheat.com`. Before becoming a full-time writer, Dale consulted as a computer programmer and systems analyst for several companies, including IBM, MCI, and GTE (now Verizon). Dale is a two-term past president of the Dallas Personal Robotics Group, the world's oldest personal robotics club. He is a member of the National Honor Society, Phi Theta Kappa, and intends to continue his education as long as they keep the doors open. He lives with his wife, Anne, near Dallas, Texas.

About the Technical Reviewer

■ Cliff Wootton is a former Interactive TV systems architect at BBC News. The "News Loops" service developed there was nominated for a BAFTA and won a Royal Television Society Award for Technical Innovation. An invited speaker on pre-processing for video compression at the Apple WWDC conference. Taught post graduate MA students about real-world computing, multimedia, video compression, metadata and researching the deployment of next generation interactive TV systems based on open standards.

Currently working on R&D projects investigating new Interactive TV technologies, involved with MPEG standards working groups, writing more books on the topic and speaking at conferences when not lecturing on Multimedia at the University of the Arts in London.

Acknowledgments

This book was Michelle Lowman's idea. I just wrote down some of the words.

Corbin Collins and Brigid Duffy, coordinating editors at Apress, helped keep me on track with this project, despite all my best efforts. Cliff Wootton and Alan Smith provided excellent insight and suggestions to help the chapters along. The entire Apress editorial and production teams make what could be a hard job into a thing of joy.

My wife, Anne, continues to buy into the fantasy that I am a "professional writer," giving me the time and space I need to do this. Her patience, love, support, and trust make all the difference in the world.

My good neighbor and friend Jerry Johnson's fervent prayers and constant encouragement and enthusiasm really helped pull this project through the difficult times that were encountered. While I was complaining about "narrative pacing and clarity," he underwent brain surgery (twice) and chemotherapy for cancer, always with a smiling laugh and a twinkle in his eye.

VOL. 1

Charles Platt

Encyclopedia of Electronic Components

Power Sources & Conversion

Resistors ▪ Capacitors ▪ Inductors
Switches ▪ Encoders ▪ Relays ▪ Transistors

O'REILLY®

Make:
makezine.com

Encyclopedia of Electronic Components Volume 1

Charles Platt

O'REILLY®
Beijing • Cambridge • Farnham • Köln • Sebastopol • Tokyo

Encyclopedia of Electronic Components Volume 1

by Charles Platt

Copyright © 2013 Helpful Corporation. All rights reserved.

Printed in the United States of America.

Published by O'Reilly Media, Inc., 1005 Gravenstein Highway North, Sebastopol, CA 95472.

O'Reilly books may be purchased for educational, business, or sales promotional use. Online editions are also available for most titles (*http://my.safaribooksonline.com*). For more information, contact our corporate/institutional sales department: 800-998-9938 or *corporate@oreilly.com*.

Editor: Brian Jepson
Production Editor: Melanie Yarbrough
Proofreader: Melanie Yarbrough
Indexer: Judy McConville

Cover Designer: Mark Paglietti
Interior Designer: Edie Freedman and Nellie McKesson
Illustrator: Charles Platt
Photographer: Charles Platt
Cover Production: Randy Comer

October 2012: First Edition

Revision History for the First Edition:

2012-10-03 First release

See *http://oreilly.com/catalog/errata.csp?isbn=9781449333898* for release details.

Nutshell Handbook, the Nutshell Handbook logo, and the O'Reilly logo are registered trademarks of O'Reilly Media, Inc. *Encyclopedia of Electronic Components Volume 1*, the cover images, and related trade dress are trademarks of O'Reilly Media, Inc.

Many of the designations used by manufacturers and sellers to distinguish their products are claimed as trademarks. Where those designations appear in this book, and O'Reilly Media, Inc., was aware of a trademark claim, the designations have been printed in caps or initial caps.

While every precaution has been taken in the preparation of this book, the publisher and authors assume no responsibility for errors or omissions, or for damages resulting from the use of the information contained herein.

ISBN: 978-1-449-33389-8

[TI]

To Mark Frauenfelder, who reacquainted me with the pleasures of Making.

Table of Contents

Preface . . . . **xix**

1. How to Use This Book 1

Reference vs. Tutorial 1
Theory and Practice 1
Organization 1
Subject Paths 2
Inclusions and Exclusions 2
Typographical Conventions 3
Volume Contents 3
Safari® Books Online 3
How to Contact Us 4

> POWER

> > SOURCE

2. Battery 5

What It Does 5
How It Works 6
    Electrode Terminology 7
Variants 7
    Disposable Batteries 8
    Rechargeable Batteries 9
Values 11
    Amperage 11
    Capacity 11
    Voltage 13
How To Use It 14

What Can Go Wrong . . . 15
    Short Circuits: Overheating And Fire . . . 15
    Diminished Performance Caused By Improper Recharging . . 15
    Complete Discharge Of Lead-Acid Battery . . . 15
    Inadequate Current . . . 15
    Incorrect Polarity . . . 15
    Reverse Charging . . . 16
    Sulfurization . . . 16
    High Current Flow Between Parallel Batteries . . . 16

> > CONNECTION

3. Jumper . . . 17
What It Does . . . 17
How It Works . . . 17
Variants . . . 18
Values . . . 18
How To Use It . . . 19
What Can Go Wrong . . . 19

4. Fuse . . . 21
What It Does . . . 21
How It Works . . . 21
Values . . . 22
Variants . . . 22
    Small Cartridge Fuses . . . 23
    Automotive Fuses . . . 23
    Strip Fuses . . . 24
    Through-Hole Fuses . . . 24
    Resettable Fuses . . . 24
    Surface Mount Fuses . . . 26
How To Use It . . . 26
What Can Go Wrong . . . 27
    Repeated Failure . . . 27
    Soldering Damage . . . 27
    Placement . . . 28

5. Pushbutton . . . 29
What It Does . . . 29
How It Works . . . 29
Variants . . . 30
    Poles And Throws . . . 30
    On-Off Behavior . . . 30
    Slider . . . 31
    Styles . . . 31
    Termination And Contact Plating . . . 32
    Mounting Style . . . 32
    Sealed Or Unsealed . . . 32

Latching 33
Foot Pedal 33
Keypad 33
Tactile Switch 34
Membrane Pad 34
Radio Buttons 35
Snap-Action Switches 35
Emergency Switch 35
Values 35
How To Use It 35
What Can Go Wrong 35
No Button 35
Mounting Problems 35
LED Issues 36
Other Problems 36

6. **Switch** **37**
What It Does 37
How It Works 37
Variants 38
Terminology 38
Poles And Throws 38
On-Off Behavior 39
Snap-Action 39
Rocker 40
Slider 40
Toggle 41
DIP 43
SIP 44
Paddle 44
Vandal Resistant Switch 45
Tactile Switch 45
Mounting Options 45
Termination 45
Contact Plating Options 45
Values 45
How To Use It 46
Power Switches 46
Limit Switches 46
Logic Circuits 47
Alternatives 47
What Can Go Wrong 47
Arcing 47
Dry Joints 48
Short Circuits 48
Contact Contamination 48
Wrong Terminal Type 48
Contact Bounce 48

Mechanical Wear 48
Mechanical Wear 48
Mounting Problems 48
Cryptic Schematics 49

7. Rotary Switch **51**
What It Does 51
How It Works 52
Variants 52
Conventional 52
Rotary DIP 53
Gray Code 54
PC Board Rotary Switch 55
Mechanical Encoder 55
Pushwheel And Thumbwheel 55
Keylock 55
Values 56
How To Use It 56
What Can Go Wrong 57
Vulnerable Contacts 57
Contact Overload 57
Misalignment 57
Misidentified Shorting Switch 57
User Abuse 57
Wrong Shaft, Wrong Knobs, Nuts That Get Lost, Too Big To Fit 57

8. Rotational Encoder **59**
What It Does 59
How It Works 59
Variants 60
Pulses And Detents 61
Format 61
Output 61
Rotational Resistance 61
Values 61
Contact Bounce 61
Sliding Noise 62
How To Use It 62
What Can Go Wrong 62
Switch Bounce 62
Contact Burnout 63

9. Relay **65**
What It Does 65
How It Works 66
Variants 67
Latching 67
Polarity 67
Pinout Variations 67

        Reed Relay 68
        Small Signal Relay 68
        Automotive Relays 69
        General Purpose/Industrial 69
        Time Delay Relay 69
        Contactor 70
    Values 70
    How To Use It 71
    What Can Go Wrong 72
        Wrong Pinouts 72
        Wrong Orientation 72
        Wrong Type 72
        Wrong Polarity 72
        AC And DC 72
        Chatter 72
        Relay Coil Voltage Spike 72
        Arcing 72
        Magnetic Fields 72
        Environmental Hazards 73

> > MODERATION

10. **Resistor** **75**
    What It Does 75
    How It Works 76
    Variants 76
        Resistor Array 77
    Values 79
        Tolerance 79
        Value Coding 81
        Stability 82
        Materials 82
    How To Use It 84
        In Series With LED 84
        Current Limiting With A Transistor 84
        Pullup And Pulldown Resistors 85
        Audio Tone Control 85
        RC Network 85
        Voltage Divider 86
        Resistors In Series 86
        Resistors In Parallel 86
    What Can Go Wrong 87
        Heat 87
        Noise 87
        Inductance 87
        Inaccuracy 87

Wrong Values 88

11. **Potentiometer** **89**
What It Does 89
How It Works 90
Variants 90
Linear And Log Taper 90
Classic-Style Potentiometer 91
Multiple-Turn Potentiometer 92
Ganged Potentiometer 93
Switched Potentiometer 93
Slider Potentiometer 93
Trimmer Potentiometer 93
How To Use It 94
What Can Go Wrong 95
Wear And Tear 95
Knobs That Don’t Fit 95
Nuts That Get Lost 95
A Shaft That Isn’t Long Enough 96
Sliders With No Finger Grip 96
Too Big To Fit 96
Overheating 96
The Wrong Taper 96

12. **Capacitor** **97**
What It Does 97
How It Works 97
Variants 99
Format 99
Principal Types 101
Dielectrics 103
Values 104
Farads 104
Commonly Used Values 104
Dielectric Constant 105
The Time Constant 105
Multiple Capacitors 106
Alternating Current And Capacitive Reactance 106
Equivalent Series Resistance 106
How To Use It 107
Bypass Capacitor 107
Coupling Capacitor 107
High-Pass Filter 107
Low-Pass Filter 107
Smoothing Capacitor 108
Snubber 108
Capacitor As A Battery Substitute 109
What Can Go Wrong 109

Wrong Polarity 110
Voltage Overload 110
Leakage 110
Dielectric Memory 110
Specific Electrolytic Issues 110
Heat 110
Vibration 110
Misleading Nomenclature 111

13. Variable Capacitor 113

What It Does 113
How It Works 113
Variants 114
  Values 115
  Formats 115
How To Use It 115
What Can Go Wrong 117
  Failure To Ground Trimmer Capacitor While Adjusting It . . . 117
  Application Of Overcoat Material Or “Lock Paint” 117
  Lack Of Shielding 117

14. Inductor 119

What It Does 119
How It Works 120
  DC Through A Coil 121
  Magnetic Core 122
  EMF And Back-EMF 122
  Electrical And Magnetic Polarity 123
Variants 124
  Magnetic Cores 124
  Nonmagnetic Cores 125
  Variable Inductors 125
  Ferrite Beads 126
  Toroidal Cores 126
  Gyrator 127
Values 128
  Calculating Inductance 128
  Calculating Reactance 128
  Calculating Reluctance 129
  Datasheet Terminology 129
  Series And Parallel Configurations 129
  Time Constant 129
How To Use It 130
  Core Choices 132
  Miniaturization 132
What Can Go Wrong 132
  Real-World Defects 132
  Saturation 132

RF Problems 133

> > CONVERSION

15. **AC-AC Transformer** 135
- What It Does 135
- How It Works 136
  - The Core 137
  - Taps 137
- Variants 138
  - Core Shapes 138
  - Power Transformer 138
  - Plug-In Transformer 139
  - Isolation Transformer 139
  - Autotransformer 140
  - Variable Transformer 140
  - Audio Transformer 140
  - Split-Bobbin Transformer 141
  - Surface-Mount Transformer 141
- Values 141
- How To Use It 142
- What Can Go Wrong 142
  - Reversal Of Input And Output 142
  - Shock Hazard From Common Ground 142
  - Accidental DC Input 142
  - Overload 142
  - Incorrect AC Frequency 142

16. **AC-DC Power Supply** 143
- What It Does 143
- Variants 143
  - Linear Regulated Power Supply 143
  - Switching Power Supply 144
  - Unregulated Power Supply 146
  - Adjustable Power Supply 146
  - Voltage Multiplier 146
- Formats 146
- How To Use It 147
- What Can Go Wrong 147
  - High Voltage Shock 147
  - Capacitor Failure 147
  - Electrical Noise 147
  - Peak Inrush 147

17. **DC-DC Converter** 149
- What It Does 149
- How It Works 149
- Variants 150

        - Buck Converter . . . 150
        - Boost Converter . . . 151
        - Flyback Converter With Inductor . . . 151
        - Flyback Converter With Transformer . . . 151
        - Formats . . . 151
    - Values . . . 152
        - Nominal Input Voltage And Frequency . . . 152
        - Output Voltage . . . 153
        - Input Current And Output Current . . . 153
        - Load Regulation . . . 153
        - Efficiency . . . 153
        - Ripple And Noise . . . 154
        - Isolated Or Non-Isolated . . . 154
    - How To Use It . . . 154
    - What Can Go Wrong . . . 155
        - Electrical Noise In Output . . . 155
        - Excess Heat With No Load . . . 155
        - Inaccurate Voltage Output With Low Load . . . 155

- 18. **DC-AC Inverter** . . . **157**
    - What It Does . . . 157
    - How It Works . . . 157
    - Variants . . . 158
    - Values . . . 158
    - How To Use It . . . 159
    - What Can Go Wrong . . . 160

> > REGULATION

- 19. **Voltage Regulator** . . . **161**
    - What It Does . . . 161
    - How It Works . . . 161
    - Variants . . . 163
        - Packaging . . . 163
        - Popular Varieties . . . 163
        - Adjustable Regulators . . . 163
        - Negative And Positive Regulators . . . 164
        - Low-Dropout Linear Regulators . . . 164
        - Quasi-Low-Dropout Linear Regulators . . . 165
        - Additional Pin Functions . . . 165
    - Values . . . 165
    - How To Use It . . . 165
    - What Can Go Wrong . . . 166
        - Inadequate Heat Management . . . 166
        - Transient Response . . . 166
        - Misidentified Parts . . . 166
        - Misidentified Pins . . . 167
        - Dropout Caused By Low Battery . . . 167

- Inaccurate Delivered Voltage 167

> ELECTROMAGNETISM

> > LINEAR

- 20. **Electromagnet** **169**
  - What It Does 169
  - How It Works 169
  - Variants 170
  - Values 171
  - How To Use It 171
  - What Can Go Wrong 172
- 21. **Solenoid** **173**
  - What It Does 173
  - How It Works 174
  - Variants 176
    - Low Profile 176
    - Latching 176
    - Rotary 176
    - Hinged Clapper 176
  - Values 176
    - Coil Size Vs. Power 177
  - How To Use It 177
  - What Can Go Wrong 177
    - Heat 177
    - AC Inrush 177
    - Unwanted EMF 177
    - Loose Plunger 177

> > ROTATIONAL

- 22. **DC Motor** **179**
  - What It Does 179
  - How It Works 179
  - Variants 181
    - Coil Configurations 181
    - Gearhead Motor 181
    - Brushless DC Motor 183
    - Linear Actuator 184
    - Values 184
  - How To Use It 185
    - Speed Control 186
    - Direction Control 186
    - Limit Switches 187
  - What Can Go Wrong 187

Brushes And Commutator 187
Electrical Noise 187
Heat Effects 188
Ambient Conditions 188
Wrong Shaft Type Or Diameter 188
Incompatible Motor Mounts 188
Backlash 188
Bearings 188
Audible Noise 189

23. AC Motor 191
What It Does 191
How It Works 191
  Stator Design 191
  Rotor Design 192
Variants 195
  Single-Phase Induction Motor 195
  Three-Phase Induction Motor 196
  Synchronous Motor 196
  Reluctance Motor 197
  Variable Frequency Drive 198
  Wound-Rotor AC Induction Motor 198
  Universal Motor 198
  Inverted AC Motors 199
Values 199
How To Use It 199
What Can Go Wrong 200
  Premature Restart 200
  Frequent Restart 200
  Undervoltage Or Voltage Imbalance 200
  Stalled Motor 200
  Protective Relays 200
  Excess Torque 200
  Internal Breakage 200

24. Servo Motor 201
What It Does 201
How It Works 201
Variants 203
Values 204
How To Use It 205
  Modification For Continuous Rotation 206
What Can Go Wrong 206
  Incorrect Wiring 206
  Shaft/Horn Mismatch 206
  Unrealistically Rapid Software Commands 207
  Jitter 207
  Motor Overload 207

Unrealistic Duty Cycle 207
Electrical Noise 207

25. **Stepper Motor** **209**
What It Does 209
How It Works 209
Reluctance Stepper Motors 210
Permanent Magnet Stepper Motors 211
Bipolar Stepper Motors 213
Unipolar Motors 213
Variants 214
High Phase Count 214
Hybrid 216
Bifilar 216
Multiphase 216
Microstepping 217
Sensing And Feedback 217
Voltage Control 217
Values 218
How To Use It 218
Protection Diodes 218
Positional Control 219
What Can Go Wrong 219
Incorrect Wiring 219
Step Loss 219
Excessive Torque 219
Hysteresis 220
Resonance 220
Hunting 220
Saturation 220
Rotor Demagnetization 220

> DISCRETE SEMICONDUCTOR

> > SINGLE JUNCTION

26. **Diode** **221**
What It Does 221
How It Works 223
Variants 224
Packaging 224
Signal Diodes 224
Rectifier Diodes 224
Zener Diode 224
Transient Voltage Suppressor (TVS) 225
Schottky Diode 225
Varactor Diode 225

        - Tunnel Diode, Gunn Diode, PIN Diode 226
        - Diode Array 226
        - Bridge Rectifier 226
    - Values 226
    - How To Use It 227
        - Rectification 227
        - Back-EMF Suppression 228
        - Voltage Selection 229
        - Voltage Clamping 230
        - Logic Gate 230
        - DC Voltage Regulation And Noise Suppression 230
        - AC Voltage Control And Signal Clipping 231
        - Voltage Sensing 231
    - What Can Go Wrong 232
        - Overload 232
        - Reversed Polarity 233
        - Wrong Type Of Diode 233

27. Unijunction Transistor 235
    - What It Does 235
    - How It Works 236
    - Variants 238
    - Values 238
        - How To Use It 239
    - What Can Go Wrong 239
        - Name Confusion 239
        - Incorrect Bias 239
        - Overload 240

> > MULTI-JUNCTION

28. Bipolar Transistor 241
    - What It Does 241
    - How It Works 241
        - Current Gain 244
        - Terminology 245
    - Variants 245
        - Packaging 245
        - Connections 246
    - How To Use It 246
        - Darlington Pairs 248
        - Amplifiers 250
    - What Can Go Wrong 251
        - Wrong Connections On A Bipolar Transistor 251
        - Wrong Connections On A Darlington Pair Chip 251
        - Soldering Damage 252
        - Excessive Current Or Voltage 252

Excessive Leakage 252

28. Field Effect Transistor 253
What It Does 253
How It Works 253
JFETs 253
JFET Behavior 255
MOSFETs 256
The Substrate Connection 261
Variants 262
MESFET 262
V-Channel MOSFET 262
Trench MOS 262
Values 262
How To Use It 263
P-Channel Disadvantage 263
Bipolar Substitution 263
Amplifier Front Ends 263
Voltage-Controlled Resistor 263
Compatibility With Digital Devices 263
What Can Go Wrong 263
Static Electricity 263
Heat 263
Wrong Bias 264

Appendix A. Schematic Symbols 265

Index 269

Preface

At a time when information is widely and freely available in greater quantities than ever before, the reader may wonder whether *The Encyclopedia of Electronic Components* is really necessary. Surely, anything you want to know can be found online?

Well, yes and no. Let's consider the available resources.

1. Datasheets

Datasheets are indispensable, but they have limitations. Some are detailed; others are skimpy. Some show you sample schematics as a guide to using a component; many don't. None of them tells you much about how a component works, because that's not their purpose. Often they don't mention other components that must be added. Some datasheets for DC-DC converters, for instance, say nothing at all about bypass capacitors, even though the capacitors may be essential. A datasheet for an optocoupler says nothing about the pullup resistor required by the open-collector output.

Datasheets don't facilitate comparison shopping. A datasheet from one manufacturer will not compare its products with those from another manufacturer, and may not even provide much guidance about alternatives that are available from the same manufacturer. For example, a datasheet for a linear voltage regulator won't suggest that you might do better to use a DC-DC converter in an application where high efficiency is important.

Most of all, datasheets don't tell you how to avoid common mistakes. What actually happens if you connect that tantalum capacitor the wrong way around? A datasheet gives you the customary list of absolute maximum values, and after that, you are on your own, burning things out, encountering mysterious electronic behavior, and discovering limitations that are so well known, the datasheet didn't bother to mention them. In my experience, relying on datasheets creates a significant risk of reinventing the wheel.

2. Wikipedia

Wikipedia's coverage of electronics is impressive but inconsistent. Some entries are elementary, while others are extremely technical. Some are shallow, while others are deep. Some are well organized, while others run off into obscure topics that may have interested one of the contributors but are of little practical value to most readers. Many topics are distributed over multiple entries, forcing you to hunt through several URLs. Overall, Wikipedia tends to be good if you want theory, but not-so-good if you want hands-on practicality.

3. Manufacturers' Tutorials

A few helpful and enlightened manufacturers have compiled highly authoritative, instructional overviews of the components that they sell. Littelfuse, for instance, publishes an excellent series of documents telling you everything you could possibly want to know about fuses. But now you encounter a different problem: There is so much information, you'll need a couple of hours to dig through it all. Also, because the tutorials tend not to receive high page rankings on Google, they can be hard to find. And if a manufacturer has gaps in its product line, its tutorial is unlikely to mention them. Consequently, you won't know what's missing.

4. Personal Guides

It is a well-known attribute of the Web that many individuals feel the impulse to share everything they know (or think they know) about a particular topic. These personal guides can present surprisingly thorough online coverage of relatively obscure issues, such as the types of capacitors most suitable for loudspeaker crossover circuits, or the correct derivation of amp-hour numbers for lead-acid batteries. Unfortunately, on some sites you can also find errors, unsubstantiated opinions, plagiarism, and eccentricity. My general rule is that three or more guides generally have to agree with each other before their statements can be trusted—and even then, I have a small residue of doubt. The search-inspect-and-verify process can take a while.

So—yes, the information that you want usually does exist somewhere online, but no, it may not be easy to find. The vastness of the Web is not organized like an encyclopedia.

What about books? Generally speaking, they tend to be entry-level, or they specialize in narrow areas. A few broad-ranging books are truly excellent, but they are primarily educational, organized in an instructional sequence. They are not reference books.

The Encyclopedic Solution

Scarcity or inaccessibility of information ceased to be a problem many years ago. Its vast quantity, inconsistency, and dispersal have become the new barriers to acquiring knowledge. If you have to go hunting among datasheets, Wikipedia, manufacturers' tutorials (which may or may not exist), personal guides (which may have unrevealed bias), and multiple educational books, the process will be inconvenient and time-consuming. If you plan to revisit the topic in the future, you'll have to remember which URLs were useful and which ones weren't—and you may find that many of them are not even there anymore.

When I considered these issues during my own work as an electronics columnist for *Make* magazine, I saw a real need for a fact-checked, cross-referenced encyclopedia that would compile the basic information about components concisely, in an organized, consistent format, with informative photographs, schematics, and diagrams. It might save many people a lot of search time if it could summarize how components work, how to use them, what the alternatives are, and what the common errors and problems may be.

That is the modest ambition of *The Encyclopedia of Electronic Components*.

The Audience

Like any reference work, this one hopes to serve two categories of readers: The informed and the not-yet-informed.

Perhaps you are learning electronics, and you see a part listed in a catalog. It looks interesting, but the catalog doesn't tell you exactly what the part does or how it is commonly used. You need to look it up either by function or by name, but you're not sure where to start. An encyclopedic reference can simplify the fact-finding process, can save you from ordering a part that may be inappropriate, and can tell you how it should be used.

Perhaps, instead, you are an electronics engineer or hobbyist, thinking about a new circuit. You remember using a component three or four years ago, but your recollection may not be reliable. You need to refresh your memory with a quick summary—and so, you open the encyclopedia, just to make sure.

Completeness

Obviously, this book cannot include every component that exists. Mouser Electronics claims to have more than 2 million products listed in its online database. *The Encyclopedia of Electronic Components* only has room for a fraction of that number—but still, it can refer you to the primary types. The electronic edition of this book should allow easy insertions and updates. My hope is that it can become an ever-expanding resource.

Acknowledgments

Any reference work draws inspiration from many sources, and this one is no exception. Three were of special importance:

Practical Electronics for Inventors by Paul Scherz (second edition) McGraw-Hill, 2007

Electronic Devices and Circuit Theory by Robert L. Boylestad and Louis Nashelsky (ninth edition) Pearson Education Inc., 2006

The Art of Electronics by Paul Horowitz and Winfield Hill (second edition) Cambridge University Press, 2006

I also made extensive use of information gleaned through Mouser Electronics and Jameco Electronics. And where would any of us be without *Getting Started in Electronics* by Forrest M. Mims III, or *The TTL Cookbook* by Don Lancaster?

In addition, there were individuals who provided special assistance. My editor, Brian Jepson, was immensely helpful in the development of the project. Michael Butler contributed greatly to the early concept and its structure. Josh Gates did resourceful research. My publishers, O'Reilly Media, demonstrated their faith in my work. Kevin Kelly unwittingly influenced me with his legendary interest in "access to tools."

Primary fact checkers were Eric Moberg, Chris Lirakis, Jason George, Roy Rabey, Emre Tuncer, and Patrick Fagg. I am indebted to them for their help. Any remaining errors are, of course, my responsibility.

Lastly I should mention my school friends from decades ago: Hugh Levinson, Patrick Fagg, Graham Rogers, William Edmondson, and John Witty, who helped me to feel that it was okay to be a nerdy kid building my own audio equipment, long before the word "nerd" existed.

—Charles Platt, 2012

How to Use This Book

1

To avoid misunderstandings regarding the purpose and method of this book, here is a quick guide regarding the way in which it has been conceived and organized.

Reference vs. Tutorial

As its title suggests, this is a reference book, not a tutorial. In other words, it does not begin with elementary concepts and build sequentially toward concepts that are more advanced.

You should be able to dip into the text at any point, locate the topic that interests you, learn what you need to know, and then put the book aside. If you choose to read it straight through from beginning to end, you will not find concepts being introduced in a sequential, cumulative manner.

My book *Make:Electronics* follows the tutorial approach. Its range, however, is more circumscribed than that of this encyclopedia, because a tutorial inevitably allocates a lot of space to step-by-step explanations and instructions.

Theory and Practice

This book is oriented toward practicality rather than theory. I am assuming that the reader mostly wants to know how to use electronic components, rather than why they work the way they do. Consequently I have not included any proofs of formulae, any definitions rooted in electrical theory, or any historical background. Units are defined only to the extent that is necessary to avoid confusion.

Many books on electronics theory already exist, if theory is of interest to you.

Organization

The encyclopedia is divided into entries, each entry being devoted to one broad type of component. Two rules determine whether a component has an entry all to itself, or is subsumed into another entry:

1. A component merits its own entry if it is (a) widely used or (b) not-so-widely used but has a unique identity and maybe some historical status. A widely used component would be a **bipolar transistor**, while a not-so-widely-used component with a unique identity would be a **unijunction transistor**.
2. A component does not merit its own entry if it is (a) seldom used or (b) very similar in function to another component that is more widely used. For example, the *rheostat* is sub-

sumed into the **potentiometer** section, while *silicon diode*, *Zener diode*, and *germanium diode* are combined together in the **diode** entry.

Inevitably, these guidelines required judgment calls that in some cases may seem arbitrary. My ultimate decision was based on where I would expect to find a component if I was looking for it myself.

Subject Paths

Entries are not organized alphabetically. Instead they are grouped by subject, in much the same way that books in the nonfiction section of a library are organized by the Dewey Decimal System. This is convenient if you don't know exactly what you are looking for, or if you don't know all the options that may be available to perform a task that you have in mind.

Each primary category is divided into subcategories, and the subcategories are divided into component types. This hierarchy is shown in Figure 1-1. It is also apparent when you look at the top of the first page of each entry, where you will find the path that leads to it. The **capacitor** entry, for instance, is headed with this path:

power > moderation > capacitor

Any classification scheme tends to run into exceptions. You can buy a chip containing a *resistor array*, for instance. Technically, this is an *analog integrated circuit*, but should it really be included with solid-state relays and comparators? A decision was made to put it in the **resistor** section, because this seemed more useful.

Some components have hybrid functions. In Volume 2, in the *integrated circuit* subcategory, we will distinguish between those that are *analog* and those that are *digital*. So where should an **analog-digital converter** be listed? It will be found under *analog*, because that category seems better associated with its primary function, and people may be more likely to look for it there.

Primary Category	Secondary Category	Component Type
power	source	battery
	connection	jumper
		fuse
		pushbutton
		switch
		rotary switch
		rotational encoder
	moderation	relay
		resistor
		potentiometer
		capacitor
		variable capacitor
	conversion	inductor
		AC-AC transformer
		AC-DC power supply
		DC-DC converter
		DC-AC inverter
	regulation	voltage regulator
electromagnetism	linear output	electromagnet
		solenoid
	rotational output	DC motor
		AC motor
		servo motor
		stepper motor
discrete semiconductor	single junction	diode
		unijunction transistor
	multi-junction	bipolar transistor
		field-effect transistor

Figure 1-1. *The subject-oriented organization of categories and entries in this encyclopedia.*

Inclusions and Exclusions

There is also the question of what is, and what is not, a component. Is wire a component? Not for the purposes of this encyclopedia. How about a **DC-DC converter**? Because converters are now sold in small packages by component suppliers, they have been included as components.

Many similar decisions had to be made on a case-by-case basis. Undoubtedly, some readers will disagree with the outcome, but reconciling all the disagreements would have been impossible. Speaking personally, the best I could do was create a book that is organized in the way that would suit me best if I were using it myself.

Typographical Conventions

Throughout this encyclopedia, the names of components that have their own entries are presented in **bold type.** Other important electronics terms or component names are presented in *italics* where they first appear in any one section.

The names of components, and the categories to which they belong, are all set in lower-case type, except where a term is normally capitalized because it is an acronym or a trademark. *Trimpot*, for instance, is trademarked by Bourns, but *trimmer* is not. **LED** is an acronym, but *cap* (abbreviation for **capacitor**) is not.

Where formulae are used, they are expressed in a format that will be familiar to computer programmers but may be unfamiliar to others. The * (asterisk) symbol is used in place of a multiplication sign, while the / (slash symbol) is used to indicate division. Where pairs of parentheses are nested, the most deeply nested pair identifies the operations that should be performed first.

Volume Contents

Practical considerations relating to book length influenced the decision to divide *The Encyclopedia of Electronic Components* into three volumes. Each volume deals with broad subject areas as follows.

Volume 1

Power, electromagnetism, and discrete semiconductors.

The *power* category includes sources of power and methods to distribute, store, interrupt, and modify power. The *electromagnetism* category includes devices that exert force linearly, and others that create a turning force. *Discrete semiconductors* include the main types of diodes and transistors.

Volume 2

Integrated circuits, light sources, sound sources, heat sources, and high-frequency sources.

Integrated circuits are divided into analog and digital components. *Light sources* range from incandescent bulbs to LEDs and small display screens; some reflective components, such as liquid-crystal displays and e-ink, are also included. *Sound sources* are primarily electromagnetic.

Volume 3

Sensing devices.

The field of sensors has become so extensive, they easily merit a volume to themselves. *Sensing devices* include those that detect light, sound, heat, motion, pressure, gas, humidity, orientation, electricity, proximity, force, and radiation.

At the time of writing, volumes 2 and 3 are still in preparation, but their contents are expected to be as described above.

Safari® Books Online

Safari Books Online is an on-demand digital library that lets you easily search over 7,500 technology and creative reference books and videos to find the answers you need quickly.

With a subscription, you can read any page and watch any video from our library online. Read books on your cell phone and mobile devices. Access new titles before they are available for print, and get exclusive access to manuscripts in development and post feedback for the authors.

Copy and paste code samples, organize your favorites, download chapters, bookmark key sections, create notes, print out pages, and benefit from tons of other time-saving features.

O'Reilly Media has uploaded this book to the Safari Books Online service. To have full digital access to this book and others on similar topics from O'Reilly and other publishers, sign up for free at *http://my.safaribooksonline.com*.

How to Contact Us

Please address comments and questions concerning this book to the publisher:

MAKE
1005 Gravenstein Highway North
Sebastopol, CA 95472
800-998-9938 (in the United States or Canada)
707-829-0515 (international or local)
707-829-0104 (fax)

MAKE unites, inspires, informs, and entertains a growing community of resourceful people who undertake amazing projects in their backyards, basements, and garages. MAKE celebrates your right to tweak, hack, and bend any technology to your will. The MAKE audience continues to be a growing culture and community that believes in bettering ourselves, our environment, our educational system—our entire world. This is much more than an audience, it's a worldwide movement that Make is leading—we call it the Maker Movement.

For more information about MAKE, visit us online:

MAKE magazine: *http://makezine.com/magazine/*
Maker Faire: *http://makerfaire.com*
Makezine.com: *http://makezine.com*
Maker Shed: *http://makershed.com/*

We have a web page for this book, where we list errata, examples, and any additional information. You can access this page at:

http://oreil.ly/encyc_electronic_comp_v1

To comment or ask technical questions about this book, send email to:

bookquestions@oreilly.com

For more information about our books, courses, conferences, and news, see our website at *http://www.oreilly.com*.

Find us on Facebook: *http://facebook.com/oreilly*

Follow us on Twitter: *http://twitter.com/oreillymedia*

Watch us on YouTube: *http://www.youtube.com/oreillymedia*

battery

2

This entry covers electrochemical power sources. Electricity is most often generated electromagnetically, but since these sources cannot be classified as components, they are outside the scope of the encyclopedia. Electrostatic sources are excluded for similar reasons.

A battery is sometimes referred to as a *cell* or *power cell*, but can actually contain multiple cells, as defined in this entry. It used to be called an *accumulator* or a *pile*, but those terms are now archaic.

OTHER RELATED COMPONENTS

- **capacitor** (see Chapter 12)

What It Does

A battery contains one or more *electrochemical cells* in which chemical reactions create an electrical potential between two immersed terminals. This potential can be discharged as *current* passing through a *load*.

An electrochemical cell should not be confused with an *electrolytic cell*, which is powered by an external source of electricity to promote *electrolysis*, whereby chemical compounds are broken down to their constituent elements. An electrolytic cell thus consumes electricity, while an electrochemical cell produces electricity.

Batteries range in size from *button cells* to large *lead-acid* units that store power generated by solar panels or windmills in locations that can be off the grid. Arrays of large batteries can provide bridging power for businesses or even small communities where conventional power is unreliable. Figure 2-1 shows a 60KW, 480VDC self-watering battery array installed in a corporate data center, supplementing wind and solar sources and providing time-of-day peak shaving of energy usage. Each lead-acid battery in this array measures approximately 28″ × 24″ × 12″ and weighs about 1,000 lb.



Figure 2-1. *A battery array providing 60KW at 480VDC as backup for a corporate data center. (Photo by permission of Hybridyne Power Systems, Canada, Inc., and the Hybridyne group of companies. Copyright by Hybridyne, an internationally registered trademark of Hybridyne Power Systems Canada Inc. No right of further reproduction unless specifically granted by Hybridyne.)*

Schematic symbols for a battery are shown in Figure 2-2. The longer of the two lines represents the positive side of the battery, in each case. One way to remember this is by imagining that the longer line can be snipped in half so that the two segments can combine to form a + sign. Traditionally, multiple connected battery symbols indicate multiple cells inside a battery; thus the center symbols in the figure could indicate a 3V battery, while those on the right would indicate a voltage greater than 3V. In practice, this convention is not followed conscientiously.



Figure 2-2. *Schematic symbols for a battery. Each pair of symbols within a blue rectangle is functionally identical.*

How It Works

In a basic battery design often used for demonstration purposes, a piece of copper serves as an *electrode*, partially immersed in a solution of copper sulfate, while a piece of zinc forms a second electrode, partially immersed in a solution of zinc sulfate. Each sulfate solution is known as an *electrolyte*, the complete battery may be referred to as a *cell*, and each half of it may be termed a *half-cell*.

A simplified cross-section view is shown in Figure 2-3. Blue arrows show the movement of electrons from the zinc terminal (the *anode*), through an external load, and into a copper terminal (the *cathode*). A *membrane separator* allows the electrons to circulate back through the battery, while preventing electrolyte mixing.

Orange arrows represent positive copper *ions*. White arrows represent positive zinc ions. (An ion is an atom with an excess or deficit of electrons.) The zinc ions are attracted into the zinc sulfate electrolyte, resulting in a net loss of mass from the zinc electrode.

Meanwhile, electrons passing into the copper electrode tend to attract positive copper ions, shown as orange arrows in the diagram. The copper ions are drawn out of the copper sulfate electrolyte, and result in a net accumulation of copper atoms on the copper electrode.

This process is energized partially by the fact that zinc tends to lose electrons more easily than copper.



Figure 2-3. *A classically simple electrochemical cell. See text for additional details.*

Batteries for use in consumer electronics typically use a paste instead of a liquid as an electrolyte, and have been referred to as *dry cells*, although this term is becoming obsolete. The two half-cells may be combined concentrically, as in a typical 1.5-volt C, D, AA, or AAA alkaline battery (see Figure 2-4).



Figure 2-4. *Cross-section view of a typical 1.5-volt alkaline battery.*

A 1.5V battery contains one cell, while a 6V or 9V battery will contain multiple cells connected in series. The total voltage of the battery is the sum of the voltages of its cells.

Electrode Terminology

The electrodes of a cell are often referred to as the *anode* and the *cathode*. These terms are confusing because the electrons enter the anode inside the cell and leave it outside the cell, while electrons enter the cathode from outside the cell and leave it inside the cell. Thus, the anode is an electron emitter if you look at it externally, but the cathode is an electron emitter if you look at it internally.

Conventional current is imagined to flow in the opposite direction to electrons, and therefore, outside the cell, this current flows from the cathode to the anode, and from this perspective, the cathode can be thought of as being “more positive” than the anode. To remember this, think of the letter t in “cathode” as being a + sign, thus: ca+hode. In larger batteries, the cathode is often painted or tagged red, while the anode may be painted or tagged black or blue.

When a reusable battery is recharged, the flow of electrons reverses and the anode and the cathode effectively trade places. Recognizing this, the manufacturers of rechargeable batteries may refer to the more-positive terminal as the anode. This creates additional confusion, exacerbated further still by electronics manufacturers using the term “cathode” to identify the end of a **diode** which must be “more negative”(i.e., at a lower potential) than the opposite end.

To minimize the risk of errors, it is easiest to avoid the terms “anode” and “cathode” when referring to batteries, and speak instead of the negative and positive terminals. This encyclopedia uses the common convention of reserving the term “cathode” to identify the “more negative” end of any type of diode.

Variants

Three types of batteries exist.

1. *Disposable batteries*, properly (but infrequently) referred to as *primary cells*. They are not reliably rechargeable because their chemical reactions are not easily reversible.
2. *Rechargeable batteries*, properly (but infrequently) known as *secondary cells*. They can be recharged by applying a voltage between

the terminals from an external source such as a *battery charger*. The materials used in the battery, and the care with which the battery is maintained, will affect the rate at which chemical degradation of the electrodes gradually occurs as it is recharged repeatedly. Either way, the number of charge/discharge cycles is limited.

3. *Fuel Cells* require an inflow of a reactive gas such as hydrogen to maintain an electrochemical reaction over a long period. They are beyond the scope of this encyclopedia.

A large **capacitor** may be substituted for a battery for some applications, although it has a lower energy density and will be more expensive to manufacture than a battery of equivalent power storage. A capacitor charges and discharges much more rapidly than a battery because no chemical reactions are involved, but a battery sustains its voltage much more successfully during the discharge cycle. See Figure 2-5.



Figure 2-5. *The voltage drop of a discharging capacitor is much steeper initially than that of a battery, making capacitors unsuitable as a battery substitute in many applications. However, the ability of a capacitor to discharge very rapidly at high amperage can sometimes be a significant advantage.*

Capacitors that can store a very large amount of energy are often referred to as *supercapacitors.*

Disposable Batteries

The energy density of any disposable battery is higher than that of any type of rechargeable battery, and it will have a much longer shelf life because it loses its charge more slowly during storage (this is known as the *self-discharge rate*). Disposable batteries may have a useful life of five years or more, making them ideal for applications such as smoke detectors, handheld remotes for consumer electronics, or emergency flashlights.

Disposable batteries are not well suited to delivering high currents through loads below 75Ω. Rechargeable batteries are preferable for higher-current applications. The bar chart in Figure 2-6 shows the rated and actual capabilities of an alkaline battery relative to the three most commonly used rechargeable types, when the battery is connected with a resistance that is low enough to assure complete discharge in 1 hour.

The manufacturer's rating of watt hours per kilo is typically established by testing a battery with a relatively high-resistance load and slow rate of discharge. This rating will not apply in practice if a battery is discharged with a C-rate of 1, meaning complete discharge during 1 hour.

Common types of disposable batteries are *zinc-carbon cells* and *alkaline cells*. In a zinc-carbon cell, the negative electrode is made of zinc while the positive electrode is made of carbon. The limited power capacity of this type of battery has reduced its popularity, but because it is the cheapest to manufacture, it may still be found where a company sells a product with "batteries included." The electrolyte is usually ammonium chloride or zinc chloride. The 9V battery in Figure 2-7 is actually a zinc-carbon battery according to its supplier, while the smaller one beside it is a 12V alkaline battery designed for use in burglar alarms. These examples show that batteries cannot always be identified correctly by a casual assessment of their appearance.



Figure 2-6. *Because of their relatively high internal resistance, alkaline batteries are especially unsuited to high discharge rates, and should be reserved for applications where a small current is required over a long period. (Chart derived from http://batteryuniversity.com.)*



Figure 2-7. *At left, a cheap carbon-zinc battery; at right, a 12V alkaline burglar-alarm battery. See text for additional details.*

In an alkaline cell, the negative electrode is made of zinc powder, the positive electrode is manganese dioxide, and the electrolyte is potassium hydroxide. An alkaline cell may provide between three to five times the power capacity of an equal size of zinc-carbon cell and is less susceptible to voltage drop during the discharge cycle.

Extremely long shelf life is necessary in some military applications. This may be achieved by using a *reserve battery*, in which the internal chemical compounds are separated from each other but can be recombined prior to use.

Rechargeable Batteries

Commonly used types are *lead-acid*, *nickel cadmium* (abbreviated *NiCad* or *NiCd*), *nickel-metal hydride* (abbreviated *NiMH*), *lithium-ion* (abbreviated *Li-ion*), and *lithium-ion polymer*.

Lead-acid batteries have existed for more than a century and are still widely used in vehicles, burglar alarms, emergency lighting, and large power backup systems. The early design was described as *flooded*; it used a solution of sulfuric acid (generically referred to as *battery acid*) as its electrolyte, required the addition of distilled water periodically, and was vented to allow gas to escape. The venting also allowed acid to spill if the battery was tipped over.

The *valve-regulated lead-acid* battery (*VRLA*) has become widely used, requiring no addition of water to the cells. A pressure relief valve is included, but will not leak electrolyte, regardless of the position of the battery. VRLA batteries are preferred for *uninterruptible power supplies* for data-processing equipment, and are found in automobiles and in electric wheelchairs, as their low gas output and security from spillage increases their safety factor.

VRLA batteries can be divided into two types: absorbed glass mat (AGM) and gel batteries. The electrolyte in an AGM is absorbed in a fiber-glass mat separator. In a gel cell, the electrolyte is mixed with silica dust to form an immobilized gel.

The term *deep cycle battery* may be applied to a lead-acid battery and indicates that it should be more tolerant of discharge to a low level—perhaps 20 percent of its full charge (although manufacturers may claim a lower number). The plates in a standard lead-acid battery are composed of a lead *sponge*, which maximizes the surface area available to acid in the battery but can be physically abraded by deep discharge. In a deep cycle battery, the plates are solid. This means they are more robust, but are less able to supply high amperage. If a deep-discharge battery is used to start an internal combustion engine, the battery should be larger than a regular lead-acid battery used for this purpose.

A sealed lead-acid battery intended to power an external light activated by a motion detector is shown in Figure 2-8. This unit weighs several pounds and is trickle-charged during the daytime by a 6″ × 6″ solar panel.


SUNAGO
Sealed Lead-Acid Rechargeable Battery
SB606B 6V,6.0Ah
CAUTION: DO NOT SHORT CIRCUIT

Figure 2-8. *A lead-acid battery from an external light activated by a motion sensor.*

Nickel-cadmium (*NiCad*) batteries can withstand extremely high currents, but have been banned in Europe because of the toxicity of metallic cadmium. They are being replaced in the United States by *nickel-metal hydride* (*NiMH*) types, which are free from the *memory effect* that can prevent a NiCad cell from fully recharging if it has been left for weeks or months in a partially discharged state.

Lithium-ion and lithium-ion polymer batteries have a better energy-to-mass ratio than NiMH batteries, and are widely used with electronic devices such as laptop computers, media players, digital cameras, and cellular phones. Large arrays of lithium batteries have also been used in some electric vehicles.

Various small rechargeable batteries are shown in Figure 2-9. The NiCad pack at top-left was manufactured for a cordless phone and is rapidly becoming obsolete. The 3V lithium battery at top-right was intended for a digital camera. The three batteries in the lower half of the photograph are all rechargeable NiMH substitutes for 9V, AA, and AAA batteries. The NiMH chemistry results in the AA and AAA single-cell batteries being rated for 1.2V rather than 1.5V, but the manufacturer claims they can be substituted for 1.5V alkaline cells because NiMH units sustain their rated voltage more consistently over time. Thus, the output from a fresh NiMH battery may be comparable to that of an alkaline battery that is part-way through its discharge cycle.


LEXEL
Ni-Cd Rechargeable Battery
3.6V 300mAh 2/3AAA
Must be recycled or disposed of properly
MADE IN CHINA
CR-123A 3.0V
Powerizer
NI-MH
Tenergy
NICKEL-METAL HYDRIDE BATTERY RECHARGEABLE
9V
Tenergy
AAA 1.2V
2600mAh RECHARGEABLE
NICKEL-METAL HYDRIDE BATTERY

Figure 2-9. *Top left: NiCad battery pack for a cordless phone. Top right: Lithium battery for a digital camera. The other batteries are rechargeable NiMH substitutes for everyday alkaline cells.*

NiMH battery packs are available to deliver substantial power while being smaller and lighter than lead-acid equivalents. The NiMH package in Figure 2-10 is rated for 10Ah, and consists of ten

D-size NiMH batteries wired in series to deliver 12VDC. This type of battery pack is useful in robotics and other applications where a small motor-driven device must have free mobility.



Figure 2-10. *This NiMH battery pack is rated at 10Ah and delivers 12 volts from ten D-size cells wired in series.*

Values

Amperage

The current delivered by a battery will be largely determined by the resistance of the external load placed between its terminals. However, because ion transfer must occur inside the battery to complete the circuit, the current will also be limited by the *internal resistance* of the battery. This should be thought of as an active part of the circuit.

Since a battery will deliver no current if there is no load, current must be measured while a load is attached, and cannot be measured by a meter alone. The meter will be immediately overloaded, with destructive results, if it is connected directly between the terminals of a battery, or in parallel with the load. Current must always be measured with the meter in series with the load, and the polarity of the meter must correspond with the polarity of the battery. See Figure 2-11.



Figure 2-11. *When measuring current using an ammeter (or a multimeter configured to measure amps), the meter must be placed in series with the battery and a load. To avoid damaging the meter, it must never be applied directly across the terminals of the battery, or in parallel with a load. Be careful to observe the polarity of the meter.*

Capacity

The *electrical capacity* of a battery is measured in *amp-hours*, abbreviated *Ah*, *AH*, or (rarely) *A/H*. Smaller values are measured in *milliamp-hours*, usually abbreviated *mAh*. If I is the current being drawn from a battery (in amps) and T is the time for which the battery can deliver that current (in hours), the amp-hour capacity is given by the formula:

```
Ah = I * T
```

By turning the formula around, if we know the amp-hour rating that a manufacturer has determined for a battery, we can calculate the time in hours for which a battery can deliver a particular current:

```
T = Ah / I
```

Theoretically, Ah is a constant value for any given battery. Thus a battery rated for 4Ah should provide 1 amp for 4 hours, 4 amps for 1 hour, 5 amps for 0.8 hours (48 minutes), and so on.

In reality, this conveniently linear relationship does not exist. It quickly breaks down as the current rises, especially when using lead-acid batteries, which do not perform well when required to deliver high current. Some of the current is lost as heat, and the battery may be electrochemically incapable of keeping up with demand.

The *Peukert number* (named after its German originator in 1897) is a fudge factor to obtain a more realistic value for T at higher currents. If n is the Peukert number for a particular battery, then the previous formula can be modified thus:

$$T = Ah / I^n$$

Manufacturers usually (but not always) supply Peukert's number in their specification for a battery. So, if a battery has been rated at 4Ah, and its Peukert number is 1.2 (which is typical for lead-acid batteries), and I=5 (in other words, we want to know for how long a time, T, the battery can deliver 5 amps):

$$T = 4 / 5^{1.2} = \text{approximately } 4 / 6.9$$

This is about 0.58 hours, or 35 minutes—much less than the 48 minutes that the original formula suggested.

Unfortunately, there is a major problem with this calculation. In Peukert's era, the amp-hour rating for a battery was established by a manufacturer by drawing 1A and measuring the time during which the battery was capable of delivering that current. If it took 4 hours, the battery was rated at 4Ah.

Today, this measurement process is reversed. Instead of specifying the current to be drawn from the battery, a manufacturer specifies the time for which the test will run, then finds the maximum current the battery can deliver for that time. Often, the time period is 20 hours. Therefore, if a battery has a modern 4Ah rating, testing has probably determined that it delivered 0.2A for 20 hours, not 1A for 4 hours, which would have been the case in Peukert's era.

This is a significant distinction, because the same battery that can deliver 0.2A for 20 hours will not be able to satisfy the greater demand of 1A for 4 hours. Therefore the old amp-hour rating and the modern amp-hour rating mean different things and are incompatible. If the modern Ah rating is inserted into the old Peukert formula (as it was above), the answer will be misleadingly optimistic. Unfortunately, this fact is widely disregarded. Peukert's formula is still being used, and the performance of many batteries is being evaluated incorrectly.

The formula has been revised (initially by Chris Gibson of SmartGauge Electronics) to take into account the way in which Ah ratings are established today. Suppose that AhM is the modern rating for the battery's capacity in amp-hours, H is the duration in hours for which the battery was tested when the manufacturer calibrated it, n is Peukert's number (supplied by the manufacturer) as before, and I is the current you hope to draw from the battery. This is the revised formula to determine T:

$$T = H * (AhM / (I * H)^n)$$

How do we know the value for H? Most (not all) manufacturers will supply this number in their battery specification. Alternatively, and confusingly, they may use the term *C-rate*, which can be defined as 1/H. This means you can easily get the value for H if you know the C-rate:

$$H = 1 / C\text{-rate}$$

We can now use the revised formula to rework the original calculation. Going back to the example, if the battery was rated for 4Ah using the modern system, in a discharge test that lasted 20 hours (which is the same as a C-rate of 0.05), and the manufacturer still states that it has a Peukert number of 1.2, and we want to know for how long we can draw 5A from it:

$$T = 20 * (4/(5 * 20)^{1.2}) = \text{approximately } 20 * 0.021$$

This is about 0.42 hours, or 25 minutes—quite different from the 35 minutes obtained with the old version of the formula, which should never be used when calculating the probable discharge time based on a modern Ah rating. These issues may seem arcane, but they are of great importance when assessing the likely performance of battery-powered equipment such as electric vehicles.

Figure 2-12 shows the probable actual performance of batteries with Peukert numbers of 1.1, 1.2, and 1.3. The curves were derived from the revised version of Peukert's formula and show how the number of amp-hours that you can expect diminishes for each battery as the current increases. For example, if a battery that the manufacturer has assigned a Peukert number of 1.2 is rated at 100Ah using the modern 20-hour test, but we draw 30A from it, the battery can actually deliver only 70Ah.



Figure 2-12. *Actual amp-hour performance that should be expected from three batteries of Peukert numbers 1.1, 1.2, and 1.3 when they discharge currents ranging from 5 to 30 amps, assuming that the manufacturer has rated each battery at 100Ah using the modern system, which usually entails a 20-hour test (a C-rate of 0.05).*

One additional factor: For any rechargeable battery, the Peukert number gradually increases with age, as the battery deteriorates chemically.

Voltage

The rated voltage of a fully charged battery is known as the *open circuit voltage* (abbreviated *OCV* or V_{oc}), defined as the potential that exists when no load is imposed between the terminals. Because the internal resistance of a volt meter (or a multimeter, when it is used to measure DC volts) is very high, it can be connected directly between the battery terminals with no other load present, and will show the OCV quite accurately, without risk of damage to the meter. A fully charged 12-volt car battery may have an OCV of about 12.6 volts, while a fresh 9-volt alkaline battery typically has an OCV of about 9.5 volts. Be extremely careful to set a multimeter to measure DC volts before connecting it across the battery. Usually this entails plugging the wire from the red probe into a socket separately reserved for measuring voltage, not amperage.

The voltage delivered by a battery will be pulled down significantly when a load is applied to it, and will decrease further as time passes during a discharge cycle. For these reasons, a **voltage regulator** is required when a battery powers components such as digital integrated circuit chips, which do not tolerate a wide variation in voltage.

To measure voltage while a load is applied to the battery, the meter must be connected in parallel with the load. See Figure 2-13. This type of measurement will give a reasonably accurate reading for the potential applied to the load, so long as the resistance of the load is relatively low compared with the internal resistance of the meter.

Figure 2-14 shows the performance of five commonly used sizes of alkaline batteries. The ratings in this chart were derived for alkaline batteries under favorable conditions, passing a small current through a relatively high-ohm load for long periods (40 to 400 hours, depending on battery type). The test continued until the final voltage for each 1.5V battery was 0.8V, and the final voltage for the 9V battery was a mere 4.8V. These voltages were considered acceptable when the


Meter measuring open circuit voltage
Load
Meter measuring voltage while battery is in use

Figure 2-13. *When using a volt meter (or a multimeter configured to measure voltage), the meter can be applied directly between the battery terminals to determine the open-circuit voltage (OCV), or in parallel with a load to determine the voltage actually supplied during use. A multimeter must be set to measure DC volts before connecting it across a battery. Any other setting may damage the meter.*

Ah ratings for the batteries were calculated by the manufacturer, but in real-world situations, a final voltage of 4.8V from a 9V battery is likely to be unacceptable in many electronics applications.

Battery type	Rating (Ah)	Final voltage	Load (ohms)	Current (mA)
AAA	1.15	0.8	75	20
AA	2.87	0.8	75	20
C	7.8	0.8	39	40
D	17	0.8	39	40
9V	0.57	4.8	620	14

Figure 2-14. *The voltage delivered by a battery may drop to a low level while a manufacturer is establishing an amp-hour rating. Values for current, shown in the chart, were calculated subsequently as estimated averages, and should be considered approximate. (Derived from a chart published by Panasonic.)*

As a general rule of thumb, if an application does not tolerate a significant voltage drop, the manufacturer's amp-hour rating for a small battery may be divided by 2 to obtain a realistic number.

How to Use it

When choosing a battery to power a circuit, considerations will include the intended shelf life, maximum and typical current drain, and battery weight. The amp-hour rating of a battery can be used as a very approximate guide to determine its suitability. For 5V circuits that impose a drain of 100mA or less, it is common to use a 9V battery, or six 1.5V batteries in series, passing current through a **voltage regulator** such as the LM7805. Note that the voltage regulator requires energy to function, and thus it imposes a voltage drop that will be dissipated as heat. The minimum drop will vary depending on the type of regulator used.

Batteries or cells may be used in series or in parallel. In series, the total voltage of the chain of cells is found by summing their individual voltages, while their amp-hour rating remains the same as for a single cell, assuming that all the cells are identical. Wired in parallel, the total voltage of the cells remains the same as for a single cell, while the combined amp-hour value is found by summing their individual amp-hour ratings, assuming that all the batteries are identical. See Figure 2-15.

In addition to their obvious advantage of portability, batteries have an additional advantage of being generally free from power spikes and noise that can cause sensitive components to misbehave. Consequently, the need for smoothing will depend only on possible noise created by other components in the circuit.

Motors or other inductive loads draw an initial surge that can be many times the current that they use after they start running. A battery must be chosen that will tolerate this surge without damage.



Figure 2-15. *Theoretical results of using 1.5V cells in series or in parallel, assuming a 2Ah rating for one cell.*

Because of the risk of fire, United States airline regulations limit the amp-hour capacity of lithium-ion batteries in any electronic device in carry-on or checked passenger baggage. If a device may be carried frequently as passenger baggage (for example, emergency medical equipment), NiMH batteries are preferred.

What Can Go Wrong

Short Circuits: Overheating and Fire

A battery capable of delivering significant current can overheat, catch fire, or even explode if it is short-circuited. Dropping a wrench across the terminals of a car battery will result in a bright flash, a loud noise, and some molten metal. Even a 1.5-volt alkaline AA battery can become too hot to touch if its terminals are shorted together. (Never try this with a rechargeable battery, which has a much lower internal resistance, allowing much higher flow of current.) Lithium-ion batteries are particularly dangerous, and almost always are packaged with a current-limiting component that should not be disabled. A short-circuited lithium battery can explode.

If a battery pack is used as a cheap and simple workbench DC power supply, a **fuse** or circuit breaker should be included. Any device that uses significant battery power should be fused.

Diminished Performance Caused by Improper Recharging

Many types of batteries require a precisely measured charging voltage and a cycle that ends automatically when the battery is fully charged. Failure to observe this protocol can result in chemical damage that may not be reversible. A charger should be used that is specifically intended for the type of battery. A detailed comparison of chargers and batteries is outside the scope of this encyclopedia.

Complete Discharge of Lead-Acid Battery

Complete or near-complete discharge of a lead-acid battery will significantly shorten its life (unless it is specifically designed for deep-cycle use —although even then, more than an 80% discharge is not generally recommended).

Inadequate Current

Chemical reactions inside a battery occur more slowly at low temperatures. Consequently, a cold battery cannot deliver as much current as a warm battery. For this reason, in winter weather, a car battery is less able to deliver high current. At the same time, because engine oil becomes more viscous as the temperature falls, the starter motor will demand more current to turn the engine. This combination of factors explains the tendency of car batteries to fail on cold winter mornings.

Incorrect Polarity

If a battery charger or generator is connected with a battery with incorrect polarity, the battery may experience permanent damage. The **fuse** or *circuit breaker* in a charger may prevent this from occurring and may also prevent damage to the charger, but this cannot be guaranteed.

If two high-capacity batteries are connected with opposite polarity (as may happen when a clumsy attempt is made to start a stalled car with jumper cables), the results may be explosive. Never lean over a car battery when attaching cables to it, and ideally, wear eye protection.

Reverse Charging

Reverse charging can occur when a battery becomes completely discharged while it is wired (correctly) in series with other batteries that are still delivering current. In the upper section of the schematic at Figure 2-16 two healthy 6V batteries, in series, are powering a resistive load. The battery on the left applies a potential of 6 volts to the battery on the right, which adds its own 6 volts to create a full 12 volts across the load. The red and blue lines indicate volt meter leads, and the numbers show the reading that should be observed on the meter.

In the second schematic, the battery on the left has become exhausted and is now a "dead weight" in the circuit, indicated by its gray color. The battery on the right still sustains a 6-volt potential. If the internal resistance of the dead battery is approximately 1 ohm and the resistance of the load is approximately 20 ohms, the potential across the dead battery will be about 0.3 volts, in the opposite direction to its normal charged voltage. Reverse charging will result and can damage the battery. To avoid this problem, a battery pack containing multiple cells should never be fully discharged.

Sulfurization

When a lead-acid battery is partially or completely discharged and is allowed to remain in that state, sulfur tends to build up on its metal plates. The sulfur gradually tends to harden, forming a barrier against the electrochemical reactions that are necessary to recharge the battery. For this reason, lead-acid batteries should not be allowed to sit for long periods in a discharged condition. Anecdotal evidence suggests that even a very small trickle-charging current can prevent sulfurization, which is why some people recommend attaching a small solar panel to a battery that is seldom used—for example, on a sail boat, where the sole function of the battery is to start an auxiliary engine when there is insufficient wind.



Figure 2-16. *When a pair of 6V batteries is placed in series to power a resistive load, if one of the batteries discharges completely, it becomes a load instead of a power source, and will be subjected to reverse charging, which may cause permanent damage.*

High Current Flow Between Parallel Batteries

If two batteries are connected in parallel, with correct polarity, but one of them is fully charged while the other is not, the charged battery will attempt to recharge its neighbor. Because the batteries are wired directly together, the current will be limited only by their internal resistance and the resistance of the cables connecting them. This may lead to overheating and possible damage. The risk becomes more significant when linking batteries that have high Ah ratings. Ideally they should be protected from one another by high-current **fuses.**

jumper

3

A jumper may also be referred to as a *jumper socket* or a *shunt*. A jumper should not be confused with *jumper wires*, which are not considered components for the purposes of this encyclopedia.

OTHER RELATED COMPONENTS

- **switch** (See Chapter 6)

What It Does

A jumper is a low-cost substitute for a **switch,** where a connection has to be made (or unmade) only a few times during the lifetime of a product. Typically it allows a function or feature on a circuit board to be set on a semipermanent basis, often at the time of manufacture. A *DIP switch* performs the same function more conveniently. See "DIP" (page 43).

There is no standardized schematic symbol to represent a jumper.

How It Works

A jumper is a very small rectangular plastic tab containing two (or sometimes more) metal sockets usually spaced either 0.1" or 2mm apart. The sockets are connected electrically inside the tab, so that when they are pushed over two (or more) pins that have been installed on a circuit board for this purpose, the jumper shorts the pins together. The pins are usually 0.025" square and are often part of a *header* that is soldered into the board. In a parts catalogue, jumpers may be found in a section titled "Headers and Wire Housings" or similar.

Three jumpers are shown in Figure 3-1. The blue one contains two sockets spaced 0.1" and is deep enough to enclose the pins completely. The red one contains two sockets spaced 2mm and may allow the tips of the pins to emerge from its opposite end. The black one contains four sockets, each pair spaced 0.1" apart.



Figure 3-1. *Three jumpers containing two sockets spaced 2mm (left), two sockets spaced 0.1" (top right), and four sockets, each pair spaced 0.1" (bottom right).*

The set of pins with which a jumper is used is often referred to as a *header*. Headers are available with pins in single or dual rows. Some headers are designed to be snapped off to provide the desired number of pins. A dual 28-pin header is shown in Figure 3-2 with a black jumper pushed onto a pair of pins near the midpoint.



Figure 3-2. *A jumper pushed onto a pair of pins midway along a dual 28-pin header.*

Variants

A *jumper assembly* may be a kit containing not only the jumper but also the array of pins with which it is intended to be used. Check the manufacturer's datasheet to find out exactly what is included.

The most common types of jumpers have two sockets only, but variants are available with as many as 12 sockets, which may be arranged in one or two rows. *Header sockets* may be used as a substitute for purpose-made jumpers, with the advantage that they are often sold in long strips that can be snapped off to provide as many sockets as needed. However, the pins attached to header sockets must be manually connected by soldering small lengths of wire between them.

In some jumpers, the plastic tab extends upward for about half an inch and functions as a finger grip, making the jumper much easier to hold during insertion and removal. This is a desirable feature if there is room to accommodate it.

The sockets inside a jumper are often made from phosphor-bronze, copper-nickel alloy, tin alloy, or brass alloy. They are usually gold-plated, but in some instances are tin-plated.

Rarely, a jumper may consist of a metal strip with U-shaped connections suitable for being used in conjunction with screw terminals. Two jumpers of this type are shown in Figure 3-3. They should not be confused with high-amperage fuses that look superficially similar.



Figure 3-3. *These jumpers are designed to short together two or three screw terminals.*

Values

The spacing between the sockets in a jumper is referred to as its *pitch*. As previously noted, 0.1″ and 2mm are the most popular values.

A typical maximum rating for a jumper of 0.1″ pitch is 2A or 2.5A at 250V.

How to Use it

A jumper may activate a "set it and forget it" circuit function. An example would be the factory configuration of a product to work with 115VAC or 230VAC power input. End users were expected to set jumpers in some computer equipment sold during the 1980s, but this is no longer the case.

What Can Go Wrong

Jumpers are easily dropped, easily lost, and easily placed incorrectly. When purchasing jumpers, buy extras to compensate for their fragility and the ease of losing them.

Any location where a jumper may be used should be clearly labelled to define the function of each setting.

Cheap, poorly made jumpers may self-destruct from mechanical stresses when removed from their pins. The plastic casing can come away, leaving the sockets clinging naked to the pins protruding from the circuit board. This is another reason why it is a good idea to have a small stock of spare jumpers for emergencies.

Oxidation in jumpers where the contacts are not gold- or silver-plated can create electrical resistance or unreliable connections.

fuse

4

The alternate spelling *fuze* is seldom used.

OTHER RELATED COMPONENTS

- None

What It Does

A fuse protects an electrical circuit or device from excessive current when a metal element inside it melts to create an open circuit. With the exception of *resettable fuses* (discussed separately in "Resettable Fuses" (page 24)), a fuse must be discarded and replaced after it has fulfilled its function.

When high current melts a fuse, it is said to *blow* or *trip* the fuse. (In the case of a resettable fuse, only the word *trip* is used.)

A fuse can work with either AC or DC voltage, and can be designed for almost any current. In residential and commercial buildings, *circuit breakers* have become common, but a large cartridge fuse may still be used to protect the whole system from short-circuits or from overcurrent caused by lightning strikes on exposed power lines.

In electronic devices, the **power supply** is almost always fused.

Schematic symbols for a fuse are shown in Figure 4-1. Those at the right and second from right are most frequently used. The one in the center is approved by ANSI, IEC, and IEEE but is seldom seen. To the left of that is the fuse symbol understood by electrical contractors in architectural plans. The symbol at far left used to be common but has fallen into disuse.



Figure 4-1. *Alternate schematic symbols for a fuse. See text for explanation.*

How It Works

The *element* in a fuse is usually a wire or thin metal strip mounted between two terminals. In a cartridge fuse, it is enclosed in a glass or ceramic cylinder with a contact at each end, or in a small metallic can. (Old-style, large, high-amperage fuses may be packaged in a paper or cardboard tube.) The traditional glass cartridge allows visual inspection to confirm that the fuse has blown.

A fuse responds only to current, not to voltage. When choosing a fuse that will be reliable in conditions of steady current consumption, a safe rule is to figure the maximum amperage when all components are functioning and add 50%. However, if current surges or spikes are likely, their duration will be relevant. If I is the current surge in amps and t is its duration in seconds, the surge sensitivity of a fuse—which is often referred to verbally or in printed format as I2t—is given by the formula:

```
I2t = I² * t
```

Some semiconductors also have an I2t rating, and should be protected with a similarly rated fuse.

Any fuse will present some resistance to the current flowing through it. Otherwise, the current would not generate the heat that blows the fuse. Manufacturer datasheets list the voltage drop that the internal resistance of a fuse is likely to introduce into a circuit.

Values

The *current rating* or *rated current* of a fuse is usually printed or stamped on its casing, and is the maximum flow that it should withstand on a continuous basis, at the ambient temperature specified by the manufacturer (usually 25 degrees Centigrade). The ambient temperature refers to the immediate environment of the fuse, not the larger area in which it may be located. Note that in an enclosure containing other components, the temperature is usually significantly higher than outside the enclosure.

Ideally a fuse should function reliably and indefinitely at its rated maximum amperage, but should blow just as reliably if the current rises by approximately 20% beyond the maximum. In reality, manufacturers recommend that continuous loading of a fuse should not exceed 75% of its rating at 25 degrees Centigrade.

The *voltage rating* or *rated voltage* of a fuse is the maximum voltage at which its element can be counted on to melt in a safe and predictable manner when it is overloaded by excess current. This is sometimes known as the *breaking capacity*. Above that rating, the remaining pieces of the fuse element may form an arc that sustains some electrical conduction.

A fuse can always be used at a lower voltage than its rating. If it has a breaking capacity of 250V, it will still provide the same protection if it is used at 5V.

Four differently rated glass cartridge fuses are shown in Figure 4-2. The one at the top is a slow-blowing type, rated at 15A. Its element is designed to absorb heat before melting. Below it is a 0.5A fuse with a correspondingly thinner element. The two smaller fuses are rated at 5A each. The center two fuses have a maximum voltage rating of 250V, while the one at the top is rated at 32V and the one at the bottom is rated at 350V. Clearly, the size of a fuse should never be used as a guide to its ratings.



Figure 4-2. *Four glass cartridge fuses. See text for details.*

Variants

Early power fuses in residential buildings consisted of bare nichrome wire wrapped around a porcelain holder. In the 1890s, Edison developed *plug fuses* in which the fuse was contained in a porcelain module with a screw thread, compatible with the base of an incandescent bulb. This design persisted in some U.S. urban areas for more than 70 years, is still found in old buildings, and is still being manufactured.

Small Cartridge Fuses

Small cartridge fuses for appliances and electronics equipment—such as those shown in Figure 4-2--are available in sizes tabulated in Figure 4-3. With the exception of the 4.5mm diameter fuse (a European addition), these sizes were originally measured in inches; today, they are often described only with the equivalent metric measurement. Any cartridge fuse is usually available with the option of a lead attached to it at each end, so that it can be used as a through-hole component.

Fuse type	Diameter (inches)	Diameter (metric)	Length (inches)	Length (metric)
1AG	1/4"	6mm	5/8"	16mm
2AG	0.177"	4.5mm	0.588"	15mm
3AG	1/4"	6mm	1-1/4"	32mm
4AG	9/32"	7mm	1-1/4"	32mm
5AG	13/32"	10mm	1-1/2"	38mm
7AG	1/4"	6mm	7/8"	22mm
8AG	1/4"	6mm	1"	25mm

Figure 4-3. *The approximate physical sizes of commonly used small glass or ceramic cartridge fuses are shown here with the codes that are often used to identify them.*

Fuses may be fast acting, medium acting, or slow-blowing, the last of which may alternatively be referred to as *delay fuses*. Extra-fast–acting fuses are available from some manufacturers. The term *Slo-Blo* is often used but is actually a trademark of Littelfuse. None of the terms describing the speed of action of a fuse has been standardized with a specific time or time range.

Some cartridge fuses are available in a ceramic format as an alternative to the more common glass cylinder. If accidental application of extremely high current is possible (for example, in a multimeter that can be set to measure amps, and may be accidentally connected across a powerful battery), a ceramic cartridge is preferable because it contains a filler that will help to stop an arc from forming. Also, if a fuse is physically destroyed by application of very high current, ceramic fragments may be preferable to glass fragments.

Automotive Fuses

Automotive fuses are identifiable by their use of blades designed for insertion in flat sockets where the fuse is unlikely to loosen as a result of vibration or temperature changes. The fuses come in various sizes, and are uniformly color-coded for easy identification.

A selection of automotive fuses is shown in Figure 4-4. The type at the top is typically described as a “maxi-fuse” while the type at bottom-left is a “mini-fuse.” Here again, size is irrelevant to function, as all three of those pictured are rated 30A at 32V.



Figure 4-4. *Three automotive fuses. All have the same rating: 30A at 32V.*

In Figure 4-5, the largest of the fuses from Figure 4-4 has been cut open to reveal its element.



Figure 4-5. *The largest fuse from the previous figure, cut open to reveal its element.*

Usually automotive fuses are mounted together in a block, but if aftermarket accessory equipment is added, it may be protected by an inline fuse in a holder that terminates in two wires. This is shown with two sample fuses in Figure 4-6. Similar inline fuse holders are manufactured for other types of fuses.

Strip Fuses

High-amperage fuses for vehicles may be sold in "strip fuse" format, also known as a *fusible link*, designed to be clamped between two screw-down terminals. Since some **jumpers** may look very similar, it is important to keep them separate. A strip fuse is shown in Figure 4-7.

Through-Hole Fuses

Small fuses with radial leads, which seem appropriate for through-hole insertion in printed circuit boards, are actually often used in conjunction with appropriate sockets, so that they can be easily replaced. They are described in catalogues as "subminiature fuses" and are typically found in laptop computers and their power supplies, also televisions, battery chargers, and air conditioners. Three examples are shown in Figure 4-8. All have slow-blowing characteristics.



Figure 4-6. *Two blade-type fuses, commonly used for automotive applications, shown with an inline fuse holder. The plastic cap, at right, is closed over the holder when a fuse has been installed.*



Figure 4-7. *This strip fuse is intended for use in diesel vehicles. The example shown is rated 100A at 36V.*

Resettable Fuses

Properly known as a *polymeric positive temperature coefficient* fuse (often abbreviated *PTC* or *PPTC*), a *resettable fuse* is a solid-state, encapsulated component that greatly increases its resistance in response to a current overload, but gradually returns to its original condition when the flow of current is discontinued. It can be thought



Figure 4-8. *Three subminiature fuses terminating in wire leads. From left to right: 10A at 250V, 2.5A at 250V, and 5A at 250V.*

of as a **thermistor** that has a nonlinear response. Three through-hole examples are shown in Figure 4-9. While different sizes of cartridge fuse may share the same ratings, differently rated resettable fuses may be identical in size. The one on the left is rated 40A at 30V, while the one on the right is rated 2.5A at 30V. (Note that the codes printed on the fuses are not the same as their manufacturer part numbers.) The fuse at the top is rated 1A at 135V.

When more than the maximum current passes through the fuse, its internal resistance increases suddenly from a few ohms to hundreds of thousands of ohms. This is known as *tripping* the fuse. This inevitably entails a small delay, but is comparable to the time taken for a slow-blowing fuse to respond.

A resettable fuse contains a polymer whose crystalline structure is loaded with graphite particles that conduct electricity. As current flowing through the fuse induces heat, the polymer transitions to an amorphous state, separating the graphite particles and interrupting the conductive pathways. A small current still passes through the component, sufficient to maintain its amorphous state until power is disconnected.



Figure 4-9. *Some through-hole resettable fuses. See text for details.*

After the resettable fuse cools, it gradually recrystallizes, although its resistance does not fall back completely to its original value for more than an hour.

The maximum safe level of current for a resettable fuse is known as the *hold current*, while the current that triggers its response is termed the *trip current*. Resettable fuses are available with trip-current ratings from 20mA to 100A. While conventional appliance and electronics fuses may be rated as high as 600V, resettable fuses are seldom rated above 100V.

Typical cartridge fuses are affected only to a minor extent by temperature, but the current rating of a resettable fuse may diminish to 75% of its normal value at 50 degrees Centigrade and may drop to 50% of its normal value at 80 degrees Centigrade. In other words, a fuse that is rated for 4A at 25 degrees may tolerate a maximum of only 3A when it operates at twice that temperature. See Figure 4-10.



Figure 4-10. *The three curves give a very approximate idea of the temperature sensitivity of three types of fuses commonly used to protect electronic equipment. The left-hand scale provides an approximate value for the amperage which will trip the fuse.*

Conventional slow-blowing fuses are temperature-sensitive, but to a lesser degree than resettable fuses.

Resettable fuses are used in computer power supplies, USB power sources, and loudspeaker enclosures, where they protect the speaker coils from being overdriven. They are appropriate in situations where a fuse may be tripped relatively often, or where technically unsophisticated users may feel unable to replace a fuse or reset a circuit breaker.

Brand names for resettable fuses include PolySwitch, OptiReset, Everfuse, Polyfuse, and Multifuse. They are available in *surface-mount* (SMT) packages or as *through-hole* components, but not in cartridge format.

Surface Mount Fuses

Because surface-mount fuses are difficult or impossible to replace after they have been soldered onto the board, they are often resettable.

A surface-mount resettable fuse approximately 0.3″ square is shown in Figure 4-11. It is rated for 230V and has an internal resistance of 50 ohms. Its hold current is 0.09A and its trip current is 0.19A.



Figure 4-11. *A surface-mount resettable fuse. See text for details.*

How to Use it

Any equipment that may be plugged into a wall outlet should be fused, not only to protect its components but also to protect users who may open the box and start investigating with a screwdriver.

Equipment that contains powerful motors, pumps, or other inductive loads should be protected with slow-blowing fuses, as the initial surge of current when the equipment is switched on is likely to rise well above the rating of the fuse. A slow-blowing fuse will tolerate a surge for a couple of seconds. Other fuses will not.

Conversely, fast-acting fuses should be used with electronic equipment, especially integrated circuits that are quickly and easily damaged.

Any device using substantial **battery** power should be fused because of the unpredictable and generally bad behavior of batteries when they are short-circuited. Parallel connections between multiple large batteries should be fused to avoid the possibility that a highly charged battery may attempt to recharge its neighbor(s). Large "J size" fuses rated from 125A to 450A have become common in the solar power community, where banks of lead-acid batteries are often used. These fuses have a thick brass tab at each end, drilled so that they can be bolted into place. Alternatively, they will push-fit into an appropriate *fuseholder*.

For cartridge fuses up to 1/4" in diameter that don't have leads attached, appropriately sized fuseholders are available in several formats:

Panel mounted fuse enclosure is probably the most common, consisting of a plastic tube with a spring-contact at the bottom, and a plastic cap with a second contact inside. The cap either screws onto the tube of the fuse, or is pushed down and turned to hold it in place. A nut is provided to secure the fuseholder after it has been inserted into a hole drilled in the panel. The fuse is dropped into the tube, and the cap is applied. This type of holder is available in full-length or shorter, "low profile" formats. A low-profile holder is shown in Figure 4-12. It is shown assembled at right, with its component parts disassembled alongside.



Figure 4-12. *A low-profile panel-mounted fuse holder shown disassembled (left) and assembled (right).*

Circuit board mounted fuse enclosure is basically the same as the panel-mounted version, but with through-hole solder pins attached.

Fuse block is a small plastic block with two clips on its upper surface for insertion of a cartridge fuse.

Fuse clips can be bought individually, with solder pins for through-hole mounting.

Inline fuse holder is designed to be inserted in a length of wire. Usually made of plastic, it will either terminate it, wires or will have metal contacts to crimp or solder at each end. See Figure 4-6.

Through-hole fuse holders are available for subminiature fuses.

What Can Go Wrong

Repeated Failure

When a fuse in a circuit blows frequently, this is known as *nuisance opening*. Often it can result from failure to take into account all the aspects of the circuit, such as a large filtering capacitor in a power supply that draws a major surge of current when the power supply is switched on. The formally correct procedure to address this problem is to measure the power surge, properly known as *peak inrush current*, with an oscilloscope, calculate the $I^2 * t$ of the wave form, and select a fuse with a rating at least 5 times that value.

A fuse should never be replaced with an equivalent length of wire or any other conductor.

Soldering Damage

When a through-hole or surface-mount fuse is soldered into place, heat from the soldering process can cause the soft metal element inside the fuse to melt partially and reflow. This is likely to change the rating of the fuse. Generally, fuses should be treated with the same caution as semiconductors when they are fixed in place with solder.

Placement

A fuse should be placed close to the power source or power input point in a circuit, so that it protects as much of the circuit as possible.

pushbutton

5

Often referred to as a *pushbutton switch* and sometimes as a *momentary switch*. In this encyclopedia, a pushbutton is considered separately from a **switch**, which generally uses a lever-shaped actuator rather than a button, and has at least one *pole* contact where a pushbutton generally has contacts that are not distinguishable from each other.

OTHER RELATED COMPONENTS

- **switch** (See Chapter 6)
- **rotary switch** (See Chapter 7)

What It Does

A pushbutton contains at least two contacts, which close or open when the button is pressed. Usually a spring restores the button to its original position when external pressure is released. Figure 5-1 shows schematic symbols for pushbuttons. The symbols that share each blue rectangle are functionally identical. At top is a normally-open single-throw pushbutton. At center is a normally-closed single-throw pushbutton. At bottom is a double-throw pushbutton.

Unlike a **switch**, a basic pushbutton does not have a primary contact that can be identified as the *pole*. However, a single pushbutton may close or open two separate pairs of contacts, in which case it can be referred to, a little misleadingly, as a double-pole pushbutton. See Figure 5-2. Different symbols are used for slider pushbuttons with multiple contact pairs; see "Slider" (page 31).

A generic full-size, two-contact pushbutton is shown in Figure 5-3.



Figure 5-1. *Commonly used schematic symbols to represent a simple pushbutton. See text for details.*

How It Works

Figure 5-4 shows a cross-section of a pushbutton that has a single steel return spring, to create resistance to downward force on the button, and a pair of springs above a pair of contacts, to hold each contact in place and make a firm connection when the button is pressed. The two upper contacts are electrically linked, although this feature is not shown.



Figure 5-2. *Commonly used schematic symbols to represent a double-pole pushbutton.*



Figure 5-4. *Cross-section of a pushbutton showing two spring-loaded contacts and a single return spring.*

Variants

Poles and Throws

Abbreviations that identify the number of poles and contacts inside a pushbutton are the same as the abbreviations that identify those attributes in a **switch**. A few examples will make this clear:

SPST, also known as 1P1T
: Single pole, single throw

DPST also known as 2P1T
: Double pole, single throw



Figure 5-3. *The simplest, traditional form of pushbutton, in which pressing the button creates a connection between two contacts.*

SPDT also known as 1P2T
: Single pole, double throw

3PST also known as 3P1T
: Three pole, single throw

While a switch may have an additional center position, pushbuttons generally do not.

On-Off Behavior

Parentheses are used to indicate the momentary state of the pushbutton while it is pressed. It will return to the other state by default.

OFF-(ON) or (ON)-OFF
: Contacts are normally open by default, and are closed only while the button is pressed. This is sometimes described as a *make-to-make* connection, or as a *Form A* pushbutton.

ON-(OFF) or (OFF)-ON
: Contacts are normally closed by default, and are open only while the button is pressed. This is sometimes described as a *make-to-break* connection, or as a *Form B* pushbutton.

ON-(ON) or (ON)-ON
: This is a double-throw pushbutton in which one set of contacts is normally closed. When the button is pressed, the first set of contacts

is opened and the other set of contacts is closed, until the button is released. This is sometimes described as a *Form C* pushbutton.

For a single-throw pushbutton, the terms NC or NO may be used to describe it as *normally closed* or *normally open*.

Slider

This type, also known as a *slide* pushbutton, contains a thin bar or rod that slides in and out of a long, narrow enclosure. Contacts on the rod rub across secondary contacts inside the enclosure. Closely resembling a slider switch, it is cheap, compact, and well adapted for multiple connections (up to 8 separate poles in some models). However, it can only tolerate low currents, has limited durability, and is vulnerable to contamination.

A four-pole, double-throw pushbutton is shown in Figure 5-5. A variety of plastic caps can be obtained to press-fit onto the end of the white nylon actuator.



Figure 5-5. *A 4PDT slider pushbutton, shown without the cap that can be snapped onto the end of the actuator.*

Figure 5-6 shows schematic symbols for two possible slide pushbuttons, with a black rectangle indicating each sliding contact. The lead that functions as a pole is marked with a P in each case. Standardization for slide pushbutton schematic symbols does not really exist, but these examples are fairly typical. An insulating section that connects the sliding contacts internally is shown here as a gray rectangle, but in some datasheets may appear as a line or an open rectangle.

Since the symbols for a slide pushbutton may be identical to the symbols for a slide switch, care must be taken when examining a schematic, to determine which type of component is intended.



Figure 5-6. *Left: schematic symbol for a simple SPDT slide pushbutton, where a movable contact shorts together either the left pair or right pair of fixed contacts. Right: A 4PDT pushbutton in which the same principle has been extended. The movable contacts are attached to each other mechanically by an insulator. Each pole terminal is marked with a P.*

Styles

Many pushbutton switches are sold without caps attached. This allows the user to choose from a selection of styles and colors. Typically the cap is a push-fit onto the end of the rod or bar that activates the internal contacts. Some sample caps are shown in Figure 5-7, alongside a DPDT pushbutton. Any of the caps will snap-fit onto its actuator.

An *illuminated* pushbutton contains a small *incandescent bulb*, *neon bulb*, or **LED** (*light-emitting diode*). The light source almost always has its own two terminals, which are isolated from the other terminals on the button housing and can be wired to activate the light when the button is pressed, when it is released, or on some other basis. Pushbuttons containing LEDs usually



Figure 5-7. *Caps (buttons or knobs) that may be sold as separate accessories for some pushbuttons, shown here alongside a compatible pushbutton switch.*

require external series resistors, which should be chosen according to the voltage that will be used. See the **LED** entry in Volume 2 for additional commentary on appropriate series resistors. An example of an illuminated pushbutton is shown in Figure 5-8. This is a DPDT component, designed to be mounted on a printed circuit board, with an additional lead at each end connecting with an internal LED underneath the translucent white button.

Termination and Contact Plating

These options are the same as for a **switch** and are described in that entry.

Mounting Style

The traditional panel-mounted button is usually secured through a hole in the panel by tightening a nut that engages with a thread on the bushing of the pushbutton. Alternatively, a pushbutton housing can have flexible plastic protrusions on either side, allowing it to be snapped into place in an appropriate-sized panel cutout. This style is shown in Figure 5-4.



Figure 5-8. *This pushbutton contains an LED underneath the white translucent button.*

PC pushbuttons (pushbuttons mounted in a printed circuit board, or PCB) are a common variant. After the component has been installed in the circuit board, either the button must align with a cutout in the front panel and poke through it when the device is assembled, or an external (non-electrical) button that is part of the product enclosure must press on the actuator of the pushbutton after assembly.

Surface-mount pushbuttons that allow direct fingertip access are uncommon. However, about one-quarter of tactile switches are designed for surface mount at the time of writing. They are typically found beneath membranes that the user presses to activate the switch beneath—for example, in remotes that are used to operate electronic devices.

Sealed or Unsealed

A sealed pushbutton will include protection against water, dust, dirt, and other environmental hazards, at some additional cost.

Latching

This variant, also known as a *press-twice* pushbutton, contains a mechanical ratchet, which is rotated each time the button is pressed. The first press causes contacts to latch in the closed state. The second press returns the contacts to the open state, after which, the process repeats. This press-twice design is typically found on flashlights, audio equipment, and in automotive applications. While *latching* is the most commonly used term, it is also known as *push-push*, *locking*, *push-lock push-release*, *push-on push-off*, and *alternate*.

In a latching pushbutton with *lockdown*, the button is visibly lower in the latched state than in the unlatched state. However, buttons that behave this way are not always identified as doing so on their datasheets.

A six-pole double-throw pushbutton that latches and then unlatches each time it is pressed is shown in Figure 5-9.



Figure 5-9. *This 6PDT pushbutton latches and then unlatches, each time it is pressed.*

Two more variants are shown in Figure 5-10. On the right is a simple DPDT latching pushbutton with lockdown. On the left is a latching pushbutton that cycles through four states, beginning with one "off" state, the remaining three connecting a different pair of its wires in turn.

A simple OFF-(ON) button may appear to have a latching output if it sends a pulse to a **microcontroller** in which software inside the microcontroller toggles an output between two states. The microcontroller can step through an unlimited number of options in response to each button press. Examples are found on cellular phones or portable media players.



Figure 5-10. *At right, a simple DPDT latching pushbutton with lockdown. At left, this pushbutton cycles through four states, one of them an "off" state, the others connecting a different pair of its wires in turn.*

A mechanically latching pushbutton has a higher failure rate than a simple OFF-(ON) button, as a result of its internal mechanism, but has the advantage of requiring no additional microcontroller to create its output. Microcontrollers are discussed in Volume 2.

Foot Pedal

Foot pedal pushbuttons generally require more actuation force than those intended for manual use. They are ruggedly built and are commonly found in vacuum cleaners, audio-transcription foot pedals, and "stomp boxes" used by musicians.

Keypad

A keypad is a rectangular array of usually 12 or 16 OFF-(ON) buttons. Their contacts are accessed via a *header* suitable for connection with a ribbon cable or insertion into a printed circuit board. In some keypads, each button connects with a separate contact in the header, while all the buttons share a common ground. More often, the buttons are *matrix encoded*, meaning that each of them bridges a unique pair of conductors in a matrix. A 16-button matrix is shown in Figure 5-11. This configuration is suitable for polling by a **microcontroller**, which can be programmed to send an output pulse to each of the four horizontal wires in turn. During each pulse, it checks the remaining four vertical wires in sequence, to determine which one, if any, is carrying a signal. Pullup or pulldown resistors should be added to the input wires to prevent the inputs of the microcontroller from behaving unpredictably when no signal is present. The external appearance of two keypads is shown in Figure 5-12.



Figure 5-11. *Buttons in a numeric keypad are usually wired as a matrix, where each button makes a connection between a unique pair of wires. This system is suitable for being polled by a microcontroller.*

Tactile Switch

Despite being called a switch, this is a miniature pushbutton, less than 0.4" square, designed for insertion in a printed-circuit board or in a solderless breadboard. It is almost always a SPST device but may have four pins, one pair connected to each contact. Tactile switches may be PC-mounted behind membrane pads. An example is shown in Figure 5-13.



Figure 5-12. *The keypad on the left is matrix-encoded, and is polled via seven through-hole pins that protrude behind it. The keypad on the right assigns each button to a separate contact in its header. See the text for details about matrix encoding.*



Figure 5-13. *A typical tactile switch.*

Membrane Pad

Typically found on devices such as microwave ovens where contacts must be sealed against particles and liquids. Finger pressure on a membrane pad closes hidden or internal pushbuttons. They are usually custom-designed for specific product applications and are not generally available as generic off-the-shelf components. Some surplus pads may be found for sale on auction websites.

Radio Buttons

The term *radio buttons* is sometimes used to identify a set of pushbuttons that are mechanically interlinked so that only one of them can make an electrical connection at a time. If one button is pressed, it latches. If a second button is pressed, it latches while unlatching the first button. The buttons can be pressed in any sequence. This system is useful for applications such as component selection in a stereo system, where only one input can be permitted at a time. However, its use is becoming less common.

Snap-Action Switches

A snap-action switch (described in detail in the **switch** section of this encyclopedia) can be fitted with a pushbutton, as shown in Figure 5-14. This provides a pleasingly precise action, high reliability, and capability of switching currents of around 5A. However, snap-action switches are almost always single-pole devices.



Figure 5-14. *A pushbutton mounted on top of a SPDT snap-action switch.*

Emergency Switch

An emergency switch is a normally-closed device, usually consisting of a large pushbutton that clicks firmly into its "off" position when pressed, and does not spring back. A flange around the button allows it to be grasped and pulled outward to restore it to its "on" position.

Values

Pushbutton current ratings range from a few mA to 20A or more. Many pushbuttons have their current ratings printed on them but some do not. Current ratings are usually specified for a particular voltage, and may differ for AC versus DC.

How to Use it

Issues such as appearance, tactile feel, physical size, and ease of product assembly tend to dictate the choice of a pushbutton, after the fundamental requirements of voltage, current, and durability have been satisfied. Like any electromechanical component, a pushbutton is vulnerable to dirt and moisture. The ways in which a device may be used or abused should be taken into account when deciding whether the extra expense of a sealed component is justified.

When a pushbutton controls a device that has a high inductive load, a *snubber* can be added to minimize arcing. See "Arcing" (page 47) in the **switch** entry of this encyclopedia, for additional information.

What Can Go Wrong

No Button

When ordering a pushbutton switch, read datasheets carefully to determine whether a cap is included. Caps are often sold separately and may not be interchangeable between switches from different manufacturers.

Mounting Problems

In a panel-mount pushbutton that is secured by turning a nut, the nut may loosen with use, allowing the component to fall inside its enclosure when the button is pressed. Conversely, overtightening the nut may strip the threads on the pushbutton bushing, especially in cheaper components where the threads are molded into plastic. Consider applying a drop of Loc-Tite or similar adhesive before completely tightening the nut. Nut sizes vary widely, and finding a replacement may be time-consuming.

LED Issues

When using a pushbutton containing an LED, be careful to distinguish the LED power terminals from the switched terminals. The manufacturer's datasheet should clarify this distinction, but the polarity of the LED terminals may not be clearly indicated. If a diode-testing meter function is unavailable, a sample of the switch should be tested with a source of 3 to 5VDC and a 2K series resistor. Briefly touching the power to the LED terminals, through the resistor, should cause the LED to flash dimly if the polarity is correct, but should not be sufficient to burn out the LED if the polarity is incorrect.

Other Problems

Problems such as arcing, overload, short circuits, wrong terminal type, and contact bounce are generally the same as those associated with a **switch**, and are summarized in that entry in this encyclopedia.

switch

The term **switch** refers here to a physically operated mechanical switch, controlled by flipping a lever or sliding a knob. Although there is some overlap of function, **rotary switches** and **pushbuttons** have their own separate entries. Solid-state switching components are described in entries for **bipolar transistor**, **unijunction transistor**, and **field-effect transistor**. Integrated-circuit switching devices will be found in Volume 2. *Coaxial switches* are used for high-frequency signals, and are not included in this encyclopedia. *Multidirectional switches* differentiate up, down, left, right, diagonal, rotational, and other finger inputs, and are not included in this encyclopedia.

OTHER RELATED COMPONENTS

- **pushbutton** (See Chapter 5)
- **rotary switch** (See Chapter 7)

What It Does

A switch contains at least two contacts, which close or open when an external lever or knob is flipped or moved. Schematic symbols for the most basic type of on-off switch are shown in Figure 6-1.



Figure 6-1. *The two most common schematic symbols for a SPST switch, also known as an on-off switch. The symbols are functionally identical.*

The most fundamental type of switch is a *knife switch*, illustrated in Figure 6-2. Although it was common in the earliest days of electrical discovery, today it is restricted to educational purposes in schools, and (in a more robust format) to AC electrical supply panels, where the large contact area makes it appropriate for conducting high amperages, and it can be used for “hot switching” a substantial load.

How It Works

The *pole* of a switch is generally connected with a movable contact that makes or breaks a connection with a secondary contact. If there is only one pole, this is a *single-pole* switch. If there is an additional pole, electrically isolated from the first, with its own contact or set of contacts, this is a *two-pole* switch, also known as a *double-pole* switch. Switches with more than 4 poles are uncommon.

If there is only one secondary contact per pole, this is a *single-throw* or *ST* switch, which may also be described as an *on-off* or *off-on* switch. If there is an additional secondary contact per pole, and the pole of the switch connects with the second contact while disconnecting from the first, this is a *double-throw* or *DT* switch, also known as a *two-way* switch.



Figure 6-2. *A DPST knife switch intended for the educational environment.*

A double-throw switch may have an additional center position. This position may have no connection (it is an "off" position) or in some cases it connects with a third contact.

Where a switch is spring-loaded to return to one of its positions when manual pressure is released, it functions like a **pushbutton** even though its physical appearance may be indistinguishable from a switch.

Variants

Float switch, *mercury switch*, *reed switch*, *pressure switch*, and *Hall-effect switch* are considered as sensing devices, and will be found in Volume 3.

Terminology

Many different types of switches contain parts that serve the same common functions. The *actuator* is the lever, knob, or toggle that the user turns or pushes. A *bushing* surrounds the actuator on a toggle-type switch. The *common contact* inside a switch is connected with the *pole* of the switch. Usually a *movable contact* is attached to it internally, to touch the secondary contact, also known as a *stationary contact* when the movable contact is flipped to and fro.

Poles and Throws

Abbreviations identify the number of poles and contacts inside a switch. A few examples will make this clear:

SPST also known as 1P1T
Single pole, single throw

DPST also known as 2P1T
Double pole, single throw

SPDT also known as 1P2T
Single pole, double throw

3PST also known as 3P1T
Three pole, single throw

Other combinations are possible.

In Figure 6-3, schematic symbols are shown for double-throw switches with 1, 2, and 3 poles. The dashed lines indicate a mechanical connection, so that all sections of the switch move together when the switch is turned. No electrical connection exists between the poles.



Figure 6-3. *Schematic symbols to represent three types of double-throw switch. Top left: Single-pole. Bottom left: Double-pole. Right: Triple-pole, more commonly known as 3-pole.*

On-Off Behavior

The words ON and OFF are used to indicate the possible states of a switch. The additional word NONE is used by some manufacturers to indicate that a switch does not have a center position. Some manufacturers don't bother with the word NONE, assuming that if the word is omitted, a center position does not exist.

ON-OFF or ON-NONE-OFF

A basic on-off SPST switch with no center position.

ON-ON or ON-NONE-ON

A basic SPDT switch with no center position.

ON-OFF-ON

A double-throw switch with center-off position (no connection when the switch is centered).

ON-ON-ON

A triple-throw switch where the center position connects with its own set of terminals.

Parentheses are used in descriptions of spring-loaded switches to indicate a momentary state that lasts only as long as pressure is applied to the actuator.

(ON)-OFF or OFF-(ON)

A spring-loaded switch that is normally off and returns to that position when pressure is released. Also known as *NO* (normally open), and sometimes described as *FORM A*. Its performance is similar to that of a pushbutton and is sometimes described as a *make-to-make* connection.

ON-(OFF) or (OFF)-ON

A spring-loaded switch that is normally on and returns to that position when pressure is released. This is sometimes described as a *make-to-break* connection. Also known as *NC* (normally closed), and sometimes described as *FORM B*.

(ON)-OFF-(ON)

A spring-loaded double-throw switch with a no-connection center position to which it returns when pressure on its actuator is released.

Other combinations of these terms are possible.

Most double-throw switches break the connection with one contact (or set of contacts) before making the connection with the second contact (or set of contacts). This is known as a *break before make* switch. Much less common is a *make before break* switch, also known as a *shorting switch*, which establishes the second connection a moment before the first connection is broken. Use of a shorting switch may cause unforeseen consequences in electronic components attached to it, as both sides of the switch will be briefly connected when the switch is turned.

Snap-Action

Also known as a *limit switch* and sometimes as a *microswitch* or *basic switch*. This utilitarian design is often intended to be triggered mechanically rather than with finger pressure, for example in 3D printers. It is generally cheap but reliable.

Two snap-action switches are shown in Figure 6-4. A sectional view of a snap-action ON-(ON) limit switch is shown in Figure 6-5. The pole contacts are mounted on a flexible strip which can move up and down in the center of the switch. The strip has a cutout which allows an inverted U-shaped spring to flip to and fro. It keeps the contacts pressed together in either of the switch states.



Figure 6-4. *Two SPDT snap-action switches, also known as limit switches. The one on the right is full-size. The one on the left is miniature, with an actuator arm to provide additional leverage. The arm may be trimmed to the required length.*



Figure 6-5. *Top: Two contacts inside this limit switch are touching by default. Bottom: When the external button is pressed, it pushes a flexible metal strip downward until it connects with the lower contact. The inverted-U–shaped component is a spring that rests inside a cutout in the flexible strip and resists motion through the central part of its travel.*

The term *snap action* refers to a spring-loaded internal mechanism which snaps to and fro between its two positions. This type of switch is usually SPDT and has a momentary action; in other words, it functions in ON-(ON) mode, although OFF-(ON) and (less often) ON-(OFF) versions are available. The body of the switch is sealed, with a small button protruding through a hole. A thin metal arm may provide additional leverage to press the button. A roller may be mounted at the end of the arm so that the switch can be activated as it slides against a moving mechanical component such as a cam or a wheel. The switch is commonly used to limit the travel or rotation of such a component. Literally thousands of variants are available, in different sizes, requiring different amounts of force for activation. Subminiature snap-action switches can often be actuated by a pressure of only a few grams.

Rocker

Three rocker switches are shown in Figure 6-6. A sectional view of a rocker switch is shown in Figure 6-7. In this design, a spring-loaded ball bearing rolls to either end of a central rocker arm when the switch is turned. Rocker switches are often used as power on-off switches.

Slider

Many types of slider switch (also known as *slide switch*) are widely used as a low-cost but versatile way to control small electronic devices, from clock-radios to stereos. The switch is usually mounted on a circuit board, and its knob or cap protrudes through a slot in the panel. This design is more vulnerable to dirt and moisture than other types of switch. It is usually cheaper than a toggle switch but is seldom designed for use with a high current.

Most slide switches have two positions, and function as SPDT or DPDT switches, but other configurations are less commonly available with more poles and/or positions. A subminiature slide switch is shown in Figure 6-8, while some schematic representations are shown in Figure 6-9,



Figure 6-6. *Three rocker switches, the upper two designed for push-insertion into a suitably sized rectangular hole in a panel. The switch at front-center is intended to be screwed in place, and is more than 20 years old, showing that while the choice of materials has changed, the basic design has not.*



Figure 6-7. *This sectional view of a rocker switch shows a spring-loaded ball-bearing that rolls to and fro along a rocker arm, connecting either pair of contacts when the switch is turned.*

where a black rectangle indicates a sliding internal contact, and a terminal that functions as a pole is identified with letter P in each case. Top left: A SPDT switch using a two-position slider. Top right: A 4PDT slide switch. Bottom left: There are no poles in this switch, as such. The slider can short together any of four pairs of contacts. Bottom right: The slider shorts together three possible pairs of contacts out of four. Here again, there is no pole.

Note that the schematic representation of a slide switch may be identical to that of a slide **pushbutton**. A schematic should be inspected carefully to determine which type is intended.



Figure 6-8. *This subminiature slide switch is less than half an inch long, rated 0.3A at 30VDC. Larger versions look almost identical, but can handle only slightly more current.*

The representation of sliders in schematics has not been standardized, but the samples shown are common.

Toggle

A *toggle switch* provides a firm and precise action via a lever (the *toggle*) that is usually tear-drop shaped and nickel plated, although plastic toggles are common in cheaper variants. Formerly used to control almost all electronic components (including early computers), the toggle has declined in popularity but is still used in applications such as automobile accessory kits, motorboat instrument panels, and industrial controls.

Three miniature DPDT toggle switches are shown in Figure 6-10. Two full-size, heavy-duty toggle switches are shown in Figure 6-11. A full-size, four-pole, double-throw heavy-duty toggle switch is shown in Figure 6-12. Toggle switches with more poles are extremely rare.



Figure 6-9. *Slide switch schematics. Each black rectangle represents a movable contact that connects two pairs of fixed contacts at a time. Detailed commentary on these variants will be found in the body of the text. Manufacturers may use variants of these symbols in their datasheets (for example, the gray rectangle indicating an insulating contact carrier, at top right, may be represented as a single line, or a black outline with a white center).*



Figure 6-10. *Three miniature toggle switches with current ratings ranging from 0.3A to 6A at 125VAC. Each small square in the background grid measures 0.1" x 0.1".*

An automotive toggle switch is shown in Figure 6-13. Its plastic toggle is extended to minimize operating error.



Figure 6-11. *Two full-size toggle switches capable of handling significant current. At left, the switch terminates in quick-connect terminals. At right, the switch has solder terminals (some of them containing residual traces of solder).*



Figure 6-12. *A 4PDT full-size toggle switch with solder terminals, capable of switching 25A at 125VAC. Four-pole switches are relatively unusual.*



Figure 6-13. *A toggle switch intended for control of automotive accessories.*

High-end toggle switches are extremely durable and can be sealed from environmental contamination with a thin *boot* made from molded rubber or vinyl, which screws in place over the toggle, using the thread on the switch bushing. See Figure 6-14.



Figure 6-14. *A rubber or vinyl boot can be used to protect a toggle switch from contamination with dirt or water. Each boot contains a nut that screws onto the threads of a toggle switch, as shown at left.*

A *locking toggle switch* has a toggle that must be pulled out against the force of a retaining spring, before the toggle can be moved from one position to another. The toggle then snaps back into place, usually engaging in a small slot in the bushing of the switch.

DIP

A DIP switch is an array of very small, separate switches, designed for mounting directly on a circuit board, either in through-hole or surface-mount format. Through-hole DIP switches have two rows of pins with a 0.1″ pitch, the rows being spaced 0.3″ apart to fit a standard DIP (dual-inline package) socket or comparable configuration of holes in the board. Surface-mount DIP switches may have 0.1″ or 0.05″ pitch.

Most DIP arrays consist of SPST switches, each of which can close or open a connection between two pins on opposite sides of the switch body. The switch positions are usually labelled ON and OFF. Figure 6-15 shows a selection of DIP switches. Figure 6-16 shows the internal connections in a DIP switch.



Figure 6-15. *As shown here, DIP switches are available with a variety of "positions," meaning the number of switches, not the number of switch states.*



Figure 6-16. *The interior connections of a 16-pin DIP switch.*

The number of switches in a DIP array is usually referred to as its number of "positions." This should not be confused with the two positions of each physical switch lever. SPST DIP switches are made with 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 12, and 16 positions.

Early IBM-compatible desktop computers often required the user to set the position of an internal DIP switch when making routine upgrades such as installing an additional disk drive. While this feature is now obsolete, DIP switches are still used in scientific equipment where the user is expected to be sufficiently competent to open a cabinet and poke around inside it. Because of the 0.1″ spacing, a small screwdriver or the tip of a pen is more appropriate than a finger to flip individual levers to and fro.

DIP switches may also be used during prototype development, as they allow a convenient way to test a circuit in numerous different modes of operation.

Most DIP switches have wire terminals which are just long enough for insertion into a standard breaboard.

DIP switch package options include standard, low-profile, right-angle (standing at 90 degrees relative to the circuit board), and piano (with switch levers designed to be pressed, like tiny rocker switches, instead of being flipped to and fro).

Some SPDT, DPST, DPDT, 3PST, and 4PST variants exist, but are uncommon. Multiple external pins connect with the additional internal switch contacts, and a manufacturer's datasheet should be consulted to confirm the pattern of internal connections. A surface-mount, 0.1" pitch, DPST DIP switch is shown in Figure 6-17, with a plastic cover to protect the switches from contamination during wave soldering (at left), and with the cover peeled off (at right).



Figure 6-17. *A SPDT surface-mount double-throw DIP switch, sold with a plastic cover (shown at left) to protect it during wave soldering. The cover has been removed at right.*

SIP

A SIP switch is an array of small, separate switches, identical in concept to a DIP switch, but using only one row of pins instead of a double row. The applications for SIP switches are the same as DIP switches; the primary difference is simply that the SIP switch occupies a little less space, while being perhaps slightly less convenient to use.

One terminal of each switch usually shares a common bus. The internal connections in a typical 8-pin SIP array are shown in Figure 6-18. Pin spacing is 0.1", as in a typical DIP switch.



Figure 6-18. *The interior connections of an 8-pin SIP switch incorporating a common bus.*

Paddle

A paddle switch has a flat-sided tab-shaped plastic actuator, relatively large to allow a firm, error-free grip. Internally it is often comparable with a rocker switch, and is generally used with AC power. Some toggle-switch bodies are also sold with paddle-shaped actuators. A subminiature paddle switch is shown in Figure 6-19.



Figure 6-19. *A subminiature paddle switch. Full-size versions are often used as power switches.*

Vandal Resistant Switch

Typically fabricated from stainless steel, this is designed to withstand most types of abuse and is also weather-proof. The pushbuttons that allow pedestrians to trigger a traffic signal are a form of vandal-resistant switch.

Tactile Switch

This is considered to be a **pushbutton**, and is described in that entry. See "Tactile Switch" (page 34).

Mounting Options

A *panel mount* switch generally has a threaded bushing that is inserted from behind the front panel of a product, through a hole of appropriate size. It is supplied with a lockwasher and a nut (often, two nuts) that fit the thread on the switch bushing.

Front panel mount usually means that screws visible from the front of the panel are attached to a bracket on the switch behind the panel. The actuator of the switch is accessible through a cutout in the panel. This mounting style is mostly used for rocker switches and sometimes for slide switches.

Subpanel mount means that the switch is attached to a separate plate or chassis behind the control panel. The actuator of the switch is accessible through a cutout.

Snap-in mount requires a switch with flexible plastic or metal tabs each side, designed to push through a cutout in the panel, at which point the tabs spring out and retain the switch.

PC mount switches have pins that are soldered into a printed circuit board. They may have additional solderable lugs to provide mechanical support.

Surface mount switches are attached to a board in the same manner as other surface-mount components.

Termination

Switches (and pushbuttons) are available with a variety of terminals.

Solder lugs are small tabs, each usually perforated with a hole through which the end of a wire can be inserted prior to soldering.

PC terminals are pins that protrude from the bottom of the switch, suitable for insertion in a printed circuit board. This style is also known as a *through-hole*. The terminals may have a right-angle bend to allow the component to be mounted flat against the board, with the switch actuator sticking out at the side. This termination style is known as *right-angle PC.* Many manufacturers offer a choice of straight or bent pin terminals, but the component may be listed in a catalog under either of those options, with no indication that other options exist. Check manufacturer datasheets carefully.

Quick connect terminals are spade-shaped to accept push-on connectors, commonly used in automotive applications. Hybrid quick-connect terminals that can also function as solder lugs are sometimes offered as an option.

Screw terminals have screws premounted in flat terminals, for solderless attachment of wires.

Wire leads are flexible insulated wires, often with stripped and tinned ends, protruding at least an inch from the body of the component. This option is becoming uncommon.

Contact Plating Options

The internal electrical contacts of a switch are usually plated with silver or gold. Nickel, tin, and silver alloys are cheaper but less common. Other types are relatively rare.

Values

Switches designed for electronic devices vary widely in power capability, depending on their purpose. Rocker switches, paddle switches, and toggle switches are often used to turn power on and off, and are typically rated for 10A at 125VAC, although some toggle switches go as high as 30A. Snap-action or limit switches may be similarly rated, although miniature versions will have reduced capability. Slide switches cannot handle significant power, and are often rated around 0.5A (or less) at 30VDC. DIP and SIP switches have a typical maximum rating of 100mA at 50V and are not designed for frequent use. Generally they are used only when the power to the device is off.

How to Use it

Power Switches

When a simple SPST switch is used to turn DC power on and off, it conventionally switches the positive side of the power supply, also sometimes known as the *high side*. The primary reason for following this convention is that it is widely used; thus, following it will reduce confusion.

More importantly, an on-off switch that controls AC power must be used on the "live" side of the supply, not the "neutral" side. If you have any doubts about these concepts (which go beyond the scope of this book), consult a reference guide on this subject. Using a DPST component to switch both sides of an AC supply may be a worthwhile additional precaution in some applications. The ground wire of an AC supply should never be switched, because the device should always be grounded when it is plugged into an electric outlet.

Limit Switches

An application for two limit switches with a DC motor and two rectifier **diodes** is shown in Figure 6-20. This diagram assumes that the motor turns clockwise when its lower terminal is positive, and counter-clockwise when its upper terminal is positive. Only two terminals are used (and shown) in each limit switch; they are chosen to be normally-closed. Other terminals inside a switch may exist, may be normally-open, and can be ignored.

The motor is driven through a dual-coil, DPDT latching **relay**, which will remain in either position indefinitely without drawing power. When the upper coil of the relay receives a pulse from a pushbutton or some other source, the relay flips to its upper position, which conducts positive current through the lower limit switch, to the lower terminal of the motor. The motor turns clockwise until the arm attached to its shaft hits the lower limit switch and opens it. Positive current is blocked by the lower diode, so the motor stops.



Figure 6-20. *In this schematic, normally-closed limit switches are opened by pressure from an arm attached to a motor, thus switching off its power at each end of its permitted travel and preventing overload and burnout. A two-coil latching relay activates the motor. Rectifier diodes allow power to reach the motor to reverse its rotation when a limit switch is open.*

When the lower coil of the relay is activated, the relay flips to its lower position. Positive current can now reach the upper side of the motor through the upper limit switch. The motor runs counter-clockwise until its arm opens the upper limit switch, at which point the motor stops again. This simple system allows a DC motor to be run in either direction by a button-press of any duration, without risk of burnout when the motor reaches the end of its travel. It has been used for applications such as raising and lowering powered windows in an automobile.

A DPDT pushbutton could be substituted for the latching relay if manual control, only, is acceptable. However, in this scenario, sustained pressure on the pushbutton would be necessary to move the motor arm all the way to the opposite end of its travel. A DPDT switch might be more appropriate than a pushbutton.

Logic Circuits

Logic circuits that depend purely on switches can be constructed (for example, to add binary numbers) but are rare and have no practical applications. The most familiar and simplest example of manually switched logic is a pair of SPDT switches in house wiring, one positioned at the top of a flight of stairs and the other at the bottom, as shown in Figure 6-21. Either switch will turn the light on if it is currently off, or off if it is currently on. To extend this circuit by incorporating a third switch that has the same function as the other two, a DPDT switch must be inserted. See Figure 6-22.



Figure 6-21. *SPDT switches are commonly used in house wiring so that either of them will turn a shared light on if it is off, or off it is on.*



Figure 6-22. *A DPDT switch must be inserted if three switches must have identical function to control the on-off state of a single light bulb.*

Alternatives

As **microcontrollers** have become cheaper and more ubiquitous, they have taken over many functions in electronic products that used to be served by switches. A menuing system driven by a microcontroller can use one **rotational encoder** with a SPST pushbutton built into it to select and adjust numerous parameters in a device such as a car stereo, where functions were once selected and adjusted by individual switches and potentiometers. The rotational-encoder option takes up less space, is cheaper to build (assuming a microcontroller is going to be used in the device for other purposes anyway), and can be more reliable, as it reduces the number of electromechanical parts. Whether it is easier to use is a matter of taste. Cost and ergonomics may be the primary factors to consider when choosing where and how to use switches.

What Can Go Wrong

Arcing

The contacts inside a switch will be rapidly eroded if *arcing* (pronounced "arking") occurs. An electric arc is a spark that tends to form when a switch is opened while conducting a high current or high voltage (typically 10A or more and 100V or more). The most common cause is an inductive load that generates back-EMF when it is switched on and forward-EMF when it is switched off. The surge can be many times the amperage that the load draws during continuous operation. In DC circuits, arcing can be reduced by using a rectifier **diode** in parallel with the load (with its polarity blocking normal current flow). This is often referred to as a *flyback diode* or *freewheeling diode*. In AC circuits, where a diode cannot be used in this way, a *snubber* (a simple combination of capacitor and resistor) may be placed around the load. A snubber can also be used around the switch itself, in DC circuits. See "Snubber" (page 108).

When switching an inductive load, it is generally prudent to use switches rated for twice as much current as the circuit will normally draw.

Dry Joints

Switches that control significant current will have substantial terminals, and these terminals will be attached to heavy-gauge wire. When using solder to make this type of connection, the combined heat capacity of the wire and the terminal will sink a lot more heat than a small component on a circuit board. At least a 30W soldering iron should be used. Lower-wattage irons may be incapable of melting the solder completely (even though they seem to), and a "dry joint" will result, which can have a relatively high electrical resistance and will be mechanically weak, liable to break later. Any good solder joint should withstand flexing of the wire attached to it.

Short Circuits

Because many switches are still wired in with solder tabs, screw terminals, or quick-connect terminals, wires that become accidentally detached can be a significant hazard. Heat-shrink tubing should be applied to enclose wires and terminals at the rear of a power switch, as an additional precaution. Power switches should always be used in conjunction with appropriate **fuses**.

Contact Contamination

Sealed switches should be used in any environment where dirt or water may be present. Slide switches are especially vulnerable to contamination, and are difficult to seal. Switches used in audio components will create "scratchy" sounds if their contacts deteriorate.

Wrong Terminal Type

Because switches are available with a wide variety of terminal types, it's easy to order the wrong type. Switches may be supplied with pins for through-hole insertion in circuit boards; screw terminals; quick-disconnect terminals; or solder lugs. Variants may also be available for surface mount. If a project requires, for example, the insertion of pins in a printed circuit board, and a switch is supplied with solder lugs, it will be unusable.

Part numbers generally include codes to identify each terminal variant, and should be studied carefully.

Contact Bounce

Also known as *switch bounce*. When two contacts snap together, extremely rapid, microscopic vibrations occur that cause brief interruptions before the contacts settle. While this phenomenon is not perceptible to human senses, it can be perceived as a series of multiple pulses by a **logic chip**. For this reason, various strategies are used to *debounce* a switch that drives a logic input. This issue is explored in detail in the entry on logic chips in Volume 2 of the encyclopedia.

Mechanical Wear

Any toggle or rocker switch contains a mechanical pivot, which tend to deteriorate in harsh environments. Friction is also an issue inside these switches, as the design often entails the rounded tip of a lever rubbing to and fro across the center of a movable contact.

The spring inside a snap switch or limit switch may fail as a result of metal fatigue, although this is rare. A slide switch is far less durable, as its contacts rub across each other every time the switch changes position.

In any application that entails frequent switching, or where switch failure is a critical issue, the most sensible practice is to avoid using cheap switches.

Mounting Problems

In a panel-mount switch that is secured by turning a nut, the nut may loosen with use, allowing the component to fall inside its enclosure. Conversely, overtightening the nut may strip the threads on the switch body, especially in cheaper components where the threads are molded into plastic. Consider applying a drop of Loc-Tite or similar adhesive after moderately tightening the nut. Note that nut sizes vary widely, and finding a replacement may be time-consuming.

Cryptic Schematics

In some circuit schematics, the poles of a multipole switch may be visually separated from each other, even at opposite sides of the page, for convenience in drawing the schematic. Dotted lines usually, but not always, link the poles. In the absence of dotted lines, switch segments are often coded to indicate their commonality. For example, SW1(a) and SW1(b) are almost certainly different parts of the same switch, with linked poles.

rotary switch

7

Not to be confused with **rotational encoder**, which has its own entry in this encyclopedia.

OTHER RELATED COMPONENTS

- **switch** (See Chapter 6)
- **rotational encoder** (See Chapter 8)

What It Does

A rotary switch makes an electrical connection between a *rotor*, mounted on a shaft that is turned by a knob, and one of two or more stationary contacts. Traditionally, it was the component of choice to select wavebands on a radio receiver, broadcast channels on a television or inputs on a stereo preamplifier. Since the 1990s, it has been substantially superceded by the **rotational encoder**. However it still has applications in military equipment, field equipment, industrial control systems, and other applications requiring a rugged component that will withstand heavy use and a possibly harsh environment. Also, while the output from a rotational encoder must be decoded and interpreted by a device such as a microcontroller, a rotary switch is an entirely passive component that does not require any additional electronics for its functionality.

Two typical schematic symbols for a rotary switch are shown in Figure 7-1. They are functionally identical. A simplified rendering of the interior of a traditional-style rotary switch is shown in Figure 7-2. A separate contact (not shown) connects with the rotor, which connects with each of the stationary contacts in turn. The colors were chosen to differentiate the parts more clearly, and do not correspond with colors in an actual switch.



Figure 7-1. *Typical schematic symbols for a rotary switch. The two symbols are functionally identical. The number of contacts will vary depending on the switch.*

A selection of rotary switches is shown in Figure 7-3. At top-left is an *open frame* switch, providing no protection to its contacts from contaminants. This type of component is now rare. At top-right is a twelve-position, single-pole switch rated 2.5A at 125VAC. At front-left is a four-position, single-pole switch rated 0.3A at 16VDC or 100VAC. At front right is a two-position, two-pole switch with the same rating as the one beside it. All the sealed switches allow a choice of panel mounting or through-hole printed circuit board mounting.



Figure 7-2. *A simplified rendering of interior parts in a basic SP6T rotary switch. Arbitrary colors have been added for clarity.*

How It Works

A switch may have multiple poles, each connecting with its own rotor. The rotors are likely to be on separate *decks* of the switch, but two, three, or four rotors, pointing in different directions, may be combined on a single deck if the switch has only a small number of positions.

Rotary switches are usually made with a maximum of twelve positions, but include provision for limiting the number of positions with a *stop*. This is typically a pin, which may be attached to a washer that fits around the bushing of the switch. The pin is inserted into a choice of holes to prevent the switch from turning past that point. For example, an eight-position rotary switch can be configured so that it has only seven (or as few as two) available positions.

A specification for a rotary switch usually includes the angle through which the switch turns between one position and the next. A twelve-position switch usually has a 30-degree turn angle.



Figure 7-3. *A selection of rotary switches. See text for details.*

Variants

Conventional

The traditional style of rotary switch is designed to be panel-mounted, with a body that ranges from 1" to 1.5" in diameter. If there is more than one deck, they are spaced from each other by about 0.5". The switch makes an audible and tactile "click" as it is turned from one position to the next.

A rugged sealed five-deck rotary switch is shown in Figure 7-4. It has five poles (one per deck), and a maximum of 12 positions. The contacts are rated 0.5A at 28VDC. This type of heavy-duty component is becoming relatively rare.

If the rotor in a switch establishes a connection with the next contact a moment before breaking the connection with the previous contact, this is known as a *shorting* switch, which may also be described as a *make-before-break* switch. In a *nonshorting* or *break-before-make* switch, a tiny



Figure 7-4. *A five-pole, twelve-position rotary switch.*

interval separates one connection from the next. This can be of significant importance, depending on the components that are connected with the switch.

The shaft may be round, splined, or D-shaped in section. A knob is seldom supplied with a switch and must be chosen to match the shaft. Some shaft dimensions are metric, while others are measured in inches, with 1/4" diameter being the oldest standard. Some switches with a splined shaft are supplied with an adapter for a knob of D-shaped internal section; the adapter can be slipped onto the shaft in any of 12 or more positions, to minimize the inconvenience of positioning the body of the switch itself so that the knob is correctly oriented in relation to positions printed on the face of the panel.

Miniature rotary switches may be as small as 0.5" diameter, and usually terminate in pins for through-hole mounting on a PC board. Miniature switches usually have lower current ratings than full-size switches.

Rotary switches must be securely anchored to resist the high turning forces that can be inflicted upon them by users. In a panel-mount design, a nut is tightened around a thread on the bushing of the switch. Through-hole versions can be secured to the PC board with the shaft protruding loosely through a cutout in the panel. To minimize mechanical stress on the circuit board, the detents in a PC-board switch are usually weaker than in a full-size switch, and the knob is usually smaller, allowing less leverage.

Rotary DIP

A conventional *DIP switch* is a linear array of miniature SPST switches designed to fit a standard DIP (dual-inline package) layout of holes in a circuit board. It is described in the **switch** entry of this encyclopedia. A *rotary DIP* switch (also known as an *encoded output rotary switch* or a *coded rotary switch*) does not conform with a DIP layout, despite its name. It is approximately 0.4" square and usually has five pins, one of which can be considered the input or common pin while the other four can function as outputs. The pins are spaced at 0.1" pitch from one another. Pin function and layout are not standardized.

A dial on top of the switch has either 10 positions (numbered 0 through 9) or 16 positions (0 through 9 followed by letters A through F). One switch of each type is shown in Figure 7-5.

Each position of the dial closes pairs of contacts inside the component to create a unique binary-coded decimal pattern (in a 10-position switch) or binary-coded hexadecimal pattern (in the 16-position switch) on the four output pins. The pin states are shown in Figure 7-6. A rotary DIP switch is a relatively flimsy device, and is not designed for frequent or heavy use. It is more likely to be a "set it and forget it" device whose state is established when it is installed in a circuit board.

Because each position of the switch is identified with a unique binary pattern, this is an example of *absolute encoding*. By contrast, a typical **rotational encoder** uses *relative encoding*, as it merely generates a series of undifferentiated pulses when the shaft is turned.



Figure 7-5. *A rotary DIP switch, also known as an encoded output rotary switch, may be used as a substitute for a DIP switch in some applications.*

A *real-coded* rotary DIP makes a connection between input and output pins wherever a binary 1 would exist. In the *complement-coded* version, the output is inverted. The switch is primarily intended for use with a **microcontroller**, enabling only four binary input pins on the microcontroller to sense up to sixteen different switch positions.

A six-pin rotary DIP variant is available from some manufacturers, with two rows of three pins, the two center pins in each row being tied together internally, and serving as the pole of the switch.

Rotary DIPs are available with a screw slot, small knurled knob, or larger knob. The screw-slot version minimizes the height of the component, which can be relevant where circuit boards will be stacked close together. A *right-angle PC* variant stands at 90 degrees to the circuit board, with pins occupying a narrower footprint. The switch on the left in Figure 7-5 is of this type.

While most rotary DIPs are through-hole components, surface-mount versions are available.

Most rotary DIPs are sealed to protect their internal components during wave-soldering of circuit boards.



Switch Position	Pin 1	Pin 2	Pin 3	Pin 4
0	⚫	⚫	⚫	⚫
1	🔴	⚫	⚫	⚫
2	⚫	🔴	⚫	⚫
3	🔴	🔴	⚫	⚫
4	⚫	⚫	🔴	⚫
5	🔴	⚫	🔴	⚫
6	⚫	🔴	🔴	⚫
7	🔴	🔴	🔴	⚫
8	⚫	⚫	⚫	🔴
9	🔴	⚫	⚫	🔴
A	⚫	🔴	⚫	🔴
B	🔴	🔴	⚫	🔴
C	⚫	⚫	🔴	🔴
D	🔴	⚫	🔴	🔴
E	⚫	🔴	🔴	🔴
F	🔴	🔴	🔴	🔴

Figure 7-6. *Positive and negative states of the four output pins of a real-coded 16-position rotary DIP switch, assuming that the common pin of the switch is connected with a positive supply voltage. A ten-position rotary DIP switch would use only the states from 0 through 9. In a complement-coded switch, the positive and negative states would be reversed.*

Gray Code

A Gray code (named after its originator, Frank Gray) is a system of absolute encoding of a switch output, using a series of nonsequential binary numbers that are chosen in such a way that each number differs by only one digit from the preceding number. Such a series is useful because it eliminates the risk that when a switch turns, some bits in the output will change before others, creating the risk of erroneous interpretation. A minority of rotary switches or rotational encoders are available with Gray-coded outputs. Typically, a microcontroller must use a lookup table to convert each binary output to an angular switch position.

PC Board Rotary Switch

Miniature switches with a conventional, non-encoded output are available for printed-circuit board mounting, sometimes requiring a screwdriver or hex wrench to select a position. A single-pole eight-position switch of this type is shown in Figure 7-7. Its contacts are rated to carry 0.5A at 30VDC, but it is not designed to switch this current actively.



Figure 7-7. *This miniature switch is designed for insertion on a printed circuit board. It can be used to make a setting before a device is shipped to the end user.*

Mechanical Encoder

A *mechanical encoder* functions similarly to a rotary DIP switch but is intended for much heavier use. It outputs a binary-coded-decimal value corresponding with its shaft position, is typically the size of a miniature rotary switch, and is designed for panel mounting. The Grayhill Series 51 allows 12 positions, each generating a code among four terminals. The Bourns EAW provides 128 positions, each generating a code among 8 terminals.

Pushwheel and Thumbwheel

A *pushwheel switch* is a simple electromechanical device that enables an operator to provide a code number as input to data processing equipment, often in industrial process control. The decimal version contains a wheel on which numbers are printed, usually in white on black, from 0 through 9, visible one at a time through a window in the face of the switch. A button above the wheel, marked with a minus sign, rotates it to the next lower number, while a button below the wheel, marked with a plus sign, rotates it to the next higher number. A connector at the rear of the unit includes a common (input) pin and four output pins with values 1, 2, 4, and 8. An additional set of pins with values 1, 2, 3, and 4 is often provided. The states of the output pins sum to the value that is currently being displayed by the wheel. Often two, three, or four pushwheels (each with an independent set of connector pins) are combined in one unit, although individual pushwheels are available and can be stacked in a row.

A *thumbwheel switch* operates like a pushwheel switch, except that it uses a thumbwheel instead of two buttons. Miniaturized thumbwheel switches are available for through-hole mounting on PC boards.

Hexadecimal versions are also available, with numbers from 0 through 9 followed by letters A through F, although they are less common than decimal versions.

Keylock

A *keylock switch* is generally a two-position rotary switch that can be turned only after insertion of a key in a lock attached to the top of the shaft. This type of switch almost always has an OFF-(ON) configuration and is used to control power.

Keylock switches are found in locations such as elevators, for fire-department access; in cash registers; or on data-processing equipment where switching power on or off is reserved for a system administrator.

Values

A full-size rotary switch may be rated from 0.5A at 30VDC to 5A at 125VAC, depending on its purpose. A very few switches are rated 30A at 125VAC; these are high-quality, durable, expensive items.

A typical rotary DIP switch is rated 30mA at 30VDC and has a carrying current rating (continuous current when no switching occurs) of no more than 100mA at 50VDC.

How to Use it

In addition to its traditional purpose as a mode or option selector, a rotary switch provides a user-friendly way to input data values. Three ten-position switches, for instance, can allow user input of a decimal number ranging from 000 to 999.

When used with a **microcontroller**, a rotary switch can have a *resistor ladder* mounted around its contacts, like a multi-point *voltage divider*, so that each position of the rotor provides a unique potential ranging between the positive supply voltage and negative ground. This concept is illustrated in Figure 7-8, where all the resistors have the same value. The voltage can be used as an input to the microcontroller, so long as the microcontroller shares a common ground with the switch. An analog-digital converter inside the microcontroller translates the voltage into a digital value. The advantage of this scheme is that it allows very rapid control by the user, while requiring only one pin on the microcontroller to sense as many as twelve input states.



Figure 7-8. *A resistor ladder can be formed around the contacts of a rotary switch, with the pole of the switch connected to a microcontroller that has an analog-digital converter built in. The microcontroller converts the voltage input to an internal digital value. Thus, one pin can sense as many as twelve input states.*

For a ladder consisting of 8 resistors, as shown, each resistor could have a value of 250Ω. (The specifications for a particular microcontroller might require other values.) To avoid ambiguous inputs, a nonshorting rotary switch should be used in this scheme. A *pullup resistor* of perhaps 10K should be added to the microcontroller input, so that there is no risk of it “floating” when the switch rotor is moving from one contact to the next. The code that controls the microcontroller can also include a blanking interval during which the microcontroller is instructed to ignore the switch.

Because the rotary switch is an electromechanical device, it has typical vulnerabilities to dirt and moisture, in addition to being bulkier, heavier, and more expensive than a **rotational encoder**. Rotary switches have also been partially replaced by pushbuttons wired to a microcontroller. This option is found on devices ranging from digital alarm clocks to cellular phones. In addition to being cheaper, the pushbutton alternative is preferable where space on a control panel, and behind it, is limited.

What Can Go Wrong

Vulnerable Contacts

Most modern rotary switches are sealed, but some are not. Any switch with exposed contacts will be especially vulnerable to dirt and moisture, leading to unreliable connections. This was an issue in old-fashioned TV sets, where periodic contact cleaning of the channel selector switch was needed.

Exposed contacts are also more vulnerable to side-effects from temperature cycling (when a device warms up and then cools down).

Contact Overload

The contacts on a cheap rotary switch are especially vulnerable to arcing, as the user may turn the switch slowly, causing gradual engagement and disengagement of contacts instead of the snap-action that is characteristic of a well-made toggle switch. If a rotary switch may control significant currents or current surges, it must be appropriately rated, regardless of the extra expense. For more information on arc suppression in switches, see "Arcing" (page 47).

Misalignment

Most knobs for rotary switches consist of a pointer, or have a white line engraved to provide clear visual indication of the position of the switch. If this does not align precisely with indications printed on the panel, confusion will result. For hand-built equipment, the switch can be installed first, after which the control-panel indications can be glued or riveted in place on a separate piece of laminated card, plastic, or metal for precise alignment. If the switch is not secured tightly, its body may turn slightly under repeated stress, leading to erroneous interpretation of the knob position.

Misidentified Shorting Switch

If a shorting switch is used where a nonshorting switch was intended, the results can be disconcerting or even destructive, as one terminal will be briefly connected with the adjacent terminal while the switch is being turned. Multiple functions of a circuit may be activated simultaneously, and in a worst case scenario, adjacent terminals may be connected to opposite sides of the same power supply.

User Abuse

The turning force that must be applied to a full-size conventional rotary switch is significantly greater than the force that is applied to most other types of panel-mounted switches. This encourages aggressive treatment, and the turning motion is especially likely to loosen a nut holding the switch in place. The lighter action characteristic of miniature rotary switches does not necessarily solve this problem, as users who are accustomed to older-style switches may still apply the same force anyway.

Rotary switches should be mounted in expectation of rough use. It is prudent to use Loc-Tite or a similar compound to prevent nuts from loosening, and a switch should not be mounted in a thin or flimsy panel. When using a miniature rotary switch that has through-hole mounting in a circuit board, the board must be sufficiently robust and properly secured.

Wrong Shaft, Wrong Knobs, Nuts That Get Lost, Too Big to Fit

These problems are identical to those that can be encountered with a **potentiometer**, which are discussed in that entry in this encyclopedia.

8

rotational encoder

The term *rotational encoder* used to be reserved for high-quality components, often using optical methods to measure rotation with precision (more than 100 intervals in 360 degrees). Cheaper, simpler, electromechanical devices were properly referred to as *control shaft encoders*. However, the term *rotational encoder* is now applied to almost any device capable of converting rotational position to a digital output via opening and closing internal mechanical contacts; this is the sense in which the term is used here. It is sometimes distinguished from other types of encoder with the term *mechanical rotary encoder*. Magnetic and optical rotary encoders do not contain mechanical switches, are classified as *sensors* by this encyclopedia, and will appear in Volume 3. They are found in a device such as an *optical mouse*.

OTHER RELATED COMPONENTS

- **rotary switch** (See Chapter 7)

What It Does

A rotational encoder has a knob that a user can turn to display a series of prompts on an LCD screen, or to adjust the input or output on a product such as a stereo receiver. The component is almost always connected to inputs on a **microcontroller** and is usually fitted with *detents* that provide tactile feedback suggesting many closely spaced positions. The encoder often allows the user to make a selection by pushing the knob in, which closes an internal momentary switch. Thus, this type of encoder functions as a pushbutton as well as a switch.

A rotational encoder is an *incremental* or *relative* device, meaning that it merely creates and breaks internal switch connections when rotation occurs, without providing a unique code to identify each absolute rotational position. An *absolute* encoder is discussed in the **rotary switch** entry of this encyclopedia.

No schematic symbol exists to represent a rotational encoder.

How It Works

An encoder contains two pairs of contacts, which open and close out of phase with each other when the shaft rotates. In a clockwise direction, the A pair of contacts may be activated momentarily before the B pair; in a counter-clockwise direction, the B pair may be activated before the A pair. (Some encoders reverse this phase difference.) Thus if one contact from each pair is connected with two inputs of an appropriately programmed microcontroller, and if the other contact of each pair is connected with negative ground, the microcontroller can deduce which way the knob is turning by sensing which pair of contacts closes first. The microcontroller can then count the number of pulses from the contacts and interpret this to adjust an output or update a display.

A simplified schematic is shown in Figure 8-1. The two buttons inside the dashed line represent the two pairs of contacts inside the encoder, while the chip is a microcontroller. The knob and shaft that activate the internal switches are not shown. The schematic assumes that when a contact closes, it pulls the chip input to a low state. A pullup resistor is added to each input of the chip to prevent the pins from "floating" when either pair of contacts is open.



Figure 8-1. *Simplified schematic showing the typical setup for a rotational encoder. The pushbuttons inside the dashed line represent the contacts inside the encoder. The chip is a microcontroller.*

Figure 8-2 gives a conceptual view of the outputs of an encoder that is turned clockwise (top) and then counter-clockwise (bottom). Some encoders may reverse this phase sequence. Red and black colors have been assigned to the pin states on the assumption that the terminals that are common to both pairs of contacts are connected with negative ground. Thus a "high" pulse in the graphical representation actually indicates that the encoder is grounding its output.

Microcontrollers have become so ubiquitous, and rotational encoders are so cheap, they have displaced rotary switches in many applications where a low current is being switched. The combination of a rotational encoder and a microcontroller is very versatile, allowing display and control of an almost unlimited number of menus and options.



Clockwise Rotation
Detent Positions
Output from contact pair A
Output from contact pair B
Pin States
A A A A A A A A
B B B B B B B B
Counter-Clockwise Rotation
Detent Positions
Output from contact pair A
Output from contact pair B
Pin States
A A A A A A A A
B B B B B B B B

Figure 8-2. *Hypothetical outputs from a rotational encoder, assuming that the common terminals of the contact pairs are connected to negative ground. A high pulse in the graphical representation therefore indicates that the contact pair is grounded. The number of detents relative to the number of pulses per rotation varies from one type of encoder to another.*

Variants

There are two types of rotational encoders containing mechanical contacts: absolute and relative. An absolute encoder generates a code corresponding with each specific rotational position. The code is usually a binary output among four or more pins. It is discussed under *mechanical encoder* in the **rotary switch** section of this encyclopedia. The variants listed here are all relative encoders.

Pulses and Detents

Rotational encoders from different manufacturers may have as few as 4 or as many as 24 pulses per rotation (PPR), with 12 to 36 detents (or no detents at all, in a few models.) The relationship between pulses and detents shown in Figure 8-2 is typical but is far from being universal. The number of detents may be equal to, greater than, or less than the number of pulses per rotation.

Format

Rotational encoders are generally panel-mounted or through-hole devices. In the latter category, most are horizontally mounted, with a minority being at 90 degrees to the board.

Output

In an encoder containing two switches, four switch-state combinations are possible: OFF-OFF, ON-OFF, OFF-ON, and ON-ON. This is known as a *quadrature* output. All of the rotational encoders discussed here conform with that system.

Rotational Resistance

Rotational encoders vary widely in the resistance that they offer when the user turns the knob. This is largely a function of the detents, if they are included. Still, all rotational encoders generally offer less rotational resistance than a rotary switch, and do not have the kind of heavy-duty knobs that are typically used with rotary switches. Since an encoder creates only a stream of pulses without any absolute positional information, a knob with any kind of pointer on it is inappropriate.

Values

Virtually all rotational encoders are designed to work with a low-voltage supply, 12VDC or less. All of them are intended for low currents, reflecting their purpose to drive microcontroller inputs. Some sample rotational encoders are pictured in Figure 8-3. At rear: nine pulses per rotation (PPR), 36 detents, 10mA at 10VDC. Far left: 20PPR, 20 detents, with switch. Far right: 24PPR, no detents, 1mA at 5VDC. Center (blue): 16PPR, no detents, 1mA at 5VDC. Front: 12PPR, 24 detents, 1mA at 10VDC, requires Allen wrench or similar hexagonal shaft to engage with the rotor.



Figure 8-3. *Rotational encoders with a variety of specifications. See text for details.*

Contact Bounce

Any mechanical switch will suffer some degree of *contact bounce* when its contacts close. Datasheets for rotational encoders may include a specification for bounce duration ranging from around 2ms to 5ms, which is sometimes known as the *settling time*. Naturally, a lower value is preferred. The microcontroller that interprets the positional information from the encoder can include a debouncing routine that simply disregards any signals during the bounce period following switch closure.

Sliding Noise

Sliding noise is the opposite of contact bounce. When two contacts have made a connection and then rub across each other (as occurs inside a rotational encoder while the knob is being turned), the connection may suffer momentary lapses. Datasheets for rotational encoders generally do not supply ratings for this.

How to Use it

As noted above, a rotational encoder can only be used in conjunction with a microcontroller or similar device that is capable of interpreting the phase difference between the pairs of contacts, and is capable of counting the number of opening/closing events while the knob is being turned. (Some dedicated chips are designed for this specific purpose.)

It can be adapted to be driven by a **stepper motor**, to provide feedback regarding the rotation of the motor shaft, and its output can also be interpreted to calculate angular acceleration.

Programming the microcontroller is the most significant obstacle. Generally the program should follow a sequence suggested by this pseudocode:

Check:

- If the encoder contains a pushbutton switch, check it. If the pushbutton is being pressed, go to an appropriate subroutine.
- The status of contacts A.
- The status of contacts B.

Compare their status with previously saved states for A and B. If the status has not changed, repeat from Check.

Debounce:

- Recheck the contacts status rapidly and repeatedly for 50ms, and count the states for contacts A and B. (The 50ms duration may be adjusted for different encoders, as an encoder with a higher number of pulses per rotation will tend to create shorter pulses.)
- Compare the total number of changed states with unchanged states.

If the changed states are in a small minority, probably the signal was erroneous, caused by bounce or sliding noise. Go back to Check and start over.

Interpret:

- Deduce the rotational direction from these four possibilities:
  - — Contacts A were open and have closed.
  - — Contacts A were closed and have opened.
  - — Contacts B were open and have closed.
  - — Contacts B were closed and have opened. (The specific type of encoder will determine how these transitions are interpreted.)
- Revise the variable storing the direction of rotation if necessary.
- Depending on the direction of rotation, increment or decrement a variable that counts pulses.
- Take action that is appropriate to the direction of rotation and the cumulative number of pulses.
- Go back to Check again.

What Can Go Wrong

Switch Bounce

In addition to a debouncing algorithm in the microcontroller, a 0.1µF bypass capacitor can be used with each of the output terminals from the encoder, to help reduce the problem of switch bounce.

Contact Burnout

Rotational encoders are TTL-compatible. They are not generally designed to drive even a small output device, such as an LED. The contacts are extremely delicate and will be easily damaged by any attempt to switch a significant current.

relay

9

Properly known as an *electromagnetic armature relay* to distinguish it from a *solid-state relay*. However, the full term is very rarely used. It may also be described as an *electromechanical relay*, but the term **relay** is normally understood to mean a device that is not solid state.

OTHER RELATED COMPONENTS

- **solid state relay** (Volume 2)
- **switch** (See Chapter 6)

What It Does

A relay enables a signal or pulse of electricity to switch on (or switch off) a separate flow of electricity. Often, a relay uses a low voltage or low current to control a higher voltage and/or higher current. The low voltage/low current signal can be initiated by a relatively small, economical switch, and can be carried to the relay by relatively cheap, small-gauge wire, at which point the relay controls a larger current near to the load. In a car, for example, turning the ignition switch sends a signal to a relay positioned close to the starter motor.

While solid-state switching devices are faster and more reliable, relays retain some advantages. They can handle double-throw and/or multiple-pole switching and can be cheaper when high voltages or currents are involved. A comparison of their advantages relative to **solid state relays** and **transistors** is tabulated in the entry on **bipolar transistor** in Figure 28-15.

Common schematic symbols for single-throw relays are shown in Figure 9-1 and for double-throw relays in Figure 9-2. The appearance and orientation of the coil and contacts in the symbols may vary significantly, but the functionality remains the same.



Figure 9-1. *Commonly used schematic symbols for a SPST relay. The symbols are functionally identical.*



Figure 9-2. *Commonly used schematic symbols for a SPDT relay. The symbols are functionally identical.*

How It Works

A relay contains a *coil*, an *armature*, and at least one pair of *contacts*. Current flows through the coil, which functions as an **electromagnet** and generates a magnetic field. This pulls the armature, which is often shaped as a pivoting bracket that closes (or opens) the contacts. These parts are visible in the simplified rendering of a DPST relay in Figure 9-3. For purposes of identification, the armature is colored green, while the coil is red and the contacts are orange. The two blue blocks are made of an insulating material, the one on the left supporting the contact strips, the one on the right pressing the contacts together when the armature pivots in response to a magnetic field from the coil. Electrical connections to the contacts and the coil have been omitted for simplicity.



Figure 9-3. *This simplified rendering shows the primary parts of a DPST relay. See text for details.*

Various small relays, capable of handling a variety of voltages and currents, are pictured in Figure 9-4. At top-left is a 12VDC automotive relay, which plugs into a suitable socket shown immediately below it. At top-right is a 24VDC SPDT relay with exposed coil and contacts, making it suitable only for use in a very clean, dry environment. Continuing downward, the four sealed relays in colored plastic cases are designed to switch currents of 5A at 250VAC, 10A at 120VAC, 0.6A at 125VAC, and 2A at 30VDC, respectively. The two blue relays have 12VDC coils, while the red and yellow relays have 5V coils. All are nonlatching, except for the yellow relay, which is a latching type with two coils. At bottom-left is a 12VDC relay in a transparent case, rated to switch up to 5A at 240VAC or 30VDC.



Figure 9-4. *An assortment of small DC-powered relays. See text for details.*

The configuration of a relay is specified using the same abbreviations that apply to a **switch**. SP, DP, 3P, and 4P indicate 1, 2, 3, or 4 poles (relays with more than 4 poles are rare). ST and DT indicate single-throw or double-throw switching. These abbreviations are usually concatenated, as in 3PST or SPDT. In addition, the terminology Form

A (meaning normally open), Form B (normally closed), and Form C (double-throw) may be used, preceded by a number that indicates the number of poles. Thus "2 Form C" means a DPDT relay.

Variants

Latching

There are two basic types of relay: *latching* and *nonlatching*. A nonlatching relay, also known as a *single side stable* type, is the most common, and resembles a *momentary switch* or **pushbutton** in that its contacts spring back to their default state when power to the relay is interrupted. This can be important in an application where the relay should return to a known state if power is lost. By contrast, a latching relay has no default state. Latching relays almost always have double-throw contacts, which remain in either position without drawing power. The relay only requires a short pulse to change its status. In semiconductor terms, its behavior is similar to that of a *flip-flop*.

In a *single-coil* latching relay, the polarity of voltage applied to the coil determines which pair of contacts will close. In a *dual-coil* latching relay, a second coil moves the armature between each of its two states.

Schematic symbols for a dual-coil latching relay are shown in Figure 9-5. Some symbol styles do not make it clear which switch position each coil induces. It may be necessary to read the manufacturer's datasheet or test the relay by applying its rated voltage to randomly selected terminal pairs while testing for continuity between other terminal pairs.

Polarity

There are three types of DC relay. In a *neutral relay*, polarity of DC current through the coil is irrelevant. The relay functions equally well either way. A *polarized relay* contains a diode in series with the coil to block current in one direction. A *biased relay* contains a permanent magnet near the armature, which boosts performance when current flows through the coil in one direction, but blocks a response when the current flows through the coil in the opposite direction. Manufacturers' datasheets may not use this terminology, but will state whether the relay coil is sensitive to the polarity of a DC voltage.



Figure 9-5. *Schematic symbols for a two-coil latching relay. The symbols are functionally identical.*

All relays can switch AC current, but only an *AC relay* is designed to use AC as its coil current.

Pinout Variations

The layout and function of relay pins or quick connects is not standardized among manufacturers. Often the component will have some indication of pin functions printed on it, but should always be checked against the manufacturer's datasheet and/or tested for continuity with a meter.

Figure 9-6 shows four sample pin configurations, adapted from a manufacturer's datasheet. These configurations are functionally quite different, although all of them happen to be for DPDT relays. In each schematic, the coil of the relay is shown as a rectangle, while the pins are circles, black indicating an energized state and white indicating a non-energized state. The bent lines show the possible connections between the poles and other contacts inside the relay. The contacts are shown as arrows. Thus, pole 4 can connect with either contact 3 or contact 5, while pole 9 can connect with either contact 8 or contact 10.

Top-left: Polarized nonlatching relay in its resting condition, with no power applied. Top right: Single-coil latching relay showing energized contacts (black circles) when the coil is powered with the polarity indicated. If the polarity is reversed, the relay flips to its opposite state. Some manufacturers indicate the option to reverse polarity by placing a minus sign alongside a plus sign, and a plus sign alongside a minus sign. Bottom-left and bottom-right: Polarized latching relays with two coils, with different pinouts.



Figure 9-6. *Relay pinouts depicted in the style commonly found in manufacturers' datasheets, showing different relay types. Top-left: Single coil, nonlatching. Top-right: Single coil, latching. Bottom left: Two-coil, latching. Bottom right: Two-coil, latching, alternate pinouts. (Adapted from a Panasonic datasheet.)*

In these diagrams, the relay is seen from above. Some datasheets show the relay seen from below, and some show both views. Some manufacturers use slightly different symbols to indicate interior functions and features. When in doubt, use a meter for verification.

Reed Relay

A *reed relay* is the smallest type of electromechanical relay with applications primarily in test equipment and telecommunications. With a coil resistance ranging from 500 to 2000 ohms, these relays consume very little power. The design consists of a *reed switch* with a coil wrapped around it. Figure 9-7 shows a simplified rendering. The two black contacts are enclosed in a glass or plastic envelope and magnetized in such a way that a magnetic field from the surrounding coil bends them together, creating a connection. When power to the coil is disconnected, the magnetic field collapses and the contacts spring apart.



Figure 9-7. *This simplified rendering shows a reed relay, consisting of a magnetized reed switch inside a glass or plastic pod, activated by a coil wrapped around it.*

In Figure 9-8, two reed relays are shown, at top-left and center-right. At bottom-left, the type of relay on the right has been opened by a belt sander to reveal its copper coil and inside that, a capsule in which the relay contacts are visible.

Surface-mount reed relays can be smaller than 0.5″ × 0.2″. Through-hole versions are often around 0.7″ × 0.3″ with pins in two rows, though some are available in SIP packages.

Reed relays have limited current switching capacity and are not suitable to switch inductive loads.

Small Signal Relay

A *small signal relay* is also known as a *low signal relay*. This type may have a footprint as small as a reed relay but generally stands slightly taller, requires slightly more coil current, and is available in versions that can switch slightly higher



Figure 9-8. *Three reed relays, one of which has had its packaging partially removed by a belt sander to reveal its copper coil and internal contacts.*

voltages and currents. There are usually two rows of pins, spaced either 0.2″ or 0.3″ apart. The red and orange relays in Figure 9-4 are small signal relays.

Automotive Relays

An *automotive relay* is typically packaged in a cube-shaped black plastic case with quick-connect terminals at the bottom, typically plugged into a socket. Naturally they are designed to switch, and be switched by, a 12VDC supply.

General Purpose/Industrial

These relays cover a very wide range and are usually built without significant concern for size. They may be capable of switching high currents at high voltages. Typically they are designed to plug into a socket such as an *octal base* of the type that was once used for **vacuum tubes**. The base, in turn, terminates in solder tabs, screws, or quick connects and is designed to be screwed to a chassis. It allows the relay to be unplugged and swapped without resoldering.

Two industrial relays are shown in Figure 9-9. Both are DPDT type with 12VDC coils and rated to switch up to 10A at 240VAC. The one on the left has an octal base. An octal socket that fits an octal base is shown in Figure 9-10.



Figure 9-9. *Two relays powered by 12VDC, capable of switching up to 10A at 240VAC.*



Figure 9-10. *An octal socket with screw terminals, designed to accept a relay with an octal base.*

Time Delay Relay

Generally used to control industrial processes, a *time delay relay* switches an output on and off at preset time intervals that can be programmed to repeat. The example in Figure 9-11 has a 12VDC coil and is rated to switch up at 10A at 240VAC. It has an octal base.



Figure 9-11. *The control switches on a time-delay relay, allowing separately configured "on" and "off" intervals.*

Contactor

A contactor functions just like a relay but is designed to switch higher currents (up to thousands of amperes) at higher voltages (up to many kilovolts). It may range from being palm-sized to measuring more than one foot in diameter, and may be used to control heavy loads such as very large motors, banks of high-wattage lights, and heavy-duty power supplies.

Values

Datasheets usually specify maximum voltage and current for the contacts, and nominal voltage and current for the coil, although in some cases the coil resistance is stated instead of nominal coil current. The approximate current consumption can be estimated, if necessary, by using Ohm's Law. The minimum voltage that the relay needs for activation is sometimes described as the *Must Operate By* voltage, while the *Must Release By* voltage is the maximum coil voltage that the relay will ignore. Relays are rated on the assumption that the coil may remain energized for long periods, unless otherwise stated.

While the contact rating may suggest that a relay can switch a large load, this is not necessarily true if the load has significant inductance.

Reed relays

Usually use a coil voltage of 5VDC and have a contact rating of up to 0.25A at 100V. Through-hole (PCB) versions may have a coil voltage of 5VDC, 6VDC, 12VDC, or 24VDC and in some cases claim to switch 0.5A to 1A at up to 100V, although this rating is strictly for a noninductive load.

Small signal/low signal relays

Usually use a coil voltage ranging from 5VDC to 24VDC, drawing about 20mA. Maximum switching current for noninductive loads ranges from 1A to 3A.

Industrial/general purpose relays

A very wide range of possible values, with coil voltages ranging up to 48VDC or 125VAC to 250VAC. Contact rating is typically 5A to 30A.

Automotive relays

Coil voltage of 12VDC, and contact rating often 5A at up to 24VDC.

Timer relays

Usually these specify a coil voltage of 12VDC, 24VDC, 24VAC, 125VAC, or 230VAC. The timed interval can range from 0.1 sec to 9999 hours in some cases. Common values for contact ratings are 5A up to 20A, with a voltage of 125V to 250V, AC or DC.

How to Use it

Relays are found in home appliances such as dishwashers, washing machines, refrigerators, air conditioners, photocopy machines, and other products where a substantial load (such as a motor or compressor) has to be switched on and off by a control switch, a thermostat, or an electronic circuit.

Figure 9-12 shows a common small-scale application in which a signal from a microcontroller (a few mA at 5VDC) is applied to the base of a transistor, which controls the relay. In this way, a logic output can switch 10A at 125VAC. Note the rectifier diode wired in parallel with the relay coil.



Figure 9-12. *A signal from a digital source such as a microcontroller can switch substantial voltage and current if it is applied to the base of a transistor that activates a relay.*

A latching relay is useful wherever a connection should persist when power is switched off or interrupted, or if power consumption must be minimized. Security devices are one common application. However, the circuit may require a "power reset" function to restore known default settings of latched relays.

A circuit including every possible protection against voltage spikes is shown in Figure 9-13, including a snubber to protect the relay contacts, a rectifier diode to suppress back-EMF generated by the relay coil, and another rectifier diode to protect the relay from EMF generated by a motor when the relay switches it on and off. The snubber can be omitted if the motor draws a relatively low current (below 5A) or if the relay is switching a noninductive load. The diode around the relay coil can be omitted if there are no semiconductors or other components in the circuit that are vulnerable to voltage spikes. However, a spike can affect components in adjacent circuits that appear to be electrically isolated. A severe spike can even be transmitted back into 125VAC house wiring. For information on using a resistor-capacitor combination to form a snubber, see "Snubber" (page 108).



Figure 9-13. *This hypothetical schematic shows three types of protection against voltage spikes induced by an inductive load (a motor, in this instance) and the coil of the relay.*

What Can Go Wrong

Wrong Pinouts

The lack of standardization of relay pinouts can cause errors if one relay is replaced with another that appears to be the same, but isn't. In particular, the pins that connect with normally-closed contacts may trade places with pins connected with normally-open contacts, in relays from different manufacturers.

Pinouts are also confusing in that some datasheets depict them from above, some from below, and some from both perspectives.

Wrong Orientation

Small relays of through-hole type usually have pins spaced in multiples of 0.1". This allows them to be inserted the wrong way around in a perforated board. Almost all relays have an identification mark molded into one end or one corner of the plastic shell. Manufacturers do not standardize the position and meaning of these marks, but they are usually replicated in datasheets. When using a relay of a type that you have not used before, it is a sensible precaution to test it with a meter to verify the functions of its terminals before installing it.

Wrong Type

A latching relay may have exactly the same appearance as a nonlatching relay from the same manufacturer, and the same two pins may energize the coil. However, in a latching relay, the contacts won't spring back to their nonenergized position, causing functional errors that may be difficult to diagnose. The part numbers printed on latching and nonlatching versions of the same relay may differ by only one letter or numeral and should be checked carefully.

Wrong Polarity

A relay with a DC-energized coil may require power to be applied with correct polarity and may malfunction otherwise.

AC and DC

A relay coil designed to be powered by DC will not work from AC and vice-versa. The contact rating of a relay is likely to be different depending whether it is switching AC or DC.

Chatter

This is the noise created by relay contacts when they make rapid intermittent connection. Chatter is potentially damaging to relay contacts and should be avoided. It can also create electrical noise that interferes with other components. Likely correctible causes of chatter include insufficient voltage or power fluctuations.

Relay Coil Voltage Spike

A relay coil is an inductive device. Merely switching a large relay on and off can create voltage spikes. To address this problem, a rectifier diode should be placed across the coil terminals with polarity opposing the energizing voltage.

Arcing

This problem is discussed in the **switch** entry of this encyclopedia. See "Arcing" (page 47). Note that because the contacts inside a *reed relay* are so tiny, they are especially susceptible to arcing and may actually melt and weld themselves together if they are used to control excessive current or an inductive load.

Magnetic Fields

Relays generate magnetic fields during operation and should not be placed near components that are susceptible.

The reed switch inside a reed relay can be unexpectedly activated by an external magnetic field. This type of relay may be enclosed in a metal shell to provide some protection. The adequacy of this protection should be verified by testing the relay under real-world conditions.

Environmental Hazards

Dirt, oxidation, or moisture on relay contacts is a significant problem. Most relays are sealed and should remain sealed.

Relays are susceptible to vibration, which can affect the contacts and can accelerate wear on moving parts. Severe vibration can even damage a relay permanently. **Solid-state relays** (discussed in Volume 2) should be used in harsh environments.

resistor

10

OTHER RELATED COMPONENTS

- **potentiometer** (See Chapter 11)

What It Does

A resistor is one of the most fundamental components in electronics. Its purpose is to impede a flow of current and impose a voltage reduction. It consists of two wires or conductors attached at opposite ends or sides of a relatively poor electrical conductor, the resistance of which is measured in ohms, universally represented by the Greek omega symbol, Ω.

Schematic symbols that represent a resistor are shown in Figure 10-1 (Left: The traditional schematic symbol. Right: The more recent European equivalent). The US symbol is still sometimes used in European schematics, and the European symbol is sometimes used in US schematics. Letters K or M indicate that the value shown for the resistor is in thousands of ohms or millions of ohms, respectively. Where these letters are used in Europe, and sometimes in the US, they are substituted for a decimal point. Thus, a 4.7K resistor may be identified as 4K7, a 3.3M resistor may be identified as 3M3, and so on. (The numeric value in Figure 10-1 was chosen arbitrarily.)



Figure 10-1. *Resistor symbols. The left one is more common in the United States, while the right one is widely used in Europe. The 4.7K value was chosen arbitrarily.*

A resistor is commonly used for purposes such as limiting the charging rate of a **capacitor**; providing appropriate control voltage to semiconductors such as **bipolar transistors**; protecting **LED**s or other semiconductors from excessive current; adjusting or limiting the frequency response in an audio circuit (in conjunction with other components); pulling up or pulling down the voltage at the input pin of a digital logic chip; or controlling a voltage at a point in a circuit. In this last application, two resistors may be placed in series to create a *voltage divider*.

A **potentiometer** may be used instead of a resistor where variable resistance is required.

Sample resistors of various values are shown in Figure 10-2. From top to bottom, their power dissipation ratings are 3W, 1W, 1/2W, 1/4W, 1/4W, 1/4W, and 1/8W. The accuracy (tolerance) of each resistor, from top to bottom, is plus-or-minus 5%, 5%, 5%, 1%, 1%, 5%, and 1%. The beige-colored body of a resistor is often an indication that its tolerance is 5%, while a blue-colored body often indicates a tolerance of 1% or 2%. The blue-bodied resistors and the dark brown resistor contain metal-oxide film elements, while the beige-bodied resistors and the green resistor contain carbon film. For more information on resistor values, see the upcoming *Values* section.



Figure 10-2. *A range of typical resistors. See text for details.*

How It Works

In the process of impeding the flow of current and reducing voltage, a resistor absorbs electrical energy, which it must dissipate as heat. In most modern electronic circuits, the heat dissipation is typically a fraction of a watt.

If R is the resistance in ohms, I is the current flowing through the resistor in amperes, and V is the voltage drop imposed by the resistor (the difference in electrical potential between the two contacts that are attached to it), Ohm's law states:

$$V = I / R$$

This is another way of saying that a resistor of 1Ω will allow a current of 1 amp when the potential difference between the ends of the resistor is 1 volt.

If W is the power in watts dissipated by the resistor, in a DC circuit:

$$W = V * I$$

By substitution in Ohm's law, we can express watts in terms of current and resistance:

$$W = I^2 / R$$

We can also express watts in terms of voltage and resistance:

$$W = V^2 * R$$

These alternates may be useful in situations where you do not know the voltage drop or the current, respectively.

Approximately similar relationships exist when using alternating current, although the power will be a more complex function.

Variants

Axial resistors have two leads that emerge from opposite ends of a usually cylindrical body. *Radial resistors* have parallel leads emerging from one side of the body and are unusual.

Precision resistors are generally defined as having a tolerance of no more than plus-or-minus 1%.

General-purpose resistors are less stable, and their value is less precise.

Power resistors are generally defined as dissipating 1 or 2 watts or more, particularly in power supplies or power amplifiers. They are physically larger and may require *heat sinks* or fan cooling.

Wire-wound resistors are used where the component must withstand substantial heat. A wire-wound resistor often consists of an insulating tube or core that is flat or cylindrical, with multiple turns of resistive wire wrapped around it. The wire is usually a nickel-chromium alloy known as *nichrome* (sometimes written as *Ni-chrome*) and is dipped in a protecting coating.

The heat created by current passing through resistive wire is a potential problem in electronic circuits where temperature must be limited. However, in household appliances such as hair dryers, toaster ovens, and fan heaters, a nichrome element is used specifically to generate heat. Wire-wound resistors are also used in 3D printers to melt plastic (or some other compound) that forms the solid output of the device.

Thick film resistors are sometimes manufactured in a flat, square format. A sample is shown in Figure 10-3, rated to dissipate 10W from its flat surface. The resistance of this component is 1K.



Figure 10-3. *A thick-film resistor measuring about 1" square and 0.03" thick.*

Surface-mount resistors generally consist of a resistive ink film printed on top of a tablet of aluminum oxide ceramic compound, often approximately 6mm long, known as a 2512 form factor. Each surface-mount resistor has two nickel-plated terminations coated in solder, which melts when the resistor is attached to the circuit board. The upper surface is coated, usually with black epoxy, to protect the resistive element.

Resistor Array

This is also known as a *resistor network* or *resistor ladder*, and consists of a chip containing multiple equal-valued resistors.

A resistor array in a *single-inline package* (or *SIP*) may have three possible internal configurations: isolated, common bus, and dual terminator. These options are shown at top, center, and bottom, respectively, in Figure 10-4. The isolated variant is commonly available in SIPs with 6, 8, or 10 pins. The common-bus and dual-terminator configurations generally have 8, 9, 10, or 11 pins.

In the isolated configuration, each resistor is electrically independent of the others and is accessed via its own pair of pins. On a common bus, one end of each resistor shares a bus accessed by a single pin, while the other ends of the resistors are accessed by their own separate pins. A dual-terminator configuration is more complex, consisting of pairs of resistors connected between ground and an internal bus, with the midpoint of each resistor pair accessible via a separate pin. The resistor pairs this function as voltage dividers and are commonly used in emitter-coupled logic circuits that require termination with -2 volts.

A *dual-inline package* (*DIP*) allows a similar range of internal configurations, as shown in Figure 10-5. At top, isolated resistors are commonly available in DIPs with 4, 7, 8, 9, or 10 pins. At center, the common bus configuration is available in DIPs with 8, 14, 16, 18, or 20 pins. At bottom, the dual-terminator configuration usually has 8, 14, 16, 18, or 20 pins.

The external appearance of SIP and DIP resistor arrays is shown in Figure 10-6. From left to right, the packages contain seven 120Ω resistors in



Figure 10-4. *Multiple resistors can be embedded in a single-inline package (SIP) in a variety of formats. See text for additional details.*

isolated configuration; thirteen 120Ω resistors in bussed configuration; seven 5.6K resistors in bussed configuration; and six 1K resistors in bussed configuration.

Resistor arrays with isolated or common-bus configurations are a convenient way to reduce the component count in circuits where pullup, pulldown, or terminating resistors are required for multiple chips. The common-bus configuration is also useful in conjunction with a 7-segment **LED display**, where each segment must be terminated by a series resistor and all the resistors share a common ground or common voltage source.



Figure 10-5. *Multiple resistors can be obtained embedded in a dual-inline package (DIP). See text for additional details.*

Surface-mount chips are available containing a pair of resistors configured as a single voltage divider.

Chips containing multiple *RC circuits* (each consisting of a capacitor and a resistor in series) are available, although uncommon. A package containing a single RC circuit may be sold as a



Figure 10-6. *Resistor arrays in DIP and SIP packages. See text for values.*

snubber to protect contacts in a **switch** or **relay** that switches a large inductive load. More information on snubber circuits is in the **capacitor** entry of this encyclopedia; see "Snubber" (page 108).

Values

1 *kilohm,* usually written as 1K, is 1,000Ω. 1 *megohm,* usually written as 1M or 1 meg, is 1,000K. 1 *gigaohm* is 1,000 megs, although the unit is rarely used. Resistances of less than 1Ω are uncommon and are usually expressed as a decimal number followed by the Ω symbol. The term *milliohms* (thousandths of an ohm) is used in special applications. Equivalent resistor values are shown in Figure 10-7.

A resistance value remains unchanged in DC and AC circuits, except where the AC reaches an extremely high frequency.

In common electronics applications, resistances usually range from 100Ω to 10M. Power ratings may vary from 1/16 watt to 1000 watts, but usually range from 1/8 watt to 1/2 watt in most electronic circuits (less in surface-mount applications).

Ohms	Kilohms	Megohms
1	0.001	0.000001
10	0.01	0.00001
100	0.1	0.0001
1,000	1	0.001
10,000	10	0.01
100,000	100	0.1
1,000,000	1,000	1

Figure 10-7. *Equivalent values in ohms, kilohms, and megohms.*

Tolerance

The tolerance, or precision, of a resistor may range from plus-or-minus 0.001% up to plus-or-minus 20%, but is most commonly plus-or-minus 1%, 2%, 5%, or 10%.

The traditional range of resistor values was established when a tolerance of 20% was the norm. The values were spaced to allow minimum risk of a resistor at one end of its tolerance range having the same value as another resistor at the opposite end of its tolerance range. The values were rounded to 10, 15, 22, 33, 47, 68, and 100, as illustrated in Figure 10-8 where each blue diamond represents the possible range of actual values of a 20% resistor with a theoretical value shown by the white horizontal line at the center of the diamond.

Resistor factors repeat themselves in multiples of 10. Thus, for example, beginning with a resistor of 100Ω, subsequent increasing values will be 150, 220, 330, 470, 680, and 1K, whereas the range of resistors beginning with 1Ω will be 1.5, 2.2, 3.3, 4.7, 6.8, and 10Ω.

Resistance multiplication factors are now expressed as a list of preferred values by the International Electrotechnical Commission (IEC) in their 60063 standard. Intermediate factors have been added to the basic sequence to



Figure 10-8. *Graphical representation of standard resistor values (white lines) established by the International Electrotechnical Commission, showing the acceptable range of actual values (dark blue areas) assuming precision of plus-or-minus 20%. The overlap, if any, between each range and the next is shown in black.*

accommodate better tolerances. A table showing resistor values for tolerances of plus-or-minus 20%, 10%, and 5% appears in Figure 10-9. Resistors with a tolerance of 5% have become increasingly common.

	Resistor Tolerances (plus or minus)		
	20%	10%	5%
Standard Resistor Values	100	100	100
			91
		82	82
			75
	68	68	68
			62
		56	56
			51
	47	47	47
			43
		39	39
			36
	33	33	33
			30
		27	27
			24
	22	22	22
			20
		18	18
			16
	15	15	15
			13
		12	12
			11
	10	10	10

Figure 10-9. *Standard values for resistors of different precisions. For resistors outside the range shown, values can be found by multiplying or dividing (repeatedly, if necessary) by a factor of 10.*

The IEC has established 3-digit preferred values for resistors with values accurate to plus-or-minus 0.5%.

Because many capacitors still have a tolerance no better than 20%, their values also conform with the old original set of resistance values, although the units are expressed in farads or fractions of a farad. See the **capacitors** entry in this encyclopedia for additional information.

Value Coding

Through-hole axial resistors are traditionally printed with a sequence of three colored bands to express the value of the component, each of the first two bands representing a digit from 0 through 9, while the third band indicates the decimal multiplier (the number of zeroes, from 0 to 9, which should be appended to the digits). A fourth band of silver or gold indicates 10% or 5% tolerance respectively. No fourth band would indicate 20% tolerance, although this has become very rare.

Many resistors now have five color bands, to enable the representation of intermediate or fractional values. In this scheme, the first three bands have numeric values (using the same color system as before) while the fourth band is the multiplier. A fifth band, at the opposite end of the resistor, indicates its tolerance.

In Figure 10-10 the numeric or multiplier value of each color is shown as a "spectrum" at the top of the figure. The tolerance, or precision of a resistor, expressed as a plus-or-minus percentage, is shown using silver, gold, and various colors, at the bottom of the figure.

Two sample resistors are shown. The upper one has a value of 1K, indicated by the brown and black bands on the left (representing numeral 1 followed by a numeral 0) and the third red band (indicating two additional zeroes). The gold band at right indicates a precision of 5%. The lower one has a value of 1.05K, indicated by the brown, black, and green bands on the left (representing numeral 1 followed by numeral 0 followed by a numeral 5) and the fourth band brown (indicating one additional zero). The brown band at right indicates a precision of 1%.



Figure 10-10. *Color coding of through-hole resistors. See text for details.*

In extremely old equipment, resistors may be coded with the body-tip-dot scheme, in which the body color represents the initial digit, the end color represents the second digit, and a dot represents the multiplier. The numeric identities of the colors is the same as in the current color scheme.

In all modern schemes, the three or four bands that show the resistance value are spaced close together, while a larger gap separates them from the band that shows the tolerance. The resistor value should be read while holding the resistor so that the group of closely-spaced numeric bands is on the left.

Confusingly, some resistors may be found where the first three bands define the value, using the old three-band convention; the fourth band indicates tolerance; and a fifth band at the opposite end of the component indicates reliability. However, this color scheme is uncommon.

Other color-coding conventions may be found in special applications, such as military equipment.

It is common for through-hole carbon-film resistors to have a beige body color, while through-hole metal-film resistors often have a blue body color. However, in relatively rare instances, a blue body color may also indicate a *fusible* resistor (designed to burn out harmlessly like a fuse, if it is overloaded) while a white body may indicate a *non-flammable* resistor. Use caution when replacing these special types.

Some modern resistors may have their values printed on them numerically. Surface-mount resistors also have digits printed on them, but they are a code, not a direct representation of resistance. The last digit indicates the number of zeroes in the resistor value, while the preceding two or three numbers define the value itself. Letter R is used to indicate a decimal point. Thus a 3R3 surface-mount resistor has a value of 3.3Ω, while 330 would indicate 33Ω, and 332 indicates 3,300Ω. A 2152 surface-mount resistor would have a value of 21,500Ω.

A surface-mount resistor with a single zero printed on it is a *zero ohm* component that has the same function as a **jumper** wire. It is used for convenience, as it is easily inserted by automated production-line equipment. It functions merely as a bridge between traces on the circuit board.

When resistor values are printed on paper in schematics, poor reproduction may result in omission of decimal points or introduction of specks that look like decimal points. Europeans have addressed this issue by using the letter as a substitute for a decimal point so that a 5.6K resistor will be shown as 5K6, or a 3.3M resistor will be shown as 3M3. This practice is followed infrequently in the United States.

Stability

This term describes the ability of a resistor to maintain an accurate value despite factors such as temperature, humidity, vibration, load cycling, current, and voltage. The *temperature coefficient* of a resistor (often referred to as T_{cr} or T_c, not to be confused with the time constant of a charging capacitor) is expressed in parts per million change in resistance for each degree centigrade deviation from room temperature (usually assumed to be 25 degrees Centigrade). T_c may be a positive or a negative value.

The *voltage coefficient* of resistance—often expressed as V_c—describes the change of a resistor's value that may occur as a function of changes in voltage. This is usually significant only where the resistive element is carbon-based. If V1 is the rated voltage of the resistor, R1 is its rated resistance at that voltage, V2 is 10% of the rated voltage, and R2 is the actual resistance at that voltage, the voltage coefficient, V_c, is given by this formula:

$$V_c = (100 * (R1 - R2)) / (R2 * (V1 - V2))$$

Materials

Resistors are formed from a variety of materials.

Carbon composite. Particles of carbon are mixed with a binder. The density of the carbon determines the end-to-end resistance, which typically ranges from 5Ω to 10M. The disadvantages of this system are low precision (a 10% tolerance is common), relatively high voltage coefficient of resistance, and introduction of noise in sensitive circuits. However, carbon-composite resistors have low inductance and are relatively tolerant of overload conditions.

Carbon film. A cheap and popular type, made by coating a ceramic substrate with a film of carbon compound. They are available in both through-hole and surface-mount formats. The range of resistor values is comparable with carbon-composite types, but the precision is increased, typically to 5%, by cutting a spiral groove in the carbon-compound coating during the manufacturing process. The carbon film suffers the same disadvantages of carbon composite resistors, but to a lesser extent. Carbon film resistors generally should not be substituted for metal film resistors in applications where accuracy is important.

Metal film. A metallic film is deposited on a ceramic substrate, and has generally superior characteristics to carbon-film resistors. During manufacture, a groove may be cut in the metal film to adjust the end-to-end resistance. This may cause the resistor to have higher inductance than carbon-composite types, though it has lower noise. Tolerances of 5%, 2%, and 1% are available. This type of resistor was originally more expensive than carbon-film equivalents, but the difference is now fractional. They are available in both through-hole and surface-mount formats. They are available in lower-wattage variants (1/8 watt is common).

Thick-film resistors are spray-coated, whereas thin-film resistors are sputtered nichrome. Thin-films enjoy a flatter temperature coefficient and are typically used in environments that have a huge operational temperature range, such as satellites.

Bulk metal foil. The type of foil used in metal film resistors is applied to a ceramic wafer and etched to achieve the desired overall resistance. Typically these resistors have axial leads. They can be extremely accurate and stable, but have a limited maximum resistance.

Precision wire-wound. Formerly used in applications requiring great accuracy, but now largely replaced by precision metal foil.

Power wire-wound. Generally used when 1 or 2 watts or more power dissipation is required. Resistive wire is wrapped around a core that is often ceramic. This can cause the resistor to be referred to, inaccurately, as "ceramic." The core may alternatively be fiberglass or some other electrically insulating compound that actively sinks heat. The component is either dipped (typically in vitreous enamel or cement) or is mounted in an aluminum shell that can be clamped to a heat sink. It almost always has the ohm value printed on it in plain numerals (not codes).

Two typical wire-wound resistors are shown in Figure 10-11. The upper resistor is rated at 12W and 180Ω while the lower resistor is rated at 13W and 15K.



Figure 10-11. *Two wire-wound resistors of greatly differing resistance but similar power dissipation capability.*

A larger wire-wound resistor is shown in Figure 10-12, rated for 25W and 10Ω.



Figure 10-12. *A large wirewound resistor rated to dissipate 25W.*

In Figure 10-13, two resistors encapsulated in cement coatings are shown with the coatings removed to expose the elements. At left is a 1.5Ω 5W resistor, which uses a wire-wound element. At right is a very low-value 0.03Ω 10W resistor.



Figure 10-13. *Two low-value resistors with their cement coatings removed to show the resistive elements.*

In Figure 10-14, the resistor at right has an exposed 30Ω element while the resistor at left is rated 10W and 6.5Ω, enclosed in an anodized aluminum shell to promote heat dissipation.



Figure 10-14. *A 30Ω resistor (right) and 6.5Ω resistor (left).*

In power resistors, heat dissipation becomes an important consideration. If other factors (such as voltage) remain the same, a lower-value resistor will tend to pass more current than a higher-value resistor, and heat dissipation is proportional to the square of the current. Therefore power wire-wound resistors are more likely to be needed where low resistance values are required. Their coiled-wire format creates significant inductance, making them unsuitable to pass high frequencies or pulses.

How to Use it

Some of the most common applications for a resistor are listed here.

In Series with LED

To protect an LED from damage caused by excessive current, a *series resistor* is chosen to allow a current that does not exceed the manufacturer's specification. In the case of a single through-hole LED (often referred to as an *indicator*), the forward current is often limited to around 20mA, and the value of the resistor will depend on the voltage being used. (See Figure 10-15.)

When using high-output LEDs (which may contain multiple elements in a single 5mm or 10mm package), or LED arrays that are now being used for domestic lighting, the acceptable current may be much greater, and the LED unit may contain its own current-limiting electronics. A datasheet should be consulted for details.



Figure 10-15. *A series resistor is necessary to limit the current that passes through an LED.*

Current Limiting with a Transistor

In Figure 10-16, a transistor is switching or amplifying current flowing from B to C. A resistor is used to protect the base of the transistor from excessive current flowing from point A. Resistors are also commonly used to prevent excessive current from flowing between B and C.



Figure 10-16. *A resistor is typically necessary to protect the base of a transistor from excessive current.*

Pullup and Pulldown Resistors

When a mechanical switch or pushbutton is attached to the input of a logic chip or **microcontroller**, a *pullup* or *pulldown* resistor is used, applying positive voltage or grounding the pin, respectively, to prevent it from "floating" in an indeterminate state when the switch is open. In Figure 10-17, the upper schematic shows a pulldown resistor, whereas the lower schematic shows a pullup resistor. A common value for either of them is 10K. When the pushbutton is pressed, its direct connection to positive voltage or to ground easily overwhelms the effect of the resistor. The choice of pullup or pulldown resistor may depend on the type of chip being used.

Audio Tone Control

A resistor-capacitor combination can limit the high-frequency in a simple audio tone-control circuit, as shown in Figure 10-18. Beneath a signal travelling from A to B, a resistor is placed in series with a capacitor that passes high frequencies to ground. This is known as a low-pass filter.

RC Network

A resistor will adjust the charge/discharge time when placed in series with a capacitor, as in Figure 10-19. When the switch closes, the resistor limits the rate at which the capacitor will charge itself from the power supply. Because a capacitor has an ideally infinite resistance to DC current, the voltage measured at point A will rise until it



Figure 10-17. *A pulldown resistor (top) or pullup resistor (bottom) prevents an input pin on a logic chip or microcontroller from "floating" in an indeterminate state when the button is not being pressed.*



Figure 10-18. *This configuration may be used to remove high frequencies from an audio signal. It is known as a low-pass filter because low frequencies are passed from A to B.*

is close to the supply voltage. This is often referred to as an *RC* (*resistor-capacitor*) network and is discussed in greater detail in the **capacitor** section of this encyclopedia.



Figure 10-19. *In an RC (resistor-capacitor) network, a resistor limits the rate of increase in potential of the capacitor, measured at A, when the switch is closed.*

Voltage Divider

Two resistors may be used to create a voltage divider (see Figure 10-20). If V_{in} is the supply voltage, the output voltage, V_{out}, measured at point A, is found by the formula:

$$V_{out} = V_{in} * (R2 / (R1 + R2))$$

In reality, the actual value of V_{out} is likely to be affected by how heavily the output is loaded.

If the output node has a high impedance, such as the input to a logic chip or comparator, it will be more susceptible to electrical noise, and lower-value resistors may be needed in the voltage divider to maintain a higher current flow and maintain stability in the attached device.

Resistors in Series

If resistors in series have values R1, R2, R3 . . . the total resistance, R, is found by summing the individual resistances:



Figure 10-20. *In a DC circuit, a pair of resistors may be placed in series to function as a voltage divider. The voltage measured at A will be lower than the supply voltage, but above ground potential.*

$$R = R1 + R2 + R3. . .$$

The current through each of the resistors will be the same, whereas the voltage across each of them will vary proportionately with its resistance. If the supply voltage across the series of resistors is VS, and the total of all the resistor values is RT, and the resistance of one resistor is R1, the voltage across that resistor, V1, will be given by the formula:

$$V1 = VS * (R1 / RT)$$

Resistors in Parallel

Where two or more resistors (R1, R2, R3 . . .) are wired in parallel, their total resistance, R, is found from the formula:

$$1/R = (1/R1) + (1/R2) + (1/R3). . .$$

Suppose that R1, R2, R3 . . . all have the same individual resistance, represented by RI, and the number of resistors is N. Their total resistance, RT, when wired in parallel, will be:

$$RT = RI / N$$

If each resistor has an equal resistance and also has an equal individual rating in watts (represented by WI), the total wattage (WT) that they can handle when wired in parallel to share the power will be:

```
WT = WI * N
```

Therefore, if an application requires high-wattage resistors, multiple lower-wattage, higher-value resistors may be substituted if they are wired in parallel—and may even be cheaper than a single high-wattage wire-wound resistor. For example, if a 5W, 50Ω resistor is specified, 10 resistors can be substituted, each rated at 0.5W and 500Ω. Bear in mind that if they are tightly bundled, this will interfere with heat dissipation.

What Can Go Wrong

Heat

Resistors are probably the most robust of all electronic components, with high reliability and a long life. It is difficult to damage a resistor by overheating it with a soldering iron.

The wattage rating of a resistor does not necessarily mean that it should be used to dissipate that amount of power on a constant basis. Small resistors (1/4 watt or less) can overheat just as easily as big ones. Generally speaking, it is safe practice not to exceed 75% of a resistor's power rating on a constant basis.

Overheating is predictably more of a problem for power resistors, where provision must be made for heat dissipation. Issues such as component crowding should be considered when deciding how big a heat sink to use and how much ventilation. Some power resistors may function reliably at temperatures as high as 250 degrees Centigrade, but components near them are likely to be less tolerant and plastic enclosures may soften or melt.

Noise

The electrical *noise* introduced by a resistor in a circuit will vary according to the composition of the resistor, but for any given component, it will be proportional to voltage and current. Low-noise circuits (such as those at the input stage of a high-gain amplifier) should use low-wattage resistors at a low voltage where possible.

Inductance

The coiled wire of a wire-wound resistor will be significantly inductive at low frequencies. This is known as *parasitic inductance*. It will also have a resonant frequency. This type of resistor is unsuitable for applications where frequency exceeds 50KHz.

Inaccuracy

When using resistors with 10% tolerance, imprecise values may cause greater problems in some applications than in others. In a voltage divider, for instance, if one resistor happens to be at the high end of its tolerance range while the other happens to be at the low end, the voltage obtained at the intersection of the resistors will vary from its expected value. Using the schematic shown in Figure 10-20, if R1 is rated for 1K and R2 is rated for 5K, and the power supply is rated at 12VDC, the voltage at point A should be:

```
V = 12 * (( 5 / (5 + 1)) = 10
```

However, if R1 has an actual value of 1.1K and R2 has an actual value of 4.5K, the actual voltage obtained at point A will be:

```
V = 12 * (( 4.5 / (4.5 + 1.1)) = 9.6
```

If the resistors are at opposite ends of their respective tolerance ranges, so that R1 has an actual value of 900Ω while the lower resistor has an actual value of 5.5K, the actual voltage obtained will be:

```
V = 12 * (( 5.5 / (5.5 + 0.9)) = 10.3
```

The situation becomes worse if the two resistors are chosen to be of equal value, to provide half of the supply voltage (6 volts, in this example) at their intersection. If two 5K resistors are used, and the upper one is actually 4.5K while the lower one is 5.5K, the actual voltage will be:

```
V = 12 * (( 5.5 / (4.5 + 5.5)) = 6.6
```

Whether this variation is significant will depend on the particular circuit in which the voltage divider is being used.

Common through-hole resistors may occasionally turn out to have values that are outside their specified tolerance range, as a result of poor manufacturing processes. Checking each resistor with a meter before placing it in a circuit should be a standard procedure.

When measuring the voltage drop introduced by a resistor in an active circuit, the meter has its own internal resistance that will take a proportion of the current. This is known as *meter loading* and will result in an artificially low reading for the potential difference between the ends of a resistor. This problem becomes significant only when dealing with resistors that have a high value (such as 1M), comparable with the internal resistance of the meter (likely to be 10M or more).

Wrong Values

When resistors are sorted into small bins by the user, errors may be made, and different values may be mixed together. This is another reason for checking the values of components before using them. Identification errors may be nontrivial and easily overlooked: the visible difference between a 1 megohm resistor and a 100Ω resistor is just one thin color band.

potentiometer

11

Also known as a *variable resistor*; may be substituted for a *rheostat*.

OTHER RELATED COMPONENTS

- **rotational encoder** (see Chapter 8)
- **resistor** (see Chapter 10)

What It Does

When a voltage is applied across a potentiometer, it can deliver a variable fraction of that voltage. It is often used to adjust sensitivity, balance, input, or output, especially in audio equipment and sensors such as motion detectors.

A potentiometer can also be used to insert a variable resistance in a circuit, in which case it should really be referred to as a *variable resistor,* although most people will still call it a potentiometer.

It can be used to adjust the power supplied to a circuit, in which case it is properly known as a *rheostat*, although this term is becoming obsolete. Massive rheostats were once used for purposes such as dimming theatrical lighting, but solid-state components have taken their place in most high-wattage applications.

A full-size, classic-style potentiometer is shown in Figure 11-1.



Figure 11-1. *A generic or classic-style potentiometer, approximately one inch in diameter.*

Schematic symbols for a potentiometer and other associated components are shown in Figure 11-2, with American versions on the left and European versions on the right in each case. The symbols for a potentiometer are at the top. The correct symbols for a variable resistor or rheostat are shown at center, although a potentiometer symbol may often be used instead. A preset variable resistor is shown at the bottom, often referred to as a *trimmer* or *Trimpot*. In these examples, each has an arbitrary rated resistance of 4,700Ω. Note the European substitution of K for a decimal point.



Figure 11-2. *American (left) and European (right) symbols for a potentiometer, a rheostat, and a trimmer potentiometer, reading from top to bottom. The 4.7K value was chosen arbitrarily.*

How It Works

A potentiometer has three terminals. The outer pair connect with the opposite ends of an internal resistive element, such as a strip of conductive plastic, sometimes known as the *track*. The third center terminal connects internally with a contact known as the *wiper* (or rarely, the *pick-off*), which touches the strip and can be moved from one end of it to the other by turning a shaft or screw, or by moving a slider.

If an electrical potential is applied between opposite ends of the resistive element, the voltage "picked off" by the wiper will vary as it moves. In this mode, the potentiometer works as a resistive voltage divider. For example, in a potentiometer with a linear taper (see "Variants," coming up), if you attach the negative side of a 12V battery to the right-hand end terminal and the positive side to the left-hand end terminal, you will find an 8V potential at the center terminal when the potentiometer has rotated clockwise through one-third of its range. In Figure 11-3, the base of the shaft (shown in black) is attached to an arm (shown in green) that moves a wiper (orange) along a resistive element (brown). The voltages shown assume that the resistive element has a linear taper and will vary slightly depending on wire resistance and other factors.

Because a potentiometer imposes a voltage reduction, it also reduces current flowing through it, and therefore creates waste heat which must be dissipated. In an application such as an audio circuit, small currents and low voltages generate negligible heat. If a potentiometer is used for heavier applications, it must be appropriately rated to handle the wattage and must be vented to allow heat to disperse.

To use a potentiometer as a *variable resistor* or *rheostat*, one of its end terminals may be tied to the center terminal. If the unused end terminal is left unconnected, this raises the risk of picking up stray voltages or "noise" in sensitive circuits. In Figure 11-4, a potentiometer is shown adjusting a series resistance for an *LED* for demonstration purposes. More typically, a trimmer would be used in this kind of application, since a user is unlikely to need to reset it.

Variants

Linear and Log Taper

If the resistive element in a potentiometer is of constant width and thickness, the electrical potential at the wiper will change in ratio with the rotation of the wiper and shaft (or with movement of a slider). This type of potentiometer is said to have a linear taper even though its element does not actually taper.

For audio applications, because human hearing responds nonlinearly to sound pressure, a potentiometer that has a linear taper may seem to have a very slow action at one end of its scale and an abrupt effect at the other. This problem used to be solved with a non-uniform or tapered re-



Figure 11-3. *Inside a potentiometer. See text for details.*



Figure 11-4. *A potentiometer can be used to adjust a series resistance, as shown in this schematic. Tying the wiper to one of the end terminals reduces the risk of picking up electrical noise.*

sistive element. More recently, a combination of resistive elements has been used as a cheaper option. Such a potentiometer is said to have an audio taper or a log taper (since the resistance may vary as a logarithm of the angle of rotation). A reverse audio taper or antilog taper varies in the opposite direction, but this type has become very uncommon.

Classic-style Potentiometer

This consists of a sealed circular can, usually between 0.5″ and 1″ in diameter, containing a resistive strip that is shaped as a segment of a circle. A typical example is shown in Figure 11-1, although miniaturized versions have become more common. A shaft mounted on the can turns the internal wiper that presses against the strip. For panel-mount applications, a threaded bushing at the base of the shaft is inserted through a hole in the front panel of the electronics enclosure, and a nut is tightened on the bushing to hold the potentiometer in place. Often there is also a small offset index pin that, when paired with a corresponding front panel hole, will keep the pot from spinning freely.

Many modern potentiometers are miniaturized, and may be packaged in a box-shaped plastic enclosure rather than a circular can. Their power ratings are likely to be lower, but their principle of operation is unchanged. Two variants are shown in Figure 11-5.



Figure 11-5. *Two modern miniaturized potentiometers. At left: 5K. At right: 10K. Both are rated to dissipate up to 50mW.*

The three terminals on the outside of a potentiometer may be solder lugs, screw terminals, or pins for direct mounting on a circuit board. The pins may be straight or angled at 90 degrees.

The resistive element may use carbon film, plastic, cermet (a ceramic-metal mixture), or resistive wire wound around an insulator. Carbon-film potentiometers are generally the cheapest, whereas wire-wound potentiometers are generally the most expensive.

Wire-wound potentiometers may handle more power than the other variants, but as the wiper makes a transition from one turn of the internal wire element to the next, the output will tend to change in discrete steps instead of varying more smoothly.

In a potentiometer with detents, typically a spring-loaded lever in contact with notched internal wheel causes the shaft to turn in discrete steps that create a stepped output even if the resistive element is continuous.

The shaft may be made of metal or plastic, with its length and width varying from one component to another. A control knob can be fitted to the end of the shaft. Some control knobs are push-on, others have a set screw to secure them. Shafts may be splined and split, or round and smooth, or round with a flat surface that matches the shape of a socket in a control knob and reduces the risk of a knob becoming loose and turning freely. Some shafts have a slotted tip to enable screwdriver adjustment.

Some shaft options for full-size potentiometers are shown in Figure 11-6.



Figure 11-6. *Three shaft options for potentiometers.*

Multiple-Turn Potentiometer

To achieve greater precision, a track inside a potentiometer may be manufactured in the form of a helix, allowing the wiper to make multiple turns on its journey from one end of the track to the other. Such multiple-turn potentiometers typically allow 3, 5, or 10 turns to move the wiper from end to end. Other multiple-turn potentiometers may use a screw thread that advances a wiper along a linear or circular track. The latter is comparable with a trimmer where multiple turns of a screwdriver are used to rotate a worm gear that rotates a wiper between opposite ends of a circular track.

Ganged Potentiometer

Two (or rarely, more) potentiometers can be stacked or combined so that their resistive elements and wipers share the same shaft but can use different voltages or have different taper. Each resistance-wiper assembly is known as a *cup*, and the potentiometers are said to be *ganged*.

Flat ganged potentiometers combine two resistive elements in one enclosure. Some *dual ganged* potentiometers are concentric, meaning that the pots are controlled separately by two shafts, one inside the other. Suitable concentric knobs must be used. You are unlikely to find these potentiometers sold as components in limited quantities.

Switched Potentiometer

In this variant, when the shaft is turned clockwise from an initial position that is fully counterclockwise, it flips an internal switch connected to external terminals. This can be used to power-up associated components (for example, an audio amplifier). Alternatively, a switch inside a potentiometer may be configured so that it is activated by pulling or pushing the shaft.

Slider Potentiometer

Also known as a *slide potentiometer*. This uses a straight resistive strip and a wiper that is moved to and fro linearly by a tab or lug fitted with a plastic knob or finger-grip. Sliders are still found on some audio equipment. The principle of operation, and the number of terminals, are identical to the classic-style potentiometer. Sliders typically have solder tabs or PC pins. In Figure 11-7, the large one is about 3.5" long, designed for mounting behind a panel that has a slot to allow the sliding lug to poke through. Threaded holes at either end will accept screws to fix the slider behind the panel. A removable plastic finger-grip (sold separately, in a variety of styles) has been pushed into place. Solder tabs underneath the slider are hidden in this photo. The smaller slider is designed for through-hole mounting on a circuit board.



Figure 11-7. *Slider potentiometers.*

Trimmer Potentiometer

Often referred to as Trimpots, this is actually a proprietary brand name of Bourns. They are usually mounted directly on circuit boards to allow fine adjustment or trimming during manufacturing and testing to compensate for variations in other components. Trimmers may be single-turn or multi-turn, the latter containing a worm gear that engages with another gear to which the wiper is attached. Trimmers always have linear taper. They may be designed for screwdriver adjustment or may have a small knurled shaft, a thumb wheel, or a knob. They are not usually accessible by the end user of the equipment, and their setting may be sealed or fixed when the equipment is assembled. In Figure 11-8, the beige Spectrol trimmer is a single-turn design, whereas the blue trimmer is multi-turn. A worm gear inside the package, beneath the screw head, engages with an interior gear wheel that rotates the wiper.

In Figure 11-9, a 2K trimmer potentiometer has a knurled dial attached to allow easy finger adjustment, although the dial also contains a slot for a flat-blade screwdriver.



Figure 11-8. *Like most trimmers, these are designed for through-hole mounting on a circuit board.*



Figure 11-9. *A trimmer potentiometer with a knurled dial to facilitate finger adjustment.*

How to Use it

The classic-style potentiometer was once used universally to control volume, bass, and treble on audio equipment but has been replaced increasingly by digital input devices such as **tactile switches** (see "Tactile Switch" (page 34)) or **rotational encoders** (see Chapter 8), which are more reliable and may be cheaper, especially when assembly costs are considered.

Potentiometers are widely used in lamp dimmers and on cooking stoves (see Figure 11-10). In these applications, a solid-state switching device such as a **triac** (described in Volume 2) does the actual work of moderating the power to the lamp or the stove by interrupting it very rapidly. The potentiometer adjusts the duty cycle of the power interruptions. This system wastes far less power than if the potentiometer controlled the lighting or heating element directly as a rheostat. Since less power is involved, the potentiometer can be small and cheap, and will not generate significant heat.



Figure 11-10. *Typical usage of a potentiometer in conjunction with a diac, triac, and capacitor to control the brightness of an incandescent bulb, using an AC power supply. Diacs and triacs are discussed in Volume 2.*

Because true logarithmic potentiometers have become decreasingly common, a linear potentiometer in conjunction with a fixed resistor can be used as a substitute, to control audio input. See Figure 11-11.



Figure 11-11. *In this circuit, a 100K linear potentiometer is used in conjunction with a 22K resistor to create an approximately logarithmic volume control for an audio system with input coming from a mono jack socket at left.*

A potentiometer may be used to match a sensor or analog input device to an analog-digital converter, or it can calibrate a device such as a temperature or motion sensor.

What Can Go Wrong

Wear and Tear

Since classic-style potentiometers are electromechanical devices, their performance will deteriorate as one part rubs against another. The long open slot of a slider potentiometer makes it especially vulnerable to contamination with dirt, water, or grease. Contact-cleaner solvent, lubricant-carrying sprays, or pressurized "duster" gas may be squirted into a potentiometer to try to extend its life. Carbon-film potentiometers are the least durable and in audio applications will eventually create a "scratchy" sound when they are turned, as the resistive element deteriorates.

If the wiper deteriorates to the point where it no longer makes electrical contact with the track, and if the potentiometer is being used as a variable resistor, two failure modes are possible, shown in Figure 11-12. Clearly the right-hand schematic is a better outcome. This is an argument for always tying the wiper to the "unused" end of the track.



Figure 11-12. *If the wiper of a potentiometer breaks (indicated by the loose arrow head) as a result of wear and tear, and the potentiometer is being used as a variable resistor, the voltage from it will drop to zero (top schematic) unless the wiper has been tied to one end of the track (bottom schematic).*

If you are designing a circuit board that will go through a production process, temperature variations during wave soldering, and subsequent washing to remove flux residues, create hostile conditions for potentiometers, especially sliders where the internal parts are easily contaminated. It will be safer to hand-mount potentiometers after the automated process.

Knobs that Don't Fit

Control knobs are almost always sold separately from potentiometers. Make sure the shaft of the potentiometer (which may be round, round-with-flat, or knurled) matches the knob of your choice. Note that some shaft diameters are expressed in inches, while others are metric.

Nuts that Get Lost

For panel-mounted potentiometers, a nut that fits the thread on the bushing is almost always included with the potentiometer; an additional nut and lock washer may also be supplied. Because there is no standardization of threads on potentiometers, if you lose a nut, you may have some difficulty finding an exact replacement.

A Shaft that Isn't Long Enough

When choosing a shaft length, if in doubt, buy a potentiometer with a long shaft that you can cut to the desired length.

Sliders with No Finger Grip

Slider potentiometers are often sold without a knob or plastic finger-grip, which must be ordered separately and may be available in different styles. The finger-grip usually push-fits onto the metal or plastic tab or lug that moves the slider to and fro.

Too Big to Fit

Check the manufacturer's datasheet if you need to know the physical size of the potentiometer. Photographs may be misleading, as a traditional-style potentiometer that is 0.5″ in diameter looks much the same as one that is 1″ in diameter. High-wattage potentiometers will be more costly and physically large (2 to 3 inches in diameter). See Figure 11-13.

Overheating

Be sure to leave sufficient air space around a high-wattage potentiometer. Carefully calculate the maximum voltage drop and current that you may be using, and choose a component that is appropriately rated. Note that if you use the potentiometer as a rheostat, it will have to handle more current when its wiper moves to reduce its resistance. For example, if 12VDC are applied through a 10-ohm rheostat to a component that has a resistance of 20 ohms, current in the circuit will vary from 0.4 amps to 0.6 amps depending on the position of the rheostat. At its maximum setting, the rheostat will impose a 4V voltage drop and will therefore dissipate 1.6 watts from the full length of its resistive element. If the rheostat is reset to impose only a 4-ohm resistance, the voltage drop that it imposes will be 2V, the current in the circuit will be 0.5 amps, and the rheostat will therefore dissipate 1 watt from 4/10ths of the length of its resistive element. A wire-wound potentiometer will be better able to handle high dissipation from a short segment of its element than other types of rheostat. Add a fixed resistor in series with a rheostat if necessary to impose a limit on the current.



Figure 11-13. *The large potentiometer is approximately 3″ in diameter, rated at 5 ohms, and able to handle more than 4 amps. The small potentiometer is 5/8″ diameter, rated at 2K and 1/4 watt, with pins designed for through-hole insertion in a circuit board, and a grooved shaft that accepts a push-on knob. Despite the disparity in size, the principle of operation and the basic features are identical.*

When using a trimmer potentiometer, limit the current through the wiper to 100mA as an absolute maximum value.

The Wrong Taper

When buying a potentiometer, remember to check the specification to find out whether it has linear or audio/log taper. If necessary, attach a meter, with the potentiometer set to its center position, to verify which kind of taper you have. While holding the meter probes in place, rotate the potentiometer shaft to determine which way an audio/log taper is oriented.

capacitor

12

Quite often referred to as a *cap*. Formerly known (primarily in the United Kingdom) as a *condenser*, but that term has become obsolete.

OTHER RELATED COMPONENTS

- **variable capacitor** (See Chapter 13)
- **battery** (See Chapter 2)

What It Does

A capacitor connected across a DC power source will accumulate a charge, which then persists after the source is disconnected. In this way, the capacitor stores (and can then discharge) energy like a small rechargeable battery. The charge/discharge rate is extremely fast but can be limited by a series resistor, which enables the capacitor to be used as a timing component in many electronic circuits.

A capacitor can also be used to block DC current while it passes pulses, or electrical "noise," or alternating current, or audio signals, or other wave forms. This capability enables it to smooth the output voltage provided by **power supplies**; to remove spikes from signals that would otherwise tend to cause spurious triggering of components in digital circuits; to adjust the frequency response of an audio circuit; or to couple separate components or circuit elements that must be protected from transmission of DC current.

Schematic symbols for capacitors are shown in Figure 12-1. At top-left is a nonpolarized capacitor, while the other two indicate that a polarized capacitor must be used, and must be oriented as shown. The variant at the bottom is most commonly used in Europe. Confusingly, the nonpolarized symbol may also be used to identify a polarized capacitor, if a + sign is added. The polarized symbols are sometimes printed without + signs, but the symbols still indicate that polarity must be observed.



Figure 12-1. *Schematic symbols for polarized and nonpolarized capacitors. See text for details.*

How It Works

In its simplest form, a capacitor consists of two plates, each with a lead attached to it for connection with a DC power source. The plates are separated by a thin, insulating layer known as the *dielectric*, which is usually a solid or a paste but may be liquid, gel, gaseous, or vacuum.

The plates in most capacitors are made from thin metal film or metallized plastic film. To minimize the size of the component, the film may be rolled up to form a compact cylindrical package, or multiple flat sections may be interleaved.

Electrons from the power source will migrate onto the plate attached to the negative side of the source, and will tend to repel electrons from the other plate. This may be thought of as creating *electron holes* in the other plate or as attracting *positive charges*, as shown in Figure 12-2. When the capacitor is disconnected from the power source, the opposite charges on its plates will persist in equilibrium as a result of their mutual attraction, although the voltage will gradually dissipate as a result of *leakage,* either through the dielectric or via other pathways.



Figure 12-2. *Because the plates of a capacitor are electrically conductive, they will become populated with positive and negative charges when connected with a DC power source. As opposite charges attract each other, they will tend to congregate on either side of the dielectric, which is an insulating layer. The battery symbol is shown here colored for clarity.*

When a **resistor** is placed across the leads of a charged capacitor, the capacitor will discharge itself through the resistor at a rate limited by the resistance. Conversely, if a capacitor is charged through a resistor, the resistor will limit the charging rate.

A resistor in series with a capacitor is known as an *RC network* (Resistor-Capacitor network). In Figure 12-3, an RC circuit is shown with a SPDT switch that charges or discharges the capacitor via a series resistor. The voltage at point A increases nonlinearly (relative to the negative side of the power supply) while the capacitor is charging, and decreases nonlinearly while the capacitor is discharging, as suggested by the graphs. At any moment, the time that the capacitor takes to acquire 63% of the difference between its current charge and the voltage being supplied to it is known as the *time constant* for the circuit. See "The Time Constant" (page 105) for additional information.

When a capacitor is connected across an AC voltage source, each surge of electrons to one plate induces an equal and opposite positive surge to the other plate, and when polarity of the power supply reverses, the charges on the plates switch places. These surges may make it seem that the capacitor is conducting AC current, even though the dielectric that separates the plates is an insulator. See Figure 12-4. Often a capacitor is said to "pass" AC, even though this is not really happening. For convenience, and because the concept is widely established, this encyclopedia refers to capacitors as "passing" AC.

Depending on the size of the capacitor, it will block some AC frequencies while passing others. Generally speaking, a smaller capacitor will pass high frequencies relatively efficiently, as each little surge of current fills each plate. However, the situation is complicated by the *inductive reactance* (which creates the *effective series resistance*) of a capacitor, as discussed below. See "Alternating Current and Capacitive Reactance" (page 106).



Figure 12-3. *An RC (Resistor-Capacitor) network with a switch to control charge and discharge of a capacitor. At top, the curve gives an approximate idea of the charging behavior of the capacitor. At bottom, the curve illustrates its discharging behavior.*

Variants

Format

The three most common packages for capacitors are cylindrical, disc, and rectangular tablet.

A *cylindrical capacitor* may have *axial leads* (a wire attached to each end) or *radial leads* (both wires emerging from one end). Radial capacitors are more widely used as they allow easy insertion into a circuit board. The capacitor is usually packaged in a small aluminum can, closed at one end, capped with an insulating disc at the other end, and wrapped in a thin layer of insulating plastic. Some samples are shown in Figure 12-5 and Figure 12-6.



Figure 12-4. *In the left diagram, a source of alternating current charges the upper plate of a capacitor positively and the lower plate negatively. This process entails a flow of conventional current shown by the arrows. A moment later, when the AC current flow reverses, the flow also reverses, creating the impression that the capacitor "passes" AC current.*



Figure 12-5. *Cylindrical capacitors with radial leads. All are electrolytic.*



Figure 12-6. *Cylindrical capacitors with radial leads (top and bottom) and axial leads (center). All are electrolytic.*

A *disc capacitor* (sometimes referred to as a *button capacitor*) is usually encased in an insulating ceramic compound, and has radial leads. Modern small-value ceramic capacitors are more likely to be dipped in epoxy, or to be square tablets. Some samples are shown in Figure 12-7.



Figure 12-7. *Generic ceramic capacitors. Left: rated for 0.1µF at 50V. Center: 1µF at 50V. Right: 1µF at 50V.*

A *surface-mount capacitor* is square or rectangular, usually a few millimeters in each dimension, with two conductive pads or contacts at opposite ends. It appears almost identical to a surface-mount resistor. Larger-value capacitors are inevitably bigger but can still be designed for surface-mount applications. See Figure 12-8.



Figure 12-8. *Most surface-mount capacitors are as tiny as other surface-mount components, but this 4,700µF electrolytic (at 10V) has a base approximately 0.6" square. A solder tab is visible at the center of the nearest edge.*

Many capacitors are nonpolarized, meaning that they are insensitive to polarity. However, electrolytic and tantalum capacitors must be connected "the right way around" to any DC voltage source. If one lead is longer than the other, it must be the "more positive" lead. A mark or band at one end of the capacitor indicates the "more negative" end. Tantalum capacitors are likely to indicate the positive lead by using a + sign on the body of the component.

An arrow printed on the side of a capacitor usually points to the "more negative" terminal. In an aluminum can with axial leads, the lead at one end will have an insulating disc around it while the other lead will be integral with the rounded end of the can. The wire at the insulated end must be "more positive" than the wire at the other end.

A *capacitor array* contains two or more capacitors that are isolated from each other internally and accessed by external contacts. They are sold in surface-mount format and also in *through-hole* chips of DIP (dual-inline package) or SIP (single-inline package) format. The internal components may be connected in one of three configurations: isolated, common-bus, or dual-ended common bus. Technically the isolated configuration should be referred to as a capacitor array, but in practice, all three configurations are usually referred to as *capacitor networks*. See Figure 12-9 and Figure 12-10.



Figure 12-9. *A capacitor network most often consists of a single-inline package (SIP) chip containing multiple capacitors in one of three configurations shown here. Top: Isolated. Center: Common bus. Bottom: Dual-ended common bus. Individual capacitor values ranging from 0.001μF to 0.1μF are common.*

Capacitor networks can reduce the component count in circuits where digital logic chips require bypass capacitors. They are comparable in concept to *resistor arrays*.



Figure 12-10. *A capacitor array in through-hole, SIP format.*

Chips containing *RC circuits* (multiple resistor-capacitor pairs) are available, although uncommon.

Principal Types

Electrolytic capacitors are relatively cheap, compact, and available in large values. These attributes have made them a popular choice in consumer electronics, especially for power supplies. The capacitive capability of an electrolytic is refreshed by periodic application of voltage. A moist paste inside the capacitor is intended to improve the dielectric performance when voltage is applied, but can dry out during a period of years. If an electrolytic is stored for 10 years or so, it may allow a short circuit between its leads when power is applied to it. The capacitors in Figure 12-5 and Figure 12-6 are all electrolytic. The capacitor in Figure 12-11 is at the high end of the scale.

A *bipolar electrolytic* is a single package containing two electrolytic capacitors in series, end-to-end, with opposed polarities, so that the combination can be used where the voltage of a signal fluctuates above and below 0VDC. See Figure 12-12 and Figure 12-13. This type of component is likely to have “BP” (bipolar) or “NP”



Figure 12-11. *This 13,000µF electrolytic capacitor is larger than would be required in most everyday applications.*

(nonpolarized) printed on its shell. It may be used in audio circuits where polarized capacitors are normally unsuitable, and is likely to be cheaper than non-electrolytic alternatives. However, it suffers from the same weaknesses as all electrolytics.



Figure 12-12. *Schematic view of the internal configuration of a bipolar electrolytic capacitor, also known as nonpolarized electrolytic capacitor. It consists of two electrolytics in series, with opposing polarities.*



Figure 12-13. *Bipolar electrolytic capacitors. The larger size of the one at top-left is a consequence of its higher voltage rating. "BP" on the other two capacitors is an acronym for "bipolar," meaning that they have no polarity, even though one lead may be shorter than the other.*

Tantalum capacitors are compact but relatively expensive, and can be vulnerable to voltage spikes. They are sensitive to application of the wrong polarity. Typically they are epoxy-dipped rather than mounted inside a small aluminum can like electrolytics, and consequently the electrolyte may be less likely to evaporate and dry out. In Figure 12-14, two tantalum capacitors (rated 330µF at 6.3V, left, and 100µF at 20V, right) are shown above a polyester film capacitor (rated 10µF at 100V). Surface-mount tantalum capacitors are decreasing in popularity as large-value ceramic capacitors are becoming available, with smaller dimensions and lower equivalent series resistance.

Plastic-film capacitors are discussed in the following section.

Single-layer *ceramic* capacitors are often used for bypass, and are suitable for high-frequency or audio applications. Their value is not very stable with temperature, although the "NPO" variants are more stable. Multilayer ceramic capacitors are more compact than single-layer ceramic, and



Figure 12-14. *Two tantalum capacitors are shown above a polyester film capacitor. The polarity of the tantalum capacitors is indicated by the plus signs adjacent to the longer lead, in each case. The polyester capacitor is nonpolarized.*

consequently are becoming increasingly popular. Three multilayer ceramic capacitors are shown in Figure 12-15. At bottom-right, even the largest (rated at 47µF at 16V) is only 0.2″ square.



Figure 12-15. *Multilayer ceramic capacitors are extremely compact, and are nonpolarized. Top: 1,000pF (i.e. 1nF) at 100V. Bottom left: 1µF at 25V. Bottom right: 47µF at 16V.*

Dielectrics

The dielectric used in a capacitor most often consists of an electrolytic layer, a ceramic compound, a plastic film (polycarbonate, polypropylene, or polystyrene), or paper.

An *electrolytic layer* in an electrolytic capacitor traditionally consists of paper soaked in an electrolyte. It is interleaved with a thin film of aluminum on which is deposited a layer of aluminum oxide. The layers are rolled up to create a cylindrical component. The functioning dielectric is created when voltage is applied.

Polyester
: This is the most common type of plastic film, with the highest dielectric constant, enabling highest capacitance per unit volume. Widely used in DC applications, but the rolled layers create parasitic inductance. Often used in decoupling, coupling, and bypass, but not so suitable for situations requiring stability and low leakage. May not be suitable for high current.

Polycarbonate
: Thermally very stable, often specified for filters and timing circuits that require a fixed frequency. An excellent type of capacitor, compatible for mil-spec applications, but expensive.

Mylar, Polyester, and other plastic-film types are often used in audio circuits, where their voltage limitation (typically less than 100VDC) is not a problem, and their nonpolarized attribute is an advantage.

Polypropylene
: Vulnerable to heat (a maximum of 85 degrees Centigrade is common), and less thermally stable than polycarbonate. A very low power dissipation factor allows it to handle higher power at higher frequencies. Available with tolerances down to 1%. These capacitors are a popular choice in crossover

networks for loudspeaker combinations, and are used in switching power supplies. They tend to be physically larger than other capacitors using film dielectric.

Values

Farads

The electrical storage capacity of a capacitor is measured in *farads,* universally represented by the letter F. A capacitor that can be charged with a potential difference between its plates of 1 volt, in a time of 1 second, during which it draws 1 amp, has a capacitance of 1 farad.

Because the farad is a large unit, capacitors in electronic circuits almost always have fractional values: *microfarads* (μF), *nanofarads* (nF), and *picofarads* (pF). The Greek letter μ (mu) should be used in the μF abbreviation, but a lowercase letter u is often substituted. Thus, for example, 10uF means the same as 10μF.

1F = 1,000,000μF, and 1μF = 1,000,000pF. Therefore, 1 farad is equivalent to 1 trillion picofarads —a very wide range of possible values. See Figure 12-16 and Figure 12-17 for charts showing equivalent values in different units.

pF	nF	μF
1	0.001	0.000001
10	0.01	0.00001
100	0.1	0.0001
1,000	1	0.001
10,000	10	0.01
100,000	100	0.1
1,000,000	1,000	1

Figure 12-16. *Equivalent values for picofards, nanofarads, and microfarads. The nF unit is used primarily in Europe.*

μF	F
1	0.000001
10	0.00001
100	0.0001
1,000	0.001
10,000	0.01
100,000	0.1
1,000,000	1

Figure 12-17. *Equivalent values for microfarads and farads. Because the farad is such a large unit, electronic circuits almost always use fractional values.*

The nF unit is more common in Europe than in the United States. A 1nF capacitance is often expressed in the US as 0.001μF or 1,000pF. Similarly, a 10nF capacitance is almost always expressed as a 0.01μF, and a 0.1nF capacitance is more likely to be expressed as 100pF.

European schematics may use value-symbols as a substitute for decimal points. For example, a 4.7pF capacitor may be shown as 4p7, a 6.8nF capacitor may be shown as 6n8, and a 3.3μF capacitor may be shown as 3μ3.

Commonly Used Values

The traditional range of capacitor values was established on the same basis as the traditional range of resistor values, by assuming an accuracy of plus-or-minus 20% and choosing factors that would minimize the possible overlap between adjacent tolerance ranges. The factors 1.0, 1.5, 2.2, 3.3, 4.7, 6.8, and 10 satisfy this requirement. See Chapter 10 for a more detailed explanation, including a graphical representation of values and overlaps in Figure 10-8. While many resistors are now manufactured with high precision, 20%

tolerance is still common for electrolytic capacitors. Other types of capacitors are available with an accuracy of 10% or 5%, but are more expensive.

While large-value capacitors are likely to have their actual value printed on them, smaller capacitors are identified by a variety of different codes. These codes are not standardized among manufacturers, and exist in various colors and abbreviations. A multimeter that can measure capacitance is a quicker, easier, and more reliable method of determining the value of a component than trying to interpret the codes.

In addition to capacitance, a large capacitor is likely to have its working voltage printed on it. Exceeding this value increases the risk of damaging the dielectric. In the case of electrolytic capacitors, a voltage that is much lower than the rated value should also be avoided, because these capacitors require an electrical potential to maintain their performance.

In common electronics applications, values larger than 4,700µF or smaller than 10pF are unusual.

Electrolytics are available at a moderate price in a wider range of values than other commonly used capacitors. They range from 1µF to 4,700µF and sometimes beyond. Working voltages typically range from 6.3VDC to 100VDC, but can be as high as 450VDC.

Tantalum capacitors are usually unavailable in sizes above 150µF or for voltages above 35VDC.

Single-layer ceramic capacitors have small values ranging from 0.01µF to 0.22µF, with working voltages usually not exceeding 50VDC, although very small-value capacitors may be rated much higher for special applications. Poor tolerances of +80% to -20% are common.

Some variants of multi-layer ceramic capacitors are capable of storing up to 47µF, although 10µF is a more common upper limit. They are seldom rated above 100VDC. Some are accurate to plus-or-minus 5%.

Dielectric Constant

If A is the area of each plate in a capacitor (measured in square centimeters), and T is the thickness of the dielectric (measured in centimeters), and K is the *dielectric constant* of the capacitor, the capacitance, C (measured in farads) will be obtained from the formula:

```
C = (0.0885 * K * A) / T
```

The dielectric constant of air is 1. Other dielectrics have different standard values. Polyethylene, for instance, has a constant of approximately 2.3. Thus a capacitor of 1 square centimeter plate area and polyethylene dielectric 0.01 centimeters thick would have a capacitance of about 20pF. A tantalum capacitor of equal plate area and dielectric thickness would have capacitance closer to 100pF, since the dielectric constant of tantalum oxide is much higher than that of polyethylene.

The Time Constant

When a capacitor is charged in series through a resistor (it is used in an RC network), and it begins with no charge on its plates, the *time constant* is the time, in seconds, required to charge the capacitor to 63% of the supply voltage. After an additional, identical interval of time, the capacitor will acquire 63% of the remaining difference between itself and the power supply. In theory the capacitor gets closer and closer to a full charge, but never quite reaches 100%. However, five time constants are sufficient for the capacitor to reach 99%, which is regarded as close enough to being fully charged for all practical purposes.

Refer to Figure 12-3 for a schematic of an RC network.

The time constant is a simple function of the resistance and the capacitance. If R is the value of the resistor (in ohms), and C is the value of the capacitor (in farads), the time constant, TC, will be obtained by the formula:

```
TC = R * C
```

If we multiply the R value by 1,000 while dividing the C value by 1,000, the time constant remains the same, and we can use the more convenient values of kilohms for the resistance and µF for the capacitance. In other words, the formula tells us that a 1K resistor in series with a 1,000µF capacitor has a time constant of 1 second.

The formula suggests that if the value of R diminishes to zero, the capacitor will charge instantly. In reality, the charging time will be rapid but finite, limited by factors such as the electrical resistance of the materials used.

Multiple Capacitors

When two or more capacitors are wired in parallel, their total capacitance is the sum of their separate capacitances. When two or more capacitors are wired in series, the relationship between their total capacitance © and their individual capacitances (C1, C2, C3 . . .) is given by this formula:

$$1 / C = (1/C1) + (1/C2) + (1/C3).\ .\ .$$

The formula to calculate the total capacitance of capacitors connected in series resembles the one used to calculate the total resistance of resistors connected in parallel. See Chapter 10.

Alternating Current and Capacitive Reactance

The apparent resistance of a capacitor to AC is properly known as *capacitive reactance*. In the following formula, capacitive reactance (X_C, in ohms) is derived as a function of capacitance (C, in farads) and AC frequency (f, measured in hertz):

$$X_C = 1 / (2 * \pi * f * C)$$

The formula shows that when frequency becomes zero, capacitive reactance becomes infinite; in other words, a capacitor has theoretically infinite resistance when DC current tries to flow through it. In reality, a dielectric has a finite resistance, and thus always allows some leakage.

The formula also shows that capacitive reactance diminishes when the size of the capacitor increases and/or the frequency being applied to it increases. From this it appears that an AC signal will be attenuated less at higher frequencies, especially if we use a small capacitor. However, a real-world capacitor also exhibits some degree of *inductive reactance*. This value will depend on its configuration (cylindrical vs. multiple flat plates), its physical length, the materials from which it is fabricated, the lengths of its leads, and other factors. Inductive reactance tends to *increase* with frequency, and since capacitive reactance tends to *decrease* with frequency, at some point the curves for the two functions intersect. This point represents the capacitor's *self-resonant frequency*, which is often referred to simply as its *resonant frequency*. See Figure 12-18.



Figure 12-18. *As an AC current applied to a capacitor increases in frequency, the capacitive reactance of the component decreases, while its inductive reactance increases. The resonant frequency of the capacitor is found where the two functions intersect.*

Equivalent Series Resistance

A theoretically ideal capacitor would be purely reactive, without any resistance. In reality, capacitors are not ideal, and they have *equivalent series resistance,* or *ESR*. This is defined as the resistor that you would have to place in series with an ideal version of the capacitor, so that the combination would behave like the real version of the capacitor on its own.

If X_c is the reactance of the capacitor, then its Q factor (which means its *quality factor*) is given by the simple formula:

$$Q = X_C / ESR$$

Thus, the quality factor is higher if the ESR is relatively low. However, the reactance of the capacitor will vary significantly with frequency, and this simple formula is only an approximate guide.

The Q-factor for capacitors should not be confused with the Q-factor for inductors, which is calculated quite differently.

How to Use it

The figures illustrate some simplified schematics for common applications.

Bypass Capacitor

In Figure 12-19, a low-value capacitor (often 0.1µF) is placed near the power input pin of a sensitive digital chip to divert high-frequency spikes or noise to negative ground. This *bypass capacitor* may also be described as a *decoupling capacitor*.



Figure 12-19. *A bypass capacitor (typically 0.1µF) configured to protect an integrated circuit logic chip from voltage spikes and noise in the power supply.*

Coupling Capacitor

In Figure 12-20, a 1µF *coupling capacitor* transmits a pulse from one section of a circuit to another, while blocking the DC voltage. Some reshaping of the waveform may occur.



Figure 12-20. *A coupling capacitor (typically around 1µF) preserves DC isolation of one section of a circuit from another, while allowing a pulse to be transmitted.*

High-Pass Filter

In Figure 12-21, a 0.1µF capacitor blocks the low-frequency component of a complex waveform and transmits only the higher frequency that was superimposed on the low frequency.

Low-Pass Filter

In Figure 12-22, a 0.1µF decoupling capacitor diverts the higher frequency component of a complex waveform to negative ground, allowing only



Figure 12-21. *A small capacitor (typically 0.1μF) can be used to create a high-pass filter, passing high frequencies while blocking low frequencies.*



Figure 12-22. *A small capacitor (typically 0.1μF) in this configuration routes high frequencies to negative ground, filtering them out of an analog signal.*

the lower frequency to be preserved. A lower-value capacitor (such as 0.001μF) will bleed away high-frequency noise from an AM radio source without affecting audio frequencies.

Smoothing Capacitor

In Figure 12-23, a 100μF capacitor charges and discharges to smooth an AC signal after a diode has removed the negative portion.

Snubber

In Figure 12-24, an RC network (inside a white dashed line) is known as a *snubber* when used to protect a switch from the problem of *arcing* (pronounced “arking”)—that is, a sustained spark that can quickly erode the switch contacts. Arcing may occur in switches, pushbuttons, or relays that control an inductive load, such as a large motor. This problem can become significant at high DC currents (10A or more) or relatively high AC or DC voltages (100V or more).

When the switch is opened, the magnetic field that has been sustained by the inductive load collapses, causing a surge of current, or *forward EMF*. The capacitor in the snubber absorbs this surge, thus protecting the switch contacts. When the switch is closed again, the capacitor discharges itself, but the resistor limits the outrush of current—again, protecting the switch.

A snubber placed around the switch in a DC circuit could typically use a 0.1μF capacitor (polypropylene or polyester) rated for 125VAC/200VDC, and a 100-ohm carbon resistor rated 0.5



Figure 12-23. *A capacitor of 100µF or more smooths the upper half of an AC signal that has passed through a diode. The capacitor charges during each positive pulse and discharges to "fill the gaps" between them.*

watt or higher. Prepackaged snubbers containing appropriate capacitor-resistor pairs are available from some parts suppliers, primarily for industrial use.

In an AC circuit, a snubber can be placed around the inductive load itself. Although a **diode** is often used this way in a DC circuit, it cannot be used with AC.

Although solid-state switching devices such as a **solid state relay** contain no mechanical contacts, they may still be damaged by substantial pulses of back-EMF, and can be protected by a snubber where they are controlling inductive loads that take 10A or more at 100V or more.



Figure 12-24. *An RC network (outlined with a white dashed line) protects a switch that controls a high inductive load. Used in this way, the RC network is known as a snubber.*

Capacitor as a Battery Substitute

A capacitor may be substituted for a battery for some applications, although it has a lower energy density and will be more expensive to manufacture. A capacitor charges and discharges much more rapidly than a battery because no chemical reactions are involved, but a battery sustains its voltage much more successfully during the discharge cycle.

Capacitors that can store a very large amount of energy are often referred to as *supercapacitors.*

What Can Go Wrong

Common problems associated with capacitors are age-related deterioration (especially in electrolytics), inductive reactance (especially in cylindrical formats), nonlinear response, resistivity, excessive current leakage, and dielectric memory. Some of these problems are discussed below. A manufacturer's datasheet should be consulted carefully in conjunction with the notes regarding compositions in the preceding Variants section before making a commitment to a particular type of capacitor.

Wrong Polarity

A polarized capacitor may offer virtually no resistance if it is connected the wrong way around to a DC power source. A very high current can result, damaging the capacitor and probably other components in the circuit. Failing to observe the polarity of a tantalum capacitor can have destructive or even explosive consequences, depending on the amperage.

Voltage Overload

If the DC working voltage of a capacitor is exceeded, there is a risk of breaking down the dielectric and allowing a spark, or arc, that will form a short circuit. Note that the DC rating of a capacitor does not mean that it can be used safely with an equivalent AC voltage. The maximum AC voltage should be no greater than approximately 0.7 times the DC rated voltage. If a DC-rated capacitor is used directly across an AC power line, it will create an effective short circuit.

If capacitors are connected in series or in parallel, ideally the voltage rating for each capacitor should be the same, and certainly no less than the supply voltage.

Tantalum capacitors are easily damaged by current spikes that exceed their maximum working voltage, and are unsuitable for high-frequency coupling because of their inductance.

Leakage

Charge leakage is a problem especially associated with electrolytic capacitors, which are not suitable for storing a charge over a significant interval. Polypropalene or polystyrene film capacitors are a better choice.

Dielectric Memory

Also known as *dielectric absorption*, this is a phenomenon in which a capacitor's electrolyte displays some percentage of its former voltage after the capacitor has been discharged and then disconnected from the circuit. Single-layer ceramic capacitors especially tend to suffer from this problem.

Specific Electrolytic Issues

Electrolytic capacitors have high inductive reactance, are not manufactured to close tolerances, and deteriorate significantly with age. While other components may be stockpiled and used over a period of years, this is not a sensible policy with electrolytics.

The "capacitor plague" affecting many of these capacitors manufactured from 1999 onward provided a salutary lesson regarding their potential weaknesses. Faulty composition of the dielectric allowed it to deteriorate, liberating hydrogen gas, which eventually caused the aluminum shells of the capacitors to bulge and burst. Circuit boards from major manufacturers were affected. Because the problem took two years to become apparent, literally millions of boards with faulty capacitors had been sold before the fault was diagnosed and eventually corrected.

Unfortunately electrolytics cannot be easily replaced with other types of capacitors in applications such as power supplies, because substitutes will be considerably larger and more expensive.

Heat

The equivalent series resistance (ESR) of a large capacitor inevitably means that it must dissipate some power as heat during use. Ripple current can also create heat. Capacitor performance will change as the temperature increases. A common maximum component temperature for electrolytic capacitors is 85 degrees Centigrade.

Vibration

In a high-vibration environment, electrolytics should be protected by clamping them mechanically in place, using a *capacitor clamp*, also known as a *c-clamp*.

Misleading Nomenclature

Rarely, in the United States, the term “mF” may be used as a probable alternative to µF. This can be a source of confusion and risk because mF is properly (but very rarely) used to mean “millifarads.” The term should always be avoided.

variable capacitor

13

Formerly known (primarily in the United Kingdom) as a *variable condenser*. The term is now obsolete.

OTHER RELATED COMPONENTS

- **capacitor** (See Chapter 12)

What It Does

A variable capacitor allows adjustment of capacitance in much the same way that a **potentiometer** allows adjustment of resistance.

Large variable capacitors were developed primarily to tune radio receivers, in which they were known as *tuning capacitors*. Cheaper, simpler, and more reliable substitutes gradually displaced them, beginning in the 1970s. Today, they are still used in semiconductor fabrication, in RF plastic welding equipment, in surgical and dental tools, and in ham radio equipment.

Small *trimmer capacitors* are widely available and are mostly used to adjust high-frequency circuits. Many of them look almost indistinguishable from *trimmer potentiometers*.

The schematic symbols commonly used to represent a variable capacitor and a trimmer capacitor are shown in Figure 13-1.

A *varactor* is a form of diode with variable capacitance, controlled by reverse voltage. See "Varactor Diode" (page 225) for this component.

How It Works

The traditional form of variable capacitor consists of two rigid semicircular plates separated by an air gap of 1mm to 2mm. To create more capacitance, additional interleaved plates are added to form a stack. One set of plates is known as the *rotor*, and is mounted on a shaft that can be turned, usually by an externally accessible knob. The other set of plates, known as the *stator*, is mounted on the frame of the unit with ceramic insulators. When the sets of plates completely overlap, the capacitance between them is maximized. As the rotor is turned, the sets of plates gradually disengage, and the capacitance diminishes to near zero. See Figure 13-2.



Figure 13-1. *Typical schematic symbols for variable capacitor (left) and trimmer capacitor (right).*

The air gaps between the sets of plates are the *dielectric*. Air has a dielectric constant of approximately 1, which does not vary significantly with temperature.

The most common shape of plate is a semicircle, which provides a linear relationship between capacitance and the angle of rotation. Other shapes have been used to create a nonlinear response.



Figure 13-2. *In this simplified view of a variable capacitor, the brown plates constitute the rotor, attached to a central shaft, while the blue plates are the stator. The colors have no electrical significance and are added merely for clarity. The area of overlap between rotor and stator determines the capacitance.*

Reduction gears may be used to enable fine tuning of a variable capacitor, which means multiple turns of a knob can produce very small adjustments of the capacitor. At the peak of variable capacitor design, units were manufactured with high mechanical precision and included *anti-backlash gears*. These consisted of a pair of equal-sized gears mounted flat against each other with a spring between them that attempted to turn the gears in opposite directions from each other. The pair of gears meshed with a single pinion, eliminating the looseness, or backlash, that normally exists when gear teeth interlock. A vintage capacitor with a spring creating anti-backlash gearing (circled) is shown in Figure 13-3. This is a two-gang capacitor—it is divided into two sections, one rated 0 to 35pF, the other rated 0 to 160pF.



Figure 13-3. *A "traditional style" variable capacitor of the type designed to tune radio frequencies. The spring, circled, enables anti-backlash gearing.*

Variants

The traditional variable capacitor, with exposed, air-spaced, rigid, rotating vanes, is becoming hard to find. Small, modern variable capacitors are entirely enclosed, and their plates, or vanes, are not visible. Some capacitors use a pair of concentric cylinders instead of plates or vanes, with an external thumb screw that moves one cylinder up or down to adjust its overlap with the other. The overlap determines the capacitance.

Trimmer capacitors are available with a variety of dielectrics such as mica, thin slices of ceramic, or plastic.

Values

A large traditional capacitor can be adjusted down to a near-zero value; its maximum will be no greater than 500pF, limited by mechanical factors. (See Chapter 12 for an explanation of capacitance units.)

A maximum value for a trimmer capacitor is seldom greater than 150pF. Trimmers may have their values printed on them or may be color-coded, but there is no universal set of codes. Brown, for example, may indicate either a maximum value around 2pF or 40pF, depending on the manufacturer. Check datasheets for details.

The upper limit of a trimmer's rated capacitance is usually no less than the rated value, but can often be 50% higher.

Formats

All trimmer capacitors are designed for mounting on circuit boards. Many are surface-mount, with a minority being through-hole. Surface-mount units may be 4mm × 4mm or smaller. Through-hole are typically 5mm × 5mm or larger. Superficially, trimmer capacitors resemble single-turn trimmer potentiometers with a screw head in the center of a square package. A through-hole example is shown in Figure 13-4.



Figure 13-4. *A trimmer capacitor rated 1.5pF to 7.0pF.*

How to Use it

A variable capacitor is often used to tune an *LC circuit,* so called because a coil (with reactance customarily represented by letter L) is wired in parallel with a variable capacitor (represented by letter C). The schematic in Figure 13-5 shows an imaginary circuit to illustrate the principle. When the switch is flipped upward, it causes a large fixed-value capacitor to be charged from a DC power source. When the switch is flipped down, the capacitor tries to pass current through the coil—but the coil's *reactance* blocks the current and converts the energy into a magnetic field. After the capacitor discharges, the magnetic field collapses and converts its energy back into electricity. This flows back to the capacitor, but with inverted polarity. The cycle now repeats with current flowing in the opposite direction. A low-current **LED** across the circuit would flash as the voltage oscillates, until the energy is exhausted.



Figure 13-5. *In this imaginary circuit, the capacitor is charged through the double-pole switch in its upper position. When the switch is turned, the capacitor forms an LC (inductance-capacitance) circuit with the coil, and resonates at a frequency determined by their values. In reality, extremely high values would be needed to obtain a visible result from the LED.*

Because the oscillation resembles water sloshing from side to side in a tank, an LC circuit is sometimes referred to as a *tank circuit.*

In reality, unrealistically large values would be required to make the circuit function as described. This can be deduced from the following formula, where f is the frequency in Hz, L is inductance in Henrys, and C is capacitance in Farads:

$$f = 1 / (2\pi * \sqrt{(L * C)})$$

For a frequency of 1 Hz, a massive coil opposite a very large capacitor of at least 0.1F would be needed.

However, an LC circuit is well-suited to very high frequencies (up to 1,000MHz) by using a very small coil and variable capacitor. The schematic in Figure 13-6 shows a high-impedance earphone and a diode (right) substituted for the LED and the resistor in the imaginary circuit, while a variable capacitor takes the place of the fixed capacitor. With the addition of an antenna at the top and a ground wire at the bottom, this LC circuit is now capable of receiving a radio signal, using the signal itself as the source of power. The resonant frequency of the circuit is tuned by the variable capacitor. The impedance peaks at the resonant frequency, causing other frequences to be rejected by passing them to ground. With suitable refinement and amplification, the basic principle of an LC circuit is used in AM radios and transmitters.

Because variable capacitors are so limited in size, they are unsuitable for most timing circuits.

Trimmer capacitors are typically found in high-power transmitters, cable-TV transponders, cellular base stations, and similar industrial applications.

They can be used to fine-tune the resonant frequency of an oscillator circuit, as shown in Figure 13-7.



Figure 13-6. *The principle of an LC circuit is used here in a basic circuit that can tune in to a radio station and create barely audible sound through the earphone at right, using only the broadcast signal for power. The variable capacitor adjusts the frequency of the circuit to resonate with the carrier wave of the radio signal.*



Figure 13-7. *A trimmer capacitor in series with a crystal fine-tunes the frequency of this basic circuit using an op-amp.*

In addition to tuning a circuit frequency, a trimmer capacitor can be used to compensate for changes in capacitance or inductance in a circuit that are caused by the relocation of wires or rerouting of traces during the development process. Readjusting a trimmer is easier than swapping fixed-value capacitors. A trimmer may also be used to compensate for capacitance in a circuit that gradually drifts with age.

What Can Go Wrong

Failure to Ground Trimmer Capacitor While Adjusting it

Although trimmer capacitors are not polarized, the manufacturer may mark one terminal with a plus sign and/or the other with a minus sign. If the capacitor is adjusted while its negative terminal is floating or ungrounded, a metal screwdriver blade will create erroneous readings. Always ground the appropriate side of a trimmer capacitor before fine-tuning it, and preferably use a plastic-bladed screwdriver.

Application of Overcoat Material or "Lock Paint"

Overcoat material is a rubbery adhesive that may be spread over assembled components to immunize them against moisture or vibration. *Lock paint* is a dab of paint that prevents a screw adjustment from turning after it has been set. Most manufacturers advise against applying these materials to a trimmer capacitor, because if penetration occurs, the capacitor can fail.

Lack of Shielding

Variable capacitors should be shielded during use, to protect them from external capacitive effects. Merely holding one's hand close to a variable capacitor will change its value.

inductor

14

The term **inductor** is used here to describe a coil that has the purpose of creating *self-inductance* in an electronic circuit, often while passing alternating current in combination with resistors and/or capacitors. A *choke* is a form of inductor. By comparison, the **electromagnet** entry in this encyclopedia describes a coil containing a center component of ferromagnetic material that does not move relative to the coil, and has the purpose of attracting or repelling other parts that respond to a magnetic field. A coil containing a center component of ferromagnetic material that moves as a result of current passing through the coil is considered to be a **solenoid** in this encyclopedia, even though that term is sometimes more broadly applied.

OTHER RELATED COMPONENTS

- **solenoid** (See Chapter 21)
- **electromagnet** (See Chapter 20)

What It Does

An inductor is a coil that induces a magnetic field in itself or in a *core* as a result of current passing through the coil. It may be used in circuits to block or reshape AC current or a range of AC frequencies, and in this role can "tune" a simple radio receiver or various types of oscillators. It can also protect sensitive equipment from destructive voltage spikes.

The schematic symbol for an inductor includes a coil that can be drawn in two basic styles, shown at the top and at the bottom of Figure 14-1. The style at the bottom has become more common. In each vertical section of the diagram, the functionality of the symbols is identical.

One or two parallel lines alongside the coil indicate that it is wound around a solid core of material that can be magnetized, while one or two dotted lines indicate that it is wound around a core containing metal particles, such as iron filings. Where no core is shown, this indicates an air core.



Figure 14-1. *The coil symbol for an inductor may be drawn in two styles which are functionally identical. Line(s) beside the coil indicate a solid core. Dotted line(s) indicate a core containing metal particles.*

A selection of inductors designed for through-hole mounting is shown in Figure 14-2.



Figure 14-2. *Four inductors designed for through-hole insertion into printed circuit boards.*

How It Works

Direct current passing through an electrical conductor, such as a wire, creates a magnetic field around the conductor. In Figure 14-3, *conventional current* (flowing from positive to negative) is passing through a straight wire from left to right, as indicated by the red/blue arrow. The resulting magnetic field is indicated by the green arrows. If the wire is now bent into a curve, as shown in Figure 14-4, the magnetic field exerts an aggregate force downward through the curve. This magnetic force is conventionally said to flow from *south* to *north*.

If direct current could be induced to circulate through an unbroken circle of wire, the resulting magnetic field could exert a force through the circle as shown in Figure 14-5, assuming clockwise circulation of conventional current as suggested by the red/blue arrows.

Conversely, if a magnet was pushed through the center of the circle, it would induce a pulse of electric current in the circle. Thus, electricity passing through a wire can induce a magnetic field around the wire, and conversely, a magnet moving near a wire can induce an electric current in the wire. This principle is used in an electrical *generator*, and also in a **transformer**, where alternating current in the primary coil induces a fluctuating magnetic field in the core, and the field in the core is turned back into alternating current in the secondary coil.



Figure 14-3. *Conventional current passing through a wire from left to right (as indicated by the red/blue arrow) induces a magnetic field around the wire (shown by the green arrows).*



Figure 14-4. *If the wire is bent into a curve, the magnetic fields can create a net force shown by the large green arrow.*

Note that a static or unchanging magnetic field will not induce a flow of electricity.



Figure 14-5. *Hypothetically, if conventional current flows around a circular conductor (as suggested by the red/blue arrows), it will create a magnetic field that can create a force as shown by the green arrow.*

DC Through a Coil

If the wire is formed into a helix (a series of approximate circles) as shown in Figure 14-6, and if DC current is passed through the wire, the aggregate of the magnetic fields can create a force in the direction of the green arrow in each example, depending whether the wire is wound clockwise or counter-clockwise, and depending on the direction of the current. The helix is usually referred to as a *coil* or a *winding*.

In actuality, a magnetic field is not open-ended, and its lines of force are completed by circling around outside the inductor, to complete a *magnetic circuit*. This completion of the field can be demonstrated by the traditional high-school experiment of positioning a compass or scattering iron filings on a sheet of paper above a magnet. A simplified depiction of lines of force completing a magnetic circuit is shown in Figure 14-7, where a coil is inducing the magnetic field. Note that throughout this encyclopedia, the color green is used to indicate the presence of magnetic force.



Figure 14-6. *When DC current flows through a coil, it creates magnetic fields that will exert a force whose direction depends on the direction of the current and on whether the coil is wound clockwise or counterclockwise. The force is shown by the green arrow in each case.*

The completion of a magnetic field is not relevant to the primary function of the inductor. In fact the external part of the magnetic field is mostly a source of trouble in electronics applications, since it can interact with other components, and may necessitate the use of magnetic shielding. In addition, the field is weakened by completing itself through air, as air presents much greater *reluctance* (the magnetic equivalent of resistance) than the core of an electromagnet.

The polarity of a magnetic field created by a coil can be demonstrated by moving a small permanent magnet toward the coil, as shown in



Figure 14-7. *A magnetic field in reality is not open-ended, and each line of force traveling through a rod-shaped magnet or electromagnet is completed outside of the magnet. The completion of magnetic fields has been omitted from other diagrams here for clarity.*

Figure 14-8. If the magnet has opposite polarity to the coil, it will tend to be repelled, as like poles repel. If it has the same polarity, it will tend to be attracted, because opposite poles attract. This principle may be used in **solenoids**.



Figure 14-8. *A permanent magnet (left) will either be drawn toward a DC-energized coil or repelled from it, depending on the polarity of the two magnetic fields.*

Magnetic Core

The inductive power of a coil will be enhanced, and the saturation point will be reduced, by using a *magnetic core*. The term "magnetic" in this context does not mean that the core is a permanent magnet; it means that the core can be magnetized briefly by a transient pulse of electricity through the surrounding coil.

A core enhances the effectiveness of an inductor because it has a lower reluctance than that of air. In other words, magnetic flux will flow much more readily through the core than through air.

Roughly speaking, the *permeability* of a magnetic circuit is the opposite of reluctance; it is a measure of how easily a magnetic field can be induced, and is usually expressed relative to the permeability of air, which is approximately 1. The permeability of different core types is discussed in the following "Values" section.

The core of the coil contains *magnetic domains* that behave as tiny magnets, with north and south poles. In the absence of a polarizing magnetic field, the domains are randomly aligned. As a magnetic field is introduced around them and grows stronger, the domains align themselves with it, increasing the total magnetic force. When the domains are almost all uniformly aligned, the core approaches *magnetic saturation* and ceases adding to the net magnetic field. At this point the current in the inductor is said to be *continuous*.

When power to the coil is disconnected, the domains revert partially to their previous random orientation. Thus the core remains a weak permanent magnet. This effect is known as *hysteresis*, while the weak residual field is known as *remanent magnetism*.

EMF and Back-EMF

When DC current is connected through an inductor, the creation of a magnetic field takes a brief but measurable period of time. The field induces an *EMF* (*electro-motive force*) in the wire. Since this force opposes the supplied current, it is referred to as *back-EMF*. It lasts only so long as the field is increasing to its full strength. After the field reaches a steady state, current flows through the coil normally.

This transient resistive effect is caused by the *self-inductance* of the coil, and is opposite to the behavior of a capacitor, which encourages an initial inrush of direct current until it is fully charged, at which point it blocks subsequent current flow.

When high-frequency alternating current attempts to flow through an inductor, if each pulse is too brief to overcome the back-EMF, the coil will block the current. A coil can thus be designed to block some frequencies but not others.

Even a simple electrical circuit that does not contain a coil will still have some self-inductance, simply because the circuit consists of wires, and even a straight length of wire induces a magnetic field when the power is switched on. However, these inductive effects are so small, they can generally be ignored in practical applications.

The transient electrical resistance to alternating current caused by either an inductor or a capacitor is known as *reactance*, although it occurs under opposite electrical conditions, as the coil impedes an initial pulse of DC current and then gradually allows it to pass, while a capacitor allows an initial pulse of DC current and then impedes it.

When a flow of DC current through a coil is switched off, the magnetic field that was created by the coil collapses and releases its stored energy. This can cause a pulse of forward EMF, and like back-EMF, it can interfere with other components in a circuit. Devices such as motors and large relays that contain substantial coils can create problematic spikes of back-EMF and forward-EMF. The forward-EMF that occurs when power to the coil is interrupted is typically dealt with by putting a diode in parallel with the coil, allowing current to circulate through it. This is known as *clamping* the voltage transient. A diode-capacitor combination known as a *snubber* is also commonly used. For a schematic and additional information on this topic, see "Snubber" (page 108).

A schematic to demonstrate EMF and back-EMF is shown in Figure 14-9. The coil can be a 100-foot spool of 26-gauge (or smaller) hookup wire, or magnet wire. It will function more effectively if a piece of iron or steel, such as half-inch galvanized pipe, is inserted through its center. When the button is pressed, current is briefly impeded by the back-EMF created by the coil, and is diverted through D1, making it flash briefly. Then the coil's reactance diminishes, allowing the current to flow through the coil and bypass the LED. When the pushbutton is released, the coil's magnetic field collapses, and the consequent forward-EMF circulates through D2, causing it to flash briefly. Note that the polarity of back-EMF and forward-EMF are opposite, which is why the LEDs in the circuit are oriented with opposite polarities.

The 220Ω resistor should be rated at 1/4 watt minimum, and the button should not be held down for long, as the electrical resistance of the coil is relatively low. The LEDs ideally should be rated for a minimal forward current of no more than 5mA.

Electrical and Magnetic Polarity

Various mnemonics and images have been created to assist in memorizing the polarity or direction of the magnetic field that will be created by a flow of electricity. The *right-hand rule* suggests that if the fingers of the right hand are curled around a coil in the same direction in which the turns of the coil were wound, and if conventional DC current also flows in this direction, the extended thumb will point in the direction of the principal force that can be created by the magnetic field.

By convention, the magnetic field is oriented from *south* to *north*, which can be remembered since the north end of the magnetic field will be



Figure 14-9. *A test circuit to demonstrate the EMF and back-EMF created when DC current starts and stops passing through a coil. See text for details.*

the negative end of the coil (north and negative both beginning with letter N). This mnemonic only works if conventional (positive) current flows through a coil that is wound clockwise.

Another model is the "corkscrew rule" in which we imagine conventional DC current flowing from the handle of a corkscrew, down through its metal section, toward the pointed end. If the corkscrew is turned clockwise, in the same direction as the electricity, the corkscrew will sink into the cork in the same as the direction as the resulting magnetic force.

Variants

Variants include core materials, core shapes, termination style (for through-hole mounting in perforated board, or for surface-mount), and external finish (some inductors are dipped in insulating material, while others allow their copper magnet wire to be exposed).

In addition there are two functional variants: variable inductors and ferrite beads. Their schematic symbols are shown in Figure 14-10.



Figure 14-10. *Schematic symbols for a ferrite bead (farthest right) and variable inductors (all other symbols, which are functionally identical).*

Magnetic Cores

A magnetic core may be made from solid iron, plates of iron or steel separated by thin insulating material, powdered iron mixed with a binder, or a ferrite compound derived from nickel, zinc, manganese, or a combination. An iron core has at least 1,000 times the permeability of air, while some ferrites are 10,000 times as permeable.

One major disadvantage of a magnetic core is *hysteresis*, which in this context refers to the tendency of the core to retain some magnetic "memory" as a cycle of alternating current changes from positive to negative. This residual magnetism must be overcome by the next positive pulse of AC. The tendency of the core to retain magnetic polarity is known as its *retentivity*. Iron cores are especially retentive.

Another disadvantage of some magnetic cores is that they may host eddy currents induced by the magnetic field of the coil. These electrical currents tend to circulate through the core, reducing efficiency by generating waste heat, especially if coil currents are high. Forming a core from iron or steel plates, separated by thin layers of insulation, will inhibit these currents. Powdered iron inhibits eddy currents because the particles have limited contact. Ferrites are nonconductive, and are therefore immune to eddy currents. They are widely used.

Hysteresis and eddy currents both incur energy losses with each AC cycle. Therefore, the losses increase linearly as the AC frequency increases. Consequently, inductor cores that suffer either of these problems are not well-suited to high frequencies.

Nonmagnetic Cores

The problems associated with magnetic cores may be avoided by winding the coil around a nonmagnetic core that may be hollow, ceramic, or plastic. A hollow core is referred to as an *air core*. The permeability of ceramic and plastic cores is close to that of air.

An inductor with a nonmagnetic core will be immune to eddy currents and retentivity, but will have to be significantly larger than a magnetic-cored coil with comparable inductance. In the case of a very primitive radio receiver, such as a crystal set, the air-cored coil that selects a radio frequency may be several inches in diameter. A basic circuit diagram for a crystal set (so-called because it uses a diode containing a germanium crystal) is shown in Figure 14-11. The antenna, at top, receives signals broadcast from radio stations. The coil can be tapped (as indicated by the black dots) as a simple way to select different inductance values, blocking all but a narrow range of frequencies. The T-shaped white component at right is a high-impedance earphone. The diode blocks the lower half of the alternating current in a radio signal, and since the signal is *amplitude-modulated*, the earphone responds to variations in intensity in the signal and reproduces the sound encoded in it.



Figure 14-11. *An early and basic application for an inductor is to select radio-station frequencies, as in this schematic for a crystal set. See text for details.*

Variable Inductors

A *variable inductor*, also known as an *adjustable inductor*, is relatively uncommon but can be fabricated by using a magnetic core that penetrates the center of the inductor on an adjustable screw thread. The inductance of the assembly will increase as a larger proportion of the magnetic core penetrates into the open center of the coil. A photograph of a variable inductor is at Figure 14-12.



Figure 14-12. *A variable inductor. Its inductance is adjusted via a screw thread that varies the insertion of the core in the coil. In this component the core is turned by inserting a hex wrench, as shown. It is rated from 0.09µH to 0.12µH.*

Ferrite Beads

A *ferrite bead* inverts the design of a typical inductor by running a wire through a hole in the center of the bead, instead of coiling the wire around the core. Two ferrite beads are shown in Figure 14-13. At top, the bead is divided into two sections, each mounted in one-half of a plastic clam shell, which can be closed around a wire. At bottom, the bead must be threaded onto a wire. The purpose is either to limit radio-frequency radiation from a wire by absorbing it into the bead (where it is transformed into heat), or to protect a wire from external sources of radio-frequency radiation. Computer cabling to external devices; lamp dimmers; and some types of motors can be sources of radio frequency.



Figure 14-13. *Two examples of ferrite beads. They can inhibit radio-frequency radiation from a wire, or protect the wire from interference.*

Toroidal Cores

The magnetic circuit created by a rod-shaped core must be completed by the lines of force traveling back around from one end of the rod to the other, through the surrounding air. Since air has low permeability, this is a major source of inefficiency. By comparison, a torus (a geometrical shape resembling a donut) completes the entire magnetic circuit inside its core. This significantly increases its efficiency. Also, because its field is better contained, a toroidal inductor needs little or no shielding to protect other components from stray magnetic effects.

Two through-hole toroidal inductors are shown in Figure 14-2. Bottom left: Rated at 345μH. Bottom right: Rated at 15μH. The one at bottom-left has pins beneath it for insertion into a printed circuit board.

Surface-mount inductors often are toroidal to maximize the efficiency of a component that has to function on a very small scale. Examples are shown in Figure 14-14, Figure 14-15, and Figure 14-16.



Figure 14-14. *In a typical toroidal inductor, the coil is wrapped around a magnetic core shaped as a torus. This surface-mount component (viewed from the bottom, at left, and from the top, at right) is at the low end of the range of component sizes. It is rated at 750nH.*



Figure 14-15. *A medium-sized surface-mount toroidal inductor (viewed from the bottom, at left, and from the top, at right). It is rated at 25μH.*



Figure 14-16. *A larger-sized surface-mount toroidal inductor (viewed from the bottom, at left, and from the top, at right). It is rated at 3.8μH.*

A chart showing some types of inductor cores, their commonly available inductances, and their maximum frequencies is shown in Figure 14-17.

Gyrator

A *gyrator* is a small network, sometimes encapsulated in a silicon chip, using **resistors**, a semiconductor, and a **capacitor** to simulate some but not all of the behavior of a coil-based inductor. The semiconductor may be a transistor or a capacitor, depending on the specific circuit. A sample schematic is shown in Figure 14-18. Because no magnetic effects are induced, the gyrator is completely free from the problems of saturation and hysteresis, which affect coils with cores, and also produces no back-EMF. It simply attenuates a signal initially, and then gradually lowers its reactance, thus imitating this aspect of an inductor.

A gyrator may be used where a coil may be unacceptably large (as in a cellular phone) or where signal quality is of paramount importance—for example, in a graphic equalizer or other audio components that perform signal processing at input stages, such as preamplifiers.



Figure 14-17. *Some commonly used inductor cores and their characteristics. Adapted from "Producing wound components" by R.Clark@surrey.ac.uk.*



Figure 14-18. *A possible schematic for a coil substitute known as a gyrator, which may be used where a conventional coil would be unacceptably bulky.*

A gyrator does impose some limits on circuit design. While neither side of a real inductor needs to be at ground potential, a gyrator does require a ground connection. However, the performance advantages of gyrators are significant, as they can emulate high inductance without parasitic effects, can be more accurately calibrated (leading to more predictable performance), and do not create magnetic fields that can interfere with other components.

Values

Calculating Inductance

The magnetic inductance of a coil is measured with a unit known as the Henry, named after Joseph Henry, a pioneer in electromagnetism. It is defined by imagining a coil in which current is fluctuating, causing the creation of EMF. If the rate of fluctuation is 1 amp per second and the induced EMF is 1 volt, the inductance of the coil is 1 Henry.

The letter L is commonly used to represent inductance. To derive a useful formula, L will be expressed in microhenrys. If D is the diameter of a coil, N is the number of turns of wire, and W is the width of coil (when the windings are viewed from the side, as shown in Figure 14-19), the precise relationship of the variables is complex but can be reduced to an approximate formula:

$$L = \text{approx } (D^2 * N^2) / 18 * D) + (40 * W$$



Figure 14-19. *Dimensions of a coil, referenced by a formula to calculate its approximate inductance. See text for details.*

From this, it is clear that inductance tends to increase with coil diameter, and also increases (more significantly) with the square of the number of turns. If the number of turns remains constant, inductance will be higher for a coil that is short and fat than for a coil that is narrow and long.

Because the Henry is a large unit, inductors in electronics circuits typically have their inductances measured in millihenrys (mH), microhenrys (µH), and nanohenrys (nH), where 1H = 1,000mH, 1 mH = 1,000µH, and 1µH = 1,000 nH. This relationship is shown in Figure 14-20.

Calculating Reactance

The reactance of an inductor (that is, its dynamic resistance to alternating current) varies with the frequency of the current. If f is the AC frequency (in Hertz), and L is the inductance (in Henrys), the reactance, X_L in ohms, is given by the formula:

$$X_L = 2 * \pi * f * L$$

From this equation, it's apparent that as the frequency tends toward zero (DC current), or if the inductance tends toward zero (a short piece of

nH	µH	mH
1	0.001	0.000001
10	0.01	0.00001
100	0.1	0.0001
1,000	1	0.001
10,000	10	0.01
100,000	100	0.1
1,000,000	1,000	1

Figure 14-20. *Inductance is typically measured in nanohenrys (nH), microhenrys (µH), and millihenrys (mH). Equivalent values in these units are shown here.*

straight wire), the reactance will tend toward zero. Conversely, the inductor will impede current increasingly as the frequency and/or the inductance increases.

Calculating Reluctance

The letter S is often used to represent reluctance, while Greek letter µ customarily represents permeability (not to be confused with the use of µ as a multiplication factor of 1/1,000,000, as in µF, meaning "microfarad"). If A is the area of cross-section of the magnetic circuit and L is its length:

```
S = L / µ * A
```

Datasheet Terminology

A typical manufacturer's datasheet should include an *inductance index* for an inductor, expressed in µH per 100 turns of wire (assuming the wire is in a single layer) for inductors with a powdered iron core, and mH per 1,000 turns of wire for inductors with ferrite cores.

The *DCR* is the DC resistance of an inductor, derived purely from the wire diameter and its length.

The *SRF* is the *self-resonant frequency*. An inductor should be chosen so that AC current passing through it will never get close to that frequency.

ISAT (or I_{sat}) is the saturation current, which results in a magnetic core losing its function as a result of magnetic saturation. When this occurs, inductance drops and the charge current rate increases drastically.

Series and Parallel Configurations

Because the inductance of a coil conducting DC current is proportional to the current, the calculations to derive the total inductance of coils in series or in parallel are identical to the calculations used for resistors.

In series, all the coils inevitably pass the same current, and the total inductance is therefore found by summing the individual inductances. When coils are wired in parallel, the current distributes itself according to the inductances; therefore, if L1 is the reluctance of the first coil, L2 is the reluctance of the second coil, and so on, the total reluctance L of the network is found from the formula:

```
1/L = 1/L1 + 1/L2 + 1/L3. . .
```

This is shown in Figure 14-21. In reality, differences between the coils (such as their electrical resistance), and magnetic interaction between the coils, will complicate this simple relationship.

Time Constant

Just as the *time constant* of a capacitor defines the rate at which it accumulates voltage when power is applied through a resistor, the time constant of an inductor defines the rate at which it gradually allows amperage to pass through it, overcoming the EMF generated by the coil. In both cases, the time constant is the number of seconds that the component requires to acquire approximately 63% of the difference between its current value and its maximum value. In the case of an inductor, suppose we assume zero internal resistance in the power source, zero resistance in



Figure 14-21. *Calculating the total inductance of inductors in parallel (top) and series (bottom).*

the coil windings, and an initial current of zero. If L is the inductance of the coil and R is the value of the series resistor, then the time constant—TC—is given in seconds by the formula

```
TC = L / R
```

Therefore a coil of 10 millihenrys (0.01 Henry) in series with a 100-ohm resistor will pass 63% of the full current in 0.0001 seconds, or 1/10 of a millisecond; it will take an equal additional amount of time for the current to rise by another 63% of the remaining difference between its charge and the maximum amperage of the circuit. In theory, the reactance of a coil can never diminish to zero, but in practice, five time constants are considered adequate to allow maximum current flow.

How to Use it

Because the inductance of an inductor peaks as current increases, and then gradually diminishes, an inductor can be used to block or attenuate high frequencies. A circuit that does this is often referred to as a *low-pass filter*. The schematic and a graph suggesting its performance are shown in Figure 14-22. A basic application could be the *crossover network* in a loudspeaker system, where high-frequency signals are blocked from a low-frequency driver and are diverted to a high-frequency driver.



Figure 14-22. *By using the ability of an inductor to block a range of frequencies, a low-pass filter blocks higher frequencies.*

If the location of the inductor is shifted so that it shunts the signal away from the output, the results are reversed, and the circuit becomes a *high-pass filter*. The schematic and a graph suggesting its performance are shown in Figure 14-23.

Note that **capacitors** may also be used to create frequency filters, but because their function is roughly inverse to that of inductors, the place-


Input
Output
Decibels
80
60
40
20
Output at different frequencies (assuming constant 80dB input)
10
100
1K
10K
100K
Frequency (log scale)

Figure 14-23. *Here the inductor diverts low frequencies away from the output, allowing high frequencies to pass through.*

ment of a capacitor in a circuit would be opposite to the placement of the inductor. Examples of filter circuits using capacitors are found in the entry for that component in this encyclopedia.

An inductor can be combined with a capacitor to form a *bandpass filter*, as shown in Figure 14-24. In this configuration, the inductor blocks the high frequencies while the capacitor blocks the low frequencies, allowing only a limited band of frequencies to get through.

Once again if the location of the components is shifted to shunt the signal away from the output, the results are reversed, as shown in Figure 14-25. This is known as a *notch filter*.

The performance of these filters will depend on the component values, and in most applications, additional components will be necessary. Sophisticated filter circuits are outside the scope of this encyclopedia.


Input
Output
Decibels
80
60
40
20
Output at different frequencies (assuming constant 80dB input)
10
100
1K
10K
100K
Frequency (log scale)

Figure 14-24. *If the values of a capacitor and an inductor are correctly chosen, and the components are placed in series, the inductor blocks high frequencies while the capacitor blocks low frequencies, creating a bandpass filter, in which only a narrow band of frequencies can get through.*

Inductors are of great importance in **DC-DC converters** and **AC-DC power supplies** where voltage changes are enabled by rapid switching. See the relevant entries of this encyclopedia for additional details.

Generally, as electronic equipment has become increasingly miniaturized, the unavoidable bulk of inductors has limited their application. However they may still be used to tune oscillators, to block sudden spikes in power supplies, and to protect equipment from sudden voltage spikes (they are used, for example, in surge suppressors for computing equipment).



Figure 14-25. *Here the capacitor and inductor block all frequencies except a narrow band, which they divert from the output. The result is a notch filter.*

Core Choices

Air-cored inductors have relatively low inductance, because of their low permeability. However, they can be operated at very high frequencies up to the gigahertz range, and can tolerate higher peak currents.

Inductors with an iron core suffer increasing power losses due to hysteresis and eddy currents as the AC frequency passing through the inductor increases. Consequently, iron-cored inductors are not suitable for frequencies much above 10KHz.

Miniaturization

A low-value inductor can be formed by etching a spiral onto a circuit board, in applications where size must be minimized. They may also be incorporated in integrated circuit chips. However, in small devices such as cellular phones, it is more common to use a coil substitute such as a *gyrator*, as described previously.

What Can Go Wrong

Real-World Defects

The theoretically ideal inductor has no resistance or capacitance and suffers no energy losses. In reality, an inductor possesses both resistance and capacitance, also creates electrical noise, and may pick up electrical noise. It tends to create stray magnetic fields, and generally is more troublesome to deal with than its two cousins, the **resistor** and the **capacitor**.

Parasitic capacitance occurs between adjacent turns of wire. This capacitance becomes more significant at higher frequencies, leading ultimately to a situation where the coil becomes *self resonant*.

The workarounds for these problems involve coil geometries and choices of core material that go beyond the scope of this encyclopedia.

A *gyrator* should be considered as a possible substitute where inductors are troublesome or excessively expensive.

Saturation

Inductance increases as the current passing through a coil increases, but if a magnetic core is used, its contribution to inductance will stop abruptly when the core becomes magnetically *saturated*. In other words, when all of the randomly distributed *magnetic domains* in the core have been induced to align themselves with the pervasive magnetic field, the core cannot become more highly magnetized, and ceases to contribute to the inductance. Note that as a core approaches saturation levels, its hysteresis increases because reversing its magnetization requires greater energy. Antidotes to saturation would include a larger core, a lower current, a smaller number of turns in the coil, and using a core with lower permeability (such as air).

RF Problems

Radio frequencies (*RF*) introduce various problems affecting the efficiency of inductors. The *skin effect* is the tendency of high-frequency AC current to flow primarily on the surface of a strand of wire. The *proximity effect* refers to the tendency of the magnetic fields caused by adjacent wires to introduce eddy currents in the coil.

Both of these effects increase the effective resistance of the coil. Various coil geometries have been developed to minimize these effects, but are outside the scope of this encyclopedia. The fundamental lesson is that coils specifically designed for RF are the only ones that should be used with RF.

AC-AC transformer

15

OTHER RELATED COMPONENTS

- **AC-DC power supply** (See Chapter 16)
- **DC-DC converter** (See Chapter 17)
- **DC-AC inverter** (See Chapter 18)

What It Does

A transformer requires an input of *alternating current* (AC). It transforms the input voltage to one or more output voltages that can be higher or lower.

Transformers range in size from tiny impedance-matching units in audio equipment such as microphones, to multi-ton behemoths that supply high voltage through the national power grids. Almost all electronic equipment that is designed to be powered by municipal AC in homes or businesses requires the inclusion of a transformer.

Two small power transformers are shown in Figure 15-1. The one at the rear is rated to provide 36VAC at 0.8A when connected with a source of 125VAC. At front, the miniature transformer is a Radio Shack product designed to provide approximately 12VAC at 300mA, although its voltage will be more than 16VAC when it is not passing current through a load.



Figure 15-1. *Two small power transformers. The one at the rear measures approximately 1" × 2" × 2" and is rated to provide 36VAC at 0.8A. The term "sec" on the smaller unit is an abbreviation for "secondary," referring to the rating for its secondary winding.*

Transformer schematic symbols are shown in Figure 15-2. The different coil styles at left and right are functionally identical. Top: A transformer with a magnetic core—a core that can be magnetized. Bottom: A transformer with an air core. (This type of transformer is rare, as it tends to be less efficient.) The input for the transformer is almost always assumed to be on the left, through the *primary* coil, while the output is on the right, through the *secondary* coil. Often the two coils will show differing numbers of turns to indicate whether the transformer is delivering a reduced voltage (in which case there will be fewer turns in the secondary coil) or an increased voltage (in which case there will be fewer turns in the primary coil).



Figure 15-2. *Alternate symbols for a transformer with a ferromagnetic core (top) and air core (bottom). The differing coil symbols at left and right are functionally identical.*



Figure 15-3. *Three basic parts of a transformer, shown in simplified form.*

How It Works

A simplified view of a transformer is shown in Figure 15-3. Alternating current flowing through the primary winding (orange) induces magnetic flux in a laminated core formed from multiple steel plates. The changing flux induces current in the secondary winding (green), which provides the output from the transformer. (In reality, the windings usually consist of thousands of turns of thin magnet wire, also known as enameled wire; and various different core configurations are used.)

The process is known as *mutual induction*. If a load is applied across the secondary winding, it will draw current from the primary winding, even though there is no electrical connection between them.

In an ideal, lossless transformer, the ratio of turns between the two windings determines whether the output voltage is higher, lower, or the same as the input voltage. If V_p and V_s are the voltages across the primary and secondary windings respectively, and N_p and N_s are the number of turns of wire in the primary and secondary windings, their relationship is given by this formula:

$$V_p / V_s = N_p / N_s$$

A simple rule to remember is that fewer turns = lower voltage while more turns = higher voltage.

A *step-up transformer* has a higher voltage at its output than at its input, while a *step-down transformer* has a higher voltage at its input than at its output. See Figure 15-4.

In an ideal, lossless transformer, the power input would be equal to the power output. If V_{in} and V_{out} are the input and output voltages, and I_{in} and I_{out} are the input and output currents, their relationship is given by this formula:

$$V_{in} * I_{in} = V_{out} * I_{out}$$

Therefore, if the transformer doubles the voltage, it allows only half as much current to be drawn from the secondary winding; and if the voltage is cut in half, the available current will double.

Transformers are not 100% efficient, but they can be more than 98% efficient, and relationships between voltage, current, and the number of turns in the windings are reasonably realistic.

When the transformer is not loaded, the primary winding behaves like a simple inductor with reactance that inhibits the flow of current. Therefore a power transformer will consume relatively


More turns, higher voltage
Fewer turns, lower voltage
Output
Step-down transformer
Fewer turns, lower voltage
More turns, higher voltage
Output
Step-up transformer

Figure 15-4. *The ratio of input voltage to output voltage is equal to the ratio of primary turns to secondary turns in the transformer windings, assuming a transformer of 100% efficiency.*

little electricity if it is left plugged in to an electrical outlet without any load connected to its output side. The power that it does consume will be wasted as heat.

The Core

The ferromagnetic core is often described as being made of iron, but in reality is more often fabricated from high permeability silicon steel. To reduce losses caused by eddy currents, the core is usually laminated—assembled from a stack of plates separated from each other by thin layers of varnish or a similar insulator. Eddy currents tend to be constrained within the thickness of each plate.

Because a DC voltage would cause magnetic saturation of the core, all transformers must operate with alternating current or pulses of current. The windings and geometry of a transformer are optimized for the frequency range, voltage, and current at which it is designed to operate. Deviating significantly from these values can damage the transformer.

Taps

A *tap* on a transformer is a connection part-way through the primary or (more often) the secondary coil. On the primary side, applying an input between the start of a coil and a tap part-way through the coil will reduce the number of turns to which the voltage is applied, therefore increasing the ratio of output turns to input turns, and increasing the output voltage. On the secondary side, taking an output between the start of a coil and a tap part-way through the coil will reduce the number of turns from which the voltage is taken, therefore decreasing the ratio of output turns to input turns, and decreasing the output voltage. This can be summarized:

- A tap on the primary side can increase output voltage.
- A tap on the secondary side can provide a decreased output voltage.

In international power adapters, a choice of input voltages may be allowed by using a double-throw switch to select either the whole primary winding, or a tapped subsection of the winding. See Figure 15-5. Modern electronics equipment often does not require a voltage adapter, because a **voltage regulator** or **DC-DC converter** inside the equipment will tolerate a wide range of input voltages while providing a relatively constant output voltage.

A transformer's secondary winding is often tapped to provide a choice of output voltages. In fact, most power transformers have at least two outputs, since the cost of adding taps to the secondary winding is relatively small. As an



Figure 15-5. *An international power adapter can provide a fixed output voltage by using a double-throw switch to apply 230VAC voltage across a transformer's primary winding, or 115VAC to a tapped midpoint of the primary winding.*

alternative to tapped outputs, two or more separate secondary windings may be used, allowing the outputs to be electrically isolated from each other. See Figure 15-6.



Figure 15-6. *Multiple output voltages may be obtained from a transformer by tapping into the secondary winding (top) or using two or more separate secondary windings (bottom), in which case the outputs will be electrically isolated from each other.*

If the winding on the primary side of a transformer is coiled in the same direction as the winding on the secondary side, the output voltage will be 180 degrees out of phase with the input voltage. In schematics, a dot is often placed at one end of a transformer coil to indicate where the coil begins. If the dots on the primary and secondary sides are at the same ends of the coils, there will be a 180 degree phase difference between input and output. For many applications (especially where the output from a power transformer is going to be converted to DC), this is immaterial.

If there is a center tap on the secondary winding, and it will be referenced as ground, the voltages relative to it, at opposite ends of the secondary winding, will be out of phase. See Figure 15-7.

Variants

Core Shapes

The *shell core* is a closed rectangle, as shown in Figure 15-3. This is the most efficient but most costly to manufacture. A C-shaped core is another option (three sides of the rectangle) and an E-I core is popular, consisting of a stack of E-shaped plates with two coils wound around the top and bottom legs of the E, or wound concentrically around the center leg of the E. An additional stack of straight plates is added to close the gaps in the E and form a magnetic circuit.

In Figure 15-8, the small transformer from Figure 15-1 has been sliced open with a band saw and a belt sander to reveal a cross-section of its windings. This clearly shows that its primary and secondary windings are concentric. It also reveals the configuration of its core, which is in the E-I format. In Figure 15-9, the E-I configuration is highlighted to show it more clearly.

Power Transformer

Typically designed to be bolted onto a chassis or secured inside the case or cabinet housing a piece of electrical equipment with solder tabs or connectors allowing wires to connect the transformer to the power cord, on one side, and a cir-



Figure 15-7. *A dot indicates the start of each winding. Where primary and secondary windings are in the same direction, the voltage output will be 180 degrees out of phase with the input. Where the dots indicate windings in opposite directions, the voltage output will have the same phase as the input. Where a center tap on the secondary winding serves as a common ground, the voltages at opposite ends of the secondary winding will be opposite to each other in phase.*

cuit board, on the other side. Smaller power transformers such as the one in Figure 15-1 have "through-hole" design with pins allowing them to be inserted directly onto circuit boards.

Plug-in Transformer

Usually sealed in a plastic housing that can be plugged directly into a wall power outlet. They are visually identical to **AC adapters** but have an AC output instead of a DC output.



Figure 15-8. *The small transformer from the first figure in this entry is shown sliced open to reveal its internal configuration.*



Figure 15-9. *The "EI" shaped plates that form the core of the transformer are outlined to show their edges.*

Isolation Transformer

Also known as a *1:1 transformer* because it has a 1:1 ratio between primary and secondary windings, so that the output voltage will be the same as the input voltage. When electrical equipment is plugged into the isolation transformer, it is separated from the electrical ground of AC power wiring. This reduces risk when working on "live" equipment, as there will be negligible electrical potential between itself and ground. Consequently, touching a grounded object while also touching a live wire in the equipment should not result in potentially lethal current passing through the body.

Autotransformer

This variant uses only one coil that is tapped to provide output voltage. Mutual induction occurs between the sections of the coil. An autotransformer entails a common connection between its input and output, unlike a two-coil transformer, which allows the output to be electrically isolated from the input. See Figure 15-10. Autotransformers are often used for impedance matching in audio circuits, and to provide output voltages that differ only slightly from input voltages.



Figure 15-10. *An autotransformer contains only one coil and core. A reduced output voltage can be obtained by tapping into the coil. A common connection prevents the output from being electrically isolated from the input.*

Variable Transformer

A variable transformer, also known as a *variac*, resembles a wire-wound **potentiometer**. Only one winding is used. A *wiper* can be turned to contact the winding at any point, and serves as a movable tap. Like an autotransformer, a variable transformer entails a common connection between input and output.

Audio Transformer

When a signal is transmitted between two stages of a circuit that have different impedance, the signal may be partially reflected or attenuated. (Impedance is measured in ohms but is different from DC electrical resistance because it takes into account reactance and capacitance. It therefore varies with frequency.)

A device of low input impedance will try to draw significant current from a source, and if the source has high output impedance, its voltage will drop significantly as a result. Generally, the input impedance of a device should be at least 10 times the output impedance of the device that is trying to drive it. Passive components (resistors, and/or capacitors, and/or coils) can be used for impedance matching, but in some situations a small transformer is preferable.

If N_p and N_s are the number of turns of wire in the transformer primary and secondary windings, and Z_p is the impedance of a device (such as an audio amplifier) driving the transformer on its primary side, and Z_s is the impedance of a device (such as a loudspeaker) receiving power from the secondary side:

$$N_p / N_s = \sqrt{(Z_p / Z_s)}$$

Suppose that an audio amplifier with rated output impedance of 640Ω is driving a loudspeaker with 8Ω impedance. A matching transformer would be chosen with a ratio of primary turns to secondary turns give by:

```
√(640/8) = √80 = approximately 9:1
```

The two transformers in Figure 15-11 are through-hole components designed for telecommunications purposes, but are capable of passing audio frequencies and can be used for impedance matching in applications such as a preamplifier.



Figure 15-11. *Through-hole transformers. See text for details.*

In Figure 15-12, the transformers are designed for audio coupling. The one on the right has impedances of 500 ohms (primary) and 8 ohms (secondary). On the left is a fully encapsulated line matching transformer with a 1:1 turns ratio.



Figure 15-12. *Through-hole transformers. See text for details.*

Split-Bobbin Transformer

This variant has primary and secondary coils mounted side by side to minimize capacitive coupling.

Surface-Mount Transformer

May be less than 0.2" square and is used for impedance matching, line coupling, and filtering. Two surface-mount transformers are shown in Figure 15-13.



Figure 15-13. *Two surface-mount transformers, each measuring less than 0.2" square, typically used in communications equipment and suited for frequencies higher than 5 MHz.*

Values

When selecting a power transformer, its power handling capability is the value of primary interest. It is properly expressed by the term VA, derived from "volts times amps." VA should not be confused with watts because watts are measured instantaneously in a DC circuit, whereas in an AC circuit, voltage and current are fluctuating constantly. VA is actually the *apparent power*, taking reactance into account.

The relationship between VA and watts will vary depending on the device under consideration. In a worst-case scenario:

```
W = 0.65 VA (approximately)
```

In other words, the averaged power you can draw from a transformer should be no less than two-thirds of its VA value.

Transformer specifications often include input voltage, output voltage, and weight of the component, all of which are self-explanatory. Coupling transformers may also specify input and output impedances.

How to Use it

For most electronic circuits, a power transformer will be followed by a *rectifier* to convert AC to DC, and **capacitors** to smooth fluctuations in the supply. Using a prepackaged **power supply** or *AC adapter* that already contains all the necessary components will be more time-effective and probably more cost-effective than building a power supply from the ground up. See Chapter 16.

What Can Go Wrong

Reversal of Input and Output

Suppose a transformer is designed to provide an output voltage of 10 volts from domestic AC power of 115 volts. If the wrong side of the transformer is connected with 115VAC by mistake, the output will now be more than 1,000 volts—easily enough to cause death, quite apart from destroying components that are connected with it. Reversing the transformer in this way may also destroy it. Extreme caution is advisable when making connections with power transformers. A meter should be used to check output voltage. All devices containing transformers should be fused on the live side and grounded.

Shock Hazard from Common Ground

When working on equipment that uses an autotransformer, the chassis will be connected through the transformer to one side of 115VAC power. So long as a plug is used that prevents reversed polarity, the chassis should be "neutral." However, if an inappropriate power cord is used, or if the power outlet has been wired incorrectly, the chassis can become live. For protection, before working on any device that uses 115VAC power with an autotransformer, plug the device into an isolation transformer, and plug the isolation transformer into the wall outlet.

Accidental DC Input

If DC current is applied to the input side of a transformer, the relatively low resistance of the primary coil will allow high current that can destroy the component. Transformers should only be used with alternating current.

Overload

If a transformer is overloaded, heat will be generated that may be sufficient to destroy the thin layers of insulation between coil windings. Consequently, input voltage can appear unexpectedly on the output side. Transformers with a toroidal (circular) core are especially hazardous in this respect, as their primary and secondary windings usually overlap.

Some (not all) power transformers contain a thermal fuse that melts when it exceeds a temperature threshold. If the fuse is destroyed, the transformer must be discarded.

The consequences of moderate overloading may not be obvious, and can be cumulative over time. Ventilation or heat sinkage should be taken into account when designing equipment around a power transformer.

Incorrect AC Frequency

Single-phase AC power in the United States fluctuates at 60Hz, but Great Britain and some other countries use AC power at 50Hz. Many power transformers are rated to be compatible with either frequency, but if a transformer is specifically designed for 60Hz, it may eventually fail by overheating if it is used with a 50Hz supply. (A 50Hz transformer can be used safely with 60Hz AC.)

AC-DC power supply

16

Also known as an *AC adapter*. When packaged as a palm-sized plastic package that plugs directly into a power outlet, it is occasionally known colloquially as a *wall-wart*.

OTHER RELATED COMPONENTS

- **transformer** (See Chapter 15)
- **DC-DC converter** (See Chapter 17)
- **DC-AC inverter** (See Chapter 18)

What It Does

An AC-DC power supply converts *alternating current* (*AC*) into the *direct current* (*DC*) that most electronic devices require, usually at a lower voltage. Thus, despite its name, a power supply actually requires an external supply of power to operate.

Larger products, such as computers or stereo equipment, generally have a power supply contained within the device, enabling it to plug directly into a wall outlet. Smaller battery-powered devices, such as cellular phones or media players, generally use an external power supply in the form of a small plastic pod or box that plugs into a wall outlet and delivers DC via a wire terminating in a miniature connector. The external type of power supply is often, but not always, referred to as an *AC adapter*.

Although an AC-DC power supply is not a single component, it is often sold as a preassembled modular unit from component suppliers.

Variants

The two primary variants are a *linear regulated power supply* and *switching power supply*.

Linear Regulated Power Supply

A linear regulated power supply converts AC to DC in three stages:

1. A power **transformer** reduces the AC input to lower-voltage AC.
2. A *rectifier* converts the AC to unsmoothed DC. Rectifiers are discussed in the entry on **diodes** in this encyclopedia.
3. A **voltage regulator**, in conjunction with one or more **capacitors**, controls the DC voltage, smooths it, and removes *transients*. The regulator is properly known as a *linear voltage regulator* because it contains one or more **transistors**, which are functioning in linear mode—that is, responding linearly to fluctuations in base current, at less than their saturation level. The linear voltage regulator gives the linear regulated power supply its name.

A simplified schematic of a linear regulated power supply is shown in Figure 16-1.

This type of power supply may be described as *transformer-based*, since its first stage consists of a transformer to drop the AC input voltage before it is rectified.



Figure 16-1. *A basic linear regulated power supply.*

Because the rectifier in a power supply generally passes each pulse of AC through a pair of silicon diodes, it will impose a voltage drop of about 1.2V at peak current. A smoothing capacitor will drop the voltage by about 3V as it removes ripple from the current, whereas a voltage regulator typically requires a difference of at least 2V between its input and its output. Bearing in mind also that the AC input voltage may fluctuate below its rated level, the output from the power transformer should be at least 8VAC higher than the ultimate desired DC output. This excess power will be dissipated as heat.

The basic principle of the linear regulated power supply originated in the early days of electronic devices such as radio receivers. A transistorized version of this type of power supply remained in widespread use through the 1990s. Switching power supplies then became an increasingly attractive option as the cost of semiconductors and their assembly decreased, and high-voltage transistors became available, allowing the circuit to run directly from rectified line voltage with no step-down power transformer required.

Some external AC adapters are still transformer-based, but are becoming a minority, easily identified by their relatively greater bulk and weight. An example is shown in Figure 16-2.



Figure 16-2. *A simple transformer-based power supply can be encapsulated in a plastic shell, ready to plug into a power outlet. However, today this format more typically contains a switching power supply, which is usually lighter, smaller, and cheaper.*

Figure 16-3 shows the handful of components inside a cheap, relatively old AC adapter. The output from a power transformer is connected directly to four diodes (the small black cylinders), which are wired as a full-wave rectifier. A single electrolytic capacitor provides some smoothing, but because there is no voltage regulator, the output will vary widely depending on the load. This type of AC adapter is not suitable for powering any sensitive electronic equipment.

Switching Power Supply

Also known as a *switched-mode power supply*, an *SMPS,* or *switcher*, it converts AC to DC in two stages.

1. A *rectifier* changes the AC input to unsmoothed DC, without a power transformer.
2. A DC-DC **converter** switches the DC on and off at a very high frequency using *pulse-width modulation* to reduce its average effective voltage. Often the converter will be the *flyback* type, containing a transformer, but the high-frequency switching allows the transformer to be much smaller than the power transformer required in a linear regulated power supply. See the DC-DC **converter** entry in this encyclopedia for an explanation of the working principles.



Figure 16-3. *A relatively old, cheap AC adapter contains only the most rudimentary set of components, and does not supply the kind of properly regulated DC power required by electronic equipment.*

A simplified schematic of a switching power supply is shown in Figure 16-4.

The interior of a relatively early switching power supply designed to deliver 12VDC at up to 4A is shown in Figure 16-5. This supply generated considerable waste heat, necessitating well-spaced components and a ventilated enclosure.

The type of small switching power supply that is now almost universally used to power laptop computers is shown in Figure 16-6. Note the smaller enclosure and the higher component count than in the older power supply shown in Figure 16-5. The modern unit also delivers considerably more power, and generates less waste heat. Although this example is rated at 5A, the transformer (hidden under the yellow wrapper at the center of the unit) is smaller than the power transformer that would have been found in an old-style AC adapter delivering just 500mA.

The modern power supply is completely sealed, where earlier versions required ventilation. On



Figure 16-4. *Greatly simplified schematic showing the principal components of a switching power supply. Note the absence of a 115VAC power transformer. The transformer that is inserted subsequently in the circuit functions in conjunction with the high switching frequency, which allows it to be very much smaller, cheaper, and lighter.*



Figure 16-5. *The interior of an early switching power supply.*

the downside, the plastic case of the switching supply requires a metal liner (removed for this photograph) to contain high-frequency electromagnetic radiation.

Unregulated Power Supply

Typically this consists of a transformer and rectifying diodes with little or no smoothing or voltage control of the output.

Adjustable Power Supply

This is usually a linear power supply incorporating an adjustable **voltage regulator**. This type of supply has laboratory applications and is found as a benchtop item to power electronics design projects during their development.



Figure 16-6. *The interior of the type of switching power supply that powers a laptop computer.*

Voltage Multiplier

Devices such as photocopiers and laser printers, televisions, cathode-ray tubes, and microwave ovens require voltages significantly higher than those supplied by domestic AC power outlets. A voltage multiplier usually contains a step-up transformer followed by DC conversion components, but detailed consideration is outside the scope of this encyclopedia.

Formats

An *open frame* power supply consists of components on a circuit board, usually mounted on a metal chassis, with no enclosure or fan cooling.

A *covered* power supply is enclosed in a protective perforated metal box with a cooling fan if needed. Power supplies sold for desktop computers are usually in this format.

Power supplies are also available in rack-mount and DIN-rail formats.

How to Use it

Because a switching power supply contains no power transformer, it is lighter and smaller, and may be cheaper than a linear power supply. It is also more efficient and generates less waste heat. These advantages have made switching power supplies the most popular option to provide DC power for electronics devices. However, the high-frequency switching tends to create *electromagnetic interference* (*EMI*), which must be filtered to protect the output of the device and also to minimize the risk of this interference feeding back into AC power wiring. The high-frequency switched power may also generate harmonics, which must be suppressed.

High-quality linear regulated power supplies still find application in laboratory equipment, low-noise signal processing, and other niches where excellent regulation and low-ripple output are necessary. They are relatively heavy, bulky, and inefficient.

See Figure 16-7 for a chart comparing the advantages and disadvantages of linear and switching power supplies.

What Can Go Wrong

High Voltage Shock

One or more capacitors in a power supply may retain a relatively high voltage for some time after the unit has been unplugged. If the power supply is opened for inspection or repairs, caution is necessary when touching components.

Capacitor Failure

If *electrolytic capacitors* fail in a switching power supply (as a result of manufacturing defects, disuse, or age), allowing straight-through conduction of alternating current, the high-frequency switching semiconductor can also fail, allowing input voltage to be coupled unexpectedly to the output. Capacitor failure is also a potential problem in linear power supplies. For additional information on capacitor failure modes, see Chapter 12.

	Switching power supply	Linear power supply
Component count	High	Medium
Load regulation	0.05% to 0.5%	0.005% to 0.2%
Line regulation	0.05% to 0.2%	0.005% to 0.05%
Ripple (RMS)	10mV to 25mV	0.25mV to 1.5mV
Efficiency	70% to 85%	40% to 60%
EMI	High	Very low
Leakage	High	Low
Physical size	Small	Large
Weight	Light	Heavy
Heat management	Usually fan-cooled	Usually cooled by convection

Figure 16-7. *Comparison of attributes of linear regulated power supplies and switching power supplies. (Adapted from Acopian Technical Company.)*

Electrical Noise

If *electrolytic capacitors* are used, their gradual deterioration over time will permit more electrical noise associated with high-frequency switching in a switching power supply.

Peak Inrush

A switching power supply allows an initial inrush or surge of current as its capacitors accumulate their charge. This can affect other components in the circuit, and requires fusing that tolerates brief but large deviations from normal power consumption.

DC-DC converter

17

Often referred to as a *switching regulator*, and sometimes as a *switcher*, not to be confused with a *switching power supply*.

OTHER RELATED COMPONENTS

- **AC-DC power supply** (See Chapter 16)
- **voltage regulator** (See Chapter 19)
- **DC-AC inverter** (See Chapter 18)

What It Does

A DC-DC converter, often referred to simply as a *converter*, receives a DC voltage as its input and converts it to a regulated DC voltage as its output. The output voltage may be higher or lower than the input voltage, may be user-adjustable by adding an external resistor, and may be completely electrically isolated from the input, depending on the type of converter that is used. The overall efficiency is not greatly affected by the difference between input and output voltage, and can exceed 90%, minimizing waste heat and enabling the unit to be extremely compact.

A DC-DC converter is an integrated circuit package that includes a high-speed switching device (almost always, a *MOSFET*) in conjunction with an oscillator circuit, an inductor, and a diode. By comparison, a **linear regulator** is usually based around bipolar transistors. Its input must always be at a higher voltage than its output, and its efficiency will be inversely proportional with the voltage drop that it imposes. See the **voltage regulator** entry in this encyclopedia for additional information.

There is no single symbol to represent a DC-DC converter. Some simplified schematics showing the principles of operation of commonly used converters are referenced under the following Variants section.

A DC-DC converter is also typically found in the output stage of a switching **AC-DC power supply**.

How It Works

An internal oscillator controls a *MOSFET* semiconductor that switches the DC input on and off at a high frequency, usually from 50KHz to 1MHz. Output voltage is adjusted by varying the *duty cycle* of the oscillator—the length of each “on” pulse relative to each “off” interval. This is known as *pulse-width modulation*, or *PWM*. The duty cycle is controlled by sampling the output of the converter and using a comparator to subtract the output voltage from a reference voltage, to establish an error value. This is passed to another comparator, which subtracts the error voltage from an oscillator ramp signal. If the error increases, the oscillator signal is more heavily clipped, thus changing the effective ratio of on/off pulse lengths. A simplified schematic of the PWM circuit is shown in Figure 17-1, which omits other components for clarity. The system of subtracting an error voltage from a ramp oscillator voltage to obtain a pulse-width modulated signal is illustrated in Figure 17-2.



Figure 17-1. *The heart of a DC-DC converter is a MOSFET switch, which operates at a high frequency with pulse-width modulation used to create an adjustable DC output.*



Figure 17-2. *To achieve pulse-width modulation, an error-level voltage is established by comparing the output from the converter with a reference voltage. The error level, shown as an orange line, is then subtracted from the output from a ramp oscillator. The pulse width varies accordingly.*

The key to the efficiency of a DC-DC converter is an inductor, which stores energy in its magnetic field during "on" pulse and releases it in the discharge phase. Thus, the inductor is used as a temporary reservoir and minimizes the ripple current. All converter variants use a coil for this purpose, although its placement varies in relation to the diode and capacitor that complete the basic circuit.

Variants

Four basic switching circuits are used in DC-DC converters and are defined in the coming sections, with a formula to determine the ratio between input voltage (V_{in}) and output voltage (V_{out}) in each case. In these formulae, variable D is the duty cycle in the pulse train generated through an internal MOSFET switch. The duty cycle is the fraction of the total on-off cycle that is occupied by each "on" pulse. In other words, if T_{on} is the duration of an "on" pulse and T_{off} is the "off" time:

$$D = T_{on} / (T_{on} + T_{off})$$

Buck Converter

See Figure 17-3. The output voltage is lower than the input voltage. The input and output share a common ground. For this circuit:

$$V_{out} = V_{in} * D$$



Figure 17-3. *Basic topology of a buck-type DC-DC converter.*

Boost Converter

See Figure 17-4. The output voltage is greater than the input voltage. The input and output share a common ground. For this circuit:

$$V_{out} = V_{in} / (1-D)$$



Figure 17-4. *Basic topology of a boost-type DC-DC converter.*

Flyback Converter with Inductor

Commonly known as a *buck-boost converter*. See Figure 17-5. The output voltage can be less than or greater than the input voltage. The input and output share a common ground. For this circuit:

$$V_{out} = V_{in} * (D / (1-D))$$



Figure 17-5. *Basic topology of a flyback-type DC-DC converter.*

Flyback Converter with Transformer

See Figure 17-6. The output voltage can be less than or greater than the input voltage. The input and output are isolated from one another. For this circuit:

$$V_{out} = V_{in} * (D / (1-D))$$



Figure 17-6. *Basic topology of a flyback-type DC-DC converter. (Buck, boost, and flyback topologies adapted from Maxim Integrated Products.)*

Using a transformer in the converter allows multiple outputs with different voltages, supplied through multiple transformer windings.

Formats

A converter may be packaged in a flat rectangular box that requires no additional heat sink and has pins for through-hole insertion into a PC board. Sizes usually range up to to 2" × 2". Power handling can range from 5 to 30 watts. Converters of this type are shown in Figure 17-7. (Top: Input range of 9 to 18VDC, fixed output of 5VDC at 3A completely isolated from the input. Typical efficiency of approximately 80%. The case is made of copper, providing good heat dissipation with electrical shielding. Center: Input range of 9 to 18VDC, fixed output of 5VDC at 500mA completely isolated from the input. Typical efficiency of approximately 75%. The manufacturer claims that external capacitors are only needed in critical applications. Bottom: SIP format, fixed input of 12VDC, fixed output of 5VDC at 600mA completely isolated from the input. Typical efficiency of approximately 75%. Requires external capacitors for ripple rejection.)



Figure 17-7. *A selection of sealed DC-DC converters.*

Lower-power converters are also available as surface-mount devices.

Some adjustable-output converters are supplied as multiple surface-mounted components preinstalled on a mini-board that has pins for through-hole insertion in a printed circuit board. Their high efficiency enables them to handle a lot of power for their size. In Figure 17-8, the converter accepts a 4.5 to 14VDC input range and has an adjustable output of 0.6 to 6VDC. It is rated at a surprising 10A or 50W and is more than 90% efficient. However, it draws 80mA in a no-load state, causing it to become quite hot. A thermal cutout or automatic shutdown may be used if the converter will not be driving a consistent load.



Figure 17-8. *An adjustable DC-DC converter rated for 10A or 50W. The output voltage is determined by adding an external resistor or trimmer potentiometer. External smoothing capacitors are required, as shown in the component's datasheet.*

The miniboard in Figure 17-9 accepts an input voltage from 7 to 36VDC and has an adjustable output ranging from 2.5 to 12.6VDC, at up to 6A. It is non-isolated (has a common negative bus) and claims to be more than 95% efficient at full load.

The miniboard in Figure 17-10 accepts an input voltage from 4.5 to 14VDC and has an adjustable output ranging from 0.6 to 6VDC at up to 20A. It is non-isolated (has a common negative bus) and claims to be more than 90% efficient at full load.

Values

Relevant values include:

Nominal Input Voltage and Frequency

A wide range of input voltages is often acceptable, as the PWM can vary accordingly. Converters



Figure 17-9. *Another adjustable DC-DC converter. The output voltage is determined by adding an external resistor or trimmer potentiometer. External smoothing capacitors are required, as shown in the component's datasheet.*



Figure 17-10. *Another adjustable DC-DC converter. The output voltage is determined by adding an external resistor or trimmer potentiometer. External smoothing capacitors are required, as shown in the component's datasheet.*

often allow equipment to be usable internationally, on any voltage ranging from 100VAC to 250VAC, at a fequency of 50Hz or 60Hz, without any adaptation.

Output Voltage

As previously noted, many converters allow the output voltage to be adjusted by adding an external resistor or potentiometer. Alternatively, there may be multiple fixed output voltages, accessible via different pins on the package. They may also provide a positive voltage and equally opposite negative voltage relative to a ground pin.

Input Current and Output Current

Because input voltage and output voltage are likely to be different, the current alone is not a reliable guide to power handling.

A datasheet should specify input current with no load (open circuit on the output side). This current will have to be entirely dissipated as heat.

Load Regulation

This is usually expressed as a percentage and suggests the extent to which output voltage may be pulled down when the load on a DC-DC converter increases. If V_{nil} is the measured output voltage with no load, and V_{max} is the measured output voltage with the maximum rated load:

$$\texttt{Load regulation} = 100 * (V_{nil} - V_{max})/V_{max}$$

However, note that some converters are designed with the expectation that they will never be used with zero load across the output. In these cases, V_{nil} will be the voltage at minimum rated load.

Efficiency

This is a measure of how much input current must be dissipated as heat. A converter with a 12-volt input, drawing a maximum 300mA input current, will consume 3.6 watts (3,600mW). If it is 80% efficient, it will have to dissipate roughly 20% of its power as heat, or 720mW.

Ripple and Noise

Sometimes abbreviated R/N, this may be measured in mV or as a percentage. Check the specification carefully to determine whether the ripple-and-noise values require use of external smoothing capacitors. Often, this is the case.

Isolated or Non-Isolated

This crucial piece of information is often found near the top of a datasheet, not in the detailed specifications.

How to Use it

Because a converter creates electrical noise, it should be prevented from affecting other components by adding substantial *bypass capacitors* as close as possible to its input and output pins. For most converters, external capacitors are mandatory, and their *effective series resistance* (ESR) should be as low as possible (see the **capacitor** entry in this encyclopedia for an explanation of ESR). Tantalum capacitors are preferable to electrolytics for this reason, and are also more durable. Some manufacturers recommend placing a tantalum capacitor in parallel with an electrolytic. A small ceramic capacitor, typically 0.1 µF, is often recommended in an addition to larger-value capacitors on the output side.

The voltage rating of each capacitor should be twice the voltage at the point in the circuit where it is used. The capacitance value will usually be higher for higher-current converters. Values of 100µF are common, but for high amperage, a value may be as high as 1,000µF.

While datasheets are often inadequate for some types of components, datasheets for DC-DC converters usually include detailed instructions regarding bypass capacitors. Following these instructions is essential. In the relatively rare instances that a datasheet makes no mention of bypass capacitors for a converter, this does not necessarily mean that the capacitors are unnecessary. The manufacturer may assume that they will be used as a matter of course.

Converters are used in a very wide range of devices, supplying power ranging from a few milliamps to tens of amps. At the lower end of the scale, devices such as cellular telephones, portable computers, and tablets contain subcircuits that require different voltages, some of which may be higher than the voltage of a single battery or battery pack that powers the device. A converter can satisfy this requirement. Because a converter can be designed to maintain a fixed output in response to a range of input voltages, it can also compensate for the gradual decline in voltage that occurs during battery usage.

A boost-type converter can be used to double the voltage from a single 1.5V battery in an LED flashlight where 3 volts are required to power the LED. Similarly, a boost-type converter can provide the necessary voltage to run a cold-cathode fluorescent tube that provides backlighting in an LCD computer display.

On a circuit board that is primarily populated with 5VDC components and is fed by a single 5VDC power supply, a converter can be used to supply 12VDC for one special purpose, such as an analog-digital converter or a serial data connection.

If electromechanical **relays** or other inductive loads share a common ground with components ,such as *logic chips* or **microcontrollers**, it may be difficult to protect the sensitive components from voltage spikes. A A flyback converter with a transformer separating the output from the input can allow the “noisy” section of the circuit to be segregated, so long as the converter itself does not introduce noise. Since the electromagnetic interference (EMI) introduced by converters varies widely from one model to another, specifications should be checked carefully.

Very low-power components can pick up EMI from the wires or traces leading into and out of a converter. In this type of circuit, adequate noise suppression may be impossible, and a converter may not be appropriate.

What Can Go Wrong

Electrical Noise in Output

Electrolytic capacitors may be inadequate to smooth the high frequencies used. Multilayer ceramic capacitors or tantalum capacitors may be necessary. Check the manufacturer's datasheet for minimum and maximum values. Also check the datasheet for advice regarding placement of capacitors on the input side as well as across the output.

Excess Heat with No Load

Some converters generate substantial heat while they are powered without a load. The manufacturer's datasheet may not discuss this potential problem very prominently or in any detail. Check the input rating, usually expressed in mA, specified for a no-load condition. All of this current will have to be dissipated as heat, and the very small size of many converters can result in high localized temperatures, especially since many of them allow no provision for a heat sink.

Inaccurate Voltage Output with Low Load

Some converters are designed to operate with at least 10% of full rated load across their output at all times. Below this threshold, output voltage can be grossly inaccurate. Read datasheets carefully for statements such as this: "Lower than 10% loading will result in an increase in output voltage, which may rise to typically double the specified output voltage if the output load falls to less than 5%." Always use a meter to verify the output voltage from a converter at a variety of different loads, and perform this test before installing the converter in a circuit.

DC-AC inverter

18

A power inverter must not be confused with a *logic inverter*, which functions as a digital component in *logic circuits* to invert the state of a low-voltage DC input from high to low or low to high. Logic inverters are discussed in Volume 2.

OTHER RELATED COMPONENTS

- **AC-DC power supply** (See Chapter 16)
- **DC-DC converter** (See Chapter 17)

What It Does

A power inverter is included here as counterpoint to a **power supply** or *AC adapter*, since it has the opposite function. The inverter receives an input of *direct current* (typically 12VDC from a car battery) and delivers an output of *alternating current* (AC) in the range 110VAC-120VAC or 220VAC-240VAC, suitable to power many low-wattage appliances and devices. The interior of a low-cost inverter is shown in Figure 18-1.



Figure 18-1. *The interior components in a 175-watt inverter.*

How It Works

The first stage of an inverter typically raises a 12VDC input to a higher DC voltage via an internal **DC-DC converter**, then uses a switching circuit to create an approximation of the sinusoidal profile that is characteristic of AC voltage.

Digital switching components naturally tend to create square waves, whose simple appearance conceals the presence of higher frequencies, or *harmonics*, that are ignored by some devices (especially those that convert electricity into heat) but can be troublesome in consumer electronics equipment. A primary objective of inverter design is to adapt or combine square waves to emulate a classic AC sine wave with reasonable fidelity. Generally speaking, the more accurately an inverter emulates a sine wave, the more expensive it tends to be.

The most primitive inverter would create a plain square wave such as that shown in red in Figure 18-2, superimposed on a comparable sine wave (in green). Note that alternating current rated at 115 volts actually peaks at around 163 volts because the number 115 is the approximate *root mean square* (*RMS*) of all the voltage values during a single positive cycle. In other words, if the voltage is sampled x times during a cycle, an

RMS value can be derived by squaring each sample, adding all the samples, dividing by x, and then taking the square root of the result. The RMS value is important as a means to calculate actual power delivered because it can be multiplied by the current to obtain an approximate value in watts.



Figure 18-2. *Comparison of an AC voltage sine wave (green) and a square wave of the same frequency (red), both delivering a roughly similar amount of power.*

Variants

As a first step toward a better approximation of a sine wave, gaps of zero voltage can be inserted between square-wave pulses. This "gapped" square wave is shown in Figure 18-3.



Figure 18-3. *Introducing pauses or gaps of zero voltage between square-wave pulses can produce slightly improved resemblance to a sine wave.*

A further improvement can be achieved if an additional, shorter pulse of higher voltage is added to each primary pulse, as shown in Figure 18-4. Outputs of this kind are referred to as *modified sine wave*, although they are actually square waves modified to emulate a sine wave. Their inaccuracy is expressed as *total harmonic distortion* (*THD*). Some authorities estimate that the THD of gapped square-wave output is around 25%, whereas the addition of shorter square waves reduces this to around 6.5%. This is a topic on which few people agree, but there is no doubt that a "stacked" sequence of square waves provides a closer emulation of a sine wave.



Figure 18-4. *A secondary stream of narrower square-wave pulses can improve the fidelity of an inverter's output.*

A *true sinewave inverter* typically uses *pulse-width modulation* (*PWM*) to achieve THD of less than 1%. It generates a stream of pulses much higher in frequency than that of the AC output, and varies their widths in such a way that their averaged voltage closely approximates the voltage variations in a sine wave. A simplified representation of this principle is shown in Figure 18-5.

Values

Small inverters are typically rated to deliver up to 100 watts and may be fitted with a 12VDC plug for insertion in a vehicle's cigarette lighter. Since a cheap inverter may be only 80% efficient, 100 watts at 135VAC will entail drawing as much as



Figure 18-5. *Pulse-width modulation adjusts the widths of pulses delivered at a high frequency. The pulse widths can be averaged to generate voltage that follows a close approximation of a sine wave.*

10 amps at 12VDC. Cigarette lighters are usually fused at 15 or 20 amps, so 100 watts is a reasonable value. Inverters that are rated above 150 watts usually have cables terminating in oversize alligator clips for direct connection to the terminals of a 12V battery.

While the *cold cranking* rating of a car battery may be 100 amps or more, the battery is only designed to deliver that power for up to 30 seconds at a time. Inverters rated for as much as 500 watts will exceed the normal capacity of a single car battery, although if the battery is mounted in a vehicle, it can be supplemented by running the engine so that the alternator shares some of the load. A 500-watt inverter is better supplied by two or more 12-volt car batteries wired in parallel.

How to Use it

Small inverters are typically used in vehicles to run cellphone chargers, music players, or laptop computers. Large inverters are an integral part of off-the-grid solar and wind-powered systems, where battery power must be converted to AC house current. Uninterruptible power supplies contain batteries and inverters capable of running computer equipment for a brief period. Battery-driven electric vehicles with AC motors use inverters with an exceptionally high current rating.

There is a lack of consensus regarding possible harmful effects of powering electronics equipment with a low-cost modified sine wave inverter. Anecdotal evidence suggests that where the equipment uses its own *switching power supply* or uses an *AC adapter* (either mounted internally or as an external plug-in package), the filtering built into the power supply will block harmonics from the inverter.

Other evidence suggests that cheap inverters may have adverse effects on devices containing synchronous motors that run direct from AC. There are reports that fluorescent lighting and photographic electronic flash systems may be unsuitable for use even with modified sine wave inverters. However, differences in product design and component quality make it impossible to generalize. A cheaply made inverter may generate a wave form that is not even a close approximation of a square wave. See Figure 18-6.



Figure 18-6. *A cheaply made inverter can generate a distorted wave form that is even higher in noise than a pure square wave. This sample is adapted from an actual oscilloscope trace.*

What Can Go Wrong

If multiple batteries are connected in parallel, using suitably heavy-gauge wire to power a large inverter, the batteries must be identical in specification and age, and must all be equally charged to prevent high and potentially dangerous flows of current among the batteries as they attempt to reach an equilibrium among themselves. Interconnections must be firmly clamped to clean battery terminals. For additional information, see the **battery** entry in this encyclopedia.

Problems associated with inverters are likely to be mundane. A 12V wiring to the inverter can overheat if items such as clothes or bedding are left on top of it; a high-wattage fan-cooled inverter can overheat if the fan is obstructed by poor placement or impaired by accumulated dirt; alligator clips may become dislodged from battery terminals; and power surges drawn by inductive loads such as motors may trigger the inverter's *breaker*, especially if they are used in conjunction with other equipment.

As always, high amperage should be treated with caution and respect, regardless of it being delivered at "only 12 volts."

voltage regulator

19

Correctly known as a *linear voltage regulator* to distinguish it from a *switching regulator* or **DC-DC converter**. However, the full term is not generally used, and "voltage regulator" is normally understood to mean a linear voltage regulator.

OTHER RELATED COMPONENTS

- **DC-DC converter** (See Chapter 17)
- **AC-DC power supply** (See Chapter 16)

What It Does

A linear voltage regulator provides a tightly controlled DC output, which it derives from an unregulated or poorly regulated DC input. The DC output remains constant regardless of the load on the regulator (within specified limits). It is a cheap, simple, and extremely robust component.

There is no single schematic symbol for a linear voltage regulator.

The general physical appearance of a commonly used type of regulator, rated for an output of around 1A DC, is shown at Figure 19-1. The LM7805, LM7806, LM7812, and similar regulators in the LM78xx series are encapsulated in this type of package, with pins that are spaced at 0.1" and have functions as shown. Other types of regulator may differ in appearance, or may look identical to this one but have different pin functions. Always check datasheets to be sure.

How It Works

All linear regulators function by taking some feedback from the output, deriving an error value by comparing the output with a reference voltage (most simply provided by a zener diode), and using the error value to control the base of a *pass transistor* that is placed between the input and the output of the regulator. Because the transistor operates below saturation level, its output current varies linearly with the current applied to its base, and this behavior gives the linear regulator is name. Figure 19-2 shows the relationship of these functions in simplified form; Figure 19-3 shows a little more detail, with a *Darlington pair* being used as the pass transistor. The base of the pair is controlled by two other transistors and a comparator that delivers the error voltage. This version of a voltage regulator is known as the *standard type*.

The voltage difference required between the base and emitter of an NPN transistor is a minimum of 0.6V. Because multiple transistors are used inside a standard-type voltage regulator, it requires a minimum total voltage difference, between its input and its output, of 2VDC. This voltage difference is known as the *dropout voltage*. If the voltage difference falls below this minimum, the regulator ceases to deliver a reliable output voltage until the input voltage rises again. *Low dropout regulators* allow a lower voltage difference, but are more expensive and less commonly used. They are described under the following Variants section.



Figure 19-1. *The package design of a commonly used voltage regulator. Others may be significantly different, and the pin functions may vary. Check manufacturer datasheets for details.*

Discrete components could in theory be used to build a voltage regulator, but this ceased to be cost-effective several decades ago. The term is now understood to mean one small integrated package containing the basic circuit augmented with additional, desirable features, such as automatic protection against overload and excessive heat. Instead of burning out if it is overloaded, the component simply shuts down. Most voltage regulators also tolerate accidentally reversed power connection (as when batteries are inserted the wrong way around) and accidentally reversed insertion of the regulator in a circuit board.

Other components can satisfy the requirement to deliver power at a reduced voltage. Most simply, if two resistors in series are placed across a



Figure 19-2. *A linear voltage regulator basically consists of a transistor whose base is controlled by corrective feedback derived from the output.*



Figure 19-3. *The fundamental internal features of a standard-type voltage regulator, including a Darlington pair, two transistors, a voltage divider, comparator, and reference voltage source, shown inside the dashed white line.*

power source, they form a *voltage divider*, which provides an intermediate voltage at the connection between them. However, this voltage will vary depending on fluctuations in the input voltage and/or load impedance. A voltage regulator is the simplest way to supply a voltage that remains stable regardless of excursions in the input or fluctuations in power consumed by the load.

The disadvantage of a standard-type voltage regulator is that it is inefficient, especially when a relatively high input voltage is used to deliver a relatively low output voltage. If V_{in} is the input voltage, V_{out} is the output voltage, and I_{out} is the output current, the average power loss, P, is given by the formula:

$$P = I_{out} * (V_{in} - V_{out})$$

For example, if the output current is 1A, the input voltage is 9VDC, and the output is 5VDC, 44% of the input power will be wasted, and the component will be only 56% efficient. The wasted power (about 4 watts, in this case) will be dissipated as heat. Even when a standard-type regulator runs at its minimum 2VDC dropout voltage, it must dissipate 1W when delivering 0.5A.

Variants

Packaging

The package for the LM78xx series of regulators, shown in Figure 19-1, incorporates an aluminum plate drilled with a hole so that it can be bolted to a heat sink. Voltage regulators with a lower rated maximum output current (typically, 100mA) do not have the same need for a heat sink, and are available in a package that resembles a small transistor.

Some integrated circuits are available containing two voltage regulators, electrically isolated from each other.

Popular Varieties

In the LM78xx series, the last two digits in the part number specify the output voltage, which is fixed. Thus the LM7805 delivers 5VDC, the LM7806 delivers 6VDC, and so on. For regulators with a fractional voltage output (3.3VDC being common), an additional letter may be inserted in the part number, as in the 78M33.

Many copies of the LM78xx series are made by different manufacturers, the copies being functionally identical, regardless of additional letters that are added to the part number to identify its source or other attributes.

The LM78xx regulators are mostly rated to be accurate within 4%, although actual samples almost always deliver voltages that are more precise than this range suggests.

Adjustable Regulators

While the majority of regulators have a fixed output, some allow the user to set the output by adding one or more resistors. The LM317 is a popular example. Its output voltage can range from 1.25VDC to 37VDC and is set via a resistor and a trimmer potentiometer, as illustrated in Figure 19-4. If R1 is the fixed-value resistor and R2 is the trimmer, as shown in the schematic, the output voltage, V_{out}, is given by the formula

$$V_{out} = 1.25 * (1 + (R2 / R1))$$

Typical values for R1 and R2 would be 240Ω and 5K, respectively. With the trimmer at the middle of its range, V_{out} would be 1.25 * (1 + (2500 / 240)) = approximately 15VDC, requiring an input of at least 17VDC. However, if the trimmer is reduced to 720Ω, the output would be 5VDC. In practice, the value of a trimmer should be chosen so that a mid-range setting provides approximately the desired output. This will enable fine adjustment of the output voltage.

While the versatility of an adjustable regulator is desirable, its overall power dissipation is still proportional to the difference between the input voltage and the output voltage. To minimize heat loss, this difference should not exceed the dropout voltage by a larger amount than is absolutely necessary.

An adjustable regulator may require larger bypass capacitors than a regulator with a fixed output. A manufacturer's recommendations for the LM317 are shown in Figure 19-4.

Negative and Positive Regulators

While most linear voltage regulators are designed for "positive input" (conventional current flow from input to output), some are intended for "negative input." In this variant, the common terminal is positive, and the input and output are negative in relation to it.



Figure 19-4. *Schematic for the LM317L adjustable voltage regulator, based on a circuit recommended by National Semiconductor, with bypass capacitors added for ripple rejection.*

Low-Dropout Linear Regulators

Low-dropout regulators (sometimes referred to as *LDO* regulators) allow a much lower dropout voltage by using a single PNP or MOSFET transistor. LDO regulators are popularly used in battery-powered devices where efficiency should be maximized and heat dissipation should be minimized. For example, the LM330 is a regulator with a 5VDC output, tolerating a dropout voltage of 0.6V, allowing it to be used with four AAA cells. In an LDO regulator the dropout voltage actually varies with load current and may diminish to as little as one-tenth of its rated value when the output current is minimal.

The majority of low-dropout regulators are sold in surface-mount packages, and are designed for maximum output of 100mA to 500mA. Only a few exceptions exist. They tend to be slightly more expensive than regulators with the typical 2V dropout rating.

Three voltage regulators are shown in Figure 19-5. From left to right, they are rated 5VDC at 1A, 12VDC at 1A, and 5VDC at 7.5A. The two smaller regulators are of the LM78xx series. The larger regulator claims a low maximum dropout voltage of 1.5VDC, and its output voltage can be adjusted with an external potentiometer and resistor.



Figure 19-5. *Two voltage regulators from the LM78xx series, and a third high-current, low-dropout, adjustable regulator rated 5VDC (adjustable upward) at 7.5A.*

Quasi-Low-Dropout Linear Regulators

Where a standard regulator uses a Darlington pair as the pass transistor and an LDO uses a single PNP transistor, the so-called Quasi-LDO uses a combination of NPN and PNP transistors and has an intermediate dropout voltage, typically a maximum of 1.5VDC. However, the terms LDO and Quasi-LDO are not used uniformly in the industry. One manufacturer markets Quasi-LDO regulators as LDO regulators, and describes its LDO regulators as *Very Low Dropout* regulators. Consult datasheets to determine the actual specification of the product, regardless of its classification.

Additional Pin Functions

Some voltage regulators include an extra pin, typically known as an *enable pin*, which switches off the device in response to a signal from a microcontroller or logic gate.

Some regulators offer another option, an additional *status pin* that can signal a microcontroller that an error mode exists if the regulator output falls significantly below its rated value.

In battery-powered devices, a low-battery sensor is a desirable feature, since a regulator may simply shut down without warning if the input voltage is insufficient. A few regulators, such as the LP2953, provide a low-battery warning output via an extra pin.

Values

Linear voltage regulators with a single, fixed output are commonly available to supply DC outputs of 3.3, 5, 6, 8, 9, 10, 12, 15, 18, and 24 volts, with a few variants offering fractional values in between. The most commonly used values are 5, 6, 9, 12, and 15 volts. The input voltage may be as high as 35VDC.

Maximum output current is typically 1A or 1.5A, in the traditional three-pin, through-hole, TO-220 format. A surface-mount version is available. Other surface-mount formats have lower power limits.

Accuracy may be expressed as a percentage or as a figure for load regulation in mV. A typical load regulation value would be 50mV, while voltage regulation accuracy ranges from 1% to 4%, depending on the manufacturer and the component. While low-dropout regulators are generally more efficient, they do require more ground-pin current. This is not usually a significant factor.

How to Use it

Some components, such as many old-design CMOS chips or the traditional TTL version of the 555 timer, allow a wide range of acceptable input voltages, but most modern logic chips and microcontrollers must have a properly controlled power supply. Regulators such as the LM7805 are traditionally used to provide this, especially in small and relatively simple devices that draw a moderate amount of current, have a low component count, and are powered via a battery or an **AC adapter**. A fully fledged switching power supply is overkill in this kind of application.

A linear voltage regulator cannot respond instantly to changes in input voltage. Therefore, if the input supply contains voltage spikes, these spikes may pass through the regulator. Bypass capacitors should be applied preventively. A sample schematic showing an LM7805 regulator with bypass capacitors recommended by a manufacturer is shown in Figure 19-6.

In a battery-powered device where standby power is required for long periods and full power is only needed intermittently, the *quiescent current* drawn by a minimally loaded voltage regulator is important. Modern LDO regulators may draw as little as 100µA when they are very lightly loaded. Other types may consume significantly more. Check datasheets to find the most appropriate component for a particular application.



Figure 19-6. *Typical schematic for use of an LM7805 regulator, with capacitor values based on recommendations from Fairchild Semiconductor.*

Note that DC-DC power **converters** may draw a lot of current when they are lightly loaded, and will dissipate large amounts of heat as a result. An LDO is therefore preferable in this situation.

What Can Go Wrong

Inadequate Heat Management

The ability to "dial up" a wide range of voltages from an adjustable regulator such as the LM317 can be a temptation to use it on a "one size fits all" basis, to deliver any output ranging from 5VDC to 18VDC from a uniform 24VDC input. Assuming 1A output current, the worst-case power dissipation in this scenario would be almost 20W. To achieve reasonable efficiency and maintain waste heat at a manageable level, the input voltage should not exceed the output voltage by much more than the dropout voltage.

Even when a voltage regulator is used correctly, it can generate more heat than was expected if the requirements of a circuit are altered during development. An initial handful of components may draw only 100mA, but as more capabilities are requested and more parts are added (especially relays or LED displays) the power consumption can quickly add up, generating an unexpected amount of waste heat and raising the possibility of a sudden (and mysterious) shutdown if the regulator does not have an adequate heat sink.

Transient Response

When there is a major fluctuation in the demand by the load (for example, if an inductive device is switched on elsewhere in the circuit), the voltage regulator requires a finite time to adjust itself and maintain its specified output voltage. This time lag is known as its *transient response*. If a momentary fluctuation is likely, and other components may be sensitive to it, a larger capacitor should be used between the output of the voltage regulator and ground.

The transient response time may also be insufficient to block sudden, brief spikes in input voltage. This may occur, for example, when a low-cost AC adapter that does not have a properly smoothed output is used as the power source. Additional 1µF bypass capacitors may be added at the input and output of a regulator to provide better protection from power fluctuations.

Misidentified Parts

Many types of linear voltage regulators appear physically identical. Care is needed to distinguish those which have fixed output from those that allow a variable output. When using the LM78xx series, double-check the last pair of digits in the part number, which provide the only guide regarding the output. Using an LM7808 instead of an LM7805 may be sufficient to destroy all the 5VDC chips in a logic circuit. It is advisable to use a meter to check the output of any power supply before connecting it with a circuit.

Misidentified Pins

The LM78xx series of voltage regulators uses a very intuitively obvious and consistent scheme for the functions of its pins: input on the left, ground in the center, and output on the right, when looking at the regulator from the front, with its pins facing downward. Unfortunately the consistency of this scheme can encourage an unthinking habit for making connections. The LM79xx series of negative voltage regulators swaps the identity of the input and ground pins, whereas adjustable regulators use yet another different scheme. Good practice suggests checking a component against the manufacturer's datasheet before connecting it.

Dropout Caused by Low Battery

If a regulator rated to deliver 6VDC has a 2VDC dropout voltage and is powered from a 9V battery, the battery can easily drop below the minimum acceptable 8VDC if it becomes old or depleted. When this happens, the output from the regulator will tend to fall, or may oscillate.

Inaccurate Delivered Voltage

A voltage regulator maintains its output voltage between its output pin and ground pin. Thin traces on a circuit board, or a long run of very small-gauge wiring, can impose some electrical resistance, reducing the actual voltage delivered to a component. Ohm's Law tells us that the voltage drop imposed by a trace (or thin wire) will be proportional to the current flowing through it. For example, if the resistance between the output pin of a voltage regulator and a component is 0.5Ω and the current is 0.1A, the voltage drop will be only 0.05V. But if the current increases to 1A, the voltage drop is now 0.5V. Bearing this in mind, a linear voltage regulator should be positioned close to voltage-sensitive components. In printed circuit designs, the traces that deliver power should not have significant resistance.

When using linear voltage regulators with adjustable output, there may be a temptation to connect adjustment resistor R1 to the positive end of the load, to obtain a "more accurate" delivered voltage. This configuration will not produce the desired result. R1 should always be connected as closely as possible between the output pin and the adjustment pin of the voltage regulator, while R2 should connect between the adjustment pin and the negative end of the load. This is illustrated in Figure 19-7, where the gray wire in each schematic indicates that it possesses significant resistance.



Figure 19-7. *When the connection between an adjustable-output voltage regulator and load components has a significant resistance (shown here as a gray "resistive wire"), R1 should always be connected as closely as possible to the pins of the regulator, as shown in the upper schematic. (Derived from schematics prepared by National Semiconductor.)*

electromagnet

20

The term **electromagnet** is used here to mean a coil containing a core of ferromagnetic material that does not move relative to the coil. The core is used solely to create a magnetic field that attracts or repels other parts that have appropriate inherent magnetic properties. Where a center component moves in response to the magnetic force created by current through a coil, this is discussed in the **solenoid** entry. By comparison, the **inductor** entry describes a coil that may or may not have a ferromagnetic core, and is used for the specific purpose of creating reactance, or self-inductance, in an electronic circuit, often in association with alternating current and in combination with resistors and/or capacitors. The **inductor** entry contains a basic discussion and explanation of magnetic force created by electricity.

OTHER RELATED COMPONENTS

- **solenoid** (See Chapter 21)
- **electromagnet** (See Chapter 20)
- **DC motor** (See Chapter 22)
- **AC motor** (See Chapter 23)

What It Does

An electromagnet consists of a coil that creates a magnetic field in response to an electric current. The field is channeled and reinforced by a core of magnetic material (that is, material that can be magnetized). Electromagnets are incorporated in motors, generators, loudspeakers, microphones, and industrial-sized applications such as mag-lev trains. On their own, they provide a means for electric current to hold, lift, or move objects in which a magnetic field can be induced.

A very small, basic electromagnet about 1 inch in diameter is shown in Figure 20-1. No specific schematic symbol for an electromagnet exists, and the symbol for an induction coil with a solid core is often used instead, as shown in Figure 14-1 (the center variant of each of the three) in the **inductor** entry of this encyclopedia.



Figure 20-1. *An electromagnet approximately 1 inch in diameter, rated to draw 0.25A at 12VDC.*

How It Works

Electric current flowing through a circle of wire (or a series of connected loops that form a helix or *coil*) will induce a magnetic field through the center. This is illustrated in the **inductor** entry of this encyclopedia, specifically in diagrams Figure 14-3, Figure 14-4, Figure 14-5, and Figure 14-6.

If a stationary piece of ferromagnetic material is placed in the center of the circle or coil, it enhances the magnetic force because the *reluctance* (magnetic resistance) of the material is much lower than the reluctance of air. The combination of the coil and the core is an electromagnet. This is illustrated in Figure 20-2. For a lengthier discussion of this effect, see "Magnetic Core" (page 122).



Figure 20-2. *Direct conventional current flowing through a wire coiled around a ferromagnetic rod induces a magnetic force in the rod, conventionally considered to flow from south to north.*

The magnitude of the electromagnetic *flux density* will be proportional to the current flowing through the coil, assuming a DC power source.

Variants

Electromagnet designs vary according to their application. The simplest design consists of a single coil wound around a rod which may terminate in a plate for applications such as lifting scrap metal. This design is relatively inefficient because the magnetic circuit is completed through air surrounding the electromagnet.

A more efficient, traditional design consists of a U-shaped core around which are wound one or two coils. If the U-shaped core is smoothly curved, it resembles a *horse-shoe magnet*, as shown in Figure 20-3. This design has become relatively uncommon, as it is cheaper to make windings across two separate, straight vertical cores and bridge them. However, the horseshoe configuration is extremely efficient, as the coils induce north and south magnetic polarities in the open ends of the U-shaped core, and the magnetic circuit is completed through any object that is attracted toward the open ends and links them. The attracted object is shown as a rectangular plate in Figure 20-3. Because a magnetic circuit will naturally attempt to limit its extent, and because this goal will be achieved when the circuit is completed, the attractive force of the U-shaped magnet is maximized.

An electromagnet powered by direct current naturally produces a consistently polarized, stable magnetic field. When AC current is applied, an electromagnet may still be used to exert an attractive force on a passive object that is not magnetized but is capable of being magnetized. The electromagnet will change its polarity at almost the same frequency as the AC, and will induce equal and opposite fluctuating polarity in the target, causing mutual attraction. The core of the magnet will be composed of plates separated by thin layers of insulation to inhibit the eddy currents induced by the AC, but still an AC-powered electromagnet will be less efficient than a comparable DC-powered electromagnet because it will also suffer from *hysteresis* as power is consumed by repeatedly reversing the polarity of the *magnetic domains* in the core.

Some electromagnets that are described as suitable for AC power actually contain *rectifiers* that convert the AC to DC.



Figure 20-3. *This traditional design for an electromagnet has a pedigree stretching back for more than a century. It maximizes efficiency by completing a magnetic circuit through any object that the magnet attracts.*

Values

Electromagnets are typically calibrated in terms of their power consumption and retaining force (the weight of an iron target that they can support). The retaining force is usually measured in grams or kilograms.

How to Use it

Electromagnets are used mostly as subassemblies in other components, such as motors and generators, relays, loudspeakers, and disk drives. They have also been used in audio (and video) tape recorders to magnetize ferric oxide on tape, using a magnetic field of varying strength to record an audio signal. In this application, a form of horseshoe magnet with an extremely narrow gap is used, the width of the gap determining the highest frequency that the electromagnet can record, in conjunction with the speed of the tape moving past the head.

The tape recording process can be reversed when the electromagnet "reads" the tape and turns the signal back into a weak alternating current that can be amplified and reproduced through a loudspeaker.

A simple application for an electromagnet is in a traditional-style doorbell, where one or two coils attract a spring-loaded lever, at the top of which is a knob that hits a bell. When the lever is pulled toward the bell, it breaks a contact that supplies power to the electromagnet. This allows the lever to spring back to its original position, which reestablishes the circuit, repeating the process for as long as power is applied to the bell. The bulk and weight of the component parts in this type of doorbell are making it obsolete, as electronic versions containing small loudspeakers become relatively cheaper. However, a **solenoid** may still be used in the type of bell that creates a single chime or pair of chimes.

In any device using a *cathode-ray tube*, electromagnetic coils are used to form a *yoke* around the neck of the tube, to deflect the beam of electrons on its way to the screen. A similar principle is used in electron microscopes. In some cases, electrostatically charged plates are used to achieve the same purpose.

An electromagnet may be used to activate a *reed switch* (the diagram in Figure 9-7 shows such a switch). In this application, the combination of the electromagnet and the switch are functioning as a **relay**.

When an electromagnet is energized by alternating current, it can be used to *degauss* (in other words, to demagnetize) other objects. The AC is either applied with diminishing current, so that the alternating magnetic polarities gradually subside to zero, or the electromagnet is gradually moved away from the target, again reducing the magnetic influence to (virtually) zero. This latter procedure may be used periodically to demagnetize record and replay heads on tape recorders, which otherwise tend to acquire residual magnetism, inducing background hiss on the tape.

Traditional large-scale applications for electromagnets tend to involve lifting and moving heavy objects or scrap metal, such as junked cars. A more modern application is in magnetic resonance imaging (MRI), which has revolutionized some areas of medicine.

Very large-scale applications for electromagnets include particle accelerators, in which multiple magnetic coils are energized sequentially, and fusion-power generators, where high-temperature plasma is contained by a magnetic field.

What Can Go Wrong

Because an electromagnet requires constant power to maintain its magnetic force, yet it is not doing any actual work so long as its target remains stationary (in contact with the core of the magnet), the current running through the coil of the magnet must be dissipated entirely as heat. Further discussion of this issue will be found at "Heat" (page 177) in the **solenoid** section of this encyclopedia.

solenoid

21

The term **solenoid** was historically used to describe any coil without a magnetic core. More recently and more commonly it describes a coil inside of which a cylindrical plunger moves in response to the magnetic field generated by the coil. In this encyclopedia, the term **electromagnet** has its own entry, and describes a coil with a center component of ferromagnetic material that does not move relative to the coil. It is used solely to attract or repel other parts that have inherent magnetic properties. By comparison, the **inductor** entry describes a coil that is used for the specific purpose of creating reactance, or self-inductance, in an electronic circuit, often in association with alternating current and in combination with resistors and/or capacitors. The **inductor** entry contains a basic discussion and explanation of magnetic force created by electricity.

OTHER RELATED COMPONENTS

- **inductor** (See Chapter 14)
- **solenoid** (See Chapter 21)

What It Does

A typical solenoid consists of a hollow coil inside a *frame*, which may be a sealed cylinder or box-shaped with open sides. In the case of a cylinder, its opposite ends may be referred to as *pole faces*.

At least one of the pole faces has a hole through which a *plunger* (also known as an *armature*) is pulled or pushed by the solenoid. Thus, the solenoid is a device for applying a linear mechanical force in response to current passing through it. In most solenoids, current must be maintained in order to maintain the mechanical force.

A small open-frame solenoid is pictured in Figure 21-1. The upper section of the figure shows the three basic parts: frame, compression spring, and plunger. The lower part of the figure shows the parts assembled.

A larger, closed, cynlindrical solenoid is shown in Figure 21-2, with the plunger and spring removed.

A 3D rendering showing a simplified, imaginary, cylindrical solenoid cut in half appears in Figure 21-3. The diagram includes a gray cylindrical shell, often described as the frame; the coil, shown in orange; the plunger, which is pulled into the coil by its magnetic field; and the triangular stop, which limits the plunger's upward travel. The frame of the solenoid exists not merely to protect the coil, but to provide a magnetic circuit, which is completed through the plunger.

The lower end of the plunger is often fitted with a nonmagnetic yoke or perforated plate for connection with other components. Stainless steel can be used for this purpose. The stop may be fitted with a thrust rod (also fabricated from stainless steel) if the solenoid is intended to "push" as well as "pull." Springs to adjust the force of the plunger, or to return it to its initial position when the current through the coil is interrupted, are not shown in the rendering.





Figure 21-1. *A small 12VDC solenoid.*



Figure 21-2. *A larger solenoid rated for 24VDC.*

Because there is no standardized schematic symbol for a solenoid, and because this type of component is so widely used in conjunction with valves, any diagram involving solenoids is more likely to emphasize fluid or gas flow with symbols that have been developed for that purpose. In such circuits, a solenoid may be represented simply by a rectangle. However, the symbols shown in Figure 21-4 may occasionally be found.

How It Works

Current flowing through the coil creates a magnetic force. This is explained in the **inductor** entry of this encyclopedia, using diagrams in Figure 14-3, Figure 14-4, Figure 14-5, and Figure 14-6.

If the plunger is fabricated from a material such as soft iron, the coil will induce an equal and opposite magnetic polarity in the plunger. Consequently the plunger will attempt to occupy a position inside the coil where the ends of the plunger are equal distances from the ends of the coil. If a collar is added to the free end of the plunger, this can increase the pulling force on the plunger when it is near the end of its throw because of the additional magnetic pull distributed between the collar and the frame of the solenoid.



Figure 21-3. *A simplified view of a solenoid cut in half, showing the primary parts.*



Figure 21-4. *Although no standard schematic symbol for a solenoid exists, these symbols may sometimes be found.*

A spring can be inserted to apply some resistive force to compensate for the increase in pulling force that occurs as a larger proportion of the plunger enters the coil. A spring may also be used to eject the plunger, partially at least, when current to the coil is interrupted.

If the plunger is a permanent magnet, reversing DC current to the coil will reverse the action of the plunger.

A solenoid with a nonmagnetized plunger may be energized by AC current, since polarity reversals in the magnetic field generated by the coil will induce equal and opposite reversals in the polarity of the plunger. However, the force curve of an AC-powered solenoid will be different from the force curve of a DC-powered solenoid. See Figure 21-5. The alternating current is likely to induce humming, buzzing, and vibration.



Figure 21-5. *A comparison of the force exerted on a plunger, relative to its position as it enters the coil, in hypothetical AC and DC solenoids.*

The frame of the solenoid increases the magnetic power that the coil can exert by providing a magnetic circuit of much lower *reluctance* than that of air (reluctance being the magnetic equivalent of electrical resistance). For a lengthier discussion of this effect, see "Magnetic Core" (page 122) in the **inductor** entry of this encyclopedia. If current flowing through the coil increases to the point where the frame becomes magnetically *saturated*, the pulling power of the solenoid will level off abruptly.

The heat generated by a solenoid when it is maintained in its energized state may be reduced if the manufacturer includes a series resistor and a switch that functions as a *bypass switch*. The switch is normally closed, but is opened mechanically when the plunger reaches the end of its throw, thus diverting electricity through the series resistor. This itself will generate some heat as a result of the current flowing through it, but by increasing the total resistance of the system, the total heat output will be reduced. The resistor value is chosen to provide the minimum power needed to retain the plunger at the end of its throw.

Variants

The most common variant is tubular, with open-frame as a secondary option. A tubular solenoid has been shown in Figure 21-2.

Additional variants include:

Low Profile

A shorter, fatter solenoid which may be used if a short throw is acceptable.

Latching

A permanent magnet holds the plunger when it reaches the end of its travel, and continues to hold it after power to the solenoid is disconnected. The plunger itself is also a permanent magnet, and is released by running current of reverse polarity through the coil.

Rotary

This variant is similar in principle to a brushless DC motor and causes the armature to rotate through a fixed angle (typically ranging from 25 to 90 degrees) instead of moving linearly. It is used as a mechanical indicator in control panels, although it is being displaced by purely electronic indicators.

Hinged Clapper

Instead of a plunger, a small hinged panel (the "clapper") moves in when the solenoid is active, and springs back when the power is interrupted.

Values

The stroke length, duty cycle, and holding force are the most significant values found in solenoid datasheets.

Holding forces for DC solenoids can range from a few grams to hundreds of kilograms. The holding force will be inversely proportional to the length of the solenoid, if all other variables are equal. The force that the solenoid can exert on its plunger also varies depending on the position of the plunger in the length of its throw.

Duty cycle is of special importance because the solenoid continues to draw power and create heat so long as it is holding the plunger at the end of its throw (assuming the solenoid is not the latching type). The initial current surge in an AC solenoid generates additional heat.

The duty cycle is simply calculated. If T1 is the time for which the solenoid is on and T2 is the time for which the solenoid is off, the duty cycle, D, is derived as a percentage from the formula

```
D = 100 * (T1 / (T1 + T2))
```

Some solenoids are designed to withstand a 100% duty cycle, but many are not, and in those cases, there is a maximum value not only for D but for the peak "on" time, regardless of the duty cycle. Suppose a solenoid is rated for a 25% duty cycle. If the solenoid is appropriately switched on for one second and off for three seconds, the heat will be allowed to dissipate before it has time to reach overload levels. If the solenoid is switched on for one minute and off for three minutes, the duty cycle is still 25%, but the heat that may accumulate during a one-minute "on" cycle may overload the component before the "off" cycle can allow it to dissipate.

Coil Size vs. Power

Because additional windings in a coil will induce a greater magnetic force, a larger solenoid tends to be more powerful than a smaller solenoid. However this means that if a larger and a smaller solenoid are both designed to generate the same force over the same distance, the smaller solenoid will probably draw more current (and will therefore generate more heat) because of its fewer coil windings.

How to Use it

Solenoids are primarily used to operate valves in fluid and gas circuits. Such circuits are found in laboratory and industrial process control, fuel injectors, aircraft systems, military applications, medical devices, and space vehicles. Solenoids may also be used in some electronic locks, in pinball machines, and in robotics.

What Can Go Wrong

Heat

Overheating is the principal concern when using solenoids, especially if the maximum "on" time is exceeded, or the duty cycle is exceeded. If the plunger is prevented from reaching the end of its throw, this can be another cause of overheating.

Because coil resistance increases with heat, a hot solenoid passes less current and therefore develops less power. This effect is more pronounced in a DC solenoid than an AC solenoid. A manufacturer's force curve should show the solenoid performance at its maximum rated temperature, which is typically around 75 degrees Centigrade, in a hypothetical ambient temperature of 25 degrees Centigrade. Exceeding these values may result in the solenoid failing to perform. As in all coils using magnet wire, there is the risk of excessive heat melting the insulation separating the coil windings, effectively shortening the coil, which will then pass more current, generating more heat.

AC Inrush

When an AC solenoid reaches the end of its travel, the sudden stop of the plunger results in forward *EMF* that generates additional heat. Generally speaking, a longer stroke creates a greater surge. Rapid cycling will therefore exacerbate coil heating.

Unwanted EMF

Like any device containing a coil, a solenoid creates back EMF when power is connected, and forward EMF when the power is disconnected. A protection diode may be necessary to suppress power spikes that can affect other components.

Loose Plunger

The plunger in many solenoids is not anchored or retained inside the frame and may fall out if the solenoid is tilted or subjected to extreme vibration.

DC motor

22

In this section, the term "traditional DC motor" is used to describe the oldest and simplest design, which consists of two *brushes* delivering power via a rotating, sectioned *commutator* to two or more electromagnetic coils mounted on the motor shaft. *Brushless* DC motors (in which DC is actually converted to a pulse train) are also described here because "brushless DC" has become a commonly used phrase, and the motor is powered by direct current, even though this is modified internally via *pulse-width modulation*.

OTHER RELATED COMPONENTS

- **AC motor** (See Chapter 23)
- **stepper motor** (See Chapter 25)
- **servo motor** (See Chapter 24)

What It Does

A traditional DC motor uses direct current to create magnetic force, which turns an output shaft. When the polarity of the DC voltage is reversed, the motor reverses its direction of rotation. Usually, the force created by the motor is equal in either direction.

How It Works

Current passes through two or more coils that are mounted on the motor shaft and rotate with it. This assembly is referred to as the *rotor*. The magnetic force produced by the current is concentrated via cores or poles of soft iron or high-silicon steel, and interacts with fields created by permanent magnets arrayed around the rotor in a fixed assembly known as the *stator*.

Power to the coils is delivered through a pair of *brushes*, often made from a graphite compound. Springs press the brushes against a sleeve that rotates with the shaft and is divided into sections, connected with the coils. The sleeve assembly is known as the *commutator*. As the commutator rotates, its sections apply power from the brushes to the motor coils sequentially, in a simple mechanical switching action.

The most elementary configuration for a traditional DC motor is shown in Figure 22-1.

In reality, small DC motors typically have three or more coils in the rotor, to provide smoother operation. The operation of a three-coil motor is shown in Figure 22-2. The three panels in this figure should be seen as successive snapshots of one motor in which the rotor turns progressively counter-clockwise. The brushes are colored red and blue to indicate positive and negative voltage supply, respectively. The coils are wired in series, with power being applied through the commutator to points between each pair of coils. The direction of current through each coil determines its magnetic polarity, shown as N for north or S for south. When two coils are energized in series without any power applied to their midpoint, each develops a smaller magnetic field than an individually energized coil. This is



Figure 22-1. *The simplest traditional DC motor contains these parts. The combination of coil, shaft, and commutator is the rotor. The fixed magnetic structure in which it rotates is the stator.*

indicated in the diagram with a smaller white lowercase n and s. When two ends of a coil are at equal potential, the coil produces no magnetic field at all.

The stator consists of a cylindrical permanent magnet, which has two poles—shown in the figure as two black semicircles separated by a vertical gap for clarity—although in practice the magnet may be made in one piece. Opposite magnetic poles on the rotor and stator attract each other, whereas the same magnetic poles repel each other.

DC motors may be quite compact, as shown in Figure 22-3, where the frame of the motor measures about 0.7″ square. They can also be very powerful for their size; the motor that is shown disassembled in Figure 22-4 is from a 12VDC bilge pump rated at 500 gallons per hour. Its output was delivered by the small impeller attached to the rotor at right, and was achieved by using



Figure 22-2. *Three sequential views of a typical three-coil DC motor viewed from the end of its shaft (the shaft itself is not shown). Magnetic effects cause the rotor to turn, which switches the current to the coils via the commutator at the center.*

two extremely powerful neodymium magnets, just visible on the inside of the motor's casing (at top-left) in conjunction with five coils on the rotor.



Figure 22-3. *A miniature 1.5VDC motor measuring about 0.7" square.*



Figure 22-4. *A traditional DC motor removed from its cylindrical casing. The brushes of the motor are attached to the white plastic end piece at bottom-left. Large squares on the graph paper in the background are 1" × 1", divided in 0.1" increments. The motor was used in a small bilge pump.*

Variants

Coil Configurations

The series connection of coils used in Figure 22-2 is known as the *delta configuration*. The alternative is the *wye configuration* (or *Y configuration*, or *star configuration*). Simplified schematics are shown in Figure 22-5. Generally speaking, the delta configuration is best suited to high-speed applications, but provides relatively low torque at low speed. The wye configuration provides higher torque at low speed, but its top speed is limited.

Gearhead Motor

A *gearhead motor* (also often known as a *gear motor*) incorporates a set of reduction gears that increase the torque available from the output shaft while reducing its speed of rotation. This is often desirable as an efficient speed for a traditional DC motor may range from 3,000 to 8,000 RPM, which is too fast for most applications. The gears and the motor are often contained in a single sealed cylindrical package. Two examples are shown in Figure 22-6. A disassembled motor, revealing half of its gear train under the cap and the other half still attached to a separate circular plate, appears in Figure 22-7. When the motor is assembled, the gears engage. As in the case of the bilge-pump motor, the stator magnets are mounted inside the cylindrical casing. Note that the brushes, inside the circular plate of white plastic, have a resistor and capacitor wired to suppress voltage spikes.

Spur gears are widely used for speed reduction. *Planetary gears* (also known as *epicyclic gears*) are a slightly more expensive option. Spur gears such as those in Figure 22-8 may require three or more pairs in series. The total speed reduction is



Figure 22-5. *Coils on the rotor of a traditional DC motor may be connected in delta configuration (top) or wye configuration (bottom).*



Figure 22-6. *Two typical small gearhead motors.*

found by multiplying the individual ratios. Thus, if three pairs of gears have ratios of 37 : 13, 31 : 15, and 39 : 17, the total speed reduction ® is obtained by:

```
R = ( 37 * 31 * 39 ) / ( 13 * 15 * 17 )
```



Figure 22-7. *Spur gears from a gearhead motor provide speed reduction and increased torque.*

Therefore:

```
R = 44733 / 3315 = about 13.5 : 1
```

Datasheets almost always express R as an integer. For example, the gear train shown in Figure 22-7 is rated by the manufacturer as having an overall reduction of 50:1. In reality, the reduction can be expected to have a fractional component. This is because if two gears have an integer ratio, their operating life will be shortened, as a manufacturing defect in a tooth in the smaller gear will hit the same spots in the larger gear each time it rotates. For this reason, the numbers of teeth in two spur gears usually do not have any common factors (as in the example above), and if a motor rotates at 500 RPM, a gear ratio stated as 50:1 is very unlikely to produce an output of exactly 10

RPM. Since traditional DC motors are seldom used for applications requiring high precision, this is not usually a significant issue, but it should be kept in mind.



Figure 22-8. *A pair of spur gears.*

Figure 22-9 shows *planetary gears*, also known as *epicyclic gears*. The outer ring gear is properly referred to as the *annulus*, while the *sun gear* is at the center, and the intermediate *planet gears* may be mounted on a *carrier*. The greatest speed reduction will be achieved by driving the sun gear while the annulus is kept in a stationary position and the output is taken from the carrier of the planet gears. If A is the number of teeth in the annulus and S is the number of teeth in the sun gear, the total speed reduction, R, is given by the following formula:

```
R = (S + A) / S
```

Note that in this drive configuration, the number of teeth in each planet gear is irrelevant to the speed reduction. In Figure 22-9, the sun gear has 27 teeth whereas the annulus has 45 teeth. Therefore, the reduction is found by:

```
R = (27 + 45) / 27 = about 2.7 : 1
```

Successive reductions can be achieved by stacking planetary gear sets, using the carrier of one set to drive the sun gear in the next set.

Planetary gears are used primarily if a motor drives a heavy load, as the force is divided among more gear pairs, reducing wear and tear on gear teeth and minimizing the breakdown of lubrication. A planetary gear train may also be more compact than a train of spur gears. These advantages must be evaluated against the higher price and slightly increased friction resulting from the larger number of gears interacting with each other.



Figure 22-9. *Planetary gears, also known as epicyclic gears, share the torque from a motor among more teeth than simple spur gears.*

Brushless DC Motor

In a *brushless* DC motor, sometimes referred to as a *BLDC motor*, the coils are located in the stator and the permanent magnets are relocated in the rotor. The great advantage of this design is that power can be applied directly to the coils, eliminating the need for brushes, which are the primary source of failure in DC motors as a result of wear and tear. However, since there is no rotating commutator to switch the DC current to the coils, the current must be switched by electronic components, which add to the cost of the motor.

In the *inrunner* configuration the stator surrounds the rotor, whereas in the *outrunner* configuration the stator is located in the center of the motor while the rotor takes the form of a ring or cup that spins around the stator. This is a common design for small cooling fans, where the blades are attached to the outer circumference of a cup that is lined with permanent magnets. An example is shown in Figure 22-10. In this picture, the stator coils are normally hidden from view, being fixed to the fan housing (shown at the top of the picture). Power is controlled by the surface-mount components on the green circular circuit board. The cup attached to the fan blades contains permanent magnets.



Figure 22-10. *A typical brushless DC cooling fan uses stationary coils, with permanent magnets rotating around them.*

The use of a solid-state switching system to energize the coils sequentially is known as *electronic commutation*. *Hall effect* sensors may be used to detect the position of the rotor and feed this information back to the frequency control circuit, so that it stays "one step ahead" of the rotor (when bringing it up to speed) or is synchronized with the rotor (for a constant running speed). The system is comparable to a *reluctance motor* or *synchronous motor.* These variants are described in the **AC motor** section of this encyclopedia.

While traditional DC motors have been commercially available since the late 1800s, brushless DC motors were not introduced until the 1960s, when the availability of solid-state control electronics began to make the motor design economically viable.

Linear Actuator

Linear actuator is a generic term for any device that can exert a pushing or pulling force in a straight line. In industrial applications, actuators may be powered pneumatically or hydraulically, but smaller-scale units are usually driven by a traditional DC motor. These are more properly (but not often) referred to as *electromechanical linear actuators*.

The rotational force of the motor is typically converted to linear motion by using a threaded motor shaft in conjunction with a nut or collar. The unit is often mounted in an enclosure containing *limit switches* that stop the motor automatically at the limits of travel. For an explanation of limit switches, see "Limit Switches" (page 46) in the **switch** entry in this encyclopedia.

Values

A manufacturer's datasheet should list the maximum operating voltage and typical current consumption when a motor is moderately loaded, along with the *stall current* that a motor draws when it is so heavily loaded that it stops turning. If stall current is not listed, it can be determined empirically by inserting an ammeter (or multimeter set to measure amperes) in series with the motor and applying a braking force until the motor stops. Motors should generally be protected with slow-blowing **fuses** to allow for the power fluctuations that occur when the motor starts running or experiences a change in load.

In addition, the *torque* that a motor can deliver should be specified. In the United States, torque is often expressed in *pound-feet* (or *ounce-inches* for smaller motors). Torque can be visualized by imagining an arm pivoted at one end with a weight hung on the other end. The torque exerted at the pivot is found by multiplying the weight by the length of the arm.

In the metric system, torque can be expressed as gram-centimeters, Newton-meters, or dyne-meters. A Newton is 100,000 dynes. A dyne is defined as the force required to accelerate a mass of 1 gram, increasing its velocity by 1 centimeter per second each second. 1 Newton-meter is equivalent to approximately 0.738 pound-feet.

The speed of a traditional DC motor can be adjusted by varying the voltage to it. However, if the voltage drops below 50% of the rated value, the motor may simply stop.

The power delivered by a motor is defined as its speed multiplied by its torque at that speed. The greatest power will be delivered when the motor is running at half its *unloaded speed* while delivering half the *stall torque*. However, running a motor under these conditions will usually create unacceptable amounts of heat, and will shorten its life.

Small DC motors should be run at 70% to 90% of their unloaded speed, and at 10% to 30% of the stall torque. This is also the range at which the motor is most efficient.

Ideally, DC motors that are used with reduction gearing should be driven with less than their rated voltage. This will prolong the life of the motor.

When choosing a motor, it is also important to consider the *axial loading* (the weight or force that will be imposed along the axis or shaft of the motor) and *radial loading* (the weight or force that will be imposed perpendicularly to the axis). Maximum values should be found in motor datasheets.

In the hobby field, motors for model aircraft are typically rated in watts-per-pound of motor weight (abbreviated w/lb). Values range from 50 to 250 w/lb, with higher values enabling better performance.

Relationships between torque, speed, voltage, and amperage in a traditional DC motor can be described easily, assuming a hypothetical motor that is 100% efficient:

If the amperage is constant, the torque will also be constant, regardless of the motor speed.

If the load applied to the motor remains constant (thus forcing the motor to apply a constant torque), the speed of the motor will be determined by the voltage applied to it.

If the voltage to the motor remains constant, the torque will be inversely proportional with the speed.

How to Use it

A traditional DC motor has the advantages of cheapness and simplicity, but is only suitable for intermittent use, as its brushes and commutator will tend to limit its lifetime. Its running speed will be approximate, making it unsuitable for precise applications.

As the cost of control electronics has diminished, brushless DC motors have replaced traditional DC motors. Their longevity and controllability provide obvious advantages in applications such as hard disk drives, variable-speed computer fans, CD players, and some workshop tools. Their wide variety of available sizes, and good power-to-weight ratio, have encouraged their adoption in toys and small vehicles, ranging from remote-controlled model cars, airplanes, and helicopters to personal transportation devices such as the Segway. They are also used in direct-drive audio turntables.

Where an application requires the rotation of a motor shaft to be converted to linear motion, a prepackaged *linear actuator* is usually more reliable and simpler than building a crank and connecting rod, or cam follower, from scratch. Large linear actuators are used in industrial automation, while smaller units are popular with robotics hobbyists and can also be used to control small systems in the home, such as a remote-controlled access door to a home entertainment center.

Speed Control

A *rheostat* or **potentiometer** may be placed in series with a traditional DC motor to adjust its speed, but will be inefficient, as it will achieve a voltage drop by generating heat. Any rheostat must be rated appropriately, and should probably be wire-wound. The voltage drop between the wiper and the input terminal of the rheostat should be measured under a variety of operating conditions, along with the amperage in the circuit, to verify that the wattage rating is appropriate.

Pulse-width modulation (*PWM*) is preferable as a means of speed control for a traditional DC motor. A circuit that serves this purpose is sometimes referred to as a *chopper*, as it chops a steady flow of current into discrete pulses. Usually the pulses have constant frequency while varying in duration. The pulse width determines the average delivered power, and the frequency is sufficiently high that it does not affect smoothness of operation of the motor.

A **programmable unijunction transistor** or PUT can be used to generate a train of pulses, adjustable with a potentiometer attached to its emitter. Output from the transistor goes to a *silicon-controlled rectifier* (*SCR*), which is placed in series with the motor, or can be connected directly to the motor if the motor is small. See Figure 27-7.

Alternatively, a *555 timer* can be used to create the pulse train, controlling a *MOSFET* in series with the motor.

A **microcontroller** can also be used as a pulse source. Many microcontrollers have PWM capability built in. The microcontroller will require its own regulated power supply (typically 5VDC, 3.3VDC, or sometimes less) and a switching component such as an *insulated-gate bipolar transistor* (*IGBT*) to deliver sufficient power to the motor and to handle the flyback voltage. These components will all add to the cost of the system, but many modern devices incorporate microcontrollers anyway, merely to process user input. Another advantage of using a microcontroller is that its output can be varied by rewriting software, for example if a motor is replaced with a new version that has different characteristics, or if requirements change for other reasons. Additionally, a microcontroller enables sophisticated features such as pre-programmed speed sequences, stored memory of user preferences, and/or responses to conditions such as excessive current consumption or heat in the motor.

A PWM schematic using a microcontroller and IGBT is shown in Figure 22-11.



Figure 22-11. *A sample schematic for control of a DC motor via pulse-width modulation, using a microcontroller and an insulated-gate bipolar transistor.*

Direction Control

The *H bridge* is a very early system for reversing the direction of a DC motor simply by swapping the polarity of its power supply. This is shown in Figure 22-12. The switches diagonally opposite each other are closed, leaving the other two switches open; and then to reverse the motor, the switch states are reversed. This is obviously a primitive scheme, but the term "H bridge" is still used when prepackaged in a single chip such as the LMD18200 H bridge motor controller from National Semiconductor.



Figure 22-12. *A DC motor can be reversed by this very basic circuit, known as an H bridge, by opening and closing pairs of switches that are diagonally opposite each other.*

A double-throw, double-pole **switch** or **relay** can achieve the same purpose, as shown in Figure 22-13.



Figure 22-13. *A DPDT switch or relay can reverse the direction of a traditional DC motor simply by swapping the polarity of the power supply.*

Limit Switches

When a traditional DC motor is used reversibly within a restricted range of motion, it can be fitted with *limit switches* to prevent the motor from stalling and burning out at either end of its permitted travel. Limit switches are explained in "Limit Switches" (page 46) in the **switch** entry in this encyclopedia.

What Can Go Wrong

Brushes and Commutator

The primary cause of failure in DC motors is abrasion of the brushes and wear and tear, oxidation, and/or accumulation of dirt on the commutator. Some motors are designed to allow replacement of the brushes; sealed motors and gearhead motors generally are not. High current and high speed will both tend to accelerate wear in the areas where the brushes meet the commutator.

Electrical Noise

The intermittent contact between the brushes and sections of the commutator of a traditional DC motor can induce voltage spikes that may travel back into the power supply for the motor and cause seemingly random effects in other components. Sparking in the commutator can be a significant source of *electromagnetic interference* (*EMI*), especially where cheap or poorly fitted brushes are used. Even if the commutator is running cleanly, the rapid creation of a magnetic field in a motor winding, following by collapse of the field, can create spikes that feed back into the power supply.

Wires that power a motor should be in twisted-pair configuration, so that their radiated EMI tends to cancel itself out. They should be routed away from data lines or encoder outputs, and may be shielded if necessary. Data lines from sensors in brushless motors may also be shielded.

Installing a capacitor across the motor terminals can significantly reduce EMI. Some motors have capacitors preinstalled. If the motor is in a sealed casing, it may have to be disassembled to reveal whether a capacitor is present.

Heat effects

Since all motors in the real world are less than 100% efficient, some power is lost by the motor during normal operation, and will be dissipated as heat. The resistance of motor windings, and consequently the magnetic force that they generate, will decrease as the temperature rises. The motor becomes less efficient, and will try to draw more current, worsening the situation. A manufacturer's rating for maximum temperature should be taken seriously.

The insulation of the coil windings is usually the most vulnerable part of a motor if excess heat persists. Short circuits between adjacent coils as a result of insulation breakdown will degrade the performance of the motor while increasing its power consumption, which will create even more heat.

Where motor casings have protruding ridges, these cooling fins should be exposed to ambient air.

Frequent starting, stopping, and reversing will tend to generate heat as a result of power surges, and will reduce the lifetime of the motor.

Ambient Conditions

A warm, dry environment will tend to dry out bearing lubricants and graphite brushes. Conversely, a very cold environment will tend to thicken the bearing lubricants. If a motor will be used in unusual environmental conditions, the manufacturer should be consulted.

Wrong Shaft Type or Diameter

Motors have a variety of possible output shaft diameters, some measured in inches and others in millimeters, and shafts may be long or short, or may have a D-shaped cross section or splines to mate with appropriate accessories such as gears, pulleys, or couplings. Careful examination of datasheets and part numbers is necessary to determine compatibility. In the hobby-electronics world, retailers may offer purpose-built discs or arms for specific motor shafts.

Incompatible Motor Mounts

Mounting lugs or flanges may or may not be provided, and may be incompatible with the application for which the motor is intended. The same motor may be available with a variety of mount options, differentiated only by one letter or digit in the motor's part number. A mount option that was available in the past may become obsolete or may simply be out of stock. Again, examination of datasheets is necessary.

Backlash

Backlash is the looseness or "slack" in a gear train that results from small gaps between meshing gear teeth. Because backlash is cumulative when gears are assembled in series, it can become significant in a slow-output gearhead motor. When measured at the output shaft, it is generally in the range of 1 to 7 degrees, tending to increase as the load increases. If a geared motor is used as a positioning device, and is fitted with an encoder to count rotations of the motor shaft, control electronics may cause the motor to hunt to and fro in an attempt to overcome the hysteresis allowed by the backlash. A **stepper motor** or **servo motor** is probably better suited to this kind of application.

Bearings

When using a motor that is not rated for significant axial loading, the bearings may be damaged by applying excessive force to push-fit an output gear or pulley onto the motor shaft. Even minor damage to bearings can cause significant noise (see the following section) and a reduced lifetime for the component.

In brushless DC motors, the most common cause of failure is the deterioration of bearings. Attempting to revive the bearings by unsealing them and adding lubricant is usually not worth the trouble.

Audible Noise

While electric motors are not generally thought of as being noisy devices, an enclosure can act as a sounding board, and bearing noise is likely to increase over time. Ball bearings become noisy over time, and gears are inherently noisy.

If a device will contain multiple motors, or will be used in close proximity to people who are likely to be sensitive to noise (for example, in a medical environment), care should be taken to insure that motor shafts are properly balanced, while the motors may be mounted on rubber bushings or in sleeves that will absorb vibration.

AC motor

23

The distinction between AC and DC motors has become blurred as controllers for DC motors make increasing use of *pulse-width modulation*, which can be viewed as a form of alternating current. All motors that consume DC power are referenced in the **DC motor** section of this encyclopedia, regardless of whether they modulate the power internally. **Stepper motors** and **servo motors** are considered as special cases, each with its own entry. AC motors, described here, are those that consume alternating current, usually in the form of a sine wave with a fixed frequency.

OTHER RELATED COMPONENTS

- **DC motor** (see Chapter 22)
- **stepper motor** (see Chapter 25)
- **servo motor** (see Chapter 24)

What It Does

An AC motor uses a power supply of alternating current to generate a fluctuating magnetic field that turns a shaft.

How It Works

The motor consists primarily of two parts: the *stator*, which remains stationary, and the *rotor*, which rotates inside the stator. Alternating current energizes one or more coils in the stator, creating fluctuating magnetic fields that interact with the rotor. A simplified representation is shown in Figure 23-1, where the coils create magnetic forces indicated by the green arrows, N representing North and S representing South.



Figure 23-1. *A simplified representation of a basic AC motor. The green arrows indicate magnetic force.*

Stator Design

Plug-in electric fans typically use AC motors. The stator from a large electric fan is shown in Figure 23-2, where the large diameter of each coil maximizes its magnetic effect. The stator from a smaller electric fan is shown in Figure 23-3, in which only one coil is used. (The coil is wrapped in black electrical tape.)



Figure 23-2. *The stator from a large electric fan. Each coil of copper wire is centered on a lug pointing inward to the hole at the center, where the rotor would normally be mounted. The coils overlap because their diameter is maximized to increase their magnetic effect. Each coil is tapped to allow speed selection in steps via an external rotary switch.*

The core of a stator resembles the core of a **transformer** in that it usually consists of a stack of wafers of high-silicon steel (or sometimes aluminum or cast iron). The layers are insulated from one another by thin layers of shellac (or a similar compound) to prevent eddy currents that would otherwise circulate through the entire thickness of the stator, reducing its efficiency.

The coil(s) wound around the stator are often referred to as *field windings*, as they create the magnetic field that runs the motor.

Rotor Design



Figure 23-3. *This stator from a smaller electric fan uses only a single coil, wrapped in black tape. It is sufficient to induce a magnetic field but is generally less efficient than a motor using multiple coils.*

In most AC motors, the rotor does not contain any coils and does not make any electrical connection with the rest of the motor. It is powered entirely by induced magnetic effects, causing this type of motor to be known generally as an *induction motor*.

As the AC voltage changes from positive to negative, the magnetic force induced in the stator collapses and a new field of opposite polarity is created. Because the stator is designed to create an asymmetrical field, it induces a rotating magnetic field in the rotor. The concept of a rotating magnetic field is fundamental in AC motors.

Like the stator, the rotor is fabricated from wafers of high-silicon steel; embedded in the wafers are nonmagnetic rods, usually fabricated from aluminum but sometimes from copper, oriented approximately parallel to the axis of rotation. The rods are shorted together by a ring at each end of the rotor, forming a conductive "cage," which explains why this device is often referred to colloquially as a *squirrel cage* motor.

Figure 23-4 shows the configuration of a rotor cage with the surrounding steel wafers removed for clarity. In reality, the rods in the cage are almost always angled slightly, as shown in Figure 23-5, to promote smooth running and reduce *cogging*, or fluctuations in torque, which would otherwise occur.



Figure 23-4. *The rotor of a typical AC motor contains a cage of aluminum (or sometimes copper) in which eddy currents occur, as a result of the rotating magnetic field inside the steel body of the rotor (which is omitted here for clarity). These currents cause their own magnetic fields, which interact with the fields generated by coils in the stator.*

In Figure 23-6, the steel wafers of a rotor are shown, with channels to accommodate an angled aluminum cage. Figure 23-7 shows a cross-section of a rotor with the cage elements in pale red and the steel wafer in gray.



Figure 23-5. *To promote smooth running of the motor, the longitudinal elements of the cage are typically angled, as suggested in this rendering.*



Figure 23-6. *The steel wafers in the rotor of an AC motor are typically offset as shown here. The channels are to accommodate a cage of aluminum or copper conductors.*



Figure 23-7. *Cross-section of a rotor with steel shown in gray and embedded elements of an aluminum cage shown in pale red.*



Figure 23-8. *The rotor from a small fan motor. The aluminum cage and its end pieces are the pale gray sections, steel plates are the darker sections.*

The actual rotor from an induction motor is shown in Figure 23-8. This rotor was removed from the stator shown in Figure 23-3. The bearings at either end of the rotor were bolted to the stator until disassembly.

Although the cage is nonmagnetic, it is electrically conductive. Therefore the rotating magnetic field that is induced in the steel part of the rotor generates substantial secondary electric current in the cage, so long as the magnetic field inside the rotor is turning faster than the rotor itself. The current in the longitudinal elements of the cage creates its own magnetic field, which interacts with the fields created by coils in the stator. Attraction and repulsion between these fields causes the rotor to turn.

Note that if the turning speed of the rotor rises to match the frequency of the alternating current powering the coils in the stator, the cage in the rotor is no longer turning through magnetic lines of force, and ceases to derive any power from them. In an ideal, frictionless motor, its unloaded operating speed would be in equilibrium with the AC frequency. In reality, an induction motor never quite attains that speed.

When power is applied while the rotor is at rest, the induction motor draws a heavy surge of current, much like a short-circuited **transformer**. Electrically, the coils in the stator are comparable to the primary winding of a transformer, while the cage in the rotor resembles the secondary winding. The turning force induced in the stationary rotor is known as *locked-rotor torque*. As the motor picks up speed, its power consumption diminishes. See Figure 23-9.

When the motor is running and a mechanical load is applied to it, the motor speed will drop. As the speed diminishes, the cage of conductors embedded in the rotor will derive more power, as they are turning more slowly than the rotating magnetic field. The speed of rotation of the field is determined by the frequency of the AC power, and is therefore constant. The difference in rota-



Figure 23-9. *An approximated graph showing the typical current consumption of an AC induction motor as it starts from rest and gains speed over a period of time.*

tional speed between the magnetic field and the rotor is known as *slip*. Higher levels of slip induce greater power, and therefore the induction motor will automatically find an equilibrium for any load within its designed range.

When running under full load, a small induction motor may have a slip value from 4 to 6 percent. In larger motors, this value will be lower.

Variants

Variants of the generic induction motor described above are generally designed to take advantage of either *single-phase* or *three-phase* alternating current.

A *synchronous motor* is a variant in which the rotor maintains a constant speed of rotation regardless of small fluctuations in load.

Some AC motors incorporate a *commutator*, which allows an external connection to coils mounted on the rotor, and can enable variable speed control.

A *linear motor* may consist of two rows of coils, energized by a sequence of pulses that can move a permanent magnet or electromagnet between the coils. Alternatively, the linear motor's coils may move as a result of magnetic interaction with a segmented fixed rail. Detailed description of linear motors is outside the scope of this encyclopedia.

Single-Phase Induction Motor

The majority of induction motors run on single-phase alternating current (typically, from domestic wall outlets). This type of motor is not innately self-starting because the stator coils and rotor are symmetrical. This tends to result in vibration rather than rotation.

To initiate rotation, the stator design is modified so that it induces an asymmetrical magnetic field, which is more powerful in one direction than the other. The simplest way to achieve this is by adding one or more *shorting coils* to the stator. Each shorting coil is often just a circle of heavy-gauge copper wire. This ploy reduces the efficiency of the motor and impairs its starting torque, and is generally used in small devices such as electric fans, where low-end torque is unimportant. Because the shorting coil obstructs some of the magnetic field, this configuration is often known as a *shaded pole* motor.

Copper shorting coils are visible in the fan motor shown in Figure 23-3.

A **capacitor** is a higher-cost but more efficient alternative to a shorting coil. If power is supplied to one or more of the stator coils through a capacitor, it will create a phase difference between these coils and the others in the motor, inducing an asymmetrical magnetic field. When the motor reaches approximately 80% of its designed running speed, a centrifugal switch may be included to take the capacitor out of the circuit, since it is no longer necessary. Switching out the capacitor and substituting a direct connection to the stator coils will improve the efficiency of the motor.

A third option to initiate rotation is to add a second winding in the stator, using fewer turns of smaller-gauge wire, which have a higher resistance than the main winding. Consequently the magnetic field will be angled to encourage the motor to start turning. This configuration is known as a *split-phase* induction motor, in which the starter winding is often referred to as the *auxilliary winding* and consists of about 30% of the total stator windings in the motor. Here again, a centrifugal switch can be incorporated, to eliminate the secondary winding from the circuit when the motor has reached 75 to 80 percent of its designed running speed.

The relationship between motor speed and torque of the three types of motors described above is shown in Figure 23-10. These curves are simplified and do not show the effect that would be produced by introducing a centrifugal switch.



Figure 23-10. *Approximate curves showing the relationship between speed and torque for three types of single-phase induction motor. (Graph derived from AC Induction Motor Fundamentals published by Microchip Technology Inc.)*

Three-Phase Induction Motor

Larger induction motors are often *three-phase* devices. Three-phase AC (which is by far the most common form of *polyphase* AC) is delivered by a power utility company or generator via three wires, each of which carries alternating current with a phase difference of 120 degrees relative to the other two, usually for industrial applications. A common configuration of stator coils for a three-phase motor is shown in Figure 23-11. Since the three wires take it in turns to deliver their peak voltage, they are ideally suited to turn the stator of a motor via induction, and no shorting coil or capacitor is needed for startup. Heavy-duty 3-phase induction motors are extremely reliable, being brushless and generally maintenance-free.

Synchronous Motor

A synchronous motor is a form of induction motor that is designed to reach and maintain equilibrium when the rotor is turning in perfect synchronization with the AC power supply. The speed of the motor will depend on the number of poles (magnetic coils) in the stator, and the number of phases in the power supply. If R is the RPM of a synchronous motor, f is the frequency of the AC current in Hz, and p is the number of poles per phase:

```
R = (120 * f) / p
```

This formula assumes 60Hz AC current. In nations where 50Hz AC is used, the number 120 should be replaced with the number 100.

Two basic types of synchronous motors exist: *direct current excited*, which require external power to start turning, and *non-excited*, which are self-starting. Since non-excited synchronous motors are more common in electronic applications, this encyclopedia will not deal with direct current excited variants.

A *hysteresis motor* is a synchronous motor containing a solid rotor cast from cobalt steel, which has high coercivity, meaning that once it is magnetized, a substantial field is required to reverse the magnetic polarity. Consequently the polarity of the rotor lags behind the constantly changing



Figure 23-11. *The graph shows voltage delivered via three wires constituting a three-phase power supply. (The curve colors are arbitrary.) A three-phase motor contains a multiple of three coils—often six, as shown here diagrammatically. The three wires of the power supply are connected directly to the coils, which induce a rotating magnetic field.*

polarity of the stator, creating an attracting force that turns the rotor. Because the lag angle is independent of motor speed, this motor delivers constant torque from startup.

Reluctance Motor

Reluctance is the magnetic equivalent to electrical resistance. If a piece of iron is free to move in a magnetic field, it will tend to align itself with the field to reduce the reluctance of the magnetic circuit. This principle was used in very early reluctance motors designed to work from AC and has been revived as electronics to control variable frequency drives have become cheaper.

The simplest reluctance motor consists of a soft iron rotor with projecting lugs, rotating within a stator that is magnetically energized with its own set of inwardly projecting poles. The rotor tends to turn until its lugs are aligned with the poles of the stator, thus minimizing the reluctance.

A basic reluctance motor design is shown in Figure 25-2. It is located in the **stepper motor** section of this encyclopedia, as stepper motors are a primary application of the reluctance principle.

Although a reluctance motor can be used with polyphase fixed-frequency AC power, a variable frequency drive greatly enhances its usefulness. The timing of the frequency is adjusted by the speed of the motor, which is detected by a sensor. Thus the energizing pulses can remain "one step ahead" of the rotor. Since the rotor is not a magnet, it generates no back-EMF, allowing it to reach very high speeds.

The simplicity of the motor itself is a compensating factor for the cost of the electronics, as it requires no commutator, brushes, permanent magnets, or rotor windings. Characteristics of reluctance motors include:

- Cheap parts, easily manufactured, and high reliability.
- Compact size and low weight.
- Efficiencies greater than 90% possible.
- Capable of high start-up torque and high speed operation.

Disadvantages include noise, cogging, and tight manufacturing tolerances, as the air gap between the rotor and stator must be minimized.

A reluctance motor can function synchronously, if it is designed for that purpose.

Variable Frequency Drive

A basic induction motor suffers from significant problems. The surge of power that it draws when starting from rest can pull down the supply voltage enough to affect other devices that share the AC power supply. (Hence, the brief dimming of lights that may occur when the compressor in an air conditioner or refrigerator starts running.) While the motor is turning, it can introduce electrical noise, which feeds back into the power supply, once again causing potential problems for other devices. In addition, the narrow range of speed of an AC induction motor is a great disadvantage.

The advent of cheap solid-state technology encouraged the development of *variable-frequency power supplies* for induction motors. Because the impedance of the motor will diminish as the frequency diminishes, the current drawn by the motor will tend to increase. To prevent this, a variable frequency supply also varies the voltage that it delivers.

Wound-Rotor AC Induction Motor

The stator of this variant is basically the same as that of a single-phase induction motor, but the rotor contains its own set of coils. These are electrically accessible via a *commutator* and *brushes*, as in a **DC motor**. Because the maximum torque (also known as *pull-out* torque) will be proportional to the electrical resistance of the coils in the rotor, the characteristics of the motor can be adjusted by adding or removing resistance externally, via the commutator. A higher resistance will enable greater torque at low speed when the slip between the rotor speed and rotation of the magnetic field induced by the stator is greatest. This is especially useful in corded power tools such as electric drills, where high torque at low speed is desirable, yet the motor can accelerate to full speed quickly when the external resistance is reduced. Typically, the resistance is adjusted via the trigger of the drill.

Figure 23-12 shows a wound-rotor AC induction motor. The disadvantage of this configuration is the brushes that supply power to the rotor will eventually require maintenance. Much larger wound-rotor motors are also used in industrial applications such as printing presses and elevators, where the need for variable speed makes a simple three-phase motor unsuitable.



Figure 23-12. *A motor in a corded electric drill uses coils in a brushed rotor to enable variable speed output. In most AC motors, the speed is not adjustable and the rotor does not make any electrical connection with the rest of the motor.*

Universal Motor

A wound-rotor motor may also be described as a *universal motor* if its rotor and stator coils are connected in series. This configuration allows it to be powered by either AC or DC.

DC supplied to the rotor and the stator will cause mutual magnetic repulsion. When the rotor turns, the brushes touching the split commutator reverse the polarity of voltage in the rotor coils, and the process repeats. This configuration is very similar to that of a conventional DC motor, except that the stator in a universal motor uses electromagnets instead of the permanent magnets that are characteristic of a **DC motor**.

When powered by AC, the series connection between stator and rotor coils insures that each pulse to the stator will be duplicated in the rotor, causing mutual repulsion. The addition of a shorting coil in the stator provides the necessary asymmetry in the magnetic field to make the motor start turning.

Universal motors are not limited by AC frequency, and are capable of extremely high-speed operation. They have high starting torque, are compact, and are cheap to manufacture. Applications include food blenders, vacuum cleaners, and hair dryers. In a workshop, they are found in routers and miniature power tools such as the Dremel series.

Because a universal motor requires commutator and brushes, it is only suitable for intermittent use.

Inverted AC Motors

Some modern domestic appliances may seem to contain an AC motor, but in fact the AC current is *rectified* to DC and is then processed with pulse-width modulation to allow variable speed control. The motor is really a **DC motor**; see the entry on this type of motor for additional information.

Values

Because a basic AC induction motor is governed by the frequency of the power supply, the speed of a typical four-pole motor is limited to less than 1,800 RPM (1,500 RPM in nations where 50Hz AC is the norm).

Variable-frequency, universal, and wound-rotor motors overcome this limitation, and can reach speeds of 10,000 to 30,000 RPM. Synchronous motors typically run at 1,800 or 1,200 RPM, depending on the number of poles in the motor. (They run at 1,500 or 1,000 RPM in locations where the frequency of AC is 50Hz rather than 60Hz).

For a discussion of the torque that can be created by a motor, see "Values" (page 184) in the **DC motor** entry in this encyclopedia.

How to Use It

Old-fashioned record players (where a turntable supports a vinyl disc that must rotate at a fixed speed) and electric clocks (of the analogue type) were major applications for synchronous motors, which used the frequency of the AC power supply to control motor speed. These applications have been superceded by CD players (usually powered by brushless DC motors) and digital clocks (which use crystal oscillators).

Many home appliances continue to use AC-powered induction motors. Small cooling fans for use in electronic equipment are sometimes AC-powered, reducing the current that must be provided by the DC power supply. An induction motor generally tends to be heavier and less efficient than other types, and its speed limit imposed by the frequency of the AC power supply is a significant disadvantage.

A simple induction motor cannot provide the sophisticated control that is necessary in modern devices such as CD or DVD players, ink-jet printers, and scanners. A **stepper motor**, **servo motor**, and **DC motors** controlled with *pulse-width modulation* are preferable in these applications.

A *reluctance motor* may find applications in high-speed, high-end equipment including vacuum cleaners, fans, and pumps. Large variable reluctance motors, with high amperage ratings, may be used to power vehicles. Smaller variants are being used for power steering systems and windshield wipers in some automobiles.

What Can Go Wrong

Compared with other devices that have moving parts, the brushless induction motor is one of the most reliable and efficient devices ever invented. However, there are many ways it can be damaged. General problems affecting all types of motors are listed at "Heat effects" (page 188). Issues relating specifically to AC motors are listed below.

Premature Restart

Large industrial three-phase induction motors can be damaged if power is reapplied before the motor has stopped rotating.

Frequent Restart

If a motor is stopped and started repeatedly, the heat that is generated during the initial surge of current is likely to be cumulative.

Undervoltage or Voltage Imbalance

A voltage drop can cause the motor to draw more current than it is rated to handle. If this situation persists, overheating will result. Problems also are caused in a three-phase motor where one phase is not voltage-balanced with the others. The most common cause of this problem is an open circuit-breaker, wiring fault, or blown fuse affecting just one of the three conductors. The motor will try to run using the two conductors that are still providing power, but the result is likely to be destructive.

Stalled Motor

When power is applied to an induction motor, if the motor is prevented from turning, the conductors in the rotor will carry a large current that is entirely dissipated as heat. This current surge will either burn out the motor or blow a fuse or circuit breaker. Care should be taken, in equipment design, to minimize the risk that an induction motor may stall or jam.

Protective Relays

Sophisticated protective relays are available for industrial 3-phase motors, and can guard against all of the faults itemized above. Their details are outside the scope of this encyclopedia.

Excess Torque

As has been previously noted, the torque of an induction motor increases with the slip (speed difference) between the rotation of the magnetic field and the rotation of the rotor. Consequently, if the motor is overloaded and forced to run more slowly, it can deliver more rotational force. This can destroy other parts attached to the motor, such as drive belts.

Internal Breakage

An overloaded induction motor may suffer some cracking or breakage of its rotor. This may be obvious because of reduced power output or vibration, but can also be detected if the motor's power consumption changes significantly.

24

servo motor

Should be referred to as an *RC servo* if it is intended for use in small devices that are remote-controlled and battery powered. However, in practice, the RC acronym is often omitted.

OTHER RELATED COMPONENTS

- **AC motor** (See Chapter 23)
- **DC motor** (See Chapter 22)
- **stepper motor** (See Chapter 25)

What It Does

A servo motor is actually a combination of a motor, reduction gearing, and miniaturized control electronics, usually packaged together inside a very compact sealed plastic case. The motor itself may be AC or DC, and if DC, it may be brushed or brushless. What distinguishes a servo from other types of motor is that it is not designed for continuous rotation. It is a position-seeking device. Its rotational range may be more than 180 degrees but will be significantly less than 360 degrees. Two typical RC servos are shown in Figure 24-1. A side view of a motor is shown in Figure 24-2.

The electronics inside the motor enclosure interpret commands from an external controller. The command code specifies the desired turn angle measured as an offset either side of the center position of the motor's range. The motor turns quickly to the specified position and stops there. So long as the command signal continues and power to the motor is sustained, the motor will hold its position and "push back" against any external turning force. In the absence of such a force, while the motor is stationary, it will use very little current.



Figure 24-1. *A typical RC servo motor is capable of more than 50 inch-ounces of torque yet can be driven by three or four AA alkaline cells in series, and weighs under 2 ounces.*

The electronics inside a typical RC servo motor are shown in Figure 24-3.

How It Works

Servo motors are generally controlled via *pulse-width modulation* (*PWM*).



Figure 24-2. *RC servo motors are mostly similar in size. This is a typical side view.*

An industrial servo typically requires a controller that is an off-the-shelf item sold by the manufacturer of the motor. The encoding scheme of the control signals may be proprietary. A heavy-duty servo may be designed to run from three-phase power at a relatively high voltage, and may be used in applications such as production-line automation.

The remainder of this encyclopedia entry will focus primarily on small RC servos rather than industrial servos.

For small RC servos, the stream of control pulses is at a constant frequency of 20ms, with the positive durations of each pulse being interpreted as a positioning command to the motor, and the gaps between the pulses being disregarded. A typical range of pulse widths for a small motor is 1ms to 2ms, specifying a range of -90 to +90 degrees either side of a center location. Many modern motors are capable of excursions beyond these limits, and can be calibrated to establish the precise relationship between pulse width and turn angle. The motor can then be controlled by a lookup table in microcontroller software, or by using a conversion factor between degree-angle and pulse width.

Figure 24-4 shows the typical range of pulse widths within the fixed 20ms period (a frequency of 50Hz) between the start of one pulse and the start of the next, and the meaning of each pulse width to the servo motor. Intermediate pulse widths are interpreted as instructions to rotate to intermediate positions.



Figure 24-3. *The electronics inside a servo motor decode a stream of pulses that specify the turn angle of the motor.*

Small servo motors require the user to provide a controller that will conform with the above specification. This is often achieved by programming a *microcontroller*, and some microcontroller chips make this especially easy by providing a PWM output specifically tailored to the requirements of an RC servo. Either way, the microcontroller can be directly connected to the servo, enabling an extremely simple and flexible way to manage a positioning device.

Alternatively, a simple pulse generator such as a *555 timer chip* can be used, or controller boards are available from hobbyist supply sources. Some controller boards have USB connections enabling a servo to be governed by computer software.



Figure 24-4. *The turn angle of a small RC servo motor is determined by a pulse width from a controller ranging from 1ms to 2ms in duration. The frequency of the pulses is constant at 50Hz.*

In Figure 24-5, a schematic illustrates the connection of a 555 timer with an RC servo, with component values to create a constant frequency of about 48Hz (slightly more than 20ms from peak to peak). The 1μF capacitor in the circuit charges through the 2.2K resistor in series with the diode, which bypasses the 28K resistor. This charging time represents the "on" cycle of the timer chip. The capacitor discharges through the 28K resistor, representing the "off" cycle. The 1K potentiometer, in series with the 5K resistors, acts as a voltage divider applied to the control pin of the timer, adjusting the timer's charge and discharge thresholds. Turning the potentiometer will lengthen or shorten the "on" time of each cycle, without changing the frequency. In practice, because capacitors are manufactured with wide tolerances, the frequency of the timer output cannot be guaranteed. Fortunately most servos will tolerate some inaccuracy.

Since the motor shares the power supply of the timer in this circuit, a protection diode and capacitor have been added between the power supply to the motor and negative ground, to suppress noise and back-EMF.



Figure 24-5. *An RC servo can be controlled via a 555 timer with appropriate component values. The potentiometer determines the angular position of the servo.*

Inside a servo motor's casing, the electronics include a **potentiometer** that turns with the output shaft, to provide feedback confirming the motor's position. The limited turning range of the potentiometer determines the turn limits of the motor output shaft.

Variants

Small servos may contain brushed or brushless DC motors. Naturally the brushless motors have greater longevity and create less electrical noise. See the **DC motor** entry in this encyclopedia for a discussion of brushed versus brushless motors.

Servos may use nylon, "Karbonite," or metal reduction gearing. The nylon gears inside a cheaper RC servo are shown in Figure 24-6.

Brushless motors and metal gears add slightly to the price of the motor. Metal gears are stronger than nylon (which can crack under load) but may wear faster, leading to *backlash* and inaccuracy in the gear train. The friction between nylon-to-nylon surfaces is very low, and nylon is certainly



Figure 24-6. *Nylon gearing inside a servo motor.*

adequate and may be preferable if a servo will not be heavily loaded. "Karbonite" is claimed to be five times stronger than nylon and may be a satisfactory compromise. If a gear set experiences a failure (for example, teeth can be stripped as a result of excessive load), manufacturers usually will sell a replacement set to be installed by the user. Installation requires manual dexterity and patience, and some skill.

Servos may have roller bearings or plain sintered bearings, the latter being cheaper but much less durable under side loading.

So-called *digital servos* use faster internal electronics than the older, so-called *analog servos*, and because they sample the incoming pulse stream at a higher frequency, they are more responsive to small, rapid commands from the controller. For this reason they are preferred by hobbyists using servos to control the flight of model airplanes. Externally, the control protocol for digital and analog servos is the same, although a digital servo can be reprogrammed with new code values establishing the limits to its range. A standalone programming unit must be purchased to achieve this.

The most popular manufacturers of small servo motors are Futaba and Hitec. While their control protocols are virtually identical, the motor output shafts differ. The shaft is typically known as the *spline*, and is grooved to fit push-on attachments. The spline of a Futaba motor has 25 grooves, while Hitec uses 24 grooves. Attachments must be appropriate for the brand of motor that has been chosen.

Values

A small servo typically weighs 1 to 2 ounces, has a rotation time of 1 to 2 seconds from one end of its travel to the other, and can exert a surprisingly robust torque of 50 ounce-inches or greater.

Voltage

Small servos were originally designed to run from 4.8V rechargeable batteries in model aircraft. They can be driven with 5VDC to 6VDC on a routine basis. A few servos are designed for higher voltages.

Amperage

The datasheets provided by most manufacturers often fail to specify the power that a servo will draw when it is exerting maximum torque (or indeed, any torque at all). Since small servos are often driven by three or four AA alkaline batteries in series, the maximum current draw is unlikely to be much greater than 1 amp. When the motor is energized but not turning, and is not resisting a turning force, its power consumption is negligible. This feature makes servos especially desirable for remote-controlled battery-powered devices.

Some motors that have a turning range exceeding 180 degrees will respond to pulses of less than 1ms or greater than 2ms. A newly acquired motor should be tested with a microcontroller that steps through a wide range of pulse durations, to determine the limits empirically. Pulses that are outside the motor's designed range will generally be ignored and will not cause damage.

The *turn rate* or *transit time* specified in a datasheet is the time a servo takes to rotate through 60 degrees, with no load on the output shaft. A high-torque servo generally achieves its greater turning force by using a higher reduction gear ratio, which tends to result in a longer transit time.

How to Use it

Typical applications for a small servo include rotating the flaps or rudder of a model aircraft, steering a model boat, model car, or wheeled robot, and turning robotic arms.

A servo generally has three wires, colored red (power supply), black or brown (ground), and orange, yellow, or white (for the pulse train from the controller). The ground wire to the motor must be common with the ground of the controller, and consequently a ceramic bypass **capacitor** of 0.1µF or 0.01µF should be placed between the (red) power wire to the motor and ground. A protection **diode** should also be used. Neither a diode nor a capacitor should be attached to the wire carrying control signals, as it will interfere with the pulse train.

When powering the motor, an AC adapter should only be used with some caution, as its power output may be inadequately smoothed. A voltage regulator is not necessary, but bypass **capacitors** are mandatory. Figure 24-7 shows two hypothetical schematics. The upper section of the figure shows a battery-driven system, possibly using four 1.2V NiMH rechargeable batteries. Since batteries do not generally create voltage spikes, no capacitors are used, but a diode is included to protect the microcontroller from EMF when the servo stops and starts. The lower section of the figure shows the additional precautions that may be necessary when using DC power from an **AC adapter**. The DC-DC **converter**, which derives 6VDC for the motor requires smoothing capacitors (this should be specified in its datasheet), and so does the **voltage regulator**, which delivers regulated 5VDC power to the microcontroller. Once again, the protection diode is included. In both diagrams, the orange wire represents the control wire transmitting pulses to the servo motor.



Figure 24-7. *Two possible schematics to run a small servo motor, the upper example using battery power (for example, from four 1.2V NiMH cells) and the lower example using a 9VDC AC adapter. See text for additional explanation.*

Various shaft attachments are available from the same online hobby-electronics suppliers that sell servos. The attachments include discs, single arms, double arms, and four arms in a cross-shaped configuration. A single-arm attachment is often known as a *horn*, and this term may be applied loosely to any kind of attachment. The horn is usually perforated so that other components can be fixed to it by using small screws or nuts and bolts. Figure 24-8 shows a variety of horns.



Figure 24-8. *Various shaft attachments, known as horns, are available from motor manufacturers. The blue one is metallic; the others are plastic.*

After the horn is pushed onto the spline (the motor shaft), it is held in place with one central screw. As previously noted, the two major manufacturers of small servos, Futaba and Hitec, have incompatible splines.

Modification for Continuous Rotation

It is possible to modify a small servo motor so that it will rotate continuously.

First the motor case must be opened, and the potentiometer must be centered by using a controller to send some 1.5ms pulses. The potentiometer must then be glued or otherwise secured with its wiper in this precise center position, after which the potentiometer is disconnected from the drive train.

Mechanical stops that would limit the rotation of the motor shaft must be cut away, after which the motor is reassembled. Because the potentiometer has been immobilized, the motor's internal electronics will now "see" the shaft as being in its center position at all times. If the controller sends a pulse instructing the motor to seek a position clockwise or counter-clockwise from center, the motor will rotate in an effort to reach that position. Because the potentiometer will not provide feedback to signal that the motor has achieved its goal, the shaft will continue to rotate indefinitely.

In this mode, the primary distinguishing characteristic of the servo has been disabled, in that it can no longer turn to a specific angle. Also, stopping the servo may be problematic, as it must receive a command that precisely matches the fixed position of the potentiometer. Since the potentiometer may have moved fractionally during the process in which it was immobilized, some trial and error may be needed to determine the pulse width that corresponds with the potentiometer position.

The purpose of modifying a servo for continuous rotation is to take advantage of its high torque, small size, light weight, and the ease of controlling it with a microcontroller.

In response to the interest shown by hobbyists in modifying servos for continuous rotation, some manufacturers now market servos with continuous rotation as a built-in feature. Typically they include a trimmer potentiometer to calibrate the motor, to establish its center-off position.

What Can Go Wrong

Incorrect Wiring

The manufacturer's datasheet should be checked to confirm the color coding of the wires. While a simple DC motor can be reversed by inverting the polarity of its power supply, this is totally inappropriate for a servo motor.

Shaft/Horn Mismatch

Attachments for the spline of one brand of motor may not fit the spline of another brand, and cannot be forced to fit.

Unrealistically Rapid Software Commands

Microcontroller software that positions a servo must allow sufficient time for the servo to respond before the software specifies a new position. It may be necessary to insert delay loops or other wait times in the software.

Jitter

A servo arm that twitches unpredictably usually indicates that the pulse train is being corrupted by external electrical noise. The control wire to the servo should be as short as possible, and should not run closely adjacent to conductors carrying AC or high frequency current switching, or control wires for other servo motors.

Motor Overload

A servo capable of delivering 2 lbs of force 1 inch from its shaft can easily generate enough torque, when it stalls, to break itself free from its mounts, or bend or break any arm or linkage attached to its shaft. Ideally, a relatively "weak link" should be included so that if breakage occurs, it will be predictable and will be relatively easy and cheap to repair.

Unrealistic Duty Cycle

Small servos are designed for intermittent use. Constant cycling will cause wear and tear, especially if the motor has a brushed commutator or metal reduction gears.

Electrical Noise

Brushed motors are always a source of electrical interference, and any servo will also tend to create a voltage dip or surge when it starts and stops. A protection diode may be insufficient to isolate sensitive microcontrollers and other integrated circuit chips. To minimize problems, the servo can be driven by a source of positive voltage that is separate from the regulated power supply used by the chips, and larger filter capacitors may be added to the voltage supply of the microcontroller. A common ground between the motor and the chips is unfortunately unavoidable.

stepper motor

25

Also often referred to as a *stepping motor*, and sometimes known as a *step motor*. It is a type of *induction motor* but merits its own entry in this encyclopedia as it has acquired significant and unique importance in electronics equipment where precise positioning of a moving part is needed and digital control is available.

OTHER RELATED COMPONENTS

- **DC motor** (See Chapter 22)
- **AC motor** (See Chapter 23)
- **servo motor** (See Chapter 24)

What It Does

A stepper motor rotates its drive shaft in precise steps in response to a timed sequence of pulses (usually one step per pulse). The pulses are delivered to a series of coils or *windings* in the *stator*, which is the stationary section of the motor, usually forming a ring around the *rotor*, which is the part of the motor that rotates. Steps may also be referred to as *phases*, and a motor that rotates in small steps may be referred to as having a high *phase count*.

A stepper motor theoretically draws power for its stator coils at a constant level that does not vary with speed. Consequently the torque tends to decrease as the speed increases, and conversely, it is greatest when the motor is stationary or locked.

The motor requires a suitable control system to provide the sequence of pulses. The control system may consist of a small dedicated circuit, or a microcontroller or computer with the addition of suitable driver transistors capable of handling the necessary current. The torque curve of a motor can be extended by using a controller that increases the voltage as the speed of the control pulses increases.

Because the behavior of the motor is controlled by external electronics, and its interior is usually symmetrical, a stepper motor can be driven backward and forward with equal torque, and can also be held in a stationary position, although the stator coils will continue to consume power in this mode.

How It Works

The stator has multiple poles made from soft iron or other magnetic material. Each pole is either energized by its own coil, or more commonly, several poles share a single, large coil. In all types of stepper motor, sets of stator poles are magnetized sequentially to turn the rotor and can remain energized in one configuration to hold the rotor stationary.

The rotor may contain one or more permanent magnets, which interact with the magnetic fields generated in the stator. Note that this is different from a *squirrel-cage* **AC motor** in which a "cage" is embedded in the rotor and interacts with a rotating magnetic field, but does not consist of permanent magnets.

Three small stepper motors are shown in Figure 25-1. Clockwise from the top-left, they are four-wire, five-wire, and six-wire types (this distinction is explained in the following section). The motor at top-left has a threaded shaft that can engage with a collar, so that as the motor shaft rotates counter-clockwise and clockwise, the collar will be moved down and up.



Figure 25-1. *Three small stepper motors.*

Reluctance Stepper Motors

The simplest form of stepper motor uses a rotor that does not contain permanent magnets. It relies on the principle of *variable reluctance*, reluctance being the magnetic equivalent of electrical *resistance*. The rotor will tend to align its protruding parts with the exterior source(s) of the magnetic field, as this will reduce the reluctance in the system. Additional information about variable reluctance is included in "Reluctance Motor" (page 197) in the section of this encyclopedia dealing with the **AC motor**.

A variable reluctance motor requires an external controller that simply energizes the stator coils sequentially. This is shown in Figure 25-2, where six poles (energized in pairs) are arrayed symmetrically around a rotor with four protrusions, usually referred to as *teeth*. Six stator poles and four teeth are the minimum numbers for reliable performance of a reluctance stepper motor.

In the diagram, the core of each pole is tinted green when it is magnetized, and is gray when it is not magnetized. In each section of this diagram, the stator coils are shown when they have just been energized, and the rotor has not yet had time to respond. External switching to energize the coils has been omitted for simplicity. In a real motor, the rotor would have numerous ridges, and the clearance between them and the stator would be extremely narrow to maximize the magnetic effect.

In a 6-pole reluctance motor where the rotor has four teeth, each time the controller energizes a new pair of poles, the rotor turns by 30 degrees counter-clockwise. This is known as the *step angle*, and means that the motor makes 12 steps in each full 360-degree rotation of its shaft. This configuration is very similar to that of a 3-phase AC *induction motor*, as shown in Figure 23-11 in the **AC motor** section of this encyclopedia. However, the AC motor is designed to be plugged into a power source with a constant frequency, and is intended to run smoothly and continuously, not in discrete steps.

Generally, reluctance motors tend to be larger than those with magnetized rotors, and often require feedback from a sensor that monitors shaft angle and provides this information to control electronics. This is known as a *closed loop* system. Most smaller stepper motors operate in an *open loop* system, where positional feedback is considered unnecessary if the number of pulses to the motor is counted as a means of tracking its position.



Figure 25-2. *In a variable reluctance stepper motor, the rotor moves to minimize magnetic reluctance each time the next pair of coils is energized. At each step, the coils have been energized a moment before the rotor has had time to respond.*

Permanent Magnet Stepper Motors

More commonly, the rotor of a stepper motor contains permanent magnets, which require the controller to be capable of reversing the magnetic field created by each of the stator coils, so that they alternately attract and repel the rotor magnets.

In a *bipolar* motor, the magnetic field generated by a coil is reversed simply by reversing the current through it. This is shown diagrammatically in Figure 25-3. In a *unipolar* motor, the magnetic field is reversed by applying positive voltage to the center tap of a coil, and grounding one end or the other. This is shown diagrammatically in Figure 25-4.



Figure 25-3. *In a bipolar motor, the magnetic field generated by each stator coil is reversed simply by reversing the current through the coil.*

Either type of motor is often designed with an upper and lower deck surrounding a single rotor,



Figure 25-4. *The magnetic field of this coil is reversed by applying positive voltage constantly to a center tap and grounding one end of the coil or the other.*

as suggested in Figure 25-5. A large single coil, or center-tapped coil, induces a magnetic field in multiple poles in the top deck, out of phase by one step with a second set of poles, energized by their own coil, in the bottom deck. (All three motors shown in Figure 25-1 are of this type.) The rotor of the motor is tall enough to span both decks, and is rotated by each of them in turn.

In Figure 25-6, the decks of a two-deck four-wire motor have been split apart. The rotor remains in the left-hand section. It is enclosed within a black cylinder that is a permanent magnet divided into multiple poles. In the right-hand section, a coil is visible surrounding metal "teeth" that function as stator poles when the coil is energized.

In Figure 25-7, the same motor has been further disassembled. The coil was secured with a length of tape around its periphery, which has been removed to make the coil visible. The remaining



Figure 25-5. *A simplified rendering of the common "two deck" type of motor. See text for details.*



Figure 25-6. *A two-deck stepper motor split open to reveal its rotor (left) and one of the stators (right) encircled by a coil.*

half of the motor, at top-right, contains a second, concealed but identical coil with its own set of poles, one step out of phase with those in the first deck.

Because the field effects in a two-deck stepper motor are difficult to visualize, the remaining diagrams show simplified configurations with a minimum number of stator poles, each with its own coil.



Figure 25-7. *The stepper motor from the previous figure, further disassembled.*

Bipolar Stepper Motors

The most basic way to reverse the current in a coil is by using an *H-bridge* configuration of switches, as shown in Figure 25-8, where the green arrow indicates the direction of the magnetic field. In actual applications, the switches are solid-state. Integrated circuits are available containing all the necessary components to control a bipolar stepper motor.

Four sequential steps of a bipolar motor are shown in Figure 25-9, Figure 25-10, Figure 25-11, and Figure 25-12. The H-bridge control electronics for each coil are omitted for clarity. As before, energized coils are shown with the pole inside the coil tinted green, while non-energized coils are gray, and the rotor is shown before it has had time to respond to the magnetic field in each step.

Unipolar Motors

The control electronics for a unipolar motor can be simpler than those for a bipolar motor, as off-the-shelf switching transistors can ground one end of the coil or the other. The classic five-wire unipolar stepper motor, often sold to hobbyists and used in robotics projects and similar applications, can be driven by nothing more elaborate



Figure 25-8. *The simplest and most basic way to reverse the current through a coil is via an H-bridge circuit. In practice, the switches are replaced by solid-state components.*



Figure 25-9. *A bipolar stepper motor depicted a moment before the rotor has had time to make its first step in response to magnetic fields created by the stator coils.*



Figure 25-10. *The bipolar stepper motor from the previous figure is shown with its rotor having advanced by one step, and coil polarity changed to induce it to make a second step.*



Figure 25-11. *The bipolar stepper motor after taking its second step, immediately before making its third step.*

than a set of *555 timer* chips. However, this type of motor is less powerful for its size and weight because only half of each coil is energized at a time.

In Figure 25-13, Figure 25-14, Figure 25-15, and Figure 25-16, the simplest configuration of a unipolar system is shown in diagrammatic form using four stator coils and a rotor containing six magnetic poles. Each figure shows the stator coils when they have just been energized, a moment before the rotor has had time to move in response to them. Coils that are energized are shown with the metal cores tinted green. Wires that are not conducting current are shown in gray. The open and closed positions of switches a, b, c, and d suggest the path that current is taking along the wires that are colored black.



Figure 25-12. *The bipolar stepper motor after taking its third step. When the rotor responds to the new pattern of magnetic fields, its orientation will be functionally identical with that shown in the first step.*

Note that coils on opposite sides of the motor are energized simultaneously, while the other pair of coils is de-energized. Adjusting the controller so that it overlaps the “on” cycles of the coils can generate more torque, while consuming more power.

A motor containing more stator poles can advance in smaller steps, if the poles are separately energized. However, if the coils have individual windings, this will increase the cost of the motor.

Variants

In addition to bipolar and unipolar variants, previously described, three others are available.

High Phase Count

This term describes any type of stepper motor in which additional poles reduce the step size. The advantages of a high phase count include


Step 1
c
b
S
N
S
N
d
a
N
S
S
N
N
S

Figure 25-13. *The coils of this unipolar stepper motor are shown an instant after they have been energized, before the rotor has had time to respond by making its first step.*


Step 2
c
b
S
N
d
a
S
N
N
S
S
N
N
S

Figure 25-14. *The same motor from the previous figure is shown with coils energized to induce the rotor to make its second step.*


Step 3
c
b
N
S
N
S
d
a
S
N
N
S
S
N

Figure 25-15. *The same motor from the previous figure is shown with coils energized to induce the rotor to make its third step.*


Step 4
c
b
N
S
d
a
N
S
S
N
N
S
S
N

Figure 25-16. *When the rotor makes its fourth step, it will be back in an orientation that is functionally identical with the first figure in this series.*

smoother running at high speed and greater precision when selecting a desired motor position. The additional coils also enable higher power density, but naturally tend to add to the cost of the motor.

Hybrid

This type of motor uses a toothed rotor that provides variable reluctance while also containing permanent magnets. It has become relatively common, as the addition of teeth to the rotor enables greater precision and efficiency. From a control point of view, the motor behaves like a regular permanent-magnet stepper motor.

Bifilar

In this type of motor, also sometimes known as a *universal* stepper motor, two coils are wound in parallel for each stator pole. If there are two poles or sets of poles, and both ends of each winding are accessible via wires that are run out of the motor, there will be eight wires in total. Consequently this type is often referred to as an *8-wire motor*.

The advantage of this scheme is that it allows three possible configurations for the internal coils. By shorting together the wires selectively, the motor can be made to function either in unipolar or bipolar mode.

In Figure 25-17, the upper pair of simplified diagrams depicts one end of one coil connected to the beginning of the other, while positive voltage is applied at the midpoint, as in a unipolar motor. The magnetic polarity of the coil is determined by grounding either end of the coil. The section of each coil that is not conducting current is shown in gray.

The center pair of diagrams shows the adjacent ends of the coils tied together, so that they are now energized in parallel, with the magnetic polarity being determined by the polarity of the voltage, as in a bipolar motor.

The coils may also be connected in series, as shown in the lower pair of diagrams. This will provide greater torque at low speed and lower torque at high speed, while enabling higher-voltage, lower-current operation.



Figure 25-17. *In a bifilar motor, two coils are wound in parallel around each stator pole and can be connected with a center tap to emulate a unipolar motor (upper diagrams), or can be energized in parallel (middle diagrams) or series (lower diagrams) to emulate a bipolar motor.*

Multiphase

In a multiphase motor, multiple stator coils are usually connected in series, with a center tap applied between each pair. A possible configuration is shown in Figure 25-18, where the two diagrams show two consecutive steps in rotation, although the step angle could be halved by changing the voltage polarity in only one location at a time. The way in which the motor is wired enables only one stator coil to be unpowered during any step, because its two ends are at equal potential. Therefore this type of motor is capable of high torque in a relatively small format.

In some multiphase motors, additional wires allow access to both ends of each coil, and the coils are not connected internally. This allows control of the motor to be customized.

Microstepping

An appropriately designed stepper motor can be induced to make very small, intermediate steps if the control voltage is modulated to intermediate levels. Step angles as low as 0.007 degrees are claimed by some manufacturers. However, a motor running in this mode is less able to generate torque.

The simplest form of microstepping is half-stepping. To achieve this in a unipolar motor, each coil passes through an "off" state before its magnetic polarity is reversed.

Sensing and Feedback

So long as the series of pulses to the motor allows the rotor ample time to respond, no feedback mechanism from the rotor is necessary to confirm its position, and an open-loop system is sufficient. If sudden acceleration, deceleration, load fluctuations, and/or rotation reversal will occur, or if high speeds are involved, a *closed loop system*, in which a sensor provides positional feedback, may be necessary.

Voltage Control

Rapid stepping of a motor requires rapid creation and collapse of magnetic fields in the stator windings. Therefore, self-inductance of the windings can limit the motor speed. One way to overcome this is to use a higher voltage. A more sophisticated solution is to use a controller that provides a high initial voltage, which is reduced or briefly interrupted when a sensor indicates that coil current has increased sufficiently to overcome the self-inductance of the windings and has reached its imposed limit. This type of controller may be referred to as a *chopper drive* as the voltage is "chopped," usually by power transistors. It is a form of *pulse width modulation*.



Figure 25-18. *A multiphase stepper motor. By applying voltage in the pattern shown, only one coil is not energized during each step. This enables high torque compared with the size of the motor.*

Values

The *step angle* of a stepper motor is the angular rotation of its shaft, in degrees, for each full step. This will be determined by the physical construction of the motor. The coarsest step angle is 90 degrees, while sophisticated motors may be capable of 1.8 degrees (without microstepping).

The maximum torque that a motor can deliver is discussed in "Values" (page 184) in the **DC motor** entry of this encyclopedia.

Motor weight and size, shaft length, and shaft diameter are the principal passive values of a stepper motor, which should be checked before it is selected for use.

How to Use it

Stepper motors are used to control the seek action in disk drives, the print-head movement and paper advance in computer printers, and the scanning motion in document scanners and copiers.

Industrial and laboratory applications include the adjustment of optical devices (modern telescopes are often oriented with stepper motors), and valve control in fluid systems.

A stepper motor may be used to power a *linear actuator*, usually via a screw thread (properly known as a lead screw) or worm gear. For more on linear actuators, see "Linear Actuator" (page 184). While the stepper motor will enable greater accuracy than a traditional DC motor, the gearing inevitably will introduce some imprecision.

Advantages of stepper motors include:

- Precise positioning, typically within 3 percent to 5 percent per step. The percentage step error does not accumulate as the motor rotates
- Able to run at a wide range of speeds, including very slow speeds without reduction gearing
- Trouble-free start, stop, and reverse action
- Cheap controller hardware where open-loop applications are acceptable
- High reliability, since no brushes or commutator are involved

Disadvantages include:

- Noise and vibration
- Resonance at low speeds
- Progressive loss of torque at high speeds

Protection Diodes

While a small stepper motor may be driven directly from power transistors, *darlington pairs*, or even *555 timers*, larger motors will create *back-EMF* when the magnetic field of each stator coil is induced or forward EMF when the field is allowed to collapse, and bipolar motors will also induce voltage spikes when the current reverses. In a unipolar motor, while only one-half of the coil is actually energized via its center tap, the other half will have an induced voltage, as the coil acts like a *linear transformer*.

A simplified schematic illustrating diode placement for a bipolar motor is shown in Figure 25-19.



Figure 25-19. *The H-bridge circuit must be augmented with protection diodes to guard against back-EMF created by fluctuating current in the stator coil.*

Integrated circuit chips are available taht incorporate protection diodes, in addition to the necessary power transistors. Stepper motors may also have protection diodes built in. Consult the manufacturer's datasheet for details before attaching a motor to a power source.

Positional Control

The built-in control electronics of a **servo motor** typically turn the shaft to a precisely known position in response to pulse-width modulation from an exterior source such as a **microcontroller**, whereas the angle of rotation of a stepper motor in an open-loop system must be calculated by counting the number of steps from an initial, home position. This limitation of a stepper motor can be overcome by using a closed-loop system, but that will require monitoring the motor, adding complexity to the external controller. The choice between stepper and servo motors should be evaluated on a case-by-case basis.

What Can Go Wrong

General problems affecting all types of motors are listed in "Heat effects" (page 188). Issues relating more specifically to stepper motors are listed in the following sections.

Incorrect Wiring

Because a stepper motor is driven via multiple conductors, there is a significant risk of wiring errors, especially since many motors are not identified with part numbers. The first challenge, then, may be to determine what type of motor it is. When the motor is disconnected from any power, and the shaft is rotated with finger and thumb, a magnetized-rotor motor will not spin as freely as a reluctance motor, because the magnets in the rotor will provide intermittent turning resistance.

If a unipolar motor is relatively small and is fitted with five wires, almost certainly the motor contains two coils, each with a center tap, and their function can be determined by applying positive voltage to the red wire and grounding each of the other wires in turn. Attaching a small piece of tape to the motor shaft will assist in viewing its orientation.

A multimeter set to measure ohms can also be useful in deducing the internal coil connections of the motor, since the end-to-end resistance of a coil should be approximately twice the resistance between the center tap and either end of the coil.

A multiphase motor may have five wires, but in this case, the resistance between any two nonadjacent wires will be 1.5 times the resistance between any two adjacent wires.

Step Loss

In an open-loop system, if the motor skips or misses pulses from the controller, the controller no longer has an accurate assessment of the shaft angle. This is known as *step loss*. Since this can be caused by sudden changes in control frequency, the frequency should be increased (or decreased) gradually. This is known as *ramping* the motor speed. Stepper motors cannot respond instantly to changes in speed, because of inertia in the rotor or in the device that the motor is driving.

Where the motor turns one or more steps beyond its commanded stopping point, this is known as *overshoot*.

Step loss may also occur if the motor continues turning after power has been interrupted (either intentionally or because of an external fault). In an open-loop system, the controller should be designed to reset the motor position when power is initiated.

Excessive Torque

When the motor is stationary and not powered, *detent torque* is the maximum turning force that can be applied without causing the shaft to turn. When the motor is stationary and the controller does deliver power to it, *holding torque* is the maximum turning force that can be applied without causing the shaft to turn, and *pull-in torque* is the maximum torque which the motor can apply to overcome resistance and reach full speed. When the motor is running, *pull-out torque* is the maximum torque the motor can deliver without suffering step loss (pulling it out of sync with its controller). Some or all of these values should be specified on the motor's datasheet. Exceeding any of them will result in step loss.

Hysteresis

When a controller directs a stepper motor to seek a specified position, the term *hysteresis* is often used to mean the total error between the actual position it reaches when turning clockwise, and the actual position it reaches when turning counter-clockwise. This difference may occur because a stepper motor tends to stop a fraction short of its intended position, especially under significant load. Any design that requires precision should be tested under real-world conditions to assess the hysteresis of the motor.

Resonance

A motor has a natural resonant frequency. If it is stepped near that frequency, vibration will tend to be amplified, which can cause positional errors, gear wear (if gears are attached), bearing wear, noise, and other issues. A good datasheet should specify the resonant frequency of the motor, and the motor should run above that frequency if possible. The problem can be addressed by rubber motor mounts or by using a resilient component, such as a drive belt, in conjunction with the drive shaft. *Damping* the vibration may be attempted by adding weight to the motor mount.

Note that if the motor has any significant weight attached directly to its shaft, this will lower its resonant frequency, and should be taken into account.

Resonance may also cause *step loss* (see preceding sections).

Hunting

In a closed-loop system, a sensor on the motor reports its rotational position to the controller, and if necessary, the controller responds by adjusting the position of the motor. Like any feedback system, this entails some lag time, and at certain speeds the motor may start *hunting* or *oscillating* as the controller over-corrects and must then correct its correction. Some closed-loop controllers avoid this issue by running mostly in open-loop mode, using correction only when the motor experiences conditions (such as sudden speed changes), which are likely to cause step loss.

Saturation

While it may be tempting to increase the torque from a stepper motor by upping the voltage (which will increase the current through the stator coils), in practice motors are usually designed so that the cores of the coils will be close to saturation at the rated voltage. Therefore, increasing the voltage may achieve very little increase in power, while causing a significant increase in heat.

Rotor Demagnetization

The permanent magnets in a rotor can be partially demagnetized by excessive heat. Demagnetization can also occur if the magnets are exposed to high-frequency alternating current when the rotor is stationary. Therefore, attempting to run a stepper motor at high speed when the rotor is stalled can cause irrevocable loss of performance.

diode

26

The term **diode** almost always means a semiconductor device, properly known as a *PN junction diode*, although the full term is not often used. It was formerly known as a *crystal diode*. Before that, **diode** usually meant a type of *vacuum tube*, which is now rarely used outside of high-wattage RF transmitters and some high-end audio equipment.

OTHER RELATED COMPONENTS

- **rectifier** (See "Rectification" (page 227))
- **unijunction transistor** (See Chapter 27)
- **LED** (light-emitting diode) (Volume 2)

What It Does

A diode is a two-terminal device that allows current to flow in one direction, known as the *forward direction,* when the *anode* of the diode has a higher positive potential than the *cathode*. In this state, the diode is said to be *forward biased*. If the polarity of the voltage is reversed, the diode is now *reverse biased*, and it will attempt to block current flow, within its rated limits.

Diodes are often used as *rectifiers* to convert alternating current into direct current. They may also be used to suppress voltage spikes or protect components that would be vulnerable to reversed voltage, and they have specialized applications in high-frequency circuits.

A *Zener diode* can regulate voltage, a *varactor diode* can control a high-frequency oscillator, and *tunnel diodes*, *Gunn diodes*, and *PIN diodes* have high-frequency applications appropriate to their rapid switching capability. An **LED** (*light-emitting diode*) is a highly efficient light source, which is discussed in Volume 2 of this encyclopedia. A **photosensitive diode** will adjust its ability to pass current depending on the light that falls upon it, and is included as a *sensor* in Volume 3.

See Figure 26-1 for schematic symbols representing a generic diode.



Figure 26-1. *Commonly used schematic symbols for a generic diode. All the symbols are functionally identical. The direction of the arrow formed by the triangle indicates the direction of conventional current (from positive to negative) when the diode is forward-biased.*

The basic diode symbol is modified in various ways to represent variants, as shown in Figure 26-2.

At top

Each symbol in the group of six indicates a Zener diode. All are functionally identical.

Bottom-left
Tunnel diode.

Bottom-center
Schottky diode.

Bottom-right
Varactor.

A triangle with an open center does not indicate any different function from a triangle with a solid center. The direction of the arrow always indicates the direction of conventional current, from positive to negative, when the diode is forward-biased, although the functionality of Zener diodes and varactors depends on them being reverse-biased, and thus they are used with current flowing opposite to the arrow symbol. The bent line used in the Zener symbol can be thought of as an opened letter Z, while the curled line used in the Schottky diode symbol can be thought of as a letter S, although these lines are sometimes drawn flipped left-to-right.



Figure 26-2. *Commonly used schematic symbols for specialized types of diodes. See text for details.*

A range of rectifier and signal diodes is shown in Figure 26-3. (Top: Rectifier diode rated 7.5A at 35VDC. Second from top: Rectifier diode rated 5A at 35VDC. Center: Rectifier diode rated 3A at 35VDC. Second from bottom: 1N4001 Rectifier diode rated 1A at 35VDC. Bottom: 1N4148 signal switching diode rated at 300mA.) All values are for forward continuous current and RMS voltage. Each cylindrical diode is marked with a silver stripe (a black stripe on the 1N4148) to identify its *cathode*, or the end of the diode that should be "more negative" when the component is forward biased. Peak current can greatly exceed continuous current without damaging the component. Datasheets will provide additional information.



Figure 26-3. *Diodes ranging in continuous forward-current capability from 7.5A (top) to 300mA (bottom). See text for additional details.*

How It Works

A PN diode is a two-layer *semiconductor*, usually fabricated from silicon, sometimes from germanium, and rarely from other materials. The layers are doped with impurities to adjust their electrical characteristics (this concept is explained in more detail in Chapter 28). The *N layer* (on the negative, cathode side) has a surplus of electrons, creating a net negative charge. The *P layer* (on the positive, anode side) has a deficit of electrons, creating a net positive charge. The deficit of electrons can also be thought of as a surplus of "positive charges," or more accurately, a surplus of *electron holes*, which can be considered as spaces that electrons can fill.

When the negative side of an external voltage source is connected with the cathode of a diode, and the positive side is connected with the anode, the diode is forward-biased, and electrons and electron holes are forced by mutual repulsion toward the junction between the n and p layers (see Figure 26-4). In a silicon diode, if the potential difference is greater than approximately 0.6 volts, this is known as the *junction threshold voltage*, and the charges start to pass through the junction. The threshold is only about 0.2 volts in a germanium diode, while in a Schottky diode it is about 0.4 volts.

If the negative side of an external voltage source is connected with the anode of a diode and positive side is connected with the cathode, the diode is now reverse-biased, and electrons and electron holes are attracted away from the junction between the n and p layers. The junction is now a *depletion region*, which blocks current.

Like any electronic component, a diode is not 100% efficient. When it is forward-biased and is passing current, it imposes a small voltage drop of around 0.7V for a silicon-based diode (Schottky diodes can impose a drop of as little as 0.2V, germanium diodes 0.3V, and some LEDs between 1.4V and 4V). This energy is dissipated as heat. When the diode is reverse-biased, it is still not 100% efficient, this time in its task of blocking current. The very small amount of current that manages to get through is known as *leakage*. This is almost always less than 1mA and may be just a few µA, depending on the type of diode.



Figure 26-4. *Inside a PN junction diode. Left: in forward-biased mode, voltage from a battery (bottom, with plates colored for clarity) forces charges in the N and P layers toward the central junction of the diode. Current begins to flow. Right: in reverse-biased mode, charges in the N and P layers are attracted away from the central junction, which becomes a depletion region, unable to pass significant current.*

The performance of a theoretical generic PN diode is illustrated in Figure 26-5. The right-hand side of the graph shows that if a diode is forward-biased with a gradually increasing potential, no current passes until the diode reaches its junction threshold voltage, after which the current rises very steeply, as the *dynamic resistance* of the diode diminishes to near zero. The left-hand side of the graph shows that when the diode is reverse-biased with a gradually increasing potential, initially a very small amount of current passes as leakage (the graph exaggerates this for clarity). Eventually, if the potential is high enough, the diode reaches its intrinsic *breakdown voltage*, and once again its effective resistance diminishes to near zero. At either end of the curve, the diode will be easily and permanently damaged by excessive current. With the exception of Zener diodes and varactors, reverse bias on a diode should not be allowed to reach the breakdown voltage level.

The graph in Figure 26-5 does not have a consistent scale on its Y axis, and in many diodes the magnitude of the (reverse-biased) breakdown voltage will be as much as 100 times the magnitude of the (forward-biased) threshold voltage. The graph has been simplified for clarity.



Figure 26-5. *As the forward voltage across a diode reaches the junction threshold, the diode begins passing current. If the voltage across the diode is reversed, initially a small amount of current leakeage occurs. Excessive forward or reverse voltage will create sufficient current to destroy the component.*

Variants

Packaging

Some diodes have no information at all printed on them, while others may have a part number. Any additional information is rare. No convention exists for indicating the electrical characteristics of the component by colors or abbreviations. If one terminal is marked in any way, almost certainly it is the cathode. One way to remember the meaning of a stripe on the cathode end of a rectifier diode or signal diode is by thinking of it as resembling the line in the diode schematic symbol.

Signal Diodes

Also known as *switching diodes* and *high-speed diodes*, their small size provides a low junction capacitance, enabling fast response times. They are not designed to withstand high currents. Signal diodes traditionally were packaged with axial leads for through-hole installation (like traditional-style resistors). Although this format still exists, signal diodes are now more commonly available in surface-mount formats.

Rectifier Diodes

Physically larger than signal diodes, and capable of handling higher currents. Their higher junction capacitance makes them unsuitable for fast switching. Rectifier diodes often have axial leads, although different package formats are used where higher currents are involved, and may include a heat sink, or may have provision for being attached to a heat sink.

There are no generally agreed maximum or minimum ratings to distinguish signal diodes from rectifier diodes.

Zener Diode

A Zener diode generally behaves very similarly to a signal or rectifier diode, except that its breakdown voltage is lower.

The Zener is intended to be reverse-biased; that is, conventional current is applied through it “in the wrong direction” compared with conventional diodes. As the current increases, the *dynamic resistance* of the Zener diode decreases. This relationship is shown in Figure 26-6, where the two colored curves represent the performance of different possible Zener diodes. (The curves are adapted from a manufacturer’s datasheet.) This behavior allows the Zener to be used in simple voltage-regulator circuits, as it can allow a reverse current to flow at a voltage limited by the diode's breakdown voltage. Other applications for Zener diodes are described in "DC Voltage Regulation and Noise Suppression" (page 230). A typical Zener diode is shown in Figure 26-7.



Figure 26-6. *A manufacturer's datasheet may include graphs of this kind, showing the variation in dynamic resistance of two reverse-biased Zener diodes in response to changes in current.*



Figure 26-7. *A 1N4740 Zener diode.*

Transient Voltage Suppressor (TVS)

A form of Zener diode designed to protect sensitive devices from transient voltage spikes by clamping them—in other words, diverting the energy to ground. A TVS can absorb as much as 30,000 volts from a lightning strike or static discharge. Typically the Zener diode is incorporated in a network of other diodes in a surface-mount integrated circuit chip.

Zener diodes can also be used in circuits to handle electrostatic discharge (ESD), which can occur when a person unknowingly accumulates an electrostatic potential and then grounds it by touching an electronic device.

Schottky Diode

This type has a low junction capacitance, enabling faster switching than comparable generic silicon diodes. It also imposes a lower forward voltage drop, which can be desirable in low-voltage applications, and allows less power dissipation when a diode is necessary to control current flow. The Schottky diode is fabricated with a semiconductor-to-metal junction, and tends to be slightly more expensive than generic silicon diodes with similar voltage and current specifications.

Varactor Diode

Also known as a *varicap*, this type of diode has variable capacitance controlled by reverse voltage. While other diodes may exhibit this same phenomenon, the varactor is specifically designed to exploit it at very high frequencies. The voltage expands or contracts the depletion region in the junction between the P and N regions, which can be thought of as analogous to moving the plates of a capacitor nearer together or farther apart.

Because the capacitance of a varactor has a low maximum of about 100pF, its uses are limited. It is used extensively in RF applications where its voltage-controlled variable capacitance provides a uniquely useful way to control the frequency of an oscillator circuit. In almost all radio, cellular, and wireless receivers, a varactor controls a phase-locked loop oscillator. In ham radio receivers, it can be used to adjust the tuning of a filter that tracks an incoming radio frequency.

A varactor is always reverse-biased below its breakdown voltage, so that there is no direct conduction. The voltage that controls a varactor must be absolutely free from random fluctuations that would affect its resonant frequency.

Tunnel Diode, Gunn Diode, PIN Diode

Mostly used in very high frequency or microwave applications, where ordinary diodes are unacceptable because they have insufficiently high switching speeds.

Diode Array

Two or more diodes may be encapsulated in a single DIP or (more commonly) surface-mount integrated circuit chip. The internal configuration and the pinouts of the chip will vary from one device to another. Diode arrays may be used for termination of data lines to reduce reflection noise.

Bridge Rectifier

Although this is a diode array, it is commonly indexed in parts catalogues under the term *bridge rectifier*. Numerous through-hole versions are available with ratings as high as 25A, some designed for single-phase input while others process three-phase AC. Screw-terminal components can rectify more than 1,000 volts at 1,000 amps. The package does not usually include any provision for smoothing or filtering the output. See "Rectification" (page 227) for more information on the behavior of a bridge rectifier.

Values

A manufacturer's datasheet for a typical generic diode should define the following values, using abbreviations that may include those in the following list.

- Maximum sustained forward current: I_f or I_o or I_{Omax}
- Forward voltage (the voltage drop imposed by the diode): V_f
- Peak inverse DC voltage (may be referred to as maximum blocking voltage or breakdown voltage): P_{iv} or V_{dc} or V_{br}
- Maximum reverse current (also referred to as leakage): I_r

Datasheets may include additional values when the diode is used with alternating current, and will also include information on peak forward surge current and acceptable operating temperatures.

A typical signal diode is the 1N4148 (included at the bottom of Figure 26-3), which is limited to about 300mA forward current while imposing a voltage drop of about 1V. The component can tolerate a 75V peak inverse voltage. These values may vary slightly among different manufacturers.

Rectifier diodes in the 1N4001/1N4002/1N4003 series have a maximum forward current of 1A and will impose a voltage drop of slightly more than 1V. They can withstand 50V to 1,000V of inverse voltage, depending on the component. Here again, the values may vary slightly among different manufacturers.

Zener diodes have a different specification, as they are used with reverse bias as voltage-regulating devices rather than rectification devices. Manufacturers' data sheets are likely to contain the following terminology:

- Zener voltage (the potential at which the diode begins to allow reverse current flow when it is reverse-biased, similar to breakdown voltage): V_z
- Zener impedance or dynamic resistance (the effective resistance of the diode, specified when it is reverse-biased at the Zener voltage): Z_z

- Maximum or admissible Zener current (or reverse current): I_z or I_{zm}
- Maximum or total power dissipation: P_d or P_{tot}

Zener voltage may be defined within a minimum and maximum range, or as a simple maximum value.

Limits on forward current are often not specified, as the component is not intended to be forward-biased.

How to Use it

Rectification

A *rectifier diode*, as its name implies, is commonly used to rectify alternating current—that is, to turn AC into DC. A half-wave rectifier uses a single diode to block one-half of the AC sinewave. The basic circuit for a half-wave rectifier is shown in Figure 26-8. At top, the diode allows current to circulate counter-clockwise through the load. At bottom, the diode blocks current that attempts to circulate clockwise. Although the output has “gaps” between the pulses, it is usable for simple tasks such as lighting an LED, and with the addition of a smoothing capacitor, can power the coil of a DC relay.

A full-wave bridge rectifier employs four diodes to provide a more efficient output, usually filtered and smoothed with appropriate **capacitors**. The basic circuit is shown in Figure 26-9. A comparison of input and output waveforms for half-wave and full-wave rectifiers appears in Figure 26-10.

Discrete components are seldom used for this purpose, as off-the-shelf bridge rectifiers are available in a single integrated package. Rectifier diodes as discrete components are more likely to be used to suppress *back-EMF* pulses, as described below.



Figure 26-8. *A half-wave rectifier. In this configuration the diode allows AC current to circulate counter-clockwise but blocks it clockwise.*



Figure 26-9. *The basic circuit commonly used to form a bridge rectifier, with color added to indicate polarity. Wires shown in black are not passing current because diodes are blocking it. Note that the polarity at the load remains constant.*

An old but widely used design for a full-wave bridge rectifier is shown in Figure 26-11. This unit measured approximately 2″ × 2″ × 1.5″ and was divided into four sections (as indicated by the solder terminals on the right-hand side), each



Figure 26-10. *Top: The voltage-amplitude sinewave of an alternating current source that fluctuates between positive voltage (shown red) and negative voltage (shown blue) relative to a neutral (black) baseline. Center: AC current converted by a full-wave rectifier. Because the diodes do not conduct below their threshold voltage, small gaps appear between pulses. Bottom: Output from a half-wave rectifier.*

section corresponding with the functionality of one modern diode. Figure 26-12 shows relatively modern rectifier packages, the one on the left rated at 20A continuous at 800V RMS, the one on the right rated 4A continuous at 200V RMS. In Figure 26-13, the one on the left is rated 4A continuous at 50V RMS, whereas the one on the right is rated 1.5A at 200V RMS.

DC output from rectifier packages is usually supplied via the outermost pins, while the two pins near the center receive AC current. The positive DC pin may be longer than the other three, and is usually marked with a + symbol.

Full-wave bridge rectifiers are also available in surface-mount format. The one in Figure 26-14 is rated for half an amp continuous current.



Figure 26-11. *Prior to the perfection of chip fabrication in the late 1960s, it was common to find silicon rectifiers of this type, measuring about 2" square.*



Figure 26-12. *Full-wave bridge rectifies are commonly available in packages such as these. See text for details.*

Back-EMF Suppression

A relay coil, motor, or other device with significant inductance will typically create a spike of voltage when it is turned on or off. This *EMF* can be shunted through a rectifier diode to safeguard other components in the circuit. A diode in this configuration may be referred to as a *protection diode*, a *clamp diode*, or *transient suppressor*. See Figure 26-15.



Figure 26-13. *Smaller full-wave bridge rectifiers capable of 1.5A to 4A continuous current.*



Figure 26-14. *This surface-mount component contains four diodes forming a full-wave bridge rectifier circuit, and can pass 0.5A continuous current. It measures approximately 0.2" square.*

Voltage Selection

A diode is sensitive to the relative voltage between its anode and cathode terminals. In other words, if the cathode is at 9V relative to the ground in the circuit, and the anode is at 12V, the 3V difference will easily exceed the threshold voltage, and the diode will pass current. (Actual tolerable values will depend on the forward voltage capability of the diode.) If the voltages are reversed, the diode will block the current.



Figure 26-15. *A rectifier diode is very often placed across a motor (top), relay (bottom), or other device with significant inductance that creates a spike of reverse voltage when switched on or off. The surge is shunted through the diode, protecting other components in the circuit.*

This attribute can be used to make a device choose automatically between an AC adapter and a 9V battery. The schematic is shown in Figure 26-16. When an AC adapter that delivers 12VDC is plugged into a wall outlet, the adapter competes with the battery to provide power to a voltage regulator. The battery delivers 9VDC through the lower diode to the cathode side of the upper diode, but the AC adapter trumps it with 12VDC through the upper diode. Consequently, the battery ceases to power the circuit until the AC adapter is unplugged, at which point the battery takes over, and the upper diode now prevents the battery from trying to pass any current back through the AC adapter.

The voltage regulator in this schematic accepts either 12VDC or 9VDC and converts it to 5VDC. (In the case of 12VDC, the regulator will waste more power, which will be dissipated as waste heat.)



Figure 26-16. *Two diodes with their cathodes tied together will choose automatically between an AC adapter that delivers 12VDC and an internal 9V battery.*

Voltage Clamping

A diode can be used to *clamp* a voltage to a desired value. If an input to a 5V CMOS semiconductor or similarly sensitive device must be prevented from rising out of range, the anode of a diode can be connected to the input and the cathode to a 5V voltage source. If the input rises much above 5.6V, the potential difference exceeds the diode's junction threshold, and the diode diverts the excess energy. See Figure 26-17.



Figure 26-17. *A clamping diode can limit output voltage—in this example, to about 5.6V. If the input rises above that value relative to the common ground, the potential difference across the diode feeds the excess voltage back through it to the 5V source.*

Logic Gate

A signal diode is less than ideal as a logic gate, because it imposes a typical 0.6V voltage reduction, which can be significant in a 5V circuit and is probably unacceptable in a 3.3V circuit. Still, it can be useful on the output side—for example, if two or more outputs from a logic chip or microcontroller are intended to drive, or share, another device such as a single **LED**, as shown in Figure 26-18. In this role, the diodes wired in parallel behave similarly to an OR gate, while preventing either output from the chip from feeding current back into the other output.



Figure 26-18. *Two or more outputs from a logic chip or microcontroller may be coupled with diodes to power another device, such as an LED, while protecting the chip from backflow of current. The diodes form a logical OR gate.*

DC Voltage Regulation and Noise Suppression

As previously noted, the dynamic resistance of a reverse-biased Zener diode will diminish as the current increases. This relationship begins at the point where breakdown in the diode begins—at its *Zener voltage*--and is approximately linear over a limited range.

The unique behavior of the Zener makes it usable as a very simple voltage controller when placed in series with a resistor as shown in Figure 26-19. It is helpful to imagine the diode and the resistor as forming a kind of voltage divider, with power being taken out at point A in the schematic. If a supply fluctuation increases the input voltage, this will tend to increase the current flowing through the Zener, and its dynamic resistance will diminish accordingly. A lower resistance in its position in the voltage divider will reduce the output voltage at point A, thus tending to compensate for the surge in input voltage.

Conversely, if the load in the circuit increases, and tends to pull down the input voltage, the current



Figure 26-19. *A simplified, basic circuit illustrating the ability of a Zener diode to compensate for variations in the power supply or load in a circuit, creating an approximately constant voltage at point A.*

flowing through the Zener will diminish, and the voltage at point A will tend to increase, once again compensating for the fluctuation in the circuit.

As the series resistor would be a source of heat, a transistor could be added to drive the load, as shown in Figure 26-20.



Figure 26-20. *A transistor could be added to the circuit in the previous figure to reduce power waste through the resistor.*

A manufacturer's datasheet may provide guidance regarding the dynamic resistance of a Zener diode in response to current, as previously shown in Figure 26-6. In practice, a packaged **voltage regulator** such as the LM7805 would most likely be used instead of discrete components, since it includes self-calibrating features, requires no series resistor, and is relatively unaffected by temperature. However, the LM7805 contains its own Zener diode, and the principle of operation is still the same.

AC Voltage Control and Signal Clipping

A more practical Zener application would be to limit AC voltage and/or impose clipping on an AC sinewave, using two diodes wired in series with opposed polarities. The basic schematic is shown in Figure 26-21, while clipping of the AC sinewave is illustrated in Figure 26-22. In this application, when one diode is reverse-biased, the other is forward-biased. A forward-biased Zener diode works like any other diode: it allows current to pass relatively freely, so long as the voltage exceeds its threshold. When the AC current reverses, the Zeners trade their functions, so that the first one merely passes current while the second one limits the voltage. Thus, the diodes divert peak voltage away from the load. The Zener voltage of each diode would be chosen to be a small margin above the AC voltage for voltage control, and below the AC voltage for signal clipping.



Figure 26-21. *Two Zener diodes placed in series, with opposite polarities, can clip or limit the voltage sinewave of an AC signal.*

Voltage Sensing

A Zener diode can be used to sense a small shift in voltage and provide a switched output in response.



Figure 26-22. *AC input showing a pure sinewave (left) and a clipped version (right) created by Zener diodes wired in series, as in the previous figure.*

In Figure 26-23, the upper schematic shows a Zener diode preventing voltage from reaching the emitter of a PNP transistor while the divided input signal is below the Zener (breakdown) voltage of the diode. In this mode, the transistor is relatively non-conductive, very little current flows through it, and the output is now at near-zero voltage. As soon as the input signal rises above the Zener voltage, the transistor switches on and power is supplied to the output. The input is thus replicated in the output, as shown in the upper portion of Figure 26-24.

In Figure 26-23, the lower schematic shows a Zener diode preventing voltage from reaching the base of an NPN transistor while the input signal is below the Zener (breakdown) voltage of the diode. In this mode, the transistor is relatively non-conductive, and power is supplied to the output. As soon as the input signal rises above the Zener voltage, the transistor is activated, diverting the current to ground and bypassing the output, which is now at near-zero voltage. The input is thus inverted, as shown in the lower portion of Figure 26-24 (provided there is enough current to drive the transistor into saturation).



Figure 26-23. *A Zener diode can be used in conjunction with a PNP transistor. See text for details.*

What Can Go Wrong

Overload

If maximum forward current is exceeded, the heat generated is likely to destroy the diode. If the diode is reverse-biased beyond its peak in-



Figure 26-24. *Theoretical output from the transistors in the two previous schematics.*

verse voltage limit, the current will overwhelm the diode's ability to block it, and an *avalanche breakdown* will occur, once again probably destroying the component. The graph in Figure 26-5 illustrates the performance range of a hypothetical generic diode.

Reversed Polarity

Zener diodes look almost identical to other types, and all diodes share the same convention of marking the cathode for identification. Yet Zeners must be reverse-biased while others are forward-biased. This creates a significant risk of installing a diode "the wrong way around," with potentially destructive or at least confusing results, especially when used in a power supply. The very low resistance of a diode to forward current makes it especially vulnerable to burnout if installed incorrectly.

Wrong Type of Diode

If a Zener diode is used accidentally where a signal or rectifier diode is appropriate, the circuit will malfunction, as the Zener will probably have a much lower breakdown voltage, and therefore will not block reverse current. Conversely, if a signal or rectifier diode is used where the circuit calls for a Zener diode, reverse voltage will be clamped (or regulated at the diode's forward voltage value). Since diodes are often poorly marked, a sensible precaution is to store Zener diodes separately from all other types.

unijunction transistor

27

The unijunction transistor (UJT) and programmable unijunction transistor (PUT) are different internally, but are sufficiently similar in function to be combined in this entry.

OTHER RELATED COMPONENTS

- **diode** (See Chapter 26)
- **bipolar transistor** (See Chapter 28)
- **field-effect transistor** (See Chapter 29)

What It Does

Despite their names, the unijunction transistor (UJT) and programmable unijunction transistor (PUT) are not current-amplification devices like bipolar transistors. They are switching components that are more similar to diodes than to transistors.

The UJT can be used to build low- to mid-frequency oscillator circuits, while the PUT provides similar capability with the addition of more sophisticated control, and is capable of functioning at lower currents. The UJT declined in popularity during the 1980s after introduction of components such as the *555 timer*, which offered more flexibility and a more stable output frequency, eventually at a competitive price. UJTs are now uncommon, but PUTs are still available in quantity as through-hole discrete components. Whereas an integrated circuit such as a 555 timer generates a square wave, unijunction transistors in oscillator circuits generate a series of voltage spikes.

The PUT is often used to trigger a **thyristor** (described in Volume 2) and has applications in low-power circuits, where it can draw as little as a few microamps.

Schematic symbols for the two components are shown in Figure 27-1 and Figure 27-2. Although the symbol for the UJT is very similar to the symbol for a field-effect transistor (FET), its behavior is quite different. The bent arrow identifies the UJT, while a straight arrow identifies the FET. This difference is of significant importance.

The schematic symbol for a PUT indicates its function, as it resembles a diode with the addition of a gate connection.



Figure 27-1. *Schematic symbol for a unijunction transistor (UJT). Note the bent arrow. The symbol for a field-effect transistor looks similar, but has a straight arrow. The functionality of the two components is very different.*

In Figure 27-3, the transistors at left and center are old-original unijunction transistors, while the one at right is a programmable unijunction transistor. (Left: Maximum 300mW, 35V interbase voltage. Center: 450mW, 35V interbase voltage. Right: 300mW, 40V gate-cathode forward voltage, 40V anode-cathode voltage.)



Figure 27-2. *Schematic symbol for a programmable unijunction transistor (PUT). The symbol accurately suggests the similarity in function to a diode, with the addition of a gate to adjust the threshold voltage.*



Figure 27-3. *The unijunction transistors at left and center are becoming obsolete; the one at the right is a programmable unijunction transistor (PUT), still readily available and widely used as a thyristor trigger.*

How It Works

The UJT is a three-terminal semiconductor device, but contains only two sections sharing a single junction—hence its name. Leads attached to opposite ends of a single channel of N-type semiconductor are referred to as base 1 and base 2, with base 2 requiring a slightly higher potential than base 1. A smaller P-type insert, midway between base 1 and base 2, is known as the emitter.

The diagram in Figure 27-4 gives an approximate idea of internal function.

When no voltage is applied to the emitter, a relatively high resistance (usually more than 5K) prevents significant current flow from base 2 to base 1. When the positive potential at the emitter increases to a *triggering voltage* (similar to the *junction threshold voltage* of a forward-biased diode), the internal resistance of the UJT drops very rapidly, allowing current to enter the component via both the emitter and base 2, exiting at base 1. (The term "current" refers, here, to conventional current; electron flow is opposite.) Current flowing from base 2 to base 1 is significantly greater than current flowing from the emitter to base 1.



Figure 27-4. *Internal workings of a unijunction transistor.*

The graph in Figure 27-5 outlines the behavior of a UJT. As the voltage applied to the emitter increases, current flowing into the component from the emitter increases slightly, until the triggering voltage is reached. The component's internal resistance now drops rapidly. This pulls down the voltage at the emitter, while the current continues to increase significantly. Because of the drop in resistance, this is referred to as a *negative resistance* region. The resistance actually cannot fall below zero, but its change is negative. After emitter voltage drops to a minimum known as the *valley voltage*, the current continues to increase with a small increase in voltage. On datasheets, the peak current is often referred to as I_p while valley current is I_v.



Figure 27-5. *Response curve of a unijunction transistor (UJT). When positive potential at the emitter reaches the triggering voltage, internal resistance drops radically and the component goes through a phase known as "negative resistance" as current increases.*

Figure 27-6 shows a test circuit to demonstrate the function of a UJT, with a volt meter indicating its status. A typical supply voltage would range from 9VDC to 20VDC.



Figure 27-6. *A test circuit for a unijunction transistor (UJT) using a volt meter to show its response as a potentiometer increases the voltage applied to its emitter.*

A PUT behaves similarly in many ways to a UJT but is internally quite different, consisting of four semiconducting layers and functioning similarly to a thyristor.

The PUT is triggered by increasing the voltage on the anode. Figure 27-7 shows a test circuit for a PUT. This component is triggered when the voltage at its anode exceeds a threshold level, while the gate sets the threshold where this occurs. When the PUT is triggered, its internal resistance drops, and current flows from anode to cathode, with a smaller amount of current entering through the gate. This behavior is almost identical to that of a forward-biased diode, except that the threshold level can be controlled, or "programmed," according to the value of the positive potential applied at the gate, with R1 and R2 establishing that potential by functioning as a voltage divider.



Figure 27-7. *A test circuit for a programmable unijunction transistor (PUT) using a volt meter to show its response as a potentiometer increases the voltage applied to its anode.*

The voltage output of a PUT follows a curve that is very similar to that shown in Figure 27-5, although current and voltage would be measured at the cathode.

Variants

PUTs and UJTs are not made as surface-mount components.

UJTs are usually packaged in black plastic, although older variants were manufactured in cans. PUTs are almost all packaged in black plastic. With the leads pointing downward and the flat side facing toward the viewer, the lead functions of a PUT are usually anode, gate, and cathode, reading from left to right.

Values

The triggering voltage of a UJT can be calculated from the values of R1 and R2 in Figure 27-7 and the voltage at base 1. The term R_{bb} is often used to represent the sum of R1 + R2, with V_{bb} representing the total voltage across the two resistors (this is the same as the supply voltage in Figure 27-6). V_t, the triggering voltage, is given by:

$$V_t = V_{bb} * (R1 / R_{bb})$$

The term ($R1/R_{bb}$) is known as the *standoff ratio*, often represented by the Greek letter ϱ.

Typically the standoff ratio in a UJT is at least 0.7, as R1 is chosen to be larger than R2. Typical values for R1 and R2 could be 180Ω and 100Ω, respectively. If R4 is 50K and a 100K linear potentiometer is used for R3, the PUT should be triggered when the potentiometer is near the center of its range. The emitter saturation voltage is typically from 2V to 4V.

If using a PUT, typical values in the test circuit could be supply voltage ranging from 9VDC to 20VDC, with resistances 28K for R1 and 16K for R2, 20Ω for R5, 280K for R4, and a 500K linear potentiometer for R3. The PUT should be triggered when the potentiometer is near the center of its range.

Sustained forward current from anode to cathode is usually a maximum of 150mA, while from gate to cathode the maximum is usually 50mA. Power dissipation should not exceed 300mW. These values should be lower at temperatures above 25 degrees Centigrade.

Depending on the PUT being used, power consumption can be radically decreased by upping the resistor values by a multiple of 100, while supply voltage can be decreased to 5V. The cathode output from the PUT would then be connected with the base of an NPN transistor for amplification.

How to Use it

Figure 27-8 shows a simple oscillator circuit built around a UJT, Figure 27-9 shows a comparable circuit for a PUT. Initially the supply voltage charges the capacitor, until the potential at the emitter of the UJT or the gate of the PUT reaches the threshold voltage, at which point the capacitor discharges through the emitter and the cycle repeats. Resistor values would be similar to those used in the test circuits previously described, while a capacitor value of 2.2µF would provide a visible pulse of the LED. Smaller capacitor values would enable faster oscillation. In the PUT circuit, adjusting the values of R1 and R2 would allow fine control of triggering the semiconductor.



Figure 27-8. *A basic oscillator circuit using a unijunction transistor (UJT). As the capacitor accumulates charge, the voltage on the emitter increases until it triggers the UJT, at which point the capacitor discharges through the emitter.*

Probably the most common use for a PUT at this time is to trigger a **thyristor**.



Figure 27-9. *A basic oscillator circuit using a programmable unijunction transistor (PUT). As the capacitor accumulates charge, the voltage on the anode increases until it triggers the PUT, at which point the capacitor discharges through the anode. The gate voltage is preset by R1 and R2 to adjust the triggering voltage.*

What Can Go Wrong

Name Confusion

A programmable unijunction transistor (PUT) is sometimes referred to simply as a "unijunction transistor" (UJT). Bearing in mind the totally different modes of operation of UJT and PUT, the PUT should always be identified by its acronym or by its full name. A circuit will not function if a UJT is substituted for a PUT, or a PUT is substituted for a UJT.

Incorrect Bias

Neither the UJT nor the PUT is designed to operate with reverse bias. In the UJT, a small forward bias should be applied from base 2 to base 1 (that is, base 2 should be at a higher potential relative to base 1) regardless of the voltage on the emitter. The emitter voltage may vary from 0 volts upward. The PUT must be forward biased between its anode and cathode (the anode must have a higher potential relative to the cathode), with an intermediate positive voltage at the gate established by resistors R1 and R2 functioning as a voltage divider (see Figure 27-7). Failure to observe correct biasing will result in unpredictable behavior and possible damage to the component.

Overload

Like any semiconductor, the UJT and the PUT must be protected from excessive current, which can burn out the component. Never connect either of these components directly across a power source without appropriate resistances to limit current flow. Maximum continuous power dissipation for UJTs and PUTs is usually 300mW.

28

bipolar transistor

The word *transistor*, on its own, is often used to mean *bipolar transistor*, as this was the type that became most widely used in the field of discrete semiconductors. However, *bipolar transistor* is the correct term. It is sometimes referred to as a *bipolar junction transistor* or *BJT*.

OTHER RELATED COMPONENTS

- **unijunction transistor** (See Chapter 27)
- **field-effect transistor** (See Chapter 29)
- **diac** (Volume 2)
- **triac** (Volume 2)
- **relay** (Volume 2)
- **solid-state relay** (Volume 2)

What It Does

A bipolar transistor amplifies fluctuations in current or can be used to switch current on and off. In its amplifying mode, it replaced the *vacuum tubes* that were formerly used in the amplification of audio signals and many other applications. In its switching mode it resembles a **relay**, although in its "off" state the transistor still allows a very small amount of current flow, known as *leakage*.

A bipolar transistor is described as a *discrete* semiconductor device when it is individually packaged, with three leads or contacts. A package containing multiple transistors is an *integrated circuit*. A Darlington pair actually contains two transistors, but is included here as a discrete component because it is packaged similarly and functions like a single transistor. Most integrated circuits will be found in Volume 2 of this encyclopedia.

How It Works

Although the earliest transistors were fabricated from germanium, silicon has become the most commonly used material. Silicon behaves like an insulator, in its pure state at room temperature, but can be "doped" (carefully contaminated) with impurities that introduce a surplus of electrons unbonded from individual atoms. The result is an *N-type semiconductor* that can be induced to allow the movement of electrons through it, if it is *biased* with an external voltage. *Forward bias* means the application of a positive voltage, while *reverse bias* means reversing that voltage.

Other dopants can create a deficit of electrons, which can be thought of as a surplus of "holes" that can be filled by electrons. The result is a *P-type semiconductor*.

A bipolar NPN transistor consists of a thin central P-type layer sandwiched between two thicker N-type layers. The three layers are referred to as *collector*, *base*, and *emitter*, with a wire or contact attached to each of them. When a negative charge is applied to the emitter, electrons are forced by mutual repulsion toward the central base layer. If a forward bias (positive potential) is applied to the base, electrons will tend to be attracted out through the base. However, because the base layer is so thin, the electrons are now close to the collector. If the base voltage increases, the additional energy encourages the electrons to jump into the collector, from which they will make their way to the positive current source, which can be thought of as having an even greater deficit of electrons.

Thus, the emitter of an NPN bipolar transistor emits electrons into the transistor, while the collector collects them from the base and moves them out of the transistor. It is important to remember that since electrons carry a negative charge, the flow of electrons moves from negative to positive. The concept of positive-to-negative current is a fiction that exists only for historical reasons. Nevertheless, the arrow in a transistor schematic symbol points in the direction of conventional (positive-to-negative) current.

In a PNP transistor, a thin N-type layer is sandwiched between two thicker P-type layers, the base is negatively biased relative to the emitter, and the function of an NPN transistor is reversed, as the terms “emitter” and “collector” now refer to the movement of electron-holes rather than electrons. The collector is negative relative to the base, and the resulting positive-to-negative current flow moves from emitter to base to collector. The arrow in the schematic symbol for a PNP transistor still indicates the direction of positive current flow.

Symbols for NPN and PNP transistors are shown in Figure 28-1. The most common symbol for an NPN transistor is shown at top-left, with letters C, B, and E identifying collector, base, and emitter. In some schematics the circle in the symbols is omitted, as at top-right.

A PNP transistor is shown in the center. This is the most common orientation of the symbol, since its collector must be at a lower potential than its emitter, and ground (negative) is usually at the bottom of a schematic. At bottom, the PNP symbol is inverted, allowing the positions of emitter and collector to remain the same as in the symbol for the NPN transistor at the top. Other orientations of transistor symbols are often found, merely to facilitate simpler schematics with fewer conductor crossovers. The direction of the arrow in the symbol (pointing out or pointing in) always differentiates NPN from PNP transistors, respectively, and indicates current flowing from positive to negative.



Figure 28-1. *Symbols for an NPN transistor (top) and a PNP transistor (center and bottom). Depending on the schematic in which the symbol appears, it may be rotated or inverted. The circle may be omitted, but the function of the component remains the same.*

NPN transistors are much more commonly used than PNP transistors. The PNP type was more difficult and expensive to manufacture initially, and circuit design evolved around the NPN type. In addition, NPN transistors enable faster switching, because electrons have greater mobility than electron-holes.

To remember the functions of the collector and the emitter in an NPN transistor, you may prefer to think in terms of the collector collecting positive current *into* the transistor, and the emitter emitting positive current *out of* the transistor. To remember that the emitter is always the terminal with an arrow attached to it (both in NPN and PNP schematic symbols), consider that "emitter" and "arrow" both begin with a vowel, while "base" and "collector" begin with consonants. To remember that an NPN transistor symbol has its arrow pointing outward, you can use the mnemonic "N/ever P/ointing i/N."

Current flow for NPN and PNP transistors is illustrated in Figure 28-2. At top-left, an NPN transistor passes no current (other than a small amount of leakage) from its collector to its emitter so long as its base is held at, or near, the potential of its emitter, which in this case is tied to negative or ground. At bottom-left, the purple positive symbol indicates that the base is now being held at a *relatively* positive voltage, at least 0.6 volts higher than the emitter (for a silicon-based transistor). This enables electrons to move from the emitter to the collector, in the direction of the blue arrows, while the red arrows indicate the conventional concept of current flowing from positive to negative. The smaller arrows indicate a smaller flow of current. A resistor is included to protect the transistor from excessive current, and can be thought of as the load in these circuits.

At top-right, a PNP transistor passes no current (other than a small amount of leakage) from its emitter to its collector so long as its base is held at, or near, the potential of the emitter, which in this case is tied to the positive power supply. At bottom-right, the purple negative symbol indicates that the base is now being held at a *relatively* negative voltage, at least 0.6 volts lower than the emitter. This enables electrons and current to flow as shown. Note that current flows into the base in the NPN transistor, but out from the base in the PNP transistor, to enable conductivity. In both diagrams, the resistor that would normally be included to protect the base has been omitted for the sake of simplicity.



Figure 28-2. *Current flow through NPN and PNP transistors. See text for details.*

An NPN transistor amplifies its base current only so long as the positive potential applied to the collector is greater than the potential applied to the base, and the potential at the base must be greater than the potential at the emitter by at least 0.6 volts. So long as the transistor is biased in this way, and so long as the current values remain within the manufacturer's specified limits, a small fluctuation in current applied to the base will induce a much larger fluctuation in current between the collector and the emitter. This is why a transistor may be described as a *current amplifier*.

A *voltage divider* is often used to control the base potential and ensure that it remains less than the potential on the collector and greater than the potential at the emitter (in an NPN transistor). See Figure 28-3.

See Chapter 10 for additional information about the function of a voltage divider.



Figure 28-3. *Resistors R1 and R2 establish a voltage divider to apply acceptable bias to the base of an NPN transistor.*

Current Gain

The amplification of current by a transistor is known as its *current gain* or *beta value*, which can be expressed as the ratio of an increase in collector current divided by the increase in base current that enables it. Greek letter β is customarily used to represent this ratio. The formula looks like this:

$$\beta = \Delta I_c \ / \ \Delta I_b$$

where I_c is the collector current and I_b is the base current, and the Δ symbol represents a small change in the value of the variable that follows it.

Current gain is also represented by the term h_{FE}, where E is for the common Emitter, F is for Forward current, and lowercase letter h refers to the transistor as a "hybrid" device.

The beta value will always be greater than 1 and is often around 100, although it will vary from one type of transistor to another. It will also be affected by temperature, voltage applied to the transistor, collector current, and manufacturing inaccuracies. When the transistor is used outside of its design parameters, the formula to determine the beta value no longer directly applies.

There are only two connections at which current can enter an NPN transistor and one connection where it can leave. Therefore, if I_e is the current from the emitter, I_c is the current entering the collector, and I_b is the current entering the base:

$$I_e = I_c + I_b$$

If the potential applied to the base of an NPN transistor diminishes to the point where it is less than 0.6V above the potential at the emitter, the transistor will not conduct, and is in an "off" state, although a very small amount of leakage from collector to emitter will still occur.

When the current flowing into the base of the transistor rises to the point where the transistor cannot amplify the current any further, it becomes *saturated*, at which point its internal impedance has fallen to a minimal value. Theoretically this will allow a large flow of current; in practice, the transistor should be protected by resistors from being damaged by high current resulting from saturation.

Any transistor has maximum values for the collector current, base current, and the potential difference between collector and emitter. These values should be provided in a datasheet. Exceeding them is likely to damage the component.

Terminology

In its *saturated mode*, a transistor's base is saturated with electrons (with no room for more) and the internal impedance between collector and emitter drops as low as it can go.

The *cutoff mode* of an NPN transistor is the state where a low base voltage eliminates all current flow from collector to emitter other than a small amount of leakage.

The *active mode*, or *linear mode*, is the intermediate condition between cutoff and saturated, where the beta value or h_{FE} (ratio of collector current to base current) remains approximately constant. That is, the collector current is almost linearly proportional to the base current. This linear relationship breaks down when the transistor nears its saturation point.

Variants

Small signal transistors are defined as having a maximum collector current of 500 mA and maximum collector power dissipation of 1 watt. They can be used for audio amplification of low-level inputs and for switching of small currents. When determining whether a small-signal transistor can control an inductive load such as a motor or relay coil, bear in mind that the initial current surge will be greater than the rated current draw during sustained operation.

Small switching transistors have some overlap in specification with small signal transistors, but generally have a faster response time, lower beta value, and may be more limited in their tolerance for collector current. Check the manufacturer's datasheet for details.

High frequency transistors are primarily used in video amplifiers and oscillators, are physically small, and have a maximum frequency rating as high as 2,000 MHz.

Power transistors are defined as being capable of handling at least 1 watt, with upper limits that can be as high as 500 watts and 150 amps. They are physically larger than the other types, and may be used in the output stages of audio amplifiers, and in switching **power supplies** (see Chapter 16). Typically they have a much lower current gain than smaller transistors (20 or 30 as opposed to 100 or more).

Sample transistors are shown in Figure 28-4. Top: A 2N3055 NPN power transistor. This type was originally introduced in the late 1960s, and versions are still being manufactured. It is often found in power supplies and in push-pull power amplifiers, and has a total power dissipation rating of 115W. Second row, far left: general purpose switching-amplification PNP power transistor rated for up to 50W power dissipation. Second row, far right: A high-frequency switching transistor for use in lighting ballast, converters, inverters, switching regulators, and motor control systems. It tolerates relatively high voltages (up to 700V collector-emitter peak) and is rated for up to 80W total power dissipation. Second row, center-left and center-right: Two variants of the 2N2222 NPN small signal switching transistor, first introduced in the 1960s, and still very widely used. The metal can is the TO-19 package, capable of slightly higher power dissipation than the cheaper plastic TO-92 package (1.8W vs. 1.5W with a collector temperature no greater than 25 degrees Centigrade).

Packaging

Traditionally, small-signal transistors were packaged in small aluminum "cans" about 1/4" in diameter, and are still sometimes found in this form. More commonly they are embedded in buds of black plastic. Power transistors are packaged either in a rectangular module of black



Figure 28-4. *Samples of commonly used transistors. See text for details.*

plastic with a metal back, or in a round metal "button." Both of these forms are designed to dissipate heat by being screw-clamped to a *heat sink*.

Connections

Often a transistor package provides no clue as to which lead is the emitter, which lead is the base, and which lead is the collector. Old can-style packaging includes a protruding tab that usually points toward the emitter, but not always. Where power transistors are packaged in a metal enclosure, it is typically connected internally with the collector. In the case of surface-mount transistors, look for a dot or marker that should identify the base of a bipolar transistor or the gate of a field-effect transistor.

A through-hole transistor usually has its part number printed or engraved on its package, although a magnifying glass may be necessary to see this. The component's datasheet may then be checked online. If a datasheet is unavailable, meter-testing will be necessary to confirm the functions of the three transistor leads. Some multimeters include a transistor-test function, which may validate the functionality of a transistor while also displaying its beta value. Otherwise, a meter can be put in diode-testing mode, and an unpowered NPN transistor should behave as if diodes are connected between its leads as shown in Figure 28-5. Where the identities of the transistor's leads are unknown, this test will be sufficient to identify the base, after which the collector and emitter may be determined empirically by testing the transistor in a simple low-voltage circuit such as that shown in Figure 28-6.



Figure 28-5. *An NPN transistor can behave as if it contains two diodes connected as shown. Where the functions of the leads of the transistor are unknown, the base can be identified by testing for conductivity.*

How to Use it

The following abbreviations and acronyms are common in transistor datasheets. Some or all of the letters following the initial letter are usually, but not always, formatted as subscripts:

h_{FE}

Forward current gain

β

Same as hFE

V_{CEO}

Voltage between collector and emitter (no connection at base)



Figure 28-6. *This simple schematic can be used to breadboard-test a transistor empirically, determining its functionality and the identities of its collector and emitter leads.*

V_{CBO}

Voltage between collector and base (no connection at emitter)

V_{EBO}

Voltage between emitter and base (no connection at collector)

V_{CEsat}

Saturation voltage between collector and emitter

V_{BEsat}

Saturation voltage between base and emitter

I_c

Current measured at collector

I_{CM}

Maximum peak current at collector

I_{BM}

Maximum peak current at base

P_{TOT}

Total maximum power dissipation at room temperature

T_J

Maximum junction temperature to avoid damage

Often these terms are used to define “absolute maximum values” for a component. If these maximums are exceeded, damage may occur.

A manufacturer’s datasheet may include a graph showing the *safe operating area* (SOA) for a transistor. This is more common where power transistors are involved, as heat becomes more of an issue. The graph in Figure 28-7 has been adapted from a datasheet for a silicon diffused power transistor manufactured by Philips. The safe operating area is bounded at the top by a horizontal segment representing the maximum safe current, and at the right by a vertical segment representing the maximum safe voltage. However, the rectangular area enclosed by these lines is reduced by two diagonal segments representing the *total power limit* and the *second breakdown limit*. The latter refers to the tendency of a transistor to develop internal localized “hot spots” that tend to conduct more current, which makes them hotter, and able to conduct better—ultimately melting the silicon and causing a short circuit. The total power limit and the second breakdown limit reduce the safe operating area, which would otherwise be defined purely by maximum safe current and maximum safe voltage.

Uses for discrete transistors began to diminish when integrated circuits became cheaper and started to subsume multi-transistor circuits. For instance, an entire 5-watt audio amplifier, which used to be constructed from multiple components can now be bought on a chip, requiring just



Figure 28-7. *Adapted from a Philips datasheet for a power transistor, this graph defines a safe operating area (SOA) for the component. See text for details.*

a few external capacitors. More powerful audio equipment typically uses integrated circuits to process inputs, but will use individual power transistors to handle high-wattage output.

Darlington Pairs

Discrete transistors are useful in situations where current amplification or switching is required at just one location in a circuit. An example would be where one output pin from a **microcontroller** must switch a small motor on and off. The motor may run on the same voltage as the microcontroller, but requires considerably more current than the typical 20mA maximum available from a microcontroller output. A *Darlington pair* of transistors may be used in this application. The overall gain of the pair can be 100,000 or more. See Figure 28-8. If a power source feeding through a potentiometer is substituted for the microcontroller chip, the circuit can function as a motor speed control (assuming that a generic DC motor is being used).

In the application shown here, the microcontroller chip must share a common ground (not shown) with the transistors. The optional resistor may be necessary to prevent leakage from the first transistor (when in its "off" state) from triggering the second. The diode protects the transistors from voltage transients that are likely when the motor stops and starts.



Figure 28-8. *Where the emitter of one NPN transistor is coupled to the base of another, they form a Darlington pair (identified by the dashed rectangle in this schematic). Multiplying the gain of the first transistor by the gain of the second gives the total gain of the pair.*

A Darlington pair can be obtained in a single transistor-like package, and may be represented by the schematic symbol shown in Figure 28-9.

Various through-hole Darlington packages are shown in Figure 28-10.



Figure 28-9. *When a Darlington pair is embedded in a single transistor-like package, it may be represented by this schematic symbol. The leads attached to the package can be used as if they are the emitter, base, and collector of a single NPN transistor.*



Figure 28-10. *Various packaging options for Darlington pairs. From left to right: The 2N6426 contains a Darlington pair rated to pass up to 500mA continuous collector current. The 2N6043 is rated for 8A continuous. The ULN2003 and ULN2083 chips contain seven and eight Darlington pairs, respectively.*

Seven or eight Darlington pairs can be obtained in a single integrated chip. Each transistor pair in these chips is typically rated at 500mA, but they can be connected in parallel to allow higher currents. The chip usually includes protection diodes to allow it to drive inductive loads directly.

A typical schematic is shown in Figure 28-11. In this figure, the microcontroller connections are hypothetical and do not correspond with any actual chip. The Darlington chip is a ULN2003 or similar, containing seven transistor pairs, each with an "input" pin on the left and an "output" pin opposite it on the right. Any of pins 1 through 7 down the left side of the chip can be used to control a device connected to a pin on the opposite side.

A high input can be thought of as creating a negative output, although in reality the transistors inside the chip are sinking current via an external device—a motor, in this example. The device can have its own positive supply voltage, shown here as 12VDC, but must share a common ground with the microcontroller, or with any other component which is being used on the input side. The lower-right pin of the chip shares the 12VDC supply because this pin is attached internally to clamp diodes (one for each Darlington pair), which protect against surges caused by inductive loads. For this reason, the motor does not have a clamp diode around it in the schematic.

The Darlington chip does not have a separate pin for connection with positive supply voltage, because the transistors inside it are sinking power from the devices attached to it.



Figure 28-11. *A chip such as the ULN2003 contains seven Darlington pairs. It will sink current from the device it is driving. See text for details.*

A surface-mount Darlington pair is shown in Figure 28-12. This measures just slightly more than 0.1" long but is still rated for up to 500mA collector current or 250mW total power dissipation (at a component temperature no higher than 25 degrees Centigrade).



Figure 28-12. *A surface-mount package for a Darlington pair. Each square in the background grid measures 0.1". See text for additional details.*

Amplifiers

Two basic types of transistor amplifiers are shown in Figure 28-13 and Figure 28-14. The *common-collector* configuration has current gain but no voltage gain. The capacitor on the input side blocks DC current from entering the amplifier circuit, and the two resistors forming a voltage divider on the base of the transistor establish a voltage midpoint (known as the *quiescent point* or *operating point*) from which the signal to be amplified may deviate above and below.

The *common-emitter* amplifier provides voltage gain instead of current gain, but inverts the phase of the input signal. Additional discussion of amplifier design is outside the scope of this encyclopedia.

In switching applications, modern transistors have been developed to handle a lot of current compared with earlier versions, but still have some limitations. Few power transistors can handle more than 50A flowing from collector to emitter, and 1,000V is typically a maximum value. Electromechanical relays continue to exist because they retain some advantages, as shown in the table in Figure 28-15, which compares switching capabilities of transistors, **solid-state relays**, and electromechanical **relays**.



Figure 28-13. *The basic schematic for a common-collector amplifier. See text for details.*



Figure 28-14. *The basic schematic for a common-emitter amplifier. See text for details.*

	Transistor	Solid-State Relay	Electro-Mechanical Relay
Long-term reliability	Excellent	Excellent	Limited
NC contacts?	No	Yes	Yes
DT contacts?	No	No	Yes
Ability to switch large current	Limited	Some	Good
Ability to switch AC	No	Yes	Yes
Can be triggered by AC voltage?	No	Yes	Yes
Suitability for miniaturization	Excellent	Poor	Poor
Vulnerable to heat	Yes	Yes	Not very
Vulnerable to corrosion	No	No	Yes
OK at high speed	Excellent	Good	Poor
Price advantage for low-voltage low-current	Yes	No	No
Price advantage for high-voltage high-current	No	No	Yes
Current leakage when "off"	Yes	Yes	No
Trigger circuit isolated from switched circuit	No	Yes	Yes

Figure 28-15. *A comparison of characteristics of switching devices.*

What Can Go Wrong

Wrong Connections on a Bipolar Transistor

Failing to identify a transistor's leads or contacts correctly can obviously be a potential source of damage, but swapping the collector and emitter accidentally will not necessarily destroy the transistor. Because of the inherent symmetry of the device, it will in fact function with collector and emitter connections reversed. Rohm, a large semiconductor manufacturer, has included this scenario in its general information pages and concludes that the primary indicator of transposed connections is that the β value, or h_{FE} , drops to about 1/10th of specification. If you are using a transistor that works but provides much less amplification than you expect, check that the emitter and collector leads are not transposed.

Wrong Connections on a Darlington Pair Chip

While a single-component package for a Darlington pair functions almost indistinguishably from a single transistor, multiple Darlington pairs in a DIP package may create confusion because the component behaves differently from most other chips, such as logic chips.

A frequent error is to ground the output device instead of applying positive power to it. See Figure 28-11 and imagine an erroneous connection of negative power instead of the 12VDC positive power.

Additional confusion may be caused by reading a manufacturer's datasheet for a Darlington pair chip such as the ULN2003. The datasheet depicts the internal function of the chip as if it contains logic inverters. While the chip can be imagined as behaving this way, in fact it contains bipolar transistors that amplify the current applied to the base of each pair. The datasheet also typically will not show the positive connection that should be made to the common-diode pin (usually at bottom-right), to provide protection from surges caused by inductive loads. This pin must be distinguished carefully from the common-ground pin (usually at bottom-left). The positive connection to the common-diode pin is optional; the common-ground connection is mandatory.

Soldering Damage

Like any semiconductor, transistors are vulnerable to heat and can be damaged while soldering, although this seldom happens if a low-wattage iron is used. A copper alligator clip can be applied as a heat sink to each lead before it is soldered.

Excessive Current or Voltage

During use, a transistor will be damaged if it is subjected to current or voltage outside of its rated range. Passing current through a transistor without any series resistance to protect it will almost certainly burn it out, and the same thing can happen if incorrect resistor values are used.

The maximum wattage that a transistor can dissipate will be shown in its datasheet. Suppose, for example, this figure is 200mW, and you are using a 12VDC supply. Ignoring the base current, the maximum collector current will be 200 / 12 = approximately 15mA. If the transistor's emitter is connected to ground, and the load applied to the transistor output has a high impedance, and if we ignore the transresistance, Ohm's Law suggests that a resistor that you place between the collector and the supply voltage should have a resistance of at least 12 / 0.015 = 800 ohms.

When transistors are used in switching applications, it is customary for the base current to be 1/5th of the collector current. In the example discussed here, a 4.7K resistor might be appropriate. A meter should be used to verify actual current and voltage values.

Excessive Leakage

In a Darlington pair, or any other configuration where the output from one transistor is connected with the base of another, leakage from the first transistor while in its "off" state can be amplified by the second transistor. If this is unacceptable, a bypass resistor can be used to divert some of the leakage from the base of the second transistor to ground. Of course the resistor will also steal some of the base current when the first transistor is active, but the resistor value is typically chosen so that it takes no more than 10% of the active current. See Figure 28-8 for an example of a bypass resistor added to a Darlington pair.

field effect transistor

28

The term **field-effect transistor** encompasses a family primarily consisting of the *junction field-effect transistor* (or *JFET*, which is the simplest generic type) and the *metal-oxide semiconductor field-effect transistor* (or *MOSFET*, also sometimes known as an *insulated-gate field-effect transistor*, or *IGFET*). Because the principles of operation overlap considerably, the entire -FET family is grouped in this entry.

OTHER RELATED COMPONENTS

- **bipolar transitor** (See Chapter 28)
- **unijunction transistor** (See Chapter 27)
- **diode** (See Chapter 26)

What It Does

A field-effect transistor creates an electric field to control current flowing through a channel in a semiconductor. MOSFETs of microscopic size form the basis of complementary metal oxide semiconductor (CMOS) *integrated circuit chips*, while large discrete MOSFETs are capable of switching substantial currents, in lamp dimmers, audio amplifiers, and motor controllers. FETs have become indispensable in computer electronics.

A **bipolar transistor** is generally thought of as a *current amplifier* because the current passing through it is controlled by a smaller amount of current passing through the base. By contrast, all FETs are considered to be *voltage amplifiers*, as the control voltage establishes field intensity, which requires little or no current. The negligible leakage through the gate of an FET makes it ideal for use in low-power applications such as portable hand-held devices.

How It Works

This section is divided into two subsections, describing the most widely used FETs: JFETs and MOSFETs.

JFETs

A *junction field-effect transistor* (or *JFET*) is the simplest form of FET. Just as a bipolar transistor can be of NPN or PNP type, a JFET can have an *N-channel* or *P-channel*, depending whether the channel that transmits current through the device is negatively or positively *doped*. A detailed explanation of semiconductor doping will be found in the **bipolar transistor** entry.

Because negative charges have greater mobility, the N-channel type allows faster switching and is more commonly used than the P-channel type. A schematic symbol for it is shown in Figure 29-1 alongside the schematic for an NPN transistor. These symbols suggest the similarity of the devices as amplifiers or switches, but it is important to remember that the FET is a primarily a voltage amplifier while the bipolar transistor is a current amplifier.



Figure 29-1. *A comparison between schematic symbols for N-channel JFET (left) and NPN bipolar transistor (right) suggests their functional similarity as switches or amplifiers, although their behavior is markedly different.*

Three JFETs are shown in Figure 29-2. The N-channel J112 type is supplied by several manufacturers, the figure showing two samples, one from Fairchild Semiconductor (left) and the other from On Semiconductor (right). Although the full part numbers are different, the specifications are almost identical, including a drain-gate voltage of 35V, a drain-source voltage of 35V, and a gate current of 50mA. The metal-clad 2N4392 in the center has similar values but is three times the price, with a much higher power dissipation of 1.8W, compared with 300mW and 350mW for the other two transistors respectively.



Figure 29-2. *Junction Field Effect Transistors (JFETs). See text for details.*

Schematic symbols for N-channel and P-channel JFETs are shown in Figure 29-3, N-channel being on the left while P-channel is on the right. The upper-left and lower-left symbol variants are both widely used and are functionally identical. The upper-right and lower-right variants likewise mean the same thing. Because the upper variants are symmetrical, an S should be added to clarify which terminal is the source. In practice, the S is often omitted, allowing some ambiguity. While the source and drain of some JFETs are in fact interchangeable, this does not apply to all types.

The circle around each symbol is occasionally omitted when representing discrete components, and is almost always omitted when multiple FETs are shown connected to form an integrated circuit.



Figure 29-3. *Schematic symbols for junction field-effect transistors (JFETs). Left: N-channel. Right: P-channel. The symbols at top and bottom on each side are functionally identical. Circles may be omitted. Letter S may be omitted from the symmetrical symbol variants, even though this creates some ambiguity.*

The internal function of an N-channel JFET is shown diagrammatically in Figure 29-4. In this component, the source terminal is a source of electrons, flowing relatively freely through the N-doped channel and emerging through the drain. Thus, conventional current flows nonintuitively from the drain terminal, to the source terminal, which will be of lower potential.

The JFET is like a normally-closed switch. It has a low resistance so long as the gate is at the same potential as the source. However, if the potential of the gate is reduced below the potential of the source—that is, the gate acquires a more relatively negative voltage than the source—the current flow is *pinched off* as a result of the field created by the gate. This is suggested by the lower diagram in Figure 29-4.


Gate voltage
same as
Source voltage
Drain
N-channel JFET
Gate
Conventional Current
Electron Flow
No field effect
Source
Gate voltage
lower than
Source voltage
Drain
N-channel JFET
Reduced Conventional Current
Gate
Field Effect: Increased Depletion Region
Reduced Electron Flow
Source

Figure 29-4. *At top, conventional current flows freely from drain to source through the channel of an N-doped JFET. At bottom, the lowered voltage of the gate relative to the source creates a field effect that pinches off the flow of current.*

The situation for a P-channel JFET is reversed, as shown in Figure 29-5. The source is now positive (but is still referred to as the source), while the drain can be grounded. Conventional current now flows freely from source to drain, so long as the gate is at the same positive potential as the source. If the gate voltage rises above the source voltage, the flow is pinched off.

A bipolar transistor tends to block current flow by default, but becomes less resistive when its base is forward-biased. Therefore it can be referred to as an *enhancement device*. By contrast, an N-channel JFET allows current to flow by default, and becomes more resistive when its base is reverse-biased, which widens the *depletion layer* at the base junction. Consequently it can be referred to as a *depletion device*.


Gate voltage
same as
Source voltage
Drain
P-channel JFET
Gate
Electron Flow
Conventional Current
No field effect
Source
Gate voltage
higher than
Source voltage
Drain
P-channel JFET
Gate
Reduced Electron Flow
Field Effect: Increased Depletion Region
Reduced Conventional Current
Source

Figure 29-5. *At top, conventional current flows freely from source to drain through the channel of a P-doped JFET. At bottom, the higher voltage of the gate relative to the source creates a field effect that pinches off the flow of current.*

The primary characteristics of a junction field-effect transistor relative to an NPN bipolar transistor are summarized in the table in Figure 29-6.

JFET Behavior

The voltage difference between gate and source of a JFET is usually referred to as V_{gs} while the voltage difference between drain and source is referred to as V_{ds}.

	NPN Bipolar Transistor	N-Channel JFET
Type of amplifier	Current	Voltage
Active bias	Positive	Negative
Unbiased state	Nonconductive	Conductive
Biased state	More conductive	Less conductive

Figure 29-6. *This table contrasts the characteristics of an N-channel JFET with those of an NPN bipolar transistor.*

Suppose the gate of an N-channel JFET is connected with the source, so that $V_{gs}=0$. Now if V_{ds} increases, the current flowing through the channel of the JFET also increases, approximately linearly with V_{ds}. In other words, initially the JFET behaves like a low-value resistor in which the voltage across it, divided by the amperage flowing through it, is approximately constant. This phase of the JFET's behavior is known as its *ohmic region*. While the unbiased resistance of the channel in a JFET depends on the component type, it is generally somewhere between 10Ω and 1K.

If V_{ds} increases still further, eventually no additional flow of current occurs. At this point the channel has become *saturated*, and this plateau zone is referred to as the *saturation region*, often abbreviated I_{dss}, meaning "the saturated drain current at zero bias." Although this is a nearly constant value for any particular JFET, it may vary somewhat from one sample of a component to another, as a result of manufacturing variations.

If V_{ds} continues to increase, the component finally enters a *breakdown* state, sometimes referred to by its full formal terminology as *drain-source breakdown*. The current passing through the JFET will now be limited only by capabilities of the external power source. This breakdown state can be destructive to the component, and is comparable to the breakdown state of a typical **diode**.

What if the voltage at the gate is reduced below the voltage at the source—such as V_{gs} becomes negative? In its ohmic region, the component now behaves as if it has a higher resistance, and it will reach its saturation region at a lower current value (although around the same value for V_{ds}). Therefore, by reducing the voltage on the gate relative to the voltage at the source, the effective resistance of the component increases, and in fact it can behave as a *voltage-controlled resistor*.

The upper diagram in Figure 29-7 shows this graphically. Below it, the corresponding graph for a P-channel JFET looks almost identical, except that the current flow is reversed and is pinched off as the gate voltage rises above the source voltage. Also, the breakdown region is reached more quickly with a P-channel JFET than with an N-channel JFET.

MOSFETs

MOSFETs have become one of the most widely used components in electronics, everywhere from computer memory to high-amperage switching power supplies. The name is an acronym for *metal-oxide semiconductor field-effect transistor*. A simplified cross-section of an N-channel MOSFET is shown in Figure 29-8.

Two MOSFETs are shown in Figure 29-9.

Like a JFET, a MOSFET has three terminals, identified as drain, gate, and source, and it functions by creating a field effect that controls current flowing through a channel. (Some MOSFETS have a fourth terminal, described later). However, it has a metal source and drain making contact with each end of the channel (hence the term "metal" in its acronym) and also has a thin layer of silicon dioxide (hence the term "oxide" in its acronym) separating the gate from the channel, thus raising the impedance at the gate to at least



Figure 29-7. *The top graph shows current passing through the channel of an N-channel JFET, depending on gate voltage and source voltage. The lower graph is for a P-channel JFET.*

100,000 gigaohms and reducing gate current essentially to zero. The high gate impedance of a MOSFET allows it to be connected directly to the output of a digital integrated circuit. The layer of silicon dioxide is a *dielectric*, meaning that a field applied to one side creates an opposite field on the other side. The gate attached to the surface of the layer functions in the same way as one plate of a capacitor.



Figure 29-8. *Simplified diagram of an N-channel MOSFET. The thickness of the silicon dioxide layer has been greatly exaggerated for clarity. The black terminals are metallic.*



Figure 29-9. *Two MOSFETs. At left, the TO-220 package claims a drain current of up to 65A continuous, and a drain-to-source breakdown voltage 100V. At right, the smaller package offers a drain current of 175mA continuous, and a drain-to-source breakdown voltage of 300V.*

The silicon dioxide also has the highly desirable property of insulating the gate from the channel, thus preventing unwanted reverse current. In a JFET, which lacks a dielectric layer, if source voltage is allowed to rise more than about 0.6V higher than gate voltage, the direct internal connection between gate and channel allows negative charges to flow freely from source to gate, and as the internal resistance will be very low, the resulting current can be destructive. This is why the JFET must always be reverse-biased.

A MOSFET is freed from these restrictions, and the gate voltage can be higher or lower than the source voltage. This property enables an N-channel MOSFET to be designed not only as a depletion device, but alternatively as an *enhancement device*, which is "normally off" and can be switched on by being forward-biased. The primary difference is the extent to which the channel in the MOSFET is N-doped with charge carriers, and therefore will or will not conduct without some help from the gate bias.

In a depletion device, the channel conducts, but applying negative voltage to the gate can pinch off the current.

In an enhancement device, the channel does not conduct, but applying positive voltage to the gate can make it start to do so.

In either case, a shift of bias from negative to positive encourages channel conduction; the depletion and enhancement versions simply start from different points.

This is clarified in Figure 29-10. The vertical (logarithmic) scale suggests the current being conducted through the channel of the MOSFET, while the green curve describes the behavior of a depletion version of the device. Where this curve crosses the center line representing 0 volts bias, the channel is naturally conductive, like a JFET. Moving left down the curve, as reverse bias is applied (shown on the horizontal axis), the component becomes less conductive until finally its conductivity reaches zero.

Meanwhile on the same graph, the orange curve represents an enhancement MOSFET, which is nonconductive at 0 volts bias. As forward bias increases, the current also increases—similar to a bipolar transistor.

To make things more confusing, a MOSFET, like a JFET, can have a P-doped channel; and once again it can function in depletion or enhancement mode. The behavior of this variant is shown in Figure 29-11. As before, the green curve shows the behavior of a depletion MOSFET, while the orange curve refers to the enhancement version. The horizontal axis now shows the voltage difference between the gate and the drain terminal. The depletion component is naturally conductive at zero bias, until the gate voltage increases above the drain voltage, pinching off the current flow. The enhancement component is not conductive until reverse bias is applied.



Figure 29-10. *The current conduction of depletion and enhancement N-channel MOSFETs. See text for details. (Influenced by The Art of Electronics by Horowitz and Hill.)*

Figure 29-12 shows schematic symbols that represent depletion MOSFETs. The two symbols on the left are functionally identical, representing N-channel versions, while the two symbols on the right represent P-channel versions. As in the case of JFETs, the letter "S" should be (but often is not) added to the symmetrical versions of the symbols, to clarify which is the source terminal. The left-pointing arrow identifies the components as N-channel, while in the symbols on the right, the right-pointing arrows indicate P-channel MOS-



Figure 29-11. *The current conduction of depletion and enhancement P-channel MOSFETs. See text for details.*

FETs. The gap between the two vertical lines in each symbol suggests the silicon dioxide dielectric. The right-hand vertical line represents the channel.



Figure 29-12. *Schematic symbols for depletion MOSFETs. These function similarly to JFETs. The two symbols on the left are functionally identical, and represent N-channel depletion MOSFETs. The two symbols on the right are both widely used to represent P-channel depletion MOSFETs.*

For enhancement MOSFETs, a slightly different symbol uses a broken line between the source and drain (as shown in Figure 29-13) to remind us that these components are "normally off" when zero-biased, instead of "normally on." Here again a left-pointing arrow represents an N-channel MOSFET, while a right-pointing arrow represents a P-channel MOSFET.



Figure 29-13. *Schematic symbols for enhancement MOSFETs. The two on the left are functionally identical, and represent N-channel enhancement MOSFETs. The two on the right represent P-channel enhancement MOSFETs.*

Because there is so much room for confusion regarding MOSFETs, a summary is presented in Figure 29-14 and Figure 29-15. In these figures, the relevant parts of each schematic symbol are shown disassembled alongside text explaining their meaning. Either of the symbols in Figure 29-14 can be superimposed on either of the symbols in Figure 29-15, to combine their functions. So, for instance, if the upper symbol in Figure 29-14 is superimposed on the lower symbol in Figure 29-15, we get an N-channel MOSFET of the enhancement type.



N-channel MOSFET
Source relatively negative
Drain relatively positive
Gate relatively negative
changes conductivity as gate becomes more negative

P-channel MOSFET
Source relatively positive
Drain relatively negative
Gate relatively positive
changes conductivity as gate becomes more positive

Figure 29-14. *Either of the two symbols can be combined with either of the two symbols in the next figure, to create one of the four symbols for a MOSFET. See text for details.*



Depletion MOSFET normally ON
Change of gate voltage (more negative for N-channel, more positive for P-channel) pinches off the current flow.

Enhancement MOSFET Normally OFF
Change of gate voltage (less positive for N-channel, less negative for P-channel) pinches off the current flow.

Figure 29-15. *Either of the two symbols can be combined with either of the two symbols from the previous figure, to create one of the four symbols for a MOSFET. See text for details.*

In an additional attempt to clarify MOSFET behavior, four graphs are provided in Figure 29-16, Figure 29-17, Figure 29-18, and Figure 29-19. Like JFETs, MOSFETs have an initial ohmic region, followed by a saturation region where current flows relatively freely through the device. The gate-to-source voltage will determine how much flow is permitted. However, it is important to pay close attention to the graph scales, which differ for each of the four types of MOSFET.



Figure 29-16. *Current flow through a depletion-type, N-channel MOSFET.*

In all of these graphs, a bias voltage exists, which allows zero current to flow (represented by the graph line superimposed on the horizontal axis). In other words, the MOSFET can operate as a switch. The actual voltages where this occurs will vary with the particular component under consideration.

The N-channel, enhancement-type MOSFET is especially useful as a switch because in its normally-off state (with zero bias) it presents a very high resistance to current flow. It requires a relatively low positive voltage at the gate, and effectively no gate current, to begin conducting conventional current from its drain terminal to its source terminal. Thus it can be driven directly by typical 5-volt logic chips.

Depletion-type MOSFETs are now less commonly used than the enhancement-type.



Figure 29-17. *Current flow through a depletion-type, P-channel MOSFET.*



Figure 29-18. *Current flow through an enhancement-type, N-channel MOSFET.*



Figure 29-19. *Current flow through an enhancement-type, P-channel MOSFET.*

The Substrate Connection

Up to this point, nothing has been said about a fourth connection available on many MOSFETs, known as the *body terminal*. This is connected to the substrate on which the rest of the component is mounted, and acts as a diode junction with the channel. It is typically shorted to the source terminal, and in fact this is indicated by the schematic symbols that have been used so far. It is possible, however, to use the body terminal to shift the threshold gate voltage of the MOSFET, either by making the body terminal more negative than the source terminal (in an N-channel MOSFET) or more positive (in a P-channel MOSFET). Variants of the MOSFET schematic symbols showing the body terminal are shown in Figure 29-20 (for depletion MOSFETS) and Figure 29-21 (for enhancement MOSFETS).

A detailed discussion of the use of the body terminal to adjust characteristics of the gate is beyond the scope of this encyclopedia.



Figure 29-20. *Schematic symbol variants for depletion MOSFETs, showing the body terminal separately accessible instead of being tied to the source terminal.*



Figure 29-21. *Schematic symbol variants for enhancement MOSFETs, showing the body terminal separately accessible instead of being tied to the source terminal.*

Variants

A few FET variants exist in addition to the two previously discussed.

MESFET

The acronym stands for *MEtal-Semiconductor Field Effect Transistor*. This FET variant is fabricated from gallium arsenide and is used primarily in radio frequency amplification, which is outside the scope of this encyclopedia.

V-Channel MOSFET

Whereas most FET devices are capable of handling only small currents, the *V-channel MOSFET* (which is often abbreviated as a *VMOS FET* and has a V-shaped channel as its name implies) is capable of sustained currents of at least 50A and voltages as high as 1,000V. It is able to pass the high current because its channel resistance is well under 1Ω. These devices, commonly referred to as *power MOSFETs*, are available from all primary semiconductor manufacturers and are commonly used in switching power supplies.

Trench MOS

The TrenchMOS or Trenchgate MOS is a MOSFET variant that encourages current to flow vertically rather than horizontally, and includes other innovations that enable an even lower channel resistance, allowing high currents with minimal heat generation. This device is finding applications in the automobile industry as a replacement for electromechanical **relays**.

Values

The maximum values for JFETs, commonly found listed in datasheets, will specify V_{ds} (the drain-source voltage, meaning the potential difference between drain and source); V_{dg} (the drain-gate voltage, meaning the potential difference between drain and gate); V_{gsr} (the reverse gate-source voltage); gate current; and total device dissipation in mW. Note that the voltage differences are relative, not absolute. Thus a voltage of 50V on the drain and 25V on the source might be acceptable in a component with a V_{ds} of 25V. Similarly, while a JFET's "pinch-off" effect begins as the gate becomes "more negative" than the source, this can be achieved if, for example, the source has a potential of 6V and the gate has a potential of 3V.

JFETs and MOSFETs designed for low-current switching applications have a typical channel resistance of just a few ohms, and a maximum switching speed around 10Mhz.

The datasheet for a MOSFET will typically include values such as gate threshold voltage, which may be abbreviated V_{gs} (or V_{th}) and establishes the relative voltage at which the gate starts to play an active role; and the maximum on-state drain current, which may be abbreviated $I_{d(on)}$ and establishes the maximum limiting current (usually at 25 degree Centigrade) between source and gate.

How to Use it

The combination of a very high gate impedance, very low noise, very low quiescent power consumption in its off state, and very fast switching capability makes the MOSFET suitable for many applications.

P-Channel Disadvantage

P-channel MOSFETs are generally less popular than N-channel MOSFETS because of the higher resistivity of P-type silicon, resulting from its lower carrier mobility, putting it at a relative disadvantage.

Bipolar Substitution

In many instances, an appropriate enhancement-type MOSFET can be substituted for a bipolar transistor with better results (lower noise, faster action, much higher impedance, and probably less power dissipation).

Amplifier Front Ends

While MOSFETs are well-suited for use in the front end of an audio amplifier, chips containing MOSFETs are now available for this specific purpose.

Voltage-Controlled Resistor

A simple voltage-controlled resistor can be built around a JFET or MOSFET, so long as its performance remains limited to the linear or ohmic region.

Compatibility with Digital Devices

A JFET may commonly use power supplies in the range of 25VDC. However, it can accept the high/low output from a 5V digital device to control its gate. A 4.7K pullup resistor is an appropriate value to be used if the FET is to be used in conjunction with a TTL digital chip that may have a voltage swing of only approximately 2.5V between its low and high thresholds.

What Can Go Wrong

Static Electricity

Because the gate of a MOSFET is insulated from the rest of the component, and functions much like a plate of a capacitor, it is especially likely to accumulate static electricity. This static charge may then discharge itself into the body of the component, destroying it. A MOSFET is particularly vulnerable to electrostatic discharge because its oxide layer is so thin. Special care should be taken either when handling the component, or when it is in use. Always touch a grounded object or wear a grounded wrist band when handling MOSFETs, and be sure that any circuit using MOSFETs includes appropriate protection from static and voltage spikes.

A MOSFET should not be inserted or removed while the circuit in which it performs is switched on or contains residual voltage from undischarged capacitors.

Heat

Failure because of overheating is of special concern when using power MOSFETs. A Vishay Application Note (“Current Power Rating of Power Semiconductors”) suggests that this kind of component is unlikely to operate at less than 90 degrees Centigrade in real-world conditions, yet the power handling capability listed in a datasheet usually assumes an industry standard of 25 degrees Centigrade.

On the other hand, ratings for continuous power are of little relevance to switching devices that have duty cycles well below 100%. Other factors also play a part, such as the possibility of power surges, the switching frequency, and the integrity of the connection between the component and its heat sink. The heat sink itself creates uncertainty by tending to average the temperature of the component, and of course there is no simple way to know the actual junction temperature, moment by moment, inside a MOSFET.

Bearing in mind the accumulation of unknown factors, power MOSFETs should be chosen on an extremely conservative basis. According to a tutorial in the *EE Times*, actual current switched by a MOSFET should be less than half of its rated current at 25 degrees, while one-fourth to one-third are common. Figure 29-22 shows the real-world recommended maximum drain current at various temperatures. Exceeding this recommendation can create additional heat, which cannot be dissipated, leading to further accumulation of heat, and a thermal runaway condition, causing eventual failure of the component.



Figure 29-22. *Maximum advised drain current through a power MOSFET, related to case temperature of the component. Derived from EE Times Power MOSFET Tutorial.*

Wrong Bias

As previously noted, applying forward bias to a JFET can result in the junction between the gate and the source starting to behave like a forward-biased diode, when the voltage at the gate is greater than the voltage at the source by approximately 0.6V or more (in an N-channel JFET). The junction will present relatively little resistance, encouraging excessive current and destructive consequences. It is important to design devices that allow user input in such a way that user error can never result in this eventuality.

Schematic Symbols

A

This section contains a compilation of schematic symbols for components that have been described in this volume. They are sequenced primarily in alphabetical order, as this section is intended for use as an index. However, symbols that have a strong similarity are grouped together; thus **potentiometer** is found adjacent to **resistor**, and all types of transistors are in the same group.

The symbol variants shown in each blue rectangle are functionally identical.

Where a component has mandatory polarity or is commonly used with a certain polarity, a red plus sign (+) has been added for guidance. This sign is not part of the symbol. In the case of polarized capacitors, where a plus sign is normally shown (or should be shown) with the symbol, the plus sign is a part of the symbol and appears in black.

This is not intended to be an exhaustive compilation of symbol variants. Some uncommon ones may not be here. However, the list should be sufficient to enable identification of components in this volume.


Battery: Single cell
Diode: Varactor
Battery: Two cells
Diode: Zener
Battery: Multiple cells
Fuse
Capacitor: Nonpolarized
Fuse (ANSI, IEC, IEEE)
+
+
Capacitor: Polarized
Fuse (building contractor)
Capacitor: Variable
Fuse (becoming disused)
Diode
Inductor: Air core
Diode: Schottky
Inductor: Solid core
Diode: Tunnel
Inductor: Particle core

Figure A-1. *Schematic symbols*



Inductor: Ferrite bead

Relay: SPDT, two-coil latching

Inductor: Solenoid or electromagnet

Resistor

Inductor: Variable

Resistor: Potentiometer

Pushbutton: Normally open

Resistor: Variable resistor or rheostat

Pushbutton: Normally closed

Resistor: Trimmer

Pushbutton: DT

Switch: SPST

Pushbutton: DP

Switch: SPDT

Relay: SPST, normally open, nonlatching

Switch: DPDT

Relay: SPDT, nonlatching

Switch: 3PDT

Figure A-2. *Schematic symbols, continued*


Switch: Rotary
Switch: Slider, SPDT
Switch: Slider, 4PDT
Transformer: Solid core
Transformer: Air core
Transformer: Same phase output
Transformer: 180 degree phase output
Transformer: Center tapped secondary
B
C
E
B
C
E
E=Emitter
B=Base
C=Collector
Transistor: Bipolar, NPN
B
E
C
B
E
C
E=Emitter
B=Base
C=Collector
Transistor: Bipolar, PNP
G
D
S
G
D
S
D=Drain
G=Gate
S=Source
Transistor: JFET, N-channel
G
D
S
G
D
S
D=Drain
G=Gate
S=Source
Transistor: JFET, P-channel
G
D
S
D
S
D=Drain
G=Gate
S=Source
Transistor: MOSFET, depletion, N-channel
G
D
S
D
S
D=Drain
G=Gate
S=Source
Transistor: MOSFET, depletion, P-channel
G
D
S
D
S
D=Drain
G=Gate
S=Source
Transistor: MOSFET, enhancement, N-channel
G
D
S
D
S
D=Drain
G=Gate
S=Source
Transistor: MOSFET, enhancement, P-channel
G
A
C
A=Anode
G=Gate
C=Cathode
Transistor: Unijunction
E
B2
B1
B2=Base 2
E=Emitter
B1=Base 1
Transistor: Unijunction, programmable (PUT)

Figure A-3. *Schematic symbols, continued*

Index

Symbols

18 * D) + (40 * W, 128
1:1 transformers (see isolation transformers)

A

absolute encoding, 53
AC adapters, 142, 143, 157, 159
AC inrush, 177
AC motors, 191–200
  design of, 191
  function of, 191
  potential problems, 200
  types of, 195
  use of, 199
  values for, 199
AC-AC transformers, 135–142
  design of, 136
  function of, 135
  potential problems, 142
  schematic symbol for, 135
  types of, 138
  use of, 142
  values for, 141
AC-DC power supplies, 143–147
  function of, 143
  potential problems, 147
  types of, 143
  use of, 147
accumulators, 5
active mode, 245
actuators, 38
adjustable inductors, 125
adjustable output converters, 152
adjustable voltage regulators, 163
Ah/AH/A/H (see amp-hours)
air cores, 125
alkaline cells, 8, 13
alternate pushbuttons, 33
alternating current (AC), 135, 143, 157, 196, 221
amp-hour capacity, 11, 13,
amp-hours (Ah), 11
amplifiers, 250
amplitude-modulated, 125
analog servo motors, 204
annulus, 183
anodes, 6, 221
anti-backlash gears, 114
apparent power, 141
arcing, 47, 72, 108
armatures, 66
audio tone control, 85
audio transformers, 140
audio-taper potentiometers, 91, 96
automotive fuses, 23
automotive relays, 69
autotransformers, 140
auxilliary winding, 196
avalanche breakdown, 233
axial leads, 99
axial loading, 185
axial resistors, 76

B

back EMF, 108, 218, 227, 228
backlash, 188, 204
bandpass filters, 131
basic switches, 39
batteries, 5–16
  capacitors as, 109
  capacity, 11
  DC-AC inverters and, 160

We'd like to hear your suggestions for improving our indexes. Send email to index@oreilly.com.

  design of, 6
  disposable, 7, 8
  fuel cells, 8
  function of, 5
  potential problems, 15
  rechargeable, 7, 9
  schematic symbols for, 6
  use of, 14
  values for, 11
  voltage, 13
battery acid, 9
battery chargers, 8
bearings
  failure of, 189
beta value (β), 244
biased relays, 67
biased semiconductors, 241
bifilar motors, 216
bipolar electrolytic capacitors, 102
bipolar junction transistor (BJT) (see bipolar transistors)
bipolar motors, 211
bipolar stepper motors, 213
bipolar transistors, 241–252
  design of, 241
  function of, 241
  potential problems, 251
  schematic symbols for, 242
  types of, 245
  use of, 246
BLDC motors (see brushless DC motors)
blown fuses, 21, 27
body terminals, 261
boost-type converters, 151, 154
boots, 43
break-before-make switches, 39, 53
breakdown state, 256
breakdown voltage, 224
breakers, 160
breaking capacity, 22
bridge rectifiers, 226
brushes, 179, 187, 198
brushless DC motors, 183
buck converters, 150
buck-boost converters (see flyback converters)
bulk metal foil, 83
bushings, 38
button capacitors (see disk capacitors)
button cells, 5
bypass capacitors, 107, 154
bypass switches, 176

C

c-clamps, 110
C-rate, 12
capacitance, 105, 115
capacitive reactance, 106
capacitor arrays, 101
capacitor clamps, 110
capacitor networks, 101
capacitors, 8, 97–111, 97
  (see also variable capacitors)
  as alternative to shorting coils, 195
  design of, 97
  function of, 97
  potential problems, 109
  schematic symbols, 97
  types of, 99
  use of, 107
  values for, 104
capacity, 11–14
caps (see capacitors)
carbon-composite resistors, 82
carbon-film potentiometers, 95
carbon-film resistors, 82
carriers, 183
cartridge fuses, 23
cathode-ray tubes, 171
cathodes, 6, 221
cells, 5, 6
ceramic capacitors, 103
charging
  incorrect voltage and, 15
  reverse charging, 16
chatter, 72
chokes, 119
chopper drives, 217
circuit breakers, 15, 21
circuits
  RC circuits, 79
clamp diodes, 230
closed-loop systems, 210, 217
CMOS (complementary metal oxide semiconductor), 253
code samples
  digital access to, 3
coded rotary switches, 53
cogging, 193
coils, 66, 121, 135, 170
cold cranking rating, 159
collectors, 242, 246
common contacts, 38
common-bus configurations, 78
common-collector amplifiers, 250
common-emitter amplifier, 250
commutators, 179, 195, 198
complement-coded rotary switches, 54,
complementary metal oxide semiconductor (see CMOS)
components
  definition of, 2
condensers (see capacitors)
contact bounce, 61
contacts
  burnout of, 63
  contamination of, 48, 73
  overloading of, 57
  relays and, 66
  vulnerability of, 57
continuous inductors, 122
contractors, 70
control shaft encoders, 59
conventional current, 7
  inductors and, 120
converters (see DC-DC converters)
cores, 119, 132, 137, 138
coupling capacitors, 107
covered power supplies, 146
crossover networks, 130
crystal diodes (see diodes)
crystal sets, 125
cup (potentiometer), 93
current, 5
  inadequate, 15
  stall current, 184
current amplifiers, 243, 253
current gain (hFE), 244

current ratings
  DC motors, 184
  fuses, 22
  pushbuttons, 35
  relays, 70
  rotary switches, 56
  rotational encoders, 61
cutoff mode, 245
cylindrical capacitors, 99

D

damping, 220
Darlington chips, 249
Darlington pair chips, 251
Darlington pairs, 161, 218, 241, 248
DC current
  AC-AC tranformers and, 142
  inductors and, 121
DC motors, 179–189
  current rating, 184
  design of, 179
  function of, 179
  potential problems, 187
  types of, 181
  use of, 185
DC-AC inverters, 157–160
  design of, 157
  function of, 157
  potential problems, 160
  types of, 158
  use of, 159
  values for, 158
DC-DC converters, 149–155
  design of, 149
  function of, 149
  potential problems, 155
  types of, 150
  use of, 154
  values for, 152
DCR (DC resistance), 129
debounce, 48
decks, 52
decoupling capacitors, 107
deep cycle batteries, 9
degauss, 171
delay fuses, 23
delta configuration, 181
demagnetization
  of rotors, 220
demagnetizing objects, 171
depletion device, 255
depletion layer, 255
depletion region, 223
detent torque, 220
detents, 59
dielectric absorption, 110
dielectric constant, 105
dielectric memory, 110
dielectrics, 97, 103, 113, 257
digital access
  code samples, 3
digital servo motors, 204
diode arrays, 226
diodes, 221–233
  DC circuits and, 47
  design of, 223
  function of, 221
  potential problems, 232
  schematic symbol for, 221
  types of, 224
  use of, 227
  values for, 226
DIP (see dual-inline package)
DIP switches, 43, 53
  (see also rotary DIP switches)
  vs. jumpers, 17
direct current (DC), 143, 157
direct current-excited motors, 196
discrete semiconductors, 241
disk capacitors, 100
disposable batteries, 7, 8–9
doping, 253
double-pole pushbuttons, 29
double-pole switches, 37
double-throw (DT) switches, 37
drain-source breakdown, 256
dropout voltage, 161
dry cells, 7
dry joints, 48
dual-coil latching relays, 67
dual-ganged potentiometers, 93
dual-inline package (DIP), 77
dynamic resistance, 224, 225
dyne-meters, 185

E

effective series resistance (ESR), 98, 154
efficiency
  converters and, 153
8-wire motors, 216
electrical capacity (see capacity)
electrical noise, 87, 97, 132, 147, 155, 207, 230
electrical polarity, 123
electrochemical cells, 5
electrochemical power sources, 5
electrodes, 6, 7
electrolysis, 5
electrolytes, 6
electrolytic capacitors, 101, 110, 147
electrolytic cells, 5
electrolytic layer dielectrics, 103
electromagnetic armature relays, 65
electromagnetic interference (EMI), 147, 154, 187
electromagnets, 169–172
  function of, 169, 169
  potential problems, 172
  types of, 170
  use of, 171
  values for, 171
electromechanical linear actuators, 184
electromechanical relays, 65
electromotive force (EMF), 177, 218, 227, 228
electron holes, 98, 223
electronic commutation, 184
electrostatic discharge (ESD), 225, 263
element, 21
emergency switches, 35
EMI (see electromagnetic interference)
emitters, 242, 246
enable pins, 165
encoded output rotary switches, 53
enhancement devices, 255, 258

epicyclic gears, 182
equivalent series resistance (ESR), 110
errata, web address for, 4
ESD (see electrostatic discharge)

F

farads (F), 104
ferrite beads, 126
ferromagnetic cores, 137
field effect transistor (FET)
    design of, 253
    function of, 253
    potential problems, 263
    types of, 262
    use of, 263
    values for, 262
field windings, 192
field-effect transistor (FET), 253–264
555 timer, 186, 202, 214, 218, 235
flat-ganged potentiometers, 93
flip-flop behavior, 67
flooded design, 9
flux density, 170
flyback converters, 151
flyback diodes, 47
flyback-type converters, 144
foot pedal pushbuttons, 33
FORM A/B switches, 39
Form A/B/C pushbuttons, 30
formulae
    presentation of, 3
forward bias, 241
forward direction (diodes), 221
forward EMF, 177
frames, 173
freewheeling diodes, 47
front panel mount switches, 45
fuel cells, 8
fuseholders, 27
fuses, 15, 21–28
    (see also circuit breakers)
    current rating, 22
    design of, 21
    function of, 21
    potential problems, 27
    schematic symbols for, 21
    types of, 22
    use of, 26, 28
    voltage rating, 22
fusible links, 24
fusible resistors, 82

G

ganged potentiometers, 93
gear motors (see gearhead motors)
gearhead motors, 181, 188
gears
    nylon vs. metal, 204
general-purpose resistors, 76
generators, 120
gigaohms, 79
Gray-coded outputs, 55
grounding
    common ground, 142
    variable capacitors and, 117
Gunn diodes, 221, 226
gyrators, 127, 132

H

H bridge system, 187
half-cells, 6
half-stepping mode, 217
Hall effect sensors, 184
harmonics, 157
header sockets, 18
headers, 18, 34
heat
    AC motors and, 200
    capacitors and, 110
    converters and, 155
    diodes and, 233
    effect on motors, 188
    power resistors and, 84
    resistors and, 87
    solenoids and, 177
    voltage regulators and, 166
heat sinks, 76, 246
Henry units, 128
high phase count motors, 216
high side, 46
high-frequency transistors, 245
high-pass filters, 107, 130
high-speed diodes, 224
hold current, 25
holding torque, 220
horse-shoe magnet design, 170
hot switching, 37
hunting, 220
hybrid motors, 216
hysteresis, 122, 124, 170, 220
hysteresis motors, 197

I

IGBT (see insulated-gate bipolar transistor)
illuminated pushbuttons, 31
impedance, 140
in-line fuse holders, 24,
inaccuracy
    resistors and, 87
incandescent bulbs, 31
incremental devices
    rotational encoders, 59
indicators, 84
inductance, 87, 128
inductance index, 129
inductance-capacitance circuits (see LC circuits)
induction motors, 210
induction rotors, 192
inductive loads
    switch choices for, 48
    voltage spikes and, 71
inductive reactance, 98, 106
inductors, 119–133
    design of, 120
    function of, 119
    potential problems, 132
    schematic symbol for, 119
    types of, 124
    use of, 130
    values for, 128
inrunner configuration, 184
insulated-gate bipolar transistor (IGBT), 186

insulated-gate field-effect transistor (IGFET), 253
integrated circuits, 241
internal resistance, 11
inverted AC motors, 199
ions, 6
ISAT (saturation current, 129
isolated vs. non-isolated, 154
isolation transformers, 140

J

jumper assemblies, 18
jumper sockets (see jumpers)
jumper wires, 17
jumpers, 17–19
junction field-effect transistor (JFET), 253, 253–256
junction threshold voltage, 223, 236

K

Karbonite gears, 204
keylock switches, 56
keypad pushbuttons, 34
kilohms, 79
knife switches, 37

L

latching pushbuttons, 33
latching relays, 46, 67
LC (inductance-capacitance) circuits, 115
lead-acid batteries, 5, 9, 15
leakage, 98, 223, 241, 252
LED (light-emitting diode), 36, 221
  pushbuttons and, 31
  resistors and, 84
limit switches, 39, 184, 187
linear actuators, 184, 186, 218
linear mode, 245
linear motors, 195
linear regulated power supplies, 143
linear taper potentiometers, 90
linear voltage regulators (see voltage regulators)
lithium-ion batteries (Li-ion), 9, 15
lithium-ion polymer batteries, 9
load regulation, 153
loads, 5
lock paint, 117
locked-rotor torque, 194
locking pushbuttons, 33
locking toggle switches, 43
log-taper potentiometers, 91, 96
logarithmic volume control, 95,
logic chips, 48, 154
logic circuits, 47, 157
logic gates, 230
logic inverters, 157
low-dropout voltage regulators, 161, 164
low-pass filters, 108, 130
low-signal relays, 69
lubricants
  environmental effects on, 188

M

magnetic circuits, 121
magnetic cores, 122, 124
magnetic domains, 122, 132, 170
magnetic fields, 72
magnetic polarity, 123
magnetic resistance (see reluctance)
magnetic saturation, 122
mAh (see milliamp-hours)
MAKE magazine
  contact information, 4
make-before-break switches, 39, 53
make-to-break connections, 30, 39
make-to-make connections, 30
matrix encoded pushbuttons, 34
mechanical encoders, 55
mechanical rotary encoders, 59
mechanical wear
  of switches, 48
  potentiometers, 95
megohms, 79
membrane pad pushbuttons, 34
membrane separators, 6
memory effect, 10
MESFET (MEtal-Semiconductor Field Effect Transistor), 262
metal-film resistors, 83
metal-oxide semiconductor field-effect transistor (see MOSFET)
meter loading, 88
microcontrollers
  as alternative to switches, 47
  as pulse sources, 186
  increasing output of, 248
  keypads and, 34
  pushbuttons and, 33
  rotary switches and, 56
  rotational encoders and, 59, 62
  servo motors and, 202
microfarads (µF), 104, 111
microhenrys (µH), 128
microstepping mode, 217
microswitches, 39
milliamp-hours (mAh), 11
millihenrys (mH), 128
milliohms, 79
miniaturized potentiometers, 92
modified sine waves, 158
monetary switches, 29, 67
MOSFET (metal-oxide semiconductor field-effect transistor), 149, 186, 253, 256–261, 263
movable contacts, 38
multiphase motors, 217
multiple-turn potentiometers, 93
Must Operate By voltage, 70
Must Release By voltage, 70
mutual induction, 136

N

N layer, 223
N-channel, 253
N-type semiconductors, 241
nanofarads (nF), 104

nanohenrys (nH), 128
negative resistance region, 237
negative voltage regulators, 164
neon bulbs, 31
neutral relays, 67
Newton-meters, 185
nichrome (Ni-chrome) elements, 77
nickel-cadmium batteries (nicad/NiCd), 9, 10
nickel-metal hydride batteries (NiMH), 9, 10
noise
  electrical, 87, 97, 132, 147, 155, 207
  reduction of, 189, 230
non-excited synchronous motors, 196
non-flammable resistors, 82
nonlatching relays, 67
nonmagnetic cores, 125
nonshorting switches, 53, 57
normally closed (NC), 31, 39
normally open (NO), 31, 39
notch filters, 131
nuisance opening, 27
nylon vs. metal gears, 204

O

octal base, 69
OCV (see open circuit voltage)
ohmic region, 256
on-off switches, 37
open circuit voltage (OCV/Voc), 13
open-frame power supplies, 146
open-frame switches, 51
open-loop systems, 210, 217
operating point, 250
optical mouse, 59
oscillating, 220
ounce-inches, 185
output
  voltage regulators and, 166
outrunner configuration, 184
overcoat material, 117
overheating
  DC-AC inverters and, 160
  MOSFETs, 263
  potentiometers, 96
  transformers and, 142
overshoot, 219

P

P layer, 223
P-channel, 253
P-type semiconductors, 241
paddle switches, 44
panel-mount switches, 45, 49
panel-mounted pushbuttons, 32
parallel batteries
  high current flow, 16
parasitic capacitance, 132
parasitic inductance, 87, 103
pass transistors, 161
PC board rotary switches, 55
PC mount switches, 45
PC pushbuttons, 32
PC terminals, 45
peak inrush, 147, 177
peak inrush current, 27
permanent magnet stepper motors, 211
permeability, 122
Peukert number, 12
phase count, 209
phases (steps), 209
pick-offs, 90
picofarads (pF), 104
piles, 5
pin configurations
  correct identification of, 167
  relays, 67, 72
PIN diodes, 221, 226
pitch, 18
planetary gears, 182
plastic-film dielectrics, 103
plug fuses, 22
plug-in transformers, 139
plungers, 173
PN junction diodes (see diodes)
polarity
  danger of incorrect, 15, 110
  danger of reversed, 233
  DC relays and, 67
  mnemonics for, 123
  preventing reversed, 142
polarized relays, 67
pole faces, 173
poles, 29, 30, 37, 38, 38
polymeric positive temperature coefficient fuse, 24
polyphase AC, 196
positive charges, 98
positive voltage regulators, 164
potentiometers, 75, 89–96, 186
  design of, 90
  function of, 89
  potential problems, 95
  schematic symbols for, 89
  types of, 90
  use of, 94
pound-feet, 185
power cells, 5
power cords
  correct choice of, 142
power MOSFETs, 262
power resistors, 76
power transformers, 139
power transistors, 245
power wire-wound resistors, 83
PPR (see pulses per rotation)
precision resistors, 76
precision wire-wound resistors, 83
press-twice pushbuttons, 33
primary cells, 7
primary coils, 135
programmable unijunction transistor (PUT), 235, 239
protection diodes, 218, 228
proximity effect, 133
PTC/PPTC (see polymeric positive temperature coefficient fuse)
pull-in torque, 220
pull-out torque, 220
pulldown resistors, 85
pullup resistors, 56, 85
pulse-width modulation (PWM), 144, 150, 158, 186, 199, 201, 217
pulses per rotation (PPR), 61

push-lock push-release pushbuttons, 33
push-on push-off pushbuttons, 33
push-push pushbuttons, 33
pushbutton switches, 29
pushbuttons, 29–36
  current ratings, 35
  design of, 29
  function of, 29
  potential problems, 35
  schematic symbol for, 29
  types of, 30
  use of, 35
pushwheel switches, 55
PUT (programmable unijunction transistor), 235, 239
PWM (see pulse-width modulation)

Q

quadrature output, 61
quality factor, 107
quasi-low-dropout voltage regulators, 165
quick connect terminals, 45
quiescent current, 166
quiescent point, 250

R

radial leads, 99
radial loading, 185
radial resistors, 76
radio buttons, 35
radio crystal set, 125
radio frequencies (RF), 133
ramping, 219
rated current
  fuses, 22
rated voltage, 22
RC (resistor-capacitor) network, 86, 98
RC circuits, 79
RC servo motors, 201
reactance, 115, 123, 128
real-coded rotary switches, 54,
rechargeable batteries, 7, 9–11
rectified current, 199
rectifier diodes, 224, 227, 233
rectifiers, 142, 143, 144, 170, 221
reed relays, 68, 72
reed switches, 68, 171
relative devices
  rotational encoders, 59
relative encoding, 53
relays, 65–73
  current rating, 70
  design of, 66
  function of, 65
  possible problems, 72
  schematic symbols for, 65, 67
  types of, 67
  use of, 71
reluctance, 121, 129, 170, 176
reluctance motors, 184, 197, 199
reluctance stepper motors, 210
remanent magnetism, 122
reserve batteries, 9
resettable fuses, 21, 24
resistance, 210
  rotational encoders, 61
resistor arrays, 77
resistor ladders, 56
resistor networks/ladders (see resistor arrays)
resistor-capacitor (RC) network, 86, 98
resistors, 75–88
  design of, 76
  function of, 75
  materials, 82
  possible problems, 87
  schematic symbols for, 75
  types of, 76
  use of, 84
  values for, 79
resistors in parallel, 86
resistors in series, 86
resonant frequency, 106, 220
response curves, 237
retentivity, 124
reverse charging, 16
rheostats, 89, 186
right-angle PC rotary switch, 54
right-angle PC terminals, 45
right-hand rule, 123
ripple-and-noise values, 154
RMS (see root mean square)
rocker switches, 40
root mean square (RMS), 158
rotary DIP switches, 53
rotary switches, 51–57
  current rating, 56
  design of, 52
  function of, 51
  potential problems, 57
  schematic symbol for, 51
  types of, 52
  use of, 56
rotational encoders, 47, 59–63
  current rating, 61
  design of, 59
  function of, 59
  potential problems, 62
  types of, 60
  use of, 62
rotors, 51, 113, 179, 191, 192, 209
  demagnetization of, 220

S

Safari Books Online, 3
safe operating area (SOA), 247
saturated mode, 245
saturation, 132, 220, 244
saturation current, 129
saturation region (Idss), 256
saturation, magnetic, 176
schematic symbols, 265
  AC-AC transformers, 135, 138
  batteries, 6
  bipolar transistors, 242
  capacitors, 97
  diodes, 221
  fuses, 21
  inductors, 119
  MOFSET, 259
  potentiometers, 89
  pushbuttons, 29
  relays, 65, 67
  resistors, 75, 82
  rotary switches, 51

  - slide switches, 41
  - switches, 49
  - unijunction transistors, 235
- Schottky diodes, 225
- SCR (see silicon-controlled rectifier)
- screw terminals, 45
- secondary cells, 7
- secondary coils, 135
- self-discharge rate, 8
- self-inductance, 119, 217
- self-resonance, 132
- self-resonant frequency, 106, 129
- semiconductors, 223
- series resistors, 84
- servo motors, 201–207
  - design of, 201
  - function of, 201
  - potential problems, 206
  - types of, 203
  - use of, 205
  - values for, 204
  - vs. stepper motors, 219
- settling time, 61
- shaded pole motors, 195
- shell cores, 138
- shielding
  - variable capacitors and, 117
- shock hazards
  - AC-AC transformers and, 142
  - AC-DC power supplies, 147
- short-circuited batteries, 15, 26
- short-circuited switches, 48
- shorting coils, 195
- shorting switches, 39, 53, 57
- shunts (see jumpers)
- signal clipping, 231
- signal diodes, 224, 233
- silicon-controlled rectifier (SCR), 186
- single side stable relays, 67
- single-coil latching relays, 67
- single-inline package (SIP), 77
- single-layer ceramic capicitors, 110
- single-phase induction motors, 195
- single-pole switches, 37
- single-throw (ST) switches, 37
- SIP (see single-inline package)
- SIP switches, 44
- skin effect, 133
- slide pushbuttons, 41
- slider potentiometers, 93
- slider pushbuttons, 31
- slider switches, 40, 48
- sliding noise, 62
- slip, 195
- Slo-Blo fuses, 23
- slow-blowing fuses, 26
- small cartridge fuses, 23
- small-signal relays, 69
- small-signal transistors, 245
- small-switching transistors, 245
- SMPS (see switching power supply)
- SMT (see surface-mount fuses)
- snap-action switches, 35, 39
- snap-in mount switches, 45
- snubbers, 35, 47, 79, 108
- SOA (see safe operating area)
- solder lug terminals, 45
- soldering damage, 27, 252
- solenoids, 173–177
  - design of, 174
  - function of, 173
  - potential problems, 177
  - types of, 176
  - use of, 177
  - values for, 176
- solid-state relays, 65
- splines, 204
- split-bobbin transformers, 141
- split-phase induction motors, 196
- sponge (lead), 9
- spur gears, 182
- squirre-cage motors, 192
- squirrel-cage motors, 210
- SRF (self-resonant frequency, 129
- stability
  - resistors and, 82
- stall current, 184
- stall torque, 185
- standard type regulators, 161
- star configuration, 181
- stationary contacts, 38
- stators, 113, 179, 191, 209
- status pins, 165
- step angle, 210
- step loss, 219
- step motors (see stepper motors)
- step-down transformers, 136
- step-up transformers, 136
- stepper motors, 209–220
  - design of, 209
  - function of, 209
  - potential problems, 219
  - types of, 214
  - use of, 218
  - values for, 218
- stepping motors (see stepper motors)
- stops, 52
- strip fuses, 24
- subject-oriented organization, 2
- subminiature fuses, 24
- subminiature paddle switches, 44
- subminiature slide switches, 41
- subminiature switches, 40
- subpanel mount switches, 45
- substrate connections, 261
- sulfurization, 16
- sun gear, 183
- supercapacitors, 8, 109
- surface mount switches, 45
- surface-mount (SMT) fuses, 26
- surface-mount capacitors, 100
- surface-mount resistors, 77
- surface-mount transformers, 141
- surface-mounted pushbuttons, 32
- surge sensitivity, 22
- switch bounce, 48, 62
- switched potentiometers, 93
- switched-mode power supply (see switching power supply)
- switchers (see DC-DC converters) (see switching power supply)
- switches, 17, 37–49, 51
  - (see also rotary switches)
  - design of, 37
  - function of, 37
  - potential problems, 47
  - terminology, 38
  - types of, 38
  - use of, 46
  - values for, 45

switching diodes, 224
switching power supplies, 143, 144, 159
switching regulators (see DC-DC converters)
synchronous motors, 184, 196

T

tactile swithes, 34
tank circuits (see LC circuits)
tantalum capacitors, 102, 110
taps, 137
Tcr/Tc (see temperature coefficient)
teeth (rotor), 210
temperature coefficient (Tcr/Tc), 82
terminals, choosing correct, 48
terminals, for switches, 45
THD (see total harmonic distortion)
thick-film resistors, 77, 83
thin-film resistors, 83
three-phase induction motors, 196
through-hole chips (capacitors), 101
through-hole fuses, 24, 26
through-hole terminals, 45
throws, 30, 38
thumbwheel switches, 55
time constant, 105, 130
time-delay relay switches, 70
toggle switches, 41
tolerance
    resistors, 79
toroidal core inductors, 126
torque
    expression of, 185
    fluctuations in, 193
    motor overloading and, 200
    stepper motors and, 220
total harmonic distortion (THD), 158
tracks, 90
transformer-based power supplies, 143
transient response, 166
transient suppressors, 228
transient voltage suppressor (TVS), 225
transients, 143
transistors, 241
    (see also bipolar transistors)
    resistors and, 84
transit time, 205
TrenchMOS, 262
triggering voltage, 236
trimmer capacitors, 113, 117
trimmer potentiometers, 89, 93, 113
Trimpots (see trimmer potentiometers)
trip current, 25
tripped fuses, 21
true sinewave inverters, 158
tuning capacitors, 113
tunnel diodes, 221, 226
turn rate, 205
TVS (see transient voltage suppressor)
two-contact pushbuttons, 29
two-pole switches, 37
two-way switches, 37

U

UJT (see unijunction transistor)
unijunction transistor (UJT), 235–240
    design of, 236
    function of, 235
    potential problems, 239
    schematic symbol for, 235
    types of, 238
    use of, 239, 240
    values for, 238
uninterruptible power supplies, 9
unipolar motors, 211, 214
universal motors, 198
universal stepper motors (see bifilar motors)
unloaded speed, 185

V

V-channel MOSFET (VMOS FET), 262
VA (see volts times amps)
vacuum tubes, 221, 241
valley voltage, 237
value coding, 88
    resistors, 81
valve-regulated lead-acid batteries (VRLA), 9
vandal resistant switches, 45
varactor diodes, 221, 225
variable capacitors, 113–117, 113
    (see also capacitors)
    design of, 113
    function of, 113
    possible problems, 117
    types of, 114
    use of, 115
    values for, 115
variable condensers (see variable capacitors)
variable frequency power supplies, 198
variable inductors, 125
variable reluctance, 210
variable resistors, 89
variable transformers, 140
variacs (see variable transformers)
varicaps (see varactor diodes)
Vc (see voltage coefficient)
Very Low Dropout voltage regulators, 165
vibration
    capacitors and, 110
    damping of, 220
    relays and, 73
Voc (see open circuit voltage)
voltage, 13
    automatic selection of, 229
    imbalance in AC motors, 200
    inaccurate in converters, 155
    inaccurate in voltage regulators, 167
    multiple outputs, 138,
    regulation with diodes, 230

  sensing with diodes, 232
voltage amplifiers, 253
voltage coefficient (Vc), 82
voltage dividers, 56, 56, 75, 86, 163, 244
voltage multipliers, 146
voltage overload
  bipolar transistors and, 252
  capacitors and, 110
voltage rating, 22
voltage regulators, 161–167
  design of, 161
  function of, 161
  potential problems, 166
  types of, 163
  use of, 165, 167
  values for, 165
voltage spikes
  protection against, 71, 221
voltage-controlled resistors, 256
volts times amps, 141
VRLA (see valve-regulated lead-acid batteries)

W

wall-warts, 143
windings, 121, 209
wipers, 90, 140
wire lead terminals, 45
wire-wound resistors, 77
wound-rotor AC induction motors, 198
wye configuration, 181

Y

Y configuration, 181
yokes, 171

Z

Zener diodes, 221, 225, 230, 231, 233
Zener voltage, 230
zero ohm components
  resistors, 82
zinc-carbon cells, 8

Science / Electronics

VOL. 2

Encyclopedia of Electronic Components

Signal Processing

Want to know how to use an electronic component? This second book of a three-volume set includes key information on electronics parts for your projects—complete with photographs, schematics, and diagrams. You'll learn what each one does, how it works, why it's useful, and what variants exist. No matter how much you know about electronics, you'll find fascinating details you've never come across before.

Convenient, concise, well-organized, and precise

Perfect for teachers, hobbyists, engineers, and students of all ages, this reference puts reliable, fact-checked information right at your fingertips—whether you're refreshing your memory or exploring a component for the first time. Beginners will quickly grasp important concepts, and more experienced users will find the specific details their projects require.

- **Unique:** the first and only encyclopedia set on electronic components, distilled into three separate volumes
- **Incredibly detailed:** includes information distilled from hundreds of sources
- **Easy to browse:** parts are clearly organized by component type
- **Authoritative:** fact-checked by expert advisors to ensure that the information is both current and accurate
- **Reliable:** a more consistent source of information than online sources, product datasheets, and manufacturer's tutorials
- **Instructive:** each component description provides details about substitutions, common problems, and workarounds
- **Comprehensive:** Volume 1 covers power, electromagnetism, and discrete semiconductors; Volume 2 includes integrated circuits, and light and sound sources; Volume 3 covers a range of sensing devices.

Charles Platt

Charles Platt's lifelong love of electronics began when he built a telephone answering machine at age 15. A contributing editor to *Make Magazine*, he wrote the widely acclaimed *Make: Electronics*. He's also a science-fiction writer (author of *The Silicon Man*), and a former senior writer at *Wired* magazine.

US $29.99 CAN $31.99
ISBN: 978-1-4493-3418-5

Make:
makezine.com

---

2 Make: Encyclopedia of Electronic Components Platt MAKER MEDIA

VOL. 2

Charles Platt with Fredrik Jansson

Encyclopedia of Electronic Components

Signal Processing

LEDs ▪ LCDs ▪ Audio ▪ Thyristors
Digital Logic ▪ Amplification

Make:
makezine.com

Science / Electronics

VOL. 2

Encyclopedia of Electronic Components

Signal Processing

Want to know how to use an electronic component? This second book of a three-volume set includes key information on electronics parts for your projects—complete with photographs, schematics, and diagrams. You'll learn what each one does, how it works, why it's useful, and what variants exist. No matter how much you know about electronics, you'll find fascinating details you've never come across before.

Convenient, concise, well-organized, and precise

Perfect for teachers, hobbyists, engineers, and students of all ages, this reference puts reliable, fact-checked information right at your fingertips—whether you're refreshing your memory or exploring a component for the first time. Beginners will quickly grasp important concepts, and more experienced users will find the specific details their projects require.

- **Unique:** the first and only encyclopedia set on electronic components, distilled into three separate volumes
- **Incredibly detailed:** includes information distilled from hundreds of sources
- **Easy to browse:** parts are clearly organized by component type
- **Authoritative:** fact-checked by expert advisors to ensure that the information is both current and accurate
- **Reliable:** a more consistent source of information than online sources, product datasheets, and manufacturer's tutorials
- **Instructive:** each component description provides details about substitutions, common problems, and workarounds
- **Comprehensive:** Volume 1 covers power, electromagnetism, and discrete semiconductors; Volume 2 includes integrated circuits, and light and sound sources; Volume 3 covers a range of sensing devices.

Charles Platt

Charles Platt's lifelong love of electronics began when he built a telephone answering machine at age 15. A contributing editor to *Make:* magazine, he wrote the widely acclaimed *Make: Electronics*. He's also a science-fiction writer (author of *The Silicon Man*), and a former senior writer at *Wired* magazine.

US $29.99 CAN $31.99
ISBN: 978-1-4493-3418-5

Make:
makezine.com

2

Make: **Encyclopedia of Electronic Components** **Platt**

MAKERMEDIA

VOL. 2

Charles Platt with Fredrik Jansson

Encyclopedia of Electronic Components

Signal Processing

LEDs ▪ LCDs ▪ Audio ▪ Thyristors
Digital Logic ▪ Amplification

Make:
makezine.com

Encyclopedia of Electronic Components
Volume 2

Charles Platt
with Fredrik Jansson

MAKER MEDIA
SEBASTOPOL, CA

Encyclopedia of Electronic Components Volume 2

by Charles Platt
with Fredrik Jansson

Copyright © 2015 Charles Platt. All rights reserved.

Printed in the United States of America.

Published by Maker Media, Inc., 1005 Gravenstein Highway North, Sebastopol, CA 95472.

Maker Media books may be purchased for educational, business, or sales promotional use. Online editions are also available for most titles (*http://safaribooksonline.com*). For more information, contact our corporate/institutional sales department: 800-998-9938 or *corporate@oreilly.com*.

Editor: Brian Jepson
Production Editor: Melanie Yarbrough
Proofreader: Jasmine Kwityn
Indexer: Last Look Editorial
Cover Designer: Karen Montgomery
Interior Designer: David Futato
Illustrator and Photographer: Charles Platt

November 2014: First Edition

Revision History for the First Edition:

2014-11-10: First release

See *http://oreilly.com/catalog/errata.csp?isbn=9781449334185* for release details.

Make:, Maker Shed, and Maker Faire are registered trademarks of Maker Media, Inc. The Maker Media logo is a trademark of Maker Media, Inc.

Many of the designations used by manufacturers and sellers to distinguish their products are claimed as trademarks. Where those designations appear in this book, and Maker Media, Inc. was aware of a trademark claim, the designations have been printed in caps or initial caps.

While the publisher and the author have used good faith efforts to ensure that the information and instructions contained in this work are accurate, the publisher and the author disclaim all responsibility for errors or omissions, including without limitation responsibility for damages resulting from the use of or reliance on this work. Use of the information and instructions contained in this work is at your own risk. If any code samples or other technology this work contains or describes is subject to open source licenses or the intellectual property rights of others, it is your responsibility to ensure that your use thereof complies with such licenses and/or rights.

ISBN: 978-1-449-33418-5

[TI]

In fond memory of my father, Maurice Platt

Table of Contents

How to Use This Book . . . . **xxi**

> DISCRETE SEMICONDUCTOR

> > THYRISTOR

1. SCR **1**
- What It Does 1
- How It Works 1
  - Switching Behavior 2
- Internal Configuration 3
  - Breakdown and Breakover Voltage 4
  - SCR Concept Demo 4
  - AC Current Applications 5
- Variants 5
- Values 5
  - Commonly Used Abbreviations 6
- How to Use It 6
  - Phase Control 7
  - Overvoltage Protection 7
- What Can Go Wrong 8
  - Unexpected Triggering Caused by Heat 8
  - Unexpected Triggering Caused by Voltage 8
  - Confusion of AC and DC Ratings 8
  - Maximum Current versus Conduction Angle 9
  - Confusing Symbols 9

2. diac **11**
- What It Does 11

    - Symbol Variants 11
- How It Works 12
    - Switching AC 13
- Variants 13
- Values 14
- What Can Go Wrong 14
    - Unexpected Triggering Caused by Heat 14
    - Low-Temperature Effects 14
    - Manufacturing Tolerances 14

3. triac 15
- What It Does 15
    - Symbol Variants 15
- How It Works 17
    - Quadrants 17
    - Threshold, Latching, and Holding Current 18
    - Triac Testing 19
    - Breakover Voltage 20
    - Switching AC 20
    - Triac Triggered by a Diac 22
    - Other Triac Drivers 22
    - Charge Storage 23
- Variants 23
- Values 23
- What Can Go Wrong 24
    - Unexpected Triggering Caused by Heat 24
    - Low-Temperature Effects 24
    - Wrong Type of Load 24
    - Wrongly Identified Terminals 24
    - Failure to Switch Off 24

> INTEGRATED CIRCUIT

> > ANALOG

4. solid-state relay 25
- What It Does 25
    - Advantages 25
    - Disadvantages 26
- How It Works 26
- Variants 27
    - Instantaneous versus Zero Crossing 27
    - NC and NO Modes 28
    - Packaging 28
    - Solid-State Analog Switch 28
- Values 29
- How to Use It 29
- What Can Go Wrong 30

Overheating Caused by Overloading 30
Overheating Caused by Bad Terminal Contact 30
Overheating Caused by Changing Duty Cycle 30
Overheating Caused by Component Crowding 30
Overheating in Dual Packaging 30
Reverse-Voltage Burnout 30
Low Voltage Output Current May Not Work 30
Inability to Measure AC Output 30
Relay Turns On but Won't Turn Off 31
Relays in Parallel Won't Work 31
Output Device Doesn't Run at Full Power 31
Solid-State Relays and Safety Disconnects 31

5. **optocoupler** **33**
What It Does 33
How It Works 34
Variants 35
Internal Sensors 35
Basic Optocoupler Types 36
Values 36
How to Use It 36
What Can Go Wrong 37
Age 37
LED Burnout 37
Transistor Burnout 37

6. **comparator** **39**
What It Does 39
Hysteresis 39
How It Works 39
Differences from an Op-Amp 42
Variants 42
Values 43
How to Use It 44
AND gate 45
Bistable Multivibrator 46
Relaxation Oscillator 46
Level Shifter 46
Window Comparator 46
Other Applications 47
What Can Go Wrong 47
Oscillating Output 47
Confused Inputs 48
Wrong Chip Type 48
Omitted Pullup Resistor 48
CMOS Issues 48
Erratic Output 48
Swapped Voltages 48
Heat-Dependent Hysteresis 48

7. op-amp **49**
- What It Does 49
- How It Works 49
    - Dual Inputs 50
    - Negative Feedback 51
    - Op-Amps and Comparators 52
- Variants 52
- Values 52
- How to Use It 53
    - Controlling the Gain 53
    - Calculating Amplification 53
    - Unintentional DC Voltage Amplification 54
    - Low-Pass Filter 54
    - High-Pass Filter 55
    - Relaxation Oscillator 55
    - Single Power Source 56
    - Offset Null Adjustment 56
- What Can Go Wrong 57
    - Power Supply Problems 57
    - Bad Connection of Unused Sections 57
    - Oscillating Output 57
    - Confused Inputs 58

8. digital potentiometer **59**
- What It Does 59
    - Advantages 59
- How It Works 60
- Variants 61
    - Volatile and Nonvolatile Memory 61
    - Taper 62
    - Data Transfer 62
    - SPI 62
    - I2C Protocol 63
    - Up/Down Protocol 63
    - Other Control Systems 64
    - Connections and Modes 64
- Values 65
- How to Use It 66
    - Achieving Higher Resolution 66
- What Can Go Wrong 67
    - Noise and Bad Inputs 67
    - Wrong Chip 67
    - Controller and Chip Out of Sync 67
    - Nonlinear Effects 67
    - Data Transfer Too Fast 67

9. timer **69**
- What It Does 69
    - Monostable Mode 69

Astable Mode . . . 70
How It Works . . . 70
Variants . . . 70
The 555 Timer . . . 70
555 Monostable Operation . . . 71
555 Astable Operation . . . 72
556 Timer . . . 73
558 Timer . . . 73
CMOS 555 Timer . . . 74
5555 Timer . . . 74
7555 Timer . . . 74
7556 Timer . . . 74
4047B Timer . . . 75
Dual Monostable Timers . . . 75
Values . . . 76
555 Timer Values . . . 76
Time Calculation in Monostable Mode . . . 77
Time Calculation in Astable Mode . . . 77
Dual Monostable Timers . . . 77
How to Use It . . . 79
555 Monostable Mode . . . 79
555 Astable Mode . . . 80
Separate Control of High and Low Output Times . . . 80
555 Fifty Percent Astable Duty Cycle: 1 . . . 80
555 Fifty Percent Astable Duty Cycle: 2 . . . 81
Use of the 555 Control Pin . . . 81
555 Flip-Flop Emulation . . . 82
555 Hysteresis . . . 83
555 and Coupling Capacitors . . . 84
555 Loudspeaker Connection . . . 84
Burst Mode . . . 84
"You Lose" Game Sound . . . 85
What Can Go Wrong . . . 85
Dead Timer . . . 85
CMOS Confused with Bipolar . . . 86
The Pulse that Never Ends . . . 86
Erratic Chip Behavior . . . 86
Interference with Other Components . . . 86
Erratic Behavior of Output Devices . . . 86
Fatal Damage Caused by Inductive Loads . . . 87

> > DIGITAL

10. logic gate . . . 89
What It Does . . . 89
Origins . . . 89
How It Works . . . 89
Inversion . . . 90
Single-Input Gates . . . 90

Gates with More than Two Inputs 91
Boolean Notation 91
Arithmetical Operations 91
Other Operations 92
Variants 93
Part Numbers 94
Families 95
Family Interoperability 96
Gates per Chip 96
Two Inputs, Single Gate 96
Three Inputs, Single Gate 97
Single Gate, Selectable Function 97
Two Inputs, Dual Gate 98
Original 74xx 14-Pin Format 98
Quad Two-Input 74xx Pinouts 98
Triple Three-Input 74xx Pinouts 99
Dual Four-Input 74xx Pinouts 100
Single Eight-Input 74xx Pinouts 100
74xx Inverters 101
Additional Variations 102
Pinouts in the Original 4000 Series 102
4000 Series Inverters 103
How to Use It 103
Which Family 103
Applications 104
What Can Go Wrong 105
Static 105
Floating Pins 105
Family Incompatibilities 105
Overloaded Outputs 105
Output Pulled Down 105
Incorrect Polarity and Voltages 105
Bent Pins 105
Unclean Input 106
Analog Input 106

11. flip-flop 107
What It Does 107
How It Works 107
NAND-Based SR Flip-Flop 108
NOR-Based SR Flip-Flop 109
Forbidden States 110
The JK Flip-Flop 112
Master-Slave Flip-Flop 113
D-Type Flip-Flops 114
Summary 116
Variants 116
Packaging 117
Values 117

How to Use It . . . 118
What Can Go Wrong . . . 119
    Ambiguous Documentation . . . 119
    Faulty Triggering . . . 119
    Metastability . . . 119
    Other Issues . . . 119

12. **shift register** . . . 121
What It Does . . . 121
    Schematic Representation . . . 122
How It Works . . . 122
    Abbreviations and Acronyms . . . 123
    Parallel Outputs and Inputs . . . 123
Variants . . . 124
    Serial In, Serial Out . . . 124
    Serial In, Parallel Out . . . 124
    Parallel In, Serial Out . . . 124
    Parallel In, Parallel Out . . . 125
    Universal . . . 125
Values . . . 125
    Power Considerations . . . 126
    Three-State Output . . . 126
How to Use It . . . 126
    Dual Inputs . . . 127
    Preloading the Shift Register . . . 127
    Polling a Keyboard . . . 127
    Arithmetical Operations . . . 127
    Buffering . . . 128
What Can Go Wrong . . . 128
    Confusing Classification . . . 128
    Inadequate Setup Time . . . 128
    Unconnected Input . . . 129
    Output Enable Issues . . . 129
    Floating Output Bus . . . 129

13. **counter** . . . 131
What It Does . . . 131
    Schematic Representation . . . 131
How It Works . . . 132
    Modulus and Modulo . . . 132
    Pin Identifiers . . . 133
Variants . . . 134
    Ripple versus Synchronous . . . 134
    Ring, Binary, and BCD . . . 134
    Clock Sources . . . 135
    Rising Edge and Falling Edge . . . 136
    Multiple Stages . . . 136
    Single and Dual . . . 136
    High-State, Low-State, and Three-State . . . 136

        Descending Output 136
        Programmable Counters 137
        Examples 137
    Values 137
    What Can Go Wrong 137
        Lock-Out 137
        Asynchronous Artifacts 137
        Noise 138

14. encoder 139
    What It Does 139
        Schematic Symbol 139
        Similar Devices 140
    How It Works 140
    Variants 141
    Values 142
    How to Use It 142
        Cascaded Encoders 142
    What Can Go Wrong 143

15. decoder 145
    What it Does 145
        Input Devices 145
        LED Driver 146
        Schematic Symbol 146
        Similar Devices 146
    How It Works 148
    Variants 148
    Values 148
    How to Use It 149
    What Can Go Wrong 149
        Glitches 149
        Unhelpful Classification 149
        Active-Low and Active-High 149

16. multiplexer 151
    What It Does 151
        Differential Multiplexer 152
        Similar Devices 152
    How It Works 153
        Schematic Symbol 153
        Pin Identifiers 154
    Variants 155
    Values 155
    How to Use It 156
        Other Application Notes 157
    What Can Go Wrong 157
        Pullup Resistors 157
        Break Before Make 157

Signal Distortion 157
Limits of CMOS Switching 157
Transients 157

> LIGHT SOURCE, INDICATOR, OR DISPLAY

> > REFLECTIVE

17. LCD 159
What It Does 159
How It Works 159
Variants 160
Active and Passive Types 161
Crystal Types 161
Seven-Segment Displays 161
Additional Segments 162
Dot-Matrix Displays 163
Color 166
Backlighting Options 167
Zero-Power Displays 167
How to Use It 167
Numeric Display Modules 167
Alphanumeric Display Module 168
What Can Go Wrong 169
Temperature Sensitivity 169
Excessive Multiplexing 170
DC Damage 170
Bad Communications Protocol 170
Wiring Errors 170

> > SINGLE SOURCE

18. incandescent lamp 171
What It Does 171
History 172
How It Works 172
Spectrum 173
Non-Incandescent Sources 174
Power Consumption 175
Variants 175
Miniature Lamps 175
Panel-Mount Indicator Lamps 176
Halogen or Quartz-Halogen 176
Oven Lamps 176
Base Variants 177
Values 177
Power 177
Illuminance 178

Intensity 178
MSCP 178
Efficacy 179
Efficiency 179
How to Use It 179
Relative Advantages 179
Derating 180
What Can Go Wrong 180
High Temperature Environment 180
Fire Risk 181
Current Inrush 181
Replacement Problems 181

19. neon bulb 183
What It Does 183
How It Works 184
Construction 184
Ionization 184
Negative Resistance 185
How to Use It 186
Limited Light Output 187
Efficiency 187
Ruggedness 187
Power-Supply Testing 188
Life Expectancy 188
Variants 189
Nixie Tubes 189
What Can Go Wrong 189
False Indication 189
Failure in a Dark Environment 189
Premature Failure with DC 190
Premature Failure through Voltage Fluctuations 190
Replacement 190

20. fluorescent light 191
What It Does 191
How It Works 191
Ballast and Starter 192
Flicker 193
Variants 193
CCFLs 194
Sizes 194
Comparisons 194
Values 195
Brightness 195
Spectrum 195
What Can Go Wrong 195
Unreliable Starting 195
Terminal Flicker 195

    - Cannot Dim . . . 196
    - Burned Out Electrodes . . . 196
    - Ultraviolet Hazard . . . 196

21. laser . . . 197

- What It Does . . . 197
- How It Works . . . 198
    - Laser Diode . . . 198
    - Coherent Light . . . 200
- Variants . . . 201
    - CO2 Lasers . . . 201
    - Fiber Lasers . . . 201
    - Crystal Lasers . . . 201
- Values . . . 201
- How to Use It . . . 202
    - Common Applications . . . 202
- What Can Go Wrong . . . 202
    - Risk of Injury . . . 202
    - Inadequate Heat Sink . . . 202
    - Uncontrolled Power Supply . . . 203
    - Polarity . . . 203

22. LED indicator . . . 205

- What It Does . . . 205
    - Schematic Symbols . . . 206
    - Common Usage . . . 206
- How It Works . . . 207
    - Multicolor LEDs and Color Mixing . . . 207
- Variants . . . 208
    - Size and Shape . . . 208
    - Intensity . . . 208
    - Efficacy . . . 208
    - Diffusion . . . 209
    - Wavelength and Color Temperature . . . 209
    - Internal Resistor . . . 210
    - Multicolored . . . 210
    - Infrared . . . 211
    - Ultraviolet . . . 211
- Values . . . 211
    - Forward Current . . . 211
    - Low-Current LEDs . . . 211
    - Forward Voltage . . . 212
    - Color Rendering Index . . . 212
    - Life Expectancy . . . 212
    - Light Output and Heat . . . 212
    - View Angle . . . 213
- How to Use It . . . 213
    - Polarity . . . 213
    - Series Resistor Value . . . 214

    - LEDs in Parallel 214
    - Multiple Series LEDs 214
    - Comparisons with Other Light Emitters 214
    - Other Applications 215
- What Can Go Wrong 215
    - Excessive Forward Voltage 215
    - Excessive Current and Heat 215
    - Storage Issues 215
    - Polarity 215
    - Internal Resistors 215

23. LED area lighting 217
- What It Does 217
    - Trends in Cost and Efficiency 218
    - Schematic Symbol 218
- How It Works 218
    - Visible Differences 220
    - Side-by-Side Comparison 220
    - Heat Dissipation 222
    - Efficacy 222
    - Dimming 222
    - Ultraviolet Output 222
    - Color Variation 222
- Variants 223
    - Comparisons 223
- Values 225
- What Can Go Wrong 225
    - Wrong Voltage 225
    - Overheating 225
    - Fluorescent Ballast Issues 225
    - Misleading Color Representation 226

> > MULTI-SOURCE OR PANEL

24. LED display 227
- What It Does 227
- How It Works 228
- Variants 228
    - LCD comparisons 228
    - Seven-Segment Displays 228
    - Multiple Numerals 229
    - Additional Segments 229
    - Dot-Matrix Displays 230
    - Pixel Arrays 231
    - Multiple Bar Display 232
    - Single Light Bar 232
- Values 232
- How to Use It 232
    - Seven-Segment Basics 232

- Driver Chips and Multiplexing . . . 233
- Sixteen-Segment Driver Chip . . . 234
- Dot-Matrix LED Display Modules . . . 234
- Pixel Arrays . . . 235
- Multiple Bar Display Driver . . . 236
- One-Digit Hexadecimal Dot Matrix . . . 236
- What Can Go Wrong . . . 237
  - Common Anode versus Common Cathode . . . 237
  - Incorrect Series Resistance . . . 237
  - Multiplexing Issues . . . 237

25. **vacuum-fluorescent display . . . 239**
- What It Does . . . 239
- How It Works . . . 239
  - Anode, Cathode, and Grid . . . 240
- How to Use It . . . 240
  - Modern Application . . . 241
- Variants . . . 241
  - Color . . . 241
  - Character Sets and Pictorial Design . . . 242
  - Comparisons . . . 242
- What Can Go Wrong . . . 242
  - Fading . . . 242

26. **electroluminescence . . . 243**
- What It Does . . . 243
- How It Works . . . 243
  - Phosphors . . . 244
  - Derivation . . . 244
- Variants . . . 244
  - Panels . . . 244
  - Flexible Ribbons . . . 245
  - Rope Light . . . 245
  - OLED . . . 246

> SOUND SOURCE

> > AUDIO ALERT

27. **transducer . . . 249**
- What It Does . . . 249
- How It Works . . . 249
- Variants . . . 250
  - Electromagnetic . . . 250
  - Piezoelectric . . . 250
  - Ultrasonic Transducer . . . 250
  - Formats . . . 251
- Values . . . 251

Frequency Range 251
Sound Pressure 251
Weighted Sound Values 252
Unweighted Values 253
Measurement Location 253
Limitations 253
Voltage 254
Current 254
How to Use It 254
Appropriate Sound Intensity 254
Volume Control 254
AC Supply 254
Self-Drive Transducer Circuit 254
What Can Go Wrong 254
Overvoltage 254
Leakage 255
Component Mounting Problems 255
Moisture 255
Transducer-Indicator Confusion 255
Connection with a Microcontroller 255

28. audio indicator 257
What It Does 257
How It Works 257
Audio Frequency 258
History 258
Variants 258
Sound Patterns 258
Formats 258
Values 259
Voltage 259
Current 260
Frequency 260
Duty Cycle 260
How to Use It 260
Appropriate Sound Intensity 260
Volume Control 260
Wiring 260
What Can Go Wrong 260

> > REPRODUCER

29. headphone 261
What It Does 261
How It Works 261
Audio Basics 261
Variants 262
Moving Coil 262
Other Types 263

        Mechanical Design . . . 264
    Values . . . 265
        Intensity . . . 265
        Frequency Response . . . 265
        Distortion . . . 266
        Impedance . . . 266
    What Can Go Wrong . . . 266
        Overdriving . . . 266
        Hearing Damage . . . 266
        Mismatched Impedance . . . 266
        Incorrect Wiring . . . 266

30. **speaker** . . . **267**
    What It Does . . . 267
    How It Works . . . 267
        Construction . . . 268
        Multiple Drivers . . . 269
        Venting . . . 270
        Resonance . . . 270
        Miniature Speakers . . . 270
    Variants . . . 271
        Electrostatic Speaker . . . 271
        Powered Speakers . . . 271
        Wireless Speakers . . . 271
        Innovative Designs . . . 271
    Values . . . 271
    What Can Go Wrong . . . 272
        Damage . . . 272
        Magnetic Field . . . 272
        Vibration . . . 272

Index . . . **273**

How to Use This Book

This is the second of three volumes. Its purpose is to provide an overview of the most commonly used electronic components, for reference by students, engineers, hobbyists, and instructors. While you can find much of this information dispersed among datasheets, introductory books, websites, and technical resources maintained by manufacturers, the *Encyclopedia of Electronic Components* gathers all the relevant facts in one place, properly organized and verified, including details that may be hard to find elsewhere. Each entry includes typical applications, possible substitutions, cross-references to similar devices, sample schematics, and a list of common problems and errors.

You can find a more detailed rationale for this encyclopedia in the Preface to Volume 1.

Volume Contents

Practical considerations influenced the decision to divide this encyclopedia into three volumes. Each deals with broad subject areas as follows.

Volume 1

Power; electromagnetic devices; discrete semiconductors

The *power* category includes sources of electricity and methods to distribute, store, interrupt, convert, and regulate power. The *electromagnetic devices* category includes devices that exert force linearly, and others that create a turning force. *Discrete semiconductors* include the primary types of diodes and transistors. A contents listing for Volume 1 appears in Figure P-1.

Volume 2

Thyristors (SCRs, diacs, and triacs); integrated circuits; light sources, indicators, and displays; and sound sources

Integrated circuits are divided into analog and digital components. *Light sources, indicators, and displays* are divided into reflective displays, single sources of light, and displays that emit light. *Sound sources* are divided into those that create sound, and those that reproduce sound. A contents listing for Volume 2 appears in Figure P-2.

Volume 3

Sensing devices

The field of sensors has become so extensive, they easily merit a volume to themselves. *Sensing devices* include those that detect light, sound, heat, motion, pressure, gas, humidity, orientation, electricity, proximity, force, and radiation.

At the time of writing, Volume 3 is still in preparation, while Volume 1 is complete and is available in a variety of formats.

Primary Category	Secondary Category	Component Type
power	source	battery
	connection	jumper
		fuse
		pushbutton
		switch
		rotary switch
		rotational encoder
	moderation	relay
		resistor
		potentiometer
		capacitor
		variable capacitor
	conversion	inductor
		AC-AC transformer
		AC-DC power supply
		DC-DC converter
		DC-AC inverter
	regulation	voltage regulator
electro-magnetism	linear output	electromagnet
		solenoid
	rotational output	DC motor
		AC motor
		servo motor
		stepper motor
discrete semi-conductor	single junction	diode
		unijunction transistor
	multi-junction	bipolar transistor
		field-effect transistor

Figure P-1. *The subject-oriented organization of categories and entries in Volume 1.*

Primary Category	Secondary Category	Component Type
discrete semi-conductor	thyristor	SCR
		diac
		triac
integrated circuit	analog	solid-state relay
		optocoupler
		comparator
		op-amp
		digital potentiometer
		timer
	digital	logic gate
		flip-flop
		shift register
		counter
		encoder
		decoder
		multiplexer
light source, indicator or display	reflective	LCD
	single source	incandescent lamp
		neon bulb
		fluorescent light
		laser
		LED indicator
		LED area lighting
	multi-source or panel	LED display
		vacuum-fluorescent
		electroluminescence
sound source	audio alert	transducer
		audio indicator
	reproducer	headphone
		speaker

Figure P-2. *The subject-oriented organization of categories and entries in Volume 2.*

Organization

Reference versus Tutorial

As its title suggests, this is a reference book, not a tutorial. A tutorial begins with elementary concepts and builds sequentially toward concepts that are more advanced. A reference book assumes that you may dip into the text at any point, learn what you need to know, and then put the book aside. If you choose to read it straight through from beginning to end, you will find some repetition, as each entry is intended to be self-sufficient, requiring minimal reference to other entries.

My books *Make: Electronics* and *Make: More Electronics* follow a tutorial approach. They don't go into as much depth as this Encyclopedia, because a tutorial inevitably allocates a lot of space to step-by-step explanations and instructions.

Theory and Practice

This book is oriented toward practicality rather than theory. I assume that the reader mostly wants to know how to use electronic components, rather than why they work the way they do. Consequently, I have not included proofs of formulae or definitions rooted in electrical theory. Units are defined only to the extent necessary to avoid confusion.

Many books on electronics theory already exist, if theory is of interest to you.

Entries

This encyclopedia is divided into entries, each entry being devoted to one broad type of component. Two rules determine whether a component has an entry all to itself, or is subsumed into another entry:

Rule 1

> A component merits its own entry if it is (a) widely used, or (b) not so widely used but has a unique identity and maybe some historical status. The **bipolar transistor** entry is an example of a widely used component, whereas the **unijunction transistor** entry is an example of a not so widely used component with a unique identity.

Rule 2

> A component does not merit its own entry if it is (a) seldom used, or (b) very similar in function to another component that is more widely used. For example, a *rheostat* is subsumed into the **potentiometer** section, while *silicon diode*, *Zener diode*, and *germanium diode* are combined together in the **diode** entry.

Inevitably, these guidelines required judgment calls which in some cases may seem arbitrary. My ultimate decision was based on where I would expect to find a component if I was looking for it myself.

Subject Paths

Entries are not organized alphabetically. They are grouped by subject, in much the same way that books in the nonfiction section of some libraries are organized by the Dewey Decimal System. This is convenient if you don't know exactly what you are looking for, or if you don't know all the options that may be available to perform a task that you have in mind.

Each primary category is divided into subcategories, and the subcategories are divided into component types. This hierarchy is shown in Figure P-2. It is also apparent when you look at the top of the first page of each entry, where you will find the path that leads to it. The **diac** entry, for instance, is headed with this path:

discrete semiconductor > thyristor > diac

Any classification scheme will run into exceptions. You can buy a chip containing a *resistor array*, for instance. Technically, this is an *analog integrated circuit*, but a decision was made to put it in the **resistor** section of Volume 1, because it can be directly substituted for a group of resistors.

Some components have hybrid functions. A **multiplexer**, for instance, may pass analog signals and may have "analog" in its name. However, it is digitally controlled and is mostly used in conjunction with other digital integrated circuits. This seemed to justify placing it in the digital category.

Inclusions and Exclusions

There is also the question of what is, and is not, a component. Is wire a component? Not for the purposes of this encyclopedia. How about a **DC-DC converter**? Because converters are now sold in small packages by component suppliers, they are included in Volume 1 as components.

Many similar decisions had to be made on a case-by-case basis. Some readers will disagree with the outcome, but reconciling all the disagreements would have been impossible. The best I could do was to create a book which is organized in the way that would suit me best if I were using it myself.

Typographical Conventions

Within each entry, **bold type** is used for the first occurrence of the name of a component that has its own entry elsewhere. Other important electronics terms or component names may be presented in *italics*.

The names of components, and the categories to which they belong, are all set in lowercase type, except where a term is normally capitalized because it is an acronym or a trademark. The term *Trimpot*, for instance, is trademarked by Bourns, but *trimmer* is not. **LED** is an acronym, but *cap* (abbreviation for **capacitor**) is not.

The European convention for representing fractional component values eliminates decimal points. Thus, values such as 3.3K and 4.7K are expressed as 3K3 and 4K7. This style has not been adopted to a significant degree in the United States, and is not used in this encyclopedia.

In mathematical formulae, I have used the style that is common in programming languages. The * (asterisk) is used as a multiplication symbol, while the / (forward slash) is used as a division symbol. Where some terms are in parentheses, they must be dealt with first. Where parentheses are inside parentheses, the innermost ones must be dealt with first. So, in this example:

```
A = 30 / (7 + (4 * 2) )
```

You would begin by multiplying 4 times 2, to get 8; then add 7, to get 15; then divide that into 30, to get the value for A, which is 2.

Visual Conventions

Figure P-3 shows the conventions that are used in the schematics in this book. A black dot always indicates a connection, except that to minimize ambiguity, the configuration at top right is avoided, and the configuration at top center is used instead. Conductors that cross each other without a black dot do not make a connection. The styles at bottom right are sometimes seen elsewhere, but are not used here.

All the schematics are formatted with pale blue backgrounds. This enables components such as switches, transistors, and LEDs to be highlighted in white, drawing attention to them and clarifying the boundary of the component. The white areas have no other meaning.

Photographic Backgrounds

All photographs of components include a background grid that is divided into squares measuring 0.1". Although the grid is virtual, it is equivalent in scale to physical graph paper placed immediately behind the component. If the component is photographed at an angle, the grid may be reproduced at a similar angle, creating perspective on the squares.

Background colors in photographs were chosen for contrast with the colors of the components, or for visual variety. They have no other significance.

Component Availability

Because there is no way of knowing if a component may have a long production run, this encyclopedia is cautious about listing specific part numbers. To find a specific part that has a narrow function, searching the websites maintained by suppliers will be necessary. The following suppliers were checked frequently during the preparation of the book:

- Mouser Electronics
- Jameco Electronics


To show there is a connection
This style is used
This style is not used
To show there is no connection
This style is used
These styles are not used

Figure P-3. *Visual conventions that are used in the schematics in this book.*

When seeking obsolete parts, or those that are nearing the end of their commercial life, eBay can be very useful.

Issues and Errata

If you believe you have found an error in this book, you will find guidance on how to report it here: *http://bit.ly/eec_v2_errata*.

Before posting your own erratum, please check those that have been submitted previously, to see if someone else already reported it.

I value and encourage reader feedback. However, before you post feedback publicly to a site such as Amazon, I have a request. Please be aware of the power that you have as a reader, and use it fairly. A single negative review can create a bigger effect than you may realize. It can certainly outweigh half-a-dozen positive reviews. If you feel you have not received a prompt or adequate response from the O'Reilly errata site mentioned here, you can email me personally at:

make.electronics@gmail.com

I check that address irregularly—sometimes only once in a couple of weeks. But I do answer all messages.

Safari® Books Online

Safari Books Online is an on-demand digital library that delivers expert content in both book and video form from the world's leading authors in technology and business.

Technology professionals, software developers, web designers, and business and creative professionals use Safari Books Online as their primary resource for research, problem solving, learning, and certification training.

Safari Books Online offers a range of plans and pricing for enterprise, government, education, and individuals.

Members have access to thousands of books, training videos, and prepublication manuscripts in one fully searchable database from publishers like Maker Media, O'Reilly Media, Prentice Hall Professional, Addison-Wesley Professional, Microsoft Press, Sams, Que, Peachpit Press, Focal Press, Cisco Press, John Wiley & Sons, Syngress, Morgan Kaufmann, IBM Redbooks, Packt, Adobe Press, FT Press, Apress, Manning, New Riders, McGraw-Hill, Jones & Bartlett, Course Technology, and hundreds more. For more information about Safari Books Online, please visit us online.

How to Contact Us

Please address comments and questions concerning this book to the publisher:

Make:
1005 Gravenstein Highway North
Sebastopol, CA 95472
800-998-9938 (in the United States or Canada)
707-829-0515 (international or local)
707-829-0104 (fax)

Make: unites, inspires, informs, and entertains a growing community of resourceful people who undertake amazing projects in their backyards, basements, and garages. Make: celebrates your right to tweak, hack, and bend any technology to your will. The Make: audience continues to be a growing culture and community that believes in bettering ourselves, our environment, our educational system—our entire world. This is much more than an audience, it's a worldwide movement that Make: is leading—we call it the Maker Movement.

For more information about Make:, visit us online:

Make: magazine: *http://makezine.com/magazine/*
Maker Faire: *http://makerfaire.com*
Makezine.com: *http://makezine.com*
Maker Shed: *http://makershed.com/*

We have a web page for this book, where we list errata, examples, and any additional information. You can access this page at: *http://bit.ly/encyclopedia_of_electronic_components_v2*.

Acknowledgments

Any reference work draws inspiration from many sources. Datasheets and tutorials maintained by component manufacturers were considered the most trustworthy sources of information online. In addition, component retailers, college texts, crowd-sourced reference works, and hobbyist sites were used. The following books provided useful information:

Boylestad, Robert L. and Nashelsky, Louis: *Electronic Devices and Circuit Theory*, 9th edition. Pearson Education, 2006.

Braga, Newton C.: *CMOS Sourcebook*. Sams Technical Publishing, 2001.

Hoenig, Stuart A.: *How to Build and Use Electronic Devices Without Frustration, Panic, Mountains of Money, or an Engineering Degree*, 2nd edition. Little, Brown, 1980.

Horn, Delton T.: *Electronic Components*. Tab Books, 1992.

Horn, Delton T.: *Electronics Theory*, 4th edition. Tab Books, 1994.

Horowitz, Paul and Hill, Winfield: *The Art of Electronics*, 2nd edition. Cambridge University Press, 1989.

Ibrahim, Dogan: *Using LEDs, LCDs, and GLCDs in Microcontroller Projects*. John Wiley & Sons, 2012.

Kumar, A. Anand: *Fundamentals of Digital Circuits*, 2nd edition. PHI Learning, 2009.

Lancaster, Don: *TTL Cookbook*. Howard W. Sams & Co, 1974.

Lenk, Ron and Lenk, Carol: *Practical Lighting Design with LEDs*. John Wiley & Sons, 2011.

Lowe, Doug: *Electronics All-in-One for Dummies*. John Wiley & Sons, 2012.

Mims III, Forrest M.: *Getting Started in Electronics*. Master Publishing, 2000.

Mims III, Forrest M.: *Electronic Sensor Circuits & Projects*. Master Publishing, 2007.

Mims III, Forrest M.: *Timer, Op Amp, & Optelectronic Circuits and Projects*. Master Publishing, 2007.

Predko, Mike: *123 Robotics Experiments for the Evil Genius*. McGraw-Hill, 2004.

Scherz, Paul: *Practical Electronics for Inventors*, 2nd edition. McGraw-Hill, 2007.

Williams, Tim: *The Circuit Designer's Companion*, 2nd edition. Newnes, 2005.

I also made extensive use of information on vendor sites, especially:

- Mouser Electronics
- Jameco Electronics
- All Electronics
- sparkfun
- Electronic Goldmine
- Adafruit
- Parallax, Inc.

In addition, some individuals provided special assistance. My editor, Brian Jepson, was immensely helpful in the development of this book. Philipp Marek and Steve Conklin reviewed the text for errors. My publisher demonstrated faith in my work. Kevin Kelly unwittingly influenced me with his legendary interest in "access to tools." It was Mark Frauenfelder who originally brought me back to the pleasures of building things, and Gareth Branwyn who revived my interest in electronics.

Lastly, I should mention my school friends from decades ago: Patrick Fagg, Hugh Levinson, Graham Rogers, William Edmondson, and John Witty, who helped me to feel that it was OK to be a nerd building my own audio equipment, long before the word "nerd" actually existed.

—Charles Platt, 2014

SCR

1

The acronym **SCR** is derived from *silicon-controlled rectifier*, which is a gate-triggered type of *thyristor*. A thyristor is defined here as a semiconductor having four or more alternating layers of p-type and n-type silicon. Because it predated integrated circuits, and in its basic form consists of a single multilayer semiconductor, a thyristor is considered to be a discrete component in this encyclopedia. When a thyristor is combined with other components in one package (as in a **solid-state relay**), it is considered to be an integrated circuit.

Other types of thyristor are the **diac** and **triac**, each of which has its own entry.

Thyristor variants that are not so widely used, such as the *gate turn-off thyristor (GTO)* and *silicon-controlled switch (SCS)*, do not have entries here.

OTHER RELATED COMPONENTS

- **diac** (see Chapter 2)
- **triac** (see Chapter 3)

What It Does

In the 1920s, the *thyratron* was a gas-filled tube that functioned as a switch and a rectifier. In 1956, General Electric introduced a solid-state version of it under the name *thyristor*. In both cases, the names were derived from the thyroid gland in the human body, which controls the rate of consumption of energy. The thyratron and, subsequently, the thyristor enabled control of large flows of current.

The **SCR** (silicon-controlled rectifier) is a type of thyristor, although the two terms are often used as if they are synonymous. Text that refers loosely to a thyristor may actually be discussing an SCR, and vice versa. In this encyclopedia, the **SCR**, **diac**, and **triac** are all considered to be variant types of thyristor.

An SCR is a solid-state switch that in many instances can pass high currents at high voltages. Like a **bipolar transistor**, it is triggered by voltage applied to a gate. Unlike the transistor, it allows the flow of current to continue even when the gate voltage diminishes to zero.

How It Works

This component is designed to pass current in one direction only. It can be forced to conduct in the opposite direction if the reversed potential exceeds its *breakdown voltage*, but this mistreatment is likely to cause damage.

By comparison, the diac and triac are designed to be bidirectional.

The SCR has three leads, identified as anode, cathode, and gate. Two functionally identical versions of the schematic symbol are shown in Figure 1-1. Early versions sometimes included a circle drawn around them, but this style has become obsolete. Care must be taken to distinguish between the SCR symbol and the symbol that represents a **programmable unijunction transistor** (PUT), shown in Figure 1-2.



Figure 1-1. *Two functionally identical schematic symbols for an SCR (silicon-controlled rectifier). The symbol on the left is more common.*



Figure 1-2. *The symbol shown here is for a programmable unijunction transistor (PUT). Care must be taken to distinguish it from the symbol for an SCR.*

Switching Behavior

When the SCR is in its passive or nonconductive state, it will block current in either direction between anode and cathode, although a very small amount of *leakage* typically occurs. When the SCR is activated by a positive voltage at the gate, current can now flow from anode to cathode, although it is still blocked from cathode to anode. When the flow reaches a level known as the *latching current*, the flow will continue even after the triggering voltage drops to zero. This behavior causes it to be known as a *regenerative* device.

If the current between anode and cathode starts to diminish while the gate voltage remains zero, the current flow will continue below the latching level until it falls below the value known as the *holding current*. The flow now ceases. Thus, the only way to end a flow of current that has been initiated through an SCR is by reducing the flow or attempting to reverse it.

Note that the self-sustaining flow is a function of current rather than voltage.

Unlike a transistor, an SCR is either “on” or “off” and does not function as a *current amplifier*. Like a diode, it is designed to conduct current in one direction; hence the term *rectifier* in its full name. When it has been triggered, the impedance between its anode and cathode is sufficiently low that heat dissipation can be managed even at high power levels.

The ability of SCRs to pass relatively large amounts of current makes them suitable for controlling the power supplied to motors and resistive heating elements. The fast switching response also enables an SCR to interrupt and abbreviate each positive phase of an AC waveform, to reduce the average power supplied. This is known as *phase control*.

SCRs are also used to provide *overvoltage protection*.

SCR packages reflect their design for a wide range of voltages and currents. Figure 1-3 shows an SCR designed for on-state current of 4A RMS (i.e., measured as the root mean square of the alternating current). Among its applications are small-engine ignition and *crowbar* overvoltage protection, so named because it shorts a power supply directly to ground, much like a crowbar being dropped across the terminals of a car battery (but hopefully with a less dramatic outcome). See Figure 1-15.

In Figure 1-4, the SCR can handle up to 800V repetitive peak off-state voltage and 55A RMS. Possible applications include AC rectification, crowbar protection, welding, and battery charging. The component in Figure 1-5 is rated for 25A and 50V repetitive peak off-state voltage. To assess the component sizes, bear in mind that the graph line spacing is 0.1”.



Figure 1-3. *SCR rated for 400V repetitive off-state voltage, no greater than 4A RMS.*



Figure 1-4. *SCR rated for 800V repetitive off-state voltage, no greater than 55A RMS.*

Internal Configuration

The function of an SCR can be imagined as being similar to that of a PNP transistor paired with an NPN transistor, as shown in Figure 1-6. In this simplified schematic, so long as zero voltage is applied to the "gate" wire, the lower (NPN) transistor remains nonconductive. Consequently, the upper (PNP) transistor cannot sink current, and this transistor also remains nonconductive.

When voltage is applied to the "gate," the lower transistor starts to sink current from the upper transistor. This switches it on. The two transistors now continue to conduct even if power to the "gate" is disconnected, because they have created a positive feedback loop.



Figure 1-5. *Stud-packaged SCR rated for 50V repetitive off-state voltage, no greater than 25A RMS.*



Figure 1-6. *An SCR behaves similarly to an NPN and a PNP transistor coupled together.*

Figure 1-7 shows the same two transistors in simplified form as sandwiches of p-type and n-type silicon layers (on the left), and their combination in an SCR (on the right). Although the actual configuration of silicon segments is not as simple or as linear as this diagram suggests, the SCR can be described correctly as a *PNPN device*.

An SCR is comparable with an electromagnetic **latching relay**, except that it works much faster and more reliably.



Figure 1-7. *The two transistors from the previous figure are shown here in simplified form as two stacks of p-type and n-type silicon layers. These layers are combined in an SCR, on the right.*

Breakdown and Breakover Voltage

The curves in Figure 1-8 illustrate the behavior of a hypothetical SCR, and can be compared with the curves shown for a diac in Figure 2-5 and a triac in Figure 3-10. Beginning with zero voltage applied between anode and cathode, and zero current flowing (i.e., at the center origin of the graph), if we apply a voltage at the anode that is increasingly negative relative to the cathode (i.e., we attempt to force the SCR to allow negative current flow), we see a small amount of leakage, indicated by the darker blue area (which is not drawn to scale). Finally the *breakdown voltage* is reached, at which point the negative potential overcomes the SCR and its impedance drops rapidly, allowing a surge of current to flow, probably damaging it.

Alternatively, starting once again from the center, if we apply a voltage at the anode that is increasingly positive relative to the cathode, two consequences are possible. The dashed curve assumes that there is zero voltage at the gate, and shows that some leakage occurs until the applied potential at the anode reaches the *breakover voltage*, at which point the SCR allows a large current flow, which continues even when the voltage decreases.



Figure 1-8. *The solid curve shows current passing between the anode and cathode of a hypothetical SCR for varying voltages, while a triggering voltage is applied to the gate. The dashed curve assumes that no triggering voltage is applied to the gate.*

In practice, the SCR is intended to respond to a positive gate voltage. Under these circumstances, its behavior is shown by the solid curve in the top-right quadrant in Figure 1-8. The SCR begins to conduct current without having to reach the breakover voltage at the anode.

- When used as it is intended, the SCR should not reach breakdown or breakover voltage levels.

SCR Concept Demo

In Figure 1-9, pushbutton S1 applies voltage to the gate of the SCR, which puts the SCR in self-sustaining conductive mode. When S1 is released, the meter will show that current continues to pass between the anode and the cathode. The X0403DF SCR suggested for this circuit has a holding current of 5mA, which a 5VDC supply should be able to provide with the 1K resistor in the circuit. If necessary, this resistor can be reduced to 680Ω.

Now if pushbutton S2 is pressed, the flow is interrupted. When S2 is released, the flow will not resume. Alternatively, if pushbutton S3 is pressed while the SCR is conducting current, the flow is diverted around the SCR, and when the pushbutton is released, the flow through the SCR will not resume. Thus, the SCR can be shut down either by a normally closed pushbutton in series with it (which will interrupt the current), or a normally open pushbutton in parallel with it (which will divert the current).



Figure 1-9. *In this test circuit, S1 triggers the SCR, while S2 or S3 will stop it. See text for additional details.*

The test circuit is shown installed on a breadboard in Figure 1-10. In this photograph, the red and blue wires supply a minimum of 5VDC. The two red buttons are tactile switches, the one at top left being S1 in the schematic while the one at bottom right is S3. The large switch with a rectangular button is S2; this is normally closed, and opens when pressed. The X0403DF SCR is just below it and to the right. The square blue trimmer is set to the midpoint of its range.

AC Current Applications

If the SCR is used with alternating current, it stops conducting during each negative cycle, and is retriggered in each positive cycle. This suggests one of its primary applications, as a controllable rectifier that can switch rapidly enough to limit the amount of current that passes through it during each cycle.



Figure 1-10. *A breadboarded version of the SCR test circuit. The two red buttons correspond with S1 and S3 in the schematic, while the large rectangular button at top right opens S2. See text for details.*

Variants

SCRs are available in surface-mount, through-hole, and stud packages, to handle increasing currents and voltages. Some special-purpose SCRs can control currents of hundreds of amps, while high-power SCRs are used to switch thousands of amps at more than 10,000V in power distribution systems. They are too specialized for inclusion in this encyclopedia.

Typical power ratings for SCRs in general use are summarized in the next section.

Values

Any SCR will impose a forward voltage drop, which typically ranges from around 1V to 2V, depending on the component.

Because SCRs are often used to modify AC waveforms, the current that the component can pass is usually expressed as the root mean square (RMS) of its peak value.

Commonly Used Abbreviations

- V_{DRM} Maximum repetitive forward voltage that may be applied to the anode while no voltage is applied to the gate (i.e., when the SCR is not in conductive mode).
- V_{RRM} Maximum repetitive reverse voltage that may be applied to the anode while no voltage is applied to the gate (i.e., when the SCR is not in conductive mode).
- V_{TM} Maximum on-state voltage while the SCR is in conductive mode. T indicates that this value changes with temperature.
- V_{GM} Forward maximum gate voltage.
- V_{GT} Minimum gate voltage required to trigger.
- V_{GD} Maximum gate voltage that will not trigger.
- I_{DRM} Peak repetitive forward blocking current (i.e., maximum leakage).
- I_{RRM} Peak repetitive reverse blocking current (i.e., leakage in the off state).
- I_{GM} Maximum forward gate current.
- $I_{T(RMS)}$ Maximum RMS current between anode and cathode while the SCR is in conductive mode. T indicates that this value changes with temperature.
- $I_{T(AV)}$ Maximum average current between anode and cathode while the SCR is in conductive mode. T indicates that this value changes with temperature.
- I_{GT} Maximum gate current required to trigger.
- I_H Typical holding current.
- I_L Maximum latching current.
- T_C Case temperature, usually expressed as an acceptable range.
- T_J Operating junction temperature, usually expressed as an acceptable range.

Surface-mount variants may tolerate maximum anode-cathode currents that typically range from 1A to 10A. Maximum voltages as high as 500V are allowed in some cases. Leakage in the "off" state may be as high as 0.5mA or as low as 5μA. Gate trigger voltage is likely to range from 0.8V to 1.5V, and trigger current of 0.2mA to 15mA is typical.

Through-hole variants may be packaged in TO-92 format (like discrete transistors) or, more commonly, in TO-220 format (like a typical 1A voltage regulator). They may be rated for a maximum of 5A up to 50A, depending on the component, with maximum voltages ranging from 50V to 500V. Leakage is similar to surface-mount variants. The gate trigger voltage is typically around 1.5V, and trigger current ranges from 25–50mA.

A stud-type SCR may have a maximum 50A to 500A current rating, although some components are capable of tolerating even higher values. Maximum voltages of 50V to 500V are possible. Leakage is likely to be higher than in other formats, with 5mA to 30mA being common. The gate trigger voltage is typically 1.5 to 3V, and trigger current may range from around 50mA to 200mA.

How to Use It

Although other applications are possible, in practice SCRs have two main applications:

- Phase control, which interrupts each positive phase of an AC power supply. It can moderate the speed of a motor or the heat generated by a resistive load.
- Overvoltage protection. This can safeguard sensitive components in a circuit where there is a DC power supply.

SCRs are often incorporated in ground-fault circuit interruptors (although not usually as discrete components) and in automotive ignition systems.

Phase Control

Phase control is a convenient way to control or limit the AC power delivered to a load by abbreviating each pulse in the AC waveform. This is done by adjusting the gate voltage so that the SCR blocks the first part of each positive phase, then conducts the remainder, and then stops conducting below its holding level. The SCR will then block the reversed flow in the negative phase of the AC waveform, but an additional SCR with opposite polarity can be added.

This is a form of *pulse-width modulation*. It is highly efficient, as the effective internal resistance of the SCR is either very high or very low, and the component does not waste significant energy in the form of heat.

On a graph showing the fluctuating voltage of an AC waveform, a single cycle is customarily divided into four stages: (1) zero voltage, (2) maximum positive voltage, (3) zero voltage, (4) minimum negative voltage, all measurements being made between the live side of the supply and the neutral side of the supply.

The cycle then repeats. Its transitions are often referred to as *phase angles* of 0 degrees, 90 degrees, 180 degrees, and 270 degrees, as shown in Figure 1-11.

The fluctuating voltage in an AC power supply is proportional with the sine of the phase angle. This concept is illustrated in Figure 1-12. If an imaginary point (shown as a purple dot) is moving in a circular path counterclockwise at a constant speed, its vertical distance (shown in green) above or below the X axis (horizontal centerline) can represent an AC voltage corresponding with the angle (shown as purple arcs) of the circle radius to the point, each angle being measured from at the center relative to a start position at right on the X axis.

When an SCR is used for phase control, the point at which it starts to conduct may be anywhere from 0 to almost 180 degrees. This is achieved by diverting a small amount of the AC power into an RC network attached to the gate of the SCR, as shown in Figure 1-13. The capacitor in this schematic introduces a delay that can be varied by the potentiometer. This enables the SCR to be triggered even after the peak of the AC power signal. In Figure 1-14, the AC power is shown by the center (green) curve, and the slightly delayed, reduced voltage at the gate is shown by the upper, purple curve. When the gate voltage rises to the trigger level, it causes the SCR to begin conducting current, creating an abbreviated output shown in the bottom curve. In this way, triggering from an AC phase angle of 0 degrees to almost 180 degrees is possible. The phase angle where the SCR begins to allow conduction is known as the *conduction angle*.

If two SCRs with opposite polarity are placed in parallel with each other, they can be used to provide phase control on both the positive-going and negative-going sections of an AC cycle. This configuration is used in high-powered devices. A **triac** is used for the same purpose with lower current.

Six SCRs may be used to control three-phase power.

Overvoltage Protection

The tolerance of an SCR for high current makes it suitable for use in a crowbar voltage limiting circuit.

In Figure 1-15, the SCR does not conduct current (other than a small amount of leakage) until the Zener diode senses a voltage above the maximum level considered safe. The diode then allows power to reach the gate of the SCR. Its impedance drops immediately, and the resulting surge of current trips the fuse. After the cause of the overvoltage condition is corrected, the fuse can be replaced and the circuit may resume functioning.

A capacitor is included so brief spikes in the power supply will be passed to ground without triggering the SCR. A resistor of around 100Ω ensures that the gate voltage of the SCR remains near zero during normal operation. When the Zener diode starts to conduct current, the resistor acts as a voltage divider with the diode, so that sufficient voltage reaches the SCR to activate it.

This circuit may be unsuitable for low-voltage power supplies, because the Zener diode has to be chosen with a high enough rating to prevent small power fluctuations from tripping it. Bearing in mind that the real triggering voltage of the diode may be at least plus-or-minus 5% of its rated voltage, the diode may have to be chosen with at least a 6V rating in a 5V circuit, and it may not be activated until the voltage is actually 6.5V. This may be insufficient to protect the components being used with the power supply.



Figure 1-11. *An AC waveform is customarily measured in degrees of phase angle.*

What Can Go Wrong

Like other semiconductors, an SCR can be adversely affected by excessive heat. Usual precautions should be taken to allow sufficient ventilation and heat sinking, especially when components are moved from an open prototyping board to an enclosure in which crowding is likely.

Unexpected Triggering Caused by Heat

On a datasheet, the values for triggering current and holding current are valid only within a recommended temperature range. A buildup of heat can provoke unexpected triggering.

Unexpected Triggering Caused by Voltage

A very rapid increase in forward voltage at the anode can induce a triggering voltage in the gate by capacitive coupling. As a result, the SCR can trigger itself without any external application of gate voltage. This is sometimes known as *dv/dt triggering*. If necessary, a snubber circuit can be added across the anode input to prevent sudden voltage transitions.



Figure 1-12. *The fluctuating voltage of an AC power supply (shown as vertical green lines) is proportional with the sines of the angles (purple arcs) in this diagram. The angles are referred to as phase angles.*

Confusion of AC and DC Ratings

The on-state current for an SCR is averaged only over the width of each pulse that the SCR actually conducts. It is not time-averaged over an entire AC cycle, and it will be different again from a DC rating. Care must be taken to match the current rating with the way in which the component will actually be used.

Maximum Current versus Conduction Angle

Current-carrying capability will be very significantly affected by the length of the duty cycle when the SCR is being used to abbreviate each positive AC pulse. When the SCR imposes a 120-degree conduction angle, it may be able to handle twice the average on-state current as when it is imposing a 30-degree conduction angle. The manufacturer's datasheet should include a graphical illustration of this relationship. If an SCR is chosen for a high conduction angle, and the angle is later reduced, overheating will result, and damage is likely.



Figure 1-13. *In this schematic, an SCR is used to apply phase control, adjusting the power that passes through a load.*

Confusing Symbols

When reading a schematic, unfortunate errors can result from failure to distinguish between the symbol for a **programmable unijunction transistor (PUT)** and the symbol for an SCR. The characteristics of a PUT are described in Volume 1 of this encyclopedia.



Figure 1-14. *If the AC power applied to the anode of an SCR (center) is reduced in voltage and delayed slightly by an RC network, it can trigger the SCR (top), causing it to pass only an abbreviated segment of each positive AC pulse (bottom).*


Voltage regulator
Protected components
0.1µF
100

Figure 1-15. *In this schematic, an SCR is used to provide crowbar overvoltage protection for sensitive components.*

diac

2

A **diac** is a self-triggering type of *thyristor*. Its name is said to be derived from the phrase "diode for AC," and because it is not an acronym, it is not usually capitalized.

A thyristor is defined here as a semiconductor having four or more layers of p-type and n-type silicon. Because the thyristor predated integrated circuits, and in its basic form consists of a single multilayer semiconductor, it is categorized as a discrete component in this encyclopedia. When a thyristor is combined with other components in one package (as in a **solid-state relay**) it is considered to be an integrated circuit.

Other types of thyristor are the **SCR** (silicon-controlled rectifier) and the **triac**, each of which has its own entry in this encyclopedia.

Thyristor variants that are not so widely used, such as the *gate turn-off thyristor (GTO)* and *silicon-controlled switch (SCS)*, do not have entries here.

OTHER RELATED COMPONENTS

- **SCR** (see Chapter 1)
- **triac** (see Chapter 3)

What It Does

The **diac** is a bidirectional thyristor with only two terminals. It blocks current until it is subjected to sufficient voltage, at which point its impedance drops very rapidly. It is primarily used to trigger a **triac** for purposes of moderating AC power to an **incandescent lamp**, a resistive heating element, or an AC **motor**. The two leads on a diac have identical function and are interchangeable.

By comparison, a **triac** and an **SCR** are thyristors with three leads, one of them being referred to as the gate, which determines whether the component becomes conductive. A triac and a diac allow current to flow in either direction, while an SCR always blocks current in one direction.

Symbol Variants

The schematic symbol for a diac, shown in Figure 2-1, resembles two diodes joined together, one of them inverted relative to the other. Functionally, the diac is comparable with a pair of Zener diodes, as it is intended to be driven beyond the point where it becomes saturated. Because its two leads are functionally identical, they do not require names to differentiate them. They are sometimes referred to as A1 and A2, in recognition that either of them may function as an anode; or they may be identified as MT1 and MT2, MT being an acronym for "main terminal."



Figure 2-1. *Symbol variants to represent a diac. All four are functionally identical.*

The symbol may be reflected left to right, and the black triangles may have open centers. All of these variants mean the same thing. Occasionally the symbol has a circle around it, but this style is now rare.

When only a moderate voltage is applied (usually less than 30V) the diac remains in a passive state and will block current in either direction, although a very small amount of *leakage* typically occurs. When the voltage exceeds a threshold known as its *breakover level*, current can flow, and the diac will continue to conduct until the current falls below its *holding level*.

A sample diac is shown in Figure 2-2.



Figure 2-2. *Because a diac is not intended to pass significant current, it is typically packaged in a small format. The graph squares in the photograph each measure 0.1".*

How It Works

Figure 2-3 shows a circuit that demonstrates the conductive behavior of a diac.



Figure 2-3. *A test circuit to demonstrate the behavior of a diac. See text for details.*

When the pushbutton is held down, current from the positive side of the AC supply flows through the diode and the 470K resistor to the capacitor. The diac is not yet conductive, so the capacitor accumulates a potential that can be monitored with the volt meter. After about 30 seconds, the charge on the capacitor reaches 32V. This is the breakover voltage for this particular diac, so it becomes conductive. The positive side of the capacitor can now discharge through the diac and the 1K series resistor to ground.

If the pushbutton is released at this moment, the meter will show that the capacitor discharges to a potential below the holding level of the diac. The capacitor now stops discharging because the diac has ceased being conductive.

If the pushbutton is held down constantly, the meter will show the capacitor charging and then discharging through the diac repeatedly, so that the circuit behaves as a *relaxation oscillator*. The 1K series resistor is included to protect the diac from excessive current. If a standard quarter-watt resistor is used, it should not become unduly warm because current passes through it only intermittently.

- Because this circuit uses 115VAC, basic precautions should be taken. The fuse should not be omitted, the capacitor should be rated for at least 50V, and the circuit should not be touched while it is connected to the power source. Breadboarding a circuit using this voltage requires caution and experience, as wires can easily come loose, and components can be touched accidentally while they are live.

Figure 2-4 shows the test circuit on a breadboard. The red and blue leads at the top of the photograph are from a fused 115VAC power supply. The live side of the supply passes through a diode to a pushbutton switch that has a rectangular black cap. A 470K resistor connects the other side of the switch to the positive side of a 100µF electrolytic capacitor, and also to the diac (small blue component). A 1K resistor connects the other end of the diac back to the negative side of the capacitor, which is grounded. The yellow and blue wires leaving the photograph at the left are connected with a volt meter, which is not shown.



Figure 2-4. *A breadboarded version of the diac test circuit. See text for details.*

The behavior of a diac is also illustrated in Figure 2-5, which can be compared with the curves in Figures 3-10 and 1-8, depicting the behavior of a triac and an SCR respectively.



Figure 2-5. *The curve shows current passing through a diac when various voltages are applied.*

Switching AC

The diac cannot function as a switch, because it lacks the third terminal which is found in a triac, an SCR, or a bipolar transistor. However, it is well suited to drive the gate of a triac, because the behavior of a diac is symmetrical in response to opposite voltages, while the triac is not. If an AC voltage applied to a diac is adjusted with a potentiometer in an RC circuit, the diac will pass along a portion of each positive or negative pulse, and will delay it by a brief amount of time determined by the value of the capacitor in the RC circuit and the setting of the potentiometer. This is known as *phase control*, as it controls the *phase angle* at which the diac allows current to flow.

See Figure 3-13 for a schematic showing a diac driving a triac. See Figures 1-14 and 3-11 for graphs illustrating phase control. See "Phase Control" for a discussion of phase in AC waveforms.

Variants

Diacs are available in through-hole and surface-mount formats. Because they are not intended to handle significant current, no heat sink is included.

A *sidac* behaves very similarly to a diac, its name being derived from "silicon diode for alternating current." Its primary difference from generic diacs is that it is designed to reach its breakover voltage at a higher value, typically 120VAC or 240VAC.

Values

When performing its function to trigger a triac, a diac is unlikely to pass more than 100mA.

The breakover voltage of a diac is usually between 30V and 40V, with a few versions designed for up to 70V. When the diac starts to conduct, its on-state impedance is sufficient to reduce the voltage significantly, with 5V being a typical minimum output voltage.

Although the rise time when a diac responds is very brief (around 1µs), the component is not expected to run at a high frequency. It will normally be used with 50Hz or 60Hz AC to trigger a triac. For this reason, its repetitive peak on-state current is usually specified at no more than 120Hz.

Abbreviations in datasheets are likely to include:

- V_{BO} Breakover voltage (sometimes may be specified as latching voltage, which for a diac is the same thing).
- V_{BO1} - V_{BO2} Breakover voltage symmetry. The hyphen is intended as a minus sign, so that this value is the maximum difference between breakover voltage in each direction.
- V_O Minimum output voltage.
- I_{TRM} Repetitive peak on-state current.
- I_{BO} Breakover current, usually the maximum required, and less than 20µA.
- I_R Maximum leakage current, usually less than 20µA.
- T_J Operating junction temperature, usually expressed as an acceptable range.

What Can Go Wrong

Like other semiconductors, a diac is heat sensitive. Usual precautions should be taken to allow sufficient ventilation and heat sinking, especially when components are moved from an open prototyping board to an enclosure in which crowding is likely.

Unexpected Triggering Caused by Heat

On a datasheet, a value for breakover current is valid only within a recommended temperature range. A buildup of heat can provoke unexpected triggering.

Low-Temperature Effects

A higher breakover voltage will be required by a diac operating at low temperatures, although the variation is unlikely to be greater than plus-or-minus 2% within a normal operating range. Temperature has a much more significant effect on a triac.

Manufacturing Tolerances

The breakover voltage for a diac is not adjustable, and may vary significantly between samples of the component that are supposed to be identical. The diac is not intended to be used as a precision component. In addition, while its breakover voltage should be the same in either direction, a difference of plus-or-minus 2% is possible (1% in some components).

triac

3

A **triac** is a gate-triggered type of *thyristor*. Its name was probably derived from the phrase “triode for AC,” and because it is not an acronym, it is not usually capitalized.

A thyristor is defined here as a semiconductor having four or more layers of p-type and n-type silicon. Because the thyristor predated integrated circuits, and in its basic form consists of a single multilayer semiconductor, it is categorized as a discrete component in this encyclopedia. When a thyristor is combined with other components in one package (as in a **solid-state relay**) it is considered to be an integrated circuit.

Other types of thyristor are the **SCR** (silicon-controlled rectifier) and the **diac**, each of which has its own entry in this encyclopedia.

Thyristor variants that are not so widely used, such as the *gate turn-off thyristor (GTO)* and *silicon-controlled switch (SCS)*, do not have entries here.

OTHER RELATED COMPONENTS

- **SCR** (see Chapter 1)
- **diac** (see Chapter 2)

What It Does

The **triac** is ubiquitous in AC dimmers for **incandescent lamps**. It is also used to control the speed of AC motors and the output of resistive heating elements. It is a type of *thyristor* which contains five segments of p-type and n-type silicon and has three leads, one of them attached to a gate that can switch a bidirectional flow of current between the other two. Its name was originally a trademark, generally thought to be derived from the phrase “triode for AC.” A triode was a common type of vacuum tube when thyristors were first introduced in the 1950s.

By comparison, a **diac** is a thyristor with only two leads, allowing current to flow in either direction when the component reaches a *breakover voltage*. Its name was probably derived from the phrase “diode for AC.” It is often used in conjunction with a triac.

An **SCR** (silicon-controlled rectifier) is a thyristor that resembles a triac, as it has three leads, one of them a gate. However, it only allows current to flow in one direction.

Symbol Variants

The schematic symbol for a triac, shown in Figure 3-1, resembles two diodes joined together, one of them inverted relative to the other. While a triac does not actually consist of two diodes, it is functionally similar, and can pass current in either direction.



Figure 3-1. *The schematic symbol for a triac, with four naming conventions that are used for its leads. The different conventions do not indicate any functional difference.*

An appended bent line represents the gate. The labels for the other two leads are not standardized, and can be referred to as A1 and A2 (for Anode 1 and Anode 2), or T1 and T2 (for Terminal 1 and Terminal 2), or MT1 and MT2 (for Main Terminal 1 and Main Terminal 2). The choice of terms does not indicate any functional difference. In this encyclopedia entry, A1 and A2 are used.

The A1 terminal (or T1, or MT1) is always shown closer to the gate than A2 (or T2, or MT2). This distinction is important because although the triac can pass current in either direction, its behavior is somewhat asymmetrical.

- Voltages are expressed relative to terminal A1 (or T1, or MT1, if those terms are used).

The schematic symbol may be reflected or rotated, the black triangles may have open centers, and the placement of the bent line representing the gate may vary. However, terminal A1 is always nearer to the gate than terminal A2.

Figure 3-2 shows 12 of the 16 theoretical possibilities. All of these variants are functionally identical. Occasionally the symbol has a circle around it, but this style is now rare.



Figure 3-2. *Interchangeable variants of the schematic symbol for a triac.*

Triacs with various characteristics are shown in Figures 3-3, 3-4, and 3-5.



Figure 3-3. *The BTA208X-1000B triac can conduct 8A continuous on-state current RMS, and withstands peak off-state voltage of up to 1,000V. This is a "snubberless" triac.*



Figure 3-4. *The BTB04-600SL triac can conduct 4A continuous on-state current RMS, and withstands peak off-state voltage of up to 600V.*



Figure 3-5. *The MAC97A6 triac can conduct 0.8A continuous on-state current RMS, and withstands peak off-state voltage of up to 400V.*

How It Works

When no gate voltage is applied, the triac remains in a passive state and will block current in either direction between A1 and A2, although a very small amount of *leakage* typically occurs. If the gate potential becomes sufficiently positive *or* negative relative to terminal A1, current can begin to flow between A1 and A2 in *either* direction. This makes the triac ideal for controlling AC.

Quadrants

While a gate voltage is applied, four operating modes are possible. In each case, A1 is the reference (which can be thought of as being held at a neutral ground value). Because the triac is conducting AC, voltages above and below ground will occur. The four modes of operation are often referred to as four *quadrants*, and are typically arranged as shown in Figure 3-6.

In some reference sources (especially educational text books), current is shown with an arrow indicating a flow of electrons moving from negative to positive. Because the type of current flow is often undefined, diagrams should be interpreted carefully. In this encyclopedia, current is always shown flowing from a more-positive location to a more-negative location.

Quadrant 1 (upper right)

A2 is more positive than A1, and the gate is more positive than A1. Conventional current (positive to negative) will flow from A2 to A1. (This behavior is very similar to that of an **SCR**.)

Quadrant 2 (upper left)

A2 is more positive than A1, and the gate is more negative than A1. Once again, conventional current (positive to negative) will flow from A2 to A1.

Quadrant 3 (lower left)

A2 is more negative than A1, and the gate is more negative than A1. Conventional current is reversed from A1 to A2.

Quadrant 4 (lower right)

A2 is more negative than A1, but the gate is more positive than A1. Conventional current is reversed from A1 to A2.

- Note that two positive symbols or two negative symbols in Figure 3-6 do not mean that both locations are of equal voltage. They simply mean that these locations are at potentials that are significantly different from A1.



Figure 3-6. *The "quadrants" of triac behavior. Positive and negative symbols indicate which terminal is "more positive" or "more negative" than A1. The ground symbol represents a potential midway between positive and negative. See text for details.*

Suppose that gate current increases gradually. When it reaches the *gate threshold current* of the triac, the component starts conducting between A1 and A2. If the current between A1 and A2 rises above the value known as the *latching current*, it will continue to flow, even if gate current disappears completely.

If the self-sustaining current through the triac gradually diminishes, while there is no voltage applied to the gate, conduction between the main terminals will stop spontaneously when it falls below a level known as the *holding current*. This behavior is similar to that of an SCR. The triac now returns to its original state, blocking current until the gate triggers it again.

The triac is sufficiently sensitive to respond to rapid fluctuations, as in 50Hz or 60Hz AC.

Threshold, Latching, and Holding Current

Figure 3-7 shows the relationship between the gate threshold current, the latching current, and holding current. In the upper half of the figure, gate current is shown fluctuating until it crosses the threshold level. This establishes current flow between the main terminals, shown in the lower half of the figure. Prior to this moment, a very small amount of leakage current occurred (shown in the figure, but not to scale).

In this hypothetical scenario, the triac starts passing current between external components—and the current exceeds the latching level. Consequently, gate current can diminish to zero, and the triac remains conductive. However, when external factors cause the current between the main terminals to diminish below the holding level, the triac abruptly ceases to be conductive, and current falls back to the leakage level.



Figure 3-7. *The relationship between gate current of a triac and the current between its main terminals. See text for details.*

Unlike a **bipolar transistor**, a triac is either "on" or "off" and does not function as a *current ampli-*

fier. When it has been triggered, the impedance between A1 and A2 is low enough for heat dissipation to be manageable even at relatively high power levels.

Triac Testing

Figure 3-8 shows a circuit which can demonstrate the conductive behavior of a triac. For simplicity, this circuit is DC powered. In a real application, the triac is almost always used with AC.



Figure 3-8. *A test circuit to show the behavior of a triac when varying positive and negative potentials are applied to the gate and to the A2 terminal, relative to A1.*

Note that this circuit requires at least a +12VDC and -12VDC power supply (higher values may also be used). The ground symbol represents a midpoint voltage of 0VDC, applied to terminal A1 of the triac, which is an MAC97A6 or similar. If a dual-voltage power supply is unavailable, the gate of the triac can be connected directly to +12VDC, omitting potentiometer P2; but in this case, only two operating modes of the triac can be demonstrated by turning potentiometer P1.

Each potentiometer functions as a voltage divider between the positive and negative sides of the power supply. P1 applies a positive or negative voltage to A2, relative to A1. P2 applies a positive or negative voltage to the gate, relative to A1.

If the test begins with both potentiometers at the top ends of their range, A1 and G both have a positive potential relative to A1, so that the triac is now in quadrant 1 of its operating modes. Pressing the pushbutton should cause it to start conducting current limited by the 1K resistor, and the meter should change from measuring 0mA to around 12mA. If the pushbutton is released, the triac should continue to conduct current, because 12mA is above this triac's latching level. If P1 is slowly moved toward the center of its range, the current diminishes, ceasing when it falls below the holding level. If P1 is now moved back to the top of its range, the current will not resume until the triac is retriggered with the pushbutton.

The test can be repeated with P1 at the top of its range and P2 at the bottom of its range, to operate the triac in quadrant 2; P1 at the bottom of its range and P2 at the bottom of its range, to operate the triac in quadrant 3; and P1 at the bottom of its range and P2 at the top of its range, to operate the triac in quadrant 4. The functionality should be the same in each case. The pushbutton will initiate a flow of current, which will diminish when P1 is turned toward the center of its range.

In any of these quadrants, P2 can be turned slowly toward the center of its range while the pushbutton is pressed repeatedly. This will allow empirical determination of the gate threshold current for this triac. The meter, measuring milliamps, will measure the current if it is inserted between the wiper of the potentiometer and the gate of the triac.

The test circuit is shown installed on a breadboard in Figure 3-9. In this photograph, the red and blue wires at left supply +12VDC and -12VDC relative to the black ground wire at top right. The yellow and green wires connect with a meter set to measure milliamps. The red button is a tactile switch, while the MAC97A6 triac is just above it and to the left. The square blue 10K trimmers are set to opposite ends of their scales, so that the meter will show current flowing when the tactile switch is pressed.



Figure 3-9. *A breadboarded triac test circuit.*

Breakover Voltage

If a much higher voltage is applied to A2, the triac can be forced to conduct current without any triggering voltage being applied to the gate. This occurs when the potential between A1 and A2 reaches the triac's *breakover voltage*, although the component is not designed to be used this way. The concept is illustrated in Figure 3-10, which can be compared with the behavior of an SCR illustrated in Figure 1-8 and the behavior of a diac shown in Figure 2-5. While the term *breakdown voltage* defines the minimum reverse voltage required to force a diode to conduct, *breakover voltage* refers to the minimum forward voltage that has this effect. Because a triac is designed to conduct in both directions, it can be thought of as having a breakover voltage in both directions.

In Figure 3-10, the numbers in yellow squares are the quadrants referred to in Figure 3-6. The solid curve represents current flow if a triggering voltage is applied to the gate while a positive or negative potential is applied to A2, relative to A1. If the gate is not triggered while the voltage between A1 and A2 gradually increases, the dashed section of the curve illustrates the outcome when the component reaches breakover voltage. Although this may not damage the triac, the component becomes uncontrollable.

- In normal usage, the voltage between A1 and A2 should not be allowed to reach breakover level.



Figure 3-10. *The solid curve shows current passing between A1 and A2 in a hypothetical triac, for varying voltages, while triggering voltage is applied to the gate. The dashed curve assumes that no triggering voltage is applied to the gate. The numbers in yellow squares are the quadrants of triac operation.*

Switching AC

"Switching" AC with a triac means interrupting each pulse of current so that only a portion of it is conducted through to the load. Usually this is done with the triac functioning in quadrants 1 and 3. In quadrant 3, the polarity of the flow between A1 and A2 is opposite to that in quadrant 1, and the gate voltage is also reversed. This enables a relatively simple circuit to control the duration of each half-cycle passing through the triac. The theory of this circuit is shown in Figure 3-11.


Alternating supply voltage (green) and current to gate (purple)
AC power to triac
AC to gate reduced by resistor
Gate threshold current
Gate threshold current
Current between main terminals
Latching level
Holding level
Latching level
Holding level
Time

Figure 3-11. *To moderate the power of AC current, a triac can block a section of each AC pulse.*

The upper section of Figure 3-11 shows alternating voltage to the triac in green. The purple curve represents the gate current of the triac, reduced by a variable resistor. (The figure is for conceptual purposes only; the alternating power supply voltage and the fluctuating gate current cannot actually share the same vertical scale of a graph.)

Figure 3-11 can be compared with Figure 3-7, except that the negative threshold level for the gate is now shown as well as the positive threshold level. Remember, either a positive or negative voltage can activate the gate.

In Figure 3-11, initially the triac is nonconductive. As time passes, the gate current reaches the threshold level, and this triggering event enables current to flow between the main terminals of the triac, as shown in the lower part of the figure.

This current exceeds the latching level, so it continues to flow, even though the gate current diminishes below its threshold level. Finally the current between the main terminals falls below the holding level, at which point the triac stops conducting. It waits for the next triggering event, which occurs as the power supply swings to negative.

This simple system blocks a section of each AC pulse, which will vary in length depending how much current is allowed to flow through the gate. Because the blocking process occurs rapidly, we notice only the reduced overall power passing through the triac (in terms of the brightness of a light, the heat emitted by a resistive element, or the speed of a motor).

Unfortunately, there is a problem in this scenario: the triac does not quite behave symmetrically. Its gate threshold level for positive current is not exactly equal and opposite to its gate threshold level for negative current. The upper part of Figure 3-11 shows this flaw in the differing vertical offsets of the positive and negative thresholds from the central zero line.

The result is that negative AC pulses through the triac are shorter than positive pulses. This asymmetry produces harmonics and noise that can feed back into power supply wiring, interfering with other electronic equipment. The actual disparities in gate response, in each quadrant of operation for two triacs, are shown in Figure 3-12.

Current capacity of triac	Ratio of gate current required to conduct, relative to quadrant 1		
	Quadrant 2	Quadrant 3	Quadrant 4
4 amp	1.6	2.5	2.7
10 amp	1.5	1.4	3.1

Figure 3-12. *Because the internal structure of a triac is asymmetrical, it requires a different trigger current in each of its operating quadrants. This table, derived from a Littelfuse technical briefing document, shows the ratio of the minimum trigger current in quadrants 2, 3, and 4 relative to quadrant 1.*

See Figure 1-14 for a graph illustrating phase control in the SCR. See "Phase Control" for a discussion of phase in AC waveforms generally.

Triac Triggered by a Diac

The problem of asymmetrical triggering can be overcome if the triac is triggered with a voltage pulse generated by another component that does behave symmetrically. The other component is almost always a diac, which is another type of thyristor. Unlike an SCR or a triac, it has no gate. It is designed to be pushed beyond its breakover voltage, at which point it latches and will continue to conduct until current flowing through it diminishes below its holding level. See Chapter 2 for more information about the diac.

In Figure 3-13, the diac is shown to the right of the triac, and is driven by a simple RC network consisting of a fixed resistor, a potentiometer, and a capacitor. (In an actual application, the RC network may be slightly more complex.) The capacitor takes a small amount of time to charge during each half-cycle of AC. The length of this delay is adjusted by the potentiometer, and determines the point in each AC half-cycle when the voltage to the diac reaches breakover level. Because the delay affects the phase of the AC, this adjustment is known as *phase control*.

As the voltage exceeds breakover level, the diac starts to pass current through to the gate of the triac, and triggers it. The holding level of the diac is lower than its latching level, so it continues to pass current while the capacitor discharges and the voltage diminishes. When the current falls below the holding level, the diac stops conducting, ready for the next cycle. Meanwhile, the triac continues to pass current until the AC voltage dips below its holding level. At this point, the triac becomes nonconductive until it is triggered again.

This chopped waveform will still create some harmonics, which are suppressed by the coil and capacitor at the left side of the circuit in Figure 3-13.



Figure 3-13. *A minimal schematic showing typical operation of a triac, with a diac supplying pulses to the triac gate. The potentiometer adjusts the delay created by the capacitor.*

Other Triac Drivers

It is possible, although unusual, to drive a triac from a source other than a diac.

Simple on-off control can be achieved by using a special optocoupler such as the MOC3162 by Fairchild Semiconductor. This emits a switching signal to a triac only when the AC voltage passes through zero. A *zero cross* circuit is desirable because it creates much less interference. The use of an optocoupler helps to isolate the triac from other components.((("zero cross circuit"))

Phase control can be achieved using an optocoupler such as the H11L1, which can be driven by rectified but unsmoothed AC after it passes through a Zener diode to limit the voltage. The output from the optocoupler is logic-compatible and can be connected with the input to a timer such as the 555, set to one-shot mode. Each pulse from the timer passes through another optocoupler such as the MOC3023, which uses an internal LED to trigger the gate of a triac.

Yet another possibility is to use the programmed output from a microcontroller, through an optocoupler, to control the gate of a triac. An online search for the terms “microcontroller” and “triac” will provide some additional suggestions.

Charge Storage

While switching AC, the internal charge between A1 and A2 inside the triac requires time to dissipate before the reverse voltage is applied; otherwise, *charge storage* occurs, and the component may start to conduct continuously. For this reason, the triac is normally restricted to relatively low frequencies such as domestic 60Hz AC power.

When a triac controls a motor, the phase lag between voltage and current associated with an inductive load can interfere with the triac’s need for a transitional moment between a positive and negative voltage cycle. In a datasheet, the term *commutating dv/dt* defines the rate of rise of opposite polarity voltage that the triac can withstand without locking into a continuous-on state.

An RC *snubber network* is often wired in parallel with A1 and A2 to control the rise time of voltage to the triac, as shown within the darker blue rectangle in Figure 3-14, where a resistor and capacitor have been added just to the left of the triac. The highest resistance and lowest capacitance, consistent with trouble-free operation, should be chosen. Typical values are 47Ω to 100Ω for the resistor, and 0.01µF to 0.1µF for the capacitor.

Variants

Triacs are available in through-hole and surface-mount packages.

Some components that are referred to as triacs actually contain two SCR components of opposite polarity. The “alternistor” range from Littelfuse is an example. The SCR will tolerate faster voltage rise times than a conventional triac, and is more suitable for driving inductive loads such as large motors.



Figure 3-14. *To prevent a triac from locking itself into a continuous-on state while driving an inductive load such as a motor, a snubber circuit can be added (shown here as a resistor and capacitor in the darker blue rectangle to the left of the triac).*

A *snubberless triac*, as its name implies, is designed to drive an inductive load without need for a snubber circuit. An example is the STMicroelectronics BTA24. Datasheets for this type of component impose some limits that may be stricter than for a generic triac.

Values

Surface-mount triacs are typically rated between 2A to 25A of switched AC current (RMS), the higher-current versions being as large as 10mm square. The necessary gate trigger voltage may range from 0.7V to 1.5V. Through-hole packages may be capable of slightly higher currents (up to 40A), with gate trigger voltages of 1V to 2.5V being common.

As noted previously, the majority of triacs are restricted to relatively low frequency switching, 60Hz being very common.

Abbreviations in datasheets are likely to include:

- V_{DRM} or V_{RRM} Peak repetitive reverse off-state voltage. The maximum reverse voltage that the component will withstand in its “off” state without experiencing damage or allowing current to pass.

- V_{TM} The maximum voltage difference between A1 and A2, measured with a short pulse width and low duty cycle.
- V_{GT} Gate trigger voltage necessary to produce the gate trigger current.
- I_{DRM} Peak repetitive blocking current (i.e., maximum leakage).
- I_{GM} Maximum gate current.
- I_{GT} Minimum gate trigger current.
- I_H Holding current.
- I_L Latching current.
- $I_{T(RMS)}$ On-state RMS current. The maximum value passing through the component on a continuous basis.
- I_{TSM} Maximum non-repetitive surge current. Specified at a stated pulse width, usually 60 Hz.
- T_C Case temperature, usually expressed as an acceptable range.
- T_J Operating junction temperature, usually expressed as an acceptable range.

What Can Go Wrong

Like other semiconductors, a triac is heat sensitive. Usual precautions should be taken to allow sufficient ventilation and heat sinking, especially when components are moved from an open prototyping board to an enclosure in which crowding is likely.

Unexpected Triggering Caused by Heat

On a datasheet, a value for triggering current is valid only within a recommended temperature range. A buildup of heat can provoke unexpected triggering.

Low-Temperature Effects

Significantly higher gate current will be required by a triac operating at low temperatures. It is quite possible that the component will need twice as much current at 25° C compared with 100° C, junction temperature. If the triac receives insufficient current, it will not turn on.

Wrong Type of Load

If an **incandescent lamp** is replaced with a **fluorescent light** or **LED area lighting**, a preexisting triac may no longer work as a dimmer. Fluorescent lamps will have some inductance, and may also provide a capacitive load, either of which will interfere with the normal behavior of a triac.

The light output of an LED varies very differently compared with the light output of an incandescent bulb, in response to reduction in power. Therefore an LED should be dimmed using pulse-width modulation that is appropriate for its output characteristics. A triac is generally not suitable.

Wrongly Identified Terminals

A triac is often thought of as a symmetrical device, because it is designed to switch AC current using either positive or negative voltage at the gate. In reality, its behavior is asymmetrical, and if it is installed “the wrong way around” it may function erratically or not at all.

Failure to Switch Off

As already noted (see “Charge Storage” on page 23), a triac will tend to suffer from *charge storage* if there is insufficient time between the end of one half-cycle and the beginning of the next. A component that works with a resistive load may cease to function if it is used, instead, to power an inductive load.

4

solid-state relay

A **solid-state relay** is less-commonly referred to by its acronym, *SSR*. It is sometimes regarded as an **optocoupler**, but in this encyclopedia the two components have separate entries. An optocoupler is a relatively simple device consisting of a light source (usually an **LED**) and a light sensor, in one package. It is used primarily for isolation rather than to switch a high current. A solid-state relay can be thought of as a substitute for an electromagnetic **relay**, usually has additional components in its package, and is intended to switch currents of at least 1A.

A component that works like a solid-state relay but only switches a 5V (or lower) logic signal may be referred to as a *switch*, even though it is entirely solid-state. This type of component is included in this entry because it functions so similarly to a solid-state relay.

OTHER RELATED COMPONENTS

- **electromagnetic relay** (see Volume 1)
- **optocoupler** (see Chapter 5)

What It Does

A **solid-state relay** (SSR) is a semiconductor package that emulates an electromagnetic **relay** (see Volume 1). It switches power on or off between its output terminals in response to a smaller current and voltage between its input terminals. Variants can switch AC or DC and may be controlled by AC or DC. An SSR functions as a *SPST switch*, and is available in normally open or normally closed versions. SSRs that function as an SPDT switch are relatively unusual and actually contain more than one SSR.

No single schematic symbol has been adopted to represent a solid-state relay, but some alternatives are shown in Figure 4-1:

Top

An unusually detailed depiction of an SSR that switches DC current using MOSFETS. Symbols for this device often omit the diodes on the output side and may simplify the MOSFET symbols.

Bottom left

An SSR that uses an internal **triac** to switch AC. The box labeled 0x indicates that this is a *zero-crossing* relay, meaning that it switches when alternating voltage crosses the 0V level from positive to negative or negative to positive.

Bottom right

A generic SSR, showing a symbol for a normally open relay, although whether it is designed for AC or DC is unclear.

Advantages

- Great reliability and long life.
- No physical contacts that are vulnerable to arcing and erosion or (under extreme conditions) that could weld themselves together.

- Very fast response, typically 1µs on and 0.5µs off.
- Very low power consumption on the input side, as low as 5mA at 5VDC. Many solid-state relays can be driven directly from logic chips.
- Lack of mechanical noise.
- No contact bounce; a clean output signal.
- No coil that would introduce back EMF into the circuit.
- Safe with flammable vapors, as there is no sparking of contacts.
- Often smaller than a comparable electromagnetic relay.
- Insensitive to vibration.
- Safer for switching high voltages, as there is complete internal separation between input and output.
- Some variants work with input control voltages as low as 1.5VDC. Electromagnetic relays typically require at least 3VDC (or more, where larger relays are required to switch higher currents).

Disadvantages

- Less efficient; its internal impedance introduces a fixed-value voltage drop on the output side (although this may be negligible when switching higher voltages).
- Generates waste heat in its "on" mode, in accordance with the voltage drop.
- Passes some *leakage* current (usually measured in microamps) on the output side when the relay is supposed to be "off."
- A DC solid-state relay usually requires observation of polarity on the output side. An electromagnetic relay does not.
- Brief voltage spikes on the input side, which would be ignored by a slower electromagnetic relay, may trigger a solid-state relay.
- More vulnerable than an electromagnetic relay to surges and spikes in the current that is switched on the output side.



Figure 4-1. *Schematic symbols for solid-state relays have not been standardized. See text for details.*

How It Works

Almost all modern SSRs contain an internal **LED** (light-emitting diode, see Chapter 22) which is switched on by the control input. Infrared light from the LED is detected by a sensor consisting of one or more **phototransistors** or **photodiodes**. In a relay that controls DC current, the sensor usually switches a **MOSFET** (see Volume 1) or an **SCR** (silicon-controlled rectifier—see Chapter 1). In relays that control AC current, a **triac** (see Chapter 3) controls the output. Because the input side and the output side of the SSR are linked only by a light signal, they are electrically isolated from each other.

The MOSFETs require so little power, it can be provided entirely by light falling on an array of 20 or more photodiodes inside the SSR package.

Typical solid-state relays are shown in Figures 4-2 and 4-3.



Figure 4-2. *A solid-state relay capable of switching up to 7A DC. See text for a detailed description.*

The Crydom DC60S7 accepts a control voltage ranging from 3.5VDC to 32VDC, with a typical input current of less than 3mA. Maximum turn-on time is 0.1ms and maximum turn-off time is 0.3ms. This relay can switch up to 7A and tolerates a surge of up to twice that current. It imposes a voltage drop of as much as 1.7VDC, which can become a drawback when switching voltages that are significantly lower than its maximum 60VDC. The electronics are sealed in thermally conductive epoxy, mounted on a metal plate approximately 1/8" thick which can be screwed down onto an additional heat sink.

The Crydom CMX60D10 tolerates a more limited range of control voltages (3VDC to 10VDC) and requires a higher input current of 15mA at 5VDC. However, its very low maximum on-state resistance of 0.018Ω imposes a much smaller voltage drop of less than 0.2 volts when passing 10A. This results in less waste heat and enables a *single-inline package* (SIP) without a heat sink. The CMX60D10 weighs 0.4 ounces, as opposed to the 3 ounces of the DC60S7. Relays from other manufacturers use similar packaging and have similar specifications.



Figure 4-3. *A solid-state relay capable of switching up to 10A. Its lower internal resistance results in less waste heat and enables a smaller package. See text for a detailed description.*

Variants

Many solid-state relays have protective components built into the package, such as a varistor on the output side to absorb transients. Check datasheets carefully to determine how much protection from external components may be necessary when switching an inductive load.

Instantaneous versus Zero Crossing

A *zero crossing* SSR is one that (a) switches AC current and (b) will not switch "on" until the instant when the AC voltage crosses through 0V. The advantages of this type are that it does not have to be built to switch such a high current, and creates minimal voltage spike when the switching occurs.

All SSRs that are designed to switch AC will wait for the next voltage zero crossing before switching to their "off" state.

NC and NO Modes

Solid-state relays are SPST devices, but different models may have a normally closed or normally open output. If you require double-throw operation, two relays can be combined, one normally closed, the other normally open. See Figure 4-4. A few manufacturers combine a normally closed relay and a normally open relay in one package, to emulate a SPDT relay.



Figure 4-4. *A normally closed solid-state relay can be paired with a normally open solid-state relay to emulate a SPDT switch. This combination is available in a single package from some manufacturers.*

Packaging

High-current solid-state relays are often packaged with screw terminals and a metal base that is appropriate for mating with a *heat sink*. Some are sold with heat sinks integrated. Spade terminals and crimp terminals may be optional. The Crydom DC60S7 shown in Figure 4-2 is an example. This type of package may be referred to as *industrial mount.*

Lower-current solid-state relays (5A or less), and those with a very low output resistance, may be packaged with single-inline pins for through-hole mounting in circuit boards.

Solid-State Analog Switch

DIP packaging may be used for solid-state relays that are designed for compatibility with the low voltages and currents of logic chips. This type of component may be referred to simply as a *switch*. The 74HC4316 is an example, pictured in Figure 4-5.



Figure 4-5. *This DIP package contains four "switches" that function as solid-state relays but are restricted to low voltages and currents, compatible with logic chips. See text for details.*

Typically the control voltage and the switched voltage are limited between +7V and −7V, with a maximum output current of 25mA. Each internal switch has its own Control pin, while an additional Enable pin forces all switches into an "off" state if its logic state is high. The simplified functionality of this component is illustrated in Figure 4-6, without showing internal optical isolation.

The "on" resistance of each internal pathway will be approximately 200Ω when the component is powered with +5VDC on the positive side and 0VDC on the negative side. This resistance drops to 100Ω if the negative power supply is -5VDC.

If all of the outputs from the chip are shorted together, it functions as a **multiplexer** (see Chapter 16). In fact, this type of switch component is often listed in catalogs as a multiplexer, even though it has other applications.

Because the component tolerates equal and opposite input voltages, it is capable of switching AC.



Figure 4-6. *The functionality of a chip containing four solid-state analog switches. A high state on a Control pin closes its associated switch. The Enable pin must be held low for normal operation; a high Enable state forces all the switches into the "off" position. If the outputs are tied together, this component can function as a multiplexer.*

Values

Industrial-mount solid-state relays typically can switch currents ranging from 5A to 500A, with 50A being very common. The higher-current relays mostly require DC control voltage; 4V to 32V are typical, although some versions can go much higher. They contain an SCR or triac to switch AC.

Smaller solid-state relays in SIP, DIP, or surface-mount packages often use MOSFETs on the output side, and are often capable of switching up to 2A or 3A. Some can switch either AC or DC, depending on the way the output is wired. The LED on the input side may require as little as 3mA to 5mA for triggering.

How to Use It

Solid-state relays find their primary uses in telecommunications equipment, industrial control systems and signalling, and security systems.

The component is very simple externally. Power on the input side can come from any source capable of delivering the voltage and current specified by the manufacturer, and any device that doesn't exceed maximum current rating can be connected to the output side, so long as provision is made for suppressing back-EMF from an inductive load, as shown in Figure 4-7. Often a solid-state relay can be substituted directly for an electromagnetic relay, without modifying the circuit.



Figure 4-7. *Use of a diode around an inductive load, to protect a solid-state relay from back-EMF.*

Solid-state relays are heat sensitive, and their rating for switching current will diminish as their temperature increases. Manufacturer datasheets will provide specific guidance. Using a heat sink will greatly improve the performance. Bear in mind that the relay generates heat continuously while it is in its "on" mode—about 1 watt per ampere.

Because it requires so little current on the input side (typically no more than 15mA), a solid-state relay can usually be driven directly by chips such as *microcontrollers* that would not be able to activate an equivalent electromagnetic relay.

Applications may take advantage of the solid-state relay's reliability, immunity to vibration, lack of contact sparking, freedom from coil-induced surges on the input side, and lack of contact bounce on the output side. A solid-state relay is ideal within digital equipment that is sensitive to power spikes. It may switch a fuel pump that handles volatile, flammable liquids, or a wastewater pump in a basement subject to flooding (where long-term zero-maintenance reliability is necessary, and contact corrosion could be a risk in electromagnetic relays). Small solid-state relays can switch motors in robots or appliances where vibration is common, and are often used in arcade games.

What Can Go Wrong

Overheating Caused by Overloading

Relays must be *derated* when used at operating temperatures above the typical 20 or 25º C for which their specification applies. In other words, the sustained operating current must be reduced, usually by an amount such as 20% to 30% for each 10-degree increase in ambient temperature. Failure to observe this rule may result in failure of the component. Burnout may also occur if a high-current solid-state relay is used without a heat sink, or the heat sink isn't big enough, or *thermal compound* is not applied between the solid-state relay and the heat sink.

Overheating Caused by Bad Terminal Contact

If the screw terminals on the output side of a high-current solid-state relay are not tightened sufficiently, or if there is a loose spade terminal, or if a crimped connection isn't crimped tightly enough, the poor contact will create electrical resistance, and at high currents, the resistance will create heat, which can cause the solid-state relay to overheat and burn out.

Overheating Caused by Changing Duty Cycle

If a high-current solid-state relay is chosen for an application where it is in its "on" state only half the time, but the application changes during product development so that the solid-state relay is in its "on" state almost all the time, it will have to dissippate almost twice as much heat. Any time the duty cycle is changed, heat should be considered. The possibility of the relay being used in an unconventional or unexpected manner should also be considered.

Overheating Caused by Component Crowding

Overheating increases dramatically when components are tightly crowded. At least 2cm (3/4") should be allowed between components.

Overheating in Dual Packaging

When a package contains two solid-state relays, the additive effects of the heat created by each of them must be considered.

Reverse-Voltage Burnout

Because a solid-state relay is more sensitive to *back-EMF* than an electromagnetic relay, greater care should be used to protect it from reverse voltage when switching inductive loads. A *protection diode* should be used, and a *snubber* can be added between its output terminals, if it is not included inside the relay package.

Low Voltage Output Current May Not Work

Unlike electromagnetic relays, solid-state relays require some voltage on the output side to enable their internal operation. If there is no voltage, or only a very low voltage, the SSR may not respond to an input. The minimum voltage required on the output side is usually specified in a datasheet.

To test a solid-state relay, apply actual voltages on input and output sides and use a load such as an incandescent light bulb. Merely applying a meter on the output side, set to measure continuity, may not provide sufficient voltage to enable the relay to function, creating the erroneous impression that it has failed.

Inability to Measure AC Output

When a multimeter is used to test continuity across the output of an AC-switching solid-state relay of zero-crossing specification, the meter will generate enough voltage to prevent the solid-state relay from finding zero voltage across its output terminals, and consequently the solid-state relay won't switch its output.

Relay Turns On but Won't Turn Off

When a solid-state relay controls a relatively high-impedance load such as a small **solenoid** (see Volume 1) or a **neon bulb** (see Chapter 19), the relay may switch the device on but will seem unable to switch it off. This is because the leakage current of the solid-state relay, in its "off" state, may be just enough to maintain the load in its "on" state.

If an SSR containing a triac is used erroneously to switch DC, it will not be able to switch off the current.

Relays in Parallel Won't Work

Two solid-state relays usually cannot be used in parallel to switch twice as much current. Because of small manufacturing variances, one relay will switch on a moment before the other. When the first relay is on, it will divert the load current away from the second relay. The second relay needs a small amount of current on its output side, to function. Without any current, it will not switch on. This means the first relay will pass the total current without any help from the second relay, and will probably burn out, while the second relay does nothing.

Output Device Doesn't Run at Full Power

A solid-state relay imposes a voltage reduction on its output side. This will be a fixed amount, not a percentage. When switching 110V, this difference may be negligible; when switching 12V, it may deliver only 10.5V, which represents enough of a drop to cause a motor or a pump to run noticeably more slowly. The internal switching device inside the relay (MOSFET, triac, SSR, or bipolar transistor) will largely determine the voltage drop. Check the manufacturer's datasheet before using the relay.

Solid-State Relays and Safety Disconnects

Because a solid-state relay always allows some leakage in its "off" state, it can still deliver a shock when used to switch high voltages. For this reason, it may not be suitable in a safety disconnect.

optocoupler

5

Sometimes known as an *optoelectronic coupler*, *opto-isolator*, *photocoupler*, or *optical isolator*.

A **solid-state relay** is sometimes referred to as an **optocoupler**, but in this encyclopedia it has a separate entry. An optocoupler is a relatively simple device consisting of a light source (usually an LED) and a light sensor, both embedded in one package. It is used primarily for isolation rather than to switch a high current. A solid-state relay can be thought of as a substitute for an electromagnetic **relay**, usually has additional components in its package, and is intended to switch currents of at least 1A.

OTHER RELATED COMPONENTS

- **electromagnetic relay** (see Volume 1)
- **solid-state relay** (see Chapter 4)

What It Does

An optocoupler allows one section of a circuit to be electrically isolated from another. It protects sensitive components, such as logic chips or a microcontroller, from voltage spikes or incompatible voltages in other sections of a circuit. Optocouplers are also used in medical devices where a patient has to be protected from any risk of electric shock, and are used in devices which conform with the MIDI standard for digital control of music components.

In Figure 5-1, three possible applications for an optocoupler are suggested:

Top

The output from a logic chip passes through an optocoupler to an inductive load such as a relay coil, which may create voltage spikes that would be hazardous to the chip.

Center

The noisy signal from an electromagnetic switch passes through an optocoupler to the input of a logic chip.

Bottom

The low-voltage output from a sensing device on a human patient passes through an optocoupler to some medical equipment, such as an EEG machine, where higher voltages are used.

Internally, an optocoupler works on the same principle as a **solid-state relay**. An LED is embedded on the input side, shining light through an interior channel or transparent window to a sensing component that is embedded on the output side. Because the only internal connection is a light beam, the input and output of the optocoupler are isolated from each other.



Figure 5-1. *Possible applications for a photocoupler. See text for details.*

Isolation transformers were traditionally used for this purpose prior to the 1970s, when optocouplers became competitive. In addition to being smaller and cheaper, an optocoupler can also pass slow-changing signals or on-off DC states which a transformer would ignore.

More recently, inductive and capacitive coupling components have become available in surface-mount packages that are competitive with optocouplers for high-speed data transfer. They also claim to be more durable. Because of the gradual reduction in output from an LED, the performance of an optocoupler degrades over time, and is typically rated for up to 10 years.

How It Works

The LED in an optocoupler almost always emits light in the near-infrared part of the spectrum, and is matched to the sensitivity of a **phototransistor**, or a **photodiode**, or (less often) a **photoresistor** that provides the output. Photosensitive **triacs** and **SCRs** are also sometimes used.

The most common type of optocoupler uses a bipolar phototransistor with an open-collector output. Schematic symbols for this type are shown in Figure 5-2:

Top left

The most common generic form.

Top right

Two diodes on the input side allow the use of alternating current.

Center left

An additional terminal allows addition of bias to the photosensitive base of the output transistor, to reduce its sensitivity.

Center right

An Enable signal can be used as the input to the NAND, suppressing or enabling the output.

Bottom left

A *photodarlington* allows higher emitter current.

Bottom right

Relatively uncommon, and is also used for a **solid-state relay**.

In each symbol, the diode is an LED, and the zigzag arrow indicates light that is emitted from it. A pair of straight arrows, or wavy arrows, may alternatively be used.

An optocoupler in through-hole DIP format is shown in Figure 5-3.

An *optical switch* can be thought of as a form of optocoupler, as it contains an LED opposite a sensor. However, the LED and the sensor are separated by an open slot, to allow a thin moving object to pass through, interrupting the light beam as a means of detecting the event. It is categorized as a *sensor* in this encyclopedia, and will be found in Volume 3.



Figure 5-2. *Six variants of schematic symbols that may be used to represent an optocoupler. See text for details.*



Figure 5-3. *An optocoupler in through-hole 8-pin DIP format.*

Variants

Internal Sensors

Historically, a photoresistor (often referred to as a *photocell*) was the first type of sensor to be used. It has a more linear response than other sensor types, but its response is much slower. It is still found in audio applications. "Stomp box" pedals used by guitarists typically contain an optocoupler that employs a photoresistor, and are valued for their linearity and their immunity from the mechanical wear, contamination, and "scratchiness" that builds up over time in a **potentiometer**. Optocouplers also eliminate *ground loops*, which tend to be induced by small differences in ground potential, introducing hum or buzz in audio applications when two or more power supplies are tied together.

The type of optocoupler that contains a photoresistor and is commonly used by musicians was initially trademarked as a *Vactrol*, and that term is still used generically. Vactrols have also been used to provide audio compression in telephone voice networks, and were used in photocopiers and photographic exposure meters, but these applications are now obsolete.

Photoresistors are becoming uncommon because of their cadmium content, which is unlawful in many countries (especially in Europe) because of its environmental toxicity.

A photodiode provides the fastest response time in an optocoupler, limited primarily by the characteristics of the LED that shines light upon it. A *PIN diode* can respond in less than a nanosecond; its acronym is derived from its fabrication from p-type and n-type semiconductor layers with an *intrinsic* layer connecting them. This additional layer can be responsive to light. When the diode is slightly reverse-biased, a photon entering the intrinsic layer can dislodge an electron, enabling current to flow. The reverse bias enlarges the active area and enhances the effect. In this mode, the PIN acts like a photoresistor, appearing to reduce its resistance in response to light.

When the PIN is used in *photovoltaic* mode, no bias is applied, and the component actually generates a small voltage (less than 1VDC), like a solar cell, in response to incoming light. Where an optocoupler uses a MOSFET on its output side, as many as 30 photodiodes may be connected in series to develop the necessary threshold voltage to trigger the transistor. This arrangement is common in **solid-state relays**.

A bipolar phototransistor is a slower-speed device but is still usually capable of a 5µs response time or better. Its open collector requires external voltage and a *pull-up resistor* to deliver a positive output so long as the phototransistor is nonconductive. When the LED turns on, the phototransistor sinks current, effectively creating a low output. In this way, the optocoupler functions like an *inverter*, although some variants include a noninverting output.

Basic Optocoupler Types

An optocoupler with *high linearity* will respond more proportionally to variations in current to its LED. *High Speed* optocouplers are used for high-frequency data transfer. *Logic-output* optocouplers have a clean high/low output transition, rather than an *analog output*, which varies with fluctuations in the input. Linearity is of importance only where an optocoupler is being used to transmit an analog signal with some fidelity. Some logic-output optocouplers provide the function of a Schmitt trigger on their output side.

While optocouplers are available in various package formats, the DIP style with six or eight pins remains popular, providing sufficient physical space for the LED, the sensor, and a light channel, while providing good electrical isolation.

Variants may have two or four optocouplers combined in one package. A *bidirectional* optocoupler may consist of two optocouplers in parallel, inverted with respect to each other.

Values

In a datasheet, the characteristics of primary importance in an optocoupler are:

- CTR is the Current Transfer Ratio, the ratio of maximum output current to input current, expressed as a percentage. With a bipolar phototransistor output, 20% is a typical minimum CTR. With a photodarlington output, the CTR may be 1,000% but the bandwidth is much lower—the response time may be measured in microseconds rather than nanoseconds. Optocouplers with a photodiode output have a very low CTR, and their output is in microamps. However, they provide the most linear response.
- $V_{CE(MAX)}$ is the maximum collector-emitter voltage difference (in an optocoupler with a bipolar phototransistor output). Values from 20 to 80 volts are common.
- V_{ISO} is the maximum potential difference, in VDC, between the two sides of the optocoupler.
- I_{MAX} is the maximum current the transistor can handle, generally in mA.
- Bandwidth is the maximum transmittable signal frequency, often in the range of 20kHz to 500kHz.

The LED in an optocoupler typically requires 5mA at a forward voltage of 1.5V to 1.6V.

The maximum collector current on the output side of an optocoupler is unlikely to be higher than 200mA. For higher output currents, a solid-state relay should be considered. It provides photo-isolation on the same basis as an optocoupler, but high-current versions tend to be considerably more expensive.

How to Use It

The primary purpose of an optocoupler is to provide protection against excessive voltage—from transients, incompatible power supplies, or equipment with unknown characteristics. If a device is designed to be plugged into a USB port on a computer, for instance, the computer may be isolated via an optocoupler.

A series resistor for the LED is not built into most optocouplers, because the value of the resistor will depend on the input voltage that is used. Care must be taken to determine what the maximum voltage on the input side will be, and a series resistor should be chosen to reduce current appropriately. Allowance should be made for some degradation in the performance of the LED over time.

For an optocoupler with an open-collector output, a pull-up resistor is necessary in most applications. The voltage from the optocoupler must be matched to the input requirements of other components, and the collector current must remain within the specified limits. Some trial and error in resistor selection may be necessary.

In Figure 5-4, a schematic shows typical component values in a test circuit using a pushbutton as input. The separation of the two power supplies is emphasized by the different color shades used for the positive and negative symbols. Although the input side and the output side of an optocoupler may be used with a common ground, this defeats its purpose in providing complete isolation between the sections of the circuit.

The pinouts for an optocoupler must be checked carefully in the manufacturer's datasheet. While the input for an 8-pin DIP chip is usually applied to pins 2 and 3, the output pin functions are not standardized and will vary depending on the internal configuration of the chip. An optocoupler such as the Optek D804, with an enable function using an internal NAND gate, requires its own power supply.

Where an optocoupler allows an external connection to the base of its internal bipolar output phototransistor, reverse bias applied to this pin will decrease the sensitivity of the optocoupler but can increase its immunity to noise on the input side.

What Can Go Wrong

Overload conditions on the input or the output side of an optocoupler will be the most likely cause of failure.

Age

Because optocouplers are typically rated for only 10 years of average use, the age of a component may cause it to fail.



Figure 5-4. *Typical values for a series resistor (to protect the LED) and pull-up resistor (to control current and voltage on the output side) in an optocoupler test circuit.*

LED Burnout

Because the LED is hidden inside the component, there is no immediate indication of its performance. A meter can be inserted into the circuit on the input side to determine if current is passing through the LED. A meter set to measure volts can be used to discover whether the LED is imposing a normal voltage drop. While significant overload will cause immediate burnout, slightly exceeding the current rating of the LED may have more pernicious consequences, as the LED may not fail until days or weeks have passed without any sign of trouble. The failure of the optocoupler will be unexpected and difficult to determine.

Transistor Burnout

Here again the damage caused by excessive current may be progressive, occurring over a prolonged period. The easiest way to test an optocoupler that may have failed is by removing it from the circuit. A socketed DIP package is preferable for this purpose.

comparator

6

Although a **comparator** has the same schematic symbol as an **op-amp**, their applications differ and they are described in separate sections of this encyclopedia.

This entry describes an analog comparator. A *digital comparator* is very different, being a logic chip that compares two binary numbers that can be referred to as A and B. Outputs from the chip indicate whether A>B or A<B or A=B. The digital comparator does not have an entry in this encyclopedia.

OTHER RELATED COMPONENTS

- **op-amp** (see Chapter 7)

What It Does

A **comparator** is an integrated circuit chip that compares a variable voltage on one input pin with a fixed, reference voltage on a second input pin. Depending which voltage is higher, the output from the comparator will be high or low.

The output will make a clean transition between two fixed values, even if the input is infinitely variable. Thus the comparator can function as an *analog-digital converter*, as shown in Figure 6-1.

Because the output voltage range can be adjusted up or down independently of the input range, a comparator can also function as a *voltage converter*.

Hysteresis

If positive feedback is added through external resistors, *hysteresis* can be introduced. We may imagine a *hysteresis zone* extending above and below the reference voltage level. Small input variations that occur within the zone will be ignored. The comparator only reacts when the input signal emerges above or below the hysteresis zone. When the input signal returns into the hysteresis zone, this event also will be ignored. The concept is illustrated graphically in Figure 6-2. A circuit to create hysteresis is shown in Figure 6-10.

How It Works

The schematic symbol for a comparator is shown in Figure 6-3. This seems identical to the symbol for an op-amp, described in Chapter 7, but an op-amp is traditionally a *dual-voltage* device using positive and negative power sources that are equal and opposite, in addition to a zero value midway between the two. Modern comparators mostly use a conventional single voltage, and therefore the negative symbol used in comparator schematics throughout this section of the encyclopedia represents 0 volts. It has the same meaning as the ground symbol found in many schematics elsewhere.

The two inputs to a comparator are described as *inverting* and *noninverting* (for reasons explained later). Confusingly, these are identified with plus and minus symbols inside the triangle that represents the component. These plain black-and-white symbols have nothing to do with the power supply.



Figure 6-1. *The basic behavior of a simple comparator is shown here.*

Often, in schematics, the power supply is not shown, because it is assumed to be present. However, all comparators require a power supply in order to function.

The basic internal and external connections used in conjunction with a typical comparator are shown in Figure 6-4.

The potentiometer at top left is often a *trimmer*, to fine-tune a reference voltage. The variable input can come from a sensor or any other device capable of delivering a voltage up to the limit set by V1.

The output is often an *open collector* from an internal bipolar transistor, as shown in the figure.

Note that as many as three different voltages can be used, as indicated by the different colors associated with V1, V2, and V3. However, they must share a common ground to enable the comparator to make valid comparisons.

When the noninverting input exceeds the voltage of the inverting input, the output transistor goes into its "off" state, and blocks current from an external *pullup resistor*. Because the current from the resistor now has nowhere else to go, it is available to drive other devices attached to the comparator output, and the output appears to be high.



Figure 6-2. *The performance of a comparator shown in the previous figure can be modified by the addition of hysteresis. Small variations that occur within the hysteresis zone are ignored.*

When the noninverting input falls below the voltage of the inverting input, the transistor becomes conductive, and sinks almost all the current from the pullup resistor, assuming other devices attached to the output have a relatively high impedance. The output from the comparator now appears to be low.

This can be summed up as follows:

- When a variable voltage is applied to the noninverting input, and it rises *above* the reference voltage applied to the *inverting input*, the output transistor turns off, and the comparator delivers a *high* output.
- When a variable voltage is applied to the noninverting input, and it falls *below* the reference voltage applied to the *inverting input*, the output transistor turns on, and the comparator delivers a *low* output.


Inverting Input
(positive voltage, may be higher or lower than V+)
Noninverting Input
(positive voltage, may be higher or lower than V+)
V+ (positive DC power supply)
Output
0V (negative ground)
−
+

Figure 6-3. *The symbol for a comparator is the same as the symbol for an op-amp, even though they often require different types of power supply and their functions are significantly different.*


V1
0V
V2
V3
Reference Voltage
Power
Pullup
Other Components
V1
Variable Input
Output Device
0V
0V
0V
−
+

Figure 6-4. *Connections to a comparator, and their functions.*

If the reference voltage and the variable voltage are swapped between the input pins, the behavior of the comparator is reversed. This relationship is illustrated in Figure 6-5. When a voltage transition is applied to the *inverting* input, the transition is *inverted* at the output.


Reference
Variable Input Low-to-High
Output Low-to-High
Variable Input Low-to-High
Reference
Output High-to-Low
−
+

Figure 6-5. *Depending which input pin is used for the reference voltage, and which input carries a variable voltage, the comparator output either follows the variable voltage or inverts it.*

Placement of the plus and minus signs inside the comparator symbol may vary. Most often, the minus sign is above the plus sign, as shown in all the schematics here. Sometimes, however, for convenience in drawing a schematic, the plus sign may be shown above the minus sign. Regardless of their placement, the plus sign always identifies the noninverting input, and the minus sign always identifies the inverting input. To avoid misinterpretations, schematics should be inspected carefully.

Where a power supply for the comparator is shown, the positive side is always attached to the upper edge of the symbol, while 0V ground is always attached to the lower edge.

Differences from an Op-Amp

Saturation versus linearity

The output of a comparator is optimized for saturation (high or low, without intermediate levels, using positive feedback). The output of an op-amp is optimized for linearity (faithful reproduction of nuances in the input, using negative feedback).

Output mode

The majority of comparators have open-collector outputs (or open-drain outputs in CMOS devices) where the voltage is established by a pullup resistor. This can be adjusted for compatibility with other components, especially 5VDC logic. Only a minority have push-pull amplifier outputs that require no pullup resistor. By comparison, among op-amps, a push-pull output that functions as a voltage source is the traditional default.

Faster response

A comparator responds more quickly than an op-amp to changes in input voltage, if the op-amp is used in the role of a comparator. The comparator is primarily a switching device, not an amplifier.

Hysteresis

This is generally desirable in a comparator, for reasons already explained, and some components are designed with hysteresis built in. This feature is undesirable in an op-amp, as it degrades sensitivity.

Open-loop operation

(i.e., without feedback) this can be used with a comparator. An op-amp is intended for use in closed-loop circuits (i.e., with feedback), and manufacturers will not specify its performance in an open loop.

As previously noted, a comparator usually requires a single-voltage power supply, while an op-amp often requires a dual-voltage power supply.

Variants

Where a comparator uses a MOSFET output transistor, it may have an open-drain output, which requires a pullup resistor, as with an open-collector output.

Some comparators have a *push-pull* output, capable of supplying output current (usually a small amount). In these instances, no pullup resistor is necessary or desirable. The output voltage range will be closest to *rail-to-rail* values (i.e., the range of the power supply) where MOSFETs are used for the output, as MOSFETs impose a smaller voltage drop than bipolar transistors.

The advantage of an open collector (or open drain) relative to a push-pull output is that it allows the output voltage to be set independently of the power supply voltage. Another advantage is that multiple outputs can be connected in parallel, as in a *window comparator* circuit (described below).

Some comparators incorporate a reference voltage on the chip, based on the power supply to the chip. In this case, a separate reference voltage does not have to be supplied, and the component will draw less current.

Many chips are available containing two or more comparators. This is often expressed as the number of *channels* in the component. A *dual comparator* typically allows two different voltage sources for the outputs of the comparators. They will share the same 0V ground, however. Chips such as the LM139 and LM339 contain four comparators, and are available in through-hole or surface-mount formats. They have become a generic choice, costing less than $1 apiece.

An LM339 comparator chip is shown in Figure 6-6. This is a quad chip, meaning that it contains four comparators. They share a common power supply. The chip is TTL and CMOS compatible, is typically powered by 5VDC, but can be driven by up to 36VDC. The input differential voltage range also extends up to 36V.



Figure 6-6. *The LM339 quad comparator chip, shown here, was introduced long ago but remains widely used.*

Some comparators have an internal *latch* function that is accessed by a dedicated pin. The latch-enable signal forces the comparator to assess its inputs and hold an appropriate output which can then be checked by other components.

Values

In a datasheet, V_{IO} (also referred to as V_{OS}) is the *input offset voltage*. This is a small voltage, in addition to the reference voltage, which the comparator will require to *toggle* its output in either direction, up or down. Figure 6-7 shows this graphically. V_{IO} sets the limit of *resolution* of the comparator, which will not respond unless the input voltage exceeds the reference voltage by this amount. A smaller value for V_{IO} is better than a larger value. Common values for V_{IO} range from 1mV to 15mV. The actual offset voltage tends to vary between one sample of a component and another. V_{IO} is the maximum allowed value for a component.

Because the comparator will not respond until the reference voltage is exceeded by V_{IO}, the output pulse width will be narrower than if the comparator reacted at the point where the variable voltage input was precisely the same as the reference voltage.



Figure 6-7. *The input offset voltage is the very small voltage that a comparator requires, additional to the reference input voltage, before it will toggle its output from low to high or high to low.*

V_{TRIP+} and V_{TRIP-} are the *rising* and *falling voltages*, respectively, that will trip the comparator output where the comparator exhibits some innate hysteresis without an external feedback loop. They are also referred to as *Lower State Transition Voltage* (LSTV) and *Upper State Transition Voltage* (USTV).

V_{HYST} is the *hysteresis range* defined as V_{TRIP+} minus V_{TRIP-}. The relationship is shown graphically in Figure 6-8.

A_{VD} is the *voltage gain* of a comparator, in which the letter "A" can be thought of as meaning "amplification." The gain is measured as a maximum ratio of output voltage to input voltage. Typically it ranges from 40 to 200.

Supply voltage for modern comparators is often low, as the components are used in surface-mount format for battery-powered devices where low power consumption is a primary concern. Thus, 3VDC is common as a power requirement, and 1.5VDC comparators are available. Still, older chips can use as much as 35VDC.



Figure 6-8. *The value of V_{TRIP} shows the hysteresis in a comparator—the range of input voltages, relative to the reference voltage, in which it will not respond.*

Supply current can range from 7mA down to below 1µA.

I_{SINK} is the recommended typical or maximum *sink current* that the component will tolerate, if it has an open-collector output. This value should be considered in relation to the power dissipation, P_D.

The *propagation delay* in a comparator is measured from the moment when an input (usually a square wave) reaches the triggering value, to the time when the consequent output reaches 50% of its final value.

When a comparator is driving CMOS logic using a 5VDC power supply, a typical value for a pullup resistor is 100K. It does not have to be lower, because CMOS has such a high input impedance.

How to Use It

In Figure 6-1, a hypothetical comparator responds immediately when the input voltage equals the reference voltage value. However, this is an idealized scenario. A magnified view, in Figure 6-9, suggests that the comparator is likely to respond with *jitter* when the input signal is very close to the reference voltage, because of tiny variations in heat, current, and other variables. This jitter will cause significant problems if the comparator is driving a device such as a relay, directly or indirectly.

Hysteresis eliminates this uncertainty around the transition level of the input, by telling the comparator to ignore small irregularities in the input voltage. Hysteresis is also useful in many situations where larger variations in a sensor input should be ignored. In Figure 6-2, for instance, suppose that the input voltage comes from a temperature sensor. The small bump in the right-hand section of the curve is probably unimportant; it could be caused by someone opening a door, or a person's body heat in brief proximity to the sensor. There's no point in responding to every little event of this type. In this application, the larger, longer-term temperature trend is what matters, and significant hysteresis is appropriate.

Also, if a comparator is being used as a thermostat, to switch a heating system on and off, we do not want the comparator to respond as soon as the temperature rises just a small amount. The heating system should run for a while before it elevates the temperature beyond the hysteresis zone.

The usual way to create hysteresis is with *positive feedback*. In Figure 6-10, a connection from the output of the comparator runs back through a 1M potentiometer to the variable (noninverting) input. The effect that this has is to reinforce the input voltage with the output voltage, as soon as the comparator input goes high. Now the input can diminish slightly without switching off the comparator. But if the input declines significantly, even the feedback from the output voltage won't be sufficient to maintain the variable input at a higher level than the reference voltage. (Remember, the "high" output voltage from the comparator is a fixed value; it does not change in proportion with the input voltage.) Consequently, the output toggles to low. Now the variable input is deprived of help from the comparator output, so it will be low enough that it has to rise considerably to toggle the comparator back on again. During that period, once again, small variations will be ignored.



Figure 6-9. *In real-world applications, tiny variations where the variable input voltage crosses the reference voltage can induce jitter in the output from a comparator that has no hysteresis.*

In the schematic, a **phototransistor** (PT1, at left) is in series with a 3.3K resistor to adjust its voltage output to a suitable range. A 1M potentiometer at upper-left is wired as a voltage divider, so that it can establish a reference level that matches the light level that we wish to detect with the phototransistor.



Figure 6-10. *A simple circuit to achieve hysteresis with positive feedback to the variable input of a comparator.*

The 470Ω resistor is the pullup resistor, which protects the LED from excessive current. The lower 1M resistor adjusts the amount of positive feedback, which determines the width of the hysteresis zone.

Values for components may have to be adjusted depending on the supply voltage, the variable input voltage, and other factors. But the principle will remain the same. Note that in the example shown, all the positive voltage sources are identical. In practice, different voltages could be used, so long as they share a common ground.

AND gate

A set of open-collector comparators can function jointly as an AND gate, when their outputs are tied together with one pullup resistor. So long as all the output transistors are nonconductive, the output will be high. If just one comparator toggles into conductive mode, the output will be low. See Figure 6-11.



Figure 6-11. *If the outputs of multiple open-collector comparators are tied together with a suitable pullup resistor, they will function as an AND gate.*

Bistable Multivibrator

If positive feedback to the noninverting input of the comparator is sufficiently high, a voltage almost at 0V ground will be required to counter the high output from the comparator—after which, a voltage almost equal to the supply voltage will be needed to turn it back on. In other words, the comparator is behaving like a *bistable multivibrator*, or **flip-flop**.

Relaxation Oscillator

A *relaxation oscillator*, which is a form of *astable multivibrator,* can be created using direct positive feedback in combination with delayed negative feedback. In Figure 6-12, positive feedback goes to the noninverting input, as before, but negative feedback also passes through a 220K resistor to the inverting input of the comparator. A 0.47μF capacitor initially holds the inverting input low, while the capacitor charges. Gradually the capacitor reaches and exceeds the charge on the noninverting input, so the output from the comparator toggles to its low state. This means that its internal transistor is now sinking current, and it discharges the capacitor. Because the noninverting input is being held at a voltage midway between supply and ground by the two 100K resistors forming a voltage divider, eventually the voltage on the inverting input controlled by the capacitor falls below the noninverting voltage, so the cycle begins again.



Figure 6-12. *A comparator can be used to create a relaxation oscillator.*

Level Shifter

Where a comparator is used simply to change the level of an input voltage, it can be referred to as a *level shifter*. An example of a level shifter is shown in Figure 6-13, in which a high/low 3VDC logic input is converted to a high/low logic output at 5VDC.

Window Comparator

A *window comparator* is a circuit (not a single component) that will respond to input voltages that deviate outside an acceptable "window" of values. In other words, the circuit responds anytime the variable input is either unacceptably low or unacceptably high.

An example could be an alarm that will sound if a temperature is either too low or too high. In Figure 6-14, two comparators are used to create a window comparator circuit, both sharing a variable voltage input from a sensor. A voltage divider is necessary to establish a higher voltage limit at the noninverting input of the upper comparator, while a separate voltage divider would establish a lower limit at the inverting input of the lower comparator. If an alarm has an appropriate resistance, it can be used instead of a pull-up resistor. The alarm will sound when the output from either comparator is low, which happens if the inverting input has a higher voltage than the non-inverting input.



Figure 6-13. *A comparator can be used to convert high and low 3V logic inputs into high and low 5V logic outputs.*

Other Applications

As previously noted, a comparator can be used as a simple *analog-digital converter*. It has "one bit" accuracy (i.e., its output is either high or low).

A comparator can be used as a *zero point finder* when its variable voltage input is attached to an AC signal. The output from the comparator will be toggled whenever the AC signal passes through zero volts. The output will be a square wave (approximately) instead of a sine wave.



Figure 6-14. *A basic, simplified circuit for a window comparator. See text for details.*

A *continuous converter* changes its output promptly in response to a change in input. This requires continuous current consumption. Because many applications only need to check the output from a comparator at intervals, power can be saved by using a *clocked* or *latched* comparator.

What Can Go Wrong

Oscillating Output

The high input impedance of a comparator is vulnerable to stray electromagnetic fields. If the conductors leading to and from the comparator are relatively long, the output can couple capacitively with the input during voltage transitions, causing unwanted oscillations.

The commonly recommended solution to this problem is to add 1µF bypass capacitors to the power supply on either side of the comparator. However, some manufacturers recommend alternatives such as introducing just a small amount of hysteresis, or reducing the value of input resistors to below 10K.

If a chip contains multiple comparators, and one of them is unused, one of its input pins should be tied to the positive side of the voltage supply while the other should be tied to 0V ground, to eliminate the possibility of an oscillating output.

Confused Inputs

A comparator will function if its two inputs are swapped accidentally, but its high and low output states will be the inverse of what is expected. Also, if positive feedback is used, transposed inputs can create oscillations. Because the comparator symbol may appear in a schematic with the noninverting input either below or above the inverting input, the inputs are easily transposed by accident.

One way to remember which way the inputs should be connected is to use the mnemonic: "plus, high, positive." The *plus* input creates a *high* output when the input becomes *more positive* than the reference voltage on the other input. The opposite is less intuitively obvious: the *minus* input creates a *high* output when the input becomes *more negative* than the reference voltage on the other input.

Wrong Chip Type

Different comparators offer different outputs: open collector, open drain, and push-pull. While open collector and open drain function similarly, the pullup resistor value is likely to be different in each case. If a push-pull output is mistakenly connected as if it is open collector or open drain, it will not work correctly, if at all. Different types of comparators must be sorted and stored in clearly labeled bins.

Omitted Pullup Resistor

It is relatively easy to forget to include the pullup resistor on an open-collector output. In this case, when the transistor inside the comparator is in its nonconductive state, the output pin will be floating, with an indeterminate voltage that will create confusing or random results.

CMOS Issues

As usual when using CMOS chips, it is bad practice to allow unconnected, floating inputs. This is an issue where a chip contains multiple comparators, some of which are not being used. The solution recommended by some manufacturers is to tie one input of an unused comparator to the supply voltage, and the other input of the same comparator to ground.

Erratic Output

If positive feedback is insufficient, the comparator output may show signs of *jitter*. Conversely, if the positive feedback is excessive, the comparator may get stuck in an on state or an off state. Feedback must be chosen carefully.

Swapped Voltages

A comparator is often capable of controlling an output voltage that is much higher than that of its power supply. Because both voltages are applied to different pins on the same chip, mistakes can be made quite easily. The chip is likely to be damaged if the voltages are swapped accidentally between the relevant pins.

Heat-Dependent Hysteresis

Remember that the voltages at which the comparator turns on and off will vary slightly with the temperature of the component. This *drift* should be tested by running the comparator at higher temperatures.

op-amp

7

Although a comparator has the same schematic symbol as an **op-amp**, their applications differ and they are described in separate sections of this encyclopedia.

The unabbreviated name for an op-amp is an *operational amplifier*, but this term is seldom used.

OTHER RELATED COMPONENTS

- **comparator** (see Chapter 6)

What It Does

An op-amp is an *operational amplifier* consisting of multiple transistors packaged in an integrated circuit chip. It senses the fluctuating voltage difference between two inputs, uses power from an external supply to amplify that difference, and uses *negative feedback* to ensure that the output is an accurate replica of the input. Its amplification can be adjusted by changing the values of two external resistors.

Op-amps were developed originally using vacuum tubes, for use in analog computers, before the era of digital computing. Their implementation in integrated circuits dates from the late 1960s, when chips such as the LM741 were introduced (lower-noise versions of it still being widely used today). Multiple op-amps in a single package were introduced in the 1970s.

An LM741 is shown in Figure 7-1. Inside the 8-pin, DIP package is a single op-amp.

How It Works

In alternating current, voltages deviate above and below a zero value, which is sometimes referred to as the *neutral* value. This occurs in domestic power supplies and in audio signals, to name two very common examples. A *voltage amplifier* multiplies the positive and negative voltage excursions, using an external power source to achieve this. Most op-amps are voltage amplifiers.



Figure 7-1. *The LM741, shown here, is still one of the most widely used op-amps.*

An ideal amplifier maintains a *linear relationship* between its input and its output, meaning that the output voltage values are a constant multiple of the input voltages over a wide range. This is illustrated in Figure 7-2, where the lower curve is a duplicate of the upper curve, the only difference being that its amplitude is multiplied by a fixed amount (usually much greater than shown here). The ratio is properly known as the *gain* of the amplifier, usually represented with letter A (for amplification).



Figure 7-2. *In an ideal voltage amplifier, the output voltage will be a duplicate of the fluctuating input voltage, the only difference being that the amplitude of the output is multiplied by a fixed amount. This ratio is known as the gain of the amplifier.*

Figure 7-3 shows the triangular symbol for a generic single-input amplifier (not an op-amp). It may contain any number of components. The triangle almost always points from left to right, with its input on the left and its output on the right, and power attached above and below. This is often a *dual voltage* power supply, which is convenient for amplifying a signal that fluctuates above and below 0V. In some schematics, the power supply connections may not be shown, as they are assumed to exist.



Figure 7-3. *The generic symbol for a single-input amplifier (not an op-amp), with the positive side of its power supply being equal and opposite in value to the negative side, and 0V being at the midpoint between them.*

- While the blue negative symbol is generally used throughout this encyclopedia to indicate 0V ground, it represents a voltage identified as V– in a dual voltage power supply, being equal in value but opposite in polarity to the positive side of the supply, V+. (Sometimes these voltages are indicated as V– and V+.)

The output from this imaginary generic amplifier is shown in the figure as a linear amplification of the input.

Dual Inputs

An op-amp has two inputs instead of one, and amplifies the voltage difference between them. Its symbol is shown in Figure 7-4. The upper input in this figure is held at 0V, midway between V+ and V–. Because the op-amp has so much gain, an accurate reproduction of its input would create an output exceeding the voltage of the power supply. Because this is not possible, the output tends to become saturated and consequently is *clipped* when it reaches its maximum value, as shown in the figure. The thumbnail graphs give only an approximate impression, as they are not drawn to the same scale.



Figure 7-4. *An op-amp has so much gain, its output will tend to saturate, producing a square wave regardless of the shape of the input.*

The small black plus and minus signs alongside the two inputs to the op-amp have nothing to do with the voltage supplied to the component. The "minus" input is properly referred to as the *inverting input* while the "plus" input is the *noninverting input*, in recognition of their functions.

The inputs are sometimes arranged with the minus above the plus, and sometimes with the plus above the minus. Schematics should be inspected carefully to note which arrangement is being used.

The positive and negative power connections to the op-amp may be omitted, but if shown, they always place V+ at the top, regardless of which way around the inputs are presented.

If a signal is applied to the noninverting input, while the inverting input is held at 0V ground, the op-amp provides an output in which the voltage is not inverted relative to the input.

If the input connections are swapped, so that the inverting input receives the incoming signal while the noninverting input is tied to 0V ground, the output from the op-amp is inverted (the gain remains the same). See Figure 7-5.



Figure 7-5. *When the incoming signal is applied to the inverting input of an op-amp while its noninverting input is held at 0V ground, the output is inverted.*

- An op-amp that is being used without any other components to moderate its output is functioning in *open loop* mode.

Negative Feedback

To create an output that is an accurate replica of the input, the op-amp must be brought under control with *negative feedback* to the input signal. This is illustrated in Figure 7-6. A resistor connects the output back to the inverting input, so that the input is automatically reduced to the point where the output is no longer saturated. The values of R1 and R2 will determine the gain of the op-amp, as explained in "How to Use It" on page 53. The op-amp is now functioning in its intended *closed loop* mode, meaning that the output is being tapped for feedback.

To obtain a linear output that is noninverted, connections are made as shown in Figure 7-7. The resistors form a voltage divider between the output and 0V ground, effectively increasing the comparison value on the inverting input.



Figure 7-6. *A resistor applies negative feedback to the inverting input of an op-amp, and creates a linear output.*


R1
Feedback resistor R2
0V neutral ground
Noninverted linear output
V+
–
+
V-
Signal applied to noninverting input

Figure 7-7. *Where the incoming signal is applied to the noninverting input, negative feedback is created by using a pair of resistors forming a voltage divider between the output and 0V ground.*

- Note that the gain of an op-amp is specific to a particular frequency range of AC signal. This is discussed in "How to Use It" on page 53.

Op-Amps and Comparators

A **comparator** can be regarded as a type of op-amp, and in fact an op-amp can be used as a comparator, comparing a variable DC voltage on one input with a reference voltage on another input. However, the two types of components have diverged in design to the point where they should be considered separately. The distinction is sufficiently important to have prompted Texas Instruments to issue an Application Report in 2001 titled "Op Amp and Comparators—Don't Confuse Them!".

Differences in function are summarized in the previous entry discussing comparators (see "Differences from an Op-Amp" on page 42).

Variants

Because op-amps are mostly low-current devices, they are widely available in very small surface-mount formats, in addition to the through-hole DIP packages which used to be more common.

Many chips are available containing two or more op-amps. This is often expressed as the number of *channels* in the component. A dual chip contains two op-amps, while a quad chip contains four op-amps. Usually all the op-amps in a chip share the same power supply. Bipolar or CMOS transistors may be used.

Because op-amps are widely available in dual and quad packages, it's quite common for a circuit designer to have one op-amp in a chip "left over." The designer may be tempted to use that spare unit as a comparator instead of installing an additional chip. To address this situation, some manufacturers offer hybrid op-amp chips containing an additional comparator. The Texas Instruments TLV2303 and TLV2304 are examples.

Values

The op-amps derived from 1970s designs often tolerate a wide range of power-supply voltages. Plus-or-minus 5VDC to plus-or-minus 15VDC is a common range. Modern op-amps are available that run from as little as 1VDC to as much as 1,000VDC.

Op-amps are available for frequencies ranging from 5KHz all the way up to 1GHz.

A "classic" op-amp such as the LM741, which is still widely used, will operate with a power supply ranging from plus-or-minus 5VDC to plus-or-minus 22VDC. Its output is rated for up to 25mA, and its input impedance is at least 2MΩ. The most current it will draw from an input is around 0.5μA.

V_{IO} is the *input offset voltage*. In an ideal component, the output from an op-amp should be 0V when its inputs have a voltage difference of 0V. In practice, the output will be 0V when the inputs differ by the offset voltage. V_{IO} is likely to be no greater than a couple of mV, and negative feedback can compensate for the offset.

V_{ICR} is the *common mode voltage range*. This is the range of input voltages that the op-amp will tolerate. This can never be more than the positive power supply voltage and will often be less, depending on the types of transistors that are used on the input side. If an input voltage goes outside the common mode voltage range, the op-amp will stop functioning.

V_{IDR} is the *input differential voltage range*—the maximum permissible difference between peak positive and peak negative input voltages. This is often expressed as plus-or-minus the power supply voltage, or slightly less. Exceeding the range can have destructive consequences.

I_B is the *input bias current*, averaged over the two inputs. Most op-amps have extremely high input impedance and consequently use very low input currents.

Slew rate at unity gain is the rate of change of the output voltage caused by an instantaneous change on the input side, when the output of the op-amp is connected directly back to the inverting input (during operation in noninverting mode).

How to Use It

In addition to being an amplifier for AC signals, an op-amp can serve as an oscillator, filter, signal conditioner, actuator driver, current source, and voltage source. Many applications require some understanding of the complexities of mathematics describing alternating current, which are not included this encyclopedia. Almost all the applications have a common starting point, however, which is to establish and control the gain of the feedback circuit.

Controlling the Gain

"A_{VOL} is the *open-loop voltage gain*, defined as the maximum voltage amplification that can be achieved when no feedback is applied from the output to an input. This remains constant until the AC frequency rises to a point known as the *breakover frequency*. If the frequency continues to rise, the maximum gain diminishes quite rapidly, until finally it terminates in 1:1 amplification at the *unity gain frequency*. This transition is shown by the orange line in Figure 7-8. The length of each purple line shows the frequencies which can be tolerated when the op-amp is used in closed-loop mode, and a negative feedback loop limits the gain. For example, where the gain is just 10:1, it can remain constant to just above 10KHz.

Note that both of the scales in this graph are logarithmic.

Calculating Amplification

So long as an op-amp is used within the boundaries of the graph, its voltage amplification can be controlled by choosing appropriate feedback and input resistors. If the op-amp is being used in noninverting mode, and R1 and R2 are placed as shown in Figure 7-7, the amplification ratio, A, is found approximately by the formula:

```
A = (approximately) 1 + (R2 / R1)
```

From this it can be seen that when R1 is very large compared with R2, the gain diminishes to near unity. If R1 becomes infinite and R2 is zero, the gain is exactly 1:1. This can be achieved by replacing R2 with a section of wire (theoretically of zero resistance) and omitting R1 entirely, as in Figure 7-9. In this configuration, the output from the op-amp should be identical with its input.



Figure 7-8. *Where each horizontal purple line meets the diagonal orange line, this is the maximum frequency that can be used without reduction in the maximum gain of an op-amp.*



Figure 7-9. *While an op-amp is in noninverting mode, if the feedback resistor is replaced with a section of wire and the 0V ground connection is omitted entirely, the gain of the op-amp diminishes theoretically to 1:1.*

If the op-amp is being used in inverting mode, and R1 and R2 are placed as shown in Figure 7-6, then the voltage amplification ratio, A, is found approximately by the formula:

```
A = (approximately) −(R2 / R1)
```

- Note the minus sign. In inverting mode, gain is expressed as a negative number.
- In a practical circuit, at the expected frequency, the amplification factor established by choice of resistors should be no more than 20.
- An inverting circuit has a relatively low input impedance. For this reason, in most applications, a noninverting circuit is preferred.

Unintentional DC Voltage Amplification

Although the op-amp is intended primarily as an AC signal voltage amplifier, it will also amplify a DC difference between the voltages on its inputs. In the upper section of Figure 7-10, a positive DC offset is inverted and amplified to the point where the output is forced to its negative limit, and the signal is lost, because its fluctuations have been overwhelmed by the positive offset. A coupling capacitor (shown in the lower section of the figure) removes the DC voltage while passing the AC signal. The appropriate capacitor value will depend on the frequency of the signal.

Low-Pass Filter

An op-amp can facilitate a very simple low-pass audio filter, just by adding a capacitor to the basic inverting circuit previously shown in Figure 7-6. The filter schematic is shown in Figure 7-11. Capacitor C1 is chosen with a value that passes higher audio frequencies and blocks lower audio frequencies. Because the gain of the basic inverting circuit is approximately −(R2 / R1), the op-amp functions normally when the impedance of C1 is blocking the low frequencies, forcing them to pass through R2. Higher frequencies, however, are able to bypass R2 through C1, lowering the effective resistance of the feedback section of the circuit, thus reducing its gain. This way, the power of the op-amp is greatly reduced for higher frequencies compared with lower frequencies. A passive RC circuit could achieve the same effect, but would attenuate the signal, while the op-amp circuit boosts part of it.



Figure 7-10. *The addition of a capacitor at the input of an op-amp is often necessary to prevent any DC voltage offset being amplified. In the upper section of this figure, a DC offset is large enough to force the inverted output to its negative limit, and the signal is completely lost.*



Figure 7-11. *A very basic low-pass filter, which works by allowing capacitor C1 to bypass resistor R2 at higher audio frequencies.*

High-Pass Filter

A simple high-pass filter can be created by adding a capacitor to the basic noninverting circuit previously shown in Figure 7-7. The filter schematic is shown in Figure 7-12. Once again capacitor C1 is chosen with a value that passes higher audio frequencies and blocks lower audio frequencies. Because the gain of the basic noninverting circuit is approximately 1 + (R2 / R1), the op-amp functions normally when the impedance of C1 is blocking the low frequencies, forcing them to pass through R1. Higher frequencies, however, are able to bypass R1 through C1, lowering the effective resistance of that section of the circuit, thus reducing the negative feedback and increasing the gain. This way, the power of the op-amp is increased for higher frequencies compared with lower frequencies. A passive RC circuit could achieve the same effect, but would attenuate the signal, while the op-amp circuit boosts part of it.



Figure 7-12. *A very basic high-pass filter, which works by allowing capacitor C1 to bypass resistor R1 at higher audio frequencies.*

Relaxation Oscillator

The schematic in Figure 7-13 is similar to the circuit shown in Figure 6-12 using a comparator. It functions as a *relaxation oscillator*, which is a form of *astable multivibrator*. The lower half of the circuit is a positive feedback loop that reinforces the output while the upper half of the circuit is charging the capacitor. Eventually the charge on the capacitor exceeds the voltage on the noninverting input of the op-amp, creating negative feedback that exceeds the positive feedback. The capacitor discharges and the cycle repeats. The component values in the figure should generate an output that runs at around 2Hz. Reducing the value of the capacitor will increase the frequency.

Single Power Source

A few op-amps are designed to work from single voltages, but they are a relatively small minority, and will clip the output signal if the input goes negative. Power supplies are readily available that provide multiple voltages such as +15VDC, 0V, and -15VDC. They are ideal for driving an op-amp—but may not be useful for any other components in the circuit. Can an op-amp that is designed for dual voltages be made to run from a single supply, such as 30VDC?



Figure 7-13. *A relaxation oscillator.*

This is relatively easy to do. The op-amp simply needs a potential difference to power its internal transistors, and 30VDC on the V+ pin with 0VDC on the V– pin will work just as well as +15VDC and -15VDC. However, referring back to Figure 7-6, if the op-amp is used in inverting mode, an intermediate voltage must be supplied to the noninverting input. Likewise, in noninverting mode, an intermediate voltage is necessary for one of the inputs, and must be half-way between the extremes of the power supply. If the supply is +15VDC and -15VDC, the midpoint is 0V. If the supply is 30VDC and 0V, the midpoint is 15VDC.

Because the inputs of an op-amp have a very high impedance and draw negligible current, the intermediate voltage can be provided with a simple voltage divider, as shown in Figure 7-14, where R3 and R4 should be no greater than 100K each. Their exact values are not important, so long as they are equal.



Figure 7-14. *A voltage divider, comprised of R3 and R4 in this schematic, can provide a voltage halfway between V+ and negative ground, enabling the op-amp to use just one power supply instead of two.*

A coupling capacitor should still be used on the input side, as shown, because there is no guarantee that the input signal will be centered precisely on 15V, and any offset will be amplified, potentially causing clipping of the signal. For similar reasons, a coupling capacitor is also added on the output side.

Offset Null Adjustment

Some op-amps provide two pins for *offset null adjustment*, which is a setup process to ensure that identical voltage on the two inputs will produce a null output. This is a way of compensating for any internal inconsistencies introduced during the manufacturing process.

To perform offset null adjustment, both input pins are connected directly to 0V ground, and the ends of a trimmer potentiometer (typically, 10K) are connected with the offset null pins, while the wiper of the potentiometer is centered and then connected with the negative power supply. The probes of a meter that is set to measure DC volts are placed between the output of the op-amp and 0V ground. The potentiometer is then adjusted until the meter shows a reading of 0VDC. A schematic is shown in Figure 7-15.



Figure 7-15. *Connections for making an offset null adjustment to an op-amp that allows this procedure.*

What Can Go Wrong

Power Supply Problems

Op-amps are especially vulnerable to reversed polarity in a power supply. If there is even a remote possibility of this occurring, a diode in series with one side of the supply can provide protection.

A more realistic concern is the destructive consequence of an input signal that exceeds the power supply voltage(s) of the op-amp. Even if the input is within the acceptable range, it can still cause permanent damage if it is applied before the op-amp powers up.

Bad Connection of Unused Sections

Multiple op-amps are often combined in a single package. If some of these "sections" remain unused, they will still receive power from the shared supply, and will attempt to function. If the inputs are left unconnected, they will pick up small stray voltages by capacitance or induction, and in the absence of negative feedback, the op-amp will create unpredictable outputs, consuming power and possibly interacting with other sections of the same chip. Figure 7-16 shows three incorrect options for addressing this problem, and one recommended option (derived from Texas Instruments Application Report SLOA067).



Figure 7-16. *When multiple op-amps share a chip, one that is unused will still receive power from the shared supply. Its inputs must not be allowed to float, and must be connected to minimize activity and power consumption. Three common errors are shown here, with one recommended option. Note the distinction between 0V ground (0V) and negative power (V−).*

Oscillating Output

The inputs of an op-amp are vulnerable to stray electromagnetic fields. If the conductors leading to and from the op-amp are relatively long, the output can couple capacitively with the input during voltage transitions, causing unwanted oscillations.

The commonly recommended solution to this problem is to add a 1μF bypass capacitor between the power supply and 0V ground. However, some manufacturers recommend alternatives such as introducing a very small amount of hysteresis, or reducing the value of input resistors to below 10K.

Confused Inputs

A schematic may show an op-amp with the noninverting input above the inverting input, or vice versa. The only indication of this will be the plus and minus signs inside the chip, which can be extremely small and easily overlooked. For convenience in drawing a diagram, two op-amps in the same circuit may have their inputs shown in opposite configurations. Special care must be taken to verify that the inverting and noninverting input pins on a chip are correctly assigned.

digital potentiometer

A **digital potentiometer** is also known as a *digitally adjustable potentiometer*, a *digitally controlled potentiometer*, a *digitally programmed potentiometer* (with acronym *DPP*), a *digpot*, or a *digipot*. The terms are functionally interchangeable. Because the abbreviation *pot* is often used to describe an analog potentiometer, some people refer to digital potentiometers colloquially as *digital pots*. In printed documentation, the letters in *pot* may be capitalized. Because it is an abbreviation, not an acronym, it is not capitalized here.

Because this component enables digital control of a variable voltage, it is a *mixed signal device*. It is classified here as an analog chip because it primarily emulates the function of an analog device. It may be thought of as a form of *digital-analog converter*, although this encyclopedia does not have a section devoted to that type of component or to *analog-digital converters*, as their application is relatively specialized.

OTHER RELATED COMPONENTS

- **potentiometer** (see Volume 1)

What It Does

This component is an integrated circuit chip that emulates the function of an analog **potentiometer**. It is often described as being *programmable*, meaning that its internal resistance can be changed via a control input.

Digital potentiometers are particularly suited for use in conjunction with a *microcontroller*, which can control the internal resistance of the component. Possible applications include adjustment of the pulse width of an oscillator or multistable multivibrator (e.g., using the Control pin of a 555 **timer** chip); adjustment of the gain in an **op-amp**; specification of voltage delivered by a *voltage regulator*; and adjustment of a *bandpass filter*.

A digital potentiometer in combination with a microcontroller may also be used in conjunction with a pair of external buttons or a rotational encoder, to adjust the gain of an audio amplifier and for similar applications.

Advantages

A digital potentiometer offers significant advantages over an analog potentiometer:

- Reliability. The digital component may be rated for as many as a million cycles (each storing the wiper position in an internal memory location). An analog component may be capable of just a few thousand adjustment cycles.
- Digital interface.
- Elimination of long signal paths or cable runs. The digital potentiometer can be placed close to other chips, whereas an analog potentiometer often has to be some distance away to enable control by the end user. Reduction in the length of signal paths can reduce capacitive effects, while elimina-

tion of cable runs will reduce manufacturing costs.

- Reduction in size and weight compared with a manual potentiometer.

A digital potentiometer also has some disadvantages:

- Its internal resistance is somewhat affected by temperature.
- It is not usually capable of passing significant current. Few chips can sink or source more than 20mA at the output, and 1mA is common. The output is primarily intended for connection with other solid-state components that have high impedance.
- Users may prefer the immediacy and tactile feel of a knob attached to an analog potentiometer, rather than a pair of buttons or a rotational encoder.

How It Works

A digital potentiometer changes the point at which a connection is made along a *ladder* of many fixed resistors connected in series inside the chip. Each end of the ladder, and each intersection between two adjacent resistors, is known as a *tap*. The pin that can connect with any of the taps is referred to as the *wiper*, because it emulates the function of a wiper in an analog potentiometer. In reality, a digital potentiometer does not contain a wiper or any other moving parts.

A fully featured digital potentiometer allows access to each end of the ladder through two pins that are often labeled “high” and “low,” even though they are functionally interchangeable (except in the case of a component that simulates a logarithmic taper, as described later). The “low” end of the ladder is sometimes numbered 0. In this case, if there are *n* resistors, the “high” end of the ladder will be numbered *n*. Alternatively, if the “low” end of the ladder is numbered 1, and there are *n* resistors, the “high” end will be numbered *n+1*. This principle is illustrated in Figure 8-1.



Figure 8-1. *Available wiper connections to a resistor ladder inside a digital potentiometer, showing two numbering systems that may be used.*

The “low” pin on a digital potentiometer may be identified as L, or A, or R_L, or P_A in a datasheet, while the “high” pin may be identified as H, or B, or R_H, or P_B and the pin that accesses the wiper is typically identified as W, or R_W, or P_W. Letters L, H, and W are used below. Although the L and H pins are functionally interchangeable, their labels are useful to identify which direction the W connection will move in response to an external signal.

Digital potentiometers are available with as few as 4 or as many as 1,024 taps, but common values are 32, 64, 128, or 256 taps, with 256 being the most common.

No specific schematic symbol represents a digital potentiometer. Often the component is shown as an analog potentiometer symbol inside a box that has a part number, as suggested in

Figure 8-2. Control pins and the power supply may be omitted if the schematic is just intended to show logical connections. Alternatively, if the digital potentiometer is depicted in a schematic where it is connected with other components such as a microcontroller, multiple pins and functions may be included, as shown in Figure 8-3. The pins additional to L, H, and W are explained below.



Figure 8-2. *There is no single specific symbol to represent a digital potentiometer. It may be shown using an analog potentiometer symbol in a box with a part number, as suggested here, where power connections and additional pins are omitted for clarity.*



Figure 8-3. *If a digital potentiometer appears in a schematic where it is connected with other components such as a microcontroller, additional pins and functions may be indicated. This generic representation of a digital potentiometer shows some of the functions that can be included.*

Variants

A *dual* digital potentiometer contains two complete units, while a *quad* contains four. Triples exist but are relatively uncommon. A few chips contain six potentiometers. Multiple digital potentiometers in a chip can be used as the digital equivalent of *ganged* analog potentiometers, for simultaneous synchronized adjustment of multiple inputs in an audio system (two channels in a stereo amplifier, or more in a surround-sound system).

The pinouts of a sophisticated quad digital potentiometer chip are shown in Figure 8-4. Other quad chips have different pinouts and capabilities; there is no standardized format as there is with digital logic chips. In this example, the high/low states of Address 0 and Address 1 select one of the four internal resistor ladders, numbered 0 through 3. The Chip Select pin makes the whole chip either active or inactive. The Write Protect pin disables writing to the internal wiper memory. The Serial Clock pin inputs a reference pulse stream to which the serial input data must be synchronized. The Hold pin pauses the chip while data is being transmitted, allowing the data transmission to be resumed subsequently. The NC pins have no connection.

Volatile and Nonvolatile Memory

Any type of digital potentiometer requires memory to store its current wiper position, and this memory may be volatile or nonvolatile. Nonvolatile memory may be indicated in a datasheet by the term *NV*.

A digital potentiometer with volatile memory will typically reset its wiper to a center-tap position if power is disconnected and then restored. A digital potentiometer with nonvolatile memory will usually restore the most recently used wiper position, provided the chip is fully powered down and then fully powered up without glitches in the supply. If a microcontroller is being used to control the digital potentiometer, it can store the most recent resistance value in its own nonvolatile memory, in which case the type of memory in the potentiometer becomes irrelevant.



Figure 8-4. *Pinouts of a sophisticated quad digital potentiometer chip. Other chips will have different pinouts and capabilities. This example is available in surface-mount formats only. See text for details.*

Taper

Digital potentiometers are available with *linear taper* or *logarithmic taper*. In the former, each resistor in the ladder has the same value. In the latter, values are chosen so that the cumulative resistance between the wiper and the L end of the ladder increases geometrically as the wiper steps toward the H end of the ladder. This is useful in audio applications where sound intensity that increases exponentially may seem to increase linearly when perceived by the human ear.

A microcontroller can emulate logarithmic steps by skipping some taps in the ladder in a digital potentiometer, but this will result in fewer increments and lower precision.

Data Transfer

Digital potentiometers are mostly designed to use one of three serial protocols:

- *SPI*. This acronym is derived from *serial peripheral interface*, a term trademarked by Motorola but now used generically. The standard is adapted in various radically different ways among digital potentiometers.
- *I2C*. More correctly printed as *I^2C* and properly pronounced "I squared C," this acronym is derived from the term *inter-integrated circuit*. Developed by Philips in the 1990s, it is a relatively slow-speed bus-communication protocol (up to 400kbps or 1Mbps in its basic form). It is built into some microcontrollers. The standard is more uniformly and rigorously defined than SPI.
- *Up/down*, also sometimes known as *push-button* or *increment/decrement* protocol.

Both SPI and I2C are supported by many microcontrollers, including the Atmel AVR at the heart of the Arduino.

These three systems for controlling a digital potentiometer are described in more detail in the following sections.

SPI

This is the most widely used protocol, but when reading datasheets, a lot of care must be taken to determine how it varies in each case.

The Microchip 4131-503, shown in Figure 8-5, uses SPI protocol. It contains 128 resistors and can be powered by 1.8VDC to 5.5VDC.

The one feature that all versions of SPI have in common is that a series of high/low pulses is interpreted by the chip as a set of bits whose value defines a tap point in the resistor ladder. In computer terminology, every tap point has an *address*. The incoming bits define the address, after which the status of an additional input pin can tell the chip to move the wiper to that location.

Typically, there will be a chip select pin, identified as CS; a serial data input pin, identified as SDA, SI, DIN, or a similar acronym; and a serial clock pin, identified as SCL, SCLK, or SCK, which must receive a stream of pulses to which the high/low data input pulses must be synchronized. In addition, the SPI protocol allows bidirectional (duplex) serial communication. Only a minority of digital potentiometers make use of this capability, but where it exists, a serial data output pin may be labeled SDO. Alternatively, one pin may be multiplexed to enable both input and output, in which case it may be labeled SDI/SDO.



Figure 8-5. *This digital potentiometer uses SPI protocol. See text for details.*

If a pin is active-low, a bar (a horizontal line) will be printed above its acronym.

The most common type of digital potentiometer has 255 resistors and therefore 256 tap points, which have addresses numbered 0 through 255, each of which can be specified by a sequence of eight data bits constituting one byte. However, a different coding system will be applied in chips that have a different number of taps. In a 32-tap component, for instance, data is still sent in groups of eight bits, but only the first five bits define a *tap address*, while the remaining three are interpreted as commands to the chip.

Most 256-tap chips use an SPI protocol in which two eight-bit bytes are sent, the first being interpreted by the chip as a command, while the second specifies a tap address. Each manufacturer may use a different set of command codes, and these will vary among chips even from the same manufacturer.

Most commonly, three wires are used for data transmission and control (causing these chips to be described as *3-wire* programmable potentiometers).

CS is usually, but not always, pulled low to activate the digital potentiometer for input. A series of low or high states is then applied to the data-input pin. Each time the clock input changes state (usually on the rising edge of the clock pulse) the state of the data input is copied to a **shift register** inside the chip. After all the bits have been clocked in, CS can change from low to high, causing the contents of the shift register to be copied into a decoder section of the chip. The first bit received becomes the most significant bit in the decoder. The value of the eight bits is decoded, and the chip connects the W pin directly to the corresponding tap along the ladder of 255 internal resistors.

I2C Protocol

The I2C specification is controlled by NXP Semiconductors (formerly Philips), but can be used in commercial products without paying licensing fees. Only two transmission lines are required: one carrying a clock signal, the other allowing bidirectional data transfer synchronized with the clock (although many digital potentiometers use the I2C connection only to receive data). The pins are likely to be identified by the same acronyms as the pins on a chip that uses SPI protocol.

As in SPI, a command byte is followed by a data byte, although the command set differs from that of SPI and will also differ among various I2C chips. Full implementation of I2C allows multiple devices to share a single bus, but this capability may remain unused.

Up/Down Protocol

This simpler, asynchronous protocol does not require a clock input. The chip will respond to data pulses that are received at any speed (up to its maximum speed), and the pulse widths can be inconsistent.

Each pulse moves the wiper connection one step up or down the ladder. While this has the advantage of simplicity, the taps are not addressable, and consequently the wiper cannot skip to any tap without passing through intervening taps incrementally. This is not an inconvenience when the potentiometer controls audio gain, which is a primary application.

In some chips, an increment pin, usually labeled INC, receives pulses while the high or low state of a second pin, usually labeled U/D, determines whether each pulse will step the wiper up the ladder or down the ladder.

In other chips, pulses to an Up pin will step the wiper up the ladder, while pulses to a Down pin will step the wiper down the ladder.

Either of these chip designs can be referred to as a *two-wire* type. If an additional chip-select pin is included (labeled CS on datasheets), this type of digital potentiometer can be referred to as a *three-wire* type. The chip select pin is likely to be active-low, meaning that so long as it has a high state, the chip will ignore incoming signals.

The CAT5114 shown in Figure 8-6 uses an U/D pin. It contains 31 resistors, is available in 8-pin DIP or surface-mount formats, and can be powered by 2.5VDC to 6VDC. Each of its logic inputs draws only 10μA.

In six-pin chips the INC pin is omitted, one of the H, L, or W pins will be omitted, and the U/D pin will function differently. When CS is pulled low, the chip checks the state of the U/D pin. If it is high, the chip goes into increment mode; if it is low, the chip goes into decrement mode. So long as CS remains low, each transition of the U/D pin from low to high will either increment or decrement the wiper position, depending on the mode that was sensed initially. When CS goes high, further transitions on the U/D pin will be ignored until CS goes low again, at which point the procedure repeats.



Figure 8-6. *This digital potentiometer contains 31 resistors and uses the simplest up/down protocol to step from one tap to the next.*

The chip does not provide any feedback regarding the position of its wiper, and consequently a control device such as a microcontroller cannot know the current wiper position. If the chip has nonvolatile memory (as is the case in many up/down digital potentiometers), it will resume its previous wiper location at power-up, but here again a control device will have difficulty determining what that position is. Therefore, in its basic form, an up/down chip is only appropriate for simple tasks, especially in response to up/down pushbuttons.

Other Control Systems

A few digital potentiometers use a parallel interface. Because they are relatively uncommon, they are not included here.

Connections and Modes

Some variants of digital potentiometers minimize the chip size and number of connections by limiting accessibility to the internal resistor ladder. In a chip designed to function in *rheostat mode*, the W pin is eliminated and the chip moves an internal connection point to change the resistance between the H and L pins.

In some variants, the low end of the ladder is permanently, internally connected with ground, and the L pin is omitted. In other variants, one end of the ladder is unconnected inside the chip.

A chip designed to function in *voltage divider mode* will include all three pins—H, L, and W—except in some instances where the low end of the ladder is grounded internally.

Variants are shown in Figures 8-7, 8-8, 8-9, and 8-10. Because some pins may be omitted, and there is no standardization of function among the pins that do exist, circuits and chips must be examined carefully prior to use.


V+
0V
Serial clock
High
Wiper
Serial data in
(Texas Instruments TPL0401A, CAT5125)

Figure 8-7. *Some digital potentiometers minimize chip size and provide specialized functionality by eliminating pins. In the variant shown here, the W pin provides a voltage between H and an internal ground connection. The chip is controlled via I2C serial protocol.*


V+
0V
Serial clock
H
Low
Wiper
Serial data in
(Texas Instruments TPL0401C)

Figure 8-8. *In this variant, the H end of the internal resistor ladder is allowed to float inside the chip, and the digital potentiometer functions as a rheostat. The chip is controlled via I2C serial protocol.*


V+
0V
Up/Down
High
Chip select
(Texas Instruments CAT5118, CAT5123)

Figure 8-9. *This variant provides a variable resistance between the H pin and an internal connection with negative ground. Pin 5 is omitted. The chip is controlled by up/down pulses.*


V+
0V
Up/Down
High
Low
Chip select
(Texas Instruments CAT5119, CAT5124

Figure 8-10. *This variant provides a variable resistance between H and L pins, without allowing either end of the resistor ladder to float. The W pin is omitted, as the wiper is tied internally to the H pin. The chips listed are controlled by up/down pulses.*

Values

A primary limitation of digital potentiometers is that they cannot withstand significant current. This may prevent them from being substituted for an analog potentiometer unless changes are made in the circuit. H, L, and W pins are usually unable to source or sink continuous, sustained current exceeding 20mA.

Wiper resistance is the resistance that is added internally by the wiper. This is nontrivial; it is often around 100Ω, and can be as high as 200Ω.

Typical end-to-end resistance of the ladder of internal resistors may range from 1K to 100K. Values of 1K, 10K, and 100K are common.

While the number of taps is likely to be a power of two in chips where the taps are addressable, up/down chips are not so constrained and may contain, for example, 100 taps.

The end-to-end resistance of a whole ladder may vary by as much as 20% from one sample of a chip to the next. Among resistor ladders in digital potentiometers sharing the same chip (i.e., in dual or quad chips) the variation will be much smaller.

Almost all digital potentiometers are designed for a supply voltage of 5V or less. The H and L pins are not sensitive to polarity, but the voltage applied to either of them must not exceed the supply voltage.

How to Use It

While most microcontrollers contain one or more analog-digital converters that change an analog *input* to an internal numeric value, a microcontroller cannot create an analog *output*. A digital potentiometer adds this functionality, although applications will be restricted by its limitation on current.

An up/down digital potentiometer can be controlled directly by a pair of **pushbuttons**, one of which will increase the resistance value while the other will reduce it. The pushbuttons must be *debounced* when used in this way. An alternative to pushbuttons is a **rotational encoder**, which emits a stream of pulses when its shaft is turned. In this case, an intermediate component (probably a microcontroller) will usually interpret the pulse stream and change it to a format that the digital potentiometer can understand.

Where a digital potentiometer is used in audio applications, it should be of the type that moves the wiper connection from one tap to another during a *zero crossing* of the audio signal (i.e., that is, at the moment when the AC input signal passes through 0V on its way from positive to negative or negative to positive). This suppresses the “click” that otherwise tends to occur during switching. Potentiometers with this feature may include phrases such as “glitch free” in their datasheets.

Digital potentiometers that are intended primarily for audio applications often have 32 taps spaced at intervals of 2dB. This will be sufficient to satisfy most listeners.

Achieving Higher Resolution

For sensitive applications where a resolution with more than 1,024 steps is required, multiple digital potentiometers with different step values can be combined. One way of doing this is shown in Figure 8-11. In this circuit, the wipers of P2 and P3 must be moved in identical steps, so that the total resistance between the positive power supply and negative ground remains constant. These two potentiometers could be contained in a dual chip, and would receive identical up/down commands. P1 is at the center of the voltage divider formed by P2 and P3, and is adjusted separately to “fine tune” the output voltage that is sensed at point A.

If all three of the potentiometers in this circuit contain 100 taps, a combined total of 10,000 resistance steps will be possible.



Figure 8-11. *If all three digital potentiometers in this schematic have 100 taps, and the wipers of P2 and P3 are moved in synchronization, the voltage measured at point A can have a high resolution of up to 10,000 steps.*

What Can Go Wrong

Noise and Bad Inputs

Because a digital potentiometer is capable of receiving data at speeds as high as 1MHz, it is sensitive to brief input or power fluctuations, and can misinterpret them as instructions to move the wiper—or can misinterpret them as command codes, in a component using SPI or I2C serial protocol.

To minimize noise in the power supply, some manufacturers recommend installing a 0.1µF capacitor as close as possible to the power supply pin of the component. In addition, it is obviously important to provide clean input signals. This means thorough debouncing of any electromechanical switch or pushbutton inputs.

Wrong Chip

The wide diversity of input protocols and pinouts creates many opportunities for installation error.

Up/down, SPI, and I2C protocol require totally different pulse streams. Many manufacturers offer components that are distinguished from each other by just one or two digits in their part numbers, yet have radically different functionality.

If more than one specific type of digital potentiometer may be used during circuit development, they should be stored carefully to avoid inadvertant substitutions. Using the wrong chip may be particularly confusing in that an inappropriate input protocol will still produce some results, although not those which were intended.

Controller and Chip Out of Sync

As noted in the discussion of data transmission protocols, most digital potentiometers are not capable of providing feedback to confirm the position of the internal wiper. A designer may wish to include a power-up routine which establishes the state of the digital potentiometer by resetting it to a known position, at one end of its scale or the other.

Nonlinear Effects

While the end-to-end resistance of the resistor ladder inside a digital potentiometer is not likely to be affected significantly by changes in temperature, the resistance at the wiper is more heat sensitive.

In an up/down chip, there can be differential errors between incremental and decremental modes. In other words, if a tap is reached by stepping up to it incrementally, the resistance between the W pin and H or L may not be quite the same as if the same tap is reached by stepping down to it decrementally. The difference may not be significant, but may be puzzling for those who are unfamiliar with this phenomenon.

Some differences may be found among resistors in a ladder. That is, in a supposedly linear digital potentiometer, each resistor may differ in value slightly from the next.

Data Transfer Too Fast

When using a microcontroller to send data to a digital potentiometer, a small delay may be necessary between pulses, depending on the microcontroller's clock speed. A digital potentiometer may require a minimum pulse duration of 500ns. Check the manufacturer's datasheet for details.

timer

A device that creates a single timed pulse, or a series of timed pulses with timed intervals between them, is properly known as a *multivibrator*, although the generic term **timer** has become much more common and is used here.

Three types of multivibrator exist: *astable*, *monostable*, and *bistable*. The behavior of *astable multivibrators* and *monostable multivibrators* is described in detail in this entry. A timer chip can also be made to function as a bistable multivibrator. This is described briefly below, but it is not a designed function of a timer. The primary discussion of bistable multivibrators will be found in the entry of this encyclopedia dealing with **flip-flops**.

OTHER RELATED COMPONENTS

- **flip-flop** (See Chapter 11)

What It Does

A *monostable* timer emits a single timed pulse of fixed length in response to a triggering input that is usually of shorter duration. Many monostable timers are also capable of running in *astable* mode, in which the timer spontaneously emits an ongoing stream of timed pulses with timed gaps between them. A dual-mode timer can run in either mode, determined either by external components attached to it, or (less commonly) by changing the status of a mode selection pin.

Monostable Mode

In monostable mode, the timer emits a pulse in response to a change from high to low voltage (or, less commonly, from low to high voltage) at a *trigger pin*. Most timers respond to a *voltage level* at the trigger pin, but some are insensitive to any persistent pin state and only respond to a *voltage transition*. This is known as *edge triggering*.

The pulse generated by the timer may consist of a change from low to high (or, less commonly, from high to low) at an output pin. The length of the pulse will be determined by external components, and is independent of the duration of the triggering event, although in some cases, an output pulse may be prolonged by *retriggering* the timer prematurely. This is discussed below.

At the end of the output pulse, the timer reverts to its quiescent state, and remains inactive until it is triggered again.

A monostable timer can control the duration of an event, such as the time for which a light remains on after it has been triggered by a motion sensor. Alternatively, the timer can impose a delay, such as the interval during which a paper towel dispenser refuses to respond after a towel has been dispensed. A timer can also be useful to generate a clean pulse in response to an unstable or noisy input, as from a manually operated pushbutton.

Astable Mode

In astable mode, a timer will generally trigger itself as soon as power is connected, without any need for an external stimulus. However, the output can be suppressed by applying an appropriate voltage to a *reset pin*.

External components will determine the duration of each pulse and the gap between it and the next pulse. The pulse stream can be slow enough to control the flashing of a turn signal in a 1980s automobile, or fast enough to control the bit rate in a data stream from a computer.

Modern timer circuits are often incorporated in chips that have other purposes. The flashing of a turn signal in a modern car, for instance, is now likely to be timed by a microcontroller that manages many other functions. Still, chips that are purely designed as timers remain widely used and are very commonly available in numerous through-hole and surface-mount formats.

How It Works

The duration of a single pulse in monostable mode, or the frequency of pulses in astable mode, is most commonly determined by an external *RC network* consisting of a resistor in series with a capacitor. The charging time of the capacitor is determined by its own size and by the value of the resistor. The discharge time will be determined in the same way. A **comparator** inside the timer is often used to detect when the potential on the capacitor reaches a *reference voltage* that is established by a voltage divider inside the chip.

Variants

The 555 Timer

An eight-pin integrated circuit manufactured by Signetics under part number 555 was the world's first fully functioned timer chip, introduced in 1972. It combined two comparators with a **flip-flop** (see Chapter 11) to enable great versatility while maintaining excellent stability over a wide range of supply voltages and operating temperatures. Subsequent timers have been heavily influenced by this design. A typical 555 timer chip is shown in Figure 9-1.



Figure 9-1. *A typical 555 timer chip. Functionally identical versions in which the "555" identifier is preceded or followed by different letter combinations are available from many different manufacturers.*

The 555 was designed by one individual, Hans Camenzind, working as an independent consultant for Signetics. According to a transcript of an interview with Camenzind maintained online at the Transistor Museum, "There was nothing like it at the time. You had to use quite a few discrete components—a comparator, a Zener diode or even two. It was not a simple circuit."

The 555 timer quickly became the most widely used chip in the world, and was still selling an annual estimated 1 billion units three decades after its introduction. It has been used in spacecraft, in intermittent windshield wiper controllers, in the early Apple II (to flash the cursor), and in children's toys. Like many chips of its era, its design was unprotected by patents, allowing it to be copied by numerous manufacturers.

The initial version was built around **bipolar transistors**, and consequently is referred to as the *bipolar version* or (more often) the *TTL version*, this being a reference to *transistor-transistor logic* protocol. Within a few years, CMOS versions based around **MOSFETs** were developed. They reduced the ability of the chip to sink or source current at its output pin, but consumed far less power, making them better suited to battery-operated products. The CMOS versions were and still are pin-compatible with the original bipolar version, both in through-hole and surface-mount formats. Their timing parameters are usually the same.

555 Monostable Operation

The internal functionality of a 555 timer wired to run in monostable mode is illustrated in Figure 9-2 with the chip seen from above. The pins are identified in datasheets by the names shown. To assist in visualizing the behavior of the chip, this figure represents the internal flip-flop as a switch which can be moved by either of two internal comparators, or by an input from the Reset pin.



Figure 9-2. *The internal functions of a 555 chip, with its flip-flop represented as a switch that can be moved by either of two comparators, or by a low voltage on the Reset pin. An external resistor and capacitor, shown as R1 and C1, cause the timer to run in monostable (one-shot) mode, generating a single high pulse when the state of the Input pin is pulled from high to low.*

Inside the chip, three resistances of 5K each are connected between V+ (positive supply voltage) and negative ground. It has been suggested that the part number of the 555 chip was derived from these three 5K resistors, but Hans Camenzind has pointed out that Signetics was already using three-digit part numbers beginning with the number 5, and probably chose the 555 part number because the sales department had high expectations for the chip and wanted its number to be easily memorable. (A similar rationale explains the part number of the 2N2222 transistor.)

The resistances inside the timer function as a *voltage divider*, providing a reference of 1/3 of V+ to the noninverting pin of Comparator A and 2/3 of V+ to the inverting pin of Comparator B. (See Chapter 6 for an explanation of the functioning of comparators.)

When power is initially supplied to the timer, if the Input pin is at a high state, Comparator A has a low output, and the flip-flop remains in its “up” position, allowing the Output pin to remain in a low state. The flip-flop also grounds the lower end of R1, which prevents any charge from accumulating on capacitor C1.

If the state of the Input pin is pulled down externally to a voltage less than 1/3 of V+, Comparator A now creates a high output that changes the flip-flop to its “down” position, sending a high signal out through the Output pin. At the same time, C1 is no longer grounded, and begins to charge at a rate determined by its own size and by the value of R1. When the charge on the capacitor exceeds 2/3 of V+, it activates Comparator B, which forces the flip-flop into its “up” position. The Output pin goes low, C1 discharges itself into the Discharge pin, and the timer’s cycle is at an end.

The low voltage on the Input pin of the timer must end before the end of the output cycle. If the voltage on the Input pin remains low, it will re-trigger the timer, prolonging the output pulse.

A pullup resistor may be used on the Input pin to avoid false triggering, especially if an external electromechanical **switch** or **pushbutton** is used to pull down the Input pin voltage.

The Reset pin should normally be held high, either by being connected directly to positive supply voltage (if the reset function will not be needed) or by using a pullup resistor. If the Reset pin is pulled low, this will always interrupt an output pulse regardless of the timer's current status.

If a voltage higher or lower than 2/3 of V+ is applied to the Control pin, this will change the reference voltage on Comparator B, which determines when the charging cycle of C1 ends and the discharge cycle begins. A lower reference voltage will shorten each output pulse by allowing a lower charge limit for C1. If the control voltage drops to 1/3 of V+ (or less), the capacitor will not charge at all, and the pulse length will diminish to zero. If the control voltage rises to become equal to V+, the capacitor will never quite reach that level, and the pulse length will become infinite. A workable range for the control voltage is therefore 40% to 90% of V+.

Because the Control pin is an input to the chip, it should be grounded through a 0.01µF ceramic capacitor if it will not be used. This is especially important in CMOS versions of the timer.

A defect of the bipolar 555 is that it creates a *voltage spike* when its Output pin changes state. If it will be sharing a circuit with sensitive components, a 0.01µF bypass capacitor should be added as closely as possible between the V+ pin and negative ground. The voltage-spike problem was largely resolved by the CMOS 555.

555 Astable Operation

In Figure 9-3, the 555 timer chip is shown with external components and connections to run it in astable mode. The pin names remain the same but have been omitted from this diagram because of limited space. The labeling of the two external resistors and capacitor as R1, R2, and C1 is universal in datasheets and manufacturers' documentation.

When the timer is powered up initially, capacitor C1 has not yet accumulated any charge. Consequently, the state of the Threshold pin is low. But the Threshold pin is connected externally with the Input pin, for astable operation. Consequently, the Input pin is low, which forces the flip-flop into its "down" state, creating a high output. This happens almost instantaneously.



Figure 9-3. *The internal functions of a 555 chip, with two external resistors and a capacitor wired to run the timer in astable (free-running) mode.*

While the flip-flop is "down," the Discharge pin is not grounded, and current flowing through R1 and R2 begins to charge the capacitor. When the charge exceeds 2/3 of positive supply voltage, Comparator B forces the flip-flop into its "up" position. This ends the high pulse on the Output pin, and starts to drain the charge from the capacitor through R2, into the Discharge pin. However, the voltage on the capacitor is still being shared by the Input pin, and when it diminishes to 1/3 of V+, the Input pin reactivates Comparator A, starting the cycle over again.

The functions of the Reset and Control pins are the same as in monostable mode. Because voltage applied to the Control pin changes the length of each pulse and the gaps between pulses, it has the effect of adjusting the frequency of the output in astable mode.

When power is first connected to the timer, C1 must initially charge from an assumed state of zero potential to 2/3 V+. Because subsequent cycles will begin when the capacitor is at 1/3 V+, the first high output pulse from the timer will be slightly longer than subsequent output pulses. This is unimportant in most applications, especially because the rate at which a capacitor accumulates charge is greater when beginning from 0V than when it has reached 1/3 V+. Still, the longer initial pulse can be noticeable when the timer is running slowly.

Because the capacitor charges through R1 and R2 in series, but discharges only through R2, the length of each positive output pulse in astable mode is always greater than the gap between pulses. Two strategies have been used to overcome this limitation. See "Separate Control of High and Low Output Times" on page 80.

556 Timer

The 556 consists of two 555 bipolar-type timers in one package. An example of the chip is shown in Figure 9-4. The pinouts are shown in Figure 9-5. Although 556 timers have become relatively uncommon compared with the 555, they are still being manufactured in through-hole and surface-mount versions by companies such as Texas Instruments and STMicroelectronics, under part numbers such as NA556, NE556, SA556, and SE556 (with various letters or letter pairs appended). Each timer in the chip has its own set of inputs and outputs, but the timers share the same V+ and ground voltages.

558 Timer

This 16-pin chip is now uncommon, and many versions have become obsolete. It has been identified by a part number such as NE558 although different prefix letters may be used. The NTE926, shown in Figure 9-6, is actually a 558 timer.

The chip contains four 555 timers sharing a common power supply, common ground, and common control-pin input. For each internal timer, the Threshold and Discharge functions are connected internally, so that the timers can only be used in one-shot mode. However, one timer can trigger another at the end of its cycle, and the second timer can then retrigger the first, to create an astable effect.

Each timer is edge-triggered by a voltage transition (from high to low), instead of being sensitive to a voltage level, as is the case with a 555 timer. Consequently the timers in the 558 chip are insensitive to a constant (DC) voltage.



Figure 9-4. *An example of the 556 timer chip.*



Figure 9-5. *The 556 timer contains two separate 555 timers sharing the same power supply and ground. The pin functions for timer A and timer B are shown here.*

The output from each timer is an open collector, and therefore requires an external pullup resistor. Each output is capable of sinking up to 100mA.



Figure 9-6. *The NTE926 is a 558 timer chip.*

CMOS 555 Timer

While the part numbers of many CMOS versions are significantly different from part numbers of the bipolar versions, in some instances the CMOS numbers are only distinguished by a couple of initial letters. The ST Microelectronics TS555 series and Texas Instruments TLC555 series, for example, use MOSFETs internally. The ST Microelectronics SE555 series and Texas Instruments SA555 series use bipolar transistors internally.

One way to distinguish between the two types, when searching a website maintained by a parts supplier, is to begin by looking generically for a "555 timer" and then add a search filter to show chips either with a minimum power supply of 3VDC (which will be CMOS) or with a minimum power suply of 4.5VDC (which will be bipolar).

CMOS versions of the 555 timer do not create the power spike that is characteristic of the bipolar versions during output transitions. The CMOS chips can also be powered by a lower voltage (3VDC, or 2VDC in some cases), and will draw significantly less current in their quiescent state. They also require very little current for threshold, trigger, and reset functions.

The wiring of external resistors and capacitors to the CMOS version of the chip, and the internal voltage levels as a fraction of V+, are identical to the original 555 timer. Pin functions are likewise identical. The only disadvantages of CMOS versions are their greater vulnerability to static discharge, and their lower output currents. The TLC555, for instance, will source only 15mA (although it can sink 10 times that amount). Other manufacturers have different specifications, and datasheets should be checked carefully.

5555 Timer

The 5555 contains a digital **counter** that enables it to time very long periods. Its full part number is 74HC5555 or 74HCT5555, although these numbers may be preceded or followed by letter combinations identifying the manufacturer. It is not pin-compatible with a 555 timer.

Two input pins are provided, one to trigger the timer on a rising edge, the other on a falling edge, of the input pulse. The inputs are Schmitt-triggered.

The timer is rated for 1Hz to 1MHz (using an external resistor and external capacitor). The counter section can divide the pulse frequency by values ranging from 2 to 256. For longer timed periods, different settings on the digital control pins will divide the frequency by values ranging from 2^{17} through 2^{24} (131,072 through 16,777,216). This enables the timer to achieve a theoretical pulse length lasting for more than 190 days. The timer will accept a clock input from an external oscillator to achieve better accuracy than is available with a resistor-capacitor timing circuit.

7555 Timer

This 8-pin chip is a CMOS version of the 555 timer, manufactured by companies such as Maxim Integrated Products and Advanced Linear Devices. Its characteristics are similar to those of CMOS 555 timers listed above, and the pinouts are the same.

7556 Timer

This 14-pin chip contains two 7555 timers, sharing common power supply and ground connections. Pinouts are the same as for the original 556 timer, as shown in Figure 9-5.

4047B Timer

This 14-pin CMOS chip was introduced in an effort to address some of the quirks of the 555 timer while also providing additional features. It runs in either monostable or astable mode, selectable by holding one input pin high or another input pin low. In astable mode, its duty cycle is fixed at approximately 50%, a single resistor being used for both charging and discharging the timing capacitor. An additional "oscillator" output runs twice as fast as the regular output.

In monostable mode, the 4047B can be triggered by a positive or negative transition (depending on which of two input pins is used). It ignores steady input states and will also ignore additional trigger pulses that occur during the output pulse. However, a retrigger pin is provided to extend the output pulse if desired.

Complementary output pins are provided, one being active-high while the other is active-low.

To time very long periods, the 4047B was designed to facilitate connection with an external counter.

The power supply for the 4047B can be as low as 3VDC. Its maximum source or sink output current is only 1mA when powered at 5VDC, but up to 6.8mA when powered at 15VDC.

The chip is still available from manufacturers such as Texas Instruments (which markets it as the CD4047B) in through-hole and surface-mount formats. However, despite its versatility, the 4047B is less popular than dual monostable timers, described in the next section.

Dual Monostable Timers

Various timers that run only in monostable mode are available in dual format (i.e., two timers in one chip). This format became popular partly because two monostable timers can trigger each other to create an astable output, in which the pulse width, and the gap between pulses, can be set by a separate resistor-capacitor pair on each timer. This allows greater flexibility than is available when using a 555 timer.

Most dual monostable timer chips are edge-triggered by a change in input voltage, and will ignore a steady DC voltage. Consequently, the output from one timer can be connected directly to the input of another, and no coupling capacitors are necessary.

As in the 4047B, the user has a choice of two input pins for each timer, one triggered by a transition from low to high, the other triggered by a transition from high to low. Similarly, each timer has two outputs, one shifting from low to high at the start of the output cycle, the other shifting from high to low.

The values of a single resistor and capacitor determine the pulse duration of each timer.

Dual monostable timers often have the numeric sequence 4528 or 4538 in their part numbers. Examples include the HEF4528B from NXP, the M74HC4538 from STMicroelectronics, and the MC14538B from On Semiconductor. The 74123 numeric sequence identifies chips that have a very similar specification, with chip-family identifiers such as HC or LS inserted, as in the 74HC123 and 74LS123, and additional letters added as prefix or suffix. The pinouts of almost all these chips are identical, as shown in Figure 9-7. However, Texas Instruments uses its own numbering system, and datasheets should always be consulted for verification before any connections are made.

Many chips of this type are described as "retriggerable," meaning that if an additional trigger pulse is applied to the input before an output pulse has ended, the current output pulse will be extended in duration. Check datasheets carefully to determine whether a chip is "retriggerable" or will ignore new inputs during the output pulse.

The 74HC221 dual monostable vibrator (pictured in Figure 9-8) functions very similarly to the components cited above, but has slightly different pinouts.



Figure 9-7. *Pin functions for most 4528, 4538, and 74123 series of dual monostable timer chips. An RC network is shown connected for each timer. Note that Texas Instruments uses different pinouts on its versions.*



Figure 9-8. *A dual-timer chip containing two monostable multivibrators that can function in astable mode if they are connected externally to trigger each other.*

Values

555 Timer Values

The original bipolar version of the 555 timer was designed to operate using a wide range of positive supply voltages, from 4.5VDC to 16VDC. CMOS versions vary in their recommended V+ values, and datasheets must be consulted for verification.

The output of a bipolar 555 is rated to source or sink up to 200mA. In practice, the maximum current will be lower when the timer is powered at the low end of its range, around 5VDC. Attempting to source more than 50mA will pull down the voltage internally, affecting operation of the timer.

CMOS versions all impose restrictions on output current, allowing higher values for sinking than sourcing. Again, datasheets must be consulted for the values, which vary widely from one component to another.

The voltage measured on the output pin, when it is used for sourcing current, will always be lower than the power supply voltage, and a 1.7V drop is commonly specified for bipolar versions. In practice, the voltage drop that is actually measured may be less, and will vary according to the load on the output.

The voltage drop does not increase significantly with a higher supply voltage, and because it is a relatively constant value, it becomes less significant when a higher value for V+ is used.

CMOS versions of the 555 timer achieve a claimed output source voltage that is only 0.2V less than the power supply.

When choosing values for R1 and R2, a minimum for each resistor is 5K, although 10K is preferred. Lower values will increase power consumption, and may also allow overload of the internal electronics when the chip sinks current from C1. A typical maximum value for each resistor is 10M.

A high-value capacitor may cause the timer to function less accurately and predictably, because large capacitors generally allow more *leakage*. This means that the capacitor will be losing charge at the same time that it is being charged through R1 + R2. If these resistors have high values, and the capacitor has a value of 100µF or more, the rate of charge may be so low that it is comparable with the rate of leakage. For this reason, a 555 timer is not a good choice for timing intervals much greater than a minute. If a large-value capacitor is used, tantalum is preferable to electrolytic.

The minimum practical value for a timing capacitor is around 100pF. Below this, performance may not be reliable.

Although some CMOS versions may enable fast switching, the shortest practical output pulse for a 555 timer is around 10 microseconds. On the input pin, a triggering pulse of at least 1 microsecond should be used.

Time Calculation in Monostable Mode

If R1 is measured in kilohms and C1 is measured in microfarads, the pulse duration, T, in seconds, of a 555 timer running in monostable mode can be found from this simple formula:

```
T = 0.0011 * R1 * C1
```

This relationship is the same in all versions of the 555. Figure 9-9 provides a quick and convenient way to find the pulse value using some common values for R1 and C1. Resistors can be obtained with tolerances below plus-or-minus 1%, but capacitors are often rated with an accuracy of only plus-or-minus 20%. This will limit the accuracy of the pulse values shown in the chart.

Time Calculation in Astable Mode

If R1 and R2 are measured in kilohms and C1 is measured in microfarads, the frequency of pulses, F (measured in Hz) of a 555 timer running in astable mode can be found from this simple formula:

```
F = 1440 / ( ( R1 + (2 * R2) ) * C1)
```

This relationship is found in all versions of the 555. Figure 9-10 shows the frequency for common values of R2 and C1, assuming that the value of R1 is 10K. In Figure 9-11, a value of 100K is assumed for R1.



Figure 9-9. *To determine the pulse duration of a 555 timer running in monostable mode: find the value of R1 on the horizontal scale, follow its vertical grid line upward to the intersection with a green line which corresponds with the value of capacitor C1, and read across to the vertical scale providing the duration in seconds. Both axes are logarithmic.*

Dual Monostable Timers

Dual chips such as the HEF4528B from NXP, the M74HC4538 from STMicroelectronics, the MC14538B from On Semiconductor, and the 74HC123 from Texas Instruments have widely varying requirements for power supply. Some accept a limited range from 3VDC to 6VDC, while others tolerate a range of 3VDC to 20VDC. When powered with 5VDC their required input and output states are compatible with those of 5V logic chips.

Output pins of these chips source and sink no more than 25mA (much less in some instances). Because there are so many variants, they cannot be summarized here, and datasheets must be consulted for details.



Figure 9-10. *To obtain the frequency of a 555 timer running in astable mode, when R1 has a value of 10K: find the value of R2 on the horizontal scale, follow its vertical grid line upward to the intersection with a green curve which corresponds with the value of capacitor C1, and read across to the vertical scale providing the frequency in Hertz. Both axes are logarithmic.*



Figure 9-11. *To obtain the frequency of a 555 timer running in astable mode, when R1 has a value of 100K: find the value of R2 on the horizontal scale, follow its vertical grid line upward to the intersection with a green curve which corresponds with the value of capacitor C1, and read across to the vertical scale providing the frequency in Hertz. Both axes are logarithmic.*

As these timers are all monostable, and each timer uses just one resistor and one capacitor, the only formula required is to give the pulse time as a function of these two variables. If R is the resistor value in ohms, and F is the capacitor value in farads, and K is a constant supplied by the manufacturer, the pulse time T, in seconds, is found from the formula:

```
T = R * F * K
```

K ranges between 0.3 and 0.7 depending on the manufacturer and also on the voltage being used. Its value should be found in the manufacturer's datasheet. If R is measured in megohms and F is measured in microfarads, the formula is still valid, as the multipliers cancel each other out.

Generally speaking, these dual monostable CMOS timers are not intended for pulse duration exceeding 1 minute.

The timing capacitor should be no larger than 10µF, as it discharges directly and rapidly through the chip.

How to Use It

Where a timer is required to drive a load such as a relay coil or small motor directly, the original TTL version of the 555 timer will be the only choice. Even in this instance, a protection diode must be used across the inductive device.

For smaller loads and applications in chip-to-chip circuits, CMOS versions of the 555, including the 7555, use less power, cause less electrical interference, and are pin-compatible while using the same formulae to calculate frequency in astable mode or pulse duration in monostable mode. They are of course more vulnerable to static discharge, and care must be taken to make a connection to every pin (the capacitor that grounds the Control pin, if Control is not going to be used, is mandatory).

In dual monostable timers, unused rising-edge trigger inputs should be tied to V+ while unused falling-edge trigger inputs should be tied to ground. A Reset pin that will not be used should be tied to V+, unless that entire timer section of the chip will be unused, in which case the pin should be grounded.

To measure durations longer than a few minutes, a timer which incorporates a programmable counter to divide the clock frequency is the sensible choice. See the description of the 5555 timer that was included earlier in this entry.

The original bipolar version of the 555 remains a robust choice in hobby applications such as robotics, and its design allows some versatile variations which may even be used in logic circuits. A variety of configurations are shown in the schematics below.

555 Monostable Mode

The basic schematic for a 555 timer running in monostable mode is shown in Figure 9-12. In this particular example, a pushbutton that is liable to suffer from *switch bounce* is connected to the Input pin of the timer, which responds to the very first connection made by the pushbutton and ignores the subsequent "bounces," thus producing a "clean" output. To avoid retriggering, which results in a prolonged output pulse, the timer's output should exceed the time for which the button is likely to be pressed. The output should also exceed the duration of any possible switch bounce, which can otherwise create multiple output pulses. In the schematic, an LED is attached to the timer output for demonstration purposes.



Figure 9-12. *The basic monostable configuration of a 555 timer. This particular circuit debounces an input from a pushbutton switch and converts it to a clean pulse of fixed duration, powering an LED for demonstration purposes.*

This circuit is shown on a breadboard in Figure 9-13. The red and blue wires, at the top of the photograph, supply 9VDC to the board. R1 is 1M, while C1 is 1µF, creating a pulse of just over 1 second. A tactile switch, just above the timer, provides the input.



Figure 9-13. *The basic monostable configuration for a 555 timer, mounted on a breadboard.*

555 Astable Mode

A basic schematic for a 555 timer running in astable mode is shown in Figure 9-14. Once again, an LED is attached to the output for demonstration purposes. If the pulse rate exceeds the persistence of vision, a small loudspeaker can be used instead, in series with a 47Ω resistor and a 100µF capacitor.



Figure 9-14. *A 555 timer with external connections and components causing it to run in astable (free-running) mode.*

Separate Control of High and Low Output Times

In Figure 9-15, a bypass diode has been added around R2. The capacitor now charges primarily through R1, as the diode has a much lower effective resistance than R2. It discharges only through R2, as the diode blocks current in that direction. Consequently, the length of the high output pulse can be adjusted with the value of R1 only, while the length of the low output pulse can be adjusted with the value of R2 only. The duration of the high output can be lower than, or equal to, the duration of the low output, which is not possible with the basic configuration of components in Figure 9-14.



Figure 9-15. *In this circuit, a diode bypasses R2, so that the "on" time and the "off" time of the 555 timer can be set independently of each other, with R1 and R2, respectively.*

555 Fifty Percent Astable Duty Cycle: 1

In Figure 9-16, the circuit enables a fixed astable output duration of approximately 50% high and 50% low. Initially, C1 has no charge, pulling the Input of the timer low, and causing it to begin a cycle with a high pulse from the Output pin, as usual. In this demonstration circuit, the output illuminates an LED. At the same time, resistor R1 is attached to the output and charges C1. When the voltage on C1 reaches 2/3 of V+, this is communicated to the timer Input pin, which ends the "high" cycle and initiates low status on the Output pin. This starts to sink the charge from C1, through R1. When the voltage drops to 1/3 V+, this initiates a new cycle. Because only one resistor is used to charge and discharge the capacitor, we may imagine that the charge and discharge times should be identical. However, a higher load on the output will probably pull down the output voltage to some extent, lengthening the charge time. Conversely, a load on the Output pin that has low resistance will probably sink at least some of the charge from the capacitor, shortening the discharge cycle.



Figure 9-16. *This configuration provides an approximate 50-50 on-off duty cycle at the output pin, although the precise duration will depend on the load.*

555 Fifty Percent Astable Duty Cycle: 2

In Figure 9-17, a small modification of the basic astable circuit shown in Figure 9-14 provides another way to enable a 50% duty cycle. Compare the two schematics, and you will see that just the connection between R1 and R2 has been altered so that C1 now charges only through R1, and discharges only through R2. However, in this configuration the capacitor is discharging into a voltage divider created by the two resistors. Empirical adjustment of the resistor values may be necessary before the duty cycle is precisely 50%.



Figure 9-17. *An alternative configuration to provide an approximate 50-50 on-off duty cycle in a 555 timer.*

Use of the 555 Control Pin

In Figure 9-18, a potentiometer and two series resistors allow a varying voltage to be applied to the Control Pin. This will lengthen or reduce both the charge and the discharge times of the timing capacitor. If values for the capacitor and its associated resistors are chosen to create a frequency of approximately 700Hz, a 10K potentiometer should demonstrate more than an octave of audible tones through the loudspeaker. Other components can be substituted for a potentiometer, creating possibilities for producing pulse-width modulation. Alternatively, if a large capacitor is added between the Control pin and ground while a second 555 timer, running slowly in astable mode, applies its output to the Control pin, the charging and discharging of the capacitor will apply a smoothly rising and falling voltage. If the first 555 timer is running at an audio frequency, the output will have a "wailing siren" effect.



Figure 9-18. *A circuit that allows adjustment of the astable 555 frequency by increasing or lowering the voltage on the Control pin.*

Figure 9-19 shows the components specified in Figure 9-18 mounted on a breadboard.



Figure 9-19. *The components in the previous schematic are shown here mounted on a breadboard. They will generate an audio output ranging between approximately 425Hz and 1,075Hz. A lower value for the timing capacitor will shift the audio range higher in frequency.*

555 Flip-Flop Emulation

The flip-flop inside a 555 timer can be accessed to control the timer's outputs. In Figure 9-20, pushbutton switch S1 applies a negative pulse to the Input pin, creating a high output from the timer, which illuminates LED D1. Normally the pulse length would be limited by the charge time of a capacitor attached to the Threshold pin, but in this circuit there is no capacitor, and the Threshold pin is hard-wired to negative ground. So, it never rises to 2/3 of positive power, and the output from the timer remains high indefinitely.



Figure 9-20. *A 555 timer can have its timing features disabled so that it functions as a flip-flop.*

However, if S2 is pressed, it grounds the Reset pin of the timer, which ends the high output and pulls the Output pin down to a low state. D1 goes out and D2 lights up, as the timer is now sinking current through it. When S2 is released, the timer output remains low and D2 remains illuminated, because the Input pin is held high by a pullup resistor. Therefore, the timer now functions in bistable mode, as a flip-flop. While this may be seen as an inappropriate use of the chip, because its full functionality is being disabled, its ability to deliver substantial current and to tolerate a wide range of supply voltages may make it more convenient to use than a digital flip-flop. See Chapter 11 for more information about flip-flops.

A 555 timer emulating a flip-flop is shown on a breadboard in Figure 9-21.



Figure 9-21. *The schematic in which a 555 timer acts as a flip-flop is shown here adapted for a breadboard.*

555 Hysteresis

The comparators inside a 555 timer enable the chip to produce hysteresis. In Figure 9-22, the Input pin and the Threshold pin are shorted together, and C1, the timing capacitor, is omitted. A 10K potentiometer, wired as a voltage divider, delivers a voltage to the Input pin ranging smoothly from V+ to negative ground. As the input dips below 1/3 V+, the Output pin goes high, lighting LED D1. Now if the input voltage gradually rises, the output remains high, even as the input rises above 1/3 V+. The output state is "sticky" because the timer does not end an output pulse until the Threshold pin tells it to, by reaching 2/3 V+. When this finally occurs, the Output pin goes low, D1 goes out, and D2 comes on, sinking current into the Output pin.

Suppose, now, the input voltage starts to go down again. Once again the output state is "sticky" because it remains low until the Input pin drops below the 1/3 level. When that happens, the output finally flips back to a high state, D2 goes out, and D1 comes on.

In the "dead zone" between 1/3 and 2/3 of supply voltage, the timer remains in its current mode, waiting for the input to stray outside of those limits. This behavior is known as *hysteresis*, and is of special importance when processing a varying signal, such as the voltage from a temperature sensor, to control an on/off device such as a thermostat. In fact the 10K potentiometer in this demo could be replaced with a thermistor or a phototransistor, wired in series with a resistor to create a voltage divider which will have an input range compatible with the 555 timer. The hysteresis can then be adjusted by varying the supply voltage that powers the timer, as this will change the values of 1/3 V+ and 2/3 V+. Alternatively, varying the voltage on the Control pin will affect the hysteresis.

A **comparator** can provide much more versatile control of hysteresis by using positive feedback (see Chapter 6 for additional details). But the 555 timer provides a quick-and-simple substitute, and its greater ability to source or sink current enables it to be connected with a wider range of other components.



Figure 9-22. *A 555 timer wired so that it creates hysteresis, when supplied by a variable input voltage.*

555 and Coupling Capacitors

As previously noted, when a basic bipolar 555 timer (and some of its variants) is wired in monostable mode, it will retrigger itself indefinitely if its input remains low. One way to avoid this is by using a coupling capacitor. This will pass a transition from high to low, but will then block a steady subsequent voltage. In Figure 9-23, a phototransistor in series with a resistor provides a variable voltage to the noninverting input of a comparator. The reference voltage of the comparator is adjusted with a potentiometer, and resistor R3 provides positive feedback, ensuring that the output from the comparator will be quick and clean. The output from the 555 timer goes through a transistor to the relay, shown at the bottom.

It is important to see the function of the coupling capacitor, C3, with the pullup resistor, R2, which holds the Input pin of the 555 timer high by default. When the output from the comparator drops from high to low, C3 passes this transition to the Input pin of the timer, momentarily overcoming the positive potential, and triggering the timer. After the timer responds, however, C3 blocks any continuation of low voltage from the comparator. Pullup resistor R2 resumes its function of holding the input high, and prevents the timer from being retriggered.

555 Loudspeaker Connection

A small 8-ohm loudspeaker can be driven from the output of a bipolar 555 timer running in astable mode, but should be isolated from it with a 10µF to 100µF capacitor. A series resistor of 47Ω (minimum) should be used. See Figure 9-24.

Burst Mode

It is sometimes useful to create a short beep of fixed length in response to a button-press. The beep should terminate even if the button is held down. This “burst mode” can be achieved with the circuit in Figure 9-25, where the button connects power to a bipolar-type 555 timer running in astable mode, and an RC network applies a decreasing potential to a 47µF capacitor, which is wired to the Reset pin of the timer. The resistor in series with the capacitor will vary the length of the beep. When voltage to the pin drops below approximately 0.3V, output from the timer stops and cannot restart until the button is released.

A resistor of greater than 1.5K may not allow the input value at the reset pin to fall below the voltage, which is necessary to enable a reset. If a lower power supply voltage than 9VDC is used, the resistor value should be higher—for example, a 5VDC power supply works well with a 1.5K to 2K resistor.



Figure 9-23. *A coupling capacitor (C3) is used in this circuit to isolate the 555 timer from a sustained low input from the comparator. The capacitor only passes a transition from high to low. The rest of the time, the pullup resistor (R3) holds the input high.*



Figure 9-24. *A small 8-ohm loudspeaker can be attached through a capacitor and a resistor to the output of a bipolar 555 timer.*



Figure 9-25. *An RC circuit, wired to apply a decreasing voltage on the Reset pin of a bipolar 555 timer, will shut off the timer shortly after it is powered up. This can be used to create a fixed-length beep in response to a button press of any duration.*

Figure 9-26 shows the components installed on a breadboard.

"You Lose" Game Sound

A timer is a simple, cheap way to create a variety of simple game sounds. The schematic in Figure 9-27 makes a groaning sound as the 100µF capacitor wired to the Control pin of a bipolar-type 555 gradually charges through the 1K resistor. Note that if a larger resistor is paired with a smaller capacitor, the effect will differ. The 150K resistor is included to discharge the capacitor reasonably quickly in time for the next cycle.



Figure 9-26. *The "burst mode" circuit installed on a breadboard with a miniature loudspeaker.*

What Can Go Wrong

Dead Timer

Like any chip, the 555 can be damaged by overvoltage, excessive source current or sinking current, static electricity, incorrectly applied polarity of power supply, and other forms of abuse. The TTL version of the timer is fairly robust, but the CMOS type much less so. Check for obvious errors such as lack of supply voltage, incorrect or ambiguous input voltages, and unusual current draw (too high, or none at all, at the V+ pin). Use the meter probes on the actual pins of the chip, in case there is a break in the wiring that feeds them. Because timer chips are cheap, a reserve supply of them should be maintained.



Figure 9-27. *An RC circuit, wired to apply an increasingly positive voltage to the Control pin of a bipolar timer running in astable mode, will gradually pull down the frequency at the Output pin, creating a sound that may be useful in simple game applications.*

CMOS Confused with Bipolar

The part numbers of some bipolar chips are very similar to those of some CMOS versions, and the chips look physically identical. But the CMOS version is easily overloaded, as it may source only 10mA to 20mA maximum while the TTL version is capable of 200mA. Make sure that your chips are carefully labeled when they are stored.

The Pulse that Never Ends

If a 555 timer responds correctly to a high-to-low transition on the input pin, but the output pulse continues indefinitely, check the voltage on pin 6 to see if the timing capacitor is charging above 2/3 of V+. While a 555 can run from 5VDC, a high-current device on the Output pin can pull down the voltage inside the chip to the point where the capacitor never charges sufficiently to end the cycle.

Also check that the input transition from high to low lasts for a shorter time than the pulse. A persistent low input can retrigger the timer.

Erratic Chip Behavior

Possible causes include:

- Floating pins. The Input pin, in particular, should always be connected with a defined voltage (via a 10K pullup resistor, if necessary), and must not be allowed to float at an indeterminate potential.
- Voltage spikes. A timer can be triggered by transients from other components, especially inductive loads. If the input to a monostable timer dips for even a fraction of a second, the timer will initiate a new cycle. A *protection diode* should be used in conjunction with an inductive load.
- Voltage spikes can also introduce variations in the pulse train from an astable timer.
- TTL versions of the 555 timer will tolerate a wide range of supply voltage, but if a voltage regulator is not used, fluctuations in voltage can have unpredictable consequences.

Interference with Other Components

Because the bipolar version of a 555 timer creates a voltage spike when its output changes state, it can interfere with the normal function of other components, especially CMOS chips. A 0.1µF bypass capacitor can be applied between the timer's V+ pin and ground.

Erratic Behavior of Output Devices

If a 555 timer powers an output device such as a relay, and the relay is not opening or closing in a reliable manner, first check that it is receiving sufficient voltage. If the 555 timer is powered with 5VDC, its output will be only around 4VDC.

This problem can be avoided by using the output from the timer to control the voltage on the base of a transistor which switches a separate source of power to the relay coil.

Fatal Damage Caused by Inductive Loads

While it is possible to drive an inductive load such as a small motor or relay directly from a TTL 555 timer, two precautions should be taken. First, the motor or the coil of the relay should have a clamping diode added around it, as is standard practice. Second, because the output of the timer is capable of sinking current as well as sourcing current, it can be protected from sinking back-EMF by inserting a diode in series with the load. This is illustrated in Figure 9-28.



Figure 9-28. *In addition to a standard protection diode clamped around an inductive load such as a relay coil, the 555 timer can be protected from back-EMF by adding a diode in series. The series diode must of course be rated to carry sufficient current through the coil. When choosing a relay, allowance must be made for the voltage drop that will be imposed by the series diode.*

logic gate

10

Only basic **logic gates** are included in this entry—that is, components that perform a Boolean logic operation on two to eight inputs (or one input, in the case of an inverter) to create a single high or low logical output.

OTHER RELATED COMPONENTS

- **flip-flop** (see Chapter 11)

What It Does

A **logic gate** is a circuit that delivers an output, either high or low, depending on the states of its two inputs, either or both of which can be high or low.

Some gates may have more than two inputs, and an *inverter* only has one input, but the basic gates all conform with the two-input, one-output model. The components that constitute a logic gate are almost always etched into a wafer inside a silicon chip.

In a digital computer, a *high logic state* is traditionally close to 5VDC and represents a value of 1 in *binary arithmetic*, while a *low logic state* is traditionally close to 0VDC and represents a binary 0. Modern devices may use a lower voltage for the high state, but the principle is still the same.

A small network of logic gates can perform binary addition, and all other operations in a digital computer are built upon this foundation.

Origins

The concept of digital logic originated in 1894, when English mathematician George Boole announced his invention of a form of algebra (now referred to as *Boolean algebra*) to analyze combinations of two logical states that could be interpreted as "true" and "false." This concept had few practical applications until the 1930s, when Claude Shannon saw that because a basic switch has two states, Boolean algebra could enable analysis of complex networks of switches that were being used in telephone systems.

Because the state of a switch could also be used to represent the values 0 or 1 in binary arithmetic, and because a transistor could function as a switch, Boolean algebra was implemented in solid-state digital computing equipment.

How It Works

While conventional arithmetic uses *arithmetical operators* to represent procedures such as addition or multiplication, Boolean algebra uses *Boolean operators*. The operators of special interest in digital electronics are named AND, NAND, OR, NOR, XOR, and XNOR.

Although each gate actually contains multiple transistors, it is represented by a single logic symbol, as shown in Figure 10-1. The names of the Boolean operators are customarily printed all in caps. A gate requires a power supply and a connection with negative ground, separate from its inputs, but these connections are omitted from gate schematics because they are assumed to exist.



Figure 10-1. *Six types of two-input logic gates are used in digital electronics, although the XNOR gate is rare, as it has few applications. The names are customarily printed in uppercase letters.*

The functions of the gates with two inputs can be defined in electrical terms. In Figure 10-2, the four possible combinations of inputs are tabulated in the left column, with red indicating a high input and black indicating a low input. The corresponding output from each gate is shown beneath its name. This kind of tabulation is known as a *truth table*, as it is derived from Boolean algebra which originally concerned itself with "true" and "false" states.

Input states of a two-input gate	Gate Outputs					
	AND	NAND	OR	NOR	XOR	XNOR
⚫ ⚫	⚫	🔴	⚫	🔴	⚫	🔴
⚫ 🔴	⚫	🔴	🔴	⚫	🔴	⚫
🔴 ⚫	⚫	🔴	🔴	⚫	🔴	⚫
🔴 🔴	🔴	⚫	🔴	⚫	⚫	🔴

Figure 10-2. *The four possible combinations of input states in a 2-input logic gate are shown at left. The corresponding output from each gate is shown beneath its name. Red indicates a high state, while black indicates a low state.*

The truth table assumes that *positive logic* is being used. Negative logic is very uncommon, but if it were used, the red dots in the truth table would correspond with low inputs and outputs, while the black dots would correspond with high inputs and outputs.

Inversion

The small circles appended to the outputs of NAND, NOR, and XNOR gates mean that the output of each gate is inverted compared with the AND, OR, and XOR gates. This can be seen by inspection of the output states shown in Figure 10-2. The circles are known as *bubbles*.

Sometimes logic symbols are shown with a bubble applied to one input, as in Figure 10-3. In these cases, the circle indicates that an input must be inverted. More than one gate may be needed to achieve this logic function in an actual circuit. The style is often used to show the inner workings of an IC, using a minimum number of logic symbols.



Figure 10-3. *The circle in a logic gate symbol indicates that a signal is being inverted. Circles can be inserted at gate inputs, but in a real circuit a separate inverter is likely to be needed to create this effect.*

Single-Input Gates

Two gates exist that have a single input and a single output, shown in Figure 10-4. The *buffer* should not be confused with the symbol for an **op-amp** or a **comparator**. (Those components always have two inputs.) The output state of a buffer is the same as its input state, but the component may be useful to deliver more current or to isolate one section of a circuit from another.

When a bubble is appended to a buffer, it becomes a NOT gate, more commonly known as an *inverter*. Its function is to create an output state that is opposite to its input state.



Figure 10-4. *The two logic gates that have only one input and one output. Note that in some schematics showing internal logic of ICs, the bubble on an inverter may be found on the input side instead of the output side.*

Gates with More than Two Inputs

AND, NAND, OR, and NOR gates can have any number of inputs, as suggested in Figure 10-5, although practical factors usually limit the inputs to a maximum of eight.

Input states of a gate with more than two inputs	Gate Outputs			
	AND	NAND	OR	NOR
All low	●	🔴	●	🔴
All high	🔴	●	🔴	●
At least 1 low and at least 1 high	●	🔴	🔴	●

Figure 10-5. *The previous table has been modified to show the outputs from logic gates that have more than two inputs. XOR and XNOR gates are not included in the table, because a strict interpretation of their logic requires that a unique output state exists if one input is high while the other is low.*

The rules can be summarized like this:

- Output from an AND gate: Low if any of its inputs is low, high if all of its inputs are high.
- Output from a NAND gate: High if any of its inputs is low, low if all of its inputs are high.
- Output from an OR gate: High if any of its inputs is high, low if all of its inputs are low.
- Output from a NOR gate: Low if any of its inputs is high, high if all of its inputs are low.

In the case of XOR and XNOR gates, their logic requires that a unique output state must exist if one input is high while the other input is low.

In fact, so-called three-input XOR gates do exist, an example being the 74LVC1G386 chip, in which the output is high if all three inputs are high, or if one input is high, but not if two inputs are high or no inputs are high. Further discussion of more-than-two-input XORs is outside the scope of this encyclopedia.

Boolean Notation

For reference, the original written notation for Boolean operators is shown in Figure 10-6. Unfortunately, the notation for these operators was never properly standardized, and in more than one instance, multiple symbols acquired the same meaning. The letters P and Q are often, but not always, used to represent two input states that can be true or false.

- The use of a horizontal line above a symbol, to indicate that its state has been reversed, has carried over to datasheets where this notation can show that an output state from any digital chip is inverted. The line is known as a *bar*.

Arithmetical Operations

Suppose we wish to sum two binary numbers, each containing two digits. There are four digits altogether, and depending on their values, there are 16 different possible addition sums, as shown in Figure 10-7.

If A0 and B0 represent the rightmost digits of the two numbers being added, and S0 is the sum of those two digits, inspection of the figure shows that the sum can be derived using just three rules:

1. If A0 = 0 and B0 = 0, then S = 0.
2. If A0 and B0 have opposite states, then S0 = 1.
3. If A0 = 1 and B0 = 1, then S0 = 0, and carry 1 to the next place left.

If A0 and B0 are the two inputs to an XOR logic gate, the output of the gate satisfies all three rules, except the need to carry 1 to the next place left. This last function can be satisfied with an AND gate. The function of two gates is known as a *half adder*, and is shown in the top section of Figure 10-8.



Figure 10-6. *Boolean operators as they have been expressed in written notation. Lack of standardization has resulted in more than one symbol representing some of the operators.*

When we consider the next pair of binary digits to the left, the situation now becomes more complicated, because we may be carrying 1 into this addition sum from the previous stage, and we still need to be able to to carry 1 out (if necessary) to the next stage. An assembly of five logic gates can deal with this, and their combination is known as a *full adder*. This is shown in the bottom section of Figure 10-8.



Figure 10-7. *Sixteen different addition sums are possible, when summing two binary numbers of two digits each.*

The combination of XOR and AND gates shown in Figure 10-8 is not the only one that works to add binary numbers. However, it may be the most intuitively obvious.

Other Operations

Binary arithmetic remains the most important application of logic gates, but individually packaged gates are seldom used for that purpose anymore. They were long since subsumed into large multifunction computing chips.

Single gates still have application in small systems, or to modify the inputs and outputs of microcontrollers, or to convert the output from one complex digital chip to make it compatible with the input of another. This last application is often referred to as *glue logic*.

Applications for single gates are discussed in "How to Use It" on page 103.



Figure 10-8. *Logic gates can be used to add binary numbers, using a high input or output to represent a binary 1 and a low input or output to represent a binary 0. This schematic shows one possible way for gates to add two two-digit binary numbers.*

Variants

Chips containing logic gates were introduced in the 1960s. The 7400 NAND chip, from Texas Instruments, was the first of a series that became so influential, the same basic part numbers (with letters added before, after, and among the digits) are still used today. An example of a currently available through-hole 7400 chip is shown in Figure 10-9.



Figure 10-9. *A modern version of a 7400 chip containing four NAND gates.*

Initially, these chips conformed with a *transistor-transistor logic* (*TTL*) standard that had been invented at TRW in 1961 and introduced in commercial products by Sylvania in 1963. It established the now-familiar standard of 5VDC for the power supply. Many logic chips now use other voltages, but the term "high" still means an input or output that is near to the supply voltage, while "low" means an input or output that is near to negative ground. The exact definition of "near" will be found in datasheets for the chips.

The *7400 series* was successful partly because it was engineered for compatibility. The output from one gate could be connected directly to the input of another gate, with a few bypass capacitors added on a circuit board to suppress voltage spikes caused by rapid switching. Earlier components had not been so easy to interface with each other. The new standard dominated the industry to the point where dozens of manufacturers started making chips that conformed with it, and a single board could mix-and-match chips from multiple vendors.

Because many logic chips acquired part numbers that began with 74, they are often referred to as the 74xx series, where other digits (sometimes more than two) can be substituted for xx. This avoids ambiguity, as the very first chip in this format was a NAND gate that had 7400 as its actual part number. In the text below, 7400 will refer to that specific chip, whereas 74xx will refer to the whole series of chips.

RCA introduced a competing family of logic gates in 1968, using CMOS transistors. As each part number began with a 4 and contained four digits, this was referred to as the *4000 series*. The CMOS chips were slower and more expensive, but tolerated a wider range of power supply voltages (3V to 12V, initially). Their biggest advantage was that they used much less current. This was important, as TTL chips created a lot of waste heat. The lower power consumption of CMOS also enabled one chip to control the inputs of many others, which simplified circuit design. This one-to-many relationship is known as *fanout*.

Ultimately, CMOS chips transcended their early limitations. While they were reserved initially for battery-powered devices in which very low power consumption was more important than speed, CMOS is now used almost everywhere, still maintaining its advantage of low current (almost zero, in fact, while a chip is quiescent) while equalling the speed of TTL. However, CMOS logic chips are very often pin-compatible with the old TTL components, and modern CMOS part numbers are often derived from the old 74xx series.

Most CMOS logic chips in the old 4000 series are still available, and may be used in situations where a power supply greater than 5VDC is convenient.

Part Numbers

As the performance of semiconductors gradually improved, successive *families* of logic chips were introduced, identified by one-letter, two-letter, or three-letter acronyms. The acronym was inserted into the part number, so that a 7400 NAND gate in the HC (high-speed CMOS) family became a 74HC00 NAND gate.

Because these chips were available from multiple sources, the part number was also preceded with one or more letters indicating the manufacturer. And because each chip was manufactured in different versions (for example, some complied with military specifications, while others didn't), letters were also appended to the end of the part number. Today, the appended letters may indicate whether the chip is of the old through-hole format, or conforms with a more recent surface-mount format.

Summing up:

- Prefix: manufacturer ID.
- Numerals, omitting any letters in the middle: Chip functionality.
- Middle letters: Chip family.
- Suffix letters: Package format.

Thus, for example, the actual part number for a 74HC00 NAND chip could be SN74HC00N, where the SN prefix indicates that it is manufactured by Texas Instruments and the N suffix means that it is in plastic dual-inline-pin (DIP) format. (The SN prefix was introduced by Texas Instruments in the earliest days of integrated circuits as an acronym for "semiconductor network," meaning that multiple transistors were "networked" on a wafer of silicon. Other manufacturers used their own schemes for part numbering, and so SN became exclusively identified with Texas Instruments.)

The system of augmenting part numbers has been further extended by inserting 1G, 2G, or 3G immediately after the family identifier, to indicate surface-mount chips that contain one, two, or three logic gates. If the "G" identifier is missing, the chip usually has four logic gates, which was the standard used in the original 74xx series. This rule applies even in surface-mount formats, where the surface-mount pads of four-gate chips have the same functions as the pinouts of the original TTL versions (except in the case of square-format surface-mount chips, which are not discussed here).

When searching a catalog to find a chip by its part number, it helps to remember that searching for a 7400 chip may not find any hits, but searching for a 74HC00 (or any other valid number containing a family identifier) is much more likely to be understood.

A key to understanding part numbers is shown in Figure 10-10. The upper part of the figure is a guide to interpreting numbers on a generic basis, while the lower part interprets the specific part number shown.

Families

As of 2013, the HC family in the 74xx series has become so widely used, it can be considered the default in the traditional DIP 14-pin format. Incremental improvements are still being made, and new families are being introduced, primarily in surface-mount formats which use lower power-supply voltages (down to around 1VDC).


Generic meaning of logic chip part numbers
Manufacturer ID: usually 1 to 3 letters
How many logic gates: only for surface-mount chips with 1, 2, or 3 logic gates (not used for other chips)
Chip series: first 2 digits
Chip family: 1 to 3 letters
Chip type: 1 to 4 digits
Package format: usually 1 to 5 letters
SN
74
LVC
2G
00
DCUR
74xx logic
Two logic gates on chip
Texas Instruments code for VSSOP: Very thin Shrink Small Outline Package
Texas Instruments
Meaning of this part number
Lower Voltage CMOS
7400 part number: NAND gate

Figure 10-10. *How to interpret the segments of a logic chip part number in the 74xx family (in this case, a 7400 NAND gate).*

Here is an historical summary of the most important chip families.

- 74xx: Original series of bipolar TTL chips.
- 74Hxx: Bipolar TTL, high speed, about twice as fast as the original 74xx chips, but twice the power consumption.
- 74Lxx: Bipolar TTL, lower power consumption than the original TTL, but also much lower speed.
- 74LSxx: Bipolar TTL, lower power with Schottky input stages, faster than original TTL. Some LS chips are still being manufactured.
- 74ASxx: Bipolar TTL, Advanced Schottky, intended to supercede the 74Lxx.
- 74ALSxx: Bipolar TTL, Advanced Low Power Schottky, intended to supercede the 74LSxx.
- 74Fxx: Bipolar TTL, Faster.
- 74HCxx: CMOS high-speed emulation of 74LSxx.
- 74HCTxx: CMOS but with similar high-state input voltage threshold to bipolar TTL chips, for compatibility.
- 74ACxx: Advanced CMOS.
- 74ACTxx: Advanced CMOS emulation of TTL with similar high-state input voltage threshold to TTL, for compatibility.
- 74AHCxx: Advanced Higher-Speed CMOS, three times as fast as HC.
- 74VHCxx: Very High Speed CMOS.
- 74AUCxx, 74FCxx, 74LCXxx, 74LVCxx, 74ALVCxx, 74LVQxx, 74LVXxx: Various specifications, many using power supply voltages of 3.3V or below.

In the 4000 series, an early significant improvement was the 4000B family, which allowed a higher power supply limit (18V instead of 12V) and was much less susceptible to damage by static discharge. The 4000B family almost totally replaced the old 4000 family, and most 4000B chips are still available, as they are useful in situations where a power supply delivers more than 5VDC.

- When it is referenced casually, the B at the end of a chip number in the 4000 series may be omitted. When the number is listed in a catalog, the B is included.

Chips with 45 as their first two digits were introduced as a new generation, but were not widely adopted. After that, the 4000 series ceased to evolve, and CMOS chips adopted 74xx part numbers, distinguishing themselves by the insertion of letter groups in the center of the number.

To add to the confusion, some 4000 series part numbers were appended to 74xx part numbers, so that, for example, the 74HCT4060 is designed to be compatible with the old 4060B chip.

Family Interoperability

One of the most important issues relating to chip families is their differing specifications for a low-state voltage and a high-state voltage in inputs and outputs.

The original 74xx TTL series, using a 5VDC power supply, used these approximate specifications:

- Output: 74xx voltage representing a low state (at most 0.4V to 0.5V)
- Input: 74xx input voltage interpreted as a low state (maximum 0.8V)
- Output: 74xx voltage representing a high state (at least 2.4V to 2.7V)
- Input: 74xx input voltage interpreted as a high state (minimum 2V)

This provided a safe margin of error of at least 0.4V when chips were communicating with each other.

In the CMOS 4000 family, however, logic chips required a minimum input of 3V to 3.5V to be interpreted as a high state. The minimum acceptable output from a TTL chip was below this level, creating problems if anyone should try to use the output from a TTL chip to communicate with an input on a CMOS chip.

One solution is to add a 4.7K pullup resistor to the TTL output, guaranteeing that it won't fall too low. But this wastes power, and the need for the resistor is easily forgotten. Another option is to use the HCT or ACT family of CMOS logic. The "T" in these family names indicates that they have been engineered to share the input standards of the old TTL chips. They still deliver the same high output as other types of CMOS, making them seem to be the best possible solution. Unfortunately, it does entail a compromise: the "T" chips are more sensitive to noise, among other factors.

- Ideally, chip families should not be intermingled.

Gates per Chip

Each of the original 74xx chips contained multiple gates within the limits of a uniform 14-pin through-hole format. The gates that were most commonly used had two inputs, and there were four of these gates per chip.

However, the desire for miniaturization, and the use of automatic chip-placement and soldering equipment, made one-gate and two-gate logic chips desirable and practical in surface-mount format. (Three-gate surface-mount chips exist, but are sufficiently unusual that they are not described in this encyclopedia.)

Two Inputs, Single Gate

Where a chip contains just one logic gate, it is almost always a surface-mount component, and the part number has 1G in the middle to indicate "one gate." Pad functions are shown in Figure 10-11. The layout is standardized for all logic gates, with the exception of XNOR gates, which are not manufactured in surface-mount format.



Figure 10-11. *Internal configuration and solder-pad functions for a two-input surface-mount single-gate logic chip that can contain an AND, NAND, OR, NOR, or XOR gate. XNOR gates are not manufactured in this format.*

In the figure, a gate is shown in generic form, indicating that it may be an AND, NAND, OR, NOR, or XOR gate, depending on the part number of the chip. Inputs are on the left of the gate, while its output is on the right. The chip does not have a solder pad in position 5, but the pad at top right is identified as pin 6 for consistency with the numbering pattern in other surface-mount components where six pads are common.

The generic part numbers for single-gate surface-mount two-input logic chips are shown here, with letter x indicating that letter sequences are likely to be inserted to indicate manufacturer, logic family, and chip format:

- AND gate: x74x1G08x
- OR gate: x74x1G32x
- NAND gate: x74x1G00x
- NOR gate: x74x1G02x
- XOR gate: x74x1G86x

Three Inputs, Single Gate

AND, NAND, OR, and NOR single gates are available with more than two inputs. Their output is determined by rules shown in Figure 10-5. XOR and XNOR gates are not included in the table, because a strict interpretation of their logic requires that a unique output state exists if one input is high while the other is low.

The pad functions for a surface-mount single-gate logic chip with three inputs are shown in Figure 10-12. The generic part numbers for these chips are shown below. Again, each x indicates that letter sequences are likely to be inserted to indicate manufacturer, logic family, and chip format.



Figure 10-12. *Internal configuration and solder-pad functions for a three-input surface-mount single-gate logic chip that can contain an AND, NAND, OR, or NOR gate.*

The generic part numbers for single-gate surface-mount three-input logic chips are shown here, with each x indicating that letter sequences are likely to be inserted to indicate manufacturer, logic family, and chip format:

- AND: x74x1G11x
- NAND: x74x1G10x
- OR: x74x1G32x
- NOR: x74x1G27x

Single Gate, Selectable Function

A few surface-mount chips can emulate a variety of two-input gates, by using appropriate external connections. The internal logic of one example, with generic part number x74x1G97x (an actual example would be Texas Instruments SN74LVC1G97), is shown in Figure 10-13. Depending which pin is grounded and which other pins are used as inputs, the chip can emulate all five of the most commonly used gates. To achieve this, however, some inputs have to be inverted.



Figure 10-13. *Internal configuration for a configurable surface-mount chip that can emulate various two-input logic gates, depending which inputs are used and which are grounded. Some inputs have to be inverted to emulate some gates.*

Two Inputs, Dual Gate

Two-input surface-mount AND, NAND, OR, NOR, and XOR gates are available in dual layout (two gates per chip). The internal logic and pad functions are shown in Figure 10-14. The generic part numbers for these chips are shown here. Again, each x indicates that letter sequences are likely to be inserted to indicate manufacturer, logic family, and chip format.



Figure 10-14. *Internal configuration and solder-pad functions for a two-input surface-mount dual-gate logic chip that can contain two AND, NAND, OR, NOR, or XOR gates. XNOR chips are not manufactured in this format.*

The generic part numbers for dual-gate surface-mount two-input logic chips are shown below, with each x indicating that letter sequences are likely to be inserted to indicate manufacturer, logic family, and chip format:

- AND: x74x2G08x
- NAND: x74x2G00x
- OR: x74x2G32x
- NOR: x74x2G02x
- XOR: x74x2G86x

Original 74xx 14-Pin Format

Each of the original 74xx TTL chips contained multiple gates within the limits of a uniform 14-pin chip format. The available options were, and still are:

- Quad 2-input: Four gates with two inputs each
- Triple 3-input: Three gates with three inputs each
- Dual 4-input: Two gates with four inputs each
- Dual 5-input: Two gates with five inputs each
- Single 8-input: One gate with eight inputs

The five-input chips have become so uncommon that they are not described in this encyclopedia.

Quad Two-Input 74xx Pinouts

14-pin DIP 74xx quad two-input logic chips are available in AND, NAND, NOR, XOR, or XNOR versions, all of which have an internal layout shown in Figure 10-15. The layout is unchanged in surface-mount format. The gates are shown in generic form, as the layout remains the same regardless of which type of gate is in the chip. All the gates in any one chip are of the same type. The four connections leading to a gate are its inputs, while the single connection from a gate is its output.


Quad 2-input AND, NAND, NOR, XOR, or XNOR
GATE
GATE
GATE
GATE
1
2
3
4
5
6
7
14
13
12
11
10
9
8
(74xx family)

Figure 10-15. *In a 14-pin quad two-input 74xx logic chip, the AND, NAND, NOR, XOR, and XNOR versions all share this generic layout.*

- The 14-pin quad two-input OR chip has different pinouts from all the other 74xx logic chips. It is shown in Figure 10-16.


Quad 2-input OR
OR
OR
OR
OR
1
2
3
4
5
6
7
14
13
12
11
10
9
8
(74xx family)

Figure 10-16. *In a quad two-input 74xx OR chip, this layout is used, which is different from that used in all the other quad two-input logic gates.*

Triple Three-Input 74xx Pinouts

The AND, NAND, and NOR versions of a 14-pin DIP 74xx triple three-input logic chip all have an internal layout shown in Figure 10-17. The layout is unchanged in surface-mount format. The gates are shown in generic form, as the layout remains the same regardless of which type of gate is in the chip. All the gates in any one chip are of the same type. Three connections leading to a gate are its inputs, while a single connection from a gate is its output.


Triple 3-input AND, NAND, or NOR
GATE
GATE
GATE
1
2
3
4
5
6
7
14
13
12
11
10
9
8
(74xx family)

Figure 10-17. *In a 14-pin triple three-input 74xx logic chip, the AND, NAND, and NOR versions all share this generic layout.*

- The 14-pin triple three-input OR chip has different pinouts from all the other 74xx logic chips. It is shown in Figure 10-18.


Triple 3-input OR
OR
OR
OR
1
2
3
4
5
6
7
14
13
12
11
10
9
8
(74xx family)

Figure 10-18. *In a triple three-input 74xx OR chip, this layout is used, which is different from that used for all the other triple three-input logic gates.*

Dual Four-Input 74xx Pinouts

A 14-pin DIP 74xx dual four-input logic chip contains two four-input gates. The AND, NAND, and NOR versions all have an internal layout shown in Figure 10-19. The layout is unchanged in surface-mount format. The gates are shown in generic form, as the layout remains the same regardless of which type of gate is in the chip. All the gates in any one chip are of the same type.

- There is no OR chip of the 14-pin dual four-input type.



Figure 10-19. *In a 14-pin dual four-input 74xx logic chip, the AND, NAND, and NOR versions all share this generic layout. There is no 74xx OR chip with four inputs per gate.*

Single Eight-Input 74xx Pinouts

A 14-pin DIP 74xx single eight-input NAND chip contains one eight-input gate, as shown in Figure 10-20. The layout is unchanged in surface-mount format.

- There is no AND chip of the 14-pin single eight-input type.

A 14-pin eight-input logic chip in the 74xx series, able to function as both an OR and a NOR, is shown in Figure 10-21. The output from the NOR gate is connected with pin 13, but also passes through an inverter to create an OR output at pin 1. (Because a NOR gate is equivalent to an inverted-OR, when its output is inverted again, it returns to being an OR.)



Figure 10-20. *The internal layout of single eight-input NAND chip in the 14-pin 74xx series. There is no 74xx AND chip with eight inputs per gate.*



Figure 10-21. *The internal layout of single eight-input OR/NOR chip in the 14-pin 74xx series. Pin 13 has the NOR output, while pin 1 has the OR output.*

The following list shows the generic part numbers for DIP and surface-mount versions of 14-pin logic chips in the 74xx series that have two or more inputs per gate. As before, an x indicates that letter sequences are likely to be inserted to indicate manufacturer, logic family, and chip format.

- Quad 2-input AND: x74x08x
- Quad 2-input NAND: x74x00x
- Quad 2-input OR: x74x32x
- Quad 2-input NOR: x74x02x
- Quad 2-input XOR: x74x86x
- Quad 2-input XNOR: x74x266x
- Triple 3-input AND: x74x11x
- Triple 3-input NAND: x74x10x
- Triple 3-input OR: x74x4075x
- Triple 3-input NOR: x74x27x
- Dual 4-input AND: x74x21x
- Dual 4-input NAND: x74x20x
- Dual 4-input NOR: x74x4002x
- Single 8-input NAND: x74x30x
- Single 8-input OR/NOR: x74x4078x

74xx Inverters

Single, dual, and triple inverter packages in the 74xx series are available in surface-mount format only. Their internal arrangement is shown in Figures 10-22, 10-23, and 10-24.



Figure 10-22. *The internal layout of a 74xx series logic chip containing one inverter. This is available in surface-mount format only. Pin 5 is absent. Pin 1 is not connected.*



Figure 10-23. *The internal layout of a 74xx series logic chip containing two inverters. This is available in surface-mount format only.*



Figure 10-24. *The internal layout of a 74xx series logic chip containing three inverters. This is available in surface-mount format only.*

In the 14-pin format, a hex inverter chip (containing six inverters) is available, as shown in Figure 10-25. The layout is the same for DIP and surface-mount formats.

Generic part numbers for inverter chips are as follows:

- Single inverter: x74x1G04x
- Dual inverter: x74x2G04x
- Triple inverter: x74x3G14x
- Hex inverter: x74x04x



Figure 10-25. *The internal layout of a 14-pin 74xx hex inverter logic chip, containing six inverters. This layout is the same for DIP and surface-mount versions.*

Additional Variations

Some chips in the 74xx series (both DIP and surface mount versions) have variants with open drain or open collector outputs, while others have inputs that are configured as Schmitt triggers. These variants will be found as hits when searching supplier websites for logic chips by gate name and number of inputs.

Pinouts in the Original 4000 Series

Each of the original 4000 CMOS chips contained multiple gates within the limits of a uniform 14-pin chip format. The available options were, and still are:

- Quad 2-input: Four gates of two inputs each
- Triple 3-input: Three gates of three inputs each
- Dual 4-input: Two gates of four inputs each
- Single 8-input: One gate of eight inputs

In the 4000 family, 14-pin quad two-input logic chips are available in AND, OR, NAND, NOR, XOR, or XNOR versions, all of which have an internal layout shown in Figure 10-26. The gates are shown in generic form, as the layout remains the same regardless of which type of gate is in the chip. All the gates in any one chip are of the same type. The four connections leading to a gate are its inputs, while the single connection from a gate is its output.

Unlike the 74xx family, the quad two-input OR chip in the 4000 family has the same pinouts as the other types of quad two-input logic chips.



Figure 10-26. *In the 4000 family, the AND, OR, NAND, NOR, XOR, and XNOR versions of a quad two-input logic chip all share this generic layout.*

In the 4000 family, a 14-pin triple three-input logic chip contains three three-input gates. The AND, OR, NAND, and NOR versions all have an internal layout shown in Figure 10-27. The gates are shown in generic form, as the layout remains the same regardless of which type of gate is in the chip. All the gates in any one chip are of the same type. The three connections leading to a gate are its inputs, while a single connection from a gate is its output.

Unlike the 74xx family, the triple three-input OR chip in the 4000 family has the same pinouts as the other types of triple three-input logic chips.

In the 4000 family, a 14-pin dual four-input logic chip contains two four-input gates. The AND, NAND, OR, and NOR versions all have an internal layout shown in Figure 10-28. The gates are shown in generic form, as the layout remains the same regardless of which type of gate is in the chip. All the gates in any one chip are of the same type. Each pair of connections leading to a gate are its inputs, while the single connection from a gate is its output.



Figure 10-27. *In the 4000 family, the AND, OR, NAND, and NOR versions of a triple three-input logic chip all share this generic layout.*

Note that the 4000 family does have a dual four-input OR chip, whereas the 74xx family does not.

In the 4000 family, a 14-pin eight-input logic chip with AND and NAND outputs is available, as shown in Figure 10-29.

The following list shows the generic part numbers for 14-pin logic chips in the 4000 family that have two or more inputs per gate (in actual part numbers, letters will be substituted where an x appears):

- Quad 2-input AND: x4081x
- Quad 2-input NAND: x4011x
- Quad 2-input OR: x4071x
- Quad 2-input NOR: x4001x
- Quad 2-input XOR: x4070x
- Quad 2-input XNOR: x4077x
- Triple 3-input AND: x4073x
- Triple 3-input NAND: x4023x
- Triple 3-input OR: x4075x
- Triple 3-input NOR: x4025x
- Dual 4-input AND: x4082x
- Dual 4-input NAND: x4012x
- Dual 4-input OR: x4072x
- Dual 4-input NOR: x4002x
- Single 8-input AND/NAND: x4068x



Figure 10-28. *In the 4000 family, the AND, OR, NAND, and NOR versions of a dual four-input logic chip all share this generic layout.*

4000 Series Inverters

In the 4000 family, the 4069B is a 14-pin hex inverter chip (containing six inverters), as shown in Figure 10-30. This has the same pinouts as the x74x04x chip.

How to Use It

Which Family

In DIP format, the HC family has existed for more than 30 years, and has become established as a widely used default choice.

In surface-mount formats, the choice of family will largely be determined by the choice of supply voltage.



Figure 10-29. *In the 4000 family, a single eight-input AND/NAND chip has this internal layout. The inverted output from the NAND gate becomes an AND output from pin 1 of the chip.*



Figure 10-30. *The internal layout of a 14-pin 4069B hex inverter logic chip, containing six inverters. This layout is the same as for the x74x04x chip.*

Although the 4000 series is now more than 40 years old, it may still be useful where a 5VDC power supply is not required for other reasons in a circuit and would be added purely to power a 74xx series logic gate or other digital chip. If a circuit contains a 9VDC or 12VDC relay, for instance, a Darlington pair may be used with that voltage to drive the relay, and an old-school 4000 series logic chip could share the same supply. The relay coil would need a clamping diode to protect the logic chip from transients.

Applications

The output from a logic chip may be used as an input for a microcontroller, to enable multiple inputs to share one pin. An eight-input NAND gate, for instance, could combine the inputs from eight normally on motion sensors. If just one sensor responds to an intrusion, the gate output would change from high to low.

Logic gates may be useful in any simple device that has to respond to a single, specific combination of inputs. A digital combination lock is one example; games of chance are another. Most simple dice simulations use logic gates to convert the output from a counter to drive a dice-pattern of LEDs.

A logic gate may be used as an interface between an electromechanical **switch** and a circuit containing digital chips. A 10K pullup or pulldown resistor prevents the gate input from floating when the switch is open. A buffer can be used for this purpose, or an inverter, or any “spare” gate on a logic chip that is already in the circuit. One input of the chip can be tied to the positive power supply or negative ground, to create an appropriate input from the chip when the switch, attached to the other input, is opened or closed.

A jam-type **flip-flop** can be used to *debounce* a switch input. See Chapter 11 for details. If two NOR or two NAND gates are unused in a circuit, they can form a flip-flop.

In the original CMOS 4000 family, a positive output may be capable of driving an LED if the current does not exceed 5mA with a power supply of 5VDC or 10mA with a power supply of 10VDC. Note that the output voltage will be pulled down significantly by these loads. In the 74HCxx family, chips can source or sink as much as 20mA, but here again the output voltage will be pulled down. Note that the total limit for all outputs from a 74HCxx chip is around 70mA.

The output from a logic chip can be passed through a buffer such as the 7407, which has an open-collector output capable of sinking as much as 200mA. This enables direct drive of modest loads, so long as they are not inductive.

Solid-state relays and **optocouplers** can be driven directly from logic chips, as they draw very little current. A solid-state relay can switch 50A or more.

What Can Go Wrong

Two problems are common when using CMOS digital chips: damage from *static electricity*, and erratic behavior caused by *floating pins*.

Static

The early 4000 series CMOS chips were especially vulnerable, but more recent CMOS designs generally include diodes at the inputs, which reduces the risk. Still, logic chips should be protected by inserting them into anti-static foam or enclosing them in conductive wrappers until they are installed in a board. While handling chips, it is good practice to be grounded, ideally using a wrist-mounted ground wire.

Floating Pins

Any pin which is unconnected in a logic chip is considered to be "floating," and can pick up signals by capacitive coupling, possibly disrupting the behavior of the chip and also causing power consumption, as the ambiguous pin state will tend to prevent that gate in the chip from entering quiescent mode.

Generally speaking, input pins in a TTL logic chip that are not being used for any purpose should be tied to the positive voltage supply, while unused CMOS pins should be tied to negative ground.

Family Incompatibilities

As previously noted, older TTL logic chips may deliver a "high" output voltage that is lower than the minimum expected by newer CMOS logic chips. The best option is not to mix families, but if chips are stored carelessly, some intermingling can occur. Part numbers should be checked if one chip appears to be ignoring output from another.

Overloaded Outputs

If a circuit calls for a logic chip with an open-collector output, and a regular chip is used by mistake, it will almost certainly be damaged.

Output Pulled Down

If the output from one logic chip is connected with the input of another logic chip, and if the output from the first chip is also connected to an **LED**, the LED may pull down the output voltage so that the second chip will not recognize it as a high state. As a general rule, a logic output can drive an LED, or can drive another logic chip, but not both. Very-low-current LEDs, which draw as little as 2mA, may be acceptable.

Incorrect Polarity and Voltages

Logic chips can be knocked out by applying incorrect polarity, or voltage to the wrong pin, or the wrong voltage. Modern logic chips tolerate a very limited voltage range, and a 74xx series chip will be irrevocably damaged if it is used where a 4000 series chip was specified for a power supply higher than 6VDC.

If a chip is inserted upside-down, it will probably be damaged when voltage is applied.

Bent Pins

Like all through-hole chips, DIP logic chips can be inserted accidentally with one or more pins bent underneath the chip. This error is very easy to miss. The bent pins will not make contact with any socket that is used, and the chip will behave unpredictably. Check for proper pin insertion with a magnifying glass if necessary.

Unclean Input

Logic chips expect a clean input without voltage spikes. A 555 timer of TTL type generates spikes in its output which can be misinterpreted as multiple pulses by the input of a logic chip. A CMOS-type 555 timer is more suitable for connection with logic chips.

If a pushbutton, rotational encoder, or electromechanical switch provides a high or low input, the input must be debounced. In hardware, this is traditionally done with a **flip-flop**. It can also be done with code in a microcontroller.

Analog Input

The input of a logic chip can be connected directly with a thermistor, phototransistor, or similar analog component, but only if there is some certainty that the voltage at the input pin will remain within the range that is acceptable to the chip. In the case of a phototransistor, for example, it should be exposed to a limited, known range of light intensity.

In general, it is best to avoid applying intermediate-voltage signals to a digital logic input, as they can create unpredictable output, or output of an intermediate voltage. A **comparator** can be placed between the analog source and the digital logic chip, or a logic chip with a Schmitt-trigger input can be used.

flip-flop

11

The term **flip-flop** is sometimes printed with a space instead of a hyphen, but the hyphenated form seems to predominate in the United States. Therefore, the hyphen is included here. The term *flipflop* (with neither a hyphen nor a space) is sometimes seen, but is unusual. The acronym *FF* is confined mostly to logic diagrams or schematics.

The term *latch* is sometimes used interchangeably with *flip-flop* but is assumed here to describe a minimal asynchronous circuit that responds immediately and transparently to an input. A flip-flop can function as a latch and also as a synchronous device which is opaque, meaning that the input does not flow directly through to the output.

OTHER RELATED COMPONENTS

- **counter** (see Chapter 13)
- **shift register** (see Chapter 12)

What It Does

Transistors enable logic gates; logic gates enable flip-flops; and flip-flops enable many mathematical, storage, and retrieval functions in digital computing. Most flip-flops today are embedded in much larger integrated circuits that have complex functions. However, they are still available as separate components in chip form, and will be discussed on that basis here.

A flip-flop is the smallest possible unit of memory. It can store a single bit of data, represented by either a high or low *logic state*. (A full explanation of logic states is included in the **logic gate** entry. See Chapter 10.) Flip-flops are especially useful in **counters**, **shift registers**, and *serial-to-parallel converters*.

A flip-flop circuit can be classified as a form of *bistable multivibrator*, as each of its outputs is stable in one of two states until an external trigger stimulates it to "flip" from one state and "flop" into the other. (For a comprehensive discussion of monostable and astable multivibrators, see the **timer** entry in Chapter 9.)

An *asynchronous* flip-flop will respond immediately to a change of input, and can be used for applications such as debouncing the signal from an electromechanical **switch** or building a *ripple* **counter**. More often, a flip-flop is *synchronous*, meaning that a change in input state will be unrecognized until it is enabled by a low-to-high or high-to-low transition in a stream of pulses from an external *clock*.

How It Works

Every flip-flop has two outputs, each of which may have a high or low state. When the flip-flop is functioning normally, the outputs will be in opposite logical states, one being high while the other is low. These outputs are typically identified as Q and NOT-Q (the latter term meaning a letter Q with bar printed above it, sometimes referred to verbally as "Q-bar"). In datasheets and other documents where a bar symbol cannot be represented easily above a letter, the NOT-Q output may be represented as letter Q with an apostrophe after it, as in Q′.

Almost always, in a schematic diagram, a flip-flop is represented by a simple rectangle, with inputs and outputs identified by letters and other marks. Because a description of the inner workings is necessary before the different types of flip-flop can be understood, schematic symbols for various flip-flops will not be introduced until "Variants" on page 116.

The simplest flip-flop contains two logic gates whose function can be most easily understood if the inputs are controlled by a SPDT switch. It can be created from two NAND gates or two NOR gates, as described next. This type of component can be described as:

- *asynchronous*: Will accept data on an impromptu basis, as it is not synchronized with a clock.
- *jam-type*: Colloquial equivalent of *asynchronous*. The input is jammed in at any time, forcing an immediate change of output.
- *transparent*: The input state flows straight through to the output.

NAND-Based SR Flip-Flop

Figure 11-1 shows two NAND gates attached to a SPDT switch, with two pullup resistors. When either of the NANDs has a floating input from the switch, the pullup resistor attached to that input will maintain it in a high state. The data inputs for the NAND gates are labeled S and R, meaning Set and Reset, giving this component its name as an *SR* flip-flop:

- In a NAND-based SR flip-flop, a low state is considered an active logic input, as indicated by the bar placed above each letter.
- A high state is considered an inactive logic output.

The schematic style in this figure, with diagonally crossing conductors, is universally used and easily recognizable. The equivalent schematic in Figure 11-2, which might be created by circuit-drawing software, has the same functionality but would not be immediately recognizable as a flip-flop. The "classic" crossed-conductor representation is preferable.



Figure 11-1. *The schematic for a simple NAND-based SR-type flip-flop, with a switch and pullup resistors added to control two inputs.*



Figure 11-2. *An alternative component layout for an SR flip-flop, functionally identical to the previous schematic, but not so easily recognizable. The layout with a pair of diagonally crossing conductors has become so ubiquitous, it should be considered to be a standard.*

The first step toward understanding the behavior of flip-flops is to recall the relationship between the two inputs and the output of NAND or NOR gates. This is shown in Figure 11-3, where red indicates a high logic state and black indicates a low logic state.



Figure 11-3. *The four possible input combinations for a NAND gate and a NOR gate, with the corresponding logical outputs. A flip-flop can be built from two NANDs or two NORs.*

The behavior of a NAND gate can be summarized:

- Both inputs high: Output low.
- Other input combinations: Output high.

Figure 11-4 shows a series of snapshots of the SR flip-flop circuit as the switch moves from one position, through an intermediate state where it makes no connection, to the other position. Remember that in this circuit, the active logical input state is low, and the active logical output state is high.

In the top panel, the pullup resistor of the lower NAND is overwhelmed by the direct connection to negative ground, which holds the R input in a low state. The other input of this gate is irrelevant, because the output from a NAND will be high if either of its inputs is low. So, the lower NAND has a high output, which feeds back to the secondary input of the upper NAND gate. The S input of this gate is high, because of the pullup resistor. Because both inputs of this gate are now high, its output is low, which feeds back to the lower gate. The lower gate doesn't change its output, because either of its low inputs is enough to keep its output high. So, the circuit is in equilibrium. A high state on the NOT-Q output is known as the *Reset* state for a NAND-based flip-flop.

The second panel shows what happens if the switch now moves up into a neutral, disconnected position. The R input of the lower NAND now becomes high, because of the pullup resistor. But this NAND still has one low input, supplied by the output of the upper gate, so its output remains high, and the circuit is still in equilibrium. This is known as the *Hold* state for the NAND circuit.

Suppose the switch bounces to and fro between the states shown in the first two panels. The output from the circuit won't change. This shows that the circuit provides a method for eliminating *switch bounce*—the very fast, momentary spikes that occur when the mechanical contacts of a switch open and close.

The third panel shows what happens if the switch now moves to its upper position. The top input of the upper NAND gate is now pulled low. Consequently, its output goes high. This feeds back to the lower gate. Its other input is high because of the pullup resistor. With both of its inputs high, its output goes low. The gate outputs have flipped and swapped values. A high state on the Q output is known as the *Set* state for a NAND-based flip-flop.

The circuit still remains in equilibrium even if the switch returns to its central, disconnected position shown in the bottom panel. Therefore, the debouncing capability of the circuit works equally well for both positions of the switch.

NOR-Based SR Flip-Flop

Figure 11-5 shows a similar circuit using two NOR gates attached to an SPDT switch. Because the NOR gates function differently, this circuit uses active-high input logic, and pulldown resistors are needed instead of pullup resistors. The output from the circuit still uses active-high logic, and is identical with the NAND-based circuit in this respect, although the relative positions of the Q and NOT-Q outputs have been swapped.


$\overline{S}$
NAND
Q
NAND
$\overline{Q}$
$\overline{R}$
$\overline{S}$
NAND
Q
NAND
$\overline{Q}$
$\overline{R}$
$\overline{S}$
NAND
Q
NAND
$\overline{Q}$
$\overline{R}$
$\overline{S}$
NAND
Q
NAND
$\overline{Q}$
$\overline{R}$

Figure 11-4. *Four snapshots of transitions in a NAND-based SR flip-flop as the switch moves down and up through an intermediate no-connection zone. See text for details.*

- In a NOR-based SR flip-flop, a high state is considered an active logic input, as indicated by the absence of a bar placed above the letters S and R.
- A high state is considered an active logic output.


S
NOR
Q
NOR
$\overline{Q}$
R

Figure 11-5. *The schematic for a simple SR flip-flop using NOR gates instead of NANDs.*

In the case of the NOR gate:

- Both inputs low: Output high.
- Other input combinations: Output low.

Figure 11-6 shows a series of snapshots as the switch moves from one position to the other, through intermediate states where it makes no connection. Remember that in this circuit, the active logical state is high at both the inputs and the outputs.

In this circuit, as in the previous circuit using NAND gates, it will ignore switch bounce, allowing the gate outputs to remain stable.

Forbidden States

Either of the circuits described so far depicts an SR flip-flop, regardless of whether it is NAND-based or NOR-based. Its input and output states are summarized in Figure 11-7. However, as this table suggests, there are some input states that create problems.



Figure 11-6. *Four snapshots of a NOR-based SR flip-flop, showing the consequence of changing switch positions, comparable with the NAND-based flip-flop.*

Flip-Flop Inputs		Flip-Flop Outputs			
		NAND-based		NOR-based	
S	R	Q	$\bar{Q}$	Q	$\bar{Q}$
●	●	🔴 Problem 🔴		Same as Previous	
●	🔴	🔴	●	●	🔴
🔴	●	●	🔴	🔴	●
🔴	🔴	Same as Previous		● Problem ●	

Figure 11-7. *A table of input states and the consequent output states for NAND-based and NOR-based SR flip-flops.*

In either the NAND-based flip-flop or the NOR-based flip-flop, the output when the switch is in its unconnected center position will remain the same as when the switch was in its previous position. This is the usefulness of the flip-flop: it remembers the previous state. These situations are identified as “Same as Previous” in the table.

The pullup resistors (in a NAND-based flip-flop) and pulldown resistors (in a NOR-based flip-flop) are intended to guarantee that both inputs will be high (NAND) or both inputs will be low (NOR) even when the switch makes no connection. Therefore, it should be impossible for both inputs to be low (NAND) or high (NOR).

But what happens if the circuit is powered up with the switch in the unconnected position? One input of each gate is controlled by the output of the other gate. But what will those outputs be?

In the NAND-based version, the outputs from the NANDs will be low while the chips are powering up. As soon as the NAND chips are functioning, each of them will sense that it has one input high and one input low, so it will change its output to high.

But now that each chip has a high output, it will feed back to the secondary input of the other chip. Now both chips have both inputs high. This will cause them both to change their outputs to low—but this will feed back again, flipping the outputs back to high again. In fact, if the gates are absolutely identical, the circuit will oscillate very rapidly. This is sometimes known as *ringing*.

In real life, the gates will not be absolutely identical, and eventually one of them will respond fractionally ahead of the other, tipping the circuit into the state shown either in the second panel or the fourth panel in Figure 11-4. But which chip will win? There is no way of knowing. This is known as a *race condition*, and the winner is unpredictable.

A similar but opposite situation occurs in the NOR-based flip-flop if it is powered up with the switch in the disconnected position, and the S and R outputs are both low, because of the pulldown resistors. Here again it will be a race condition.

We can address the problem by making a rule that the switch must always be in one position or the other when the flip-flop is powered up. But what if there is a faulty switch? Or what if a power interruption occurs while the switch is changing position?

Another problem occurs if the switch makes one contact a fraction before it breaks the other contact. This would result in both S and R inputs being low, in a NAND flip-flop. The same state could occur if a separate logic circuit is driving the S and R inputs, and an error causes it to make S and R both low. This is shown in Figure 11-8. Because the output from a NAND gate is always high if at least one of its inputs is low, both gates now have a high output, and the circuit is stable.

The problem is, the states of the outputs from a flip-flop should always be opposite to each other. If both of them are high, this can create logic problems in the rest of the circuit attached to the flip-flop.

- In a NAND-based SR flip-flop, if S and R are both low, this is known as a *forbidden state* or a *restricted combination*.



Figure 11-8. *What happens when both S and R inputs to a NAND flip-flop are low as a result of an error in a separate control circuit.*

A similar problem afflicts a NOR-based SR flip-flop, except that the forbidden state will occur when the S and R inputs are both high.

- In a NOR-based SR flip-flop, if S and R are both high, this is a *forbidden state* or a *restricted combination*.

The SR flip-flop is useful as a switch debouncer, but for computing applications, it is vulnerable to errors.

The JK Flip-Flop

Because the name of the JK flip-flop shares the initials of Jack Kilby, who won a Nobel prize for his fabrication of the world's first integrated circuit, some people speculate that this type of flip-flop was named after him. The attribution seems implausible, and may have gained currency simply because a flip-flop was the first device that Kilby happened to build when he was developing an integrated circuit.

Regardless of how it came to be named, the JK design is shown in Figure 11-9. This is commonly referred to as a JK *latch*. The electromechanical switches that were shown driving the SR flip-flop, along with pullup or pulldown resistors, are no longer included, because the inputs at positions J and K are assumed to come from other devices that have properly defined high and low states. Their behavior may be unpredictable, but neither of them will ever have a floating state.

This is a *gated* circuit, meaning that an additional input stage blocks direct access to the output stage, and it is also a *synchronous* circuit, as it uses a train of pulses at a clock input. Two three-input NAND gates are placed in front of a NAND-based SR flip-flop, and they address the problem of simultaneous identical inputs by using crossover feedback from the second stage to the first stage (via the conductors at top and bottom of the schematic).



Figure 11-9. *The basic circuit for a clocked JK flip-flop, using two additional NAND gates prepended to an SR flip-flop.*

Versions of a JK flip-flop are possible using NOR gates, but are less common. Only the NAND-based version will be considered here.

In the case of a three-input NAND gate:

- All three inputs high: Output low.
- Other input combinations: Output high.

Because of the additional pair of NANDs, the circuit now recognizes a high input as logically active, instead of the low-active input in the previous SR flip-flop using NAND gates. Consequently, two simultaneous high inputs might be expected to create the type of forbidden state that was caused by two simultaneous low inputs previously. However, in Figure 11-10, the top and bottom panels show that simultaneous high inputs at J and K will support two possible valid outputs, where the state at Q is always opposite to the state at NOT-Q. In fact, when both inputs are high, a positive pulse on the clock input will *toggle* the outputs (i.e., they will switch places). In fact, the toggling will continue so long as the clock input is high. Consequently, this type of flip-flop is intended for use with short clock pulses.



Figure 11-10. *When the J input and the K input are both high, this no longer causes a forbidden state. The combination will toggle the outputs of the flip-flop between the two states shown here.*

Master-Slave Flip-Flop

A more stable form is shown in Figure 11-11 where yet another stage has been added, this one being a "master" to the first. In fact, this configuration is known as a *master-slave* flip-flop, the slave stage being driven by the master stage but remaining inactive until a low clock input at the master stage passes through an *inverter* to become a high clock input at the slave stage. The master and slave stages thus take turns, one being activated by a high clock pulse while the other is activated by the low part of the pulse cycle. The output from the slave stage cannot feed back to the master stage while the clock pulse is still high, and thus the timing issue in the single-stage JK latch is eliminated. Because the master-slave version of the JK configuration is not *transparent*, it is correctly known as a flip-flop rather than a latch.

In addition, Preset and Clear inputs may be added to override the clock to Set or Reset the outputs. These inputs are active-low.

Figure 11-12 summarizes the behavior of a JK master-slave flip-flop that is triggered by the falling edge of each clock pulse (shown as a downward-pointing arrow in the Clock column of the table). Note that the output will be delayed while the slave stage waits for the second part of each clock cycle.

The letter X in the table indicates that the state in that cell is irrelevant.

When J and K are both low, the states of Q and NOT-Q will remain the same as in the previous cycle, and this is still referred to as a *Hold* state. When J and K are both high, the outputs toggle, meaning that their new states will be opposite to the previous states.

D-Type Flip-Flops

A D-type flip-flop places an inverter between two inputs to guarantee that they will always be in opposite states, and uses a clock signal to copy their states to a pair of logic gates.

When an inverter is added between the inputs in this way, either an SR flip-flop or a JK flip-flop can become a D-type flip-flop. Figure 11-13 shows the simplest possible D-type circuit, added to a basic SR flip-flop. Only one data input is now required (customarily labeled D), because it drives the other through the inverter.



Figure 11-11. *A master-slave circuit that drives one flip-flop with another.*

Flip-Flop Inputs					Outputs	
Clock	Preset	Clear	J	K	Q	$\overline{Q}$
X	⚫	🔴	X	X	🔴	⚫
X	🔴	⚫	X	X	⚫	🔴
↓	🔴	🔴	⚫	⚫	Same as Prev	
↓	🔴	🔴	⚫	🔴	⚫	🔴
↓	🔴	🔴	🔴	⚫	🔴	⚫
↓	🔴	🔴	🔴	🔴	Toggle	

Figure 11-12. *A table showing inputs and outputs for a JK master-slave flip-flop.*



Figure 11-13. *A simple D-type flip-flop. The inverter guarantees that the state of one input will always be opposite to the state of the other.*

Figure 11-14 uses snapshots to show how the circuit responds to changing input and clock conditions. Initially, in the top panel, the data input is high, the clock input is high, and the Q output is high. In the second panel, the clock goes low, causing the output from the upper NAND gate in the input stage to change from low to high. But the upper NAND gate in the output stage still has one low input, so its state remains unchanged. In fact, the S and R inputs of the output NANDs are now both high, which creates the hold condition.

In the third panel, the D input changes from high to low, but this has no effect so long as the clock is low. The D input can fluctuate repeatedly, and nothing will happen until the clock goes high, as shown in the fourth panel. Now the clock copies the new D input state through to the output.



Figure 11-14. *Four snapshots showing the behavior of a D-type flip-flop.*

Summary

- An SR flip-flop can be used for switch debouncing, but in other applications it can enter an unacceptable race condition if its inputs and power supply are not carefully controlled.
- A JK flip-flop is gated, meaning that an SR circuit is preceded with an input stage and a clock input. This eliminates the race condition, adds the ability to toggle the outputs, but requires a very brief clock input. The circuit is edge-triggered.
- A master-slave flip-flop consists of two flip-flops, one driving the other. They can be JK type or SR type. The first flip-flop is activated by a positive clock state, while the second is activated by the subsequent negative clock state. Timing issues are resolved.
- A D-type flip-flop is gated with an inverter between the inputs, so that they cannot be simultaneously high or low. Consequently, only one input, labeled D, is needed. A high state on the D input causes a Set condition, while a low input causes a Reset condition, but only when the clock copies the status of the inputs through to the outputs. The status of the outputs remains stable (the flip-flop enters a hold condition) after the clock goes low.
- The JK circuit used to be widely used, because of its versatility. The D-type circuit now predominates.
- A T-type (toggling) flip-flop exists but is uncommon, and is not included in this encyclopedia.
- Many flip-flop circuits exist in addition to the ones that have been illustrated here. Only the most commonly cited circuits have been included.

A chip containing two positive-edge triggered D-type flip-flops is shown in Figure 11-15. Each flip-flop in this component has its own data, set, and reset input and complementary outputs.



Figure 11-15. *This chip contains two positive-edge triggered D-type flip-flops.*

Variants

A selection of schematic symbols representing flip-flops is shown in Figure 11-16. Letters S, R, J, K, or D define the type of flip-flop. Q and NOT-Q are the outputs. CLK is the clock input but may alternatively be identified with letter E, meaning *Enable*. SRCK or SCLK may also identify it, the abbreviations being intended to mean “serial clock.

A triangle preceding CLK indicates that the flip-flop is positive-edge triggered. A circle, properly termed a *bubble*, preceding the triangle, indicates that the flip-flop is negative-edge triggered. In other locations, the bubble indicates that the input (or output) is inverted; it means the same thing as a bar printed above the text abbreviation, and indicates active-low logic. Synchronous inputs are shown on the left side of the flip-flop with the CLK input, while asynchronous inputs (if any) are shown above and below the flip-flop rectangle.

Using these guidelines, the examples in Figure 11-16 can be decoded:

1. An unclocked SR flip-flop with active-low inputs (probably NAND-based).
2. An unclocked SR flip-flop with active-high inputs (probably NOR-based).

3. An SR flip-flop with active-high inputs, pulse-triggered by an active-high clock input.
4. A JK flip-flop with active-high inputs, edge-triggered by a rising-edge clock input. The bubble on the lower Q output means the same thing as a letter Q with a bar printed above it.
5. A D-type flip-flop pulse-triggered by an active-low clock input.
6. A D-type flip-flop edge-triggered by a falling-edge clock input.
7. A JK flip-flop with active-high inputs, edge-triggered by a rising-edge clock input, with asynchronous active-low Preset and Clear inputs.



Figure 11-16. *The schematic symbol for a flip-flop is an annotated rectangle. See text for an explanation of the letters and marks.*

Packaging

Only about 10% of the flip-flops listed by a typical parts warehouse are through-hole chips. The rest are now surface-mount. Still, even if the search is narrowed further to through-hole packages in the 74xx and 4000 series, at least 100 types still exist. They provide opportunities in education and prototyping work, even though they are less often used as standalone components.

A package often contains more than one flip-flop. Dual and quad arrays are common. The flip-flops may be independently clocked, or may share a single clock input; datasheets should be checked carefully for details. Octal flip-flops, such as the D-type 74x273, are intended for use as eight-bit registers.

Many of the older flip-flops are numbered in the 74xx series of logic chips. See Chapter 10 for a detailed guide to this numbering system and the various logic families. D-type flip-flops include 74x74, 74x75, 74x174, and 74x175, where an acronym for the logic family is substituted for the x. Old-style CMOS flip-flops include the 4042B D-type latch, the 4043B quad NOR SR flip-flop, and the 4044B quad NAND SR flip-flop. The last two are synchronous, and both allow two Set inputs, labeled S1 and S2 in the datasheet.

Examples of JK flip-flops include the 74x73, 74x76, and 74x109.

Values

As is the case with other logic chips, most flip-flops in the through-hole 74xx series are intended for 5VDC power supply while the older 4000 series may tolerate up to 18VDC. Surface-mount versions may use voltages as low as 2VDC.

See "Variants" on page 93 for a discussion of acceptable high and low logic input voltages. On the output side, the 4000 series chips are able to source less than 1mA at 5VDC, but the 74HCxx series can manage around 20mA.

If a flip-flop is used for high-speed operation, the following values must be considered:

- t_S Setup time: The minimum time in nanoseconds for an input to be constant before the next clock pulse can process it.
- t_H Hold time: The minimum time in nanoseconds for an input to persist after the active edge of a clock pulse that has processed it. The interaction between a clock pulse and an input state takes a brief but measurable amount of time; errors may occur if the clock is given less than that amount of time to do its job.
- t_{CO} Clock-to-output: The elapsed time after an active clock edge, before the output changes. This is a function of the internal workings of the chip, and may be broken down into low-to-high and high-to-low output transitions, as follows.
- T_{PLH} Propagation to Low-to-High: The elapsed time after an active clock edge, before a low-to-high swing occurs at an output. This may not be identical to T_{PHL}.
- T_{PHL} Propagation to High-to-Low: The elapsed time after an active clock edge, before a high-to-low swing occurs at an output. This may not be identical to T_{PLH}.
- f_{MAX} Maximum clock frequency for reliable operation.
- $t_{W(H)}$ The minimum high clock pulse width in nanoseconds.
- $t_{W(L)}$ The minimum low clock pulse width in nanoseconds.

In a shift register or counter, where multiple flip-flops are cascaded but they share the same clock, the t_{CO} of one flip-flop must be shorter than the hold time of the next flip-flop, to allow the input of data to be complete before the window of opportunity is over.

How to Use It

The asynchronous SR flip-flop is of primary use in debouncing switches. Examples are the single MAX6816, dual MAX6817, and octal MAX6818.

D-type flip-flops are widely incorporated in frequency dividers, which are used to count pulses and display a binary output. If the NOT-Q output is wired back to the D input, the pulse stream to the clock input will have the following effect:

1. Suppose the initial D state is low and the initial state of the NOT-Q output is low.
2. The first high clock pulse propagates the low D state into the flip-flop.
3. The next low clock state forces the NOT-Q output high. This feeds back and creates a high D input.
4. The second clock pulse propagates the high D state into the flip-flop.
5. The next low clock state pulls the NOT-Q output low. This feeds back and creates a low D input.

The sequence then repeats. Only one high output is generated at NOT-Q (or at Q) for every two clock pulses; thus the circuit can become a divide-by-two **counter**. If the Q output is tapped to serve as the clock input for another flip-flop, that circuit now has a divide-by-four output. A series of many flip-flops can be chained together, so long as the propagation of signals along the chain is fast enough to occur before the next clock pulse. This is known as an *asynchronous counter*.

For more information on the use of counters, see Chapter 13.

While flip-flops have tended to be integrated with other components in digital computing, they are still used as registers where 8 or 16 bits of serial data must be assembled at a time, prior to being disseminated as parallel data.

What Can Go Wrong

Ambiguous Documentation

For reasons which are unclear, instructional texts and tutorials can be erratic when describing flip-flops:

- A truth table may fail to clarify whether the circuit uses active-high or active-low logic.
- Truth tables from different sources are often inconsistent in their representation of current and future output states, and may even fail to include the clock status in a clocked flip-flop.
- Tutorials may include logic diagrams for some types of circuit, but not others.
- NOR gates may be used, without any mention that NAND gates can also be used (and may be more common or convenient).
- The active-low or active-high status of inputs in an SR flip-flop may not be shown.

Bearing this in mind, manufacturer datasheets should be consulted whenever possible as the primary source of information.

Faulty Triggering

In many cases, a flip-flop designed for edge triggering can give erroneous results if it is level-triggered, and vice versa. Rising-edge-triggered flip-flops must be distinguished from falling-edge-triggered flip-flops. As always, it is important for similar parts that have similar functions to be stored separately.

Metastability

The behavior of flip-flops has been described in this entry under ideal conditions, where they are operating well within parameters established by the manufacturer. In reality, non-ideal scenarios may occur, especially where inputs such as data and clock, or clock and reset, are almost simultaneous. This may be difficult to avoid if a signal is received from an external source such as a sensor, with no way to control its arrival time. If the input occurs within the setup time or the hold time of a clock pulse, the flip-flop may be unable to determine whether the input precedes or follows the clock.

This may lead to *metastability*, meaning an unpredictable output and/or oscillations that take several clock cycles to settle into a stable state. If the output from a flip-flop may be used by two separate components with slightly different response times, one may interpret the oscillating output as a high state while the other interprets it as low. In a computing circuit, metastability can lead to calculation errors or a system crash. To avoid these issues, limits in datasheets should be observed. Attention should be paid to the manufacturer specifications for minimum setup time and hold time, so that the circuit has sufficient opportunity to recognize a signal and respond.

One solution to metastability is to connect multiple flip-flops in series, all sharing a common clock signal. This will tend to filter out irregularities, at the expense of requiring additional clock cycles if the flip-flops are not transparent.

Metastable-hardened flip-flops minimize metastability but cannot eliminate it completely.

Other Issues

Problems that tend to affect digital chips generally are listed in the section of the entry on logic gates (see “What Can Go Wrong” on page 105).

shift register

12

The term **shift register** is rarely hyphenated. In this encyclopedia, no hyphen is used.

A shift register can function as a *queue*, but this term is more usually applied to software. When the output from the last stage of a shift register is connected back to its input, it can function as a *ring counter*, but that application is described in the **counter** entry of this encyclopedia.

Component catalogs sometimes list shift registers as binary ripple **counters**, instead of giving them their own section. In this encyclopedia, a binary counter is considered to have binary-weighted outputs (with values 1, 2, 4, 8…. in decimal notation) and is described in the **counter** entry. A shift register has outputs that are not necessarily binary-weighted.

OTHER RELATED COMPONENTS

- **flip-flop** (see Chapter 11)
- **counter** (see Chapter 13)
- **multiplexer** (see Chapter 16)

What It Does

A *register* is a component (or a small section of computer memory) that stores information. The smallest unit of information is one *bit* (i.e., one *binary digit*) with a value 1 or 0 that can be represented by a high or low logic state. A **shift register** most commonly is designed to store eight bits, although some store four.

Each bit is memorized by the status of a **flip-flop** inside the register. For a detailed description of flip-flops, see Chapter 11. When a pulse from an external *clock* is received by the shift register, all of the bits in storage are moved along one step, from each flip-flop to the next. The high or low status of an input pin at that moment is *clocked in* to the first flip-flop, while the bit in the last flip-flop is overwritten by the bit preceding it. A diagram representing the function of a basic four-bit shift register is shown in Figure 12-1.

Note that the status of the input pin is ignored until the moment when a clock pulse copies it into the first flip-flop. In the figure, when the input pin has a brief high state that ends immediately before clock pulse three, the high state is ignored.

A shift-register chip is shown in Figure 12-2.

Because the functionality of a shift register is now often incorporated in much larger logic chips, it is less widely used as a stand-alone component than it used to be. It is still useful for purposes of serial-parallel or parallel-serial conversion, and for small tasks such as scanning a matrix-encoded keyboard or keypad. It also has educational applications and can be used in conjunction with a microcontroller.


Input pin
Flip-flop A
Flip-flop B
Flip-flop C
Flip-flop D
Initial state
Clock pulse 1
Clock pulse 2
Clock pulse 3
Clock pulse 4
Clock pulse 5

Figure 12-1. *The function of a four-bit shift register in which each flip-flop may be set to a high or a low state, represented here with red or black squares. After a high bit is clocked into the chip, it is moved one space along by each subsequent clock pulse.*


03DQ0HK
TPIC6596N

Figure 12-2. *This 8-bit shift-register chip is unusual in that it uses "power logic," in which open-drain outputs enable it to drive relatively high-current devices. It can sink up to 250mA at each of its output pins, at up to 45VDC.*

Schematic Representation

No specific symbol exists for a shift register. It is represented in a schematic by a simple rectangle, often (but not always) with control inputs on the left, data inputs arrayed along the upper edge, and data outputs along the lower edge. An example is shown in Figure 12-3, along with a diagram showing the physical chip and its pinouts. The meaning of the abbreviations identifying the inputs, outputs, and control functions will be described in "How It Works" on page 122.


SA
SB
CLK
CLR
74HC164
QA QB QC QD QE QF QG QH
SA
SB
QA
QB
QC
QD
GND
74HC164
V+
QH
QG
QF
QE
CLR
CLK

Figure 12-3. *Typical schematic representation of a shift register, compared with the pinouts of the actual component.*

The schematic symbol representing a shift register may appear superficially similar to the physical form of the chip which contains it, but the physical layout of the pins is unlikely to be the same.

How It Works

A shift register generally consists of a chain of D-type flip-flops. See the entry describing **flip-flops** in Chapter 11 for a detailed explanation of this component.

The simplest shift register functions as a *serial-in, serial-out* device, abbreviated with the acronym *SISO*. Because the first bit that enters it will be the first to leave at the opposite end, it can also be described as a *first-in, first-out* data storage device, using the acronym *FIFO*.

The basic connections between flip-flops in a four-bit SISO shift-register are shown in Figure 12-4. The D input in each section refers to the fact that it is a D-type flip-flop. The primary output from each flip-flop is identified with letter Q.



Figure 12-4. *The simplest shift register is a serial-in, serial-out (SISO) device. This example contains four D-type flip-flops.*

Each clock input is labeled CLK. When the output of each flip-flop is coupled to the input of the next flip-flop, and both share the same clock signal, the clock signal will cause the state of the third flip-flop to be sent to the fourth, the output of the second to be copied to the third, the output of the first to the second, and the input state will be copied to the first.

Abbreviations and Acronyms

The shift register will usually have an additional input that forces an immediate "clear" of all the registers, regardless of the clock state at that moment. This input is usually labeled CLR and will have a bar printed above it if it is active-low (which is the usual convention). If there is a pin labeled MR (meaning "Master Reset"), it will have the same function as CLR.

Because its effect is independent of the clock state, the clear signal is described as an *asynchronous* input.

While the abbreviation CLK is frequently used to identify the clock input, SCLK is also used (meaning "serial clock"), and occasionally the abbreviation CP may be found, meaning "clock pulse" input. If the shift register contains two stages, one to clock data in and the second to clock data out, they may be separately clocked, in which case they will be identified with different abbreviations. These are not standardized, but should be explained in the manufacturer's datasheet. No matter which abbreviation is used for a clock input, it will have a bar printed above it if the input is active-low.

Shift registers are generally *edge triggered*, meaning that the rising or falling edge of a clock pulse triggers the bit-shifting operation. If the component responds to a clock transition from low to high, it is *rising-edge triggered*. If it responds to a transition from high to low, it is *falling-edge triggered*, and this may be indicated in the schematic by a small circle, properly known as a *bubble*, preceding the triangle which indicates that this is an edge-triggered device.

Most shift registers are positive-edge triggered.

Parallel Outputs and Inputs

In many shift registers, data may be read out in parallel (from all flip-flops simultaneously), using pins provided for this purpose. In this mode, the shift register can function as a *serial-parallel converter* (*serial in, parallel out*, represented by the acronym *SIPO*). A simplified schematic of the internal connections is shown in Figure 12-5.

Where parallel outputs are provided, they are often identified as QA, QB, QC, and so on (moving from left to right) but may alternatively be described as Q1, Q2, Q3, Q4, and so on.

In a schematic, the input pin is conventionally shown as being at the left end of the component. Often two inputs are provided, connected internally as inputs to a NAND gate. The inputs are likely to be labeled A and B, but may alternatively be named SA and SB, indicating that they are serial inputs. S1 and S2 are alternative classifications. If parallel inputs exist, they may be identified as PA, PB, PC, and so on.



Figure 12-5. *Many shift registers have pins connected to points along the chain of flip-flops. These connections enable data to be read from the shift register in parallel.*

If serial data is supplied asynchronously, as in the illustration in Figure 12-1, it will be ignored until the shift register is triggered by the next clock pulse. The input state at that moment will then be copied into the first flip-flop, while the data that is already being stored in the shift register will be moved along the chain. In datasheets, this is customarily represented by a diagram such as the one in Figure 12-6. This diagram assumes that the shift-register is rising-edge triggered. Note that a brief fluctuation in the input which does not coincide with a clock-trigger event will be ignored.

Variants

Serial In, Serial Out

A basic SISO shift register allows only for serial input (at one end of the chain of flip-flops) and serial output (at the other end of the chain). No pins are available for parallel output of data.

This type of component usually permits 64-bit storage, where parallel output is simply impractical, as too many pins would be required. An example is the 4031B chip. This includes provision for recirculation of bits, so that it will also function as a ring counter (see Chapter 13 for a discussion of this function). As is always the case with logic chips, the part number will be preceded by letter(s) identifying the manufacturer, and a suffix will distinguish variants of the chip.

Another type of SISO shift register is programmable. It will store any number of bits from 1 through 64, determined by a binary number applied in the form of high/low states to five pins reserved for this purpose. An example is the 4557B.



Figure 12-6. *In a rising-edge-triggered shift register, the high or low state of an asynchronous input (purple line) is copied into the first flip-flop of a shift register by each clock pulse (orange line). Brief fluctuations that do not coincide with a rising clock pulse are ignored. Existing data in the register is shifted from one flip-flop to the next.*

Serial In, Parallel Out

The majority of serial-input shift registers allow parallel output from points along the chain in addition to serial output at the end of the chain. These chips almost all are 8-bit registers. Typically two inputs are provided, one of which can be used to receive bits that recirculate from the end of the chain, back to the beginning. Widely used examples are the 4094B and the 74x164, where an acronym identifying the logic family will be substituted for the x.

Parallel In, Serial Out

A minority of shift registers are able to function as *parallel-serial converters* (*parallel in, serial out*, represented by the acronym *PISO*). Typically this type of chip allows *jam-type* parallel data input, meaning that the data is forced into the flip-flops via a separate pin for each of them. Parallel input is enabled by the status of a serial/parallel control pin. When the control pin reverts to its opposite status, each clock pulse will now shift data along the chain of flip-flops, allowing it to be read from the final output one bit at a time. Thus, data can be entered into the chip in parallel and read out of it serially. Examples are the 4014B and 4021B. Both are 8-bit.

Parallel In, Parallel Out

Shift registers that permit parallel output in addition to parallel input are almost all of the *universal* type, described in the next section.

Universal

A *universal* shift register is capable of all four modes of operation: SISO, SIPO, PISO, and PIPO. The four modes of the component are selected by the high or low status of two *mode select* pins. In addition, this component may have the ability to shift the register states either left or right. A *bidirectional* shift register has this same capability, and may also have PISO and PIPO capability, depending on the chip. Examples are the 74x195 and 74x299, where an acronym identifying the logic family will be substituted for the x in the number.

Universal shift registers are almost all 4-bit or 8-bit. They often have relatively complicated features, such as access to internal JK flip-flops, or pins that are multiplexed to provide different functionality depending whether an enable pin is held high or low. Datasheets must be checked carefully to ensure correct use.

Dedicated shift registers of SIPO or PISO type will be easier to use.

Values

As is the case with other logic chips, most flip-flops in the through-hole 74xx series are intended for 5VDC power supply while the older 4000 series may tolerate up to 18VDC. Surface-mount versions may use voltages as low as 2VDC. See the section on logic gates in Chapter 10 for a discussion of acceptable high and low logic-input states. On the output side, the 4000 series chips are able to source less than 1mA at 5VDC, but the 74HCxx series can usually manage around 20mA.

If a shift register is used for high-speed operation, the following values must be considered (identical notation, and similar values, are found in specifications for flip-flops):

- t_S Setup time: The input state of a shift register must exist for a very brief period before the clock trigger that processes it. This period is known as the *setup time*. In the 4000 series of chips, recommended setup may be as long as 120ns. The value will be much lower in 74xx chips.
- t_H Hold time: The minimum time in nanoseconds for an input to persist after the active edge of a clock pulse that has processed it. In many shift registers, no hold time is necessary, as the chip has already been activated by the rising edge of the clock pulse.
- t_{CO} Clock-to-output: The elapsed time after a clock trigger, before the output changes. This is a function of the internal workings of the chip, and may be broken down into low-to-high and high-to-low output transitions, as follows.
- T_{PLH} Propagation to Low-to-High: The elapsed time after an active clock trigger, before a low-to-high swing occurs at an output. This may not be identical to T_{PHL}.
- T_{PHL} Propagation to High-to-Low: The elapsed time after an active clock trigger, before a high-to-low swing occurs at an output. This may not be identical to T_{PLH}.
- f_{MAX} Maximum clock frequency for reliable operation. In the older design of 4000 series chips, 3MHz may be recommended with a power supply of 5VDC. Higher frequencies are possible with a higher voltage power

supply. Frequencies as high as 20MHz are possible in the 5VDC 74HC00 series.

- $t_{W(H)}$ The minimum high clock pulse width in nanoseconds. In the older design of 4000 series chips, 180ns may be recommended with a power supply of 5VDC. Shorter pulses are possible with higher voltage power supply. Pulses as short as 20ns are possible in the 5VDC 74HC00 series.
- $t_{W(L)}$ The minimum low clock pulse width in nanoseconds. This is likely to be the same as $t_{W(H)}$.

Power Considerations

Shift registers conform with the usual power-supply requirements for logic families. These are described in detail in the **logic gate** entry in Chapter 10. Likewise, the ability of a shift register to source or sink current is usually determined by its logic family. In a few cases, however, shift registers have an additional *open-drain* output stage for each register, capable of sinking currents as high as 250mA. The Texas Instruments TPIC6596 shown in Figure 12-2 is an example. When an open-drain output is connected with a logic device whose input cannot be allowed to float indeterminately, a *pullup resistor* must be added.

Three-State Output

A chip may have a *three-state output* (also known as *tri-state output*, a term which was trademarked but is now used generically). This means it will be capable of changing its outputs so that instead of sourcing or sinking current in a logical high or low state, they can have a high impedance. The chip then becomes “invisible” to others which may be sharing the same output bus. The high-impedance state is usually applied to all outputs from the shift register simultaneously when enabled by a separate pin, often identified as *OE*, meaning *output-enable*. Examples of three-state shift registers are the 74x595 or the 4094B chip.

The high-impedance state can be thought of as being almost equivalent to switching the outputs of the shift register out of the circuit. Consequently, if other components sharing the bus are also in high-impedance output mode, the state of the bus will “float,” with uncertain results. To avoid this, a pullup resistor of 10K to 100K can be used on each bus-line.

Where the internal components of a shift register are shown in a datasheet, a three-state output is usually represented with a buffer symbol or inverter symbol that has an additional control input located on its upper edge, as shown in Figure 12-7. This should not be confused with the similar placement of a positive power supply input to an amplifier or op-amp. (Schematics showing the interior elements of a logic chip almost never include power-supply connections.)



Figure 12-7. *A shift register may be capable of a three-state output, where high impedance is an option additional to the usual high or low logic state. An output enable pin allows this. It is typically shown as an additional input to an inverter (left) or buffer (right) inside the shift-register chip.*

How to Use It

The SISO application of a shift register can be used simply to delay the transmission of data by storing it and moving it from one flip-flop to the next before it is read out of the end of the chain.

The SIPO application of a shift register (serial in, parallel out) may be useful where a microcontroller has insufficient outputs to control multiple devices. Serial data can be sent from a single microcontroller output to the input of a shift register. The chip can then drive a separate device from each of its parallel output pins. If there are eight devices, the microcontroller can send a sequence of eight bits, each of which will control the on/off status of one device when the bits are read out of the shift register in parallel. If more devices are used, an additional shift-register can be daisy-chained to the output from the first.

Clock signals can be supplied from the microcontroller, along with a signal to the clear input of the shift register, if desired. Alternatively, the old bit states in the shift register can simply be "clocked out" and replaced with a new set of serial data. During the process of "bit banging," the parallel outputs of the shift register can remain connected directly with the output devices if the clock speed from the microcontroller is fast enough, as devices such as relays will not respond to extremely brief pulses.

For generic shift registers that do not have open-drain outputs, a buffer will be needed to provide sufficient current for any device using more current than an LED.

If a shift register is configured for PISO mode (parallel in, serial out) it can be placed on the input side of a microcontroller, polling a variety of devices and feeding their states into the microcontroller serially.

Dual Inputs

Where a shift register has two serial inputs (as is often the case), they are almost always linked as inputs to an internal NAND gate. This allows the output from the end of the chain of flip-flops to be connected back to the beginning of the chain, if the shift register is to function as a ring counter. However, if this function is not used and a single input is required, the two inputs to the shift register can be tied together. In this configuration, the input becomes active-low. The two possible configurations are shown in Figure 12-8. It is important never to leave an input *floating*, or unconnected.



Figure 12-8. *Two possible configurations where a shift register allows two inputs linked with an internal NAND gate.*

Preloading the Shift Register

Where a shift register will be used to output a single recirculating bit (or in similar applications), the component must be preloaded with a high state in its first register. This may require a one-shot (monostable) timer which is activated only when the circuit is powered up.

Polling a Keyboard

Two shift registers can be used to scan the data lines in a matrix-encoded keyboard or keypad. This is often known as *polling* the keyboard. Provided the scan rate is sufficiently fast, the user experiences a seemingly immediate response to a key-press.

While the full schematic is too large and complex to be included here, many examples can be found online.

Arithmetical Operations

Shift registers were traditionally used to perform arithmetical operations on binary numbers. If the number is represented by eight bits (i.e., one byte) with the most significant digit on the left, shifting the bits one space to the right will have the effect of dividing the byte value by 2. If the bits are shifted one space to the left, the byte value will be multiplied by 2 (provided an additional register is available to store the most significant bit after it has been shifted). This concept is illustrated in Figure 12-9.



Figure 12-9. *In the upper section of this diagram, a binary number represented by eight bits in a shift register is multiplied by 2 by shifting all the bits one space to the left. In the lower section, the same binary number is divided by 2 by shifting all the bits one space to the right. The binary values are shown in decimal notation to the left.*

In the upper section of the figure, the binary number 10010110 (chosen arbitrarily) is represented in the eight flip-flops of a shift register. The decimal place value of each digit is indicated. Adding up the place values of the 1s in the number, the total is 128 + 16 + 4 + 2 = 150. Below the white line, the digits have been shifted one place to the left, with the leftmost digit carried over to an additional location, while a zero is inserted in the rightmost location. Assuming that the additional place at the leftmost location has a place value of 256, the total is now 256 + 32 + 8 + 4 = 300.

In the lower section of the figure, the same binary number has been shifted one space to the right, with a 0 introduced in the leftmost location. The decimal value is now 64 + 8 + 2 + 1 = 75.

While this application for shift registers was common during development of digital computing in the 1960s and 1970s, the shift register as a separate component became less common subsequently, as its functionality was acquired by modern CPU chips.

Buffering

A shift register may also be used as a *buffer* between two circuits where the clock speeds are different. Digits are clocked in by the first circuit, then clocked out by the second. Some shift registers allow two clock inputs and can be used for this purpose.

What Can Go Wrong

Problems that tend to affect digital chips generally are listed in the entry on logic gates (see "What Can Go Wrong" on page 105).

Confusing Classification

Because of the functional similarity to a binary ripple **counter**, a shift register is sometimes listed by component suppliers as a counter. In fact, a binary counter will almost always have outputs that have place values 1, 2, 4, 8.... and upward, while the outputs from a shift register will not have place values.

When searching for a shift register, it can be found by specifying a "counting sequence" of serial to parallel, serial to serial, parallel to serial, or parallel to parallel. If the "counting sequence" is simply up or down, the component is a counter, not a shift register.

Inadequate Setup Time

Each flip-flop in a shift register must have a stable input state before the next triggering event shifts the data. If this setup time is reduced below the minimum specified in the datasheet, results will be unpredictable.

Unconnected Input

Because many shift registers have a choice of two inputs to the same chain of internal flip-flops, it is easy to leave one of them unconnected by accident. A floating input will be vulnerable to any stray electromagnetic fields, and is almost certain to create random effects.

Output Enable Issues

The output enable pin on a shift register that has three-state logic outputs is usually active-low. Consequently, if the pin is left unconnected, the logic outputs may go into high-impedance mode, or will fluctuate unpredictably. Where three-state outputs are not required, a safe course of action will be to avoid using three-state chips.

Floating Output Bus

If a pullup resistor is omitted from a bus that is shared by three-state chips, the results will be unpredictable. Even if the circuit design seems to guarantee that at least one chip will have a high or low output on the bus, a pullup resistor should still be included.

counter

13

The term **counter** is used here to mean a digital-logic chip. A counter could be built from discrete transistors, but this approach is obsolete. Counters may also be devised from parts such as multiple relays, or a solenoid advancing a ratchet wheel, but such electromechanical devices are not included in this encyclopedia.

In this encyclopedia, a counter by definition has binary-weighted outputs with values 1, 2, 4, 8.... in decimal notation. The exception to this rule is a *ring counter*, which does not have binary-weighted outputs but is included here because its name identifies it as a counter. A **shift register** may be used as a ring counter, but is more versatile and has many other functions; hence it has a separate entry.

Gray code counters, in which successive outputs differ by only one binary digit, are not described in this encyclopedia.

OTHER RELATED COMPONENTS

- **flip-flop** (see Chapter 11)
- **shift register** (see Chapter 12)

What It Does

A counter can be used to count events, or can measure time in convenient intervals if it is connected with a component such as a *quartz crystal* that operates at a precise and reliable frequency. The counter receives input pulses (usually referred to as a *clock input*) and counts a predetermined number of them before restarting from the beginning. It will repeat in this fashion so long as power is connected, and the clock pulses continue, and a reset signal is not supplied.

Almost all counters create some form of output during the count. Most commonly, the output is a pattern of high and low states expressing the number of clock pulses in binary code. Where a counter counts to a very high number before recycling, some intermediate binary digits may be omitted.

While standalone counter chips are not as widely used now as in the early days of computing, they still find application in industrial processes, small devices, and education, and can be used to control incremental devices such as stepper motors. They can be used in conjunction with microcontrollers.

Schematic Representation

No specific logic symbol exists for a counter. It is most often shown in a schematic as a rectangle with clock input(s) and clear input(s) on the left and outputs on the right. An example appears in Figure 13-1, above a representation of the physical chip and its pinouts. The meaning of the abbreviations identifying the inputs, outputs, and control functions will be found in "How It Works" on page 132. Because the two MR inputs for this particular counter are ANDed inside the chip, the AND symbol is included with the counter symbol.



Figure 13-1. *Typical schematic representation of a counter, compared with the pinouts of the actual component.*

A counter chip is shown in Figure 13-2.



Figure 13-2. *The 74HC163 shown in this photograph is a 4-bit synchronous counter capable of being preloaded with a starting value, and able to do a synchronous reset.*

How It Works

A counter is built from a chain of **flip-flops**, with each one triggering the next. JK, T-type, or D-type flip-flops may be used. For a thorough description of a flip-flop, see Chapter 11. In Figure 13-3, a D-type flip-flop is shown, triggered by each rising clock pulse.



Figure 13-3. *When the complementary (NOT-Q) output from a D-type flip-flop is connected back to its input, the Q output frequency is half of the clock input frequency. See text for additional details.*

Initially the Q output of the flip-flop is low, so its NOT-Q output (identified by Q with a bar above it) is high. This feeds back to the D input, but has no effect until the rising edge of the next clock pulse copies the high D input to the Q output. The Q output is now latched high while the NOT-Q output is latched low and feeds back to the D input. The triggering event has passed, so the low D input does not have any immediate effect. The rising edge of the next clock pulse copies the low state of the D input to the output, and changes the NOT-Q output to high, causing the cycle to repeat. As a result, the output frequency of the flip-flop is one-half of the input frequency from the clock. If the output is carried to the next flip-flop to become its clock input, once again the frequency will be divided by two.

Modulus and Modulo

The *modulus* of a counter is the number it will count up to, before it repeats. This is sometimes written incorrectly as *modulo*.

In fact, *modulo* is the name of an arithmetical operation, often abbreviated as *MOD* (usually capitalized, even though it is not an acronym). This operation consists of a division sum in which the *remainder* from the division is the result of the operation. Thus 100 modulo 5 gives a result of 0, because there is no remainder when 100 is divided by 5. But 100 modulo 7 gives a result of 2, because 2 is the remainder of the division operation.

To exacerbate the confusion, *MOD* is also used as an adjective referring to the modulus of a counter. Thus a MOD-4 counter has a modulus of 4, and a MOD-16 counter has a modulus of 16. As a general rule, when a counter is being described, *modulo* and *MOD* will mean the same thing as *modulus*. This may be confusing to people such as computer programmers who are already familiar with the correct usage of MOD as an arithmetical operator.

In a counter, to obtain a modulus that is not a power of two, logic gates inside the chip can intercept a particular value (such as 1010 binary, which is 10 decimal) and use this as a signal to restart the count at zero. External connections to the chip can achieve the same purpose.

Pin Identifiers

Abbreviations and acronyms are used in datasheets to identify pin functions. These identifiers have not been standardized, and many variants exist.

CLK is the abbreviation most commonly used for the clock input, sometimes alternatively shown as CK or CP. If it is active-low, or if its falling edge will be active, a bar will be printed above it. Where a printed font does not permit an underscore to be placed in this way, CLK' (the abbreviation followed by an apostrophe) may be used instead. Often two or more stages of a counter can be separately clocked, and the input pins will be identified with abbreviations such as CLK1 and CLK2, or 1CLK and 2CLK, or CKA and CKB, or CP1 and CP2, or similar.

Where a clock input is edge-triggered, this is indicated by a small triangle. The triangle can be seen in Figure 13-3.

CLR designates a pin which will clear the count and reset it back to zero. This signal is often active-low, indicated by a bar printed above the abbreviation.

In a schematic, a small circle, properly known as a *bubble*, may be placed at any input which is active-low. On a clock input, the circle indicates that it is falling-edge triggered. See Figure 11-16 for various implementations of symbols with flip-flop schematics.

The CLR operation may be *synchronous* (the pin state will not be recognized until the next clock pulse) or *asynchronous* (in which case the pin state overrides the clock and resets the counter immediately). MR stands for "Master Reset," and has the same function as CLR.

Where two or more counters (or multiple stages within one counter) can be reset separately, more than one clear input will be shown, and may be identified with abbreviations such as CLR1 and CLR2, or MR1 and MR2.

Output pins will almost always be identified as Q0, Q1, Q2 … or QA, QB, QC … up to the maximum necessary to express the modulus. If two or more counters are included in one chip, outputs may be prefixed with an appropriate number. Thus 2Q3 would be the third output in the second counter. Multiple counters in one chip are identified with numbers starting from 1.

Where internal flip-flops are shown, they will have identifiers such as FF1 or FF2. Each flip-flop will have its own clear function, identified as C or CD (the latter meaning "clear data"), and may have inputs labeled D1, D2, D3… in a D-type flip-flop or J and K in a JK flip-flop. See Chapter 11 for an explanation of flip-flop inputs and outputs.

The input to a counter is always imagined to begin from the left, and consequently the leftmost flip-flop shown in an internal schematic will express the least significant bit of the current value of the count, even though a binary number is written with the least significant bit in the rightmost place.

If a counter is capable of receiving parallel data as an input (explained below) it will have a pin labeled PE for parallel enable. It may also have a CE or CET pin, for count enable.

As is generally the case in logic chips, VCC or V+ are typically used to identify the positive power supply pin, while GND or V- will identify the negative-ground pin. NC means that a pin has no internal connection at all, and consequently requires no external connection.

Variants

All counter chips use binary code internally, and the number of *bits* (*binary digits*) in the counter's modulus will be the same as the number of internal flip-flops. A 4-bit counter (the usual minimum) will have a modulus of 2^4 which is 16. A 21-bit counter (the maximum typically available) will have a modulus of 2^{21} which is 2,097,152. For higher moduli, counters can be chained together, each sending a carry signal to the next. This is known as a *cascade*.

Multiple counters, with different moduli, may be chained in a single chip. For example, in a digital clock that displays hours and minutes using the 60Hz frequency of an American domestic power supply as its timebase, the initial counting stage will have a modulus of 60, to count individual seconds. The next counting stages will have moduli of 60, 10, and 6, so that they can count from 00 to 59 minutes. Additional stages in the chip will tally hours.

A counter with a *parallel input* can be preloaded with an initial value (in binary code) from which it may count up or down. A *parallel-enable* pin may put the counter into a mode where the number can be *jam loaded*, meaning that it is jammed into the counter regardless of the clock state. Other types of counter are loaded synchronously.

Ripple versus Synchronous

In a *ripple counter* each internal flip-flop triggers the clock input of the next, so that their states change in a rapid but incremental sequence from the input to the output. This is also known as an *asynchronous* counter. Because the final state will not be valid until the clock pulse has rippled all the way through the counter (and through additional counters if they are cascaded together), a ripple counter will tend to suffer from a *propagation delay* of up to a microsecond. Ripple counters may also create output spikes or momentary transient count values that are invalid. Therefore, they are more suitable for applications such as driving a numeric display than for interfacing at high speed with other logic chips.

In a *synchronous counter*, all the flip-flops are clocked simultaneously. A synchronous counter is better suited to operation at high speed.

Of the counter chips available today, about half are synchronous and half are asynchronous.

Ring, Binary, and BCD

A counter that activates output pins one at a time sequentially is said to have a *decoded output*. It is often referred to as a *ring counter*. It has the same number of output pins as its modulus. An example is the 4017B chip.

A *binary counter* is more common and has an *encoded output*, meaning that it will express the running total of the count in binary code through *weighted outputs* that typically have (decimal) values of 1, 2, 4, 8, and so on. A modulus-8 counter (often referred to as an *octal counter*) will require three outputs which represent the binary numbers 000, 001, 010, 011, 100, 101, 110, and 111 (decimal 0 through 7) before going back to 000 and repeating.

A *modulus-16* counter, also known as a *hexadecimal counter* or a *divide-by-16 counter*, will have a binary output represented by four output pins, counting from 0000 through 1111 (decimal 0 through 15). Four-digit binary counters are very common, and their outputs are compatible with other components such as a **decoder**, which converts a binary-number input into a ring-counter-style output.

A *decade counter* is a modulus-10 binary counter. It is described as having a *binary-coded decimal* output (often expressed with the acronym *BCD*), using four weighted output pins which represent the numbers 0000, 0001, 0010, 0011, 0100, 0101, 0110, 0111, 1000, and 1001 (decimal 0 through 9) before repeating. Because this counter skips binary outputs from 1010 through 1111 (decimal 10 through 15), it is said to have a *shortened modulus*.

Figure 13-4 shows a schematic diagram of JK flip-flops in a decade ripple counter. The J and K inputs are all tied to the positive power supply, as this causes the clock input to toggle the output high and low. Note that because the primary input is always shown at the left end of the component, the least significant output bit (Q0) is in the leftmost position.

To intercept binary 1010 (decimal 10), an internal NAND gate is used. Its output goes low when its two inputs, from Q1 and Q3, go high. The output from the NAND immediately activates the CLR function on all the flip-flops, so that as soon as the decade counter reaches 1010 (decimal 10), it resets itself to 0.

In this particular chip, the preload for each flip-flop is tied to the positive power supply, so that it is always inactive. In some counters, the preload feature of each flip-flop is accessible via pins outside the chip. This creates the potential hazard of preloading the counter with one of the numbers that it normally skips (for instance, 11 decimal in a decade counter). This is referred to as an *invalid number* or *disallowed state*. (This use of the term "state" refers only to the binary number stored in the counter's flip-flops. It has nothing to do with the high-state or low-state voltages used to represent binary 0 or 1.)

The counter's datasheet should include a *state diagram* showing how the counter will deal with this situation. It may reset itself to a valid value after a maximum of two steps, but this can still cause confusion, depending on the application.

The state diagram for a 74HC192 counter is shown in Figure 13-5.



Figure 13-4. *The internal logic of a synchronous decade counter that uses JK flip-flops.*

Clock Sources

The clock input may be provided by a **timer** chip or by an *RC network*, which has the advantage of being able to run at a relatively low speed for purposes where this is desirable. It may alternatively be provided by a *quartz crystal* oscillating at a much higher frequency such as 1MHz. Successive counters may be necessary to reduce this value, depending on the application.

In some counters, the clock is built into the chip. More commonly, a resistor and capacitor may be used externally to establish a clock rate in conjunction with logic gates inside the chip. The datasheet for this type of component will include a formula for calculating the clock frequency from the resistor and capacitor values. The 4060B chip is an example.



Figure 13-5. *A state diagram shows the transitions that a counter will make from each number to the next (in decimal notation), including the transitions which enable it to exit from disallowed states. This example is for a 74HC192 chip.*

Rising Edge and Falling Edge

A counter may be designed to be triggered either by the rising edge or the falling edge of the clock input, or by its high or low logic state. Generally speaking, ripple counters use the falling edge, so that the final output from one counter can become the clock input of the next. In other words, when the most significant digit of the first counter changes from a high to low logic state, this transition toggles the least significant bit of the second counter.

Synchronous counters generally use the rising edge of the clock input. If multiple synchronous counters are cascaded, they must all share the same clock signal, and will all change their flip-flop states simultaneously.

Multiple Stages

It is common for a counter chip to contain two or more *stages* with differing moduli. To take a common example, a divide-by-2 stage and a divide-by-5 stage that are both present in a single chip can be used to create a decade counter by connecting external pins. The extra stages provide a choice of moduli if they are used individually.

Single and Dual

Counter chips may contain two counters of the same modulus. This is known as a *dual* counter. Dual 4-bit counter chips are common. Each counter can be used separately, or they can be cascaded, in which case the total modulus will be found by multiplying the individual moduli together.

High-State, Low-State, and Three-State

Almost all counters use positive logic where a 1 is represented by a high state and 0 by a low state. Some counters allow an additional output state which has a high impedance and is equivalent to an open circuit. This feature is useful when two or more chips share the same output bus. It is discussed in the entry for **shift registers** in "Three-State Output" on page 126.

Descending Output

Most components only create an ascending count. The output can be converted to a descending count by passing each binary state through an inverter, but this will only work properly if the modulus is equal to the number of states. In a BCD counter, its inverted outputs will count from decimal 15 to decimal 6, not from decimal 9 to decimal 0.

A few counters are available which are designed to create a correct descending count. Other counters are available which allow the user to set the mode to ascending or descending. Examples are the 74x190 or 74x192 (where an acronym for the chip family will be substituted for the letter x).

A descending output is useful in combination with a parallel input, where a user may set an initial value from which the counter will descend to 0. With suitable logic, this can enable a user-specified delay period.

Programmable Counters

A programmable counter can usually allow a modulus ranging from 2 to more than 10,000. The counter counts down by dividing an initial number repeatedly with a value that is preset with binary inputs. An example is the 4059B chip.

Examples

Many counter specifications date back to the 4000 family of logic chips. Versions of them subsequently became available in the 74xx series, often with the old 4000 part number preceded by 74x (where x is replaced by a designation of the logic family). For example, a version of the 4518B dual BCD chip can be obtained as the 74HC4518. As is the case with all logic chips, this part number will be preceded by letter(s) designating the particular manufacturer, with a suffix added to differentiate minor variants of the chip. The 74xx series has the advantage of higher speed and a greater ability to source or sink current at its output pins.

Most of the original CMOS chips, such as the 4518B, are still available, even in surface-mount versions. These offer the possible advantage of being able to use a higher power supply voltage.

Many counters offer multiple options such as different modulus values that can be selected by external pin connections. Some chips are tolerant of slow clock frequencies; others are not. Most are edge-triggered, but a few are level triggered. Some, such as the 4518B mentioned above, allow a choice of a rising-edge clock input and falling-edge clock input on different pins. For a specific application, it is really necessary to read a variety of datasheets to select the chip that is most suitable.

Values

As is the case with other logic chips, most counters in the through-hole 74xx series are intended for 5VDC power supply while the older 4000 series may tolerate up to 18VDC. Surface-mount 74xx versions may use voltages as low as 2VDC.

See the section on logic gates in Chapter 10 for a discussion of acceptable high and low logic-input states. On the output side, the 4000 series chips are able to source or sink less than 1mA at 5VDC, but the 74HCxx series can usually manage around 20mA.

A few counters are capable of delivering more power through additional output stages that can drive LEDs. The 4026B decade counter is still being manufactured, capable of powering modest 7-segment displays. The 4033B has the additional option of blanking any leading zeros in a multi-digit display. Other chips that were designed for direct connection to LED numerals have become obsolete as the need for this application has diminished. The 74C925, 74C926, 74C927, and 74C928 are examples. They may still be found from surplus outlets, but should not be specified in new circuit designs.

What Can Go Wrong

The entry that deals with problems affecting shift registers (see "What Can Go Wrong" on page 128), describes issues which also affect counters. The entry that deals with logic chips (see "What Can Go Wrong" on page 105), describes problems affecting all types of logic chips. In addition, the potential problems listed below are specific to counters.

Lock-Out

This is the condition which occurs if a counter with a shortened modulus is loaded with a binary state that is out of its range. Consult the datasheet and study its state diagram to determine the most likely outcome if this problem occurs.

Asynchronous Artifacts

Because the flip-flops in an asynchronous (ripple) counter do not change simultaneously, they create very brief false outputs while the ripple process is taking place. In a 4-bit counter, the binary number 0111 (decimal 7) should be followed by 1000 (decimal 8). However, the rightmost digit (i.e., the least significant bit) will change to a 0 initially, creating 0110 as a momentary binary output (decimal 6). The carry operation will then change the next digit to a 0, creating 0100 (decimal 4). The carry operation continues, changing the next digit to a 0, creating 0000. Finally the operation completes by creating 1000 as the correct output.

These intermediate states on the output pins are often referred to as *glitches*. Because they are extremely brief, they will be indetectable when a counter is used to drive a display. They can cause significant issues, however, if the outputs of the counter are connected with other logic chips.

Another type of asynchronous problem will occur if the clock speed is sufficiently high that a new pulse is received at the first flip-flop before the ripple of changing states has passed all the way through to the final flip-flop. This will result in a different brief invalid value on the output pins.

Noise

Old TTL-type counters, such as the 74LSxx series, are especially noise-sensitive. Adding a 0.1µF or 0.047µF bypass capacitor as close to the power supply pin as possible is recommended. Breadboarding counters of this type may result in errors if a high-frequency clock is used, because conductors such as patch-cords are liable to pick up noise. Modern 74HCxx counters are preferable.

encoder

14

In this encyclopedia, an **encoder** is a digital chip that converts a decimal-valued input into a binary-coded output.

The term "encoder" may alternatively refer to a **rotational encoder** (also known as a *rotary encoder*) which has a separate entry in Volume 1 of this encyclopedia. The term may also describe a *code hopping encoder*, which is an encryption device used in keyless entry systems for automobiles.

OTHER RELATED COMPONENTS

- **decoder** (see Chapter 15)
- **multiplexer** (see Chapter 16)

What It Does

An encoder is a *logic chip* that receives an input consisting of an active logical state on one of at least four input pins, which have decimal values from 0 upward in increments of 1. The encoder converts the active pin number into a binary value represented by logic states on at least two output pins. This behavior is opposite to that of a **decoder**.

Encoders are identified in terms of their inputs and outputs. For example:

- 4-to-2 encoder (four input pins, two output pins)
- 8-to-3 encoder (eight input pins, three output pins)
- 16-to-4 encoder (sixteen input pins, four output pins)

In the early days of computing, encoders processed interrupts. This application is now rare, and relatively few encoder chips are still being manufactured. However, they are still useful in small devices—for example, if a large number of inputs must be handled by a microcontroller that has insufficient pins to receive data from each individually.

Schematic Symbol

Like other logic-based components, the encoder does not have a specific schematic symbol and can be represented by a plain rectangle as in Figure 14-1, with inputs on the left and outputs on the right. The bars printed above some of the abbreviations indicate that an input or output is active-low. In this chip, the 74LS148, all inputs and outputs are active-low.

Generally speaking, inputs labeled D0, D1, D2… are used for data input, although they may simply be numbered, with no identifying letter. The encoded outputs are typically identified as Q0, Q1, Q2… or A0, A1, A2… with Q0 or A0 designating the least significant bit in the binary number.

Pins labeled E and GS are explained in the following section.



Figure 14-1. *While no specific schematic symbol exists for an encoder chip, this style is commonly used. Shown here is a 16–to–4 encoder with active-low inputs and outputs.*

Similar Devices

The similarities and differences between encoder, decoder, multiplexer, and demultiplexer can cause confusion.

- In an **encoder**, an active logic state is applied to one of four or more input pins, while the rest remain in an inactive logic state. The input pin number is converted to a binary code which is expressed as a pattern of logic states on two or more output pins.
- In a **decoder**, a binary number is applied as a pattern of logic states on two or more input pins. This value determines which one of four or more output pins will have an active logic state, while the rest remain in an inactive logic state.
- A **multiplexer** can connect a choice of multiple inputs to a single output, for data transfer. The logic state of an enable pin, or a binary number applied as a pattern of logic states to multiple control pins, chooses which input should be connected with the output pin. The alternative term *data selector* evokes the function of this device more clearly.
- An analog multiplexer may allow its inputs and outputs to be swapped, in which case it becomes a **demultiplexer**. It can connect a single input to one of multiple outputs, for data transfer. The logic state of an enable pin, or a binary number applied as a pattern of logic states to multiple control pins, chooses which output should be used. The alternative term *data distributor* evokes the function of this device more clearly.

How It Works

An encoder contains **logic gates**. The internal logic of an 8-to-3 encoder is shown in Figure 14-2, where the darker blue rectangle represents the chip. The switches in this figure are external and are included only to clarify the concept. An open switch is imagined to provide an inactive logic input, while a single closed switch provides an active logic input. (Multiple active inputs can be handled by a *priority encoder*, described below).

Each input switch has a numeric status from 1 to 7. The switch with value 0 does not make an internal connection, because the output from the OR gates is 000 by default.

The logic state of each OR output represents a binary number, weighted with decimal values 1, 2, and 4, as shown at the bottom of the figure. Thus, if switch 5 is pressed, by tracing the connections it is clear that the outputs of OR gates 4 and 1 become active, while the output from gate 2 remains inactive. The values of the active outputs thus sum to 5 decimal.

Figure 14-3 shows the outputs for all possible input states of a 4-to-2 encoder. Figure 14-4 shows the outputs for all possible input states of an 8-to-3 encoder. These diagrams assume that a high logic state is an active logic state, on input or output. This is usually the case.


Inputs
7
6
5
4
3
2
1
0
4
2
1
Binary-coded Outputs

Figure 14-2. *A simplified simulation of the internal logic of an 8-to-3 encoder. The dark blue rectangle indicates the space inside the chip. The external switches are included only to clarify the concept. An encoder chip would have an Enable line to create an active output.*


First-of-four input
Encoder
Binary 00 output
Second-of-four input
Encoder
Binary 01 output
Third-of-four input
Encoder
Binary 10 output
Fourth-of-four input
Encoder
Binary 11 output

Figure 14-3. *The four possible inputs of a 4-to-2 encoder (top of each panel) and the encoded outputs (below).*


First-of-eight input
Encoder
Binary 000 output
Second-of-eight input
Encoder
Binary 001 output
Third-of-eight input
Encoder
Binary 010 output
Fourth-of-eight input
Encoder
Binary 011 output
Fifth-of-eight input
Encoder
Binary 100 output
Sixth-of-eight input
Encoder
Binary 101 output
Seventh-of-eight input
Encoder
Binary 110 output
Eighth-of-eight input
Encoder
Binary 111 output

Figure 14-4. *The eight possible inputs of an 8-to-3 encoder (at the top of each panel), and the encoded outputs (below). Note that one input of an encoder must always be logic-high. All logic-low inputs are not a valid state.*

Unlike ripple counters, where propagation delays can reduce the overall response time of the component, decoders respond within two or three nanoseconds.

Variants

A *simple encoder* assumes that only one input pin can be logically active at a time. A *priority encoder* assigns priority to the highest-value input pin if more than one happens to receive an active input. It ignores any lower-value inputs. An example is the 74LS148, which is an 8-to-3 chip.

A few encoders feature *three-state* outputs (also known as *tri-state*), in which a high-impedance or "floating" output state is available in addition to the usual high and low logic states. The high-impedance state allows multiple chips to share an output bus, as those that are in high-impedance mode appear to be disconnected. This is useful if two or more encoders are cascaded to handle a larger number of inputs.

Values

As is the case with other logic chips, most encoders in the through-hole 74xx series are intended for 5VDC power supply while the older 4000 series may tolerate up to 18VDC. Surface-mount versions may use voltages as low as 2VDC.

See the section on logic gates in Chapter 10 for a discussion of acceptable high and low input states. On the output side, the 4000 series chips are able to source less than 1mA at 5VDC, but the 74HCxx series can manage around 20mA.

How to Use It

Suppose that a microcontroller should respond to an eight-position rotary switch. Because the switch cannot be turned to more than one position at a time, all of its eight contacts can be connected with the inputs on an encoder, which will deliver a 3-bit binary number to three inputs of the microcontroller. Code inside the microcontroller then interprets the pin states.

This is shown in Figure 14-5. Pulldown resistors would be needed on the input pins of the encoder, to prevent them from floating when they are not connected by the rotary switch. They have been omitted from this diagram for simplicity. Debouncing the switch would be handled by the microcontroller.

Other forms of input may be used instead of a rotary switch. For example, the outputs from eight comparators or eight phototransistors could be passed through an encoder.



Figure 14-5. *Output from an eight-input rotary switch could be connected through an 8-to-3 encoder to provide input to a microcontroller using a reduced number of pins. Pulldown resistors have been omitted for simplicity.*

Cascaded Encoders

Encoders are often provided with features to facilitate handling additional inputs via multiple chips. Typically, a second Enable pin is provided, as an output that connects with the Enable input of the preceding chip. This preserves the priority function, so that an input on the second chip prevents any additional input to the first chip from affecting the output. In a datasheet, the enable pins may be labeled E_{IN} and E_{OUT}, or E_I and E_O.

In addition, a GS pin will be included, meaning "Group Select." It is logically active only when the encoder is enabled and at least one input is active. The GS pin of the most-significant encoder provides an additional binary digit.

The outputs from two encoders can be linked via OR gates, as shown in Figure 14-6, where the lower chip's GS output provides the most significant bit of a four-bit binary number.


D0
D1
D2
D3
D4
D5
D6
D7
E_IN
E_OUT
GS
MC14532
Q0
Q1
Q2
Q0
Q1
Q2
Q3
D8
D9
D10
D11
D12
D13
D14
D15
E_IN
E_OUT
GS
MC14532
Q0
Q1
Q2

Figure 14-6. *Two eight-bit encoders can be cascaded to handle 16 separate inputs. In this example, the encoders use active-high logic.*

What Can Go Wrong

Problems that are common to all digital chips are summarized in the section on logic gates in "What Can Go Wrong" on page 105.

See "What Can Go Wrong" on page 149 in the entry describing **decoders** for a list of more specific problems that also afflict encoders.

decoder

15

In this Encyclopedia, a **decoder** is a digital chip that receives a binary-coded input and converts it to a decimal output by applying a logic state to one of a sequence of pins, each of which is assigned an integer value from 0 upward.

The term "decoder" also refers to components and devices that have other functions, such as decoding audio or video formats. These functions are not included here.

OTHER RELATED COMPONENTS

- **encoder** (see Chapter 14)
- **multiplexer** (see Chapter 16)

What it Does

A decoder receives a binary-coded number on two or more input pins. It *decodes* that number and expresses it by activating one of at least four output pins.

The behavior of a decoder with a two-bit binary input is shown in four sequential snapshots in Figure 15-1, where the least significant bit of the input is on the right in each diagram, and the output moves from right to left.

Figure 15-2 shows a similar sequence in a decoder where various values of a three-bit input are decoded to create an eight-pin output.

One sample state of a four-bit decoder is shown in Figure 15-3.

All of these figures assume that a high state represents an active input or output. In a few chips, a low state is used to represent an active output.

Decoders with 2, 3, or 4 input pins are common. To handle a binary input greater than 1111 (decimal 15), decoders can be chained together, as described below.

Manufacturers' datasheets often describe decoders in terms of their inputs and outputs. Typical examples would include:

- 2-to-4 decoder (two input pins, four output pins)
- 3-to-8 decoder (three input pins, eight output pins)
- 4-to-10 decoder (for converting *binary-coded decimal* to decimal output)
- 4-to-16 decoder (also known as a *hex decoder*).

Input Devices

The input pins of a decoder can be driven by a counter that has a binary-coded output. A decoder can also be driven by a microcontroller, which may have an insufficient number of output pins to control a variety of devices. Two, three, or four of the outputs can be used to represent a binary number which is passed through the decoder to activate the devices one at a time, perhaps with transistors or Darlington arrays introduced to handle the load. This is suggested in Figure 15-4.

A **shift register** can be used for a similar purpose, but often has only one pin for input. This pin must be supplied sequentially with a serial pattern of bits that will match the desired high/low states of the output pins. The relative advantage of this system is that a shift register can generate any pattern of output states. A one-of-many decoder can activate only one output at a time.

LED Driver

A special case is a *seven-segment decoder* designed to drive a seven-segment **LED display** numeral. A binary-coded decimal number on four input pins is converted to a pattern of outputs appropriate for lighting the segments of the display that will form a number from decimal 0 through 9.

Schematic Symbol

Like other logic-based components, the decoder does not have a specific schematic symbol and is represented by a plain rectangle as in Figure 15-5, with inputs on the left and outputs on the right. The bars printed above the E and LE abbreviations (which stand for Enable and Latch Enable, respectively) indicate that they are active-low. In this chip, the 74HC4514, all outputs are active-high, but in a related 4-to-16 decoder, the 74HC4515, all outputs are active-low. In both of these chips, the Enable pin is held low to activate the outputs. The Latch Enable pin freezes the current state of the outputs (i.e., it latches them) when it is held low.

Generally speaking, pins labeled A0, A1, A2… in a datasheet are often the binary inputs (although A, B, C… may be used), with A0 designating the least significant bit. Outputs are usually labeled Y, and are activated in sequence from Y0 when the binary input starts counting upward.

Similar Devices

The similarities and differences between encoder, decoder, multiplexer, and demultiplexer can cause confusion.

- In a **decoder**, a binary number is applied as a pattern of logic states on two or more input pins. This value determines which one of four or more output pins will have an active logic state, while the rest remain in an inactive logic state.
- A **multiplexer** can connect a choice of multiple inputs to a single output, for data transfer. The logic state of an enable pin, or a binary number applied as a pattern of logic states to multiple control pins, chooses which input should be connected with the output pin. The alternative term *data selector* evokes the function of this device more clearly.
- An analog multiplexer may allow its inputs and outputs to be reversed, in which case it becomes a **demultiplexer**. It can connect a single input to one of multiple outputs, for data transfer. The logic state of an enable pin, or a binary number applied as a pattern of logic states to multiple control pins, chooses which output should be used. The alternative term *data distributor* evokes the function of this device more clearly.


Binary 00 / Decimal 0 input
Decoder
3
2
1
0
Output
Binary 01 / Decimal 1 input
Decoder
3
2
1
0
Output
Binary 10 / Decimal 2 input
Decoder
3
2
1
0
Output
Binary 11 / Decimal 3 input
Decoder
3
2
1
0
Output

Figure 15-1. *A decoder with two input pins can interpret their binary-number representation to create an active logic state on one of four output pins.*


Binary 000 / Dec. 0 input
Decoder
First-of-eight output
Binary 001 / Dec. 1 input
Decoder
Second-of-eight output
Binary 010 / Dec. 2 input
Decoder
Third-of-eight output
Binary 011 / Dec. 3 input
Decoder
Fourth-of-eight output
Binary 100 / Dec. 4 input
Decoder
Fifth-of-eight output
Binary 101 / Dec. 5 input
Decoder
Sixth-of-eight output
Binary 110 / Dec. 6 input
Decoder
Seventh-of-eight output
Binary 111 / Dec. 7 input
Decoder
Eighth-of-eight output

Figure 15-2. *A decoder with three input pins can interpret their binary-number representation to create a high logic state on one of eight output pins.*


Binary 1101 / Decimal 13 input
Decoder
Output

Figure 15-3. *A decoder with four input pins can interpret their binary-number representation to create a high logic state on one of 16 output pins. Only one of the 16 possible states is shown here.*


Microcontroller or counter
Decoder
Darlington array
Darlington array
16
14
12
10
8
6
4
2
15
13
11
9
7
5
3
1
Up to 16 devices

Figure 15-4. *Four outputs from a binary counter or microcontroller can be used by a decoder to activate one of up to 16 output devices.*

A photograph of a 74HC4514 decoder chip appears in Figure 15-6.


74HC4514
$\overline{E}$
$\overline{LE}$
A0
A1
A2
A3
Y0
Y1
Y2
Y3
Y4
Y5
Y6
Y7
Y8
Y9
Y10
Y11
Y12
Y13
Y14
Y15

Figure 15-5. *While no specific schematic symbol exists for a decoder chip, this style is commonly used. Shown here is a 4-to-16 decoder.*



Figure 15-6. *The 24-pin 74HC4514 decoder chip processes a 4-bit input and represents it by making one of its 16 output pins active-high.*

How It Works

A decoder contains logic gates, each of which is wired to respond to a unique binary pattern of inputs. (In the case of a seven-segment decoder, the internal logic is more complicated.) Figure 15-7 shows the logic of a 2-to-4 decoder. The darker blue area contains the components inside the chip. The external switches are included only to clarify the function of the decoder. An open switch is imagined to provide a low logic input, while each closed switch provides a high logic input.

Unlike ripple counters, where propagation delays can reduce the overall response time of the component, decoders function within two or three nanoseconds.

Variants

Decoder variants have not proliferated with time, and relatively few are available. Most are 3-to-8, 4-to-16, and binary-coded-decimal types.

The 7447 and 74LS47 are seven-segment decoders that have an open-collector output capable of driving a 7-segment display directly. The 7448 is similar but also contains built-in resistors and a capability to blank out leading zeros in a display. However, some suppliers now list the 74LS48 as obsolete. It may be still available from old stock, but should not be specified in new circuits.



Figure 15-7. *A simplified simulation of the logic in a decoder. An actual chip would have an Enable line to activate the output. The dark blue rectangle indicates the space inside the chip.*

Although 74LS47 is still being manufactured, and is available in surface-mount as well as through-hole format, a version is not available in the widely used HC family of 74xx chips. Care must be taken to satisfy the input voltage requirements of the 74LS47 when driving it with 74HCxx chips.

Values

As is the case with other logic chips, most decoders in the through-hole 74xx series are intended for 5VDC power supply while the older 4000 series may tolerate up to 18VDC. Surface-mount versions may use voltages as low as 2VDC.

See the section on logic gates in Chapter 10 for a discussion of acceptable high and low input states. On the output side, the 4000 series chips are able to source or sink less than 1mA at 5VDC, but the 74HCxx series can manage around 20mA.

How to Use It

The original applications for decoders in computer circuits have become uncommon, but the chips can still be useful in small appliances and gadgets where multiple outputs are controlled by a **counter** or microcontroller.

Although 16 is usually the maximum number of outputs, some chips are designed to allow expansion. The 74x138 (where a chip family identifier such as LS or HC can be substituted for the letter x) is a 3-to-8 decoder with two logic-low Enable pins and one logic-high Enable. If a value-8 binary line is applied to the low-enable of one chip and the high-enable of another, the first chip will be disabled when the line goes high to indicate that the binary number 1000 has been reached, and the second chip can continue upward from there by sharing the same three less-significant-bit inputs. As many as four chips can be chained in this way.

What Can Go Wrong

Problems that are common to all digital chips are summarized in the section on logic gates in "What Can Go Wrong" on page 105.

Glitches

Although a decoder typically functions faster than a ripple counter, it suffers the same tendency to introduce brief *glitches* in its output. These are momentary invalid states which occur while processes inside the chip that are slightly slower are catching up with other processes that reach completion slightly faster. A brief *settling time* is necessary to ensure that the output is stable and valid. This will be irrelevant when powering a device such as an **LED indicator**, which will not display such brief transients. The problem may be more important if the output from the decoder is used as an input to other logic chips.

If the input to a decoder is derived from a ripple counter, the input may also contain glitches, which can cause erroneous outputs from the decoder. It is better to use a synchronous counter on the input side of a decoder.

Unhelpful Classification

Online parts suppliers tend to list decoders under the same category heading as encoders, multiplexers, and demultiplexers, making it difficult to find what you want. Under this broad subject heading (which will include thousands of chips), if you search by selecting the number of inputs relative to the number of outputs that you have in mind, this will narrow the search considerably.

Active-Low and Active-High

Chips with identical appearance and similar part numbers may have outputs that are either active-low or active-high. Some may offer a latch-enable pin, while others have enable pins that must be pulled low or forced high to produce an output. Accidental chip substitution is a common cause of confusion.

multiplexer

16

May be abbreviated as a *mux* (this term is sometimes printed all in caps), and may be referred to alternatively as a *data selector*. Some sources maintain that a multiplexer has no more than two channels, whereas a data selector has more, but there is no consensus on this, and datasheets continue to use the term "multiplexer" predominantly.

Analog multiplexers are usually bidirectional, and thus will function equally well as *demultiplexers*. Consequently, this encyclopedia does not contain a separate entry for demultiplexers.

OTHER RELATED COMPONENTS

- **encoder** (see Chapter 14)
- **decoder** (see Chapter 15)

What It Does

A multiplexer can select one of two or more input pins, and connect it internally with an output pin. Although it is an entirely solid-state device, it behaves as if it contains a **rotary switch** in series with a SPST switch, as shown in Figure 16-1. A binary code applied to one or more Select pins chooses the input, and an Enable pin establishes the connection with the output. The Select and Enable functions are processed via an internal section referred to as a *decoder*, not to be confused with a **decoder** chip, which has its own entry in this encyclopedia.

All multiplexers are digitally controlled devices, but may be described as either *digital* or *analog* depending how they process the input signal. A digital multiplexer creates an output that is adjusted to logic-high or logic-low within the limits of its logic family. An analog multiplexer does not impose any processing on the voltage, and passes along any fluctuations. Thus, it can be used with alternating current.



Figure 16-1. *A multiplexer functions as if it contains a rotary switch. The switch position is determined by a binary number applied to external Select pins. The internal connection is completed by applying a signal to an Enable pin.*

Because an analog multiplexer merely switches a flow of current, it can be *bidirectional*; in other words, it can function as a *demultiplexer*, in which case the input is applied to the pole of the (imaginary) internal switch and outputs are taken from the terminals.

Differential Multiplexer

A *differential* multiplexer contains multiple switches that are differentiated from one another (i.e., they are electrically isolated, although they are controlled by the same set of select pins). A differential multiplexer is conceptually similar to a rotary switch with two or more decks controlled by a single shaft. See Figure 16-2.



Figure 16-2. *A differential multiplexer contains two or more electronic switches that are differentiated from one another, similarly to the decks on a rotary switch. Although the channels into each switch are typically numbered from 0 upward, the switches are numbered from 1 upward.*

A bidirectional dual 4-channel differential analog multiplexer is shown in Figure 16-3.

Modern multiplexers are often found switching high-frequency data streams in audio, telecommunications, or video applications.

Similar Devices

The similarities and differences between multiplexer, demultiplexer, encoder, and decoder can cause confusion:

- A **multiplexer** can connect a choice of multiple inputs to a single output, for data transfer. The logic state of an enable pin, or a binary number applied as a pattern of logic states to multiple control pins, chooses which input should be connected with the output pin. The alternative term *data selector* evokes the function of this device more clearly.
- An *analog* multiplexer may allow its inputs and outputs to be reversed, allowing it to become a **demultiplexer**, connecting a single input to one of multiple outputs, for data transfer. The logic state of an enable pin, or a binary number applied as a pattern of logic states to multiple control pins, chooses which output should be used. The alternative term *data distributor* evokes the function of this device more clearly.



Figure 16-3. *This CMOS chip contains two four-channel differential analog multiplexers.*

- In an **encoder**, an active logic state is applied to one of four or more input pins, while the rest remain in an inactive logic state. The input pin number is converted to a binary code which is expressed as a pattern of logic states on two or more output pins.
- In a **decoder**, a binary number is applied as a pattern of logic states on two or more input pins. This value determines which one of four or more output pins will have an active logic state, while the rest remain in an inactive

logic state. A digital multiplexer does not allow reversal of its inputs and outputs, but a decoder functions as if it were a digital demultiplexer.

How It Works

The multiple inputs to a multiplexer are referred to as *channels*. Almost always, the number of channels is 1, 2, 4, 8, or 16. A 1-channel component is only capable of "on" or "off" modes and functions similarly to a SPST switch.

If there are more than two channels, a binary number will determine which channel is connected internally. The number of channels is usually the maximum that can be identified by the number of select pins, so that 2 pins will control 4 channels, 3 pins will control 8 channels, and 4 pins (the usual maximum) will control 16 channels.

In multiplexers with three or more channels, an enable pin is usually still present to activate or deactivate all the channels simultaneously. The enable feature may be described alternatively as a *strobe*, or may have an inverse function as an *inhibit* pin.

Although a rotary switch is helpful in conceptualizing the function of a multiplexer, a more common representation (sometimes in datasheets) is an array of SPST switches, each of which can be opened or closed by the decoder circuit. A typical example, depicting a dual differential multiplexer, is shown in Figure 16-4. Note that the internal decoder can only close one switch in each channel at a time.

The switch analogy is appropriate in that when an output from a multiplexer is not connected internally (i.e., its switch is "open") it is effectively an open circuit. However, some multiplexers contain *pullup resistors* to give each output a defined state. This can be an important factor in determining whether the multiplexer is suitable for a particular application.



Figure 16-4. *The internal function of a dual multiplexer is commonly represented as a network of SPST switches, each of which is controlled by decoder logic.*

A digital multiplexer actually contains a network of logic gates, shown in simplified form in Figure 16-5.

A demultiplexer has internal logic shown in simplifier form in Figure 16-6.

Schematic Symbol

In a schematic, a multiplexer and demultiplexer may be represented by a trapezoid with its longer vertical side oriented toward the larger number of connections. This is shown in Figure 16-7. However, this symbol is falling into disuse.

More often, as is the case with most logic components, a multiplexer or demultiplexer is represented by a rectangle with inputs on the left and outputs on the right, as shown in Figure 16-8. The distinction between inputs and outputs is problematic, however, in an analog multiplexer which will allow data flow to be reversed.


In 0
In 1
In 2
In 3
AND
AND
AND
AND
OR
Out
Decoder
Select
Enable

Figure 16-5. *A simplified representation of the logic gates in a digital multiplexer.*


In
AND
AND
AND
AND
Out 0
Out 1
Out 2
Out 3
Decoder
Select
Enable

Figure 16-6. *A simplifier representation of the logic gates in a digital demultiplexer.*

Pin Identifiers

The lack of standardization in the identification of pin functions is perhaps more extreme in the case of multiplexers than for other types of logic chips.


In 0
In 1
In 2
In 3
Out
Select
In
Out 0
Out 1
Out 2
Out 3
Select

Figure 16-7. *The traditional symbol for a multiplexer (left) and demultiplexer (right). The trapezoid is oriented with its longer vertical side facing the larger number of connections. This symbol is falling into disuse.*


E
X0
X1
X2
X3
Y0
Y1
Y2
Y3
CD4052B
X
Y
B
A

Figure 16-8. *A simple rectangle is most often used as a schematic symbol for a multiplexer, but the abbreviations assigned to pin functions are not standardized. See text for details.*

An output enable pin will be shown as E or EN, or occasionally OE. It may alternatively be described as an inhibit pin, labeled INH, or sometimes will be called a strobe. The function is the same in each case: one of its logic states will enable the internal switches, while its other logic state will prevent any internal switches from closing.

Switch inputs may be labeled S0, S1, S2… or X0, X1, X2… or may simply be numbered, almost always counting up from 0. Where two or more sets of switches coexist in one package, each set of inputs may be distinguished from the others by preceding each identifier with a numeral or letter to designate the switch, as in 1S0, 1S1, 1S2… or 1X0, 1X1, 1X2… (Switches are generally numbered from 1 upward, even though their inputs are numbered from 0 upward.) Outputs may be identified using the same coding scheme as inputs, bearing in mind that the inputs and outputs of an analog multiplexer usually are interchangeable. Some manufacturers, however, prefer to identify each multiplexer output by preceding it with letter Y. Alternatively, Z1, Z2, Z3… may identify the outputs from switches 1, 2, 3… Fortunately, datasheets usually include some kind of key to this grab-bag of abbreviations.

Control pins are often identified as A, B, C… with letter A representing the least significant bit in the binary number that is applied to the pins.

Voltages can be confusing in multiplexers. Components intended for use with digital inputs are straightforward enough, as the supply voltage will be identified as V_{CC} and is typically 5VDC for through-hole packages (often lower for surface-mount), while negative ground is assumed to be 0VDC. However, where a multiplexer may be used with AC inputs in which the voltage varies above and below 0V, supply voltages above and below 0VDC are also possible—such as +7.5VDC and −7.5VDC, to take a random example. Three power-supply pins may be provided for this purpose. The positive supply will usually be identified as V_{DD} (the D refers to the Drain in the internal MOSFETs). A V_{EE} pin may be at 0VDC or at a negative value equal and opposite to V_{DD}. The E in this abbreviation is derived from Emitter voltage, even though the component may not contain a bipolar transistor with an emitter. Customarily, a V_{SS} pin (the S being derived from the Source in the internal MOSFETs) will be at 0VDC, and other voltages will be measured above and below this baseline. This ground pin may alternatively be labeled GND.

As is customary in logic chips, low-active control pins will have a bar printed above their identifiers, or an apostrophe will be placed after an identifier if the font does not permit printing the bar. Alternatively, low-active pins may be represented by showing a small circle, properly referred to as a *bubble*, at the input or output point of the symbol for the multiplexer. Note that analog inputs and outputs are neither high-active nor low-active; they merely pass voltages through.

Variants

Most multiplexers are "break before make" devices, where one input is disconnected before the next input is connected. However, some exceptions exist, and datasheets should be checked for this. It can be a significant issue, because make-before-break switching will briefly connect external devices with each other, through the chip.

Many multiplexers can tolerate control voltages above the usual high value in a logic circuit—as high as 15VDC in some cases. The voltage that is switched by the multiplexer may be the same as the control voltage, or may be higher.

Some analog multiplexers have *overvoltage protection* that allows them to withstand input voltages that are twice or three times the recommended maximum.

Datasheets may mention "internal address decoding," meaning that the binary number input, specifying a channel to be switched, is decoded inside the chip. In fact, virtually all multiplexers now have on-chip address decoding, and this feature should be assumed to exist, regardless of whether it is mentioned.

Values

The voltage to be switched will usually be referred to as the *input voltage*, V_{IN}.

An analog multiplexer should not be subjected to current exceeding the value that it is designed to switch. This is known as the maximum *channel current*. A typical value would be 10mA, although many modern surface-mount components are designed for currents in the microamp range.

The *on-resistance* is the resistance imposed by the analog multiplexer on the signal flowing through it. While modern, specialized analog multiplexers may have an on-resistance as low as 5Ω, these are relatively unusual. An on-resistance of 100Ω to 200Ω is more common. This value will vary within a component depending on the power supply voltage and the voltage being switched. It will increase slightly as V_{IN} deviates above (or below) 0V, will increase substantially for lower values of supply voltage, and will increase significantly with temperature.

The curves in Figure 16-9 show on-resistance of an analog multiplexer varying with input voltage, with three different power supplies: plus-and-minus 2.5VDC (described in the graph as a "spread" of 5VDC), plus-and-minus 5VDC (a "spread" of 10VDC), and plus-and-minus 7.5VDC (a "spread" of 15VDC). These curves were derived from a datasheet for the MC14067B analog multiplexer; curves for other chips will be different, although the basic principles remain the same.

Switching time is an important consideration in high-speed applications. The "on" and "off" times specified in a datasheet (often as t_{ON} and t_{OFF}) are a function of the propagation delay from the control input to the toggling of the switch, and are generally measured from the halfway point of the rising or falling edge of the control input, to the 90% point of the output signal level.

Leakage current is the small amount of current (often measured in picoamperes) that the solid-state switch will pass when it is in its "off" state. This should be insignificant except when very high-impedance loads are used.

Separate switches inside a multiplexer may have characteristics that differ slightly from one another. Differences in on-resistance between adjacent switches can be important when switching parallel analog signals. A datasheet should mention the extent to which switches have matched characteristics, and may define the maximum deviation from one another using the abbreviation R_{ON} even though this same term may be used, confusingly, to denote the on-resistance of each individual switch.



Figure 16-9. *Variations in on-resistance in an analog multiplexer. Each voltage "spread" is the difference between positive supply voltage and an equal-and-opposite negative ground voltage. Thus a "spread" of 10VDC means plus and minus voltages of 5VDC. (Curves derived from On Semiconductor datasheet for MC14067B analog multiplexer.)*

How to Use It

A multiplexer may be used as a simple switch to choose one of multiple inputs, such as a choice of input jacks on a stereo system. A dual differential multiplexer is useful in this application, as it can use a single select signal to switch two signal paths simultaneously.

A multiplexer can also be used as a digital volume control by switching an audio signal among a variety of resistances, similar to a **digital potentiometer**. In this application, the possible presence of pullup resistors inside the multiplexer must be considered.

Where a microcontroller must monitor a large number of inputs (for example, a range of temperature sensors or motion sensors), a multiplexer can reduce the number of input pins required. Its data-select pins will be cycled through all the possible binary states by the microcontroller, to select each data input in turn, while its single-wire output will carry the analog data to a separate pin on the microcontroller which performs an analog-digital conversion.

Conversely, a demultiplexer (i.e., an analog multiplexer such as the 4067B chip which can be used in demultiplexer mode) can be used by a microcontroller to switch multiple components on and off. Four outputs from the microcontroller can connect with the control pins of a 16-channel demultiplexer, counting from binary 0000 through binary 1111 to select output pins 0 through 15. After selecting each pin, the microcontroller can send a high or low pulse through it. The process then repeats. (A **decoder** can be used in the same way.)

Other Application Notes

Multiplexers may be *cascaded* to increase the inputs-to-outputs ratio.

Modern multiplexers are found on computer boards where they choose among video output ports, or as PCI express channel switches.

A multiplexer may be used as a parallel-to-serial converter, as it samples multiple channels and converts them into a serial data stream.

In telecommunications, a multiplexer can sample voice signals from multiple separate inputs and combine them into a digital stream that can be transmitted at a faster bit rate over a single channel. However, this application goes far beyond the simple uses for multiplexers described here.

What Can Go Wrong

Problems that are common to all digital chips are summarized in the section on logic gates (see "What Can Go Wrong" on page 105).

Pullup Resistors

While they are often necessary to prevent connections from floating, pullup resistors built into a multiplexer may have unexpected consequences if the user is unaware of them.

Break Before Make

For most applications, it is desirable for each internal solid-state switch to break one connection before making a new one. This avoids the possibility of separate external components being briefly connected with each other through the multiplexer. Datasheets should be checked to verify that a multiplexer functions in break-before-make mode. If it doesn't, the enable pin can be used momentarily to disable all connections before a new connection is established.

Signal Distortion

Where a multiplexer is passing analog signals, signal distortion can result if the on-resistance of multiple internal switches varies significantly at different voltages. A datasheet for an analog multiplexer should usually include a graph showing on-resistance over the full signal range. The flatter the graph is, the less distortion the component will create. This is often described in datasheets as R_{ON} Flatness.

Limits of CMOS Switching

Although most multiplexers are built around CMOS transistors, their switching speed may be insufficient for video signals, and their on-resistance may vary enough to introduce distortion. Multiplexers are available with complementary bipolar switching for very high-speed applications. They impose some penalties in cost and power consumption.

Transients

Switch capacitance inside a multiplexer can cause transients in the output when the switch changes state. An allowance for *settling time* may be necessary. This will be additional to the switching speed claimed by the datasheet.

LCD

17

The full term *liquid-crystal display* is seldom used. Its acronym, **LCD**, is much more common. Sometimes the redundant combination **LCD display** is found. All three terms refer to the same device. In this encyclopedia, the first two words in *liquid-crystal display* are hyphenated because they are an adjectival phrase. Other sources often omit the hyphen.

The acronym **LED** (for **light-emitting diode**) is easily confused with **LCD**. While both devices display information, their mode of action is completely different.

OTHER RELATED COMPONENTS

- **LED display** (see Chapter 24)

What It Does

An LCD presents information on a small display panel or screen by using one or more segments that change their appearance in response to an AC voltage. The display may contain alphanumeric characters and/or symbols, icons, dots, or pixels in a *bitmap*.

Because of its very low power consumption, a basic monochrome LCD is often used to display numerals in battery-powered devices such as digital watches and calculators. A small liquid-crystal display of this type is shown in Figure 17-1.

Color-enabled, backlit LCDs are now frequently used in almost all forms of video displays, including those in cellular telephones, computer monitors, game-playing devices, TV screens, and aircraft cockpit displays.

How It Works

Light consists of electromagnetic waves that possess an electric field and a magnetic field. The fields are perpendicular to each other and to the direction in which the light is traveling, but the field polarities are randomly mixed in most visible radiation. This type of light is referred to as *incoherent*.



Figure 17-1. *A small, basic monochrome LCD.*

Figure 17-2 shows a simplified view of an LCD that uses a backlight. Incoherent light emerges from the backlight panel (A) and enters a vertical polarizing filter (B) that limits the electric field vector. The polarized light then enters a liquid crystal (C) which is a liquid composed of molecules organized in a regular helical structure that rotates the polarity by 90 degrees when no voltage is applied to it. The light now passes through a horizontal polarizing filter (D) and is visible to the user.



Figure 17-2. *The combination of two polarizers and a liquid crystal appears transparent when voltage is not applied. See text for details.*

- A liquid crystal itself does not emit light. It can only modify light that passes through it.

Figure 17-3 shows what happens when voltage is applied to the liquid crystal via transparent electrodes (not included in the figure). The molecules reorganize themselves in response to the electric potential and allow light to pass without changing its polarity. Consequently, the vertically polarized light is now blocked by the front, horizontally polarized filter, and the display becomes dark.

A liquid crystal contains ionic compounds that will be attracted to the electrodes if a DC voltage is applied for a significant period of time. This can degrade the display permanently. Therefore, AC voltage must be used. An AC frequency of 50Hz to 100Hz is common.



Figure 17-3. *The LCD appears dark when voltage is applied. See text for details.*

Variants

A *transmissive LCD* requires a backlight to be visible, and is the type illustrated in Figure 17-2. In its simplest form, it is a monochrome device, but is often enhanced to display full color by adding red, green, and blue filters. Alternatively, instead of a white backlight, an array of pixel-sized red, green, and blue **LEDs** may be used, in which case filters are unnecessary.

Backlit color LCDs have displaced *cathode-ray tubes*, which used to be the default system in almost all video monitors and TVs. LCDs are not only cheaper but can be fabricated in larger sizes. They do not suffer from *burn in*, where a persistent unchanging image creates a permanent scar in the phosphors on the inside of a tube. However, large LCDs may suffer from dead pixels or stuck pixels as manufacturing defects. Different manufacturers and vendors have varying policies regarding the maximum acceptable number of pixel defects.

In a *reflective LCD*, the structure is basically the same as that shown in Figure 17-2 except that a reflective surface is substituted for the backlight. Ambient light enters from the front of the display, and is either blocked by the liquid crystal in combination with the polarizing filters, or is allowed to reach the reflective surface at the rear, from which it reflects back through the liquid crystal to the eye of the user. This type of display is very easily readable in a bright environment, but will be difficult to see in dim conditions and will be invisible in darkness. Therefore, it may be augmented with a user-activated light source mounted at the side of the display.

A *transreflective LCD* contains a translucent rear polarizer that will reflect some ambient light, and is also transparent to enable a backlight. While this type of LCD is not as bright as a reflective LCD and has less contrast, it is more versatile and can be more energy efficient, as the backlight can be switched off automatically when ambient light is bright enough to make the display visible.

Active and Passive Types

An *active matrix* LCD adds a matrix of thin-film transistors to the basic liquid-crystal array, to store the state of each segment or pixel actively while the energizing AC voltage transitions from positive to negative. This enables a brighter, sharper display as *crosstalk* between adjacent pixels is reduced. Because *thin-film transistors* are used, this is often described as a *TFT* display; but the term is interchangable with *active matrix*.

A *passive matrix* LCD is cheaper to fabricate but responds sluggishly in large displays and is not so well suited to fine gradations in intensity. This type of component is used primarily in simple monochrome displays lacking intermediate shades of gray.

Crystal Types

Twisted Nematic (TN) are the cheapest, simplest type of LCD, allowing only a small viewing angle and average contrast. The appearance is limited to black on gray. The response rate is relatively slow.

Super Twisted Nematic (STN) displays were developed in the 1980s for passive LCDs, enabling better detail, wider view angle, and a faster response. The natural appearance is dark violet or black on green, or dark blue on silver-gray.

Film-compensated Super Twisted Nematic (FSTN) uses an extra coating of film that enables a pure black on white display.

Double Super Twisted Nematic provides further enhancement of contrast and response times, and automatic contrast compensation in response to ambient temperature. The appearance is black on white. This display requires backlighting.

Color Super Twisted Nematic (CSTN) is an STN display with filters added for full color reproduction.

Seven-Segment Displays

The earliest monochrome LCDs in devices such as watches and calculators used seven segments to display each numeral from 0 through 9. This type of LCD is still used in low-cost applications. A separate control line, or electrode, connects to each segment, while a *backplane* is shared by all the segments, connecting with a *common* pin to complete the circuit.

Figure 17-4 shows a typical seven-segment display. The lowercase letters *a* through *g* that identify each segment are universally used in datasheets. The decimal point, customarily referred to as "dp," may be omitted from some displays. The array of segments is slanted forward to enable more acceptable representation of the diagonal stroke in numeral 7.



Figure 17-4. *Basic numeric display format for LCD numeric displays (the same layout is used with LEDs). To identify each segment, lowercase letters are universally used.*

Seven-segment displays are not elegant but are functional and are reasonably easy to read, as shown in Figure 17-5. Letters A, B, C, D, E, and F (displayed as A, b, c, d, E, F because of the restrictions imposed by the small number of segments) may be added to enable display of hexadecimal values.

In appliances such as microwave ovens, very basic text messages can be displayed to the user within the limitations of 7-segment displays, as suggested in Figure 17-6.

The advantage of this system is low cost, as 7-segment displays are cheap to fabricate, entail the fewest connections, and require minimal decoding to create each alphanumeric character. However, numbers 0, 1, and 5 cannot be distinguished from letters O, I, and S, while letters containing diagonal strokes, such as K, M, N, W, X, and Z, cannot be displayed at all.



Figure 17-5. *Numerals and the first six letters of the alphabet created with a 7-segment display.*

Additional Segments

Alphanumeric LCDs were developed using 14 or 16 segments to enable better representation of letters of the alphabet. Sometimes these displays were slanted forward, like the 7-segment displays, perhaps because the style had become familiar, even though the addition of diagonal segments made it unnecessary. In other cases, the 14 or 16 segments were arrayed in a rectangle. See Figure 17-7.

The same words represented in Figure 17-6 are shown in Figure 17-8, using 16-segment LCDs. Clearly, the advantage gained by enabling diagonal strokes entailed the disadvantage of larger gaps in the letters, making made them ugly and difficult to read.



Figure 17-6. *Basic text messages can be generated with 7-segment displays, although they cannot contain alphabetical letters that use diagonal strokes.*

A full character set using 16-segment LCDs is shown in Figure 17-9. This conforms partially with the ASCII coding system, in which each character has an identifying numeric code ranging from 20 hexadecimal for a letter-space to 7A hexadecimal for letter z (although this character set does not attempt to represent lowercase letters differently from uppercase). The ASCII acronym stands for *American Standard Code for Information Interchange*.

Because backlit LCDs had become common by the time 16-segment displays were introduced, the characters were often displayed in light-on-dark or "negative" format, as suggested in this figure. LEDs, of course, have always used the light-on-dark format, as an LED is a light-emitting component.



Figure 17-7. *LCDs using 14 segments (left) and 16 segments (right) were introduced to represent a full alphabet in addition to numerals. Sometimes these displays were slanted forward, like the previous 7-segment type, even though this was no longer necessary to represent the number 7.*

Dot-Matrix Displays

The 16-segment displays were never widely popular, and the declining cost of microprocessors, LCD fabrication, and ROM storage made it economic to produce displays using the more easily legible 5x7 dot-matrix alphabet that had been common among early microcomputers. Figure 17-10 shows a dot-matrix character set that is typical of many LCDs.

Because the original ASCII codes were not standardized below 20 hexadecimal or above 7A hexadecimal, manufacturers have represented a variety of foreign-language characters, Greek letters, Japanese characters, accented letters, or symbols using codes 00 through 1F and 7B through FF. The lower codes are often left blank, allowing user installation of custom symbols. Codes 00 through 0F are often reserved for control functions, such as a command to start a new line of text. There is no standardization in this area, and the user must examine a datasheet for guidance.



Figure 17-8. *The same text messages shown previously using 7-segment LCDs are shown here using 16-segment displays.*

Dot-matrix LCDs are usually packaged in arrays consisting of eight or more columns and two or more rows of characters. The number of columns is always stated before the number of rows, so that a typical 8 x 2 display contains eight alphanumeric characters in two horizontal rows. An array of characters is properly referred to as a *display module*, but may be described, confusingly, as a *display*, even though a single seven-segment LCD is itself a display. A 16x2 display module is shown from the front in Figure 17-11 and from the rear in Figure 17-12.



Figure 17-9. *A full character set using 16-segment LCDs.*



Figure 17-10. *A dot-matrix character set typical of LCDs capable of displaying a matrix of 5×7 dots.*



Figure 17-11. *A 16x2 LCD display module seen from the front.*



Figure 17-12. *The same 16x2 LCD display module from the previous figure, seen from the rear.*

Multiple-character display modules have been widely used in consumer electronics products such as audio components and automobiles where simple status messages and prompts are necessary—for example, to show the volume setting or broadcast frequency on a stereo receiver. Backlighting is almost always used.

Because the cost of small, full-color, high-resolution LCD screens has been driven down rapidly by the mass production of cellular phones, color displays are likely to displace monochrome dot-matrix LCD display modules in many applications. Similarly, touchscreens will tend to displace pushbuttons and tactile switches. Touchscreens are outside the scope of this encyclopedia.

Color

The addition of filters to create a full color display is shown in simplified form in Figure 17-13.



Figure 17-13. *The addition of red, green, and blue color filters, in conjunction with variable density liquid crystal pixels, enables an LCD full-color display.*

Red, green, and blue are almost always used as primary colors for transmitted light, because the combination of different intensities of these *RGB* primaries can create the appearance of many colors throughout the visible spectrum. They are said to be *additive* primaries, as they create brighter colors when they are combined. The principle is illustrated in Figure 17-14.

The use of the word "primaries" to refer to red, green, and blue can cause confusion, as full-color printed materials use a different set of *reflective* primaries, typically cyan, magenta, and yellow, often with the addition of black. In this *CMYK* system, additional layers of pigment will absorb, or subtract, more visible frequences. See Figure 17-15.



Figure 17-14. *When colors red, green, and blue are transmitted directly to the eye, pairs of these additive primaries create secondary colors cyan, magenta, and yellow. Combining all three additive primaries creates an approximation of white light. This can be verified by viewing a color monitor with a magnifying glass.*



Figure 17-15. *When ink colors cyan, magenta, and yellow are superimposed on white paper and are viewed in white light, pairs of these subtractive primaries create secondary colors red, green, and blue. Overprinting all three subtractive primaries creates an approximation of black, limited by the reflective properties of available pigments. Black ink is usually added to provide additional contrast.*

The complete range of colors that can be created as a combination of primaries is known as the *gamut*. Many different RGB color standards have been developed, the two most widely used being *sRGB* (almost universal in web applications) and *Adobe 1998* (introduced by Adobe Systems for Photoshop, providing a wider gamut). None of the available systems for color reproduction comes close to creating the full gamut that can be perceived by the human eye.

Backlighting Options

For monochrome LCDs, **electroluminescent** backlighting may be used. It requires very low current, generates very little heat, and has a uniform output. However, its brightness is severely limited, and it requires an inverter that adds significantly to the current consumption.

For full-color LCDs, **fluorescent** lights were originally used. They have a long lifetime, generate little heat, and have low power consumption. However, they require a relatively high voltage, and do not work well at low temperatures. Early flat screens for laptop computers and desktop monitors used *cold-cathode fluorescent panels.*

Subsequently, white light-emitting diodes (**LED**s) were refined to the point where they generated a range of frequencies that was considered acceptable. Light from the LEDs passes through a diffuser to provide reasonably consistent illumination across the entire screen. LEDs are cheaper than fluorescent panels, and allow a thinner screen.

High-end video monitors use individual red, green, and blue LEDs instead of a white backlight. This eliminates the need for colored filters and produces a wider gamut. So-called *RGB* LCD monitors are more expensive but are preferred for professional applications in video and print media where accurate color reproduction is essential.

Zero-Power Displays

Some techniques exist to create LCDs that require power only to flip them to and fro between their transparent and opaque states. These are also known as *bistable* displays, but have not become as widely used. They are similar in concept to *e-ink* or *electronic paper* displays, but the principle of operation is different.

How to Use It

So long as an LCD consists of just one numeral, it can be driven by just one decoder chip that translates a binary-coded input into the outputs required to activate the appropriate segments of the LCD. The evolution of multi-digit displays, alphanumeric displays, dot-matrix displays, and graphical displays has complicated this situation.

Numeric Display Modules

An LCD consisting of a single digit is now a rare item, as few circuits require only one numeral for output. More commonly, two to eight numerals are mounted together in a small rectangular panel, three or four numerals being most common. A typical digital alarm clock uses a four-digit numeric display module, incorporating a colon and indicators showing AM/PM and alarm on/off. Other numeric display modules may include a minus sign.

Modules that are described as having 3.5 or 4.5 digits contain three full digits preceded by a numeral 1 composed of two segments. Thus, a 3-digit module can display numbers from 000 through 999, while a 3.5-digit display can display numbers from 000 through 1999, approximately doubling the range.

Numeric display modules of the type described here do not contain any decoder logic or drivers. An external device, such as a microcontroller, must contain a lookup table to translate a numeric value into outputs that will activate the appropriate segments in the numbers in a display, with or without decimal points and a minus sign. To avoid reinventing the wheel, a programmer may download code libraries for microcontrollers to drive commonly used numeric display modules. It is important to remember, though, that segments in monochrome LCDs must be activated by AC, typically a square wave with a frequency of 30Hz to 90Hz.

An alternative is to use a decoder chip such as the 4543B or 4056B, which receives a binary-coded decimal input (i.e., 0000 through 1001 binary, on four input puts) and translates it into an output on seven pins suitable for connection with the seven segments of a 7-segment display. The 4543B requires a square-wave input to its "phase" pin. The square-wave must also be applied simultaneously to the backplane of the LCD, often identified as the "common" pin on datasheets. Pinouts for the 4543B are shown in Figure 17-16.

The 4543B includes provision for "display blanking," which can be used to suppress leading zeros in a multidigit number. However, the lack of outputs to control a minus sign or decimal point limits the decoder to displaying positive integers.



Figure 17-16. *Pinouts for the 4543B decoder chip, which is designed to drive a seven-segment numeric LCD.*

The power supply for a 4543B can range from 5VDC to 18VDC, but because the logic-high output voltage will be almost the same as that of the power supply, it must be chosen to match the power requirements of the LCD (very often 5VAC).(((

To drive a three-digit numeric display module, a separate decoder chip can be used to control each digit. The disadvantage of this system is that each decoder requires three inputs, so that a three-digit display will require nine outputs from the microcontroller.

To deal with this issue, it is common to *multiplex* a multi-digit display. This means that each output from the decoder is shared among the same segments of all the LCD numerals. Each LCD numeral is then activated in sequence by applying AC voltage to its common pin. Simultaneously, the decoder sends the data appropriate to that LCD. This process must be fast enough so that all the digits appear to be active simultaneously, and is best managed with a microcontroller. A simplified schematic is shown in Figure 17-17. It can be compared with a similar circuit to drive LED displays, shown in Figure 24-13.

Alphanumeric Display Module

Arrays of dot-matrix LCDs that can display alphabetical characters as well as numerals require preset character patterns (usually stored in ROM) and a command interpreter to process instructions that are embedded in the data stream. These capabilities are often built into the LCD module itself.

While there is no formal or de facto standard, the command set used by the Hitachi HD44780 controller is installed in many displays, and code libraries for this set are available for download from sites dedicated to the Arduino and other microcontrollers. Writing code from scratch to control all aspects of an alphanumeric display is not a trivial chore. The Hamtronix HDM08216L-3-L30S is a display that incorporates the HD44780.



Figure 17-17. *When two or more numeric displays are multiplexed, a control device (typically, a microcontroller) activates each of them in turn via its backplane (common terminal) while sending appropriate data over a shared bus.*

Regardless of which standard is used, some features of alphanumeric display modules are almost universal:

- Register select pin. Tells the display whether the incoming data is an instruction, or a code identifying a displayable character.
- Read/write pin. Tells the display whether to receive characters from a microcontroller or send them to a microcontroller.
- Enable/disable pin.
- Character data input pins. There will be eight pins to receive the 8-bit ASCII code for each displayable character in parallel. Often there is an option to use only four of these pins, to reduce the number of microcontroller outputs necessary to drive the display. Where four pins are used, each 8-bit character is sent in two segments.
- LED backlight pin. Two may be provided, one connected to the anode(s) of the LED backlight, the other to the cathode(s).
- Reset pin.

Embedded instruction codes can be complex, including commands to reposition the cursor at a specific screen location, backspace-and-erase, scroll the display, and erase all characters on the screen. Codes may be included to adjust screen brightness and to switch the display between light-on-dark (negative) and dark-on-light (positive) characters.

Some display modules also have graphics capability, allowing the user to address any individual pixel on the screen.

Because of the lack of standardization in control codes, manufacturer's datasheets must be consulted to learn the usage of a particular alphanumeric display module. In addition to datasheets, online user forums are a valuable source of information regarding quirks and undocumented features.

What Can Go Wrong

Temperature Sensitivity

Liquid crystals vary in their tolerance for low and high temperatures, but generally speaking, a higher voltage may be necessary to create a sufficiently dense image at a low temperature. Conversely, a lower voltage may be necessary to avoid "ghosting" at a high temperature. An absolutely safe operating temperature range is likely to be 0 through 50 degrees Celsius, but check the manufacturer's datasheet for confirmation. Special-purpose LCDs are available for extreme temperatures.

Excessive Multiplexing

A twisted nematic display is likely to perform poorly if its duty cycle is greater than 1:4. In other words, more than four displays should not be multiplexed by the same controller.

DC Damage

An LCD can be damaged quickly and permanently if it is subjected to DC current. This can occur by accident if, for example, a timer chip is being used to generate the AC pulse stream, and the timer is accidentally disconnected, or has an incorrect connection in its RC network. Check timer output with a meter set to measure AC volts before allowing any connection to the common pin of an LCD.

Bad Communications Protocol

Many alphanumeric display modules do not use a formal communications protocol. Duplex serial or I2C connection may not be available. Care must be taken to allow pauses of a few milliseconds after execution of embedded commands, to give the display sufficient time to complete the instruction. This is especially likely where a command to clear all characters from the screen has to be executed. If garbage characters appear on the screen, incorrect data transfer speed or lack of pause times may be to blame.

Wiring Errors

This is often cited by manufacturers as the most common cause of failure to display characters correctly, or lack of any screen image at all.

incandescent lamp

18

The terms *incandescent light*, *incandescent bulb*, and *incandescent light bulb* are often used interchangeably with **incandescent lamp**. Because the term "lamp" seems to be most common, it is used here. A *panel-mounted indicator lamp* is considered to be an assembly containing an incandescent lamp.

A *carbon arc*, which generates light as a self-sustaining spark between two carbon electrodes, can be thought of as a form of incandescent lamp, but is now rare and is not included in this encyclopedia.

OTHER RELATED COMPONENTS

- **LED area lighting** (see Chapter 23)
- **LED indicator** (see Chapter 22)
- **neon bulb** (see Chapter 19)
- **fluorescent light** (see Chapter 20)

What It Does

The term *incandescent* describes an object that emits visible light purely as a consequence of being hot. This principle is used in an **incandescent lamp** where a wire *filament* glows as a result of electric current passing through it and raising it to a high temperature. To prevent oxidation of the filament, it is contained within a sealed bulb or tube containing an inert gas under low pressure or (less often) a vacuum.

Because incandescent lamps are relatively inefficient, they are not considered a wise environmental choice for area lighting and have been prohibited for that purpose in some areas. However, small, low-voltage, panel-mount versions are still widely available. For a summary of advantages of miniature incandescent lamps relative to **light-emitting diodes** (LEDs) see "Relative Advantages" on page 179.

Schematic symbols representing an incandescent lamp are shown in Figure 18-1. The symbols are all functionally identical except that the one at bottom right is more likely to be used to represent small panel-mounted indicators.



Figure 18-1. *A variety of symbols can represent an incandescent lamp. The one at bottom right may be more commonly used for small panel-mounted indicators.*

The parts of a generic incandescent light bulb are identified in Figure 18-2:

A: Glass bulb.

B: Inert gas at low pressure.

C: Tungsten filament.

D: Contact wires (connecting internally with brass base and center contact, below).

E: Wires to support the filament.

F: Internal glass stem.

G: Brass base or cap.

H: Vitreous insulation.

I: Center contact.



Figure 18-2. *The parts of a typical incandescent lamp (see text for details).*

History

The concept of generating light by using electricity to heat a metal originated with Englishman Humphrey Davy, who demonstrated it with a large battery and a strip of platinum in 1802. Platinum was thought to be suitable because it has a relatively high melting point. The lamp worked but was not practical, being insufficiently bright and having a short lifespan. In addition, the platinum was prohibitively expensive.

The first patent for an incandescent lamp was issued in England in 1841, but it still used platinum. Subsequently, British physicist and chemist Joseph Swan spent many years attempting to develop practical carbon filaments, and obtained a patent in 1880 for *parchmentized thread*. His house was the first in the world to be illuminated by light bulbs.

Thomas Edison began work to refine the electric lamp in 1878, and achieved a successful test with a carbonized filament in October 1879. The bulb lasted slightly more than 13 hours. Lawsuits over patent rights ensued. Carbonized filaments were used until a tungsten filament was patented in 1904 by the German/Hungarian inventor Just Sándor Frigyes and the Croatian inventor Franjo Hanaman. This type of bulb was filled with an inert gas, instead of using a vacuum.

Many other pioneers participated in the effort to develop electric light on a practical basis. Thus it is incorrect to state that "Thomas Edison invented the light bulb." The device went through a very lengthy process of gradual refinement, and one of Edison's most significant achievements was the development of a power distribution system that could run multiple lamps in parallel, using filaments that had a relatively high resistance. His error was insisting on using *direct current* (DC) while his rival Westinghouse pioneered *alternating currrent* (AC), enabling power transmission over longer distances through the use of **transformers**. The use of AC also enabled Tesla's brushless induction motor.

By the mid-1900s, most incandescent bulbs used tungsten filaments.

How It Works

All objects emit electromagnetic radiation as a function of their temperature. This is known as *black body radiation*, based on the concept of an object that absorbs all incoming light, and thus does not reflect any sources from outside itself. As its temperature increases, the intensity of the radiation increases while the wavelength of the radiation tends to decrease.

If the temperature is high enough, the wavelength of the radiation enters the visible spectrum, between 380 and 740 nanometers. (A nanometer is one-billionth of a meter.)

The melting point of tungsten is 3,442 degrees Celsius, but a lamp filament typically operates between 2,000 and 3,000 degrees. At the higher end of this scale, evaporation of metal from the filament tends to cause deposition of a dark residue on the inside of the bulb, and erodes the filament more rapidly, to the point where it eventually breaks. At the lower end of this scale, the light will be yellow and the intensity will be reduced.

Spectrum

The color of black-body radiation is measured using the Kelvin temperature scale. The increment of 1 degree Kelvin is the same as 1 degree Celsius, but the Kelvin scale has a zero value at *absolute zero*. This is the theoretical lowest conceivable temperature, at which there is complete absence of heat. It is approximately –273 degrees Celsius.

From this it is evident that if K is a temperature in degrees Kelvin and C is a temperature in degrees Celsius:

`K = C + 273` (approximately)

Calibration of light sources in degrees Kelvin is common in photography. Many digital cameras allow the user to specify the *color temperature* of lights that are illuminating an indoor scene, and the camera will compensate so that the light source appears to be pure white with all colors in the visible spectrum being represented equally.

Some computer monitors also allow the user to specify a white value in degrees Kelvin.

Color temperature is used in astronomy, because the spectrum of many stars is comparable with that of a theoretical black body.

A color temperature of 1,000 degrees K will have a dark orange hue, while 15,000 degrees K or higher will have a blue hue comparable to that of a pale blue sky. The color temperature of the sun is approximately 5,800 K. Interior lighting is often around 3,000 K, which many people find acceptable because it creates pleasant flesh tones. An incandescent bulb described by the manufacturer as "soft white" or "warm" will have a lower color temperature than one which is sold as "pure white" or "paper white."

Graphs showing the emission of wavelengths at various color temperatures are shown in Figure 18-3. The rainbow section indicates the approximate range of visible wavelengths between ultraviolet, on the left, and infrared, on the right. For purposes of clarity, the peak intensity for each color temperature has been equalized. In reality, increasing the temperature also increases the light output.



Figure 18-3. *Approximate peak wavelengths for black-body radiation at various color temperatures in degrees Kelvin. The curves have been adjusted so that their peak values are equalized. Adapted from an illustration in the reference book Light Emitting Diodes by E. Fred Schubert.*

Non-Incandescent Sources

So long as light is generated by heating a filament, plotting the intensity against wavelength will result in a smooth curve without irregularities. A higher Kelvin value will simply displace and compress the curve laterally without changing its basic shape to a significant degree.

The introduction of **fluorescent** sources and, subsequently, light-emitting diodes (**LEDs**) has complicated this scenario. Because they are *luminescent* rather than *incandescent*, they do not generate an evenly weighted, continuous range of wavelengths.

LEDs tend to emit monochromatic light, meaning that it is tightly centered around just one color. A "white" LED is really a blue LED in which a phosphor coating on the semiconductor die is excited to create light over a broader range. A fluorescent light tends to create *spectral lines* which show up as sharp peaks at a few wavelengths determined by the mercury inside the bulb. Figure 18-4 illustrates these problems.

The human eye tends to compensate for the yellow emphasis of incandescent lamps and for the irregularities in spectra emitted by other light sources. Also, the eye is often unable to distinguish between "white" light created as a mix of all the visible wavelengths, and light that appears white even though it is dominated by a few isolated wavelengths from a fluorescent source.

However, when the eye views colors that are illuminated by a source that has gaps in its spectrum, some of the colors will appear unnaturally dull or dark. This is true also if an imperfect source is used as a backlight to create colors on a video monitor. Colors rendered by different light sources are shown in Figure 23-7 and subsequent figures.



Figure 18-4. *The relative performance of three light sources compared with sensitivity of the human eye to the visible spectrum. Note that the range of wavelengths on the horizontal scale in this figure is not the same as the range in the previous figure. The color assigned to each curve is arbitrary. Adapted from VU1 Corporation.*

Photography is adversely affected by the use of LEDs or fluorescents as a light source. Reds, for example, can seem dark when lit by white LEDs, while blues can be inappropriately intense. Because the source does not have an emission curve comparable to that of an incandescent light, the auto-white balance feature of a digital camera may be unable to address this problem, and it cannot be resolved by entering a different Kelvin number manually.

The fidelity with which a light source is capable of displaying the full visible spectrum is known as the *color rendering index* (CRI), ranging from a perfect score of 100 down to 0 or even lower (sodium-vapor street lighting has a negative value). Computing the index requires standard reference color samples and has been criticized for generating scores that do not correlate well with subjective assessments.

Incandescent bulbs can have a CRI of 100, while an uncorrected "white" LED may score as low as 80.

Power Consumption

Approximately 95% of the power consumed by an incandescent lamp generates heat instead of visible light. This wastage of power in room lighting is compounded by the power consumption of air conditioning to remove the heat from enclosed spaces in hot climates. While the heat from incandescent lamps does reduce the need for space heating in cold environments, heat is delivered more efficiently by using systems designed for that purpose. Consequently, greater energy efficiency can be achieved with a light source that generates less heat, regardless of ambient air temperature.

Variants

Miniature Lamps

Prior to the development of **LED**s, all light-emitting panel-mounted indicators were either **neon bulbs** or **incandescent lamps**. The use of neon is limited by its need for a relatively high voltage.

Miniature incandescents were the traditional choice for battery-powered light sources, and at the time of writing are still used in cheap flashlights. Variants are available that are as small as a 5mm LED, with a claimed life expectancy that is comparable, although they draw more current to generate an equivalent light intensity, because much of their power is wasted in infrared wavelengths.

The photograph in Figure 18-5 is of a miniature lamp terminating in pins spaced 0.05" apart. The total height of the lamp, including its ceramic base, is less than 0.4," while its diameter is just over 0.1". It draws 60mA at 5V and is rated for 25,000 hours.

The photograph in Figure 18-6 is of a lamp of similar size and power consumption, but terminating in wire leads and rated for 100,000 hours. It emits 0.63 lumens.



Figure 18-5. *A miniature lamp less than 0.4" high, terminating in pins spaced 0.05" apart.*



Figure 18-6. *This lamp is 0.25" high and terminates in wire leads.*

The lamp pictured in Figure 18-7 is slightly larger, with a glass envelope about 0.25" diameter. It is rated for less than half the lifetime of the lamp in Figure 18-6 but emits three times as much light —a typical tradeoff. Various base styles are available.



Figure 18-7. *This lamp has a glass envelope about 0.35" high. Its screw-in base makes it easier to replace than an LED.*

In the United States, the light output from miniature incandescent lamps may be measured in lumens, but is more often rated in *mean spherical candlepower* (MSCP). An explanation of light measurement is included in "MSCP" on page 178.

Lamp lenses provide a quick and simple way to add color to a miniature incandescent lamp. Usually the lens is cylindrical with a hemispherical end cap, and is designed to push-fit or snap-fit over a small lamp. Even when the cap is translucent, it may still be referred to as a lens.

Panel-Mount Indicator Lamps

This term often refers to a tubular assembly containing a miniature lamp, ready for installation.

The enclosure is often designed to snap-fit into a hole drilled in the panel. If the incandescent bulb inside the enclosure cannot be replaced, the component is said to be "non-relampable." Figure 18-8 shows a 12-volt panel-mount indicator lamp.



Figure 18-8. *This panel-mount indicator lamp is designed to push-fit into a hole 1/2" in diameter. The bulb inside it is not replacable, causing the assembly to be classified as "non-relampable."*

Halogen or Quartz-Halogen

This is a type of incandescent lamp containing gases under pressure in which halogens such as iodine or bromine cause evaporated tungsten atoms to be redeposited on the filament. A halogen lamp can therefore operate at a higher temperature, creating a light that is less yellow and brighter than that from a comparable incandescent lamp. It also enables a smaller bulb, but requires an envelope of borosilicate-halide glass (often termed *fused quartz*) instead of regular glass. A halogen lamp will be slightly more efficient than an incandescent bulb of the same wattage, and will last longer.

Halogens are available in a variety of formats. The small bulb pictured in Figure 18-9 consumes 75W, emitting 1,500 lumens at 3,000 degrees Kelvin. The light intensity is claimed to be equivalent to that of a 100W incandescent bulb. It has a mini-candelabra base.

Oven Lamps

Oven lamps are designed to withstand the high temperature in an oven. Typically they are usable with ambient temperatures up to 300 degrees C. A common power rating is 15W.



Figure 18-9. *A halogen bulb slightly more than 2" in length, designed for 115VAC.*

Base Variants

Miniature lamps are available with a wide variety of connection options, including wire terminals, single-contact bayonet, double-contact bayonet, miniature screw base, and fuse style. Most of these options require a matching socket.

Screw-in lamps for room illumination are common in household lighting in the United States and many other countries (but not in the UK, where bayonet fittings are used). The US socket size is designated by letter E followed by a number that gives the socket diameter in millimeters. Common sizes are E10, E14 and E27.

A *bayonet base* is fitted with two small lugs protruding on opposite sides. The lamp is secured by pushing it in and twisting it to engage the lugs in slots in the socket. The advantage of a bayonet base is that the bulb is less likely to become loose as a result of vibration.

A *pin base* consists simply of a pair of pins that will push-fit into small holes in a socket.

A *flange base* has a flange that engages in a socket where flexible segments will retain it.

A *wedge base* is forced between two contacts which retain the bulb by friction.

Some indicator lamps terminate simply in long, thin leads that can be soldered.

Values

While the power consumption of full-size incandescent lamps is rated in watts, small indicator lamps are rated in milliamps at the voltage for which they are designed. Miniature lamps may require specific voltages ranging from as low as 2V to 24V. A higher voltage generally necessitates a longer filament, which may entail a larger bulb.

The light that a lamp will emit can be measured in two ways: either as the power of the lamp (not its power consumption, but its radiating power), or as the light delivered to a specific area at a specific distance. These two measurements may differ because a lamp may concentrate its light in a beam, as in the case of a reflector bulb or an LED.

Power

Flux, in watts, is a measurement of energy flow in joules per second. The total radiating power of a lamp, in all wavelengths, in all directions, is known as its *radiant flux*. Because invisible wavelengths are of little interest when assessing the brightness of a lamp, the term *luminous flux* is used to describe the apparent brightness of the lamp in the visible spectrum. The unit for luminous flux is the *lumen*.

The human eye is most responsive to yellow-green hues in the center of the spectrum. Consequently, the measurement of luminous flux is weighted toward green at a wavelength of 555 nanometers. Red and violet are considered to have low luminous flux, while infrared and ultraviolet have a zero value.

When considering a value expressed in lumens, remember:

- Lumens are a measure of the total radiated power output of a light source, in all directions, in the visible spectrum only, weighted toward the characteristics of the human eye.
- The number of lumens of a light source does not define the direction in which the light is shining, or its uniformity.
- The abbreviation for lumen is *lm*.

A conventional incandescent lamp that consumes 100W of electricity is likely to have a light output of about 1,500 lumens. A 40W fluorescent tube can have a light output of about 2,600 lumens.

Illuminance

The *illuminance* of a light source is defined as the luminous flux per unit of area. This can be thought of as the brightness of a surface illuminated by the source.

Illuminance is measured in *lux*, where 1 lux = 1 lumen per square meter. For accurate calibration, the illuminated surface should be spherical in shape, and must be located 1 meter from the light source, with the source at the geometrical center of the sphere.

Illuminance used to be measured in *foot-candles*, where 1 foot-candle was 1 lumen per square foot.

- The number of lumens per square meter (lux) does not define the size of the illuminated area, only the brightness per unit of area.
- A lamp that has a tightly focused beam can achieve a high lux rating. When selecting a lamp for an application, the angle of dispersion of the beam must be considered in conjunction with its lux rating.

Intensity

A *candela* measures the luminous flux within an angle of dispersion. The angle is three-dimensional, and can be imagined as the sharpness of a point of a cone, where the light source is at the point and the cone represents the dispersion of light.

The three-dimensional angle of dispersion is measured in *steradians*. If a light source is at the center of a sphere that has a radius of 1 meter, and is illuminating one square meter of the surface of the sphere, the angle of dispersion is 1 steradian.

- A source of 1 lumen which projects all its light through a dispersion angle of 1 steradian is rated at 1 candela.
- The number of candelas does not define the angle of dispersion, only the intensity within that angle.
- A light source rated for 1,000 candelas could have a power of 10 lumens concentrated within an angle of 0.01 steradians, or could have a power of only 1 lumen concentrated within an angle of 0.001 steradians.
- There are 1,000 millicandelas in 1 candela. The abbreviation for candela is *cd* while the abbreviation for a millicandela is *mcd*.
- LEDs are often rated in mcd. The number describes the intensity of light within its angle of dispersion.

MSCP

Although the term *candlepower* is obsolete, it has been redefined as being equal to 1 candela. *Mean spherical candlepower* (MSCP) is a measurement of all the light emitted from a lamp in all directions. Because the light is assumed to be omnidirectional, it fills 4 * π (about 12.57) steradians. Therefore 1 MSCP = approximately 12.57

lumens. In the United States, MSCP is still the most common method of rating the total light output of a miniature lamp.

Efficacy

The *radiant luminous efficacy* (abbreviated *LER*) assesses how effective a lamp is at channeling its output within the visible spectrum, instead of wasting it in other wavelengths, especially infrared. LER is calculated by dividing the power emitted in the visible spectrum (the *luminous flux*) by the power emitted over all wavelengths.

Thus, if VP is the power emitted in the visible spectrum, and AP is the power emitted in all wavelengths:

```
LER = VP / AP
```

LER is expressed in *lumens per watt*. It can range from a low value of around 12 lm/W for a 40W incandescent bulb to 24 lm/W for a quartz halogen lamp. Fluorescent lamps may average 50 lm/W. LEDs vary, but can achieve 100 lm/W.

Efficiency

The *radiant luminous efficiency* (abbreviated *LFR*) of a lamp measures how good its radiant luminous efficacy is, compared with an imaginary ideal lamp. (Note the difference between the words “efficiency” and “efficacy.”) LFR is determined by dividing the radiant luminous efficacy (LER) by the maximum theoretical LER value of 683 lm/W, and multiplying by 100 to express the result as a percentage. Thus:

```
LFR = 100 * ( LER / 683 )
```

The LFR ranges from around 2% for a 40W bulb to 3.5% for a quartz halogen lamp. LEDs may be around 15% while fluorescents are closer to 10%.

How to Use It

When first introduced, LEDs were limited by their higher price, lower maximum light output, and inability to display blue or white. The price difference has disappeared for small indicators, while gaps in the color range have been filled (although the color rendering index of LEDs is still inferior).

Brightness remains an advantage for large incandescents relative to LEDs, as they are more upwardly scalable. However, fluorescents and vapor lamps have an advantage for very high light output, as in the lighting of big-box stores or parking lots. Thus the range of applications for incandescent bulbs is diminishing, especially because common types are now illegal for domestic light fixtures in many parts of the world.

Relative Advantages

When choosing whether to use an incandescent lamp or an LED, these advantages of an incandescent lamp should be considered:

- The intensity can be adjusted with a **triac**-based dimmer. Regular fluorescents cannot be dimmed, while LEDs often require different dimmer circuitry.
- The intensity can also be adjusted with a rheostat. The output from fluorescents cannot.
- Easy white-balance correction. LEDs and fluorescents do not naturally produce a consistent output over the visible spectrum.
- Can be designed to operate directly from a wide range of voltages (down to around 2V and up to around 300V). A higher voltage entails a longer filament wire, which may require a larger bulb. LEDs require additional components and circuitry to use higher voltages.
- Incandescent bulbs are more tolerant of voltage fluctuations than LEDs. With battery operation, the incandescent will still provide some reduced light output when the voltage has diminished radically. LEDs will not perform at all at currents lower than their threshold.
- An incandescent is nonpolarized and may be socketed, which simplifies user replacement.

LEDs are polarized and are usually soldered in.

- Can be powered by AC or DC without any modification or additional circuitry. LEDs require DC, which must be provided through a transformer and rectifier, or similar electronics, if AC power is the primary source.
- Can be equally visible from a wide range of viewing angles. LEDs have restricted viewing angles.
- The heat output from an incandescent bulb may occasionally be useful (for example in a terrarium, or in incubators for poultry).
- Trouble-free switching. Fluorescents tend to hesitate and blink when power is applied, and they require a *ballast* to energize them. The lifespan of fluorescents is reduced by frequent switching.
- No low-temperature problems. Incandescent lamps are not significantly affected by low temperatures. Fluorescents may not start easily in a cold environment, and may flicker or glow dimly for 10 minutes (or more) until they are warm enough to function properly.
- Easy disposal. Fluorescent lights contain small quantities of mercury that are an environmental hazard. They should not be mixed with ordinary trash. Compact fluorescent lamps (CFLs) and LEDs used for room lighting will be packaged with electronics that should ideally be recycled, although this is not very practical. Incandescent bulbs impose the least burden on the environment when they are thrown away.

However, the incandescent lamp has some obvious disadvantages:

- Relatively inefficient.
- More susceptible to vibration.
- More fragile.
- Likely to have a shorter natural life expectancy than LEDs, fluorescents, or neon bulbs, although the lifetime of a small panel indicator can be equal to that of an LED if a low color temperature is acceptable.
- Requires a filter or tinted glass envelope to generate colored light. This further reduces the lamp's efficiency.
- Cannot be miniaturized to the same degree as an LED indicator.

Derating

The lifespan of a lamp can be greatly extended by choosing one with a higher current rating or using it at a lower voltage. The light output will be reduced, and the color temperature will be at a lower Kelvin number, but in some situations this tradeoff may be acceptable.

The graphs in Figure 18-10 suggest that if the voltage of a hypothetical miniature lamp is reduced to 80% of the manufacturer's recommended value, this can make the lamp last 20 times as long. Note, however, that this will cut the light intensity to 50% of its normal value.

Conversely, using 130% normal voltage will give 250% of the normal light output, while shortening the life of the lamp to 1/20 of its normal value. Naturally these figures are approximations that may not apply precisely to a specific lamp.

What Can Go Wrong

High Temperature Environment

If an incandescent lamp is used in an environment hotter than 100 degrees Celsius, the life of the lamp is likely to be reduced by the "water cycle." Any water molecules inside the glass envelope will break down, allowing oxygen to combine with the tungsten filament to form tungsten oxide. The tungsten is deposited on the inside of the glass while the oxygen is liberated and begins a new cycle.



Figure 18-10. *The life expectancy of a hypothetical miniature lamp is very strongly influenced by voltage. Applying only 60% of the rated voltage can make a lamp last 500 times its normal lifespan, although it will greatly reduce light output. Note that the vertical axes apply to curves of the same color. Adapted from "Characteristics of Miniature Lamps" from Toshiba Lighting and Technology Corporation.*

Fire Risk

The partially evacuated bulb of an incandescent lamp provides some separation and protection from the heat in the filament, but if the bulb cannot disperse heat by radiation or convection, its temperature can rise to the point where it ignites flammable materials.

Halogen lamps have an elevated fire risk because they operate at a higher temperature and are smaller, providing less surface area to disperse the heat. They also contain gases under seven to eight atmospheres of pressure. Thermal stress can cause a halogen bulb to shatter, and fingerprints on the glass can increase this risk.

Current Inrush

When an incandescent lamp is first switched on, its filament has one-tenth the resistance that it will exhibit when it becomes hot. Consequently, the lamp will take a large initial surge of current, which stabilizes after about 50 milliseconds. This should be considered if one or more small lamps shares a DC power supply with components such as logic chips that may be sensitive to voltage fluctuations.

Replacement Problems

Because of the limited life of incandescent lamps, they should be installed in such a way that they are easy to replace. This can be an issue with panel indicators, where disassembly of a device may be necessary to reach the lamp.

The range of small incandescent lamps is diminishing, and may continue to diminish in the future. Future availability of replacement lamps should be considered when designing a circuit. When building equipment in small quantities, spare lamps should be purchased for future use.

neon bulb

19

The terms **neon bulb**, *neon indicator*, and *neon lamp* tend to be used interchangeably. In this encyclopedia, a neon *bulb* is defined as a glass capsule containing two electrodes in neon gas (or a combination of gases in which neon is present). A neon *lamp* is an assembly containing a neon bulb, usually using a plastic tube with a tinted transparent cap at one end. A neon *indicator* is a miniature neon lamp that is usually panel-mounted.

Large-scale neon tubes used in signage are not included in this encyclopedia.

OTHER RELATED COMPONENTS

- **incandescent lamp** (see Chapter 18)
- **fluorescent light** (see Chapter 20)
- **LED indicator** (see Chapter 22)

What It Does

When voltage is applied between two electrodes inside a neon bulb, the inert gas inside the bulb emits a soft red or orange glow. This color may be modified by using a tinted transparent plastic cap, known as a *lens*, in a *neon lamp* assembly.

A neon bulb is usually designed for a power supply of 110V or higher. It functions equally well with alternating or direct current.

The schematic symbols in Figure 19-1 are commonly used to represent either a neon bulb or a neon lamp. They are all functionally identical. The black dot that appears inside two of the symbols indicates that the component is gas filled. The position of the dot inside the circle is arbitrary. Even though all neon bulbs are gas filled, the dot is often omitted.



Figure 19-1. *Any of these symbols may represent a neon bulb or a neon lamp. The dot in two of the symbols indicates that the component is gas filled. All neon bulbs are gas filled, but the dot is often omitted.*

The photograph in Figure 19-2 shows a neon bulb with a series resistor preattached to one lead. Many bulbs are sold in this configuration, because a resistor must be used to limit current through the bulb. The bulb has no polarity and can be used on an AC or DC power supply. The same bulb is shown in its energized state in Figure 19-3.



Figure 19-2. *A typical neon bulb with series resistor attached to one lead.*

How It Works

Construction

The parts of a neon bulb are illustrated in Figure 19-4. When the bulb is fabricated, it begins as a glass tube. The leads are made of *dumet*, consisting of a copper sheath around a nickel iron core. This has the same coefficient of expansion as glass, so that when the glass is heated and melted around the leads, it forms a seal that should be unaffected by subsequent temperature fluctuations. This area is known as the *pinch* in the tube.

Nickel electrodes are welded onto the leads before the leads are inserted into the tube. The electrodes have an emissive coating that reduces the minimum operating voltage. The glass tube is filled with a combination of neon and argon gases, or pure neon for higher light output (which reduces the life of the component). The top end of the glass tube is heated until it melts, and is pinched off. This creates a distinctive protrusion known as the *pip*.



Figure 19-3. *The same bulb from the previous photograph, energized with 115VAC.*

Ionization

When a voltage is applied between the leads to the bulb, the gas becomes ionized, and electrons and ions are accelerated by the electric field. When they hit other atoms, these are ionized as well, maintaining the ionization level. Atoms are excited by collisions, moving their electrons to higher energy levels. When an electron returns from a higher level to a ground state, a photon is emitted.

This process begins at the *starting voltage* (also known as the *striking voltage*, the *ignition voltage*, or the *breakdown voltage*) usually between 45V and 65V for standard types of bulb, or between 70V and 95V for high-brightness types.

When the bulb is operating, it emits a soft radiance known as a *glow discharge* with a wavelength ranging from 600 to 700 nanometers.



Figure 19-4. *The parts of a neon bulb. See text for details.*

The ionization of the gas allows current to flow through it. This will continue even if the power supply is reduced by 10 to 20 volts to a level known as the *maintaining voltage*.

Negative Resistance

When the glow discharge persists below the starting voltage, this is a form of *hysteresis*, meaning that the neon bulb tends to "stick" in its on state. It remains on while its power supply decreases to the maintaining voltage, but once it switches off, it will "stick" in its off state until the power supply increases again above the maintaining voltage to the starting voltage. The concept of hysteresis is discussed in the entry on **comparators**. See Figure 6-2.

A neon bulb is said to have *negative resistance*. If the current is allowed to increase without restraint, the resistance eventually decreases while the current increases further. If this runaway behavior is not controlled, the bulb will destroy itself.

This behavior is characteristic of gas-discharge tubes generally. A graph showing this appears in Figure 19-5. Note that both scales are logarithmic. Also note that the curve shows how current will be measured in response to voltage. If the voltage is reduced after it has increased, the transitional events shown by the graph will not recur in reverse order. This is especially true if arcing is allowed to begin, as it will almost certainly destroy the component.



Figure 19-5. *A gas discharge tube, such as a neon bulb, is said to have a negative resistance, as current passing through it tends to increase uncontrollably after the gas is ionized and becomes conductive. (Derived from measurements made by David Knight, on a web page named after his radio ham call sign, G3YNH.)*

A neon bulb can be controlled very simply with a series resistor that maintains it in gas-discharge mode. To understand the operation of the resistor, consider the combination of the lamp and the resistor as a voltage divider, as shown in Figure 19-6. Before the lamp begins to pass current, it has an almost infinite resistance. Therefore, the voltage on both sides of the resistor will be approximately equal, the bulb passes almost no current, and it remains dark.



Figure 19-6. *A series resistor is essential to limit the current through a neon bulb.*

After the lamp begins to pass current, the requirement now is for the series resistor to reduce the voltage from the supply level (probably around 110V) to the maintaining level (probably around 90V). This means that the desired voltage drop is 20V, and if the manufacturer's specification tells us that the lamp should pass 1mA (i.e., 0.001 amps), R, the value of the series resistor, is given by Ohm's Law:

```
R = 20 / 0.001
```

Thus, the value for R is 20K. In fact, the value of a resistor supplied with a neon bulb may range from 10K to 220K, depending on the characteristics of the bulb and the supply voltage that will be used.

Now if the bulb's effective internal resistance falls radically, the resistor still limits the currrent. In a hypothetical worst-case scenario, if the bulb's resistance drops all the way to zero, the resistor must now impose the full voltage drop of 110V, and the current, I, will be found by Ohm's law:

```
I = 110 / 20,000
```

That is, about 5mA, or 0.005A.

Neon tubes used in signage require a more sophisticated voltage control circuit which is not included in this encyclopedia.

How to Use It

The use of a neon bulb for an indicator lamp is primarily limited to situations where domestic supply voltage (115VAC or 220VAC) is readily available. "Power on" lights are the obvious application, especially as neon indicators can accept AC. The switch shown in Figure 19-7 is illuminated by an internal neon bulb. The rectangular indicator in Figure 19-8 is designed to run on domestic supply voltage, and its internal bulb and resistor can be clearly seen through the green plastic. The assembly in Figure 19-9 is about 0.5" in diameter, which is the lower limit for neon indicators.



Figure 19-7. *This power switch is illuminated by an internal neon bulb.*



Figure 19-8. *The neon bulb and its series resistor are visible inside this indicator.*



Figure 19-9. *A relatively small neon indicator lamp, designed for insertion in a hole 0.5" diameter.*

Limited Light Output

Neon bulbs have a light output of around 0.06 lumens per milliamp of consumed power (standard brightness type) or 0.15 lumens per milliamp of consumed power (high brightness type).

Comparing this value with the intensity of **LED** indicators is difficult. Their light output is customarily measured in *millicandelas* (mcd), because LED indicators almost always include a lens that focuses the light, and the candela is a measurement of luminous flux within an angle of dispersion. Moreover, because the intensity of neon indicators is not of great interest in most applications, datasheets usually do not supply an intensity value.

One way around the problem of comparisons is to use the standard of *radiant luminous efficacy* (LER), which is defined in the entry on incandescent lamps (see "Efficacy" on page 179). A standard-brightness neon bulb has an LER of about 50 lumens per emitted watt of luminous flux. A light-emitting diode may reach an LER of 100 lm/W. However, a neon bulb operates typically around 1mA while an LED indicator may use 20mA. Therefore, a typical LED indicator may appear to be 30 to 50 times brighter than a typical neon bulb.

Consequently, neon may be an inferior choice in a location where there is a high level of ambient light. Direct sunlight may render the glow of a neon indicator completely invisible.

Efficiency

Because a neon bulb does not use a lot of power and generates negligible heat, it is a good choice where current consumption is a consideration (for example, if an indicator is likely to be on for long periods). The durability and low wattage of neon bulbs, and their convenient compatibility with domestic power-supply voltage, made them a favorite for night-lights and novelty lamps in the past. Figure 19-10 shows an antique bulb containing an ornamental electrode, while Figure 19-11 is a piece of folk art, approximately 1" in diameter, mounted on a plug-in plastic capsule containing a neon bulb.

Ruggedness

Neon bulbs are a good choice in difficult environments, as they are not affected by vibration, sudden mechanical shock, voltage transients, or frequent power cycling. Their operating temperature range is typically from -40 to +150 degrees Celsius, although temperatures above 100 degrees will reduce the life of the lamp.



Figure 19-10. *In bygone decades, ornamental neon bulbs with specially shaped electrodes were popular.*

Figure 19-11. *Neon folk art survives in this hand-painted night-light sold in a Florida tourist shop.*

Power-Supply Testing

When driven by DC current, only the negative electrode (the *cathode*) of a neon bulb will glow. When AC current passes through the bulb, both terminals will glow.

If a bulb (with series resistor) is placed between the "hot" side of a domestic AC power supply and ground, the bulb will glow. If it is placed between the neutral side of the supply and ground, it will not glow.

These features enable a neon bulb to be used for simple power-supply testing.

Life Expectancy

The metal of the electrodes gradually vaporizes during everyday use of a neon bulb. This is known as *sputtering* and can be observed as the glass capsule becomes darkened by deposition of vaporized metal. The electrodes will have a more limited life in a lamp used with DC voltage, where sputtering affects only the cathode. Using AC, the electrodes take turns functioning as the cathode, and vaporization is distributed between both of them.

Failure of a neon lamp can occur as sputtering erodes the electrodes to the point where the maintaining voltage will increase until it almost reaches the level of the power supply. At this point, the bulb will flicker erratically.

Failure can also be defined as a gradual reduction in brightness to 50% of rated light output, caused by accumulated deposition in the glass capsule. Because deposition occurs more heavily on the sides of the bulb, a longer apparent life is possible if the bulb is mounted so that it is viewed from the end.

Typically, neon bulbs are rated for 15,000 to 25,000 hours (two to three years of constant operation). However, the life can be greatly increased by a slight reduction in voltage, which may be achieved by substituting a series resistor with a slightly higher value.

The relationship between operating life and resistor value is shown below. If LA is the normal operating life, LB is the extended operating life, RA is the normal resistor value, and RB is a higher resistor value:

```
LB = LA * ( RB / RA ) 3.3
```

For example, if a normal resistor value is 20K, and it is increased to 22K, the life of the lamp should increase by a factor of slightly more than 1.4.

Variants

A typical neon bulb terminates in leads, and a lamp assembly often has solder tabs, although it may have a base with a screw thread, flange, or bayonet pins for insertion into a compatible socket. A lamp assembly that does not use a base will either snap-fit into a hole of appropriate size and shape, or may be retained with a nut that engages with a plastic thread on the cylinder of the lamp.

Some neon bulbs or lamp assemblies terminate in pins for direct insertion into a printed circuit board.

Almost all neon bulbs operate either in the 100V to 120V range or in the 220V to 240V range.

Light intensity is expressed either as “standard” or “extra-bright,” although datasheets usually do not define those terms.

Nixie Tubes

Nixie tubes, first marketed in 1955, were used to display numerals from 0 through 9 in the days before LEDs took over this capability. They are no longer being manufactured.

Each numeral was physically formed from metal and functioned as an electrode inside a tube filled with a neon-based gas mixture. The typographical elegance of the digits and their aesthetically pleasing glow made Nixies enduringly popular. With a long lifespan, vintage tubes are still usable and can be purchased cheaply from sources such as eBay. Many originate in Russia, where Nixie-type displays were manufactured into the 1980s. The Russian tubes can be identified by their use of a numeral 5 that is a numeral 2 turned upside-down.

Nixie tubes typically require 170VDC. This creates a challenge for a power supply and switching, and can be a safety hazard.

Figure 19-12 shows six Nixie-type tubes repurposed for use as a 24-hour digital clock.



Figure 19-12. *A 24-hour clock using Nixie-type tubes. Source: Wikipedia, public domain.*

What Can Go Wrong

False Indication

Because a neon bulb requires so little power, it may be energized by induced voltages from elsewhere in a circuit, especially if inductive components such as transformers are used. To prevent this, a high-value resistor can be placed in parallel with the bulb, in addition to the series resistor that must always be used.

Failure in a Dark Environment

Because a neon bulb requires a minimal amount of light to initiate its own photon emissions, it may take time to start glowing in a very dim environment, and may not light at all in total darkness. A few bulbs include a small amount of radioactive material that enables them to self-start in complete absence of ambient light.

Premature Failure with DC

The life expectancy quoted in datasheets for neon bulbs usually assumes that they are powered by AC. Because DC results in faster vaporization of the electrodes, the expected lifetime should be reduced by 50% if DC power will be used.

Premature Failure through Voltage Fluctuations

Because the deterioration of a neon bulb accelerates rapidly with current, a sustained voltage that passes slightly more current can radically reduce the expected lifespan.

Replacement

Replacement can be an issue with panel indicators, where disassembly of a device may be necessary to reach the bulb. Bear in mind, however, that an easily removable bulb becomes vulnerable to tampering.

fluorescent light

20

This entry deals primarily with *fluorescent tubes* (infrequently but sometimes described as *fluorescent lamps*), and *compact fluorescent lamps* (CFLs) that are marketed as a substitute for **incandescent lamps**. *Cold-cathode fluorescent lamps* (CCFLs) are also mentioned.

Vacuum fluorescent devices have a separate entry in this encyclopedia. A fluorescent tube or CFL does not contain a vacuum.

Although the diode(s) in a white **LED area lighting** unit are coated with a layer of fluorescent phosphors, they are not categorized here as fluorescent lights, and have their own entry.

A **neon bulb** resembles a fluorescent light in that it is a *gas-discharge* device, but the interior of its glass envelope is usually not coated with fluorescent phosphors, and therefore it has its own entry.

OTHER RELATED COMPONENTS

- **incandescent lamp** (see Chapter 18)
- **LED area lighting** (see Chapter 23)
- **vacuum fluorescent** devices (see Chapter 25)
- **neon bulb** (see Chapter 19)

What It Does

Fluorescent tubes or *compact fluorescent lamps* (CFLs) are primarily used for area lighting. A partially disassembled CFL appears in Figure 20-1, showing the control electronics that are normally hidden inside the base.

There is no standardized schematic symbol to represent a fluorescent light. Figure 20-2 shows three commonly used symbols for a fluorescent tube on the left, and three symbols for a CFL on the right. Note that two of the symbols for a CFL are the same as those for an **incandescent lamp**, shown in Figure 18-1.

How It Works

Luminescence is the emission of light as a result of a process that does not require heat. (The opposite phenomenon is *incandescence*, in which heating causes an object to emit light; see Chapter 18 for a description of **incandescent lamps**.)

Fluorescence is a form of luminescence. It occurs when electrons in a material are energized and then make a transition back to ground level, at which point they radiate their energy as visible light. The incoming energy can consist of other light at a higher frequency. Some creatures, including species of arachnids and fish, will fluoresce when they are lit with ultraviolet light.



Figure 20-1. *A compact fluorescent lamp with its base cut away to reveal the control electronics.*



Figure 20-2. *Schematic symbols to represent fluorescent tubes and bulbs are not standardized. See text for details.*

A *fluorescent tube or lamp* contains a very small amount of mercury vapor that can be stimulated to emit ultraviolet light. This encounters a thin layer of *phosphors* coating the inner surface of the glass enclosure. The light causes the phosphors to *fluoresce*, emitting a diffuse radiance in the visible spectrum.

The tube or lamp also contains one or more inert gases such as argon, xenon, neon, or krypton at about 0.3% of normal atmospheric pressure. Two electrodes inside the glass enclosure are made primarily from tungsten, which can be preheated to initiate ionization of the gas. Confusingly, both electrodes are often referred to as *cathodes*.

The function of the gas is not to emit light, but to conduct electric current, so that free electrons may encounter mercury atoms, raising their electrons briefly to a higher energy level. When one of these electrons reverts from its unstable energized state to its previous energy level, it emits a photon at an ultraviolet wavelength.

Figure 20-3 provides a diagram showing the interior of a fluorescent tube.



Figure 20-3. *The basic parts of a fluorescent tube.*

Ballast and Starter

Heating the tungsten electrodes is necessary but not sufficient to trigger ionization. A high-voltage pulse is also needed when the light is switched on. In a typical 48" tube, the pulse may range from 200V to 300V.

After current flow has been established, the gas, which is now a plasma, enters a phase of negative resistance. Current passing through it will tend to increase even if the voltage decreases. This process must be controlled to prevent the formation of an *arc*, which will destroy the electrodes. (A similar process occurs in any gas discharge tube, such as a **neon bulb**, and is described in a graph in Figure 19-5.)

To heat the electrodes, ionize the gas, and then control the current, the fixture for a fluorescent tube contains components that are separate from the tube. In their simplest, traditional form, these components consist of a *starter* and a *ballast*. The starter is a neon bulb that contains a bimetallic strip serving as a normally closed switch. It allows current to flow through the electrodes in series, to heat them. The basic circuit is shown in Figure 20-4.



Figure 20-4. *The traditional circuit to trigger ionization of the gas in a fluorescent tube uses a starter (shown at the bottom as a neon tube containing a bimetallic strip, which serves as a switch) and ballast (an inductive load, shown at left).*

The starting process may not be immediately successful, in which case the starter may repeat several times in succession, causing the tube to flicker before its discharge becomes stable. In a cold environment, the tube will have more difficulty starting.

After the tube becomes conductive, current between the electrodes bypasses the starter. At this point, the *ballast* limits the current to prevent an arc from forming. The simplest form of ballast is a coil that functions as an **inductor**.

In a more modern system, an *electronic ballast* replaces the starter-ballast combination. It not only applies the initial surge of high current but also raises the 50Hz or 60Hz frequency of the power supply to 10KHz or more. This increases the efficiency of the tube and eliminates any visible flickering of the light.

All compact fluorescent bulbs (CFLs) contain electronic ballasts. The small components visible in Figure 20-1 are the ballast.

Flicker

When a fluorescent tube uses a conventional ballast and is illuminated with 50Hz or 60Hz AC, the glow discharge stops each time the current flow passes through the zero point in its cycle. In fact, the ionized gas in the tube cannot conduct until it is close to the maximum voltage, and stops conducting when the voltage rolls off. Consequently, the voltage across the tube fluctuates in an approximate square wave, and the light output begins and ends very abruptly. Although this occurs 100 times per second on a 50Hz supply and 120 times per second on a 60Hz supply, some people complain that the flicker is noticeable and can induce headaches.

The rapid on-off discharge is hazardous when it illuminates rotating parts in machinery, as a stroboscopic effect can make the parts seem to be stationary. To mitigate this effect, adjacent tubes in a fixture are powered by separate supplies that are out of phase. This is done either by using a three-phase power supply or by adding an LC circuit to the supply for one of the tubes.

Variants

The traditional type of ballast is also known as a *rapid-start ballast*. By preheating the electrodes, it reduces damage to them that otherwise tends to occur during the starting process. A tube designed for use with a rapid-start ballast has two contacts at each end, and is referred to as a *bi-pin* tube.

An electronic ballast is also known as an *instant-start ballast*. It does not preheat the electrodes, and a tube designed to work with it has only one pin at each end.

CCFLs

A *cold cathode fluorescent lamp* (CCFL) may resemble a miniature fluorescent tube, typically measuring 2mm to 5mm in diameter. The tube may be straight or bent into a variety of shapes. It works on the same principle as a full-size fluorescent tube, containing mercury vapor and one or more inert gases, with an interior coating of phosphors to enable fluorescence. CCFLs are available in many colors and many shades of white.

As its name implies, the electrodes in a CCFL are not heated to establish ionization. Instead, a very high voltage (1,000VAC or more) is applied, dropping to 500VAC to 600VAC after the flow of current has been established. Because CCFLs have been often used to backlight laptop computer screens, inverter circuits are commonly available that create a high-frequency output at a high voltage from an input that can range from 3VDC to 20VDC. The inverter also includes provision to dim the CCFL by using *pulse-width modulation*.

Some CCFLs are designed for illumination of small spaces—for example, the interior of a display case. A few CCFLs look exactly like CFLs and can be used in light fixtures. Some may be compatible with the type of dimmer designed for incandescent lamps.

A CCFL usually has a limited light output compared with that of a conventional fluorescent tube, but has the advantage of working better at low temperatures. Some are designed for signage and exterior lighting in cold-weather locations.

They have a relatively long lifetime of up to 60,000 hours. A hot-cathode fluorescent lamp may fail between 3,000 and 15,000 hours.

Any tube or bulb that uses unheated electrodes to ionize a gas is technically a cold-cathode device, but will not be identified as a CCFL unless it also has an inner layer of phosphors to achieve fluorescence.

It is important to match a tube with the type of ballast installed in a fixture. This is not an issue with CFLs, as they have the appropriate ballast built in.

Sizes

Straight bi-pin tubes are sold in the United States in the following standard sizes:

- T5: 5/8″ diameter. A more modern tube, but still with tungsten electrodes that serve to heat it.
- T8: 1″ diameter. Very often 24″ or 48″ in length, consuming 18W or 36W respectively.
- T12: 1-1/2″ diameter.
- T17: 2-1/8″ diameter.

CFLs are sold in a very wide variety of configurations.

Comparisons

Fluorescent lights have significant advantages and disadvantages. On the plus side:

- After the fixture containing the ballast has been paid for, a tube is relatively cheap. A CFL or an LED light does not have this advantage, as the electronics are built in and will be discarded when the light fails.
- Fluorescent lights have a longer life than incandescent bulbs.
- Fluorescent lights are available in a wide range of shades of white.
- Fluorescent tubes create a diffuse radiance that is ideal for general lighting using ceiling-mounted fixtures. They do not cast harsh shadows.

On the minus side:

- Fluorescents were traditionally more energy-efficient than any other light source, but **LED area lighting** is now more efficient in some designs. LEDs are expected to become more efficient in the future.
- A fluorescent tube with a traditional type of ballast may cause complaints of flickering. By comparison, an LED light uses DC, and an incandescent bulb retains sufficient heat between power cycles so that it does not appear to flicker.
- Fluorescent flicker creates problems when shooting video.
- The fluorescent emission spectrum has sharp peaks that give the lighting an unnatural look.
- In applications that require a defined beam of light, a fluorescent source cannot be used.
- Conventional ballasts can create radio interference, especially in the AM band.
- Because fluorescent tubes and bulbs contain mercury, they require proper disposal, which can incur fees.
- Even an instant-on fluorescent light tends to hesitate briefly when it is switched on.
- The lifespan of a fluorescent light is greatly reduced if it is cycled on and off frequently. An incandescent bulb is less severely affected by cycling, and an LED light is not affected at all.
- Fluorescent lights have difficulty starting at low temperatures.

Values

Brightness

The intensity of a fluorescent light is measured in *lumens per watt*. Because invisible wavelengths are of little interest when assessing brightness, *luminous flux* is used to describe apparent brightness in the visible spectrum. The unit for luminous flux is the *lumen*. Additional information about light measurement is included in the entry describing incandescent lamps (see "Power" on page 177).

Spectrum

The spectrum of photons emitted from mercury vapor in a fluorescent light has wavelengths that peak at 253.7 nanometers and 185 nanometers. (A *nanometer*, customarily abbreviated as nm, is one-billionth of a meter.) These wavelengths are invisible, being in the ultraviolet range, but when the light is transposed into the visible spectrum by the layer of phosphors, "spikes" in the range of wavelengths are still present. For a comparison of output curves for incandescent, fluorescent, and LED lights, see the graph in Figure 18-4.

Various formulations for the phosphors in a tube or CFL attempt to modify the character of the light to suit the human eye, but none of them looks as "natural" as the radiance from an incandescent bulb, probably because the characteristics of incandescent light are very similar to those of sunlight.

What Can Go Wrong

Unreliable Starting

At a low temperature, the mercury inside a fluorescent tube may be slow to vaporize. At very low temperatures, vaporization may not be possible at all. Until the mercury vaporizes, fluorescence will not occur.

Terminal Flicker

As a tube ages, it may start to conduct current only in one direction, causing it to flicker visibly. As it ages more, the gas discharge becomes even less reliable, and the flicker becomes erratic. Eventually, the gas discharge fails completely. In this state, a tube may show only a dim light at each end, in proximity to the tungsten electrodes.

Cannot Dim

Neither the older style of "conventional" ballast nor a modern electronic ballast will respond appropriately to a dimmer of the type designed for incandescent bulbs. This may be an important factor when an incandescent bulb is swapped out for a CFL.

Burned Out Electrodes

Like the tungsten filament in an **incandescent lamp**, the tungsten electrodes in a fluorescent tube suffer progressive erosion. This is evident when a black tungsten deposit forms on the inside of the tube at one or both ends.

Ultraviolet Hazard

Some critics of CFLs maintain that the complex shape of a coiled or zig-zag tube tends to permit small imperfections in the internal phosphor coating, potentially allowing ultraviolet light to escape. If this occurs, and if a CFL is used in a desk fixture in close proximity to the user, ultraviolet light could elevate the risk of skin cancer.

laser

21

The term *maser* was coined in the 1950s to describe a device that used stimulated emission to amplify microwaves. When a device using similar principles amplified visible light in 1960, it was termed an *optical maser*. However, that term is now obsolete, having been replaced with **laser**. This term is always printed in lowercase letters, even though it is an acronym for Light Amplification by Stimulated Emission of Radiation.

The invented verb *to lase* is derived from *laser* and is used to describe the process of generating laser light, with the past participle *lased* and present participle *lasing* sometimes being used.

Thousands of laser variants exist. Because of space limitations, this entry will concentrate primarily on *laser diodes*, which are the smallest, most common, and most affordable type.

OTHER RELATED COMPONENTS

- **LED indicator** (see Chapter 22)

What It Does

A **laser** generally emits a thin beam of intense light, often in the visible spectrum, and usually in such a narrow range of wavelengths, it can be considered *monochromatic*. The light is also *coherent*, as explained below.

Light output from a laser has three important attributes:

- Intensity. A high-powered laser can deliver energy to a very small, well-defined area, where it may be capable of burning, cutting, welding, or drilling. Large lasers may also be used as weapons, or for power transmission.
- Collimation. This term describes a beam of light that has parallel boundaries, and therefore does not disperse significantly when passing through a transparent medium such as air, glass, or a vacuum. A laser beam can have such excellent collimation, it can be used in precision measuring devices, and has been transmitted over very long distances, even from the Earth to the Moon, where astronauts placed reflectors during the Apollo missions.
- Controllability. Because the beam can be generated with eletrical power, its intensity can be modulated rapidly with relatively simple electronic circuits, enabling applications such as burning microscopic pits in the plastic of a CD-ROM or DVD.

Laser diodes are now more common than all other forms of lasers. They are found in pointers, printers, barcode readers, scanners, computer mice, fiber-optic communications, surveying tools, weapon sights, and directional lighting sources. They are also used as a light source to trigger more powerful lasers.

No generic symbol is used for a laser, but a laser diode is often represented with the same symbol that is used for a light-emitting diode. See Figure 22-2 in the entry for **LED indicators**.

How It Works

A laser is built around a *gain medium*, which is a material that can amplify light. The medium can be a solid, liquid, gas, or plasma, depending on the type of laser.

Initially, an input of energy provides stimulation for some atoms in the gain medium. This is known as *pumping* the laser. The energy input can come from a powerful external light source, or from an electric current.

Stimulation of an atom raises the quantum energy level of an electron associated with the atom. When the electron collapses back to its former energy state, it releases a photon. This is known as *spontaneous emission*.

If one of the photons encounters an atom that has just been excited by the external energy source, the atom may release two photons. This is known as *stimulated emission*. Beyond a threshold level, the number of released photons can increase at an exponential rate.

If two parallel reflectors are mounted at opposite ends of the gain medium, they form a *resonant cavity*. Light bounces to and fro between the reflectors, while pumping and stimulated emission amplifies the light during each pass. If one of the mirrors is partially transparent, some of the light will escape through it in the form of a laser beam. The partially transparent mirror is known as the *output coupler*.

Laser Diode

A laser diode contains an **LED**. (See "How It Works" on page 207 for a more detailed description of the function of an LED.) The p-n junction of the diode functions as the resonant cavity of the laser. Forward bias injects charges into the junction, causing spontaneous emission of photons. The photons, in turn, cause other electrons and electron-holes to combine, creating more photons in the process of stimulated emission. When this process crosses a threshold level, current passing through the diode causes it to *lase*.

The original patent for a laser diode was filed by Robert N. Hall of General Electric in 1962, and the diagram in Figure 21-1 is derived from the drawing in that patent, with color added for clarity.



Figure 21-1. *The original design for a laser diode, from the patent filed in 1962.*

In the figure, the junction shown as a yellow layer forms the resonant cavity in which lasing occurs. It measures only 0.1 microns thick (the diagram is not drawn to scale). Its vertical front side is highly polished, and is parallel to the back side, which is also highly polished. Thus, photons reflect between these two vertical sides. The slanted face visible in the figure, and the other slanted face opposite it, are oriented and roughened to minimize internal reflection between them.

Figure 21-2 shows a simplified cross-section of the laser diode.



Figure 21-2. *Simplified cross-section of a laser diode.*

Figure 21-3 shows a cross-section of the diode installed in a component sold as a laser. It includes a photodiode to sense the intensity of light emerging through the polished rear end of the laser diode. External electronics are necessary to control the intensity of the laser, using feedback from the photodiode.

The component has three pins (shown pale yellow in the figure), one connecting to the photodiode, another connecting to the p-type layer of the laser diode, and the third being common to the n-type layer of the laser diode and the ground side of the photodiode.

A photograph of a laser diode is shown in Figure 21-4. Note the three pins, comparable to the pins shown in Figure 21-3, indicating that this component requires external control electronics.

In Figure 21-5, a laser is shown with a surface-mount chip adjacent to the solder pad connecting the blue wire. The presence of this chip, with only two wires, indicates that this component has its own control electronics and requires only a DC power supply.



Figure 21-3. *A laser diode is typically mounted with a photodiode to provide feedback for a driver circuit, to control the current consumed by the laser.*



Figure 21-4. *Lite-On 505T laser diode that emits light at 650nm. Power consumption 5mW at 2.6VDC. As indicated by the graph squares, this component is only about 0.2" in diameter.*



Figure 21-5. *This laser incorporates its own control electronics and requires only a 5VDC power supply. It draws 30mA and generates an output up to 5mW.*

Coherent Light

The emission of *coherent light* by a laser is often explained by suggesting that wavelengths are synchronized with each other. In fact, there are two forms of coherence that can be described approximately as *spatial coherence* and *wavelength coherence*.

If an observer looks up at a cloudy sky, the eye will perceive light radiating chaotically from many distances and directions. Thus, the light is not spatially coherent. The light also consists of many wavelengths, and thus it is not wavelength-coherent.

The filament of an incandescent lamp is a much smaller source of light, but still large enough to generate a profusion of light emissions that are spatially incoherent. The light also includes many different wavelengths.

Suppose a barrier containing a very tiny hole is placed in front of the **incandescent lamp**. If the aperture is very small, an observer on the far side will see the light as a point source. Consequently, the light that emerges from it is now spatially coherent, and will not have chaotically overlapping waves. If the light then passes through a filter, its wavelengths also will become coherent. This is suggested in Figure 21-6 where the light source is an incandescent lamp emitting a wide range of wavelengths.



Figure 21-6. *An incandescent lamp, at the bottom of the figure, emits incoherent light at many wavelengths (exaggerated here for clarity). When it passes through a pinhole, it becomes spatially coherent. When it then passes through a colored filter, it becomes wavelength coherent.*

The small amount of light emerging through a pinhole is inevitably much dimmer than light from the original source. A laser, however, amplifies its light output, as well as tending to behave like a point source. The “hall of mirrors” effect of the parallel reflective surfaces in the resonant cavity causes much of the light to shuttle to and fro over a long distance before it emerges through the output coupler. Any light that deviates significantly from the axis of the laser will not escape at all, because the deviations will be cumulative with each reflection. Thus, the light from a laser appears to come from a point source at an almost infinite distance.

Because of the particular geometry of a light-emitting diode, the output from a laser diode is not naturally collimated, and tends to spread by an angle of around 20 degrees. A lens must be used to focus the beam.

Variants

Lasers are sold generally as fully assembled tools for a specific purpose. A very brief summary of CO2, fiber, and crystal lasers is included here.

CO2 Lasers

The gain medium is primarily carbon dioxide but also contains helium and nitrogen, with sometimes hydrogen, water vapor, and/or xenon. The laser is electrically pumped, causing a gas discharge. Nitrogen molecules are excited by the discharge and transfer their energy to the CO2 molecules when colliding with them. Helium helps to return the nitrogen to base energy state and transfer heat from the gas mixture.

CO2 lasers are infrared, and are commonly used in surgical procedures, including ophthalmology. Higher powered versions have industrial applications in cutting a very wide range of materials.

Fiber Lasers

Light is pumped via diodes and amplified in purpose-built glass fibers. The resulting beam has a very small diameter, providing a greater intensity than CO2 lasers. It can be used for metal engraving and annealing, and also for working with plastics.

Crystal Lasers

Like fiber lasers, they are pumped by diodes. These compact lasers are available in a very wide variety of wavelengths, covering the whole visible spectrum, infrared, and ultraviolet. They find applications in holography, biomedicine, interferometry, semiconductor inspection, and material processing.

Values

The output power of a laser is measured in watts (or milliwatts). This should not be confused with the power consumed by the device.

In the United States, any device sold as a laser pointer is limited to a power output of 5mW. However, laser diodes packaged similarly to laser pointers can be mail-ordered with an output of 200mW or more. The legal status of these lasers may be affected by regulations that vary state by state.

In a CD-RW drive that is capable of burning a disc, the diode may have a power of around 30mW. A laser mounted in a CD-ROM assembly is shown in Figure 21-7.



Figure 21-7. *An assembly incorporating a laser for reading a CD-ROM.*

Lasers have such a narrow range of wavelengths, they are given specific output values in nanometers. A laser in an optical mouse may have a wavelength of 848nm; in a CD drive, 785nm; in a bar-code reader, 670nm; in a modern laser pointer, 640nm; in a Blu-ray disc player, 405nm.

How to Use It

While powerful lasers in a laboratory setting have exotic applications, a typical low-power laser diode has become so affordable (costing less than $5 in some instances, at the time of writing) it can be considered merely as a useful source of a clearly defined light beam, ideal for detecting the position of a movable mechanical component or the presence of an intruder.

Generic light-emitting diodes are made with a view angle (i.e., a dispersion angle) as low as 3 degrees, but the beam is soft-edged compared with the precise boundary of a laser beam, and cannot be used reliably in conjunction with sensors at a distance of more than a few inches.

Laser diodes that are sold as components may or may not have current-limiting control electronics built in. Applying power to the laser diode directly will result in thermal runaway and rapid destruction of the component. Drivers for laser diodes are available separately as small, preassembled circuits on breakout boards.

For many applications, it may be simpler and cheaper to buy a laser diode as an off-the-shelf product. A laser pointer provides an easy way to get a source of laser light, and if it would normally be driven by two 1.5V batteries, it can be adapted to run off a 5V supply by using a 3.3V voltage regulator.

Common Applications

In addition to being used with PowerPoint presentations and in conjunction with position sensors, laser pointers have other applications:

- Astronomy. A high-powered laser beam is visible even in clear air as a result of interaction with air molecules. This is known as *Rayleigh scattering*. The phenomenon allows one person to point out a star (or planet) for another person. Because celestial objects are so far away, parallax error is not detectable by two people viewing the beam while standing next to each other. A laser pointer may also be mounted on a telescope to assist in aiming the telescope at an object of interest. This is easier than searching for an object through an eyepiece.
- Target acquisition. Lasers are commonly used on firearms to assist in targeting, especially in low-light conditions. Infrared lasers can be used in conjunction with infrared viewing goggles.
- Survival. A small laser can be included in emergency supplies to signal search teams. A laser can also be used to repel predatory animals.

What Can Go Wrong

Risk of Injury

Lasers are potentially dangerous. Those that have an infrared or ultraviolet output are more dangerous than those with a visible beam, as there is no visual warning that the laser is active. A laser is capable of scarring the retina, although controversy exists regarding the power output that should be considered a high risk.

If a project incorporates a laser, it should be switched off while building or testing the device. It may be advisable to wear protective glasses that block laser light even when an experimenter feels confident that a laser is switched off.

Active lasers should never be pointed at people, vehicles, animals (other than dangerous animals), or oneself.

Inadequate Heat Sink

Lasers may be designed and rated for intermittent use. The burner assembly for a CD-ROM drive, for instance, will be rated for pulsed power, not continuous power. Read datasheets carefully, and provide an adequate heat sink.

Uncontrolled Power Supply

A diode laser that does not have a feedback system in place to control the flow of current can self-destruct.

Polarity

Both the light-emitting diode and the photodiode in a three-pin laser package can be damaged by incorrect polarity of applied power. Pin functions should be checked carefully against datasheets.

LED indicator

22

In this encyclopedia, an **LED indicator** is defined as a component usually 10mm or smaller in diameter, made of transparent or translucent epoxy or silicone, most often containing one *light-emitting diode*. It is purposed as a status indicator in a device, rather than as a source of illumination, and is sometimes referred to as a *standard LED*.

LED indicators that emit infrared and ultraviolet light are included in this entry. LEDs that are designed to illuminate large interior or exterior areas are discussed in a separate entry as **LED area lighting**. They are sometimes described as *high-brightness LEDs* and almost always emit white light.

The term **light-emitting diode** is becoming less common, as the acronym **LED** has become ubiquitous. The acronym does not usually include periods between the letters.

The words “light emitting” are hyphenated here, as they form an adjectival phrase, but in everyday usage the hyphen is often omitted, and no definitive rule seems to exist.

Originally, a standard LED contained only one diode, but may now include multiple diodes, either to emit additional light or to provide a range of colors. In this encyclopedia, a single epoxy or silicone capsule is still considered to be an **LED indicator** regardless of how many diodes it contains. By contrast, any component consisting of multiple separately discernible light-emitting diodes, as in a seven-segment numeral, a 14- or 16-segment alphanumeric character, a dot-matrix character, or a display of multiple characters, is listed in a separate entry as an **LED display**.

OTHER RELATED COMPONENTS

- **LED area lighting** (see Chapter 23)
- **LED display** (see Chapter 24)
- **incandescent lamp** (see Chapter 18)
- **neon bulb** (see Chapter 19)
- **laser** (see Chapter 21)

What It Does

An **LED indicator** emits light in response to a small current, typically around 20mA (but sometimes much less), at a voltage lower than 5VDC. It is usually molded from epoxy or silicone that may be colorless and transparent (often referred to as *water clear*), or colorless but translucent, or tinted and transparent, or tinted and translucent.

The color of the light is initially determined by the chemical compounds used internally, and by their dopants; therefore, a water-clear LED may emit colored light.

Ultraviolet LEDs are usually water-clear. Infrared LEDs often appear to be black, because they are opaque to the visible spectrum while being transparent to infrared.

When an LED indicator is described as being *through hole,* it has leads for insertion into holes in a circuit board. The term does not mean that the indicator itself is meant to be pushed through a hole in a panel, although this may also be done. The LED is cylindrical with a hemispherical top that acts as a lens. The leads are relatively thick, to conduct heat away from the component. A dimensioned diagram of a typical LED measuring 5mm in diameter is shown in Figure 22-1.



Figure 22-1. *Dimensions of a typical 5mm LED. The longer wire connects with the anode, while the shorter wire connects with the cathode. Adapted from a datasheet published by Lite-On Technology Corporation.*

An LED indicator that is not the through-hole type is usually a surface-mount component. LEDs for surface mounting are mostly rectangular and can be as small as 1mm x 0.5mm. They may require a *heat sink*.

Schematic Symbols

Figure 22-2 shows a variety of symbols that are commonly used to represent an LED. The triangle at the center of each symbol points in the direction of conventional (positive-to-negative) current flow—from the anode to the cathode. Each pair of arrows radiating away from the diode indicates emitted light. Wavy arrows are sometimes used to represent infrared (thermal) radiation. Often, however, an infrared LED is represented in exactly the same style as an LED that emits visible light. With the exception of the wavy arrows, the various styles of schematic symbol are functionally identical and do not identify different attributes of the component such as size or color.



Figure 22-2. *Various symbols may be used to represent an LED. See text for details.*

Common Usage

LED indicators have mostly displaced **neon bulbs** and miniature **incandescent lamps** for the purpose of showing the status of a device. They are found in industrial control panels, home audio systems, battery chargers, washer/dryers, and many other consumer-electronics products. Higher output variants are used in flashlights, traffic signals, taillights on automobiles, and for illumination of subjects that are being photographed. LED indicators may be assembled in large numbers in attention-getting displays such as Christmas lights.

Red, orange, yellow, green, and blue are the basic standard colors. LEDs that appear to generate white light are common, but they do not emit an evenly weighted spectrum of wavelengths. See "Non-Incandescent Sources" on page 174 for a discussion of this topic.

How It Works

An LED, like any **diode**, contains a semiconductor *PN junction* that conducts current only in the forward direction (i.e., from the more-positive side of a power supply to the more-negative side). The diode becomes conductive above a *threshold voltage* sufficient to force electrons in the n-type region and holes in the p-type region to combine with each other. Each time this occurs, energy is released. The energy liberated by one electron-hole combination creates a *photon*, or one quantum of light.

The amount of energy released depends on the *band gap*, which is a property of the semiconductor material. The band gap is the smallest energy that can create an electron-hole pair. The energy determines the light's wavelength, and thus the color.

The band gap also determines the threshold voltage of the LED. For this reason, LEDs of different colors have widely different threshold voltages.

Because an LED will often be used in devices where the DC power supply exceeds the maximum forward voltage, a *series resistor* is customarily used as a simple way to restrict current through the diode.

The light emitted by a colored LED indicator tends to include only a narrow range of wavelengths. However, the addition of a phosphor coating to the diode can broaden the output. This technique is used to make the light from a blue LED appear white, as shown in Figure 22-3. Most white LEDs are actually blue LEDs with a colored phosphor layer added. See the section on **LED area lighting** in Chapter 23 for a more detailed discussion of this topic.



Figure 22-3. *Increasing the range of emitted wavelengths by adding phosphors to a blue LED. Source: Philips Gardco Lighting.*

Multicolor LEDs and Color Mixing

If red, green, and blue light sources are mounted extremely close together, the eye perceives them as a single source, of a color determined by their combined relative intensities. This system of additive color mixing is shown in Figure 17-14 in the entry dealing with LCDs. It is used in LED indicators that contain red, green, and blue light-emitting diodes in a single epoxy or silicone capsule.

While most video monitors use white LEDs or **fluorescent lights** to form a backlight for an **LCD** video screen, some high-end monitors use a matrix of very tiny red, green, and blue LEDs, because the combination of these separate colors generates a wider *gamut* of color wavelengths. The concept of gamut is discussed in "Color" in the **LCD** entry. The tiny LEDs in a backlight cannot be considered as indicators, but indicators are used for this purpose in billboard-sized video displays.

Variants

LED indicators vary widely in size, shape, intensity, view angle, diffusion of light, wavelength of light, minimum and maximum forward voltage, and minimum and maximum forward current.

Size and Shape

The original sizes for round LED indicators were 3mm, 5mm, or (more rarely) 10mm in diameter. Today, through-hole LEDs are sold in many intermediate sizes, although 3mm and 5mm are still most widely used.

The traditional round LED indicator is now augmented with square and rectangular shapes. In a parts catalog, a pair of dimensions such as 1mm × 5mm suggests that the LED is rectangular.

Intensity

The light intensity of an LED is usually expressed in *millicandelas*, abbreviated *mcd*. There are 1,000 mcd in a candela. For more information about units for measurement of light, see "Intensity" on page 178.

The candela measures the *luminous flux*, or visible radiant power, contained within a specified angle of dispersion, usually referred to as the *view angle*. This can be imagined as the rotated angle at the apex of a cone, where the cone defines the "spread" of the light, and the source is at the apex.

If a diode is emitting a fixed amount of luminous flux, the rating in mcd will increase with the inverse square of the view angle. This is because the light delivered to an area in front of the LED will become more intense as the angle becomes smaller. The use of mcd to rate the brightness of an LED can be misleading if it is not considered in comparison with the view angle.

For example, suppose an LED is rated at 1,000 mcd and has a view angle of 20 degrees. Now suppose the same diode is embedded in a different epoxy or silicone capsule with a lens that creates a view angle of only 10 degrees. The LED will now be rated at 4,000 mcd, even though its total power output is unchanged.

- To compare the brightness of two LED indicators meaningfully, they should share the same view angle.

Four through-hole LED indicators with a wide range of specifications are shown in Figure 22-4. From left to right: water-clear white generic, 10mm; Vishay TLCR5800 5mm (emitting red, even though the capsule is water-clear), rated for 35,000mcd with 4 degrees view angle; Everlight HLMPK150 5mm red diffused, rated for 2mcd with 60 degrees view angle; and Chicago 4302F5-5V 3mm green, rated for 8mcd at 60 degrees view angle, containing its own series resistor to allow direct connection with a 5VDC power supply.



Figure 22-4. *Four assorted LED indicators with very different specifications. See text for details.*

Efficacy

The *radiant luminous efficacy* (LER) of an incandescent light source compares how effective it is at channeling its output within the visible spectrum, instead of wasting it in other wavelengths, especially infrared. Note that the word *efficacy* has a different meaning from *efficiency*. The LER acronym may help to avoid confusion.

LER is expressed in lumens per watt, and in an incandescent bulb it is calculated by dividing the power emitted in the visible spectrum (the *lumi-*

nous flux) by the power emitted over all wavelengths. This is described in detail on "Efficacy" on page 179 in the entry dealing with incandescent lamps.

In an LED indicator, almost all the radiation can be within the visible spectrum, but some power is wasted by generating heat internally. The efficacy varies depending on the type of LED; thus a red-orange indicator can have an efficacy of 98% while a blue LED will be probably below 40%.

Diffusion

Some LED indicators use epoxy or silicone that is formulated to be translucent or "cloudy" instead of transparent. They diffuse the light so that it is not projected in a defined beam, has a softer look, and has an approximately equal intensity when viewed from a wider range of angles.

"Clear" and "diffused" are options that must be taken into account when choosing LEDs from an online catalog, unless the user is willing to turn a clear LED into a diffuse LED by applying some sandpaper.

Wavelength and Color Temperature

The wavelength of light is measured in *nanometers* (abbreviated *nm*), a nanometer being 1 billionth of a meter. The visible spectrum extends from approximately 380nm to 740nm. Longer wavelengths are at the red end of the spectrum, while shorter wavelengths are at the blue end.

A typical LED emits a very narrow range of wavelengths. For example, Figure 22-5 shows the emission from a standard red LED indicator manufactured by Lite-On. Graphs of this type are typically included in manufacturers' datasheets.

Because a red LED stimulates the cones in the eye that respond to red light, it "looks red" even though the color is not comparable with the natural red that is seen, for instance, in a sunset. That natural color actually contains an additional spread of wavelengths.



Figure 22-5. *The narrow range of wavelengths emitted by a typical red LED indicator.*

The following list shows the ranges of peak output values, in nanometers, for the most commonly available basic LED indicators (LEDs that emit other wavelengths are available, but they are less common):

- Infrared LED: 850 to 950
- Red LED: 621 to 700
- Orange LED: 605 to 620
- Amber LED: 590 to 591
- Yellow LED: 585 to 590
- Green LED: 527 to 570
- Blue LED: 470 to 475
- Ultraviolet LED: 385 to 405

Figure 22-6 shows this list graphically, omitting infrared and ultraviolet LEDs.

For almost 30 years, blue LEDs were a laboratory curiosity of little practical value, as efficiencies were stuck around 0.03%. An efficiency of more than 10% was finally achieved in 1995. Blue LEDs were marketed soon afterward.

However, when yellow phosphors are added to create the impression of white light by spreading the output over the whole visible spectrum, the wavelengths around 500nm are still not well represented, as suggested in Figure 22-3.



Figure 22-6. *Ranges for peak wavelengths of the most commonly used LEDs. (Source: Survey of approximately 6,000 through-hole LEDs stocked at www.mouser.com.)*

Fluorescent lights perform even more poorly than white LEDs, as can be seen in Figure 18-4 in the entry describing **incandescent lamps**.

Because white LEDs do not emit a single peak of wavelengths, their color is expressed in color temperature rather than nanometers. The concept of color temperature is explained in "Spectrum" on page 173. White LEDs are available rated from 2,800 to 9,000 degrees Kelvin, and are discussed in more detail in the **LED area lighting** entry in this encyclopedia.

Internal Resistor

To eliminate the chore of adding a series resistor to limit current through an LED, some indicators are sold with a series resistor built in. They may be rated for use with 5VDC or 12VDC, but are externally indistinguishable from each other. They are also externally indistinguishable from LEDs that do not contain series resistors. Figure 22-7 shows two 3mm LEDs, the one on the right containing its own series resistor, the one on the left being a generic LED without a series resistor.

Because of the nonlinear response of a diode, LEDs with or without internal resistors cannot be distinguished from each other reliably with a multimeter. If the meter is set to measure ohms, typically it will give an "out of range" error to all types of LED. If it is set to identify a diode, the reading will not tell you if the LED contains a resistor.



Figure 22-7. *An LED (left) that does not contain its own series resistor is usually indistinguishable from one that does (right).*

One way to determine whether an LED contains an internal series resistor would be to connect it with a variable power supply through a multimeter set to measure mA. Carefully increase the supply voltage from zero until the meter shows a current of 20mA. If the LED does not contain a series resistor, the supply voltage will be close to the recommended forward voltage for that type of LED (no lower than 1.6V for a red LED, and no higher than 3.6V for a white LED). If the LED does contain a series resistor, the supply voltage will be higher. This procedure is time consuming, but may be worthwhile to evaluate multiple LEDs that are known to be identical.

Multicolored

The leads for an LED indicator containing two or more diodes can be configured in several ways:

- Two leads, two colors. Two diodes are mounted internally in parallel, but with opposite polarity.
- Three leads, two colors. Two diodes share a common anode or common cathode.
- Four leads, three colors (RGB). Three diodes share a common anode or common cathode.

- Six leads, three colors. Three diodes, each with its own pair of leads, separate from the others.

Infrared

Most infrared emitters are LEDs that generate wavelengths longer than 800nm. They are found in handheld remotes to control consumer-electronics devices such as televisions and stereo systems, and are also used in some security systems, although *passive infrared motion detectors*, which assess infrared radiation from sources such as people or vehicles, are more commonly used for this purpose.

In conjunction with an infrared emitter, an infrared sensor is necessary, and must be sensitive to the same wavelength. To prevent false positives, the emitter modulates its output, typically with a carrier frequency between 10 and 100kHz. Remotes often use carrier frequencies of 30 to 56kHz. At the receiving end, the signal is processed with a band-pass filter matching the modulation frequency. Many different pulse-coding schemes are used, and no particular standard is dominant.

Ultraviolet

Because ultraviolet radiation can damage the eyes, LED indicators that emit ultraviolet light are potentially dangerous and should be used with caution. A yellow eyeshield can be worn to block the short wavelengths.

Ultraviolet light can be used to cure some adhesives and dental filling material. It can also kill bacteria, and can detect fluorescent print on bank notes, to check for counterfeiting. Ultraviolet flashlights are sold to detect some species of pests, such as scorpions, which fluoresce in response to ultraviolet light.

Values

The specification for an LED will include the wavelength of emitted light, luminous intensity, maximum forward voltage and current, maximum reverse voltage and current, and working values for voltage and current. All these values are important when choosing an indicator for a specific function.

White LEDs for room lighting or external use are calibrated differently. See the entry for **LED area lighting** in Chapter 23.

Forward Current

About half of all the thousands of available types of LED indicators are rated for a typical forward current of 20mA to 25mA. Absolute maximum ratings may be twice as high, but should not generally be applied.

The light intensity of a typical 5mm red LED indicator is plotted against its forward current in Figure 22-8. Note that current and light intensity have an approximately linear relationship up to the typical working current of 20mA. Even above this point, to the absolute maximum of 50mA, the light intensity rolls off only a very small amount.

Although an LED indicator can be dimmed by controlling the current passing through it, the current does not have a linear relationship with the applied voltage, and the indicator will stop functioning completely when the voltage drops below the threshold required by the diode. Consequently, LEDs are commonly dimmed by using *pulse-width modulation*.

Because of the nonlinear response of a diode, LEDs with or without internal resistors cannot be distinguished from each other reliably with a multimeter. If the meter is set to measure ohms, typically it will give an “out of range” error to all types of LED. If it is set to identify a diode, the reading will not tell you if the LED contains a resistor.

Low-Current LEDs

Indicators that require a very low forward current are convenient for direct connection to output pins of logic chips and other integrated circuits. Although a single output from an HC family chip is capable of supplying 20mA without damaging the chip, the current will pull down the output voltage, so that it cannot be used reliably as an input to another chip while also lighting the LED.



Figure 22-8. *The relationship between forward current and light intensity of a typical 5mm LED indicator is approximately linear up to the 20mA operating current, and almost linear up to the absolute maximum of 50mA.*

Various LED indicators drawing 2mA or 1mA are available, with intensities typically ranging between 1.5mcd and 2.5mcd. This low light output is still bright enough for viewing in a lab-bench environment. Low-current blue LEDs are not available. The only LEDs that draw as little as 1mA are red, as this is the most efficient type.

Using a higher value series resistor with a generic LED will of course reduce its current consumption, and some light will be visible so long as the forward voltage across the LED remains at its minimum level or above.

Forward Voltage

Red is the color that requires not only the least forward current, but the lowest forward voltage. In the range of 1.6VDC to 1.7VDC, all the LEDs are red. Typical forward voltages for various colors are shown here:

- Infrared LED: 1.6V to 2V
- Red LED: 1.6V to 2.1V
- Orange LED: 1.9V to 2.1V
- Amber LED: 2V to 2.1V
- Yellow LED: 2V to 2.4V
- Green LED: 2.4V to 3.4V
- Blue LED: 3.2V to 3.4V
- Ultraviolet LED: 3.3V to 3.7V
- White LED: 3.2V to 3.6V

Color Rendering Index

The *color rendering index* (CRI) evaluates the fidelity with which a light source is capable of displaying the full visible spectrum. It ranges from a perfect score of 100 down to 0 or even lower (sodium-vapor street lighting has a negative value). Computing the index requires standard reference color samples and has been criticized for generating scores that do not correlate well with subjective assessments.

Incandescent bulbs can have a CRI of 100, while an uncorrected white LED may score as low as 80.

Life Expectancy

Because the light output from an LED tends to decrease very gradually with time, the life expectancy is often defined as the number of hours required for the output to diminish to 70% of its output when new. Life expectancy is commonly stated on datasheets for high-brightness white LEDs, but is often omitted from datasheets for LED indicators.

Unlike incandescent lamps and fluorescent lights, LEDs do not have a shorter lifespan if they are frequently cycled on and off.

Light Output and Heat

The light intensity of an LED, measured in mcd, can vary from a few mcd to a maximum of 40,000mcd. Intensities above 30,000mcd generally are achieved by limiting the view angle to 15 degrees or less. Because the candela is weighted toward the central, green segment of the visible spectrum, green LEDs are likely to have a relatively high mcd rating. LEDs rated between 20,000mcd and 30,000mcd, with a view angle of 30 degrees, are almost all green.

Datasheets may often include a *derating curve* showing the lower limit that should be placed on forward current through an LED indicator when its temperature increases. In Figure 22-9, the LED should be operated only within the boundary established by the green line.



Figure 22-9. *Safe operation of an LED entails limiting the forward current if the temperature increases. The green line shows the boundary for operation of this particular component.*

View Angle

An LED formed from transparent epoxy or silicone (either water-clear or tinted) will create a well-defined beam with a view angle as narrow as 4 degrees or as wide as 160 degrees (in a few instances). The most common view angles for LED indicators are 30 degrees and 60 degrees.

Datasheets for LED indicators often include a *spatial distribution* graph showing the relative intensity of the light when viewed at various angles from the axis of the LED. The spatial distribution graph in Figure 22-10 is for an LED with a view angle defined as 40 degrees. This is the angle at which the relative luminous intensity diminishes to 50%.



Figure 22-10. *A spatial distribution graph shows the relative intensity of light from an LED at various view angles.*

The view angle is of special concern in devices such as flashlights, where the spread of the beam affects the functionality.

How to Use It

Like all semiconductor devices, LEDs can be impaired by excess forward current and may break down irreversibly if subjected to excess reverse voltage. Their limits for reverse voltage are much lower than those of a rectifier diode. They are also vulnerable to heat, but are not particularly vulnerable to static electricity.

Polarity

A through-hole LED will have two leads of unequal length. The longer lead connects internally with the *anode* of the diode, and should be wired externally to the "more positive" side of a power source. The shorter lead connects internally with the *cathode* of the diode, and should be wired externally to the "more negative" side of a power source.

To remember the functions of the leads, consider that the plus sign would be twice as long as a minus sign if its horizontal and vertical stroke were disassembled and placed end to end.

If a round LED has a flange around its base, a flat spot in the flange will be closest to the cathode side of the component.

Series Resistor Value

Because the effective internal resistance of a diode is not a constant value at different voltages, a trial-and-error approach may be necessary to determine the ideal value for a series resistor with an LED indicator. For this purpose, a trimmer potentiometer can be used with a sample LED while measuring the current through it and the voltage drop across it. A fixed-value resistor can then be substituted. If the choice is between a resistor value that is a little too high and a value that is a little too low, the higher value resistor should be used.

An approximate value can be found using a very simple formula in which R is the resistor value, V_{CC} is the supply voltage, V_F is the forward voltage specified for the LED, and I is the desired current:

$$R = (V_{CC} - V_F) / I$$

Normally a series resistor rated at 1/4 watt will be acceptable, and 1/8 watt may be used in 5VDC circuits. However, care should be taken with a power supply of 9V or higher. Suppose an LED is rated for 1.8V forward voltage at 20mA. In a 5V circuit, the voltage drop across the series resistor will be:

$$V = 5 - 1.8 = 3.2$$

Therefore, the resistor must dissipate 3.2V * 20mA = 64mW. This is comfortably below the 125mW rating of a 1/8 watt resistor. However, with a 9V power supply, the voltage drop across the series resistor will be:

$$V = 9 - 1.8 = 7.2$$

Now the resistor must dissipate 7.2V * 20mA = 144mW. This exceeds the 125mW limit for a 1/8 watt resistor.

LEDs in Parallel

If multiple LEDs are to be driven in parallel, and none of them has to be switched individually, it is naturally tempting to save time by using a single series resistor for all of them. In these circumstances, assess the maximum current carefully and multiply by the voltage drop imposed by each of the LEDs, to determine the wattage of a series resistor.

Linking dissimilar LEDs in parallel is not recommended, because the threshold voltage decreases with increasing temperature. The hottest LED will therefore receive the largest current, and thus become even hotter. Thermal runaway can result.

LEDs containing their own series resistors can safely be wired in parallel.

Multiple Series LEDs

A series resistor wastes current by dissipating it as heat. In an application where two or more LED indicators will be illuminated simultaneously, the LEDs can be connected in series with a lower-value resistor, and three LEDs in series may eliminate the need for a resistor completely, depending on the voltage of the power supply. Here again a trimmer potentiometer should be used to determine an ideal value for any series resistor that may be necessary.

Comparisons with Other Light Emitters

Because LED indicators have largely replaced neon bulbs and miniature incandescent lamps, comparisons are of limited importance at this point. The situation regarding **LED area lighting** is different in that it is still competing actively with fluorescent lights and, in some instances, halogen. A list of advantages and disadvantages for high-intensity white LEDs is given in "Comparisons" on page 223. The advantages of incandescent lamps are listed in "Relative Advantages" on page 179.

Other Applications

LEDs are used in **optocouplers** and in **solid-state relays**. Usually an infrared LED is embedded inside a chip or a plastic module, and emits light through an interior channel to activate a phototransistor. This arrangement provides electrical isolation between the switching signal and the switched current.

Some sensors use an LED paired with a phototransistor at opposite sides of a U-shaped plastic mount. A sensor of this type can monitor industrial processes or may be found inside a photocopy machine, to detect the presence of a sheet of paper.

What Can Go Wrong

Excessive Forward Voltage

Like any diode, the LED has a *threshold voltage* in the forward direction. If this threshold is exceeded, the effective internal resistance of the LED falls very rapidly. Current rises equally rapidly, and quickly damages the component, unless it is protected by an appropriate series resistor.

Excessive Current and Heat

Exceeding the recommended value for forward current, or allowing an LED to overheat, will shorten its lifetime and cause a premature dimming of light output. LEDs generally require some current limiting or regulation (most commonly with a series resistor). They should not be connected directly to a voltage source such as a battery, even if the battery voltage matches the voltage of the diode. The exception to this rule is if the internal resistance of the battery is high enough to limit the current, as in the case of button-cell batteries.

Storage Issues

LEDs of different types are often indistinguishable from each other. They can also be indistinguishable from photodiodes and phototransistors. Careful storage is mandatory, and reusing LEDs that have been breadboarded may cause future problems if they are wrongly identified.

Polarity

If the leads on an LED indicator are trimmed, and if the indicator lacks a flange in which a flat spot will identify the cathode, the component is easily misused with reversed polarity. If it is connected with a component that has limited current sourcing capability (for instance, the output pin of a digital chip), the LED will probably survive this treatment. However, maximum reverse voltage is often as low as 5VDC. To minimize the risk of errors, the anode lead can be left slightly longer than the cathode lead when they are trimmed for insertion in a breadboard or perforated board.

Internal Resistors

As previously noted, it is difficult to distinguish an LED that contains its own series resistor from another LED that does not. The two types should be stored separately, and should be reused circumspectly.

LED area lighting

23

The term **LED area lighting** is used in this encyclopedia to describe a white LED source that is bright enough to illuminate rooms, offices, or outdoor areas. It may also be used in desk lamps or table lamps as *task lighting*. LEDs for these purposes may be categorized as *high-brightness*, *high-power*, *high-output*, or *high-intensity*. A complete fixture containing at least one light source is properly known as a *luminaire*, although the term is not uniformly applied and is sometimes written incorrectly as a *luminary*.

The full term *light-emitting diode* is not normally applied to an LED used for area lighting. For this purpose, the LED acronym has become universal. Periods are not normally placed between the letters.

While an LED area-lighting package may contain more than one diode, it is still categorized here as a single source. By contrast, any component consisting of multiple separately discernible light-emitting diodes, as in a seven-segment numeral, a 14- and 16-segment alphanumeric character, a dot-matrix character, or a display of multiple characters, is listed in a separate entry as an **LED display**.

The term *OLED* is an acronym for *Organic Light-Emitting Diode*, a thin panel in which an organic compound is contained between two flat electrodes. Despite its functionality as a form of LED, its design is similar to that of thin-film electroluminiscent light sources. Therefore it is discussed in the entry on **electroluminescence**.

OTHER RELATED COMPONENTS

- **LED indicator** (see Chapter 22)
- **incandescent lamp** (see Chapter 18)
- **fluorescent light** (see Chapter 20)
- **neon bulb** (see Chapter 19)
- **electroluminescence** (see Chapter 26)

What It Does

High-brightness white LEDs provide a plug-compatible alternative to **incandescent lamps**, *halogen lighting*, and **fluorescent lights** for work spaces and the home.

At the time of writing, products are still evolving rapidly in the field of LED area lighting. A shared goal of manufacturers is to increase efficiency while reducing retail price to the point where high-brightness LEDs will displace fluorescent tubes for most low-cost lighting applications.

A wall-mounted LED reflector-bulb that emulates a halogen fixture is shown in Figure 23-1. A small LED floodlight for exterior use is shown in Figure 23-2. An early attempt to package an LED area light in a traditional-style bulb is shown in Figure 23-3. Within a decade, as LED area lighting continues to evolve, some of these examples may look quaint. Configurations are evolving, with final results that remain to be seen.



Figure 23-1. *A small LED reflector-light emulating a halogen fixture. Note the square of yellow phosphors mounted on the diode.*



Figure 23-2. *A floodlight for exterior use. Nine LEDs are assembled behind the yellow phosphors. The steel frame measures about 4" by 3".*

Trends in Cost and Efficiency

The *luminous flux* of a source is the total power that it radiates in all directions, within the visible spectrum. The unit that measures luminous flux is the *lumen*. For a more detailed discussion of this topic, see "Power" on page 177. Since 1965, the cost per lumen of light from a given color of LED has decreased by about a factor of 10, while the maximum number of lumens emitted by an LED package has increased by a factor of 20, during each decade. This is known as Haitz's Law, named after Dr. Roland Haitz of Agilent Technologies. Figure 23-4 illustrates it graphically.

Figure 23-3. *An LED light bulb. Unlike an incandescent bulb, it focuses the illumination in one direction, like a reflector-light. Consuming only 6W, it is claimed to be equivalent to a 40W incandescent bulb.*

Schematic Symbol

Schematic symbols that are commonly used to represent an LED are shown in Figure 23-5. The symbol remains the same regardless of the size or power of the component, but architectural plans may represent any type of light using the circle-and-X symbol at bottom right.

How It Works

A high-brighteness LED functions on the same basis explained in the entry describing **LED indicators**. Photons are emitted when electrons are sufficiently energized to cross a PN junction and combine with electron-holes.

An LED that appears white, or off-white, actually emits blue light that is re-radiated over a wide range of wavelengths by adding a layer of yellow phosphors to the chip. A cutaway diagram of an

LED chip (properly known as a *die*), mounted under a silicone lens, is shown in Figure 23-6.



Figure 23-4. *The increase in light output (luminous flux, in lumens) of a single LED compared with the decrease in cost-per-lumen during the years since 1965. The vertical logarithmic scale measures both dollars and lumens. Source: Philips Gardco site-lighting fact sheet with additional data from a "Strategies in Light Report" published by Semiconductor Equipment and Materials International in 2013.*



Figure 23-5. *The symbol for an LED remains the same regardless of its size and power, but architectural plans may use the circle-and-X symbol at bottom right for any type of light fixture.*

LEDs are mass-produced by etching them into crystals that are then cut into *wafers* before being subdivided into *dies*, like silicon chips. Most of the blue LEDs that form the basis of white lighting use sapphire crystals as their substrate. The crystal may range in diameter from two inches to six inches. Large sapphire wafers are also finding potential applications in camera lens covers and scratch-resistant cover plates for cellular phones.



Figure 23-6. *Cutaway diagram of a high-brightness white LED. Adapted from Philips Lumileds Technical Reference document.*

While a die for an LED indicator may be 0.3mm x 0.3mm, a die in a high-brightness LED is often 1mm x 1mm. The size is limited by technical issues involving total internal reflection of the generated light.

The precise color of the light is adjusted by adding red phosphors to the yellow phosphors. This reduces the overall efficiency of the LED by around 10% but creates a "warmer" radiance. A graphical illustration of this principle is shown in Figure 22-3, in the entry on LED indicators.

The *color temperature* of white or offwhite light is measured in degrees Kelvin, typically ranging from 2,500K to 6,500K, where a lower number represents a light with more red in it and a higher number represents a light with more blue in it. This system of measurement was originally used with **incandescent bulbs** to define the temperature of the filament, which determined its color. See "Spectrum" on page 173 for a detailed explanation.

Visible Differences

The effects of different types of illumination are compared in Figure 23-7. To create this figure, first a color chart was prepared in Photoshop and printed on high-gloss photo-grade paper with a Canon Pro9000 Mark II inkjet printer, which has separate colors for red and green in addition to cyan, pale cyan, magenta, pale magenta, yellow, and black.

The color chart was then photographed twice with a Canon 5D Mark II, using a fixed white balance of 4000K. The first exposure was made with "daylight spectrum" LED lighting (claimed color temperature of 6500K) while the second was made with halogen lighting (claimed color temperature of 2900K). The photographs were adjusted in Photoshop for levels only, to fill the available range of 256 values. The two exposures show how the same chart would appear when viewed under the different lights, if the human eye did not adjust itself at all. Note the large area of the LED exposure which is rendered in shades of blue or purple. Also note the dullness of the reds. This confirms the everyday belief that "daylight spectrum" LEDs tend to have a cold, purplish cast while incandescents have a warmer, yellow look.

The same camera was then used to make two more exposures, this time with the white balance set to 6500 for LED lighting and 2900 for halogen lighting, which would be the recommended standard procedure, suggesting the kind of compensation that the human eye also tends to make for different ambient lighting. The result is shown at Figure 23-8. The LED version has improved, but the reds and yellows are still muted. The halogen version also looks better than before, but the magenta end of the spectrum has too much yellow in it. These images show the limits of white-balance correction for indoor photography.



Figure 23-7. *The same printed color chart viewed with "daylight white" LEDs (top) and halogen lighting (bottom), without any compensation to allow for the different light spectra. A fixed white balance of 4000K was used for both pictures.*

Side-by-Side Comparison

Because the human eye is much better at comparing colors when they are adjacent to each other, another color chart was prepared using just six color bars of fully saturated red, yellow, green, cyan, blue, and magenta, with paler and darker versions above and below. The bars were separated with large white gaps. The chart was photographed first with the white balance set to

6500 under "daylight white" LED lighting and then again with the white balance at 2900 for halogen lighting. In Photoshop, the bars from the halogen version were copied and pasted beside the bars from the LED version to facilitate an A-B comparison. The result is shown in Figure 23-9.



Figure 23-8. *The same color chart as before, photographed with appropriate color temperature settings of 6500K (top, using "daylight-spectrum" LEDs) and 2900K (bottom, using halogen).*

In each pair of colors, LEDs lit the one on the left, and halogen lights lit the one on the right. This figure shows the dramatic difference at the red end of the spectrum, and the poor reproduction of yellows by LED lighting. However, the LED rendering of green is better, and likewise the rendering of magenta, except where its darker version is concerned. Among the pale versions of the colors, the LED lights produce much less density (i.e., they have a brighter look) in the blues, greens, and cyans. The low densities will show up as pale highlights in a photograph of an object, and the picture will tend to have excessive contrast. This will also contribute to the "harsh" look of "daylight white" LED lighting which may be perceived by the eye.



Figure 23-9. *A range of six fully saturated colors, with lighter and darker shades added above and below, photographed first with "daylight spectrum" LEDs and then with halogen lights, after which the two sets of colors were paired for easy comparison. The LED version is on the left in each pair.*

Halogen is deficient at the blue-violet end of the spectrum, even when the camera has an appropriate white-balance setting. Photographers can correct this using image-editing software. LED "daylight spectrum" lights are more difficult to correct. LEDs classified as "warm" should reproduce reds better, but may not do so well with blues.

Diffuse light from a uniformly cloudy sky may be the most ideal form of lighting for photographing objects, but this is of little help for people who work (or take photographs) under artificial lights.

LED lights that contain separate red, green, and blue emitters may perform better, but create a different problem, in that shadows will tend to have color fringes caused by the small offsets between the colored emitters.

Heat Dissipation

An LED is less than 100% efficient because not all electrons mate with electron holes. Some manage to bypass the semiconductor junction; some recombine without generating light; and some transfer their energy to other atoms. In each instance, waste heat is created. While the heat in an incandescent bulb is mostly dissipated by radiation, an LED must get rid of the heat almost entirely by conduction, typically through a *heat sink*. This complicates the design of a fixture, because the integrity of the pathway to dispose of the heat must be retained when the LED bulb or tube is replaced.

Efficacy

The *radiant luminous efficacy* (LER) of an incandescent light source measures how effective it is at channeling its output within the visible spectrum instead of wasting it in infrared radiation. LER is expressed in lumens per watt, and in an incandescent bulb, it is calculated by dividing the power emitted in the visible spectrum (the *luminous flux*) by the power emitted over all wavelengths. This is described in detail in "Efficacy" on page 179 in the entry dealing with incandescent lamps.

In an LED indicator, almost all the radiation can be contained within the visible spectrum, which suggests that its efficacy should be 100%. However, because some waste heat is still created internally, the efficacy is calculated by dividing the light output, in lumens, by the power input, in watts, at the voltage required by the LED. (Lumens can be converted directly to watts, and therefore this division makes a comparison between similar units).

In an LED lighting fixture that contains its own electronics to convert higher voltage AC to lower voltage DC, the power consumption of the fixture is measured not at the diode, but at the input side of the electronics. Therefore, the inefficiency of the electronics reduces the efficacy value of the lighting unit.

Dimming

An incandescent bulb is very sensitive to reduction in power. It becomes radically inefficient, emitting perhaps 1% of its normal light output if the power is reduced to 40%.

LEDs have an almost linear response to the supplied power. Usually a triac-based dimmer will not work well with LED area lighting, and a dimmer designed for LEDs must be substituted, using pulse-width modulation.

Ultraviolet Output

The gas plasma in a fluorescent light generates ultraviolet wavelengths that are shifted to the visible spectrum by the phosphor coating inside the glass envelope. Imperfections in the phosphor coating can potentially allow leakage of ultraviolet light, causing some researchers to claim that the use of CFLs (compact fluorescent lighting) for close-up work with desk lamps can increase the risk of developing some forms of skin cancer. (This claim remains controversial.)

LED manufacturers are quick to point out that white LEDs do not emit any ultraviolet radiation. Figure 23-10 shows spectral power distribution curves derived from measurements of three high-brightness Color Kinetics LEDs manufactured by Philips. The manufacturer states categorically that "The LED-based color and white light products made by Color Kinetics do not emit outside the visible spectrum." Infrared radiation is also negligible.

Color Variation

The *correlated color temperature* (CCT) is determined by finding the conventional incandescent color temperature which looks most similar to the light from a white LED. Unfortunately, because the CCT standard is insufficiently precise, and because small manufacturing inaccuracies can occur, two LED sources with the same CCT number may still appear different when they are side by side. While the human eye adjusts itself to overall color temperature, it is sensitive to differences between adjacent sources. If two or more white LEDs in a lighting fixture do not have identical spectra, the difference will be noticeable.



Figure 23-10. *Spectral power distribution curves for three high-brightness white LED lamps showing no ultraviolet emissions. (Adapted from a graph in a white paper published by Color Kinetics Incorporated.)*

To address the issue, manufacturers introduced the concept of "binning," in which lights are subclassified to tighter specifications and are assigned bin numbers based on their measured characteristics. The Philips Optibin system, for instance, assesses the light from various angles, as well as perpendicularly to the source. This is especially important where a large area such as a building lobby is painted white and is lit by high-brightness LEDs that must appear uniform in color temperature.

Variants

LED area lighting products are often designed to emulate the form factors of incandescent bulbs, halogen reflector bulbs, or fluorescent tubes. The standard screw-in base of an LED light bulb, the pin-base of a miniature 12V LED reflector bulb, and the pins on an LED tube enable easy migration to the newer technology.

Strip lights are unique to LED lighting systems. They are thick, flexible plastic ribbons in which are embedded a series of LEDs. For area lighting, the LEDs are white, and the strips can contain necessary control electronics for conversion of AC power. The strips can be placed behind ledges or moldings to provide soft, even illumination of the ceiling above.

Strip lights are also available for 12VDC power, to create lighting effects in customized automobiles and trucks. These strip lights are available in various colors in addition to white. Many have multicolor capability and can be controlled with a handheld remote.

Comparisons

The advantages of an **incandescent lamp** are listed in "Relative Advantages" on page 179, while advantages of **fluorescent lights** are listed in "Comparisons" on page 194. These lists can be compared with the following advantages for LED area lighting:

- While the life of an incandescent lamp for room lighting can be as little as 1,000 hours, LED area lighting typically claims up to 50,000 hours.
- The lifetime of an incandescent bulb is the average time it can emit light before catastrophic failure. The lifetime of an LED is the average time it can emit light before gradually dimming to 70% of its rated output. This is a much gentler, less inconvenient failure mode that does not require immediate replacement.
- Unlike a fluorescent light or incandescent bulb, the LED does not contain hot tungsten that fails as a result of erosion.

- Unlike a fluorescent light, an LED does not contain mercury, and therefore does not require special recycling arrangements that entail associated fees.
- While fluorescents can have difficulty starting in low temperatures, an LED is not sensitive to a cold environment.
- Bright LEDs are available in a wide range of colors that do not require filtering. Filters greatly reduce the efficiency of incandescent bulbs when they are used in applications such as traffic signals or rear lights on automobiles.
- High-brightness LEDs can be dimmable. Fluorescent lights are usually not dimmable, or perform poorly in this role.
- LEDs are inherently directional, because the die radiates light at an angle of 90 degrees to its plane. This makes it ideal for ceiling mounting, where as much light as possible should be directed downward. A fluorescent tube or incandescent bulb often requires a reflector which reduces the overall efficiency.
- LEDs are insensitive to cycling. The life expectancy of an incandescent bulb or (especially) a fluorescent tube is reduced by cycling it on and off.
- No flickering. Fluorescent tubes may start to flicker as they age.
- No electrical interference. Fluorescent tubes can interfere with AM radio reception and some audio devices.
- Safe from breakage. LED area lighting does not necessarily use any glass.

However, high-brightness LEDs still have some barriers to overcome:

- Cost. In the United States, before 60W incandescent bulbs were legislated out of existence, they could be sold profitably for less than $1 each. A T8 fluorescent tube, measuring 1” diameter and 48” long, currently costs between $5 and $6 (retail) but has a life expectancy in the region of 25,000 hours, and uses only 20% of the power of an incandescent bulb to generate two to three times as much light. Clearly the fluorescent tube is a more economical choice, despite the price of the electronics that must be included in the fixture to start the tube. By comparison, currently the purchase price of an LED tube is three times that of a fluorescent tube. It may last twice as long, but is not significantly more efficient, generating perhaps 100 lumens per watt while a fluorescent is typically capable of 90 lumens per watt. Prototype high-brightness LEDs have exceeded 200 lumens per watt, and should be competitive with fluorescents by 2020, but even then, migration will take time.
- Heat sensitivity. Heat reduces the light output and the lifespan of LED fixtures.
- Placement issues. Because LEDs are heat sensitive, they must be installed in locations that do not become excessively hot, their heat sinks must be correctly oriented, and they must have adequate ventilation.
- Color shift. Heat and age may cause the color temperature of an LED to shift slightly, as the color is usually derived from two types of phosphors.
- Nonuniformity. Manufacturing inconsistencies can cause LEDs of the same type to display slightly different color temperatures. Fluorescents and incandescents are more uniform.
- Lower heat output than incandescents. While this is an advantage from the point of view of efficiency, it can be a disadvantage in applications such as traffic signals or airport runway lighting where waste heat can help to keep the lights free from snow or ice.

Values

Although the output from an LED area light is directional, while the output from an incandescent bulb or a fluorescent light is omnidirectional, the intensity is measured the same way in each instance, using *lumens*. This unit expresses the total light emission, without taking directionality into account. (The intensity of **LED indicators** is calibrated in candelas, which measure the power within an angle of dispersion; but candelas are not used for area lighting.)

Typical values for incandescent bulbs are 450 lumens for a power consumption of 40 watts, 800 lumens for a consumption of 60 watts, 1,100 lumens for a consumption of 75 watts, and 1,600 lumens for a consumption of 100 watts. Because much of the output from an incandescent bulb may be wasted by using inefficient reflectors or allowing the light to shine in directions where it is not needed, a high-brightness LED rated at 1,000 lumens may actually appear brighter than a 75-watt incandescent bulb.

A T8 fluorescent tube measuring 48″ long by 1″ in diameter consumes only 32 watts but emits almost 3,000 lumens—when it is new. This output gradually diminishes by as much as 40% over the lifetime of the tube.

Incandescent bulbs deliver between 10 and 15 lumens per watt, approximately. A new fluorescent tube produces around 80 to 90 lumens per watt, and LED area lighting at the time of writing can provide 100 lumens per watt, under real-world conditions.

What Can Go Wrong

Wrong Voltage

Many high-brightness LED lighting units can be used with either 115VAC or 230VAC. There are exceptions, however. Check the specifications to make sure. Also, it is important to avoid applying domestic supply voltage to 12V LED miniature reflector-bulbs that are intended to replace 12VAC halogen bulbs of the same size.

Overheating

If a high-brightness LED fixture is equipped with a heat sink, this must be exposed to freely flowing air. Any vanes on the heat sink should be oriented vertically to encourage convection, and the fixture must not be placed in an enclosure. Overheating will radically shorten LED life.

Fluorescent Ballast Issues

A fluorescent fixture contains a *ballast* to limit the tendency of the tube to draw excessive current. The ballast is contained in a plastic box attached to the back of the frame in which the tube is mounted.

A *magnetic ballast* contains a coil, and is bypassed by an additional *starter* that applies unlimited current for one second when the power is switched on, preheating the tube to initiate plasma discharge.

An *electronic ballast* performs the same function without a separate starter.

Some LED tubes designed as substitutes for fluorescent tubes may allow a magnetic ballast to remain in the circuit, but may not tolerate an electronic ballast. Other LED tubes require any type of ballast to be unwired from the circuit. The unwiring operation will require disconnection of a couple of wires by removing wire nuts (assuming that the fixture has been designed to comply with U.S. building codes). The wires are then reconnected to apply power directly to the tube, and the wire nuts are reapplied to complete the new connection. The ballast can remain passively in the fixture.

Failing to remove the ballast and/or the starter from a fluorescent fixture before installing an LED tube that requires direct connection to the power supply can damage the tube. Connecting the power incorrectly to the LED tube may result in it failing to light up. Documentation supplied with the LED tube should provide guidance for disconnecting the ballast and connecting the tube. Note that the pin functions on LED tubes are not standardized at this time.

Misleading Color Representation

Because the spectrum of a white LED is not evenly weighted across all wavelengths, it will fail to represent some colors accurately, as shown previously. This can be important if LEDs are used to illuminate full-color printing or artwork, or if they are installed in stores selling merchandise such as clothes, furnishings, or food.

LED display

24

In this encyclopedia, a component consisting of multiple separately discernible light-emitting diodes, such as a seven-segment numeral, 14- or 16-segment alphanumeric character, a dot-matrix character, or a display module containing multiple characters, is categorized as an **LED display**. The term *light-emitting diode* is hardly ever used to describe an LED display, as the LED acronym has become ubiquitous. The acronym does not usually include periods between the letters.

An **LED indicator** is defined here as a component usually 5mm or smaller in diameter, made of transparent or translucent epoxy or silicone, most often containing one *light-emitting diode*. It is purposed as a status indicator in a device, rather than as a source of illumination, and is sometimes referred to as a *standard LED*.

LEDs that are designed to illuminate large living or working areas are discussed in a separate entry as **LED area lighting**. They are sometimes referred to as *high-brightness LEDs* and almost always emit white light.

The term *OLED* is an acronym for *Organic Light-Emitting Diode*, a thin panel in which an organic compound is contained between two flat electrodes. Despite its functionality as a form of LED, its design is similar to that of thin-film electroluminiscent light sources. Therefore it is discussed in the entry on **electroluminescence**.

OTHER RELATED COMPONENTS

- **LED indicator** (see Chapter 22)
- **LED area lighting** (see Chapter 23)
- **vacuum-fluorescent** (see Chapter 25)
- **electroluminescence** (see Chapter 26)
- **LCD** (see Chapter 17)

What It Does

An LED display presents information on a panel or screen by using multiple segments that emit light in response to a DC current, almost always at a voltage ranging between 2VDC and 5VDC. The display may contain alphanumeric characters and/or symbols; simple geometrical shapes; dots; or pixels that constitute a *bitmap*.

A *liquid-crystal display*, or **LCD**, serves the same purpose as an LED display and may appear very similar, except that a liquid crystal reflects incident light while an LED emits light. The increasing use of backlighting with LCDs has made them appear more similar to LED displays.

There is no schematic symbol to represent an LED display. Where a segmented display is used, often the segments are represented with drawn outlines.

The simplest, most basic, and probably the best-known example of an LED display is the *seven-*

segment numeral, one of which is shown in Figure 24-1. This is a Kingbright HDSP-313E with a character height of 0.4".



Figure 24-1. *The most basic LED display, able to create numerals from 0 through 9 using seven light-emitting segments that can be illuminated individually. An eighth segment forms the decimal point.*

How It Works

The process by which an LED generates light is explained in "How It Works" on page 207, in the entry dealing with **LED indicators**. Each light-emitting diode in an LED display is functionally the same as the diode in an LED indicator.

LEDs must be driven with DC. This is a primary distinction between an LED display and an LCD, which requires AC.

Variants

LCD comparisons

LCDs and LED displays can look very similar. This raises the obvious question: which is appropriate for a particular application?

LCDs (without backlighting) are more appropriate for applications such as digital watches and solar-powered calculators where power consumption must be minimized. They are capable of running for years from a single button cell. LCDs are easily visible in bright ambient light, where LED displays are not. LCDs can also be designed to display complex pictographic shapes and symbols, while the segments of an LED display are more constrained to be simple in shape.

An LCD is more likely to be affected by temperature than an LED, and powering it entails some slight inconvenience, because it requires an AC source that is unlikely to be useful elsewhere in a circuit. If the LCD uses LED backlighting, it will also require a low-voltage DC power source for the backlight. An LED display is easier to use in that it can be driven directly from a microcontroller or logic chip, with only some series resistors to limit the current, and the addition of transistors to provide additional power where necessary.

Seven-Segment Displays

Early seven-segment LED displays were used in digital calculators, before LCDs became an affordable, practical alternative that greatly extended battery life. Initially, the size of the diodes was limited, sometimes requiring magnifying lenses to make them legible.

Seven-segment displays are still used in some low-cost applications, although LCDs have become more common.

Figure 24-2 shows how the segments are identified with letters *a* through *g*. This scheme is used universally in datasheets, and is also used for LCDs. The decimal point, customarily referred to as "dp," is omitted from some displays. The segments are slanted forward to enable more acceptable reproduction of the diagonal stroke in numeral 7.

Although seven-segment displays are not elegant in appearance, they are functional and are reasonably easy to read. They also enable the representation of hexadecimal numbers using letters A, B, C, D, E, and F (displayed as A, b, c, d, E, F because of the restrictions imposed by the small number of segments), as shown in Figure 24-3.



Figure 24-2. *A seven-segment LED display. The lowercase identifying letters are universally used in datasheets.*

In appliances such as microwave ovens, very basic text messages can be displayed to the user within the limitations of seven-segment displays, as suggested in Figure 24-4.

Numbers 0, 1, and 5 cannot be distinguished from letters O, I, and S, while letters containing diagonal strokes, such as K, M, N, V, W, X, and Z, cannot be displayed at all.

Multiple Numerals

Displays consisting of a single numeral are now rare, as few applications require only one digit. Displays of two, three, and four digits are more common, as shown in Figure 24-5.

Additional Segments

Displays with 14 or 16 segments were introduced in an effort to enable the representation of all the letters of the alphabet. The segment layout of these LED displays is identical to that of comparable LCDs. The differences between 14-segment and 16-segment displays are shown in Figure 24-6. Some are angled forward like seven-segment displays, even though the addition of diagonal segments makes this unnecessary for display of characters such as numeral 7.



Figure 24-3. *Numerals and the first six letters of the alphabet created with seven-segment displays.*

Figure 24-7 shows the scheme for identifying the segments of a 16-segment display. This naming convention is used in all datasheets. The lowercase letters that were customary with seven-segment displays are usually abandoned in favor of uppercase, perhaps to avoid confusion with the letter L. Note that letter I is omitted from the sequence.

For a complete alphanumeric character set enabled by a 16-segment display, see Figure 17-9 in the entry discussing LCDs.

An example of a 16-segment alphanumeric LED display is shown in Figure 24-8, mounted on a breadboard and wired to show the letter N. This is a Lumex LDS-F8002RI with a character height of 0.8″. The component is still available at the time of writing, but in limited quantities.

Generally speaking, 16-segment displays were never very popular, because the gaps between adjacent segments impaired legibility. LED versions remain more readily available than LCD versions, but dot-matrix displays allow a better-looking, more easily legible alphabet, with the added possibility of simple graphics.

Dot-Matrix Displays

In the 1980s, some personal computers used a video character set in which each letter, numeral, punctuation mark, and special character was formed on a video screen from a fixed-size matrix of dots. A similar alphabet is now used in LED dot-matrix displays (and LCDs, as shown in Figure 17-10).



Figure 24-4. *Basic text messages can be generated with seven-segment displays, although they cannot represent alphabetical letters containing diagonal strokes.*



Figure 24-5. *Multiple seven-segment LED displays are often combined in a single component. Top: An Avago 2.05VDC 20mA display designed for a clock. Bottom: A Kingbright two-digit display which draws 20mA at 2.1VDC. The unlit outlines of the numerals would normally be hidden behind panels that are tinted to the same colors emitted by the LED segments when lit.*



Figure 24-6. *Layouts for 14-segment and 16-segment alphanumeric LEDs are identical to those of LCDs.*



Figure 24-7. *The scheme for identification of segments in a 16-segment alphanumeric LED display.*



Figure 24-8. *A 16-segment alphanumeric LED display showing the letter N.*

Alphanumeric dot-matrix characters are often grouped in two or more rows with eight or more characters per row. The number of characters is always listed before the number of rows, so that an 8x2 display would contain eight alphanumeric characters in two horizontal rows. This type of component is properly described as a *display module*.

Display modules are used in consumer electronics products such as a stereo receiver where simple status messages and prompts are necessary —for example, to show the tone control settings or the frequency of a radio station. Because the cost of small, full-color, high-resolution LCD screens has been driven down rapidly by the mass production of cellular phones, and because these high-resolution screens are much more versatile, they have already displaced dot-matrix display modules in many automobiles and are likely to follow a similar path in other devices.

Pixel Arrays

The 8x8 pixel array of LED dots shown in Figure 24-9 measures 60mm square (slightly more than 2”) and contains 64 LEDs, each approximately 5mm in diameter. Similar arrays are available in other sizes and with different numbers of dots. Displays of the same type may be assembled edge-to-edge to enable scrolling text or simple graphics.



Figure 24-9. *An 8x8 matrix of LED dots measuring more than two inches square.*

Multiple Bar Display

A bar display is a row of small rectangular LEDs in a single component. It may be used for digital representation of an analog signal. The higher the voltage of the signal, the more bars will be illuminated. A typical application would be to show the signal strength of an input to an audio recorder. Ten bars are often used, as in the display shown in Figure 24-10, but multiple components can be combined end to end.



Figure 24-10. *Two LED bar displays in which segments can be lit individually.*

Single Light Bar

A light bar can be thought of as a single-source LED, as it is configured as a single square or rectangle. It is mentioned here, rather than in the entry for single-source LED indicators, because variants may be subdivided into two, three, four, or (sometimes) more discrete sections. These variants are often included in the same datasheet as the monolithic version.

A light bar contains multiple LEDs (often, four in number) behind a translucent panel that provides evenly diffused radiance.

Values

The values for most LED displays are basically the same as for LED indicators, in terms of color, brightness, current consumption, and voltage. See "Values" on page 211 for information.

Multiple-character dot-matrix LED display modules may have different requirements for forward voltage and forward current, depending on drivers that are incorporated in the module. Because there is no standardization for these modules, it will be necessary to consult the manufacturer's datasheet.

How to Use It

Seven-Segment Basics

The diodes in a seven-segment LED display share either a *common anode* or a *common cathode*, the latter being more frequently used. The two types of internal wiring are provided for convenience only. Externally, the displays function identically.

A schematic suggesting the internal wiring and pinouts of a typical ten-pin common-cathode display is shown in Figure 24-11. The pins are numbered as seen from above. Appended to each number is the identity of the segment to which it is connected. Pins 3 and 8 are connected with the cathodes of all the internal LEDs. Both of these pins should be used, to serve as heat sinks for the display.

Note that series resistors are not included inside the display and must be added externally. Their value will be determined by the power supply, to limit the forward current and forward voltage through the LEDs to the extent specified by the manufacturer.

An encapsulated *resistor array* containing either seven or eight resistors in an SIP or DIP chip can be used instead of individual resistors. A seven-segment LED display would require the type of resistor array in which both ends of each resistor are accessible.

Where two or more numerals are combined in a single component, this type of display is likely to have two horizontal lines of pins. In this case, pin 1 will be at the bottom-left corner, seen from above. As always, the pins are numbered counterclockwise, seen from above.


1g
2f
3cc
4e
5d
10a
9b
8cc
7c
6dp

Figure 24-11. *A schematic view of internal connections and pinouts of a seven-segment common-cathode LED display. The numbers refer to the pins of the component, seen from above. The 1 pin may also have a mark beside it on the component, for identification. The orientation of the display can be deduced if there is a decimal point, as this should be at the bottom-right corner.*

Where three or more numerals are combined in a single component, the pinouts may be designed for multiplexing rather than individual access to every segment of each numeral. A four-digit clock display, for instance, may have seven pins that connect in parallel to respective segments in all of the numerals, and four additional pins that can ground each numeral in turn, so that they can be selected sequentially.

Driver Chips and Multiplexing

Illuminating the appropriate segments in a single numeral can be done directly from a microcontroller, or through a driver chip such as the well-known and widely used 4543B that converts a binary-coded decimal input into appropriate segment output patterns. The chip can source sufficient current to drive each segment through a series resistor. Its pinouts are shown at Figure 24-12.


Active low
1
Latch disable
16
5VDC to 18VDC
BCD inputs (values shown in decimal)
2
Input 4
3
Input 2
4
Input 8
5
Input 1
Decoder for 7-segment LED
Seg f
15
Seg g
14
Seg e
13
Seg d
12
Outputs to 7 segments of LCD
Active high
6
Phase
Seg c
11
Active high
7
Blanking
Seg b
10
Note f and g are out of sequence
8
Seg a
9
4543B

Figure 24-12. *Pinouts of the 4543B seven-segment LED driver chip.*

When used in conjunction with a microcontroller, the 4543B can drive several seven-segment displays by multiplexing them. The basic schematic to achieve this is shown in Figure 24-13, omitting optional features such as leading-zero blanking or connections for a decimal point. The microcontroller sends the binary code for the first numeral and simultaneously grounds the common cathode of that numeral through a transistor, which is needed because as many as seven segments of the numeral may be passing current in parallel. The microcontroller then sends the binary code for the second numeral, and grounds it; then sends the binary code for the third numeral, and grounds it; and the cycle repeats. So long as this process is performed at sufficient speed (at least 50Hz), persistence of vision will create the illusion that all the numerals are active simultaneously. The circuit can be compared with a similar circuit to drive LCDs, shown in Figure 17-17.



Figure 24-13. *A basic, simplified circuit for driving multiple seven-segment LED displays by multiplexing them.*

The disadvantage of this system is that the microcontroller must update the numerals constantly while performing other duties. To reduce this burden, a "smarter" driver such as the MC14489 can be used, controlling up to five 7-segment digits, or the Intersil ICM7218, which can control up to eight 7-segment digits.

The MC14489 controller receives data serially, using SPI protocol, and handles the details of addressing the LEDs. Because it contains latches to sustain the displayed data, a microcontroller only needs to communicate with the driver when the displayed information needs to be updated.

The ICM7218 is a more sophisticated chip, available in several variants, one of which can receive data on an 8-bit bus and run the seven-segment displays in hexadecimal mode.

Sixteen-Segment Driver Chip

The MAX6954 by Maxim can drive up to eight 16-segment alphanumeric LED displays using a scheme known as Charlieplexing, named after a Maxim employee named Charlie Allen who came up with the concept as a way of reducing the pin count required for multiplexing. Other Maxim controllers use this same protocol, which is transparent to the user.

A microcontroller sends data serially via I2C protocol to the MAX6954, which contains a variety of features. It can drive 14-segment and 7-segment displays as well as 16-segment displays, and contains a 104-character alphabet for each of them. Setting up a microcontroller to send the various necessary command codes to the MAX6954 is not a trivial matter, and bearing in mind the probably impending end-of-life of 16-segment displays, a better option may be to use dot-matrix LED display modules that have controller logic built in.

Dot-Matrix LED Display Modules

A dot-matrix LED display module requires data to define a character set, and a command interpreter to process instructions that will be embedded in a serial data stream. These capabilities are provided either by separate chips or (more often) are incorporated into the LED display module itself.

The SSD1306 is a monochrome graphical controller capable of I2C or SPI serial communication, or parallel communication. When this capability is built into a display module, only one of these types of communication may be activated.

The SSD1331 is a color graphical controller with similar communication capabilities.

The WS0010 is a monochrome controller, compatible with HD44780, which is designed to control LCDs.

Typical controller functions are summarized in "Alphanumeric Display Module" on page 168. Because there is no standardization in this field, precise details must be found in manufacturers' datasheets.

Pixel Arrays

The connections inside an 8x8 pixel array are shown in Figure 24-14, where the schematic symbols for LEDs have been replaced by gray circles for space reasons. To illuminate one LED, power is supplied to the intersection where it resides. In the figure, each vertical conductor (identified as A1, A2 . . . A8) can power the anodes of a column of eight LEDs, while each horizontal conductor (identified as C1, C2 . . . C8) can ground the cathodes of a row of eight LEDs. If only one vertical conductor is connected with positive power while one horizontal conductor is grounded, only one LED will light up, at the intersection of the active conductors.

A problem occurs if we wish to illuminate two LEDs. Suppose they are located at (A3,C2) and (A6,C5). Unfortunately, providing power to them will also result in activating LEDs at (A3,C5) and (A6,C2), as shown in Figure 24-15, where the yellow circles represent LEDs that have been switched on.

The answer to this problem is to rasterize the process. In other words, data is supplied on the array one line at a time, as in the process by which a TV picture is generated. If this is done quickly enough, persistence of vision will create the illusion that the LEDs are illuminated simultaneously.



Figure 24-14. *Internal connections in the 8x8 matrix. Each gray circle represents an LED.*



Figure 24-15. *An attempt to illuminate LEDs at (A3,C2) and (A6,C5) will also activate the LEDs at (A3,C5) and (A6,C2).*

A form of multiplexing is used to achieve this. One row of LEDs is connected to negative ground for a brief interval. During this interval, the anodes of selected LEDs are powered momentarily. Then the next row is grounded, and selected LEDs along that row are powered momentarily. This process is repeated for all eight rows before being repeated.

If several 8x8 matrices are assembled edge to edge, their horizontal conductors can be common to all of them. A horizontally scrollable display (sometimes referred to by the archaic term, *electric newspaper*) would then be possible, although the circuit design would be nontrivial.

Multiple Bar Display Driver

The LM3914 is a driver for a bar display that compares an analog input with a reference voltage and provides power to the segments of a multiple bar display, ranging from 2mA to 30mA, adjustable to match the specification of the display that is being used. The chip can generate either a "thermometer" effect, as more outputs are activated when the analog input increases, or a "moving dot" effect, in which only one output is on at a time.

One-Digit Hexadecimal Dot Matrix

While multi-character dot-matrix LED display modules are a versatile way to display prompts and numbers, a simpler component is sometimes sufficient. The Texas Instruments TIL311 is a minimal dot-matrix LED display that receives a binary value from 0000 through 1111 on its four input pins and generates the output in hexadecimal form, using numerals 0 through 9 and letters A through F. The sixteen possible outputs in the dot-matrix display are shown in Figure 24-16. Although this component is no longer being manufactured, it is widely available from many sources, especially in Asia. It eliminates the series resistors and controller chip that are customary for a seven-segment display, and has a better-looking output.



Figure 24-16. *Sixteen possible outputs that can be displayed by the Texas Instruments TIL311 to show a hexadecimal value in response to a four-digit binary input.*

A sample of the TIL311 is shown in Figure 24-17 displaying the number 2.

If two or more of these chips are put together, they can be multiplexed to display multi-digit decimal or hexadecimal integers.

The chip features two decimal points, one to the left of the displayed numeral, and one to the right. If they are activated, they require their own series resistors to limit the current.



Figure 24-17. *The Texas Instruments TIL311 can be driven directly by a microcontroller or counter chip, with no series resistors necessary. It can generate a hexadecimal output.*

What Can Go Wrong

Common Anode versus Common Cathode

An LED display containing a common cathode is usually identical in appearance to a display containing a common anode, and the two versions will be distinguished by only one digit or letter in their part numbers. Because LED displays have a limited tolerance for reverse voltage, part numbers should be double-checked before applying power.

Incorrect Series Resistance

A common error is to assume that only one series resistor is necessary for a seven-segment LED display, either between the common cathode pin and ground, or, if there is a common anode, between that and the positive power supply. The problem is that if the resistor is suitable for a single LED, its value will be too high when several segments of the display are sinking current or drawing current through it. If its value is reduced, it will be too low when only two segments are using it (as when generating the number 1).

To provide equal illumination of all the segments, each must have its own series resistor.

Multiplexing Issues

When several displays are multiplexed, they naturally appear dimmer, creating a temptation to compensate by upping the current. Because current is only being applied to each display intermittently, a natural assumption is that a higher current can be safely used.

This may or may not be true. When running an LED device with pulsed current, the peak junction temperature, not the average junction temperature, determines the performance. At refresh rates below 1kHz, the peak junction temperature is higher than the average junction temperature, and the average current must therefore be reduced.

Datasheets must be checked to determine whether a device is designed with multiplexing in mind and, if so, what the recommended peak current is. Very often this value will be accompanied by a maximum duration in milliseconds, and a calculation may be necessary to determine the refresh rate, bearing in mind how many other LED displays are being multiplexed in the same circuit at the same time.

Irresponsible multiplexing will shorten the life of an LED display or burn it out.

vacuum-fluorescent display

25

The term **vacuum-fluorescent display** is seldom hyphenated, but the first two words are hyphenated here as they constitute an adjectival phrase. The acronym *VFD* is becoming increasingly popular, although it is ambiguous, being also used to identify a *variable frequency drive*. In both instances, the acronym is printed without periods between the letters.

The entry in this encyclopedia dealing with **fluorescent lights** does not include VFDs, because their purpose and design are very different. A VFD is an informational display, often showing numerals and letters, while a fluorescent light merely illuminates a room or work area. Although a VFD does use fluorescent phosphors, they are printed onto light-emitting segments of the display instead of being applied to the inside surfaces of a glass envelope.

OTHER RELATED COMPONENTS

- **LED indicator** (see Chapter 22)
- **LCD display** (see Chapter 17)
- **electroluminescence** (see Chapter 26)

What It Does

A **vacuum-fluorescent display** or *VFD* superficially resembles a backlit monochrome **LCD** or an **LED display**, as it can represent alphanumeric characters by using *segments* or a *dot matrix*, and can also display simple shapes. It is often brighter than the other information display systems, and can emit an intense green phosphorescent glow that some people find aesthetically pleasing, even though a grid of very fine wires is superimposed internally over the displayed image.

There is no specific schematic symbol to represent a vacuum-fluorescent display.

How It Works

The display is mounted inside a sealed capsule containing a high vacuum. A widely spaced series of very fine wires, primarily made of tungsten, functions as a *cathode*, moderately heated to encourage electron emission. The wires are often referred to as *filaments*.

A **fluorescent light** uses AC, and both of its electrodes are often confusingly referred to as cathodes. A VFD uses DC, and its cathode array has the function that one would expect, being connected with the negative side of the DC power supply.

Opposite the cathode, just a few millimeters away, is an anode that is subdivided into visible alphanumeric segments, symbols, or dots in a matrix. Each segment of the anode is coated with *phosphors*, and individual segments can be separately energized via a substrate. When electrons strike a positively charged anode segment, it emits visible light in a process of *fluorescence*. This behavior can be compared with that of a *cathode-ray tube*. However, the cathodes in a VFD are efficient electron emitters at a relatively low temperature, while the cathodes in a cathode-ray tube require substantial heaters.

Anode, Cathode, and Grid

A *grid* consisting of a mesh of very fine wires is mounted in the thin gap between the filaments of the cathode and the segments of the anode. A simplified view of this arrangement is shown in Figure 25-1.



Figure 25-1. *The basic elements of a vacuum-fluorescent display.*

The polarity of the charge on the grid controls and diffuses electrons emitted by the cathode. If a grid section is negatively charged, it repels electrons and prevents them from reaching the sections of the anode beneath it. If the grid section is positively charged, it encourages electrons to reach the anode. Thus, the grid functions in the same way as the grid in a triode vacuum tube, but its conductors are so thin, they are barely visible.

How to Use It

Electronic calculators used vacuum-fluorescent displays during the 1970s, before LED displays and LCDs became more competitive. Purely numeric VFD modules are still available as strings of digits, although they are becoming uncommon and have been replaced by alphanumeric dot-matrix modules where each VFD character is mounted in its own glass module on a separate substrate.

Figure 25-2 shows the interior of a Commodore calculator from the 1970s, with its nine-digit vacuum-fluorescent display enclosed in one glass capsule.



Figure 25-2. *The vacuum-fluorescent display from a 1970s Commodore calculator.*

A closeup of three digits from the previous figure appears in Figure 25-3, showing the grid superimposed above each numeral.



Figure 25-3. *Three digits from the previous figure, showing the grid that controls their illumination.*

A tinted filter of the same color as the display is usually placed in front of it, to conceal some of its workings. Thus, the Commodore calculator used a green filter in front of its green numerals. Figure 25-4 shows two seven-segment numerals from another device, with the filter removed. This reveals not only the grid but also the horizontal wires that function as the cathode. Connections between the segments of the numerals and a backplane are also visible.



Figure 25-4. *Seven-segment numerals viewed without a colored filter, revealing the cathode (horizontal wires) and the grid (wire mesh).*

Modern Application

A modern VFD module is likely to be mated with a driver that converts 5VDC to the higher voltage (typically 50VDC to 60VDC) required for the display. Built-in logic may offer the option to receive data via an 8-bit parallel bus or with SPI serial protocol, and will contain a character set. A typical display resolution is 128 x 64 pixels.

The combination of a grid and a segmented anode enables a VFD to be controlled by *multiplexing*. For instance, in a display of four seven-segment numerals, the same equivalent segments in all four numerals can be connected in parallel while a separate grid covers each numeral. When each grid is positively energized, it selects the corresponding numeral, and the on-off segment patterns appropriate to that numeral are supplied. This procedure is repeated for each numeral in turn. Persistence of vision makes it appear that they are all active simultaneously.

Variants

Color

Although a VFD cannot provide a full-color display, selected anode segments can be coated with different phosphor colors, which can fluoresce simultaneously. Two or three individual colors are typically used, as in the display for a CD player where color helps to distinguish a variety of different functions. A closeup of a portion of the display from a CD player (with color filter removed) appears in Figure 25-5.



Figure 25-5. *The lefthand section of a vacuum-fluorescent display from a CD player.*

Character Sets and Pictorial Design

In the past, VFDs have combined seven-segment numerals in the same display as custom-shaped anodes. Solid-state gain meters in an audio amplifier, for instance, have used numerals beside a pictorial representation of gain levels resembling analog meters. The look and layout of a display of this type has been unique to a particular product.

Modern VFDs tend to use a generic dot-matrix display in which a character set in firmware dictates how patterns of dots are grouped to form numbers, letters, symbols, or icons.

The appearance of character sets generated with generic segments and dot-matrix arrays is thoroughly discussed and illustrated in the entry describing liquid-crystal displays in Chapter 17. VFD alphanumeric modules are identical in visual design to LCD modules, even though the internal electronics are different.

Comparisons

Two advantages of a VFD are that it functions well at low temperatures (unlike an LCD) and has sufficient brightness and contrast to be usable in sunlight (unlike many LED displays). It can be viewed from almost any angle.

Typical applications have included digital instrumentation in automobiles, information displays in audio and video consumer-electronics equipment, and numerical readouts in vending machines, medical devices, and some digital clocks.

Because a VFD requires a relatively high voltage, has significant power consumption, can show only a limited range of fixed colors, and is more expensive than LED displays or LCDs, its popularity has declined since the end of the 1990s.

What Can Go Wrong

Fading

VFDs gradually fade with age, as a result of reduced electron emission from the electrodes or diminishing performance of the phosphor coatings. Increasing the working voltage can prolong the life of a display.

electroluminescence

26

The field of **electroluminescent** devices is sometimes referred to as *EL*. The same acronym can also be applied as an adjective to an individual electroluminescent device, as in, for example, "an EL panel."

An *organic light-emitting diode*, more commonly known by its acronym *OLED*, is included in this entry because it is technically an electroluminescent device and its design concept is similar to that of an electroluminescent panel. Generic LEDs are also technically electroluminescent, but are not commonly described as such, and have their own entries in this encyclopedia under the subject categories **LED indicator**, **LED area lighting**, and **LED display**.

OTHER RELATED COMPONENTS

- **LED indicator** (see Chapter 22)
- **LCD display** (see Chapter 17)
- **fluorescent light** (see Chapter 20)
- **vacuum-fluorescent** display (see Chapter 25)

What It Does

An electroluminescent device configured as a *panel*, *ribbon*, or *rope-light* contains phosphors that emit light in response to a flow of electricity.

Panels can be used as backlights for LCD displays or, more often, as always-on low-power devices such as exit signs and night lights. Ribbons and rope lights (the latter being also known, more accurately, as *light wires*) are used mainly as recreational novelties. They can be battery powered through a suitable voltage converter. A battery-powered rope light can be wearable.

Thin-film OLED electroluminescent panels are used in small video screens in handheld devices. At the time of writing, OLED TV screens measuring 50" or more have been demonstrated, but are not yet economic for mass production.

No specific schematic symbol exists to represent any electroluminescent device or component.

How It Works

Luminescence is the emission of light as a result of a process that does not require heat. (The opposite phenomenon is *incandescence*, in which heating causes an object to emit light; see Chapter 18 for a description of **incandescent lamps**.)

Electroluminescence is luminescence resulting from stimulation by electricity. This very broad definition really includes devices such as **LED**s, although they are hardly ever described in those terms. Electroluminescence generally refers to panels, films, or wires where electrodes are in direct contact with light emitters such as phosphors.

The exception is an *organic LED*, usually known by its acronym *OLED*, which is frequently described as an electroluminescent device, perhaps because its configuration as a sandwich of thin, flat layers resembles an electroluminescent panel. Two of the layers are semiconductors, and they interact as light-emitting diodes.

Phosphors

A *phosphor* is a compound such as zinc sulfide that will emit light when it receives an energy input from another light source or from electricity. Typically the compound must be mixed with an *activator* such as copper or silver.

For many decades, TV sets and video monitors were built around *cathode-ray tubes* in which the interior of the screen, at the front of the tube, was coated with phosphors. A beam of electrons that fluctuated in intensity generated a picture on the screen by drawing it as a series of lines.

Derivation

The term *phosphor* is derived from *phosphorescence*, which in turn comes from the name of the element *phosphorous*, which will glow when it oxidizes in moist air. (These terms were established before other forms of luminescence were discovered and understood. The behavior of phosphorous is really an example of *chemiluminscence*.)

For our purposes, a phosphor is a compound that is capable of fluorescence or electroluminescence.

Variants

Panels

Electroluminescent panels using phosphor powder, sometimes referred to as *thick phosphor*, are a popular choice where a constant, uniform, low light output is acceptable.

An electric potential is established between two films that act as electrodes, separated by a layer of phosphor crystals. Some manufacturers refer to this configuration as a *light-emitting capacitor* because the structure resembles a capacitor, even though that is not its purpose. The front film is transparent, allowing light to escape.

An electroluminescent panel can be powered by AC or DC but requires at least 75V. Its power consumption is self-limiting, so that no control electronics are required other than a voltage converter if battery power is used.

The phosphors generate a constant, evenly distributed luminescence over the entire area, although the output is not very intense. Applications include night-lights, exit signs, and backlighting for wristwatches.

Panelescent electroluminescent lighting by Sylvania was used for instrument panel displays in some car models such as the Chrysler Saratoga (1960 through 1963) and Dodge Charger (1966 through 1967). It is still used for night-lights. *Indiglo* electroluminiscent displays are still widely used in wristwatches.

The interior components of a disassembled electroluminescent night-light are shown in Figure 26-1. The panel emits a natural pale green glow. A separate blue or green filter passes the glow while blocking other colors of incident light that would otherwise reflect off the panel.



Figure 26-1. *The two interior components of an electroluminiscent night-light: the luminescent panel, and a separate translucent filter.*

Electroluminescent night-lights were popular in the 1970s and 1980s, often featuring cartoon characters to appeal to children. Figures 26-2 and 26-3 show the same night-light in its daytime off-state and its night-time on-state, respectively.



Figure 26-2. *A vintage Panelescent brand night-light, several decades old, in its off-state.*



Figure 26-3. *The same night-light, with its green radiance visible under conditions of low ambient light.*

Advantages of electroluminescent panels include the following:

- Low current consumption. One US manufacturer claims that a single exit sign will use electricity costing less than 20 cents per year, while the annual cost of a night-light will be less than 3 cents per year.
- Long life, up to 50,000 hours.
- Self-regulating; no control circuitry required.
- Omnidirectional light output.
- Very wide operational temperature range, between approximately -60 and +90 degrees Celsius.
- Can be plugged directly into a wall outlet.

Disadvantages include:

- Limited light output.
- Very limited choice of colors.
- Not very efficient, 2 to 6 lumens per watt (although the low light output naturally entails low power consumption).
- Gradual reduction in phosphor performance over time.
- High voltage required: 60V to 600V. Ideal for plugging into a wall outlet, but requires a converter when used with battery-powered devices.

Flexible Ribbons

The light-emitting layers inside a night-light are somewhat flexible, and can be made more flexible by reducing their thickness. The result is an electroluminescent ribbon that has some novelty value, and may be used for customizing automobiles. Figure 26-4 shows a ribbon about 1.5" wide and 12" long, designed for 12VDC power applied through an inverter.

Rope Light

A rope light or wire light may resemble a *glowstick*. However, a glowstick generates light from chemiluminescence (chemical reactions that release photons), while a rope light uses electricity.

Figure 26-5 shows a rope light powered by two AA batteries connected through an inverter.

At the center of the rope light is a conductor that serves as one electrode. It is coated in phosphors, and the layer of phosphors is protected by a transparent sheath. One or more thin wires is wrapped around the sheath in a spiral, with large gaps between one turn and the next. These wires serve as the second electrode. The wires are enclosed in transparent insulation that forms an outer sheath.



Figure 26-4. *A 12" length of electroluminescent ribbon.*

When AC is applied between the electrodes, the layer of phosphors emits light that radiates out in the gaps between the thin wires. The color of the light can be modified by using tinted outer insulation.

OLED

An OLED uses two thin, flat electrodes, somewhat like a thick-phosphor electroluminescent panel, except that it contains more layers and is capable of generating more light. The layers in an OLED are "organic" in that they consist of chemically organic molecules containing carbon and hydrogen atoms and generally do not contain heavy metals.

While an LCD video monitor or TV screen must have a separate backlight, an OLED generates its own light. This reduces the thickness of the display to a few millimeters and makes it potentially more efficient.

The semiconductor layers are subdivided into pixels, each functioning as a light-emitting diode, while additional layers carry a matrix of conductors for pixel addressing. In an AMOLED, the conductors form an active matrix, while in a PMOLED, they form a passive matrix.



Figure 26-5. *A length of glowing rope light, also known as a light wire.*

In an active matrix, each pixel is backed with a *thin-film transistor* to store its state while the energizing voltage transitions. This is often described as a *TFT* display; but the term is interchangable with "active matrix."

In a passive matrix, each pair of conductors simply supplies current to a pixel. This is cheaper and easier to fabricate but is less responsive.

The terms "active matrix" and "passive matrix" have the same meaning as when used to describe a **liquid-crystal display**.

Monochrome OLED display modules with dot-matrix characters are currently available from China for just a few dollars. Although they appear superficially similar to LCD modules, they generate pure white-on-black characters.

Small full-color OLED screens are used in smartphones and on camera backs, but at the time of writing, large OLED screens are not a mature technology, partly because of production costs. A great variety of chemicals and layer configurations have been tried, and the application of pixels to a substrate has been attempted with vacuum deposition through a shadow mask and with a system similar to inkjet printing. Pixels that emit red, green, and blue light have also been used. Filtered pixels have been used. One dominant process has not yet emerged.

Longevity and brightness have been problems. Where red, green, and blue diodes have been used, the different colors deteriorate at different rates. While the human eye tolerates an overall reduction in brightness, it does not tolerate a slight color shift caused by blue pixels, for instance, losing brightness more rapidly than red pixels.

Because OLED screens promise to be thinner, lighter, and brighter, and may eliminate the need for a fragile glass substrate, there is a strong incentive to develop this technology, which seems likely to gain dominance in the future.

OLED panels may also become a source of diffuse, shadowless room lighting or office lighting when practical problems have been solved and costs have fallen significantly.

transducer

27

The term **transducer** is used here to describe a *noise-creating device* that is driven by external electronics. By comparison, an **audio indicator** (discussed in the next entry) contains its own internal electronics and only requires a DC power supply. Either of these components is often described as a *beeper* or *buzzer*.

A **speaker**, more properly termed a *loudspeaker*, is an electromagnetic transducer but is seldom described in those terms. It has a separate entry in this encyclopedia and is defined here as a *sound reproduction device* that is larger and more powerful than a typical transducer and has a more linear frequency response.

While piezoelectric transducers formerly used crystals, only the more modern piezoelectric type that uses a ceramic wafer will be considered here.

Some transducers convert sound into electricity, but these are categorized as *sensors*, and will be discussed in Volume 3. The only transducers discussed in this entry are those that convert electricity into sound.

OTHER RELATED COMPONENTS

- **audio indicator** (see Chapter 28)
- **headphone** (see Chapter 29)
- **speaker** (see Chapter 30)

What It Does

An audio **transducer** is a device that can create an *alert*. It requires an AC signal that is supplied by external electronics, and in its simplest form may be referred to as a *buzzer* or a *beeper*.

Audio alerts are used in microwave ovens, washer/dryers, automobiles, gasoline pumps, security devices, toys, phones, and many other consumer products. They are often used in conjunction with touch pads, to provide audio confirmation that a tactile switch has been pressed.

The schematic symbols in Figure 27-1 can be used to represent any kind of audio alert, including **indicators**, which contain their own electronics to generate a simple tone or series of tones. Type A is probably the most popular symbol. Types B and C often appear with the word "buzzer" printed beside them for clarification. D and E are really symbols for a **speaker**, but are often used for an alert. F is the symbol for a *crystal*, now sometimes used to indicate a piezoelectric noise maker. G specifically represents an electromagnetic transducer, but is seldom used.

How It Works

A circular diaphragm is glued at its edges inside a cylindrical plastic enclosure, usually measuring from around 0.5″ to 1.5″ in diameter. The enclosure is sealed at the bottom but has an opening at the top, so that sound can emerge from the upper side of the diaphragm without being partially cancelled by sound of opposite phase that is emitted from the underside of the diaphragm. The enclosure also amplifies the sound by resonating with it, in the same way that the body of a guitar or violin amplifies a note being played on the strings.



Figure 27-1. *An assortment of symbols which can represent a transducer or an indicator. See text for details.*

The diaphragm is activated either electromagnetically or piezoelectrically, as described next.

Externally, a transducer may be indistinguishable from an audio indicator such as the one pictured at Figure 28-1.

Variants

Electromagnetic

An electromagnetic transducer contains a diaphragm that is usually made of plastic. Mounted on it is a smaller *ferromagnetic disc* that responds to the fluctuating field from AC passing through a coil. When the diaphragm vibrates, it creates pressure waves that are perceived by the human ear as sound.

A car horn is a particularly loud form of electromagnetic transducer.

Piezoelectric

A piezoelectric transducer contains a diaphragm consisting of a thin brass disc on which is mounted a *ceramic wafer*. When an AC signal is applied between the piezoelectric wafer and the disc, the disc flexes at that frequency.

The term *piezo* is derived from the Greek *piezein*, which means "to squeeze or press."

Ultrasonic Transducer

The diaphragm in an *ultrasonic transducer* vibrates at a frequency above the range of human hearing. This component may be electromagnetic, piezoelectric, or crystal-based. Often it is used in conjunction with an ultrasonic receiver as a distance measuring device. The two components can be sold pre-mounted on a breakout board. An output from the board can consist of a pulse train where the pulse duration is proportional to the distance between the transducer and the nearest sound-reflecting object.

An ultrasonic transducer is pictured in Figure 27-2. Its internal components are shown in Figure 27-3.



Figure 27-2. *The exterior of an ultrasonic transducer.*

Submersible ultrasonic transducers may be used in cleaning systems, where they agitate a liquid that dislodges dirt or debris. Ultrasonic transducers are also used in echo-sounding and sonar equipment with marine applications.



Figure 27-3. *Inside an ultrasonic transducer, a small aluminum cone is the sound radiating element. The white blobs are adhesive to secure the thin wires.*

Formats

Some transducers are available in surface-mount format, measuring about 0.5″ square or less. Because the resonant frequency is related to the size of the component, surface-mount transducers usually generate a high-pitched beep.

Values

Frequency Range

Audio frequency is measured in Hertz, abbreviated Hz, named after Heinrich Rudolf Hertz, the first scientist to prove the existence of electromagnetic waves. The H in Hz is capitalized because it refers to a real name. One thousand Hertz can be written as 1 kiloHertz, almost always abbreviated as 1kHz (note that the k is lowercase).

The human ear is often described as being able to detect sounds between 20Hz and 20kHz, although the ability to hear sounds above 15kHz is relatively unusual and diminishes naturally with age. Sensitivity to all frequencies can be impaired by long-term exposure to loud noise.

The most common frequencies applied to audio transducers range between 3kHz and 3.5kHz. Piezoelectric elements are inefficient for generating sounds below 1kHz, but electromagnetic transducers are better able to generate lower frequencies. Their response curve can be approximately flat to frequencies as low as 100Hz.

Sound Pressure

Sound pressure can be measured in Newtons per square meter, often abbreviated as Pa. Newtons are units of force, while Pa is an abbreviation of Pascals.

The *sound pressure level* (SPL) of a sound is not the same as its sound pressure. SPL is a logarithmic value, to base 10, in units of decibels (dB), derived from the pressure of a sound wave relative to an arbitrary reference value, which is 20 micro-Pascals (20μPa). This is the agreed minimum threshold of human hearing, comparable to a mosquito at a distance of three meters. It is assigned the level of 0dB.

Because the decibel scale is logarithmic, a linear increase in the decibel level of a sound does not correspond with a linear increase in actual sound pressure:

- For each additional 6dB in the SPL, the actual sound pressure approximately doubles.
- For each additional 20dB in the SPL, the actual sound pressure is multipled by 10.

Bearing in mind that 0dB corresponds with the reference sound pressure of 20μPa, an SPL of 20dB represents a sound pressure of 200μPa (that is 0.0002Pa), and so on.

Many tables show an estimated decibel level for various noise sources. Unfortunately, these tables may contradict each other, or may fail to mention the distance at which a sound is measured. Figure 27-4 shows estimates derived by averaging eight similar tables. It should be viewed as an approximate guide.

Decibels	Noise Example
140	Jet engine at 50 meters
130	Threshold of pain
120	Loud rock concert
110	Automobile horn at 1 meter
100	Jackhammer at 1 meter
90	Propeller plane 300 meters above
80	Freight train at 15 meters
70	Vacuum cleaner
60	Business office
50	Conversation
40	Library
30	Quiet bedroom
20	Leaves rustling
10	Calm breathing at 1 meter
0	Auditory threshold

Figure 27-4. *Approximate decibel values for some sound sources (averaged from a selection of eight similar charts).*

Sometimes the claim is made that an increase of +10 on the decibel scale will correspond with a subjective experience that the noise is "twice as loud." Unfortunately, this statement cannot be quantified.

Weighted Sound Values

Subjective assessment of sound is complicated by the nonlinear frequency response of the human ear, which causes some frequencies to seem "louder" than others, even though their sound pressure is the same. The frequency weighting of the ear can be determined by playing a reference tone of 1kHz at 20dB and then doing an A-B comparison with a secondary tone at another frequency, asking the subject to adjust the gain of the secondary tone up or down until the two tones seem equally loud.

This procedure is performed for a range of frequencies. The test is then repeated with a louder 1kHz reference tone, at 30dB. Repetitions continue to a final reference tone of 90dB.

The resulting curves are known as *equal-loudness contours*. An averaged set, from multiple sources, has become an international standard with ISO number 226:2003. The curves shown in Figure 27-5 are derived from that standard. The curves show that the sound pressure of lower frequencies must be boosted by a significant amount to sound as loud as a 1kHz frequency, while a frequency around 3kHz must be reduced slightly, because it tends to sound louder than all others.



Figure 27-5. *Equal loudness contours derived from ISO 226:2003. See text for details.*

Although the accuracy of equal-loudness contours is controversial, they have been the basis of a widely used weighting system to adjust dB values to represent subjective perceptions of loudness. This *A-weighting* system remains the best-known and most widely applied audio standard in the United States, even though it has been criticized for assigning too little value to sounds that are brief in duration. If a sound level is expressed in dBA, it is A-weighted, meaning that the sounds to which the ear is least sensitive are assigned a value that is lower than their measured value. Thus, a tone of 100Hz has a dBA value about 20dB lower than its dB value, because the human ear is relatively insensitive to low-pitched sounds. dBA values are used in regulations that limit noise in the work place and other environments.

Unweighted Values

If sound intensity is expressed in dBSPL, it is a measurement of the actual Sound Pressure Level and has not been adjusted with the A-weighting system. A graph of unadjusted dbSPL values will display low frequencies as if they are more intense than the ear will perceive. In practical terms, subjective perception of low-end rolloff will be even more severe than the graph makes it appear.

If sound intensity is expressed merely in dB, probably it is unweighted and should be considered as dBSPL.

From a practical point of view, when choosing a tone for a transducer, a 500Hz tone may sound relatively mellow and not subjectively loud. A 3.5kHz tone can be a good attention-getting signal, as the ear is most sensitive in that range.

Transducers generally have a sound pressure rating in dBSPL ranging between 65dBSPL to 95dBSPL, with just a few products that can make more or less noise.

Measurement Location

The sound pressure from an audio alert will naturally diminish if the measurement point moves farther away. Therefore, any rating in decibels should be expressed with reference to the distance at which the measurement is made.

Measurement locations may be expressed in centimeters or inches, and may vary from 10cm to 1 meter, even in datasheets for different devices from the same manufacturer. If the measurement distance doubles, the SPL diminishes by approximately 6dB.

Limitations

A piezoelectric transducer is not intended as a sound reproducer, and does not have a smooth or flat frequency response. The curve for the Mallory PT-2040PQ is not unusual, reproduced in Figure 27-6. This component measures about 3/4" in diameter, is rated for 5VDC, and uses only 1.5mA to generate 90dB (measured at a distance of 10cm). Like many piezoelectric audio devices, its response peaks around 3500kHz and diminishes above and below that value, especially toward the low end. While it is perfectly adequate as a "beeper," it will not reproduce music successfully.



Figure 27-6. *The frequency response from a typical small piezoelectric transducer.*

An electromagnetic transducer is better able to generate low frequencies than a piezoelectric transducer. It has a low impedance that may be suitable in some circuits. However, it is slightly heavier than a comparable piezoelectric transducer, uses much more power, and as an AC device containing a coil, it can create electromagetic interference or may cause fluctuations in the circuit as an inductive load. It is also vulnerable to magnetic interference from elsewhere, while a piezoelectric transducer is not.

While an electromagnetic transducer can be used to reproduce speech or music, and will do a better job than a piezoelectric transducer, its performance will still be dissatisfying. A miniature speaker is more appropriate for the task.

Voltage

Transducers are typically designed to work with voltages ranging from 5VAC to 24VAC. The ceramic wafer in a piezoelectric transducer usually cannot withstand voltages much above 40VAC, and its sound output will not increase significantly above 30VAC.

Current

Typical piezoelectric transducers use less than 10mA and generate negligible heat. An electromagnetic transducer may draw as much as 60mA.

How to Use It

Appropriate Sound Intensity

An alert should be chosen with reference to the environment in which it will be used. To be easily heard, it should be at least 10 dB louder than ambient background noise.

Volume Control

Sound pressure can be lowered by reducing the voltage. Because a transducer does not consume much current, a *trimmer* can serve as a volume control. Alternatively, a rotary switch with a set of fixed-value resistors can select preset sound values.

AC Supply

Although a transducer is an AC device, it is unlikely to be designed for voltage that fluctuates positively and negatively either side of a neutral value. Typically it is intended for voltage that fluctuates between 0V (ground) and the rated positive value of the power supply, and its pins, wires, or terminals are usually marked accordingly. If it has wire leads, the red lead should be connected to the more-positive side of the supply. If it has pins, the longer pin should be more positive.

The alternating signal for a transducer can be supplied by any simple oscillator or astable multivibrator circuit. For a given peak voltage, a square wave will generate a louder signal than a sinusoidal wave. A simple 555 timer circuit can be used, with a second monostable timer to limit the duration of the beep if necessary. An astable 555 can be used to test the transducer and select the audio frequency that sounds best.

Self-Drive Transducer Circuit

If a transducer has three wires or pins, it is probably a *self-drive* type. The datasheet may identify its inputs as M, G, and F, meaning Main, Ground, and Feedback. The Feedback terminal is connected with a section of the diaphragm which vibrates 180 degrees out of phase with the Main terminal. This facilitates a very simple external drive circuit, such as that in Figure 27-7, where the frequency is determined by the transducer's resonant frequency.



Figure 27-7. *A circuit to control a self-drive type of piezoelectric transducer.*

What Can Go Wrong

Overvoltage

Mallory Sonalerts, one of the largest producer of piezoelectric alerts, states that in the "vast majority" of returned products, the failure was caused by excessive voltage, often in the form of a transient voltage spike.

Leakage

If an alert makes a small, low-volume sound when it is supposed to be off, some current is leaking through it. Less than 1mA may be enough to cause this problem. According to one manufacturer, it can be fixed by placing a 30V Zener transient voltage suppressor diode in series with the alert, or by wiring a small **incandescent lamp** in parallel with the alert.

Note that when the alert is activated, the full supply voltage will be seen at the lamp.

Component Mounting Problems

Some alerts are packaged with mounting holes, but many are not. Those with pins can be soldered into a board, but those without must be glued in place or inserted into a cavity from which they cannot shake loose. Silicone adhesive is recommended, but care must be taken to avoid any of it dripping into the alert before it sets.

Moisture

If an alert will be used in a location where it is vulnerable to moisture, it should be of a type that is sealed against the environment. Even a sealed unit should ideally be oriented so that it faces slightly downward.

Transducer-Indicator Confusion

Externally, a transducer and an indicator often look identical, and some of them are not marked with a manufacturer's part number. Damage can be caused by applying DC to a transducer or AC to an indicator. If both types of parts are kept in inventory, they should be carefully labeled.

Connection with a Microcontroller

A piezoelectric transducer can be driven by a microcontroller, but an electromagnetic transducer is not appropriate in that role, because of its relatively higher current consumption and its behavior as an inductive load.

audio indicator

28

An **audio indicator** is defined here as a noise-creation device that generates a simple tone or series of tones. Unlike a **transducer**, which requires an external source of AC to determine its audio frequency, an indicator contains its own electronics and requires only a DC power supply. Either of these components is often described as a *beeper* or *buzzer*.

While piezoelectric alerts formerly used crystals, only the more modern piezoelectric type that uses a ceramic wafer will be considered here.

OTHER RELATED COMPONENTS

- **transducer** (see Chapter 27)
- **headphone** (see Chapter 29)
- **speaker** (see Chapter 30)

What It Does

When DC power is applied to an **audio indicator**, in its simplest form it creates a continuous or intermittent tone of a fixed frequency. This is called an *alert*.

Audio alerts are used in microwave ovens, washer/dryers, automobiles, gasoline pumps, security devices, toys, phones, and many other consumer products. They are often applied with touch pads, to provide audio confirmation that a tactile switch has been pressed.

A few indicators are programmed to create a two-tone sound, or multiple-tone sequences.

See Figure 27-1 in the previous entry for an assortment of schematic symbols that may be used to represent either an alert or a transducer.

How It Works

A circular diaphragm is glued at its edges inside a cylindrical plastic enclosure, usually measuring from around 0.5″ to 1.5″ in diameter. The enclosure is sealed at the bottom but has a small hole at the top, so that sound can emerge from the upper side of the diaphragm without being partially cancelled by sound of opposite phase that is emitted from the underside of the diaphragm. The enclosure also contains electronics to generate one or more audio tones, and amplifies the sound by resonating with it, in the same way that the body of a guitar or violin amplifies a note being played on the strings.

A PUI XL453 piezoelectric audio indicator is pictured in Figure 28-1, fully assembled on the right, and with its circuit board and diaphragm removed on the left. This indicator creates a pulsed tone at 3.5kHz with a sound pressure of 96dB. It draws 6mA at 12VDC and measures approximately 1″ in diameter.

For more information about the measurement of sound frequency and pressure, see “Frequency Range” on page 251 and “Sound Pressure” on page 251 in the previous entry.



Figure 28-1. *A typical piezoelectric audio indicator.*

Externally, an audio indicator may be indistinguishable from a transducer. However, internally, an indicator is almost always a piezoelectric device, in which a *ceramic wafer* is mounted on a thin brass diaphragm. The term *piezo* is derived from the Greek *piezein*, which means to squeeze or press.

A transducer (described in the previous entry) is a piezoelectric or electromagnetic alert that does not usually contain its own circuitry and must be driven by an external source of AC, which establishes the audio frequency.

The distinction between an indicator and a transducer is often unclear in parts catalogs, where all alerts may be identified as *buzzers*, even though they mostly beep rather than buzz.

Audio Frequency

For a discussion of audio frequency, see "Frequency Range" on page 251 in the previous entry.

History

Probably the earliest form of electrically activated alert was the door bell, in which a 6VDC battery-powered solenoid pulled a spring-loaded lever terminating in a small hammer. The hammer struck the bell, but the motion of the lever also opened a pair of contacts, cutting off power to the solenoid. The lever sprang back to its rest position, which closed the contacts and repeated the cycle so long as power was supplied through an external pushbutton.

Subsequent systems used a small loudspeaker powered by AC house current through a step-down transformer. This created a buzzing sound and may have been the origin of the term "buzzer."

Small components that made a beeping sound only became common when digital equipment required a simple, cheap way to confirm user input or attract attention to the status of a device.

Variants

Sound Patterns

Because an audio indicator contains its own electronics, the manufacturer has the freedom to create various patterns of sound output.

The default is a steady tone. Other common variants include an intermittent tone and a dual tone that fluctuates rapidly between two frequencies. This is sometimes referred to as a *siren*. A few variants can generate an output pattern consisting of several tones in sequence, or effects such as warbling or whooping sounds, which are used mainly in alarm systems.

Formats

Some audio indicators are available in surface-mount format, measuring 1/2" square or less. Because the resonant frequency is related to the size of the component, surface-mount alerts usually make a high-pitched beep.

Panel-mount and board-mount formats range from about 1/2" to 1.5" in diameter. A small audio alert designed to be mounted on a circuit board is shown in Figure 28-2, with its top removed on the right to expose the brass diaphragm glued around the edges. The same component is shown with its plastic enclosure removed completely in Figure 28-3.



Figure 28-2. *An audio indicator approximately 0.5" in diameter, partially disassembled on the right, revealing its brass diaphragm.*



Figure 28-3. *The same indicator from the previous photograph, with its enclosure completely removed.*

Values

For an explanation and discussion of sound pressure and its measurement in decibels, see "Sound Pressure" on page 251 in the previous entry.

Audio indicators generally have a sound pressure rating in dBSPL ranging between 65dBSPL to 95dBSPL, with just a few products that make more or less noise. At 120dB and above, most products are packaged as alarm sirens ready for installation, often with a small horn attached. Their power consumption can be 200mA or more, and they are many times the price of a simple indicator designed for circuit-board mounting.

Voltage

An audio indicator containing its own electronics will almost always be rated somewhere in the range from 5VDC to 24VDC. Sirens intended for use with burglar alarms are often designed for 12VDC or 24VDC, as these are popular values for security systems with battery backup. However, in addition to a rated voltage, a datasheet may specify a wide range of acceptable operating voltages. For example, an indicator with a *rated* voltage of 12VDC may have an *operating* voltage of 3VDC to 24VDC. Naturally, the sound intensity will vary with the voltage, but not as much as one might assume. The graph at Figure 28-4 shows that the sound output from an alarm, measured in decibels, increases by only 8dB when voltage increases by almost a factor of five. Of course, the decibel scale is not linear, but human perception of sound is not linear, either.



Figure 28-4. *Variation of sound output relative to voltage, in a commonly used piezoelectric indicator.*

Current

Typical piezoelectric indicators use less than 10mA (often as little as 5mA) and generate negligible heat.

Frequency

The most common frequencies for indicators range between 3kHz and 3.5kHz. Piezoelectric elements are inefficient for generating sounds below 1kHz.

Duty Cycle

Piezoelectric alerts generate very little heat and can be run on a 100% duty cycle.

If an alert will be pulsed briefly, the minimum pulse time is 50ms. A shorter duration will merely generate a clicking sound.

How to Use It

Appropriate Sound Intensity

An indicator should be chosen with reference to the environment in which it will be used. To be easily heard, it should be at least 10 dB louder than the ambient background noise.

Volume Control

Sound intensity can be reduced by reducing the voltage. Because an indicator does not consume much current, a trimmer can serve as a volume control. Alternatively, a rotary switch with a set of fixed-value resistors can select preset sound values.

However, in many indicators, variations in voltage may have relatively little effect on sound output, as shown in Figure 28-4.

Wiring

An indicator requires DC voltage. Because the indicator contains a transistor, polarity of the power supply is important. If the indicator has leads attached, the one intended for connection to the positive side of the power supply will be red. If it has pins, the longer pin will be for the positive connection.

What Can Go Wrong

The potential problems in an indicator are the same as those for a transducer. See "What Can Go Wrong" on page 254 in the previous entry.

headphone

29

The term **headphone** is used here to include almost any device that fits into or over the ear for the purpose of sound reproduction. (*Hearing aids* are not included.) Because headphones are used in pairs, the term is usually pluralized.

The term *phones* is fairly common as a colloquial diminution of *headphones* but is not used here.

An *earphone* used to be a single sound reproduction device designed for insertion into the ear, but has become rare. Pairs of *earbuds* are now common.

Because this encyclopedia assigns more emphasis to electronic components than to consumer products, this entry provides only a superficial overview of fully assembled headphones, and deals more with the drivers inside them, their principles of operation, and the general topic of sound reproduction.

OTHER RELATED COMPONENTS

- **transducer** (see Chapter 27)
- **speaker** (see Chapter 30)

What It Does

A headphone converts fluctuations of an electric signal into pressure waves that the human ear perceives as sound. It can be used for reproduction of music for entertainment purposes, or for speech in telecommunications, broadcasting, and audio recording.

Two symbols for headphones are shown in Figure 29-1. The symbol on the left shows a single headphone or earphone; when this symbol is flipped horizontally, it can represent a microphone. The pictographic symbol on the right has been used for many decades, but is still often found in schematics.



Figure 29-1. *Schematic symbols for a single earphone or headphone (left) and a pair of headphones (right).*

How It Works

Audio Basics

Sound is transmitted as pressure waves through a medium that is usually air but can be a gas, fluid, or solid. The speed of transmission will vary with the density and other attributes of the medium. Small hairs in the inner ears, known as *cilia*, vibrate in sympathy with pressure waves and transmit nerve impulses to the brain, which interprets the impulses as sound.

Three quantities describe the propagation of any type of wave, including a sound wave: its frequency (customarily represented with letter f), its speed of propagation (represented with letter v, for velocity), and its wavelength from peak-to-peak (represented by the Greek letter lambda, which appears as this λ symbol).

The relationship is defined by a very simple equation:

```
v = λ * f
```

Velocity is usually measured in meters per second, wavelength in meters, and frequency in Hertz, abbreviated Hz. One cycle per second is 1Hz. The H is always capitalized, as it refers to the name of Heinrich Rudolf Hertz, the first scientist to prove the existence of electromagnetic waves. One thousand Hertz can be written as 1 kilo-Hertz, almost always abbreviated as 1kHz (note that the k is lowercase).

The human ear is often described as being able to detect sounds between 20Hz and 20kHz, although the ability to hear sounds above 15kHz is relatively unusual and diminishes naturally with age. Sensitivity to all frequencies can be impaired by long-term exposure to loud noise.

Naturally occurring sounds can be converted to fluctuations in voltage by a **microphone**, which will be found listed as a *sensor* in Volume 3 of this encyclopedia. Artificial sounds can be generated as voltage fluctuations by oscillators and other electronic circuits. In either case, the output fluctuations can range between an upper limit set by a positive supply voltage and a lower limit established by electrical ground (which is assumed to be 0 volts). Alternatively, the fluctuations can range between the positive supply voltage and an equal and opposite negative supply voltage, with 0V lying midway between the two. This option can be less convenient electrically but is a more direct representation of sound, because sound waves fluctuate above and below ambient air pressure, which can be considered analogous to a ground state.

The concept of positive and negative sound waves is illustrated in Figure 29-2 (originally published in the book *Make: More Electronics*).



Figure 29-2. *The use of positive and negative voltages to represent a wave of high sound pressure followed by a trough of lower pressure.*

The topic of sound amplification is explored in detail in the entry on *op-amps* in Chapter 7.

A headphone inverts the function of a microphone by converting electricity back into air-pressure waves. This is done electromagnetically (moving a diaphragm in response to an electromagnet) or electrostatically (moving a membrane in response to electrostatic force between two charged electrodes).

Variants

Moving Coil

The most enduringly popular type of headphone uses a coil attached to a *diaphragm*. This is known as a *moving-coil* headphone, as the coil moves with the diaphragm. It can also be referred to as having a *dynamic driver* or *dynamic transducer*, "dynamic" referring to the movement of the coil.

The moving-coil concept is illustrated in Figure 29-3. The coil slides into a deep, narrow, circular slot in a magnet that is attached to the plastic frame of the headphone. The diaphragm is supported at its edges by a flexible rim. Variations in current passing through the coil create a fluctuating magnetic field that interacts with the field of the fixed magnet, causing the diaphragm to move in and out. A very similar configuration is used in many **loudspeakers**. Detail modifications may be made to increase efficiency, reduce production costs, or enhance sound quality, but the principle remains the same.



Figure 29-3. *The basic elements of a moving-coil headphone.*

The internal element of a headphone is shown in Figure 29-4. A plastic diaphragm is visible, measuring slightly less than 2" in diameter. The magnet and coil are concealed underneath.

The element in the previous figure is normally enclosed in an assembly such as the one in Figure 29-5, which incorporates a soft padded rim to rest upon the ear.

In an effort to achieve a more balanced frequency response, some designs use two moving-coil drivers in each headphone, optimized for low frequencies and high frequencies, respectively.

Earbuds, described after the next section, often use a miniaturized version of the moving-coil design.



Figure 29-4. *The sound reproducing element removed from a headphone.*



Figure 29-5. *The sound reproducing element from the previous figure is normally packaged inside this enclosure.*

Other Types

Electrostatic headphones use a thin, flat diaphragm suspended between two grids that function as electrodes. A fluctuating potential between the grids, coupled with a reverse-phase voltage on the diaphragm, will vibrate the diaphragm, generating pressure waves. A relatively high voltage is necessary to achieve this, anywhere from 100V to 1,000V, supplied through a conversion unit between the headphones and an amplifier. Electrostatic headphones are known for low distortion and an excellent high frequency response, at some extra cost.

Electret headphones work on a similar principle, except that the membrane is permanently charged, and a high voltage is not required. Electret headphones tend to be small, inexpensive, and not of high sound quality.

A *balanced armature* design, often referred to by the acronym *BA*, uses a pivoting magnet that is claimed to increase efficiency while reducing stress on a diaphragm. BA drivers can be extremely compact, contained within a sealed metal enclosure measuring less than 10mm x 10mm x 5mm. They are commonly used in conjunction with *in-ear* earphones, described in the next section.

Mechanical Design

Circumaural headphones use large soft pads to encircle the ear and block external noise. Their size tends to make them heavy, requiring a well-designed headband to provide comfortable support. *Supra-aural* headphones are smaller and lighter, resting on the ears instead of enclosing them. They cannot exclude ambient noise, and may have inferior bass response compared with the circumaural type.

Open-back headphones, also known as *acoustically transparent*, are favored by some audiophiles because their vented outer surfaces are thought to create a more natural sound, similar to that of a **speaker**. The open backs naturally allow ambient noise to intrude, but also allow the sound generated by the headphones to be heard by others in a room. *Closed-back* headphones contain their sound and provide more insulation against ambient noise.

Earbuds rest just within the outer folds of the ear, facing inward like a pair of tiny **speakers**. They are easily dislodged and provide very little insulation against ambient noise. Their use became common after the introduction of Apple's iPod. A pair of earbuds, one of them with its plastic cover removed, is shown in Figure 29-6.



Figure 29-6. *A pair of earbuds, one with its cover removed to show the sound reproducing element, which closely resembles the diaphragm in a full-sized headphone.*

In-ear headphones are designed for insertion into the ear canal, often using a soft sheath that conforms with the ear like an earplug. This sheath is disposable for hygienic reasons, and because it may lose some of its plasticity with use. It excludes most ambient noise, and by minimizing the air gap between the driver of the headphone and the ear drum enables a high quality of sound reproduction.

In-ear headphones are also known as *in-ear monitors*, *IEMs*, *ear canal headphones*, *earphones*, and *canalphones*. A pair of in-ear headphones is shown in Figure 29-7, one of them with its foam sheath removed. The rectangular silver-colored object in the headphone on the left contains a transducer to create sound pressure.

A *headset* consists of one or two headphones plus a flexible microphone that extends to the promiximity of the mouth of the user.

Noise-cancelling headphones, popularized by Bose, monitor external noise with a built-in microphone and generate sound of opposite phase, to provide some cancellation. They are particularly effective on jet aircraft, where background noise tends to be consistent.



Figure 29-7. *A pair of in-ear headphones, supplied with disposable foam plugs that conform flexibly with the ear canal. The headphone on the left is shown with its plug removed.*

Although an *earphone* is almost obsolete, it is still obtainable from specialty suppliers. It has a high impedance, making it suitable for use with a *crystal-set radio*. An earphone is pictured in Figure 29-8.



Figure 29-8. *A vintage earphone of the type suitable for use with a crystal-set radio.*

Values

Intensity

Sound pressure is measured in decibels. For a complete explanation and discussion of weighted and unweighted decibel scales, see "Sound Pressure" on page 251 in the **transducer** entry.

Frequency Response

A plot of sound pressure as a function of frequency shows the *frequency response* of a headphone. Measuring the sound pressure meaningfully is a challenge, because the ear canal will add coloration to the sound and can amplify some frequencies while masking others. Ideally, measurement should be done at the ear drum, but this is not feasible. Consequently, high-end headphones are evaluated by making sound measurements inside simulated ear canals in a dummy human head.

A comparison between a high-quality $500 audio product and a transducer that is sold as a component for less than $1 illustrates the difference in frequency response; see Figure 29-9. The Sennheiser headphones have a smooth response that rises toward the low end, compensating for the lack of bass response that tends to be a problem in headphones, and the relative insensitivity of the human ear to low frequencies. The fluctuations at the high end are within about 5dB.

By comparison, the Kobitone emphasizes the range between 3kHz and 4kHz because its primary task is to be heard, and these are the frequencies where human hearing is most sensitive. Its low-frequency response trails off (although is still much better than that of a piezoelectric transducer, where the low response typically diminishes by 40dB to 50dB). The low-frequency output of the Kobitone is actually impressive bearing in mind that the component is only 9mm in diameter. It draws 60mA at 5VAC.



Figure 29-9. *Comparison between frequency responses of a $1 electromagnetic transducer intended as an audio alert and a $500 pair of headphones intended for sound reproduction. The upper graph is derived from a review online at headroom.com; the lower graph is from the manufacturer's datasheet.*

Some manufacturers of audio reproduction equipment prefer not to supply frequency response curves. Instead they may claim, for example, that the frequency response of a product ranges from 100Hz to 20kHz. This claim means very little unless it is accompanied by a range of sound pressure levels. If the frequency response is consistent within a range of, say, plus-or-minus 5dB, this may be acceptable. If the range is plus-or-minus 20dB, it is not acceptable. The ability to reproduce a high note or a low note is not useful if the sound is too faint to hear.

Distortion

The *total harmonic distortion* (THD) of any audio equipment measures its tendency to add spurious *harmonics* of a single frequency. If headphones are required to reproduce a pure 1kHz sinewave, they will also tend to create an additional 3kHz tone that is an artifact. This can be caused by the mechanical behavior of a vibrating diaphragm. The human ear recognizes distortion as a fuzzy or rasping sound. A square wave theoretically contains all the harmonics that are odd multiples of its fundamental frequency, and sounds extremely distorted.

THD should be less than 1% in good-quality audio devices.

Impedance

The electrical impedance of headphones is relevant in that it should match the output specification of the amplifier that drives them.

What Can Go Wrong

Overdriving

Headphones can be damaged by overdriving them. Because a low frequency requires larger excursions of a diaphragm to transmit the same energy as a high frequency, headphones are especially vulnerable to being damaged by bass at high volume.

Hearing Damage

Human hearing can be damaged by prolonged listening to headphones at a high volume. Some controversy remains regarding an acceptable limit for sound pressure.

Mismatched Impedance

If the impedance of headphones does not match the output of the amplifier driving them, distortion or a skewed frequency response can result. This is known as *mismatching*.

Incorrect Wiring

In most consumer products, a pair of headphones will share a common ground. While the connections in a typical three-layer jack plug have been standardized, hand-wired repairs or extensions should be tested carefully. Incorrect wiring will cause unpredictable results.

speaker

30

The term **speaker** is a diminution of *loudspeaker*. The full word is now so rarely used, some catalogs do not recognize it as a search term. This encyclopedia acknowledges contemporary usage by using **speaker** rather than *loudspeaker*.

A fully assembled consumer product can be referred to as a “speaker,” but it also contains one or more individual components that are described as “speakers.” To resolve this ambiguity, referring to the components as *drivers* is helpful, but this practice can create more ambiguity because other types of components are also called “drivers.” The only real guide to the meaning of *speaker* is the context in which it is used.

For the purposes of this entry, a speaker is a *sound reproduction device*, distinguished from a typical electromagnetic **transducer** by being larger and more powerful, with a more linear frequency response. A transducer may be used as a *noise-creating device* to provide an alert, informing the user of the status of a piece of equipment. Because some speakers have been miniaturized for use in handheld products, they may be used as transducers, allowing some overlap between the two categories.

Because this encyclopedia assigns more emphasis to electronic components than to consumer products, this entry provides only a superficial overview of fully assembled speakers, and deals more with the drivers inside them, their principles of operation, and the general topic of sound reproduction.

OTHER RELATED COMPONENTS

- **headphone** (see Chapter 29)
- **transducer** (see Chapter 27)

What It Does

A speaker converts fluctuations of an electric signal into pressure waves that the human ear perceives as sound. It can be used for entertainment purposes or to provide information in the form of spoken words or distinctive sounds (as in the case of a miniature speaker in a cellular phone, playing a ring tone).

The internationally accepted schematic symbol for a speaker is shown in Figure 30-1.



Figure 30-1. *Only one symbol exists to represent a speaker. This is it.*

How It Works

For a summary of basic concepts and terminology relating to sound and its reproduction, see “Audio Basics” on page 261 in the previous entry.

Construction

A speaker contains a *diaphragm* or *cone* with a coil attached to it. Fluctuations of current through the coil interact with a permanent magnet, causing the speaker to emit pressure waves that are proportionate with the current. The design is similar in concept to that of a headphone, shown diagrammatically in Figure 29-3. The primary difference is that a speaker of around 2″ or more will use a cone rather than a flat diaphragm. The cone shape is more rigid and creates a more directional sound.

A 2″ speaker rated for 1/4W with a 63Ω coil is shown in Figure 30-2, undamaged on the left but with its cone cut out on the right. The neck of the cone, which is normally inserted in the circular groove in the speaker magnet, is shown with the inductive coil wrapped around it.



Figure 30-2. *On the left is a 2″ speaker. On the right, its cone has been cut away to reveal the magnet, with a circular groove in it. The neck of the cone, which normally slides into the groove, is shown removed.*

A speaker with a cone 4″ in diameter is shown from the rear in Figure 30-3.

A miniature surface-mount speaker is shown from the front and from the rear in Figures 30-4 and 30-5. It measures just under 0.4″ diameter and was made for Motorola. Its power rating is 50mW.



Figure 30-3. *The back side of a speaker with a cone measuring approximately 4″ in diameter. Its magnet is the large round section that is uppermost. This unit is rated for 4W and has an impedance of 8Ω.*

A speaker designed for a cellular phone is shown in Figure 30-6. Note the close resemblance in design to the driver used in an earbud, shown in Figure 29-6 in the previous entry.

In the past, speaker cones were made from tough, fibrous paper. Modern cones are more likely to be plastic, especially in small sizes.



Figure 30-4. *Front view of a surface-mount speaker measuring less than 0.4″ diameter.*



Figure 30-5. *Rear view of the speaker shown in the previous figure.*



Figure 30-6. *A miniature speaker measuring slightly more than 1/2" diameter and only 0.13" thick, designed for use in a cellular phone. It has an impedance of 150Ω.*

Multiple Drivers

Generally speaking, a large-diameter speaker cone is more effective than a small cone at moving the greater volumes of air associated with reproduction of bass notes. However, the inertia of a large cone impairs its ability to vibrate at high frequencies.

To address this problem, a large speaker and a small speaker often share a single enclosure. A *crossover network* using coils and capacitors prevents low frequencies from reaching the small speaker and high frequencies from reaching the large speaker. The basic principle is shown in the simplified schematic in Figure 30-7.



Figure 30-7. *The basic principle of a crossover network.*

Because the crossover network must be "tuned" to match the characteristics of the speakers, and because the combined sound pressure of the speakers must be relatively consistent over a wide range of frequencies, an actual network usually includes additional components.

Because the audio output from an amplifier consists of alternating current, polarized capacitors cannot be used. Polyester capacitors are common.

The small speaker in a pair is known as a *tweeter* while the large speaker is a *woofer*. Although these appellations were whimsically coined, they have endured.

More than two speakers may be combined in an enclosure, in a wide variety of configurations.

Venting

A speaker radiates pressure waves from the back side of its cone as well as from the front, and because the waves from front and back are opposite in phase, they will tend to cancel each other out.

In a miniature speaker, this problem can be addressed simply by sealing the section of the enclosure at the rear. For larger components, a more efficient enclosure can be designed with a *vent* or *reflex port* at the front. Pressure waves from the back of the speaker are diverted over a sufficient distance inside the cabinet so that by the time they emerge through the port, they are approximately in phase with low frequencies from the front of the speaker, although the back wave will lag the front wave by one wavelength.

This design is referred to as a *bass-reflex enclosure*, and was almost universal in high-fidelity components until amplifiers became increasingly powerful during the 1960s. At that point, Acoustic Research, located in Massachusetts, marketed a product line in which speaker enclosures were sealed, the argument being that when an amplifier can deliver 100W per channel, efficiency is no longer an issue, and a sealed enclosure can eliminate compromises associated with a bass-reflex design.

Acoustic Research referred to their concept as "air suspension," as the cushion of air in the sealed cavity helped to protect the speaker by limiting its excursion. This configuration is now often referred to as a *closed-box speaker*. Some audiophiles argue that it must always be inherently superior to a bass-reflex design, partly because of the one-wavelength lag time associated with a reflex port. However, as in many aspects of sound reproduction, the debate is inconclusive.

Resonance

The enclosure for a speaker will tend to have a dominant resonant frequency. This should be lower than the lowest frequency that the speaker will reproduce; otherwise, the resonance will emphasize some frequencies relative to others, creating unwanted peaks in the response.

One reason why high-quality speakers tend to be physically heavy is to reduce their resonant frequency. A modern Thiel speaker assembly, for instance, uses a front panel of particle board that is a full 2" thick. However, heavy enclosures are expensive to transport and inconvenient to locate or relocate in the home.

To address this problem, a tweeter and a woofer can be mounted in separate boxes. The enclosure for the tweeter can be very small, lightweight, and suitable for placement on a shelf, while the heavy box for the woofer can go on the floor. Human senses have difficulty locating the source of low-frequency sound, so the woofer can be located almost anywhere in a room. In fact, its single speaker can serve both stereo channels.

This configuration has become the default for computer speakers. It is also used in home-theater systems, where the woofer has now become a subwoofer capable of very low frequency reproduction.

Miniature Speakers

If an electronics project has an audio output, and the circuit board will be sharing an enclosure with a small speaker, the size of the box and the material from which it is fabricated will affect the sound quality significantly. A box made from thin hardwood may add resonance that sounds pleasing, if the speaker is being used just for simple electronic tones. By comparison, a metal box may sound "tinny." A box fabricated from a plastic such as ABS will be relatively neutral, provided the plastic is reasonably thick (1/4" being preferable).

Variants

Electrostatic Speaker

The principle of an electrostatic speaker is the same as that of an electrostatic headphone. A charged membrane is stretched between two grids in front of it and behind it that act as electrodes. Because the membrane is so light, it responds with very little latency, and its large surface area creates a diffused sound that many audiophiles find pleasing. However, a high voltage is required to drive electrostatic speakers, and they are not cheap.

Powered Speakers

A unit containing its own driver electronics is referred to as a *powered speaker*, and is used almost universally with desktop computers, because the computer itself does not contain a power amplifier. Powered speakers may also enable a more versatile crossover network.

A subwoofer may have its own amplifier allowing control of the cutoff frequency above which the speaker will not attempt to reproduce sound. The electronics can include protection for a speaker against being overdriven.

Wireless Speakers

A wireless link between a stereo receiver and its speakers will eliminate the speaker wires that are normally necessary. However, the speakers themselves must be powered, and will have to be wired to electric outlets.

Innovative Designs

The need for small speakers in consumer products such as laptop computers has encouraged innovative designs. The speaker in Figure 30-8 is just 1" square, and its shape is easier to accommodate in a small product than the traditional circular speaker. In Figure 30-9, the interior of the same speaker shows that inductive coils are applied to a square plastic diaphragm.



Figure 30-8. *A speaker 1" square, suitable for use with a small electronic device.*



Figure 30-9. *The speaker from the previous figure, opened to show its inductive coils applied to a square plastic diaphragm.*

Values

The typical *impedance* for speakers in audio systems is 8Ω. Small speakers may have a higher impedance, which can be useful when driving them from devices that have limited power, such as a TTL-type 555 timer.

In the United States, the diameter of a circular speaker is usually expressed in inches. Speakers larger than 12" are rare for domestic use. A 4" speaker used to be considered minimal because of its limited low-end frequency response, but much smaller speakers have become common in portable devices.

The low-end frequency response of a miniature loudspeaker designed to be surface-mounted on a circuit board will be very poor. The graph in Figure 30-10 was derived from data supplied by the manufacturer.



Figure 30-10. *Frequency response for a speaker measuring 15mm x 15mm x 5mm. Small dimensions and lack of an enclosure result in a negligible low-end response.*

Power rating for speakers is in watts, measured on a root-mean-square (RMS) basis.

Sensitivity is measured in decibels, at a distance of one meter, while a speaker is reproducing a single constant tone with a power input of 1W. A speaker assembly designed for undemanding home use may be rated at 85dB to 95dB.

Efficiency is a measure of sound power output divided by electrical power input. A value of 1% is typical.

What Can Go Wrong

Damage

As is the case with headphones, the most common problem affecting a speaker is damage caused by overdriving it. Because a low frequency requires larger excursions of a speaker cone to transmit an amount of energy comparable to that of a high frequency, loud bass notes can be hazardous to the cone. On the other hand, if an amplifier generates distortion (perhaps because it, too, is being overdriven), the harmonics created by the distortion can damage high-frequency speakers.

Magnetic Field

Even a small speaker (measuring 2" or less) contains a magnet that is sufficiently powerful to cause problems if it is in close proximity to other components, especially if sensors such as reed switches or Hall-effect switches are being used. Initial circuit testing should be done with the speaker as far away as possible, to eliminate it as a source of interference.

Vibration

Solder joints will be stressed if they are subjected to low-frequency vibration from a speaker. Loose parts may rattle, and parts that are bolted into place may become unbolted. The speaker itself may become loose. Thread-locker such as Loc-Tite should be applied to nuts before they are tightened.

Index

Symbols

2N682 SCR, 2
4047B timer, 75
40TPS12 SCR, 2
4131-503 digital potentiometer, 62
4543B decoder, 168
4543B decoder chip, 168
555 timer, 70–73, 76, 79–84
5555 timer, 74
556 timer, 73
558 timer, 73
7447 decoder, 148
74HC00 logic gate, 93
74HC123 timer, 75
74HC163 counter, 132
74HC221 timer, 76
74HC4514 decoder, 147
74HC4515 decoder, 139, 147
74HC5555 timer, 74
74HCT5555 timer, 74
74LS123 timer, 75
74LS148 decoder, 139
74LS47 decoder, 148
7555 timer, 74
7556 timer, 74
BTA208X-1000B triac, 16
BTB04-600SL triac, 16
CAT5114 digital potentiometer, 64
CD4047B timer, 75
CMX60D10 relay, 27
D804 optocoupler, 37
DB3TG diac, 12
DC60S7 relay, 27, 28
HEF4528B timer, 75
LM339 comparator, 42
LM3914 driver, 236
LM741 op-amp, 49, 53
M74HC4538 timer, 75
MAC97A6 triac, 16
MAX6954 driver chip, 234
MC14538B timer, 75
NTE926 timer, 73
OPTEKD804 optocoupler, 34
PT-2040PQ transducer, 253
PUI XL453 audio indicator, 257
SSD1306 LED display module, 235
SSD1331 LED display module, 235
TIL311 driver, 236
WS0010 LED display module, 235
X0403DF SCR, 2, 5

A

A-weighting audio standard, 252
absolute zero, 173
acoustically transparent headphones, 264
activator, electroluminescent, 244
active matrix LCD, 161
additive primaries, 166
address of tap, digital potentiometer, 62, 63
Adobe 1998, 167
alert, 249, 257
alternating current, 172
American Standard Code for Information Interchange (ASCII), 163
AMOLED (active-matrix OLED), 246
analog input/output, 66

analog integrated circuits
  comparator, 39–48
    (see also comparator)
  digital potentiometer, 59–67
    (see also digital potentiometer)
  op-amp, 49–58
    (see also op-amp)
  optocoupler, 33–37
    (see also optocoupler)
  solid-state relay, 25–31
    (see also solid-state relay)
  timer, 69–87
    (see also timer)
analog multiplexer, 151, 152
analog output optocoupler, 36
analog-digital converter, 39, 47, 59
AND gate, 45, 90, 91, 92, 97, 98, 100, 102, 103
anode
  LED display, 232
  LED indicator, 213
  vacuum-fluorescent display (VFD), 240
arithmetical operations, binary, 91
arithmetical operators, 89
ASCII (see American Standard Code for Information Interchange)
astable multivibrator, 46, 55, 69
  (see also timer)
astable timer, 70, 72, 77, 80
asynchronous counter, 118, 134
asynchronous flip-flop, 107
asynchronous input, 123
audio alerts
  audio indicator, 257–260
  transducer, 249–255
audio frequency, 54, 251, 252, 253, 254, 257, 258
audio indicator, 249, 257–260
  PUI XL453, 257
  current, 260
  design, 257–258
  duty cycle, 260
  formats, 258
  frequency, 258, 260
  function, 257
  history, 258
  potential problems, 260
  sound intensity, 260
  sound patterns, 258
  use of, 260
  values, 259
  variants, 258
  voltage, 259
  volume control, 260
  wiring, 260
audio transducer (see transducer)

B

back-EMF, 29, 30, 87
backlighting, electroluminescent, 167
backplane, 161
ballast, 180, 192, 194, 225
band gap, 207
bandpass filter, 59
bandwidth, 36
bass-reflex enclosure, 270
bayonet base, 177
BCD output, 135
beeper, 249, 257
bi-pin tube, 194
bidirectional multiplexer, 151
bidirectional optocoupler, 36
bidirectional shift, 125
bidirectional thyristor, 11
binary addition, 91
binary arithmetic, 89, 92
binary counter, 134
binary digit, 121, 134
binary ripple counter, 121
binary-coded decimal (BCD) output, 135
bipolar transistor, 1, 18, 70
bistable displays, 167
bistable multivibrator, 46, 69, 107
  (see also flip-flop)
bit, 121, 134
bitmap, 159, 227
black body radiation, 173
Boolean algebra, 89
Boolean operators, 89, 91
breakdown voltage, 1, 4, 20, 184
breakover frequency, 53
breakover level, 12
breakover voltage, 4, 14, 15, 20
bubble, 90, 116, 123, 133, 155
buffer, 90, 128
burn in, 160
burst mode, 84
buzzer, 249, 257, 258

C

Camenzind, Hans, 70
canalphones, 264
candela, 178
candlepower, 178
capacitor
  coupling, 84
  light-emitting, 244
carbon arc, 171
cascade, 134
cascaded encoders, 142
cascading, 157
cathode, 188, 192, 232, 239
cathode vacuum-fluorescent display (VFD), 240
cathode-ray tube (CRT), 160, 239, 244
CCFL (see cold-cathode fluorescent lamp)
CCT (see correlated color temperature)
cd (candela), 178
ceramic wafer, 250, 258
CFL (see compact fluorescent lamp)
channel current, 155
channels, 42, 52, 153
charge storage, 23, 24
chemiluminescence, 244
chip select pin (CS), 63, 64
cilia, 261
circumaural headphones, 264
clipped output, 50
clock, 121
clock input, 131, 133
clocked comparator, 47
clocked in, 121

closed-back headphones, 264
closed-box speaker, 270
CLR operation, 133
CMOS 555 timer, 74
CMOS chips, 48, 94
CMYK system, 166
CO2 lasers, 201
code hopping encoder, 139
coherent light, 197, 200
cold-cathode fluorescent lamp (CCFL), 191, 194
cold-cathode fluorescent panel, 167
color
  fluorescent lights, 194, 241, 242
  in LCDs, 166–167
  of LEDs, 205, 207, 209–211, 212, 219–222, 222, 226
  primary, 166–167
color rendering index (CRI), 174
color super twisted nematic (CSTN) LCD, 161
color temperature, 173, 209, 219, 222
color-rendering index (CRI), 212
common anode, 232
common cathode, 232
common mode voltage range, 53
common pin, 161
commutating dv/dt, 23
compact fluorescent lamp (CFL), 191
comparator, 39–48, 70, 83, 90
  LM339, 42
  analog-digital converter, 47
  AND gate, 45
  bistable multivibrator, 46
  clocked, 47
  continuous converter, 47
  design, 39–42
  digital, 39
  dual, 42
  function, 39
  hysteresis, 39, 44
  latched, 47
  level shifter, 46
  and op-amps, 42, 52
  potential problems, 47–48
  relaxation oscillator, 46
  use of, 44–47
  values, 43–44
  variants, 42–43
  window, 42
  window comparator, 46
  zero point finder, 47
conduction angle, 7, 9
cone, 268
confused inputs, 48
continuous converter, 47
converter, serial to parallel, 107
correlated color temperature, 222
counter, 107, 121, 131–138
  74HC163, 132
  asynchronous, 118, 134
  binary, 134
  binary ripple, 121
  clock sources, 135
  decade, 135
  decoded output, 134
  descending output, 136
  design, 132–134
  divide-by-16, 134
  function, 131–132
  glitches, 138
  gray code, 131
  hexadecimal, 134
  modulus-16, 134
  modulus/modulo, 132
  multiple stages, 136
  octal, 134
  output states, 136
  pin identifier, 133
  potential problems, 137–138
  programmable, 137
  ring, 131, 134
  ripple, 107, 134, 148
  rising edge and falling edge, 136
  schematic representation, 131–132
  single and dual, 136
  synchronous, 134, 136
  values, 137
  variants, 134–137
coupler, output, 198
coupling capacitor, 84
CRI (see color rendering index)
crossover network, 269
crosstalk, 161
crowbar overvoltage protection, 2
CRT (see cathode-ray tube)
crystal, 249
crystal lasers, 201
crystal-set radio, 265
CS (chip select pin), 63, 64
current
  alternating, 172
  audio-indicator, 260
  channel, 155
  direct, 172
  forward, 211
  gate threshold, 18
  holding, 2, 18
  latching, 2, 18
  leakage, 156
  transducer, 254
current amplifier, 2, 18
Current Transfer Ration (CTR), 36

D

D-type flip-flop, 114, 116
data distributor, 140, 146, 152
data selector, 140, 146, 151, 152 (see also multiplexer)
data transfer, 62
Db (see decibels)
dBA, 253
debounced, 66
decade counter, 135
decibel, 251–252, 259, 265
decoded output counter, 134
decoder, 134, 139, 140, 143, 145–149, 151, 153, 157
  7447, 148
  74HC4514, 147
  74HC4515, 147
  74LS47, 148
  design, 148
  function, 145–146
  input devices, 145–146
  LED driver, 146
  potential problems, 149–149
  schematic symbol, 146–146

    - seven-segment, 146
    - similar devices, 146
    - use of, 149
    - values, 148
    - variants, 148
- decoder chip, 151
- demultiplexer, 140, 146, 151
- derated relay, 30
- derating curve, 213
- descending output counter, 136
- diac, 1, 11–14, 15, 22
    - DB3TG, 12
    - abbreviations, 14
    - design, 12–13
    - function, 11
    - potential problems, 14
    - switching AC, 13
    - symbol variants, 11
    - values, 14
    - variants, 13
- diaphragm, 262, 268
- dies, 219
- differential multiplexer, 152
- digipot (see digital potentiometer)
- digital comparator, 39
- digital integrated circuits
    - counter, 131–138
    - decoder, 145–149
    - encoder, 139–143
    - flip-flop, 107–119
    - logic gate, 89–106
    - multiplexer, 151–157
    - shift register, 121–129
- digital multiplexer, 151
- digital potentiometer, 59–67, 156
    - 4131-503, 62
    - CAT5114, 64
    - address of tap, 62, 63
    - advantages/disadvantages, 59–60
    - connections and modes, 64
    - data transfer, 62
    - design, 60–61
    - function, 59–60
    - higher resolution, 66
    - I2C protocol, 63
    - potential problems, 66
    - programmable, 59
    - SPI protocol, 62
    - taper, 62
    - up/down protocol, 63
    - use of, 66
    - values, 65–66
    - variants, 61–65
    - volatile/nonvolatile memory, 61
- digital-analog converter, 39, 47, 59
- digitally adjustable potentiometer (see digital potentiometer)
- digitally controlled potentiometer (see digital potentiometer)
- digitally programmed potentiometer (DPP) (see digital potentiometer)
- digpot (see digital potentiometer)
- diode, PIN, 35
- diode, protection, 30
- direct current, 172
- disallowed state, 135
- discrete semiconductor
    - diac, 22
- discrete semiconductors, 1
    - (see also thyristor)
- dispersion, 178, 208, 225
- display
    - electroluminescent (see electroluminscent (EL) display)
    - LED (see LED display)
- display module, 164, 231
- divide-by-16 counter, 134
- dot-matrix displays, 163–165, 230, 234–236, 239
- double super twisted nematic LCD, 161
- drift, 48
- driver, 267
- driver chip, 233–234
- driver, dynamic, 262
- dual comparator, 42
- dual counter, 136
- dual digital potentiometer, 61
- dual inputs, 50–51, 127
- dual monostable timer, 75–76, 77
- dual voltage device, 39
- dual voltage power supply, 50
- duty cycle, 260
- dv/dt triggering, 8
- dynamic driver, 262
- dynamic transducer, 262

E

- e-ink displays, 167
- ear canal headphones, 264
- earbuds, 261, 263, 264
- earphone, 261, 264
- edge pass, 69
- edge triggering, 69
- edge-triggered shift register, 123
- efficiency, 272
- EL (see electroluminescent (EL) display)
- electret, 264
- electric newspaper, 236
- electroluminescence, 243
- electroluminescent (EL) display, 243–247
    - derivation, 244
    - design, 243
    - flexible ribbons, 245
    - function, 243
    - OLED, 246–247
    - panels, 244–245
    - phosphors, 244
    - rope light, 245
    - variants, 244–247
- electroluminescent backlighting, 167
- electromagnetic relay, 33
- electromagnetic transducer, 250, 253
- electronic ballast, 193, 225
- electronic paper displays, 167
- electrostatic headphones, 263
- electrostatic speaker, 271
- Enable, 116
- encoded output, 134
- encoder, 139–143, 152
    - 74HC4515 decoder, 139
    - 74LS148 decoder, 139
    - cascaded, 142
    - code hopping, 139
    - design, 140–141

  - function, 139–140
  - potential problems, 143
  - priority, 140, 141
  - rotary, 139
  - rotational, 66
  - schematic symbol, 139
  - similar devices, 140
  - simple, 141
  - tri-state, 141
  - use of, 142
  - values, 142
  - variants, 141
- equal-loudness contours, 252
- erratic output, 48

F

- falling voltage, 43
- falling-edge triggered shift register, 123
- fanout, 94
- feedback
  - negative, 51–52
  - positive, 44
- ferromagnetic disc, 250
- FF (see flip-flop)
- fiber lasers, 201
- FIFO (see first-in, first-out (FIFO) shift register)
- filament, 171, 239
- film-compensated super twisted nematic (FSTN) LCD, 161
- first-in, first-out (FIFO) shift register, 123
- flange base, 177
- flexible ribbon, 245
- flicker, 193
- flip-flop, 46, 70, 89, 107–119, 121, 132
  - asynchrononous/synchronous, 107
  - D-type, 114
  - design, 107–116
  - forbidden states, 110–112
  - function, 107
  - JK, 112–113
  - master-slave, 113
  - NAND-based, 108–109
  - NOR-based, 109–110
  - packaging, 117
  - potential problems, 118–119
  - summary of types, 116
  - use of, 118
  - values, 117–118
  - variants, 116–117
- flip-flop emulation, 82
- floating inputs, 127
- floating pins, 105
- fluoresce, 192
- fluorescence, 191, 239
- fluorescent lamp, 191
- fluorescent light, 24, 167, 174, 191–196, 207, 217, 223, 239
  - (see also vacuum-fluorescent display)
  - ballast and starter, 192
  - brightness, 195
  - CCFLs, 194
  - comparisons, 194
  - design, 191–195
  - flicker, 193
  - function, 191
  - potential problems, 195
  - sizes, 194–194
  - spectrum, 195
  - tubes, 191
  - values, 195
  - variants, 193
- fluorescent tubes, 191
- flux, 177
- foot-candles, 178
- forbidden states, 110–112
- frequency
  - audio, 54, 251, 252, 253, 254, 257, 258, 260
  - breakover of op amp, 53
  - unity gain, 53
- frequency response, 265
- fused quartz, 176

G

- gain, 50
- gain medium, 198
- game sound, 85
- gamut, 167, 207
- ganged analog potentiometer, 61
- gas-discharge device, 191
- gate threshold current, 18
- gate turn-off thyristor (GTO), 1, 11, 15
- gated circuit, 113
- glitches, 138, 149
- glow discharge, 185
- gray code counters, 131
- ground loops, 35
- GTO (see gate turn-off thyristor)

H

- half adder, 92
- halogen lighting, 176, 217, 221
- harmonics, 266
- headphone, 261–266
  - acoustically transparent, 264
  - balanced armature, 264
  - circumaural, 264
  - closed-back, 264
  - design, 261–262
  - distortion, 266
  - electret, 264
  - electrostatic, 263
  - frequency response, 265–266
  - function, 261
  - impedence, 266
  - in-ear, 264
  - intensity, 265
  - mechanical design, 264–265
  - moving coil, 262–263
  - noise-cancelling, 264
  - open-back, 264
  - potential problems, 266
  - supra-aural, 264
  - values, 265–266
  - variants, 262–265
- headset, 264
- hearing aids, 261
- heat sensitivity, 14
- heat sink, 28, 206, 222
- Hertz, Heinrich Rudolph, 262
- hexadecimal counter, 134
- high linearity optocouplers, 36
- high logic state, 89
- high speed optocoupler, 36

high-brightness LED, 205, 217, 227
high-intensity LED, 217
high-output LED, 217
high-pass filter, 55
high-power LEDs, 217
Hold state, 109, 114
holding current, 2, 18
holding level, 12
hysteresis, 42, 44–45, 48, 83, 185
hysteresis range, 43
hysteresis zone, 39

I

I2C protocol, 62, 63
IEM (see in-ear monitor)
ignition voltage, 184
illuminance, 178
impedence, 271
in-ear earphones, 264
in-ear headphones, 264
in-ear monitor, 264
incandescence, 191, 243
incandescent bulbs, 219
incandescent lamp, 11, 15, 24, 171–181, 200, 223
  advantages/disadvantages, 179–180
  base variants, 177
  derating, 180
  design, 172–175
  efficacy, 179
  efficiency, 179
  function, 171–172
  halogen or quartz halogen, 176
  illuminance, 178
  intensity, 178
  mean spherical candlepower (MSCP), 178
  miniature lamps, 175–176
  non-incandescent sources, 174
  oven lamp, 176
  panel-mount indicator lamp, 176
  potential problems, 180
  power, 177–178
  power consumption, 175
  schematic symbols, 171
  spectrum, 173
  use of, 179–180
  values, 177–179
  variants, 175–177
incandescent lamps, 206, 217
incoherent light, 159
increment/decrement protocol, 62
Indiglo electroluminscent displays, 244
inductor, 193
infrared emitters, 211
inhibit pin, 153
input
  analog, 66
  asynchronous, 123
  clock, 131, 133
  confused, 48, 58
  dual, 50–51, 127
  floating, 127
  inverting/noninverting, 39, 51
  parallel, 123, 134
input bias current, 53
input devices, decoder, 145
input differential voltage range, 53
input offset voltage, 43, 53
input voltage, 155
instant-start ballast, 194
integrated circuits (see analog integrated circuits, digital integrated circuits)
inter-integrated circuit, 62
internal sensors, 35
internal series resistor, 210
intrinsic layer, optocoupler, 35
invalid number, 135
inversion, logic gates, 90
inverter, 36, 89, 91, 114
inverting input, 39, 51
ionization, 184
isolation transformers, 34

J

jam loaded, 134
jam-type flip-flop, 108
jam-type parallel data input, 124
jitter, 44
JK flip-flop, 112–113, 116

K

keyboard, polling, 127

L

ladder, 60
lamp
  oven, 176
  panel-mount indicator lamp, 176
lamp lenses, 176
laser, 197–203
  CO2 lasers, 201
  coherent light, 200–201
  common applications, 202
  crystal lasers, 201
  design, 198–201
  fiber lasers, 201
  function, 197
  laser diode, 197, 198–199
  potential problems, 202
  use of, 202
  values, 201
  variants, 201
laser diode, 197, 198–199
latch, 107, 112
latch function, 43
latched comparator, 47
latching current, 2, 18
latching relay, 4
LCD (liquid-crystal display), 159–170, 207, 227, 246
  4543B decoder, 168
  active and passive types, 161
  additional segments, 162–163
  alphanumeric display module, 168–169
  backlighting, 167

  - color, 166–167
  - color super twisted nematic (CSTN), 161
  - crystal types, 161
  - design, 159–160
  - dot-matrix displays, 163–165
  - double super twisted nematic, 161
  - film-compensated super twisted nematic (FSTN), 161
  - function, 159
  - LED comparisons, 228
  - numeric display module, 167–168
  - potential problems, 169–170
  - reflective, 161
  - seven-segment displays, 161–162
  - super twisted nematic (STN), 161
  - transreflective, 161
  - twisted nematic (TN), 161
  - use of, 167–169
  - variants, 160–167
  - zero-power displays, 167
- LCD display (see LCD (liquid crystal display))
- leakage
  - capacitors, 77
  - diac, 12
  - SCR, 2
  - solid-state relay (SSR), 26
  - triac, 17
- leakage current, 156
- LED (generic), 26, 159, 167, 174, 227, 243
- LED area lighting, 24, 191, 195, 217–226, 227
  - color variation, 222
  - comparisons, 220–222, 223–224
  - costs and efficiency, 218
  - design, 218–223
  - dimming, 222
  - efficacy, 222
  - function, 217–218
  - heat dissipation, 222
  - high-brightness, 217
  - high-output, 217
  - high-power, 217
  - potential problems, 225
  - schematic symbol, 218
  - ultraviolet output, 222
  - values, 225
  - variants, 223–224
  - visible differences, 220–220
- LED display, 146, 227–237
  - LM3914, 236
  - MAX6954, 234
  - SSD1306, 235
  - SSD1331, 235
  - TIL311, 236
  - WS0010, 235
  - additional segments, 229–230
  - design, 228
  - dot-matrix displays, 230, 234–236
  - driver chips and multiplexing, 233–234
  - function, 227–228
  - LCD comparisons, 228
  - multiple bar display, 232, 236
  - multiple numerals, 229
  - one-digit hexadecimal dot matrix, 236
  - pixel arrays, 231, 235–236
  - potential problems, 237
  - seven segment numeral, 228
  - seven-segment displays, 228–229, 232–233
  - single light bar, 232
  - sixteen-segment driver chip, 234
  - use of, 232–236
  - values, 232
  - variants, 228–232
- LED indicator, 205–215, 218, 227
  - color rendering index (CRI), 212
  - common usage, 206
  - comparisons to other light emitters, 214
  - design, 207
  - diffusion, 209
  - efficacy, 208
  - forward current, 211
  - forward voltage, 212
  - function, 205–207
  - high-brightness, 205
  - infrared, 211
  - intensity, 208
  - internal resistor, 210
  - LEDs in parallel, 214
  - life expectancy, 212
  - light output and heat, 212
  - low-current LEDs, 211
  - multicolor LEDs and color mixing, 207
  - multicolored, 210
  - multiple series LEDs, 214
  - other applications, 215
  - polarity, 213
  - potential problems, 215
  - schematic symbols, 206
  - series resistor value, 214
  - size and shape, 208
  - ultraviolet, 211
  - use of, 213–215
  - values, 211–213
  - variants, 208–211
  - view angle, 213
  - wavelength and color temperature, 209–210
- lens, 183
- level shifter, 46
- light
  - coherent, 197, 200–201
  - incoherent, 159
  - monochromatic, 197
- light wires, 243
- light-emitting capacitor, 244
- light-emitting diode (see LED)
- linear relationship, 50
- linear taper, 62
- linearity versus saturation, 42
- liquid-crystal display (see LCD)
- logarithmic taper, 62
- logic chip, 139
- logic gate, 89–106, 108, 126, 140
  - 74HC00, 93
  - 4000 series, 94
  - 7400 series, 93
  - binary arithmetical operations, 91
  - Boolean notation, 91
  - chip families, 95–96
  - design, 89

  - function, 89
  - gates and inputs, 90, 96–103
  - inversion, 90
  - part numbers, 94–95
  - potential problems, 105–106
  - uses, 103
  - variants, 93
- logic state, 89, 107
- logic, positive, 90
- logic, transistor-transistor, 70, 93
- logic-output optocoupler, 36
- loudspeaker, 84, 249, 263, 267
- low logic state, 89
- low-current LEDs, 211
- low-pass filter, 54
- Lower State Transition Voltage (LSTV), 43
- lumen (lm), 177, 195, 218, 225
- lumens per watt, 179, 195
- luminaire, 217
- luminary, 217
- luminescence, 191, 243
- luminous flux, 177, 195, 208, 218
- lux, 178

M

- magnetic ballast, 225
- maintaining voltage, 185
- maser, 197
- master-slave flip-flop, 113, 116
- mc (millicandela), 178
- mean spherical candlepower (MSCP), 176, 178
- metal-oxide semiconductor field-effect transistor (see MOSFET)
- metastability, in flip-flops, 119
- microcontroller, 29, 59
- microphone, 262
- millicandelas, 187, 208
- miniature speakers, 270
- mismatching, 266
- mixed-signal device, 59
- MOD, 133
- mode select pins, 125
- modulo/modulus, 132
- modulus-16 counter, 134
- monochromatic light, 197
- monostable multivibrator, 69
  - (see also timer)
- monostable timer, 69, 71, 77, 79
- MOSFET (metal-oxide semiconductor field-effect transistor), 26, 70
- motion detector, passive infrared, 211
- motor, AC, 11
- moving coil headphones, 262
- MSCP (see mean spherical candlepower)
- multicolor LED, 207
- multiple bar display, 232, 236
- multiple series LED, 214
- multiple-stage counter, 136
- multiplexer, 28, 140, 146, 151–157
  - analog, 151, 152
  - bidirectional, 151
  - demultiplexer, 140, 146, 151, 152, 157
  - design, 153
  - differential, 152
  - digital versus analog, 151
  - function, 151
  - pin identifiers, 154–155
  - potential problems, 157
  - schematic symbol, 153
  - similar devices, 152–153
  - use of, 156
  - values, 155
  - variants, 155
- multiplexing, 168, 233–234, 241
- multisource lighting
  - electroluminescent (EL) display, 243–247
  - LED display, 227–237
  - vacuum-fluorescent display (VFD), 239–242
- multivibrator, 69
  - (see also timer)
  - astable, 46, 55, 69
  - bistable, 46, 69, 107
- MUX (see multiplexer)

N

- NAND gate, 37, 90, 91, 93, 94, 95, 97, 98, 100, 102, 103, 108, 109, 123, 127, 135
  - (see also NAND-based SR flip-flop)
- NAND-based SR flip-flop, 108–109, 116
- nanometer, 195, 209
- negative feedback, 49, 51–52
- negative resistance, 185
- neon bulb, 31, 183–190, 191, 193
  - construction, 184
  - efficiency, 187
  - function, 183
  - how it works, 183–186
  - ionization, 184
  - life expectancy, 188
  - light output, 187
  - negative resistance, 185–186
  - Nixie tubes, 189
  - potential problems, 189
  - power-supply testing, 188
  - ruggedness, 187
  - use of, 186–189
  - variants, 189
- neon bulbs, 206
- neon indicator, 183
- neon lamp, 183
- neon lamp assembly, 183
- neutral value, 49
  - (see also zero value)
- Newtons per square meter (Pa), 251
- Nixie tubes, 189
- noise-cancelling headphones, 264
- noise-creating device, 249, 267
- noninverting input, 39, 51
- nonvolatile memory, 61
- NOR gate, 90, 91, 97, 98, 100, 102, 103, 108, 109
  - (see also NOR-based SR flip-flop)
- NOR-based SR flip-flop, 109–110
- numeric display module, 167–168

NV (see nonvolatile memory)

O

octal counter, 134
OE (output-enable), 126
offset null adjustment, 56
OLED (organic light-emitting diode), 217, 227, 243, 246–247
on-resistance, 156
one-digit hexadecimal dot matrix, 236
op-amp, 39, 49–58, 90
  LM741, 49, 53
  calculating amplification, 53
  and comparators, 52
  confused input, 58
  controlling the gain, 53
  design, 49–52
  differences from comparator, 42
  dual inputs, 50–51
  as high-pass filter, 55
  as low-pass filter, 54
  negative feedback, 51–52
  offset null adjustment, 56
  oscillating output, 57
  potential problems, 57–58
  as relaxation oscillator, 55
  as single power source, 56
  use of, 53–57
  values, 52
  variants, 52
  what it does, 49
open collector, 40
open loop mode, 51
open loop operation, 42
open loop voltage gain, 53
open-back headphones, 264
open-drain outputs, 126
operating voltage, 259
operational amplifier (see op-amp)
optical maser, 197
optical switch, 34
optocoupler, 25, 33–37, 215
  D804, 37
  OPTEKD804, 34
  analog output, 36
  basic types, 36
  bidirectional, 36
  design, 34–34
  function, 33–34
  high speed, 36
  high-linearity, 36
  internal sensors, 35–36
  logic-output, 36
  potential problems, 37
  schematic symbols, 34
  use of, 36–37
  values, 36
  variants, 34–36
OR gate, 90, 91, 97, 98, 99, 100, 102, 103, 140, 142
organic LED (see OLED (organic light-emitting diode))
oscillating output, 47, 57
oscillator, relaxation, 12, 46, 55
output
  analog, 66
  clipped, 50
  descending, 136
  encoded, 134
  erratic, 48
  open-drain, 126
  oscillating, 47, 57
  parallel, 123
  push-pull, 42
  three-state, 142
  types of, 134
  ultraviolet, 222
  weighted, 134
output coupler, 198
output mode, comparator, 42
oven lamp, 176
overvoltage protection, 2, 6, 155

P

Pa (Pascals), 251
panel, 243
Panelescent electroluminescent lighting, 244
parallel input, 134
parallel-enable pin, 134
parallel-in, parallel-out (PIPO) shift converters, 125
parallel-in, serial-out (PISO) shift register, 124
parallel-serial converters, 124
parchmentized thread, 172
passive infrared motion detector, 211
passive matrix LCD, 161
phase angle, 7, 13
phase control, 2, 7–7, 13, 22
phones (see headphone)
phosphor, 192, 239, 244
phosphorescence, 244
photocell, 35
photodarlington, 34
photodiode, 26, 34
photon, 207
photoresistor, 34
phototransistor, 26, 34, 45
photovoltaic PIN diode, 35
piezein, 250
piezo, 258
piezoelectric alerts (see audio indicator)
piezoelectric transducer, 249, 250, 253
pin
  common, 161
  floating, 105
  inhibit, 153
  parallel-enable, 134
  reset, 70
  trigger, 69
pin base, 177
PIN diode, 35
pin identifier, 133
pip, 184
PIPO (see parallel-in, parallel-out (PIPO) shift converters)
pixel arrays, 231, 235–236
PMOLED (passive-matrix OLED), 246
PN junction, 207
PNPN device, 3
polling a keyboard, 127
positive feedback, 44
positive logic, 90

potentiometer, 35
  (see also digital potentiometer)
power rating, 272
powered speaker, 271
primary colors, 166–166
priority encoder, 140, 141
programmable counter, 137
programmable digital potentiometer, 59
programmable unijunction transistor (PUT), 2, 9
propagation delay, 44, 134
protection diode, 30
pullup resistor, 36, 40, 48, 71, 126, 153
pulse-width modulation, 7, 194, 211
pumping a laser, 198
push-pull output, 42
pushbutton, 66, 71
pushbutton protocol, 62

Q

quad digital potentiometer, 61
quadrants, 17–18
quartz crystal, 131, 135

R

race condition, 112
radiant flux, 177
radiant luminous efficacy (LER), 179, 187, 208, 222
radiant luminous efficiency (LFR), 179
radiation, black body, 173
rail-to-rail values, 42
rapid-start ballast, 194
rated voltage, 259
Rayleigh scattering, 202
RC network, 70
rectifier, 2
reference voltage, 70
reflective display (see LCD (liquid crystal display))
reflective LCD, 161
reflective primaries, 166
reflex port, 270
regenerative device, 2
register, 121
relaxation oscillator, 12, 46, 55
relay
  electromagnetic, 33
  latching, 4
  solid-state (see solid-state relay)
  zero-crossing, 25, 27
remainder, 132
reproducers
  headphone, 261–266
  speaker, 267–272
reset pin, 70
reset state, 109
resistor array, 232
resolution, 43
resonant cavity, 198
response time, comparator, 42
restricted combination, 112
retriggering, timer, 69
RGB LCD monitors, 167
RGB primaries, 166
rheostat mode, 64
ring counter, 121, 131, 134
ringing, 112
ripple counter, 107, 134, 148
rising voltage, 43
rising-edge triggered shift register, 123
rope light, 243, 245
rotary encoder, 139
rotary switch, 151
rotational coder, 139
rotational encoder, 66

S

saturation versus linearity, 42
SCR (silicon-controlled rectifier), 1–9, 11, 15, 26, 34
  2N682, 2
  40TPS12, 2
  X0403DF, 2, 5
  abbreviations, 6
  AC current applications, 5
  breakdown and breakover voltage, 4
  concept demo, 4
  design, 1–2
  function, 1
  internal configuration, 3–5
  overvoltage protection, 7
  phase control, 7–7
  potential problems, 8–9
  switching behavior, 2
  use, 6–8
  values, 5
  variants, 5, 6
screw-in lamps, 177
SCS (see silicon-controlled switch)
segments, 239
self-drive transducer circuit, 254
sensitivity, 272
sensor, 34, 35, 249, 262
serial peripheral interface (see SPI)
serial-in, parallel-out (SIPO) shift register, 123, 124
serial-in, serial-out (SISO) shift register, 123, 124
serial-parallel coverter, 123
serial-to-parallel converters, 107
series resistor, 207
series resistor value, 214
settling time, 149, 157
setup time, 125
seven-segment decoder, 146
seven-segment displays, 228–229, 232–233
seven-segment numeral, 228
shift register, 63, 121–129, 131, 146
  abbreviations and acronyms, 123
  arithmetical operations, 127
  buffering, 128
  design, 122
  function, 121–122
  parallel outputs and inputs, 123–124
  polling the keyboard, 127
  potential problems, 128–129

- power considerations, 126
- preloading, 127
- schematic representation, 122
- three-state output, 126
- use of, 126–128
- values, 125–126
- variants, 124–125

shift registers, 107
shortened modulus, 135
sidac, 14
silicon-controlled rectifier (see SCR)
silicon-controlled switch (SCS), 1, 11, 15
simple encoder, 141
single counter, 136
single light bar, 232
single power source, 56
single-inline package (SIP), 27
single-input gates, 90
single-source lighting
- fluorescent light, 191–196
- incandescent lamp, 171–181
- lasers, 197–203
- LED area lighting, 217–226
- LED indicator, 205–215
- neon bulb, 183–190

sink current, 44
SIPO (see serial-in, parallel-out (SIPO) shift register)
siren, 258
SISO (see serial-in, serial-out (SISO) shift register)
sixteen-segment driver chip, 234
slew rate at unity gain, 53
snubber, 30
snubber network, 23
snubberless triac, 23
solid-state analog switch, 28
solid-state relay (SSR), 1, 11, 15, 25–31, 33, 36, 215
- (see also optocoupler)
- CMX60D10, 27
- DC60S7, 27, 28
- advantages/disadvantages, 25
- design, 26–27
- function, 25–26
- instantaneous versus zero crossing, 27
- NC and NO modes, 28
- packaging, 28
- potential problems, 30
- solid-state analog switch, 28
- use of, 29–30
- values, 29
- variants, 27–28

sound pressure level, 251–252, 251
sound reproduction device, 249, 267
sound sources (see audio alerts, reproducers)
spatial coherence, 200
spatial distribution, 213
speaker, 249, 267–272
- closed-box, 270
- construction, 268
- design, 267–270
- electrostatic, 271
- function, 267
- innovative designs, 271
- miniature speakers, 270
- multiple drivers, 269–270
- potential problems, 272
- powered, 271
- resonance, 270
- values, 271
- variants, 270–271
- venting, 270
- wireless, 271

spectral lines, 174
SPI (serial peripheral interface), 62
spontaneous emission, 198
SPST switch, 25
sputtering, 188
SR flip-flop (see NAND-based SR flip-flop)
sRGB, 167
SSR (see solid-state relay)
standard LED, 205, 227
starter, 192, 225
starting voltage, 184
state diagram, 135
steradians, 178
stimulated emission, 198
striking voltage, 184
strip lights, 223
strobe, 153
super twisted nematic (STN) LCD, 161
supra-aural headphones, 264
surface-mount transducers, 251
swapped voltages, 48
switch, 25, 71, 107
- rotary, 151
- silicon-controlled (SCS), 1, 11, 15
- solid-state analog switch, 28
- SPST, 25

switch bounce, 109
synchronous circuit, 113
synchronous counter, 134, 136
synchronous flip-flop, 107

T

T-type flip-flop, 116
tap, 60
tap address, 62, 63
taper, 62
task lighting, 217
TFT (see thin-film transistor)
THD (see total harmonic distortion)
thermal compound, 30
thick phosphor, 244
thin-film OLED, 243
thin-film transistor (TFT), 161, 246
3-wire programmable potentiometers, 63
three-state output, 126, 142
three-wire chips, 64
threshold voltage, 207
through hole, 206
thyratron, 1
thyristor
- diac, 11–14, 15
- SCR, 1–9
- triac, 15–24

timer, 69–87
- 4047B, 75
- 555, 70–85
- 5555, 74
- 556, 73
- 558, 73

  74HC123, 75
  74HC221, 76
  74HC5555, 74
  74HCT5555, 74
  7555, 74
  7556, 74
  CD4047B, 75
  HEF4528B, 75
  M74HC4538, 75
  MC14538B, 75
  NTE926, 73
  astable mode, 70, 72, 77, 80
  bipolar version, 70
  burst mode, 84
  CMOS 555, 74
  CMOS version, 71
  and coupling capacitors, 84
  design, 70
  dual monostable, 75–76, 77
  function, 69–70
  game sound, 85
  hysteresis, 83
  loudspeaker connection, 84
  monostable mode, 69, 71, 77, 79
  output time control, 80
  potential problems, 85–87
  TTL version, 70
  use of, 79–85
  values, 76–79
  variants, 70–76
toggle, 43, 113
total harmonic distortion (THD), 266
transducer, 249–255, 257, 267
  PT-2040PQ, 253
  AC supply, 254
  current, 254
  design, 249
  dynamic, 262
  electromagnetic, 250, 253
  formats, 251
  frequency range, 251
  function, 249
  limitations, 253–254
  measurement location, 253
  piezoelectric, 249, 250, 253
  potential problems, 254
  self-drive transducer circuit, 254
  sound intensity, 254
  sound pressure, 251–252
  surface-mount, 251
  ultrasonic, 250
  unweighted values, 253
  use of, 254
  values, 251–254
  variants, 250–251
  voltage, 254
  volume control, 254
  weighted sounds values, 252–253
transformer, isolation, 34
transistor, bipolar, 1
transistor-transistor logic, 93
transistor-transistor logic protocol, 70
transparent, 108, 114
transreflective LCD, 161
tri-state encoder, 142
triac, 1, 7, 11, 15–24, 25, 34
  BTA208X-1000B, 16
  BTB04-600SL, 16
  MAC97A6, 16
  breakover voltage, 20
  charge storage, 23
  design, 17–23
  function, 15–16
  other drivers, 22
  potential problems, 24
  quadrants, 17–18
  snubberless, 23
  switching AC, 20–22
  symbol variants, 15–16
  testing, 19–20
  triggered by diac, 22
  values, 23–24
  variants, 23
triac-based dimmer, 179
trigger pin, 69
trimmer, 40, 254
truth table, 90
TTL (see transistor-transistor logic)
tweeter, 269
twisted nematic (TN) LCD, 161
two-wire chips, 64

U

ultrasonic transducer, 250
ultraviolet output, 222
unity gain frequency, 53
universal shift register, 125
unweighted sound values, 253
up/down protocol, 62, 63
Upper State Transition Voltage (USTV), 43

V

Vactrol, 35
vacuum-fluorescent display, (VFD), 239–242
  anode in, 240
  cathode, 240
  character sets and pictorial design, 242
  color, 241
  comparisons, 242
  design, 239–240
  function, 239
  modern application, 241
  potential problems, 242
  use of, 240–241
  variants, 241–242
variable frequency drive, 239
velocity, 262
vent, 270
VFD (see vacuum-fluorescent display)
view angle, 208
volatile memory, 61
voltage, 259
  breakdown, 1, 4, 20, 184
  breakover, 4, 15, 20
  dual, 39
  falling, 43
  forward, 212
  ignition, 184
  input, 155
  input offset, 43, 53
  maintaining, 185
  in multiplexers, 155
  operating, 259

  - rated, 259
  - reference, 70
  - rising, 43
  - starting/striking, 184
  - threshold, 207
  - transducer, 254

voltage amplification, 53
voltage amplifier, 49
voltage converter, 39
voltage divider, 71
voltage divider mode, 65
voltage gain, 43
voltage level, 69
voltage regulator, 59
voltage spike, 72
voltage transition, 69

W

wafers, 219
water clear, 205
wavelength, 262
wavelength coherence, 200
wedge base, 177
weighted output, 134
weighted sound values, 252–253
window comparator, 42, 46
wiper, 60
wiper resistance, 65
wireless speaker, 271
woofer, 269

X

XNOR gate, 90, 91, 98, 100, 102, 103
XOR gate, 90, 91, 92, 97, 98, 100, 102, 103

Z

zero point finder, 47
zero value, 49
zero-crossing relay, 25, 27
zero-crossing signal, 66

About the Authors

Charles Platt is a contributing editor and regular columnist for *Make:* magazine, where he writes about electronics. He is the author of the highly successful introductory hands-on book, *Make: Electronics*, and its sequel, *Make: More Electronics*. His science fiction novels are currently being reissued by Stairway Press.

Platt was a Senior Writer for *Wired* magazine and has written various computer books. As a prototype designer, he created semi-automated rapid cooling devices with medical applications, and air-deployable equipment for first responders. He was the sole author of four mathematical-graphics software packages, and has been fascinated by electronics since he put together a telephone answering machine from a tape recorder and military-surplus relays at age 15. He lives in a Northern Arizona wilderness area, where he has his own workshop for prototype fabrication and projects that he writes about for *Make:* magazine.

Fredrik Jansson is a physicist from Finland, with a PhD from Åbo Akademi University. He is currently living in the Netherlands, where he works on swarm robotics and simulates sea animals in the computational science group at the University of Amsterdam. Fredrik has always loved scavenging discarded household electronics for parts, and is a somewhat inactive radio amateur with the call sign OH1HSN. He also fact-checked Charles Platt's previous book, *Make: More Electronics*.

Colophon

The cover and body font is Myriad Pro, the heading font is Benton Sans, and the code font is Ubuntu Mono.

Technology & Engineering / Sensors

VOL. 3

Encyclopedia of Electronic Components

Sensors

Want to know how to use an electronic component? This third book of a three-volume set includes key information on electronic sensors for your projects—complete with photographs, schematics, and diagrams. You'll learn what each one does, how it works, why it's useful, and what variants exist. No matter how much you know about electronics, you'll find fascinating details you've never come across before.

Convenient, concise, well-organized, and precise

Perfect for teachers, hobbyists, engineers, and students of all ages, this reference puts reliable, fact-checked information right at your fingertips. Beginners will quickly grasp important concepts, and more experienced users will find the specific details their projects require.

- **Unique:** the first and only multivolume encyclopedia of electronic components, distilled into three separate volumes
- **Instructive:** each component description provides details about substitutions, common problems, and workarounds
- **Incredibly detailed:** includes information distilled from hundreds of sources
- **Easy to browse:** parts are clearly organized by component type
- **Authoritative:** fact-checked by experts to ensure current and accurate information
- **Reliable:** a more consistent source of information than online sources, product datasheets, and manufacturer's tutorials
- **Comprehensive:** Volume 1 covers power, electromagnetism, and discrete semiconductors; Volume 2 includes integrated circuits, and light and sound sources; Volume 3 covers all major types of sensing components

Charles Platt is the author of *Make: Electronics* and *Make: More Electronics*. He is a former senior writer for *Wired* magazine, and is a contributing editor to *Make:* magazine, for which he writes a column on electronics.

Fredrik Jansson is a physicist from Finland, with a PhD from Åbo Akademi University. He is currently living in The Netherlands, where he works on swarm robotics and simulates sea animals in the Computational Science group at the University of Amsterdam. Fredrik has always loved scavenging discarded household electronics for parts, and is a somewhat inactive radio amateur with the call sign OH1HSN.

US $29.99 CAN $34.99
ISBN: 978-1-4493-3431-4

Make:
makezine.com

3

Make: **Encyclopedia of Electronic Components** **Platt & Jansson**

Make:

VOL. 3

Charles Platt and Fredrik Jansson

Encyclopedia of Electronic Components

Sensors

Location ▪ Presence ▪ Proximity ▪ Orientation ▪ Oscillation ▪ Force ▪ Load ▪ Human Input ▪ Liquid and Gas Properties ▪ Light ▪ Heat ▪ Sound ▪ Electricity

Technology & Engineering / Sensors

VOL. 3

Encyclopedia of Electronic Components

Sensors

Want to know how to use an electronic component? This third book of a three-volume set includes key information on electronic sensors for your projects—complete with photographs, schematics, and diagrams. You'll learn what each one does, how it works, why it's useful, and what variants exist. No matter how much you know about electronics, you'll find fascinating details you've never come across before.

Convenient, concise, well-organized, and precise

Perfect for teachers, hobbyists, engineers, and students of all ages, this reference puts reliable, fact-checked information right at your fingertips. Beginners will quickly grasp important concepts, and more experienced users will find the specific details their projects require.

- **Unique:** the first and only multivolume encyclopedia of electronic components, distilled into three separate volumes
- **Instructive:** each component description provides details about substitutions, common problems, and workarounds
- **Incredibly detailed:** includes information distilled from hundreds of sources
- **Easy to browse:** parts are clearly organized by component type
- **Authoritative:** fact-checked by experts to ensure current and accurate information
- **Reliable:** a more consistent source of information than online sources, product datasheets, and manufacturer's tutorials
- **Comprehensive:** Volume 1 covers power, electromagnetism, and discrete semiconductors; Volume 2 includes integrated circuits, and light and sound sources; Volume 3 covers all major types of sensing components

Charles Platt is the author of *Make: Electronics* and *Make: More Electronics*. He is a former senior writer for *Wired* magazine, and is a contributing editor to *Make:* magazine, for which he writes a column on electronics.

Fredrik Jansson is a physicist from Finland, with a PhD from Åbo Akademi University. He is currently living in The Netherlands, where he works on swarm robotics and simulates sea animals in the Computational Science group at the University of Amsterdam. Fredrik has always loved scavenging discarded household electronics for parts, and is a somewhat inactive radio amateur with the call sign OH1HSN.

US $29.99 CAN $34.99
ISBN: 978-1-4493-3431-4

Make:
makezine.com

3
Make: Encyclopedia of Electronic Components
Platt & Jansson

Make:

VOL. 3

Charles Platt and Fredrik Jansson

Encyclopedia of Electronic Components

Sensors

Location ▪ Presence ▪ Proximity ▪ Orientation ▪ Oscillation ▪ Force ▪ Load ▪ Human Input ▪ Liquid and Gas Properties ▪ Light ▪ Heat ▪ Sound ▪ Electricity

Encyclopedia of Electronic Components Volume 3

Charles Platt and Fredrik Jansson

MAKER MEDIA™
SAN FRANCISCO, CA

Encyclopedia of Electronic Components, Volume 3
by Charles Platt

Copyright © 2016 Charles Platt. All rights reserved.

Printed in Canada.

Published by Maker Media, Inc., 1160 Battery Street East, Suite 125, San Francisco, CA 94111.

Maker Media books may be purchased for educational, business, or sales promotional use. Online editions are also available for most titles (*http://safaribooksonline.com*). For more information, contact O'Reilly Media's institutional sales department: 800-998-9938 or *corporate@oreilly.com*.

Editor: Brian Jepson
Production Editor: Melanie Yarbrough
Copyeditor: Christina Edwards
Proofreader: Charles Roumeliotis
Indexer: Charles Platt
Interior Designer: David Futato
Cover Designer: Karen Montgomery
Illustrator: Charles Platt

April 2016: First Edition

Revision History for the First Edition
2016-04-05: First Release

See *http://oreilly.com/catalog/errata.csp?isbn=9781449334314* for release details.

Make:, Maker Shed, and Maker Faire are registered trademarks of Maker Media, Inc. The Maker Media logo is a trademark of Maker Media, Inc. *Encyclopedia of Electronic Components, Volume 3* and related trade dress are trademarks of Maker Media, Inc.

Many of the designations used by manufacturers and sellers to distinguish their products are claimed as trademarks. Where those designations appear in this book, and Maker Media, Inc. was aware of a trademark claim, the designations have been printed in caps or initial caps.

While every precaution has been taken in the preparation of this book, the publisher and authors assume no responsibility for errors or omissions, or for damages resulting from the use of the information contained herein.

978-1-449-33431-4

[TI]

To Brian Jepson

Table of Contents

Preface .... **xix**

1. **GPS** **1**
   - What It Does 1
     - Schematic Symbol 1
     - GPS Segments 1
   - How It Works 2
   - Variants 2
   - Values 3
   - How to Use It 3
     - Pulse per Second Output 4
   - What Can Go Wrong 4
     - Electrostatic Discharge 4
     - Failure to Ground Properly 4
     - Cold Joints 4
     - Restricted Availability 4
     - Inability to Detect Satellites 4
     - Exceeding Maximum Velocity or Altitude 4

2. **magnetometer** **5**
   - What It Does 5
     - Schematic Symbol 5
     - IMU 5
     - Applications 6
   - How It Works 6
     - Magnetic Fields 6
     - Earth’s Axes 7
     - Coil Magnetometer 8
     - Hall Effect and Magnetoresistance 8
   - Variants 9

How to Use It . . . 9
What Can Go Wrong . . . 9
  Bias . . . 9
  Mounting Errors . . . 10

3. object presence sensor . . . 11

What It Does . . . 11
  Schematic Symbol . . . 12
Variants . . . 12
Optical Detection . . . 12
  Transmissive Optical Sensors . . . 13
  Retroreflective Optical Sensors . . . 15
Magnetic Sensors . . . 16
Reed Switch . . . 17
  Reed Switch Variants . . . 17
  Reed Switch Values . . . 18
  How to Use a Reed Switch . . . 18
Hall-Effect Sensor . . . 18
  How a Hall-Effect Sensor Works . . . 19
  Hall-Effect Sensor Variants . . . 19
  Other Applications . . . 20
Values . . . 20
How to Use a Hall-Effect Sensor . . . 20
Configuration of Object Presence Sensors . . . 21
  Linear Motion . . . 21
  Sensing by Interruption . . . 21
  Angular Motion . . . 21
Sensor Comparisons . . . 22
  Advantages of Optical Presence Sensors . . . 22
  Disadvantages of Optical Presence Sensors . . . 22
  Advantages of a Reed Switch . . . 22
  Disadvantages of a Reed Switch . . . 22
  Advantages of a Hall Effect Sensor . . . 22
What Can Go Wrong . . . 23
  Optical Sensor Issues . . . 23
  Reed Switch Issues . . . 23

4. passive infrared sensor . . . 25

What It Does . . . 25
  Schematic Symbols . . . 25
  Applications . . . 25
How It Works . . . 26
  Pyroelectric Detector . . . 26
  Elements . . . 26
  Lenses . . . 27
Variants . . . 29

What Can Go Wrong . . . 30
  Temperature Sensitivity . . . 30
  Detector Window Vulnerability . . . 30
  Moisture Vulnerability . . . 30

5. **proximity sensor . . . 31**
What It Does . . . 31
  Schematic Symbols . . . 31
  Applications . . . 32
Variants . . . 32
  Ultrasound . . . 32
  Infrared . . . 32
  Relative Advantages . . . 33
Ultrasonic Examples . . . 33
  Imports . . . 33
  Individual Elements . . . 34
Infrared Examples . . . 34
  Trends in Infrared Proximity Sensing . . . 35
Capacitive Displacement Sensor . . . 36
  Applications . . . 37
How It Works . . . 37
  Sources of Error . . . 37
  Values . . . 38
What Can Go Wrong with Optical and Ultrasound Proximity Sensors . . . 38
  Object Too Close . . . 38
  Multiple Signals . . . 38
  Inappropriate Surfaces . . . 38
  Environmental Factors . . . 38
  Deterioration of LEDs . . . 38

6. **linear position sensor . . . 39**
What It Does . . . 39
  Applications . . . 39
  Schematic Symbol . . . 39
How It Works . . . 39
  Linear Potentiometer . . . 40
  Magnetic Linear Encoders . . . 41
  Optical Linear Encoders . . . 41
  Linear Encoder Applications . . . 42
  Linear Variable Differential Transformers . . . 42
What Can Go Wrong . . . 43
  Mechanical Issues . . . 43
  LED Longevity . . . 43

7. **rotary position sensor . . . 45**
What It Does . . . 45

Applications 45
Schematic Symbol 46
Potentiometers 46
Arc-Segment Rotary Potentiometer 46
End Stops 46
Multiturn Rotary Potentiometer 46
Magnetic Rotary Position Sensor 47
Rotary Position Sensing Chips 48
Rotary Encoders 48
Optical Rotary Encoders 48
Optical Products 49
Computer Mouse Principles 50
Rotational Speed 50
Absolute Position 51
The Gray Code 51
Magnetic Rotary Encoders 52
How to Use It 53
What Can Go Wrong 53
Wiring Errors 53
Coding Errors 53
Ambiguous Terminology 54

8. tilt sensor 55
What It Does 55
Schematic Symbol 56
How It Works 56
Simplified Version 57
Applications 57
Variants 58
Mercury Switches 58
Pendulum Switch 58
Magnetization 59
Tilt Sensors 59
Two-Axis Tilt Sensors 59
Values 60
How to Use It 61
What Can Go Wrong 61
Contact Erosion 61
Random Signals 61
Environmental Hazard 61
Requirement for Gravity 61
Requirement for Stability 62

9. gyroscope 63
What It Does 63
Schematic Symbol 63

    IMU . . . 63
    Applications . . . 63
  How It Works . . . 64
    Vibrating Gyroscope . . . 64
  Variants . . . 66
    IMUs . . . 66
  Values . . . 67
  How to Use It . . . 67
  What Can Go Wrong . . . 67
    Temperature Drift . . . 67
    Mechanical Stress . . . 68
    Vibration . . . 68
    Placement . . . 68

10. **accelerometer** . . . **69**
  What It Does . . . 69
    IMU . . . 69
    Schematic Symbols . . . 70
    Applications . . . 70
  How It Works . . . 70
    Gravity and Free Fall . . . 71
    Rotation . . . 71
    Calculation . . . 72
  Variants . . . 72
  Values . . . 73
  What Can Go Wrong . . . 74
    Mechanical Stress . . . 74
    Other Problems . . . 74

11. **vibration sensor** . . . **75**
  What It Does . . . 75
    Schematic Symbols . . . 75
  Variants . . . 75
    Pin-and-Spring . . . 76
    Piezoelectric Strip . . . 76
    Chip-Based Piezoelectric . . . 77
    “Mousetrap” Type . . . 77
    Magnetic . . . 77
    Mercury . . . 78
  Values . . . 78
    Primary Variables . . . 78
    Dynamic Attributes . . . 79
  How to Use It . . . 79
  What Can Go Wrong . . . 79
    Long Cable Runs . . . 79
    Interference . . . 79

Correct Grounding 80
Fatigue Failure 80

12. **force sensor** **81**
What It Does 81
  Applications 81
  Schematic Symbol 82
How It Works 82
  Strain Gauge 82
  Wheatstone Bridge Circuits 83
  Wheatstone Bridge Errors 84
  Strain-Gauge Amplification 84
  Other Strain-Gauge Modules 85
  Plastic-Film Force Sensors 85
How to Use It 86
Values 87
  Film-Based Force Sensors for User Input 87
  Specifications for Film-Based Force Sensors 87
  Strain Gauges 88
What Can Go Wrong 88
  Soldering Damage 88
  Bad Load Distribution 88
  Water Damage 88
  Temperature Sensitivity 88
  Leads Too Long 88

13. **single touch sensor** **89**
What It Does 89
  Applications 90
  Schematic Symbols 90
How It Works 90
How to Use It 91
  Obtaining Touch Pads 91
  Individual Touch Pad 91
  Wheels and Strips 92
  Design Considerations 92
What Can Go Wrong 93
  Insensitive to Gloves 93
  Stylus Issues 93
  Conductive Ink 93

14. **touch screen** **95**
What It Does 95
  Schematic Symbol 95
Variants 95
  Resistive Sensing 95

Capacitive Sensing . . . 96
Screens Available as Components . . . 97

15. **liquid level sensor . . . 99**
What It Does . . . 99
Schematic Symbols . . . 99
Applications . . . 99
How It Works . . . 100
Binary-Output Float Sensor . . . 100
Analog-Output Float Sensor . . . 101
Incremental-Output Float Sensor . . . 101
Displacement Level Sensors . . . 102
Ultrasonic Level Sensors . . . 102
Reservoir Weight . . . 103
Pressure Sensing . . . 103
What Can Go Wrong . . . 104
Turbulence . . . 104
Tilting . . . 104

16. **liquid flow rate sensor . . . 105**
What It Does . . . 105
Schematic Symbols . . . 105
Paddlewheel Liquid Flow Rate Sensors . . . 105
Turbine Flow Rate Sensors . . . 106
Limitations of Paddlewheels and Turbines . . . 107
Thermal Mass Liquid Flow Rate Sensor . . . 107
Sliding Sleeve Liquid Flow Switch . . . 108
Sliding Plunger Liquid Flow Switch . . . 108
Ultrasonic Liquid Flow Rate Sensor . . . 108
Magnetic Liquid Flow Sensor . . . 108
Differential Pressure Liquid Flow Meter . . . 109
What Can Go Wrong . . . 109
Vulnerability to Dirt and Corrosive Materials . . . 109

17. **gas/liquid pressure sensor . . . 111**
What It Does . . . 111
Schematic Symbols . . . 111
Applications . . . 111
Design Considerations . . . 112
Units . . . 112
How It Works . . . 112
Basic Sensing Elements . . . 112
Relative Measurement . . . 113
Variants . . . 114
Ambient Air Pressure . . . 114
Altitude . . . 114

Gas Pressure 115
What Can Go Wrong 116
Vulnerability to Dirt, Moisture, and Corrosive Materials 116
Light Sensitivity 116

18. **gas concentration sensor 117**
What It Does 117
Schematic Symbol 117
Semiconductor Gas Sensors 117
Oxygen Sensors 119
Humidity Sensors 119
Dew-Point Sensor 120
Absolute Humidity Sensors 120
Relative Humidity Sensors 120
Humidity Sensor Output 121
Analog Humidity Sensor 121
Design Considerations 122
Digital Humidity Sensor 122
What Can Go Wrong 122
Contamination 122
Recalibration 123
Soldering 123

19. **gas flow rate sensor 125**
What It Does 125
Applications 125
Schematic Symbol 125
How It Works 126
Anemometer 126
Mass Flow Rate Sensing 127
Applications 128
Units 128
Measuring Higher Volumes 128
Output 128
What Can Go Wrong 129

20. **photoresistor 131**
What It Does 131
Schematic Symbol 131
How It Works 132
Construction 132
Variants 132
Photoresistors in Optical Isolators 132
Values 133
Comparisons with a Phototransistor 133
How to Use It 133

  Choosing a Series Resistor 134
What Can Go Wrong 134
  Overload 134
  Excessive Voltage 134
  Confusion Among Components 134

21. photodiode 135
What It Does 135
  Schematic Symbols 135
  Applications 135
How It Works 135
Variants 136
  PIN Photodiodes 136
  Avalanche Diodes 136
  Packages 136
  Wavelength Range 137
  Photodiode Arrays 137
  Output Options 137
  Specific Variants 137
Values 138
How to Use It 139
What Can Go Wrong 140

22. phototransistor 141
What It Does 141
  Schematic Symbols 141
  Applications 142
How It Works 142
Variants 142
  Optional Base Connection 142
  Photodarlington 142
  PhotoFET 142
Values 143
  Behavior Compared to Other Light Sensors 143
  Binning 144
How to Use It 144
  Output Calculation 145
What Can Go Wrong 145
  Visual Classification Errors 145
  Output Out of Range 145

23. NTC thermistor 147
What It Does 147
  Schematic Symbols 147
  Applications 148
How an NTC Thermistor Works 148

Output Conversion for Temperature Sensing 149
Choosing a Series Resistor 149
Wheatstone Bridge Circuit 150
Deriving the Temperature Value 150
Inrush Current Limiter 150
Restart 151
Thermistor Values 152
Time and Temperature 152
Resistance and Response 152
Kilohms and Kelvin 152
Reference Temperature 152
Reference Resistance 152
Dissipation Constant 152
Temperature Coefficient 152
Thermal Time Constant 152
Tolerance 153
Temperature Range 153
Switching Current 153
Power Limitations 153
Interchangeability 153
What Can Go Wrong 153
Self-Heating 153
Heat Dissipation 153
Lack of Heat 153
Addendum: Comparison of Temperature Sensors 153
NTC Thermistor 154
PTC Thermistor 154
Thermocouple 154
Resistance Temperature Detector 154
Semiconductor Temperature Sensor 155

24. PTC thermistor 157
What It Does 157
Schematic Symbols 157
PTC Overview 158
Silistor for Temperature Measurement 158
RTDs 159
Nonlinear PTC Thermistors 159
Over-Temperature Protection 159
Over-Current Protection 160
PTC Inrush Current Limiting 161
PTC Thermistor for Lighting Ballast 162
PTC Thermistor as a Heating Element 162
What Can Go Wrong 163
Self-Heating 163
Heating Other Components 163

25. thermocouple **165**
- What It Does 165
  - Schematic Symbol 166
- Thermocouple Applications 166
- How a Thermocouple Works 167
  - Thermocouple Details 168
- How to Use It 168
  - Types of Thermocouples 169
  - Seebeck Coefficients 169
  - Chips for Output Conversion 170
- Thermopile 171
- What Can Go Wrong 171
  - Polarity 171
  - Electrical Interference 171
  - Metal Fatigue and Oxidation 171
  - Using the Wrong Type 171
  - Heat Damage from Creating a Thermocouple 172

26. RTD (resistance temperature detector) **173**
- What It Does 173
- RTD Attributes 173
  - Schematic Symbol 174
  - Applications 174
- How It Works 174
- Variants 175
  - Wiring 175
  - RTD Probe 176
  - Signal Conditioning 176
- What Can Go Wrong 176
  - Self-Heating 176
  - Insulation Affected by Heat 176
  - Incompatible Sensing Element 176

27. semiconductor temperature sensor **177**
- What It Does 177
  - Semiconductor Temperature Sensor Applications 178
  - Schematic Symbol 178
  - Attributes 178
- How It Works 179
  - CMOS Sensors 179
  - Multiple Transistors 179
  - PTAT and the Brokaw Cell 180
- Variants 180
  - Analog Voltage Output 181
  - Analog Current Output 182
  - Digital Output 183

CMOS Semiconductor Temperature Sensors 185
What Can Go Wrong 185
    Different Temperature Scales 185
    Interference in Cable Runs 185
    Latency 186
    Processing Time 186

28. **infrared temperature sensor 187**
What It Does 187
    Applications 188
    Schematic Symbol 188
How It Works 188
    Thermopile 189
    Temperature Measurement 190
Variants 190
    Surface-Mount Specifications 191
    Sensor Arrays 191
Values 191
    Temperature Range 191
    Field of View 192
What Can Go Wrong 192
    Inappropriate Field of View 192
    Reflective Objects 192
    Glass Obstruction 192
    Multiple Heat Sources 192
    Thermal Gradients 192

29. **microphone 193**
What It Does 193
    Schematic Symbol 193
How It Works 194
    Carbon Microphone 194
    Moving-Coil Microphone 194
    Condenser Microphone 194
    Electret Microphone 195
    MEMS Microphone 195
    Piezoelectric Microphone 196
Values 196
    Sensitivity 196
    Directionality 197
    Frequency Response 197
    Impedance 198
    Total Harmonic Distortion 198
    Signal-to-Noise Ratio 198
What Can Go Wrong 198
    Cable Sensitivity 198

Noisy Power Supply 198

30. **current sensor** **199**
What It Does 199
  Applications 199
Ammeter 199
  Schematic Symbol 200
  Ammeter Wiring 200
Series Resistor 200
  Current-Sense Resistors 201
  Voltage Measurement 202
Hall-Effect Current Sensing 202
What Can Go Wrong 203
  Confusing AC with DC 203
  Magnetic Interference 203
  Incorrect Meter Wiring 203
  Current Out of Range 203

31. **voltage sensor** **205**
What It Does 205
  Applications 205
Volt Meter 205
  Schematic Symbol 206
  Volt Meter Wiring 206
How It Works 206
  Load-Related Inaccuracy 207
  Bar Graph 207
What Can Go Wrong 208
  Confusing AC with DC 208
  High Circuit Impedance 208
  Voltage Out of Range 208
  Voltage Relative to Ground 208

Appendix A. **Sensor Output** **209**

Glossary **217**

Index **221**

Preface

This third and final volume of the *Encyclopedia of Electronic Components* is devoted entirely to sensors.

Two factors have caused very significant changes in the field of sensors since the 1980s. First, features such as antilock braking, airbags, and emissions controls stimulated the development of low-priced sensors for automotive applications. Many of these sensors were fabricated in silicon as MEMS (microelectromechanical) devices.

The second wave began in 2007 when MEMS sensors were installed in the iPhone. A modern phone may contain almost a dozen different types of sensors, and their size and price have been driven down to a point that would have been unimaginable 20 years previously.

Many MEMS sensors are now as cheap as basic semiconductor components such as a voltage regulator or a logic chip, and they are easy to use in conjunction with microcontrollers. In this Encyclopedia, we have allocated significant space to this segment of the market, hoping that the specific products that we have chosen will remain popular and available for at least the next decade.

In addition, we have devoted space to older components where durability has been proven.

Purpose

While much of the information in this volume can be found dispersed among datasheets, introductory texts, Internet sites, and technical briefings published by manufacturers, we believe there is a real need for a durable resource that assembles all the relevant data in one place, properly organized and verified, including details that may be hard to find elsewhere.

This volume may also serve a useful purpose by attempting to categorize and classify components in a field that is remarkably chaotic. For example, is an *object presence sensor* different from a *proximity sensor*? Some manufacturers seem to think so; others disagree. Understanding the distinctions and the underlying principles can be important if you are trying to decide which sensor to use.

Sensor terminology can also be confusing. To take another example, what is the difference between a *reflective interrupter*, a *reflective object sensor*, a *reflective optical sensor*, a *reflective photointerrupter*, and an *opt-pass sensor*? These terms are used in various datasheets to describe components that are all *retroreflective sensors*. Understanding the proliferating variety of terminology can be essential if you simply want to find something in a product index.

Organization

As in volumes 1 and 2, this volume is organized by subject. For example, if you want to measure temperature, you'll find the entries for a thermistor and a thermocouple next to each other, in an entire section devoted to the sensing of heat. This will help you to compare capabilities and choose the component that best suits your application.

The subject path leading to each sensor is shown at the top of the first page of each entry. For gas flow rate, for instance, you would follow this path:

```
fluid > gas > flow rate
```

Note that the word "fluid" is properly used to include gases as well as liquids.

Exceptions and Conflicts

Unfortunately, some sensors are not easily categorized. There are four problems in this area.

1. What Does a Sensor Really Sense?

A GPS chip is a radio receiver, picking up transmissions from satellites. Does this mean it should be categorized as a sensor of radio waves? No, its purpose is to tell you your location. Therefore, it is categorized as a location sensor. This leads to the first general rule: sensors are categorized by their primary purpose. Secondary purposes may be found in the index.

2. How Many Sensors Are in a Sensor?

Many surface-mount chips perform more than one sensing function. For example, an inertial measurement unit (often identified by its acronym, *IMU*) can contain three gyroscope sensors and three accelerometers—and may contain three magnetometers, too. How should it be categorized?

The answer is that an IMU will be mentioned in more than one entry in the Encyclopedia, because it performs more than one function; but it will not have its own separate entry, because each entry in the Encyclopedia is for a single primary sensing function.

The names of multisensor chips are, of course, included in the index.

3. How Many Stimuli Can One Sensor Sense?

A single sensing element may be used in multiple different types of sensors. The most notable example is the Hall-effect sensor, which can be found in magnetometers, object presence sensors, speed sensors, current sensors, and dozens more. Modern automobiles can contain Hall-effect sensors everywhere from the ignition system to the trunk-locking mechanism. If you are using a hard drive with rotating platters, it probably contains a Hall-effect sensor to monitor the speed of rotation. If you have a generic computer keyboard, each keypress is probably detected with a Hall-effect sensor.

Bearing this in mind, how should a Hall-effect sensor be classified? And where should you expect to find an explanation of how it works?

The answer is that where different types of components contain the same type of sensing element, the entry for each component will include a cross-reference to one location where the sensing element is explained in detail.

This location will be chosen for its relevance. Thus, Hall-effect sensors are explained in the entry for **object presence** sensors, because this is their primary function. While it is true that a Hall-effect sensor works by detecting a magnetic field, that is not its most common application.

4. Too Many Sensors!

Wikipedia lists more than 100 general types of sensors, and even that list is probably not complete. Consequently, we had to pick and choose. Some of the decisions may seem arbitrary, but all of them were made on the grounds of practicality. There were three principles for deciding what to include and what to leave out.

1. Is it a component? We are more interested in board-mounted components than in packaged products that happen to contain sensors. For instance, a thermocouple is often enclosed in a tubular steel probe, and its wire is often plugged in to a specially designed meter that displays temperature. While we do include a photograph of a probe, we are primarily interested in the welded wires of the thermocouple inside it.
2. How much does it cost? An industrial ultrasonic sensor to check items on a factory conveyor belt will be sealed into a module with a waterproof grommet around a shielded cable—which is all very nice, but will not be very affordable. This Encyclopedia is more interested in board-mountable components for one-tenth of the price.
3. How many people are likely to want it? The stock of each type of sensor was checked on component vendor sites. If a sensor wasn't in the inventory, or if only a couple of variants were stocked, we concluded that the limited demand probably didn't justify including it here. For example, a Ferraris acceleration sensor responds to eddy currents in a rotating motor shaft, as a way of measuring vibration in the shaft. This is a really interesting device, but is unlikely to be on most people's shopping lists.

Volume Contents

Having explained the organization of this book and our decisions to include or omit various components, we now present a summary of the contents of all three Encyclopedia volumes:

Volume 1

Power; electromagnetic devices; discrete semiconductors.

The *power* category includes sources of electricity and methods to distribute, store, interrupt, convert, and regulate power. The *electromagnetism* category includes devices that exert force linearly, and others that create a turning force. *Discrete semiconductors* include the primary types of diodes and transistors. See Figure P-1 for a contents listing.

Primary Category	Secondary Category	Component Type
power	source	battery
	connection	jumper
		fuse
		pushbutton
		switch
		rotary switch
		rotational encoder
	moderation	relay
		resistor
		potentiometer
		capacitor
		variable capacitor
	conversion	inductor
		AC-AC transformer
		AC-DC power supply
		DC-DC converter
		DC-AC inverter
	regulation	voltage regulator
electromagnetism	linear output	electromagnet
		solenoid
	rotational output	DC motor
		AC motor
		servo motor
		stepper motor
discrete semiconductor	single junction	diode
		unijunction transistor
	multi-junction	bipolar transistor
		field-effect transistor

Figure P-1 *The subject-oriented organization of categories and entries in Volume 1 of this Encyclopedia.*

Volume 2

Thyristors (SCRs, diacs, and triacs); integrated circuits; light sources, indicators, and displays; and sound sources.

Integrated circuits are divided into analog and digital components. *Light sources, indicators, and displays* are divided into reflective displays, single sources of light, and displays that emit light. *Sound sources* are divided into those that create sound, and those that reproduce sound. A contents listing for Volume 2 appears in Figure P-2.

Volume 3

All the most common types of sensing devices, including those that detect location, presence, proximity, orientation, oscillation, force, load, human input, liquid properties, gas types and concentrations, pressure, flow rate, light, heat, sound, and electricity. A contents listing for Volume 3 appears in Figure P-3.

Method

Reference Versus Tutorial

As its title suggests, this is a reference book, not a tutorial. A tutorial such as *Make: Electronics* begins with elementary concepts and builds sequentially toward concepts that are more advanced. A reference book assumes that you may dip into the text at any point, learn what you need to know, and then put the book aside. If you choose to read it straight through from beginning to end, you will find some repetition, as each entry is intended to be self-sufficient, requiring minimal reference to other entries.

Theory and Practice

This book is oriented toward practicality rather than theory. We assume that the reader mostly wants to know how to use electronic components, rather than why they work the way they do. Consequently we do not include detailed proofs of formulae or definitions rooted in electrical theory.

Primary Category	Secondary Category	Component Type
discrete semi-conductor	thyristor	SCR
		diac
		triac
integrated circuit	analog	solid-state relay
		optocoupler
		comparator
		op-amp
		digital potentiometer
		timer
	digital	logic gate
		flip-flop
		shift register
		counter
		encoder
		decoder
		multiplexer
light source, indicator or display	reflective	LCD
	single source	incandescent lamp
		neon bulb
		fluorescent light
		laser
		LED indicator
		LED area lighting
	multi-source or panel	LED display
		vacuum-fluorescent
		electroluminescence
sound source	audio alert	transducer
		audio indicator
	reproducer	headphone
		speaker

Figure P-2 *The subject-oriented organization of categories and entries in Volume 2.*

Primary Category	Attribute to be Sensed	Type of Sensor
spatial	location	GPS
		magnetometer
	presence	object presence
		passive infrared
	distance	object proximity
		linear position
	orientation	rotary position
		tilt
		gyroscope
		accelerometer
mechanical	oscillation	vibration
	force	force
	human input	single touch
		touch screen
fluid	liquid	liquid level
		liquid flow rate
	gas/liquid	pressure
	gas	gas concentration
		gas flow rate
radiation	light	photoresistor
		photodiode
		phototransistor
	heat	NTC thermistor
		PTC thermistor
		thermocouple
		RTD
		semiconductor
		infrared temperature
	sound	microphone
electricity	metering	current
		voltage

Figure P-3 *The subject-oriented organization of categories and entries in Volume 3.*

Sensor Output

In Volumes 1 and 2 of the *Encyclopedia*, each entry included hints on how to use a component. However, many sensors have identical forms of output, which are processed in a similar way. To avoid repetition, general guidance for using nine principal types of sensor outputs has been placed in Appendix A at the back of this volume.

For example, many sensors provide an analog voltage output that varies with the phenomenon that is being sensed. In Appendix A, you will find suggestions on how to adjust the range of the output, if necessary, or how to digitize it with an analog-to-digital converter.

You will also find a comparison between serial protocols such as I2C and SPI, both of which are commonly used when a microcontroller communicates with a digital sensor via a bus.

Glossary

In the world of sensors, many terms tend to recur. *Hysteresis* is one; *MEMS* is another. Rather than define these terms repeatedly, some quick definitions are gathered in a Glossary. Please remember the existence of the glossary if you encounter a term that is unfamiliar. See Glossary.

In many instances, terms that are italicized in the text are defined in the glossary.

Typographical Conventions

Within each entry, **bold type** is used for the first occurrence in each entry of the name of a component that has its own entry elsewhere. Other important electronics terms or component names may be presented in *italics*.

The names of components, and the categories to which they belong, are all set in lowercase type, except where a term is normally capitalized because it is an acronym or a trademark, or contains a proper noun. The term *Hall effect*, for instance, has an initial cap because it is named after a person named Hall. The term *GPS* is all in caps, because it is an acronym; but *psi* (meaning pounds per square inch) remains in lowercase, because even though it is an acronym, the lowercase form is more common.

The situation is different when specifying units that are named after electrical pioneers. All of these units should be lowercased when spelled out. Thus, when referring to the SI unit of force, it is “the newton.” However, where a unit named after a person is abbreviated, the abbreviation is capitalized, as in N for newtons, Hz for hertz, Pa for pascals, and A for amperes.

Mathematical Syntax

In mathematical formulae, we have used the style that is common in programming languages. The * (asterisk) is used as a multiplication symbol, while the / (forward slash) is used as a division symbol. Where some terms are in parentheses, they must be dealt with first. Where parentheses are inside parentheses, the innermost ones must be dealt with first. Consider this example:

```
A = 30 / (7 + (4 * 2) )
```

You would begin by multiplying 4 times 2, to get 8; then add 7, to get 15; then divide that into 30, to get the value for A, which is 2.

Visual Conventions

Figure P-4 shows the conventions that are used in the schematics in this book. A black dot always indicates a connection, except that to minimize ambiguity, the configuration at top-right is avoided, and the configuration at top-center is used instead. Conductors that cross each other without a black dot do not make a connection. The styles at bottom right are sometimes seen elsewhere, but are not used here.

All the schematics are formatted with pale blue backgrounds. This enables components such as switches, transistors, and LEDs to be highlighted in white, drawing attention to them and clarifying the boundary of the component. The white areas have no other meaning.


To show there is a connection
This style is used
This style is not used
To show there is no connection
This style is used
These styles are not used

Figure P-4 *Visual conventions that are used in the schematics in this book.*

Units and Backgrounds

So long as the United States clings stubbornly to the habit of expressing dimensions in inches, there is a good argument to follow this custom in books intended for an American audience. With this in mind, Volumes 1 and 2 mostly avoided metric units of length. However, as time passed, the books were translated for use in many parts of the world where the inch is regarded as an anachronism.

Recognizing that we now have an international audience, we have used the metric system throughout this volume (with very few exceptions, such as a photograph of an American plumbing fixture that is designed to fit 3/4” pipe). For readers who are metrically impaired, here are some units of length, and their abbreviations:

- 1 nanometer (nm)
- 1 micrometer (µm) = 1,000nm
- 1 millimeter (mm) = 1,000µm
- 1 centimeter (cm) = 10mm
- 1 meter (m) = 100cm = 1,000mm

A micrometer is also known as a *micron*.

The basic conversion factor from meters to inches is 0.0254. Thus:

- 1 inch = 2.54cm = 25.4mm
- 1/1000 inch = 25.4µm

Sometimes 1/1000 inch is called a *mil*.

In many of the component photographs, a graph-paper background is included. Each square in these backgrounds is 1mm.

To avoid confusion, please remember that a few of these same component photographs appeared in books such as *Make: More Electronics*, where the background grid was in tenths of an inch. Captions to photographs in this volume will remind you that millimeters are now used.

Background colors in the photographs were chosen for contrast with the colors of the components, or for visual variety. They have no other significance.

Component Availability

The world of sensors is changing rapidly, and we have no way of knowing if a component will enjoy a long production run. We recommend checking availability at the following suppliers, which we used frequently during the preparation of the book:

- *http://www.mouser.com*
- *http://www.jameco.com*
- *http://www.sparkfun.com*
- *http://www.adafruit.com*

For obsolete parts, or those that are nearing the end of their commercial life, eBay can be very useful. Alternatively, new substitutions for old parts are often listed at *http://www.mouser.com*.

Issues and Errata

There are three situations where the reader and the writer may want to communicate with each other.

- We may want to tell you if the book contains a mistake of some significance. This is *us-informing-you* feedback.
- You may want to tell us if you think you found an error in the book. This is *you-informing-us* feedback.
- You may be having trouble making something work, and you don't know whether we made a mistake or you made a mistake. You would like some help. This is *you-asking-us* feedback.

Here's how you can deal with each of these situations.

Us Informing You

If you already registered your contact information in connection with *Make: Electronics* (second edition) or *Make: More Electronics*, you don't need to register again for updates relating to the Encyclopedia. If you have not already registered, here's how it works.

The only way you can be notified if there's an error in the book is if you supply your contact information. If we have your email address:

- You will be notified of any significant errors that are found in this book, and you will receive a correction.
- You will be notified if there is a completely new edition of this book, or of *Make: Electronics*, or any other books by Charles Platt. These notifications will be very rare.

Your contact information will not be used for any other purpose.

Simply send a blank email (or include some comments in it, if you like) to:

make.electronics@gmail.com

Please put REGISTER in the subject line.

You Informing Us

If you only want to report an error that you have found, it's really better to use the "errata" system maintained by our publisher. The publisher uses the "errata" information to fix the error in updates of the book.

If you feel sure that you found an error, please visit:

http://bit.ly/encyclopedia_electronic_components_v3

The web page will tell you how to submit errata.

You Asking Us

Our time is obviously limited, but if you have a question, a quick answer may be available. You can send email to *make.electronics@gmail.com* for this purpose. Please put the word HELP in the subject line.

Going Public

There are dozens of forums online where you can discuss this book and mention any problems you are having, but please be aware of the power that you have as a reader, and use it fairly. A single negative review can create a bigger effect than you may realize. It can certainly outweigh half-a-dozen positive reviews.

Responses in the past have been generally positive, but in a couple of cases people have been annoyed over small issues such as being unable to find a part online. Help is available on this kind of topic, if you need it. All you have to do is send a request to *make.electronics@gmail.com*.

Safari® Books Online

Safari Books Online is an on-demand digital library that delivers expert content in both book and video form from the world's leading authors in technology and business.

Technology professionals, software developers, web designers, and business and creative professionals use Safari Books Online as their primary resource for research, problem solving, learning, and certification training.

Safari Books Online offers a range of plans and pricing for enterprise, government, education, and individuals.

Members have access to thousands of books, training videos, and prepublication manuscripts in one fully searchable database from publishers like O'Reilly Media, Prentice Hall Professional, Addison-Wesley Professional, Microsoft Press, Sams, Que, Peachpit Press, Focal Press, Cisco Press, John Wiley & Sons, Syngress, Morgan Kaufmann, IBM Redbooks, Packt, Adobe Press, FT Press, Apress, Manning, New Riders, McGraw-Hill, Jones & Bartlett, Course Technology, and hundreds more. For more information about Safari Books Online, please visit us online.

You can access the errata page at *http://bit.ly/encyclopedia-electronic-components-v3*.

Make: unites, inspires, informs, and entertains a growing community of resourceful people who undertake amazing projects in their backyards, basements, and garages. Make: celebrates your right to tweak, hack, and bend any technology to your will. The Make: audience continues to be a growing culture and community that believes in bettering ourselves, our environment, our educational system—our entire world. This is much more than an audience, it's a worldwide movement that Make is leading. We call it the Maker Movement.

For more information about Make:, visit us online:

Make: magazine: *http://makezine.com/magazine*
Maker Faire: *http://makerfaire.com*
Makezine.com: *http://makezine.com*
Maker Shed: *http://makershed.com*

To comment or ask technical questions about this book, send email to:

bookquestions@oreilly.com.

Acknowledgments

Datasheets and tutorials maintained by component manufacturers were considered the most trustworthy sources of information online. In addition, component retailers, college texts, crowd-sourced reference works, and hobbyist sites were used. The following books provided useful information:

Boylestad, Robert L. and Nashelsky, Louis: *Electronic Devices and Circuit Theory*, 9th edition. Pearson Education, 2006.

Braga, Newton C.: *CMOS Sourcebook*. Sams Technical Publishing, 2001.

Hoenig, Stuart A.: *How to Build and Use Electronic Devices Without Frustration, Panic, Mountains of Money, or an Engineering Degree*, 2nd edition. Little, Brown, 1980.

Horn, Delton T.: *Electronic Components*. Tab Books, 1992.

Horn, Delton T.: *Electronics Theory*, 4th edition. Tab Books, 1994.

Horowitz, Paul and Hill, Winfield: *The Art of Electronics*, 2nd edition. Cambridge University Press, 1989.

Ibrahim, Dogan: *Using LEDs, LCDs, and GLCDs in Microcontroller Projects*. John Wiley & Sons, 2012.

Kumar, A. Anand: *Fundamentals of Digital Circuits*, 2nd edition. PHI Learning, 2009.

Lancaster, Don: *TTL Cookbook*. Howard W. Sams & Co, 1974.

Lenk, Ron and Lenk, Carol: *Practical Lighting Design with LEDs*. John Wiley & Sons, 2011.

Lowe, Doug: *Electronics All-in-One for Dummies*. John Wiley & Sons, 2012.

Mims III, Forrest M.: *Getting Started in Electronics*. Master Publishing, 2000.

Mims III, Forrest M.: *Electronic Sensor Circuits & Projects*. Master Publishing, 2007.

Mims III, Forrest M.: *Timer, Op Amp, & Optelectronic Circuits and Projects*. Master Publishing, 2007.

Predko, Mike: *123 Robotics Experiments for the Evil Genius*. McGraw-Hill, 2004.

Scherz, Paul: *Practical Electronics for Inventors*, 2nd edition. McGraw-Hill, 2007.

Williams, Tim: *The Circuit Designer's Companion*, 2nd edition. Newnes, 2005.

In addition, three individuals provided special assistance. Our editor, Brian Jepson, was immensely helpful in the development of this book. Philipp Marek reviewed the text for errors, and Erico Narita collaborated on the Photoshop work.

GPS

1

The acronym **GPS** properly refers to the entire Global Positioning System, including satellites and ground-based control installations. However, a *GPS sensor* consists of a surface-mount chip that processes signals from GPS satellites using a small rectangular antenna, often mounted on top of a *GPS chip*.

A *GPS module* is usually a small board on which a GPS sensor is mounted with additional components. A *GPS receiver* is a device including a data display and other features, such as memory, in addition to a GPS module. In casual colloquial usage, someone who refers to "a GPS" usually means a GPS receiver.

GPS is almost always capitalized without periods.

OTHER RELATED COMPONENTS

- **magnetometer** (see Chapter 2)

What It Does

The Global Positioning System is a navigational aid jointly funded by the U.S. Department of Defense and the U.S. Department of Transportation, while being maintained by the U.S. Air Force. Signals from GPS satellites can be received and processed by modules in a wide variety of equipment ranging from aircraft to wristwatches. The signals provide location data, and may also be used as an accurate time reference.

Schematic Symbol

There is no specific schematic symbol for a GPS chip. It is likely to be shown as a box containing abbreviations that define pin functions, similar to any integrated circuit chip.

GPS Segments

The Global Positioning System consists of three segments:

The space segment

This originally required 24 communications satellites, but was revised in 2011 to require 27, to provide better global coverage. As of August 2015, there were actually 31 satellites in service, with additional "spares" that can be activated if necessary. The satellites occupy orbits 12,500 miles above the Earth, allowing each of them to circle the planet twice in 24 hours. Specifications are maintained online.

The control segment

This includes a master ground-based control station, an alternate master control station, 12 command and control antennas, and 16 monitoring sites, all maintained by the U.S. Air Force.

The user segment
This consists of receiving devices, including those that are government-owned and those that are privately owned.

How It Works

Each satellite carries multiple atomic clocks that maintain precise time, and a pseudo-random number generator in the form of a linear-feedback **shift register** (see Volume 2).

A GPS receiver can distinguish the signals from at least four satellites by comparing their received pseudo-random bit sequences, and can compute the receiver's distance to each satellite by comparing the arrival times of satellite signals.

When a satellite appears above the horizon, it approaches a receiver. After passing overhead, it moves away. This relative motion causes a *Doppler shift* in the received frequency, which the receiver circuit must take into account.

GPS satellites transmit on several frequencies simultaneously. The one for civilian use is 1575.42 MHz, called L1. Another one, 1227.6 MHz, called L2, is reserved for military use.

Variants

A GPS chip generally processes input from an antenna and provides output through solder pads. The antenna is often integrated as a ceramic square or rectangle mounted above the chip, but many chips can also process input from an external antenna. Figure 1-1 shows a GPS chip with a metal shield that is easily mistaken for an antenna. In Figure 1-2, the GPS sensor does incorporate a ceramic antenna.

Some GPS chips contain flash memory for internal data logging, although this is not a standard feature.

Suppliers such as Adafruit and Sparkfun offer GPS modules mounted on breakout boards for easier connection with other components, as shown in Figure 1-2. Some breakout boards also include provision for battery backup with a button cell.



Figure 1-1 *A GPS sensor. This surface-mount chip is hidden beneath a metal shield.*



Figure 1-2 *A breakout board offered by Adafruit, incorporating a GPS sensor.*

GPS capability is almost always included in modern smartphones and tablets. It is used in handheld devices for navigation on foot, and in devices designed to be mounted in motor vehicles. Cars offer GPS capability as an option accessed via a built-in screen.

A *GPS tracker* is a device that may lack a display and simply logs its position to internal memory, from which data can be downloaded to a computer later. Many (older) handheld GPS receivers have a connector giving access to a serial or USB port, and provide data in the same NMEA format as the GPS modules described below.

After the Global Positioning System became widely used, other competing systems were introduced. These include the European Galileo, the Russian GLONASS (an acronym for Global Navigation Satellite System), and the Chinese Beidou. As of 2015, GLONASS had become fully operational. Some receivers, including those in cellular phones, compare signals from GPS and GLONASS satellites to achieve higher accuracy.

Values

Sensitivity is expressed usually in dBm, meaning the power ratio in decibels (dB) of the measured power referenced to one milliwatt (mW).

Time to First Fix (TTFF) is the time required to obtain an initial fix from a satellite.

Number of channels is the number of satellites that a GPS receiver can track simultaneously. Early GPS receivers could sense only four channels. Modern units may be able to deal with 22.

Power consumption may be measured in milliwatts. For example, the FGPMMOPA6H GPS standalone module by G.top claims power consumption of 82mW during acquisition of satellite signals and 66mW while tracking subsequently. At a typical voltage of 4VDC, the chipset consumes about 20mA and approximately 17mA, respectively.

Form factor. This is the size of a chip, often determined by the dimensions of the ceramic antenna on top of it. Dimensions may be 15mm x 15mm or larger.

Update rate. The number of position measurements per second. While 1 update per second is often sufficient, some chips generate updates more rapidly. The frequency of updates is expressed in hertz.

Output type. This is often TTL-level serial providing NMEA data. The baud rate can vary and is often selectable.

Supply voltage. Often below 5VDC.

Current consumption. Higher during satellite acquisition.

How to Use It

A GPS module requires only a DC power supply, and will start outputting data as soon as it has identified satellites that are currently within range.

Data provided by a GPS module uses a rather slow and primitive plain-ASCII protocol known as NMEA, developed by the National Marine Electronics Association. Each block of data is known as a *sentence*, and can be parsed independently of previous and subsequent sentences. The default transmission rate is 4,800 bits per second, using 8 bits to identify an ASCII character, no parity, and 1 stop bit. However, some GPS modules use a serial rate of 9,600 bps or faster.

A sentence begins with a two-letter abbreviation defining the type of device employing the sentence. For a GPS device, the abbreviation is GP. The sentence continues with another abbreviation of three characters or more, describing the type of data being transmitted, so that numeric values in the sentence can be interpreted correctly.

The remainder of a sentence consists of letters and numerals in plain ASCII, with values separated by commas. A sentence cannot contain more than 80 characters. A sentence will specify the latitude, longitude, and altitude of the GPS, and a value defining the time when the readings were derived from satellite signals. Some sentence data structures are proprietary, established by the device manufacturer, and will begin with the letter P.

A GPS device may send a variety of different sentence types in succession, to overcome the 80-character sentence length limit. Each sentence will be preceded with an identifier. Sentence types and data contents will be defined in a manufacturer's datasheet.

Output from GPS chips may be compatible with a microcontroller. Output from a GPS breakout board will almost certainly be compatible, and the board is likely to have its own voltage regulator. The microcontroller can receive serial data from the GPS chip, can stop the GPS chip via its enable pin, and can start and stop internal logging of data in flash memory on the GPS chip if this feature is available.

Code libraries are available online for a microcontroller, to enable it to receive and interpret serial data from a GPS device.

Pulse per Second Output

As the GPS positioning depends on calculating distances from the time it takes for a radio signal to travel, accurate timekeeping is needed. When a GPS receiver obtains a fix for its position, it will get a value for the current time as well. This makes GPS receivers usable to supply time and frequency standards. Most receiver modules report the time together with the position. Many also provide a special PPS output, which produces one pulse per second, precisely synchronized with the satellites in view.

The accurate time provided by the GPS receiver can be used to *discipline* a crystal oscillator. This means measuring the crystal oscillator frequency relative to a GPS-provided reference, and continuously adjusting the crystal frequency to keep it stable.

What Can Go Wrong

Problems generally affect chips and modules rather than devices.

Electrostatic Discharge

The patch antenna on a GPS chip connects with the chip via an RF input. If the antenna is subjected to an electrostatic discharge, the chip can be permanently damaged. Likewise, damage will result if a discharge is applied to the RF input, for example through a soldering iron. The chip must be grounded before any work is done involving the RF input.

Failure to Ground Properly

The ground solder pad on a chip, or the ground pin on a breakout board, must make contact before voltage is applied to other pads or pins.

Cold Joints

The patch antenna on a GPS chip can function as a heat sink, increasing the risk of cold solder joints when the chip is being mounted on a board.

Restricted Availability

U.S. regulations limit the export of some GPS devices capable of rapid positional updates that could be usable in military aircraft or missiles. Other restrictions also apply. Suppliers may be inconsistent in their refusal to allow purchase of restricted items outside of the United States.

Inability to Detect Satellites

Any GPS device may fail to detect satellite signals if its view of the sky is obstructed. Reception is usually possible through window glass, but may not be available through walls, a roof, heavy tree cover, and other natural obstructions.

Exceeding Maximum Velocity or Altitude

Security regulations limit the capability of GPS devices to function above 60,000 feet or at greater than 1,200 miles per hour. Outside of these limits, the GPS device will not provide data. This may affect applications in amateur rocketry or high-altitude balloons.

magnetometer

2

This entry deals only with magnetic sensors that respond to the Earth's magnetic field. Small magnetic sensors such as the ubiquitous *Hall sensor* may be used for many other purposes, such as determining the position or rotational speed of mechanical components. These applications involve **object presence** sensing; see Chapter 3. In that entry, Hall sensors are discussed at "Hall-Effect Sensor".

In the past, a **magnetometer** was a bulky measurement device incorporating knobs or other controls and some form of display. While that use of the word is still common, this entry deals only with chip-based magnetic sensors.

OTHER RELATED COMPONENTS

- **accelerometer** (see Chapter 10)
- **gyroscope** (see Chapter 9)
- **GPS** (see Chapter 1)

What It Does

A traditional compass consists of a thin magnetized strip of metal balanced on a pivot. It aligns itself with the Earth's magnetic field.

A *scalar magnetometer* measures the total strength of a magnetic field. A *vector magnetometer* can measure the strength in a specified direction. In particular, it can provide a numeric output describing the angle between the orientation of the measuring device and the Earth's magnetic poles.

Chip-based magnetometers are usually vector-type, containing three sensors mounted orthogonally—that is, each of them at 90 degrees to the other two. Suitable software can interpret the analog readings from the sensors to calculate magnetic north or south regardless of the angle at which the instrument is being held, relative to the ground.

Schematic Symbol

There is no specific schematic symbol for a magnetometer.

IMU

A **gyroscope** measures the rate of rotation of the enclosure in which it is mounted. This is properly known as the *angular velocity*. A gyroscope will also respond to changes in the rate of rotation. It does not measure linear motion or a static angle of orientation.

An **accelerometer** measures variations in linear motion and will also measure its own static orientation relative to the force of gravity. If an accelerometer rotates around its own axis, it will not measure angular velocity.

When an accelerometer and a gyroscope are contained in the same package, optionally with a magnetometer, they may be described as an *IMU* (inertial measurement unit), which can provide necessary data to maneuver aircraft, spacecraft, and watercraft, especially when **GPS** signals are unavailable.

Applications

Magnetometers are found in handheld equipment such as digital compasses, cameras, and cellular phones. They are usually surface-mount chips that are manufactured in large quantities and may be used in conjunction with microcontrollers. For the hobby-electronics community, or for experimental product development, a magnetometer may be mounted on a breakout board for ease of use. A board using a Honeywell HMC5883L is shown in Figure 2-1.



Figure 2-1 *The Honeywell HMC5883L 3-axis magnetometer mounted on a breakout board. The background grid is in millimeters.*

How It Works

An explanation of magnetometers requires an understanding of the fundamentals of magnetism.

Magnetic Fields

A magnetic field is often represented by *field lines* that show the strength and vector of the field. Field lines associated with a simple permanent magnet are shown in Figure 2-2, where the strength, or *flux density*, at any point, is indicated by the spacing the lines, while the angle tangential to a line indicates its vector. (For an extended discussion of magnetism, see **electromagnet** in Volume 1.)



Figure 2-2 *Field lines representing magnetic flux created by a bar magnet. Space between the field lines is inversely proportional to flux density. In reality this is a three-dimensional effect, and a more accurate representation would show the magnet and field lines revolved around the axis of the magnet.*

The flux density of a magnetic field is usually represented by the letter B, and is measured in *newton-meters per ampere*, more commonly referred to as *teslas* (T). An older unit of measurement was gauss (G), 1 tesla being equivalent to 10,000 gauss. Some datasheets still refer to gauss.

The Earth's magnetic field is believed to result from convection currents in the outer liquid of the Earth's core. The strength of this field varies from 25 to 65 microteslas (0.25 to 0.65 gauss) depending on the location where it is measured. To a very rough approximation, the Earth behaves as if a giant bar magnet connects the magnetic north pole and the magnetic south pole. See Figure 2-3.



Figure 2-3 *The magnetic field of the Earth approximately resembles the field around a bar magnet.*

Note that in northern and southern latitudes, the field lines angle steeply down toward the surface, while the lines are approximately parallel with the surface near the equator. Consequently a magnetometer held tangentially to the surface of the Earth will tend to measure a stronger horizontal field near the equator than near the poles.

The varying angle of the field lines tangential to the Earth is known as their *inclination*. Variations in field strength can be used to determine an approximate location, although the **GPS** (Global Positioning System, using satellites) enables this much more accurately.

Confusion results from the fact that the nothern magnetic pole of the Earth actually behaves as a south pole, while the southern magnetic pole behaves as a north pole. That is, when a permanent magnet is free to rotate, its north pole will orient itself toward the so-called northern magnetic pole of the Earth, even though opposite poles attract. The northern pole of the Earth should therefore be thought of as the pole that attracts the north end of a compass.

Earth's Axes

Planet Earth revolves around an imaginary line referred to as the *axis of rotation*. This line is close to, but not quite coincident with, the *magnetic axis* connecting the magnetic north pole and magnetic south pole, as shown in Figure 2-4.



Figure 2-4 *The angle between the magnetic axis and the rotational axis of the Earth is approximately 11 degrees.*

Magnetic declination is the angle between the magnetic north pole and the geographical north pole, as perceived by an observer. This angle will vary depending on the observer's location on the surface.

Because of declination, the direction of magnetic force at points on the surface of the planet will vary with latitude and longitude, as shown in Figure 2-5. In this figure, the *magnetic meridians* are shown in red, superimposed on the *geographical meridians* shown in green. Magnetic meridians show the direction of magnetic force, while geographic meridians are drawn between the ends of the axis of rotation of the Earth. While there is an approximate correlation between the two, in some areas, especially near the north and south poles, the discrepancy can be more than 40 degrees.



Figure 2-5 *The red lines indicate the direction in which a compass would be likely to point to magnetic north. The green lines connect the geographical poles of the planet. (From Wikimedia Commons.)*

Standard declination tables for locations on the Earth are available, and these values must be added to, or subtracted from, the reading from a compass or magnetometer to determine the direction of geographical north. Navigational systems customarily express the heading of a vehicle or vessel relative to geographical north, as shown in Figure 2-6.

Coil Magnetometer

Current flowing through a wire creates a magnetic field with flux density that is directly proportional to the current in amperes. Conversely, a changing magnetic field will induce current in a wire. This principle is used in a *coil magnetometer*, which can detect buried objects when the coil moves above them. A *rotating coil magnetometer* can determine magnetic field strength while remaining in a stationary position. However, the coil in a coil magnetometer must be relatively large.

Hall Effect and Magnetoresistance

In modern handheld devices, a magnetometer will generally use either the *Hall effect* (see "Hall-Effect Sensor") or *magnetoresistance*, described here.



Figure 2-6 *Heading is an angle usually calculated relative to geographical north, sometimes referred to as "true north."*

Magnetoresistance is a phenomenon where the resistance of a material changes fractionally when it is exposed to a magnetic field. This is capable of yielding greater accuracy than Hall-effect sensors, but has tended to be more expensive.

Orthogonally oriented sensors contained in a surface-mount chip are aligned with axes identified with letters X, Y, and Z. These sensors are analog devices whose values are converted to digital values by an onboard *analog-to-digital converter* (ADC). The values are stored in *registers* that are available to other devices, often via the *I2C* protocol, which is widely used by microcontrollers.

Typically there will be two eight-bit registers for each axis, one defining the high byte and the other defining the low byte for the digital value. In reality the ADC is likely to use 10 to 13 bits, with the remaining 6 to 3 bits being unused.

Variants

The Freescale Semiconductor FXMS3110 is a typical low-cost chip containing a 3-axis magnetometer sensor. Many chips now additionally include a 3-axis accelerometer sensor. An example is the LSM303 by STMicroelectronics, which is sold on a breakout board by Adafruit. See Figure 2-7.



Figure 2-7 *The LSM303 is a chip manufactured by STMicroelectronics. It is shown here on a breakout board from Adafruit.*

See Chapter 10 for an explanation of the function of accelerometers.

The InvenSense MPU-9250 is a highly sophisticated IMU, including a 3-axis **gyroscope** in addition to a 3-axis magnetometer and 3-axis accelerometer.

A processing unit in the MPU-9250 reconciles the nine variables, and the digital output can be accessed via I2C or SPI protocol at speeds up to 1MHz. All functions of the chip are contained within a package measuring less than 3mm square.

See Chapter 9 for additional details about the functioning of a gyroscope.

How to Use It

A basic 3-axis magnetometer sensor such as the HMC5883L can be tested with a microcontroller that can receive data from its registers via I2C protocol. This is relatively easy with an Arduino, which was designed to be I2C-capable.

Several breakout boards are available with the HMC5883L mounted on them. Many of these boards contain a voltage regulator, allowing a 5VDC power supply to be used even though the chip is designed for a typical supply of 2.5VDC.

In addition to the power supply, the breakout board only requires two connections for I2C communication, to its SCL pin (serial clock input) and SDA pin (serial data input/output). If basic I2C software is installed on the microcontroller, it will read digital values from the magnetometer registers. If additional software is used, it will convert the values to magnetic flux densities in microteslas for the X, Y, and Z axes. Code libraries to achieve these goals are widely available online.

A more sophisticated chip such as the InvenSense MPU-9250 can be used similarly, but yields additional data for conversion. Here again, code libraries can be found online. The slightly older MPU-9150 is sold on a breakout board with downloadable code from Sparkfun.

What Can Go Wrong

Bias

Magnetometers are sensitive to their environment, which can induce *magnetometer bias* of two types.

Hard-iron bias is primarily caused by magnetized material inside the device containing the magnetometer. Because this effect is usually unvarying, compensating for it is relatively easy. *Soft-iron bias* is caused by interaction between variations in the Earth's magnetic field and materials inside a magnetometer that can be magnetized.

A common example of soft-iron bias would be power lines, generating a magnetic field that can affect model aircraft and drones using magnetometers for navigation.

Mounting Errors

Placement of a chip-based magnetometer on a circuit board is critical. The field effects of transformers or relays must be taken into account, and even the low voltage and low current in a circuit trace can create a magnetic field sufficient to disturb a chip. No traces on any layer of the board should pass across the footprint of the chip. A magnetometer should not be mounted within a ferromagnetic case.

object presence sensor

3

An **object presence** sensor may also be described as an *object detector* or *detection sensor*.

The term **proximity** sensor may be applied to this component. However, in this Encyclopedia a proximity sensor has the capability of estimating the distance to a target. See Chapter 5. An object presence sensor merely detects whether an object is within a preset range, and does not provide additional information.

Optical and *magnetic* object-presence sensors are described and compared in this entry. *Ultrasonic sensors* are described in the entry dealing with proximity sensors, because they tend to be used for distance measurement rather than just for detection. Other methods of object presence sensing, including *capacitive*, *doppler*, *inductive*, *radar*, and *sonar*, are not included in this Encyclopedia.

A sensor that detects an object by receiving light reflected from it is categorized as a *reflective* sensor, and is included in this entry. (If a module includes a light source as well as a light sensor, it is properly categorized as *retroreflective*, although that term is not always used.)

A sensor that detects an object when it interrupts a beam of light is a *transmissive* sensor, and is included in this entry. It may also be described as a *through-beam* sensor or as an *optical switch*.

A sensor that responds to the motion of an object that emits infrared radiation is a **passive infrared** motion sensor, also described by its acronym, PIR, and often referred to simply as a *motion sensor*. It has its own separate entry. See Chapter 4.

Phototransistors and **photodiodes** may be used as sensing elements in presence sensors. These components have their own entries as light sensors. See Chapter 22 and Chapter 21.

OTHER RELATED COMPONENTS

- **proximity** sensor (see Chapter 5)
- **passive infrared** sensor (see Chapter 4)

What It Does

An **object presence** sensor verifies the presence or absence of an object within a predetermined range, without necessarily measuring how far away it is or how fast it is moving. The object may be described as a *target*.

Object presence sensing is often used to verify the correct function of an automated system—for example, the placement of objects on a conveyor belt. It can also be used to count objects as they pass a sensor.

Some types of security systems use presence sensors to sound an alarm if an intruder interrupts a beam of light. They can verify that a door or window is closed. They may also function as a limit switch to control the operation of a motor.

Schematic Symbol

In schematics, an optical presence sensor may be indicated with the symbol for an LED, plus the symbol for a **phototransistor**, with one or two arrows connecting them, as shown at top-left in Figure 3-1. Wavy-line arrows may indicate an infrared connection.

A **photodiode** may be substituted for a phototransistor, as shown at top-right in the figure.

A magnetic sensor may be shown with the symbol for a *Hall-effect sensor*, as in the lower half of Figure 3-1.


Power
Output
Output
Negative ground

Figure 3-1 *Top: two possible schematic symbols for an optical presence sensor, using a phototransistor (left) or photodiode (right). Other variants are possible. Bottom: the schematic symbol for a Hall-effect sensor, commonly used in a magnetic sensor.*

Variants

To assist the reader in comparing different options for detecting the presence of an object, this entry includes two primary variants: *optical* and *magnetic*.

The optical sensors are divided into *transmissive* and *reflective* (including *retroreflective*). The magnetic sensors are *reed switches* and *Hall-effect sensors*. A chart showing the categories and subcategories is shown in Figure 3-2.


Object Presence Sensor
Optical
Magnetic
Transmissive
Reed Switch
Slot (optical switch)
Separate Emitter & Detector
SPDT
SPST
N.O.
N.C.
Reflective
Hall Effect
Retro-reflective
Separate Emitter & Detector
Unipolar
Bipolar
Omnipolar
Linear

Figure 3-2 *Categories of object presence sensors discussed in this entry. Other types of object presence sensors exist, but are less common, and are not included here.*

Optical Detection

A *transmissive optical sensor*, also known as a *through-beam sensor*, is really a pair of components, one emitting light and the other receiving it. The sensor is triggered if an object interrupts or reflects the light beam, as shown in Figure 3-3.



Figure 3-3 *Various configurations of optically activated object presence sensors. See text for details.*

If the light emitter and the light detector face each other across a small gap, they may be contained in a single module (usually with a slot in it) as shown in section 2 of Figure 3-3. This is often referred to as an *optical switch* (not to be confused with the solid-state switching devices used in telecommunications). It is sometimes described as a *photointerruptor* or *photointerrupter*.

A *reflective optical sensor* also consists of a light emitter and a light detector, but they are placed adjacent to each other, facing in the same general direction. When they are mounted in one module, as is often the case, the arrangement is properly known as a *retroreflective sensor*. Either way, the combination may be triggered in one of two ways:

- An object passing in front of the light beam reflects it back to the detector. The object must be naturally reflective (for example, glass containers or white boxes on a conveyor), or must have a reflective patch applied to it, or the light source must be bright enough to reflect from an object that is not highly reflective. This configuration is shown in section 3 of Figure 3-3.
- A stationary reflector can be mounted opposite the light emitter, in which case a detector beside the light emitter is triggered when an object interrupts the reflected light beam. This configuration is shown in section 4 of Figure 3-3.

Transmissive Optical Sensors

A light source and light detector may be sold as separate components in a matched pair. An example is the Vishay TCZT8020, shown in Figure 3-4. These components are small, each measuring no more than 5mm x 3mm. They are designed to be placed just a few millimeters apart. The light source is an infrared LED, while the detector is a **phototransistor** (see Chapter 22 for information about phototransistors).

The source and detector are both designed to use 5VDC. Output from the phototransistor is an open collector. Current through the collector must not exceed 50mA, and must be limited by a pullup resistor of 100 ohms or more. Current through the source must not exceed 60mA, and must be limited by an appropriate series resistor.

Details on using an open-collector output will be found in the Appendix. See Figure A-4.



Figure 3-4 *A matched light source and light detector, for use as a transmissive optical sensor. The background grid is in millimeters.*

The Omron EE-SX range includes a variety of configurations of light source and detector separated by a 5mm slot in one module. The source is an infrared LED, and the detector is a phototransistor.

The Omron components tolerate a wide range of supply voltages, from 5VDC to 24VDC, with no series resistor necessary for the LED. Open-collector output from the phototransistor can tolerate 50mA to 100mA, depending on the particular version of the sensor. A red indicator LED is illuminated when an object blocks the slot in the sensor. Some versions have a high output when the slot is open, while others have a high output when the slot is closed. Because of their various features, these sensors are relatively expensive.

A much cheaper optical switch is the Everlight ITR9606 (described by the manufacturer as an "opto interrupter"). It is pictured in Figure 3-5. This is intended as a 5V device and has an open-collector output. It requires a series resistor for the LED and a pullup resistor for the open-collector output. Many similar detectors are available.



Figure 3-5 *A low-cost transmissive sensor, more commonly known as an optical switch. The background grid is in millimeters. The slot in the sensor is about 5mm wide.*

For longer-distance detection, an infrared receiver can be mounted separately from an infrared LED. The TSSP77038 from Vishay detects infrared light from as far away as 50cm, and pulls its open collector output low in response. The light must be modulated at 38kHz.

Polulo Robotics and Electronics sells a very affordable breakout board containing a TSSP77038 receiver paired with an infrared LED modulated by a 555 timer. It is shown in Figure 3-6. Because this board contains a light source as well as a light detector, it is really a retroreflective sensor.

Where distances exceeding 1 meter are involved, a laser coupled with a phototransistor that is shielded from ambient light may be necessary.



Figure 3-6 *The Vishay TSSP77038 installed with an appropriate light source on a breakout board from Polulo Robotics and Electronics.*

Retroreflective Optical Sensors

As is the case with a transmissive object detector, the retroreflective type may be listed by vendors as an *optical switch*. Other terms used in datasheets include *reflective interrupter*, *reflective object sensor*, *reflective optical sensor*, *reflective photointerrupter*, *opt-pass sensor*, and *photomicrosensor (reflective)*. The remarkable lack of standardization in terminology creates a problem when searching online for these devices. Why so many different names evolved for the exact same component is unclear.

Many retroreflective object-detection sensors are available in packages ranging from 5mm x 5mm to 10mm x 10mm in size. Almost all of these modules are analog devices using an infrared LED as the light source and a phototransistor as the sensor, with an open-collector output. (For more information about phototransistors, see Chapter 22.)

With a suitable pullup resistor, the output voltage will be proportional with the inverse of the distance. If V is the voltage, d is the distance, and k is a conversion factor:

```
V = k * ( 1 / d)
```

While many of the smaller modules are surface-mount, some have leads, as shown in Figure 3-7. A major limitation of these small components is that they have a very limited range, typically less than 5mm. They can only be used in applications such as process control where the position of a target is controlled and predictable.



Figure 3-7 *The Rodan RT-530 is a small object-presence sensor with a limited range typical of this type of retroreflective component. The background grid is in millimeters.*

Another example of a retroreflective sensor in a small package is the Optek OPB606A shown in Figure 3-8. The background grid is in millimeters.



Figure 3-8 *The Optek OPB606A. The background scale is in millimeters.*

A retroreflective module, with a lensed LED and lensed phototransistor to focus the outgoing and reflected beams, is the Vishay TCRT5000 shown in Figure 3-9.



Figure 3-9 *The Vishay TCRT5000 retroreflective sensor. The background grid is in millimeters.*

Retroreflective modules that have a greater range tend to be physically larger, less common, and more expensive. Sharp makes a popular series. Some part numbers and distance sensing limits are: GP2Y0D805Z0F (5mm to 5cm), GP2Y0D810Z0F (2cm to 10cm), and GP2Y0D815Z0F (5mm to 15cm). Figure 3-10 shows the GP2Y0D810Z0F mounted on a small breakout board from Polulo Robotics and Electronics. The board is useful, as the pins on the sensor are spaced only 1.5mm apart. The size of the board is approximately 8mm x 20mm.



Figure 3-10 *The Sharp GP2Y0D810Z0F detection sensor mounted on a board from Polulo Robotics and Electronics. From a photograph by Adafruit Industries.*

Each of the detection sensors in this series is described in Sharp datasheets as a "Distance Measuring Sensor Unit," but in fact they do not measure distance. A single output is normally logic-high and drops to logic-low when a target is within range. Sharp refers to this as a "digital" output, but in fact it is binary, and should not be confused with the digital buffer on a more sophisticated proximity sensor that contains an analog-to-digital converter and provides a numeric output.

It is important to distinguish the Sharp object-presence sensors listed above from the range of Sharp **proximity** sensors described in the entry in Chapter 5. The proximity sensors are physically larger, and most have an analog output that varies with the distance of a target.

Magnetic Sensors

Prepackaged magnetic sensing units are sold in many configurations for industrial and military applications. Although they may be referred to as "magnetic sensors," they are outside the scope of this Encyclopedia. Here we discuss board-mounted components. Almost always, they use a *reed switch* or a *Hall-effect* sensor as their sensing elements.

Reed Switch

A reed switch is a magnetically activated mechanical switch. It consists of two metallic contacts in a small enclosure that is usually a glass capsule. The contacts are magnetic, and move in response to a magnetic field. A permanent magnet is used to activate the switch. Two reed switches are shown in Figure 3-11.



Figure 3-11 *Two SPST reed switches. Although the contacts may seem to be touching, in fact they are separated by a tiny gap, and these switches are the normally open type. The background grid is in millimeters.*

A reed switch exhibits a small amount of *hysteresis*, because the magnetic field strength required to overcome the mechanical resistance of the springy contacts is greater than the field strength required to keep them closed.

Very small electromagnetic relays that only switch a very low current may use a coil-activated reed switch. For purposes of this Encyclopedia, such a component is considered to be a relay, not a sensor. For more information about **relays**, see the entry in Volume 1.

The most common everyday application for a reed switch is in an alarm system that is triggered by an intruder entering a building. A magnet in a sealed plastic enclosure is attached to a door or window, while a reed switch, in another sealed plastic enclosure, is attached to the frame, very close to the magnet. Typical components of this type are shown in Figure 3-12. A diagram illustrating the mode of operation appears in Figure 3-13.



Figure 3-12 *A typical alarm sensor to detect the opening of a door or window. The nearer module contains a magnet, while the module behind it contains a reed switch.*



Figure 3-13 *The dashed white lines suggest the magnetic field that closes the contacts of a reed switch.*

So long as the alarmed door or window remains closed, the magnet activates the reed switch. If the door or window is opened, the magnet moves away from the reed switch, and its contacts relax. Usually in this application the reed switch is the normally open type, and is held in its closed state by the magnet. This allows multiple switches to be wired in series, completing a circuit. If a single switch opens, the circuit is broken, and an alarm is triggered.

Reed Switch Variants

Most reed switches are SPST, either normally open or normally closed, although normally open variants are more common. Some switches are SPDT, although this variant is relatively rare. An example of a SPDT reed switch is shown in Figure 3-14.



Figure 3-14 *A SPDT reed switch. The background grid is in millimeters.*

The physical size of a reed switch tends to vary roughly in proportion with its current-switching capability.

Reed switches are most commonly supplied with axial leads. A minority are available for surface-mount applications.

Some reed switches are packaged in a plastic pod to provide physical protection for the glass capsule.

Reed Switch Values

The datasheet for a reed switch is likely to contain the following values:

Pull-in: The minimum magnetic field strength required to activate the switch, often measured in ampere-turns.

Drop-out: The maximum magnetic field strength that allows the contacts of the switch to relax, often measured in ampere-turns. Pull-in will be a higher value than drop-out.

Maximum switching current: While a few industrial reed switches can switch as much as 100A, they are uncommon and expensive. A common value for a reed switch about 15mm long is 500mA.

Maximum carry current: If specified, it will be higher than the switching current.

Maximum switched power: Because a reed switch can be used with alternating current, its switching capability may be expressed in watts, or as VA (volts multiplied by amps). 10VA is a common value.

Maximum voltage: While reed switches are most often used with low voltages, some are rated to switch up to 200V.

How to Use a Reed Switch

While an optical object presence sensor may be supplied in a single package containing a light emitter and a light detector, a reed switch always requires an activating magnet that is mounted separately. For reliable operation, the maximum distance between the switch and the magnet is usually restricted to a few millimeters.

The orientation of a magnet that activates a reed switch is not crucial, but will affect the sensitivity of the switch. A manufacturer's datasheet should be consulted for information about optimal magnetic polarity.

As in other mechanical switches, the contacts in reed switches vibrate very briefly when opening or closing. This is known as *contact bounce*, and can be misintepreted as a series of separate signals by digital logic or a microcontroller. *Debouncing* with hardware designed for that purpose, or software (in a microcontroller), may be necessary. See the entry on **switches** in Volume 1.

Hall-Effect Sensor

A Hall-effect sensor responds to a magnetic field by generating a small voltage, usually amplified by a transistor included in the package with the sensor.

When a Hall sensor is in its “off” state (i.e., not triggered by a magnetic field), the sensor creates high resistance between the collector of an internal NPN transistor and negative ground. Consequently, if voltage through a pullup resistor is applied to the collector, the voltage on the collector will be high.

When the sensor is in its “on” state, the resistance drops, the voltage supplied to the collector from the pullup resistor is shunted to ground, and the output voltage appears to go low. As a general rule:

- Activated Hall sensors appear to have a low output.
- Inactive Hall sensors appear to have a high output.

Information about using open-collector outputs is contained in the Appendix. See Figure A-4.

The clean output, reliability, small size, and cheapness of Hall sensors have encouraged their use in devices as different such as hard drives, cameras, keyboards, and automobiles. They are useful in almost any situation where a sensor must detect a mechanical operation at close range. Three through-hole Hall sensors are shown in Figure 3-15. Surface-mount versions are much smaller.



Figure 3-15 *Three through-hole Hall-effect sensors. The background grid is in millimeters.*

How a Hall-Effect Sensor Works

When current is flowing through the length of a conductor, and a magnetic field is applied across the width of the conductor, the field generates a force causing electrons and electron holes to accumulate asymmetrically on opposite sides. This is known as the *Hall effect*.

The voltage difference between the electron-rich and electron-depleted zones is known as the *Hall voltage*. It is proportional to the magnetic field, and inversely proportional to the density of free electrons in the material. For this reason, the Hall effect is easiest to observe in semiconductors, where the density of electrons or electron holes is low.

Hall sensor components contain amplifier circuitry in addition to the sensing element itself. Typically there is an open-collector output, and a comparator or Schmitt trigger to provide some hysteresis.

Hall-Effect Sensor Variants

Four primary variants of Hall sensors are widely used.

Unipolar Hall Sensor

This is activated when an external magnetic field exceeds a threshold value. When the field diminishes, the sensor switches off. Unipolar sensors are available in versions activated by the north magnetic pole or south magnetic pole.

Bipolar Hall Sensor

Proximity to one magnetic pole will switch it on. Proximity to the opposite magnetic pole will switch it off. The sensor remains in its current state (on or off) in the absence of a magnetic field.

Omnipolar Hall Sensor

Proximity to a strong magnetic field of either polarity will switch it on. Removal of the magnetic field will switch it off. An omnipolar sensor can be thought of as a pair of unipolar sensors mounted in opposite directions and with their (open-collector) outputs wired together. This component functions similarly to a reed switch, although of course it still requires a power supply.

Linear Hall Sensor

Also known as an *analog* Hall sensor, its output voltage varies in proportion to an external magnetic field instead of switching cleanly between high and low states. When no magnetic field is detected, the output is half of the sensor's supply voltage. In response to one magnetic polarity, the output can drop almost to zero. The opposite polarity can increase the output almost to supply voltage.

The output from a linear sensor usually is supplied from the emitter of an internal NPN transistor, not the collector. A minimum 2.2K resistor should be connected between output and ground.

The variable output can be interpreted as a measurement of distance between the sensor and a magnet. In this mode, a Hall sensor functions as a **proximity** sensor. However, it is not usually capable of measuring a distance of more than 10mm.

Other Applications

Hall sensors are incorporated in other types of components. A **magnetometer**, for example, may contain Hall sensors.

Additional discussion of Hall-effect sensors, with test circuits, will be found in the book *Make: More Electronics*, from which some of the figures here have been excerpted.

Values

Magnetic field at operating point is the minimum field necessary for the output to switch on. It is measured in tesla or gauss, and the abbreviation B_{OP} is used.

Magnetic field at release point is the maximum field that allows the output to switch off. It is measured in tesla or gauss, and the abbreviation B_{RP} is used.

Magnetic field range may be specified for linear (analog) Hall sensors.

Supply voltage may range as widely as 3VDC to 20VDC, or may be restricted between 3VDC to 5.5VDC. Check datasheets carefully.

Sourcing or sinking capability for the open-collector output is typically 20mA.

How to Use a Hall-Effect Sensor

Hall sensors are often made in 3-pin packages. Through-hole variants are usually made of black plastic and look like TO-92 transistors, but are slightly smaller.

Surface-mounted variants are common.

A typical through-hole Hall sensor has one bevelled face and a flat face on the opposite side. The bevelled face may be referred to as the "front" of the component in a datasheet. The sensor responds when an appropriate magnetic pole is brought close to the front face of the sensor.

The part number printed on the front of the sensor may be abbreviated as three digits. The code below this usually refers to the date of manufacture.

A simple circuit for a Hall sensor resembles a typical circuit for a phototransistor. Positive supply voltage and negative ground are applied to two of the three leads. Positive voltage is also applied, through a pullup resistor, to the third lead, which is the open-collector output (except in the case of a linear Hall sensor, described previously). The output pin is then tapped as the output from the sensor, to be applied to a component that will not draw more than 20mA.

Configuration of Object Presence Sensors

While most of the following suggestions relate specifically to Hall-effect sensors, some general principles may be applied to optical sensors.

Linear Motion

A presence sensor can be activated when the triggering source (such as light or a magnet) approaches it directly. This is sometimes referred to as *head-on mode*. Alternatively, triggering can be arranged when the source moves past the sensor. This is sometimes referred to as *slide-by mode*. The two modes are illustrated in sections 1 and 2 of Figure 3-16.



Figure 3-16 *Section 1 of this figure illustrates a presence sensor being used in head-on mode, while section 2 illustrates slide-by mode.*

Slide-by mode may be preferred because it eliminates the risk of damage to the sensor if overshoot occurs in head-on mode.

In slide-by mode, using a bipolar Hall-effect sensor, two magnets can be placed together with opposite polarity, creating a very steep transition in the overall magnetic field. This minimizes the risk of imprecise triggering. Using neodymium magnets, the triggering point can be adjusted with a precision of 0.01mm or better. See Figure 3-17.



Figure 3-17 *In slide-by mode, two magnets with opposite polarity can be put together to create a very precise transition in a bipolar Hall-effect sensor.*

Sensing by Interruption

An *optointerrupter* is sensitive to an object passing between the light source and the light sensor. A comparable arrangement can be used with a Hall-effect sensor or a reed switch, but only if the interrupting object is thin and ferrous. This configuration is known as a *ferrous vane interruptor*.

Note that the magnet will exert significant force on the ferrous vane. This becomes an issue in sensors where the mechanical force is limited—for example, in paper-path sensors in a photocopy machine.

Additional information about the detection and measurement of moving objects will be found in the entry describing **linear position** sensors. See Chapter 6.

Angular Motion

One or more magnets can be used with a Hall-effect sensor to detect the angular motion, relative angular position, or absolute angular position of a rotating part. This data can be used to determine its speed of rotation. Some techniques to achieve this are described in the entry describing **rotary position** sensors. See Chapter 7.

Sensor Comparisons

Advantages of Optical Presence Sensors

- Not affected significantly by magnetic fields that can interfere with operation of a Hall-effect sensor or a reed switch.
- May be contained in a small, all-in-one package.
- Some optical sensors can operate over a distance of 50cm.
- Very well suited to sensing an object that blocks the light source (the *optointerrupter* configuration).

Disadvantages of Optical Presence Sensors

- Must have clear line-of-sight with the object and/or a reflector.
- Performance will be degraded by accumulation of dust or dirt.
- Limited lifetime of LED light source, if used continuously.
- May be accidentally triggered or impaired by some types of ambient light.
- Often requires a load resistor for the LED as well as a pullup resistor for the open-collector output.
- Range of acceptable voltage is usually narrow.

Advantages of a Reed Switch

- No polarity.
- No additional components required, other than a magnet.
- Able to switch AC or DC.
- Able to switch to voltages as high as 200V in some cases.
- Can be maintained by a magnet in open or closed state indefinitely without any power consumption.
- Many variants are capable of switching 500mA, and higher-current types are available.
- Can be activated through nonmagnetic materials (plastic, paper).
- Not significantly affected by dust or dirt that can degrade performance of an optical switch.

Disadvantages of a Reed Switch

- Requires a separate magnet (which must be placed carefully to avoid affecting other components).
- Cannot be miniaturized to the same extent as a surface-mount chip.
- Glass envelope is easily damaged.
- Arcing may occur between contacts.
- Will not work reliably when the activating magnet is more than a few millimeters from the switch.
- Can be activated accidentally by other magnetic fields.
- When sensing an object that comes between the switch and a magnet, only a ferrous object can be used.
- Must be debounced when connected with a logic chip or controller.

Advantages of a Hall Effect Sensor

- Robust solid-state component.
- Can be miniaturized for surface-mount applications.
- Very low cost.
- Fast response.
- No contact bounce.

- Extremely durable, with an almost unlimited lifetime.
- Not significantly affected by dust or dirt that can degrade performance of an optical switch.
- Low cost.

Disadvantages of a Hall Effect Sensor

- Requires a separate magnet (which must be placed carefully to avoid affecting other components).
- Open-collector output typically limited to 20mA or less.
- May be vulnerable to magnetic fields.
- When sensing an object that comes between the switch and a magnet, only a ferrous object can be used.

What Can Go Wrong

Optical Sensor Issues

Deterioration of LEDs

Most object presence sensors depend on infrared LEDs as a light source. An LED has many virtues (discussed in Volume 2), but does tend to suffer from gradual reduction in light output over a period of years. In a device such as a photocopy machine, which is used intermittently and may have an "economy" or "sleep" mode in which most of its components are powered down, LED-based detectors should last almost indefinitely. In other applications where an LED is powered continuously, its light output will diminish signicantly in 3 to 5 years. Bearing this in mind, an optical sensor should be chosen to operate well below its light-detection limits.

Object Too Close

Some optical and ultrasonic detectors triangulate on an object; that is, the light emitter and light sensor are angled slightly toward each other (as shown in sections 3 and 4 of Figure 3-3). The signal output from the sensor will peak at the distance where the emitter and sensor focus at a point. Consequently the output voltage will diminish when the object comes closer, which may create the misleading impression that the object is moving further away. To avoid spurious readings, detectors should not be used with objects that are closer than the minimum distance specified by the manufacturer.

Reed Switch Issues

Mechanical Damage

Bending the axial leads on a reed switch can easily fracture the glass envelope. Reed switches must be handled with care.

Contact Bounce

If the switch is wired to the input of a logic chip or microcontroller, contact bounce when the switch opens or closes is likely to be misinterpreted as multiple switching events. Debouncing will be necessary, either by additional components or by insertion of a momentary delay in the code embedded in a microcontroller.

Arcing

When switching high voltages or currents, an arc may be created briefly between the switch contacts, most often when they are moving from the closed to the open state. The arc erodes the contacts of the switch. Inductive loads make the arcing problem worse. If the switched voltage is kept below 5V arcing generally does not occur, extending the life of the switch.

passive infrared sensor

4

In coloquial speech, the term *motion sensor* is usually understood to mean a **passive infrared** motion sensor.

The acronym *PIR* is often used for a passive infrared sensor. It is always capitalized, without periods.

Object presence sensors and **proximity** sensors require an active source of a magnetic field, ultrasound, or infrared radiation. A passive infrared sensor does not require any such source, and responds passively to heat radiated from the object that is being detected.

OTHER RELATED COMPONENTS

- **object presence** sensor (see Chapter 3)
- **proximity** sensor (see Chapter 5)

What It Does

A **passive infrared** motion sensor, often described as a *PIR*, detects *black-body radiation*, which all objects emit as a function of their temperature relative to absolute zero. The sensor responds to infrared radiation centered around a wavelength of 10µm (10 microns, or 10,000nm). This is the approximate body temperature of people and animals.

The word “passive” in the term “passive infrared” refers to the behavior of the detector, which receives infrared radiation passively. **Proximity** sensors must generate their own infrared radiation actively, which is interrupted or reflected by nearby objects. See Chapter 5.

Schematic Symbols

Schematic symbols that are sometimes used to represent a passive infrared motion sensor are shown in Figure 4-1.



Figure 4-1 *Schematic symbols that may represent a passive infrared motion sensor. The orientation (pointing left or right) is arbitary. The pin sequence may vary.*

Applications

Motion-sensitive outdoor lighting almost always is based around a PIR. Similarly, a security system may sound an alarm or activate a video camera when a PIR indicates human activity.

Wildlife monitoring systems use PIRs to start a video camera that can then run for a preset interval.

Warning systems for automobiles have been developed that use a rear-facing PIR to detect pedestrians.

Industrial indoor lighting may use PIRs that switch the lights on automatically when people enter a room, and then switch the lights off (after a timed delay) when people are no longer detected in the room. The goal is to prevent wastage of energy as a result of employees forgetting to switch the lights off.

How It Works

A PIR module contains multiple components. Most visible is an array of at least 15 small lenses that focus infrared light from zones in the environment onto a *pyroelectric detector*, also known as a *pyroelectric sensor*. The response of the detector is processed by an amplifier, so that the signal can trigger an electromechanical **relay** or **solid-state relay** (see Volume 2). The relay operates an external device such as a light or an alarm.

Additional circuitry may allow the user to control the sensitivity of the PIR module and the length of time that the relay remains closed. The user may also be able to set the time of day when the PIR is active, or an additional **phototransistor** can shut down the PIR during daylight hours. If a phototransistor is included, its sensitivity is adjustable. For more information about phototransistors, see Chapter 22.

Pyroelectric Detector

The pyroelectric detector is actually a type of *piezoelectric* device. It is based around a wafer of lithium tantalate, which generates a small voltage in response to incident thermal radiation. However, like other piezoelectric components, it does not respond to a steady-state input, and must be activated by a transition. This distinguishes it from other types of light sensors, such as an infrared **photodiode**, in which the response is consistently related to a temperature input.

The response of a pyroelectric detector is suggested by the graphs in Figure 4-2.



Figure 4-2 *Top: incident infrared light intensity. Center: the voltage output from a hypothetical photodiode. Bottom: the voltage output from a hypothetical pyroelectric detector.*

A pyroelectric detector in a PIR module is mounted in a sealed metallic container, as shown in Figure 4-3. The rectangular window in the detector is usually made of silicon, which is opaque to visible wavelengths but transparent to long-wave infrared radiation.

Elements

The pyroelectric detector used in a PIR contains at least two *elements* with opposite polarities, connected in series. If a sudden change in temperature affects both elements equally, their responses will cancel each other out. Thus, the detector ignores changes in ambient temperature. However, if a source of infrared radiation in the appropriate waveband affects one element before the other, the detector will emit two pulses of opposite polarity. See Figure 4-4.



Figure 4-3 *A pyroelectric detector mounted on a small circuit board in a passive infrared radiation sensor.*



Figure 4-4 *Top: in a pyroelectric detector, if a change in temperature affects two elements of opposite polarity simultaneously, their voltages cancel each other out. Bottom: if one element is triggered before the other, the detector emits a signal.*

Lenses

Lenses are used to trigger the elements sequentially. Each lens faces toward one visible zone in the target area. When a source of infrared radiation moves from one zone to the next, it energizes the elements alternately, creating an output.

In some PIRs, four pyroelectric elements are used instead of two, to provide better coverage. The pairs of sensors may be wired in series or in parallel, but the principle remains the same.

The lenses are molded into a polyethylene dome that is often white and covers the pyroelectric detector. The dome appears smooth on the outside, but fine patterns of concentric ridges are molded on the inside. These are *fresnel lenses*, which are much cheaper, smaller, lighter, and easier to fabricate than conventional optical lenses. A fresnel lens introduces some distortion and aberration, but these defects are unimportant in a PIR.

Figure 4-5 illustrates the principle of a simple fresnel lens. The first section of this figure shows a conventional optical lens with one flat side and one curved side. A distant object emits almost-parallel beams of infrared light that are focused by the lens. Section 2 shows the same lens divided into segments that are stacked with no space between them. They behave in exactly the same way as the original lens. In section 3, each segment has been reduced in width, but because the optical faces still have the same geometry, they will still have the same function, although a small amount of distortion will be added by the reduction in width. This is a fresnel lens, which found an early application in lighthouses, where it greatly reduced the weight of very large glass lenses that focused the beam.



Figure 4-5 *Principle of a fresnel lens. See text for details.*

The same principle can be applied to a lens in which both surfaces are curved, as shown in Figure 4-6. In practice this will introduce more imperfections in the image, although some compensation is possible by adjusting the exact shape of the lens.



Figure 4-6 *The principle of a fresnel lens applied to a conventional lens in which both surfaces are curved.*

Figure 4-7 shows three curved fresnel lenses placed edge-to-edge, seen from above. In section 1 of this figure, infrared rays from a distant source are focused by the first lens onto the right-hand element of a pyroelectric sensor. In section 2, the external source has moved laterally, and the rays now focus on the left-hand element. In section 3, the source has moved into the zone covered by the centrally located fresnel lens, which focuses on the right-hand element again. The fluctuating inputs will trigger the sensor.



Figure 4-7 *Sections 1, 2, and 3 show fresnel lenses focusing an external source of infrared radiation on individual elements of a pyroelectric sensor.*

PIRs may combine fresnel lenses in a variety of patterns. Figure 4-8 shows an evenly weighted mosaic that would be suitable for a motion detector mounted on a ceiling, facing directly downward. Figure 4-9 shows a pattern weighted toward lateral motion, providing less sensitivity for motion above and below the primary band.



Figure 4-8 *An evenly weighted mosaic of fresnel lenses.*



Figure 4-9 *A mosaic weighted more toward sensing lateral motion. The grooves of the fresnel lenses are visible.*

Variants

PIR sensor modules are available mounted on a small board such as the one shown in Figure 4-10 from Parallax, Inc. The detection range is 5 to 10 meters, selected by a jumper on the board. The three pins visible in the photograph are for power supply (3VDC to 6VDC), ground, and output. The output can source up to 23mA with a 5VDC power supply. Power consumption of the module is only 130µA when it is idle, or 3mA when it is active but has no load.



Figure 4-10 *A passive infrared detector mounted with basic necessary components on a small board.*

A board of this type still requires additional components to set the "on" time for a light or alarm, and to deactivate the PIR during daylight hours.

Various lens patterns are available, sold separately.

A PIR can be bought as a single component containing two elements and FET transistors to amplify the signal. Surface-mount and through-hole versions are available, requiring a typical power supply of 3VDC to 15VDC.

However, a PIR bought as a "bare" component requires significant external circuitry, using comparators or op-amps. Circuit design is nontrivial, entailing practical problems such as op-amps being sensitive to voltage spikes caused by activating a relay that shares the same power supply.

An easier alternative is an all-in-one detector, lens, and control circuit such as the Panasonic AMN31111, which is ready for board mounting. Its small output current of 100μA would be capable of activating a solid-state relay. Similar Panasonic PIRs offer a variety of ranges, sensitivities, and supply voltages.

The AMN31111 is in Panasonic's AMN series. There are many type numbers for combinations of analog or digital output, lens shape, and black or white lens. A selection of lens shapes, derived from the manufacturer's datasheet, is shown in Figure 4-11.



Figure 4-11 *Four lenses from the Panasonic AMN series of passive infrared sensors.*

What Can Go Wrong

Temperature Sensitivity

In warmer weather, objects in the field of view of a PIR will tend to be warmer, and the temperature difference between them and human skin will diminish. This can degrade the performance of a PIR.

Detector Window Vulnerability

The silicon window on a detector is vulnerable to dirt or grease. Avoid touching the component if it is not protected by lenses.

Moisture Vulnerability

Water absorbs far-infrared light. Consequently, condensation on the lens or detector can degrade performance, and a PIR may not function in heavy rain or snow.

5

proximity sensor

Proximity sensors that use infrared, ultrasound, and capacitance are described here. This Encyclopedia does not include proximity sensors that use magnetism, inductance, or other methods of determining distance.

Sometimes proximity sensors are referred to as *distance sensors*. An ultrasonic proximity sensor may be described as a *range finder* or a *ranger*.

High-end ultrasound proximity sensors sold as large, sealed modules with cabling can monitor the status of industrial processes. These commercial units are outside the scope of the Encyclopedia.

A sensor that detects whether an object is present, but does not measure the distance to it, is considered to be an **object presence** sensor and has its own separate entry. See Chapter 3. Many devices that are sold as proximity sensors or distance sensors actually do not provide meaningful distance data, and therefore in this Encyclopedia they are included with presence sensors.

Phototransistors and **photodiodes** may be used as sensing elements in proximity sensors. These components have their own entries as light sensors. See Chapter 22 and Chapter 21.

OTHER RELATED COMPONENTS

- **object presence** sensor (see Chapter 3)
- **passive infrared** sensor (see Chapter 4)

What It Does

A proximity sensor measures the distance between itself and a physical object that is often described as the *target*. The output from the sensor may be analog (voltage), serial data, or pulse-width modulation. It may be transmitted via a serial protocol such as SPI, TTL, or I2C, and may be stored as digital data in a register that is accessed by a microcontroller, using I2C. For additional details about protocol, see Appendix A.

Schematic Symbols

Either of the schematic symbols in Figure 5-1 may represent a proximity sensor, but are not used consistently. The sensor may also be represented as a rectangle containing text describing its function.



Figure 5-1 *Two ways to represent a proximity sensor in a schematic.*

Applications

In robotics, a proximity sensor can prevent a collision between a robot and an object or barrier in front of it. Some sophisticated proximity sensors can provide sufficient data for software to map the entire environment, but are outside the scope of this entry.

Proximity sensors can also be used in alarm systems, or for liquid-level sensing in storage tanks, or in automobiles to sound a warning if the driver is backing into an obstacle (although these devices are being augmented with rear-view video monitors).

In handheld devices, proximity sensors are used to sense the presence of the user's hand or face —for example, to shut down the display when a person raises a phone to talk into it.

Variants

This entry is subdivided to describe proximity sensors that use ultrasound, infrared light, and capacitance.

Ultrasound

An ultrasonic proximity sensor functions by emitting a short burst of sound and then listening for echoes from objects in front of it.

The sound is created by a **piezoelectric transducer** (see Volume 2) at a frequency between 30kHz and 50kHz, well above the range that can be detected by the human ear. The transducer may do dual duty as a microphone, sending and receiving sound on an alternating basis; or a second transducer, serving as a microphone, may be mounted beside the emitter on a small circuit board. The economically priced HC-SR04 is an ultrasound proximity detector popular in the robotics community, working reliably in the range of 2cm to 5m.

A board on which the sensor is mounted may include a microcontroller to measure the delay between propagation of a pulse and reception of the echo. Distance to the reflecting object is then calculated using the speed of sound in air at sea level, which is approximately 340 meters per second.

Infrared

An infrared proximity sensor requires a beam of infrared light from an LED that may be incorporated in the sensing module or mounted separately. Light reflects from the target and is detected by a **phototransistor** or **photodiode**. From the angle of the reflected light, onboard electronics can calculate the distance to the target by a process known as *triangulation*. See Figure 5-2. (This diagram is simplified. An actual sensor may use a linear array of photodiodes to assess the angle of the returning light beam.)



Figure 5-2 *An infrared proximity sensor determines the distance to an object by assessing the angle of reflected light.*

To reduce the risk of false positives, light from the LED contains only a narrow range of infrared wavelengths. Also, it is modulated at a frequency recognized by sensing circuitry in the module.

Relative Advantages

Ultrasound Devices

- Generally more suitable for detecting objects that are more than 1 meter away.
- Unaffected by direct sunlight, fluorescent tubes, and other light sources that can interfere with infrared devices.
- More accurate, often capable of placing objects within 5mm.
- Able to measure the distance to liquids and transparent objects, which may not be easily detected with infrared.

Infrared Devices

- Physically smaller—especially surface-mount versions.
- Able to measure the distance to soft objects, which may not be easily detected by ultrasound.
- More appropriate for targets that are closer than 10mm.
- More affordable.

Ultrasonic Examples

The proximity sensor in Figure 5-3 is a low-priced model, popular in the robotics community. Manufactured by MaxSonar, it uses a single element to send and receive. The manufacturer claims that it can detect a 6mm (quarter-inch) dowel 1.8 meters directly in front of it, and a 9cm dowel at 3.3 meters. This performance is beyond the capability of almost all infrared sensors.

MaxSonar offers a variety of sensors that appear physically very similar but have different range capabilities. Each has three outputs that can be accessed simultaneously: serial data at 9,600bps, analog voltage, and pulse-width modulation.



Figure 5-3 *The MaxSonar MB1003 can detect large solid objects as far away as 5 meters. Photo derived from an image by Adafruit.*

The serial output uses the RS232 protocol and consists of the letter R followed by four ASCII-coded numerals representing the measured range in millimeters. Thus, R1000 would indicate an object at 1 meter distance.

The analog voltage ranges linearly from 293mV when sensing an object at 300mm to 4,885mV for an object at 5,000mm.

The pulse-width output sends pulses ranging from 300μs indicating an object 300mm away to 5,000μs indicating an object 5 meters away.

The unit incorporates a temperature sensor that compensates for the lower density of air when its temperature increases. Weatherproofed versions are available. The power supply is 5VDC and must be smoothed.

Imports

Some international sources offer minimal paired ultrasound components at a very low price, such as the HC-SR04 from Cytron Technologies in Malaysia. See Figure 5-4.

Sound dispersion of the transducer is claimed to be plus-or-minus 15 degrees, and the claimed range is up to 4 meters. The module requires a triggering input pulse that must last at least 10μs. This prompts it to emit eight rapid ultrasound signals at 40kHz. The module measures the response time and applies a high state to its echo pin for a duration that is proportional with the distance measured. An external microcontroller must time the duration, then divide by a factor of 58 to obtain distance in centimeters.



Figure 5-4 *The HC-SR04 is a very low-cost import that can provide acceptable performance when used with an external microcontroller.*

Many online sources offer simple code libraries for Arduino or PICAXE microcontrollers for use in conjunction with the HC-SR04.

Individual Elements

Individual ultrasonic components such as those shown in Figure 5-5 are available from many vendors. The user must add circuitry to generate a high frequency for a short duration, amplify the microphone signal, measure the time difference, and calculate distance.



Figure 5-5 *These components, listed as the "40TR12B-R ultrasonic sensor kit" by the online supplier Jameco, could form the basis of a DIY ultrasonic proximity sensor.*

Infrared Examples

Sharp manufactures four infrared proximity sensors that are widely regarded as accurate and easy to use. They are popular in the robotics community. Their part numbers and ranges are:

- GP2Y0A51SK0F (20mm to 150mm)
- GP2Y0A21YK0F (10cm to 80cm)
- GP2Y0A02YK0F (20cm to 150cm)
- GP2Y0A60SZLF (10cm to 150cm).

The GP2Y0A60SZLF is the most recent product, with the most impressive specification. The GP2Y0A21YK0F is shown in Figure 5-6.



Figure 5-6 *The Sharp GP2Y0A21YK0F infrared proximity sensor. The background grid is in millimeters.*

Sharp describes these sensors as having an *analog output*. The voltage on an output pin varies in inverse proportion with the distance being measured. The relationship is illustrated by the graph in Figure 5-7, derived from the manufacturer's datasheet for model GP2Y0A02YK0F.



Figure 5-7 *Relationship between output voltage and target distance for a Sharp infrared proximity sensor, derived from the manufacturer's datasheet.*

The Sharp sensors can work with 5VDC. They consume around 30mA, except for the GP2Y0A60SZLF, which uses less current. Because the infrared LED functions in bursts, the manufacturer recommends protecting other components sharing the power supply by placing a 10µF capacitor across the sensor supply pins.

Trends in Infrared Proximity Sensing

Like many other types of sensors, proximity sensors have been affected by the huge market for handheld devices.

Handheld applications have had four consequences:

Miniaturization

Infrared proximity sensors are now commonly found in surface-mount chips measuring 5mm × 3mm or smaller.

Onboard processing

The status of a photodiode can be processed by a microcontroller on the same chip, to determine what the sensor is really "seeing." Input from an included ambient light sensor is factored into the evaluation.

Cost reduction

While chip-based proximity sensors have become increasingly sophisticated, their unit cost has plummeted, so that they are now actually much cheaper than simpler devices such as the Sharp analog sensors described above.

Complexity

Modern sensors must be programmed with a complex variety of instructions, and their coded output must be interpreted with a separate microcontroller running its own program. Whether this compensates for the low price and added functionality is something for the individual developer or experimenter to decide.

The Silicon Labs Si1145/46/47 series are chips with the kind of sophisticated capabilities required for handheld devices. An external microcontroller communicates with the sensor via an I2C connection, and can instruct it to adjust its distance range (from 1cm to more than 50cm), its analog-to-digital conversion sensitivity, and its current-sinking capability for up to 3 external LEDs. The chip incorporates ultraviolet sensing and ambient-light sensing capability. Its I2C connection can run at up to 3.4Mbps. Because its light output is pulsed for only 25.6µs every 800ms at 180mA, the average power consumption is only 9µA, assuming a supply voltage of 3.3VDC.

For additional details about protocols such as I2C, see Appendix A.

In addition to its use in handheld devices, the manufacturer suggests applications including heart-rate monitoring, pulse oximetry, and display backlighting control. These applications require only a subset of the features built into the sensor, but its price is so low, it may be cost-effective even when many of its capabilities are unused.

Proximity sensors with comparable specifications are available from many manufacturers. Examples are the Vishay VCNL4040 and the Avago HSDL-9100. Figure 5-8 shows the Silicon Labs SI1145 on the left, and the Avago HSDL-9100 on the right.



Figure 5-8 *Two sophisticated surface-mount proximity sensors with digital output. Left: Silicon Labs SI1145. Right: Avago HSDL-9100. The background grid is in millimeters.*

Several guidelines must be observed when using this kind of sensor. First and most obviously, if an external LED is used, it must have a peak wavelength compatible with the photodiode in the sensor. The LED must be placed as near as possible to the photodiode, as reducing the separation increases the sensitivity; but crosstalk between the photodiode and LED must be minimized, usually by placing a thin barrier between them that is barely taller than the higher component.

If the light emitter and/or light sensor are protected behind a transparent glass or plastic panel, it must have minimal resistance to infrared wavelengths, and its thickness must be chosen in compliance with guidelines in the sensor datasheet. To prevent light from reaching the sensor by reflection from the rear of the panel, a thin, opaque tube can be installed between the LED and the panel.

A sensor of this type may be configurable with a "detection scheme," meaning high and low sensing threshold levels appropriate to the object that is likely to be detected. Determining this may be a process of trial and error.

Capacitive Displacement Sensor

This is also known as a *capacitive linear displacement sensor*. It should not be confused with a capacitive **single touch** sensor, a human-input device that has its own entry. See Chapter 13.

A **capacitive displacement** sensor measures the distance between itself and a target that must be electrically conductive. Unlike optical or ultrasound position sensors, no additional source of light, sound, or other radiation is required. Unlike a magnetic position sensor, it does not require a separate permanent magnet. It simply measures its electrical capacitance with the target.

High-precision capacitive displacement sensors are used mainly for industrial process management. Lower-precision variants are much less expensive and can be used as **object presence** sensors to determine if an object is anywhere within a specified range.

A typical maximum range would be 10mm. For larger distances, optical and ultrasound sensors are more appropriate.

A selection of cylindrical sensor probes is shown in Figure 5-9.



Figure 5-9 *Some high-precision capacitive displacement sensors from Lion, which builds them into cylindrical probes ranging from 3mm to 18mm in diameter.*

Applications

The high-precision variant of this type of sensor is commonly used during the production of small devices, such as disk drives. It can also measure vibration of a rotating metal part, such as a motor shaft, and may maintain automatic focus of a microscope.

Lower-precision variants can be used for applications such as counting objects on a conveyor.

When used to measure materials thickness, the sensor finds applications in checking automobile brake rotor fabrication and the thickness of silicon wafers.

How It Works

When two plates of electrically conductive material are placed opposite each other, they possess capacitance. This means that they have an electrical storage capacity enabled by accumulation of opposite charges on each plate.

The capacity is directly proportional to the plate area, inversely proportional to the distance between the plates, and is affected by the medium separating the plates, known as the *dielectric*.

If the plate area and dielectric remain constant, the distance between the plates will be the only factor affecting the capacitance. Therefore, the distance between the plates can be calculated by measuring the capacitance.

Measurement can be performed by evaluating the *displacement current* that passes through the dielectric from one plate to another when a pulse of voltage is applied. (Hence the term "capacitive displacement" in the name of this type of sensor.)

A detailed explanation of displacement current is included in the second edition of *Make: Electronics*.

The sensor itself functions as one plate of the capacitor while the target functions as the opposite plate. Alternating current is applied as a rapid series of pulses, and the current that passes between the plates is proportional to the distance between them.

Ideally, the target should be grounded to the current source. However, since AC is being used, capacitive coupling of the target to the current source is also possible, so long as the additional capacitor has a value of 0.1µF or higher.

Sources of Error

To obtain a meaningful measurement, the electric field from the sensor is focused on the target. Some dispersion will still occur, and the combination of sensor and target must be compatible. A target typically should be flat and should have a larger surface area than the sensor.

Humidity can affect sensor performance, as it changes the value of the dielectric. Temperature can affect performance, partly because it causes small dimensional variations in the sensor and the target.

The surface of the sensor and the surface of the target should be precisely parallel, because the spot where the field hits the target will be elongated if the target is tilted relative to the sensor. Elongation increases the capacitive area and affects the accuracy of measurement.

This type of sensor can also measure the thickness of a nonconductive material, if the material is a thin sheet that can be interposed between two sensors. In this mode the material functions as a dielectric, and its thickness will affect the AC current passing through it.

While lower-precision capacitive displacement sensors are relatively unusual, they can potentially serve as a relatively affordable and simple **object presence** sensor, so long as the target is conductive and will not be damaged by passing a small alternating current at a relatively low voltage.

Values

A high-precision capacitive displacement sensor can measure distances usually ranging from 0.25mm to 10mm with an accuracy that can be better than 0.05mm. High voltages are not required, with a supply of plus-or-minus 15V being common.

The sensing element, often referred to as a *probe*, is usually plugged into a custom-designed control unit that converts the capacitance measurement into a variable output voltage. The performance is then expressed in millimeters per volt. Thus if the voltage varies by 5V over a distance of 1mm, the sensor is rated as providing 0.2mm per volt.

What Can Go Wrong with Optical and Ultrasound Proximity Sensors

Object Too Close

Because both types of proximity sensors (ultrasonic and infrared) may include emitters that are angled toward the distance range for which they are designed, they may fail to “see” an object that is closer. Consequently the sensor will provide no response, or may detect a different object that is further away. In either case, if the sensor is being used on a moving device, the device may collide with the undetected near object.

Multiple Signals

If two or more sensors and emitters are used concurrently, their combined signals can interfere with each other and create inaccurate readings.

Inappropriate Surfaces

Ultrasonic proximity sensors are intended to identify a single object that is closer to the sensor than other objects, within a narrow beam dispersion angle. Multiple objects, complex surfaces, soft surfaces such as clothing or furnishings, or an unusual configuration of interior walls can create inaccurate readings.

Infrared sensors may be unable to “see” liquids or transparent objects, and may give different assessments of distance depending on the properties of a surface. Human skin, for example, is a poor reflector, as it absorbs some infrared radiation.

Environmental Factors

An ultrasonic transducer uses a very small moving diaphragm to generate sound. Like any system containing moving parts, it will be vulnerable to moisture or excessive humidity, and may need to be protected.

After a device is built and tested indoors, in a controlled environment, it is likely to behave differently if it is moved outside where the temperature is significantly higher or lower.

Deterioration of LEDs

As noted in the section on presence sensors (see Chapter 3), LEDs tend to suffer from gradual reduction in light output over time. The performance of an infrared proximity sensor may deteriorate over a period of years, depending on how intensively it is used.

linear position sensor

A **linear position** sensor may also be described as a *linear displacement sensor* or a *linear position transducer*. It is sometimes categorized as a type of **proximity** sensor, but in this Encyclopedia a proximity sensor emits a signal and receives an echo to measure the distance from itself to an object. By comparison, a linear position sensor measures the position of a sliding object within a stationary enclosure.

An **object presence** sensor can be considered as a form of linear position sensor, but it only responds to the presence of an object, without measuring its position.

OTHER RELATED COMPONENTS

- **proximity** sensor (see Chapter 5)
- **object presence** sensor (see Chapter 3)
- **rotary position** sensor (see Chapter 7)

What It Does

Control of a mechanical device may require accurate and timely information about the position of a movable part in the device. A **linear position** sensor can be used for this purpose.

Three attributes are likely to be of interest:

- Position
- Direction of motion
- Speed of motion

Typically a linear position sensor measures only the first attribute. Additional electronics may calculate the second and third attributes by taking multiple position readings. Thus a *speed sensor* is very likely to be built around a position sensor, and therefore this Encyclopedia does not have a separate entry for speed sensors.

Applications

Robotic arm positioning, wing flap and rudder positions on an aircraft, computer-controlled machine tools, 3D printers, and automobile seat position sensors are some of the many applications.

Schematic Symbol

In a schematic, a linear position sensor may be represented by symbols for the sensing elements that are inside it (potentiometer, LED, phototransistor, or others).

How It Works

Linear potentiometers, *magnetic linear encoders*, *optical linear encoders*, and *linear variable differential transformers (LVDTs)* are described here. Other options are available, but they tend to be more specialized, and are not included.

Linear Potentiometer

For a full description of **potentiometers**, see Volume 1.

A linear potentiometer, often referred to as a *slider potentiometer*, contains an electrical resistance in the form of a straight section of *track.* The track may be a strip of *resistive polymer* or (less often) may consist of an insulator with a coil of nichrome wire wrapped around it.

For sensing purposes, the potentiometer is wired as a voltage divider, and a fixed potential is applied across its full length, as shown in Figure 6-1. A *wiper* slides along the track, sensing a voltage that varies linearly with the wiper's position. Output from the wiper can be used directly to control an analog indicator such as a meter, or can be processed by an analog-to-digital converter.



Figure 6-1 *A linear potentiometer can consist of a fixed track with a known voltage applied at each end, and a movable wiper.*

For audio applications, a slider potentiometer may have resistance that varies logarithmically with the position of the wiper. However, this type of component is not generally used as a position sensor.

For sensing purposes, the potentiometer is usually protected by a long, narrow box or tube through which a rod slides on sealed bearings. An example is shown in Figure 6-2.



Figure 6-2 *A linear potentiometer contained in a tube with sealed bearings.*

Small linear potentiometers for position sensing are available from companies such as Bourns. The one shown in Figure 6-3 is about 20mm long, and the rod that slides through it has a travel of approximately 10mm. The component is available with resistance values ranging from 1K to 50K, and its power rating is 1/8 watt. The manufacturer claims a life expectancy of 500,000 cycles.



Figure 6-3 *A miniature linear potentiometer. The body is about 20mm long.*

A linear potentiometer is simple, inexpensive, compact, and requires few additional components. The track contains a lubricant, but inevitably some wear occurs as a result of motion of the wiper. Life expectancy will be reduced by vibration or by contamination with dirt or moisture.

A linear potentiometer may rarely be described as a *linear potentiometric sensor*.

Magnetic Linear Encoders

A ferrous rod or strip can be magnetized with alternating north and south poles. When it slides past a single bipolar Hall-effect sensor, it generates a pulse train from the sensor that can be interpreted to provide positional information. The principle of the component is shown in Figure 6-4. (Magnetic rotary encoders also exist; see "Rotary Encoders".)



Figure 6-4 *When a strip magnetized with alternating north and south poles slides past a sensor, the pulse train from the sensor can be decoded to indicate the relative position of the strip.*

The sensing element may be described as a *read head*. If two are used, with a spacing equal to half the interval between the north and south poles on the strip, the phase difference between the pulse trains from the sensors will indicate the direction in which the magnetized strip is moving. This is shown in Figure 6-5.

The combination of pulse trains is known as *quadrature*, because there are four possible combinations: A and B both high, A and B both low, A high and B low, or A low and B high. The same principle is used in an optical rotary position sensor; see Figure 7-6.

This type of linear position sensor is often described as a *magnetic encoder*, meaning that the position of the sliding part is encoded in a series of pulses. Relatively high resolution is possible, as the north and south poles on a strip of ferrous material can be as close as 2mm. Optical encoders may use the same principle; see "Optical Linear Encoders".



Figure 6-5 *Pulse trains from Hall-effect sensors A and B are shown in green. The phase difference between them can be interpreted to show the direction in which the magnetized strip is moving.*

The sensor can be built into a module containing an analog-to-digital converter that provides numeric output defining the position of the read head.

In an *absolute* magnetic encoder, nonvolatile memory can store the digitized position when the device is switched off. An *incremental* magnetic encoder does not store this information, and will require at least one additional *home sensor* to detect when the encoder is at either end of its travel. At power-up, an initialization routine moves the magnetized strip until the home sensor is triggered.

For details of Hall-effect sensors see "Hall-Effect Sensor".

Optical Linear Encoders

The operation of an optical linear encoder is identical to that of the magnetic linear encoder described immediately above, except that a sliding *optical grating* is used in conjunction with a light source and a detection device such as a **phototransistor** or **photodiode** that functions as the read head. The principle is shown in Figure 6-6. The grating may be described as a *codestrip*.


Strip with optical grid alternating transparent and opaque sections
Phototransistor
Infrared LED

Figure 6-6 *An optical linear encoder uses the same general principle as a magnetic linear encoder.*

For details of phototransistors, see Chapter 22. For details of photodiodes, see Chapter 21.

An example of a low-cost optical linear encoder is the Avago HEDS-9 series, which consists of a horseshoe-shaped module with an LED in one arm and an array of photodiodes in the opposite arm. When a codestrip passes between the arms, the module emits two pulse trains from internal comparators. The pulse trains are 90 degrees out of phase, and can be interpreted to show which way the codestrip is moving.

These sensors have a body measuring approximately 10mm wide and are designed to read opaque/transparent intervals ranging from 1.5 to 7.87 cycles per millimeter. The output rate can be as high as 20kHz. No pullup resistor is required on the output, as a 2.5K resistor is integrated.

A *codewheel* may be used, in which case the module senses rotation instead of linear motion. This is described in detail in the entry on **rotary position** sensors. See Chapter 7.

Linear Encoder Applications

Optical or magnetic linear encoders are found in some laboratory equipment, machine tools, and industrial robots. The mean time between failures can range from 100,000 to 1,000,000 hours. Optical encoders must be sealed to provide good protection from dust and dirt.

Linear Variable Differential Transformers

This type of sensor, often referred to by the acronym LVDT, tends to be used in industrial environments where great reliability is required under severe conditions. Examples are high-temperature steam valves and nuclear reactor control mechanisms. However, the robust, frictionless design suggests other possible applications, and custom fabrication is a possibility.

Figure 6-7 illustrates the general principle. Three coils are wound sequentially around a (nonmagnetic) stainless-steel tube, enclosed in a second tube also made of stainless steel. The coils act as transformers with the variable voltage ratio determined by the position of a solid iron armature that slides through them.

The center coil is the primary winding, to which AC is applied between 2kHz to 50kHz, depending on the application. (The frequency must be at least ten times the maximum rate of motion of the armature.) The iron armature is attached to a nonmagnetic rod. The voltages on the secondary windings provide the output from the sensor.

While more than one wiring arrangement is possible, the most common schematic is shown in Figure 6-8. The secondary coils are in series, with one of them reversed, so that the phase of the output is inverted as the armature moves from one end of its travel to the other. The phase detector responds to the phase difference by creating a DC output that varies with movement of the armature. All the functions shown in the schematic are available on a single integrated circuit chip.


Secondary Winding
Primary Winding
Secondary Winding
Iron Armature
Stainless Steel Casing
Nonmagnetic Rod

Figure 6-7 *Cutaway drawing showing the internal design of a linear variable differential transformer, in which the position of a sliding iron armature determines the voltage induced in the secondary windings.*


Phase Detector
Bipolar DC Output
Oscillator

Figure 6-8 *Typical schematic for using a linear variable differential transformer.*

An example of a linear variable differential transformer is shown in Figure 6-9.



Figure 6-9 *External view of a linear variable differential transformer.*

What Can Go Wrong

Mechanical Issues

Any sliding mechanism will involve friction, and will be vulnerable to wear and tear, resulting in looseness that will degrade its accuracy. In addition, optical systems are vulnerable to dust and dirt.

LED Longevity

Light output of an LED diminishes over a period of years if the LED is "always on." This will limit the life of the sensor.

rotary position sensor

7

Alternative terms for **rotary position** sensor are *rotary sensor*, *rotational position sensor*, *angular position sensor*, and *angle sensor*.

The terms *rotary* and *rotational* are used interchangeably. In this entry, an attempt has been made to use the term that is most common for each specific application. For example, "rotary position sensor" versus "rotational encoder."

A few sensors are available that specifically measure *rotary speed*, but generally a rotary speed sensor uses information from a rotary position sensor. Therefore, this Encyclopedia does not include a separate entry for rotary speed sensing.

A **rotational encoder** can be used as a rotary position sensor. It is mentioned briefly here but is described in more detail in Volume 1 of this Encyclopedia in the entry describing **switches**.

OTHER RELATED COMPONENTS

- **linear position** sensor (see Chapter 6)

What It Does

Control of a mechanical device may require accurate and timely information about the orientation of a rotating part in the device. A **rotary position** sensor can be used for this purpose.

A sensor may be capable of measuring three attributes:

- Angular orientation
- Direction of rotation
- Speed of rotation

Typically a rotary position sensor measures only the first attribute. Additional electronics are required to calculate the second and third attributes by taking multiple position readings. Thus a *speed sensor* is very likely to be built around a position sensor, and therefore, this Encyclopedia does not have a separate entry for speed sensors.

Applications

In robotics, a rotary position sensor is commonly used to show the orientation of a pivoting arm or strut. It can also be used as a limit switch on a motor.

Specific applications include solar array positioning, remotely piloted vehicles, guidance and navigation, antenna positioning, and wind turbine pitch control.

Pulses from a rotary position sensor are used to measure speed of rotation in vehicles, industrial processes, and aviation. Small rotary speed sensors are built into devices such as cooling fans and computer hard drives.

Schematic Symbol

In a schematic, a rotary position sensor may be represented by symbols for the sensing elements that are inside it (potentiometer, LED, phototransistor, and others).

Potentiometers

Single-turn and multiturn potentiometers may be used as rotary position sensors. For basic information about **potentiometers**, see the entry describing this component in Volume 1.

Arc-Segment Rotary Potentiometer

An *arc-segment rotary potentiometer* is often referred to simply as a “potentiometer,” as this type is more common than the multiturn type or the linear type. When used as a sensor, it can measure a turn angle that is less than 360 degrees.

This component contains a resistor in the shape of an arc, referred to as the *track*. It may be a strip of *resistive polymer* or (less often) may consist of an insulator with a coil of nichrome wire wrapped around it.

For sensing purposes, the potentiometer is wired as a voltage divider, and a fixed potential is applied along the full length of the track, as shown in Figure 7-1. A *wiper* slides along the track, sensing a voltage that varies linearly with the wiper’s angular position. Output from the wiper can be used directly to control an analog indicator such as a meter, or can be processed by an analog-to-digital converter.

For audio applications, an arc-segment potentiometer may have resistance that varies logarithmically with the position of the wiper. However, this type of component is not generally used as a position sensor.

Low-cost potentiometers were traditionally used as volume or tone controls in stereo systems. When a potentiometer is designed for use as a sensor, it tends to be more ruggedly built and better protected against dust, dirt, and moisture. Its advantages are that it is simple, inexpensive, compact, and requires few additional components.



Figure 7-1 *An arc-segment potentiometer consists of a fixed track in the shape of an arc with a known voltage applied at each end, and a movable wiper.*

The major disadvantage is that although the track contains a lubricant, some wear will gradually result from friction with the wiper. Life expectancy will be further reduced if there is vibration or contamination with dirt or moisture.

End Stops

An arc-segment potentiometer usually has *end stops* to prevent the wiper from running off either end of the track. Typically, these stops limit rotation to around 300 degrees.

A few arc-segment potentiometers allow unrestricted rotation. The Bourns 6639 series is an example, although the wiper still passes through a “dead zone” of 20 degrees between the start and end of its track. An application for this type of potentiometer could be as a direction sensor for a weather vane.

Multiturn Rotary Potentiometer

A spiral track, which resembles a coil spring, enables a rotary potentiometer to make multiple turns. The wiper rotates inside the track and follows its contour. A potentiometer of this type will still be calibrated in degrees; thus, a 10-turn component may be listed as allowing an *electrical travel* of approximately 3,600 degrees.

The exterior of a multiturn rotary potentiometer is shown in Figure 7-2.



Figure 7-2 *A multiturn rotary potentiometer. Each pair of solder tags is attached internally to one end of the internal coiled track. The smaller tag at the far end connects with the wiper.*

A simpler type of multiturn potentiometer is intended for use as a trimmer—a small potentiometer that can be mounted on a circuit board to allow adjustment or calibration, often during the manufacturing process. This type of trimmer contains a worm gear that engages with a spur gear internally. The wiper is mounted on the spur gear. It has no applications as a sensor, but is mentioned here to avoid ambiguity, as it is probably the component that is most commonly referred to as a "multiturn potentiometer."

Magnetic Rotary Position Sensor

Externally, a modern magnetic rotary position sensor may look very much like an arc-segment rotary potentiometer. Internally, a permanent magnet is attached to the base of the shaft, and one or more **Hall-effect** sensors are mounted on a small circuit board immediately below the magnet, in the bottom of the enclosure. A simplified diagram appears in Figure 7-3.



Figure 7-3 *Simplified interior view of a magnetic rotary position sensor.*

For more information about Hall-effect sensors, see "Hall-Effect Sensor".

A magnetic rotary position sensor may be described as a *noncontacting* sensor. Two views of an example are shown in Figure 7-4.



Figure 7-4 *Two views of a Bourns AMS22 magnetic rotary position sensor.*

The AMS22 sensor shown in Figure 7-4 has an analog output ranging from 0.1VDC to 4.9VDC when powered with 5VDC. A noncontacting sensor of this type will cost three to four times as much as a conventional potentiometer, but has the great advantage of extreme durability, with the manufacturer claiming a life of 50 million shaft rotations. A disadvantage is its low-current output, limited to 10mA. The maximum rotation speed of its shaft is 120rpm.

Rotary Position Sensing Chips

Chips of the type used in a magnetic rotary position sensor are available as individual components, many of which have advanced features. For example, the AM8192B angular magnetic encoder by RLS is a 44-pin surface-mount chip containing Hall sensors that detect the orientation of a permanent magnet above or below the chip. Various outputs provide information such as sine or cosine of the turn angle, incremental pulses, and digitized output via an SPI interface.

Rotary Encoders

Many rotating position sensors communicate their angle of rotation with an output that consists of a pulse train or some other coded signal. This type of rotary sensor is known as a *rotary encoder* or *rotational encoder*. (Linear encoders also exist; see "Magnetic Linear Encoders".)

The simplest version of this component is a *mechanical encoder* containing two small electromechanical switches that are activated, out of phase, by a toothed wheel attached to the rotating shaft. This component is described in detail in Volume 1 of the Encyclopedia, where it is categorized as being a form of **switch**. Its low cost and simplicity has made it popular for rotary controls on car radios and small stereo systems, but its switches have a limited life expectancy and create a "noisy" output that must be *debounced* if connected with a logic chip or microcontroller. Typically the microcontroller will include a pause of up to 50ms in its program code to allow time for the switch contacts to settle (although some manufacturers claim only 5ms).

Confusingly, a mechanical encoder is often identified only as a "rotational encoder," even though optical and magnetic rotational encoders also exist, as described immediately below. As a general rule, if a component is described simply as a rotational encoder, it probably contains electromechanical switches.

Optical Rotary Encoders

This type of component works on the same principle as an *optical linear encoder* of the type described in "Optical Linear Encoders". The difference is that a *codewheel* is used instead of a *codestrip*. Typically the codewheel is supplied by the manufacturer of the component that is designed to read it.

A *transmissive* codewheel is shown in Figure 7-5. The distance between the light emitter and the light detector has been exaggerated in this diagram for clarity.



Figure 7-5 *A light-transmissive codewheel for use in an optical rotary encoder.*

Some optical rotary encoders use a *reflective* codewheel, in which case alternating sections of the wheel are light-absorptive and light-reflective, and the emitter and detector are both on the same side of the wheel.

If only one light emitter and light detector are used, the pulse train from the sensor reveals how many increments the wheel has turned relative to its previous position.

A single sensor cannot indicate the direction of rotation, but if a second emitter-sensor pair is added, 90 degrees out of phase with the first, a microcontroller can assess the phase difference between pulse streams to determine which way the wheel is turning. This principle is illustrated in Figure 7-6 where one transmitter-detector pair is located in position A and another is in position B. The resulting pulse trains, for clockwise and counterclockwise rotation of the wheel, are shown in green. The combination of pulse trains is known as *quadrature*, because there are four possible combinations: A and B both high, A and B both low, A high and B low, or A low and B high.



Figure 7-6 *With transmitter-detector pairs mounted at positions A and B, the phase difference between their pulse trains can show the direction of rotation of the wheel.*

This is the same principle as illustrated for a magnetic linear position sensor in Figure 6-5.

An alternative system of quadrature for an optical rotary encoder uses two separate tracks on the disc, each having an equal number of opaque and transparent sections, but half an interval out of phase.

Any system that reveals the relative motion of the wheel, but cannot determine its absolute angular position, is an *incremental sensor*.

Optical Products

High-end optical rotary encoders may use discs with as many as 600 sequential opaque and transparent segments to provide extremely high resolution. They are outside the scope of this Encyclopedia.

Moderately priced optical encoders are available as shaft-driven assemblies very similar in external appearance to potentiometers. Typically they have four terminals, one pair for power and ground connections and another pair for quadrature output from the two internal sensors, usually identified as A and B in datasheets. Some encoders also contain an on-off switch that is activated by pressing the shaft, in which case two additional terminals will be provided.

Bourns is a leading manufacturer of this type of encoder, an example being the EM14, which is mounted in a box-shaped body measuring 14mm square. It uses a 5VDC power supply and provides pulses of 4VDC minimum with intervals of 0.8VDC maximum. Variants are available with 8 to 64 pulses per revolution. Intended for audio applications, this type of encoder has a maximum rotation speed of 120rpm.

An example of an optical rotary encoder from a German manufacturer is shown in Figure 7-7. Its resolution is 25 pulses per rotation. The rectangular package measures approximately 19mm × 25mm. The power supply can be 3.3VDC or 5VDC.

Optical rotary encoders of this type cost about five times as much as mechanical rotary encoders at the time of writing, but their longevity and their clean output signals make them an attractive alternative, and the price difference may diminish over time.



Figure 7-7 *A compact incremental optical rotary encoder in the MRB25 series from Megatron Elektronik AG & Co.*

Encoders such as the Avago HEDS-9 series are not protectively enclosed, and require assembly with a codewheel supplied by the manufacturer. See Figure 6-6 for additional information.

A more basic optical rotary encoder, shown in Figure 7-8, is sold by Cytron Technologies as an *optical switch* mounted on a small board, with a separate codewheel consisting of a slotted disc. This low-cost kit is intended for use in DIY robotics. More information about optical switches will be found in the entry dealing with **optical presence** sensors. See Figure 3-3.



Figure 7-8 *A bare-bones optical encoder for DIY robotics.*

Computer Mouse Principles

The original design of a computer mouse, with a hard rubber ball, contained two optical rotary encoders oriented at right angles to each other. Each of them used a transmissive codewheel. The rolling ball turned the codewheels as the mouse was moved across a desktop, and electronics in the mouse converted the outputs from the encoders into a pulse train that could be interpreted by a computer. Figure 7-9 shows the primary components.



Figure 7-9 *From Wikimedia Commons, this rendering by Jeremy Kemp shows (1) rotation of the ball, (2) a roller touching the ball, (3) a transmissive optical codewheel, (4) an infrared LED that shines through a second codewheel, and (5) a sensor detecting the pulses of light.*

An *optical mouse* works on a different principle, maintaining a monochrome image of the desk surface on an optical array that functions like a very low-resolution camera sensor. Electronics in the mouse detect displacement of the image as the mouse is moved.

Rotational Speed

Incremental rotary encoders, which only supply relative data, are adequate in many applications, especially speed measurement, where a microcontroller can compare a pulse stream from a sensor with a target frequency, and can also provide feedback to control motor speed appropriately. This is convenient when a stepper motor is being used, or a DC motor that is controlled with pulse-width modulation. (See the entry on **motors** in Volume 1.)

Toothed wheels or magnetized wheels are commonly used to measure speed of rotation in applications ranging from automobile transmissions to computer disk drives.

While a second sensor can be added to determine the direction of rotation, this still does not provide information about the absolute orientation of a part.

Absolute Position

If associated electronics are equipped with nonvolatile memory, it may be used to store a sensor-wheel position from one session to the next. This may be sufficient in noncritical applications such as volume control in a car radio or stereo system.

Alternatively, an additional single window in an optical wheel can activate a *home sensor*. When the device is powered up, the wheel is turned until the home sensor is triggered, at which point the orientation of the wheel is known, and subsequent pulses from rotation sensor(s) will add or subtract angular information.

The pulse generated by a home sensor may be described in datasheets as a *reference signal* or *index signal*. In the early days of desktop computers, each 5.25-inch floppy diskette was perforated with an index hole for this purpose.

The Gray Code

For greater reliability in determining absolute position, an optical wheel can be divided into several concentric tracks, each of which contains a different coded sequence and is assigned its own light emitter and light sensor. The sensors are arranged in a radial line to scan the disc as it rotates. Since each detector will provide either a signal or no signal, output from the set of sensors can be combined to create a binary number.

Figure 7-10 shows binary codes from 0000 through 1111, corresponding with decimal numbers 0 through 15, where a white square is equivalent to a numeral 1 and a black square is equivalent to a numeral 0.



Figure 7-10 *Binary codes from 0000 through 1111, using white to represent 1 and black to represent 0.*

Figure 7-11 shows this system mapped onto a codewheel. The red circles indicate the locations of four stationary light detectors, which begin by providing a reading of 0000, since they coincide with four opaque areas of the wheel. Now if the wheel makes 1/16th of a full rotation in the direction of the arrow, the detectors will register 0001. If the wheel continues to rotate, the detectors will count in binary up to 1111 before the sequence repeats.

The problem with this design is that small manufacturing inaccuracies and other imperfections will result in some light detectors responding fractionally more quickly than others as the wheel rotates. This will occur in transitions where two or more adjacent segments of the wheel change between transparency and opacity. For instance, where 0011 is followed by 0100, transient values of 0010, 0001, 0111, 0110, or 0101 are possible. Although they will be brief, these values may trigger associated electronics.



Figure 7-11 *The binary sequence mapped onto a codewheel as areas of opacity and transparency. Red circles indicate light detectors.*

To eliminate this problem, a different code sequence can be used in which only one of the four sensors is allowed to make a transition from each value to the next. This is called a *Gray code*, and eliminates the issue of simultaneous transitions. A commonly used Gray code is shown in Figure 7-12.



Figure 7-12 *A Gray code that allows only one binary digit to change in each transition from one value to the next.*

Magnetic Rotary Encoders

If a ferrous wheel is magnetically polarized in multiple domains, its rotation can be detected by a Hall-effect sensor in much the same way that a wheel divided into transparent and opaque sections can be assessed by light detectors and emitters. This is illustrated in Figure 7-13, where magenta and cyan bands indicate north and south magnetic poles.



Figure 7-13 *A Hall-effect sensor can detect the rotation of a wheel that is divided into multiple north and south magnetic poles.*

See "Hall-Effect Sensor" for information about Hall-effect sensors.

An additional Hall sensor can be added, offset from the first, as in Figure 7-14. Once again the phase difference between the pulse trains can be used to determine the direction of rotation.



Figure 7-14 *Direction of rotation of the wheel can be deduced from the phase difference between the pulse trains from two sensors.*

Alternatively, a toothed wheel can be used, as suggested in Figure 7-15.



Figure 7-15 *A toothed wheel can trigger a Hall sensor if the teeth are magnetized.*

Another option is to mount a pair of magnets on a nonmagnetic wheel, with a Hall-effect sensor in the center. If it is a sensor with an analog output, the voltage will fluctuate smoothly between positive and negative, relative to the power supply for the sensor. Alternatively, a bipolar Hall-effect sensor can be used to provide a binary output. The concept is illustrated in Figure 7-16. An advantage of this configuration is that it provides approximate information about the absolute position of the wheel.

The two magnets will provide usable linear sensor outputs over a span of plus-or-minus 30 degrees of rotation, approximately. Additional magnets or sensors can produce a more complex output that would be decoded by a microcontroller.

How to Use It

An optical or rotary encoder is well suited for use with a microcontroller program that can count pulses, compare pulse trains, or interpret a Gray code. The microcontroller then takes appropriate action. For example, if a rotational encoder is used to control the gain of an audio amplifier, the microcontroller determines the direction and angle through which the encoder turns, and can respond by changing the value of a **digital potentiometer** (see Volume 1).



Figure 7-16 *A Hall-effect sensor can detect the angle of rotation of a ring on which two magnets are mounted as shown.*

Integrated circuit chips are available to convert a sequence of quadrature signals into an up-pulse or a down-pulse, thus eliminating the chore of achieving this with a microcontroller program. The LS7183 by LSI Computer Systems is an example.

What Can Go Wrong

Wiring Errors

If two sensors are used to detect the direction of rotation of a rotary encoder, and outputs from the sensors are accidentally swapped, the component will seem to work normally except that the indicated direction will be inverted.

Coding Errors

Microcontroller code that interprets quadrature signals must be fast enough to keep up with the pulse streams. If a microcontroller is performing other tasks, an interrupt may be necessary for processing the rotational data. This should not be a significant problem when interpreting human input from a knob or dial, but for a motor-driven encoder, pulse counting in hardware may be a better alternative.

Ambiguous Terminology

Rotational encoders are often referred to simply as “encoders,” because they are more common than linear encoders. When searching for an encoder, check each datasheet carefully to determine which type you are dealing with.

8

tilt sensor

A *tilt switch* is defined here as an electromechanical switch, while a *tilt sensor* uses electronics. Both types are included in this entry.

A *tipover switch* is very similar to a tilt switch and uses the same principles. Therefore, it is included in this entry.

Some manufacturers' datasheets refer to tilt sensors as *tip sensors*. Some Asian supply catalogues refer to tilt switches as *breakover switches*.

An **accelerometer** can measure the angle at which it is held relative to the downward force of gravity, but it has additional capabilities. Therefore, it has its own separate entry in this Encyclopedia.

An *inclinometer* measures the incline, or positive slope, from an observation point to the top of an object such as a building or tree. The height of the object can be calculated from the angle. A *clinometer* can additionally measure a decline, or negative slope. These measurement devices are fully featured products as opposed to sensors, and are not included in this Encyclopedia.

OTHER RELATED COMPONENTS

- **accelerometer** (see Chapter 10)
- **vibration** sensor (see Chapter 11)

What It Does

Three principal types of tilt sensor exist.

1. Single axis, single output. The sensor responds to being tilted around one horizontal axis, relative to the downward force of gravity.
2. Dual axis, dual output. The sensor contains two sensing elements at 90 degrees to each other. Each has an output determined by its angle of tilt from vertical around one axis.
3. Dual axis, single output. A single sensor responds to an angle of tilt from vertical around any horizontal axis.

A *tilt switch* is usually of the third type, and is defined here as containing an electromechanical or electronic switch that opens or closes a connection. Most tilt switches are SPST (normally open) or SPST (normally closed). A minority are DPDT.

A *tipover switch* is a type of high-current tilt switch that cuts power to a device such as an electric heater when it is tipped over.

This Enclopedia defines a *tilt sensor* as being an electronic component, as opposed to an electromechanical component. The distinction is often observed in datasheets, but not always.

Schematic Symbol

No specific schematic symbol is generally used for any variant of a tilt sensor. It can be represented with an annotated switch symbol.

How It Works

Because a tilt switch is a simpler device than a tilt sensor, it will be described first.

The most common type of tilt switch consists of a cylindrical metal or plastic enclosure, often measuring about 5mm by 15mm, containing two spherical steel balls that may be nickel-plated or gold-plated. When the switch is tilted, the balls eventually run downhill, and the lower ball completes an electrical connection between two contacts or between a single contact and the metal enclosure of the switch. The second ball is included to add weight and suppress vibration in the first.

Figure 8-1 shows a switch manufactured by Comus Global, rated for 0.25A at 60VAC or 60VDC, maximum. The body of the switch measures approximately 10mm x 5mm, and the switch is activated when tilting -10 degrees from horizontal. It is deactivated when tilting +10 degrees. A scale drawing of the interior is shown in Figure 8-2.



Figure 8-1 *The CW1300 tilt switch manufactured by Comus Global.*



Figure 8-2 *Interior of the CW1300 tilt switch, from a scale drawing supplied by the manufacturer. The lower lead is welded to the shell of the sensor. The leads may be inserted in a circuit board.*

Figure 8-3 shows three common internal configurations of a generic tilt switch. The top version has axial leads and uses the metal shell of the switch to complete the circuit. The center version has radial leads, with a plastic shell. The bottom version has radial leads, one of which is attached to the metal shell to complete the circuit.



Figure 8-3 *Three variants of a generic ball-operated tilt switch. The graph-paper scale is in millimeters.*

Figure 8-4 shows the parts of a disassembled tilt switch.

Simplified Version

Where size is not a significant consideration, a tilt switch can be created by attaching a pivoting, weighted arm to a small snap-action switch.

Applications

An old-style (nonelectronic) thermostat may contain a tilt switch attached to the end of a bimetallic strip coiled into a spiral. When the strip bends in response to a drop in temperature, the switch closes its contacts, activating a relay that starts a heating unit. If the temperature rises, an additional set of contacts in the same relay may activate an air-conditioning unit. In old thermostats, the tilt switch may contain mercury in a glass tube, which should be handled with caution.



Figure 8-4 *At right, a tilt switch. At left, the cap removed, and the two balls that make internal contact. The background grid is in millimeters.*

A tilt switch may detect the opening of a door or window in a simple alarm system.

Tilt switches have been used in automobiles to switch on the interior light in the trunk when its lid is opened.

A normally closed tilt switch is often used to stop the inflow of granular material to a bin when it is almost full. This is colloquially known as a *bin switch*. In industrial applications of this kind, the switch is activated by a long lever that has a ball mounted at the end. The switch assembly is physically large. See Figure 8-5.

A normally open tilt switch may operate a valve or start a pump when the liquid in a tank drops below a certain point. If the switch uses a float to sense the level of the liquid, it is often known as a *float switch*. This is described in the entry on liquid level sensors. See Chapter 15.



Figure 8-5 *The flow of granular material into a bin can be sensed and stopped by a tilt switch of this type, often known as a bin switch.*

A *tipover switch* may use the simplified system of a weighted arm that activates a snap-action switch. When used in conjunction with a room heater, the switch must handle substantial current.

A motorcycle may contain a tipover switch to stop the electric fuel pump if the motorcycle falls on its side.

Four tilt switches placed in a cross-shaped pattern on a flexible mount can be used as the basis of a very simple game controller, with a joystick mounted in the center.

Variants

The three configurations of ball-type tilt switches shown in Figure 8-3 are functionally interchangeable and can be chosen for convenience of their leads in fitting the circuit.

Mercury Switches

Early tilt switches contained a blob of mercury in a glass bulb. When the bulb was tilted, the mercury rolled to the end and made an electric connection between two metal contacts that penetrated the bulb.

A small mercury switch is shown in Figure 8-6. This type of sensor became less common after many countries classified mercury as an environmental hazard and established regulations restricting its use.



Figure 8-6 *Small mercury switch rated for 0.3A at 24VDC or 24VAC. Larger mercury switches can switch more power; 1A at 230V is common. The background grid is in millimeters.*

Mercury is an excellent electrical conductor. It remains in a liquid state between about -38 degrees Celsius and +356 degrees Celsius, and has very high surface tension, encouraging it to form a single blob instead of breaking up into small droplets. Because free space in the bulb is filled with an inert gas to prevent oxidation of the electrodes, a mercury switch can have a very long operating life. In the United States in the 1970s, some light switches were sold containing mercury switches with a claimed life expectancy of 100 years.

Pendulum Switch

This type of switch, now relatively rare, was found in vintage pinball machines. It consists of a pendulum about 5cm long, suspended inside a steel ring about 1cm in internal diameter. If the machine was rocked sufficiently to bring the pendulum in contact with the ring, the game was cancelled and the word "Tilt" appeared on the display. Consequently this was referred to as a tilt switch, although really it was a form of **vibration** sensor with a long period of oscillation.

Magnetization

Some tilt switches use a steel ball that is weakly magnetized, so that it will seat itself more firmly when it rolls into a circular depression or ring. This type of switch must be tilted back through a larger angle to dislodge the ball. Therefore it will exhibit greater *hysteresis*.

Tilt Sensors

Unlike a tilt switch, a tilt sensor is not built around an electromechanical switch.

The principle of a rolling ball has been miniaturized and encapsulated in a small enclosure (10mm square or smaller), in which the ball rolls to interrupt a beam from an internal LED shining on a phototransistor. Examples are found in the Panasonic AHF series. Internal circuitry ensures a clean on-off signal, free from the switch bounce that is a problem in basic ball-type tilt switches. However, the switch requires a power supply, and the open-collector output must be used with a pullup resistor. By comparison, a simple electromechanical tilt switch can be wired directly to the device that it controls.

Diagrams from the Panasonic datasheet show the three types of AHF sensor available for vertical, horizontal, and reverse mounting. In each case, the ball (dotted circle) rests in a shallow cup (dotted curve) where it obstructs the beam from an internal LED (not shown). See Figure 8-7. An exterior view of the AHF22 is shown in Figure 8-8.



Figure 8-7 *Three types of Panasonic tilt sensor, from the manufacturer's datasheet. See text for details.*



Figure 8-8 *Exterior view of the Panasonic AHF22 tilt sensor. The background grid is in millimeters.*

Two-Axis Tilt Sensors

The Rohm RPI-1035 is a surface-mount tilt sensor about 4mm square, with two phototransistor outputs that indicate which axis the sensor is tilting around. The outputs can be interpreted as a 2-bit binary number, with its four possible states indicating the rotation of the switch around two axes at 90 degrees to each other. Switches of this type were developed to indicate the orientation of consumer-electronic devices such as digital cameras, but more sophisticated sensors containing accelerometers are becoming price-competitive.

Surface-mount 2-axis tilt sensors have been made available on small breakout boards that are easy to use experimentally. An example is the Parallax 28036 shown in Figure 8-9.



Figure 8-9 *A 2-axis tilt sensor mounted on a breakout board available from Parallax.*

The behavior of the rolling-ball sensor at the heart of this board is shown in Figure 8-10. The sensor contains a square cavity in which the ball is depicted as a blue circle. At one corner of the cavity is a red LED, while two phototransistors, labeled A and B, are at the corners on the left and right. When the sensor is held as in section 1 of the figure, with the LED at the top and the ball resting at the bottom, both phototransistors have a high output as they receive light from the LED.

In section 2 of Figure 8-10, the sensor has been turned through 90 degrees. The ball now prevents light from reaching sensor B, while phototransistor A is still active. In section 3 of the figure, the sensor has been turned through another 90 degrees, so that the ball prevents light from escaping from the LED, and both phototransistors are now dark. In section 4, the ball obstructs phototransistor A but not phototransistor B.



Figure 8-10 *The rolling-ball sensor inside the Parallax 28036. See text for details.*

Suppose that the sensor is placed flat on a horizontal surface. The sensor will now respond to being tipped either way around two horizontal axes. This justifies its description as a 4-directional tilt sensor, although its design suggests that it may have been intended for use as described above, rotating through four positions around one horizontal axis.

Values

A heavy-duty tilt switch can be rated as highly as 10A at 240VAC. More commonly, a tilt switch about 15mm long can be expected to switch about 0.3A at 24VAC or 24VDC.

The *operating angle* is the angle through which the switch must be turned to activate it, relative to its normal rest position.

The *return angle* is the angle to which the switch must be returned to deactivate it. Hysteresis results from the return angle being smaller than the angle that activates the sensor.

Tilt sensors with an open-collector output will specify maximum forward current for the internally mounted LED (usually no greater than

50mA), the maximum collector-emitter voltage at the output (typically 30V), and the maximum collector current (often 30mA). An explanation of open-collector outputs is given in Appendix A (see "3. Analog: Open Collector").

How to Use It

An electromechanical tilt switch can be connected directly between a power supply and a device, so long as the device does not draw more current than the switch is rated to handle. Note that inductive loads such as motors draw an initial surge that can be at least twice the operational rating, while relays may be more likely to create a voltage spike when disconnecting. Switches should be chosen accordingly. For more discussion of this topic, see **switch** in Volume 1.

A small tilt switch can be used in conjunction with a relay or transistor to amplify its signal sufficiently to drive a larger load.

If an electromechanical tilt switch is connected to an electronic device such as a microcontroller or logic chip, output from the switch will have to be *debounced* to prevent a series of brief voltage spikes that can cause false triggering when the switch turns on or off. A debouncing logic circuit or chip can be used, or the program code in a microcontroller can introduce a wait period of up to 50 milliseconds to allow the contacts to settle.

Mercury switches are much less likely to create a noisy output than rolling-ball switches, and may require little or no debouncing.

For an application that must sense rotation around two or three axes, multiple single-axis tilt switches can be combined. A microcontroller or logic gates will be necessary to evaluate signals from the switches, to determine the orientation.

What Can Go Wrong

Contact Erosion

If a ball-type tilt switch is subjected to current that exceeds its specification, arcing may erode its contacts, and they will become less reliable, especially if the contacts are plated with a thin metallic film that is eroded. For additional information on arcing in switches, see the **switch** entry in Volume 1.

Random Signals

During the brief time when a ball-type tilt switch is turning from one position to the other, vibration of the ball(s) inside it is likely to create erratic, random signals. If the output from the switch is being evaluated by a microcontroller, a debouncing routine may be insufficient to prevent the random signals from being sensed, and some programming will be necessary to ignore the signals during this transitional phase. If the switch is connected directly to a relay, the intermittent signals may occur sufficiently rapidly that the relay will ignore them.

Environmental Hazard

A device that incorporates a mercury switch may have to be re-engineered in the future if the availability of mercury switches becomes unreliable as a result of tighter environmental regulations. For the same reason, the end user may have difficulty replacing a mercury switch if it fails. Therefore, a ball-type tilt switch should be used instead of a mercury switch in any newly designed device.

Requirement for Gravity

Because a tilt switch depends on gravity to roll a ball or move a blob of mercury, it will not work in low-gravity, reversed-gravity, or zero-gravity conditions—for example, in a rocket during the unpowered phase of ascent and descent, or in an aircraft that performs aerobatic maneuvers. Performance of a tilt switch in a vehicle that accelerates or decelerates suddenly may also be unreliable. Likewise, it cannot be used on a small boat.

Requirement for Stability

A tilt switch will tend to give erroneous results in a location where there is significant vibration or where the object containing the switch may be turned or repositioned unpredictably by the user.

gyroscope

Historically, a **gyroscope** always contained a spinning disc. Some devices for navigation still depend on rotating elements, but they are outside the scope of this Encyclopedia. This entry deals primarily with *vibrating gyroscopes*, also known as *resonator gyroscopes*, that are MEMS devices contained within silicon chips.

OTHER RELATED COMPONENTS

- **accelerometer** (see Chapter 10)
- **GPS** (see Chapter 1)
- **magnetometer** (see Chapter 2)

What It Does

A **gyroscope** resists rotation around any axis at right angles to its own axis of rotation or vibration. Consequently, if the gyroscope is allowed to move freely on gimbals in a sealed enclosure, the gyroscope will tend to maintain its orientation while the enclosure can rotate freely around it.

Taking this concept a step further, if the enclosure is mounted in an aircraft, the aircraft's rotation around two axes can be determined by referring to the gyroscope. If additional gyroscopes are added orthogonally to the first, the aircraft's rotation around all three axes can be determined.

A gyroscope does not measure linear motion in any direction, or any static angle of orientation.

Schematic Symbol

A chip-based gyroscope, magnetomer, or accelerometer may be represented in a schematic as a rectangular box containing abbreviations to identify pin functions (as in any integrated circuit chip).

IMU

An **accelerometer** measures variations in linear motion and will also measure its own static orientation relative to the force of gravity. If an accelerometer rotates around its own axis, it will not measure angular velocity.

A **magnetometer** measures the magnetic field surrounding it, and may be sufficiently sensitive to determine its orientation relative to the Earth's magnetic field.

When an accelerometer and a gyroscope are contained in the same package, optionally with a magnetometer, they may be described as an *IMU* (inertial measurement unit), which can provide necessary data to maneuver aircraft, spacecraft, and watercraft, especially when **GPS** signals are unavailable.

Applications

The first chip-based gyroscope was used in automobiles in 1998 as a yaw sensor in a skid-control system. Subsequent automotive applications include active suspension control, air bag sensors, rollover detection and prevention, and navigation systems.

Gyroscopes may be installed in military ordnance to provide backup in case an onboard **GPS** system fails, possibly as a result of radio jamming.

Handheld 3D game controllers and headsets may use gyroscopes to control images displayed to the viewer. A digital camera may employ a gyroscope to provide image stabilization. Gyroscopes are usually found in quadcopters or drones, are used to stabilize two-wheeled vehicles such as the Segway, and are used in robotics.

How It Works

The traditional form of gyroscope is a rotating wheel, which will resist turning forces perpendicular to its own axis of rotation. In Figure 9-1, three directions at right angles to each other are defined in the bottom-right corner of the diagram as X, Y, and Z. The wheel is rotating around the X axis, as shown by the green arrow. It will resist any turning force around the Y axis (red arrows) or the Z axis (yellow arrows).



Figure 9-1 *In a traditional gyroscope, a wheel that is rotating (shown by the green arrow) will resist a turning force on either of the axes (shown by red and yellow arrows) perpendicular to its axis of rotation.*

Vibrating Gyroscope

A vibrating fork can be substituted for a wheel. In Figure 9-2 a fork is secured at its base while its tines are induced to vibrate toward each other and away from each other, as suggested by the double-ended arrow. In a chip-based gyroscope, this vibration is induced piezoelectrically or by static electricity.



Figure 9-2 *A vibrating fork (green arrows) can be substituted for a rotating wheel in a gyroscope.*



Figure 9-3 *A turning force is applied to the base of the fork around a vertical axis, as shown by the lower arrow.*

Now suppose a turning force is applied around the vertical axis at the base of the fork, as suggested by the lower arrow in Figure 9-3.

The angular momentum of the vibrating tines causes them to resist this turning force, and consequently they will tend to bend, as shown by the yellow arrows in Figure 9-4. The amount of their deflection can be measured capacitively. This system is used in many chip-based gyroscope systems, and may be referred to as a *vibrating gyroscope* or a *resonator gyroscope*.



Figure 9-4 *The angular velocity of the rotating fork causes deflection of its vibrating tines, shown by the yellow arrows.*

An assembly of microscopic forks can be etched into a silicon chip. In Figure 9-5, an electron micrograph shows the interior of this type of chip. It contains three rotational sensors, responding to the X, Y, and Z axes of motion. These sensors respond to *pitch* (rotation around the X axis), *roll* (rotation around the Y axis), and *yaw* (rotation around the Z axis).

Fork-based sensors are analog devices whose values are converted to digital values by an onboard *analog-to-digital converter* (ADC). The values are stored in registers that are available to other devices, often via the I2C protocol, which is widely used by microcontrollers.

For additional details about I2C, see Appendix A.

Typically there will be two 8-bit registers for each axis. Each register stores the binary equivalent of a signed integer, where the positive or negative value represents the direction and magnitude of deflection, usually in degrees per second (dps).



Figure 9-5 *Electron micrograph of the STMicroelectronics LIS331DLH vibrating gyroscope installed in the Apple iPhone 4. The parallel plates at bottom-left function as a spring, while the elements at top-left and at right measure capacitance as their orientation varies according to rotational velocity. Photo courtesy of MEMS Journal published by Chipworks*

Variants

The L3G420D by STMicroelectronics is a 3-axis gyroscope-only chip. It communicates via the SPI or I2C protocol, is approximately 4mm square, and can measure rotational rates up to plus-or-minus 2,000 degrees per second.

The Freescale FXAS21002C has a similar specification. Gyroscope-only chips of this type have fallen in price to the point where they are comparable to the retail cost of everyday components such as a small-signal relay or an audio amplifier on a chip.

IMUs

Chips that only contain gyroscopes are becoming less common as the cost of adding accelerometers decreases.

Gyroscopes and accelerometers are complementary, as gyroscopes are insensitive to linear motion or the Earth's gravity, but accelerometers can measure the rate of change of linear motion and orientation of the chip relative to the Earth. Software can combine this data to calculate the shape of the path being described by a device containing the chip, in addition to the changing velocity of the chip along that path.

The InvenSense MPU-6050 is a common 3-gyroscope, 3-accelerometer chip. It also includes an interface for connecting an external 3-axis magnetometer. The SPI and I2C communications protocols are supported. The MPU-6050 has been a popular choice in the hobby-electronics community, so that Arduino-compatible code to interpret its data is available from many sources. Breakout boards are available with the MPU-6050 installed. An example is the Sparkfun SEN-11028 shown in Figure 9-6.



Figure 9-6 *A breakout board from Sparkfun, providing easy access to the InvenSense MPU-6050 chip combining three gyroscopes and three accelerometers.*

Values

The *rotational velocity* of a gyroscope element is usually expressed in degrees of rotation per second (dps), and sometimes in rotations per minute (RPM).

A datasheet will specify the number of sensor axes (usually 3), supply voltage (3.3VDC is common), maximum digital-low and minimum digital-high output voltages, and power consumption in normal mode and sleep mode. Power consumption is usually less than 10mA.

The *dynamic range* is the maximum forward and reverse rotational velocity, which usually will not exceed plus-or-minus 2,000 degrees per second. Lower ranges may be user-selectable. The advantage of selecting a lower maximum rate of change is that it can be converted to a digital value with higher precision.

The *sensor resonant frequency* will be several kilohertz, and must be higher than the frequency of any vibration that is applied to the sensor during use.

The *communications protocol* is usually I2C and SPI may be offered as an option, with a selectable digital output data rate.

Bias temperature coefficient describes the effect of temperature on the gyroscope.

The *resolution* of the gyroscope relates to the number of bits used in the digital output from the onboard ADC. A 16-bit resolution is common.

How to Use It

Using a smart chip such as the MPU-6050, the circuit designer can take advantage of its onboard digital motion processor (DMP). Still, obtaining orientation information from the contents of registers on the MPU-6050 is non-trivial. Online sources and code libraries are necessary. The book *Make: Sensors* contains code listings for the Raspberry Pi as well as the Arduino.

What Can Go Wrong

Temperature Drift

Vibrating materials at the heart of a chip-based gyroscope are likely to change their behavior with temperature. Typically the chip will contain a temperature sensor, the value of which can be used to adjust the output value of the gyroscope.

Mechanical Stress

Stress can be induced when a surface-mount chip is soldered to a board. The vibrating parts of a chip-based gyroscope may be adversely affected. Datasheets will supply information regarding maximum acceptable temperature during the soldering process.

Vibration

Because a chip-based gyroscope depends on the consistent behavior of internal vibrating parts, external vibration can degrade its accuracy. Sensor design can minimize the effects of vibration, but the datasheet should be consulted for details.

Placement

A gyroscope should be placed on a circuit board near a hard mounting point where deflection of the board will be minimized.

accelerometer

10

OTHER RELATED COMPONENTS

- **GPS** (see Chapter 1)
- **gyroscope** (see Chapter 9)
- **tilt** sensor (see Chapter 8)
- **vibration** sensor (see Chapter 11)

What It Does

Acceleration is the rate at which velocity changes over time. If a car takes 10 seconds to increase its speed from 30kph to 40kph relative to the road on which it is traveling, it is accelerating at an average of 1kph each second. If it then reduces its speed back to 30kph during another 10-second interval, it is decelerating at the same rate—although deceleration is really just negative acceleration.

While a car is accelerating, passengers will feel a lateral force exerted on them. Similarly, astronauts in a rocket that blasts off will feel a downward force. According to Einstein's theory of equivalence, forces resulting from acceleration are indistinguishable from the force of gravity.

Consequently, a sensor that measures acceleration can also measure gravity. This sensor is an **accelerometer**. Its output may be measured in *gravities*, abbreviated with the letter g (not to be confused with the usage of G to measure the strength of a magnetic field in gauss).

If three accelerometers are mounted orthogonally (at 90 degrees to each other), their readings can reveal:

- The direction of acceleration of a moving object.
- If an object has been dropped and is falling freely.
- Which way up it is being held in a stationary position.
- The severity of an impact when a moving object collides with some other object.

IMU

A **gyroscope** measures the rate of rotation of the enclosure in which it is mounted. This is properly known as the *angular velocity*. A gyroscope will also respond to changes in the rate of rotation. It does not measure linear motion or a static angle of orientation.

A **magnetometer** measures the magnetic field surrounding it, and may be sufficiently sensitive to determine its orientation relative to the Earth's magnetic field.

When an accelerometer and a gyroscope are contained in the same package, optionally with a magnetometer, they may be described as an *IMU* (inertial measurement unit), which can provide necessary data to maneuver aircraft, spacecraft, and watercraft, especially when **GPS** signals are unavailable.

Schematic Symbols

A chip-based accelerometer may be represented in a schematic as a rectangular box containing abbreviations to identify pin functions, as in any integrated circuit chip. No specific symbol is used for any of these components.

Applications

In the past, accelerometers were laboratory devices that calibrated the performance of cars, airplanes, and other types of vehicles. Measuring the ability of car tires to withstand cornering forces was an application where an accelerometer was used.

Miniaturization of accelerometer elements, coupled with a radical reduction in their cost, has enabled them to be installed in small electronic devices ranging from smartphones to hard drives.

In a phone or a camera, accelerometers can determine which way up the user is holding the device. The camera can rotate the picture appropriately, and the orientation of the picture can be saved with its image data.

In an external hard drive containing rotating platters, accelerometers can protect the read-write heads by rapidly parking them during the fraction of the second that elapses between someone dropping the hard drive and its impact with the floor.

Accelerometers can be installed in a 3D mouse or virtual-reality headset to determine its orientation and motion. This enables a video image to be updated appropriately. For example, the Nintendo Wii Remote has been marketed with an ADXL330 accelerometer.

In an automobile, an accelerometer can trigger the deployment of an air bag when the deceleration caused by an impact exceeds a threshold level.

How It Works

The simplest conceptual model of an accelerometer consists of a mass attached to one end of a coiled compression spring. The other end of the spring is anchored in an object whose acceleration is being measured. The mass can only move along the same axis as the spring.

Figure 10-1 shows three views of a simplified accelerometer, which is a sealed tube shown in dark red. In the center image, the accelerometer is in its rest state. The top image shows the mass (a dark blue square) responding when the tube accelerates from left to right. The third image shows it decelerating (that is, undergoing negative acceleration, or acceleration from right to left). Using an ideal spring, the displacement of the mass will be proportional to the rate of acceleration, within reasonable limits. The displacement can be measured optically or capacitively.

Note that the rest state will resume when the acceleration stops, regardless of constant motion in any direction. An accelerometer only measures a *change* in velocity. It does not measure a constant velocity.

An accelerometer cannot measure rotation around its own axis of movement. Therefore, it may be used in conjunction with a **gyroscope**, which measures angular velocity.



Figure 10-1 *Simplified view of an accelerometer consisting of a sealed tube (dark red outline) with a spring anchored to it at left. A small mass (dark blue) is attached to the right end of the spring. The mass responds to acceleration of the tube.*

Gravity and Free Fall

If a device containing the simplified accelerometer described previously rests on the ground, and is mounted vertically as in the left section of Figure 10-2, gravity acting on the mass will apply a force to one end of the spring, while the other end is restrained. The accelerometer will now measure 1g as a downward force.



Figure 10-2 *Left: an accelerometer resting on the ground measures 1g, as the force of gravity pulls the mass downward. Right: in free fall, the accelerometer measures 0g.*

If the device is dropped so that it falls freely under the influence of gravity, it is in *free fall* and will accelerate at approximately 9.8 meters per second each second. This is usually written as 9.8m/sec^2, or can be described as 1 gravity, often expressed as 1g.

An accelerometer in free fall will measure 0g, as shown on the right in Figure 10-2, because all parts of the accelerometer are now accelerating equally under the force of gravity.

If three accelerometers are assembled orthogonally, and if one accelerometer is vertical, and the device is held motionless relative to the Earth, the vertical sensor will show 1g while the other two accelerometers will show 0g. If the device is dropped, all sensors will show 0g.

Rotation

If a device containing three accelerometers is turned over, and is not in free fall, accelerometers mounted orthogonally will show values that vary depending on their alignment with the force of gravity.

Calculation

The force acting upon an object will cause a rate of acceleration that can be calculated by Newton's Second Law of Motion, provided that the object can move freely and is not being subjected to any additional forces, such as the force of gravity. If F is the force, m is the mass of the object, and a is the acceleration:

```
F = m * a
```

And therefore:

```
a = F / m
```

If the mass is restrained by a spring whose compression or extension has an approximately linear relationship to the force applied to it, acceleration can be calculated as a function of the linear displacement of the mass.

These statements ignore relativistic effects that are insignificant unless ultra precise time and motion measurement may be involved.

In a real-world accelerometer, movement of the mass will require some form of damping to prevent it from oscillating.

Variants

Accelerometer prices dropped radically after 2010. In an effort to maintain profitability, manufacturers have loaded more features onto chips. While a 2-axis accelerometer such as the Memsic 2125 seemed a good option when first introduced, it is now facing obsolescence as 3-axis accelerometer chips that also contain 3-axis gyroscopes have become ubiquitous—and no more expensive.

Early chip-based accelerometers provided analog outputs where voltage was proportional with acceleration and could be processed by a comparator. On some breakout boards, such as the Dimension Engineering DE-ACCM6G, which used the STMicroelectronics LIS244ALH chip, a comparator was included (see Figure 10-3).



Figure 10-3 *A relatively early, relatively expensive breakout board using the 2-axis accelerometer LIS244ALH chip by STMicroelectronics. It has been superceded by chips that combine accelerometers, gyroscopes, and processors to provide a digital output.*

Because this board allowed a maximum output of only 0.83mA, it was only suitable for high-impedance logic chips or a microcontroller. However, because the output was analog, it could be passed through another comparator for direct connection to a piezo beeper to create a device that would sound an alarm when tilted. This is shown in Figure 10-4.



Figure 10-4 *Connecting the analog output from the DE-ACCM6G 2-axis comparator breakout board through a comparator to a piezo beeper.*

Many chips now contain gyroscopes as well as accelerometers. The electron micrograph in Figure 10-5 shows the interior of a chip of this kind, where the zig-zag shapes are “springs” etched into the die, the large areas patterned with dots are masses that can respond to various forms of motion, and the parallel plates are capacitive sensors.



Figure 10-5 *Interior of a chip combining gyroscopes with accelerometers.*

The complexity of a chip combining two types of sensors creates a need for more complicated code to process the six outputs. Consequently most accelerometer chips now have their own onboard ADCs, and digital registers for communication with microcontrollers via the I2C communication protocol. Some chips also have onboard processing to interpret the mix of data. However, microcontrollers still need code to make sense of the data.

The hobby-electronics community has responded. A breakout board such as the LSM9DS0 from Adafruit, using a chip from STMicroelectronics that shares that same part number, tries to make this extremely complex chip accessible to experimenters. Shown in Figure 10-6, the LSM9DS0 contains a 3-axis magnetometer in addition to a 3-axis gyroscope and a 3-axis accelerometer.

The datasheet for the LSM9DS0 runs to more than 70 pages. At the time of writing, Adafruit is still refining code for the Arduino to make the features of this chip accessible.



Figure 10-6 *This breakout board from Adafruit is built around an LSM9DS0 chip that combines accelerometers with gyroscopes and magnetometers.*

Despite the complexity of the LSM9DS0 chip, the breakout board sells for approximately the same price, at the time of writing, as the DE-ACCM6G 2-axis analog-output magnetometer four years ago. In the future we may expect IMU prices to fall still further, so that this type of multifunction chip becomes the default, and users simply ignore the functions that they don’t need.

Values

Current consumption will vary depending on the activity of the chip, and may be broken down for different types of sensors on multi-sensor chips. A modern accelerometer may typically draw less than 1mA. Gyroscope power consumption will be greater, as a segment of the chip will be maintained in a state of vibration.

Linear acceleration measurable by an accelerometer is customarily expressed in gravities, abbreviated g. Current generations of chips may be able to measure as much as plus-or-minus 16g, but because the value is converted internally to a digital quantity, smaller accelerations will not be expressed so accurately. Therefore the measurement range for acceleration is usually user-selectable by sending an appropriate code to the chip. Ranges may include plus-or-minus 2g, 4g, 6g, 8g, and 16g.

Sensitivity defines the smallest increment of acceleration measurable by the least significant bit (LSB) in an output register, for each of the acceleration ranges. In a range of plus-or-minus 2g, the internal 16-bit ADC may be capable of measuring 0.06 milligravities. When the range is reset to plus-or-minus 16g, the smallest increment may be around 0.7 milligravities.

The measurable range of gravities should not be confused with the maximum acceleration that the chip can tolerate without suffering internal mechanical damage, either while it is powered or unpowered. This will be more than 1,000g provided the duration is brief, and would only be experienced during an impact.

Linear acceleration sensitivity change versus temperature is usually expressed as a percentage, such as plus-or-minus 1.5%.

Output type will be analog or digital. If digital, the data protocol will be I2C or SPI. If I2C, the address of the device should be configurable. The data transfer rate is typically at least 100kHz, and this also may be configurable to different rates.

For additional details about protocols such as I2C, see Appendix A.

What Can Go Wrong

Mechanical Stress

Stress can be induced when a surface-mount chip is soldered to a board. The moving parts in a chip-based accelerometer may be adversely affected. Datasheets will supply information regarding maximum acceptable temperature during the soldering process.

Other Problems

If the accelerometer function is combined with other sensing functions such as magnetometer or gyroscope, see Chapter 2 or Chapter 9 for additional cautions about potential problems affecting these kinds of sensors.

vibration sensor

11

An **accelerometer** can measure some aspects of vibration. However, this entry deals primarily with mechanical devices (often described as *vibration switches*) and piezoelectric devices (often described as *vibration sensors*) that are solely intended to measure vibration.

A *vibrometer* measures vibration using a laser beam aimed at a reflective spot applied to a surface. It is usually a laboratory instrument, beyond the scope of this Encyclopedia.

OTHER RELATED COMPONENTS

- **accelerometer** (see Chapter 10)
- **tilt** sensor (see Chapter 8)
- **force** sensor (see Chapter 12)

What It Does

A vibration sensor responds to repetitive mechanical motion. Most versions contain two switch contacts that are normally open and will close if the sensor vibrates in its designed frequency range. In some sensors, the frequency range and sensitivity are manually adjustable.

Large sensors are used as automatic shutdown switches responding to excessive vibration in machinery, and may be capable of switching substantial currents (10A or higher). Smaller versions can shut down domestic appliances such as a washing machine that is seriously out of balance during a spin cycle.

A vibration sensor can be used as a simple user-input device in toys and games.

A shock sensor can detect abuse of a sensitive device, for example, by including the sensor and a data logger when the device is transported.

Schematic Symbols

Either of the symbols in Figure 11-1 may represent a piezoelectric or piezoresistive vibration sensor, but they also represent other piezo-based devices.



Figure 11-1 *Either of these symbols may represent a piezoelectric or piezoresistive device, including (but not limited to) vibration sensors that operate on this principle. The symbol on the left is more common.*

Variants

Vibration sensors use a wide variety of detection methods.

Pin-and-Spring

Probably the simplest type of sensor consists of a small, thin pin in the center of a miniature coil spring. The spring is anchored at its base, but its other end is free to vibrate. If the vibration reaches a sufficient amplitude, the spring touches the pin, completing a circuit between the two leads of the device.

An example is shown in Figure 11-2, where two identical sensors are shown, one of them cut open to reveal the gold-plated rod and spring inside. This sensor is rated for 10mA at up to 12VDC.



Figure 11-2 *When the spring in this sensor vibrates, it touches the pin that is centered in it. The background grid is in millimeters.*

Advantages of this system are low cost, ability to respond along two out of three axes, no power supply requirement, and ability to switch AC or DC. However, because the internal contact is extremely brief, it must be connected with a latching component of some type. A flip-flop could be used, or a 555 timer. The switch may also be connected with an input pin on a microcontroller, provided a pullup or pulldown resistor is used to prevent the input from floating when the switch is open.

Externally, the packaging of a pin-and-spring vibration sensor is almost indistinguishable from a small **tilt** sensor that contains one or two spherical metal balls. The tilt sensor may respond to vibration, but only of a large amplitude and low frequency.

A miniature board containing a pin-and-spring vibration sensor, comparator, and trimmer potentiometer for sensitivity control is sold cheaply by the Chinese supplier Elecrow as their product SW-18015P, shown in Figure 11-3. Elecrow also offers a wide range of other low-cost sensors.



Figure 11-3 *A pin-and-spring vibration sensor mounted on a board with sensitivity control.*

Piezoelectric Strip

The LDT0-028K by Measurement Specialties is a section of piezoelectric polymer film laminated to a polyester substrate. The film is designed to be anchored at one end, allowing the other end to vibrate. An unweighted version and a weighted version are shown in Figure 11-4, each measuring about 13mm x 25mm. Addition of the weight alters the resonant frequency of the sensor.

Deflection of about 2mm is sufficient to generate a surprising 7VDC between the two leads. Larger deflections will generate higher voltages. The manufacturer suggests that direct connection to a CMOS component is possible. An op-amp may be used for signal conditioning.

A piezoelectric device of this type only generates voltage during the process of deflection. If the strip is held in a curved position, its output diminishes to zero.

This sensor has a resonant frequency around 170Hz when there is no weight attached to its free end.



Figure 11-4 *Two versions of the LDT0-028K vibration sensor from Measurement Specialties, one with an added weight to lower its resonant frequency.*

Chip-Based Piezoelectric

The Murata PKGS series is an example of a surface-mount piezoelectric shock sensor. Measuring only about 1mm x 2mm x 4mm it has an analog output designed for connection through an op-amp. The manufacturer suggests application in a hard-disk drive to block read-write operations when vibration occurs. Similarly, these shock sensors may be used in CD-ROM or DVD drives. They may also be installed in cash dispensing machines to sound an alarm if vandalism occurs.

Toshiba's TB6078FUG is a similar product. Note that because these devices contain electronic components, they require a power supply (usually 3.3VDC to 5VDC) for operation.

"Mousetrap" Type

Some vibration switches rely on a simple system of leverage that is comparable to a mousetrap, in that a relatively small stimulus releases a strong spring. In Figure 11-5 the upper part of the figure shows the switch at rest, held in its position by a powerful spring and by the weight of a mass attached to a pivoted arm. In the lower part of the figure, severe vertical vibration has caused the assembly to move up and down with sufficient energy to overcome the tension in the spring while the inertia of the mass has resisted the motion. Consequently the arm has moved past the position where the spring is aligned with the pivot, and the spring now acts to hold the arm against a snap-action switch. A system of this type is used in sensors on some power-station cooling towers, where the loss of a large fan blade can result in major vibration.



Figure 11-5 *A spring-loaded vibration sensor.*

Magnetic

Typically this method is used to detect excessive vibration in machines or other devices containing heavy rotating mechanical components. The sensor may be physically large, moving switch contacts that are designed to handle currents of 1A or significantly more.

In one system, a steel ball is retained by a permanent magnet that is barely powerful enough to prevent the ball from falling. Excessive low-frequency vibration will dislodge the ball, which falls and completes a circuit between two contacts. This activates a relay that powers down the piece of machinery that is vibrating.

The ball may be spaced a small distance from the magnet by a beveled nonmagnetic seat, and the seat may be movable with an external screw. This will adjust the sensitivity of the switch. After the switch has been triggered, it must be reset, which may entail using an external lever to raise the ball back to its location near the magnet.

Another magnetic system is shown in Figure 11-6, where a magnet on a vertical arm can be displaced by horizontal vibration, and an inertial mass on a spring-loaded horizontal rod can also dislodge the magnet in response to vibration along the other two axes.



Figure 11-6 *A magnetic vibration switch. See text for details.*

Mercury

A small *mercury switch* may be used as a vibration sensor, although this application is uncommon. See Chapter 8 for more information about mercury switches.

Values

Measurement of vibration is a complex science of special interest in mechanical design, especially in areas such as the powertrain and suspension geometry in an automobile. Only a few fundamentals will be summarized here.

Primary Variables

The four primary variables in vibration are frequency, displacement, velocity, and acceleration. Frequency describes how rapidly the vibration occurs; displacement describes how far the vibrating object moves in each direction; velocity describes how fast it moves during each cycle; and acceleration describes how rapidly the velocity changes during each cycle. Different types of sensors can be chosen for their responsiveness to each attribute.

Figure 11-7 shows the theoretical relationships between displacement, velocity, and acceleration plotted against the frequency of vibration. The y axis of this graph (the vertical axis) is often labeled “amplitude,” but in reality it is being used to measure three different units, as shown. The curves indicate that if the velocity of vibration remains constant while frequency increases, acceleration must increase as a function of the frequency while displacement decreases. The acronym “rms” denotes that the values are measured as the “root mean square” of their fluctuations.



Figure 11-7 *Theoretical relationships among the primary attributes of vibration.*

Mechanical sensors or switches that respond to displacement are best suited to low frequencies, while piezoelectric sensors that are sensitive to acceleration are best suited to higher frequencies. Serious mechanical problems tend to result in low-frequency vibrations, while wear on bearings and in gear trains will be more likely to create high-frequency vibration.

Dynamic Attributes

Datasheets for small piezoelectric sensors may only show basic values such as the voltage range that is likely to be created.

Small mechanical sensors of the pin-and-spring type will be rated for maximum voltage and switching current. Typical values may be around 12V (AC or DC) and 10mA, indicating that the output from this type of sensor should be used with an op-amp, microcontroller, logic chip, solid-state relay, or other semiconductor with a high-impedance input.

Sensors that are manufactured for industrial applications will be rated for attributes such as measurable acceleration range (in gravities), temperature sensitivity, frequency response, resonant frequency, capacitance, and power requirement.

The sensitivity of piezoelectric sensors is usually expressed in mV/g. This type of sensor will require a comparator to process the tiny amount of current that it creates.

How to Use It

If a vibration sensor has an analog output requiring a comparator, the output from the comparator is likely to be of the open-collector type. This will require a pullup resistor of a value that provides an appropriate voltage for the next stage in the circuit. For more information about comparators, see Volume 2. For more information about the use of an open-collector output, see “3. Analog: Open Collector”.

A *coupling capacitor* can remove the DC component from the comparator output, allowing only the frequency of vibration to pass through. The choice of capacitor value will depend on the frequency.

When using a piezoelectric sensor with analog output, a 10M resistor may be installed across its two terminals to reduce voltage drift.

The primary challenge in getting a vibration sensor to work successfully will be matching it to the source of vibration. Manufacturers’ datasheets for chip-sized sensors often provide very little information about the optimal values for their products. Peak performance will occur when the natural resonant frequency of a sensor is close to the frequency of vibration that it must detect. Trial and error may be necessary.

A sensor must be mounted appropriately. Most sensors are directional, at least to some extent, and many will not respond significantly to vibration at 90 degrees to their primary axis of sensitivity. Their performance will also diminish if they are placed too far from the vibration source, or if they are mounted on a flexible or yielding surface that will tend to absorb vibration.

While industrial vibration switches may be adjusted manually, the response of small devices designed for circuit-board mounting can only be tweaked using external components to filter out unwanted signals from the sensor.

What Can Go Wrong

Long Cable Runs

The output from a piezoelectric vibration sensor is primarily an AC signal, fluctuating at the frequency of the vibration. Long cabling, or inadequately shielded cabling, can potentially introduce capacitive effects that can degrade the sensor signal. This issue will only affect higher frequencies.

Interference

Sensor signals can also be affected by electromagnetic interference from power lines, transformers, and large motors. This is a significant issue, as a primary application for industrial vibration sensors is to measure vibration created by motors.

Correct Grounding

For large sensing equipment, grounding may be important to shield cables that transmit data. In an industrial environment, however, grounding is primarily motivated by safety considerations, and an electrical ground can carry unwanted interference. Ground loops may be created if there are multiple ground points. Ideally, a "ground tree" should be used, where there is only one primary grounding point, and grounds to equipment branch out from it.

Fatigue Failure

In installations where some vibration normally exists, cables should be anchored properly to minimize the risk of fatigue failures.

force sensor

12

A *load cell* or *load sensor* is generally intended to measure a static load, while a *force sensor* can respond dynamically. However, this semantic distinction is not always observed. This entry differentiates between load cells and force sensors but includes them both.

Traditional types of *hydraulic* and *pneumatic* load sensors are not electronic devices. They are outside the scope of this Encyclopedia.

Capacitive, *ultrasonic*, *magnetic*, *optical*, and *electrochemical* force sensors are relatively unusual, and are not included in this Encyclopedia.

A force sensor is occasionally described as a **pressure** sensor, but that term is ambiguous, as it is more often used in conjunction with fluids. This Encyclopedia assumes that a pressure sensor only measures gas or liquid pressure. See Chapter 17.

A **vibration** sensor reacts to rapidly changing forces, but usually cannot measure them accurately, and is simply triggered when vibration exceeds a threshold. See Chapter 11.

Impact sensors that measure the force of a collision are outside the scope of this Encyclopedia.

A sensor designed to respond to a single touch from a fingertip is considered a human-input device and is discussed in the **single touch** sensor entry. See Chapter 13.

OTHER RELATED COMPONENTS

- **vibration** sensor (see Chapter 11)
- **single touch** sensor (see Chapter 13)

What It Does

A **force** sensor measures physical force that is applied to it, either by a person or by an object. Many force sensors respond rapidly and can measure fluctuating forces.

A *load cell* or *load sensor* is usually intended to measure the static weight of an object.

Applications

In robots, force sensors can provide feedback to limit the grip of a mechanical hand. They can also provide haptic feedback for a surgeon performing robotic surgery. In the future, force sensors may find increasing application in agriculture, as mechanized handling of fruit and other foods requires a carefully controlled gripping force.

In medicine, the use of force sensors to evaluate muscle strength in hands or limbs can be important as an indicator of neurological problems or to monitor progress in occupational therapy. Thin force sensors can be installed in shoes to check the weight distribution of each foot. They can also be used for entertainment purposes, to light LEDs in sneakers.

A force sensor may respond to a single-touch user input. See Chapter 13 for more information about **single touch** sensors. Some video game controllers use resistive force sensors to measure the amount of pressure applied to a button. The PlayStation is an example. (Old PlayStation DualShock 2 controllers are a salvageable source of pressure-sensitive buttons.)

Load sensors are used to weigh industrial products, and are also used domestically in kitchen and bathroom scales.

A load sensor can also detect human presence —for example, in the passenger seat of an automobile, where an air bag must not deploy if a young child is present, or in a hospital, to monitor the number of times the patient gets out of bed.

Schematic Symbol

No specific schematic symbol is used for either a force sensor or a load sensor. If a force sensor uses a piezoelectric or piezoresistive element, it may be represented by the symbol shown in Figure 11-1, which is used for many piezo devices.

How It Works

Two methods of force measurement are commonly used: resistive and piezoelectric.

A *piezoelectric* force sensor uses a piezoelectric element, often consisting of a quartz crystal, to convert force to a small voltage that can be amplified. However, this type of sensor only responds to changes in force. If a constant load is applied, the output peaks quickly and then gradually diminishes to zero.

Resistive force sensors change their electrical resistance when force is applied. They include *metallic strain gauges* and *plastic-film* sensors in which two layers of conductive ink are pressed together.

In SI (standard international) units, the force needed to activate a sensor is measured in newtons, abbreviated with a capital letter N. A newton is defined as the force that would accelerate a mass of 1 kilogram at 1 meter per second each second. More practically, in the gravitational field at the surface of the Earth, 1N = about 100 grams of weight. There are about 28 grams in an ounce; thus 1N is slightly less than 4 ounces.

Strain Gauge

A strain gauge is often made from metallic foil applied to an insulating flexible backing. The backing is glued to a shaped piece of metal, usually steel or aluminum, which is designed to flex slightly under pressure and may be referred to as a *spring*, even though it is often one solid object. Its deflection will be related to the force imposed on it.

The maximum deformation of the spring under a strain gauge is usually 500 to 2,000 parts per million (ppm) when subjected to the maximum force that it is designed to measure. A change of 1ppm is referred to as a *microstrain* (abbreviated µe).

The strain gauge has no polarity, and functions like a force-controlled **potentiometer** (see Volume 1). The ratio of the change in its resistance to the change in the strain that it experiences is called the *gauge factor*. For metal foil gauges, the gauge factor is usually around 2.0. This is an approximately linear relationship.

The most common type of foil pattern is shown in Figure 12-1. In the figure, if a stretching force is applied horizontally, the multiple thin sections of foil are slightly elongated, and their resistance increases within the limits of elasticity of the foil. This effect is multiplied by the number of sections. If the stretching force is applied vertically, the sections are merely separated slightly, and the result is negligible.

Wheatstone Bridge Circuits

The very small changes in resistance in a strain gauge must be amplified to be usable, and the first step is to use a Wheatstone bridge circuit. The simplest form of this circuit is shown in Figure 12-2.


Sensitive to Strain in This Direction
Not Sensitive in This Direction

Figure 12-1 *The pattern of metallic foil used in a typical strain gauge.*



Figure 12-2 *A demonstration version of the basic Wheatstone bridge circuit that is often used to detect small changes in a resistance.*

Each pair of resistors (R1 + R2, and R3 + R4) functions as a voltage divider. If all the resistors have an exactly equal value, the voltage at the midpoint of each pair will be identical, and the volt meter at the center will have a zero reading. However, if the value of one resistor changes slightly, the meter will register the imbalance. This circuit is commonly used because of its sensitivity to small variations.

In Figure 12-3 two strain gauges have been substituted for resistors R3 and R4. The upper strain gauge has been mounted so that it experiences an increase in force at the same time that the lower strain gauge experiences a decrease, usually because one gauge is mounted on the top side of a flexing element while the other gauge is mounted on the underside.



Figure 12-3 *Two strain gauges, oppositely oriented, can be used as resistances in the Wheatstone bridge circuit.*

Using two strain gauges in this way doubles the sensitivity of the Wheatstone bridge circuit. The configuration is known as a "half Wheatstone" force sensor, and will have three connecting wires. One will be black, one will be red, and the third will be a different color. The red and black wires are for connection to the power supply, as shown in the schematic, while the third wire is common and should be considered as an output.

If an additional two strain gauges are inserted in the Wheatstone bridge circuit, this is now a "full Wheatstone" force sensor (see Figure 12-4). Note, however, the diagonally symmetrical orientations of the strain gauges, necessary to multiply their effect.



Figure 12-4 *Two additional strain gauges create a "full Wheatstone" circuit.*

A typical digital bathroom scale contains two half-Wheatstone force sensors, wired to create a full-Wheatstone configuration.

The force sensors shown in Figure 12-5 are rated for up to 50kg each, and can thus weigh up to 100kg if they are combined in a scale. In this figure, one sensor has been turned over to show its underside. The strain gauges are hidden in each sensor where the steel sections overlap.

Wheatstone Bridge Errors

Where more than one strain gauge is used in a Wheatstone bridge, they should ideally have identical performance. Since this is impossible as a result of manufacturing tolerances, some error correction is built into devices using multiple strain gauges.



Figure 12-5 *Two force sensors suitable for a bathroom scale, each containing a pair of strain gauges that will flex oppositely under load.*

Strain-Gauge Amplification

The voltage output from a Wheatstone bridge circuit is given by the following formula, where V_{IN} is the supply voltage, V_{OUT} is the output, and R1 through R4 are the resistance values that were used in Figure 12-2.

$$V_{OUT} = [(R3/(R3+R4)) - (R2/(R1+R2))] * V_{IN}$$

The good news is that the output when a strain gauge is used will vary linearly with the load applied. The bad news is that it will be very small.

To amplify it, an op-amp such as the AD620 is often recommended. Using external resistors, its amplification factor can be adjusted from 1:1 to 10,000:1. Alternatively a chip such as the HX711 by Avia Semiconductor contains a 10-bit analog-to-digital converter and is specifically designed for use in weighing scales. Its digital output uses a very simple serial format. Sparkfun sells a breakout board incorporating this chip. See Figure 12-6.



Figure 12-6 *Sparkfun HX711 breakout board for the HX711 amplifier chip, specifically designed for a full-Wheatstone array of strain gauges in a force sensor.*

Other Strain-Gauge Modules

Strain gauges are built into a variety of sensor modules. Figure 12-7 shows a selection, all of which are available from Sparkfun. Many more can be found online.



Figure 12-7 *A selection of load cells containing strain gauges, available from Sparkfun.*

Plastic-Film Force Sensors

Plastic-film resistive sensors contain two layers of conductive ink, sealed between two layers of thin, transparent plastic film. The resistance between the ink layers diminishes when they are pressed together. It may vary from as little as 30K when fully loaded to more than 1M when unloaded.

Like a strain gauge, this sensor has no polarity and requires no power supply.

Examples of this type of sensor are shown in Figures 12-8 and 12-9. Other shapes and sizes are available. Manufacturers include Tekscan, whose product is named FlexiForce; Alpha Electronic, in Taiwan; and Interlink Electronics.



Figure 12-8 *A FlexiForce A401 resistive film sensor made by Tekscan, Inc. Its sensing area is 25.4mm in diameter (1 inch) and is rated to measure up to 111N (25lbs).*



Figure 12-9 *An Interlink FSR406 resistive film sensor. Its sensing area is slightly less than 40mm square, and is rated to measure up to 20N (4.5lbs).*

Plastic-film sensors should not be confused with film-based piezoelectric vibration sensors, which are described in the **vibration** entry (see "Piezoelectric Strip"). Those sensors provide a transient output when they flex rapidly. The resistive sensors provide a stable output in response to a steady load.

Deformative Force Sensors

A sheet of natural or silicone-based rubber can be impregnated with conductive particles. The conductivity of the sheet may not change significantly when it is compressed, but if it is separated from a metal plate by a mesh of thin nylon fibers, compression will result in greater conductivity by pushing the rubber into the gaps between the fibers. See Figure 12-10.



Figure 12-10 *In the top image, a flexible conductive layer is separated from an underlying rigid electrode by nylon mesh. In the lower image, a load applied to the flexible layer has forced more of it into contact with the electrode, reducing the resistance between them.*

Improvised Resistive Sensors

Polyethylene film impregnated with carbon particles is available under the brand name Velostat, owned by 3M. Although it was developed as an antistatic packaging material for semiconductors, it can be used to make a DIY force sensor. When the material is stretched, the embedded particles are more dispersed, and electrical resistance increases. When the material is compressed, its resistance is reduced.

Antistatic foam of the type used to package CMOS components can be used in the same way, although some types behave like memory foam, being slow to recover from pressure. The foam can be sandwiched between a pair of copper-plated circuit boards as electrodes.

How to Use It

Plastic-Film Resistive Force Sensors

The conductivity of a plastic-film sensor has an almost linear relationship with the force applied. In other words, if F is the force and I is the current:

```
I = k * F
```

where k is a constant determined by the characteristics of the materials used.

By Ohm’s Law, R = V / I where V is the voltage drop across a resistance of value R. By substitution, using k * F instead of I:

```
R = V / (k * F)
```

Therefore, if a constant voltage is applied across the force sensor, the resistance of the sensor will be proportional to the reciprocal of the force (i.e., 1 / F). These relationships are shown in Figure 12-11.

For convenient measurement, it will be helpful if the resistance of the sensor can be converted to a voltage output that varies linearly with the force applied. To achieve this, a resistive force sensor of this type is customary amplified with an **op-amp** (see Volume 2). Using the schematic shown in Figure 12-12, the amplification ratio, A, is found from this formula:

```
A = 1 + (R2 / R1)
```

where R2 if the potentiometer, and R1 is the resistive force sensor. Therefore, the output from the op-amp should have an approximately linear relationship with the force applied to the sensor.



Figure 12-11 *The relationship between force, current, and resistance in a flexible resistive sensor, assuming a constant voltage of 1V is applied across it (derived from FlexiForce Sensors User Manual).*



Figure 12-12 *An amplification circuit with an output that is approximately linear with force applied to a resistive film sensor.*

The capacitor in this circuit is added to suppress noise that the circuit might otherwise pick up.

An alternative is to wire a resistive sensor in series with a capacitor, and connect the other side of the capacitor to a comparator that has adjustable feedback. The resistance of the sensor will determine how quickly the capacitor charges. However, because of the mathematics describing the charge rate, the output from the comparator would not be linear with the force on the sensor. Also, provision would be necessary to discharge the capacitor intermittently.

Values

Film-Based Force Sensors for User Input

A very light pressure with a fingertip could be around 50g. A more defined finger-press would be 250g, and a heavy push with a finger would be around 1kg.

The Interlink range of flexible force sensors requires a minimum pressure of 0.2N, or about 20g. Similarly, Alpha products range from a minimum of 10g to 30g.

These specifications suggest that film-based force sensors may be used for one-touch user input, but the no-load resistance will be at least 1M, and more than 10M in some instances. A small amount of pressure is unlikely to reduce this electrical resistance much below 500K. Using an op-amp or comparator to detect that difference and convert it into a reliable on-off output may be vulnerable to noise and power-supply disturbance.

Another consideration is that film-based sensors provide no tactile feedback. For these reasons, and because film-based products are described by their manufacturers as “force sensors” rather than as “touch sensors,” they are included in this entry rather than in Chapter 13. That said, they may be considered as an option for one-touch user input where they are appropriate—for instance, in games where players are likely to slap or hit a sensor vigorously.

Specifications for Film-Based Force Sensors

Durability of film-based sensors is excellent, with manufacturers claiming that performance is not degraded after 1 million applications of a 20kg load. Sensors have no polarity, will function using voltages from 1V to 15V in most cases, and have a response time of less than 5ms. They do not generate, and are not vulnerable to, electromagnetic interference.

Important attributes when evaluating film-type sensors are their limits of tolerance for applied force, and resistance values at each end of the range. Unfortunately these values are poorly documented for many sensors, or may be unspecified.

Maximum force may range from 20N to 440N, depending on the brand and model of sensor.

Electrical resistance is at least 1M when unloaded, and may be as high as 20M.

Accuracy ranges from plus-or-minus 2% to plus-or-minus 5% from one application of force to the next, depending on the model of sensor and the manufacturer. If force is not applied each time in exactly the same area of the sensor, results will vary. If a sensor is swapped with another sensor of the same type, sensor-to-sensor consistency will be uncertain. Therefore, film-based force sensors are not a good choice for applications where accuracy is important.

Sensors may be rated for 5% to 10% hysteresis.

The area of active detection may range from about 4mm wide (FlexiForce sensors) to more than 40mm wide (Interlink FSR-406).

Strain Gauges

Strain gauges are not sold as individual components by most electronics suppliers. They are sometimes available as surplus parts or from sites such as eBay, where specifications range from 100 ohms to 1K as the resistance when no load is applied.

A load sensor on which a strain gauge has been preinstalled is much easier to use, and will be plug-compatible with an appropriate amplifier chip as previously described.

What Can Go Wrong

Soldering Damage

The pins on plastic-film resistive sensors are embedded in thin plastic. Heat from a soldering iron can easily damage this plastic. Heat-sink alligator clips should be used while soldering, or the pins can be socketed instead of soldered.

Bad Load Distribution

Film-based sensors will not provide accurate readings if a load is imposed unevenly or inconsistently, or extends outside the detection area. A *puck* consisting of a small, rigid disc may be interposed between the source of the force and the sensor, to distribute the load within the maximum area. A puck may also be referred to as a *shim*.

Similarly, the sensor must be mounted on a flat, smooth surface, and if this is not available, a rigid plate should be interposed.

Water Damage

Although film-based sensors are enclosed in plastic, they are not waterproof. Immersion may cause the layers to delaminate.

Temperature Sensitivity

Because electrical resistance tends to vary with temperature, readings from resistive force sensors will vary with temperature.

Ambient temperatures of 70 degrees Celsius and above may damage a film-based sensor.

Leads Too Long

Although film-based sensors are supplied with a variety of lead lengths enclosed in the laminated layers of flexible plastic, the leads may be too long for a particular application. If they are trimmed, wires cannot be attached with solder, as it will melt the plastic. Conductive epoxy should be used.

single touch sensor

13

This entry only describes *capacitive* touch sensors. A *conductive* sensor, which uses the fingertip to complete a circuit between two exposed contacts, is not very common, and is not included here.

The type of touch sensor described in this entry requires no physical pressure for activation. It should not be confused with a resistive or piezoelectric **force** sensor that requires pressure. See Chapter 12.

An integrated circuit chip that processes a signal from a *touch pad* is often described as a *touch sensor*, even though it does not contain a sensing element. This entry describes it as a "touch sensor chip" to eliminate ambiguity, and refers to touch input elements as "touch pads."

Touch pads that contain *tactile switches* or *membrane switches* are described in the entry discussing **switches** in Volume 1. All types of switches are described in that volume, with the exception of a *reed switch*, which is magnetically activated and is therefore categorized as a sensor.

Capacitive touch sensors are sometimes referred to as *capacitive proximity sensors*, because they sense the proximity of a human fingertip. In this Encyclopedia, and in most other sources, a **proximity** sensor measures distance, not touch. See Chapter 5.

A *capacitive displacement sensor* employs the same principle as a capacitive touch sensor, but is used to detect the position of an object, not for human input.

OTHER RELATED COMPONENTS

- **force** sensor (see Chapter 12)
- **touch screen** (see Chapter 14)

What It Does

A *touch pad* detects the presence of a human fingertip (or other part of the body) and signals an integrated circuit chip, which is very often termed a *touch sensor*, even though it does not contain a sensing element itself. The chip creates an output to signify that human touch has been recognized.

A keypad of the type found on microwave ovens may appear similar to an array of touch pads, but is more likely to contain *membrane switches* or *tactile switches*, which are described with other forms of switches in Volume 1. The type of touch pad described in this entry requires no physical force and contains no parts that move or flex when pressed.

A modern **touch screen** is usually a capacitive device and can be thought of as an array of touch pads. See Chapter 14.

Applications

Capacitive touch sensors have become common as their cost has fallen relative to simpler components that respond to being pressed.

A touch sensor can be used to start or stop a process, or to power up or power down a device. Multiple sensors may be found wherever user input of a few alphanumeric characters is required. Because touch pads can be completely sealed, they are useful where hygiene is important.

Specific applications include the activation of a backlight in a handheld device, wake-up from standby, ear detection in a cellular telephone, control of medical devices, and activation of interior lighting in some automobiles.

The absence of moving parts or electrical contacts means that a touch pad is more reliable than any type of electromechanical switch. A disadvantage is that it provides no tactile feedback, and therefore will require a visual or audible confirmation when it responds to input. Lack of tactile feedback makes touch pads unsuitable for computer keyboards and other key-entry devices where rapid typing is required.

When the capacitive elements of a touch pad are transparent, it can be mounted in front of a screen.

Schematic Symbols

Either of the schematic symbols in Figure 13-1 may sometimes be used to represent a touch sensor, but not on a consistent basis.



Figure 13-1 *Two possible schematic symbols that may represent a touch sensor.*

How It Works

The two plates in a capacitor are separated by an insulator known as the *dielectric*. Paper, plastic, glass, air, and other insulators can serve this purpose. Although no electrical connection exists between the plates, AC passes through the dielectric as a field effect.

Electrical capacitance exists between any pair of electrical conductors. The human body has high electrical resistance but still is electrically conductive, and therefore has capacitance with other conductive objects.

A touch pad can function as one side of a capacitor, with a fingertip functioning as the other side. In this mode, AC can pass from the touch pad and through the human body to ground. The current is very small, but fluctuations can be detected by an appropriately designed integrated circuit chip, or by a microcontroller.

The precise characteristics of a dielectric will affect the performance of a capacitor to some extent, but will not prevent it from working. Therefore a touch pad can function even when it is shielded behind a protective layer of glass or plastic, as is often the case.

A touch sensor chip generates pulses of low-voltage AC and sends them to a touch pad. The chip detects any variation in the current through the touch pad, indicating the presence of a fingertip. Where an input occurs, the chip changes its output, which usually requires a microcontroller for processing.

How to Use It

Touch sensor chips are available in as many as 40 different formats and configurations. All of them are surface-mount. For breadboarding, an experimenter can use breakout boards that have sensor chips installed. Figure 13-2 shows a product from Adafruit that is capable of addressing 12 touch pads. Its output is accessible from a microcontroller via the I2C protocol. For additional details about protocols such as I2C, see Appendix A.



Figure 13-2 *A capacitive touch sensor chip on a breakout board from Adafruit.*

Similar breakout boards are available from Sparkfun, and from large online vendors such as *http://www.mouser.com* (where they are categorized as *development tools*).

While most touch sensor chips require a microcontroller, a few are available with the same number of output pins as touch-pad input pins, and each output pin will transition between logic-high and logic-low when an input on the corresponding pin is detected. Another breakout board from Adafruit, the AT42QT1070, uses this simple system.

A library exists for Arduino that enables two pins to sense touch on a piece of aluminum foil.

It can also work with conductive ink or paint.

Obtaining Touch Pads

Sensor chips are widely available as components, and are very inexpensive. On the other hand, touch pads are not common as components, probably because a touch pad is usually created as a pattern of copper traces etched onto a circuit board by a device manufacturer.

Touch pads from hobby-electronics sources usually include touch sensor chips. Sparkfun offers a 12-key keypad on this basis, and also a 9-key keypad designed as a “touch shield” for use with the Arduino. Both of the Sparkfun products are shown in Figure 13-3. They include the same MPR121 touch sensor chip as the breakout board from Adafruit shown in Figure 13-2, and require an I2C connection with a microcontroller.



Figure 13-3 *Two capacitive keypads from Sparkfun, the one on the right designed as an Arduino shield.*

Because a capacitive touch pad is usually mounted inside an enclosure, the appearance of the bare touch pad as a component is unimportant. The outside of the enclosure can be printed with a design showing key outlines.

Individual Touch Pad

Adafruit sells the AT42QT1010 touch pad that emulates a momentary switch. Its output transitions from logic-low to logic-high when a finger presence is detected, and transitions back to logic-low when the finger is removed.

An alternative, shown in Figure 13-4, toggles between a logic-high and logic-low output and latches in each state with each single key press.

Both of these keypads contain sensor chips to generate the output.



Figure 13-4 *The output from the AT42QT1012 sensor chip on this touch pad from Adafruit toggles between logic-high and logic-low each time the pad is touched.*

Wheels and Strips

A touch wheel uses a circular pattern of conductive traces, often referred to as *electrodes*, to receive finger input. A simple configuration is shown in Figure 13-5. The traces interlock without making contact with each other, so that moving the finger in a circular motion creates a capacitive input that rises and falls sequentially on each element. In the figure, three sections are used, each colored differently here for purposes of clarity. Other touch wheels may contain more sections.

Firmware that is designed to interact with wheel-shaped touch pads will generally assume that two electrodes are receiving input at one time. The firmware attempts to calculate the position and motion of the finger by assessing the relative capacitance of adjacent segments. Ideally the capacitance values should vary linearly and complementarily; that is, from a 50-50 value at a midpoint between two segments, the progression should change to 60-40, 70-30, and so on, as the finger moves around the wheel.

A *touch potentiometer* consists of multiple touch pads, usually arrayed in a straight line. This may be described as a *touch strip*. An example is made by GHI Electronics and sold by Robot Shop as their L12 Capacitive Touch Module, shown in Figure 13-6.



Figure 13-5 *A touch wheel created by copper traces on a circuit board (green). Each section is colored differently, for purposes of clarity.*



Figure 13-6 *Multiple capacitive touch pads arrayed as a strip, made by GHI Electronics.*

Design Considerations

A simple touch pad is often surrounded by additional copper that is grounded and may be described as a *shield* or a *guard*. The capacitance of a fingertip (spaced above the electrode by a layer of plastic or glass that functions as the dielectric) interferes with the field between the electrode and the shield.

The underside of the circuit board is often plated and grounded to protect the touch pad from electromagnetic interference. This, too, can be referred to as a shield or a guard. The ground plating can be in a hatched pattern to reduce its capacitance with the electrode above.

Layout of a circuit involving a single touch sensor chip can affect its performance significantly. A touch sensing device may have to be "tuned" to detect finger presence reliably.

A long trace between the touch sensor and an electrode will tend to pick up noise and will increase capacitance.

The distance between adjacent traces from multiple touch pads must be maximized to reduce capacitance between them. If output from a sensor chip uses the I2C or SPI digital protocol, any trace carrying that digital signal should be at least 4mm from input traces. If they cross, they should be at 90 degrees to each other.

Electrodes should not be shaped to resemble numbers or other characters printed above them. A single basic electrode should be circular.

What Can Go Wrong

Insensitive to Gloves

Gloves are a challenge for touch-sensor design, as they alter the dielectric and the distance between the electrode and the finger. Capacitive touch sensors may not work at all with some types of gloves. However, special gloves containing metallic threads are available.

Stylus Issues

A nonconductive stylus cannot activate a touch pad.

Conductive Ink

Ink that prints the shapes of touch pads on the exterior of a device should be nonconductive.

touch screen

14

The term **touch screen** is written as two words in this Encyclopedia. In many sources, the words are concatenated as "touchscreen."

The two words are hyphenated here when they function as an adjective, but not otherwise. In manufacturers' datasheets where the two words are used, they are not usually hyphenated.

OTHER RELATED COMPONENTS

- **single touch** sensor (see Chapter 13)
- **force** sensor (see Chapter 12)

What It Does

A touch screen is a video display with embedded touch sensing. The screen reports the position of the touch, and is used as a pointing device as an alternative to a mouse or trackpad. Some touch screens report pressure as well as position.

Touch screens are widely used in smartphones and tablets, and also in some laptop computers. Smaller, simpler touch screens may be found in office equipment such as photocopiers.

Schematic Symbol

No specific schematic symbol is used to represent a touch screen.

Variants

Early designs used infrared LEDs recessed into the edges of a frame around a screen. A matching photodiode picked up the focused beam from each LED. The presence of a fingertip was detected when it interrupted one or more of the beams. This system was not capable of high resolution, but was adequate for detecting user input at predefined locations.

Most touch screens currently are either resistive or capacitive.

Resistive Sensing

A resistive touch screen consists of two transparent layers that can be installed over a separate video display.

Each of the layers has uniform electrical resistance. Pressure from a fingertip on the outer layer (which we can refer to as layer 1) forces it to make contact at a point with the inner layer (referred to here as layer 2).

Two vertical electrodes connect with layer 1 along its left and right edges. Two horizontal electrodes connect with layer 2 along its top and bottom edges. When voltage is applied between the vertical electrodes on layer 1, the layer acts as a horizontal voltage divider. The voltage at the point where the layer is being pressed is applied to layer 2, and can be read from either of the electrodes on layer 2, so long as the metering has a much higher impedance than that of the layer. The voltage is decoded as a value for the horizontal position on layer 1.

An external switching device now repeats the procedure, except that it applies voltage to layer 2, and reads it from layer 1 to supply a value for the vertical position on layer 2. The sequence is illustrated by the top and bottom sections of Figure 14-1.

Because only four connections are necessary, this is referred to as a *four-wire* resistive touch screen. Five-wire variants exist, but are less common, and are not included in this entry.

Advantages of a resistive screen include:

- Simplicity. Only four connections are necessary, and the layers of the screen do not have to be subdivided into separate conductors.
- Low cost, relative to capacitive touch screens.
- Will respond equally well if a user wears gloves or uses a stylus.

Disadvantages of a resistive screen include:

- Some resistive versions require a stylus input instead of finger pressure.
- Resistive screens only respond to a one-location input. Two-finger gestures are not supported.
- Contact bounce occurs when the flexible layer is pressed against the underlying layer, and voltage spikes may be associated with switching power to the screen. To address this issue, firmware in a microcontroller may have to take a median value from several rapid readings.
- The flexible membrane is vulnerable to damage from sharp objects.



Figure 14-1 *Sections of a resistive touch screen are shown displaced for clarity. In reality they would be separated by a very small gap, allowing one section to make contact with the other in response to finger pressure.*

Capacitive Sensing

A capacitive touch screen can consist of an array of **single touch** sensors printed onto a glass panel as vertical and horizontal lines of transparent conductive ink.

Alternatively, a small capacitive screen can measure the tiny amount of current drained by a fingertip from four sources located at corners of the screen.

For more information about capacitive touch sensing, see the entry on touch sensors in Chapter 13.

Screens Available as Components

A wide variety of screens can be found in diagonal sizes ranging from 2 inches upward. Onboard electronics can be suitable for connection with a microcontroller using the I2C and SPI protocols, or USB. Different screen resolutions are available.

An example of a 3.5-inch touch screen with 320x200 resolution, mounted on a breakout board that can be used with a breadboard and an Arduino, is shown in Figure 14-2.



Figure 14-2 *An Arduino-compatible touch screen mounted on a breakout board, available from Adafruit.*

A 7-inch resistive touch screen that can be mounted on a separate video display is shown in Figure 14-3. It can be used with the STMPE610 controller chip, which converts resistive screen values into digital coordinates and can be accessed by a microcontroller over both SPI and I2C. This surface-mount chip is available on a breakout board.



Figure 14-3 *This resistive touch screen is intended for use as a layer applied to a 7-inch video display. The screen is available from Adafruit.*

When choosing a touch screen as a component for a DIY project, the availability of microcontroller code libraries for reading and refreshing the display is an important consideration.

liquid level sensor

15

Level indicators that contain no electronic components are not included in this entry.

Specialized industrial level-sensing equipment is generally outside the scope of this Encyclopedia. This entry discusses small-scale, lower-cost sensors.

Liquid volume can be assessed by measuring liquid pressure at the bottom of a reservoir. Sensors for this purpose are discussed in the entry describing **gas/liquid pressure** sensors. See Chapter 17.

OTHER RELATED COMPONENTS

- **liquid flow rate** sensor (see Chapter 16)
- **gas/liquid pressure** sensor (see Chapter 17)

What It Does

Measuring the volume of liquid in a storage vessel or reservoir is such a fundamental task, countless methods have been devised, of which only the simplest and most common will be discussed here.

A liquid level sensor can have a binary output, meaning that it signals when the volume rises above or falls below a level that can be preset or reset. Often the sensor will be connected to a pump or valve that maintains a relatively constant volume in a container.

Alternatively a sensor can indicate the actual stored volume, either with an analog output or in digital increments.

Schematic Symbols

Three variants of a schematic symbol for a simple liquid level sensor are shown in Figure 15-1. They are not always used, however, and a sensor may be shown simply as an annotated switch.



Figure 15-1 *Three variants of a schematic symbol to represent a liquid level sensor. The rightmost symbol indicates that a rising level closes, rather than opens, a switch.*

Applications

The fuel gauge in a vehicle is one of the most commonly encountered applications of a liquid level sensor. The water tank in a recreational vehicle or boat may use similar electronics. In industry, the choice of a sensor will be influenced by the type of liquid that is being stored, the desired accuracy, the temperature range, and whether the storage tank is sealed or open to atmospheric pressure.

How It Works

Desirable attributes of any liquid-level sensor include resistance to vibration, some damping to average out fluctuations caused by turbulence or sloshing in the liquid, resistance to chemical reactions with the liquid, and few moving parts that may require maintenance if the sensor is inside a sealed tank. Desirable attributes of an analog float sensor include a linear response, and some hysteresis if the application requires it.

This entry compares a variety of sensing strategies.

Binary-Output Float Sensor

The term "binary output" is used here to describe an output that only has two states (on and off, or logic-high and logic-low). The simplest type of liquid-level sensor with a binary output consists of a donut-shaped float that contains a permanent magnet and is free to slide vertically up and down a sealed tube containing a reed switch. The tube is supported on a bracket that can be mounted on the wall or the lid of the vessel containing the liquid.

The tube and float must be nonmagnetic, and the float must have a significantly lower specific gravity than the liquid that is being used ("significantly" because the float requires sufficient buoyancy to carry the weight of the magnet and overcome any friction between itself and the tube). A diagram illustrating this configuration is shown in Figure 15-2.

To change the level setting of the sensor, the bracket may be mounted on a screw thread to adjust its vertical position.

The reed switch can be normally open or normally closed, as needed to respond to a rising or falling liquid level. For basic information about reed switches, see "Reed Switch". Additional, detailed information about reed switches is included in the book *Make: More Electronics*.



Figure 15-2 *The principal parts of a basic binary-output float sensor.*

For increased reliability, a Hall-effect sensor could be substituted for a reed switch. See "Hall-Effect Sensor" for general information about Hall-effect sensors.

Another binary-output float sensor is shown in Figure 15-3. This is a sealed plastic capsule containing a snap-action switch and a steel ball. The cable is attached to the underside of the top of a tank, and the capsule dangles into liquid in the tank. A separate weight (not shown) has a hole in the middle, and is threaded over the wire. The weight keeps the wire approximately in a vertical position as it dangles into the tank.



Figure 15-3 *An air-filled float that switches external power depending on its orientation.*

Figure 15-4 shows the components inside the float. When the liquid level in the tank falls, the float adopts the position shown on the left in the figure. The ball drops against a lever that closes a snap-action switch, which starts an external pump to replenish the tank. As the liquid level rises, the buoyancy of the air-filled float changes its orientation to that shown on the right in Figure 15-4. The ball drops and the switch opens, stopping the pump.



Figure 15-4 *Internal components of the float shown in the previous figure.*

Two circular indents on the inner surface of the plastic capsule prevent the ball from rolling erratically if there is turbulence in the liquid. They also provide some hysteresis.

Analog-Output Float Sensor

The simplest type of liquid-level sensor with an analog output consists of a float on an arm attached to a potentiometer, as shown in Figure 15-5. This very basic design was used in fuel tanks in vehicles for many decades. Disadvantages include a nonlinear response and the limited life expectancy characteristic of potentiometers. Some compensation for the nonlinear response can be made by using an analog fuel gauge with a nonlinear scale.

For more information about potentiometers, see "Arc-Segment Rotary Potentiometer".



Figure 15-5 *A basic float sensor with an analog output.*

Incremental-Output Float Sensor

A schematic diagram for a simple float sensor with incremental output is shown in Figure 15-6. A magnet embedded in a donut-shaped float, similar to that shown in Figure 15-2, interacts with a sequence of reed switches installed in the central tube. The switches are spaced at equal intervals and apply power between resistors of equal value wired in series. This system has been used in motorcycle and automobile fuel tanks, where the switches may be enclosed in a (nonmagnetic) stainless-steel tube. The accuracy is limited by the number of reed switches.



Figure 15-6 *A float sensor with incremental output.*

Displacement Level Sensors

If a heavy object, described as the *displacer*, is suspended in liquid, the effective weight of the object diminishes as the liquid rises up around it. This occurs because according to Archimedes' Principle, the upward buoyant force is equal to the weight of liquid that the object displaces. The displacer is suspended from a load sensor that measures its weight. Analog output from the sensor will be approximately linear with liquid level.

For a simplified diagram showing a displacement level sensor using this concept, see Figure 15-7.



Figure 15-7 *A displacement sensor. The displacer is heavier than the liquid around it, but its effective weight diminishes as the liquid rises.*

For more information on load sensors, see Chapter 12.

Ultrasonic Level Sensors

An ultrasonic sensor can be used to measure the level of liquid in a reservoir, as shown in Figure 15-8. For more information about this type of sensor, see the entry discussing proximity sensors in Chapter 5. A disadvantage of using ultrasound for liquid level sensing is that the speed of sound will be affected by any vapor given off by a volatile liquid.



Figure 15-8 *An ultrasonic proximity sensor can measure the level of liquid in a reservoir.*

Reservoir Weight

The weight of a reservoir can be measured to assess the volume of liquid in it. This can be done by mounting the reservoir on load sensors. However, pipes leading to and from the reservoir must be designed so that they do not add or subtract any significant weight. Figure 15-9 suggests an arrangement, although the outflow will still change the weight to some extent depending on the amount of suction that is applied. For more information on load sensors, see Chapter 12.



Figure 15-9 *Using load sensors to assess the weight of liquid in a reservoir requires that the weight of plumbing should not be imposed on the structure of the reservoir.*

Pressure Sensing

A differential pressure sensor can be added to a pipe near the bottom of a reservoir. The sensor measures the difference between the liquid pressure and ambient air pressure. See Figure 15-10.



Figure 15-10 *A pressure sensor can assess the volume of liquid in a reservoir.*

This arrangement assumes that the reservoir is vented so that air pressure above the liquid level is equal to air pressure at the sensor. If the reservoir is not vented, a pipe must connect the reference port on the sensor with the space above the liquid.

The reservoir must have straight, vertical sides for the pressure to be directly proportional to the liquid volume.

Liquid volume can also be assessed by measuring the pressure inside a container, near the bottom. A submersible pressure sensor can be used, typically consisting of a watertight capsule fitted with a diaphragm that connects with an internal strain gauge. The sensor is lowered on a cable that also contains an air line. Because pressure in a liquid is affected by atmospheric pressure above the surface of the liquid, the sensor requires an air line so that its measurements are relative to the outside air.

Submersible pressure sensors are useful where access is limited—for example, when measuring fluctuations in an open-air municipal water reservoir.

What Can Go Wrong

Turbulence

Surface turbulence consisting of ripples, waves, or sloshing of liquid will tend to occur when a reservoir is refilled rapidly or is subjected to lateral movements as a result of being mounted in a moving vehicle. To minimize output fluctuations, some *damping* is desirable.

Baffles consisting of perforated plates inside the reservoir are a common strategy, as shown in Figure 15-11. In the upper section of the figure, lateral acceleration causes submersion of a float sensor in the reservoir. In the lower section, perforated baffles minimize the problem.



Figure 15-11 *Insertion of perforated baffles in a reservoir minimizes the sloshing that otherwise tends to occur when the reservoir is subject to lateral motion.*

Sensors that measure the weight or pressure of a liquid are less susceptible to turbulence. In a displacement sensor, the weight of the displacer provides a damping effect.

Tilting

All level sensors will tend to give inaccurate readings when a reservoir is tilted. A float sensor will be affected less if it is mounted centrally in a reservoir, because the reservoir will tilt around the sensor, as shown in Figure 15-12.



Figure 15-12 *If a float sensor is mounted centrally in a reservoir, it will be significantly less affected if the reservoir tilts.*

liquid flow rate sensor

16

Flow rate sensors that contain no electronic components are not included in this entry.

Some methods of liquid flow sensing can also be applied to gases, but sensors are usually designed for one application or the other. Therefore, gas flow sensors have their own entry. See Chapter 19.

Many liquid flow rate sensors are large devices designed for industrial applications. This entry focuses on lower-cost solid-state sensors.

OTHER RELATED COMPONENTS

- **liquid level** sensor (see Chapter 15)
- **gas/liquid pressure** sensor (see Chapter 17)
- **gas flow rate** sensor (see Chapter 19)

What It Does

A liquid flow rate sensor measures the rate at which liquid flows past or through the device. A water meter is an example of a flow rate sensor.

A sensor may have a binary output, meaning that it signals when flow stops or starts, or if its rate rises above or falls below a level that can be preset or reset. However, most flow meters have an analog output that varies with the volume per unit of time.

Measuring the flow rate of a liquid can be challenging if the viscosity is very high, the liquid is chemically reactive, or the rate is very low. Such factors may require specialized equipment that is outside the scope of this Encyclopedia.

This entry compares the most popular sensing strategies.

Schematic Symbols

Many specialized symbols are used in flow diagrams to represent pumps, valves, and sensors. Typically they involve a single letter or an X in a circle. These symbols are not generally found in electronic schematics, and therefore they are not included here.

Paddlewheel Liquid Flow Rate Sensors

The simplest and most common liquid flow rate sensor uses a *paddlewheel*, also referred to as a *rotor*, that is mounted with its axis of rotation at 90 degrees to the direction of liquid flow. An example is the Koolance INS-FM16 shown in Figure 16-1. This sensor is intended for use in an aftermarket cooling system for the CPU in an overclocked desktop computer, but can be used in any system where the rate of flow ranges from 0.5 to 15 liters per minute. The paddlewheel has a pair of magnets mounted in it, activating a *reed switch* that is mounted in a sealed enclosure beneath the wheel. (For more information regarding reed switches, see "Reed Switch" in the entry describing **object presence** sensors.)



Figure 16-1 *A low-cost, simple paddlewheel sensor designed for rates of 0.5 to 15 liters per minute. The background grid is in millimeters.*

While the reed switch in the Koolance flow sensor inevitably suffers from contact bounce, it has the advantage of simplicity and can be used in conjunction with appropriate hardware or microcontroller code to debounce the pulse stream.

As in any device with a rotating part, friction and wear will afflict a paddlewheel sensor, especially because the bearings are often in the chamber through which the liquid passes. This eliminates the possibility for roller bearings. Typically a plain bearing is used, consisting of a pin that engages in a hole in the casing. Friction wears the bearing surface, creating a larger gap, which allows the rotor to vibrate or bounce instead of spinning smoothly. Flow resistance increases and accuracy is degraded.

In modern designs, the mass of the rotor is minimized to reduce the friction. Also, if the shaft is horizontal (but still at 90 degrees to the direction of the flow), buoyancy of the rotor in the liquid can reduce friction still further, as suggested in Figure 16-2. Ideally, the density of the rotor and the density of the liquid will be the same.



Figure 16-2 *In this configuration, friction on the rotor bearings is mitigated by taking advantage of the buoyancy of a low-density rotor in the liquid that passes through.*

The U-shaped flow path in the Koolance sensor in Figure 16-1 maximizes the responsiveness of the rotor, but an inline path is more common. An example is shown in Figure 16-3.



Figure 16-3 *An inline flow sensor rated for 3 to 6 liters per minute.*

Turbine Flow Rate Sensors

In a turbine-type sensor, two or more spiral blades are attached to a hub that rotates around an axis in line with the liquid flow, as shown in Figure 16-4. A magnet in each spiral blade triggers a reed switch or Hall-effect sensor mounted in a bracket that suspends the turbine from the interior walls of the tube.



Figure 16-4 *Simplified view of a turbine flow rate sensor mounted inside a tube.*

The support bracket often consists of four struts, which impose resistance to liquid flow. The bearings suffer from the same kinds of problems as the bearings in a paddlewheel sensor, and must withstand additional load resulting from the inline force exerted by flow. Overall, while the turbine type of sensor is popular in laboratory equipment, it has disadvantages that are not shared by the bulkier paddlewheel type.

Limitations of Paddlewheels and Turbines

Both the paddlewheel and turbine types of sensors require a minimum flow to overcome the friction in their bearings. Below this minimum, liquid will find its way around the rotor without turning it. Even when the flow exceeds the minimum, response of the rotor is likely to be nonlinear as a result of turbulence and other factors.

Above a limit stated by the manufacturer, turbulence increases to the point where output from the sensor is no longer meaningful. Wear on the bearing will also increase with flow rate.

A significant problem for these types of sensors is that they do not respond well to sudden variations in flow. The paddlewheel, in particular, has inertia as a function of the diameter of the rotor, and will take some time to spin up in response to an increase in flow. Conversely, when the flow diminishes, the paddlewheel will tend to overrun.

The viscosity of the liquid passing through a paddlewheel or turbine sensor will have a very significant effect on its performance.

Thermal Mass Liquid Flow Rate Sensor

The thermal-mass system is commonly used when volumes are extremely low. The system is illustrated in Figure 16-5. A tube containing liquid is fabricated from a heat-conductive metal such as aluminum. It is enclosed in a larger tube, and the gap between them is filled with thermal insulation. A temperature sensor such as a thermistor measures the temperature of liquid entering the system. A second sensor, combined with a small resistive heater in the form of a coil around the tube, is placed downstream. Liquid passing through the tube will tend to remove heat more effectively at higher flow rates, and the difference in temperature between the two sensors is a logarithmic function of the flow rate.



Figure 16-5 *In this type of low-flow sensor, the temperature differential between the two sensors is a logarithmic function of the flow rate.*

Variants of this system use slightly different tube configurations and sensor placement, but the principle is the same. Its advantages include the lack of any moving parts, and the avoidance of any probes intruding into the liquid, which is desirable in biochemical and medical applications.

The same principle is applied in many **gas flow rate** sensors. See "Mass Flow Rate Sensing".

Sliding Sleeve Liquid Flow Switch

This sensor is used in some domestic systems, where flow-activated water heating is required. A vertical section of brass (nonmagnetic) water pipe contains a sliding inner sleeve that incorporates a magnet. An external reed switch is activated when the sleeve is moved by water flowing through it. When the flow stops, the sleeve is returned to its rest position by the force of gravity.

Sliding Plunger Liquid Flow Switch

Figure 16-6 shows an exploded view of a similar device, using a plastic plunger that slides inside a nylon plumbing fixture designed for 3/4-inch pipe. The plunger contains a magnet and is restrained by a compression spring and a circular perforated plate. When water flow is sufficient to overcome the resistance of the spring, the plunger slides far enough for the magnet to activate a reed switch sealed into the external housing.

Ultrasonic Liquid Flow Rate Sensor

This type of sensor passes ultrasound through a liquid in a pipe. The speed of sound through the liquid is affected by the flow rate, and external electronics translate this lag time into a value for volume-per-minute. The system adjusts for variations in temperature that also affect the speed of sound.



Figure 16-6 *Parts of a flow switch. The small plunger is inserted into the pipe and retained with the perforated plate and compression spring.*

Various configurations are available, some allowing ultrasound sources and detectors to be clamped to the outside of a pipe, as shown in Figure 16-7. To eliminate other variables, one ultrasound pulse is transmitted in the same direction as the flow, followed by another pulse contrary to the flow, and the difference between the two transmission times is used as an indicator of the flow rate.



Figure 16-7 *Some ultrasound flow sensors are designed to be clamped externally to a pipe.*

Magnetic Liquid Flow Sensor

A magnetic field is induced in a metal pipe by a coil generating its field perpendicular to flow. The inside of the pipe is lined with nonconductive material in which two electrodes are mounted. Because water containing ions is conductive, the flow of water through the magnetic field induces a small potential difference between the electrodes. This voltage can be used as an indication of the flow rate.

To eliminate external factors that would also affect the potential difference, the polarity of current through the coil around the pipe alternates rapidly. The induced field remains the same regardless of the direction of the current.

A magnetic flow sensor should not be confused with a magnetic flow *switch.* Various types of switches are made, including large, heavy-duty devices where flow moves a magnet that triggers a shutoff valve. This type of industrial device is outside the scope of the Encyclopedia.

Differential Pressure Liquid Flow Meter

In this system, a pipe contains a perforated plate or some similar constrictor that partially obstructs the flow of liquid. Pressure is measured by a pair of pressure transducers placed before and after the constrictor. The pressure difference is an indicator of flow, because it increases as the flow rate increases.

This system was developed originally for large industrial applications but has been miniaturized and etched into silicon to measure very small flow rates. The Omron D6F-PH is an example, measuring less than 3cm square. It contains digital correction to enable a close-to-linear output. Because of its small size, it can be used only for slow flow rates, or as a bypass sensor. The general concept of a bypass sensor is illustrated in Figure 19-7, in the entry discussing gas flow sensors.

What Can Go Wrong

Vulnerability to Dirt and Corrosive Materials

MEMS liquid flow rate sensors containing very delicate, very small sensing elements are very vulnerable to contamination with dirt. Liquids should be filtered to minimize this risk. A manufacturer's datasheet should provide information about the use of corrosive or chemically active liquids.

gas/liquid pressure sensor

17

Pressure measurement devices that do not contain any electronics, such as a nondigital tire-pressure gauge or a mercury manometer, are outside the scope of this Encyclopedia.

Many pressure sensing methods can be used with both gases and liquids. To avoid duplication, gas pressure sensors and liquid pressure sensors do not have separate entries. Both types are described here.

This entry deals almost exclusively with MEMS components. It does not include pressure measurement devices sold as industrial products.

Some manufacturers and vendors use the term *pressure sensor* to describe a component that measures mechanical load or force. In this Encyclopedia, the term only describes components that measure liquid or gas pressure. Mechanical load cells and force sensors will be found in the section on **force** sensors. See Chapter 12.

OTHER RELATED COMPONENTS

- **liquid level** sensor (see Chapter 15)
- **liquid flow rate** sensor (see Chapter 16)
- **gas flow rate** sensor (see Chapter 19)

What It Does

A pressure sensor measures the force exerted by a gas or liquid, often in a container or pipe.

Static pressure is measured under conditions that change slowly or not at all. *Dynamic pressure* is subject to fluctuations. Pressure sensors tend to be designed for one condition or the other.

Schematic Symbols

Many specialized symbols are used in flow diagrams to represent pumps, valves, and sensors, including pressure sensors. Typically they involve a single letter or an X in a circle. These symbols are not generally found in electronic schematics, and therefore they are not included here.

Applications

Barometric sensors are found in barometers and weather stations. Altimeters are really a specialized form of barometric sensor, used in airborne vehicles. Gas pressure sensors have many industrial applications, and are used to monitor tire inflation in vehicles and the output from air compressors. They may also measure liquid pressure indirectly, as in a blood-pressure cuff.

Liquid pressure sensors are widely used to measure oil pressure in automobile engines and hydraulic braking systems. They have medical applications, and monitor water pressure in municipal systems and pumped supplies.

Design Considerations

As a result of random molecular movement, gases will tend to disperse to fill a container. After a gas reaches equilibrium, the pressure will be almost equal in all directions, affected only slightly by gravity. Where a gas is in a sealed, rigid container, pressure will vary linearly with temperature.

A liquid will tend to accumulate at the bottom of any container under the force of gravity. Liquid pressure in a container will be highest at the bottom, because of the weight of liquid above it. However, because almost all liquids are not easily compressible, they transmit force from any point in a container to any other point, including the sides of a container.

Units

Pressure is measured as force per unit area, which can be expressed in a confusing variety of units.

In the United States, gas and liquid pressure are still often expressed in pounds per square inch, abbreviated as PSI, or more often as psi, or sometimes as lb/in^2.

In standard international (SI) units, 1 bar of pressure is approximately equal to atmospheric pressure at sea level. Millibars are popular among meteorologists, 1 millibar being 1/1000 of a bar, equivalent to 100 pascals, where 1 pascal = 1 newton per square meter.

A bar is equivalent to 14.504 psi.

Blood pressure is measured in millimeters of mercury, because mercury manometers were used for this purpose originally. Atmospheric pressure may also be measured in millimeters of mercury, because the earliest barometers used a tube containing mercury. In the United States, some sources still refer to inches of mercury.

How It Works

Pressure sensing usually entails three stages.

1. A *sensing element* translates pressure into the mechanical displacement of a flexible part.
2. A *transducer* converts mechanical displacement into an electrical effect, either modifying resistance or creating a small voltage or current.
3. Electronics are used for *signal conditioning*. This may entail modifying a nonlinear signal, or may convert an analog output to a digital output.

As pressure sensors are increasingly taking the form of MEMS devices, all three stages may be combined in one silicon chip.

Basic Sensing Elements

Figure 17-1 shows four types of sensing elements that are used, or have been used, to convert pressure into mechanical motion. In each case, a green arrow shows where gas or liquid is introduced under pressure. 1: A Bourdon tube flexes under pressure, increasing its radius. The tube is hollow, open at one end and sealed at the other. 2: A coiled Bourdon tube uncoils partially under pressure, causing the top end to rotate. 3: A simple flat diaphragm. 4: A ribbed diaphragm.



Figure 17-1 *Sensing elements. See text for details.*

The sensing elements numbered 1 and 2 are less likely to be used in modern systems, although a coiled Bourdon tube may be used to turn a potentiometer in low-cost oil-pressure sensing designs. Number 3 is well suited to MEMS devices, as it can be etched into silicon using the principle illustrated in Figure 17-2.



Figure 17-2 *A section of a flat-diaphragm pressure sensor, viewed from the side. An aperture in the top face of the chip allows air to enter. The sensor is etched into silicon, and the deflection of the wafer is measured using embedded piezoresistors.*

Relative Measurement

Pressure is a relative measurement. It is expressed relative to a *reference pressure* of some kind. Three types of measurement are commonly used:

1. *Absolute pressure*, relative to the zero value of a vacuum.
2. *Gauge pressure*, relative to ambient pressure (that is, pressure in the environment around the sensor). Air pressure is the reference source for gauge pressure, and a *vent* is incorporated into the sensing system.
3. *Differential pressure*. In this case, the pressure being measured is relative to some other pressure—for example, the pressure differential between two sealed tanks.

Figure 17-3 illustrates these three measurement types.



Figure 17-3 *Three ways in which pressure is measured.*

Variants

Ambient Air Pressure

A *barometric* sensor measures the pressure of air around it. This is an absolute value, relative to a vacuum.

The earliest barometers consisted of a tube sealed at one end, containing mercury. No air was allowed to enter the tube. It was inverted so that its open end was immersed in a small reservoir that was open to the air, the pressure of which supported the column of mercury in the tube. Thus, the height of the column was ratiometrically equivalent to atmospheric pressure. Because low air pressure is often an indicator of inclement weather, a barometer was a very simple tool for weather forecasting.

A modern barometric sensor consists of a chip with a vent hole in its upper surface, allowing ambient air pressure to reach a sensor inside the chip. A popular example has been the Bosch BMP085, shown soldered onto a breakout board in Figure 17-4. The BMP180 has a very similar specification, the primary difference being that it is designed for a SPI bus instead of I2C. For additional details about protocols such as SPI and I2C, see Appendix A.



Figure 17-4 *A Bosch barometric sensor on a breakout board. The background grid is in millimeters.*

This sensor uses a supply voltage ranging from approximately 2VDC to 3.5VDC, but a breakout board includes a voltage regulator that tolerates a 5VDC supply. The output is digitized for access by a microcontroller, but the format is quite complex and consists of raw data that must be converted to air pressure by applying a formula. The manufacturer offers free code in the C language for this purpose. A thermometer that is built into the chip enables temperature compensation.

Subsequent products from Bosch include the BME280, which adds a humidity sensor. Breakout boards using this and other barometric chips are available from sources such as Sparkfun and Adafruit, where Arduino code libraries to interpret the data are available for download.

Altitude

A barometric sensor can be used to determine altitude. At sea level, air pressure is approximately 101kPa (kilopascals), or 760 millimeters of mercury. At 5,000 meters altitude, air pressure drops to 56kPa. The transition is nonlinear, changing most rapidly at lower altitudes.

Air pressure will be affected by temperature and weather conditions. Weather is unlikely to affect the value by more than plus-or-minus 1%, and temperature has a smaller effect; but the barometric sensor can be reset to a zero point based on current temperature and weather data.

Gas Pressure

Thousands of board-mountable gas pressure sensors are available from retail component suppliers. The need to make connections via tubing imposes a minimum size limit on these parts. Many have a through-hole format, but even the surface-mount variants can be relatively large (e.g., 10mm × 10mm). Most tend to have barbed tubing ports, the “barbs” being ridges to retain push-on flexible tubing. Output may be analog or digital, the digital protocol being designed for I2C, SPI, or plain TTL serial buses.

These components are designed for pressures ranging up to 500kPa (kilopascals). Some manufacturers use psi in their specifications, while others use bars and millibars, and a few state gas pressures equivalent to inches of water.

Dual-ported gas sensors for differential pressure measurement can be used for gauge measurement (i.e., relative to ambient air) if one port is left open. Absolute pressure sensors have only one port, as they measure pressure relative to a vacuum maintained inside the chip, behind the diaphragm.

- Some gas pressure sensors can do dual duty as liquid pressure sensors, but others cannot, and datasheets must be consulted carefully, as online vendors may not include this information prominently.

The sensor in Figure 17-5 by All Sensors Corporation is designed for flexible tubing with 1/16” internal diameter (1.6mm). Its pin spacing is 0.1” (2.54mm), making it breadboardable. This sensor is intended for gases only, but has a “10-inch” water-equivalent rating, meaning that it can tolerate a maximum pressure equivalent to that of a 10-inch (25.4cm) column of water.

When supplied with up to 16VDC, an internal Wheatstone bridge circuit provides an analog output that varies ratiometrically by a few millivolts over the full range of measurable pressures (the exact specification depending on the power supply). The output may be amplified with an external op-amp. Although this is a differential sensor, it can provide gauge pressure if one of the ports is left open.



Figure 17-5 *A gas pressure sensor for use with 1/16” (1.6mm) internal diameter flexible tubing. The background grid is in millimeters.*

The larger sensor in Figure 17-6 is in the ADCA range from All Sensors Corporation, designed for flexible tubing with 1/8” internal diameter (3.2mm). This is intended for gases only, and has a “5-inch” water-equivalent rating. It requires a 5VDC power supply and has an internal op-amp that provides an output that varies ratiometrically by 0.2VDC (centered on 4VDC) over the range of measurable differential pressures. Like its smaller cousin, it can provide gauge pressure if one of the ports is left open.



Figure 17-6 *A gas pressure sensor for use with 1/8" (3.2mm) internal diameter flexible tubing. The background grid is in millimeters.*

What Can Go Wrong

Vulnerability to Dirt, Moisture, and Corrosive Materials

MEMS pressure sensors containing very delicate, very small sensing elements must inevitably come into direct contact with gases and, in some cases, liquids. Datasheets will provide warnings regarding humidity and corrosive fluids, but the risk of contamination with dirt remains. Liquids should be filtered to minimize this risk.

Barometric sensors have a hole in the package, exposing the sensor element to the ambient air. This vent must be protected from direct contact with the environment.

Light Sensitivity

If light is allowed into the vent hole in a barometric sensor, it can create photocurrents in the chip. This will affect accuracy.

gas concentration sensor

18

Humidity sensors and *vapor sensors* are included in this entry, as they measure concentrations of a liquid while it is in its gas phase.

Sophisticated *industrial sensors* are available for accurate gas sensing, but this entry deals almost entirely with lower-cost solid-state sensors that are often classified as *board-mount* components.

OTHER RELATED COMPONENTS

- **gas/liquid pressure** sensor (see Chapter 17)

What It Does

Small semiconductor-based gas sensors provide a low-cost method for detecting specific gases in ambient air. The sensors vary their electrical resistance or capacitance in response to the concentration of the gas. They may be used in conjunction with an alarm system that will sound if gases such as *propane* or *carbon monoxide* exceed a preset level, or if the concentration of *oxygen* drops below a preset level.

Because vapor consists of a liquid in its gas phase, gas sensors can respond to vapor, as in the case of *alcohol sensors*.

A *humidity sensor* measures the amount of water vapor in the air, which can be important in refrigeration, HVAC (heating, venting, and air conditioning), medical equipment, meteorology, and storage rooms where art objects, antiques, or paper archives must be preserved in an environment that is neither too dry nor too moist, and is held at a constant temperature. Humidity control can be important also in climates where growth of mold is a concern. Humidity sensors are also used in automobile climate control and windshield defogging, and in the storage of food, fabrics, wood products, and medications.

High humidity coupled with high temperature contributes to the decomposition of many substances, while low humidity can cause desiccation. High humidity can also create damage if it causes materials to expand as a result of taking up moisture.

Many methods have been devised to detect individual gases, but semiconductor sensors are now dominant in applications where accuracy and gas-specificity are not crucial.

Schematic Symbol

No specific schematic symbol exists to represent a semiconductor gas sensor.

Semiconductor Gas Sensors

During the development of transistors in the 1950s, engineers noticed that semiconductor p-n junctions were sensitive to the presence of some gases in the atmosphere. This was regarded as a problem, which was solved by encapsulating transistors to prevent their exposure.

During the 1980s, Japanese law required installation of sensors in every home to detect hazardous concentrations of propane gas. This encouraged the development of cheap, long-lasting components that took advantage of semiconductor sensitivity.

Tin oxide is widely used in a variety of solid-state gas sensors. A sintered layer of the compound is deposited on a ceramic substrate in combination with other compounds such as antimony oxide. The granular layer functions as an n-type semiconductor in which electron transfer increases when certain gases are adsorbed among the grains. When the gas concentration diminishes, oxygen atoms displace the gas molecules, and the sensor returns to its original state. It is unimpaired by being activated, and has a life expectancy of at least 5 years during active (powered) use.

Each sensor includes a tiny resistive heater that is necessary for the chemical reaction to occur. Voltage must be applied to two pins that are connected with the heater. Two other pins connect internally with the sensing element. The resistance between these pins will vary with presence of the target gas; thus, this type of component has a resistive output.

It is a feature of semiconductor gas sensors that they tend to suffer from *cross-sensitivity*. That is, one sensor may respond to more than one gas. Manufacturers control this problem to some extent by adding filtering material around the semiconductor element, or by adjusting the proportions of dopants used in the semiconductor. Datasheets should be consulted carefully to see if a sensor may give false positives as a result of other gases that are likely to be present in the area where it will be used.

Figure 18-1 shows an MQ-5 propane sensor from Hanwei Electronics. The component also responds to methane, hydrogen, alcohol, and carbon monoxide, but with much less sensitivity. The manufacturer recommends calibrating the sensor by using a resistor ranging from 10K to 47K in series with the output resistance.



Figure 18-1 *A propane gas sensor. The background grid is in millimeters.*

Figure 18-2 shows an MQ-3 alcohol sensor, also manufactured by Hanwei. It has some sensitivity to benzene, but this is unlikely to be a problem, as benzene is seldom present in significant concentrations in ambient air. However, the response of the sensor to alcohol varies with temperature and humidity. Consequently this component can only be used as a "breathalyzer" if the user can be satisfied with an approximate response.

Semiconductor gas sensors are also available for detecting methane, carbon monoxide, hydrogen, ozone, and other gases.

These components are not low-current devices. Typically the internal heater in the Hanwei range has a resistance of slightly more than 30 ohms, and will draw 150mA to 160mA at 5V (i.e., slightly less than 1W). Because the heater is a simple resistive device, it can be used with AC or DC. The output resistance of the sensor can also be assessed with an AC or DC signal.



Figure 18-2 *An alcohol sensor. The background grid is in millimeters.*

A breakout board from Parallax simplifies the use of Hanwei gas sensors. The board is shown in Figure 18-3. It is compatible with carbon monoxide, propane, methane, and alcohol sensors, each of which can be plugged into a socket on the board. Two trimmers establish the sensitivity and the trip point for the sensing element, and the TTL output is then logic-high when a gas is detected, and logic-low otherwise.



Figure 18-3 *A Parallax breakout board to simplify the use of Hanwei gas sensors.*

Oxygen Sensors

Oxygen sensors are often built using a membrane made of zirconium dioxide. This material has the property that it can transport oxygen ions when heated. One setup is to have a zirconium membrane separating the gas to be measured from ambient air. This is a type of fuel cell, called a concentration cell or Nernst cell. If the oxygen concentration differs between the two sides of the membrane, oxygen ions will flow through it. Only oxygen ions can move—not neutral oxygen atoms or molecules. The ions are negatively charged, so the transport will lead to a potential difference over the cell, which can be measured with platinum electrodes.

To comply with emissions regulations, automobiles sense the oxygen level of exhaust gases. This data controls the fuel-air ratio in the fuel injection system. Too much air results in the formation of nitrogen oxides, while too little air results in excessive carbon monoxide.

Humidity Sensors

Moisture content of the air is expressed in three different ways:

Absolute humidity

This is the weight of water vapor in a fixed volume of air. It is measured in grams per cubic meter in the metric system. An absolute humidity sensor is properly called a *hygrometer*.

Dew point

If a sample of air is cooled without a change of pressure, the dew point is the temperature at which moisture will start to condense. The dew point is a way of describing how humid the ambient air is currently, as water will condense more readily in humid conditions.

Relative humidity

This is often referred to by its acronym, RH. If temperature, pressure, and volume of a sample of air remain constant, relative humidity is the ratio between the current value of absolute humidity and the hypothetical level where the addition of water vapor would result in condensation. The ratio is expressed as a percentage. Thus, if moisture is already condensing in an air sample, relative humidity is 100%. If an air sample contains half the weight of moisture required for condensation to begin, relative humidity is 50%. If there is no moisture at all in the air, relative humidity is 0%.

Colloquial usage of the term “humidity” usually means relative humidity, and sensor output is usually convertible to this value. However, some absolute humidity sensors do exist.

Dew-Point Sensor

Historically, meteorologists used a *chilled mirror hygrometer*, in which a metal mirror was exposed to the atmosphere and cooled until the surface was seen to become misty with condensation. The temperature where this occurred was the dew point.

This system is still used in conjunction with an LED and a **phototransistor**. The LED is positioned so that its light reflects from a mirror, directly onto the phototransistor. The mirror is cooled until mist starts to form, which diffuses the reflected light and causes a well-defined change in output from the phototransistor.

Although the formula linking dew point with relative humidity is complex, a simplified approximation is available that is reasonably accurate so long as the relative humidity is 50% or greater. If RH is the relative humidity, t is the current temperature, and t_D is the dew-point temperature at which mist forms:

$$RH = 100 - (5 * (t - t_D)) \text{ approx.}$$

Although a chilled-mirror dew-point sensor has a reputation for being accurate, it is heavy, expensive, and impractical for most applications outside of meteorology.

Absolute Humidity Sensors

An absolute humidity sensor may use two NTC (negative temperature coefficient) **thermistors** in a Wheatstone bridge circuit. One thermistor is sealed in a compartment containing dry nitrogen, with zero humidity. The other is exposed to the atmosphere. Current passing through the thermistors raises their temperature to at least 200 degrees Celsius. Because heat radiates less efficiently when there is moisture in the air, the exposed thermistor will run hotter, and its resistance will be higher, at higher levels of humidity. This type of sensor is used in clothes dryers and wood kilns, among other applications.

See Chapters 23 and 24 for more information about thermistors.

Relative Humidity Sensors

Two main types of sensing elements are used to measure relative humidity: resistive and capacitive.

In a *resistive* sensing element, a thin layer of polymer, salt, or other hygroscopic substance is deposited on a substrate consisting of ceramic or other unreactive material. When the substance absorbs water, its electrical conductivity increases. Voltage is applied to the sensing element, and AC is used to avoid polarizing it. The current flow is processed externally, with conversion to DC followed by linearization, meaning that the current is processed to establish an almost linear relationship with gas concentration, with temperature compensation factored in. Alternatively, these functions can be performed by hardware built into the sensor, and a digital value for relative humidity can be accessed by an external microcontroller.

In a *capacitive sensor*, once again a thin film of polymer or metal oxide is deposited on a ceramic or glass substrate, but the film functions as a *dielectric* between two metal electrodes that serve as the plates of a capacitor. The dielectric value changes as the film absorbs moisture, and this causes the capacitance to vary, typically by 0.2pF to 0.5pF for each 1% change in relative humidity. This is almost a linear relationship extending over the entire range from 0% to 100% relative humidity.

The actual capacitance value at 50% relative humidity is likely to be between 100pF and 500pF. The sensor may be excited with AC from an external source, or can be incorporated in a chip that derives AC from a DC power supply and provides a digital output.

To determine the dew point or absolute humidity from a value for relative humidity, ambient temperature must also be measured. A chip such as the Si7005 from Silicon Labs includes a temperature sensor with a relative-humidity sensor based around a capacitor in which polyimide film forms the dielectric. If condensation forms, an on-chip heater will cause it to evaporate so that normal operation can resume. Data from the chip is supplied via an I2C interface.

Humidity Sensor Output

When the output is analog, resistance or capacitance of the internal sensing element is available via two pins or solder pads on the sensor. The analog value must be converted to a value for relative humidity by performing a calculation that takes the current temperature into account. The component may or may not include a temperature sensor.

With a digital output, an internal analog-to-digital converter can be accessed by a microcontroller via serial, I2C, or SPI interface. Alternatively, the sensor may communicate values using pulse-width modulation. Either way, the output is a value for relative humidity, calculated on the chip with reference to an onboard temperature sensor.

Analog Humidity Sensor

The Humirel HS1101 is a low-cost analog-output humidity sensor that varies its internal capacitance between approximately 160pF and 200pF as relative humidity increases from 0% to 100%. The response is almost linear, with the curve steepening slightly when humidity exceeds 80%. The component is shown in Figure 18-4.



Figure 18-4 *A Humirel HS1101 humidity sensor. The background grid is in millimeters.*

The manufacturer claims a recovery time of 10 seconds after 150 hours of condensation. In other words, the performance of the sensor should be restored to its original specification.

A microcontroller can evaluate the output by measuring the charge time of the internal capacitor in the sensor. If the sensing element is wired in parallel with a 10M resistor, this will allow the capacitor to discharge before the microcontroller charges it again. A 220-ohm series resistor should be used between the microcontroller and the sensor, to limit the charge current. This circuit is illustrated in Figure 18-5.

Alternatively, the sensor manufacturer suggests using the capacitance value to control the output frequency of a 555 timer. A counter or microcontroller may be used to count the number of pulses per unit of time.



Figure 18-5 *Using a microcontroller to measure the charge time of a gas sensor with capacitive output.*

The Honeywell HIH4030 is a surface-mount humidity sensor with a more convenient analog voltage output that increases almost linearly from approximately 0.8VDC at 0% humidity to 3.8VDC at 100% humidity, assuming a 5VDC power supply. The sensor is available on a miniature breakout board from Sparkfun, shown in Figure 18-6.



Figure 18-6 *The Honeywell HIH4030 on a breakout board from Sparkfun.*

Design Considerations

As relative humidity is temperature-dependent, a relative-humidity sensor must have the same temperature as the air it measures. Many datasheets recommend that when a sensor is mounted on a printed circuit board, slots should be milled around it to minimize heat transfer to it. The sensor should also be mounted as far away as possible from heat-generating components.

Where a capacitive humidity sensor with an analog output is located some distance from the electronics that will process its output, shielded cables or twisted pair cables should be used to minimize capacitance in the wiring. A decoupling capacitor between the supply voltage and ground close to the sensor can help to keep the supply voltage stable.

Digital Humidity Sensor

The AM2302, available from Adafruit, is a capacitive humidity sensor with a digital output accessible by a microcontroller via the I2C protocol. Onboard electronics calculate relative humidity with reference to an included temperature sensor. This component is pictured in Figure 18-7.



Figure 18-7 *A low-cost humidity sensor with temperature-compensated digital output. From a photograph by Adafruit.*

What Can Go Wrong

Contamination

A semiconductor gas sensor can be damaged by exposure to volatile chemical vapors. This would be unusual in a domestic environment, but is still an important consideration, as there will be no obvious indication that damage has occurred.

Recalibration

If a humidity sensor is exposed to very high humidity where condensation occurs, some datasheets advise a baking procedure, where the sensor is placed in warm, dry air for several hours and then allowed to rehumidify.

Soldering

Semiconductor gas sensors should be soldered quickly and at a controlled temperature, to minimize heat transfer.

gas flow rate sensor

19

Sensors that contain no electronic components are not included in this entry.

A **gas flow rate** sensor may often be described as a *mass flow* sensor or *mass flow rate* sensor. Although it measures volume rather than mass, the mass of gas can be calculated so long as its temperature and pressure are controlled.

Some methods of gas flow sensing can also be applied to liquids, but sensors are usually designed for one application or the other. Therefore, **liquid flow rate** sensors have their own entry. See Chapter 16.

An *anemometer* is a gas flow rate sensor that measures air speed. It is included in this entry.

Many gas flow rate sensors are large devices designed for industrial applications. This entry focuses mostly on lower-cost solid-state sensors that are often classified as *board-mount* components.

OTHER RELATED COMPONENTS

- **liquid flow rate** sensor (see Chapter 16)

What It Does

A **gas flow rate** sensor measures the volume of gas flowing past or through the device, usually inside a pipe. In most applications, users wish to know the mass of the gas that is passing per unit of time. Consequently a gas flow rate sensor is very often identified as a *mass flow rate* sensor. If it functions by heating the gas and measuring the heat dissipation, it is a *thermal mass flow rate sensor*.

A sensor that measures the flow of open air is often described as an *anemometer*. Its output will be expressed as a velocity, not as a volume or mass.

Applications

Mass flow rate sensors are used frequently for laboratory and medical applications, although the reliability and affordability of thermal mass flow rate sensors is now making them attractive for metering municipal gas supplies.

Anemometers are used mostly in meteorology, aviation, and on boats.

Schematic Symbol

Many specialized symbols are used in flow diagrams to represent pumps, valves, and sensors, but they are not schematic symbols of the type generally found in electronic circuit diagrams, and are not included here.

How It Works

Because an anemometer functions so differently from a gas flow rate sensor that is enclosed in a pipe, the two types of sensors will be discussed separately.

Anemometer

The name of this device is derived from the Greek word *anemos*, meaning "wind." The *cup anemometer* was invented in 1846, using four hemispherical cups attached to horizontal arms rotating on a vertical shaft. The rate of rotation was proportional to wind speed over a substantial range, but the conversion factor between wind speed and RPM varied depending on the size of the cups and their distance from the shaft.

Anemometer design was simplified to three cups in 1926 and was modified in 1991 by adding a tag to one cup. This causes the speed of rotation to fluctuate as the tag rotates through the wind stream, and the direction of the wind can be calculated from the speed fluctuations. Not all anemometers rely on this principle, however, and a separate wind vane can be used to determine wind direction.

The basic design of a modern anemometer is illustrated in Figure 19-1.



Figure 19-1 *The basic design of a metereological cup anemometer.*

Anemometers traditionally used a mechanical counter to log the number of rotations, which were checked at fixed intervals to derive the wind speed. The output of a modern anemometer may be achieved by generating AC or DC power, or from *Hall-effect sensors* (see "Hall-Effect Sensor" for a full discussion of Hall-effect sensors).

Handheld Anemometer

A digital handheld anemometer for personal use is shown in Figure 19-2. A cup anemometer made by Vaavud for use with a mobile phone (with appropriate software) is shown in Figure 19-3.



Figure 19-2 *A handheld digital anemometer.*



Figure 19-3 *A cup anemometer sold as an accessory for smartphones.*

Ultrasound Anemometer

The movement of air affects the speed of sound, enabling calculation of both wind direction and wind velocity by using an array of ultrasound emitters and receivers. The lack of rotating parts promises greater reliability, and in Figure 19-4 an ultrasound anemometer manufactured by Biral Metereological Sensors also includes heaters so that it will be immune to snow or ice accumulation during freezing conditions.



Figure 19-4 *Made by Biral Metereological Sensors, this anemometer uses ultrasound to determine wind speed and direction.*

Ultrasound anemometers have been built on a DIY basis by hobbyists, typically using off-the-shelf ultrasound emitters and an Arduino to decode the signals. Several of these projects are documented online.

Hot Wire Anemometer

A hot wire anemometer measures the cooling effect of the air. It heats a thin wire by passing current through it, and measures the heating power needed to keep the temperature constant.

It is also possible to keep either the voltage over the wire or the current constant, and to assess the wire temperature. The temperature can be measured directly or calculated from the wire's resistance, which increases as the wire gets hotter.

Mass Flow Rate Sensing

A mass flow rate sensor measures the flow speed of a gas. When this is multiplied by the density, the mass flow rate can be calculated.

Most sensors of this type heat the gas and are categorized as *thermal mass flow rate* sensors. The gas passes over a *thermopile* (consisting of several thermocouples wired in series), then a heater, and then another thermopile. These components are miniaturized and can be etched into a chip measuring 2mm square or less.

The temperature difference between the two thermopiles increases as the flow of gas becomes faster and transports more heat to the second thermopile. This is known as the *heat transfer principle*, illustrated in Figure 19-5.



Figure 19-5 *In a thermal mass flow sensor, the flow of gas heats the thermopiles disproportionately, and the temperature difference can be used to evaluate the rate of flow.*

This principle is used also in a liquid thermal mass flow rate sensor, described in "Thermal Mass Liquid Flow Rate Sensor".

An example of a thermal mass flow rate sensor is shown in Figure 19-6.



Figure 19-6 *A thermal mass flow rate sensor made by the Chinese manufacturer Zhengzhou Winsen Electronic Technology Co. Ltd.*

Applications

In medicine, mass flow rate sensors are used in anesthesia delivery, respiratory monitoring, sleep apnea machines, ventilators, and other devices. Industrial uses include air-to-fuel ratio measurement, gas leak detection, and gas metering.

While the metering of municipal gas supplies was traditionally done with all-mechanical devices, MEMS-based meters are replacing many of the 400 million mechanical gas meters estimated to exist worldwide.

Units

Mass flow rate sensors are often rated in SLM, meaning standard liters per minute. A "standard liter" has a temperature of 0 degrees Celsius and a pressure of 101.325 kPa (kilopascals). This pressure is equivalent to that of air at sea level. Because temperature and pressure are specified, the mass of a gas in a standard liter can be calculated by knowing the density of the gas. Thus SLM is a way of measuring mass flow, even though it is a measurement of volume.

The acronym SLPM is also used, but it means the same thing as SLM. SLs and SLPs are measurements of standard liters per second, while SCCM refers to standard cubic centimeters per minute.

Measuring Higher Volumes

MEMS sensors are typically equipped with inflow and outflow nozzles suitable for flexible tubing of 3mm or 5mm internal diameter. The nozzles are "barbed," meaning that they have ridges to retain the tubing.

Small tubing can only deal with low flow rates. A few sensors are threaded for standard plumbing pipes, and can accept volumes of up to 10 liters per minute. They are a minority. A low-rate sensor can still be used to measure higher volumes if it is supplied with just a percentage of the primary flow. This principle is illustrated in Figure 19-7, where an adjustable vane in the main pipe creates a pressure differential. A narrower, constricting section of pipe could have a similar effect, but it would not be adjustable.



Figure 19-7 *A vane in a primary pipe can divert a percentage of the flow to a sensor.*

Output

Many mass flow sensors have an analog output consisting of a voltage that varies ratiometrically with gas flow. With a typical 5VDC power supply, output voltage may vary from around 1VDC to 4VDC.

Some sensors now incorporate analog-to-digital converters and data processing to provide SLM digital values, accessible from a microcontroller via an I2C interface.

What Can Go Wrong

The primary risk for gas flow rate sensors is damage caused by particles and contaminants in the gas stream. A 5-micron filter is recommended. A *dust segregation system* can also be used, consisting of a small compartment containing semicircular centrifugal chambers. Dust tends to follow the outer edge of the flow path, while the flow sensor is placed on the inner side of the path.

photoresistor

20

A **photoresistor** has a function similar to that of a **phototransistor**, but as its name implies, it is a purely passive component that varies its resistance in response to light.

The term *photocell* was used formerly, but has been displaced by the term **photoresistor**, which describes its function more accurately. The term *photoconductive cell* is sometimes used, or *light-dependent resistor* (or its acronym, *LDR*).

OTHER RELATED COMPONENTS

- **resistor** (see Volume 1)
- **photodiode** (see Chapter 21)
- **phototransistor** (see Chapter 22)

What It Does

Formerly known as a *photocell*, a **photoresistor** is a disc-shaped component with two leads. When light falls on the surface of the disc, resistance between the leads will diminish. Some photoresistors have a resistance in darkness as high as 10 megohms. A few have a resistance in bright light as low as 500 ohms, although several kilohms would be more common.

A photoresistor is less sensitive to light than a **phototransistor** or **photodiode**, and unlike them it is a passive component with no polarity. It presents equal resistance to current in either direction, and may be used with DC or AC.

Because cadmium sulfide is commonly used in this component and is regarded as hazardous to the environment, photoresistors are now unavailable in some regions (notably, Europe). However, at the time of writing, they are still available from many Asian sources, and from some importers in the United States.

Schematic Symbol

Six schematic symbols for a photoresistor are shown in Figure 20-1. They are functionally identical, regardless of whether the single slanting arrow across the resistor symbol is omitted.



Figure 20-1 *All six symbols for a photoresistor are functionally identical.*

How It Works

Cadmium sulfide is a semiconductor. When exposed to light, more charge carriers are excited into states where they are mobile and can participate in conduction. As a result, electrical resistance decreases.

Construction

A closeup of a photoresistor appears in Figure 20-2. The brown material is a layer of cadmium sulfide deposited onto a ceramic base. The silver material is a conductive compound evaporated onto the cadmium sulfide to form two interlocking electrodes, in a pattern that maximizes the length of the boundary between each of them and the semiconductor. The electrodes connect with leads projecting from the back of the component.



Figure 20-2 *Closeup of a photoresistor. Two interlocking electrodes are mounted on a brown semiconductor layer.*

Variants

Figure 20-3 shows a variety of photoresistors, illustrating the range of sizes available. Small photoresistors may be less than 5mm in diameter; large ones may be 25mm in diameter. The size generally suggests the ability of the component to pass current.



Figure 20-3 *Photoresistors are available in a wide range of sizes. The component in the center is shown at the same scale as the others. Generally speaking, larger components are able to conduct higher currents. The background grid is in millimeters.*

Photoresistors in Optical Isolators

An *optical isolator*, popularly known as an *optocoupler*, contains an LED opposite to a photoresistor, in a sealed package. This is discussed in Volume 2. A *Vactrol* is a similar component, except that the LED is placed opposite to a photoresistor. An example is shown in Figure 20-4.



Figure 20-4 *A Vactrol, containing an LED opposite to a photoresistor. The background grid is in millimeters.*

Vactrol is a brand name owned by its initial manufacturer, Vactec. It was developed to control a vacuum tube, hence its name. In the 1950s, Vactrols were used in guitar amplifiers to control tremolo.

Because of the relatively slow response time of a photoresistor, and its sensitivity to temperature, optical isolators based on photoresistors are not used in digital devices. They still retain some utility in audio components and music equipment, where the ability of the photoresistor to pass AC is an advantage and its response time is adequate.

Values

Datasheets for a few photoresistors can still be found from some suppliers, such as Digi-Key, but are mostly unobtainable, as major semiconductor companies have stopped making these components. Vendors may quote basic values, but in the absence of part numbers or a manufacturer name, a buyer cannot verify the information.

The resistance range can be determined by testing a sample component. A typical range would be from 50K in a light intensity of 10 lux, up to 1M in darkness. Maximum power dissipation is likely to range from 100mW for a small photoresistor to 500mW for a large one.

Maximum voltage may be as high as 200V, but photoresistors will work just as well at low voltages.

Comparisons with a Phototransistor

Slower response

A photoresistor typically takes several milliseconds to respond to bright light, and can require more than 1 second to regain its dark resistance. A phototransistor is much more responsive, and a photodiode is faster still.

Narrower range of resistance

The maximum resistance of a photoresistor is almost always significantly lower than the effective maximum resistance of a phototransistor in darkness, and the minimum resistance is likely to be significantly higher than that of a phototransistor in bright light.

Greater current-carrying capacity

Often a photoresistor is rated for twice as much current as the output from a phototransistor.

Not directional

Because a photoresistor is not packaged with a lens, it is sensitive to incident light from anywhere in front of it. If an application requires that light sensitivity should be confined within a narrow angle while the component is insensitive to incident light from other directions, a phototransistor or photodiode should be used.

Temperature dependent

The resistance of a photoresistor varies more with temperature than the effective resistance of a phototransistor.

Cost

At this time, photoresistors are likely to be more expensive than phototransistors.

Lack of information

Photoresistors are often sold without means of checking their specification in a datasheet.

How to Use It

While the effective resistance of phototransistors and photodiodes varies with the applied voltage, photoresistors present the same resistance for a particular light intensity regardless of the voltage applied. This property has made them suitable for use in “stomp box” guitar-effects pedals.

Because the minimum resistance of a photoresistor in bright light tends to be relatively high, and because its response time is quite slow, it is suitable primarily as an analog component rather than as a switch.

In principle, any resistor in a circuit can be replaced by a photoresistor, and its smooth response to light variations would make it suitable, for example, as the resistance in an RC oscillator circuit, where it would determine the charge time of a capacitor. The frequency of the circuit would thus become light-dependent.

Cadmium sulfide photoresistors respond most actively to wavelengths of light ranging from 400nm to 800nm. This is especially important where an **LED indicator** is used as a light source, as LEDs often emit an extremely narrow range of wavelengths. (See the entry for LED indicators in Volume 2.)

Choosing a Series Resistor

To convert light intensity into a voltage, a photoresistor can be connected in series with a regular resistor, to form a voltage divider. There are two ways to do this, as shown in Figure 20-5. On the left side of this figure, light falling on the photoresistor will cause the output voltage to rise. On the right side, light will cause the output to drop.



Figure 20-5 *Using a photoresistor to create a variable voltage. See text for details.*

If R_{MIN} is the minimum photoresistor value in the brightest light that will be used, and R_{MAX} is the maximum value in the dimmest light that will be used, a simple formula can be used to find R_S, the optimum value for a series resistor, which will provide the widest range of voltage values at the center of the voltage divider:

$$R_s = \sqrt{R_{min} * R_{max}}$$

What Can Go Wrong

Overload

Because a datasheet may be unavailable, a photoresistor may have to be used on a trial-and-error basis. A test-to-destruction approach may be necessary to determine the limits of the component.

Excessive Voltage

Exceeding the maximum rated voltage for a photoresistor, even for a short time, can cause irreversible damage. Depending on the component, overvoltage can range from 100V to 300V.

Confusion Among Components

Because photoresistors often have no part numbers printed on them and may be sold in miscellaneous assortments, one component may be easily confused with another that has different characteristics. Where two or more photoresistors are used in one device, their characteristics should be measured to determine whether they are functionally identical.

photodiode

21

OTHER RELATED COMPONENTS

- **diode** (see Volume 1)
- **photoresistor** (see Chapter 20)
- **phototransistor** (see Chapter 22)

What It Does

Light falling on a **photodiode** causes it to generate a very small current. This is often called the *photovoltaic effect*. The component functions like a solar panel; in fact, a solar panel can be thought of as being an array of very large photodiodes.

Often, a DC power source is used to apply *reverse bias* to a photodiode. This enables the component to deliver more current. It is now operating in *photoconductive* mode.

Schematic Symbols

Schematic symbols for a photodiode are shown in Figure 21-1. Wavy arrows are often (but not always) used to indicate infrared light.



Figure 21-1 *Symbols representing a photodiode.*

Applications

The rapid response of photodiodes makes them suitable for use in optical disc drives, telecommunications, infrared data transfer, digital cameras, and optical switches. Many sensors in this Encyclopedia use a photodiode. **Proximity** sensors, optical encoders, and light meters are examples.

How It Works

When light falls on a semiconductor, it can excite an electron to a higher energy state. The electron then becomes mobile, and leaves behind an *electron hole* (See the entry discussing **diodes** in Volume 1.)

In photovoltaic mode, incident light creates pairs of electrons and electron holes in the semiconductor material. The electrons move to the cathode of the diode while the holes move to the anode, creating voltage between the two. Note that this happens to some extent even in the absence of visible light, as the photodiode may respond to infrared radiation. The tiny amount of current created without visible light is called *dark current*.

In photoconductive mode, light falling on the photodiode creates pairs of electrons and electron holes in the semiconductor material. These will move in opposite directions due to the bias voltage, which means a small current flows through the diode.

Photoconductive mode enables a faster response than photovoltaic mode, because reverse-bias voltage makes the depletion layer wider, which in turn decreases the capacitance. (The same effect is used in *capacitance diodes*.)

Simplified circuits showing the component in photovoltaic mode and photoconductive mode appear in Figure 21-2.



Figure 21-2 *Two modes in which a photodiode may be used. In photovoltaic mode, voltage between the two pins must be measured.*

Variants

PIN Photodiodes

Like *PIN diodes*, PIN photodiodes incorporate an undoped (intrinsic) semiconductor layer between the p- and n-doped layers. They are more sensitive and have faster responses than regular PN photodiodes. Many of the photodiodes available are of the PIN type.

Avalanche Diodes

When light enters the undoped region of the avalanche photodiode, it triggers the creation of electron-hole pairs. When electrons migrate toward the *avalanche region* of the diode, the cumulative field strength increases their velocity to the point where collisions with the crystal lattice create further electron-hole pairs.

This behavior causes the avalanche diode to be more sensitive than a PIN photodiode. However, the sensitivity also makes it vulnerable to electrical noise, and it is significantly affected by heat. A guard ring is added around the p-n junction, and a heat sink is often used.

Packages

Many surface-mount and through-hole versions are available. A selection is shown in Figure 21-3 and Figure 21-4. While a through-hole photodiode may look indistinguishable from a through-hole 3mm or 5mm LED, versions are available without lenses, and some are sensitive to incident light coming from the side (they are referred to as *side-looking* or *side-view* variants).



Figure 21-3 *Two sample photodiodes. Left: top-view unfiltered Vishay BPW34. Right: Osram BPX43 in metal can suitable for temperatures up to 125 degrees Celsius.*



Figure 21-4 *Two side-looking photodiodes. Left: Vishay BPV22NF with lens. Right: Vishay BPW83 without a lens. Both have daylight-blocking filters.*

Wavelength Range

In order for a photon to be detected by the photodiode, it must carry enough energy to be able to create an electron-hole pair. This energy is a property specific to the semiconduct material, and is known as its *band gap*. Additionally, the epoxy packaging of the photodiode may be designed to block some wavelengths of light. Often, an application will require that the component should only respond to infrared light, not visible light.

Photodiode Arrays

A *photodiode array* has several photodiodes mounted in a row or in a grid, for imaging or measurement applications. A row of photodiodes may be used in a flatbed scanner, where it is moved relative to the reflective object being scanned.

In some arrays, photodiodes are available with color filters preinstalled, to facilitate full-color scanning using the transmitted primary colors.

Output Options

Because the output from a photodiode must be processed to be usable, options exist to convert it to a more convenient form, such as a wider range of voltages, a square wave signal where the frequency is proportional with light input, or a binary value accessible by a microcontroller via a serial bus such as I2C. For a discussion of sensor outputs see Appendix A.

Specific Variants

Light to Frequency

The Taos TSL235R is a 3-pin, through-hole chip. It combines a photodiode with logic that creates a square-wave pulse train in which frequency is proportional to the light intensity.

Logarithmic Light Meter

The Sharp GA1A1S202WP light sensor has an output voltage that changes logarithmically with the light level. This gives the sensor a large dynamic range, from 3 lux to 55,000 lux, without requiring a high-resolution analog-to-digital converter. (Human perception of light and sound levels is approximately logarithmic.) This is a surface-mount chip, but is available on a breakout board from Adafruit.

Ultraviolet to Analog

The ML8511 from Lapis Semiconductor combines an ultraviolet-sensitive photodiode with an op-amp that provides an output voltage from approximately 1V to 3V, varying with ultraviolet intensity. A breakout board containing this surface-mount chip is available from Sparkfun and many other sources.

Ultraviolet to Digital

The SI1145 from SiLabs combines ultraviolet sensing with data processing to create a UV index, readable from a microcontroller with I2C. Adafruit offers it on a breakout board.

Color to Digital

The Taos TCS3414FN module contains photodiodes sensitive to red, green, blue, and clear (no filtering). Four 16-bit analog-to-digital converters, one for each channel, provide a digital output accessible over an I2C bus. This module can be used to determine the color of ambient light with some accuracy.

Color to Analog

The Taos TCS3200 also uses red, green, blue, and clear photodiodes but encodes the output from each as a square wave in which the frequency corresponds with the light intensity. The surface-mount chip is available on a breakout board from Robot Shop, shown in Figure 21-5.



Figure 21-5 *This breakout board from Robot Shop uses the Taos TCS3200 chip to analyze the color of incident light.*

Values

Abbreviations found in datasheets are included in the list below, with values in parentheses for an Osram SFH229FA infrared photodiode, which resembles a 3mm through-hole LED. It has a peak sensitivity of 880nm and appears black to the human eye, being opaque to wavelengths of light shorter than 700nm, the red end of the visible spectrum.

In Figure 21-6 the SFH229FA is shown beside the SFH229, which has the same peak sensitivity of 880nm but is encapsulated in an untinted module, allowing a sensitivity that tapers gradually to below 400nm, in the green part of the visible spectrum. With the exception of their spectral range, the two photodiodes have identical specifications.



Figure 21-6 *Osram infrared photodiodes SFH229 (left) and SFH229FA (right). The background grid is in millimeters.*

- Typical forward voltage: V_F (1.3V)
- Typical photocurrent: I_P (20µA)
- Maximum power dissipation: P_{TOT} (150mW)
- The *half angle* is measured from the axis of the photodiode to the angle at which the sensitivity has dropped by 50% (plus or minus 17 degrees)
- Dark current: I_R (50pA)
- Wavelength of maximum sensitivity: $\lambda_{S\ MAX}$ (880nm)
- Response speed is the rise and fall time of photocurrent: t_r and t_f (10ns)

Infrared photodiodes exist with a variety of peak wavelengths. They are designed to function in conjunction with an LED that has a matching wavelength.

The angle of sensitivity depends on the geometry of the package.

Rise and fall speeds are important for high-speed measurement, signaling, or data transfer. The rise and fall time of a typical photodiode can be 1,000 times faster than that of a phototransistor. See “Values” in Chapter 22 for a comparison. Note also that the dark current of a photodiode is much lower than that for a phototransistor.

How to Use It

In photoconductive mode, the photodiode can be connected in series with a suitable resistor so that a voltage divider is formed, as shown in Figure 21-2. The voltage at the output will then vary almost linearly with the intensity of the light.

In the photoconductive mode of operation, the output signal is generally measured in millivolts and microamperes. This signal needs to be amplified, usually with an **op-amp** (described in Volume 2).

Figure 21-7 shows simplified schematics for a standard voltage amplifier, in section 1, and a transimpedance amplifier, in section 2.

A transimpedance amplifier measures the current through the photodiode and converts it into a voltage, without the need for a voltage divider. Advantages include less noise, and no need to determine the value of a voltage-divider resistor.

The output voltage of this amplifier is calculated by using this simple formula:

```
V = R * Ip
```

R is the value of the feedback resistor, which determines the gain of the amplifier.



Figure 21-7 *Simplified op-amp circuits for use with photodiodes.*

What Can Go Wrong

Photodiodes can be hard to distinguish from phototransistors and LEDs, in particular infrared ones. They are typically not marked with type numbers. Using a meter may not be helpful, as regular LEDs behave similarly to photodiodes.

Decision procedure:

1. Does the component conduct in either direction while shielded from light? If so, it is a diode and not a phototransistor or photodiode.
2. Pass a weak current (e.g., 4mA) in the forward direction. If it emits visible or infrared light, it's an LED. (Infrared light may be visible when using a digital camera, or can be detected with a known phototransistor or photodiode.) If the package is clear but cloudy so that the die cannot be seen, it is probably a white LED in which the cloudiness is the fluorescent pigment converting blue light into white.

phototransistor

22

OTHER RELATED COMPONENTS

- **photodiode** (see Chapter 21)
- **photoresistor** (see Chapter 20)
- **passive infrared** sensor (see Chapter 4)
- **transistor** (see Volume 1)

What It Does

A **phototransistor** is a transistor controlled by exposure to light. (**Transistors** are described in Volume 1.) It can be either a bipolar transistor or field-effect transistor (FET), and its body is often superficially similar in appearance to a 3mm or 5mm **photodiode** or **LED indicator** encased in resin or plastic. (LED indicators are described in Volume 2.) However, some phototransistors are encased in a metal shell with a window in it.

The window or the plastic body is either transparent to visible light, or may appear black if the component is intended for use only with infrared while blocking visible wavelengths. A selection of phototransistors is shown in Figure 22-1 (left: Optek/TT Electronics OP506A with a broad spectral response centered around 850nm; center: Vishay TEKT5400S with a side-view lens; right: Vishay BPW17N).

Typically a phototransistor has two leads that connect internally with its collector and emitter (or source and drain, in the case of an FET). The base of the transistor (or the gate of an FET) responds to light and controls the flow of current between the leads.



Figure 22-1 *A variety of phototransistors. The background grid is in millimeters. See text for details.*

In the absence of light, a bipolar phototransistor permits leakage between collector and emitter of 100nA or less. When exposed to light, it conducts up to 50mA. This alone differentiates it from a photodiode, which cannot pass much current.

Schematic Symbols

Symbols for a phototransistor are shown in Figure 22-2. They are functionally identical, with the exception of type C, where an additional connection to the base is included. Often (but not always), wavy arrows indicate infrared light.



Figure 22-2 *Schematic symbols for a phototransistor.*

Applications

A phototransistor may be used for light measurement or as a light-sensitive switch.

Often the output from a phototransistor is used in conjunction with a *microcontroller* containing an analog-to-digital converter.

Where a clean on-or-off signal is required, a phototransistor can drive the input of a logic chip that contains a *Schmitt trigger*, or it can be processed by a **comparator**.

An *optocoupler* or **solid-state relay** (described in Volume 1) usually contains a phototransistor that is activated by an internal LED. Its purpose is to switch current while electrically isolating one section of a circuit from another.

How It Works

Like a photodiode, the phototransistor responds to light when the light generates electron-hole pairs in the semiconductor material. For a bipolar NPN phototransistor (the most common variant), the important region for pair generation is the reverse-biased collector-base interface. Photocurrent generated here acts as current injected into the base of an ordinary transistor, and permits a larger current to pass from the collector to the emitter.

The behavior of a phototransistor can be visualized as being similar to a photodiode controlling an ordinary bipolar transistor, as shown in Figure 22-3.



Figure 22-3 *A phototransistor is functionally similar to a photodiode controlling an ordinary transistor.*

Variants

While surface-mount variants are very widely available, through-hole packaging also remains common. When encapsulated like an LED indicator, a phototransistor gathers light from a relatively narrow angle. Variants with a flat surface are sensitive to light from almost any direction in front of the component.

Optional Base Connection

The base of a phototransistor is usually not accessible. However, some variants provide a base connection (or gate connection, in an FET) in addition to the collector and emitter (or the source and drain, in an FET). This third connection allows the application of a bias current, which can prevent low light levels from triggering the transistor.

Photodarlington

A photodarlington is a pair of bipolar transistors, the first being sensitive to light while the second acts as an amplifier for the first. This configuration is very similar to that of a *Darlington transistor* (described in Volume 1). The two-stage design makes it more sensitive to light than a regular phototransistor, but makes the response slower and less linear.

PhotoFET

A field-effect phototransistor is sometimes identified as a *photoFET*. They are relatively uncommon as separate components, but are used in optocouplers, because they have some interesting properties:

- Provided the applied voltage is low enough (less than 0.1V) the photoFET works as a controllable resistance—in contrast to bipolar transistors, where the current is controlled, and is relatively independent of the applied voltage.
- The FET transistor is symmetrical, functioning similarly for signals of either polarity. This makes an FET optocoupler suitable for AC signals.

Values

Abbreviations found in datasheets are included in the list below, with values in parentheses for an Osram SFH300FA infrared photodiode, which resembles a 5mm through-hole LED. It has a peak sensitivity of 880nm and appears black to the human eye, being opaque to wavelengths of light shorter than 700nm, the red end of the visible spectrum.

In Figure 22-4 the SFH300FA is shown beside the SFH300, which has the same peak sensitivity of 880nm but is encapsulated in an untinted module, allowing a sensitivity that tapers gradually to 450nm, in the green part of the visible spectrum. With the exception of their spectral range, the two phototransistors have identical specifications.



Figure 22-4 *Osram infrared phototransistors SFH300 (left) and SFH300FA (right). The background grid is in millimeters.*

- Maximum collector-emitter voltage: V_{CE} (35V)
- Maximum collector current: I_C (50mA)
- Maximum power dissipation: P_{TOT} (200mW)
- The *half angle* is measured from the axis of the photodiode to the angle at which sensitivity has dropped by 50% (plus or minus 25 degrees)

The angle of sensitivity depends on the geometry of the package. For phototransistors that resemble an LED indicator, with a rounded end that acts as a lens, typical values are plus-or-minus 20 degrees.

- Dark current (when the phototransistor receives no incident light): I_{CE0} (1nA)
- Wavelength of maximum sensitivity: $\lambda_{S\ MAX}$ (880nm)

Infrared phototransistors exist with a variety of peak wavelengths. They are designed to function in conjunction with an LED that has a matching wavelength.

- Response speed is the rise and fall time of photocurrent: t_r and t_f (10 µs)

Behavior Compared to Other Light Sensors

An extended list of comparisons between a photoresistor and a phototransistor will be found in the entry on **photoresistors**. See "Comparisons with a Phototransistor".

A photodiode has a close-to-linear electrical response over a much wider range of intensities of light than a phototransistor. Consequently, photodiodes tend to be the component of choice in applications where measurement of light must be wide-ranging and precise.

Photodiodes can pass less current than a phototransistor, but also tend to draw less current, making them appropriate in battery-powered devices that must draw as little current as possible.

Rise and fall speeds are important for high-speed measurement, signaling, or data transfer. The rise and fall time of a typical phototransistor can be 1,000 times slower than that of a photodiode. See "Values" in Chapter 21 for a comparison. Note also that the dark current of a phototransistor is much higher than that for a photodiode.

The ability of a phototransistor to sink 20mA to 50mA at its output is useful where it will be connected to a component that has relatively low impedance. For instance, a phototransistor can drive a piezoelectric audio transducer directly, or an LED indicator.

Unlike a photodiode, a phototransistor is a solid-state switch. Its saturation voltage (listed in datasheets as $V_{SE(SAT)}$ as described above) is the voltage drop between collector and emitter, and seldom exceeds 0.5V.

Binning

Small variations that occur during the fabrication process can cause inconsistency in the performance of phototransistors that share the same part number. To provide a more consistent response, manufacturers use *binning*, meaning that units sharing the same bin number are likely to share a tighter tolerance. (The same concept is used to minimize variations in **LED area lighting**, described in Volume 1.)

Datasheets will provide information on the availability and meaning of bin numbers, if available.

Bins with higher photocurrents typically have longer response times.

How to Use It

Most phototransistors are bipolar devices with an *open collector output*. That is, the collector of the transistor is accessible from one of the two leads, making it "open" to being used. See Figure A-4 for general instructions on using an open-collector output. A summary relating to phototransistors is included here.

The schematic in Figure 22-5 shows the basic concept. The resistor is referred to as a *pullup resistor*. When the phototransistor is receiving very little light, its effective resistance is high. Consequently almost all the current flowing through the pullup resistor will go to any device attached to the output, and the output voltage will seem to be "high."



Figure 22-5 *How an open-collector output works.*

If the phototransistor is exposed to a significant light source, the effective resistance between the collector and emitter drops dramatically, and the phototransistor will sink current to ground. Consequently, the output will seem to be "low."

The pullup resistor is necessary between the power source and the collector pin to protect the phototransistor from sinking excessive current when it is exposed to light. The ideal value of the resistor will depend partly on the impedance of any device attached to the output.

In this scenario, exposure to light causes low output whereas darkness causes high output. What if we wish to have it the other way around?

The protective resistor can be moved to the emitter pin, where it becomes a pulldown resistor. It will still protect the phototransistor from passing excessive current, so long as the output is connected to a high impedance. The output is taken from the emitter pin, and will transition from low to high when the component is exposed to light. This is illustrated in Figure 22-6.



Figure 22-6 *Moving the resistor and taking an output from the emitter pin inverts the behavior of a phototransistor. Any device attached to the output must have a relatively high impedance to protect the phototransistor from excessive current.*

Output Calculation

Using an open-collector output, the photocurrent is almost independent of the applied voltage V_{CE}, provided that the voltage is higher than the saturation voltage $V_{CE(SAT)}$, which is typically between 0.4V and 0.5V.

If the pullup resistor has value R, the voltage across it is

$$U = R * I_P$$

where I_P is the photocurrent passed by the phototransistor.

When choosing R, one should consider the range of currents expected in the light conditions that will be measured, and the voltage range suitable for the next stage of the circuit. 10K is a reasonable starting point (e.g., when measuring light intensity with a microcontroller's analog input). The resistor value can be reduced from there, if necessary.

The value of the pullup resistor must also be chosen to restrict current within the limits specified by the phototransistor datasheet. A value for the resistor guaranteed to be safe is

```
R = V / I~MAX~
```

where V is the supply voltage and I_{MAX} is the maximum allowed current. With this value, the resistor limits the current to the highest allowed value, even if the phototransistor is brightly illuminated and assumed to conduct perfectly.

When V = 5V and I_{MAX} = 15mA, R should be at least 330 ohms.

What Can Go Wrong

Visual Classification Errors

Phototransistors can be visually similar to LEDs and photodiodes. They are easily confused, as neither type of component is usually marked with any identification number. The entry for **photodiodes** describes a system for distinguishing the three types of components. See "What Can Go Wrong" in Chapter 21.

Output Out of Range

The output voltage from a phototransistor will depend on the intensity of incident light, the value of any pullup resistor that is used, and the supply voltage. While a circuit is being developed, the light range may seem predictable, but in actual use the output range may not fall within expectations.

NTC thermistor

23

PTC thermistors, in which the resistance increases as the temperature increases, have a separate entry. See Chapter 24.

A *resistance temperature detector* or **RTD** has a resistance that increases as its temperature increases, but it is not usually classified as a thermistor, because its sensing element is fabricated differently. Its entry will be found at Chapter 26.

Semiconductor temperature sensors and **thermocouples** each have their own entries.

Infrared temperature sensors and **passive infrared** motion sensors have their own entries. They are *noncontact* temperature sensors that respond to infrared radiation.

OTHER RELATED COMPONENTS

- **PTC thermistor** (see Chapter 24)
- **infrared temperature** sensor (see Chapter 28)
- **passive infrared** motion sensor (see Chapter 4)
- **semiconductor** temperature sensor (see Chapter 27)
- **thermocouple** (see Chapter 25)
- **RTD** (resistance temperature detector) (see Chapter 26)

What It Does

An NTC thermistor is the most common type of discrete-component temperature sensor, and is usually the most affordable. Its resistance diminishes as its temperature increases. This behavior is referred to as a *negative temperature coefficient*, which is the source of the acronym NTC.

This is a simple, passive component that is not polarized. It requires no separate power supply, but an external device must pass a small AC or DC current through it to determine its resistance. This is known as an *excitation current*.

Schematic Symbols

Schematic symbols for a thermistor are shown in Figure 23-1. Those in the top row may still be found in the United States, but are being replaced by the European variants in the second row. The addition of -t° to the symbol indicates an NTC type of thermistor, while +t° indicates that it is the PTC type, with a positive coefficient (see Chapter 24). If no indication is shown, the thermistor is likely to be the NTC type.



Figure 23-1 *Schematic symbols representing a thermistor. Letter t preceded by a plus or minus sign indicates whether the thermistor is the PTC or NTC type, respectively.*

Applications

Thermistors monitor temperature in air-conditioning systems, clothes washers, refrigerators, pool and spa controls, dishwashers, toasters, and other domestic devices. They are used in laser printers, 3D printers, industrial process controls, and medical equipment.

As many as 20 thermistors may be found in a modern automobile, measuring temperature in locations ranging from the transmission to the ambient air in the passenger compartment.

Comparison of Temperature Sensors

In this Encyclopedia, contact temperature sensors, which measure temperature by making contact with the source, are divided into five main categories, each of which has a separate entry. For convenience, these categories are listed in a comparative summary at the end of this entry. See "Addendum: Comparison of Temperature Sensors".

How an NTC Thermistor Works

Although the term *thermistor* suggests that it is a thermally sensitive resistor, in fact an NTC thermistor is a semiconductor.

Some metal oxides, such as ferric oxide or nickel oxide, become n-type semiconductors when they are treated with dopants. The exact mix is a proprietary secret of each manufacturer. Raising the temperature of this kind of material increases the number of charge carriers in it, promoting electron mobility and thus lowering its effective resistance.

To create a thermistor, the metal oxide mix is heated until it melts and turns into a ceramic. Typically a thin sheet is cut into small pieces for individual sensors. After two leads are connected, the assembly is dipped into epoxy or encapsulated in glass. The most common packages consist of a glass bead, surface-mount chip, or ceramic disc.

Figure 23-2 shows three NTC thermistors. At left is a Murata NXFT15XH103FA2B100 approximately 1mm in diameter, with a reference resistance of 10K and a tolerance of plus-or-minus 1%. At center is a Vishay NTCALUG03A103GC rated 10K at 2%, fitted with a mini-lug. At right is a TDK B57164K153K rated 15K and 3%.



Figure 23-2 *Sample NTC thermistors. See text for details. The background grid is in millimeters.*

Output Conversion for Temperature Sensing

Ideally, the electrical behavior of a temperature sensor should be a linear function of temperature. Thermistors fail in this respect, as their resistance is an approximately inverse exponential function. This is illustrated in Figure 23-3, where the measured resistance of a thermistor rated for 5K at 25 degrees is plotted against temperatures from 0 degrees to 120 degrees Celsius.

- In many datasheets, graphs of this kind may appear flatter because they are customarily plotted against a vertical logarithmic scale.



Figure 23-3 *Resistance of a thermistor from 0 to 120 degrees Celsius.*

To monitor the resistance of a thermistor, it can be placed in a simple voltage divider as shown in Figure 23-4, where the fluctuating resistance of the component creates a fluctuating voltage at point A.

- The voltage can be used as an input to a microcontroller that contains an analog-to-digital converter. Alternatively it can be connected directly to a solid-state relay, or amplified with an op-amp, or can be passed through a comparator to create an adjustable switching threshold.

Although this circuit is a voltage divider, it is also known as a *half bridge*, as it is half of a Wheatstone bridge.



Figure 23-4 *A half-bridge circuit for determining the resistance of a thermistor.*

If V_{CC} is the supply voltage, V_T is the measured voltage at point A, R_T is the resistance of the thermistor, and R_K is the constant value of the series resistor, the basic formula for a voltage divider looks like this:

$$V_T = V_{CC} * (R_T / (R_T + R_K))$$

By transposing terms, a formula can be derived to obtain a value for R_T from the measured voltage and the value of R_K:

$$R_T = (R_K * V_T) / (V_{CC} - V_T)$$

Choosing a Series Resistor

The value for R_K in the formula should be chosen to provide a reasonably wide response over the range of temperatures for which the thermistor is likely to be used. To calculate R_K, another formula must be applied. If R_{MIN} is the resistance of the thermistor at the lowest likely temperature, and R_{MAX} is its resistance at the highest likely temperature:

$$R_k = \sqrt{R_{min} * R_{max}}$$

(This is the same formula as suggested in Figure 20-5 to find the value of a series resistor for use with a photoresistor.)

Wheatstone Bridge Circuit

The half-bridge circuit has the disadvantage that it does not compensate for nonlinearity of a thermistor. Voltage values will change rapidly at the low end of the temperature range, but will change more slowly at the high end, requiring an analog-to-digital converter with a high degree of accuracy to distinguish one voltage value from the next.

A full Wheatstone bridge circuit has a nonlinear output that compensates, somewhat, for the inverse nonlinearity of the thermistor. Referring to the circuit shown in Figure 23-5, the three resistors R_K are chosen using the formula above.



Figure 23-5 *A thermistor may be placed in a full Wheatstone bridge circuit. Outputs A and B are often connected with the two inputs of an op-amp or comparator.*

A standard formula provides the relationship between R_T, the resistance of the thermocouple; V_{CC}, the supply voltage; R_K, the fixed resistances; and V_{AB}, the output voltage measured between points A and B:

$$V_{AB} = (V_{CC} / 2) * (R_T - R_K) / (R_T + R_K)$$

From this formula, a version can be derived to calculate R_T by measuring the output voltage, V_A:

$$R_T = R_K * (V_{CC} + (2*V_{AB})) / (V_{CC} - (2*V_{AB}))$$

- The polarity of V_{AB} is reversible, depending on whether R_T is greater or less than R_K. To accommodate this, A and B can be connected to the two inputs of a comparator or op-amp.

Deriving the Temperature Value

After the resistance of the thermistor has been calculated, it can be converted to a temperature value. The datasheet for a thermistor will usually provide a table showing temperature values tabulated against resistance values, so that a lookup table can be created in a microcontroller program.

Alternatively, a datasheet usually includes constants that can be inserted in a resistance-to-temperature conversion equation, but this is nontrivial and requires natural logarithms, which may not be available in a language implemented on a particular microcontroller.

Inrush Current Limiter

NTC thermistors with appropriate characteristics can be used to limit the inrush of current that tends to occur when a circuit is switched on and large capacitors in the power supply charge very quickly.

An *inrush current limiter* is also known as a *surge limiter*, or may be referred to by its acronym, *ICL*. It is an NTC thermistor whose initial resistance diminishes rapidly as its temperature increases.

While NTC thermistors are the type most often used for inrush limiting, PTC thermistors can serve this purpose if wired differently. See "PTC Inrush Current Limiting". The remainder of this discussion refers only to NTC current limiters.

A suitable NTC thermistor can be placed as shown in the simplified schematic in Figure 23-6, where a rectified AC source is connected with a DC-to-DC converter, and a large smoothing capacitor is used. Initially the thermistor has resistance that is sufficient to limit current and generate heat. But the rise in temperature causes the resistance of the thermistor to fall. Eventually it reaches a steady state where it remains sufficiently warm to maintain a low resistance that imposes a negligible load on the circuit.



Figure 23-6 *Placement of an NTC thermistor that is designed for inrush current limiting.*

In thermistors that are used for temperature measurement, self-heating is an undesirable attribute. By contrast, an inrush current limiter depends on self-heating to perform its function.

The TDK B57237S509M inrush limiter, shown in Figure 23-7, is rated for 5A and has an initial resistance of 5 ohms at 25 degrees Celsius while not passing current. When tested with a 2,800μF capacitor at 110VAC, its resistance drops to a minimum of 0.125 ohms at 5A. The relationship between current and resistance is shown in Figure 23-8.



Figure 23-7 *A TDK B57237S509M NTC thermistor designed as an inrush current limiter, rated 5 ohms at 5 amps. The background grid is in millimeters.*



Figure 23-8 *This graph shows the relationship between resistance and current in a TDK B57237S509M inrush limiter.*

Restart

If a protected device is switched off momentarily and is then switched on again, the thermistor cannot provide protection, as it has not had time to cool down and regain its resistance. However, during the 30 seconds to 2 minutes required for heat in the thermistor to dissipate, smoothing capacitors are unlikely to lose much of their charge. Therefore, if the device is restarted, an inrush of current should not occur.

Thermistor Values

Datasheets for thermistors may be more complex and cryptic than for many components.

When examining a datasheet, first check to see if the thermistor is described as being suitable for temperature measurement or inrush current limiting. A component designed for temperature measurement will not survive inrush current, while one designed for inrush current limiting will have a very low resistance making it unsuitable for temperature measurement.

Time and Temperature

In most datasheets, lowercase letter t is used for values relating to time, whereas an uppercase T is used for values relating to temperature. Unfortunately, T may also be used as an abbreviation for "thermistor."

Resistance and Response

Letter R often means resistance, but may indicate response time, depending on the context in which it is used. For example, R_T is the resistance of a thermistor, and t_R is a response time.

Kilohms and Kelvin

Letter K may be used to represent temperature in degrees Kelvin, 0 degrees on the Celsius scale being approximately 273 degrees Kelvin. However, letter K is also used to represent thousands of ohms, sometimes in the same datasheet. In both instances, K is capitalized.

Reference Temperature

This is the temperature at which many attributes of the component are measured, such as its temperature coefficient and resistance. Usually the reference temperature is 25 degrees Celsius, but in some cases it may be 0 degrees, and other values are occasionally used. The term is abbreviated T_{REF}.

Reference Resistance

The reference resistance for a thermistor (sometimes described as its nominal resistance) may be referred to as R_R, and is the resistance at the reference temperature. It may be referred to as the "R value," but in thumbnail product descriptions it can be cited simply as "Resistance."

In datasheets, R25 or R_{25} is the resistance at 25 degrees Celsius. If this is the reference temperature, R_R and R_{25} will be the same.

Dissipation Constant

DC is the *power dissipation constant*, a ratio normally expressed as milliwatts per degree Celsius (written as mW/°C). This is a measurement of how much thermal power the thermistor can transfer to the environment for a 1 degree increase in temperature.

Temperature Coefficient

TC may be used as an acronym for the *temperature coefficient*, which represents the sensitivity of the thermistor. (Sometimes TCR is used instead of TC, the letter R denoting resistance. The two acronyms both mean the same thing.) The value is the percentage change in resistance for each change in temperature of 1 degree Celsius. Thus, if the resistance of a thermistor drops from 800 ohms to 768 ohms when the temperature increases from 28 to 29 degrees Celsius, TC = -4%. For NTC thermistors, which have a resistance that decreases when temperature increases, the temperature coefficient is negative. However, the minus sign may be omitted.

The coefficient may be expressed in parts per million (abbreviated ppm) instead of as a percentage. To convert parts per million to a percentage, divide by 10,000. Thus, a figure of 50,000ppm is equivalent to 5%.

Thermal Time Constant

Unfortunately TC is also used to represent the thermal *time constant*. If T_D is the temperature difference between the thermistor's initial temperature and a new, higher ambient temperature in which it finds itself, TC is the time it takes for the thermistor to add 63.2% of T_D to its current temperature. TC is expressed in seconds, and is defined without power being applied to the thermistor. A low thermal time constant is characteristic of a physically small thermistor that acquires heat rapidly. (TC is very similar to the concept of a time constant for a capacitor acquiring charge. See the entry on **capacitors** in Volume 1.)

Tolerance

The *tolerance* of a thermistor is a measure of its accuracy, usually at 25 degrees Celsius, unless a range of temperatures is stated. A thermistor rated for 5K, with a tolerance of plus-or-minus 1% at 25 degrees, may be found to have an actual resistance ranging from 4,950 to 5,050 ohms at that temperature. Some thermistors have a tolerance of plus-or-minus 20%. A tolerance better than plus-or-minus 1% is relatively rare.

Temperature Range

The *working temperature range* of any thermistor that uses silicon dioxide is usually between about -50 and +150 degrees Celsius (slightly wider for versions encapsulated in glass, and slightly narrower if accuracy is important).

Switching Current

For a thermistor with a nonlinear response, the switching current is the approximate current that forces a sharp transition in resistance. It is represented by I_S.

Power Limitations

Operating current is the maximum current recommended to avoid self-heating. The *power rating* is the maximum allowed power (usually 100mW to 200mW).

Interchangeability

To measure temperature reliably, two thermistors of the same type, from the same manufacturer, should display the same characteristics. This is known as *interchangeability*. A value of plus-or-minus 0.2 degrees Celsius is common for a modern thermistor, but is not often mentioned in a datasheet.

What Can Go Wrong

Self-Heating

Self-heating can affect the accuracy of an NTC thermistor that is used for temperature measurement. To get accurate temperature readings, keep the current as small as possible. When the resistance of a thermistor is at the high end of its range, brief pulses of current can be used.

Heat Dissipation

Where a thermistor is used for inrush current limiting, it will create some heat during the whole time that a device is switched on. If insufficient air space is allowed between the thermistor and other components, they may be affected.

Lack of Heat

An NTC thermistor will sometimes fail as an inrush current limiter. In very cold climates, it may never become warm enough for its resistance to drop to an acceptable level. Conversely, in a very hot location (such as close proximity to a hot-water pump) it may not get cool enough to provide adequate initial protection.

Addendum: Comparison of Temperature Sensors

A chart illustrating the five main types of contact sensors, and their variants, is shown in Figure 23-9.



Figure 23-9 *Five types of contact temperature sensors (green boxes) and the variants (red).*

NTC Thermistor

The electrical resistance of an **NTC thermistor** diminishes as its temperature increases. Thus, it has a *negative temperature coefficient*, which is the source of the acronym NTC.

An NTC thermistor is traditionally used where low cost and simplicity are desirable and a relatively limited temperature range is acceptable (often -50 to +150 degrees Celsius). It has the advantage of familiarity, having existed in its present form for many decades. It remains the lowest-cost option among the various types of temperature sensors, and can be connected directly with an external device such as a solid-state relay, in which case no microcontroller is necessary.

PTC Thermistor

The sensing element for a positive-coefficient thermistor is a polycrystalline compound that increases in resistance very rapidly above a threshold temperature. This makes it suitable for blocking a high current to prevent circuit overload.

A *silicon temperature sensor*, sometimes called a *silistor*, can be considered as a PTC thermistor, in that it is a resistive component with a positive temperature coefficient. Its sensing element is etched into silicon.

PTC thermistors are passive, nonpolarized components with two leads or solder pads. For more information about them, see Chapter 24.

Thermocouple

This sensor consists of two wires made from different metals, joined at one end. The differing thermoelectric properties of the wires creates a very small voltage between their free ends. Thermocouples have the widest range of any contact sensor. They are simple, robust, and free from self-heating effects, as they consume no power. Their response is rapid, but very nonlinear, and their sensitivity is limited. They are used in industry and in laboratories, often plugged into a panel meter that combines a digital temperature display with hardware to decode the signal from the type of thermocouple being used.

For more information about thermocuples, see Chapter 25.

Resistance Temperature Detector

Often known by its acronym **RTD**, and sometimes referred to as a *Resistive Temperature Device*, it commonly uses a sensing element fabricated from pure platinum, nickel, or copper. The element may consist of wire wound around a core, or a very thin film deposited on an insulating substrate.

An RTD has a positive temperature coefficient, as its resistance increases while its temperature increases. It is very accurate and stable, providing an almost linear output, especially near the center of its range. However, its sensitivity is often one-tenth of that of an NTC thermistor.

Like a thermistor or a thermocouple, an RTD is a passive device, able to operate at a wide range of voltages and requiring no power supply. It is nonpolarized, with two leads or solder pads.

For more information about resistance temperature detectors, see Chapter 26.

Semiconductor Temperature Sensor

This is a chip-based sensor that requires no additional components to linearize its output, as linearization is performed in the chip.

The temperature range is similar to that of an NTC thermistor, but the output is a variable voltage with a positive temperature coefficient of about 20mV per degree Celsius, supplied by a built-in op-amp. Response time is 4 to 60 seconds.

This type of sensor requires a power supply, typically of 5VDC or less. It does not have to be calibrated before use, as it is trimmed during the production process to achieve accuracy that can be better than that of a thermistor. Manufacturers may claim plus-or-minus 0.15 degrees over the whole temperature range, which is usually -50 degrees Celsius to +150 degrees, but may be less for variants in which accuracy is more important.

The linear analog output is very convenient for use with a microntroller that has an analog-to-digital converter, and the relatively low cost makes this type of sensor increasingly competitive with thermistors.

An analog-to-digital converter may be included on the sensor chip, in which case it is often described as a *digital temperature sensor* or *digital thermometer*, with an output in degrees Celsius (or, sometimes, Fahrenheit) accessible via I2C or SPI bus. For additional details about protocols such as I2C and SPI, see Appendix A.

A *digital thermostat* or *thermostatic switch* is a semiconductor temperature sensor with a binary output that transitions from logic-high to logic-low (or vice-versa) if the temperature goes above a maximum or below a minimum level. The level can be programmed into the chip.

Semiconductor temperature sensors are identified with a variety of other names. For more information, see Chapter 27.

PTC thermistor

24

A *silistor*, or *silicon-based thermistor*, is included in this entry as a form of **PTC thermistor**.

A *resettable fuse* is not quite the same as a PTC thermistor. For more information, see the entry on **fuses** in Volume 1.

NTC thermistors, in which the resistance decreases as the temperature increases, have a separate entry. See Chapter 23.

A *resistance temperature detector* or **RTD** has a resistance that increases as its temperature increases, but it is not usually classified as a thermistor, because its sensing element is fabricated differently. Its entry will be found at Chapter 26.

Infrared temperature sensors, **semiconductor temperature** sensors, and **thermocouples** each have their own entries.

OTHER RELATED COMPONENTS

- **infrared temperature** sensor (see Chapter 28)
- **semiconductor** temperature sensor (see Chapter 27)
- **thermocouple** (see Chapter 25)
- **NTC thermistor** (see Chapter 23)
- **RTD** (resistance temperature detector) (see Chapter 26)

What It Does

The electrical resistance of a PTC thermistor increases as its temperature increases. Variants can measure temperature or can protect circuits by detecting excessive heat or current.

Because a PTC thermistor is a resistive sensor, it has no polarity. Current may flow through it in either direction, or AC may be used.

Schematic Symbols

The schematic symbol for a PTC thermistor is very similar to the symbol for an NTC thermistor. See Figure 23-1.

Comparison of Temperature Sensors

In this Encyclopedia, contact temperature sensors are divided into five main categories, each of which has a separate entry. For convenience, a comparative summary is included in the entry for

NTC thermistors. See "Addendum: Comparison of Temperature Sensors". Also see Figure 23-9.

PTC Overview

PTC thermistors can be subdivided into two groups:

- *Linear*, with a chip-sized silicon-based sensing element. They are sometimes referred to as *silistors*. The component has a very linear response and is used for temperature measurement. It may be connected directly to a microcontroller.

- *Nonlinear*, mostly using a sensing element containing barium titanate in a polycrystalline compound that increases in resistance very sharply above a threshold temperature. This type of sensor may be described as a *switching thermistor*, because its nonlinear output can activate a switching device.

The sensing elements in positive-coefficient thermistors are different in principle from the element in an NTC thermistor.

Nonlinear thermistors are used in two different ways:

Externally heated

The thermistor responds to ambient heat or to the temperature of a device to which it is attached. It can be used to protect a circuit or a motor from overheating. Current through the thermistor is minimized to avoid self-heating.

Internally heated

The thermistor responds to its own temperature caused by current passing through it. It can activate a warning signal or shut down equipment in the event of a short circuit. It can also control current for starting a motor or a fluorescent tube, and is sometimes used as a source to create localized heat.

Silistor for Temperature Measurement

A silicon-based PTC thermistor, sometimes known as a *silistor*, provides a highly desirable, almost linear relationship between temperature and resistance. A popular example is the KTY81 series from NXP, a sample of which is shown in Figure 24-1.



Figure 24-1 *A KTY81 thermistor from NXP. The background grid is in millimeters. Note the amputated center lead.*

The response of this thermistor is shown in Figure 24-2.



Figure 24-2 *Resistance of the KTY81 thermistor in response to temperature.*

Note that this graph is plotted with a linear vertical scale, unlike the performance curves for many thermistors that are plotted with a log scale. The log scale tends to make a response curve look flatter.

The sensor is a silicon chip designed on the “spreading resistance principle,” in which current fans out from a metal contact through a thin layer of silicon to a metallized bottom plane. This effect progresses less actively as the temperature increases. Although the result is partly dependent on polarity, a second metal contact is biased in the opposite direction, and when the two active regions of the chip are wired in series, the result is a component that has no polarity.

- The almost-linear output of this type of sensor makes it easy to use with a microcontroller that has a built in analog-to-digital converter.

Tolerance ranges from plus-or-minus 1% to 5%, depending on the temperature. Variants have a typical reference resistance of 1K or 2K. The temperature coefficient is commonly about 1%, which is considerably lower than that of a typical NTC thermistor, where 4% is common.

- Guidance on reading thermistor datasheets will be found in the entry describing NTC thermistors. See “Thermistor Values”.

For correct operation, a typical silistor requires a current ranging from around 0.1mA to 1mA.

- The lower sensitivity and slightly higher price of a PTC temperature-measurement thermistor, compared with an NTC thermistor, may explain why the NTC type seems to remain more popular, with many more variants available. In addition, the NTC type is much more tolerant of variations in current.
- Silistors continue to find some automotive applications, measuring oil temperature, transmission temperature, and climate control, among other parameters.

As a simple strategy to determine its resistance, a series resistor can be used with a PTC sensor to create a voltage divider. The circuit is identical to that used for NTC thermistors. See “Output Conversion for Temperature Sensing”.

RTDs

A *resistance temperature detector* or **RTD** is sometimes classified as a PTC thermistor. However, it has a different type of pure-metal sensing element, much lower sensitivity, and is discussed in a separate section of this Encyclopedia. See Chapter 26.

Nonlinear PTC Thermistors

Over-Temperature Protection

This type of nonlinear thermistor is externally heated, but has a switching function. If it is incorporated among other components on a circuit board, its output can be used to activate a warning signal, or can trigger a relay to shut down the circuit until the temperature subsides. This is of special interest for battery chargers where excessive heat can often be a problem, but is also useful in electronic devices generally.

To avoid the possibility of self-heating, current passing through the thermistor must be minimized to a few milliamps.

Some thermistors in the Vishay PTCSL series will make a transition at a temperature as low as 70 degrees Celsius. Others will be triggered by temperatures above 100 degrees. A typical response curve is shown in Figure 24-3, where resistance rises from 100 ohms at 25 degrees to around 1K at the transitional reference temperature of 90 degrees, and reaches at least 4K at 105 degrees.



Figure 24-3 *The relationship of resistance to heat in an over-temperature protection thermistor.*

To respond to this transition, the manufacturer recommends a Wheatstone bridge circuit with its outputs connected to a comparator, as suggested for an NTC thermistor in Figure 23-5. The comparator can then activate a signal or a relay.

A picture of the PTCSL20T091DBE thermistor appears in Figure 24-4.



Figure 24-4 *A thermistor in the PTCSL range from TDK. It is color coded using a proprietary scheme by the manufacturer to indicate a reference temperature of 90 degrees Celsius. The background grid is in millimeters.*

This type of thermistor can tolerate a maximum of 30V (AC or DC).

Over-Current Protection

This type of nonlinear thermistor is a substitute for a fuse, as it responds to internal heat created by current passing through it. If the flow of current is excessive, the resistance of the thermistor increases, throttling the flow. When the over-current problem is resolved, the thermistor returns to its normal state. Whereas a fuse must be placed in a location allowing replacement, the thermistor is unharmed by its transition and does not have to be replaced.

Over-current may occur as a result of failure of other components, such as a rectifier diode or a capacitor, or can occur in situations such as a DC motor locking up.

The B598 series from TDK can tolerate voltages over 240V, AC or DC. They typically respond when currents exceed 100mA to 1A, depending on the specific component (a few fall outside that range), and many can withstand 1A to 7A. The B59810C0130A070 pictured in Figure 24-5 is switched by 980mA, can tolerate as much as 7A, and has a reference resistance of 3.5 ohms, rising above 10K when excessive current causes sufficient heat.



Figure 24-5 *A large over-current protection PTC thermistor. The background grid is in millimeters.*

An over-current thermistor of this type remains wired into the power supply for a device on a permanent basis. Its reference resistance will generate some heat, which is why this type of component is usually restricted to applications where the triggering current is below 1A.

The Murata PTGL07BD220N3B51B0 pictured in Figure 24-6 provides over-current protection with a reference resistance of 22 ohms, has a trip current of 200mA, and tolerates a maximum of 1.5A.



Figure 24-6 *An over-current protection PTC thermistor with a trip current of 200mA. The background grid is in millimeters.*

PTC Inrush Current Limiting

This nonlinear thermistor responds to internal heat caused by an inrush of current when power to a device is switched on. The inrush occurs when current flows rapidly into smoothing capacitors, charging them very rapidly. This can overload a power supply and shorten its life expectancy.

NTC thermistors are traditionally used as inrush limiters. The initially high resistance of this type of component blocks the surge in current, but as heating occurs, the resistance of the NTC thermistor drops rapidly. It remains in the circuit, imposing a relatively small load while the device functions normally. For more details of this application, see "Inrush Current Limiter" in the entry discussing NTC thermistors.

However, an NTC thermistor used in this way will waste some power. Suppose a supply of 120VAC is being used. If the power consumption of a device is 1,000W, the current will be approximately 8A. An NTC thermistor that has a resistance of 0.2 ohms while running warm will introduce a voltage drop of approximately 1.6V, consuming about 13W. This power loss will be greater in applications where the current is even higher—for example, in an electric vehicle recharging station.

To eliminate the loss, a timed bypass relay can be added around the thermistor. The relay closes automatically after a short interval, eliminating the power loss. This is known as *active inrush current limiting*.

However, in this arrangement, an ordinary resistor could be used instead. But in that case, why not use a PTC thermistor that has a reference (cold) resistance of 50 ohms or more? This not only limits the inrush current, but provides additional protection. If a smoothing capacitor in the circuit suffers a short circuit, or if the bypass relay fails to close, excess current passing through the PTC thermistor quickly raises its resistance, protecting the rest of the circuit.

The B5910 series of PTC thermistors from TDK is designed for inrush current limiting. They are packaged in a flame-retardant phenolic resin plastic case, as shown in Figure 24-7. The B59105J0130A020 has a reference resistance of 22 ohms that rises quickly beyond 10K when the temperature exceeds 120 degrees Celsius, as shown in Figure 24-8. This type of component is robust enough to withstand a complete short circuit across a 220-volt supply.



Figure 24-7 *This inrush current-limiting PTC thermistor by TDK is packaged in a flame-retardant case. The background grid is in millimeters.*



Figure 24-8 *Relationship of resistance to temperature in a PTC inrush current limiting thermistor. Note that the vertical axis has a logarithmic scale.*

PTC Thermistor for Starting Current

In some applications an initial inrush of current is actually necessary and desirable. An air conditioning compressor, for example, requires a surge of high current for "torque assist" when it is starting from a rest state.

High-current PTC thermistors may be used in this kind of situation. The Vishay PTC305C series is an example. These are heavy-duty components that have a switching time of about half a second, a maximum voltage rating of 410VAC or more, and a current rating from 6 to 36 amps.

The PTC thermistor has a relatively high temperature while the motor is running, and must be allowed time to cool before a restart is possible after shutdown. A waiting time of 3 to 5 minutes is imposed by a thermostat or separate time-delay relay.

PTC Thermistor for Lighting Ballast

The starting sequence for a fluorescent lamp requires that current should flow through the cathode heater initially. The thermistor allows this by bypassing a capacitor. Within less than a second, the resistance of the thermistor rises to block current. By this time, the heater has done its job and the lamp runs from high-frequency AC.

PTC Thermistor as a Heating Element

For small applications, a heating element can be made from a PTC thermistor, using its internal resistance to create heat. It has the advantage of being self-limiting, as its resistance rises with temperature. The TDK 5906 series is an example, shown in Figure 24-9. The component is approximately 12mm in diameter, and is designed to be clamped in place, not soldered. It has automotive applications for diesel fuel preheating and spray nozzle defrosting. Residential applications include vaporizers for air fresheners.

The initial resistance is as low as 3 or 4 ohms, rising very quickly at a transition temperature ranging from 70 to 200 degrees Celsius, depending on the specific component.



Figure 24-9 *This TDK B59060A0060A010 heating element is a PTC thermistor whose resistance rises rapidly around 80 degrees Celsius. Rated for 12VDC, it is intended for automotive applications. The background grid is in millimeters.*

What Can Go Wrong

Self-Heating

Self-heating may affect the accuracy of a temperature sensor. To get accurate readings, keep the current small. When the resistance of a thermistor is at the high end of its range, brief pulses of current can be used.

Heating Other Components

In cases where the self-heating of thermistors serves a useful purpose, as in surge protectors and when used for delays, the heat can damage nearby components or materials.

thermocouple

25

Because a *thermopile* is an assembly of thermocouples, it is included at the end of this entry. Other types of temperature sensors have their own entries.

OTHER RELATED COMPONENTS

- **NTC thermistor** (see Chapter 23)
- **PTC thermistor** (see Chapter 24)
- **semiconductor** temperature sensor (see Chapter 27)
- **RTD** (resistance temperature detector) (see Chapter 26)
- **infrared temperature** sensor (see Chapter 28)

What It Does

A **thermocouple** measures temperature by using a pair of wires made from dissimilar metals. At one end of each wire, they are joined together, often by welding them. The differing thermoelectric characteristics of the wires generates a very small voltage between their free ends, from which the temperature of the joined ends can be derived.

No power supply is needed for a thermocouple, but the voltage that it generates is extremely small (measured not just in millivolts, but microvolts) and very nonlinear, requiring hardware and/or software to convert it to a temperature value. Laboratory equipment or integrated circuit chips are available for this purpose.

Different types of thermocouples are available to measure different temperature ranges, and each type has its own characteristics, requiring appropriate conversion.

A “raw” thermocouple looks very unimpressive, as it merely consists of two wires welded together at one end. This is illustrated in Figure 25-1. The full length of the photocouple is shown in Figure 25-2.



Figure 25-1 *Closeup of the welded wires in a K-type thermocouple. The background grid is in millimeters.*



Figure 25-2 *Overview of the thermocouple in the previous photograph.*

A thermocouple sold as a commercial product is likely to be enclosed in a probe, as shown in Figure 25-3.



Figure 25-3 *A probe that contains a thermocouple.*

Schematic Symbol

A schematic symbol that is often used to represent a thermocouple is shown in Figure 25-4. Because this component does not consume current, the plus and minus signs do not mean that power should be applied to the wires. The positive sign indicates which wire will generate a higher voltage than the wire with the negative sign.



Figure 25-4 *A symbol that is often used for a thermocouple.*

Comparison of Temperature Sensors

In this Encyclopedia, temperature sensors are divided into five main categories, each of which has a separate entry. For convenience, a comparative summary is included in the entry for **NTC thermistors**. See "Addendum: Comparison of Temperature Sensors" for an overview. Also see Figure 23-9.

Thermocouple Applications

Thermocouples have a wider range than any other form of contact temperature sensor, some types being capable of measuring up to 1,800 degrees Celsius. The main limitation is the ability of the joint between the wires to withstand the heat. Appropriate insulation must be used, but segments of ceramic tube are marketed to serve this purpose if necessary.

The very small thermal mass of a thermocouple enables a rapid response to temperature fluctuations. No self-heating occurs, because the thermocouple consumes no power. It is simple and robust. However, its response is very nonlinear, and the tiny voltages involved are vulnerable to corruption by electrical noise. Accuracy is usually not better than plus-or-minus 0.5 degrees Celsius, and may be less at low temperatures.

Thermocouples are commonly found in laboratories and in some industrial applications, such as monitoring the temperature in a blast furnace or inside an internal combustion engine.

They may also measure temperatures as low as -200 degrees, but at temperatures below -100 degrees the temperature coefficient diminishes to the point where voltage increments are less than 30µV per degree Celsius.

How a Thermocouple Works

When one end of a piece of wire is maintained at a temperature that is different from the other end, the temperature gradient along the wire creates a small electromotive force that manifests itself as a difference in electrical potential between one end of the wire and the other. This is known as the *Seebeck effect*, named after the man who discovered it. The magnitude of the potential will depend on two factors: the temperature difference between the ends of the wire, and the type of wire that is used.

Figure 25-5 illustrates the concept. Part 1 of this figure shows two wires, named A and B. The left ends of the wires are heated to the same temperature, T_X, while the right ends remain at a cooler temperature, T_Y. Because the wires are composed of different metals, the voltage drop across each wire will be different.

To make this model useful, some factors must be eliminated. In part 2 of Figure 25-5, the hot ends of the wires have been welded together. This now guarantees that they share the same temperature and the same voltage, V_X. We do not yet know what these X values are.

In part 3 of the figure, the cold ends of the wires are clamped in an isothermal block, which keeps them at an equal temperature, still represented as T_Y. The block is not electrically conductive, so the cold ends of the wires still have different voltages, V_A and V_B. We cannot measure these voltages directly, because they are relative to V_X, which is unknown. However, a volt meter can measure V_A and V_B relative to each other.

The volt meter will have its own voltage gradient on its wires, and possibly a temperature gradient too, but both of these wires are made of the same metal (probably copper) and share the same temperature gradient. Therefore, their effects will be equal.



Figure 25-5 *Basic principles of a thermocouple. See text for details.*

A mathematical relationship exists between the temperature gradient and the voltage difference in each thermocouple wire. Suppose K_A is a constant or function that enables the voltage difference in wire A to be determined from its temperature gradient, and K_B serves the same function for wire B. Suppose T_{DIF} is the difference in temperature between T_X and T_Y. We may state:

$$K_A * (T_{DIF}) = V_X - V_A$$

$$K_B * (T_{DIF}) = V_X - V_B$$

By subtracting the second equation from the first and rearranging the terms, we get:

$$T_{DIF} * (K_A - K_B) = V_X - V_A - V_X + V_B$$

The two V_X terms cancel out, leaving $V_B - V_A$ on the right. We can recognize $V_B - V_A$ as the voltage difference measured by the meter. Call it V_M. So:

$$T_{DIF} = V_M / (K_A - K_B)$$

This enables calculation of the temperature difference between the ends of the wires, based on the meter reading and the conversion factor for each wire, which can be found experimentally. Because T_Y is being held at a known, constant value, we can determine the value of T_X:

$$T_X = T_Y + T_{DIF}$$

Thermocouple Details

When the thermocouple was first invented, the cold ends of the wires were placed in a bath of ice and water, forcing them to acquire and maintain a known temperature of 0 degrees Celsius.

The advent of accurately calibrated thermistors made it possible simply to measure the temperature of the cold ends. In this way, a thermistor enables a thermocouple to work. This prompts the question: why not just use the thermistor to measure T_X, and throw away the thermocouple? The reason is that a thermistor has a more limited range, seldom being used for temperatures above 150 degrees Celsius.

Note that the "hot end" of the thermocouple wires does not actually have to be hotter than the "cold end," even though those terms are commonly used. The equation to find T_X works just as well if T_Y is higher than T_X. The temperature difference will simply have a negative value instead of a positive value.

Because "hot" and "cold" are misleading terms, modern documents generally refer to the "measurement junction" and the "reference junction" of the wires. Note, however, that the wires are not actually joined with each other at the reference junction.

A common misconception is that voltage is generated where the wires are joined at the measurement junction. This is not correct. The voltage is a function of the temperature gradient between the measurement junction and the reference junction in each wire. Therefore, the way in which the wires are joined is irrelevant, provided there is an electrical connection between them. They can be welded, soldered, brazed, or crimped together.

How to Use It

Where a thermocouple is used in a laboratory, typically each wire is insulated, and they terminate in a plug that is inserted in a meter. The reference junction is hidden inside the meter, along with some electronics to decode the temperature data. The meter must have a setting that is appropriate to the specific type of thermocouple being used, so that the conversion factors are correct.

Because the type of metal in each wire must be consistent all the way from the measurement junction to the reference junction, other types of wires cannot be used to extend the reach of a thermocouple. Any extension must use wires made from the same metals. Connectors, also, must have pins and sockets that match the types of metals in the wires.

An extension wire for a thermocouple is shown in Figure 25-6.



Figure 25-6 *Extension wire for a type K thermocouple. Note the polarized plug.*

Types of Thermocouples

Thermocouples are identified by ANSI standard codes consisting of single letters of the alphabet, shown below. Temperature ranges are approximate, in Celsius, with minimums rounded up and maximums rounded down to the nearest 50 degrees. Some data sources recommend narrower temperature ranges for practical use.

K type

-250 to +1,350 degrees. Most popular type of thermocouple. Positive wire is a nickel-chromium alloy, negative wire is a nickel-aluminum alloy. Commonly used in 3D printers.

J type

-200 to +1,200 degrees. Positive wire is iron, negative wire is a copper-nickel alloy. The iron wire is magnetic and vulnerable to corrosion. This thermocouple is not recommended for low temperatures, even though it is theoretically capable of measuring them.

T type

-250 to +400 degrees. Recommended for cryogenic applications. Positive wire is copper, negative wire is a copper-nickel alloy.

E type

-250 to +1,000 degrees. Most sensitive type, with the highest temperature coefficient. Positive wire is a nickel-chromium alloy, negative wire is a copper-nickel alloy.

N type

-250 to +1,300 degrees. An alternative to the K type, more stable at higher temperatures. Positive wire is a nickel-chromium-silicon alloy, negative wire is a nickel-silicon-magnesium alloy.

R type

-50 to +1,750 degrees. For high-temperature applications. Positive wire is a platinum-rhodium alloy, negative wire is platinum. Very low temperature coefficient.

S type

-50 to +1,750 degrees. For high-temperature applications. Positive wire is a platinum-rhodium alloy, negative wire is platinum. Very low temperature coefficient.

Seebeck Coefficients

Datasheets for thermocouples list the Seebeck coefficient, which is the temperature coefficient caused by the Seebeck effect, measured in microvolts per degree. In other words, the value provided by a Seebeck coefficient is the number of additional microvolts that a thermocouple will generate for an increase in 1 degree Celsius.

Each type of thermocouple has a different coefficient, and because thermocouples tend to have a very nonlinear response, the coefficients will vary with temperature. Figure 25-7 shows the variations for six types of thermocouples, over a range from -400 to +1,400 degrees Celsius. It is important to understand that the vertical scale shows the coefficient for each type of thermocouple—that is, the *change* in voltage, not the *actual* voltage, at temperature values along the horizontal axis.



Figure 25-7 *The Seebeck (temperature) coefficient for six types of thermocouples. Partially derived from a datasheet published by Analog Devices.*

R and S type thermocouples have a relatively consistent response, but cannot achieve great accuracy, because the voltage increment is so small for each change in temperature. The K type thermocouple does relatively well between 0 and 1,200 degrees, but the J type only performs adequately between 0 and 800 degrees, while the T and E types are quite inconsistent.

For lower voltage readings, electrical noise becomes an issue. Thermocouple wires are often twisted together, and may also be shielded, to reduce sensitivity to noise. The electronics that decode the thermocouple voltage should include a filter to reject 50Hz or 60Hz interference from wiring in the vicinity.

Chips for Output Conversion

Meters that are designed to interpret the output from a thermocouple and display a temperature tend to be expensive, and may not be convenient for a custom-built application. Fortunately integrated circuit chips are now available to amplify the thermocouple output and apply signal conditioning to create an almost linear response.

The AD8494 and AD8496 from Analog Devices are precalibrated by laser wafer trimming to match the characteristics of J type thermocouples, while the AD8495 and AD8497 match the characteristics of K type. The chips require a power supply of at least 3VDC and have an analog output of 5mV per degree Celsius, enabling measurement over a range of almost 1,000 degrees. They require a very low supply current of 180µA. The manufacturer claims an accuracy of plus-or-minus 2 degrees Celsius.

The chip contains a temperature sensor which should be at the same temperature as the reference junction of the thermocouple. This means that the reference junction (typically, at the socket where a thermocouple plug is inserted) should be as close to the chip as possible, and the chip should be protected from heat created by other components. Any difference in temperature between the reference junction and the chip will create a temperature measurement error.

The MAX31855K chip from Maxim Integrated Products is another thermocouple-to-digital converter. It linearizes the output from the thermocouple and digitizes it as a temperature that is accessible by a microcontroller via a serial SPI bus. Breakout boards with this chip are available. The last letter of the chip number specifies the thermocouple type. Variants for J, K, N, T, S, and R are available.

The AD8495 is mounted on a breakout board from Adafruit, and the MAX31855K is mounted on a breakout board from Sparkfun. These boards are pictured in Figure 25-8.



Figure 25-8 *Thermocouple amplifier/conversion chips from Adafruit (left) and Sparkfun (right).*

Thermopile

A thermopile is an assembly of thermocouples connected in series, as suggested in Figure 25-9, where a hot area is shown on the left and a cooler area is shown on the right. The figure assumes that the orange-colored wires have a voltage difference of 5mV from left to right, as a result of the temperature difference, while the purple-colored wires only have a voltage difference of 1mV from left to right. Therefore, the voltage difference between each reference junction and the next is 4mV, as shown on the right side of the figure. So long as the temperature difference exists, the voltage differences will be cumulative, totaling 16mV between top and bottom in this example.

Note that the multiple thermocouple junctions are not electrically connected with each other in each temperature zone.

In reality, more thermocouples than this will be added, and the voltage differences may be lower.

Generally a thermopile is not sold as a separate component from retail suppliers, but is built into other devices. It may be used to generate small amounts of current from a heat difference, as in an infrared thermometer. It can also be used as a safety device to shut down a gas supply if a burner is not lit. See Chapter 28.



Figure 25-9 *The operating principle of a thermopile. The numbers represent mV, but are chosen arbitrarily as an example.*

What Can Go Wrong

Polarity

The output from a thermocouple has polarity. If this is not observed, an error will result.

Electrical Interference

Thermocouple wires are vulnerable to electrical interference, and should be a twisted pair or, ideally, shielded.

Metal Fatigue and Oxidation

The wire used in some thermocouples tends to be relatively brittle, and cannot withstand much flexing. Also, some metals or alloys are vulnerable to oxidation.

Using the Wrong Type

Different types of thermocouples have totally different characteristics. The electronics to decode the signal from a thermocouple must be matched to the type of thermocouple being used. The plugs on the ends of the thermocouple wires are often retained with screws. A detached plug should be replaced immediately, to avoid the error of attaching it to the wrong type of thermocouple.

Heat Damage from Creating a Thermocouple

If a thermocouple is made from two wires on a DIY basis by welding the tips of the wires together, minimal heat must be used to avoid degrading the alloys in the wires.

RTD (resistance temperature detector)

26

RTD is an acronym, either for *resistance temperature detector* or *resistive temperature device*. No definitive information seems to exist regarding which term is correct, but *resistance temperature detector* is more common.

Occasionally an RTD may be described as a *PTC thermistor*, but its sensing element is different, consisting of pure metal wire or film.

OTHER RELATED COMPONENTS

- **thermocouple** (see Chapter 25)
- **NTC thermistor** (see Chapter 23)
- **PTC thermistor** (see Chapter 24)
- **semiconductor** temperature sensor (see Chapter 27)
- **infrared temperature** sensor (see Chapter 28)

What It Does

A *resistance temperature detector*, also known as a *resistive temperature device*, is usually referred to as an **RTD**. It has a positive temperature coefficient (that is, its resistance increases as its temperature increases) but differs from a **PTC thermistor** in that its sensing element is pure metal instead of a semiconductor.

Comparison of Temperature Sensors

In this Encyclopedia, temperature sensors are divided into five main categories, each of which has a separate entry. For convenience, a comparative summary is included in the entry for **NTC thermistors**. See "Addendum: Comparison of Temperature Sensors" for an overview. Also see Figure 23-9.

RTD Attributes

Positive attributes of RTDs include:

- Accuracy, often plus-or-minus 0.01 degrees Celsius. This very small tolerance allows excellent interchangeability.
- Stability, with a response that drifts by as little as 0.01 degree per year.
- The output is an almost linear function of temperature, making them easily used with a microcontroller.
- Immunity to electrical noise.
- Reasonably rapid response to temperature changes (about 1 to 10 seconds).

Undesirable attributes include:

- Temperature coefficient about one-tenth of that of an NTC thermistor.
- To measure the resistance, some current must pass through the sensor, raising the possibility of self-heating (as in the case of other temperature sensors, with the exception of a thermocouple).
- Relatively high cost, especially of the wire-wound type.

The resistance curves for three generic NTC thermistors are shown in Figure 26-1, plotted against the resistance for a generic platinum RTD that has a reference resistance of 100 ohms at 0 degrees Celsius. Note that this graph is unlike many that illustrate the response of NTC thermistors, in that its vertical scale is not logarithmic.



Figure 26-1 *The brown, green, and blue curves show the resistance of three generic NTC thermistors varying with temperature. The red line shows the resistance of a platinum RTD. Derived from a diagram created by Texas Instruments.*

Schematic Symbol

There is no specific schematic symbol for an RTD. Often the symbol for a thermistor may be used. See Figure 23-1.

Applications

Because of its high accuracy, an RTD may be used where precision is important. It can calibrate other temperature sensors, and may measure the temperature of a reference junction of a thermistor. However, it requires sensitive electronics for signal conditioning, because of its low temperature coefficient.

How It Works

An RTD exploits the fractional increase in electrical resistance of a metal film, metal filament, or (in some cases) a carbon film, when the temperature of the metal rises. In its simplest form, an RTD is a 2-wire device with no polarity.

The sensing element is often made from platinum, as this has a linear response to temperature over a wide range. High-quality RTD sensors with a wide temperature range usually consist of platinum wire that is wound around a glass or ceramic core. Smaller sensors may be fabricated from a thin layer of platinum evaporated onto an insulating substrate. Nickel may be substituted for platinum, and has a more sensitive but less linear response.

The wire-wound type is usable at temperatures as high as 500 Celsius (up to 1,000 degrees for some platinum-element types). Some variants are able to measure temperatures as low as -250 degrees.

DIN 60751 is an international standard defining the performance of platinum RTDs. It specifies a reference resistance of 100.00 degrees at 0 degrees, and a temperature coefficient between 0 degrees and 100 degrees. Outside of this range, a formula defines the response.

The response is almost precisely linear, ranging from 100 ohms at 0 degrees to approximately

138 ohms at 100 degrees. The temperature deviation from a straight line, between 0 and 100 degrees, is no more than plus-or-minus 0.8 degrees.

However, current through the RTD must be restricted to avoid self-heating. A range of 0.5mA to 1mA is recommended.

Variants

Some RTDs are potted in glass or resin, as shown in Figure 26-2. This shows an RTD in the TFPTL range from Vishay, containing a nickel thin-film sensing element with a temperature coefficient of about 0.4% and a tolerance of 0.01%. It is available with a very wide range of reference resistances, from 100 ohms to 5K (measured at 25 degrees Celsius). The temperature range is -55 to +70 or -55 to +150 degrees, and the maximum voltage is 30V to 40V, depending on the specific component.



Figure 26-2 *An RTD in the TFPTL series from Vishay. The background grid is in millimeters.*

The flat package shown in Figure 26-3 may be encased in a protective sheath of plastic or silicone rubber, and can be used for surface temperature sensing where the component is glued to the exterior of a flat-sided container. This figure shows an RTD in the L420 range from Heraeus Sensor Technology, containing a platinum thin-film sensing element with a temperature coefficient of 0.385%. It is available in reference resistances of 100, 500, and 1,000 ohms (measured at 25 degrees Celsius). The temperature range is -50 degrees to +400 degrees.



Figure 26-3 *An RTD in the L420 series from Heraeus. The background grid is in millimeters.*

Wiring

The leads to an RTD can be a source of error. If a simple 2-wire configuration is used, the leads will have an unknown resistance that will be affected by temperature, just as the element inside the RTD will have a temperature-sensitive resistance.

To enable temperature compensation, a three-wire design can be used. Figure 26-4 illustrates the principle. In the first section of this figure, resistances R_A and R_B remain unknown. In the second section, the resistances of R_B and R_C can be found by passing a test current through one wire and back through the other, bypassing the component. Assuming that all of the leads are identical in length and composition, the resistance of $R_A + R_B$ will be equal to that of $R_B + R_C$.



Figure 26-4 *A three-wire configuration enables temperature compensation for the leads to an RTD. See text for details.*

RTD Probe

For practical applications, an RTD sensor is often packaged inside a probe that can be indistinguishable from the type of probe used with a **thermocouple**. However, a thermocouple always uses two wires, as the wires themselves create the voltage. An RTD often uses three wires, as shown in Figure 26-5. This particular sensor is sold for use in a "Brew-Magic" system for brewing craft beer on a commercial basis.



Figure 26-5 *A three-wire RTD is packaged inside this steel probe.*

Signal Conditioning

To process the signal of an RTD, a chip such as the LM75 from National Semiconductor can be used. This is calibrated for connection with a platinum RTD. Internally it converts the resistance of an RTD to a value of 5mV per degree Celsius. This then passes through an analog-to-digital converter on the chip, creating a digital value that can be read via an I2C bus.

What Can Go Wrong

Self-Heating

Self-heating is an issue for RTDs, just as it is for thermistors. Current through an RTD should be limited to 1mA, especially when measuring low temperatures.

Insulation Affected by Heat

The resistance of insulation on the wires leading to a sensor can change with temperature, leading to incorrect resistance readings. This is a more likely source of problems for RTDs than for thermistors, as RTDs are often used at higher temperatures and have a lower temperature coefficient.

Incompatible Sensing Element

If signal conditioning is applied to an RTD that has an incompatible sensing element, temperature readings will be incorrect. For example, an RTD with a nickel element should not be used with signal conditioning designed for a platinum element.

semiconductor temperature sensor

27

This type of sensor may also be referred to as a *bandgap temperature sensor*, a *diode temperature sensor*, a *chip-based temperature sensor*, or an *IC temperature sensor*.

The unfortunate term *integrated silicon-based sensor* is sometimes used, which can be confused with *silicon temperature sensor* (also known as a *silistor*), which is a type of **PTC thermistor**. See Chapter 24.

Some vendors do not divide temperature sensors into clear categories. Semiconductor temperature sensors may be classified as *board-mount* temperature sensors, even though many of them have leads and are not specifically designed to be mounted on circuit boards.

A semiconductor temperature sensor with a digital output is sometimes described as a *digital temperature sensor* or *digital thermometer*. This can be misleading, as the outputs from other types of temperature sensors may be digitized with appropriate components.

OTHER RELATED COMPONENTS

- **thermocouple** (see Chapter 25)
- **NTC thermistor** (see Chapter 23)
- **PTC thermistor** (see Chapter 24)
- **infrared temperature** sensor (see Chapter 28)
- **RTD** (resistance temperature detector) (see Chapter 26)

What It Does

A **semiconductor** temperature sensor is an integrated circuit chip incorporating a sensing element composed of transistor junctions. It has an approximately linear response and is easy to use, in some cases being designed for direct connection with a microcontroller, requiring no additional components.

In analog variants, the output consists either of voltage or current that varies with temperature. These components have a positive temperature coefficient, except for a few CMOS variants where a voltage output diminishes as temperature increases.

Digital variants are becoming more common, creating a numeric output accessible by a microcontroller.

In almost all semiconductor temperature sensors, the characteristics of silicon dioxide limit the temperature range to approximately -50 to +150 degrees Celsius (sometimes less).

This type of component is not (yet) as low in cost as a thermistor, but can include its own amplification, signal processing, and (optionally) analog-to-digital conversion on one chip.

Comparison of Temperature Sensors

In this Encyclopedia, temperature sensors are divided into five main categories, each of which has a separate entry. For convenience, a comparative summary is included in the entry for **NTC thermistors**. See "Addendum: Comparison of Temperature Sensors" for an overview. Also see Figure 23-9.

Semiconductor Temperature Sensor Applications

When a semiconductor temperature sensor is used in surface-mount format, it can measure the temperature of the board on which it is mounted. This enables protection from overheating, often in power supplies.

Because the sensing elements and signal processing circuits are all chip-based, they can be transplanted into other types of sensors. For example, a gas pressure sensor or a proximity sensor can have onboard compensation using a semiconductor temperature sensor. They have also been built into computer CPUs such as the Pentium series from Intel.

Some variants are manufactured in a three-lead TO-92 package, appearing superficially similar to bipolar transistors. They are suitable for remote temperature sensing, and have automotive applications such as measuring the temperature of the transmission, engine oil, or cabin interior. They may also be found in some heating and air-conditioning systems, and some kitchen equipment.

Schematic Symbol

No unique schematic symbol has been developed for a semiconductor temperature sensor. It may be represented by a rectangle containing text abbreviations to represent pin functions, similar to other types of integrated circuit chips.

In the case of a sensor with an output consisting of current that varies with temperature, the sensor may be shown as a *current source*, using the symbol in Figure 27-1. However, this symbol is not specific to temperature sensors; it is used for any component that is a current source.



Figure 27-1 *A temperature sensor whose output consists of current varying with temperature may be shown in a schematic as a current source, using this symbol.*

Attributes

Desirable attributes of a semiconductor temperature sensor include:

- Easy to use. Few or no external components may be required, and little or no signal processing.
- Factory-calibrated, with an almost linear response.
- Versions with a digital output are easy to add to any system that already has an I2C bus. For additional details about protocols such as I2C, see Appendix A.

Undesirable attributes of semiconductor temperature sensors include:

- Limited temperature range, the same as thermistors.
- Self-heating issues, especially in versions where signal-processing functions are built into the same chip.

- Not as rugged as some types of temperature sensors.

For an explanation of terminology used for temperature sensors in datasheets, see "Thermistor Values".

How It Works

When a constant current is flowing through a p-n junction in a diode, the voltage across the diode will change by about 2mV for each change in temperature of 1 degree Celsius. This can be demonstrated by the simple circuit shown in section 1 of Figure 27-2.



Figure 27-2 *Left, a basic circuit for demonstrating the temperature sensitivity of a diode. Right, an NPN transistor can be substituted to emulate the diode.*

Similarly, the voltage across the p-n junction in an NPN transistor varies with temperature, if the current is constant. A transistor can be substituted for a diode as suggested in section 2 of Figure 27-2. Integrated circuit chips that contain transistors can measure temperature by exploiting this phenomenon.

CMOS Sensors

Some semiconductor temperature sensors use CMOS instead of bipolar transistors. The general concept is similar, but they are described separately, below. See "CMOS Semiconductor Temperature Sensors".

Multiple Transistors

The heat sensitivity of a bipolar transistor can be defined with an equation. If the base-emitter voltage is V_{BE}, q is the charge of an electron, k is a constant (known as Boltzmann's constant), T is the temperature in degrees Kelvin (relative to absolute zero), I_C is the collector current, and I_S is the saturation current (which is less than I_C):

$$V_{BE} = ((\ k*T\ )\ /\ q)\ *\ \log_e\ (I_C\ /\ I_S)$$

The term $\log_e$ means, "the logarithm to base e of the expression in parentheses."

Because k and q have known values, the base-emitter voltage turns out to be proportional to the logarithm of the collector current divided by the saturation current. However, the saturation current depends on the geometry of a transistor, and varies with temperature in a nonlinear way.

To eliminate the factor of saturation current, one transistor can be compared with another transistor that has a larger emitter area. This enables the derivation of a new equation that specifies temperature while getting rid of the troublesome saturation currents, with their nonlinear behavior.

However, it may not be easy to fabricate two transistors, in the same silicon chip, that have the same characteristics except that the emitter area of one is bigger than that of the other. It is much easier to add multiple transistors in parallel, each of them identical to the first. The total emitter area will then be equal to the area in one transistor multiplied by the number of transistors.

In Figure 27-3, assuming all the transistors are at the same temperature in addition to being of identical specification, we can now write two equations. The figure allows room to show only three transistors, but suppose there are N of them. If V_{BE0} is the base-emitter voltage of transistor Q0, on the left, and V_{BEN} is the aggregate base-emitter voltage of the N transistors on the right:

$$V_{BE0} = ((\ k*T\ )\ /\ q)\ *\ \log_e\ (I_C\ /\ I_S)$$

$$V_{BEN} = ((\ k*T\ )\ /\ q)\ *\ \log_e\ (I_C\ /\ N*I_S)$$

From these, an equation can be derived that gets rid of I_C and I_S:

$$V_{BE0}\ -\ V_{BEN} = ((\ k*T\ )\ /\ q\ )\ *\ \log_e\ (N)$$



Figure 27-3 *Comparing the base-emitter voltage of one transistor with a set of identical transistors can enable measurement of temperature regardless of the collector current and saturation currents, so long as all the transistors are at the same temperature. See text for details.*

PTAT and the Brokaw Cell

Now if a comparator is added to control the current, a circuit known as the Brokaw Cell is created, shown in Figure 27-4. This is also known generically as a *bandgap temperature sensor*. (A couple of resistors have been omitted for the sake of simplicity.)

Typically, N = 8. That is, there is a set of eight transistors in addition to Q0 (only three being shown here). The voltage difference in the previous equation, V_{BE0} - V_{BEN}, now appears across R2 in the figure, and the voltage across R1 is *proportional to absolute temperature*, often referred to by its acronym, *PTAT*. This voltage can be found from this equation:

$$V_{PTAT} = ((k*T)/q)\ *\ \log_e(N)\ *\ (2*R1/R2)$$

The Brokaw Cell was the basis of the AD580 chip introduced in 1974 by Analog Devices, and the principle is now used very widely in semiconductor temperature sensors.



Figure 27-4 *The Brokaw Cell. See text for details.*

Variants

Three output types are used:

- Analog voltage output (voltage varies with temperature).
- Analog current output (current varies with temperature).
- Digital output.

A fourth type creates an output in the form of a square wave, either with a frequency or wavelength proportional to temperature. The Maxim MAX6576 and MAX6577 are examples. However, this type of output is so rare, it is not described in detail here.

Some semiconductor temperature sensors are CMOS-based, and have a voltage output with a negative temperature coefficient. They are described separately. See "CMOS Semiconductor Temperature Sensors".

Analog Voltage Output

LM35 Series

The LM35 is a typical, widely used semiconductor temperature sensor, available from Analog Devices, Texas Instruments, and other manufacturers. Its output voltage changes by 10mV per degree Celsius over a range of approximately -50 degrees to +150 degrees. Accuracy is stated to be plus-or-minus 0.25 degrees at room temperature and plus-or-minus 0.75 degrees over the whole range.

The sensor can be obtained packaged like a transistor, in a TO-92 plastic capsule or metal can. It is also available as a surface-mount component, or in a TO-220 package, like a 5V voltage regulator, as shown in Figure 27-5.



Figure 27-5 *This version of the LM35 can be used to measure surface temperature when secured with a bolt. The background grid is in millimeters.*

This is a three-wire component, two pins or solder pads being used for the power supply while the third serves as the sensor output. The supply voltage typically ranges from 4V to 30V. Necessary current consumption is only 60μA, which minimizes self-heating.

Because this device is specifically designed for the Celsius temperature range, its output is scaled to 0mV at 0 degrees. A pulldown resistor can be added to measure temperatures below zero.

A bypass resistor of 200 ohms between the output and ground is recommended as a precaution against capacitive effects in the cable run.

The LM34 is almost identical to the LM35, except that its output changes by 10mV per degree Fahrenheit instead of 10mV per degree Celsius.

LM135 Series

Although this sensor contains multiple NPN junctions, the manufacturer describes it as behaving like a zener diode in which the breakdown voltage is directly proportional to absolute temperature. The output increases by 10mV per degree over a range from -55 to +150 degrees Celsius.

For the LM135, the manufacturer claims an error of less than plus-or-minus 1 degree Celsius between 0 and 100 degrees. For the LM235 and LM335, in the same product series, the temperature range is narrower, the accuracy is lower, and the price, also, is lower. An LM335 sensor is shown in Figure 27-6.



Figure 27-6 *A sample of the LM335 temperature sensor in a TO-92 package. The background grid is in millimeters.*

The sensor is available in a TO-92 package (plastic, like a transistor) or a TO-46 (metal can). It is also manufactured in a surface-mount format. The negative terminal is connected directly to ground, while the positive terminal is connected through a series resistor to the positive side of a power supply that can range from 5V to 40V. The third terminal, labeled "ADJ" on datasheets, allows for the output to be adjusted. Figure 27-7 shows the basic circuit. The value of R1 can be chosen to establish an optimal current of 1mA through the sensor, although a range of 400µA to 5mA is tolerable.



Figure 27-7 *Basic schematic for using an LM135, including output adjustment. Because the sensing element behaves like a zener diode, it is represented with the zener symbol.*

Analog Current Output

Fewer components exist using output current to measure temperature. The output is applied to a grounded resistor, and the voltage across the resistor then changes with current from the sensor.

The useful aspect of a current output is that its accuracy is unaffected by a cable run as long as 200 or 300 feet. Therefore, this type of component is appropriate as a remote sensor.

LM234-3 Series

This is a three-wire sensor, two wires being used for bias power supply and ground (labeled V+ and V- on the datasheet) and a third (labeled R) that delivers current proportional to temperature. The current from pin R passes through an external resistor to ground, and the voltage across this resistor varies by 214µV per degree Kelvin. A bias voltage ranging from 1V to 40V is required.

A sample of the LM234 is shown in Figure 27-8.



Figure 27-8 *The LM234Z temperature sensor in a TO-92 package. The background grid is in millimeters.*

If the component is used for remote sensing, the resistor should be 230 ohms and can be connected directly between pin R and pin V- of the sensor at the far end of a wire run. At the "home" end of the wire run, temperature output is taken from above a 10K resistor that is placed between the return wire and ground, as shown in Figure 27-9. With these component values, the output voltage will change by 10mV per degree Kelvin.



Figure 27-9 *Using an LM243-3 sensor with a current output that varies with temperature.*

The LM234-3 can be encapsulated in a plastic TO-92 package or a TO-46 metal can. A surface-mount version is also available.

The claimed accuracy is plus-or-minus 3 degrees. The temperature range is -25 degrees to +100 degrees.

AD590 Series

The Analog Devices AD590 (successor to the original AD580) is a current-output sensor that uses only two wires. Like the LN234-3 it is available in a TO-46 metal can, but with one lead making no internal connection. It also can be bought in a two-wire "flatpack," or as a surface-mount chip (with eight solder pads, only two of which are connected).

Using a supply voltage of 4V to 30V, the sensor's high-impedance output changes by 1μA per degree Kelvin. Voltage supply variations produce very small errors in the output current; substituting 10V for 5V creates a deviation of only 1μA.

Figure 27-10 shows an application for the AD590 using a resistor and a trimmer to adjust the scale factor. When properly set up, this circuit provides an output that changes by 1mV per degree Kelvin.



Figure 27-10 *The simplest circuit allowing fine adjustment for use with an AD590 sensor.*

Digital Output

Some of the most popular examples of semiconductor temperature sensors with digital output include the TMP102 series from Texas Instruments, MCP9808 series from Microchip, LM73 series from Texas Instruments and National Semiconductor, and DS18B20 series from Maxim. All of these components can measure a range typical of semiconductor temperature sensors, from approximately -50 to +150 degrees Celsius. Most of them claim an accuracy in the region of plus-or-minus 1 degree over the full range or 0.5 degree in the 0 to 100 range. With the exception of the Maxim DS18B20, which uses its own unique protocol, the components communicate via either the I2C or SMBus protocol.

TMP102 Series

This is available only in a surface-mount format. It has fewer features than the other sensors listed here, and is less accurate, claiming plus-or-minus 3 degrees Celsius over its maximum range of -40 to +125 degrees Celsius. However, it is less expensive. (For greater accuracy, the TMP112 is available.) This is a low-voltage chip requiring 1.4V to 3.6V as its power supply, drawing a quiescent current of 10μA. Temperatures are stored in a 12-bit or 13-bit format that requires some conversion, as a single bit represents 0.0625 degrees Celsius. An alert pin is activated when the measured temperature deviates above or below limits that are preset by the user. No hysteresis adjustment is available for the alerts. The TMP102 is available on a breakout board from Sparkfun, as shown in Figure 27-11.



Figure 27-11 *The Texas Instruments TMP102 on a breakout board from Sparkfun.*

MCP9808 Series

This multifunction sensor is available either as a regular surface-mount component, or as a surface-mount with an exposed "thermal pad." It conforms with the I2C bus standard at up to 400kHz, allowing up to 16 sensors to share the same bus. The chip has a variety of temperature alert features, including high and low limits that can activate a dedicated "alert" pin, and a hysteresis value that can be set for the limits, to ignore brief temperature excursions. The chip can be put into "comparator mode," where it simply provides logic-high or logic-low output if the temperature is above or below a user-specified value. This feature makes the chip operate as a thermostat. Temperature resolution is user-selectable. The temperature storage format requires some conversion to obtain a Celsius value, to deal with negative values and fractional values. However the chip is available on a breakout board from Adafruit, as shown in Figure 27-12, and an Arduino code library is available.



Figure 27-12 *The Microchip MCP9808 on a breakout board from Adafruit.*

LM73 Series

This sensor is only available in surface-mount format. It conforms with the I2C bus standard at up to 400kHz. Its temperature resolution can be set to 11, 12, 13, or 14 bits. An "alert" pin becomes active if the temperature exceeds a preprogrammed limit. An "address" pin can select one of three device addresses by being held in logic-high, ground, or disconnected status. The chip can be put into shutdown mode when power conservation is necessary.

DS18B20 Series

Unlike most digital sensors, this is a three-wire component, because it uses Maxim's proprietary "1-wire bus" with a unique protocol. The bus allows access to a 2-byte register storing digital output from the temperature sensor, but also allows the user to perform other functions, such as setting the resolution of an onboard analog-to-digital converter (which has a maximum resolution of 12 bits), setting a high-temperature and low-temperature alarm, and allowing the sensor to be identified, as each component has a unique 48-bit serial number in ROM.

The chip can draw sufficient power from the data bus to operate, so long as the bus is held high by a 4.7K pullup resistor. (Maxim describes this as "parasite power.") An internal capacitor sustains the chip briefly while the bus is used for its normal purpose of transferring data, but if the bus has low voltage for more than 480µs the chip will reset itself. The "parasite power" feature also will not work above 100 degrees Celsius. Perhaps recognizing that this system may create more problems than it solves, Maxim has also given the component a normal power input pin.

The DS18B20 is available in the TO-92 package and two sizes of surface-mount chip. Its lack of a standard I2C bus, and its use of complicated proprietary codes, create a steep learning curve. Still, it remains a popular sensor, and an Arduino code library for it is available online.

CMOS Semiconductor Temperature Sensors

CMOS variants of semiconductor temperature sensors have appeared relatively recently compared with the bipolar variants. They draw a very low quiescent current (typically, a few microamps) and can work with a power supply from 5.5VDC down to 2.2VDC, making them suitable for handheld battery-powered devices. An analog output is common. Popular examples are the LM20 and the LMT86 series.

Like bipolar sensors, the LMT86 sensors have a limited temperature range, between approximately -50 and +150 degrees Celsius. Again, like the bipolar sensors, they are available optionally in TO-92 and surface-mount packages. A significant difference is that the output has a negative temperature coefficient, diminishing by 10mV per degree Kelvin, because of the characteristics of CMOS semiconductors. The claimed accuracy is plus-or-minus 0.25 degrees Celsius. The output voltage covers a range of about 2V, diminishing from 0.5V below the supply voltage at -50 degrees Celsius.

A sample of the LMT86 is shown in Figure 27-13.



Figure 27-13 *A sample of the LMT86 CMOS temperature sensor. The background grid is in millimeters.*

What Can Go Wrong

Different Temperature Scales

Some voltage-output sensors create an output convertible to degrees Kelvin, while others use degrees Celsius. While the temperature degrees are the same in each scale, a component with an output in millivolts may assign 0mV either to 0 degrees Celsius or 0 degrees Kelvin (equivalent to -273.15 degrees Celsius). The advantage of using a Kelvin scale is that it avoids the problem of negative temperature values.

Rarely, a sensor may use degrees Fahrenheit.

Interference in Cable Runs

Sensors with a voltage output are susceptible to electrical interference. Twisted-pair or shielded cable runs are recommended when sensors are placed remotely.

For the Maxim DS18B20, which uses a 1-wire bus, multiple sensors should be connected along one run of wire (linear topology) instead of each sensor being connected to a central point (star topology). If the cable lengths are longer than a few meters, the topology starts to matter.

Latency

The packaging of semiconductor temperature sensors can create latency in their response time. While a thermocouple consists only of a pair of wires joined by a small dot of melted metal, a TO-92 semiconductor package adds thermal mass that will slow the response considerably. Moreover, copper leads will conduct heat from a circuit board if the board is warmer than its environment.

Surface-mount chips have a very low mass, but must be soldered to some kind of board, even if it is a very small one. Generally, other types of sensors may be appropriate where rapid response is necessary.

Processing Time

In a sensor with a digital output, the onboard analog-to-digital converter will add a small delay before the data becomes available, and during that delay, the component cannot respond to a new temperature. The output from an analog device may be more suitable for rapid detection of temperature variations.

infrared temperature sensor

28

An **infrared temperature** sensor is sometimes described as a *thermopile*. In reality the sensor module *contains* a thermopile. In this Encyclopedia, a thermopile is considered to be a separate component, described in the entry discussing **thermocouples**. See "Thermopile" in Chapter 25.

Other terms that are sometimes used for an infrared temperature sensor are *contactless thermometer* or *infrared thermometer*. This Encyclopedia classifies a thermometer as a commercially marketed product, not a component.

Devices such as a *radiation pyrometer*, *IR pyrometer*, *optical pyrometer*, or *thermal imager* provide ways of measuring infrared radiation, but are outside the scope of this Encyclopedia.

A **passive infrared** motion sensor (PIR) can detect infrared radiation, but only responds to fluctuations in intensity. An infrared temperature sensor measures the steady-state value of incident radiation.

OTHER RELATED COMPONENTS

- **passive infrared** motion sensor (see Chapter 4)
- **thermocouple** (see Chapter 25)

What It Does

Most temperature sensors discussed in other entries in this Encyclopedia are *contact sensors*, meaning that to measure the temperature of an object, liquid, or gas, they must make contact with it. In situations where contact is not possible or desirable, an **infrared temperature** sensor can be used. It responds to the *black-body radiation* (sometimes known as *characteristic radiation*) that is emitted by all materials above absolute zero (0 degrees Kelvin). This varies with temperature as a result of the movements of molecules.

Situations where noncontact sensors may be preferable to contact sensors include:

- An object is inconveniently located or too far away.
- The temperature of a large area must be measured.
- Contact with a small object would change the temperature of the object. The act of measurement would change the value being measured.
- The object is corrosive, abrasive, or otherwise liable to damage a sensor.
- The object is moving or vibrating.
- The surface of the object must not be contaminated (for example, unprotected foods).

- The temperature of the object is lower than around -50 degrees Celsius or higher than 1,300 degrees Celsius.

However, noncontact sensors have some limitations:

- Normally, only the surface temperature of a target can be measured.
- The optics of the sensor must be protected from dust, dirt, and liquid.
- The target must be clearly visible, in line-of-sight.
- Air pollution will degrade the temperature measurement. Some gases, such as carbon dioxide, will tend to absorb infrared radiation.
- The sensor will be affected by other sources, including reflected, transmitted, and convective heat.
- While an infrared sensor can theoretically respond to a very wide range of temperatures, in practice separate sensors of differing sensitivity are needed to cover a full range.
- Different types of materials emit differing intensities of black-body radiation, even if they are at the same temperature. Some compensation is necessary, or the surface of the object may have to be painted.

Applications

Handheld contactless thermometers were an early application for noncontact sensors.

In astronomy, the thermal radiation from the Sun and other stars is of interest to astronomers.

More recently, the declining cost of an infrared temperature sensor, and the ease of deploying it, have made it appropriate in consumer products. A significant area of adoption is in notebook computers and handheld devices, where processor performance must be balanced against the need to prevent the case from becoming too hot to hold comfortably. In this kind of application, gluing a sensor to the interior of the case would be a manual operation during the production process and would require a wired connection. An infrared temperature sensor mounted on the circuit board, viewing the underside of the case, can achieve the same objective more simply.

A contactless sensor is also very useful for measuring the temperature of rotating objects, such as heating rollers in a laser printer.

Schematic Symbol

No specific schematic symbol exists for an infrared temperature sensor.

How It Works

While nanometers (abbreviated nm) are generally used to measure visible wavelengths, the longer wavelengths of far-infrared are often measured in micrometers (abbreviated μm). The measurable infrared values are defined as ranging from 0.7μm to 14μm, corresponding to peak emissions from a black body ranging in temperature from 200 degrees Kelvin to 6,000 degrees Kelvin (about -70 to +5,700 Celsius).

Unfortunately an object does not emit just one wavelength of black-body radiation for each temperature value. It emits a spread of wavelengths that becomes wider as the temperature increases. However, the peak intensity also increases with temperature, when measured as *spectral radiance*, which is defined as watts per steradian, per micrometer of wavelength. (A steradian is the solid angle at the top of a cone, in this case the cone being of emitted radiation.) Because the intensity increases, it can be used to calculate the temperature.

Figure 28-1 illustrates this concept. Note that both of the axes have logarithmic scales.



Figure 28-1 *The increase in intensity, and the widening spread of wavelengths, of black-body radiation emitted by one object at six different temperatures (in degrees Kelvin).*

All the curves are for one object. Each curve is specific to one temperature in degrees Kelvin, showing how the intensity of emitted radiation varies with wavelength. Note that radiation at wavelengths shorter than 0.7µm is within the visible spectrum; thus, objects at 1,000 degrees Kelvin, or hotter, may be seen to glow visibly.

Because of the wide variety of intensities and temperatures, an infrared sensor that is ideal for measuring a temperature of 1,000 degrees Kelvin will not provide an accurate result at 200 degrees Kelvin. The peak spectral radiance at 1,000 degrees is more than 10,000 times the peak at 200 degrees. Also, the curves in the figure are for an "ideal" object emitting pure black-body radiation. In reality, glass, plastic, and many other materials have a much lower *emissivity*, meaning that they emit less radiation, and are classified as *gray bodies*. A metallic object with a polished surface may emit one-tenth of true black-body radiation.

These issues cannot be ignored, but may be dealt with by relatively simple strategies. Infrared sensors will be rated according to their suitability for different temperature ranges, and the emissivity of the object being measured can be determined by consulting standard tables. Alternatively, the object can be spray-painted with special black paint (such as "Senotherm" or "3-M Black") that has a known emissivity of about 0.95 of pure black-body radiation. Alternatively, a specially formulated black sticker may be applied to the object that is being measured, so long as its temperature is within reasonable limits.

However, a basic infrared temperature sensor will not function reliably if it is pointed randomly at a variety of objects that vary widely in temperature. Specialized, expensive industrial devices incorporate compensation to deal with these issues, but they are outside the scope of this Encyclopedia.

Thermopile

A typical low-cost, chip-based infrared temperature sensor contains a *thermopile* consisting of multiple thermocouples etched into silicon and connected in series. The concept of a thermopile is illustrated in Figure 25-9, where a brief explanation is included.

The configuration of the thermopile is arranged so that the hot junctions of its thermocouples are all clustered in a small central area, where they receive incoming radiation through a window (often made of silicon) that is transparent to infrared wavelengths. The cold junctions are dispersed around the periphery, where they are shielded from incoming radiation. One way to visualize this is shown in Figure 28-2, although this is not a literal depiction of an actual sensor.

Instead of using alternating types of wire, as in a **thermocouple**, a chip-based thermopile often uses alternating segments of n-type and p-type silicon. The hot junctions are mounted on a thin film that has very little heat capacity, while the cold junctions are mounted on a thicker substrate that acts as a heat sink.



Figure 28-2 *Simplified diagram of the thermopile configuration inside an infrared sensor chip. Radiation arriving through a window in the chip affects the thermocouple junctions in the central region, while junctions around the edges remain at a lower temperature.*

Temperature Measurement

The voltage generated by the thermopile is related to the difference in temperature between the hot and cold thermocouple junctions. Thus there are three interrelated variables: hot temperature, cold temperature, and voltage. To calculate one variable, we must know the other two.

The hot temperature is what we wish to know. Therefore we must establish the voltage (which can easily be measured) and the cold temperature. The cold temperature can be determined by adding a thermistor inside the chip.

Typically an infrared temperature sensor with an analog output will have two pins that provide access to the internal thermistor, so that its temperature can be calculated from its resistance. Another two pins provide the voltage between the ends of the thermopile.

Interpreting and reconciling these values is not a trivial matter, especially bearing in mind that the thermistor has a negative temperature coefficient and a nonlinear output, and the thermopile will also have some nonlinearity. To simplify this situation, some infrared temperature sensors incorporate electronics to perform the necessary calculations and provide a digital output. This output can be converted to degrees of temperature by some fairly simple mathematical operations in an external microprocessor.

Variants

Two types of sensors are popular. One is surface-mounted, such as the TMP006, shown in Figure 28-3. This type generally has a digital output. The other type is a discrete component with four leads, such as the Amphenol ZTP135, shown in Figure 28-4. Discrete components may have either an analog or a digital output.



Figure 28-3 *A surface-mount infrared temperature sensor with digital output. Eight tiny solder pads are located on the underside. The background grid is in millimeters.*

Both types of sensors allow infrared light to enter through an area that is opaque to the visible spectrum but transparent to the appropriate range of wavelengths.



Figure 28-4 *A through-hole infrared temperature sensor with analog output. The background grid is in millimeters.*

The ZTP135 has an analog output shown in Figure 28-5.



Figure 28-5 *Analog output from an infrared temperature sensor.*

The TMP006 is only about 1.5mm square, but is available on a breakout board from Sparkfun. Its successor, the TMP007, is available on a breakout board from Adafruit, shown in Figure 28-6.



Figure 28-6 *The TMP007 sensor mounted on a breakout board from Adafruit.*

Surface-Mount Specifications

The TMP006 and TMP007 require a supply voltage that can range from 3.3V to 5V. These chips support the SMBus and I2C bus protocols, using a bus address that can be user-selected. An internal analog-to-digital converter uses 1 least-significant bit to represent 1/32nd of a degree Celsius, and data is saved as a 14-bit signed integer. Up to 16 temperature samples can be averaged internally.

Measurable temperature range is -40 to +125 degrees Celsius. Some hysteresis is built in. The TMP007 supports an alert mode if temperature falls above or below a user-specified threshold.

Sensor Arrays

Using multiple thermopile sensors arrayed in a line or a grid, with an array of lenses, it is possible to capture an image of temperature variations over a surface or a scene. This is known as *thermal imaging*. It can detect heat leakage from buildings, indicating poor insulation, or can locate hot spots in electronic circuits. Heimann Sensor has pioneered the miniaturization of a 31 x 31 grid of thermopile sensors in a single TO-8 or TO-39 package.

Values

Temperature Range

Chip-based infrared temperature sensors are typically designed for a range from about -20 degrees Celsius to about +125 degrees Celsius. Their peak sensitivity is to wavelengths between 4µ and 16µm.

Other types of infrared temperature sensors can have a much wider temperature range, but are more costly.

Field of View

Often referred to by its acronym, *FOV*, the field of view is the angle at the apex of an imaginary cone extending outward from the sensor, defining a boundary where the sensitivity diminishes below 50% of the value directly in front of the sensor. Greek letter ϕ may be used to represent the angle between the surface of the cone and the center line, while θ represents the angle between the opposite surfaces of the cone (i.e., 2 * ϕ). This is shown in Figure 28-7. θ is usually the angle defined as field of view.



Figure 28-7 *Measurement of the field of view from a sensor, defined as the boundary of an imaginary cone where sensitivity drops below 50%.*

Because most infrared temperature sensing components do not have a lens, they are sensitive over a wide angle. The field of view is typically 90 degrees.

What Can Go Wrong

Inappropriate Field of View

The object being evaluated must fill the field of view of the sensor, to avoid measuring other objects around it.

Reflective Objects

A reflective object has lower infrared emissivity, and also may provide misleading output if the sensor is actually measuring thermal radiation reflected in the surface of the object in front of it. In a permanent installation, such as inside a device, the surface to be measured may have to be painted to reduce its reflectivity.

Glass Obstruction

Because glass is opaque to the spectrum of infrared that is of interest, temperature cannot be measured through a glass window. Silicon is opaque to visible wavelengths but is transparent to wavelengths longer than 2µm.

Multiple Heat Sources

Heat is transferred by convection, conduction, and radiation. While an infrared temperature sensor is designed to be sensitive to radiation, it will also respond to other heat sources. Warm or cold air currents will affect its response, and so will heat conducted through the material on which it is mounted. Careful placement of the sensor is important. A shield around the sensor, with a small hole in the center, can prevent convection, while correct location on a circuit board can minimize conduction.

Thermal Gradients

An infrared temperature sensor should be mounted in a stable environment where it will not be exposed to thermal gradients (one side being hotter than another). This asymmetry can cause inaccurate readings.

microphone

29

OTHER RELATED COMPONENTS

- **speaker** (see Volume 2)
- **headphone** (see Volume 2)

What It Does

The sensation of sound is created by rapid waves of air pressure impinging upon the eardrum. A microphone can convert these pressure waves into an alternating electrical signal that can be amplified, recorded, broadcast, transmitted through wires, and reproduced as sound by a headphone or speaker. The principle is illustrated in Figure 29-1. (For more information about sound reproduction, see the entries on **headphone** and **speaker** in Vol. 2.)



Figure 29-1 *The principle of converting pressure waves into an alternating electrical signal (adapted from an illustration in Make: More Electronics).*

Schematic Symbol

Various schematic symbols for a microphone have been used during the decades since its invention. A selection is shown in Figure 29-2. Each symbol assumes that sound is traveling from left to right. This is important when interpreting the symbol at top right, which can represent an earphone when it points in the opposite direction. Unfortunately, some schematics do not conform with this rule.

The two symbols at the bottom, showing a capacitor inside the microphone, should be reserved for condenser or electret microphones.



Figure 29-2 *A selection of schematic symbols that represent a microphone.*

How It Works

Some types of microphones generate a small voltage, while others have a fluctuating resistance that modulates a DC current.

Carbon Microphone

This was a very early attempt to reproduce sound. It contained carbon granules whose packing density increased and decreased in response to air pressure waves. When the density increased, the resistance between the granules diminished, and vice-versa. The principle is illustrated in Figure 29-3, and was patented by Thomas Edison in 1877 for use in telephones. As late as the 1950s (and even later in some countries), wired telephone handsets contained carbon microphones. Their bandwidth was extremely limited.



Figure 29-3 *The principle of a carbon microphone.*

Moving-Coil Microphone

Also known as a *dynamic* microphone, this consists of a very small, light coil of thin wire on a cylindrical tube that can vibrate along the axis of a permanent magnet. This principle is illustrated in Figure 29-4. A diaphragm is attached to the front of the tube, and responds to air pressure waves that penetrate the perforated enclosure of the microphone. Movements of the coil around the magnet create small alternating currents in the wire. The inertia of the coil, tube, and diaphragm, and the force needed to overcome the interaction between the coil and the magnet, impose a limit on the high-frequency response of this design.



Figure 29-4 *The principle of a moving-coil microphone.*

Condenser Microphone

This type of microphone contains two thin discs or plates that form a capacitor. (In the early days of electricity, a capacitor used to be known as a condenser. The terminology has persisted for microphones.) An equal and opposite charge is applied to the plates. One plate is flexible, and as it responds to pressure waves, the capacitance between it and the other, rigid plate fluctuates. If the charge on the plates is kept approximately constant while the capacitance fluctuates, the voltage across the capacitor fluctuates also. These fluctuations can be amplified, as suggested in Figure 29-5.



Figure 29-5 *The principle of a condenser microphone.*

Electret Microphone

This works on the same principle as a condenser microphone, except that its plates are made from a ferroelectric material that retains an electrical charge, just as iron will retain a magnetic polarization. The name of the microphone is derived from “electrostatic” and “magnet.” While early electret microphones were of poor quality, they have evolved to rival condenser microphones, and are extremely affordable. Because the electret creates very small currents, it usually includes a transistor or op-amp in its package to boost the signal, and has an open-collector output. The basic circuit for an electret is shown in Figure 29-6. For more information about using an open-collector output, see Figure A-4.



Figure 29-6 *The basic circuit for using an electret microphone.*

An example of a low-cost electret microphone is shown in Figure 29-7. This type of component is sold either with leads attached, or with solder pads.



Figure 29-7 *A generic electret microphone. The background grid is in millimeters.*

MEMS Microphone

This type, often used in mobile phones, is a capacitive device that works on the same principle as a condenser microphone, although the component is etched in silicon and has a diaphragm that measures only about 1mm square. Many MEMS microphones have an analog output that is amplified in the same chip. Others have a digital output, using *PDM encoding*. This reduces the analog signal to a very fast bit stream, in which the density of the bits represents the amplitude of each fluctuation in a sound wave. PDM is an acronym for *pulse density modulation*. It requires an external clock signal to time the bit stream.

A breakout board from Sparkfun, on which is mounted an Analog Devices ADMP401 MEMS microphone with a preamplifier, is shown in Figure 29-8.



Figure 29-8 *A breakout board for a MEMS microphone (the metal-clad rectangular component at the far end).*

Piezoelectric Microphone

This has also been known as a *crystal* microphone. It contains a diaphragm that functions as a transducer. When it flexes in response to pressure waves, the mechanical energy is transformed into a small amount of electrical energy. Piezoelectric microphones were replaced by the moving-coil type in domestic audio devices when vacuum tubes were replaced with transistors, but may still be used as contact microphones to amplify acoustic musical instruments, or to trigger the playback of digitally sampled musical sounds.

Other variants include *ribbon* microphones (which were common in recording studios in the 1950s and 1960s, but have become rare), *laser* microphones, and *fiber-optic* microphones. They are not sufficiently common to be included in this entry.

Values

Sensitivity

Sound pressure is a complicated topic, explored in detail in the **transducer** entry in Volume 2. It can be measured in pascals, where 1 pascal = 1 newton per square meter.

The *sound pressure level* is a different concept. It measures the *relative* intensity of a sound, in a logarithmic scale calibrated in *decibels* (abbreviated dB). The reference value for this relative scale is 20 micropascals, considered to be the threshold of human hearing, comparable to a mosquito three meters away. This is assigned the value of 0dB.

From this point upward, the actual sound pressure doubles for each additional 6dB. A table of noise sources and their approximate decibel values is shown in Figure 29-9. This is derived from averaging eight similar tables, which are not always consistent in their estimates. It is an approximate guide only.

Decibels	Noise Example
140	Jet engine at 50 meters
130	Threshold of pain
120	Loud rock concert
110	Automobile horn at 1 meter
100	Jackhammer at 1 meter
90	Propeller plane 300 meters above
80	Freight train at 15 meters
70	Vacuum cleaner
60	Business office
50	Conversation
40	Library
30	Quiet bedroom
20	Leaves rustling
10	Calm breathing at 1 meter
0	Auditory threshold

Figure 29-9 *Decibel values for some common sound sources. Reproduced from Volume 2 of this Encyclopedia.*

The decibel unit is important when understanding the specifications of microphones, because it is used to measure their response. Microphone sensitivity is established with a standard input sine wave of 1kHz in frequency and 94dB in intensity (equivalent to 1 pascal in actual sound pressure), measured at the microphone. The sensitivity of an analog microphone is then defined as the number of decibels in an output signal of 1V. Because the output is an AC signal, voltage is measured as a root-mean-square (RMS) value.

For digital microphones, sensitivity is measured as the decibels that can be reproduced by a full-scale digital output. This value is abbreviated as dBFS.

Directionality

A microphone that has a directional response is desirable in many situations. Often, for example, sounds in front of the microphone are more important than sounds from behind the microphone. The directionality of a microphone (sometimes referred to as its *directivity*) is usually represented with a *polar graph* in which the microphone is seen from above, and its sensitivity to sounds from various directions is shown with a curve such as those in Figure 29-10. The circles are drawn at intervals of 5dB, with 0dB at the periphery and -30dB at the center. The precise response for an individual microphone should be shown in its documentation.

Frequency Response

Every microphone tends to be more sensitive to some sound frequencies than others. A manufacturer will provide a graph showing this sensitivity, in decibels, plotted against sound frequency on a logarithmic horizontal axis. Theoretically, human hearing extends from around 20Hz to 20kHz, but few people are actually capable of hearing the high end of that range, and 15kHz may be a more realistic limit for a young person, diminishing to 10kHz with middle age.



Figure 29-10 *Six generic sensitivity patterns. Individual microphones will deviate somewhat from these generic curves.*

An ideal flat response would show that a microphone is equally sensitive to all frequencies. In reality, *rolloff* usually occurs at low frequencies, and will eventually occur at high frequencies, although it may be preceded by a rise in response. If the central section of a curve is flat within plus-or-minus 1dB, this is a level of performance that was attained only by expensive studio microphones in the past. Electrets and MEMS microphones can now provide equivalent frequency response for $1 or $2 apiece, as opposed to the hundreds or even thousands of dollars that used to be necessary for professional equipment.

The response curve shown in Figure 29-11 is for the eMerging i436, an electret microphone sold in a module as an accessory to enable high-quality recordings on handheld devices. The rise around 15kHz may have been introduced deliberately by the manufacturer to compensate for reduced sensitivity of the human ear in that range.



Figure 29-11 *Frequency response for an electret microphone.*

Impedance

The impedance value for a microphone is a function of its resistance, capacitance, and inductance. An amplifier input will also have an impedance rating, and for ideal power transfer between microphone and amplifier, the impedance values should be identical. However, a more important consideration in audio equipment is to avoid voltage loss between the output device (in this case, the microphone) and the input device (the amplifier). To achieve this, the output device should have a low impedance, while the input device should have a high impedance. Most microphones are rated at 150 to 200 ohms, while an amplifier may be rated at 1.5K to 3K.

Total Harmonic Distortion

When an audible sine wave is converted to an electrical output by a microphone (and by its preamplifier, if one is included in the module), the output may become corrupted by some multiples of the basic frequency. These are known as *harmonics*, and they are considered as a distortion of the signal. Total harmonic distortion, measured by a spectrum analyzer over the entire frequency range, should ideally be less than 0.01%.

Signal-to-Noise Ratio

Often abbreviated as S/N or SNR, the signal-to-noise ratio in a microphone is measured in decibels, and should be 60dB or higher.

What Can Go Wrong

Cable Sensitivity

Audio amplification is always vulnerable to electrical noise, which tends to be amplified along with the signal. Small signals from microphones require the use of shielded cables to reduce hum and other types of interference.

Noisy Power Supply

For similar reasons, power supplies must be as free as possible from voltage spikes and other fluctuations.

current sensor

30

The entry describes components that can be installed to monitor current on an indefinite basis. It does not include test equipment, such as test meters or multimeters.

A *current transformer* may be used to measure current, but is not included in this Encyclopedia.

OTHER RELATED COMPONENTS

- **voltage** sensor (see Chapter 31)

What It Does

A current sensor measures the flow of electricity through a wire or a device, and supplies an output that can be interpreted either visually or by a microcontroller to provide a reading in amperes or fractions of an ampere.

Applications

Current sensing is important in industrial applications such as the control of high-powered motors. It can be used to monitor the performance of an inverter, or for everyday purposes such as monitoring the long-term power consumption of an appliance. During product development, a current sensor can indicate the power consumption of a circuit as it changes with modifications.

This entry describes three methods to measure current: an ammeter, series resistor, and Hall sensor. While other methods exist, they are outside the scope of this Encyclopedia.

Ammeter

An ammeter that is sold as a standalone device with leads for circuit testing is often described as a *test meter*. Its functionality is usually built into a *multimeter*. Test meters and multimeters are outside the scope of this Encyclopedia.

An ammeter designed for permanent installation in a device or prototype is a type of *panel meter*, such as the one shown in Figure 30-1. This traditional-style analog meter may be less expensive than the many digital types that are available. It uses a magnetic field created by current flowing through a coil to pull a needle across a scale, against the force of a spring.



Figure 30-1 *A traditional-style analog ammeter.*

A digital ammeter allows a wider range of values to be viewed more easily. The meter from Adafruit in Figure 30-2 has a range of 0A to 9.99A, at voltages from 4.5VDC to 30VDC. The meter can be powered parasitically from the currents that it is measuring, or can use a separate isolated 5VDC supply.



Figure 30-2 *A panel-mount digital ammeter that can measure up to 9.99A.*

Schematic Symbol

An ammeter may be represented in a schematic with the letter A inside a circle, as shown in Figure 30-3.



Figure 30-3 *An ammeter may be represented like this in a schematic.*

Ammeter Wiring

Two ways to use an ammeter in a circuit are illustrated in Figure 30-4, where the load may be any equipment, device, or component that provides some electrical resistance. Because current is the same at all points in a simple circuit, the current that the meter measures flowing through itself will be the same as the current flowing through the load, and the sequence of components is immaterial.



Figure 30-4 *Two options for placement of an ammeter in a circuit.*

However, regardless of the placement of the meter, the process of measuring current will inevitably change the value of the current being measured. This is because the ammeter imposes some internal resistance of its own. The resistance is extremely low, and may be considered negligible for loads of more than a few ohms.

- The low internal resistance of an ammeter means that it must never be connected in parallel with a load, or directly across a power source.

A disadvantage shared by analog and digital meters is that they are not usually interchangeable between AC and DC.

Series Resistor

The current flowing through a load can be calculated by measuring the voltage across a series resistor that is inserted between the load and its ground connection. The concept is illustrated in Figure 30-5.

Using Ohm’s law, if U is the voltage drop, I is the current, and R is the value of the resistor:

```
I = U / R
```

This tells us that for a fixed value of R, current is proportional to voltage. Therefore, measuring the voltage enables calculation of the current, so long as the value of R is known.


Load
Low-value resistor (e.g. 0.01 ohms)
Voltage measurement device

Figure 30-5 *A basic circuit for measuring current as a function of the voltage drop across a small-value resistor. The load in this figure is any circuit or device with a relatively higher resistance. The voltage measurement device could be a microcontroller or analog-to-digital converter.*

Suppose that R has a very small value, which is trivial compared with the resistance of the load. Consequently, the current in Figure 30-5 will be mainly determined by the load, and we may consider the value of the current to be almost the same with or without the addition of R. In that case, the voltage drop across the resistor will be smaller if R is smaller. A smaller voltage drop will not be as easy to measure, but a lower resistance will result in less wastage of power.

If P is the power:

$$P = R * I^2$$

An example may help to make this clear. Suppose the resistor has a value of 0.5 ohms, and the voltage drop across it is measured to be 1V. Ohm's law shows that current flow is 1 / 0.5 = 2A. The power formula shows that P = 0.5 * 4 = 2W.

To waste less power, the value of the resistor should be reduced further. Suppose a resistor of 0.01 ohms is used, and the voltage drop across it is measured as 0.02 volts. The current is 0.02 / 0.01 = 2A, as in the preceding example, but the power dissipation is now only 0.01 * 4 = 0.04W, which is negligible.

But are resistors available that have values measured in fractions of an ohm?

Current-Sense Resistors

In fact, many *current sense* resistors are available, with values of 0.1 ohms, 0.001 ohms, 0.0001 ohms, and many in between. Some resistors have values measured in micro-ohms. Examples are shown in Figures 30-6, 30-7, and 30-8.

Measuring a small voltage drop is easily done by using a microcontroller. However, the connection to the microcontroller must be made as near to the resistor as possible, to eliminate the additional resistance of wires or circuit-board traces. For this reason, precision current-sense resistors may be equipped with four terminals. Two are wider, and are meant for connection to the flow of current. The other two are narrow, for measuring the voltage over the resistor. With this *4-point* configuration, voltage drop over the resistor can be measured as close to it as possible. The 0.001-ohm surface-mount resistor in Figure 30-8 is designed for 4-point measurement.



Figure 30-6 *Two current resistors manufactured by KOA Speer. Left: 0.1 ohms, 5W, 5%. Right: 1 ohm, 5W, 5%. The background grid is in millimeters.*



Figure 30-7 *Two styles of current resistors rated for 0.01 ohms. Bottom left: A plug-in version from TT Electronics, rated 1W and 5%. Top right: Ohmite, 4W, 1%. The background grid is in millimeters.*

Resistors that have the lowest values and are intended to tolerate high current may consist of just a metallic strip welded to solderable pins. This type of component is sometimes called an *open-air resistor*. It is commonly used in multimeters, for measuring currents up to 10A or above.



Figure 30-8 *This Vishay 4-terminal surface-mount current resistor is rated for 0.001 ohms, 3W, 1%. The background grid is in millimeters.*

Voltage Measurement

Some chips are designed for amplifying the voltage drop across a current-sensing resistor. An example is the Texas Instruments INA169.

A few chips contain an analog-to-digital converter in addition to the amplifier. The INA219 by Texas Instruments is designed to measure voltage as well as current, on the "high side" of a circuit—that is, between the positive power supply and the power input of the circuit. It makes its digital data available over an I2C bus.

For additional details about protocols such as I2C, see Appendix A.

Measuring current from the voltage drop across a series resistor offers the advantages of simplicity, ability to work with AC or DC, and low cost (although some resistors of extremely low value can be relatively expensive). A possible disadvantage is that the measurement circuit is not isolated from the circuit whose current is being measured.

Hall-Effect Current Sensing

The principle of a Hall-effect sensor is explained in the entry for **object presence** sensors. See "Hall-Effect Sensor". Normally this type of sensor is activated by an external permanent magnet, but it can also react to the magnetic field generated by current flowing through a wire.

Because the field generated around a wire is proportional with the current, the analog output voltage generated by a linear Hall-effect sensor can also be proportional with the current.

Hall-effect sensors for this specific purpose are available in 8-pad surface-mount packaging. The current to be measured passes through a copper conductor that is embedded in the chip. An example is Allegro's ACS712, for AC or DC currents up to 30A. The internal resistance of the current path through this chip is stated as 1.2 milliohms, and the path is isolated from the sensing circuitry.

Three variants of the chip are available, for currents of plus-or-minus 5A, 20A, and 30A. Depending on which variant is used, the output will range from 66mV to 185mV for each increase of 1A in the current path. Because the current path is isolated, the chip requires a separate power supply of 5VDC.

The 5A version of the AVS712 can be bought on breakout boards from Sparkfun. In Figure 30-9, the board at top-left contains only the ACS712, while the board at lower-right adds an op-amp with sensitivity control, to amplify the voltage output when measuring small currents.



Figure 30-9 *Breakout boards using the AVS712 Hall-effect current sensor. The one at lower-right includes an op-amp to amplify small signals.*

What Can Go Wrong

Confusing AC with DC

A panel meter that is designed only to measure DC should not be used with AC, and vice-versa. Erroneous readings or damage to the meter may result.

Magnetic Interference

A disadvantage of Hall-effect current sensing is that the sensor can be affected by stray magnetic fields. Because a Hall-effect chip is responding to very small magnetic effects, it is vulnerable to interference. Consult the manufacturer's datasheet carefully regarding correct placement of a chip on a circuit board.

Incorrect Meter Wiring

The correct wiring of an ammeter is in series with a load, not in parallel with a load. This may seem an elementary error, but is easy to make if an ammeter and a volt meter are both being used, and they look similar.

Because some panel meters are not fused, applying an ammeter directly across a power supply, without any series resistance, may result in immediate and hazardous destruction of the meter.

Incorrect wiring can also occur when using a digital meter that has four wires emerging from it: two for current testing and two for a separate power supply. This issue is especially important when measuring substantial currents (above 1A).

Current Out of Range

Attempting to measure a current that exceeds the range of an ammeter may damage the meter or blow its internal fuse, if it has one.

voltage sensor

31

The entry describes the type of component that can be installed to monitor voltage on an indefinite basis. It does not include test equipment, such as test meters or multimeters.

OTHER RELATED COMPONENTS

- **current** sensor (see Chapter 30)

What It Does

A voltage sensor measures the electrical potential between any two points in a circuit, or the voltage supplied by a power source, and provides data in volts or fractions of a volt. It should not be confused with an *analog-to-digital converter*, which is not a sensor in itself, but can process the voltage output from a sensor by digitizing it. More information about analog-to-digital conversion is in the Appendix. See Appendix A.

Applications

Voltage measurement is important in conjunction with all types of power supplies, to verify their performance. A volt meter may also be used to show the output from various types of analog sensors that have voltage output.

A graphical display may be used in audio equipment to indicate signal level, which can be proportional with voltage.

Volt Meter

A volt meter that is sold as a standalone device with leads for circuit testing is often described as a *test meter*. Its functionality is usually built into a *multimeter*. Test meters and multimeters are outside the scope of this Encyclopedia.

A volt meter designed for permanent installation in a device or prototype is a type of *panel meter*, which is described here.

An antique analog panel meter is shown in Figure 31-1.



Figure 31-1 *An antique analog volt meter.*

The four scales on the dial correspond with separate input terminals at the rear of the unit. The unequally divided scales are a simple way to compensate for the nonlinear response of the mechanical movement inside the meter.

Modern analog volt meters are still manufactured, and may be cheaper than their digital equivalents. However, a digital volt meter allows a wider range of values to be viewed more easily. The meter in Figure 31-2, sold as a low-cost battery tester, measures voltages from 4VDC to 13VDC to an accuracy of two decimal places. It needs no separate power supply.



Figure 31-2 *A panel-mount digital volt meter.*

Sometimes the number of digits in a volt meter is specified as ending with one-half, as in 3.5 or 3-1/2 digits. This means that the most significant (leftmost) digit can only be a 1 or a blank. The extra "half digit" may seem inconsequential but doubles the range of displayable values. For example, a 2-digit display can only show 100 values, from 0 to 99. A 2-1/2-digit display can show 200 values, from 0 to 199.

Schematic Symbol

A volt meter may be represented in a schematic with the letter V inside a circle, as shown in Figure 31-3.



Figure 31-3 *A volt meter may be represented like this in a schematic.*

Volt Meter Wiring

Two ways to use a volt meter in a circuit are illustrated in Figure 31-4, where the load may be any equipment, device, or component that provides some electrical resistance.



Figure 31-4 *Two options for placement of a volt meter.*

On the left side of the figure, a volt meter may be connected directly across a power source, because the internal resistance of the meter is so high, it will draw very little current. In this configuration, the meter measures the voltage of a source when the source is virtually unloaded.

On the right, the meter can measure the voltage drop across a load, or can measure the voltage across any component, or group of components, that are a subset of the load.

A disadvantage shared by dedicated analog and digital volt meters is that they are not usually interchangeable between AC and DC.

How It Works

An analog volt meter usually contains a built-in, high-value fixed resistance, and an ammeter measuring the current passing through it. The current sensed by the ammeter is then converted to a reading in volts.

Suppose that R represents the fixed resistance, U is the voltage drop across the resistance, and I is the current flowing through it. Ohm's Law tells us:

```
U = I * R
```

The formula shows that if the resistance is fixed, the voltage will vary in proportion with the current, and therefore can be calculated from it.

Load-Related Inaccuracy

When the meter is measuring the voltage drop created by a load that has high resistance comparable to the internal resistance of the meter itself, the meter will not give an accurate reading. Figure 31-5 illustrates this problem.

On the left side of the figure, two resistors 10M each are wired in series between a 9VDC power source and negative ground. Because the resistors are equal, each of them imposes an equal voltage drop of 4.5V.

On the right side of the figure, an additional 10M resistance has been added in parallel with the lower resistor. When two resistors of values R1 and R2 are wired in parallel, their total resistance, R, is given by this formula:

```
1 / R = ( 1 / R1 ) + ( 1 / R2 )
```

Therefore, the total resistance in the bottom half of the circuit is now 5M instead of 10M, and the voltage drop across the upper resistor becomes twice the voltage drop across the two lower resistors.



Figure 31-5 *If a meter measuring the voltage drop across a load has an internal resistance comparable to that of a load, the meter will not give an accurate reading. See text for details.*

Now suppose that the additional 10M resistor is actually the fixed resistance inside a volt meter. In fact, many volt meters do have an internal resistance of around 10M. Because the meter has reduced the resistance in the bottom half of the circuit by a factor of 2, it measures the voltage drop as 3V. If the meter had an ideal, infinite resistance, it would give the correct value of 4.5V. In the real world, that is impossible.

Bar Graph

Sometimes it is useful to represent voltage with a graphical display. A *bar graph* component makes this possible, and is often used in audio equipment.

The bar graph can consist of a row of *LEDs*. In a component designed for this purpose, there are usually 10 or more. To represent 0 volts, all the LEDs remain dark. More LEDs are illuminated as the voltage increases.

Because the bar graph itself only contains LEDs, a driver is necessary to convert voltage into the "rising thermometer" effect. Examples are the LM3914 (linear), the LM3915 (logarithmic, 3 dB per step), and the LM3916 (using VU or Volume Units, for audio). Each of these components has 10 LED outputs, and is fabricated using a chain of resistors as a multitap voltage divider, with 10 comparators.

A driver can be set to show only one LED corresponding with the current voltage level, or (more commonly) a cumulative string of LEDs from zero upward. Some bar graphs also contain different colored LEDs, such as green for the first 7, yellow for the next 2, and red for the final one.

A microcontroller containing an analog-to-digital converter can be used to illuminate a bar graph, instead of a driver chip.

An example of a bar graph is the Avago HDSP-4830, shown in Figure 31-6.



Figure 31-6 *A bar graph LED display, which can be used to represent voltage. The background grid is in millimeters.*

What Can Go Wrong

Confusing AC with DC

A panel meter that is designed only to measure DC should not be used with AC, and vice-versa. Erroneous readings or damage to the meter may result.

High Circuit Impedance

When a meter is measuring the voltage drop across a high-value resistance, it will give an inaccurate reading, as it is diverting a significant proportion of the current.

Voltage Out of Range

Attempting to measure a voltage that exceeds the limited range of a meter can damage the meter or blow its internal fuse, if it has one. Attempting to measure a voltage that is at the very low end of a meter's range will result in an inaccurate value.

Voltage Relative to Ground

If one input to a digital meter is connected with ground, the meter will only be able to measure voltage in a circuit relative to ground.

Sensor Output

This appendix provides some basic information about nine forms of sensor outputs, and the ways in which they can be processed. Other types of encoded output exist, but those examined here are the ones most likely to be found.

Figure A-1 provides an overview. Every sensor initially creates an analog output, which is sometimes connected directly to an output pin. In thermistors and photoresistors, for example, the internal resistance of the component constitutes its output. In many sensors, however, the behavior of the sensing element is processed internally to create voltage, open collector, encoded pulse stream, or current output.

If the sensor is chip-based, it may process the analog sensor response internally to create a binary output or a digital output.

In this Encyclopedia, the term "binary output" means "an output that has two states," usually logic-low or logic-high. The states may be accessible via an output pin, or may be processed internally to create a pulse stream. In that case the stream fluctuates between the two states as a way of encoding an analog value with pulse-width modulation (PWM) or frequency. Other types of encoding are also possible, but are unusual.



Figure A-1 *Nine possible types of output from sensors. The primary categories are highlighted in green.*

The term *digital output* is used here to mean one or two bytes of data that are stored in a register (memory location) in the sensor chip. While other forms of output are "always on" and can be accessed at any time from an output pin, a digital output is usually not available until an external device, such as a microcontroller, sends an instruction to the sensor chip, telling it to return the data. This two-way communication usually is handled by the I2C or SPI protocols (other protocols exist, but are less common).

Analog Outputs

Voltage is by far the most common form of analog output. Other forms of analog output can easily be converted to a voltage value, using the simple techniques described here.

1. Analog: Voltage

Direct Connection: Analog-to-Analog

An analog voltage output can be connected directly to an analog input, so long as the range is compatible and the sensor can provide sufficient current. Examples of external analog devices would be an analog volt meter, a light source or sound source that changes intensity, or a transistor or op-amp that will amplify the output for other audio/visual purposes.

If the voltage output from the sensor rises above a usable range, it can be converted to a lower value by applying it across two resistors connected in series to form a voltage divider. This is shown in Figure A-2.



Figure A-2 *Using a voltage divider to reduce the range from a sensor.*

The values of R1 and R2 can be derived from this basic formula, where V_{SEN} is the voltage from the sensor and V_{OUT} is the output from the voltage divider:

Example A-1

$$V_{OUT} = V_{SEN} * (R2 / (R1 + R2))$$

The impedance of the device used for voltage sensing must be high relative to the values of R1 and R2. Note also that if the analog voltage out from the sensor varies linearly with the phenomenon being sensed, this relationship is likely to be disturbed by the voltage divider.

Analog-to-Binary Conversion

The term "binary" is used here to mean an output that can be in one of two states, such as logic-high and logic-low.

A varying analog voltage output can be simplified by passing it through a component that transforms the signal into binary form. This may be done by using a logic chip with a *Schmitt trigger* input, a *zener diode*, or a **comparator**. (For a description of comparators, see the entry in Volume 2.) A comparator provides desirable features such as adjustable positive feedback to create hysteresis. It may be used, for example, to convert a slowly changing signal from a phototransistor while the sun is setting, to a high/low output that can activate a relay to switch on a light.

Analog-to-Digital Conversion

The analog voltage output from a sensor can be digitized by an external analog-to-digital converter (ADC), either inside a microcontroller or by a separate ADC chip.

If a microcontroller is used, a sensor may often be wired directly to an input pin that connects internally with an ADC. A program in the microcontroller can then assess the integer output from the ADC and either execute a conditional statement or convert the value to a format appropriate for another device, such as a digital display.

If an ADC chip is used, there are thousands to choose from. A few basics:

- A *flash* converter contains a row of comparators with different reference voltages generated with a chain of equal resistors. The comparator outputs are fed into a priority **encoder** that outputs a binary number. This system is very fast but has limited resolution.

- A *successive approximation* converter uses a single comparator, comparing the input voltage with the output from a DAC. The binary number that is supplied to the DAC is determined one bit at a time, from the most significant to the least significant bit, using the comparator's result to determine if the bit should be 0 or 1. These bits are stored in a register, called a successive approximation register (SAR). When the process finishes, the SAR contains a binary representation of the input voltage. This type of ADC can achieve high resolution (many bits) at the cost of lower conversion speed.
- In a *dual slope* converter, a capacitor is charged for a fixed time, with a rate proportional to the input voltage, then discharged at a known rate while measuring time by counting clock pulses. The resulting count is the ADC output.

  The name of the converter is derived from the voltage on the capacitor.
- A *voltage-to-frequency* converter uses a voltage-controlled oscillator to produce pulses with a frequency proportional to the input voltage. If the pulses are counted over a fixed time interval, the count is proportional to the signal level.

The number of the bits in the output from an ADC must be sufficient to digitize the input voltage range with desired accuracy. Because the voltage range may contain unexpected peaks, a cautious strategy is to use many more bits than are necessary. However, this means that for most of the time, only a few bits will be used to represent the low end of the voltage range, and accuracy will suffer.

For example, suppose a voltage input normally ranges from 0V to 2V, with occasional brief excursions to 8V. An 8-bit ADC can provide 256 digital values to represent input voltages. If the values are spread uniformly over the full 8V input range, the least significant bit can measure 1/32nd of a volt, or about 31mV. Smaller voltage fluctuations will be ignored. On the other hand, if the 256 values are used to measure a range of just 2 volts, the least significant bit can measure 1/128th of a volt, or slightly less than 8mV—but voltages higher than 2V will be clipped.

An ADC will typically require a reference voltage, and will digitize the range from 0V to that voltage. The reference voltage must be chosen with the issues of accuracy and range in mind.

A microcontroller may provide a feature in its language to perform automatic scaling of an analog input within limits set by a variable in program code. This is done by comparing the input with a selectable voltage level, such as the voltage of the power supply, an externally supplied voltage, or a fixed built in reference. While the ADC in the microcontroller normally digitizes values from 0V to the supply voltage for the chip, the conversion routine can instruct the microcontroller to use its full number of bits (often, 10) to digitize an input range from 0V to 1V.

For a higher sample rate, an ADC chip may be connected with the microcontroller over an I2C or SPI bus.

2. Analog: Resistance

Resistance-to-Voltage Conversion

A sensor that changes its resistance as it responds to its environment can be placed in a *voltage divider* to provide an analog voltage output. This is illustrated in Figure A-3.


Variable
voltage
output
Variable
resistance
sensor
Sensor

Figure A-3 *The basic principle of putting a variable-resistance sensor in series with a fixed resistance, to create a voltage divider.*

To choose the value for the series resistor, if R_{MIN} and R_{MAX} are the minimum and maximum resistance values for the sensor, the optimum value R_S for the series resistor, to produce the widest variation in voltages, will be found from this formula:

$$R_s = \sqrt{(R_{min} * R_{max})}$$

When the sensor has been set up in this way, the output can now be processed in the same way as any analog voltage output from a sensor.

The datasheet of the sensor should be consulted to make sure that a series resistor value does not allow any chance of the sensor being damaged by excessive current.

3. Analog: Open Collector

Many sensor packages or modules include a bipolar transistor that has an *open-collector* output (or *open drain*, if a CMOS transistor is used). The transistor may or may not be incorporated in an internal **op-amp** (described in Volume 2). Either way, the principle is the same.

Figure A-4 shows a sensor, in darker blue, that has one connection for positive power, another connection for negative ground, and a third connection to the collector of the internal transistor.


Transistor not conductive
Power for
sensor
Pullup
resistor
Sensor
Sensing
element
Output high
Transistor is conductive
Power for
sensor
Pullup
resistor
Sensor
Sensing
element
Output low

Figure A-4 *How to use an open-collector output from an internal transistor.*

In the upper section of the figure, the sensing element is not applying voltage to the base of the internal transistor, and the transistor only conducts a tiny amount of leakage current. Power applied to it through an external *pullup resistor* cannot reach negative ground in any significant quantity, and therefore it can provide a voltage input to a high-impedance device such as a microcontroller, or can power a component such as an LED, which draws relatively little current (20mA or less).

In the lower section of the figure, the sensing element is now applying voltage to the base of the transistor, drastically lowering its effective resistance. The transistor diverts current from the pullup resistor to ground, and the output appears to go low.

The type of sensing element will determine whether the transistor becomes conductive or nonconductive when the element detects a stimulus.

The value that should be chosen for the pullup resistor will depend on the impedance of any device attached to the open-collector output. A 10K resistor may be appropriate for use with a device such as a microcontroller, which has very high impedance. At the other extreme, if the device is an LED, a 330-ohm resistor may be necessary. The value of the pullup resistor must be sufficiently low to enable reliable operation, but sufficiently high to prevent excessive current from passing through the internal transistor when it becomes conductive (20mA is a common maximum value).

The voltage from the open collector can be processed in the same way as any analog voltage output from a sensor.

An open-collector output may be used when the outputs from multiple devices share the same bus. One device can drive the bus without the problem of other devices attempting to hold the bus voltage high.

4. Analog: Current

Relatively few sensors provide an output consisting of variations in current. Some semiconductor temperature sensors function in this way. The output current can be converted to a voltage output simply by placing a fixed series resistor, as shown in Figure A-5.

The voltage at the point shown, relative to negative ground, will vary linearly with the current. The value of the resistor should be defined in a datasheet for the sensor.

The voltage can now be processed in the same way as any analog voltage output from a sensor.



Figure A-5 *How to convert the output from a variable-current sensor.*

5. Binary: High/Low

A sensor that provides a binary output (that is, an output that is either logic-high or logic-low) can be connected directly with a microcontroller, if the voltage range is compatible. Program code in the microcontroller can then test the pin to establish its state. Note that some microcontrollers require a 3.3VDC power supply, while sensor chips may use 5VDC.

A binary output can also be used to control a solid-state relay, or an electromagnetic relay if transistor amplification is used. The output may be sufficient to power an LED indicator.

6. Binary: PWM

PWM is an abbreviation for *pulse-width modulation*. The sensor emits a stream of square-wave pulses with a fixed frequency, but the width of each pulse varies with the stimulus to which the sensor is responding. The width of each high pulse, relative to the wavelength between the start of one pulse and the start of the next, is called the *duty cycle*. A duty cycle of 0% means that there are no pulses at all. With a duty cycle of 100%, there are no gaps between pulses, so the output is high all the time. With a duty cycle of 50%, the duration of each high pulse is the same as the duration of the gap between pulses.

Various microcontrollers offer different ways to decode a PWM pulse stream. The most basic way is for a program to check an input pin repeatedly, as fast as possible, until a high state is detected. The microcontroller copies the value of its internal clock into a variable, then continues to check the input repeatedly until the pulse ends. The pulse duration that has been measured can be converted to a sensor value with a formula or lookup table.

This system is not recommended, as the microcontroller may miss the next pulse while it is converting the value of the previous pulse. To address this problem, a microcontroller language may offer a function that blocks execution of code while waiting for a pulse. The pulseIn() function on the Arduino is an example of this feature. However, the microprocessor must now spend most of its time waiting for a pulse instead of doing useful work.

A better solution is to write a program that is interrupt-driven.

Another option for decoding PWM is to use a low-pass filter that converts the pulse stream into an analog voltage, although some ripples will tend to remain.

Finally PWM can be used directly to power an LED or a DC motor, with transistor amplification as required. The speed of the motor or the brightness of the LED will vary with the duty cycle.

7. Binary: Frequency

Here again, the pulseIn() function on the Arduino may be used, so long as the frequency is a square wave with a known duty cycle.

8. Digital: I2C

In digital electronics, a *bus* is a communal pathway for sharing data among components or devices. The *I2C bus* is an abbreviation for *inter-integrated circuit* bus, developed originally by Philips in 1982. (Philips has since been subsumed into NXP Semiconductors.) The correct notation for I2C is I^2C, and it is spoken as "I-squared-C." However, the term is very commonly written as I2C.

The I2C standard defines a data sharing protocol that is limited to 400kHz (with some exceptions) and designed to work on a small scale, almost always within one device, and usually on one circuit board. It is a low-cost, simple design. Data is transmitted serially over two wires, and the devices sharing the bus are connected in parallel.

Typically there is one *master* device on the bus, and a number of *slave* devices. Masters and slaves can both transmit information, but the master normally initiates communication. It also emits a clock signal for synchronization of data.

A sensor is a slave device that can be interrogated by a microcontroller in its role as the master device. Because multiple slave devices can share a bus, the microcontroller needs a way to identify the slave that it wishes to talk to, and each slave is assigned a unique address for this purpose. Often a slave will allow the user to modify the last two bits of the address, so that up to four identical devices can share a bus.

Code libraries to support the I2C protocol are available for most microcontrollers, and communication with a sensor that uses I2C should simply require knowledge of the sensor's I2C address. However, the data registers in a sensor can be quite elaborate, requiring careful study of the manufacturer's datasheet. Multiple procedures may be required to set functions on a device (such as the sensitivity range of an accelerometer, or the threshold for a temperature alarm). Multiple procedures may also be required to read data out of a sensor (such as two bytes to define a temperature, and several bytes to obtain time as well as location readings from a GPS module).

9. Digital: SPI

SPI is an acronym for serial peripherals interface, a standard introduced by Motorola that serves a similar function to the I2C bus, described immediately above. The SPI standard is slightly more sophisticated, enabling duplex communication and higher data transfer speeds. However, SPI requires a minimum of three wires shared by all devices on the bus, and an additional device-selection line for each slave device. The benefit of the extra device lines is that devices are easier to select and address than on an I2C bus, where more program statements are required. As is the case for I2C, code libraries for microcontrollers are widely available to support SPI. However, the requirement for SPI to use three pins on a microcontroller, plus an additional pin for each slave device, is a disadvantage.

More sensors have I2C capability than SPI capability. The SPI protocol is potentially much faster than I2C.

A sensor that is SPI-enabled will almost certainly be available in a similar version that uses I2C. An increasing number of chip-based sensors support both protocols.

Glossary

This glossary is not comprehensive. It contains only the technical terms that have been used most frequently in this book in conjunction with sensor attributes.

ADC Analog-to-digital converter, which accepts a varying signal (usually, a voltage) as an input, and converts it to a digital value in the form of a binary number. This number is likely to have a high limit ranging from 255 decimal to 65535 decimal. Many microcontrollers contain their own ADC, which is multiplexed to assess the inputs on several pins. On an Arduino Uno, the ADC creates a digital value ranging from 0 through 1,023.

analog output When a sensor creates a voltage or varies its resistance without steps or increments, as a function of the phenomenon that it is measuring, this is an analog output.

binary output In this Encyclopedia, the term "binary output" describes a sensor output that only has two states: logic-high and logic-low, or on and off. The term is used in some datasheets, but more often a binary output is described, misleadingly, as an analog output.

breakout board A small printed-circuit board containing one or more integrated circuit chips, usually surface-mounted. The board makes the features of the chips easier to access, because it has pins or connectors with 2.54mm (0.1") spacing for convenient experimental use with a breadboard. Additional features may be included, such as a voltage regulator.

chip-based sensor This term is used in the Encyclopedia to describe a sensor that is etched into a silicon chip and usually has signal conditioning components and circuitry built in.

contact bounce The tiny and rapid vibrations of mechanical switch contacts, when the switch opens or closes. If the switch is connected with a digital device such as a logic chip, debouncing hardware may be necessary, to allow the contacts time to settle. If the switch is connected with a microcontroller, a delay from 5ms to 50ms may be written into program code. Different switches have widely different settling times.

decibel A unit that expresses relative power or intensity, often (but not exclusively) applied to audible sound. The decibel is one-tenth of a bel, and is abbreviated dB, with the B capitalized because it is derived from the name of Alexander Graham Bell. Because dB is a logarithmic unit, the scale has no zero origin. However, 0dB may be assigned arbitrarily to any intensity, in which case lower intensities will have a negative value. An increase of 3dB corresponds to a doubling of sound intensity (acoustic energy). However, when a sound is sensed by the human ear and evaluated by the brain, its subjective loudness doubles when the intensity increases by 10dB.

dielectric The insulating layer separating two plates in a capacitor.

hysteresis The difference between thresholds for switching an output on and off. When a sensor exhibits hysteresis, it may be unresponsive to a stimulus slightly above or below its equivalent current value. This may be useful to eliminate numerous responses to very small stimuli —for example, in a room thermostat.

I2C Interintegrated circuit bus. Sometimes written as I^{2}C, and often referred to verbally as "I-squared-C." A communications protocol that is often used between a microcontroller and other components on a circuit board. For a description, see "8. Digital: I2C" in the Appendix.

IMU Inertial measurement unit, consisting of three accelerometers and three gyroscopes, sometimes with the addition of three magnetometers. It can be used as a navigational aid. It may also be used in handheld user input devices, such as game controllers.

Kelvin A temperature scale, often abbreviated with the letter K, in which each degree is equivalent to a Celsius degree, but 0 degrees is at absolute zero—the temperature at which materials have no heat energy at all. 273 degrees K is approximately equal to 0 degrees C.

MEMS Microelectromechanical system, i.e., an integrated circuit chip that also contains tiny moving parts. For example, a MEMS accelerometer is built around microscopic springs that respond to accelerative forces.

newton A unit of force named after Isaac Newton, abbreviated with the capital letter N. A force of 1N will accelerate a mass of 1kg at a rate of 1 meter per second each second.

open collector output Many sensors have an open collector output, or contain an op-amp that has an open collector output. The output pin is attached to the collector of an internal transistor, with its emitter connected to negative ground. Positive voltage applied through a pullup resistor to the open collector will be grounded when the internal transistor is conducting current, but will be available for other devices when the transistor is off. See "3. Analog: Open Collector".

orthogonal Angled at 90 degrees. Three orthogonal elements in a sensor will all be angled at 90 degrees to each other.

pascal A unit of pressure equivalent to 1 newton of force per square meter.

PIR Passive infrared sensor. See Chapter 4.

pullup resistor A resistor that pulls up an output or input voltage in the absence of a signal. May be used in conjunction with an **open collector output**.

quadrature An encoding system for output from a pair of sensors. If the sensors are identified as A and B, four output combinations are possible: A high and B low; A high and B high; A low and B high; A low and B low. A common application is to show the direction of movement of a magnetic or optical pattern past the sensor pair.

reference temperature The temperature at which the output signal of a temperature sensor is measured. This is often listed in a datasheet.

register A section of memory that stores a digital value (usually 1 or 2 bytes in a sensor).

target Any object that is being detected by a motion sensor, proximity sensor, or presence sensor.

temperature coefficient The percentage increase or decrease in the value of a sensor as a result of unit change in temperature (usually 1 degree Celsius). Often abbreviated as TC. The value may be resistance, voltage, or current, depending on the sensor. The temperature coefficient should be negative if the value of the sensor diminishes when its temperature increases. If it is expressed in parts per million, abbreviated ppm, it can be converted to a percentage by dividing by 10,000.

Wheatstone bridge A network of four resistors. At least one of the resistors has an unknown value, while the others have precisely known reference values. The network enables calculation of the unknown value. See Figure 12-2.

Index

A

absolute humidity, 119, 120
absolute magnetic encoder, 41
absolute pressure, 113
accelerometer
  and gyroscope, 72
  applications, 70
  free fall, 71
  gravity, 71
  how it works, 70
  IMU, 5, 63, 66, 69
  Newton's Second Law, 72
  rotation, 71
  schematic symbol, 70
  spring, 70
  values, 73
  variants, 72
  what can go wrong, 74
  what it does, 69
ADC, 210, 217
air pressure, 114
alcohol vapor sensor (see gas concentration sensor, alcohol)
altimeter, 114
ammeter (see current sensor)
analog-to-digital conversion, 210, 217
anemometer, 125, 126
angle sensor (see rotary position sensor)
angular motion, 21
angular position sensor (see rotary position sensor)
Arduino-compatible
  gas flow rate sensor, 127
  gyroscope, 67
  IMU, 67
  magnetometer, 9
  pressure sensor, 114
  proximity sensor, 34
  temperature sensor, 184, 185
  touch screen, 97
  touch sensor, 91
avalanche diode, 136
axis of the earth, 7

B

bandgap temperature sensor (see semiconductor temperature sensor)
barometer, 114
barometric pressure, 114
Beidou positioning system, 3
bin switch, 57
black-body radiation, 25
Bourdon tube, 112
breakout board, 217
breakover switch (see tilt sensor)
Brokaw cell, 180

C

capacitive displacement sensor, 36
capacitive proximity sensor (see touch sensor)
capacitive touch screen, 96
capacitive touch sensor, 90
carbon microphone, 194
chip-based temperature sensor (see semiconductor temperature sensor)
clinometer, 55
coil magnetometer, 8
communications satellites, 1
compass, 6, 8
condenser microphone, 194
contact bounce, 18, 23
contents
  volume 1, xxi
  volume 2, xxii
  volume 3, xxii
crystal microphone, 196
current sensor
  ammeter, 199-200
  applications, 199
  Hall effect, 202
  how it works, 199
  microcontroller, 201
  panel meter, 199
  schematic, 200
  schematic symbol, 200

  series resistor, 200
  voltage drop, 200
  what can go wrong, 203
  what it does, 199
current-sense resistor, 201

D

debouncing, 18, 48, 61, 217
decibels, 196, 217
declination, 7
detection sensor (see presence sensor)
dew point, 119
dielectric, 90, 218
differential pressure, 113
diode temperature sensor (see semiconductor temperature sensor)
distance sensor (see proximity sensor)
dual slope converter, 211
dynamic pressure, 111

E

electret microphone, 195
encoder
  linear, 41
  magnetic, 41
  rotary, 48
errata, xxv

F

feedback to and from authors, xxv
flash converter, 211
float sensor, 100
float switch, 57
flux density, 6
flux, magnetic, 6
force sensor
  applications, 81
  deformative, 86
  how it works, 82
  how to use it, 86
  piezoelectric, 82
  plastic film, 82, 85-87
  resistive, 82, 86
  schematic symbol, 82
  strain gauge, 82, 83, 85, 88
  units of measurement, 82
  values, 87
  what can go wrong, 88
  what it does, 81
  wheatstone bridge, 83
four-wire touch screen, 96
frequency response, 197
fresnel lens, 27

G

Galileo positioning system, 3
gas concentration sensor
  alcohol, 118
  breakout board, 119
  cross-sensitivity, 118
  how it works, 117
  humidity, 117, 119
  oxygen, 119
  propane, 118
  schematic symbol, 117
  semiconductor-based, 117
  what can go wrong, 122
  what it does, 117
gas flow rate sensor
  anemometer, 125, 126
  applications, 128
  data output, 128
  schematic symbol, 125
  thermal mass, 127
  thermopile, 127
  units of measurement, 128
  what can go wrong, 129
  what it does, 125
gas pressure sensor (see pressure sensor)
gas sensor (see gas concentration sensor)
gauge pressure, 113
geographical meridians, 7
Global Positioning System (see GPS)
GLONASS positioning system, 3
GPS
  antenna, 2
  definitions, 1
  frequencies, 2
  how to use it, 3
  NMEA protocol, 3
  satellites, 1
  schematic symbol, 1
  time-keeping, 4
  tracker, 2
  values, 3
  what can go wrong, 4
  what it does, 1
gray code, 51
gyroscope
  and accelerometer, 72
  applications, 63
  axes, 64
  how it works, 64
  how to use it, 67
  IMU, 5, 63, 66, 69
  resonator (see gyroscope, vibrating)
  schematic symbol, 63
  values, 67
  variants, 66
  vibrating, 64
  what can go wrong, 67
  what it does, 63

H

Hall effect
  current sensor, 202
Hall effect sensor
  advantages, 22
  applications, xx, 52
  float sensor, 100
  how it works, 18
  how to use, 20
  magnetometer, 8
  rotary position sensor, 48
  variants, 19
hard-iron bias, 9
heading, navigational, 5
humidity sensor (see gas concentration sensor, humidity)
hygrometer, 120
hysteresis

    float sensor, 101, 218
    reed switch, 17, 218

I

I2C, 214, 218
IC temperature sensor (see semiconductor temperature sensor)
IMU, 5, 63, 66, 69, 218
inclination, 7
inclinometer, 55
inertial measurement unit (see IMU)
infrared proximity sensor, 32-34
infrared radiation, 188
infrared temperature sensor
    advantages, 187
    applications, 188
    array, 191
    compared with other temperature sensors, 153
    how it works, 188
    limitations, 188
    schematic symbol, 188
    thermopile, 189
    values, 191
    variants, 190
    what can go wrong, 192
    what it does, 187
inrush current limiter, 150, 161
interintegrated circuit bus (see I2C)

K

Kelvin temperature scale, 218

L

light meter, 137
light-dependent resistor (see photoresistor)
linear displacement sensor (see linear position sensor)
linear feedback shift register, 2
linear position sensor
    absolute, 41
    applications, 39, 42
    how it works, 39
    incremental, 41
    linear potentiometer, 40
    magnetic linear encoder, 41
    optical linear encoder, 41
    quadrature, 41, 218
    schematic symbols, 39
    what can go wrong, 43
    what it does, 39
linear potentiometer, 40
linear variable differential transformer, 42
liquid displacement sensor, 102
liquid flow rate sensor
    differential pressure, 109
    magnetic, 108
    paddlewheel, 105
    reed switch, 105
    rotor, 105
    schematic symbols, 105
    thermal mass, 107
    turbine, 106
    ultrasonic, 108
    what can go wrong, 109
    what it does, 105
liquid flow switch, 108
liquid level sensor
    displacement, 102
    float, 100
    float switch, 57
    how it works, 100
    incremental output, 101
    potentiometer, 101
    pressure of liquid, 103
    schematic symbols, 99
    tilting, 104
    turbulence, 104
    ultrasonic, 102
    weight of reservor, 103
    what can go wrong, 104
    what it does, 99
liquid pressure sensor (see pressure sensor)
load cell (see load sensor)
load sensor, 81
    (see also force sensor)
    applications, 82
    deformative, 86
    liquid level measurement, 103
    schematic symbol, 82
    strain gauge, 83, 85, 88
    values, 87
    what can go wrong, 88
    what it does, 81
LVDT (see linear variable differential transformer)

M

magnetic
    axis, 7
    ball in tilt sensor, 59
    declination, 7
    encoder, 41, 52
    field, 6
    flux, 6
    liquid flow rate sensor, 108
    meridians, 7
    presence sensors, 16
    rotary position sensor, 47
magnetic, linear encoder, 41
magnetometer
    breakout board, 6, 9
    coil, 8
    hard-iron bias, 9
    heading, 5
    how it works, 6
    how to use it, 9
    IMU, 5, 63, 69
    magnetoresistance, 8
    meridians, 7
    placement, 10
    scalar, 5
    schematic symbol, 5
    soft-iron bias, 9
    vector, 5
    what can go wrong, 9
    what it does, 5
magnetoresistance, 8
mass flow rate sensor (see gas flow rate sensor)
mathematical syntax, xxiv
membrane switch, 89
MEMS, xix, 218
MEMS microphone, 195
mercury switch, 58, 61, 78

meridians, 7
metric system, xxiv
microelectromechanical devices (see MEMS)
microphone
  carbon, 194
  condenser, 194
  crystal, 196
  directionality, 197
  dynamic, 194
  electret, 195
  frequency response, 197
  how it works, 194
  impedance, 198
  MEMS, 195
  moving coil, 194
  piezoelectric, 196
  rolloff, 197
  schematic symbols, 193
  sensitivity, 196
  signal-to-noise ratio, 198
  total harmonic distortion, 198
  units of measurement, 196
  what can go wrong, 198
  what it does, 193
motion sensor (see PIR)
mouse, 50
moving coil microphone, 194

N

navigational heading, 5
newton unit of force, 218
Newton's Second Law, 72
NMEA protocol, 3
north pole, 7
NTC thermistor (see thermistor, NTC)

O

object detector (see presence sensor)
object presence sensor (see presence sensor)
open collector output, 218
opt-pass sensor, 15
optical
  linear encoder, 41
optical isolator, 132
optical presence sensor, 12
optical rotary encoder, 48, 53
optical switch, 13, 15, 50
optocoupler, 142
optointerrupter, 21
orthogonal, 218
output
  analog current conversion, 213
  analog voltage conversion, 210, 217
  analog-to-binary conversion, 210
  analog-to-digital conversion, 210
  binary, 209, 210, 213, 217
  digital, 209
  dual slope converter, 211
  flash converter, 211
  frequency conversion, 214
  I2C, 214, 218
  open collector, 212, 218
  options, 209
  pullup resistor, 213, 218
  PWM conversion, 209, 213
  resistance-to-voltage conversion, 211
  scaling, 211
  SPI, 215
  successive approximation converter, 211
  voltage divider, 210
  voltage-to-frequency converter, 211
over-current protection, 160
over-temperature protection, 159
oxygen sensor (see gas concentration sensor, oxygen)

P

paddlewheel flow rate sensor, 105
panel meter, 199, 205
pascal unit of pressure, 218
passive infrared motion sensor (see PIR)
pendulum switch, 58
photocell (see photoresistor)
photoconductive cell (see photoresistor)
photodarlington, 142
photodiode
  applications, 135
  array, 137
  avalanche diode, 136
  band gap, 137
  color sensing, 137
  dark current, 135
  how it works, 135
  how to use it, 139
  light meter, 137
  photoconductive mode, 135
  phototransistor comparison, 143
  photovoltaic mode, 135
  PIN type, 136
  reverse bias, 135
  schematic symbols, 135
  ultraviolet, 137
  values, 138
  variants, 136-137
  wavelength range, 137
  what can go wrong, 140
  what it does, 135
photointerruptor, 13
photomicrosensor, 15
photoresistor
  availability, 131
  how it works, 132
  how to use it, 133
  optical isolator, 132
  phototransistor comparison, 133
  schematic symbols, 131
  sizes, 132
  voltage divider, 134
  wavelengths of sensitivity, 134
  what can go wrong, 134
  what it does, 131
phototransistor
  applications, 142
  base connection, 142
  binning, 144
  FET, 142
  how it works, 142
  how to use it, 144

  optocoupler, 142
  output current calculation, 145
  photodarlington, 142
  photodiode comparison, 143
  photoresistor comparison, 133
  schematic symbols, 141
  values, 143
  what can go wrong, 145
  what it does, 141
photovoltaic effect, 135
piezoelectric
  force sensor, 82
  heat detector, 26
  microphone, 196
  ultrasonic transducer, 32
  vibration sensor, 76
PIN photodiode, 136
pin-and-spring vibration sensor, 76
PIR
  applications, 25
  fresnel lens, 27
  how it works, 26
  schematic symbols, 25
  variants, 29
  what can go wrong, 30
  what it does, 25
potentiometer
  arc segment, 46
  end stops, 46
  float sensor, 101
  logarithmic, 46
  multiturn, 46
  rotary position, 46
presence sensor
  angular motion, 21
  configuration, 21
  linear motion, 21
  magnetic, 16
  optical, 12, 22, 23
  optointerrupter, 21
  reflective, 12
  retroreflective, 12, 15
  schematic symbol, 12
  transmissive, 12-13
  what can go wrong, 23
  what it does, 11
pressure sensor
  absolute pressure, 113
  altitude, 114
  ambient air, 114
  applications, 111
  barometric, 114
  Bourdon tube, 112
  diaphragm, 112
  differential pressure, 113
  dynamic, 111
  gas and liquid behavior, 112
  gases, 115
  gauge pressure, 113
  how it works, 112
  schematic symbols, 111
  sensing elements, 112
  static, 111
  units of measurement, 112
  what can go wrong, 116
  what it does, 111
propane sensor (see gas concentration sensor, propane)
proximity sensor
  applications, 32
  capacitive displacement, 36
  infrared, 32-34
  schematic symbols, 31
  triangulation, 32
  ultrasound, 32-33
  what can go wrong, 38
  what it does, 31
PTC thermistor (see thermistor, PTC)
pullup resistor, 213, 218
pulse-width modulation (see PWM)
PWM, 209, 213
pyroelectric detector, 26

Q

quadrature, 41, 49, 218

R

range finder (see proximity sensor)
reed switch
  advantages, 22
  alarm system, 17
  float sensor, 100
  how it works, 17
  how to use it, 18
  hysteresis, 17
  liquid flow rate sensor, 105
  values, 18
  variants, 17
  what can go wrong, 23
reference sources, xxvii
reference temperature, 218
reflective interrupter, 15
reflective object sensor, 15
reflective optical sensor, 15
reflective photointerrupter, 15
register, 218
relative humidity, 119, 120
resistance temperature detector (see RTD temperature sensor)
resistance-to-voltage conversion, 211
resistive force sensor, 82, 86
resistive temperature device (see RTD temperature sensor)
resistive touch screen, 95
retroreflective presence sensor, 12, 15
rotary encoder, 48, 52-53
rotary position sensor
  absolute, 51
  accelerometer, 71
  applications, 45
  gray code, 51
  Hall Effect sensor, 48
  incremental, 49
  magnetic, 47
  mouse, 50
  optical encoder, 48
  potentiometer, 46
  quadrature, 49, 218
  reflective optical, 48
  rotary encoder, 48
  schematic symbols, 46
  sensing chips, 48
  transmissive optical, 48
  what can go wrong, 53
  what it does, 45
rotary sensor (see rotary position sensor)
rotating coil magnetometer, 8

rotation sensor (see rotary position sensor)
rotational encoder (see rotary encoder)
rotational position sensor (see rotary position sensor)
RTD temperature sensor
  applications, 174
  attributes, 173
  compared with other temperature sensors, 153
  how it works, 174
  output conversion, 176
  probe enclosure, 176
  schematic symbol, 174
  three-wire variant, 175
  variants, 175
  what can go wrong, 176
  what it does, 173

S

Safari Books Online, xxvi
satellites, 1
scalar magnetometer, 5
schematic conventions, xxiv
schematic symbol
  accelerometer, 70
  current sensor, 200
  force sensor, 82
  gas concentration sensor, 117
  gas flow rate sensor, 125
  GPS, 1
  gyroscope, 63
  infrared temperature sensor, 188
  linear position sensor, 39
  liquid flow rate sensor, 105
  liquid level sensor, 99
  load sensor, 82
  magnetometer, 5
  microphone, 193
  photodiode, 135
  photoresistor, 131
  phototransistor, 141
  PIR, 25
  presence sensor, 12
  pressure sensor, 111
  proximity sensor, 31
  rotary position sensor, 46
  RTD temperature sensor, 174
  semiconductor temperature sensor, 178
  thermistor, NTC, 147
  thermistor, PTC, 157
  thermocouple, 166
  tilt sensor, 56
  touch screen, 95
  touch sensor, 90
  vibration sensor, 75
  voltage sensor, 206
Seebeck effect, 167
semiconductor temperature sensor
  analog current output, 182
  analog voltage output, 181
  applications, 178
  attributes, 178
  Brokaw cell, 180
  CMOS type, 185
  compared with other temperature sensors, 153
  digital output, 183
  how it works, 179
  multiple transistors, 179
  schematic symbol, 178
  variants, 180
  what can go wrong, 185
  what it does, 177
sensor
  categories, xx
  chip-based, 217
  multifunction, xx
  output options, 209
  suppliers, xxv
serial peripherals interface (see SPI)
shift register, 2
silistor, 158
slider potentiometer, 40
soft-iron bias, 9
solar panel, 135
sound pressure, 196
sources, xxvii
south pole, 7
speed sensor, 45
SPI, 215
static pressure, 111
stomp box, 133
strain gauge, 82-83, 85, 88
successive approximation converter, 211
suppliers, xxv
surge limiter (see inrush current limiter)

T

tactile switch, 89
target, 218
temperature coefficient, 147, 152, 218
temperature sensor
  comparison of types, 153
  infrared (see infrared temperature sensor)
  noncontact type, 187
  RTD (see RTD temperature sensor)
  semiconductor (see semiconductor temperature sensor)
  thermistor, NTC (see thermistor, NTC)
  thermistor, PTC (see thermistor, PTC)
  thermocouple (see thermocouple)
thermal mass flow rate sensor (see gas flow rate sensor)
thermal mass liquid flow rate sensor, 107
thermistor, NTC
  applications, 148
  compared with other temperature sensors, 153
  datasheet terminology, 152
  how it works, 148
  inrush current limiter, 150
  output conversion, 149
  schematic symbols, 147
  values, 152
  what can go wrong, 153
  what it does, 147
  wheatstone bridge, 150
thermistor, PTC

  - compared with other temperature sensors, 153
  - externally heated, 159
  - heating element, 162
  - inrush current limiter, 161
  - lighting ballast, 162
  - linear, 158
  - nonlinear, 158, 159
  - over-current protection, 160
  - over-temperature protection, 159
  - schematic symbols, 157
  - silistor, 158
  - starting current, 162
  - what can go wrong, 163
  - what it does, 157
- thermocouple
  - applications, 166
  - compared with other temperature sensors, 153
  - how it works, 167
  - how to use it, 168
  - identifiers, 169
  - measurement junction, 168
  - output conversion, 170
  - reference junction, 168
  - schematic symbol, 166
  - Seebeck coefficients, 169
  - Seebeck effect, 167
  - thermopile, 171
  - what can go wrong, 171
  - what it does, 165
- thermopile
  - gas flow rate sensor, 127
  - infrared temperature sensor, 189
  - overview, 171
- tilt sensor
  - applications, 57
  - bin switch, 57
  - breakout board, 59
  - float switch, 57
  - how it works, 56
  - how to use it, 61
  - magnetic ball, 59
  - mercury switch, 58, 61
  - miniaturized, 59
  - pendulum switch, 58
  - schematic symbol, 56
  - two-axis, 59
  - values, 60
  - what can go wrong, 61
  - what it does, 55
- tilt switch (see tilt sensor)
- tip sensor (see tilt sensor)
- tipover switch (see tilt sensor)
- touch pad (see touch sensor)
- touch screen
  - Arduino-compatible, 97
  - capacitive, 96
  - four-wire, 96
  - resistive, 95
  - schematic symbol, 95
  - variants, 95, 97
  - what it does, 95
- touch sensor
  - applications, 90
  - breakout boards, 91
  - capacitive, 90
  - design considerations, 92
  - how it works, 90
  - how to use it, 91
  - schematic symbols, 90
  - tactile feedback, 90
  - touch pad availability, 91
  - what can go wrong, 93
  - what it does, 89
  - wheels and strips, 92
- touch strip, 92
- touch wheel, 92
- triangulation, 32
- turbine flow rate sensor, 106

U

- ultrasonic anemometer, 126
- ultrasonic flow rate sensor, 108
- ultrasonic liquid level sensor, 102
- ultrasonic proximity sensor, 32-33
- units of measurement, xxiv

V

- Vactrol, 132
- vapor sensor (see gas concentration sensor)
- vector magnetometer, 5
- vibrating gyroscope, 64
- vibration sensor
  - how to use it, 79
  - magnetic, 77
  - mercury switch, 78
  - mousetrap type, 77
  - piezoelectric, 76
  - pin-and-spring, 76
  - schematic symbols, 75
  - values, 78
  - variables, 78
  - variants, 75
  - what can go wrong, 79
  - what it does, 75
- vibration switch (see vibration sensor)
- video display, 95
- volt meter (see voltage sensor)
- voltage divider, 210
- voltage sensor
  - accuracy, 207
  - bar graph, 207
  - how it works, 206
  - panel meter, 205
  - schematic, 206
  - schematic symbol, 206
  - volt meter, 205
  - what can go wrong, 208
  - what it does, 205
- voltage-to-frequency converter, 211

W

- wheatstone bridge, 83, 150, 160, 219

About the Authors

Charles Platt is the author of *Make: Electronics* and *Make: More Electronics*. He is a former senior writer for *Wired* magazine, and is a contributing editor to *Make:* magazine, for which he writes a column on electronics.

Fredrik Jansson is a physicist from Finland, with a PhD from Åbo Akademi University. He is currently living in The Netherlands, where he works on swarm robotics and simulates sea animals in the Computational Science group at the University of Amsterdam. Fredrik has always loved scavenging discarded household electronics for parts, and is a somewhat inactive radio amateur with the call sign OH1HSN. He also fact-checked Charles Platt's previous book, *Make: More Electronics*.

Colophon

The cover and body fonts are Myriad Pro, the heading font is Benton Sans, and the code font is Dalton Maag's Ubuntu Mono.

US 20030197093A1

(19) **United States**

(12) **Patent Application Publication**

St.Clair

(10) **Pub. No.: US 2003/0197093 A1**

(43) **Pub. Date: Oct. 23, 2003**

(54) MAGNETIC VORTEX WORMHOLE GENERATOR

(76) Inventor: **John Quincy St.Clair**, San Juan, PR (US)

Correspondence Address:
John St.Clair
Hyperspace Research Institute
52 Kings Court, 4A
San Juan, PR 00911 (US)

(21) Appl. No.: **10/127,098**

(22) Filed: **Apr. 20, 2002**

Publication Classification

(51) **Int. Cl.^{7}** **B64C 27/00**; B64C 39/00

(52) **U.S. Cl.** **244/62**

(57) ABSTRACT

This invention relates to a magnetic vortex generator which has the ability to generate negative mass and a negative spring constant which, according to Einstein's General Theory of Relativity, is required in order to create a stable wormhole between our space and hyperspace. Two separate, but electrically connected, toroidal coils of differing radii, carry magnetic flux in opposite directions about their common centerline. According to Maxwell's equation, this produces bucking electric fields along said centerline. Because the two solenoids have different radii, the parallel spring constant of both coils is negative. The negative mass together with the negative spring constant produce a real resonant frequency which can distort the spacetime curvature due to the creation of powerful spikes of negative mass. This phenomenon, similar to the common electrical thunderstorm, opens up a wormhole into hyperspace through which low-density hyperspace energy can enter into our dimension. This energy finds many application in new types of power supplies, inertia-less and mass-less spacecraft, vehicles that can travel light-years by moving out of dimension through hyperspace, surgery-less medical tables, cranes for lifting heavy objects, cold-welded crystals for crystal rotors, folding space waveguides, and electromagnetic field propulsion vehicles using highly relativistic fields.



Figure 1



Figure 2



Figure 3



Figure 4



Figure 5


I_θ
coil
$B_\theta = F^{rz}$
n_θ Area
laminations

Figure 6

$$F^{\mu\nu} = \begin{array}{c|cccc|} & t & r & \theta & z \\ t & 0 & 0 & 0 & 0 \\ r & 0 & 0 & 0 & B_\theta \\ \theta & 0 & 0 & 0 & 0 \\ z & 0 & -B_\theta & 0 & 0 \end{array}$$

Figure 7

$$k^z = \frac{\text{coul}}{\text{sec}} \cdot m^2 \cdot \frac{1}{m^2} \cdot \frac{\text{kg}}{\text{sec} \cdot \text{coul}} = \frac{\text{newton}}{m} = \frac{\text{force}}{m}$$

Figure 8

$$k^z = \frac{1}{(r+a)^2} - \frac{1}{r^2} = -a \frac{(2 \cdot r + a)}{\left[(r+a)^2 \cdot r^2\right]}$$

Figure 9

$$g_{\alpha\beta} = \begin{array}{c|cccc|} & \mathrm{t} & \mathrm{r} & \theta & \mathrm{z} \\ \hline t & -1 & & B(\cos\theta - \sin\theta) & 0 \\ r & 0 & 1 & 0 & 0 \\ \theta & B(\cos\theta - \sin\theta) & 0 & r^2 & 0 \\ z & 0 & 0 & 0 & 1 \end{array}$$

Figure 10



MVG generates two negative mass spikes along centerline of coils at a radius r = 0.

Figure 11


A
B
C
D
E
F
G
H
I
J
K
L
M

Figure 12



MAGNETIC VORTEX WORMHOLE GENERATOR

BRIEF SUMMARY OF THE INVENTION

[0001] This invention, which is the subject of my present application, is comprised of two solenoids wound with a common wire in opposite directions on two separate toroidal curved-sheet transformer laminates of differing radii. The smaller solenoid is mounted along the centerline of the larger solenoid. This circular magnetic geometry creates linear bucking electric fields along the centerline of the coils. Because the magnetic flux in the laminates travels in opposite directions along arcs of differing radii in the two coils, a negative mass and a negative spring constant are generated by the system. From the theory of gravitational physics, a negative mass is prerequisite to producing a wormhole because it allows the throat of the wormhole to remain open and stable. The creation of the wormhole is facilitated by the appearance of a negative spring constant which allows the spacetime curvature to resonate to such a degree that said wormhole develops between our dimension and another co-dimension of hyperspace. Because the physics constants of hyperspace are different from ours, the wormhole allows hyperspace energy having a low speed of light to enter our dimension. Because electromagnetic fields obey the Lorentz transformation, it is now possible with this lower velocity of light to create huge relativistic fields which can drive the new electromagnetic field propulsion vehicles.

BACKGROUND OF THE INVENTION

[0002] The idea for this coil configuration comes from the observation of powerful thunderstorms, as described by physicist Dr. Richard Feynman in his *Lectures on Physics,* a copy of which is enclosed as a reference. Upon reading his explanation, I realized that the thunderstorm is actually a hyperspace physics phenomenon.

[0003] After the passage of a large lightning storm, people have observed that a car tire rim has merged with the trunk of a tree growing in the ground. Due to the large branches of the tree, there is no possible way that it could slide down the branches and around the trunk. It was observed also that a straw of wheat became embedded in the hard wood of a telephone pole. It turns out that the thunderstorm offers an explanation as to how this can occur.

[0004] After reading Feynman's explanation, it can be seen that the key to this phenomenon is that there is a downward and an upward lightning bolt, sometimes occurring together if the leader branches into two paths. Bolts of lightning also like to strike tall objects such as telephone poles or trees. Now an electrical current moving downward produces a clockwise magnetic B field, as seen from above. On the return stroke, the current is moving upward which produces a counterclockwise magnetic B field. Thus the thunderstorm produces two huge bucking magnetic B fields which is the magnetic geometry of this magnetic vortex generator. Using my tetrahedron diagram, I will then show that the low density hyperspace energy with its low speed of light is able to pull the rim out of dimension so that it can merge with the tree at the moment the lightning strikes.

SUMMARY OF THE INVENTION

[0005] It is the object of this invention to produce two toroidal oppositely-directed magnetic flux fields in two separate yet electrically connected solenoids of differing radii. Because the lines of flux are traveling in toroidal, curved-sheet transformer laminates along arcs of different curvature, the fields produce what is known in gravitational physics as negative mass. Negative mass has the property that if you project it onto a hot surface, the surface will cool rather than heat up. The negative mass, together with the resonance of the spacetime curvature involving a negative spring constant, create a wormhole into hyperspace. This interdimensional connection allows low speed of light hyperspace energy into our dimension which can be used to decrease the weight of an object, or produce huge relativistic electromagnetic fields that can be used to drive the new electromagnetic field propulsion spacecraft.

STATEMENT REGARDING FEDERALLY SPONSORED RESEARCH OR DEVELOPMENT

[0006] Not Applicable.

A BRIEF DESCRIPTION OF THE DRAWINGS

[0007] **FIG. 1**. Front view of magnetic vortex generator.

[0008] **FIG. 2**. Perspective view of the magnetic vortex generator.

[0009] **FIG. 3**. The non-linear coil winding on the interior face of the laminations.

[0010] **FIG. 4**. The non-linear coil winding on the exterior face of the laminations showing that there is an electrical current component in the theta direction.

[0011] **FIG. 5**. The coil variables for the tensor calculation of the negative spring constant.

[0012] **FIG. 6**. The Faraday electromagnetic tensor showing the position of the magnetic field in the $\{r,z\}$ slots.

[0013] **FIG. 7**. The units of the spring constant.

[0014] **FIG. 8**. The parallel spacetime spring constant.

[0015] **FIG. 9**. The cylindrical g metric tensor including the magnetic fields.

[0016] **FIG. 10**. A plot of the mass term G_n for Einstein's G curvature tensor showing that two negative mass spikes are created along the centerline of the generator. Negative mass is required to keep open the throat of the wormhole.

[0017] **FIG. 11**. Circuit diagram for the magnetic vortex generator.

[0018] **FIG. 12**. BH curve for non-linear SuperMalloy toroidal core. From the equation, $B=\mu H$, the slope of the line is equal to the permeability $\partial B/\partial H=\mu$.

DETAILED DESCRIPTION OF THE INVENTION

[0019] 1. The fact that negative mass is required to keep the throat of a wormhole open has been shown to be valid by physicist Dr. Kip Thorne in the enclosed reference physics paper. The key point of this invention is that if you have a negative mass, you also require a negative spring constant in order to get a real frequency and vice versa. The angular frequency of vibration is equal to the square root of the spring constant K divided by the mass M, or $\omega=\sqrt{K/M}$. If the mass is negative, and the spring constant is positive, the frequency is imaginary. Therefore, in order to get a real frequency, the spring constant has to be negative also.

[0020] 2. Referring to **FIG. 1**, the magnetic vortex generator consists of a large toroidal solenoid (A) and its support structure (C), a smaller toroidal coil (B) with its support structure (D) which holds the coil along the centerline of the larger coil. The entire structure sits on a base (E).

[0021] 3. The two solenoids are wound with a common wire in opposite directions on two separate toroidal curved-sheet transformer laminations of differing radii. From the right hand rule, a changing circular magnetic field in the direction of the fingers produces a linear electric field in the direction of the thumb. Because there are two coils producing two magnetic fields in opposite directions, there are two bucking electric fields down the centerline of the coils. This duplicates the thunderstorm conditions. A perspective view of the generator is shown in **FIG. 2**.

[0022] 4. A enlarged view of the non-linear coil winding is shown in **FIG. 3**. The wire (B) is wound around the thin transformer laminations (A) with a non-linear coil spacing as shown by the difference in spacing between length (C) and (C'). On this inner side of the coil, the wire is wound straight across where it can be seen that the wire is normal to the edge of the laminations. Not shown are two strips of Velcro which keep the wire aligned and offset from the tape-covered metal laminations.

[0023] 5. Since the wire is straight across on this side, the opposite side has to have the wire run in a diagonal manner as seen in **FIG. 4A**. In terms of cylindrical coordinates, the components of the electrical current in the coil flow in the z-direction across the breadth of the lamination and in the O-direction around the lamination.

[0024] 6. The reason for the non-linear spacing is to preserve the vector potential of the coil. The vector potential is a more important field than the magnetic field because it can extend out past the windings of a long solenoid. If you look at the units, it is the field momentum per charge or kilogram meter per second coulomb. Notice that the derivative of the vector potential with respect to time is an electric field, while a derivative with respect to length is the magnetic field. The inductance of the coil times the current density is equal to the vector potential. Thus the inductance gradient of the coil times the current per meter is the magnetic field. So the non-linear coil picks up an additional magnetic field around the coil besides the one created in the laminations by the winding itself

[0025] 7. Taking a closer look at the coil in **FIG. 5**, it is constructed of thin laminations taped together to form a cylindrical shape with a wire coil wrapped around it. This creates a magnetic field in the theta θ direction within the laminations. Because the coil is wrapped as a helix, there is a current component I_θ in the theta direction. The cross-sectional area Area through which the magnetic flux flows times a normal vector n in the theta direction is the tensor area n_θ Area. If the radius of the coil is r, then the curvature K is $1/r^2$ pointing in the radial direction. Because there are two coils with differing radii, the generator has two curvatures associated with it.

[0026] 8. In the geometry of electromagnetism, the magnetic field is part of the electromagnetic Faraday tensor $F^{\mu\nu}$ which is a 4 by 4 spacetime matrix having rows and columns of time t, radius r, angle θ and height z in cylindrical coordinates. The first index μ refers to the row, and the second index v refers to the column. The diagonal of the matrix is zero. The first row and column belong to the electric field. All the other slots are filled by the components of the magnetic field. The B_θ component is located in the complementary slots of r and z as shown in **FIG. 6**. Now a tensor product can be written with the available variables I^θ no Area $K_r F^{rz}=k^z$. This says that the current around the loop in the theta direction times the lamination area vector in the theta direction times the curvature K of the coil in the radial direction times the magnetic field in the theta direction is equal to a spring constant in the z-direction, or normal to the plane of the coil. All the tensor components cancel out except for the z-direction. That is, the coil produces a spacetime spring constant through the center of the coil where there are resonant bucking electric fields. So the coil is creating a magnetic spring. The units of the spring constant are shown in **FIG. 7** as force per meter.

[0027] 9. Because there are two coils operating in opposite directions in regions of differing curvature, there are two parallel spring constants generated along the centerline. Two springs in parallel sum, but the inner coil is negative due to the triple product of negative signs of current, field and area. Looking at the front view of the coils, the right hand rule shows the field going counterclockwise with the thumb pointing along the electric field in the positive z-direction. The inner coil with the field going in the clockwise direction has the electric field in the negative z-direction. Therefore the outer coil's positive spring constant sums with the inner coil's negative spring constant to produce an overall negative spring constant as shown in **FIG. 8**. The inner coil has a radius r, and the spacing between the outer and inner coil is a. In this design, the inner radius is 1, and the outer radius is 3 which is the magic ratio in physics of 1/3. That makes length a equal to 2. Substituting r=1 and a=2 into the spring constant equation shows that the ratio is negative 8/9. That is, the spring constant is negative as previously asserted. If the spring constant is negative, it must produce negative mass in order to have a real frequency of resonance. Since it produces negative mass, then it can produce a wormhole as shown by Dr. Kip Thorne.

[0028] 10. The geometry of hyperspace physics is based on the geometry of the tetrahedron which is circumscribed by the sphere. The corners of the tetrahedron touch the sphere at a latitude of 19.47122063° which turns out to be, in terms of planet cosmology, the location where all the large volcanoes and vortices occur on Earth, Mars, Jupiter, Uranus and Neptune. Furthermore, the cosine squared of this angle is 8/9, which is the spring constant ratio for the magnetic vortex generator. That is, the coil is interacting with the geometry of spacetime which is why it is such an effective wormhole generator. As will be demonstrated later, the tetrahedral geometry of hyperspace shows that the electron and proton are one and the same particle. This is a new discovery in science coming out of this research. The diagram also shows that when the speed of light is reduced, due to the low density of energy coming into our dimension through the wormhole, Planck's constant divided by the speed of light puts the electron at the boundary between space and hyperspace. That is, the electron and the proton go out of dimension which is the reason that the car tire rim can become merged with the tree. The ramifications of this magnetic vortex generator are enormous. It means developing new types of crystals through interdimensional merging which will be needed in the development of these spacecraft and their crystal rotors. It means the possibility of teleporting spacecraft through hyperspace over distances of light years using the new folding space waveguides. It means light-weight or inertia-less spacecraft which can be accelerated at hundreds of thousands of g's. It means the ability to lift extraordinary loads in construction work. It means surgery-less medical tables where tumors can be pulled directly out of the patient's body.

[**0029**] 11. Because we have a magnetic spring, then there is some resonant frequency at which the coil can be operated in order to create a large spacetime distortion. It is this distortion that creates the wormhole into hyperspace. From this it follows that the wormhole attaches to a low pressure region with a magnetic monopole. Because pressure is linear mass times the speed of light squared divided by area, a low pressure signifies a low speed of light and less dense matter. What this means is that opposite polarity spacetime curvature at two ends of an electrode will produce a voltage along the electrode, effectively creating a power supply. The reason for this is that spacetime curvature, as shown by Einstein's General Theory of Relativity equation $G_{\alpha\beta}=8\pi T_{\alpha\beta}$, is equal to the square of the electromagnetic fields in the stress-energy tensor T. So the curvature on the ends of the electrode appear as voltages and the system acts as a battery supply to power the spacecraft.

[**0030**] 12. The other characteristic of the magnetic vortex generator is that it can pull objects out of dimension allowing the object to apparently move through solid walls. The object doesn't actually move through the wall because the object is not in the same dimension as the wall; it just appears that way. Moving out of dimension and then back again on the other side of the wall would effectively move the object through the wall for all intents and purposes.

[**0031**] 13. The tetrahedron diagram is a physics diagram which plots the natural logarithm of mass to the natural logarithm of wavelength. The product of mass times wavelength is equal to Planck's constant divided by the speed of light. So the product of the electron mass times its wavelength is equal to the proton mass times its wavelength is equal to the Planck mass times the Planck wavelength. The Planck wavelength is the bottom dimensional limit of the universe. We live in the Planck box which is bounded by the Planck wavelength and Planck mass. Outside this box is hyperspace.

[**0032**] 14. Because logarithms sum, the sum of the log of the mass plus the log of the wavelength is a constant sum. Thus the electron and proton and Planck mass slide on a 45° line known as the base constant which is equal at the axes to the log of Planck's constant divided by the speed of light. Planck's constant is measured in joule-sec so that multiplying it by the frequency 1/second of light gives the energy of the photon particle.

[**0033**] 15. Planck's constant is equal to the Planck wavelength times the Planck mass times the speed of light. The 45° base constant is Planck's constant divided by the speed of light, which means that the speed of light cancels out top and bottom, leaving the area of the Planck box as the value of the base constant. Hyperspace has a low linear mass compared to our dimension. Therefore, Planck's constant is reduced when this energy enters our dimension through the wormhole created by the generator. And the base constant is also so reduced. In terms of logs, this means that the 45° base line becomes more negative and moves to the right on the diagram. As it does so, the base line intersects the electron at the Planck wavelength which is the separation point between space and hyperspace. That is, the electron moves out of dimension. Because the electron and proton are one and the same particle, as shown in reference tetrahedron diagram tet0565, the proton and hence the entire atom is taken out of dimension as well.

[**0034**] 16. All of this can be seen more easily graphically on the tetrahedron diagram itself, referring to reference tetrahedron diagram tet3025. The 45° line which intersects the electron at point (b) is the base constant for our dimension. As you can see, this base line intersects the horizontal axis at a value of −95.91546344 which is the log of Planck's constant h divided by the speed of light. Because Planck's constant is proportional to the linear mass, it is reduced in value by the low density hyperspace energy and, in terms of logs, becomes more negative. This moves the base line to the right at a value of around minus **105**. The new base line intersects the electron at point (a) which is located on the Planck wavelength that is the boundary between space and hyperspace. Thus the electron at point (a) goes out of dimension.

[**0035**] 17. It was inferred previously that a negative spring constant meant a negative mass was produced by the wormhole generator. This can actually be calculated using Einstein's General Theory of Relativity. The calculation starts with the g metric tensor which is a spacetime measurement of distance in terms of time t, radius r, horizontal angle θ and length z. This 4 by 4 matrix is shown in **FIG. 9** where the diagonal line has a signature in cylindrical coordinates of values equal to $\{-1, 1, r^2, 1\}$. All the other terms of the matrix are zero except for the magnetic fields in the two coils. Because the field is changing sinusoidally with time in the theta direction, the field has to go into the {t, θ} and {θ, t} slots of the matrix. Because the field in the inner coil is in the negative direction compared to the outer coil, and including a 90° phase shift between the two fields, a suitable magnetic field function would be B (cos(θ)-sin(θ)).

[**0036**] 18. Using a general relativity software package, Einstein's G curvature tensor can be calculated for this particular metric. The first term G t in the upper left hand slot in the corner is the mass term for the tensor. All the other terms are either electromagnetic fluxes or pressure terms involving the squares of the fields.

[**0037**] 19. Referring to **FIG. 10, a** plot of the mass as a function around a small circle shows that two negative mass spikes occur around the circumference of the circle. Because the radius is almost zero, the two spikes are actually coincident.

[**0038**] 20. This next section shows the electrical system used to drive the magnetic vortex generator. Referring to **FIG. 11**, the system is driven by a sinusoidal voltage source (A) into a 1:1 turns isolation transformer (B). The voltage is stepped up into the range of thousands of volts using a step-up hi-pot transformer (C). The first loop consists of a direct current blocking capacitor (D), a transformer choke (E), a variable inductance (G) and the current in the loop (F). The variable inductance is a coil winding on a toroidal core wound with thousandth-inch thick SuperMalloy tape. This coil acts as a magnetic switch due to its variable permeability.

[0039] 21. Referring to the accompanying drawing in **FIG. 12**, the slope of the BH curve is actually the permeability of the core. At point (a) on the curve, the slope is very low and therefore the permeability is very small. The resistance of the coil is the frequency of the current times the inductance of the coil. If the permeability is small, then the inductance is low, which means that the coil resistance is low initially. With a low resistance in the coil, current (F) flows through the winding rather easily. Then the coil goes from point (a) to point (b) where the permeability and resistance increase. This change in resistance from a low to a high value dumps the magnetic energy into capacitor (H). Then the non-linear coil saturates between points (b) and (c) where again the coil has a small slope and the coil resistance switches to a low value. Capacitor (D) then dumps its charge (I) through coil (G) producing a large voltage spike in the input and output winding of transformer toroidal coil (J). The magnetic flux in coil (J) then produces a voltage spike in coils (L) and (M) of the magnetic vortex generator. The frequency of oscillation of the generator is determined by capacitor (K) and the overall inductance of the two coils. The diagram shows that the winding is non-linear and in opposite directions going from outer coil to the inner coil.

[0040] 22. Frequency of oscillation has to be kept under 20 MHz in order to create a soft wormhole that connects to low pressure regions of hyperspace. The pressure regions of hyperspace are similar to the pressure produced by a dam holding water. The upper surface of the water, where there is no water pressure, is analogous to the black void into which our universe is expanding. In the middle of the dam, there is a region just above us having a lower water pressure which corresponds to the low density hyperspace energy. This analogy is not perfect because the many frequencies of hyperspace are quantized, as we know from quantum physics, rather than being a continuous spectrum of lower and lower frequencies down to the zero frequency of the black void.

What I claim as my invention is

1. A magnetic vortex generator which can generate negative mass according to Einstein's General Theory of Relativity, which is a tested and proven theory. As a result of this theory, it can be shown that negative mass is required to create a stable wormhole between space and hyperspace. Without the negative mass, the throat would close.

2. The generator consists of two solenoids wound with a common wire in opposite directions on two separate toroidal curved-sheet transformer laminates of differing radii. The smaller solenoid is mounted along the centerline of the larger solenoid.

3. According to Maxwell's equations, said geometrical and magnetic arrangement produces linear bucking electric fields along the centerline of said coils. Since curvature and the square of the electromagnetic fields are one and the same phenomenon according to Einstein's spacetime curvature tensor $G=8\pi T$, this resonance of the electric fields causes a resonance of the spacetime curvature and the opening of the wormhole.

4. Due to the fact that the magnetic flux travels within the laminations at a curvature equal to the inverse of the radius squared, each coil produces a spring constant which depends on the current, lamination area, magnetic field strength and the individual curvature of each coil.

5. Due to the fact that the flux travels in opposite directions in each solenoid, the spring constant of the outer coil is positive, and the spring constant of the inner coil is negative. These two spring constants, one positive and one negative, add in parallel to create a negative spring constant for the generator. Because the frequency of resonance is equal to the square root of the negative spring constant divided by the negative mass, the resonant frequency is positive real.

6. This process of creating and keeping open the wormhole allows low density hyperspace energy to enter our dimension. Because the linear mass is lower, Planck's constant, equal to the Planck mass times the Planck wavelength times the speed of light, is reduced to such an extent that the electron is moved out of dimension. Because the electron and proton are one and the same particle, when considering a path through space and hyperspace, the proton is also moved out of dimension. Thus this process of moving the atom in and out of dimension using the magnetic vortex generator has the ability to create cold-welded crystals, new types of materials and new ways to cold solder one disparate material to another.

7. As a consequence of said process, highly relativistic electromagnetic fields can be created because the velocity of light has been reduced considerably. These fields than can be used to produce life in the new class of electromagnetic propulsion vehicles.

8. As a consequence of said process, refrigeration systems can be created because negative energy cools rather than heats.

9. As a consequence of said process, power supplies can be made such that a differential spacetime curvature on the ends of a carbon electrode can create a differential voltage similar to a regular chemical battery.

10. As a consequence of this process, surgery-less medical tables can be fabricated whereby tumors can be pulled directly from the patient's body.

11. As a consequence of this process, the negative mass produced by the generator can offset the mass of a spacecraft to create a mass-less, inertia-less vehicle which can accelerate at hundreds of thousands of g's.

12. As a consequence of this process, the folding space waveguide becomes a reality whereby hyperspace energy, which has a low spring constant, can be easily folded and curved using powerful, relativistic electromagnetic fields. Spacecraft will be able to teleport themselves out-of-dimension over huge distances measured in terms of light-years.

13. Because the wormhole opens up an interdimensional connection to hyperspace having a magnetic monopole, a radial magnetic field is created. As a consequence of this process, a changing magnetic monopole field crossed with a changing electric field can produce a toroidal electromagnetic flux around the circular hull of the spacecraft. As a consequence of the merger of these two fields, a spacetime curvature G_{zz} is produced over the hull of the spacecraft which creates a tension or lift force which enables the spacecraft to ascend, hover or descend.

14. An electrical system, comprised of a variable frequency generator and amplifier, an isolation transformer and voltage step-up transformer, drives a non-linear inductance which switches on and off the current in the output circuit in such a manner as to produce large voltage spikes through magnetic vortex generator. The generator responds by producing two large negative mass spikes close to the centerline of the two coils.

15. The winding on each coil of the generator has a non-linear spacing to enhance the magnetic field and to reduce the interwinding coil capacitance.

16. The ratio of the radius of the small coil to that of the larger coil is 1/3, which is the magic ratio in physics. This creates a spring constant that is proportional to 8/9. The square of the cosine of the tetrahedral angle of 19.47° is equal to this ratio. Also the ratio of the area-to-volume ratio of the circumscribing sphere of a tetrahedron to the area-to-volume ratio of the tetrahedron is also 1/3. And the corners of the tetrahedron touch the circumscribing sphere at 19.47°. All the large volcanoes and vortices on Earth, Mars, Jupiter, Uranus and Neptune are located at this latitude. Thus this invention is more effective in developing a wormhole because it is tuned geometrically to the tetrahedral geometry of space.

* * * * *

US 20060071122A1

(19) **United States**
(12) **Patent Application Publication**
St. Clair
(10) **Pub. No.: US 2006/0071122 A1**
(43) **Pub. Date: Apr. 6, 2006**

(54) **FULL BODY TELEPORTATION SYSTEM**

(76) Inventor: **John Quincy St. Clair**, San Juan, PR (US)

Correspondence Address:
JOHN ST. CLAIR
4A
52 KINGS COURT
SAN JUAN, PR 00911 (US)

(21) Appl. No.: **10/953,212**

(22) Filed: **Sep. 29, 2004**

Publication Classification

(51) **Int. Cl.**
B64C 39/00 (2006.01)
(52) **U.S. Cl.** **244/62**

(57) **ABSTRACT**

A pulsed gravitational wave wormhole generator system that teleports a human being through hyperspace from one location to another.



Figure 1



Figure 2



Figure 3


L
m_1
$\delta\theta$
m_2
L cos(θ)

Figure 4



Figure 5



Figure 6


-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
-10 -20 -30 -40 -50 -60 -70 -80 -90 -100 -110 -120 -130 -140 -150 -160 -170 -180 -190
ln(wavelength)
a
b
c
d
e
A
B
C
D
E

Figure 7


-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
-110
-120
-130
-140
-150
-160
-170
-180
-190
ln(wavelength)
a
b
c
d
e
f
A
B
C
D
E
F

Figure 8



Figure 9



Figure 10



Figure 11



Figure 12



Figure 13



Figure 14



Figure 15



Figure 16



FULL BODY TELEPORTATION SYSTEM

BRIEF SUMMARY OF THE INVENTION

[0001] This invention is a system that teleports a human being through hyperspace from one location to another using a pulsed gravitational wave traveling through hyperspace.

BACKGROUND OF THE INVENTION

[0002] The basis for this invention is an event, referring to **FIG. 1**, occurring on May 2, 2004, in which the inventor ("he") personally experienced a full-body teleportation while walking to the bus stop (A) along a road (B) that runs perpendicular to the nearby commercial airport runways where planes are landing. There is a wide iron grating (D) for water drainage that crosses the road at the center of the bus stop. The grating width is such that one has to make a concerted effort to jump across it in order to get from one side to the other. Approximately 50 meters from the iron grating, he (E) felt a vertical wave (F), similar to a flag waving in the breeze, traveling down the street toward the bus stop. The wave velocity was about 1 meter per second, which was slightly faster than his walking speed. In the next instance, he (G) found himself down the street near the corner of the next block. Realizing that he had passed the bus stop, he turned around to see the iron grating approximately 50 meters up the street in back of him. Because there was no recollection of having jumped across the iron grating nor of having passed the bus stop's yellow marker line, he realized that he had been teleported a distance of 100 meters while moving along with the traveling wave. It was obvious that the wave was pulsed because the front edge overtook the inventor, moved with him momentarily, and then the back edge of wave left him as it moved on down the street. While contemplating this sequence of events, he then looked up and saw in a span of a few seconds a twin-turboprop airplane (C) in the distance crossing above the road while making a shallow descent in order to land at the airport.

[0003] It took a number of days in order to understand this sequence of events. The explanation involves knowledge of a wide range of subjects such as gravitation physics, hyperspace physics, wormhole electromagnetic theory and experimentation, quantum physics, and the nature of the human energy field.

[0004] It is obvious from the above scenario that the airplane momentarily crossing perpendicular to the road generates the aforementioned pulse. Because the airplane has an engine on each wing, there are two propellers which conceivably are rotating out-of-phase with each other. That is, the blade of one propeller could be pointing up and the equivalent blade on the other engine could be pointing in a slightly different direction. Notice that the tip of the blade traces out a helix as the plane is landing.

[0005] In gravitation physics, referring to **FIG. 2**, it is known that two masses of mass m**1** and m**2** (A,B) attached by lever arms slightly offset by an angle δθ along the radial direction to the rotating shaft (C), will produce a gravitational wave (D) traveling perpendicular to the shaft. The mass and wave are referred to as the source and receptor respectively. Referring to a side view looking along the shaft **FIG. 3**, the product of the mass m times the angular acceleration a is a constant such that m**1***a***1** is equal to m**2***a***2**. The distance between the masses is length L, which makes an angle θ with the horizontal axis. The difference in time of travel to the receptor gives rise to a difference in phase δθ equal to the angular velocity ω of the rotating shaft times the length L times the cosine of the angle θ

$$\delta\theta=\omega L\cos(\theta)$$

[0006] At the receptor, the amplitude of the wave is equal to the mass times the acceleration times the phase difference divided by the radius r to the receptor

$$A=\frac{m_1a_1}{r}\delta\theta\approx\left(\frac{m\omega L\sin(\theta)}{r}\right)(\omega L\cos(\theta))=\frac{m\omega^2L^2\sin(2\theta)}{r}$$

Even though the turboprop airplane engines have a high rotational speed and a large separation distance between masses, the gravitational wave which is produced is small and not noticed. The problem is that the gravitational constant G in this dimension has such a small value equal to the speed of light c squared divided by the linear mass Ω of the universe

$$G=\frac{c^2}{\Omega}=\frac{(299792458\ \mathrm{m/s})^2}{1.346812891\cdot10^{27}\ \mathrm{kg/m}}=6.673200002\cdot10^{-11}\ \frac{\mathrm{m}^3}{\mathrm{kgs}^2}$$

[0007] On the other hand, a gravitational wave traveling in hyperspace would be magnified enormously due to the face that the linear mass is so small. The magnitude of the gravitational constant in hyperspace can be estimated in the following manner. At the beginning of the 20th century, a man's parents were dying of tuberculosis. With their permission, he placed them and their beds on weighing scales. When each one passed away, each scale registered a drop in mass equal to 0.071 kilograms. This is the mass of the hyperspace energy being which resides in the physical body. Because hyperspace is co-dimensional with our dimension, the energy being interpenetrates the body and controls its movement.

[0008] Referring to **FIG. 4**, a human being has seven vortices (A through G) which are aligned along the centerline of the body. Each vortex is actually a co-gravitational field K which causes a pendulum placed in the field to spin in circles. For this reason, the K field has units of inverse seconds similar to an angular velocity. The vortex transports energy from our dimension to the energy being located in hyperspace. The gravitational field g and the co-gravitational field K are equivalent gravitationally to the electric E field and the magnetic B field found in electromagnetism. The equivalent gravitational solution to an electromagnetic problem can be obtained by substituting the following gravitational constants for the electromagnetic constants

Electromagnetic	Gravitational
q (charge)	m (mass)
ρ (volume charge density)	ρ (volume mass density)
σ (surface charge density)	σ (surface mass density)
λ (line charge density)	λ (line mass density)
J (convection current density)	J (mass current density)

-continued

Electromagnetic	Gravitational
E (electric field)	g (gravitational field)
B (magnetic field)	K (co-gravitational field)
ϵ_0 (permittivity of space)	$-1/4\pi G$
μ_0 (permeability of space)	$-4\pi G/c^2$
$-1/4\pi\epsilon_0$ or $-\mu_0\, c^2/4\pi$	G (gravitational constant)

[0009] Referring to **FIG. 5**, each vortex is connected through the pineal gland by light cords to a separate hyperspace quantum well having its own frequency and dimension. The reason for this separation is that the conical spiritual eye, attached to vortex B, has to have its own energy structure which is different from vortex (A) which is connected to the quantum energy field in which the mental processes are developed. Due to the high speed of light in our dimension, the quantum wells are the size appropriate to molecules and atoms. In hyperspace, where the speed of light is one meter per second, the quantum wells are huge and can be manipulated. This manipulation has shown that the quantum wells are in the shape of a cube about a meter on a side. This makes the whole structure about seven meters tall for a volume of seven cubic meters. Thus the mass density ρ of hyperspace is about

$$\rho_h = \frac{.071\ \mathrm{kg}}{7\ \mathrm{m}^3} = .01\ \frac{\mathrm{kg}}{\mathrm{m}^3}$$

which per unit area is the same value. Therefore the hyperspace gravitational constant is equal to

$$G_h = \frac{c^2}{\Omega_h} = \frac{\left(1\ \frac{\mathrm{m}}{\mathrm{s}}\right)^2}{.01\ \mathrm{kg/m}} = 100\ \frac{\mathrm{m}^3}{\mathrm{kgs}^2}$$

The enormous magnification of the gravitational constant is therefore of the order of

$$\frac{G_h}{G} = \frac{100}{6.6732 \cdot 10^{-11}} \approx 1.5 \cdot 10^{12}$$

The question is how does this amplified gravitational wave created by the rotating propellers and turbines get into hyperspace from our dimension?

[0010] The answer comes from experiments done using the ancient Chinese form of breathing known as Chi Kung. Using this breathing technique, we have been able to levitate the human body over six feet in the air. The internal temperature of the stomach is around 200 degrees Fahrenheit. By simultaneously squeezing the diaphragm to bring hot air up through the lungs, and breathing through the nose to bring cold air down, rotating vortices are generated in the lung passages when these two air masses meet and twist around each other as depicted in the famous Yin-Yang diagram. Because the lung has variable diameter passages from the large diameter at the throat to the final small air sacs, there is a spectrum of rotating frequencies.

[0011] From quantum physics it is known that if there is a temperature fluctuation occurring among a group of harmonic oscillators in the environment, then Planck's reduced constant $\hbar$ is increased by the cotangent of the constant times the frequency ω of the oscillator divided by twice Boltzmann's constant k times the temperature T

$$\hbar = \hbar \coth\left(\frac{\hbar\omega_n}{2kT}\right)$$

[0012] The effect of increasing Planck's constant, referring to **FIG. 6**, can be seen in the tetrahedron diagram. This diagram, of which there are now over 4000, plots the natural logarithm of mass on the vertical axis versus the natural logarithm of wavelength on the horizontal axis. In terms of mathematics, it is a subspace logarithmic manifold which projects geometrically the physics constants into our **4**D spacetime dimension. That is, it is the geometry of the tetrahedron circumscribed by the sphere that determines the mass of the proton and electron. The mass of the electron times its wavelength is equal to the mass of the proton times its wavelength which in turn is equal to Planck's constant h divided by the speed of light c

$$m_e\lambda_e = m_p\lambda_p = \frac{h}{c}$$

Taking the natural logarithm of the above equation shows that the mass plus the wavelength is equal to what is termed the base constant

$$\ln(m_e) + \ln(\lambda_e) = \ln\left(\frac{h}{c}\right) = -95.91546344$$

which is represented in **FIG. 6** by the 45 degree line (A) from point (a) on the horizontal axis to the vertical axis at point (b). The electron is located at point (c) which is the intersection of the electron wavelength (B) with line (A). The electron wavelength (B) reflects off the sphere (D) at points (d) and (e) and returns along line (C) as the electron mass. As shown in tetrahedron diagram tet0565, stored in the Library of Congress, the clockwise path of the electron transitions into the counter-clockwise path of the proton showing that the electron and proton are one and the same particle. Because the electron and proton travel in opposite directions along the path, they have the same charge but of opposite sign.

[0013] Our dimension is represented by Planck box (E) which is bounded by the Planck mass and the Planck wavelength. The Planck mass is equal to the linear mass of the universe times the Planck length which is the bottom limit of our dimension. The Planck wavelength is 2π times the Planck length. Notice that the electron is located within the Planck box.

[0014] Referring to **FIG. 7**, if there is an increase in Planck's constant due to the temperature fluctuations among the harmonic oscillators, the 45 degree base line (A) moves to the left on the tetrahedron diagram as shown by line (F).

Because of the increase in the base constant, there is a corresponding increase in the electron mass and wavelength. The electron moves from point (c) to point (f) which places it at the edge of the Planck box (F) which is the boundary between space and hyperspace. At point (f), the electron is essentially no longer in our dimension.

[0015] Referring to **FIG. 8**, imagine a box (A) filled with nine electron oscillators (B). If Planck's constant is increased near the three oscillators in the middle, these electrons will leave this dimension. This leaves six oscillators as shown in the box (C). However, box (C) is the equivalent of box (D) in which there are still nine positive mass oscillators together with 3 negative mass oscillators. Thus there is an accumulation of negative energy (−ρ) when information is lost from the environment to another dimension.

[0016] Dr. Kip Thorne, who co-authored the book *Gravitation* with Dr. Archibald Wheeler of Princeton University, has shown in a General Relativity spacetime curvature calculation that negative energy is required to open and stabilize the throat of a wormhole between space and hyperspace. The accumulation of negative energy in the aforementioned example generates wormholes between into hyperspace. Hyperspace has a low energy density because of the reduced speed of light in that dimension. Ordinarily, energy would not flow from hyperspace to space because space has a higher potential than the potential of hyperspace. This, of course, is the reason that the body vortices can flow energy into the energy field of the human being who is located in hyperspace. By creating negative energy, the potential becomes reversed such that low density hyperspace energy flows into our dimension as seen by the positive head

$$PE=\rho_{\text{hyperspace}}-(-\rho_{\text{space}})=+2\rho$$

The low-density energy fills the body which allows a human being to float upwards like a helium balloon as verified by Chi Kung breathing as well as spinning on a motorized platform known as the Chakra Vortex Accelerator. The latter device resulted in the first mechanical means to produce anti-gravity.

[0017] The process of creating spinning thermal fluctuations is the same as found in the hot air vortices created by the jet airplanes landing at the airport near the road where the full-body teleportation occurred. Large vortices are created over the wing of the airplane at the same time that the turbine engines are spinning hot vortices into relatively cold air. These conditions produce wormholes between space and hyperspace. It takes a twin turboprop airplane landing behind the jet to generate the gravitational wave in the region where the wormholes have formed. The gravitational wave then traverses the wormholes into hyperspace, becoming highly amplified due to the change in linear mass and speed of light. Because the propeller blades are co-linear with the road, the gravitational wave travels in the direction along the road where it was encountered by the inventor.

[0018] From experiments with cavitating bubbles (see patent application Cavitating Oil Hyperspace Energy Generator), it was found that it is possible to produce a wormhole if the surfaces of the bubble collapse asymmetrically. A symmetric collapse of a spherical bubble produces enormous spacetime curvature distortions. An asymmetric collapse, using a magnetic field to distort the collapse, produces, in addition to the same severe spacetime distortions, negative energy as the bubble collapses. Due to some General Relativity considerations, the wormhole that is created starts rotating in a manner similar to the beacon light produced by a lighthouse.

[0019] Referring to **FIG. 9**, due to the forward helical motion (A) of the propellers (B) as the airplane crosses the road, the pulsed gravitational wave (C) is skewed backward at an angle (D). Due to the wormholes created by the presence of thermal vorticity fluctuations generated by the wing and turbines of the airplane, this skewed wave moves into hyperspace where it is highly magnified and detected by the inventor.

[0020] Referring to top view **FIG. 10**, the gravitational wave (A) causes a skewed compression and expansion of the hyperspace quantum wells (B) which constitute the human energy being. Due to this asymmetric distortion in the xy-plane, the quantum wells take the physical body out of dimension as long as the wave pulse is traveling with the human energy field. Once the back edge of the gravitational wave moves on past the quantum wells, the body is then brought back into dimension.

SUMMARY OF THE INVENTION

[0021] It is the object of this invention to teleport a human being from one location to another by creating a pulsed gravitational wave traveling through hyperspace that asymmetrically compresses and expands the quantum wells of the human energy being. This spacetime curvature distortion of the hyperspace quantum wells pulls the physical body out of dimension such that the human being is teleported along with the wave. As the pulsed wave moves on past the quantum wells, the human is brought back into dimension at some distant location. The invention requires (1) a device that will generate a wormhole between space and hyperspace, and (2) a device that will generate a gravitational wave which can be inserted through the wormhole.

[0022] Referring to **FIG. 11**, a magnetic vortex wormhole generator has already been developed which generates a wormhole between space and hyperspace as described in a previous patent application entitled Magnetic Vortex Wormhole Generator. Using this generator, it was found that smoke blown through one side of the coil does not appear on the other side of cylindrical coil. The smoke flows through the wormhole and appears in a hyperspace co-dimension. It was this experiment that resulted in making first contact with the androids of the Grey aliens who told me, in a remote viewing session, that "We saw you blowing smoke into hyperspace."

[0023] The wormhole generator consists of two concentric cylindrical coils (A,B), one of larger radius than the other, made of thin transformer iron laminate wrapped in opposite directions with one continuous wire driven by a sinusoidal current. The solenoidal coil generates a magnetic field through the laminate. Because the electrical current flows in opposite directions at different radii through the two windings, bucking electric fields (C) are created along the centerline of the generator. These radially-offset magnetic fields and bucking electric fields, as shown by a calculation using Einstein's General Theory of Relativity, generate both an enormous spiking spacetime curvature and negative energy at small radius along the centerline where the wormhole is formed. The gravitational wave generator is then coupled to this wormhole generator.

[0024] Referring to **FIG. 12**, it is known from gravitation physics that injecting an electromagnetic wave (A) into a hollow toroidal waveguide (B) produces a hyperbolic spacetime curvature stress (C) in the plane of the waveguide. The tips of the arrows indicate compression and the tail of the arrows indicate expansion or stretching of spacetime. The reason for this spacetime curvature is because the waveguide forces the electromagnetic wave to curve around and travel in a circle. Spacetime has to compensate for this toroidal-generated stress by creating hyperbolic lines of stress in the inner plane of the toroid so that the overall spacetime curvature is zero. For a greater gravitational effect, three toroidal waveguides, phased 120 degrees apart, are used to seal off the curvature.

[0025] Referring to **FIG. 13**, the three toroids create a rotating, twisting, vertical propagating gravitational field (A) through the centerline of the toroids provided that the period of the electromagnetic wave is twice the period of the gravitational wave. This phase relationship is adjusted by selecting the correct radius for the frequency of the monochromatic wave.

[0026] In order to effectively use this gravitational wave, referring to **FIG. 14**, three phased toroidal waveguides (A,B) are mounted at the top of each of two identical square granite obelisks (C,D). The two obelisks are offset by a short distance between them. As the vertical gravitational wave rotates around along the vertical axis inside the obelisk, the edges of the square obelisks are compressed and expanded such as to create two cylindrical asymmetric gravitational waves traveling radially outward.

[0027] Referring to **FIG. 15**, these waves meet to form a plane gravitational wave (A) which travels down the centerline between the two obelisks.

[0028] Referring to **FIG. 16**, the full body teleportation system consists of the twin granite obelisks (A,B) on which are mounted near the top of each the toroidal waveguides (C,D) which produce the pulsed gravitational waves (E,F) that run the length of the obelisks. Because the gravitational wave is rotating inside the obelisk, the granite stone undergoes a very small asymmetrical compression and expansion. A cylindrical gravitational wave propagates out from each obelisk such that along the centerline between the two there is generated a plane gravitational wave. This wave enters the wormhole (H) created by the magnetic vortex generator which is located a short distance from and parallel to the obelisks. The wave is amplified by a factor of almost 10^{13} when it enters the hyperspace co-dimension.

A BRIEF DESCRIPTION OF THE DRAWINGS

[0029] **FIG. 1**. Perspective view of site where full-body teleportation occurred.

[0030] **FIG. 2**. Perspective view of gravitational wave generator.

[0031] **FIG. 3**. Planar view of gravitational wave generator.

[0032] **FIG. 4**. Perspective view of seven vortices of human energy being.

[0033] **FIG. 5**. Perspective view of seven large quantum wells of human energy being.

[0034] **FIG. 6**. Tetrahedron diagram showing Planck's constant and electron.

[0035] **FIG. 7**. Tetrahedron diagram showing electron moving out of dimension.

[0036] **FIG. 8**. Perspective view showing production of negative energy.

[0037] **FIG. 9**. Perspective view of skewed gravitational wave produced by propellers.

[0038] **FIG. 10**. Planar view of skewed quantum wells deformed by gravitational wave.

[0039] **FIG. 11**. Perspective view of magnetic vortex wormhole generator.

[0040] **FIG. 12**. Perspective view of hyperbolic lines of stress generated by toroidal waveguide.

[0041] **FIG. 13**. Perspective view of rotating, twisting, propagating gravitational wave generated by toroidal waveguides.

[0042] **FIG. 14**. Perspective view of toroidal waveguides attached to obelisks.

[0043] **FIG. 15**. Perspective view of gravitational wave generated by obelisks.

[0044] **FIG. 16**. Perspective view of magnetic vortex wormhole generator and obelisk gravitational wave generator.

DETAILED DESCRIPTION OF THE INVENTION

[0045] 1. The obelisks are quarried out of granite stone and cut with a large-diameter diamond saw that is used in highway construction. The beveled piece at the top is cut separately and cemented in place. A tapered aluminum bracket holds the toroids in place.

[0046] 2. The electronics for the magnetic vortex generator are similar to that used in the patent application Magnetic Vortex Wormhole Generator.

[0047] 3. The electronics for the toroidal waveguides is the familiar stub and coaxial cable driven by an amplifier and pulsed variable-frequency generator.

I claim:

1. A full body teleportation system consisting of:

generating a pulsed gravitational wave which propagates through a magnetic vortex wormhole generator; and

generating a wormhole with the magnetic vortex generator whereby the pulsed gravitational wave traverses through the wormhole and enters into hyperspace where the wave is enormously magnified due to the lower speed of light in that dimension.

2. The method of claim 1, wherein the step of generating the pulsed gravitational wave comprises:

using two granite stone obelisks;

mounting monochromatic-wave toroidal waveguides on top of each obelisk to create a rotating, twisting, propagating gravitational wave through the vertical axis of each obelisk; and

creating a cylindrical compression and expansion in each obelisk to produce a plane gravitational wave traveling down the centerline between the two obelisks.

3. The method of claim 1, wherein the step of generating a wormhole into hyperspace comprises:

using two concentric cylindrical solenoidal coils of different radii connected by a single wire wrapped in opposite directions on thin iron transformer laminate;

generating bucking electric fields down the centerline of the vortex generator which creates a spacetime curvature distortion with negative energy in accordance with Einstein's General Theory of Relativity.

4. A teleportation system comprising:

generating a gravitational wave traveling through hyperspace which interacts with the human energy being; and

pulling the human energy being and physical body out of dimension when interacting with the pulsed gravitational wave such that the person is teleported from one location to another through hyperspace and back again into our **4**D spacetime dimension.

* * * * *

US 20060145019A1

(19) **United States**
(12) **Patent Application Publication** (10) **Pub. No.: US 2006/0145019 A1**
St. Clair (43) **Pub. Date: Jul. 6, 2006**

(54) **TRIANGULAR SPACECRAFT**

(76) Inventor: **John Quincy St. Clair**, San Juan, PR (US)

Correspondence Address:
JOHN ST. CLAIR
52 KINGS COURT, 4A
SAN JUAN, PR 00911 (US)

(21) Appl. No.: **11/017,093**

(22) Filed: **Dec. 20, 2004**

Publication Classification

(51) **Int. Cl.**
B64G 1/40 (2006.01)
(52) **U.S. Cl.** **244/171.5**

(57) **ABSTRACT**

A spacecraft having a triangular hull with vertical electrostatic line charges on each corner that produce a horizontal electric field parallel to the sides of the hull. This field, interacting with a plane wave emitted by antennas on the side of the hull, generates a force per volume combining both lift and propulsion.



Figure 1



Figure 2



Figure 3



Figure 4



Figure 5



Figure 6



Figure 7


$\frac{3}{4}\lambda$
$\frac{\lambda}{2}$
$\frac{\lambda}{2}$
E
D
B
A
F
C

TRIANGULAR SPACECRAFT

BRIEF SUMMARY OF THE INVENTION

[0001] This invention is a spacecraft having a triangular hull with vertical electrostatic line charges on each corner. The line charges create a horizontal electric field that, together with a plane wave emitted by antennas on the side of the hull, generates a force per volume providing a unique combination of both lift and propulsion.

BACKGROUND OF THE INVENTION

[0002] Referring to **FIG. 1**, the spacecraft has a hull in the shape of an equilateral triangle. A parabolic antenna (E) is centrally located in the bottom of the hull. An array of horizontal slot antennas is located along the side of the hull (A). Each back corner (F,G) has a corner conducting plate which is charged to a positive voltage +V. The forward corner (C) has a conducting plate charged to a negative voltage −V. A motion control hemisphere (D) is located on the bottom surface in each of the three corners.

[0003] Referring to **FIG. 2**, two planes (A,B) intersect at the origin O at an opening angle β. Each plane (x,y) is charged to a voltage V. The potential at point P is determined in polar coordinates {ρϕ}. The Laplace equation for the potential Φ in polar coordinates is given by:

$$\frac{1}{\rho}\frac{\partial}{\partial\rho}\left(\rho\frac{\partial\Phi}{\partial\rho}\right)+\frac{1}{\rho^2}\frac{\partial^2\Phi}{\partial\phi^2}=0$$

Using a separation of variables solution, the potential is given as the product of two functions:

$$\Phi(\rho,\phi)=R(\rho)\Psi(\phi)$$

which when substituted into the Laplace equation becomes:

$$\frac{\rho}{R}\frac{d}{d\rho}\left(\rho\frac{dR}{d\rho}\right)+\frac{1}{\Psi}\frac{d^2\Psi}{d\phi^2}=0$$

Since the two terns are separately functions of ρ and ϕ respectively, each one has to be constant with the sum of the constants equal to zero:

$$\frac{\rho}{R}\frac{d}{d\rho}\left(\rho\frac{dR}{d\rho}\right)=v^2 \quad \frac{1}{\Psi}\frac{d^2\Psi}{d\phi^2}=-v^2$$

These two equations have solutions:

$$R(\rho)=a\rho^{v+b\rho-v}$$

$$\psi(\phi)=A\cos(v\phi)+B\sin(v\phi)$$

The azimuthal angle ϕ is restricted to a value in the range $0\leqq\phi\leqq\beta$. The boundary condition is that the potential Φ is equal to V for any radius ρ when ϕ=0 and ϕ=β. This means that v has to be an integer value of π so that the sine function is zero:

$$\sin(v\beta)=\sin\left(\frac{m\pi}{\beta}\beta\right)=\sin(m\pi)=0 \quad m=1, 2 \ldots$$

which in turn means that the coefficient A of the cosine term has to be zero in the solution above. Choosing b=0 makes the general solution for the potential equal to:

$$\Phi(\rho,\phi)=V+\sum_{m=1}^{\infty}a_m\rho^{m\pi/\beta}\sin(m\pi\phi/\beta)$$

which shows that when the angle is zero, the sine is zero and the potential is V. If the angle is β, then there is a multiple of π such that the sine is zero again.

[0004] Because the series involves positive powers of the radius, for small enough ρ, only the first term *m*=1 in the series is important. Thus around ρ=0, the potential is approximately

$$\phi(\rho,\phi)\approx V+a,\rho^{\pi/\beta}\sin(\pi\phi/\beta)$$

[0005] The electric field component is the negative gradient of the potential:

$$E_\phi(\rho,\phi)=-\frac{1}{\rho}\frac{\partial\Phi}{\partial\phi}=-\frac{\pi a_1}{\beta}\rho^{(\pi/\beta)-1}\cos(\pi\phi/\beta)$$

The surface charge distribution σ at ϕ=0 and ϕ=β is equal to the electric field perpendicular to the surface times the permittivity of space ϵ_0:

$$\sigma(\rho)=\varepsilon_0E_\phi(\rho,0)=-\frac{\varepsilon_0\pi a_1}{\beta}\rho^{\frac{\pi}{\beta}-1}$$

Notice that if angle of intersection β is less than π, then the equation says that there is a very small radius to a positive power which means little charge density accumulation.

[0006] Referring to **FIG. 3**, the value of β, in the case of the triangular hull, is equal to 360° less 60° for a total of 300° or:

$$\beta=\frac{300}{180}\pi=\frac{5}{3}\pi$$

$$\rho^{\frac{\pi}{\frac{5}{3}\pi}-1}=\frac{1}{\rho^{\frac{2}{5}}}$$

which says that there is a charge density singularity to the two fifths power for small radius. Thus, the corner plates on the hull create a huge line charge density along the sharp vertical corner edge. The equation for the potential of a line charge density is given as:

$$\Phi(x,y)=-\frac{\lambda}{2\pi\varepsilon_0}\mathrm{Ln}((x-x_0)^2+(y-y_0)^2)$$

where λ is the charge per unit length in the vertical z-direction, and x_0 and y_0 are the location of the line charge in the xy-plane.

[0007] Referring to **FIG. 4**, the triangular hull (D) is plotted together with the potential contours (A) and the electric field arrows (B) created by the three corner line charges. The line charges are perpendicular to the paper. Notice that the electric field arrows are parallel crossing the center parabolic antenna (C). The electric field is also parallel to the sides (D) of the triangle.

[0008] Referring to **FIG. 5**, along the side of the triangle (A), an array (B) of horizontal slot antennas emit electromagnetic waves that have a vertically polarized electric E field (C). These traveling waves interact with the electric field (D) produced by the line charges on the corners of the triangle.

[0009] Using differential forms mathematics, this combination of fields is represented by the Hodge star of the differential of the wedge product of the two fields. The antenna electromagnetic field is a combination of a traveling magnetic field B_w, and electric field E_w. The stationary field E created by the line charges is perpendicular to the traveling wave.

$$^{*}d(E \wedge (B_w + E_w \wedge dt))\frac{\varepsilon}{c} = \frac{\text{force}}{\text{volume}}$$

where ϵ is the linear capacitance of space and c is the speed of light. Thus there is a force per volume around the hull.

[0010] This combination of fields produces a spacetime curvature as determined by Einstein's General Theory of Relativity. The traveling electric field has an amplitude in the vertical z-direction and travels in the x-direction

$$E_{\mathrm{w=Ez}}\cos(x-t)$$

The Faraday electromagnetic tensor contains all the electric and magnetic fields in all the {x,y,z} directions. The first row and first column contain the two electric fields

$$F^{\alpha}_{\beta} = \begin{array}{c|cccc|} t & 0 & E_x & 0 & E_z\cos(x-t) \\ x & E_x & 0 & 0 & 0 \\ y & 0 & 0 & 0 & 0 \\ z & E_z\cos(x-t) & 0 & 0 & 0 \end{array}$$

The stress exerted on spacetime occurs in the xx, yy and zz-direction as calculated from the stress-energy tensor T of gravitational physics

$$4\pi T^{\mu\nu} = F^{\mu\alpha}F^{\mu}_{\alpha} - \frac{1}{4}g^{\mu\nu}F_{\alpha\beta}F^{\alpha\beta}$$

where g is the metric tensor for Cartesian space

$$g_{\alpha\beta} = \begin{array}{c|cccc|} t & -1 & 0 & 0 & 0 \\ x & 0 & 1 & 0 & 0 \\ y & 0 & 0 & 1 & 0 \\ z & 0 & 0 & 0 & 1 \end{array}$$

where the diagonal components are the coefficients of the elementary spacetime length ds squared

$$(ds)^2=-(dt)^2+(dx)^2+(dy)^2+(dz)^2$$

The calculation produces three stresses T^{xx},T^{yy} and T^{zz} in their respective {x,y,z} directions.

[0011] Referring to **FIG. 6**, these three stresses are plotted together as a **3**D vector field animated over time in nine frames. The graphs show that there is a lift force as depicted by the vertical arrows as well as a force of propulsion as shown by the interspersed horizontal arrows. With the passage of time, these vectors exchange places with each other so that the lift becomes the propulsion and vice versa, creating a wavy stress-energy field around the hull.

SUMMARY OF THE INVENTION

[0012] This invention is a spacecraft with a triangular hull having charged flat plates on the vertical corners of the three sides. The two rear corners are charged to a potential V. The forward corner is charged to a potential –V. The 60° angle on the corner creates a line charge density singularity that produces a huge horizontal electric field pointing from the back to the front of the craft which is also parallel to the sides of the triangle. An array of horizontal slot antennas located on the sides of the triangular hull produce an electromagnetic wave with the electric field polarized in the vertical direction. This combination of fields produces a spacetime force in both the vertical and horizontal directions such that the spacecraft receives a lift force and a force of propulsion.

A BRIEF DESCRIPTION OF THE DRAWINGS

[0013] **FIG. 1**. Perspective view of triangular spacecraft.

[0014] **FIG. 2**. Drawing of the intersection of two charged plates in order to calculate the charge density in the corner.

[0015] **FIG. 3**. Perspective view of the corner angle β for the equilateral triangle.

[0016] **FIG. 4**. Planar **2**D graph showing the electric field produced by three line charges on the corners of the triangular hull.

[0017] **FIG. 5**. Perspective view of electric field produced by the linear charge interacting with the traveling electromagnetic wave produced by the slot antenna.

[0018] **FIG. 6**. **3**D vector animation of the lift and thrust force generated by the fields.

[0019] **FIG. 7**. Perspective view of slot antenna.

DETAILED DESCRIPTION OF THE INVENTION

[0020] Referring to **FIG. 7**, the antenna (A) is made out of sheet copper in which a rectangular horizontal slot (B) has been notched out using a die press and sheet metal fixture. A coaxial cable from the amplifier and frequency generator is attached across the slot by soldering the outer cable (D) to one side of the slot and the inner cable (E) to the other side of the slot. This creates the positive and negative charges across the gap which forms the vertical electric field (F) which radiates out perpendicularly to the copper sheet.

[**0021**] Although the invention has been described with reference to specific embodiments, such as a particular antenna system, those skilled in the art will appreciate that many modifications and variations are possible without departing from the teachings of the invention. All such modifications and variations are intended to be encompassed within the scope of the following claims.

1. A spacecraft comprised of the following components:

(a) a triangular hull in the form of an equilateral triangle;

(b) two copper plates attached on opposite vertical sides at each of the three corners of the hull (**1***a*) such that a sharp vertical edge is formed where they come together;

(c) an electrostatic generator used to charge the back two copper-cladded corners (**1***b*) to a high positive voltage, and the third forward copper-cladded corner to a high negative voltage;

(d) a horizontal slot antenna array mounted-on the sides of the hull; and

(e) a frequency generator, antenna and coaxial cables to drive the antenna array (**1***d*).

2. To create, by claims (**1***a*, **1***b*, **1***c*), an intense vertical line charge at the corners (**1***b*) and a horizontal electric field that that is parallel to the sides of the hull (**1***a*);

3. To create, by claims (**1***d*,**1***e*), an electromagnetic wave with a vertically polarized electric field traveling outward from the side of the hull (**1***a*); and

4. To create, by claims (**2**,**3**), an interaction of the electrostatic field (**2**) with the electromagnetic wave (**3**) such that a combined spacetime curvature pressure is generated on the hull in the upward and forward direction to produce lift and propulsion respectively.

* * * * *

March 25, 1969 W. C. BROWN ET AL 3,434,678

MICROWAVE TO DC CONVERTER

Filed May 5, 1965

Sheet 1 of 3

FIG. 1


11
4
2
10
6
8
DC
MICROWAVE
ENERGY


20
DIPOLE
24
25
DC LOAD
26
27
22

FIG. 2

FIG. 3


30
30
30
32
33

FIG. 4


40
40
40
41
42


52
53
54
51
50

FIG. 5

INVENTORS
WILLIAM C. BROWN
ROSCOE H. GEORGE
NEIL I. HEENAN
ROGER C. WONSON

BY Edgar O. Rost
ATTORNEY

March 25, 1969 W. C. BROWN ET AL **3,434,678**

MICROWAVE TO DC CONVERTER

Filed May 5, 1965

Sheet 2 of 3

FIG. 7


70
86
84
82
HELICOPTER
72
MICROWAVE
BEAM
74
MICROWAVE
GENERATOR
76
78
FOCUSING ANTENNA
80



FIG. 6

INVENTORS
WILLIAM C. BROWN
ROSCOE H. GEORGE
NEIL I. HEENAN
ROGER C. WONSON

BY Edgar O. Kost
ATTORNEY



82
94
90
101
100
92
101
97
100
102
A
99
97
95
B
99

FIG. 8



92
90
91
90
91
90
91
99
102
96
101
98

FIG. 9

INVENTORS
WILLIAM C. BROWN
ROSCOE H. GEORGE
NEIL I. HEENAN
ROGER C. WONSON

BY Edgar O. Rost
ATTORNEY

United States Patent Office

3,434,678

Patented Mar. 25, 1969

3,434,678

MICROWAVE TO DC CONVERTER

William C. Brown, Weston, Mass., Roscoe H. George, West Lafayette, Ind., and Neil I. Heenan, Needham, and Roger C. Wonson, Beverly, Mass., assignors to Raytheon Company, Lexington, Mass., a corporation of Delaware

Filed May 5, 1965, Ser. No. 453,415
Int. Cl. B64g *1/00*
U.S. Cl. 244—1 3 Claims

ABSTRACT OF THE DISCLOSURE

A combined antenna and conversion mechanism for reception of beamed high frequency electromagnetic energy in space including a large array of unidirectional current semiconductor rectifier devices. A self-supporting space vehicle utilizing the rectified DC electrical energy for propulsion is disclosed in an illustrative embodiment.

The present invention relates in general to the transfer of energy by means of an electromagnetic wave beam and more particularly to interception and rectification of such energy into low frequency electrical DC energy with a high degree of efficiency.

Improved technology in the field of microwave energy generation at superpower levels has resulted in the realization of electrical energy transmission over considerable distances for remote energization of devices or vehicles without the aid of wires. The transmission of microwave electromagnetic energy into space has been commonly employed in the radar pulse echo systems for the detection and orientation of desired objects within a predetermined scanning range of a transmitting antenna. Beams of a similar nature may now be employed for other useful purposes and the advantages attendant the utilization of electromagnetic energy in the microwave region in contrast with other wavelengths may now be enumerated.

Microwaves have been generally defined as high frequency radio waves whose wavelength is less than 30 centimeters, with a lower wavelength limit on the order of 1 millimeter sometimes being applied to what is commonly referred to as the "microwave region." The superiority of high frequency microwaves is due in part to the fact that it is generally desirable to focus the transmitted energy so as to achieve a high power density at a remote point or area with respect to a given power source. In accordance with the laws of optics, the sharpness of the microwave beam produced by a transmitting antenna varies as the ratio of antenna dimensions to the wavelength of the transmitted energy. Therefore, for a given or desired power density or beam sharpness, a decrease in the wavelength of the transmitted energy permits a corresponding decrease in the dimensions of the antenna. From the standpoint of mechanical considerations, it is desirable to employ small antennas and other components, and it is therefore advantageous to employ high frequency energy of very short wavelength. In addition, the difficulties encountered in long wave transmission as a result of natural and man-made interference or noise do not occur with any appreciable significance at microwave frequencies. Further, in aerospace applications with considerable distances separating the transmitter at an earth or mother planet location and the employment of shorter wavelength beamed energy is preferred since longer wave signals will generallly be reflected at certain altitudes by reflecting layers in the atmosphere.

In view of certain losses due to absorption which may occur in the atmosphere, microwaves in the region having the approximate bounds of 2 and 30 centimeters are

readily adaptable to the convenient radiation of power to remote points without the utilization of wires. The preferred wavelengths are of the order of 5 or 10 centimeters to provide efficient focusing with existing transmitting antenna systems which may be maintained at a reasonable size. An illustrative device of the superpower high frequency microwave generators operative in the desired band is the so-called Amplitron which is an amplifier having a broad bandwidth and excellent performance characteristics for the focusing of the beam. Such devices are capable of producing 15 or 20 kilowatts of average continuous wave power in the neighborhood of 10 centimeters in wavelength with capabilities expected in the region of 500 kilowatts or more average power with 50 megawatts peak power. A complete description of such devices may be had by referring to Patent No. 2,933,723 issued Apr. 19, 1960 to William C. Brown and assigned to the assignee of the present invention.

With microwave energy capable of being generated and directed over longer distances conversion of such high frequency electromagnetic energy is of paramount concern. One conversion mechanism in the prior art involves direct conversion of such energy into heat which may then be utilized directly or indirectly for propulsion or generation of flight-producing forces. Examples of such devices for heat energy exchange as well as space vehicles utilizing such energy may be noted in Patent No. 3,174,705, issued Mar. 23, 1965, to D. Schiff et al., as well as U.S. Letters Patent No. 3,083,528, issued Apr. 2, 1963 and No. 3,114,517, issued Dec. 17, 1963, to William C. Brown. The heat exchanger method of conversion of electromagnetic energy into useful power is limited by the overall efficiencies of approximately 25 percent in the conversion of heat into mechanical or electrical work. Desirable, therefore, would be the direct rectification of the high frequency electromagnetic energy into low frequency electrical energy for the operation of many useful aerospace devices as well as systems.

The present invention has for its primary object the conversion of high frequency electromagnetic energy in the microwave region directly into low frequency electrical energy.

A further object of the present invention is the provision of a combined nondirectional receiving antenna and microwave electromagnetic energy to low frequency electrical energy conversion means in a unitary structure.

A still further object of the present invention is a provision of a new and novel combined nondirectional receiving antenna and microwave to DC energy converter for aerospace applications.

Another object of the present invention is the provision of a new and novel nondirectional receiving antenna and microwave to DC energy converter having a high degree of efficiency.

Still another object of the present invention is the provision of a new and novel aerospace vehicle with nondirectional receiving antenna and microwave to DC energy converter means with said vehicle being capable of being supported by its own energy generation means at a distance spaced apart from the power generation means.

In accordance with the teachings of the present invention, the above and other objects are achieved by the employment of efficient unidirectional microwave power rectifiers and dipole antenna means. Such rectifying devices, while being individually limited in power-handling capabilities, normally in the order of fractions of watts, have been found to be highly efficient means for the rectification of microwave power when assembled in large numbers in various arrays. It is interesting to note that the observed collective efficiency was on the order of 40 to 70 percent. In an illustrative embodiment, point-contact semiconductor diodes were arranged in four arm bridge connected networks with the networks interconnected in various configurations such as series, parallel and series-parallel.

In discussing aerospace applications, an additional problem is encountered in the beaming of microwave energy to a remote point and the interception and utilization of such electrical energy. In such applications the advantages of a vehicle which may be maintained in space for indeterminate periods of time without employing a local fuel source are readily apparent. Such devices could readily provide communication networks, surveillance functions using radar techniques along with numerous other functions. The acapture of the beamed high frequency electromagnetic energy raises the need for an efficient antenna means capable of intersecting the beam at high altitudes. Conventional techniques employed in microwave radar usage such as receiving antenna horns are capable of intersecting only a small portion of the beam energy and add considerable weight in applications involving heavier-than-air vehicles. In an exemplary embodiment of the invention a space vehicle, namely a helicopter, is disclosed for either moving flight or a stationary location with self-supporting electrically operative propulsion means. The semi-conductor diode rectifier arrays have been demonstrated to fulfill the receiving antenna functions as well as the electrical energy rectification means in a highly efficient manner. Such combined antenna and rectifier means has also assisted in reduction of the weight problem in airborne devices. Further, it has provided a nondirectional means for the interception of the microwave energy to thereby reduce the problems of focusing inherent in prior art directional horn type receiving antennas.

With the above features, advantages and objects in mind the invention will now be described by reference to the following detailed description together with the accompanying drawings in which:

FIG. 1 is a perspective view of an illustrative diode rectifier;

FIG. 2 is a schematic circuit diagram of a bridge connected diode network with dipole antenna means;

FIG. 3 is a schematic circuit diagram of a plurality of bridge connected networks arranged in series;

FIG. 4 is a schematic circuit diagram of a parallel bridge connected network array;

FIG. 5 is a perspective view of an illustrative embodiment of a combined antenna and rectifier array in a folded or rolled up configuration;

FIG. 6 is a schematic circuit diagram illustrating the bridge connected diode array incorporated in the aerospace vehicle shown in FIG. 7;

FIG. 7 is a schematic representation in elevation illustrative of a heavier-than-air aerospace vehicle incorparating the structure of the present invention;

FIG. 8 is a perspective view of the aerospace vehicle embodiment as viewed from the under portion thereof; and

FIG. 9 is an enlarged partial view in elevation of a portion of the illustrative embodiment shown in FIG. 8.

FIG. 1 illustrates a point-contact semiconductor diode rectifier of the type employed in radar microwave receiver apparatus to rectify returned radar pulses. Any of the high burnout semiconductor diodes having high rectification characteristics are preferred and are commercially available, such as the 1N82 or 1N830. The rectifying junction is formed by whisker element **2** contacting the semiconductor element **4** respectively connected to leads **6** and **8**. Silicon is preferred over germanium for element **4** because of its ability to operate at higher temperatures and thereby handle higher powers. Envelope **10** houses the rectifying elements and may be of a hermetically sealed dielectric material or combination metal and ceramic composition. The inherent characteristic of such diode rectifiers is that the microwave energy is intercepted and rectified in a unidirectional manner and the line **11** indicate pictorially the rays of the beamed electromagnetic microwave energy in a plane normal to the envelope. In FIG. 2 a full-wave bridge connected diode network is illustrated with the forward direction of the rectified DC electric current indicated by the direction of the arrow symbols. The network shown consists of half-wave dipoles **20** and **22** each terminated with a diode rectifier element **24** to **27** in an arm of the bridge connected network. The dipole elements **20** and **22** are of the half-wave configuration and may be spaced apart from each other a one-half wavelength at the frequency of the beamed electromagnetic energy.

Referring now to FIG. 3, an array of bridge connected diode networks each with the half-wave dipoles are shown connected in series. Each network is referred to by the numeral **30** and is similar in the bridge connections to the single element network shown in FIG. 2. The DC output of the collective rectified energy is coupled by means of terminals **32** and **33**. In FIG. 4, a similar number of individual bridge connected diode-dipole networks are shown connected in a parallel array. Each network is indicated by the numeral **40**, and the output terminals are indicated as **41** and **42**.

Any number of diode-dipole networks may be provided and in FIG. 5 such a multi-element array is illustrated by mounting on a flexible material **50** which may be rolled or folded into any desired package or enclosed within a capsule to be launched and released at a predetermined point in space. Any flexible material which is pervious to electromagnetic energy is preferred. The total power desired would be the determining factor in a number of individual diode-dipole elements required. In this embodiment, the bridge connected networks **51** are connected in parallel to the output load indicated by terminals **52** and **53**, and representative measurements of electrical characteristics have shown that approximately five watts of DC electrical energy is realizable for each square foot of area of the combined antenna-rectifier. While the dipole elements **54** have been indicated in a particular array, it is within the scope of the invention to stagger the placement of such dipoles to increase the overall efficiency of the antenna-rectifier.

To further increase the DC powder output, the full-wave bridge connected networks are preferably arranged with a plurality of diodes in series in each arm of the bridge. An illustrative schematic circuit diagram of such a configuration is shown in FIG. 6 wherein seven diodes **60** are shown in each arm of the bridge circuit and are connected in series for a total of twenty-eight diodes in each bridge network. The dipole members will then be the substantially U-shaped end portions **61** at the ends of each brace of seven diodes. In the illustration three such twenty-eight diode bridge networks are shown connected in parallel to terminals **62** and **63**. This closer spacing and compact arrangement has been shown to be a source of improved power output and is capable of a high degree of reliability through the redundant nature of the parallel series connections within each bridge network. If one of the diode rectifiers fails to function the over-all voltage drop across this element would be divided among the six remaining diode rectifiers. If any of the connecting wires between the diode elements should break, the adjacent arms of the other bridge assemblies would take the additional load due to the close proximity of the respective arms to each other. In addition, it is possible to have a number of open connections or inoperative diodes dispersed throughout the array without any serious impairment in performance.

In relation to the array concept to be hereinafter described it may be stated that within a six inch square area ten such individual bridge networks each containing twenty-eight diode rectifiers for a total of 280 diode rectifiers may be deployed in such a manner as to provide maximum exposed area for each diode as well as the connecting leads. Such an arrangement will be hereinafter referred to as a "module" and a DC output in excess of fourteen watts has been measured for such a module. Any number of such modules could be connected provided for a desired power yield and this module concept readily lends itself to use in certain aerospace applications now to be described.

In FIG. 7 a propelled type of space vehicle **70** is shown wholly supported by means of the transfer and rectification of continuous wave electromagnetic energy via a microwave beam **72**. The source of the microwave energy which may be of the Amplitron type device as described in the aforementioned issued Patent No. 2,933,723 is indicated as **74**. This energy is fed by waveguide means **76** to a transmitting horn **78** to illuminate an ellipsoidal beam forming focusing antenna **80** for the transmission of the microwave beam **72**. It will be appreciated by those skilled in the art that the representations of the microwave generation and transmitting antenna means are pictorial representations to illustrate the usage of the invention in diagrammatic form and the present invention is not limited to any particular source of microwave energy or transmitting antenna assembly. It may be stated the reflector of the antenna assembly is considerably larger than most of the reflectors of the prior art in order to focus a large amount of the microwave power at high altitudes for use in the transfer of energy to space vehicles. Such antenna assemblies may be partially supported in a large hollowed area on the earth's surface or other convenient means of support.

The space vehicle or helicopter **70** can be described as a main body member supporting antenna-rectifier means **82** including a large number of the so-called modules connected together and rigidly supported in a planar parallel array. A motor **84** is supported by the combined body member and the receiving antenna-rectifier means and actuates the rotor **86** of conventional design employed in such self-propelled hovering vehicles. The disclosed vehicle provides for the illumination of the planar array of the semiconductor diode dipole elements by the microwave beam and the direct conversion of the microwave power transmitted by the beam into usable electrical energy for the self-propulsion of the device without any local fuel supply being required.

FIGS. 8 and 9 illustrate a space vehicle **82** comprising a plurality of the combined receiving antenna-rectifier module means for interception and rectification of the electromagnetic microwave energy beam emanating from an earth or mother planet source. A planar array of the antenna-rectifier modules is mechanically supported by means of structural members **90** of any lightweight wood or metal. Insulators **91** positioned coextensive with the members **90** support the diode rectifier array and avoid interference with the receiving and electrical performance characteristics by the structural support members. Carrying forward the module concept of 280 diode rectifiers to provide an approximate power output of 14 watts, it was noted that any number of such modules may be coupled together since the individual module outputs are relatively insensitive to a wide range of load resistances connected to the common output terminals. To achieve the desired electrical output of approximately 120 volts and 250 watts of power, subgroups of four modules each were assembled and parallel connected with an approximate 30 volts available for each subgroup. Four such subgroups were series-connected to result in a total of 4,480 diode rectifiers or 16 modules assembled in a two foot square self-supporting planar parallel array structure. The individual diode rectifiers connected in each arm of the bridge network are indicated by the numeral **92**. An exemplary module configuration would extend within the area delineated by the dotted lines and reference letter A on one side and similar dotted lines and reference letter B on the other side.

A motor **94** is connected to the DC side of the overall array and may be additionally supported by tubular member **95**. A shaft and propulsion means consisting of rotor blades **97** provide for the upward lift of the overall vehicle for the self-supporting of same in space applications. Additional structural support such as interlaced rigging **96** of a high tensile strength material such as nylon or steel wire, as well as bracing member **98**, may be employed for strengthening of the body means to withstand the vibrational forces and downwash from the propulsion means.

In accordance with the well known technology of microwave transmission the combined array of diode rectifiers and propulsion means presents a specific load impedance which must be suitably matched to the transmitted microwave energy beam to result in maximum efficiency. In aerospace applications a mismatch of approximately ten to one may be evident. Matching of the load impedance to a value of approximately 377 ohms as the free space value will be provided by a plurality of coplanar parallel metallic rod members **99** disposed in a grating array in front of the diode rectifiers a predetermined distance. Rod members **99** are linearly disposed and extend in a similar direction as the assembled diode rectifiers. A selected frontal spacing of one-quarter of the wavelength of the microwave frequency being transmitted has been experimentally determined to be suitable for impedance matching purposes. An approximate spacing of two inches between the respective members was preferred for a selected microwave frequency of 2,450 megacycles. Each of the members **90** are provided with lateral sections **100** to support the elongated bar members **101** which in turn maintain the rod members **99** in the desired position. A tubular member **102** of a lightweight metal may also be provided to combine with the motor support member **95** for structural support.

The combined antenna-rectifier array provides a source of electrical energy to render any space vehicle self-supporting. The diode rectifier elements when assembled in the antenna array have been found to be nondirectional with respect to interception of the beamed microwave energy. This represents a large step forward in the utilization of high power microwave energy over the prior art horn-type receiving antennas which must be accurately focused and pointed in a particular direction for the reception of any energy. The connections between the respective members of the diode rectifier array and deployment in the parallel configuration serves to provide maximum exposed area. Such connections and in particular the end loop portions adjacent the terminus of each arm of the bridge networks serves as an efficient dipole for the interception of the microwave energy.

Although it is not intended as a full explanation of the high degree of efficiency attained with the disclosed antenna-rectifier array, it is believed that the whisker elements within the semiconductor diodes themselves are a contributing factor and may function as additional dipole elements. The disclosed embodiment functioned efficiently when illuminated by microwave energy generating a vertically polarized beam. Hence, an efficient and light weight energy conversion apparatus is disclosed which may be self-supporting without the requirement of a large local fuel supply payload.

It may be within the purview of the invention to use the available rectified electrical energy for performing many functions in addition to the actuation of the propulsion means. Hence, communications' payloads may be maintained at predetermined positions in space in a hovering attitude utilizing a portion of the electrical energy available. Relay signals to other such vehicles or return signals to ground stations would then be within the realm of possibility. Such available energy may also be employed for servomechanisms, stabilizing and countertorque systems for the navigation of such vehicles.

The electrical efficiencies realized with the combined receiving antenna and rectifier means have also provided certain weight advantages over other energy converters in aerospace applications. Examples of such converters would be heat exchangers or solar cells. In comparison to the present invention where five to eight pounds per kilowatt of energy realized is a normal characteristic, other energy conversion means weigh in the vicinity of 150 pounds per kilowatt of realizable energy. The inherent advantages of the present invention are therefore apparent. While the technology in the diode rectifier art is being continually advanced, new diode power rectifiers as well as integrated circuit techniques are readily available to future configurations of the present invention. The so-called Schottky barrier diodes could be employed to produce combined antenna-rectifier means weighing even less than two pounds per kilowatt of available energy.

Although the foregoing detailed description has referred to DC power rectification it will be evident that with suitable circuit components low frequency AC energy may also be made available. In addition, other propulsion means may be readily substituted using electrical energy. The embodiments disclosed herein are illustrative only and other modifications or alterations will be apparent to those skilled in the art which do not depart from the scope of the broadest aspects of the present invention as defined in the appended claims.

What is claimed is:

1. A space vehicle comprising:
body means;
said body means including spaced structural support members;
combined antenna and DC electrical energy rectification means for the interception and rectification of incident high frequency electromagnetic microwave energy carried by said support members in a planar parallel array;
said rectification means comprising a plurality of four arm full-wave bridge connected rectifier circuit networks each having a plurality of unidirectional semiconductors in each arm;
said networks being electrically interconnected to common output terminals;
electrically operable propulsion means comprising a motor and rotor members carried by said body means and connected to said terminals for the utilization of said rectified DC energy; and
means for matching the load impedance of said combined antenna and electrical energy rectification means to the incident microwave energy.

2. A space vehicle according to claim **1** wherein said load impedance matching means are arranged in a coplanar array coextensive with said antenna and energy rectification means array, and spaced therefrom a distance of approximately one-quarter of a wavelength at the frequency of the microwave energy.

3. A space vehicle according to claim **2** wherein said load impedance matching means comprise a plurality of parallel disposed elongated metallic members.

References Cited

UNITED STATES PATENTS

1,217,149	2/1917	Caldwell	321—27 X
2,165,055	7/1939	Kafka	321—27
2,444,458	7/1948	Master	321—8
2,927,321	3/1960	Harris	343—6.8 X
3,098,971	7/1963	Richardson	325—592 X
3,174,705	3/1965	Schiff et al.	244—1

RODNEY D. BENNETT, *Primary Examiner.*

MALCOMB F. HUBLER, *Assistant Examiner.*

U.S. Cl. X.R.

307—151; 318—16; 321—27; 325—494; 343—100

Teleportation of Entangled Coherent States through Visual Pathways in the Human Brain

[1,2,3]**V. Salari**[*] , [1,2]**M. Rahnama**[†] and [4]**J. A. Tuszynski**[‡]

[1]*Department of Physics, Shahid Bahonar University of Kerman, P. O. Box 76175, Kerman, Iran*
[2]*Afzal Research Institute, Kerman, Iran*
[3]*Neuroscience Research Center, Kerman, Iran*
[4]*Department of Physics, University of Alberta, Edmonton, T6G 2J1, Canada*

Abstract:
In this paper we have proposed a new model for visual consciousness based on the premise there exists a quantum teleportation mechanism between the eye and the brain. In our model, some open questions will be answered.

1) Introduction:

Schrödinger's book "What is life?" has had an enormous influence on the development of molecular biology [1]. His insight has since then inspired many researchers to investigate the molecular basis of a living organism [2,3,4]. Several researchers have noticed the sweeping consequences that would follow from the discovery that living organisms might process information quantum mechanically, either at the bio-molecular level, or the cellular/neuronal level [5,6,7,8,9]. Computational models of the behavior of networks of neurons are still mainly based on the integrate-and-fire model of neural function. Mainstream cognitive neuroscience typically ignores the role of quantum physical effects in the neural processes underlying cognition and consciousness. However, many unsolved problems remain, suggesting the need to consider new approaches. Recent contributions to the investigations of quantum effects in the human brain are due to Jibu and Yasue, Pribram, Lockwood, Mavromatos and Nanopoulous, Hameroff and Penrose, and Stapp [10]. These authors have proposed models in which the operation of consciousness is associated with some sort of explicit wave function collapse. There have been numerous suggestions that consciousness is a macroscopic quantum effect possibly involving superconductivity, superfluidity, electromagnetic fields, Bose-Einstein condensation or some other physical mechanism. Perhaps the most specific model developed thus far is that of Penrose and Hameroff and it asserts that quantum information processing takes place in microtubules (MTs). It has been argued that MTs can process information similarly to a cellular automaton, and hence Hameroff and Penrose suggest that neuronal MTs may operate as a quantum computer.

In this paper, we investigate visual information transfer from a quantum information point of view. Theoretically we consider the conscious observer looking at a quantum system and propose that the state of this system is reported via superposed photons. We address the question whether the observer can receive the exact same state of this system quantum mechanically in his/her brain or this quantum state collapses before reaching the brain. Below we investigate the problem in detail.

2) Evolution of Information from the Eye to the Brain

We assume that a conscious observer directs his/her attention to a quantum system. For simplicity we consider this system to be a manifestation of the celebrated *Schrödinger's cat*. This system can exist in two states: Live$|L\rangle$, or Dead$|D\rangle$.

---

[*] *vahidsalari@graduate.uk.ac.ir*
[†] *Majid.rahnama@mail.uk.ac.ir*
[‡] *jtus@phys.ualberta.ca*

$$\psi_{sys} = \frac{1}{\sqrt{2}}(|L\rangle + |D\rangle) \qquad (2\text{-}1)$$

The state of this system is then reported via superposed photons. 4% of these photons are reflected from the cornea. 50% of remaining photons are dissipated through ocular media absorption. Other photons enter the 200-250 μm thick retina. There, photons interact with the photoreceptors in the rods and cons layer after 80% loss due to retinal transmission [11],[12]. In this case, we consider just a few remaining photons which are in a superposed quantum state. The key question here is whether this quantum state of photons can be reported to the brain.

When this state interacts with the last layer of retina, according to Thaheld, this superposed photon undergoes a wavefunction collapse. On the other hand, photons can be absorbed and then transformed into classical signals. Here, we use the symbols introduced by Tegmark [13] for the observer. The symbol $|\overset{..}{\_}\rangle$ denotes the state for which the information on photons is not received by the brain and thus the observer is amphoteric. The symbol $|\overset{..}{\smile}\rangle$ stands for the state in which the information received in the brain reports that the cat is alive (and the observer is happy). Finally, the symbol $|\overset{..}{\frown}\rangle$ corresponds to the state in which the information received in the brain indicates that the cat is dead (and the observer will be sad). It means that:

$$U|\overset{..}{\_}D\rangle = |\overset{..}{\frown}D\rangle \qquad (2\text{-}2\text{-}a)$$

$$U|\overset{..}{\_}L\rangle = |\overset{..}{\smile}L\rangle \qquad (2\text{-}2\text{-}b)$$

Where $U = \exp\left[-\frac{i}{\hbar}\int H_{photon-brain}\, dt\right]$.

Now, we consider another state in which the brain interacts with itself. Penrose and Hameroff have proposed a model of consciousness involving quantum computation with objective reduction in *microtubules* (or MTs) within the brain's neurons (see Figure 1) [14],[15],[16],[17]. MTs are cylindrical polymers comprised of the protein tubulin which organize numerous cellular activities including neuronal motor transport. According to Hameroff and Penrose, switching of tubulin conformational states is governed by quantum mechanical forces within each tubulin interior, and an essential feature of the Orch OR model is that tubulins may exist in quantum superpositions of two or more conformations. Therefore, these states could function as quantum bits, or "qubits" by interacting non-locally (through their entanglement) with other tubulin qubits so that MTs may act as quantum computers. When sufficiently many entangled tubulins are superposed for long enough to reach Penrose's OR threshold given by E=h/T, an objective reduction (OR) "conscious event" occurs as stated in the Orch-OR model.


Dendrite
Dendritic Spine/Synaptic Receptor
Nucleus
Membrane
Axon
Microtubule
Microtubule Associated Protein

Figure 1 **Representation of MTs inter a brain neuron. The Orch OR model suggests that the main information processing is implemented in these structures.**

If previous evolution is described by Penrose's self-collapse in the brain (i.e. Orch-OR), MTs in the neurons of the brain collectively evolve and then collapse (i.e. conscious event) to one of the happy or sad states. It mathematically means that:

$$U|\ddot{\_}\rangle = \frac{1}{\sqrt{2}}(|\ddot{\smile}\rangle + |\ddot{\frown}\rangle \qquad (2\text{-}3)$$

where $U = \exp[-\frac{i}{\hbar}\int H_{brain}\, dt]$.

If we compare this state (2-3) and the state which has the information about the photon (2-2), we can say that there's a great amount of correlation between the retina and the visual cortex, because their result should be identical. We know that in accordance with the Einstein-Podolsky-Rosen (EPR) pair, when two entities originate from a common source they can be entangled with each other. Retina has a similar layered structure as the gray-matter top layers of the cerebral cortex of the brain. In fact, retina is an extension of the central nervous system (the brain and spinal cord) that forms during embryonic development. One reason why scientists are interested in retinal processing is that retina is an accessible part of the brain that can be easily stimulated with light [18]. Thus, we can say that retina and visual cortex are entangled with each other. The other argument for this entanglement is that the image of a system is inverted on the retina but it is perceived in the brain directly. As we know, in two entangled entities when one has a property in some direction the other exhibits that property but in the opposite direction. Thus retina receives an inverted image, while it is received in the visual cortex upright. This property is special to entanglement.

The human body is made up of many organs, which themselves are made up of many millions of cells. How can such a system, with millions, or even billions, of parts function effectively and coherently? This is a no small feat as even small-size human societies often undergo periods of turbulence and trouble due to conflict and poor organization. Now some scientists think that quantum coherence in MTs is a major factor responsible for our bodies, and especially our brains, being so efficiency. Here, we intend to describe visual processing on the basis of quantum information theory.

3) Generation of Entangled Coherent States

Centrioles and cilia, which are microtubular structures, are involved in photoreceptor functions in single cell organisms and primitive visual systems. Cilia are also found in all retinal rod and cone cells. The dimensions of centrioles and cilia are comparable to the wavelengths of visible and infrared light (see Figure 2) [50]. Moreover, cytoskeletons are found mostly among the retina and the visual cortex in the cells of the optic nerve. Cytoskeletal structures of the centrioles can be expected to vibrate like a harmonic oscillator in its ground state. Vibrational dynamics of MT's has been the subject of a recent paper where typical frequency ranges have been discussed [19].

When a photon interacts with a centriole, its electric field can displace the potential of the harmonic oscillator and then releases it, thus generating coherent states [20]. It means that:

$$D(\alpha)|0\rangle = |\alpha\rangle \qquad (3\text{-}1)$$

Where $D(\alpha)$ is the displacement operator; $D(\alpha) = e^{\alpha a^{\dagger} - \alpha^{*} a}$, and $|0\rangle$ is the ground state of harmonic oscillator, and $|\alpha\rangle$ is the coherent state: $|\alpha\rangle = e^{-\frac{|\alpha|^2}{2}} \sum_{n=0}^{\infty} \frac{\alpha^n}{\sqrt{n!}} |n\rangle$.

Hameroff [21] and Penrose [22] have suggested that MTs inside cells permit long-range quantum coherence, enabling quantum information processing to take place at the sub-cellular level. They use this hypothesis to develop their theory of consciousness. Cells interconnected by gap junctions form networks which fire synchronously, behaving like one giant neuron [23], and possibly accounting for synchronized neural activity such as coherent 40 Hz waves [24]. Marshall [25] suggested that coherent quantum states known as Bose-Einstein condensation occurred among neural proteins [26], [27], [28]. Other issues, such as preconscious-to-conscious transitions were identified by Stapp [29] with the collapse of a quantum wave function in presynaptic axon terminals [7]. The other reason for coherence of these structures is that light is an electromagnetic wave and thus is vibrational, and according to Froehlich's theory [44],[45],[46] it can take these cytoskeletal structures (i.e. nonlinear structures composed of electric dipoles) into one mode of frequency and coherence.



Figure 2 Representation of one centriole, the dimensions of centrioles are comparable to wavelengths of visible and infrared light.

Centrioles are two cylinders composed of MTs which are perpendicular to each other and in accordance with the Hameroff theory of the origin of cancer [30], centrioles are entangled with each other. Because of this entanglement, when a coherent state $|\alpha\rangle$ is generated in one centriole, in the other it will generate state $|-\alpha\rangle$. Now, we can say that after interaction of photons with centrioles, they generate "entangled coherent states" in these structures in the retina, i.e.:

$$|\varphi\rangle_{12} = (A|\alpha\rangle_1|\alpha\rangle_2 - B|-\alpha\rangle_1|-\alpha\rangle_2\ ) \qquad (3\text{-}2)$$

where $|\varphi\rangle_{12}$ is an entangled coherent state in centrioles with two modes 1 and 2. QED-cavity model of MTs [31] describes that coherent modes of electromagnetic radiation can be sustained in the interior of the MTs. These modes are provided by the interaction of the electric dipole moments of the ordered-water molecules in the interior of MTs with quantized electromagnetic radiation [32],[33]. Jibu, et. al.[49], have proposed that the quantum dynamical system of water molecules and the quantized electromagnetic field confined inside the hollow MT core can manifest a specific collective dynamical effect called superradiance [34] by which the MT can transform any incoherent, thermal and disordered molecular, atomic or electromagnetic energy into coherent photons inside the MT. Furthermore, they have also shown [49] that such coherent photons created by superradiance penetrate perfectly along the internal hollow core of the MT as if the optical medium inside it were made "transparent" by the propagating photons themselves. This is referred to as the quantum phenomenon of self-induced transparency [35]. Superradiance and self-induced transparency in cytoskeletal MTs can lead to "optical" neural holography [36]. Neurons (and maybe also other cells) may contain microscopic coherent optical supercomputers with enormous capacity. Thus Jibu, et. al.[49], suggest that MTs can behave as optical waveguides which result in coherent photons. They estimate that this quantum coherence is capable of superposition of states among MT spatially distributed over hundreds of microns. These in turn are in superposition with other MTs hundreds of microns away in other directions and so on. With the above conclusions $|\varphi\rangle_{12}$ can produce those photons which produced itself, thus if the state $|\varphi\rangle_{12}$ can be restored in the brain, it will reproduce the photons which were absorbed in the retina.

Additional arguments in favor of the feasibility of production of photons in the brain can be found in the conclusions of the paper [37], which also asserts that there exists a neural activity-dependent ultra-weak photon (biophoton) emission in the brain. Thus there is the possibility to restore the initial state of the photon in the brain after absorption in the eye. This process can be implemented through teleportation mechanism between retina and the visual cortex as will be discussed in the following sections.

4) The Decoherence Problem

The important question about the quantum processing in the living systems is: how is it possible for MTs to process information quantum mechanically while the environment surrounding them is relatively hot, wet and noisy?

According to the Orch-OR model, microtubular structures in the neurons of the brain process information quantum mechanically and to avoid decoherence, like lasers maintain quantum coherence against thermal noise. Water within cells is itself not truly liquid, but has been shown to be, to a large extent, ordered [38]. Most of the ordered water in the cell in fact surrounds the cytoskeleton [39]. MTs and other cytoskeletal components are embedded in cytoplasm which exists in alternating phases of (1) “sol” (solution, liquid); and (2) “gel” (gelatinous, solid). Among the most primitive of biological activities, “sol-gel transformations” within neurons and other living cells are caused by assembly and disassembly of cytoskeletal actin (e.g. regulated by calcium ions through the protein calmodulin, in turn regulated by MTs). Sol-gel transformations are essential in basic cellular activities such as (“amoeboid”) movement, growth and synaptic formation and neurotransmitter vesicle release [40], [41]. Transitions can occur rapidly (e.g. 40 sol-gel cycles per second), and some actin gels can be quite solid, and withstand deformation without transmitted response [42]. Cyclical encasement of MTs by actin gels may thus be an ideal quantum isolation mechanism. In the gel phase of cytoplasm, the water ordering surfaces of a MT are within a few nanometers of actin surfaces which also order water. Thus bundles of MTs encased in actin gel may be effectively isolated extending over the radius of the bundle, on the order of hundreds of nanometers. There are many mechanisms which can protect these structures against decohering factors. In general, Quantum states of tubulin/MTs are protected from environmental decoherence by biological mechanisms which include phases of actin gelatin, plasma-like Debye layering, coherent pumping and topological quantum error correction [54]. Moreover, quantum spin transfer between quantum dots connected by benzene rings (the same structures found in aromatic hydrophobic amino acids) is more efficient at warm temperature than absolute zero[43]. It is conjectured that the “flexibility” of the resonant benzene electrons is advantageous to quantum processes by harnessing ambient thermal energy. MTs may possibly utilize nonspecific thermal energy for "laser-like" coherent pumping, for example in the GHz range by a mechanism of "pumped phonons" suggested by Froehlich [44,45,46].

5) What is the mechanism of Teleportation?

According to the definition of teleportation as stated in [47], in the process of quantum teleportation, one can construct an exact replica of the original unknown quantum state at a cost of destroying the original state. Therefore, to call a quantum state transfer operation- quantum teleportation, the process should not only generate output states with better qualities than what can be done classically but also obey the no-cloning theorem [48].The quantum state of a system can be transmitted from a location to a distant one using only classical information provided that a quantum channel exists between the sender and the receiver. Sharing entangled states between the two parties opens the necessary quantum channel. Research in quantum state transfer, especially the quantum teleportation, has emerged as one of the major research areas of theoretical and experimental quantum mechanics. Assume that Alice wants to send Bob an unknown quantum state but when she receives this state she does not know anything about that unless she affects it and collapses it to classical state, or in other hand she destroys that quantum state. She just can send classical signals to Bob through classical channel, but if there is a shared entangled channel between Alice and Bob, Bob can construct initial quantum state with the help of classical signal which is sent by Alice and quantum channel between them. This operation is implemented by operating special unitary operators. For more details see [47]. Here, we want to simulate visual information transfer with teleportation mechanism. We know that when photon penetrates the retina, it changes to action potentials or electrical signals and these classical signals are sent to the brain for interpretation. It means that *retina* (Alice) wants to send the *brain* (Bob) a *photon state* (unknown quantum state), but *retina* (Alice) absorbs it (collapses the quantum state) and changes it to *action potential* (classical state) and send it through *membranes of axons of the brain neurons* (classical channel). *Brain* (Bob) can reconstruct the initial *state of photon* (unknown quantum state) to process it to emerge consciousness. Our arguments for this simulation are below conclusions:

> *Orch OR* [14], [15]: There is quantum processing in the neurons of the brain (there is a quantum channel between retina and brain)
>
> *Tegmark* [13]: Displacement of ions through membranes of brain neurons is a classical phenomenon (action potentials are classical signals and membranes of neurons are classical channels).
>
> *Thaheld* [11],[12]: Superposed photons do collapse in the retina (the quantum state is collapsed by the sender [Alice]).
>
> We assert that they describe different aspects of the teleportation mechanism. We simulate visual consciousness with the teleportation mechanism as shown in Table 5-1.

Table 5- 1 Simulation of the transferring visual information from the eye to the brain to the Teleportation mechanism.

Human Brain	***Quantum Teleportation Mechanism***
Retina	Alice
Membrane of axons in neurons	Classical channel
Cytoskeletal structures	Entangled channel (quantum channel)
Visual cortex	Bob
Action potentials	Classical signals

Now we want to investigate this teleportation mechanism via teleporting of entangled coherent states through visual pathways in more details. We will show how photon states are constructed in the visual cortex.

6) Teleportation of Entangled Coherent States through Visual Pathways

Super radiance and self induced transparency [49] besides Froehlich oscillations can cause the coupling of MT dynamics over wide areas and take them into a superposition and a coherent state. While in superposition, tubulins communicate with entangled tubulins in the same manner, and in MTs in neighboring neurons, and through macroscopic regions of the brain via tunneling through gap junctions and possibly tunneling nanotubes [50]. As we have already said, retina and the visual cortex are entangled with each other. Thus there is a quantum channel between retina and the visual cortex which is composed of microtubular structures. MTs interact with membrane structures mechanically by linking proteins, chemically by ions and second messenger signals, and electrically by voltage fields. The transduction of light into electrical signals takes place in the photoreceptors. Except for the ganglion cells, none of the retinal cells display action potentials [51].



Figure 3 The LGN is a laminated structure, having 6 layers. Contralateral fibers and ipsilateral fibers couple in the LGN. The ipsilateral fibers of the optic nerve terminate in laminae 2,3 and 5 of LGN, while the contralateral fibers terminate in laminae 1, 4 and 6.[52]

Axons leaving the temporal half of the retina traverse the optic nerve to the optic chiasm, where they join the optic tract and project to ipsilateral structures. Axons leaving the nasal half of the retina cross the midline at the chiasm and terminate in contralateral structures. This arrangement means that all the axons in the optic tract carry information about the contralateral visual field. Axons of the optic tract terminate in three areas of the central nervous system, the lateral geniculate nucleus (i.e. LGN), the superior colliculus and the pretectal area. The trajectory through the LGN is the largest most direct and clinically most important pathway by which visual information reaches the cerebral cortex. About 80% of the optic tract axons synapse in the LGN. The LGN is a laminated structure, having 6 layers. Contralateral fibers and ipsilateral fibers couple in the LGN. The ipsilateral fibers of the optic nerve terminate in laminae 2,3 and 5 of LGN, while the contralateral fibers terminate in laminae 1, 4 and 6 of LGN (see Figure 3). There are about 10^6 neurons in each LGN, all of which project to the ipsilateral occipital cortex (area 17) as the optic radiations. The portion of the cerebral cortex that receives LGN axons is called the striate cortex and is usually labeled V1 to designate it as the primary visual cortical area (Figure 3). Virtually all information in the visual system is recognized as being processed by V1 first, and then passed out to higher order systems [53]. The upper visual cortex receives signals from the lower visual field and similarly, lower visual cortex process information from the upper visual field. The right visual cortex processes the left field of view and vice versa (see figure 4).

Now, we investigate the information transfer through visual pathways. The important model among quantum models about the processing in the human brain is the Orch-OR model which is based on the structure of the cytoskeleton. As already said this model asserts that the main processing in the neurons of the brain is performed in the MTs and the nature of the processing is mainly quantum mechanical. The processing unit in this model is *tubulin* which can be in a superposed state. Tubulins act like qubits in quantum computers. *Max Tegmark* believes that there is no quantum processing in the human brain. He has calculated decoherence times for every superposition state which can be possible in the neurons of the brain [13]. In his opinion, superposition states include ions such as Na^+ which are “in” and “out” of the membrane of axon. On the other hand, Na^+ ions are in the superposition of “in” and “out” with a separation distance comparable to the membrane thickness. He has considered three factors which can destroy this superposition state in neurons. *Collisions with the neighboring ions, Collisions with the water molecules* and *Interaction with distant ions* are the factors which Tegmark investigated for decoherence. He has estimated 10^{-19} s and 10^{-20} s for decoherence times. It is clear that above times are very small for the brain processes such as seeing, thinking, speaking and the other cognitive processes. Typically, dynamical timescales for neuron firing and cognitive processes are in the range of 10^{-4} to 1 seconds, whereas decoherence timescales are many orders of magnitude shorter. Thus, action potentials should be regarded as classical signals or the displacement of ions through the membrane of axons should be investigated classically. It is remarkable that Tegmark has also calculated decoherence time for MTs, but he has used wrong assumptions about these structures (for more details see [54]) and we just accept his calculations about action potentials. Thaheld [11], [12] believes that the wave function of any superposed photon state or states is always objectively changed within the complex architecture of the eye, and any incident photons have to run a very daunting gauntlet before they are even converted or transduced to retinal ganglion cell spike trains (To learn more about Thaheld arguments, the reader is referred to refs. [55,56,57]). According to Thaheld, the quantum state of photons does collapse in the retina and it does not reach the brain.

Is Thaheld right? Is not there any mechanism to rebuild the quantum state of photons in the brain? Here we accept that the states of photons collapse in the retina but we believe that they can be restored in the visual cortex via the teleportation mechanism.

Now, the question is how can it be possible to restore the exact state of photons in the brain while its state is collapsed in the retina. The other question which one may ask is: if this state is reported through action potentials how is this information reported to the brain and how can it interpret action potentials to obtain the exact state of the photons? Our solution to the above problems involves the teleportation of entangled coherent states through visual pathways. The state of the photon is teleported from the eye to the brain. On the other hand, the state of the photon is transferred via some “cut-and-paste” mechanism from the eye to the brain. But how is it possible?



Figure 4 Visual pathways from the eye to the brain. See crossing of pathways.

We concluded before that retina and the visual cortex are entangled. Also we explained how the entangled coherent state is generated in the retina. Now, we want to formulate the process of information transfer from the retina to V1. The state (3-2) with two modes 1 and 2 should be teleported to V1. After the interaction of light with retina, modes 3, 4 and 5, 6 are generated through microtubular structures between retina and V1, and thus they produce entangled coherent channels between retina and V1. It means that the channels are:

$$|\psi\rangle_{35} = \frac{1}{\sqrt{N_\alpha}}\left(|\alpha\rangle_3|\alpha\rangle_5 - |-\alpha\rangle_3|-\alpha\rangle_5\right) \qquad (6\text{-}1)$$

$$|\phi\rangle_{46} = \frac{1}{\sqrt{N_\alpha}}\left(|\alpha\rangle_4|\alpha\rangle_6 - |-\alpha\rangle_4|-\alpha\rangle_6\right) \qquad (6\text{-}2)$$

Where N_α is the number of tubulins in each channel. Each mode is reported via a special fiber through visual pathways. All of the neurons which are collected in the LGN are divided into two major pathways: ipsilateral fibers and contralateral fibers. Information transfer in the contralateral fibers takes longer than information transfer in ipsilateral fibers because contralateral fibers have crossing relative to ipsilateral fibers and then they have longer lengths than ipsilateral fibers. On the other hand, contralateral fibers have a retarded phase relative to ipsilateral fibers. Now we want to answer the following questions. What is this phase difference? What is the role of this crossing? And how does crossing restore the initial state in the retina?

7) The Role of Phase Shift to Restore Information in LGN

When the information is collapsed in the retina, action potentials are produced. The shape of action potentials is the same for each neuron, but the main problem is which neurons are fired, or in other words which neurons carry action potentials and information. Consider two fibers selected from ipsilateral fibers and two fibers selected from contralateral fibers. The two ipsilateral fibers are called 1 and 2, and the two contralateral fibers are called 3 and 4 while the two fibers from the LGN to V1 are called 5 and 6 which are selected from the group of magnocellular and parvocellular fibers. Now, we start from the retina. The state of centrioles and channels is:

$$|\psi'\rangle = |\varphi\rangle_{12} \otimes |\psi\rangle_{35} \otimes |\phi\rangle_{46}$$

$$= \frac{1}{N_{\propto}'}(A|\alpha\rangle_1|\alpha\rangle_2|\alpha\rangle_3|\alpha\rangle_4|\alpha\rangle_5|\alpha\rangle_6$$

$$-A|\alpha\rangle_1|\alpha\rangle_2|\alpha\rangle_3|-\alpha\rangle_4|\alpha\rangle_5|-\alpha\rangle_6$$

$$-A|\alpha\rangle_1|\alpha\rangle_2|-\alpha\rangle_3|\alpha\rangle_4|-\alpha\rangle_5|\alpha\rangle_6$$

$$+A|\alpha\rangle_1|\alpha\rangle_2|-\alpha\rangle_3|-\alpha\rangle_4|-\alpha\rangle_5|-\alpha\rangle_6$$

$$-B|-\alpha\rangle_1|-\alpha\rangle_2|\alpha\rangle_3|\alpha\rangle_4|\alpha\rangle_5|\alpha\rangle_6$$

$$+B|-\alpha\rangle_1|-\alpha\rangle_2|\alpha\rangle_3|-\alpha\rangle_4|\alpha\rangle_5|-\alpha\rangle_6$$

$$+B|-\alpha\rangle_1|-\alpha\rangle_2|-\alpha\rangle_3|\alpha\rangle_4|-\alpha\rangle_5|\alpha\rangle_6$$

$$-B|-\alpha\rangle_1|-\alpha\rangle_2|-\alpha\rangle_3|-\alpha\rangle_4|-\alpha\rangle_5|-\alpha\rangle_6) \qquad (7\text{-}1)$$

All of the above states are collected in the LGN. But here the role of action potentials is very important. They determine which fibers are fired. If fibers 1 and 2 carry action potentials, then it shows that information passes through ipsilateral fibers. Thus to select information from the LGN to send it via fibers 5 and 6 to V1 there is no need for phase difference (or to apply the phase shift operator on the states) and thus the state of (3-2) can be transferred like its first state through fibers 5 and 6. In the formulation (7-1) we see that if fibers x and y are fired, the expression with $|\alpha\rangle_x|\alpha\rangle_y$ should be selected from the terms with coefficients +A besides the expression $|-\alpha\rangle_x|-\alpha\rangle_y$ from the terms with coefficients $-B$. Hence,

$$1,2\,firing \quad \xrightarrow{yields} \quad |\phi'\rangle_{56} = A|\alpha\rangle_5|\alpha\rangle_6 - B|-\alpha\rangle_5|-\alpha\rangle_6 \qquad (7\text{-}2)$$

In another state, if fibers 1 and 4 are fired it means that one fiber is selected from ipsilateral fibers and the other is from contralateral fibers, thus they have phase difference with respect to each other. Hence,

$$1,4\,firing \quad \xrightarrow{yields} \quad |\phi'\rangle_{56} = A|\alpha\rangle_5|-\alpha\rangle_6 - B|-\alpha\rangle_5|\alpha\rangle_6 \qquad (7\text{-}3)$$

To restore initial information, the operator

$$R(\varphi) = e^{-i\pi a^{\dagger}{}_{6}a_{6}}$$

should operate on the state in LGN in which fibers 1 and 4 have conveyed action potentials. This operator changes the ket $|\alpha\rangle_6$ to $|-\alpha\rangle_6$ and vice versa. It means that fiber 4 has a π radian phase difference with respect to fiber 1, and this phase difference can restore the exact state of the photon. If fibers 2 and 3 are fired, this yields:

$$2,3\ firing \quad \xrightarrow{yields} \quad |\phi'\rangle_{56} = A|-\alpha\rangle_5|\alpha\rangle_6 - B|\alpha\rangle_5|-\alpha\rangle_6 \qquad (7\text{-}4)$$

In this case the operator

$$R(\varphi) = e^{-i\pi a^{\dagger}{}_{5}a_{5}}$$

should be involved. For the case of 3 and 4 firing, this yields,

$$3,4\ firing \quad \xrightarrow{yields} \quad |\phi'\rangle_{56} = A|-\alpha\rangle_5|-\alpha\rangle_6 - B|\alpha\rangle_5|\alpha\rangle_6 \qquad (7\text{-}5)$$

in which case the operator

$$R(\varphi) = e^{-i\pi(a^{\dagger}{}_{5}a_{5}+a^{\dagger}{}_{6}a_{6})}$$

should be involved. In this case we see that the main path is that of ipsilateral fibers which are direct to each eye and fibers 3 and 4 both have a π radian phase difference with it. We also know that there are two LGNs and the left and right V1. Now, another question emerges. How do these two left and right parts in V1 can instantaneously receive information? To answer this question, we can say that the synaptic β-neurexin/neuroligin-1 adhesive protein complex is claimed to be a device mediating entanglement between the cytoskeletons of the cortical neurons. Thus the macroscopic coherent quantum state can extend through large brain cortical areas [58].

We see that crossing or rotation of neurons in the visual pathways has an important role in restoring information in the brain. Maybe rotations or crossings of neurons throughout the body are there for this very reason.

8) Discussion

In general, we can briefly summarize our approach by listing the following properties:

1- It can combine the Orch-OR model with Tegmark's approaches and the Thaheld conclusion in a compact physical model which is called Teleportation.

2- It investigates visual pathways from atomic scales to macroscopic scales. This approach includes classical descriptions as well as new answers to open questions.

3- It explains why the shape of action potentials stays the same. Classical models state that "sensations" are action potentials that reach the brain via sensory neurons, and "perception" is the awareness and interpretation of the sensation. It is reasonable to assume that the constant shape of action potentials cannot result in different profiles of information. Thus the shape of information should be due to neurons. In this approach MTs are the representatives of information carriers. In our approach action potentials just determine which neurons fire and which do not.

4- It describes why neurons cross at some point. This crossing causes a phase shift relative to a special pathway. In teleportation of entangled coherent states the phase shift operators can rebuild initial information.

5- It explains that how the inverted image on the retina is perceived in the brain as upright.
6- It can describe how different information can be simultaneously perceived as a binding nature of conscious experience. This can be done via quantum parallel processing.
7- It explains how the brain of the observer can receive quantum information from the environment. We can see that there still exists this possibility that the mind can play the main role in the measurement problem, and this is in accord with what London, Bauer, von Neumann and Wigner (initially) asserted.

9) Conclusions

In this paper we have theoretically demonstrated the plausibility of a quantum teleportation mechanism between the eye and the brain which can describe different aspects of visual processing through visual pathways. Our model covers both quantum and classical aspects of neuroscience. This mechanism can combine some features of the Orch-OR model with Tegmark's conclusions and Thaheld's belief in one general model.

Acknowledgement

V. Salari and M. Rahnama thank Dr. Vahid Sheybani, the head of Neuroscience Research Center, for his good instructions and helps.

References:

---

[1] Schrödinger. E, What is life? Cambridge University Press, London, 1944.
[2] Davies. P, Does quantum mechanics play a non-trivial role in life?, Biosystems, 78**,** 69, 2004.
[3] Matsuno. K, *Quantum and biological computation*, Biosystems, 35, 209-212, 1995.
[4] Penrose. R, *Shadows of the mind*, Oxford University Press, 1994.
[5] Matsuno. K and Paton. R. C, *Is there biology of quantum information?,* Biosystems, **55**, 39-46 2000.
[6] Vedral. V, *Entanglement hits the big time*, Nature, **425**, 28-9, 2003.
[7] Beck. F and Eccles. J.C, *Quantum aspects of brain activity and the role of consciousness*, Proc. Nat. Acad. Sci. USA, **89**, 11357-11362, 1992.
[8] Penrose. R, The Emperor's New Mind (Oxford University Press, Oxford, 1989); S.R., *Quantum coherence in MTs: a neural basis for emergent consciousness?*, Journal of Consciousness Studies, **1**, 98–118, 1994.
[9] Davies. P.C.W.s, *The Origin of Life* (Penguin, London, 2003); The Fifth Miracle (Simon & Schuster, New York, 1998)
[10] Tarlaci. S., NeuroQuantology 2003; 3: 292-294

[11] Thaheld. F. 2005 *Preprint* quant-ph/0509042
[12] Thaheld. F. 2006 *Preprint* quant-ph/060418

[13] Tegmark. M., Phys. Rev. E61, 4194-4206 (2000). It's preprint exists in [arXiv:quant-ph/9907009 v2].

[14] Penrose. R. and Hameroff. S.R., J. Conscious. Stud. **2**, 98(1995).
[15] Hameroff. S.R. and Penrose. R., J. Conscious. Stud. **3**, 36(1996).
[16] Hameroff. S.R., Philos. Trans. R. Soc. London Ser. A **356**, 1869(1998).
[17] Hameroff. S.R. ,NeuroQuantology , March 2007 , Vol 5 , Issue 1 , Page 1-8

[18] Dowling. J. E., *The Retina: An Approachable Part of the Brain*. Belknap Press of Hrward University Press, Cambridge. (1987).

[19] Portet. S., Tuszynski. J. A., Hogue. C. M. and Dixon. J. M., *Elastic vibrations in seamless microtubules*, European Biophysics Journal, 34, Number7, October 2005, 912-920.

[20] Gerry, C., Knight, P. "*Introductory Quantum Optics*", Cmbridge University Press,(2005).

[21] Hameroff, S.R., 1994. *Quantum coherence in MTs: a neural basis for emergent consciousness?* J. Conscious. Stud. 1, 98–118.

[22] Penrose, R., 1989. *The Emperor's New Mind*. Oxford UniversityPress, Oxford.

[23] Kandel, E. R., Siegelbaum, S. A. & Schwartz, J. H. 1991 *Synaptic transmission.* In Principles of neural science (ed. E. R. Kandel, J. H. Schwartz & T. M. Jessell), 3rd edn, pp. 121-134. New York: Elsevier. Karplus, M. & McCammon

[24] Jibu, M. *On a heuristic model of the coherent mechanism of the global reaction process of a group of cells. Bussei Kenkyuu (Mater. Phys. Res.)* **53**, 431-436. (In Japanese.) (1990)

[25] Marshall, I. N. *Consciousness and Bose-Einstein condensates*. New Ideas Psychol. **7**, 73, 83. (1989)

[26] Penrose, R. *Newton, quantum theory and reality*. In 300 years of gravity (ed. S. W. Hawking& W. Israel). Cambridge University Press. (1987).

[27] Bohm, D. & Hiley, B. J. 1993 *The undivided universe*. New York: Routledge.

[28] Jibu, M. & Yasue, K. 1995 *Quantum brain dynamics: an introduction*. Amsterdam: John Benjamins.

[29] Stapp, H. P. 1993 *Mind, matter and quantum mechanics*. Berlin: Springer.

[30] Hameroff. S. R., BioSystems **77** 119-136 . (2004).

[31] Mavromatos, N. E., Mershin, A. and Nanopoulos, D. V. (2002), "*QED-Cavity model of MTs implies dissipationless energy transfer and biological quantum teleportation*," http://arxiv.org/abs/quant-ph/0204021

[32] Del Giudice. E., Doglia. S., Milani. M. and Vitiello. G., Nucl. Phys. B275 (FS 17) (1986), 185.

[33] Del Giudice. E., Preparata. G. and Vitiello. G., Phys. Rev. Lett. 61 (1988), 1085.

[34] Dicke. R. H., Phys. Rev. 93 (1954) 99.

[35] McCall. S. L. and Hahn. E. L., Phys. Rev. Lett. 18 (1967) 908

[36] Hameroff. S. R., *Ultimate Computing: Biomolecular Consciousness and Nanotechnology* (North-Holland, Amsterdam, 1987), and Journal of Consciousness Studies, 1 (1994) 91.

[37] Bokkon. I., *Phosphene phenomenon: A new concept*, BioSystems 92(2008) 168-174.

[38] Clegg. J. S. Amer. J. Physiol. **246**, R133 (1984).

[39] Clegg. J. Coll. Phenomena **3**, 289 (1981).

[40] Miyamoto, S. "*Changes in mobility of synaptic vesicles with assembly and disassembly of actin network.*" *Biochim. Biophys. Acta* **1244**, 85-91. (1995).

[41] Muallem, S., Kwiatkowska, K., Xu, X. & Yin, H. L. *Actin filament disassembly is a sufficient final trigger for exocytosis in nonexcitable cells*. *J. Cell Biol.* **128**, 589-598. (1995).

[42] Wachsstock, D. H., Schwarz, W. H. & Pollard, T. D. *Cross-linker dynamics determine the mechanical properties of actin gels*. *Biophys. Jl* **66**, 801-809. (1994).

[43] Ouyang. M., Awschalom. D. D., " *coherent spin transfer between moleculary bridged quantum dots*". Science, 301, 1074-1078, (2003).

[44] Fröhlich. H., Int, J. Quantum Chem. **2**, 641 (1968).

[45] Fröhlich. H., Nature (London) **228**, 1093 (1970).

[46] Fröhlich. H., Proc. Natl. Acad. Sci. U.S.A. **72**, 4211 (1975).

[47] Bennett. C. H., Brassard. G., Crepeau. C., Jozsa. R., Peses. A., and Wootters. W. K., Phys. Rev. Lett. **70**, 1895 (1993).

[48] Wootters. W. K. and Zurek. W. H., Nature (London) **299**, 802 (1982); Dieks .D., Phys. Lett. A **92**, 271 (1982).

[49] Jibu, M., Hagan, S., Hameroff, S.R., Pribram, K.H., Yasue, K. (1994). "*Quantum optical coherenc in cytoskeletal MTs: implications for brain function*", Biosystems 32, 95-209.

[50] Hameroff. S., Tuszynski. J., “*Quantum states in proteins and protein assemblies: The essence of life?*”, Proceedings of SPIE Conference on Fluctuationa and Noise, Canary Islands, June 2004

[51] D. D. Georgiev, arXiv: quant-ph/ 0208053

[52] Web address: *http://thebrain.mcgill.ca/.../i_09_cl_dev.html*

[53] Zeki, S. “ *The visual image in mind and brain*”, Scientific American, 267:42-50 (1993).

[54] Hagan. S., Hameroff. S. R., and Tuszynski. J. A., *Quantum computation in brain MTs: Decoherence and biological feasibility.* Physical Review E, Volume **65**, 061901. (2002).

[55] Thaheld. F. H., *A method to explore the possibility of nonlocal correlations between brain electrical activities of two spatially separated animal subjects.* BioSystems **73**, 205-216.(2004).

[56] Thaheld. F. H., *Can we determine if the linear nature of quantum mechanics is violated by the perceptual process?* BioSystems **71**, 305-309.(2003).

[57] Thaheld. F. H., Comment on *Quantum superpositions and definite perceptions: envisaging new feasible experimental tests.* Phys. Lett. A **273**,232-234.(2000).

[58] Georgiev. D. D., Glazebrook. J. F., Informatica **30,** 221–232 (2006).

DTIC Copy

AFRL-PR-ED-TR-2003-0034 AFRL-PR-ED-TR-2003-0034

Teleportation Physics Study

Eric W. Davis
Warp Drive Metrics
4849 San Rafael Ave.
Las Vegas, NV 89120

August 2004

Special Report

APPROVED FOR PUBLIC RELEASE; DISTRIBUTION UNLIMITED.

AIR FORCE RESEARCH LABORATORY
AIR FORCE MATERIEL COMMAND
EDWARDS AIR FORCE BASE CA 93524-7048

REPORT DOCUMENTATION PAGE

Form Approved
OMB No. 0704-0188

Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing this collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports (0704-0188), 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number. **PLEASE DO NOT RETURN YOUR FORM TO THE ABOVE ADDRESS.**

1. REPORT DATE *(DD-MM-YYYY)* 25-11-2003	**2. REPORT TYPE** Special	**3. DATES COVERED** *(From - To)* 30 Jan 2001 – 28 Jul 2003

4. TITLE AND SUBTITLE

Teleportation Physics Study

5a. CONTRACT NUMBER
F04611-99-C-0025

5b. GRANT NUMBER

5c. PROGRAM ELEMENT NUMBER
62500F

6. AUTHOR(S)

Eric W. Davis

5d. PROJECT NUMBER
4847

5e. TASK NUMBER
0159

5f. WORK UNIT NUMBER
549907

7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES)

Warp Drive Metrics
4849 San Rafael Ave.
Las Vegas, NV 89120

8. PERFORMING ORGANIZATION REPORT NO.

9. SPONSORING / MONITORING AGENCY NAME(S) AND ADDRESS(ES)

Air Force Research Laboratory (AFMC)
AFRL/PRSP
10 E. Saturn Blvd.
Edwards AFB CA 93524-7680

10. SPONSOR/MONITOR'S ACRONYM(S)

11. SPONSOR/MONITOR'S REPORT NUMBER(S)
AFRL-PR-ED-TR-2003-0034

12. DISTRIBUTION / AVAILABILITY STATEMENT

Approved for public release; distribution unlimited.

13. SUPPLEMENTARY NOTES

14. ABSTRACT

This study was tasked with the purpose of collecting information describing the teleportation of material objects, providing a description of teleportation as it occurs in physics, its theoretical and experimental status, and a projection of potential applications. The study also consisted of a search for teleportation phenomena occurring naturally or under laboratory conditions that can be assembled into a model describing the conditions required to accomplish the transfer of objects. This included a review and documentation of quantum teleportation, its theoretical basis, technological development, and its potential applications. The characteristics of teleportation were defined and physical theories were evaluated in terms of their ability to completely describe the phenomena. Contemporary physics, as well as theories that presently challenge the current physics paradigm were investigated. The author identified and proposed two unique physics models for teleportation that are based on the manipulation of either the general relativistic spacetime metric or the spacetime vacuum electromagnetic (zero-point fluctuations) parameters. Naturally occurring anomalous teleportation phenomena that were previously studied by the United States and foreign governments were also documented in the study and are reviewed in the report. The author proposes an additional model for teleportation that is based on a combination of the experimental results from the previous government studies and advanced physics concepts. Numerous recommendations outlining proposals for further theoretical and experimental studies are given in the report. The report also includes an extensive teleportation bibliography.

15. SUBJECT TERMS
teleportation; physics, quantum teleportation; teleportation phenomena; anomalous teleportation; teleportation theories; teleportation experiments; teleportation bibliography

16. SECURITY CLASSIFICATION OF:			**17. LIMITATION OF ABSTRACT**	**18. NUMBER OF PAGES**	**19a. NAME OF RESPONSIBLE PERSON** Franklin B. Mead, Jr.
a. REPORT **Unclassified**	**b. ABSTRACT** **Unclassified**	**c. THIS PAGE** **Unclassified**	A	88	**19b. TELEPHONE NO** *(include area code)* (661) 275-5929

Standard Form 298
(Rev. 8-98)
Prescribed by ANSI Std. 239.18

NOTICE

USING GOVERNMENT DRAWINGS, SPECIFICATIONS, OR OTHER DATA INCLUDED IN THIS DOCUMENT FOR ANY PURPOSE OTHER THAN GOVERNMENT PROCUREMENT DOES NOT IN ANY WAY OBLIGATE THE US GOVERNMENT. THE FACT THAT THE GOVERNMENT FORMULATED OR SUPPLIED THE DRAWINGS, SPECIFICATIONS, OR OTHER DATA DOES NOT LICENSE THE HOLDER OR ANY OTHER PERSON OR CORPORATION; OR CONVEY ANY RIGHTS OR PERMISSION TO MANUFACTURE, USE, OR SELL ANY PATENTED INVENTION THAT MAY RELATE TO THEM.

FOREWORD

This Special Technical Report presents the results of a subcontracted study performed by Warp Drive Metrics, Las Vegas, NV, under Contract No. F04611-99-C-0025, for the Air Force Research Laboratory (AFRL)/Space and Missile Propulsion Division, Propellant Branch (PRSP), Edwards AFB, CA. The Project Manager for AFRL/PRSP was Dr. Franklin B. Mead, Jr.

This report has been reviewed and is approved for release and distribution in accordance with the distribution statement on the cover and on the SF Form 298. This report is published in the interest of scientific and technical information exchange and does not constitute approval or disapproval of its ideas or findings.

//Signed//

FRANKLIN B. MEAD, JR.
Project Manager

//Signed//

RONALD E. CHANNELL
Chief, Propellants Branch

//Signed//

PHILIP A. KESSEL
Technical Advisor, Space and Missile
Propulsion Division

//Signed//

RANNEY G. ADAMS III
Public Affairs Director

AFRL-ERS-PAS-04-155

This Page Intentionally Left Blank

Table of Contents

Section **Page**

1.0 INTRODUCTION……1
  1.1 Introduction……1
  1.2 The Definitions of Teleportation……1
2.0 vm -TELEPORTATION……3
  2.1 Engineering the Spacetime Metric……3
    2.1.1 Wormhole Thin Shell Formalism……3
    2.1.2 "Exotic" Matter-Energy Requirements……11
  2.2 Engineering the Vacuum……11
    2.2.1 The Polarizable-Vacuum Representation of General Relativity……20
  2.3 Conclusion and Recommendations……26
3.0 q-TELEPORTATION……30
  3.1 Teleportation Scenario……30
  3.2 Quantum Teleportation……32
    3.2.1 Description of the q-Teleportation Process……34
    3.2.2 Decoherence Fundamentally Limits q-Teleportation……38
    3.2.3 Recent Developments in Entanglement and q-Teleportation Physics……38
  3.3 Conclusion and Recommendations……46
4.0 e-TELEPORTATION……50
  4.1 Extra Space Dimensions and Parallel Universes/Spaces……50
  4.2 Vacuum Hole Teleportation……52
  4.3 Conclusion and Recommendations……53
5.0 p-TELEPORTATION……55
  5.1 PK Phenomenon……55
    5.1.1 Hypothesis Based on Mathematical Geometry……60
  5.2 Conclusion and Recommendations……61
6.0 REFERENCES……63
APPENDIX A – A Few Words About Negative Energy……73
  A.1 A General Relativistic Definition of Negative or Exotic Energy……73
  A.2 Squeezed Quantum States and Negative Energy……73
APPENDIX B – THεμ Methodology……75

List of Figures

Figure **Page**

Figure 1. Diagram of a Simultaneous View of Two Remote Compact Regions (Ω_1 and Ω_2) of Minkowski Space Used to Create the Wormhole Throat $\partial\Omega$, Where Time is Suppressed in This Representation……………..…………………….……………………………………5

Figure 2. The Same Diagram as in Figure 1 Except as Viewed by an Observer Sitting in Region Ω_1 Who Looks Through the Wormhole Throat $\partial\Omega$ and Sees Remote Region Ω_2 (Dotted Area Inside the Circle) on the Other Side……………………………………………………. 6

Figure 3. A Thin Shell of (Localized) Matter-Energy, or Rather the Two-Dimensional Spacelike Hypersurface $\partial\Omega$ (via (2.3)), Possessing the Two Principal Radii of Curvature ρ_1 and ρ_2……..8

Figure 4. A Schematic of Vacuum Quantum Field Fluctuations (a.k.a. Vacuum Zero Point Field Fluctuations) Involved in the "Light-by-Light" Scattering Process That Affects the Speed of Light………………………………………………………………………………………13

Figure 5. A Schematic of the Casimir Effect Cavity/Waveguide……………………………………...15

Figure 6. Classical Facsimile Transmission (Modified IBM Press Image)………………………………35

Figure 7. Quantum Teleportation (Modified IBM Press Image)…………………………………………36

Figure 8. Quantum Teleportation (From www.aip.org)..43

Approved for public release; distribution unlimited.

List of Tables

Table **Page**
Table 1. Metric Effects in the PV-GR Model When K > 1 (Compared With Reference Frames at Asymptotic Infinity Where K = 1)…………………………………………………………...…21
Table 2. Metric Effects in the PV-GR Model When K < 1 (Compared With Reference Frames at Asymptotic Infinity Where K = 1)……………………………………………………………...22
Table 3. Substantial Gravitational Squeezing Occurs When $\lambda \geq 8\pi r_s$ (For Electromagnetic ZPF)............28

Approved for public release; distribution unlimited.

Glossary

AEC	Average Energy Condition
AFRL	Air Force Research Laboratory
AU	Astronomical Unit
BBO	Beta (β)-Barium Borate
CGS	Centimeter-Gram-Second
CIA	Central Intelligence Agency
DARPA	Defense Advanced Research Projects Agency
DEC	Dominant Energy Condition
DIA	Defense Intelligence Agency
DNA	Deoxyribo Nucleic Acid
DoD	Department of Defense
EPR	Einstein, Podolsky and Rosen
ESP	Extrasensory Perception
eV	Electron Volt
FRW	Friedmann-Robertson-Walker
FTL	Faster-Than-Light
IBM	International Business Machines
INSCOM	Intelligence and Security Command
IR	Infrared
MeV	Mega-Electron Volt
MKS	Meter-Kilogram-Second
NEC	Null Energy Condition
NLP	Neuro-Linguistic Programming
NMR	Nuclear Magnetic Resonance
NSA	National Security Agency
PK	Psychokinesis
PPN	Parameterized Post-Newtonian
PRC	Peoples Republic of China
PV-GR	Polarizable-Vacuum Representation of General Relativity
QED	Quantum Electrodynamics
QISP	Quantum Information Science Program
R&D	Research and Development
SAIC	Science Applications International Corporation
SEC	Strong Energy Condition
SRI	Stanford Research Institute
USSR	Union of Soviet Socialist Republics
UV	Ultraviolet
WEC	Weak Energy Condition
ZPE	Zero-Point Energy
ZPF	Zero-Point Fluctuations

Acknowledgements

This study would not have been possible without the very generous support of Dr. Frank Mead, Senior Scientist at the Advanced Concepts Office of the U.S. Air Force Research Laboratory (AFRL) Propulsion Directorate at Edwards AFB, CA. Dr. Mead's collegial collaboration, ready assistance, and constant encouragement were invaluable to me. Dr. Mead's professionalism and excellent rapport with "out-of-the-box" thinkers excites and motivates serious exploration into advanced concepts that push the envelope of knowledge and discovery. The author owes a very large debt of gratitude and appreciation to both Dr. David Campbell, Program Manager, ERC, Inc. at AFRL, Edwards AFB, CA, and the ERC, Inc. staff, for supporting the project contract and for making all the paperwork fuss totally painless. Dr. Campbell and his staff provided timely assistance when the author needed it, which helped make this contract project run smoothly.

There are two colleagues who provided important contributions to this study that I wish to acknowledge. First, I would like to express my sincere thanks and deepest appreciation to my first longtime mentor and role model, the late Dr. Robert L. Forward. Bob Forward was the first to influence my interests in interstellar flight and advanced breakthrough physics concepts (i.e., "Future Magic") when I first met him at an AIAA Joint Propulsion Conference in Las Vegas while I was in high school (ca. 1978). The direction I took in life from that point forward followed the trail of exploration and discovery that was blazed by Bob. I will miss him, but I will never forget him. Second, I would like to express my sincere thanks and appreciation to my longtime friend, colleague and present mentor, Dr. Hal Puthoff, Institute for Advanced Studies-Austin, for our many discussions on applying his Polarizable Vacuum-General Relativity model to a quasi-classical teleportation concept. Hal taught me to expand my mind, and he encourages me to think outside the box. He also gave me a great deal of valuable insight and personal knowledge about the Remote Viewing Program. Last, I would like to offer my debt of gratitude and thanks to my business manager (and spouse), Lindsay K. Davis, for all the hard work she does to make the business end of Warp Drive Metrics run smoothly.

Eric W. Davis, Ph.D., FBIS
Warp Drive Metrics
Las Vegas, NV

Approved for public release; distribution unlimited.

Preface

The Teleportation Physics Study is divided into four phases. Phase I is a review and documentation of quantum teleportation, its theoretical basis, technological development, and its potential application. Phase II developed a textbook description of teleportation as it occurs in classical physics, explored its theoretical and experimental status, and projected its potential applications. Phase III consisted of a search for teleportation phenomena occurring naturally or under laboratory conditions that can be assembled into a model describing the conditions required to accomplish the disembodied conveyance of objects. The characteristics of teleportation were defined, and physical theories were evaluated in terms of their ability to completely describe the phenomenon. Presently accepted physics theories, as well as theories that challenge the current physics paradigm were investigated for completeness. The theories that provide the best chance of explaining teleportation were selected, and experiments with a high chance of accomplishing teleportation were identified. Phase IV is the final report.

The report contains five chapters. Chapter 1 is an overview of the textbook descriptions for the various teleportation phenomena that are found in nature, in theoretical physics concepts, and in experimental laboratory work. Chapter 2 proposes two quasi-classical physics concepts for teleportation: the first is based on engineering the spacetime metric to induce a traversable wormhole; the second is based on the polarizable-vacuum-general relativity approach that treats spacetime metric changes in terms of equivalent changes in the vacuum permittivity and permeability constants. These concepts are theoretically developed and presented. Promising laboratory experiments were identified and recommended for further research. Chapter 3 presents the current state-of-art of quantum teleportation physics, its theoretical basis, technological development, and its applications. Key theoretical, experimental, and applications breakthroughs were identified, and a series of theoretical and experimental research programs are proposed to solve technical problems and advance quantum teleportation physics. Chapter 4 gives an overview of alternative teleportation concepts that challenge the present physics paradigm. These concepts are based on the existence of parallel universes/spaces and/or extra space dimensions. The theoretical and experimental work that has been done to develop these concepts is reviewed, and a recommendation for further research is made. Last, Chapter 5 gives an in-depth overview of unusual teleportation phenomena that occur naturally and under laboratory conditions. The teleportation phenomenon discussed in the chapter is based on psychokinesis (PK), which is a category of psychotronics. The U.S. military-intelligence literature is reviewed, which relates the historical scientific research performed on PK-teleportation in the U.S., China and the former Soviet Union. The material discussed in the chapter largely challenges the current physics paradigm; however, extensive controlled and repeatable laboratory data exists to suggest that PK-teleportation is quite real and that it is controllable. The report ends with a combined list of references.

1.0 INTRODUCTION

1.1 Introduction

The concept of teleportation was originally developed during the Golden Age of 20th century science fiction literature by writers in need of a form of instantaneous disembodied transportation technology to support the plots of their stories. Teleportation has appeared in such SciFi literature classics as Algis Budry's *Rogue Moon* (Gold Medal Books, 1960), A. E. van Vogt's *World of Null-A* (Astounding Science Fiction, August 1945), and George Langelaan's *The Fly* (Playboy Magazine, June 1957). The Playboy Magazine short story led to a cottage industry of popular films decrying the horrors of scientific technology that exceeded mankind's wisdom: *The Fly* (1958), *Return of the Fly* (1959), *Curse of the Fly* (1965), *The Fly* (a 1986 remake), and *The Fly II* (1989). The teleportation concept has also appeared in episodes of popular television SciFi anthology series such as *The Twilight Zone* and *The Outer Limits*. But the most widely recognized pop-culture awareness of the teleportation concept began with the numerous *Star Trek* television and theatrical movie series of the past 39 years (beginning in 1964 with the first TV series pilot episode, *The Cage*), which are now an international entertainment and product franchise that was originally spawned by the late genius television writer-producer Gene Roddenberry. Because of *Star Trek* everyone in the world is familiar with the "transporter" device, which is used to teleport personnel and material from starship to starship or from ship to planet and vice versa at the speed of light. People or inanimate objects would be positioned on the transporter pad and become completely disintegrated by a beam with their atoms being patterned in a computer buffer and later converted into a beam that is directed toward the destination, and then reintegrated back into their original form (all without error!). "*Beam me up, Scotty*" is a familiar automobile bumper sticker or cry of exasperation that were popularly adopted from the series.

However, the late Dr. Robert L. Forward (2001) stated that modern hard-core SciFi literature, with the exception of the ongoing *Star Trek* franchise, has abandoned using the teleportation concept because writers believe that it has more to do with the realms of parapsychology/paranormal (a.k.a. psychic) and imaginative fantasy than with any realm of science. Beginning in the 1980s developments in quantum theory and general relativity physics have succeeded in pushing the envelope in exploring the reality of teleportation. A crescendo of scientific and popular literature appearing in the 1990s and as recently as 2003 has raised public awareness of the new technological possibilities offered by teleportation. As for the psychic aspect of teleportation, it became known to Dr. Forward and myself, along with several colleagues both inside and outside of government, that anomalous teleportation has been scientifically investigated and separately documented by the Department of Defense.

It has been recognized that extending the present research in quantum teleportation and developing alternative forms of teleportation physics would have a high payoff impact on communications and transportation technologies in the civilian and military sectors. It is the purpose of this study to explore the physics of teleportation and delineate its characteristics and performances, and to make recommendations for further studies in support of Air Force Advanced Concepts programs.

1.2 The Definitions of Teleportation

Before proceeding, it is necessary to give a definition for each of the teleportation concepts I have identified during the course of this study:

- *Teleportation* – SciFi: the disembodied transport of persons or inanimate objects across space by advanced (futuristic) technological means (adapted from Vaidman, 2001). We will call this *sf-Teleportation*, which will not be considered further in this study.

- *Teleportation* – psychic: the conveyance of persons or inanimate objects by psychic means. We will call this *p-Teleportation*.

- *Teleportation* – engineering the vacuum or spacetime metric: the conveyance of persons or inanimate objects across space by altering the properties of the spacetime vacuum, or by altering the spacetime metric (geometry). We will call this *vm-Teleportation*.

- *Teleportation* – quantum entanglement: the disembodied transport of the quantum state of a system and its correlations across space to another system, where *system* refers to any single or collective particles of matter or energy such as baryons (protons, neutrons, etc.), leptons (electrons, etc.), photons, atoms, ions, etc. We will call this *q-Teleportation*.

- *Teleportation* – exotic: the conveyance of persons or inanimate objects by transport through extra space dimensions or parallel universes. We will call this *e-Teleportation*.

We will examine each of these in detail in the following chapters and determine whether any of the above teleportation concepts encompass the instantaneous and or disembodied conveyance of objects through space.

2.0 vm-TELEPORTATION

2.1 Engineering the Spacetime Metric

A comprehensive literature search for vm-Teleportation within the genre of spacetime metric engineering yielded no results. No one in the general relativity community has thought to apply the Einstein field equation to determine whether there are solutions compatible with the concept of teleportation. Therefore, I will offer two solutions that I believe will satisfy the definition of vm-Teleportation. The first solution can be found from the class of traversable wormholes giving rise to what I call a true "stargate." A stargate is essentially a wormhole with a flat-face shape for the throat as opposed to the spherical-shaped throat of the Morris and Thorne (1988) traversable wormhole, which was derived from a spherically symmetric Lorentzian spacetime metric that prescribes the wormhole geometry (see also, Visser, 1995 for a complete review of traversable Lorentzian wormholes):

$$ds^2 = -e^{2\phi(r)}c^2dt^2 + [1 - b(r)/r]^{-1}dr^2 + r^2d\Omega^2 \qquad (2.1),$$

where by inspection we can write the traversable wormhole metric tensor in the form

$$g_{\alpha\beta} = \begin{pmatrix} -e^{2\phi(r)} & 0 & 0 & 0 \\ 0 & [1-b(r)/r]^{-1} & 0 & 0 \\ 0 & 0 & r^2 & 0 \\ 0 & 0 & 0 & r^2\sin^2\theta \end{pmatrix} \qquad (2.2)$$

using standard spherical coordinates, where c is the speed of light, $\alpha,\beta \equiv (0 = t, 1 = r, 2 = \theta, 3 = \varphi)$ are the time and space coordinate indices ($-\infty < t < \infty$; r: $2\pi r$ = circumference; $0 \le \theta \le \pi$; $0 \le \varphi \le 2\pi$), $d\Omega^2 = d\theta^2 + sin^2\theta d\varphi^2$, $\phi(r)$ is the freely specifiable redshift function that defines the proper time lapse through the wormhole throat, and $b(r)$ is the freely specifiable shape function that defines the wormhole throat's spatial (hypersurface) geometry. Such spacetimes are asymptotically flat. The Einstein field equation requires that a localized source of matter-energy be specified in order to determine the geometry that the source induces on the local spacetime. We can also work the Einstein equation backwards by specifying the local geometry in advance and then calculate the matter-energy source required to induce the desired geometry. The Einstein field equation thus relates the spacetime geometry terms comprised of the components of the metric tensor and their derivatives (a.k.a. the Einstein tensor) to the local matter-energy source terms comprised of the energy and stress-tension densities (a.k.a. the stress-energy tensor). The flat-face wormhole or stargate is derived in the following section.

2.1.1 Wormhole Thin Shell Formalism

The flat-face traversable wormhole solution is derived from the thin shell (a.k.a. junction condition or surface layer) formalism of the Einstein equations (Visser, 1989; see also, Misner, Thorne and Wheeler, 1973). We adapt Visser's (1989) development in the following discussion. The procedure is to take two copies of flat Minkowski space and remove from each identical regions of the form $\Omega \times \Re$, where Ω is a three-dimensional compact spacelike hypersurface and $\Re$ is a timelike straight line (time axis). Then identify these two incomplete spacetimes along the timelike boundaries $\partial\Omega \times \Re$. The resulting spacetime is geodesically complete and possesses two asymptotically flat regions connected by a wormhole. The throat of the wormhole is just the junction $\partial\Omega$ (a two-dimensional space-like hypersurface) at which the two original Minkowski spaces are identified (see Figures 1 and 2).



Figure 1. Diagram of a Simultaneous View of Two Remote Compact Regions (Ω_1 and Ω_2) of Minkowski Space Used to Create the Wormhole Throat $\partial\Omega$, Where Time is Suppressed in This Representation (adapted from Bennett et al., 1995)

Approved for public release; distribution unlimited.



Figure 2. The Same Diagram as in Figure 1 Except as Viewed by an Observer Sitting in Region Ω_1 Who Looks Through the Wormhole Throat $\partial\Omega$ and Sees Remote Region Ω_2 (Dotted Area Inside the Circle) on the Other Side

The resulting spacetime is everywhere Riemann-flat except possibly at the throat. Also, the stress-energy tensor in this spacetime is concentrated at the throat with a δ-function singularity there. This is a consequence of the fact that the spacetime metric at the throat is continuous but not differentiable, while the connection is discontinuous; thus causing the Riemann curvature to possess a δ-function singularity (causing undesirable gravitational tidal forces) there. The magnitude of this δ-function singularity can be calculated in terms of the second fundamental form on both sides of the throat, which we presume to be generated by a localized thin shell of matter-energy. The second fundamental form represents the extrinsic curvature of the ∂Ω hypersurface (i.e., the wormhole throat), telling how it is curved with respect to the enveloping four-dimensional spacetime. The form of the geometry is simple, so the second fundamental form at the throat is calculated to be (McConnell, 1957):

$$\begin{aligned} K^{i}{}_{j}{}^{\pm} &= \pm\begin{pmatrix} \kappa_0 & 0 & 0 \\ 0 & \kappa_1 & 0 \\ 0 & 0 & \kappa_2 \end{pmatrix} \\ &= \pm\begin{pmatrix} 0 & 0 & 0 \\ 0 & 1/\rho_1 & 0 \\ 0 & 0 & 1/\rho_2 \end{pmatrix} \end{aligned} \qquad (2.3),$$

where $i,j = 0,1,2$ and $K^{i\,\pm}_{j}$ is the second fundamental form. The full 4×4 matrix $K^{\alpha}{}_{\beta}$ has been reduced to 3×3 form, as above, for computational convenience because the thin shell (or hypersurface) is essentially a two-surface embedded in three-space. The overall ± sign in equation (2.3) comes from the fact that a unit normal points outward from one side of the surface and points inward on the other side. We hereafter drop the ± sign for the sake of brevity in notation. The quantities κ_0, κ_1, and κ_2 measure the extrinsic curvature of the thin shell of local matter-energy (i.e., the stuff that induces the wormhole throat geometry). Since the wormhole throat is a space-like hypersurface, we can exclude time-like hypersurfaces and their components in the calculations. Therefore we set $\kappa_0 = 0$ in equation (2.3) because it is the time-like extrinsic curvature for the time-like hypersurface of the thin shell of matter-energy. As seen in equation (2.3) κ_1 and κ_2 are simply related to the two principal radii of curvature ρ_1 and ρ_2 (defined to be the eigenvalues of $K^{i}{}_{j}$) of the two-dimensional spacelike hypersurface ∂Ω (see Figure 3). It should be noted that a convex surface has positive radii of curvature, while a concave surface has negative radii of curvature.


thin shell of mass-energy
ρ1
ρ2

Figure 3. A Thin Shell of (Localized) Matter-Energy, or Rather the Two-Dimensional Spacelike Hypersurface $\partial\Omega$ (via (2.3)), Possessing the Two Principal Radii of Curvature ρ_1 and ρ_2

It is a standard result of the thin shell or junction condition formalism that the Einstein field equation may be cast in terms of the surface stress-energy tensor S^i_j of the thin matter-energy shell localized in $\partial\Omega$ (note: we are exploiting the symmetry of the wormhole with respect to interchange of the two flat regions Ω_1 and Ω_2):

$$S^i{}_j = -\frac{c^4}{4\pi G}\left(K^i{}_j - \delta^i{}_j K^k{}_k\right) \quad (2.4),$$

where G is Newton's gravitational constant and δ^i_j is the (three-dimensional) unit matrix. K^k_k is the trace of equation (2.3):

$$\begin{aligned} K^k{}_k &= Tr\, K^i{}_j \\ &= \frac{1}{\rho_1} + \frac{1}{\rho_2} \end{aligned} \quad (2.5)$$

and

$$\delta^i{}_j K^k{}_k = \begin{pmatrix} \frac{1}{\rho_1} + \frac{1}{\rho_2} & 0 & 0 \\ 0 & \frac{1}{\rho_1} + \frac{1}{\rho_2} & 0 \\ 0 & 0 & \frac{1}{\rho_1} + \frac{1}{\rho_2} \end{pmatrix} \quad (2.6).$$

Substituting (2.3) and (2.6) into (2.4) gives (after simplification):

$$S^i{}_j = \frac{c^4}{4\pi G}\begin{pmatrix} \frac{1}{\rho_1} + \frac{1}{\rho_2} & 0 & 0 \\ 0 & 1/\rho_2 & 0 \\ 0 & 0 & 1/\rho_1 \end{pmatrix} \quad (2.7).$$

The thin matter-energy shell's surface stress-energy tensor may be interpreted in terms of the surface energy density σ and principal surface tensions ϑ_1 and ϑ_2:

$$S^i{}_j = \begin{pmatrix} -\sigma & 0 & 0 \\ 0 & -\vartheta_1 & 0 \\ 0 & 0 & -\vartheta_2 \end{pmatrix} \quad (2.8).$$

Thus we arrive at the Einstein field equation by equating (2.8) and (2.7) and multiplying both sides by –1:

$$\begin{pmatrix} \sigma & 0 & 0 \\ 0 & \vartheta_1 & 0 \\ 0 & 0 & \vartheta_2 \end{pmatrix} = -\frac{c^4}{4\pi G} \begin{pmatrix} \frac{1}{\rho_1} + \frac{1}{\rho_2} & 0 & 0 \\ 0 & 1/\rho_2 & 0 \\ 0 & 0 & 1/\rho_1 \end{pmatrix} \qquad (2.9),$$

which gives the final result

$$\sigma = -\frac{c^4}{4\pi G}\left(\frac{1}{\rho_1} + \frac{1}{\rho_2}\right) \qquad (2.10a)$$

$$\vartheta_1 = -\frac{c^4}{4\pi G}\frac{1}{\rho_2} \qquad (2.10b)$$

$$\vartheta_2 = -\frac{c^4}{4\pi G}\frac{1}{\rho_1} \qquad (2.10c).$$

These are the Einstein equations. Equations (2.10a-c) imply that (for $\partial\Omega$ convex) we are dealing with ***negative*** surface energy density and ***negative*** surface tensions. This result is in fact the primary matter-energy requirement for traversable wormholes, as was proved by Morris and Thorne (1988), and later by Visser (1995), within the paradigm of classical Einstein general relativity. The negative surface tension (= *positive outward pressure*, a.k.a. gravitational repulsion or antigravity) is needed to keep the throat open and stable against collapse. The reader should **not** be alarmed at this result. Negative energies and negative stress-tensions are an acceptable result both mathematically and physically, and they manifest gravitational repulsion (antigravity!) in and around the wormhole throat. One only needs to understand what it means for stress-energy to be negative within the proper context. In general relativity the term "*exotic*" is used in place of "*negative*." The effects of negative energy have been produced in the laboratory (the Casimir Effect is one example). In short, negative energy arises from Heisenberg's quantum uncertainty principle, which requires that the energy density of any electromagnetic, magnetic, electric or other fields must fluctuate randomly. Even in a vacuum, where the average energy density is zero, the energy density fluctuates. This means that the quantum vacuum can never remain truly empty in the classical sense of the term. The quantum picture of the vacuum is that of a turbulent plenum of virtual (i.e., energy non-conserving) particle pairs that spontaneously pop in and out of existence. The notion of "zero energy" in quantum theory corresponds to the vacuum being filled with such fluctuations going on. This issue is further elaborated on and clarified in greater detail in Appendix A. We will also revisit this in Section 2.2. Finally, it should be noted that for the analysis in this section we assumed an ultrastatic wormhole [i.e., $g_{00} \equiv 1 \Rightarrow \phi(r) = 0$ in equation (2.1)] with the "exotic" matter-energy confined to a thin layer, and we dispensed with the assumption of spherical symmetry.

We can now build a wormhole-stargate and affect *vm-Teleportation* such that a traveler stepping into the throat encounters **no** exotic matter-energy there. This will require that our wormhole be flat shaped. To make the wormhole flat requires that we choose the throat $\partial\Omega$ to have at least one flat face (picture the thin shell in Figure 3 becoming a flat shell). On that face the two principal radii of curvature become $\rho_1 = \rho_2 = \infty$ as required by standard geometry. Substituting this into equations (2.10a-c) gives

$$\sigma = \vartheta_1 = \vartheta_2 = 0 \qquad (2.11),$$

which is a remarkable result. A further consequence of this is that now $K^i_j = 0$, thus making the Riemann curvature and stress-energy tensors (Riemann: $R^\alpha{}_\beta \sim K^\alpha{}_\beta$; stress-energy: $T^\alpha{}_\beta \sim K^\alpha{}_\beta$) at the throat become zero such that the associated δ-function singularities disappear there. This means that a traveler encountering and going through such a wormhole will feel no tidal gravitational forces and see no exotic matter-energy (that threads the throat). A traveler stepping through the throat will simply be ***teleported*** into the other remote spacetime region or another universe (note: the Einstein equation does not fix the spacetime topology, so it is possible that wormholes are inter-universe as well as intra-universe tunnels). We construct such a *teleportation* stargate by generating a thin shell or surface layer of "exotic" matter-energy much like a thin film of soap stretched across a loop of wire.

2.1.2 "Exotic" Matter-Energy Requirements

Now we have to estimate the amount of negative (or exotic) mass-energy that will be needed to generate and hold open a *vm-Teleportation* wormhole. A simple formula originally due to Visser (1995) for short-throat wormholes using the thin shell formalism gives:

$$\begin{aligned} M_{wh} &= -\frac{r_{throat}c^2}{G} \\ &= -(1.3469x10^{27}\ kg)\frac{r_{throat}}{1\ meter} \qquad (2.12), \\ &= -(0.709\,M_{Jupiter})\frac{r_{throat}}{1\ meter} \end{aligned}$$

where M_{wh} is the mass required to build the wormhole, r_{throat} is a suitable measure of the linear dimension (radius) of the throat, and $M_{Jupiter}$ is the mass of the planet Jupiter (1.90×10^{27} kg). Equation (2.12) demonstrates that a mass of $-0.709\ M_{Jupiter}$ (or -1.3469×10^{27} kg) will be required to build a wormhole 1 meter in size. As the wormhole size increases the mass requirement grows negative-large, and vice versa as the wormhole size decreases. After being alarmed by the magnitude of this, one should note that M_{wh} is **not** the total mass of the wormhole as seen by observers at remote distances. The non-linearity of the Einstein field equations dictates that the total mass is zero (actually, the total net mass being positive, negative or zero in the Newtonian approximation depending on the details of the negative energy configuration constituting the wormhole system). And finally, Visser et al. (2003) have demonstrated the existence of spacetime geometries containing traversable wormholes that are supported by ***arbitrarily small quantities*** of exotic matter-energy, and they proved that this was a general result. In Section 2.3 we will discuss how or whether we can create such a wormhole in the laboratory.

2.2 Engineering the Vacuum

Engineering the spacetime vacuum provides a second solution that also satisfies the definition of vm-Teleportation. The concept of "*engineering the vacuum*" was first introduced to the physics community by Lee (1988). Lee stated:

"*The experimental method to alter the properties of the vacuum may be called vacuum engineering…If indeed we are able to alter the vacuum, then we may encounter some new phenomena, totally unexpected.*"

This new concept is based on the now-accepted fact that the vacuum is characterized by physical parameters and structure that constitutes an energetic medium which pervades the entire extent of the universe. We note here the two most important defining properties of the vacuum in this regard (Puthoff et al., 2002):

- ☐ Within the context of quantum field theory the vacuum is the seat of all energetic particle and field fluctuations.
- ☐ Within the context of general relativity theory the vacuum is the seat of a spacetime structure (or metric) that encodes the distribution of matter and energy.

We begin our look into this concept by examining the propagation of light through space. We know from quantum field theory that light propagating through space interacts with the vacuum quantum fields (a.k.a. vacuum quantum field fluctuations). The observable properties of light, including the speed of light, are determined by these interactions. Vacuum quantum interactions with light lead to an effect on the speed of light that is due to the absorption of photons (by the vacuum) to form virtual electron-positron pairs followed by the quick re-emission (from the vacuum) of the photon (see Figure 4). The virtual particle pairs are very short lived because of the large mismatch between the energy of a photon and the rest mass-energy of the particle pair. A key point is that this process makes a contribution to the observed vacuum permittivity ε_0 (and permeability μ_0) constant and, therefore, to the speed of light c [$c = (\varepsilon_0\mu_0)^{-1/2}$].

Approved for public release; distribution unlimited.


Virtual electron
Photon
Virtual photon
Virtual positron
Virtual electron
Photon
Virtual photon
Virtual positron
Time

Photons can change into a variety of short-lived, or "virtual", particles. as they fly through the vacuum. The processes above, represented by Feynman diagrams, are "two-loop"' processes. They affect light's speed

Figure 4. A Schematic of Vacuum Quantum Field Fluctuations (a.k.a. Vacuum Zero Point Field Fluctuations) Involved in the "Light-by-Light" Scattering Process That Affects the Speed of Light (from Chown, 1990)

Approved for public release; distribution unlimited.

The role of virtual particle pairs in determining the ε_0 (μ_0) of the vacuum is analogous to that of atoms/molecules in determining the relative permittivity ε (and μ) of a dielectric material. We know that the absorption/re-emission of photons by atoms/molecules in a transparent medium (note: there are no strongly absorbing resonances, so the atoms/molecules remain in their excited states for a very short time before re-emitting photons) is responsible for the refractive index of the medium, which results in the reduction of the speed of light for photons propagating through the medium. This absorption/re-emission process is also known in physics as a scattering process. We know from experiment that a change in the medium leads to a change in ε (μ), thus resulting in a change of the refractive index. The key point arising from this analogy is that a modification of the vacuum produces a change in ε_0 (μ_0) resulting in a subsequent change in c, and hence, a corresponding change in the vacuum refraction index.

Scharnhorst (1990) and Latorre et al. (1995) have since proved that the suppression of light scattering by virtual particle pairs (a.k.a. coherent light-by-light scattering) in the vacuum causes an ***increase*** in the speed of light accompanied by a decrease in the vacuum refraction index. This very unique effect is accomplished in a Casimir Effect capacitor cavity (or waveguide) whereby the vacuum quantum field fluctuations (a.k.a. zero-point fluctuations or ZPF) inside have been modified (becoming anisotropic and non-translational invariant) to satisfy the electromagnetic boundary conditions imposed by the presence of the capacitor plates (or waveguide walls). The principal result of this modification is the removal of the electromagnetic zero-point energy (ZPE) due to the suppression of vacuum ZPE modes with wavelengths longer than the cavity/waveguide cutoff ($\lambda_0 = 2d$, where d = plate separation; see Figure 5). This removal of free space vacuum ZPE modes suppresses the scattering of light by virtual particle pairs, thus producing the speed of light increase (and corresponding decrease in the vacuum refraction index). We know from standard optical physics and quantum electrodynamics (QED) that the optical phase and group velocities can exceed c under certain physical conditions, but dispersion always ensures that the signal velocity is $\leq c$. But recent QED calculations (see, Scharnhorst, 1990 and Latorre et al., 1995) have proved that in the Casimir Effect system, the dispersive effects are *much weaker* still than those associated with the increase in c so that the phase, group and signal velocities will therefore *all increase* by the same amount. Note that, in general, no dispersion shows up in all of the modified vacuum effects examined by investigators.

Approved for public release; distribution unlimited.



Casimir effect: the vacuum is full of virtual photons, but photons with wavelengths (λ), more than twice the separation of the plates, are excluded from the space between them. The imbalance pushes the plates together

Figure 5. A Schematic of the Casimir Effect Cavity/Waveguide (from Chown, 1990)

Examples demonstrating the increase in light speed (decrease in vacuum refraction index) via the Casimir Effect vacuum and other modified vacuum effects, as well as those effects producing a decrease in light speed (increase in vacuum refraction index), are described as follows. The vacuum modification effect on the speed of light described in the previous paragraph is (Scharnhorst, 1990):

$$\begin{aligned}\frac{c_{\perp}^{*}}{c_0} &= \left(1+\frac{11}{2^6 \bullet (45)^2}\frac{e^4}{(m_e a)^4}\right) \qquad (\hbar = c_0 = \varepsilon_0 = \mu_0 = 1) \\ &= \left(1+\frac{11\pi^2}{8100}\alpha^2\frac{1}{(m_e a)^4}\right) > 1\end{aligned} \qquad (2.13),$$

where $c_{\perp}^{*}$ is the (modified) speed of light propagation perpendicular to the Casimir Effect capacitor plates, c_0 is the speed of light in free space (3×10^8 m/s in MKS units), m_e is the electron mass, α is the fine structure constant ($\approx 1/137$), e is the electron charge ($e^2 = 4\pi\alpha$ in quantum field theory natural units), a is the plate separation, $\hbar$ is Planck's reduced constant, and ε_0 is the vacuum permittivity constant. The condition $\hbar = c_0 = \varepsilon_0 = \mu_0 = 1$ stresses that (2.13), and all the equations that follow, are in quantum field theory natural units. The speed of light and vacuum refraction index measured parallel to the plates is unchanged from their free space values ($c_{\|} = c_0$, $n_{\|} = n_0 = 1$). The modified vacuum refraction index measured perpendicular to the plates is (Scharnhorst, 1990):

$$n_{\perp} = \left(1-\frac{11}{2^6 \bullet (45)^2}\frac{e^4}{(m_e a)^4}\right) < 1 \qquad (\hbar = c_0 = \varepsilon_0 = \mu_0 = 1) \qquad (2.14).$$

Equations (2.13) and (2.14) show that in general $n_{\perp} < 1$ and $c_{\perp}^{*} > c_0$. But $c_{\perp}^{*} \to c_0$ and $n_{\perp} \to 1$ when $a \to \infty$ as expected, since we are now allowing all of the vacuum ZPE modes to re-enter the Casimir cavity in this case.

We now survey the additional examples of modified vacuums which increase/decrease light speed (from Latorre et al., 1995):

- ❑ For light (photons) propagating in a Friedmann-Robertson-Walker (FRW) vacuum (i.e., a homogeneous and isotropic Robertson-Walker gravitational background with Friedmann cosmology):

$$\frac{c^{*}}{c_0} = \left(1+\frac{11}{45}\alpha G\frac{\rho_r + p}{m_e^{\,2}}\right) > 1 \qquad (\hbar = c_0 = \varepsilon_0 = \mu_0 = 1) \qquad (2.15),$$

where c^{*} is the modified vacuum speed of light, G is Newton's constant, ρ_r is the energy density and p is the pressure of a radiation-dominated universe ($p = \rho_r/3$). Here the speed of light is increased.

- ❑ For light (photons) propagating in a homogeneous and isotropic thermal vacuum:

$$\frac{c^{*}}{c_0} = \left(1-\frac{44\pi^2}{2025}\alpha^2\frac{T^4}{m_e^{\,4}}\right) < 1 \qquad (\hbar = c_0 = \varepsilon_0 = \mu_0 = k_B = 1) \qquad (2.16),$$

where T is the temperature of the vacuum and k_B is the Boltzmann constant. Here the speed of light is decreased.

- For light (photons) propagating in an anisotropic vacuum given by an external constant uniform magnetic field ***B***:

$$\begin{aligned} \frac{c_{\parallel}^{*}}{c_0} &= \left(1-\frac{8}{45}\alpha^2\frac{\mathbf{B}^2}{m_e^4}\sin^2\theta\right)<1 \qquad (\hbar = c_0 = \varepsilon_0 = \mu_0 = 1) \\ \frac{c_{\perp}^{*}}{c_0} &= \left(1-\frac{14}{45}\alpha^2\frac{\mathbf{B}^2}{m_e^4}\sin^2\theta\right)<1 \end{aligned} \qquad (2.17),$$

where the speed of light is decreased in this vacuum for polarizations coplanar (||) with and perpendicular (⊥) to the plane defined by ***B*** and the direction of propagation, and θ is the angle between ***B*** and the direction of propagation. Latorre et al. (1995) calculated the polarization-average of (2.17) to give the averaged (modified) speed of light in the B-field:

$$\frac{c^{*}}{c_0} = \left(1-\frac{22}{135}\alpha^2\frac{\mathbf{B}^2}{m_e^4}\right)<1 \qquad (\hbar = c_0 = \varepsilon_0 = \mu_0 = 1) \quad (2.18).$$

- For light (photons) propagating in an anisotropic vacuum given by an external constant uniform electric field ***E***, the polarization-averaged modified speed of light is:

$$\frac{c^{*}}{c_0} = \left(1-\frac{22}{135}\alpha^2\frac{\mathbf{E}^2}{m_e^4}\right)<1 \qquad (\hbar = c_0 = \varepsilon_0 = \mu_0 = 1) \qquad (2.19).$$

Here the speed of light is decreased.

Equations (2.16) – (2.19) are the result of vacuum modifications that populate the vacuum with virtual or real particles that induce coherent (light-by-light) scattering, which reduces the speed of massless particles. By examining the form of equations (2.13) and (2.15) – (2.19) Latorre et al. (1995) discovered that the low energy modification of the speed of light is proportional to the ratio of the modified vacuum energy density (as compared to the standard vacuum energy density, $\rho_{\text{vac}} = 0$) over m_e^4, with a universal numerical coefficient and the corresponding coupling constants. And a general rule became apparent from their analysis that is applicable to modified vacua for massive and massless quantum field theories, for low energy:

$c^* > c_0$ (vacuum refraction index < 1) when the modified vacuum has a lower energy density
$c^* < c_0$ (vacuum refraction index > 1) when the modified vacuum has a higher energy density
$c^* = c_0$ (vacuum refraction index = 1) when the vacuum is free (or un-modified) with $\rho_{\text{vac}} = 0$

The first two rules explain the sign of the change of the speed of light. From this rule and the mathematical commonality between the form of (2.13) and (2.15) – (2.19) Latorre et al. (1995) found a single unifying expression to replace these equations:

$$\frac{c^{*}}{c_0} = 1-\frac{44}{135}\alpha^2\frac{\rho}{m_e^4} \qquad (\hbar = c_0 = \varepsilon_0 = \mu_0 = 1) \qquad (2.20),$$

where ρ is the energy density of the modified vacua under consideration such that $\rho \to \rho_E \sim \boldsymbol{E}^2$ for the electric field vacuum, $\rho \to \rho_B \sim \boldsymbol{B}^2$ for the magnetic field vacuum, and $\rho \to \rho_T \sim \pi^2 T^4$ for the thermal vacuum. If the vacuum is a FRW gravitational vacuum, then one has to substitute one factor of α in (2.20) by $-m_e^2 G$ and $\rho \to \rho_r$. Equation (2.13) for the Casimir Effect vacuum studied earlier is recovered when $\rho \to \rho_{\text{Casimir}} = -(\pi^2/240)a^{-4}$.

Let us recast (2.20) into a more useful form. We subtract one from both sides of (2.20), do some algebra, and thus define the ratio of the change in the speed of light Δc in a modified vacuum to the speed of light in free space c_0:

$$\frac{c^*}{c_0} - 1 = \frac{c^* - c_0}{c_0} \equiv \frac{\Delta c}{c_0}$$

$$\frac{\Delta c}{c_0} = -\frac{44}{135}\alpha^2 \frac{\rho}{m_e^4} \qquad (\hbar = c_0 = \varepsilon_0 = \mu_0 = 1) \quad (2.21).$$

Equations (2.20) and (2.21) are in quantum field theory natural units, which is completely undesirable for estimating physically measurable values of $\Delta c/c_0$. We thus transform or “unwrap” (2.20) and (2.21) back into MKS or CGS units by making the following substitutions (Puthoff, 2003)

$$\rho\ (\text{natural units}) \to \frac{\rho}{\hbar c}\ (\text{MKS or CGS units})$$

$$m_e\ (\text{natural units}) \to \frac{m_e c}{\hbar}\ (\text{MKS or CGS units}),$$

and after some algebra and rearranging we arrive at the final result:

$$\frac{c^*}{c_0} = 1 - \frac{44}{135}\alpha^2 \frac{\rho}{m_e c_0^2}\left(\frac{\hbar}{m_e c_0}\right)^3 \qquad (2.22)$$

and

$$\frac{\Delta c}{c_0} = -\frac{44}{135}\alpha^2 \frac{\rho}{m_e c_0^2}\left(\frac{\hbar}{m_e c_0}\right)^3 \qquad (2.23),$$

where all quantities are now in MKS or CGS units. We chose the former units so that $c_0 = 3\times10^8$ m/s, $\hbar = 1.055\times10^{-34}$ J-s, $m_e = 9.11\times10^{-31}$ kg, and $\alpha = 1/137$. Note that the ratio of the modified vacuum energy density to the electron rest-mass energy has the dimension of (*volume*)$^{-1}$ while the quantity in the bracket is the cubed Compton wavelength of the electron having the dimension of (*volume*), and the product of these is dimensionless.

An excellent example for estimating the magnitude of the change in the speed of light (in a modified vacuum) is the Casimir Effect vacuum, since Casimir Effect experiments are common and widespread such that this would be ideal to experimentally test (2.23). We substitute the Casimir vacuum energy density $\rho_{\text{Casimir}} = -(\pi^2 \hbar c_0/240)a^{-4}$ (in MKS units) into (2.23), do the algebra, insert the MKS values for the physical constants, and make further simplifications to get:

$$\begin{aligned}\frac{\Delta c}{c_0} &= -\frac{44}{135}\alpha^2\left(-\frac{\pi^2}{240}\frac{\hbar c_0}{a^4}\right)\frac{1}{m_e {c_0}^2}\left(\frac{\hbar}{m_e c_0}\right)^3 \\ &= \frac{11}{8100}\alpha^2\pi^2\left(\frac{\hbar}{m_e c_0 a}\right)^4 \qquad (2.24), \\ &\approx \left(1.59\times10^{-56}\right)a^{-4}\end{aligned}$$

where a (the plate separation) is in meters. Another useful equation is:

$$c^* = \left(1+\frac{\Delta c}{c_0}\right)c_0 \qquad (2.25),$$

where we make the substitution $c^* \to c_\perp^*$ for the present case. H. E. Puthoff and the author (Puthoff, 2003) compared the third line in (2.24) with equation (26) in Scharnhorst (1990) and discovered that the result cited there is in error, because the numerical coefficient is four orders of magnitude too small (Scharnhorst originally pointed out this error to Forward, 1996).

We now set $a = 10^{-6}$ m (1 μm) and we get $\Delta c/c_0 \approx 10^{-32}$ and $c_\perp^* \approx c_0$, which is a horrifically small 1 part in 10^{32} change that we cannot hope to measure at present. But for $a = 10^{-10}$ m (1 Å) we get $\Delta c/c_0 \approx 10^{-16}$ and $c_\perp^* \approx c_0$, which is a 1 part in 10^{16} change that could be measurable at present or in the very near future using high precision laser technology. Last, for $a = 1.1229\times10^{-14}$ m (11.229 fm or ≈ 11 times the nuclear diameter; 1 fm = 10^{-15} m) we find that $\Delta c/c_0 \approx 1$ and $c_\perp^* \approx 2c_0$. We are not able to do technical work at nuclear distances at this time; however, that could change as ultrahigh precision measurement technology continues to evolve. The threshold for the onset of significant changes in light speed occurs when $a < 10^{-12}$ m. This result is generally true for the other modified vacua surveyed in (2.15) – (2.19), since accessible (everyday) values for electric and magnetic field strengths, thermal temperatures and radiation densities are not large enough to overcome the size of the electron mass to create a measurable effect. However, there is a class of ultrahigh intensity tabletop lasers that have achieved such extreme electric and magnetic field strengths and temperatures that it may now be possible to consider using them to explore vacuum modification effects in the lab. We will return to this theme in a later section.

•**Key Point**: As disappointing as the Casimir Effect vacuum (and other modified vacua) results are, it should be strongly pointed out that special relativity theory says that if in one inertial reference frame an object travels only one part in 10^{16} (or even one part in 10^{32}) times faster than c_0, then one can find another reference frame where departure and arrival times of the object are simultaneous, and thus the velocity is ***infinite***. This is what motivates us to look at a teleportation mechanism based on engineering of the vacuum.

•**Technical Notes**:

- Equation (2.15) is interpreted as an increase in the speed of light due to a decrease in the number of vacuum ZPE modes. However, this effect is totally unrelated to light-by-light scattering in the vacuum because the gravitational background "squeezes" (as in squeezed quantum optics states; see Davis, 1999a) the ZPE modes, therefore reducing the vacuum energy density. We further note that the coefficient of 11 is the same for the gravitational vacuum as for the other modified vacua examples based on QED. This factor also appears in the coefficient of the Euler-Poincare characteristic spin-½ contribution to the gravitational trace anomaly (Birrell and Davies, 1982). It is beyond the scope of this study to consider the deep connections between quantum field theory and gravitation.

- We have excluded from our survey the Latorre et al. (1995) results pertaining to all other (high or low energy) modifications of the speed of massless particles. That is because the other examples invoked different QED theories possessing massless ($m_e = 0$), massive and intrinsic mass scales that introduced complex correction terms (beyond the leading low energy terms surveyed above) which are mass-related or running mass-related, and they introduced no new speed modification effects (beyond the low energy electron-positron virtual pair contributions); or no genuine speed modification was possible (especially for the massless Quantum Chromodynamic sector involving pseudo-Goldstone particles).

- There is ongoing (very noisy) controversy within the physics community over the effects of $c^* > c_0$ on causality. As this topic is beyond the scope of this study, I will make three points in this regard: 1) There are no grounds for microcausality violations in accordance with Drummond and Hathrell (1980). 2) A new definition of causality is in order for FTL (faster-than-light) phenomena. 3) Investigators have found that time machines (a.k.a. closed timelike curves) do not affect Gauss's theorem, and thus do not affect the derivation of global conservation laws from differential ones (Friedman et al., 1990). The standard conservation laws remain globally valid while retaining a natural quasi-local interpretation for spacetimes possessing time machines (for example, asymptotically flat wormhole spacetimes). Thorne (1993) states that it may turn out that causality is violated at the macroscopic scale. Even if causality is obeyed macroscopically, then quantum gravity might offer finite probability amplitudes for microscopic spacetime histories possessing time machines. Li and Gott (1998) found a self-consistent vacuum for quantum fields in Misner space (a simple flat space with closed timelike curves), for which the renormalized stress-energy tensor is regular (in fact zero) everywhere. This implies that closed timelike curves could exist at least at the level of semi-classical quantum gravity theory. Therefore, FTL causality paradoxes are just a reflection of our ignorance or inadequate comprehension of the physics of chronology and causality.

In this section we have shown how "vacuum engineering" can modify the speed of light, and how this can, in principle, lead to vm-Teleportation. The vacuum modification concepts summarized above lead us to a formal theory that implements the concept of vacuum engineering within a framework that parallels general relativity theory. This theory is called the Polarizable-Vacuum Representation of General Relativity. In the next section we will introduce and summarize this theory.

2.2.1 The Polarizable-Vacuum Representation of General Relativity

The polarizable-vacuum representation of general relativity (a.k.a. PV-GR) treats the vacuum as a polarizable medium of variable refractive index (Puthoff, 1999a, 2002a, b; Puthoff et al., 2002) exemplifying the concept of the vacuum modification (or vacuum engineering) effects surveyed and discussed in the previous section. The PV-GR approach treats spacetime metric changes in terms of equivalent changes in the vacuum permittivity and permeability constants (ε_0 and μ_0), essentially along the lines of the "$TH\varepsilon\mu$" methodology (see Appendix B for a brief description of this) used in comparative studies of alternative metric theories of gravity (Lightman and Lee, 1973; Will, 1974, 1989, 1993; Haugan and Will, 1977). Such an approach, relying as it does on parameters familiar to engineers, can be considered a "metric engineering" approach. Maxwell's equations in curved space are treated in the isomorphism of a polarizable medium of variable refractive index in flat space (Volkov et al., 1971); the bending of a light ray near a massive body is modeled as due to an induced spatial variation in the refractive index of the vacuum near the body; the reduction in the velocity of light in a gravitational potential is represented by an effective increase in the refractive index of the vacuum, and so forth. This optical-engineering approach has been shown to be quite general (de Felice, 1971; Evans et al., 1996a, b).

As recently elaborated by Puthoff (1999a, 2002a, b; Puthoff et al., 2002) the PV-GR approach, which was first introduced by Wilson (1921) and then developed by Dicke (1957, 1961), can be carried out in a self-consistent way so as to reproduce to appropriate order both the equations of general relativity and the match to the standard astrophysics weak-field experimental (PPN parameters and other) tests of those equations while posing testable modifications for strong-field conditions. It is in application that the PV-GR approach demonstrates its intuitive appeal and provides additional insight into what is meant by a curved spacetime metric.

Specifically, the PV-GR approach treats such measures as the speed of light, the length of rulers (atomic bond lengths), the frequency of clocks, particle masses, and so forth, in terms of a variable vacuum dielectric constant K in which the vacuum permittivity ε_0 transforms as $\varepsilon_0 \rightarrow K\varepsilon_0$ and the vacuum permeability transforms as $\mu_0 \rightarrow K\mu_0$ (see also, Rucker, 1977). In a planetary or solar gravitational potential $K = exp(2GM/rc_0^2) > 1$ (M is a local mass distribution, r is the radial distance from the center of M) while $K = 1$ in "empty" or free asymptotic space (Puthoff, 1999a, 2002a, b; Puthoff et al., 2002). In the former case, the speed of light is reduced, light emitted from an atom is redshifted as compared with a remote static atom (where $K = 1$), clocks run slower, objects/rulers shrink, etc. See Table 1.

Table 1. Metric Effects in the PV-GR Model When $K > 1$ (Compared With Reference Frames at Asymptotic Infinity Where $K = 1$; adapted from Puthoff et al., 2002**)**

Variable	**Determining Equation** (subscript 0 is asymptotic value where $K = 1$)	$K > 1$ *(typical mass distribution, M)*
modified speed of light $c^*(K)$	$c^* = c_0/K$	speed of light < c_0
Modified mass $m(K)$	$m = m_0K^{3/2}$	effective mass increases
modified frequency $\omega(K)$	$\omega = \omega_0K^{-1/2}$	redshift toward lower frequencies
modified time interval $\Delta t(K)$	$\Delta t = \Delta t_0K^{1/2}$	clocks run slower
modified energy $E(K)$	$E = E_0K^{-1/2}$	lower energy states
Modified length $L(K)$	$L = L_0K^{-1/2}$	objects/rulers shrink
dielectric-vacuum "gravitational" forces $F(K)$	$F(K) \propto \nabla K$	attractive gravitational force

When $K = 1$ we have the condition that $c^* = c_0$ (vacuum refraction index = 1), because the vacuum is free (or un-modified, and $\rho_{vac} = 0$) in this case. When $K > 1$, as occurs in a region of space possessing a gravitational potential, then we have the condition that $c^* < c_0$ (vacuum refraction index > 1), because the modified vacuum has a higher energy density in the presence of the local mass distribution that generates the local gravitational field. This fact allows us to make a direct correspondence between the speed of light modification physics discussion in Section 2.2 and the underlying basis for the physics of the PV-GR model. Under certain conditions the spacetime metric can in principle be modified to reduce the value of K to below unity, thus allowing for faster-than-light (FTL) motion to be physically realized. In this case, the local speed of light (as measured by remote static observers) is increased, light emitted from an atom is blueshifted as compared with a remote static atom, objects/rulers expand, clocks run faster, etc. See Table 2. We therefore have the condition that $c^* > c_0$ (vacuum refraction index < 1) because the modified vacuum has a lower energy density. In fact, Puthoff (1999a, 2002a) has analyzed certain special black hole metrics and found $K < 1$ from the model. We will return to this theme later. In what follows we briefly review and summarize the key points and equations from the development of the PV-GR model, and we refer the reader to Puthoff (1999a, 2002a, b) for more extensive discussion and derivations.

Table 2. Metric Effects in the PV-GR Model When $K < 1$ (Compared With Reference Frames at Asymptotic Infinity Where $K = 1$; adapted from Puthoff et al., 2002**)**

Variable	**Determining Equation** (subscript 0 is asymptotic value where $K = 1$)	$K < 1$ *(typical mass distribution, M)*
modified speed of light $c^*(K)$	$c^* = c_0/K$	speed of light > c_0
modified mass $m(K)$	$m = m_0 K^{3/2}$	effective mass decreases
modified frequency $\omega(K)$	$\omega = \omega_0 K^{-1/2}$	blueshift toward higher frequencies
modified time interval $\Delta t(K)$	$\Delta t = \Delta t_0 K^{1/2}$	clocks run faster
modified energy $E(K)$	$E = E_0 K^{-1/2}$	higher energy states
modified length $L(K)$	$L = L_0 K^{-1/2}$	objects/rulers expand
dielectric-vacuum "gravitational" forces $F(K)$	$F(K) \propto \nabla K$	repulsive gravitational force

We begin by recalling that in flat space electrodynamics, the electric flux vector ***D*** in a linear, homogeneous medium can be written

$$\begin{aligned}\mathbf{D} &= \varepsilon\mathbf{E} \\ &= \varepsilon_0\mathbf{E} + \mathbf{P} \qquad (2.26), \\ &= \varepsilon_0\mathbf{E} + \alpha_V\mathbf{E}\end{aligned}$$

where ε is the permittivity of the medium, the polarization ***P*** corresponds to the induced dipole moment per unit volume in the medium whose polarizability per unit volume is α_V, and ***E*** is the electric field. The identical form of the last two terms naturally leads to the interpretation of ε_0 as the polarizability per unit volume of the vacuum. The quantum picture of the vacuum, where it has been shown that the vacuum acts as a polarizable medium by virtue of induced dipole moments resulting from the excitation of virtual electron-positron particle pairs (Heitler, 1954), completely justifies the interpretation that the vacuum is a medium. Note that there are other virtual particle pairs in the vacuum that also contribute to this picture; however, it is the electron-positron pairs that dominate the others, as shown in Section 2.2. The basic postulate of the PV-GR model for curved space conditions is that the polarizability of the vacuum in the vicinity of localized mass-energy distributions differs from its asymptotic free space value by virtue of vacuum polarization effects induced by the presence of the local mass-energy. Thus the postulate for the vacuum itself is

$$\begin{aligned}\mathbf{D} &= \varepsilon\mathbf{E} \\ &\equiv K\varepsilon_0\mathbf{E}\end{aligned} \qquad (2.27),$$

where K (a function of position) is the modified dielectric constant of the vacuum due to the induced vacuum polarizability changes under consideration. Equation (2.27) defines the transformation $\varepsilon = K\varepsilon_0$.

Table 1 shows the various quantitative effects a polarizable vacuum (in the presence of positive mass-energy distributions) has on the various measurement processes important to general relativity. The effects demonstrated in the middle and right columns demonstrate the basis of the polarizable vacuum approach to general relativity. Table 2 shows what effects are manifested when negative mass-energy distributions induce vacuum polarizability changes that lead to FTL phenomenon. Experimental observations impose constraints on the model causing key physical constants to remain constant even with variable polarizability present in the local space. Puthoff (1999a, 2002a, b) has shown that the fine structure constant is constrained by observational data to remain constant within a variable polarizable vacuum, and this constraint actually defines the transformation $\mu = K\mu_0$. The elementary particle charge e is also taken to be constant in a variable polarizable vacuum because of charge conservation. And $\hbar$ remains a constant by conservation of angular momentum for circularly polarized photons propagating through the (variable polarizability) vacuum. The remaining constant of nature is the speed of light, and although the tables showed how this was modified in variable polarizability vacuums, it is interesting to see how this modification comes about. In a modified (variable polarizability) vacuum the speed of light is defined, as it is in standard electrodynamics, in terms of the permittivity and permeability by:

$$\begin{aligned} c^* &\equiv (\varepsilon\mu)^{-1/2} \\ &= (K\varepsilon_0 \bullet K\mu_0)^{-1/2} \\ &= (K^2\varepsilon_0\mu_0)^{-1/2} \\ &= \frac{1}{K}(\varepsilon_0\mu_0)^{-1/2} \\ &= \frac{c_0}{K} \end{aligned} \qquad (2.28),$$

where the permittivity/permeability transformations and the free space (un-modified vacuum) definition for c_0 were inserted. Note that (2.28) can be re-written as $c^*/c_0 = 1/K$, and this is to be compared with (2.22). Thus we see from (2.28), and by comparison with (2.22), that K plays the role of a variable refractive index under conditions in which the vacuum polarizability is assumed to change in response to general relativistic-type influences. One further note of interest is that the permittivity/permeability transformations also maintains constant the ratio

$$\sqrt{\frac{\mu}{\varepsilon}} = \sqrt{\frac{\mu_0}{\varepsilon_0}} \,,$$

which is the impedance of free space. This constant ratio is required to keep electric-to-magnetic energy ratios constant during adiabatic movement of atoms from one position in space to another of differing vacuum polarizability (Dicke, 1957, 1961). And this constant ratio is also a necessary condition in the $TH\varepsilon\mu$ formalism for an electromagnetic test particle to fall in a gravitational field with a composition-independent acceleration (Lightman and Lee, 1973; Will, 1974, 1989, 1993; Haugan and Will, 1977).

Now we make the "crossover connection" to the standard spacetime metric tensor concept that characterizes conventional general relativity theory, as originally shown by Puthoff (1999a, 2002a, b). In flat (un-modified or free) space the standard four-dimensional infinitesimal spacetime interval ds^2 is given (in Cartesian coordinates with subscript 0) by

$$ds^2 = -c_0{}^2 dt_0{}^2 + \sum_{i=1}^{3} dx_{i0}{}^2 \qquad (2.29),$$

where $i \equiv (1 = x,\ 2 = y,\ 3 = z)$. This metric means that measuring rods and clocks are non-varying wherever one goes in spacetime to make measurements. However, this has been shown to be incorrect in general relativity theory, so the length and time transformations (between proper and coordinate values) given in the tables (middle columns) indicate that measuring rods and clocks do vary when placed in regions where $K \neq 1$. Therefore, we replace the time and space differentials in (2.29) with the length and time transformations in the tables into (2.29), and derive the general relativistic spacetime interval

$$ds^2 = -\frac{1}{K} c_0{}^2 dt^2 + K\left(\sum_{i=1}^{3} dx_i{}^2\right) \qquad (2.30).$$

Note that observers within a $K \neq 1$ region will always measure the speed of light to be c_0. Equation (2.30) defines an isotropic coordinate system, which is a common and useful way to represent spacetime metrics in general relativity studies. By inspection the metric tensor is written

$$g_{\alpha\beta} = \begin{pmatrix} -1/K & 0 & 0 & 0 \\ 0 & K & 0 & 0 \\ 0 & 0 & K & 0 \\ 0 & 0 & 0 & K \end{pmatrix} \qquad (2.31).$$

The Lagrangian density for matter-field interactions in a vacuum of variable K is given by Puthoff (1999a, 2002a, b) as

$$\begin{aligned} L_d = &-\left[\frac{m_0 c_0{}^2}{\sqrt{K}}\sqrt{1-\left(\frac{v}{c_0/K}\right)^2} + q\Phi - qA_i v^i\right]\delta^3(\mathbf{r}-\mathbf{r}_0) \\ &-\frac{1}{2}\left(\frac{\mathbf{B}^2}{K\mu_0} - K\varepsilon_0\mathbf{E}^2\right) - \frac{c_0{}^4}{32\pi G}\frac{1}{K^2}\left[(\nabla K)^2 - \frac{1}{(c_0/K)^2}\left(\frac{\partial K}{\partial t}\right)^2\right] \end{aligned} \qquad (2.32),$$

where the first term is the Lagrangian density for a free particle of mass m_0, charge q and 3-vector velocity $\boldsymbol{v}$ ($v = |\boldsymbol{v}|$, 3-vector components are labeled by i) interacting with electromagnetic fields via the electromagnetic field 4-vector potential $A_\mu = (\Phi, A_i)$ (note that $\delta^3(\mathbf{r} - \mathbf{r}_0)$ is the delta function that locates the point particle at position $\mathbf{r} = \mathbf{r}_0$); the second term is the Lagrangian density for the electromagnetic fields themselves, and the last term is the Lagrangian density for K (treated here as a scalar variable). This last term emulates the Lagrangian density for the gravitational field. Equation (2.32) does not include any quantum gauge field interaction terms because it is beyond the scope of the present incarnation of the PV-GR approach to include them. We can obtain the equations of particle motion in a variable dielectric vacuum by performing the standard variations of the Lagrangian density $\delta(\int L_d\, dx\, dy\, dz\, dt)$ with respect to the particle variables. However, we are more interested in obtaining the "master equation" for K by varying the Lagrangian density with respect to K, and Puthoff (1999a, 2002a, b) gives the result:

$$\nabla^2\sqrt{K} - \frac{1}{(c_0/K)^2}\frac{\partial^2\sqrt{K}}{\partial t^2}$$

$$= -\frac{8\pi G}{c_0{}^4}\sqrt{K}\left\{\frac{\left(m_0 c_0{}^2/\sqrt{K}\right)}{\sqrt{1-\left(\frac{v}{c_0/K}\right)^2}}\,\frac{1}{2}\left[1+\left(\frac{v}{c_0/K}\right)^2\right]\delta^3(\mathbf{r}-\mathbf{r}_0)\right. \qquad (2.33).$$

$$\left. +\frac{1}{2}\left(\frac{\mathbf{B}^2}{K\mu_0}+K\varepsilon_0\mathbf{E}^2\right)-\frac{c_0{}^4}{32\pi G}\frac{1}{K^2}\left[(\nabla K)^2+\frac{1}{(c_0/K)^2}\left(\frac{\partial K}{\partial t}\right)^2\right]\right\}$$

This equation describes the generation of general relativistic vacuum polarization effects due to the presence of matter and fields. By inspecting the right-hand side of the equation, we observe that changes in K are driven by the mass density (1st term), electromagnetic energy density (2nd term), and the vacuum polarization energy density itself (3rd term). In fact, the 3rd term emulates the gravitational field self-energy density. Note that the 2nd and 3rd terms in (2.33) appear with opposite signs with the result that electromagnetic field effects can counteract the gravitational field effects. Puthoff found that (2.33) gives the solution $K = exp(2GM/rc_0{}^2)$ in the vicinity of a static spherically symmetric (uncharged) mass M (in the low velocity limit $v << c_0$, $\partial K/\partial t = 0$, $\boldsymbol{E} = \boldsymbol{B} = 0$, $q = 0$), which reproduces to appropriate order the standard general relativistic Schwarzschild spacetime metric for the weak gravitational field conditions prevailing in the solar system. This solution guarantees that $K > 1$ near mass concentrations.

Of major importance to the present study are solutions giving $K < 1$ so that teleportation can be realized. Puthoff has found one such solution by studying the case of a static spherically symmetric mass M with charge Q familiar from the study of the Reissner-Nordstrϕm spacetime metric. In this case Puthoff found the result

$$K = \left[\cos\left(\frac{\sqrt{b^2-a^2}}{r}\right)+\frac{a}{\sqrt{b^2-a^2}}\sin\left(\frac{\sqrt{b^2-a^2}}{r}\right)\right]^2 \qquad \left(b^2 > a^2\right) \qquad (2.34),$$

where $a^2 = (GM/c_0{}^2)^2$, $b^2 = Q^2G/4\pi\varepsilon_0 c_0{}^4$, and r is the radial distance from the center of M. And in this case (2.34) gives $K < 1$, which shows that FTL solutions are available in the PV-GR approach (as they are also in the Einstein theory). (For $a^2 > b^2$ the solution is hyperbolic-trigonometric and describes the standard Reissner-Nordstrϕm metric where $K > 1$.)

Generally speaking, in Einstein general relativity the Reissner-Nordstrϕm metric can be manipulated along with two shells of electrically charged matter to form a traversable wormhole (Schein and Aichelburg, 1996). But there are two drawbacks to this. The first is that the scheme involves dealing with the collapsed state of the stellar matter that generates the metric (a.k.a. Reissner-Nordstrϕm black hole) along with the unpleasant side effects that are encountered, such as the crushing singularities and multiple (unstable) event horizons. Second, the traversable wormhole is an eternal time machine connecting remote regions of the same universe together. Now there are no black hole solutions found in the PV-GR model because in that approach stellar matter collapses smoothly to an ultra-dense state and without the creation of singularities and event horizons (Puthoff, 1999b).

In either case, the Reissner-Nordstrϕm metric does not offer a viable mechanism for vm-Teleportation. We are more interested in examining other PV-GR cases (where $K < 1$ or even $K << 1$)

that emulate the effects of traversable wormhole metrics that do obey the vm-Teleportation definition, such as the example presented in Section 2.1. Equation (2.33) suggests that we search for a vacuum engineering concept that exploits electromagnetic fields to alter the vacuum dielectric constant *K* to induce the desired vm-Teleportation effect in the modified vacuum. (However, we can insert other source terms that will lead to the desired result.) We envision this particular teleportation concept to resemble Figure 2. [Note: Before this report went to press H. E. Puthoff, C. Maccone and the author discovered a number of $K < 1$ solutions to equation (2.33) that uniquely meet the definition of vm-Teleportation and FTL motion. We discovered that the generic energy density required to generate $K < 1$ solutions must be negative, and that the total energy density of the system as seen by remote observes is approximately zero. This unique result compares very well with the traversable wormhole mass-energy density requirements discussed in Section 2.1.2. This discovery will be the subject of a forthcoming paper.]

2.3 Conclusion and Recommendations

The concept we envision for vm-Teleportation is that animate or inanimate objects would be placed inside an environmentally enclosed vessel that would simply be moved into the teleportation device. The "teleporter" would be activated, and the vessel would almost immediately disappear and then reappear at the remote destination as if it were briefly moving through a portal or "stargate." The teleportation device might be required to operate in the vacuum of space outside of the Earth's atmosphere. We have shown two practically equivalent ways to implement vm-Teleportation. There is the manipulation of spacetime geometry via exploiting negative (i.e., quantum vacuum zero point) energy as shown by Einstein's general relativity theory, and there is the modification of the vacuum dielectric constant as shown by the PV-GR model. Both have a great deal of theoretical foundation to begin exploring experimentally. The PV-GR model needs additional theoretical work for the present application, but it is now mature enough for experimental exploration.

There already is extensive theoretical, and more importantly, experimental research proving that the vacuum can be engineered (or physically modified) so that the vacuum ZPE can be exploited (via the Casimir Effect, for example) to extract electrical energy or actuate microelectromechanical devices (see for example, Ambjϕrn and Wolfram, 1983; Forward, 1984, 1996, 1998; Puthoff, 1990, 1993; Cole and Puthoff, 1993; Milonni, 1994; Mead and Nachamkin, 1996; Lamoreaux, 1997; Chan et al., 2001, and the references cited therein). But most of this research involves very low energy density regimes, which are much too low for our purposes. The Mead and Nachamkin (1996) device is actually designed to extract electrical energy from the higher frequency/higher energy density ZPE modes. However, new ultrahigh-intensity lasers became available in the 1990s that have achieved extreme physical conditions in the lab that are comparable to the extreme astrophysical conditions expected to be found in stellar cores and on black hole event horizons (Perry, 1996; Mourou et al., 1998; Perry, 2000). The power intensity of these lasers has reached the point to where they actually probe QED vacuum physics and general relativistic physics, and they have even modified the vacuum itself. The lasers were originally called petaWatt lasers (operating range of $10^{14} - 10^{18}$ Watts/cm^2 at femtosecond pulses), but they have now reached power intensity levels in the $10^{25} - 10^{30}$ Watts/cm^2 range. The lasers were made possible by a novel breakthrough called "chirped pulse amplification" whereby the initial low energy/low power intensity laser beam is stretched, amplified and then compressed without experiencing any beam distortions or amplifier damage. This laser system was initially designed as a large-optics beam-line power booster for the NOVA laser fusion experiment at Lawrence Livermore National Laboratory. But researchers found a way to shrink the optics down to tabletop scale, and one can now own and operate a tabletop ultrahigh-intensity laser for ≈ $500,000. The dimensions of the optical bench used by the University of California-San Diego is ≈ 5 m × 12 m (or ≈ 60 m^2; see Mourou et al., 1998). In tabletop lab experiments ultrahigh-intensity lasers have generated >> gigagauss magnetic fields, ≥ 10^{16} Volt/cm electric field strengths, >> terabar light pressures and >> 10^{22} m/sec^2 subatomic particle accelerations. These ultrahigh-intensity tabletop lasers are thus the ideal instrument with which to explore the fundamental physics underlying the two possible concepts for vm-Teleportation.

There are several ideas on how to generate negative energy in the lab that could potentially be extracted and concentrated in the proper fashion to induce the traversable flat-face wormhole outlined in Section 2.1.1 or induce the $K < 1$ condition (in the PV-GR model) outlined in Section 2.2.1. The schemes for generating negative energy are:

- Casimir Effect (described in Section 2.2): This is the easiest and most well known way to generate negative energy in the lab. The energy density $\rho_{\mathrm{Casimir}} = -(\pi^2 \hbar c_0/240)a^{-4}$ within a Casimir capacitor cavity is negative and manifests itself by producing a force of attraction between the capacitor plates. This has been measured in the lab (see above references). Forward (1998) proposes a mechanism for the endless extraction of energy from the vacuum in a Casimir cavity by cyclic manipulation of the cavity dimensions.

- Moving Mirror: Negative quantum vacuum energy can be created by a single moving reflecting surface (a moving mirror). If a mirror moves with increasing acceleration, then a flux of negative energy emanates from its surface and flows out into the space ahead of the mirror (Birrell and Davies, 1982). However, this effect is known to be exceedingly small, and it is not the most effective way to generate negative energy.

- Optically Squeezed Laser Light: Negative quantum vacuum energy can also be generated by an array of ultrahigh intensity lasers with an ultrafast rotating mirror system. In this scheme a laser beam is passed through an optical cavity resonator made of lithium niobate crystal that is shaped like a cylinder with rounded silvered ends to reflect light. The resonator will act to produce a secondary lower frequency light beam in which the pattern of photons is rearranged into pairs. This is the quantum optical "squeezing" of light effect. (See Section A.2 in Appendix A for a complete definition and description of squeezed quantum states.) Therefore, the squeezed light beam emerging from the resonator will contain pulses of negative energy interspersed with pulses of positive energy. Another way to squeeze light would be to manufacture extremely reliable light pulses containing precisely one, two, three, etc. photons apiece and combine them together to create squeezed states to order. Superimposing many such states could theoretically produce bursts of intense negative energy. For the laser beam resonator example we find that both negative and positive energy pulses are of $\approx 10^{-15}$ second duration. We could arrange a set of rapidly rotating mirrors to separate the positive and negative energy pulses from each other. The light beam is to strike each mirror surface at a very shallow angle while the rotation ensures that the negative energy pulses are reflected at a slightly different angle from the positive energy pulses. A small spatial separation of the two different energy pulses will occur at some distance from the rotating mirror. Another system of mirrors will be needed to redirect the negative energy pulses to an isolated location and concentrate them there.

- Gravitationally Squeezed Vacuum Energy: A natural source of negative quantum vacuum energy comes from the effect that gravitational fields (of astronomical bodies) in space have upon the surrounding vacuum. For example, the gravitational field of the Earth produces a zone of negative energy around it by dragging some of the virtual particle pairs (a.k.a. virtual photons or vacuum ZPF) downward. This concept was initially developed in the 1970s as a byproduct of studies on quantum field theory in curved space (Birrell and Davies, 1982). However, Hochberg and Kephart (1991) derived an important application of this concept to the problem of creating and stabilizing traversable wormholes, and their work was corrected and extended by Davis (1999a). They proved that one can utilize the negative vacuum energy densities, which arise from *distortion of the electromagnetic zero point fluctuations* due to the interaction with a prescribed gravitational background, for providing a violation of the energy conditions (see

Section A.1 in Appendix A). Hochberg and Kephart (1991) showed that the squeezed quantum states of quantum optics provide a natural form of matter having negative energy density. And since the vacuum is defined to have vanishing energy density, anything possessing less energy density than the vacuum must have a negative energy density. The analysis, via quantum optics, shows that gravitation itself provides the mechanism for generating the squeezed vacuum states needed to support stable traversable wormholes. The production of negative energy densities via a squeezed vacuum is a necessary and unavoidable consequence of the interaction or coupling between ordinary matter and gravity, and this defines what is meant by gravitationally squeezed vacuum states. The magnitude of the gravitational squeezing of the vacuum can be estimated from the squeezing condition, which simply states that substantial gravitational squeezing of the vacuum occurs for those quantum electromagnetic field modes with *wavelength* (λ in meters) > *Schwarzschild radius* (r_S in meters) of the mass in question (whose gravitational field is squeezing the vacuum). The Schwarzschild radius is the critical radius, according to general relativity theory, at which a spherically symmetric massive body becomes a black hole; i.e., at which light is unable to escape from the body's surface. We can actually choose any radial distance from the mass in question to perform this analysis, but using the Schwarzschild radius makes equations simpler in form. The general result of the gravitational squeezing effect is that as the gravitational field strength increases the negative energy zone (surrounding the mass) also increases in strength. Table 3 shows when gravitational squeezing becomes important for example masses. The table shows that in the case of the Earth, Jupiter and the Sun, this squeeze effect is extremely feeble because only ZPF mode wavelengths above 0.2 m – 78 km are affected. For a solar mass black hole (radius of 2.95 km), the effect is still feeble because only ZPF mode wavelengths above 78 km are affected. But note from the table that quantum black holes with Planck mass will have enormously strong negative energy surrounding them because all ZPF mode wavelengths above 8.50×10^{-34} meter will be squeezed; in other words, all wavelengths of interest for vacuum fluctuations. Black holes with proton mass will have the strongest negative energy zone in comparison because the squeezing effect includes all ZPF mode wavelengths above 6.50×10^{-53} meter. Furthermore, a black hole smaller than a nuclear diameter ($\approx 10^{-16}$ m) and containing the mass of a mountain ($\approx 10^{11}$ kg) would possess a fairly strong negative energy zone because all ZPF mode wavelengths above 10^{-15} meter will be squeezed.

Table 3. Substantial Gravitational Squeezing Occurs When $\lambda \geq 8\pi r_S$ (For Electromagnetic ZPF; adapted from Davis, 1999a**)**

Mass of body	Schwarzschild radius of body, r_S	ZPF mode wavelength, λ
Sun = 2.0×10^{30} kg	2.95 km	≥ 78 km
Jupiter = 1.9×10^{27} kg	2.82 m	≥ 74 m
Earth = 5.976×10^{24} kg	8.87×10^{-3} m	≥ 0.23 m
Typical mountain ≈ 10^{11} kg	≈ 10^{-16} m	≥ 10^{-15} m
Planck mass = 2.18×10^{-8} kg	3.23×10^{-35} m	≥ 8.50×10^{-34} m
Proton = 1.673×10^{-27} kg	2.48×10^{-54} m	≥ 6.50×10^{-53} m

•**Recommendations**:

- Theoretical Program 1: A one to two year theoretical study (cost ≈ \$80,000) should be initiated to explore the recently discovered $K < 1$ (FTL) solutions to equation (2.33) in order to define, characterize and model the negative energy density source(s) that induce the FTL vacuum modification. The study should also identify potential lab experiments designed to test theoretical predictions.

- Theoretical Program 2: A one to two year study (cost ≈ \$80,000) should be initiated to conduct a detailed review of the negative energy generation schemes summarized above to define their characteristics, performances and requirements. The study should develop technical parameters for each of the schemes in order to identify potential lab experiments.

- Experimental Program 1: An experimental study should be conducted to test Forward's (1998) Casimir energy extraction proposal. An experiment definition study will be required to estimate the experimental method, procedure, equipment needs and costs.

- Experimental Program 2: An experimental study using ultrahigh-intensity lasers should be conducted to test the Optically Squeezed Laser Light proposal. An experiment definition study will be required to estimate the experimental method, procedure, equipment needs and costs.

- Experimental Program 3: An experimental study using ultrahigh-intensity lasers should be conducted to probe QED vacuum physics and vacuum modification as well as test elements of the PV-GR model. A starting point for this program would be to use such lasers to perform the Ding and Kaplan (1989, 1992, 2000; see also, Forward, 1996) experiment. This is an important fundamental physics experiment to do, because it can distinguish between the rival quantum vacuum electromagnetic ZPE fluctuation and fluctuating charged particle source field theory models, which would settle the acrimonious debate over whether the vacuum really fluctuates or not. R. L. Forward (1999) told the author that a Nobel Prize rides on performing this experiment and settling the issue once and for all. The Ding and Kaplan proposal is already designed to probe QED vacuum physics and vacuum modification. [The essence of the Ding and Kaplan proposal is to demonstrate that a form of photon-photon scattering predicted by QED gives rise to 2^{nd}-harmonic generation of intense laser radiation in a DC magnetic field due to the broken symmetry of interaction (in the Feynman "box" diagram approximation). This effect is possible only when the field system (optical wave + DC field) is inhomogeneous, in particular when a Gaussian laser beam propagates in either a homogeneous or inhomogeneous DC magnetic field. In other words, a vacuum region is filled with a DC magnetic field that polarizes the virtual particle pairs (a.k.a. virtual photons) in the vacuum. This polarized vacuum then scatters incident ultrahigh-intensity laser photons of frequency ν (energy E), thereby generating outgoing photons of frequency 2ν (energy $2E$).] An experiment definition study will be required to estimate the experimental method, procedure, equipment needs and costs.

- Experimental Program 4: An experimental study using ultrahigh-intensity lasers should be conducted to establish the extreme physical conditions necessary to test the strong-field limit of general relativity with an emphasis on generating spacetime curvature and negative energy in order to induce a putative micro-wormhole. (Experimental Programs 3 and 4 could be done together to determine whether Puthoff's PV-GR theory or Einstein's general relativity theory is the correct model for nature.) A Nobel Prize is in the offing if this question were to be addressed and settled. An experiment definition study will be required to estimate the experimental method, procedure, equipment needs and costs.

3.0 q-TELEPORTATION

3.1 Teleportation Scenario

Future space explorers and their equipment will need to easily and quickly travel from an orbiting spacecraft to the surface of some remote planet in order to get their work done, or military personnel in the United States need to easily and quickly travel from their military base to another remote location on Earth in order to participate in a military operation, or space colonists will need quick transport to get from Earth to their new home planet. Instead of using conventional transportation to expedite travel the space explorer, military personnel or space colonist and/or their equipment go into the "Teleporter" (a.k.a. "Transporter" in Star Trek lingo) and are "beamed down" or "beamed over" to their destinations at light speed. The mechanism for this teleportation process is hypothetically envisioned to be the following:

1. Animate/inanimate objects placed inside the teleporter are scanned by a computer-generated and -controlled beam.
2. The scan beam encodes the entire quantum information contained within the animate/inanimate object(s) into organized bits of information, thus forming a digital pattern of the object(s).
3. The scan beam then dematerializes the object(s) and stores its pattern in a pattern buffer, thus transforming the atomic constituents of the dematerialized object(s) into a matter stream. Alternative 1: The dematerialization process converts the atoms into a beam of pure energy. Alternative 2: The scan beam does not dematerialize the object(s).
4. The teleporter then transmits the matter/pure energy stream and quantum information signal in the form of an annular confinement beam to its destination. Alternative: Only the quantum information signal is transmitted.
5. At the receiving teleporter the matter/pure energy stream is sent into a pattern buffer whereby it is recombined with its quantum information, and the object(s) is rematerialized back into its original form. Alternative 1: The receiving teleporter recombines the transmitted quantum information with atoms stored inside a reservoir to form a copy of the original. Alternative 2: The quantum information is reorganized in such a way as to display the object on some three-dimensional (holographic) visual display system.

Problem: This generic scenario is modeled after teleportation schemes found in SciFi. There are a lot of important little details that were left out of the teleportation process because we simply do not know what they are. This technology does not yet exist. And we are left with the question of which one of the alternative processes identified in items 3 – 5 one wants to choose from. The above scenario is only an outline, and it is by no means complete since it merely serves to show what speculation exists on the subject. The above scenario describes a speculative form of what we call *q-Teleportation*.

There are questions to be addressed in the above scenario. Does the teleporter transmit the atoms and the quantum bit information signal that comprises the animate/inanimate object or just the quantum bit information signal? There are $\approx 10^{28}$ atoms of matter combined together in a complex pattern to form a human being. How does one transmit this much information and how do we disassemble that many atoms? Computer information gurus would insist that it is not the atoms that matter but only the bits of information representing them when considering the transmission of large "bodies" of information. But are humans simply the sum of all the atoms (and the related excited atom quantum states) that comprise them? We could possibly learn to reconstitute a beam of atoms into a chemically accurate human being. However, would this also include the reconstruction of a person's consciousness (personality, memories, hopes, dreams, etc.) and soul or spirit? This question is beyond the scope of this study to address, but it is nevertheless one of the most important concepts awaiting a complete scientific understanding.

For the teleporter to process and transmit the quantum bit information signal that encodes the animate/inanimate object's pattern will require stupendous digital computer power. For each atom comprising the object we must encode its location in space (three position coordinates), its linear and angular momentum (three vector components for each quantity), and its internal quantum state (electron orbital-energy levels and their excitation/de-excitation and ionization states, binding to other atoms to form molecules, molecular vibrational/rotational states, bound nuclei states, spin states for electrons and nuclei, etc.), etc. If we assume that we can digitally encode all of this information for a single atom with a minimum of one kilobyte (1 byte = 8 bits, 1 bit ≡ 0 or 1) of data, then we will require a minimum of 10^{28} kilobytes to encode and store an entire human being (in three-dimensions). To digitally store and access this much information at present (and for the foreseeable future) is nontrivial. It will take more than 2,400 times the present age of the universe (≈ 13 billion years) to access this amount of data using commercially available computers (operating at ≈ 10 gigabyte/sec). Top-of-the-line supercomputers will not reduce this time significantly. The computer technology needed to handle such a large data storage requirement simply does not exist. The largest commercially available computers can store ≈ 40 gigabytes on a single hard drive. We will need ≈ 10^{20} of these hard drives to store the encoded information of just one human being. Also, wire and coaxial/fiber optic cables do not have the physical capacity to transmit this amount of data between devices. These numbers will not be significantly different for macroscopic inanimate objects. The information processing and transfer technology required for the teleportation system may become possible in 200 – 300 years if improvements in computer storage and speed maintains a factor of 10 – 100 increase for every decade. There is speculation that emergent molecular, bio-molecular (DNA-based systems) and quantum computer technology may achieve the performances required for a teleportation system. In the former case molecular dynamics mimics computer logic processes and the ≈ 10^{25} particles in a macroscopic sample will all act simultaneously, making for far greater digital information processing and transfer speeds. Researchers have given no formal performance estimates for this emergent technology. In the latter case quantum computing would take advantage of entangled quantum states of subatomic matter or photons, whereby digital logic processes would occur at light speed. This technology is in its infancy, and there has been no clear direction on what performance levels will be possible in the future. This topic will be discussed further in Section 3.2.3.

In the above teleportation scenario we might consider dematerializing animate/inanimate objects into a matter stream consisting of only the object's constituent atoms or atomic subcomponents (protons, neutrons and electrons) and transmitting them at the speed of light (or close to it). To push atoms or subatomic particles to near the speed of light will require imparting to them an energy comparable to their rest-mass energy, which will be at a minimum of one order of magnitude larger than the amount of energy required to break protons up into free quarks. The energy required to completely dematerialize (or dissolve) matter into its basic quantum constituents or into pure energy is alone stupendous. At first one will have to impart to every molecule within the object an energy that is equivalent to the binding energy between atoms (atomic binding energy ~ chemical energy ~ *several* eV) in order to break apart the molecules comprising the object's macro-structure. After this an energy equivalent to nuclear binding energies (≈ *several* × 10^6 times atomic binding energy, or ≈ *several* MeV) must be imparted to every free atomic nucleus inside the object in order to break apart the protons and neutrons residing within each nucleus. And last, an energy equivalent to the binding energy that holds together the three quarks residing within each proton and neutron must be imparted to each of the free protons and neutrons within the object. According to the Standard Model and experimental data, the quark binding energy is practically infinite. But all is not lost, because the Standard Model also predicts that if we could heat up the nuclei to ≈ 10^{13} °C (≈ 10^6 times hotter than the core temperature of the Sun, or ≈ 10^3 MeV), then the quarks inside would suddenly lose their binding energies and become massless (along with other elementary matter). This heat is also equivalent to the rest-mass energy of protons and neutrons. Therefore, to heat up and dematerialize one human being would require the annihilation of the rest mass-energy of all 10^{28} protons-neutrons or the energy equivalent of 330 1-megaton thermonuclear bombs. Compare this stupendous explosive energy with the explosive yield of the largest thermonuclear bomb ever detonated on Earth, which was a 50-megaton bomb that was built by Andrei Sakharov in the USSR and detonated on October 30, 1961; it was called "Tzar Bomba." Its first incarnation (ca. early October 1961) comprised a uranium fusion tamper, which gave an estimated explosive yield of ≈ 100 megatons. But the weapon was too heavy (27 metric tons) for a bomber to carry, so the tamper was replaced by one made of lead, which reduced both the weight and the yield. In the end we see that it is not a trivial problem to simply heat up and dematerialize any human or inanimate objects. The technology to do so does not exist unless we invoke new physics to get around the energy requirement.

Finally, we must consider the resolution and aperture of the optics required to scan and transmit the animate/inanimate object's matter (or energy) stream. The Heisenberg quantum uncertainty principle fundamentally constrains the measurement resolution of conjugate observable quantities, such as position and momentum or energy and time. The measurement of any combination of (conjugate) observables with arbitrarily high precision is not possible, because a high precision measurement of one observable leads to imprecise knowledge of the value of the conjugate observable. The quantum uncertainty principle makes it impossible to measure the exact, total quantum state of any object with certainty. The scan resolution of a teleportation system is defined by the wavelength of light used to illuminate the object's atomic/subatomic constituents and record their configurations. To resolve matter at atomic/subatomic distance scales requires that the energy of the scanner light (photons) be extremely large (according to the uncertainty principle); and during the scan this large light energy will be conveyed to the constituents, causing them to drastically change their speed and direction of motion. This means that it is physically impossible to resolve an object's atomic/subatomic particle components and their configurations with the precision necessary to accurately encode and later recreate the object being teleported. To resolve atomic/subatomic particles requires wavelengths smaller than the size of these constituents, which will typically be 1 Å – 1 fm. Such wavelengths are in the gamma ray part of the spectrum, and this becomes a major technical problem for us because at present there is no gamma ray electro-optics with which to work with. Now consider the example of teleporting an object from the surface of a planet back to its spacecraft in orbit some *several* × 10^2 – 10^3 km away. The optical aperture required to illuminate and scan an object with ≈ 1 Å – 1 fm resolution from orbit will be >> *several* × 10^2 – 10^3 km. If we are to consider teleporting an object from planet to planet or from star to star then the aperture required will be >> *several* × 10^8 – 10^{13} km. These technical problems are truly insurmountable unless totally new physics becomes available.

3.2 Quantum Teleportation

It turns out that there does in fact exist a form of teleportation that occurs in nature despite the numerous technical roadblocks described in the previous section. It is called *quantum teleportation*, which is based on the well-known concept of quantum entanglement. Erwin Schrödinger coined the word "entanglement" in 1935 in a three-part paper (Schrödinger, 1935a, b, c, 1980). These papers were prompted by the Einstein, Podolsky and Rosen (1935; denoted hereafter as EPR) paper that raised fundamental questions about quantum mechanics, whereby Einstein had loudly complained that quantum mechanics allowed physical processes resembling "spooky action at a distance" to occur. EPR recognized that quantum theory allows certain correlations to exist between two physically distant parts of a quantum system. Such correlations make it possible to predict the result of a measurement on one part of a system by looking at the distant part. On this basis, EPR argued that the distant predicted quantity should have a definite value even before being measured, if quantum theory is complete and respects locality (a.k.a. causality). EPR concluded that, from a classical perspective, quantum theory must be incomplete because it disallows such definite values prior to measurement. Schrödinger's perspective on this argument gives the modern view of quantum mechanics, which is to say that the wavefunction (a.k.a. quantum state vector) provides all the information there is about a quantum system. In regards to the nature of entangled quantum states, Schrödinger (1935a, b, c, 1980) stated that, "The whole is in a definite state, the parts taken individually are not." This statement defines the essence of pure-state entanglement. Schrödinger went on to give a description of quantum entanglement by introducing his famous cat experiment.

To better understand the concept of quantum entanglement/teleportation we will focus on the quantum wavefunction (a.k.a. quantum state function). Any quantum system such as a particle that possesses a position in space, energy, angular and linear momentum, and spin is completely described by a wavefunction. This is usually symbolized in a variety of ways, and we choose to represent a generic wavefunction using the traditional "bra-ket" notation of quantum mechanics: $|\varphi\rangle$. Anything that we want to know about the particle is mathematically encoded within $|\varphi\rangle$. As we discussed in the previous section the wavefunction can never be completely known because there is no measurement that can determine it completely. The only exception to this is in the special case that the wavefunction has been prepared in some particular state or some member of a known basis group of states in advance. By measuring one of the properties of a quantum system, we can get a glimpse of the overall quantum state that is encoded within $|\varphi\rangle$. According to the quantum uncertainty principle the act of doing such a measurement will destroy any ability to subsequently determine the other properties of the quantum system. So the act of measuring a particle actually destroys some of the information about its pristine state. This makes it impossible to copy particles and reproduce them elsewhere via quantum teleportation. However, it turns out that one can recreate an unmeasured quantum state in another particle as long as one is prepared to sacrifice the original particle. The trick is to exploit the EPR process to circumvent the quantum uncertainty principle.

As discussed previously, EPR discovered that a pair of spatially separated quantum sub-systems that are parts of an overall quantum system can be "entangled" in a non-local (i.e., non-causal) way. When two particles come into contact with one another, they can become "entangled." In an entangled state, both particles remain part of the same quantum system so that whatever you do to one of them affects the other one in a predictable fashion. More precisely, a measurement on one of the entangled sub-systems puts it into a particular quantum state, while instantaneously putting the sub-system with which it is entangled into a corresponding quantum state, while the two sub-systems are separated by arbitrarily large distances in spacetime (even backwards in time!). A simple example of this phenomenon is to prepare a pair of photons in the same quantum state such that they are entangled, and then allow them to fly apart to remote locations without any form of communication occurring between them along their journey. Measuring the polarization of one of the pair of entangled photons induces the other photon, which may be light-years away, into the same state of polarization as that which was measured for its entangled twin. The basic operation of quantum teleportation can be described as determining the total quantum state of some large quantum system, transmitting this state information from one place to another, and making a perfect reconstruction of the system at the new location. In principle, entangled particles can serve as "transporters" of sorts. By introducing a third "message" particle to one of the entangled particles, one could transfer its properties to the other one, without ever measuring those properties.

Historically, quantum entanglement was never reconciled with the quantum uncertainty principle and the requirement of locality (or causality) in observed physical phenomena, thus it became a paradox in quantum theory. A three-decade debate began following the appearance of the EPR paper over whether quantum entanglement (a.k.a. "spooky action at a distance") was a real quantum phenomenon or not, and this debate came to be called the "EPR dilemma." Einstein's only solution to the dilemma was to suggest that quantum mechanics was incomplete and needed a reformulation to incorporate local hidden-variables that can account for observed physical phenomena without violating causality. Bell (1964) later solved the EPR dilemma by deriving correlation inequalities that can be violated in quantum mechanics but have to be satisfied within every model that is local and complete. Such models are called "local hidden-variable models." Bell showed that a pair of entangled particles, which were once in contact but later moved too far apart to interact directly (i.e., causally), can exhibit individually random behavior that is too strongly correlated to be explained by classical statistics. Bell's inequalities make it possible to test whether local hidden-variable models can account for observed physical phenomena in lab experiments. Groundbreaking experimental work by Aspect et al. (1982a, b) along with further theoretical and experimental work done by others (Freedman and Clauser, 1972; Aspect, 1983; Aspect and Grangier, 1985; Hong and Mandel, 1985; Bennett and Wiesner, 1992; Tittel et al., 1998a, b; Tittel and Weihs, 2001) demonstrated violations of the Bell inequalities, which therefore invalidated the local hidden-variable models. The key result of recent theoretical and experimental work is that an observed violation of a Bell inequality demonstrates the presence of entanglement in a quantum system.

3.2.1 Description of the q-Teleportation Process

The experimental work of Bennett et al. (1993) followed by the theoretical and experimental work of others (Vaidman, 1994; Kwiat et al., 1995; Braunstein, 1996; Braunstein and Kimble, 1998; Pan et al., 1998; Stenholm and Bardroff, 1998; Zubairy, 1998; Vaidman and Yoran, 1999; Kwiat et al., 1999) made the breakthrough that was necessary to demonstrate the principle of quantum teleportation in practice. It was a remarkable technical breakthrough that settled, once and for all, the nagging question of whether quantum entanglement could be used to implement a teleportation process to transfer information between remotely distant quantum systems non-causally (i.e., at FTL speed). It is easy to describe how quantum teleportation works in greater detail. Figure 6 compares conventional facsimile transmission with the quantum teleportation process seen in Figure 7. In a conventional facsimile transmission the original document is scanned, extracting partial information about it, but it remains more or less intact after the scanning process. The scanned information is then sent to the receiving station, where it is imprinted on new paper to produce an approximate copy of the original. In quantum teleportation (Figure 7) one scans out part of the information from object A (the original), which one wants to teleport, while causing the remaining, unscanned, part of the information in A to pass, via EPR entanglement, into another object C which has never been in contact with A. Two objects B and C are prepared and brought into contact (i.e., entangled), and then separated. Object B is taken to the sending station, while object C is taken to the receiving station. At the sending station object B is scanned together with the original object A, yielding some information and totally disrupting the states of A and B. This scanned information is sent to the receiving station, where it is used to select one of several treatments to be applied to object C, thereby putting C into an exact replica of the former state of A. Object A itself is no longer in its original initial state, having been completely disrupted by the scanning process. The process just described is teleportation and not replication, and one should not confuse the two. There is a subtle, unscannable kind of information that, unlike ordinary information or material, can be delivered via EPR correlations/entanglement, such that it cannot by itself deliver a meaningful and controllable message. But quantum teleportation delivers exactly that part of the information in an object that is too delicate to be scanned out and delivered by conventional methods.


Intact Original
Approximate Copy
Apply Treatment
Send Data
Scan
Original
Raw Material

Figure 6. Classical Facsimile Transmission (Modified IBM Press Image)


Teleported Replica of Object A
C
Disrupted Original
B
A
Send Data
Apply Treatment
Scan
B
C
A
Original
Entangled Pair of Objects

Figure 7. Quantum Teleportation (Modified IBM Press Image)

We now go one more final step to give a simplified outline of the actual teleportation process according to Bennett et al. (1993). They propose a multistep procedure by which any quantum state $|\chi\rangle$ of a particle or a photon (that correspond to an N-state system) is to be teleported from one location to another. For example, $|\chi\rangle$ might be a two-level system that could refer to the polarization of a single photon, the nuclear magnetic spin of a hydrogen atom, or the electronic excitation of an effective two-level atom. The following scenario outlines the q-Teleportation process in a very simplified way:

1. Prepare a pair of quantum subsystems $|\varphi\rangle$ and $|\psi\rangle$ in an EPR entangled state so that they are linked together. $|\varphi\rangle$ and $|\psi\rangle$ are maximally entangled and together constitute a definite pure state superposition even though each of them is maximally undetermined or mixed when considered separately.

2. Transport $|\varphi\rangle$ to the location of the teleportation transmitter and transport $|\psi\rangle$ to the location of the teleportation receiver. (In the technical literature the transmitter is called "Alice" and the receiver is called "Bob.") The transmitter and receiver can be many light years apart in space. Note that the two subsystems are non-causally correlated via entanglement, but they contain no information about $|\chi\rangle$ at this point. The two subsystems represent an open quantum channel that is ready to transmit information.

3. Now Alice brings the teleported state $|\chi\rangle$ into contact with the entangled state $|\varphi\rangle$ and performs a quantum measurement on the combined system $|\chi\rangle|\varphi\rangle$. Bob and Alice have previously agreed upon the details of the quantum measurement.

4. Using a conventional classical communication channel, Alice transmits to Bob a complete description of the outcome of the quantum measurement she performed on $|\chi\rangle|\varphi\rangle$.

5. Bob then subjects $|\psi\rangle$ to a set of linear transformations (i.e., suitable unitary rotations) that are dictated by the outcome of Alice's quantum measurement. The quantum subsystem Bob originally first received is no longer in state $|\psi\rangle$ after the linear transformations because it is now in a state identical to the original state $|\chi\rangle$. Therefore, $|\chi\rangle$ has in effect been teleported from Alice to Bob.

Bennett et al. (1993) showed in their experimental work that this scheme requires both a conventional communication channel and a non-causal EPR channel to send the state $|\chi\rangle$ from one location to another. In addition to this, a considerable pre-arrangement of entangled states and quantum measurement procedures is required to make the process work. Bennett et al. (1993) analyzed the information flow implicit in the process and showed that Alice's measurement does not provide any information about the quantum state $|\chi\rangle$. All of the quantum state information is passed by the EPR link between the entangled particle states $|\varphi\rangle$ and $|\psi\rangle$. We can think of the measurement results as providing the "code key" that permits the EPR information to be decoded properly at Bob's end. And because the measurement information must travel on a conventional communications channel, the decoding cannot take place until the code key arrives, insuring that no FTL teleportation is possible.

The q-Teleportation scheme teleports the state of a quantum system without having to completely measure its initial state. The outcome of the process is that the initial quantum state $|\chi\rangle$ is destroyed at Alice's location and recreated at Bob's location. It is very important for the reader to understand that it is the ***quantum states*** of the particles/photons that are destroyed and recreated in the teleportation process, and not the particles/photons themselves. The quantum state or wavefunction contains the information on the state of a particle, but is not a directly observable physical quantity like mass-energy. The quantum information contained within a state is available in the form of probabilities or expectation values.

Therefore, q-Teleportation *cannot* teleport animate or inanimate matter (or energy) in its physical entirety. However, some experts argue that because a particle's or a photon's quantum state is its defining characteristic, teleporting its quantum state is completely *equivalent* to teleporting the particle/photon even though the original particle's/photon's quantum state (and defining characteristic) was completely destroyed in the process (more on this in Section 3.3). Therefore, no quantum cloning is possible and we are left with a (near-perfect) copy of the now-destroyed original after teleportation (Wootters and Zurek, 1982; Barnum et al., 1996). And finally, classical information itself *cannot* be teleported faster than the speed of light via the non-causal EPR channel; however, quantum information can (more on this in Section 3.2.3).

3.2.2 Decoherence Fundamentally Limits q-Teleportation

Finally, the reader must understand that the q-Teleportation scenario described in the previous section was simplified because we unrealistically assumed that Alice and Bob shared an EPR entangled pair that was free of noise or decoherence. Decoherence is the process, whereby an object's quantum states degrade when information leaks to or from the environment (i.e., environmental noise) through stray interactions with the object. In reality, Alice and Bob have quantum systems that interact directly or through another mediating quantum system like two ions in an ion trap that interact through phonon modes of the trap, or Rydberg atoms in a laser cavity that interact via photons (Sackett, 2001; Raimond et al., 2001). Decoherence degrades the fidelity of the quantum link (i.e., the set of pure EPR entangled pairs) between two quantum systems, thus introducing a certain level of error in the exchange of quantum information between the systems.

In a real-world example of an application of q-Teleportation to quantum computation (discussed in the next section), we can devise an array of interconnected ion traps with each trap holding a small number of ions that are coupled by ions that are moved between the traps or by traveling photons (Wineland et al., 2002). The quantum link (or EPR interaction) between a pair of systems is subject to noise or decoherence through photon loss or heating of the phonons. At present, decoherence imposes a fundamental limit on our ability to perform quantum information processing. Research is continuing on whether decoherence can be reduced, circumvented, or otherwise be (partially or totally) eliminated. Dür and Briegel (2003) have taken the first step towards this goal at rudimentary level by showing that fault-tolerant quantum computation can be achieved in the presence of very high noise levels occurring in the interaction link between small quantum systems, if one assumes that local quantum processing on each end is nearly error free. They showed that the interaction link can have an error rate of two-thirds.

3.2.3 Recent Developments in Entanglement and q-Teleportation Physics

Quantum teleportation physics is still in its infancy. Both theoretical and experimental developments are advancing in many different directions, but are far from maturity at this point in time because the field is still evolving at present. Technical applications of entanglement and q-Teleportation are just becoming conceptualized for the first time, while a small number of basic physics breakthroughs and their related applications are in experimental progress at present. The research community is still in the process of discovering the full nature of entanglement and q-Teleportation, its rules, and what roadblocks nature has in store for its applications and further progression. The literature cited in this study is by no means complete, and only represents a subset of the entire field, because the research is still evolving.

An important application of quantum entanglement and q-Teleportation was the discovery made by Shor (1994, 1997) that computation with quantum states instead of classical bits can result in large savings in computation time. For example, the best algorithms take exponentially more resources to factor ever-larger numbers on a classical computer. A 500-digit number needs 10^8 times as many computational steps to factor as a 250-digit number. The latter classically requires $\approx 5\times10^{24}$ computational steps, or about 150,000 years computing time at terahertz speed, to factor. Shor found a polynomial-time quantum algorithm that solves the problem of finding prime factors of a large integer.

He showed that his algorithm rises only polynomially so that a 500-digit number takes only eight times as many computational steps to factor as a 250-digit number. And by using the quantum factoring algorithm, a 250-digit number requires only ≈ 5×10^{10} steps or < 1 second to factor at terahertz speed, so that a 500-digit number will take ≤ 1 second to factor. No classical polynomial-time algorithm for this problem exists at present. This breakthrough generated a cottage industry of research into quantum computing and quantum information theory.

IBM (2001) constructed a prototype quantum computer that uses the nuclear spins of seven atoms that are part of a large molecule with the iron-based chemical composition $H_5C_{11}O_2F_5Fe$. The computer uses entangled nuclear spins for storage and has a capacity of seven qubits (qubits are defined in the bulleted list in the next two paragraphs below). All of the Fluorine atoms in the large molecule are Fluorine isotope 19 and two of the Carbon atoms are Carbon isotope 13. All the other non-hydrogen atoms have even isotope numbers and no nuclear spins. The objective of the prototype quantum computer was to factor the number 15 into its two prime factors 3 and 5 by using Shor's quantum factoring algorithm. The quantum computation required that a sample of ≈ 10^{18} of the large molecules be placed in a magnetic field and manipulated by nuclear magnetic resonance (NMR) techniques. This mechanism allows the spins to function as qubits, whereby Schor's algorithm can be performed via manipulation of the NMR fields. NMR was used to implement quantum computing in this prototype, because the nuclear spins are well isolated from decoherence as a result of the very long decoherence time (the time after which quantum coherence is lost due to environmental noise) in the system.

To factor larger numbers will require a system that uses more than seven qubits. It is estimated that a quantum computer using ≈ 36 qubits could very quickly perform computations that would require a conventional computer ≈ 13 billion years to perform. And such a computer could solve one of the technical problems of human teleportation discussed in Section 3.1. However, a scale-up in the number of qubits is difficult because the IBM prototype has reached the technology limit of NMR quantum computing. The prototype's operation requires that all of the qubits must be in the same molecule. And molecules with more than seven spins that can be used as qubits are not feasible at present. However, there are alternative technologies for quantum computing that show promise for scaling up the number of qubits. The technologies of nuclear spin orientation of single atom impurities in semiconductors, electron spin orientation in quantum dots, and the manipulation of magnetic flux quanta in superconductors all show promise of providing a basis for scalable quantum computers. Finally, the primary technical problem in quantum computing at the present time is decoherence, and this must be eliminated or otherwise mitigated before new quantum technology can become competitive with conventional computer technology.

A byproduct of the recent quantum computing and information research is that a modern theory of entanglement has emerged. Researchers now treat entanglement as a quantifiable physical resource that enables quantum information processing and computation. Entanglement is no longer treated as a paradox of quantum theory. It has been recently discovered that (Nielsen and Chuang, 2000; Nielsen, 2003; Terhal et al., 2003):

- various kinds of pure and mixed entangled states may be prepared in addition to the simple pure-state superpositions that was described in the previous section

- the members of an entangled group of objects do not have their own individual quantum states, only the group as a whole has a well-defined state (i.e., "the whole is greater than the sum of its parts")

- entangled objects behave as if they were physically connected together no matter how far apart they actually are, distance does not attenuate entanglement in the slightest – it has been demonstrated that information can be teleported over 40 km using existing technology (H. Everitt, Army Research Office, 2000)

- if something is entangled with other objects, then a measurement of it simultaneously provides information about its partners

- some quantum systems can have a little entanglement while others will have a lot

- the more entanglement available, the better suited a system is to quantum information processing

- decoherence degrades the fidelity of the quantum link (i.e., the set of pure EPR entangled pairs) between two quantum systems, thus introducing a certain level of error in the exchange of quantum information between the systems; thus limiting our ability to perform quantum information processing (see more on this issue in the next paragraph below)

- mixed entangled states may be measured, distilled, concentrated, diluted, and manipulated

- the basic resource of classical information is the bit (i.e., the two values 0 and 1), while quantum information comes in quantum bits (i.e., qubits) that are described by their quantum state; qubits can exist in superpositions that simultaneously involve 0 and 1, thus giving them an infinite range of values; groups of qubits can be entangled; qubits must be insulated against decoherence, so that the coherent state of the quantum system in a quantum computer is preserved for a time that is long enough to set up a calculation, perform it, and read out the results

- quantum computers processing qubits or entangled qubits can outperform classical computers; functional requirements of quantum computers:

    - they must have the ability to initialize any qubit in a specified state, and to measure the state of a specific qubit
    - they must have universal quantum gates, which are logical elements capable of arranging any desired logical relationship between the states of qubits
    - they must also have a processor capable of interlinking quantum gates to establish rules and boundary conditions for their inter-relationships – in a quantum computation, the arrangement of quantum gates connects the qubits in a logical pattern, according to a program or algorithm, and after an interval the qubits assigned to the result are read out

- quantum error correction codes exist, whereby qubits are passed through a circuit (the quantum analogue of logic gates) that will successfully fix an error in any one of the qubits without actually reading what all the individual qubit states are; no qubit cloning is required

- a completely secure quantum key can be generated and distributed (for communication and decoding of encrypted messages) using entangled photons has been demonstrated (Tittel et al., 2000; Jennewein et al., 2000; Naik et al., 2000); any eavesdropper's attempt to intercept the quantum key will alter the contents in a detectable way, enabling users to discard the compromised parts of the data

- in an experiment which verified that EPR entanglement obeys Special Relativity (Seife, 2000; Scarani et al., 2000; Gisin et al., 2000; Zbinden et al., 2000a, b), and involving a photon detector moving at relativistic speeds (for example, Bob moves away from Alice at close to the speed of light), investigators determined that quantum information via EPR photon pair entanglement must travel > 10^7 times light speed (the photon detectors were 10.6 km apart)

- investigators are still developing quantitative laws of entanglement to provide a set of principles for understanding the behavior of entanglement and how it is used to do information processing

- investigators are working to develop an understanding of the general principles that govern complex quantum systems such as quantum computers

Other developments are equally as interesting or compelling. For example, the quantum state of the object we wish to teleport does not have to describe single microscopic systems like photons, ions, atoms or electrons. Quantum states can describe large collections of atoms like chemical compounds, humans, planets, stars, and galaxies. Hartle and Hawking (1983) even derived the quantum wavefunction of the Universe in closed form, although, it was extremely simplified and excluded the presence of quantum matter-energy. So it has become possible to consider teleporting large quantum systems. We summarize the more recent spectacular developments in the following:

- Generation of entanglement and teleportation by Parametric Down-Conversion (Bouwmeester et al., 1997; Zeilinger, 2003): EPR entangled photon pairs are created when a laser beam passes through a nonlinear β-barium borate or BBO crystal. Inside the crystal (BBO, for example) an ultraviolet photon (λ = 490 nm) may spontaneously split into two lower energy infrared photons (λ = 780 nm), which is called parametric down-conversion. The two "down-conversion" photons emerge as independent beams with orthogonal polarizations (horizontal or vertical). (The orthogonal polarization states represent a classic example of the discrete quantum state variables that can be teleported. Other examples of discrete quantum variables that have been teleported using other schemes include the nuclear magnetic spin of a hydrogen atom, electronic excitations of an effective two-level atom, elementary particle spins, etc.) In the two beams along the intersections of their emission cones, we observe a polarization-entangled two-photon state. For the experimental realization of quantum teleportation, it is necessary to use pulsed down-conversion. Only if the pulse width of the UV light, and thus the time of generating photon pairs is shorter than the coherence time of the down-converted photons, then interferometric Bell-state analysis can be performed. In this type of experiment, the pulses from a mode-locked Ti:Saphire laser have been frequency doubled to give pulses of ≈ 200 fs duration (1 fs = 10^{-15} second). The interfering light is observed after passage through IR filters of 4 nm bandwidth giving a coherence time of ≈ 520 fs. After retroflection during its second passage through the crystal, the UV pulse creates another pair of photons. One of these will be the teleported photon, which can be prepared to have any polarization. Beam splitters and photon detectors are used to perform the Bell-state analysis during the standard teleportation process that ensues. See Figure 8 for a schematic showing the layout of a standard parametric down-conversion entanglement-teleportation experiment.

- Teleportation of squeezed states of light and continuous quantum state variables (Furusawa et al., 1998; Sørensen, 1998; Braunstein and Kimble, 1998; Opatrný et al., 2000; Braunstein et al., 2001; Zhang et al., 2002; Bowen et al., 2002; Bowen et al., 2003; Zeilinger, 2003): Squeezed light (see Section A.2 in Appendix A) is used to generate the EPR entangled beams, which are sent to Alice and Bob. A third beam, the input, is a coherent state of unknown complex amplitude. This state is teleported to Bob with a high fidelity only achievable via the use of quantum entanglement. Entangled EPR beams are generated by combining two beams of squeezed light at a 50/50 beam splitter. EPR beam 1 propagates to Alice's sending station, where it is combined at a 50/50 beam splitter with the unknown input state, in this case a coherent state of unknown complex amplitude. Alice uses two sets of balanced homodyne detectors to make a Bell-state measurement on the amplitudes of the combined state. Because of the entanglement between the EPR beams, Alice's detection collapses Bob's field (EPR beam 2) into a state conditioned on Alice's measurement outcome. After receiving the classical result from Alice, Bob is able to construct the teleported state via a simple phase-space displacement of the EPR field 2. Quantum teleportation in this scheme is theoretically perfect, yielding an output state which equals the input with a fidelity $F = 1$. In practice, fidelities less than one are realized due to imperfections in the EPR pair, Alice's Bell measurement, and Bob's unitary transformation. By contrast, a sender and receiver who share only a classical communication channel cannot hope to transfer an arbitrary quantum state with a fidelity of one. For coherent states, the classical teleportation limit is $F = 0.5$, while for light polarization states it is $F = 0.67$. The quantum nature of the teleportation achieved in this case is demonstrated by the experimentally determined fidelity of $F = 0.58$, greater than the classical limit of 0.5 for coherent states. The fidelity is an average over all input states and so measures the ability to transfer an arbitrary, unknown superposition from Alice to Bob. This technique achieves the teleportation of continuous quantum state variables, as opposed to the discrete quantum state variables used in the Bennett et al. (1993) teleportation protocol and its variants. The teleportation of a squeezed state of light from one beam of light to another demonstrates the teleportation of a continuous feature (of light) that comes from the superpositions of an infinite number of basic states of the electromagnetic field, such as those found in squeezed states. This line of research also involves the experimental demonstration of the mapping of quantum states from photonic to atomic media via entanglement and teleportation. Hald et al. (1999) reported on the experimental observation of a spin-squeezed macroscopic ensemble of 10^7 cold atoms, whereby the ensemble is generated via quantum state entanglement/teleportation from non-classical light to atoms.


Quantum Teleportation
135° POLARIZATION DETECTOR
BEAM SPLITTER
45° POLARIZATION DETECTOR
BOB
RECEIVING STATION
PHOTON B
UV PULSE
ENTANGLED PHOTONS
PHOTON A
PHOTON M WITH 45° POLARIZATION
DETECTOR 1
UV PULSE
PHOTON M
BEAM SPLITTER
MESSAGE TO BE TELEPORTED: 45° POLARIZATION
ALICE
SENDING STATION
DETECTOR 2

Figure 8. Quantum Teleportation (From www.aip.org)

At the sending station of the quantum teleporter, Alice encodes a "messenger" photon (M) with a specific state: 45 degrees polarization. This travels towards a beam splitter. Meanwhile, two additional entangled photons (A and B) are created. The polarization of each photon is in a fuzzy, undetermined state, yet the two photons have a precisely defined interrelationship. Specifically, they must have complementary polarizations. For example, if photon A is later measured to have horizontal (0 degrees) polarization, then the other photon must collapse into the complementary state of vertical (90 degrees) polarization. Entangled photon A arrives at the beam splitter at the same time as the message photon M. The beam splitter causes each photon to either continue toward detector 1 or change course and travel to detector 2. In 25% of all cases, in which the two photons go off into different detectors, Alice does not know which photon went to which detector. This inability for Alice to distinguish between the two photons causes quantum weirdness to kick in. Just by the very fact that the two photons are now indistinguishable, the M photon loses its original identity and becomes entangled with A. The polarization value for each photon is now indeterminate, but since they travel toward different detectors Alice knows that the two photons must have complementary polarizations. Since message photon M must have complementary polarization to photon A, then the other entangled photon (B) must now attain the same polarization value as M. Therefore, teleportation is successful. Indeed, Bob sees that the polarization value of photon B is 45 degrees: the initial value of the message photon.

- Entanglement of Atoms (Hagley et al., 1997; Sackett et al., 2000): EPR entanglement at the level of atoms has been experimentally demonstrated using rubidium atoms prepared in circular Rydberg states (i.e., the outer electrons of the atom have been excited to very high energy states and are far from the nucleus in circular orbits). The experimental apparatus produces two entangled atoms, one atom in a ground state and the other atom in an excited state, physically separated so that the entanglement is non-local. And when a measurement is made on one atom, let us say the atom in a ground state, then the other atom instantaneously presents itself in the excited state – the result of the second atom wave function collapse, thus determined by the result of the first atom wave function collapse. This work is now evolving towards the demonstration of entanglement for molecules and larger entities followed by teleportation of their states. Bose and Home (2002) have improved on this concept by proposing a single, simple generic method by which any atoms, ions and macroscopic objects can be entangled and teleported.

- Teleportation of an Atomic State via Cavity Decay (Bose et al., 1999; Sackett et al., 2000): It has been shown how the state of an atom trapped in a cavity can be teleported to a second atom trapped in a distant cavity simply by detecting photon decays from the cavities.

- Biological Quantum Teleportation (Mavromatos et al., 2002): There are several obstacles to teleporting large complicated objects, especially biological entities. Decoherence is the primary obstacle. That is because observable quantum effects in biological matter is thought to be strongly suppressed due to the macroscopic nature of most biological entities and the fact that such systems live at near room temperature, and there is always contact between biological entities and the environment (the source of decoherence). These conditions result in very fast collapse of pertinent quantum wavefunctions to one of the allowed classical states of the biological entity. Mavromatos et al. (2002) propose a daring model that predicts dissipationless energy transfer along shielded macromolecules at near room temperatures as well as quantum teleportation of states across microtubules and perhaps neurons. It is proposed that under certain circumstances it is in principle possible to obtain the necessary isolation against environmental decoherence, so that meso/macroscopic quantum coherence, and entanglement extending over scales that are larger than the atomic scale, may be achieved and maintained for times comparable to the characteristic times for biological and cellular processes. Microtubules are comprised of tubulin that is a common polar protein found in the cytoskeleton of eukariotic cells, which is especially enriched in brain tissue. The model treats microtubules as quantum mechanically isolated high-Q QED cavities, exhibiting properties analogous to those of electromagnetic cavities routinely used in quantum optics. The model builds a microtubule network that achieves quantum teleportation of coherent quantum states, leading to decoherence-resistant bulk quantum information processing and computing within the biological matter. It is speculated that the model can explain how consciousness works, and how the brain processes and computes information.

- Teleportation of a laser beam with embedded radio signal (Bowen et al., 2003): The teleportation of a laser beam from one part of a lab to another has been demonstrated. Investigators embedded a radio signal into a laser beam, then disintegrated the beam and reassembled it a meter away, virtually instantaneously. The laser beam was destroyed in the teleportation process, but the radio signal survived. The laser light at one end of an optical communications system was disassembled and its replica was recreated elsewhere in the lab. Even though the laser beam did not survive teleportation, its encoded message did. This system could be used to transport secure data, such that it could become possible to construct a perfect cryptography system. When two parties want to communicate with one another, one can enable the secrecy of the communication to be absolutely perfect.

- Entanglement and Teleportation of a Macroscopic Ensemble of Atoms (Julsgaard et al., 2001): Expanding upon the earlier work of Hald et al. (1999) and Sackett et al. (2000), investigators experimentally demonstrated the entanglement of two macroscopic objects, each consisting of a cesium gas sample containing $\approx 10^{12}$ atoms. Entanglement is generated via interaction of the samples with a pulse of light, which performs a non-local Bell measurement on the collective spins of the samples. The entangled spin-state can be maintained for 0.5 milliseconds. The teleportation of macro-ensemble atom quantum states is expected to follow this experiment. This work is evolving towards the experimental demonstration of the Bose and Home (2002) proposal, which proved that there is a single generic process that can entangle and teleport any atoms, ions and macroscopic objects.

- Entanglement/teleportation of internal state and external motion information of atoms (Opatrný and Kurizki, 2001): Investigators propose an experiment for transmitting an atom's full information, including its "external" states, such as its energy of motion. This procedure replicates the quantum features of the external motion of a particle. For example, if particle-to-be-teleported C yielded a diffraction pattern after passing through two slits, then the same pattern would be produced by particle B, which receives the teleported information. The researchers propose the following idea: Dissociate a very cold molecule with a laser pulse into two atoms (called A and B). Then manipulate the two atoms so that they become entangled: each one is in a fuzzy state individually, but has a precisely defined relationship with its partner. Then let one of the entangled particles (such as A) collide with particle C, whose unknown state should be teleported. After their collision, the momentum values of the collision partners A and C are measured. With that information, the researchers know how to "kick" and deflect atom B, so that the motion of B precisely emulates that of particle C. The investigators say that state-of-the-art equipment for studying atomic collisions and quantum effects makes this experiment difficult, but feasible, to do. If this proposal proves to be correct, then the implication is that it will become possible to experimentally expand this concept to the teleportation of a large ensemble of atoms, such that the entire physical motion and quantum states of the ensemble can be teleported. This could lead to the future development of a teleportation process similar to what was discussed in Section 3.1.

- Laser-like Amplification of Entangled Particles and Entangled-Photon Lasers (Lamas-Linares et al., 2001): Entangled particles are notoriously difficult to create in bulk. To create entangled photons, for example, researchers use the parametric down-conversion technique to send laser light through a barium borate crystal. Passing through the crystal, a photon sometimes splits into two entangled photons (each with half the energy of the initial photon). However, this only occurs for one in every ten billion incoming photons. To increase the yield, researchers added a step: they put mirrors beyond the crystal so that the laser pulse and entangled pair could reflect, and have the chance to interact. The entangled pair and reflected laser pulse interfere constructively to generate fourfold more two-photon pairs or interfere destructively to create zero pairs. Following these steps, the researchers increased production of two-photon entangled pairs, and also of more rare states such as four-photon entangled quartets. This achievement could represent a step towards an entangled-photon laser, which would repeatedly amplify entangled particles to create greater yields than previously possible, and also towards the creation of new and more complex kinds of entangled states.

This list is by no means complete as new developments in this field continue to arise.

3.3 Conclusion and Recommendations

Given the incredible advancements that have been made in the entanglement and teleportation of macroscopic objects the size of 10^{12} atoms, we are still very far away from being able to entangle and teleport human beings (and even simpler biological entities such as cells, etc.) and bulk inanimate objects (tools, technical equipment, pencils and pens, weapons platforms, communications devices, personal hygiene supplies, etc.). There still remain four essential problems:

- One needs an entangled pair of such bulk objects.
- The bulk objects to be entangled and teleported must be in a pure quantum state (as in a Bose-Einstein condensate, for example). And pure quantum states are very fragile.
- The bulk objects to be entangled and teleported must be extremely isolated from the environment to prevent the onset of decoherence.
- The Bell-state measurement of animate or inanimate objects during entanglement/teleportation will require extracting an amount of information (in bits) that equals or exceeds the number of atoms contained within the object. This infers that the computer storage and processing requirements to entangle and teleport a complete bulk object will be astronomically huge (recall the discussion in Section 3.1).

It is difficult to imagine how we can achieve an extreme level of environmental isolation for an object, let alone a living being that breathes air and radiates heat. Experiments with atoms and larger objects must be done in a high vacuum to avoid collisions with molecules. Thermal radiation from the walls of a teleportation apparatus would easily disturb a tiny amount of matter. At present, decoherence imposes a fundamental limit on quantum entanglement and teleportation. Decoherence is the primary reason why we do not routinely see any quantum effects in our everyday world. Research is continuing on whether decoherence can be reduced, circumvented, or otherwise be eliminated. And some minor progress has been made in that direction.

In q-Teleportation it is the ***quantum states*** of the objects that are destroyed and recreated, and not the objects themselves. Therefore, q-Teleportation ***cannot*** teleport animate or inanimate matter (or energy) in its physical entirety. However, some experts argue that because an object's quantum state is its defining characteristic, teleporting its quantum state is completely ***equivalent*** to teleporting the object, even though the original object's quantum state (and defining characteristic) was completely destroyed in the process. This goes to the heart of what is meant by identity. When an object has all the right properties and features, it will be the same object that one observes whether it was observed now or 24 hours ago. Quantum physics reinforces the point that objects of the same type in the same quantum state are indistinguishable from each other. One should, according to this quantum principle, be able to swap all the atoms in a particular object with the same atoms from a mound of raw materials, and reproduce the original object's quantum states exactly with the end result that the new object is identical to the original. Last, we do not know how to put a human being into a pure quantum state or what doing so would mean for biological functioning (including brain function), but we do know how to put $\leq 10^{12}$ gas atoms/ions and a beam of photons into a pure state in practice. Further research will be required to ascertain whether microbiological and higher-level biological systems, in addition to bulk inanimate matter, can be put into pure quantum states and entangled/teleported.

To perform a Bell-state measurement on (bulk) animate or inanimate objects, during the entanglement/teleportation process, to extract and encode its information will require extracting an amount of information (in bits) that equals or exceeds the number of atoms contained within the object. An object containing a few grams of matter will require the extraction of $> 10^{28}$ bits of data. A simple virus of $\approx 10^7$ atoms would require the extraction of $\geq 10^8$ bits of information during the entanglement/teleportation process, whereas the extraction of a minimum of 10^{28} kilobytes will be required to encode and store an entire human being. This is beyond the capability of present digital electronic computer technology to store and process. It is difficult to see how far computer technology will advance towards meeting this requirement.

It is difficult to fathom what will be in store for the teleportation of human beings given some possible future technology. What about the effects of the q-Teleportation process on the human consciousness, memories and dreams, and the spirit or soul? We know from quantum physics that "the whole is greater than the sum of its parts." So what happens to the fundamental characteristics of a human being when he/she steps into the teleporter-transmitter, where their quantum states (i.e., their complete identity) are destroyed during the quantum entanglement/teleportation process, and then their copy is created at the teleporter-receiver an instant later? What will things be like during the entanglement process? Will a teleported individual's consciousness, memories and dreams, and spirit/soul be successfully and accurately teleported or not? This is a major ethical and technical question that will have to be addressed by future research.

•**Recommendations**:

- Broad-spectrum Quantum Computing Technology Development Program: At present, the Quantum Information Science Program (QISP) is coordinated by the U.S. Army Research Office with funding and support from the Army, the National Security Agency, DARPA, and the Office of the Deputy Director of Defense for Research and Engineering. The Naval Research Lab and the CIA are both involved in their own programs. The CIA vets new commercial development of computer technology and computer information processing via its In-Q-Tel company (reference 44). This includes R&D on quantum entanglement and teleportation for computer, information processing and secure communications. QISP was funded for $19 million in 1999. The program involves 34 projects by researchers at 21 universities, three government laboratories and two corporate laboratories. QISP goals include building a quantum computer, developing quantum information processing, and further advances in quantum teleportation. The AFRL should join QISP and provide partnership funding on the order of $1 million per year. An alternative to this would be for AFRL to collaborate with In-Q-Tel and participate in its technology R&D venture capital programs. This R&D investment would allow the Air Force to acquire very advanced quantum physics and related technological applications that can support its mission. The R&D investment benefits would include the development and implementation of quantum computing/information processing and secured quantum communications technology, which can significantly enhance the performance and security of Air Force computing and communication systems infrastructure, and aerospace weapons systems.

- Quantum Cryptography: A dedicated research program should be implemented to develop a mature quantum cryptography technology. Theoretical and experimental work is in progress among a small number of select groups (QISP, In-Q-Tel, universities, etc.), but this field is not advancing fast enough for practical applications to become available to meet increasing adversarial threats against secured military and intelligence communications. The goal of proposed quantum cryptography research is to bring the theoretical and experimental foundation of quantum cryptography and secure quantum information processing to maturity, and to fully develop and implement quantum entanglement/teleportation-based cryptography technology. Recent experimental work has demonstrated that a completely secure quantum key can be generated and distributed for the communication and decoding of encrypted messages using entangled photons. Any eavesdropper's attempt to intercept the quantum key will alter the contents in a detectable way, enabling users to discard the compromised parts of the data. There is much more work that needs to be done in this area. I recommend that the AFRL implement a

$1 million/year program for five years in order to advance the state-of-art in quantum cryptography technology.

- Quantum Decoherence: Decoherence is the primary reason why we do not routinely see any quantum effects in our everyday world. And it imposes a fundamental limit on quantum entanglement and teleportation via the interaction between entangled/teleported quantum systems and their local environment. In order to advance quantum entanglement/teleportation physics and develop applied technologies, it is necessary that a research program be implemented by the AFRL to explore whether decoherence can be significantly reduced, circumvented, or otherwise be eliminated. An insufficient number of small university groups have slowly made minor progress in this direction. I recommend that a $500,000 - 750,000 per year R&D program be conducted for five years to overcome this technical challenge.

- Pure Quantum States: In order to entangle and teleport quantum particles and bulk objects, they both must be prepared in a pure quantum state. And pure quantum states are very fragile to decoherence. A technical challenge for entanglement/teleportation physics is whether the requirement for pure quantum states can be relaxed and how much decoherence will play a role in this situation, what technical challenges will arise when increasing the size of entangled/teleported matter to larger macroscopic scale ($\gg 10^{12}$ atoms), and whether matter of mixed composition (such as a gas or Bose-Einstein condensate of mixed atomic elements) can be entangled/teleported in both pure and mixed quantum states. I recommend that a $250,000 – 500,000 per year research program be conducted for five years to study this problem.

- Entangling Bulk Matter and Bell-State Measurement to Extract Information: Recent experiments demonstrated the entanglement of two macroscopic objects, each consisting of a cesium gas sample containing $\approx 10^{12}$ atoms. Entanglement was generated via interaction of the samples with a pulse of light, which performs a non-local Bell measurement on the collective spins of the samples. In order to push the envelope on this development and take it to higher practical levels, it will be necessary to ascertain the limit on the size and composition of bulk matter entanglement (given the decoherence and pure-state constraints); and to determine what other quantum states can be used for entanglement, what other Bell-state measurement techniques can be used, and whether multiple quantum states can be entangled. The chief technical challenge is the computer technology that will be required to facilitate the huge amount of data that must be extracted, processed and stored from bulk matter quantum states during the Bell-state measurement process. I recommend that a $500,000 – 1 million per year research program be implemented for five years in order to explore these questions and ascertain what solutions may be technically available, and to develop such solutions.

- Biological Quantum Teleportation: The Mavromatos et al. (2002) theoretical model for biological entanglement and teleportation is a remarkable concept that could result in the development of a workable physics theory of consciousness. The model has potential applications to advanced quantum computing/information processing physics and the physics of psi phenomena (see Chapter 5). A research program should be implemented to continue the Mavromatos et al. (2002) work and bring their model to theoretical maturity. It is recommended that this program be funded at $500,000 – 800,000 per year for five years. A parallel or follow-up program should be implemented to experimentally test this model and ascertain any useful technological applications. One application that should be explored in the proposed research program is advanced, ultra-fast, ultra-high-capacity quantum computing and information processing using natural and/or artificial biological systems. The parallel or follow-up experimental research program should be funded at $800,000 – 1.5 million per year for five years.

- FTL Communication: Experiments verifying that EPR entanglement obeys Special Relativity (Seife, 2000; Scarani et al., 2000; Gisin et al., 2000; Zbinden et al., 2000a, b) determined that quantum information via EPR photon pair entanglement must travel > 10^7 times light speed. Can this mechanism be exploited to achieve FTL communication? If so, then the potential military and commercial applications will be revolutionary, and the science and industry of communications will be forever transformed. A comprehensive theoretical and experimental research program should be implemented to answer this question. It is recommended that this program be funded at $700,000 – 1 million per year for five years. A modest experiment definition study should be funded at $80,000 for one year to delineate the most promising experimental approaches to be used for the larger research program. [There is much controversy and debate over FTL (a.k.a. superluminal) signals/communication, and the reader should see the selected superluminal references in the Teleportation References section of this study.]

➢ New Entanglement/Teleportation Breakthroughs: The most exciting developments in quantum teleportation physics has included the teleportation of a laser beam with an embedded radio signal, the teleportation of squeezed states of light (and hence, continuous quantum state variables), the teleportation of photon states to atoms/ions (from light to matter!), the entanglement of two similar/dissimilar quantum particles that are created by two (independently) different particle sources, the laser-like amplification of entangled particle/photon pairs, parametric down-conversion entanglement and teleportation (of discrete quantum state variables), quantum cryptography with unbreakable keys, the teleportation of quantum information at speeds > 10^7 times light speed, the entanglement and teleportation of macroscopic (10^{12} atoms) matter quantum states, etc. There is also the yet-untested proposal to entangle/teleport the external physical motion and internal quantum state information of atoms. This shows that quantum physics sets no apparent limit on what it is that can be teleported/entangled and how it is to be teleported/entangled, or where it is to be teleported/entangled. At present teleportation technology requires fiber optic and coaxial cables to teleport quantum state information from one location to another. Can we avoid the use of cables and teleport through free space? [Note: Before this report went to press, Aspelmeyer et al. (2003) reported their outdoor experiment that demonstrated the distribution of quantum entanglement (of laser photons) via optical free-space links to independent receivers separated by 600 m across the Danube River (during inclement nighttime weather), with no line of sight between them. This experiment is revolutionary and begins the step toward conducting satellite-based distributed quantum entanglement.] We have not discovered all the possibilities that nature has in store for us. The present breakthrough discoveries will likely introduce novel military and intelligence technology applications in the near and far future. But further R&D must be conducted in order to discover new applications for these recent breakthroughs, to make additional breakthroughs and discoveries, and to advance the state-of-art in quantum teleportation physics to meet future challenges to the Air Force mission. I recommend that a two-track R&D program be implemented over five years. The first track should be funded at $250,000 – 750,000 per year for the purpose of developing new entanglement/teleportation breakthroughs in quantum teleportation physics. The second track should be funded at $750,000 – 1.5 million per year for the purpose of developing applications for any new breakthroughs with the proviso that such applications benefit the Air Force mission and have commercial dual-use capability to leverage advance technology in the private sector.

4.0 e-TELEPORTATION

4.1 Extra Space Dimensions and Parallel Universes/Spaces

A literature search for proposed e-Teleportation concepts based on the conveyance of objects through extra space dimensions and/or parallel universes/spaces has yielded only one result (see Section 4.2). The present state-of-art in research on parallel universes/spaces and extra space dimensions has been strictly limited to the work on developing a grand unified quantum field theory and a quantum theory of gravity, whereby the former necessarily includes the latter. Quantum gravity/unified field theory research has been evolving since the 1920s when Kaluza and Klein published the first papers to describe a model for the unification of gravity with electrodynamics. Many of the more prominent theories today invoke extra spatial dimensions, the existence of parallel universes/spaces, or both in order to quantise gravity and/or to unify gravity with the other forces of nature. It is beyond the scope of this study to provide an in-depth review of all of the research that has been done in this area, so we list below a select few of the historically prominent models that have largely gained a secure foothold in present-day research:

- Kaluza-Klein Electromagnetic-Gravity Unification Theory/Modern Kaluza-Klein Gravity Theories (Kaluza, 1921; Klein, 1926; de Sabbata and Schmutzer, 1983; Lee, 1984; Appelquist et al., 1987; Kaku, 1993, 1994; Overduin and Wesson, 1998): It was originally suggested that Maxwellian electrodynamics and Einstein gravitation could be unified in a theory of five-dimensional Riemannian geometry, where the gravitational and electromagnetic potentials together would determine the structure of spacetime. The fifth space dimension is curled up into a ball of space with a radius slightly larger than 10^{-35} m, and it was originally regarded as having no physical significance because it was simply a mathematical tool used to catalyze unification. At present, the generic name of Kaluza-Klein stands for a wide variety of approaches to quantising and unifying gravitation with other quantum fields using any number of dimensions greater than four.

- Superstring Theories (Green, 1985; Kaku, 1988, 1993, 1994): These theories come in a wide variety of interrelated concepts, and they are a highly evolved form of Kaluza-Klein theories. They are based on the dynamics of string-like fundamental quanta, whereby the observed fundamental particles are manifested by the vibrational ground or excitation states of a quantum string (open or closed loop). The superstrings are $\approx 10^{-35}$ m (i.e., the Planck length) in size. There are different versions of these theories that require ten, eleven or twenty-six extra space dimensions to unify and quantise gravity, whereby the extra dimensions are curled up (i.e., compactified) into balls of space with a radius $< 10^{-35}$ m. These theories later evolved into versions that are now called F- and M-theory. The mathematics behind this class of theories is very ugly, and it is difficult for even the best superstring theorists to make simple or sophisticated calculations and predictions. And so far, this class of quantum gravity theories has escaped experimental verification.

- D-Brane and 3-Brane Theories/Parallel Spaces (Rubakov and Shaposhnikov, 1983a, b; Polchinski, 1995; Antoniadis et al., 1998; Randall and Sundrum, 1999a, b; Weiss, 2000; Pease, 2001; Arkani-Hamed et al., 1998, 2000, 2002): D-brane theory is a recent incarnation of the original superstring theories in which open strings, corresponding to the fundamental particles of the standard model (quarks, leptons, gauge bosons), have their free ends stuck on a (hypersurface) membrane called a D-brane (D = Dirichlet boundary conditions). But the graviton, which corresponds to a closed loop of string, can propagate in all the dimensions. It provides both unification and quantization of gravity by assuming that there are n new spatial dimensions in addition to the three infinite spatial dimensions we know about. And the extra space dimensions are $\approx 10^{-35}$ m in extent. A very recent alternative version of this model is called "3-brane" theory. In this theory, each of the n extra space dimensions is of finite extent $R \approx 2\times10^{(32/n)-17}$ centimeters. The space spanned by the new dimensions is called "the bulk." In this theory, the particles of the standard model live within our familiar realm of three spatial dimensions, which forms a three-dimensional (hypersurface) membrane or "3-brane" within the bulk. The propagation of electroweak and strong nuclear forces is then confined to our 3-brane. However, at distances (r) less than R, gravity (via gravitons) propagates in the full $(3 + n)$-dimensional space, whereby its strength falls as $r^{-(2+n)}$ with increasing separation r. When $r > R$, the gravitational force reverts to its normal Newtonian r^{-2} falloff because there is no longer any extra-dimensional space for it to spread into. If $n = 1$, then the size of the extra-dimension would have to be $R \approx 2\times10^{15}$ cm (or 2×10^{10} km = 133.3 AU; 1 AU = 1.5×10^{8} km is the mean Earth-Sun distance) in order to account for the weakness of gravity, but an extra space dimension this large would have already made itself obvious in the observed dynamics of the solar system. For this reason, investigators have discounted the possibility that $n = 1$. If $n = 2$, then the size of both extra space dimensions would have to be $R \approx 0.2$ cm (or 2 mm). In any case, inconspicuous neighboring 3-branes may be separated from the 3-brane we live on by only a fraction of a millimeter, or even much smaller distances, across the higher-dimensional bulk. Such neighboring 3-branes may be distant folds of our own 3-brane, with the same physics, but able to influence us across shortcuts through the bulk. Or they may be completely separate 3-branes possessing their own fundamental laws and parameters of nature that are completely different from our own. Several tabletop Cavendish-type experiments are now looking for sub-millimeter deviations from Newtonian gravitation as a first step towards verifying 3-brane theory, and other experiments are now being planned or are already underway (Pease, 2001). At present the preliminary experimental results have been negative for the existence of extra space dimensions, and the experimental data suggests that two extra space dimensions are now constrained to length scales << 0.2 – 0.3 millimeters while seven extra space dimensions can be no larger than 2 femtometers (Pease, 2001).

- Parallel Universes/Parallel Spaces (Everett, 1957; Wheeler, 1957, 1962; DeWitt, 1970; DeWitt and Graham, 1973; Jammer, 1974; Davies, 1980; Wolf, 1988; Kaku, 1994; Visser, 1995 and Section 2.1): There are only two other research tracts that are concerned with parallel universes besides 3-brane theory. The first tract is the traversable wormhole research that was discussed in Section 2.1. Traversable wormholes can connect many different universes in the "multiverse" (i.e., a conglomeration of many universes), and these are called inter-universe wormholes. However, traversable wormhole physics (a.k.a. Einstein's General Relativity Theory) does not provide a physical prescription for the existence and nature (i.e., fundamental parameters and physical laws) of other putative universes. The difference between inter-universe and intra-universe (i.e., two distant regions of one universe are connected with each other) wormholes arises only at the level of global geometry and global topology. Local physics near the throat of a traversable wormhole is insensitive to issues of intra-universal or inter-universal travel. An observer in the vicinity of the throat, while making local measurements, would not be able to tell whether he was traveling to another universe or to a remote part of our own universe. And one cannot rely on the topological (as opposed to geometrical) information to determine which is the case, because topological information is not enough to uniquely characterize an inter-universe connection. And General Relativity Theory does not fix the topology of spacetime, so we cannot ascertain the existence of other universes. [Note: Traversable wormholes are also geometrically possible for higher dimensional spaces.] The second tract is the "Many Worlds" interpretation of quantum theory. This version of quantum theory requires the simultaneous existence of an infinite number of equally real worlds, all of which are more-or-less causally disjoint, in order to interpret consistently the relationship between observed phenomena and observers. The theory was proposed in an attempt to overcome a number of deep paradoxes inherent in the interpretation of the theory of measurement and quantum theory. The Many Worlds theory argues that quantum theory requires the existence of a "superspace" of worlds spanning the range of all possible quantum observations (or quantum measurements). Through our acts of measurement we are imagined to trace a path through the mesh of possible outcomes. All the "worlds" are causally disjoint, and the uncertainty of quantum observation can be interpreted as an artifact of our access to such a limited portion of the superspace of possible worlds. The evolution in the superspace as a whole is entirely deterministic.

At present, none of the theoretical concepts outlined above have been brought to a level of technical maturity, where it becomes meaningful to ascertain whether any form of e-Teleportation is theoretically possible between extra space dimensions and different or parallel universes/spaces. However, as mentioned in the item on parallel universes/parallel spaces, there is the exception that traversable wormholes (three- and higher-dimensional) provide a solid physics principle for the implementation of teleportation between parallel universes/spaces. And traversable wormholes can be devised to connect 3-branes together. See Section 2.1 for the discussion on teleportation via traversable wormholes. Also, Kaluza-Klein theories, superstring theories and D-brane theory all have the common feature that their extra space dimensions are $\leq 10^{-35}$ m in extent, which makes it impossible for any useful form of macroscopic-level teleportation to occur between space dimensions. Last, it is not yet possible to do theoretical calculations or even experimentally verify most of these theories. Three-brane theory is the best parallel space theory there is, with the possibility that macroscopic-level teleportation is possible between space dimensions (only if the extra space dimension(s) has length scale(s) >> millimeters). But this theory is still in the stage of maturing theoretically and achieving experimental verification (or falsification). Therefore, we can go no further in this section.

4.2 Vacuum Hole Teleportation

An unusual teleportation concept has been proposed by Leshan (1999, 2002), which describes the teleportation of objects throughout our universe by using the geometrical properties of spacetime. The proposal posits that there is a "zero-space" that exists outside the boundary of our universe, whereby this zero-space is a "point form" space, where the distance between any two points is always equal to zero. Leshan also calls this space a "hole." Further requirements and assumptions of the model are:

- ☐ time does not exist as a property in zero-space
- ☐ the cosmological principle (i.e., there are no privileged frames relative to another place or point in the universe) requires that the boundary or border of the universe must pass through every point of space
- ☐ virtual holes (or zero-space) in spacetime must exist at every point of the universe, which are also called "vacuum holes"
- ☐ vacuum holes exist as virtual particles

The last item is interesting because it implicitly says that vacuum holes (a.k.a. zero-space) must also be virtual particles, and in Section 2.2 we showed that virtual particles are a representation of the vacuum ZPF. Therefore, this infers that vacuum holes can be considered to be vacuum zero-point fluctuations in

Leshan's model. Thus, a teleportation mechanism can arise in this model because distances between zero-space and any other point in the universe are zero, so that the vacuum holes can potentially exist at every point in the universe simultaneously. Therefore, if an object is sent "out of the universe" and into a vacuum hole (a.k.a. zero-space), then the object can appear at random at any spacetime point in the universe.

The mechanism for teleportation in this model is:

- to send an object outside of the universe by creating a closed surface (i.e., "hole sphere"), which consists of vacuum holes, around the object;
- while inside the hole sphere, the object then ceases to exist because objects cannot really exist outside of the universe;
- however, the object simultaneously exists at any other remote location in the universe (via the cosmological principle) at the instant it became enclosed by the hole sphere;
- therefore, it has been teleported to some remote location in the universe

Leshan points out that the teleportation device must curve spacetime so that the starting and destination points in the universe coincide, and the curved geometry must be similar to that of a black hole for an instant, so that a channel between the two points can be formed. (This sounds suspiciously like creating a traversable wormhole via an Einstein-Rosen bridge, which can be made traversable by perturbing the Schwarzschild spacetime metric an infinitesimal amount.) There is no space to traverse, so therefore there will be no passage of time during teleportation. The only expenditure of energy in this teleportation scheme is the energy that will be needed to curve spacetime.

This teleportation concept is very convoluted. Leshan does not offer any further explanations that are useful nor does he offer any precise technical description for the vacuum holes, and how they are to be produced and manipulated. There is also no mathematical physics derivation published by Leshan to support this concept. I am totally unable to evaluate this concept in the absence of a rigorous theoretical framework. This concept is too sketchy and full of technical "holes" to seriously consider it any further for this study. The reader should note that it has already been demonstrated that traversable wormholes are the best physical principle available to implement teleportation between universes and extra space dimensions.

4.3 Conclusion and Recommendations

At present, none of the theoretical concepts explored in this chapter have been brought to a level of technical maturity, where it becomes meaningful to ascertain whether any form of e-Teleportation is theoretically possible between extra space dimensions and different or parallel universes/spaces. However, there is the exception that traversable wormholes (three- and higher-dimensional) provide a solid physics principle for the implementation of teleportation between parallel universes/spaces. And traversable wormholes can be devised to connect 3-branes together. Kaluza-Klein, superstring and D-brane theories do not allow for any useful form of macroscopic-level teleportation to occur between space dimensions, because these theories require that the extra space dimensions be $\leq 10^{-35}$ m in extent. Last, it is not yet possible to do theoretical calculations to make predictions or even to experimentally verify most of these theories. Three-brane theory is the best parallel space theory there is with the possibility that macroscopic-level teleportation is possible between space dimensions. But this theory is still in the stage of maturing theoretically and getting experimental verification.

•**Recommendations**:

- The recommendations outlined in Section 2.3 are relevant to the investigation of the possibility for e-Teleportation.

5.0 p-TELEPORTATION

5.1 PK Phenomenon

P-Teleportation is a form of psychokinesis (or PK) similar to telekinesis but generally used to designate the movement of objects (called apports) through other physical objects or over great distances. Telekinesis is a form of PK, which describes the movement of stationary objects without the use of any known physical force. And PK is essentially the direct influence of mind on matter without any known intermediate physical energy or instrumentation. Rigorously controlled modern scientific laboratory PK, and related psychic (a.k.a. "psi", "paranormal" or parapsychology), research has been performed and/or documented by Rhine (1970), Schmidt (1974), Mitchell (1974a, b, see also the references cited therein), Swann (1974), Puthoff and Targ (1974, 1975), Hasted et al. (1975), Targ and Puthoff (1977), Nash (1978, see also the references cited therein), Shigemi et al. (1978), Hasted (1979), Houck (1984a), Wolman et al. (1986, see also the references cited therein), Schmidt (1987), Alexander et al. (1990), Giroldini (1991), Gissurarson (1992), Radin (1997, see also the references cited therein), Tart et al. (2002), Shoup (2002), and Alexander (2003).

A well-known theoretical/experimental/operational program directed by H. E. Puthoff, R. Targ, E. May and I. Swann was conducted at SRI International and the NSA, and sponsored at various times by the Central Intelligence Agency (CIA), the Defense Intelligence Agency (DIA), and the Army Intelligence and Security Command (INSCOM) over more than two decades; and the program was later carried on by E. May at SAIC (Alexander, 1980; Puthoff, 1996; Targ, 1996; Schnabel, 1997; Tart et al., 2002). This was called the Remote Viewing program, and it was a compartmentalized special access program possessing a variety of codenames during its 22 years of operation. Remote viewing involves precognition and clairvoyance, and it allows a practitioner to acquire information irrespective of intervening distance or time. The Remote Viewing program ended in 1994 and President W. J. Clinton officially declassified it in 1995. The reader should note that the very first U. S. military-intelligence R&D programs on psi, PK and mind control were conducted by H. K. (Andrija) Puharich, M.D., L.L.D during his military service at the Army Chemical and Biological Warfare Center at Fort Detrick, Maryland in the 1940s-50s. Puharich had an interest in clairvoyance and PK, and dabbled in theories for electronically and pharmaceutically enhancing and synthesizing psychic abilities. While in the Army, Puharich took part in a variety of parapsychology experiments, and he lectured Army, Air Force and Navy groups on possibilities for mind warfare. He was a recognized expert in hypnotism and microelectronics.

PK phenomenon was also explored in the Remote Viewing program. Col. J. B. Alexander (USA ret.) credits professional aerospace engineer Jack Houck for "capturing PK phenomenon and transitioning it into an observable form" (Houck, 1982, 1984a, b; Alexander et al., 1990; Alexander, 2003). During the past three decades, Houck (along with Alexander) held a number of PK sessions, whereby attendees are taught the PK induction process, and initiate their own PK events using various metal specimens (forks, spoons, etc.). Individuals were able to completely bend or contort their metal specimens with no physical force being applied whatsoever. Numerous government science advisors and senior military officials took part in and/or witnessed these events, which took place at the Pentagon, at officers' or scientists' homes, and at one quarterly INSCOM retreat attended by the commanding general and a group of colonels and generals commanding INSCOM units around the globe. Spontaneous deformation of the metal specimens was observed at the PK session conducted during the INSCOM retreat, causing a great deal of excitement among those present. Other notable trained observers were also present at this session, and they critically reviewed the events. Psychic Uri Geller (1975) is the original model for demonstrating

PK metal bending. During a talk that he gave at the U.S. Capitol building, Uri caused a spoon to curve upward with no force applied, and then the spoon continued to bend after he put it back down and continued with his talk (Alexander, 1996). Jack Houck continues doing extensive experimental work and data collection on micro- and macro-PK phenomena. Scientifically controlled PK experiments at the Princeton University Engineering Anomalies Research Laboratory were conducted by Robert Jahn (Dean Emeritus of the School of Engineering), who reported that repeatedly consistent results in mentally affecting material substances has been demonstrated in the lab (Jahn and Dunne, 1987). In the 1980s, Jahn attended a meeting on the PK topic at the Naval Research Laboratory, and warned that foreign adversaries could exploit micro- or macro-PK to induce U.S. military fighter pilots to lose control of their aircraft and crash.

Very early investigations of, and experiments on, p-Teleportation occurred during the 19th and early 20th centuries. Many cases that were studied, and the experiments that were performed, were undoubtedly due to fraud, and few experiments have occurred under controlled conditions during that period. However, most of the credible, scientific reports of p-Teleportation phenomenon and related (controlled) experiments occurred in the late 20th century (see for example, Alexander et al., 1990; Radin, 1997). Some of that scientific work involved the investigation of Uri Geller and a variety of other recurrent spontaneous PK phenomena (Hasted et al., 1975; Puthoff and Targ, 1975; Targ and Puthoff, 1977; Nash, 1978; Wolman et al., 1986). Psychics Uri Geller (1975) and Ray Stanford (1974) claimed to have been teleported on several occasions. Most claimed instances of human teleportation of the body from one place to another have been unwitnessed. There are also a small number of credible reports of individuals who reported being teleported to/from UFOs during a UFO close encounter, which were scientifically investigated (Vallee, 1988, 1990, 1997). But there are a larger number of such reports that are anecdotal, whereby the witness data tends to be unreliable. However, we will confine our discussion to the controlled laboratory experiments that have been performed and reported.

One of the more interesting examples of controlled experiments with Uri Geller was one in which he was able to cause a part of a vanadium carbide crystal to vanish (Hasted et al., 1975). The crystal was encapsulated so it could not be touched, and it was placed in such a way that it could not be switched with another crystal by sleight of hand. A more spectacular series of rigorously controlled (and repeatable!) laboratory experiments occurred in the Peoples Republic of China (PRC). In September 1981, an extraordinary paper was published in the PRC in the journal Ziran Zazhi (transl.: Nature Journal), and this paper was entitled, "Some Experiments on the Transfer of Objects Performed by Unusual Abilities of the Human Body" (Shuhuang et al., 1981). The paper reported that gifted children were able to cause the apparent teleportation of small objects (radio micro-transmitters, photosensitive paper, mechanical watches, horseflies, other insects, etc.) from one location to another (that was meters away) without them ever touching the objects beforehand. The experiments were operated under exceptionally well-controlled conditions (both blind and double-blind). The researchers involved included not only observers from various PRC colleges and medical research institutes, but also representatives from the PRC National Defense Science Commission. Because of the involvement of the latter, it was deemed necessary that an unclassified Intelligence Information Report be prepared by the DIA (see Shuhuang et al., 1981), which included a detailed English translation of the article.

Additional research carried out by the Aerospace Medicine Engineering Institute in Beijing was reported in the July 1990 issue of the Chinese Journal of Somatic Science (Kongzhi et al., 1990; Jinggen et al., 1990; Banghui, 1990), which was also translated into English by the DIA. Reported in several articles are experiments involving the videotaping and high-speed photography of the transfer of test specimens (nuts, bundles of matches, pills, nails, thread, photosensitive paper, chemically treated paper, sponges dipped in $FeCl_3$, etc.) through the walls of sealed paper envelopes, double layered KCNS type paper bags, sealed glass bottles and tubes with sealed caps, and sealed plastic film canisters without the walls of any of these containers being breached. All of the Chinese experiments reported using gifted children and young adults, who possessed well-known extraordinary PK ability, to cause the teleportation of the various test specimens. In all the experimental cases that were reported, the test specimens that were teleported were completely unaltered or unchanged from their initial state, even the insects were unaffected by being teleported. The experiments were well controlled, scientifically recorded, and the experimental results were always repeatable.

The Chinese papers are all extremely interesting and very well written, and they show photographs and schematic diagrams of the various experimental setups. The experimental protocols were explained in lengthy detail, and thorough data and statistical analysis were presented in the results. The combined results from the several Chinese experiments showed that:

- different research groups designed different experimental protocols, used different gifted psychics, used different sealed containers, and used different test specimens (live insects, bulk inanimate objects, and even radio micro-transmitters were used to track the location of the specimens) that were to be teleported;

- the time required for the teleportation of test specimens through various barriers was anywhere from a fraction of a second to several minutes, and this was not dependent on the test specimen that was used, the sealed container that was used (or its barrier thickness), which experimental protocol was used, or which psychic was being used

- the high-speed photography/videotaping recorded in one series of experiments that test specimens would physically "meld" or blend with the walls of sealed containers; and recorded in a different series of experiments that test specimens would simply disappear from inside the container only to reappear at another location (after seconds to several minutes of time transpired), such that the test specimen did not actually undergo total material disintegration/reintegration during teleportation – this data is important, because without the aid of electronic monitoring instruments, the average person's sensory organs and usual methods of detection are temporarily unable to perceive the test specimen's (ambiguous) existence during the teleportation process;

- the radio micro-transmitter used as a test specimen in one series of experiments (Shuhuang et al., 1981) transmitted a radio signal to several stationary electronic instruments/receivers, so that the specimen could be tracked and monitored (via signal amplitude and frequency measurements) during the teleportation process; the experimenters discovered that there was large fluctuations in the intensity (in both amplitude and frequency) of the monitored signal to the effect that it would either completely disappear or become extremely weak (to the extent that the monitoring instruments could scarcely detect it) – it was discovered that there was a definite correlation between the change in strength (i.e., radical frequency shifts were observed) of the monitored radio signal and the teleportation of the test specimen, such that the weak or absent signal indicated that the specimen was "nonexistent" (or in an altered physical state) during teleportation (note: the monitored signal amplitude and frequency of the micro-transmitter specimen were stable before and after teleportation);

- before and after "passing through the container wall/barrier", the test specimen and the container's wall/barrier are both complete solid objects;

- the gifted psychics were never allowed to see (they were blindfolded in many experiments) or touch each of the test specimens or the sealed containers before and after experiments were conducted, and only the experimenters touched the specimens and containers (using both blind and double-blind protocols);

- the experimental results were all repeatable

- the conditions for fraud and sleight of hand were totally eliminated, and multiple independent outside witnesses (technical and military-intelligence experts) were present at all times to ensure total fidelity of the experiments

The experimental radio micro-transmitter and high-speed photography/videotaping data offer an important clue on what the teleportation mechanism is, and this will be discussed further in Section 5.1.1. The Chinese were unable to offer any significant physics hypothesis that could explain their results. Some researchers stated that it is necessary to invoke a new physics, which somehow unifies the human consciousness (i.e., physics of consciousness) with quantum and spacetime physics, in order to understand p-Teleportation and related PK phenomena. The researchers were amazed by their repeated results, and were barely able to fathom the altered "state of being" that test specimens underwent during teleportation.

It is also important to point out that during the Cold War the DIA produced three (now declassified) reports on the parapsychology research of the Soviet Union and its Warsaw Pack allies (LaMothe, 1972; Maire and LaMothe, 1975; DIA Report, 1978; other related studies were reported by Groller, 1986, 1987). The purpose of the reports was to collate and summarize collected intelligence, describe in great detail, and assess the Soviet Union and Warsaw Pact R&D on parapsychology and paraphysics. The reports outlined the history of pre-revolutionary (Czarist) Russian, and WWII and post-WWII era Soviet R&D on psychotronics, human mind/behavior control, and the entire spectrum of parapsychology. The Soviet information also mentions the psychotronic/parapsychology R&D materials that Soviet military forces took from various Nazi research centers in and around Germany at the end of WWII. The entire spectrum of parapsychology phenomena was explored by the Soviets, which resulted in the generation of a wealth of experimental data and related scientific research literature. One DIA report noted that there was an East versus West science debate in the Soviet literature over whether paranormal phenomenon and related experimental data was real or even scientifically sound in comparison to western scientific practice and philosophy. Another DIA report lists the names and affiliations of all the researchers, as well as the names of the various Soviet and Warsaw Pact research centers, that were involved. Also, Pratt (1986) reviews and summarizes the history of Soviet psychotronics research.

The U.S. military-intelligence establishment was concerned with the possibility that the Soviets and their Warsaw Pact allies were conducting psychotronics and mind control R&D in order to discover how to exploit and control powerful phenomena that could be used against the U.S. and its allies. LaMothe (1972) chronicled how the Soviets had been researching methods of influencing human behavior for over sixty years. The Soviets and their allies extensively explored an influence technology that they called "controlled offensive behavior", which is defined as "research on human vulnerability as it applies to methods of influencing or altering human behavior" (LaMothe, 1972). Also, LaMothe (1972) describes the revolutionary techniques the Soviets studied to influence human behavior, which included: sound, light, color, odors, sensory deprivation, sleep, electromagnetic fields, biochemicals, autosuggestion, hypnosis, and parapsychology phenomena (such as psychokinesis, telekinesis, extrasensory perception-ESP, astral projection, clairvoyance, precognition, and dream state, etc.). The LaMothe (1972) report became an aid in the development of countermeasures for the protection of U.S. and/or allied personnel.

Psychotronics is the general term that was used in the former Soviet Union/Warsaw Pact countries to categorize many psychic phenomena undergoing scientific research. The conclusions that were reached in the DIA reports are that within the category of psychotronics, the Soviets identified two discrete skills (LaMothe, 1972):

- bioenergetics: those phenomena associated with the production of objectively detectable effects such as psychokinesis, telekinesis, levitation effects, transformations of energy, i.e. the altering or affecting of matter

- bioinformation: those phenomena associated with the obtaining of information through means other than the normal sensory channels (i.e., ESP), such as telepathy, precognition, and clairvoyance, i.e., using the mind to tap into the thoughts of others or to acquire present or future information about objective events in the world

These phenomena involve using the mind and/or some "field" of the body to affect other minds and inanimate objects irrespective of intervening distance or elapsed time, and without engaging any conventional tools. Bioenergetics and bioinformation are two classifications that form a single branch of science the Soviets preferred to call biocommunications. Soviet biocommunications research is primarily concerned with exploring the existence of a definite group of natural phenomena controlled by laws that are not based on any known (energetic) influence. The types of biocommunication (a.k.a. psychotronics) phenomena includes special sensory biophysical activities, brain and mind control, telepathic communications or bioinformation transceiving, bioluminescent and bioenergetic emissions, and the effects of altered states of consciousness on the human psyche. Psychotronics and remote viewing provide capabilities that have obvious intelligence applications. The Soviets and their Warsaw Pact allies invested millions of dollars in psychotronics R&D because they understood this, and saw the potential payoff for military and intelligence applications.

The U.S. response to Soviet psychotronics R&D programs was the Remote Viewing program. In addition, the U.S. Army began the JEDI Project in 1983, which sought to increase human potential using teachable models of behavioral/physical excellent by unconventional means (Alexander et al., 1990). The JEDI Project was essentially a human-performance modeling experiment based on neuro-linguistic programming (NLP) skills, whereby advanced influence technologies to model excellence in human performance was used. The program ran under the auspices of the Army INSCOM and the Organizational Effectiveness School, and was sponsored by a U.S. government interagency task force. Finally, it should be pointed out that the program had successfully trained several hundred people, including members of Congress (such as Al Gore, Jr. and Tom Downey), before being terminated.

There is a wealth of factual scientific research data from around the world attesting to the physical reality of p-Teleportation and related anomalous psi phenomena (Mitchell, 1974b; Targ and Puthoff, 1977; Nash, 1978; Radin, 1997; Tart et al., 2002). The skeptical reader should not be so quick to dismiss the subject matter in this chapter, because one must remain open-minded about this subject and consider p-Teleportation as worthy of further scientific exploration. The psychotronics topic is controversial within the western scientific community. The debate among scientists and scientific philosophers is highly charged at times, and becomes acrimonious to the point where reputable skeptical scientists cease being impartial by refusing to examine the experimental data or theories, and they prefer to bypass rational discourse by engaging in ad hominem attacks and irrational "armchair" arguments.

P-Teleportation and related phenomena are truly anomalous, and they challenge accepted modern scientific paradigm. Lightman and Gingerich (1991) wrote, "Scientists are reluctant to change paradigms for the purely psychological reasons that the familiar is often more comfortable than the unfamiliar and that inconsistencies in belief are uncomfortable." And theories change over time when anomalies enter the picture. Anomalies are particularly helpful for they point to the inadequacies of an old model and point the way to a new one. Anomalous scientific facts are unexpected and difficult to explain within an existing conceptual framework. Kuhn (1970) describes scientific discovery as a complex process, in which an anomalous fact of nature is recognized, and then followed by a change in conceptual framework (i.e., paradigm) that makes the new fact no longer an anomaly. Kuhn stated that, "Discovery commences with the awareness of anomaly, that is, with the recognition that nature has somehow violated the pre-induced expectations that govern normal science." This statement neatly describes exactly what transpired during the historical revolution that took place in physics between the classical mechanics/electrodynamics age in the 19th century and the quantum/atomic/nuclear/relativistic age in the 20th century. And this isn't the only time in human history that scientific paradigms have dramatically changed. The discovery of p-Teleportation already commenced in the 20th century, so let us continue the discovery and create a new physics paradigm for the 21st century.

5.1.1 Hypothesis Based on Mathematical Geometry

The Chinese researchers reported in their teleportation experiments that high-speed photography/videotaping recorded test specimens physically "melding" or blending with the walls of sealed containers, and in a different series of experiments the test specimens would simply disappear from inside the container only to reappear at another location (after seconds to several minutes of time transpired). They also reported in the series of radio micro-transmitter experiments that there were large fluctuations in the intensity (in both amplitude and frequency) of the monitored signal to the effect that it would either completely disappear or become extremely weak (to the extent that the monitoring instruments could scarcely detect it); and they discovered that there was a definite correlation between the change in strength (i.e., radical frequency shifts were observed) of the monitored radio signal and the teleportation of the radio micro-transmitter, such that the weak or absent signal indicated that the specimen was "nonexistent" (or in an altered physical state) during teleportation. This data is important because without the aid of electronic monitoring instruments, the average person's sensory organs and usual methods of detection are temporarily unable to perceive the test specimen's (ambiguous) existence during the teleportation process. This data offers an important clue on what the teleportation mechanism is.

It is beyond the scope of this study to propose a complete self-consistent physics theory of consciousness/mind, which explains how the mind can activate p-Teleportation and related psychotronics phenomena. This topic has been under study in recent decades by a legion of medical science, bio- and neuro-physiology, psychology, mathematics, philosophy, and physics experts. Many different theories with varying degree of theoretical maturity and self-consistency have been proposed over the years, and most of them have not yet been experimentally tested for various reasons. However, some first-order experimental work has been done (Mitchell, 1974b; Targ and Puthoff, 1977; Wolman et al., 1986; Radin, 1997; Tart et al., 2002). Ironically, quantum mechanics theory, and the related physics of quantum entanglement and teleportation, has become the primary focus of all of the physics theories of consciousness/psychotronics that have been recently proposed (see for example, Shan, 2003). Wolman et al. (1986) and Radin (1997) provide a review and discussion on recent theories and experiments that are based on quantum physics theory (see also, Walker, 1974; Targ and Puthoff, 1977; Mitchell, 1999, and the references cited therein; Tart et al., 2002). It appears that the physics of q-Teleportation (Chapter 3) has tremendous relevance to the physics of p-Teleportation and psychotronics.

In the following I propose a parsimonious first-order hypothesis that can explain the gross features of both the Chinese p-Teleportation data and the other reported p-Teleportation phenomena. But I will refrain from including any role that might be played by quantum phenomena since the scientific community has not yet settled that particular issue. (However, it is apparent that quantum theory and quantum phenomena will likely play a key role in a formal physics theory of PK and psychotronics.)

First-Order Hypothesis:

- ☐ Fact 1: The mature discipline of mathematical geometry developed the properties of higher dimensional spaces (Reichenbach, 1957; Manning, 1977; Rucker, 1977). An example of one such property that is of relevance to the hypothesis: One can visualize a four-dimensional world by using color as the 4th dimension. We can think of a three-dimensional world, whereby objects pass through one another if their colors (i.e., four-dimensional locations) are different (Reichenbach, 1957). For example, color can be used as a 4th dimension to see how a knot in three-dimensions can be untied in a 4th spatial dimension without moving the ends of the cord. That is because a cord cannot stay knotted in four-dimensional space, because the extra degree of freedom will cause any knot to slip through itself. Two other interesting and relevant examples are that the links of a chain may be separated unbroken in the 4th dimension, and a flexible sphere may be turned inside out without tearing in the 4th dimension (Manning, 1977; Rucker, 1977).

- ☐ Proposition 1 and Fact 2: It has been proposed that our space actually possesses a slight four-dimensional hyperthickness, so that the ultimate components of our nervous system are actually higher dimensional, thus enabling the human mind/brain to imagine four-dimensional space (Hinton, 1888, 1904; Rucker, 1977). If this is the case, then the three-dimensional nets of neurons that code thoughts in our brain may form four-dimensional patterns to achieve four-dimensional thought. The "bulk" space in 3-brane theory (see Section 4.1), and experimental data from the Remote Viewing program (see Section 5.1), provide support for this concept. Can we see into the 4th dimension and have four-dimensional thoughts? Yes, we can. Proof (see, Rucker, 1977, 1984): If you look at a Necker cube for a while, it spontaneously turns into its mirror image and back again. If you watch it do this often enough, the twinkling sort of motion from one state to the other begins to seem like a continuous motion. But this motion can only be continuous if it is a rotation in four-dimensional space. The mathematician August F. Möbius discovered in 1827 that it is in fact possible to turn a three-dimensional solid object into its mirror image by an appropriate rotation through four-dimensional space (a.k.a. hyperspace rotation). Thus, it is actually possible for our minds to perform such a rotation. Therefore, we can actually produce four-dimensional phenomenon in our minds, so our consciousness is four-dimensional. Rucker (1984) shows another dramatic example of being able to see into the 4th dimension via a "Neck-A-Cube."

- ☐ Fact 3: Another property of higher dimensional geometry (Reichenbach, 1957; Rucker, 1977, 1984) is that one can move through solid three-dimensional obstacles without penetrating them by passing in the direction of the 4th (spatial) dimension. The 4th dimension is perpendicular to all of our normal three-dimensional space directions, and so our three-dimensional enclosures have no walls against this direction.

- ☐ Conclusion and Hypothesis: Therefore, the results of the Chinese p-Teleportation experiments can simply be explained as a human consciousness phenomenon that somehow acts to move or rotate test specimens through a 4th spatial dimension, so that the specimens are able to penetrate the solid walls/barriers of their containers without physically breaching them. No real dematerialization/rematerialization of the specimens takes place. The intensity fluctuations of the radio micro-transmitter specimen's electromagnetic signal, and the apparent blending of the other specimens with the walls of their containers, represent the passage of the specimens through a 4th spatial dimension. During teleportation the radio signals emitted by the micro-transmitter became weak/non-existent and fluctuated, because they were spreading out into the 4th dimension and became undetectable in our three-dimensional space. The weak signals that were ("barely") detected represent the leakage of a portion of the radio signal back into our three-dimensional space from the 4th dimension during teleportation. The observed blending of the other specimens with the walls of their containers is how the movement/rotation of the specimens through the 4th dimension was visually interpreted by the mind (along the lines of the Necker cube or Neck-A-Cube examples).

5.2 Conclusion and Recommendations

We will need a physics theory of consciousness and psychotronics, along with more experimental data, in order to test the hypothesis in Section 5.1.1 and discover the physical mechanisms that lay behind the psychotronic manipulation of matter. P-Teleportation, if verified, would represent a phenomenon that could offer potential high-payoff military, intelligence and commercial applications. This phenomenon could generate a dramatic revolution in technology, which would result from a dramatic paradigm shift in science. Anomalies are the key to all paradigm shifts!

•**Recommendations**:

- There are numerous supporters within the U.S. military establishment who comprehend the significance of remote viewing and PK phenomenon, and believe that they could have strategic implications. Bremseth (2001), a U.S. Navy SEAL, attended the Marine War College and studied the Remote Viewing program, and interviewed many of the former program participants. Bremseth then wrote his thesis on the topic, and concluded that the evidence supported continued research and applications of remote viewing. A research program improving on and expanding, or implementing novel variations of, the Chinese and Uri Geller-type experiments should be conducted in order to generate p-Teleportation phenomenon in the lab. The performances and characteristics of p-Teleportation need to be delineated in order to develop a refined hypothesis. Such a program should be designed so that an operational model for p-Teleportation can be developed and implemented as a prototype. An experimental program similar in fashion to the Remote Viewing program should be funded at $900,000 – 1,000,000 per year in parallel with a theoretical program funded at $500,000 per year for an initial five-year duration. The role of quantum physics theory and related quantum phenomena (i.e., entanglement and teleportation) in p-Teleportation and psychotronics should be explored in this program (see for example, the Biological Quantum Teleportation recommendation in Section 3.3). An experiment definition study should be conducted first to identify and propose the best experiments for this program, which should be funded at $80,000 for one year.

6.0 REFERENCES

1. Aczel, A. D. (2002), Entanglement: The Greatest Mystery in Physics, Four Walls Eight Windows Press, New York
2. Aharonov, Y., Reznik, B. and Stern, A. (1998), "Quantum limitations of superluminal propagation," Phys. Rev. Lett., 81, 2190-2193
3. Aharonov, Y. and Albert, D. (1981), "Can we make sense of the measurement process in relativistic quantum mechanics?," Phys. Rev. D, 24, 359-370
4. Alexander, Col. J. B. (2003), Winning The War: Advanced Weapons, Strategies, And Concepts For The Post-9/11 World, St. Martin's Press, New York, pp. 238 – 244
5. Alexander, J. B. (1996), "Uri's Impact on the U.S. Army," posted on http://www.urigeller.com
6. Alexander, Lt. Col. J. B. (1980), "The New Mental Battlefield: 'Beam Me Up, Spock,'" Military Review, vol. XL, no. 12
7. Alexander, Col. J. B., Groller, Maj. R. and Morris, J. (1990), The Warrior's Edge, W. Morrow Co., New York
8. Ambjϕrn, J. and Wolfram, S. (1983), "Properties of the Vacuum. I. Mechanical and Thermodynamic," Annals Phys., 147, 1-32
9. Antoniadis, I., Arkani-Hamed, N., Dimopoulos, S. and Dvali, G. (1998), "New dimensions at a millimeter to a fermi and superstrings at a TeV," Phys. Lett. B, 436, 257-263
10. Appelquist, T., Chodos, A. and Freund, P. G. O. eds. (1987), Modern Kaluza-Klein Theories, Addison-Wesley, Menlo Park
11. Arkani-Hamed, N., Dimopoulos, S. and Dvali, G. (2002), "Large Extra Dimensions: A New Arena for Particle Physics," Physics Today, 55, 35-40
12. Arkani-Hamed, N., Dimopoulos, S. and Dvali, G. (1998), "The hierarchy problem and new dimensions at a millimeter," Phys. Lett. B, 429, 263-272
13. Arkani-Hamed, N., Dimopoulos, S., Kaloper, N. and Dvali, G. (2000), "Manyfold universe," Journal of High Energy Physics (JHEP online physics papers), http://jhep.sissa.it/archive/papers/jhep122000010/jhep122000010.pdf0012
14. Aspect, A. (1983), Trois tests expérimentaux des inégalités de Bell par mesure de corrélation de polarisation de photons, Ph.D. thesis No. 2674, Université de Paris-Sud, Centre D'Orsay
15. Aspect, A., Dalibard, J. and Roger, G. (1982a), "Experimental Tests of Bell's Inequalities Using Time-Varying Analyzers," Phys. Rev. Letters, 49, 1804-1807
16. Aspect, A., Grangier, P. and Roger, G. (1982b), "Experimental Realization of Einstein-Podolsky-Rosen-Bohm Gedankenexperiment: A New Violation of Bell's Inequalities," Phys. Rev. Letters, 49, 91
17. Aspect, A. and Grangier, P. (1985), Lettere al Nuovo Cimento, 43, 345
18. Aspelmeyer, M., et al. (2003), "Long-Distance Free-Space Distribution of Quantum Entanglement," Science, 301, 621 - 623
19. Banghui, W. (1990), "Evidence of the Existence of Abnormal States of Matter," Chinese J. Somatic Sci., First Issue, 36 [translated into English by the Defense Intelligence Agency]
20. Barcelo, C. and Visser, M. (2002), "Twilight for the energy conditions?," Int. J. Mod. Phys. D, 11, 1553
21. Barnum, H., Caves, C., Fuchs, C., Jozsa, R. and Schumacher, B. (1996), "Noncommuting Mixed States Cannot Be Broadcast," Phys. Rev. Lett., 76, 2818-2821
22. Bell, J. S. (1964), "On the Einstein Podolsky Rosen Paradox," Physics, 1, 195
23. Bennett, C. H., et al. (1993), "Teleporting an unknown quantum state via dual classical and Einstein-Podolsky-Rosen channels," Phys. Rev. Lett., 70, 1895-1899
24. Bennett, C. H. and Wiesner, S. J. (1992), "Communication via one- and two-particle operators on Einstein-Podolsky-Rosen states," Phys. Rev. Lett., 69, 2881-2884

25. Bennett, G. L., Forward, R. L. and Frisbee, R. H. (1995), "Report on the NASA/JPL Workshop on Advanced Quantum/Relativity Theory Propulsion," AIAA-95-2599, 31st AIAA/ASME/ASE/ASEE Joint Propulsion Conference and Exhibit, San Diego, CA
26. Birrell, N. D. and Davies, P. C. W. (1982), Quantum fields in curved space, Cambridge University Press, Cambridge
27. Blaauboer, M., et al. (1998), "Superluminal pulse transmission through a phase conjugating mirror," Optics Communications, 148, 295-299
28. Boschi, D., et al. (1998), "Experimental realization of teleporting an unknown pure quantum state via dual classical and Einstein-Podolski-Rosen channels," Phys. Rev. Lett., 80, 1121-1125
29. Bose, S. and Home, D. (2002), "Generic Entanglement Generation, Quantum Statistics, and Complementarity," Phys. Rev. Lett., 88, 050401
30. Bose, S., Knight, P. L., Plenio, M. B. and Vedral, V. (1999), "Proposal for Teleportation of an Atomic State via Cavity Decay," Phys. Rev. Lett., 83, 5158-5161
31. Bouwmeester, D., et al. (1997), "Experimental quantum teleportation," Nature, 390, 575-579
32. Bowen, W. P., et al. (2003), "Experimental investigation of continuous variable quantum teleportation," Phys. Rev. A, 67, 032302
33. Bowen, W. P., Treps, N., Schnabel, R. and Lam, P. K. (2002), "Experimental demonstration of continuous variable polarization entanglement," Phys. Rev. Lett., 89, 253601
34. Brassard, G., Braunstein, S. and Cleve, R. (1998), "Teleportation as a quantum computation," Physica D, 120, 43-47
35. Braunstein, S. (1996), "Quantum teleportation without irreversible detection," Proc. Royal Acad., 53, 1900-1903
36. Braunstein, S., Fuchs, C., Kimble, H. and van Loock, P. (2001), "Quantum versus classical domains for teleportation with continuous variables," Phys. Rev. A, 64, 022321
37. Braunstein, S. and Kimble, J. (1998), "Teleportation of continuous quantum variables," Phys. Rev. Lett., 80, 869-872
38. Bremseth, Cmdr. L. R. (2001), Unconventional Human Intelligence Support: Transcendent and Asymmetric Warfare Implications of Remote Viewing, Thesis, Marine War College
39. Buttler, W., et al. (1998), "Practical free-space quantum key distribution over 1 km," Phys. Rev. Lett., 81, 3283-3286
40. Center for Quantum Computation Web Site: http://www.qubit.org
41. Chan, H. B., et al. (2001), "Quantum Mechanical Actuation of Microelectromechanical Systems by the Casimir Force," Science, 291, 1941-1944
42. Chiao, R. and Steinberg, A. (1998), "Quantum optical studies of tunneling and other superluminal phenomena," Physica Scripta, T76, 61-66
43. Chown, M. (1990), "Can photons travel 'faster than light'?," New Scientist, 126, 32
44. CIA In-Q-Tel Web Site information: http://www.cia.gov/cia/publications/inqtel/
45. Cole, D. C. and Puthoff, H. E. (1993), "Extracting Energy and Heat from the Vacuum," Phys. Rev. E, 48, 1562
46. Davies, P. C. W. (1980), Other Worlds, Dent, London
47. Davis, E. W. (1999a), Research Summary Report #1 to Dr. Hal Puthoff, IASA: Brief Summary of "Lorentzian Wormholes From The Gravitationally Squeezed Vacuum", NASA Research Center Online Library – Interstellar Studies (available from the author)
48. Davis, E. W. (1999b), Research Summary Report #2 to Dr. Hal Puthoff, IASA: Brief Summary of "Gravitational Vacuum Polarization. Parts I – IV", NASA Research Center Online Library – Interstellar Studies (available from the author)
49. de Felice, F. (1971), "On the gravitational field acting as an optical medium," Gen. Rel. Grav., 2, 347-357
50. de Oliveira, E. C. and Rodriguez, W. (1998), "Superluminal electromagnetic waves in free space," Annalen der Physik, 7(7-8), 654-659

51. de Sabbata, V. and Schmutzer, E. eds. (1983), Unified Field Theories of More Than 4 Dimensions, Proc. Int'l School of Cosmology and Gravitation (Erice), World Scientific, Singapore
52. Deutsch, D. (1998), The Fabric of Reality, Penguin Books
53. DeWitt, B. S. and Graham, N. eds. (1973), The Many Worlds Interpretation of Quantum Mechanics, Princeton University Press, Princeton
54. DeWitt, B. S. (1970), Physics Today, 23, 30
55. DIA Report (1978), Paraphysics R&D – Warsaw Pact, Defense Intelligence Agency, Report No. DST-1810S-202-78, DIA Task No. PT-1810-18-76, Washington DC (authors' names redacted)
56. Dicke, R. H. (1961), "Mach's principle and equivalence," in Proc. of the Int'l School of Physics "Enrico Fermi" Course XX, Evidence for Gravitational Theories, ed. C. Møller, Academic Press, New York, pp. 1-49
57. Dicke, R. H. (1957), "Gravitation without a principle of equivalence," Rev. Mod. Phys., 29, 363-376
58. Ding, Y. J. and Kaplan, A. E. (1992), "Nonlinear Magneto-Optical Effect in Vacuum: Inhomogeneity-Originated Second-Harmonic Generation in DC Magnetic Field," J. Nonl. Opt. Phys., 1, 51-72
59. Ding, Y. J. and Kaplan, A. E. (1989), "Nonlinear Magneto-Optics of Vacuum: Second-Harmonic Generation," Phys. Rev. Lett., 63, 2725-2728
60. Drummond, I. J. and Hathrell, S. J. (1980), "QED vacuum polarization in a background gravitational field and its effect on the velocity of photons," Phys. Rev. D, 22, 343-355
61. Dür, W. and Briegel, H.-J. (2003), "Entanglement purification for Quantum Computation," Phys. Rev. Lett., 90, 067901
62. Einstein, A., Podolsky, B. and Rosen, N. (1935), "Can quantum mechanical description of physical reality be considered complete?," Phys. Rev., 47, 777-780
63. Evans, J., Nandi, K. and Islam, A. (1996a), "The Optical-Mechanical Analogy in General Relativity: New Methods for the Paths of Light and of the Planets," Am. J. Phys., 64, 1401-1415
64. Evans, J., Nandi, K. and Islam, A. (1996b), "The Optical-Mechanical Analogy in General Relativity: Exact Newtonian Forms for the Equations of Motion of Particles and Photons," Gen. Rel. Grav., 28, 413-439
65. Everett, H. (1957), Rev. Mod. Phys., 29, 454
66. Forward, R. L. (2001), Personal Communication, Salt Lake City, UT
67. Forward, R. L. (1999), Personal Communication, Los Angeles, CA
68. Forward, R. L. (1998), "Apparent Method for Extraction of Propulsion Energy from the Vacuum," AIAA-98-3140, 34th AIAA/ASME/SAE/ASEE Joint Propulsion Conference & Exhibit, Cleveland, OH
69. Forward, R. L. (1996), Mass Modification Experiment Definition Study, PL-TR-96-3004, Phillips Laboratory-Propulsion Directorate, Air Force Materiel Command, Edwards AFB, CA
70. Forward, R. L. (1984), "Extracting electrical energy from the vacuum by cohesion of charged foliated conductors," Phys. Rev. B, 30, 1770-1773
71. Freedman, S. J. and Clauser, J. F. (1972), "Experimental Test of Local Hidden-Variable Theories," Phys. Rev. Lett., 28, 938-941
72. Friedman, J. et al. (1990), "Cauchy problem in spacetimes with closed timelike curves," Phys. Rev. D, 42, 1915-1930
73. Furusawa, A., et al. (1998), "Unconditional quantum teleportation," Science, 282, 706-710
74. Furuya, K., et al. (1999), "Failure of a proposed superluminal scheme," Phys. Lett. A, 251, 294-296
75. Geller, U. (1975), Uri Geller: My Story, Praeger Publ., New York
76. Giroldini, W. (1991), "Eccles's Model of Mind-Brain Interaction and Psychokinesis: A Preliminary Study," J. Sci. Explor., 5, no. 2

77. Gisin, N. (1990), “Weinberg’s non-linear quantum mechanics and superluminal communications,” Phys. Lett. A, 143, 1-2
78. Gisin, N., Scarani, V., Tittel, W. and Zbinden, H. (2000), “Optical tests of quantum non-locality: from EPR-Bell tests towards experiments with moving observers,” Ann. Phys. (Leipzig), 9, 831-841
79. Gissurarson, L. R. (1992), “The Psychokinesis Effect: Geomagnetic Influence, Age and Sex Difference,” J. Sci. Explor., 6, no. 2
80. Green, M. B. (1985), “Unification of forces and particles in superstring theories,” Nature, 314, 409
81. Greenberger, D. (1998), “If one could build a macroscopical Schrodinger cat state, one could communicate superluminally,” Physica Scripta, T76, 57-60
82. Groller, Capt. R. (1987), “Soviet Psychotronics – a Closer Look,” Military Intelligence, PB 34-87-1 (Test), pp. 43-44
83. Groller, Capt. R. (1986), “Soviet Psychotronics – a State of Mind,” Military Intelligence, 12, no. 4, pp. 18-21, 58
84. Hagley, E., et al. (1997), “Generation of Einstein-Podolsky-Rosen Pairs of Atoms,” Phys. Rev. Lett., 79, 1-5
85. Hald, J., Sørensen, J. L., Schori, C. and Polzik, E. S. (1999), “Spin Squeezed Atoms: A Macroscopic Entangled Ensemble Created by Light,” Phys. Rev. Lett., 83, 1319-1322
86. Hartle, J. B. and Hawking, S. W. (1983), “Wave function of the Universe,” Phys. Rev. D, 28, 2960-2975
87. Hasted, J. B. (1979), “Paranormal Metal Bending,” in The Iceland Papers: Selected Papers on Experimental and Theoretical Research on the Physics of Consciousness, Puharich, A. ed., Research Associates Publ., Amherst, WI
88. Hasted, J. B., Bohm, D., Bastin, E. W. and O’Reagan, B. (1975), “Scientists confronting the paranormal,” Nature, 254, 470-472
89. Haugan, M. P. and Will, C. M. (1977), “Principles of equivalence, Eötvös experiments, and gravitational red-shift experiments: The free fall of electromagnetic systems to post—post-Coulombian order,” Phys. Rev. D, 15, 2711-2720
90. Hawking, S. W. and Ellis, G. F. R. (1973), The Large-Scale Structure of Space-Time, Cambridge Univ. Press, Cambridge, pp. 88-91 and 95-96
91. Hegerfeldt, G. (1998), “Instantaneous spreading and Einstein causality in quantum theory,” Annalen der Physik, 7(7-8), 716-725
92. Heitler, W. (1954), The Quantum Theory of Radiation (3rd ed.), Oxford University Press, London, p. 113.
93. Herrmann, F. (1989), “Energy Density and Stress: A New Approach to Teaching Electromagnetism”, Am. J. Phys., 57, 707-714
94. Hinton, C. H. (1904), The Fourth Dimension, Sonnenschein, London
95. Hinton, C. H. (1888), A New Era of Thought, Sonnenschein, London
96. Hochberg, D. and Kephart, T. W. (1991), “Lorentzian wormholes from the gravitationally squeezed vacuum,” Phys. Lett. B, 268, 377-383
97. Hong, C. K. and Mandel, L. (1985), “Theory of parametric frequency down conversion of light,” Phys. Rev. A, 31, 2409-2418
98. Houck, J. (1984a), “Surface Change During Warm-Forming,” Archaeus, 2, no. 1
99. Houck, J. (1984b), “PK Party History,” Psi Research, 3, no. 1
100. Houck, J. (1982), “PK Party Format,” unpublished paper
101. IBM Press Release (2001), “IBM’s Test-Tube Quantum Computer Makes History,” http://www.research.ibm.com/resources/news/20011219_quantum.shtml
102. Jahn, R. G. and Dunne, B. J. (1987), Margins of Reality: The Role of Consciousness in the Physical World, Harcourt Brace Jovanovich, New York

103. Jammer, M. (1974), The Philosophy of Quantum Mechanics, Wiley-Interscience, New York, pp. 507-521
104. Jennewein, T., Simon, C., Weihs, G., Weinfurter, H. and Zeilinger, A. (2000), "Quantum Cryptography with Entangled Photons," Phys. Rev. Lett., 84, 4729-4732
105. Jinggen, H., Xinghai, Y. and Laijing, S. (1990), "Investigation into the 'Force' in Parapsychological Writing," Chinese J. Somatic Sci., First Issue, 32 [translated into English by the Defense Intelligence Agency]
106. Julsgaard, B., Kozhekin, A. and Polzik, E. S. (2001), "Experimental long-lived entanglement of two macroscopic objects," Nature, 413, 400-403
107. Kaku, M. (1994), Hyperspace: A Scientific Odyssey Through Parallel Universes, Time Warps, and the 10th Dimension, Anchor Books-Doubleday, New York
108. Kaku, M. (1993), Quantum Field Theory, Oxford University Press, New York
109. Kaku, M. (1988), Introduction to Superstrings, Springer-Verlag, New York
110. Kaluza, T. (1921), "Unitätsproblem der Physik," Sitz. Preuss. Akad. Wiss. Phys. Math., K1, 966
111. Kaplan, A. E. and Ding, Y. J. (2000), "Field-gradient-induced second-harmonic generation in magnetized vacuum," Phys. Rev. A, 62, 043805-(1-9)
112. Kim, Y.-H., Kulik, S. P. and Shih, Y. (2001), "Quantum Teleportation of a Polarization State with a Complete Bell State Measurement," Phys. Rev. Lett., 86, 1370-1373
113. Klein, O. (1926), "Quantentheorie und fünfdimensionale Relativitätstheorie," Zeits. Phys., 37, 895
114. Kongzhi, S., Xianggao, L. and Liangzhong, Z. (1990), "Research into Paranormal Ability to Break Through Spatial Barriers," Chinese J. Somatic Sci., First Issue, 22 [translated into English by the Defense Intelligence Agency]
115. Kuhn, T. S. (1970), The Structure of Scientific Revolutions, 2nd ed., Univ. of Chicago Press, Chicago
116. Kwiat, P. G., et al. (1995), "New high-intensity source of polarization-entangled photon pairs," Phys. Rev. Lett., 75, 4337-4341
117. Kwiat, P. G., et al. (1999), "Ultrabright source of polarization-entangled photons," Phys. Rev. A., 60, R773-R776
118. Lamas-Linares, A., Howell, J. C. and Bouwmeester, D. (2001), "Stimulated emission of polarization-entangled photons," Nature, 412, 887-890
119. Lamoreaux, S. K. (1997), "Measurement of the Casimir Force Between Conducting Plates," Phys. Rev. Letters, 78, 5-8
120. LaMothe, Capt. J. D. (1972), Controlled Offensive Behavior – USSR, Defense Intelligence Agency, Report No. ST-CS-01-169-72, DIA Task No. T72-01-14, Washington DC
121. Latorre, J. I., Pascual, P. and Tarrach, R. (1995), "Speed of light in non-trivial vacua," Nucl. Phys. B, 437, 60-82
122. Lee, H. C. ed. (1984), An Introduction to Kaluza-Klein Theories, Proc. Chalk River Workshop on Kaluza-Klein Theories, World Scientific, Singapore
123. Lee, T. D. (1988), Particle Physics and Introduction to Field Theory, Harwood Academic Press, London
124. Leggett, A. J. (1999), "Quantum Theory: Weird and Wonderful," Physics World, 12, 73-77
125. Leshan, C. (2002), "Proposal for Teleportation by Help of Vacuum Holes," in Gravitation and Cosmology: From the Hubble Radius to the Planck Scale, Proc. of a Symposium in Honour of the 80th Birthday of Jean-Pierre Vigier, Amoroso, R. L., Hunter, G., Kafatos, M. and Vigier, J.-P. eds., Kluwer Academic Publ., Boston, pp. 515-516
126. Leshan, C. (1999), "Thought Experiment to the Border of Universe," J. Theoretics, 1, no.4
127. Li, L.-X. and Gott, J. R. (1998), "Self-Consistent Vacuum for Misner Space and the Chronology Protection Conjecture," Phys. Rev. Lett., 80, 2980-2983
128. Lightman, A. P. and Gingerich, O. (1991), "When Do Anomalies Begin?," Science, 255, 690-695

129. Lightman, A. P. and Lee, D. L. (1973), "Restricted proof that the weak equivalence principle implies the Einstein equivalence principle," Phys. Rev. D, 8, 364
130. Maierle, C., Lidar, D. and Harris, R. (1998), "How to teleport superpositions of chiral amplitudes," Phys. Rev. Lett., 81, 869-872
131. Maire, L. F. and LaMothe, Capt. J. D. (1975), Soviet and Czechoslovakian Parapsychology Research, Defense Intelligence Agency, Report No. DST-1810S-387-75, DIA Task No. PT-1810-12-75, Washington DC
132. Mandel, L. and Wolf, E. (1995), Optical Coherence and Quantum Optics, Cambridge University Press
133. Manning, H. P. (1977), The Fourth Dimension Simply Explained, Peter Smith Publ., Gloucester, MA
134. Mavromatos, N. E., Mershin, A. and Nanopoulos, D. V. (2002), "QED-Cavity model of microtubules implies dissipationless energy transfer and biological quantum teleportation," http://arxiv.org/abs/quant-ph/0204021
135. McConnell, A. J. (1957), Applications of Tensor Analysis, Dover Publ., New York, pp. 163-217
136. Mead, F. B. and Nachamkin, J. (1996), "System for Converting Electromagnetic Radiation Energy to Electrical Energy," United States Patent No. 5,590,031
137. Milonni, P. W. (1994), The Quantum Vacuum: An Introduction to Quantum Electronics, Academic Press, NY
138. Mitchell, E. D. (1999), "Nature's Mind: the Quantum Hologram," National Institute for Discovery Science, Las Vegas, NV, http://www.nidsci.org/articles/naturesmind-qh.html
139. Mitchell, E. D. (1974a), "Appendix: Experiments with Uri Geller," in Psychic Exploration: A Challenge for Science, Mitchell, E. D., White, J. ed., G. P. Putnam's Sons, New York, pp. 683-686
140. Mitchell, E. D. (1974b), Psychic Exploration: A Challenge for Science, White, J. ed., G. P. Putnam's Sons, New York
141. Mittelstaedt, P. (2000), "What if there are superluminal signals?," Eur. Phys. J. B**,** 13, 353-355
142. Mittelstaedt, P. (1998), "Can EPR-correlations be used for the transmission of superluminal signals?," Annalen der Physik, 7(7-8), 710-715
143. Mittelstaedt, P. and Nimtz, G. eds. (1998), "Workshop on Superluminal Velocities," Annalen der Physik, 7(7-8), 591-592
144. Morris, M. S. and Thorne, K. S. (1988), "Wormholes in spacetime and their use for interstellar travel: A tool for teaching general relativity", Am. J. Phys., 56, 395-412
145. Mourou, G. A., Barty, C. P. J. and Perry, M. D. (1998), "Ultrahigh-Intensity Lasers: Physics Of The Extreme On A Tabletop," Physics Today, 51, 22-28
146. Naik, D. S., Peterson, C. G., White, A. G., Berglund, A. J. and Kwiat, P. G. (2000), "Entangled state quantum cryptography: Eavesdropping on the Ekert protocol," Phys. Rev. Lett., 84, 4733
147. Nash, C. B. (1978), Science of PSI: ESP and PK, C. C. Thomas Publ., Springfield, Ill.
148. Nielsen, M. A. (2003), "Simple Rules for a Complex Quantum World," Sci. Am., 13, 25-33
149. Nielsen, M. A. and Chuang, I. L. (2000), Quantum Computation and Quantum Information, Cambridge University Press
150. Nielsen, M., Knill, E. and Laflamme, R. (1998), "Complete quantum teleportation using nuclear magnetic resonance," Nature, 396, 52-55
151. Nimtz, G. (1998), "Superluminal signal velocities," Annalen der Physik, 7(7-8), 618-624
152. Opatrný, T., Clausen, J., Welsch, D.-G. and Kurizki, G. (2000), "Squeezed-Vacuum Assisted Quantum Teleportation," Paper No. 7thCEWQO/015, in Proc. 7th Central-European Workshop on Quantum Optics, Hungary
153. Opatrný, T. and Kurizki, G. (2001), "Matter-Wave Entanglement and Teleportation by Molecular Dissociation and Collisions," Phys. Rev. Lett., 86, 3180-3183
154. Overduin, J. M. and Wesson, P. S. (1998), "Kaluza-Klein Gravity," http://arxiv.org/abs/gr-qc/9805018

155. Pan, J.-W., et al. (1998), "Experimental entanglement swapping," Phys. Rev. Lett., 80, 3891-3894
156. Pease, R. (2001), "Brane new world," Nature, 411, 986-988
157. Peres, A. (2000), "Classical intervention in quantum systems. II. Relativistic invariance," Phys. Rev. A, 61, 022117(8)
158. Perry, M. D. (2000), "The Amazing Power of the Petawatt," Science & Technology Rev. (LLNL-DoE publication), March issue, 4-12
159. Perry, M. D. (1996), "Crossing the Petawatt Threshold," Science & Technology Rev. (LLNL-DoE publication), December issue, 4-11
160. Polchinski, J. (1995), "Dirichlet Branes and Ramond-Ramond Charges," Phys. Rev. Lett., 75, 4724-4727
161. Pratt, J. G. (1986), "Soviet Research in Parapsychology," in Handbook of Parapsychology, Wolman, B. B., Dale, L. A., Schmeidler, G. R. and Ullman, M. eds., McFarland and Co. Publ., Jefferson, NC, pp. 883-903
162. Preskill, J., Lecture Notes: http://www.theory.caltech.edu/people/preskill/ph229/
163. Puthoff, H. E. (2003), Personal Communication, Institute for Advanced Studies at Austin, Austin, TX
164. Puthoff, H. E. (2002a), "Polarizable-Vacuum (PV) Approach to General Relativity", Found. Phys., 32, 927-943
165. Puthoff, H. E. (2002b), "Polarizable-Vacuum Approach to General Relativity", in Gravitation and Cosmology: From the Hubble Radius to the Planck Scale, eds. R. L. Amoroso, G. Hunter, M. Kafatos, and J.-P. Vigier, Kluwer Academic Publ., Dordrecht, the Netherlands, pp. 431-446
166. Puthoff, H. E. (1999a), "Polarizable-vacuum (PV) representation of general relativity," http://arxiv.org/abs/gr-qc/9909037
167. Puthoff, H. E. (1999b), Personal Communication, Institute for Advanced Studies at Austin, Austin, TX
168. Puthoff, H. E. (1996), "CIA-Initiated Remote Viewing Program at Stanford Research Institute," J. Sci. Explor., 10, 63-76
169. Puthoff, H. E. (1993), "On the Feasibility of Converting Vacuum Electromagnetic Energy to Useful Form," Int'l Workshop on the Zeropoint Electromagnetic Field, Cuernavaca, Mexico
170. Puthoff, H. E. (1990), "The Energetic Vacuum: Implications for Energy Research," Spec. in Sci. & Technology, 13, 247
171. Puthoff, H. E., Little, S. R. and Ibison, M. (2002), "Engineering the Zero-Point Field and Polarizable Vacuum for Interstellar Flight," J. British Interplanetary Soc., 55, 137-144
172. Puthoff, H. E. and Targ, R. (1975), "Physics, Entropy and Psychokinesis," in Proc. Conf. Quantum Physics and Parapsychology (Geneva, Switz.), Parapsychology Foundation Publ., New York
173. Puthoff, H. E. and Targ, R. (1974), "PK experiments with Uri Geller and Ingo Swann," in Research in Parapsychology 1973, Roll, W. G., Morris, R. L. and Morris, J. D. eds., Scarecrow Press, Metuchen, New Jersey, pp. 125-128
174. Quantum Information: Special Issue (1998), Physics World, 11, no. 3
175. Radin, D. (1997), The Conscious Universe: The Scientific Truth of Psychic Phenomena, HarperEdge-HarperCollins Publ., New York
176. Raimond, J. M., Brune, M. and Haroche, S. (2001), "Colloquium: Manipulating quantum entanglement with atoms and photons in a cavity," Rev. Mod. Phys., 73, 565-582
177. Randall, L. and Sundrum, R. (1999a), "Large Mass Hierarchy from a Small Extra Dimension," Phys. Rev. Lett., 83, 3370-3373
178. Randall, L. and Sundrum, R. (1999b), "An Alternative to Compactification," Phys. Rev. Lett., 83, 4690-4693
179. Rarity, J. G. (2003), "Getting Entangled in Free Space," Science, 301, 604 - 605
180. Reichenbach, H. (1957), The Philosophy of Space and Time, Dover Publ., New York
181. Rhine, L. E. (1970), Mind over Matter: Psychokinesis, Macmillan, New York

182. Rubakov, V. A. and Shaposhnikov, M. E. (1983a), "Do we live inside a domain wall?," Phys. Lett. B, 125, 136-138
183. Rubakov, V. A. and Shaposhnikov, M. E. (1983b), "Extra space-time dimensions: Towards a solution to the cosmological constant problem," Phys. Lett. B, 125, 139-143
184. Rucker, R. (1984), The Fourth Dimension: A Guided Tour of the Higher Universes, Houghton Mifflin Co., Boston, pp. 45-49
185. Rucker, R. (1977), Geometry, Relativity and the Fourth Dimension, Dover Publ., New York
186. Sackett, C. A. (2001), Quant. Inf. Comput., 1, 57
187. Sackett, C. A., et al. (2000), "Experimental entanglement of four particles," Nature, 404, 256
188. Scarani, V., Tittel, W., Zbinden, H. and Gisin, N. (2000), "The speed of quantum information and the preferred frame: analysis of experimental data," Phys. Lett. A, 276, 1-7
189. Scharnhorst, K. (1990), "On Propagation of Light in the Vacuum Between Plates," Phys. Lett. B, 236, 354-359
190. Schein, F. and Aichelburg, P. C. (1996), "Traversable Wormholes in Geometries of Charged Shells," Phys. Rev. Letters, 77, 4130-4133
191. Schmidt, H. (1987), "The Strange Properties of Psychokinesis," J. Sci. Explor., 1, no. 2
192. Schmidt, H. (1974), "Psychokinesis," in Psychic Exploration: A Challenge for Science, Mitchell, E. D., White, J. ed., G. P. Putnam's Sons, New York, pp. 179-193
193. Schnabel, J. (1997), Remote Viewers: The Secret History of America's Psychic Spies, Dell Publ., New York
194. Schrödinger, E. (1980), Proc. Am. Philos. Soc., 124, 323
195. Schrödinger, E. (1935a), Die Naturwissenschaften, 48, 807
196. Schrödinger, E. (1935b), Die Naturwissenschaften, 49, 823
197. Schrödinger, E. (1935c), Die Naturwissenschaften, 49, 844
198. Seife, C. (2000), "'Spooky Action' Passes a Relativistic Test," Science, 287, 1909-1910
199. Shan, G. (2003), "A Primary Quantum Model of Telepathy," http://cogprints.ecs.soton.ac.uk/archive/00003065/
200. Shigemi, S., Yasuo, O. and Akihira, T. (1978), "Some Observations with Scanning Electron Microscope (SEM) of the Fracture Surface of Metals Fractured by Psychokinesis," Japan PS Soc. J., 2, no. 2
201. Shor, P. W. (1997), "Polynomial-Time Algorithms for Prime Factorization and Discrete Logarithms on a Quantum Computer," SIAM J. Sci. Statist. Comput., 26, 1484
202. Shor, P. W. (1994), "Polynomial-Time Algorithms for Prime Factorization and Discrete Logarithms on a Quantum Computer", in Proc. 35th Annual Symposium on Foundations of Computer Science, IEEE Computer Society Press, p. 124
203. Shoup, R. (2002), "Anomalies and Constraints: Can Clairvoyance, Precognition, and Psychokinesis Be Accommodated within Known Physics?," J. Sci. Explor., 16, no. 1
204. Shuhuang, L., et al. (1981), "Some Experiments on the Transfer of Objects Performed by Unusual Abilities of the Human Body," Nature Journal (Peoples Republic of China), 4, no. 9, 652 [Defense Intelligence Agency Requirements and Validation Branch, DIA Translation LN731-83, Intelligence Information Report No. 6010511683 (1983)]
205. Siegfried, T. (2000), The Bit and the Pendulum, John Wiley & Sons
206. Sørensen, J. L. (1998), Nonclassical light for atomic physics and quantum teleportation, Ph.D. thesis, Univ. of Aarhus
207. Srikanth, R. (July 1999), "Noncausal superluminal nonlocal signaling," http://arxiv.org/abs/quant-ph/9904075
208. Stanford, R. (1974), "Interview," Psychic, 7
209. Stenholm, S. and Bardroff, P. (1998), "Teleportation of N-dimensional states," Phys. Rev. A, 58, 4373-4376

210. Swann, I. (1974), "Scientological Techniques: A Modern Paradigm for the Exploration of Consciousness and Psychic Integration," in Proc. First Int'l Conf. on Psychotronic Research, United States Joint Publications Research Service, Document No. JPRS L/5022-1, Virginia
211. Targ, R. (1996), "Remote Viewing at Stanford Research Institute in the 1970s: A Memoir," J. Sci. Explor., 10, 77-88
212. Targ, R. and Puthoff, H. E. (1977), Mind-Reach: Scientists Look at Psychic Ability, Jonathan Cape Ltd.-Anchor Press, London
213. Tart, C. T., Puthoff, H. E. and Targ, R. eds. (2002), Mind at Large: Institute of Electrical and Electronics Engineers Symposia on the Nature of Extrasensory Perception, Hampton Roads Publ. Co., Charlottesville, VA
214. Terhal, B. M., Wolf, M. M. and Doherty, A. C. (2003), "Quantum Entanglement: A Modern Perspective," Physics Today, 56, 46-52
215. Thorne, K. S. (1993), "Closed Timelike Curves," GRP-340, CalTech, Pasadena, CA
216. Tittel, W. and Weihs, G. (2001), Quantum Inf. Comput., 1, 3
217. Tittel, W., Brendel, J., Zbinden, H. and Gisin, N. (2000), "Quantum Cryptography Using Entangled Photons in Energy-Time Bell States," Phys. Rev. Lett., 84, 4737-4740
218. Tittel, W., Brendel, J., Gisin, B., Herzog, T., Zbinden, H. and Gisin, N. (1998a), "Experimental demonstration of quantum correlations over more than 10 km," Phys. Rev. A, 57, 3229-3232
219. Tittel, W., Brendel, J., Zbinden, H. and Gisin, N. (1998b), "Violation of Bell Inequalities by Photons More Than 10 km Apart," Phys. Rev. Lett., 81, 3563-3566
220. Vaidman, L. (1994), "Teleportation of quantum states," Phys. Rev. A, 49, 1473-1476
221. Vaidman, L. and Yoran, N. (1999), "Methods for reliable teleportation," Phys. Rev. A, 59, 116-125
222. Vallee, J. (1997), Personal Communication, Science Advisory Board of the National Institute for Discovery Science, Las Vegas, NV
223. Vallee, J. (1990), Confrontations: A Scientist's Search for Alien Contact, Ballantine Books, New York
224. Vallee, J. (1988), Dimensions: A Casebook of Alien Contact, Ballantine Books, New York
225. van Enk, S. (March 1998), "No-cloning and superluminal signaling," http://arxiv.org/abs/quant-ph/9803030
226. Visser, M., Kar, S. and Dadhich, N. (2003), "Traversable Wormholes with Arbitrarily Small Energy Condition Violations," Phys. Rev. Lett., 90, 201102
227. Visser, M. (1997), Personal Communication, Washington University, St. Louis, MO
228. Visser, M. (1995), Lorentzian Wormholes: From Einstein to Hawking, AIP Press, New York
229. Visser, M. (1990), "Wormholes, baby universes, and causality", Phys. Rev. D, 41, 1116-1124
230. Visser, M. (1989), "Traversable wormholes: Some simple examples", Phys. Rev. D, 39, 3182-3184
231. Volkov, A. M., Izmest'ev, A. A. and Skrotskii, G. V. (1971), "The propagation of electromagnetic waves in a Riemannian space," Sov. Phys. JETP, 32, 686-689
232. Walker, E. H. (1974), "Consciousness and Quantum Theory," in Psychic Exploration: A Challenge for Science, Mitchell, E. D., White, J. ed., G. P. Putnam's Sons, New York, pp. 544-568
233. Weihs, G., Jennewein, T., Simon, C., Weinfurter, H. and Zeilinger, A. (1998), "Violation of Bell's Inequality under Strict Einstein Locality Conditions," Phys. Rev. Lett., 81, 5039-5043
234. Weinberg, S. (1992), Dreams of a Final Theory, Vintage Books, pp. 88-89
235. Weinberg, S. (1989), "Testing Quantum Mechanics," Ann. Phys., 194, 336-386
236. Weiss, P. (2000), "Hunting for Higher Dimensions: Experimenters scurry to test new theories suggesting that extra dimensions are detectable," Science News, 157, 122-124
237. Westmoreland, M. and Schumacher, B. (March 1998), "Quantum entanglement and the non existence of superluminal signals," http://arxiv.org/abs/quant-ph/9801014
238. Wheeler, J. A. (1962), Monist, 47, 40

239. Wheeler, J. A. (1957), Rev. Mod. Phys., 29, 463
240. Wheeler, J. A. and Zurek, W. H. eds. (1983), Quantum Theory and Measurement, Princeton University Press
241. Will, C. M. (1993), Theory and Experiment in Gravitational Physics (rev. ed.), Cambridge University Press, Cambridge, Section 2.6
242. Will, C. M. (1989), "The confrontation between gravitation theory and experiment," in General Relativity: An Einstein Centenary Survey, eds. S. W. Hawking and W. Israel, Cambridge University Press, Cambridge, Chapter 2
243. Will, C. M. (1974), "Gravitational red-shift measurements as tests of nonmetric theories of gravity," Phys. Rev. D, 10, 2330-2337
244. Wilson, H. A. (1921), "An electromagnetic theory of gravitation," Phys. Rev., 17, 54-59
245. Wineland, D. J., et al. (2002), "Quantum information processing with trapped ions," http://arxiv.org/abs/quant-ph/0212079
246. Wolf, F. A. (1988), Parallel Universes: The Search for Other Worlds, Simon and Schuster, New York
247. Wolman, B. B., Dale, L. A., Schmeidler, G. R. and Ullman, M. eds. (1986), Handbook of Parapsychology, McFarland and Co. Publ., Jefferson, NC
248. Wootters, W. K. and Zurek, W. H. (1982), "A single quantum cannot be cloned," Nature, 299, 802-803
249. Zbinden, H., Brendel, J., Gisin, N. and Tittel, W. (2000a), "Experimental Test of Non-Local Quantum Correlation in Relativistic Configurations," http://arxiv.org/abs/quant-ph/0007009
250. Zbinden, H., Brendel, J., Tittel, W. and Gisin, N. (2000b), "Experimental Test of Relativistic Quantum State Collapse with Moving Reference Frames," http://arxiv.org/abs/quant-ph/0002031
251. Zeilinger, A. (2003), "Quantum Teleportation," Sci. Am, 13, 34-43
252. Zhang, T. C., et al. (2002), "Quantum teleportation of light beams," http://arxiv.org/abs/quant-ph/0207076
253. Zubairy, S. (1998), "Quantum teleportation of a field state," Phys. Rev. A, 58, 4368-4372

APPENDIX A – A Few Words About Negative Energy

A.1 A General Relativistic Definition of Negative or Exotic Energy

We saw in equations (2.10a-c) that the surface energy and stress-tension densities of the material required to create and thread a traversable wormhole must be "negative." For surface stress-energy, and volume stress-energy in general, this is "negative" in the sense that the material we must deploy to generate and thread the traversable wormhole must have an energy density (ρc^2, ρ = mass density) that is less than the stress-energy density (τ), or we can write this condition as: *mass-energy* $\rho c^2 \leq$ *stress-energy* τ. On the basis of this condition, we call this material property "exotic." Therefore, the term "negative" is just a misnomer in this context. The condition for ordinary, non-exotic forms of matter that we are all familiar with is *mass-energy* $\rho c^2 >$ *stress-energy* τ. This condition represents one version of what is variously called the weak (WEC), null (NEC), average (AEC), dominant (DEC), strong (SEC) or "standard" energy conditions (that are mere hypotheses!), which allegedly forbid negative mass-energy density and gravitational repulsion (antigravity) between material objects to occur in nature. Hawking and Ellis (1973) formulated these energy conditions in order to establish a series of mathematical proofs in their study of the application of general relativity theory to cosmology and black hole physics.

However, there are general theorems of differential geometry that guarantee that there must be NEC violations (meaning exotic matter-energy is present) at a wormhole throat (Visser, 1997). In view of this, it is known that static radial electric or magnetic fields are borderline exotic when threading a wormhole, if their tension were infinitesimally larger, for a given energy density (Herrmann, 1989; Hawking and Ellis, 1973). Other exotic (energy condition violating) matter-energy fields are known to be squeezed quantum states of the electromagnetic field and other squeezed quantum fields (see Section A.2 for the discussion on squeezed quantum states), gravitationally squeezed vacuum electromagnetic zero-point energy (see Section 2.3 for the discussion on Gravitationally Squeezed Vacuum Energy), Casimir (electromagnetic zero-point) energy and other quantum fields/states/effects. These examples represent forms of matter-energy that possess negative energy density. Since the vacuum is defined to have vanishing energy density, anything possessing less energy density than the vacuum must have a negative energy density. With respect to creating wormholes, these have the unfortunate reputation of alarming physicists. This is unfounded since all the energy condition hypotheses have been experimentally tested in the laboratory and experimentally shown to be false - 25 years before their formulation (Visser, 1990 and references cited therein). Further investigation into this technical issue showed that violations of the energy conditions are widespread for all forms of both classical and quantum matter-energy such as planets, stars, black holes, neutron stars, people, space dust clouds, etc. (Davis, 1999b; Barcelo and Visser, 2002). In addition, Visser (1995) showed that all (generic) spacetime geometries violate all the energy conditions. Violating the energy conditions commits no offense against nature.

A.2 Squeezed Quantum States and Negative Energy

In quantum mechanics the energy (E) and frequency (ν) of a quantum oscillator system, such as electromagnetic radiation (or light), are interchangeable via the Planck relation $E = h\nu$ ($h = 2\pi\hbar$). And from the Heisenberg quantum uncertainty principle, we know that the conjugate variable to the frequency is the oscillator phase (φ), such that $\Delta\nu\Delta\varphi \geq \hbar$ is obeyed. Phase is difficult to measure and is ignored in characterizing complex quantum systems.

Recent theoretical and experimental work has shown that in many quantum systems the limits to measurement precision imposed by the quantum vacuum zero-point fluctuations (ZPF) can be breached by decreasing the frequency noise at the expense of increasing the phase noise (thus maintaining $\Delta\nu\Delta\varphi \geq \hbar$), while at the same time the variations in frequency, and therefore the energy, are reduced below the ZPF such that the energy becomes "negative." "Squeezing" is thus the control of quantum fluctuations and corresponding uncertainties, whereby one can squeeze the variance of one (physically important) observable quantity provided the variance in the (physically unimportant) conjugate variable is stretched/increased. The squeezed quantity possesses an unusually low variance, meaning less variance than would be expected on the basis of the equipartition theorem. We can exploit quantum squeezing to extract energy from one place in the ordinary vacuum at the expense of piling up excess energy elsewhere (Morris and Thorne, 1988).

Appendix B – *TH*εμ Methodology

In the formalism of the *TH*εμ methodology, the functions *T* and *H* are introduced by requiring that the Lagrangian for the motion of particles (with charge e_a and mass m_{0a} for the a^{th} particle), under the joint action of gravity and the electromagnetic field A_α ($\alpha \equiv$ spacetime vector components), be expressed in the canonical form

$$L = \sum_a \int \left(-m_{0a}\sqrt{T - Hv_a{}^2} + e_a A_\alpha v_a{}^\alpha \right) dt + \left(8\pi\right)^{-1} \int \left(\varepsilon \mathbf{E}^2 + \mu^{-1}\mathbf{B}^2 \right) d^3x\, dt \qquad \text{(B.1);}$$

where the arbitrary functions *T*, *H*, ε, and μ are functions of the metric (a.k.a. gravitation field), $v_a{}^\alpha$ is the a^{th} particle four-vector velocity, and A_α is the electromagnetic field four-vector potential, ***E*** and ***B*** are the electric and magnetic field strengths, and (B.1) is in geometrodynamic natural units ($\hbar = c_0 = G = \varepsilon_0 = \mu_0 = 1$). The Lagrangian characterizes the motion of charged particles in an external gravitational field by the two functions *T* and *H*, and characterizes the response of the electromagnetic fields to the external gravitational field by the two functions ε and μ. For all standard (metric) theories of gravity, the four functions are related by

$$\varepsilon = \mu = \sqrt{\frac{H}{T}} \qquad \text{(B.2);}$$

and ***every*** metric theory of gravity satisfies this relation, such that the Einstein Equivalence Principle is satisfied.

AFRL-PR-ED-TR-2003-0034
Primary Distribution of this Report:

AFRL/PRSP (15 CD)
Dr. Frank Mead
10 E. Saturn Blvd
Edwards AFB CA 93524-7680

AFRL/PRSA (1 CD)
Dr. Jean-Luc Cambier
10 E. Saturn Blvd.
Edwards AFB CA 93524-7680

AFRL/PR (1 CD)
Dr. Alan Garscadden
1950 Fifth Street
Building 18
Wright-Patterson AFB, OH 45433-7251

AFRL/PR Technical Library (2 CD + 1 HC)
6 Draco Drive
Edwards AFB CA 93524-7130

Chemical Propulsion Information Agency (1 CD)
Attn: Tech Lib (Dottie Becker)
10630 Little Patuxent Parkway, Suite 202
Columbia MD 21044-3200

Defense Technical Information Center
(1 Electronic Submission via STINT)
Attn: DTIC-ACQS (Pat Mawby)
8725 John J. Kingman Road, Suite 94
Ft. Belvoir VA 22060-6218

Dr. Eric Davis (10 CD)
4849 San Rafael Ave.
Las Vegas, NV 89120

Dr. Dana Andrews (1 CD)
P.O. Box 36
Leavenworth, WA 98826

Dr. Jim Degnan (1 CD)
AFRL/DEHP
Kirtland AFB, NM 87117

Dr. Greg Benford (1 CD)
Physics Department
University of California
Irvine, CA 92717

Dr. Jim Benford (1 CD)
Microwave Sciences, Inc.
1041 Los Arabis Ln.
Lafayette, CA 94549

Dr. Gary L. Bennett (1 CD)
7517 West Devonwood Dr.
Boise, ID 83703

Dr. Mitat Birkan (1 CD)
AFOSR/NA
801 N. Randolf St.
Arlington, VA 22203

Dr. Jon Campbell (1 CD)
P.O. Box 295
Harvest, AL 35749

Mr. Michael Libeau
NSWCDD
17320 Dahlgren Rd.
Attn: Code G23 Libeau
Dalgren VA 22448

Dr. Phil Carpenter (1 CD)
US Dept. of Energy
Oak Ridge National Laboratory
P.O. Box 2008, MS: 6269
Oak Ridge, TN 37831

Dr. Brice N. Cassenti (1 CD)
Pratt & Whitney Aircraft
400 Main Street – MS: 163-07
East Hartford, CT 06108

Dr. Chan K. Choi (1 CD)
Purdue University
School of Nuclear Engineering
West Lafayette, IN 47907

Dr. Terry Kammash (1 CD)
University of Michigan
Nuclear Engineering Dept.
Ann Arbor, MI 48109

Dr. Ingrid Wysong (1 CD)
EOARD
223-321-Old Merylebone Rd.
London NW1 5th
United Kingdom

Dr. Robert Frisbee (1 CD)
JPL, MS 125-109
4800 Oak Grove Dr.
Pasadena, CA 91109

Dave Froning (1 CD)
Flight Unlimited
5450 Country Club
Flagstaff, AZ 86004

Geroge D. Hathaway (1 CD)
Hathaway Consulting Services
39 Kendal Ave.
Toronto, Canada, Ontario
Canada M5R 1L5

Clark W. Hawk, Director (1 CD)
Propulsion Research Center
University of Alabama in Huntsville
5000 Technology Drive, TH S-266
Huntsville, AL 35899

Alan C. Holt (1 CD)
NASA/Johnson Space Center
Code OD
Houston, TX 77058

Dr. Steven Howe (1 CD)
19 Karen Lane
Los Alamos, NM 87544

Mike Kaiserman (1 CD)
Raytheon Missile Systems Company
Bldg 805, M/S C3
Tucson, AZ 85734

Dr. George Miley (1 CD)
University of Illinois, Dept. of Nuclear Engr.
214 Nuclear Engineering Laboratory
103 South Goodwin Ave.
Urbana, IL 61801

Marc Millis (1 CD)
NASA Glenn Research Center
M.S. SPTD-2
21000 Brookpark Road, MS: 86-2
Cleveland, OH 44135

Dr. Jordon Kare (1 CD)
222 Canyon Lakes Pl.
San Ramon, CA 94583

Ron J. Kita (1 CD)
87 Shady Springs DR.
Doyelstown, PA 18901

Dr. Gerald L. Kulcinski (1 CD)
Nuclear Engineering Dept.
University of Wisconsin
1500 Johnson Dr.
Madison, WI 53706

Dr. Geoffrey A. Landis (1 CD)
Sverdrup Technology
21000 Brookpark Rd., MS 302-1
Cleveland, OH 44135

Dr. Michael LaPointe (1 CD)
NASA Lewis Research Center, MS: SPTD-1
21000 Brookpark Rd.
Cleveland, OH 44135

Dr. Sheldon Meth (1 CD)
DARPA
Tactical Technology Office
3701 N. Fairfax Dr.
Arlington, VA 22203

Dr. Michael M. Micci (1 CD)
Prof. of Aerospace Engineering
233 E. Hammond Bldg.
University Park, PA 16802

Dr. Hal Puthoff (1 CD)
Institute for Advanced Studies
4030 Braker Lane, West
Suite 300
Austin, TX 78759

Dr. Eric E. Rice (1 CD)
Orbital Technologies Corp.
402 Gammon Place, Suite 10
Madison, WI 53719

Dr. Aurthur Morrish (1 CD)
DARPA/ATO
3701 N. Fairfax Dr.
Arlington, VA 22203

Dr. Paul Murad (1 CD)
Sr. Analyst, Director for Intel Production
Missile & Space Intel Center
Defense Intelligence Agency
Washington, DC 20340-6054

Dr. Brian Palaszewski (1 CD)
NASA Glenn Research Center
21000 Brookpartk Road, MS: 5-10
Cleveland, OH 44135

Dr. Alan Pike (1 CD)
DSAS
1988 Crescent Park Drive
Reston, VA 20190

Dr. Dennis Pelaccio (1 CD)
SAIC
8100 Shaffer Parkway, Suite 100
Littleton, CO 80127

Ben Plenge (1 CD)
101 W. Eglin Blvd
Suite 342
Eglin AFB, FL 32542-6810

Dr. James Powell (1 CD)
Plus Ultra Technologies, Inc.
25 East Loop Rd.
Stony Brook, NY 11970-3350

Mr. Charles A. Yost (1 CD)
Electric Spacecraft Journal
73 Sunlight Drive
Leicester, NC 28748

Dr. George Schmidt (1 CD)
NASA HQ
300 E. Street SW
Washington, DC 20546

Steve Squires (1 CD)
Directorate of Applied Technology
Test and Simulation
STEWS-DATTS-OO
WSMR, NM 88002

Robert Talley (1 CD)
Topaz 2000, Inc
3380 Sheridan Dr.
Suite 172
Amherst, NY 14226

Dr. Kenneth D. Ware (1 CD)
Defense Nuclear Agency
Simulation Technology
6801 Telegraph Road
Alexandria, VA 22310

Dr. Feiedwardt Winterberg (1 CD)
University of Nevada
Desert Research Institute
Reno, NV 89507

Dr. Young Bae (1 CD)
1101 Bryan Ave.
Suite C
Tustin, CA 92780

Dr. Thomas M York (1 CD)
1215 Inverary Pl.
State College, PA 16801

Dr. Robert J. Barker (1CD)
AFOSR/NE
801 N. Randolf St.
Arlington, VA 22203

Time Travel: Time Dilation

Daniel Buzzo
University of the West of England
Department of Computer Science and Creative Technology,
Coldharbour Lane,
Bristol, UK
daniel.buzzo@uwe.ac.uk

In this paper I discuss the theory and actuality of the effects of Time Dilation, as predicted by Einstein’s Special Relativity. Alongside this the research investigates the visible, experiential effects of most personal form of Time Travel from a personal, phenomenological perspective, illustrated through digital media.

The body of work, this paper and an accompanying book of modified digital images, recalls the Hafele-Keating experiment of October 1971 and parallels the Quantified Self experiments of diary photography and personal analytics in a holistic, interconnected way.

The work tracks 12 months of air travel and illustrates with practical data the physics and mathematics behind the theory and actuality of Time Dilation. The research combines the interdisciplinary worlds of Computer Arts with Data and Scientific Visualisation to create a tangible collision between the visualisation of the personal and illustration of theory

The observations are documented in ethnographic, photo essay illustrations as an investigation into the mathematics and physics of personal and interpersonal time. Using situated imaging presented as a practice-based body of work to communicate the abstract world of very small time periods and the direct relevance of Einstein’s work on the personal and perceptual world we inhabit. Contrasting Newtonian mechanics and Einsteinian space-time the work seeks to illustrate the personal nature of how the reality of time travel influences every aspect of the interpersonal

Time dilation. Time travel. General relativity. Special relativity. Visual thinking. Photography. Visualisation. Practice-based research. Art.

1. INTRODUCTION

In 1971 two American researchers, J.C. Hafele and R. E. Keating, conducted an experiment.

They placed two caesium atomic clocks on passenger airplanes and flew them in opposite directions around the globe to test a hypothesis first posited in Einstein's theory of special relativity.

Their aim was to measure the effects of relativity on these highly accurate devices - the predictions indicated that the eastward flying clock would lose 40ns and the westward gain 275ns. A nanosecond is equal to one billionth of a second (10^{-9} or $^{1}/_{1,000,000,000}$ s). To compare, one nanosecond is to one second as one second is to 31.7 years.

> During October, 1971, four cesium atomic beam clocks were flown on regularly scheduled commercial jet flights around the world twice, once eastward and once westward, to test Einstein's theory of relativity with macroscopic clocks. From the actual flight paths of each trip, the theory predicted that the flying clocks, compared with reference clocks at the U.S. Naval Observatory, should have lost 40+/-23 nanoseconds during the eastward trip and should have gained 275+/-21 nanoseconds during the westward trip ... Relative to the atomic time scale of the U.S. Naval Observatory, the flying clocks lost 59+/-10 nanoseconds during the eastward trip and gained 273+/-7 nanosecond during the westward trip, where the errors are the corresponding standard deviations. These results provide an unambiguous empirical resolution of the famous clock ‘paradox’ with macroscopic clocks. (Hafele & Keating 1972)

The results showed that compared to stationary clocks in the laboratory the eastward clock lost 59ns and the westward gained 273ns. Whilst there has been discussion of the accuracy and therefore reliability of the measurements the experiment is commonly held up as one of the first to give practical evidence of the physical effects of time dilation.

2. SPECIAL RELATIVITY AND TIME DILATION

In special relativity Einstein States that the duration of time will pass at different rates when comparing an object at rest versus an object in motion. The greater the velocity of the object in motion, the closer to the speed of light, c, the greater the effect of what is known as 'time dilation'

The effect of this phenomenon is significant at speeds close to the constant of light speed but becomes exponentially less as the object in question approaches rest.

$$t' = \frac{t}{\sqrt{1 - \frac{v^2}{c^2}}}$$

Figure 1: *The mathematical relationship of time, velocity and the speed of light describing Time Dilation*

Unless our velocity is a substantial fraction of the constant speed of light the dilation effect (γ) is approximately 1. This, combined with our extremely limited lifespan is why we don't immediately notice time dilation at ordinary speeds. The fastest speed most humans will achieve, an airplane travelling near the speed of sound, gives a time dilation where γ = 1.0000000000005.

In other words, 1 second for a passenger on the plane would pass as 1.0000000000005 seconds for a stationary observer.

Time effectively passes more slowly for the traveller relative to the observer.

3. THE REALITY OF THE EFFECT

Whilst there is discussion of the validity of the results of the 1971 Hafele & Keating experiment, particularly around the 'corrections' made to their data at publication, their initial observations are clearly aligned with the predicted results to be expected from the mathematics for time dilation.

As Reinhardt *et al* (2007) note:

> Time dilation is one of the most fascinating aspects of special relativity as it abolishes the notion of absolute time

In their 2007 paper they investigate the effects of time dilation with even more accurate atomic clocks, adding more experimental evidence consistent with special relativity. There are also numerous other experiments, such as those into muon decay, that provide additional practical evidence that the effect described is real and measurable.

Figure 2: *Over Dorset: Duration 55 minutes*

4. IMPLICATIONS FOR EVERYDAY LIFE

The practical implications for everyday life at first appear intangible when one considers the seemingly miniscule time periods being discussed. Even taking some of the most extreme examples one can imagine being feasible, such as that of a cosmonaut living in a fast low earth orbit, circumnavigating the earth every 90 minutes gives γ of approximately 1.0000000003.

If one considers our astronaut in orbit for two years, the Time Dilation due to special relativity would give an increase in lifespan of approximately 20 milliseconds. A millisecond is a thousandth (10^{-3} or $^{1}/_{1,000}$) of a second.

This gap of 20 milliseconds, or two hundredths of a second, are suddenly well within human scale perception and understanding. This is a common measured gap in motor racing and fast sports like downhill skiing. Even the record for the 100m sprint is now is 9.58 seconds, run by Usain Bolt at the World Athletics championships in Berlin in 2009.

Scales in milliseconds are spaces and durations that even humans with our modest lifespans can perceive and understand.

As Ed Lu, Science Officer on the International Space Station writes, from orbit, in his blog post on experiments in 'Relativity':

> After our 6 months in space, we will have actually aged slightly less than everyone else on the ground because of an effect called time dilation. It isn't by much (about 0.007 seconds), but it is one side benefit of flying in space!

Though the effects of time dilation at human scale speeds are often imperceptibly small they are nonetheless real. Seeing the implications of this reflected in everyday life reveals the truly personal nature of the time travel that we undertake in everything we do.

The realisation that time dilation is a tangible and observable phenomena that affects ourselves and everything around us was given heightened poignancy by spending large amounts of time flying at altitude and high speed. Observing the curvature of our planet and seeing the dark sky at the edge of space overhead, watching the mountains and deserts as they slid effortlessly under the wings of successive aeroplanes. Being able to observe the size of the individual against the backdrop of a macro-cosmic scale all the while reflecting on the fact that to a subatomic particle travelling near the speed of light, the universe is about four weeks old and it can be crossed in a matter of months.

> Nature can produce even larger particle energies. Some particles striking the Earth's upper atmosphere have energies that exceed 2*1020 eV. If such particles are protons (with mass of about 1 GeV), their speeds would be 0.999 999 999 999 999 999 999 995 c. For them, γ is 1011. Now the age of the universe is about 13 billion years for us, but for such particles, the age of the universe would be about (13 billion years/1011), ie about a month. Such a particle could cross the visible universe in a matter of months (their time).

This twist of perspective, the deliberate 'making strange' that Shlovsky (1917) describes occurs when translating the abstract of the macrocosmic to the intimacy of the personal. The act of comparing and contrasting macro-scale physics and mathematics with recordings of human scale observations evidence reveals useful and potentially significant insights into the nature of the world we actually inhabit.



Figure 3: *Sunset over Northern China. Duration: 10 hours 50 minutes*

5. THE PICTORIAL AS PRACTICE-BASED RESEARCH

As Blevis (2011) so eloquently puts it, as an introduction to the extensive list of uses of digital imagery in design thinking.

> **Visual thinking** is the use of imagery and other visual forms to make sense of the world and to create meaningful content. Digital imagery is a special form of visual thinking, one that is particularly salient for HCI and interaction design

Alongside the descriptions of digital imagery as a *'form of information'* and a '*shared and externalised memory and cognition'* (Blevis 2012) I would argue that practice-based research, when used as an investigative tool, can assist in revealing and documenting subtle but important non-verbal evidence and also provide compelling and persuasive arguments within presentation of research findings and conclusions. The research approach taken in this area is explicitly practice-based, rooted within contemporary lens based digital media and video art. The investigative material presented as the counterpart to this research paper was collated from hundreds of minutes of digital video and several hundreds of digital still images taken while airborne on commercial passenger aircraft during January - December 2013. Taken over the course of 44 flights, totalling over 80 hours airborne the visual material is published as a 42 page visual essay, also containing text elements and descriptions taken from this academic paper.

***Figure 4**: Sunset over London. Duration: 55 minutes*

6. REALISATION OF EFFECT ON THE PERSONAL

Having recorded the number of flights, durations and distances the calculations based upon the mathematics of special relativity, as discussed earlier show that.

Given 44 flights totalling 85 hours and 20 minutes or approximately 5120 minutes flying time. gives 307,200 seconds of travel per year.

If $\gamma = 1.0000000000005$ when travelling at or near the speed of sound, gives a dilation of 0.0000001536 seconds.

To slip one second from base reference, such as the clock sat on my kitchen table I need to travel at my present annual rate for 6,510,416 Years.

Or to put it a different way, travel for a little over 260,000 years to slip one frame out of sync on a standard rate video camera.

7. CONSIDERING PHOTOGRAPHY IN EVIDENCE

When collating the increasing amounts of video and photographic material recorded whilst airborne, travelling at or near the speed of sound, the overwhelming sensation of velocity, of speed, of travel is ever-present. Viewed at a macro scale the visual material illustrates this distancing, sliding nature of objects moving in a larger framework. It supports the realisation that the terra firma so often taken as a baseline for observation is in itself only a small part of a larger perspective. The perspective that the proprioceptive nature of our observations of time, informed by the physicality of the form we have evolved and the life span perspective we consider as a norm and useful context are challenged by the linking of these measurable effects. The effects of the micro-scale variations in time seen in contrast to the macro-scale movement around the curve of the earth.



***Figure 5:** An airplane travelling near the speed of sound gives a time dilation where γ = 1.0000000000005*

The visual material, when presented as an adjunct to the evidence of the universal but intimately personal nature of the effects of time dilation help communicate the simple fact that we are all time travelling. Pursuing our own clearly delineated paths and durations relative to each other. Rather than there being one universal time that exists everywhere, for everyone, all at the same moment the personal implication that there is real evidence to prove that this is an illusion is both moving and compelling.

Sitting in an airline seat riding at the edge of space, looking down on the oceans, seas, cities, forests and deserts, seeing terra firma for the illusion that it is. Not a constant underlying grid of space and time - the universal yard stick and the universal clock, such as Newtonian physics promised as it replaced the Aristotelian events-make-time view of the world that had reigned before in popular consciousness.

Realising that the H&K caesium clock from 1971 could be sat beside me, ticking away in its own little timetrack, ticking to a completely separate rhythm than its counterpart clock sat on my kitchen table at home. Realising that the slipping and sliding of our lives against each other is our own intimate version of time travel, we all move forward as future becomes present becomes past but the durations we experience, and that actually occur, and when ***now*** happens is subtly different for everyone. The time we each experience actually does expand and contract as we move in space.

Figure 6: *Frost over Mongolia. Duration: 10 hours 55 minutes*

The illusion of the Newtonian ideal of a universal timescale, the idea of a 'universal now' is disappearing and being replaced by the ideas of general relativity. Of a universe full of individual 'nows' all unique and all moving independently. This change is akin to seeing the universe of unique, individual 'nows' at a human, personal scale and seeing a life travelling, sliding, back and forth in time against the 'nows' of those around one.

The important element this body of work seeks to describe is not physics or even a discussion of physics but an explanation of physics and the revelatory moment of seeing it in 'real' experienced life. This work seeks to relate that revelatory moment and articulate it with the artefacts, the book and the paper, telling the story of seeing how each and every one of us is travelling in time, independently, uniquely, every day.

> To see a World in a Grain of Sand
> And a Heaven in a Wild Flower,
> Hold Infinity in the palm of your hand
> And Eternity in an hour. (William Blake)

8. REFERENCES

Bergson, H. (1923) *The Creative Mind: An Introduction to Metaphysics*, Citadel Press [1992]

Blevis, E. (2011) Digital imagery as meaning and form in HCI and design: an introduction to the Visual Thinking Backpage Gallery. Interactions 18, 5 (September 2011), 60-65.

Blevis, E, Churchill. E, Odom. W, Pierce.J, Roedl.D,, and Wakkary.R. (2012) Visual thinking & digital imagery. In *Proc. CHI EA '12*. ACM, New York, NY, USA, 2715-2718.

Callender, C., and Edney, R. (2001). *Introducing Time.* Icon Books. ISBN 1-84046-592-1.

Hafele J.C., and Keating. R. E. (1972) Science 177, 166.

Lu. E, 'Expedition 7, Relativity' Blog Post. http://spaceflight.nasa.gov/station/crew/exp7/luletters/lu_letter13.html (retrieved 20 March 2014).

Muon Experiment in Relativity. http://hyperphysics.phy-astr.gsu.edu/hbase/relativ/muon.html (retrieved 5 March 2014).

Reinhardt, S. *et al.* (2007). Test of relativistic time dilation with fast optical atomic clocks at different velocities. Nature Physics 3 (12): 861–864.

Shklovsky, V. (1917) *Art as Technique*. In: Russian Formalist Criticism: Four Essays. Trans. Lee T. Lemon and Marion J. Reis. University of Nebraska Press, Lincoln, 1965.

The Quantified Self. http://quantifiedself.com/ (retrieved 4 December 2013).

Toothman, J. How Do Humans age in space? HowStuffWorks. http://science.howstuffworks.com/humans-age-in-space.htm (retrieved 24 April 2012).

US 20030230675A1

(19) United States

(12) Patent Application Publication (10) Pub. No.: US 2003/0230675 A1

St. Clair (43) Pub. Date: Dec. 18, 2003

(54) ROTOR INDUCTANCE PROPULSION SYSTEM

(76) Inventor: **John Quincy St. Clair**, San Juan, PR (US)

Correspondence Address:
John St. Clair
Hyperspace Research Institute
52 Kings Court, 4A
San Juan, PR 00911 (US)

(21) Appl. No.: **10/170,847**

(22) Filed: **Jun. 12, 2002**

Publication Classification

(51) **Int. Cl.^{7}** **B64G 1/40**; B64G 1/42

(52) **U.S. Cl.** **244/172**

(57) ABSTRACT

The invention is a spacecraft having a circular, domed hull around which dual electrically-charged rotors one above the other are counter-rotating on the edge of the hull. Embedded in the hull are three solenoids which create a positive vector potential at the rotors. The surface charge density times the radius times the vector potential times the area of the rotors creates an angular momentum in the vertical direction. This angular momentum produces a positive spacetime curvature over the dome of the hull and a negative spiking spacetime compression over the rotors. By machining circumferential grooves of decreasing height along the radius of the rotor, a negative surface inductance is generated. This negative inductance gradient times the negative spacetime compression time the rotor current density squared times the rotor area squared is a positive lift force on the spacecraft.



Figure 1



Figure 2



Figure 3



Figure 4



Figure 5

$$A = \frac{n\,I\,a^2}{2\varepsilon_0 c^2}\frac{1}{r'}$$

Figure 6

$$A \equiv \frac{1}{\mathrm{m}}\frac{\mathrm{coul}}{\mathrm{sec}}\mathrm{m}^2\frac{\mathrm{m}^2\mathrm{kg\,m}}{\mathrm{coul}^2\,\mathrm{sec}^2}\frac{\mathrm{sec}^2}{\mathrm{m}^2}\frac{1}{\mathrm{m}} = \frac{\mathrm{kg\,m}}{\mathrm{sec\,coul}}$$

Figure 7



Figure 8


A
B
C
D
E
F
G
H
J
K

Figure 9


Im
ωr
$\frac{\pi}{2}$
r
π
ωt
Re
ω
$\omega^2 r$

Figure 10

$$\begin{aligned}
S_k &= \left[-\sigma r e^{i\omega t} + \sigma r e^{-i\omega t}\right] \frac{n I a^2}{2\varepsilon_0 c^2} \frac{n_z \text{area}}{r'} \\
&= -\left[e^{i\omega t} - e^{-i\omega t}\right]\left[\sigma r \frac{n I a^2}{2\varepsilon_0 c^2} \frac{n_z \text{area}}{r'}\right] \\
&= -\left[e^{i\omega t} - e^{-i\omega t}\right] K
\end{aligned}$$

Figure 11

$$S \equiv \frac{\text{coul}}{\text{m}^2}\,\text{m}\,\frac{1}{\text{m}}\frac{\text{coul}}{\text{sec}}\,\text{m}^2\,\frac{\text{m}^2}{\text{coul}^2}\frac{\text{kg}\,\text{m}}{\text{sec}^2}\frac{\text{sec}^2}{\text{m}^2}\frac{\text{m}^2}{\text{m}} = \frac{\text{kg}\,\text{m}^2}{\text{sec}}$$

Figure 12

$$e^{i\omega t} - e^{-i\omega t} = 2 i \,\text{Sin}[\omega t]$$

Figure 13

$$S_k = -2 i K \,\text{Sin}[\omega t]$$

Figure 14

$$ds^2 = \ldots - 4\frac{S}{r}dtd\theta = \ldots 8\frac{iK\,\mathrm{Sin}[\omega t]}{r}dtd\theta$$

Figure 15

$$g_{\mu\nu} = \begin{array}{c|cccc|} & t & r & \theta & z \\ \hline t & -1 & 0 & 4\frac{iK\,\mathrm{Sin}[\omega t]}{r} & 0 \\ r & 0 & 1 & 0 & 0 \\ \theta & 4\frac{iK\,\mathrm{Sin}[\omega t]}{r} & 0 & r^2 & 0 \\ z & 0 & 0 & 0 & 1 \end{array}$$

Figure 16



Figure 17

$$\text{Magnetic Energy} = -L\,K\,J^2\,A^2$$

Figure 18

$$\text{Magnetic Energy} \equiv -\frac{\text{kg}\,\text{m}^2}{\text{coul}^2}\frac{1}{\text{m}^2}\frac{\text{coul}^2}{\text{sec}^2\,\text{m}^2}\text{m}^4 = -\frac{\text{kg}\,\text{m}^2}{\text{sec}^2} = -\text{joule}$$

Figure 19



Figure 20

$$h = h_0 - (r - r_0)\left(\frac{h_0 - h_1}{W}\right)$$

Figure 21

$$\frac{dL}{dr} = \mu n^2 \, 2\pi w \frac{\partial}{\partial r}\left(r\left(h_0 - (r - r_0)\left(\frac{h_0 - h_1}{w}\right)\right)\right)$$

$$\frac{dL}{dr} = \mu n^2 \, 2\pi w\left(h_0 - \frac{(h_0 - h_1)(2r - r_0)}{w}\right)$$

Figure 22



Figure 23

$$F = \frac{dL}{dr} K_c J^2 A^2 = \frac{\mathrm{kg\,m}}{\mathrm{coul}^2}\frac{1}{\mathrm{m}^2}\frac{\mathrm{coul}^2}{\mathrm{sec}^2\,\mathrm{m}^2}\mathrm{m}^4 = \frac{\mathrm{kg\,m}}{\mathrm{sec}^2} = \mathrm{newton}$$

ROTOR INDUCTANCE PROPULSION SYSTEM

BRIEF SUMMARY OF THE INVENTION

[**0001**] The invention, which is the object of my present application, is a spacecraft with a circular, domed hull around which are located dual electrically-charged counter-rotating rotors. The top surface of the upper rotor is etched with circular metallic grooves which give the rotor a surface inductance. The groove height decreases from the inside radius to the outside radius of the rotor giving it a radial inductance gradient. The surface charge density times the angular velocity produces a current density. The counter-rotating rotors produce a negative spacetime curvature over the rotors. The negative surface inductance gradient times the negative spiking spacetime curvature times the current density squared times the area squared is the positive lift force on the rotor.

REFERENCE WORKS

[**0002**] *Gravitation*, Wheeler

[**0003**] *Traveling-Wave Tubes*, The Bell System Technical Journal, Vol. XXIX, January 1950, No. 1, J. R. Pierce.

[**0004**] *The Magnetron as a Generator of Centimeter Waves*, The Bell System Technical Journal, Vol. XXV, April 1946, No. 2, J. B. Fisk, H. D. Hagstrum, P. L. Hartman.

[**0005**] *Lectures on Physics*, Richard Feynman

[**0006**] *Geometry of Electromagnetism*, Paul Hammond

BACKGROUND OF THE INVENTION

[**0007**] I was reading several articles about the development of the magnetron during World War II in the Bell System Technical Journal. I was trying to understand why the device resonates because it must contain a spring constant which would arise from an inductance and capacitance due to the geometry of the cavity. As given by Feynman, inductance of a solenoid is the permeability of space times the turns per length squared times the volume of the solenoid. Referring to **FIG. 1**, the magnetron cavity (A) has a circular region connected to a planar region. The electrical current flows on the sides of the cavity shown by the arrows (B). In this case, there is only one turn per height of the cavity times the volume of the cavity times the permeability which produces the inductance. The two planar regions produce a capacitance across the ends which creates the resonant frequency.

[**0008**] From my previous patent application Dual Rotor Propulsion System I know that the two rotors produce a current density in the angular direction along the rotor. If I spread out the magnetron cavity into a circular groove around a rotor, then the current would flow on the side walls enclosing the groove volume. The rotors also produce a spacetime curvature profile as shown in **FIG. 2**. Curve (A) is a positive spacetime curvature tension over the dome. Curve (B) is a negative spiking spacetime curvature over the rotors. The curvature is measured in inverse meter squared. So the surface inductance times the negative curvature times the current density squared times the rotor area squared is magnetic energy. The differential of the magnetic energy would be a force. So there has to be a gradient of the surface inductance. The volume element of a groove is equal to the circumferential length times the height times the width of the groove. The easiest is to vary the height with radius. Since the curvature is negative, the gradient has to be negative as well in order to get a positive lift force. Thus the height goes from large to small from the inside to the outside radius.

SUMMARY OF THE INVENTION

[**0009**] The invention relates to a spacecraft with a domed, circular hull of elliptical cross-section having dual electrically-charged counter-rotating rotors located one above the other on the edge of the hull. The upper rotor is positively charged and rotates clockwise with a negative angular velocity per the right-hand rule. The lower rotor is negatively charged and rotates with a positive angular velocity. The current density is the surface charge density times the velocity of the rotor. This particular combination of velocity and charge produces an angular momentum which creates a negative spiking spacetime curvature over the rotors.

[**0010**] The top surface of the rotor is etched or machined with circular grooves around the rotor. This creates a surface inductance which is equal to the permeability of space times the turns per length squared times the volume of the groove. In this case, there is only one turn per height of the groove. If the height of the groove decreases from one groove to the next, then there is a negative surface inductance gradient in the radial direction. So the lift force on the rotors would be the negative surface inductance gradient times the negative spacetime curvature times the current density squared times the rotor area squared.

STATEMENT REGARDING FEDERALLY SPONSORED RESEARCH OR DEVELOPMENT

[**0011**] Not Applicable.

A BRIEF DESCRIPTION OF THE DRAWINGS

[**0012**] **FIG. 1**. Perspective of magnetron cavity.

[**0013**] **FIG. 2**. Spacetime curvature G_{zz} over hull and rotor.

[**0014**] **FIG. 3**. Perspective view of spacecraft with dual rotors.

[**0015**] **FIG. 4**. Wire frame view of three solenoids.

[**0016**] **FIG. 5**. Vector potential equation for solenoid.

[**0017**] **FIG. 6**. Units of vector potential.

[**0018**] **FIG. 7**. 3D graph of vector potential using three solenoids.

[**0019**] **FIG. 8**. Perspective of vector potential along rotors.

[**0020**] **FIG. 9**. Rotor mechanics diagram using exponential representation.

[**0021**] **FIG. 10**. Angular momentum equation due to vector potential and rotating charged rotors.

[**0022**] **FIG. 11**. Units of angular momentum.

[**0023**] **FIG. 12**. Exponential equation for twice imaginary sine of the angle.

[0024] **FIG. 13**. Angular momentum equation for g metric tensor.

[0025] **FIG. 14**. Angular momentum term for elemental line length ds^2.

[0026] **FIG. 15**. The g metric tensor containing the angular momentum.

[0027] **FIG. 16**. The spacetime curvature tension G_{zz} versus radius due to angular momentum.

[0028] **FIG. 17**. Magnetic energy equation.

[0029] **FIG. 18**. Units of magnetic energy.

[0030] **FIG. 19**. Cross-section of rotor showing groove height gradient.

[0031] **FIG. 20**. Equation for the height h of the rotor groove as a function of radius.

[0032] **FIG. 21**. Equation for the groove inductance gradient.

[0033] **FIG. 22**. Plot of the groove inductance gradient as a function of radius showing that it is negative at the rotor.

[0034] **FIG. 23**. Lift force on rotors due to inductance gradient, compression curvature, rotor current density and area.

DETAILED DESCRIPTION OF THE INVENTION

[0035] 1. Referring to **FIG. 3**, the spacecraft has a circular, domed hull of elliptical cross-section with dual electrically-charged counter-rotating rotors one above the other on the edge of the hull.

[0036] 2. Referring to **FIG. 4**, embedded within the hull are three solenoids or current loops carrying a constant electrical current in the positive sense per the right-hand rule.

[0037] 3. Referring to **FIG. 5**, Feynman has shown that the vector potential {A} of a solenoid is equal to the number of turns per length {n} times the current {I} times the radius of the solenoid {a} squared divided by half the permittivity of space $\{\epsilon_0\}$ times the speed of light {c} squared times the radius {r'} prime from the center of the coil to some location in space such as the rotors. It has been found by physicists Bohm and Aharanov that the vector potential field is not confined to an infinitely long solenoid as is the magnetic B field. The vector potential has units of kilogram-meter per second-coulomb as seen in **FIG. 6**.

[0038] 4. Referring to **FIG. 7**, the three solenoids of varying radius and area produce a positive vector potential at the centerline of the rotors as seen in the graph.

[0039] 5. This graph is then rotated ninety degrees so that it can be located in relation to the rotors as seen in **FIG. 8**. The vector potential (D), which is created by solenoids (A,B,C), passes through rotors (E) and (H). Rotor (E), which has a positive charge (G), is rotating clockwise (F), and rotor (H), which has a negative charge (K), is rotating counter-clockwise (J).

[0040] 6. Referring to **FIG. 9**, rotor mechanics uses the exponential function for the harmonic motion of the rotor. The radius is $\{r\ e^{i\omega t}\}$ which when differentiated with respect to time becomes a velocity $\{i\ \omega\ r\ e^{i\omega t}\}$ where the imaginary {i} is a 90° phase lead which makes the velocity tangential to the rotor.

[0041] 7. The rotor surface charge {σ sigma} is rotating around at some radius {r}. For the upper rotor the surface charge density is positive (+σ} but the rotor has a negative angular velocity {−ω}. For the lower rotor, the surface charge density is negative {−σ} but the rotor has a positive angular velocity {+ω}. So the combined surface charge rotation is $\{-\sigma\ r\ e^{i\omega t}+\sigma\ r\ e^{-i\omega t}\}$. This charge rotation times the positive vector potential due to the solenoids times the rotor surface area is equal to angular momentum S as shown in **FIG. 10**. The units are given in **FIG. 11**. The angular momentum is equal to the negative of the difference of the exponentials times a constant. I then recalled that this difference is equal to twice imaginary sine of the angle as shown in **FIG. 12**.

[0042] 8. Referring to **FIG. 13**, the angular momentum is equal to minus two times the imaginary number times a constant times the sine of the rotational angle. In most of my spacecraft designs, the electromagnetic fields determine the flow rate of angular momentum. When the flow rate is integrated with respect to time, the angular momentum becomes imaginary. In this invention, the angular momentum is imaginary due directly to the rotors. The importance of being imaginary is that the radius resonates with the angular momentum. In some spacetime curvature equations, the denominator has a term equal to the radius to the fourth power plus twice the square of the angular momentum. In spacetime units, angular momentum is viewed as meter squared. So the square of imaginary angular momentum is negative angular momentum equal to negative meters to the fourth power. So at some radius, these two terms are equal, the denominator goes to zero, and the spacetime curvature becomes infinitely-large, creating a huge spike.

[0043] 9. This next section calculates the spacetime curvature from the equation for the angular momentum.

[0044] 10. Referring to **FIG. 14**, the elemental length ds^2 is curved by the presence of the angular momentum which is one of the energies, such as mass, charge, and electromagnetic fields, that Einstein showed can curve spacetime. Because the angular momentum is pointing in the vertical z-direction, due to the direction of the unit normal vector to the surface of the rotor, it rotates around in the angular direction {dtdθ} as found in cylindrical coordinates {t,r,θ,z}.

[0045] 11. In gravitational physics there is a g metric tensor which is a measure of length in spacetime coordinates. It is a 4 by 4 matrix with rows and columns equal to the cylindrical coordinates. Referring to **FIG. 15**, the diagonal of the matrix is $\{-1,1,r^2,1\}$ where the minus one corresponds to time which is Einstein's convention. Half the angular momentum goes in the {tθ} slot of the g metric tensor, and the other half goes in the {θt} slot.

[0046] 12. From this g metric tensor, Einstein's G curvature tensor can be calculated in the various directions. In Einstein's General Theory of Relativity, his equation is G=8πT where G is the spacetime curvature measured in inverse meter squared, and the T tensor is the stress-energy-momentum matrix containing all the electromagnetic pressures, mass and momentum components that curve spacetime. The spacetime curvature tension G_{zz} in the vertical direction, as a function of radius, is shown in **FIG. 16**. A positive curvature indicates that there is a spacetime tension over the hull which produces lift. The curvature has a large positive spike over the dome of the hull (A) which means that there is a large lift force over the center of the hull. The curvature then falls off and spikes with a negative spacetime curvature compression over the rotors (B). This curvature also oscillates back and forth a short distance due to the sinusoidal term. The problem is to convert this compression into a lift force which this invention solves.

[0047] 13. This next section shows how the spacetime compression over the rotors generates lift.

[0048] 14. As I mentioned, I have been reading some of the World War II magnetron scientific papers of the Bell System Technical Journal. It turns out that inductance of a solenoid is equal to the permeability of space times the number of wire turns per length squared times the volume of the solenoid. Imagine having a copper strip in the shape of the magnetron cavity in **FIG. 1**. The electrical current (B) flows around the height of the strip (A), so there is only one turn per the height. Then that is multiplied by the volume of the cavity and permeability to get the inductance. The inductor is storing magnetic energy equal to half the inductance times the current squared. In this invention, current density J in amp per meter is used rather than current. So taking a hint from this information, the magnetic energy would have to be related to the inductance times the square of the current density times the area squared of the rotor and times the negative spacetime curvature. The curvature is measured in inverse meter squared. That product produces a negative magnetic energy when in fact I want a positive force. This means that there has to be an inductance gradient in the equation instead of pure inductance and, furthermore, the gradient has to be negative in order to cancel out the negative sign of the compression curvature.

[0049] 15. The equation for the magnetic energy in terms of the inductance $\{\mathcal{L}\}$, curvature {K}, current density {J} and area {A} is shown in **FIG. 17** with the units in **FIG. 18**. The inductance in the equation is proportional to the volume of the circular groove in the top surface of the rotor. That volume is equal to {2π r h w} where {h] is the height of groove (depth) and {w} is the width located at some radius {r}. In terms of machining, it would be more difficult to machine a variable width groove rather than a deeper groove of a constant width. So I am going to say the gradient is in the radial direction with the height of the groove decreasing going from the inside radius to the outside radius as depicted in **FIG. 19**.

[0050] 16. **FIG. 20** gives the equation for the height of the groove along the radius of the rotor.

[0051] 17. **FIG. 21** gives the inductance gradient by differentiating the inductance with respect to the radius. The initial groove height ho is not very large, and the inductance gradient becomes negative at the rotor as seen in the graph of **FIG. 22**.

[0052] 18. Referring to **FIG. 23**, the lift force on the rotor is now positive due to the combined negative inductance gradient times the negative spacetime compression. The square of the negative current density is positive also. This means that that the top surface of the lower rotor can also have a surface inductance gradient which would double the lift force.

What I claim as my invention is:

1. A spacecraft having a circular, domed hull with dual electrically-charged counter-rotating rotors one above the other located on the edge of hull.

2. Said hull having embedded within it three or more solenoids which generate a positive vector potential at the rotors.

3. Said upper rotor having a positive surface charge density, and rotating clockwise in the negative direction per the right-hand rule.

4. Said lower rotor having a negative surface charge density, and rotating counterclockwise in the positive direction per the right-hand rule.

5. Said rotor surface charge density and velocity creating a negative current density on both rotors.

6. Said vector potential and rotating surface charge density on rotors generating an angular momentum in the vertical direction.

7. Said angular momentum, generating a spacetime curvature tension over the dome of the hull, and a negative oscillating spacetime curvature compression over the rotors.

8. Said rotors having circumferential grooves of decreasing height machined into the top surface of the rotors in order to create a negative surface inductance gradient.

9. Said negative surface inductance gradient times the negative spacetime curvature compression times the rotor current density squared times the rotor area squared generating a positive lift force on the spacecraft.

* * * * *

US 20060014125A1

(19) **United States**

(12) **Patent Application Publication** (10) **Pub. No.: US 2006/0014125 A1**

St. Clair (43) **Pub. Date: Jan. 19, 2006**

(54) **WALKING THROUGH WALLS TRAINING SYSTEM**

(76) Inventor: **John Quincy St. Clair**, San Juan, PR (US)

Correspondence Address:
JOHN ST. CLAIR
4A
52 KINGS COURT
SAN JUAN, PR 00911 (US)

(21) Appl. No.: **10/890,635**

(22) Filed: **Jul. 14, 2004**

Publication Classification

(51) **Int. Cl.**
G09B 19/00 (2006.01)

(52) **U.S. Cl.** **434/258**

(57) **ABSTRACT**

This invention is a training system which enables a human being to acquire sufficient hyperspace energy in order to pull the body out of dimension so that the person can walk through solid objects such as wooden doors.



Figure 1



Figure 2



Figure 3



Figure 4


C
b
B
c
a
A
d
ln(mass)
-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(wavelength)
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
-110
-120
-130
-140
-150
-160
-170
-180
-190

Figure 5


-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
-10 -20 -30 -40 -50 -60 -70 -80 -90 -100 -110 -120 -130 -140 -150 -160 -170 -180 -190
ln(wavelength)
C
b
B
c
D
A
a
d

Figure 6


-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
-110
-120
-130
-140
-150
-160
-170
-180
-190
ln(wavelength)
C
E
F
B
b
c
e
D
A
a
d

Figure 7


-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
-110
-120
-130
-140
-150
-160
-170
-180
-190
ln(wavelength)
A
B
C
D
E
F
G
H
a
b
c
d
e
f
g
h

Figure 8


C
E
F
B
b
h
c
g
i
e
D
f
H
G
I
A
a
d
ln(mass)
ln(wavelength)
-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
-110
-120
-130
-140
-150
-160
-170
-180
-190

Figure 9



Figure 10



Figure 11


-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
-110
-120
-130
-140
-150
-160
-170
-180
-190
ln(wavelength)
C
E
F
J
K
b
h
B
c
g
i
e
j
D
f
H
G
I
A
a
d

Figure 12


-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
-110
-120
-130
-140
-150
-160
-170
-180
-190
ln(wavelength)
a
b
c
d
e
f
g
A
B
C
D

Figure 13


-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
-110
-120
-130
-140
-150
-160
-170
-180
-190
ln(wavelength)
a
b
c
d
e
f
g
h
i
A
B
C
D
E
F
G

Figure 14


-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
-110
-120
-130
-140
-150
-160
-170
-180
-190
ln(wavelength)
H
B
C
D
E
A
a
F
b
G
c

Figure 15


-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
-110
-120
-130
-140
-150
-160
-170
-180
-190
ln(wavelength)
A
B
D
b
E
c
a
G
H
C
F
I

Figure 16


Start
Enter Data
Banner Length
Shoe Size
Weight
Calculate Stride Length
M
Load Banner Paper
Print Banner
Foot Prints
Use Timer
Walk
Generate Vortex

Figure 17


File Timer Window Help
?
Print Banner
Input
Weight (lbs)
Shoe size (inches)
Banner length (strides)
OK
Cancel
Help
Messages

Enter data:
weight (lbs)
shoe size (length in inches)
banner length (number of strides)

Figure 18


File
Timer
Window
Help
Print Banner
Messages

```
Mass = 99.79032139 kgs
Weight = 220 lbs
Shoe Size = 12 inches
Banner Length = 6 strides
Stride Length per second = 20 inches

Insert 11 banner sheets in printer.
```

Figure 19



Figure 20


Project Tree
Start
Enter Data
Continue
Load Banner Paper
Print Banner
Use Timer
Walk
Banner Length
Shoe Size
Weight
Note
OK

Load Banner Paper:
Remove cut sheets from printer,
raise banner switch on printer to up position,
insert sufficient paper into tray with open edge in,
choose Printer toolbar to print.

WALKING THROUGH WALLS TRAINING SYSTEM

BRIEF SUMMARY OF THE INVENTION

[0001] This invention is a training system that enables a human being to acquire sufficient hyperspace energy in order to pull the body out of dimension so that the person can walk through solid objects such as wooden doors.

BACKGROUND OF THE INVENTION

[0002] A human being is a hyperspace energy being living in a physical container or body that is comprised of 67% water. This high percentage of water makes this invention possible. Referring to **FIG. 1**, the hyperspace energy being receives energy from our dimension through seven vortices that run the length of the body. Each vortex connects to a separate hyperspace dimension having its own particular frequency. This arrangement allows for the development of seven modular energy components corresponding to the mind, spiritual eye, voice, body, abdomen, plasma energy ball (battery), and ground connection.

[0003] Vortex (A), known as the top vortex, supplies energy to the mind and provides a channel of communication to other entities in the universe. This channel has been tested up to 100,000 light years which is the diameter of the galaxy.

[0004] Vortex (B), known as the spiritual eye, has a hollow cone-like appearance surrounded by white, misty, low-density hyperspace energy. Because the eye is modular, the mind can project it to vast distances, a process known as remote viewing.

[0005] Vortex (C), known as the voice and hearing module, can also be projected to enormous distances in order to communicate verbally with other entities. Using the proper remote viewing instruments, it is possible to project both the eye and verbal modules to see and talk at the same time.

[0006] Vortex (D), known as the heart vortex, provides protective energy to the upper internal organs, arms and hands.

[0007] Vortex (E) provides protective energy for the lower organs such as the intestines, liver and kidneys.

[0008] Vortex (F), known as the battery of the body, consists of an orange-colored plasma energy ball about one to two inches in diameter. The body becomes paralyzed if this ball is removed from the body. When the hyperspace energy being leaves the body, the vortices close and the battery takes over in order to keep the body functioning. This vortex also plays a role in the creation of the astral energy baby that attaches to the fertilized egg.

[0009] Vortex (G) is the ground vortex which rotates in the counter-clockwise direction in order to provide an energy ground for the electrical circuit. All the other vortices rotate in the clockwise direction as seen from the front such that energy flows into the vortex according to the right-hand rule of physics.

[0010] Vortex (H) is the hand vortex which rotates counterclockwise on the right hand and clockwise on the left hand as seen looking at the palm. Thus there is a rotating flow of hyperspace energy between the two hands when the palms are facing each other.

[0011] Referring to **FIG. 2**, each vortex feeds energy into its own hyperspace module shown by the lettered box. In terms of quantum mechanics, each box is actually a potential energy well in which each module develops separately. At the time of death of the body, these modules are joined together as a single energy being. The process is powered by the plasma energy ball battery which also contains the logical instructions for assembly.

[0012] Different people, as tested by the pendulum on the hand vortex, have different vortex sizes. Three people were tested. The first person had almost no rotational movement showing very little energy. The second person had a vortex radius of one inch. Another had a vortex radius of four inches which covered his entire hand. The latter also has the ability to lift another human being, lying prone on a table, off the table by flowing low-density hyperspace energy into the person through the hand vortices. He has also experienced walking through a solid wooden door with a dog at his side. What this means is that there is a way, as described in this invention, of creating large energy vortices which will enable a person to acquire sufficient energy to walk out of dimension through solid objects such as wooden doors.

[0013] Researching the historical records, referring to the statue in **FIG. 3**, a humble black Catholic Dominican friar of the Santo Rosario Convent, by the name of San Martin de Porres, living in Peru in the 1500's, also developed this ability to walk through doors. For his beatification, many witnesses came forward to recount his extraordinary abilities. For example, a witness, who worked in the Convent, went to the cell of San Martin to ask for something to eat. When he reached the cell, he saw San Martin leaving with some medications apparently to heal someone sick. The witness waited by the open door of the cell for his return. After having waited awhile without being distracted by anything else, he saw said venerable brother fray Martin come out from his cell from the inside and call him by name. The witness was terrified, not understanding how this was possible.

[0014] The woman who gave me the statue told me that he would walk miles and miles each day to visit the poor. The task of walking means that there is a velocity involved. Because the body has mass, then there is a mass times a velocity, or momentum, involved in this ability. Notice also that the statue shows him walking with his right arm crossed over his left arm in the form of an X.

[0015] What this walking momentum means in terms of physics is given in the following analysis. The human body consists of 67% water. A water molecule consists of two hydrogen atoms and one oxygen atom having the atomic formula H_2O. The atomic weight of one atom of hydrogen is 1.008 awu. The atomic weight of one atom of oxygen is 16.000 awu. The molecular weight of one atom of water is therefore:

Weight of two atoms of hydrogen 2 × 1.008 awu =	2.016 awu
Weight of one atom of oxygen 1 × 16.000 awu =	16.000 awu
	18.016 awu

The formula weight is just the atomic weight expressed in grams. Thus the formula weight of water would be 18.016

grams or 0.018016 kilograms. According to Avogadro's law, the formula weight contains N=6.02×10^{23} molecules. Thus the mass of one water molecule is the formula weight divided by the number of molecules:

$$\text{mass} = \frac{.018016\text{ kg}}{N} = 2.99269103\cdot 10^{-26}\text{ kg}$$

$$\ln\left(\frac{\text{mass}}{1\text{ kg}}\right) = -58.77103943$$

[0016] According to Einstein's Special Theory of Relativity, energy is equal to the mass times the speed of light squared. The energy of a photon is equal to Planck's constant h times the frequency f of the photon. Equating these two energies shows that

$$E = \text{mc}^2 = hf = h\frac{c}{\lambda} = \frac{h}{c}\frac{c^2}{\lambda}$$

$$\Rightarrow m\lambda = \frac{h}{c}$$

$$\Rightarrow \ln(m) + \ln(\lambda) = \ln\left(\frac{h}{c}\right) = \text{base} = -95.91546344$$

which says that the natural logarithm of the mass plus the natural logarithm of the wavelength is equal to the natural logarithm of Planck's constant divided by the speed of light c, known as the base constant in the tetrahedron diagram. This diagram plots the mass versus wavelength in natural logarithms. Notice that the left hand side of the equation is the sum of mass and wavelength, so the right hand side must also be the same.

$$\ln\left(\frac{h}{c}\right) = \ln\left(\frac{\Omega\Lambda\ 2\pi\Lambda\ c}{c}\right) = \ln(\Omega\Lambda) + \ln(2\pi\Lambda)$$

where ΩΛ, known as the Planck mass, is the linear mass Ω of the universe times the bottom dimensional limit of the universe Λ, and 2πΛ is the bottom dimensional wavelength, known as the Planck wavelength. That is, our dimension is bounded by the Planck box having sides Planck mass and Planck wavelength. These boundaries have values:

$\ln(\Omega\Lambda)=-17.64290101$

$\ln(2\pi\Lambda)=-78.27256243$

[0017] Referring to **FIG. 4**, these two lines are plotted on the tetrahedron diagram. The Planck mass line (A) reflects off the sphere (C) and returns as the Planck wavelength (B) which shows the dual nature of quantum physics. This creates the Planck box (a,b,c,d) which is the boundary of our dimension.

[0018] Referring to **FIG. 5**, the mass of the water molecule is plotted as horizontal line (D) on the diagram. The energy of the water molecule is the mass times the speed of light squared.

$E=mc^2$

$\ln(c)=19.51860099$

$\ln(mc^2)=\ln(m)+2\ln(c)$

[0019] Referring to **FIG. 6**, a circle (E), having a radius equal to the speed of light squared, centered on the mass of the water molecule at the vertical axis, generates a circle (F), centered at the origin, that intersects (e) the mass of the water molecule at the Planck wavelength. That is, this intersection point sits right on the Planck box boundary between space and hyperspace. The radius of circle (F) is actually the mass of the water molecule divided by the speed of light squared.

$$E = \frac{m}{c^2} = m$$

$$\Rightarrow \frac{1}{c^2} = 1$$

$$\Rightarrow c = 1\frac{\text{meter}}{\text{sec}}$$

$$\ln(c) = 0$$

Taking the positive square root, the speed of light is one meter per second at the Planck boundary. The experiments with brain hemisphere resonance show that the resonant frequency of the human energy field is between 1 Hz to 5 Hz which is well below the hearing threshold of 20 Hz. Because the traveling wave has a wavelength of 0.3048 m and the speed of light is unity at the boundary, the frequency should be

$$f = \frac{c}{\lambda} = \frac{1\frac{m}{\text{sec}}}{.3048\ m} = 3.28\text{ Hz}$$

which is within the middle of the experimental male range. At this resonant frequency, the human energy being pops out of the body. This represents only a first stage in the development of the energy being. But what is really wanted is to have both the physical body and the energy field move out of dimension together as San Martin did.

[0020] Referring to **FIG. 7**, the 45° base line (G) is added to the diagram. Notice that the Planck mass intersects (b,d) the Planck wavelength on this line because they sum to the base constant. The mass of the water molecule crosses this line at point (f). A circle, centered (f), with a radius equal to the speed of light, is tangent to the Planck wavelength (h) and the Planck mass (g). Since mass times velocity is momentum, the diagram says that the momentum of the water molecule is tangent to the boundaries of the Planck box which separates space from hyperspace. In order to get to point (e) from the momentum of the water molecule, a second circle is added to the momentum.

[0021] Referring to **FIG. 8**, a circle (I), centered on the water molecule mass at the speed of light circle (i), is made tangent to the Planck wavelength at point (e). The momentum M of space is equal to the Planck mass times the Planck scale times the speed of light. At point (e), the speed of light is unity, so that the momentum is just the Planck mass in momentum units:

$$M = \Omega\Lambda c = 2.176634194 \cdot 10^{-8}\ \text{kg}\frac{m}{s}$$

Circle (I) has a radius equal to

$$\text{ratio}=e^{21.572952}=2338912700$$

Therefore the walking momentum in order to get to point (e) is the momentum of space M times this ratio

$$M_w = M \cdot \text{ratio} = 50.909573606\ \text{kg}\frac{m}{\text{sec}}$$

The stride length L per second that a person of mass W has to walk is the walking momentum divided by the mass W times a period T of one second

$$L = \frac{M_w}{W}T$$

For a person with a mass W of 99.79 kg (220 pounds), then the stride length L is 20.08 inches or one foot and eight inches. The person has to walk this length in one second on each foot.

[**0022**] Looking at the statue of San Martin, his arms are crossed over each other. The vortex of the right hand points backward, and the left hand vortex points forward due to the reversed rotation. Referring to **FIG. 9**, this creates a rotational energy channel (D) around his body (A). The stride length (C) is calculated according to the body mass, and then a banner printout is made showing where the footprints (B) are to be placed each second. The question is: "What happens when one walks the walk?".

[**0023**] On the very first experiment, referring to **FIG. 10**, what happens is that, after taking only six strides on the banner printout (A), a huge spinning vortex (C) develops over the top of the head and the vertex locks onto the heart vortex in the center of the chest (B). In everyday life, this vortex is not created because normal walking is much faster and the hands are held at the side of the body. The energy rush through the pineal gland is so intense that one feels immediately sleepy and starts yawning excessively due to the increased flow of melatonin.

[**0024**] After practicing with the banner printout, long walks were made through the park. In this case, a vertical white line rotated around a vertical axis located about six feet perpendicular to the path on the right side of the body. When the walking speed was correct, this white line would lock onto the centerline of the body. Speeding up or down caused the white line to lose synchronization and rotate away. This white line is related to the ability to levitate the body. San Martin had so much energy that, according to witness testimony, he could float horizontally in the air with his head resting against the bowed head of Christ on a carved wooden cross. Thus San Martin's energy sources were channeling energy from Christ, collective broom energy as described in a separate patent application, and the walking momentum vortex energy.

[**0025**] During the early part of the 20th century, a man's parents were lying in bed dying of tuberculosis. With their permission, he placed a weighing scale under each of their beds. When they passed away, he found that each scale registered a loss in weight of 2.5 ounces. This is equivalent to 0.071 kg, which is the mass of the human energy being.

[**0026**] After conducting a number of experiments with water vortices draining from a cylindrical tank, it can be stated from Bernoulli's theorem that the potential energy plus the kinetic energy is a constant

$$gz + \frac{1}{2}mv^2 = const$$

The shape of the inner surface of the water circulation has a velocity proportional to the inverse of the radius, so the shape of the surface is

$$(z - z_0) = \frac{k}{r^2}$$

which says that the height of the vortex is proportional to the inverse of the square of the radius.

[**0027**] The hand vortex area ratio between the second test subject and the third test subject is equal to the square of their radii:

$$\text{ratio} = \frac{(1\ \text{in})^2}{(4\ \text{in})^2} = \frac{1}{16}$$

Because the speed of light at the boundary was determined to be one meter per second, the energy of the third test subject is

$$E = \left(\frac{.071\ \text{kg}}{16}\right)\left(\frac{1\ \text{m}}{\text{sec}}\right)^2 = 4.4375 \cdot 10^{-3}\ \text{joule}$$

$$\ln(E) = -5.417664124$$

[**0028**] Referring to **FIG. 11**, a circle (K), having this radius, is added to the energy of the water molecule (E), to produce augmented energy circle (J). This circle (J) intersects the mass of the water molecule outside the Planck box at point (j). This means that the increased hyperspace energy moves the water molecule, and hence the body, out of dimension. Furthermore, circle (J) is tangent to the walking momentum ratio circle (I) which keeps the geometry locked together.

SUMMARY OF THE INVENTION

[**0029**] It is the object of this invention to create a training system that allows a person to develop the ability to walk around out of dimension, passing through solid objects. This invention is based on one of the most remarkable relationships between the water molecule and the boundary between space and hyperspace. The mass of the water molecule is equal to the energy of the water molecule at this boundary. Because the body is composed of 67% water, the body sits on the boundary such that any additional increase in energy would move the body out of dimension into hyperspace. Because human beings are actually hyperspace energy beings living in physical bodies, the additional energy required to move the body out of dimension comes from increasing the energy of the hyperspace being. One source of this energy comes from walking cross-handed at the proper velocity in order to generate a large hyperspace energy vortex that flows energy into the potential wells of the hyperspace being. This increased hyperspace energy will then allow the person to walk around out of dimension through solid wooden doors. Because the door and the person are in two slightly different dimensions at the same moment, it appears that the person is walking through the door. After passing through the closed door, the person then returns to our dimension and emerges in the interior of the closed-door room.

[0030] This technique can be used in reverse to heal an infected hand instantaneously. A salve made from the St.Mary's herb is applied to the skin of the infected hand. The hyperspace energy then flows through the right-hand vortex such that the infected hand and the salve are taken slightly out of dimension. What happens is similar to when a short piece of straw is embedded in a hard wooden telephone pole as a tornado passes over the pole. The straw and pole are taken out of dimension such that they briefly merge together. As the tornado moves on, both objects come back to dimension merged together. Thus the salve (straw) is merged with the bacteria (pole) in hyperspace such that the bacteria is killed instantly. Removing the hand vortex brings the infected hand back into dimension cured.

[0031] Based on this information and the results of many experiments, this invention creates a large vortex by walking at a certain velocity with the hands crossed over the chest. The proper walking momentum is created by a computer program that inputs the person's weight, shoe length, and the number of strides to be taken. The program then prints out a banner showing the footprints where the person has to step each second. When a person obtains sufficient energy from these methods, the person is then tuned to the subspace geometry of the universe as will be shown using the tetrahedron physics diagram.

A BRIEF DESCRIPTION OF THE DRAWINGS

[0032] **FIG. 1**. Energy vortices of the human body.

[0033] **FIG. 2**. Seven potential wells fed by the energy vortices of the body.

[0034] **FIG. 3**. Carved wooden statue of San Martin de Porres who could walk through solid wooden doors.

[0035] **FIG. 4**. Tetrahedron diagram showing boundaries of the Planck box of dimension.

[0036] **FIG. 5**. Tetrahedron diagram showing mass of water molecule.

[0037] **FIG. 6**. Tetrahedron diagram showing water molecule energy and mass are equal at the Planck box boundary.

[0038] **FIG. 7**. Tetrahedron diagram showing that water molecule momentum is tangent to the boundaries of the Planck box.

[0039] **FIG. 8**. Tetrahedron diagram showing the momentum ratio required to reach the Planck wavelength boundary from the water momentum.

[0040] **FIG. 9**. Perspective view of crossed-hand momentum walking using banner printout.

[0041] **FIG. 10**. Perspective view of vortex generated by momentum walking.

[0042] **FIG. 11**. Tetrahedron diagram showing how additional hyperspace energy supplied to the potential wells of the hyperspace energy being enables the human body to be pulled out of dimension.

[0043] **FIG. 12**. Tetrahedron diagram showing the inverted tetrahedrons whose crossing represents the merging of two worlds between space and hyperspace.

[0044] **FIG. 13**. Tetrahedron diagram showing that the proton wavelength is determined by the Planck mass tangent to the inverted tetrahedrons.

[0045] **FIG. 14**. Tetrahedron diagram showing that the mass of the universe determines the electron and proton elementary particles.

[0046] **FIG. 15**. Tetrahedron diagram showing that momentum walking together with the increased energy of the hyperspace energy being is tangent to the mass of the universe.

[0047] **FIG. 16**. Computer program block diagram for printing banner footprints.

[0048] **FIG. 17**. Computer program input dialog window.

[0049] **FIG. 18**. Computer program calculation of stride length per second.

[0050] **FIG. 19**. Six-stride screen banner printout for 220 lb. person.

[0051] **FIG. 20**. Project tree showing help information by double clicking on node.

DETAILED DESCRIPTION OF THE INVENTION

[0052] 1. Referring to **FIG. 12**, a tetrahedron (A, path abc) is added to the diagram. The tip of the tetrahedron (e) falls on the base constant which is equal to Planck's constant divided by the speed of light. A second tetrahedron (B, path def) is inverted around horizontal line (D) which has a geometrical relationship to the base constant. The line is located at

$$\text{centerline} = \frac{2}{\sqrt{3}}\ln\left(\frac{h}{c}\right) = -110.7536373$$

Notice that the intersection of the two inverted tetrahedrons (g) occurs at the Planck wavelength which is the boundary between space and hyperspace. Line (D) is referred to as the merging of two worlds or the connecting of two worlds, a phrase obtained by means of remote viewing. That is, it is the dividing line between space and hyperspace. This is the reason that the two boundaries intersect at this point.

[0053] Referring to **FIG. 13**, the proton wavelength (E) is added to the diagram. The proton wavelength has a value of the electron wavelength divided by 1836.1527

$$\ln(\lambda_p)=\ln\left(\frac{\lambda_e}{1836.1527}\right)=-34.26005901$$

A line (hd), from the base constant at the proton wavelength (h), to the corner of the inverted tetrahedron (d), intersects the merging of two worlds line at point (i). A circle, with a radius equal to the Planck mass (G), centered (i), is tangent to the inverted tetrahedrons. Thus the proton is defined by the base constant and the geometry of subspace. The reason that the proton is tangent to both tetrahedrons is because the electron and proton follow one single path between space and hyperspace. Thus there is only one single particle in nature. Because the particle enters our space at two different locations, we see the one particle as two distinct elementary particles. This relationship can be seen in Library of Congress tetrahedron diagram tet0565.

[0054] Referring to **FIG. 14**, the mass of the universe MU is equal to the linear mass Q of the universe times the radius R of the universe which is 10^{26} meters

$$\ln(MU)=\ln(\Omega R)=122.3347509$$

as shown on the diagram as line (A). The electron wavelength (B) reflects off the circumscribing sphere (H) and returns as the electron mass (C). The distance between reflection points is the hyperspace charge which is equal to the charge of space less the electron charge. So the electron goes from wavelength to electric charge to mass. The proton wavelength (D) reflects off the sphere and returns as the proton mass (E) which intersects the horizontal axis at point (c). A line (abc) from the mass of the universe at the vertical axis (a) to the proton at the horizontal axis (c) intersects the electron (b) which determines the electron's mass and wavelength since this point is on the 45° base line. What this means is that cosmology determines the values of the elementary particles.

[0055] Referring to **FIG. 15**, the mass of the water molecule (C) intersects the 45° base line at point (a). A circle (F), with a radius equal to the Planck mass is centered on point (c) at the Planck wavelength boundary (B) where the mass of the water molecule numerically equals the energy of the water molecule and where the speed of light is unity. The Planck mass is tangent to the base constant which is the vertical centerline (I) of the diagram. The large circle (H), centered (a) on the water molecule, is tangent to the mass of the universe (b) and tangent to the inverted tetrahedron (E). The difference between this circle (H) and the base constant (I) is the energy the hyperspace being has to acquire in order to be tuned to the mass and geometry of subspace. This difference, shown as circle (G), has a mass

$$m=e^{-4.792671}\text{ kg}=8.29\cdot 10^{-3}\text{ kg}$$

Thus the hand vortex radius ratio has to be the square root of the mass of the hyperspace energy being divided by this tangent mass, or:

$$r=\sqrt{\frac{.071\text{ kg}\cdot 1\text{ in}^2}{e^{-4.792671}\text{ kg}}}\approx 3\text{ inches}$$

which is a vortex radius that is three times larger than that of a normal person, but one inch smaller than the third test subject who had a hand vortex radius of 4 inches. This is the reason that the third test subject was able to walk through walls and teleport to other locations because his energy was sufficiently large enough to cross over the inverted tetrahedron into a co-dimension of hyperspace. Notice also that dotted circle (J) with a radius equal to the mass of the water molecule, centered (c) on the boundary, is tangent to the tetrahedron (K). This makes the combined geometry tangent to the inverted tetrahedrons and the mass of the universe.

[0056] 2. Referring to **FIG. 16**, a computer program generates a banner printout with footprints spaced for walking according to the weight, shoe size and length of banner desired. Some banners could fit in a small room, or be placed on the floor of a long corridor. As shown in the block diagram the program inputs these three variables with error checking. Then the program calculates the stride length L per second from the equation

$$L=\frac{M}{W}T$$

[0057] 3. In the above equation, the value of the momentum M, as determined by the tetrahedron diagram, is preferably 50.9095736 kg m/s. The weight of the person is converted to mass W in kilograms. The stride period is preferably 1 second. Referring to **FIG. 17**, the data is entered in the dialog input window.

[0058] 4. Once the stride length has been calculated, the program displays the stride length and the required number of banner sheets in the message window, as seen in **FIG. 18**.

[0059] 5. The print banner menu is selected and the foot prints are printed on continuous banner paper. A six-stride scaled screen version of the banner is shown in **FIG. 19**. The banner paper is then placed on the floor, and a one-second beeping timer is activated from the toolbar or menu. The person then walks beside the printed foot prints, taking one stride per beep, which produces the correct walking momentum to generate the hyperspace vortex. The vortex, which forms in only six strides, brings additional hyperspace energy into the quantum potential wells of the hyperspace energy being.

[0060] 6. A help system consists of a project tree which explains the various steps in using the program. Double mouse clicking on a project tree node displays the help instructions in a dialog window as shown in **FIG. 20**.

[0061] 7. In summary, the purpose of the training system is to substantially increase the energy of a human being who will then have the capability of walking through walls, body levitation, instantaneous healing of infections, full-body teleportation to another location, remote viewing at vast distances in terms of light-years, and looking into hyperspace co-dimensions. The third test subject and I have been able to experience all the above phenomena. He did it through augmenting his energy, and I have done it through the application of electromagnetic fields, by spinning on my vortex accelerator machine and using this invention.

I claim:

1. A training method comprising the steps of:

generating a banner having a plurality of footprints spaced at regular intervals wherein the banner is placed on the ground;

generating a periodic audible signal, whereby the audible signal repeats at a regular interval of time equal to the period; and

walking on the banner by tracing the footprints spaced at regular intervals, wherein one step is made with each audible signal.

2. The method of claim 1, wherein the step of generating the banner further comprises:

providing a person's actual mass in kilograms; and

determining the stride length based upon the following equation:

$$L=(M/W)*T$$

where L is the stride length in meters, M is a constant of approximately 50.91, W is the mass of the person in kilograms, and T is the period of the audible signal in seconds, and

wherein the footprints on the banner are spaced at the stride length.

3. The method of claim 2, wherein the audible signal is a beep and the period of the audible signal is one second.

4. A training method for a person comprising the steps of:

generating an audible signal having a fixed period;

generating a banner having regularly spaced indicia for identifying preferred step locations, wherein the distance between adjacent indicia is determined by the following formula:

$$L=(M/W)*T$$

where the distance between adjacent indicia in meters is L, a constant of 50.9095736 is equal to M, the person's mass in kilograms is W, and the fixed period in seconds is T; and

walking on the marked path by stepping upon each of the regularly spaced indicia wherein one step is made with each period of the audible signal.

5. The training method of claim 4 wherein the fixed period is one second.

6. The training method of claim 5, wherein the regularly spaced indicia are footprints.

* * * * *

US 20030209636A1

(19) **United States**
(12) **Patent Application Publication**
St.Clair
(10) **Pub. No.: US 2003/0209636 A1**
(43) **Pub. Date: Nov. 13, 2003**

(54) BOBBIN ELECTROMAGNETIC FIELD PROPULSION VEHICLE

(76) Inventor: **John Quincy St.Clair**, San Juan, PR (US)

Correspondence Address:
John St.Clair
Hyperspace Research Institute
52 Kings Court, 4A
San Juan, PR 00911 (US)

(21) Appl. No.: **10/142,583**

(22) Filed: **May 9, 2002**

Publication Classification

(51) **Int. Cl.^{7}** **B64G 1/32**

(52) **U.S. Cl.** **244/166**

(57) ABSTRACT

This invention relates to a spacecraft which generates its own magnetic moment and magnetic field gradient in order to produce lift on the hull. The magnetic moment is generated by a large area solenoid located in the hull. A toroidal core wrapped with electrical bobbins at intervals along said core produces a traveling magnetic wave along its surface. This magnetic wave creates a spacetime curvature, similar to a tilted plate, which causes the formation of a magnetic field gradient. Power is not critical because the system uses a magnetic vortex wormhole generator to lower the speed of light in order to efficiently create highly relativistic fields due to Lorentz transformation.



Figure 1

$$\text{Force} = \mu \cdot \frac{\partial B_z}{\partial z} = \text{amp} \cdot \text{m}^2 \frac{\text{kg}}{\text{sec} \cdot \text{coul} \cdot \text{m}} = \frac{\text{coul}}{\text{sec}} \cdot \text{m}^2 \cdot \frac{\text{kg}}{\text{sec} \cdot \text{coul} \cdot \text{m}} = \frac{\text{kg} \cdot \text{m}}{\text{sec}^2} = \text{newton}$$

Figure 2



Figure 3

$$B_Z = \mu n I$$

Figure 4



Figure 5

$$v = \sqrt{\frac{\omega}{\sigma\mu}}$$

Figure 6

$$g_{\alpha\phi} = \begin{array}{c|cccc|} & t & r & \theta & z \\ t & -1 & 0 & \mathrm{Sin}[\theta - t] & 0 \\ r & 00 & 1 & 0 & 0 \\ \theta & \mathrm{Sin}[\theta - t] & 0 & r^2 & 0 \\ z & 0 & 0 & 0 & 1 \end{array}$$

Figure 7



Figure 8


G zz curvature
dB z / dz
Flat space

BOBBIN ELECTROMAGNETIC FIELD PROPULSION VEHICLE

BRIEF SUMMARY OF THE INVENTION

[0001] This invention, which is the subject of my present application, is comprised of a toroidal core around which are wound a plurality of electromagnetic bobbins. The bobbins are pulsed electrically to create an amplified magnetic wave that travels around the core. At the same time, a circular electrical conductor carrying direct current creates a magnetic field around its area which results in the formation of a magnetic moment. This magnetic moment, together with the spacetime curvature distortion created by the traveling magnetic wave, produces a lift force on the vehicle.

REFERENCE PAPERS

[0002] Levitron, Hones, U.S. Pat. No. 5,404,062.

[0003] *Geometry of Electromagnetic Systems,* Paul Hammond, page 179.

BACKGROUND OF THE INVENTION

[0004] The idea for this invention comes from experiments I have done using thin transformer laminations wound in intervals with bobbins of wire connected to a frequency generator. Pulsing the bobbins electrically creates a slow traveling magnetic wave along the surface of the lamination. The velocity of the wave, as shown by Hammond in the reference paper, is the square root of the frequency divided by the conductivity and permeability of the material. From Einstein's General Theory of Relativity, this type of wave around the circumference creates a spacetime curvature distortion in the vertical direction that looks like a tilted plate. The magnetic field traveling around the circumference has to follow this curvature. This creates a magnetic gradient in the z-direction which together with the magnetic moment developed by a solenoid produces lift on the vehicle.

SUMMARY OF THE INVENTION

[0005] It is the object of this invention to create a magnetic field gradient and magnetic moment in order to produce a lift force on the hull of a vehicle. The magnetic field gradient is produced by a traveling magnetic wave which produces a tilting-plate spacetime curvature around the hull. The magnetic moment is created by a simple circular wire carrying direct current around its area.

STATEMENT REGARDING FEDERALLY SPONSORED RESEARCH OR DEVELOPMENT

[0006] Not Applicable.

A BRIEF DESCRIPTION OF THE DRAWINGS

[0007] **FIG. 1**. The lift force on the vehicle is equal to a magnetic moment times the magnetic field gradient.

[0008] **FIG. 2**. Magnetic moment μ created by direct current I flowing counterclockwise around the wire coil. Cylindrical coordinates are shown to the right.

[0009] **FIG. 3**. The wire coil solenoid creates a magnetic field in the z-direction equal to the permeability of space times the number of turns per length of the solenoid times the current in the windings.

[0010] **FIG. 4**. Perspective view of bobbin spacecraft.

[0011] **FIG. 5**. Magnetic wave velocity along core.

[0012] **FIG. 6**. The g metric tensor in cylindrical coordinates with the sinusoidal wave function in the $\{t,\theta\}$ slots.

[0013] **FIG. 7**. The spacetime curvature G_{zz} in the vertical direction created by the magnetic wave traveling around the core.

[0014] **FIG. 8**. Tilted plate spacetime curvature showing magnetic gradient.

DETAILED DESCRIPTION OF THE INVENTION

[0015] 1. Referring to the equation in **FIG. 1**, the lift force on the bobbin spacecraft is equal to its magnetic moment times its magnetic field gradient. The magnetic moment has units of electrical current, measured in amps, times the area enclosed by the current. Thus the units of the magnetic moment are amp–m^2. The magnetic moment can be created by a large, circular coil of wire carrying direct current I as shown in **FIG. 2**. The spacetime cylindrical coordinates $\{t, r, \theta, z\}$ are shown to the right of the drawing where t is time, r the radius, the horizontal angle θ, and the vertical height z.

[0016] 2. The wire coil solenoid also produces a magnetic field in the vertical z-direction equal to the permeability of space μ times the number of turns per unit length of the solenoid n, times the current I in the winding. The equation is shown in **FIG. 3** which can be developed from Ampere's law that the magnetic field around a loop is equal to the current passing through the loop.

[0017] 3. Referring to **FIG. 4**, the bobbin spacecraft consists of a large, horizontal, highpermeability toroidal core (D) wrapped at intervals with electrical bobbins (B) which can be pulsed electrically to create a traveling magnetic wave around the core. Interior to this core is a large direct current solenoid (C) which produces said magnetic field in the z-direction. These devices are enclosed in a circular hull (A) containing the coils on the outer rim and a cabin area in the center.

[0018] 4. Referring to **FIG. 5**, the velocity of the magnetic wave on the surface of the core is equal to the square root of the wave frequency ω divided by the conductivity a times the permeability μ of the core material. When the first bobbin is pulsed, a wave starts to propagate along the surface of the core. As the wave passes the second bobbin in sequence, another electrical pulse is generated to amplify the wave. After many cycles, the wave traveling around the core becomes larger and larger in amplitude.

[0019] 5. A traveling wave has a wave function equal to a sinusoidal function with an argument of the angle θ around the periphery less the time t, or $\mathrm{Sin}[\theta-\omega t]$.

[0020] 6. In gravitational physics, there is a g metric tensor which is a measure of length in spacetime coordinates. When mass or electromagnetic fields are involved in a certain region of space, a curvature of space is created. The curvature of space can then be calculated directly from this metric tensor. The result is Einstein's G curvature tensor which shows the spacetime distortion. The g metric tensor is a 4 by 4 matrix having rows and columns equal to time t, radius r, angle theta, and vertical height z. The diagonal from top left to bottom right has a signature equal to $\{-1, 1, r^2, 1\}$.

[0021] 7. Because the magnetic wave traveling around the core is varying with time t in the theta direction, the wave function has to go into the $\{t,\theta\}$ and $\{\theta,t\}$ slots of the metric tensor, as shown in **FIG. 6**.

[0022] 8. From this metric tensor, Einstein's G curvature tensor is calculated using a general relativity software program. The spacetime curvature in the vertical z-direction is contained in the G_{zz} component. A 3D plot of this curvature with respect to radius and theta is shown in **FIG. 7**. The axis on the right side is the angle around the periphery, and the axis on the left is the radius which goes from 0 to 20 meters. The vertical axis of the graph is the spacetime curvature in the vertical z-direction. The center of the vertical axis is zero. At a small radius, there is a sinusoidal curvature which is positive from 0 to π and which is negative from π to 2π. What this looks like is a tilted plate as depicted in **FIG. 8**.

[0023] 9. In flat spacetime with no electromagnetic fields or mass, the curvature would be the horizontal plate as seen **FIG. 8**. Due to the traveling magnetic wave, the spacetime curvature looks like the tilted plate. The flat-space magnetic field was pointing up in the vertical direction, having no divergence and no gradient. In curved spacetime, however, the magnetic field becomes tilted just like the plate and a magnetic gradient dB_z/dz is created. This spacetime curvature gradient of the magnetic field times the magnetic moment of the second coil produces a lift force on the hull which is anchored to these coils.

What I claim as my invention is:

1. A spacecraft that generates a magnetic moment and a magnetic field gradient in the vertical direction in order to create a lift force on the hull.

2. A toroidal core wrapped with electrical bobbins at intervals around the core whose purpose is to create and amplify a magnetic wave that travels along the surface of the core.

3. A circular, direct-current carrying solenoid, located radially inside the toroidal core, to create the magnetic moment.

4. Said magnetic surface wave creates a spacetime curvature, similar to a tilted plate, which produces a magnetic field gradient in the vertical direction.

5. A circular hull, with interior cabin, electrical power supply to drive the coils, and a computer to calculate and sequence the activation of the electrical bobbins.

6. Magnetic sensors, in the form of small coils, located on the toroidal core which can detect the velocity and position of the traveling magnetic wave as feedback to the computer control system.

7. A magnetic vortex generator, either rotating magnet or dual coil, to produce a wormhole through which low linear mass and low speed of light hyperspace energy can enter the hull in order to create highly relativistic electromagnetic fields.

8. A variable current generator to modulate the direct current in the coil so as to produce a variable magnetic moment that can control lift, hover and descent.

9. An electrical power supply using mechanical flywheel stored energy together with a large area capacitor, resupplied with energy by solar cells located on the outer surface of the hull.

* * * * *

US 20040164824A1

(19) **United States**
(12) **Patent Application Publication** (10) **Pub. No.: US 2004/0164824 A1**
St. Clair (43) **Pub. Date: Aug. 26, 2004**

(54) **HYPERSPACE ENERGY GENERATOR**

(76) Inventor: **John Quincy St. Clair**, San Juan, PR (US)

Correspondence Address:
John St. Clair
Hyperspace Research Institute
52 Kings Court, 4A
San Juan, PR 00911 (US)

(21) Appl. No.: **10/372,556**

(22) Filed: **Feb. 21, 2003**

Publication Classification

(51) **Int. Cl.**^{7} **H01P 3/06**
(52) **U.S. Cl.** **333/243**

(57) **ABSTRACT**

This invention is a braided gold wire coaxial cable of micron size which generates hyperspace energy by coupling to the tetrahedral geometry of subspace, dimension and the Planck mass.



Figure 1



Figure 2



Figure 3


4
9
8
10
7
5
3
6
1
2

Figure 4



Figure 5



Figure 6


proton wavelength
4π
electron mass
ln(2π)
√10/10
√2
ln(ΩΛc)−1
.599547652
zero point
√2
2π/10

Figure 7


220
−210
−200
−190
−180
−170
−160
−150
−140
−130
−120
−110
−100
−90
−80
−70
−60
−50
−40
−30
−20
−10
ln(mass)
C
B
B
B
D
A
a
−10
−20
−30
−40
−50
−60
−70
−80
−90
−100
−110
−120
−130
−140
−150
−160
−170
−180
−190
ln(wavelength)

Figure 8


-220
-210
-200
-190
180
-170
-160
-150
-140
-130
-120
110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
g
G
F
K
f
a
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
-110
-120
-130
-140
-150
-160
-170
-180
-190
ln(wavelength)

Figure 9


-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
g
G
A
B
C
b
f
a
10
20
30
40
50
60
70
80
90
100
110
120
130
140
150
160
170
180
190
ln(wavelength)

Figure 10


-220
-210
-200
-190
180
-170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
50
-40
-30
-20
-10
ln(mass)
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
-110
-120
-130
-140
-150
-160
-170
-180
-190
ln(wavelength)
a
b
c
d
f
g
A
B
C
D
E
G

Figure 11


-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
g
G
c
A
B
E
b
f
d
a
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
-110
-120
-130
-140
-150
-160
-170
-180
-190
ln(wavelength)

Figure 12


-220
-210
-200
-190
-180
170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
G
A
B
F
C
b
E
a
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
-110
-120
-130
-140
-150
-160
-170
-180
-190
ln(wavelength)

Figure 13


-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
120
-110
-100
90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
A
B
G
F
C
b
c
E
H
a
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
-110
-120
-130
-140
-150
-160
-170
-180
-190
ln(wavelength)

Figure 14



Figure 15



HYPERSPACE ENERGY GENERATOR

BRIEF SUMMARY OF THE INVENTION

[0001] This invention is a braided gold wire coaxial cable of micron size which generates hyperspace energy.

BACKGROUND OF THE INVENTION

[0002] Electrical experiments with micron-sized braided gold wire coaxial cable show that it is capable of generating substantial amounts of hyperspace energy. Referring to the electron microscope photograph shown in **FIG. 1**, the white mist emanating from the cable is low-density hyperspace energy that is flowing in from a co-dimension of our universe. The dimensions of the cable are of such a particular size as to couple the cable to the tetrahedral geometry of subspace, the dimension of space, the Planck mass and the linear inductance of the universe.

[0003] According to physicist Dr. Edward Witten of Princeton University, space has twenty-four dimensions, of which ten dimensions are non-redundant. Imagine taking a path around the Pythagorean triangle, as known as the planar tetrahedron, with sides equal to $\{\sqrt{1}, \sqrt{2}, \sqrt{3}\}$ as shown in **FIG. 2**. There are three squares denoted the one-square (A), the two-square (B) and the three-square (C). Each square has four sides. The edge of each square can be traversed in two directions. Thus the total number of dimensions is

$$dim_{\text{total}}=2\cdot(4+4+4)=24$$

[0004] Referring to **FIG. 3**, there is a path starting at the corner of the triangle, along the one-square (**1**), around the two-square (**2,3,4,5**), back along the one-square (**6**), around the three-square (**7,8,9,10**) and back to the corner of the triangle. The numbering of the edges shows that there are ten edges. Because the path is traversed in only one direction, the number of reduced dimensions is

$$dim_{\text{reduced}}=1\cdot(10)=10$$

[0005] Referring to **FIG. 4**, the planar tetrahedron (B) forms one edge of the three-dimensional tetrahedron (A). Rotating the planar tetrahedron ±120° produces the other two edges. The tetrahedron has four faces which are equilateral triangles. The ten dimensional path starts and ends at (C), the corner of the tetrahedron known as the zero point.

[0006] Referring to **FIG. 5**, the projection of the 3D tetrahedron (A) onto a plane is called the tetrahedron diagram (B) which is the main diagram of the new geometrical physics known as Δphysics. All the constants of physics can be derived geometrically from the tetrahedron diagram and its associated planar tetrahedron. An example of this is shown in **FIG. 6** where the edges are given specific constants related to tetrahedral geometry, dimension, curvature, and the mass and wavelength of the elementary particles such as the electron and proton. The ten dimensional path includes the following constants

[0007] a. electron wavelength

[0008] b. proton wavelength

[0009] c. 47π The solid angle of the sphere. The tetrahedron is circumscribed by a sphere.

[0010] d. ln(2π) The natural log of the curvature. The subspace geometry is a logarithmic manifold. The tetrahedron diagram plots the logarithm of mass versus the logarithm of wavelength.

[0011] e. 0.599547652 A constant related to fractal dimension and the speed of light factor 2.99792458.

[0012] f. $\sqrt{2}$ The edge of the two-square.

[0013] g. $\sqrt{10}/10$ The square root of ten dimensions per 10 dimensions.

[0014] h. ln(ΩΛc)−1 The natural log of the momentum of space less one.

[0015] i.

$$\frac{2\pi}{10}$$

[0016] The curvature of space per 10 dimensions.

[0017] j. $\sqrt{2}$ The edge of the two-square.

[0018] The length of each edge is multiplied by the constant assigned to that edge. The ten edges have the order of $\{\sqrt{1}, \sqrt{2}, \sqrt{2}, \sqrt{2}, \sqrt{1}, \sqrt{3}, \sqrt{3}, \sqrt{3}, \sqrt{3}\}$. What subspace geometry does is to multiply the edge length, such as $\sqrt{1}$, times the square root of two $\sqrt{2}$. Then it takes the square root of that number and multiplies it by the next edge, which is $\sqrt{2}$, times the curvature per 10 dimensions

$$\frac{2\pi}{10}.$$

[0019] It then takes the square root of that number and so on. In equation form, this looks like the following calculation

$$\sqrt{3a\sqrt{3b\sqrt{3c\sqrt{3d\sqrt{1e\sqrt{2f\sqrt{2g\sqrt{2h\sqrt{2i\sqrt{1j}}}}}}}}}} = 80.1104395$$

[0020] where the letters correspond to those in the list of constants. The square root sum total is equal to the Planck scale Λwhich is the bottom dimensional limit of the universe. The sum of the ten constants per a speed of light circumference is equal to unity

$$\frac{\sum\limits_{n=10} s_n}{2\pi\ln(c)} = 1.000000000$$

[0021] where the log of the speed of light is

$$\ln(c)=\ln(299792458)=19.51860099$$

[0022] and multiplying by 2π is the circumference of a circle with a radius equal to the speed of light.

[0023] Referring to **FIG. 7**, the tetrahedron diagram plots the natural logarithm of mass on the vertical axis (C) versus the natural logarithm of wavelength on the horizontal axis (A). The reason for this is that the mass of the electron times its wavelength is equal to the mass of the proton times its wavelength which in turn is equal to Planck's constant h divided by the speed of light, known as the base constant (B). If two numbers multiply, they sum in logarithms. In subspace geometry, the sum of the logarithm of the mass of the electron plus the logarithm of the wavelength is equal to the logarithm of the base constant which has a value of −95.91546344.

$$\ln(m_{electron}) + \ln(\lambda_{electron}) = \ln\left(\frac{h}{c}\right) = -95.91546344$$

[0024] What this means is that the mass and wavelength slide on a 45° base line (D) which has end points on the vertical and horizontal axes equal to the base constant.

[0025] Referring to **FIG. 8, a** line (af) drawn from the origin at the tetrahedral angle of 19.47122063, equal to the asin(⅓), creates a tetrahedron (F) along path (afg). This tetrahedron is circumscribed by a sphere (G) with sphere diameter (K).

[0026] The Planck scale path calculation showed that the electron mass and the proton wavelength were the last two edges. The electron mass has a value of

$\ln(m_e)=-69.17083217$

[0027] and the electron wavelength has a value of

$\ln(\lambda_E)=-26.74463127$

[0028] Referring to **FIG. 9**, the electron wavelength (A) is plotted as a vertical line on the tetrahedron diagram. The wavelength reflects off the circumscribing sphere (G), and returns as the electron mass (B). So the diagram incorporates the concepts of both classical physics (point mass particles) and quantum mechanics (wave particles).

[0029] The proton wavelength has a value of

$\ln(\lambda_p)=-34.26005901$

[0030] The proton wavelength (C) is plotted as a horizontal line in order to get the intersection (b) with the electron mass.

[0031] Referring to **FIG. 10, a** circle (D) with a radius equal to the Planck scale is drawn centered (b) on the intersection of the electron mass with the proton wavelength, which are the last two edges of the Planck scale calculation. A line (ac) from the origin to the intersection of the base constant with the rotated tetrahedron creates the vertical tetrahedron (acd). As can be seen, the Planck scale is tangent to the tetrahedron on side (cd). This tetrahedron is the projection of the 3D tetrahedron shown before in **FIG. 5**. What this means is that the tetrahedral geometry of subspace determines the bottom limit of our universe. And this bottom limit, called the Planck scale, contains within itself the mass and wavelength of the elementary particles, curvature, dimension and planar tetrahedral geometry. Tetrahedron diagram tet0565 shows that the electron and proton are one and the same particle because the electron path rotates counterclockwise around the curvature and then returns clockwise as the proton path. This path occurs moving through space and hyperspace. Because the single particle enters our universe from hyperspace at two different positions, we see it as two distinct particles. Thus the tetrahedron diagram shows that hyperspace exists.

[0032] The speed of light is equal to the inverse of the square root of the permeability μ of space times the permittivity ϵ of space

$$c = \sqrt{\frac{1}{\mu\varepsilon}}$$

[0033] The permeability is linear inductance or inductance per length which you would find in a solenoid for example. The permittivity is linear capacitance or capacitance per length which you find in a capacitor. In an electrical circuit, the inductance and capacitance form a resonant circuit. The resonance frequency can be changed by changing the inductor or capacitor. In a similar manner, the speed of light is not constant, but can be lowered by increasing the permittivity. Hyperspace energy has a high permittivity and therefore a low speed of light. This low speed of light gives hyperspace energy a luminescent quality which is seen as a white mist **(FIG. 1)**.

[0034] From Einstein's General Theory of Relativity, the stress pressure T on spacetime is proportion to the square of the ratio of the electric field E to the speed of light c.

$$T = \left(\frac{E}{c}\right)^2$$

[0035] Thus substantially lowering the speed of light creates an enormous spacetime pressure which can be used to generate the lift force on electromagnetic field propulsion vehicles. Furthermore, the electric field is subject to the Lorentz transformation

$$E = \frac{E_0}{\sqrt{1 - \frac{v^2}{c^2}}}$$

[0036] The electric field E_0 moving in a frame velocity of v, can quickly attain relativistic proportions because the speed of light could be 1 meter per second, rather than the enormous value in our universe of 299792458 meters per second. Thus one would like to permeate the hull of the electromagnetic field propulsion vehicle with this hyperspace energy in order to increase the electric field and hence the spacetime curvature around the hull which produces the enormous lift force on the vehicle. The method of bringing in this hyperspace energy is to use braided gold wire coaxial cable which is coupled to the geometry of subspace. The subspace geometry is contained in the Δphysics tetrahedron diagram.

[0037] Just as space has a linear inductance and linear capacitance, it also has a linear mass Ω or mass per meter.

Physicist Dr. John A. Wheeler of Princeton likes to invert this and call it "mom" for meter of mass. The Planck mass is equal to the Planck scale Λtimes the linear mass Ω

$$\ln(m_{\text{Plank}})=\ln(\Omega\Lambda)=-17.64290101$$

[0038] Planck's constant h is equal to 2π times the Planck scale squared times the linear mass Ω times the speed of light c.

$$h=2\pi\Lambda^2\,\Omega c=2\pi\Lambda(\Omega\Lambda)c$$

[0039] which shows that Planck's constant is actually the circumference of a circle of radius Planck scale times the Planck mass times the speed of light. The base constant is therefore

$$\text{base}=\frac{h}{c}=\frac{2\pi\Lambda(\Omega\Lambda)c}{c}=(2\pi\Lambda)(\Omega\Lambda)=-95.91546344$$

[0040] which is an area, known as the Planck box, bounded by the Planck wavelength (2πΛ) and the Planck mass. Everything outside the Planck box is hyperspace. Everything inside the Planck box is our universe. Thus the boundary between space and hyperspace is the Planck wavelength and the Planck mass. In logarithms, notice that the Planck mass and Planck wavelength, just like the electron and proton, sum to the base constant.

[0041] Referring to **FIG. 11**, the Planck mass (A) and the Planck wavelength (B) are plotted on the diagram and reflected off the sphere. The Planck wavelength intersects the tetrahedron at (b) which is the boundary between space and hyperspace known as the centerline of the diagram. The centerline has a value equal to the base times the square root of 4/3.

$$centerline=\sqrt{\frac{4}{3}}\,base=-110.7536373$$

[0042] Referring to **FIG. 12**, the centerline (C) is drawn on the diagram and the tetrahedron (E) is mirrored (F) across the centerline to indicate the co-dimensions of hyperspace.

[0043] Referring to **FIG. 13, a** circle (H), centered at the base at the base (c), tangent to the centerline (C), has a radius equal to base times the square root of 4/3 less one

$$R=\left(\sqrt{\frac{4}{3}}-1\right)base=14.83817383$$

[0044] This is the length that has to traversed in order to cross over the centerline from the base constant of our universe to the co-dimension of hyperspace. Furthermore, the Planck mass, which is the other boundary, has to be crossed in order to get to either axis as seen by the length between the vertical axis and line (A). It can be looked at also as the length needed to go from the Planck wavelength (B) to the tangent point of circle (H) in order to reach the center of the mirror tetrahedrons.

SUMMARY OF THE INVENTION

[0045] This invention is a braided gold wire coaxial cable of micron size that is coupled to the subspace geometry of the universe for the purpose of bringing in low-density hyperspace energy into our universe from the co-dimensions of hyperspace. The dimensions of the coaxial cable are of such particular size as to enable it to couple to the ten dimensions of space, the 3:1 geometrical ratio of the tetrahedron, the coaxial wave function based on the logarithm of the ratio of the outer radius to the inner radius of the cable, the length between the base constant of our universe and the centerline between mirror tetrahedrons, and the geometrical relationship between the Planck mass and the linear inductance of the cable.

[0046] Referring to **FIG. 14**, the coaxial guide has an outer braided conductor (A) and an inner braided conductor (B) in which the outer and inner conductors are at radii a and b respectively. The linear inductance L of the cable is equal to the natural logarithm of the ratio of the radii times the permeability μ of space divided by the curvature 2π

$$L=\ln\left(\frac{a}{b}\right)\frac{\mu}{2\pi}$$

[0047] It can be shown that the ratio of the area-to-volume ratio of the tetrahedron to the area-to-volume ratio of its circumscribing sphere is 3:1. It is also the ratio of the area of the three-square to the area of the one-square on the planar tetrahedron. It is also the tetrahedral angle asin(1/3) equal to 19.47122063°. It is also a maximum work condition between the velocity ratio of a fluid stream and a moving vane such as in turbomachinery. So the first constraint on the radii is

$$\exp\left(\ln\left(\frac{a}{b}\right)+1\right)\equiv 3$$

[0048] The second constraint is that the radius c of the circle, equal to the difference between the base constant and the centerline, is related to ten dimensions. The value of the radius projected into our universe is

$$c=\left(\sqrt{\frac{4}{3}}-1\right)\text{base}=.3596358547\cdot\text{microns}$$

[0049] and the dimensional constraint is

$$\left[\ln(c)+\ln\left(\frac{1}{a}\right)\right]^2=10$$

[0050] The coaxial wave function constraint is

$$\frac{\ln(a)^2}{2\pi\ln\left(\frac{a}{b}\right)} \equiv \ln(c)^2$$

[0051] The linear inductance of the coaxial cable has to be such that it gets geometrically across the Planck mass which is the second boundary of our Planck box

$$\exp\left(\ln(\Omega\Lambda) - \ln\left(\frac{\ln\left(\frac{a}{b}\right)}{2\pi}\mu\right) + 1\right) \equiv 3$$

[0052] With these four subspace constraints, the outer radius a and inner radius b of the cable are

[0053] a=8.342461828 microns

[0054] b=7.559058141 microns

[0055] so the cable has an outside diameter of roughly 16 to 17 microns.

STATEMENT REGARDING FEDERALLY SPONSORED RESEARCH OR DEVELOPMENT

[0056] Not Applicable.

A BRIEF DESCRIPTION OF THE DRAWINGS

[0057] **FIG. 1**. Electron microscope photograph of the coaxial cable and hyperspace mist.

[0058] **FIG. 2**. The planar tetrahedron.

[0059] **FIG. 3**. The ten dimensional path around the planar tetrahedron.

[0060] **FIG. 4**. The relationship between the planar tetrahedron and the 3D tetrahedron.

[0061] **FIG. 5**. Projection of the 3D tetrahedron onto a plane to create the tetrahedron diagram.

[0062] **FIG. 6**. Dimension, geometry, curvature and elementary particles that make up the ten dimensional Planck scale path.

[0063] **FIG. 7**. Tetrahedron diagram showing base constant.

[0064] **FIG. 8**. Tetrahedron diagram showing rotated tetrahedron and circumscribing sphere with electron mass and wavelength reflecting off sphere.

[0065] **FIG. 9**. Tetrahedron diagram showing intersection of electron mass with proton wavelength which are components of the Planck scale path.

[0066] **FIG. 10**. Tetrahedron diagram showing Planck scale tangent to tetrahedron.

[0067] **FIG. 11**. Tetrahedron diagram showing Planck mass and Planck wavelength intersecting tetrahedron.

[0068] **FIG. 12**. Tetrahedron diagram showing mirror tetrahedrons across centerline, the boundary between space and hyperspace.

[0069] **FIG. 13**. Tetrahedron diagram showing distance between the base constant and the centerline used to calculate the dimensions of the coaxial cable.

[0070] **FIG. 14**. End view of coaxial cable showing radii a and b used in the subspace geometry constraints in order to couple to hyperspace.

[0071] **FIG. 15**. Perspective view of braided gold wire coaxial cable.

DETAILED DESCRIPTION OF THE INVENTION

[0072] 1. Referring to **FIG. 15**, the coaxial cable has a braided gold wire outer conductor (A) and a braided gold wire inner conductor (B) separated by a dielectric (C). The open braiding promotes the conduction of the electromagnetic wave while allowing the hyperspace mist to seep out of the braid and permeate the surrounding material in which it is embedded.

[0073] 2. The radius of the outer conductor a and the radius of the inner conductor b have the following values in order to couple the cable to the tetrahedral geometry of subspace.

[0074] a=8.342461828·microns

[0075] b=7.559058141·microns

[0076] 3. Even though the wire size is very small, the cable can be made in limited lengths using the new nanotechnology and silicon micromotors.

I claim:

1. A coaxial cable which has:

a) a braided gold wire outer conductor of radius 8.34 microns;

b) a braided gold wire inner conductor of radius 7.56 microns;

c) a thin dielectric separator between the two conductors; and

d) an open weave to allow the hyperspace mist to seep out of the cable and permeate the surrounding material in which the cable is embedded;

2. A specific relationship between the physical dimensions of the coaxial cable, given in items (**1***a*) and (**1***b*), to the following tetrahedral subspace couplings:

a) the ratio of the area-to-volume ratio of the tetrahedron to the area-to-volume ratio of its circumscribing sphere, equal to 3:1, with a coupling to the natural logarithm of the ratio of the radii of the conductors;

b) the ratio of the area of the three-square of the planar tetrahedron to the area of the one-square, equal to 3:1, with a coupling to the Planck mass and the linear inductance of the cable;

b) the distance between the base constant and $\sqrt{4/3}$ times the base constant, equal to −14.83817383 in natural logarithms, with a coupling to the outer radius of the conductor, the ten dimensions of space, and the codimensions of hyperspace; and

c) the wave function of the coaxial guide given in terms of item (**2***c*), the natural logarithm of the ratio of the radius of the outer conductor to the radius of the inner conductor, and the curvature 2π.

* * * * *

US 20060070371A1

(19) **United States**
(12) **Patent Application Publication** (10) **Pub. No.: US 2006/0070371 A1**
St. Clair (43) **Pub. Date: Apr. 6, 2006**

(54) **ELECTRIC DIPOLE MOMENT PROPULSION SYSTEM**

(76) Inventor: **John Quincy St. Clair**, San Juan, PR (US)

Correspondence Address:
JOHN ST. CLAIR
52 KINGS COURT, 4A
SAN JUAN, PR 00911 (US)

(21) Appl. No.: **10/958,436**

(22) Filed: **Oct. 5, 2004**

Publication Classification

(51) **Int. Cl.**
F03H 1/00 (2006.01)
(52) **U.S. Cl.** **60/203.1**

(57) **ABSTRACT**

A spacecraft propulsion system utilizing a rotating octagon of trapezoidal electrically charged flat panels to create an electric dipole moment that generates lift on the hull.



Figure 1



Figure 2



Figure 3



Figure 4



Figure 5



Figure 6



Figure 7


$\frac{dB}{dz} = \frac{E_r}{c^2}\frac{dv}{dz}$
$\frac{dv}{dz}$
hull profile

Figure 8



Figure 9


μ_r
μ_z
μ
$\mu_z \cdot \frac{dB_z}{dz}$

Figure 10



Figure 11



ELECTRIC DIPOLE MOMENT PROPULSION SYSTEM

BRIEF SUMMARY OF THE INVENTION

[0001] The invention is a spacecraft utilizing trapezoidal electrostatically charged flat plate panels which form a pyramidal hull. A panel contains three holes each of which produces a potential energy ellipsoidal bubble that creates an electric dipole moment. The rotation of the hull generates a magnetic moment and a magnetic field gradient in the vertical direction that produces a lift force on the spacecraft.

BACKGROUND OF THE INVENTION

[0002] It is known from electrodynamics that a hole in a conducting plane forms a potential energy bubble. This bubble creates an electric dipole moment from which it is possible to develop a magnetic moment. A rotating tilted hull produces a velocity gradient that generates a magnetic field gradient in the vertical direction. This combination produces a lift force on the spacecraft. A very large potential energy bubble is produced provided that the hole protrudes out of the plate in an ellipsoidal shape. Furthermore, a double cladding, in which each layer around the hole has a different permittivity, confines the field to the outside of the hull for even better results.

[0003] The planar potential energy is created by a grid of electrically charged wires or rods running the length of each panel. A circular potential energy from each rod very quickly sums to form a flat sheet of energy which emerges from the hole to form the potential energy bubble.

SUMMARY OF THE INVENTION

[0004] The invention relates to a spacecraft utilizing a rotating octagon of trapezoidal electrically charged flat plate panels to form a hull in the shape of a pyramid. Each panel has three protruding ellipsoidal bubbles that produce an electric dipole moment from a planar potential energy field created by a group of charged rods parallel to the panel. Because the panels are tilted and the hull is rotating, there is a tangential velocity gradient in the vertical direction. This creates the magnetic moment. Because the hull rotates, the radial electric field produces a magnetic field gradient in the vertical direction. This combination of magnetic moment and magnetic field gradient produces a lift force on the hull of the spacecraft.

[0005] On the underside of each panel is a group of high voltage electrically charged rods which run parallel to the panel. These wires or rods produce a planar electrical potential field underneath the holes in the panel. This potential energy field then bubbles out of the holes in the panel to create a large ellipsoidal potential energy field above the hull. The potential energy bubble carries an electric dipole moment which when rotated with the hull generates a magnetic moment in the vertical direction.

A BRIEF DESCRIPTION OF THE DRAWINGS

[0006] **FIG. 1**. Perspective view of electric dipole moment spacecraft.

[0007] **FIG. 2**. Perspective exploded view of one panel with the ellipsoidal domes, flat hull panel with three holes, the charged rod grid and the planar potential energy field.

[0008] **FIG. 3**. Planar view of flat potential energy field produced by electrically charge wire rods.

[0009] **FIG. 4**. Perspective view of cylindrical coordinates $\{r, \theta, z\}$.

[0010] **FIG. 5**. Perspective view of ellipsoidal potential energy field emerging from hole in plate which produces an electric dipole moment.

[0011] **FIG. 6**. Planar view of field lines of potential energy bubble emerging from plate hole.

[0012] **FIG. 7**. Planar view of sloping hull profile needed to get a velocity gradient.

[0013] **FIG. 8**. Perspective view of hull showing electric dipole moment, the tangential velocity of the hull, and the magnetic moment.

[0014] **FIG. 9**. Perspective view of the magnetic moment components in the radial and vertical direction whereby the lift force is generated by the dot product of the vertical magnetic moment with the magnetic field gradient.

[0015] **FIG. 10**. Perspective view of cross section of dome showing two layer cladding with different permittivities to enhance potential energy field.

[0016] **FIG. 11**. Planar view of enhanced potential energy field with two layer cladding.

DETAILED DESCRIPTION OF THE INVENTION

[0017] 1. Referring to **FIG. 1**, the spacecraft is a rotating octagon of trapezoidal electrostatically charged flat panels which form a closed hull (A). Each panel has three ellipsoidal domes (B) of varying size centrally located along the major length of the panel. The purpose of the dome is to create a large ellipsoidal potential energy bubble over the hull which develops an electrical dipole moment. Because the hull is rotating, a magnetic moment is created in the vertical direction. A magnetic field gradient created by the rotating electric field on the hull in combination with the magnetic moment produces a lift force on the hull.

[0018] 2. Referring to **FIG. 2**, the trapezoidal hull panel (A) contains three ellipsoidal holes (E). A group of wires or rods (C) running parallel to and just underneath the panel are electrically charged to a high voltage at the end terminals (B). The rods produce a planar potential energy field (D) just under the holes in the panel. The field emerges from the holes in the shape of an ellipsoidal bubble and is amplified by an ellipsoidal dome (F) on the outside of the hull.

[0019] 3. Referring to **FIG. 3**, the group of parallel rods (A) are given a linear charge λ in units of charge per meter. The electric field E developed by the rod is the linear charge divided by the circumference of a circle of radius r around the wire times the permittivity ϵ of space. The analysis of this arrangement shows that within a few grid width spacings, the potential energy field ϕ due to the electric field E_0 has become planar (B) in the z-direction given by the equation

$$\phi=-E_0 z$$

[0020] 4. Referring to **FIG. 4**, the following analysis is done in cylindrical coordinates {r,θ,z}.

[0021] 5. Referring to **FIG. 5**, the ellipsoidal potential energy (B) emerges through the hole in the panel plate (A). In doing so it creates an electrical dipole moment (C) shown by the arrow normal to the hole area.

[0022] 6. Referring to **FIG. 6**, the bubble (B) emerges through plate (A).

[0023] 7. Because the bubble has the shape of an ellipse, the centroid y of the bubble would be four thirds the radius a divided by π as given by

$$\bar{y}_{ellipse} = \frac{4}{3}\frac{a}{\pi}$$

[0024] The electric dipole moment is then given as the charge q times the centroid y. The charge of the hole is equal to the permittivity E times the electric field E emerging from the hole times the area of the hole of radius a

$$q = \varepsilon_0 E \pi a^2 \frac{\text{coul}^2}{\text{m}^2\ \text{newton}} \frac{\text{newton}}{\text{coul}}\ \text{m}^2 = \text{coul} = \text{charge}$$

[0025] 8. The electric dipole moment p is the centroid y times the charge q

$$p = qy = \varepsilon_0 E \pi a^2 \frac{4}{3}\frac{a}{\pi} = \frac{4}{3}\varepsilon_0 E a^2\ \text{coul}\cdot\text{meter}$$

[0026] The electric dipole moment p times the hull velocity v is equal to a magnetic moment μ which is what creates the lift force on the hull

$\mu = pv$ amp·m^2

[0027] 9. The rotating hull creates the electric dipole moment velocity so that the entire hull develops a magnetic moment. In tensor notation, the magnetic moment μ is in the vertical z-direction because there is a radial component of the electric dipole moment times the velocity. The velocity is the radius r in the radial direction times the angular velocity ω in the z-direction

$\mu^z = p_r x^r \omega^z$

[0028] 10. The force F on the hull is the gradient of the dot product of the magnetic moment μ with the magnetic B field

$F = \nabla(\mu \cdot B)$

[0029] 11. By electrically charging the hull of the vehicle, a radial electric field is produced. By rotating the hull, the radial electric field changes with time. Thus Maxwell's equations will involve the curl of the magnetic field in the radial direction because the radial electric field is varying with time

$$(\nabla \times B)_r = \frac{1}{c^2}\frac{\partial E_r}{\partial t}$$

[0030] 12. The cross product involves the magnetic field in the theta direction which is zero

$$\frac{1}{r}\frac{\partial B_z}{\partial \theta} - \frac{\partial B_\theta}{\partial z} = \frac{1}{c^2}\frac{\partial E_r}{\partial t} = \frac{1}{r}\frac{\partial B_z}{\partial \theta}$$

[0031] Substituting the derivative of the electric field E

$E_r = E_0 e^{i\omega t}$

[0032] and integrating with respect to angle theta gives the vertical magnetic field B as the tangential velocity v times the radial electric field E divided by the speed of light c squared

$$B_z = \frac{v}{c^2} E_r$$

[0033] 13. The force on the hull is the gradient of the magnetic moment μ times the magnetic field B. In the equation for the magnetic field, the only available variable to work with in order to get a gradient of the magnetic field comes from the velocity.

$$\frac{dB_z}{dz} = \frac{E_r}{c^2}\frac{dv}{dz}$$

[0034] 14. Referring to **FIG. 7**, because the hull is in the shape of a pyramid, the velocity is a function of the height z of the hull. Using eight flat sides keeps the radial electric field pointing in the same direction in each panel. Each panel has three domes to produce the magnetic moment for a total of 24 magnetic moment generators.

[0035] 15. Referring to **FIG. 8**, the electric dipole moment (A) points in the radial direction, the rotating hull produces a tangential velocity (B), and the result is a magnetic moment (C) along the panel.

[0036] 16. Referring to **FIG. 9**, because the magnetic moment is parallel to the panel, there are vertical and radial components of the magnetic moment. The vertical magnetic moment creates the dot product with the magnetic field gradient, which is equal to the lift force.

[0037] 17. **FIG. 10** shows a cross-section of the dome (A) and the plate hole (B) with double cladding to enhance the field. The upper cladding (D) has a low relative permittivity in the range of 2 to 40, and the lower layer has a high relative permittivity in the range of 1200 to 4000.

[0038] 18. Comparing **FIG. 11** to **FIG. 7**, this dome and cladding configuration creates a much larger electric dipole moment compared to a hole in the plate. The wavy lines are the equi-potential energy lines from the dome (C) and the upper layer (B) and the lower level (A).

I claim:

1. A spacecraft propulsion system comprising:

a rotating octagon of trapezoidal electrostatically charged flat panels which form a closed sloping hull in the shape of a pyramid;

panels each having three holes covered by three ellipsoidal domes of varying size centrally located along the major length and axis of each panel; and

a grid of high voltage electrostatically charged rods located on the interior side of each panel such that a planar potential field is produced parallel to and under each panel hole.

2. The domes, holes and rotating charged hull of method 1 producing:

an ellipsoidal potential energy field emerging from the holes and generating an electric dipole moment on the outside of the hull;

a magnetic moment in the vertical direction due to the rotating electric dipole moment; and

a rotating electric field in the radial direction which generates a corresponding magnetic field gradient in the vertical direction proportional to the velocity gradient of the sloping panels of the hull.

3. A lift force on the spacecraft hull generated by:

the magnetic moment times the gradient of the magnetic field in the vertical direction; and

a dual surface layer hull cladding having different permittivities which enhance the electric dipole moment whereby the upper cladding has a low relative permittivity in the range of 2 to 40, and the lower layer has a high relative permittivity in the range of 1200 to 4000.

* * * * *

US 20060038081A1

(19) **United States**

(12) **Patent Application Publication** (10) **Pub. No.: US 2006/0038081 A1**

St. Clair (43) **Pub. Date: Feb. 23, 2006**

(54) **ELECTRIC DIPOLE SPACECRAFT**

(76) Inventor: **John Quincy St. Clair**, San Juan, PR (US)

Correspondence Address:
JOHN ST. CLAIR
52 KINGS COURT, 4A
SAN JUAN, PR 00911 (US)

(21) Appl. No.: **10/912,621**

(22) Filed: **Aug. 4, 2004**

Publication Classification

(51) **Int. Cl.**
B64G 1/40 (2006.01)

(52) **U.S. Cl.** **244/171.5**

(57) **ABSTRACT**

This invention is a rotating spacecraft that produces an electric dipole on four rotating spherical conducting domes perturbing a uniform spherical electric field to create a magnetic moment interacting with the gradient of a magnetic field that generates a lift force on the hull.



Figure 1


$\varphi = \frac{q}{4\pi\epsilon_0}\left[\frac{1}{r_1} - \frac{1}{r_2}\right]$
r_2
r
r_1
θ
-q
q
z=-a
z=a
z

Figure 2


E_0
z
E
φ=0

Figure 3



Figure 4



Figure 5



Figure 6



Figure 7



Figure 8



Figure 9



Figure 10



Figure 11


μ_z
v_θ
p_r

Figure 12



Figure 13



Figure 14



ELECTRIC DIPOLE SPACECRAFT

BRIEF SUMMARY OF THE INVENTION

[0001] This invention is a rotating spacecraft that utilizes four spherical conducting domes perturbing a uniform electric field in order to create a lift force by means of a magnetic moment times the gradient of a magnetic field.

BACKGROUND OF THE INVENTION

[0002] An electric dipole p is two electrical charges of opposite sign {q, −q} separated by a distance a.

$$p = qa = \text{coulomb}\cdot\text{meter}$$

[0003] If this dipole is moving with a velocity v, it produces a magnetic moment μ.

$$\mu = pv = qav = \text{coulomb meter}\frac{\text{meter}}{\text{sec}} = \frac{\text{coulomb}}{\text{sec}}\text{meter}^2 = IArea$$

[0004] The magnetic moment is equal to a current I circulating around an area. The magnetic field B has units of kilogram per second per charge coulomb.

$$B = \frac{\text{kg}}{\text{sec } coul}$$

[0005] The gradient of the magnetic field in the vertical direction z has units of

$$\frac{dB}{dz} = \frac{\text{kg}}{\text{sec } coul \text{ meter}}$$

[0006] This gradient interacting with a magnetic moment creates a force F measured in newtons.

$$F_z = \mu\frac{dB}{dz} = \frac{coul\ \text{m}^2}{\text{sec}}\frac{\text{kg}}{\text{sec } coul\ m} = \frac{\text{kg } m}{\text{sec}^2} = \text{newton}$$

[0007] In terms of vectors, the force is equal to

$$F = \nabla(\mu\cdot B)$$

which is the gradient ∇ of the dot product $(\cdot)$ of the magnetic moment with the magnetic field. This means that the magnetic moment has to be aligned with the field. The lift force on the spacecraft would then be the magnetic moment in the vertical z-direction μ_z times the magnetic field in the z-direction B_z. For constant magnetic moment, the gradient affects the magnetic field only, resulting in the same force equation

$$F_z = \nabla(\mu_z\cdot B_z) = \mu_z\nabla B_z$$

[0008] Referring to **FIG. 1**, the electric dipole has a positive charge q located on the z-axis at a distance a from the origin of the graph. A second negative charge −q is located at a distance −a from the origin. The positive charge produces an electrostatic potential ϕ_1 at a radius r_1 equal to the charge q divided by 4π times the permittivity of space ϵ_0

$$\varphi_1 = \frac{q}{4\pi\varepsilon_0}\frac{1}{r_1}$$

where the permittivity is linear capacitance, measured in farads per meter. The electrostatic potential has units of volts

$$\varphi = \frac{coul}{\left(\frac{\text{farad}}{\text{meter}}\right)}\frac{1}{\text{meter}} = \frac{coul}{\text{farad}} = \text{volt}$$

because the charge in coulombs held by a capacitor is equal to the capacitance, measured in farads, times the capacitor voltage. Because the second charge has the opposite sign, the potential ϕ_2 at a radius r_2 to the same point in space is

$$\varphi_2 = \frac{-q}{4\pi\varepsilon_0}\frac{1}{r_2}$$

[0009] The total potential ϕ at some point in space is equal to the sum of the two potentials, or

$$\varphi = \varphi_1 + \varphi_2 = \frac{q}{4\pi\varepsilon_0 r_1} - \frac{q}{4\pi\varepsilon_0 r_2} = \frac{q}{4\pi\varepsilon_0}\left[\frac{1}{r_1} - \frac{1}{r_2}\right]$$

[0010] As seen in the diagram, the point of space is a distance r from the origin. Using the law of cosines, radius r_1 can be written as

$$r_1 = (r^2 + a^2 - 2ar\cos(\theta))^{\frac{1}{2}} = r\left(1 + \left(\frac{a}{r}\right)^2 - 2\left(\frac{a}{r}\right)\cos(\theta)\right)^{\frac{1}{2}} = r(1 - 2xt + t^2)^{\frac{1}{2}}$$

where t is the ratio of the charge location over the radius, and x is $\cos(\theta)$. The potential for positive charge q_1 can be written

$$\varphi_1 = \frac{q}{4\pi\varepsilon_0}\frac{1}{r_1} = \frac{q}{4\pi\varepsilon_0}\frac{1}{r}(1 - 2xt + t^2)^{-1/2}$$

[0011] Dropping the factor $q/4\pi\epsilon_0 r$, the square root can be expressed in terms of the Legendre polynomial $P_n\cos(\theta)$ of the nth power

$$g(t, x) = (1 - 2xt + t^2)^{-1/2} = \sum_{n=0}^{\infty} P_n(x)t^n$$

where the absolute value of t is less than one. The polynomial coefficients of t^n can be obtained by using the binomial theorem to expand the generating function g(t,x) as

$$(1-2xt+t^2)^{-1/2}=\sum_{n=0}^{\infty}\frac{(2n)!}{2^{2n}(n!)^2}(2xt-t^2)^n$$

which evaluates to

$$\frac{0!}{2^0(0!)^2}(2xt-t^2)^0+\frac{2!}{2^2(1!)^2}(2xt-t^2)^1+\frac{4!}{2^4(2!)^2}(2xt-t^2)^2$$

$$1t^0+xt^1+\left(\frac{3}{2}x^2-\frac{1}{2}\right)t^2+\text{order}(t^3)$$

[0012] The first three Legendre polynomials are therefore

$$P_0=1$$

$$P_1=x$$

$$P_2=\frac{1}{2}(3x^2-1)$$

[0013] The electrostatic potential for both charges of the electric dipole is

$$\varphi=\frac{q}{4\pi\varepsilon_0}\frac{1}{r}\left\{\left(1-2\left(\frac{a}{r}\right)\cos(\theta)+\left(\frac{a}{r}\right)^2\right)^{-1/2}-\left(1+2\left(\frac{a}{r}\right)\cos(\theta)+\left(\frac{a}{r}\right)^2\right)^{-1/2}\right\}$$

[0014] The potential can be evaluated in terms of the Legendre polynomials as

$$\begin{aligned}\varphi&=\frac{q}{4\pi\varepsilon_0 r}\left[\sum_{n=0}^{\infty}P_n(\cos(\theta))\left(\frac{a}{r}\right)^n-\sum_{n=0}^{\infty}P_n(\cos(\theta))(-1)^n\left(\frac{a}{r}\right)^n\right]\\&=\frac{2q}{4\pi\varepsilon_0 r}\left[P_1(\cos(\theta))\left(\frac{a}{r}\right)+P_3(\cos(\theta))\left(\frac{a}{r}\right)^3+\dots\right]\end{aligned}$$

[0015] The first and most dominant term when the radius is much greater than location a is equal to

$$\varphi=\frac{2aq}{4\pi\varepsilon_0}\frac{P_1(\cos(\theta)0}{r^2}$$

which is the electric dipole potential and 2aq is the dipole moment

$p=2aq$

[0016] Now imagine a constant electric field E_0 which is perturbed by a conducting sphere of radius a. The unperturbed electrostatic potential outside the sphere would the negative of the electric field times the radius times the Legendre polynomial, or

$\Phi_1=-E_0rP_1$

[0017] The electrostatic potential perturbed by the charges is the voltage E_0a times the radius a times the a of the dipole moment times the Legendre polynomial divided by the radius squared

$$\varphi_2=E_0aaa\frac{P_1}{r^2}=E_0a^3\frac{P_1}{r^2}$$

[0018] The total potential outside the sphere is the sum of the two potentials equal to

$$\varphi=-E_0rP_1+E_0a^3\frac{P_1}{r^2}=-E_0P_1\left(r-\frac{a^3}{r^2}\right)=-E_0rP_1\left(1-\left(\frac{a}{r}\right)^3\right)$$

[0019] Referring to **FIG. 2**, the previously uniform electric field is shown perturbed by the neutral conducting sphere. The center of the sphere is taken as the origin and the z-axis is oriented parallel to the original uniform field.

[0020] The electric field induces a surface charge density σ on the sphere equal to the negative of the permittivity of space times the gradient of the electrostatic potential

$$\sigma=-\varepsilon_0\frac{\partial\varphi}{\partial r}|_{r=a}=3\varepsilon_0E_0\ \cos(\theta)$$

[0021] The electric field also induces an electric dipole moment on the sphere equal to the

$$p=\frac{qa}{r}\cdot\frac{2a^2}{r}=4\pi\varepsilon_0E_0a^3$$

with units of coulomb-meter. If this sphere is rotating around a central axis at a velocity v, it will create a magnetic moment μ equal to the dipole moment times the velocity.

$\mu=pv$

with units of ampere-meter^2.

SUMMARY OF THE INVENTION

[0022] As shown in the preceding background section, a neutral conducting sphere placed in a uniform electric field will generate a magnetic moment when rotated around a central axis. The electric field can be created by two points charges of opposite sign separated by a distance between them.

[0023] Referring to **FIG. 3**, the spacecraft has a spherical cabin (A) to which are attached cone-shaped electrostatic towers (B,C) above and below the cabin along the direction of travel in the z-direction. Because the electric field goes from the positive charge to the negative charge, the tip of the lower tower has a positively charged electrode, and the upper tower has a negatively charged electrode. Four equally-spaced neutral conducting spheres (D) are connected to the cabin by non-conducting tubes (E). The tubes make an angle with the cabin such that the distance (CD) is greater than distance (DB). The angle θ of the tube with respect to the cabin can be seen in side view **FIG. 4**.

[0024] Referring to **FIG. 5**, the charges create a uniform spherical field between the towers. The conducting spheres perturb this field such that the electric field (E) points toward the upper tower in a manner similar to that shown previously in **FIG. 2**.

[0025] Referring to **FIG. 6**, the conducting sphere produces an electric dipole moment (A) pointing at an angle toward the upper tower.

[0026] Referring to **FIG. 7**, by the law of addition of vectors, the electric dipole $\bar{p}$ can be represented by two orthogonal vectors pointing in the vertical z-direction p_z and in the inward radial direction p_r.

[0027] Referring to **FIG. 8**, the hollow tube (A) connecting the cabin with the conducting sphere contains a spiral-wound electrical solenoid (B) which produces a magnetic field (C). This magnetic field B can be decomposed into two orthogonal vectors pointing in the vertical z-direction B_z and in the outward radial direction B_r as shown in **FIG. 9**.

[0028] Referring to top-view **FIG. 10**, the spacecraft has a clockwise angular velocity ω (A) which gives the conducting sphere a velocity v as shown by the vector (B). By the right-hand rule of physics, the angular velocity vector points in the negative z-direction. The angular velocity in the z-direction crossed with the radius r in the radial direction produces a velocity v in the clockwise θ-direction using cylindrical coordinates {r,θ,z}.

$$v_\Theta = w_z \times r_r = -\omega r$$

[0029] Referring to **FIG. 11**, the negative radial dipole moment p_r crossed with the negative velocity v_Θ of the sphere produces a positive magnetic moment μ_z in the z-direction.

$$\mu_z = p_r \times v_\Theta = (-p_r)(-v_\Theta) = pv$$

[0030] Referring to **FIG. 12**, the magnetic field B_z in the vertical z-direction is dotted with the magnetic moment μ_z in the z-direction to produce a force F_z in the vertical z-direction on each conducting sphere (**FIG. 13**).

$$F_z = \nabla(\mu_z \cdot B_z) = \mu_z \nabla B_z$$

[0031] The magnetic field that is produced by the solenoid actually curves away and around. Thus there is a gradient of the field in the z-direction.

[0032] The force can also be expressed in tensor notation. The magnetic B field in the vertical direction is part of an electromagnetic 4×4 matrix Faraday tensor F

$$F_\beta^\alpha = \begin{array}{r|cccc|} & \beta = t & r & \theta & z \\ \alpha = t & 0 & 0 & 0 & 0 \\ \alpha = r & 0 & 0 & B_z & 0 \\ \alpha = \theta & 0 & -B_z & 0 & 0 \\ \alpha = z & 0 & 0 & 0 & 0 \end{array}$$

which shows that the magnetic field is located in slot F^r_Θ of the Faraday tensor. In tensor notation the subscripts and superscripts have to match up on both sides of the equation. Matching subscripts and superscripts on the same side of the equation cancel. In this case, the electric dipole moment is in the radial direction p_r. The velocity can be represented as a time derivative of the θ-coordinate x^Θ or

$$v^\theta = \frac{\partial x\theta}{\partial t}$$

[0033] Thus the force component in the z-direction becomes

$$F_z = p_r v^\theta F^r_{\theta,z} = (-p)(-v)\frac{\partial B_z}{\partial z} = pv\frac{\partial B_z}{\partial z}$$

where the angular and radial tensor components cancel and comma-z (, z) represents differentiation of the magnetic field in the z-direction.

[0034] The spacecraft design also has an inherent motion control system for moving in various directions. If the magnetic field of one solenoid arm is increased or decreased, the force on that sphere will be increased or decreased. Thus the spacecraft can turn in a particular direction.

A BRIEF DESCRIPTION OF THE DRAWINGS

[0035] **FIG. 1**. Electric dipole.

[0036] **FIG. 2**. Uniform electric field perturbed by electric dipole.

[0037] **FIG. 3**. Perspective view of spacecraft.

[0038] **FIG. 4**. Angle of solenoid tube.

[0039] **FIG. 5**. Electric field perturbed by conducting sphere.

[0040] **FIG. 6**. Electric dipole generated by conducting sphere.

[0041] **FIG. 7**. Orthogonal vector components of electric dipole.

[0042] **FIG. 8**. Magnetic field produced by tube arm solenoid.

[0043] **FIG. 9**. Orthogonal vector components of magnetic field.

[0044] **FIG. 10**. Angular velocity of hull.

[0045] **FIG. 11**. Magnetic moment produced by radial electric dipole and sphere velocity.

[0046] **FIG. 12**. Dot product of the magnetic moment with the magnetic field.

[0047] **FIG. 13**. Vertical lift force on all four conducting spheres.

[0048] **FIG. 14**. Perpective view of spacecraft interior.

DETAILED DESCRIPTION OF THE INVENTION

[0049] 1. Referring to the cut-away view **FIG. 14**, the construction of the spacecraft is a thin-wall insulating thermoplastic having a dielectric constant in the range of 20 kilovolts per millimeter (A). An insulated electrode (B) runs from the cabin power supply and high-voltage transformer

(C) to the tip of each tower (D). The four spheres (E) are silver plated to make them conducting. The tube solenoids (F) are driven by a direct current power supply (G).

[0050] 2. The present model uses 3D computer design software and stereolithography fabrication techniques to create the thin-wall, low-weight, hollow structure of the hull. The computer model is sliced into many thin horizontal slices. A laser, mounted on an x-y table, draws out the slice on a table immersed in a bath of liquid polymer. Due to its sensitivity to the light, the liquid polymerizes. The table is then lowered a few thousandths of an inch more and the process is repeated. Thus making hollow spherical and conical shapes is extremely easy to do. Parts can be designed and stored in *.STL stereolithography files for transmission by Internet e-mail to the service bureau machine shop which sends the finished parts back the next day by express mail.

I claim:

1. A spacecraft comprising:

a. a spherical cabin;

b. an electrostatic conical tower mounted on top of item (**1***a*), supporting a vertically-mounted negatively-charged insulated electrode at the tip of the tower;

c. an electrostatic conical tower mounted on the bottom of item (**1***a*), supporting a vertically-mounted positively-charged insulated electrode at the tip of the tower;

d. a vertical electric dipole created by items (**1***b*) and (**1***c*);

e. a high-voltage transformer to drive item (**1***d*), mounted in item (**1***a*);

f. four tubular arms, mounted at 90° around and extending at an angle from item (**1***a*);

g. four solenoids, each of which is mounted axially inside item (**1***f*);

h. a direct current power supply to drive item (**1***g*);

i. four silver-plated conducting spheres, each of which is mounted on the end of item (**1***f*);

2. an electrostatic lift system that:

a. produces a uniform spherical electric field by means of item (**1***d*) which envelopes item (**1***i*);

b. produces a perturbed electric field due to the presence of item (**1***i*);

c. produces an electric dipole moment in the direction of item (**1***b*) due to items (**2***a*) and (**2***b*);

d. produces a vertical magnetic moment due to the clockwise angular velocity of item (**1***a*) combined with item (**2***c*);

e. produces a vertical lift force on item (**1***i*) due to item (**2***d*) combined with the magnetic field gradient in the vertical direction produced by item (**1***g*); and

f. creates a motion control system by varying the current to item (**1***g*) in order to increase or decrease the effect of item (**2***e*) on a particular item (**1***i*).

* * * * *

US 20060144035A1

(19) **United States**

(12) **Patent Application Publication**

St. Clair

(10) **Pub. No.: US 2006/0144035 A1**

(43) **Pub. Date: Jul. 6, 2006**

(54) **PHOTON SPACECRAFT**

(76) Inventor: **John Quincy St. Clair**, San Juan, PR (US)

Correspondence Address:
JOHN ST. CLAIR
52 KINGS COURT, 4A
SAN JUAN, PR 00911 (US)

(21) Appl. No.: **11/027,969**

(22) Filed: **Jan. 3, 2005**

Publication Classification

(51) **Int. Cl.**
F03H 1/00 (2006.01)

(52) **U.S. Cl.** **60/203.1**; 60/204

(57) **ABSTRACT**

A spacecraft propulsion system utilizing photon particles to create negative energy over the hull in order to generate a lift force on the hull.



Figure 1



Figure 2



Figure 3



Figure 4



Figure 5



Figure 6



Figure 7



Figure 8


15
14
17
16
19
18
20

Figure 9



PHOTON SPACECRAFT

BRIEF SUMMARY OF THE INVENTION

[0001] This invention is a spacecraft propulsion system that employs photon particles to generate a field of negative energy in order to produce lift on the hull.

BACKGROUND OF THE INVENTION

[0002] Referring to **FIG. 1**, an electromagnetic wave traveling in the z-direction consists of an electric E field vibrating in the x-direction and a magnetic flux density B field vibrating at right angles in the horizontal y-direction. The energy-stress-momentum of this photon can be analyzed using Einstein's General Theory of Relativity and the Faraday F tensor. The Faraday tensor is a 4×4 matrix containing the electromagnetic wave components as shown here in general where c is the speed of light

$$F^{\alpha}_{\beta}=\begin{array}{c|cccc|} t & 0 & \frac{E_x}{c} & \frac{E_y}{c} & \frac{E_z}{c} \\ x & \frac{E_x}{c} & 0 & B_z & -B_y \\ y & \frac{E_y}{c} & -B_z & 0 & B_x \\ z & \frac{E_z}{c} & B_y & -B_x & 0 \end{array}$$

For this particular photon, this tensor is

$$F^{\alpha}_{\beta}=\begin{array}{c|cccc|} t & 0 & \frac{E_x}{c} & 0 & 0 \\ x & \frac{E_x}{c} & 0 & 0 & -B_y \\ y & 0 & 0 & 0 & 0 \\ z & 0 & B_y & 0 & 0 \end{array}$$

[0003] The elemental spacetime length ds squared is equal to sum of the squares of the Cartesian elemental lengths

$$(ds)^2=-(dt)^2+(dx)^2+(dy)^2+(dz)^2$$

The coefficients of this equation, $\{-1,1,1,1\}$ are the diagonal components of the g metric tensor

$$g_{\alpha\beta}=\begin{array}{c|cccc|} t & -1 & 0 & 0 & 0 \\ x & 0 & 1 & 0 & 0 \\ y & 0 & 0 & 1 & 0 \\ z & 0 & 0 & 0 & 1 \end{array}$$

The stress-energy-momentum tensor T can then be calculated for the photon using the Faraday tensor and the g metric tensor in the following equation from gravitation physics

$$4\pi T^{\mu\nu}=F^{\mu\alpha}F^{\nu}_{\alpha}-\frac{1}{4}g^{\mu\nu}F_{\alpha\beta}F^{\alpha\beta}$$

The stress-energy-momentum tensor indicates the curvature of space due to the application of electromagnetic fields, mass, angular momentum and charge. The mass of the Earth, for example, generates a negative curvature of spacetime such that objects fall toward the mass. The T tensor, which is also a 4×4 matrix, contains the momentum or flux terms in the first row and first column. The normal pressure stress is located along the diagonal. The shearing stresses are located off the diagonal. The energy term is in the upper left corner as depicted here,

$$T^{\mu\nu}=\begin{array}{c|cccc|} t & \text{energy} & flux_x & flux_y & flux_z \\ x & -flux_x & pressure_x & shear_{xy} & shear_{xz} \\ y & -flux_y & shear_{yx} & pressure_y & shear_{yz} \\ z & -flux_z & shear_{zx} & shear_{zy} & pressure_z \end{array}$$

[0004] Since $B^2=E^2/c^2$, the stress-energy-momentum tensor for the photon is therefore

$$T^{\mu}_{\nu}=\begin{array}{c|cccc|} t & \frac{-E^2}{c^2} & 0 & 0 & \frac{+E^2}{c^2} \\ x & 0 & 0 & 0 & 0 \\ y & 0 & 0 & 0 & 0 \\ z & \frac{-E^2}{c^2} & 0 & 0 & \frac{+E^2}{c^2} \end{array}$$

This remarkable result shows that the photon is actually a negative energy particle (top left corner) which is pushed along by a positive pressure wave (lower right corner). The particle has a positive flux (upper right corner) in the z-direction, as well as a balancing negative flux in the lower left corner so that the overall momentum of the universe remains the same. All four components cancel and we see the photon as a massless particle moving at the speed of light.

[0005] Thus the key idea behind this invention is that it is possible to cancel out the pressure term and leave a stationary vibrating electromagnetic field of negative energy over the hull of the spacecraft. The importance of negative energy is that it is a prerequisite to generating wormholes between space and hyperspace.

[0006] Hyperspace consists of the those co-dimensions which have different physics constants such as a low speed of light. The existence of hyperspace, which has a white misty look, is not a well-known scientific concept. Experiments with our magnetic vortex wormhole generators, hyperspace torque generator, full body levitation using Chi Kung breathing, arm levitation by spinning the co-gravitational K field, full body teleportation through hyperspace a distance of 100 meters using a pulsed gravitational wave, jumping into hyperspace, having a plate of toast enfold off the breakfast table and disappear into thin air, walking through walls and doors out-of-dimension, looking into other dimensions, remote viewing through subspace to distances of 100,000 light years, and other electromagnetic experiments carried out by co-researchers, have shown us the reality and existence of hyperspace.

[0007] Referring to **FIG. 2**, the spacecraft consists of an upper (**1**) and lower (**2**) hull attached by ceramic insulators to a circular ring (**3**). The ring provides support and is attached to an outer sharp-edged rim which is electrostatically charged to a potential −V. The purpose of the charged rim is to generate a radial electric E field around the vehicle.

[0008] Referring to **FIG. 3**, the radius of the ring (**4**) is equal to a. The distance from a point on the ring to the z-axis is r. The potential on the z-axis is therefore the charge divided by the distance,

$$potZ = \frac{q}{\sqrt{a^2 + r^2}}$$

This potential is expanded as a series in terms of inverse radius r

$$potZout = \frac{35qa^8}{128r^9} - \frac{5qa^6}{16r^7} + \frac{2qa^4}{8r^5} - \frac{qa^2}{2r^3} + \frac{q}{r}$$

The potential outside the ring can be written in terms of the Legendre polynomials P

$$Vout = \sum_{n=0}^{s} \left(\frac{a}{r}\right)^{n+1} A[n] LegendreP[n, \mathrm{Cos}(\theta)]$$

where s is the number of terms in the expansion. By equating the known particular solution potZout on the z-axis with the general Vout solution, the coefficients A[n] are found to be

$$A(0) = \frac{q}{a}$$

$$A(1) = 0$$

$$A(2) = \frac{-q}{2a}$$

$$A(3) = 0$$

which are substituted back into the Vout equation to get the potential outside the ring.

[0009] Referring to **FIG. 4**, the potential (dotted lines **6**) looking at a slice through the ring (**5**) is shown together with the electric E field. The negative gradient of the potential is the electric field (**7**) shown by the direction of the arrows. The importance of this diagram is that the electric field points in the radial direction toward the negatively charged ring. The force on an electron is the electron charge times the electric field

$$F = q_e E_r = -/q_e|(-|E_r|) = +F$$

Because the electron charge is negative and the radial field points in the negative direction toward the ring, the force on the electron is positive. Thus the electron moves away from the ring in the positive radial direction. A 3-dimensional plot of the ring (**8**) and the electric field (**9**) is shown in **FIG. 5**.

[0010] The stress-energy-momentum generated by a radial electric field is calculated using the Faraday F tensor

$$F_\alpha^\beta = \begin{vmatrix} 0 & E_r & 0 & 0 \\ E_r & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 \end{vmatrix}$$

The g metric tensor has to be given in spherical coordinates {r,θ,ϕ}

$$g_{\alpha\beta} = \begin{vmatrix} -1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & r^2 & 0 \\ 0 & 0 & 0 & r^2 \sin(\theta)^2 \end{vmatrix}$$

where θ is the angle from the vertical to the radius r. The stress tensor T^{rr} along the radial direction is

$$T^{rr} = \frac{E_r^2}{8\pi c^2}$$

which shows that the pressure is negative along the radial line equal to the square of the radial electric field divided by the square of the speed of light. Because the field is squared, it doesn't matter that the electric field points in the negative direction. The square makes it positive, but the overall curvature pressure is negative. Thus this negative pressure cancels out the positive pressure propelling the photon along. The second key idea of the invention is how to generate this photon moving in the radial direction.

[0011] It has been known for a long time in physics that an electron moving in a circular path will emit photons in a process known by the German word Bremsstrahlung which is translated as "breaking radiation." There are several types of radiation such as classical Bremsstrahlung involving a charged particle making a collision with another charged or uncharged particle in which photons are emitted. The quantum mechanical Bremsstrahlung involves the sudden appearance or disappearance of a charged particle which also emits radiation. In space, having a field of wormholes in which the electrons are spiraling down into hyperspace would result in the emission of photons by the quantum mechanical method. Also, in the atmosphere, having collisions with air molecules results in emission of photons in the classical way.

[0012] In order to get the electrons to spiral around and emit photons, a crossed electromagnetic field is used as shown by the following equation

$$F = q(E_r + v_r \times B_\theta)$$

where the velocity v is in the positive radial direction due to the force of the electric field. The velocity crossed with a magnetic flux density B field in the θ-direction makes the electron move sideways back and forth in a wiggling motion.

[0013] Referring to **FIG. 6**, a direct current solenoid (**10**), represented by multiple current loops, running vertically through the center of the hull, generates a magnetic field that curves around the outside of the hull, as shown by contour lines (**12**). The north pole (**11**) is at the bottom of the hull. A radial arrow (**13**) from the electrostatically-charged rim is perpendicular to the magnetic field lines. The cross product in the force equation becomes the electron radial velocity times the magnetic field $v_r B_\theta$.

[0014] Referring to **FIG. 7**, the electric field is in the y-direction and the magnetic field is in the z-direction. The flat looping path in the x-direction is the motion of the electron. The electron, which has a negative charge, starts to move in the direction opposite to that of the electric field. In this particular diagram, the electron acquires a velocity in the negative y-direction. Then a sideways force in the x-direction is produced due to the cross product of the velocity with the magnetic field times the negative charge

$$-q(-v_y \times B_z)=+F_x$$

Depending on the magnitude of the velocity, various size loops can be produced.

[0015] In terms of the hull coordinates, because the flat loop is in the plane of the electric field which points in the radial direction, the electron emits light in the radial direction. This condition means that the negative radial pressure created by the electric field cancels the radial pressure of the photon. Thus the photon becomes a stationary vibrating quantum of negative energy. This has the appearance of a luminescent light source. The stress tensor for this condition is therefore

$$T_\mu^\nu = \begin{vmatrix} -\frac{E^2}{c^2} & 0 & 0 & \frac{E^2}{c^2} \\ 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 \\ -\frac{E^2}{c^2} & 0 & 0 & 0 \end{vmatrix} = -\frac{E^2}{c^2} \text{residual negative energy}$$

[0016] residual negative energy

which leaves a residual negative energy per photon.

[0017] Referring to **FIG. 8**, the negatively charged rim (**14**) produces a radial electric field (**16**) that crosses the magnetic B field (**15**) of the solenoid. Electrons emitted by the charged rim then encounter this crossed field which makes them spiral (**17**) around the hull. Because of the tight loop, the electron emits Bremsstahlung radiation in the radial direction (**18**). The positive pressure field of the photon, which is directed in the radial direction, is canceled by the negative pressure field (**19**) created by the electric field. Because the photon energy is negative, a stationary vibrating electromagnetic quantum of negative energy (**20**) surrounds the hull.

[0018] This negative energy and the pressure stress created by the electromagnetic fields open up wormholes between space and hyperspace. The potential head is positive from hyperspace into space because the energy of hyperspace is more positive than the negative energy field. The low-density hyperspace energy fills the hull and its surrounding space with a white misty hyperspace energy which makes the spacecraft lighter in mass, and therefore lighter in weight within a gravitational field. The actual physics is more complicated still because the electrons find that the resistance of hyperspace is lower than the resistance of space. Thus they spiral down the wormholes which results in a sudden disappearance of charge. The quantum mechanical effect of this is to radiate even more photons which in turn produce even more negative energy.

[0019] The lift on the hull is generated by the radial electric field. In cylindrical coordinates, the g metric tensor is

$$g_{\alpha\beta} = \begin{vmatrix} -1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & r^2 & 0 \\ 0 & 0 & 0 & 1 \end{vmatrix}$$

Using this metric tensor, the pressure stress in the vertical direction T^{zz} is

$$T^{zz} = \frac{E^2}{8\pi c^2}$$

which is a positive curvature over the hull. The mass of Earth produces a negative curvature in which objects fall toward the mass. By counteracting this negative curvature with a more than positive curvature, lift is developed on the spacecraft. Because the negative energy lowers the effective mass of the vehicle, the acceleration is large with a modest electric field. Moreover, in our dimension, the speed of light is 299792458 meters per second. Hyperspace energy has a speed of light equal to one meter per second. Thus the stress is amplified by a factor of

$$A = \left(\frac{299792458\,m/s}{1\,m/s}\right)^2 \approx 9 \cdot 10^{16}$$

Because electromagnetic fields are relativistic, motion in a low-velocity-of-light energy field amplifies their strength.

SUMMARY OF THE INVENTION

[0020] It is the object of this invention to create a spacecraft propulsion system that produces wormholes between space and hyperspace using negative energy in order to generate lift on the hull. It was discovered in the Riemannian curvature calculations of gravitation physics that negative energy is required to keep open the throat of the wormhole. From experiments with the magnetic vortex wormhole generator, it is known that the proper combination of electromagnetic fields, together with this negative energy, can create a wormhole through which smoke can be blown into hyperspace.

[0021] Referring to **FIG. 9**, the directions of force, velocity, and electromagnetic fields are referred to in the cylindrical coordinate system $\{r,\theta,z\}$. An electrostatically charged sharp-edged ring in the θ-direction around the hull of the spacecraft produces a radial electric field. A vertical solenoid in the z-direction through the center of the hull produces a magnetic field which is perpendicular at the rim to the electric field. With the current in the solenoid flowing in the clockwise (−θ) direction, using the right-hand rule, the magnetic field points in the upward z-direction outside the rim. Because the rim is charged to a negative voltage, the electric field points toward the hull in the negative radial (−r) direction. Electrons emitted by the rim travel outward (+v) because the charge on the electron is negative which, together with the negative electric field, produces a positive radial force. The radial force on the electron causes it to acquire a velocity which interacts with the magnetic field. The cross product of the velocity (+v) with the positive (+B) magnetic field produces a sideways force on the electron in the negative θ-direction. However, because the charge on the electron is negative, the force is

$$F=-q\{v_r,0,0\}\times\{0,0,B_z\}=\{0,qB_zv_r,0\}$$

which is positive in the θ-direction. It is this sideways force that produces a flat spiraling or looping motion whereby the electron emits photons, known in German as Bremsstahlung radiation, in the radial direction. The photon, which is actually a quantum of negative energy, has a positive radial pressure which propels it along. Because the radial electric field produces a negative pressure in the radial direction, the two opposite fields cancel in the radial direction to form a residual stationary vibrating negative energy. Thus the hull becomes surrounded by negative energy which, together with the pressure stresses created by the electric field, generates wormholes between space and hyperspace.

[0022] The gravitational potential between hyperspace and space is positive because the hyperspace energy is more positive than the negative energy around the hull. Thus the low-density, low-speed-of-light hyperspace energy flows through the wormhole and fills the hull. This has the effect of reducing the effective mass of the hull. Because the electric field generates a positive pressure over the hull in the vertical z-direction, there is an upward force on the vehicle due to the pressure times the hull area. Since the vehicle has a low mass, there is a modest upward acceleration on the spacecraft equal to the force divided by mass.

A BRIEF DESCRIPTION OF THE DRAWINGS

[0023] **FIG. 1**. Perspective view of an electromagnetic wave.

[0024] **FIG. 2**. Perspective view of spacecraft.

[0025] **FIG. 3**. Perspective view of charged ring.

[0026] **FIG. 4**. Planar plot of the radial electric field produced by charged ring.

[0027] **FIG. 5**. Perspective view of radial electric field around ring.

[0028] **FIG. 6**. Planar view of magnetic flux density field contour lines.

[0029] **FIG. 7**. Perspective view of electron motion in crossed electric and magnetic fields.

[0030] **FIG. 8**. Perspective view of production of negative energy around hull.

[0031] **FIG. 9**. Perspective view of cylindrical coordinate system {r,θ,z}.

DETAILED DESCRIPTION OF THE INVENTION

[0032] 1. The hull is made from a single sheet of aluminum which has been stretched to its yield point by hydraulic cylinders. An upper and lower die is CNC machined to the profile of the hull. The soft sheet is then clamped in the die where it takes on the smooth shape of the hull without any wrinkles. The hull is extremely rigid after forming and does not require any structural reinforcements.

[0033] 2. A section of the aluminum ring is made in a 3D computer graphics program. The model is stored as a stereolithography file (*.stl). The computer model is then sent via Internet e-mail to the stl server who prints the part in an ultraviolet light-cured polymer. The part is returned the next day by Express Mail. Using a rubber blanket mold to create several ring sections, the entire ring is assembled together in another wooden mold box having thin circular laminate-coated particulate wall boards on either side of the ring. Then a liquid rubber mold is poured on top of the ring and allowed to harden overnight at room temperature. Since the rubber mold is flexible, the ring can be extracted fairly easily. This ring model is then sent to the foundry where it is cast in aluminum using the lost wax process in which a wax mold evaporates out of the sand casting. We are also experimenting with non-magnetic copper casting metals containing beryllium having good conductivity.

[0034] 3. A 11.5 cm plastic pipe is mounted on a rotating fixture driven slowly by a microcontoller, stepper motor, and power electronics board. Using a large diameter insulated wire, such as a 17 AWG with a wire diameter of 0.127 cm, the wire is wound slowly on the pipe and expoxied so that the windings don't come loose. The solenoid is then mounted vertically in the hull supported by the support ring and driven by a current generator located nearby on the test rig.

[0035] 4. The ring is driven by a high voltage electrostatic generator similar to the night vision scope high voltage power supplies. The ring charge is isolated from the hull by ceramic insulators.

I claim:

1. A spacecraft propulsion system comprising the components:

an aluminum horizontal circular structural support ring;

an aluminum hull in the shape of a high dome on top and shallow dome on the bottom attached to the circular support ring using ceramic insulators;

an electrostatically negatively-charged sharp-edged circular ring, preferably of non-magnetic aluminum or copper, attached with ceramic insulators to the outside of the support ring;

a solenoid mounted through the center of the hull in the vertical direction and attached to the center of the support ring;

an electrostatic high-voltage generator to drive the outer electrostatic ring; and

a direct high-current generator to drive the solenoid.

2. The method of claim 1, wherein a negative radial electric field is generated around the hull by placing a negative potential on the sharp-edged electrostatic ring using the electrostatic generator.

3. The method of claim 1, wherein the current-driven solenoid generates a vertical magnetic field around the hull with the north pole of the solenoid facing down through the bottom of the hull which causes the magnetic flux density field to point up outside the rim.

4. The method of claim 1, wherein electrons are emitted radially by the sharp edge of the charged ring.

5. The methods of claims **2**, **3** and **4**, wherein the crossed electromagnetic fields cause the electrons to spiral around in flat loops during which photons are emitted in the radial direction.

6. The methods of claims **2** and **5**, wherein the negative radial pressure created by the electric field cancels the positive radial pressure of the photon to leave a residual quantum of negative energy per photon around the hull.

7. The methods of claims **2** and **6**, wherein the pressure stress created by the electric field, and the negative energy combine to form wormholes between space and hyperspace.

8. The method of claim 7, wherein low-density hyperspace energy of a higher gravitational potential flows through the wormholes to fill the hull and surrounding space around the hull with the effect of reducing the effective mass of the spacecraft.

9. The method of claim 2, wherein the electric field generates a positive pressure in the vertical direction over the hull which together with the hull surface area, generates an upward lift force on the hull.

10. The method of claim 6, wherein the negative energy, having a low light speed, amplifies the strength of the electromagnetic fields and pressure stress fields.

11. The methods of claims **4** and **7**, wherein the electrons spiral down the low resistance wormholes into hyperspace such as to create a sudden disappearance of electrical charge which quantum mechanically causes a large emission of additional photons.

* * * * *

US 20040200925A1

(19) **United States**

(12) **Patent Application Publication** (10) **Pub. No.: US 2004/0200925 A1**

St.Clair (43) **Pub. Date: Oct. 14, 2004**

(54) **CAVITATING OIL HYPERSPACE ENERGY GENERATOR**

(76) Inventor: **John Quincy St.Clair**, San Juan, PR (US)

Correspondence Address:
John St.Clair
Hyperspace Research Institute
52 Kings Court, 4A
San Juan, PR 00911 (US)

(21) Appl. No.: **10/372,557**

(22) Filed: **Feb. 21, 2003**

Publication Classification

(51) **Int. Cl.^{7}** **B64C 27/22**
(52) **U.S. Cl.** **244/10**

(57) **ABSTRACT**

A hyperspace energy generator that uses cavitating oil bubbles within a magnetic field in order to create wormholes between space and hyperspace for the purpose of permeating the hull of a spacecraft with low-density hyperspace energy.



Figure 1



Figure 2



Figure 3



Figure 4


B
C
A
Machine

Figure 5



Figure 6


A
B
C
M
D
E
G
H
J
F
L
K
I

Figure 7


H
d
f
E
c
C
D
F
G
B
e
A
b
a
19.471220°
-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
-10 -20 -30 -40 -50 -60 -70 -80 -90 -100 -110 -120 -130 -140 -150 -160 -170 -180 -190
ln(wavelength)

Figure 8


ϕ
B
$+\rho_m$
A
C
$-\rho_m$

Figure 9



Figure 10



Figure 11



Figure 12


R acceleration
1/S
R velocity
1/S
R
+
+
.1
1/X
1/R
*
1/R
+
+
-3/2
*
R velocity
+
+
.0001
t
e^-sTd
x
R
-2087000
+
pow
*
+
1/R
83810
R velocity
Viscosity
-.0001019
*
1/R
+
+
-.096
1/R


R
Plot
.20
.18
.16
.14
.12
.10
.08
.06
.04
.02
0
0
.0002
.0004
.0006
.0008
.001
.0012
.0014
.0016
Time (sec)

Figure 13


BUBBLE SIZE
SOUND WAVE
LIGHT FLASH
BUBBLE RADIUS (MICRONS)
0
10
20
30
40
50
ACOUSTIC PRESSURE AMPLITUDE (ATMOSPHERES)
3
2
1
0
−1
−2
−3
5
10
15
20
25
30
35
TIME (MICROSECONDS)

Figure 14



Figure 15



Figure 16


Rx, Ry
Asymmetrical Collapse x upper curve , y lower curve
25
20
15
10
5
2.5
5
7.5
10
12.5
15
time

Figure 17



Figure 18


Gtt
Asymmetrical Collapse Energy Density Gtt
2
-2
-4
-6
2.5
5
7.5
10
12.5
15
time

Figure 19



Figure 20



Figure 21



Figure 22



Figure 23



Figure 24


A
B
C
D
E
F
G
H
I
J
K
L
M

CAVITATING OIL HYPERSPACE ENERGY GENERATOR

BRIEF SUMMARY OF THE INVENTION

[**0001**] This invention is a hyperspace energy generator that uses cavitating oil bubbles within a magnetic field in order to create wormholes between space and hyperspace for the purpose of permeating the hull of a spacecraft with low-density, low-speed-of-light hyperspace energy.

BACKGROUND OF THE INVENTION

[**0002**] As shown by physicist Dr. John Archibald Wheeler of Princeton University, there is a second term in Newton's gravitational equation which includes an additional force depending on whether or not the body is spinning.

$$F=mg+m(v\times\Omega)$$

[**0003**] where F is the force, m the mass, g the acceleration of gravity, v the forward velocity of the body, and Ω the angular velocity of the body. Referring to **FIG. 1**, a rotating cylinder (A) is moving with a velocity (B) while spinning counterclockwise as shown by the angular velocity vector (C). The velocity crossed with the angular velocity vector produces a force in the upward direction (D).

[**0004**] Referring to **FIG. 2**, a pendulum (A) held in the left hand over the right hand will spin in the counterclockwise direction due to the hyperspace energy vortex (B) emanating from the palm of the right hand. This vortex arises because human beings are hyperspace energy beings that live in physical containers located in this universe. The vortex might be considered a wormhole between space and hyperspace. Notice that the angular momentum vector of the vortex points up out of the palm of the hand. If the hand were spinning from left to right, then there would be a force exerted, as shown by the above equation, that would bring hyperspace energy into the right arm.

[**0005**] Referring to **FIG. 3**, in order to test this hypothesis, a Chakra Vortex Accelerator was built for the purpose of spinning this hand vortex. The motor-driven machine has a base (A) on which is mounted a warehouse palletizing ring and platform (B). A control column (C) has a speed control and on/off switch. A person (D) stands on the platform with his right arm outstretched and palm facing upward (E). The platform spins from left to right.

[**0006**] Referring to **FIG. 4**, the velocity vector (A) points to the right. The angular momentum vector of the rotating chakra energy vortex points up. The cross product A×B=C produces a force that brings in high permeability hyperspace energy into the arm.

[**0007**] Referring to **FIG. 5**, after spinning 99 times per day for a few months, it was noticed that the right arm (A) would remain out at an angle ϕ from the body without making any exertion to do so. The left arm, which was not receiving the energy, remained at the side of the body. That is, the low-density hyperspace energy in the right arm was making the arm lighter and producing a subsequent anti-gravitational effect. The conclusion was that it might be possible to invent some device which would produce large amounts of hyperspace energy. This would make possible relativistic electromagnetic fields which can be used to produce the lift force for electromagnetic field propulsion vehicles.

[**0008**] Then in the February 1995 issue of *Scientific American*, an article appeared entitled *Producing Light from a Bubble of Air* which gave the details for producing sonoluminescence from a cavitating bubble using a kit for sale containing the piezoelectric transducers. Referring to **FIG. 6**, the experimental setup includes a ring stand (A) with a three-finger clamp (B) holding a 100 milliliter flask containing degassed water produced by a Walsh vacuum/pressure pump. Piezoelectric drive transducers (D) are mounted on the sides of the flask in order to create sound pressure waves which create the cavitation bubble (M) in the center of the flask. The transducers are connected by insulated wire (I) to a pair of inductors (E) having a mutual inductance between them. These inductors are driven by a frequency generator (H) connected to an audio amplifier (G). The oscillation signals are picked up by the oscilloscope (J) which is connected to the resistors (F) using the probes (K). The piezoelectric drive transducers act electrically as capacitors. The inductors are wired in series with the capacitance such that the combination resonates at the frequency at which acoustic resonance occurs. Bubbles introduced into the flask tend to coalesce in the center of the flask Above a certain sound intensity, the bubble will collapse and emit a dim light visible to the unaided eye in a darkened room, a process called sonoluminescence.

[**0009**] Further research showed that there were some earlier doctoral theses available. One of them by Dr. Steven DeWitt Horsburgh entitled *Radial Instabilities of a pulsating air bubble in water* mentioned a most interesting observed phenomenon of the surface oscillations called a "beaconing effect." When a bubble exhibited a stable or long-lived shape oscillation lasting more than two minutes, the bubble had a tendency to slowly precess. The precession rate was on the order of a few hertz which can be taken to mean around 3 Hz. Visually, the beacon looked like a light house beacon. It was a very obvious effect and when the beacon crossed the photodiode, the output voltage increased by at least an order of magnitude.

[**0010**] Upon reading this, it became apparent that sonoluminescence is involved with gravitational hyperspace physics. Einstein's theory says that inertia is a manifestation of the geometry of spacetime. It also says that geometry is affected by the presence of matter to an extent proportional to the factor G/c^2 where G is the gravitational constant and c is the speed of light. The inverse of this factor is the linear mass Ω of the universe. A spherical shell of mass m with a radius R will create a drag angular velocity on a pendulum equal to

$$\omega_{drag}=\frac{4}{3}\frac{G}{c^2}\frac{m_{shell}}{R_{shell}}\omega_{shell}=\frac{4}{3}\frac{\frac{m_{shell}}{\Omega}}{R_{shell}}\omega_{shell}$$

[**0011**] The mass of the shell divided by the linear mass (mass per length) converts the mass into a length which is then divided by the radius of the shell which is also a length. The numerical factor 4/3 is found only by a detailed calculation. The calculation, starting from a flat background spacetime manifold, showed the effect of the moving current of mass on the metric. Expressed in polar coordinates, the metric acquires a non-zero coefficient $g_{\phi t}$. Inserted into the equation for geodesic motion, this off-diagonal metric coefficient gives rise to a precession according to the above equation. The numerical factor corresponds to a pendulum located anywhere inside the rotating shell of mass.

[0012] In other doctoral theses, books and physics articles on cavitation, light is emitted after the bubble starts to collapse. A very sharp peak of light is produced which lasts in terms of picoseconds. Thus this type of sonoluminescence is very different than the beaconing effect where the bubble remains stable for long periods of time. The beaconing effect is actually a rotating wormhole between space and hyperspace.

[0013] Briefly what happens is that there is ionized gas in the bubble which releases electrons. As the electrons spiral down through the wormhole from space into hyperspace, they give off light. This situation puts the electrons in contact with the charge of hyperspace. Space has a charge which is equal to the sum of the electron charge q_e and the hyperspace charge q_h. The charge of space q is equal to the Planck mass times a conversion factor between mass and charge. The Planck mass is equal to the linear mass Ω of the universe times the bottom dimensional limit of the universe known as the Planck scale Λ. The conversion factor is the square root of the gravitational constant G times the permittivity of space ϵ. The permittivity is linear capacitance or capacitance per unit length. Thus the charge of space is

$$q=\Lambda\Omega\sqrt{G\epsilon}=q_e+q_h$$

[0014] Because the electron comes in contact with the hyperspace charge, the drag angular velocity in the above equation has to be modified. Notice that if the angular velocity of the shell is modified by the electron fine structure constant α, and the mass involved is the mass of the electron, moving through a radius into hyperspace of the Planck scale Λ, then the drag angular velocity would be

$$\omega_{drag}=\frac{4}{3}\frac{\frac{m_{electron}}{\Omega}}{\Lambda}\omega_{shell}\frac{1}{\alpha}$$

[0015] The angular frequency of the shell is 2π times the electron frequency f_e.

$$\omega_{shell}=\omega_{electron}=2\pi f_e$$

[0016] The inverse of the electron fine structure constant α is equal to Planck's reduced constant ħ times the speed of light c times the factor 4π times the permittivity of space ϵ divided by the square of the charge of the electron q_e.

$$\frac{1}{\alpha}=\frac{\hbar c4\pi\varepsilon}{q_e^2}n=137.037916527$$

[0017] Planck's constant is equal to the Planck scale Λ squared times the linear mass Ω times the speed of light.

$$\hbar=\Lambda^2\Omega c$$

[0018] Notice that the fine structure constant has a square in it and Planck's constant also has a square. If the electron charge were traveling through the Planck scale into hyperspace, then there would be a linear charge equal to the electron charge divided by the Planck scale

$$\frac{1}{\alpha}=\frac{\hbar c4\pi\varepsilon}{q_e^2}n=\frac{\Lambda^2\Omega cc4\pi\varepsilon}{q_e^2}n=\frac{4\pi\Omega\varepsilon c^2}{\left(\frac{q_e}{\Lambda}\right)^2}n$$

[0019] The constant equal to the linear mass Ω times the permittivity times the square of the speed of light is actually the square of the linear charge χ of space. So the fine structure constant can be written

$$\frac{1}{\alpha}=4\pi n\frac{(\chi)^2}{\left(\frac{q_e}{\Lambda}\right)^2}=4\pi n\frac{\left(\frac{q}{\Lambda}\right)^2}{\left(\frac{q_e}{\Lambda}\right)^2}=4\pi n\left(\frac{q}{q_e}\right)^2=4\pi n\left(\frac{q_h+q_e}{q_e}\right)^2=$$

$$4\pi n\left(\frac{q_h}{q_e}+1\right)$$

[0020] So the electron fine structure constant is related to the ratio of the charge of hyperspace to the charge of the electron, which is the reason that the equation had to be modified. The electron moving across the Planck scale wormhole is modified by the hyperspace charge it is seeing in a hyperspace co-dimension. This confirms that the beaconing effect is a rotating wormhole into hyperspace.

[0021] The electron fine structure constant is actually the fastest velocity in the Bohr atom. The fine structure constant is the ratio of the electron orbital velocity to the speed of light.

$$\alpha=\frac{v_n}{c}$$

[0022] where the permitted quantized n orbital speeds are v_n/n or v/1, v/2, v/3 and so on. Using a value of v/3, the fine structure constant would be

$$\frac{1}{\alpha}=\frac{3c}{v}=4\pi n\left(\frac{q_h}{q_e}+1\right)=12\pi\left(\frac{q_h}{q_e}+1\right)$$

[0023] which when substituted into the drag angular frequency equation

$$\omega_{drag}=\frac{4}{3}\frac{\frac{m_e}{\Omega}}{\Lambda}2\pi f_e12\pi\left(\frac{q_h}{q_e}+1\right)=17.809\ \frac{\text{radians}}{\text{sec}}$$

[0024] The frequency of precession is

$$f_{drag}=\frac{\omega_{drag}}{2\pi}=2.83\text{ Hz}$$

[0025] which is close to the 3 Hz observed in the experiment. The ionized electrons are moving at a slower velocity in the bubble. The 1/3 ratio could also come from the subspace tetrahedron geometry where the tetrahedral angle is determined by this ratio

$$\theta=\mathrm{asin}(1/3)=19.47122063^\circ$$

[0026] This is an alternative possibility because this angle determines the charge of hyperspace according to the tetrahedron diagram of Δphysics. In geometrical physics, all the constants of physics are determined geometrically by the tetrahedron. The tetrahedron diagram plots the natural logarithm of mass versus the natural logarithm of wavelength. The tetrahedron is circumscribed by a sphere which reflects the electron wavelength into the electron mass. Thus the diagram combines the dual reality of classical physics, involving point mass particles, and quantum physics, involving wave-like particles. The scientific discovery that the electron and the proton are one and the same particle was made using this diagram. It also shows that hyperspace exists.

[0027] Referring to the tetrahedron diagram in **FIG. 7**, a line drawn at the tetrahedral angle produces the tetrahedral lines (A,B) along path (abc). This tetrahedron is circumscribed by sphere (C) with diameter (G). The electron wavelength (vertical dotted line D) reflects off the sphere (d,f) and returns as the electron mass (F). The distance (df) between reflection points is equal to the natural logarithm of the hyperspace charge. It can be shown that the electron charge is related to the geometry around the top of the sphere. Part of the geometry is outside the sphere which makes the charge immune to relativistic velocities.

[0028] Referring to **FIG. 8**, a current-carrying solenoid (A) produces a magnetic flux (B) through the center of the coil. The end of the solenoid behaves like a magnetic monopole. One end has a positive magnetic charge density $+\rho_m$ and the other has a negative magnetic charge density $-\rho_m$. One of Maxwell's electromagnetic equations states that the divergence of the magnetic field is equal to the magnetic charge density.

$$\nabla\cdot B=\rho_m=+\rho_m-\rho_m=0$$

[0029] Because the magnetic field is solenoidal, the sum of the charges in our spacetime is equal to zero, which is the usual Maxwell equation. In the case of the wormhole, one pole of the magnetic flux is in our spacetime and the other pole is in a co-dimension of hyperspace. In our universe, there is a net magnetic charge density, and Maxwell's equation becomes

$$\nabla\cdot B=\rho_m$$

[0030] When working with bar magnets, bringing two north poles together shows that there is a spring constant involved. The electrons on the surface of the pole spin in the same direction which creates an electrical current around the surface. The magnetic pole strength g is therefore a spring constant K divided by the current per area J.

$$g=\frac{K}{J}\equiv\frac{kg\;m}{s^2}\frac{1}{m}\frac{s\,m^2}{q}=\frac{kg\;m^2}{s\,q}$$

[0031] The magnetic charge density is then the pole strength per volume V or

$$\rho_m=\frac{g}{V}=\frac{kg\,m^2}{s\,q}\frac{1}{m^3}=\frac{kg}{m\,s\,q}$$

[0032] The divergence of the magnetic field has units of

$$\nabla\cdot B=\frac{1}{m}\frac{kg}{s\,q}$$

[0033] which are the units of the magnetic charge density. Notice that the units can also be formatted as a pressure per electrical current in the wire.

$$\rho_m=\frac{kg}{s\,q\,m}=\frac{kg\;m}{s^2\frac{q}{s}m^2}=\frac{\text{force}}{\text{area}}\frac{1}{I}=\frac{\text{pressure}}{\text{current}}$$

[0034] The current flowing through the coils of the solenoid, or around the pole face of the bar magnetic creates a pressure on spacetime. And it is this pressure that can punch through spacetime into hyperspace. Referring again to **FIG. 8**, an electrical charge winding n times around the end of the spacetime solenoid, as seen by path (C), is equal to the charge divided by Planck's constant times the pole flux

$$2\pi n=\frac{q}{\hbar}\int_{Surface}B=\frac{q}{\hbar}\Phi$$

[0035] which shows that the flux Φ is quantized by the winding number n

$$\Phi=n\frac{2\pi\hbar}{q}=n\frac{h}{q}$$

[0036] where the flux is equal to the winding number n times Planck's constant h divided by the charge. Since the flux is the pole strength in webers, the pole strength g has a value of

$$g=n\frac{h}{q}$$

[0037] The magnetic charge density is the pole strength divided by the Planck volume or

$$\rho_m=\frac{g}{\Lambda^3}=n\frac{h}{q}\frac{1}{\Lambda^3}=n\frac{2\pi\Lambda^2\Omega c}{q\Lambda^3}=\frac{2\pi n}{\Lambda}\frac{\Omega c}{q}=2\pi n\frac{B}{\Lambda}$$

[0038] The magnetic B field of space divided by the Planck length of the wormhole, acting as a linear magnetic field, times the winding number is equal to the magnetic charge density.

[0039] Referring to **FIG. 9**, the wormhole (A), connecting space and hyperspace (D), is precessing (C) in the counterclockwise direction with the angular velocity vector in the vertical z-direction. The magnetic flux (B) through the wormhole is in the radial direction. The mouth of the wormhole is an area with a normal vector in the radial direction also. This arrangement creates an electric field which circulates around the interior periphery of the wormhole. Maxwell's equation says that the curl of the electric field E is equal to the negative time rate of change of the magnetic B field.

$$\nabla \times E = -\frac{\partial B}{\partial t}$$

[0040] This equation is difficult to manage in differential form. As both Maxwell and Feynman have said, it is better to use the integral form involving Stokes' theorem where the area da is converted into a line integral ds which goes well with Maxwell's idea of flux linkage.

$$\int_{surface} (\nabla \times E) \cdot n\, da = \oint E \cdot ds = -\frac{\partial}{\partial t} \int_{surface} B \cdot n\, da = -\frac{\partial}{\partial t} \Phi = -\Phi\, \omega_{drag}$$

[0041] The flux Φ, which is precessing around at the drag angular velocity calculated previously, is equal to the negative of the electric field around the interior perimeter (E) of the wormhole. This is the reason that the beaconing effect lasts for such a long length of time. The force on the electron is equal to the charge of the electron times the electric field. Because the charge is negative, the electron rotates counterclockwise in the opposite direction to that of the electric field. The electrons continuously circulate around the inside periphery of the wormhole. Quantum theory predicts that any radiated electromagnetic energy from an accelerated electron will give off one or more discrete quanta, or photons. The electron is accelerating because it is moving in a circular path. Because the water vapor is ionized in the cavitating bubble due to shock waves, surface oscillations and high temperatures, there are huge numbers of electrons available for producing an intense light which, as registered by the photodiode, increased by an order of magnitude when the beacon rotated by the photodiode.

[0042] From gravitational physics it is known that negative energy has to be produced in order to create a wormhole. Most experimenters are using collapsing spherical bubbles that do not produce negative energy and therefore do not produce the beaconing effect. This next background section shows that if the bubble collapses asymmetrically, then negative energy is produced.

[0043] Referring to an experiment carried out by Fizeau, **FIG. 10**, water flows (B,C) in opposite directions in two tubes of water (A). A light beam from a lamp (D) is projected through both tubes using half-silvered mirrors (E). Fizeau measured an interference (F) between light propagating with the flow and light swimming against the current, indicating that the flow of the medium does affect light propagation. A moving medium turns out to drag light to an extent quantified by a dragging coefficient

$$\alpha = 1 - \frac{1}{n^2}$$

[0044] where n is the index of refraction of the medium. Einstein's addition theorem of velocities states

$$v = \frac{v' + u}{1 + \frac{v'u}{c^2}} = \frac{\frac{c}{n} + u}{1 + \frac{cu}{nc^2}} = \frac{\frac{c}{n} + u}{1 + \frac{u}{nc}}$$

[0045] In the limit of slow flows compared with the speed of light in a vacuum, the effective velocity of light v in the medium flowing at a velocity u is

$$v \approx \left(\frac{c}{n} + u\right)\left(1 - \frac{u}{nc}\right) \approx \frac{c}{n} + \alpha u$$

[0046] The relationship between cavitating bubbles and light dragging is that when the bubble collapses, the surface has a tremendous acceleration and velocity which creates internal shockwaves that bounce back and forth within the medium. At the same time, the water vapor and air are ionized which creates short bursts of light. Thus there is light that is being dragged along by the collapsing surface of the bubble. This moving medium appears to light as a change in the metric of spacetime resembling, it turns out, a gravitational field. The velocity of the medium affects the elemental length ds^2 of spacetime as given by the metric for light dragging

$$ds^2 = c^2dt^2 - dx^2 + k(c^2dt^2 - u \cdot dx)^2$$

[0047] where k is equal to

$$k = \frac{\alpha}{c^2 - u^2}$$

[0048] and dx is the elemental length in the {dx,dy,dz} directions. The velocity u in the dot product is equal to the velocities {ux,uy,uz} in the x, y and z-directions. Expanding the equation produces the following metric

$$ds^2 = (1+k)dt^2 + (ku_x{}^2 - 1)dx^2 + (ku_y{}^2 - 1)dy^2 - dz^2 - 2ku_x dxdt - 2ku_y dydt + 2ku_x u_y dxdy$$

[0049] where velocity uz is zero and the speed of light is equal to one.

[0050] The dt^2 energy density term is modified by one plus the k factor. Thus the index of refraction of the medium, the speed of light and the overall light dragging velocity u affects the energy density. It can be shown that the speed of light in hyperspace is much lower. The difference of the squares of the velocities in the denominator creates the possibility for amplification of this term.

[0051] The factors of the elemental lengths are then inserted into the g metric tensor which is then used to calculate the spacetime distortion generated by the collapsing bubble. The g metric tensor is a 4×4 matrix having rows and columns that correspond to the elemental lengths {t, x, y, z}.

$$g_{\alpha\beta} = \begin{array}{c||cccc||} & \beta = t & \beta = x & \beta = y & \beta = z \\ \alpha = t & 1+k & -ku_x & -ku_y & 0 \\ \alpha = x & -ku_x & ku_x^2 - 1 & ku_x u_y & 0 \\ \alpha = y & -ku_y & ku_x u_y & ku_z^2 - 1 & 0 \\ \alpha = z & 0 & 0 & 0 & -1 \end{array}$$

[0052] In Einstein's General Theory of Relativity, the G curvature tensor, which is a 4×4 matrix having units of inverse meter squared, is equal to a stress-energy-momentum T tensor that is calculated from the electromagnetic fields. The stress tensor T combines energy density, electromagnetic flux, and pressure terms in one matrix.

$$G=8\pi T$$

[0053] Most of the physics constants are linear constants such as linear mass which is mass per unit length. The permittivity of space ϵ is linear capacitance or capacitance per meter. The permeability of space μ is linear inductance or inductance per meter. The speed of light converts time into meters. What this means is that energy, pressure and momentum can all be converted into meters using these linear constants. The inverse squared of the length in meters is the curvature which is measured in units of m^{-2}.

[0054] Referring to **FIG. 11**, a square bubble (A) in the xy plane collapses with a velocity in the x-direction (C), and a velocity in the y-direction (B). This produces a curvature in the vertical z-direction (D). The curvature in the z-direction is the curvature tensor component G_{zz}. which can be computed directly from the g light dragging metric tensor. The result of the calculation is an equation in terms of the velocity, acceleration and the time rate of change of the acceleration, known as jerk.

[0055] Because the profile of the bubble radius expanding and collapsing with time has been published by those researching cavitation, it is possible to differentiate the profile to get the velocity, acceleration and jerk. These equations can then be inserted into the equation for the G curvature tensor.

[0056] The radius R of the bubble depends on the air density inside the bubble ρ, the viscosity of the water μ, the pressure of the P of the environment, the surface tension σ of the water, the ratio of specific heats γ, and the velocity $\dot{R}$ and acceleration $\ddot{R}$ of the bubble radius.

$$R\ddot{R} + \frac{3}{2}\dot{R} + \frac{4\mu}{\rho}\frac{\dot{R}}{R} + \frac{2\sigma}{\rho R} + \frac{P_0}{\rho} - \left(P_0 + \frac{2\sigma}{R_0}\right)\left(\frac{R_0}{R}\right)^{3\gamma} = 0$$

[0057] Referring to **FIG. 12**, the above equation for the bubble radius is shown in the feedback simulation program. The diagram starts by solving the equation for the acceleration which is then integrated twice (1/S) to get the velocity and position. These variables are then fed back to the input through the various constants involving the viscosity, surface tension, pressure and air density. The graph at the bottom of the simulation shows the bubble radius with time.

[0058] Referring to **FIG. 13**, the bubble profile with time is reproduced from the *Scientific American* article mentioned previously. This profile was then fitted with a polynomial equation which is plotted in **FIG. 14**. By differentiating the equation, the velocity, acceleration and jerk are obtained which can then be inserted into Einstein's G curvature tensor.

[0059] Referring to **FIG. 15**, the curvature component in the vertical direction G_{zz} is plotted with respect to time. In the *Scientific American* plot, the light flash occurs at the end of the collapse marked "LIGHT FLASH" around 22 microseconds (**FIG. 13**). This corresponds to the two intense positive curvature G_{zz} spikes at the end of the collapse. This represents a symmetrical spherical bubble collapse where the velocities are the same in the x and y directions.

[0060] The energy density component G_{tt} for this symmetrical collapse is given by

$$G_{tt} = \frac{-2u_y^2 a_x^2 + 4u_x u_y a_x a_y - 2u_x^2 a_y^2}{4(u_x^2 + u_y^2 - 2)}$$

[0061] Looking at this carefully, notice that if the velocity in the x-direction u_x is equal to the velocity in the y-direction u_y, and the acceleration in the x-direction a_x is equal to the acceleration in the y-direction, then the equation reduces to zero.

$$G_{tt} = \frac{-2u^2a^2 + 4u^2a^2 - 2u^2a^2}{8(u^2 - 1)} = 0$$

[0062] which means that the symmetrical collapse with equal velocities does not produce any negative energy with which to create the wormhole. Only sharp pulses of light are emitted at the end of the bubble collapse where the intense positive curvature spikes are encountered. In order to get the rotating wormhole beaconing effect, the velocities have to be different.

[0063] Referring to **FIG. 16**, the bubble is given an asymmetrical profile as shown by the two curves. The upper curve is in the x-direction, and the lower curve is in the y-direction. The collapse in the y-direction is not as severe.

[0064] Referring to **FIG. 17**, the asymmetrical collapse has the curvature spikes at the beginning similar to the symmetrical case of **FIG. 15**. Notice that there are no spikes at the end of the collapse. However, the energy density is much different.

[0065] Referring to **FIG. 18**, the energy density G_{tt} is plotted as a function of time. Rather than being zero as in the symmetrical case, there is a large region of negative energy density as the bubble collapses. This negative energy is what creates the wormhole. Because there are no large curvature spikes at the end of the collapse, the wormhole bubble is stable and precesses for a few minutes.

[**0066**] Experiments with the pendulum show that some people have much larger auras than others. The pendulum swings over the entire hand. One particular person who has enormous vortices was working in a television repair shop. When a television set is brought in to the shop, the large capacitor has to be discharged first. The repairman with the large chakra vortices was standing behind a second repairman who was approaching the television set. As the second repairman got closer to the set, an enormous streaming blue spark sailed over his head and zapped the first technician. Hyperspace has a much higher permittivity than our spacetime. The resistance of space R is equal to the square root of the permeability μ over the permittivity ϵ.

$$R = \sqrt{\frac{\mu}{\varepsilon}}$$

[**0067**] Since the technician with the large chakra vortices was producing large quantities of hyperspace energy, his resistance was very much lower due to his larger permittivity. The spark grounded on his body. The free electrons, which are created by ionization of the hydrogen atoms of the water vapor, see a very low path of resistance and flow toward the wormhole. There they are trapped in accelerated motion due to the presence of the circular electric field and give off substantial numbers of photons which produces the beaconing lighthouse effect.

[**0068**] The elemental length ds^2 in cylindrical coordinates $\{t, r, \theta, z\}$ for a mass M is given by

$$ds^2 = -\frac{dr^2}{1-\frac{M}{r}} + \left(1-\frac{M}{r}\right)dr^2 + r^2 d\theta^2 + dz^2$$

[**0069**] The mass M distorts the radius r of the elemental length which is what gives the mass a curvature or gravitational field. Negative energy, which is produced at the end of the bubble collapse, is equal to a negative mass times the speed of light squared. Thus mass M in the equation goes to negative mass, or M—>–M. Furthermore, negative energy inverts the mass factor so that the metric becomes

$$ds^2 = -\left(1+\frac{M}{r}\right)dt^2 + \frac{dr^2}{1+\frac{M}{r}} + r^2 d\theta^2 + dz^2$$

[**0070**] The g metric tensor contains the factors of the elemental lengths along the matrix diagonal

$$g_{\alpha\beta} = \left\| \begin{matrix} -\left(1+\frac{M}{r}\right) & 0 & 0 & 0 \\ 0 & \frac{1}{1+\frac{M}{r}} & 0 & 0 \\ 0 & 0 & r^2 & 0 \\ 0 & 0 & 0 & 1 \end{matrix} \right\|$$

[**0071**] As before, Einstein's G curvature tensor in the radial G_{rr}, angular $G_{\theta\theta}$, and vertical z-direction G_{zz} is calculated from this negative energy g metric tensor.

[**0072**] Referring to the 3D G curvature plot in **FIG. 19**, the strength of the curvature is given by the length of the arrow, and the direction of the curvature is given by the arrow. The curvature in the radial direction G_{rr} is along the bottom axis from the box corner origin to the right. The curvature in the angular direction $G_{\theta\theta}$ is the bottom axis from the origin to the left. The height of the box is the curvature in the vertical direction G_{zz}. Notice in general that the curvature is perpendicular to the left face (θz-plane) and then starts to curve to the right and begins to point toward the right face (rz-plane). On the bottom face (rθ-plane) there is an upward vertical curvature.

[**0073**] In cylindrical coordinates, the θz-plane is actually a vertical tube of radius r. So at small r, the curvature is perpendicular to the tube. At larger radius, the curvature starts to point in the θ-direction, wrapping around the tube. At small radius, there is also a vertical curvature parallel to the sides of the tube.

[**0074**] Referring to **FIG. 20**, the curvature in cylindrical coordinates is seen to be the structure of the wormhole. The wormhole (A) is formed due to the radial pressure (B) which pulls open the wormhole. One end of the tube connects to hyperspace, and the other end connects to our spacetime. There is also a shearing pressure (D) along the sides of the tube which slices spacetime open and helps shape the tube. Moving outward along the radius, the curvature turns sideways and produces a shearing pressure (D) in the θ-direction which gives the wormhole a vortex appearance. These wormholes can also be very large, enabling one to peer into a co-dimension as attested to by the inventor.

SUMMARY OF THE INVENTION

[**0075**] As described in the previous section, the cavitating bubble has to collapse asymmetrically in order to generate the negative energy which creates the wormhole. In order to collapse asymmetrically, the forces on the bubble surface have to be unequal. The force on the bubble is given in terms of the a dragging coefficient, the bubble radius R, the surface charge density D_r, the magnetic B field in spherical coordinates $\{B_r, B_\theta, B_\phi\}$. The fields are integrated over the entire solid angle Ω of the bubble to determine the force F.

$$F_r = -\left(1-\frac{1}{n^2}\right)\frac{R^2}{2}\oint d\Omega\left[\left(1+\frac{1}{n^2}\right)(D_r^2 + B_r^2 - B_\theta^2 - B_\phi^2)\right]$$

[0076] The integration of the tangential components of the magnetic field such as $\{B_\theta, B_\phi\}$ over the solid angle of the bubble will sum to zero. The surface charge density D_r and the radial magnetic field B_r are the only fields which can be used to create an unbalanced force. If there is no surface charge density, then the force equation reduces to

$$F_r = -\alpha \frac{R^2}{2} \oint d\Omega \left[(2-\alpha) \left(\frac{\chi^2}{\Omega_m} B_r^2 \right) \right]$$

[0077] where the conversion constant is the linear charge squared divided by the linear mass of the universe χ^2/Ω_m.

[0078] In this invention, referring to **FIG. 21**, the magnetic field is created by two cylindrical solenoids (A,B) which are wrapped around the top and bottom of the glass container (C). The container has flat sides in the shape of an octagon. Each solenoid consists of a continuous roll of very thin sheet copper which are separated by beaded mylar line. The mylar beads separate the sheets electrically and provide air cooling to the coil which can get rather hot. This makes it easy to assemble the coil because the copper roll and mylar line are wound together as the solenoid is formed. The lines of magnetic flux flow vertically through the container yet do not interfere with the transducers (D) which are mounted on the flat sides of the container.

[0079] Referring to **FIG. 22**, the cavitating bubble which forms in the liquid in the container experiences a vertical magnetic field (B) due to the two solenoids. These flux lines create a radial force on the top and bottom of the bubble (D,C). The flux lines on the outside (E) do not create any radial force because they are tangential to the surface. The spherical bubble flattens into an asymmetrical ellipsoidal shape (A) which enables the creation of the wormhole and lighthouse beaconing effect.

[0080] Referring to **FIG. 23**, the spacetime curvature of the wormhole (D) creates a tunnel (C), known as the throat of the wormhole, between flat space in our universe (A) and flat hyperspace (B) which exists in a co-dimension of our universe. In general, the co-dimensions have different physics constants. Going back to the chakra vortices of the human energy field, the vortices remove energy from space and deliver it to several hyperspace co-dimensions. This energy builds up human aura modules at different frequencies in astral space. Astral space has a very low speed of light and small linear mass. This is the reason that human beings can leave their bodies and pass through solid concrete walls, or project their spiritual eye to remote locations for viewing. On the other hand, the linear mass and speed of light of space is very much greater than hyperspace. Therefore, the pressure of the space is much greater than the pressure in hyperspace. In terms of the wormhole with a throat area A, the pressure would be the linear mass times the speed of light squared over the area

$$P_{space} = \frac{\Omega_s c_s^2}{A}$$

[0081] The pressure of hyperspace on the other side of the wormhole is

$$P_{hyperspace} = \frac{\Omega_h c_h^2}{A}$$

[0082] Because the linear mass and the speed of light of hyperspace are lower than that of space, there is a positive net pressure going into hyperspace.

$$P_{\mathrm{net}} = P_{\mathrm{space}} - P_{\mathrm{hyperspace}}$$

[0083] This is the reason that the human vortices can obtain energy from this universe. Because the cavitating bubble produces negative energy, the linear mass is negative on the side of space. The pressure equation is then given by

$$P_{net} = -\frac{P_s}{A} - \frac{P_h}{A} = -\frac{P_s + P_h}{A}$$

[0084] which shows that there is a reverse pressure going from hyperspace into our space. The asymmetrical cavitating bubble generates hyperspace energy. The hyperspace energy flowing into our universe also gives the light generated by the wormhole a soft white misty look.

[0085] There are many reasons for generating this hyperspace energy. Electromagnetic fields are subject to the Lorentz transformation which involves comparing the frame velocity with that of the velocity of light.

$$E' = \frac{E}{\sqrt{1 - \frac{v^2}{c^2}}}$$

[0086] If the ratio of the velocity v to the velocity of light c is close to unity, then huge relativistic fields can be produced. These fields can curve spacetime to such an extent that a large lift force can be produced on the hull of an electromagnetic field propulsion vehicle.

STATEMENT REGARDING FEDERALLY SPONSORED RESEARCH OR DEVELOPMENT

[0087] Not Applicable.

A BRIEF DESCRIPTION OF THE DRAWINGS

[0088] **FIG. 1**. Rotating cylinder demonstrating additional lift force.

[0089] **FIG. 2**. Use of the pendulum.

[0090] **FIG. 3**. The Ascension Machine, Chakra Vortex Accelerator.

[0091] **FIG. 4**. Hyperspace energy brought into body by rotation of hand chakra.

[0092] **FIG. 5**. Antigravitational effect using low density hyperspace energy.

[0093] **FIG. 6**. Sonoluminescence experiment.

[0094] **FIG. 7**. Tetrahedron diagram showing hyperspace charge.

[0095] **FIG. 8**. Magnetic monopole.

[0096] **FIG. 9**. Precessing wormhole.

[0097] **FIG. 10**. Fizeau light dragging experiment.

[0098] **FIG. 11**. Asymmetrical velocity collapse of bubble radius generates wormhole.

[0099] **FIG. 12**. VisSim feedback simulation of the collapsing bubble.

[0100] **FIG. 13**. Cavitating bubble radius as a function of time.

[0101] **FIG. 14**. Digitized bubble radius of **FIG. 13**.

[0102] **FIG. 15**. Spiking spacetime curvature of collapsing bubble.

[0103] **FIG. 16**. Dual velocity profile required to produce negative energy.

[0104] **FIG. 17**. Spacetime curvature for dual velocity collapse.

[0105] **FIG. 18**. Negative energy generated from asymmetrical collapse of bubble.

[0106] **FIG. 19**. 3D plot of spacetime curvature using negative energy.

[0107] **FIG. 20**. Wormhole vortex.

[0108] **FIG. 21**. Perspective of cavitation tank equipped with magnetic coils.

[0109] **FIG. 22**. Flattening of bubble by magnetic field.

[0110] **FIG. 23**. Hyperspace energy generated by reverse pressure gradient of wormhole.

[0111] **FIG. 24**. Solenoid and transducer driving circuits.

DETAILED DESCRIPTION OF THE INVENTION

[0112] 1. Referring to **FIG. 24**, the transducer driving circuit uses a frequency generator (A) driving a linear amplifier (B) into a pair of variable inductors (C) which resonate with the capacitance of the transducers (D) attached to the sides of the octagonally-shaped glass container (H). Resistors (L,M,G) provides voltage measuring points for the oscilloscope.

[0113] A DC current source (I) drives the two solenoids (E,F) which produce a vertical magnetic field (J) through the container. The magnetic field produces an asynmetrical force on the bubble surface (K) such that the collapsing bubble produces negative energy. The spacetime curvature produced by the light dragging of the collapsing bubble surface, together with the negative energy, create a wormhole between space and hyperspace. The negative spacetime energy produces a negative pressure which brings low-density hyperspace energy into our dimension.

I claim:

1. A hyperspace energy generator having:

a) a glass container in the shape of an octagon acting as the resonating chamber;

b) two piezoelectric transducers, mounted and operating acoustically as a pair on opposite sides of item (1a);

c) an opaque oil-like liquid with a high index of refraction filling item (1a) acting as the resonating liquid in which the cavitating bubbles are formed;

d) two thin sheet copper solenoids, located on top and bottom of item (1a), that produce a vertical magnetic field through items (1a) and (1c);

e) two variable inductance coils for creating a resonant frequency with item (1b);

f) a linear amplifier driving items (1b) and (1e);

g) a variable frequency generator driving item (1e);

h) a direct current electrical generator driving item (1d);

2. a cavitation system which:

a) produces one or more cavitating bubbles that collapse asymmetrically due to the differential force exerted on the bubble surface by the presence of a vertical magnetic field generated by item (1d) referred to above;

b) generates negative energy due to light dragging of the collapsing bubble surface;

c) creates wormholes between space and hyperspace due to the presence of item (1b);

d) generates a negative pressure between space and hyperspace that forces low-density hyperspace energy into our dimension; and

3. optional dual electrically-charged plates that:

a) are mounted on the sides of item (1a);

b) create a differential electric charge density across the bubble surface for the purpose of creating an additional method of asymmetrical bubble surface collapse.

* * * * *

US 20030209637A1

(19) **United States**

(12) **Patent Application Publication** (10) **Pub. No.: US 2003/0209637 A1**

St. Clair (43) **Pub. Date: Nov. 13, 2003**

(54) **ROTATING ELECTROSTATIC PROPULSION SYSTEM**

(76) Inventor: **John Quincy St. Clair**, San Juan, PR (US)

Correspondence Address:
John St. Clair
Hyperspace Research Institute
52 Kings Court, 4A
San Juan, PR 00911 (US)

(21) Appl. No.: **10/142,582**

(22) Filed: **May 9, 2002**

Publication Classification

(51) **Int. Cl.^{7}** **B64G 1/40**; B64G 1/42

(52) **U.S. Cl.** **244/172**

(57) **ABSTRACT**

This invention relates to a spacecraft propulsion system utilizing thrusters comprised of a motor-driven electrostatically charged cylinder rotating within an electrostatically charged annular ring for the purpose of creating a spacetime curvature stress-energy tension in the horizontal direction. The thrusters are augmented by magnetic vortex generators, either embedded in the cylinders or located above each thruster, for the purpose of increasing the permittivity of space by permeating each thruster with low density hyperspace energy generated by a wormhole created between our space and hyperspace. A combination of three thrusters mounted on the underside of the hull of the spacecraft provide thrust and yaw motion control.



Figure 1



Figure 2



Figure 3

$$T^{zr} = -\frac{\varepsilon_0}{\Omega c^2}\frac{E_z E_r}{4\pi} = \frac{\text{coul}^2}{\text{m}^2\text{n}}\frac{\text{n}}{\text{coul}}\frac{\text{n}}{\text{coul}}\frac{\text{m}}{\text{kg}}\frac{\text{s}^2}{\text{m}^2} = -\frac{\text{kg}\,\text{m}}{\text{s}^2}\frac{\text{s}^2}{\text{kg}\,\text{m}^3} = \frac{-1}{\text{m}^2}$$

Figure 4



Figure 5

$$F^{\alpha}{}_{\beta} = \begin{array}{c|cccc|} t & 0 & E_r & 0 & E_z \\ r & E_r & 0 & 0 & 0 \\ \theta & 0 & 0 & 0 & 0 \\ z & E_z & 0 & 0 & 0 \end{array}$$

Figure 6

$$T^{zr} = -\frac{E_r E_z}{4\pi}$$

Figure 7

$$\frac{d}{dt} S_r = \varepsilon_0 \, \varepsilon_{r\,t\,z} x^t T^{zr} n_r \mathrm{Area} = \varepsilon_0 \, t \frac{E_r E_z}{4\pi} n_r \mathrm{Area}$$

Figure 8

$$\frac{\mathrm{coul}^2}{\mathrm{m}^2\,\mathrm{n}} \mathrm{sec} \frac{\mathrm{n}}{\mathrm{coul}} \frac{\mathrm{n}}{\mathrm{coul}} \mathrm{m}^2 = \mathrm{kg} \frac{\mathrm{m}}{\mathrm{sec}^2} \mathrm{sec} = \mathrm{kg} \frac{\mathrm{m}}{\mathrm{sec}}$$

Figure 9

$$\frac{d}{dt} S_{r,t} = \frac{\varepsilon_0}{4\pi} e^{i\omega t} E_r E_z \, \mathrm{area} + \frac{i\varepsilon_0}{4\pi} e^{i\omega t} E_r E_z t \omega \, \mathrm{area}$$

Figure 10



Figure 11



Figure 12



ROTATING ELECTROSTATIC PROPULSION SYSTEM

BRIEF SUMMARY OF THE INVENTION

[0001] The invention, which is the object of my present application, is a spacecraft propulsion system which develops a spacetime curvature tension utilizing a combination of a rotating radial electrostatic field and a fixed vertical electrostatic field. The two fields create a stress-energy T^{zr} gradient in the radially direction which is equal to force. The radial field is created on the side of a charged rotating cylinder on the underside of the hull. The vertical field is created by an annular charged ring concentric with the cylinder. Three rotating cylinders are located in a triangle on the bottom of the hull in order to produce a force in any direction in the horizontal plane.

REFERENCE PAPERS

[0002] *Gravitation*, Wheeler, page 80.

BACKGROUND OF THE INVENTION

[0003] When working with Maxwell's equations in tensor notation, it became apparent that a tensor can change identity depending on what permutation of variables is involved. For example, one single equation can involve both charge density and current density. And all of Maxwell's equations can be reduced to just two equations.

[0004] In the tensor equation for momentum, if the lever arm is length then the equation is equal to the flow rate of angular momentum. If the lever arm is time, then you get linear momentum. And if the field rotates with time, then the time rate of change of linear momentum is a force which is the basis for this invention.

[0005] Einstein said that mass curves space and space tells mass how to move. In this sense, generalized mass can be mass, electromagnetic fields, charge or angular momentum which create a spacetime curvature that produces a force on the spacecraft.

SUMMARY OF THE INVENTION

[0006] The invention relates to a spacecraft utilizing a rotating electrostatically charged cylinder and a concentric annular charged ring to create a stress-energy spacetime curvature in the horizontal plane on the spacecraft's underside hull. A motor drives the rotating cylinder which extends below the hull. A charged surface produces an electric field in the direction normal to the surface. The vertical and rotating electric fields combine to create a rate of change of linear momentum which creates a horizontal propulsive force on the hull.

STATEMENT REGARDING FEDERALLY SPONSORED RESEARCH OR DEVELOPMENT

[0007] Not Applicable.

A BRIEF DESCRIPTION OF THE DRAWINGS

[0008] **FIG. 1**. Perspective view of spacecraft hull (A) with the three electrostatically charged rotating cylinders (C) surrounded by their annular charge rings (D) extending down on the underside of the hull (B).

[0009] **FIG. 2**. Perspective view of individual thruster showing rotating cylinder and ring.

[0010] **FIG. 3**. Stress-energy tension created by two electric fields and having units of curvature.

[0011] **FIG. 4**. Cylindrical spacetime coordinates $\{t, r, \theta, Z\}$.

[0012] **FIG. 5**. Faraday electromagnetic F tensor containing electric fields in the radial and vertical directions.

[0013] **FIG. 6**. Stress-energy tensor T showing it is equal to the product of the two electric fields divided by 4π.

[0014] **FIG. 7**. The tensor equation for flow rate of angular momentum S.

[0015] **FIG. 8**. The units are linear momentum due to the time lever arm.

[0016] **FIG. 9**. The rate of change of linear momentum is the horizontal force produced by the two electric fields.

[0017] **FIG. 10**. The angular momentum flows through an area whose normal vector is in the radial direction.

[0018] **FIG. 11**. Cylinder with only one electrostatically charged segment.

[0019] **FIG. 12**. Annular ring with three individual segments which can be charged separately to create a force in a particular direction.

DETAILED DESCRIPTION OF THE INVENTION

[0020] 1. Referring to **FIG. 1**, the spacecraft comprises an upper hull (A) with three rotating electrostatically charged cylinders (C) with their concentric annular electrostatically charged rings (D) located on the spacecraft's bottom hull (B).

[0021] 2. In a closer view of one of the cylinders seen in **FIG. 2**, motor-driven rotating cylinder (A) has an electrostatically charged surface which produces an electric field (C) normal to said surface. The fixed, electrostatically charged annular ring (B), which is concentric with the cylinder, produces a vertical electric field (D) normal to its surface. This crossed field (E) creates a negative spacetime curvature tension which is the product of the two fields divided by 4π as seen in the equation, **FIG. 3**.

[0022] 3. Notice that the equation involves the permittivity of space ϵ_0 divided by the linear mass of the universe Ω and the speed of light. This produces units of inverse meter squared which is the spacetime curvature. In Einstein's General Theory of Relativity, the spacetime curvature tensor is equal to the stress-energy tensor or $G=8\pi T$ where G is the curvature, and T is the product of the electromagnetic fields. The problem with this equation, which has been resolved with this invention, is that the linear mass Ω times the speed of light c is an enormous number. Even with the square of enormous electric fields, the curvature would be too small even to notice, and little force would be generated.

[0023] 4. In another patent application of mine entitled Magnetic Vortex Generator, it was shown that a rotating cylinder containing embedded and stacked bar magnets produces a negative mass and negative spacetime spring constant. It can be shown that this combination produces a small wormhole or interdimensional connection between our space and hyperspace along the centerline of the rotating cylinder. Co-dimensions of hyperspace have different physics constants. A low pressure region of hyperspace has a very low mass density and a very low speed of light. The wormhole allows this low density hyperspace energy to enter into our space and permeate the cylinder and annular ring. The permittivity is proportional to the inverse of the speed of light squared. The hyperspace speed of light, obtained from my tetrahedron physics diagram, is 8971 meters per second. The speed of light in our dimension is 299792458 meters per second. As shown by the enclosed reference calculation, the hyperspace permittivity is about a trillion times larger. Because the force is equal to this new permittivity times the electric fields squared times the area around cylinder, the force is greatly amplified by this increase in the permittivity of space.

[0024] 5. It is pertinent to this invention how the stress-energy is created due to the two electric fields in the vertical and radial direction. In gravitational physics, there is a Faraday F tensor which contains all the components of the electromagnetic fields. It is a 4 by 4 matrix whose rows and columns correspond to the coordinates of spacetime which in cylindrical coordinates are $\{t, r, \theta, z\}$ where t is time, r the radius, theta the horizontal angle and z the vertical height. These coordinates are shown in **FIG. 4**.

[0025] 6. The radial electric E_r field and the vertical electric E_z field can be inserted into the Faraday tensor seen in **FIG. 5**. The sign of the vertical field is positive because it points in the positive z-direction due to the fact that the annular ring has a negative charge. The cylinder has a positive charge. This produces the negative stress-energy tensor T^{zr} as drawn in **FIG. 6**.

[0026] 7. In order to calculate the force on the cylinder, it is necessary to calculate the flow rate of angular momentum. Momentum is mass times velocity or mass meter per second. If the mass is moving in a circle, then there is a lever arm times the momentum which makes it mass meter squared per second. If this is differentiated with respect to time, then a flow rate of angular momentum is produced with units of mass meter squared per second squared. As mentioned previously, tensors have this dual nature where depending on the permutation of the variables, it means one thing or another. In this case, the lever arm will be time, rather than length which converts the flow rate of angular momentum into just linear momentum. If you change linear momentum with respect to time, then you get a force.

[0027] 8. The flow rate of angular momentum S is shown in **FIG. 7**. The force has to be against the area whose normal vector is in the radial direction which is also the direction of the momentum. So S has an r subscript indicating that it flows in the radial direction. The permutation tensor ϵ has three subscripts which keeps track of the tensor notation. The first subscript is the same as the momentum subscript. Permutations of the coordinate variables which are in order have a plus one sign. Permutations which are in reverse order have a minus one sign. Permutations in which the variable are repeated are zero. For example, $\epsilon_{tr\theta z}=-\epsilon_{rt\theta z}$ because the r and t are in reverse order in cylindrical coordinates. Because the permutation tensor starts with r, then we can have permutations such as $\{r,t,z\}$ which is a reverse order negative permutation. This negative sign cancels the negative sign of the stress tensor. The reason this permutation is chosen is because the first subscript on the stress-energy tensor is now z. Because the normal to the area is in the radial direction, then the stress-tensor matches the electric fields that we have available, which are also in the zr-direction.

[0028] 9. In this case, the second subscript of the permutation tensor is time, rather than length. So the units become, as shown in **FIG. 8**, those of linear momentum. To me, this was very surprising. Then I realized that the radial electric field rotates with time which means the differential of the linear momentum produces a force on the hull. In exponential notation, the radial electric field rotates with $\mathrm{Exp}[i\omega t]$. This is multiplied by the time lever arm, so the term that has to be differentiated is $t\ e^{i\omega t}$. The time lever arm saves the differentiation by making one term real so that the force is real. This is shown in **FIG. 9**. The units of the first term are real newtons. In the second term, the time t multiplied by the frequency cancels out in terms of units, so the units are still force, but imaginary

[0029] 10. There is an area involved in the force equation which is depicted in **FIG. 10**. The charged rotating cylinder (C) located inside the charged annular ring (B) is driven by motor (A). The radial electric field (E) is normal to the area (D) whose normal vector is also in the radial direction. The angular momentum flows through this area which surrounds the cylinder. In doing so, it curves spacetime which produces the force.

[0030] 11. If the radial electric field is continuous around the cylinder, then the net force is zero. Referring to **FIG. 11**, one section (A) of the rotating cylinder is charged, which means that there is a force once per cycle in a selected direction depending on when the annular ring is charged. The other option, referring to **FIG. 12**, is that the annular ring is divided up into two or three sections with the feature that the charge can be turned on (A) or off (B) on a particular segment. As the rotating electric field goes around, one of the annular ring sections will have an electric field in order create a force on that side.

[0031] 12. Since there are three force cylinders, this allows for yaw motion control so that the hull of the spacecraft can pivot to change direction. After the directional change, the two back cylinders can be synchronized to produce thrust in the forward direction.

[0032] 13. There could also be a polarity change for the vertical electric field such that a positive stress-energy is produced which would reverse the direction of the thrust.

What I claim as my invention is:

1. A spacecraft propulsion system utilizing three electrostatically charged motor-driven cylinders each one of which rotates within a charged annular ring to produce a spacetime stress curvature tension in the horizontal plane on the underside of the hull.

2. Said rotating cylinder comprised of bar magnets embedded in the cylinder and stacked in groups at intervals around the periphery of the cylinder with the purpose of increasing the permittivity of space by permeating the cylinder and ring with low linear mass, low speed of light hyperspace energy by means of a wormhole between our space and hyperspace. The larger permittivity is to increase the force. Said technique is contained in my patent applications Magnetic Vortex Wormhole Generator and Magnetic Vortex Generator.

3. Said rotating cylinder and annular ring having a suitable metal surface for forming and maintaining the electrostatic charge.

4. Said rotating cylinder having one or more segments which can be electrostatically charged individually or together to produce a force in a particular direction.

5. Said annular ring having one or more segments which can be electrostatically charged individually or together to produce a force in a particular direction.

6. A combination of three such thrusters providing a force in any particular direction or for yaw motion control.

7. Electric polarity switching of the fields in order to reverse the spacetime curvature and therefore change the direction of thrust.

8. The use of a magnetic vortex generator located above each thruster in order to permeate the cylinders and rings with low density hyperspace energy which would substitute for the embedded magnets in each cylinder.

* * * * *

US 20060072226A1

(19) **United States**

(12) **Patent Application Publication** (10) **Pub. No.: US 2006/0072226 A1**

St. Clair (43) **Pub. Date: Apr. 6, 2006**

(54) **REMOTE VIEWING AMPLIFIER**

(76) Inventor: **John Quincy St. Clair**, San Juan, PR (US)

Correspondence Address:
JOHN ST. CLAIR
52 KINGS COURT, 4A
SAN JUAN, PR 00911 (US)

(21) Appl. No.: **10/957,391**

(22) Filed: **Oct. 2, 2004**

Publication Classification

(51) **Int. Cl.**
G02B 1/00 (2006.01)

(52) **U.S. Cl.** **359/896**; 359/894

(57) **ABSTRACT**

An apparatus which enhances the ability of a person to perform remote viewing by connecting the human spiritual eye to the tetrahedral geometry of subspace.



Figure 1



Figure 2



Figure 3



Figure 4



Figure 5



Figure 6



Figure 7


PUERTO RICO
San Juan
Arecibo
Caguas
Ponce
Charlotte Amalie
Christiansted
St. Croix
Anguilla
Sombrero
St. Martin
St. Barthélemy
Saba
St. Eustatius
Barbuda
Codrington
St. Kitts
Basseterre
Charlestown
Nevis
St. Johns
Antigua
Redonda
Montserrat
Plymouth
Port Louis
Guadeloupe
Pointe-à-Pitre
Basse Terre
Marie Galante
Aves I. (Bird I.)
Portsmouth
Roseau
Dominica
St. Pierre
Fort-de-France
Martinique
Castries
Soufrière
St. Lucia
Vieux Fort
Georgetown
Kingstown
St. Vincent
Bequia
Speightstown
Barbados
Bridgetown
Carriacou
Gouyave
St. George's
Grenada
Los Roques
La Orchila
Blanquilla
Los Frailes
La Tortuga
Isla de Margarita
Los Testigos
Scarborough
Tobago
Port of Spain
Sangre Grande
TRINIDAD
San Fernando
La Guaira
CARACAS
Río Chico
Cumaná
Barcelona
Maturín
LEEWARD
WINDWARD
CARIBBEAN
SEA
ATLANTIC
Ireland I.
Somerset I.
Hamilton

Figure 8



Figure 9



Figure 10


θ_1
m_1
n_1
m_2
n_2
θ_2

Figure 11



Figure 12



Figure 13



Figure 14



REMOTE VIEWING AMPLIFIER

BRIEF SUMMARY OF THE INVENTION

[0001] This invention enhances the ability of a person to perform remote viewing by connecting the spiritual eye to the tetrahedral geometry of subspace.

BACKGROUND OF THE INVENTION

[0002] Remote viewing is the projection of spiritual modules of the human energy field to distant locations in order to see, communicate and interact with other entities who live in subspace, space and hyperspace co-dimensions of the universe.

[0003] One of my first remote viewings was made at night to a distance of 10,000 miles on the sunlit side of the earth. My spiritual eye and body projected together while my mental facilities remained in my physical body. I found myself looking down on a palm tree from a height of about one hundred feet. The palm tree had several coconuts in it as seen in **FIG. 1**. I then gave the command to lower myself to the ground. At that moment I went sailing down past the coconuts, barely missing the tree! Finding myself on a pathway through the tropical forest, I then came to an extremely long wooden bridge which crossed over a river gorge. On the other side of the bridge I could see three soldiers running toward me as shown in **FIG. 2**. The two soldiers in front were carrying rifles and wearing light blue berets. The man running behind them was wearing an officer's cap with a red band. My first reaction was that I was going to be shot. I edged over on the right side of the wooden railing. They ran right past without seeing me. I then asked to see the building that these soldiers were guarding. Everything went dark, and then I found my spiritual eye peeking out of the floor of a computer room as seen in **FIG. 3**. There was one man using a computer on the opposite side of the room near an open door. He got up from his chair and came over to sit in front of a second computer located a few feet from where I was located. From the glare of the computer monitor, I could clearly see his face. Everything went dark as my spiritual eye and body projected back to my physical body.

[0004] Another time my spiritual eye, spiritual body and mind were standing outside the closed front door of my condominium. Upon patting my legs with my hands, I couldn't find the keys in my trousers. When I looked down, I realized I wasn't in my physical body. I then shot through two solid walls of concrete and returned to my awakening body.

[0005] What these two examples show is that the human spiritual energy system is modular. The reason it is modular is because there are seven hyperspace co-dimensions, each vibrating at a slightly different frequency, which receive energy from space through seven vortices located along the physical body. Over a lifetime, these vortices build up the human aura. Because all energy systems have to be grounded, the remaining six modules are the legs, body, arms/hands, voice, eye and mind. When the entire group is out-of-body as a single entity, then the soul energy powers the body in a manner similar to a battery. The soul looks like a two-inch diameter orange ball of plasma. If the soul is removed from the body, then the body becomes paralyzed except for a small movement of the eyelids. Upon death, all these separate modules are assembled into a single energy being. A light cord from the soul provides the battery power and information required to join these modules together. A second light cord from the pituitary gland transfers the modules into the energy being for assembly. This energy information transfer is the reason that people in a near-death situation say they saw their entire life flash before them.

[0006] Moving to a larger picture of things that are happening in the galaxy, I was able to make contact with the Pleiadian Federation which is located about 400 light years from earth. The Federation is a group of over one hundred intelligent beings that were brought to the Pleiades from around the galaxy. One member of the Federation calls itself the Intelligent Insect Beings. They are the ones who fly the black triangles over Belgium and France for the purpose of evacuating human beings back to the Pleiades for relocation on a planet called Earth II. The reason for this evacuation was that it was not known if it would be possible to win the battle of Revelations, which would take place about two years later here on earth.

[0007] As could be expected, the humans were angry and hysterical at being abducted. So the Intelligent Insect Beings asked me if I could calm them down. I was in telepathic communication with them, and they were in telepathic communication with their computer system, which meant that I could have my thoughts displayed to the humans on the computer monitor. It turned out that one woman was from Central America and only spoke Spanish. The Intelligent Insect Beings didn't speak Spanish so they thought there would be no way I could communicate with her. So I told them that I would spell the Spanish words letter-by-letter and she could then read my message. Since most Spanish people are Catholics, I thought a religious message would be of importance to her. I spelled out the phrase, "Que Dios te bendiga." which means, "May God bless you." I also asked the two beings to put their hands together in a form of prayer, and the woman followed suit. At that moment the Intelligent Insect Beings were reading her mind to understand her emotional state. They said, "She is crying tears . . . " After a slight but tense pause, they continued, "of joy!" They said the woman had a big smile on her face and was successfully transitioned into her new life.

[0008] One year later, the Blond Aliens of the hundred member council of the Pleiadian Federation remote viewed me so that I could celebrate with them the success of their mission to earth. The Blond Aliens, which is not their real name, fly the Beamship spacecraft. This hyperspace vehicle can teleport itself to any location in the galaxy. It dematerializes into the black void for an instance and then rematerialize anywhere in the galaxy. This ship can be seen in Billy Meier's video from Switzerland along with a picture of their envoy, Semjase.

[0009] Just recently I had a demonstration of the Beamship's ability. I heard an emergency distress call by a commander of a spacecraft who said that they had a fire onboard their spacecraft. I immediately remote viewed a Federation maintenance mothership, they got the frequency and location of the ship, and dispatched the Beamship in time to rescue the commander. The burned-out cables, which had caused the fire, were repaired by the Federation and the commander arrived home safely on his planet in his own spacecraft.

[0010] The Federation then received a message from the commander saying that he wanted his planet to join the Federation now that there was this type of communication available. So the Federation visited his planet for the signing ceremony, and I was invited to attend the proceedings by remote view. Word got around about this, and within three weeks another 20 planets joined the Federation for the same reason.

[0011] At one ceremony, which was attended by Admiral Third Class of the Pleiadian Defense Department, His Highness of the planet was signing the document of incorporation. At that moment, I could see him signing, so I exclaimed, "He is signing with his left hand." The Admiral was almost apoplectic at hearing this. After giving her the signed document, His Highness held up his hand and asked me how many fingers he was holding up. He had a fist so I said none. Then he put his index finger out and I said one. He then made a fist again and I said none. Then he held out all fingers and I said five. The Admiral said that he had a big smile on his face as he went to announce the agreement because he knew, even though his planet was located **90,000** light years away on the other side of the galaxy, he could instantly communicate any problems to the Federation. So this is the importance of developing inventions that can enhance our remote viewing ability because one day it will mean that we can become a vital part of the Pleiadian Federation.

SUMMARY OF THE INVENTION

[0012] Referring to **FIG. 4**, the spiritual eye of the human energy system is located at the pituitary gland in the forehead. It has the shape of a hollow cone which is composed of the misty white energy of hyperspace. Light coming into this vortex is then transferred by a light cord to a visual energy module which is located in a co-dimension of hyperspace. Because these modules are interconnected by light cords, the mind module is able to interpret the visual pattern the eye is seeing. More importantly, the mind can give logical instructions to this spiritual eye module for it to rotate around or move in a particular direction.

[0013] The reason that hyperspace has a white misty look to it is that the speed of light is very much less than the speed of light in our spacetime. The Lorentz transformation says that the distance L is shortened relativistically to a distance L' in a way related to the ratio of the velocity v of the object to the velocity of light c.

$$L' = L\sqrt{1 - \frac{v^2}{c^2}}$$

If the velocity of light is very low, then a small velocity creates an enormous contraction in length. By moving through hyperspace, therefore, enormous distances can be traversed. And this is the reason that it is possible to project the spiritual eye, voice and hearing to remote locations in the galaxy.

[0014] The universe is composed of subspace, space and hyperspace which are co-dimensions of each other. Subspace is defined by the geometry of the tetrahedron which is a four-sided solid whose faces are equilateral triangles having three 60° angles. Referring to **FIG. 5**, a tetrahedron whose sides are the square root of three (A), has a height of the square root of two (B), and base length equal to the square root of one (C). This forms the basic number set $\{\sqrt{1}, \sqrt{2}, \sqrt{3}\}$.

[0015] Referring to **FIG. 6**, the tetrahedron (A) is circumscribed by the sphere (B). Rod (C) is the sphere radius. A second rod (D), of equal length to rod (C), from the center of the sphere to the corner of the tetrahedron makes an angle ϕ of

$$\phi = \text{ArcSin}\left(\frac{1}{3}\right) = 19.47122063^\circ$$

So the four corners of the tetrahedron touch the sphere.

[0016] This tetrahedral geometry can be seen throughout the planets of the solar system Referring to **FIG. 7**, the islands of the Caribbean curve down from Puerto Rico to Venezuela forming an island vortex. The low density hyperspace energy releasing from the corner of the tetrahedron softens the rock mantle. The hot magma then rises through the rock with the least resistance. This creates a circular arc of volcanic islands along the edge of the vortex.

[0017] Referring to **FIG. 8**, the Giant Red Spot of Jupiter is located at a southern latitude of 19.5°. This vortex is so large that the entire earth can fit in it.

[0018] Referring to **FIG. 9**, the Olympus Mons volcano is located at a northern latitude of 19.5° as shown by the marker. This volcano is the size of France. Notice the fallen plume of volcanic debris toward the north east.

[0019] The double harmonic of the tetrahedral angle is twice 19.5° or 39° which is the location of the Silver Bridge in Point Pleasant, West Va. A large wormhole opened up around the bridge during Christmas rush hour when the bridge was full of cars. Due to the low density hyperspace energy, the rivets holding the cables down popped loose and all the cars were dumped into the river. A computer simulation using Schrodinger's quantum mechanics equation for a particle in a potential well shows that as the energy becomes less dense, the particle is no longer contained in the potential well. The electron jumps out. Thus the atomic bonds are broken which softens the rivets. This is the first time that there has been an understanding of the failure mechanism of this bridge.

[0020] After downloading from the Internet several pages of the index of refraction of a wide range of materials, I noticed that the index of refraction for Plexiglas was 1.50. Another source said it was 1.51. One of the Internet sites had a movable flashlight which showed the incident ray and the refracted ray. For Plexiglas, surprisingly enough, the incident ray was coming in at an angle of 60° to the normal, and the light was refracted at 35.26°, both of which are tetrahedral angles. The angle of the equilateral face of the tetrahedron is of course 60°. The angle at the top of tetrahedron is the arc-cosine of the ratio of the height over the edge length.

$$\theta = \text{ArcCos}\left(\frac{\sqrt{2}}{\sqrt{3}}\right) = 35.26^\circ$$

According to Snell's law, the index of refraction n, times the sine of the angle sin(θ_1) of the ray leaving material m_1, is equal to the index of refraction n_2 times the sine of the angle of refraction sin(θ_2) of the ray entering material m_2. Referring to **FIG. 10**, the equation is

$$n_1 \sin(\theta_1)=n_2 \sin(\theta_2)$$

The index of air n_1 is equal to one. The index n_2 of Plexiglas is 1.50. If the incident ray is at $\theta_1=60^\circ$ to the normal, then the output angle is

$$\theta_2 = \text{ArcSin}\left[\frac{n_1}{n_2}\text{Sin}(\theta_1)\right] = \text{ArcSin}\left[\frac{2}{3}\frac{\sqrt{3}}{2}\right] = 35.26^\circ$$

which is equal to the angle of the tetrahedron.

[0021] Then I recalled several months earlier that I had gone to the Subway restaurant to get a sandwich. I was sitting by the Plexiglas window communicating with the Admiral whose mothership was in earth orbit. She mentioned that they were bringing two people aboard. At that moment I looked out through the window and I could see both of them clearly and easily through my spiritual eye. To my amazement, I saw both of the captives start to pull out guns from behind their backs. I then projected by spiritual hands which resulted in preventing the attack on the security guards. To say the least, the Admiral was rather surprised at these events. She then asked me to look at the design of the window because she thought it had something to do with my enhanced remote viewing capabilities. Looking at the Plexiglas, I noticed that on the edge of the large window pane there was a shorter piece of Plexiglas which was mounted parallel to the window pane. This smaller panel acted to protect the yellow neon fluorescent tube. I took the measurements of the design using a piece of paper that I found near the table.

[0022] I then went home and designed up a mounting bracket with my 3D computer software. I had already installed the stereolithography software that converts the design to the *.STL file format. How stereolithography works is that it slices the design into many thin horizontal sections. The machine has a platform which is mounted in a bath of liquid polymer. An ultraviolet laser, mounted on an xy-table, then traces out the slice. Because the liquid polymer is light sensitive, it polymerizes immediately into solid plastic. Then the platform is lowered a few thousandths of an inch and the second slice is added. This process eventually builds up the complete 3D part. Using the Internet, the *.STL file is sent by e-mail to the stereolithography service provider who returns the part overnight. So the next day I had the piece from which I made a plastic mold and several additional pieces for mounting the Plexiglas bracket on a full sheet of Plexiglas that I ordered locally. It never occurred to me to measure the angles, so after I got the index of refraction for Plexiglas, I measured the incident angle and it turned out to be 61°. So then I realized that the spiritual eye was being diffracted across these two Plexiglas plates which connected it to the tetrahedral geometry of subspace. Because subspace is the foundation of space, this created a much more efficient route for remote viewing. The result is that this invention has allowed me to make contact with 430 alien civilizations. Since then I have been awarded the Aphysics prize for my work in the invention and elaboration of the tetrahedron diagram of which there are now over 4000 graphs. The scientific discoveries contained in the diagram are (1) the electron and proton are one and same particle, (2) the existence of hyperspace, (3) how mass can be taken out of dimension, (4) cosmology determines the elementary particles, (4) all the physics constants and the tetrahedral geometry are contained in the two 360° circles of the infinity symbol and (5) all the physics constants are determined geometrically and projected from a subspace manifold into our dimension. For my work in Revelations, I was awarded four beautiful galloping riderless white horses of the Apocalypse.

A BRIEF DESCRIPTION OF THE DRAWINGS

[0023] **FIG. 1**. Remote viewing the top of a palm tree containing several coconuts.

[0024] **FIG. 2**. Remote viewing three soldiers running across a wooden bridge.

[0025] **FIG. 3**. Remote viewing computer building that soldiers were guarding.

[0026] **FIG. 4**. Spiritual eye of human aura.

[0027] **FIG. 5**. Tetrahedron.

[0028] **FIG. 6**. Tetrahedron circumscribed by sphere.

[0029] **FIG. 7**. Caribbean volcanic island vortex.

[0030] **FIG. 8**. Giant Red Spot on Jupiter.

[0031] **FIG. 9**. Olympus Mons volcano on Mars.

[0032] **FIG. 10**. Snell's Law of Refraction.

[0033] **FIG. 11**. Perspective view of remote viewing station.

[0034] **FIG. 12**. Wedge-shaped spacers for diffraction panel.

[0035] **FIG. 13**. Remote viewing angle.

[0036] **FIG. 14**. A remote viewing session taking place on a planet located 90,000 light years from earth on the other side of the galaxy showing His Highness signing with his left hand the document that allows his planet to become a member of the Pleiadian Federation.

DETAILED DESCRIPTION OF THE INVENTION

[0037] 1. Referring to **FIG. 11**, the remote viewing station is a rectangular box wooden frame (A) on which is mounted on one side a large sheet of Plexiglas (B). The diffraction panel (C), made of a shorter length of Plexiglas, is mounted with acrylic glue on the Plexiglas sheet using clear polyoptic molded plastic spacers (D).

[0038] Referring to **FIG. 12**, the wedge-shaped spacers (D) hold the diffraction panel (C) to the sheet of Plexiglas (B). The angle of the wedge is 30° which makes the incident angle 60° to the normal.

[0039] Referring to the top view perspective **FIG. 13**, sitting on the wide bench, the remote viewer can adjust his sight along the wedge for proper alignment at an angle of 60°. Due to the 1.50 index of refraction of Plexiglas, the spiritual eye is diffracted across the edge of the first panel and then refracted across the second panel at the tetrahedral angle of 35.26°.

[0040] Referring to **FIG. 14**, the remote viewing image is seen superimposed on the large sheet of Plexiglas which acts as the viewing screen.

I claim:

1. A remote viewing station comprising:

(a) a rectangular box frame made of wood having a length of six feet, a width of four feet and a height of six feet;

(b) a large sheet of quarter inch Plexiglas, having an index of refraction of 1.50, mounted on the right side of item (1a);

(c) several wedge-shaped clear plastic spacers, three inches in width and eight and a half inches in length, having a wedge angle of 30° that are mounted on the interior right side of item (1b);

(d) a shorter sheet of quarter inch Plexiglas, having a length of one and a half feet, mounted on item (1c) parallel to item (1b);

(e) a wide bench on which the remote viewer sits so that the remote viewer can align his sight along the wedge angle of item (1c);

2. A remote viewing amplifier that:

(a) diffracts the spiritual eye of the remote viewer across the edge of item (1d) at an incident angle of 60° to the normal;

(b) refracts the spiritual eye at 35.26° to the normal due to the refractive index of item (1a) according to Snell's Law of Refraction; and

(c) aligns the spiritual eye with the tetrahedral geometry of subspace due to the diffraction/refraction combination of item (2a) and (2b).

* * * * *

US 20060145019A1

(19) **United States**

(12) **Patent Application Publication**

St. Clair

(10) **Pub. No.: US 2006/0145019 A1**

(43) **Pub. Date: Jul. 6, 2006**

(54) **TRIANGULAR SPACECRAFT**

(76) Inventor: **John Quincy St. Clair**, San Juan, PR (US)

Correspondence Address:
JOHN ST. CLAIR
52 KINGS COURT, 4A
SAN JUAN, PR 00911 (US)

(21) Appl. No.: **11/017,093**

(22) Filed: **Dec. 20, 2004**

Publication Classification

(51) **Int. Cl.**
B64G 1/40 (2006.01)

(52) **U.S. Cl.** **244/171.5**

(57) **ABSTRACT**

A spacecraft having a triangular hull with vertical electrostatic line charges on each corner that produce a horizontal electric field parallel to the sides of the hull. This field, interacting with a plane wave emitted by antennas on the side of the hull, generates a force per volume combining both lift and propulsion.



Figure 1



Figure 2



Figure 3



Figure 4



Figure 5



Figure 6



Figure 7


$\frac{3}{4}\lambda$
$\frac{\lambda}{2}$
$\frac{\lambda}{2}$
E
B
D
C
A
F

TRIANGULAR SPACECRAFT

BRIEF SUMMARY OF THE INVENTION

[0001] This invention is a spacecraft having a triangular hull with vertical electrostatic line charges on each corner. The line charges create a horizontal electric field that, together with a plane wave emitted by antennas on the side of the hull, generates a force per volume providing a unique combination of both lift and propulsion.

BACKGROUND OF THE INVENTION

[0002] Referring to **FIG. 1**, the spacecraft has a hull in the shape of an equilateral triangle. A parabolic antenna (E) is centrally located in the bottom of the hull. An array of horizontal slot antennas is located along the side of the hull (A). Each back corner (F,G) has a corner conducting plate which is charged to a positive voltage +V. The forward corner (C) has a conducting plate charged to a negative voltage −V. A motion control hemisphere (D) is located on the bottom surface in each of the three corners.

[0003] Referring to **FIG. 2**, two planes (A,B) intersect at the origin O at an opening angle β. Each plane (x,y) is charged to a voltage V. The potential at point P is determined in polar coordinates {ρφ}. The Laplace equation for the potential Φ in polar coordinates is given by:

$$\frac{1}{\rho}\frac{\partial}{\partial\rho}\left(\rho\frac{\partial\Phi}{\partial\rho}\right)+\frac{1}{\rho^2}\frac{\partial^2\Phi}{\partial\phi^2}=0$$

Using a separation of variables solution, the potential is given as the product of two functions:

$$\Phi(\rho,\phi)=R(\rho)\Psi(\phi)$$

which when substituted into the Laplace equation becomes:

$$\frac{\rho}{R}\frac{d}{d\rho}\left(\rho\frac{dR}{d\rho}\right)+\frac{1}{\Psi}\frac{d^2\Psi}{d\phi^2}=0$$

Since the two terns are separately functions of ρ and φ respectively, each one has to be constant with the sum of the constants equal to zero:

$$\frac{\rho}{R}\frac{d}{d\rho}\left(\rho\frac{dR}{d\rho}\right)=v^2 \quad \frac{1}{\Psi}\frac{d^2\Psi}{d\phi^2}=-v^2$$

These two equations have solutions:

$$R(\rho)=a\rho^{v+b\rho-v}$$

$$\psi(\phi)=A\cos(v\phi)+B\sin(v\phi)$$

The azimuthal angle φ is restricted to a value in the range 0≦φ≦β. The boundary condition is that the potential Φ is equal to V for any radius ρ when φ=0 and φ=β. This means that v has to be an integer value of π so that the sine function is zero:

$$\sin(v\beta)=\sin\left(\frac{m\pi}{\beta}\beta\right)=\sin(m\pi)=0 \quad m=1,2\ldots$$

which in turn means that the coefficient A of the cosine term has to be zero in the solution above. Choosing b=0 makes the general solution for the potential equal to:

$$\Phi(\rho,\phi)=V+\sum_{m=1}^{\infty}a_m\rho^{m\pi/\beta}\sin(m\pi\phi/\beta)$$

which shows that when the angle is zero, the sine is zero and the potential is V. If the angle is β, then there is a multiple of π such that the sine is zero again.

[0004] Because the series involves positive powers of the radius, for small enough ρ, only the first term *m*=1 in the series is important. Thus around ρ=0, the potential is approximately

$$\phi(\rho,\phi)\approx V+a,\rho^{\pi/\beta}\sin(\pi\phi/\beta)$$

[0005] The electric field component is the negative gradient of the potential:

$$E_\phi(\rho,\phi)=-\frac{1}{\rho}\frac{\partial\Phi}{\partial\phi}=-\frac{\pi a_1}{\beta}\rho^{(\pi/\beta)-1}\cos(\pi\phi/\beta)$$

The surface charge distribution σ at φ=0 and φ=β is equal to the electric field perpendicular to the surface times the permittivity of space ϵ_0:

$$\sigma(\rho)=\varepsilon_0E_\phi(\rho,0)=-\frac{\varepsilon_0\pi a_1}{\beta}\rho^{\frac{\pi}{\beta}-1}$$

Notice that if angle of intersection β is less than π, then the equation says that there is a very small radius to a positive power which means little charge density accumulation.

[0006] Referring to **FIG. 3**, the value of β, in the case of the triangular hull, is equal to 360° less 60° for a total of 300° or:

$$\beta=\frac{300}{180}\pi=\frac{5}{3}\pi$$

$$\rho^{\frac{\pi}{\frac{5}{3}\pi}-1}=\frac{1}{\rho^{\frac{2}{5}}}$$

which says that there is a charge density singularity to the two fifths power for small radius. Thus, the corner plates on the hull create a huge line charge density along the sharp vertical corner edge. The equation for the potential of a line charge density is given as:

$$\Phi(x,y)=-\frac{\lambda}{2\pi\varepsilon_0}\mathrm{Ln}((x-x_0)^2+(y-y_0)^2)$$

where λ is the charge per unit length in the vertical z-direction, and x_0 and y_0 are the location of the line charge in the xy-plane.

[**0007**] Referring to **FIG. 4**, the triangular hull (D) is plotted together with the potential contours (A) and the electric field arrows (B) created by the three corner line charges. The line charges are perpendicular to the paper. Notice that the electric field arrows are parallel crossing the center parabolic antenna (C). The electric field is also parallel to the sides (D) of the triangle.

[**0008**] Referring to **FIG. 5**, along the side of the triangle (A), an array (B) of horizontal slot antennas emit electromagnetic waves that have a vertically polarized electric E field (C). These traveling waves interact with the electric field (D) produced by the line charges on the corners of the triangle.

[**0009**] Using differential forms mathematics, this combination of fields is represented by the Hodge star of the differential of the wedge product of the two fields. The antenna electromagnetic field is a combination of a traveling magnetic field B_w, and electric field E_w. The stationary field E created by the line charges is perpendicular to the traveling wave.

$$*d(E\wedge(B_w+E_w\wedge dt))\frac{\varepsilon}{c}=\frac{\text{force}}{\text{volume}}$$

where ϵ is the linear capacitance of space and c is the speed of light. Thus there is a force per volume around the hull.

[**0010**] This combination of fields produces a spacetime curvature as determined by Einstein's General Theory of Relativity. The traveling electric field has an amplitude in the vertical z-direction and travels in the x-direction

$$E_{\mathrm{w=Ez}}\cos(x-t)$$

The Faraday electromagnetic tensor contains all the electric and magnetic fields in all the {x,y,z} directions. The first row and first column contain the two electric fields

$$F^{\alpha}_{\beta}=\begin{array}{c|cccc|} t & 0 & E_x & 0 & E_z\cos(x-t) \\ x & E_x & 0 & 0 & 0 \\ y & 0 & 0 & 0 & 0 \\ z & E_z\cos(x-t) & 0 & 0 & 0 \end{array}$$

The stress exerted on spacetime occurs in the xx, yy and zz-direction as calculated from the stress-energy tensor T of gravitational physics

$$4\pi T^{\mu\nu}=F^{\mu\alpha}F^{\mu}_{\alpha}-\frac{1}{4}g^{\mu\nu}F_{\alpha\beta}F^{\alpha\beta}$$

where g is the metric tensor for Cartesian space

$$g_{\alpha\beta}=\begin{array}{c|cccc|} t & -1 & 0 & 0 & 0 \\ x & 0 & 1 & 0 & 0 \\ y & 0 & 0 & 1 & 0 \\ z & 0 & 0 & 0 & 1 \end{array}$$

where the diagonal components are the coefficients of the elementary spacetime length ds squared

$$(ds)^2=-(dt)^2+(dx)^2+(dy)^2+(dz)^2$$

The calculation produces three stresses T^{xx},T^{yy} and T^{zz} in their respective {x,y,z} directions.

[**0011**] Referring to **FIG. 6**, these three stresses are plotted together as a **3**D vector field animated over time in nine frames. The graphs show that there is a lift force as depicted by the vertical arrows as well as a force of propulsion as shown by the interspersed horizontal arrows. With the passage of time, these vectors exchange places with each other so that the lift becomes the propulsion and vice versa, creating a wavy stress-energy field around the hull.

SUMMARY OF THE INVENTION

[**0012**] This invention is a spacecraft with a triangular hull having charged flat plates on the vertical corners of the three sides. The two rear corners are charged to a potential V. The forward corner is charged to a potential −V. The 60° angle on the corner creates a line charge density singularity that produces a huge horizontal electric field pointing from the back to the front of the craft which is also parallel to the sides of the triangle. An array of horizontal slot antennas located on the sides of the triangular hull produce an electromagnetic wave with the electric field polarized in the vertical direction. This combination of fields produces a spacetime force in both the vertical and horizontal directions such that the spacecraft receives a lift force and a force of propulsion.

A BRIEF DESCRIPTION OF THE DRAWINGS

[**0013**] **FIG. 1**. Perspective view of triangular spacecraft.

[**0014**] **FIG. 2**. Drawing of the intersection of two charged plates in order to calculate the charge density in the corner.

[**0015**] **FIG. 3**. Perspective view of the corner angle β for the equilateral triangle.

[**0016**] **FIG. 4**. Planar **2**D graph showing the electric field produced by three line charges on the corners of the triangular hull.

[**0017**] **FIG. 5**. Perspective view of electric field produced by the linear charge interacting with the traveling electromagnetic wave produced by the slot antenna.

[**0018**] **FIG. 6**. **3**D vector animation of the lift and thrust force generated by the fields.

[**0019**] **FIG. 7**. Perspective view of slot antenna.

DETAILED DESCRIPTION OF THE INVENTION

[**0020**] Referring to **FIG. 7**, the antenna (A) is made out of sheet copper in which a rectangular horizontal slot (B) has been notched out using a die press and sheet metal fixture. A coaxial cable from the amplifier and frequency generator is attached across the slot by soldering the outer cable (D) to one side of the slot and the inner cable (E) to the other side of the slot. This creates the positive and negative charges across the gap which forms the vertical electric field (F) which radiates out perpendicularly to the copper sheet.

[0021] Although the invention has been described with reference to specific embodiments, such as a particular antenna system, those skilled in the art will appreciate that many modifications and variations are possible without departing from the teachings of the invention. All such modifications and variations are intended to be encompassed within the scope of the following claims.

1. A spacecraft comprised of the following components:

(a) a triangular hull in the form of an equilateral triangle;

(b) two copper plates attached on opposite vertical sides at each of the three corners of the hull (**1***a*) such that a sharp vertical edge is formed where they come together;

(c) an electrostatic generator used to charge the back two copper-cladded corners (**1***b*) to a high positive voltage, and the third forward copper-cladded corner to a high negative voltage;

(d) a horizontal slot antenna array mounted-on the sides of the hull; and

(e) a frequency generator, antenna and coaxial cables to drive the antenna array (**1***d*).

2. To create, by claims (**1***a*, **1***b*, **1***c*), an intense vertical line charge at the corners (**1***b*) and a horizontal electric field that that is parallel to the sides of the hull (**1***a*);

3. To create, by claims (**1***d*,**1***e*), an electromagnetic wave with a vertically polarized electric field traveling outward from the side of the hull (**1***a*); and

4. To create, by claims (**2**,**3**), an interaction of the electrostatic field (**2**) with the electromagnetic wave (**3**) such that a combined spacetime curvature pressure is generated on the hull in the upward and forward direction to produce lift and propulsion respectively.

* * * * *

US 20060112848A1

(19) **United States**
(12) **Patent Application Publication**
St. Clair
(10) **Pub. No.: US 2006/0112848 A1**
(43) **Pub. Date: Jun. 1, 2006**

(54) **PERMANENT MAGNET PROPULSION SYSTEM**

(76) Inventor: **John Quincy St. Clair**, San Juan, PR (US)

Correspondence Address:
JOHN ST. CLAIR
52 KINGS COURT, 4A
SAN JUAN, PR 00911 (US)

(21) Appl. No.: **11/001,217**

(22) Filed: **Dec. 1, 2004**

Publication Classification

(51) **Int. Cl.**
B61C 3/00 (2006.01)
(52) **U.S. Cl.** **105/49**

(57) **ABSTRACT**

This invention is a propulsion system for a train that uses permanent magnets mounted on a rotating iron cylindrical plate carrying a radial current in order to create a spacetime curvature distortion which pulls the locomotive along the track.



Figure 1



Figure 2



Figure 3


J
D
K
E
G
A
F
C
H
I
B

Figure 4



PERMANENT MAGNET PROPULSION SYSTEM

BRIEF SUMMARY OF THE INVENTION

[0001] This invention is a propulsion system for a train that utilizes spinning cylindrical magnets in order to create a spacetime pressure distortion ahead of the vehicle that pulls the locomotive along the track.

BACKGROUND OF THE INVENTION

[0002] At the present time, referring to **FIG. 1**, proposed permanent magnet propulsion systems use a dual railway track (A) supporting a series of coil windings (B) located along the track. The vehicle is attached to two permanent magnets (D) between steel pole pieces (C). The north pole of each magnet faces the interior pole piece such that the magnetic flux path (E) follows the center pole piece up through the railway bed and then back to the south pole of the magnet. As the magnets move along the track, the coil windings are activated at the correct time by Hall sensors. With the coil energized as a north pole, the permanent magnet north pole is repelled which drives the vehicle along the track The problem with this design, and other similar designs, is that it is not practical to wind huge numbers of sensor-activated electrical coils along a steel track.

[0003] From Einstein's General Theory of Relativity, it is known that a spacetime curvature pressure develops perpendicular to direction of vibration of the electric and magnetic field. As an example, the photon has an electric field vibrating in the vertical y-direction and a magnetic field vibrating in the horizontal x-direction. The spacetime curvature pressure is therefore along the z-axis of radiation which pushes the negative mass of the photon along. Thus in order to create a spacetime curvature pressure in the z-direction along the track which would pull the train forward, a magnetic flux density field is required in the radial direction.

[0004] Referring to **FIG. 2**, four equally-spaced north permanent magnets (B) surrounding a centrally-located south permanent magnet (C) are mounted on an iron cylinder which acts as the radial flux return path. The magnetic flux density field (D) is in the radial direction from the north pole to the south pole. In order to provide strength, the magnets are molded onto a steel shaft and coated with epoxy so that they don't rust. During the molding process, a capacitor-discharge magnetizer is used to create the magnetic field of the magnet.

[0005] In Cartesian coordinates {−ct,x,y,z}, the elemental spacetime length ds squared is the sum of the squares of the incremental lengths {cdt,dx,dy,dz}

$$(ds)^2=-(dt)^2+(dx)^2+(dy)^2+(dz)^2$$

where the speed of light c is unity. The coefficients (−1,1,1,1) of this equation make up the g metric 4×4 tensor

$$g_{\alpha\beta} = \begin{array}{c|cccc|} & [t & x & y & z] \\ t & -1 & 0 & 0 & 0 \\ x & 0 & 1 & 0 & 0 \\ y & 0 & 0 & 1 & 0 \\ z & 0 & 0 & 0 & 1 \end{array}$$

[0006] The Faraday electromagnetic tensor contains the magnetic fields which determine how the spacetime length ds is curved. For a magnetic flux density field in the x-direction, Bx, and a magnetic flux density field in the y-direction, By, the Faraday tensor is

$$F^{\alpha}_{\beta} = \begin{array}{c|cccc|} & t & x & y & z \\ t & 0 & 0 & 0 & 0 \\ x & 0 & 0 & 0 & -By \\ y & 0 & 0 & 0 & Bx \\ z & 0 & By & -Bx & 0 \end{array}$$

The stress-energy-momentum tensor T, which determines how space is curved, is calculated from the following equation

$$4\pi T^{\mu\nu} = F^{\mu\alpha}F^{\nu}_{\alpha} - \frac{1}{4}g^{\mu\nu}F_{\alpha\beta}F^{\alpha\beta}$$

The stress-energy in the z-direction ahead of the locomotive is

$$T^{zz} = \frac{B_x^2 + B_y^2}{8\pi} = \frac{B_r^2}{8\pi}$$

where the sum of the squares of the fields in the x and y directions is the radial B field. In Einstein's General Relativity Theory, the curvature G tensor is equal to the stress-energy tensor divided by 8π. The G tensor is the curvature of space having units of inverse radius squared.

$$G = \frac{T}{8\pi}$$

Therefore the curvature G_{zz} generated along the z-direction ahead of the train is proportional to the square of the magnetic flux density field

$$G_{zz} = \frac{1}{r^2} = \frac{G\varepsilon}{c^2}\frac{B_r^2}{8\pi} = \frac{1}{meter^2}$$

where G is Newton's gravitational constant (not to be confused with the curvature tensor), ε is the linear capacitance of space, and c is the speed of light. The linear mass of space Ω is the speed of light c squared divided by the gravitational constant G, so that the equation can be written as

$$\frac{G\varepsilon}{c^2}\frac{B_r^2}{8\pi} = \frac{\varepsilon}{\Omega}\frac{B_r^2}{8\pi} = \frac{1}{\frac{\Omega}{\varepsilon}}\frac{B_r^2}{8\pi}$$

where the conversion factor is the square of the magnetic vector potential A

$$\sqrt{\frac{\Omega}{\varepsilon}} = \frac{\text{kgm}}{seccoul} = A$$

which is actually the momentum per charge. Therefore the curvature equation can be written as

$$\frac{1}{r^2} = \frac{1}{8\pi}\left(\frac{B_r}{A}\right)^2$$

This equation shows that it is necessary to create a magnetic vector potential together with the radial magnetic flux density field in order to create a curvature of space. Looking at the units of A shows that it is a mass momentum per charge

$$A = \frac{\text{kg}}{sec}\frac{m}{coul} = \frac{m\omega^2 r}{I}$$

or a mass m rotating with angular velocity c) per current along the radius. In terms of the invention, what this means is that the mass of the iron cylinder has to be rotating and there has to be a radial electrical current I in order to produce the linear charge along the radius. The differential mass dm depends on the circumference times the differential radius dr, the mass density p, and the length L of the cylinder

$$dm=\rho 2\pi rLdr$$

so that the magnetic vector potential becomes

$$A = \int_0^R \frac{\rho 2\pi rL\omega^2 r}{I}\,dr = \frac{2}{3}R^3\rho\pi L\frac{\omega^2}{I}$$

The value of A for the iron cylinder is

$$L = .2m$$

$$\rho = 7866\frac{kg}{m^3}$$

$$R = 1m$$

$$\omega = 2\pi f = 6.28\ \text{sec}^{-1}$$

$$I = 3000000\ \text{amp}$$

$$A = .04335\frac{kgm}{\text{sec}coul}$$

$$Br = 1.2tesla$$

$$\frac{1}{8\pi}\left(\frac{Br}{A}\right)^2 = 30.47m^2$$

$$r_{curvature} = \sqrt{8\pi}\left(\frac{A}{Br}\right) = .181m$$

What makes this possible is that the new N-machines can easily generate a minimum of 6 million amps which is twice the value of the electrical current above.

[0007] Referring to **FIG. 3**, the assembly consists of a large induction motor (A) mounted on the train's base plate (B) driving a motor shaft (C) attached to the iron cylinder (D). The shaft is held in place by two thrust bearings mounted in two pillow blocks (E,F). The current-generating N-machine (G) is electrically connected by a copper bus (H) to a copper-beryllium brush (I) on the motor shaft with a similar return brush (J) on the edge of the iron cylinder. The current (K) flows through the motor shaft to the center of the rotating cylinder and then radially outward to the edge. The magnetic flux density flows from the north poles of the outer permanent magnets to the central south pole, along the central magnet to the center of the rotating cylinder and then radially outward to the south poles of the outer magnets.

[0008] The thrust F developed is the radius of curvature of spacetime r_c calculated above times the magnet flux density field times the current I

$$F = \frac{r_c B_r I}{\sqrt{8\pi}} \approx 30000lbf$$

Using conservation of tensor coordinates, the radius of curvature is in the z-direction, the magnetic flux density field is in the radial direction and the current is in the radial direction

$$F^z=x^zB_rI^r$$

where the radial indices cancel, leaving the z-index as the direction of the force.

SUMMARY OF THE INVENTION

[0009] It is the object of this invention to create a spacetime curvature in front of a train locomotive in order to pull the vehicle along the track It is known from gravitational physics that a spacetime curvature is generated perpendicular to the direction of vibration of the electric and magnetic field. A radial magnetic field, which can be produced by permanent magnets attached to the flat faces near the rim of a iron cylinder rotating about the z-axis, will create a curvature in the z-direction. Four cylindrical north-pole-oriented magnets produce a radial magnetic flux density with is channeled into a central cylindrical south-pole-oriented magnet. The flux lines then flow radially outward through the steel rotating cylinder and reconnect with the south poles of the four outer magnets. The rotating iron cylinder generates the equivalent of a magnetic vector potential when an electrical current flows from the center of the cylinder to the edge. This current is generated by an N-machine current generator. The square of the magnetic flux density divided by the magnetic vector potential is equal to the spacetime curvature. The square root of the inverse of the spacetime curvature is the radius of curvature. The thrust developed is this radius of curvature times the magnetic flux density field times the current.

A BRIEF DESCRIPTION OF THE DRAWINGS

[0010] **FIG. 1**. Perspective view of proposed permanent magnetic propulsion system using coil windings on the steel track.

[0011] **FIG. 2**. Perspective view of permanent magnet rotor assembly.

[0012] **FIG. 3**. Perspective view of system showing motor drive, N-machine and permanent magnet rotor.

[0013] **FIG. 4**. Perspective view of locomotive and rotor/magnet assembly.

DETAILED DESCRIPTION OF THE INVENTION

[0014] 1. The permanent magnets are made of neodymium-iron-boron material which is heated to its melt temperature and injection molded around a steel shaft threaded at one end while at the same time a pulsed magnetic field is applied to the material using a charge-discharge magnetizer. Because of the iron in the material, a coat of epoxy is applied to the magnet in order to protect it from the environment. Holes are drilled into the iron plate 90° apart near the rim, threaded, and then the steel shaft with the magnet is then inserted. Another hole is drilled and tapped in the center of the circular plate for attaching the south pole magnet which is used as the return path for the magnetic flux.

[0015] 2. Another easier way to make the magnets is to purchase short lengths of tubular NdFeB magnets and then stack them on the steel shaft with a cylindrical iron pole piece on the end of the shaft. The pole piece then holds the magnets down in place when the shaft is threaded into the plate.

[0016] 3. Referring to **FIG. 4**, the propulsion system is mounted inside the train cabin such that the rotor/magnet assembly extends out in front of the locomotive where the spacetime curvature is generated.

I claim:

1. A train propulsion system consisting of the following components:

a. a rotating iron cylindrical plate rotor of high relative permeability driven by an induction motor and horizontal steel motor shaft mounted in pillow block thrust bearings;

b. four cylindrical magnets, each molded to a steel support shaft threaded into the iron plate at 90° intervals around the rim of the plate with their north poles facing away from the plate;

c. a fifth cylindrical magnet molded to a steel support shaft which is threaded into the center of the iron plate with the south pole facing away from the plate;

d. an N-machine current generator supplying a radial electrical current from the center of the rotating plate by means of a copper-beryllium brush on the motor shaft (**1***a*) and another similar brush on the outside edge of the rotor.

e. a locomotive train on which the components are mounted such that the rotor/magnet assembly extends out in front of the locomotive with the rotor's angular velocity vector pointing along the track.

2. a closed magnetic flux path along a radial path in air from the north poles of the four outer magnets (**1***b*) to the south pole of the central magnet (**1***c*), through the center magnet and then radially outward through the rotor (**1***a*), returning back through the four outer magnets, such that the flux and electrical current (**1***d*) flow in the same outward radial direction through the rotor.

3. the creation of a spacetime curvature due to claims (**1***a* through **2**) that produces a large force on the locomotive equal to the radius of the spacetime curvature times the flux times the current.

* * * * *

US 20060180473A1

(19) **United States**
(12) **Patent Application Publication**
St. Clair
(10) **Pub. No.: US 2006/0180473 A1**
(43) **Pub. Date: Aug. 17, 2006**

(54) WATER ENERGY GENERATOR

(76) Inventor: **John Quincy St. Clair**, San Juan, PR (US)

Correspondence Address:
JOHN ST. CLAIR
52 KINGS COURT, 4A
SAN JUAN, PR 00911 (US)

(21) Appl. No.: **11/060,037**

(22) Filed: **Feb. 17, 2005**

Publication Classification

(51) **Int. Cl.**
C25D 5/34 (2006.01)
(52) **U.S. Cl.** **205/210**

(57) ABSTRACT

A water energy generator that generates electricity using a magnetic vortex wormhole generator and a water injector/vacuum chamber to produce low density hyperspace energy that causes the hydrogen atoms of water molecules to decay into electron pairs.





Figure 1



Figure 2



Figure 3



Figure 4



Figure 5


Iy
z
r
θ
x

Figure 6



Figure 7



Figure 8



Figure 9


13
23
22
14
16
19
24
18
15
17
21
20

Figure 10


Energy of Electric Field per Volume vs. Time t
0.01
0.02
0.03
0.04
0.05
0.06
-2 × 10⁶
-4 × 10⁶
-6 × 10⁶
-8 × 10⁶

Figure 11


-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
-10 -20 -30 -40 -50 -60 -70 -80 -90 -100 -110 -120 -130 -140 -150 -160 -170 -180 -190
ln(wavelength)
32
31
27
28
35
34
36
30
37
26
29
33
25
a
b
c
d
e
f

Figure 12


p
u_r
u_g
d_b
u_r
π^0
$\bar{u}_r$
X
e^+

Figure 13



Figure 14


H
38
p + e⁻
40
e⁺ + e⁻
p
39
π⁰ + e⁺
π⁰
41
hν + hν
66
hν
42
e⁺ + e⁻
66
hν
43
e⁺ + e⁻
133 pairs

Figure 15


56
57
58
49
48
47
45
44
46
50
51
52
53
54
55

Figure 16



Figure 17



WATER ENERGY GENERATOR

BRIEF SUMMARY OF THE INVENTION

[0001] This invention is an energy generator that uses the transition through wormholes of the hydrogen atoms of water molecules to break the bonds of the atoms and convert the protons into photons and electrons which can be collected for energy.

BACKGROUND OF THE INVENTION

[0002] A molecule of water consists of two hydrogen H atoms and one atom of oxygen O which has the chemical formula

$$H_2O$$

The hydrogen atoms can be separated from the oxygen atom by electrolysis. In this process, a direct current of electricity, such as from a battery, is passed through water decomposing it into hydrogen and oxygen. Pure water, however, is a poor conductor of electricity. It is therefore necessary to add some substance to form a solution that will conduct an electric current. Such a solution that will conduct electric current is called an electrolytic solution. A small amount of sulfuric acid or sodium hydroxide is added to the water to form an electrolytic solution. Water electrolyzed yields hydrogen plus oxygen

Water->hydrogen+oxygen

$$2H_2O \rightarrow 2H_2+O_2$$

Because this invention is to be used on spacecraft, the oxygen can be used for breathing and the hydrogen can be used to produce energy that will be used to create the electromagnetic fields which provide lift and propulsion.

[0003] Referring to **FIG. 1**, a single hydrogen atom consists of one proton (1) in the nucleus and one electron (2) moving in an orbital (3) around the nucleus. In quantum physics notation, there is only one main K shell and one orbital containing a single electron in the 1 s subshell. An orbital is an energy level containing one or two electrons in a subshell of an atom. Only a total of two electrons may be placed in one orbital with the added constraint that the electrons spin in opposite directions. Looking at the 1 s orbital, it can be seen that only half of it is occupied. What this means is that it is possible to add another hydrogen atom in which its electron occupies the other position in the orbital to from the hydrogen molecule H_2.

[0004] In 1925, a physicist by the name of Edwin Schrodinger developed a wave equation, which bears his name, that models the hydrogen atom. Even though the classical picture of **FIG. 1** showing a distinct electron orbiting the proton is easy to visualize, in reality the electron is a wavefunction Ψ whose square indicates the probability of finding the electron at a particular point. This then was the start of quantum physics where it was found that the electron energy can only take on certain discrete values.

[0005] A traveling wave moving in the positive x-direction can be represented by the function $\Psi_1=\Psi_1(x,t)$ of the form

$$\Psi_1=A_1 \cos(2\pi(x/\lambda-v\ t))$$

where x is the distance along the x-axis, A the wave amplitude, λ the monochromatic wavelength, v the velocity of the wave and t time.

[0006] A similar monochromatic wave moving to the left can be represented by

$$\Psi_2=A_2 \cos(2\pi(x/\lambda+v\ t))$$

where the sign of the velocity is reversed. The superposition of these traveling waves results in a standing wave, or stationary waves, of the form

$$\Psi=\Psi_1+\Psi_2=A \cos(2\pi x/\lambda) \cos(2\pi v\ t)$$

which is now a product of a spatial-dependent term A $\cos(2\pi x/\lambda)$, and a time-dependent term $\cos(2\pi v\ t)$. Taking the partial derivative of Ψ twice with respect to x

$$\frac{\partial^2\Psi}{\partial x^2} = -\left(\frac{2\pi}{\lambda}\right)^2\Psi$$

The momentum p of a particle is equal to Planck's constant h divided by the mass m of the particle

$$p = h/\lambda = \frac{2\pi\hbar}{\lambda}$$

where h bar is the reduced Planck constant. Thus Schrodinger's equation can be written as

$$\frac{\partial^2\Psi}{\partial x^2} = -\frac{p^2}{\hbar^2}\Psi$$

For a particle whose potential energy is V(x), the total energy is the kinetic energy K plus the potential energy

$$E=K+V=(p^2/2m)+V$$

Therefore,

$$p^2=2\ m\ (E-V)$$

and Schrodinger's equation becomes

$$\frac{\hbar^2}{2m}\frac{\partial^2\Psi}{\partial x^2} + (E-V)\Psi = 0$$

The potential V is just the Coulomb potential of the product of two charges e divided by the radius r between them

$$V = \frac{e^2}{4\pi\varepsilon r}$$

where ϵ is the linear capacitance of space. A general wavefunction can be separated into a radial R part and a spherical harmonics part Y

$$\Psi=R_{n,1}Y_{1,m}(\theta,\phi)$$

where the first term is called a radial wavefunction which describes the "in-out" motion of the electron. When Schrodinger's equation is separated, it is found that the radial part of the wavefunction, R, must be a solution of the quantized differential equation

$$\frac{\hbar^2}{2mr}\frac{d^2(rR)}{dr^2} + \left(E - \frac{l(l+1)\hbar^2}{2mr^2} + \frac{e^2}{4\pi\varepsilon r}\right)R = 0$$

This can be expressed in a simpler form by defining the function

$$f=rR$$

which is then found to satisfy the equation

$$\frac{\hbar^2}{2m}\frac{d^2 f}{dr^2} + (E - V_{eff})f = 0$$

where the effective potential is given by

$$V_{eff} = \frac{l(l+1)\hbar^2}{2mr^2} - \frac{e^2}{4\pi\varepsilon r}$$

where the 1's are the quantum orbital numbers. For s orbitals equal to 1=0, the effective potential is just the electrostatic potential of the nucleus. For 1 greater than zero, the first term is equal to the kinetic energy owing to the angular motion of the electron at a distance r and with angular momentum √1(1+1)h.

[0007] Referring to **FIG. 2**, the effective potential is graphed as a function of radius r and the orbital numbers. For orbital number l=0, which is the lower of the three curves, the potential does not provide a stable position for the electron (black disk) and the negatively-charged electron just crashes into the positively-charged proton nucleus as shown by the arrow. For orbital l=1, the first term is called the centrifugal repulsion which together with the electrostatic potential provides for a stable position for the electron as seen in the middle curve. The potential energy is negative which creates a slight valley in which the electron obtains a stable orbit. Higher orbital numbers l=2 produce a similar valley potential further out on the radius. The l=1 orbital does not allow the electron to come near the proton which provides for a stable hydrogen atom. So the key to this invention is how to destabilize this hydrogen atom energy system and produce usable energy which can propel the electromagnetic spacecraft and run other hyperspace inventions. Refer to my patent applications such as Dipole Moment Spacecraft, Dual Potential Hull Spacecraft, Photon Spacecraft, Electromagnetic Field Propulsion System, Full Body Teleportation, Magnetic Vortex Wormhole Generator, Electric Vortex Wormhole Generator, Sulfur S8 Wormhole Generator, Cavitating Oil Hyperspace Energy Generator, Rotor Inductance Propulsion System and Triangular Spacecraft.

[0008] Many of these patent applications involve wormholes and hyperspace which are not well-known concepts in the scientific community. Hyperspace consists of those dimensions which are co-dimensional with our spacetime. The reason I know about hyperspace is because (1) I have been in hyperspace on a number of occasions and have experienced Einstein's time dilation according to his General Theory of Relativity, (2) I have experienced more than one full-body hyperspace teleportation over a distance of 100 meters, (3) we have been able to create a wormhole between space and hyperspace with the magnetic vortex wormhole generator in which smoke was blown through one side of the coil into hyperspace, a first contact verified by the Grey Aliens, (4) I have seen the green mist associated with moving out of dimension and crossing over into hyperspace, (5) I have looked into another dimension and have seen another building, a car and a man who waving at me in the presence of an artificially-intelligent Cyborg with the "high-tech look" from the Pleiadian Defense Department, (6) I can remote view through hyperspace subgeometry to distances of 100,000 light years to the edge of the galaxy and have made first contact with around 500 extraterrestrial civilizations involving the use of patent applications such as Remote Viewing Amplifier, Quantum Dot Energy Cylinder and Walking Through Walls Training System, (7) I am the only person on Earth who has communicated with the designers of the crop circles found in England and explained their design to them in terms of subspace geometry, (8) I can walk through walls as a hyperspace energy being, and (9) I have discovered how anti-gravity is possible using low density hyperspace energy, not to mention all the other research work on these electromagnetic field propulsion vehicles. For my work in developing the geometry of the subspace manifold known as the tetrahedron diagram, I was given the Aphysics award by the Admiral, who is third in line to the Admiralty of the Pleiadian Defense Department. For my work in Revelations, she awarded me four beautiful galloping white riderless horses of the Apocalypse. The reason that the Pleiadian Defense Department was involved was that the Admiral had the task of creating the energy being that would protect the subspace manifold during the battle of Revelations which took place in the year 2001. So these are some of my personal experiences in the field of hyperspace physics.

[0009] As to the scientific aspect of hyperspace physics, observations of the solar system have noted that large vortices occur on the planets at a latitude of ±19.5°. On the planet Jupiter, for example, the Giant Red Spot vortex, which is the size of two planets like Earth, is located at −19.5° latitude.

[0010] Referring to **FIG. 3**, the Olympus Mons volcano, which is the size of France, occurs in the northern hemisphere at 19.5°. The plume of volcanic ash can be seen being blown to the upper right.

[0011] Here on Earth, just north of me at +19.5° in the Caribbean, there is a slow moving rock mantle vortex that curves the islands down toward Venezuela. Since the tetrahedron has three corners, another corner occurs at 120° to the west where the Marshall Islands are located. The reason that the volcanic islands form is that low density hyperspace energy softens the atoms and molecules to such an extent that the atomic bonds are broken. The hot magma from the core has an easier path to the surface through the soft rock compared to the hard rock of surrounding areas. As the vortex rotates, the rising hot magma creates volcanoes which form the chain of islands.

[0012] As another example of this, the Silver bridge, which is located at a double harmonic of 39° between Ohio and West Virginia, collapsed because a large wormhole opened up and flooded the bridge with low density hyperspace energy. The metal rivets softened and pulled out of the plates holding down the suspension cables. Thus the roadway tilted to one side and all the cars fell into the river.

[0013] If you look at the quarried granite polygonal megalithic stone blocks that were used to build Machu Picchu, the blocks are put together as though they were soft putty. They fit together perfectly. Machu Picchu, or Great Picchu, is the Quichua name for a sharp peak which rises ten thousand feet above the sea. How this was achieved is described in my patent application *Rotating Magnetic Vortex Generator* which shows that rotating permanent magnets can create a wormhole between space and hyperspace. The low density hyperspace energy then floods the block as to make it weightless. The block is then floated up from the quarry which is 2500 feet below Machu Picchu. The huge 1000-ton blocks found in the platform at Baalbek in the Cedar Mountains of Lebanon were also lifted into position in this manner.

[0014] Using a technique called Chi Kung breathing, not necessarily known to the Chinese, one of our researchers has been able to levitate himself to a height of six feet. He might have gone higher but he lost his balance and his arm touched a nearby metal pipe. He then floated back to the ground. Contracting the abdominal muscles causes hot air to rise in the lungs while at the same time cold air is inhaled through the nose. This combination of hot and cold air mixing together creates environmental oscillators having a temperature fluctuation. This changes Planck's constant such that the body goes out of dimension and low density hyperspace energy fills the body.

[0015] The final example comes from Biblical times. Jesus and his father Joseph were both carpenters. A chair that Joseph had made for a client was found to be too small. So Jesus placed his hands on either side of the chair and stretched the chair to fit. The phrase in Spanish is “mas silla” which means that Jesus made more chair. In the dictionary, the Spanish word for putty is “masilla.” The reason that Jesus could do this is that he passed hyperspace energy through his hand vortices which softened the wood. See my patent application called *Hyperspace Torque Generator* which shows this in more detail. The hand vortex is actually a planar co-gravitational K field that can rotate a pendulum around in circles. This solenoidal field corresponds to the magnetic H field. The electric field corresponds to the linear gravitational g field. The equations are identical for both sets of fields. I learned that Jesus actually reincarnated here on Earth in order to identify the planet on which the battle of Revelations would take place.

[0016] In summary, these are some examples as to how low density hyperspace energy can soften and break the bonds of atoms and molecules.

[0017] As mentioned previously, the astronomical observations suggest that the structure of the universe is related to the tetrahedron. Referring to **FIG. 4**, the corners of a tetrahedron circumscribed by a sphere, touch the sphere at an angle of 19.47122063°. The ratio of the area-to-volume ratio of the sphere to the area-to-volume ratio of the tetrahedron is ⅓ which is the magic ratio in physics. The arcsin(⅓) is 19.47°.

[0018] In order for all the physics constants to be projected into our universe and the co-dimensional hyperspace dimensions, there has to be a tetrahedral subspace manifold. The only mathematical function which allows multiple rotations of the complex plane is the logarithmic function Log[z].

[0019] Referring to **FIG. 5**, the complex number z in the complex plane is equal to x+I y where x and y are real constants and $I^2=-1$. The complex number z can also be written in terms of a radius and an angle

$$z=r\ \mathrm{Exp}[I\ \theta]$$

Because the angle can rotate more than once in 2π m multiples, the complex number z is actually

$$z=r\ \mathrm{Exp}[I(\theta+2\pi\ m\ )]$$

Taking the logarithm of z

$$\mathrm{Log}[z]=\mathrm{Log}[r]+I(\theta+2\pi m)$$

[0020] Referring to **FIG. 6**, it can be seen that it is not possible to go around multiple times on the same surface due to a branch cut along the origin where Log[0] is undefined. What happens is that as you rotate around on surface (4) and get to the origin, you go down along the branch (5) to the next hyperspace plane (6). Thus the universe is composed of many hyperspace co-dimensions. From personal experience, I estimate that the distance separating the two dimensions is about 3 meters when I was looking into another dimension at the man waving at me. The physics is even more complicated because there is a Lorentz dimensional transformation in which higher dimensions appear smaller and lower dimensions appear larger. In one case I was looking at a huge mothership at a much higher dimension and it looked like a tiny toy model spacecraft. They fired a laser cannon at me, and I then curved space which made the beam change course. You can see why I was awarded the four horses.

[0021] The antilog of Log[z] is

$$e^{\mathrm{Log}[z]}=z=re^{I\ \omega t}$$

where the angle is the angular frequency ω times the time t. The subspace geometry remains stationary or fixed, but the projection of the antilog into our dimension generates a system which is frequency dependent. This is why we get oscillating fields.

[0022] From Einstein's General Theory of Relativity, it is known that various kinds of energy can curve spacetime such as mass, electromagnetic fields, angular momentum and electrical charge. The elemental spacetime length ds in cylindrical coordinates {t,r,θ,z}, known as the Schwarzschild metric, shows that spacetime can be curved using mass M and charge Q

$$(ds)^2=-(dt)^2\left(1-\frac{2M}{r}+\frac{Q^2}{r^2}\right)+\frac{dr^2}{\left(1-\frac{2M}{r}+\frac{Q^2}{r^2}\right)}+(rd\theta)^2+(dz)^2$$

where you can see that the elemental time dt is dilated by the mass M and the elementary radius dr is reduced. I have actually experienced this time dilation in which, as I was jumping into hyperspace, I was hit by a car which broke my shoulder. When I came back into dimension which appeared to be a few seconds later, I found that I had an 8-inch blood ring down the right side of my chest. My shoulder blade, which sticks up about two inches, is still broken to this day.

[0023] Referring to **FIG. 7**, flat space (**7**) can be curved (**9**) by a massive body (**8**) such as a planet. For example, the mass of the Earth gives space a negative curvature such that objects tend to fall toward the center of the mass (bowl). On the other hand, using electromagnetic fields, it is possible to produce a positive curvature such that a spacecraft rises by falling upward.

[0024] Referring to **FIG. 8**, if the fields are intense enough, then a wormhole (**12**) forms between space (**10**) and hyperspace (**11**). This depiction is called an embedding diagram because there is no open space going through the wormhole. An object traversing the wormhole moves along the surface from one dimension to another. In order to open the throat (**12**) of the wormhole, negative energy is required. Referring to my patent application Dual Potential Hull Spacecraft, negative energy is produced by the interaction of a microwave beam with an oscillating magnetic H field. In terms of differential forms mathematics, this is given as the Hodge Star * of the differential d of the wedge ^ product of the magnetic H field with the electromagnetic wave {B,E}

$$*d(H\wedge(B+E\wedge dt))=\frac{\partial(-\rho)}{\partial t}$$

which says that there is an increasing rate of change of negative energy (−ρ). Due the presence of negative energy together with the spacetime curvature pressure produced by the electromagnetic fields, wormholes open up between space and hyperspace. There is a positive gravitational potential between hyperspace and space because the low density hyperspace energy is more dense than the negative energy in this dimension. Thus the hyperspace energy flows into our dimension which reduces the mass of the spacecraft. The upward spacetime pressure stress over the hull due to the electromagnetic fields creates a lift force on the nearly massless vehicle. Because the hyperspace energy has a speed of light equal to one meter per second, the electromagnetic fields become relativistically strong since they obey the Lorentz transformation. Due to the low mass, high spacetime lift pressure and strong EM fields, the vehicle can attain very high rates of acceleration.

[0025] Another method to produce a wormhole is to use bucking magnetic fields which is described in my patent application *Magnetic Vortex Wormhole Generator*. In gravitation physics, the Faraday F tensor, which is a 4×4 spacetime metric {t,x,y,z}, contains all the components of the electromagnetic fields in the various spatial directions {x,y,z}

$$F^{\alpha}_{\beta}=\begin{array}{c|cccc|}
t & 0 & E_x & E_y & E_z \\
x & E_x & 0 & B_z & -B_y \\
y & E_y & -B_z & 0 & B_x \\
z & E_z & B_y & -B_x & 0
\end{array}$$

where contravariant index a refers to the rows, and the covariant index β refers to the columns. For example, the component $F^t_x=E_x$ is the electric field in the x-direction. If there were two magnetic bucking fields in the x-direction the Faraday tensor would be

$$F^{\alpha}_{\beta}=\begin{array}{c|cccc|}
t & 0 & 0 & 0 & 0 \\
x & 0 & 0 & 0 & 0 \\
y & 0 & 0 & 0 & B_x-B_x \\
z & 0 & 0 & -(B_x-B_x) & 0
\end{array}=\begin{vmatrix}0&0&0&0\\0&0&0&0\\0&0&0&0\\0&0&0&0\end{vmatrix}$$

which says that the Faraday tensor is zero. Thus no spacetime curvature is generated from two bucking magnetic fields at the same position. On the other hand, if the two bucking magnetic fields are concentric at different radii, then the Faraday tensor becomes

$$F^{\alpha}_{\beta}=\begin{array}{c|cccc|}
t & 0 & 0 & 0 & 0 \\
x & 0 & 0 & 0 & 0 \\
y & 0 & 0 & 0 & B_x\delta(x_1)-B_x\delta(x_2) \\
z & 0 & 0 & -(B_x\delta(x_1)-B_x\delta(x_2)) & 0
\end{array}$$

which is not zero due to the presence of the Kronecker δ delta function which locates the fields at different positions. The spacetime stress-energy-momentum tensor T is then computed from the following equation

$$4\pi T^{\mu\nu}=F^{\mu\alpha}F^{\nu}_{\alpha}-\frac{1}{4}g^{\mu\nu}F_{\alpha\beta}F^{\alpha\beta}$$

where g is the metric tensor containing the coefficients of the elemental spacetime length ds. With the mass M and charge Q term equal to zero, there being just electromagnetic fields involved, the g metric tensor in cylindrical coordinates becomes

$$g_{\alpha\beta}=\begin{array}{c|cccc|}
t & -\left(1-\frac{2M}{r}+\frac{Q^2}{r^2}\right) & 0 & 0 & 0 \\
r\ \theta & 0 & \left(1-\frac{2M}{r}+\frac{Q^2}{r^2}\right)^{-1} & 0 & 0 \\
z & 0 & 0 & r^2 & 0 \\
 & 0 & 0 & 0 & 1
\end{array}$$

$$=\begin{vmatrix}-1&0&0&0\\0&1&0&0\\0&0&r^2&0\\0&0&0&1\end{vmatrix}$$

[0026] Referring to **FIG. 9**, the magnetic vortex generator has two concentric, thin, flat cylindrical silicon-iron cores (**13**,**14**), each consisting of a stack of three 0.020 inch thick transformer laminations wrapped with insulating tape. Using insulated magnetic wire, a flat helical coil (**16**) is wrapped counter-clockwise around the outer laminations. The coil receives power through connection (**15**). The winding then continues around the core until coil (**17**) where the wire (**18**) is extended to the inner core and the wrapping of coil (**19**) proceeds in the clockwise direction. The inner core wrapping terminates on coil (**20**) with the extension of the second power connection (**21**). Because the coils are wound in opposite directions, the generator produces two bucking magnetic fields at different radii (**22**,**23**).

[0027] According to Maxwell's electromagnetic equations, the curl of the magnetic flux density B field times the square of the speed of light squared is equal to the rate of change of the electric E field

$$c^2\nabla xB = \frac{\partial E}{\partial t}$$

Multiplying both sides by the elemental area of the core and integrating over the area

$$c^2\int_0^{r_0}\nabla xBdA = \frac{\partial}{\partial t}\int_0^{r_0}E\cdot ndA = \frac{\partial}{\partial t}\int_0^{r_0}E\cdot n2\pi rdr$$

The curl of the field can be converted into a line integral around the core contour using Stokes' Theorem

$$c^2\int_0^{r_0}\nabla xBdA = c^2\oint_{r_0}B\cdot ds = c^2\int_0^{2\pi}Br_0d\theta$$

[0028] The magnetic flux density B field oscillates with angular frequency ω

$B=B_0e^{I\omega t}$

Substituting this into the equation and integrating over time for the inner core field

$$-c^2\int_0^t\int_0^{2\pi}B_0e^{I\omega t}r_0d\theta = \int_0^{r_0}E2\pi rdr = E\pi r_0^2$$

This can be solved for the electric E field that is produced by the oscillating magnetic flux density B field

$$E_0 = \frac{2IB_0c^2(-1+e^{I\omega t})}{r_0\omega}$$

The electric field for the outer core is the same equation except that the opposite sign of the magnetic flux density B field and the radius r**1**

$$E_1 = \frac{-2IB_0c^2(-1+e^{I\omega t})}{r_1\omega}$$

Adding these two fields together is the total electric field E

$$E = E_0 + E_1 = \frac{-2B_0c^2(-1+\mathrm{Exp}(I\omega t))(r_0-r_1)}{r_0r_1\omega}$$

The electrostatic energy of the field is equal to half the linear capacitance of space times the summation over the volume of the dot product of the electric field with itself

$$U = \frac{\varepsilon}{2}\int E\cdot EdV$$

Because the electric field points in the z-direction out of the coil, the dot product is actually the square of the electric field.

[0029] Referring to **FIG. 10**, the energy U per volume is plotted as a function of time with a radius ratio r_1/r_0 of 3/1. As the graph shows, the magnetic vortex wormhole generator produces mostly negative energy which is required in order to create the wormholes. Because the stress-energy-momentum T tensor is also the square of the electric field, this graph gives the spacetime curvature pressure. Thus the electric field produces both the pressure and negative energy required to open up wormholes between space and hyperspace.

[0030] Going back to the effective potential equation,

$$V_{eff} = \frac{l(l+1)\hbar^2}{2mr^2} - \frac{e^2}{4\pi\varepsilon r}$$

it can be seen that the first term is divided by the mass of the particle. In current gravitation physics, the mass of the particle is invariant with velocity. It does not obey the Lorentz transformation. The mass is related to the energy E of the particle and its momentum p by

$m^2=E^2-p^2$

In different inertial frames moving with a relative velocity v, the energy and the momentum obey the Lorentz transformation, but no matter what the relative motion, the mass of the particle is constant. In the first term of the effective potential, the mass is constant which leaves just Planck's constant.

[0031] Having worked for over ten years on the subspace manifold, known as the tetrahedron diagram, I found a most incredible intersection on the diagram when working with the water molecule. The water molecule has two hydrogen atoms and one oxygen atom as mentioned previously. The atomic weight of one atom of hydrogen is 1.008 atomic weight units (awu). The atomic weight of oxygen is 16.000 awu. Therefore the molecular weight of water is

$$\text{Weight of two atoms of hydrogen } 2\times 1.008\ awu = 2.016\ awu$$

$$\text{Weight of one atom of oxygen } 1\times 16.000\ awu = \frac{16.000\ awu}{18.016\ awu}$$

The gram molecular weight is the atomic weight expressed in grams, so there are 18.016 grams in Avogadro's number of molecules. So the mass per molecule in logs is

$$\mathrm{Log}\left[\frac{18.016\ \mathrm{gram-mol}\Big/\left(1000\ \frac{\mathrm{gm}}{\mathrm{kg}}\right)}{6.02\times10^{23}\ \mathrm{mol}}\right] = -58.77103943$$

[0032] Referring to **FIG. 11**, the tetrahedron diagram plots the natural logarithm of mass versus the natural logarithm of wavelength. The reason for this is that mass times wavelength is equal to Planck's constant divided by the speed of light c, known on the diagram as the base constant. At the present time there are over 4000 diagrams which are copyrighted in the Library of Congress. In logarithms, the product of two numbers is the sum of the two numbers. This means that the sum of the mass and the wavelength are equal to the base constant which has a value of

$$\ln[m]+\ln[\lambda]=\ln[h/c]=-95.91546344=\text{base constant}$$

Our dimension has a lower limit on mass and length known respectively as the Planck mass and the Planck wavelength. The Planck mass is the linear mass Ω of the universe times the Planck scale Λ. The Planck wavelength is circumference of a circle of radius Planck scale. In terms of logs, the Planck mass and Planck wavelength are

$$\text{Planck mass}=\ln(\Omega\Lambda)=-17.64290101$$

$$\text{Planck wavelength}=\ln(2\pi\Lambda)=-78.27256243$$

[0033] When these values are plotted on the tetrahedron diagram shown in **FIG. 11**, the Planck box (abcd) is formed which are the boundaries of our dimension in subspace. The line numbering is as follows

Planck mass	25, 27
Planck wavelength	26, 28
mass of water molecule	29, 31
speed of light squared circle	30
base constant	33
inverted tetrahedrons	34, 35
centerline	36

The energy of the water molecule, circle (**37**), is equal to the sum of the water molecule mass (**29**) plus the speed of light squared circle (**30**). The energy circle (**37**) intersects the mass of the water molecule (**29**) at the Planck wavelength (**28**, point e), which is the boundary between space and hyperspace. What this means is that the mass is equal to the energy at the Planck box boundary. The only way that this is possible is if the speed of light c is equal to one meter per second

$$E=m\ c^2=m\ c=1\ \text{meter/second}$$

A water molecule traversing a wormhole into hyperspace undergoes a change in the speed of light from 299792458 m/s to 1 m/s.

[0034] Planck's constant $\hbar$ is equal to the Planck mass ΩΛ times the Planck scale Λ times the speed of light c.

$$\hbar=\Omega\Lambda\Lambda c$$

By having the speed of light go to 1 m/s, the orbital term in the effective potential V_{eff} is reduced by a factor of the speed of light squared equal to 9×10^{16}. This unbalances the equation to such an extent that only the Coulomb potential term remains.

$$\frac{l(l+1)\hbar^2}{2mr^2} \ll \text{coulomb term}$$

The electron is attracted to the proton nucleus because the centrifugal term no longer provides a stable orbit for the electron. Thus the atomic binding is destroyed and the water molecule becomes soft as putty.

[0035] Referring to **FIG. 12**, the collision of the electron with the proton together with the enormous change in the proton's energy causes the proton p to become unstable and decay. According to the Standard Model of particle physics, the elementary particles are composed of smaller particles known as quarks. The six quarks have been named up u, down d, strange s, charm c, top t, and bottom b. The subscript on the quark indicates one of three colors {red r, blue b, green g). As shown in the diagram, the proton is composed of three quarks $\{u_r, u_g, d_b\}$, two of which are up quarks of which one is red and the other green, and a third blue down quark. The proton p decays into a positron e^+ which is an electron with a positive charge, and a neutrally-charged pion π^0 particle through the exchange of an X boson particle. The pion has a mass between the electron and the proton.

$$p\rightarrow\pi^0+e^+$$

[0036] Referring to **FIG. 13**, the pion π^0 then decays into a proton p and antiproton $\bar{p}$ which annihilate each other to produce two photons shown on the right by the traveling waves. So the overall energy exchange is

$$p \rightarrow \frac{2hv}{c^2} + e^+$$

where hv is the energy per gamma photon with frequency v. The electron of the hydrogen atom would then annihilate the positron for additional photon energy.

[0037] Referring to **FIG. 14**, the hydrogen H atom is composed (**38**) of the proton and electron as seen in the upper left corner. The proton decays (**39**) into the neutral pion and a positron. The electron from the hydrogen atom and this positron form one electron pair (**40**). The pion then decays (**41**) into two gamma photons which produce an electron pair production energy cascade into 132 pairs (**42**,**43**) for a total of 133 electron pairs. These electrons can then be captured electrostatically and used for the production of electricity.

[0038] Referring to **FIG. 15**, the electrons are captured with the water droplet injector . The plunger (**46**) of a spring-loaded cylindrical solenoid (**44**) is attached to a tapered piston (**47**). By means of ring collar and bolts (**45**), the solenoid is bolted to the injector (**48**). A supply of purified water is attached to the water inlet connection (**49**). When the solenoid is activated, it pulls back slightly so that water can enter the valve. When the solenoid is deactivated, the piston forces the water droplet out through the nozzle (**50**) into a cylindrical glass vacuum chamber (**52**). Two cylindrical glass disks (**51**) hold the nozzle in place. On the other end of the vacuum chamber is the sealed-tube connection (**56**,**57**,**58**) to the vacuum pump. In the middle of the vacuum chamber, two metal plates (**53**) are attached through sealed glass collars (**54**) to electrical pins (**55**). The plates are electrostatically-charged with opposite charges so as to form a capacitor. This creates an electrical field between the plates which attracts the electrons to the positively-charged plate.

[0039] Referring to **FIG. 16**, the vacuum tube and water injector (**61**) are mounted along the centerline of the inner (**60**) and outer (**59**) magnetic vortex wormhole generator coils. The low density hyperspace energy traversing the wormhole along the centerline of the coils causes the injected water molecules to soften and decay into a cascade of electrons. The oscillating electric field along the centerline causes the electrons to vibrate back and forth. The crossed electric field between the charged capacitor plates causes the electrons to flow toward the positively-charge plate in order to produce electricity.

[0040] Referring to **FIG. 17**, the vacuum tube is connected to the vacuum pump through a hose connection to the pump air inlet (**64**). A 5 Hp electric motor (**62**) drives dual rotating flights of screws which trap the air and move it toward the exhaust outlet (**65**) shown with no muffler. On a spacecraft operating in the vacuum of outer space, this component would not be needed.

SUMMARY OF THE INVENTION

[0041] It is the object of this invention to generate electricity by using low density hyperspace energy to soften water molecules such that the atomic binding is broken which causes the hydrogen nucleus to decay into a cascade of electron pairs. These electrons are then collected on a positively-charged plate in order to produce electricity. The water molecules are softened by flooding them with low density hyperspace energy that is produced by a magnetic vortex wormhole generator. The generator creates negative energy and a spacetime curvature along the centerline of two concentric coils. This combination opens up wormholes along the centerline. Because the gravitational potential of low density hyperspace energy is greater than the negative energy, the hyperspace energy flows through the wormhole from hyperspace into our dimension. The hyperspace energy has a speed of light equal to one meter/second. This causes a change in Planck's constant h such that the proton orbitals of the hydrogen atom are unable to produce a centrifugal repulsion which keeps the electron in orbit. The Coulomb potential term dominates and the electron is attracted to the proton. Due to the vast change in the speed of light, and the collision of the electron with the proton, the proton becomes unstable and decays into a neutral pion and a positron. The pion then decays into two gamma photons which produce a large cascade of electron pairs.

[0042] A water injector, consisting of a solenoid-activated valve and nozzle, injects water droplets into a vacuum chamber which is positioned along the centerline of the two concentric coils where the wormholes form. Due to the low density hyperspace energy passing through the wormholes into our dimension, the water molecules soften and decay into electrons which are collected on an electrostatically-charged capacitor plate having a positive charge located in the glass vacuum chamber.

A BRIEF DESCRIPTION OF THE DRAWINGS

[0043] **FIG. 1**. Perspective view of hydrogen atom K shell.

[0044] **FIG. 2**. Graph showing potential binding energy of hydrogen atom.

[0045] **FIG. 3**. Perceptive view of Olympus Mons volcano at +19.5° Mars latitude.

[0046] **FIG. 4**. Perspective view of tetrahedron inscribed in sphere.

[0047] **FIG. 5**. Graph showing complex plane.

[0048] **FIG. 6**. Perspective view of hyperspace co-dimensions of logarithmic manifold.

[0049] **FIG. 7**. Perspective view of embedding diagram showing curvature of space caused by a mass.

[0050] **FIG. 8**. Perspective view of wormhole embedding diagram.

[0051] **FIG. 9**. Perspective view of coils of magnetic vortex wormhole generator.

[0052] **FIG. 10**. Graph showing that generator produces negative energy.

[0053] **FIG. 11**. Tetrahedron diagram showing that the speed of light at the Planck box boundary at the water molecule is one meter/second.

[0054] **FIG. 12**. Perspective view of proton decay into neutral pion and positron.

[0055] **FIG. 13**. Perspective view of pion decaying into two gamma photons.

[0056] **FIG. 14**. Diagram showing decay of the hydrogen atom into electrons.

[0057] **FIG. 15**. Perspective view of water injector and vacuum chamber.

[0058] **FIG. 16**. Perspective view of vacuum chamber mounted along centerline of magnetic vortex wormhole generator.

[0059] **FIG. 17**. Perspective view of vacuum pump used to evacuate vacuum chamber.

DETAILED DESCRIPTION OF THE INVENTION

[0060] 1. The coils of the magnetic vortex wormhole generator are made of three stacks of 0.020 inch silicon-iron transformer laminates. These are washed to remove the oil, and then wrapped with insulating tape in order to keep the laminations together. Using a very long bench made of wooden planks and 2×4 sawhorses, the outer coil is wrapped counter-clockwise right to left using a large spool of 14 AWG magnetic wire. A thin spacer is used between windings in order to reduce the winding capacitance. Once the outer coil is wound, the wire is continued to the second inner coil which is wrapped clockwise, leaving enough wire between coils such that when the coils are mounted in the wooden frame, the coil is one continuous winding having an input and output connection. Using an inductance meter, the inductance of the coil is measured. Using a standard frequency of 60 Hz, the capacitance of a sheet metal capacitor is calculated such that the generator is electromagnetically resonant at this frequency. The generator is connected to the line voltage by a 1:1 isolation transformer which is connected to a small primary coil wrapped on a toroidal core whose similar secondary coil is connected to the sheet metal capacitor and inductance coil. Resonance is achieved by adjusting the spacing and overlap of the sheet metal.

[0061] 2. The vacuum chamber is made of a glass tube with sufficient wall thickness to withstand the vacuum pressure. A number of glass blowing techniques are used to make the glass-electrode connection for the capacitor plates. Then circular pieces of glass plate are cut out and ground to the inside diameter of the tube, fitted with the nozzle and vacuum connection, and then heat sealed to the chamber. The chamber and water injector are then attached to a wooden bracket mounting which is doweled and glued to the wooden frame of the generator.

I claim:

1. A water energy generator system comprising the components:

a magnetic vortex wormhole generator and driving resonant electrical circuit;

a water droplet injector;

a vacuum chamber and vacuum pump; and

an electrostatic electron capture system.

2. By means of claim (**1**), a magnetic vortex wormhole generator comprising two concentric cylindrical coils of different radii wound in opposite directions, made of thin sheet silicon-iron transformer laminations wound with one continuous length of magnetic wire providing a single input and single output connection to the driving electrical circuit.

3. By means of claim (**2**), a coil winding method and oscillating driving circuit producing bucking electric fields along the centerline of the generator normal to the coils which create a spacetime curvature pressure and negative energy.

4. By means of claim (**3**), the generation of wormholes between space and hyperspace along the centerline of the generator such that low density, low speed of light hyperspace energy flows through a positive gravitational gradient from hyperspace to space.

5. By means of claim (**1**), a water injector comprising a solenoid-activated water valve, water supply connection, seal and nozzle for injecting water droplets into the vacuum chamber.

6. By means of claims (**5**) and (**4**), the softening and particle decay of the water molecules by the hyperspace energy into neutral pions, positrons, gamma photons and finally a cascade of electron pairs.

7. By means of claims (**6**) and (**1**), the capture of the electrons on electrostatically charged capacitor plates located in the vacuum chamber for the purpose of producing electrical energy.

8. By means of claims (**1**) and (**2**), a resonant electrical driving circuit comprising a line isolation transformer connected to a primary coil wound on a toroidal coil whose secondary output coil is connected to a capacitor and the inductance coil of the generator such that the capacitance of the capacitor and the inductance of the coil form a highly resonant electrical circuit.

* * * * *

US 20060168937A1

(19) **United States**
(12) **Patent Application Publication**
St. Clair
(10) **Pub. No.: US 2006/0168937 A1**
(43) **Pub. Date: Aug. 3, 2006**

(54) MAGNETIC MONOPOLE SPACECRAFT

(76) Inventor: **John Quincy St. Clair**, San Juan, PR (US)

Correspondence Address:
JOHN ST. CLAIR
52 KINGS COURT, 4A
SAN JUAN, PR 00911 (US)

(21) Appl. No.: **11/048,026**

(22) Filed: **Jan. 31, 2005**

Publication Classification

(51) **Int. Cl.**
F03H 1/00 (2006.01)
(52) **U.S. Cl.** **60/203.1**

(57) **ABSTRACT**

A spacecraft propulsion system that utilizes a dual method of providing lift on the hull by means of magnetic monopoles and electromagnetic spacetime curvature pressure.



Figure 1



Figure 2



Figure 3


-220
-210
-200
-190
-180
-170
-160
-150
-140
-130
-120
-110
-100
-90
-80
-70
-60
-50
-40
-30
-20
-10
ln(mass)
-10 -20 -30 -40 -50 -60 -70 -80 -90 -100 -110 -120 -130 -140 -150 -160 -170 -180 -190
ln(wavelength)
6
a
5
4
7

Figure 4



Figure 5


m=0
m=1
m=2
i (θ + 2πm)

Figure 6



Figure 7



Figure 8



Figure 9



Figure 10


m=0
m=1
15
20
14
19
18
17
16
13b
13a

Figure 11



Figure 12



Figure 13



Figure 14



Figure 15


34
33
30
31
32
35

Figure 16


B
B
36
τ=μxB
37
B
μ

Figure 17



Figure 18



MAGNETIC MONOPOLE SPACECRAFT

BRIEF SUMMARY OF THE INVENTION

[0001] This invention is a spacecraft propulsion system that generates a field of wormholes which are threaded with a magnetic field. Acting as two attracting magnets, the spacecraft's north magnetic field is attracted to the constantly regenerating south magnetic monopoles of the wormholes which provides lift on the hull.

BACKGROUND OF THE INVENTION

[0002] According to one of Maxwell's electromagnetic equations, the curl of the electric E field is equal to the negative time rate of change of the magnetic flux density B field.

$$\overline{V} \times E = -\frac{\partial B}{\partial t}$$

The curl can be thought of as a circulation around a closed loop specified by the right-hand rule where the fingers curl in the direction of the electric field and the thumb represents the changing magnetic flux density field through the area of the loop. At no time is the electric field diverging around the loop. That is, the divergence of the curl is zero which is a well-known vector operation

$$div\ \mathrm{curl}E = \frac{\partial}{\partial t}(divB) = 0$$

The partial derivatives of divB are zero at all points in space. Performing the integration, therefore, the divergence of B is equal to a constant

div B=constant

[0003] Referring to **FIG. 1**, the following discussion is made in cylindrical coordinates {r,θ,z}. In cylindrical coordinates, the divergence of the radial B field, div B, is equal to a constant C

$$Br'[r] + \frac{Br[r]}{r} = C$$

where the prime (') represents differentiation with respect to the radius r. The solution to this equation resides in determining the constant C. In the vacuum of space without any wormholes, the constant C is zero. Because the spacecraft is surrounded by a field of wormholes, there is a magnetic flux density field threading each one. That is, each wormhole is actually a magnetic monopole, and therefore the entire field of monopoles constitutes a large magnet with one pole in this dimension and the other pole in the hyperspace dimension.

[0004] The concept of the wormhole involves a new type of scientific thinking involving the creation of a gateway between our spacetime and that of a hyperspace co-dimension. The gateway is created electromagnetically as shown by my patent applications Rotating Magnetic Vortex Generator, Magnetic Vortex Wormhole Generator, and Sulfur 8 Wormhole Generator. The gateway can also be created ultrasonically through bubble cavitation as shown in my patent application Cavitating Oil Hyperspace Energy Generator. In one experiment, smoke was blown through one side of the coil of the magnetic vortex wormhole generator and no smoke came out the other side. The smoke was blown through the wormhole into another dimension.

[0005] The existence of hyperspace is not generally known in the scientific community. The reason it exists can be thought of in the following manner. Referring to **FIG. 2**, the corners of a tetrahedron (**2**) circumscribed by a sphere (**1**) touch the sphere at an angle (**3**) of −19.47°. Looking at the planets of the solar system, the Giant Red Spot vortex of Jupiter, which can hold two planets the size of Earth, is located at this angle. On Mars, the Olympic Mons volcano, which is the size of France, is located at north 19.5° Here in the Caribbean there is a slow moving rock mantle vortex at north 19.5° that curves the islands down toward Venezuela. So the geometry of space is related to the tetrahedron. What this suggests is that there is a subspace manifold whose tetrahedral geometry projects all the constants of physics into our dimension.

[0006] Referring to **FIG. 3**, this subspace geometry is shown in the tetrahedron diagram which plots the natural logarithm of mass on the vertical axis versus the natural logarithm of wavelength on the horizontal axis. With this diagram, it is possible to visualize the entire universe on a single sheet of paper. Triangle (**4**) is the tetrahedron whose vertical centerline shown by the small π circle (a) is equal to Planck's constant h divided by the speed of light c, known as the base constant. The base constant in logs is equal to −95.91546344. Line (**5**) is the diameter of the sphere (**6**). A circle (**7**), centered on (a), with a radius equal to the speed of light squared, is tangent to the tetrahedron. It can be shown that all the constants of physics, such as the speed of light squared and the Planck mass and the Planck wavelength, are determined geometrically by this logarithmic subspace tetrahedral geometry.

[0007] Referring to **FIG. 4**, the complex plane consists of a real horizontal axis, and a complex vertical axis where the value of the complex number z is given by a radius r and an angle θ

$$z=re^{i(\theta+2\pi m)}$$

The logarithm of z is

$$\mathrm{Log}[z]=\mathrm{Log}[r]+i(\theta+2\pi m)$$

where m is an integer m=0,1,2 . . . corresponding to multiple rotations of 2π. What this means in terms of the tetrahedron diagram, referring to **FIG. 5**, is that there are multiple diagrams separated by 2π rotations. Each multiple is another hyperspace dimension. Only the log manifold has this characteristic. Referring to **FIG. 6**, the hyperspace dimension, shown as 2π circular surface (**8**), has a cut (**9**) on the undefined Log[0] origin line such that another hyperspace dimension is created below it (**10**).

[0008] Referring to **FIG. 7**, this branch cut does not bring one back to the original surface nearing the origin. It takes one down to another level of the universe into another hyperspace dimension. I can attest personally that I have been able to look into another hyperspace co-dimension as well as jump into another dimension.

[0009] Furthermore, Dr. Stephen Hawking of Cambridge University has shown that our dimension is connected to a wormhole through complex time. That is, the hyperspace dimension is rotated forward by 90° which makes it orthogonal to us. While this is the mathematical explanation as to why there are hyperspace co-dimensions, I can attest personally to the fact, as described in my patent application Full Body Teleportation, that I was teleported through hyperspace and returned to our dimension over a distance of 100 meters. Because hyperspace exists, it is then possible, using electromagnetic fields, to open wormholes between our dimension and other hyperspace dimensions.

[0010] Referring to **FIG. 8**, the constant C in the magnetic flux density B field equation is determined as follows. The end of a solenoid (**11**) is equivalent to a local magnetic source of flux Φ which represents the wormhole. A charge (**12**) encircling the solenoid has the same value at P_1 and P_2 but there is a phase difference of 2 π n where n is an integer equal to the number of times the charge encircles the solenoid. The change in phase is equal to the charge q divided by Planck's reduced constant times the flux for a solenoid of radius r=R

$$\Delta\theta = 2\pi n = \frac{q}{\hbar}\Phi = \frac{q}{\hbar}B\pi R^2$$

Solving for the magnetic flux density field threading the wormhole

$$B = \frac{2\pi nh}{q\pi R^2}$$

The differential equation becomes

$$Br'[r] + \frac{Br[r]}{r} = C[2]$$

Solving the equation for the radial field Br

$$Br[r] = \frac{C[2]r}{2} + \frac{C[1]}{r}$$

Equating this Br field with the B field and solving for the C[2] constant

$$C[2] = \frac{-2[-2\hbar n + qrC[1]]}{qr^2}$$

Substituting for C[2], the C[1] constant drops out and therefore the wormhole magnetic flux density field becomes a constant inside the throat radius R

$$Br = \frac{2hn}{qR^2}$$

but the divergence moving from outside to inside the radius is a constant due to the discontinuity.

[0011] Referring to **FIG. 9**, the wormhole has a constant cylindrically-shaped magnetic field of radius R with a negative south pole due to the negative charge on the electron, Using a wormhole radius equal to one hundred times the electron radius with n equal to 10 turns, the magnetic flux density B field has a magnitude of 1.4×10^6 tesla.

[0012] Referring to **FIG. 10**, the wormhole surface (**14**) is a connection through a throat area (**20**) between space and hyperspace (**13**) to another surface in hyperspace (**15**). The electron path (**19**) is actually spiraling down the surface of the wormhole. The magnetic flux density field (**18**) points into the wormhole such that the cross product of the electron velocity (**16**) with the field (v×B) points toward the outside rim of the wormhole. Because the electron has a negative charge, the force (**17**) on the electron (−q v×B) is inward toward the centerline of the wormhole. Since one pole of the field is in space, and the other pole is in hyperspace, the wormhole appears to us as a magnetic monopole. The key to this invention is how to generate this magnetic wormhole field.

[0013] Referring to **FIG. 11**, the aluminum spacecraft is constructed of a flattened, shallow spherical lower hull (**21**), a circular upper hull with a flat sloping surface (**22**), a spherical dome cupola (**23**), and a cylindrical section (**24**) housing a circular array of radial microwave waveguides. Surfaces (**22**) and (**23**) are electrically charged, using high-voltage transformers, to an alternating electrostatic potential such that the potential on the dome is +V when the sloping hull has a −V potential and vice versa. This creates an electric field from the positively charged surface to the negatively charged surface.

[0014] Referring to **FIG. 12**, the dome (**25**) is charged to a positive potential. The spherical potential lines (**26**) emanate from the dome and curve around toward the sloping hull. The negative gradient of this potential field is the electric E field (**27**) which is perpendicular to the potential lines. The electric field lines from the dome then terminate on the sloping hull which can be seen in the lower right hand comer of the graph.

[0015] Looking down from above at the top of the dome, referring to **FIG. 13**, the oscillating electric field generates a circular oscillating magnetic field around the hull at various elevations. The last two graphs in the right-hand comer are near the top of the dome as seen by the smaller radius contour lines.

[0016] Referring to **FIG. 14**, the oscillating electric field lines (**28**) are between the dome and the sloping hull. The oscillating magnetic field (**29**) encircles the hull at the level of the microwave waveguides.

[0017] From gravitation physics, it is known that negative energy is required to open up the throat of the wormhole. In terms of differential forms mathematics, the negative energy is created by wedging the magnetic field with the radial microwave beams of the waveguides. This generates an increasing time rate of change of negative energy ρ as shown by

$$*d(B^{\wedge}(B_{wave}+E_{wave}dt))=\frac{\partial(-\rho)}{\partial t}$$

where (*) is the Hodge Star operator, (d) the differential operator and (^) the wedge operator which joins the circular magnetic flux density B field with the electromagnetic wave (B_{wave}, E_{wave}).

[0018] Referring to **FIG. 15**, the interaction of the circular magnetic field (**33**), generated by the oscillating electric field (**34**), interacts with the radial electromagnetic field of the microwave beams (**31**) of the waveguides (**30**) to generate negative energy (**32**) over the sloping hull (**35**).

[0019] This combination of fields also creates the wormhole field over the hull. The spacetime curvature pressure T in the vertical z-direction is equal to the square of the circular magnetic flux density field

$$T^{zz}=\frac{B^2}{8\pi}$$

This stress-energy-momentum tensor can be thought of as a spacetime curvature proportional to the inverse of the radius squared, or as a pressure term which acts on the surface area of the hull. Thus there is the combination of a pressure stress and negative energy which creates the wormhole field over the sloping hull. Even though the magnetic flux density B field is oscillating, it is the square of the field which creates the stress. Thus the tension is still in the positive vertical z-direction.

[0020] Due to the low speed of light of hyperspace, the hyperspace energy is low density. Thus there is a positive gravitational potential between hyperspace and our dimension such that the hyperspace energy flows through the wormholes and onto the hull of the spacecraft. When this happens, a white mist forms over the hull. The effect of the hyperspace energy is to lessen the mass of the spacecraft, and relativistically increase the strength of the electromagnetic fields due to the smaller speed of light.

[0021] Referring to **FIG. 16**, the circular magnetic flux density field (**36**) is interacting with the magnetic monopole (**37**). The monopole acts as one pole of a magnet and therefore has a magnetic moment equal to the area times the electrical current circulating through it as the electrons move from our dimension into hyperspace. The great physicist Maxwell (**1870**) pointed out that the energy associated with charges and poles is potential energy and that therefore these objects tend to move in a direction that will decrease the potential energy, similar to a brick sliding down an inclined plane. Now to reduce the potential energy is the same as to reduce the field which gives a measure of the potential energy. If two like charges are brought together they strengthen one another's field, while opposite charges reduce one another's field. Thus like charges repel and unlike ones attract.

[0022] However, the energy associated with electric currents is not potential but kinetic in origin, because it is associated with moving charges. Now in mechanics it is well known that bodies move in a direction to increase their kinetic energy, if there is a source of external energy. The magnetic field of currents is a measure of kinetic energy and currents will try to move in a direction that will increase the field. Thus similarly-directed currents attract and unlike currents repel. In **FIG. 16**, the monopole will act so as to increase the field of the circular magnetic B field generated by the spacecraft. The monopole will then rotate into alignment with the flux tube. This increases the field strength of the flux tube. There is a torque τ on the monopole equal to the cross product of the magnetic moment with the B field

$$\tau=\mu\times B$$

[0023] Referring to **FIG. 17**, when the monopole is aligned with the flux tube, the cross product is zero and there is zero torque on the monopole. Notice that even if the oscillating B field points in the opposite direction, there is still zero torque since the torque depends on the sine of the angle between them. The sin(0°) or sin(180°) is the same zero value. With the monopole aligned with the flux tube, the kinetic energy is now maximized. That is, both the flux tube and the monopole point in the θ-direction.

[0024] The magnetic B field can be represented as a vector having three components. The only component is in the angular direction

$$B=\{B_r,B_\theta,B_z\}=\{0,\ \mathrm{B}_\theta(z),\ 0\}$$

where the field varies, as was seen in **FIG. 13**, in the vertical z-direction. The magnetic monopole field also points in the θ-direction

$$\mu=\{0,\mu_\theta(z),0\}$$

where there is a negative gradient of the monopole field in the z-direction due to the location of the microwave waveguides near the sloping hull.

[0025] The force F on the monopole is the gradient of the monopole's magnetic moment μ with the magnetic flux density B field

$$F=\nabla(\mu\cdot B)=\{0,\ 0,\ \mu_\theta\ B_\theta'(z)+B_\theta(z)\mu_\theta'(z)\}$$

which says that there is a force on the monopole in the z-direction equal to the magnetic moment times the gradient of the magnetic field in the z-direction plus the magnetic field times the gradient of the magnetic moment in the z-direction.

[0026] Referring to **FIG. 18**. differentiating the magnetic field in the z-direction shows that the gradient is negative outside the hull. This can also be seen visually in **FIG. 13** where the graphs decrease in intensity.

[0027] A negative gradient for both the magnetic moment and the field means that the force on the monopole is negative. The force on the tube connected to the hull is therefore the negative of a negative, yielding a positive lift force.

$$F_{monopole}=-\{0,\ 0,|\mu_\theta B_\theta'(z)+B_\theta(z)\mu_\theta'(z)|\}=-F_{tube}$$

$$F_{tube}=+\{0,\ 0,|\mu_\theta B_\theta'(z)+B_\theta(z)\mu_\theta'(z)|\}$$

which says there is an upward lift force on the hull due to the combination magnetic monopole and flux tube. This lift force is in addition to the vertical lift force generated by the spacetime curvature created by the electromagnetic fields themselves.

SUMMARY OF THE INVENTION

[0028] This invention is a spacecraft propulsion system that utilizes electromagnetic fields and microwaves to generate negative energy and a spacetime curvature over the hull. The hull consists of a hemispherical dome, a circular array of radial microwave waveguides, a sloping flat hull, and a shallow spherical hull on the bottom. Alternating current high voltage transformers connected to the dome and the sloping hull generate a curving oscillating electric field between the dome and the sloping hull. Due to this oscillation, a horizontal circular oscillating magnetic flux density B field is created around the dome.

[0029] By firing the microwaves at right angles to the B field, negative energy is created over the hull. The negative energy and spacetime curvature pressure generate wormholes between space and hyperspace. Because hyperspace has a low speed of light and positive gravitational potential, low density hyperspace energy flows through the wormholes and onto the hull. The effect of the hyperspace energy is to lessen the mass of the vehicle and to increase the strength of the electromagnetic fields. Because the resistance of hyperspace is less than the resistance of space, electrons spiral down the wormholes into hyperspace. This creates a magnetic field through the wormhole with one pole in our dimension and the other pole in hyperspace. Thus a field of magnetic monopoles is created over the hull.

[0030] The magnetic monopoles, which represent kinetic energy, align themselves with the magnetic flux tubes in order to maximize the total magnetic field. Because there is a gradient of the monopoles and field in the vertical direction, a negative force develops on the monopoles equal to the gradient of the dot product of the magnetic moment of the monopole with the B field. Thus the opposite reaction is a positive force on the flux tubes attached to the hull which is equivalent to bringing the north pole of a magnet together with the south pole of a second magnet. Because the hull constantly regenerates the wormhole field, the hull experiences a constant upward lift force. This is in addition to the lift generated by the spacetime curvature pressure which is proportional to the square of the magnetic flux density B field.

A BRIEF DESCRIPTION OF THE DRAWINGS

[0031] **FIG. 1**. Perspective view of cylindrical coordinate system $\{r, \theta, z\}$.

[0032] **FIG. 2**. Perspective view of tetrahedron circumscribed by sphere.

[0033] **FIG. 3**. Tetrahedron diagram showing speed of light squared is determined by the tetrahedron.

[0034] **FIG. 4**. Complex number z representation in the complex plane.

[0035] **FIG. 5**. Perspective view showing multiple log manifold hyperspace dimensions.

[0036] **FIG. 6**. Perspective view of orthogonal hyperspace dimensions.

[0037] **FIG. 7**. Perspective view of Log[z] showing cut along origin.

[0038] **FIG. 8**. Perspective view of charge phase shift around a magnetic flux.

[0039] **FIG. 9**. Perspective view of wormhole magnetic flux density B field.

[0040] **FIG. 10**. Perspective view of magnetic monopole wormhole.

[0041] **FIG. 11**. Perspective view of spacecraft.

[0042] **FIG. 12**. Graph showing electrostatic potential and electric field over dome.

[0043] **FIG. 13**. Animation showing circular magnetic field around dome at increasing elevation.

[0044] **FIG. 14**. Perspective view of electric and magnetic fields around hull.

[0045] **FIG. 15**. Perspective view of generation of negative energy.

[0046] **FIG. 16**. Perspective view of monopole misaligned with flux tube with torque.

[0047] **FIG. 17**. Perspective view of monopole aligned with flux tube at zero torque.

[0048] **FIG. 18**. Graph showing negative gradient of flux tube in the z-direction.

DETAILED DESCRIPTION OF THE INVENTION

[0049] 1. The aluminum hull is made by a technique called stretch forming which uses hydraulic cylinders to stretch a large sheet of aluminum to its yield point. This makes the aluminum sheet soft and pliable. Using a die which has been CNC machined to the desired hull profile, the sheet is then die pressed into a very rigid, smooth and lightweight structure requiring no other support. There are actually three dies consisting of a spherical dome, sloping hull, and shallow spherical dome.

[0050] 2. The rest of the hull consists of a cylindrical hull with a radius equal to the upper dome. A segment of this hull is designed on a 3D computer graphics program and stored as a stereolithography *.stl file. The file is then transmitted over the Internet to a server who prints up the part on an xy-plotter with an ultraviolet laser and ultraviolet light sensitive polymer bath. The computer model is sliced by a special program into many thousands of slices which are printed one over the other until the part is completed. The server returns the part next day by Express Mail. Several parts are then molded using liquid plastic such as to form the complete ring. A sand mold is then constructed from all the molds to form a plastic cylindrical hull having the waveguide slots molded into it. The waveguide silver-coated aluminum boxes are then installed in the slots and connected to the frequency generators and amplifiers. The purpose of the plastic waveguide cylinder is to separate the electrostatic charges on the dome and the sloping hull In this particular case we used a dome from another spacecraft design which saved on the cost of the die.

I claim:

1. A spacecraft propulsion system consisting of the following components:

- a lower hull made of aluminum sheet having a shallow spherical profile;
- a circular flat sloping hull made of aluminum sheet attached to the top of the lower hull on the periphery;
- an electrically-insulated plastic-molded tubular cylindrical hull containing slots for mounting an array of radial microwave waveguides, attached to top of the flat sloping hull;
- a hemispherical cupola in the shape of a dome made of aluminum sheet mounted on top of the insulated cylindrical hull;
- an array of rectangular microwave waveguides mounted in the waveguide slots of the cylindrical hull;
- a high-voltage alternating current transformer with one side electrically attached to the upper dome and the other side electrically attached to the flat sloping hull; and
- a frequency generator and amplifier to drive the microwave waveguides.

2. By means of claim (**1**), an oscillating electric field is created between the upper dome and the sloping hull using the high-voltage alternating current transformer.

3. By means of claim (**2**), an oscillating circular magnetic flux density field is generated around the sloping hull and upper dome.

4. By means of claims (**1**) and (**3**), negative energy is generated by the radial microwave beams of the waveguide array impinging on the circular magnetic flux density field around the hull.

5. By means of claim (**3**), a positive spacetime curvature pressure constituting a lift force is developed over the hull in the vertical direction proportional to the square of the field.

6. By means of claims (**4**) and (**5**), a field of wormholes between space and hyperspace are generated over the hull.

7. By means of claim (**6**), due to the positive gravitational potential between hyperspace and space, low-density hyperspace energy flows through the wormholes onto the hull to reduce the mass of the spacecraft and strengthen relativistically the electromagnetic fields.

8. By means of claim (**6**), electrons, emitted by the charged hulls, spiraling down the wormholes, generate a field of magnetic monopoles with one pole in space and the other in hyperspace.

9. By means of claims (**6**) and (**3**), the magnetic monopoles maximize their kinetic field energy by aligning with the magnetic flux tube.

10. By means of claim (**9**), the gradient in the vertical direction of the dot product of the magnetic moments of the monopoles with the magnetic flux density field is a negative force on the monopoles and an equal but opposite positive lift force on the magnetic flux tubes attached to hull.

11. By means of claims (**10**) and (**5**), a dual method of providing apositive lift force on the spacecraft is constituted.

* * * * *

US 20060073976A1

(19) **United States**
(12) **Patent Application Publication**
Pohlman
(10) **Pub. No.: US 2006/0073976 A1**
(43) **Pub. Date: Apr. 6, 2006**

(54) **METHOD OF GRAVITY DISTORTION AND TIME DISPLACEMENT**

(76) Inventor: **Marlin B. Pohlman**, Tulsa, OK (US)

Correspondence Address:
STITES & HARBISON PLLC
1199 NORTH FAIRFAX STREET
SUITE 900
ALEXANDRIA, VA 22314 (US)

(21) Appl. No.: **10/954,767**

(22) Filed: **Oct. 1, 2004**

Publication Classification

(51) **Int. Cl.**

F16C	***39/06***	(2006.01)
G01V	***7/00***	(2006.01)
G09B	***23/06***	(2006.01)
F41B	***6/00***	(2006.01)
H01S	***3/09***	(2006.01)

(52) **U.S. Cl.** .... **505/166**; 505/180; 434/300; 73/382 G; 505/164

(57) **ABSTRACT**

A method for employing sinusoidal oscillations of electrical bombardment on the surface of one Kerr type singularity in close proximity to a second Kerr type singularity in such a method to take advantage of the Lense-Thirring effect, to simulate the effect of two point masses on nearly radial orbits in a 2+1 dimensional anti-de Sitter space resulting in creation of circular timelike geodesics conforming to the van Stockum under the Van Den Broeck modification of the Alcubierre geometry (Van Den Broeck 1999) permitting topology change from one spacelike boundary to the other in accordance with Geroch's theorem (Geroch 1967) which results in a method for the formation of Godel-type geodesically complete spacetime envelopes complete with closed timelike curves.




10
11
9
7
8
1
2
4
5
3
6
12
+
-

Figure 1


This area is not to scale
①
②
③
④
⑤
⑥
⑦
⑧
⑨
10
11
12

Figure 2

METHOD OF GRAVITY DISTORTION AND TIME DISPLACEMENT

FIELD OF THE INVENTION

[0001] The present invention relates to the use of technical time displacement devices, which operate by the modification of gravitational fields. These drive systems do not depend on the emission of matter to create thrust to take advantage of time dilation, but rather create a change in the curvature of space-time, in accordance with general relativity. This allows travel across topologies by warping space-time, to produce a topology change from one spacelike boundary to the other in accordance with Geroch's theorem (Geroch 1967)

THEORETICAL BACKGROUND OF THE INVENTION

[0002] The concept of gravity should be examined in the light of quantum gravity and in turn as a component of quantum physics itself. The fundamental minimal quantum of energy in quantum physics is Planck's constant; h. Thus in accordance with the energy equivalence formula $E=mc^2$, the fundamental minimum quantity of mass (m_q) can therefore be derived, from known constants by; $m_q=h/c^2$ (1). Taking this minimal mass, it is possible to show that the formation of all matter, the forces of nature and indeed space-time itself derive from this single quintessential quantity.

[0003] Thus if the number of quintessences in a system is; $n_q=m/m_q$: then the total Energy of the system is more logically given by, the energy of a single quintessence (h); directly multiplied by the number of quintessences (n_q) in that system, thus

$$E=hn_q=mc^2 \tag{1 a}$$

[0004] Furthermore, this minimal mass, termed quintessence, can form the basis of the existence of a quantum gravitational field in the form of a space-time lattice, from which quantum gravity may be derived from first principles. Furthermore, the conglomeration of these quintessences also accounts for the formation of the elementary particles and the forces acting between them, as in superstring theory. This concept explains the formation of matter and the forces of nature on a quantum mechanical basis and directly explains the existence of wave particle duality. Thus as $n_q=m/m_q$; the frequency of light and matter (f) is determined, directly, from the number of constituent quintessences. This leads automatically to the fundamental equation, derived from (1), $f=n_q=E/h$, where n_q is the number of quintessences, which leads directly to the frequency of both light and matter. This in turn leads directly to a Universal wave equation for matter and light $\lambda=c/\beta n_q=hc/\beta E$ (2), where β is the relative directional velocity, v/c. As the momentum, $p=\beta\times E/c$, then this equation also gives the standard de-Broglie wave equation, $\lambda=h/p$ in agreement with current theory and experiments[1].

[0005] Using the Universal wave equation, the standard equation for special relativity, $m'=m_o/(1-\beta^2)^{1/2}$, derives from first principles. Also from these observations, a modified Dirac wave equation may be derived, $E\psi=(-j\beta\cdot\nabla+\beta m)\psi$ (2a), the results of which have been recently verified by a paper in which the orbitals of electrons were experimentally directly visualised[2]. Moreover, a fundamental equation for general relativity can be formulated, where G is the gravitational constant and r_q is the given radius of quintessence; $G=9(r_q)^2c^4/\lambda\beta E$ (3), such that the Universal wave equation is in direct agreement with general relativity[3]. Thus special and general relativity and quantum mechanics can be unified.

[0006] From here it is possible to proceed in a number of ways; the geometric structure of the electron and the forces of Nature may be derived from first principles and in turn the structure of the quarks, including the top and bottom, otherwise known as truth and beauty can be seen. Moreover, the presence of a space-time lattice results in an understanding of quantum EPR effects. By allowing a theoretical flow of energy through the space-time lattice it can be shown that:

[0007] Energy is not bound by space-time

[0008] Thus logically accounting for phenomena such as entanglement and quantum tunnelling. Quintessence can also be used to explain, logically, the inner physics of a black hole, the missing mass of the Galaxy, the continuing expansion of the Universe, Guth's inflationary theory and the Big Bang. Hence, it is now possible to understand the Universe, including space-time, matter and the forces of nature from the radius, mass and vibration of a single quantity, quintessence.

[0009] With this understanding of space-time, matter and the forces of Nature, and in particular gravity, it is possible to demonstrate that the modification of gravitational fields, and in turn the warping of space-time, can be technically readily achieved.

[0010] Using standard equations for special relativity, $m'=m_O/(1-\beta^2)^{1/2}$, it can be demonstrated that by differentially increasing the velocity of electrons, by applying a differential current, their mass can be increased in a specific way. In turn by increasing the mass of electrons, by general relativity, the number of gravitons emitted from these electrons can be modulated. By multiplying this effect using an ultracentrifugational device the differential graviton emission can be manifestly amplified. This in turn, in accordance with general relativity, will cause a change in the curvature of space-time.

[0011] This effective warping of space-time does not, of necessity, imply superluminal velocities, but does allow the creation of warp drive systems, which do not depend on the creation of thrust by the ejection of material as used in current space technologies.

Part 1—Fundamental Laws of Physics

[0012] Quintessential Mass

[0013] The quantum physical, minimum component of energy is Planck's constant; h. To define the minimal component of mass, using the standard energy equivalence formula; $E=mc^2$, such a minimal mass (m_q) would be required to have the value equivalent to; $m_q=h/c^2$ (1). The total mass of a system (m) would then be; $m=n_q m_q$, where (n_q) is the number of these minimal units. Thence, the total energy of a system can be derived from the minimal energy; h, multiplied by the number of these energy units (n_q). Thus as, $E=mc^2$, then also $E=m_q n_q c^2$ and substituting $m_q=h/c^2$, the energy equivalence formula has the more logical formulation; $E=hn_q$(1a). Thus the energy of a system is equivalent to the minimal energy unit; h, multiplied by the number of those minimal energy units (n_q).

[0014] Taking this minimal mass/energy, it is possible to show that all matter, the forces of nature and space time can be constructed from this single quintessential quantity. Moreover, using this quantity the laws of physics can be derived from first principles. Thus, a priori, all components of the physical universe, including space-time, can be constructed from this minimal mass component, termed quintessence.

[0015] Wave Particle Duality

[0016] If the presence of quintessence accounts for the structure of matter and if matter itself forms from the number of quintessences, then the frequency of matter and thus wave particle duality directly arises from first principles. Specifically the wavelength of matter derives from the vibration of quintessence from which it is constituted. Thus the frequency (f) and in turn the wavelength of light and matter is directly equivalent to the number of quintessences contained within it. We find that the actual frequency of light can be directly derived from first principles from the effective mass of the photon (m,) and thus by the number of quintessences (n_q) it contains.

[0017] Thus for light conventionally:

$$f=E/h$$

[0018] and if $E=mc^2$, and $h=m_q c^2$, then

$$f=m_{\gamma}c^2/m_q c^2$$

and

$$f=m_{\gamma}/m_q=n_q$$

Thus

$$f=n_q \tag{4}$$

[0019] Thus the formula for the frequency of light E=hf is now readily explained by the observation that the frequency is determined quite directly from the number of quintessences n_q within the photon.

[0020] The wavelength is thus also given by:

$$\lambda=c/f=m_{qc}/m_{\gamma}=h/p$$

[0021] We can now show that the frequency of matter also has the same derivation from quintessence, as has the frequency of light. The frequency of matter is again equivalent to the number of quintessences it contains. Thus the wave particle duality of matter itself can be explained by its composition from quintessence. The amount of quintessences contained within a electron sphere will depend on the number of quintessences constituting the electron and those passing through it as a result of its relative velocity β^2 (where $\beta=v/c$); effectively its relativistic momentum (p). The frequency will then be related to the total number of quintessences. Thus for matter,

$$f=\beta^2 n_q \tag{4a}$$

[0022] Thus it is possible to derive the conventional de Broglie wave equation for matter from first principles. Thus, as $\lambda=v/f$, we have:

$$\lambda=v/\beta^2 n_q \tag{5}$$

[0023] thus as $n_q=E/h$

$$\lambda=hc/\beta E \tag{2}$$

[0024] and as conventionally $\beta E/c=p$, then for matter:

$$\lambda=h/p$$

[0025] Provided that in the de Broglie equation, the momentum of the object is calculated using the relativistic mass, thus accounting for the total number of quintessences n_q in an object, this gives an accurate value for the wavelength of matter[1].

[0026] Thus the wavelength of matter follows directly from its constituents, quintessence. As matter is made of quintessence, similarly to light, its frequency depends on the number of quintessences n_q within it, traveling relative to the speed of light. Moreover, $\lambda=hc/\beta E$, underpins a fundamental relationship between wavelength and energy. Furthermore, this is mathematically the same as the term $\lambda=hv/\beta^2 E$, giving a relativistic expression for the wavelength of matter, from which the relativistic equations may be directly derived

[0027] Wave Equations

[0028] The derivation of wave particle duality from first principles also now allows the derivation of a modified wave equation for matter.

[0029] To derive his wave equation Shrodinger commenced with the de Broglie equation using momentum (p). For lower energies the momentum of an electron is conventionally derived from the kinetic energy of the electron and the mass of the electron m_0. Thus conventionally:

$$E_k = \frac{1}{2}mv^{1/2} \quad \text{and} \quad p = m_0 v$$

Thus

$$E_k = p^2/2m_0$$

then

$$p = \sqrt{(E_k \cdot 2m_0)}$$

[0030] and conventionally, the de Broglie equation can also be written as:

$$\lambda=h/p=h/\sqrt{(E_k \cdot 2m_0)}$$

[0031] In turn the Shrodinger wave equation directly derives from the square of the above classical non relativistic term for kinetic energy:

$$\lambda^2 = h^2/E_k \cdot 2m_0$$

$$\text{thus } E_k = \frac{h^2}{2m} \cdot \frac{1}{\lambda^2}$$

$$\text{As } E = E_k + V$$

$$\text{then } E\psi = -\frac{h^2}{2m} \cdot \frac{d^2\psi}{dx^2} + V\psi = jh \cdot \frac{d\psi}{dt}$$

[0032] However, the Shrodinger equation, may be refined by taking into account relativity. Thus the true values for the energy are given by the relativistic momentum (p).

[0033] A fundamental relativistic wave equation for ψ, and its logical derivation may now be developed through the concept of quintessence as a fundamental constituent of matter.

[0034] The amount of quintessences in the electron is determined by the number of quintessences forming the electron at rest, plus the amount of quintessences passing through it due to its relativistic velocity, which will determine the relativistic momentum (p) of a particle.

[0035] The frequency of matter can now be readily calculated from first principles to give a more accurate result. Thus as matter is made of quintessence, similarly to light, its frequency is equal to the number of quintessences n_q within it. The wavelength will depend on its velocity travelling relative to the speed of light and thus multiplied by the relative velocity compared to c(β=v/c);

[0036] Hence for matter as previously shown:

$$\beta = v/\beta^2 n_q = hc/\beta E \qquad (2)$$

[0037] And conventionally

$$E = (p^2c^2 + m_0^2c^4)^{1/2}$$

[0038] Using these equations, we can now, also, reformulate the Shrodinger wave equation, which has the advantage that relativity can be treated in a quantum mechanical way. Thus if the wave energy of matter is defined as:

$$E_\lambda = \frac{\beta\sqrt{p^2c^2 + m_0^2c^4}}{c^2}$$

thus

$$E_\lambda = \sqrt{(\beta^2p^2/c^2) + \beta^2m_0^2}$$

[0039] which in complex space generalises to

$$E_\psi = (-j\beta\cdot\nabla + \beta m)_\psi \qquad (2a)$$

[0040] As the term

$$\alpha = \frac{e^2}{hc}4\pi\varepsilon_0;$$

also represents the ground state ratio of the velocity of the electron to c. Thus α=β=v/c=1/137.

[0041] Thus, also

$$E_\psi = (-j\alpha\cdot\nabla + \beta m)_\psi$$

[0042] This is thus the standard relativistic equation that Dirac was able to construct from the Shrodinger wave equation. This relativistic equation can be derived from the modified wave equation. This takes into account the relative mass energy which the quintessential wave equation contains.

[0043] Where importantly the term β·m is the mass m, multiplied by the ratio of the relative velocity to light β=v/c, and the term a is also essentially the relative velocity of the electron.

[0044] The Dirac equation was an empirical formula which worked mathematically, nevertheless even Dirac admitted it was not logically understood. The importance of these equations is that they show that the existence of quintessence allows the waveparticle duality of matter to be explained and mathematically derived from first principles, Thus the frequency of matter or even light is simply determined by the number of quintessences it contains.

[0045] Indeed, a recent publication in Nature has suggested that the direct visualisation of the orbitals of electrons shows that these are in very close agreement with theory. However, there is a significant departure from theory, in the interstitial molecular regions, suggesting that the higher velocities of the electrons obey the modified Dirac equation. Thus these orbitals were in keeping with the modified Dirac equation, which itself may be derived from the wave equation above, λ=hc/βE

[0046] The Shrodinger wave equation will approximate to the correct values until v approaches c. Indeed the Shrodinger equation will give similar answers as that derived from equation, under most experimental conditions.

[0047] However, equation 2 and its derivative may have advantages over standard Shrodinger theory with relativistic speeds. Furthermore, equation 2, conceptually shows that the wave particle duality of matter derives from the principle that the frequency of matter is directly equal to the number of quintessences it contains. Importantly it also mathematically allows relativity and quantum mechanics to be united.

[0048] With v≅c, the modified Dirac equation will yield more accurate results, particularly compared with the Schrodinger equation. We also find that the equation λ=hc/βE is equivalent to the de Broglie wave equation, λ=h/p, provided we use the relativistic mass in the de Broglie equation. Given this, these equations yield accurate experimental results.

[0049] Thus we find that the modified formulation of de Broglie wave equation λ=hc/βE leads directly to a modified Dirac relativistic wave equation and is supported by recent experiments which measure the wavelength of matter and demonstrate the electron orbitals experimentally from these wave equations for matter.

[0050] Wave Particle Duality and Relativity

[0051] From here it is possible to proceed in several ways using the relativistic wave equation. It is apparent that the reintroduction of the term for relative velocity into the wave equations will enable the reintroduction of special relativity into quantum mechanics. In particular we should now be able to derive the term

$$\sqrt{\left(1 - \frac{v^2}{c^2}\right)}$$

as a special case of quantum mechanics.

[0052] Thus if:

$$\lambda = hc/\beta E$$

As $E = \sqrt{p^2c^2 + m_0^2c^4}$, squaring

$$\lambda^2 = \frac{h^2c^2}{\beta^2\cdot(p^2c^2 + m_0^2c^4)}$$

-continued

Conventionally $p^2c^2 = \frac{E^2v^2}{c^2}$

then

$$\lambda^2 = \frac{h^2c^2}{\beta^2 \cdot ((E^2v^2/c^2) + m_0^2c^4)}$$

Thus as $\beta^2 = \frac{v^2}{c^2}$ and $m_0^2c^4 = E_0^2$, then:

$$\beta^4E^2 + \beta^2E_0^2 = \frac{h^2c^2}{\lambda^2}$$

hence $\beta^4E^2 = h^2c^2 \cdot \frac{1}{\lambda^2} - \beta^2m_0^2c^4$ thus

$$\beta^2 = \frac{h^2c^2}{\beta^2E^2} \cdot \frac{1}{\lambda^2} - \frac{\beta^2m_0^2c^4}{\beta^2E^2}$$

As $E^2 = m^2c^4$

$$\beta^2 = \frac{h^2c^2}{\beta^2m^2c^4} \cdot \frac{1}{\lambda^2} - \frac{\beta^2m_0^2c^4}{\beta^2E^2}$$

Substituting $h = m_qc^2$

$$\beta^2 = \frac{m_q^2c^6}{\beta^2m^2c^4} \cdot \frac{1}{\lambda^2} - \frac{\beta^2m_0^2c^4}{\beta^2E^2}$$

As $m_q/{}'m = 1/n_q$ (eq. 2)

$$\beta^2 = \frac{c^2}{\beta^2n_q^2} \cdot \frac{1}{\lambda^2} - \frac{\beta^2m_0^2c^4}{\beta^2E^4}$$

Thus if $f = \beta^2n_q$; (eq. 7a)

$$\beta^2 = \frac{v^2}{f^2} \cdot \frac{1}{\lambda^2} - \frac{\beta^2m_0^2c^4f^2}{\beta^2E^2}$$

As $1/\lambda^2 = f^2/v^2$

$$\beta^2 = \frac{v^2}{f^2} \cdot \frac{f^2}{v^2} - \frac{\beta^2m_0^2c^4f^2}{\beta^2E^2}$$

Thus

$$\beta^2 = 1 - \frac{\beta^2m_0^2c^4}{\beta^2E^2}$$

As $E^2 = m^2c^4$

$$\beta^2 = 1 - \frac{m_0^2}{{}'m^2}$$

Hence

$$m_0/{}'m = (1-\beta^2)^{1/2}$$

Thus

$${}'m = m_0 \Big/ \left[1 - \frac{v^2}{c^2}\right]^{1/2}$$

[0053] Thus this derivation now allows relativity as a universal case of the quintessential wave nature of matter.

[0054] The original premises on which special relativity was based were: that the speed of light is a constant and that all observers are equal. As the speed of light has dimensions of length and time but not apparently of mass, the relativistic change in mass is not accounted for. Using quintessence logically and directly accounts for the relativistic mass changes.

[0055] Moreover, relativity can be derived from the de Broglie equation, and visa versa, directly, thus linking relativity and quantum mechanics by taking into account the existence of quintessence mass.

[0056] Hence, it is now possible to derive the relativistic equations for mass and in turn for space and time from the quintessential wave equation, thus deriving special relativity as a universal case of quantum mechanics and thus uniting special relativity and quantum mechanics. This now allows a further understanding of the nature of space-time.

[0057] The Space-Time Lattice

[0058] The understanding of the true nature of space-time and how it is formulated in three dimensions of real space is crucial. To simply assume that space-time exists, and thence not to question the nature of that existence, denies a deeper understanding of the universe.

[0059] In order to understand the nature of space-time itself, at the quantum level a further look at the nature light and the photon is necessary. Since Einstein's description of light as a particle (the photon) and the description of the photoelectric effect, the standard picture of light as simply a wave can, no longer be applied. If light was to exist as a photon, it could not exist in one dimension, as ordinary waves do, it would need to be three dimensional, with the addition of time. Let us suppose, in this case, that a photon is a three dimensional helical ringlet of light, travelling in the x vector, and spinning around the x-axis. Conventionally this ringlet has a radius; $r=\lambda/2\pi$. The ringlet itself would be vibrating in the y and z vectors. The vectors x, y and z would represent the photon, the substance of which, would be travelling in the x direction and oscillating in the y and z vectors, which would represent oscillatory energy. This in turn would allow it to act as a wave, and create oscillatory electromagnetic fields.

[0060] It is important to re-examine space-time itself in this light, this would have one directional vector with two vector dimensions of energy, one of capacitance and one of electrical permeability, thus accounting for the well known constants of free space; the permittivity of free space (ϵ_0) and the permeability of free space (μ_0) respectively. The vector dimension of direction x, would be the direction of travel and those "quintessences" travelling in an outwardly direction would account for none other than the expansion of the universe. Three of these quintessences would naturally constitute three dimensional visible space-time. These constituents of space-time would interact with the generations of the other vector dimensions reciprocally. Thus one quintessence would sweep out one vector of permeability and one vector of permittivity, through which the other two quintessences could travel, and vica versa, creating a three dimensional space-time lattice.

[0061] The permittivity of free space, (ϵ_0) which is equivalent to capacitance, would as with capacitance plates, be determined by the effective separation between quintessences. The permeability of free space (μ_0) is in fact a force, measured as $4\pi\times10^{-7}$ N/A^2, would result from the force produced by the vibration of quintessence and would be dependent on the density of quintessence. Hence these two parameters would be reciprocal and thus the product of these two would therefore be a constant, which is recognised as none other than the speed of light.

$$c = \frac{1}{\sqrt{\mu_0 \varepsilon_0}}$$

[0062] This space time lattice would in effect be created by quintessences travelling in all directions with a speed of c within the lattice. The quintessences of the space time lattice would in effect produce a non-static ether. A non-static ether is fully compatible with special and general relativity. Indeed such an ether explains how space time can be curved as in general relativity. Furthermore, the existence of a non-static ether, was espoused by Einstein in his University of Leyden lecture on general relativity of May 5, 1920. In Einstein's own words;

[0063] "According to the general theory of relativity space without ether is unthinkable."

[0064] Recent evidence from a number of sources now strongly support the presence of this non-static ether, in the form of quintessence. An editorial from a major journal states "combined with other observations such as those of distant Supernova, the QMAP results corroborate the prevailing theory of inflation with the twist that the Universe is only one third matter (both ordinary and dark) and two thirds quintessence, a form of energy possibly inherent in empty space".

[0065] If we take into account the existence of quintessence and as such a three dimensional space-time lattice, matter which is intrinsically made of constituents of charge would interact with this lattice to produce the effects of mass. Mass would be perceived as a result of matter (whose constituent particles appear to contain charge) interacting with this lattice directly due to the inhibition of motion by the lattice's electrical permeability and permittivity vectors, which would form the existence of complex space. These quintessences would in the direction in the y and z vectors produce small vibrations of the order of the Planck length (10^{-35} m), whilst passing through the vectors of permeability and permittivity, thus producing the effects of mass.

[0066] The vibration would endow quintessence itself a (non rest) mass m_q equivalent, to the minimal mass of:

$$m_q = h/c^2 = 7\times373\times10^{-51}\ \text{kg}\cdot\text{sec} \tag{1}$$

[0067] The presence and magnitude of Planck's constant (h) and especially the speed of light (c) is thus explained. Indeed, the speed of light

$$c = \frac{1}{\sqrt{\mu_0 \varepsilon_0}}$$

is not in itself a fundamental quantity.

[0068] As the energy equivalence formula is $E=mc^2$, the minimal mass of a single quintessence, would thus be the minimal mass, h/c^2, hence again:

$$m_q = h(\mu_0\epsilon_0) = h/c^2 = 7.373\times10^{-51}\ \text{kg}\cdot\text{sec} \tag{1b}$$

or

$$m_q c^2 = h \tag{1c}$$

[0069] It is postulated by general relativity that the shape of space time itself can be altered, indeed the presence of the space time lattice now allows this to be altered by altering the density of quintessence. It is further clear that if quintessences underly the structure of the space-time lattice, they may also underly the structure of matter itself.

[0070] With regards a single quintessence, this passing through an energy vector of the space-time lattice would appear as a vibrating string. In a similar way to string theory, the conglomeration of these quintessences would produce the constituents of ordinary matter. Thus the general equation for the number of quintessences (n_q) in an object of mass (m) would be

$$m/m_q = n_q$$

[0071] The mass of the electron (m_e) for example, would be directly determined by the number of quintessences in the electron, multiplied by the mass of quintessence.

[0072] Quintessence and Complex Space

[0073] Quintessence is postulated to constitute the fundamental nature of space-time. Three quintessences each travelling in their respective x vectors at 90° to each other would create three dimensional real space-time. These quintessences would in the direction in their respective y and z vectors produce small vibrations of the order of the Planck length (10^{-35} m), this would create the vector dimensions of permeability and permittivity. The result would give space-time 9 dimensions of space as in superstring theory. However, unlike superstring theory the six hidden dimensions would not be "curled up so as to be so small as to be invisible" these six dimensions would be present in complex space. Thus, only three of these dimensions would represent ordinary three dimensional particulate space time i.e. three dimensional objects. The other six dimensions produced by the vibrations of quintessence would form complex space.

[0074] The mathematics of complex space, using imaginary $\sqrt{-1}$ or (j) numbers, is assumed in the standard formulation of the Shrodinger wave equation. Thus the presence of complex space is an integral part of quantum mechanics.

$$-\frac{h^2}{2m}\cdot\frac{d^2\psi}{dx^2} + V\psi = jh\cdot\frac{d\psi}{dt}$$

[0075] The mathematics of complex space is also an essential and integral part of the principles and application of modern electronic and control engineering. Indeed it has been well recognised for some time that each direction vector in electronic engineering can, be associated with complex vectors.

[0076] As this complex space consists of the vectors of permittivity and permeability it would only be "felt" by charged particles as in the electron. Nevertheless, as all particles are fundamentally composed of charged particles the effects of complex space would be felt by endowing these particles with mass and in turn kinetic energy.

[0077] In conventional complex space, a 2 dimensional Cartesian Argand diagram is mathematically used. However, in order to formulate the equations for particles a three dimensional Argand diagram is essential. This will have three dimensional vectors, one real vector and two imaginary vectors. Three of these diagrams will be required to fully describe the nature of particles, each with a real vector in the x, y and z vectors, respectively. Nevertheless, in the instance below the real vector is the x vector and the two imaginary vectors are given by $({}_jy, {}_jz)$

[0078] The Three Dimensional Argand Diagram

[0079] The beauty of a three dimensional Argand diagram is that the complex conjugate (i.e. the mirror image which confers mathematical reality on the coordinates) is formed by the value of the minus coordinate in the other complex vector dimension. Thus the complex conjugate of $(C_x{}^{1/2}+{}_jc_y{}^{1/2}+{}_{-j}c_z{}^{1/2})$ is $(c_x{}^{1/2}+{}_jc_y{}^{1/2}+{}_jc_z{}^{1/2})$. These two sums when multiplied thus give a real number solution.

[0080] Furthermore it is clear that nine dimensions of space time are necessary in the general relativistic equations. By including complex space we thereby create the nine dimensional spacial metrictensor and the metric energy tensor of matter necessary for computations for general relativity From here we can begin to understand the true structure of matter.

[0081] Energy and the Space-Time Lattice

[0082] The presence of numerous experimental data for quantum tunnelling. and indeed the recent observations by Nicholas Gisin, on the entanglement of distant photons now returns us to EPR experiments.

[0083] Using the quintessential modification of the de Broglie wave equation, gives us an insight into these teleportation and EPR effects.

[0084] As

$$\lambda = hc/\beta E \tag{2}$$

and

$$E = hn_q \tag{1a}$$

then

$$\lambda = c/\beta n_q \tag{2b}$$

[0085] Importantly, as indicated by equation (2b), energy having no quintessence; would have a wavelength of infinity. Specifically pure energy containing no quintessences, would have a lambda of infinity. According to quantum mechanics an infinite wavelength would result in the probability of that energy being anywhere. As energy itself has no electrical charge it would not be impeded by the permittivity and permeability of the three dimensional space-time lattice. Moreover, energy would not be detectable in three dimensional space-time, unless it interacted with matter, as in the EPR experiments. Indeed, energy is not observed when not bound to any form of mass or particle. Thus equation 9d, takes us to our original assertion

[0086] Energy is Not Bound by the Space-Time Lattice

[0087] Thus, as the EPR experiments suggest the existence of energy separate from matter and thus separate from the three dimensional space-time lattice, it is interesting to find that experiment suggests the existence of free energy in a continuum separate from space time to produce the effects of quantum teleportation

[0088] This is not, however, teleportation across an additional dimension, this is a term to describe in partially familiar terms the dissociation of energy from the three dimensional space-time lattice. As time is inextricably linked to each dimension of space, the effects of energy would be inextricably linked to the events, such as the creation of virtual particles, we see interacting within space-time.

[0089] It is unlikely that observers have any direct day to day experience to explain quantum events. Nevertheless, quantum physics may have given us a window into the hitherto hidden workings of the Universe. Thereby, the mystery of the uniformity of the Universe, across distances which the speed of light could not apparently traverse, is readily explained by the fact that the free energy contained in the Universe is not bound by the space-time lattice.

[0090] In the case of light, due to the exceedingly small masses involved, there would be relatively easy exchange of matter with free energy within a photon. This would make the photon the ideal experimental tool to look for energy which is not bound by matter and in turn energy which is not bound in space-time. Indeed, very recently Furusawa et at. have reported to have observed the transference of energy as photons from A to B, without those photons traversing space-time. This finding which has been supported using other experimental techniques, is very important as it suggests the existence of such a quantum continuum.

[0091] We have already seen strong experimental data using photons, atomic spins and other data for quantum teleportation which have recently been published which support these findings. According to the above equations the teleportation would vary in a predictable fashion, as with photons, in line with the wavelength of the light used, relative to the size of vibration of quintessence. As regards matter, the results do confirm that the effect of quantum tunnelling is indeed dependant on the wavelength of matter and the size of that matter.

Part II—Particle Physics

[0092] Electron Structure

[0093] Understanding the electron is fundamental to the understanding of the elementary particles. The hidden nature of the electron may recently have been revealed through observations by Horst Stormer, Daniel Tsui and Robert Laughlin for which a Nobel prize has recently been awarded. They describe a quasi electron particle of charge ⅓e. This has been described on a quantum basis as a vortex of energy, bound as a quasi particle in one dimension x, but not bound in the other two dimensions y and z, allowing dispersion in space-time as a vortex. What is more intriguing are the experimental conditions in which this occurs. First of all a two dimensional electron gas is created and held between two capacitance plates. A magnetic force is then applied in the remaining dimension, virtually creating a one dimensional passage through which only a quasi electron appears to be able to pass.

[0094] Given the presence of charge of ⅓e, then three of these quasi electrons could form an entire electron in three dimensional visible space time. Nevertheless, each would have energy and hence a wave function which would be present in the other vectors. This electron could thus follow the probability functions as described by the Shrodinger wave equation for ψ (otherwise termed as "essence" by Shrodinger)

[0095] If the mass of the electron (m_e) is constituted from quintessence, using the formula:

$$m_e/m_q=n_q$$

[0096] Then an electron would be constituted from:

$$\frac{9.11\times10^{-3}\ \text{kg}}{7.373\times10^{-51}\ \text{kg}\cdot\text{sec}}=1.235\times10^{20}\ \text{quintessences/sec.}$$

[0097] Thus taking into account the mass-energy content of quintessence (m_q) it is independently possible to derive the magnitude of the charge of an electron (e) using the following equation.

$$e=\sqrt{\frac{m_q\varepsilon_0}{\left(\frac{4}{3}\right)\pi hc}}=1.61\times10^{-19}C$$

[0098] This is in close agreement with the experimentally observed charge on the electron of 1.602×10^{-19} C.

[0099] Interestingly substituting $m_q=h/3c^2$ in the above equation we have:

$$e=\sqrt{\frac{\varepsilon_0}{3\left(\frac{4}{3}\pi c^3\right)}} \tag{6}$$

[0100] This can also be written as

$$e=\sqrt{\frac{\varepsilon_0}{3\left(\frac{4}{3}\right)\pi c^3}} \tag{6a}$$

[0101] Equation (6) has a number of very special implications, if re-examined, firstly three of these quasi electron spheres appear to be required to constitute the charge of the electron. More intriguingly, it indicates that the charge is related to the volume of a sphere with an apparent radius of c. Thirdly it indicates that the square of the charge of an electron (e) is proportional to the permittivity of free space (so). The charge given from equation (3) is in close agreement with the measured charge of the electron. Furthermore a more exact value for the charge of the electron (to seven decimal places) can be deduced by taking into account the gravitational field of the Earth (see Gravity and the Charge of the Electron). Furthermore the charge of the electron (e) can now be derived from first principles. Thus, equation (3) corroborates the evidence that the electron is indeed composed of three quasi electrons in keeping with recent experimental findings.

[0102] The significance of the electron, composed of three spheres each with a radius of c, is not immediately clear, but can be understood if the frequency of rotation of the electron is taken into account. Thus if the diameter of the electron was approximately 10^{-19} m, then its spin would need to be

$$\frac{1}{c}\times10^{-15}$$

m approx. eq. 10^6 cycles/sec. Thus given a very high rotation rate an electron could have an effective radius of 1/c and still occupy subatomic sizes. Indeed these observations might be used to estimate the rate of rotation of the quasi electron and its size (see Appendix 1).

[0103] With regards a single quintessence, this passing through an energy vector of the space-time lattice would appear as a vibrating string. In a similar way to string theory, the conglomeration of these quintessences would produce the constituents of ordinary matter. The electron, for example, would be constituted from approximately 1.235×10^{20} quintessences.

[0104] The dimensions of the equation for the electron can be readily resolved by considering each of the three vector dimensions. The exact dimensions of the equation need to be considered in the light of the nature of space-time itself. These dimensional equations help explain the nature of matter. Indeed the equation for the electron may be necessary for the full understanding of gravity

[0105] Complex Space and Electron Structure

[0106] The presence of complex space also now further explains the conformation of the electron, and its formulation at the quantum level, and the presence of particles, anti-particles and their spin up and spin down characteristics.

[0107] Indeed the short form equation for the charge of the electron (−e) can now be rewritten as a metric tensor with three dimensions in real space and six in complex space.

[0108] Thus if three of the x, y and z vectors are in real space and six vectors in complex space, where c is the speed of light in the real space vector, ${}_{j}c$ is the speed of light in the complex vector and ${}_{-j}c$ is the complex conjugate of ${}_{j}c$, thus the electron can be mathematically represented by the equation:

$$-e=\varepsilon_{qe}\Big/\left(\frac{4}{3}\pi\right)^{1/2}\cdot\begin{matrix}(c_x)^{1/2}\cdot(jc_y)^{1/2}\cdot(-jc_z)^{1/2}\\+\quad+\quad+\\(-jc_x)^{1/2}\cdot(c_y)^{1/2}\cdot(jc_z)^{1/2}\\+\quad+\quad+\\(jc_x)^{1/2}\cdot(jc_y)^{1/2}\cdot(c_z)^{1/2}\end{matrix}$$

[0109] Which now elegantly gives the real number solution

$$e = \frac{\varepsilon_{qe}}{3\sqrt{\left(\frac{4}{3}\right)\pi c^3}}$$

[0110] Where e=ϵ_{qe} is given as the permittivity of free space for a single quasi electron Equation 4 represents a "complex" tensor

[0111] Whilst the two dimensional Argand diagram has four quadrants, the three dimensional Argand diagram has eight cubic sectors. Two of these cubic sectors are diametric opposites and can represent "real" particulate objects. These have the primary coordinates x, y, −z; as in the electron described above, and the −x, −y, z, with the real vector x now having a minus sign. These two "real" cubic sectors, therefore, mathematically represent particles and their anti-particles.

[0112] The mathematical presence of the two primary diagonal mirror images (x, y, −z and −x, −y, z) now allow the introduction of the concept of antiparticles. This extension of the maths into a three dimensional Argand diagram thus results in the automatic formulation of the maths of anti-particles. Thus the charge of the positron ($^{+}$e) is formulated by the shortened form equation, where the real vectors now each have the minus sign, and therefore exist in the −x, −y, z sector of the three dimensional Argand diagram.

$$e = \varepsilon_{qe} \Big/ \left(\frac{4}{3}\pi\right)^{1/2} \cdot \begin{matrix} -c_x^{1/2} \cdot_{-j} c_y^{1/2} \cdot_{j} c_z^{1/2} \\ {}_{j}c_x^{1/2} \cdot -c^{1/2y} \cdot_{-j} c_z^{1/2} \\ {}_{-j}c_x^{1/2} \cdot jc_y^{1/2} \cdot -c_z^{1/2} \end{matrix}$$

[0113] The three dimensional Argand diagram also accounts for chirality and indeed the up and down spin of the electron. There are two other "real" primary coordinates in the Argand diagram, these are themselves the partial mirror images of the above coordinates (i.e. x, −y, z and −x, y, −z). In particular the y axis is of the opposite sign, thus in particles the y axis is in the downward direction, to form down spin particles and in anti-particles in the up direction, to form the antiparticle The up spin electron is given by eq. 8 and hence the down spin electron (−e|↓≦) is given by the equation

$$-el\downarrow\rangle = \varepsilon_{qe} \Big/ \left(\frac{4}{3}\pi\right)^{1/2} \cdot \begin{matrix} c_x^{1/2} \cdot_{-j} c_y^{1/2} \cdot_{j} c_z^{1/2} \\ {}_{j}c_x^{1/2} \cdot c^{1/2y} \cdot_{-j} c_z^{1/2} \\ {}_{-j}c_x^{1/2} \cdot jc_y^{1/2} \cdot -c_z^{1/2} \end{matrix} \tag{9}$$

[0114] Thus the three dimensional Argand diagram accounts directly for the presence of antiparticles and the spin up and spin down particles seen in nature. It also accounts for the necessity of the electron to form a square root spherical object, as complex space depends on √−1, otherwise known as j.

[0115] Electron Pairing and Superconductivity

[0116] As the quintessences making up the electron are in a square root conformation, each of these quasi electrons would have a tendancy to pair to form an entire sphere.

[0117] The square root sphere structure of electrons with up and down spins can now superimpose to produce a complete sphere of varying extents. This produces electron pairing as seen at the atomic and molecular levels. It also accounts for the Pauli exclusion principle. This pairing thus accounts for the reactivity of the valence electrons and the electron probability densities, which in turn accounts for the existence of chemistry.

[0118] Furthermore, it is possible to account directly for superconductivity from first principles. For if both the complex and real vectors of the electron combine completely, the product of an up and down spin electron form a perfect superimposed sphere with radius c, with a charge of 2.59×10^{-38} C, denoted by the formula:

$$e^2 = \frac{\varepsilon o}{3\left(\frac{4}{3}\pi c^3\right)} = 2.59\times10^{-38} C \tag{6b}$$

[0119] As with standard superconducting theory, superconductivity can be explained by the formation of "Cooper" electron pairs, where the electrons are forced to pair by the presence of positive crystal charge in particular formation, at supercooled temperatures. In addition the electron pair now forms a stable entity whose angular momentum cancels.

[0120] It additionally becomes clear that the charge of two separate electrons (2e) is 3.2×10^{-19} C, but the charge of the combined electrons (e^2) is 2.59×10^{-38} C. This electron pair thus appears to have 19 orders of magnitude less charge than the electron and in turn 19 orders of magnitude less resistance. It is this effective reduction in charge and in turn resistance, which may account for superconductivity. When observed directly any electrical interaction with the Cooper electron pair will, however, result in the release of the full charge of both electrons, so that the full electrical charge put in will be equal to that coming out of the apparatus.

[0121] The Fine Structure Constant

[0122] Intruiginty from our knowledge of the electron we can further define the term .alpha., the fine structure constant; from the structure of the electron. Thus as the standard term

$$\alpha = \frac{e^2}{hc\times 47\pi\varepsilon_0};$$

substituting the term

$$e^2 = \frac{\varepsilon_0}{3(4/3)\pi c^3} \tag{eq. 6}$$

and

$$h = m_q c^2 \tag{eq. 1}$$

we find:

$$\frac{2\pi}{\alpha}=m_q[3(4/3\pi c^3)]^2$$

*or

$$\frac{2\pi}{\alpha}=\frac{m_q e^4}{\varepsilon_0^2}$$

[0123] For brevity we may represent the quasi electron structure as $(4/3)\pi c^3=\theta$; to signify its threefold symmetry, thus

$$\frac{2\pi}{\alpha}=m_q(3\theta)^2 \tag{10}$$

[0124] Indicating that the fine structure constant of the electron (a) is indeed related to its dimensional structure. Again taking into account the effects of gravity the fine structure constant can be derived from first principles to nine decimal places (see Gravity and the Charge of the Electron).

[0125] Fundamental Forces and Particle Structure

[0126] In order to understand the fundamental forces and the nature of fundamental particles, an overview is required. Thus, there are three major forces; strong, electro-weak and gravity, each mediated by three force particles the gluon, photon and graviton respectively. These in turn, influence three types of particle, the quark, lepton, and by general relativity space-time itself. Each of these are composed of particles with multiples of charge of ⅓, which are themselves in three generations, and are present in three dimensions of real space. It is important that a comprehensive view of nature explains this threefold symmetry.

[0127] Using the Standard Model of particles, it is well accepted there exist quark particle charges of −⅓, −⅔ and +⅓ and +⅔ in quarks and anti-quarks. Given that each particle is made up of three quarks the presence of these fractional charges support the association of the fractional charges in this way to form three dimensional charged particles. In stable particles each of the three quarks would have a vector in one dimension, giving the three quarks together an existence in three dimensional visible space time. The particles that bind the quarks (gluons) are themselves required, in stable particles, to have three different color charges, one color in each dimension, for the particle to exist in three dimensional space-time. Furthermore, there are three generations of quarks (and indeed leptons).

[0128] The Standard Model (or a modification of this) and in particular the observation of quarks and indeed quasi electrons with fractional charge of ⅓ and ⅔ in both cases, indicates that particles are constituted from the equivalent of three of these quasi particles to form an electron and quarks to form baryons. In the normal three dimensions the energy would be carried by the particle, However, because each particle is constituted of three quasi particles and in each quasi particle or quark one visible dimension would be the direction vector, in the other two hidden dimensions of each vector the waves would carry energy. Thus each particle would be associated with vibration, which would account for wave particle duality and Heisenberg's uncertainty principle in three dimensional visible space-time.

[0129] These observations lead us directly to the previous postulate that the structure of the electron is composed of none other than three (root) spheres, and that this equation for the electron allows the determination of the charge of the electron from first principles, thus:

$$e=\frac{\varepsilon 0^2}{[3(4/3\pi c^3)]} \tag{6}$$

[0130] In addition the mass of the proton (m_p) can be directly calculated from the ratio of the mass (m_e) of the electron, given by the equation:

$$\frac{m_e}{m_p}=5.45\times10^{-4}=3\frac{\pi}{\sqrt{c}} \tag{11}$$

[0131] Strictly we should write,

$$\frac{m_e}{m_p+m_e}=3\pi\sqrt{c};$$

which is much more elegant.

[0132] Which now gives

$$\frac{m_e}{m_p}=\frac{1}{\sqrt{c}\,/3\pi-1}=5.4462\times10^{-3}$$

[0133] This is in very close agreement with the experimentally derived ratio of the proton to electron masses which is also; 5.4462×10^{-3}

[0134] Thus the correlation factor between theory and experiment has a maximum error <0.00001.

[0135] If we combine equation 3:

$$e=\sqrt{\frac{\varepsilon_0}{3(4/3)\pi c^3}}$$

and equation 13:

$$\frac{m_e}{m_p}=3\frac{\pi}{\sqrt{c}}$$

the positive charge of the proton (e_p) is given by:

$$e_p = \sqrt{\frac{\varepsilon_0}{3(4/3)\pi c^3}} \times m_e \times 3\frac{\pi/\sqrt{c}}{m_p} = e \tag{12}$$

[0136] The stable nuclear proton conformation can thus be represented by the short form equation:

$$p=3^{+}\sqrt{3(4/3)\pi c^3}\times 3(\pi/\sqrt{c}) \tag{13}$$

[0137] This forms a stable 3×3 conformation as with the stable electron structure.

[0138] Importantly the term $(\pi/\sqrt{c})$ is the 90° solution to the Shrodinger wave equation for an electron confined in a space with radius c!.

[0139] Thus the standard equation for an electron confined in a one dimensional box is given by:

$$E\psi(x) = -\frac{h^2}{2m}\frac{d^2\psi(x)}{dx^2}$$

[0140] If the one dimensional box has a length 2L the quantum amplitude (A) can only be non zero between x=0 and X=2L and the standard solution for the amplitude is none other than:

$$A=(1/L^{1/2})$$

[0141] Thus in one dimension the standard solution to the Shrodinger wave equation is:

$$\psi(x)=(\pi/L^{1/2})\mathrm{Sin}\ x/L$$

[0142] Thus not only is the electron charge derived from the equation for three spheres each with a radius of c (eq. 3); but the proton mass and charge can also be derived from the standard solution to the Shrodinger wave equation for a an electron confined in a space of radius c!.

[0143] The term $(\pi/c^{1/2})$ itself would thus most logically represent the gluon which is present in the proton. These gluons would bind the quasi electrons together to form the fundamental particles

[0144] The masses of all the known particles, including the up and down quarks, the W boson, the muon, charm, strange, the tauon, truth and beauty can thus also be derived from first principles in this fashion, and have the quasi electron as their basic constituent particle (see Appendix 1).

[0145] Thus the structure of the muon (μ) can also be derived from the ratio of the mass of the electron (m_e) and the mass of the muon (m_μ):

$$m_e/m_\mu=4.7\times10^{-3}=c^{1/3}$$

Thus

$$\mu=\epsilon_0{}^{1/2}\times m_e/m_\mu\times3^{-}(4/3=\pi c^3)^{1/2}\times(\pi/c^{1/3})$$

[0146] Where the charge of the muon is in this equation equivalent to that of the electron e. In this case $(\pi/c^{1/3})$ can be considered to represent a specific high energy photon. Thus the structure of the muon, written in short form is:

$$\mu=3^{-}(4/3\pi c^3)^{1/2}\times(\pi/c^{1/3}). \tag{14}$$

[0147] Moreover the structure of the tauon can be calculated from the ratio of the mass of the electron and that of the Tauon (1.79 Mev);

[0148] Thus

$$0.511\ \mathrm{Mev}/1.79\ \mathrm{Gev}=2.85\times10^{-4}$$

$$m_e/m_r=(\pi/c)^{1/3}\times(\pi/c)^{1/9}=2.85\times10^{-4}$$

[0149] As the charge of the tauon is equivalent to the charge of the electron, hence the structure of the Tauon is given by the above equation

$$e_\tau=\epsilon_{qe}\times(m_e/m_\tau)\times3^{-}(4/3\pi c^3)^{1/2}\times(\pi/c)^{1/3}\times(\pi/c)^{1/9}=e$$

[0150] This equation accurately predicts the charge −1; and mass of the Tauon (.~1.78 Gev). Thus the structure of the Tauon can in short form be given by the equation

$$\tau=-3(4/3\pi c^3)^{1/2}\times(\pi/c)^{1/3}\times(\pi/c)^{1/9} \tag{15}$$

[0151] Furthermore a more exact value for the mass of the muon and tauon can be deduced by taking into account the gravitational field of the Earth in a similar way to identifying the exact charge of the electron. In addition it may be necessary to take into account a possible mass value of the neutrino to arrive at a precisely accurate mass value of the muon and tauon. Nevertheless, the mathematical proof of these short form equations lies in the fact that they can very closely identify the charge and the masses of these particles, from first principles, as in equations.

[0152] Overall the mathematical geometrical structure of all the particles can be derived from the quasi electron, which is in turn derived from quintessence. Thus, the short form particle structures can now be derived from first principles. This includes the quasi electron (qe) and electron (e), from which the quarks (u,d) and in turn the stable proton (p) and stable neutron (n) and alpha particle (a) respectively are derived. The general structure of the force carrying bosons the photon. (g) and the gluon (γ) and the intermediate vector boson (W) can be given. It will also intriguingly be possible to derive, according to their generation, the structure of the strange (s) charm (c), beauty (b, or bottom) and truth (t or top) quarks directly from the structure of the muon (μ) and Tauon (τ) respectively.

[0153] Using the term $\Theta=(4/3\pi c^3)$, where, −/+ represents the charge of the quasi electron, we find:

[0154] 1st Generation:

$$(q_e)={}^{-}\Theta^{1/2} \tag{6c}$$

$$e=3^{-1/2} \tag{6}$$

$$d={}^{-}\Theta^{1/2}\cdot3(\pi/c^{1/2}) \tag{16}$$

$$u=2^{+}\Theta^{1/2}\cdot3(\pi/c^{1/2}) \tag{17}$$

$$s={}^{-}\Theta^{1/2}\cdot3(\pi/c^{1/2}) \tag{18}$$

[0155] 2nd Generation

$$\mu=3^{-}\Theta^{1/2}\cdot(\pi/c^{1/3}) \tag{14}$$

$$c=2^{+}\Theta^{1/2}\cdot(\pi/c^{1/3})\cdot(\pi/c^{1/4}) \tag{19}$$

$$b={}^{-}\Theta^{1/2}\cdot(\pi/c^{1/9})\cdot(\pi/c)^{1/4} \tag{20}$$

[0156] 3rd Generation

$$\tau=3^{-}\Theta^{1/2}\cdot(\pi/c)^{1/3}\cdot(\pi/c)^{1/9} \tag{15}$$

$$t=2^{+}\Theta^{1/2}\cdot(\pi/c)^{1/3}\cdot(\pi/c)^{1/9}\cdot(\pi/c)^{1/4} \tag{21}$$

[0157] Particle Gluons (g):

$$g_1=(\pi/c^{1/2}) \tag{22}$$

$$g_2=(\pi/c)^{1/2} \tag{22a}$$

$$g_3=(\pi/c^{1/4}) \tag{22b}$$

$$g_4=(\pi/c)^{1/4} \tag{22c}$$

[0158] Particle Photons (.gamma.):

$$\gamma_1=(\pi/c^{1/3}) \tag{23}$$

$$\gamma_2=(\pi/c)^{1/3} \tag{23a}$$

$$\gamma_3=(\pi/c^{1/9}) \tag{23b}$$

$$\gamma_4=(\pi/c)^{1/9} \tag{23c}$$

[0159] Intermediate Vector Boson ($W^{+/-}$):

$$W^{+}=3^{+}\Theta^{1/2}\cdot 2(\pi/c^{1/6})^{6} \tag{24}$$

$$W^{-}=3^{-}\Theta^{1/2}\cdot 2(\pi/c^{1/6})^{6} \tag{25}$$

[0160] Stable* Proton:

$$p=3^{+}\Theta^{1/2}\cdot 3(\pi/c^{1/2}) \tag{13}$$

[0161] Stable* Neutron:

Stable * Neutron:

$$n = \begin{matrix} {}^{+}\Theta\downarrow^{1/2}\cdot 2(3\pi/c^{1/2})\cdot{}^{-}\Theta\uparrow^{1/2} \\ {}^{+}\Theta\downarrow^{1/2}\cdot 2(3\pi/c^{1/2})\cdot{}^{-}\Theta\uparrow^{1/2} \\ {}^{+}\Theta\downarrow^{1/2}\cdot 2(3\pi/c^{1/2})\cdot{}^{-}\Theta\uparrow^{1/2} \end{matrix}$$

* Stable nucleonic neutron and proton conformations differ slightly from the Standard Model, this is due to the sharing of quasi electron and quasi positron particles within the nucleus, which allows stabalisation of these particles by the formation of stable 3x3 structures. The Standard conformations which describe non-nucleonic neutrons and protons are additionally given in Appendix 1.

[0162] Alpha particle (α):

$$\text{Alpha particle } (\alpha) := \alpha = \begin{matrix} [3^{+}\Theta]\downarrow^{1/2}\cdot 2(3\pi/c^{1/2})\cdot[3^{-}\Theta]\uparrow^{1/2} \\ [3^{+}\Theta]\uparrow^{1/2}\cdot 2(3\pi/c^{1/2})\cdot[3^{-}\Theta]\downarrow^{1/2} \\ [3^{+}\Theta]\downarrow^{1/2}\cdot 2(3\pi/c^{1/2})\cdot[3^{-}\Theta]\uparrow^{1/2} \end{matrix} \tag{27}$$

[0163] The mathematical proof for these structures and their decay mechanisms is lengthy and is thus fully contained in Appendix 1. All the particle structures are accurately mathematically defined by the masses of these particles.

[0164] The structure of these particles all contain the quasi electron and thus the metric tensor structure necessary in the formulation of the gravitational equations is sustained. The respective forces created by the gluon and the photon are important as they tell us the behaviour of matter and also lead to the likely structure of the graviton

[0165] Particle Spin and Size

[0166] The significance of the electron, composed of three spheres each with a radius of 1/c, is not immediately clear, but can be understood if the frequency of rotation of the electron is also taken into account. Knowing the structure of the electron has led us to deduce its charge and thus may lead us estimate its size and spin. Thus these observations might be used to calculate the radius and rate of rotation of the electron.

[0167] Let us suppose, that nature is truly beautiful, and that the radius of the fundamental quasi electron is indeed 1/c, and in turn the radius was balanced by the velocity of rotation 2π/c. This can be directly confirmed mathematically by taking into account the known spin of the electron, h/4π. Thus the actual spin of the electron may be calculated form the known energy of the spin.

[0168] The radius of the electron is not up till now known, but the radius of a quark has been estimated, and this is the radius derived from deep inelastic collisions of the proton. These estimates reveal a radius of approx. $r_p=1.18\times10^{-15}$ m This value may be used to assist in confirming the spin of the proton in revolutions per sec. (revs) and in turn the spin and size of the electron. Firstly we may proceed to estimate the spin of the proton. Thus as h=E·t (Joules×sec) and h=E·t=F·d·t (Joules×sec), then the spin;

$$h/4\pi=F\cdot d\cdot t \tag{28}$$

[0169] As F=ma, where $\alpha=(\text{revs}\cdot2\pi)^2 r_p$ and m=the mass of the proton, then

$$h/4\pi=m(revs\cdot2\pi)^2 r_p\cdot d\cdot t$$

[0170] The actual distance (d) traveled in a circle of half integer spin in 1 second is: revs·πr_p thus:

$$h/4=m(revs\cdot2\pi)^3 r_p{}^2/2$$

[0171] Hence:

$$revs=[h/m(2\pi)^4 r_p{}^2]^{1/3}$$

[0172] Taking the effective mass the proton as 1.6726×10^{-27} kg, then the rate of spin of the proton in revolutions/sec is:

$$revs=5.65\times10^{6}\text{ cycles/sec}$$

[0173] From the frequency of the specific rotation of the proton, given the half integer spin associated with the proton, we can thus mathematically confirm the relationship between the radius of a particle and its spin:

$$r_p\times revs/2=1/c \tag{29}$$

[0174] Furthermore, the fundamental radius of 1/c seen in geometric structure the quasi electron, is also reflected in the rotation rate and radius for the proton, thus as above 1/c÷½ revs=1.85×10^{-15} m. Moreover, this means the actual half integer velocity of rotation is none other than 2π/c in metres/sec. So that the particle is in harmonic balance.

[0175] Using the fundamental formula h/4π=F·d·t, it is possible to obtain accurate estimates of the radius and spin rates of the electron, or indeed any particle, using the same principle of harmonic balance. Using the formula:

$$revs=[h/m(2\pi)^4 r_e{}^2]^{1/3}$$

[0176] It appears there are two unknowns, the radius if the electron and its revolution rate, however, in accordance with the equation, r_p=2/c.revs, which gives the revolution rate of the proton, the same principle may also be used for the electron, by substituting r_e=2/c.revs, such that:

$$revs=hc^2/4m_e(2\pi)^4 \tag{30}$$

[0177] Taking the mass of the electron 9.109382×10^{-31} kg, the rate of revolution of the electron is:

$$revs=1.048\times10^{10}\text{ cycles/sec}$$

[0178] Which gives a predicted radius of the electron as

$$r_e=6.336\times10^{-19}\text{ cycles/sec}$$

[0179] So the half integer rotation velocity (revs.πr) is 2π/c !, for the electron in keeping with the harmonic balance of the electron.

[0180] The same principle may be used to obtain an accurate estimate of the spin and radius of the muon, or any other particle. Using the above formula

$$revs=hc^2/4m_e(2\pi)^4 \tag{31}$$

[0181] Then as the mass of the muon is 1.8823×10^{-28} kg then the revs of the muon $f_\mu=5.070\times10^{-7}$ cycles/sec and the radius r_μ is thus 1.316×10^{-16} m.

[0182] It is now possible to begin to explain how the muon and the other subatomic particles are formed. If a quasi electron is complexed with another structure the total geometric structure needs to maintain harmonic balance. So the frequency of rotation would need to match geometric structure with which the quasi electron was complexed

[0183] Intriguingly we find asymptotic convergence for the formulas for frequency and mass occurs, when the geometric structure complexed with the quasi electron has the structure represented by $(\pi/c^{1/3})$ [giving the frequency divided by two, because the single integer spin of the force carrying particles compares to a half integer spin for the muon]. So that

$$(f_r 3\pi/2)^{1/3}=f_\mu$$

[0184] When the ratio of the masses of the electron (m_e) and muon (m_μ) are related, such that:

$$m_e(3\pi/c^{1/3})=m_\mu$$

[0185] Indeed we find that (allowing for the neutrino) this ratio is very close to the actual ratio of the mass of the electron to the mass of the muon, determined experimentally.

[0186] Furthermore, we have seen that these geometric structures, representing harmonics of the speed of light, which either match the frequency or the amplitude of vibration of the quasi electron, mathematically define the masses of the particles and the fundamental forces of Nature.

Part III—Quantum Gravity

[0187] Quantum General Relativity

[0188] Given the overall energy "complex" energy tensor structure of the electron and the metric tensor, assumed in general relativity, the quantum nature of gravity itself can now be explored. The spherical complex tensor for the electron and the positron give the mathematical quantum structure and energy tensor for all the other particles. Together with the time dimension these nine space dimensions account for the 10 parameters present in the metric tensor necessary to formulate the equations for gravity using Riemann geometry and thus forms the basis of quantum gravity. Intriguingly the metric tensor at each point in space time is required to consist of a collection of ten numbers, Consequently, ten dimensional space-time hypotheses, such as this or superstring theory, do automatically yield general relativity.

[0189] Furthermore, the mathematical representation of the graviton and the gravitational constant may be directly estimated from the knowledge of the mass and radius of quintessence. Thence, the force of the vibrations of quintessence lead directly to quantum gravity.

[0190] The radius of quintessence should be approximately in keeping with the Planck length estimate (r), which is conventionally derived from the standard dimensional equation:

$$r_q^2\cong Gh/c^3 \tag{32}$$

[0191] Given the nine spacial parameters present in the metric tensor, used in general relativity we find that the actual formula for r_q^2 is mathematically in agreement with theory when:

$$9r_q^2=Gh/c^3 \tag{33}$$

[0192] This again supports the 9 dimensional view of space and the size of the vibrations of quintessence can thus be estimated.

$$r_q=1.35\times10^{-35}\text{ m} \tag{33a}$$

[0193] This value is in agreement with the Planck length. Indeed if the above equation is correct then we find that we can derive the standard equation for the general relativistic increase in radius, r', (eq. 34) directly from first principles and arrive at a more fundamental equation for quantum gravity. As

$$r'=G\cdot M/3c^3 \tag{34}$$

[0194] By substituting eq. 33) into equation 34, a fundamental relationship between r' and M is obtained.

$$r'/3r_q^2=GMc^3/Ghc^3=Mc/h$$

[0195] And substituting the quintessential equation, $h=m^q c^2$ (eq. 1) then:

$$r'/3r_q^2=M/m_q c=n_q/c \tag{35}$$

[0196] Hence the ratio of the change in radius to that of the radius of quintessence squared, is proportional, by a factor of c, to the ratio of the mass M of an object to that of the mass of quintessence, effectively the number of quintessences. Thus the change in radius, r' due to gravitation, is related to none other than the ratio of the mass and radius of an object to the mass and the square of the radius of quintessence. Thus again the gravitational change in radius is directly related to the number of quintessences.

[0197] Naturally, this would be exactly what would be logically expected if quintessence, like the equation for the charge of the electron (eq. 6) forms from a root sphere. Thus the change in spacial radius of a normal sphere is dependant on the square of the quintessential radius.

[0198] This increase in apparent radius represents none other than the (gravitational) binding energy for quintessence.

[0199] The meaning of the above dimensional equation (33) might itself be further understood by substituting the mass of quintessence (where $m_q=h/c^2$) into the equation. Thus in nine dimensions the gravitational constant (G) may be more logically given as,

$$9(\pi r_q^2/m_q)=G\pi/c \tag{36}$$

[0200] Where πr_q^2 is the cross sectional area of quintessence and m_q is the effective mass of quintessence, and thus

$(\pi r_q^2/m_q)$ represents the effective mass per unit area which quintessence exerts. This equation reduces to:

$$9r_q^2/m_q=G/c \tag{37}$$

[0201] From this we may derive the standard general relativistic relationship for the apparent change in radius (r') around a mass (M), from an understanding of the mass m_q and number (n_q) of quintessences. As $m_q=M/n_q$, then:

$$3r_q^2=G\cdot M/3c\cdot n_q \tag{38}$$

[0202] Then if

$$n_q=r'c/3r_q^2 \tag{39}$$

[0203] thus directly substituting for n_q in eq. 38:

$$r'=G\cdot M/3c^2 \tag{34}$$

[0204] The importance of this is that the gravitational change in radius now logically derives from equation 36, which describes the gravitational force as resulting directly from the mass of quintessence exerted/per unit area of quintessence.

$$9(\pi r_q^2/m_q)=G\cdot\pi/c \tag{36}$$

[0205] Thus equation 34 is the conventional equation for the general relativistic increase in radius (r') in a gravitational field, which is here derived from the underlying nature of quintessence. Thus the gravitational constant is derived from the mass and radius of vibration squared of quintessence from first principles.

[0206] Indeed it is apparent that a more fundamental equation for gravitation now exists, for equation (39) is mathematically accurate and numerically agrees with eq. 34:

$$r'/3r_q^2=n_q/c \tag{39}$$

[0207] These equations may be readily mathematically verified. If in accordance with standard general relativity, the apparent increase in radius r' is:

$$r'=GM/3c^2 \tag{34}$$

[0208] Then given that the mass of the Earth is 5.9745×10^{24} kg;

$$r'=1.478\times10^{-3}\text{ m}$$

[0209] Accordingly if $r'=3r_q^2\cdot n_q/c$; (eq. 39). Given the number of quintessences n_q constituting the Earth is M_E/m_q, then

$$n_q=5.9745\times10^{24}/7.3725\times10^{-5}=8.104\times10^{74}$$

[0210] As $r_q^2=1.823\times10^{-70}$ (eq. 33a) then:

$$r'=1.478\times10^{-3}\text{ m}$$

[0211] Thus equation 39 gives the same answer as the standard equation and may be understood on a logical basis. Indeed the meaning of c in the equation may be understood as it has been previously shown as being the basis for the radius of matter (eq. 6). Hence the general relativistic change in radius, r', is none other than the effective binding energy for quintessence.

[0212] Quantum Gravity and Wave Particle Duality

[0213] Quantum gravity can now be readily linked with quantum mechanics, indeed any observations which are self consistent must be able to do so easily.

[0214] The frequency of light has been previously derived

$$f=E/h=n_q$$

[0215] Thus the formula for the frequency of light (E=hf) has previously been explained theoretically by the simple observation that the frequency is determined quite directly from the number of quintessences (n_q) within the photon. The same principle has also been shown to apply to matter.

[0216] Let us now follow these equations for matter by calculating the wavelength of a photon from the Gravitational constant as an example; and also as a test of these observations and to demonstrate that the gravitational equations can also apply to the quantum world.

[0217] If

$$n_q=r'c/3r_q^2 \tag{39a}$$

[0218] where r' is the general relativistic increase in radius, and r_q is the radius of quintessence (eq. 33). Where $f=E/h=n_q$, substituting for n_q, then the frequency of the photon f_γ(where $\beta=1$) is given by:

$$f_\gamma=r'c/3r_q^2$$

[0219] Using the standard equation, $r'=GM/3c^2$ (eq. 34); we may substitute for r', thus we have:

$$f_\gamma=GM/9r_q^2c\ 15\text{ Thus}$$

$$f_\gamma=\frac{G}{9r_q^2c^3}\cdot m_\gamma c^2\text{ and as }E=m_\gamma c^2;$$

$$f_\gamma=\frac{GE}{9r_q^2c^3} \tag{40}$$

Indeed as $9r_q^2=Gh/c^3$, then $f_\gamma=E/h=n_q$

[0220] It is possible to also demonstrate that the same relationship holds for the wave equation for matter. If we take the relativistic wave energy of matter, which has been previously derived,

$$f=\beta^2n_q$$

[0221] This includes the term for the number of quintessences flowing through the electron, in the complex vectors of space-time, to give the relativistic electron momentum (p) and a term for the rest mass, thus substituting into (40)

$$f_\gamma=\frac{GE}{9r_q^2c^3} \tag{40}$$

[0222] As $f=\beta^2n_q$ for matter then the equation expands to:

$$f_m=\frac{G}{9r_q^2c^3}\cdot\beta^2E\text{ As }\lambda=v/f\text{, then}$$

$$\lambda=\frac{9r_q^2c^3v}{G\beta^2E} \tag{41}$$

[0223] Then the equation again reduces to:

$$G = \frac{9r_q^2c^4}{\lambda\beta E} \tag{3}$$

[0224] Equations 3, 40 and 41 are important as they show that the quantum wavelength of any particle of rest mass m can be derived from the gravitational constant G. Thus linking quantum mechanics to quantum gravity.

[0225] It is therefore important to confirm the numerical accuracy of the above equation (40). We can do this by comparing the result to the standard computation of the de Broglie equation, in a range where de Broglie itself is likely to be most accurate; which according to these observations is in the low energy range (see section on Wave Particle Duality).

[0226] If we take an electron with an energy of 0.1 KeV the wavelength is conventionally given (where the kinetic energy of the electron E_k is given by the product of the charge of the electron (C) and the potential applied eV=0.1 Kev), by the standard equation:

$$\lambda = h/p = h/(E_k \cdot 2m_0)^{1/2} \text{ thus}$$

$$\lambda = 6.63\times10^{-34}/[1.602\times10^{-19}\times1\times10^{2}\times18.22\times10^{-31}]^{1/2}$$

$$\text{hence}$$

$$\lambda \cong 1.23\times10^{-10}m \text{ Using}$$

$$\lambda = \frac{9r_q^2c^4}{G\beta E} \text{ Where } E = \gamma m_0c^2 \tag{3a}$$

[0227] At 0.1 Kev, electron velocity is 6×10^6 r/sec, thus $\beta=2\times10^{-2}$ and $\gamma=1/(1-v^2/c^2)^{1/2}=1.0002$. Thus:

$$\gamma = \frac{9\times1.82\times10^{-70}\times80.78\times10^{32}}{6.76\times10^{-11}\times\beta\times1.0002\times9.11\times10^{-31}\times8.998\times10^{16}}$$

$$\lambda = 1.21\times10^{-10}m$$

[0228] Divergence between the de Broglie equation and the above equation (2) occurs at intermediate and high energies where it is generally accepted that the standard de Broglie equation may be less accurate. The values for eq. 2 and de Broglie are compared to recent experiments, which demonstrate a relativistic curvilinear plot for wavelengths of matter in keeping with eq. 40.

[0229] The de Broglie equation in the non-relativistic format yields a simple log/linear scale, which is not in keeping with relativity; whereas eq. 3 is dependent on relativity and mathematically accounts for both relativity in calculating the wavelength. Indeed recent experiment on quantum tunnelling through a wire mesh strongly suggests that the relationship between energy and wavelength is relativistically curvilinear(ref 1). Furthermore equation 3a suggests a fundamental relationship between energy (E), relative velocity (v/c=.β), gravity (G) and the quantum wavelength (λ)

$$\lambda = \frac{9r_q^2c^4}{G\beta E} \text{ Indeed as } {}^9r_q^2 = Gh/c^3\text{, then} \tag{3a}$$

$$\lambda = hc/\beta E \tag{2}$$

[0230] Equation 2 is the very same as the Universal wave equation derived form first principles for the wavelength of tight and matter, which allowed a relativistic solution to the equations for wave particle duality (see Wave Particle Duality). This now indicates that these quintessential equations are compatible with relativity, quantum mechanics and quantum gravity.

[0231] Graviton Structure

[0232] From these observations, if the value for the gravitational constant is substituted into the equation (35) we may now estimate the probable geometric structure of the gravitation, which is the force particle mediating gravity by acting on quintessence. Thus the Gravitational constant has been previously derived from the vibration of quintessence by the equation:

$$G\cdot(\pi/c)=9(\pi r_q{}^2/m_q) \tag{36}$$

[0233] This is in accurate agreement with the value for G(6.67×10^{-11} N m^2 kg^{-2}). This suggests that the most probable mathematical representation of the graviton (ϕ), the third force carrying particle is

$$\phi=(\pi/c) \tag{42}$$

[0234] Thus the gravitational constant (G) can be given by the mass and radius of quintessence and the structure of the graviton

$$G=9\pi r_q{}^2/\phi m_q \tag{43}$$

[0235] This shows the gravitational force to be related to the fundamental radius of quintessence space time, and the graviton.

[0236] Quantised General Relativity

[0237] The classical general relativistic formula, as given by Einstein is:

$$R_{\mu\nu}-1/2g_{\mu\nu}R=-\kappa T_{\mu\nu}$$

[0238] Where R is effectively the curvature of space-time, $R_{\mu\nu}$ denotes the contracted Riemann tensor of curvature and $T_{\mu\nu}$ is the "energy tensor" of matter.)

[0239] If we substitute the energy tensor matrix of the electron (eq. 9)×time, for the energy tensor of matter $T_{\mu\nu}$; and the metric tensor of the space-time lattice×time for the contracted Riemann tensor we can arrive at the same solutions for general relativity.

[0240] Furthermore, in his published paper on General Relativity, Einstein. defined the constant κ as:

$$\kappa=8\pi G/c^2$$

[0241] Therefore Einstein's equation should be written as

$$R_{\mu\nu} - 1/2g_{\mu\nu}R = \frac{8\pi G}{c^2}\cdot T_{\mu\nu} \tag{43}$$

[0242] Einstein himself was apparently not happy about the right hand component of the equation. However, we find that this part of the equation can now be explained and quantised by substituting the gravitational constant, $G=9\pi r_q^2/\phi m_q$, (eq. 42a),

[0243] Giving:

$$R_{\mu\nu} - 1/2g_{\mu\nu}R = -\frac{8\pi^2 9r_q^2}{\varphi m_q c^2} \cdot T_{\mu\nu} \tag{44}$$

[0244] By substituting $m_q \cdot c^2=h$, and further substituting h=h/2π, we arrive at a quantised solution to Einstein's equations. Where A_q is the surface area of quintessence ($A_q=4\pi r_q^2$); φ is the graviton [φ=(π/c)] and h is Plancks constant. thus:

$$R_{\mu\nu} - 1/2g_{\mu\nu}R = -\frac{9A_q}{\varphi\hbar} \cdot T_{\mu\nu} \tag{45}$$

[0245] The gravitational equation can now be further understood on a logical basis. The term $A_q=(4\pi r_q^2)$, where represents standard term for the surface area of a sphere of quintessence for the 9 space dimensions of the space time lattice, h is the energy content of quintessence×time and φ is the graviton, thus the right hand term now represents a true "metric energy tensor" of matter.

[0246] This leads directly to the standard solution to the field equations, for the general relativistic increase in radius r' of an object, where A is the surface area of a sphere of a given mass M, such that

$$r=\sqrt{(A/4\pi)}-r=GM/3c^2 \tag{34}$$

[0247] Furthermore, although equation 45, gives the same solutions as Einstein's equation, which is essentially correct, the difference is that the equation is now dependant upon Planck's constant (h), and moreover the radius of quintessence, which now defines a quantised solution to the equations.

[0248] Graviton Force Characteristics

[0249] Similar to the photon, the previously derived equation (42) for the graviton [φ=(π/c)] appears to also mathematically represent a helical ringlet of quintessence, but with a spin of 2. For the photon, taking the direction of motion as the x vector and its axis of spin also as the x vector, would account for the electromagnetic force and its attraction and repulsion characteristics. In the case of the gluon component ($\pi/c^{1/2}$), if the direction vector is x, then the axis of spin would be in the y vector, the same as quasi electrons, accounting for the particle binding characteristics of the gluon force. In the case of the graviton, if the direction of motion was in the x vector, the graviton spin axis would be in the z vector thus, as will be demonstrated, accounting for the gravitational force.

[0250] The spin axis of the graviton can also be derived using the known characteristics of the electron. If an electron is travelling in the x direction, then its spin axis is determined by the by the sign of the $_j$y vector (up or down). This view is in agreement with conventional theory, which indicates that the electron spin is similar to a rotating planet orbiting the sun, (the electron even appears to have orbital precession). As the electron passes through the space-time lattice, this spin would generate the formation of gravitons. This would occur as a result of the ejection of the excess quintessence passing through the electron. As the electron spins, the ejection of these gravitons would occur at a tangent to the electron's direction of motion. The ejection of the gravitons would occur, similarly to the ejection of energy of a pulsar or quasar, through the equivalent of the north and south poles of the electron. Thus, propelling the graviton in the direction of the electrons y vector. The ejection of the graviton would re-orientate and impart a specific angular momentum to the gravitons which would thus end up spinning on its own z axis. If for instance the graviton is released from an up spin electron the graviton will be rotating clockwise and its leading edge will displace quintessence downwards. In turn this will provide an upwards force.

[0251] This picture accounts for Fleming's left hand rule, is logical and provides an explanation for the magnetic force around a wire. According, to the left hand rule if the direction of the current is in the x vector, the magnetic field is in the z vector, and the force is upwards, in the y vector, in accordance with the above model. Therefore, this particular spin axis and the structure of the graviton results in its force characteristics. As the graviton is very small compared to the electron and both have different rather rapid spin axis it is difficult for these to bind and interact. Nevertheless, because the graviton has a spin of 2, and as it spin axis is perpendicular to its direction of motion, in the z vector, it readily displaces space-time quintessence to produce gravity. Thus because the graviton is able to displace space-time, it is capable of escaping a black hole. How else could the effects of gravity be felt beyond a black hole?

[0252] Quantum Gravity and Electromagnetism

[0253] With the above electron model of graviton production the nature of magnetism can be understood from first principles, Furthermore, the presence of a space-time lattice links relativity, and the forces of gravity with the electromagnetic and other forces of Nature. Indeed, evidence for these links may first date back to the 1820's, when Andre Ampere first defined the Amp. The force of attraction between two parallel wires 1 metre apart each carrying 1 Amp in a vacuum was defined as none other than the permeability of free space (2×10^{-7} N per metre of conductor). Thus conventionally the magnetic field strength around a long straight wire is given as:

$$B=\mu_0 I/2\pi r$$

[0254] Where I is the current and μ_0 is the permeability of free space ($4\pi\times10^{-7}$ N A^{-2})

[0255] The attraction between two wires both carrying negative charge is, however, counterintuitive as negative charges should repel. A conventional explanation overcomes this by invoking the presence of a magnetic field which is created by the current by the production of virtual photons. Thus we appear to have an explanation for the effects of magnetism which involves virtual photons, however, these photons are not observed. More accurately, according to conventional special relativity the magnetic field is none other than the electric field viewed relativistically.

[0256] A more satisfactory explanation, therefore, lies in the interaction between the electrons and the space time lattice. The moving electrons in the two wires interact with the lattice to produce gravitons; which are in phase when both streams of electrons are traveling in the same direction. The gravitonic waves interact constructively to disperse the space time lattice between the wires and induce an attractive force between the two wires, which produces in effect the permeability of free space. Thus this force results from the vibration of quintessence itself.

[0257] Conversely in two wires with current going in opposite directions the graviton waves are in anti-phase and would interact destructively between the wires. The gravitonic waves traveling radially outward from the wires would, however, disperse the lattice outside the two wires and produce apparent repulsion between the wires, which is exactly what is observed. These effects of electricity suggest that gravitons act as waves and that phase is important.

[0258] This effect is also seen with the north and south poles of ferromagnets. Nevertheless, with matter other than iron, cobalt or nickel, the graviton emission cannot be phased as the atoms are unable to align and magnets do not appear to exist with other materials.

[0259] In ordinary magnetic system the release of gravitons from the north pole would be exactly balanced by those released from the south pole of the magnet and hence there would be no net force on the magnet until an external magnet or electrical current were applied.

[0260] Overall the magnitude of the forces in electrical systems where electrical conduction occurs are well defined by the permeability and permittivity of free space μ_0, and ϵ_0. Where v is the constant velocity of the charge and ϵ is the electric field produced by the charge.

$$B=[\mu_0\epsilon_0]v\cdot\epsilon$$

[0261] These observations suggest that the forces of electricity which produce magnetism are indeed related to the permittivity and permeability of free space and that these quantities are exerted by an apparent vacuum. Thus the effects of magnetism could be explained by none other than the phased effects of gravitational waves on the space time lattice.

[0262] Electromagnetism is of further interest to quantum gravity, particularly if we combine the standard equations, $B=\mu_0 I/2\pi r$ and $B=[\mu_0\epsilon_0]v\cdot\epsilon$, substituting for B we have:

$$2\pi r=I/\epsilon_0 v\epsilon \qquad (46)$$

[0263] Thus $2\pi r$ is proportional to the inverse of ϵ_0. Thus as space time is dispersed by gravitons the permittivity field will increase in the same way capacitance increases with separation of plates. Because of the inverse relationship between ϵ_0 and $2\pi r$, as ϵ_0 increases the circumference of a circle and the apparent ratio of π is to r, will appear to diminish in accordance with general relativity. This not an actual diminution in the circumference of a circle but the effective reduction of the resistance to motion in a circular path in this field.

[0264] Incidentally, the above observations, also lead us directly to Schrödinger's formula for the average equilibrium distance (r) between an electron with charge (e) in orbit around a proton, which is conventionally given by:

$$r=n^2 4\pi h^2\epsilon_0/me^2$$

[0265] Where ϵ_0 is again the permittivity of free space, m is the mass of the electron and n is an orbital integer, h is Planck's constant and e is the charge of the electron. Furthermore if $e=[\epsilon_0/3(4/3\pi c^3)]^{1/2}$ (eq. 3); then the equation at n=1, for the electron orbital radius elegantly simplifies to:

$$r=4h^2c^3/m$$

[0266] Hence the orbital radius of the electron is related to spin of the electron (h) and its mass (m).

[0267] Quantum Gravity and the Charge of the Electron

[0268] The equation for the charge of the electron (eq. 1) contains the term so (permittivity of free space) which according to these observations should vary in a gravitational field.

$$e=[\epsilon_0/3(4/3\pi c^3)]^{1/2} \qquad (6a)$$

[0269] If we combine the standard equations, $B=\mu_0 I/2\pi r$ and $B=[\mu_0\epsilon_0]v\cdot\epsilon$, substituting for B we have:

$$2\pi r=I/\epsilon_0 v\epsilon \qquad (46)$$

[0270] Thus $2\pi r$ is proportional to the inverse of ϵ_0. Thus as space time is dispersed by gravitons the permittivity field will increase in the same way capacitance increases with separation of plates. Because of the inverse relationship between ϵ_0 and $2\pi r$, as ϵ_0 increases the circumference of a circle and the apparent ratio of π to r, will appear to diminish in accordance with general relativity.

[0271] Thus ϵ_0 rises when space-time is dispersed by the gravitons that produce the gravitational field, This occurs in a similar way to the process by which capacitance increases with separation of plates in a capacitor.

[0272] Nevertheless, as c is a constant and as $c=[\mu_0\epsilon_0]^{-1/2}$, then if ϵ_0 rises then μ_0 falls. This is entirely consistent as μ_0, which represents the force that quintessence exerts, would be reduced if the quintessence space time lattice is dispersed.

[0273] Furthermore, as $\mu_0=4\pi\times10^{-7}$ N A^{-2}; then as μ_0 falls, then the apparent ration π to r, also falls in a gravitational field. This is largely the same as stating, as does general relativity, that the apparent radius r', rises in a gravitational field. So this view is consistent with general relativity.

[0274] Nevertheless, to derive an exact value for the charge of the electron we must account for gravity in the above equation. We will take the specific example of the Earth's gravitational field in order to obtain the exact value for the electron. If in accordance with standard general relativity, the apparent increase in radius r' is:

$$r'=GM/3c^2 \qquad (34)$$

[0275] Then given that the mass of the Earth is 5.9745×10^{24} kg; then

$$r'=1.47864\times10^{-3}\text{ m}$$

thus

$$2\pi r'=9.29057\times10^{-3}$$

[0276] Which is the incremental factor by which ϵ_0 must increase in Earth's gravitational field. So to correct ϵ_0 to account for gravity, ϵ_0 must be divided by the incremental factor, $2\pi r'$. Similarly as effectively π decreases in a gravitational field, to correct π to account for gravity it must be multiplied by this incremental factor. So the equation for an electron in a zero gravitational field is:

$$e=[\epsilon_0/3(4/3\pi c^3)]^{1/2}\div(1+2\pi r')=1.6022\times10^{-19}\text{ C} \qquad (6b)$$

[0277] This now gives the charge of the electron as measured in a zero gravitational field as 1.6022×10^{-19} C, which is the same as that measured on Earth. Notably these observations appear to suggest that the charge of the electron is the same irrespective of the gravitational field.

[0278] Virtually unlimited degrees of accuracy for the charge of the electron and for the fine structure constant (α), may be achieved by taking into account 2nd and nth order gravitometric effects. Thus if we take into account the effect of gravity upon the radius of the Earth it is also important to take into account an effect upon the instruments with which we measure quantities, this would be a second order gravitometric effect. Thus taking into account 2nd order effects (r''), we have a very small, but nevertheless relevant change, such that: $r''=r'(1+2r')$. Thus $2r''=9.3180486\times10^{-3}$, and thus:

$$e=[\epsilon_0/3(4/3\pi c^3)]^{1/2}\div(1+2\pi r'')=1.6021765\times10^{-19}\text{ C} \qquad (6c)$$

[0279] This agrees exactly to the nearest 7 decimal places with the maximum accuracy of the experimental value for the charge of the electron. Furthermore by taking into account the nth order gravitometric effect, it is theoretically possible to predict accuracy for the charge of the electron to 3n decimal places. This mathematically accuracy confirms the structure of the electron from first principles and indeed the theoretical effects of gravity on the permittivity of free space (ϵ_0).

[0280] This returns us directly to the fine structure constant for the electron which is conventionally given by: $\alpha=e^2/hc\cdot4\pi\epsilon_0$. If $\alpha=e^2=\epsilon_0/3(4/3\pi c^3)$, accordingly the quintessential equation for α is structurally given by: $2\pi/\alpha=m^q[3\Theta]^2$ (where $\Theta=4/3\ \pi c^3$; see The Structure of the Electron and Matter), we must now take into account the effects of gravity, as above, thus:

$$2\pi\alpha/m_q[3\Theta]^2\div(1\_\_2\pi r'')^2=0.007297353$$

[0281] Where the gravitational term for the increase in radius r'' allows the mathematical derivation of $\alpha=0.007297353$, and the above equation is in agreement with the conventional experimental value for $\alpha=0.007297353$ to the nearest 9 decimal places.

[0282] Hence the term $(1\_\_2\pi r'')^2$ is in accordance with these observations for the effect of gravity on electromagnetic forces. To a maximum accuracy governed by current knowledge of the mass of the Earth and the Gravitational constant and thus the term for the gravitational increase in radius r'. These observations can also be used to accurately predict the magnetic moment of the electron

[0283] Thus the presence of the fine structure constant can now be further understood, by deriving the constant from first principles; specifically from the actual dimensional conformation for the charge of the electron: $e=[\epsilon^0/3(4/3\pi c^3)]^{1/2}$ (eq. 6).

[0284] Overall the fine structure constant α (allowing for the term r' which is the general relativistic increase in the radius of the Earth due to gravitation) is given by none other than the formula for the mass of quintessence and from the structure of the electron, which can now be derived from first principles to seven decimal places or more.

[0285] Quantum Gravity and the Electron Magnetic Moment

[0286] The theoretical origin and nature of magnetism remains obscure in current electromagnetic theory. An explanation suggests these magnetic effects are produced by photons, although no photons have ever been observed. To get round this difficulty it is postulated by physics that magnetism results from "virtual" photons. However, Maxwell's equation for electromagnetism states that the photon has no net magnetic effect.

$$\delta B_x/\delta B_y/\delta y+\delta B_z/\delta z=0$$

[0287] Thus magnetism could not, by the above standard equation, be derived from a photon real or virtual.

[0288] In addition observational data suggests that black holes have powerful magnetic fields and as in theory photons are unable to escape from black holes (except for small quantities in the form of Hawking radiation), it would be difficult to explain these magnetic fields on the basis of photon emission.

[0289] Einstein postulated that magnetism was merely due to special relativity .sup.(ref 17). The postulate for the nature of magnetism in these current observations, states that the magnetic force results from relativity due to none other than the phased emission of gravitons (why postulate two invisible forces, magnetism and gravity, when one, the graviton, will do). This view as previously discussed (Quantum Gravity and Electromagnetism) is entirely compatible with standard relativity(ref 19). Thus with the graviton origin of magnetism, the equation for the magnetic moment of the electron should have an expression in terms of quintessence and in turn the gravitational force and in particular the graviton.

[0290] The standard term for the magnetic moment of the Bohr Magneton (SIB) is:

$$\mu B=eh/4\pi m_e$$

[0291] In standard quantum mechanics the Bohr Magneton, μB, however, needs to be corrected to agree with experiment. The "correction factor" is termed "ϵ"; where $\epsilon=(\alpha/2\pi)-0.328\alpha^2/\pi^2=0.001159641$. Thus theory reveals μ_e, the magnetic moment of the electron where:

$$\mu_e=(eh/4\pi m_e)[1+(\alpha/2\pi)-0.328\alpha^2/\pi^2]$$

[0292] The conventional derivation of the term ϵ above, is given from the fine structure constant, ($\alpha/2\pi$) which is theoretically consistent. However, a rather arbitrary mathematical correction term; $0.328\alpha^2/\pi^2$ needs to be used in this standard equation. This appears ad hoc and needless to say, more accurate measurements show, the electron magnetic moment to the Bohr magneton ratio, $1+\epsilon=1.001159652$, which suggests the correction factor is indeed incorrect. Nevertheless, this correction factor is essential for "renormalisation" and thus for quantum mechanics to work.

[0293] Quantum gravity readily explains the discrepancy between the theoretical Bohr Magneton (μB) and the actual measured magnetic moment of the electron (μ_e). In accordance with the above chapter (Quantum Gravity and the Charge of the Electron)

[0294] Thus the significant mathematical discrepancies can be removed by accounting for the effects of quantum gravity.

[0295] Thus taking the charge of the electron (e), using the equation for the Bohr magneton and the effects of quantum gravity such that gravitational change in radius is r". The magnetic moment of the electron is given by:

$$\mu_e=(eh/4\pi m_e)(1+[\alpha/2\pi\div(1+r'')])$$

[0296] This gives an electron magnetic moment to Bohr magneton ratio of 1.00115968. Thus the mathematical term for the magnetic moment of the electron is given, avoiding the arbitrary and dubious term $0.328\alpha^2/\pi^2$ used in the standard equation, simply by accounting for quantum gravity.

[0297] It is now possible to unite the equations for gravity and magnetism by substituting the fundamental key equations of quantum gravity. Thus if: $h=3m_qc^2$ (eq. 1b) and $m_e=m_qn_q$ (eq. 2). Then we can express the magnetic moment of any particle with the charge of the electron, including the proton, in terms of the number of quintessences (n_q) in that particle.

$$\mu B=ec^2/(4/3\pi n_q); \tag{47}$$

[0298] Given that the postulated structure of the graviton is: ($\phi=\pi/c$) (eq. 42), then substituting we have

$$\mu B=3ec/4\phi n_q \tag{48}$$

[0299] Showing that the equations for the magnetic moment are compatible with the gravitational equations given earlier. Principally, the quintessential equations now allow the determination of the magnetic moment of any charged object from the equation for the graviton and directly from the number of quintessences it contains. In conventional physics the magnetic moment of the electron requires a correction factor, $(1+(\alpha/2\pi c)-0.328\alpha^2/\pi^2)$, to derive the correct experimental value. These observations herein, indicate that the correction factor is more logically (1+r"), where r" is the general relativistic increase in radius around a gravitational body. This suggests that magnetism is not only affected by gravity, but can, as shown as above, be derived using the quantum gravitational equations.

[0300] Quantum Gravity and Special Relativity

[0301] Ordinary matter passing through the lattice would produce gravitons which would interact with space-time as described by general relativity. The quantity of gravitons would be determined by the apparent mass and in turn these would apparently curve space time. The geometry of this "curvature" is elegantly described by general relativity using Riemann geometry, specifically using metric tensors. Intriguingly the metric tensor is not a single number, but at each point in space time it is required to consist of a collection of ten numbers, Consequently, ten dimensional space-time hypotheses, such as this or superstring theory, may automatically yield general relativity

[0302] General relativity is indeed very elegant, nevertheless there was a logical step yet to answer. That is, how do gravitons shape space time? This can now be readily answered by considering the interaction of a three dimensional space time lattice with gravitons themselves to produce the effects of gravity. The effects of gravity are as such to compel a body in motion towards the gravitational object and to a much smaller extent visa versa. This effect can only be produced If gravitons repel quintessence (the constituents of the 3D lattice). Indeed, it has been stated that in order to explain cosmic inflation and the "flatness" of the Universe that quintessence must shun (or be shunned by) matter.

[0303] In descriptive terms a body close to a large mass will have a tendency to move toward it because the three dimensional lattice would be less dense as it approached the surface of the large mass. Overall there would be less resistance to motion in the direction of the large mass, and the motion in this direction would be facilitated by the vibration of quintessence.

[0304] In general relativity the principle governing motion is the geodesic of least distance, this can be re-expressed using similar equations using least action. Furthermore, the concept of motion due to the vibrations of quintessence is more logically and experimentally compelling.

[0305] These observations can now be used to link general and special relativity. Thus as we approach the speed of light, the mass of an object travelling through the space-time lattice would approach infinity, directly because the number of quintessences passing through a body would increase with increasing velocity, hence the equation:

$$m'=m_0/(1-v^2/c^2)^{1/2} \tag{50}$$

or

$$m'=m_0/(1-v^{2\,[\mu}{}_0\epsilon_0])^{1/2} \tag{50a}$$

[0306] In turn this would generate increasing gravitons and accordingly this would explain the observed effects of special relativity. Time itself is due to passage through the space-time lattice, and where the space-time lattice is dispersed by gravitons, time and length are reduced with increasing velocity and hence increasing space-time lattice dispersion, similar to the way in which gravity alters space-time

[0307] As a result:

$$t'=t(1-v^2/c^2)^{1/2},\ l'=l(1-v^2/c^2)^{1/2}$$

[0308] Thus resulting in the effects of special relativity.

[0309] Quintessence and Black Holes

[0310] To address the relationship of the space-time lattice to gravity directly, it is important to discuss the concept of quintessence with regard to general relativistic equations. The standard general relativistic equation for the apparent increase in radius (r) due to the curvature of space time around a gravitational object, which has also been previously derived from first principles (eq. 36), is:

$$r'=GM/3c^2 \tag{34}$$

[0311] This can also thus be written as:

$$3r'=GM[\mu_0\epsilon_0] \tag{51}$$

[0312] This standard equation, is in keeping with the above observations. Specifically, as the mass increases, ϵ_0 increases, in turn the radius will appear to increase (relative to π).

[0313] The above observations now allow us to examine the effects with regard to the interior of black holes themselves. The event horizon would represent a critical density for quintessence, in which light could not escape. The Schwarzschild radius would now be given by:

$$R_s=2GM[\mu_0\epsilon_0]$$

[0314] The event horizon will occur at the point at which there is less resistance to circular motion than motion in a straight or partially curved line. Given that π is proportional to $1/\epsilon_0$. The event horizon should occur when the permittivity has increased by a factor of π.

[0315] Effectively because the permittivity of free space rises, π decreases. This is entirely in keeping with general relativity which predicts the effective change in the ratio of the radius to the circumference as given by the conventional equation, where r', is again the apparent change in radius.

$$r=GM/3c^2$$

[0316] Hence π will effectively decrease as we approach the event horizon of a black hole, When π decreases to 1, the circular circumference is equal to the diameter and moreover, inside this limit it is shorter for light to travel in a circle. Thus light cannot escape the event horizon.

[0317] This can give us great insights into the workings of space-time, for flat Euclidean space the standard equation is:

$$e^{i\pi}=-1$$

[0318] In accordance with general relativity, the ratio of the radius to the circumference changes in a gravitational field, and effectively π=1, at the event horizon, thus the boundary condition for the shape of space-time at the event horizon now has the direct equation:

$$e^{f}$$

[0319] Within a black hole as the permittivity of space increases by a factor of 2π an object within it will complete two rotations rather than travel in a straight line. In effect exceeding the speed of light by 2π. Hence, the condition for space-time is represented by the equation:

$$e^{i/2}$$

[0320] Thus an increase in the permittivity of free space by a minimum factor of π, to produce a black hole is estimated to result from an increase in mass by a factor of approx. 10^6 (the ratio of the mass of the earth and that of a putative black hole).

[0321] Continuing with the subject of a black hole, according to the model inside the black hole, the gravitons produced by the matter present would be in equilibrium with the density of the space-time lattice. Increasing the rate of rotation of the matter in the black hole for instance would thus increase the production of gravitons and its effective mass and increase the radius of the event horizon. A density gradient of the space-time lattice would continue to exist within the black hole. Progressively closer to the center of a black hole matter itself would be increasingly compressed and the spherical structure of the quasi electron would be predicted to collapse. This collapse would result in the formation of an exotic form of matter in the form of pure quintessence in a black hole.

[0322] This pure quintessence would produce the singularity at the centre of the black hole. The larger the black hole in terms of mass the more pure quintessence would exist at its core.

[0323] Quintessence and the Big Bang

[0324] Quintessence theory not only predicts the occurrence of the Big Bang, but allows a prediction for the value of the entire mass of the Universe, from first principles.

[0325] In accordance with quintessence theory the big bang resulted from the explosion of an immense black hole singularity, which was constituted from pure quintessence.

[0326] On the basis of quintessence, there will be a critical mass for Big Bang event; thus if entire space-time between quintessence is compacted so that no further quintessence can be accommodated, the addition of further quintessence would destabilize the immense black hole, resulting in the Big Bang.

[0327] It is possible to predict this critical mass, using the radius of quintessence as a benchmark. Given the nine spatial parameters present in the metric tensor, used in general relativity we find that the actual formula for the radius of quintessence; r_q^2, is mathematically in agreement with general relativistic theory when:

$$9r_q^2=Gh/C^3 \tag{33}$$

[0328] This again supports the 9 dimensional view of space (so crucial in superstring theory). Moreover, the size of the vibrations of quintessence can thus be calculated as:

$$r_q=1.35\times10^{-35}\text{ m} \tag{33a}$$

[0329] The volume of each quintessence is thus:

$$4/3\pi r_q^3=1.0306\times10^{-104}\text{ m}^3 \tag{33b}$$

[0330] So to be accommodated within unit volume of space time, with no intervening apparent space time, (given that each of 9 overlapping quintessences are required) would require approx.

$$9\times10^{104}\text{ quintessences}$$

[0331] As the mass of quintessence is $m^q=h/c^2=7.373\times10^{-51}$ kg sec (eq. 1). Then the mass of the Universe, to two decimal places, is:

$$1.18\times10^{53}\text{ kg} \tag{33c}$$

[0332] This is in close agreement with a recent estimate of the mass of the Universe from COBE and other satellite data, which estimates the mass to be 100 trillion trillion trillion trillion tonnes (10^{53} kg)

[0333] Moreover, the early formation of the galaxies can be readily explained, it is likely that in such a big bang some very small black holes might have prevailed and that these formed the seeds of the galaxies we see today.

[0334] The event horizon, calculated from the Schwartzschild radius, of such an immense black hole is about 10^{26} m, which would have allowed Guth's inflationary component to the early expansion of the Universe.

[0335] In addition, inflation may result directly from the observation that once electrons have formed from the primordial soup of quintessence, they emit gravitons which in turn repel space time, which might also result in another cosmic inflationary cycle.

[0336] Most importantly quintessence theory explains the Big Bang from first principles and is capable of accurately predicting the mass of the Universe.

[0337] The Nature of Energy

[0338] These observations allow a fundamental understanding of energy. The quantum physical, minimum component of energy is Planck's constant; h. To define the minimal component of mass, using the standard energy equivalence formula; $E=mc^2$, such a minimal mass (m_q)

would be required to have the value equivalent to; $m_q=h/c^2$ (1). The total mass of a system (m) would then be; $m=m_q n_q$, where (n_q) is the number of these minimal units. Thence, the total energy of a system can be derived from the minimal energy; h, multiplied by the number of these energy units (n_q). Thus as, $E=mc^2$, then also $E=m_q n_q c^2$ and substituting $m_q=h/c^2$, the energy equivalence formula has the more logical formulation;

$$E=hn_q \qquad (1a)$$

[0339] Thus the energy of a system is equivalent to the minimal energy unit; h, multiplied by the number of those minimal energy units (n_q)

[0340] This leads directly to a deeper understanding of wave particle duality and the wave nature of matter.

[0341] This is encapsulated by the quintessential energy formulae

[0342] As conventionally $\beta \cdot E/c=p$, then

$$\lambda=h/p=hc/\beta E \qquad (2)$$

and

$$E=hn_q \qquad (1a)$$

then

$$\lambda=c/\beta n_q \qquad (2b)$$

[0343] Importantly, as indicated by equation (2b), energy having no quintessence; would have a wavelength of infinity. Specifically pure energy containing no quintessences, would have a lambda of infinity. According to quantum mechanics an infinite wavelength would result in the probability of that energy being anywhere. As energy itself has no electrical charge it would not be impeded by the permittivity and permeability of the three dimensional space-time lattice. Moreover, energy would not be detectable in three dimensional space-time, unless it interacted with matter, as in the EPR experiments. Indeed, energy is not observed when not bound to any form of mass or particle.

[0344] Thus equation 2b, takes us to our original assertion regarding the existence of pure energy.

[0345] Energy is not Bound by the Space-Time Lattice

[0346] Thus, as the EPR experiments suggest the existence of energy separate from matter and thus separate from the three dimensional space-time lattice, it is interesting to find that experiment suggests the existence of free energy in a continuum separate from space time and matter to produce the effects of quantum teleportation.

[0347] This is not, however, teleportation across an additional dimension, this is a term to describe in partially familiar terms the dissociation of energy from the three dimensional space-time lattice. As time is inextricably linked to each dimension of space, the effects of energy would be inextricably linked to the events, such as the creation of virtual particles, we see interacting within space-time. It is unlikely that observers have any direct day to day experience to explain quantum events. Nevertheless, quintessence theory may have given us a window into the hitherto hidden workings of the Universe. Thereby, the mystery of the uniformity of the Universe, across distances which the speed of light could not apparently traverse, is readily explained by the fact that the free energy contained in the Universe is not bound by the space-time lattice.

[0348] In the case of light, due to the exceedingly small masses involved, there would be relatively easy exchange of matter with free energy within a photon. This would make the photon the ideal experimental tool to look for energy which is not bound by matter and in turn energy which is not bound in space-time. Indeed, very recently Furusawa et al. have reported to have observed the transference of energy as photons from A to B, without those photons traversing space-time. This finding which has been supported using other experimental techniques, is very important as it suggests the existence of such free energy.

[0349] Overall, quintessence theory gives an a priori explanation for the concept of mass, the elementary particles, the forces of nature and quantum effects. It can equally be used logically to explain the inner physics of a black hole, the missing mass in the Galaxy, the expansion of the Universe, Guth's inflationary theory and predicts the Big Bang, from first principles.

[0350] Part IV: Applied Theory with the Intent to Create Closed Timelike Curves

[0351] Electron Bombardment of the Photosphere to Induce Gravitational Shift

[0352] Leveraging the above relationship between mass and quintessence we derive that if an electromagnetic radiation with velocity v strikes the event horizon singularity of rest inertial mass mi, and U is the electromagnetic energy absorbed by the singularity, then, according to Maxwell's prediction, a momentum q=U/v is transferred to it. Mass shift $d \cdot m_b$, dependent on the external electromagnetic energy, equals the inertial mass shift dependent on the increment of energy in the particle. Since in this case the inertial mass shift does not depend on velocity V, i.e., it is related only to the momentum q absorbed, it can be obtained by making p=0 in variation $\Delta H=H'-H=c[q^2+(m_i c)^2]^{1/2}-(m_i c)^2$ from the particles inertial Hamiltonian. Consequently, the expression of d_{m_p}, is written as:

$$d_{m_p}=\Delta H/c^2=m_i\sqrt{1+U/m_i c^2\left[\varepsilon_r u_{r/2}\left\{\sqrt{1+d/w\varepsilon^2+1}\right\}^2=1\right.}$$

[0353] Comparing now the expression of m_i and m_g we have $m_g=m_i-2dm_b$. By replacing m_b in this equation, given by equation above, we obtain the expression of the correlation between gravitational mass and inertial mass, i.e.,

$$m_g=m_t-2\sqrt{1+U/m_t c^2\left[\sqrt{\varepsilon_r u_{r/2}\{[d/we]^2+1\}^2-1}\right.}\cdot m_t$$

[0354] We see that only in the absence of electromagnetic radiation on the event horizon (U=0) is the gravitational mass equivalent to the inertial mass. Note that the electromagnetic characteristics, e, m and s do not refer to the singularity itself, but to the outside medium around the singularity (photosphere) in which the incident radiation is propagating.

[0355] Stable CTC Solution From Modified M-Theory

[0356] Our innovation is a method of creating an event where a dual membrane or dual boundary condition exists. We do this using generalization from a Misner space which has been modified if one analytically continues the maximal extended Misner Metric so that $ds^2=-du^2+dw^2+(dx^2)^2+(dx^3)^2$ to the Euclidean section so that u=iota zeta we obtain a Misner instanton on the section where w and zeta are both real. The Euclidean time, t, and the closed spacelike coordinate are both periodic, the later having a period of $2\Pi t^2$. Going back to the Lorentzian sector we find that the period of the closed coordinate becomes linearly dependent on the physical time. Using automorphic fields in the Hadamard function one can obtain a quantized condition for time. This gives us a figure on the order of the Plank time. This confines such a stable wormhole condition to the general area of the Plank scale in its modified form which is that area defined by the Membrane itself. As such, these Plank scale wormholes are the true source of the true virtual aspects of the vacuum and quintessence. The effects of the dual singularity system can be viewed as an overlap zone of two distinct space-times which have boundary conditions on both sides. As an object accelerates towards C it is this same boundary or horizon that object encounters when the Time defined horizon solution for the universe is imposed. At this point drawing upon Van Den Broeck's alterations for this space-time geometry to create a single closed Friedman-Robertson-Walker spacetime the space-time geometry can be represented by this equation $ds^2=dct^2-B^2[(dx-\beta fdct)^2]+dy^2+dz^2$ B can be any function that is large near the displacement device. We then consider this transformation as extended to four dimensional space-time with arbitrarily time dependent acceleration. We also present the device frame energy density T00 from a four dimensional calculation and note that the 4d classical calculation is everywhere finite.

[0357] Consider an Alcubierre interval given according to a remote frame's cylindrical coordinates by:

$$ds^2=(1-\beta^2f^2)dct^2+2bfdctdz-dz^2-dr^2-r^2df^2$$

where f is a function that is 1 at the location of the device and zero far from it.

[0358] Starting out with the first transformation z'=z–òct beta dct. Where b is first expressed here as a function of time ct. With some algebra for simplification this results in

$$ds^2=[1-\beta^2(1-f)^2]dct^2-2b(1-f)dctdz'-dz^2-dr^2-r^2df^2$$

Let g=1–f and this becomes

$$ds^2=[1-\beta^2g^2]dct^2-2bgdctdz'-dz'^2-dr^2-r^2df^2$$

[0359] Notice that this returned the original intervals form with a reversal on the sign of b and a reversal of the boundary conditions for g. Now we notice that at r=0, this interval becomes the interval for special relativity transformed to cylindrical coordinates. Thus, we have found a transformation to a frame based local to the device. One can also verify that in these coordinates the relevant affine connections vanish at r=0. a further proposed modification to this field we will reintroduce a time dilation term into the devices frame's interval. Only we will use different boundary conditions for it. We will keep A=1 both at the location of the device, and far from it, but allow it to become large in the warped region. This is achieved by the simplest means possible in the proposed field generation method. Since rotating kerr singularity under bombardment would produce an equal negative energy region. With the effect focused outward away from the device slightly by the relative alignment of the kerr singularity the actual inward going portion of such fields would overlap and cancel their effect out in the region of the device. This yields a space normal time region, which is again restored at the fringes of the outward going field. From the standpoint of a geometric picture of space-time around the device and extending outwards one has actually created a dual event horizon situation as far as time goes. The inner one is the shell of the canceled out field inside of which normal time flow is restored. The outer one is formed at the boundary where normal time resumes and within which we have a negative energy field.

SUMMARY OF THE INVENTION

[0360] The present invention is A method for the generation of a pseudo 2+1 dimensional anti-de Sitter space (DeDeo & Gott 2002) using two Kerr type positively charged rotating dilation singularities where one singularity is maintained as a axis of rotation or "reference" singularity, and the other "target" singularity is subjected to a differential electron flow so as to simultaneously pass above the photosphere of said singularity in its direction of rotation—prograde orbit—and contrary to its direction of rotation—retrograde orbit—to release a directed flow of gravitons in a sinusoidal oscillation simulating a rotational effect of the "target" singularity around the axis of rotation provided by the "reference" singularity, resulting in the creation of timelike curves in a compact time-oriented manifold permitting topology change from one spacelike boundary to the other in accordance with Geroch's theorem (Geroch 1967) which results in a method for the formation of G odel-type geodesically complete spacetime envelopes complete with closed timelike curves.

BRIEF DESCRIPTION OF THE DRAWINGS

[0361] **FIG. 1** is a schematic representation of the mechanism employed to house the components necessary to generate a 2+1 dimensional anti-de Sitter space, resulting in the creation of timelike curves in a compact time-oriented manifold

[0362] **FIG. 2** is a schematic representation of the G odel-type geodesically complete spacetime envelope created by the mechanism complete with closed timelike curves

DETAILED DESCRIPTION OF THE INVENTION

[0363] Principles of Gravity Distortion Time Displacement Systems

[0364] The theoretical understanding of quantum gravity allows the design of time displacement systems from first principles. It is unlikely that gravitons or Kerr singularities can be controlled in a precise way using current technology. Nevertheless, an understanding of three dimensional space-time and matter, does allow the design of elementary displacement systems. That is, systems whose displacement rely on direct warping space-time as opposed to the ejection of material to provide thrust resulting in time dilatational effects.

[0365] The background for these systems are already partially understood and quintessence theory allows their further development. For this invention, the formation of black holes in the laboratory represents a crucial step in understanding the mechanisms that underlay gravitational physics and in turn the warping of space-time. The existence of black holes permits the localized application of the Axial torsion Spin-Rotation Coupling Effect (Zhang & Beesham 2002) resulting in a Rotating Frame with Relativistic Factor (Zhang 2003) which can be used in the creation of a Alcubierre space time bubble under the Van Den Broeck modification of the Alcubierre geometry (Van Den Broeck 1999) resulting in a method for the generation of a pseudo 2+1 dimensional anti-de Sitter space (DeDeo & Gott 2002) using two Kerr type positively charged rotating dilation singularities where one singularity is maintained as a axis of rotation or "reference" singularity, and the other "target" singularity is subjected to a differential electron flow so as to simultaneously pass above the photosphere of said singularity in its direction of rotation and contrary to its direction of rotation to release a directed flow of gravitons in a sinusoidal oscillation simulating a rotational effect of the "target" singularity around the axis of rotation provided by the "reference" singularity. In this instance the space-time lattice would be repelled by gravitons in such a way as to disperse space-time quintessence in a circular fashion around each of the singularities, producing multiple event horizons around the simulated axis of rotation provided by the reference singularity.

[0366] The release of gravitons from the target singularity is controlled by differentially governing the electron flow across the photosphere with the use of powerful electric currents. In turn the differential direction of flow across the photosphere of gravitons would determine the direction of motion through the space time lattice and the resulting time displacement from one spacelike boundary to the other in accordance with Geroch's theorem (Geroch 1967) when implementing this approach it is important to remember that the black hole is not excited by the smashing of the clump as it "hits" the horizon. The hole is rather excited when the metric perturbation associated with the clump is "felt" by the background metric. The excitation event therefore constitutes a smooth process whereby in-fall of a clump from .rmb and through r+ serves as a source in the Teukolsky (1973) equation for small perturbations to the Kerr geometry (with appropriate boundary conditions at r+ and r∞). This is an important distinction with a great deal of relevance to the practical engineering of the displacement unit since we need to gauge the "driving" of QNR modes in terms of an e_ective coupling from clump in-fall.

[0367] What results is a method for resonant driving of the quasi-normal ringing (QNR) wave modes of the Kerr geometry of the target singularity. The micro black hole hyper-accreting at rates ÿ M. 1 M□sec. 1 from a neutrino cooled disk is pushed through to oscillate near resonance of its (l,m=2, 2) quadrupole QNR frequency due to the in-fall of compact mass over-densities from the cusp in e_ective potential on a dynamical time scale. This mode is induced via induced magneto-rotationally induced fluid dynamics in the ultra-relativistic region of the flow bounded from below by the marginally bound orbit radius: rmb If the QNR modes are fed resonantly for a few seconds of hyper-accretion, the enhanced amplitude of the oscillations yields a very high rate of energy deposition into gravitational waves. Indeed, the integrated energy deposition is large enough to "evaporate" the equivalent of a factor of a few times the total rest mass-energy of a single clump into gravitational waves, which in turn interact with the reference singularity

[0368] Application of the method described in the previous section results in translation outside of the cosmological horizon, where F(R)<0. The topology of the resulting geodesic, for large constant R, is mathematically equivalent to a Euclidean cylinder of the condition R×Sn where T is the coordinate along the cylinder. I± are located outside the future/past cosmological horizons, where R is timelike and T is spacelike. In the case of a rotating Kerr black hole, there are two circular photon orbits that can exist in the equatorial plane and be exploited to create a tipler sinusoid. One is a prograde orbit moving in the same direction as the black hole's rotation, while the other is a retrograde orbit moving against the black hole's rotation. Their radii are respectively given by

$$r1=2M(1+\mathrm{Cos}(2/3\ \arccos(-|\alpha|/M)))$$

$$r2=2M(1+\mathrm{Cos}(2/3\ \arccos(|\alpha|/M)))$$

where a is the angular momentum per unit mass of the black hole. The orbits fall in the range M greater or equal to r1 greater or equal to 3M greater or equal to r2 greater or equal to 4M The fact that a prograde photon or in or case cooper pair with Bose characteristics orbits the black hole at a smaller radius than a retrograde one can be attributed to the well-known Lense-Thirring effect, i.e., the dragging of inertial frames due to the black hole's rotation which we control and influence via electromagnetic induced load coupling with the open magnetic field lines threading the BH horizon. This dragging would cause charged cooper pairs to revolve around the black hole relative to a static observer at infinity. Thus, to such an observer, a prograde cooper pair would have to orbit at a smaller radius to compensate for the 'extra' angular momentum acquired, while a retrograde one would have to orbit at a larger radius to compensate for the 'lost' angular momentum. Indeed, in the limit of zero rotation, these two orbits coincide at r D 3M, giving the single circular orbit of the Schwarzschild black hole. Now, recall that orbits around the Schwarzschild black hole are necessarily confined to a plane passing through its center, because of the spherical symmetry of the space-time. However, the Kerr black hole space-time has only an axial symmetry (in addition to being stationary), and this raises the possibility of non-planar orbits. One could, for example, contemplate the existence of spherical Boseon orbits—orbits with constant coordinate radii that are not necessarily confined to the equatorial plane—around the Kerr black hole. Such orbits would be a nontrivial generalization of the two circular photon orbits that lie in the equatorial plane. At first it may seem a little surprising that such spherical orbits could even exist, but there is an interesting reason as to why they are possible. Note that an object in a spherical orbit would, in addition to moving around the black hole in the azimuthal direction, be undergoing some periodic motion in the latitudinal direction. This is only possible if there is a conserved quantity associated with motion in this direction, just as angular momentum is necessarily conserved by its rotational motion in the azimuthal direction. (This result can be seen, for example, using action-angle variable) Now, because the Kerr space-time has only axial symmetry, geodesics in it should have only two constants of motion, namely energy and angular momentum. However, Carter discovered the remarkable fact that geodesics in the Kerr space-time possess a third constant of motion. It turns out that Carter's new constant governs the motion of geodesics in the latitudinal direction, although it is not related to any obvious space-time symmetry. Thus, spherical timelike orbits, which assume eigenlike properties around the Kerr black hole, are possible and when coupled with charged Bosons may be exploited to manipulate the relative event horizons of the "target" singularity. The location and the temperature of the modified event horizon depend on the time, charge and angle of incidence of the cooper pairs. The Fermionic spectrum of Dirac particles displays a spin-rotation coupling effect due to the interaction between the particles with spin-1=2 and the black holes with rotation. The effects arise from the interaction between the spin of Dirac particles and the rotation of the evaporating black holes. The feature of this spin-rotation coupling effect is its dependence on different helicity states of coupled particles with spin-½ and its irrelevance to the mass of particles.

[0369] In order to design a mechanism for time displacement exploiting the Carter asymettry cited above we utilize two positively charged top spin rotating kerr type black holes aligned on demand to create a simulated rotational effect around a central axis provided by the "reference" singularity. In the case of the Kerr blackhole (singularity), this is accomplished by an inverse Blandford-Znajek (BZ) process utilizing the magnetic flux of open field lines connecting the horizon and an induced remote load. (Ding-Xiong Wang, Kan Xiao & Wei-Hua Lei, 2001) permitting the microscopic blackhole (singularity) to be rotated along its horizontal axis in at relativistic centrifugational speeds. A differential current is then applied in such a way as to pass through the entire photosphere in the desired direction. As a result the gravity field can be manipulated by three factors that affect it in distinct ways. Adding electric charge to the singularities increases the diameter of the inner event horizons. Adding mass to the singularities increases the area of gravitational influence around the singularities. Rotating and positioning the polar axis of the singularities affects and alters the resulting gravity sinusoid

[0370] In order to create a sinusoid capable of inducing a topology change from one spacelike boundary to the other in accordance with Geroch's theorem The electric charge in the upper half of the photosphere would be maximised. The electrons will have a vector in the left to right direction as the singularity spins clockwise. If a maximised current is applied to the singularity in the same direction this will result in a increase in the velocity of the electrons relative to the centre of gravity of the singularity, due to the flow of current. In turn, according special relativity and to the space-time lattice model, this wilt result in an increase in the relativistic mass if the electrons and in turn by general relativity an increase in the release of gravitons.

[0371] Conversely in the lower half of the singularity the electrons will have a vector of motion in the right to left direction due to the spin of the singularity. This will be relativistically slowed by the differential current applied in the same direction as the current above, and hence in the opposite direction to the direction of rotation. The charge can be separately applied and adjusted to ensure that the electrons are relativistically stationary relative to the centre of gravity. In turn this will minimize the relativistic mass and result in a decrease in the release of gravitons for the lower half of the singularity.

[0372] The overall result will be a greater release of gravitons in one direction and a lesser release of gravitons in the converse direction. The effect will be enhanced by the use of a multi-phasic current simultaneously applied. This will result in the release of multi-phasic gravitons which will disperse space time in the singularity with increase in density in the converse this effect can also be produced and supplemented with the use radio frequency pulses, The radio frequency pulses must be designed to produce a change in the spin of the particle to enhance the release of gravitons in the desired direction

[0373] With the use of large currents the drift velocity of the electrons across the photosphere could be greatly increased. Within this region the electrical resistance is virtually eliminated. Thereby allowing large currents to be induced with minimum total power output.

[0374] The result is the production of cooper paired electrons of high speed and hence high relativistic mass in the desired half of the singularity, whilst producing low speed and thus low mass paired electrons at the converse of the singularity, in accordance with special relativity. The imbalance in the rotating singularity will be continuously present creating a dynamic warping of space-time. In effect, the differential current flow, will produce differential graviton production and in turn, by general relativity, the warping of space-time

[0375] As the cooper pairs cross the photosphere, accretion of the Bose particles results. Near-hole accretion across the target singularity is then motivated by magneto-rotationally induced, ultra-relativistic disk dynamics in the region of the flow bounded from below by the marginally bound geodesic radius rmb. As the particles impelled have high spin values, a largely coherent magnetic field in this region has the dynamical implication of compact mass segregation at the displacement nodes of the non-axisymmetric, MRI modes. This results in prolific gravitational wave emission coincident with the gamma-ray stage. The gravitational wave emissions are then manipulated to influence the reference singularity to produce a variable gravitational sinusoid which is then used to mathematically approximate the gravametric distortion, inducing a topology change from one spacelike boundary to the other in accordance with Geroch's theorem.

BIBLIOGRAPHY

[0376] Mesoscopic behaviour of the neutral Fermi gas ^{3}He confined in quantum wires. S. L. Phillipson, A. M. Genault, S. N Fisher, G. R. Pickett, P. J. Y Thibault. Nature, 395: 578-580.

[0377] Direct Observation of d-orbital Holes and Cu—Cu Bonding in Cu_2. J. M. Zuo et al. Nature 401: 49-52.

[0378] The Foundation of the General Theory of Relativity, A Einstein. Translated from "Die Grundlage der Allgemeinen Relativittstheorie". Annalen der Physik, 49, 1916. Published in, Einstein, The Principle of Relativity, Dover publications, 1952.

[0379] Sidelights on Relativity. Ether and the Theory of Relativity Albert Einstein. Dover Publications 1983.

[0380] Inflation is dead long live inflation. George Musser. Scientific American, July 1998, p 9.

[0381] The flip side of the Universe. George Musser. Scientific American, September 1998, p 13.

[0382] The Fifth Element, Marcus Chown. New Scientist, Apr. 3, 1999, pp 29-32

[0383] The Quantum Universe. Tony Hey and Patrick Walters. Cambridge University Press 1987. (Solving the Shrodinger equation pp. 165-167).

[0384] Complex Numbers, Mathematics for Engineers. W. Bolton; Longman Scientific & Technical; Chap. Introducing Complex Numbers, p 1-11.

[0385] Unconditional Quantum Teleportation. A. Furusawa, I. Sorensen, S. L. Braunstein, C. A. Fuchs, H. J Kimble, E. S. Polzik. Science, Oct. 23, 1998. Vol. 282: 706-709.

[0386] Complete quantum teleportation using nuclear magnetic resonance. M. A. Neilsen, E. Knill, R. Laflamme. Nature, Nov. 5, 1998. Vol. 396: 52-55.

[0387] Experimental quantum teleportation. D. Bouwmeester et al. Nature, 390: 575-579 (1997).

[0388] Experimental realization of teleporting an unknown pure quantum state via dual classical and Einstein-Podolski-Rosen channels. D. Boschi, S. Branca, F. De Martini, L. Hardy, S. Popescu. Phys. Rev. Lett. 80: 1121-1125 (1998).

[0389] W. Tittel, J. Brendel, H. Zhuniden, N. Gisin, Phys. Rev. Lett. 81: 3563-3566. (1998) into the Vortex. Charles Seife. New Scientist, Oct. 24, 1998. p 7.

[0390] Direct observation of a fractional charge. R de Picciotto, M Reznikov, M. Heibium, V Umansky, G. Bunin, D. Mahalu. Nature, 389: 162-164.

[0391] Tables of Physical and Chemical Constants. Kay & Laby. Longman Scientific & Technical.

[0392] Physics in Focus. Michael Brimicombe. Section, Wave Mechanics; p 521. Nelson Special Relativity. A. P. French. Nelson. Chapter 8, Special Relativity and Electricity, pp 256.

[0393] Universe In Balance. Jeff Peterson. New Scientist, 168: p 27

[0394] The Accelerating Universe. Mario Livio. John Wiley and Sons, Inc. (2000)

[0395] Escape from Earth, Charles Seife, New Scientist, Feb. 6, 1999. p 6.

[0396] The Discovery of the Top Quark. Tony Liss and Paul Tipton. Scientific American; September 1997, pp. 26-41.

[0397] The Mystery of the Nucleon Spin. Klaus Rith and Andreas Schaifer. Scientific American: July 1999, pp 42-47.

[0398] And you're glue. Frank Wilczek. Nature; 400, pp 21-23.

[0399] The warp drive: hyper-fast travel within general relativity Miguel Alcubierre —Classical and Quantum Gravity, vol. 11, L73-L77, (1994)

[0400] Photon propagation in a stationary warp drive space-time: Claes R. Cramer (1995)

[0401] Some thoughts on the Implications of Faster-Than-Light Interstellar Space Travel: I. A. Crawford, Quarterly Journal of the Royal Astronomical Society, vol. 36, 205-218, (1995)

[0402] Physical and Cosmological Implications of a Possible Class of Particles Able to Travel Faster than Light: Luis Gonzalez-Mestres: Contribution to the 28th International Conference on High Energy Physics, Warsaw (Poland), (1996)

[0403] Warp drive and causality: Allen E. Everett, Physical Review D, vol. 53, 7365-7368, (1996)

[0404] A Superluminal Subway: The Krasnikov Tube, Allen E. Everett & Thomas A. Roman, Physical Review D, vol. 56, 2100-2108, (1997)

[0405] Quantum effects in the Alcubierre warp drive spacetime, William A. Hiscock, Classical and Quantum Gravity, vol. 14, L183-L188 (1997)

[0406] The unphysical nature of "Warp Drive", Michael J. Pfenning & L. H. Ford; Classical and Quantum Gravity, vol. 14, 1743-1751, (1997)

[0407] On the Possibility of a Propulsion Drive Creation Through a Local Manipulation of Spacetime Geometry; Vesselin Petkov; Presented at the 34th

[0408] AIAA/ASME/SAE/ASEE Joint Propulsion Conference, (1998)

[0409] 'Operational' energy conditions, Adam D. Helfer; Classical and Quantum Gravity, vol. 15, 1169-1183, (1998)

[0410] No warp drive; D. H. Coule; Classical and Quantum Gravity, vol. 15, 2523-2527, (1998)

[0411] Quantum Inequality Restrictions on Negative Energy Densities in Curved Spacetimes, Michael John Pfenning; Doctoral Dissertation, (1998)

[0412] Hyperfast Interstellar Travel in General Relativity; S. V. Krasnikov; Physical Review D, vol. 57, 4760, (1998)

[0413] Superluminal travel requires negative energies; Ken D. Olum; Physical Review Letters, vol. 81, 3567-3570, (1998)

[0414] Hyper-fast travel without negative energy, Eric Baird; (1999)

[0415] Warp drives, wavefronts and superluminality, Eric Baird; (1999)

[0416] A traversable wormhole, S. Krasnikov; (1999)

[0417] Speed Limits in General Relativity; Robert J. Low; Classical and Quantum Gravity, vol. 16, 543-549, (1999)

[0418] Null geodesics in the Alcubierre warp drive spacetime: the view from the bridge; Chad Clark, William A. Hiscock & Shane L. Larson; Classical and Quantum Gravity, vol. 16, 3965-3972, (1999)

[0419] A 'warp drive' with more reasonable total energy; Chris Van Den Broeck; Classical and Quantum Gravity, vol. 16, 3973-3979, (1999)

[0420] On the warp drive space-time, Pedro F. Gonzalez-Diaz; Physical Review D, vol. 62, 44005-44012, (2000)

[0421] On the (im)possibility of warp bubbles; Chris Van Den Broeck; Summary of talk delivered at STAIF-2000, (2000)

[0422] Reduced Total Energy Requirements for a Modified Alcubierre Warp Drive Spacetime; F. Loup, D. Waite & E. Halerewicz Jr. (2001)

[0423] Warp Drive With Zero Expansion, Jose Natario; Classical and Quantum Gravity, vol. 19, 1157-1166, (2002)

[0424] A Causally Connected Superluminal Warp Drive Spacetime; F. Loup, R. Held, D. Waite, E. Halerewicz, Jr., M. Stabno, M. Kuntzman & R. Sims, (2002)

[0425] Weak Energy Condition Violation and Superluminal Travel; Francisco Lobo & Paulo Crawford (2002)

[0426] On the Problems of Hazardous Matter and Radiation at Faster than Light Speeds in the Warp Drive Space-Time; C. B. Hart, R. Held, P. K. Hoiland, S. Jenks, F. Loup, D. Martins, J. Nyman, J. P. Pertierra, P. A. Santos, M. A. Shore, R. Sims, M. Stabno & T. O. M. Teage, (2002)

[0427] 2+1 gravity, chaos and time machines; Bengtsson I and Brannlund J, J. Math. Phys. 42 (2001) 3565

[0428] Time Travel in Einstein's Universe: the Physical Possibilities of Travel through Time, Gott J R; Houghton Mifflin Company, Boston, 2001

[0429] Gravitational memory of natural wormholes, Anchordoqui L A Trobo M L Vucetich H Zyserman F Mod Phys Lett A 15(6): 429-438, 2000

[0430] A traversable singularity-free wormhole. The gravitational memory phenomenon Gott time machines, BTZ black hole formation, and Choptuik scaling, Birmingham D, Sen S; Phys Rev Left 84 (2000) 1074-1077

[It is shown that the Gott time machine provides a mechanism for black hole formation]

[0431] Negative energy, wormholes and warp drive, Ford L H, Roman, T A; Sci Am: 46-53, 2000 Jan (reply: 2000 May p. 12)

[0432] Warp drive space-time; Gonzalez-Diaz P F; Phys Rev D62: 044005 (2000)

[0433] Misner-brane cosmology, Gonzalez-Diaz P F; Phys Lett B486: 158-164 (2000)

[0434] Kinks, energy conditions and closed timelike curves; Gonzalez-Diaz P F; Int J Mod Phys D 9(5): 531-541, 2000. (gr-qc/0007065)

[0435] Will we travel back (or forward) in time? Gott J R; Time, Apr. 10, 2000 pp 68-70

[0436] Charged universes of the Godel type with closed timelike curves; Klepac P and Horsky J, Class Quant Grav 17(13): 2547-2555, 2000

[0437] The Ori-Soen time machine, Olum K D; Phys Rev D61 (2000) 124022

[0438] How much energy do closed timelike curves in 2+1 spacetimes need?, Tiglio M H, Phys Rev D61 (2000) 08 1503

[0439] Energy conditions and their cosmological consequences, Visser M and Barcelo C gr-qc/0001099

[0440] Cylindrically symmetric spinning Brans-Dicke spacetimes with closed timelike curves Anchordoqui L A, Perez Bergliaffa S E, Trobo M L, Birman G S; Mod Phys Lett A14 (1999): 1105-1112

[0441] From spinning to non-spinning cosmic string spacetime; De Lorenci V A De Paola R DM Svaiter N F, Class Quant Grav 16(10): 3047-3055, 1999

[0442] Bounds on negative energy densities in static space-times, Fewster C J, Teo E; Phys Rev D 5910(10): 4016, 1999

[0443] Decohering a charged scalar field in a time-machine wormhole background, Flagga M SN; Int J Theor Phys 38(8): 2121-2161, 1999

[0444] Rotating black holes in unified theories; Gibbons G W. Progress of Theoretical Physics Supplement. (136): 18-28, 1999

[0445] Supersymmetric rotating black holes and causality violation; Gibbons G W and Herdeiro C AR, Class Quant Grav 16 (11) 3619-3652, 1999

[0446] Perdurance of multiply connected de Sitter space; Gonzalez-Diaz P F, Phys Rev D 59, 1999, 123513

[0447] Nonorientable spacetime tunneling; Gonzalez-Diaz P F, Garay L J, Phys Rev D 59 (1999) 064026

[0448] Can the universe create itself?; Gott J R, and Li X L, Phys Rev D 58, 1998, 023501. Also: astro-ph/9712344

[0449] Supersymmetric rotating black holes and causality violation; Holst S, Matschull H-J Class Quant Grav 16, 1999, 3095

[0450] Godel-type universes in string-inspired charged gravity; Kanti P, Vayonakis C E, Phys Rev D 60, 1999, 103519

[0451] Quantum field theory and time machines; Krasnikov S., Phys Rev D 59: 4010, 1999 Jan 14 Dec. 1998

[0452] Time machines constructed from anti-de Sitter space; Li L X, Phys Rev D 59 (1999) 084016

[0453] Wormholes in string theory, Vollick D N., Class Quant Grav 16(5):1599-1604, 1999

[0454] Time machines and the breakdown of unitarity; Antonsen F and Bormann K, Int J Theor Phys 37(9): 2383-2393, 1998

[0455] An exterior for the Godel spacetime; Bonnor W B, Santos N O, MacCallum M A H, Class. Quant. Grav. 15 (1998) 357-366

[0456] All the worlds a time machine, Chown M, New Scientist 157(2124): 38-41, 1998 Mar. 7.

[short exposition of M. Hadleys idea that an elementary particle is a local ST warp that it permits closed timelike curves. Hence general relativity could reproduce (explain) the effects of QM]

[0457] Quantum time machine; Gonzalez-Diaz P F Phys Rev D 58 (12): 4011, 1998

[0458] A design for a quantum time machine, Gray A quant-ph/9804008

{misleading title. On QM measurement problem; quantum "seeing into future."}

[0459] Time machines with non-compactly generated cauchy horizons and "handy singularities"; Krasnikov S V, gr-qc/9711040 (To appear in the proceedings of the 8th Marcel Grossman Conference)

[0460] A singularity-free WEC-respecting time machine, Krasnikov S V, Class Quant Grav 15 (1998) 997-1003

[0461] Self-consistent vacuum for Misner space and the chronology protection conjecture, Li L X and Gott J R, Phys Rev Lett 80, 2980, 1998

{Misner space stable to quantum flutuations; against CPC}

[0462] Decoherence caused by topology in a time-machine spacetime; Mensky M B and Novikov I D, Int. J. Mod. Phys. D5 (1996) 1-27

[0463] Godel metric as a squashed anti-de Sitter geometry, Rooman M, Spindel Ph, Class Quant Grav 15 (1998) 3241-3249

[0464] Testing causality violation on spacetimes with closed timelike curves; Rosenberg S, Phys Rev D 57(6):3365-3377, 1998

{politzer TM used to investigate the scattering experiment; interesting results on agreement with the no CTC case if there is enough TM's}

[0465] A new non-Hausdorff spacetime model for resolution of the time travel paradoxes; Sharlow M F Annals of Physics 263(2): 179-197, 1998

[0466] Particle creation near the chronology horizon; Sushkov S V, Phys Rev D 58, 1998, 044006

[0467] Divergences in the effective action of acausal spacetimes, Cassidy M J, Class Quant Grav 14 p 523, 1997 {shows that a self-consistent quantum vacuum for Misner space exist, allowing time travel}

[0468] The 1-loop instability of Misner space; Cassidy M J, Class Quant Grav 15 (8),

[0469] Superluminal subway—the Krasnikov tube; Everett A E and Roman T A, Phys Rev D 56 (4): 2100-2108, 1997

[0470] Time machines and the principle of self-consistency as a consequence of the principle of stationary action (ii)—the Cauchy problem for a self-interacting relativistic particle, Carlini A and Novikov I D, Int J Mod Phys D 5(5): 445-479, 1996 Oct.

[0471] Warp drive and causality, Everett A E, Phys Rev D 53 (12) pp 7365-7368, 1996 Ringholes and closed timelike curves, Gonzalez-Diaz P F Phys Rev D 54(10): 6122-6131, 1996

[0472] Time machine as four-dimensional wormhole; Guts A K gr-qc/9612064

[0473] Gott time machines in the Anti-de Sitter space; Holst S, Gen Rel Grav 28 (1996) 387-403

[0474] The quantum stability of the time machine, Krasnikov S V, Phys Rev D54 (1996) 7322-7327

[0475] Must time machine be unstable against vacuum fluctuations?, Li L X, Class Quant Grav 13 (1996) 2563-2568

[0476] Three-dimensional billiards with time machine, Mensky M B and Novikov I D, Int J Mod Phys D 5(2): 179-192, 1996

[0477] Decoherence caused by topology in a time-machine spacetime, Mensky M B and Novikov I D, Int J Mod Phys D 5(1): 1-27, 1996.

[0478] Improved time-machine model; Soen Y and Ori A, Phys Rev D 54(8): 4858-4861,

[0479] Unitarity restoration in the presence of closed timelike curves; Anderson A, Phys Rev D51 (1995) 5707-5715

[0480] Problems in time-machine construction due to wormhole evolution; Antonsen F and Bormann K, Int J Theor Phys 34 1995, p 2061

[0481] Time machines: the principle of self-consistency as a consequence of the principle of minimal action; Carlini A, Frolov V P, Mensky M B, Novikov I D, and Soleng H H, Int J Mod Phys D4 (1995) 557-580; Erratum-ibid. D5 (1996) 99

[0482] Nonlinearity in quantum theory and closed timelike curves; Cassidy M J, Phys Rev D52 (1995) 5676-5680

[0483] Unitarity of Quantum Theory and Closed Time-Like Curves; Fewster C J, Wells C G, Phys Rev D52 (1995) 5773-5782

[0484] Time machines without closed causal geodesics; Low R J, Class Quant Grav 12(5): L 37-L 38, 1995 May.

[0485] A remark on kinks and time machines; Yurtsever U, Gen Rel Grav 27(6): 691-693, 1995

[0486] The warp drive: hyper-fast travel within general relativity; Alcubierre M, Class Quantum Grav 11, L73 (1994)

[0487] Energy-momentum restrictions on the creation of Gott time machines; Carroll S M, Farhi E, Guth A H and Olum K D, Phys Rev D 50 pp 6190-6206, 1994

[0488] Kinks and time machines; Chamblin A, Gibbons G W and Steif A R, Phys Rev D 50(4) pp R2353-R2355, 1994

[0489] The breakdown of quantum mechanics in the presence of time machine, Goldwirth D S, Perry M J and Piran T, Gen Rel Grav 25 pp 7-13 1994

[0490] Quantum propagator for a nonrelativistic particle in the vicinity of a time machine; Goldwirth D S, Perry M J, Piran T and Thorne K S, Phys Rev D 49(8): 3951-3957, 1994

[0491] Time machine, self-consistency and the foundations of quantum mechanics; Gonella F, Found Phys Lett 7(2): 161-166, 1994

[0492] Time walk through the quantum cosmic string; Gonzalez-Diaz P F, gr-qc/9412034

[0493] Unitarity and causality in generalized quantum mechanics for nonchronal spacetimes; Hartle J B, Phys Rev D 49 (12) pp 6543-6555, 1994

[0494] (2+1)-dimensional spacetimes containing closed timelike curves; Headrick M P, Gott J R; Phys Rev D 50, 1994, 7244-7259

[0495] Time travel, Jackiw R.; Ukrainskii Fizicheskii Zhurnal. 39(1): 6-14, 1994.

[0496] On the classical stability of a time machine; Krasnikov S V, Class Quant Grav 11 (11): 2755-2759, 1994 Nov.

[0497] Isometries between Gott's two-string spacetime and Grant's generalization of Misner space, Laurence D, Phys Rev D 50 pp 4957-4965

[0498] Negative Energy Densities in Extended Sources Generating Closed Timelike Curves in General Relativity with and without Torsion; Soleng H H, Phys Rev D49 (1994) 1124-1125

[0499] Multiparticle solutions in 2+1 gravity and time machines; Steif A R, Int J Mod Phys D 3(1): 277-280, 1994

[0500] VanVleck determinants—traversable wormhole spacetimes; Visser M

[0501] Algebraic approach to quantum field theory on non-globally-hyperbolic spacetimes; Yurtsever U, Class Quant Grav 11 (1994) 999

[0502] Cosmic strings and chronology protection; Grant J DE, Phys Rev D 47, 2388 (1993)

[0503] Complex geometry, quantum tunneling, and time machines; Li L X, Xu J M and Liu L, Phys Rev D 48(10): 4735-4737, 1993

[0504] Quantum field theory in spaces with closed timelike curves; Boulware D G, Phys Rev D46 (1992) 4421-4441

[0505] Global structure of Gott's two-string spacetime; Cutler C, Phys Rev D 45 p. 487-494, 1992 {Cauchy horizons for Gott's machine (two-string space-time)}

[0506] "Cosmic flashing" in four dimensions; Ford L H and Roman T A, Phys Rev D 46, 1328-1339 (1992)

[0507] Unitarity of interacting fields in curved spacetime; Friedman J L Papastamatiou, Phys Rev D 46 4442, 1992

[0508] Feilure of unitarity for interacting fields on spacetimes with closed timelike curves; Friedman J L Papastamatiou, and Simon J Z, Phys Rev D 46 4456-4469, 1992

[0509] Particle creation for time travel through a wormhole; Kim S W, Phys Rev D 46 2428-2434, 1992

[0510] Time machine and self-consistent evolution in problems with self-interaction; Novikov I D, Phys Rev D 45 p. 1989, 1992

[0511] Structure of the singularity inside a realistic rotating black hole, Phys Rev Lett} 68, 2117-2120; Ori A (1992)

[0512] Simple quantum systems in spacetimes with closed timelike curves; Politzer H D, Phys Rev D 46 4470-4476, 1992

[0513] Quantum mechanics near closed timelike lines; Deutsch D, Phys Rev D 44 (10) p 3197-3217 1991

[0514] Billiard balls in wormhole spacetime with closed timelike curves: Classical theory; Echeverria F, Klinkhammer G and Thorne K S, Phys Rev D 44 (4) p. 1077-1099, 1991

[0515] Closed timelike curves produced by pairs of moving cosmic strings: Exact solutions; Gott J R, Phys Rev Left 66, 1126, (1991)

[0516] Inner structure of a charged black hole: An exact mass-inflation solution; Ori A, Rev Left 67: 789, 1991

[0517] On the outcome of Kerr-like collapse; Charlton N and Clarke C J S, Classical and Quantum Gravity 7 No. 5 (May 1990)

[0518] Cauchy problem in spacetimes with closed timelike curves; Friedman J, Morris M S, Novikov I D, Echeverria F, Klinkhammer G, Thorne K S and Yurtsever U, Phys Rev D 42 (6) 1915-1930, 1990 {QM fixes the TM classical billiard paradox (Polchinski's prdx. "CTC's may be not as nasty as people have assumed". The principle of self-consistency in time travel reviewed.}

[0519] Traversable wormholes from surgically modified Schwarzschild spacetimes, Visser M, Nucl Phys B 328 pp 203-212

[0520] Traversable wormholes: some simple examples; Visser M; Phys Rev D 39: 3182-3184 1989

[0521] Minimal acceleration requirements for time travel in Godel spacetime; Malament D, Journal of Mathematical Physics 26, 1985, p 774-777

[0522] Timelike nongeodesic trajectories which violate causality: A rigorous derivation; de Felice F, Nuovo Cimento 65 B pp 224-232, 1981

[0523] Rotating cylinders and the possibility of global causality violation; Tipler F J, Phys Rev D 9 pp 2203-2206, 1974

[0524] Global structure of the Kerr family of gravitational fields, Carter B, Phys Rev 174, p 1559, 1968

[0525] Complete analytic extension of the symmetry axis of Kerr's solution of Einstein's equations, Carter B, Phys Rev 141, p 1242, 1966

[0526] Acta Physica Polonica, Staruszkiewicz A 24 1963, p 734

[0527] An example of a new type of cosmological solutions of Einstein's field equations of gravitation, Goedel K, Rev Mod Phys 21 p. 447, 1949

[0528] Gravitational field of a distribution of particles rotating about an axis of symmetry; Van Stockum W J, Proc R Soc Edin 57 pp 135-154, 1937

[0529] Appendix A: The Synthetic creation of micro singularities. Throughout this patent application the creation of micro singularities has been maintained. While at first glance this may seem to be a deficiency in the patent application it is in fact an engineering problem that is in the process of being solved. In the International Journal of Theoretical Physics 41 (11): 2073-2090, November 2002 L. J. Garay published "Black Holes in Bose-Einstein Condensates". In this article Garay showed that there exist both dynamically stable and unstable dilute-gas Bose-Einstein condensates that, in the hydrodynamic limit, exhibit a behavior completely analogous to that of gravitational black holes. This discovery coupled with creation of color glass condensate (CGC) an extreme form of nuclear matter in which a nucleus travels at near-light (relativistic) speed which flattens like a pancake in its direction of motion and spawns a large number of gluons hold the key to high energy singularity formation.

I claim:

1. A method for the generation of a pseudo 2+1 dimensional anti-de Sitter space comprising the steps of:

creating two Kerr type positively charged rotating dilation singularities, including the steps of

maintaining one of the singularities as a axis of rotation reference singularity,

maintaining the other of the singularities as a target singularity, and

subjecting the target singularity to a differential electron flow so as to simultaneously pass the differential electron flow above a photosphere of said target singularity in a direction of rotation thereof and contrary to the direction of rotation thereof, in order to release a directed flow of gravitons in a sinusoidal oscillation simulating a rotational effect of the target singularity around the axis of rotation provided by the reference singularity.

2. A method of generating a force around a body, comprising the steps of:

employing sinusoidal oscillations of electrical bombardment on the surface of one Kerr type reference singularity in close proximity to a second Kerr type target singularity to take advantage of the Lense-Thirring effect, wherein the electrical currents employed in the bombardment are passed simultaneously across the photosphere of said reference singularity in its direction of rotation and contrary to its direction of rotation to release a directed flow of gravitons in a sinusoidal oscillation simulating a rotational effect of the target singularity around the axis of rotation provided by the reference singularity;

creating timelike curves in a compact time-oriented manifold of Godel-type geodesically complete spacetime envelope under the Van Den Broeck modification of the Alcubierre geometry, resulting in the creation of timelike curves in a compact time-oriented manifold permitting topology change from one spacelike boundary to the other in accordance with Geroch's theorem.

* * * * *

US 20070285325A1

(19) **United States**
(12) **Patent Application Publication**
St. Clair
(10) **Pub. No.: US 2007/0285325 A1**
(43) **Pub. Date: Dec. 13, 2007**

(54) **CHI ENERGY AMPLIFIER**

(76) Inventor: **John Quincy St. Clair**, San Juan, PR (US)

Correspondence Address:
JOHN ST. CLAIR
52 KINGS COURT, 4A
SAN JUAN, PR 00911

(21) Appl. No.: **11/448,456**

(22) Filed: **Jun. 7, 2006**

Publication Classification

(51) **Int. Cl.**
H01Q 1/00 (2006.01)
H01Q 13/10 (2006.01)

(52) **U.S. Cl.** **343/720**; 343/767

(57) **ABSTRACT**

A Chi energy amplifier that utilizes a co-gravitational K field to generate a flow of hyperspace energy into or out of a ceramic dome containing a slot antenna.



Figure 1



Figure 2


6
8
7
9
11
10
12

Figure 3



Figure 4



Figure 5


19
20
21
24
22
23

Figure 6


27
30
25
34
28
35
26
29
37
31
32
38
33
39
36

Figure 7



Figure 8



Figure 9


$\frac{3}{4}\lambda$
$\frac{\lambda}{2}$
48
47
$\frac{\lambda}{2}$
49
46

Figure 10


1
0.75
0.5
d
0
0
-0.5
-0.75
-1
2·10^4
4·10^4
6·10^4
8·10^4
1·10^5
1.2·10^5
2×10^4
f
1.2×10^5

Figure 11


10
.6.
5
d
0
- 5
-5
2.78MHz
1·10^6
1.5·10^6
2·10^6
2.5·10^6
3·10^6
3.5·10^6
4·10^6
4.5·10^6
5·10^6
.1×10^6.
f
.5×10^6.

Figure 12



CHI ENERGY AMPLIFIER

BRIEF SUMMARY OF THE INVENTION

[0001] This invention is an energy amplifier that controls the direction of the second co-gravitational K field by means of a slot antenna located in a resonating sphere. The hyper-space mass flow rate entering into this dimension is determined by the frequency of the antenna. This energy flow is used to increase the energy of the human energy field known as Chi.

BACKGROUND OF THE INVENTION

[0002] Referring to FIG. **1**, a pendulum suspended by a string (**3**) is held by the string with the right hand (**1**) over the upright palm of the left hand (**2**). The pendulum swings in circles shown by the clockwise direction of the arrow (**4**). The pendulum swings at a constant frequency at about 1 to 2 Hz. What this means is that there is a second gravitational K field (**5**) that can cause a mass to rotate in circles.

[0003] Everyone is familiar with the linear gravitational g field which is defined as Newton's gravitational constant G times the mass of the earth divided by the square of the radius of the earth. This is the field that causes objects to accelerate radially toward the earth's surface. Newton's gravitational constant G is equal to the speed of light c squared divided by the linear mass Ω of the universe. The speed of light is

$$c = 299792458\ \frac{\text{meters}}{\text{second}}$$

$$\Omega = 1.346812891 \cdot 10^{27}\ \frac{\text{kilograms}}{\text{meter}}$$

$$G = \frac{c^2}{\Omega} = 6.673200002 \cdot 10^{-11}\ \frac{meter^3}{second^2\ \text{kilogram}}$$

The mass and radius of the earth are

[0004]

$$ME = 5.977 \cdot 10^{24}\ \text{kilograms}$$

$$RE = 6371.03\ 10^3\ \text{meters}$$

$$g = G\frac{ME}{RE^2} = 9.82\ \frac{\text{meters}}{second^2}$$

[0005] From electromagnetism, the electric E field is linear and the B magnetic field is circular or forms closed loops. The electric field starts and ends on electric charges. Since there are two electromagnetic fields, it makes sense that there are also two gravitational fields. A flow of electric current through a straight wire causes a circular magnetic B field to form around the wire. In a similar manner, a flow of mass through a channel causes a circular gravitational K field to form around the channel.

[0006] Referring to FIG. **2**, the right hand rule (**6**) shows that if the flow is along the direction of the thumb of the right hand, then the field curls around in the direction of the fingers. If an electric current is flowing through the wire (**7**) in the direction of arrow (**8**), then a counter-clockwise magnetic field circles the wire shown by arrow (**9**). In the bottom view, a mass flowing through a channel (**10**) in direction (**11**) generates a counter-clockwise gravitational K field shown by arrow (**12**). This field is the reason that the pendulum swings in circles. The gravitational K field only exists if there is a mass flow. In the wire there is also an electric field driving the electrons, so it must be that there is a g gravitational field driving the mass along the channel.

[0007] The correspondence between electromagnetic and gravitational constants must be the following:

Electric	Gravitational
Charge q	Mass m
Electric Field E	Gravitational Field g
Magnetic Field B	Co-gravitational Field K
Linear Electric Charge λ	Linear Mass Ω
Permittivity of Space ϵ_0	$-1/4\pi G$
Permeability of Space μ_0	$-4\pi G/c^2$
Convection Current Density J	Mass Current Density J

[0008] Maxwell's equation for the curl or circulation of B involves the current density J and an electric field E changing with time t

$$\nabla \times B = \mu_0 J + \frac{1}{c^2}\frac{\partial E}{\partial t}$$

The corresponding gravitational equation is therefore

[0009]

$$\nabla \times K = -\frac{4\pi G}{c^2} J + \frac{1}{c^2}\frac{\partial g}{\partial t}$$

[0010] If the g field is constant with time, then the circulation of the K field only depends on the mass density flow through the channel. Notice the minus sign in front of the first term which says that if energy is entering our dimension through a channel, then the K field is in the counterclockwise direction as indicated by the pendulum. As seen in FIG. **1**, the energy is leaving through the left hand because the rotation is clockwise. On the right hand, the pendulum rotates in the counterclockwise direction indicating that energy is coming from the hand. Thus there is a flow of energy between the hands known as the Chi energy. The purpose of this invention is to amplify this energy.

[0011] The g gravitational field is due to a negative space-time curvature created by the mass of the earth. In many physics books this is depicted as a bowl. So the idea was to acquire a ceramic kiln which could produce ceramic bowls using earthenware clay and a bowl mold. The curvature created by the bowl, if any, could be detected by the pendulum.

[0012] Referring to FIG. **3**, a pendulum (**13**) held in the right hand with the left hand near the side of the concave mold (**14**) starts to swing toward the right, away from the plaster mold as shown by arrow (**15**).

[0013] Referring to FIG. **4**, a pendulum (**16**) held in the right hand over a positive curvature dome (**17**) swings toward the top of the dome as shown by arrow (**18**).

Supposedly the K gravitational field rotates in circles, but these experiments showed that the pendulum movement was radial.

[0014] Referring to FIG. **5**, the pendulum (**19**) swings radially (**20**) toward the top of the dome (**23**) because the forces (**24**) around the dome counteract each other as shown by arrows (**21**, **22**). Thus there is no sideways pressure on the pendulum.

[0015] The next question was what is the value of the co-gravitational K constant? In electromagnetism the electric field is the speed of light times the magnetic field. So the g gravitational field should be the speed of light times the co-gravitational K field.

$$\begin{aligned} K &= \frac{g}{c} \\ &= \frac{1}{c}G\frac{MU}{RU^2} \\ &= \frac{1}{c}\frac{c^2}{\Omega}\frac{MU}{\frac{MU}{\Omega}RU} \\ &= \frac{c}{RU} \end{aligned}$$

$$\ln(K) = -40.34861143$$

[0016] where the radius RU of the universe is 10^{26} meters and c is the speed of light. The speed of light divided by the radius is angular frequency measured in Hz. Recall that the pendulum over the hand has a frequency f of 1 Hz which makes the angular frequency o equal to 2π radians per second since ω=2πf So the question is whether or not this value of K means anything in terms of hyperspace physics?

[0017] The universe has a geometrical sub-manifold based on the tetrahedron. All the physics constants of the universe are determined by this tetrahedral geometry. As shown in diagram tet0565 stored in the Library of Congress, the electron and proton are one and the same particle. There is a continuous clockwise path from the electron wavelength, through electric charge to electron mass and returning out-of-dimension back along a counterclockwise path as the proton. Because the paths are in opposite directions, the proton has a positive charge and the electron has the opposite negative charge. Because this path crosses into our dimension from hyperspace, we see two different particles. Thus Nature only has one particle. The tetrahedron diagram also shows that our dimension is offset from the origin of the diagram by the Cabibbo angle which is found in particle physics. Our dimension is determined by the Planck mass and the Planck wavelength which are the bottom limits of our dimension, known as the Planck box. If the proton mass is centered on the Planck mass, a tangent line to the circle can only be made by using the down quark and up quark which comprise the proton (duu). And the tangent line is drawn at the Cabibbo angle. So the diagram verifies some important experimental physics data.

[0018] Referring to FIG. **6**, the tetrahedron diagram is drawn with a vertical axis (**35**) corresponding to the natural logarithm of mass. The horizontal axis (**36**) is the natural logarithm of wavelength. The inverted tetrahedrons (**25**, **26**) cross at the centerline (**28**) which is known through remote viewing as “the merging of two worlds.” The centerline is the separation point between space and hyperspace. The circumscribing sphere (**27**) has a horizontal diameter (**29**) and a vertical diameter (**30**). The electron wavelength (**34**) reflects off the sphere and returns as the electron mass (**33**).

[0019] Because the K co-gravitational field is related to circular or spinning motion, as well as vorticity per area, it might be imagined that it has something to do with the spinning electron. The energy E of the electron is equal to the mass m_e of the electron times the speed of light c squared.

$$\begin{aligned} m_e &= 9.1093897\cdot 10^{-31}\ \text{kilogram} \\ c &= 299792458\cdot\frac{\text{meter}}{\text{second}} \\ E &= m_e c^2 \\ \ln(E) &= -30.13363019 \end{aligned}$$

[0020] The tips of the inverted tetrahedrons pass through the base constant, vertical line (**37**), which is equal to Planck’s constant h divided by the speed of light.

$$h = 2.210260685\cdot 10^{-42}\ \text{kilogram meter}$$

$$\text{base} = \ln\left(\frac{h}{c}\right) = -95.91546344$$

[0021] On the tetrahedron diagram, the co-gravitational circle K (**31**) is centered on the base (**37**) at the electron energy (**32**) shown by the small π circle at the intersection (**38**). As can be seen, the K circle determines the electron mass (**33**) at the horizontal axis (**36**) as shown by intersection (**39**). Because the electron is the proton, it also sets the constants of the proton such as wavelength, charge and mass. Thus the K co-gravitational field determines our elementary particles. Because these particle paths go in and out of dimension, it means that hyperspace exists. And because the K field is circular, depending on the direction of the energy flow, another purpose of this invention is to control the direction of the field.

SUMMARY OF THE INVENTION

[0022] Referring to FIG. **7**, the Chi energy amplifier consists of two ceramic domes (**40**, **41**) resting one on the other such as to form a hollow internal clam-like structure. The domes are mounted on a cylindrical ceramic base (**42**) containing a reinforced passageway for the coaxial cable and BNC connector (**43**). The BNC connector plugs into the frequency generator (not shown) which has a frequency range of 0.4 Hz to 5 MHz.

[0023] Referring to FIG. **8** with the upper dome removed, the coaxial cable (**44**) extends vertically through the base into the lower dome. The cable is soldered to a slot antenna (**45**). The center conductor of the cable is soldered to the left side of the slot and the ground shielding is soldered to the right side of the slot. Thus there is a voltage difference on the two sides which produces an oscillating electric field across the slot which radiates electromagnetic energy into the hollow dome.

[0024] A close-up of the slot antenna is shown in FIG. **9**. The antenna is a 0.050" thick copper sheet (**46**) with a width of ¾ wavelength by a height of ½ wavelength. A slot (**47**) of ½ wavelength is electric-discharge machined into the copper sheet (**47**). The center conductor (**48**) from the coaxial cable is soldered to the top of the slot. The ground wire (**49**) is soldered to the bottom of the slot. This configuration produces a voltage difference between the inner top and bottom surfaces of the slot. The frequency generator produces an oscillating voltage across the slot which generates an electric field that radiates from the antenna into the ceramic cavity.

[0025] The wavelength of the antenna and the dimensions of the ceramic cavity have to be tuned to the geometry of our dimension. Newton's gravitational constant G is equal to

$$\ln(G) = -23.4303342$$

$$f = e^{23.4303432} * \mathrm{Hz} = 15\ Ghz$$

$$\lambda = \frac{c}{f} = .020\ \mathrm{meter} = .787\ \mathrm{inch}$$

$$\mathrm{slotwidth} = \frac{\lambda}{2} = .393\ \mathrm{inch}$$

$$\mathrm{antennawidth} = \frac{3}{4}\lambda = .590\ \mathrm{inch}$$

The frequency of the antenna is the inverse of the gravitational constant. The reason for this is that when a circle of radius natural logarithm G is centered on the proton on the tetrahedron diagram, the circle intersects the corner of the Planck box which bounds our dimension between space and hyperspace. It is the low-density hyperspace energy that the amplifier will bring into this dimension.

[0026] The size of the ceramic cavity based on the angular frequency ω=2πf is

$$\frac{\frac{\omega^2}{c^2} + \frac{1}{ab}}{\frac{\omega^2}{c^2} + ab\left(\frac{\omega^2}{c^2} - \frac{1}{a^2}\right)\left(\frac{\omega^2}{c^2} - \frac{1}{b^2}\right)} = \frac{\tan\left(\frac{\omega}{c}(b-a)\right)}{\omega}\frac{c}{b-a}$$

where b is inside radius of the cavity, a is the radius of an object at the center of the cavity and c is the speed of light. Using the object radius as a=0.020 meter to account for the antenna, the inside radius of the cavity is b=4.25 inches which is the size of the 8.5 inch diameter ceramic dome using ¼ inch thick clay. The frequency is then equal to

$$f = \ln\left(\frac{\omega}{2\pi}\right) = 23.45$$

which is close to the inverse of the gravitational constant G of −23.43. Thus the amplifier is tuned to the gravitational constant of the universe both in size of the cavity and the frequency of the slot antenna. Using a SMD surface mount capacitor and inductor in the picofarad and nanohenry range, it is possible to get up to this high frequency, but it was found that it was not necessary because the amplifier works at lower frequencies that are pulsed.

[0027] Referring to FIG. **10**, the swinging movement of the pendulum measured in inches at the side of the dome is plotted against a range of frequencies from 20 kHz to 120 kHz. At 20 kHz, the pendulum swings ¾ inch away from the dome. Then at 40 kHz, the pendulum swings ¾ inch toward the dome. This pattern is repeated until 120 kHz. What this means is that the amplifier can control the direction of the co-gravitational field using frequency. The tetrahedron diagram shows that this phenomenon is related to the two axes of the circumscribing sphere of the tetrahedron.

[0028] Referring to FIG. **11**, the swinging of the pendulum is plotted for a range of frequencies from 1 MHz to 5 MHz. At a frequency of 2.78 MHz the pendulum was swinging strongly from the vertical to the horizontal, a distance of six inches. On the tetrahedron diagram, the distance from our base constant to the centerline between inverted tetrahedrons is equal to 14.838168. This corresponds to a frequency of

$$f = e^{14.838168} * \mathrm{Hz} = 2.780574169\ \mathrm{MHz}$$

which is close to the experimental value.

[0029] Referring to FIG. **12**, the Chi energy flowing between the hands, shown by the arrows, is amplified by placing the hands across the dome. This energy from the right hand mixes with the hyperspace energy entering the dome from hyperspace. The combined energy is then absorbed in the left hand vortex. The effects of this amplified energy are simply amazing and have to be experienced to appreciate what it means.

A BRIEF DESCRIPTION OF THE DRAWINGS

[0030] FIG. **1**. Perspective view of pendulum movement over left hand vortex.

[0031] FIG. **2**. Perspective view of right hand rule of physics showing similarity between electromagnetism and gravity.

[0032] FIG. **3**. Perspective view of plaster mold cavity showing negative curvature.

[0033] FIG. **4**. Perspective view of dome showing positive curvature.

[0034] FIG. **5**. Perspective view of dome showing radial pendulum movement.

[0035] FIG. **6**. Graph of co-gravitational K field on tetrahedron diagram.

[0036] FIG. **7**. Perspective view of Chi Energy Amplifier with BNC coaxial cable.

[0037] FIG. **8**. Perspective view of slot antenna in dome.

[0038] FIG. **9**. Perspective view of slot antenna showing dimensions.

[0039] FIG. **10**. Graph of pendulum movement versus frequency of antenna, 20 KHz.

[0040] FIG. **11**. Graph of pendulum movement versus frequency from 1 MHz to 5 MHz.

[0041] FIG. **12**. Perspective view of amplifying Chi energy.

DETAILED DESCRIPTION OF THE INVENTION

[0042] The dome of the amplifier is made of red earthenware clay from Minnesota having a cone 06 kiln firing temperature of 1828° F. over a period of 7.5 hours. The clay is placed between two hardwood ¼ inch thick slats. It is then rolled flat with a rolling pin. The sheet of clay is cut in half and one half is placed in a 9-inch diameter bowl mold using a soft sponge to push it into position. The second half is then added to the first with the seam between worked flat with a metal kidney and elephant ear sponge. The top of the mold is scrapped flat to create the bowl shape. The moist clay is left to dry for one day after which it falls out of the mold due to shrinkage. After completely drying, the dome is then placed in a kiln which runs the computer-controlled cone 06 temperature firing profile. A preheat at 180° F. for one hour is required to make sure the dome is completely bone dry. It takes 7 to 8 hours to fire the dome with another 12 hours to cool down naturally.

[0043] The base is also made of ¼ inch clay. A circular shape is cut out and fitted with a ribbon of extruded clay from a clay gun to make the cylindrical wall. Using a hole cutter made of hollow tubing, a hole is made in the side of the base for the coaxial cable. The second lower dome has a hole cut in the bottom when the clay is leather hard.

[0044] A 0.050" thick copper sheet is EDM machined to cut a half wavelength slot in the copper. The inner conductor of the coaxial cable is soldered using silver epoxy to the one side of the slot. The ground shielding of the cable is silver epoxied to the other side of the slot. The other end of the coaxial cable has a BNC connector which plugs into the frequency generator.

[0045] The pendulum is made out of soft brass rod and machined on a lathe into a plumb bob shape. A hole is drilled in the stem to hold the 6" long string.

I claim:

1. A Chi energy amplifier comprising:

a. a hollow ceramic dome in the shape of a clam shell with a hole in the lower half that provides access to a coaxial cable;

b. a cylindrical ceramic base on which the dome is mounted with holes that provide access for a coaxial cable into item (a);

c. a slot antenna soldered to the coaxial cable, located midway inside item (a), such that the inner conductor of the cable is soldered to one side of the slot and the ground shielding is soldered to the other side of the slot;

d. a frequency generator connected to the other end of the coaxial cable by means of a BNC connector for the purpose of providing an oscillating voltage to item (c);

e. an electromagnetic wave generated by items (c, d) that resonates inside item (a);

f. a co-gravitational K field generated by items (a, b, c, d, e) whose direction can be controlled by the frequency of item (d); and

g. a flow of hyperspace energy into or out of the dome due to item (f).

* * * * *

455-619 AU 233 EX
FIP8106 OR 685,958

55

No. 685,958. **Patented Nov. 5, 1901.**

N. TESLA.

METHOD OF UTILIZING RADIANT ENERGY.

(Application filed Mar. 21, 1901.)

(No Model.)

Electric steping motor
energized by corpuscular
energy from sun



Fig.1

No refs.



P — pickup

Fig.2

Witnesses:
Raphaël Netter
M. Lawson Dyer

Nikola Tesla, Inventor
by Kerr, Page & Cooper Attys

THE NORRIS PETERS CO. PHOTO-LITHO., WASHINGTON, D. C.

UNITED STATES PATENT OFFICE.

NIKOLA TESLA, OF NEW YORK, N. Y.

METHOD OF UTILIZING RADIANT ENERGY.

SPECIFICATION forming part of Letters Patent No. 685,958, dated November 5, 1901.

Application filed March 21, 1901. Serial No. 52,154. (No model.)

To all whom it may concern:

Be it known that I, NIKOLA TESLA, a citizen of the United States, residing at the borough of Manhattan, in the city, county, and State of New York, have invented certain new and useful Improvements in Methods of Utilizing Radiant Energy, of which the following is a specification, reference being had to the drawings accompanying and forming a part of the same.

It is well known that certain radiations—such as those of ultra-violet light, cathodic, Roentgen rays, or the like—possess the property of charging and discharging conductors of electricity, the discharge being particularly noticeable when the conductor upon which the rays impinge is negatively electrified. These radiations are generally considered to be ether vibrations of extremely small wave lengths, and in explanation of the phenomena noted it has been assumed by some authorities that they ionize or render conducting the atmosphere through which they are propagated. My own experiments and observations, however, lead me to conclusions more in accord with the theory heretofore advanced by me that sources of such radiant energy throw off with great velocity minute particles of matter which are strongly electrified, and therefore capable of charging an electrical conductor, or even if not so may at any rate discharge an electrified conductor either by carrying off bodily its charge or otherwise.

My present application is based upon a discovery which I have made that when rays or radiations of the above kind are permitted to fall upon an insulated conducting body connected to one of the terminals of a condenser, while the other terminal of the same is made by independent means to receive or to carry away electricity, a current flows into the condenser so long as the insulated body is exposed to the rays, and under the conditions hereinafter specified an indefinite accumulation of electrical energy in the condenser takes place. This energy after a suitable time interval, during which the rays are allowed to act, may manifest itself in a powerful discharge, which may be utilized for the operation or control of mechanical or electrical devices or rendered useful in many other ways.

In applying my discovery I provide a condenser, preferably of considerable electrostatic capacity, and connect one of its terminals to an insulated metal plate or other conducting body exposed to the rays or streams of radiant matter. It is very important, particularly in view of the fact that electrical energy is generally supplied at a very slow rate to the condenser, to construct the same with the greatest care. I use by preference the best quality of mica as dielectric, taking every possible precaution in insulating the armatures, so that the instrument may withstand great electrical pressures without leaking and may leave no perceptible electrification when discharging instantaneously. In practice I have found that the best results are obtained with condensers treated in the manner described in a patent granted to me February 23, 1897, No. 577,671. Obviously the above precautions should be the more rigorously observed the slower the rate of charging and the smaller the time interval during which the energy is allowed to accumulate in the condenser. The insulated plate or conducting body should present as large a surface as practicable to the rays or streams of matter, I having ascertained that the amount of energy conveyed to it per unit of time is under otherwise identical conditions proportionate to the area exposed, or nearly so. Furthermore, the surface should be clean and preferably highly polished or amalgamated. The second terminal or armature of the condenser may be connected to one of the poles of a battery or other source of electricity or to any conducting body or object whatever of such properties or so conditioned that by its means electricity of the required sign will be supplied to the terminal. A simple way of supplying positive or negative electricity to the terminal is to connect the same either to an insulated conductor, supported at some height in the atmosphere, or to a grounded conductor, the former, as is well known, furnishing positive and the latter negative electricity. As the rays or supposed streams of matter generally convey a positive charge to the first condenser-terminal, which is connect-

RADIANT ENERGY.

EXAMINER

ed to the plate or conductor above mentioned, I usually connect the second terminal of the condenser to the ground, this being the most convenient way of obtaining negative electricity, dispensing with the necessity of providing an artificial source. In order to utilize for any useful purpose the energy accumulated in the condenser, I furthermore connect to the terminals of the same a circuit including an instrument or apparatus which it is desired to operate and another instrument or device for alternately closing and opening the circuit. This latter may be any form of circuit-controller, with fixed or movable parts or electrodes, which may be actuated either by the stored energy or by independent means.

The rays or radiations which are to be utilized for the operation of the apparatus above described in general terms may be derived from a natural source, as the sun, or may be artificially produced by such means, for example, as an arc-lamp, a Roentgen tube, and the like, and they may be employed for a great variety of useful purposes.

My discovery will be more fully understood from the following detailed description and annexed drawings, to which reference is now made, and in which—

Figure 1 is a diagram showing typical forms of the devices or elements as arranged and connected in applying the method for the operation of a mechanical contrivance or instrument solely by the energy stored; and Fig. 2 is a diagrammatical representation of a modified arrangement suitable for special purposes, with a circuit-controller actuated by independent means.

Referring to Fig. 1, C is the condenser, P the insulated plate or conducting body, which is exposed to the rays, and P′ another plate or conductor, all being joined in series, as shown. The terminals T T′ of the condenser are also connected to a circuit including a receiver R, which is to be operated, and a circuit-controlling device *d*, which in this case is composed of two very thin conducting-plates *t t′*, placed in close proximity and very mobile, either by reason of extreme flexibility or owing to the charater of their support. To improve their action, they should be inclosed in a receptacle from which the air may be exhausted. The receiver R is shown as consisting of an electromagnet M, a movable armature *a*, a retractile spring *b*, and a ratchet-wheel *w*, provided with a spring-pawl *r*, which is pivoted to armature *a*, as illustrated. The apparatus being arranged as shown, it will be found that when the radiations of the sun or of any other source capable of producing the effects before described fall upon the plate P an accumulation of electrical energy in the condenser C will result. This phenomenon, I believe, is best explained as follows: The sun as well as other sources of radiant energy throw off minute particles of matter positively electrified, which, impinging upon the plate P, communicate an electrical charge to the same. The opposite terminal of the condenser being connected to the ground, which may be considered as a vast reservoir of negative electricity, a feeble current flows continuously into the condenser, and inasmuch as these supposed particles are of an inconceivably small radius or curvature, and consequently charged to a relatively very high potential, this charging of the condenser may continue, as I have found in practice, almost indefinitely, even to the point of rupturing the dielectric. Obviously whatever circuit-controller be employed it should operate to close the circuit in which it is included when the potential in the condenser has reached the desired magnitude. Thus in Fig. ② when the electrical pressure at the terminals T T′ rises to a certain predetermined value the plates *t t′*, attracting each other, close the circuit connected to the terminals. This permits a flow of current which energizes the magnet M, causing it to draw down the armature *a* and impart a partial rotation to the ratchet-wheel *w*. As the current ceases the armature is retracted by the spring *b* without, however, moving the wheel *w*. With the stoppage of the current the plates *t t′* cease to be attracted and separate, thus restoring the circuit to its original condition.

Many useful applications of this method of utilizing the radiations emanating from the sun or other source and many ways of carrying out the same will at once suggest themselves from the above description. By way of illustration a modified arrangement is shown in Fig. 2, in which the source S of radiant energy is a special form of Roentgen tube devised by me having but one terminal *k*, generally of aluminium, in the form of half a sphere with a plain polished surface on the front side, from which the streams are thrown off. It may be excited by attaching it to one of the terminals of any generator of sufficiently-high electromotive force; but whatever apparatus be used it is important that the tube be exhausted to a high degree, as otherwise it might prove entirely ineffective. The working or discharge circuit connected to the terminals T T′ of the condenser includes in this case the primary *p* of a transformer and a circuit-controller comprising a fixed terminal or brush *t* and a movable terminal *t′* in the shape of a wheel with conducting and insulating segments which may be rotated at an arbitrary speed by any suitable means. In inductive relation to the primary wire or coil *p* is a secondary *s*, usually of a much greater number of turns, to the ends of which is connected a receiver R. The terminals of the condenser being connected as indicated, one to an insulated plate P and the other to a grounded plate P′, when the tube S is excited rays or streams of matter are emitted from the same, which convey a positive charge to the plate P and condenser-terminal T, while terminal T′ is continuously receiving negative electricity from the plate

P'. This, as before explained, results in an accumulation of electrical energy in the condenser, which goes on as long as the circuit including the primary p is interrupted. Whenever the circuit is closed, owing to the rotation of the terminal t', the stored energy is discharged through the primary p, this giving rise in the secondary s to induced currents which operate the receiver R.

It is clear from what has been stated above that if the terminal T' is connected to a plate supplying positive instead of negative electricity the rays should convey negative electricity to plate P. The source S may be any form of Roentgen or Lenard tube; but it is obvious from the theory of action that in order to be very effective the electrical impulses exciting it should be wholly or at least preponderatingly of one sign. If ordinary symmetrical alternating currents are employed, provision should be made for allowing the rays to fall upon the plate P only during those periods when they are productive of the desired result. Evidently if the radiations of the source be stopped or intercepted or their intensity varied in any manner, as by periodically interrupting or rythmically varying the current exciting the source, there will be corresponding changes in the action upon the receiver R, and thus signals may be transmitted and many other useful effects produced. Furthermore, it will be understood that any form of circuit-closer which will respond to or be set in operation when a predetermined amount of energy is stored in the condenser may be used in lieu of the device specifically described with reference to Fig. 1, and also that the special details of construction and arrangement of the several parts of the apparatus may be very greatly varied without departure from the invention.

Having described my invention, what I claim is—

1. The method of utilizing radiant energy, which consists in charging one of the armatures of a condenser by rays or radiations, and the other armature by independent means, and discharging the condenser through a suitable receiver, as set forth.

2. The method of utilizing radiant energy, which consists in simultaneously charging a condenser by means of rays or radiations and an independent source of electrical energy, and discharging the condenser through a suitable receiver, as set forth.

3. The method of utilizing radiant energy, which consists in charging one of the armatures of a condenser by rays or radiations, and the other by independent means, controlling the action or effect of said rays or radiations and discharging the condenser through a suitable receiver, as set forth.

4. The method of utilizing radiant energy, which consists in charging one of the armatures of a condenser by rays or radiations and the other by independent means, varying the intensity of the said rays or radiations and periodically discharging the condenser through a suitable receiver, as set forth.

5. The method of utilizing radiant energy, which consists in directing upon an elevated conductor, connected to one of the armatures of a condenser, rays or radiations capable of positively electrifying the same, carrying off electricity from the other armature by connecting the same with the ground, and discharging the accumulated energy through a suitable receiver, as set forth.

6. The method of utilizing radiant energy, which consists in charging one of the armatures of a condenser by rays or radiations, and the other by independent means, and effecting by the automatic discharge of the accumulated energy the operation or control of a suitable receiver, as set forth.

NIKOLA TESLA.

Witnesses:

M. LAWSON DYER,

RICHARD DONOVAN.

New Energy Technologies

Published by Faraday Laboratories Ltd. Issue #3 (6) 2002

Research on advanced propulsion systems and new energy sources

Time Control experiments

Also in this issue:

* *New experiments: magnet monopole beam cures cancer*
* *Electrogravity experiments*
* *High efficiency ceramic heater*
* *New aether experiments*
* *Instantaneous telecommunication*

Editorial

Dr. Chernobrov and NET editor Olga Leontyeva.

The head of the Moscow research group "Kosmopoisk" Dr. Vadim A. Chernobrov (our readers certainly remember his articles on experiments with time) has recently visited the editorial office of New Energy Technologies in Saint-Petersburg, Russia. His visit was caused by discussion on the Time Machine project (investigation of active properties of time), started under agreement with Faraday Labs Ltd. Our magazine will inform readers on the topic in later issues.

Publisher Faraday Lab Ltd

Editor-in-Chief Alexander V. Frolov
Editor Olga O. Leontyeva
Designer Ekaterina F. Yakovleva
Translator Antonina V. Nikolaeva

Scientific Advisory Board
Kyrill P. Butusov
Ivan M. Shakhparonov

New Energy Technologies Magazine
is published by Faraday Lab Ltd
six times a year

Correspondence Address:
POBox 37, St.Petersburg,
193024, Russia
Phone/fax: 7-812-380-6564
net@faraday.ru
www.faraday.ru

Subscription: $90 any foreign
Air mail delivery included

PRINTED IN RUSSIA

Copyright © 2002 by Faraday Lab Ltd.
All rights reserved.

NEW ENERGY TECHNOLOGIES
New Book

Dear Reader!
All articles of the previous 6 NET issues will soon be published as a new book in English (400 pages, more than 100 photos, figures and drawings, format A4).
You can order by e-mail: book2001@faraday.ru
or fax 7-812-3806564
Price with airmail delivery is 83 USD.



LUTEC 1000

News from Australia

Magnet motor-generator

www.lutec.com.au

"There are a couple of other major factors that we won't go into here, suffice it to say that our current prototype demonstrates 1500% more " out" than "in"... "

"The Lutec 1000 will be sold throughout Australia within three years. The majority of buyers are expected to be the home owners, although there is strong support for our product throughout the entire strata of society and business. Market leadership should be maintained for the next five years. The product is sold through commission only sales agents and our staff at the plant, mainly to anyone who needs or uses electricity."

John Christie (left) is the co-founder, CEO and chairman of Lutec (Aust.) Pty Ltd.

Ludwig (Lou) Brits (right, above) is the co-founder, managing director and head of development of Lutec (Aust.) Pty Ltd. He is Chairman and director of TTI Pty Ltd. TTI Pty Ltd is a state government recognised R.A.P. (remote area power) system provider.







Electrogravity

by Tim Ventura
tventura@attbi.com

In this issue a report by Tim Ventura, USA on experimenting with asymmetrical capacitors.
www.americanantigravity.com

NEW ENERGY TECHNOLOGIES #6

1. Large-Scale Shakharov condition, **David Noever and Christopher Bremner**
2. Matter as a resonance longitudinal wave process, **Alexander V. Frolov**
3. Physical Principles of The Time Machine, **Alexander V. Frolov**
4. Time Machine Project by **Alexander V. Frolov**
5. Kozyrev-Dirak radiation, **Ivan M. Shakhparonov**
6. The Electrical Vortex Non-Solenoidal Fields**, S. Alemanov**
7. Physical Mechanism of Nuclear Reactions at Low Energies, **V.Oleinik, Yu. Arepjev**
8. The Evolution of Lifter Technology, **T. Ventura**
9. Reality and consciousness in education and activity, **A.Smirnov**
10. Old new energy, **Y. Andreev, A. Smirnov**
11. On the influence of time on matter, **A. Belyaeva**
12. Life without diseases and ageing-preventive electrical bio-heater features, **A. Belyaeva**
13. Technical report, on Belyaeva's high efficient ceramic heater, **Sh. Mavlyandekov**
14. Fundamental properties of aether, **A. Mishin**
15. Effect of Magnetic Blow Wave Field on Wine Systems, **I. Shakhparanov and others**
16. Nikola Tesla and Instantaneous Electric Communication, **V. Korobeynikov**
17. The Unitied Gravitation theory, **I. Kuldoshin**
18. New Sources of Energy from the Point of View of Unitary Quantum Theory, **L.G. Sapogin, Yu.A. Ryabov, V.V. Graboshnikov**
19. Antigravitation Force and antigravitation of matter. Methods of its creation, **A. K. Gaponov**
20. The capacitor, which has energy of atomic bomb (Review of A. Gaponov's research)

consequence of many commonly accepted concepts and dogmas of the modern "scientific perspective of natural phenomena". This crisis situation in modern physics is a direct consequence of many conservative scientific viewpoints, unfortunately supported and protected by modern official academic science. The evolution of our consciousness has been influenced by many undoubtedly well known experts and has been evolving for a long time in the environment of specific scientific vacuum and requires immediate revival. Even methods used for dissemination of new knowledge should be improved, if one actually wishes to accelerate the progress of Humankind.

The perspective for practical applications of new previously unknown scientific phenomena and effects looks very attractive, and they may be achieved by cooperative efforts of the human intellect. New breakthrough technologies of the 21st Century will require serious changes of many commonly accepted concepts and dogmas in fundamental physics. This process of progressive development cannot be stopped.

REFERENCES

1. Richard P. Feynman, Robert B. Leighton, Matthew Sands. The Feynman Lectures on Physics, Addison-Wesley, 1964, Vol. 2, Ch. 1. Paragraph 6 "Electromagnetism in Science and Technology" (the very end of paragraph)
2. J. Maxwell, Selected Works on the Electromagnetic Field Theory, Gostekhizdat, Moscow (1954).
3. G. V. Nikolaev, Non-contradictory Electrodynamics. Theories, Experiments, and Paradoxes, Publishing House of the Tomsk State University, Tomsk (1997).
4. A. S. Kompaniets, in: Theoretical Physics, State Technical and Theoretical Press, Moscow (1957), pp. 126-128.
5. R. T. Sigalov, T. I. Shapovalova, Kh. Kh. Karimov, and N. I. Samsonov, New Research of Forces of the Magnetic Field, FAN Press of the Uzbekskaia SSR, Tashkent (1975).
6. Ya. I. Frenkel, Electrodynamics. Vol. 1, United Scientific and Technical Presses, Leningrad/Moscow (1934).
7. G. V. Nikolaev and B. V. Okulov, Inertial Properties of Electrons, deposited at VINITI, No. 4399-77, Moscow (1978).
8. Observations of the Aharanov-Bohm Effect, Nature, No. 7, 106 (1983).
9. G. V. Nikolaev, Scientific Vacuum. Crisis in Basic Physics. Is There Any Way Out?! Publishing House Kursiv, Tomsk (1999).

Large-Scale Sakharov Condition

David Noever and Christopher Bremner

NASA Marshall Space Flight Center,
Space Sciences Laboratory
Mail Code: ES76, Huntsville AL 35812

Editor's note: This article was presented by the autors for publication in New Energy Technologies. For the first time it was published in 1999 by the American Institute of Aeronautics and Astronautics, Inc. All copyrights belong to the authors.

Abstract

Recent far reaching theoretical results have used the quantum vacuum noise as a fundamental electromagnetic radiation field to derive a frequency (ω) dependent version of Newton's gravitational coupling term, $G(\omega)$. This paper reconciles the cut-off frequency with the observed cosmological constant, and then briefly puts forward a realizable laboratory test case in the 10 - 100 MHz frequency range. One analogy is drawn between the classical vacuum energy experiments with attraction between two closely spaced plates (Casimir cavity) and the arbitrarily dense material boundaries possible in Bose condensates, such as irradiation at MHz frequencies of superfluid helium or superconductors.

Theoretical Background

Zel'dovich [1] first suggested that gravitational interactions could lead to a small disturbance in the (non zero) quantum fluctuations of the vacuum and thus give rise to a finite value of Einstein's cosmological constant in agreement with astrophysical data. Using dimensional analysis and the suggestion by Zel'dovich, Sakharov [2] derived a value for Newton's gravitational constant, G, in only one free parameter, frequency, ω:

$$G \sim c^5 \Big/ h\int \omega d\omega \sim 1 \Big/ \int \omega d\omega$$

where c is the speed of light and h is the Planck constant. The free parameter in frequency when integrated over all values from zero to high frequencies must contain the usual integration cutoff value (Planck frequency on observable electromagnetic phenomenon).

Puthoff [3] and others [4 5] have extended Sakharov's condition in a relativistically consistent model to determine constants of proportionality. His model derives an acceleration term in first order expansion (in flat space time), then equates inertial and gravitational mass (by the equivalence principle) to make contact with the gravitational constant, G, directly as:

$$G = \left(\pi c^5 / h\omega_c^2\right) \sim 1 / \int \omega d\omega$$

which is the Sakharov condition [2,3]. This paper revisits the meaning of the cutoff frequency, ω_c, for radiation interactions, of which the quantum vacuum [6-10] and

Planck frequency are only the leading terms, and for which linear combinations of forces can introduce other plausible frequencies. One purpose of this reexamination is whether the resulting gravitational coupling constant, G, can be reconciled with the anticipated energy density of the universe [11] without resorting to extreme space time curvature and thus yield enough critical density to contain the expansion of the universe. Finally we particularize the case to the high-density fluctuations possible in Bose condensates [12], a potential experimental test case for how the effects of vacuum noise might manifest observably.

One far-reaching consequence of the vacuum energy model is the attractive force of gravity becomes reducible to the radiative interaction between oscillating charges, e.g. the zero point field (ZPF) applied to subatomic charges. Mass and inertia arise from the fundamentally electromagnetic ZPF oscillations.

This random background gives the usual quantum mechanical energy spectrum from particle field effects:

$$\rho(\omega)d\omega \sim \omega^3 d\omega$$

a very important dimensional relationship, since the third power in frequency avoids anomalous Doppler shifts from velocity boosts, or stated alternatively is the correct spectra for a Lorentzian (non accelerated) invariant radiation field [13].
More specifically, the energy spectrum [3] can be written as:

$$\rho(\omega)d\omega = [\omega^2 / \pi^2 c^3][h\omega / 2]d\omega = \\ = h\omega^3 / 2\pi^2 c^3 d\omega \sim \omega^3 d\omega$$

which is an expression in the first parenthesis of the density of the normal modes and in the second parenthesis of the average energy per mode. When this energy density is integrated over all frequencies, the ω^3 divergence produces well known infinities in the integration limit of high frequencies, thus an assumed cutoff frequency (appropriate to experimental observation limits at the Planck frequency), is usually introduced:

$$\omega_\rho = \left(c^5 / hG\right)^{1/2}$$

For mass, m, moving in an accelerated reference frame $g = -a = Gm/r^2$, the resulting energy spectrum includes a gravitational spectral shift [3],

$$\Delta\rho'(\omega)d\omega = h\omega / 2\pi^2 c^5 [Gm / r^2]^2 d\omega \sim 1 / r^4 d\omega$$

a kind of short range ($1/r^4$) gravitational energy shift, but electromagnetic in origin when zero point fluctuations are included. (N.B. To account for equal gravitational mass effects in neutrons and protons, the ZPF oscillations must involve subatomic charges, or 'parton' effects. The assumption derives from high frequency interactions of ZPF wherein these subatomic particles are asymptotically free to oscillate as independent or free particles as quantum noise).

A further far reaching consequence [3] is mass itself becomes interpretable as a dependent quantity derived from a damped (with decay constant Γ) oscillation driven by random ZPF:

$$m = \Gamma c^3 / G = 2h\Gamma / \pi^2 c^3 \int \omega d\omega$$

with the only two free parameters, the damping factor Γ, and again the frequency, ω. The internal kinetic energy of the system contributes to the effective mass.

This leads to an overall average spectral density, written in terms of mass as:

$$\Delta\rho'(\omega) = m^2 c^5 \omega / 2h\omega_c^4 r^4$$

for the electromagnetic field distribution near ($1/r^4$) to the mass, m, which in detail is half electric and half magnetic.

One additionally attractive feature is the correspondence between this derivation and the view of gravity as a dynamical scaleinvariance breaking model (e.g. symmetry breaking near the Planck mass energy [14]). A final result includes the force calculation between two ZPF radiation oscillators of the correct form yielding Newton's average force law

$$< F > = -Gm^2 / r^2$$

Thus, for a Newtonian force to first order in a flat space time, Sakharov [2] could be credited for proposing gravity as not a fundamentally separate force and Puthoff [3] and co workers [4-5] applied the vacuum electromagnetic field to equate gravity to a long-range radiation force (e.g. van der Waals like force). Higher order oscillatory gravity modes vary as $\left(\sin[\omega_o / \omega_c]\right)^2$.

To first order, a weak G coupling constant, $G = \left(\pi c^5 / h\omega_c^2\right)$, appears for high frequency cutoff at the Planck scale. A corollary in analogy to electromagnetic shielding by ordinary matter can be rationalized as the problem of frequency mismatch at high Planck frequencies, e.g. ZPF cannot be fundamentally shielded. In other words, frequency mismatch precludes gravity shielding by matter.

The purpose here is to revisit the only free parameter, the frequency cutoff, more in the spirit of a mass resonant frequency. The motivation for this approach can be summarized as: 1) the generality of other complementary radiation effects without relying on ZPF alone (e.g. other isotropic, homogeneous radiation sources); 2) the weak coupling constant, G, yields a vastly smaller than observed size of the universe (e.g. too small cosmological constant) when the Planck frequency is used as a cutoff value; and (3) the particle mass, $m = \Gamma c^3/G$, can be viewed as a renormalized or 'dressed' mass with a resonant interaction potential that is frequency dependent in its coupling constant, G, and with 'bare' mass that is large, $m_o \sim \left(m_\rho^2 / m\right)$, where the experimentally unobservable, $m_\rho = \left(hc / G\right)^{1/2}$ is the Planck mass.

In particular, why this large 'bare' mass does not generate a large gravitational field is not a unique anomaly in the Sakharov derivation, since similarly large vacuum point energies are common to field theories. The important point is that the derivation $G(\omega)$ is general however to any isotropic radiation field with the Lorentz invariant energy spectra $\left[\rho(\omega) \sim \omega^3\right]$, thus the candidates for the cutoff frequency of the particular radiation source can be interpreted as a Planck scale only if the rest mass, m_o, is not composed of many terms, rather than just the ZPF leading term. Since the ZPF is akin to a van der Waals force [3 5], polarizability (in charge and mass) must be considered, but without also excluding any number of linear combinations that might have alternative cutoff frequencies, ω_c, or damping terms, Γ, 'ala particle physics interpretations for resonant masses during renormalization. In other words, once a gravitational energy spectrum, $\rho(\omega)$ is postulated that is Lorentzian invariant, many fundamental sizes (or corresponding frequency values) are smeared (or dressed) by any number of characteristic frequencies between zero and the high frequency electromagnetic (Planck) cutoff ω_ρ. Quite simply, is the expression, $\omega_c = \omega_\rho$, a requirement for all radiation sources?

Many types of particle oscillations may satisfy the general requirements of a Sakharov condition, each having a characteristic mass (and energy) as in calculating the mass of any fundamental particle at its resonant frequency (including underlying partial charges or dense bosons). This brings the calculation to a consideration of the high density fluctuations characteristic of a Bose condensate [15 19]. While the high density variation may intrinsically be of interest, the exploration has more to do with reconciling the ZPF interpretation of the Sakharov condition with the observed cosmological constant [14].

A "top down" view of calculating the cutoff frequency imposes the self consistency test for the cosmological constant, Λ, from the outset. To calculate, the total frequency integrated energy density of the universe must be included:

$$\rho(E) = \int \rho(E) dE = h\omega_c^4 / 8\pi^2 c^3$$

which must have a mass equivalent, contribute to the universe's curvature, and thus have a fundamental relation to the critical density to contain the expansion of the universe [14 15]. The mass - equivalent ZPF to reach the universe's critical density [15], $\rho \sim 10^{-29}$ g cm^{-3} would necessarily limit the cutoff frequency for gravity to the value, $\omega_c < 7 \cdot 10^7 s^{-1}$, or between 10 -100 MHz.

A higher frequency greatly overshoots the cosmological constant, Λ, and induces extreme curvature in the universe. This problem has been cited frequently and stated most bluntly, as either ZPF or the cosmological constant requires revision. The relevance here arises from similarly large positive coupling terms in quantum gravity [15], which also generate a local gravitational Instability for typical upper limits on the cosmological constant, $\Lambda/8\pi G < 10^{12}$ cm^{-4}.

Rather than to dwell on the inconsistencies that plague attempts to reconcile quantum gravity, we particularize the problem to a case where the restriction to Planck scale becomes less clew, namely the high density fluctuations and universal scaling introduced in a Bose condensate. A Bose condensate, such as superfluid helium or superconductors [15 19], becomes of potential interest, mainly because of its arbitrarily dense boundaries and the classic Casimir experiment [20 22] which allows such dense material boundaries (two closely spaced conducting plates), if available, to modulate the background quantum fluctuation of ZPF. In other words, the matter-ZPF interaction becomes measurable by the observed attraction between two material boundaries. What dense boundaries might generate in Bose condensates remains a subject of great interest.

The significant case to investigate is whether Casimir-like interactions [20 22] will not only couple to ZPF radiation at a scale comparable to the quantum noise (or other radiation field), but also alter the value imposed by the Sakharov condition for G. It remains an open question whether this potential coupling interaction shares, as in ordinary critical phenomenon, the density correlation function, Φ, that is both independent of the coupling strength (or universal in renormalization) and consistent with the observed average energy density of the visible universe.

Thus the purpose here has bow to restate the Sakharov condition in the gravitational coupling constant, G, based on its only free parameter, a frequency cutoff, ω_c. Any potential relevance arises from similarly large values for the positive coupling term in quantum gravity, which generate conditions for a local gravitational instability for typical upper limits on the constant, $\Lambda/8\pi G < 10^{12}$ cm^{-4}.

To restate the Sakharov condition, matter in the vacuum provides boundaries for reduced 'Casimir like' modes available for otherwise isotropic radiation from quantum fluctuations (broad spectral noise). That this view reproduces Einstein gravity has been examined, including the full relativistic derivation [4-5]. The details of the appropriate mass, however, remain buried in the kinetic energy of general internal particle ('parton') motion [3]. Any appeal to a specific parton representation is limited only by essentially free particles with high frequency interactions, including underlying partial charges or dense bosons. The basis of considering arbitrarily high-density fluctuations in Bose condensate in analogy to the ZPF-Casimir experiment remains both an empirical and theoretical case to examine. There exist laboratory scale cases [15-19] where resonant radiation in the required 10-100 MHz range appear to produce anomalous effect for such Bose condensates as superconductors, but further work to confirm these results would be needed. In other contexts, these effects have been discussed as the Schiff-Barnhill effect for superconductors interacting with a gravitational field [23], but for the static rest moss rather than an effective mass in a conduction band.

Experimental Propositions

J. Weber [24,25] proposed the use of a superconducting Bose condensate for gravity wave detection, principally because of its potentially higher signal to noise ratio in carrying electrical signals upon length dilations in a relativistic framework for gravity waves travelling near the speed of light. W. Weber and Hickman [26] derived an experimentally testable relation based on torquing of a charged capacitor parallel to a gravity field, with

$$\tau = 2E_g / \pi[\alpha / (1-\alpha)^{1/2}]$$

where the capacitor will rotate relative to the gravity vector, for $\alpha = 2GM / rc^2$, is Schwarzschild radial coordinate $[dR = dr(1-\alpha)^{1/2}]$, E_g is dependent on the capacitor charge and geometry of the plates, $E_g = [Q^2 d/2\varepsilon WL(1-\alpha)^{1/2}]$, for a plate separation, and radial dimensions,W and L, charge Q, and ε the permittivity of free space. For plate separations of 2 mm on Earth, the maximum torque is approximately $\tau = 10^{-12}$ Nm, when charged to 2/3 dielectric breakdown. While not entirely promising for detection of such low torques, the large separation (2 mm) distance between capacitative plates naturally prompts generalization to the classic Casimir force [21] experiments only recently confirmed experimentally [20]. In particular, we rewrite the torque values to include the frequency terms derived with the Sakharov condition

$$[G = (\pi c^5 / h\omega_c^2)]:$$

$$\alpha = 2M\pi c^3 / h\omega_c^2 r$$

The appeal of this formulation is that a frequency dependent torque is derived, which further makes contact with proposals to modulate the Casimir capacitative plates for continuous extraction of energy [27]. This result requires further investigation experimentally, particularly to compare with previous reports for anomalies in AC- tuned electrical capacitors [28].

References

1. Ze1'dovich Ya. B. JETP Letters, 6, 345, 1967.
2. Sakharov A. Vacuum quantum fluctuations in Curved Space and the Theory of Gravitation, Sov. Phys. Reports, 12,1968,1040 1041.
3. Puthoff H. E. (1989) Gravity as a zero-point fluctuation force, Physical Review A, 39(5): 2333 2342, March 1, 1989.
4. Haisch B., Rueda A., Puthoff H.E., (1994) Inertia as a Zero Point Field Lorentz Force, Physical Review A, 49:678 694.
5. Haisch B., Rueda A., Puthoff H.E.,"Inertia as a Zero Point Field Force" Physical Review A 49, N 2, 678 (1994).
6. Ambjorn J. and Wolfram S. (1983) Properties of the Vacuum, 1. Mechanical and Thermodynamic, and Properties of the Vacuum, 2. Electrodynamics, Annals of Physics
7. Ambjorn J. and Wolfram S. (1983) Properties of the Vacuum. 1. Mechanical and Thermodynamic, Annals of Physics, 147:1 32.
8. Fulcher et al., "The Decay of the Vacuum," Sci. Am., vol. 241, p. 150, Dec. 1979
9. Puthoff, H.E. "Source of Vacuum Electromagnetic Zero Point Energy" Physical Review A 4 0, 4857 Nov 1 (1989); Errata and Comments, Physical Review A 4 1, March 1(1990); Physical Review A4 4, 3382, 3385 (1991)
10. Senitzky I.P., "Radiation Reaction and Vacuum Field Effects in Heisenberg Picture Quantum Electrodynamics", Phys. Rev. Lett. 31(15), 955 (1973). As pointed out by Puthoff [3] the relativistic results for the Sakharov condition have so far been encouraging, while the consequences for nuclear interactions in all coordinate frames have not been fully explored.
11. da Costa L. N., Freudling W., Wegner G., Giovanelli R., Haynes M. P., and Salzer J. J. (1996) The Mass Distribution in the Nearby Universe, Astrophysical Journal Letters, 468: LS L8 and Plate L 1
12. Modanese G. (1996) Theoretical analysis of a reported weak gravitational shielding effect, Europhy. Lett., 35(6):413 418.
13. Shupe M.A. The Lorentz invariant vacuum media, Am. J. Phys. 53, 122 (1985). A cautionary note is that lower frequency cutoffs can violate Lorentzian invariance, thus allowing a moving detector to reveal absolute motion by recording Doppler sifted frequencies. Standard methods might treat such effects like the cancellation of terms that remove anomalous ZPF infinities from field theories, but these topics remain to be explored.
14. Zee, A. Phys. Rev, Lett, 42,417 (1979); Phys. Rev. D. 23, 858, (1981).
15. Torr D. G. and Li. N. (1993) Gravitoelctric Electric Coupling vVia Superconductivity, Foundations of Physics Letters, 6(4): 371 383.
16. Unnikrishan C. S. (1996) Does a superconductor shield gravity? Physics C, 266:133 137.
17. Podkletnov E. and Nieminen R (1992) A Possibility of Gravitational Force Shielding by Bulk $YBa_2 Cu_3 O_{7-x}$ Superconductor, Physics pp.203: 441 444.
18. Li N, and Torr D. G. (1992) Gravitational effects on the magnetic attenuation of superconductors, Physical Review B, 46(9): 5489 5494. A simple consequence of the Sakharov condition $G = (\pi c^5 / h\omega_c^2) \sim 1/\int \omega d\omega$, can be written for the gravitomagnefic permeability as: $\mu_g = 4\pi G / c^2 = 4\pi^2 c^3 / \left(h \int_{\circ}^{\omega c} \omega d\omega\right) \sim 1/\int \omega d\omega$ which suggest that the same frequency resonance implied by the ZPF derivation will share similar consequences for vector gravity

effects. See also, DeWitt, B. S. Superconductors and Gravitational Drag, Phys. Rev. Lett. 16, 102(1966).

19. Li N., Noever D., Robertson T., Koczor R., and Brantley, W. (1997) Static Test for a Gravitational Force Coupled to Type II YBCO Superconductors, Physics p., 55, 287.
20. Lamoreaux S. K. (1997) Demonstration of the Casimir Force in the 0.6 to 6 mm Range, Phys. Rev. Letters, 78:5 8.
21. Milonni P.W. et al., “Radiation pressure from the vacuum: Physical interpretation of the Casimir force”, Phys. Rev. A, Vol. 38, No. 3, 1621 August 1988.
22. Milonni P. W. (1994) The Quantum Vacuum, Academic Press, San Diego, CA.
23. Schiff L.I. and Barnhill M.V. Bull. Am. Phys. Soc. 11, 96, (1966) and refn. 18.
24. Weber J. (1960), Detection and Generation of Gravitational Waves, Physical Review, 117(1)306 313.
25. Weber J. (1966) Gravitational Shielding and Absorption, The Physical Review (The American Physical Society), 146(4): 935 937.
26. Weber W. and Hickman H. (1997) A possible interaction between gravity and the electric field, Spec. Science Tech. 20, 133 136
27. Forward R.L. “Extracting electrical energy from the vacuum by cohesion of charged foliated conductors” Phys. Rev. B, Vol. 30, No. 4,1700 August 1994
28. Woodward, J. F. (1992) A Stationary Apparent Weight Shift From a Transient Machian Mass Fluctuation, Foundations of Physics Letters, 5:425 442.

The Problem of Electron and Physical Properties of Time:

To the Electron Technologies of the 21st Century

V.P. Oleinik

[*]Department of General and Theoretical Physics,
National Technical University of Ukraine
“Kiev Polytechnic Institute”,
Prospect Pobedy 37, Kiev, 03056, Ukraine [**]Institute of
Semiconductor Physics, National Academy of Sciences,
Prospect Nauky 45, Kiev, 03028, Ukraine;
e-mail: yuri@arepjev.relc.com

> ***“…it is necessary to periodically subject to the deepest revision the principles, which were recognized as final and were no longer discussed”.***
> ***Louis de Broglie***

Abstract

The results of an approach based on the synthesis of standard quantum electrodynamics and of the ideas of self-organization in physical systems are briefly outlined. The quantum model of electron as an open self-organizing system is constructed, with the physical mechanism of self-organization consisting in the back influence of the own field created by electron on the same electron. The own field is considered as a physical property of electron, intrinsically inherent in electrically charged matter, which is included in the definition of the particle from the very beginning. The own field of electron endows the particle with wave properties and represents a bearer of superluminal signals, which can be used for the creation of qualitatively new communication systems. Because of the inseparable link between space and time, the force in relativistic mechanics is the cause of change not only of the velocity of particle, but also of the course of time along the particle’s trajectory. For this reason the flow of time in some area of space depends on the character of physical processes, occurring in it, and, therefore, time can be controlled by slowing down or accelerating its course with the help of material processes. The conclusions of the paper are not in conflict with the special theory of relativity (STR); they are a direct consequence of relativistic equations of motion and represent an essential development of the generally accepted notions about space and time. At present all the necessary prerequisites are available, both theoretical and technical, for the practical mastering of the own fields of particles and of the physical properties of time.

1. Introduction. The Problem of Electron and Future Outlook

Electrodynamics, what is this? What is its value for man? Electrodynamics is the theory of electromagnetic interaction, one of four interactions existing in nature. Its role in the life of society is seen from the fact that the most part of natural phenomena, which we encounter at every step, is of electromagnetic origin: it is due to the interaction of electromagnetic field with electrically charged particles entering into atoms and molecules. It is fair to say that electromagnetism plays a crucial role in the life of mankind as it determines the ways of technical advance of society [1].

The key problem of quantum electrodynamics is the problem of electron, which can be formulated as follows: to construct from the first principles a non-contradictory model of electron, which takes into account experimental facts, i.e. to find the dynamical equation capable of describing the unique physical properties of electron, its internal structure, its behaviour when it interacts with electromagnetic field.

Electron was discovered a little more than 100 years ago, in 1897. With discovering the electron the revolution in physics began, which has resulted in unprecedented technical advance of society. The summit of development was reached in the middle of the 1950s and then the long period of evolutional development followed, when new physical principles were used to describe various physical processes and phenomena. The violent development of physics became slower in the 1970s and was replaced by stagnation in the subsequent years. The stagnation in electrodynamics continuing already over a period of several decades is gradually giving place now to a new ascent. The new scientific revolution is starting, which is associated with electron again, much as it happened hundred years ago. The reason is that electron is the most unique particle storing in itself the deepest mysteries of nature and the degree, to which they are disclosed, determines the wants to stay anonymous, until his patent application is done and university verification tests will be done). The claims are: 1200 Watts coil out with about 1076.4 Watts in into the driving motor at 3450 RPM. 8 amps 117volts at no load 9.2 amps 117 volts at full load. The output of about 1200 Watts is already a total overunity operation! As they just increase the input power by about 140 Watts only between idle and load state and they get 1200-Watts output it seems indeed a case, where Lenz law is violated! This generator also has NO motor effect! If you supply current to the coil, the permanent magnet in the center will not rotate; cause the flux just stays inside the toroid core! There you can see, that the back drag does not influence the mechanical rotation of the magnet!" Stefan used very good criterion to prove high efficiency of the design: **There is no back-torque effect! It is most important aspect of Gramm's generator.** You can contact directly Stefan Hartmann: Keplerstr. 11 B, 10589 Berlin, Germany. Tel: +49 30 345 00 497, FAX: +49 30 345 00 498 email: harti@harti.com info@ccard.net (Please, note: Dr. Harman referred to my old web site www.time-machine.spb.ru which is closed now).

So, basic principles of MEG and Φ-machines are the same. It was patented more than 100 years ago. Primary magnetic flux is topologically separated in two (or more) fluxes, which are mutually compensated in the ring core. Advantages of MEG are absence of moving parts since special input coils produce changes of primary flux. Also level of saturation in ferromagnetic material obviously should be corresponding to intensity of primary magnetic field, which is created by the permanent magnet, Fig.4.1.

Besides MEG the same principle can be (and already was!) realized in many other systems. So, there is no any news in the USA patent #6,362,718 granted for "The Motionless Magnetic Generator". What did they claim? You can find it in the patent: "The first input coil and the first output coil **extend around portions of the first magnetic path**, while the second input coil and the second output coil **extend around portions of the second magnetic path."** Yes, it is the same bi-directional principle we discussed above: two parts of the magnetic flux and each coil produce effect to reduce flux due to this superposition.



Fig.4.1



Fig.4.2
Diagram of prototype by Bearden.

In conclusion I'd like to confirm our sincere interest to develop joint work with all new energy research teams if they are not trying to obscure the issue of the technology by means of complex theoretical constructions and common words about zero point energy.

Matter as a Resonance Longitudinal Wave Process

Alexander V. Frolov

Abstracts

There is experimental data on gravitation anomalies for cases of resonance irradiation of the Bose condensates (superfluid helium or superconductor) at 10-100 MHz frequencies. It is developed by the author in frames of his aether theory that can be used for practical applications in aerospace and new energetics.

ZPF or aether fluctuations

The fundamental electromagnetic radiation field (Zero Point Field) ZPF or the quantum vacuum noise is a recently accepted physical notion. In the article [1] David Noever and Christopher Bremner used it to derive a frequency – dependent version of Newton's gravitational coupling term G. On the other hand we can consider the quantum vacuum noise as aether fluctuations. Dr. Alexander Mishin [2] described experiments on registration of these processes by means of special equipment. Both approaches (ZPF and aether fluctuation) allow to conclude that mass and inertia arise from these oscillations. However if we are considering the oscillation as some aether process then we can assume and describe some physical mechanism of this process.

One of consequence of the vacuum energy model, which is described in [1] is that "the attractive force of gravity becomes reducible to the radiative interaction between oscillating charges..." Let's clarify which kind of radiation can be created by oscillating electric charges.

There are many different sources to find the answer on this question and one of them is the article by Prof. Kirill P.Butusov [3] on symmetrization of Maxwell's equations and practical methods of generation of longitudinal waves in vacuum. So, ZPF model has a direct relation with the aether model since indirectly it leads to the question of longitudinal waves in vacuum. Physically they are waves of density of energy and in the aether model the waves are areas of more dense and more rarefied aether. Let's note that there are standing waves besides moving waves.

To consider the interaction of some mass particles and the fundamental field the notion of subatomic charges "partons" was introduced [1]. So, the mass itself "becomes interpretable as a dependent quantity derived from a damped oscillation driven by random ZPF" [1]. The authors wrote about "internal kinetic energy" of the mass particle and it can be considered as a function of ZPF oscillation frequency. In the aether theory of mass there is a similar notion of "aether vortex", which represents some cyclical process of some frequency and it is possible to calculate its kinetic energy. This aether vortex model of matter elements allows to assume real methods to change parameters of vortex and to get changes in parameters of existence of the matter. On the other hand we can discuss the possibility to change some physical parameters of aether in areas of the vortex to get the same result. This possibility follows from the well-known N.Kozyrev's experiments, which were named "investigation of active properties of time". N.Kozyrev used chronal (temporal) approach in his theory. We have to change his notion "the density of time" to "the density of aether" to get a direct link between his experiments and the aether theory of mass.

N.Kozyrev and others have [4,5,6] experimentally demonstrated that irreversible processes in matter produced changes of aether density in the area of the experiment. Detectors of different type can register this change. It is obviously that any matter element (i.e. the aether vortex) in this area of changed aether density should get more inner (kinetic) energy or slow the inner motion. From the chronal point of view these are changes of inner time of this matter element.

Gravity shield

One more interesting point that is discussed in the article by Noever and Bremner [1] is a problem of gravity shield. The authors show that resonance interaction with ZPF produces "the particle mass" and it can be viewed as "a renormalized or "dressed" mass with a resonant interaction potential. Similar resonance approach is used in the conception of de Broglie's matter waves. Also the authors [1] mentioned the existence of an experimentally unobservable mass. In this case ZPF cannot be fundamentally shielded by matter since "frequency mismatch precludes gravity shielding by matter" [1]. The only way to get screening of ZPF fluctuations seems to be very complex: it is necessary to provide frequency matching for whole wavelength band of the oscillations.

I think some specialization is necessary here to explain experimental gravity anomalies with Bose condensates experiments (superfluid helium or superconductors): **special process in matter can be used as the gravity screen and this approach does not involve the frequency-matching problem.**

We have concluded above that any matter element is a resonance process and its energy is derived from ZPF. It is useful to note that these are longitudinal wave oscillations of energy density in aether. In this case, the gravity shield problem can be solved in frames of the aether vortex conception of matter.

The longitudinal wave is a moving (or standing) areas of rarified and thickened aether. Let's consider the moving wave, which is responsible for gravitation attraction effect. How can we stop, re-direct or reflect longitudinal wave in aether by means of aether vortexes (matter elements)? **We can produce interaction with this wave only by means of other longitudinal waves.**

In macro-level this idea can be realized as longitudinal wave generator. Electromagnetic processes, which can be used as sources of directed longitudinal waves, are known and some of them are described in [3]. In other way the gravity shield can be produced as longitudinal waves generated by natural aether vortexes (i.e. by matter elements) if the matter exist in a special exited state, for example for cases of resonance irradiation of superfluid helium or superconductor at 10-100 MHz frequencies.

Matter element as resonance process

In [1] the authors wrote that it is possible to calculate "the mass of any fundamental particle at its resonant frequency." There is the question: what is the general basis of whole spectrum of stable elements masses?

In 1996 the author published the article "The concept of mass process" [7]. At first in this work physical sense and notion of 3-dimensional curvature was introduced. By analogy with known mathematical notion of linear curvature $\rho_1 = \frac{1}{r}$ (where r is radius) and uniform surface curvature $\rho_2 = \frac{2}{r}$ it was proposed to calculate curvature of a 3-dimensional space as

$$\rho_3 = \frac{3}{r} \qquad (1)$$

The radius r in this case means that in a 3-space there is some periodical process. In other words, 3-dimensional matter is a resonance process.

Further, de Broglie used formulations E=hf and E=pc (where p is momentum, h is Planck constant, f is frequency and c is velocity of light) to derive the following:

$$hf=pc \qquad (2)$$

that allows us to get the well-known formulation

$$\lambda = \frac{h}{p} \qquad (3)$$

There is another logical branch of this idea that leads to the understanding of the mass properties of matter as a resonance process. Instead of E=pc in [7] it was proposed to use E=mc^2. In strength of the wave-particle duality we can write the equation

$$mc^2 = hf \qquad (4)$$

and from this equation the mass can be presented as resonance electromagnetic oscillations

$$m = \frac{h}{c^2} f \qquad (5)$$

Let's note that f=1/T, where T is some period of oscillation. So, we can write the following

$$m = \frac{h}{c^2}\frac{1}{T} \qquad (6)$$

where $\frac{h}{c^2}$ is new constant between mass and period of time.

There is an important conclusion: any mass is a process and there is some period of time, which corresponds to this mass. In other words, there is no physical sense of time separate from some process of existence of mass. Product mass and period is a constant value, which was named as a chronal constant

$$mT = \frac{h}{c^2} = const \qquad (7)$$

The chronal constant is a parameter of some real space and it is equal to $0.73725 \cdot 10^{-50} [Js^2 / m^2]$

Also in this work [7] there was a demonstration of several examples of newly discovered physical law: spatial curvature of some natural objects (proton, planet, DNA molecule) is a whole number. There is some analogy with the nuclear physics notion of wave number. From this fact we can assume that main natural matter elements exist in main resonance states. For example, if Bohr radius is 0.52917 Angstrom, then we can find the wave-length $l = \pi d$ and the linear curvature is $\rho = 1/l = 3.0075 \cdot 10^9 \ (m)$ and 3-dimensional curvature of this object is $\rho = 3/l = 1.0025 \cdot 10^9 \ (m)$ that is unit of mater, corresponding to simplest atom, i.e. unit matter engine. Let's note that it is near the unit and some distortion of 0.0025 means non-ideal resonance state of the system.

Calculations for planet Earth in [7] were based on the known period of orbital rotation T=31557600 sec that corresponds to frequency of electromagnetic oscillations

$$f = 1/T = 3.168861 \cdot 10^{-8} (1/s) \qquad (8)$$

and wave-length

$$\lambda = c/f = 9.46... \cdot 10^{16} (m) \qquad (9)$$

The curvature (if this wave-length is considered as radius of the resonator) is following wave number

$$\rho = 1057.00 \cdot 10^{-20} (1/m) \qquad (10)$$

Also we can use other known data about the planet. Daily rotation period of our planet is known T=86400 sec and we can calculate its wavelength $\lambda = 3469{,}82(m)$ and corresponding curvature (wave-number). Sure, it is also a whole number with a good accuracy:

$$\rho = 2882 \cdot 10^{-7} (1/m) \qquad (11)$$

The laws of physics in macro cosmos and micro cosmos are similar. From these calculations it was assumed that whole formation of mass spectrum of stable chemical elements of matter is determined by similar physical mechanism.

Creation of mass

In short we can summarize that technology of longitudinal waves in aether is a real basis for creation of matter with mass and inertia properties. N. Tesla used this method to produce different objects: from ball lightning up to electrons. Velimir Abramovic says in his article [8]: "The principle of resonance and harmonic oscillation of aether seems to be so clear that all problems of modern physics, especially a problem of energy conversion, will be solved with its development. By means of his vacuum tube Tesla got protons, electrons and neutrons directly from aether and reproduced them at any distance. Instead of giving a possibility to the bundle of protons to move through space to some place, he created conditions for momentary appearance of arbitrary quantity of particles in the given place."

Any objects can be classified as aether vortex and parameters of this vortex determine its mass, electric charge and other properties of matter.

The "parton" as element of matter in [1] is a useful tool for description of physical properties of aether.

Longitudinal waves in Woodward's experiment

In [1] the authors state that resonant radiation in the required 10-100 MHz range appears to produce anomalous effects for such Bose condensates as superconductors. In my opinion it is a particular case of discussed above technology of longitudinal waves in aether due to possibility of transformation of transverse electromagnetic waves in longitudinal waves in the superconductors. This transformation in plasma is a well known physical mechanism.

More facts to prove this idea: by Woodward [9] there is a special requirement, i.e. the frequency of mechanical vibrations should be twice the frequency of electrical oscillations in the capacitor, which demonstrates the weight anomalies. But from the other hand it is a common rule for creation of longitudinal weaves in plasma! Also it is a necessary condition for generation of parametrical oscillations! So, we can assume that basis of the effects in [1] and [9] is a generation of longitudinal wave in aether.

Conclusion

Any element of matter can be considered as resonance process of aether oscillations, which are longitudinal waves. There is an analogy with description of these longitudinal waves and well-known matter waves by de Broighl. Experimenting on the longitudinal waves generation and especially experiments on standing waves to get gradient of aether pressure allows to develop gravity control technology.

References

1. D. Noever and C. Bremner, NASA Marshall Space Flight Center, Large Scale Sakharov Condition, 35th AIAA/ASME/SAE/ASEE joint Propulsion Conference and Exhibit, 1999, Los Angeles, Ca, USA.
2. Alexander M. Mishin, The physical system of artificial biofield (experimental research of ether), New Energy Technologies, #1, 2001, p.45.
3. Kirill P.Butusov, Symmetrization of Maxwell-Lorenz equations, New energy Technologies, #2(5), 2002, p.14.
4. Kozyrev N.A. Selected Works, 1991, Leningrad, publ. by Leningrad State University.
5. L. Shikhobalov, N. Kozyrev's ideas today, New Energy Technologies #2 (5), 2002, p. 20.
6. Alexander V. Frolov, Kozyrev on possibility of decrease of mass and weight of the body, New Energy Technologies #2 (5), 2002, p. 35.
7. The Concept of Mass Process, Frolov A.V., Proceedings of the congress "New Ideas in Natural Sciences", 1996, St.Petersburg, published by PiK Co., p.123-134.
8. Tesla, Velimir Abramovic, New Energy technologies, #1(4) 2002, p.17.
9. Woodward, J.F. A Stationary Apparent Weight Shift From a Transient Machian Mass Fluctuation, Foundations of Physics Letters, 5, p.425-442, 1992.

Gerlovin's Theory of Activation

Alexander V. Frolov

It is a review of the famous book by Ilia L. Gerlovin "Basis of unified theory of all interactions in matter"published in 1990, St.Petersburg, Russia. We hope this article let you discover some new aspects of physical vacuum structure to develop more new experimental methods. Comments made by Alexander V. Frolov, Editor.

In [1] the author wrote about different methods to activate water solutions: mechanical, thermal, acoustic, magnetic and electrical. One of the known methods is an activation by means of electrohydraulic method. There is also some information about activation of other mediums, mainly liquids, but also some gases and solid bodies.

There are no theoretical explanations of these facts to explain all aspects of these phenomena. Furthermore, complexity of interpretation of these phenomena in frames of common physical notions induced some scientists to announce these phenomena as non-existing and "illegal".

Ilia L. Gerlovin formulated the physical principles of theory of activation of mediums on the basis of new physical theory, the Theory of Fundamental Field (TFF). These principles are based on his two important conclusions from the TFF:

a) "Space around us is not empty, physical vacuum consists of material physical objects, i.e. elementary particles of vacuum (EPV). These particles are responsible for main activation processes;
b) Force interactions between atoms in molecule, between molecules in crystals has not spherical symmetry in the crystals of solid bodies, but an axial symmetry and the interactions are changing in time with very high frequency of about 10^{18} Hz. This feature of force interactions also makes its own contribution to the activation of mediums." [1, p. 314]

So, it was assumed that the phenomenon of activation of mediums can be defined as anisotropy of force interactions, which leads to **"meta-stable state, which can be called *structurally activated state of the given structure*".**

Here is some difference in principle between chemical term "activation", which characterizes a transformation of molecule or atom in some active state with an increased energy, which is sufficient to provide a chemical reaction. It is ***energy activation*.** **Gerlovin described new notion, a *structural activation:* "This phenomenon can be classified as some change of structure of activation object. With this, energy of molecule can have no changes, and *active properties***

Coupled with aetherodynamics time conception, which was suggested by Alexander V. Frolov, the works on the control of space-time parameters gain the possibility for development and commercial application. As a theoretical basis there are those N. Kozyrev works where his conception of "time density" are replaced by that of "aether density" according to Frolov.

In September 2002, Faraday Labs Ltd Company plans to complete testing of the first experimental system, and to start the patenting and research of applied aspects, first of all in medicine.

Physical Principles of the Time Machine

Alexander V. Frolov

Experimental success of research team headed by Dr. Vadim A. Chernobrov, Moscow was reported in [1]. The time course can be controlled as rate of any process in local space-time (inner space of the Time Machine). It can be decelerated or accelerated by means of special "converging electromagnetic waves". Ordinary waves move from the source whereas special "converging waves" move to some central point, i.e. into the focus of the system. In Chernobrov's design of the Time Machine this process is organized by means of several spherical envelops, which consist of several electromagnets. Electronic control unit controls the processes in this design. Dr. Chernobrov reported about 3% change of the time course in 4th version of the system, which was tested with a human inside. The goal of Dr. Chernobrov's work is to research the medical aspects and experimental investigation of the principles. Several important conclusions were obtained from the project: the time course can be controlled and character of the changes is different for acceleration and deceleration mode.

Other known publication and research projects on the same topic seem to be very far from any commercial and practically useful application. Obviously the topic is very new and fantastic for most of scientific community and at first we have to clarify the physical principles of the time control project, which is started by Faraday Labs Ltd.

In this project we believe that notion of time is one of possible description of real physical properties of our Universe. So, it is not mathematical abstraction but some aspect of physical reality and we can discover some physical properties of time. Russian astrophysicist N. A. Kozyrev [2] developed a theory of active properties of time and according to his point of view there are two properties: time course and time density. Prof. Kozyrev demonstrated experimentally that time density in area of some process (changes of matter) is dependent on entropy parameters of the processes. In [3] it was demonstrated that Kozyrev's experiments could be interpreted in aether theory and it has led to simple physical conclusions and clear experimental perspectives: **time course and its density can be explained and controlled as parameters of aether.** Directions of aether flow and density of aether are subjects of experimenting with non-reversible changes in matter, for example, in crystallization or melting processes. Also it is possible to use special electromagnetic processes, for example, Chernobrov's "converging waves" or other longitudinal waves as methods of aether compression or rarefaction. If we assume that process of existence of elements of matter physically can be explained as aether vortex processes then its rate is a parameter of **aether income/outcome balance** (aether inflow in element of matter and aether outflow from the element of matter). It was also described in Time Rate Control (TRC) theory [3]. To control this balance it is necessary to develop technology of longitudinal waves generation, its focusing and resonance effects. The previous research and experimenting on the topic has been made by N. Tesla.

Let's assume that we have some technology to change parameters of time course. How should we organize this local space-time (what is spatial topology of the design)? There is a very interesting experiment to get the answer: rotation of a heavy cone (for example, lead cone) entrains surrounding aether, so a vortex appears, which is a toroidal formation of aether (rings). The rings can exist in space for a long period. The further question is: Why does the beam of light (laser beam) directed to the cone by tangent create a luminous ring? We can assume that due to natural properties of photons (light propagates along the geodesic line in space) some autonomous closed toroidal space should be created in such experiment. The next thought is: since space and any matter exist in time then we can speak about some autonomous time. The general conclusion is to be the following: autonomous 4-dimensional space-time can be created as toroidal aether vortex.

Here is point to note some aspects of research project by Prof. Robert Mallett, Connecticut University, USA. In fact, sometime next year, he hopes to produce the first piece of technology that eventually will allow him to build a time machine. By Mallett it will be a device that employs lasers "to twist space". Why is he going to close the beam of light? His theoretical background is knowledge about black holes, i.e. understanding of the connection between gravity and curvature of space-time. In Einstein's theory both matter and energy can bend space and time. So Prof. Mallett assumes that curvature of space-time can be changed not only by mass (like a black hole) but it can be affected by energy of photons. This has led Prof. Mallett to consider the possibility of using a circulating beam of light to twist space and to create closed loops in time. It is predicted that a spinning neutral particle, when placed in the ring, is dragged around by the resulting gravitational field [4]. From the first view it is the same approach we have considered above (experiment with aether toroidal rings). But proposals by Prof. Mallett differ in principle from the aether conception.

The main aspect of this technology is a creation of autonomous (self-closed) toroidal space-time. Autonomous geodesic world line of this space-time is self-closed. Any photon should be circulating in this system due to its properties: photon is always moving along the straight line of the space.

More deep understanding of this technology follows from the explanation of photon as oscillation of aether. Any photon can be considered as result of relative motion of the matter (observer) in absolute space (immovable aether). Usually a photon is considered as moving object in space. But we can assume that observer is in the motion and the photon is oscillations of the absolute space (immovable aether). Which approach is more real one? Sure, it is more easy to consider a photon as moving object but let's remember fact of our real motion in the Universe and fact of the Universe expansion.

So, ideas by Prof. Mallett are very far from the **aether nature of the time phenomenon.** He follows the black holes theory and general understanding of space-time distortion due to mass or energy presence. Also he knows that a light beam should be closed in a ring. However Prof. Mallett is very far from physical basis of the effects. **The key of time rate control is technology of artificial aether flow, creation of aether vortex systems (AVS), management on density and direction of aether flow.** There are several technical methods to produce it. Any light beam should be curved in self-closed "light ring" if it is placed in a toroidal aether vortex and we can say that this system has own space-time.

What does "some changes of time course" mean? We can measure it as some changes of standard rate of oscillation process, for example, some stable wavelength of laser beam or quartz oscillations. There is a well-known experiment with two atomic clocks (one of the clocks is placed on the roof of some building and another one is placed on surface of planet). Due to vertical component of gravity the time course should be different and it can be measured. How can we organize difference in these measurements if both atomic clocks are placed in the same altitude?

It is necessary to consider gravity nature in frames of the aether conception. Two atomic clocks demonstrate difference in measurements due to difference in aether flow density. Hence, by means of aetherodynamics methods it is possible to control the rate of oscillation processes in the atomic clocks and in any matter (i.e. time course itself).

The aetherodynamics methods have a clear analogy with electrodynamics: **motion of charge produce field and there is the induction law**. Really, classical electrodynamics can be considered as particular case of the aetherodynamics. So, physical sense of any field is stress or deformation (it is some static field) or oscillations of aether.

Let's introduce the notion of chronal (temporal) charge to consider some technical aspects. In electrodynamics we assume an electric charge as element of matter with positive or negative electric properties and we have to compare it with some reference (zero charge or test charge). Let's note that in any case we have to consider "charge of some particle" but not an "abstract charge". So, we can postulate that any element of matter has **zero chronal charge** if it is moving from Past in Future with standard (usual for measurements of surface of our planet) time course. If the time course (i.e. existence of some element of matter) is decelerated then it can be measured as decrease of standard oscillation frequency of the matter. Time course acceleration means some increase of standard oscillation frequency of the matter. Let's determine that in the first case it is negative chronal charge and in the second case it is some positive chronal charge. Atomic clock is one of possible methods to measure zero chronal charge or to find some relative positive or negative difference.

It is predicted here that motion of chronal charge should produce a chronal field. Some provisional data was received by Frolov from simple experiments on the rotation of a heat source. Accelerated motion of chronal charge (changes of density of chronal current) should produce aethero-induction effect that is an analogy (or more general case) of Faraday's induction effect. This effect can be detected as secondary (induced) deceleration of time course in nearest area of accelerated time matter. Another case is a secondary (induced) acceleration of time course in the nearest area of decelerated time matter.

Technical realization of aethero-induction method seems to be very close to idea, which is described in classical epic "Back to the Future". At first, it is necessary to create or to collect some chronal charge in a "flux condenser" and then to accelerate it in space up to some velocity. According to the aether conception, this creation of the chronal charge is a real technical process.

It is assumed that estimated chronal effects are demonstrated as some threshold field, i.e. space-time has some stable discrete energy levels and changes of its curvature should have discrete threshold mode. All new aspects disclosed in this paper are the subject of a patent process. Faraday Labs Ltd organizes experimental program on the topic. Practical application of this technology is new energy systems and propulsion methods.

References

1. Chernobrov V.A. Experiments with a man in the Time Machine, New Energy Technologies, #3 November-December 2001, p.6.
2. Kozyrev N.A. Selected works, Publ. by Leningrad State University, 1991.
3. Frolov A.V. Practical application of the Time Rate Control theory, New Energy Technologies, #3 November-December 2001, p. 15.
4. Mallett, R.L., Weak gravitational field of the electromagnetic radiation in a ring laser, Phys. Lett. A, 2000.

investigated completely yet. It was found also that harmful effect on biological systems is not related to the process of movement in Time itself but is a result of the difference of the Time rate value in various parts of a body (a biological system).

Inside of the laboratory setup it was also discovered that Time could be changed with some inertia. Areas of space having different Time rates have vague borders. With sufficient difference in Time rate the human can see an area with a different Time rate as some white mist. Higher the difference – the mist is denser, that can be used as an alarm signal for biological systems. It is possible to consider Time-travel as possible and (after experiments with mice) there are reasons to suppose it will be safe for travelers if they follow certain rules. It is especially necessary to emphasize: the trips through Time (due to new discovered properties of Time) can't affect the Past and they can't change our past history. All the so-called paradoxes for the traveler in Time (for example when "he meets himself in the Past" or "he kills his grandfather in his childhood" have clear solutions in 3-dimensional Time.

It is possible to consider as a proven fact that Time has more than one dimension, i.e. O. Bartini's theoretical calculations are confirmed by these experiments: Time has 3 dimensions. Hence our Earth world can be considered as a 6-dimensional object: length, width, height, age or date of Time, variant of a History or erosion of Time, density or rate of Time. The concept of "the Arrow of Time" as fourth dimension (moment of Time) is a particular case of the concept of sixth dimension (rate of Time) that leads to the physical concepts of gravitation and energy and they are simultaneously connected. Concepts of the " Einstein-Rosen bridges" known since 1916 or "worm-holes" introduced into science by John Willer in the 50's, are travels in 5th and 6th dimensions, i.e. the "classical" Time travels, which were described by H. Wells.



Editor's: As the reader could note, the author does not disclosure the secrets of the TM design. From the photo you can see the electromagnets, which form the regular stereometrical construction as well as the cables from the TM to the control unit. Dr. Chernobrov mentioned the converging electromagnetic waves only. So, to understand how it works, it is necessary to get a clear notion of the converging electromagnetic waves. Let's imagine the ripple effect created by a stone in the water. The waves move from a central point to periphery. The converging waves are just an opposite process: the waves move from periphery to the central point. Is it possible in Nature? Yes, sure. Dr. Chernobrov wrote: "Let's throw a hoop on the water and inside of the hoop we'll see converging waves." The Time Machine technology by Dr. Chernobrov is based on the similar principle.

Time Machine Project

Alexander V. Frolov

Scientific Expert of the Russian Physical Society,
General Director, Faraday Lab Ltd
Tel/fax: 7-812-380-6564 Tel: 7-921-993-2501
Email: director@faraday.ru alex@frolov.spb.ru

May 29, 2002

Faraday Labs Ltd and Dr. Vadim Chernobrov have signed the agreement on scientific-research work on investigation of active properties of time.

In the course of the previous experimental works, carried out by Dr. Chernobrov's research team during the period from 1984-2002, four versions of Time Machine had been made and tested. At these devices (the biggest system is about 1 meter in diameter) the effects of deceleration and acceleration of time course were created and measured. The principles of control of time course velocity were based on the interconnection of electromagnetic processes and physical properties of space-time. Special electromagnets, operating in pulse mode, are placed at the spherical frame. They create the so-called "converging wave", which by Alexander Frolov is a longitudinal wave in nature.

Alexander V. Frolov, General Director Faraday Labs Ltd and Ph. Dr. Vadim A. Chernobrov have just signed the Contract

Coupled with aetherodynamics time conception, which was suggested by Alexander V. Frolov, the works on the control of space-time parameters gain the possibility for development and commercial application. As a theoretical basis there are those N. Kozyrev works where his conception of "time density" are replaced by that of "aether density" according to Frolov.

In September 2002, Faraday Labs Ltd Company plans to complete testing of the first experimental system, and to start the patenting and research of applied aspects, first of all in medicine.

Physical Principles of the Time Machine

Alexander V. Frolov

Experimental success of research team headed by Dr. Vadim A. Chernobrov, Moscow was reported in [1]. The time course can be controlled as rate of any process in local space-time (inner space of the Time Machine). It can be decelerated or accelerated by means of special "converging electromagnetic waves". Ordinary waves move from the source whereas special "converging waves" move to some central point, i.e. into the focus of the system. In Chernobrov's design of the Time Machine this process is organized by means of several spherical envelops, which consist of several electromagnets. Electronic control unit controls the processes in this design. Dr. Chernobrov reported about 3% change of the time course in 4th version of the system, which was tested with a human inside. The goal of Dr. Chernobrov's work is to research the medical aspects and experimental investigation of the principles. Several important conclusions were obtained from the project: the time course can be controlled and character of the changes is different for acceleration and deceleration mode.

Other known publication and research projects on the same topic seem to be very far from any commercial and practically useful application. Obviously the topic is very new and fantastic for most of scientific community and at first we have to clarify the physical principles of the time control project, which is started by Faraday Labs Ltd.

In this project we believe that notion of time is one of possible description of real physical properties of our Universe. So, it is not mathematical abstraction but some aspect of physical reality and we can discover some physical properties of time. Russian astrophysicist N. A. Kozyrev [2] developed a theory of active properties of time and according to his point of view there are two properties: time course and time density. Prof. Kozyrev demonstrated experimentally that time density in area of some process (changes of matter) is dependent on entropy parameters of the processes. In [3] it was demonstrated that Kozyrev's experiments could be interpreted in aether theory and it has led to simple physical conclusions and clear experimental perspectives: **time course and its density can be explained and controlled as parameters of aether.** Directions of aether flow and density of aether are subjects of experimenting with non-reversible changes in matter, for example, in crystallization or melting processes. Also it is possible to use special electromagnetic processes, for example, Chernobrov's "converging waves" or other longitudinal waves as methods of aether compression or rarefaction. If we assume that process of existence of elements of matter physically can be explained as aether vortex processes then its rate is a parameter of **aether income/outcome balance** (aether inflow in element of matter and aether outflow from the element of matter). It was also described in Time Rate Control (TRC) theory [3]. To control this balance it is necessary to develop technology of longitudinal waves generation, its focusing and resonance effects. The previous research and experimenting on the topic has been made by N. Tesla.

Let's assume that we have some technology to change parameters of time course. How should we organize this local space-time (what is spatial topology of the design)? There is a very interesting experiment to get the answer: rotation of a heavy cone (for example, lead cone) entrains surrounding aether, so a vortex appears, which is a toroidal formation of aether (rings). The rings can exist in space for a long period. The further question is: Why does the beam of light (laser beam) directed to the cone by tangent create a luminous ring? We can assume that due to natural properties of photons (light propagates along the geodesic line in space) some autonomous closed toroidal space should be created in such experiment. The next thought is: since space and any matter exist in time then we can speak about some autonomous time. The general conclusion is to be the following: autonomous 4-dimensional space-time can be created as toroidal aether vortex.

Here is point to note some aspects of research project by Prof. Robert Mallett, Connecticut University, USA. In fact, sometime next year, he hopes to produce the first piece of technology that eventually will allow him to build a time machine. By Mallett it will be a device that employs lasers "to twist space". Why is he going to close the beam of light? His theoretical background is knowledge about black holes, i.e. understanding of the connection between gravity and curvature of space-time. In Einstein's theory both matter and energy can bend space and time. So Prof. Mallett assumes that curvature of space-time can be changed not only by mass (like a black hole) but it can be affected by energy of photons. This has led Prof. Mallett to consider the possibility of using a circulating beam of light to twist space and to create closed loops in time. It is predicted that a spinning neutral particle, when placed in the ring, is dragged around by the resulting gravitational field [4]. From the

Kozyrev-Dirak Radiation
Its influence on animals

Dr. Ivan M. Shakhparonov

International Academy of Energy-Informational Sciences

In the experiment with animals, that were made in the Center of Oncology Researches (COR) at the Russian Academy of Medical Sciences (RAMS), on the applying of Kozyrev-Dirak's Focused Radiation (KDFR), it has been found that KDFR decreases the quantity of glucose in the blood, reduces its tenacity, promotes the strengthening of immunity and the rise of the quantity of marrow cells.

Introduction

This time researchers in Russia and abroad experiment on ball lightnings by means of nonoriented circuits, which are similar to the electric analogues of Mobius band, also by means of Klein bottle and their combinations. Non-oriented fields are investigated very intensively now. Accordingly, organisms of the researchers, who observe the interactions of such fields with a matter, are also changed, thus they should take it into account on making such experiments. The aim of the article is to show in which way the fields of nonoriented circuits influence on animal and human organism. Besides the article has for its object the prevention of negative consequences, which can appear for experimenters through the research process.

Experiments with animals that were carried out in 1992-1993 in Russian Academy of Medical Sciences (RAMS) had not been published in proper time because there were no quantitative methods of radiation detection. Later, in 1996 they were developed [1] and KDFR parameters were measured in that geometry, which were applied in RAMS. In 1998 powerful and super-powerful KDRF sources were obtained. These sources were applied (and are applied now) in the researches at the controlled radioactive decay [2]. Kozyrev and Nasonov [3] and later also Lavrentyev with the collaborators [4,5] have proved experimentally that the Sun and some stars generate the radiation, which has early unknown properties. We suggest that the radiation, discovered by Kozyrev [3], and the radiation, which is researched by us and by other experimenters with nonoriented circuits, are of the same phenomenon. At first, it should be noted that on interaction between Kozyrev-Dirak radiation (KDR) and a matter made it colder. As it was demonstrated above [1], cooling effect can be explained by matter re-magnetization under the influence of KDFR beam (adiabatic demagnetization). According to the still unpublished data, KDFR bunch destroys matter lattice by the way of it's moving. However, after a couple of week matter reconstructs it to the almost tabulated points, without defects, blockness and other damages, which are peculiar to other natural crystal structures. **In the definite sense nature demonstrates the way to rejuvenate compound structures**. As it is well known, vital functions of biological systems on the Earth depend on the structure and composition of water. Therefore, we have a right to expect considerable changes in the vital functions of biological organisms under the influence of KDFR.

Experimental Devices

In experiments with animals there were applied the devices, which concentrated KDR (KDCR) and had 50 Wtt aggregate electrical power. The description is presented in [2].

KDFR indication was obtained by calorimetric method [1], along the way of movement of the main bunch (with 10 cm across diameter) and at angle of 45° from the geometrical axis of a device.

Researches of Bleeding Duration

Let us consider KDFR influence on the blood composition of animals. At the experiment 24-28 gram weighting, pelletized fed male mice were used. In the process of the experiment it was discovered that 3 and 4 hour processing of mice with KDFR at the distance 2.5 m and at the presence of animals in the sphere of maximum radiating power, caused some changes of fibrillation system. The bleeding duration was determined according to Duke method. Two groups of animals were used at the experiments: a group with 4-hour duration of KDRF processing and a group with 6-hour duration. Time of bleeding was considered in dynamics at 1, 2, 7, 14, 21, 28 and 35 day (Fig. 1). The bleeding duration of the intact animals was determined by the value 128±11 sec. After the applying of KDFR there was noticed some increase of bleeding duration to 261±15 sec and 223±21 sec on the first day after the stopping of the influence. In the subsequent periods bleeding duration gradually decreases up to the level of physiological norm. The whole normalization of the index is observed at the animals, which were processed by KDFR during 4 and 6 hours, on 28-35 day up to 115±12 and 133±18 sec correspondingly. In the process of observations at the animals, the correlation between time of fibrillation and periods of KDRF processing of the animals has not been revealed (Fig. 1).



Fig.1

In the course of the experiment the strongly marked chronometric hypocoagulation was discovered due to the extension of the parameter "K" or, probably, because of the change of aggregation properties of platelets (Table 1).

For the determination of biochemical indexes serum was obtained from 5-8 ml of rats' venous blood. Beforehand (24 hours before the slaughter), forage was taken away from the animals. The determination of biochemical indexes was provided by means of biochemical analyzer HITACHI. As a result of the experiment it was determined that at the first day after influence of KDRF there was a tendency of decrease of the glucose content (Table 2). Other indexes varied in the limit of physiological norm.

Table 1 Parameters of thromboflexogramm after KDFR, 4 hours

Animal #	Parameters of thromboflexogramm			Fibrio gene	Fibrinal activity
	R (sec)	K (sec)	Ma (mm)		
1	72	∞	10	-	-
2	102	∞	18	-	-
1	90	∞	10	275	75
2	180	150	52	315	90
1	180	∞	5	-	100

Table 2 KDFR influence on the glucose content in blood of the rats

Time (days) after the experiment	KDFR 4 hours (mmole/l)	Test (mmole/l)	KDFR 6 hours (mmole/l)	Test (mmole/l)
1	3.14	6.12	6.39	7.27
10	7.59	9.35	8.90	6.69
30	6.05	6.69		

Research of haemopoiesis system

Several criteria were considered: the dependence of biological effect on the distance, on the power flux density, on the duration of processing. Besides, KDRF influence on mice survival was considered.

At the experiment 24-28 gram weighting, pelletized fed male mice were used. The marrow was examined in the dynamic at 1, 3 and 7 day after KDFR influence. Six animals were taken on each point. After the decapitation of the mouse their thighbones were taken out and after that the absolute number of myelokaryocytes was calculated by the standard method in Goryaev chamber.

Dependence of the biological effect on the distance

In all experiments the maximum flux density along the geometrical axis of KDCR device was a constant. There were used four temporal modes of the influence (1, 2, 3, 4 hours) and three points of long distance between KDSR and the biological object (0.5; 1.5; and 2.5 m). At 0.5 m distance there were no differences in the number of marrow cells in comparison with the control cells. With the increase of distance between KDCR and the object from 0.5 to 1.5 m some tendency to the increase of the number of marrow cells up to the 7th day was observed. Four-hour KDRF processing caused the increase of the number of karyocytes up to $29.99 \pm 1.25 \times 10^6$ ($P<0{,}001$). Thus, any dependence of the biological effect on the exposition has not been revealed. For instance, at the 7th day after one hour of the exposition the number of karyocytes was equal to $28.45 \pm 1.87 \times 10^6$ at the same time after 3-hour processing it came to $27.65 \pm 0.74 \times 10^6$. Alongside with the change of the distance to the biological object from 1.5 to 2.5 m the tendency towards the increase of the number of marrow cells has kept within the same limits $28.27 \pm 1.32 \times 10^6$ and $29.57 \pm 0.88 \times 10^6$.

Dependence of the biological effect on the power flux density

The comparative investigation of KDFR influence on the biological object in the coverage of KDCR (along its geometric axis) and outside the coverage has demonstrated that alongside with the increase of the radiation intensity there was a tendency towards the decrease of stimulative influence of KDFR on haemopoiesis.

Dependence of the biological effect on the duration of processing

On processing the animals at distances up to 2.5 m from KDCR and on increase of exposition to 3-4 hours it is possible to obtain reliably significant difference in the number of marrow cells from the physiological norm to the 7th day.

KDRF influence on the survival of mice

The experiments, determining the survival reaction of animals, were made by means of gamma radiation. 30-day survival is the criterion of determination. Conditions for the experiments are the following: in the coverage of KDCR and aside the coverage, (the distance between the KDCR and the object is 2.5 m in the coverage of KDCR and 0.5m outside the coverage). Time of influence is 4 hours. Animals of both sex were used. Two groups of animals were used. The test group was put to the gamma radiation in the diapason of doses, which caused marrowy syndrome, i.e. from 7.5 to 8.5 Gr. The second group of animals after the irradiation in the same diapason of doses was repeatedly processed with KDFR. Time of the influence is 4 hours at 7.5 Gr gamma radiation on 15 mice in one bath and 8.5 Gr on 15 mice in another bath. Total gamma radiation of the animals was made by means of the source ^{137}Cs with the dosage rate of 5.2 Gr/min. Gamma radiation in this dose diapason causes death of the animals during the development of the marrowy syndrome, i.e. from the 6th to the 20th day along with the aplasia of haematogenic tissue. Combination of gamma radiation and KDFR sometimes leads to the slight increase of the number of survived animals. If the animals are irradiated by gamma rays at first and then by KDFR, the death control at 7.5 Gr radiation is equal to 5.5% from the total number of the animals and at the following KDFR processing 16% of the irradiated animals die. However, 67% of the animals in the tested group have died after KDFR processing and after the coming next gamma radiation with 8.5 Gr total dose. And in the group, which was processed with KDFR, only 46% of the animals died.

Immunity strengthening

For the investigation of KDFR influence the following tests were chosen: activity of natural killers and T-killers, which had been obtained by the immunization in vitro in the unidirectional mixed culture of lymphocytes and also in the reaction of blast transformation on the specific mitogen [6, 7]. All tests were made on the 7th day after a single KDFR influence. Unfortunately, data have been obtained with the applying of radioisotope preparations. Though the experiments of this kind were successful and though they have demonstrated the increase of some immune reactions' level, there is a certain doubt in the relevancy of radioisotopes application [2]. Thus the series of experiments was made. These experiments were aimed at the investigation of KDFR influence on the development of the swelling process. The aim of the experiment is the investigation of KDFR influence on the development of Ehrlich cancer and sarcoma-37, which were repeatedly inoculated to mice. At the first stage of the experiment there was a single KDFR influence on the mice repeatedly inoculated with sarcoma-37, on the 2nd day after the repeated inoculation of the swelling cells to the animals. The repeated inoculation was made intramuscularly in a right thigh, in a dose 10^6 of cells per a mouse. Time of KDFR influence for the first group of animals was equal to 1 hour; for the second one it came to 2 hours; and for the third one it came to 4 hours. Each group consisted of 6 animals. The test group consisted of six mice with repeatedly inoculated sarcoma-37 and which had not been processed with KDFR. As a result, the average lifetime of tested animals was equal to 9 days. The average lifetime of animals of KDFR groups came to 48 days (for 1-hour KDFR influenced group); to 12 days (for 2-hour group); and to 31 days (for 4-hour group). Thus, the average lifetime of the experimental group came to 29 days. Besides, in the group, which has been processing with KDFR during 1 hour, **the half of mice had survived (three of six mice).**

At the second stage of the experiment the repeated (5 times during 2 hours) KDFR influence on the mice was applied. These mice have been inoculated with sarcoma-37 at seven days before the beginning of the influence. As a result, the average lifetime of the animals was equal to 27 days, and for the mice, which were processed with fivefold KDFR influence, the average lifetime was equal to 76 days. The obtained results are the evidence of inhibition of swelling development for the animals, which were processed with KDFR influence. This leads to the increase of lifetime of such animals in comparison with the test. **Thereby, at a great extent the results of the previous experiments on the strengthening of immune status after KDFR influence were confirmed.**

Results and discussion

Let us make a conclusion. At the KDFR influence on animals' organism the following effects were observed: decrease of blood viscosity; strongly pronounced hypocoagulation; decrease of contents of glucose. Increase in the number of karyocytes and the extended lifetime of the animals, infected with Ehrlich cancer and sarcoma-37 were also observed.

As for human being, the researches in this area have not been carried out yet and they are still confined to the single observations. It is possible to give an example from the author's practice. In 1975 nonoriented circuit of 3kWtt power was examined. Field strength was measured. The author of the article had been working in the field for about 8 hours. And after five hours after the experiment I had felt bad. That time it was nothing known about the influence of the new radiation on human organism. The arrived ambulance has quickly diagnosed that I was close to hypoglycemic coma. On several hours after the intravenous glucose injection, my state has become normal. **Now we know that before the experiments with powerful KDFR bunches it is necessary to eat sugar.** Thus we believe that the data, which were obtained after the experiments with animals, can be applied to a human being. We can suggest that the manifestation of the symptoms of the KDFR influence on human organism depends on the power of the applied source, on the total mass of the organism and on the time of it in the coverage of the irradiation. From aforesaid it is clear that the experiment with powerful KDFR sources is far from being harmless and it is better to make it distantly after exclusion of man presence near experimental stands and devices. At the same time it is quite obvious that on applying of small capacity and fixed time of irradiation it is possible to develop methods for curing of human diseases, which are considered now as incurable (for instance of diabetes, some diseases of haematogenic system, of cancer and possibly of AIDS.

References

1. Proceeding of the International Scientific Conference "New Ideas in Natural Sciences" Problems of Modern Physics, p. 176-187
2. Journal of new energy, Vol. 3, #4,1999, I.M. Shakhparonov "Interaction between Kozyrev – Dirak radiation and radionuclides", p. 85-89
3. Kozyrev N.A. Selected works, Leningrad State University, 1991, part 3
4. Lavrentyev M.M. Eganova I.A. Luzet M.L., Fominykh S.F./ / Reports by AS USSR. – 1990, Vol. 314, #2, p. 352-355
5. Lavrentyev M.M., Gusev V.A., Eganova I.A., Luzet M.L., Fominykh S.F.// Reports by AS USSR. – 1990, Vol. 315, #2, p. 368-370
6. Methodological materials on experimental pharmacological and clinical trials of immune modulating effect of pharmacological remedies. - Ministry of Health USSR, M., 1984
7. Talmadge J.E. and Chiragos M.A. Comparison of immunomodulatory and immunotherapeutic properties of biologic response modifiers. Springer Seminar Immunopathol., 1985, 8, 429-443

Effect of Magnetic Blow Wave Field on Wine Systems

I.M.Shakhparonov (Corresponding author), S.A.Grin,
S.R.Tsimbalaev, L.N.Kreindel, V.N.Kocheshkova,
A.I.Podlesny, S.Yu.Gelfand

AGD Firm, Peschanyi pereulok, House No.20P korpus No.1, Lfl. 33
125252, Moscow, A- 252, Russian Federation

Russian Institute of Canning Industry, Shkolnaya Street. 78.
142703 Vidnoe 3. Moscow Region, Russian Federation

Introduction

Authors communicate the data on influence of Magnetic Blow Wave (MBW) field on several wineproducts. It was found, that MBW did not lead to significant changes in the major components of the wineproduct (sugar, organic acids, minerals). At the same time the taste and aroma of treated wine become more pleasant; content of heavy alcohols and wine stone in the treated samples was less than in non treated ones. A mechanism of transformations was also discussed.

Keywords: *Magnetic Blow Wave (MBW), Wineproduct, GLC of aroma compounds and ethanol, HPLC of sugars, Atomic Absorption Spectrometry (AAS) of minerals, Heavy alcohols and aldehydes, Wine stone, Turbidity tendency, Organoleptic evaluation*

Magnetic Blow Wave (MBW) was obtained for the first time during the investigations on ball lighting generation under the laboratory conditions (Shakhparonov 1994). MBW as a physical object is interesting because of some facts, which suggest that MBW is a magnetic monopole. The MBW can also interact with the matter and transforms it in a definite way. Typical example is an elementary carbon in the form of graphite, which is transformed by such magnetic treatment into ferromagnetic substance (ibid). The graphite, which is initially diamagnetic, transforms to paramagnetic one with general radiation doze of about $7 \cdot 10^{19}$ neutrons/cm^2. Other types of radiations could not affect this way (Svoistva 1975). So one unit of MBW can be considered as $1 \cdot 10^5$ of neutron masses. This fact may be regarded as an indirect evidence for assuming that MBW and magnetic monopole are the same things. In the absence of excited radioactivity a slow MBW [$v/c < 1 \cdot 10^4$] occurs, which does not ionize atoms (Devons, 1963). Therefore, their interaction with the matter can be observed only indirectly. No data exist on the interaction of MBW with organic substances. The experiments and results reported in the present communication may be a starting point for development of technology and to formulate the methods for vintage wine and best quality spirit production.

Materials and Methods

Assuming that MBW and magnetic monopole are the same things, a number of conditions were selected for all experiments. The MBW source and the samples were placed in the same axis and the axis was oriented according to magnetic meridian direction. Such magnetic orientation is appropriate, as the energy of magnetic monopole theoretically increases in a magnetic field (Devons, 1963). All of samples were placed at 250 cm distance from MBW source, in hermetically closed glasses. It should be noticed that MBW could penetrate through many other barriers, for example into cast iron reservoir with wall thickness of 5 cm (Amaldi, 1970).

The quality investigations were made by using of standard equipment. HPLC, equipped with refractometric detector was used for sugars estimation. Separation of organic acids in forms of their ethyl esters and acid esters was carried out chromatographically using a column packed with polyethylenglycol succinate and the following temperature option: initial temperature is 120°C, final temperature is 220°C, temperature growth rate: 8°/min. GLC was also employed for determination of ethanol. Minerals content conclusion: in order to obtain complete information about any system, it should be destroyed. However, destruction of tissues of the man in order to get information about their state is a too high price to pay for the information about his health.

However, the above Van Hoven's criterion can be satisfied with the minimum influence, when the cells are not destroyed and the atoms of these cells, being primary sources of torsion spectrums to be registered, are bring into the non-equilibrium state by means of outer disturbing influence.

In order to choose the frequency of the disturbing torsion influence correctly, it is necessary to take into account the role of water in physical and biochemical organization of tissues of the human organism.

At the same time, it is necessary to take into account the resonance torsion frequencies of various human organs. Finally, it turns out that the signal of torsion disturbance should be rather sophisticated considering both these factors. The TORDI system is a ready-to-use production device. Nevertheless, it is important to understand that the model is not the limit of scientific and technical potential incorporated in it and that enhanced variants of the system will appear with the course of time.

Summing up, I would like to draw your attention once more to the fact that work on torsion technologies is not limited by the directions that were discussed here. Actually, as it was pointed out in the beginning, on-going development includes all branches of economy, industry, agriculture and medicine, as well as all problems of everyday life. Technologies that we mentioned are the forerunner of the fact that the mankind is on the threshold of the age of torsion technologies, which, we believe, will change our life in the 21st century more than all the scientific and technical revolutions of the 20th century.

Reference

1. Cartan E. Compates Rendus. Akad.Sci., Paris, 1922, v.174.
2. V.Melnikov, P.Pronin. Problem of gravitation constant stability and additional interactions. Itogi Nauki I Tekniki, ser. Astronomy, v.41, Gravitation and Astronomy, Moscow, VINTI, 1991.
3. G.I.Shipov Theory of the Physical Vacuum. Nauka, Moscow 1997.
4. I.Ternov, V.Bordovitsin. On the modern interpretation of classical spin theory of Ya.Frenkel. UFN, 1980, v.132, No.2.
5. V.Bagrov, V.Bordovitsin. Classical spin theory. Izvestiya VUZ, Phys.Series, 1980, No.2.
6. F.I.Belinfante. On the spin augular momentum of mesons. Physica VI, 1939, v-6, No.9.
7. M.Markov. The very early universe. Proc of the Nuttfield Workshop, Eds. G.V.Gibbson, S.W.Hawking, S.T.Siklov, Cambridge, 1988.
8. Hideo Uchida.A method apparatus for detecting a fluid. Patent England, No 511662, May 24, 1978.
9. Anatoly Akimov. Heuristic discussion of the problem of finding long-range interactions. EGS-concepts. CISE VENT, preprint N7A, Moscow, 1992.
10. IITAP RANS, TORTECH USA, Horizonts of the Science and Technology XXI age Proc, Editor A.E.Akimov, Folium, Moscow, 2000, vol.1 (in Russian).
11. N.Kozyrev, Astronomical observations by means of the physical properties of time. In "Flarestarse" International Symposium in Byurakan, 1976,Armenian Academy of Sciences Publ., Yerevan, 1977 (in Russian)
12. Bouwmecster D. et.al. Nature, v.390, 11 dec, 1997.
13. G.I.Shipov. Theoretical and Experimental Research of Inertial Mass of Four-Dimensional Gyroscope. ITTAP RANS, preprint N10, Moscow, 2001, (in Russia).
14. The way of correction of metal alloy microstructure. Patent Russian, RU 2107105, 1998.
15. A.Dolgov, Yu.Zel'dovich, M.Sazshin. Cosmology of the Early Universe. MGU Publ., Moscow, 1988.
16. I.A.Wheeler. Einstein's vision. Springer Verlag, 1968.
17. Convegno Internazionale:Quale Fisica per 2000, Proc. Bologna, 1991. see: The Manual of Energy Devices and Systems.
Complied D.A.Kelly, D.A.K. WLFUB, Burband, California, 1986, Publ. N1269/F-289.
18. Daytlov V.L. Polarization Model of the Heterogeneous Physic Vacuum. Institute Mathematical, Sibirians Academic Science, 1998 (in Russian).

The Electrical Vortex Non-Solenoidal Fields

Sergey B. Alemanov
E-mail: alemanov@inbox.ru Phone 7 (095) 323-6848

A mistake was found in the electrodynamics: it is detected that all electrodynamics' postulates corresponds to the experimental facts, but vortex electric fields has unclosed inductive lines.

When the magnet is moving, then the current of magnetic induction is moving together with it. From known velocity of motion $\mathbf{v}$ and the value of magnetic induction $\mathbf{B}$, it is possible to calculate the intensity $\mathbf{E}$ of appearing vortex field according to electrodynamics formula of transformation of fields $\mathbf{E=vB}$.

If to change the $E=vB$ on induction $D=\varepsilon_0 E$ in formula of fields' transformation, that will get $D=\varepsilon_0 Bv$, where D is electric induction, B is magnetic induction, v is velocity of motion, ε_0 is electric constant.

Herewith the appearing electric induction is always transverse to the direction of motion. It is possible to formulate the rule of origin for electric induction under the condition of rectilinear motion: if to dispose the right hand palm so four fingers shows the motion direction of the magnetic flow (the field), connected with moving magnet, and the vector B fells into palm, then the moved aside big finger will indicate the direction of vector D. The given rule is like the rule for Lorenz' force, but on the contrary (the difference is in frame). In the first case the charge moves, but the magnet rests. Here the magnet moves, but the charge, which points the direction for lines of force of electric induction, is immovable. So, there it is the rule for left hand, but here, on the contrary, it is the rule for right hand. Thereby, if the charge moves, but the magnet is immovable, then the rule of left hand uses for determination of the force. But if the magnet moves, but the charge rests, then the rule of right hand uses for determination of the force.

The origin of electric force is connected with that, the vortex electric field $D=\varepsilon_0 Bv$ appears around moving magnet (the magnetic field does not act on immovable charges).

In common literature on electrodynamics there is no any difference between electric vortex field and solenoidal field, but these are different notions. The sign of solenoidal field is the closed lines of electric induction (the flow of vector D through the closed surface is a zero), but for the vortex field the sign is following: the work of forces can be different from zero under the condition of motion along a closed line. That is to say, the vortex fields can agitate the rotational currents.

From the electrodynamics textbook: "The work of forces of vortex electric field can be different from zero, when the electric charge is moving along a closed line."

For instance, when the magnet moves, the vortex electric field appears and this field can be solenoidal or not, depending on magnet's orientation. Let's take such example: the magnet moves evenly, rectilinearly, and it's poles are oriented transversely to direction of motion. According to the rule of origin for electric induction ($D=\varepsilon_0 Bv$ that is the rule of right hand), the appearing vortex electric flow is not a solenoidal, since the lines of electric induction are not closed. Its begins in one conditional area of disturbance (+), accompanies the moving magnet, and it finish in another area of disturbance (-). For presentation it is enough to consider only two areas (+) and (-), represented on Fig.1. These dissimilar areas of disturbance appears because that flow of magnetic induction inside the magnet has the inverse direction, that outside the magnet.



Fig.1



Fig.2

That moving disturbance of electric and magnetic fields presents itself as transverse electromagnetic disturbance. Also, it is necessary to notice, that under such magnet's motion, the appearing vortex electric field is not closed, but the current of electric displacement, connected with it, is closed (a currents are always closed). In given example, for clarity, it is possible to present a intensity of electric field through the Lorenz' force, if to take the frame, in which the magnet rests, and the test charge moves.

On the Fig.1 the moving magnet is conditionally represented (motion is toward to the text, magnet is moving away). N and S are poles of magnet. The direction of lines of electric induction, appearing when the magnet is moving, specified by arrows → and ←. Part of the lines begins in positive area (+) and finishes in negative area (-), the areas are placed on the ends of magnet. **The flow of electric induction through closed surface is not a zero; that is to say, these areas of disturbance are moving electric charges.**

From the electrodynamics textbook again: "The flow of vector D through any closed surface is equal to algebraic amount of external charges, covered by this surface. In the electrodynamics these postulates has the same role, as Newton' laws in classical mechanics."

Thereby, according to postulate, it is necessary to consider the appearing dissimilar areas of disturbance (+) and (-) to electric charges, or it is necessary to change the postulate.

It is interesting, that a part of lines of electric induction, which placed frontal and behind magnet, starts and finish at infinity, since the distribution of magnetic induction around magnet has not determined borders.

For clarity, it is possible to make following calculation. For instance, the coil (loop or turn) with current, as a magnet, moves evenly and rectilinearly, but its magnetic poles are oriented transversely on motion direction. Under such motion the lines of electric induction are not closed, and the dissimilar areas of electric field's disturbance appears in space on the edges of this coil.

On Fig.2 the moving coil with current is conditionally represented. It moves from left to right side of the page. The arrows on the coil indicate the direction of current. The appearing dissimilar areas of disturbance of electric field are marked by signs (+) and (-). Knowing, that in medium of the coil $B=\mu_0 I/2r$ and according to $D=\varepsilon_0 Bv$, it is possible to find the electric induction, appearing in the center, between two dissimilar areas $D=\varepsilon_0\mu_0 Iv/2r$, where I is current in the coil, r is radius of the coil, v is velocity of motion, ε_0 is electric constant, μ_0 is magnetic constant. The electromagnetic disturbances in transverse electromagnetic waves has the similar field construction, there also dissimilar areas of disturbance of electric field exists, that is to say the lines of electric inductance are not closed. Only the currents of electric displacement and magnetic induction are closed.

Let's consider another example: magnet moves rectilinearly, but its poles are oriented longitudinally to direction of motion. According to the rule for origin of electric induction ($D=\varepsilon_0 Bv$ is the rule of right hand), the appearing rotational electric flow is solenoidal, since in this case the inductive lines become closed lines. **Usually in books on the electrodynamics such moving magnet is considered, and the wrong conclusion is thereof done, that vortex electric field is always**

solenoidal, herewith it is forgotten, that poles of the magnet can be oriented not only along the direction of motion, but across also.

From the electrodynamics textbook: "The vortex electric field differs from electrostatic field that it is not related with any electric charges and its lines of intensity are closed lines."

From theory and from experiments it follows, that under transverse motion of magnet the lines of disturbance of vortex electric field can be unclosed and, accordingly, the flow of induction through the closed surface is not a zero. Then there is a direct discrepancy to facts in modern electrodynamics. It is strange, but for the whole history of researches in magnetism the transverse magnet's motion was not is considered. It leads to revising of electrodynamics' postulates, which plays such role in electrodynamics, as the Newton's laws plays in classical mechanics. The postulates, giving invalid belief about field processes, accordingly, do not allow to make some correct calculations. Fallaciousness of these postulates was one of the reasons, on which the electrodynamics could not to consider and to calculate the discrete electromagnetic waves (photons), where the magnetic field also is the transverse field (the field construction and calculation of photons are represented on the page http://www.comail.ru/~alemanov). **That is to say, not only particles has the charges, but areas of disturbance of field (without particles) are the charges also,** where the flow of electric induction through the closed surface is not a zero. Thereby, the vortex electric fields can be not only as closed flows of induction, but as well as inducted electric charges, accordingly, the laws for electric charges are valid for induced electric charges also. For instance, in the law of conservation of charge: if somewhere the area of disturbance with positive sign appears, that negative area appears also.

From the electrodynamics textbook: "The vortex electric field is generated by the variable magnetic field. Its force lines are always closed, like force lines of magnetic field."

But before this fundamental postulate, confirming, that force lines of vortex electric field are always closed, it was necessary to consider all variants of change for the magnetic field, including the variant of the transverse motion of the magnet. That is to say, the consideration of physical processes could not be unilateral. Faraday considered the longitudal motion of magnet and discovered the electromagnetic induction, but the transverse motion of magnet that have the principle importance for understanding of field processes in electrodynamics was not considered. Thereby, the longitudal motion of magnet brings to arising a vortex electric field with closed force lines, but transverse motion of magnet brings to arising a vortex electric field, where the lines of forces are not closed. In this case it lead to induced electric charges. It is necessary to notice, that this is first mistake, detected in electrodynamics postulates for all time of existence of electrodynamics.

From the electrodynamics textbooks: "...Gauss' theorem is valid not only for electrostatics, but also for electrodynamics, which using a variable in time electromagnetic fields. We are not sure if this hypothesis is valid or it is not valid... Only the experiment can give the answer on this question. The whole collection of experimental facts speaks in favor of this hypothesis." But, unfortunately, the experiment with transverse motion of magnet was not considered seriously in this textbook.

(Editor's note: Well-known Searl's experiments and Godin & Roshchin's experiments are based on such transverse motion of magnets (rollers). In Alemanov's article it was demonstrated that in this case the experiment should lead to induced electric charges. Really it was detected in experiments. Hence this missed aspect of electrodynamics is very important for development of the new energy technologies.)

Gravito-Inert Mass

J.A. Asanbaeva

720000, Kyrgyzstan, Bishkek, Kadyrov's Scientific Center
+996 (312) 47-25-40, +996 (312) 65-02-83
bondarenko@nazaraliev-centre.com

Nature of mass is one of the important problems of modern physics. It is accepted to consider that the mass of elementary particle is determined by fields, which are connected with it (electromagnetic, nuclear and others). However, we didn't create any quantitative theory of mass. There is no theory to explain why masses of elementary particles form a discrete spectrum of values and to allow determining this spectrum.

Mass (m) is a physical value, one of characteristics of matter, which defines its inert and gravitational properties. Accordingly, we distinguish inert mass (m_i) and gravitational mass (m_g).

Inert mass (m_i) characterizes dynamical properties of a body, its property to accelerate under the action of the force $(\vec{F}_i)$ and according to the second Newton's law is considered to be constant coefficient of proportionality for the given body between $\vec{F}$ and acceleration $\vec{a}$.

$$\vec{F}_i = m_i\vec{a} \qquad (1)$$

Gravitational mass (m_g) is a source of gravity field. Every body creates its gravity field, which is

18. Kozyrev N.A. *Selected Transactions* (Leningrad University Press, Leningrad, 1991) (in Russ.).

19. Lavrent'ev M.M., Eganova I.A., Medvedev V.G., Olejnik V.K., and Fominykh S.F. *On Scanning of Celestial Sphere by Kozyrev's Sensor.* Doklady AN SSSR, 323 (4), p.649-652 (1992) (in Russ.).

20. Akimov A.E., Kovaltchuk G.U., Medvedev B.P., Oleinik V.K., Pugatch A.F. *Preliminary Results of Astronomic Observations of the Sky by the Kozyrev Procedure.* Academy of Sciences of Ukraine, Central Astronomic Observatory. Preprint CAO-92-5P, 1992, p.16 (in Russ.).

21. *Oleinik V.P. Superluminal Transfer of Information in Electrodynamics.* SPIE Material Science and Material Properties for Infrared Optoelectronics. 3890 p. 321-328 (1998) (http://www.spie.org /).

22. Oleinik V.P. *Faster-than-Light Transfer of a Signal in Electrodynamics.* Instantaneous Action-at-a-Distance in Modern Physics (Nova Science Publishers, Inc., New York, 1999), p.261-281.

23. Eganova I.A. *The World of Events Reality: Instantaneous Action as a Connection of Events through Time.* Instantaneous Action-at-a-Distance in Modern Physics (Nova Science Publishers, Inc., New York, 1999).

24. Lavrent'ev M.M. and Eganova I.A. *Physical Phenomena Predicted and Revealed by N.A.Kozyrev, in the Light of Adequacy of Space-Time to Physical Reality.* Philosophy of Science, 1(3), p.34-43 (1997) (in Russ.).

25. Logunov A.A. *Lectures in the Theory of Relativity and Gravity.* A Present-Day Analysis of the Problem. (Nauka, Moscow, 1987) (in Russ.).

26. Oleinik V.P. *The Newest Development of Quantum Electrodynamics: Self-Organizing Electron, Superluminal Signals, Dynamical Inhomogeneity of Time.* Physical Vacuum and Nature. 4 p.3-17 (2000) (in Russ.).

27. Jefimenko O.D. *Electromagnetic Retardation and Theory of Relativity* (Electret Scientific Company, Star City, 1997).

28. Oleinik V.P., Borimsky Ju.C., Arepjev Ju.D. *Time, What is this? Dynamical Properties of Time.* Physical Vacuum and Nature. 5 p.65-82 (2001); *New Ideas in Electrodynamics: Physical Properties of Time.* Semiconductor Physics, Quantum Electronics and Optoelectronics. 3 N4 p.558-565 (2000). E-print: quant-ph/0010027.

29. Borimsky Ju.C., Oleinik V.P. *The Course of Time in Classical and Quantum Systems and Dynamical Principle.* Physical Vacuum and Nature. 6 (2001) (in print).

The Principle of Self-Organization, which can be formulated as follows: any material object represents an open self-organizing system whose internal structures are formed with the participation of the whole universe. Apparently, the Principle of Self-Organization, incorporated in nature as one of the integral properties of matter, is nothing more nor less than a spirit (or absolute idea, or creator) which operates the world and creates all its variety.

Physical Mechanism of Nuclear Reactions at Low Energies

V.P. Oleinik* and Yu.D. Arepjev

Tell me what the electron is,
and I shall explain to you everything else.
W. Thomson

Abstract

The physical mechanism of nuclear reactions at low energies caused by spatial extension of electron is considered. Nuclear reactions of this type represent intra-electronic processes, more precisely, the processes occurring inside the area of basic localization of electron. Distinctive characteristics of these processes are defined by interaction of the own field produced by electrically charged matter of electron with free nuclei. Heavy nucleus, appearing inside the area of basic localization of electron, is inevitably deformed because of interaction of protons with the adjoining layers of electronic cloud, which may cause nuclear fission. If two or more light nuclei occur "inside" electron, an attractive force will appear between the nuclei that may result in the fusion of nuclei. The intra-electronic mechanism of nuclear reactions is of a universal character. For its realization it is necessary to have merely a sufficiently intensive stream of free electrons, i.e. heavy electric current, and as long as sufficiently a great number of free nuclei. This mechanism may operate only at small energies of translational motion of the centers of mass of nuclei and electron. Because of the existence of simple mechanism of nuclear reactions at low energies, nuclear reactor turns out to be an atomic delayed-action bomb, which may blow up by virtue of casual reasons, as it has taken place, apparently, in Chernobyl. **The use of cold nuclear reactions for production of energy will provide mankind with cheap, practically inexhaustible, and non-polluting energy sources.**

Introduction

Nuclear reactions at low energies, occurring in physical and biological systems, and, in particular, the cold fusion (CF) of nuclei, attract ever increasing attention (see review articles [1,2]). This is explained by the fact that research on CF (in what follows, by cold fusion we shall understand any nuclear reactions at low energies) opens up the way to the solution of the problem which was set more than 50 years ago in the field of controlled thermonuclear reactions (CTR) and which has not been solved that is the problem to provide mankind with cheap fuel. An important point is that CF allows to create not only cheap, but also non-polluting energy sources, as nuclear reactions at low energies are not accompanied by radiations dangerous to health (γ-radiations, streams of fast neutrons and other particles). Note that the energetic problem facing mankind is presently of special interest in connection with the fact that, according to expert evaluations, the oil-and-gas resources in the world will suffice only for some decades. For this reason the study of CF is among the most important problems of physics.

It is necessary to note that, relying on the standard theory of nuclear reactions describing nuclear processes in vacuum, experts in the field of nuclear physics, engaged in CTR, reject the very possibility of existence of nuclear fusion at low energies. Two basic objections are raised against CF:

1. at low energies the penetrability of Coulomb barrier around nuclei is so small that the probability of nuclear fusion is practically equal to zero;
2. distinction between the atomic and nuclear energy scales is so great that the energy, which might be evolved as a result of nuclear fusion, could not be transferred directly to atomic lattice; therefore the energy above should be emitted in the form of streams of γ-quanta, fast neutrons and other particles. However, such streams of sufficient intensity have not been registered.

The answer to the first objection against existence of CF is that at the heart of CF are nuclear processes occurring in environment, and the basic role is played here, apparently, by collective effects caused by interaction of nuclei with particles of environment in which the nuclear reaction takes place. The laws governing the behavior of interacting nuclei in vacuum are inapplicable to the description of CF of nuclei [3]. Nuclear reactions occurring at low energies submit to completely different laws, which can be established only provided that collective effects mentioned above are taken into account. For this reason the standard theory of nuclear reactions in vacuum can by no means refute the existence of CF.

As to the impossibility of transferring the energy between levels of various scales, we can give an example of the phenomenon of sonoluminescence (luminescence of a liquid when a sound wave causing cavitation passes through it) [4], in which the energy transfer from an acoustic wave to electromagnetic field occurs with appreciable probability in spite of the fact that the distinction between energies of acoustic phonons and quanta of light reaches 11 orders.

As early as 10 years ago J. Schwinger, the Nobel winner and the known expert in the field of the theory of elementary particles and quantum electrodynamics, asserted that it is impossible to deny the reality of CF phenomenon [3,4]. Since then the CF phenomenon for nuclei was repeated hundreds times in laboratories all over the world, tens of patents on the ways of energy generation on the basis of CF were registered and enormous number of experimental works were published, which not only confirmed the existence of effect, but also contained its detailed analysis.

The most convincing evidence for the existence of nuclear reactions at low energies seems to give the mass-spectrometric research of reaction products [5] as well as research on biological systems [6]. Detailed study of electric explosion of foil made of especially pure materials in water, described in [5], suggests that at electric discharges transformation of chemical elements occurs. Study of optical spectrum of plasma arising at discharge and of the mass-spectrometric analysis of sediments, which remained after the discharge, shows that in plasma there is an appearance of a significant number of chemical elements which were not presented in the initial material of explosive foil and electrodes and also that the isotope structure of the foil material changes appreciably. The change of experimental conditions, for example, of energy contribution in foil, its mass and dimensions results only in redistribution of intensity of plasma spectral lines, i.e. in the change of statistical weight of chemical elements in plasma, but the composition of chemical elements remains unchanged and it essentially depends on the material of foil. As it is seen from the received results, nuclear reactions, which take place at electric discharge, are not accompanied by the occurrence of a neutrons stream and γ-radiation and proceed at low energies of atomic nuclei.

The research mentioned above as well as many others, carried out by different researchers in different laboratories, **allow to draw a conclusion that existence of nuclear reactions at low energies is reliably established.**

The development of research on CF is hampered by the absence of theory of the phenomenon. As noted by Schwinger [3,4], the situation in CF is closely parallel to that one in high-temperature superconductivity: reality of the last, as a result of careful experimental research, is completely established, though theory of the phenomenon is absent till now.

In [5], to account for the transformation of chemical elements, the hypothesis is put forward that at the electric explosion of foil in the plasma channel magnetic monopoles are formed which may overcome the Coulomb barrier even at insignificant kinetic energy due to the great magnitude of their magnetic charge. The monopole, appearing not far from a nucleus, causes its polarization: those nucleons of the nucleus, which are situated more close to the monopole, experience stronger influence of the last, than the nucleons situated on the opposite side of the nucleus. As a result, a deformation of the nucleus arises (the nucleus is lengthened), which may result in nuclear fission.

Obvious drawback of this mechanism of nuclear reactions is that magnetic monopoles have yet to be found out in nature.

Numerous attempts to construct a consistent theory of CF (see reviews [1,2]) have not been crowned with success. As it was noted above, for the CF to be described, the account of the collective effects may be important caused by interaction of nuclei with environment, in which nuclear reaction takes place. But does it suffice to take into account these effects in order that the theory of the phenomenon is constructed? The analysis of the experiments on transformation of chemical elements at low energies and on the CF of nuclei suggests that the discussed phenomenon does not fall within the domains of exotic ones: it seems to occur in nature constantly, at every step, in both physical and biological systems. Therefore, it is natural to expect that nuclear reactions at low energies should have a simple physical explanation.

However such explanation, which is not beyond the scope of existing representations, is yet to be found. Does not it mean that we are facing here the situation similar to that which has arisen in physics at the end of the 19th century and which has been figuratively described in the words: on the light sky of physics there are only two small dark clouds – the radiation of absolutely black body and the Michelson experiments? Let us remind that in order for these clouds to be removed, it has taken the revision of physical notions about electromagnetic field as well as about space and time.

As is noted in [8], there is a simple physical mechanism of nuclear transformations at low energies which existence follows from the quantum theory of electron as an open self-organizing system [9]. If two or the greater number of light nuclei appear inside free electron, more precisely, inside the area of basic localization of the particle, because of interaction of nuclei with electrically charged matter of electronic cloud, a force of attraction appears between the nuclei which may result in fusion of nucleus. This means that **cold nuclear reaction represents an intra-electronic process** which character is defined by physical properties of the own field produced by electrically charged matter of electron. The purpose of this paper is more detailed consideration of the mechanism above stemming from the spatial extension of electron.

In section 2 physical ideas are formulated and basic results are schematically presented of quantum theory of electron as an open self-organizing system. The theory outlined is necessary to elucidate the origin of the mechanism resulting in the occurrence of nuclear reactions of fusion and fission at low energies. The essence of the developed approach consists in that **the own field created by electron is treated as a congenital, integral physical property of electron, intrinsically inherent in the particle by the very nature of things and for this reason the own field and self-action are included in the definition of the particle** at the initial stage of formulating the theory. As is seen from the received results, electron represents a quantum (elementary excitation) of the field of electrically charged matter. It is a solition, which physical and geometrical properties are described by the non-linear and non-local dynamical equation similar to the known Dirac equation.

In section 3 the application of quantum model of self-organizing electron to nuclear reactions at low energies is considered. It is noted that because of the presence of simple physical mechanism of nuclear reactions at low energies, which is of a universal character, nuclear reactors represent, in effect, nuclear delayed-action bombs, which from time to time may blow up by virtue of the casual reasons. Hence, though nuclear stations may provide mankind with energy, however atomic engineering is a very dangerous way of energy production. The only acceptable way of solving the energetic problem consists in the use of nuclear reactions at low energies.

Quantum model of electron as an open self-organizing system

The basis for the standard formulation of quantum electrodynamics (QED) is the hypothesis that electron is a structureless point particle which does not experience self-action. This assumption results in serious difficulties – the divergences of mass and charge of electron and the impossibility to explain stability of the particle (see, for example, [10-12]).

The difficulties mentioned above are very serious. According to Dirac, **the difficulties of QED "in view of their fundamental character can be eliminated only by radical change of the foundations of the theory, probably, radical to the same extent as transition from the Bohr orbits theory to modern quantum mechanics"** ([13], p. 403). "Correct conclusion", Dirac emphasizes, "is that the basic equations are incorrect. They should be changed in such a way that divergences do not appear at all".

The main reason of occurrence of difficulties is the assumption that electron is a point-like particle. Therefore, abandonment of this hypothesis is inevitable. As an analysis of the problem shows, the key to constructing a consistent quantum theory of electromagnetism lies in taking account of the Coulomb self-action of electron, i.e. the back action of the own field created by charged particle in environmental space upon the same particle. In the special case that the particle is at rest in an inertial reference frame, own field of the particle turns into static Coulomb field.

E.Schrödinger who suggested the historically first physical interpretation of quantum mechanics put one of the boldest ideas concerning the problem of electron forward. According to Schrödinger's hypothesis, the quantity $e|\Psi(\boldsymbol{r})|^2$ (e and $\Psi(\boldsymbol{r})$ are charge and wave function of electron, respectively) is the density of spatial distribution of electron's charge and, consequently, **the linear sizes of electron are the same as those of atom** [14,15]. However, they did not succeed in substantiating the interpretation and, for this reason, it was rejected by the majority of physicists [16].

An important step to the correct understanding of the physical nature of electron was made by A. Barut and by his collaborators [16-18] who formulated and developed quantum theory of electromagnetic processes on the basis of self-energy picture (the Self-Field QED). Using expression for the total own energy of electron, they managed to calculate the Lamb shift and other radiative corrections and to show that radiative phenomena may be described in terms of the action function, without using the second quantization method. As is pointed out by Barut [17], "the correct quantum equation of motion for radiating electron is not the Dirac or the Schrödinger equation for bare electron, but an equation containing an additional non-linear self-energy term".

New lines of approach to the problem of electron are offered in [9, 19-24]. The formulation of electrodynamics is considered which represents a synthesis of standard quantum electrodynamics and ideas of the theory of self-organization [25]. The physical mechanism of self-organization of electron consists in self-action. Taking into account the self-action means that electron is treated as a feedback system.

Let us outline schematically the results of the formulation of quantum electrodynamics in which electron is an open self-organizing system.

Editor's note: The authors develop mathematics by using Lagrangian functions, 7 equations. You can contact the authors for more information about.

Thus, the negative result is received: we have tried to take into account self-action of electron in a natural way by supplementing the Lagrangian function with the self-energy term, but we came to an equation that has no reasonable physical solutions at all. This result seems to mean that the standard theoretical scheme reaches here the limits of its applicability and so, remaining in its framework, it is impossible to solve the problem of electron and elucidate the physical nature of electromagnetic interaction.

Essentially new point, which is introduced in [9] into quantum mechanics consists **in the replacement of the model of isolated system described by harmonic oscillator with the model of open system**. Let us advance the arguments indicating the inevitability of using the model of open system as a basis of the description of interaction between microparticles [26].

Note, first of all, that quantum particle theory based on the use of the models of isolated system is, strictly speaking, physically meaningless. Really, any observation conducted on a system represents a process of interaction of the system with the means of observation. But in case of microparticles (quantum particles) this interaction is not weak and consequently it is inadmissible to neglect it, i.e. microparticles should be necessarily considered as essentially non-isolated systems.

A starting point of the standard formulation of quantum mechanics is the physical idea that interaction between physical fields can be reduced to collision of the particles corresponding to these fields, the particles before and after collision being considered as free ones. According to these representations, quantum mechanics is based on the notions of "bare", non-interacting particles, with the interaction between them being considered as an additional factor which can only insignificantly alter the physical properties of non-interacting particles. However, such an approach to interaction between physical fields is obviously of an idealized character because particles constantly interact "with vacuum as with some kind of physical medium in which the particles move" [27]. Interaction of particles with vacuum fluctuations is not small and it cannot be removed.

It is well also to bear in mind that the necessary intermediary at studying micro-objects are the means of observations (the devices) with the classical field corresponding to them which should be taken into account in consistent quantum theory [28]. Inclusion in theoretical scheme of arbitrarily weak classical external field results in occurrence of non-zero width Γ of energy levels of "dressed" particles. The basic impossibility to isolate a real particle from vacuum fluctuations of the field and from the classical sources connected to the means of observation is indicative, thus, of necessity to take into account the non-zero width of energy levels of real particles [26].

The use of the harmonic oscillator model, when describing the interaction of electromagnetic radiation with substance, seems to be the main source of serious difficulties of the standard formulation of quantum theory, as such an approach means apparent neglect of those physical processes which, proceeding constantly, are responsible for inseparable coupling of real physical system to surrounding medium. Introducing artificial notion about switching on and switching out of interaction of oscillator with radiation field, we are able to calculate within the framework of existing theory the width of energy levels of oscillator, but we cannot assert with certainty that such an approach results in correct description of interaction.

From the reasoning given above it is seen that they are the models with energy levels of non-zero width that should form the basis for the description of interaction of radiation with substance. It is necessary to formulate such a quantum theory, which would take into account the energy levels of non-zero width Γ. The case in point is that one should introduce an infinitesimal damping Γ into the initial set of equations describing interaction of charged particles with electromagnetic field. Such an approach means the violation in infinitesimal of homogeneity of physical system relative to translations in time. Necessity of violating the homogeneity of time follows from that fact that in the usual approach (with $\Gamma = 0$) the states of the system of interacting fields have degeneracy of infinitely large multiplicity in relation to time translations. According to the fundamental Bogoliubov's concept of quasi-averages [29], when describing the behavior of degenerate systems, one should include into Hamiltonian an infinitesimal term removing degeneracy. In the theory presented here degeneracy of states of quantized fields relative translations in time is removed by introducing the infinitesimal damping Γ into Lagrangian. Thereby the degeneracy under study is removed already in the initial, zero-order approximation, which is of fundamental importance for the approach based on perturbation theory.

Formulation of the physical idea that quantum friction arises at the very elementary level - at the level of one particle is given in monograph [26]. Impossibility to isolate real particle from the surrounding world is that property which should be taken into account already in the one-particle theory (for each kind of particles), even before switching on the interaction with other particles. Model of the particle as an open system ($\Gamma \neq 0$) is attractive owing to the fact that from the very beginning the degeneracy of states relative to time translations is absent in it, the degeneracy, which is removed in standard approach by taking into account the interaction of particle with vacuum field fluctuations and classical fields. The basis for the developed formulation is the fundamental concept of quasi-averages supplemented with the requirement that the equations of motion of the particle with $\Gamma \neq 0$ follow from the action principle. It should be emphasized that the non-zero damping Γ is introduced into electrodynamics with the aim to establish the structure of the Lagrangian function, which takes into account the property of openness of physical system. After establishing the structure, the limiting transition $\Gamma \to 0$ is fulfilled.

In our opinion, the development of quantum theory will be inevitably connected with the use of models of open system; as such models reflect more completely the physical essence of interrelations in the real world. It is necessary, thus, to define more exactly the concept of openness of physical system, which, on the one hand, would describe real system accurately enough and, on the other, would be simple enough to describe the particular physical processes.

As open system has the richer physical contents in comparison with isolated system, some essentially new mathematical ideas are needed for its description. First of all, it is necessary to increase the number of independent dynamical variables describing the particle as open system. In papers [9,19-24], as a basis for the description of self-acting electron, the simplest model of open system is used which can be described by the Morse-Feshbach-Bateman Lagrangian function [30,31] and which was successfully used for the description of dispersive medium (the review of articles, in which applications of the model of open system to electrodynamics of dispersive medium are considered, is given in monograph [26]). In this model the number of dynamical variables is doubled as compared with the isolated system, namely, to each dynamical variable of "bare" particle, Ψ, there correspond two dynamical variables, which are denoted by ψ and $\tilde{\psi}$. These quantities are considered as components of the wave function describing the quantum state of self-acting particle. One of them, say, ψ, corresponds in a sense to the particle alone (to the "bare" particle) and the other, $\tilde{\psi}$, to the surrounding medium, in which the particle moves.

Editor's note: You can contact the authors directly for more information (8-16 equations).

Equation (16) coincides in its appearance with the usual Dirac equation for charged particle in an external field described by 4-potential . However, in reality, it differs essentially from Dirac's equation. The distinction consists in that **equation** (16) **is non-linear and non-local**, with the non-locality being of both spatial and time character. Potential ($A_{||}$) and vortex ($A_{\perp}$) components of the 4-potential, entering equation (16), differ from each other by their physical nature: the former describes the Coulomb field and is expressed quadratically in terms of the wave function components of electron, and the latter describes transverse electromagnetic waves and is expressed in terms of vortex electromagnetic field. As a detailed analysis shows, solutions to the basic dynamical equation describe the clots of self-acting electrically charged matter, localized in space, i.e. the particle is a soliton.

The internal energy spectrum of electron is discrete with an indefinitely large number of levels, and to each value of internal energy E_k (k is the set of quantum numbers) there correspond certain linear dimensions and geometrical form of the region of localization of electron's charge. Dimensions and the number of extreme of wave function increase with increasing the value of energy E_k. The distribution of electric charge of atomic electron in the ground state consists of the range of basic localization with the linear dimensions of the order of Bohr radius a_0 ($a_0 \sim 10^{-10} m$) and of the tail stretching up to infinity. It is essential that because of non-linearity of the dynamical equation of electron, wave function does not obey the superposition principle. By virtue of this, electron acquires the properties of absolutely rigid body: the perturbation acting on electron at an instant of time in the range of basic localization becomes known at the next instant $t + 0$ at any distance from the particle.

In Fig. 1 the results of calculation are represented schematically, carried out on the basis of equation (13), of the distribution of electric charge in atomic and free electrons in the ground (a) and first excited (b) states.

According to [9,19], the atom represents a system of nuclear and electronic solitons interacting with each other, the internal energy spectrum of the hydrogen atom, due to electromagnetic interaction, being of a zoned character. The occurrence of zoned structure of energy spectrum of hydrogen atom is explained as follows. Free nucleus, because of existence of Coulomb self-action, has a discrete internal energy spectrum. As the interaction of nucleus with electron is small in comparison with the energy of Coulomb self-action of the nucleus, it can be taken into account by perturbation theory. From here it follows at once that each energy



Fig. 1. Density of electric charge (ρ) of electron in the ground state (a) and in the first excited state (b): the continuous lines correspond to electron in the hydrogen atom, and the dotted ones to free electron, r is the distance from the center of mass of electron measured in Bohr radii.

level of free nucleus is split in a zone. There are indefinitely many zones (Balmer's replicas) and in each of them there are indefinitely many energy levels. The lowest zone coincides with the usual Balmer spectrum.

Physical mechanism of nuclear reactions at low energies

The quantum theory presented above schematically of electron as an open self-organizing system is indicative of the existence of the following mechanism of nuclear reactions at low energies [8].

If there occur in the region of basic localization of free electron, which linear sizes in the ground state of the particle are several times as large as those for hydrogen atom (see Fig. 1), two or the greater number of nuclei, each of them attracts on itself the adjoining areas of electronic cloud, resulting in compression of the electronic cloud as a whole. As a result, there appears automatically an attraction of the nuclei, which proved to be "inside" electron, on each other (see Fig. 2).

Calculation shows that the Coulomb barrier around nuclei is deformed, its height decreases and the probability of penetration through the barrier accordingly increases due to tunnel transition. Under certain conditions this process may result in fusion of nuclei. Obviously, the process in question can occur only at small energies of translational motion of the centers of mass of electron and nuclei: nuclei should be "inside" electron long enough for them to have time to come nearer to each other as a result of electron-nuclear interaction. This mechanism of nuclear fusion is of a universal character. In order for it to be realized, it is necessary to have only a stream of free electrons intensive enough, i.e. heavy electric current, and as long as sufficiently great number of free nuclei.

If heavy nuclei appear "inside" free electron, owing to their interaction with the electronic cloud there occurs polarization of nuclei. Because the own field of electron interacts with protons more strongly than with neutrons, nuclei are deformed (become extended), and this process may result in the decomposition of nuclei to fragments (in nuclear fission).

As is noted in [7], the official version of the reasons for Chernobyl accident contains serious contradictions, a number of facts concerning the accident has no convincing explanations, and this circumstance forces to search for the true reasons for the happening, since



Fig. 2.
The schematic image of interaction of nuclei with electronic cloud: (a) 1 is the region of basic localization of electron, 2 and 3 are nuclei, F_1 and F_2 are the attractive forces between nuclei, which appear at the expense of electronic cloud compression induced by Coulomb forces; (b) ρ is the charge density, 1 is electronic soliton, 2 and 3 are nuclear solitons, X_n ($n=1, 2, 3$) are coordinates of the centers of mass of particles.

"not having understood the mechanism of the one tragedy, we sooner or later shall become witnesses of the other". The authors hypothesize that the reason of the accident was penetration into the nuclear reactor of magnetic monopoles, which have caused the decay of nuclei ^{238}U, and this has resulted in production of delayed neutrons, growth of power output of the reactor and explosion. As an argument in favor of the assumption, the fact is presented that nucleus ^{238}U are disintegrated under the action of "strange" radiation appearing at explosion of foil.

In the opinion of the authors of [5,7], "strange" radiation is created by those magnetic monopoles, which form bound states with nuclei of atoms. These compound particles give the abnormally wide tracks similar to those of a creeping caterpillar, and also the tracks of complicated shape reminiscent of spirals and gratings. Character of tracks changes when imposing magnetic field, which, as the authors believe, is an argument in favor of the assumption above. There are also some special tracks very similar to scratches and ink spots. "Strange" radiation is of spherical form, it resembles a ball lightning, and its duration is more than ten times as great as that of the current pulse arising at electric discharge. With the course of time the luminous sphere (the ball-like plasma formation) is dividing into many small "balls".

It is our opinion that "strange" radiation is caused by free electrons in excited state arising in the area of electric discharge. According to [9, 19], linear sizes of the region of basic localization of such electrons can make many tens of sizes of atom. The heavy nucleus, for example, the nucleus ^{238}U, appearing inside the electronic cloud, is inevitably deformed because of interaction of protons with adjoining layers in the distribution of electric charge of electron, and this deformation can cause nuclear fission. If two or the greater number of light nuclei appears "inside" electron, then attractive forces arise between nuclei, which may result in fusion reaction. When electric discharge is strong enough, the areas of basic localization of some electrons can overlap, and if a nucleus lands in the area of overlap, because of Coulomb attraction of nucleus on the adjoining layers of electronic clouds, a bound state may be formed, of two electrons and the nucleus, characterized by the relative stability and significant spatial extension.

Obviously, if the concentration of free electrons is great enough, there may be formed some relatively stable bunch of plasma consisting of great number of free electrons and nuclei, which in virtue of chaotic movement of nuclei and because of the absence of preferred directions should have approximately spherical form. Let us note that atomic electrons, belonging to additional energy zones of atom (Balmer's replicas associated with nuclear self-action, see Section 2) can contribute to "strange" radiation.

As is seen from above, to account for the reasons for Chernobyl accident, there is no need to involve magnetic monopoles. The scenario of development of events during the accident, described in [7], seems to be quite plausible if only to understand by initiators of nuclear fission not hypothetical monopoles but free electrons, which powerful pulse might arise as a result of electric discharge in the region of turbo-generators.

The existence of simple physical mechanism of nuclear reactions at low energies, indicated in this paper, implies that nuclear reactors are, in effect, nuclear delayed-action bombs, which will blow up from time to time. Explosion of nuclear reactor may take place because of casual short circuit at an electric subcircuit, owing to which there appears an intensive stream of free electrons. This stream, having got for any reasons in nuclear reactor, may initiate explosion of the reactor. It follows from here that though nuclear stations may provide mankind with cheep energy, atomic energetics represents a very dangerous way of producing energy (as well as the energetics using controlled thermonuclear fusion). The only acceptable way of resolving the energetic problem consists in the use of nuclear reactions at low energies.

According to the results obtained, nuclear reactions at low temperatures occur "inside" electron under the action of own field of particle. Hence, to elucidate physical mechanism of CF, it is necessary to study in detail intra-electronic processes and physical properties of own fields of particles. Note that the own field, by its physical properties, essentially differs from the field of electromagnetic waves: this is the field of standing waves of matter, it is of purely classical character and may not be reduced to the set of photons. The own field of charged particle plays in nature a special role, consisting in that it transforms environmental space into the physical environment (physical vacuum) with the properties of absolutely rigid body [32].

As it was repeatedly noted in the literature [1,2], experiments on CF are badly reproduced, and this fact gives rise to doubt the very existence of the phenomenon. Bad reproducibility of results seems to be explained by the fact that CF depends upon great number of parameters: upon electric current density, concentration of free nucleus, concentration of impurities and dislocations in samples, sizes of samples etc. In order to obtain reproducibility of results, it is necessary that all these parameters, describing the environment in which nuclear reactions occur, be the same in various experiments, but to achieve this as a difficult task.

In conclusion we shall dwell upon the problem of linear dimensions of electron, which is of special interest in connection with the mechanism of nuclear reactions indicated here. The inference that the dimensions of electron in the ground state of atom are of the order of Bohr radius, i.e. of the order of atomic dimensions, following from dimension considerations [9,19] and confirmed by quantum model of electron, seems completely unexpected. At first sight, it is in conflict with both the theory of quarks and experimental data on scattering of electrons. According to quark models, the radius of electron corresponding to its quark structure makes up the quantity of the order of 10^{-22} m [33]. It is necessary to emphasize, however, that the above-mentioned magnitude of linear dimensions of electron refers to the internal structure induced by Coulomb field. The last is long-distance and consequently the linear dimensions of internal structures produced by it (i.e. spatial inhomogeneities in the distribution of electric charge in various quantum states) should considerably exceed the dimensions of quark structures connected with electron. There seems to exist a hierarchy of internal structures of particle produced by Coulomb forces, nuclear forces, inter-quark interactions etc. characterized by the smaller and smaller linear sizes.

As to the experiments on scattering of high energy electrons, according to which the internal structure of electron is not manifested up to distances of the order of $10^{-16} \div 10^{-17}$ m, two arguments, at least, can be adduced in favor of that there is no contradiction here with the experiment. Firstly, in experiments on scattering, investigators were trying to register the details of internal structure of electron within intervals much smaller than Bohr radius, which is why it is not surprising that results of experiments proved to be negative: at high energies electrons behave like point particles, their internal structure has no time to be manifested. Secondly, the results of experiments were analyzed from the point of view of standard representations about electron, which refer to a point particle, but are obviously inapplicable to real, self-acting electron. According to the predictions of quantum theory of electron as an open self-organizing system, real electron is a special object - soliton, i.e. such a cloud of electrically charged substance which, when interacting with other particles, tends to keep its sizes and geometrical form.

At present there is as yet no scattering theory of this kind of particles and for this reason it is impossible to predict with certainty how can the internal structure of electron be manifested in experiments on scattering.

References

1. Storms E. A *Critical Review of the "Cold Fusion" Effect.* J. Sci. Explor., **10**, #2, p.185 (1996). See also: http://www.jse.com/storms/1.html
2. Storms E. *Cold Fusion Revisited.* Infinite Energy, 4, #21, p.16(1998).
3. Schwinger J. *Cold Fusion: A Hypothesis.* Z. Nat. Forsch. A 45, 756 (1990); *Cold Fusion: A Brief History of Mine.* Infinite Energy, 1, #1, p.10 (1995).
4. Schwinger J. *Nuclear Energy in an Atomic Lattice I.* Z. Phys. D15, 221 (1990); Prog. Theor. Phys. 85, 711 (1991); *Energy Transfer in Cold Fusion and Sonoluminescence.* http://www.geocities.com/CapeCanaveral/Lab/4520/theory.htm
5. Urutskoev L. I., Liksonov V. I., Tsinoev V. G. *Experimental Detection of "Strange" Radiation and Transformation of Chemical Elements.* Applied Physics, M., 2000, p.83-100. Urutskoev L.I., Liksonov V.I., Tsinoev V.G. *Observation of Transformation of Chemical Elements During Electric Discharge* http://arxiv.org/ftp/physics/papers/0101/0101089.pdf
6. Vysotskii, V. I., Kornilova A. A., and Samoylenko I. I. *Experimental Discovery of Phenomenon of Low-Energy Nuclear Transformation of Isotopes (Mn55=Fe57) in Growing Biological Cultures.* The Sixth International Conference on Cold Fusion, Progress in New Hydrogen Energy (Ed. M. Okamoto) Oct. 13-18, 1996, Hokkaido, Japan, Vol. 2, p. 687; Infinite Energy, 2, #10, p.63 (1996).
7. Urutskoev L.I., Geras'ko V.N. *On the Possible Mechanism of Chernobyl Accident.* http://www.recom.hotmail.ru/CHER_INC_1.doc
8. Oleinik V.P. *To Electronic Technologies of the 21st Century: on the Threshold of Revolution in Communication Systems. Collection of Reports*, Millenium 2002, International Conference "To Innovations in the 21st Century", Odessa, April 13, 2002, p.268-273.
9. Oleinik V.P. *The Problem of Electron and Superluminal Signals.* (Contemporary Fundamental Physics) (Nova Science Publishers, Inc., Huntington, New York, 2001).
10. Berestetsky V.B., Lifshits E.M., Pitaevsky L.P. *Relativistic Quantum Theory*, part 1. (Moscow, Nauka, 1968).
11. Medvedev B.V. *Foundations of Theoretical Physics.* (Moscow, Nauka, 1977).
12. Dirac P.A.M. *Relativistic Wave Equation of Electron.* Progress in Phys. Sciences, 129, #4, p.681–691 (1979).
13. Dirac P.A.M. *The Principles of Quantum Mechanics.* (Moscow, Nauka, 1979).
14. Schrödinger E. *Quantisierung als Eigenwertproblem.* Vierte Mitteilung. Ann. der Physik, Bd. 81, S.109–139 (1926).
15. Schrodinger E. *Selected Works on Quantum Mechanics*, Edited by Polak L.S. (Moscow, Nauka, 1976).
16. Barut A.O. *Schrodinger's Interpretation of as a Continuous Charge Distribution.* Ann. der Physik, Bd. 45, S.31-36 (1988).
17. Barut A.O., van Huele J.F. *Quantum Electrodynamics Based on Self-Energy: Lamb Shift and Spontaneous Emission without Field Quantization.* Phys.Rev., A32, #6, p.3187–3195 (1985).
18. Barut A.O., Dowling J.P. *Quantum Electrodynamics Based on Self-Energy*: Spontaneous Emission in Cavities. Phys.Rev., A36, #2, p.649–654 (1987).
19. Arepjev Yu.D., Buts A.Yu., Oleinik V.P. *To the Problem of Internal Structure of Electrically Charged Particles. Spectra of Internal Energy and Charge Distribution for the Free Electron and Hydrogen Atom.* Preprint of the Inst. of Semiconductors of Ukraine, N8-91 (Kiev, 1991) 36 p.(in Russ.).
20. Oleinik V.P. *Quantum Electrodynamics Describing the Internal Structure of Electron.* Quantum Electronics. #44, p.51-59 (1993) (in Russ.).
21. Oleinik V.P. To *the Theory of the Internal Structure of Electron. Second Quantization and Energy Relations.* Quantum Electronics. #45, p.57-79 (1993) (in Russ.).
22. Oleinik V.P. *Quantum Theory of Self-Organizing Electrically Charged Particles. Soliton Model of Electron.* Proceedings of the NATO-ASI "Electron Theory and Quantum Electrodynamics. 100 Years Later." (Plenum Press, N.-Y., London, Washington, D.C., Boston, 1997), p.261-278.
23. Oleinik V.P. Nonlinear *Quantum Dynamical Equation for the Self-Acting Electron.* J. Nonlinear Math. Phys. 4, #1-2, p.180-189 (1997).
24. Oleinik V.P. *Quantum Equation for the Self-Organizing Electron.* Photon and Poincare Group (Nova Science Publishers, New York, Inc., 1999), p.188-200.
25. Nicolis G., Prigogine I. *Self-Organization in Non-Equilibrium Systems* (Wiley-Interscience, 1977).
26.Oleinik V.P., Belousov I.V. *The Problems of Quantum Electrodynamics of Vacuum, Dispersive Media and Intense Fields.* (Kishinev, Shtiintsa, 1983).
27. Bogoliubov N.N., Shirkov D.V. *Introduction to the Theory of Quantized Fields.* (Moscow, Nauka, 1976).
28. Bohr N. *Selected Scientific Works*, V.2. (Moscow, Nauka, 1971).
29. Bogoliubov N.N. *Quasi-Averages in the Problems of Statistical Mechanics.* In the Book: Statistical Physics and Quantum Field Theory. (Moscow, Nauka, 1973).
30. Morse P.M., Feshbach H. *Methods of Theoretical Physics*, V.1. (Moscow, Foreign Literature, 1958).
31. Dakker H. *Classical and Quantum Mechanics of the Damped Harmonic Oscillator.* Phys. Reports, 80, # 1, p.1-112 (1981).
32. Oleinik V.P. *Superluminal Signals, the Physical Properties of Time, and the Principle of Self-Organization.* Physics of Consciences and Life, Cosmology and Astrophysics, #1, p.68-76 (2001).
33. Dehmelt H. *Experiments with an Isolated Subatomic Particle at Rest.* Progress in Phys. Sciences, 160, #12, p.129–139 (1990).

The Evolution of Lifter Technology

Tim Ventura

tventura6@attbi.com

INTRODUCTION

Readers of the electric-spacecraft journal might know a little about the Lifter technology popularized recently be Jean-Louis Naudin, but they probably don't know the whole story. In the short amount of time that has transpired since the publication of that article, this technology has both literally and figuratively taken off – going from a "proof-of-concept" prototype by Naudin to an international group of researchers investigating how to give the lifter higher-performance and greater efficiency. With the first commercial products now on the horizon, if you haven't taken the time to read up on lifter technology, this is the perfect time to do so. . .
To give you a complete up-to-date overview of where this technology is, where it is going, and what I think it is capable of, let me start with the basics – an overview of how I became involved with Electrogravity research and what eventually led me to become involved with lifter technology.

MY BACKGROUND

I started college at 16 years old, back in 1992 – at the same time, I purchased a kit containing "hoverboard plans" from Hovertech, Inc. The moment that I received that $20 white-manilla envelope in October 1992 was the moment that I became involved with what has now been nearly 10 years of electrogravity research.

I worked with Bill Butler – the president and chief-scientist of Hovertech – on a variety of different antigravity, Electrogravity, and levitation ideas from approximately 1992 through 1996. While putting in my college time, I was also taking distinct advantage of the enormous college library at Western Washington University to read up on everything that might possibly relate to Electrogravity. I read books on standard electronics and physics theory alongside with books by the masters of this science, such as TT Brown and Nikola Tesla.

Bill and I played with several different ideas – many of them only peripherally related to Electrogravity. For instance, I published a manuscript initially in 1996 describing Tesla's theory on how to reliably produce Ball-Lightning using a standard Tesla coil – the information courtesy of WWU's excellent library. Bill also assisted me with obtaining video footage of a Searl-effect conference that he attended in Denver in the early 90's – this footage was an excellent overview of Searl's design and construction concepts for what he believes is the next major technological step in aviation and space travel.

Bill and I eventually found different paths, and in some ways drifted apart. Bill moved into Geomagnetic levitation research and started intense investigation on the patents of How Wachspress and the magnetic dipole levitator. I went to more traditional technologies – eventually becoming a UNIX system administrator for AT&T Wireless.

I hadn't heard from Bill Butler in about 6 months when he sent me a short email containing the words "hey, check this out" – and a link to Jean-Louis Naudin's "Lifter Experiments" home-page. I visited the site, watched all of the video clips, and then watched them again. This was the technology that I had been waiting for!

LIFTER TECHNOLOGY

I can say without a doubt that the lifter technology is completely revolutionary, but you might not realize how profoundly revolutionary it is until you've stopped to think about it for a bit. What is it about the lifter that makes it so unique, especially when so many inventions claim to produce more and better electromagnetic thrust? The answer is simple – the lifter works repeatedly.

Jean-Louis Naudin started a figurative bonfire when he decided to replicate a "proof-of-concept" experiment by a small Huntsville, AL aerospace contracting firm. The lifter initially came into being in the mind of Jeff Cameron – the chief scientist of Transdimensional Technologies – in the 1970's from experiments conducted with high-power military and research-grade lasers. A device in the lasers called a "pre-ionizer" was used to apply a high-voltage to the lasing-medium to facilitate better performance. Repeated operation of the pre-ionizer had a common side-effect of horribly twisting the wire and foil combination out of shape, which required a decent amount of work to repair.

Jeff Cameron realized that the torsional effect on the pre-ionizer was a side-effect of some unknown force acting on the pre-ionizer apparatus, and he began a long-term investigation into what was causing the apparatus to deform. His eventual results indicated that a force in the foil collector in the pre-ionizer was causing a net-thrust in the entire pre-ionizer apparatus that was making it twist and move on its mounts within the laser – the lifter came to him later as a three-dimensional device to demonstrate this force.

Naudin's genius became readily apparent not through a giant breakthrough in technology, but rather in a more subtle fashion – he replicated the lifter experiments of Transdimensional Technologies and published videos, articles, and complete construction plans on his website to allow others to do the same. In a manner similar to the open-source software movement, Naudin had taken an incredible scientific find that might have otherwise been overlooked and done and incredibly charitable and intelligent thing – he gave it away for others to play with. By following Naudin's instructions, inventors all over the globe began to slowly replicate the

Transdimensional Technologies experiments and thereby validate the proof of concept that Jeff Cameron had created to show that his "mystery force" was real after all. Naudin of course took advantage of these replications of the experiment by showcasing them on his own website – which in turn lends additional credibility to his research.

As far as technology goes, the lifter demonstrates that science and engineering have more than their share of humorous irony. For the years that I researched Electrogravity and antigravity claims, all of the devices that I had seen required something "magic" to make them work. For instance, Bob Lazar's UFO-claims could have been reverse-engineered except that they require 'element 115' to make them work – an element chemically related to Bismuth that is theorized to potentially have electrogravitic properties. I will come back to the possible electro-gravitational properties of Bismuth in a bit, as it turns out that this element may in fact provide some use for future lifter technology.

The Searl-effect disc is an even better example of the "magic" usually involved with building a working Electrogravity device. Searl's ideas seem valid enough, but although he supposedly demonstrated several working prototypes in the 1950's, he is currently pursuing millions of dollars in research funding in to replicate those experiments in a modern-day setting.

The irony involving lifter technology is that while inventors all over the world have been searching for the perfect electro-gravitational device for decades, the possible working proof of concept for many of these theories has been sitting in front of us the whole time – the lifter costs less than $10 in parts to build, and none of them are magic – in fact, for my experiments, all of them were at stores within 2 blocks of my house — balsa wood from the craft store, aluminum foil from the supermarket, 30-gauge magnet wire from the local Radio Shack, and an old computer monitor for the high-voltage power-supply.

LIFTER PHYSICS

Whether or not Jeff Cameron knew it at the time he constructed his lifter prototype, what he was actually building was a 3 dimensional representation of a drawing on a patent application by TT Brown in the 1950's. In the patent application, the drawing shows a positively charged wire suspended over a grounded foil body which was meant to demonstrate the most basic Biefeld-Brown effect generator. While Brown's drawing is a little different than Jeff's design, the resemblance is uncanny enough to indicate that both of these men had the same basic force in mind.

TT Brown's patent indicates that this Biefeld-Brown effect generator works due to a gradient electrostatic-field between the wire and the foil – in essence, these two elements compose a low-efficiency, high-voltage air-gap capacitor in which the difference in geometries between the two capacitive elements generates a net-directional force from the larger element towards the smaller element. Jeff Cameron seems to have a practical axiom that goes along with this scientific philosophy, which is that there must be both a leakage current and a capacitance between the wire and the foil in order for the lifter to function.

Conventional physics says that two capacitor elements of different sizes will not generate a net-directional force, so what gives? This is actually the thinking that convinced me to abandon my research into Biefeld-Brown effect technology in 1996 – physics says it doesn't work. What the books say will happen is that since the wire can only maintain a lower-capacitance than the foil, the overall capacitance between the two elements will be reduced to be equivalent to that on the smallest element (or plate) in the capacitor. This, of course, assumes a 2-element series-wired capacitor, such as the lifter.

I can give you the conventional physics answer to this small riddle by simply saying that the lifter uses a manifestation of ion-wind. This would state that the electrons crossing the air-gap cause a breeze that causes thrust – since the breeze would be traveling down from the wire to the foil, the thrust would be up, as demonstrated in testing. In the ion-wind explanation, the electrons are emitted from small-diameter of the positively charged wire in such great abundance that they move a significant airflow down to the foil where they are absorbed and transported electrically back to the HV power-supply's electrical ground.

Conventional physics would seem to have the theoretical answer to why the lifter causes lift, but in the experimental setting, which is what we now have an abundance of thanks to Jean-Louis Naudin, the conventional physics explanation doesn't suffice. Experimentally, there are several deviations from the ion-wind explanation that seem to invalidate it. For instance, if you completely contain the lifter in a plastic-enclosure, it will still generate lift – this would not be the case if a breeze was responsible for lifting the device. How could it be, if the breeze is limited to the inside of an enclosure which itself is levitating?

A more compelling proof that Biefeld-Brown is something other than ion-wind comes from Purdue University, where the lifter experiment was replicated inside a vacuum-enclosure with positive results. While ion-propulsion can work in space, it usually assumes that there is argon, krypton, or other noble gas to be used as the propellant – the vacuum enclosure showed that with no gas available for transport the lifter showed a moderate improvement in performance.

The vacuum enclosure tests are definitely compelling evidence that something else is going on other than ion-wind – at least compelling enough for NASA to file patent number 6,317,310 – "Apparatus and Method for Generating Thrust using a Two Dimensional, Asymmetrical Capacitor Module". The NASA patent description – which can be accessed from Naudin's lifter website – is as vague is it is compelling in that NASA is basically requesting a patent on any technology that generates force using two geometrically dissimilar capacitive plates. Disregarding the fact that this patent was issued nearly 50 years after TT Brown's patent using nearly identical descriptions and pictures, and also disregarding the fact that NASA also doesn't understand why the lifter generates thrust, it seems apparent the this phenomena is gaining credibility in engineering circles while physicists seemingly continue to deny that anything is going on.

THE EVOLUTION OF LIFTER TECHNOLOGY

Every good movie always has a sequel, and in technology, if at first a major government agency 'liberates' your idea, it may seem that a sequel is in order. In the case of the lifter, it would appear that the NASA patent would cover this technology to at least some degree – at least until someone overturns this patent under the prior-art rule – which means that the next generation has to be considerably more advanced to escape having the research and development be forfeit to the government.

The pursuit of more advanced versions of the lifter technology is currently underway by several independent inventors, as well as Transdimensional Technologies themselves. Most of the private research by inventors has delved into improving the current lifter design to produce a greater force output and utilize less power to do so. Because the lifter is so simplistic in design, many of these enhancements have been of a very basic nature.

Jean-Louis Naudin was the first independent inventor to do serious work with improving the technology behind the lifter – and even so, the majority of his work has utilized similar materials in more complex arrangements. Naudin has demonstrated dramatically increased lifting forces by building a "lifter inside a lifter" for demonstration purposes. Naudin has also done a great deal of work in taking breaking up the concept of the single triangular lifter into a parallel series of lifting cells – which means that these cells, working in parallel, can contributed to greater stability and higher force output than any single lifting element.

Saviour – an independent inventor working with Jean-Louis Naudin – has done some of the most interesting improvements on lifter design since those by Naudin himself. Saviour's concerns have not focused around the "bigger is better" philosophy that many inventors have stuck by – he has done several experiments to determine the radiation output, remote-controlled applications development, and materials analysis and improvement on the lifter that others have not had the time or expertise to conduct.

A recent experiment by Saviour demonstrates just how this gentleman's foresight is helping other experimenters – Saviour substituted nichrome heating wire for the common lightweight wire used for the emitter, and demonstrated that the lifting force greatly increased when a higher potential 12-volt charge was used to heat the emitter wire in conjunction with the standard high-voltage charge coming off it.

Transdimensional Technologies – the developers of the initial lifter design – are taking the approach to optimizing lifter performance to another level. They are currently not-so-secretly working on a 2nd generation lifter, which will consist of a 1-piece layered material to replace the current wire and foil design.

The layered material approach to the lifter is an idea that Jeff Cameron may or may not have had after some lengthy discussions with Travis Taylor – the man responsible for testing some anomalous materials known as "Art's Parts".

Art's Parts were some pieces of material sent by an unknown person to the Art Bell radio talk-show with a note stating that the they were pieces of UFO wreckage taken from the often-cited "Roswell crash" in 1947. Whether or not the pieces of material actually came from that crash is unknown, but Art Bell did the honorable thing by sending them to an acquaintance in US Army research named Travis Taylor for a professional scientific investigation.

Taylor, who apparently tested the materials after-hours in a world-class research lab to avoid potential classification by his superiors, used an electron-microscope to determine that the layered materials were actually pieces of metal – containing several hundred microscopically thin layers of magnesium and bismuth. Taylor also tested the layered-metal with a high-voltage apparatus, which seemed to indicate that when a voltage was applied to the material, the layered metal would move – and in some cases levitate.

Taylor reported his findings to Art Bell and sent video clips of his high-voltage experiments, which eventually made it back to a permanent home on the Art Bell radio show website. In addition, Taylor conveyed his belief that the only manner in which the pieces of metal could properly be produced was through an advanced form of electron-deposition technology, due (apparently) to an absence of oxygen-molecules between the different layers of metals. Additionally, the layers of metal were too thin to have been mechanically produced.

Jeff Cameron indicated that Transdimensional Technologies maintained some contact at one point in time with Travis Taylor, apparently as professional colleagues in the defense community in Huntsville, AL. I am not an expert on this relationship, other than to say that to the best of my knowledge these two individuals knew and contacted each other, and that this is how Jeff Cameron might have come up with the 2nd generation lifter idea.

ADVANCED LIFTER TECHNOLOGY

As an inventor, I couldn't care less whether or not the idea for the technology came from a crashed UFO. To be perfectly honest, I'm not what you would call a "believer" anyways, although I have often wondered about it. My point is not to attempt to lend any credibility to "Art's Parts", but rather to tie in the properties of the anomalous material's high-voltage movement with the underlying theory of lifter operation.

Even mentioning a UFO in a respected publication or article is the kiss of death in today's world – and I wouldn't do it if it wasn't an intricate part of the story. The other interesting thought is that the layered material is once again partially composed of Bismuth – which is thought to possibly have some of the same electro-gravitational properties as Bob Lazar's Area 51 "element 115". Is there a similarity, or merely a coincidence between a claim that hasn't gained credibility and a technology currently under development?

The lifter in its own right is essentially a layered material. One of those layers is the emitter wire, which is highly charged with about 30kV worth of electrons, another layer is the air-gap, which is approximately 3 cm in height, and the final layer is an electrically-grounded "skirt" of aluminum foil that surrounds the lifter. It is also reasonable to expect that there are only two possible forces at work in the lifter – one of which being a possible ion-wind effect moving down from the emitter to the foil, and the other being a possible Biefeld-Brown effect, moving up through the foil to the emitter.

There are a few shortcomings in the lifter as a design that might be overcome if we could transition the layered material from one containing an air-gap to one that does not. For instance, the lifter is currently a rather delicate object, in that having a wire under tension as the emitter makes construction difficult for future automated assembly. Additionally, because the air-gap requires struts to support the emitter wire, a trade off involving the weight versus the strength of the struts is additionally involved in any current implementation of lifter technology.

Some of the other changes that would be helpful to implement when transitioning lifter technology from one type of air-gap to another are changes in the materials used to increase the dielectric capacity. High-K dielectric materials may be used to increase the displacement of electrons in the material to enhance charge transport. And since increasing the dielectric potential of the layered materials also increases the breakdown resistance, it means that thinner materials can be used.

Designing a lifter without an air gap would accommodate lower voltage requirements between the foil and the emitter. The voltage would not have to create the large e-field gradient to create a leakage current across such a large void. Therefore the overall voltage across the device could be greatly reduced, without much cost in thrust. A lower operating voltage in turn means that a lower-output power-supply can be used for a given amount of current, which increases the overall efficiency.

Transdimensional Technologies recent research is utilizing the layered materials approach to eliminate the air-gap and substitute for it high-k dielectric materials that may allow higher overall performance. Although they have not yet released details about the exact composition or thickness of the materials that they are working with, they claim to currently have a 10% reduction in weight using a low-voltage current across the thickness of their newest device.

FUTURE LIFTER TECHNOLOGY

Thanks to the tremendous amount of research being done on lifter technology by Transdimensional Technologies and a loosely affiliated group of inventors around the world, the future of lifter technology seems very bright at this point.

Transdimensional hopes to release some breakthrough research to allow replication of their newest 2nd generation experiments in the very near future, and along with that stands the massive body of research and advancements being done by inventors and researchers such as Jean-Louis Naudin, Saviour, the Lifters-group, and myself.

My personal goals are to attempt to assist Transdimensional Technologies in popularizing this technology to increase awareness of it and help "spread the word" about what it is and how it can potentially help the world.

Imagine if instead of getting in your car and driving through the usual maze of thoroughfares and side streets you were able to simply type in your destination and have a flying vehicle take you there automatically. The lifter technology offers to potential to transform the current transportation market by offering point-to-point aerial transport without the need for roads or freeways.

Additionally, unlike the magnetic-levitation ("Maglev") technologies that are currently being promoted as the future of transportation, the lifter does not require a specially constructed and exorbitantly expensive track to operate – the greatly reduces the per-unit cost on the technology and opens the door for wider adoption by the general public for transportation solutions.

Other individuals are currently working to see if lifter technology may offer cost-effective methods of transport into space, which would reduce the cost greatly and allow a one-piece, reusable method of moving things into orbit.

LIFTER RESOURCES

All of the research involved with the lifter technology is available to the public on the internet. The list of resources below are some of the better and more common resources to obtain detailed lifter information.

American Antigravity
→ http://tventura.hypermart.net

→ The author's website that includes video clips, complete instructions, and other related lifter information.

Jean-Louis Naudin's "Lifter Experiments Website"
→http://jnaudin.free.fr
→ A very in-depth website containing video clips, complete instructions,

World-Wide Lifter Replications
→ http://jnaudin.free.fr/html/lftwrld.htm
→ An overview with photos and video from many of the independent inventors who have replicated the lifter experiments.

Transdimensional Technologies, Inc
→http://www.tdimension.com
→ The home page for Transdimensional Technologies, the developers of the lifter design.

Blaze Labs (Saviour's Research Website)
→http://bel.150m.com
→An excellent site on research into lifter enhancements, radiation testing, sealed devices, power supplies, and other topics relating to lifter technology.

Lifter Builders Group
→ http://groups.yahoo.com/group/Lifters
→ An email group for the exchange of research findings for those interested in building lifters or staying current on the state of the technology.

NASA Patent #6,317,310
→ The NASA patent regarding obtaining thrust from an asymmetrical two-dimensional capacitor, grant Nov 13, 2001.

Research on the Capacitance Converter of Environmental Heat to Electric Power

N.E. Zaev

143970, Moscow region, village Saltykovka,
Granitchnaya Str., 8 529-9664

Nickolay E. Zaev works on creation of the prototypes of converter energy, which do not require any fuel. The direct conversion of environmental heat to electric power is possible in the processes of "charge-discharge" in non-linear condensers or by means of "magnetization-demagnetization" of ferrites. Such converters of energy create cold and electric power without any fuel.

Theory of the converter, results of early experiments on the generation of microwatt power, methods and features of research are given in this article. The methods of generation of a few watts power are described in details. The possibilities and difficulties of creation of powerful capacitance converters are discussed in this article.

I. Grounds of research.

1.1. From positions of orthodox physics there is no subject of research. It is evident that the energy of charging (C) A_c condenser C_x is always equal or more than the energy of discharging (D) A_d, i. e. always $A_c \geq A_d$. Only the advanced analysis shows that it is not always true. Exactly, in C_x, where $\frac{\partial C}{\partial V} < 0$ an inequality $A_d > A_c$ is possible, and in C_x, where $\frac{\partial C}{\partial V} < 1$, then the work $A_c > A_d$. Therefore we should discuss the nonlinear capacitors (NC). In the end of 1969 I noticed a systematic inequality $A_d > A_c$ during the measurement of A_c and A_d of many capacitors with different dielectrics. Theoretical grounds and results of measurements of this phenomenon are given in the publications in 1984 [1], [2, page 73]. On the industrial standards NC (varicond), ceramic condensers VK2-ZSH, $4 \cdot 6{,}8 \cdot 10^{-9}$μF with an optimal voltage about 95 V it was stated that $\frac{A_d}{A_c} \sim 1{,}21$ with the power to about $98 \cdot 10^{-6}$ Wt and "generated" extra power is equal to $21 \cdot 10^{-6}$ Wt.

1.2. In [1] and [2] the strict theoretical proofs of realization of $A_d > A_c$ (there are four of them) are given. On 1m^3 of dielectric $|A_d| - |A_c| = -\frac{1}{2} a \cdot \varepsilon_0 \cdot E_c^3$ (E_c is an intensity of the field, V/m; ε_0 is a dielectric constant of vacuum, a is a coefficient of nonlinearity of the capacitor). Below we state one more proof more connected with the parameters of circuit.

It is well known that with the charge of a linear capacity from the source of constant voltage V_0=const through the resistor R=const it gets an energy $A_c = \frac{C \cdot V_0^2}{2}$ exactly equal to the output energy in the time of charging t_c. The output energy irradiated from the load R is a Joule heat $\Theta = R \cdot \int_0^{t_c} i^2 \cdot dt$ [3, page 546]. If NC (nonlinear condenser) is charged, then there are no proofs of such equation. The NC are the variconds or other capacitors, which have $\frac{\partial C}{\partial V} > 0$ in the interval $V = 0 \div V_k$. For the variconds V_k is some voltage, which corresponds to the maximum C_{v}. If $V > V_k$, then $\frac{\partial C}{\partial V} < 0$. For some other capacitors V_k is a voltage breakdown.

For further consideration let's believe that in the operating area of the given sample of varicond a function

Reality and Consciousness in Education and Activity

A.P. Smirnov

Vice president of International Club of Scientists
190031, Saint Petersburg, Kazanskaya str., 36
Tel: +7 (812) 312-0508
E-mail: science@shaping.org

Relation of thought to existence is the main question of philosophy as science on general laws of Nature was formulated but it still did not interpreted and solved in the frames of generally accepted logic standards. The ways to solve it lead to futile discussions of materialists and idealists, to senseless disputes of determinists with eclectics and apologists of the "chance". This discussion lost its sense without a determination of terms under discussion and condemned debaters to have subjective "gustatory" senses, which were changing while aging and depended on the extent of received and conceived knowledge. Such is the situation in this link of World studying, which does not allow creating a logic chain of reasoning in the understanding of cognizable things.

A paradoxicality of all things that happen is connected with incorrect translations and interpretation of wisdom of ancient philosophers and scornful attitude both to the knowledge of distant past and classical heritage, which highlighted the elements of natural-science approach to Weltanschauung.

According to Plato, **an ideal thing** is a visual thing, which can be felt by our organs of sense. Therefore, the understanding of objective reality is mediated by the crowd of our feelings in such a way that perception of reality by means of these feelings gives us a notion of the World. Hence, **our notions about reality are the subject of research in science, but not the World itself, i.e. the World outside of our consciousness.** So, what should be studied in our notions about the World? Let us refer to the wisdom of ancient scientists again: " The World is given in motion and its laws are the laws of motion". Then, we should speak about laws, order, i.e. about relation and interrelation in the phenomena of motion. This is the distinctness in notions and actions (determinism) to predetermine further development of reality cognition logic, i.e. what has an influence on us and determines specific character of our perception. Further we can speak about formation of ideas about reality, which require some premises, principles to organize these ideas. These principles are given in classical heritage, in "Dialogues" by G. Galilee [1] and "Mathematical principles of natural philosophy" by I. Newton [2]. A notion of force as a measure for momentum was introduced, which manifests in action and disappears from the body after the action is over, and the body keeps its new state due to the inborn "inertia force". **But the force itself cannot do anything without its application with a certain speed.** Then we introduce a notion of action as a product of acting force F_A and the speed of action V_A.

We offer a law of interaction, which determines the interaction between action of the cause and the effect appeared during this action as a reaction, i.e. the product of the force of reaction F_R and the speed of reaction V_R. Thus, this interaction between the cause and the effect is determined by the transfer of action from one object to another in equal quantity, but with appearance of new quality, which is determined by specificity of interacting objects according to fundamental law of interaction:

$$\mathbf{F_A V_A = -F_R V_R.}$$

Unfortunately, an incorrect interpretation of interaction manifestation as an opposite counteraction became strong in our mind. This manifestation is perceived as a compensation of cause by action of the effect. Moreover, the incorrect way of writing of the mathematical form of Newton's third law manifestation established in textbooks and scientific literature due to the incorrect translation as $F_A = -F_C$. This very tragic situation for the science suppressed the development of logic in description of processes. Chance and statistic approach to the description of phenomena has taken place in our perception. This approach is based on the model of non-interacting elements, in which there is no order stipulated by the interrelation of elements. The science has developed this model and its properties, and this fact predetermined the evolution of notions about real World.

This ideology penetrated in mathematics, which for sake of physics began to study properties of objects, but not operations with them. Moreover, a possibility to reflect specific character of real physical processes in the interconnection of cause-effect relations by mathematical operations is not realized. It is essential, that fundamental law of interaction establishes manifestation and description of elementary act of cause and effect interrelation, **the law of manifestation of a Fact.** It means that order in the World is conceived through manifestation of concrete facts. The action of law of interaction lies in the basis of these facts.

So, there is a conclusion: the World is perceived through the discrete manifestation of motion forms evolution. Hence, the discrete mathematics of finite discrete aggregate can be applied to describe the World, but not the continual mathematics, which lies in the basis of traditional orthodox physics. All these circumstances lead to numerous problems and difficulties in description of our notions of reality, to the plenty of used principles, which are in contradiction to each other, as R. Feinmann noticed once [3].

And what we can get from determinism, which is based on fundamental law of interaction, law of cause and effect interrelation? **The change of force value in a reaction takes place, i.e. the change of value of the potential gradient, i.e. the change of energy**

concentration. This circumstance is visually demonstrated by the operation of Archimedean lever as well as in all phenomena of the real World. This is Archimedean lever, where the loss of speed takes place, but there is a gain in force. And the load raised on a lower height than the way, which was made by the applied force, will give a huge power during its free fall. This power is higher in so many times, in how many times the time of the load fall is less than the time of action spent on its raising! And this is the fact, which determines specific character of **creation in the real World**. We should attribute both quantitative and qualitative characteristics to energy. This is the side of energy manifestation, which is reflected in Plank's formula: energy is proportional to frequency.

Manifestation of fundamental law of interaction also lies in the basis of general universal regularity of evolution of real many-particle systems with the change in external conditions. This process develops in multistage way, and on the each stage the logarithm of the ratio between the event happened and the event to happen always is equal to the work of external forces. In other words, the relation of the event happened to the resource is in exponential dependence on the initial conditions and extent of external influence. Exponential character of development of processes is the evidence that Nature develops according to the law, which conserves itself during evolution. This regularity, which manifests everywhere, can be naturally called **the Principle of Order.**

Fundamental law of interactions and Principle of Order appeared to be enough to describe and understand phenomena in the observed World. And it is natural to expect that this principle of Nature manifest in finer World also. This World includes lower and higher frequencies, which are not available for us yet to watch this wide-range frequency-wave emanating Universe.

From all aforesaid we should make a conclusion that the logic, which exists in the traditional physical tool, appeals to the model and principles of the World of non-interacting elements using the range of regularities, which also reflect some features of the real World, but they do not include fundamental law of interaction and Principle of Order, which are necessary and sufficient to describe reality. Descriptions existing in traditional physics are phenomenological ones and concern only those aspects of the phenomena under investigation, which do not include possible qualitative changes during development of processes, because the main property of real processes of interactions (creation of new energy property) was excluded.

The current situation in physics had a strong influence on formation and development of other sciences, other fields of knowledge, since the logic of reflection of cause-effect links was initially excluded. These are the links to determine existence, i.e. existence of constant creation of the World. All these circumstances give grounds to fundamentally revise educational programs, first of all, in physics, philosophy, mathematics, chemistry and biology. A change to the offered logic of cognition, which is based on the Principle of Order and fundamental law of interaction, will fundamentally change our notions about the World as well as will open big opportunities for new technique and technology. A Man has got huge opportunities in cognition and existence, but due to his immorality and features of incorrect aims in the logic of cognition he cannot use these gifts of Nature. We present wider and deeper view on the World and a Man in it, which allow analyzing, watching and operating with those fields of reality, which manifest in finer World, World of higher-frequency energies and other structures of fields. Logic of cognition had not touched these structures yet.

References

1. Galilee Galileo. Selected works in 2 volumes. M.: Nauka, 1964.
2. Newton Isaac. Mathematical principles of natural philosophy. News of Nickolaevskaya Marine Academy, issue IV, V, Petrograd, 1915-1916. Volumes I, II and III, 620 p.
3. Feinmann Richard. Character of physical laws. M.: Nauka, 1967, 160 p.

Old New Energy

Y. I. Andreev, A.P. Smirnov

St.Petersburg, Russia
E-mail: science@shaping.org
Internet: http://www.physical-congress.spb.ru

Two kinds of energy, accumulated energy [1] and free energy [2], are considered as an inexhaustible source of natural energy created by Nature itself. It is ecologically clean and possible to be renewed in natural conditions.

The energy accumulated in substance is released as a result of partial decay of substance in elementary particles. At that, the acquired defect of mass is so small that it does not change chemical properties of substance and is compensated in natural conditions. Physical mechanism of energy-release lies in the fact that an electron in plasma layerwise takes sufficiently smaller elementary particles (electrino) from positively charged atoms or fragments of substance (ions). Electrino give their kinetic energy to plasma, heat it up and move beyond the bounds of reaction zone in the form of thermal and optical radiation. There is no substance, which could not take part in such process of energy-release, i.e. phase transfer of higher form (PTHF). The most appropriate, available and low-cost substances are air and water, which play the role of nuclear fuel in PTHF. It is turned out that usual combustion is also a process of PTHF, in which oxygen is a nuclear fuel and organic fuel is a donor of electrons. In the process of combustion oxygen atoms get the defect of mass equal

concentration. This circumstance is visually demonstrated by the operation of Archimedean lever as well as in all phenomena of the real World. This is Archimedean lever, where the loss of speed takes place, but there is a gain in force. And the load raised on a lower height than the way, which was made by the applied force, will give a huge power during its free fall. This power is higher in so many times, in how many times the time of the load fall is less than the time of action spent on its raising! And this is the fact, which determines specific character of **creation in the real World**. We should attribute both quantitative and qualitative characteristics to energy. This is the side of energy manifestation, which is reflected in Plank's formula: energy is proportional to frequency.

Manifestation of fundamental law of interaction also lies in the basis of general universal regularity of evolution of real many-particle systems with the change in external conditions. This process develops in multistage way, and on the each stage the logarithm of the ratio between the event happened and the event to happen always is equal to the work of external forces. In other words, the relation of the event happened to the resource is in exponential dependence on the initial conditions and extent of external influence. Exponential character of development of processes is the evidence that Nature develops according to the law, which conserves itself during evolution. This regularity, which manifests everywhere, can be naturally called **the Principle of Order.**

Fundamental law of interactions and Principle of Order appeared to be enough to describe and understand phenomena in the observed World. And it is natural to expect that this principle of Nature manifest in finer World also. This World includes lower and higher frequencies, which are not available for us yet to watch this wide-range frequency-wave emanating Universe.

From all aforesaid we should make a conclusion that the logic, which exists in the traditional physical tool, appeals to the model and principles of the World of non-interacting elements using the range of regularities, which also reflect some features of the real World, but they do not include fundamental law of interaction and Principle of Order, which are necessary and sufficient to describe reality. Descriptions existing in traditional physics are phenomenological ones and concern only those aspects of the phenomena under investigation, which do not include possible qualitative changes during development of processes, because the main property of real processes of interactions (creation of new energy property) was excluded.

The current situation in physics had a strong influence on formation and development of other sciences, other fields of knowledge, since the logic of reflection of cause-effect links was initially excluded. These are the links to determine existence, i.e. existence of constant creation of the World. All these circumstances give grounds to fundamentally revise educational programs, first of all, in physics, philosophy, mathematics, chemistry and biology. A change to the offered logic of cognition, which is based on the Principle of Order and fundamental law of interaction, will fundamentally change our notions about the World as well as will open big opportunities for new technique and technology. A Man has got huge opportunities in cognition and existence, but due to his immorality and features of incorrect aims in the logic of cognition he cannot use these gifts of Nature. We present wider and deeper view on the World and a Man in it, which allow analyzing, watching and operating with those fields of reality, which manifest in finer World, World of higher-frequency energies and other structures of fields. Logic of cognition had not touched these structures yet.

References

1. Galilee Galileo. Selected works in 2 volumes. M.: Nauka, 1964.
2. Newton Isaac. Mathematical principles of natural philosophy. News of Nickolaevskaya Marine Academy, issue IV, V, Petrograd, 1915-1916. Volumes I, II and III, 620 p.
3. Feinmann Richard. Character of physical laws. M.: Nauka, 1967, 160 p.

Old New Energy

Y. I. Andreev, A.P. Smirnov

St.Petersburg, Russia
E-mail: science@shaping.org
Internet: http://www.physical-congress.spb.ru

Two kinds of energy, accumulated energy [1] and free energy [2], are considered as an inexhaustible source of natural energy created by Nature itself. It is ecologically clean and possible to be renewed in natural conditions.

The energy accumulated in substance is released as a result of partial decay of substance in elementary particles. At that, the acquired defect of mass is so small that it does not change chemical properties of substance and is compensated in natural conditions. Physical mechanism of energy-release lies in the fact that an electron in plasma layerwise takes sufficiently smaller elementary particles (electrino) from positively charged atoms or fragments of substance (ions). Electrino give their kinetic energy to plasma, heat it up and move beyond the bounds of reaction zone in the form of thermal and optical radiation. There is no substance, which could not take part in such process of energy-release, i.e. phase transfer of higher form (PTHF). The most appropriate, available and low-cost substances are air and water, which play the role of nuclear fuel in PTHF. It is turned out that usual combustion is also a process of PTHF, in which oxygen is a nuclear fuel and organic fuel is a donor of electrons. In the process of combustion oxygen atoms get the defect of mass equal to 10^{-6} %, which constitutes the so small value that it cannot change chemical properties of oxygen and does not call killing radioactive emanation.

There is a possibility to use energy properties both of oxygen and nitrogen of free air in the process of PTHF. To do this it is necessary to destroy nitrogen molecule at least in atoms or smaller fragments by some initiating influence. It is achieved by electrical discharge, magnetic flow, explosion and other means. These means consume much less energy than produced in PTHF. In particular, such processes were achieved in combustion engines. Such nitrogen mode of operation and combustion is accompanied by oxidation to H_2O, but not to CO_2, which is more effective in energy and ecological aspects. Accordingly, the power of engine increases and organic fuel is saved. Exhausts from this process mainly contain water vapor [3].

PTHF processes with excessive power release (more than consumed power) were also obtained in heat-generators operating with water.

Free energy diffused in the surrounding space could be transformed into mechanical, electrical or another kind of energy by means of vibration-resonance, electromagnetic and other energy systems. Classification of these systems as well as physical mechanism of energy transformation is given in [2]. The known Searl's engines can serve as an example of energy systems working with free energy.

The developed physical mechanisms of energy-release processes will allow to create industrial, stably operating, ecologically clean energy systems, which do not consume organic and nuclear kinds of fuel, harmful for humankind.

References

1. Andreev Ye.I., Smirnov A.P., Davydenko R.A., Klucherev O.A. Natural enegetics. – SPB, Nestor, 2000, 126 p.
2. Andreev Ye.I., Andreev S.Ye., Glazyrin Ye.S. Natural energetics –2. – SPb, Nevskaya Zhemchuzhina, 2002, 104 p.
3. Patent 2179649, Russia, 2000 / Andreev Ye.I., Smirnov A.P., Davydenko R.A.

On General Nature of Forces



Dr. Evgueni D. Sorokodoum

Entrepreneur and General Director, Vortex Oscillation
Technology Ltd, Volochaevskaya Street, 40-B, Flat 38,
109033, Moscow, Russia
Telephone: 7-095-362-8084
e40dum@dol.ru http://vortex.viptop.ru

Introduction

In techniques and in our life we got used to certain physical notions concerning force. We usually use these notions in creation of automobiles, airplanes, rockets and other techniques, but we don't think about **the origin of forces** in general. Usually appearance of force in continuum is connected with presence of momentum gradient.

A number of works, which describe various versions about origin of a force appeared [1, 2, 5, 8, 17, 21, 22, 23, 25, 30, 35, 36, 38, 39]. Different mechanisms of appearance of force are considered in these articles. Usually they consider origin of a force in one of the fields, which are: electromagnetic, gravitational and others. **There was a theoretical attempt to connect the force initiation with energy gradient [33]. Experimental proof of force initiation due to energy gradient was obtained in the works [7, 38].**

Below we made an attempt to show the general regularity of force initiation, which is connected with non-uniform distribution of energy in space. With this process, physical nature of any kind of energy and specific mechanism of force initiation does not play any role. These are only particular cases of general nature of force initiation.

General nature of forces

We are surrounded by space, which is full of energy. Here we mean the energy of any nature: mechanical, thermal, electromagnetic and others. Energy is related with material world and its value is connected with the volume.

Any particle (volume) of continuum has energy:

$$A = A(x, y, z, t) \qquad (1)$$

where *x, y, z* are Eighler's coordinates of the center of particle, *t* is time.

Transmission of energy from one point of space to another one can take place by various methods, both in connection with energy transmission by material particle itself (which is a "carrier" of energy in this case) and without such transmission (for example, with wave motion). For the volume degenerated in ideal point the energy will be zero. That's why it is more comfortable to operate with the energy density concluded in the increasing constantly. We are the first who analytically got the law of gravity of the masses from the known equation of thermal conductivity. Appeared that on the relatively small distances (in the bounds of the Sun System) the law of gravity by Newton remains valid, but on the larger distances the sudden decrease goes on (Gauss integral), which naturally solves the famous Zelinger's paradox of gravity.

As a conclusion we should note that in the bounds of a stable galaxy of a spiral kind there is the circulation of ether. Ether moves from the periphery of the galaxy to its center (nucleus) by two spiral branches. This becomes apparent as a weak magnetic field (8-10 micro Gauss). In the nucleus of the galaxy there is the impact of two strings as well as there is formation of the spiral toroidal circles (protons). Then the protons form the adjoined vortexes around themselves (electron shells) and from the proton- hydrogen gas the stars are forming, which are moving to the periphery by the same branches. There they dissolve in ether at the periphery since the protons will loose their energy and stability due to the viscosity. Ether which have got the freedom will return to the nucleus of the galaxy and this process is going on in our galaxy for hundreds milliard years and it will keep going until the new center of vortex formation will begin to concentrate ether. Then the new galaxy will appear and our galaxy will disappear. But it will not happen soon and we have enough time to understand that we should return to the concept of ether in modern science.

Experimental Demonstration
of Cosmic Influence on the Earth Life in N.A. Kozyrev's Researches
("On the Influence of Time on Matter")

Alexandra L. Belyaeva

Bishkek, 720075, Russia 8th Location, 46, apt.80
Tel.: 7-996-31-41-25-79
E-mail: artem_belyaev@mail.ru
Internet: www.newphysics.h1.ru

Editor's note: this article represents a part of the big scientific conception "World models in the new scientific progress". On applying of this conception a great number of practical technical devices have been created (as an example of such device we offer the description of universal electrical bio-heater, which was created by the group of researchers from Bishkek, Kyrgyz Science Technical Center "Energy" during the *work on ceramic electroconvector).*

We have to note that the position of our editorial board concerning "time" and Kozyrev's work is not in a good correlation with the authors' one.

Nicolay Alexandrovich Kozyrev scientifically and experimentally discovered the action of relations' interconnection, which was falsely named as time. Time cannot cause action because it is absolute and does not have any physical sense (Samat Kadyrov. Monograph "Theory of unified field").

Author's note: relations' interconnection is an interaction of structurally similar objects. It is a nuclear resonant gain-frequency process: in a stationary electric field, which is modeled by systematic organization, there is a development of similar to structural one, in-focus rays of powerful regular coherent radiations. These coherent radiations are determined by properties of chemical components of interrelated substances.

According to N.A. Kozyrev, it is ought to expect not identical density of relations' interconnection in space. Some processes decrease density; others on the contrary increase density of relations' interconnection. Action of the increased density is weakened according to the law of reversed squared distances; it is shielded by a solid matter, at thickness about 5cm, and is reflected by a mirror, according to the familiar optics law. The action of the decreased density on a detector is shielded, but does not reflected by a mirror. Properties of a matter can be changed under the influence of relations' interconnection. In this sense there is a big advantage in changes of electric current conductivity of resistor, which is brought into Witson bridge and is located near some process. For instance, in order to increase density it is useful to realize the process of evaporation of a volatile liquid; and for density decrease the process of cooling of a warmed-up agent can be realized. Due to these processes, change of conductor resistance is actually realized with opposite signs. Increase of density of the conductor with positive temperature coefficient leads to decrease of its resistance. At negative temperature coefficient there is an effect of the opposite sign, in the direction of changes, caused by temperature changes. Such correspondence to fall in temperature should be observed at changes of other properties of a matter, **because disorder in a matter structure is reduced along with fall in temperature**. The researches have shown the following results at the resistor, which was situated near processes of acetone evaporation on cotton wool and of solution of sugar in water. The relative resistance change of resistor was observed at the 6th or 5th digit after comma (or even at the 4th digit if resistors had especially high temperature coefficient).

There is now a possibility to study the Universal World not only by means of the investigated spectrum of electromagnetic oscillations, but also through physical properties of relations' interconnection.

At many researches the influence of relations' interconnection on resistor electroconductivity was investigated. Acetone evaporation (at 10-15 cm distance from the resistor) was applied there as the process, which controls sensitivity of a system. However, the process of evaporation can influence on the resistor not only with density increase, but also due to temperature increase that occurs at evaporation. In order to take into consideration this cooling effect, (in the area of evaporating acetone) temperature was measured by Beckman mercurial thermometer with 0.01°C multiplying factor. The first experiments (without thermal protection) have shown the fall in temperature by several hundredth of degree. This fall was enough to cause the changes of resistor electroconductivity. However, the thermometer had been keeping on the demonstration of practically the same fall in temperature at thermal insulation of the resistor. The thermometer reacted on the radiation of relations' interconnection at acetone evaporation.

The part of the thermometer with a placed in a pasteboard tube mercury tank was laid round with cotton wool and put into a glass retort. The experimental process was fulfilled near the retort, and the reading of mercury altitude in capillary was determined by the scale of the thermometer through the closed window in the next room. The mercury altitude was decreased at dissolution of sugar in water (with steady temperature) and it was increased at the release of the squeezed spring, which was placed near the thermometer.

The radiation of the relations' interconnection was observed from many stars. It is caused by the inner processes, which take place on these heavenly bodies. The Sun (with its turbulent processes) radiates the relations' interconnection besides the searched electromagnetic radiation. Actually, if sunlight is recovered with a thin screen, the significant influence on the resistor will be discovered. The influences of the Sun to the Earth through the relations' interconnection become doubtless. These influences of the Sun should have a particular significance in vital functions of organisms, because it brings the beginning for life support. The totality of the researches demonstrates the dependence of matter state from the changes of the general background of the relations' interconnection. The drift of the devices (that show daily changes) usually stops about at midnight and then changes its direction. As for the seasonal course, there is a density decrease of the relations' interconnection in spring and summer; and there is an increase of it in autumn and winter. It is connected with the absorption of the relations' interconnection by the vital functions of plants and with the return of it at their fading. There are indications at the seasonal changes of chemical processes. For instance, reaction of polymerization has more difficulties in its realization in springtime. V. Zhvirilis observations of minimum and maximum light admission by means of the crossed Nickolya prisms can be explained by the crystalline reconstruction of these prisms.

By Kozyrev, as being invisible, vital source is disseminated everywhere in Nature, thus possibility of its accumulation is the only necessary thing. Such a possibility is realized in vital organisms because all vital functions counteract to the usual course of systems' destruction. The ability of organisms to keep and accumulate this counteraction is the reason, which determines the great role of biosphere for the Earth life. But even if we assume, that spreading of life in Space is one of its peculiar properties, biosphere will not have a decisive significance.

Cosmic bodies (and first of all stars) can serve as the reservoir, which gathers vital source. Enormous stocks of energy flow out of stars in a very weak degree through the radiation of comparatively cold external layers. Inner stars energy is preserved so well, that even at the lack of supplement, matter of the Sun would become cold only at one third degree per year. For the Universe the creative source carries the relations' interconnection. Thus cosmic bodies are necessary for support of life.

Author's note: We apprehend relation's interconnection as natural radioactive background. In fact, it is a nuclear resonance gain-frequency interaction of inertial masses that depends on living systems, especially on its rituals and that regulates its survival. Cosmic bodies regulate this process. Humanity is able to control nature only obeying to natural laws. In-focus beams of powerful laser streams are formed in the electric field of living system organisms. The creation of proton-antiproton pair in the living cells, alongside with the process of the absolute release of energy serves as a creative vital force. The process of radiation, support, absorption of energy by the organization (assembly of particles) is realized through the relation's interconnection and regulates its total mass.

Humanity is able to control nature only obeying to natural laws.

Life without Diseases and Old Aging Preventive Electrical Heater with Programmed Features

Alexandra L. Belyaeva

Bishkek, 720075, Russia 8th Location, 46, apt.80
Tel.: 7-996-31-41-25-79
E-mail: artem_belyaev@mail.ru
Internet: www.newphysics.h1.ru

Universal electrical bio-heater is intended for heating of rooms and preventive clearing of an air atmosphere from disease-producing organisms at continuous exposition (continuous work). The principle of its work fundamentally differs from those of the existing analogues. Carbon crystals are in the basis of bio-heater, which makes it environmentally appropriate.

Bio-heater represents a range of ceramic cylinders, jointed with metal plates on top and underneath. These plates play the role of load-carrying structure. It is used in production areas and living rooms for heating alongside with destruction of pathogen microorganisms. One bio-heater with 0,2 kWtt power is oriented for heating of the area with volume 35-45m^3 (in the future production of modernized models powered from solar cells is planned).

As distinct from the usual oil heater, preventive electrical bio-heater destructs agents of infectious diseases, whereas, according to the researches, oil heater stimulates their reproduction.

Absolute ecological cleanness is obtained by release of the quarters from the effect of increased atmospheric dampness with the temperature, appropriate to sanitary code. Any type of mold or fungus disappears in the quarter and in the future these forms do not renew their existence (even after removal of bio-heater).

The absence of injurious radiations is attained by the following: features of raw material, which is used during the process of electrical bio-heater production; radiation is normal during bio-heater working. Pollution-free temperature influence is attained by favorable infrared radiation.

Among the other properties of electrical bio-heater there are following: fire-safety; explosion proof; chemical inertness; enormous effectiveness from the point of view of electric energy demand. Structural simplicity facilitates its durability; there is nothing in bio-heater to be broken.

Technical aspects (applied Know How): In the process of technologic production of ceramic cylinders, from which bio-heater is consisted, **diamond-like cellular ceramic structure** with superimposed combination of atoms of lattice elements is created. Rhythmic work of cells, which form ceramic mixture, leads to resonance and creates a kind of blow wave (at micro level). This blow wave physically destroys microorganisms that have no calcium framework. It is related only to those microorganisms that are agents of infectious diseases, such as: staphylococcus, enterococcus, enterobacterium, etc. Thus parameters of the evoked blow wave coincide with vibration frequency of the definite types of bacterium and elementals. These blow waves cause the similar effect in room near of bio-heater, e.g. colonies of microorganisms are noticeably decreased there (even at the absence of bio-heater in the nearest room).

Due to its self-organization, bio-heater works in the range of living systems, it is approached to them. There is a realization of active connection with living coaly forms of biological systems. Actually the work of bio-heater is adjusted to them. Bio-heater properties can be programmed at the process of its production.

Bio-heater is a patented product. Patent KR #464 MKI C 04 V 33/24 “Ceramic mixture, possessing heat-radiating properties”. Application #20010075.1 at Patent KR #464 MKI C 04 V 33/24 “The way of creation of energy, renewable, programmed hard-phase ceramic-carbon mass structure”. Application at Patent KR #464 MKI C 04 V 33/24 “Technology of producing of electrical heaters with anti-resonant air prophylactic effect”.

Finale product (FP) purchase is not more expensive than those of existent models of electrical heaters. Cost value is noticeably brought down on organization of the scaled production. It is ought to take into consideration that from all existent types of heating, from the customer’s point of view, this one is the most energy-efficient. Manufacturing of such bio-heaters can be organized on the base of acting industrial production of ceramic fabrics. It will require some expenses. Moreover production service is rather cheap because there is no need in maintenance staff.

Electrical bio-heater can be applied everywhere, where there is a need in: a) economical heating; b) decrease of air moisture; c) disinfections of rooms.

As for the life cycle of bio-heater it does not become obsolete morally and technically. It is produced from the materials, which are not liable to wear.

The invention has a certificate of KR Gosstandart. From the end of 1998 the first unimproved modification of bio-heater (with power 0,6 KWtt) were put into serial production in Bishkek (with small test production runs). This time bio-heaters are readily used as medical equipment in hospitals and maternity hospitals in Bishkek. **Inventor: Alexandra L. Belyaeva.**

Technical Report

The comparison of quantity of heat energy, required for heat of rooms, and of heat quantity, which is produced by Belyaeva's electroconvector.

Mavlyanbekov Sh.Yu.

Deputy Director KSTC "Energy"
Internet: www.newphysics.h1.ru

Editor's note: this calculatious demonstrates the advantages of the device, which at 340 Wtt energy consumption produces about 700 Wtt of heat power.

The calculation of heat output, coming from the ceramic electroconvector to a room, was based on the basis of research statement of EVNA-0.2/220 electroconvector's influence on air micro flora of industrial rooms at 23.10.01. - 06.11.01. period.

The researchers were carried out in the arbitrary room in a four-storied large-panel building. This room was on the 3rd floor, with facing east windows. The room was of 52.5 m^3 air-space, 3.5 m height and 15 m^2 area. The calculation of heat, was made on the basis of "Methods for calculation of the requirement in heat and electric energy of buildings". These methods were registered by Department of Justice of Kyrgyz Republic on 08.09.2000, #154. According to the normative data, temperature of inner air (t_{in}) in the room must be equal to +20° C. In Bishkek planned specified temperature of external air (t_{ex}) for heating is minus 23°C. The average temperature of heating period is t_{av}= -0.9°C, specific heat characteristic of the building is:
q=0.4 Kcal/m^3 h °C.

Medium quantity of heat energy, which is required for heating, is determined by the formula:

$$Q_{av}heating = q \cdot V \cdot (t_{in} - t_{ex}) \cdot 1.12 \cdot$$
$$\cdot [(t_{in} - t_{av}) \div (t_{in} - t_{av})] \text{Kcal/h}$$

$$Q_{av}heating = 0.4 \cdot 52.5 \cdot (20+23) \cdot 1.12 \cdot$$
$$\cdot [(20+0.9) \div (20+23)] = 492 \text{Kcal/h}$$

Thus at the average annual temperature of the heating period, which is: t_{av}= - 0.9°C, the quantity of heat energy required for this room, comes to 492 Kcal/h.

According to the research statement, the trials of the electroconvector with 200Wtt power were carried out at the following external air temperature: +10.2°C; +8.5°C; +10°C; +6.6°C. The calculation data and results of its examination are brought together in a table. The parameters of electroconvector with 340Wtt power are demonstrated in the same table.

Table 1
Table of determination of heat entry and heat consumption's correspondence in the experimental room

#	External air temperature, °C	Inner air temperature °C	Normative heat consumption KWtt (Gcal/h)	Experimentalheat consumption KWtt (Gcal/h)	Percentage depending on normative heat consumption %	Economy of heat energy kWtt (Gcal/h) comparing with power consumption of the device 0.2 kWtt (0.000172 Gcal/h)	Economy of heat energy kWtt (Gcal/h) comparing with power consumption of the device 0.34 kWtt (0.000292 Gcal/h)
1	- 0.9	+20	0.572 (0.000492)		100	-	
2	+10.2	+20	0.267 (0.00023)		100	-	
	+10.2	+16		0.158 (0.000136)	59	0.2-0.158=0.042	0.34-0.158= =0.182
3	+8.5	+20	0.314 (0.00027)		100		
	+8.5	+17		0.233 (0.000200)	74	0.2-0.233=-0.033	0.34-0.233= =0.107

4	+10	+20	0.273 (0.000235)		100		
	+10	+23		0.355 (0.000305)	130	0.2-0.355=-0.155	0.34-0.355= =-0.015
5	+6.6	+20	0.366 (0.000315)		100		
	+6.6	+19		0.338 (0.000291)	92	0.2-0.338=-0.138	0.34-0.338= =0.002

Calculation data demonstrate a considerable economy of heat energy at daily unevenness of external air temperature.

Heat productivity of the new structure of electric convector with 340Wtt power was calculated on the assumption on the suggestion that heating of the room is carried out by the irradiation at the process of heat exchange.

$$E = \varepsilon \cdot C_o \cdot T^4 \cdot 10^{-8} \quad \text{Wtt/m}^2$$

where: C_0 =5.67 Wtt/m^2 K^4 is a radiant emittance of blackbody, ε=0.93 is an emissitivity factor of the surface of earthenware duct tube; T=70°C=343 K is the temperature of the surface of earthenware duct tube.

On substitution of the known values into the formula we get:

$$E = 0.93 \cdot 5.67 \cdot 343^4 \cdot 10^{-8} = 727 \quad \text{Wtt/m}^2$$

As the area of irradiation surface is equal to S=0.96 m^2, then quantity of heat, which is evolved by the convector, comes to:

$$E_k = S \cdot E = 0.96 \cdot 727 = 698 \quad \text{Wtt (or 600 Kcal/h)}$$

The quantity of heat, which is required for the heating of the room, is 492 Kcal/h (at the external air temperature equal to minus 0.90 and temperature in the room equal to plus 200).

Thus, electric convector with 340 Wtt power is able to heat totally the room with 60m3 area.

Editors note: 340 input and 700 output!!!

Longitudinal Waves in Vacuum: Creation and Research

Ph. Dr. Kirill P. Butusov

190121, Saint Petersburg, Angliysky prospect, 5-18
Tel: (812) 113-8511

The author presents a new elegant system, which is the symmetrized Maxwell's equations. In practice it gives a possibility to create the longitudinal waves in vacuum. This system is of great importance in telecommunications and aerospace technigue.

There is a stable paradigm in electrodynamics that the existence of the longitudinal waves in vacuum is impossible. This paradigm played its negative role preventing scientific minds from solving this problem. However, Maxwell was not as categorical in his opinion on this question as his following were.

Particularly he wrote: "Science of electromagnetism as well as optics is not able to confirm or deny the existence of longitudinal oscillations."

Maxwell's dynamic equations are usually considered as partial derivatives in time. However, the total derivative in time includes the so called substantial derivative, which was shown in the equations for the moving coordinate system. In particular, one of these equations was written by Maxwell himself to explain the phenomenon of electromagnetic induction discovered by Faraday. This induction takes place in the conductor moving across the field lines of electromagnetic field:

$$\vec{E} = \vec{V} \times \vec{B}; \qquad \text{(I)}$$

Other equations were obtained later by other scientists. In the table I below Maxwell's equations are given in a split form. Their static and dynamic parts are given separately as well as the equations for moving and fixed coordinate systems. Such matrix concept of Maxwell's equations allowed finding their incompleteness. Really, the analysis of the matrix shows its high symmetry. However, full symmetry of the system of equations is broken by the absence of the equation (X). It seems to be strange and calls a desire to remove this defect in such an elegant system of equations.

A new equation is introduced in the Table 1 for the full symmetry of the matrix:

$$\nabla \cdot \rho = -\frac{1}{c^2} \cdot \frac{\partial \vec{j}}{\partial t}; \qquad \text{(X)}$$

Fundamental Properties of Aether

Alexander M. Mishin

Author's note: In the article the principles determining major properties of aether are formulated on the basis of an empirical material.

Real aether [1-6], the primary and superfine essence of which is still a secret, has turned out to be absolutely non-standard superfluid three-dimensional material medium, which simultaneously is at solid, liquid and gas phases. The first master phase of aether is a specifically solid absolute space or an energetical "bottom" of the Universe ("celestial stronghold"). At that the solid phase is considered as mesomorphic vortical-wave structure, which has particular holographic properties. Classical matter represents to be one of the stable and energetic space-time levels of the Universe. Aether vortexes exceed all conceivable space scales, have quasi-material properties and create a great number of stereo-dynamic subspaces (parallel worlds).

The first basic principle, to which aether entirely follows, is the principle of the least disturbance (the least action). Many well-known and unknown physics laws are the subsequent of this principle. In particular, any motion in macroscopic aether happens in such a way to minimize the interaction with the matter of our world, with zero moment of the disturbance momentum. In the classical physics this principle has been reflected as Le Shatelye principle, as variation principle, laws of thermodynamics etc.

The second principle is the principle of fractality, which confirms the similarity of forms and properties of quantum aether vortex structures regardless of their space scale. This principle also determines the Universe as stereodynamically multivariate system in the form of hierarchy of vortical-wave structures of the unified aether (fractal matreshka). On the researching of the macroscopic objects of the Universe it is possible to make a conclusion about microcosm structure if taking into account the changes of frequencies and velocities of action transmission.

In the third place there is a principle of physical autonomy, which confirms that any solitary mass (for example a planet) creates aether system. The particular principle of relativity, which reflects one of the fractal properties of the Universe, can be applied to this system. Such autonomous mass becomes similar to the miniuniverse with its aether subspaces, which repeat the basic phases of the Universe spectrum in more narrow (which depends on the size of mass) frequency band of space-time frequencies. Thus, in the local system of the Earth solid aether reproduces the structure of gravitational field with energy "bottom" in the mass center. As the result such spherical body occurs to be an energy drain and warms up from within.

The fourth is the principle of interaction between matter and vortex-wave forms, which do not depend to the spectral part of the Universe, that is quasimatter. This is the principle of new interaction in nature. The value of energy interaction in each experiment diminishes in time according to exponential law that is explained by the forming of energy informational or adaptation barrier, which separates parallel worlds and reflects the properties of vortex tenacity of aether as superfluid medium. At that, time of interaction is proportional to the size of quasimatter and the barrier for the earthly conditions is lowered at the indefinite period, on the assumption of only thrice-repeated observation of forces (triad law).

According to this principle, aether dynamic experiments in the earth laboratory do not have classical repeatability that, from the one hand, gives occasion to doubts in the objectivity and scientific character of the non-traditional experiments and from another hand it is the most reliable test feature of macroscopic aether motions. Biosystems have special relations with this principle.

The fifth is the principle of many-dimensional autobalance of forces. All vortex and linear motions of macroscopic aether organize themselves in the way that in the band of space-time spectrum of the local system (usually with the aid of fluid and gas aether) occurs to be self-balanced, that is they have zero resulting impulse and the moment of impulse due to the existence of the proportionate antivortexes and antistreams of another spectral structure at the same space volume. The self-balanced vortex structures and streams are practically closed for the outer watch from the direction of our material world, at least with respect to the methods of classical physics. The principle of autobalance of forces reflects aether properties as unified synergetic system and has a significant applied meaning.

Let call the principle of viability of aether dynamic systems as the sixth principle. Only a stereodynamic multivariate system is a viable one, that is a system, which during a definite period of time has the opportunity, called as life cycle, to realize interconcerted self-oscillating processes of vortex-wave character simultaneously at different phase states (subspaces, layers) of aether. The most important features of such a system are its space-time quasimaterial (vortex-wave) broadbandness and finite time of existence, which is determined by the conditions of creation of the energy-informational barrier. Self-oscillation regime demands the presence of an energy source, oscillatory circuit (a pendulum) of any character, intensive process (of negative tenacity) and a channel of positive feedback (negative entropy).

In the sense, referred above, any material system is viable and occurs to be a big system in the form of coordinated community of multivariate subsystems. In its turn each big system as a part of the hierarchy is a constituent of bigger system, until everything is embraced by the Biggest System, that is the Universe.

The seventh principle of the universal energy interchange is the physical realization of the law of unity and struggle of oppositions. This principle determines spontaneous creation of thermodynamic and antigravitation potentials. Any local matter mass (a body), situated in the open space, creates an exchange process with the surrounding aether volume in the way that more fine-structure fluid aether is absorbed by the body, and the less power-consuming gas aether is radiated. As the result the body as a heat engine gets energy due to the cooling of aether exteriors. At that, antigravitation forces acts between bodies and aether exteriors, which have different temperature.

This principle, which establishes the existence of antipodes of the second law of thermodynamics and Newtonian attraction, is realized mainly in cosmic scales and explains in which way the energy is created in the bowels of planets and stars and why the Universe is stable as regards to gravitation. Obviously, the most unexpected for the modern Physics is the discovery of non-traditional nuclear processes where conditional reactions of decay and fusion occur at the usage of quasimatter.

More deep research of new experimental results and of the stated above scientific principles lets to determine the priority-driven strategic tendencies in Physics, to open more entirely the laws of mechanics and thermodynamics of many-dimensional aether, including the theory of non-traditional waves and new types of electromagnetism. At that, the supreme aim is the research of differences in aetherodynamics laws on the Earth (in a laboratory) and in outer space, the unknowing of these differences has caused logical insularity, false all-sufficiency of classical physics, which had refused as "not wanted" the aether conception and fundamental Universal laws.

References

1. Mishin A.M. On the new properties of physical vacuum, gravitational field and mass. DD USSR, 1988, p. 44
2. Mishin A.M. Experimental results on the registration of aether wind // New ideas in Natural Sciences. Series: Problems of research of the Universe, issue 18. – SPb: RAS, 1995, p. 24-33
3. Mishin A.M. The Aether Model as Result of New Empirical Conception. New Ideas in Natural Sciences. (On materials of the International Conference). Part I – SPb: RAS, 1996, p.95-104
4. Mishin A.M. The physical system of artificial biofield // "New Energy Technologies" – SPb: Faraday Labs Ltd, 2001, issue #1, p. 45-50
5. Mishin A.M. Antigravitation and new energy processes // "New Energy Technologies" – SPb: Faraday Labs Ltd, 2001, issue #2, p. 37-41
6. Longitudinal thermomagnetic effect // New Energy Technologies – SPb: Faraday Labs Ltd, 2002, issue #2(5), p. 38-41

Irving Langmuir and Atomic Hydrogen

Nicholas Moller

PO Box 201
34008 Eretria
Greece

Editorial

In this paper Dr. Nicholas Moller describes the history of development of Atomic Hydrogen technologies in details. It is remarkable that this technology can be applied not only for welding processes but also as a clean free energy source. It is important to note that in this case the hydrogen process does not involve a consumption of hydrogen, which is not combusted in the process. Atomic hydrogen is not really a fuel but rather a medium, gateway or a super-conductor of ZPE form the vacuum of space, converting ZPE radiation and ultra-high frequency electrical energy into infrared (heat) radiation.

Irving Langmuir.

This is the story of Irving Langmuir who was the first to develop a theory on Atomic Hydrogen on the basis of empirical research and experimentation. His work in this field lasted from 1909 to 1927. During this period he was employed by the Research Laboratory of General Electric Company. Patents and discoveries developed by Langmuir during his time with General Electric were to a considerable extent instrumental in laying the foundations for what is today one of the largest corporations in the world.

The question that gave birth to this article, is why his work and discoveries on Atomic Hydrogen were the only work that received hardly any attention at all and why his revolutionary breakthrough was deprived of world attention for almost 100 years? This question becomes even more relevant when taking into consideration the high standing he enjoyed with his contemporaries (including being awarded the Nobel Prize in Chemistry) and it is better to make it distantly after exclusion of man presence near experimental stands and devices. At the same time it is quite obvious that on applying of small capacity and fixed time of irradiation it is possible to develop methods for curing of human diseases, which are considered now as incurable (for instance of diabetes, some diseases of haematogenic system, of cancer and possibly of AIDS.

References

1. Proceeding of the International Scientific Conference "New Ideas in Natural Sciences" Problems of Modern Physics, p. 176-187
2. Journal of new energy, Vol. 3, #4,1999, I.M. Shakhparonov "Interaction between Kozyrev – Dirak radiation and radionuclides", p. 85-89
3. Kozyrev N.A. Selected works, Leningrad State University, 1991, part 3
4. Lavrentyev M.M. Eganova I.A. Luzet M.L., Fominykh S.F./ / Reports by AS USSR. – 1990, Vol. 314, #2, p. 352-355
5. Lavrentyev M.M., Gusev V.A., Eganova I.A., Luzet M.L., Fominykh S.F.// Reports by AS USSR. – 1990, Vol. 315, #2, p. 368-370
6. Methodological materials on experimental pharmacological and clinical trials of immune modulating effect of pharmacological remedies. - Ministry of Health USSR, M., 1984
7. Talmadge J.E. and Chiragos M.A. Comparison of immunomodulatory and immunotherapeutic properties of biologic response modifiers. Springer Seminar Immunopathol., 1985, 8, 429-443

Effect of Magnetic Blow Wave Field on Wine Systems

I.M.Shakhparonov (Corresponding author), S.A.Grin,
S.R.Tsimbalaev, L.N.Kreindel, V.N.Kocheshkova,
A.I.Podlesny, S.Yu.Gelfand

AGD Firm, Peschanyi pereulok, House No.20P korpus No.1, Lfl. 33
125252, Moscow, A- 252, Russian Federation

Russian Institute of Canning Industry, Shkolnaya Street. 78.
142703 Vidnoe 3. Moscow Region, Russian Federation

Introduction

Authors communicate the data on influence of Magnetic Blow Wave (MBW) field on several wineproducts. It was found, that MBW did not lead to significant changes in the major components of the wineproduct (sugar, organic acids, minerals). At the same time the taste and aroma of treated wine become more pleasant; content of heavy alcohols and wine stone in the treated samples was less than in non treated ones. A mechanism of transformations was also discussed.

Keywords: *Magnetic Blow Wave (MBW), Wineproduct, GLC of aroma compounds and ethanol, HPLC of sugars, Atomic Absorption Spectrometry (AAS) of minerals, Heavy alcohols and aldehydes, Wine stone, Turbidity tendency, Organoleptic evaluation*

Magnetic Blow Wave (MBW) was obtained for the first time during the investigations on ball lighting generation under the laboratory conditions (Shakhparonov 1994). MBW as a physical object is interesting because of some facts, which suggest that MBW is a magnetic monopole. The MBW can also interact with the matter and transforms it in a definite way. Typical example is an elementary carbon in the form of graphite, which is transformed by such magnetic treatment into ferromagnetic substance (ibid). The graphite, which is initially diamagnetic, transforms to paramagnetic one with general radiation doze of about $7 \cdot 10^{19}$ neutrons/cm^2. Other types of radiations could not affect this way (Svoistva 1975). So one unit of MBW can be considered as $1 \cdot 10^5$ of neutron masses. This fact may be regarded as an indirect evidence for assuming that MBW and magnetic monopole are the same things. In the absence of excited radioactivity a slow MBW [$v/c < 1 \cdot 10^4$] occurs, which does not ionize atoms (Devons, 1963). Therefore, their interaction with the matter can be observed only indirectly. No data exist on the interaction of MBW with organic substances. The experiments and results reported in the present communication may be a starting point for development of technology and to formulate the methods for vintage wine and best quality spirit production.

Materials and Methods

Assuming that MBW and magnetic monopole are the same things, a number of conditions were selected for all experiments. The MBW source and the samples were placed in the same axis and the axis was oriented according to magnetic meridian direction. Such magnetic orientation is appropriate, as the energy of magnetic monopole theoretically increases in a magnetic field (Devons, 1963). All of samples were placed at 250 cm distance from MBW source, in hermetically closed glasses. It should be noticed that MBW could penetrate through many other barriers, for example into cast iron reservoir with wall thickness of 5 cm (Amaldi, 1970).

The quality investigations were made by using of standard equipment. HPLC, equipped with refractometric detector was used for sugars estimation. Separation of organic acids in forms of their ethyl esters and acid esters was carried out chromatographically using a column packed with polyethylenglycol succinate and the following temperature option: initial temperature is 120°C, final temperature is 220°C, temperature growth rate: 8°/min. GLC was also employed for determination of ethanol. Minerals content was examined with Atomic Absorption Spectrometry (AAS). Electronic spectra of samples were obtained with double beams UV Vis spectrophotometer equipped with permanent wavelength scanning. Redox potential was measured with EV-74 potentiometer.

The aroma alterations in the wine samples were investigated by GLC method after preliminary concentration of aromas by solid phase adsorption. The concentration was carried out by barbotation of inert gas (nitrogen) through liquid and consecutive catching of volatiles with tube trap, filled by Polysorb 1 sorbent (Lur'e 1972). The well-known analogue of Polysorb 1 is Porapak Q. The tube may be regarded as a short chromatographic column, and volatiles go through it according to their retention times. The choice of sorbent was motivated by the fact, that retention times of water and ethanol was rather small (ibid). Thus, a concentration process can be ended at the moment, when water and ethanol have passed through the column, as the other volatiles remained bonded. The aroma desorption was made with ethyl ester. The analysis of the concentrates obtained was carried out with gas chromatograph equipped with flame ionisation detector (FID), column 3 m x 3 mm, packed by Carbovax M on the Supelcoport. Temperature for the analysis was programmed from 100 to 190°C with increase of 1°/min. Isothermal conditions in the borders had durations of 2 and 40 min respectively. The "mild" conditions of separation were also employed (initial oven temperature was 80°C with isothermal condition duration 5 min, temperature growth rate 1°/min, final temperature 150°C and isothermal condition duration 40 min).

Optical activity was tested with Spectropol at D line of Na (580 nm). The samples were evaluated organoleptically by a group (12 persons) of workers from Russian Institute of Canning Industry. Turbidity tests were made under the methods of Valuiko et al (1987). In some cases, qualitative tests were completed by MPL turbiditymetric measurements. Before testing samples were filtered. Determinations of heavy alcohols and aldehydes contents were carried out in accordance to National Standard (GOST, 5363-67) as follows below. Determination of the constituents of "heavy spirits"(i pentanol, i butanol) was based on reaction of the sample with salicylic aldehyde in a presence of H_2S0_4. Rose colour develops if sample contains the heavy alcohols. The density was measured with Vis-photometer and the quantative determination was carried out using standard graph made with mixture solution of i pentanol and i butanol. A method for determination of aldehydes content is based on a reaction of fuchsine sulphite. The developed colour was measured with Vis-photometer. Calibrating plot constructed basing on typed solutions was used for quantification.

Results and Discussion

Investigations of wine quality changes after MBW treatment were performed using two samples of portwine ("Zemfira") type wine. Sample 1 was a reference (non treated) and sample 2 was treated with MBW.

In both samples, the fructose and glucose levels were practically the same and amounted to $43.8 \pm 3,32.22.5$ g/*l* respectively. Sucrose and maltose were absent. Total sugar content was 76.0 g/1 though the level marked on the label was 80 g/*l*. It is thus apparent that the treatment of wine with MBW does not lead to noticeable changes of sugars content. Results of organic acids determinations are given in the Table 1.

Table 1
Main organic acids content, g/1

Acid	Treated wine	Initial wine
Lactic	0.0265	0.00187
Oxalic	0.010	0.0088
Succinic	0.209	0.18
Malic	4.56	4.22
Tartric	0.0805	0.0895
Citric	0.401	0.483

Standard deviation for the determination method was estimated as 7 %. This fact shows that differences in organic acids content are not significant. It should be noted that a tendency of slight increase in light acids (up to malic) in the treated wine was observed in contrast to noticeable change in more heavy acids. The ethanol content of both of samples was 181 and 184 g/*l* for non treated and treated samples, respectively, though the label on the bottle indicated 190 g/*l* concentration. Standard deviation was 5 %. Thus, MBW treatment does not lead to significant changes in alcohol content.

Atomic Absorption Spectrometry (AAS) data indicated that the samples were practically identical in terms of K, Na, Ca, Mg, Fe, Cu and Zn contents (data are not shown).

Similarly, spectra of treated and non treated wines, diluted 150 times before photometring, were practically identical, thereby pointed out that polyphenols are unchanged.

When wine is industrially treated with IR or microwave heating, ultrasonic, ultraviolet and g radiation, different reactions occur and there include redox reaction, esterification, condensation, hydrolysis, Maillard reactions, etc (Kishkovsky 1988). Most of reactions are accompanied by redox potential changing. Increase in Redox potential points out the increase in concentration of oxidants, i.e. oxygen, peroxides, and other compounds, which are electron acceptors. Redox decrease is a result of oxidation processes (ibid). Redox potential was practically constant ($\Delta E =$ 145 mV and 150 mV in samples # 1 and 2 respectively). Evidently, oxidation processes, like they occurred during heat treatment, were absent during the MBW treatment.

One of the important reactions to be considered is the Maillard reaction. Essentially it appears in form of browning, decrease in reducing sugars and amino acids, and new aromas formation. While our result evidences on absence of irrelevant aromas, alterations of wine colour, and sugar content, thereby indicating insignificant contribution of Maillard reaction on wine quality changes due to MBW treatment. Technological treatment often leads to esters accumulation that improves wine aroma. It's well known that the most important in this context are the esters of C_6-C_{14} fatty acids (Kishkovsky 1988). During heat treatment, storage and other physical influences, different kinds of acid esters accumulate. These have weaker aroma than esters of fatty acids. But their appearance proves the existence of esterification processes. A comparison of aromas chromatograms of the samples 1 and 2 proves occurrence of changes in concentrations of the individual substances (increasing of peaks length with retention times of 13.10, 100.9; decreasing of peaks length of 54.85 min). An order of peaks exit of different volatiles is given in the Table 2.

Table 2

Exit order of different volatiles

Exit order, from published data for Carbovax 20 M	Retention time in our experiments, min	Exit order, from published data for Carbovax 20 M	Retention time in our experiments, min
Acet aldehyde	3.8	i-Pentanol	23.56
Ethyl acetate	4.71	i-Amyl butyrate	
Diacetyl	4.82	Acetone	
Methanol	4.91	n-Pentanol	27.92
Ethanol	6.01	i-Amyl valerate	
n-Propanol		Ethyl lactate	
i-Butanol	13.58	Ethyl caprilate	52.6
Butyl acetate	13.59	Acetic acid	
i-Butyl acetate		Diethyl succinate	
Ethyl valerate		Ethyl laurate	
n-Butanol	17.73	Phenyl ethanol	
Amyl acetate	20.70	Diethyl malate	

A comparison of retention times of components with peaks of standard substances of wine aroma indicates that butyl acetate and i-butanol are very close to peak 2. Data on chromatographic separation with mild condition showed that i butanol and butyl acetate peaks exited simultaneously. Organoleptic evaluation recorded a nice smell in the treated wine, thereby due to the formation of butyl acetate. Data indicated the presence of ethyl malate, ethyl tartrate and ethyl citrate in the samples, in addition to two peaks corresponding to ethyllactate and ethyl oxalate. The large experiment error does not allow any inference on changes of their height after magnetic treatment. Identification of peaks with retention time factor especially in such complex system is not unquestionable. However, the best way is to use the chromato mass spectrometer, which allows inference according to their individual mass-spectrum.

Organoleptic evaluation can depend on aliphatic alcohols content. Determination with GLC shows (Table 3), that their quantity in the both samples is rather small with respect to average values taken from literature for this type of wines. Thus such changes can not be recognized with such evaluation. For both of samples pH was equal to 4.0.

Table 3
Aliphatic alcohols content, mg/1

Alcohol	Sample #1	Sample # 2	Average literature values (Kishkovsky 1988)
Methanol			80-350
i-Propanol			0,3-3
n-Propanol	less than 20		5-50
i-butanol	less than 20	less than 20	20-100
n-Butanol	less than 10	less than 10	2-10
i-Pentanol	less than 20	less than 20	100-250

The results of optical activity measurements indicated, that both samples are not optical active. Filtration, clarification and dilution could not change the optical activity. Perhaps, there is a compensation of different forms of D- and L- compounds in the samples, thus total activity was very close to zero, and magnetic influences could not change equilibrium between the forms.

Organoleptic evaluation of more delicate taste and aroma of the treated sample with respect to non treated one, MBW treated sample as more complete, harmonic, noble, and natural in contrast untreated sample was recorded as excessively bitter and sour in spite of practically the same pH of samples.

It is interesting to test the tendency of wine to make a different kind of turbidity after the MBW treatment. Data showed that both samples were not positive for protein turbidity. In term of reversible colloid turbidity formation, after storage at 7.5°C for 1 day, the MBW treated sample was homogeneous, in contrast to the formation of different phases with different refractometric numbers in untreated sample. Both the phases in untreated sample were liquid, with a density very close to each other, but the borders of phases were like broken lines when crystallization begins in crystallization process. This alteration in untreated sample may be due to micelle state changes or of structurization of product.

The tendency test for polysaccharide turbidity based on the reaction with phenol in presence of H_2S0_4 and determination of the derivative formed by photometrically, indicated, that difference in concentrations of polysaccharide in the both samples are very small, the levels being 119 and 106 mg/*l* for untreated and treated samples respectively. These values are close to range of polysaccharide stability (150-200 mg/*l*), and thus do not allow any conclusion on changes of relative stability of the samples. A tendency for polyphenols turbidity, due to polyphenols associates precipitation upon addition of salt did not show differences. Turbidity, as determined in MPL apparatus, was 15 FEM as against value of 0.2 FEM before testing in untreated sample. These numbers were respectively 14 and 0.3 FEM for treated sample. Thus it indicates that both the samples are very stable with respect to polyphenols turbidity and that the magnetic treatment does not lead to alteration in the polyphenols stability.

The data on the colloid stability indicate, that both the samples showed rather high resistance against protein, polysaccharide and polyphenols turbidities. Besides, treated sample showed higher stability with respect to reversible colloid turbidities.

It is interesting to investigate as to how heavy alcohols and aldehydes, which are often produced, when low-grade technology is used, are affected by magnetic treatment. For these studies, a system of simple mixture, consisting only of spirit and water, was used. Commercial vodka bottled in standard 0.5 l bottles and artificial solutions, containing 40 % of food derived rectified spirit were used. Data showed, that MBW treatment significantly influenced the heavy alcohols content, as the reduction in heavy alcohol was more than two times. In addition, it reduced aldehydes by more than 3 times in vodka, and more than 30 % in rectified spirit. Data indicate that efficiency of aldehydes removal is higher when the sample contained higher level of aldehydes. Thus, the MBW treated vodka and rectified spirit will be better than untreated one. It is however stressed that untreated samples were also recorded as good by sensory panel. So, limits for aldehydes are usually present in high quality vodka established by National Standard (GOST 5363- 67) are 6 - 15 mg/*l*. Thus the organoleptic evaluation of samples does not allow to find difference in aldehyde levels in these samples.

Table 4

The main results of heavy alcohols and aldehydes determination (mg/1) in vodka and solution, contained 40 % of rectified spirit

Substance	Non-treated vodka	Treated vodka	Non-treated spirit	Treated spirit
Alcohols	8.7	2.55	3.38	1.5
Aldehydes	1.5	0.4	0.6	0.4

Sediments formation and its character were also evaluated. The sediment in treated grape juice was dense and more dark, the formless, non crystalline sort, and gel like form. The volume of the sediment occupied up to 30% of total volume. The sediment did not sink or float, nor it stick to the walls of glass. It was found that 100 ml of juice gave about 155 mg of dry sediment. Microscopic investigations showed an absence of any kind of bacteria or fungi in the sediments.

The effects of high energy of magnetic influences on sediment were also investigated. The experiments were carried out with “Portwine Erevanski, vol. 0.5 1, white, spirit content 19 vol %, sugar 10 %, prepared according to GOST (National Standard) 7208-84”. Crystalline sediment appeared on the walls and especially on the bottom of the bottle after the BMW treatment. An amorphous precipitate was also presented, and it can be separated by decantation. Crystalline sediment, after washing with ethanol and drying to constant weight, weighted 69.2 mg, and was of bright brown colour. A tartrate content as a tartrate acid, of the sediment was 59% mass. If it is considered as a tartar (a wine stone) of potassium sodium tartrate, then tartar content in sediment works out to be 86%. If it is considered as a tartar of dipotassium tartrate, tartar content in sediment will be 93%.

Generalization of data shows the positive effect of magnetic treatment on the wine samples, leading to harmonic taste of treated wine and absence of non pleasant tastes. Most of the changes were found to bein the flavour and taste components, which were minor substances in the product. For example esters concentration changes during the treatment. At the same time the content of major components, such as sugars, organic acids, particularly, heavy organic acids, and especially ethanol remain constant. It seems logical from kinetic point of view, when simple processes, like esterification, are preferable with respect to many stages reactions, and reactions with high activation energies, which can go at hard conditions. Also, it seems logical that magnetic treatment may influence on electrical state of colloid species. Thus magnetic treatment can be considered as mild, selective in the comparison with many other physical methods. Nevertheless, the changes lead to acceptable energetical and nutritious value of the product. Data show that difficult problems, such tartar removal, can be solved by MBW treatment.

References

1. Amaldi E. et al in: Preprint CERN, Report 63 13. Search of Dirak Magnetic Pole, 1970.
2. Devons S. Search for Magnetic Monopole, Sci., Progr. (No.204), 601 (1963).
3. GOST (National Standard) 5363 67. Vodka. Metody ispytaniy (Testing Methods).
4. Kishkovsky Z.N., Skurikhin I.M., Khimiyavina (Wine Chemistry), Moscow: VO "Agropromizdat", 1988, 253 p. (in Russian)
5. Lurle A.A. Sorbenty i khromatograficheskie nositely (Handbook on Sorbents and Chromatographic Supporters), Moscow, Khimiya, 1972, 320 p.(in Russian)
6. Shakhparonov I.M. in: Sharovaya molniya v laboratorii (Ball Lighting in the Laboratory) / Collection of Articles. Moscow: Khimiya, 1994, 400 p.
7. Svoistva konstrukzionnykh materialov na osnove ugleroda (The Properties of Constructional Materials Based on Carbon) / Handbook/ Nagorny V.G., Kotosonov A.S., Ostrovsky V.S., Dymov B.K., Lutkov A.I., Anufriev Yu.P., Barabanov V.N., Belgorodsky V.D., Kuteinikov A.F., Virgelev Yu.S., Sokker G.A. Moscow, Metallurgy, 1975, P. 73 77 (in Russian)
8. Valuiko G.G., Zinchenko V.I., Mekhuzla N.A. Stabilizatsiyavina (Wine Stabilization), Moscow: "Agropromizdat", 1987, 160 p. (in Russian).

The Fundamentals of the New Principle of Motion

By The Group Studying Inertialess Natural Processes (GSINP)
123430, Moscow, Mitinskaya Str., 40-1-244 Email: gibip@mail.ru

P. Sherbak

The concepts of active and passive interaction between the moving object and the space form the basis of the new principle of motion.

So as to be more understandable, let's consider what is the old principle of motion. For this we will use the concept of a moving object and the space in which the object is moving. Naturally, material objects and the space can't interact between each other directly, because the space is the philosophical category. In this case we can understand physical essence of natural phenomena easily. In our view, the material objects interact with some fundamental energy of space (FAM), which fills all space with a different density. Thus the energy (FAM) is inalienably connected with the space. One of the first names of this energy is "ether" in the early scientific works. So, for the simplicity we will accept that the object and the space interact between each other.

Thus, all existing methods of motion which have been invented by mankind till the present time are based on activity of the material object that means the one expends some energy to produce the motion, and at the same time space is passive, it means that space does not need to spent any energy to move the object. And so in common case space tries to keep the object in the former state interfering with accelerated movements of the object (in accordance with **the 1st , the 2nd and the 3rd Newton's laws**).

It should be noticed that such method of motion (for the speed, which is much less than the speed of light) takes place both in animate and inanimate natures. In this case the level of energy of motion and reaction of space (or an environment) are not very high. Incidentally, the energy of object can be of different types: electrical, chemical, biochemical, mechanical etc. The common consequence of this type of motion is existence of the ***inertia***. The classical physics can't answer the question: "what is inertia?» The same situation is applied to the concept of ***mass,*** which is closely connected with inertia. The classical physics says that ***the mass is a measure of inertia.***

There is the new principle of motion of material object: the object is passive and space is active. In this case it's more favorably for space in the energy aspect to move the passive object and to spent some power then to keep the object in the present place in the former state of immobility (in accordance with **the 1st, the 2nd and the 3rd Newton's laws**). And so we should introduce **the 4th law of** Newton's **mechanics**. It says that ***there are the systems of coordinates in which the body is moving not rectilinearly with acceleration when this body is in the state of immobility***.

The basic and the main differences of the offered principle of motion from the existing methods at the end of the XX century are the following:

1) The absence of inertia of motion;

2) There are no limits for the speed of motion;

3) The absence of "fuel reserves" "on board" of the moving material object.

Nikola Tesla and Instantaneous Electric Communication

Vladimir I. Korobeynikov

Russia
E-mail: elen@mail.infos.ru

Nikola Tesla (1856-1943), an outstanding inventor, was and still remains one of the most mysterious persons in the history of electrophysics. Whereas the most scientists were moving together in direction of microparticles investigations, as the basis of matter structure and of nature itself, he was going in opposite direction. He had a keen interest in the investigation of electric charge of the Earth as a whole. He was looking for the ways to influence on it, to control its state and methods of its regulation.

Therefore, exactly, the most of his searches, experiments, the purpose of constructions and buildings, created according to his conceptions, cause perplexity and misunderstanding of scientists even in nowadays.

The most mysterious of his main experiments were made in USA after 1904. After Nikola Tesla death in 1943, all his diaries and records over a period from 1904 year had mysteriously disappeared. Probably they were stolen (it was known, what to take). Lost records could “cast light” on one of the most “strange” of his buildings in the form of the enough tall tower, on the top of which a specially created toroidal transformer was placed. This transformer could create there a huge electric potential up to the billion volts.

Nikola Tesla switched on this tower-device, what caused the fright and even panic in mind of people from nearby settlements. Of course! Because of very high electric potential there began air ionization, which spread very high to the atmosphere accompanying by the effect of color play. Such luminous, color-playing sky caused even a horror of people, who knew nothing about the experiment made and its goals. They did not guess that Tesla by means of the electric charge, created of the tower, was influencing on the electric charge of the Earth as a whole (about 600000 Coulomb). There was a global scale in Nikola Tesla’s investigations.

There is no point in detailed analysis of the fact that the potential of the tower top influenced on the Earth charge. Interaction of charges-balls with the distortion of field lines, distortion-distribution of charge on their surfaces, induced charge, is beautifully described even in school physics textbooks. In Nikola Tesla investigations the Earth had the role of one of the charged balls. It was possible by changing of charge on the tower to deform electric charge distribution on the whole Earth surface at once. This deformation (electric currents) could be fixed at once in every point of the Earth surface. It is alluring to use this effect for data transfer telecommunication, both on the Earth, and in space.

After such introduction the question “How does the system of instantaneous electric communication for any distance look like and work?” is still opened. First of all, the readers need to know, that such instantaneous communication is possible in principle. The proving it theoretical calculations, are rather difficult for popular interpretation. Some part of readers can take it on trust, and those who are most interested in can apply to works of Oleinik V.P. (quantum physics) the professor from Kiev Polytechnic University. At the minimum there are two necessary works: Oleinik V.P. “Faster-than-light transfer of a signal in electrodynamics. Instantaneous action-at-a-distance in modern physics” (Nova Science Publishers. Inc. New York. 1999) and Oleinik V.P. “Latest development of quantum electrodynamics: self-organizing electron, faster-than-light signals, dynamical heterogeneity of time.” (Physical vacuum and nature. 4. 3-17. 2000).

“PC” magazine has devoted a rather significant article entitled “Computers and teleportation” to V.P. Oleinik works, concerning instantaneous electric communication (“PC” #6, 2000). Note, that the author of the given article has also found the possibility of instantaneous electric communication, but by means of materialistic methods, absolutely different from Oleinik’s ones, what is most important – two different solutions point to the possibility of this communication. “PC” #6, 2000 in the article “Circles on fields” cited mathematical formulae of the structure of electron electro-magnetic field as an illustration (it refers to the Earth too) that the author of this article has got.

The most attentive readers of that article could notice, that one vector Hz absolutely “ignores” Special Theory of Relativity, since its mathematical expression does not include the velocity of light, whereas it presents in other vectors as a product of electric and magnetic conductivity. Magnetic line of this Hz vector goes to infinity and returns back from infinity. It surrounds the whole Universe. It is alluring to use exactly this (Hz) line for the **instantaneous** communication for any distance.

It is not so difficult to do it. In the Fig. 1 the easiest and most available for understanding line of the **instantaneous** electric communication is shown. A rotating charged dielectric ball (an “electron”, isn’t it?) is used as transmitter. The ball can be electrically charged up to the limit of charge flow-out into the ambient space. Around the charged rotating ball there appears electro-magnetic field, entirely analogous to the electro-magnetic field of the Earth (and of the electron too). The central magnetic line Hz goes to the infinity and returns


TRANSMITTER
Tower of Nikola Tesla (non-effective in this case)
N
ω
Charged dielectric ball, rotating with ω velocity
The long capacitor (”Chinese Wall”)
Control signal (information)
U
S
Central line Hz
Magnetic lines (Hz) of the rotating ball
Angle of rotation (of deviation) of flux line in the case if signal is in the long capacitor
δ
RECEIVER
Magneto-conducting pyramid made of soft-magnetic ferrite (”Egyptian Pyramid”)
Concentration of magnetic lines into the pyramid
Received signal
U
Coil at the base of the pyramid

Fig.1

Line of the instantaneous electric communication on the basis of rotating charged ball and pyramid

back from it to the opposite side of the ball. In the same way the central magnetic line of the Earth (Hz) goes from one pole to the infinity through the whole Universe and returns from it to the center of the opposite pole.

If by the information to force the rotating ball (electron) to “wag by tail” (by Hz vector) which stretches through the whole Universe, then this “wagging” can be controlled instantly in every point of the Universe. While the rotating ball has a steady distribution of the surface charge, the line Hz does not change its dynamic position in the Universe.

If such distribution of the surface charge is broken, space position of the line Hz also will change. On mounting the Tower of Nikola Tesla on the surface of rotating ball and measuring the potential on this tower in time with an information it is possible to change the charge distribution on the ball, and, respectively, the space position of central magnetic line (Hz) in the whole Universe at once. Big disadvantage of the Tesla tower is that maximum influence on charge is executed in the point under the tower, and farther it began decreasing roughly (exponentially), according to physics laws.

Hence it is advisable to influence on the whole surface of charged ball, but not on some point of it. It is possible to influence at once on the very big part of surface by the long capacitor, placed on the perimeter (equator) of the charged rotating ball. Because of optimality reasons, this capacitor length should not exceed a quarter of the ball perimeter (equator) length. Charging and discharging this long capacitor on the ball equator by the data signal, only the position (angle 5) will be changed, not a value of the infinitely long magnetic line (Hz) in the Universe. It is a data transfer.

The natural question appears: "How to make on the Earth the most powerful transmitter for the **instantaneous** electric communication?" The answer suggests itself: "It is necessary to use the Earth itself as a rotating charged ball." It is not effective to use Nikola Tesla's Tower to deform the Earth electric charge. To place on the Earth very long (about thousands km) capacitor is quite easier. However, it must be placed not on the equator exactly, but moved a little bit because of the initial heterogeneity of the Earth surface charge distribution, caused by the presence of continents and oceans. It will be necessary to find the line of electric equator, where the amount of charge north and south of it is similar. This line will not be ideally straight and will be situated near the 30th parallel.

As a matter of fact, this grand capacitor is already built, but is half-broken. This capacitor is very well known – it is a Great Chinese Wall. The ancient, powerful Chinese Tzcin' Shi Huandi empire adapted and used it (capacitor) for the protection from nomads incursions. How unexpectedly and originally it is! In this case the electric iron would be the best tool for spiking. It is clear enough that the charged ball (as well as the Earth) will "wag by tail", which stretches through the whole Universe and does not change its energy, but only changes its position in space in time with information. Now we can go on to the question, concerning the way to control the Earth "wagging by tail" in the Universe, and thus to read information **instantaneously** in any point of the Universe.

In the Fig. 1 it is shown the input device of the electric communication receiver, made of the magnet sensitive material (it can be soft-magnetic ferrite) in the form of pyramid, with the proportions of well-known Egypt pyramids. Magnetic field lines of the far space pass through the pyramid from the top to the base and are concentrated by pyramid. If there is no signal (the "wagging by tail" of the far planet-transmitter is absent), then the magnetic flow, coming through the pyramid, does not change, and induced voltage in the coil, placed in the base of the pyramid, is absent (no information). If "wagging by tail" begins, then the magnetic flow, coming through the pyramid, will change, and it will cause the appearance of voltage on the coil in the base of the pyramid in time with the information.

Thus, the signal is received instantly. Here it is necessary to remind once again the difference between the instantaneous and usual radio transmission. The usual radio transmitter for the transmission of the information uses the **energy** distortion of space by the information. This energy change in space happens with the velocity of light and hence there is the loss of time for information passing. In the considered case there is no **energy** change in space, there is only a change of magnetic lines position (Hz).

This is exactly the vivid and fundamental difference between the usual electric communication and the instantaneous one. **In other words, in usual transmitter during the fixed time interval there is the change of signal energy (instantaneous value), whereas in instantaneous transmitter there is no this change (only information). This is exactly the fundamental difference.**

Evidently, to receive instantly the signal from the opposite part of our Galaxy, we need rather big pyramid, in order to concentrate a big amount of field lines into the oscillatory circuit under the pyramid. The question can appear: why the pyramid, why not a cone? The point is that lines of the Earth magnetic field (the very lines that compass needle reacts on) in the any place of the pyramid horizontal section have the same density of distribution and are directed strictly parallel to the pyramid base. The cone in its horizontal section cannot provide such uniformity of distribution that is why it is not advisable to use it. From the space magnetic field lines pass through and concentrate in the pyramid strictly at right angle to the pyramid base.

This is the riddle of pyramids wonderwork. Any person coming into a pyramid, at the same moment feels the change of mental and physical condition of organism; whish is very different from that it was before the entering into a pyramid. Of course! Visitors come inside, into concentrated magnetic field lines of the powerful and functioning magnetic core of the receiving electric circuit, what is absent outside the pyramid.

It is strange, but most of tourists are afraid of the ill effect, which can be produced by electrical systems on their health, but there they stand in a queue to feel this effect in pyramids. Concentration and division of magnetic field lines are the easy and effective way to reject a noise, created by the Earth magnetic field.

It is clear, pyramids should be oriented very thoroughly, so that lines of the Earth magnetic field would be strictly parallel to the base and to the opposite (East-West) sides of pyramid. To get such exactness of orientation in modern conditions is very problematically.

The most convenient place to build a pyramid (pyramids) is on the electric equator, in the place of its intersection with the electric meridian. Such place is located in Egypt, near its capital Cairo. And again we meet a paradox: such pyramids are already built on the Earth, but they are half-broken. And Egypt was not less powerful than the ancient Chinese empire.

The Egyptian dynasty of Pharaohs has "completed" and adapted pyramids to burial-vaults, where mummies of dead Pharaohs were buried. Perhaps, it is even more incredible than in China. The impression is given that ancient powerful civilizations on the Earth had a competition between themselves, who will use radio-engineering constructions for instantaneous galactic communication in the most incredible way. Let's give to a reader an opportunity to select a "winner".

It must be noted that «PC» already published information that the Chinese Wall and Egyptian Pyramids are radio engineering constructions, intended for the instantaneous galactic communication (PC #114, 1997, etc).

There appears an interest in the possibility to produce very simple and manufacturable systems of instantaneous electric communication right now. Radio-electronic industry can produce them, but still does not guess about it.

Furthermore, such systems of instantaneous electric communication can be created at home, and even senior pupils are capable to use them. In the Fig. 2 there is shown the construction of instantaneous electric communication line in comparison with the usual one. It can be produced even at home conditions. Two permanent magnets, connected between each other by analogous poles, are used as transmitting circuits.


Usual antenna
A
Usual receiver
Information
Usual antenna
A
Usual receiver
Information

Line of the usual (Einsteinian) radio communication


Antennas of the instantaneous communication
Permanent magnets (contrary S-N-N-S superposed)
Central magnetic line (Hz)
Flat ferrite rod
A
Usual receiver
Information
S
N
N
S
A
Usual receiver
Information
Coil
Angle of oscillation of flux line in the case when signal is transmitted
Coil

Line of the instantaneous (Maxwellian) radio communication

Fig. 2

Transformation of the usual line of communication of usual receiver-transmitter into the instantaneous one

Permanent magnets can be replaced by electromagnets. In the magnet connection point there is a coil, which while the signal passing through it will change its position (angle 5) in the space of the central magnetic line (Hz), coming out from the place of two magnets connection. Receiving circuit is available to be made of the flat ferrite, but coil must be winded along, through butt-ends of core, so that the whole internal part of the coil would be maximal (in area extent) filled by ferrite.

The obtained coil can be completely "winded" (screened) by flat ferrite of big size. For more clearness of the experiment the central magnet line of transmitting part must be directed strictly along the axis of the receiving coil.

Now, if we give the alternating voltage (information) from transmitter to the transmitting coil, fixed on the permanent magnet, then the receiver, connected to the circuit of the transmitting coil, placed on the flat ferrite, will detect an alternating voltage (information). Maximum effect is achieved at the resonance (coincidence of transmitter and receiver frequencies).

It is checked. It works. The dullest experts in radio-electronic (after the reading above) can rejoin, without making an experiment, that it is an absolute nonsense that any communication is out of the question. Coils with absolutely perpendicular axes, besides one of them is screened, do not interact with each other.

And here the most interesting thing starts. In the Fig.2 as it was mentioned above, the usual communication line and the instantaneous one were compared. The usual transmitter cannot generate the vector Hz that is why systems of usual and instantaneous communication cannot see each other in strict sense. What does it mean? It means, that in the same city it is possible to transmit on the one-carrier frequency ("what a nightmare!") two absolutely different television channels without any noises of one to another.

Usually by frequency match of a transmitter to the working frequency of another one, the radio communication is broken, but here it does not happen. Here some additional explanation should be given. As the vector Hz, which "ignores" the theory of Einstein is received from Maxwell equations, it follows that the usual (Einsteinian) system and the instantaneous (Maxwellian) one work on mutually perpendicular electromagnetic field lines (vectors).

In the Fig. 2 such difference is shown clearly. These are just "jokes" of complex numbers, when one value is absolutely perpendicular to another and nevertheless together they form a single whole. In other words it means, that two greatest persons in science Einstein and Maxwell as a matter of fact are something like "Siamese twins", completely grown together at the angle of 90 degrees, even by heads. On the one hand every one is on his own, but nevertheless they are the common (complex) organisms.

Hence there are a lot of misunderstandings on happened phenomena. How many scientists tried to find some mistakes of Einstein? They produced very convincing proofs concerning instantaneous interactions in nature. These scientists did not suspect that time and still do not guess now that they already for a long time are "walking" in the complex physics, which still does not exist. Einstein and Maxwell ("Siamese twins"), each occupies his own part of the complex number (complex physics) and they cannot be already taken off from there.

The only third, free "vacancy" is left to throw on the both of them at once the common "collar" and "reins", i.e. to fasten them ("twins") together by module and argument as any complex number. In this case no matter how the one part of complex number "ignore" the other one, only its argument will change, and module always will be equal to the conditional unit. Only this single fact in principle changes the conception about "appearance" and "disappearance" of elementary particles! Even considered instantaneous and usual communications on the same receivers and transmitters in a complex conception (complex physics) eliminate appeared "misunderstandings" of all kinds.

Advantages of the instantaneous (Maxwellian) electric communication are especially evident during the connection with long-distance spacecraft. At present in the interval between sending of control signal to the station in region of Solar System peripheral planets and getting the reply it is possible to have a small break for dinner (it is very convenient).

In the case of the instantaneous electric communication use, duty operators will have "no dinner". Moreover, the system of instantaneous electric communication can realize two-way communication underwater and from underwater to overland. It is clear that input and output circuits of such system must be covered by slushing composite for the protection from aggressive effect of the salt sea-water. Such systems of instantaneous communication are very required to submarines.

Now, when readers know and understand the principle of operation of instantaneous (Maxwellian) electric communication systems and their advantages over usual ones (Einsteinian), we can only wait, when radio-electronic industry will start to produce these very required systems.

ELECTRIFYING TIMES

an online and published magazine about Electric, Hybrid, Fuel Cell Vehicles, advanced batteries, ultra capacitors, fuel cells, microturbines, free energy systems, events and exhibitions worldwide

63600 Deschutes Mkt Rd,
Bend Oregon, 97701
541-388-1908
fax 541-388-2750
etimes@teleport.com
www.electrifyingtimes.com
Subscription $13/3 issues

Institute for Planetary Synthesis

P.O. Box 128, CH-1211 Geneva 20,
Switzerland
Tel. 41-022-733.88.76, Fax 41-022-733.66.49
E-mail: ipsbox@ipsgeneva.com
website: http://www.ipsgeneva.com

The Unified Gravitation Theory

(The unified super-principle, which controls the Universe)

I. P. Kuldoshin

Orenburg, Neftyanikov str., h. 2, apt. 9,
460019, Russia

(Editor's comments by Alexander V. Frolov)

A forum of the leading USA physicians took place in the White House in March 1998 in presence of President Clinton. There was only one question: "When will the nature of Gravitation be opened?"

The well-known USA physician-astrologer S. Hoking declared that it possibly would occur in twenty years and it would be **the Unified Theory of All.** So, the scientific world by default called it the greatest discovery of the future.

Some time later a new hypothesis pretending to this discovery has got its birth in Orenburg. Despite this fact this hypothesis would gain recognition and status of the **Greatest Discovery of Mankind** only by 2018 that was predicted by S. Hoking.

To present day there have been written a lot of hypotheses on this problem but they haven't been recognized. Many scientists consider our Universe as living and functioning according to the unified and rigid laws in Macro and Microworld, which provides automatic regulations of all its processes due to **circulation of radiant energy of the Universe life in cosmic space**. This energy is inexhaustible and environmentally clean, and Mankind may learn using it in the nearest time for the welfare and for prevention of **contradirectional irreversible ecological** catastrophe.

There is no alternative for humankind to escape and it will not appear in the future. Only cosmic energy will save us. From the book "Secret Doctrine" by E.P. Blavatskaya we can get complete information about the fact that a highly developed civilization of Atlases on the Earth had a "**General Theory of All**" yet 10-12 thousand years before our civilization. They had no automobiles, but instead they had flying objects (aircrafts) "Vimana" of various types as well as ships and submarines, on which they also used **Cosmic energy.**

While reading an abstract in General Soviet Encyclopedia, I got acquainted with the theory of "Aether wind", which was abolished in the beginning of the XX century, and then I understood that this theory contains a deposit to discover the nature of gravitation.

The nature of gravitation is the only one and there are no alternatives in theoretical as well as in physical sense. When scientific world of entire planet abolished the theory of "Aether wind", it lost the possibility to discover the nature of gravitation. The XX century was marked by a revolutionary development of scientific and technical progress, but there was an almost 100-year stagnation in cognition of the Universe elements.

The theory of "Aether wind" supposed that all Cosmos is filled with aether particles flying with the speed of light (these particles are "neutrino" according to modern understanding). **The role of gravitation, carrier of light and retarding medium in Cosmos** was attributed to this motion of particles.

But this theory allowed chaotic motion of particles, which is impossible in mechanism of the Universe, which is adjusted up to automatic mode. Besides, motion of these particles is not possible without an absolute buffer unit, which prevents their head-on collision at the speed of 600000 km/sec (it is thermonuclear explosion and death of matter, i.e. the Universe). E.P. Blavatskaya wrote that Cosmos is filled with radiant energy of the Universe life, luminophore, electromagnetic aether. Thereby she predicted a ready solution to make correction in the uncompleted theory of "aether wind". On the basis of above stated and due to the **un-assumed dawning up,** the theory of "aether wind" was completed. It was the ground to develop a hypothesis of radiant "aether wind". Particles of this wind (neutrino) are electromagnetic particles and move with the speed of light in all directions as **contradirectional paired single-stream flows** (like electrical current in twin-wire cable). Due to this, an absolutely stable concentration of these beams in cosmic space is provided according to the principle "what has come in, the same has gone out".

The hypothesis formulates new views on the problem of structure of elements of the Universe material world.

Some separate conclusions do not match the views of modern scientific thought on the problems of physical principles of material world structure and functioning of the Solar system.

List of topics of the hypothesis

1. The hypothesis disclosures the operating environment of a super-mechanism, which controls the Universe (it is a radiant "aether wind").

2. It disclosures the nature of retarding mechanism of flying objects in Cosmos (its name is Lorenz-Fitzgerald compression).

3. It proves the absence of Universal gravity and beams of light as we usually conceive it. (The beams of aether wind collide and compress matter. An alternative to the notion about beams of light is a temperature wave impulse on the beam of aether wind. It explains why the speed of light doesn't depend on the speed of the source of light. Light is a "passenger" on the beam of "aether wind").

4. This hypothesis disclosures the mechanism of stablization of rotary and orbital movement of the Universe matter in macro- and micro world due to retarding medium in Cosmos.

5. It disclosures the mechanism of reverse rotation of Venus due to the forces of autorotation.

6. It disclosures the mechanism of reverse orbital movement of planets and satellites of planets. (Such a planet had not been opened yet, but there are 6 satellites in the Solar system, which move counter to the others, and it is not an occasion, but **a particular case of the effect of aether wind beams**).

7. It disclosures a real nature of Tungusska catastrophe. (There were about 100 hypotheses, but **neither of them** was recognized to be true).

8. It disclosures **the nature of gravitation** and gives an explanation that gravitation can be:
   - usual (vertical);
   - horizontal;
   - circular

It is important to note: not the entire matter takes part in gravitation, but 1/3, i.e. 33,3% of matter.

9. It disclosures the **nature of Levitation** and proves that 1 liter of water on the surface of the Earth can have the weight from 0 up to 3 kg.

10. It disclosures the role of gyroscope effect in life support of the Universe. The gyroscope effect allows transformation of translation energy of radiant "aether wind" to the rotational energy for practical needs of humankind.

11. This hypothesis gives scientific and technical recommendation for creation of cosmic energy converters.

12. It gives scientific and technical recommendation for producing of levitation effects for any technical systems.

13. It disclosures the possibility of cosmic flights with the super-light speed.
14. It explains experiments on metering of horizontal gravitation (The first experiment was made on February 27, 1999).

15. It disclosures the particle (neutrino) of original matter of the Universe and gives its characteristic. (Ancient thinkers called modern "neutrino" as "Aether", and it was not occasionally, because its diameter is in 10^{25} times smaller than atom's diameter.

All matter of the Universe consists of the same indivisible particles "neutrino" presented by three groups:
- "energy" group, which is in the beams of "aether wind";
- building group, which forms the part of any micro particle;
- free group (neutral-reserve) as a building material for new matter and operating environment of all electromagnetic processes.

All neutrino of three groups rotate with the speed of 3×10^{43} rps (equatorial speed of neutrino is equal to the speed of light).

Fields are formed in every particle as a result of rotation:
- strong field of a small volume doesn't allow particles to close up;
- weak field of a big volume is a general mechanism of gravitation.

As scientists write at the present time, the World is subdivided on a dense world (which we can see) and fine world (invisible). At that the density of such world is in 10^{15} times less than density of water.

It is known in science that all matter of the Universe both great and small rotates and is a gyroscope. Particles of matter get rotation with their birth, thus the fields are born in them simultaneously. **Matter cannot exist without rotation, which generates fields.**

All mechanism of interaction between three groups of particles is based on the mutual repulsion. This is the only mechanism, which always and automatically is able to create the necessary stable interval between the particles and only this mechanism provides the function of gravitation.

Many scientists of the late XX came close to the discovery of the nature of gravitation, but they didn't accept a thought to conceive **the motion of aether particles as a pair-counter flow**. And there are three necessary conditions to realize gravitation:

1. The particles should have the fields of repulsion.
2. The contradirectional flows should envelop the particle of matter from two sides.
3. While one beam is passing a matter mass then the force of fields should decrease and gravitation effect should appear.

Mechanism of gravitation

Gravitation appears due to the intersection *(Editor's note: interference)* of fields, produced by beams particles and fields of the visual matter. As it was mentioned above, the beams are paired and contradirectional. Usually the beams in cosmos are mutually balanced and they do not call gravitation effects.

But on the surface of the Earth the contradirectional beams are not similar in their power. The powerful beams come from above, i.e. they only penetrate the atmosphere, and the weakened beams come from below, i.e. they penetrated all the Earth. Thus, gravitation appears.

Gravitation is a unique property of "aether wind" beams to loose part of their power during penetrating of matter mass. **Gravitation** is the difference of forces of contradirectional beams. *(Editor's note: Really other authors reported this idea also. I cannot find who was the first in discussion about gradient of aether as nature of gravitation.)*

Horizontal gravitation

As a particular case, there is **horizontal** gravitation on the surface of the Earth. It appears on the boundary between lowland (of the sea) and plateau. In this case one beam goes above the surface of the Earth (water), and the counter beam penetrates mountain range and weakens. The first measurements of horizontal gravitation effect were made on February 27, 1999 on the route Orenburg – Samara at 49 km before Syrtinskiy slope.



A leaden load (0,5 kg) on the float (a piece of foam plastic) moved on the water surface (not in the sea but in basin) towards the mountain.

Horizontal gravitation is much more weaker than usual gravitation, but it can reach the value that makes water to flow at some angle upwards.

Circular gravitation

Only fast-rotating bodies can create circular gravitation.

All bodies rotate by their orbits around the Sun in the open space of Solar system **due to circular gravitation guided by rotating the Sun.** Furthermore; circular gravitation always is direct (co-directional to the Sun rotation) and reversed gravitation on the periphery of Solar system. A planet with reverse orbital movement had not been discovered until now, but 6 satellites of planets in the Solar system have reversed orbital movement.

Here is the proof of the fact that circular gravitation appears only around the fast-rotating bodies and **slow-rotating bodies, for example, the planets Venus and Mercury cannot form circular gravitation**, that's why they have no satellites.

Our Sun is a prototype of mechanism to transform translation energy of aether wind beams into rotary energy.

(Editor's note: According to Kozyrev, any star is a transformer of time (chronal type of energy) into heat energy. Really, the aether wind can be considered as the chronal type of energy in our understanding and for our usual three-dimensional measurement equipment. To my mind it is a clear link to notion of 4-dimensinal objects, i.e. the time. ***Time can be described by parameters of the aether wind, i.e. its velocity, direction and density. So, we can say that quantitatively time can be described by formulations for kinetic energy of the aether movement. From the other hand it is equivalent of heat energy, which can be measured by usual methods after transformation of the longitudinal waves of the aether in transverse electromagnetic waves).***

Therefore, any mechanical disk rotating very fast will create a circular gravitational field, which is able to rotate all bodies in the direction of the disk (for example, a rim mounted on its bearing co-axially with rotating gyroscope). I designed and tested a similar device in January 2000. A gyroscope (of 200 mm diameter and 3 mm thick) was over-speeded up to 18 thousand rpm. Rotation of gyroscope called slow (but with a good momentum) rotation of the rim of 15 kg weight.

The gyroscopes with the mass of 0,5 kg, 15 kg and 90 kg were tested during summer of 2001. All them called rotation of the rims.

(Editor's note: There are other experimental facts. Fast rotation of mass should produce rotation of some part of nearby aether. Self-closed aether forms vortex and if photon is trapped by this vortex, then

experimenters can see "ring of light" near rotating mass. The rings or self-closed photos can exist in the same place after the mass was stopped or removed away.)

Nowadays gyroscopes in military devices are over-speeded up to hundreds of thousands of rpm. The more rates the gyroscope has, the more energy the rim will produce if it is connected to some generator. But these research works led to single-valued conclusions that gyroscopes themselves cannot produce big quantity of additional cosmic energy not jointly with permanent electromagnets. The Sun as well as planets has natural electromagnetism and their circular gravitation increases in many times due to the presence of electromagnetic fields.

(Editor's note: I think it is obviously that a rotating magnet can involve into the rotation much more quantity of aether than any simple rotating mass. In some theories any magnetic field is considered as circulation of aether particles.)

Electromagnetic fields are the unique boosters of circular gravitation. So, the gyroscopes themselves cannot produce necessary quantity of cosmic energy per unit mass of gyroscope without using of electromagnetism.

In October 2001, I got a copy of 24 patents description. There were patents on "perpetual motion machines". But since such "perpetual motion machines" cannot exist in reality, then we can explain them as gyroscopical transformers of cosmic energy. Efficiency of these transformers varies from 150% up to 10^6% and practically all of them work using gyroscope. But nowadays only the transformer (Bauman's machine) works in Switzerland, in Maethernitha theological community, Linden city. Some systems have been working from 1980 and producing total power of 750 kWtt, the gyroscopes of 2m diameters are provided with constant magnets.

Besides, there are ready transformers of cosmic energy in Russia. The Professor of Moscow State University, Academician of Russian Academy of Natural Science Leonid Leskov spoke about them in the first half of 2001. He actually said that Mr. Chubais does not allow innovation of energy transformers, which are ready for commercialization (see newspaper "Raduga", Samara, July 2001).

I assume that any kinds of such transformers work on the energy produced by "Aether wind" beams. Perhaps our earth ancestry (Atlases) used this energy to fly as well as extraterrestrials. I remember information about flying platforms, which were designed in Germany in 1943-1945. Nowadays there are publications that there are not less than 10 captured extraterrestrial's spacecrafts on the Earth, and some samples were tested in Russia and the USA.

On the basis of all above-mentioned it becomes extremely clear that the main secret of Nature was discovered, and let's representatives of conservative science don't pull the wool over people's eyes to prove that "it is impossible". It is possible! Physics is an experimental science in its main part, and there is no completed theory until now.

As a result, I'd like to make some conclusions: The secret of Gravitation nature was discovered not in connection with new scientific investigation, but due to dawning up and understanding of the fact that gravitation since earliest times was produced by "Aether winds", which fill all cosmic space. Instead of improvement of "Aether wind" theory, academician science abolished it and forgot it such as some scientists of nowadays don't have an idea of it. While abolishing of "Aether wind" theory, scientific world spent 100 years in vain to find an alternative to it. A real Cosmic scientific and technical progress was slowed down during this term. Without this progress all humankind will kill environment of the Earth in 30-40 years!

Rush hours for humankind to turn to cosmic energy came, we have not even an hour to wait, and otherwise we will loose a chance to survive. Today the scientific and technical level is such that taking into consideration the buildup made by inventors – enthusiasts, who created more than 50 types of Cosmic energy transformers, it is possible to begin repetition work in one year. Now there is the only barrier to do it, i.e. market relations in energetics developed during last 100 years.

Let's look into near Future. The process of energy resources (coal, oil, gas) formation in bowels of the Earth took hundreds million years. There was period of clean ecology in the World Ocean, on land and in the atmosphere. **And all it catastrophically had been diminishing during 2-nd half of the XX century**. **There are about 40 years for our civilization to reach the boundary of having no chance to support normal life on the Earth.** An irreversible process of struggle for survival using underground environment and protection from mortal ecology will begin. Our close posterity will not forgive us this betrayal.

Is there any solution? Yes, there is.

It is necessary to publish the descriptions of all "perpetual motion machines" models as well as unprofitable publication of short technical documentation in the Internet and magazines, which will give a chance to many companies, research groups and individuals to re-produce them. But at first we should choose the models, which are the most reasonable in technology and prime cost. Such a way of replication of the models will give people confidence, interest and reliable information on existence of inexhaustible salutary cosmic energy. And the victory will be the reward for courageous, enterprising and advanced people.

which generates electrical voltage $E_{\updownarrow} = \ell \dfrac{dB_{rot}}{dt}$ in the structure of vacuum. This voltage generates Gravitational Impulse itself $G = 4\pi E_{\sigma} S \cdot (\Delta r_g)^2$, where $\Delta r_g = e_0 \dfrac{E_{\updownarrow}}{b}$.

The supposed "Gravitational Impulse" in the experiment by Podkletnov is modeled by a quarter of cosine curve.

Duration of this curve is determined by the decrease of magnetic field "trapped" into the superconductor due to the partial heating of semi-conductor emitter after plasma passed the discharge of 2MV with the current strength of 10000 A. The formula of the model is the following:

$$X'' = Ae^{-2\pi f_0 D_0 t} \cos(2\pi f_0 \sqrt{1 - D_0^2}\, t) \qquad (1)$$

the calculation is made for the frequencies of 30, 3, 0,3 and 0,03 Hz and acceleration of 12 m/sec^2, which appears for the mass of the pendulum 30 g with the force horizontally to gravitation 0,03·12=0,36 N.

It can be supposed that it is necessary to make more careful solution of the problem to find the effect on the pendulum by its reaction, which is known from experiment. We should apply the more correct use of spectral method of solution of differential equation for the pendulum with setting of impulse effect. Further, having the recording of temporal function of magnetic field by Hall-effect devices and using Maxwell formulas, we should find electrical field acting in physical vacuum. This field will give us the force of gravitational impulse.

The experiment by V. Roshchin and S. Godin is simpler for physical modeling (Editor's note: the author assumes it is simpler than Podkletnov's effect). All input and output parameters are known to the authors, i.e. force of the magnets, frequency of variable magnetic field in the local place of space vacuum, change of gravity. Furthermore, there are known cylindrical formations of magnetic "loops" around the device and their approximate arrangement with the intervals divisible by the half of rotor radius. Effects of temperature decrease at 8° C in cylindrical atmospheric formations can be simply explained by adiabatic decrease of air pressure due to the decrease of gravitation between molecules of air. Formulas for estimation of decrease of gravitational and inertial forces are the same that for Podkletnov's experiment:

$$E_{\updownarrow} = \ell \frac{dB_{rot}}{dt}, \qquad (2)$$

$$G = 4\pi E_{\sigma} S \cdot (\Delta r_g)^2, \text{ where } \Delta r_g = e_0 \frac{E_{\updownarrow}}{b}. \qquad (3)$$

References

1. Podkletnov E., Giovanni M. Impulse Gravity Generator Based on Charged Superconductor with Composite Crystal Structure.
2. Roshchin V., Godin S. Experimental research on physical effects in dynamic magnetic system // Letters to the Journal of Theoretical Physics, 2000, vol. 26, issue 24.
3. Rykov A.V. Principles of full-scale physics. // Institute of Earth Physics RAS, M.: 2001, 58 p.

New Sources of Energy from the Point of View of Unitary Quantum Theory

L.G. Sapogin,

Department of Physics, Technical University (MADI)
Leningradsky pr. 64, A-319, 125829, Moscow, Russia
E-mail:sapogin@cnf.madi.ru, sapogin@cnf.madi.msk.su

Yu.A. Ryabov,

Department of Mathematics, Technical University (MADI)
Leningradsky pr. 64, A-319, 125829, Moscow, Russia
E-mail:ryabov@vmat.madi.ru

V.V. Graboshnikov

Representative in Moscow of Sceptre Electronics Ltd.
Millennium House Business Center
12, Troubnaya Street, Moscow 103045, Russian Federation.
E-mail: sceptre@orbita.ru

Abstract

The Unitary Quantum Theory (UQT) is a new version of the field quantum theory, which has been developed by the principal author (Prof. L.Sapogin) of this paper for over 25 years. The theory is directly related to the problem of new energy sources, and this paper can be of interest for Journal of New Energy for it is the UQT (and not the classical Newton mechanics or the modern standard quantum mechanics) that provides a theoretical basis for the development of new sources of energy and for the explanation of the operation principles of the existing and functioning over unity devices.

The fundamental provisions of the UQT and a number of results received on the basis of it were published in many scientific journals and reported at international conferences (see [1-6], etc.). Generally, the UQT as expressed by the language of formulae and equations represents a new mathematical model of interaction and movement of elementary particles in the form of a complicated system of non-linear integral-differential equations, an important property of this model principally defines the trajectories and velocities of the particle movement in space (unlike the standard quantum theory, which directly defines only the probabilities of the presence of the particles at a certain point in space). Another, and the most essential (for the problem of new energy sources) property of the UQT is the absence of the energy conservation laws and the impulse for single particles in it. That is why the UQT makes theoretically possible processes of energy generation as if from nothing, if they are regarded from the classical mechanics point of view or the standard quantum theory (while the UQT is able to explain the phenomenon), as well as creation of a device with efficiency above 1. In other words, the UQT provides for a theoretic possibility of making a perpetual mobile!

In the 1970's, when the UQT started to be developed, there was nearly no data of the observed phenomena, or any experimental results confirming this unusual theory. Today, such data are abundant. For example, such processes can be named as generation of excessive heat energy during cavitation of very small water bubbles; generation of excessive electric energy in an anomalous gas discharge; excess generation of electric energy when electric current passes through proton-conducting ceramics, etc. Besides, and still more important, operating devices that have been created much more energy than it was necessary for these devices functioning: electric current generators "Testatica" (Switzerland); thermal cell CETI (J.Patterson, USA); heat generators (Yu.S. Potapov, Moldavia, J.Griggs, USA); electric current generators (P.Correa, A.Correa, Canada); electric engines on magnetic ceramics (Japan), and others. The said phenomena and operation principles of the above-mentioned devices can be explained with the help of the UQT.

In this paper we will also touch upon such an important problem as cold nuclear fusion. The feasibility of this nuclear process, which is categorically denied by the standard quantum theory and nuclear physics specialists, was predicted by the author of the UQT as far back as in 1983. This phenomenon was discovered in 1989 (electrochemical experiments, M.Fleischmann, S.Pons). Many subsequently received experimental data confirmed the existence of nuclear reactions under very small energies, of nuclear transmutations in plants and biological objects, very slightly connected with generation of energy [7-8]. From the point of view of the UQT, which provides an explanation of the cold nuclear fusion mechanism, this process can be applied in practice (after the relevant devices are designed) for generation of energy, for production of isotopes, and for nuclear waste liquidation.

Introduction

Inventors, as well as swindlers of all kinds, had long ago been trying to construct, or at least design, a *perpetual mobile*, i.e. an imaginary machine that produced work without any outside energy. Peter the Great even founded the Imperial Russian Academy of Sciences for such research, but the modern Russian Academy of Sciences does not like to recollect this circumstance. On the other hand, the French Immortals in 1755 decided not to consider any *perpetual mobile* projects at all, and, as we would see, were quite right as regards the Newton mechanics. The brilliant success of the classic mechanics has strengthened still more the sacred belief of the mankind in the Divine Infallibility of the Conservation Laws, and today it is nearly indecent to express any doubts about these laws.

Let us first of all find out the origin of the conservation laws in ordinary mechanics. Practically any textbook will tell you that the Energy Conservation Law (ECL) follows from the homogeneity of time, the Impulse Conservation Law from the homogeneity of space, and the Angular Momentum Conservation Law from the isotropy of space. That is why many people have an impression that the conservation laws themselves follow only from the quality of time and space, which is today an undoubtedly relativistic notion. But, for example, the angular momentum is not a relativistic notion. So, such a narrow approach is not altogether correct, and it is necessary to turn to the second Newton law, or the equation of relativistic dynamics and the system insularity. However, *the qualities of the time and space ensue exactly from the analysis of the Newton mechanics*, though they are often construed incorrectly. Let us remind you the correct interpretation.

Homogeneity of time suggests that *if at any two moments of time two similar experiments are made in similar closed loop systems, the results thereof will not differ.*

Homogeneity and isotropy of space mean that *if a closed loop system is moved from one part of space to another, or is oriented differently, nothing will change.*

The making of the fundamental energy and impulse conservation laws from the Newton equation is very simple. Let us put down the main equation of dynamics as

$$\mathbf{F} = \frac{d\mathbf{P}}{dt}$$

For closed loop system $\mathbf{F}=0$ (no external forces operating) and the equation integral will be $\mathbf{P} = Const$ the impulse conservation law.
Now let us take the main equation of dynamics as:

$$\mathbf{F} = m\mathbf{a} = m\frac{d\mathbf{v}}{dt}$$

and multiply it scalarwise by $\mathbf{v}$

$$\mathbf{F}\cdot\mathbf{v} = m\frac{d\mathbf{v}}{dt}\mathbf{v} = \sum_{i=1}^{3} m\frac{dv_i}{dt}v_i = \sum_{i=1}^{3} m\frac{d}{dt}\left(\frac{v_i}{2}\right) = \frac{d}{dt}\left(\frac{mv^2}{2}\right)$$

where v is the module of the velocity vector $\mathbf{v}$. For closed loop system $\mathbf{F}=0$, and the equation integral will be

$$\frac{mv^2}{2} = Const$$

one of the forms of the energy conservation law. From the definition of the angular momentum for a particle,

$$\mathbf{L} = [\mathbf{r} \times \mathbf{P}]$$

Differentiating both parts by *t*, we get

$$\frac{d\mathbf{L}}{dt} = \left[\frac{d\mathbf{r}}{dt} \times \mathbf{P}\right] + \left[\mathbf{r} \times \frac{d\mathbf{P}}{dt}\right]$$

Since the impulse vector is parallel to the velocity vector, the first bracket will equal to zero. On the basis of the resultant equation and the definition of central force as not creating any momentum, we get

$$[\mathbf{r} \times \mathbf{F}] = 0 \quad \text{or} \quad \mathbf{L} = Const.$$

In case of the central force in an unclosed system, the angular momentum is preserved by value and direction. The angular momentum conservation law for a closed loop system results in the same way as the impulse conservation law from the equation of the rotary motion dynamics:

$$\mathbf{M} = \frac{d\mathbf{L}}{dt}$$

For a closed loop system, the momentum of external forces $\mathbf{M}=0$ and the integral of the equation will be the angular momentum conservation law

$$\mathbf{L} = Const$$

In relativistic dynamics the emergence of the energy and impulse conservation laws separately can be easily received from the relativistic ratio for energy and impulse

$$E^2 = P^2c^2 + m^2c^4$$

Term m^2c^4 is an invariant, i.e. the same in all reference systems. In other words, it is a certain constant. This equation can be represented in a slightly different form

$$E^2 - P^2c^2 = Const$$

For the equation to be valid, it is required that

$$E = Const \text{ and } P = Const$$

and this none the other but conservation laws for energy and impulse.

Strictly, relativistic mechanics has a conservation law for 4-impulse vector p^{μ}, but we will not dwell on these details, because small energies are what we are interested in.

In the classical theory, the energy conservation law states that the energy of a closed loop system remains unchanged, so, if the energy of such a system is designated at a moment $t=0$ as E_0, and at the moment *t* as E_t, $E_0 = E_t$.

Conservation laws in ordinary quantum mechanics

The standard quantum theory formulates the energy conservation law in the same way. In quantum mechanics we have the same movement integrals as in classic mechanics. A certain value *L* will be a movement integral, if

$$\frac{d\hat{L}}{dt} = \frac{\partial \hat{L}}{\partial t} + \left[\hat{H}, \hat{L}\right] = 0 \qquad (1)$$

Since $\left[\hat{H}, \hat{L}\right]$ is defined by commutator of operator $\hat{L}$ and of Hamilton's operator, any value *L*, *not depending explicitly on time*, will be the movement integral, if its operator commutes with the Hamilton's operator. When value *L* does not explicitly depend on time, the first item in (1) turns to zero. There remains

$$\frac{d\hat{L}}{dt} = \left[\hat{H}, \hat{L}\right] = 0 \qquad (2)$$

and for the movement integrals not explicitly depending on time the Poisson quantum bracket equals zero. From (1) and (2) it follows that the average value of the movement integrals does not depend on time:

$$\frac{d}{dt}(L) = 0$$

All good papers on the quantum theory prove that probability $w(L_n, t)$ to find at any moment *t* any value of the movement integral, i.e. L_n, does not depend on time. Further, is constructed as the movement integrals not explicitly dependent on time. Since operators $\hat{\mathrm{L}}$ and $\hat{\mathrm{H}}$ commute, they have common proper functions, which are functions of stationary states. Let us note that the latter follows from solutions of the equation without time, which was received from the full equation with imposition of requirement

$$\Psi(\mathbf{r}, t) = \Psi_0(\mathbf{r}) \exp\left(i \frac{E}{t}\right)$$

equivalent to search of only periodic solutions. Further, quite naturally, *there appeared an equation without time with actually imposed conservation laws, because now nothing depends on time*. Expansion by such proper functions looks as follows:

$$\hat{L}\Psi_n = L_n \Psi_n \qquad \hat{H}\Psi_n = E_n \Psi_n$$

where

$$\Psi(x,t) = \sum_n c_n \Psi_n(x) \exp\left(-i \frac{E_n}{\hbar} t\right) = \sum_n c_n(t) \Psi_n(x) \qquad (3)$$

$$c_n(t)=c_n\exp\left(-i\frac{E_n}{\hbar}t\right)=c_n(0)\exp\left(-i\frac{E_n}{\hbar}t\right)$$

Since (3) is expansion into proper functions of operator $L_{n'}$, probability does not depend on time:

$$w(L_n,t)=|c_n(t)|^2=|c_n(0)|^2=Const$$

Since energy is a movement integral and probability *w (E,t)* to find at a moment *t* an energy value equaling E, does not depend on time, then:

$$\frac{dw(E,t)}{dt}=0$$

Let us note once again that it is *the probability to find a certain value that does not depend on time, but not the value itself, which for any separate event is accidental and can assume a wide range of values.*

The quantum energy conservation law in the above form suggests a possibility of defining energy at a given moment without subjecting it to uncontrolled change, which raised no doubts in classic mechanics. But in the quantum theory the energy, without changing its value, can only be measured to

$$\Delta E\geq\frac{\hbar}{\tau}$$

where τ - is measurement duration. Formally, it does not present any difficulties for the energy conservation law, since energy is a movement integral, and we have much time to make long measurement. For example, let us make measurements during time τ, then leave the system to itself for time *T*, and then define energy again. The classic quantum energy conservation law states that the result of the second measurement will coincide with the result of the first measurement to $\Delta\mathrm{E}\approx\frac{\hbar}{\tau}$. But even in the ordinary quantum theory all this is not consistent enough. For the real vacuum fluctuations can interfere, that always influences the results of a single process, but their influence disappears after the passage to an ensemble of events. Here we have a violation of the conservation law due to vacuum fluctuations, though existence of movement integrals, unlike in the Unitary Quantum Theory (UQT).

The generally accepted quantum theory carefully avoids the question of conservation laws for individual events in the case of small energies. This question is either not discussed at all, or it is said that *the quantum theory does not describe individual events. Yes, it does describe individual events, but it can only predict a probability of this or that result.* It is clear that in this case there are no conservation laws for individual events (it is wrong to speak about it in case of an accidental result of an individual event), and they appear only after the averaging by large ensembles of events. Essentially, it can easily be proved that classic mechanics follows from quantum mechanics after summing up by a large number of particles, because for a sufficiently big mass, the length of the de Broglie wave becomes much less than the body dimensions, and no quantum-wave qualities can be talked about.

Conservation laws in Unitary Quantum Theory

In the UQT [1-14] any quantum particle is not a point, but a source of field like in the ordinary quantum mechanics, but it represents a bunched field (wave packet) of a certain unified field. The dispersion equation of such a nonlinear field turned out to be such that the wave packet (particle) during its movement periodically appears and disappears, and the envelope of this process coincides with the de Broglie wave. Numerous particles during their periodic disappearance (spreading in the Universe) are repeated appearance from vacuum fluctuations. A theory of quantum measurements has been built, and the probability interpretation follows from the mathematical formalism of the quantum theory [10,11], and it is not postulated as in conventional quantum mechanics. Unfortunately, the main UQT equation turned out very complicated, for it is a system of 32 nonlinear integral-differential equations, which could require for their solution some new mathematical methods. But from this the relativistically invariant Hamilton-Jacoby equation, and the Dirac equation system strictly follow.

Papers [13,14] give a solution of the simplified scalar integral-differential UQT equation, which gave a localized solution for the form of a wave packet representing a particle. It turned out that the integral from a bilinear combination of such a solution for the whole volume gives with the precision of 0.3% the value of a non-dimensional elementary electric charge [13,14], which was essentially its first theoretical calculation. Then, this solution in the form of a periodically appearing and disappearing wave packet (which square describes the density of a spatial charge) can be replaced by an oscillating charged particle [15-18], the movement whereof will be described by the conventional Newton equations:

$$m\frac{d^2\mathbf{r}}{dt^2}=-2Q\mathbf{GRAD}U(\mathbf{r})\cos^2\left(\frac{mt}{2\hbar}\left(\frac{d\mathbf{r}}{dt}\right)^2-\frac{m\mathbf{r}}{\hbar}\frac{d\mathbf{r}}{dt}+\varphi_0\right)\qquad(4)$$

$$m\frac{d^2\mathbf{r}}{dt^2}=-2Q\mathbf{GRAD}U(\mathbf{r})\cos^2\left(-\frac{m\mathbf{r}}{\hbar}\frac{d\mathbf{r}}{dt}+\varphi_0\right)\qquad(5)$$

where *m, Q,* $\mathbf{r}$ - mass, charge, and radius-vector of the particle, $U(\mathbf{r})$ – external potential, φ_0 - initial phase.

Since $\mathrm{E}=-\mathrm{GRAD}U$, and a magnetic field also exists, the Lorenz force should also be calculated for $\mathbf{F}=\frac{Q}{c}[\mathbf{v}\times\mathbf{H}]$, but in the electromagnetic wave **E** and **H** are equal, and for small energies value $\frac{v}{c}\to 0$, and force **F** can be ignored. Both these equations produce qualitatively similar results for different problems, but the first non-autonomous equation evidently does not have any movement integrals at all, and any hope for analytical solutions is very unreal. But for the second autonomous equation such hope still exists. Let us note that these equations describe more accurately the experimental results of scattering on the coulomb potential than the classic Rutherford formula! Application of these equations for the tunnel effect and scattering on short potential also produces correct results, but in this case passage through a high barrier (tunnel effect) will be defined by the initial phase. Of greatest interest, however, is the harmonic oscillator problem.

It is possible that a change in the properties of a material point in the process of its movement is just another step in the material point movement theory. In conventional mechanics this idea is not altogether new. There are Meshchersky's equations for bodies with a changing mass, and Tsiolkovsky's equation for a rocket. But so far, in the conventional quantum theory, the particle has a permanent and stable in space and time set of properties, and in the UQT all the parameters of the particle are changed and oscillate during movement.

It should be noted that *Newton did not introduce the notion of a material point at all,* and it would be ridiculous to think that he was not able to have this natural and rather trivial idea. Most probably, and it is not by chance, for today many troubles of the field quantum theory are rooted in the approach to the particle, as to the point, the most vivid example being a large bouquet of divergences. Nevertheless, this approach is very convenient and should only be used correctly. Let us also remember, that in accordance with the Newton corpuscular theory, beams of light were to be regarded as a flow of certain particles. They are emitted by a shining body in all directions and move in an empty space or a homogeneous medium evenly and straight, i.e. in the same way as the ordinary material particles do in the absence of any external or interaction forces. Newton explained reflection and refraction of light beams on the surface of border between two homogeneous mediums by the effect of certain forces on this border, in the direction perpendicular to the surface. These forces changed the normal velocity component, but did not touch upon the tangential one, which allowed to derive the reflection and refraction laws. However, the inability of such a theory to account for the light partial reflection and passage phenomena, as well as the Newton rings (which he himself discovered), led him to bouts (or fits) theory, which is quite modern, although nearly forgotten. Newton believed that for full explanation of all the processes it was necessary to suggest that some light particles could experience reflection bouts, and others – passage bouts. Let us imagine light falling to a flat surface, which is partially, reflects and partially passes. With quantum description of this phenomenon, a particle connected to the falling wave at the time of hitting the surface has a certain probability of passing or being reflected, and Newton simply used the word "bouts" in place of the word "probability".

It is absolutely clear that all descriptions of processes by the equation with an oscillating charge will be an approximation, because it is evident that no movement equations for a material point can describe even the simplest interference processes on a semi-transparent mirror, during which a material particle should be divided in two parts which will later eliminate each other by destructive addition. It is surprising, but the numerical solution of the problem of scattering on a short potential (the Ramsauer effect) for equations (4) and (5) gives the correct diffraction picture! But if we want to describe an individual particle correctly in the conventional quantum mechanics, the picture becomes inexact and purely probabilistic. At every given moment of time a particle can exist in only one of the mutually incoherent states, because one particle cannot move in different directions simultaneously (it cannot have many impulses at the same time). Nevertheless, there seems to exist a whole class of processes, where description with the help of equations (4) and (5) have certain sense. It is well known that in all experiments the local energy and impulse conservation law in individual quantum processes are true only under high-energy values. But under small energy values it is not so, at least because of the ratio of uncertainties and the probabilistic character of all the quantum theory predictions, and the idea of a global, not local ECL, is invisibly present in the quantum mechanics, and is certainly far from new.

In the strict UQT and the quantum measurement theory, a great role belongs to unavoidable vacuum fluctuations. It is clear that these fluctuations are totally unpredictable and non-invariant in relation to space and time translations. The same can be said otherwise: there are no habitual properties of time and space in this theory. Space-time is now not homogeneous and not isotropic. For example, if the system is transferred to a new point in space, or a certain experiment is repeated at another time, at the point where particle parameters are studied, and it interacts with the macro-device, a new value of vacuum fluctuations (different from the previous one) can appear and produce a different result. Of course, all this is only true for small energies and individual events.

Still more destructive is the UQT for the notion of a closed system. For individual events under small energy values this notion is simply unacceptable for the following reason: vacuum fluctuation at the location of the particle (e.g. in a potential pit) can be sharply changed at any moment. It can be caused by different factors – the nature of vacuum fluctuations itself, or the tunnel effect of another random particle.

Sometimes it is stated that conservation laws follow from the Nether theorem, though these results are present in the works by D. Gilbert and F. Klein. For any physical system, the movement equations from which can be received from the variation principle, each one-parametric continuous transformation that leaves the variation functional invariant, corresponds to one differential conservation law, and there exists a clearly conserved value. It is easy to see, however, that vacuum fluctuations imposed on the varied function (integral of Lagrangian) do not in sum remain unchanged during parametric transformations (at least today it seems so), and this consideration does not work without preliminary of ensemble.

And now we are in for a little philosophy. The local Energy Conservation Law (ECL) in individual processes follows from the Newton equations for closed systems. It would be naive to think that its local formulation will be preserved forever, and would be a bad mistake to transfer the ECL from the Newton mechanics to the quantum processes without any changes, because the latter are more fundamental.

References to the first principle of thermodynamics are, strictly speaking, groundless, because this principle is a postulate. For example, well-known Russian mathematician N. Luzin, in a letter to an inventor wrote that the first principle of thermodynamics is the result of unsuccessful attempts of the mankind at building a *perpetual mobile*, and strictly follows from nothing. *Today it may be said with a great degree of certainty that no sophisticated machine in the framework of the Newton mechanics can be a perpetual mobile,* and the decree of the French Academy of 1755 not to consider any *perpetual mobile* projects is still valid. We will only add that now it is valid only for those projects that are based exclusively on the Newton mechanics.

There is the tendency in modern physics to reduce ECL, especially in theory, to the rank of a secondary derivation from the movement equations (movement integrals). Some physicists restrict the ECL to the framework of the first principle of thermodynamics, others, like D. Blokhintsev [37], think it quite probable that with the development of a new theory the form of the ECL will undergo certain changes. F. Engels wrote in his "Dialectics of Nature": "…none of the physicists actually regard the ECL as an eternal and absolute law of nature, a law of spontaneous transformation of the movement forms of the matter and the quantitative constancy of this movement in all its transformations". But many people do not share this opinion. M. Bronstein in his book "Structure of Matter" wrote: "The ECL is one of the main laws of the Newton mechanics. Nevertheless, Newton did not ascribe to this law the general character that this law actually possesses. The reason for this *erroneous* (italicized by authors) opinion of Newton of the ECL is very interesting…". It is now clear that in view of the above, such an opinion was not at all erroneous. Let us remind you that Newton predicted many things, even the UQT, in his "bouts theory".

On the other hand, the authors of quantum mechanics realized that there was no conservation law for single quantum processes under small energies at all. The idea that the construction of ECL, together with the second law of thermodynamics, was a statistical law, true only on the average and inapplicable to individual processes with small energy, first occurred to Schroedinger, and later to Bohr, Kramers, Slater, and Gamov. In 1923 Bohr, Kramers and Slater made a desperate attempt to develop the theory, where the energy and impulse conservation laws in case of scattering would be true only statistically, on an average for long periods of time, but would be inapplicable to elementary events. Lev Landau even called it "Bohr's wonderful idea".

Later, however, the authors gave up this approach and, besides, this idea at that time did not follow from the quantum theory equations, and the authors, *to come out of the predicament, simply declared that quantum mechanics did not describe individual events at all*. Thus, the most vivid paradox of the quantum science was removed by a simple ban on thinking about it! But the ingenious idea that conservation laws do not apply to individual quantum processes and emerge only after the averaging by the ensemble of particles remains alive. This idea might have been a little premature, and, possibly, should be a little different.

The Unitary Quantum Theory (UQT), on the contrary, individual particles, and the difference in their behavior is accounted for by the initial phase of the wave function. In this case, local conservation laws do not exist for a single particle, and measuring the initial phase or some other parameters for an individual particle is quite a different matter. It is not true that the UQT has given up probabilistic description. Probabilistic interpretation remains, but the probability now is strongly dependent on the initial phase. Although the equations with an oscillating charge can determinately predict a particle's behavior, the measurements can be made only with the help of a macro device, which will give only a probabilistic result. Impossibility to determinate measurements does not change anything, for the UQT provides for a possibility of influencing the probability value, which was earlier unavailable. The existing Von Neumann theorem about hidden parameters does not effect our result, but the relevant discussion is too cumbersome, and we will leave it out.

In other words, ***all the requirements****, wherefrom the classical conservation laws follow, are now absent. We can hardly expect the conservation laws for individual particles to be preserved under small energies in such a situation.* Today we are convinced that the classical energy, impulse and angular momentum conservation laws for individual quantum objects are not valid under small energy values because of periodic appearances and disappearances of the particle. All direct experimental tests of the conservation laws were made for large energy values, and for small energies of an individual particle only probabilistic results can be received, and, in this case, it would be indecent even to recall the conservation law.

Energy generation and perpetual mobile

Let us make the following imaginary experiment. For simplification purposes we will use in our reasoning a certain quantum ball-particle. When a classical ball approaches a wall (perpendicularly for simplification), the speed of the reflected ball is always equal to the initial speed (we ignore friction and regard the ball and the walls as absolutely elastic). In the case of a quantum ball, the speed of the reflected ball will acquire in different experiments with absolutely equal initial conditions a whole range of values: some balls will be reflected at a speed greater than the initial speed, others – at a speed equal or lower than the initial speed, and all this is described by quantum mechanics.

Let us ask the following question: what if a second wall is found, parallel to the first one, in order for the ball to increase its speed after each reflection from the wall? Then we will have increased ball energy without any special efforts on our part. Such phenomena appear in the problem of particle oscillations in a potential pit (not necessarily parabolic) on the basis of equations (8) and (9), when four types of solutions are possible, three of which are most important for us: stationary, "maternity home", and "crematorium". In the two latter solutions traditional conservation laws do not work. These solutions are presented in Fig. 1. Such oscillator behavior explains many experimental facts. From the physical point of view, it means that in stationary solutions with fixed discrete energies (conventional quantum mechanics) the speed of the particle reflected from the wall will be equal to the speed of the falling particle. If the speed of the particle is decreased after each reflection, it will mean the "crematorium" solution, and if it increases, the "maternity home". Scenarios for situations will depend on the initial phase of the wave function and the particle energy. In ordinary situations the "crematorium" and "maternity home" solutions always compensate each other, and we find conservation laws.



Fig. 1. Dependence of the distance between the moving charge and the nucleus on time for autonomous and non-autonomous equations.

The task of the future developers of new energy systems of the 21st century will consist in creating such initial conditions for a great number of particles making up a body that only the "maternity home" solution would be realized, and the "crematorium" solution would, if possible, be suppressed.

It follows from the above that if the unitary quantum theory ideas are applied correctly, there is no fundamental taboo for a perpetual mobile. Such a taboo, as it was shown, does not formally exist even in conventional quantum mechanics (no conservation laws for individual processes with small energies), and, in order to generate energy, they should be somehow accumulated (all random processes with excess energy should be grouped together). But conventional quantum mechanics refuses to describe individual events and is unable to offer any ways for such grouping. The unitary quantum theory seems to offer such an opportunity.

However, the great idea of free energy generation was distorted by effort of some research associations interested to keep their stability degree, that everyone who started speaking about it was considered to be a crazy man.

Modern experimental physics has verified the correctness of conservation laws either for very large energies in individual quantum events, or for big macroobjects, when automatic averaging by ensemble is made, but the area of very small energies for individual events today is a *terra incognita*.

*I*n order to see how the conservation laws for reflection (repulsion) of an individual particle from the Coulomb heavy nucleus with different values of the initial phase are violated, we have solved numerically one-dimensional equations (8) and (9) under the different initial conditions:

$$\hbar = 1, m = 1,\ 2Zze^2 = 1,\ x_0 = 100,\ V_{x0} = -0.1$$

In the Fig. 2 the distances between the moving particle and repulsive nucleus are shown as a time function, for different initial phases in cases of non-autonomous and autonomous equations.



Conventional solution Mathernity home solutions Crematorium solutions

Fig.2 Three types of solutions for oscillator

It is evident from the calculations that the speed of a reflected particle can be equal, lower or higher than the speed of a falling particle. This situation seems to be true for all potentials.

Calculations were also made for other potentials: harmonic oscillator, Yukawa, Gauss, dipole, hyperbolic secant, and Wood-Saxon, and the quality results were nearly the same. If we sum up the impulse of all the particles falling with different phases and compare it with the summarized impulse of all the reflected particles, the summarized reflected impulse, for example, for the Coulomb potential, will be several percent higher than the summarized impulse of the falling particles. For other potentials such a small deviation can even be in the opposite direction. On the whole, this problem is very complicated and requires additional research, because all this is also dependent in quite a complex way on the initial conditions (initial speed, phase and distance).

Philosophically, any categorical taboos, like the impossibility of creating a *perpetual mobile*, are absolutely unacceptable. If everyone is convinced of it forever, the conservation laws and *perpetual mobile* taboos will remain unshakable as long as the human civilization exists. Of course, the funeral of the Conservation Laws can be very prolonged. Anyway, we are not going to do it, and our article might be just a cleanup for the future tomb, and the splendid funeral with all the necessary honors will be organized by future generations. *On the other hand, these laws will never die out completely and will surely be applied, but such spheres of science and technology will appear, though small at first, where these laws are not valid.*

The truth should be accepted irrespective of where it comes from. Words of F. Engels from the "Dialectics of Nature" will be quite appropriate here: "When the solar system ends its life circle and shares the fate of all the finite things, when it falls victim to death, what will happen next? Thus, we come to a conclusion that the heat emitted into the universe should have an opportunity, in a way yet to be established by the natural sciences, to turn into another form of movement, where it can be accumulated again and start functioning. And in this casethe main problem that prevented transformation of dead suns , back to red-hot nebulas will disappear".

The question of whether the conservation law exists in global form (we have already proved its not being local) remains open, because nothing leads to it except the inertia of the human mind. This inertia was based on the Newton laws, which were replaced by quantum laws. This mental inertia leads to a situation, when in case excessive energy is generated during solution of movement equations, a question arises how it can happen, and where it comes from. Of course, if a particle (e.g. a photon) falls on a semitransparent mirror, the packet is divided into two halves, which, due to imposition of vacuum fluctuations, will be recorded by photomultipliers as full-fledged photons [1-5]. The result is that energy is taken as if from vacuum: two photons appear in place of one. Another photon can be divided on the mirror into two halves, but they will not be recorded by the meters, and the energy will allegedly pass into vacuum. So, at one time we borrowed energy from vacuum, and then gave the same amount of energy back to vacuum at another place. You can think like that, and this process might take place. But if we consider the equation with an oscillating charge, the energy and impulse conservation laws are not valid there for solution of the movement problem, and vacuum fluctuations have nothing to do with it at all. As for the question of where the energy comes from, it is the result of our mental inertia, and is, essentially, an atavism imposed by the Newton mechanics. But the latter appears as a result of an extreme passage from quantum mechanics, which is more fundamental.

It is interesting to note that there is a bomb in the logical definition itself of the energy conservation law. If energy is something that cannot appear or disappear and always simply passes from one form to another, the only value satisfying this condition is zero. We are far from assuming that energy does not exist. But the problem of existence is solved differently in different philosophical systems, and the mathematical approach seems to be the most correct one: *an object exists if it is free from contradictions*. Energy has bad luck in this case, for under such an approach it should be zero.

Some cosmologists (for example, British prof. Fred Hoyle) are very willing to have a process, in accordance with which the Universe has certain places where energy appears from other certain places, in which it is eliminated. Besides, any philosopher at least a little bit familiar with astronomy, looking at the bright night sky, will see the birth of matter and its expansion into a still greater space. But for this purpose the Global Energy Conservation Law is superfluous and only denies what is observed. The head reels…

Cold Nuclear Fusion and Nuclear Transmutation.

Let us approach the epoch-making experiments made by Fleischmann and Pons in March 1989 [30] from the positions of the equation with an oscillating charge. One of the authors predicted in 1983 [9] the possibility of such nuclear reactions under very small energies. Without going into well-known details, we will sum it up very briefly: cold nuclear fusion exists, and there are no people or theories capable of giving a clear explanation. The chain of various mechanisms meant to explain this intriguing phenomenon is growing, but few really believe in them. The reason is as follows.

When a charged particle interacts with the nucleus, the potential energy is like in Fig. 3, where the right top part of the curve is conditioned by mutual Coulomb repulsion between the nucleus and the charged particle.

The repulsion potential will be

$$U(r)=\frac{Zze^2}{r}$$



Fig.3

where Z – charge of the nucleus, and z – charge of the approaching particle, e – charge of the electron, r – distance between the particle and nucleus. When $r=R$ (critical distance), then the potential energy curve goes sharply down, which is due to the emergence of intense nuclear gravitation, the potential whereof today appears more complex than could be imagined mathematically. If the charged particle overcomes the Coulomb barrier with a height of

$$B_c=\frac{Zze^2}{R}\approx\frac{Zz}{\sqrt[3]{A}}MeV$$

it will further get into the nuclear gravitation area and a nuclear reaction will take place.

Let us look at the nuclear interaction of a charged particle with kinetic energy $T<B_c$. From the point of view of classical mechanics, there will be no nuclear reaction in this case, because the particle will approach the nucleus and at a certain distance $r<R$ from the top of the Coulomb barrier will turn back and be reflected from it. However, from the point of view of quantum mechanics, there exists a tunnel effect, and the probability of such a tunnel passage, or transparency of potential barrier D is described by a well-known formula:

$$D\approx\exp\left(-\frac{2}{\hbar}\int_{r_1}^{r_2}\sqrt{2\mu(U-T)}dr\right) \qquad (6)$$

where $\mu=\frac{Mm}{M+m}$ is reduced mass. The bottom integration limit r_1 coincides with the nucleus radius R, and the top limit r_2 can be found from the condition $T=\frac{Zze^2}{r_2}$. After integration we will get

$$D=\exp(-2g\gamma)$$

where $g=\frac{R}{ƛ_{B_c}}$; $\gamma=\sqrt{\frac{B_c}{T}}\arccos\left(\sqrt{\frac{T}{B_c}}\right)-\sqrt{1-\frac{T}{B_c}}$,

and value $\lambda_{B_c}=\frac{h}{\sqrt{2mB_c}}$, the de Broglie wavelength corresponding to the kinetic energy of the particle equal to the barrier height $T=B_c$. If $T<<B_c$, expression (6) is easily transformed to look as

$$D=\exp\left(-\frac{2\pi RB_c}{\hbar v}\right)=\exp\left(-\frac{2\pi Zze^2}{\hbar v}\right) \qquad (7)$$

where v is velocity.

Let us now see what the shocking cold nuclear fusion will look like on the basis of the above considerations. The deuteron energy in an ordinary electrolytic Fleischmann-Pons cell will be about 0.025 eV, and the height of the Coulomb barrier for this case is $B_c=\frac{Zze^2}{\sqrt[3]{A}}=0.8MeV$. In classical mechanics it would be just naive to talk about overcoming such a barrier with a height dozens times greater than the kinetic energy. Let us now see how the tunnel effect will improve the situation. Let us assess the value of g and γ for the case of collision between two deuterons with such energy:

$$g=\frac{R\sqrt{2mB_c}}{\hbar}=1.9;$$

$\gamma=\sqrt{\frac{B_c}{T}}\arccos\left(\sqrt{\frac{T}{B_c}}\right)-\sqrt{1-\frac{T}{B_c}}\approx 8883$ and the probability of such a process will be $\exp(-2\cdot 1.9\cdot 8883)\approx 10^{-7328}$, i.e. practically pure zero. The fusion cross-section will be defined by the product of nuclear cross-section and the tunneling probability:

$$\sigma=\sigma_{nucl}D$$

and, in the case under review, is also a very small value. If the clash parameter of deuterons is not zero, the emergence of centrifugal potential

$$U = \frac{\hbar^2 l(l+1)}{2mr^2}$$

will still further lower the probability of such interaction.

It is these very circumstances that make the nuclear physics scientist think that there is no cold nuclear fusion as such. For example, such a serious and responsible edition as Encyclopedia Britannica 2001 found no place for the notion of cold nuclear fusion at all. Such an official position can be understandable only from the point of view that quantum mechanics is absolutely true and unshakable. Despite this, for the 12 years since the Fleischmann-Pons experimental discovery, nearly 30 international conferences have been devoted to this subject, there are lots of books and magazines on this subject, and the number of articles on the problem is nearing ten thousand. Today the situation is gradually developing in the positive direction, and the research in the field of hot nuclear fusion, which has already wasted over $90 billion for 45 years, is slowly coming to naught.

But today there exist well known experimental data on cold nuclear fusion. They are numerous and various. We will dwell only upon the most important and sufficiently reliable results. Thus, the classical view of electrolysis of a palladium cathode saturated with heavy hydrogen in heavy water identifies an anomalous quantity of heat energy up to 3 kWt/cm^3, or up to 200 Mj per small sample. Products of nuclear reaction have also been found: tritium (10^7 - 10^9t/s), neutrons with energy of 2.5 MeV (10-100n/s), and helium. Absence of He^3 among the reaction products shows that heat is not generated by reaction $d+p$. Besides, emission of charged particles ***(p, d, t, γ)*** is observed. Similar processes are observed in case of a gas discharge on a palladium cathode, of phase passage in different crystals saturated with heavy hydrogen, irradiation of deuterium mixture with a powerful sound or ultrasound flow, in cavitating microbubbles in heavy water, in a tube with palladium powder saturated with heavy hydrogen under a pressure of 10-15 atm., etc. In certain reactions (e.g. $d + t \rightarrow \alpha + p$) neutrons of 14 MeV are absent, and such a strange situation occurs in other cases too. Activity of Li^6 , Li^7 in reactions with heavy hydrogen and protons failed to be discovered, whereas reaction

$$K^{39} + p \rightarrow Ca^{40}$$

was well recorded even in biological objects. But the most intriguing fact of all these processes is the shortage of nuclear reaction products for explanation of the emerging heat effects. Thus, in certain cases the number of nuclear reaction products (tritium, helium, neutrons, quanta) should be millions of times greater in order to account in some way for the quantity of the generated heat. Generation of such a big amount of energy cannot be accounted for by either chemical or nuclear reactions, or by phase passages. The well-known interaction $d+d$ goes along three channels:

D + D —> T (1.01) + p (3.03) (Channel 1)
D + D —> He (0.82)+ n(2.45) (Channel 2)
D + D —> He + γ(5.5). (Channel 3)

All these reactions are exothermal. The third channel has a very small probability. It was experimentally discovered that they could occur under very small energies. In a molecule D_2 the equilibrium position between atoms is 0.74A and in accordance with the conventional quantum theory, these two deuterons could accidentally enter a nuclear fusion reaction. But the interaction value is very small $\lambda_{D_2} = 10^{-64} c^{-1}$. There is a known estimate that in the water of all seas and oceans there are 10^{43} deuterons, and in 10^{14} years there will be only one fusion.

It follows from the aforesaid that the main problem impeding the occurrence of the $d+d$ reaction lies in the existence of a very high Coulomb barrier. Our approach allows for this problem to be solved, and there is such an opportunity in the UQT. The UQT equation solutions show that the distance to which deuterons can approach each other is strongly dependent on the phase of the wave function (by the way, it is absolutely clear intuitively).

Let us consider the one-dimensional problem [15-18,31]. There is a stationary nucleus with charge Ze at the point of origin, and another nucleus is approaching it along axis x (charge ze, mass m) at a certain initial velocity. The non-autonomous and autonomous equations of such a problem will look as follows:

$$m\frac{d^2x}{dt^2} = -\frac{2Zze^2}{x^2}\cos^2\left(\frac{m}{2\hbar}\left(\frac{dx}{dt}\right)^2 t - \frac{m}{\hbar}\frac{dx}{dt}x + \varphi_0\right) \quad (8)$$

$$m\frac{d^2x}{dt^2} = -\frac{2Zze^2}{x^2}\cos^2\left(-\frac{m}{\hbar}\frac{dx}{dt}x + \varphi_0\right) \quad (9)$$

Since an analytical solution was not found for all the areas of initial phases , numerical methods were applied with the following initial values: $Z=z=1$, $e=1$, $m=1$, $x_0=-10$, $\hbar=1$ for different initial velocities and initial phase values. As had been expected, braking or acceleration of the particle happens only when the charge is large. But at the last stage, under certain initial phases close to $\frac{\pi}{2}$, a wonderful process occurs: velocity, charge and repulsing force are very small. Due to phase ratios, the small charge is not changed for a long time, which means that the particle (or rather what is left of it) is not influenced by any forces, and it is crawling at a permanent small speed for a very long time ("the snail effect") inside the field of another particle, and can come very close to the center. Such movement with a very small charge and a small speed can last for several hours, and disconnection of the external field will not effect this movement. This process reminds of quiet and invisible scout penetration into the enemy territory. This phenomenon occurs only in certain phase areas, and can be conveniently called a phase hole, which is illustrated in Fig. 4 resulting from the solution of equation (8).



Fig.4. Distance to the turning point of the moving charge depending on the initial phase value for different initial velocities.

Let us note in passing that now we can account for one of the nuclear physics anomalies, which has a tendency to be totally ignored. Under a nucleon energy of 1 MeV, its velocity is 10^9 cm/s, nuclear radius is 10^{-12} cm, and the passage time of the nucleus is 10^{-21}s, but the time period in which the nucleon passes is usually anomalously long - 10^{-14} and even more, and it is absolutely unclear what the nucleon is doing in the nucleus so long. In our model it is easily explained by the “snail effect”.

For the same equation, the minimum distance was calculated between the charges dependent on velocity (Fig. 5) for different initial phase values. For comparison, Fig. 5 also shows the result of the classical calculation based on the Coulomb law. It is obvious from Fig. 4 and 5 that the minimum distance to which charges can approach each other is nearly independent of kinetic energy, but with reduction of speed the initial phase area width is reduced as well. In other words, reduced energy brings also reduced probability of a nuclear reaction.



Fig.5 Minimum distance between charges depending on the initial velocity for different initial phase values.

The same results are true for the autonomous equation (9). Under the conventional quantum theory, the ratio of the reaction speeds in the tritium and neutron channels should be close to unity: $\frac{t}{n}=1$. But in many experiments on cold nuclear fusion this value is very different from unity and equals $\frac{t}{n}=10^9$. In different experimental situations it is reproduced by different experimental groups with a very high accuracy. This very intriguing problem has so far received no simple explanation. Let us dwell on a possible cause for such aphenomenon. With a small velocity in the phase hole, neutrons are affected by nuclear gravitation forces, and protons are affected by electrostatic repulsion forces. Under the effect of this momentum, the deuteron will have enough time to turn in such a way that the neutron parts of the deuteron would faceeach other. After the neutron gravitation the nuclear forces will be saturated, which will weaken the proton connection, and one of the protons will leave the system. This reaction can be conditionally presented in the following form:

$$d+d\to p+(n+d)\to p+t$$

This reminds of the Oppenheimer-Phillips effect.

It is well known, however, that under big energies, the probabilities of the first and second reaction channels are the same, and this phenomenon should somehow be accounted for. Increased probability of the neutron channel with growing energy can be connected with the appearance of secondary neutrons in the reaction *T + D = He + n (14.1 MeV).* In a deuterium-rich environment, a big part of the resultant tritons will pass to neutrons in the process of this reaction, which has a cross-section of 5 barns under an energy value of 70 KeV. According to assessments in [32], the number of such secondary neutrons per one triton is $7.9\cdot10^{-12},1.7\cdot10^{-9},2.7\cdot10^{-6}$ for energy tritons 10, 20 and 100 KeV respectively. Thus, the prevalence of $\frac{t}{n}>10^6$ can be expected only in those reactions, where tritium is born with energies over 40 KeV.

It should not be assumed, however, that the phase hole phenomenon in its whole area leads to a nuclear reaction. It can be assumed that reduction of the Coulomb repulsion is followed by reduction of strong interaction. But how? Today nobody knows the exact equation of the strong interaction potential. Besides, the particle approaches the turning point $X_{\min}$ is rather "thin". Will it be able to take part in a full-fledged nuclear reaction, or will it fly through, like it happens with the electron in the s – states of the atom? There are very narrow phase areas, when soon after the particle stops the charge grows quickly and is sharply accelerated. The charge can even be maximum in the nuclear force effect area. May be, it is this narrow phase area that is responsible for cold nuclear fusion, and in case of strong interactions the phase hole mechanism must be operating as well.

It was discovered long ago that nuclear transmutations have a mass character (especially in plants and biological objects), but they have little to do with energy generation. Examples of such reactions:

$$Mn^{55} + p \rightarrow Fe^{56} \;;\; Al^{27} + p \rightarrow Si^{28} \;;$$
$$P^{31} + p \rightarrow S^{32} ; K^{39} + p \rightarrow Ca^{40}$$

In reactions of this type, a very slow proton (with practically zero kinetic energy) penetrates the nucleus in the above-mentioned way and remains there. *No intranuclear energy is generated, because both before and after the reaction the nucleus remains a stable object.* In classical nuclear physics, the nucleus usually became unstable after it was penetrated by a charged nucleon with a large kinetic energy and always broke into parts, and the nuclear debris had an even greater kinetic energy. Reactions of the above type were considered impossible under small energies and for this reasons were not studied by classical nuclear physics. It seems to be *a completely new type of nuclear transmutations, not recognized by modern nuclear science, but experimentally discovered rather long ago.* Today there is a great deal of experimental material confirming mass nuclear transmutation phenomena. Moreover, there are many projects of neutralizing nuclear excess with the help of this technology. Journals *Infinite Energy, New Energy, Cold Fusion, Fusion Facts*, etc. and Internet are full of such projects.

Of course, a change in the nuclear charge will result in restructuring of electronic atom shells, but the energy related to this process will be about several electron-volts and is nothing in comparison with the energies of nuclear reactions from several to hundreds million electron-volts. By the way, nuclear engineers are accustomed to such energy ranges in nuclear reactions. It was this circumstance that made them deny *a priori* all nuclear processes in biology, because under such energy values of the debris dozens and hundreds thousand of complex biological molecules will be destroyed.

Quite a long time ago, Lois C. Kervran [33] wrote a book about nuclear transmutations in biology, and now, nearly 20 years later, its second edition was published! It gives, evidently for the first time, numerous *experimental* data of the above-mentioned phenomena. The reaction of the official science is very interesting. For example, well-known physicist Karl Sagan, after reading the book about such *experimental* data, advised Kervran to read elementary textbooks in nuclear physics!

Some time later a research was made by Panos T. Pappas [58], who studied one of the well-observed nuclear reactions in biological cells:

$$Na_{23}^{11} + O_{16}^{8} = K_{39}^{19}$$

Classical biology has long known about the existence of equilibrium, when the ratio between the number of K and Na ions is maintained with greatest accuracy despite the shortage or even absence of K ions in food. Later, in work [59] this nuclear reaction was even called the life equation, and the existence of such nuclear reactions in biological objects was proved by M.Sue Benford with the help of direct physical methods.

All thermonuclear fusion programs are based on blunt heating and compression of the reacting material. Despite the progress achieved, the head of the works in England, Dr. Alan Gibson [34], established several years ago that the model reactor design would be created not earlier than in 50 years. Today, this point of view is generally accepted. Even if the reactor is once made (although the authors have grave doubts about it), it will be very complicated, expensive, and harmful for the environment.

Classical approaches have so far not yielded any positive results, despite multi-billion investments and a great number of physicists, engineers, service personnel, and managers involved. It is only natural that this army of researchers is a potential impediment for all alternative projects of new power engineering. It has been noted that *"viability" of any idea is proportionate to the number of people involved and investments made.* For these reasons, the Fleischmann-Pons works were given a hostile reception in the USA and other countries.

All the controlled thermonuclear fusion programs are accompanied with the adjective "controlled", although there is no control whatever. It is simply that the initial quantity of the reacting substance is *prudently* made very small. For example, a ball of lithium deuteride during laser reduction has a diameter of several mm. So far no one has been seriously considering the question of utilizing the energy of an explosion of such a ball, which is approximately equal to the energy of an explosion of a box of antitank grenades.

The straightforward approach to fusion used by the modern science is very natural, because quantum mechanics has no methods of influencing this process. The future of really controlled nuclear fusion systems may be not on the way of primitive and blunt method of heating and compression of the material, but following UQT on the way of using collisions of nuclei having small energy and corresponding fine adjustment of the wave function phase.

It is essentially possible in case of imposition of the external controlling electromagnetic field on the reacting system, which contains quasi-fixed ordered deuterium atoms and free deuterons. The same properties can be demonstrated by special atomic grid geometry. Diffraction scattering of a deuteron flow on such grids will lead to automatic deuteron selection by energies and phases.

It seems that in the Fleischmann-Pons electrochemical experiments such an ordered system existed in the *Pd-D* grid, and some phasing occurred, which accounts for the results of these experiments [30].

Today it appear to us that the cold nuclear fusion processes will be effectively used for nuclear waste liquidation and production of isotopes.

Many researchers [35,36] discovered that the quantity of heat generated in the process of electrolysis of ordinary water on nickel electrodes (there is no hope for nuclear reactions in such systems) is the same as in the electrolytic cell with heavy water. It confirms other measurements, which showed that the quantity of nuclear reaction products is millions times less than is required for such an amount of generated heat, and its origin remains a mystery.

Further we will give certain concrete data demonstrating the phase values of a deuteron with an oscillating charge, under which the deuteron can approach the nucleus to a critical distance of 10^{-12} cm or less, i.e. giving the data to estimate the value of the above-mentioned phase "hole" in the interval (0,π) of the phase change.

Assume that the stationary nucleus with the charge q is placed to the coordinate origin x=0 and the deuteron with the same charge q is placed at the initial moment t=0 to the point $x_0 < 0$on the x-axis, and the deuteron velocity equals $\dot{x}_0 = v_0 > 0$. The units of mass, length and time are chosen in such a way that $m = 1, \hbar = 1, c = 1$ (*m* - deuteron mass, *c* - light velocity). Charge *q* equals 0.085137266. Our units are connected (to 4 significant figures) with the system (kg, m, s) as follows:

1 mass unit = 3.345×10^{-27}kg,
1 length unit = $1.049 \cdot 10^{-16}$ m,
1 time unit = $3.502 \cdot 10^{-25}$ s.

The electron velocity corresponding to its energy of 1eV equals $5.931 \cdot 10^{7}$ cm/s. The deuteron velocity corresponding to such energy will be assumed to be 3680 times less, and in our units it will be $5.372 \cdot 10^{-7}$ (if $c = = 3 \cdot 10^{10}$ cm/s). Then the deuteron movement towards the nucleus is described by the equation

$$\ddot{x} = -\frac{2q^2}{x^2}\cos^2\left(\frac{1}{2}(t+t_*)\dot{x}^2 + x\dot{x} + \varphi_0\right), \qquad (10)$$

where the parameter t_* is defined under the condition that the argument of cosine equals φ_0 for $t = 0, x = x_0, \dot{x} = \dot{x}_0$ (thus $t_* = -(2x_0)/\dot{x}_0$), and this parameter may be considered as the initial moment of so called local time.

In the interest for us are namely solutions of eq. (10) under very small deviation ε from phase φ_0 and so we put $\varphi_0 = \frac{\pi}{2} + \varepsilon$ and rewrite eq.(10) in the following form:

$$\ddot{x} = -\frac{a}{x^2}\sin^2\left(\frac{1}{2}(t+t_*)\dot{x}^2 + x\dot{x} + \varepsilon\right), \qquad (11)$$

where *a* = 0.0144967 Let the initial x_0 to be equal - 500000 of our length units (i.e. approximately $5 \bullet 10^{-9}$ cm) and the initial deuteron velocity v_0 to be equal to the velocity v_{00} corresponding to the deuteron energy of 1 eV or less. But it turned out that the precision of numerical integration of this equation under such initial conditions and under values $|\varepsilon| = 10^{-15}$and less is small and besides the interval of the integration must be very large. That is why this equation also had to be transformed by passing to "slow" time $\tau = |\varepsilon| t$ to the equation relative to the variable $w = \left(\frac{dx}{d\tau}\right)^2$ as a function of *x:*

$$\frac{dw}{dx} = -\frac{2a}{x^2}\left\{\frac{1}{\varepsilon^2}\sin^2\left[|\varepsilon|\left(\frac{1}{2}(\tau+\tau_*)w + x\sqrt{w} \pm 1\right)\right]\right\}, \qquad (12)$$

where $\tau_* = -(2x_0)/\sqrt{w(x_0)}$ and +1 if ε >0, and -1 if ε < 0. It must be added also the equation for τ as a function of *x* :

$$\frac{d\tau}{dx} = \frac{1}{\sqrt{w}}. \qquad (13)$$

The system of equations (12, 13) is, so to say, a "model" system describing fairly accurately the deuteron movement under all values of |ε| from 10^{-24} to $10^{-6.}$ Numerical integration of this system was fulfilled under different values of e and under following initial conditions:

$$w(x_0) = 2.103, \tau(x_0) = 0, x_0 = -500000, \tau_\bullet = 689573.18 \qquad (14)$$

It may be noted that the initial deuteron velocity v_0 equals 1.450172 (following the relation $\dot{x}_0 = |\varepsilon|\sqrt{w(x_0)}$) for given initial $w(x_0)$ and for |ε| = 10^{-7} , i.e. such velocity is approximately 3.7 times less than velocity v_{00} corresponding the deuteron energy of 1eV. If $|\varepsilon| = 10^{-6}$ then the velocity v_0 is approximately 2.7 times greater than velocity v_{00} .

It turned out that the numerical tables for values of w, τ obtained under different values of $\varepsilon < 0$ in the interval (-10^{-24}, -10^{-6}) don't differ essentially from each other. The following table is true to three-four significant figures for τ and $\dot{x}/|\varepsilon| = \sqrt{w}$:

x	τ	$\dot{x}/\|\varepsilon\|$
-500 000	0	1.450
-50 000	$1.426 \cdot 10^6$	0.0493
-500	$1.002 \cdot 10^7$	0.000489
-200	$1.067 \cdot 10^7$	0.000440
-100	$1.090 \cdot 10^7$	0.000425
-80	$1.100 \cdot 10^7$	0.000423

If reducing the table values of x to centimeters, we obtain the following corresponding approximate values:

$$5 \cdot 10^{-9}, 5 \cdot 10^{-10}, 5 \cdot 10^{-12}, 10^{-12}, 0.8 \cdot 10^{-12}$$

The time interval ΔT , in which the deuteron reaches the critical distance 10^{-12} *cm* from the center, is $67350/|\varepsilon|$ of our time units or $(1.090 \cdot 10^7/|\varepsilon|) \cdot 3.502 \cdot 10^{-25}$ seconds. If nuclear forces are not taking into account then the deuteron may approach the distance less 10^{-12} *cm* .

We present here the table, where are given the initial deuteron velocities v_0 in velocities shares v_{00} and the corresponding time intervals ΔT (in seconds) for different values of ε.

ε	$\frac{v_0}{v_{00}}$	ΔT (s)
-10^{-6}	2.7	$3.82 \cdot 10^{-12}$
-10^{-7}	0.27	$3.82 \cdot 10^{-11}$
-10^{-22}	$0.27 \cdot 10^{-15}$	$3.82 \cdot 10^{4}$ (≈ 10.6 hours)
-10^{-23}	$0.27 \cdot 10^{-16}$	$3.82 \cdot 10^{5}$ (≈ 10.6 hours)

Let us note that the given data change essentially under positive values of ε (10^{-6}, 10^{-7}, etc.). There is some asymmetry of solutions behavior under negative and positive values of ε. The calculations show the minimum distance $|x|_{\min}$ more than 500 of our lengths units even for relative big initial $w(x_0)$ = 10000. Thus, if we limit ourselves to the condition that the deuteron energy is not over $(0.27)^2$ eV at a distance of $5 \cdot 10^{-9}$ cm from the central nucleus, and the whole process of deuteron movement towards the nucleus does not exceeds approximately 10.5 hours, then the interval $(\frac{\pi}{2} - 10^{-7}, \frac{\pi}{2} - 10^{-23})$ is approximately the sought phase “hole” in the whole interval ($(0,\pi)$) of phase change φ_0 in eq. (10).

If many deuterons with the energy not more than $(0.27)^2$eV at the distance $5 \cdot 10^{-9}$ *cm* from the nucleus are equally distributed along their phases φ_0 , the ratio of the length of this “hole” to π, equaling approximately $0.3 \cdot 10^{-7}$, is equal to a share (or a relevant percentage of $0.3 \cdot 10^{-5}$) of deuterons overcoming the Coulomb barrier.

The above figures express at least the order of probability of the cold nuclear fusion occurrence, and this order is absolutely incompatible with the figures in the classical quantum mechanics mentioned above. Let us note once again that a one-dimensional problem was solved, and in case of an accurate analysis (not zero sighting distance will be taking into account) this probability will be lower. Let us also pay attention to the large time intervals ΔT calculated if $|\varepsilon|$ is very small. It explains well the effect (observed by many researchers) of continuation of cold nuclear fusion reactions during even many hours after the disconnection of the voltage in the electrolytic cell. This effect was named even “life after death”.

As for the analysis of the deuteron movement with the help of the autonomous equation, the calculations lead to initial velocities v_0 , exceeding the above mentioned numbers, although the general motion picture is the same. But the autonomous equation is interesting, because in the area of those values $x, \dot{x}$, under which the product $x\dot{x}$ is modulo small, it is possible to replace $\sin(x\dot{x})$ with $x\dot{x}$, and the eq.(11) under ε=0 to replace with simplified equation (describing the deuteron motion from initial point $x_0 > 0$ to center)

$$\ddot{x} = a\frac{(x\dot{x})^2}{x^2} = a\dot{x}^2$$

This equation has a very simple analytical solution. Without giving very simple calculations, we will present the final formulas.

Let us take the following initial conditions:

$$x(0) = x_0 > 0, \quad \dot{x}(0) = -v_0 < 0$$

Then

$$\dot{x}(t) = -\frac{v_0}{1 + av_0 t}, x(t) = x_0 - \frac{1}{a}\ln(1 + av_0 t)$$

It follows from these formulas that the velocity of a particle moving in accordance with the initial equation never turns to zero, and under

$$t = t_* = \frac{\exp(ax_0) - 1}{av_0}$$

$x(t_*) = 0$, i.e. the particle reaches the center of the nucleus, its velocity at this moment being

$$\dot{x}(t_*) = \frac{-v_0}{1+av_0t_*} = -v_0\exp(-ax_0) \text{ ,}$$

so that it *passes through the nucleus and moves further.*.

For example, let $a=0.0144967$, $x_0 = 1000$ ($\approx 10^{-11}$ cm), $\dot{x}(0) = 5.37\cdot 10^{-10}$ (≈ 16 cm/s).

Under such initial data, the product $x\dot{x} = -0.0000537$, so it is quite possible to replace $\sin(x\dot{x})$ with $x\dot{x}$.
In this case,

$$t_* \approx 2.3\cdot 10^{7} \qquad (\approx 8\cdot 10^{-18}\text{ s}),$$
$$\dot{x}(t_*) \approx -29.9\cdot 10^{-17} \qquad (\approx 9\cdot 10^{-6}\text{ cm/s})$$

These figures fit well into the reasonable framework, so the autonomous model can also be of use for the movement analysis in the problem under review. The phenomenon of particle passage through the Coulomb potential accounts very well for the existence of pendulum orbits in the Bohr-Sommerfeld model, when in states *1s,2s,3s* etc. the electron passes through the nucleus. Such states in the strict theory and experiment have no impulse, so in the Bohr-Sommerfeld model they were discarded as absurd. Now they have a right to existence. Further, the experimental data for angular distribution of non-elastic scattering by nuclear reactions (including reactions with heavy ions) reveal the big amplitude of the scattering forward. It is impossible to explain such effect by the formation of intermediate nuclei but it is may be explained from the viewpoint of our UQT.

General Principles of Creating New Energy Sources

In the ancient classical *perpetual mobile* idea it is supposed that energy is just created and not taken from outside (impossibility of *a perpetual mobile* is the first law of thermodynamics). There have appeared lately many articles and even books dwelling on the idea of energy generation from vacuum. We are not in complete agreement with many of these works, and we will dwell only on some of them, which, in our view, can be of interest. One of the main ideologists of this completely new sphere in science are Daniel C. Cole and Harold E. Puthoff, and their first serious work entitled «Extracting energy and heat from the vacuum» was published in Physical Review E, vol. 48, #2, (1993). In this work authors use the Casimir forces [60] making them produce useful work. The appearance of such forces in vacuum is understandable intuitively: if in a stormy sea we put vertically into the water two big parallel plates, on the outside part of these plates the waves will hit them at random, and between the plates there will be no waves. Then, the hitting of the waves outside the plates will produce a gravitation force between them (the Casimir force discovered experimentally long ago), which the authors of this interesting work are going to exploit. It is easily seen that in this idea energy is generated from vacuum fluctuations.

Our approach is altogether different. When the equation with an oscillating charge was solved for the quantum oscillator, 4 types of solutions were discovered. For us only two of them matter – "crematorium" and "maternity home". In one solution ("crematorium") the particle slowly falls to the bottom of the pit and finally turns into a "specter" (under the strict unitary quantum theory it disappears, spreads about the Universe and contributes to vacuum fluctuations everywhere). In the other solution ("maternity home") the particle can even be born of a very small fluctuation, or accumulate a sufficiently big energy. Let us underline once again that both these processes are not at all logically connected. In other words, there are such systems where energy will disappear completely (electrolytic baths), or increase unlimitedly (it might be our Universe).

It is the energy conservation law that presents the strongest impediment in all cosmological approaches. However, universes with birth of matter have long existed in scientific cosmology independently of us. There is known the theory of British astronomer Fred Hoyle based on the idea of continued creation of matter from nothing. The question of whether such an approach is realized in nature and whether the energy emitted by quasars is the result of work produced by a certain gigantic pit, is the most intriguing question of the future.

It is yet unclear whether the values of appearing and disappearing energy in these solutions are equal. But neither in the strict UQT nor in the equation with an oscillating charge vacuum (as a big set of random oscillations) is needed for energy generation. Of course, UQT admits of such an energy exchange with vacuum. For example, during split of a photon on a semitransparent mirror, at one time both halves of the photon will not be registered and will give their energy to the vacuum and disappear for the observers for good, at another time there will appear two photons out of one, and the lacking energy will be taken from vacuum. But *the movement equations (4) and (5) themselves know nothing about vacuum and can generate energy due to their nature* (they are noninvariant relative to the coordinate translations) and the conservation laws we are so accustomed to do not exist for them.

Let us remind you once again that the latter follow from the Newton equations, and the Newton equations result from averaging by a big number of events, while for individual events of small energies no conservation laws in quantum physics exist.

In other words, it can be said philosophically that a motion of a small wave packet, once started, will give birth to other movements (energy) and, consequently, to matter. Since most various and breath-taking speculations are possible, up to the creation of a universe, we will stop here.

Thus, the generated or disappearing energy in our approach can be manifest not only in the changes of the particle velocity during movement in a certain potential, but in the appearance or disappearance of the particles themselves as well. A change of the particle velocity in movement is most easily discoverable, and it is the velocity increase that can be used for generation of heat or electric current. There can be energy systems, which exploit the fact itself of charge oscillation and the consequence of it. It is very probable that these phenomena, contradicting the most fundamental laws of modern science, have been long discovered and even applied. But these are the very phenomena that are the easiest to be exploited at the first stage of development of such new energy technologies.

When an energy generation mechanism is used, crematorium-type solutions should be suppressed. But all the quantum processes are built on the basis of elementary acts, and each of them is impossible to be controlled separately. But if the probabilities of such processes are controlled, they, being multiplied by the great number of participants in the process, automatically become macroscopic variables of quantum kinetics, and the process itself becomes possible. It can easily be achieved, if process participants with correlated initial phases are selected.

Let us remind you that the Newton and relativistic classical mechanics follow from the strict UQT, while the Newton movement equations with the resultant energy and impulse conservation laws follow from the oscillating charge equation with averaging by the particle ensemble composing a classical body (material point). But these conservation laws are nonexistent for individual microparticles in our theory, and they appear only in case of averaging by the ensemble of particles. Thus, if the energy-generating processes are accumulated, and the processes where energy disappears are suppressed, a classical *perpetual mobile* can be created.

But the UQT and the oscillating charge equation have other differences not only from the equations of classical mechanics, but also from some equations of electrostatics and electrodynamics.

There is a fundamental theorem of circulation for the electric field. Let us dwell on it in more detail. Let us have a vector field **E,** which can be an electrostatic or a gravitation field.

$$\mathbf{E} = \mathrm{P}(\mathrm{x},\mathrm{y},\mathrm{z})\mathbf{i} + \mathrm{Q}(\mathrm{x},\mathrm{y},\mathrm{z})\mathbf{j} + \mathrm{R}(\mathrm{x},\mathrm{y},\mathrm{z})\mathbf{k}$$

Line integral

$$\Gamma = \oint_l \left(\mathrm{P}\,dx + \mathrm{Q}\,dy + \mathrm{R}\,dz\right) = \oint_l \mathbf{Edl} \qquad (15)$$

is called circulation of vector field **E** by contour *l*. Of course, circulation depends not only on **E**, but also on the passage direction accepted in contour *l*; by changing the passage direction we will change the circulation sign. Form (15) is convenient for mathematicians, but for our purposes we will present equation (15) in a different way. If both parts of equation (15) are multiplied by electric charge *q,* on the right we will get the integral of force $q\mathbf{E}$ by way **dl,** i.e. work for moving the charge along a closed loop contour. It is well known that this value is zero.

$$\int_l q\mathbf{Edl} = \mathbf{0} \qquad (16)$$

If this value were not zero, an energy source could be created. For this purpose a charge should be moved in electric field **E** from point *a*, located in the high voltage area of the field, to point *b,* located in low voltage area of the field, and then back, but along another route. The values of work from $a \rightarrow b$ and from $b \rightarrow a$ would be different, and we could extract work from the field without making any changes in the system. When the charge is constant, it is certainly true, so for a macroscopic constant charge this theorem is an analog of the energy conservation law. The authors have not come across such an interpretation of the energy conservation law in other works. If the charge is microscopic, then in the UQT it changes, depends on time, coordinate and velocity, so work from $a \rightarrow b$ and from $b \rightarrow a$ will be different, in this case work can in principle be extracted from the field without any changes made in the system.

Discussion of Experimental Results

Let us now get down to explaining some very unusual experimental results, which the authors have nothing to do with, and which they sometimes regard rather skeptically. The point is that the sphere of new energy sources is the headache of all the human civilization, and in this sphere, like nowhere else, the dividends can be exorbitantly high, and for this reason there are in this sphere a lot of swindlers (even among the theoreticians) and simply erring people. The official science of the world does not so far believe in such research, but the most suspicious fact is the great multiplicity of such works. The authors are not inclined to regard all these people as swindlers or erring, because the UQT can offer a beautiful and simple interpretation of certain phenomena.

There are strange plants with the efficiency over 100%. They are even manufactured in small quantities and are rated among energy-saving devices already termed over unities. Japanese researchers take these problems very seriously, and the leading role in studying this problem belongs not to the USA, but to Japan, which even finances many US institutes in this framework. The total Japanese expenditures for this research exceed $200.000.000 a year. It can be forecast that with the Japanese mentality and the state policy of exporting not natural resources, but superhigh technologies and intellect, Japan will find itself among the leading countries early in the 21st century. We think that our readers will not be surprised to hear that Russia has not allocated a single cent for this program, and all research was made on pure enthusiasm.

In the USA such works do not get official governmental support either (like, for example, the dying out hot nuclear fusion problem), but a great number of private firms and individual businessmen are conducting large-scale research. The following US journals are devoted to the subject: *Journal of New Energy, Infinite Energy, Cold Fusion, New Energy News, Fusion Facts*, and *NET-Journal* (Switzerland).

Switzerland, Italy, Germany, and France are also among the countries where the new energy problems are seriously researched from the cold nuclear fusion point of view.

A very young sphere of power engineering has emerged and is quickly developing, which researches many new energy sources. In future those new energy-saving sources will first be used, which will considerably differ from the existing ordinary energy transformers in that they will generate additional energy that can be used in the interests of the mankind. The development of civilization will then be limited not by long-expected reduction of natural fuel resources, but by heat pollution of the environment.

Let us enumerate just a few of the new energy directions:
1. The Patterson fuel cell (CETI).
2. Supermagnet-superengines of Takahashi, Aspden and Adams
3. Swiss plant Testatika.
4. Engines operating on water.
5. Hypersound Griggs pump, the Potapov and Schaffer heat generators.
6. Schoulder and Fox cluster systems.
7. N – machines of Farade, Bruce de Palma, Newman, Searl, Tewari, etc.
8. PAGD reactor of Canadian researchers P. Correa and A. Correa.

This list can be complemented with the surprising experimental results received by physicists A. Samgin and A. Baraboshkin (Russia, Institute of High-Temperature Electrochemistry under the Russian Academy of Sciences, Ekaterinburg) [24,25] and T.Mizuno [26] (Japan). They appear to have used, totally independently of each other, special proton-conducting ceramics, which, when electric current runs through them, generate a thousand times more heat energy than the electric energy consumed. In some experiments by T.Mizuno this value even exceeded 70000(!). T. Mizuno in a personal talk with one of the authors of this report said that he feared very much the radiation sickness. But no α, β, γ radiation or nuclear debris was found, and the nuclear processes are not responsible for such energy generation. Such proton-conducting (or, to be more exact, deuteron-conducting) ceramics was made using the power metallurgy methods by agglomeration under high temperatures. In other words, all the chemical processes in it had long been over. The origin of such an amount of excessive energy is absolutely incomprehensible in the framework of conventional science, for they cannot be accounted for either by nuclear or chemical reactions, or by phase passages. At first the authors of this experiment supposed nuclear fusion reactions of the D+D type. At our request, A. Samgin replaced heavy hydrogen (deuterium) during ceramics production with ordinary hydrogen. If the effect of such huge energy generation was connected with the nuclear D-D reactions, all the anomalous heat effects would have disappeared, but they persisted. After such a large quantity of energy was generated, the tablet disintegrated into powder.

These effects can easily be explained by UQT from the harmonic oscillator theory point of view. When the tablet is agglomerated, there remain in it some caverns of a size of hundreds Angstrom units. When direct or alternating current flows through it, the protons and deuterons in their movement (there are few electrons in such ceramics) get into these caverns, and a process can start which is described by the “maternity home” solution. A particle accumulating energy, oscillates in such a pit, and finally the energy will be sufficient both for heating and for destruction of the pit walls (tablet turning into powder). The same processes seem to be taking place in a palladium electrolytic cell with heavy water, and in a nickel electrolytic cell with ordinary water, which accounts for anomalously large heat generation, not related to nuclear processes.

It would be good to verify experimentally the dependence of the tunnel effect on the initial phase. But it seems us that it is more important for our opponents, since both cold nuclear fusion (CNF) and discovery of nuclear transmutations *(which, from the point of view of modern science, are even more absurd than the existence of CNF*) evidently cannot be accounted for in any other way. Besides, such a direct experiment is of a fundamental value. There are today a lot of people and groups in the world, who pin great hope on exploiting the nuclear transmutation phenomenon for the purposes of processing and recycling of nuclear wastes, and the question of industrial generation of tritium for military purposes using CNF methods was under consideration in Los-Alamos. Internet magazines are full of such information. We are not giving Internet addresses here, because everything is constantly changing in this live system.

Let us analyze some of the above-mentioned devices. The first, the oldest and the most mysterious information was information about internal combustion engines operating on water.

Let us give just one example. When we were students, one of our teachers, the late Professor G.V. Dudko (1959) told us that in 1951 he had participated in the testing of an internal combustion engine [39,55-57]. The device represented a hybrid of a diesel and an ordinary carburetor engine, where a gas of petrol was needed to start it and then ignition was switched off, and an ordinary fuel pump sprayed into the cylinder warmed up and strongly compressed water with special additives (which the inventor himself put into the tank in small quantities, and which, as we now understand, represented the principal secret). The engine was installed on a boat. The researchers were riding for two days in the Azov Sea, and only water vapor was the engine exhaust. Professor Dudko himself drew the water fuel overboard and poured it into the tank. They needed much water, several buckets a day, but there was no shortage of it… The question of why, if everything was so great, these engines are still not in use, can occur only to a person who has never lived in Russia.

From the point of view of the solutions of the harmonic oscillator problem, the following theoretical possibility exists [40,44,47,55-57]: if water with the necessary additives (which, evidently, represent the secret of many invented engines operating on water) is compressed and sprayed into the cylinder, each drop of water, when it gets into the cylinder after being compressed, will start dilating and will pass by inertia the equilibrium position. As a result, caverns (empty volumes) can be formed in it, with a size of several dozen of Angstrom units. If a free proton (or some other microparticle) gets into such a cavern in the required phase (it is supposed that the task of the additive is exactly this), the "maternity home" solution will be realized and some of the drops will explode… Later we heard and read many times about various Russian inventors, who had successfully created and tested engines operating on ordinary water with some mysterious additives.

Of course, the possibility of catalytic water decomposition with small energy consumption before spraying into the cylinder is not at all excluded. There are films and information in Internet about testing of cars operating on water, which is catalytically (with small energy consumption) decomposed into oxygen and hydrogen. Such power engineering would be ecologically absolutely clean, and the only restriction would lie in heat pollution of the environment.

An ideal solution for the motor transport could also lie in use of some new types of electric energy generators. The UQT even admits of the possibility, which was long observed in the experiments of Nicolas Tesla and in those made by Canadian physicists the Correas, who even received a patent for a system generating energy from vacuum fluctuations (as they believe) [45]. The readers could have got acquainted with our detailed theory of these processes in [46]. But the ideal system for the automobile would certainly be Testatika.

Any imagination will be amazed at the thermal cell CETI created by James Patterson, USA [27], in which takes place the electrolysis of specially made nickel balls in ordinary water. The US paper «Fortean Times» [1] 85, 1995, wrote about it: "December 4, 1995 will go down into history. On this day a group of independent experts from 5 US universities was testing a new source of energy with a stable output heat power of 1.3 kWt. The consumed electrical energy was 960 times smaller". All experts note that the generated heat is of mysterious origin and cannot be explained by chemical or nuclear reactions, as well as by phase passages. The US ABC TV showed on February 7 and 8 1996 in the «Nightline» and «Good Morning America» cycles of programs about the development by Patterson of a new energy source generating hundreds of times more energy than it consumes. The mysterious nature of the generated heat was again underlined. It is interesting [34] that Motorola tried to buy the CETI patent from its authors for $20.000.000, but met with a refusal. We are sure that Motorola had invested a certain amount of money into the study of this problem before making such a serious offer. All that happens within the Patterson element has nothing to do with nuclear reactions (although Patterson told one of the authors that he was of a different view), and, in our opinion, can be accounted for by exactly the same processes as were described above for proton-conducting ceramics.

The sonoluminescence phenomenon, when certain liquids start shining if weak ultrasound is run through them, also looks very mysterious. No satisfactory explanation has so far been found for this experimentally proved phenomenon, discovered by Moscow University Professor S.N. Rzhevkin in 1933. As Nobel Prize winner Professor Yulian Schvinger said, "it has no right to exist, but it does exist" [38]. This phenomenon can also be explained from the above-mentioned positions.

There are also heat generators (Yu. Potapov [21-23], Moldavia, James J.Griggs [28], and Huffman [29], Schaffer - USA). In them many cavitating bubbles are formed during circulation of ordinary water, in which excessive energy is generated, with the output to input energy ratio approaching 1.7. In these experiments and plants no chemical or nuclear reactions can take place, and thousands of Potapov's heat generators have been manufactured for heating homes. In such devices (they are very different in appearance) a great number of cavitating bubbles are created in a flow of water. This is achieved either with the help of interrupting the water flow with a special rotor (J.Griggs, Huffman, Schaffer), or the water flow is twirled by a special helix and then enters the zone of sharp dilation, where cavitating bubbles are formed (Yu. Potapov). In general, it should be said that cavitation remains a great puzzle for theoretical hydrodynamics and science. For example, forged multi-ton screw propellers of big nuclear submarines under certain operation modes and geometry of the surrounding forms can be destroyed by cavitation within only a few hours. It happens because of huge energy generated in cavitating bubbles.

Under certain values of phase and energy, a particle in the pit, each time reflecting from the walls, will have a greater velocity than that of a falling particle (this is within the uncertainty relation), and after many reflections will accumulate a fairly big energy which will be generated in the form of heat or bremsstrahlung when the pit is destroyed, and, finally, the energy of the oscillations of such a particle accumulated in the pit will always be transformed into heat in an ordinary solid body or a liquid. This physical idea immediately accounts for both sonoluminescence (although for sonoluminescence in general this mechanism is less primitive), and energy generation in proton-conducting ceramics, nickel during electrolysis in ordinary water (CETI element), and water bubbles of commercial heat generators. The theory predicts that the samples should be fissure due to increased pressure on the walls of the potential pit with the growth of energy, which fact also takes place, since both ceramic samples and nickel balls in the CETI element finally disintegrate. It is evidently for these reasons that any metal containing much hydrogen in its grid becomes fragile and is quickly destroyed, which fact is well known to engineers.

The small number of experiments does not so far allow for making concrete conclusions as to what particles generate energy in pits (microbubbles). Besides, for at least an electron to disappear a pit of about 0.5 MeV is required, while in a solid body the pits are about several eV deep, and what seems to happen is only loss of kinetic energy, and not disappearance of particles. The fact that this process requires very deep potential pits, which do not exist in a solid body, does not change the essence of the matter.

Of course, under ordinary conditions, both competing solutions usually take place at once: "maternity home" and "crematorium", which compensate for each other and the energy is preserved. For energy generation, the "maternity home" solution should prevail. Both these processes take place simultaneously and compete with each other, but, formally, they are not connected in space and time. The complexity of the energy generation problem lies in suppressing the "crematorium" solution by a careful selection of different parameters and promoting the "maternity home" solutions. So far we cannot say for sure what the optimum dimensions of such cavitating bubbles are, or which object oscillates in them, because for this purpose special experiments are needed, which so far have not been staged.

Of course, the inexorable Robber in the form of the Carnot principle stands in the way of transformation of the heat generated in a heat generator or ceramics into electrical or mechanic energy. In accordance with this principle, all mechanic or electrical energy can be transformed into heat, but the reverse process is always connected with big losses.

If there are experiments and plants in which energy generation contradicting the conventional conservation laws is discovered, there should also exist opposite ones, where energy disappears completely, i.e. the "crematorium" solution prevails. It proved to be true. There are such modes during electrolysis in electrolytic baths, under which the temperature of the solution in the bath is strongly reduced for unaccountable reasons, and this fact has no explanation at all. This phenomenon long ago was noted by attentive industrial engineers, and it is called the "bath-freezing" mode [49,50]. Chinese physicist Swe-Kai Chen from Taiwan in his experiments [48] stably observed the same phenomena. It is quite easily explained: a particle with a velocity exceeding the most probable velocity in this distribution gets into caverns on electrodes and after some oscillations reduces its velocity, which becomes smaller than the most probable one, and then the particle leaves the cavern at a small speed, and the same process can happen to another energetic particle. This leads to the cooling of the cell in the case of such mass processes.

The problem of ferromagnet magnetization (the Easing model) can also be reduced to the orientation of a magnetic doublet by the external magnetic field, and then it is essentially the harmonic oscillator equation with a slightly different return force ($F = \frac{\mu}{r^3}$) and all the conclusions made earlier remain in effect. That is why magnetization should also produce energy generation effects. This proved to be true. For the general public everything began on May 17, 1996, when Frode Olsen from the research group "Free Energy" showed on the Norwegian TV (TV2) a surprising film about a "dynamic sculpture" made by artist and sculptor Reidar Finsrud from Skaarer, Norway. The author of this "dynamic sculpture" *had no idea about physics* and had been making it for 12 years. Einstein's idea of how discoveries are made conveniently comes to mind at this point: everyone knows that a certain thing cannot be done, but there is a man who does not know it, and it is he who makes the discovery.

This "dynamic sculpture" accompanied by an "explaining" poster «*perpetual mobile*» represents an iron well-polished ball with a diameter of 2.7 inches weighing about 2 pounds. The ball is rolling along a circle on close guides resembling two parallel skids with a diameter of 25 inches past the poles of three permanent magnets, where it is magnetized. In the area of three permanent magnets three more mobile magnets are installed on special mobile 5-inch long levers, and these magnets, when the ball passes them, are slightly inclined (due to the ball gravitation) and, after the ball passes them, are raised by the holding springs (sway like yokes). The ball makes a complete turn in 3 seconds. All this magic (***they say the ball had been rolling along the close contour for more than a year***) does not have any sources of energy and is installed for everyone to see in a Norwegian picture gallery on a special stand covered with a glass cover. The authors only saw a good TV film about this installation and were mostly surprised at the fact that the ball had not stopped during uninterrupted shooting (about 20 minutes).

We are well acquainted with circus tricks, but it is absolutely incomprehensible how such a trick could be staged using some secret methods. It is clearly seen that the ball in its movement always partially transfers its energy to the three long swaying pendulums, but there is no way to use them for pushing the ball and making up for friction, this being the only trick that could, in our view, be applied here. All the rest is clearly visible and contains nothing suspicious.

Let us estimate the generated energy. At an initial speed of about 1m/s the ball stops after 30 seconds, if all the magnets are removed. It means that the energy consumed in 30 seconds is about 0.5 joules, or 1/60 Watt. The total energy generated in a month is 43,200 joules, and this is huge energy, much greater than that of a good shell!

It is clear (if the word is relevant here at all) that when the ball is approaching the permanent magnet and the process of magnetization is going on, it is accelerated, but when it mechanically gets past the equilibrium position and, moving away from the magnets, becomes demagnetized, the gravitation (which now starts slowing the ball down) will be slightly less than it was at the moment of the ball's acceleration. This small difference in forces provides for small positive work to overcome friction. Energy generation and similar things during magnetization had been *predicted* by one of the authors in magazines *Infinite Energy* vol.1, No.2, p.38, (1995); *Proceedings of the ICCF*5, p.361, April 9-13, (1995), Monte-Carlo; *Cold Fusion*, No 11, p.10, (1995); *Chinese Journal of Nuclear Physics* (vol. 19, ^{1}2, 1997). The quantum-mechanic processes are very complicated, but some of them can be understood.

All keen physicists were quick to understand it, and J. Naudin in France made a similar, but much simpler experiment. A ball of a soft magnetic material is swaying along parallel U-formed skids in a system of four magnets. Near the bottom of the U-form there is a small smooth step. It may have been made to make the magnetization and demagnetization processes different in time, which is very important. If there are no magnets, nothing interesting happens and oscillations are quickly (in a few seconds) damped. If the magnets are present, oscillations go on up to 3 hours 27 minutes. It appears that in this case the author failed to find good material and parameters of the plant, so friction was not compensated completely. In all these experiments demagnetization of permanent magnets does not happen, because the experiment is repeated many times with the same results.

And now a few vague words about demagnetization processes. During magnetization of the ball, the magnetic moments of its atoms are oriented (like the hands of a compass) along the field lines. When the ball leaves the magnetic field area, the atom magnetic moments are disoriented under the influence of the heat motion, and it becomes demagnetized. In the unitary quantum theory the share of the oriented magnetic moments in the external field can be bigger than in the conventional quantum mechanics (the "maternity home" solution), and the ball gravitation can be stronger due to it. Disorientation of these moments happens similarly in both theories. It seems to be for this reason and due to the difference in magnetization and demagnetization time that a difference in magnetic forces occurs when the ball approaches the magnet or moves off from it.

The scientists of the older generation will remember that a similar toy was shown in the 30's to David Gilbert, who said it was the most interesting thing he had ever seen. A question arises as to why it has not yet been realized. We do not know a physical-mathematical answer to this question, and it is not our task to analyze the social reasons of this phenomenon. Japan has a different mentality, and there is a governmental program for generating energy from permanent magnets. Takahashi [51] even seems to have made an electric engine with an efficiency of up to 318%!

Still more mysterious is the long-known problem of energy shortage in many biochemical reactions with ferments (enzymes). For example, in the well-studied reaction of disintegration of polysaccharides in the presence of lysozyme the following happens: a polysaccharide molecule gets into a special cavern in a big lysozyme molecule, and some time later its debris are thrown out of it (Fig. 6). The broken binding energy of the polysaccharide is about 3 eV, while the energy of the heat movement is only 0.024 eV. From the standard science point of view, it is absolutely unclear where lysozyme takes the energy to break the polysaccharide. No satisfactory mechanism for explanation of such reactions (and they are very numerous) was found, and all this was "swept under the carpet", as physicists say. The UQT provides for a completely new look at the catalytic processes, which has an incomprehensible source of energy reducing the molecule activation energy. From our point of view, this process is a variant of the "maternity home" solution for oscillator.



Fig.6. Break of polysaccharide molecule by lysozyme.

The most surprising thing is that in all the cases generation of excessive energy cannot be accounted for by chemical reactions or phase passages. If nuclear reactions do sometimes happen (which should not be according to modern science), they can account for only a hundredth or a thousandth share of the generated heat energy. There is no doubt that all these are effects of new physics, for in the framework of the old physics all this is simply unexplainable.

But the existence of a plant that produces *out of nothing* about 10 kilowatt of direct current electric energy with a voltage of 300 V seems nearly impossible. The story was described by one of the authors in three different magazines, and we will just give a brief resume [52-54].

In summer 1999, at the invitation of Swiss physicists (Director of the Institute of New Energy Sources in Egerkinhen Adolph Schneider), one of the authors visited several research organizations. It is interesting that there is such an institute in small Switzerland, and there is none in big Russia. The purpose of the invitation was very simple: to explain the operation of a plant generating energy out of nothing, i.e. a *perpetual mobile*. In Switzerland such plants are called Testatik Machine M/L Converter from religious group «Methernitha» (Address: Methernitha, CH-3517 Linden, Switzerland, phone: ++41 31 97 11 24).

Such machines exist today in the Swiss town of Linden near Bern. Part of the town belongs to the Religious Christian Community, which is fenced and heavily guarded. There are about 250 members of the Community, many of them are physicists, graduates of the universities of Geneva, Lozanne, Bern. It is not only a research laboratory, they have their own TV center, a film studio, a small furniture plant, shops, garages, residential blocks, and support services. You will probably have guessed that this community does not consume any energy, and this is the most accurate fact in the whole story, for the inquisitive journalists have found out that no money from them comes to the accounts of the local power station, which provides power for all the town. In a cellar of one of the houses they have a power station that produces energy… out of nothing. The author of this inexhaustible source of free direct current energy is Swiss physicist Paul Baumann. Let us briefly describe these fantastic plants: they are of four types (sizes) with capacities of 0.1, 0.3, 3 and 10 kWt. Externally, the plant resembles very much the standard electrostatic machine with Leyden jars often used in physical demonstrations. There are two acryl disks with 36 pasted narrow sectors of thin aluminum, which rotate in different directions. In the first samples ordinary gramophone records were used for disks. The machine is started by pushing the disks in different directions by fingers. The rotation speed is 50-70 turns per minute. After the start disks rotate independently and can be easily stopped by hand, the direct current voltage is about 300-350 V, and the current is up to 30A. The mechanical energy used for rotation (only 100 mWt, according to measurements made by Austrian Professor S. Marinov) is hundreds of thousand times smaller than the generated electrical energy. The biggest plant for 10 kWt has plastic disks with a diameter of over 2 m, the smallest one – 20 cm, the weight of the plants is small enough, the 3-kWt machine weighing about 20 kg.

The charge separation process (which consumes energy!) practically does not slow down the disks. Connection of a load in the form of a 200-Wt bulb does not change the rotation speed either. No cooling or heating of the air or machine parts during long operation takes place, only a slight smell of ozone is felt. The system is noiseless, compact, environment-friendly, and can be installed anywhere.

The Community management thinks, and quite rightly, that wide spread of such systems in the world will lead to a heat explosion, because all the energy generated by the mankind finally finds itself in an energy dump (is transformed into heat), and all this can finally lead to overheating of the environment. They absolutely do not believe (and not without grounds) in the capability of the mankind as a whole to negotiate reasonable use of this invention, and they think that the harm caused by it will be greater than from nuclear, bacteriological, or conventional weapons. Their main idea for the mankind is to live in balance with the environment and to make full use of the energy of the wind, the sun, the water, etc. For this reason the Community is heavily guarded, and they are not going to donate their main discovery to the mankind.

Professor Stephan Marinov visited the Community twice (in July 1988 and in February-March 1989). He was even given such a plant with a capacity of 100 Wt (300 V, 0.3A), which he studied in his laboratory. As far as we now know, even the inventor of this machine does not fully understand its operation principle, so he contacted Marinov out of sheer curiosity of a scientist.

In 1989 Professor Marinov published a book “Thorny Path to Truth – Documents of Violation of Conservation Laws” in International Publishers East-West. The book contains a lot of photos, a measurement report, and a description of the plant. He also organized a research group called “Free Energy” within the Community (Methernitha Group Stephan Marinov Free Energy).

There are very interesting words in this book: “I can state without any doubts that this machine is a classical *perpetual mobile* in its pure form. After the initial push, it goes on rotatingby itself for an indefinitely long time, constantly producing electrical energy in the amount of 100 Watt… It is still unclear, however, how it all can happen…”. As far as we know, nobody has managed to build a similar plant elsewhere.

We have an approximate idea of how the plant operates. The idea is as simple and ingenious as that of the wheel, which is absent from the surrounding nature, so the inventor could not borrow the idea. We will just show that the existence of such a plant is in full conformity with the UQT. It is natural that the plant operates on the basis of the charge separation principle. Let us have two metal spherical surfaces with a hole, isolated from the earth and from each other. If, with the help of an insulated stick, we transfer the first electron from Ball A to the internal surface of Ball B through the hole, a difference of potentials will occur, and if we transfer the second and the subsequent electrons, Ball A will attract the transferred charge, while Ball B will repulse it, and energy will have to be spent during the transfer of charges (Fig. 7).

Let us remind you that under the existing circulation theorem (16), the charge transfer work will consume the same amount of energy as will later be generated during the passage of electric current resulting from charge separation. But in the UQT the circulation theorem (16) for *an individual elementary charge* is not valid. Thus, we can select the time and route, along which the charge will be transferred in such a way, that



Fig.7. Work for moving the charge depends on method of movement and route.

the charge value during the transfer will be close to zero, and, consequently, the electrostatic force and the charge transfer and separation work will be close to zero too. For example, instead of selecting the route you can wait for the charge to be reduced to zero and then transfer it quickly, and when the charge increases, immediately stop the transfer and fix the charge. Or you can duly select the route and velocity. There are many options. This was evidently realized by Paul Baumann, who is *so far* practically unknown to the official science, and who can find consolation in the idea that the inventor of the wheel will never be known at all. The problem of simple arrangement of all this is just a matter of technique.

You cannot help, thinking that all these might be just tricks. The history of *perpetual mobile* abounds in evidence of downright swindling and frauds, and not a single positive result before, and who can guarantee that the information given above will not prove to be another swindle?

First of all, if all the people always piously believe in the unquestionable stability of the energy conservation law, there will never be any progress in this sphere, and it is then unexplainable how man got down from the palm at all. Secondly, to justify the proposed rebellious position, the following idea comes in mind: if 30 years ago somebody had told the authors (who were then already professors) that at the beginning of the next millennium they would deal in such research, it would have seemed not only a silly joke, but an absolutely impossible thing as well. But, as Voltaire said, “He is silly who does not change”.

In conclusion we wish to express with certainty that the time of theoretical recognition and of practical universal using of overunity devices will come soon and become the epoch of new energetics. The people of our planet will regret that so much oil, coal and gas was burned causing terrible ecological losses.

The authors thank astronaut V.A. Dzhanibekov and Professor A.P. Buslaev.

References

1. Sapogin, L.G. Unitary Field and Quantum Mechanics. In: Investigation of Systems. Academy of Sciences of the USSR, Vladivostok, No 2, p. 54-84, 1973 (in Russian).
2. Sapogin L.G. On Unitary Quantum Mechanics. Nuovo Cimento, vol.53A, No 2, p.251, 1979.
3. Sapogin, L.G. A Unitary Quantum Field Theory. Annales de la Fondation Louis de Broglie, vol.5, No 4, p.285-300, 1980
4. Sapogin, L.G. A Statistical Theory of Measurements in Unitary Quantum Mechanics. Nuovo Cimento, vol.70B, No 1, p.80, 1982.
5. Sapogin, L.G. Statistical Theory of Detector in Unitary Quantum Mechanics. Nuovo Cimento, vol.71B, No 3, p.246, 1982.
6. Boichenko, V.A. and L.G. Sapogin On Equation of Unitary Quantum Theory. Annales de la Fondation Louis de Broglie, vol.9, No3, p.221, 1984.
7. Sapogin, L.G. and V.A. Boichenko On Solution of One Non-linear Equation. Nuovo Cimento, vol.102B, No 4, p.433, 1988.
8. Sapogin, L.G. and V.A. Boichenko On Charge and Mass of Particles in Unitary Quantum Theory. Nuovo Cimento, vol.104A, No 10, p.1483.
9. Sapogin, L.G. Clearcut Picture of Microworlds. “Journal Technique for the Young” (Tekhnika Molodezhi). Moscow, No 1, p.41, 1983 (in Russian).
10. Sapogin L.G., “Statistical Theory of Measurements in Unitary Quantum Mechanics,” Nuovo Cimento, vol. 70B, No.1, p.80, 1982.
11. Sapogin L.G., “Statistical Theory of Detector in Unitary Quantum Mechanics,” Nuovo Cimento, vol. 71B, No. 3, p. 24M, 1982.
12. Boichenko V.A., Sapogin L.G., “On Equation of Unitary Quantum Theory,” Annales de la Fondation Louis de Broglie, vol. 9, No. 3, p.221, 1984.
13. Sapogin L.G., Boichenko V.A., “On Solution of One Non-linear Equation”, Nuovo Cimento, vol. 102B, No.4, p.433, 1988.
14. Sapogin L.G., Boichenko V.A., “On Charge and Mass of Particles in Unitary Quantum Theory,” Nuovo Cimento, vol. 104A, No.10, p.1483, 1991.
15. Sapogin L.G. “Deuteron Interaction in Unitary Quantum Theory”, and “On Mechanisms of Cold Nuclear Fusion”. In: Proceedings of the Forth International Conference on Cold Fusion, vol.4, Theory and Special Topics Papers TR-104188-V4, July 1994, p.171-178, Hawaii. 1994.
16. Sapogin L.G. “Deuterium Interaction in Unitary Quantum Theory”, and “On Mechanisms of Cold Nuclear Fusion”. In: Fusion Source Book. International Symposium on Cold Nuclear Fusion and Advanced Energy Sources, Belarussian State University, Minsk, May 24-26, p.91-98. 1994.
17.Sapogin, L.G. “Cold Nuclear Fusion and Energy Generation Processes in Terms of theEquation”. Chinese Journal of Nuclear Physics vol.19,#2, p.115-120, 1996 .
18. Sapogin, L.G. «Cold Nuclear Fusion and Energy Generation Processes in Terms of the Schrödinger Equation». Infinite Energy [E.Mallove, editor], vol.1, No 5,6, p.75-76, 1996.
19. Sapogin, L.G. «Energy Generation Processes and Cold Nuclear Fusion in Terms of the Schrödinger Equation». In: Proceedings of the Sixth International Conference on Cold Fusion, Progress in New Hydrogen Energy, October 13-18, 1996, Japan, vol.2, p.595-600.
20. Sapogin, L.G. “Energy Generation Processes in Terms of the Schrödinger Equation.”Proccedings îf the 2nd Russian Conference CNFNT (in Russian) p.18-24, Sochi, September 19-23,1994.
21. Potapov J.S. Patent of the Russian Federation No 2045715 Heat Generator and Device for Heating of Liquids. Registered on the 10-th of October 1995; priority from the 26-th of April 1993 (in Russian).
22. Potapov J.S. Water as a Source of Life and Energy. Enerjia-takarekossadi, Revu. p.25- 29, September 1998, Budapest.
23. Potapov J.S., MD, Patent No 649 Instalatie pentru obtiinerea enerjiei electrice si-temice. Buletin Oficial de Proprietate Industriala, No12, p.18-19, Chisinau (in Moldavian).
24. Samgin A., Baraboshkin A. et al. Influence of Conductivity on Neutron Generation Process in Proton-Conducting Solid Electrolytes. In: Proceedings of the 4th International Conference on Cold Fusion. Palo Alto, USA, v.3, p.51-57, 1994.
25. Samgin A. Cold Fusion and Anomalous Effects in Deuteron Conductors during Stationary High-Temperature Electrolysis. In: Proceedings of the 5th International Conference on Cold Fusion. April 9-13,1995, Monte-Carlo, p.201.
26. Mizuno T., Enio M., Akimoto T. and K. Azumi Anomalous Heat Evolution from $SrCeO_3$-type proton conductors during absorption/desorbtion of deuterium in alternate Electric Field. Proceedings of the 4th International Conference on Cold Fusion, December 6-9,1993, Hawaii, vol.2, p.14., EPRI, Palo Alto, USA, 1994.
27. Patterson J.A System for Electrolysis, U.S. patent No 5,494,559,27 Feb.1996; Miley G.H. and J.A. Patterson in: Proceedings of the 6th International Conference on Cold Fusion, Progress in New Hydrogen Energy, October 13-18,1996, Japan, vol.2, p.629-644.

28. Griggs J. Calorimetric Study of Excess Heat Production within Hydrosonic Pump System Using Light Water. Fusion Source Book. International Symposium on Cold Fusion and Advanced Energy Sources, Belarussian State University, Minsk, Belarus, May 24-26, p.248-253, 1994.
29. Huffman M.T. From a Sea of Water to a Sea of Energy, Infinite Energy, vol.1, No 1, p. 38-45, 1995.
30. Fleischmann M., Pons S. Electroanal. Chem., v.261, p.301, 1989.
31. Sapogin, L.G. and I.V.Kulikov "Cold Nuclear Fusion in Unitary Quantum Theory". Chinese Journal of Nuclear Physics, vol.17, No 4, p.360-370, 1995.
32. Cryz W.: Rivista Nuovo Cimento, 1, Special No, 42, 1969.
33.Kervran Lois C. Biological Transmutations. Swan House Pub. Co, NY, 11223, 1972.
34.Private Communication.
35. Notoya R., Noya Y., Ohnisi T. Fusion Technology. vol. 26, p. 179-183, 1993.
36.Swartz M. Journal of New Energy vol.1, #3, 1996.
37. Blokhintsev D.I. On Energy Conservation Law. In: Works on Methodological Problems of Physics, p.51, 1993, Print of Moscow State University. (In Russian).
38. Schwinger J. Casimir "Energy for Dielectric". In: Proceedings of the National Academy of Sciences, vol.87, p.8370-8372, 1990, "Cold Fusion: Does it Have a Future?" Journal "Cold Fusion", vol.1, #1, page 14-17,1994.
39. Sapogin L.G. «What Can Our Power Engineering Be Like in the Next Millennium», Journal Business-Match, 14, 1998 (In Russian).
40. Sapogin, L.G. On One of Energy Generation Mechanisms in Unitary Quantum Theory. Infinite Energy [E.Mallove, editor], vol.1, No 2, p.38-39, 1995.
41. Sapogin, L.G. On One of the Energy Generation Mechanisms in Unitary Quantum Theory. Proceedings of the ICCF5, p.361, April 9-13,1995, Monte Carlo.
42. Sapogin, L.G. Energy Generation Processes and Cold Nuclear Fusion in Terms of the Schrödinger Equation. In: Proceedings of the Sixth International Conference on Cold Fusion, Progress in New Hydrogen Energy, October 13-18, 1996, Japan, vol.2, p.595-600.
43. L.G. Sapogin, "On One of Energy Generation Mechanisms in Unitary Quantum Theory". Proceedings of the 2nd Russian Conference CNFNT (in Russian) p.18-24, Sochi, September 19-23, 1994; Cold Fusion, No 11, p.10, 1995.
44. L.G. Sapogin, "On One of Energy Generation Mechanisms in Unitary Quantum Theory". Cold Fusion, No 11, p.10, 1995.
45. Correa Paulo and Correa Alexandra XS NRG in Technology, Infinite Energy, vol.2, #7 p.18-38, Nr 8 p.10-15, #9 p.33-37, 1996. US Patents, numbers: 5.416.391, 5.502.354, 5.449.989.
46. Sapogin L.G. Theory of Excess Energy in PAGD Reactor (Correa reactor). In: Proceedings of ICCF-7, Vancouver, April 1998; Infinite Energy, No 20, 1998, p.49.
47. Sapogin L.G. "New Source of Energy?" Journal "Acknowledgement and Physical Reality", Moscow, vol. 2, #1, page 34-40,1997, (in Russian).
48. Swe-Kai Chen, Chu-Yung Liang «Observation of Cell Temperature Drops». In: Proceedings of ICCF-7, Vancouver, April 1998, p.68-72.
49. Jakimenko L.M. Electrolysis of Water. Chimia Press, Moscow, p.p. 33, 86, 90-114, (1970) (in Russian).
50. Pfleiderer N. Electrolysis of Water. pp. 12, 17-18, 1935, Leningrad (in Russian).
51. Rothwell J. Yasunori Takahashi´s Supermagnets, Infinite Energy, vol.1, No 5,6, p.33, 1996.
52. Sapogin L.G. "Is This Really True?", Infinity Energy, N 28, 2000.
53. Sapogin L.G. «Perpetual Mobiles Operating in Switzerland»,magazine «Chudesa I Prikluchenia» # 2, 2000.
54. Sapogin L.G. «They Say There are No Perpetual Mobiles. Then what is it?", magazine "Samolet", 4, 2000.
55. Sapogin L.G. XXI Century - New Sources of Energy? In: Chudesa i Prikliuchenia, Moscow, No 11, p.32-35 (In Russian) 1996, and No 3, 1998.
56. Sapogin L.G.,Kulikov I.V. "Neue Quantenfeldtheorie und prozesse zur electromagnetischer und thermisher energie mit overunity effekt", DVR-Mitglieder-Journal 2/2000.
57. Sapogin L.G. "The 21st Century: Will it Bring a New Quantum Picture of the Universe and New Energy Sources?", Journal of New Energy,vol.2, #3/4,1999.
58. Panos T. "Electrically Induced Nuclear Fusion in the Living Cell ", Journal of New Energy vol.3, #1, 1998.
59. M.Sue Benford, R.N. M.A. "Biological Nuclear Reactions: Empirical Data Describe Unexplained SHC Phenomenon" Journal of New Energy vol.3, #4, 1999.
60. Schwinger J. "Casimir Energy for Dielectric". In: Proceedings of the National Academy of Sciences, vol.87, p.8370-8372, 1990, "Cold Fusion: Does it Have a Future?" Journal "Cold Fusion", vol.1, #1, page 14-17,1994.

KOZYREV-DIRAC EMANATION.

INTERACTION WITH MATTER and METHODS OF DETECTING

Dr. Ivan M. Shakhparonov

125252, Russia, Moscow,Pestchanny Pas. 20-1-33
phone/fax 8·095-198-2012

In this paper the authors show the possibility of creation of a new kind of emanation. The magnetic monopole beam can be made in space as a result of focusing of some natural substance. Special devices based on the Moebius band elements make the given focusing. This emanation is able to magnetize graphite and organics, decrease the radioactivity, and influence the oncology diseases . The time reverse technology is realized in such devices.

Experimental data, which allow making a conclusion about existence of previously unknown emanation, are presented in this report. Here are descriptions of experiments and methods of measurement. The effects of interaction between new type of emanation and matter have been obtained.

Till the present moment theoretical physics didn't pay attention to the nonoriented configurations and spaces. The reason of this situation is the fact, that from the philosophic point of view it is not possible to determine and locate the area of the nonoriented topological structures in our world. We (eight scientific teams) joined our forces and we needed more than 30 years to solve this problem by an experimental approach.

The fundamental tenet of the casual mechanics developed by Kozyrev can be formulated as follows. There are two types of energy in the Universe. The positive or «right» energy acts as a factor of the entropy increase. The negative, or «left» energy tends to decrease the entropy, i.e. it acts as a factor, which regulates the entropy increase. The «right» energy is transformed to the «left» one and this fact may be interpreted as a course of time from the past to the future. When the energy is transformed from the «left» to the «right» form, time is reversed. Kozyrev supposed [1] that through revolving of a body together with a

6. Activation by nuclear magnetic resonance;
7. Activation by electronic paramagnetic resonance;
8. Activation by electrochemical force.

All these methods can be used as possible way to high efficient energy systems. Gerlovin wrote: "Usually 1, 6 and 7-th methods of structural activation are realized in catalysis simultaneously. Besides, catalysis differs from macroscopic methods because it has the most minimal distances from the sources of activator fields to the activated molecules. And finally, an active participation of force fields created by nuclei of atoms and significantly more active participation of disturbed EPV is possible in catalysis. That's why catalysis is the most effective method of structural activation. The detailed account of this method exceeds the limits of this article and we can only annotate it." [1, p.333]

Information stated above is only a small part of the questions appeared under consideration in Gerlovin's theory of fundamental field (TFF). Other important questions should be considered with a new experimental data.

References

1. Ilia L. Gerlovin, "Foundations of unified theory of all interactions in matter", published in 1990, St.Petersburg, Russia.

2. To the question of multipolarity, Alexander V. Frolov, New Energy Technologies, #1 (4) 2002, St.Petersburg, Russia.

3. N. A. Kozyrev, Selected works, St.Petersburg, LGU, 1991.

4. Practical application of time rate control (TRC) theory, Frolov A.V., New Energy Technologies, #3, 2001, p.15, St.Petersburg, Russia.

Antigravitation Force and Antigravitation of Matter. Methods of its Creation

Anatoly K. Gaponov

Sadovaya Str. 195, Novosibirsk, 630009, Russia

Part I

For a long time there is an opinion in physics about antimatter as a possible source of antigravitation, but the researches on this subject came into a dead end. The existent presentations and formulas forbade the conclusion about antigravitation, but our conducted investigations brought us to the possibility to get antigravitation of substance and to the paradoxical conclusions concerning the next:

1. Two types of space exist:
    a) The Absolute space
    b) The Relative space

2.a The Gravitation Field is the relative space, which has accelerated motion, directed to the center of a planet.

2.b The Antigravitation Field is the relative space, which has accelerated motion, directed from the center of a planet.

3. Gravity force does not depend on mass of a body! The mass can be presented in three versions:

a) m_k –mass as amount of atoms.

b) $W_{m_A^e}$ - electronic-atomic energy in mass.

c) $W_{m_G^m}$ – mechano-gravitational energy in mass.

On the basis of the stated notions we offer to revise the essence of force not only in Coulomb's formula, but in Newton's formula too.

$$F = K\frac{q_1 \cdot q_2}{R^2} \qquad F = P\frac{m_1 \cdot m_2}{R^2}$$

It is well known, that mechanical energy can be bringing in electrostatic charge, where mechanical energy runs (turns) into energy of electric field, where

(mechanical energy) $F \cdot R \rightarrow \frac{E_2 \cdot V_{m^3}}{2}$ (electrical energy)

Similarly it is also possible to insert mechanical energy into mass of a body. As the result, the mechanical energy will turn into energy of gravitational field, where

(mechanical energy) $V \cdot F \cdot t \rightarrow \frac{g^2 \cdot V_{m^3}}{2}$ (gravitational energy)

Since the volume of the Earth is constant, the acceleration of gravitational field will be increased.

It should be logical to expect, that when removing the mechanical energy from mass the inverse process will occur, that is to say acceleration reduction of gravitation field will occur.

In his works I. Newton affirmed about existence of two spaces:

The Absolute space - is an immovable non-rotatable space, which represents a limited cube, with our planet in the center.

The Relative space – is a movable space. It can move with acceleration in the absolute space.

Editor's note: In aether conception this means two parts of aether: some part is involved into the motion with the mass, but another part of aether is immovable.

The main mistake in search of aether consisted in the following: Maikelson's experiments were aimed on search of relative velocity between bodies and space. However, it was the **relative acceleration** between bodies and space that was necessary to search for.

To quote the conclusions of I. Newton: “Body can keep the quiescent mode or mode of rectilinear uniform motion ...” By this, he postulates, that the relative linear velocity between solids and space does not exist. But we know that for rotation it exists (the famous experiments with revolving pail of water).

The gravitational field is the accelerated “falling” relative space, which represents a spherical form. If relative space moves, thus the question appears: where does it move? There is only answer: it moves in the absolute cubic space.

In Einstein’s theory there is notion of unified and curved space in gravitational field, but the contradictions appear here, and on concerning that N. Tesla writes: “Only by presence of force field it is possible to explain the observed motion of celestial bodies, but thus the hypothesis of curvature of space is not necessary. The whole scientific literature on this subject is futile and doomed on oblivion”. [1]

The fact that gravitation is the accelerated moving relative space can be proved by observation of accelerated moving rocket, where the acceleration in rocket is equivalent to the acceleration in gravitational field. Accelerated movement of rocket is relatively, that allows speaking about either acceleration of rocket motion in immovable space, or accelerated motion of space in immovable rocket!

The anti-gravitational field is the relative space, which has accelerated motion from the center of a body (for example: rotating cylinder, Earth satellite and etc.) But it is possible to create the model of anti-gravitation without rotations. On the basis of analogy between mechanical and electric energy comes to conclusion that gravity between bodies does not depend on mass of the body, but on mechanical-gravitation energy, contained in this mass, which is possible to contribute or to extract from. **Therefore, this is the internal gravitation energy.**

Part II

The “Mass” can be considered as a measure of three different conditions of matter:

m_k - as a measure of amount of atoms, representing a “framework” or “container”, in which two types of independent energies are concentrated.

$W_{m_A^e}$ - as a measure of electric energy, which can be either accumulated or extracted, and it have a “compressed” form.

An example of accumulation of electric energy in mass is a big cylinder, rotating with linear velocity, close to velocity of light, in this cylinder the mass of electric and magnetic fields of atoms increases. There are another possible ways to contribute and to extract the said energy from mass.

And finally $W_m M_G$ is the mass, which can be a measure of mechanical energy, or it can be either inserted or extracted from the matter (it can be identified as the gravitational mass). This gravitational mass is what we put our attention on, because it affects upon gravitation and it is able to create antigravitation.

“In his time N. Tesla worked on more general problem, which is the problem of matter and energy. And he has found, as he believed, the new physical principle, on the ground of which he brought forth his gravitational theory that was named dynamic gravitation. But he did not tell about it until almost the end of his life”. [2] **Really, dynamic gravitation is the energy of motion.**

Let’s take the following indications:

V – mechanical velocity
F – force
t – time.
In this case the product $W = V \cdot F \cdot t$ has the dimension of energy. Hereinafter, let’s take

I – strength of electric current
U – difference of potentials
t – time.

Then $W' = I \cdot U \cdot T$ has the dimensional of energy. Thereby, $W \sim W'$ that is to say, the following products are accepted as equivalent:

1. $V \cdot F \cdot t \sim I \cdot U \cdot T$

2. In previous materials it was reported about untraditional way for accumulation of energy, under the condition, in which at constant current I the product $q = U \cdot t$ will depend on amount of inserted energy in unchangeable circuit L = const, in which the energy can be accumulated by untraditional way not only in electric capacity, but also in inductance.

Similarly the energy can be accumulated by untraditional way in a moving body, under the condition V=const and m_k=const (the product $qr = F \cdot t$ will depend on inserted energy and have unlimited value). **Exactly this charge will create the powerful gravitational fields.**

3. Let’s take: F is mechanical force, R is distance. Then the product $F \cdot R$ has the dimensionality of energy. For the uniform electric field the product $E_a \cdot \frac{E^2 \cdot V}{2}$ also has the dimensionality of energy. In this case E_a is constant, E is intensity of electric field, V is volume. Thereby, $F \cdot R \sim E^2 \cdot V$. Similarly, $V \cdot R \cdot t \sim g^2 \cdot V$

We have received the correlations of resemblance for heterogeneous physical values, on the ground of which the following physical experiments can be offered:

On the grounds of the above-mentioned analogies it can be assumed that the accumulation of "compressed" energy is possible in mechanics, as well as in electricity. Since the velocity is relative, that the mass can have zero velocity relatively a observer, who moves with this mass, but the force field will remain unchangeable, since it depends on already invected mechanical energy.

Let's note that:
When the "compressed" electric energy is accumulated, the power field does not change.

When the "compressed" mechanic energy is accumulated, the power field increases.

Now we have come to the amazing conclusion that the gravitational force does not depend on mass of matter, but it depends on mechanic energy, which is included in this mass. This energy is unstable and at contact with land it is disappearing, and at zero gravity it can be saved for a long time.



Fig. 1 The first way to obtain the antigravitational force.

1. The magnets are not revolved.
2. The cylinders of charged capacitor are revolving in different directions.



Fig. 2 The second way to obtain the antigravitational force.

1. The capacitor plates are charged and not revolving.
2. The current circuits are revolving in different directions.



Fig. 3. The third way to obtain the antigravitational force

a) electric
b) magnetic

1. The disk and the ring are made from electrical current conductive material.
2. When these disks rotate, the currents, which emit the mechanic-antigravitational energy in the manner of heat, are formed there.



Fig. 4. The fourth way to obtain the antigravitational force.
Mechanical method.

1. This is an extraction of energy from matter. It was reported in details on the 10 international symposium in Volgo-Donsk, Russia.
2. The difference with electric circuits is that it is possible not only to extract the mechanical energy, but also to insert additional energy in the system.

References

1. Magazine Inventor and Rationalizator, Russia, #9, 1979.
2. Magazine Inventor and Rationalizator, Russia, #9, 1979, p.28

The Capacitor, which has the Energy of an Atomic Bomb

(Review of Anatoly K. Gaponov's research by Eugenie and Marina Golomolzins)

Is it possible to place a pail of water into a one-liter jar? At the first look the answer is obvious: certainly not! However, the inventor from Novosibirsk, Anatoly Gaponov thinks differently. He does not "press" water, but electrical energy, placing an energy equivalent of atomic bomb into ordinary electrical capacitor.

Everybody using ordinary batteries knows its defect: they need frequent recharging. Gaponov's capacitor is slightly smaller than a matchbox. Just come home by electrical automobile, take out the capacitor from engine, and then put it into the pocket. For home needs you can just insert the capacitor into plughole to power the light, boiler, and TV system. In general, each electronic device can have its own capacitor, then an electrical wiring is not necessary. After one

On the grounds of the above-mentioned analogies it can be assumed that the accumulation of "compressed" energy is possible in mechanics, as well as in electricity. Since the velocity is relative, that the mass can have zero velocity relatively a observer, who moves with this mass, but the force field will remain unchangeable, since it depends on already invected mechanical energy.

Let's note that:
When the "compressed" electric energy is accumulated, the power field does not change.

When the "compressed" mechanic energy is accumulated, the power field increases.

Now we have come to the amazing conclusion that the gravitational force does not depend on mass of matter, but it depends on mechanic energy, which is included in this mass. This energy is unstable and at contact with land it is disappearing, and at zero gravity it can be saved for a long time.



Fig. 1 The first way to obtain the antigravitational force.

1. The magnets are not revolved.
2. The cylinders of charged capacitor are revolving in different directions.



Fig. 2 The second way to obtain the antigravitational force.

1. The capacitor plates are charged and not revolving.
2. The current circuits are revolving in different directions.



Fig. 3. The third way to obtain the antigravitational force

a) electric
b) magnetic

1. The disk and the ring are made from electrical current conductive material.
2. When these disks rotate, the currents, which emit the mechanic-antigravitational energy in the manner of heat, are formed there.



Fig. 4. The fourth way to obtain the antigravitational force. Mechanical method.

1. This is an extraction of energy from matter. It was reported in details on the 10 international symposium in Volgo-Donsk, Russia.
2. The difference with electric circuits is that it is possible not only to extract the mechanical energy, but also to insert additional energy in the system.

References

1. Magazine Inventor and Rationalizator, Russia, #9, 1979.
2. Magazine Inventor and Rationalizator, Russia, #9, 1979, p.28

The Capacitor, which has the Energy of an Atomic Bomb

(Review of Anatoly K. Gaponov's research by Eugenie and Marina Golomolzins)

Is it possible to place a pail of water into a one-liter jar? At the first look the answer is obvious: certainly not! However, the inventor from Novosibirsk, Anatoly Gaponov thinks differently. He does not "press" water, but electrical energy, placing an energy equivalent of atomic bomb into ordinary electrical capacitor.

Everybody using ordinary batteries knows its defect: they need frequent recharging. Gaponov's capacitor is slightly smaller than a matchbox. Just come home by electrical automobile, take out the capacitor from engine, and then put it into the pocket. For home needs you can just insert the capacitor into plughole to power the light, boiler, and TV system. In general, each electronic device can have its own capacitor, then an electrical wiring is not necessary. After one

or two years you will just have to come into electric service station and charge your magic capacitor like a gas balloon. Meantime, this research work began from hypnosis.

Anatoly Konstantinovich Gaponov (by birth from Kaluzhskaya region) is Ziolkovsky' countryman. In his youth Gaponov was brought by fate into Sakhalin, where he showed hypnotic abilities. As an inquisitive person Gaponov had organized a research group, started experiments and soon he understood that human brain had incredible possibilities.

A mental prick was made distantly to the hypnotized man, and he uttered a cry of pain. The ability to see people through, to define and to avoid organism's faults, was revealed in a hypnotic trance. It was possible to inspire pleasant emotions, to force "watching" a film on the given subject, as if on the screen. An uneducated person became an erudite, as if being connected to a certain global information database. Thus an idea to make an amazing experiment was appeared.

In one of the experiments Gaponov hypnotized the person with four classes education, and asked, if it was possible to transmit the electric current without wires? The hypnotized person gave the answer, that it was possible. For that it is required to convert the electric energy in x-ray radiation. And what afterwards? Afterwards it is required to focus that rays. By what? By the lens made from quartz glass, gold coated. It was a miracle! The person told about things that in usual condition he had no idea of! The information was received from somewhere outside.

Further quite an amazing thing has occurred. Gaponov asked the hypnotized person, if it was possible to intensify the abilities of hypnotist's brain?

He answered, that he could. "He turned me round and stared at the back of my head, - recalls Anatoly. - And suddenly the smile began to tear my mouth. I could not do anything with myself. When my mouth was sprawled literally from ear to ear, the hypnotized person in some inhuman voice declared that experience could not be continue since the cerebral hemorrhage would occur. I was hardly able to give the order to stop the experiment".

Thereby, the experiments with hypnosis gave the beginning to the thirty-years period of inventions in the field of accumulation and transmission of energy. After the return to native Kaluzhskaya region, Gaponov was occupied with physics, development of logical thinking and became the town champion in chess.

The necessary books fell into his hands by themselves: some time a certain acquaintance gave it to read; another time he found the last copy in a bookstore. As a majority of self-taught inventors, Anatoly preferred practical experimentation. In quest of laboratory for realization of his own ideas, he moved to Novosibirsk. **As a result, in 1980 Gaponov has made experimental system for compression of energy.** From the school Physics we have known the notion of "electric arc" – it is a small blue lightning between two electrodes. Gaponov has tamed this lightning in such a way, that having drawn apart two wires, which executed the role of electrodes, by hands and got the arc by length up to half meter. Anatoly confirms that in principle, it is possible to create an arc of any desired length under any amperage.

One of the experiments found out one more enigmatic characteristic of electric discharge. During electric photography of arc a person happened to be between the camera and the system. On typing pictures, the researchers have found with surprise, that the electric arc was perfectly seen through the person. That is to say, it created the invisible field, for which material object was not an screening obstacle, and which was fixed on the film.

The further experiments with electric arc have allowed to get a new source of energy, as well as to open the possibility of setting light and sound on fire! Just imagine, you ring up a bell, it's sound waves spread at once in all directions, and then flash up with bright blaze.

(Editor's note: this experimental facts are rare modern evidences of possibility to create longitudinal electric waves. It is clear analogy here with sound waves in air since they are longitudinal waves also. Alexander V. Frolov)

When the problem of energy source was solved, Gaponov turned to the problem of energy accumulation. According to Gaponov, he has provedexperimentally the possibility of charging of an ordinary capacitor with any amount of energy. This statement sounds paradoxically: how it is possible to place the unlimited amount of contents in limited volume? However, this is not a simple way.

Gaponov believes that energy "placing" occurs not in space, but in time by means of his system! In what way? Imagine, that you fill one-liter jar with water. But already after an instant the water-filled jar is in past, and that present one is once again ready to be filled. And so ad infinitum. Water as if it fills a certain "time reservoir", and a jar is just a neck of this "time reservoir".

(Editor's note: This method is described in other articles also but usually it is pure mathematical discussion about Minkovsky space-time and theoretical proposals. Gaponov's experiments are realization of fantastical idea to take power from the time flow, i.e. from Past or from Future to get over-unity in Present space. Alexander V. Frolov)

"It is possible to demonstrate one more example, - Anatoly Gaponov adds. – Let's charge the capacitor with the expectation, that it will supply the light bulb

for one second. Thereby, on the Earth this light bulb will be on only for an instant. But if the same capacitor with light bulb is placed in rocket and dispersed around the Earth at the velocity, closed to velocity of light, time on the board of rocket will be so slowed that the light bulb on rocket will be glowing infinitely long for an observer from the Earth. It means, that in any case it is the same energy quantity, but in one case it's action is sprawling for a second, and in another one it is sprawling for eternity! It is possible to say, that in my system I have created the condition corresponding to this hypothetic rocket".

The system for accumulation of electric energy could be charged by ordinary wall plug 220 VAC. Time period of charging is different and depends on the certain scheme of the system. By the way, sea electric slopes are the certain natural analogues of such capacitor. Some elements of internal device of these sea creations reminds the "pump" elements for placing of electric energy into "temporal jar".

Finally, the third Gaponov's invention is the system for transmitting of energy without wires. As well as in two previous cases, there is an experimental device. Anatoly Gaponov speaks that he has succeeded in getting the essence of experiments for transmitting of energy, which were conducted by Tesla.

It is clear, that the main advantage of this method is an absence of wires and losses of electric energy. The electricity could be transmitted directly into any point, where receiving equipment placed, let say from Kaluga to Sahara. However, this is not so interesting for anybody, since for the present day Anatoly Gaponov's inventions don't have demand.

" The first system was created twenty years ago", - says Mr. Gaponov. – "Now I am fifty five, but things have not budged an inch". He adds dreamily: "Eh, if only I had a laboratory and some money...".

Gritskevitch's Hydro-Magnetic Dynamo

Oleg V. Gritskevitch

RUSSIA, 690002, VLADIVOSTOK,
Okeansky prospect, 99 - ap.112
phone/fax: (7-4232) 424-674 Email: ogri@mail.primorye.ru
Russian Academy of Energy and Information,
Russian Academy of Natural Sciences

Editorial: The article presents construction and operation of Oleg V. Gritskevitch's hydro-magnetic dynamo, which is an example of very powerful new energy system. The prototype in Armenia has been produced over 1500 KWtts power during several years.

The author was born on 14 August 1936 and grew up in Vladivostok, Russia. He is married and has a son Boris. Gritskevitch is a physicist by education. He worked in the Far - East branch of the USSR Academy of Sciences. Since 1985 he has been working independently as an inventor. He has more than 70 patents on inventions ranging from household engineering up to high technologies, which he has been trying to apply in our country and met big difficulties. After numerous attempts to receive the patents the author was convinced that outflow of the information occurred. Therefore he has received the state certificates as on know-how (on a French way of patenting), for all his inventions.

Introduction

During the Institute for New Energy 1999 Symposium, I lectured on my hydro-magnetic dynamo. This paper is my attempt to explain the construction and operation of my dynamo.

To fool investigators of my secrets, I have an occasion provided misleading information. For example, the drawing accompanying the Russian patent referenced below shows a cylinder across the toroid to fool readers. The real dynamo only has the toroid without the cylinder. Even its name "hydro-magnetic dynamo" is somewhat deliberately misleading.

I have some familiarity with the new energy field. Nearly all purported new energy devices are fairly small electrical generators. The dynamo may be the only new electrical generator which most nearly meets all the requirements of an ideal large-scaled electrical generator. My dynamo really is the single most valuable invention the world has ever known.

Alexander V. Frolov of St. Petersburg recommended me to contact with Dr. Patrick Bailey, Institute for New Energy since Pat has lots of contacts who could possibly help me with patenting my invention of a new source of energy in USA.

I conducted the work on the theory and creation of the electrostatic generator-converter «Hydro-magnetic dynamo» about 20 years. (See dynamo history below.) The first primitive equipment was created when I worked in Academy of Sciences. During that time various changes were introduced in the generator and in the theory of its work. It is now possible to manufacture, install, and apply it in industry.

For the first time I made the public report on this work in 1991 on a symposium in Volgodonsk city. The report received the positive replies and reviews of the experts of a nuclear industry in USSR. The same year I was accepted in International Nuclear Society. In these years I offered development of this technology to different state bodies and private enterprises. But there was the only answer: "It is very interesting and perspective project, but there is no money for it".

NEW ENERGY TECHNOLOGIES #7

1. Gravitonics is Electronics of the XXI Century, Spartak M. Poliakov, Oleg S. Poliakov
2. Experimental Research on Gravitational Propulsion System. Review
3. Beamship Technology: A Re-working of Early 20th century Discoveries, Russell Anderson
4. Commercial Antigravity, Tim Ventura
5. Action without Reaction. New Gravidynamic Paradox, Yuri N. Ivanov
6. New Possibilities of Vortex Electric Power Devices, Stanislav A. Lisnyak
7. Investigation of Electric Energy Transmission Processes in non-Metallic Conducting Channels, D.S. Strebkov, A.I. Nekrasov, S.V. Avraamenko
8. Microcosm – Universe - Life, Alexey G. Shlienov, Ernest L. Petrov
9. Hypothesis of a Theory of Everything, Jack P. Gibson
10. The Charge and Mass of a Photon, Dzabrail Kh. Baziev
11. The Homopolar Motor: A True Relativistic Engine, Jorge Guala-Valverde, Pedro Mazzoni, Ricardo Achilles
12. Weight Reductions Generated by Bucking-Field Permanent Magnets, William C. Simpson
13. Advanced Nuclear Waste Decontamination Technologies, Mark Porringa
14. Experimental Investigations of the Radioactive Isotope Half-Value Period Changing in the Local Volume ofCause-Effect Relations, Igor A. Melnik
15. Tilley Electric Vehicle
16. The Problem of Time: Force as the Cause of Change in the Course of Time, Valentin P. Oleinik
17. Time and its Physical Relationships, Andrew Michrowski
18. Time as Phenomenon of the Expanding Universe, Michael H. Shulman
19. The Experiments on Thermo-Gravitation. Review
20. Letters to the Editor from Hector D. Perez Torrez

New Energy Technologies

Published by Faraday Lab
Issue #4 (7) 2002

Research on advanced space propulsion methods and new energy systems

History of invention: Poliakov's vortex drive

Patented by Research Institute of Space Systems named by Krunichev, Russia

Also in this issue:

- * New gravidynamic paradox
- * Experiments on weight reduction
- * New possibilities of vortex energetics
- * Experiments on homopolar motor
- * Physical relationships of time

Gravitonics is Electronics of the XXI Century

Hypothesizes, Conclusions, Speculations

Spartak M. Poliakov,
Oleg S. Poliakov

60-let SSSR str., 1-167, Friazino,
Moscow area, 141120, Russia
Tel: (096) 564-65-67

(This article was published in "ELECTRONICS: Science, Technology, Business" magazine 5/2000 p. 8-13)

Today we can easily insist that ways to solve main gravitonics problems are already defined, at that the practical realization of any of them will mean the break through in engineering. So, what successes has the Russian science already achieved in the area of gravitonics, and what priorities can we lose here in the nearest future?

Introduction to Gravitonics

The electronics of the "past century" uses electron as a ball, which has weight, radius, electric charge and magnetic moment. These very parameters define electron behavior in the electrostatic, magnetostatic and electromagnetic fields. But electron abilities are not limited by it; electron spin and internal microstructure features remain unaccounted and unclaimed. Evenly speaking, General Theory of Relativity (GTR) of Einstein was a power impulse for mathematical physics development and gave birth to many productive ideas. But the main problem, that is the secret of gravitation, remains undisclosed… In works of K.P. Stanjukovich [1] and A.Z. Petrov [2], who carefully followed GTR, it was shown that this theory described neither energy, nor impulse of gravitational radiation, i.e. it can not explain gravitation. About 20 years ago V.B. Braginsky, today's RAS Corresponding Member, came up with an idea: "if the propagation speed of gravitational signal is higher than the velocity of light, there will be already another theory, not GTR!" Maybe, the reason is the postulation of equality of gravitational and electromagnetic radiation velocities?…

Today the approximate theory of gravitational radiation sources can be built on the basis of the following simple considerations: if during annihilation of "electron-positron" pair there creates the pair of gamma-quantums with energy about 0.511 MeV, then the pair of back gamma-quantums with the energy about 0.511 MeV, could create "electron-positron" pair. Is it possible to assume, that electron, positron and gamma-quantum with the energy about 0.511 MeV are just three stages of one and the same object?! If it is possible, then for the rational description of the given object we will have to suppose the existence of subparticles, named by us uniquantums [3], or named by other authors microleptons [4].

On the basis of Heisenberg uncertainty relation conformably to the energy and duration of quantum of electromagnetic radiation, measured by laboratory means, it is possible to calculate the minimal "electrical length" of photon (i.e. quantum geometrical extension in free space in wave-length units), which is equal to 137λ, and in the uniquantum theory it is equal to 137 uniquantum-antiuniquantum pairs. On the basis of these conceptions it is possible to construct the spatial microstructure model of electron. So, what kind is it?

We think, that electron can be represented as thin-walled spheroid, walls of which are two light (C) barriers, separating the "internal" part of electron from the "external" one. From the traditional physics point of view "over-barrier" space is an "imaginary" one. This very space can contain the gravitational mass of electron. The radius of the gravitational spheroid is equal to the half of the classic electron radius, and its imaginary weight is 137 times more than the rest mass of electron. Being "cut" off by the double light C-barrier, uniquantums of the spheroid internal part are as if non-existent for the outer world, and the rest mass of electron is formed by magnetic energy of three uniquantums on the external orbit with the classic electron radius. This very spheroid, rotating with the tangential velocity C, let us get the precise value of the electron spin.

The study of presented model shows, that:

- The "electromagnetic" rest mass of electron is "magnetostatic";
- The gravitational mass of electron is an imaginary value and it is 137 times more than the rest mass of electron;
- The gravitational radius of electron is two times less than the "classical" one;
- The "internal" gravitational radius of electron is 45.7 times more than the external one, i.e. the internal space is compressed per 45.7 times (!);
- The spin is equal to the classical one, but this value is imaginary one (!);
- The value of the "effective" electron charge is three times more than the classical tabulated value;
- The native magnetic field of electron is equal to $8{,}9\cdot10^{13}$ Oersted;
- The gravitational constant is equal to 10^{33} $cm^3/g.s^2$, i.e. it is about 10^{40} more than the "world" gravitational constant of the Earth;
- The gravitational energy of electron is equal to $137\cdot0.511$ MeV, i.e. 137 times more than the equivalent energy of the rest mass of electron.

The model is paradoxical. But it can be tested experimentally! Comparing "electromagnetic" rest mass of electron with the relation of electromagnetic energy to gravitational one, it is possible to determine the connection between magnetostatic and gravitational energy of electron, and, therefore, with energy of the magnetized ferromagnetic.

Gravitational constants of the Earth and of the electron differ in about 10^{40} and can be described by the same simple equation:

$$\gamma_{loc} = 2k\gamma_0 \cdot \omega^{3/2},$$

where k - is a parameter of the gyroscope shape, γ_0 - is absolute universal constant, equal to 1/137 and ω - is native rotation frequency of the gyroscope.

Let us assume, that gravitational constants of all objects should be described by this equation. By substitution of the new gravitational constant into the known equation of the gravitational energy $W = \gamma m^2 / r$ we will get the equation of the gravitational energy of rotating gyroscope with any size (from electron up to the Galaxy!). Thus, the main point of the "non-Einsteinian" theory of gravitational energy sources comes to the thing that any rotating object and any magnetized ferromagnetic have their own gravitational energy, and the sources of gravitational radiation can be only nonlinearly moved objects, or objects which are in the state of change of phase (for example, permanent magnet during its demagnetization). It is the gravitational theory and explanation of "strong" and "weak" interactions!

Laboratory test of the equations

Magnetostriction

J.P. Joule found the effect of change of ferromagnetic linear sizes and volume during magnetization as early as 1842. Magnetostriction is widely used in modern technique, but in the physical encyclopedia of 1963 there is the following honest acknowledgement: "For the most ferrites both longitudinal and transverse magnetostriction is negative; the reason of it is still unclear."

In the scientific literature magnetostriction is usually defined as $\lambda=\Delta L/L$. However, during the change of external field to some arbitrary and enough small value ΔH, it is advisable to define magnetostriction as $\lambda=1/L\cdot\Delta L/\Delta H$, since in magnetostriction experiments the value $\Delta L/\Delta H$ (or $\partial L / \partial H$) is changed. By means of the suggested equation $W=137(BHV)=BHV/\alpha$, which connects magnetic energy with the gravitational one, it is possible to get enough simple equation for the magnetostriction:

$$\lambda = 1/L \cdot \partial L/\partial H = \alpha \cdot k / (B \cdot H)_s \cdot H^2 \cdot \partial\mu / \partial H$$

where $(B\cdot H)_s/\alpha$ - is the density of gravitational energy in the point of magnetic saturation, k – is the parameter of share of gravitational field in the magnetostriction effect, H - is magnetic bias, $\partial\mu/\partial H$ - is differential magnetic conductivity.

The new equation qualitatively corresponds to four known features of magnetostriction [5], namely:

- The magnetostriction sign is defined by the sign of $\partial\mu/\partial H$, i.e. by the course of the magnetization curve, measured in the direction of calculated component of the linear magnetostriction;
- Graphical sum of three linear components of magnetostriction, calculated by three main axes of the anisotropy form of the model, is always negative and numerically close to the value of the volume magnetostriction;
- Magnetostriction is an even effect, since the equation includes squared value of the external magnetic field;
- Dependence of magnetic conductivity μ from the filed H and hence dependence $\partial\mu/\partial H$ has a hysteresis nature. Therefore, the magnetostriction is a hysteresis phenomenon too.

So we have the right to "close" the question of physical encyclopedia on the cause of magnetostriction. **Magnetostriction is the secondary gravitational effect of ferromagnetic "self-constriction" in its own gravitational field.**

Gravitational-optic effects of GTR

Distortion of the light beam, passing near the Sun and the photon frequency bias in the field of terrestrial gravity (the Nobel experiment of Paunda and Rebki) are the main arguments in favor of GTR canonization. It is very attractive to repeat these experiments in laboratory conditions, basing on our conception of the origin of gravitational field.

The acceleration of gravity, used in experiments with ferromagnetic, reached the value $4.72\cdot10^{15}$cm/s^2, i.e. about $4.8\cdot10^{12}$g. At such values of acceleration there is no necessity to introduce a definition "space masses". In these experiments there was used the optically transparent ferromagnetic, which was the saturated solution of manganese chloride in water at room temperature. The experiment on the beam distortion was made in 1975 [7]. It was shown, that this effect is the result of two simultaneous processes. The first is an intense drift of magnetic ions, which forms the gradient of index coefficient that causes the light beam distortion. Another process is a relatively weak gravitational beam distortion, for which, nevertheless, the relation of deviation angle to the track length (the length of the dish is about 100 mm) is turned out to be about 10^{10} more than in "Einsteinian" gravitational-optic experiments.

The experiment on bias of the optic radiation frequency [8] was made in 1978-1980 and was repeated in 1983. With use of heterodyne and interferometrical methods of measurement we were succeeded to observe effects of "red" and "blue" frequency biases in the non-uniformly magnetized ferromagnetic by means of simple displacement of the working dish (with the length about 40 mm) from one side of the magnet gap to another. The maximum displacement is about 10^{-5}, that is about 10^{10} more than in the experiment of Paunda and Rebki.

Problem of the propagation speed of gravitational radiation

There are still only few publications about such fundamental parameter as the propagation speed of gravitational radiation; it is able to speak only about pages, or even lines! Let us refer to major sources:

I. Newton: *"The propagation speed of gravitational interaction is equal to infinity."* It is an argument, because otherwise we would have to bring the "delay" parameter Δt into the Law of Gravity, what is not noticed in real conditions of star observations [9].

P.S. Laplace in 1787, taking into account observation errors of that time, showed, that gravitational interaction speed was about $50 \cdot 10^6$ times more than the light propagation speed, i.e. it was about $1{,}5 \cdot 10^{18}$ cm/s [10].

A. Einstein: *"The propagation speed (of gravitational interaction) is equal to the light velocity"*. This statement is postulated.

Even during the change of propagation speed of gravitational radiation between the Earth and the Moon it is impossible to define the signal delay about 10^{-11} s, i.e. we cannot measure directly the propagation speed of gravitational radiation (supposing that we have both generators of the gravitational radiation and receivers of it). But this speed can be estimated by the reflection impulse, what exactly was made in 1987 [3]. And its value is about $9 \cdot 10^{20}$ cm/s!

On the basis of conservation law of impulse of unidirectional radiator with arbitrary energy type we can get a simple equation:

$$F/(dW/dt) \cong 10^4 \cdot V/C^2 \qquad \text{[g/Wt]}$$

where V – is the speed of radiation propagation, F – is tractive force in grams, dW/dt – is power of radiation in Watts and C – is velocity of light.

For making the experiment there were constructed, produced and adjusted: sensible scales with one degree of freedom (sensitivity of balance is about 1g at the oscillator mass together with the moving element of scales which is about 50kg); the indication system of small mass changes (phase-meter receiver); gyroscopic system, changing the mass in the dynamic mode (there are 16 possible operating modes – from the rotation with steady and variable angular speed up to the forced precession with the variable angle of precession, with the "right" and "left" rotation of all load-bearings elements at option); power sources and commutation automated system. The period from idea up to its realization took about two years (1985-1987) [3]. Taking into account the real parameters of the system, the program of calculation was drawn and propulsive burns were calculated. The results of machine computation can be compared with real impulses, demonstrated on the screen of the oscilloscope.

If strange speed value 177 C^2 is discarded, then the middle speed value is close to C^2, i.e. to $9 \cdot 10^{20}$ cm/s! Of course, we would like to think that this is the second fundamental matter speed of our world, which we has approached experimentally …

Gravitational receiver

During the creation of gravitational antennas and receivers there appear almost insuperable difficulties from the modern fundamental science point of view. That is why it is advisable to look at this problem from another side. At first, it is necessary to consider gravitational radiation interaction not with the mass, which it goes through without losses, but with the gravitational field of independently gravitating mass, when the interaction must be the most effective because of the principle of physical processes reversibility. At second, it is necessary to choose some critical parameter of auto-gravitating receiver as a value, which is directly measurable by gravitational detector. For example, angular velocity of free rotation of thin disk with big diameter, the frequency of magnetization precession during NMR (nuclear-magnetic resonance) or NFMR (non-linear ferromagnetic resonance) etc. can be chosen as such a value.

In 1987 there was the first successful attempt to receive the gravitational impulse. The source of external signal was gyroscopic precessing system with the variable angle of precession (the propagation speed of gravitational radiation was measured by it). Double gyroscope, setting in motion by one electric motor, but with the opposite directions of rotation, was used as a detector. Between disks there was placed the source of light, impulses of which, passing through disks openings, were registered by photodiodes. Their signal came into differential circuit of data processing. The memory oscilloscope reproduced impulses of gravitational radiation. At that radiating system and memory oscilloscope was started up simultaneously. During the work process there appeared a problem of exciting of slow auto-oscillations of gyroscope-detector. This problem together with the low frequency of auto-oscillations of mechanical system led to a conclusion that this research direction is not very promising. However, the fact of detection was proved!

Gravitational engine of continuous action

Only about nine years passed since the appearance of the idea about engine up to its realization! In 1997 the engine was produced and tested. The engine with weight about 28 kg was made "weightless" on the magnetic hanger, and longitudinal draft, appearing in accordance with the impulse conservation law, was measured by micrometer detector of longitudinal shifts (sensitivity is about 50g/point). Such engine could be built still in the beginning of the last century… However, it has a secret **that is a gyroscope with the variable radius, working in the continuous mode.**

The engine power is defined by the formula

$$\frac{dW}{dt} = 5k\gamma_0\omega^{3/2}\left(\frac{m^2}{r^2}\right)\cdot\frac{dr}{dt}$$

In June of 2000 there were made experiments with the model of gravitational engine, which represents a gyroscope with the variable radius (see photo on the 1st cover page). The mercury was used as rotating fluid. Tests were made in the Research Institute of Space Systems named by Krunichev. In three experiments, at a certain speed of rotating fluid there was fixed a decreasing of the engine weight (38,5 kg) up to 1.0-1.5 kg (2-3%). The specific impulse of the engine was equal to 2.5-3.0 kg per kilowatt of electric power. Analysis shows, that the increasing of propulsion force is possible at optimization of design and operating modes.

Some preliminary resume

In the magazine "Foreign Literature" #1, 1967 the article "For hundred years forward…" by Jack Marabini was published. There were made some conclusions about prognostic work of firm Rand Corp., including the area of gravitational technique. Namely:

- Development of communication facilities on gravitational waves in 2000;
- Creation of spaceships with antigravity engines in 2050;
- Transformation of gravitational energy into electric one in 2100.

In the article it was noted, that the most "fantastic" predictions of this firm, as a rule, come true passing ahead.

According to our crude estimations, the propagation speed of gravitational radiation is "C" times as much than the velocity of light, but we know neither laws of attenuation and propagation of gravitational waves, nor laws of their reflection and refraction, nor laws of their interaction with the substance… The large routine work is expected: making of measurements and investigations, tabulating of obtained data, publishing and society familiarization of the results, their "popularization". It is necessary to learn to use gravitational radiation and to protect oneself from its accidental influences, to design standards and dosimeters, etc., i.e. to repeat the way of radio engineering and nuclear physics comprehension.

For that we need generators and receivers of gravitational radiation. It means that the financial support is necessary. And engineers are sure to be ready to pay the highest price for the chance to give to the Mankind spaceships, systems of instantaneous communication with them and real perspectives for the very long history.

Conclusion

We have already passed the long way, if not in space, then in time. We have made:

- Gravitational engines of continuous action with the specific impulse about 2.5 kg/kWt [11];
- Transformers of gravitational energy into thermal and electrical ones [12];
- Communication system based on gravitational waves [13];
- Receivers of gravitational (microlepton) radiation of biological and mineral objects [5];
- Devices for control of "laboratory time" flow (time machine) [14].

The main goals of the authors were to attract readers' attention to the problems, which demand an urgent solution. Some questions were decided, and even seemed to be clear. It also seems to be clear what to do further. And what do you think about it?

References

1. Stanjukovich K.P. Dr. Phys.-Math. Sc. CTR and gravitation // Seminar of the Moscow nature investigators society. // M. – 1966.
2. Petrov A.Z. Some peculiarities of CTR // Seminar of gravitational chair of Kazansky SU. (Preprint / Ukraine Academy of Science) // Kiev – 1971.
3. Poliakov S.M., Poliakov O.S. Introduction into experimental gravitonics. // M.: Prometey – 1991.
4. Patent #2113000 RF. Method to search minerals by their own radiation, device for its realization and microlepton detector / / Ohatrin A.F., Ohatrin A.A., Sizov V.S. Priority from 21.07.1997.
5. Kirensky L.V. Magnetism. // M. Nauka – 1967, p.141.
6. Vonsovsky S.V. Magnetism // M. Nauka – 1971, p.404.
7. Poliakov S.M., Martynov V.F. Method of deflection and focusing of optic radiation. A.n. #2187534, 10.11.1975.
8. Poliakov S. M., Olihov I. M. Dorofeev V. A. and others. Displacement of optic radiation frequency in non-uniformly magnetized ferromagnetic // Proceedings of the Moldova Academy of Science. Series of Physicotechnical and mathematical sciences. // Kishinev – 1983, #2, p. 57-59.
9. Isaac Newton. Mathematical beginning of Natural Philosophy // Transl. Moscow-Leningrad – 1936.
10. Laplace P. S. Statement of the world system. // Leningrad, Nauka, vol. 4, p. 197-198.
11. Poliakov S.M., Poliakov O.S. The beginnings of experimental gravitonics // In: Proc. of Int. Conference "New Ideas in Natural Science" // S.P. – 1996, p. 529-536.
12. Potapov Ju.S., Fominsky L.P. Eddy energy // Cherkassy, Kishinev OKO-Plus – 2000, p. 387.
13. Akimov A.E, Shipov G.I. Torsion fields and their experimental manifestations // Proc. of Int. Conference "New Ideas in Natural Science" // S.P. – 1996, p.22-225.
14. Chernobrov V.A. Secrets of time // M., AST – 1999.

About the authors:

Spartak M. Poliakov. Graduated from Kishinev State University. Profession is physicist-experimenter. He works in electronic industry for about 47 years. S. M. Poliakov is the author of more than 50 scientific works. One of his latest books is "Introduction into experimental gravitonics". Interests: microwave engineering, gravitational electronics, faster-than-light communication transformation of gravitational energy into electric one.

Oleg S. Poliakov. Graduated from Moscow Institute of Electronics. Profession is "Semi-conductor electronics". Interests: computer engineering, industrial gravitonics. He is a co-author of "Introduction into experimental gravitonics" and "Self-tutorial of computer work".

BEAMSHIP TECHNOLOGY

by Russell Anderson
russanderson3@hotmail.com

Read in this issue a report by Russell Anderson, USA, on beamship Model Flying Craft

www.americanantigravity.com

Publisher Faraday Lab Ltd

Editor-in-Chief Alexander V. Frolov, Editor Olga O. Leontyeva,
Designer Ekaterina F. Yakovleva
Scientific Advisory Board Kyrill P. Butusov

New Energy Technologies Magazine, is published by Faraday Lab Ltd, six times a year. Correspondence Address:
POBox 37, St.Petersburg, 193024, Russia
Phone: 7-812-380-6564, net@faraday.ru, www.faraday.ru

Subscription: $90 any foreign. Air mail delivery included
PRINTED IN RUSSIA **Copyright © 2002 by Faraday Lab Ltd.**
All rights reserved.

Experimental Research on Gravitational Propulsion System

*Editor's: It is a review of the article by **V. A. Menchikov**, the Director of Research Institute of Space Systems, named by Krunichev, Russia. The article was published in"Polyet" magazine #10,2001, p.38-39, Russia. It scrutinizes the matters on development of propulsion systems based on the unconventional approach to the problem of gravity, i.e. gravitational engines. It also cites the results of the gravitational engine model research made by means of the experimental facility, created in the Khrunichev Research Institute of Space Systems.*

The device, transforming rotary motion into unidirectional motion, looks like S.M. Poliakov's one. It also operates with rotation of liquid, which causes the propulsive force. Truly speaking, Poliakov had an agreement with Research Institute of Space Systems named by Khrunichev in 2001. Some funds were assigned to develop the device, however the project, into which Poliakov had put a lot of work, still remains unrealized. Besides, the scientist's name is not even mentioned in the patent.

***

Scientific and technological advance opens to mankind more and more wide abilities to use space for the solution of global problems. In many respects the complete realization of these abilities will be defined by the developement of means used for delivery of payloads into the space. In the XXI century the dominating use of reactive chemical and electrical propulsion systems in rocket-space technique as well as low application level of engines with other physical principles can be the factor of an "inhibitory" influence for the development of such techniques. It is caused by the fact that created rockets practically do not correspond to noticeably increased standards of safety, operating costs, costs for transport operations execution and ecological influence on the environment.

Thus, there becomes to be urgent the problem of development of alternative approaches towards the creation of propulsion systems, made for the rocket-space technique on the base of unconventional ideas and engineering solutions. A rather old-established idea of creation of gravitational engine should be concerned as one of such ideas. It is based on the unconventional approach to the problem of gravity. Nowadays many countries take part in solution of the gravitational problem, namely Russia, USA, Japan, etc., and if till recently only some scientists and inventors showed the interest to this problem, then now it arouses interest of research-and-production majors. Unfortunately, now it is not possible to speak about sufficient theoretical or practical development of this idea. However, the interest is so considerable, that practically separate experiments on this subject were made earlier and they are still made nowadays. After all, stakes are very high and are defined by applied nature of the problem (the ability to create qualitatively new engines for the rocket-space technique), as well as by its scientific significance.

One of the directions to solve the problem of the creation of gravitational propulsion systems is the realization of associated theoretical and experimental methods of the search of physical processes, leading to the antigravity effects appearance, which cannot be adequately described by existed theoretical conceptions. V. Shauberger's patent, based on the postulate of gravitational energy radiation by "disturbed rotating mass" can be considered as an example of such practical realization. Taking into account a number of known experimental results, a model of gravitational engine and experimental system for estimation of this model parameters were made in Research Institute of Space Systems named by Khrunichev to provide the practical realization of Shauberger idea (Fig.1). It is the metal construction, which provides the model displacement in upward direction with the ability of its rotation around vertical axis.



Fig.1
Schematic circuit of the experimental system

Later, to increase the system sensitivity it was improved and the block system of suspension was replaced by the lever frame.

Turning angle of the stand frame, where the model of gravitational engine is suspended, depends on the following: weight and geometry characteristics of the frame; weight characteristics of the engine (of counterweight); engine propulsion and frictional forces in bearings. Laser indicator of frame turning angle and vertical ruler let increase the gauge of lifting height of the gravitational engine model proportionally to the arm of light beam.

On using this system there was made a wide cycle of tests, which qualitatively confirmed the presence of propulsion force. Tests were recorded by video. The analysis of experimental results shows, that acting time of propulsion was about 12 s at each switching. During repeated switching of the gravitational engine model in different conditions it is able to create the propulsion, the value of which at 40…50 s of operation can be about 3 standard units of propulsion force (1 standard unit of thrust is about 10gs), and while using the powerful electromotor it can be about 80 standard units of propulsion at the intervals up to 4 s.

Research Institute of Space Systems named by Khrunichev, works on automation of experimental researches and on development of laboratory resources for factor analysis of appearance of the propulsion vector with the usage of the described model of gravitational engine.

Patent

The patent was published in the Bulletin of Patent Information in 2001.
(11) 20946
(51) 7 F 16 H 27/00
(21) 2001121237/20
(24) 01.08.2001

Editorial: V.A. Menchikov together with A.F. Akimov, A.A. Kachegan and V.A. Svetlichnyi have got this patent. Dr. Spartak M. Poliakov, being the author of the principle, is not mentioned at all in the patent.

NEWS REVIEW

Boeing Tries to Defy Gravity

According to Jane's Defence Weekly (UK), http://www.janes.com, Boeing, the world's largest aircraft manufacturer, has admitted it is working on experimental antigravity projects. These projects are able to overturn a century of conventional aerospace propulsion technology and alter the entire aerospace business. Boeing uses researchers by Yevgeny Podkletnov, who claims to have developed a device, which can shield objects from the Earth's gravity. Many conventional scientists, who have not been able to reproduce Dr Podkletnov's results, view his project, named «GRASP» (Gravity Research for Advanced Space Propulsion) with suspicion.

Dr Podkletnov claims to have countered the effects of gravity in an experiment at the Tampere University of Technology in Finland in 1992. The scientist says he found that objects above a superconducting ceramic disc rotating over powerful electromagnets lost weight. The researches have shown that the reduction in gravity was small, about 2%, but the implications - for example, in terms of cutting the energy needed for a plane to fly - were immense.

His devise, named "impulse gravity generator" is capable to produce a beam of "gravity-like" energy that can exert an instantaneous force of 1,000g on any object – enough, in principle, to vaporize it, especially if the object is moving at high speed. Laboratory installation has already demonstrated the 4in (10cm) wide beam's ability to repel objects a kilometer away and that it exhibits negligible power loss at distances of up to 200km.

Applications of the device can include space launch systems, artificial gravity on spacecraft, aircraft propulsion and "fuel-less" electricity generation ("free energy"). However, observers say that Podkletnov's device could be engineered into a radical new weapon, for example, adapted for use as an anti-satellite weapon or a ballistic missile shield.

Documents, obtained by reliable sources, show that Boeing is taking Dr Podkletnov's research seriously. It is also possible, Boeing admits, that "classified activities in gravity modification may exist". The paper points out that Podkletnov is strongly antimilitary and will only provide assistance if the research is carried out in the "white world" of open development.

Boeing is the latest in a series of high-profile institutions trying to replicate Dr Podkletnov's experiment. The military wing of the UK hi-tech group BAE Systems is working on an anti-gravity programme, dubbed Project Greenglow. The US space agency, Nasa, is also attempting to reproduce Dr Podkletnov's findings, but a preliminary report indicates the effect does not exist.



1. Solenoids create magnetic field
2. Spinning, super-conducting ceramic ring
3. Liquid Nitrogen acts as coolant

BEAMSHIP TECHNOLOGY

by Russell Anderson
russanderson3@hotmail.com

Read in this issue a report by Russell Anderson, USA, on beamship Model Flying Craft



www.americanantigravity.com

Publisher Faraday Lab Ltd
Editor-in-Chief Alexander V. Frolov, Editor Olga O. Leontyeva,
Designer Ekaterina F. Yakovleva
Scientific Advisory Board Kyrill P. Butusov

New Energy Technologies Magazine, is published by Faraday Lab Ltd, six times a year. Correspondence Address:
POBox 37, St.Petersburg, 193024, Russia
Phone: 7-812-380-6564, net@faraday.ru, www.faraday.ru

Subscription: $90 any foreign. Air mail delivery included
PRINTED IN RUSSIA **Copyright © 2002 by Faraday Lab Ltd.**
All rights reserved.

Beamship Technology: a Re-working of Early 20th century Discoveries

Russell Anderson

Applied Electrogravitics 377 Avon Rd., Ste. D-119
Devon, PA 19333 russanderson3@hotmail.com
484-255-1072

Some Basic Background

The concept of an electric aero-spacecraft with no moving parts was initiated by the Yugoslavian electrical wizard **Nikola Tesla**, who lit the entire world 100 years ago, at the turn of another century, with his revolutionary AC electric current. In 1916-17, Dr. Francis Niepher performed meticulous mass-deflection experiments under rigorous scientific conditions with lead spheres suspended by wires with shielded and unshielded containers. An accounting of this important series of experiments is in TRANSACTIONS OF THE ACADEMY OF SCIENCE OF ST. LOUIS VOL.23, 1916 and 1917. Related article is in THE ELECTRICAL EXPERIMENTER, March 1918.

Before 1905, **George S. Piggot** was routinely suspending small silver balls to water globules, corks, wood, using the electrostatic field from a specially designed Wimshurst machine in a glass container under several atmospheres of pressure to raise the current level. Output voltage was typically 500KV. The field was propagated by a charged sphere. A small curved conducting plate on the floor acted as a ground. He observed unusual patterns of blue dots with filaments over the suspended objects, sometimes with an anomalous 1/2 cm "dark band" on the suspended objects. Piggot states, "It is my firm conviction that that somewhere on the outer confines of our planet there exists a similar contracting belt thru which naught but the gravitational vibrations of the sun penetrate, and these vibrations absolutely annihilate or absorb all other less powerful ones". If the force was Coulombic in nature, objects would be first attracted, and then strongly repelled by the charged metal sphere. After the objects were suspended, Piggot found he could remove the conducting ground plate, and the objects still floated, suspended. The phenomenon of levitation was accompanied by "luminous halos".

In 1925-27, **Albert Einstein** released his scientific "gem", his "zur Einheitlichten Feldtherie", or the Unified Field Theory for Gravitation and Electricity, to the press and the scientific community. It combines electricity, magnetism, and gravitation into a single mathematical expression, showing how High-Voltage/Low Current electricity (Electrogravity) -and conversely Low-Voltage/High-current (magnetogravity) "acceleration-fields" (G-field) could be produced using then-available relatively LOW-technology. Indeed, a very simple technology. The unifying field is the electrical field (because it can produce gravitation and repulsion fields, as well as magnetism). His Crowning work was released with much press write-ups and fanfare, then it was quickly forgotten as if the scientific community and the world had suffered some kind of collective amnesia!

All of the readers of this magazine need no introduction to the pioneering work of American Scientist **Thomas Townsend Brown**, who was playing around with an X-ray tube around the same year as Einstein's Unified Field Theory was released. He filed his first patent for this newly and accidentally discovered "electrogravitational-effect" which causes motion in a high-voltage condensor or capacitor configuration. He was only 17 at that time. The discovery that high-voltage/low amperage electrostatic potentials applied to an object causes motion in the direction of the positive pole, and electrical charges naturally move to the OUTER surface of an enclosed charge-conductor, held strong prospects for what Brown would later name the "space-car", and wrote an article "HOW I CONTROL GRAVITATION". His pioneering work, and demonstration of devices in Hawaii during World War II, drew attention from the department of Naval Intelligence. He was invited to work on "Project-Rainbow" (the Philadelphia Experiment for Electromagnetic Stealth) because of his pioneering work on what was starting to be understood very covertly as a true WARP DRIVE. Experiments with certain new and classified arc-welding apparatus at the Philadelphia Navy Yards to weld armor-plate for battleships was (by use of banks of primitive but powerful avalanche-discharge capacitors) producing anomalous and unexplained effects, such as disappearing tools and other apparatus in the heavily shielded welding chamber. These strange effects were accompanied by a strange "blackout -zone" which, like Piggot's early work, was not optical in nature. TT Brown's devices in his AH Bahnson Labs home movies lift more than their own weight and move inside vacuum chambers in these films. TT Brown later founded NICAP in 1956, which became the most respected UFO data gathering and hard scientific organization in the world, besides the US department of Naval Intelligence itself, and the Foreign Technology Division at Wright-Patterson Air Force base in Ohio.

My background and work

I primarily have a background and degree in computer programming, electronics, most fields of science, Flying Saucer Technology research (almost 30 years worth), Radio/Control fixed and rotary-wing aircraft since 1972. I have been experimenting and working with high-energy and electrogravitic devices and systems since 1987. I built my first small High-Voltage generators starting around this time. I built kits from Information unlimited and elsewhere.

In late January 1990 I built my first working 2-foot flying discs, which were a direct replication of Thomas Townsend Brown's most important representation of his electrogravity-propelled scale-model vehicular concept, from US Patent #2,949,550. In January 1992, I built a 120KV high-voltage/low-current electrostatic generator from an Information Unlimited kit, primarily for force-field propulsion research.

In June 1999, I built a tower and rotor apparatus to complete the experiment, and I powered it with the output from a 100KV generator I built from an Information Unlimited Kit. The results were spectacular, and taught me a great deal about what was involved in producing and maximizing the Biefeld-Brown Electro-gravitational effect. **I suspected from my research, and my experiments, that the basic effect was not due to current-flow and resulting ion-wind. When there was current-flow, the effect is attenuated, power consumption goes up, and thrust goes DOWN.** In late June of 2000, I presented this working TT Brown Electrokinetic Apparatus with larger 1-meter discs at the 2nd Antigravity Conference in Reno, NV, hosted by Jim Cox. A VHS videotape of this working and spectacular presentation at the first part of the conference is available from www.soundphotosynthesis.com

Now that I had mastered producing horizontal thrust, vertical thrust, or antigravity, was the next goal. About this same time, there was buzz all over the Internet about claims of two or three individuals who sounded credible at the time who had successfully replicated the many multi-layered "gravity-warp capacitor" or "electric rocket". Oddly, these claims could not be verified, and the individuals making the claims disappeared back into the woodwork. Such actions are bizarre and hinder the progress of true science, which is undergoing a shift in paradigms right now, if not a change in dogma.

I spent months die-cutting hundreds to thousands of tinfoil and aluminum-foil circular-notched conductor plates and wax paper and mylar rings. I did some initial testing with a Tin and wax-paper 400-layer gravity warp-capacitor heap, according to plans I had acquired from H & A Industries in 1992, and what was on Bill Beatty's amateur science site. No one else has come forward with positive results on this tedious and time-consuming device. So much work for so little effect! And, if you short out the stack with too much power, you must tediously and laboriously search thru hundreds of layers to find the dielectric layers with the telltale carbonized holes. The Electric rocket has been recently successfully replicated and tested in hard vacuum and patented recently by Hector Serrano. The Serrano effect is identical to the so-called Biefeld-Brown Electrogravitational effect. They are one in the same thing. I may dust off my completed 400-layer grav-cap, but I hardly find it worth the time and effort, because of my recent work starting in early October 2001.

The Lifter and The Evolution to Beamship Model Flying Craft

Although I had attempted a few small "Hagen" patent-type antigravity (VTOL) models in the early 90s, I found their performance poor at best and their power consumption high. In late summer, 2001, someone, I forget who, on the JLN's lab list of researchers and anomalous science-experiment and technology enthusiasts ran across a website owned by Transdimensional Technologies, of Huntsville, Alabama (famous for NASA research facilities, the late Dr. Rolf Schaffranke, author of the important ETHER TECHNOLOGY, under the pseudonym "Rho Sigma", and Dr. Tom Bearden) had produced a hovering device. From my previous work, I recognized it immediately as TT Brown's Electrokinetic Apparatus that I had successfully replicated and demonstrated before a live audience years earlier. I noticed the capacitors were made from Aluminum FOIL, not the thin-but-heavy Aluminum sheet stock from Home Depot that I had been using for years, (I had assumed that to make my 3-foot discs hover and ascend vertically, I would have to use voltages in the hundreds of kilovolt range, and generate high x-ray, UV, and possibly gamma-ray emissions as a by-product, in other words, a typical flying saucer with all the associated radiological effects that have been documented for over half a century) so they could lift their own weight. The result matches almost exactly the simplest graphical representations of TT Brown's patent from 1960, and De Seversky's Ionocraft patent from 1964, which was a thin foil cathode plate with a thin anode wire separated from the cathode by stand-off insulator posts. I was eager to reproduce these devices (I don't know how I overlooked this simple solution, it was all sitting in those old 1960s Brown and De Seversky patents I have studied for 15 years previously) and many people around the world, especially the webmaster of the JLN Lab's site French researcher Jean-Louis Naudin, who began replicating many different types of larger and more sophisticated devices, some of which resembled model spacecraft, and began amassing tables of very useful data, that researchers could use as basic guidelines to follow. I replicated the first hovering device, the "Lifter" (so-called by Transdimensional Technologies) as a 1-foot triangle, with 2-inch foil cathode and #42 enameled copper magnet wire. To energize it I used a commercial power supply from Gamma High-Voltage Research that I had acquired from Ebay some years ago. It was perfect for antigravity research, having full metering, and variable voltage from 0 to 40KV, and current limiting from 0 to 1.5 milli Amperes of current. The heavy 1-meter discs of the Electrokinetic Apparatus were too heavy and the rotor-friction to great for this low-powered device (60 Watts, maximum), but for the lifter, it proved ideal.

My first "lifter" antigravity device worked, but its performance was less than ideal. It had to be stripped of its lower balsa-wood frame and some of its foil before it would degravitate (counterbary), and it "maxed-out" the current-limited power supply at 33KV I 1.5mA, for a stable hover (actually this is an upward flight configuration, because the device is tethered to the lab table with 3 sewing threads). That is 49 Watts. The concept of a hovering TT Brown Electrokinetic Apparatus had been proven to my satisfaction, however, and I initiated more research into past works and patents to raise efficiency to workable levels. The performance was slightly better than my early 1990s "wire-grid" type devices. I found this slightly encouraging.

After a couple months reading and research (why re-invent the wheel, its all been done before), I started to replicate larger models in February and March 2002, but kept coming up against a size-barrier with the Multi-cellular (grid) approach that many researchers had assumed would raise thrust, and efficiency. This approach obviously did neither, as no one seemed to be able to produce hovering devices above a certain size, the current consumed (adding to total wattage consumed) was prohibitive with the low-powered (still high-voltage, low-current) devices that most of the mostly amateur researchers were using. Researchers around the world started to replicate different versions of the basic lifter 1 (an 6 to 12-inch equilateral triangle). The lifters are always tethered to the testing surface with 3 strings to keep them from going dangerously unstable and possibly short-circuit when they reach the limit of the umbilical supplying power to the device.

From my previous Biefeld-Brown effect replications years earlier, and from carefully reading Brown's EK Apparatus patent, I knew that increasing the diameter of the wire would reduce leakage current created by coronal discharge, mostly coming from the forward electrode, which in the 2 and 3-foot saucers consisted of an arc of copper tubing in the front quadrant of the saucer, or disc. Corona robs power (amperage) from the disc that otherwise would be used to "propel" the disc. Increasing the diameter of the copper tubing, as per Brown's patent if the effect was due primarily to ion-wind, more current and current flow between the electrodes would be desired to effect more air movement. But this is not what I saw in the saucers. **There was apparently another, far more powerful but subtle force effecting silent propulsion of the saucers that had nothing to do with charge-transfer and ion-momentum.**

In February of this year, I undertook an effort to replicate and improve performance and reduce power consumption of the lifter device, based on data from my electrogravitic work of years past. I started by using thicker diameter enameled copper magnet wire, #35 to #30 diameters. I first built a 1-foot equilateral triangular basic "Lifter-1", weighing only 3.5 grams. On March 16th, I built a lifter with the thicker #35 enameled copper wire.

I made the three sides 1-foot long and exactly 2-inches high. After experimentation, I found the optimum spark gap for my High-Voltage power supply (Gamma High Voltage Research 40KV with current limiting to 1.5mA). The small silver-colored device leapt off the test table and pulled violently against its anchor strings to a distance of about a foot. This seemed like a great deal of force for such low power. The large discs of my TT Brown EK apparatus required a good deal higher voltage to initiate motion in the direction of the anode. The device consumed 26KV I 0.56mA DC, which calculates out to 14.56 Watts. I was getting more excited, because this was the best efficiency seen of any result yet posted.

On March 19th, I tested 2 lifters glued together in a "diamond" shaped configuration.

This 2-foot device weighed 6.0 grams, with the same #35 wire and a 2 and 5/8" air gap. It took 25KV to nullify the weight of the device, and it achieved a stable hover at 35KV I 0.8mA. That is 28 Watts. This is about what I had initially expected, double the power for double the Watts. Still, this was far less overall power going into the device to achieve a stable hover than my first primitive and radically shorn and trimmed device. After lift off to the extent of the anchors, I found I could reduce power slightly and maintain a stable hover. On march 22nd at 3:49 pm I got the diamond lifter to achieve a stable hover with a 2 and 5/8" air gap at 29.5 KV I 0.32mA. This was only 9 Watts! This was unheard-of efficiency. I was further encouraged to build and test larger hovering devices to see how large I could get them with my low-powered commercial power supply.

I then built a "lifter-2", which consists of three 1-foot triangular capacitor cells taped together. It weighs 11.4 grams. March 30th at 3:22 pm, the device achieved a stable hover at 38KV I 0.57mA for 19.76 Watts total power. The larger device was more energy efficient than a device 1/3 the size. I wanted to see how far this could go, so I added three more lifter cells to make a 6-cell device, 3 feet on each of its three sides. I was eager to check the performance of this fairly large device. This was the diameter of my horizontally propelled TT Brown Discs.

This device weighed 21.6 grams. I kept the spark gap the same distance on this device. However this device failed to achieve counterbary (lift). It just sat on the test table, filling the air with the smell of ozone and making a sizzling sound (corona noise). I noticed that the current maxed-out on the power supply at a fairly low voltage and would not go any higher.

I concluded in my disappointment that all that wire from all the inter-connections to the cells was causing corona leakage and robbing current, which otherwise would be used by the device for propulsion.

The idea then hit me that perhaps I could make a device with the same outer diameter as the 3-foot device, but have greater efficiency because of a much shorter length of wire. I built basically a 3-foot (1-meter) version of the first 1-foot device. This device weighed 16 grams. It lifted off the table with amazing force and hovered stably with I 52mA 30KV which is 15.6 Watts. Not only had I achieved a larger-size device, but far better power efficiency for a much larger and heavier device. I was overjoyed! I saw that I had a great deal of lifting force to spare. I had not even come near the limit of my power supply. I added extra bracing at the corners and extra balsa and a triangular paper "payload -tray" in the center of the device, supported by three 1/16"x1/16-inch balsa stock. The extra bracing and payload area added approximately 2 more grams. With a 5 gram payload, the device consumed 39.9 KV I 0.99mA, for total power consumption of 39.5 Watts. I was really encouraged at that point, because I knew that these results were unheard-of, in terms of energy efficiency. I had solved the problem of decreasing efficiency by dispensing with a "grid-based" device. Increasing the area of the capacitor plate was one of the factors that increased performance and efficiency, lessening the input power requirements with increasing size. Now the Biefeld-Brown effect could be properly studied, now that most of the ion-flux had been eliminated, resulting conservation of energy by the device, and resulting in greatly increased propulsive force.

Since I now knew the limit of payload for the device at the power level I was using, I added a balsa framework that approximated a central cabin area, and three small styro-foam spheres on the center of the straight sides on short lengths of balsa. The device no longer looked like a test device, but now looked like a scale model spacecraft. I remembered the Edouard "Billy" Meier UFO contact case, and knew that all his original photographs and movie footage of extraterrestrial spaceships the extraterrestrials themselves called "beamships" (there are several styles and variations, all with different specific functions and capabilities, some manned, some remote-controlled "telemeter discs" that had a tri-hemispherical undercarriage that I knew from past research were propulsion condensors) and that the original un-tampered photos all passed rigorous analysis using the latest and most sophisticated computer and other equipment, case detractors not withstanding. Also the spiritual messages of these genetic brothers of Man and their accounting of humankind's history and origins from far across space rang true and struck a chord with me.

I decided to name this new 1-meter model spacecraft Beamship Variation I. The three sides of the device performed the same function on this device that the three spherical or hemispherical capacitors often seen on the underside of full-size "beamships" (Daylight-disc-type UFOs), which illustrates a similar if not identical propulsion methodology to full-size 3 to 7 meter and larger "off-Earth-built" aero-spacecraft. Clearly the propulsion methodologies were exactly the same in the model as in the full-size flight device.

I immediately built a 4-foot diameter model with a full cabin framework and internal payload area and achieved even greater performance and efficiency. I was ecstatic. This 4-foot device I dubbed Beamship Variation II. I received a suggestion from Mr. Tim Ventura of American Antigravity that performance could be increased by using small diameter stainless-steel wire. It seemed unlikely to me that smaller diameter wire would increase performance, it contradicted Brown's patent, and my own past research with large electrogravitic discs. But Stainless steel has a high number of free electrons in the outer valence atomic shells (electron orbits).

So I obtained some #40 stainless locally and the results confirmed Mr. Ventura's suggestion. Corona noise was heard at a much higher power level, and was greatly attenuated in volume. Leakage current was less, and the two Beamships now had more thrust with less power input. They even carried more payload at less power input. Variation II weighs 21 grams and loft a payload of 6 grams at 40KV I 1mA for 40 Watts total power. Again, this was unheard-of efficiency. The anode wires sang a strange harmony as the Beamships floated in the air, stably at any altitude, from floor to ceiling, without any fuel or visible means of support. This was very Beamship-like.

I thought that now since corona discharge on the anode wire was less, I could decrease the spark-gap distance without creating a spark (which kills lift). Thrust seemed initially to increase, but efficiency went down because there was current-flow now, and current consumption went way up. The supply would now max-out at 37KV I 1.5mA and would not increase because of the current limiting. The Beamships now were noisy, as the foils chattered loudly because of all the ion-wind that was now rushing downward along and past the foils. I used a concert fog machine to observe the ion-flux vector, and filmed it digitally with my Logitech web-cam, and with VHS analog video.

Analysis of the fog -tests showed a circular vortex of air surrounding the anode wire that flared out into a downwash of air below the Beamship. I was disappointed, because I thought then that the thrust action of the device was due to simple ion-transfer. A useful-enough effect, but of questionable use in the vacuum of space without an ionizing medium.

Beamship Variation III

I reasoned I had just about enough power in the supply to build and fly a 6-foot (2-meters) Beamship. Since the balsa came in 3-foot lengths, this was simple. As with all the lifter devices and the more evolved and efficient Beamship-series model aircraft, construction techniques are extremely simple and require little skill to assemble. Weight of the Beamship Variation III is 42 grams, with 6-feet of length on its 3 sides. Height of the foils was still 2". Full frame and cabin, with Searl "IGV"-type landing legs, to support the weight of this heavy and very large device. I set the spark gap at 2 and 1/2 inches. At 12:15pm EDT, May 12th, 2002 the Beamship was weightless at 32KV with current maxed-out at 1.5mA.

The device barely lifted off, and "hopped", across the floor once or twice at full power. It had the same loud rattling of the foils due to the terrific downwash of electrified air. I needed to raise the power level. I increased the distance of the spark gap to 2 and 3/4". Now the Beamship took off straight up with power to spare, as if it was one of the smaller craft. Beamship Variation III is weightless at 30KV I 0.85mA (25.5 Watts), and airborne into a stable hover at 35KV I 1.35mA. That is only 47.25 Watts. It can carry a payload of 5 grams, or 5 grams worth of additional framework and structure, to the limit of the power supply, which is 60 Watts (40KV I 1.5mA).

The 42-gram, six-foot model aero-spacecraft only consumes 47.25 Watts at hover, but my first small and trimmed device ate up 49 Watts! Clearly, using the single-cell Beamship methodology had a huge advantage over the "multi-cellular" design that other researchers had built and tested, seemingly reaching an impasse in terms of size and efficiency, which my large single-cell Beamship technique had seemingly solved. In early April my 1-meter Beamship, weighing 22 grams including 5-gram payload, consumed 39.6 Watts. So the 42-gram, 6-foot Beamship used only 7.65 Watts more total input power at stable hover that the 1-meter Beamship. Power-to-weight ratio for the 2-meter Beamship V. III works out to 1.125 Watts to lift 1 gram stably of scale model electric spacecraft. With little to no ion wind, the Beamship had plenty of upward force and achieved stable counterbary at greater efficiency than I had ever heard or read about. Also, I was not aware of any devices in scientific history that has achieved this type of counterbary for this little input power and this colossal size. I performed additional fog-tests with two red semiconductor-emitted laser beams in the plane of one side of the device, one above the wire, one below the foil. The Beamship without all the ion-wind was nearly silent again, except for "singing" and softly "thrumming" anode wires. These laser-beam tests further confirmed the marked absence of ion-wind with a larger spark gap.

At 1.125 Watts-per gram at 57KV I 1.4mA (78.8 Watts) would lift 89.775 grams worth of electric spacecraft. So not only is the larger size in a single cell far more efficient that the "grid" design, in thrust and power consumption, but the reduction in current from increasing the spark gap raised power level to the device, while dropping power consumption of the device. My initial suspicion of ion-wind producing most of the thrust in the Biefeld-Brown effect had been disproven also because of the great weight of the device. I never would have discovered this important fact if I had stayed with smaller devices, trying to raise their efficiency. And I never would have discovered the efficacy of the Biefeld-Brown effect if I had stayed with the multi-cellular "lifter" methodology. One of the factors that raises the level of propulsive force (if "propulsion" is the right word) is increasing the area of the plate, according to TT Brown's patents. So the larger size single-cell capacitor's ability to reduce power consumption and effect greater propulsive force and upward acceleration, was easily explained by the Biefeld-Brown Effect. Brown had been vindicated. My gut feeling had seemingly been confirmed: this was our first warp-drive (reaction-less drive).

My experiments had yielded greater efficiency, and greater size and weight of VTOL hovering models than any that I had ever heard or read about. I still am having difficulty taking in these facts; and it is very awe-inspiring to see such a large device de-gravitate and hover stably at any altitude, from floor to ceiling.

Next for me is a higher-powered supply (60KV), moving up to a three-meter Beamship Variation IV, improvements to the cathode such as a thin, symmetrical airfoil shape, as Brown suggests in his patents, tungsten wire, and then carbon-wire for the anode, and full heat-shrink coverings on the frames, running lights, onboard lasers, onboard digital/proportional Radio/Control, and now that we know the power requirements, and have a good handle on efficiency, onboard power generation. I have already begun designing with my associates our own custom-made outboard and inboard battery-powered power supplies, and finally will cut the power umbilical to the model electric spacecraft permanently, and Beamship technology advances further. If the on/off duty cycle is pulsed at a low frequency, power input can be reduced by two-thirds, at least. Experiments conducted by Jean-Louis Naudin last fall (2001) confirm this phenomenon, suggested by Brown and De Seversky in their patents. Clearly, onboard power can easily be effected, using modern miniaturization and circuitry. Pitch and roll vector control can be achieved by electrically isolating the anode wires on the three sides of the ship, and varying pulses to these three wires. Yaw control can be achieved by simply installing a horizontal-double sided capacitor inside the ship near one corner. Simple full 4-channel flight control is thus achieved.

The Beamship series aircraft are fascinating research and entertainment devices (see cover page), and are the vanguard of a whole new generation of radio/controlled antigravity model aircraft with no moving parts and dead silent propulsion. But they are more than that. The Beamships, if allowed, could probably rise up at any speed thru the atmosphere, right up to near-Earth-orbit, and probably keep on going out into limitless space. No need to achieve ballistic escape velocities of miles-per-second. This is non-ballistic flight. They even have a certain amount of wind resistance outdoors and indoors because the electrical field causes air to flow AROUND the model flying craft, not into it. This is such a safer, environmentally cleaner, vibration and nearly silent and more pleasant method of aero- space travel than carrying tons of explosive reaction mass, which can and does explode. No more use of heat energy to effect transportation.

The 21st century has begun in earnest!

Beamship series aircraft are available for sale for research and hobby/entertainment use right now through the American Antigravity website: www.americanantigravity.com. Look for the Applied Electrogravitics antigravity technology website late spring, 2002. You can contact me, Russell Anderson for details on pricing, and new and improved variations, and power supplies for outboard and onboard drive, which are currently in design stages.

Editor's note: More ideas on development of T.T. Brown's patents are on our web site: http://www.faraday.ru. Read about T-capacitor!

Data Table 1

Antigravity device	Weight of device	Wire type	Voltage/current	Total Watts	Payload	Payload/power
1-foot "Flyer-1"	3.2 grams	#42 enameled copper	33KV I 1.5mA	49	None	——
1-foot "lifter-1"	3.5 grams	#35 enameled copper	26KV I 0.56mA	14.56	None	——
2-foot "diamond-lifter"	6.0 grams	#35 enameled copper	29.5KV I 0.32mA	9	None	——
2-foot, 3-cell "lifter-2"	11.4 grams	#35 enameled copper	38KV I 0.57mA	19.76	None	——
3-foot, single-cell "Beamship Variation I"	16 grams	#35 enameled copper	30KV I 0.52mA	15.6	None	——
Beamship Variation I-fully-rigged	18.5 grams	#35 enameled copper	——	39.5	5 grams	39.9KV I 0.99mA
4-foot "Beamship Variation II"	21 grams	#40 stainless-steel	——	40	6 grams	40KV I 1mA
6-foot "Beamship Variation III"	42 grams	#40 stainless-steel	35KV I 1.35mA	47.25	None	——

References

1. Ether Technology, by Rho Sigma,
2. Lost Science, by Gerry Vassilatos,
3. The Philadelphia Experiment, by William Moore,
4. High Energy Electrostatic Research Vol. 1, Antigravity and UFOs, by Raymond A. Nelli, Homemade Lightning, by R.A. Ford,
5. Antigravity – the Dream Made Reality, by John Searl, The Law of the Squares Book 4, by John Searl,
6. The Antigravity Handbook, compiled by D.H. Childress,
7. The Coming Energy Revolution, by Jeanne Manning,
8. Agnew H. Bahnson Labs home movies (1957-60), JLN labs website, Bill Beatty's "weird-science" website, American Antigravity website (www.amercanantigravity.com).

Patent references

1. A.H. Bahnson, Jr. Electrical Thrust Producing Device, USP # 2,958.790, filed May 12,1958, granted Nov. 1, 1960.
2. Marcel Jean-Joseph Pages (France), # 1,253,902 Petit-Viton, filed Jan 5, 1960, granted January 9th, 1961
3. G.E. Hagen, Flying Apparatus, #3,120,363, filed Sept. 11th, 1958, granted Feb. 4th, 1964
4. T.T. Brown, Electrokinetic Apparatus, #2,949,550, filed July 3rd, 1957, granted Aug. 16th, 1960
5. T.T. Brown, Electrokinetic Generator, #3,022,430, filed July 3rd, 1957, granted Feb. 20th, 1962
6. A.P. De Seversky, Ionocraft, # 3,130,945, filed Aug. 31st, 1959, granted April 28th, 1964
7. V. Gradecek, Electric Aerospace Propulsion System, # 3,177,654 filed Sept. 26th 1961, granted April 13th, 1965

SmartPAK Technology™

invention by William Alek



the world's first commercial all solid-state system that provides a "standard" platform for experimenters, researchers, and developers to do energy-related practical applications, experiments, and perform exploration of highly efficient alternate energy system

The theory of operation is based on the amount of energy that is required to magnetize and de-magnetize ferromagnetic materials utilizing a core/coil/magnet assembly. It has been discovered that it takes MORE energy to magnetize a suitable core assembly than to de-magnetize it. The SmartPAK system is designed to measure and collect the difference, and store the excess energy for later use.

The SmartPAK device is controlled by a 68HC908GP32 micrcontroller programmed to measure input/output voltages and currents, calculate COP, and contains software algorithms for a complete "turn-key" power management system. The device features a "standard" user interface, which allows the user to design their own custom core/coil/magnet "head assemblies", and immediately test and display in real-time its' performance.



William Alek
President and CEO of INTALEK, INC

3506-43rd. Place
Highland, Indiana 46322-3129
e-mail: wsalek@intalek.com

Correspondence Address: POBox 37,
St.Petersburg, 193024, Russia
Phone: 7-812-380-6564,
net@faraday.ru, www.faraday.ru

Commercial Antigravity

Tim Ventura

tventura6@attbi.com

Introduction

Let me begin by posing a simple question that I would like the reader to keep in mind throughout this article: How far away is commercial antigravity? I'm not talking about a laboratory experiment where a giant magnet is used to levitate a frog, or secret UFO experiments that the government isn't sharing with the business world, but a real, viable antigravity solution to what I consider to be the most pressing issue facing the world today – transportation.

Who can answer a question like that? How far away is commercial antigravity? The author has read numerous scientific texts on the subject, and is familiar enough with contemporary theories of gravity, antigravity, and electromagnetism to suggest that most scientists believe that commercial antigravity is at least 100 years away from existence. But the author believes that most scientists are wrong.

Defining terms

Any article about antigravity would not be complete without properly defining the terms to be used. In this article, antigravity is not used in the strict sense of the word. The author's intent is to discuss a method of propulsion, which for all intents and purposes can be considered antigravity, and may include antigravity – but also may include several other forms of similar propulsion. The reasoning behind this is that experience has shown that the majority of people in the world don't care how something works – they care what it can do for them. This article is about the effect of Antigravity – not the cause.

Real Antigravity would consist of an apparatus used to either reduce the apparent mass of an object or reduce the effects of gravitational attraction between the Earth and an object. An example of an apparatus that may in fact do this is the Podkletnov superconductor apparatus currently being tested by NASA.

This Podkletnov device essentially consists of a spinning superconductor that self-levitates above a pool of liquid nitrogen and supposedly creates a "beam" or "shaft" of antigravity (or reduced gravity) directly above it as it operates. The levitation of the superconductor itself is not antigravity – it is a well-known side effect of ceramic-superconductors called the "Meissner Effect". The Meissner effect is simply a side effect of the superconductor's interaction with the Earth's magnetic field, and is easily explained by physics.

Podkletnov claims that when he worked with a team of researchers investigating superconductors in Russia around 1991, the smoke from the tobacco pipe of a fellow researcher began to climb steeply in a column directly above the superconductor. The researchers began to think that they were on to something, and Podkletnov subsequently performed several follow-up experiments that led him to the conclusion that the levitating superconductor produced a shielding effect between the Earth and anything positioned directly above the superconductor. He reasoned that gravitational shielding would provide a "column" of reduced gravity above the superconductor that should extend up and away from the Earth indefinitely. Podkletnov calculated that with a rapidly spinning levitating superconductor he had achieved a 2% loss in weight for anything directly over the superconductor.

Podkletnov's research is interesting and compelling, and it would fall into the category of "real" antigravity – but I am writing about Podklentov's type of research as well as enormous amount of research and theory available on electromagnetic propulsion systems. These can be considered "effective" antigravity.

The Harrier jet fighter can swivel its engine exhaust-nossels to create vertical lift, which resembles antigravity in that it is VTOL takeoff. However, the Harrier does not use effective antigravity because it has all of the functionality and side effects of an aircraft. A helium blimp would be a closer example to "effective" antigravity, but it too is not – because it works on basic aerodynamic principles.

Aerodynamics is not effectively antigravity – aerodynamics is instead expensive, difficult to manufacture, prone to explosive failure, and highly unreliable. This is not to suggest that a jet aircraft is unreliable, because it has a variety of backup systems, but that the technology itself is unreliable in that a jet is adversely effected by the medium that it uses to propel itself. Air pressure, humidity, temperature, and strong winds all cause a degree of unreliability. In addition, turbine engines stretch the limit of what mechanical engineering can achieve – which is why they are prone to break if even something as small as a bird gets sucked in during flight.

Antigravity is not about moving the air around — it is about a medium-agnostic means of air transportation that produces vertical and/or directional lift without relying on air-pressure like a wing or blimp. Antigravity is an electromagnetic or electrogravitic system for reducing the weight of an apparatus to allow it to lift more easily. Antigravity is pushing a button and having your vehicle take off without runways, noisy engines, minimum flight-speeds, propellers, or any of the other drawbacks that limit conventional aircraft from achieving popularity similar to what an automobile might have.

The author's definition of Antigravity for the purposes of this article is confined to electromagnetic or electrogravitic devices that reduce the weight of an object to enable it to take off without conventional thrust-producing apparatus. This definition might also fit many of the classical characteristics known at one time as “the electric spacecraft”.

1. Business Analysis versus Scientific Analysis

The author disagrees with the majority of scientists as to when commercial antigravity will become possible for some very basic and obvious reasons. To begin with, the majority of credentialed physics-related scientists come from a theoretical school of thought, which tends to limit their world-view to only contain those things that are currently or potentially explained by theory. The author, however, comes from an experimental school of thought that seeks to capitalize on existing observational data without the rigorous need to explain every last detail of its functionality. The author is an engineer, not a scientist – and engineers don’t need to totally understand how something works in order to make it better.

This difference between the engineering point of view and the physicists is also different in the manner in which they seek out observational data. A physicist looks towards naturally observable data, and in the event that none exists they look towards current theories to explain potential future observations. The engineer is more open to ideas that are less rigorously tested from the perspective of scientific method, but are currently observed as potential solutions to real-world problems.

2. Potential Technologies Overivew

Phycists currently tend to dismiss the entire concept of Electrogravity, and the reasoning behind their logic is very sound. To begin with, Electrogravity is not observable in nature. In addition, many of the claims by those persons who submit Electrogravity and antigravity devices for public review are faked, exaggerated, or just plain wrong.

Physicists are responsible for maintaining a working body of theoretical knowledge, and if they were to admit results such as Schnurer’s without skeptical scrutiny it would undermine the very fabric of technology itself. If the Podekletnov results were to be accepted as fact at face value without rigorous prrof, imagine the amount of money that would be wasted in attempts to build enormous Antigravity vehicles based on this theory.

In the middle of the spectrum lies the concept of Maglev, which is mentioned here only for the purpose of specifying that Maglev is not commercial antigravity. It has been mistakenly thought of as antigravity by many because it utilizes a magnetically-levitated train to improve the velocity of the train and reduce transit time between stops. In reality, Maglev is not really a vehicle at all.

The definition of a vehicle would be a device that transports itself as well as its passengers and cargo between two points. This is why an automobile is considered a vehicle but an escalator or elevator is not – the automobile transports its entire propulsive apparatus to another location, but an escalator or elevator does not move – it merely repositions its cargo between points. The Maglev train is not really a vehicle at all – it is actually a very long electromagnetic armature that transports people and cargo between its ends at high speed. While it may serve a commercial need, it is not to be confused with Antigravity.

On the opposite end of the spectrum is the author of this article – who has built and successfully tested over 30 electromagnetic “Lifters” at the time of this writing. The Lifter is a device based on research by Transdimensional Technologies and related to research by Thomas Townsend Brown that demonstrates an antigravity effect when a High-voltage DC current is applied to it.

Currently, the exact method of propulsion for the Lifter is being debated. It is thought to be one of two things – either an effective form of “ion-wind” propulsion, or else a form of field-effect propulsion based on an as-yet unknown force. While the debate about the exact nature of this propulsion is important with regard to future research, in reality it does not change the observational data that demonstrate that this technology works perfectly, consistently, and reliably.

The Lifter design was demonstrated by the author in a continuous mode of operation for over 7 hours straight on Sunday, April 21st, 2002, at the Seattle Center “EarthDay and Renewable Energy Exhibition”. During this seven hour period of time, the author’s Lifter hovered at a tethered height of 12 inches from the surface of the table, powered by a 30 watt load from a simple computer monitor.

This article is not meant to get into the details of methods of antigravity, only to suggest that it already exists in the form of electromagnetic propulsion systems if nothing else. The author is confident that in time physicists will find a theoretical reason for why the Lifter operates as it does, but for the time being the fact of its operation overshadows the method of its operation.

3. Market Needs

Commercial Antigravity doesn’t require a 2% loss in weight to operate – it will require something akin to a 200% loss in weight. A commercial antigravity device will have to demonstrate exceptional performance to gain market acceptance, but not for the reasons that might immediately come to mind.

One might believe that skepticism from the scientific community would prevent antigravity technology from gaining the scientific acceptance needed to become a commercially accepted engineering discipline. The long term view, however, shows that this is not the case – engineering and market forces drive innovation, and formal science plays a supporting role in explaining and quantifying the innovations that engineers have already commercially qualified as valid.

The real roadblock to success for commercial antigravity is market acceptance. The author's demonstration of the Lifter technology at the Renewable Energy Exhibition helped him to realize that the vast majority of consumers have no idea what antigravity technology could be used for, much less what they themselves could use it for. The same thinking was apparent at the dawn of the age of personal computing, when the idea of having a computer in the home was a completely foreign concept.

So in brief, a market does not exist for antigravity technology, which is why inventors working with this technology have been unable to find appreciable support for their work. Many inventors look at this technology and ask, "how could the public not understand how valuable a technology like this is?" – but that isn't the problem. The problem is that most innovators with an interest in antigravity are so closely tied to the science behind the technology that they fail to review and address the business needs that drive the market acceptance of a new technology. In other words, people don't buy antigravity – they buy solutions. People don't buy cars to simply have a car – they buy cars because people need transportation needs that they have to fulfill. People don't buy computers because they want to have a computer – they buy computers because they want to share and process information and communications.

Marketing Requirements

How will antigravity technology gain the market acceptance to become a commercially viable technology? There are a variety of ways in that antigravity technologies will become commercially viable, but only after antigravity is no longer sold as antigravity – it needs to be sold as a personal or business solution.

The solutions that antigravity technologies are best prepared to provide at the moment are in the realm of transportation technology. This includes moving people and cargo to destinations in a similar manner to conventional transportation technologies such as aircraft or automobiles.

With regard to providing transportation solutions, antigravity has the ability to incorporate the best features of both contemporary automotive and aerospace technologies into a single technology that will serve point-to-point transportation needs better than either of the two aforementioned technologies could by itself.

For a moment, assume that a person wants to travel from Los Angeles to New York in a short period of time. Currently, the most convenient method of transportation to accomplish this would require the person to take an automobile to the airport, and from there take an aircraft from the Los Angeles airport to the New York airport. After departing at the New York airport, the passenger must then take another vehicle to their intended destination.

Commercial antigravity technology could serve a dual-purpose short and long-range transportation role, taking on the aspects of both ground transport as well as air transport.

Product Delivery Requirements

In order to deliver commercial antigravity as a viable solution to business needs, a variety of work will need to be completed on the various component systems of this technology to turn it from what is currently a "proof of concept" into a commercial reality.

Let us assume for a moment that we have developed a working device based on Antigravity or some method of Field-Effect Propulsion. While this is the critical stepping stone to success, this is by no means the end al be all of the development cycle.

To begin with, the technology must be perfected to the point of being both economical and reliable. As it stands now, the market already has technologies in place that fulfill some or all of the requirements for the technology that Antigravity is being developed to replace. In order to serve as an effective replacement for these technologies, antigravity technology must then demonstrate that it both costs less in terms of operation and manufacture, as well as being more reliable than conventional air-transportation solutions.

I mention reliability in light of the recent negative media attention surrounding several recent commercial airline crashes. From a marketing perspective, air-travel disasters provide a great deal of negative publicity for the airline industry. Since the airline industry has a mostly successful track record of delivering passengers and cargo, people are for the most part willing to forgive the occasional air-disaster. However, with a new technology such as antigravity-based air-transport, there is not a long enough track record to permit public acceptance of air-disasters. One substantial disaster in the early days of antigravity could serve to forever damage the credibility of this new technology.

With regard to being economical, any type of antigravity system that intends to surpass existing methods of air-transport must be able to do so at a less-expensive rate to own and operate, and must have a vehicular lifespan at the very least similar to conventional air-transport devices. This would allow the total cost of ownership (TCO) to be less for an antigravity vehicle than it would otherwise be for a conventional craft.

There is one caveat to acceptance of antigravity technology as compared to conventional aircraft, which is simply that if antigravity vehicles are able to operate in an environment or manner that precludes conventional aircraft, then they should be able to gain a market niche without immediately having to surpass conventional aircraft in the area of TCO.

Assuming that we can develop a propulsion system that is both more reliable and less expensive to operate for the transportation of passengers and cargo, we then have to build up the skeleton of a vehicle compatible with this form of propulsion around the actual propulsion system.

For instance, a conventional aircraft has pitch, yaw, and several other flight controls, but for an antigravity vehicle there is a high likelihood that some or all of these controls will not be required, thereby changing the dynamic of flight associated with the craft. This will require new methods of pilot certification and flight-qualification, as well as requiring a control-philosophy to be created surrounding how the craft will operate.

I use the phrase "control-philosophy" instead of simply "control layout" because one of my assumptions about antigravity propulsion systems is that they will allow more flexibility in the design process for engineers to determine how the craft "should" fly, as opposed to an aircraft or helicopter, in which the components determining speed and handling are based primarily on an interaction between the design of the craft and the atmosphere.

In brief, an antigravity cargo-transport may have very different needs for flight than perhaps a lightweight passenger vehicle would, although there would also need to be a consistency between the control-systems of these devices to reduce the need for extra pilot training and competency testing.

Therefore, it should be apparent from the last few paragraphs that not only are there several propulsion-system related challenges involved with developing a commercial antigravity device, but there are also several challenges in the design, training, support aspects of this technology that also factor into the requirements to be complete before a complete product can be delivered.

Conclusion

At the beginning of this treatise, I posed the simple question of **"how far away is commercial antigravity"**. The reader, I expect, probably interpreted that question in terms of time, which is the usual measurement of questioning when new technologies will become part of our lives.

However, as I have attempted to demonstrate throughout this article, **the time component is much less important to the development process than is the distance component – that is, how far away from commercial antigravity we are.** When I use the word distance, I mean specifically what tasks must be completed in order for antigravity to go from being a proof-of-concept approach to a new form of propulsion-system to being a completed vehicle ready for manufacture.

I have attempted not to address the legal implications of antigravity technology with regard to certification for general or specific use – my thought on this is that the discussion of legal ramifications of antigravity is best left for another time. This is due primarily to the size and scope of that discussion, which is beyond what I am attempting to analyze in this article.

So, in finale, how far away from commercial antigravity we are depends not so much on time as on the rate at which we can perform the work required to provide the underpinnings on top of which the technology can be built. This seems important to me, as it underscores how close we appear to be to a working method of antigravity propulsion, and how we might consider focusing resources and goals to achieve the realization of this common dream that we share.

EDITORIAL: PERPETUAL MOBILE OF 1902

There is one more interesting example of perpetual mobile, which was described in the collected articles [1]. The motor shown in Fig.1 was invented in 1902. The vessels *b, c, d* and *e* are mounted on a shaft *a*, and have one side *f* tangential to the shaft, and the other side radial. Compressed air is forced into each vessel through the valves *p*. It is stated that under "the action of the internal pressure of the vessels, and after a slight impulse has been given to same, in the direction of the arrow, the whole apparatus will begin to move and continue to do so without ever stopping, the velocity corresponding to the pressure established within the vessels".

Really simple... Let's try to examine it.



Fig.1

Reference

R.A. Ford. The Perpetual Motion Mystery. A Continuing Quest, 1987 Lindsay Publications, Inc., Bradley, IL 60915

Action without Reaction

New Gravidynamic Paradox

Yu. N. Ivanov
Academician of Russian Academy
of Natural Sciences

Saikina, 11/2, app.4, Moscow, Russia
Tel: (095) 277-33-76/276-50-39
mirit@narod.ru
http://www.mirit.org

Editorial: Yu.N. Ivanov discovered a new unusual physical phenomenon that is a gravidynamic paradox. The sense of the paradox is the existence of the situation, which is not forbidden by physical laws and which allows any man (even a child) easily hold suspended or carry things with 100kg or more weight by means of some simple device. This phenomenon is just a part of the significant applied topic and a demonstration of the possibility to cancel weight characteristics of any material object. Per se it is a work on the obtaining of the methods to eliminate aircrafts weight.

We can use only resistant things as a support!

Galilee-Newton's Laws are in the basis of classical mechanics. Thought concerned fundamental, these laws do not explain the main thing, i.e. the internal processual essence of the phenomena, described by them. There is another scientific line – the quantum mechanics, which tries to discover the essence of deep processes. There is no connection between these lines, therefore they as if exist independently. There are also long-time conversations about necessity to combine the quantum and the classical approaches. We suppose, that practically the combining has already happened, since thanks to rhythmodynamics, there appeared phase, frequency and velocity of light in formulae of classical mechanics (without these attributes the quantum mechanics is impossible). It was revealed, that phase-frequency method of late mechanics formulae presentation gives a real physical sense both to formulae themselves, and to concepts which seemed vague before *(namely: cause of motion, force, velocity, inertiality, gravitation)*. In this sense, the upcoming rhythmodynamics fills up the gap between the main physical lines and draws them together. But let's change the vector, since **the subject of the given article is to concern cases in which the third Newton law is not directly valid.**

Newton formulated the third law in the following way:

"Action always has equal and opposite interaction, in other words, actions of two bodies on each other are equal and directed in opposite sides".

This law represents the fact that one-way action of one body to another cannot exist in nature, but there is only an interaction between them, i.e. there is no action without reaction [1].

We must note, that the third Newton law is valid only for systems with 100% feedback, appeared in the interaction period. For example, during the magnet influence on the iron object it is revealed, that this object also starts to influence upon the magnet, i.e. to attract it with the same force. It happens because in the period of action of magnetic field the iron object itself becomes the source of magnetic field (Fig.1). Here the magnetic field, as an especial environmental condition, acts as a mediator, i.e. exists by itself in the interval between object and magnet .



Fig. 1

Interaction of magnet and metal body M. Here the action is equal to reaction, i.e. the third Newton law is valid.

It is considered to be that magnetic field, created by electric current, spreads with the velocity of light. If current impulse is short, then the magnetic field spreads independently from the conductor and no matter if there is current in the conductor at present, or not. If the distance up to the object is big, then the magnetic field remains between source and object for some time, and has no influence upon the object. In this sense the portion of magnetic field, placed on the path between source and body, can be considered as moving independent "entity", i.e. the space by means of itself carries its changed state (magnetic properties) from one place to another. In this period magnetic properties in the form of quantum can influence neither on the source, from which the magnetic quantum is already detached, nor on the object, which the magnetic quantum still does not reach.

But having reached the object, magnetic field changes the state of this object. If as the result of influence the object becomes a source of magnetic field, then the part of the field is reradiated in the direction of source, i.e. the object itself becomes the source for some time, and by this it is able to influence on the first primary source. In this situation the principle of action and reaction works, because the feedback takes place.

If the feedback does not appear during the period of influence of one body to another, then the action and reaction law is not valid in the system. Let's demonstrate it by the example of the mechanical experiments, in which there is a feedback between objects.

Let there is a device (Fig. 2), which throws off two water (air) streams in the opposite directions in such a way, that reactive forces completely compensate each other. At that the thrown down stream compensates the gravity too. In this case the device will fly without falling, i.e. it will have zero weight.



Fig. 2

The ball, suspended in the water stream, does not put pressure on the source. It happens because there is no feedback between the ball and the source. If you have such a device, then, lifting the ball by means of it, you will not feel the weight of the ball. The reason: the ball hangs due to the kinetic energy, which the stream passes to it and and this ball can not influence on the source through the water stream.

The appearance of the ball with the weight P_b does not influence on the weight P_n of the device. And even in the case if we press the ball down, i.e. essentially displace its location in the stream, the device will feel nothing.

The absence of device weight is evident for us; therefore we can easily move the device if its original (vertical) orientation remains unchanged.

Let's change the situation and place the ball (body with the shape, which is steady for hanging) in the upper stream. This ball with the weight about 10 kg is placed in a way to be kept by this stream at some distance, for example at 0.5 m. Will the device react on the changed situation, i.e. on the ball appearance? Will the weight of the ball, hanging in the stream, be added to zero weight of the device (0 + 10 kg)?

The calculation shows that it will not: $\Sigma P=0+10=0$ [kg]. There is only an illusion that the ball is supported by the stream and that it is a part of the system. As a matter of fact, the ball is detached from the system and hangs due to the water kinetic energy. It is easy to check it by making an experiment in a bathroom: "Remove the douche sprayer, then direct the stream up and holding it by the one hand with the aim of weighting, try to influence on the source by the other hand through the stream. You will be surprised to feel that the hand, which is supported by the stream or any object, which is hanged in the stream, does not influence on the source".

At first sight the situation seems to be a paradox, however it very illustrates the possibility of the force action without reaction. So, the action can be one-way, i.e. calling no reply reaction in the form of pressure on the action source.

In such an unusual way it is possible to keep the ball of bigger weight (100 kg and more), at that to move it easily by means of the device and at the same time not to feel the presence of additional weight in the stream. **It is possible only in the case when there is no feedback between body and source,** i.e. the body, hanged in the stream, has no ability to act on the force source. Thus, we can both hold and move the heavy ball without additional efforts, and also lift it up to any height (for example, 100 m). As a matter of fact, we deal with the **new gravidynamic paradox**.

It is interesting then, how to solve the task of the following type: "Let the body with 100 kg weight is hanged in the water (air) stream in such a way, that it does not change the velocity and direction of liquid outflow from the source nozzle. How much energy the operator must spend to lift this body to the height about 10 m?" (Here it means that the operator must take the device, which supports the ball, and, moving upstairs, lift the body, which hangs in the stream, by means of this device to the height about 10 m). If to solve this problem correctly (the condition is that the operator lifts himself together with the device and the ball), we will find out, that operator's energy is spent only for lifting of the device, which creates water streams. The operator, lifting together with the device, will not even notice that in the stream there is a body with about 100 kg weight **(this is the sense of the paradox).**

The situation only seems to be absurd, and even paradoxical for theorists, but it is not a hopeless one.

We can also observe the effect of action without reaction in ultrasonic field of the source. If the source is fixed on scales (Fig.3) and body is hanged, as it was made in the stream, the scales will show only the precise weight of the source and will not react on the weight of the hanged body, no matter how heavy it is.



Fig. 3

The ball, made of the special absorbent material, hanged in the powerful ultrasonic field, does not put pressure on the scales. It happens because of the absence of feedback between the ball, which has changed its state, and the radiation source. If you have such ultrasonic device in your hands, then lifting the ball by means of this device you will not feel the ball weight.

The experiment of such type was made in one of the secret institutes. Water was used as an acoustic environment. The heavy ball easily floated up from the vessel bottom i.e. it behaved as if it had no weight.

The similar phenomena but such of the other organizational level, sometimes become apparent in nature. The phenomenon has its very name because the event happens unexpectedly and is not analyzable through laboratory research [3].

"A spherical ball lightning about the size of a football ball flew over a village Galtsovka of Altaisky Krai at a height of twenty to thirty meters. The first shed in its way, with ferroconcrete poles, was crushed and collapsed. Flying over a slated house, the ball lightning tore away the roofing slate together with nails, raised it into air and pulled it along, scattering its parts all over the village. Flying over a tractor station, the ball lightning crushed a frame, welded of metal angles and covered with tarpaulin. On the approaching of the ball lightning to another frame, it was at first dragged along the ground, and after the ball lightning had passed it, the frame was lifted and carried at a distance of 300 meters. The weight of the frame was no less than 100 kg".

Further the author analyzes the situation from point of view of the known physical laws: "The frame of hundreds kilograms weight was carried by fields of the flying ball lightning. However, for some reason the ball lightning kept on flying straight and did not note that some metal frame was caught to it. If the ball lightning, as it is usually considered, has a density of air and it is a weightless formation, then why the frame with the weight not less than 100 kg could not change its flight trajectory even in some extent?"

It draws attention that in some cases the ball lightning field pushed objects away, and in other cases it attracted them. It can be explained only by fact that in each case the ball lightning field specifically influenced on internal properties of objects, and then objects themselves somehow reacted on their new state (they changed their motion) . The feedback absence (in other way it happens between magnet and iron object) allows the ball lightning not react upon the things, which take place in its field. If these objects themselves became sources of similar field, i.e. reradiated it, they would influence on the ball lightning trajectory. **Most likely, in the given case, there was realized the situation when action caused no reaction.**

Conclusions

In the context of known physical laws the particular problem of direct action without feedback was formulated and solved. The solution of this problem provides deep understanding of how to control weight characteristics of material objects in open systems. As it was shown by the example with water (which is only an illustration of more fundamental processes) we can "deceive" the nature, but only through the deep understanding of the processual character of the concerned events.

By the example of ultrasound we show, that in principle there can exist such field flows, which are able to influence on bodies without the feedback effect. There were defined some conditions and criteria of bodies and methods of influence, at which the third Newton law is not directly valid (it is not published in this article).

The described type of influence can be called as pressure. But during consideration of processes at atomic or deeper level, i.e. from the position of rhythmodynamics, we find out something of another kind, that is phase-frequency one. It prompts to us, what kind of technologies will exist and how our aircrafts will look in nearest future. But not everyone is able to understand it at once.

Moscow 15.05.2002

For sponsors: mirit@yandex.ru
Our website: http://www.mirit.org

References

1. Physics textbook for the 9th class of secondary school // M., Prosveschenie, 1982
2. Ju.N. Ivanov, Rhythmodynamics // M., Noviy Tcentr, 1997
3. G.V. Nikolaev, Scientific vacuum // Tomsk, Kursiv, 1999

Comment

In the gravitation field we have a balanced open system, in which appearance of the new body at first sight must cause this system reaction such as weight increase. However, this is not the case.

The given problem is solved in two independent steps:

1) examination of interaction between water source and water (reactive effect, which is compensated by counter flow);

2) examination of interaction between water, detached from the source, and the body (unit time impulse per unit area).

It is impossible to examine the interaction between the source and the body because water has no rigidity. There are no means to influence on the source through the intermediate stream, therefore the principle of action and reaction is valid for each step individually, but not for both! But in this case the third Newton law must be developed as following: "If there is a 100% feedback between two bodies, their interactions are equal and inversely directed. And if there is no feedback, the action of one body to another causes no reaction, i.e. the action is not equal to reaction". And this is already another law!

New Possibilities of Vortex Electric Power Devices

Stanislav A. Lisnyak

Prospect Stoletiya Vladivostoka, 112-37
690069, Vladivostok, Russia
Tel/Fax: (7-4232)310-554
Email: Stasvladcomru@mail.ru

The earlier published article [1] was devoted to the explanation of the excess energy output at the rotation of flow medium in vortex tube (VT). The researches on VT demonstrated by the real examples that the excess energy output is a real fact, which is determined by natural physical processes. These processes take place in the fluid at its vortex (rotational) motion in the closed volume by means of phase transformations (skips) of the fluid state. However, the practice shows that for obtaining of patents and benefits for the real vortex devices, which are made for heat generation, it is necessary to write a little about their real technical characteristics, though technical and constructive possibilities of vortex devices can be much better. Temperature of water of these devices could not be higher than 120°C, and value of fluid pressure is confined within 5…6 kg/cm^2. Circulation pumps of pressure over 6 kg/cm^2 are used to increase thermal power output of vortex heat generators (VHG). It causes the discredit of VHG since at such a method their generative possibilities reduces to 100% value and less! We set a problem to discover the ways and engineering solutions for the essential increase of the coefficient of VHG energy conversion to not less than 200% value.

Our experience in development and exploitation of deep-sea physical devices has given some engineering solutions in this way. Actually, we have the opportunity to use the generally applicable circulation pumps, which have pressure not more than 4.0 kg/sm^2. At the same time we can raise the temperature of the heat carrier to 300°C and higher! and the pressure can be increased to 1000kg/sm^2! Such fluid parameters allow to use this fluid as a heat carrier in powerful hot-water generators of steam engines, turbines etc. By the way, this method allows to make the value of temperature of water enough to supply its PYROLESIS! The main point of the method is the following: all the closed system of water-filled VHG works at pressure with the value under 1000kg/sm^2. It is provided by means of the special device, the so-called automatic pneumohydraulic block (APHB). This lets to raise the temperature of working fluid to 1000°C with no change in its aggregative state. The practical functional scheme of such a device is shown in Fig.1.



Fig. 1

1 – vortex tube; 2 – entry vortex chamber; 3 – by-pass;
4 – upstream end; 5 – circulation pump; 6 – heat-exchangers;
7 – APHB; 8 – volume of fluid leakage compensation;
9 - compressed-air flask; 10 - gas pressure regulator

The device works in the following way. The whole device is filled with working fluid without entrapped gas. At the operation of the circulation pump (5), fluid through the upstream end (4), placing in the entry vortex chamber (2), swirls, accelerates and gets into the vortex tube (1), where its "energy saturation" is realized. Then heated fluid gets into the heat-exchangers (6) for heating or for other purposes. After passing through the heat-exchangers, fluid gets into the pneumohydraulic device (7), where there is kept up the proper level of fluid pressure in the whole system. To prevent the system breakdown at the accidental fluid leakage, there is a device (8), which compensates such leakages. Compressed-air flask (9), with the volume under 1000kg/cm^2, and gas pressure regulator (10) keep up the selected level of the pressure in the system. The use of blocks (7,8,9,10) excludes evaporation in the system and prevents the breakdown of the circulation pump (5).

This VHG scheme allows to double the effectiveness of YUSMAR devices [2] only at the expense of rise in working fluid temperature in 2…3 times.

Observation of any fluid swirls and film documents of windspouts arrive to conclusion that all vortex structures are rotation bodies, created by the lines of the second order: $Y=aX^2$. In other words, as a result of the rotation in the swirl, air or fluid mass gets the acceleration of the second order. Taking into account the aforesaid, it is evident that in order to form the classical swirl in the VT, the very VT should be a tubular body of rotation. This body is created by the curve (see below Fig.2).

In YUSMAR and similar devices the vortex fluid motion take place in straight cylinder and 1/3 of this area is used for fluid deceleration that causes vortex flew disruption. This results in the impossibility to increase additional heat in the straight tube in more than 1.54 times. It is caused by the fact that the main vortex formation takes place only in the vortex chamber and the flows separation does in the tube itself. Then, this vortex formation is right away disrupted by different plate brakes! It suggests itself that output part of VT should be made in the spiral form, expanding at the flow passage.



Fig. 2
Generatrix of the wall of vortex tube



Fig. 3
Upper part of the tube

Such section, made on the outlet of the vortex tube, helps to slow down the flow avoiding its disruption, since axial-cold flow, placed along the tube axis, should stay intact. Two of such engineering solutions allow raising the level of the additional VHG energy up to 180…200%.

YSMAR devices are designed for one tube with the assigned heat output. However, if to take into consideration and to use the aforesaid conclusions, then we can raise energy conversion coefficient (ECC) above 200% at the series connection of two and more VT. The scheme of such a device is shown in Fig. 4.



Fig. 4

Where: 1 – the first VT; 2 – the second VT; 3 – circulation pump; 4 – heat exchanger

According to Fig.4, the total energy output of the presented device is:

$$Q=K^2$$

Where: *Q* is the total output of the device; *K* is energy conversion coefficient of one VT; 2 – quantity of serially connected VT; *P* – the assigned power of the circulation pump.

In our earlier article [1], concerning VT application, we supposed that there is a straight transformation of vortex motion of ionized fluid into electric current. Under studying of many articles, devoted to the methods of water ionization, we discovered a significant one. It demonstrates that at the determined temperature, pure water increases its ionization capacity up to 3 orders without changing in the aggregative state [3]. The diagram in Fig.5 shows such dependence.



Fig.5
Diagram of the dependence of pure water ionization from temperature

The diagram demonstrates that water at 300°C temperature increase the quantity of ions in 4000 times as compared to 0°C and in 40 times as compared to 20°C. If to take into consideration that first experiments on VHG modernization help us to find the ways of fluid heating up to the practically any temperature without changing of its phase state, then on using the dependences (see Fig.5) it seems possible to create vortex fluid electric generators of the forward transformation. The aforesaid pneumohydraulic block, which is used for VHG functioning, allows to keep up water temperature at 300°C and pressure at about 90kg/cm^2 without threat of water evaporation! Presence of any rotation of fluid medium always causes appearance of two vortex flows. **These flows always move and rotate in opposite directions and if we do not put obstacles for their motion then they transform into each other and can exist without energy supply for an indefinite period of time.**

The presented VT form (see Fig.6) provides the producing of two fluid flows in the tube. These flows do not influence to each other and there is only their reciprocal overflow without disruption of the flows in the central part of VT. The tube presents a tubular body of rotation, which is created by hyperbola. There is positive angular acceleration of fluid in the lower part of the tube; maximum speed of rotation of the axial and peripheral flows is in the middle part and negative angular acceleration, i.e. deceleration and transfer of kinetic energy into heat energy, is in the upper part of VT.



Fig.6

The maximum heating of fluid and its polarization is in the point Y=0. The polarization potential in the point can reach 10.000 V at 5m/sec flow speed for 10 cm diameter in the point. The cold flow, which comes along VT axis, is opposite to the peripheral hot flow. These flows close into one system in lower and upper chambers of VT. Thus, the presented VT classically modeled “rolling” and “unrolling” of water area.

There are no single vortexes in nature. Two vortexes, rotating in opposite directions, always appear while fluid mediums rotation! Science is not still able to describe energy overflows from one vortex center to the center of another one by means of mathematics. However we believe that this moment is close. There are maximum energy transformations of rotating water in the point Y=0.

The potential of the inner flow is equal to the outer flow by its value but is opposite by its sign. Potential difference is maximum in the point Y=0, in which removal of electric charges is the most effective.

It is appropriate mention here the name of Romanian engineer and researcher Henry Koanda, who in 20th of the last century discovered the so-called “Koanda effect” (attachment of fluid jet to the surface of usual kettle at pouring of it out the cups). Basing on this effect he suggested to make new type of aircrafts, which could have advanced bearing capacity and maneuverability. Unfortunately, money and conservatism of aircraft-industrialists did not allow realization of these engineering solutions.

At the same time, Koanda charged his disciple Patrick Flanagan with the job to research all **water properties**. The result was amazing! It was turned out that water actually has infinitely many phase states and when it is moving, then it can trap energy from the environment by some way. The publications on the point appeared in our press in the early eighties, late nineties of the last century. Most likely, they had become the basis of the invention, made by Potapov, i.e. vortex tubes for water!



Fig.7
Scheme of vortex electric generator

In the presented scheme of electric generator the entry and outlet vortex chambers are made of dielectric material in the spiral form. This material certainly should withstand not less then 300°C of fluid temperature and about 100kg/sm^2 of pressure. Fluoroplastic or ceramic can be used as such a material.

From aforesaid it seems to be possible to submit the new scheme of electric generator for readers’ consideration (see Fig.8).



Fig.8
Generalized scheme of vortex electric generator
1 – vortex tubes; 2 – circulation pump; 3 – heat exchanger; 4 – automatic pneumohydraulic block; 5 - compressed-air flask

Actually we could finish the article if it were no disputes about excess energy, which is released at vortex motion of fluid in tubes. Having used a simple experiment, which any inquisitive person can repeat, we found the positive solution (see the scheme of the experiment in Fig. 9).



Fig.9
Demonstration of energy increase of fluid, rotating in vortex tube

A pipe with not less than 60 cm length and about 1-inch diameter is placed in a reservoir with not less than 50 cm depth. The lower part of the pipe is formed as an arm circular generator with about 15...17cm diameter. The gap width is about 2 cm. If we place the pipe with closed top end, which then will be open, into the reservoir, then water is splashed out above 20 cm of the reservoir level. Thus at the least 20% energy increase of energy mgH is observed.

By the way, we suggest orthodoxies of physics and other who have doubts to make one more simple experiment. Try to boil water in a can. When water starts to boil, swirl it with a spoon to the right or to the left. Then you will suddenly discover that all water surface is calm and only in the center of the can there is a water-steam mixture, which is about 20% higher than the level of water surface. You will also see that water is absolutely calm at walls of the can. This experiment can be reproduced anytime and anywhere, even in space, since it is a demonstration of **vortex** fluid motion and its actual influence on everything, which is around!

All presented engineering solutions are practically reproducible in any laboratory. The authors of the article would welcome the opportunity to co-operate with science and industry representatives for realization of the ideas in real serial production devices.

References

1. O.V. Gritskevitch, S.A. Lisnyak, On possibilities of vortex energetics //New Energy Technologies. 2002, #1(4), p.2-3
2. Patent RF #2045715, 1993
3. Chemical and Engineering News. 2000 #1, p.26

Investigation of Electric Energy Transmission Processes in non-Metallic Conducting Channels

D.S. Strebkov, A.I. Nekrasov, S.V. Avraamenko

All-Russian scientific Research Institute of Electrification
of Agricultural Economy
2 Vishnyakovsky passage, 1 Moscow, 109456, Russia,
energy@viesh.msk.su



D.S. Strebkov

(Editor's notes by Alexander V. Frolov)

It has been found that at low frequency (1-25 kHz and higher) electric power can be transmitted with low losses from generator to receiver along single channel made of non-metallic conductive media such as water in plastic tube carbon thread, layer of damp soil, ITO films on glass substrate, laser and electronic beams. Transmitted power, as well as for traditional three phase lines, is limited by natural power of the transmission line and line capacity may reach at high voltage and pulse and operation modes the value 10^9 Wtt.

Introduction

The well-known methods of electric power transmission are based on transmission of active energy by means of conductivity currents in closed circuit. Electromagnetic energy spreads along power transmission lines (PTL) as progressing waves of electromagnetic field or field of charge [1]. Line wires made of aluminum or copper are conductive (guide) channels. Electromagnetic energy stream moves along these channels from generator to energy receiver and backwards to the generator. Maximum transmission possibility of 3-phase PTLs is limited by losses on the line resistance, by peak voltage (which is determined by electric strength of the insulation) and by electromagnetic stability of the line.

The modern approach to provide the electromagnetic stability consists in rigid regulation of line parameters by means of high-speed shunt reactor and consequence capacitive compensation for the purpose to except changes of electromagnetic power flows and to suppress resonant properties of a line [2].

In Tesla works [3] and in the researches of Russian scientists [4] a method of active power transfer was offered. This method supposes to transfer active power by means of electromagnetic capacitive current assisting with resonant properties of a single-wire line (SWL), made of a metal conductor. The purpose of the present work is a research of an opportunity to use non-metal conducting mediums for transmission of electric energy.

A pipe with not less than 60 cm length and about 1-inch diameter is placed in a reservoir with not less than 50 cm depth. The lower part of the pipe is formed as an arm circular generator with about 15...17cm diameter. The gap width is about 2 cm. If we place the pipe with closed top end, which then will be open, into the reservoir, then water is splashed out above 20 cm of the reservoir level. Thus at the least 20% energy increase of energy mgH is observed.

By the way, we suggest orthodoxies of physics and other who have doubts to make one more simple experiment. Try to boil water in a can. When water starts to boil, swirl it with a spoon to the right or to the left. Then you will suddenly discover that all water surface is calm and only in the center of the can there is a water-steam mixture, which is about 20% higher than the level of water surface. You will also see that water is absolutely calm at walls of the can. This experiment can be reproduced anytime and anywhere, even in space, since it is a demonstration of **vortex** fluid motion and its actual influence on everything, which is around!

All presented engineering solutions are practically reproducible in any laboratory. The authors of the article would welcome the opportunity to co-operate with science and industry representatives for realization of the ideas in real serial production devices.

References

1. O.V. Gritskevitch, S.A. Lisnyak, On possibilities of vortex energetics //New Energy Technologies. 2002, #1(4), p.2-3
2. Patent RF #2045715, 1993
3. Chemical and Engineering News. 2000 #1, p.26

Investigation of Electric Energy Transmission Processes in non-Metallic Conducting Channels

D.S. Strebkov, A.I. Nekrasov, S.V. Avraamenko

All-Russian scientific Research Institute of Electrification
of Agricultural Economy
2 Vishnyakovsky passage, 1 Moscow, 109456, Russia,
energy@viesh.msk.su



D.S. Strebkov

(Editor's notes by Alexander V. Frolov)

It has been found that at low frequency (1-25 kHz and higher) electric power can be transmitted with low losses from generator to receiver along single channel made of non-metallic conductive media such as water in plastic tube carbon thread, layer of damp soil, ITO films on glass substrate, laser and electronic beams. Transmitted power, as well as for traditional three phase lines, is limited by natural power of the transmission line and line capacity may reach at high voltage and pulse and operation modes the value 10^9 Wtt.

Introduction

The well-known methods of electric power transmission are based on transmission of active energy by means of conductivity currents in closed circuit. Electromagnetic energy spreads along power transmission lines (PTL) as progressing waves of electromagnetic field or field of charge [1]. Line wires made of aluminum or copper are conductive (guide) channels. Electromagnetic energy stream moves along these channels from generator to energy receiver and backwards to the generator. Maximum transmission possibility of 3-phase PTLs is limited by losses on the line resistance, by peak voltage (which is determined by electric strength of the insulation) and by electromagnetic stability of the line.

The modern approach to provide the electromagnetic stability consists in rigid regulation of line parameters by means of high-speed shunt reactor and consequence capacitive compensation for the purpose to except changes of electromagnetic power flows and to suppress resonant properties of a line [2].

In Tesla works [3] and in the researches of Russian scientists [4] a method of active power transfer was offered. This method supposes to transfer active power by means of electromagnetic capacitive current assisting with resonant properties of a single-wire line (SWL), made of a metal conductor. The purpose of the present work is a research of an opportunity to use non-metal conducting mediums for transmission of electric energy.

Methods

For realization of the experiments a single-wire energy system (SWES) was used. Its electric circuit is shown in Fig. 1 a,b. SWES consists of the following parts: high-frequency generator (1) of 28V voltage AC and 1 kWtt power; transmitting (2) and receiving (3) Tesla transformer with conductive channel (4) between them; rectifier (5) and electric load (7) as an incandescent lamp or electric motor (220V, 1 kWtt power). High-voltage winding of Tesla transformer is made in the form of cylindrical winding on the ferrite core with 50-100mm in diameter, 4000-6000 turns. The internal end of a high-voltage winding is connected to the conducting channel, and the external end is not connected at all (free end). A low-voltage winding that consists of 40-60 turns provides power supply of Tesla transformer. At the submission of electric power from the high-frequency generator to the winding of power supply zero potential appears on the free end of the high-voltage winding, and voltage with corresponding to the generator 1-25 kHz frequency is formed on the conducting channel. Besides, Tesla transformer as the spiral antenna generates electromagnetic waves of 5-10 cm length , which corresponds to the turn length of a high-voltage winding. Current resonance mode is formed in a supply circuit of Tesla transformer. At the same time, voltage resonance mode (of frequency equal to the generator frequency) is formed both in the reception and transmitting circuit of high-voltage windings and in the conducting channel (1).

The following materials were used as the conducting channels: filled with water or sea water polythene tubes with 10 mm diameter and 1,5 m long; plastic tray with soil layer of 150×10×400mm; film of tin dioxide – indium oxide (ITO) on 0,3 micrometer thick and 300 Ohm resistant glass substrate; graphite thread of 0,1 mm diameter, 500 mm long and with 100 Ohm resistance. For comparison steel and copper wire of 0,1 mm diameter and 5 m long was used also.

The voltage on the conducting channel changed in limits 1-10 kV, generator frequency changed from 1 up to 25 kHz. Voltage, current and capacity were measured on SWES output and on the load by standard electric measurement equipment.

Results and discussion

The replacement of the metal conductive channel to the channel made of non-metallic conductive materials does not effect to any reduction of possibilities of transmitting SWES or heating of a material of conducting channels. The consecutive connection of the channels did not resulted in reduction of transmitted power. Circuits break in the conducting water channel by the creation of an air gap led to the occurrence of arc discharge of reactive capacitor current. However this discharge did not cause increase of water temperature at transmitted power 300 Wtt and voltage 4,5 kV within 1 hour, that confirms the absence of energy losses in the conducting channel. The increase of water temperature did not result in decrease of transmitted power. Water PH reduction from neutral value up to 4 was detected.

The increase of sea salt concentration in water up to the level of 5-7 g/l did not increase transmitted power in comparison with tap water. However the replacement of tap water to dionized water with 16 MOhm resistances resulted in 100 % decrease of transmitted power.

Thus, it is experimentally shown, that conducting channels, produced from non-metal materials, have quasisuper-conductive properties in SWES at resonant mode. Possible explanation of this effect is the absence of active conduction current in the channel and the dominant role in the process of energy transfer belongs to displacement current, for which Joule Lentz law is not valid [11]. In the supply circuit of Tesla transformer current is practically reactive, and in resonance conditions active values of inductive and capacitive currents are equal. Vectors of these currents are opposite in their phases. Current of the high-frequency converter is spent for losses (component less than 2 %) in supply circuit wires and in the core of Tesla transformer and also for creation of reactive current in the conducting channel. In the mode of voltage resonance we have measured voltage active values of high-voltage inductance windings and conducting channel, interturn capacitance of windings and the capacities of the conducting channel. **We have discovered that they were equal and their phases were opposite to each other.** Losses from transmission of capacitive current through active resistance of the conducting channel are insignificantly small. Corona discharged losses and leakage current could be decreased by isolation of conducting channel. In this case active current and magnetic field of the line are equal to zero. Electric field of the line has maximum value. As well as in usual PTLs, maximum transferred power is limited by charge power of the line. Angle between vectors of voltage is equal to zero in the beginning and at the end of a line. Quality factor of SWES at frequency 5 kHz is in 100 times above than usual PTLs at frequency 50 kHz. In the conditions of resonance it leads to the significant increase of voltage along the conducting channel and it also leads to transmission power.

In usual PTLs voltage changes along the line are insignificant. The angle between vectors of voltage in the beginning and in the end of PTL constitutes the value, which is proportional to the wavelength of line.

On the basis of the researches the methods and devices are offered for transmission of electrical energy through plastic water guide, electro-insulated from ground, through irrigational channels and through isolated pipelines, which are used for gas, oil, hot and cold water transportation. Also the energy can be transferred through fiber-optic cable with conducting film on the surface, through all-carbon composite cable and through electro-insulated part of a ground and water surface, including highway parts. There are also methods and devices, designed for the following transmissions. These methods can be applied for transfer of power to stationary and mobile units. There are also generated requirements to electrical safety and to restriction of use of drinking and hot water from pipelines, which are under electrical voltage. These requirements and restrictions are generally the grounding of pipeline parts, which are located on certain distance from the generator. This distance is equal to the whole number of half-waves and for it SWES voltage is equal to zero. In the case of a side pipeline it is necessary to ground the parts of the pipeline that are placed on the distance of odd number of quarter-wavelength from the main pipeline. For 5kHz frequency the quarter-wavelength is equal to 15000 m.

N. Tesla grounded one end of high-voltage windings of his transformer on the receiving and on the transmitting end of SWES. Tesla considered this condition as the necessary one for the transfer of power along the Earth. The results of our researchers demonstrate that it is not necessary to use metal self-closed conductor (and current lines in the Earth) for transmission of electric energy on low frequency (1-25 kHz).

For this frequency energy could be transferred from the generator to the receiver if we have single-wire guide system created as non-metal conducting channel. By the similar way electromagnetic energy is transferred by laser beam or microwave-beam. But in our case we can obtain high degree of efficiency that is caused by slight losses on energy absorption and energy emanation. Thus one of the ends of high-voltage winding at the energy generator will have zero potential and remain free. The symmetric end of a high-voltage winding on the reception end should be connected to some natural capacity 6 (Fig. a), which can represent the case of a balloon or frame of a tractor. In our experiments we used metallic safe-box as such natural capacity.

Editor's note: In 1887, October 11, the famous Russian scientist Pavel Yablotchkov got the France Patent #120684, which described the method to increase efficiency of electrical circuit by means of "atmosphere electricity". It was confirmed in many experiments that output power can be twice more than power provided for the circuit from primary electric generator. For that it is necessary to use a single-plate capacitor. The special feature by Yablotchkov, that provides maximum efficiency, is the high degree of air ionization. For this Yablotchkov proposed to use the special capacitor, which consists of a big number of metallic needles. By its view this construction reminds of a hedgehog. Thus we can assumed; that above described natural capacity (balloon or frame of a tractor) serves as a collector of free electrons. By Yablotchkov the efficiency of such systems can be increased by means of maximization of ionization process. It will not lead to the increase of losses if the second end of the high-voltage winding is not grounded.

In the other method of energy transfer, a condenser-diode block 8 was connected to the conducting channel on the receiver end. This block is one of the known circuit of voltage doubling, Fig.1 (b). On the condenser 8 electric energy is transferred through electronic switch 9 to load 7. In this case the entire length of conducting channel 4 and Tesla transformer winding 2 at generator must be equal to odd number of quarter wave-lengths.

Non-metal conducting channel (for instance, fiber-optic or coal-plastic cable) can be used for transfer of electric energy not only along but also as perpendicular to the Earth (for example, to relay aerostat or sounding balloon).

SWES conducting channel can be also created by ionization of air ions with laser beam [13]. Neodymium laser with double frequency and with energy 1 Joule in impulse is able to create 10^{15} cm^{-3} ion concentration in air. This concentration is sufficient for streamer initiation and for transfer of electric energy through the conducting channel. Ionization potential, time of ion existence and of excited molecule state, coefficient of multiquantum absorption, all these determine the limiting length of conducting channel in atmosphere that is equal to 300 km and its wave resistance at 200-400 Ohm. Voltage which is necessary for SWES comes to the quantity 0,5 MV – 15 MV, that depends on the length of a channel.

We suggest to use relativistic electron bunches of high energy as the conducting channel out of the atmosphere. As distinct from laser bunches they do not have divergency. In this connection the Moon or artificial conducting body, where the energy receiver is placed, can be used as natural capacity 6. Whereas energy generator can be installed on the Earth or on its satellite. Transmission range of electric energy is determined by the length of the generated conducting channel. The entire length of the conducting channel in the beginning and in the end must be equal to the whole number of half-waves. Here the length of high-voltage windings of two Tesla transformers must be taken in considerations. Electric energy, transmitting through the conducting channel, can exceed the energy of electron and laser beams generators in 10-100 thousand times. These generators play the role of a directing system (of usual SWEG wires), along which the transfer of electric energy proceeds.

It was offered to use colliding and crossing electron and laser beams with conducting transitional bodies as conducting channels for transfer of energy from the Space to the Earth and back. On the heights up to 30 km compositional coaly and fiber-optic cables can be used. To create the global energy system of the Earth it was also suggested to apply single-wire energy system and conducting layers of the Earth ionosphere as the conducting spherical channel [14].

Thus for electric energy transfer at the frequency 1-25 kHz and higher in the resonance mode a single-wire channel from the following non-metal conducting mediums can be used: water, damp soil, coal-plastic, oxide film, ionized air channels, that are created by laser beams in the atmosphere, ionosphere conducting layers, and also beams of relativistic electrons out of the atmosphere. These non-metal conducting channels in the resonance mode have negligibly small resistance losses especially if to be compared with metal conductors, which are used in the known non-resonance methods of energy transfer by means of active conduction currents in the closed circuit. Electric energy in the resonance mode can be transferred with small losses from the generator to the receiver along the single-wire channel, made of non-metal conducting materials. The transfer can be realized at the frequency 1-25 kHz and higher, to any distance and to any direction relatively to the Earth. The transmission capacity is limited by charge power of a line as well as in the usual PTL. At high voltage the transmission capacity can reach the quantity from 10 Wtt to 10^9 Wtt in the pulse and streaming modes.



Fig. 1
Electric circuit of single-wire energetic system with non-metal conducting channel
a) SWES with symmetric array of Tesla generators

b) SWES with diode-capacitor block in the end of conducting channel

References

1. A.M.Kalashnikov, Ya.V Stepuk. Bases of radio engineering and radiolocation. Oscillating systems. M: Department of USSR Defense 1965, - p.127-158.
2. G.N.Alexandrov, S.V. Smolovic, Flexible lines for electric energy transmission over long distances. V Symposium “Electrical Engineering-2010”, October 12-22, 1999, Moscow Region P., 35-42.
3. N.Tesla Apparatus for transmission of electrical energy. US Pat #349621, 15.05.1900.
4. S.V. Avraamenko Mode of electric devices supply and device for its realization. Pat. RF #210649 11.04.1995. Publ. 10.04.1998. Bulletin #10.
5. D.S.Strebkov, S.V.Avraamenko, A.I. Nekrasov Device for power supply of mobile electrical aggregation. Pat. RF #2158206, 15.04.1999. Publ. 27.10.2000. Bulletin #30.
6. D.S.Strebkov, S.V.Avraamenko, A.I. Nekrasov Mode of supply of electric transport devices and device for its realization. Pat. RF #2136515, 26.08.1998. Publ. 10.09.1999. Bulletin #25.
7. D.S.Strebkov, S.V.Avraamenko, A.I. Nekrasov One-trolley system of power supply of mobile electrical aggregations. Materials of the international scientific and technical conference on automation of agricultural manufacture. Minsk 6-8 July 2000, - p. 65-66.
8. D.S.Strebkov, S.V.Avraamenko, A.I. Nekrasov Research on single-wire system of electric energy transmission. International conference Ecology and agriculture. Technique. – Saint-Petersburg, 2000, - p.50-55.
9. D.S. Strebkov, S.V. Avraamenko, A.I. Nekrasov. Single-wire electric system for renewable-based electric grid. Third European Solar Congress “Eurosun 2000”, June 19-22, 2000, Copenhagen, Denmark p., 10.
10. D.S. Strebkov, S.V. Avraamenko, A.I. Nekrasov. SWEPS – a novel electric power transmission technology. Planetary Association for Clean Energy Newsletter, 2001. – vol. 11, - 3, - p. 7-11.
11. I.E. Tamm. Bases of electricity theory. – M.Science, 1976. – p. 133, 397-400.
12. D.S. Strebkov, S.V. Avraamenko, A.I. Nekrasov. Mode and device for electric power transmission. Pat. RF #2172546, 24.01.2000. Publ. 20.08.2001. Bulletin #23.
13. D.S. Strebkov, S.V. Avraamenko, A.I. Nekrasov. Mode and device for electric power transmission. Pat. RF #2143775, 25.03.1999. Publ. 27.12.1999. Bulletin #36.
14. D.S. Strebkov, S.V. Avraamenko, A.I. Nekrasov. Mode and device for electric power transmission. Pat. RF #2161850, 14.07.1999. Publ. 10.01.2001. Bulletin #1.

Microcosm, Universe, Life

Alexey G. Shlienov
Budapeshtskaya, 66-1-77,Saint Petersburg, 192286 Russia

Ernest L. Petrov
Marshala Zaharova, 50-809, Saint Petersburg, 198330 Russia,
Fax.: (812) 587-9349

The authors of this article have prepared the 3rd edition of the book "Microcosm, Universe, Life" and now they are looking for a publisher to edit Russian and English version. In particular, the mechanism of energy transformation in the Universe (Fig.1) is described in the book. Matter radiates energy in the form of photons (as well as neutrinos). In general this energy is observed in the form of Cosmic Microwave Background Radiation (CMBR). Photons and neutrinos transfer the most of energy to de Broglie longitudinal photons. Matter absorbs energy mainly in the form of longitudinal photons. Thus, a cycling process of energy transformation (as well as matter transformation) occurs in the Stable Universe.

The 3rd edition is devoted to the description of 6 World Systems (Table 1), at that the 6th System is based on Unified Field Theory, which is developed by the authors, and proceeds from the following:

(Editor's: The understanding of the energy transformation mechanism allows to develop new fuel-less energy sources based of mutual transformations: longitudinal photons⟵⟶transverse photons).

Table 1

System	Principal Ideas
The 1st – Geocentric (Ptolemaic system)	Geocentrism and Anthropocentrism
The 2nd – Classic (Copernicus – Newton's system)	Description of the Universe on basis of Newton's Law of Gravity
The 3rd – Compromise (Tycho Brahe's system)	The compromises between two first systems
The 4th – Fractal (Charlie's system)	Non-heterogeneity of Large-Scale distribution of matter in the Universe
The 5th – Relativistic (Einsteinian system)	Description of the Universe on basis of gravitational field equations. Anthrop principle
The 6th – based on Unified Field Theory	Electromagnetic nature of all physical interactions. Irreversibility of all elementary micro-processes in combination with circular character of transformations in Large Scale of space ($c/H=R$ order) and time ($t_H=I/H$ order).

1. For theoretical results, which agree with the facts, it is necessary to use assigned inertial system (as Lorentz did), which, as we have known, is connected with CMBR. Obtained by this way decisions can be applied to the other systems, in particular, with use of Lorentz transformation for mass, energy, momentum, time and length.

2. Theory must agree with the whole known collection of facts, starting with such established empirical generalizations as basic principles of Natural science (Giordano Bruno, Lyell) and conservation laws (Mayer, Joule, Helmholtz, Faraday, Newton, Huygens, Vernadsky).

3. All physical objects could be presented as the systems, consisting of quanta of positive electric charge (protons), quanta of negative electric charge (electrons in fermions or boson states, which are part of neutrons

and atomic nuclei) and quanta of energy, impulse, moment of momentum (apeirons).

4. The leading role in the Universe energetic belongs to de Broglie longitudinal photons (of the first class, i.e. with the spin I=0), energy of which is twice as much as apeiron energy and is equal to *h H*, where *h* – is Plank's constant, *H* – is Hubble's constant.

5. Longitudinal photons, polarizable and depolarizable by matter particles, are the carriers of gravitational, magnetostatic and strong interaction. Electromagnetic interaction is carried by photons with spin I=±1 and weak interaction is carried by neutrinos and apeirons with spin I=±0.5.

6. All elementary microprocesses are irreversible, that correlates with circular character of transformations in Large Scale of space and time.

7. In particular, there is an irreversibility of the process of photons and neutrinos motion. At each segment, equal to the length of de Broglie wave, photons and neutrinos lose energy *h H*, which is equal to longitudinal photon energy. In such a way, Hubble's law can be presented as the following:

$$\lambda = \lambda_1 \exp\left(\frac{r}{R}\right) = \lambda_1 \exp(Ht),$$

$$Z = \frac{\lambda}{\lambda_1} - 1 = \exp\left(\frac{r}{R}\right) - 1 = \exp(Ht) - 1,$$

where λ, λ_1 – are observable and laboratory wave lengths, *r* – is distance, *R* – is radius of gravitation interaction, which is equal to the radius of Metagalaxy, *t* – is time, *Z* – is cosmological red shift.

8. As resulted upon this process, the excess of longitudinal photons is absorbed by matter. At that, mass is considered as measure of capacity, which is absorbed by matter in form of longitudinal photons. Thus, energy of the matter should be increased according to the law:

$$E(t) = m_\circ c^2 \exp\left(\frac{\varepsilon'}{c^2} t\right) \approx m_\circ c^2 + m_\circ \varepsilon' t,$$

at that,

$$\frac{\varepsilon'}{c^2} = \frac{H}{137^2},$$

where ε'- is the capacity, which is absorbed by unit mass in form of longitudinal photons, *c* – is velocity of light. In particular, electron of the 1st Bohr orbit in hydrogen atom (i.e. in this case at de Broglie wave length) absorbs energy *h H* at 1 period.

9. Being in ionization state, intergalactic matter is the general portion of average density of matter in the Universe ρ_{av}, besides, the average value of absolute velocity of baryon component is close to c/137. Let's consider this correlation to be exactly executed.

CMBR is the most powerful cosmic radiation. Its specter is close to that one of black body at temperature T_F=2.726K, i.e. its spectral density is maximal at frequency ν=160GHz. Cosmological red shift causes the increase of spectral density in radio-region (ν<160GHz) and the decrease of it in microwave region (ν>160GHz). Each of these processes is compensated by the inverse Compton effect, i.e. by the dispersion of radio-photons at matter corpuscle, first of all at protons. Calculations demonstrate, that average energy of absorbent radio-photons is equal to $0.45 \cdot 10^{-15}$erg (ν=68GHz) and average energy of radiated microwave photons is equal to $2.17 \cdot 10^{-15}$erg (ν=330GHz). There is one re-radiated microwave photon per one absorbed radio-photon. At that, the concentration of photons and CMBR spectrum remain unchangeable. Syunyaev and Zeldovich concerned the close inverse Compton-effect of CMBR dispersion on electrons in clusters of galaxies. Actually such an effect was discovered in 2 clusters of galaxies.

Thus, on transferring of energy to photons, matter corpuscles must fill the deficiency of energy by receiving it from longitudinal photons. In fact, there are observed demonstrations of longitudinal photons, they are "static fields". In this case it is a cosmic magnetic field, which accelerates charged particles of matter (Alfven). More detailed consideration let us to find a virial correlation between 4 main components of energy density:

$$\frac{\rho_{av} c^2}{137^2} = E_F = 2E_M = 2E_{kin},$$

where $r_{av}c^2$- is an energy equivalent of mass density of matter; E_F- is energy density of CMBR; E_M - is average energy density of magnetic field; E_{kin} - is average density of kinetic energy. Thus, some kinds of energy circularly transfer to another, which are interrelated (Fig. 1).

$$\frac{\varepsilon_{av} \rho_{av} V}{1.26} = E_F HV = 2E_M HV = 2E_{kin} HV = \\ = \frac{(\varepsilon_{av} - \varepsilon')\rho_{av} V}{0.26} = \varepsilon' \rho_{av} V,$$

where ε_{av} - is average capacity, radiated by unit mass in form of photons; *V* – is volume of 10^{81} cm^3 order, according to which the averaging is made.



Fig.1

Energy transformation in Large Scale ε_{av}=0.0942 erg gr^{-1}sec^{-1} – is average energy, which matter unit radiates in unit time; ε'=0.07476 erg gr^{-1}sec^{-1} – is energy, which matter unit absorbs in form of de Broglie longitudinal photons in unit time; $\rho_{av}=0.8730 \cdot 10^{-29}$ gr cm^{-3} – is average matter density in the Universe; $E_F=4.18 \cdot 10^{-13}$ erg cm^{-3} – is energy density of cosmic microwave background radiation (CMBR); $V \approx 10^{81}$cm^{-3} –is volume at which the averaging is made; $H=1.562 \cdot 10^{-18}$ Hertz.

10. These correlations include pressures, densities and temperature T_F, i.e. we have the equation of the state of intergalactic matter, and thus of Metagalaxy and the Universe. Let us present this equation in simple form:

$$E_F = \frac{\varepsilon' \rho_{av} R}{c} \approx \frac{\varepsilon_{av} \rho_{av} R}{c}$$

and let us compare it with correlation for density of radiant energy on surface of a star * or of star system

$$E_* = \frac{\varepsilon_* \rho_* R_*}{3c} \approx \frac{\varepsilon_* \rho_* R_*}{c}.$$

It is an especially amazing analogy between Metagalaxy (and the Universe) and large-scale cosmic system *g*, for which

$$E_g \approx \frac{\varepsilon_g \rho_g R_g}{c},$$

at that $E_g \approx E_F,\ \varepsilon_g \approx \varepsilon_{av} \approx \varepsilon'.$

This equation agrees with the whole observed data of globular clusters, galaxies, groups and clusters of galaxies, in particular, with empirical correlations, which are magnitude - angular diameter.

11. The stated approach lets to determine the values of many fundamental constants by different ways. As a case in point, the results of definite values ε_{av} and ε', erg g^{-1} c^{-1} are presented in the Table 2.

Table 2

#	Data	ε_{av}	ε'
1.	The boarder between two parts of the Main Sequence of stars	of 0.1 order	of 0.1 order
2.	The results of recalculation of observed star characteristics as respects to their centers	of 0.1 order	of 0.1 order
3.	The local minimum of star luminosity function near the Sun (according to G.A. Starikova's data)	of 0.1 order	of 0.1 order
4.	The correlation: mass - luminosity of white dwarf stars	of 0.1 order	of 0.1 order
5.	The correlation: mass - luminosity of neutron stars	of 0.1 order	of 0.1 order
6.	The correlation: mass - luminosity of globular clusters	less than 0.5	less than 0.5
7.	The correlation: mass - lumonosity of elliptic galaxies	more than 0.06	more than 0.06
8.	The correlation: mass - luminosity of spiral galaxies and irregular galaxies *Ir I*	less than 0.5	less than 0.5
9.	The correlation: mass - luminosity of galaxies as a whole	of 0.1 order	of 0.1 order
10.	The correlation: mass – luminosity of clusters of galaxies	of 0.1 order	of 0.1 order
11.	Empiric values of H, ρ_{av}, E_F constants	of 0.1 order	of 0.1 order
12.	The most exact values of h, e, G, E_F constants	0.0942	0.07476

12. Uncontradictory description of Microcosm and the Universe promotes the better understanding of Life, which is inseparably unified with them. The statistical data manipulation of more than 100 catalogues of microphysics and cosmic objects let us to get more than 1000 empirical correlations and diagrams, and to determine, that they agree with theoretical correlations, which were received according to the ideas on circular character of energy transformations (Fig. 1) and of matter in the Universe.

The Russian edition of the book is mailed out: the 1st edition (1995) at the cost of \$3; the 2nd edition (1998) at the cost of \$6.

The authors are thankful for valuable discussions to Yaroslav G. Klyushin and to Alexander V. Frolov.

HYPOTHESIS OF A THEORY OF EVERYTHING

Jack P. Gibson

www.crikcritter@infoave.net

This work grew out of an interest in curious occurrences, physical, mathematical and metaphysical. Many things just do not fit normal knowledge or are of unknown origin. Items such as gravity, time, mathematical equations of higher order, ghosts, e.s.p., etc. After a number of years, the problem began to appear to be not of this physical dimension but of a grander scale. A multi-dimensional space-time format seems to offer solutions to understanding most of the problems. In the following hypothesis all known physics and mathematics are considered to be valid. Metaphysical aspects, while not accounted for by physics and mathematics, are considered to be present in nature, either real or as a defect in physical processes, simply because they are experienced by so many people. The hypothesis will be kept simple because the details require the work of many specialists beyond my abilities and there is an endless list of speculative problems to which the hypothesis could be applied. To save time and distractions to the reader the following is stated as fact, knowing full well it may not be so, in order to present the most concise statement of the hypothesis.

The Universe, from the smallest to largest unit, is a quantum probability based fractal illusion. All matter exists in three-dimensional space, both internal and external. Any grouping can be considered a fractal space. It is both real and imaginary at the same time acting according to Eulers equation:

$$(e\,\hat{}\,(i*Pi))+1=0$$

more useful in this instance is the general form:

$$e\,\hat{}\,ix = -1=\cos x + i \sin x = -\tan 45 \text{ deg}$$

which allows use of a variable where Pi , a constant, is used in the original. The key to understanding of multi-dimensional space time is the realization that Pi is a variable! As we know Pi is the lock on three-dimensional space. Because of its mathematical nature it can neither grow nor diminish, thereby locking in the three dimensional form of the fractal unit under consideration. Such a fractal unit is considered to be at rest. But Einstein's equation $E=mc^2$ includes speed or movement. When objects are moving relative to a fixed point, the moving object is foreshortened in the direction of movement. A circle becomes an ellipse and Pi becomes indeterminate letting the circumference fluctuate, according to its relative speed, between two and Pi in a circle of unit diameter. If one goes beyond the value Pi the Universe grows out of bounds without limit becoming unstable. If the value goes below two then the Universe blinks out. I.e., one has exceeded the value of the constant c. Since all matter moves relative to a fixed fractal point and there are infinitely many points in the Universe of constantly changing velocities, the Universe is constantly adjusting its reality to the relative speeds of its components. Thus you get at times some weird things. Since not only time changes but the structure and observable mass also, one finds such things a matter appearing and disappearing as the small units of chaos move through the Universe. Changes in the local probability structure cause matter or reality to change in the image structure of the Universe.

To delve further into the aspects of what is happening, let us consider the following. Einstein's familiar formula gives the relationships for our three-dimensional fractal space. The inverse of the formula gives the speed with which any fractal space can change, including the Universe. There is both a positive and negative component to the change. If we consider our fractal space to be positive then we may consider any other point to be negative. There are an infinite number of such points and while the effect on our space may be small from any one point; the effect adds up. Any moving or changing of mass must effect the entire Universe. Mass and inertia are tied together in such a system. Measured mass is the attempt of the mass to return to zero relative speed in its associated fractal space according to the laws of physics, i.e. return to its lowest energy state. Inertia is the same effect of the changing state of the mass from one-dimensional state to another. Both are the result of efforts to change the dimensional state of mass. The positive aspect of the square root of the ratio of energy/mass is the view we behold from our position in space while the negative is the view from the opposite position.

In addition to the view of the Universe as being made up as fractal space, all moving at different relative speeds to any other fractal space, one must consider the make up of space having at the same time dimensional space, according to Euler's formula given above. There are at any moment an infinite number of spatial dimensions, defined by the relative speed of the fractal units involved, extending throughout the Universe. Each fractal unit is constantly changing its position in dimensional space. There are thus constantly changing energy states throughout the Universe both in relative position in real space and in dimensional space. While on one hand the distances across the Universe are immense in relative space, many points across the Universe are present in the same dimension at the same moment, possibly allowing for instance travel across space without the time penalty. This results in what might be considered a tuned circuit for the Universe or its components.

If we consider the structure of the relative Universe to be stored energy analogous to magnetic fields and the dimensional fields to be capacitive, then we can plot the results on a conventional two-dimensional chart where x is the horizontal axis and the vertical is the imaginary axis. A well-known construction in electrical physics and which is known to very often follow relativity closely. That throws the negative side of i into the second quadrant and the positive into the fourth quadrant, if we consider the Universe to be reflective and x to be negative when i is positive. Euler's equation does not reflect a totally positive or negative result. One wonders at this point as to other equations where unity is set to one or higher dimensional equations where the three dimensional components are factored out leaving another component. The fourth is considered to be time but how do the remaining fit into a Universe as this hypothesis describes? The line of thought can be followed further into electrical analogy, which I leave to the reader. The important result is that there should be a resultant Q, figure of merit, of the Universe resulting in nodes, or peaks, of probability. The resultant tuned frequencies of the Universe can be calculated from known factors of the Universe. Such an effect should show nodes of reality where matter occurs.

Properly applied the above hypothesis gives speculative answers to most of the problems facing science today. Questions such as:

Is the Universe open or closed?

Both. At each fractal component of the Universe there is a separate universe each reaching limits beyond which it cannot exist. At the same time there is somewhere a top Universe that must ever remain open.

What is the structure of time?

Time results from the ever changing fractal Universe and goes forward because all justification of the Universe causes a corresponding change in reality. Time moves slower at higher relative speeds and as all time is perceived to be slower in other fractal units, changes in our time are perceived to always go forward.

What are such phenomena as ghosts, spirits, apparitions, etc?

Events such as these are fragments of probability left behind due to sudden changes in the probability of the illusion we perceive to be reality. Having little energy they are perceived but are not able to interact with the more forceful real reality. They float free in probability space interacting at random intervals with the more forceful realities of the real world.

Where is the missing matter of the Universe?

There may be clouds of matter floating about in deep space, however, most of the approximately 90% of matter missing will be found in the layers of dimensions making up space and which, though interacting, do not appear in our reality. Calculations show only about ten dimensions are active in any one reality. The rest curl up in a ball or knot. While an essential part of space or reality they are not perceivable from the fractal Universe of which they are a part.

Parapsychology?

Events of this type can be attributed to interconnections on the dimensional, or imaginary, level where there can be interactions between fractal units though not directly associated with each other in relative space. The manifestation varies or is temporary due to the constantly changing and adjusting due to interactions of the probabilities of the Universe. Due to the innate probabilities of each individual, one may be more susceptible or sensitive than other individuals.

Bible, prophesies, angels, demons, aliens, etc.

If one takes the Bible at face value, with some leeway for it's age and many translations, it pretty well describes what it purports to describe. Historic predictions and conditions of today. If we assume this hypothesis has any value then the passage in which God says "Let us make man in our image." takes on new meaning. If we assume the probability basis of the Universe and the constant changing due to justification of reality and time then the miracles listed do not seem so in violation of the physical world. The miracles only require some ability to control reality. Certainly well within the providence of a creator. It speaks of heavenly beings capable of traveling through the Universe in real time and some who interfered with mankind on the Earth and that they are still doing so today. If this hypothesis is correct then it is readily seen how such events could occur. Creation events closely compare with the way todays computers are made and organized. If man can do it, why could not the original creator? If one ignores a creator, then one is hard pressed for an answer as to how the Universe was created.

UFOs

If one accepts any part of the above then the functioning of UFOs begins to be understandable. They move through space by making spatial jumps through fractal nodes. Their appearing around magnetic and electrical sources maybe due to some, on our part unrealized, easy entry and exit to other space at those points. They are able to make right angle turns at high speeds because the speed is only from our viewpoint. From the viewpoint of the craft it is simply changing locations in space. The turning on edge may be only a different orientation of space at that point.

Particles "Out of the Vacuum"

As we shoot atomic matter at higher and higher speeds into nuclei we are able to fracture the construction of the building blocks of matter. The high speed fractal construction of probabilities of the unit used smashes into the target with enough speed to mix the probabilities resulting in new nodes from the total probabilities present. Various probabilities are ejected resulting in short lived particles in unstable nodes. At times fragments of probabilities appear out of nowhere as they form up to combine into larger nodes. Travel distance and speed observed may give a clue to the basic frequency of the Universe.

Black Holes

The midpoint of the tuned circuit of the relative structure and dimensional structure of the Universe. As matter spirals in, from the relative structure, to be torn apart into its basic probabilities it passes through to the dimensional structure of space which holds 90% of the matter. There it is available for recollection and use by the relative space.

Probability. Basic structure of the energy of space.

Everything operates at random but within preferred patterns set by the frequencies involved. If you look long enough anything can be found. As a result we find odd bones of prehistoric creatures that may have never existed. Weird things can happen. Odd pieces of structure can occur such as metaphysical events. The Q of space is sometimes sharp and sometimes rounded, spreading out to include things not really meant to be in the overall scheme of the Universe. Christ said "If you had the faith of a mustard seed, you could say to the mountain move and the mountain would move". (For those not of the Christian faith, this may be considered not as any proof but as a representative statement of the meaning of this paragraph.) That is in keeping with the quantum statements that nothing exists until it is seen and that we have some control over the probabilities. If the structure of space is based on probability then the next important question is 'What is a probability'. We look to probability as a simple mathematical work. But, what makes probability work?

● ●



JACK P. GIBSON

About the Author:

EDUCATION: University of North Carolina at Raleigh (Nuclear & Electrical Engineering), Air University, Gunter Air Force Base (Radio Fundamentals, Motorized Equipment) Western Electric Co Engineering Center

The entire Universe is based on mathematics but we have no idea what is underneath the mathematics. Are dimensional planes perhaps better represented by other number bases? Are some of the unsolvable mathematical problems solvable in other number bases?

Gravity

All forces in the Universe are the same. Gravity happens to be the one that works on our fractal space. Others, molecular, atomic, and nuclear are the same but work in different fractal space. All are the result of matter trying to reach its lowest potential.

The above are only random questions chosen without any order. Most other problems can in some way be answered in line with the hypothesis, if not in detail. Too many questions can be fitted to the hypothesis not to take a serious look at it even though it may seem a little far out. The number of answers from one simple statement of the structure of the Universe defends the idea better than details.

One possible proof, and a relatively simple one, occurs to mind. Einstein's theory of relativity was proved when NASA flew a clock in space and then determined that time did slow down. To test the above hypothesis I would like to see four clocks used in the following manner.

Four atomic clocks in sets of two each. Two to be left on the Earth and two to be placed in space for an appropriate time. At the end of that time one of the clocks on the Earth to be taken into space and compared to the two already in space. Bring one of the clocks in space down to the Earth and compare to the clock left on the Earth.

The clock taken to space should read slower compared to the clocks in space because the ones in space were at rest compared to the one on the Earth.

The clock brought back from space should read slower, the same as the first one flown by NASA, because the clock on the Earth was at rest compared with the one in space.

The two clocks left in space should be returned after an appropriate time and compared to the ones on the Earth. The original in space should now be slower than the original on the Earth and its mate from space. The fourth clock is unpredictable.

The author apologizes for any errors in theory, mathematics, etc. There was no one to consult on the hypothesis which is an original work of my own and drawn on many references of others from the past If it has any value I am indebted to the work of all the others whose work I relied on. Any errors are entirely my own and not attributable to others. This work is freely published in the public domain to be used by any and all who wish to do so. It is not to be copyrighted or patented in any manner so as to restrict others rights to the hypothesis or it's use.

The Charge and Mass of a Photon

Dzabrail Kh. Baziev

Sirenevy blv., 65 building 4, apt.55
105484, Moscow, Russia
(095) 461-9398, (866-22)-5-10-11

Abstract

The discovery of true elementary particle named **electrino**, which has a constant mass and constant positive charge and which is a material carrier of magnetic field, electric current and all kinds of emanation, was firstly practically applied at the modernization of wireless telephone. In the review V. Anpilogov writes: "The question on the influence of low intensity microwave radiation on human health still remains open for discussion for more than 50 years" [3]. Discussion on this question has been already inappropriate still it was definitely proved in the patent application "Device, which is made to put away the charged particles flux from the head of the user of mobile wireless phone". During the talk on mobile wirelessphone $2{,}6\cdot 10^{22}$ particle/sec pass through user's brain, whereas their energy is $7{,}65\cdot 10^{-19}$ Joule, and the energy of binding of molecules in protein polymers ranges at $4{,}3\text{-}7{,}6\cdot 10^{-19}$ Joule according to L. Poling. From that we can conclude that microwave radiation of the radiotelephone with top antenna leads to the destruction of user's brain tissue. The author of the patent application D. Baziev (#2001105456, 28.02.01. in Russia and #PCT/RU02/00054 of the international application) offers to fix the antenna on the low part of the radiotelephone and to produce radiotelephones with minimal length within 10 cm. In this case the diagram of the directional radiation pattern is on the level of the user's chin and the brain is out of the direct exposure area. This harmless of the microwave radiation could not be proved before the discovery of "electrino".

Introduction

A systems analysis of all experimental and observation material gathered in physics, astronomy, and astrophysics from the times of Galileo let us reveal the following:

1. Experimental materials do not agree with the existing physical theory.
2. There is a certain fundamental disadvantage of the experimental material, which prevents to build a consistent theory.
3. This fundamental disadvantage consists in the absence of a charge antipode of electron, which is in the form of a true elementary particle with a positive charge and finite mass.
4. The proton and positron are not true elementary particles and neither of them can be a charge antipode of the electron because they are subjected to splitting.
5. Discovery of the second true elementary particle with a positive charge could restore the charge symmetry in physics, thus leading to a radical revision of the existing theoretical physics and resolving its current crisis state.

Searching for this particle required to ascertain physical nature of Planck's constant. This became possible only after the structure of a light beam had been understood. Namely, it was the photon sector velocity, known as Millikan constant μ, rather than the speed of light *c*, that proved to be a constant, viz.:

$$\mu = \lambda_i^2 \nu_i = 119.916984\ \text{m}^2/\text{s} = \text{constant}, \tag{1}$$

where λ_i and ν_i are the wavelength and frequency of the *ion* monochromatic beam in the light beam.

This new quantity elucidated the physical nature of Planck's constant:

$$h = m_\varepsilon \mu \frac{\sqrt[3]{4\pi/3}}{2} = \\ = 6.6262681\cdot 10^{-34}\ \text{kg m}^2/\text{s} = \text{constant}, \tag{2}$$

where m_ε is the mass of the second (after electron) true elementary particle to be called "electrino". From this expression we have

$$m_\varepsilon = \frac{2h}{\mu\sqrt[3]{4\pi/3}} = \\ = 6.85575729963\cdot 10^{-36}\ \text{kg} = \text{constant}. \tag{3}$$

The electrino has a positive charge ε determined by

$$\varepsilon = \frac{m_\varepsilon n_\varepsilon e}{m_u - n_e m_e} = \frac{-3.229526609098\cdot 10^{-54}}{1.6578584539\cdot 10^{-27}} = \\ = 1.98764431671\cdot 10^{-27}\ \text{C}, \tag{4}$$

where $m_u = 1.66057 \times 10^{-27}$ kg is the mass of an elementary atom accepted as a mass equivalent of one atomic unit; $n_e = 3$ is the number of electrons in one elementary atom; $e = 1.6021892 \times 10^{-19}$ C is the charge of an electron; $m_e = 9.038487 \times 10^{-31}$ kg is an improved value of electron mass; $n_\varepsilon = 2.418198867 \times 10^{8}$ is the number of electrinos in an elementary atom.

Thus, it is obvious that Planck's constant is the angular momentum of the electrino. Moreover, it was Planck's constant that concealed the second true elementary particle, which is the charge antipode of the electron discovered by J.J. Thompson as far back as in 1897.

The solution of Planck's constant has become a basis for the synthesis of the new theory of physics [1]. This theory in particular shows that the electrino is the carrier of the magnetic field and electrical current. It is a photon of radiation of all ranges, and serves as a universal carrier of energy and information. The electrino plays the role of a neutrino in moving along the first order trajectories.

The first experiment

An extraordinary importance and novelty of the new theory required **an experimental proof of the electrino**. For that several experiments were made in the Institute of General and Inorganic Chemistry, Moscow. The experiment was based on the following effects predicted by the theory.

1. If assume that electrino exists and that light beam is a flux of particles having positive charge and finite mass [1] we can conclude the following. At the discharge of the dc source through an incandescent lamp in which the current is converted to light and irreversibly emitted, the source weight in charged state must differ from its weight in discharged state. If we prove this difference experimentally we may say that light does consist of material particles of finite mass and a dc charge carried away by light is positive because an incandescent lamp (W=15 Wtt) does not emit electrons, which are the carriers of negative charge.
2. The second effect to prove was that the weight of a discharging dc source is *increasing* whereas its weight when charged is *decreasing*.

To prove the validity of these predictions, several sealed containers with different dc sources inside were fabricated. The electrodes were brought out through glass insulators. The batteries were discharged through an electric lamp radiating in the visual and infrared ranges. The weight of containers was measured before and after discharge process with accuracy $\Delta W = \pm 0{,}02$ mg; balance error was equal to $\Delta = \pm\ 0{,}05$ mg the standard deviation of the measurements was within $\sigma = \pm 0{,}03$ mg; the buoyancy was calculated for each measurement of weight. In this paper, we present test results of only one container with four generally marketed GP rechargeable cells connected in series. The total battery voltage reached 5400 mV at 6000 mA/h charge capacity. The discharge was interrupted when the voltage dropped to 4000 mV, the duration of the discharge was measured accurate to one second. Two series of experiments were run: one in air, the other, under argon. Each series had ten charge-discharge cycles (Table 1 and Fig. 1). The total amount of the experiments and detailed discussion of results have been summarized in a recently published brochure [2].

The results of the above tests allow us to make the following conclusions:

1. Both galvanic and rechargeable cells during a discharge through an electric lamp show sufficient changes in their weight and charge thus proving that photons have a finite mass and a positive electric charge.
2. A new elementary particle, named electrino, derived from Planck's constant in August 1982, and published in May 1994, thus gets a complete and absolute experimental confirmation.

The second experiment

One of the concepts of the new theory is that the speed of light in vacuum is a function of photon frequency along the beam axis, according to the proportions:

$$c_i = \sqrt{\mu \nu_i} \quad [\text{m/s}], \qquad (5)$$

$$\nu_i = \mu / \lambda_i^2 \quad [\text{s}^{-1}]. \qquad (6)$$

According to the new theory, for the velocity of monochromatic light (solar light or mercury-discharge lamp, but not a laser) with a wavelength of $\lambda_r = 6.8 \times 10^{-7}$ m (mid-point of the red spectral line), we have

$$\nu_r = \mu / \lambda_r^2 = 2.59336038 \cdot 10^{14}\ \text{s}^{-1}, \qquad (7)$$

$$c_r = \sqrt{\mu \nu_r} = 1.76348505882 \cdot 10^{8}\ \text{m/s}, \qquad (8)$$

which is 58.823% of the speed c_v = 2.9979246×10^8 m/s of a violet beam with a wavelength of 4 × 10^{-7} m.

We have to account that, according to this theory, the laser beam is not a true light beam though it is created of electrinos. The speed of laser beam is equal to the speed of beam plus the speed of current in the conductor, viz.,

$$\nu_0 = 2.8992629 \cdot 10^8\,\text{m/s} = \text{const} \qquad (9)$$

If we select a monochromatic beam of ultra-violet light with a wavelength of $\lambda_1 = 4 \cdot 10^{-8}$ m then its velocity will be c_1=10 C:

$$c_1 = \mu / \lambda_1 = \frac{119{,}916984 m^2/\sec}{4 \cdot 10^{-8} m} =$$
$$= 2{,}9979246 \cdot 10^9 m/\sec$$

$$\nu_1 = \mu / \lambda_1^2 = \mu / 16 \cdot 10^{-16} m^2 = 7{,}4948115 \cdot 10^{16} \sec^{-1}$$



Fig. 1
Voltage drop [mV] of a battery and (2) weight increment [mg] of container #6 in an argon atmosphere during the second discharge cycle [minutes]. X-direction – is spark duration in minutes; Y-direction – is voltage of a battery; auxiliary Y-direction – is weight incensement (mg).

$$c_1 = \sqrt{\mu \cdot v_1} = \sqrt{8{,}987551907 \cdot 10^{18} m^2 / c^2} = 2{,}9979246 \cdot 10^9 m/\sec$$

This experiment has been run yet, and it is offered for experimental verification with further publication of experimental results.

Table 1

Weight of container #6 (under argon) in charge-discharge experiments

Run		Charged battery		Discharged battery			Charge
	Measured value $W \pm \sigma$, mg	Buoyancy Gmg	Real weight $W_0=W+G$	Measured value $W \pm \sigma$, mg	Buoyancy Gmg	Real weight $W_1=W+G$	weight $\Delta W_z = W_1-W_0$, mg
1	126825.13±0,02	85.031	126910.166 ±.0.02	126825.901 ±0.01	85.002	12691.903 ±0.01	0.737
2	126825.107±0.02	86.572	126911.679 ±0.02	126826.221 ±0.01	86.538	126912.759 ±0.01	1.080
3	126825.21±0.01	86.782	126911.992 ±0.01	126826.279 ±0.01	86.560	126912.839 ±0.01	0.847
4	126825.187±0.01	86.563	126911.749 ±0.01	126826.493 ±0.02	86.385	126912.878 ±0.02	1.128
5	126825. 65±0,04	86.290	126911.941 ±0.04	126826.65 ±0.01	85.836	126912.941 ±0.04	0.770
6	126827.28±0.00	85.187	126912.467 ±0.00	126827.990 ±0.01	85.204	126913.194 ±0.01	0.727
7	---	---	---	---	---	---	---
8	126826.98±0.00	86.182	126913.162 ±0.00	12682 7.897 ±0.02	86.308	126914.205 ±0.02	1.042
9	126826.95±0.00	86.307	126913.257 ±0.00	126827.757 ±0.01	86.402	126914.159 ±0.01	0.902
10	126827.25±0.00	86.294	126913.544 ±0.00	126828.35 ±0.00	85.729	126914.079 ±0.00	0.535

References

1. D.K. Basiev, Osnovy obyedinyonnoy teorii fiziki (Foundations of Unified Theory of Physics), Pedagogika, Moscow, 1994
2. D.K. Basiev, Zaryad i massa fotona (The charge and mass of a photon), Pedagogika, Moscow, 2001
3. V.P. Anpilogov, "The century of quality", #3, 2001, p.60

● ●

About the Author

When a child Dzabrail Kh. Baziev became a political exile along with all Balkarian people; in 1956 he was rehabilitated and in 1957 graduated from the secondary school with steady purpose to become an outstanding chemist. His first higher education is biological and chemical (two-profile department of Kabardino-Balkarian State University). In 1965 Baziev also completed his post-graduate study in Biological Department of Moscow State University.

At 1979 Dz.Kh. Baziev had published 25 scientific articles on ornithology and ecology, however, this period became a sudden turn in his scientific work. In order to elaborate the basis of theoretical biology, he came to the conclusion that biological process could not be described without understanding of its physical essence. On the other hand, it had become evident that there was no any solution for physical phenomenon, which is the basis of biological process.

In 1983 the scientist gave descriptions of his first fundamental discoveries. He found the solution of the physical essence of Plank's constant and pioneered the use of it in gases analysis. It was a revolutionary step in science since the synthesis of science was realized at the fundamental level for the first time.

As the result of this considerable work there was a new interdisciplinary theory of physics. The author created new thermodynamics of real gases and new electrodynamics, which differs from maxwellian one and it considers *electrino* as the carrier of magnetic field and electric current.

Dzabrail Kh. Baziev has succeeded in the systematic analysis of the vast experimental material and discovered that ***electrino,*** **as the true elementary particle with positive charge, is able to provide the connection of physics with biology, chemistry and other parts of the fundamental science. Thus it leads us to the radical reconsideration of all conceptions, existing in natural science.**

The Homopolar Motor: A True Relativistic Engine

Jorge Guala-Valverde

Norpatagonica-R&D Dept. S.Fe 449 Neuquen, Argentina
Q8300BG1, Confluencia Tech University Neuquen, Argentina
gual@ieee.org

Pedro Mazzoni

Fundación Julio Palacios Neuquen, Argentina
fundacionjuliopalacios@usa.net

Ricardo Achilles

Confluencia Tech University Neuquen,Argentina,
RA Biosystems Neuquen, Argentina
achilles@ieee.org

This article discusses experiments, which enable the identification of the seat of mechanical forces in homopolar-machines. Authors provide a suitable variation on a recent work "The Unipolar Dynamotor: A Genuine Relational Engine" [3], where "relational" implies "absolutely relativistic". The authors' view agrees with both Weber's recognition in the 19th century of the importance of relative motion in electromagnetic phenomena [4] and Einstein's 1905 statement concerning electromagnetism [5].

The Faraday disk: a reversible engine

The essential components of the homopolar machine, first conceived by Faraday in 1832, are shown in Figure 1. A conducting disk, free to rotate in the neighborhood of a permanent magnet, is attached to the end of a shaft. A closing wire provides a conducting path between two arbitrary points of the disk. Such a device exhibits *reversible* behavior.



Fig.1
Faraday's setup magnet, disk and closing wire

A radial current path of length L takes place in a region of the disk when direct current (*dc*) from an external source is injected into the closing wire. The interaction of the current with the magnetic field produces a Laplace force [6]

$\boldsymbol{F} = \int_{a}^{a+L} I(d\boldsymbol{r}x\boldsymbol{B})$ causing the rotation of the disk. This set-up is the *motor configuration.*

When the disk is spun by an external source of mechanical energy, an *emf* appears in it. The displacement of free charges is produced in this case by the Lorentz force $\boldsymbol{f} = q(\boldsymbol{v}x\boldsymbol{B})$, converting the conducting disk into an *emf* source able to drive *dc* through the whole disk plus closing-wire circuit. This set-up is the *generator configuration*.

A seemingly curious fact occurs in the motor configuration, when *dc* is injected into the circuit with the disk attached to the magnet. Both disk and magnet turn together.

Two rival theories, a relativistic and an absolutistic one, have been applied to understand the observed facts:

In relativistic view, generator configuration makes sense only when there is relative motion of the magnet with respect to either the disk or the closing wire. Also, a motor configuration will only take place if the *possibility of relative motion* between magnet and either disk or closing wire is enabled.

Thus, in the relativistic framework, with the magnet attached to the disk, the closing wire becomes the "active" part for the production of mechanical forces or *emf*. In this case the disk itself behaves as a "passive" element providing a closing-circuit current path.

Conversely, in the eyes of an absolutist, a generator configuration is enabled only because of the disk or closing-wire *absolute* motion. Here, absolute means "relative to a frame where the preponderance of the mass of the universe is at rest" [7,8]. In our case, the lab frame acts as an acceptable absolute-motion reference. Thus, from an absolutistic view, the magnet's rotation with $\partial B/t = 0$ in each point of the surrounding space is unable to produce an *emf* on nearby conductors. When in a motor configuration, *dc* is injected in the circuit, and the absolutist assigns the observed rotation to the magnet "dragging" by the conductor. Here, the closing wire acts as a "passive" circuit element.

New experimental work, complementary to that currently known on the subject, introduces arguments in favour of the relativistic viewpoint. The related experiments, whose underlying physics rests upon a modified version of the original Faraday setup, are described in the following sections.

The asymmetrical rotor

Figure 2 shows the disk-shaped ceramic permanent magnet creating the axial magnetic field ***B***. The removal of a 12° sector introduces a field-reversion region. Outgoing and ingoing ***B*** field lines are represented by the and symbols, respectively.



Fig.2
Layout of the Asymmetrical Rotor applied to the experiments

Two mercury collector rings are embedded in a wood cylinder. One is located close to the hollow-disk magnet inner rim and the other in the proximity of the outer rim. The magnet's inner and outer radii are 25 and 75 mm, respectively, and its height 25 mm. Its average flux density 2 mm above the magnet has been estimated to be 0.05 T based on a generator experiment with a rotating copper disk. The magnet-and-wood-cylinder body (the asymmetrical rotor from here on) is firmly anchored to a vertical shaft terminated in sharp points at both ends. While the lower one lays on a hard-polished surface, a conical bearing, enabling its almost frictionless rotation, centers the upper one.

Unlike the series-connected conductors diametrically anchored to the shaft in the Guala-Valverde case [3], only one radial conductor wire, a probe located 2 mm above the magnet's face, was considered. By mounting it on a bearing, its free rotation is permitted with its ends remaining in contact with both collector rings. A 12V lead-acid battery applied to the closing wire feeds the probe through the collector rings. In the first four experimental cases presented the closing wire remains firmly anchored to the lab. In two complementary experiments, rotation of the closing wire mounted on two shaft-centered bearings is allowed. Its behavior as a probe occurs by the injection of *dc* from an additional closing-circuit wire anchored to the lab.

Experimental

Six experiments performed are described below:

1. Rotor anchored to the lab, probe free to rotate above the magnet's upward magnetic-field region: A radially-ingoing injected *dc* in the 0.2 A range was enough to overcome conductor-bearing and mercury-wire contact friction. A net *counterclockwise rotation* of the probe took place.

2. Probe anchored to the rotor above the magnet's upward magnetic-field region, with both free to rotate: A radially-ingoing injected *dc* in the 5 A range was enough to overcome conductor-plus-rotor inertia and friction. A net *counterclockwise rotation* of the probe took place.

3. Rotor anchored to the lab, probe free to rotate above the magnet's downward magnetic-field region: A radially-ingoing injected *dc* in the 0.2 A range was enough to overcome conductor-bearing and mercury-wire contacts friction. A net *clockwise rotation* of the probe took place.

4. Probe anchored to the rotor above the magnet's downward magnetic-field region, both free to rotate: A radially-ingoing injected *dc* in the 5 A range was enough to overcome conductor-plus-rotor inertia and friction. A net *counterclockwise rotation* of the probe took place.

5. Rotor anchored to the lab, closing wire free to rotate above the magnet's upward magnetic-field region: A 0.4 A *dc* injected in the inner collector ring was enough to overcome conductor-bearing and mercury-wire contacts friction. A net *clockwise rotation* of the closing-wire took place.

6. Rotor anchored to the lab, closing wire free to rotate above the magnet's downward magnetic-field region: A 0.4 A *dc* injected in the inner collector ring was enough to overcome conductor-bearing and mercury-wire contacts friction. A net *clockwise rotation* of the closing-wire took place.

Discussion of results

Experiments (1) and (3) can be explained using either absolutist or relativistic viewpoints because of the coincidence of the probe motion relative to the lab with the probe motion relative to the magnet.

Experiment (2) can be explained by a trivial absolutist argument founded on a hypothetic probe "dragging effect" on the magnet. A relativistic viewpoint recognizes the "active" rotational torque on the closing wire rather than on the probe where, hinging on Newton's third law, the whole action may be split in two:

Magnet-probe. The magnet produces a counterclockwise torque on the probe, and the probe exerts an equal but opposite torque on the magnet.

Magnet-closing wire. The magnet exerts a clockwise torque on the closing wire, and the wire an equal but opposite torque on the magnet.

With the probe attached to the magnet, there is no chance for relative motion between them. Consequently, due to the action-reaction cancellation, rotation is forbidden. Conversely, with the closing wire mechanically decoupled from the magnet, relative motion of the latter is permitted. The torque exerted by the closing wire on the magnet is responsible for the observed rotation.

Experiment (4): Due to its similarity with (2) a trivial relativistic explanation is applicable to the counterclockwise torque exerted by the closing wire on the magnet. There is no known plausible absolutistic explanation for it. As quoted above, the hypothetical dragging effect would produce a clockwise rotation in this case. The consideration of the experiments (2) and (4) suffices to reject the dragging hypothesis.

Complementary experiments (5) and (6) confirm the short-range extension of the field-reversion region founded on the closing-wire *clockwise* rotation (6). Briefly speaking, the closing wire is not sensitive to the field reversion and the magnet's *counterclockwise* reaction explains at once the outcome of (4). Clearly, experiments (5) and (6) show that the torque on the closing wire is independent of its location on the magnet.

Figure 3 depicts the two rotational torques involved in (2) and (4).



Fig.3
Rotational torques acting on the magnet and on the closing wire

Topological and miscellaneous considerations

One of the keys to the success of the above described experiments lies in the dynamotor's magnet design (see Fig.4). The short-range field reversion region allows the inversion of the Laplace force on the probe, making the force on the closing wire insensitive to that ***B**-field* reversion.



Fig. 4
The magnet's field-revision region

In all the above cases the electromagnetic forces between probe and closing wire were neglected because of its small magnitude compared to the predominant magnet-wire interaction forces.

The observed torques became, in all the experiments, independent of the location of the contact points between closing wire and collector rings. Also, the closing wire shape exhibited no noticeable influence on torques. These observations can be easily explained using the $div\mathbf{B} = 0$ fundamental law, Laplace force, and some elementary topological considerations.

Kennard [1], Bartlett [1]· Panosky [7,8], Muller [9], Wesley [10] and some of this article's authors took absolutistic viewpoints when dealing with homopolar phenomena [11,12]. On the contrary, Weber [4], Assis [13], and Kelly [14] adopted a relativistic framework on the issue from the beginning.

By attaching the magnet to the disk in the original Faraday setup, the relative rotation between disk and closing wire remains unchanged. Therefore, in a generator configuration, the disk plus magnet rotation at with the closing wire at rest in the lab is entirely equivalent to the closing-wire rotation at – with the disk plus magnet at rest. This fact introduced a correct but physically "colorless" weak relativism to the homopolar generator description: the "unipolar generator really has three components, the magnet, the cylinder and the meter (including the contacts). A relative motion of the last two, not the first two, is required" [1].

A growing interest in basic electromagnetism [15,27] can not be ignored, and from time to time some authors, attempting to catch "free energy" from the space, have claimed the design of homopolar engines with efficiency greater than unity, as can be checked by searching for *homopolar motor* on the Internet. The strict application of Newton's third law precludes the above non-physical possibility.

It is worthwhile to stress that the homopolar machine is a famous example where Faraday's flux rule fails. This fact worried Faraday himself and is clearly discussed by Feynman [28] who emphasized that the correct physics is always given by the Lorentz force law and the Maxwell fundamental equation $\mathrm{curl}\, E = -B/t$. Homopolar induction is fully understood using only the Lorentz force. Our experiments enhance the relativistic structure of the Lorentz force because the only relevant velocity is the velocity of the conductor relative to the magnet.

Acknowledgments: To Profs. C.N. Gagliardo and A. Ipohorski-Lenkiewicz for the conceptual comments on this development.

References

1. J. Guala-Valverde and P. Mazzoni, "The principle of relativity as applied to motional electromagnetic induction". Am. J. Phys 63, 228-229 (1995).

2. J. Guala - Valverde, P. Mazzoni and Ro Blas, The quasilinear generator and = 0". Am. J. Phys. 65, 147-148 (1997).

3. J. Guala-Valverde and P. Mazzoni, "The unipolar dynamotor: a genuine relational engine". Apeiron 8, 41-52 (2001).

4. A.K.T. Assis, Weber Electrodynamics (Kluwer, Dordrecht, 1994).

5. A. Einstein, "Zur elektrodynamik bewegter körper". Annalen der Physik 17, 891-921 (1905). See also The Principle of Relativity. A.Einstein, H.A. Lorentz, H. Weil and H. Minkowsky, pp. 35-65 (Dover, New York, 1952).

6. G. Cavalleri et al. "Experimental proof of standard electrodynamics by measuring the self-force on a part of a current loop". Phys. Rev. E 58, 2505-2517 (1998).

7. W. K. H. Panofsky. Private communication (letter to J.Guala-Valverde, dated Jan 30, 1995).

8. W. K. H. Panofsky and M. Phillips, Classical Electricity and Magnetism. (Addisson Wesley, NY, 1955).

9. F. Müller, "Unipolar induction experiments and relativistic electrodynamics". Galilean Electrodynamics 1, N°3, 27-31 (1990).

10. J.P. Wesley. Private communication (letter to J.Guala Valverde dated Nov 01, 2001). See also "Progress in Space-Time Physics", Benjamin Wesley, Blumberg (1987).

11. J.Guala-Valverde and P. Mazzoni, "The motional electromagnetic induction revisited". Russian Academy of Sciences, 3rd Conference, pp.186-188. St. Petersburg (1995).

12. J. Guala-Valverde and P. Mazzoni, "The unipolar Faraday generator revisited". Galilean Electrodynamics, 4, 107-108 (1993).

13. A.K.T. Assis and D.S. Thober, "Unipolar induction and Weber's electrodynamics". Frontiers of Fundamental Physics, Plenum Press, NY, pp. 409-414 (1994).

14. A.G. Kelly, "Experiments on unipolar induction". Physics Essays 12, 372-382 (1999).

15. A.E. Robson and J.D. Sethian, "Railgun recoil, Ampere tension, and the laws of electrodynamics". Am. J. Phys. 60, 1111-1117 (1992).

16. A.K.T. Assis, Relational Mechanics (Apeiron, Montreal, 1999).

17. P. Graneau, "Electromagnetic jet-propulsion in the direction of current flow". Nature 295, 311-312 (1992).

18. T. E. Phipps and T.E. Phipps Jr., "Observation of Ampere forces in mercury". Phys. Lett. A 146, 6-14 (1990).

19. P.Graneau and N. Graneau, Newtonian Electrodynamics (World Scientific, Singapore, 1996).

20. V.F. Mikhailov, "The action of an electrostatic potential on the electron mass". Annales de la Fondation Louis de Broglie 24, 161-169 (1999); 26, 33-38 (2001).

21. A.K.T. Assis, "Comment on experimental proof of standard electrodynamics by measuring the self-force on a part of a current loop". Phys. Rev. E 62, 7544 (2000).

22. P. Graneau and N. Graneau, "Electrodynamic force law controversy". Phys. Rev.E 63, 058601-2 (2001).

23. T.E.Phipps and J. Guala-Valverde, "Simulation of amperian current elements by magnetic toroids". 21st Century Science & Technology 11, 55-65 (1998).

24. M. Bueno and A.K.T. Assis, Inductance and Force Calculations in Electrical Circuits (Nova Science Publishers, Huntington, N.Y. 2001).

25. H. Aspden, "Anomalous electrodynamic explosions in liquids". IEEE Trans. on Plasma. Sc. 14, 282-285 (1986).

26. G.M. Graham & D.G. Lahoz, "Observation of static electromagnetic angular momentum in vacuo". Nature 285, 154-155.

27. V. Dvoeglazov, "Essay on the nonmaxwellian theories of electromagne-Tism". Hadronic Journal Suppl. 12, 241-245 (1997).

28. R. Feynman, The Feynman Lectures on Physics, II. (Addisson Wesley,NY, 1964).

Weight Reductions Generated by Bucking-Field Permanent Magnets

LAB REPORT ON SmCo RING MAGNET EXPERIMENTS



Experiments conducted by:
William C. Simpson

New Horizons Research 600 Meridian Street Extension,
#302 Groton, CT 06340
Tel. (860) 405-1157

The following experiments were conducted at the *Coastal Environmental Laboratory* (CEL) at Avery Point, Groton, Connecticut. (41° 19‘ 0.17" N. latitude x 72° 3‘ 50.27" W. longitude x 35 feet elevation above mean sea level) I wish to thank the personnelat the CEL for their generosity for providing the use of their *Mettler Toledo®* Model AG104 electronic scale for the measurements taken in the proceeding experiments. The AG104 electronic scale is an enclosed pan unit with a maximum mass range of 101-grams with 0.0001-gram readability.

The purpose of these experiments was to see if there is any detectable weight change when permanent magnets are forced together with their like-poles facing each other. The magnets were weighed individually, in both directions, with their field poles oriented vertically. The sums of the two individual magnet weights (magnet #1 and magnet #2) in each vertical orientation were compared to the weight measurements taken when they were assembled using the nylon bolt and wing nut depicted in **DIAGRAM 1**. The specifications for the two Samarium Cobalt magnets used in the following experiments are shown in **DIAGRAM 1**.

The first set of experiments with the SmCo Ring magnets were conducted January 14, 2002. An inverted paper cup was used to raise the test sample magnets 2.75" above the AG104 electronic scale pan in order to minimize possible magnetic interaction with the scale-sensing element, as depicted in **DIAGRAM 2**. The tare adjustment was used to set the scale readout to 0.0000-gram with the cup in place. The magnets were weighed individually. Magnet #1 weighed 9.9450-gram with the N pole facing up and 9.9397-gram with the S pole facing up. Magnet #2 weighed 9.9520-gram with the N pole facing up and 9.9443-gram with the S pole facing up.

The second set of experiments with the SmCo Ring magnets were conducted February 4, 2002. These experiments were shielded with Mu 80 magnetic

Editorial: This article is one more link between magnetizm and theory of aether, to my mind. It is possible to assume that in his experiments the author creates small but detectable changes in density of aether, that demonstrates itself as the weight changes.
Alexander V. Frolov.

DIAGRAM 1



RARE EARTH MAGNET SPECIFICATIONS:

Samarium Cobalt (SmCo mixed) ~ SCIENTIFICS Cat. #B30307-30
Ring type. OD = 0.75", ID = 0.43", Thickness = 0.25"
Gauss = 8,000
density = 8.7-gram/cc

NYLON RETAINER BOLT AND WING NUT:

3/8" diameter x 1-1/2" long hex-head nylon bolt
3/8" diameter nylon wingnut

mass of nylon bolt plus nylon wing nut = 5.1610-grams shielding material as depicted in **DIAGRAM 3**. The scale was tare adjusted to 0.0000-gram with the entire set of Mu 80 shield pieces in place. Then the magnets were weighed individually. Magnet #1 weighed 9.9483-gram with the N pole facing up and 9.9486-gram with the S pole facing up. Magnet #2 weighed 9.9527-gram with the N pole facing up and 9.9542-gram with the S pole facing up. The Nylon bolt and wing nut were placed in the Mu 80 shield can (without the magnets) and the scale was tare adjusted to 0.0000-gram. Therefore, the readouts would only be reading the weight of the bucking magnets.

The first column in **TABLE 1**, the vertical measurements, is the distance of separation d, or air gap, of the magnets. The second column shows the January 14, 2002 weight measurements of the two magnets, as shown in **DIAGRAM A**. The third column shows the January 14, 2002 weight measurements of the two magnets, as shown in **DIAGRAM B**. The fourth column shows the February 4, 2002 weight measurements of the two magnets, as shown in **DIAGRAM C**. The fifth column shows the February 4, 2002 weight measurements of the two magnets, as shown in **DIAGRAM D**.

The horizontal measurement, as depicted in **TABLE 2**, **TABLE 3**, **TABLE 4** and **TABLE 5**, are through the four basic magnetic compass headings; North, East, South, and West respectively. They are referenced to **DIAGRAM E** and **DIAGRAM F** for the January 14, 2002 experiments and **DIAGRAM G** and **DIAGRAM H** for the February 4, 2002 experiments. The corresponding graphs of the force change plots, **GRAPH 1**, **GRAPH 2**, **GRAPH 3**, **GRAPH 4**, and **GRAPH 5** accompany each table. The forces were converted from the mass readings, which are a scalar measurement, to dynes. The convention used for the force vector was chosen as plus (+) for up, or a weight reduction, and minus (-) for a weight increase.

DIAGRAM 2

01/14/2002 EXPERIMENNTS

CUP HEIGHT: 2.75" above scale pan. 1.75" upper diameter, 2.5" lower diameter



DIAGRAM 3

02/04/2002 EXPERIMENTS

MU METAL SPECIFICATIONS:

Source: NATIONAL ELECTRICAL ALLOYS
Oakland, NJ
SPECIFICATION: MIL N 14411C COMP 1
GRADE: HY MU 80 SHIELDING ALLOY
COLD ROLLED BRIGHT
DESCRIPTION: COIL
HEAT # 982011207
CHEMICAL ANALYSIS:
Ni: 80.16%
Mo: 4.6%
S: 0.0007%
C: 0.010%
P: 0.004%
Mn: 0.486%
Si: < 0.010%
Fe: BALANCE
MECHANICAL PROPERTIES:
HARDNESS: HV1 = 159
GRAIN SIZE: 8.5
COERCIVE STRENGTH:
HC = 0.0080 Oe
PERMEABILITY: MUMAX = 355000
SATURATION: 7900 Gauss
THICKNESS: 0.010"
DENSITY: 8.747-gram/cc



The can bottom lid was soldered to the can cylinder with 50/50 Sn/Pb solder and the overlapping cylinder seam was attached with epoxy.


DIAGRAM E
NOT TO SCALE
S N N S
d
#1
#2
COMPASS HEADING
PAPER CUP
SCALE PAN
DIAGRAM F
NOT TO SCALE
N S S N
d
#1
#2
COMPASS HEADING
PAPER CUP
SCALE PAN
DIAGRAM G
(CUT-AWAY VIEW)
NOT TO SCALE
NOTE: ALL MU 80 COMPONENTS ARE FABRICATED WITH 0.010" THICK STOCK.
MU 80 COVER
MU 80 CAN
S N N S
d
COMPASS HEADING
#1
#2
MU 80 DISK
SCALE PAN
DIAGRAM H
(CUT-AWAY VIEW)
NOT TO SCALE
NOTE: ALL MU 80 COMPONENTS ARE FABRICATED WITH 0.010" THICK STOCK.
MU 80 COVER
MU 80 CAN
N S S N
d
COMPASS HEADING
#1
#2
MU 80 DISK
SCALE PAN

ELEVATION VIEW OF THE VERTICAL EXPERIMENTS

NOTE:

January 14, 2002 Experiments: Start time: 13:27 hours EST, End time: 15:40 hours EST.

February 4, 2002 Experiments: Start time: 13:18 hours EST, End time: 14:50 hours EST.

TABLE 1:

	01/14/2002 EXPERIMENTS OPEN, WITH PAPER CUP		02/04/2002 EXPERIMENTS WITH MU 80 SHIELDING	
Air gap d	**Diagram A** N to N vertical 19.8893-gram (Sum of 1 & 2)*	**Diagram B** S to S vertical 19.8917-gram (Sum of 1 & 2)*	**Diagram C** N to N vertical 19.9025-gram (Sum of 1 & 2)*	**Diagram D** S to S vertical 19.9013-gram (Sum of 1 & 2)*
0.0 Inch	19.8759-gram 0.0134-gram weight reduction (0.06737%)	19.8757-gram 0.0160-gram weight reduction(0.08045%)	19.8760-gram 0.0265-gram weight reduction(0.13324%)	19.8758-gram 0.0255-gram weight reduction(0.12821%)
1/8 Inch	19.8761-gram 0.0132-gram weight reduction(0.06637%)	19.8751-gram 0.0166-gram weight reduction(0.08346%)	19.8760-gram 0.0265-gram weight reduction(0.13324%)	19.8763-gram 0.0250-gram weight reduction(0.12570%)
1/4 Inch	19.8763-gram 0.0130-gram weight reduction(0.06536%)	19.8748-gram 0.0169-gram weight reduction(0.08497%)	19.8760-gram 0.0265-gram weight reduction(0.13324%)	19.8768-gram 0.0245-gram weight reduction(0.12318%)
3/8 Inch	19.8765-gram 0.0128-gram weight reduction(0.06436%)	19.8753-gram 0.0164-gram weight reduction(0.08246%)	19.8760-gram 0.0265-gram weight reduction(0.13324%)	19.8777-gram 0.0236-gram weight reduction(0.11866%)
1/2 Inch	19.8774-gram 0.0119-gram weight reduction(0.05983%)	19.8753-gram 0.0164-gram weight reduction(0.08246%)	19.8757-gram 0.0268-gram weight reduction(0.13475%)	19.8809-gram 0.0204-gram weight reduction(0.10257%)
5/8 Inch	19.8776-gram 0.0117-gram weight reduction(0.05883%)	19.8754-gram 0.0163-gram weight reduction(0.08195%)	19.8779-gram 0.0246-gram weight reduction(0.12368%)	19.8806-gram 0.0207-gram weight reduction(0.10408%)
11/16 Inch	19.8777-gram 0.0116-gram weight reduction(0.05832%)	19.8748-gram 0.0169-gram weight reduction(0.08497%)	19.8773-gram 0.0252-gram weight reduction(0.12670%)	19.8832-gram 0.0181-gram weight reduction(0.09100%)

* Magnets #1 and #2 were individually weighed in the orientation used in each experiment and their separate weights were added together.

The following equation was used to calculate the weight changes, in dynes, in the proceeding graphs.

$$\overrightarrow{\Delta F} = k \cdot \Delta mass \cdot g$$

where

$$k = 980.665 \cdot dyne \cdot gm^{-1}$$

and

$$g = 9.80665\ m \cdot sec^{-2}$$

which is the local rate of gravitational acceleration.

The product of the measured changes in mass, Δmass, and g is denoted as follows on the graphs:

$$NNopen_{n,1} = \Delta mass \cdot g$$

for N-to-N pole facings in the open (or unshielded).

$$SSopen_{n,1} = \Delta mass \cdot g$$

for S-to-S pole facings in the open (or unshielded).

$$NNshield_{p,1} = \Delta mass \cdot g$$

for N-to-N pole facings shielded with Mu 80 shielding.

$$SSshield_{p,1} = \Delta mass \cdot g$$

for S-to-S pole facings shielded with Mu 80 shielding. In the subscripts, $_n$ and $_p$ refers to the respective number of data points per plot. The subscript $_1$ refers to the vertical change in force (weight change) axis and $_0$ refers to the horizontal distance d axis. In **GRAPH 1**, $_n = {}_p$.

GRAPH 1:



ISOMETRIC AND ELEVATION VIEW OF THE HORIZONTAL EXPERIMENTS


DIAGRAM E
NOT TO SCALE
S N
N S
d
#1
#2
COMPASS HEADING
PAPER CUP
SCALE PAN


DIAGRAM F
NOT TO SCALE
N S
S N
d
#1
#2
COMPASS HEADING
PAPER CUP
SCALE PAN


DIAGRAM G
(CUT-AWAY VIEW)
NOT TO SCALE
NOTE: ALL MU 80 COMPONENTS ARE FABRICATED WITH 0.010" THICK STOCK.
MU 80 COVER
MU 80 CAN
S N
N S
d
#1
#2
COMPASS HEADING
MU 80 DISK
SCALE PAN


DIAGRAM H
(CUT-AWAY VIEW)
NOT TO SCALE
NOTE: ALL MU 80 COMPONENTS ARE FABRICATED WITH 0.010" THICK STOCK.
MU 80 COVER
MU 80 CAN
N S
S N
d
#1
#2
COMPASS HEADING
MU 80 DISK
SCALE PAN

MAGNETIC DECLINATION FROM THE LOCAL TOPOLOGICAL MAP:



1984 Magnetic Declination~ U. S. Geological Survey
New London, Connecticut Quadrangle Topological Map

TABLE 2

North # **Heading**	01/14/2002 EXPERIMENTS OPEN, WITH PAPER CUP		02/04/2002 EXPERIMENTS WITH MU 80 SHIELDING	
Air gap d	**Diagram E** N to N horizontal 19.8905-gram (Sum of 1 & 2)*	**Diagram F** S to S horizontal 19.8905-gram (Sum of 1 & 2)*	**Diagram G** N to N horizontal 19.9019-gram (Sum of 1 & 2)*	**Diagram H** S to S horizontal 19.9019-gram (Sum of 1 & 2)*
0.0 Inch	19.8735-gram 0.0170-gram weight reduction (0.08547%)	19.8778-gram 0.0127-gram weight reduction(0.06385%)	19.8890-gram 0.0129-gram weight reduction(0.06479%)	19.8810-gram 0.0209-gram weight reduction(0.10497%)
1/8 Inch	19.8728-gram 0.0177-gram weight reduction(0.08899%)	19.8790-gram 0.0115-gram weight reduction(0.05782%)	N/A **	N/A **
1/4 Inch	19.8721-gram 0.0184-gram weight reduction(0.09251%)	19.8798-gram 0.0107-gram weight reduction(0.05379%)	N/A **	N/A **
3/8 Inch	19.8705-gram 0.0200-gram weight reduction(0.10055%)	19.8800-gram 0.0105-gram weight reduction(0.05279%)	N/A **	N/A **
1/2 Inch	19.8698-gram 0.0207-gram weight reduction(0.10407%)	19.8811-gram 0.0094-gram weight reduction(0.04726%)	N/A **	N/A **
5/8 Inch	19.8693-gram 0.0212-gram weight reduction(0.10658%)	19.8818-gram 0.0087-gram weight reduction(0.04374%)	N/A **	N/A **
11/16 Inch	19.8696-gram 0.0209-gram weight reduction(0.10508%)	19.8827-gram 0.0078-gram weight reduction(0.03921%)	19.9190-gram 0.0171-gram weight increase(0.08588%)	19.9029-gram 0.0010-gram weight increase(0.00502%)

Compass Heading is approximate

* Magnets #1 and #2 were individually weighed with pole faces oriented vertically, with N up then with S up, and the results were averaged and added.

** Due to time constraints, these measurements were not taken.

GRAPH 2:



NOTE:
The calculated mass of each magnet was determined by the following formula based upon the manufacturer's dimensions and density value.

$$\mathrm{volume} := \pi \cdot \left[\left(\frac{0.75 \cdot \mathrm{in}}{2} \right)^2 - \left(\frac{0.43 \cdot \mathrm{in}}{2} \right)^2 \right] \cdot \left(\frac{1}{4} \right) \cdot \mathrm{in}$$

$$\mathrm{volume} = 1.214963\ \mathrm{cm}^3$$

$$\mathrm{density} = 8.7 \cdot \mathrm{gm} \cdot \mathrm{cm}^{-3}$$

$$\mathrm{mass} = \mathrm{density} \cdot \mathrm{volume}$$

$$\mathrm{mass} = 10.570177\ \mathrm{gm.}$$

This is higher than the magnetized mass of each magnet.

However, some tables give a lower density for the SmCo magnet, 0.300lb/in^3, which equals:

$$\mathrm{density} = 8.303971 \cdot \mathrm{gm} \cdot \mathrm{cm}^{-3}$$

$$\mathrm{mass} = 10.089017\ \mathrm{gm.}\ .$$

This is still higher than the magnetized mass of each magnet. Does the SmCo material become slightly lighter in weight when it is magnetized?

TABLE 3

East # **Heading**	01/14/2002 EXPERIMENTS OPEN, WITH PAPER CUP		02/04/2002 EXPERIMENTS WITH MU 80 SHIELDING	
Air gap D	**Diagram E** N to N horizontal 19.8905-gram (Sum of 1 & 2)*	**Diagram F** S to S horizontal 19.8905-gram (Sum of 1 & 2)*	**Diagram G** N to N horizontal 19.9019-gram (Sum of 1 & 2)*	**Diagram H** S to S horizontal 19.9019-gram (Sum of 1 & 2)*
0.0 Inch	19.8763-gram 0.0142-gram weight reduction (0.07139%)	19.8755-gram 0.0150-gram weight reduction(0.07541%)	19.8928-gram 0.0091-gram weight reduction(0.04570%)	19.8731-gram 0.0288-gram weight reduction(0.14464%)
1/8 Inch	19.8777-gram 0.0128-gram weight reduction(0.06435%)	19.8750-gram 0.0155-gram weight reduction(0.07793%)	N/A **	N/A **
1/4 Inch	19.8782-gram 0.0123-gram weight reduction(0.06184%)	19.8743-gram 0.0162-gram weight reduction(0.08145%)	N/A **	N/A **
3/8 Inch	19.8779-gram 0.0126-gram weight reduction(0.06335%)	19.8722-gram 0.0183-gram weight reduction(0.09200%)	N/A **	N/A **
1/2 Inch	19.8792-gram 0.0113-gram weight reduction(0.05681%)	19.8715-gram 0.0190-gram weight reduction(0.09552%)	N/A **	N/A **
5/8 Inch	19.8814-gram 0.0091-gram weight reduction(0.04575%)	19.8712-gram 0.0193-gram weight reduction(0.09703%)	N/A **	N/A **
11/16 Inch	19.8815-gram 0.0090-gram weight reduction(0.04525%)	19.8720-gram 0.0185-gram weight reduction(0.09301%)	19.9338-gram 0.0319-gram weight increase(0.16021%)	19.9030-gram 0.0011-gram weight increase(0.00552%)

Compass Heading is approximate
* Magnets #1 and #2 were individually weighed with pole faces oriented vertically, with N up then with S up, and the results were averaged and added.
** Due to time constraints, these measurements were not taken.

GRAPH 3:



TABLE 4

East # **Heading**	01/14/2002 EXPERIMENTS OPEN, WITH PAPER CUP		02/04/2002 EXPERIMENTS WITH MU 80 SHIELDING	
Air gap D	**Diagram E** N to N horizontal 19.8905-gram (Sum of 1 & 2)*	**Diagram F** S to S horizontal 19.8905-gram (Sum of 1 & 2)*	**Diagram G** N to N horizontal 19.9019-gram (Sum of 1 & 2)*	**Diagram H** S to S horizontal 19.9019-gram (Sum of 1 & 2)*
0.0 Inch	19.8746-gram 0.0159-gram weight reduction (0.07994%)	19.8769-gram 0.0136-gram weight reduction(0.06837%)	19.8896-gram 0.0123-gram weight reduction(0.06178%)	19.8660-gram 0.0359-gram weight reduction(0.18030%)
1/8 Inch	19.8720-gram 0.0185-gram weight reduction(0.09301%)	19.8788-gram 0.0117-gram weight reduction(0.05882%)	N/A **	N/A **
1/4 Inch	19.8709-gram 0.0196-gram weight reduction(0.09854%)	19.8797-gram 0.0108-gram weight reduction(0.05430%)	N/A **	N/A **
3/8 Inch	19.8704-gram 0.0201-gram weight reduction(0.10105%)	19.8803-gram 0.0102-gram weight reduction(0.05128%)	N/A **	N/A **
1/2 Inch	19.8711-gram 0.0194-gram weight reduction(0.09753%)	19.8814-gram 0.0091-gram weight reduction(0.04575%)	N/A **	N/A **
5/8 Inch	19.8698-gram 0.0207-gram weight reduction(0.10407%)	19.8825-gram 0.0080-gram weight reduction(0.04022%)	N/A **	N/A **
11/16 Inch	19.8703-gram 0.0202-gram weight reduction(0.10156%)	19.8817-gram 0.0088-gram weight reduction(0.04424%)	19.9423-gram 0.0404-gram weight increase(0.20290%)	19.8810-gram 0.0209-gram weight reduction(0.10497%)

Compass Heading is approximate

* Magnets #1 and #2 were individually weighed with pole faces oriented vertically, with N up then with S up, and the results were averaged and added.

** Due to time constraints, these measurements were not taken.

GRAPH 4:



TABLE 5

West # **Heading**	01/14/2002 EXPERIMENTS OPEN, WITH PAPER CUP		02/04/2002 EXPERIMENTS WITH MU 80 SHIELDING	
Air gap D	**Diagram E** N to N horizontal 19.8905-gram (Sum of 1 & 2)*	**Diagram F** S to S horizontal 19.8905-gram (Sum of 1 & 2)*	**Diagram G** N to N horizontal 19.9019-gram (Sum of 1 & 2)*	**Diagram H** S to S horizontal 19.9019-gram (Sum of 1 & 2)*
0.0 Inch	19.8777-gram 0.0128-gram weight reduction (0.06787%)	19.8748-gram 0.0157-gram weight reduction(0.07893%)	19.8933-gram 0.0086-gram weight reduction(0.04319%)	19.8724-gram 0.0295-gram weight reduction(0.14816%)
1/8 Inch	19.8767-gram 0.0138-gram weight reduction(0.06938%)	19.8737-gram 0.0168-gram weight reduction(0.08446%)	N/A **	N/A **
1/4 Inch	19.8777-gram 0.0128-gram weight reduction(0.06435%)	19.8733-gram 0.0172-gram weight reduction(0.08647%)	N/A **	N/A **
3/8 Inch	19.8783-gram 0.0122-gram weight reduction(0.06134%)	19.8727-gram 0.0178-gram weight reduction(0.08949%)	N/A **	N/A **
1/2 Inch	19.8806-gram 0.0099-gram weight reduction(0.04977%)	19.8722-gram 0.0183-gram weight reduction(0.09200%)	N/A **	N/A **
5/8 Inch	19.8811-gram 0.0094-gram weight reduction(0.04726%)	19.8715-gram 0.0190-gram weight reduction(0.09552%)	N/A **	N/A **
11/16 Inch	19.8803-gram 0.0102-gram weight reduction(0.05128%)	19.8723-gram 0.0182-gram weight reduction(0.09150%)	19.9427-gram 0.0408-gram weight increase(0.20491%)	19.8976-gram 0.0043-gram weight reduction(0.02160%)

Compass Heading is approximate

* Magnets #1 and #2 were individually weighed with pole faces oriented vertically, with N up then with S up, and the results were averaged and added.

** Due to time constraints, these measurements were not taken.

GRAPH 5:



RING MAGNET #1, N UP: 9.9483-grams
RING MAGNET #2, N UP: +9.9527-grams
TOTAL WEIGHT: 19.9010-grams
WEIGHT INCREASE WITH OPPOSITE POLES ATTRACTING, AS DEPICTED IN **DIAGRAM I**, IN MU 80 SHIELD where 19.9861-grams was the measured value:
19.9861-grams – 19.9010-grams = 0.0851-gram weight increase.


DIAGRAM I
(CUT-AWAY VIEW) NOT TO SCALE
NOTE: ALL MU 80 COMPONENTS ARE FABRICATED WITH 0.010" THICK STOCK.
MU 80 COVER
MU 80 CAN
MU 80 DISK
SCALE PAN
N
S
N
S
#2
#1
S
N
S
N

THREE RIVERS COMMUNITY COLLEGE, THAMES VALLEY CAMPUS LAB REPORT ON SmCo RING MAGNET EXPERIMENTS

The following experiments were conducted at the *Thames Valley Campus* (TVC) of the *Three Rivers Community College*, Room #207 Chemistry Laboratory, in Norwich, Connecticut on March 8, 2002. (41° 30' 34.62" N. latitude x 72° 6' 13.63" W. longitude x 115 feet elevation above mean sea level) I wish to thank the instructors at *Three Rivers* for their generosity for providing the use of their *Sartorius*® Model # 2442 analytical balance for the measurements taken in the proceeding experiments. The *Sartorius* Model # 2442 analytical balance is an enclosed pan unit with a maximum mass range of 200-grams with 0.0001-gram micrometer readability and a precision of 0.05-mg standard deviation.

The purpose of these experiments was to compare the Avery Point vertical measurements conducted on the *Mettler Toledo*® Model AG104 electronic scale, in **TABLE 1**, with the *Sartorius* Model # 2442 analytical balance measurements recorded in **TABLE 6**. The same two Samarium Cobalt magnets (magnet #1 and magnet #2) weighed individually in each vertical orientation were compared to the weight measurements taken when they were assembled using the nylon bolt and wing nut depicted in **DIAGRAM 1**. The specifications for the two Samarium Cobalt magnets used in the following experiments are shown in **DIAGRAM 1**.

The first column in **TABLE 6**, the vertical measurements, is the distance of separation d, or air gap, of the magnets. The second column shows the weight measurements of the two magnets, as shown in **DIAGRAM A**. The third column shows the weight measurements of the two magnets, as shown in **DIAGRAM B**. An inverted paper cup was used to raise the test sample magnets 2.75" above the *Sartorius* Model # 2442 balance scale pan in order to minimize possible magnetic interaction with the balance, as depicted in **DIAGRAM 2**. The fourth column shows the weight measurements of the two magnets, as shown in **DIAGRAM C**. The fifth column shows the weight measurements of the two magnets, as shown in **DIAGRAM D**. These experiments were shielded with

Mu 80 magnetic shielding material as depicted in **DIAGRAM 3**. The resultant data of **TABLE 6** is plotted on **GRAPH 6**. The results of the previous experiments at *Avery Point*, from **GRAPH 1**, and the recent *Thames Valley* experiments, from **GRAPH 6**, are plotted on **GRAPH 7** for comparison. The Mu 80 magnetically shielded experiments on the *Sartorius* Model # 2442 analytical balance at *Thames Valley* are in close agreement with the data collected with the AG104 electronic scale at Avery Point. However, the *Thames Valley* data collected for the unshielded experiments is somewhat smaller in weight reduction. I attribute this to external interference. The *Thames Valley* setup included a nonferrous tabletop, as did the Avery Point setup. However, the *Thames Valley* balance table consisted of a steel frame and legs, which may have altered the readings. The Mu 80 shielding provided a more intrinsic method for accurate data collection.

The horizontal measurements were not taken in this set of experiments due to time constraints. A final experiment was attempted to replicate the relative weight increase with the opposite poles of the ring magnets "stuck" together, as depicted in **DIAGRAM I**; however, the magnets shattered during assembly!

TABLE 6

	03/08/2002 TRCC EXPERIMENTS, @ TVC: OPEN, WITH PAPER CUP		03/08/2002 TRCC EXPERIMENTS, @ TVC: WITH MU 80 SHIELDING	
Air gap d	**Diagram A** N to N vertical 19.8734-gram (Sum of 1 & 2)*	**Diagram B** S to S vertical 19.8726-gram (Sum of 1 & 2)*	**Diagram C** N to N vertical 19.8912-gram (Sum of 1 & 2)*	**Diagram D** S to S vertical 19.8929-gram (Sum of 1 & 2)*
0.0 Inch	19.8699-gram 0.0035-gram weight reduction (0.01761%)	19.8696-gram 0.0030-gram weight reduction(0.01510%)	19.8691-gram 0.0221-gram weight reduction(0.11110%)	19.8706-gram 0.0223-gram weight reduction(0.11210%)
1/8 Inch	19.8699-gram 0.0035-gram weight reduction(0.01761%)	19.8699-gram 0.0027-gram weight reduction(0.01359%)	19.8688-gram 0.0224-gram weight reduction(0.11261%)	19.8707-gram 0.0222-gram weight reduction(0.11160%)
1/4 Inch	19.8695-gram 0.0039-gram weight reduction(0.01962%)	19.8695-gram 0.0031-gram weight reduction(0.01560%)	19.8687-gram 0.0225-gram weight reduction(0.11312%)	19.8712-gram 0.0217-gram weight reduction(0.10908%)
3/8 Inch	19.8695-gram 0.0039-gram weight reduction(0.01962%)	19.8699-gram 0.0027-gram weight reduction(0.01359%)	19.8692-gram 0.0220-gram weight reduction(0.11060%)	19.8730-gram 0.0199-gram weight reduction(0.10004%)
1/2 Inch	19.8689-gram 0.0045-gram weight reduction(0.02264%)	19.8699-gram 0.0027-gram weight reduction(0.01359%)	19.8695-gram 0.0217-gram weight reduction(0.10909%)	19.8738-gram 0.0191-gram weight reduction(0.09601%)
5/8 Inch	19.8686-gram 0.0048-gram weight reduction(0.02415%)	19.8699-gram 0.0027-gram weight reduction(0.01359%)	19.8702-gram 0.0210-gram weight reduction(0.10557%)	19.8746-gram 0.0183-gram weight reduction(0.09199%)
11/16 Inch	19.8680-gram 0.0054-gram weight reduction(0.02717%)	19.8699-gram 0.0027-gram weight reduction(0.01359%)	19.8707-gram 0.0205-gram weight reduction(0.10306%)	19.8756-gram 0.0173-gram weight reduction(0.08697%)

* Magnets #1 and #2 were individually weighed in the orientation used in each experiment and their separate weights were added together.

NOTE:
March 8, 2002 Experiments: Start time: 12:12 hours EST, End time: 13:47 hours EST.

GRAPH 6:



MAGNETIC DECLINATION FROM THE LOCAL TOPOLOGICAL MAP



1983 Magnetic Declination~ U. S. Geological Survey Norwich, Connecticut Quadrangle Topological Map

GRAPH 7:



KEY TO **GRAPH 7**:

For N-to-N pole facings in the open (or unshielded) at Avery Point (AP):
NNopenAP
For S-to-S pole facings in the open (or unshielded) at Avery Point (AP):
SSopenAP
For N-to-N pole facings shielded with Mu 80 shielding at Avery Point (AP):
NNshieldAP
For S-to-S pole facings shielded with Mu 80 shielding at Avery Point (AP):
SSshieldAP
For N-to-N pole facings in the open (or unshielded) at Thames Valley (TV):
NNopenTV
For S-to-S pole facings in the open (or unshielded) at Thames Valley (TV):
SSopenTV
For N-to-N pole facings shielded with Mu 80 shielding at Thames Valley (TV):
NNshieldTV
For S-to-S pole facings shielded with Mu 80 shielding at Thames Valley (TV):
SSshieldTV

The subscripts for the data points $_n = _p = _q = _r = 7$ are all the same value in **GRAPH 7**.

Advanced Nuclear Waste Decontamination Technologies

Mark Porringa

Zeropoint Techtonix Inc, 430 Bass Lake Road, R R # 1,
Deep River, Ontario K0J 1P0, Canada
(613) 584-2960 fax: (613) 584-4616 porringam@aecl.ca

It is a review of nine alternative, peer-reviewed techniques as candidates for the global clean-up of nuclear waste.

The following is a reasonably comprehensive list of potentially effective nuclear waste treatment methods that might be employed to treat the entire range of radioactive wastes that have proven to be such a daunting and horrendously expensive problem for the nuclear industry (in all its forms) with major, long term implications for the environment.

A wide variety of methods will probably be required to accommodate the many different radioactive waste sources including high and low level, solids, liquids and gases. Process names used here are in some cases just convenient labels used to categorize and set them apart from each other.

Theories on several of these processes are still quite speculative and solid evidence that would pass conventional peer review is still lacking. This is after all a very new field of science.

Some of these technologies are already well protected by international or national patents, with additional US and international patents pending, and further patents may be obtained on new developments as they are made.

The Brown's Gas-Metal Matrix Process:

The BG-MMX process utilizes a patented electrolysis cell of the Australian Prof. **Yull Brown**'s design that is said to produce a stoichiometric mixture of monatomic hydrogen and oxygen or possibly a quasi-stable water molecule raised to a high-energy state. This gas has some very peculiar properties including the ability to sublimate tungsten (6000°C) with an implosive flame that burns cool in air with a temperature of only 130°C.

The gas is used to heat a proprietary mixture of metals and/or metal oxides including the radwaste to be neutralized. A highly exothermic radiant reaction appears to result in the immediate reduction of radioactivity approaching 95% of the original levels judging from preliminary tests, within seconds of treatment. The process is conjectured to be effective with high level solid wastes and possibly gasses, but probably not liquids. The high temperatures involved may also preclude the processing of more volatile wastes.

Since 1991, this technology has been successfully demonstrated, on a small scale, at least 50 times to US, Chinese, Japanese and United Kingdom officials on a variety of nuclear waste products including Americium, Cobalt, Uranium, and Plutonium. The technique can be applied for the immediate decontamination of stockpiles of nuclear waste materials being held near nuclear power plants. The process is very simple, safe, and inexpensive to develop further into robotics application for on-site treatment with no foreseen environmental effects.

Photoremediation

The *Photoremediation* process of the American Dr. **Paul Brown** is essentially conventional physics, *albeit* applied in a new and novel way. The process involves the use of a high-energy electron beam impinged on a target, which in turn produces a monochromatic gamma radiation that is tuned to induce *Photofission* and *Photoneutron* reactions in the target material causing rapid neutralization of radioactive isotopes. The efficiency claimed exceeds 500% due to the high cross-section reactions in the Giant Dipole Resonance region. The 10 MeV electron beam produces typical fission reactions in the 200MeV range effectively turning high level solid wastes such as spent fuel into an energy source. The process is apparently intended for on-site treatment with some waste-partitioning required, an aspect which may not be desirable in certain countries.

While this idea is similar in topology to a system being developed by **Los Alamos National Labs**, Dr. Paul Brown's approach offers several advantages: no need for extensive chemical pre-processing and the energy required to effect transmutation is greatly reduced. No new technology needs to be developed, yet the engineering of such a photon reactor must be completed and it could itself become a practical method for generating power.

ZIPP Fusion

The ZIPP fusion process, identified by **Mark Porringa**, induces a wide variety of fusion reactions, resulting from the radial compression of individual diatomic and other simple molecules dissolved or suspended in a light water, carbon arc electrolysis cell. A variety of other cell configurations are envisioned.

The process appears to produce only stable isotopes, which should therefore make it capable of stabilizing a wide variety of radioactive waste materials. The theory on the process draws from Condensed Charge phenomena, Brown's Gas implosion, cavitation bubble collapse and sonoluminesence - all variations of the Casimir effect - which is believed to cohere the Zero-point energy of Quantum Vacuum Fluctuations. Transmutations using variations of this basic process may be applicable to a wide variety of nuclear wastes and appears capable of operating with an efficiency exceeding 100%.

A major implication of this process is that the Strong force of the nucleus is understood as an ultra close range Casimir effect. **Oakridge** Nuclear Laboratories in the US in conjunction with several international collaborators have just (this month, in fact) announced a deuterium cold fusion process based on the essential elements of the ZIPP Fusion process first reported in 1998. The process is very simple and inexpensive to develop.

RIPPLE Fission

The RIPPLE Fission process is an adaptation of existing potential technology utilizing a supersonic ionized gas to aerosol a counter flow heat exchanger that envelopes the radioactive waste aerosol in a vacuum induced plasma vortex which appears to disrupt the matter stabilizing influence of the Quantum Vacuum fluctuations resulting in "gentle" low recoil fission reactions which produce only stable fission products, with excess neutrons being prompt converted to protons via quenched Beta emissions. The process is apparently proven with conventional non-radioactive wastes and is believed applicable to the entire spectrum of radwaste without the need for waste partitioning. This process is also conjectured to operate with over-unity efficiency.

The LENTEC Processes

The Low Energy Nuclear Transmutation Electrolytic Cells of the Cincinnati group produce a variety of transmutation reactions using a variety of exotic electrolysis cell designs that generally produce condensed charge clusters composed primarily of up to 10^{11} electrons each. These electron charge clusters produced with the use of special electrodes can penetrate the nuclei of larger atoms in solution and transmute these atoms into stable elements.

The range of design and operating protocols and potential applications are essentially limitless provided for the waste that is dispersed in the electrolyte. The reported transmutation of thorium to stable titanium and copper by the Cincinnati Group and by the Salt Lake City group is one of the most dramatic examples of this type of treatment process. Application to other high-level liquid transuranic fissionable wastes such as surplus Plutonium seems likely. The glaring absence of normal fission yield energies is perplexing but probably explicable as another form of low recoil fission reaction, similar to RIPPLE fission.

The Plasma Induced/Injected Transmutation - PIT Processes (also known as HDCC)

Plasma Induced/Injected Transmutation processes run include a gamut from recent achievements dating back to the **Oshawa-Kushi** cold plasma transmutations reported in 1964. The patented high-density charge cluster process (HDCC) was first discovered by **Kenneth Shoulders** and added on to by **Harold E. Puthoff**. Later, the late **Stan Gleeson** discovered HDCC in properly processed solutions. Still later, **Alexander Ilyanok** of Belarus discovered HDCC, followed by **Vasiliy Baraboskin** in Russia.

The production of Condensed Charge Clusters and various plasma glow discharge phenomena in a variety of gaseous atmospheres is again implicated as the underlying cause with what should be by now an obvious connection with the coherence of Zero-point energy from the Quantum or Stochastic vacuum.

Desk-top high energy particle accelerators have also been envisioned, based on the "piggy back" principle, in which the clusters permit acceleration of "piggy-backed" heaver +ions to extremely high energies capable of causing fusion and transmutations in target materials including those in solution and the materials of which the electrodes are composed. Brown's Gas implosion and cavitation bubble collapse reactions are also believed to be prevalent in these types of cells due to the prevalence of electrolysis.

A high-density charge cluster technology was discovered and used by Stan Gleeson to stabilize radioactive liquid wastes and has been developed further in the last 4 years by a group led by **S-X Jin** and **Hal Fox**. Best results for radioactive liquids have been demonstrated in the processing of thorium for a 30-minute period and achieving a reduction of radioactivity of about 90% from a liquid sample.

Kervran Reactions

The very compelling evidence compiled by French Nobel Candidate Dr. **Louis Kervran** has identified a wide range of nuclear transmutations in biological systems that have not been adequately explained. Coherence of Zero-point energy via Casimir effects within the *Somatid* particles identified by the Canadian **Gaston Naessens** is implicated as a possible cause. A wide variety of *in vitro* and *in vivo* reactions are believed to be possible as proven in nature and numerous experiments typically involving a reaction medium composed of a dielectric fluid such as water. Highly radiation resistant microorganisms have been found thriving in the core of nuclear reactors indicating the possibility of microorganisms being capable of transmuting some bioactive nuclear wastes in the course of the normal metabolism of such organisms.

The Monti Process

The Italian **Roberto A. Monti's** process involves confined explosions involving proprietary mixtures of materials that include radioactive waste. Ignition of such mixtures causes nuclear transmutations resulting in reduced radioactivity (to near-background levels) following combustion, gradually over 1 to 4 days.

This technique has been confirmed by the Italian **ENEA** and is supported by the French CEA scientists as a serious candidate for treatment of waste stockpiles. The system, as currently designed, required waste to be inserted into a chamber.

Higher group symmetry electrodynamics

Extremely weak, non-classical, higher group symmetry electromagnetic fields were found during a 1991 experiment made by **Glen Rein** to alter significantly the level of radioactivity in materials, even those in the environment. The experiments suggest that higher group symmetry electrodynamics modulate the quantitative and /or qualitative properties of radioactive species. If the non-classical fields directly affect the radioactive species, it is likely that the appropriate field parameters will be discovered to neutralize radioactive emissions. In 1999, a theoretical basis for the phenomenon was developed by the Welsh physicist, **M. W. Evans**, with the participation of Lt. Col. (retired) **Thomas E. Bearden**.

The technology is extremely simple and could be applied with minimum logistics for treating massive structures, *in-to* outdoors, such as the Chernobyl disaster site.

Psitronics Group Systems, International

Robert "Paul" LeBreton, 2901 Hwy. 6, HC 77 Box 42, Laguna, NM 87026 USA

E-mail: wizzard9@earthlink.net Phone:1-(505)-836-7534

Psi/Group's Magnetic Motor - Funding for New Prototype Sought:

As the engineer who designed the self-sustaining magnetic motor being advertised by Psitronics Group Systems, International. It perhaps falls upon me to explain (as well as I am able) the methods used by me in this motor's design:

The actual "picture" description is totally Intellectual Property; Protected as a Trade Secret.

However: This magnetic motor is a "perpetually imbalanced configuration" of permanent magnets; an unequal number of magnets on the rotor & stator; that revolves in a "self-sustaining" manner as the magnets seek balance... There are no electrical components in the design unless one wished to insert alternator windings in the stator to provide an electrical output...

We have discovered: through a prior unsuccessful prototype that using a para-magnetic material (we used aluminum) for the rotor & stator was self-defeating; as with the powerful rare earth magnets used in the design aluminum destroyed the magnetic fields... On further analysis of the failed prototype it was deduced that a "latch up" condition would occur between rotor & stator magnets; unless the rotor magnets were canted or skewed at an angle from the stator magnets... The plastic prototype contemplated corrects both of these problems....

We are seeking an investor willing to put up $4000 (DUS) for the prototype and who can offer $40,000 return on investment "if it proves successful" ...We have a Global Distribution 'ready to go" as well as a pledge of $ Millions towards Manufacturing & Marketing from EarthTech, International on submission of a running motor...

Very Respectfully Yours,
Paul LeBreton

http://home.earthlink.net/~wizzard9
(Psi/Group Website)

Inquiries should be emailed to:
wizzard9@earthlink.net

Experimental Investigations of the Radioactive Isotope Half-Value Period Changing in the Local Volume of Cause-Effect Relations

Igor A. Melnik

Pr.Frunze 232, Tomsk, 634021, Russia, Ph. (3822) 244555
breg@mail.ru

Nuclear-design methods of the elemental analysis are based on the property of the radioactive isotope decay rate constant. Half period as a constant quantity is defined by the time feature (the time flow is uniform in the every space point). The given postulate is confirmed by the long-term results and raised no doubts. But in last years some researches, investigating enough fine effects by change of the registered radiation intensivity, came to the conclusion about influence of space cycles on the time flow [1]. In his turn, N. A. Kozyrev during the investigation of active physical properties of time came to the conclusion about violation of its uniform flow in the local volume of the cause-effect relations, created by the cyclic motion (rotation, oscillation) of bodies [2,3,4].

Thus, the author get an idea to use a radioactive isotope cezium-137 as a “sensor”, measuring the changes of time flow uniformity in the certain local volume of cause-effect relations. In basis there are following arguments: owing to a conception of time uniformity and considerable cezium-137 half-value period, the source activity must be permanent during the experiment time. By the time flow (period) change, i.e. changes of uniformity in the local volume of cause-effect relations, the half-value period – T is changing in the direct proportion. Source activity, respectively, is changing in the inverse proportion according to the law exp (1/T) in relation to the external space volume. Hence, registered gamma-quantum intension (amplitude impulse distribution) in the absence of the cause-effect relations is proportional to the function $N_0 \sim \exp(\ln 2/T_0)$. Then the proportion $N_0/\Delta N$, where $\Delta N = N_0 - N$ is made, and by means of it a half-value period difference is defined by the formula

$$1/\Delta T = \left| 1/T_0 + \ln(\Delta N/N_0)/\ln 2 \right| \qquad (1)$$

N_0 – selective average amplitudes of impulses at the case of static liquid (in the absence of the cause-effect relations);
N - selective average amplitudes of impulses at the case of rotation of liquid.

In this case, there were investigations of the determination of the gamma-quantum intension change (i.e. change of a half-value period) dependence on the angular velocity of the activator rotation, and also on the coordinates location and amount of cause-effect relations (Fig. 1).



Fig.1

The following devices were used as measurement equipment: semi-conducting detector (SCD-63V) (1), preamplifier (PAG-2K), amplifier (BAI-3K) and analyzer (AMA-02F1). Energy gamma-line of 662 KeV was measured with the resolution 4 KeV. The gamma-quantum source was glued to the detector housing at the distance of 100 mm from its surface; so, any spatial change through coordinate axes was executed together with the detector to avoid even a tiny change of the source-detector geometry.

The vessel with a liquid (2) was placed above the source (6), vortex fluid motion was created by an activator (5), placed on the rod of electric motor (3). The glass with a liquid, connected with the motor and frame (4), was displaced regarding to the center of the revolved activator, what was the reason of the glass vibration in horizontal line, and, hence, one of frame sides vibration in vertical line (v). In its base, the frame was a square with the side of 200 mm. To assign the direction of the space cause-effect relations, one of frame sides was vibrating, and the opposite one (on the X axis) was fixed on the table (7). An experiment was made in such a way, that vibrating parts did not adjoin with the detector. The radius of glass is 50 mm, the distance from central axis up to the vibrating frame part is 100 mm. N-selection of the every value on the diagram (Fig. 2) corresponded to twenty measurements, roots from the average variance of numbers distribution $D \approx 160$ impulses.



Fig. 2
Dependence of photopeak-N area from the angular velocity of rotation – W, where 1 – is photopeak area at static liquid, 2 – is photopeak area at clockwise rotation, 3 – is photopeak area at anticlockwise rotation

During two months eighteen experiments were made (at the one geometry) of the given effect fluctuation study, and there were no considerable deviation. An effect of the time deceleration always appeared at the angular speed of the activator rotation W=3780 r/min (during the vibration of the whole perimeter of the frame base). If there was a vibration on the only one side of the frame base (on the X axis), then this effect appeared at the higher speed of rotation. Unfortunately, the maximum motor speed of rotation W_{max}=4880 r/min did not let to define the precise position for the next rotation point. During the experimental results extrapolation $W_2 \approx 5930$ r/min ($W_2 \approx \pi W/2$) was obtained.

In the table there are selective middle amplitudes of impulses -$N = \sum N_n/n$ roots from the numbers distribution average variance D, dispersion of the simple average G at the different directions of the liquid rotation (for the rotation point W=3780 r/min). The half period is estimated by the equation (1) and formula $T = T_0 + \Delta T$ where T_0=30.2 year (the cezium-137 half-value period).

Liquid motion	N, imp.	D	G	T, year
Static liquid	16304.0	160.7	35.9	30.200
Clockwise	15696.0	162.0	36.2	30.412
Anticlockwise	15553.0	165.0	36.9	30.423

During the investigation of the activator angular speed of rotation dependence on the registered gamma-quantum intension, **there was discovered the time deceleration effect in the fixed point of ambient space of the glass with the liquid.** The effect was versatile, during the further study of the reasons of the effect disappearance, the following regularities were found:

1. Intension change appeared only at the case of asymmetrically fixed glass, when there appeared horizontal oscillations, transmitted to the vertical oscillations of the frame;
2. An effect disappeared, if the gamma-quantum source was placed in the glass center (~ 2 ÷ 3 mm down from the glass bottom);
3. At the same speed of rotation but without liquid, with an eccentric activator, the time deceleration effect disappeared.

Will consider the system with liquid, its internal chain consisted of three cause-effect relations:

1. Activator-liquid;
2. Liquid-glass (frame);
3. Frame-table.

Glass oscillations were transmitted to the frame through the hard cohesion. There was only one cause-effect relation – an activator (a frame) – a table. Thus, amplitude of the time flow changing was, most likely, influenced on by the amount of cause-effect relation, and also, there was observed a quantum effect, dependent on the activator and liquid rotation frequency.

The time deceleration maximum amplitude appeared during the source displacement from the central axis of glass along the X coordinate to the distance ~ 5 mm. There appeared the necessity to check the given effect on space points along the all coordinate axes in the radius R ≈ 100 mm from the central point of the glass bottom (an extreme vibration point along the X axis was placed on this distance).

On this purpose there were made some experiments, results of which are shown on the (Fig. 3), (Fig. 4).



Fig. 3
Dependence of the increase of photopeak -ΔN area from the spatial interval in Cause-Effect Relations by X and Z coordinates, where $X_c Z_c$ – is clockwise rotation, $X_{ac} Z_{ac}$ – is anticlockwise rotation



Fig. 4
Dependence of the increase of photopeak -ΔN area from the spatial interval in Cause-Effect Relations by X and Y coordinates, where X_cY_c – is clockwise rotation, $X_{ac}Y_{ac}$ – is anticlockwise rotation

Let us suppose that positive axis Z is directed from the glass bottom center to the ground and axis X – from the central axis of glass to the vibrated part of the frame (North-West), in this case Y is directed to the North-East. Along the all coordinates, in every adjusted space points on the distance R_i from the glass bottom center (R_i = 5; 50; 70; 100; 115 mm), there were forty measurements. At that in every point after ten measurements connected with the rotation there were measurements at the static liquid. It was made to avoid any systematic errors. The amplitude of the sample average impulses at the static liquid - $N_0=10550$ imp. In this case the root from the dispersion $\Delta=120$, dispersion of the simple average $G=19$. Amplitude increment was calculated by the formula $\Delta N=|N_0-N|$. Following regularities were found:

1. If considering the difference of impulse amplitude (in the positive coordinate space) in the first cause-effect relation evidence (activator-liquid), i.e., to put the difference between the initial (5 mm) and final (50 mm) points of amplitude registration (their middle evidence between “clockwise” and “anticlockwise”) $\Delta N_5^{50}=|N_5-N_{50}|$ into the formula (1), then relations $\Delta T_Z/\Delta T_X=\Delta T_X/\Delta T_Y\approx1.11$ ($\pi/2\sqrt{2}\approx1.11$)

2. Change of impulse amplitude difference along X is the antiphase of changes along Z and Y;

3. At the rotation clockwise and anticlockwise there takes place a periodical inversion of amplitudes difference relation;

4. At the liquid rotation clockwise and anticlockwise, there appears an obvious distinction in evidences of the increment ΔN in negative region of coordinate axes;

5. Along Y and Z-axes in points (5; 100 mm) there is observed insignificant time acceleration.

The whole cause-effect relation system was defined as an internal (activator-table), as an external one (ground - system center of gravity). **In the internal space volume time at the certain conditions breaks its own uniformity, at that the time period change is nonlinear and is defined by its quantum nature.** Therefore, standard clocks in causal relations must be considered regarding to the center of gravity and location of the measurement point in the internal system space.

References

1. Shnol S.E., Zenchenko T.A., Zenchenko K.I., PozharskyE.V., Kolombet V.A., Konradov A.A. Regular change of the statistical distributions thin structure as a result of cosmophysical causes. Kushnirenko E.A., Pogozhev I.B. Comment to the article of Shnol S.E. and Co. Progress of physical sciences. Vol. 170, #2, p.213-218, 2000.

2. Kozyrev N.A. Causal or asymmetric mechanics in the linear approximation. Pulkovo, 1958, p. 90.

3. Kozyrev N. A. Astronomic observations by means of time physical properties. Symposium transactions, Erevan, 1977, p. 209-227.

4. Kozyrev N.A. About possibility of bodies mass and weight under the influence of time active properties. Eganova I.A. Analytical survey of modern time-keeping ideas and experiments. Novosibirsk, 1984, p. 92-98.

5. Melnik I.A. Experimental researches of the time flow local deceleration. VINITI 5.02.92, N1032-mg92, #4, p.70.

UP-TO-DATE INVENTION

TILLEY ELECTRIC VEHICLE

Tilley Foundation, Inc.
131 Hiwassee Road
Lebanon, TN 37087, USA
615-443-5315
E-mail: cktilley@bellsouth.net

Nowadays there stays urgent the development of technologies, which could possibly be combined into a reliable, commercially successful advanced self powered vehicle with additional desirable but currently commercially unavailable features.

The advantages of electric vehicles seem to be evident – they are clean, quiet, powerful, require much less maintenance than gasoline or diesel-fueled vehicles, and are inherently much simpler and easier to manufacture. Their drawbacks have been a short range, long battery recharging time, and a heavy, bulky battery pack.

After several years of personal accomplishments in the alternative energy industry, **Carl B. Tilley, the inventor from USA,** was convinced that it was possible to build an electric car that could be powered without the help of external power to keep the battery charged.

The concept to produce a useful electric performance car that would last more than a few hours and would be economical to run, safe to drive around town or across the United States and never use a drop of fuel challenges the future of transportation as we know it today.

With the establishment of the **Tilley Foundation, Inc.**, in the year 2001, Carl Tilley set out to prove it could be done. It was an ambitious project and it broke ground on the facility in Tennessee that would build the first self-generating electric car.



Construction of a 1,800 square foot building, that was powered with another recently developed electric device, began in the year 2002. Electricity for this car is provided from a different energy invention, which was void of any outside power supply. It is ironic that one alternative energy device actually built the invention to power and build the electric car.

The **Tilley Electric Vehicle** (**TEV**), converted from a 1981 DeLorean, energizes the imagination and defies what has been accepted as a standard in the area of transportation for years.

From the selection of the proper car to be converted, to the advanced technology, which is on board, the **TEV** performs comparably to gasoline-powered vehicles.The difference is you have no need for fuel and you do not have to stop the vehicle to charge it after driving. There is no pollution and you can cruise the highways at the same speed as any other vehicle.

There is a new car on the road today. A car built with technology that defies the concept of fossil fuel powered cars, and can run coast to coast without ever relying on the battery being charged from an outside source.

The long awaited transportation revolution and the end of our reliance on fossil fuel has now begun **....the Tilley Electric Vehicle.**

The demonstration of a DeLorean powered by an electric motor and 12-volt standard car batteries is supposed to be on September 7, 2002, at the Nashville Superspeedway, USA. The battery bank is kept in a charged condition by the "on board" charger which is the device invented by Carl B. Tilley. Racing legend Bobby Allison is one of the guest drivers for this demonstration.

Details and results of the demonstration read in our next issue

The Problem of Time: Force as the Cause of Change of the Course of Time

Valentin P. Oleinik

Department of General and Theoretical Physics,
National Technical University of Ukraine “Kiev Polytechnic Institute”, Prospect Pobedy 37, Kiev, 03056, Ukraine;
e-mail: yuri@arepjev.relc.com
Internet: http://temporology.bio.msu.ru/OLEINIK/oleinik.htm.

Abstract

Material processes occurring in a physical system under the action of a force field necessarily influence the course of time along the trajectory of motion of particle. A general relationship is obtained which relates the course of time on one path section of a particle when moving in a force field to that on the other path section in the same inertial reference frame. According to the results obtained, the force in relativistic mechanics is not only the cause of acceleration of particle relative to an inertial frame of reference, but also the cause of change in the course of time along the particle’s trajectory. ***Therein lies the physical content of the dynamical principle underlying the special theory of relativity (relativistic mechanics).*** *The applications of the theory developed to homogeneous fields - to the field of gravity and electromagnetic field, and to the gravitational field produced by a point mass particle are considered. Physical properties of the state of imponderability of particle in an external force field are investigated. It is noted that the change in the course of time in a force field is in no way connected with the change in space-time metric and is a direct consequence of the causality principle of relativistic mechanics.* ***The existence of dependence of the course of time on the state of motion of particle in a force field points to the feasibility of controlling the course of time using force fields.***

Time is among the most common concepts, which are used constantly both in everyday life and in science. This is because all the events and material processes in the world happen in space and develop in time and, hence, the laws that govern space-time connections are the most general and hold for all the forms of matter. Nevertheless, time remains one of the most mysterious concepts of physics; its physical essence is not adequately revealed up till now [1-4]. The concept of time with difficulty yields to logical analysis.

From the point of view of common sense the essence of time is that time characterizes the duration of events and processes, indicates their natural sequence, at which the present, going away to the past, gives place to the future.

Isaac Newton gave a clear-cut characteristic of the concept of time, to which the majority of physicists adheres: “The absolute, true, and mathematical time in itself and by virtue of its nature flows uniformly and regardless to any other object”. Though, according to Newton, time flows equally and uniformly and does not depend on the processes, occurring in the world, the daily experience speaks in favour of the fact that the course of time is not uniform. Depending on circumstances in our history, it seems to us that time either flies swiftly or hangs heavy on our hands; sometimes it even changes suddenly, by leaps. In connection with these speculations the question arises of whether the subjective sensations of non-uniformity in the course of time familiar to everyone have an objective basis.

In Newtonian mechanics time is of an absolute character, it does not change as one passes from one inertial reference frame to another and represents merely a parameter, whose change at the will of explorer results in the change of state of a mechanical system in accordance with the equation of motion.

In relativistic mechanics time remains a parameter describing the development of system. But now time and space are intimately linked with each other to form a single system, i.e. the 4-dimensional space-time. In going from one inertial frame of reference to another time gets entangled with spatial coordinates, so that time in one reference frame represents a “mixture” of time and coordinates in the other. Time ceases to be universal, the same in all inertial reference frames; it takes on a relative character.

The indissoluble association of time and space takes on special importance in the light of the concept of physical field, which was called by Einstein the most important discovery in physics after Newton. According to this concept, the occurrence in space of a force field means that space turns into a physical environment, which is capable to interact directly with other bodies and gains, thus, physical properties, becoming an active participant of physical processes. In view of the fact that **space and time are indissolubly related to each other, the presence of a force field in some area of space must necessarily result in the appearance of physical properties of time caused by the motion of body in this area.**

Thus, from the synthesis of the notion of space-time and of the idea of physical field it follows with necessity that **the course of time in a given region of space should depend on physical processes in this region, i.e. time, as well as space, should have physical properties [5-8].**

It should be emphasized that in special theory of relativity (STR) time and spatial coordinates are independent and formally equal in rights quantities, which determine the position of elementary events in space-time. On the other hand, time stands out in relation to spatial coordinates. The special role of time is due, from the viewpoint of geometry, to the pseudoeuclidity of geometry of the 4-dimensional space. From the physical point of view, it is associated with the dynamical principle (causality principle), according to which the state of motion of a physical system at an instant of time t uniquely defines its behaviour at the next instant of time $t+0$. The significance of dynamical principle lies in the fact that it relates the temporal evolution of system to the physical processes caused by force fields and in doing so it allows one to determine the course of time in the system, its possible dependence upon the character of physical processes, and not just the sequence of events and their duration.

The idea about the existence of the physical properties of time belongs to N. Kozyrev [9]. By introducing into mechanics an additional parameter taking into account the directivity of the course of time, Kozyrev has formulated causal (asymmetrical) mechanics from which it follows that time has physical properties. According to the results of theoretical and experimental investigations conducted by Kozyrev and his followers [9-13], events can proceed not only in time, but also with the help of time, **information being transmitted not through force fields, but via a temporal channel, and the transfer of information happens instantaneously. The appearance of additional forces, associated with the physical properties of time and capable to fulfill work, testifies that time can serve as a power source.**

In the papers by I. Eganova [12] and M. Lavrent'ev and I. Eganova [13] it is stated the problem of direct experimental research of the physical properties of time to ascertain the relations of a new type between phenomena and to discover new methods to change the state of substance. In [14] O. Jefimenko investigated the dynamical effect of the slowing-down of time.

According to [6-8], the conclusion that physical properties of time exist follows strictly from relativistic mechanics, without introducing any additional hypotheses. The physical properties of time are of purely dynamical nature: their existence results from dynamical principle. **The availability of physical properties of time is manifested in that time has a local inhomogeneity: its course along the trajectory of motion of a point particle in a force field is continuously changed, and this change in the course of time is a result of the action upon the particle of a force field in the inertial reference frame, in which the motion is considered.**

Editor's note: The author gives a detailed consideration of the physical content of the local dynamical inhomogeneity of time. Considering the motion of a classical point particle under the action of a force field in the inertial reference frames, that moves relatively to each other, Valentin P. Oleinik derives 73 equations, that help him to obtain the following conclusion (mathematical details and physical reasoning may be found in http://temporology.bio.msu.ru/OLEINIK/oleinik.htm.*)*

The elucidation of the physical nature of time is one of the most important problems of theoretical physics. The purpose of research on the problem of time is to study the physical properties of time, i.e. to ascertain the possible interrelation between time and material processes. In particular, it is of interest to find out

- whether the flow of time depends upon physical processes and whether the back influence exists (i.e influence of the change of the time course on physical processes);
- what mechanisms of the change of the course of time are available;
- what factors are capable to speed up or to slow down the flow of time.

In papers [5-8] on the basis of Lorentz transformations relating to coordinates of points, lying on the trajectory of motion of particle in a force field, the phenomenon of local dynamical inhomogeneity of time is predicted. The main result consists in the proof that material processes occurring in a physical system under the action of a force field necessarily influence the course of time along the trajectory of motion of particle. The case in point is the change of the course of time along particle's trajectory in one inertial reference frame as compared with that in the other.

In this paper the next step is made: the relationship is obtained which relates the course of time on one path section of a particle when moving in a force field to that on the other path section in the same inertial reference frame. The main idea underlying the approach developed results from the analysis of Lorentz transformations and consists in that **the course of time of a particle moving by inertia, i.e. of a particle being not exposed to force, should be uniform.**

As is well known [17,18], the existence of dependence of the course of time upon the gravitational field potential is predicted with the general theory of relativity (GTR). According to GTR ([17], p.303), time flows differently at the different points of space in one and the same reference frame. Since "gravitational field is nothing more nor less than a change of the space-time metric" ([17], p.313), one can assert, apparently, that the change in the course of time is due, in the view of GTR, to the change of the 4-space metric. It should be emphasized that in the present paper gravitational field is considered as an ordinary force field, and the particle motion is supposed to occur in pseudo-Euclidian space-time. The main formulas of the article, (22) and (25), describe the change in the course of time in an arbitrary force field at different spatial points in one and the same inertial reference frame. As is seen from the results received, the change in the course of time in a force field is in no way connected with the change of space-time metric. It is conditioned by the force field action on particle in inertial reference frame and is a direct consequence of the dynamical principle underlying relativistic mechanics.

It should be emphasized that the existence of dependence of the course of time on the state of motion of particle in a force field points to the feasibility of controlling the course of time using force fields.

Note an important peculiarity of the non-inertial reference frame, in which the imponderability state of a particle is attained: **there is such a space-time region in which the reference frame at hand can be approximately considered as inertial.** In connection with the fact that such reference frames (it is natural to call them **quasiinertial** in contradistinction to the **true inertial** reference frames) are, generally speaking, not equivalent to each other (see previous section), the derivation of a rigorous criterion for inertial reference frame acquires especial significance. The dynamical criteria for defining the inertial and non-inertial states are considered in the papers by B. I. Peschevitsky [19]. The heliocentric reference frame seems to be among the quasiinertial reference frames, being inertial with adequate accuracy only in a restricted region of space (for example, within the limits of our Galaxy) [16].

The author is grateful to Yu.D. Arepjev for his interest to the paper and stimulating discussions.

References

1. Blokhintsev D.I. Space and Time in the Microworld (Nauka, M., 1970) (in Russian).
2. Prigogine I. From Being to Becoming: Time and Complexity in the Physical Sciences (W. H. Freeman & Co., San Francisco, 1980).
3. Prigogine I. and Stengers I. Order Out of Chaos (Bantam Books, New York, 1983).
4. Logunov A.A. Lectures on the Theory of Relativity and Gravitation: Modern Analysis of the Problem (Nauka, M., 1987) (in Russian).
5. Oleinik V.P. The Newest Development of Quantum Electrodynamics: Self-Organizing Electron, Superluminal Signals, Dynamical Inhomogeneity of Time, Physical Vacuum and Nature, 4, 3-17 (2000).
6. Oleinik V.P., Borimsky Ju.C., Arepjev Ju.D. New Ideas in Electrodynamics: Physical Properties of Time. Semiconductor Physics, Quantum Electronics & Optoelectronics, 3, #4, 558-565 (2000). E-print: quant-ph/0010027.
7. Oleinik V.P. Superluminal Signals, Physical Properties of Time, and Principle of Self-Organization, Physics of Consciousness and Life, Cosmology and Astrophysics, 1, 68-76, (2001); Borimsky Yu.C., Oleinik V.P. The Course of Time in Classical and Quantum Systems and Dynamical Principle, Physical Vacuum and Nature, 6, (2001) (in print).
8. Oleinik V.P. The Problem of Electron and Superluminal Signals. (Contemporary Fundamental Physics) (Nova Science Publishers, Inc., Huntington, New York, 2001).
9. Kozyrev N.A. Selected Transactions (Leningrad University Press, Leningrad, 1991) (in Russian).
10. Lavrent'ev M.M., Eganova I.A., Medvedev V.G., Olejnik V.K., and Fominykh S.F. On Scanning of Celestial Sphere by Kozyrev's Sensor, Doklady AN SSSR, 323(4), 649-652 (1992) (in Russian).
11. Akimov A.E., Kovaltchuk G.U., Medvedev B.P., Oleinik V.K., Pugatch A.F. Preliminary Results of As-tronomic Observations of Sky by the Kozyrev Procedure. Academy of Sciences of Ukraine, Central Astronomic Observatory. Preprint CAO-92-5P, 1992, p.16 (in Russian.).
12. Eganova I.A. The World of Events Reality: Instantaneous Action as a Connection of Events through Time, Instantaneous Action-at-a-Distance in Modern Physics (Nova Science Publishers, Inc., New York, 1999).
13. Lavrent'ev M.M. and Eganova I.A. Physical Phenomena Predicted and Revealed by N.A.Kozyrev, in the Light of Adequacy of Space-Time to Physical Reality, Phylosophy of Science, 1(3), 34-43 (1997) (in Russian).
14. Jefimenko O.D. Electromagnetic Retardation and Theory of Relativity (Electret Scientific Company, Star City, 1997).
15. Khaikin S.E. Forces of Inertia and Imponderability (Nauka, M., 1967).
16. Sivukhin D.V. The General Course of Physics. Mechanics (Nauka, M., 1979).
17. Landau L.D. and Lifshits E.M. The Classical Theory of Field (Pergamon Press, Oxford. 1985).
18. Pauli W. Theory of Relativity (Nauka, M., 1983).
19. Peschevitsky B.I. Dynamical Criteria for Inertial and Noninertial States, p.1 and 2. Phylosophy of Science, 1(7), 79-84 (2000); 1(9), 99-109 (2001) (in Russian).

EAGLE-RESEARCH

Energy Solutions
since 1984

A Research Organization
that Develops & Distributes
Practical Energy-Saving
Methods & Devices

4 Energy Way, P.O. Box 118
Porthill, Idaho 83853
FAX: 250/492-7480

Technical questions to:
wiseman@eagle-research.com

Raum&Zeit

EhlersVerlag GmbH, Geltinger Str.
14e, 82515 Wolfratshausen
Telefon: 08171/41 84-76, 08171/41 84-66
Internet: http://www.raum-und-zeit.com

Institut für Raum-Energie-Forschung (IREF)
i.m. Leonard Euler

raum & zeit
Laser harmonisiert Blut und Wasser
El Niño

Global Scaling Theory
Gravitation theory
Mathematic Biology
Gravitation energetics
Hydrogen-Helium Energetic
Information technologies
Telecommunication technologies
Transport technologies

Time and its Physical Relationships

Andrew Michrowski

President, The Planetary Association for Clean Energy, Inc., 100
Bronson Avenue, # 1001, Ottawa, Ontario K1R 6G8 Canada.
(613) 236-6265; fax: (613) 235-5876
pacenet@canada.com

> *Time cannot be absolutely defined, and there is no inseparable relation between time and signal velocity.*
> *Albert Einstein [1]*

Time does not exist by itself

The phenomenon of time emerges in relationships – as an expression of properties of physical bodies and changes that occur to them.

Time is a factor of energy. Time has to do with the *increase* and *decrease* of energy. For example, as energy is brought down to a "zero level", time is "eliminated", so in a sense, time cannot be "compressed" - only eliminated. In the zero-energy level, electrons occupying this level in unlimited numbers are available through state transitions for the building of matter and the vacuum [2]. So it is the extent and the nature of energy flow that determines the characteristics of time.

How do we know all this?

In his seminal foundations of physics work of the early 1900s, **Sir Edmund T. Whittaker** demonstrated by canonical quantization that there exist physical, time-like and longitudinal photons *in vacuo* [3,4,5]. The 2 scalar potential functions, F and G which completely characterize an electrodynamic field due to electrons in the ether are:

$$F\,(x, y, z, t) = \sum \frac{e}{4\pi} \sinh^{-1} \frac{\bar{z}'-z}{\left\{(\bar{x}'-x)^2 + (\bar{y}'-y)^2\right\}^{1/2}}$$

$$G\,(x, y, z, t) = \sum \frac{e}{4\pi}\, \tan^{-1} \frac{\bar{y}'-y}{\bar{x}'-x}$$

In these equations, for the fundamental case in which a field is due to any number of electrons moving in any way, we observe that time emerges only through the displacement of energy. Another way of putting it would be that time emerges through change in energy.

These photons have an independent physical existence. Whittaker himself observed, after computation that the "total disturbance at any point, due to this system of waves, is independent of the time, and is everywhere proportional to the gravitational potential due to the particle at the point" [6]. **A. D. Sakarov** admitted that the gravitational field is a "conglomerate of loose things and not a fundamental field of nature at all [7].

Everything electromagnetic, and probably gravitational, starts from these potentials, not fields, and under certain circumstances, there may exist photons without fields being present at all. In the *vacuo*, the longitudinal light photon travels in the direction of the beam, like an energy capsule, as a scalar four-potential-function energy standing-wave field, with many different frequencies, with an internal symmetry based on circular polarization [8,9], an energy field or nexus that "has an end, but no beginning". The time-like and space-like parts of the four potential are photons with spin –1, 0 and +1 that are longitudinally directed, and which are observed in the ***Compton*** and the photoelectric effect [10].

Movement of light affects time

Philip S. Callahan designed an elegant experiment that shows how variations in the movement of light affect time [11]. Changes in exposure settings of photographs of same objects, including coherent light laser spots results in shift of position of images. The more coherent the light, the less apparent is a shift in time. He suggested that time is neither absolute nor independent of photon activity of space.

We can also state, as a corollary, that the *movement* of light generates time. After all, the electrodynamics is associated with photons. This is particularly significant in time engineering, as will be seen later.

Time and life

Now, it is well known that the ability of cells to sense the presence of light is a primary function of life itself. If a cell can sense light, it is alive; if it cannot, it is dead [12]. Callahan was able to observe that time increments were detected on light-detecting surfaces of living organisms such as the cuticles of leaves.

The Russian time researcher, **Nikolay A. Kozyrev** considered that living systems "consume" time for their life-energy [13]. **Velimir Abramovich** suggests that living organisms are naturally-driven "time machines". They each have an inbuilt time that serves as a "code" to structure their own physical totality and to regulate their own functioning. Thus their "local time" acts as a "time operator" ("time condition") frequency [14]. The nature and level of electromagnetic fields in living systems could therefore be considered as indicators of their "energy level" and how it affects and adjusts the inherent rate of time-flow.

Time and consciousness

We append to these statements the notion that, yes, time is "consumed" by living organisms – but only if they are conscious. Essentially, time can be perceived by measurement, which always requires a conscious observer.

When we measure, we observe the differentials of energy flow. It is the measurement of these differentials - as we note from the Whittaker equations of scalar fluxes - that allows us to the measure the equivalence of time. When we measure differentials, we are effectively creating our notion of time.

It is difficult for humans to conceive that time does not exist when humans think about it. **Saint Augustine** speaks for all humans with his observation:

> *While I do not think about time, I know that time exists. When I begin to think about it, I stop understanding what it is.*

With such conditioning, humans cannot come to grips with the notion that the Universe has no beginning and no end. It is like the paradigm of absolute nothingness – people cannot deal with the concept of no time because, effectively, consciousness, like life, consumes time. One could advance the notion that thought itself is time in motion. When we think, we are creating time. Life is movement – and the brain registers energy differentials and their associated fluxes of scalar potentials.

Time and causal mechanics

Since time is the result of movement of energy (and accordingly, light), then time is associated with the cause-effect processes linked to a first position of energy to the next. In other words, time is innate to causal mechanics.

Variations in energy flow, logically, lead to variations in the characteristics of time. They also permit variations in causality.

Conversely, changes in time lead to changes in physical structure [15]. This phenomenon was proven by Kozyrev and has been labelled as the ***Kozyrev effect*** [16]. He demonstrated that changes in the course of time affect the performance of electronic components. Figuratively speaking, a transistor is like a corral in which light behaves in a certain way. By changing the way that light behaves, a transistor becomes valueless.

To create an extra-temporal causality (with linkages to another level/dimension) one must change the light movement. Changing the light patterns means changing the behaviour of a wave, and its concordant photonic reality. By altering the photons, we make them go to another dimension.

Changes in time can effect change in living systems [17]. The engineering of "time-polarized" waves has the promise to target and amplify natural healing procession in living organisms. It is these natural activities that would restore diseased cells to their original and healthy condition [18]. Such time engineering may also include the reversal of the effects of AIDS, smallpox, anthrax, and most bio warfare agents, with treatment times of only a few minutes per week, with no more than 3 treatments required in all. Eventually it may also be possible to reverse the effects of genetic disorders, effect limb regeneration, and cure spinal cord injuries [19].

Engineering causality

Variation in the density of energy determines variation in the "the course of time". By the "speed of course of time" is meant the rate of causal transformation and the input of additional forces into systems (including mechanical tensions). According to Russian scientists [20, 21,22] there are interesting possibilities in deploying engineering for causal mechanics.

In preventive time engineering, one could delay the approach of a known cause and to artificially close the consequence loop, and thereby annulling it from ever achieving an effect. In other words, one can make the effect "happen" before its normal time, disrupting space structure with its related "speed of the course of time". One can also make it "happen" after its expected deadline. This technology could have interesting implication in strategic situations (preventing a extra-planetary body from attaining a collision course).

According to the Russian experience, when the spatial structure is disrupted by time-engineered causal mechanics, the affected region undergoes relative greater entropy (or, less order). The volume of space is forced out to somewhere else, generating torsion fields, much like a balloon will drift away from denser air. A similar phenomenon occurs when the velocity of a mass increases, the force emerges against it, called "inertia" [23]. Now, to increase velocity, the energy of the mass increases. In the case of time, as the movement of energy increases, interaction or reaction with another dimension ensues to compensate for that primary change [24].

The boundary layer between the two states of space can then act as a mirror and the approaching agent may be reflected back to its source. For example, a light beam may be reflected back to its emitter, in full, or in part, depending on the engineering.

With space-time engineering, we could develop teleportation systems [25]. The course of time goes from the past to the future, in the direction of greater disorder. Going back to the past represents deceleration. The etheric continuum is perceived by Kozyrev is containing variations of "density" of structural elements. The "denser" the etheric region, the slower is the course of time. A zone of accelerated time course would be forced out into "rarefied" ether. A zone of slowed time would be forced into denser ether, hence the basis for a teleportation technique.

In vivo experiments with a Time Machine

For over 15 years, a Russian association of scientists has conducted experiments with acceleration and deceleration of time with 4 prototypes of time machines

[26]. Light-heartedly, the units are called "muskrat traps" since the experiments conducted in remote forest were disguised as a high-tech electromagnetic technology for trapping muskrats. The time machine units are spheres ranging in diameters of 30cm, 1 meter and 2.1-meter. The shells are encased with coils designed to produce convergent waves.

Team leader **Vadim A. Chernobrov** describes converging electromagnetic waves as moving from a periphery to a central point. They are observed when a hoop is thrown into the water and inside the hoop the waves converge. If a potential is applied to do work and to initiate the energy differential process, the other reverse direction scalar (the reverse-time energy flow) must react. Thus, compensation of time - in the form of the deceleration or acceleration of the rate of time - can take place [27].

The first trials involved mice, in which most (25 out of 31) died. Eventually, there were successful 2-hours runs of time travel. An experiment with a dog that was clearly frightened also showed no ill effects. This led to experiment with humans, the first being **Ivan Konov** who, on August 26, 2001 decelerated into the past by 3% of planetary time during a half-hour trial. Dozens of others have experienced the phenomenon and report such sensations as: quicker pulse, giddiness, itching skin, body twisting, numbness at extremities and a case of an out-of-body experience. Harmful effects on living systems do not appear to be linked to the change of the rate of time, but rather to the variations of the time rate value among regions of a living organism.

Some individuals reported visual experiences such as "starry sky", "luminous vortices" and colour spots. Individuals observing outside of the time travel machine noted headaches. The most interesting phenomena occurred just before the start-up: significant presence of ozone for several hundreds of meters around the machine, which was located in a forest. Also noted were strange lighting effects in the sky above the apparatus, accompanied by sounds that inexplicably appeared to generated from inside.

Factors affecting the rate of time

The experiments yielded interesting observations: the phenomenon of the rate of change of time varies according to the hour of the day and according to the lunar phase. The rate can be influenced by a variety of external inputs, including mechanical vibration.

The transition into the future differs from than into the past. It is like movement from any point in a tree – where downwards represents past time. There are many paths possible towards the future – upwards, along the branches, but only one towards the past – downwards to the trunk. The return from the past time is possible only if the time traveler does not interfere with occurring events – or the possibility of returning to another branch of the tree. However, a return move from any variant of future time is possible regardless of the behaviour of the traveller.

The Russian time-travel experiments point to a relationship between inertia and time. In changes of rates of time, the region adjacent to the spheres develops a boundary layer effect, appearing as an aura of "white mist". The greater the time differential, the denser is the mist.

A similar phenomenon has been observed, and captured on film, with some experiments conducted by **John Hutchison** involving remote-controlled lifting and disruption of objects [28,29]. It may be that the ***Hutchison effect*** involves causal mechanics.

Time and frequency

Time may be viewed as a process – or "change-of-space" in any direction that does not exist in our dimension [30,31,32]. In physics, new properties are commonly acquired as the result of change in some property: charge, current, induced magnetic field, etc. Here, the new property becomes a new dimension. For the frequency of oscillations, the formula is $f = 3/\lambda$ [l/s], where λ is wavelength in [m]. Here, the velocity of light is equal to 3 (the 10^8 mathematical degree is omitted since it is a question of scale of measurement only).

Therefore, the analogy between our dimension and frequency gives us a new notion, which is curvature ρ: $\rho=3/r$ [l/m] and $f = 3/\lambda$ [l/s]. The 3-dimensional radius is represented by $R=\lambda/\rho= r/3$ [m] and time as a period of oscillation has the relationship: $T = \lambda/f$ [s]. **Time can be considered to be equivalent to the radius of curvature ρ if the linear radius r and the wavelength λ are the same. This is a condition for the spatial resonance effect.** Note that in this analysis, *"m"* and *"s"* are unlike when length is measured in meters in our dimension. However, for a new dimension it is possible to use equal units for (m) of 4th dimension and conventional "second". Furthermore, light (photons) is possible in our dimension only as a process in such a spatial resonator.

Experiencing time dilation

Based on the above discussion, it is proposed that we experience changes in rate of time in our daily life. During sleep, as our energy level decreases, so it can be argued that time decreases and we "go" into another dimension. Aspects of what is observed during the dream-state do not obey the rules of our familiarity of physical existence, and conventional causality - because the rate of time is different. As we start our dreaming, and as we emerge from dreaming, the recalled experiences resemble more our regular experiences. Before and after sleep, our brain frequency tends to resemble the daytime's. In effect, understanding our dream state's sense of time may be a reference key to comprehending the physics and causality mechanics of time engineering.

Time and planetary gravity

The Earth's mass appears to be in continual growth. 250 to 350 million years ago, our globe may have been half size - with all of the continents as one landmass [33]. In ancient sediments, the natural angles of slope in sand beaches greatly exceeded those of today, indicating that gravity has on our planetary surface has increased 8-fold, several times, during the last 1.5 billion years. Yet the planet's average density may not have changed – only the acceleration of free fall [34,35].

There could also be another explanation possible for the change of slope of beaches. The pull of the moon may have been different in the past.

Also, the planetary magnetic fields could have increased over the millions of years, through interactions with the solar flux of hydrogen atoms. The sun is in constant explosion – production of energy differential. Earth and other planets could be responding with harmonics to compensate for the solar activity, leading to an overall increase in magnetic fields. Such a phenomenon may give the illusion that the physical body is growing larger. In other words, with time, the force of gravity would alter planetary mass and energy.

Assuming that the Earth's density has not increased, it is possible account for, mathematically, the relative increase – growth processes - of the nuclei of terrestrial atoms, including the doubling of mass of nucleons and of electrons [36]. Such calculation also accounts for the emission of 2 different photons by hydrogen atoms (also known as the "red shift" described by **E. Hubble**).

The phenomenon can be explained with the time-like and longitudinal photons described by the bi-directional 2 scalar potential functions [37,38]. Could it be suggested that matter is gravity minus time? In other words, gravity is related to accumulation of energy differential (time) in mass.

The value of gravity varies throughout the planet, in part because of the poles and in part due to local density of matter. **Kirill P. Butusov** has noted a correlation between places of civilization and regions of greater gravity. A faster rate of evolution may be associated with such gravity zones. In these zones there would be a greater influx of scalar potentials. Time would be more "authenticated" by these energy flows into conscious beings. Butusov reminds us that time has a "positive energy" and flowing into nuclei of atoms or a "negative energy" flowing out of the nuclei of atoms [39].

The outflow would be representative of gravitational energy. Longitudinal waves are known to be able to enter and to leave nuclei. Such flows of time must come from other dimensions. After all, the surface of any elementary particle separates our dimension from another. This leads to an interesting possibility in which all time-associated processes between dimensions are synchronized.

Time reconsidered

Arguments have been laid that suggest that time is equal to energy differential (including movement of light). Living systems "consume" time as part of their consciousness and measuring processes.

It is possible to engineer causality. An understanding of higher-order electrodynamics is required. Techniques exist for the generation of scalar potentials. Causality technology has many applications. They include: therapeutics, energy generation, consciousness technology, inter-dimensionality, defence systems, teleportation, and of course, "time travel".

Appreciation is expressed for guidance in this discussion by Thomas E. Bearden and Bernard de Montréal.

References

1. Einstein, Albert. How I created the theory of relativity. [Translation by Yoshimara A. Ono.] /Physics Today. Volume 35 (8), August, 1982. p. 45-7. [Lecture given by Einstein in Japan, on learning of his Nobel Prize.]
2. Phipps, Jr. Thomas E. Heretical Verities: mathematical themes in physical description. /Classic Non-Fiction Library, Urbana, 1986. p. 397-405
3. Whittaker, Edmund T. On the partial differential equations of mathematical physics. /Mathematische Annalen. Volume 57, 1903. p. 333-355.
4. Whittaker, Edmund T. On an expression of the electromagnetic field due to electrons by means of two scalar potential functions./ Proceedings of the London Mathematical Society. Volume 1, 1904. p. 362-372.
5. Whittaker, Edmund T. A history of the theories of aether and electricity. Volume 1 and 2. London: Thomas Nelson & Sons, 1953.
6. Whittaker, Edmund T. On the partial differential equations of mathematical physics. /Mathematische Annalen. Volume 57, 1903. p. 354.
7. Sakarov, A. D., Vacuum fluctuations in curved space and the theory of gravitation. /Soviet Physics Doklady. Vol. 12, 1968. p. 1040-1. [English translation.] Original in: Doklady Akad. Nauk. USSR, Vol. 177, 1967. p. 70-1.
8. Evans, Myron W., Physica B. Volume 182, 1992. p. 227
9. Evans, Myron W., and S. Kielich (editors). Modern nonlinear optics. [Special topical issue of Ilya Prigogine and Stuart A. Rice: Advances in Chemical Physics. Wiley, New York 1992, 1993, 1997, and 2001] Volume 85 (2).
10. Institute for Advanced Study (Budapest). On Whittaker's F and G fluxes, Part III: the existence of physical longitudinal and time-like photons. // Higher symmetry electrodynamics: a collection of AIAS papers. [Special Issue. Journal of New Energy.] 2000. p. 7-1 – 7-5.
11. Callahan, Philip S. and Kevin. Sinewaves of spacetime. / Newsletter of the Planetary Association for Clean Energy. Volume 9(2&3), April 1997. p. 8-9.
12. Jibu, et al. Evanesecent (tunnelling) photon and cellular "vision". /Biosystems. Vol. 43, 1997. p. 65-73.
13. Kozyrev, Nikolay. A. Selected works. University of St. Petersburg. 1991. [In Russian]. Also: On the way to understanding the time phenomenon: Construction of time. A. P. Levich, editor. World Scientific Press. 1995.
14. Abramovich, Velimir. Experimenting with Time. /New Energy Technologies. Volume 3, November-December, 2001. p. 13-5
15. Frolov, Alexander V. Practical application of time rate control (TRC) theory. /New Energy Technologies. Volume 3, November-December, 2001. p. 15-18.
16. Kozyrev, Nikolay A. The possibility of experimental study of the properties of time. /National Technical Service, US

Department of Commerce, Springfield, Virginia. (JPRS 45238). [Undated.]

17. Bearden, Thomas E. Renaissance healing, a concept whose time has come. /Proceedings of the United States Psychotronics Association. Volume 9, 2000. p. 1-2.
18. Bearden, Thomas E. Vacuum engines and Prioré's methodology: the true science of energy-medicine. I and II, /Explore! For the Professional. Volumes 6 (1), and (2) 1995.
19. Bearden, Thomas E. Private communication. February 2002.
20. Frolov, Alexander V. Practical application of time rate control (TRC) theory. /New Energy Technologies. Volume 3, November-December, 2001 p 15-8.
21. Kozyrev, Nikolay. A. Selected works. University of St. Petersburg. 1991. [In Russian]. Also: On the way to understanding the time phenomenon: construction of time. A. P. Levich, editor. World Scientific Press. 1995.
22. Kozyrev, Nikolay A. and V. V. Nasonov. On some properties of time found by means of astronomical observations. / Collection: Problems of research of the universe. Volume IX, M-L, 1980.
23. Puthoff, Harold E. The energetic vacuum: implications for energy research. /Speculation in science and technology. Volume 13 (3). p. 247.
24. Frolov, Alexander V. Trilateral spacetime effect. / Newsletter of the Planetary Association for Clean Energy. Volume 9(2&3), April 1997. p. 10-13.
25. Frolov, Alexander V. Practical application of time rate control (TRC) theory. /New Energy Technologies. Volume 3, November-December, 2001 p 15-8.
26. Chernobrov, Vadim. Experiments with a man in the Time Machine. /New Energy Technologies. Volume 3, November-December, 2001 p. 6-8.
27. Frolov, Alexander V. Trilateral spacetime effect. / Newsletter of the Planetary Association for Clean Energy. Volume 9(2&3), April 1997. p. 10-13.
28. Calante, Pelayo and Andrew Michrowski (compilers). The Hutchison File. The Planetary Association for Clean Energy, 1996. p. 16-7.
29. Hathaway, George D. The Hutchison effect – a lift and disruption system. /New Energy Technology. The Planetary Association for Clean Energy, 1990. p. 77-103.
30. Frolov, Alexander V. Trilateral spacetime effect. / Newsletter of the Planetary Association for Clean Energy. Volume 9(2&3), April 1997. p. 10-13.
31. Ouspensky, Pavel D. A new model of the universe. New York, 1971.
32. Frolov, Alexander V. The application of potential energy for the creation of power./ New Energy News. Volume 2(1), May, 1994.
33. Kirilov, I. V. Increase in volume of rocks is one of the reasons of tectonic deformations. /Academy of Science of the USSR Geologist. Volume 1, 1963.
34. Smirnov, L. S. and Ju. N. Lubina. On the possibility of studying the change in gravity together with geological time. /Reports of the USSR Academy of Science. Volume 187, Number 4. 1964.
35. Maxlow, James. Earth expansion – the definitive proof. / Nexus. Volume 8 (3), May 2001. p. 47-51.
36. Butusov, Kirill P. Time is a physical substance. /New Energy Technologies. Volume 3, November-December, 2001. p. 8-13.
37. Bjerknes, K. A. Vorlesungen ueber hydrodinamische fernkraefte. Leipzig, 1900-2.
38. Yarkovsky, I. O. Universal gravitation as a result of formation of ponderable matter inside heavenly bodies. Moscow, 1889.
39. Butusov, Kirill P. Time is a physical substance. /New Energy Technologies. Volume 3, November-December, 2001. p. 8-13.

New Energy Technologies

PRINT EDITION ADVERTIZING RATES

Full Page Ad
B/W - $400
Color - $800

Half Page Ad
B/W - $200
Color - $400

Quarter Page Ad
B/W -$100
Color- $200

Ask about discounts for multiple ads

New Energy Technologies is distributed to scientific laboratories in 20 countries around the world.

To advertise contact us:
Faraday Labs Ltd, Phone/fax 7-812-3806564,
http://www.faraday.ru, office@faraday.ru

Time as Phenomenon of the Expanding Universe

Michael H. Shulman

7 (095) 357-80-33, 7 (095) 421-11-31
E-mail: shulman@dol.ru

Preface

In 1992 the author of this words, having been stimulated by Kozyrev's book [1], started to reflect on Time meaning and Time and Space asymmetric roles during the Universe Expanding. The development of these ideas has led to the work [2], it is available now (the Russian version only) on the website of the Institute of time nature explorations (grant #00-07-90211 of the Russian fund of basic research).

I would like to thank the Chairman of the Russian Interdisciplinary Temporology Seminar Dr. A. Levich from Moscow State University for his constant support and friendly interest. Also I would like to thank A. Moskowsky for the 20-year discussion of the physics history and philosophy.

The said work [2] pretends to revise radically a number of basic physical concepts of the Space - Time, Motion and Energy nature. It includes a detail analysis and mathematical calculations. Only a brief account of the main part of this work is presented below.

Introduction

The nature of time is not yet enough clear for natural science. In Newton mechanics time was presented as some universal formal parameter. Its value rises steadily at every point of the Universe by unknown for us reason. Each physical process occurs in space in correspondence with the time course.

In the Special Relativity (SR) time and space are integrated to the common 4D-continuum. However, in this theory the time component having imaginary factor seems also to be "exotic". In this concept the increase of time is also implied in each reference frame.

The General Relativity (GR) allowed linking the time properties with gravitational fields and the space geometry. The time currency started to be associated with a spatial expansion of the Universe.

The theoretical physics traditional approach to the process description is based upon the considering of time course as primary (original) one. There are also in the modern physics [3] several attempts to deduce the time concept as secondary one from different fundamental (microscopic) concepts. However, the third way (inverse to the first one) is possible and forms the basis of this paper. A starting point of this way is the following question: "Does any universal process exist which could *generate* physical time?"

(Editor's note: The same question was formulated and the answer was proposed by Alexander V. Frolov in 1996, report "Matter as process", Scientific congress "New Ideas in Natural Sciences". It was assumed that similar process can be produced by special technical methods also.)

Such fundamental cosmic process really exists and it is well known in the modern science. **It presents the Universe expansion** and was opened at the first third of the 20th Century by the American astrophysicist E. Hubble and others [4]. It means the general increase of distances between all 3D-bodies. The same scattering of two-dimensional-figures happens on the surface of some spherical balloon during air incoming. The centre of this sphere does not belong to the surface; all points of the sphere (the Universe) are equivalent.

Some time earlier the theoretical physics had come to the same results. As it is well known, the Einstein's GR was published in the 1916. After that Friedmann (1922) proposed the concept of the expanding Universe. For example, in the book [5] a description of the basic cosmic model is given. Hereinafter this model is called "Einstein-Friedman model", or "EF-model". In this model the Universe is presented as 3D- hyper surface of a 4D- sphere with increasing radius. Of course, the curvature of the 3D-hyper surface increases with time too.

Basic hypothesis relative to time nature

Some simple and pictorial views consist a basis of the new concept. Hereinafter it is called briefly as "The Spherical Expanding Universe Theory (SEUT)".

In the SEUT, as well as in the EF-model, in every time the Universe represents the 3D-hyper surface of a 4D-sphere. However, there is one very important difference. In the Einstein's theory the spatial components of the metric tensor are opposite in sign to the time's one. For example, we may consider time as imaginary quantity, then spatial coordinate as a real one. On the contrary, in the SEUT the 4D-continuum is considered as purely

Euclidean, all the four coordinates are real quantities. The usual spherical geometry can be used on a surface of the 4D-sphere.

As it is well known, in the GR the Age of the Universe can be *calculated* using the EF-model or a similar one. Usually, the radius-age dependence is not a direct proportionality in such GR models. However this result may be deduced if to neglect the global pressure of matter that fills the Universe. In [2] it is demonstrated, that an account of the static pressure of matter follows to the Universe radius linear dependence on its age (see below).

On the contrary, in the SEUT the time universal course is *manifested.* The Universe age is *identified* with a current Universe radius divided by the velocity of light. Numerous important consequences may be deduced from this statement. On the other hand, it allows avoiding many other arbitrary postulates in the model.

Mechanical motion and maximum velocity in the SEUT

The SEUT states, there is no unlimited set of independent mechanical motions. Only world lines of moving bodies exist. Each of them has some inclination relative to the time line, which presents a normal to the hypersurface of the 4D-sphere. It is *an inclination angle that defines the spatial motion velocity*. At the increase of sphere radius the intersection point of word line and current hypersurface "moves" with exact correspondance with a modern physics prediction.

In particular, immovable objects (stars) have zero inclination, their world line are normal to the hypersurface. Hence they "scatter" according to the Hubble law, their mutual velocity is proportional to mutual distance. If a body world line has some inclination relative to normal, the angle is more than zero. But it can't exceed 90°, therefore *maximum* mechanical motion *velocity* appears *naturally*, it is equal to the velocity of light.

Let us consider three variants of motion (see Fig.1).



Fig. 1
Phenomenon of a "motion" of point on a sphere surface for immovable (at the left), uniformly moving (at the centre) and non-uniformly moving (at the right)

The left picture illustrates the Hubble effect. The right picture presents a general case of motion with acceleration. The central picture corresponds with an inertial motion; its world line is direct. In this case the moving body displacement increases proportionally to the Universe radius increment. So, *inertial* motion is not postulated in the SEUT, it appears as natural model consequence.

At a large 4-sphere radius values all the relationships of SR and usual mechanics laws are applicable approximately in the SEUT. A Special Relativity light cone transforms to all the hyper surface of the 4D-sphere. But the analogy is not complete, because an absolute remote SR area degenerates to this 3D- hyper surface in the SEUT (see Fig. 2).



Fig. 2.
4D- continuum areas in the SR (at the left) and in the SEUT (at the right)

SEUT and Minkowski geometry

Let us consider small increments of time and space coordinates along body world lines during the Universe expanding. It is enough to consider a small area of the Universe, so we can neglect its curvature. Then it is acceptably to replace approximately concentric hyper surfaces ("isochrones") by parallel hyper planes. The space-hold corresponds with a representative point "drift" perpendicularly to isochrones, an inertial motion corresponds with displacement along inclined direct lines between isochrones.

At each time the Universe is represented by a certain isochrone that contains all the real spatial points. Let us accept that 4D-sphere radius increment divided by velocity of light presents invariant measure of (absolute) time increment. We will also state that this quantity has the same value in each *inertial* reference frame, i.e. at a motion along each *direct* world line.

Let the angles of world line inclinations from normal direction are enough *small*. Then metric relationships like Minkowski geometry ones appears in our purely Euclidean 4D-continuum. In particular, well known relationship

$$c^2 ds^2 = c^2 dt^2 - dr^2$$

can be deduced from the Pythagorean theorem. It connects a spatial component *dr* with a time component *dt* (at moving reference frame) through velocity of light *c*. Here *ds* is an absolute time interval (between two 4D-events at a immovable reference frame). **Hence, if velocities aren't very high, the Lorentz transform is correct in different inertial reference frames.**

On the Einstein's relativity principle

If the world lines inclinations from exact normal direction cannot be accepted as small, then Minkowski geometry relationships are correct approximately only. It means that Einstein's relativity principle is correct (in the SEUT) only for reference frames that move with velocities enough small relative to *selected* reference frame. Such reference frame is linked hardly with a body at (absolute) rest, i.e. drifting along radial world line.

The selected reference frame existing reminds of old ether theories that contradict to the Special Relativitiy views. It seems, these theories became a thing of the past irretrievably. In fact, the velocity of light in vacuum is constant everywhere and everywhen. However, the reference frame existing can be detected in principle as a light signal frequency bias, i.e. with the help of Doppler effect. Well, this phenomenon is really detected by the modern astrophysics!

The temperature diagram of the Cosmic Microwave Background Radiation (CMBR) coming to the Solar system from all the sides of the Universe is presented on Fig.3. The data was registrated during 4 years by the Cosmic Background Explorer (COBE) satellite (NASA Goddard Flight Centre, COBE Science Working Group).



Fig. 3
The anisotropy of the Cosmic Microwave Background Radiation (CMBR)

The well-known Russian scientist J.B. Zeldovitch in the Editorial Addition to [6] in connection with earlier experiments notes that careful measurements **allowed to find out some anisotropy of CMBR.** An antenna oriented to the Lion constellation detects that the radiation temperature is 0.013% more, than mean temperature. The radiation temperature in the opposite direction is 0.013% less, than mean. **Generally, a temperature varies continuously between these two values.** The isotropy presents only for some imaginary observer. ***The Solar system, Earth move to the Lion constellation relative to this observer having velocity 390 ± 60 km/s.*** Hence, as a result of the Doppler effect, a incoming radiation seems to be more hot, and an overtaking radiation seems to be more cold. This example shows that for observer of any point of the Universe this CMBR is isotropic. We may consider this observer and the connected reference frame as selected one. The selected reference frame existence at the Universe every point looks like the physicists commonly held view preceding to Relativity. They thought that the light presented ether oscillations occupying whole the Universe. They thought also that a reference frame connected with ether was preferable, or selected. They tried to detect the Earth motion relative to ether. We know that these experiments gave the negative result: any ether doesn't exist. But the Universe evolution follows that when CMBR is observed (and only in this case!), the selected reference frame (called sometime "new ether") appears. ***The new ether or CMBR just realises the motion according to Hubble's law.***

The modern NASA's data allows to put the relation of the Solar system velocity to the velocity of light equal to 0,15%. It is enough small value justified Special Relativity and Minkowski geometry relationships application. But can we believe this phenomenon to be an exhaustive proof of the SEUT accuracy?

To test it we propose a not complicated observational experiment. If the CMBR anisotropy is due to the real selected frame existence, then it may be detected for any electromagnetic radiation. In particular, an anisotropy of solar radiation has to exist at the different year periods. It has to be detectable in August, when the both solar radiation and CMBR come to the Earth from the Lion costellation side (see Fig. 4). In February these sourses are opposite in disposition relative to the Earth, therefore the solar radiation anisotropy direction has to be opposite. The expected effect value (with account of the Lion constellation straight ascendancy and obliquity of the ecliptic) is approximately equal to 300 km/s, i.e. nearly 0,1% of the velocity of light. In November and May the anysotropy has to be practically absent.



Fig. 4
The Sun and Lion constellation disposition relative to the Earth

Probably, an analogous SEUT test in a laboratry is realizable with help of artificial radiation sources.

Particle mass, energy and impulse

So, we consider the Universe as expanding 3D-hypersurface of a 4D-sphere. Mass localisation places in the Universe present the points of the hypersurface intersection by world lines. So, **these world lines have a real physical meaning, not abstract illustrative** this one. We may expect this physical meaning to be more essential than simple word expression.

Particularly, while the Universe global analysis is making, we may suppose that such fundamental particle feature as its mass at rest presents some *relative* value. Such relation (some kind of a quantum number) may include, for example, 4D-sphere (the Universe) diameter and some characteristic size like de Broglie wave period that is inversely proportional to the mass. This hypothesis may make clear *inertia* nature as two characteristic times *relation*. It may also explain the *rest-energy* notion.

Meanwhile, the Universe radius increases with time. Well, what happens to mass? If a de Broglie wave period increased proportionally to time, we couldn't generally detect the Universe expansion, including famous "red shift". But if particle wave periods are constant, then *matter mass has to rise proportionally to the Universe age and size*.

In the Relativity (like Minkowski geometry) we use vectors having imaginary projection to time axis and real projections to space ones. Particularly, it is true for velocity, acceleration, and energy-impulse 4-vectors. As against, vectors having all the real components are only used in the SEUT. At that, a 4-interval value (length in pseudo-Euclidean space) of some relativistic vector answers the absolute time axis projection of a corresponding SEUT-vector, and imaginary component of a relativistic vector (time of motion) answers the corresponding vector length in purely Euclidean continuum of the SEUT. For example, the energy-impulse vector module presents such quantity. Its projection to absolute time axis is energy at rest divided by velocity of light, and its projections to spatial axis are impulse components. This quantity is *constant* while the particle movement is *inertial* one.

A jump to *non-inertial* motion in the SEUT is connected with a corresponding state vector *changement* law. So, if particle motion velocity changes, its *energy at rest* doesn't change, therefore full acceleration at a time interval can be calculated using the difference between new and old impulse values. Thus, the non-uniform motion equation in the SEUT can be found like SR as time derivative of an impulse expression.

The force-acceleration relation depends on a mutual orientation of force and velocity vectors in the both SR and SEUT. But in Relativity a reference frame velocity can be choised arbitrary, for example it can be zero, then the relation will be equal to one.

On the contrary, in the SEUT an *absolute* velocity is presented, it is defined by the world line inclination relative to the normal. Let the Earth move with any velocity relative to the immovable (selected) reference frame. Then we will be able to detect the absolute velocity using two measurements, the first one along the world line, and the second one in a perpendicular direction.

If this absolute velocity is really defined by direction and value following from CMBR anisotropy effect, then we can expect a relative difference near $2{,}25 \cdot 10^{-6}$ between longitudinal acceleration and transversal one.

Local gravitational fields of particles

What does the SEUT talk about body gravitational fields? Let us imagine all the bodies as immovable and drifting exactly along the *radial* world lines. If there is a mutual gravity attraction effect between two bodies in such Universe, an observer will detect some curvature of their world lines. They will seem to be bending one to another instead of a radial divergence. In essence, in this case we may replace a world line by a gravitational field line. Then the analogy allows us to identify an Universe isochronous intersection with an equal potential surface that these field lines have to be *normal* to this surface. So, we arrive to a presentation that a Universe isochronous intersection is not strictly concentric hypersurface. It is perturbed by some kind of craters (see Fig.5), that centres correspond with gravitating bodies.



Fig. 5
Local body gravitation field

The inclination angle of a crater profile relative to non-perturbed sphere hypersurface is equal exactly to the inclination angle of a normal relative to strict radial direction. Hence, a local gravitation field intencity measure agrees practically in each point with body velocity measure that we used earlier. It authorizes energy concept using for both mechanical motion and gravitation phenomenon.

SEUT and General Relativity

Let us discuss some GR's aspects. Is it acceptable to neglect pressure of matter? When Einstein searched for his early cosmological static model solution, he had to introduce a cosmic constant in his equation. This constant answered a ***negative matter pressure***, that Einstein could not determine a meaning. In a non-stationary model a solution exists independently on cosmic constant presence, therefore it may be put often as zero. As rule, bodies' velocities may be put as zero too; therefore (*dynamic*) pressure is usually neglected.

However, we insist on necessity to account a *static* pressure of gravitating matter. Really, it can be ignored in the case when Einstein's relativity principle is applicable. Accordingly with it a gravitation field can be *always* replaced by reference accelerated frame. In this case a purely kinematical side is only accounted. However, *not every* field may be considered (even locally) as uniform one (see Fig. 6). Let the radius of a field source (or a *probe particle*) have the same order that the mutual distance. Then the Einstein's equation connecting space geometry with matter physical features seems to be incomplete. More precisely, it is incorrect to put exactly equal to zero a static pressure in the matter density tensor, it is necessary to introduce its (unknown, calculable) value accounting **the *continuum deformation energy*.**



Fig. 6
At the left a locally uniform gravitation field is presented, the right field can't be considered as uniform one even locally

Are the proposed amendments important? Specialists know, that the Metagalaxy gravitation radius is *in fact* comparable with its real size. **In [2] we have showed that the Universe radius was *less* than its gravitation radius.**

It is shown also in the same work [2], that a resulting gravitational pressure in the Universe is *negative* and it is responsible for the Einstein's cosmic constant. This fact seems to be evident because a gravitation force aims to *gripe* any matter accumulation. **But it is possible to conclude it by a non-trivial way.** Let us consider a matter pressure as a reactive force operating within a uniform sphere of incompressible liquid. A pressure dependence on internal density is presented in [7]. We can see [2], **that if the sphere gravitation radius exceeds its geometric radius not more than approximately 1% (or it is still less), then a sudden negative change of the pressure appears at the internal abroad. This phenomenon may be explained as a volume "expansion" due to a metrics perturbation.**

The consideration of static pressure allows not only to find out a *new* (linear in time) cosmologic solution, but also to calculate a dependence of the Universe gravitational pressure on the radius of the Universe. This *negative* value has the representation like that one for a non-relativistic sphere (a star or a planet, for example). Also we would like to note, the formulation of density-Universe radius in the SEUT is exactly the same that the formulation of so-called *critical* density in the EF-model.

Two very important circumstances are clarified for all that. First, the **Universe mass was turned out as *linearly increasing* function of the 4D-sphere radius, and it is not a constant. A famous Einstein's programme is realized unexpectedly in the SEUT: a matter features (density) are reduced to a space features (curvature).** In other words, a necessity to introduce a mass distribution in the equations externally ("by hands") is eliminated in the SEUT. This operation is need in the GR to find out a spatial metrics changement law.

Secondly, the seeming paradoxicality of University mass (and energy!) non-conservation make us to reflect on conditions that the *accomplishment* allows to the energy conservation law correctness (see Fig.7).



Fig. 7
If space features *do not depend* on time, then the closed system energy is *constant* (at the left). But if space features *evolve* in time, then the isolated system energy *have not to be constant*.

It is evident, we believe, that the energy can be exactly constant only in such physical system (or in whole the Universe) for which space features (in particular, a curvature) are strictly constant in time also. However, the both modern physics and SEUT issue from the opposite concept. Hence, this state can only be accomplished approximately, moderately of a bit of the modern rate of a relative space curvature evolution. This rate has order 10^{-10} per year for the modern Universe.

N.A.Kozyrev [1] basing on astrophysical observations stated the common star radiation origin that has to be due to the time-energy transformation. Accordinly with the SEUT, the relative increment of star mass (and its rest energy) is equal to the Universe age relative increment. It is interesting that the Sun mass relative lost due to the radiation consists in 10^{-15} per year, i.e. five orders less than mentioned above energy increment.

Universe origin and closed geometry

The cosmological EF-model could not say anything on the Universe origin. On the contrary, the work [2] approach allows an obvious way to study the problem.

As it is noted in [7], the metrics of any sphere area having a non-zero density is perturbed relative to Euclidean one, its geometry agrees with 4D-sphere hypersurface geometry. For non-collapsing sphere its gravitation potential relief is like a very small *"pit"* that gravitation radius is much less than its geometric size. However, when the density rises, the metrics perturbs more and more, and the pit transforms to some kind of *"crater"*. The crater is connected with the external surface by a narrow neck. Only this neck or its part is visible for an external observer, and the gravitation insurmountable barrier transmutes an object central area into "a lost world".

From the point of view of the external world, the central area presents a "black hole" absorbing irreversibly all the matter and radiation. On the other hand, for our Universe inhabitant the "navel-string" connecting with the external world has to seem a spherical "white hole", to which a matter and radiation are coming continuously (and, may be, carry out an information on the external world features). There is an old Russian fiction science book called "Sannikov Land", where an internal gigantic trench concerning central small star is described. Our model seems to be like this picture.

Is it possible that we live in such a black hole? The present hypothesis answers affirmatively this question. The negative sign of the matter pressure due to continuously increasing of our world size allows to such conclusion. And the University self-closing can be physically explained by the way.

On the other hand, as it is shown in [2], in spite of matter average density negligibly small, the Universe gravitation radius is more than its geometrical radius; hence, it presents a black hole. This condition accomplishment agrees the Universe self-closing, the boundary absence in spite of its finite volume. Also, this fact confirms our assumption that the Universe rest energy localisation area does not exceed the gravity operation area.

A specific model of star collapse is created in the modern General Relativity. In general, it can study in *three* different reference frames. As a rule, the "point mass" models are used. *The first* model is linked with an external observer; the *second* one accompanies a matter falling to the black hole. *The third* model presents an internal reference frame, i.e. an observer within collapsing object.

From an external observer's point of view the matter falling time to the black hole is infinitely large. However, in an accompanying reference frame it is finite. Since in the accompanying reference frame time and space coordinates are expressed through the both types of external reference frame coordinates. What is more, in the internal reference frame the time and space coordinates quite trade places, the metrics tensor components are depending on time. Further, any matter point history in this accompanying reference frame starts at the zero moment and finishes after same universal time period in a special (singular) point, after which nothing exists ("time barrier").

As we believe, another lacing between internal and external collapse pictures will be possible, if we consider a non-point collapsing object. Nobody wonders now at a situation, when a time period can be finite in one reference frame and infinite in another one. **Therefore, we can believe, unlimited black hole *collapse* in the external Super-Universe may seem to present unlimited *expansion* of our Universe observing inside.** This expansion seems to *start* from a singular point, and the same point is the history end of all the matter of the external Super-Universe that fall to the black hole. I would like to note especially, it does not mean that internal time pass in opposite to external one. **Rather, it is possible to state, time within a black hole passes ortogonally to external one.**

References

1. Kozyrev N.A. Selected works. - Leningrad University, 1991.
2. Shulman N.H. Site of the Institute of time nature exploration (Russian-language version): www.chronos.msu.ru , Project of Chair-laboratory of time as phenomenon of expansion, 2001.
3. Vladimirov Yu. S. Relational theory of space-time and interactions. Part 2. Theory of physical ineractions. Moscow university, 1998.
4. Sharov A.S., Novikov I.D. A man, who discovered the Univerce explosion. Edvin Hubbl's life and work. Moscow, Science, 1989.
5. Einstein A. The essence of Relativity. Moscow, IL, 1955.
6. Wineberg S. First three minutes. The modern approach to the Univerce origin. Moscow, Energoizdat, 1981.
7. Tholmen R. Relativity, thermodynamics and cosmology. Moscow, Science, 1974.

INFINITE ENERGY
Cold Fusion and New Energy Technology
Including Conventional and Renewable Energy


INFINITE ENERGY
The Death of ENTROPY
Can Maxwell's Demon Be Captured?
Dirac's Equation and the "Sea of Negative Energy"

Infinite Energy Magazine
✳ Cold Fusion ✳ New Energy
✳ New Science
✳ New Technology

Subscriptions, 6 Issues Per Year
$29.95 North America
$49.95 Foreign

Single Sample Copy
$5.95 North America, $10.00 Foreign

Infinite Energy Magazine
P.O. Box 2816-FV
Concord, NH 03302-2816
Phone: 603-228-4516 Fax: 603-224-5975
http://www.infinite-energy.com

ELECTRIFYING TIMES

an online and published magazine about Electric, Hybrid, Fuel Cell Vehicles, advanced batteries, ultra capacitors, fuel cells, microturbines, free energy systems, events and exhibitions worldwide

63600 Deschutes Mkt Rd, Bend Oregon, 97701
541-388-1908, fax 541-388-2750
etimes@teleport.com
www.electrifyingtimes.com
Subscription $13/3 issues

Institute for Planetary Synthesis

P.O. Box 128, CH-1211 Geneva 20,
Switzerland
Tel. 41-022-733.88.76, Fax 41-022-733.66.49
E-mail: ipsbox@ipsgeneva.com

website: http://www.ipsgeneva.com

The Experiments on Thermo-Gravitation

This review of the article by Alexander P. Schegolev, the scientist from Saint Petersburg, was received by NET editors from our reader vladrim@mail.ru and presents his own view about Schegolev's experiment [1]. The opinion of our editorial board is not fully in agreement with the author's conclusion. Also we have no information who is vladrim@mail.ru.

It is known from the science history that the very experiment gives a push to revising of old knowledge; it also checks the new designs and conclusions. The knowledge of physical theories is based on the experiment; the experiment confirms hypothesizes or refuses them. Making experiments, we ask questions to the nature. And it always answers us on the clear pointed question. However…

Michael Faraday was trying in vain to find out the relationship between gravitation and electricity. These experiments were repeated on the modern level. Further, there was made an attempt to screen gravity force, the influence of environment on gravity was also trying to be researched. Many efforts were spent on finding out of the gravitational radiation falling to the Earth from depths of the Universe, as well as artificial generation of gravitational waves.

The experimental studies of weight change must be under attention. In particular, the attempt to find the differences in weight after sharp turning of body from the quiescent state into the state of rotation around its own axis was undertaken. The experiments of the influence of strong magnetic field and temperature on the weight of a body were made.

But alas! No changes of weight were discovered in previous experiment *(Editorial: Perhaps, the author has no information about sucessful results. We reported about such results in our magazine)*. Analyzing these experiments and theoretical premises, the author of the given article has made an unusual experiment imitating the heat motion in the Earth from core to peripheries. For that experiment there was used the steel ball with 100 mm diameter. The cone hole was made in the ball up to its center. The ball was installed by the hole upwards on laboratory scales with 50 mg scale factor and laser beam was directed inside (into the hole). The directed heat flow outgoing from the center of the ball was created by this way. While the surface temperature increasing, the arrow of scales became to be rejected aside weight decrease. The temperature was measured by the contact thermocouple. After an hour and half, approximately, when the temperature was 300 degrees Celsius the laser was switched off. The difference (the decrease) in weight against initial value (in the cold state) was four grams per 4200 grams of the test body.



Fig. 1
The ball with cone hollow

Further, the ball was getting cold slowly on the scales and its arrow was creeping to the initial position. For acceleration of this process, the ball was periodically blown on by pressure air. It was the check, if the air (heated by the ball) influences on scales or not. The stability of its data independently on actions of pressure air stream excludes such suggestion. When the temperature of the ball became the same with room temperature, its weight return to the value nearly initial. However it is necessary to add, that this "nearly" is about 200 mg. This confirms that the change of the weight was not occurred because of the evaporations of metal from action of laser beam, and we were the witnesses of absolutely unusual phenomenon. *(Editorial: Perhaps, it is necessary to take into account the deformation).*

That is all concerning the question, which was given to nature by the author of the given article. However, one more doubt remains: did the heat radiation (coming from the ball) affect on mechanism of scales? To check this, the control experiment was made, under which the same ball was heated by usual way in the electrical furnace. In spite of its temperature was about 600 degrees Celsius and the ball was placed on scales for a long time (until full cooling down), the arrow did not move from the initial position. Thus, we have really turned out face to face with a phenomenon requiring an explanation.

If the weight change in this experiment has happened in consequence of gravitational interaction, then, therefore we must revise some fundamental concepts. Today it is difficult even to assume the consequences. The only thing, which is possible to say certainly, is **that divergent on radius uni-directional (single-vector) heat flow** is the object for observation, absolutely unknown to us or unnoticed before, which holds the ensemble of surprises. Up to now, we have dealt only with **chaotic** heat motion, which was researched by the thermodynamics and heat transmission.

For analogy, it is possible to give the example **of the electric current arising, which is possible to get only under directed electrons moving.** In general, more than ten experiments were made, and all of them have given the same result: the weight of the body was decreased. Who will solve this enigma?

Editor's note: The question is presented above. The answer is the aetherodynamics theory. Any directed (unidirectional) heat flow is also a flow of aether. The mass changes are the demonstration of natural mechanism of existence of this mass as aether vortex (Alexander V. Frolov).

References

1. Collected reports "Untraditional scientific ideas about nature and its phenomena", #1, club FENID, Gomel, 1991.

The RotoVerter from arkresearch

Editor's: The description of this invention was received from Hector D. Perez Torrez, designer of the "RV" Rotoverter and TV transverter OU "transformation" devices.

Here is the first prototype, used to test a 3PH generator. Light bulb was a 100W 120V, AC generator required 380W for excitation to 120VAC plus the light bulb load for a total of 480W. Input to rotoverter was 240W for a total of 200% efficiency from the prime mover. Friction loss and prime mover loss was not calculated, PF unity, 120VAC unto a purely resistive load excitation pure DC120VDC3.1666667A (380W) + 100W = 480W. -240W=240 excess.

It is a common 3PH dual winding 230/460V motor wired to 480V run at 120v as a ROTOPHASE converter. That's the beauty of it, OFF the shelve components preferably totally enclosed motors (so fan can be removed) low friction bearings, from 3HP to 7.5HP. Re-rating hp can be from 1/7 to 1/3 the original HP (some motors can run up to 1/2 HP capacity but will require extreme care and cooling.... and exact tuning to load).

System requires starting and running capacitance; the perfect starting capacitance is the one that gives same plate current value as 480V but running at 120V. The best running capacitance is the one that gives the lowest Amperage reading at programmed load. (ALL capacitors are AC 370V OIL "no electrolytic").

Some motors are better than others; also for generator use you must choose the over-unity generator and motor combination to obtain OU. It looks easy to gain it, but requires quite a good choice of items and common sense. In this Research we have found even a few turns or a run weld in stator can change drastically the results. Up to date best performance has being obtained from US (motors 7.5 HP, BALDOR 3,5, HP, GE 3HP totally enclosed, dual winding 230/460V). Higher HP will require professional expertise in industrial electricity and power eng. (not recommended for amateur experimenter). Anyone engaged in this experiments must be familiar with safety procedures and basic electric and mechanic knowledge. Voltages and rotating machinery must be handled with great care. SEE basic diagram and connection.



Fig. 1

Latest UPDATE BELOW 7-01-02


ARK RESEARCH 2002
EXPERIMENT ON MAGNETIC ROTO AMPLIFICATION
Starting current > 9.0 A
running voltage 120.0 V
running current 3.00 A
PT 360.0 w
RLY1 contact Switch
C2 90uf 600v
C1 1200V 22.5uf
L1
L2
L3
S
A
RLY1
8A
AC IN 120V
MOTOR # 1 [PRIME MOVER]
Rotor mechanical link
MOTOR # 2 [ALTERNATOR]
C3 CAPACITORS TRIPLE FLUX WYE
?mF 370V
"?"mF 370V
130V 4.8A AC 10:1 49.0A 13V AC
DIODES
ANTINODE 3PH AT 0 POINT RES.
49A AC
AC.V 0
0V
130VAC
12.7 VDC
48
100 A m
+10 ADC 127W GAIN
100A
OUTPUT m
10
C.SHUNT
48 ADC
BATT.
LOAD 1HP
S
300,000mF 24VDC
12VDC TO 120VAC INVERTER
120VAC
12VDC 38 ADC
+ 456W OUT
RV - 360W IN
EFF.LOSS 96 W OU
+ 127 W B+
223 W OU!
L1,L2,L3 3PH 7.5 HP 3465 RPM
460 V MOTOR 184TCH
L1,L2,L3 SAME BUT WIRED FOR 230 V
THERMAL & MECHANICAL LOSS WAS NOT CALCULATED

Fig.2

Subject: RV Basic level 1 Full MODEL Disclosure (Public domain)

This is the RV (Level 1) plan of a full looped RV system:

Battery provides primary power for 12VDC to 120VAC. As to run prime mover (Roto-converter), second motor acts as ansquirrel cage self-exited generator, a triple flux-capacitor LC tank tuned to best Standing wave condition as to create standing wave current node internally in battery at 0 voltage to battery "negative resistor". At 0 volts "voltage" a negative current is created as to maintain a reverse flow (charge) to battery exceeding the forward drain of the inverter demand, detuning system with a forward charge at 10 amperes with a voltage rise of approximately 0.83333 V over the battery. Voltage charge produces OU transform from the 0 point standing wave component. System gains energy from stochastic resonance within the LC tank components draining energy from "thermal" signature of the Aether and K thermodynamic-thermoelectric ambient heat (Electron spin). This is a full disclosure of an operational and tested device. System is made of standard off shelve items. Tuning is made by changing capacitor values and the proper selection of standard items for its construction, 3PH motors, 10:1 12V or 5:1 24V transformers with the proper core and winding values (standard) off shelve, diode bridges capacitor (all standard).

Warning: System opens (NON standard) space-time anomaly as time is reversed due to aether energy transform....
Extreme warning: Do not exceed 10KW Nor use of trans-uranic elements near unit as they may reach critical mass by regressive "inversed" decay. PB 206, U235, U238 must be maintained as far as possible from unit.
Extreme Warning: Dangerous Toy, Eldridge, Event horizon and hell raiser effects may be created by protoplasmic fields at extreme potentials PK.
Use wisely. You Can create Paradise or open the gates to Armageddon.

The choice is yours now....

Hector D Perez Torrez

Lifter Project
by Jean-Louis Naudin
http://www.jlnlabs.org



Mouse aboard!

The 1st Worldwide Electronaut Lifter Project

ISSN 1684-7288

New Energy Technologies

Printed version ISSN 1684-7288
Online version ISSN 1684-9698

Published by Faraday Laboratories Ltd. *Issue #1 (10), 2003*
Research on advanced aerospace systems and new energy sources

Single-Wire Electric Power Transmission 20 kWt!

News from France

Electrostatic propulsion: 60g payload

Also in this issue:

- Cold Fusion by Plasma Electrolysis of Water
- News of Hydrogen Energetics
- Unusual Permanent Magnet Motors
- New Energy and Propulsion Systems

New Energy Technologies magazine
Back issues 2001-2002



Julia V. Sukhova
Translator



Kate M. Pomerantseva
Designer

Olga O. Leontyeva
Editor

New Energy Technologies
History of invention: Poliakov's vortex drive
7 KW output
35% weight loss
Time Machine
Time Control experiments
Acad. Oleg Gritskevich's Hydro Magnetic Dynamo: 1500 KWt power without any fuel!
September-October 2001
MEG 500%
ball lightning

Happy New Year!
2003

Kirill P. Butusov
Scientific Advisor



Alexander V. Frolov
General Director
"Faraday Laboratory" Ltd

Searl Effect Technology

http://www.sisrc.com



Experimental craft construction (self-rotating permanent magnet system)



15 kWt

Searl Effect Generator

LENR Experiments

(Low Energy Nuclear Reactions)

"Cold Fusion"

http://www.lenr-canr.org





Read in this issue!

NEW ENERGY TECHNOLOGIES #10

1. Testatika. Review of well-known electrostatic system.
2. Cold Fusion by Plasma Electrolysis of Water. Ph.M. Kanarev, T. Mizuno
3. Cold Fusion: What is it and what does it mean to science and society? E. Storms
4. Technical Introduction to LENR-CANR (Low Energy Nuclear Reactions). E. Storms
5. It started in 1989… (History of Cold Fusion Development). P. Hagelstein
6. A Science Tutorial (Cold fusion). T. Chubb
7. LENR (Low Energy Nuclear Reactions) Experiments.
8. On Electrogravitation. A.V. Lemeshko
9. Avalanchedrive Propulsion Device. M.L. Filho
10. Hydrogen-Powered Vehicles. P. Behr, G. Schneider
11. Unusual Permanent Magnet Motors. T. Valone
12. Hydrogen Energetics. A. Pashova
13. On the Longitudinal Electromagnetic Waves. A.V. Frolov
14. Space and Terrestrial Transportation and Energy Technologies. T.C. Loder
15. Commercialising the “Searl Effect”.
16. Interesting Publications of the Last Year.
17. “Lifter” Project
18. New Electric Fire Technology. V.D. Dudyshev
19. New Effect of “Cold” Evaporation. V.D. Dudyshev
20. Conceptual Hurdles to New Millennium Physics. D. Reed
21. Resonant Phenomena Occurring in Alternating Current Circuit. A.V. Frolov
22. Books Review

TESTATIKA

Review of well-known electrostatic system

Editor comments by Alexander V. Frolov
General Director, Faraday Lab Ltd

A running "free energy" machine coming from Switzerland, Europe. It was developed over a 20 years Research period by a religious group called Methernitha. This group lives in Linden, Switzerland. The head engineer of this superb machine, Mr. Paul Baumann discovered its principles while observing nature. He claims its running principle was found by studying the lightning effects from nature. The documents being offered here shed light on this energy marvel.



These documents are the result of work of people who have witnessed this wonder machine over the years... And here are the facts:

- The Testatika is a rotary-type machine that runs on it's own, once started by revolving it's two discs by hand!
- The machine not only runs on it's own energy, but produces also a huge amount of excess power, at least 3 KWtt of power! This is almost enough to supply a small house with one machine!
- The machine is about 70cm wide, by 40cm deep and is about 60cm in height!
- It delivers from 250 volts to about 320 volts direct current, depending on the humidity in the air! At this voltage it can supply at least 10 Amperes of pulsating direct current!
- Testatika is not a perpetual motion device, but an energy machine that collects it's huge amount of energy from the ions contained in air. However, there are some technological secrets implemented to overcome the normal drag-resistance of conventional generators. This is but one of it's secrets held by the Methernitha group.

There are many different sized Testatika machines, some of the smaller units deliver only about 200 to 300 watts, none of which are mass-produced. These devices are still laboratory prototype units.

Methernitha is a spiritual community (Christian Alliance) http://www.methernitha.com. They wrote: "We are fortunate in gaining the experience that paradoxically the most beautiful and useful results can be achieved by just using the most simple means. Never did we use any borrowed capital because we want to stay free Swiss citizens and do not want to be hindered or even bound in any way in the pursuance of our aims."

The two contrary-rotating discs generate an electrostatic charge. One disc represents the earth, the other the cloud. Using grid electrodes the charges are bound. After that they are collected by non-contacting so-called antenna keys and then sorted.

After being initially turned on by hand, the discs rotate by themselves according to the electrostatic laws about attraction and repulsion. A rectifying diode keeps the cycles in steady state. Otherwise the impulses of attraction and repulsion would accumulate and cause the discs to run faster and faster. The correct speed is of great importance and for optimal power generation the discs have to run quite steady and slow.



By means of grid condensers the energy is stored and then uniformly discharged, at the same time reducing the high voltage and building up power with additional devices. Finally the machine supplies a uniform direct current, which varies according to the size of the model. The machine furnishes about 3-4 kWt permanent output, depending on humidity, whereby the electric potential ranges from 270 to 320 Volt. High humidity of the atmosphere prevents the build-up of electric potential. The drier the air is, the better.

(Editor: It is necessary to note that the analogues method was used by Russian inventor Pavel N. Yablochkov who in 1877 take out a patent #120684 "The system of distribution and amplification of electrical currents by means of atmosphere electricity..." As it was shown by Yablochkov devices, power doubled in lamps, though current of consumption did not increse.)

No doubt, through the so far achieved results one main objective has been reached, namely to prove that it is possible to use Free Energy. Nevertheless the research work is not yet completed.

To the educated physicist many things of this machine may seem impossible, maybe even crazy. Maybe he is also offended by the conceptions used to explain the whole. Only partly we could use the concepts of conventional physical terminology to explain and define only approximately the functions and properties of the various parts of the machine.

After all it will be necessary to create some more new concepts like the one we have already used before, when we termed the non-contacting collectors of electric charges as antenna keys.

This machine puts experts, which are just trained in conventional physics to a very hard test, because its mode of action is not explainable with the state of the art of officially accepted physical knowledge, or at the most only partially explainable. However also a trained specialist should remain free and independent in his thinking, and should avoid to be limited by the temporal framework of publicly admitted knowledge in any science.

It has to be noted that the established science was already many times forced to change or give up some of its very fundamental concepts. Think about Galilee, to name only one example. Our human society almost condemned this man as a sorcerer and magician, just because he investigated and discovered a truth that seemed unacceptable by the established science of the days.

The book knowledge of any times is not wrong, but it is incomplete, and therefore allows to draw wrong conclusions.

There was used information from the official web site: http://www.methernitha.com

Official adress of Methernitha: Methernitha Genossenschaft Administration, Moosbuehlweg 2, 3517, Linden, SWITZERLAND

Official E-mail of Methernitha: info@methernitha.com

New Energy Technologies

PRINT EDITION ADVERTIZING RATES

Full Page Ad

B/W - $400

Color - $800

Half Page Ad

B/W - $200

Color - $400

Quarter Page Ad

B/W -$100

Color- $200

Ask about discounts for multiple ads

New Energy Technologies is distributed in the leading Scientific Laboratories in Russia and has subscribers in more than 20 countries all over the world

To advertise contact us:
Faraday Labs Ltd, Phone/fax: 7-812-380-3844
http://www.faraday.ru, office@faraday.ru

COLD FUSION BY PLASMA ELECTROLYSIS OF WATER

Ph.M. Kanarev
The Kuban State Agrarian University,
Department of Theoretical Mechanics
13, Kalinin Street, 350044 Krasnodar, Russia
E-mail: kanphil@mail.kuban.ru

Tadahiko Mizuno
Faculty of Engineering, Hokkaido University,
Kita-ku, North 13, West-8 Sapporo 060-8628, Japan

Abstract: It has been disclosed that transmutation of the atomic nuclei of alkaline metals and the atomic nuclei of the cathode material takes place during plasma electrolysis of water.

Key words: atom, nucleus, proton, neutron, electron, cathode, low-current.

INTRODUCTION

Cold nuclear fusion is the first hypothesis of a source of additional energy in heavy water electrolysis. Fleischmann and Pons, the American electrochemists, are the authors of this hypothesis [1]. They reported about it in 1989. Since that time a large number of experiments has been carried out in order to obtain additional energy from water [2], [3], [4], [5], [7], [8], [9], [10], [11], [12]. We continue to discuss this problem.

THE FIRST EXPERIMENTAL PART

In order to check this hypothesis, the following experiments were performed. Two cathodes were made of iron with mass of 18.10 g and 18.15 g. The first cathode operated during 10 hours in KOH solution; the second cathode operated during the same period in NaOH solution. Mass of the first cathode remained unchanged; mass of the second one was reduced by 0.02 g. The voltage by plasmaelectrolysis process was 220 V and the current (0.5-1.0) A (Fig.1). The indices of the consumption of the solution and the gases being generated were as follows (Table 1).



Fig. 1.
Diagram of gas generator. Patent # 2175027:
1 - lid of the reactor; 3 - body of the reactor; 6 - the cathode; 9 - the anode; 11 - solution dosing unit; 16 - cooler; 20 - pipe for gas release; 23 – anemometer

Table 1
Experimental results

Indices	Water consumption, kg	Volume of gases,m^3	Energy expenses, kWh/m^3
KOH	0.272	8.75	0.28
NaOH	0.445	12.66	0.21

In order to increase safety of experimental results, the volume of the gases introduced with the help of anemometer is reduced twofold.

It is known that from one litre of water it is possible to produce 1220 litres of hydrogen and 622 litres of oxygen. Quantity of the gases generated by the plasma electrolytic process is much greater than it is possible to get from consumed water (Table 1) [6]. It gives the reason to think that not only water molecules, but also the nuclei of alkaline metals and the atomic nuclei of the cathode material serve as a source of these gases. The analysing experiment has been performed in order to check this fact.

Tadahiko Mizuno, the famous Japanese scientist (the co-author of this article), who works at the Division of Quantum Energy Engineering Research group of Nuclear System Engineering, laboratory of Nuclear Material System, Faculty of Engineering, Hokkaido University, Japan, kindly agreed to perform chemical analysis of the cathode samples with the help of the nuclear spectroscopy method (EDX). Here are the results of his analysis. The content of chemical elements on the surface of non-operating cathode is as follows (Table 2).

Table 2
Chemical composition of the cathode surface prior its operation in the solution

Element	Fe
%	99.90

The new chemical elements have appeared on the working surface of the cathode, which works in KOH solution (Table 3).

Table 3
Chemical composition of the surface of the cathode, which operates in KOH solution

Element	Si	K	Cr	Fe	Cu
%	0.94	4.50	1.90	93.00	0.45

The chemical composition of the surface of the cathode, which operates in NaOH has proved to be different (Table 4).

Table 4
Chemical composition of the surface of the cathode, which operates in NaOH solution

Element	Al	Si	Cl	K	Ca	Cr	Fe	Cu
%	1.10	0.55	0.20	0.60	0.40	1.60	94.00	0.65

Thus, the hypothesis concerning the participation of the nuclei of alkaline metals and the atomic nuclei of the cathode material in the formation of gases during plasma electrolysis of water has experimental confirmation. Let us carry out the preliminary analysis of the data being obtained (Tables 2, 3, 4).

THE FIRST THEORETICAL PART

In any of these cases, the atoms and the molecules of hydrogen are formed. The part of it is burned and the other goes out with the steam. We have already shown that the processes of fusion of the atoms and the molecules of hydrogen and its isotopes result in occurrence of additional thermal energy [6]. Numerous experiments show that up to 50% of additional thermal energy are generated during the plasma electrolysis of water, it is less than the results of the calculations originating from the existing cold fusion theories [6]. That's why it is necessary to analyse energetics of the particle creation process during the atomic nucleus transmutation.

Having considered the model of the electron we have found out that it can exist in a free state only when it has a definite electromagnetic mass [6]. Being combined with the atomic nucleus it emits a part of energy in the form of the photons, and its electromagnetic mass is reduced. But stability of its condition does not become worse, because the energy carried away by the photons is compensated by binding energy of the electron in the atomic nucleus [6].

If the ambient temperature is increased, the electron begins to absorb the thermal photons and to pass to higher energy levels of the atom reducing binding with it. When the electron becomes free, it interacts with the atom only if the ambient temperature is reduced. As this temperature is reduced, it will emit the photons and sink to lower energy levels [6].

If the electron is in a free state due to an accidental external influence on the atom and the environment has no photons, which are necessary for it to restore its mass, **it begins to absorb the ether from the environment and to restore its constants in such a way**: mass, charge, magnetic moment, spin and radius of rotation. The electron acquires the stable free state only after it has restored its all constants [6].

Thus, if an interchange of the free state and binding state with the atom takes place due to the accidental influences on the atom, **the electron restores its electromagnetic mass every time due to absorbing the ether. It means that actually it plays the role of a converter of the ether energy into the thermal photon energy.**

The Japanese investigators Ohmori and Mizuno [4] registered neutron radiation during plasma electrolysis of water and reported that not only the nuclear process, but also the process of the electron capture by the free protons can be the source of this radiation.

As hydrogen plasma is generated during the plasma electrolytic process of water electrolysis, there exists a tendency of the capture of the free electrons by them.

It is known that rest mass of the electron is $m_e = 9.109534 \times 10^{-31}$ *kg*, rest mass of the proton is $m_p = 1.6726485 \times 10^{-27}$ *kg*, and rest mass of the neutron is $m_n = 1.6749543 \times 10^{-27}$ *kg*. The difference between the mass of the neutron and the mass of the proton is equal to $\Delta m_{np} = 23.058 \times 10^{-31}$ *kg*. It is $23.058 \times 10^{-31} / 9.109 \times 10^{-31} = 2.531$ of the mass of the electron. Thus, the proton should capture 2.531 electrons in order to become the neutron. The question arises at once: what will happen to the remained of electron mass $(3.0-2.531)m_e = 0.469m_e$? The disturbed balance of masses in this process is explained by modern physics in a simple way: a neutrino is created [6].

As the neutrino has no charge, it is very difficult to register it. If the neutrino takes the excess mass away or replenish the lacking one, can the elementary particles execute this process by themselves?

As the photons are emitted and absorbed only by the electrons, the proton, which absorbs the electrons, cannot convert the remainder of mass of the third electron into the photon. If the electron is absorbed by the third one and gives more than a half of its mass to the proton in order to convert it into the neutron, the remaining part of mass ($0.469m_e$) of the electron, which has no possibility to become the photon, is converted into a portion of the ether, which "is dissolved" and mixed with the ether in the space. The fact that plasma has no photons with the mass corresponding to the part of mass of the third electron, which has not been absorbed by the proton during its conversion into the neutron, can serve as a proof of such affirmation. Let us calculate energy of such photon [6].

The difference the mass of the neutron and the proton is equal to $\Delta m_{np} = 23.058 \times 10^{-31}$ *kg*. If we subtract this value from the mass of three electrons, we'll get mass m_F, from which the photon should be formed [6]

$$m_F = 3m_e - \Delta m_{np} = 3 \times 9.109534 \times 10^{-31} - 23.05810^{-31} = 4.270602 \times 10^{-31}\ \text{kg} \qquad (1)$$

If the photon is formed from this remainder of mass m_F, its energy will be [6]:

$$E_{ph} = m_F \times C^2 = \frac{4.270602 \times 10^{-31} \times (2.997924 \times 10^{8})^2}{1.602189 \times 10^{-19}} = 23.956126 \times 10^{4}\, eV \qquad (2)$$

This value of energy corresponds to roentgen spectrum, that's why the creation of each free neutron should be accompanied by the creation of one roentgen photon. If it does not take place, we have two opportunities: the first one – we should think that in the case when the neutron is created, the neutrino was formed from mass $m_F=4.270602 \times 10_{-31}$ *kg* and flew away in the unknown direction; the second one – there were no conditions for the formation of the photons in the process being considered, and mass, which failed to be formed as a particle, "was dissolved" in the ether. Which variant is closer to the truth [6]? There is no exact answer, but it is known that the Japanese scientists registered only neutron radiation with intensity of 50,000 neutrons per second, and they failed to register roentgen radiation [4].

If in this process the roentgen photons were created, they would not exceed heat efficacy of the plasma electrolytic process, because they would not be the thermal photons. The thermal photons are radiated and absorbed when the electrons make the energy transitions to the energy levels, which are the most remote from the atomic nuclei, where the infrared photons and neighbouring ones from the optical range of the spectrum with energies of ≈(0.001-3.3) eV are generated (Table 5) [6].

Table 5
Electromagnetic spectrum bands

Bands	Wave-length, m	Energy, eV
1. Low- frequency band	$\lambda \approx (10^{7}...10^{4})$	$E \approx 10^{-15}...10^{-11}$
2. Broadcast band	$\lambda \approx (10^{4}...10^{-1})$	$E \approx 10^{-11}...10^{-6}$
3. Microwave band	$\lambda \approx (10^{-1}...10^{-4})$	$E \approx 10^{-6}...10^{-3}$
4. Relic band (maximum)	$\lambda \approx 1 \times 10^{-3}$	$E \approx 1.2 \times 10^{-3}$
5. Infrared band	$\lambda \approx (10^{-4}...7.7 \times 10^{-7})$	$E \approx 10^{-3}...1.6 \times 10^{-2}$
6. Light band	$\lambda \approx (7.7 \times 10^{-7}...3.8 \times 10^{-7})$	$E \approx 1.6 \times 10^{-2}...3.27$
7. Ultraviolet band	$\lambda \approx (3.8 \times 10^{-7}...10^{-9})$	$E \approx 3.27...1 \times 10^{2}$
8. Roentgen band	$\lambda \approx (10^{-9}...10^{-12})$	$E \approx 10^{2}...10^{5}$
9. Gamma band	$\lambda \approx (10^{-12}...10^{-18})$	$E \approx 10^{5}...10^{9}$

Thus, the neutron fusion processes in plasma electrolysis of water will not generate additional thermal energy. But the appearance of the neutrons in plasma will promote the formation of the nuclei of deuterium and, possibly, of tritium. As the balance of masses remains almost unchanged, we have no reason to expect that **additional energy will take place** when deuterium and tritium are formed. But it is sure to appear during **fusion of the atoms of deuterium and tritium, i.e. the hydrogen atoms [6].**

In order to become a proton, the neutron should radiate something, which mass is $\Delta m_{np}=23.058 \times 10^{-31}$ *kg*. Let us convert this mass into energy [6].

$$E_{ph}= \Delta m_{np} \times C^2 = \frac{23.058 \times 10^{-31} \times (2.998 \times 10^{8})^2}{1.602 \times 10^{-19}} = 1.294 \times 10^{6}\, eV \qquad (3)$$

This energy corresponds to the gamma range photons, i.e. not to the thermal photons, and this process does not give additional energy. Thus, if the process of the formation of the helium atoms takes place during plasma electrolysis of water, it should be accompanied by gamma radiation. If there is no such radiation, but the helium atoms are formed, the neutrino takes away the above-mentioned portion of mass Δm_{np} or this mass, which has no opportunity to be formed as the photon, "is dissolved" in the environment, i.e. it is transferred into the state of the ether [6]. As the roentgen photons and the gamma photons are not the thermal ones, this process gives no excessive thermal energy [6].

Another variant is possible. When the atoms of alkali metal bombard the cathode atoms, they are destroyed completely and destroy the atoms of the cathode materials. Under the notion "completely" we'll understand such state when both the atom and the nucleus are destroyed. In this case, the protons of the destroyed nuclei begin to form the hydrogen atoms. The process of fusion of the atoms and the molecules of hydrogen generate additional thermal energy [6]. But one should bear in mind that if plasma disintegrates water molecule into hydrogen and oxygen and if these gases contact plasma, hydrogen is combined with oxygen, and water is formed. Noise generated by plasma is hydrogen microexplosions. Taking into consideration the above-mentioned fact the larger the volume of hydrogen burnt in plasma, the smaller its volume in the gas-vapour mixture. It means that such reactor operation modes are required when quantity of burnt hydrogen is minimal one. Our theory allows us to have such results.

As iron is the cathode material, the nuclei of its atoms are the targets of the atomic nuclei of potassium, alkaline metal. During the transmutation of the iron nuclei (Fig. 2 b), the atomic nuclei of chromium (Fig. 2 a) and the atomic nuclei of copper (Fig. 2 c) are formed [6].



a) Cr (24,28) b) Fe (26,28) c) Cu (29,34)

Fig. 2.
Diagrams of the atomic nuclei of: a) chromium, b) iron, c) copper

When the atomic nucleus of iron (Fig. 2 b) pass into the atomic nucleus of chromium (Fig. 2 a), two protons and two neutrons are released; two atoms of deuterium or one atom of helium can be formed from them. If the neutrons pass into the protons, four atoms of hydrogen are formed.

It is easy to see (Fig. 2) that the atomic nucleus of iron (Fig. 2 b) should lose two upper protons and two neutrons in order to pass into the atomic nucleus of chromium (Fig. 2 a).

Three additional protons and six neutrons (total 9 nucleons) are required for the formation of the atomic nucleus of copper (Fig. 2 c) from the atomic nucleus of iron. As on the cathode surface (Table 3) the number of chromium atoms, which probably are formed from the atomic nuclei of iron, four times more than the number of atoms of copper, then the solution is sure to have superfluous protons and neutrons of the destroyed atomic nuclei of iron, and we can determined their approximate relative quantity.

Let us suppose that four nuclei of the iron atoms pass into the nuclei of the chromium atom. The total quantity of free protons and neutrons (nucleons) is equal to 16. As one atom of copper falls on each four atoms of chromium, 9 nucleons are spent for the formation of one nucleus of the copper atom, and 7 nucleons remain free.



a) K (19,20) b) O (8,8) c) Si (14,14)

Fig. 3.
Diagrams of the atomic nuclei of:
a) potassium, b) oxygen, c) silicon

Let us see what is formed when the nucleus of the potassium atom is destroyed. Potassium is situated in the first group of the fourth period of the periodic law. Its nucleus contains 19 protons and 20 neutrons (Fig. 3 a) [6].

In Fig. 3 a, we can see a weak link of the nucleus of the potassium atom [6]. It is situated in the middle of its axis neutrons. When the transmutation of the nuclei of the potassium atoms takes place, the nuclei of the oxygen atoms can be formed (Fig. 3 b) as well as its isotopes and the nuclei of the silicon atoms (Fig. 3 c).

The analysis of the structure of the nuclei of the potassium atom (Fig. 3 a) shows that it is the most probable source of the nucleus of the silicon atom (Fig. 3 c), which atoms appear on the cathode (Table 3).

It is easy to count that during the destruction of one nucleus of the potassium atom and the creation of one nucleus of the silicon atom 5 free protons and 6 free neutrons, i.e. 11 nucleons, are formed.

Thus, the transmutation of the nuclei of the iron atoms and the potassium atoms results in the formation of free protons and neutrons. As the protons cannot exist in free state, the hydrogen atoms are created from them. If the protons are connected with the neutrons after the destruction of the nuclei of the iron atoms and the potassium atoms, the formation of deuterium, tritium and helium is possible.

Let us pay attention to the main fact – absence of the sodium atoms in the cathode material. It is natural that the potassium atoms have appeared on the cathode, which operated in KOH solution (Table 3). Why are no sodium atoms on the cathode, which operated in NaOH solution? The answer is as follows: the nuclei of the sodium (Fig. 4,a) atoms are completely destroyed during the plasma electrolytic process. The presence of potassium on the surface of the cathode, which operated in NaOH solution (Table 4), can be explained by insufficient ablution of the reactor after the operation with KOH solution.

As free protons and neutrons appear during the destruction of the nucleus of the sodium atom (Fig. 4,a), some nuclei of this element begin to form the atomic nuclei of aluminium (Fig. 4, b), chlorine (Fig. 4, c) and calcium (Fig. 5).

But not all free protons and neutrons are spent for the construction of the atomic nuclei of aluminium, chlorine and calcium. A part of them is spent for the hydrogen atom formation.

If we knew the total quantity of transmutating atomic nuclei of iron, potassium and sodium as well as the exact composition of the gases generated during the plasma electrolytic process, it would be possible to determine the atomic nuclei being formed from additional nucleons. Now we can only suppose that the majority of new nuclei are the protons, i.e. the nuclei of the hydrogen atoms. The increased volume of the gases generated during the plasma electrolytic process is explained by it [6].



a) Na (11,12) b) Al (13,14) c) Cl (17,18)

Fig. 4.
Diagrams of the atomic nuclei of:
a) sodium, b) aluminium, c) chlorine



Ca (20,20)

Fig. 5.
Diagram of the nucleus of the calcium atom

The analysis of these Tables shows that transmutation of the nuclei of iron, of which the cathodes are made, results in the formation of chromium and copper in both cases. Apparently, aluminium, chlorine and calcium are formed from the destroyed sodium nuclei. In any case, free protons and neutrons are formed.

But not all free protons and neutrons are spent for the formation of the atomic nuclei of copper, aluminium, chlorine and calcium. A part of them is spent for the formation of the hydrogen atoms. In any case, the atoms and the molecules of hydrogen are formed. The analysis has shown that plasma electrolytic process extracts not more than 0.005 kg of alkaline metal from one litre of the solution. It appears from this that if all neutrons of the atomic nuclei of the molecules of water and alkali metals are transferred into the protons and the atoms and the molecules of hydrogen are formed, the formed volume of gas will be considerably less than the one registered during the experiment (Table 1). A question arises: where do additional gases come from? In order to get the answer on this question we made the next experiment.

THE SECOND EXPERIMENTAL PART

First of all we take into account, that high temperature of plasma forms the conditions when a set of various processes takes place at the cathode. First of all, water is boiled and evaporated. At the same time, one part of water molecules is disintegrated with a release of the atomic hydrogen; another part of the molecules forms the orthohydrogen molecules. A part of water molecules is disintegrated completely and is released at the cathode together with hydrogen and oxygen. A part of hydrogen is combined with oxygen again generating microexplosions (noise) and forming water.

During plasma electrolysis of water, water vapor, hydrogen and oxygen are released simultaneously. If vapor is condensed, gas mixture is released. In order to measure gas flow rate the electronic anemometer have been used. Diameter of the electronic anemometer was equal to internal diameter of the gas make tube (23, Fig. 1). Its readings were registered and processed by the computer. The experiment was performed dozen times, and each time its readings were reproduced with small deviations [11]. But we had no hydrogen analyzer, that's why the results being obtained cannot be considered as final ones. We admonished it in all editions of the book Water is a New Source of Energy with such a phrase: "We abstain from lending an official status to these results with the hope to get necessary financing and to repeat them with a complete set of the necessary devices" [12, page 176].

In the middle of the year of 2002 we received small financing, which allowed us to make a new reactor and to buy some measuring instruments, in particular the scales with the measurement limit up to 600 g and accuracy of 0.02 g. Careful preparation allowed us to increase duration of continuous operation of the reactor (to 10 and more hours) and to register solution consumption for gas production.

The main difficulty of operation with the hydrogen is in the fact that its mixture with air (4-74)% or oxygen (4-94)% is combustible, and the fact was emphasized more than once during the experiments that made the researches be very careful. The second difficulty during hydrogen quantity measurements generated by the plasma electrolytic reactor is in the fact that its molecule has the smallest dimensions, that's why it penetrates easily to the places where the molecules of other substances do not penetrate. Molecular hydrogen diffuses easily even into metals. For example, one volume of palladium absorbs up to 800 volumes of hydrogen.

Gas flow speed was measured with the help of various anemometers, its readings being registered with the help of the computer. Numerous measurements and numerous analysis of gas flow speed measurement accuracy with the help of the anemometers showed that error of a conventional anemometer can be 100%.



Fig. 6.
Diagram of measurement of flow rate of the gas and its volume:
1 - tap for gas flow movement direction switching,
2 – anemometer, 3 – graduated tank, 4 – water tank

It is known that it is possible to produce 1220 litres of hydrogen and 622 litres of oxygen from one litre of water. Quantity of the gases generated by the plasma electrolytic process is much greater than it is possible to get from consumed water (Table 1). It was a strong reason for a search of the measurement error. For this purpose, the diagram of measurement of flow rate of the gases and their quantity was used (Fig. 6).

The results of the measurements were as follows. The anemometer showed that 200 litres of gas mixture penetrated through it during 10 minutes. Nearly one litre of gases was in the graduated tank during this period.

Thus, the measurement of gas flow with the help of the anemometers distorted the result 200 fold. It should be mentioned that the reactor operated in the production mode of hydrogen and oxygen in the cathode zone. As a result, their mixture burst. The pulses of these explosions increased the readings of the anemometer.

It has become necessary to return to the reactor operation modes when no oxygen is released in the cathode zone. Our theory allows us to do this easy.

PROTOCOL
of tests of the first model of low-current Electrolyzers

It is known that it is possible to produce 1.22 l of H_2+ 0.622 O_2= 1.843 (H_2+O_2) from 1 ml of H_2O

Table 6
Experimental results

Indices	1	2	3	Average
1-duration of experiment, hour	1	1	1	1
2-voltage, V	70	70	70	70
3-current, A	0.038	0.080	0.098	0.072
4 – power, W	2.7	5.60	6.44	4.91
4-volume of consumed solution, ml	1.67	3.98	4.32	3.32
5-density of the solution, kg/l	1.04	1.04	1.04	1.04
6-volume of consumed water, ml	1.60	3.83	4.15	3.19
7-volume of the gas mixture being produced, l	2.95	7.06	7.85	5.95
6-volume of hydrogen being produced, l	1.95	4.67	5.07	3.80
7-energy consumption per 1 l of hydrogen, W·h/l	1.38	1.20	1.27	1.28
8-energy consumption per 1m^3 of hydrogen, kWh/m^3	1.38	1.20	1.27	1.28
9-existing energy consumption for production of 1 m^3 of hydrogen from water, kWh/m^3	4.00	4.00	4.00	4.00

CONCLUSION

Transmutation of the atomic nuclei of alkaline metals and the atomic nuclei of the cathode material during plasma electrolysis of water existed. Plasma electrolytic process opens new prospects in study of matter on the nuclear, atomic and molecular levels. The low-current electrolysis allows us to get the inexpensive hydrogen from water.

REFERENCES

1. M. Fleischmann, S. Pons and M. Hawkins. Electrochemically Induced Nuclear Fusion of Deuterium. J. Electroanal. Chem. 261, 301 (1989),
2. ICCF-7 ACCEPTED ABSTRACTS. Infinite Energy. V. 4, Issue 20, p. 59…69.
3. Harold L. Fox. Cold nuclear fusion: essence, problems, influence on the world. View from USA. Production group SVITAX. M.: 1993, 180 pages.
4. T. Ohmori, T. Mizuno. Strong Excess Energy Evolution, New Element Production, and Electromagnetic Wave and/or Neutron Emission in Light Water Electrolysis with a Tungsten Cathode. Infinite Energy. Issue 20, 1998. Pages 14-17.
5. T. Mizuno. Nuclear Transmutation: The Reality of Cold Fusion. Infinite Energy Press. 1998. 151 pages.
6. Ph. Kanarev. Foundations of Physchemistry of Microworld. Krasnodar, 2002. 330 pages.
7. Kenneth R. Shoulders, “Method of and Apparatus for Production and Manipulations of High Density Charge”, U.S. Patent 5,054,046, issued Oct 1, 1991.
8. Ken Shoulders & Steve Shoulders, “Observations on the Role of Charge Clusters in Nuclear Cluster Reactions”, J.of New Energy, vol. 1, no 3, pp 111-121, Fall 1996, 7 refs, 22 figs.
9. Hal Fox, Robert W. Bass, & Shang-Xian Jin, “Plasma-Injected Transmutation”, J. of New Energy, vol. 1, no 3, Fall 1996, pp 222-230, 23 refs, 4 figs.
10. Shang-Xian Jin & Hal Fox, “High Density Charge Cluster Collective Ion Accelerator”, J. of New Energy, vol. 4, no 2, Fall 1999, pp 96-104, 47 refs, 4 figs., 3 tables.
11. Ph.M. Kanarev. Water is the Main Power Carrier of Future Power Engineering. Journal of New Energy. An International Journal of New Energy Systems. Vol. 6, No.2. Pag. 101-121.
12. Ph.M. Kanarev. Water is New Source of Energy. The Third Edition. Krasnodar 2002. 194p. (In English).

LENR

(Low Energy Nuclear Reactions)

http://www.lenr-canr.org

Editorial: There is a collection of some papers on LENR (Low Energy Nuclear Reactions), also known as Cold Fusion. CANR, Chemically Assisted Nuclear Reactions, is another term for this phenomenon. These original scientific papers are reprinted with permission from the authors and publishers.

Website http://www.lenr-canr.org features a growing library of scientific papers about LENR and an extensive bibliography of journal papers, news articles and books about LENR.

COLD FUSION: What is it and what does it mean to science and society?

Edmund Storms

Cold fusion is important because it promises to be a new source of pollution-free, inexhaustible energy. In addition, it is important because it reveals the existence of a new way nuclei can interact that conventional scientific theory predicts is impossible. What then is this phenomenon that suffers such promise and rejection?

Energy can be obtained from the nucleus in two different ways. On the one hand, a large nucleus can be broken into smaller pieces, such as is experienced by uranium in a conventional nuclear reactor and by the material in an atom bomb. This is called fission. On the other hand, two very small nuclei can be joined together, such as occurs during fusion of deuterium and tritium in a Hot Fusion reactor and in a hydrogen bomb. This process, called fusion, also takes place in stars to produce much of the light we see.

The fission reaction is caused to happen by adding neutrons to the nucleus of uranium or plutonium to make it unstable. The unstable nucleus splits into two nearly equal pieces, thereby releasing more neutrons, which continue the process. As every one now knows, this process produces considerable waste that is highly radioactive. The uranium used as fuel also occurs in limited amounts in the earth’s crust. As a result, this source of energy is not ideal, although widely used at the present time.

The normal hot fusion reaction requires two deuterium or tritium nuclei to be smashed together with great energy. This is accomplished by raising their temperature. However, this temperature is so high that the reactants cannot be held in a solid container, but must be retained by a magnetic field. This process has proven to be very difficult to accomplish for a time sufficient to generate useable energy. In spite of this difficulty, attempts have been under way for the last 40 years and with the expenditure of many billions of dollars. Success continues to be elusive while the effort continues.

Cold fusion, on the other hand, attempts to cause the same process, but by using solid materials as the container held at normal temperatures. The container consists of various metals, including palladium, with which the deuterium is reacted to form a chemical compound. While in this environment, the barrier between the deuterium nuclei is reduced so that two nuclei can fuse without having to be forced together. Because the process causing this to happen is not well understood, the possibility is rejected by many conventional scientists. Difficulty in producing the process on command has intensified the rejection.While this difficulty is real, it has not, as many skeptics have claimed, prevented the process from being reproduced hundreds of times in laboratories all over the world for the past 13 years. As you will see by reading the reviews and papers in our Library (see http://www.lenr-canr.org/LibFrame1.html), the process continues to be reproduced with increasing ease using a variety of methods and materials.

What is the nature of this process and why has it been so hard to understand? To answer this question, a person needs to understand the nature of the barrier that exists between all nuclei. Because all nuclei have a positive charge in proportion to their atomic number, all nuclei repeal each other. It is only the surrounding electrons that hold normal matter together, with the nuclei being at considerable distance from each other, at least on the scale of an atom. When attempts are made to push the nuclei closer, the required energy increases as the nuclei approach one another. However, when deuterium dissolves in a metal, it experiences several unique conditions. The surrounding metal atoms produce a regular array that is able to support waves of various kinds. These waves can be based on vibration of the atoms (phonons), vibration of the electrons, standing waves of electromagnetic energy, or a wave resulting from conversion of the deuterium nuclei to a wave. In addition, the high density of electrons can neutralize some of the positive charge on the deuterium nuclei allowing a process called tunneling, i.e.. allowing passage through the barrier rather than over it. The mechanism of this neutralization process is proposed to involve a novel coherent wave structure that can occur between electrons under certain conditions. All of these wave processes have been observed in the past under various conventional conditions, but applying them to the cold fusion phenomenon has been a subject of debate and general rejection.

While the debate based on wave action has been underway, people have proposed other mechanisms. These include the presence of neutrons within the lattice. Normally, neutrons are unstable outside of the nucleus, decomposing into a proton, an electron, and a neutrino. Presumably, this reaction can be reversed so that neutrons might be created in a lattice containing many free electrons and protons. Having no charge, the neutron could then interact with various atoms in the lattice to produce energy. These neutrons might also be hidden in the lattice by being attached to other nuclei in a stabilized form, to be released when conditions were right. Several particles normally not detected in nature also have been proposed to trigger fusion and other nuclear reactions.

While search for a suitable mechanism has been underway, an understanding of the environment that triggers the mechanism has been sought, the so-called nuclear-active-environment. Initially, this environment was thought to exist in the bulk of the palladium cathode used in the Pons-Fleischmann method to produce cold fusion. It is now agreed that the nuclear reactions only occur in the surface region. Recent arguments suggest that this surface layer does not even require palladium for it to be nuclear-active. Nuclear reactions have now been produced in a variety of materials using many methods. The only common feature found in all of these methods is the presence of nano-sized particles of material on the active surface. If this observation is correct, four conditions seem required to produce the nuclear reactions. First, the particle must have a critical small size; second, it must contain a critical concentration of deuterium or hydrogen; third, it must be constructed of certain atoms; and fourth, it must be exposed to a source of energy. This energy can take the form of a sufficiently high temperature, a significant high flux of hydrogen through the particle, application of energetic electrons or charged particles, or application of laser light of the proper frequency. Until, the importance of these factors is understood, the effect will continue to be difficult to replicate.

Technical Introduction to LENR-CANR

Edmund Storms

At low energies, the Coulomb barrier prevents nuclei from coming together and fusing to form a single nucleus. To initiate a nuclear reaction, several methods are used. Nuclear reactions are normally initiated by pushing two atoms together with enough force to overcome the Coulomb barrier by brute force, or by using neutrons which penetrate the nuclei without seeing a barrier. (Neutrons have no electrical charge, so the Coulomb barrier does not stop them.) These forces are normally provided by high-temperature plasma or by accelerating ions to high energies. In contrast, LENR describes the mechanism and conditions that cause a variety of nuclear reactions to take place with relatively low activation energy. These unique conditions reduce the need for excessive energy. The normal method forces the nuclei together, while the new method encourages them to come together. The challenge has been to understand the unique characteristics of the necessary solid structure such that this structure could be generated at will.

Because the proposed method is unique, at odds with current nuclear theory, and is still difficult to reproduce, support for studies in many countries, but not all, has been very limited. Nevertheless, considerable information has accumulated over the last 13 years since Profs. Stanley Pons and Martin Fleischmann showed the world the possibilities inherent in this phenomenon. Much understanding is buried in conference proceedings and reports that are not available to a serious student. This information will, as time permits, be made available on this site. Students of the subject are also encouraged to use this site to interact with other people in the field and provide objective critiques of the work published here.

PHENOMENA DISCUSSED IN SOME OF THE PAPERS

At least 10 ways have been demonstrated to produce anomalous heat and/or anomalous elemental synthesis. A few of these methods will be described here. For course, not all of the claims are worthy of belief nor are they accepted by many people. Nevertheless, the claims will be described without qualifications in order to provide the reader with the latest understanding.

conditions. The surrounding metal atoms produce a regular array that is able to support waves of various kinds. These waves can be based on vibration of the atoms (phonons), vibration of the electrons, standing waves of electromagnetic energy, or a wave resulting from conversion of the deuterium nuclei to a wave. In addition, the high density of electrons can neutralize some of the positive charge on the deuterium nuclei allowing a process called tunneling, i.e.. allowing passage through the barrier rather than over it. The mechanism of this neutralization process is proposed to involve a novel coherent wave structure that can occur between electrons under certain conditions. All of these wave processes have been observed in the past under various conventional conditions, but applying them to the cold fusion phenomenon has been a subject of debate and general rejection.

While the debate based on wave action has been underway, people have proposed other mechanisms. These include the presence of neutrons within the lattice. Normally, neutrons are unstable outside of the nucleus, decomposing into a proton, an electron, and a neutrino. Presumably, this reaction can be reversed so that neutrons might be created in a lattice containing many free electrons and protons. Having no charge, the neutron could then interact with various atoms in the lattice to produce energy. These neutrons might also be hidden in the lattice by being attached to other nuclei in a stabilized form, to be released when conditions were right. Several particles normally not detected in nature also have been proposed to trigger fusion and other nuclear reactions.

While search for a suitable mechanism has been underway, an understanding of the environment that triggers the mechanism has been sought, the so-called nuclear-active-environment. Initially, this environment was thought to exist in the bulk of the palladium cathode used in the Pons-Fleischmann method to produce cold fusion. It is now agreed that the nuclear reactions only occur in the surface region. Recent arguments suggest that this surface layer does not even require palladium for it to be nuclear-active. Nuclear reactions have now been produced in a variety of materials using many methods. The only common feature found in all of these methods is the presence of nano-sized particles of material on the active surface. If this observation is correct, four conditions seem required to produce the nuclear reactions. First, the particle must have a critical small size; second, it must contain a critical concentration of deuterium or hydrogen; third, it must be constructed of certain atoms; and fourth, it must be exposed to a source of energy. This energy can take the form of a sufficiently high temperature, a significant high flux of hydrogen through the particle, application of energetic electrons or charged particles, or application of laser light of the proper frequency. Until, the importance of these factors is understood, the effect will continue to be difficult to replicate.

Technical Introduction to LENR-CANR

Edmund Storms

At low energies, the Coulomb barrier prevents nuclei from coming together and fusing to form a single nucleus. To initiate a nuclear reaction, several methods are used. Nuclear reactions are normally initiated by pushing two atoms together with enough force to overcome the Coulomb barrier by brute force, or by using neutrons which penetrate the nuclei without seeing a barrier. (Neutrons have no electrical charge, so the Coulomb barrier does not stop them.) These forces are normally provided by high-temperature plasma or by accelerating ions to high energies. In contrast, LENR describes the mechanism and conditions that cause a variety of nuclear reactions to take place with relatively low activation energy. These unique conditions reduce the need for excessive energy. The normal method forces the nuclei together, while the new method encourages them to come together. The challenge has been to understand the unique characteristics of the necessary solid structure such that this structure could be generated at will.

Because the proposed method is unique, at odds with current nuclear theory, and is still difficult to reproduce, support for studies in many countries, but not all, has been very limited. Nevertheless, considerable information has accumulated over the last 13 years since Profs. Stanley Pons and Martin Fleischmann showed the world the possibilities inherent in this phenomenon. Much understanding is buried in conference proceedings and reports that are not available to a serious student. This information will, as time permits, be made available on this site. Students of the subject are also encouraged to use this site to interact with other people in the field and provide objective critiques of the work published here.

PHENOMENA DISCUSSED IN SOME OF THE PAPERS

At least 10 ways have been demonstrated to produce anomalous heat and/or anomalous elemental synthesis. A few of these methods will be described here. For course, not all of the claims are worthy of belief nor are they accepted by many people. Nevertheless, the claims will be described without qualifications in order to provide the reader with the latest understanding.

The most studied method involves the use of an electrolytic cell containing a LiOD electrolyte and a palladium cathode. Current passing through such a cell generates D+ ions at the cathode, with a very high effective pressure. These ions enter the palladium and, if all conditions are correct, join in a fusion reaction that produces He-4. Initially palladium wire and plate were used, but these were found to form microcracks, which allowed the required high concentration of deuterium to escape. Later work shows that the actual nuclear reaction occurs on the surface within a very thin layer of deposited impurities. Therefore, control of this impurity layer is very important, but rather difficult. The use of palladium is also not important because gold and platinum appear to be better metals on which to deposit the impurity layer. This method is found, on rare occasions, to generate tritium within the electrolyte and transmutation products on the cathode surface. Different nuclear reactions are seen when light water (H_2O) is used instead of D_2O, although the amount of anomalous energy is less when H_2O is used. These observations have been duplicated hundreds of times in dozens of laboratories.

Application of deuterium gas to finely divided palladium, and perhaps other metals, has been found to generate anomalous energy along with helium-4. Both palladium-black as well as palladium deposited as nanocrystals on carbon have shown similar anomalous behavior. In both cases the material must be suitably purified. Palladium deposited on carbon can and must be heated to above 200/260°C for the effect to be seen. When deuterium is caused to diffuse through a palladium membrane on which is deposited a thin layer of various compounds, isotopes that were not previously present are generated with isotopic ratios unlike those occurring naturally.

A plasma discharge under H_2O or D_2O between various materials generates many elements that were not previously present. When the electrodes are carbon and the plasma is formed in H_2O, the main anomalous element is iron. This experiment is relatively easy to duplicate.

Several complex oxides, including several superconductors, can dissolve D_2 when heated. When a potential is applied across a sheet of such material, the D+ ions are caused to move and anomalous heat is generated.

If deuterium ions, having a modest energy, are caused to bombard various metals, tritium as well as other elements not previously present are generated. These ions can be generated in a pulsed plasma or as a beam.

When water, either light or heavy, is subjected to intense acoustic waves, collapse of the generated bubbles on the surrounding solid walls can generate nuclear reactions. This process is different from the fusion reaction claimed to occur within a bubble just before it disappears within the liquid because neutrons are not produced in the former case, but are produced in the latter case. This method has been applied to various metals in heavy water using an acoustic transducer and in light water using a rotating vane which generates similar acoustic waves...

HOW TO EXPLAIN THE CLAIMS

A major problem in deciding which model might be correct is the absence of any direct information about the nature of the nuclear-active-environment. At this time, two important features seem to be important, the size of the nanodomain in which the reactions occur and the presence of a deuterium flux through this domain. The domain can apparently be made of any material in which hydrogen or deuterium can dissolve. Until the nature of the nuclear-active-state (NAS) is known, no theory will properly explain the effect and replication of the claims will remain difficult.

When fusion is initiated using conventional methods, significant tritium and neutrons are produced. In addition, when other elements are generated, they tend to be radioactive. This is in direct contrast to the experience using low energy methods. These products are almost completely absent and, instead, helium-4 is produced. When radiation is detected, it has a very low energy. This contrasting behavior, as well as the amount of anomalous energy, has made the claims hard to explain using conventional models. This difficulty has been amplified by a failure of many skeptics to recognize the contrasting effect of the environment, a plasma being used in the older studies and a solid lattice of periodic atoms being present as the new environment.

Over 500 models and their variations have been proposed, some of which are very novel and some are variations on conventional ideas. Most models attempt to explain the nuclear reaction once the required environment has been created, without addressing what that unique environment might be like. These models involve conversion of a proton (deuteron) to a neutron (dineutron), creation of an electron structure that is able to neutralize the barrier, conversion of deuterium to a wave which interacts without charge, and the presence of otherwise overlooked neutrons and/or novel particles. Many of the models will have to be abandoned or seriously modified once the nature of the nuclear active environment is understood.

It Started in 1989 . . .

Peter Hagelstein

Many of us recall the controversy surrounding the announcement of claims of observations of fusion reactions in a test tube that were made in 1989. At the time, these claims were greeted with considerable skepticism on the part of the physics community and the scientific community in general.

The principal claim of Pons and Fleischmann

The principal claim of Pons and Fleischmann in 1989 was that power was produced in palladium cathodes that were loaded electrochemically in a heavy water electrolyte. The evidence in support of this was a measured increase in the temperature in the electrochemical cell. There was no obvious evidence for nuclear reaction products commensurate with the claimed heat production. Fleischmann speculated that perhaps two deuterons were somehow fusing to He-4 through some kind of new mechanism.

Rejection by the physics community

This claim was not accepted by the physics community on theoretical grounds for several reasons:

First, there was no mechanism known by which two deuterons might approach one another close enough to fuse, since the Coulomb barrier prevents them from approaching at room temperature.

Second, if they did approach close enough to fuse, one would expect the conventional dd-fusion reaction products to be observed, since these happen very fast. Essentially, once two deuterons get close enough to touch, reactions occur with near unity probability, and the reaction products (p+t and n+He-3) leave immediately at high relative velocity consistent with the reaction energy released. To account for Fleischmann's claim, the proposed new reaction would seemingly somehow have to make He-4 quietly and cleanly, without any of the conventional reaction products showing up, and would somehow have to arrange for this to happen a billion times faster than the conventional reaction pathway. Most physicists bet against the existence of such a magical new effect.

Third, the normal pathway by which two deuterons fuse to make He-4 normally occurs with the emission of a gamma ray near 24 MeV. There was no evidence for the presence of any such high energy gamma emission from the sample, hence no reason to believe that any helium had been made.

Finally, if one rejects the possibility that any new mechanisms might be operative, then the claim that power was being produced by fusion must be supported by the detection of a commensurate amount of fusion reaction products. Pons and Fleischmann found no significant reaction products, which, given the rejection of new mechanisms, implied an absence of fusion reactions.

An alternate explanation is proposed

The physicists decided in 1989 that the most likely reason that Pons and Fleischmann observed a temperature increase was that they had made an error of some sort in their measurements. When many groups tried to observe the effect and failed, this led most of the physics community to conclude that there was nothing to it whatsoever other than some bad experiments.

The claim of Jones

A second very different claim was made at the same time in 1989 by Steve Jones. This work also involved electrochemistry in heavy water and the observation of reaction products corresponding to the conventional dd-fusion reactions. The initial publication showed a spectrum of neutron emission that Jones had detected from a titanium deuteride cathode loaded electrochemically. The response of the physics community was skeptical, as the signal to noise ratio was not particularly impressive. Given the polarization of the physics community in opposition to the claims of Pons and Fleischmann (which were announced essentially simultaneously), the physicists were not of a mood to accept much of any claims that fusion could happen in an electrochemical experiment at all. Jones went to great lengths to assure fellow scientists that his effect was completely unrelated to the claims of Pons and Fleischmann, and was much more reasonable.

Also rejected

Physicists had reason to be skeptical. Theoretical considerations indicated that the screening effects that Jones was relying on were not expected to be as strong as needed to account for the fusion rates claimed. As this experiment could not seem to be replicated by others at the time, it was easy for the physics community to reject this claim as well.

Cold fusion, weighed and rejected with prejudice

Cold fusion, as the two different claims were termed, was dismissed with prejudice in 1989. The initial claims were made near the end of March in Utah, and the public refutation of the claims was made at the beginning of May. It only took about 40 days for the physics community to consider the new claims, test them experimentally, and then announce loudly to the world that they had been carefully weighed and rejected.

Following this rejection, physicists have treated cold fusion rather badly. For example, Professor John Huizenga of Rochester University was selected to be co-chair of the DOE ERAB committee that met to review cold fusion and issue a report. Shortly afterward, he wrote a book entitled Cold Fusion, The Scientific Fiasco of the Century, in which he discusses the claims, the experiments, and the extreme skepticism with which the new claims were greeted. Robert Park discusses the subject in his book entitled Voodoo Science. You can find many places where physicists and other scientists happily place the cold fusion claims together with claims of psychic phenomena.

A Science Tutorial

Talbot Chubb

First it is important to recognize that there are four distinct types of energy production:
1) chemical energy, that powers our cars and most of our civilization;
2) nuclear fission energy, as used to generate about 15% or our electricity;
3) hot fusion nuclear energy, which powers the sun and most stars;
4) cold fusion nuclear energy, which appears as unexplained heat in a few experimenter's laboratory studies and which most scientists believe is impossible.

The three types of nuclear energy produce 10 million times as much heat per pound of fuel than occurs with chemical energy. How do these types of energy differ? To understand this question you need to know some chemistry and physics.

Lesson 1

Nature has provided us with two types of stable charged particles, the proton and the electron. The proton is heavy, normally tiny, and has a positive charge. The electron is light, normally large and fuzzy, and has a negative charge. The positive charge and the negative charge attract each other, just like the north pole of a magnet attracts the south pole of a magnet. When you bring two magnets together with the north pole of one facing the south pole of the other, they pull together, bang! When they bang into each other they release a little bit of energy in the form of heat, but it is too small an amount to easily measure. To pull the magnets apart you have to do work, which is another way of saying you have to use up energy. It's almost like pulling a rock back up a hill. Rolling the rock down a hill actually creates a little heat, and pulling the rock back up the hill takes energy. In the same way the positive charge of the proton pulls on the negative charge of the electron and they stick together releasing energy in the process. The result is a hydrogen atom, designated H. A hydrogen atom is nothing but a fuzzy electron hugging a compact proton. The proton is the nucleus of the hydrogen atom. If you knock the electron off the hydrogen atom you get a positive ion $H+$, which is nothing more than the original proton. An ion is the name applied to an atom or molecule that has lost or gained one or more electrons, hence is no longer electrically neutral.

Lesson 2

As you know, nature has provided us with more than one type of atom. We have oxygen atoms, nitrogen atoms, iron atoms, helium atoms, etc.. How do these atoms differ? The answer is that they all have different types of nuclei (plural of nucleus, from the Latin). And these different nuclei all have different numbers of protons inside them, which means they all have different plus charges. The nucleus of the helium atom has 2 protons inside it, hence has plus 2 charge, and requires 2 electrons to neutralize its charge. When 2 electrons stick to it, it becomes a helium atom. The oxygen nucleus has 8 protons and has charge 8. When 8 electrons stick to it, it becomes an oxygen atom. The nitrogen atom has 7 electrons, and the iron atoms something like 26. But all the atoms are built more or less the same way, with a compact positively charged nucleus embedded in a cloud of fuzzy electrons. The difference in size between the compact nucleus and the fuzzy electrons is enormous. The sun has a diameter only about 100 times that of the earth. The electron cloud on an atom has a diameter which is about 100,000 times that of the nucleus. Cube these numbers to get the difference in volumes.

Lesson 3

We now are in a position to understand what chemical energy is. The atoms, all electrically neutral, can actually join with each other and release more energy. This is another way of saying that they can join into more stable configurations. The electrons in an atom try to configure themselves so as to get as close as possible to their nucleus, but their fuzzy nature requires that they take up a certain volume of space. However, if they join together with the electrons of another atom they can usually find a tighter configuration that leaves them closer to their beloved beginning of May. It only took about 40 days for the physics community to consider the new claims, test them experimentally, and then announce loudly to the world that they had been carefully weighed and rejected.

Following this rejection, physicists have treated cold fusion rather badly. For example, Professor John Huizenga of Rochester University was selected to be co-chair of the DOE ERAB committee that met to review cold fusion and issue a report. Shortly afterward, he wrote a book entitled Cold Fusion, The Scientific Fiasco of the Century, in which he discusses the claims, the experiments, and the extreme skepticism with which the new claims were greeted. Robert Park discusses the subject in his book entitled Voodoo Science. You can find many places where physicists and other scientists happily place the cold fusion claims together with claims of psychic phenomena.

A Science Tutorial

Talbot Chubb

First it is important to recognize that there are four distinct types of energy production:
1) chemical energy, that powers our cars and most of our civilization;
2) nuclear fission energy, as used to generate about 15% or our electricity;
3) hot fusion nuclear energy, which powers the sun and most stars;
4) cold fusion nuclear energy, which appears as unexplained heat in a few experimenter's laboratory studies and which most scientists believe is impossible.

The three types of nuclear energy produce 10 million times as much heat per pound of fuel than occurs with chemical energy. How do these types of energy differ? To understand this question you need to know some chemistry and physics.

Lesson 1

Nature has provided us with two types of stable charged particles, the proton and the electron. The proton is heavy, normally tiny, and has a positive charge. The electron is light, normally large and fuzzy, and has a negative charge. The positive charge and the negative charge attract each other, just like the north pole of a magnet attracts the south pole of a magnet. When you bring two magnets together with the north pole of one facing the south pole of the other, they pull together, bang! When they bang into each other they release a little bit of energy in the form of heat, but it is too small an amount to easily measure. To pull the magnets apart you have to do work, which is another way of saying you have to use up energy. It's almost like pulling a rock back up a hill. Rolling the rock down a hill actually creates a little heat, and pulling the rock back up the hill takes energy. In the same way the positive charge of the proton pulls on the negative charge of the electron and they stick together releasing energy in the process. The result is a hydrogen atom, designated H. A hydrogen atom is nothing but a fuzzy electron hugging a compact proton. The proton is the nucleus of the hydrogen atom. If you knock the electron off the hydrogen atom you get a positive ion $H+$, which is nothing more than the original proton. An ion is the name applied to an atom or molecule that has lost or gained one or more electrons, hence is no longer electrically neutral.

Lesson 2

As you know, nature has provided us with more than one type of atom. We have oxygen atoms, nitrogen atoms, iron atoms, helium atoms, etc.. How do these atoms differ? The answer is that they all have different types of nuclei (plural of nucleus, from the Latin). And these different nuclei all have different numbers of protons inside them, which means they all have different plus charges. The nucleus of the helium atom has 2 protons inside it, hence has plus 2 charge, and requires 2 electrons to neutralize its charge. When 2 electrons stick to it, it becomes a helium atom. The oxygen nucleus has 8 protons and has charge 8. When 8 electrons stick to it, it becomes an oxygen atom. The nitrogen atom has 7 electrons, and the iron atoms something like 26. But all the atoms are built more or less the same way, with a compact positively charged nucleus embedded in a cloud of fuzzy electrons. The difference in size between the compact nucleus and the fuzzy electrons is enormous. The sun has a diameter only about 100 times that of the earth. The electron cloud on an atom has a diameter which is about 100,000 times that of the nucleus. Cube these numbers to get the difference in volumes.

Lesson 3

We now are in a position to understand what chemical energy is. The atoms, all electrically neutral, can actually join with each other and release more energy. This is another way of saying that they can join into more stable configurations. The electrons in an atom try to configure themselves so as to get as close as possible to their nucleus, but their fuzzy nature requires that they take up a certain volume of space. However, if they join together with the electrons of another atom they can usually find a tighter configuration that leaves them closer to their beloved nuclei. For example, 2 hydrogen atoms can join together into a more compact configuration if each hydrogen atom contributes its electron to a 2-electron cloud, which the separate protons share. In this manner they form a grouping of the 2 electrons in a single cloud, together with the 2 isolated protons spaced apart from each other but still within the electron cloud. The result is a heat-producing chemical reaction $H + H => H_2$. (The => means "goes to" or "becomes".) The H_2 configuration is the hydrogen molecule, and when you buy a tank of hydrogen gas, H_2 molecules is what you get. Furthermore, the 2 electrons of the H_2 molecule and the 8 electrons of the O atom can find a still more compact configuration by combining their electrons to create the water molecule H_2O, plus heat. The water molecule is really a single cloud of electrons in which are embedded the three point-like nuclei to form a minimum energy configuration. So when we burn oil or coal we reconfigure the electrons to produce more stable configurations of point-like nuclei embedded in electron clouds, liberating heat. So much for chemical energy.

Lesson 4

We have slid over one point in the above discussion. How does Nature make a nucleus containing two or more protons in the first place. After all, each of the protons has a positive charge, and the positive charges repel each other very strongly when they are separated by a tiny distance, equal to the distance across a nucleus. The repulsion of like charges is just like the repulsion between the north poles of two magnets when they are pushed together the wrong way. Something must overcome this repulsion, or else the only kind of atoms we would have would be those of hydrogen. Fortunately, this is not what we observe. The answer is that there is a second kind of force which acts on protons. This is the nuclear force. The nuclear force is very strong but requires particles to almost sit on each other to have any effect. Also, there is a second kind of heavy particle, which is just like a proton, except that it has no positive or negative charge. It is not pushed away by the proton's plus charge. This other kind of particle is called the neutron, since it is electrically neutral. A peculiar fact of life is that it exists in stable form only inside a nucleus. When not in the nucleus it changes into a proton, an electron and a very light anti-neutrino in about 10 minutes. But it lasts forever inside a nucleus. Anyway, the neutron and the proton very strongly attract each other once they get close enough together, and then they combine to form a highly stable pair called a deuteron, which we designate D+. The single deuteron, when it combines with a single electron, forms the heavy hydrogen atom called deuterium, designated D. A second nuclear reaction occurs when two deuterons make contact. When they can be forced together so as to make contact, the 2 deuterons fuse, making a doubly charged particle. The grouping of 2 protons and 2 neutrons is even tighter than the proton-neutron grouping in the deuteron. The new particle, when neutralized by 2 electrons, is the nucleus of the helium atom, designated He. Larger groupings of neutrons and protons exist in nature and serve as the nuclei of carbon, nitrogen, oxygen, and iron, etc. atoms. All of these groupings are made possible by the very strong nuclear force, which is felt between particles only when they are in contact or share the same nucleus-size volume of space.

Lesson 5

We can now understand normal nuclear energy, which is really nuclear fission energy. During the early history of the universe massive stars were formed. In the explosion of these massive stars, lots of different types of nuclei were formed and exploded back into space. Second and later generation stars and planets were formed from this mix, including the sun. In the explosion process probably every possible stable configuration of protons and neutrons was produced, plus some almost-stable groupings, such as the nucleus of the uranium atom. There are actually 3 different types of uranium atom nuclei, called uranium-234, uranium-235, and uranium-238. These "isotopes" differ in their number of neutrons, but they all have 92 protons. The nuclei of all uranium atoms can go to a lower energy configuration by ejecting a helium nucleus, but this process occurs so rarely that the Earth's uranium has already lasted over 4 billion years. But the uranium nuclei are unstable in another way. In general, groupings of protons and neutrons are happiest if they have about 60 protons-plus-neutrons. The uranium nuclei contain more than three times this number. So they would like to split in two, which would release a lot of heat. But nature doesn't provide a way for them to split apart. They have to first go to a higher energy configuration before splitting in two. However, one of the three forms of uranium nucleus found in nature called uranium-235 and designated ^{235}U, gains the needed energy if it captures a neutron. The energized nucleus that results from neutron capture then splits apart with the release of an enormous amount of energy, and incidentally with release of additional neutrons. The additional neutrons can then split more uranium-235 nuclei, keeping the reaction going. This is what happens in nuclear power plants, where the heat, which is the end product of the nuclear splitting process, is used to boil water, generate steam, and turn electrical generators. (One also gets lots of radioactive products, which are a nuisance to dispose of safely.)

Lesson 6

We are now also in a position to understand hot fusion nuclear energy. As mentioned in lesson 5, the groupings of protons plus neutrons is most stable when the numbers of neutrons and protons approximate those found in the nucleus of an iron atom. Just as uranium has too many neutrons plus protons to be comfortable, so the light elements like hydrogen, helium, carbon, nitrogen and oxygen have too few. If the nuclei can be made to make contact under proper conditions, they can combine to create more stable groupings, plus heat. This is the process of fusion. Nature has found a way of doing this in stars like the sun. All Nature has to do is heat compressed hydrogen hot enough and wait long enough and hot fusion will occur. If Nature were to start with deuterium, which already has a paired proton and neutron, the task would be relatively easy in a star. Temperature is a measure of how much speed an atom of a given type has as it bangs around inside a cloud of such atoms. The higher the temperature, the higher the speed and the closer the atoms get to each other momentarily during a collision. In a star the temperatures are high enough that all the electrons quickly get knocked off the atoms, so one is really dealing with a mixed cloud of electrons and nuclei. At very high temperature the nuclei occasionally get close enough during collisions for the pulling-together short range nuclear force to turn on. Then the nuclei can stick together and go to a lower energy grouping of protons plus neutrons, releasing heat. Hot fusion nuclear energy is an attempt to carry out this process in the lab, using deuterium and mass-3 hydrogen (whose nucleus is a compact grouping of 1 proton and 2 neutrons) as the gas. Hot fusion requires that the gas be contained at temperatures of hundreds of millions of degrees, which can be done with the help of magnetic fields, but only for 1 or 2 seconds. The hope is to contain the gas for longer times. During the period of high temperature containment nuclear reactions occur during collisions. The main form of energy release is ejection of high energy neutrons and protons. The proton energy quickly converts to heat. The neutron energy can also be converted to heat but makes the equipment highly radioactive. It then becomes difficult to repair the equipment, which could make hot fusion a poor candidate for commercial power production. In any case hot fusion power is a dream that is still probably at least 50 years away. But most scientists view hot fusion as the only way to achieve fusion power. Hot fusion produces less radioactivity than fission power, is environmentally benign, and has a virtually limitless fuel supply on earth (many millions of years at present energy usage rates).

Lesson 7

So now we come to cold fusion. Cold fusion may provide an easier and non-radioactive way of releasing nuclear fusion energy. Cold fusion relies on a different way of letting the protons and neutrons in one nucleus make contact with those in another nucleus, so that the nuclear force can bring them into a more stable configuration. The requirement for any nuclear reaction to occur is that the reacting nuclei occupy the same volume of space. This condition is called particle overlap. In hot fusion particle overlap is brought about briefly by banging the nuclei together so as to overcome momentarily the repulsion of the two positive charges which try to keep the particles apart. In cold fusion particle overlap conditions are achieved by making deuterium nuclei act as fuzzy objects like electrons in atoms, instead of like tiny points. When either light or heavy hydrogen is added to a heavy metal, each hydrogen "atom" occupies a position inside the metal where it is surrounded by heavy metal atoms. This form of hydrogen is called interstitial hydrogen. With interstitial hydrogen the electrons of the hydrogen atom become part of the pool of electrons of the metal. Each hydrogen nucleus oscillates back and forth through a negatively charged electron cloud provided by the electrons of the metal. They can be thought of as moving back and forth like the pendulum in a grandfather clock. This vibration exists even at very low temperature, due to a peculiarity of a branch of physics called quantum mechanics. The vibration is called zero point motion. The nucleus then becomes a fuzzy object, like the electrons in an atom. But this amount of fuzziness is not enough to permit a hydrogen nucleus to make contact with another hydrogen nucleus. To get two or more hydrogen nuclei to share the same volume one must go one step further. In a metal electrical current is carried by electrons that act more like vibrating matter waves than like point particles. If electrons did not become wave-like inside solids, there would be no transistors and no present day computers. This wave-like kind of electron is called a Bloch function electron. The secret of cold fusion is that one needs Bloch function deuterons. One needs wave-like deuterons inside or on the surface of a solid in order that two or more deuterons share the same volume of space. But once the Bloch function deuterons are created, the nuclear force comes into play and the protons and neutrons making up the deuterons can rearrange themselves into the more nuclearly stable Bloch function helium configuration, with release of heat. To study cold fusion the experimenter has to force deuterons to assume the wave-like form and keep them in the wave-like state. Cold fusion experiments demonstrating release of excess heat show that this can be done. But at present no one knows how to do it reliably. Since cold fusion promises millions of years of energy without the problems of global warming or radioactivity, a real effort should be made to learn how.

For more tutorials go to www.hometown.aol.com/cffuture1 and www.hometown.aol.com/cffuture2

LENR (Low Energy Nuclear Reactions) Experiments

Review from
http://www.lenr-canr.org

Have you ever wondered what a physics laboratory looks like? They are seldom spacious or organized the way they are shown in movies. Most LENR researchers work at universities or home laboratories, with tight budgets in a crowded space. They keep old, broken equipment on shelves to scavenge parts for new experiments. In this section we present some photographs of equipment provided by researchers, and close up pictures of equipment. The actual cells, cathodes and other equipment used in electrolysis experiments often have an ad-hoc, home-made appearance, because they are made by hand. They have to be; they are unique, one-of-a kind prototypes. Nothing quite like them has ever been made before.

A visitor seeing a LENR experiment the first time may feel disappointed. It looks like any other electrochemical experiment. The heat or neutron flux produced by the experiment are so small they can only be detected with sensitive instruments. A null cathode that produces no effect looks exactly like an active cathode. The difference between one cathode and another is in the microscopic structure, or the traces of elements mixed in with the palladium. Only one kind of cold fusion looks dramatic i. e. the glow discharge reaction.

Here are a few photographs of cold fusion cells and devices (also see the cover page).



Fig.1
Box Calormeter



On Fig. 1 there is a calorimeter constructed by Edmund Storms. Note the DieHard® battery, lower right, that serves as an unninterruptable power supply. A power failure can ruin an experiment. Whenever possible, inexpensive, ordinary materials and instruments are used. However, experiments are never cheap, and they cannot be done on a shoestring. The equipment, arranged for another experiment (see Fig. 2), costs about $40,000.

Fig.2 (On the left)
Vacuum system to prepare particles for gas loaded cold fusion cells, courtesy E. Storms.



Fig.3
A high resolution mass spectrometer used for on-line helium detection during a cold fusion experiment at C. R. ENEA Frascati. (http://www.frascati.enea.it/nhe/)



Fig.4
A cell at ENEA Frascati



Fig.5
A flow-type cell, courtesy E. Storms



Fig.6
Close up of a Miley-style cell, courtesy E. Storms



Fig.7

A cell installed inside a Thermonetics Seebeck calorimeter with the lid removed, courtesy E. Storms


Yamato
SPEED
POWER

Fig.8


Power meter 2
Inkubator
Power meter
Power supply
Teflon cap
Thermo-couple
Logger
Computer
Teflon tube
Coolant out
Pump
Coolant in
Pt
anode
Cathode
Cell
Water bath
Mag. Stirrer

Fig.9

A schematic of the calorimeter shown above.

On the Fig. 8 you can see a glow discharge electrochemical cell at Hokkaido University, courtesy T. Mizuno. The cell is installed inside a crowded constant temperature air-cooled chamber. It placed on a magnetic mixer. Cooling water is pumped through the plastic tubes attached to the top and bottom. The muffin fan at the back circulates the air in the chamber

Hydrogen power engineering

Faraday Laboratories Ltd, Moscow, and Spectrum Investments Ltd, London, started joint R&D project on hydrogen power engineering. Photo: Alexander V. Frolov, Faraday Laboratories Ltd and Nicholas Moller, Spectrum Investments Ltd. The project includes designing and building of prototype to use hydrogen recombination process for heat generation.



On Electrogravitation

Andrey V. Lemeshko

Krasnogvardeyskaya st., 14, apt.11
02094, Kiev, Ukraine
E-mail: jnet@ukr.net

Part I

"let's go to the Mars!"

Nowadays it becomes evident that exploration of deep space by means of rocket equipment is impossible. Aircrafts, which run on jet thrust, are too expensive and unreliable. Besides, they are too slow-speed if were considered on a scale of solar system. For example, the flight to the remote areas of our planetary system can drag on tens years. But the main disadvantage of rockets is their low load-carrying capacity. Thus, the most powerful transport system "Progress" can deliver less than 100 ton of load to the orbit of the Earth, and only 1 ton to the orbit of the Mars. Rather natural question arises as to whether any alternative ways of space exploration exist? Are there any transport systems, which can compete with rocket equipment on the interplanetary routs of future? Actually, at present there is only one technology, which is alternative to rocket ones – it is the so-called light sailers, using light pressure for acceleration. Laser and maser can be also used for their acceleration from satellites. However, there are also some disadvantages here.

There is also one more transport system, which is undeservedly consigned to oblivion. It uses electricity in acceleration aggregate. This transport system or the electric propulsion system is a result of researches and investigations of two little-known, but extremely talented American physicians and inventors, Thomas Townsend Brown and Paul Alfred Biefeld (the last one was also a professor of Astronomy).

Thomas T. Brown was the first who discovered electric principle of this propulsion system. Thus, in twenties of the XX century Thomas T. Brown, being the student of secondary school, became interested in X-rays. He wanted to reveal if the rays, outgoing the X-ray unit, could take positive effect. For his researches the inventor had got Coolidge Tube, the device, which radiates X-rays and consists of a glass tube. Deep vacuum is created in this glass tube. Anode and cathode are placed in the tube. Cathode radiates electrons and anode brakes them. X-rays are created at striking of electrons against anode. Brown used Coolidge Tube in the way nobody had done before. For ease of handling the researcher suspended the device on wires, which run to anode and cathode parallel to the Earth. During the operation of the device he noticed that every time when current fed to the tube, the tube was moved aside and tended to make slight progressive motion. Subsequent experiments demonstrated that the deviation value depended only on the value of voltage, which is between anode and cathode. The higher voltage is, the more deviation. X-rays were neither here not there. Much later at participation of Paul A. Biefeld, the same tendency to move was revealed at plane disc capacitors. The reason, which causes this motion, is the same, i.e. voltage, which exists between plates and not between anode and cathode as in Coolidge Tube.

Having run series of experiments, the researchers proved that electric energy could be directly transformed to mechanical. They also devised the physical principle, which were included in the scientific annals as Biefeld-Brown effect.

Editor's: Let us note that earlier Ampere and Faraday have been working on Electrokinetic effects which are easily detected at strong current. Modern researches on this point are known as "Sigalov's effect" (force appears in electric conductor which is bent at angle and at current impulse).

The essence of this effect lied in the fact that charged disc electric capacitors tend to move in the direction of their positive pole. At formulating of the essence of this effect the scientists consciously did not mention Coolidge Tube in order to demonstrate that according to their experimental observations, electron streams were not involved in generation of electromotive force. This effect of the direct transfer of electric energy to mechanic one (Biefeld-Brown effect) is observed, when current is fed to the Coolidge Tube or to the plane disc capacitor.

However, all this was realized much later, when in 1923 Brown became a student of Dennis University in Greenville, Ohio, where he met his teacher and later on a coauthor, Paul A. Biefeld. In school time the inventor came to the conclusion that the reopened by him phenomenon has nothing in common with X-rays and that high voltage, used for rays generation, is the basis of this phenomenon. Besides, Brown designed a device named "Gravitor". It looked like a usual bakelite box and was made as a simple construction, which consisted of several flat aluminum plates. The plates were placed as coins in a rouleau and separated with dielectric. It had only to place the box on the scale and connect it to some energy source with 100 kV voltage as the device either lost or put on about one percent of its weight that depended on polarity. An outside observer, who was not familiar with the essence of this effect, could think that mass was really changed. *(Editor's: Weight but not the mass is changed here. Weight is the force. There is a possibility of partial compensation of the weight by another force.)* But this was not the case. For better understanding of the processes, which take place at gravitor operating, let us make a mental experiment. Let us take a weight, put it on the scale and then raise it a little. The scale will certainly show that the weight has become lighter. After that let us press the weight then the scale will show that it has become heavier. However, in fact mass does not change. In the same way motive force, caused by high voltage, slightly raises the gravitor and at changing of polarity presses it. At that it seems that there is some change in weight. Thus, as if by chance, the scientist has discovered effect of direct transition of electric energy into mechanical one. *(Editor's: Let us specify the author's terminology. In T.T. Brown's Patent of 1927 it was mentioned that there* *was generated a force which partially compensated weight. The matter was always about the generation of x-force while gravitational field remained unchangeable).*

Having graduated from the University, from 1926 up to 1952 Brown already by himself was being occupied with development of his electrical propulsion system. At the same time whether in chase of fame or in hope to obtain money for his researches, T.T. Brown began asserting that he had discovered something new in physics, viz "electrogravitation", i.e. some connecting effect between gravitation and electricity. *(Editor's: In my opinion, T.T. Brown has never posed a problem in such a way. The matter always concerned the fact that X-force appears while gravitational field does not change.)* As for the development of the invention, it came to the decrease of weight of the device and increase of DC voltage, which fed the plates of the "gravitor". As a result the devices could fly and lift weight which greatly exceeded their own. Thus in 1953 in his laboratory Brown demonstrated the flight of aircraft which had a disk form. The device made 51 m/c (180 km/h), flying at circular course of 6 m diameter. This device was nothing but very lightweight capacitor in which by means of the special construction electromotive force was redirected in two planes upward and sideward. It made the device rise in air and fly around the mast. Current of 50kWtt voltage was supplied to the central mast by the wire. Then speed of "flying disks" became higher, the payload capacity was increased but that was again resulted by decrease of weight and increase of the supplied voltage. T.T. Brown so succeeded in decreasing of the thickness of capacitor plates and in making his devices superlight, that the witnesses of these demonstrations called these devices as "air films".

Later on all works in this area were placed on secret list and then closed because of lack of prospects. Thus, accounts and experiments demonstrated that it was impossible to overcome terrestrial attraction entirely and go to outer space by means of the gravitor because there are no such natural materials which could take huge electric and heat loads. Besides, sufficiently massive electric power station would be needed to produce required currents. *(Editor's: Thereupon the following question appears: why the author looks for "currents" while the essence of the technology is in applying of high voltage but not of the currents?!)* Moreover some alternative was made, i.e. jet engines. Gravitor could not compete with them by above-mentioned and quite objective reasons. In time, since the mechanism of transition of electric energy into mechanical one was not disclosed and Brown's populist idea has received some publicity, this effect became surrounded with idle talks and guess-works. However the scientists who researched this very effect, has developed only three theory wh ich could explain its existence.

The first theory was suggested by T.T. Brown, the discoverer of this effect. To his dying day Brown asserted that he had discovered the effect which could connect gravitation and electricity, i.e. "electrogravitation". But this theory can be easily refuted by practice. It is enough to put Brown's bakelite box to the scale in such a way as to place the plates of the "gravitor" at right angle to the surface of the scales. Then poles of the "gravitor" will be placed at the same level and parallel to ground and as a consequence electromotive force will influence in no way on the scale, since this force is directed sideward but not upward or downward. The scale will accurately show that there are no changes in weight and hence there is no **electrogravitation**. *(Editor's: The author will obtain propulsive force and it is directed not upward and downward but sideward. However the effect exists in any case. The changing of weight appears only when propulsive force generated by the device is directed against the weight force, i.e. upright.)*

The second theory was suggested by T. Brown's opponents. They asserted that electromotive force appears as a result of the so called "electron wind", i.e. electron streams which exist between the plates of the "gravitor". In their argumentations Brown's opponents rest upon the following facts which are well-known to every physicist. Fast electrons, as well as photons, have dual properties, i.e. interacting with matter and environment, they behave both as a wave and as a material particle. Since light or photons carry energy, then they heat bodies which are in their way and put pressure on the illuminated surface etc. Similarly electron streams carry heat or kinetic energy and hence they can put pressure on the anode of Coolidge Tube and get it moving forward. This theory seems to be interesting, however it explains appearance of electromotive force only in Coolidge Tube, but there is no explanation why discoid capacitors tend to move. Point is that there are no free electron streams in the capacitors. Usually between the plates of capacitors there is a dielectric which brings electron streams to nothing. If there is no electron wind, then what makes capacitors move?

Editor's: There is always a surface charge and reactive outflows of ions. But it is just a partial explanation of Biefeld-Brown's effect.

The third theory is based on the following fact. It is well known that electrons can have heat or Brownian chaotic motion. Free electrons, placed in a conductor, are in the similar chaotic heat motion before voltage is applied to this conductor. The higher temperature of the environment is the higher speed of this heat motion. According to school course of physics, heat energy or energy of chaotic motion of molecules (electrons) can be entirely transferred into mechanical one. If all molecules (electrons) start to move simultaneously and in the same direction, and if they push some piston toward this direction then heat energy of molecules (electrons) will be entirely transferred into mechanical work. In other ways, this piston will move until molecules (electrons) calm down. It is considered that this process is unrealizable in practice.

However, it seems that this is not quite the case, i.e. it is possible to regulate chaotic heat motion of electrons. Obviously this process takes place in the capacitor and in Coolidge Tube. It is no secret that when negative electrons try to move to the neighbor positive charged electrode, then dielectric layer which is placed between the plates of the capacitor prevents it. Electrons rest upon this layer and start to heat. Their internal energy is also increasing. The higher voltage is the higher heating of electrons, i.e. their capacity to have chaotic heat motion increases. However, chaotic motion of electrons is not observed on the capacitor plates, since the directed force (voltage) influences electrons. Electrons tend to move upward, downward, to the right and to the left, but voltage prevents it. Thus they just are forced to move in space in one direction and with the same speed. Capacitor or gravitor has to move alongside with electrons because plates of the capacitor (gravitor) become a piston which is pushed by heated electrons. This piston is in progressive motion. It starts to move under the influence of electrons, or rather together with electrons. The higher voltage is, the higher temperature of electrons and hence the higher their speed. Therefore speed of capacitor (gravitor) increases at voltage increase. There is a usual chain, i.e. electric energy transfers into heat energy and heat energy transfers into mechanical one. Approximately the similar process takes place in Coolidge Tube, but there the heat of electrons is caused by thermoelectric emission on the cathode. Electrons evaporate from the cathode surface. Voltage, existing between anode and cathode, makes electrons move in one and the same direction. They move towards anode, which serves as piston and takes heat push upon itself, i.e. it transfers heat energy of electrons into mechanical work. It is clear that the higher voltage is the more intensively electrons are heated. Therefore electrons more intensively influence anode and the suspended tube is deviated to a greater extent. (*Editor's: Nowadays this very explanation is the most admitted one.)*

Resting upon Biefeld-Brown's theory and experimental results and at sufficient financing, already within the next few years it would be possible to create a unique electric engine which can operate on hot or quick electrons. Besides there will appear a possibility to orbit the first spaceship equipped with a propulsion system similar to gravitor one's. In near future scheduled cargo-and-passenger service could be organized within planetary system. First of all such transportations can be organized between the Mars, Moon and Venus orbits that will let to start active colonization of these planets.

Thus, more than 200 flights to the Moon and back and about 70 flights to the Mars are possible by means of the gravitor which is made of modern fusions and dielectric materials and which is placed on the Earth orbit. At that there is a minimum risk for its breakdown during the flight, because gravitor has no movable parts and no explosives are used. Negative consequences for the crew in an improbable emergency are insignificant. Even if high voltage causes disruption of dielectric layer between the electrodes and voltaic arc appears then the spaceship, equipped with such a propulsion system, will mechanically arrive its destination. The source of energy will be its only trouble spot and it will happen only if nuclear reactor instead of solar batteries is used. There is also an idea to attach dwelling capsules and cargo bays, equipped with such electric engine, one after another, like carriages are attached to a locomotive. It will let to equip this interplanetary vehicle in several stages by compactly packed modules which are delivered from the Earth. Unfortunately, this project exists only on paper and support of government or financial institutions is not expected in the near future. Faint hope is rested upon enthusiasts but there are too few of such people, besides almost all of them are rather hardly related to space flights and science. Most of scientists even hear nothing about Biefeld-Brown Effect, because it has never become widely known, since all works of this field, except the very first experiments from the USA, were run and then closed in secrecy.

Part II

"...it's time to go to the stars"

Due to the theory of relativity there is an ingrained belief of several generations that it is impossible to move with more than 300 000 m/c speed, i.e. to move faster than light, since the postulates of this theory read that mass is directly depended on speed. Calculations demonstrate that while speed of some accelerated body verges towards light speed its mass will increase and in the point of equilibrium (V=c) it will unrestrictedly increase. Hence acceleration will tend to zero and speed will not virtually increase, no matter how long acceleration speed acts on the object. In other words, the accelerating mass dissipates speed. In principle it is correct but another conclusion can be also drawn from the dependence of mass and speed, for example, the following one: to accelerate an object to the speed which exceeds light speed, mass of the accelerated body should decrease and its speed should increase. Any physicist will say that this statement is correct. At first sight it is practically impossible to realize this idea therefore it was wrongly give to writers of science fiction. They added this idea to their armory and the hypothetical device, which realizes it, was named as gravitational engine. Let us realize this idea from the practical point of view and basing only on facts and logic.

Thus let us apply to the facts and give the description of one experiment. Professor of Pulkovo Observatory N.A. Kozyrev is the author of this experiment, he was also the first to discover the phenomenon of lunar volcanism. Kozyrev used a gyroscope, i.e. the device consisting of two rings of different diameter. These rings are placed athwart one in another and movably jointed. Top is attached to the inner ring through the cardan. The scientist put usual thermos filled with hot water near the beam scale. The top of the gyroscope was preliminarily spun up counterclockwise. At that balance indicator showed that gyroscope top at 90 gram weight became 4 milligram lighter in weight. Then Kozyrev started to pour water of room temperature inside the device through the vinyl chloride tube fixed into the hole, which was made in the plug of the thermos. Seemingly it is impossible to influence upon the gyroscope operating and its weight by a balloon filled with hot water, which is being cooled. Besides the thermos consists of a double-walled container which practically entirely excludes heat exchange with the environment. However balance indicator moved at one or two points, i.e. such connection existed.

This experiment can be divided into two steps. At the first stage the thermos filled with hot water is placed near the gyroscope and we can register the decrease of the top weight. At the second stage water of room temperature is poured into the thermos and the scale again shows that the weight has been changed. Somehow Kozyrev explained the second stage of this experiment. He assumed that when we pour cold water in the thermos, then the equilibrium of the system is broken because some irreversible processes take place there. Cold water can not cause temperature increase of water in the thermos. Until the system come to equilibrium at a new level, i.e. until the same temperature is set in the whole volume of the thermos, this process will cause the condensation of time which "additionally" influences the top. However the scientist missed that the weight of the top had decreased long before the moment when cold water was poured into the thermos, i.e. before irreversible processes appeared there. *(Editor's: Evidently, the author of the article is not well familiar with Kozyrev's researches and with works of other experimenters who investigated this problem.)* In other words, at the first stage of the experiment there is nothing to condense time and that insignificant weight condensation, which was equal to 4 milligram, absolutely does not fallen into his theory. Some other process is presented there.

It is quite possible that at the first stage of the experiment we deal with nullification of the top weight, i.e. mass of the top tends to zero. Some conclusion arises from this assumption, i.e. hot water can influence the mass of the top in some still incomprehensible way. *(Editor's: The point is not in water temperature but in the process of changing of the entropy.)* Thus there is a simplest and primitive model of the gravitational engine, viz there are hot water along with gyroscope and the required decrease of mass at the "outlet". Certainly, it is very bold assumption but it can be easily checked. Near the gyroscope there should be placed thermos filled with not boiling water (of 100°C temperature) but with water of 50°C temperature. If the weight of the top decreased by one half (for example, by 2 milligram instead of 4 milligram), then we can surely ascertain that the hotter water in the thermos is the more decrease of mass. Besides, each 100°C of water heating will decrease mass of the top by 4 milligram. It is not very difficult to calculate the temperature at which mass of the top will verge toward zero and the top will start accumulating negative mass.

Let us now assume that our experiment was successful then water as well as any other matter cannot be heated to such high temperature. However it is possible to heat electrons. They are very compact and have insignificant mass and can be heated to very high temperature. It is necessary to take several plates then to place a dielectric between them and to apply voltage. Electrons rest on the dielectric and start heating. The top can be rotated anti-clockwise by means of electric engines, i.e. capacitor and gyroscope should be combined in one system with common center of gravity. It is not very difficult, as the saying goes, it is just an engineering problem. The higher temperature of electrons is the more decrease of the top mass. Finally there is a moment when mass of the capacitor-gyroscope system will reach zero and this electric machine will rise to the surface of the gravitational field of the Earth or any other planet. It will be Biefeld-Brown's force that will make our apparatus taking off the gravitational field of the Earth. This very force will start to accelerate our apparatus in the space vacuum and top of the gyroscope will lose its mass which appears at acceleration. Thus it is quite possible to reach speed, which is close to the light one, or even to overcome the threshold of light speed.

Part III

"...what is new?"

What is implied by gravitational waves? This question has been exciting the scientists from the half of the XX century. But still nowadays, in spite of all attempts of the scientists to dissolve the problem, these waves were not discovered. There is a standard way to discover them, which is based on general relativity. Basing on this theory, scientists assume that gravitational waves should change in some way the weight of material objects. According to this assumption the scientists suspend very heavy balls to very precision scale and then try to trace changes of their weight. There were only negative results. It seems that mass changes so quickly and to such short period of time that scale fails to react upon these changes. However there is another way which seems to be very promising.

Dependence of time and gravitation is a well-known fact. Thus speed of time course depends on force of the gravitational field of an object. Stars and planets can be considered as an example. The more intense attraction near them the more slowly time passes there. In other words, the greater mass of the planet the more slowly time passes near it. It is possible that oscillations of masses, which generate gravitational waves, in some way change speed of the time course along the whole way of the propagation of gravitational waves. In other words, gravitational waves are always attended with slight time fluctuations. Time starts to pass a little faster or a little more slowly as compared with its usual course. These changes can be traced by means of usual quartz plates. Let me remind of the fact that quartz plates are used at some models of clocks to keep time. Thus, oscillations of gravitational masses produce in space both gravitational waves and time fluctuations (chronowaves), which can be easily detected. Possibly these chronowaves are the part of gravitational waves. This assumption is already a scientific fact which is unfortunately ignored by more than one generation of researchers.

Professor N.A. Kozyrev was the first who surmised about the existence of time ways (chronowaves). He called them as "time flows". The scientist worked out and run a simple experiment to confirm his hypothesis. Telescope and quartz plates were used. Quartz plates were placed in focus of the telescope, which was pointed to some bright star. Its objective lens was covered with black paper or tin plate in order to exclude the influence of light beams. At that quartz plates reacted upon the presence of chronowaves. Thus there was changed the frequency of oscillations of plates which were placed in focus of the telescope.

Besides the scientist discovered that in focus of the telescope there were changed electroconductivity and volume of some matters. It is explainable since some parameters of space as well as speed of passing of some physical processes and phenomena depend on the speed of time course. Outwardly it appears in change of electroconductivity and volume. In spite of the fact that during the experiments tin plate (thick metal cover) was used some skeptics insisting that the point is in infrared radiation which is produced by the heated cover. However they was silenced by Kozyrev's researches. Basing on the fact that we usually see stars not where they really are, but at the place they were at the moment of emanation of light signal, the scientist calculated the location of Procyon star, which is the nearest to the Earth. Kozyrev pointed the telescope to this "clear" part of the sky zone that allowed to avoid the influence of infrared radiation and to fix the location of the star. Thus it is nothing but chronowaves generated by the star that can change oscillation frequency of quartz plates.

After Kozyrev's death this field of research is not considered by official science and the very existence of chronowaves is denied. Only some theorists warily impute the above-listed effects to the action of some torsion fields and waves the existence of which is rather questionable. However chronowaves exist and they can be used in practice, for example, to get information from any point of our galaxy in several seconds. **It is quite possible since chronowaves have no mass and thus they are propagated more quickly than light waves.** However it is still a question what will transmit this information to us because the transmitter of these waves yet has not been invented. *(Editor's: It is interesting what mass of light waves the author means. It is a pity that the author of the article did not read 9 previous issues of NET magazine! There was a detailed demonstration of the connection of Kozyrev's theory and experiments with the theory of longitudinal waves in aether. If to replace Kozyrev's notion of "waves of time density" by the notion of "waves of aether density" then we will get a real experimental approach which can help to solve the problem of antigravitation and time control.)*

Of course theoretically chronowaves can be also generated without participation of great gravitational waves (it seems that heat processes can also generate them). However no particular success was achieved in this field. Thus by means of chronowave transmitter it is possible just to "listen" to remote stars the light of which will reach the Earth in many years. This receiver is very simple and it can be made by anyone who knows a little about radio engineering. *Under home conditions it is better to use a miniature incandescent bulb (lamp with filament tungsten) as a receiver and usual ohmmeter as measuring instrument.*

If in usual receivers radio waves are excited by weak electric currents existing in antenna then chronowave antenna is constantly under tension. Chronowaves do not excite current there but change some characteristics of it, influencing on electroconductivity of the matter which was used for the antenna (let us remember Kozyrev's experiments). Later on these insignificant changes are transferred in audio signal or fixed by any other means. That is the principle of operation of the device.

Editor's: These experiments on the registration of flicker effect in more detail are described in A.M. Mishin works which were published in previous issues of our magazine. As the reader could notice, the editors' opinion in many respects does not coincide with the author's point of view. (Alexander V. Frolov)

References

1. *G.Ya. Myakishev, B.B. Buhovtsev,* Physics, *M.: Prosveschenie, 1991*
2. *A.S. Kuzovkin, N.N. Nepomnyaschy,* What happened to torpedo-boat "Eldridge"? *M.: Znanie, 1991, Series "Znak voprosa" #3, p.37*
3. *S.N. Zigunenko,* How the time machine is made? *M.: Znanie, 1991, Series "Znak voprosa" #5, p.35*
4. A. Einstein and gravics, *Collection of articles, M.: Mir, 1979*
5. *A.D. Chernin* Physics of time, *M.: Nauka, 1978*
6. *A.I. Veinik* Thermodinamics of natural processes

Time Machine

Alexander V. Frolov gave this interview to the Spain magazine "Mas Alla de la Ciencia" ("Science"). The interview concerns some questions about scientific-research work on investigation of active properties of time. Let us remind that in 2002 Faraday Lab Ltd and Vadim A. Chernobrov (Moscow) started the join Time Machine Project.

Miguel Segui: How does it value the results obtained by the prototype of time machine?
Alexander V. Frolov: Usually it is about 3% changes, i.e. 3 sec per 100 sec of experiments.

M.S.: How other devices are preparing inside the project Time Machine?
A.F.: Now we have project with special electromagnets, which are emitters of the longitudinal waves. So, other devices are electronics parts to provide impulse current. But it is not the only one version of the system. If the emitters of the longitudinal waves are based on other principles so all device has other design.

M.S.: Do you believe that some day the time trips will be possible?
A.F.: Yes, sure. We have the clear theory for it and it is based on understanding of physical sense of the aether, its relation with notion of time and with concept about existence of elements of matter in space-time. According to aether-vortex theory any element of matter is created from aether and its temporal parameters depend on density of aether.



M.S.: What practical applications can have the prototypes that are developing?
A.F.: Any change in the time course is the method of influence onto biological systems and the medical aspect is the main application. Also any physicist know relation between G (the gravity constant) and time course (rate of time). For example, time is slower on the surface of Earth than in space. So, local time changes (which are changes in density of aether or direction of aether wind) can be used to get propulsion force without reactive mass

flow. Also we can hope that some new materials can be produced in special area of slowed or accelerated time course.

M.S.: Which are the main difficulties of developing of these devices at the moment?
A.F.: For us now it is a part of the work that is related with designing of the powerful current electronics circuits. Also there are no known analogies for patent work, but we hope to complete our patent claim in March of 2003.

M.S.: Is it foreseen that they carry out experiments with human beings and the machine of modification of the time, just as V. Chernobrov carried out?
A.F.: We, i.e. Faraday Laboratories Ltd, are developing small unit for testing of the principles. In future we'll work with other design and with participation of the pilot (human passengers). But it will be the system of other kind. Let me explain: now we are working to get small local change of the aether density, so called "chronal charge". It is analogy with electric charge, which produces electric field in space. If the electric charge is moving then it will produce magnetic field. According to our plans after confirmation of the principles we are going to create design with moving "chronal charge" to generate "chronal field". There are suppositions that this field can be used practically for antigravitation propulsion transport.



"FRCM" – Avalanchedrive
Fractioning and Replacement of a Constant Mass

Murilo Luciano Filho, Brazil

murilo@intrumenti.com.br, avalanchedrive@hotmail.com

For the while, this project has only these two names, as above. There is still a lot to do upon this development that involves free energy and / or "over-unity". It is designated to be of free use and application by everybody and everywhere, without any royalties just like it was a very old idea, which is now opened for entire community use. The inventor has enough strong reasons for this will.

This is a kind of donation, a personal donation, for the very best future of the Earth. Pioneers are needed (late pioneers?) Any person may be involved in this development to make money since there are no barriers for that. This means that this is an open idea and in this way it must stay. The principles are new and original and the energy involved is quite huge. In the inventor's mind there is realized the possibility to create an expert hands-on group to finish the project. In this article there is a rough draw which seems to be enigmatic but in fact it can clear the understanding of the principle and show the situation at which body may offer controlled spatial variation of length for the same weight.

The short text and a schematic draw (see Fig.1) are the way to show the principles and a few possible construction solutions. The photo shows a part of the device which can clear the so called weight localized rarefaction. Possibly the understanding of capacity for an observer will be a little forced. If necessary author can send the full patent requirement text, which contains 54 pages and 32 figures, not in English but in Portuguese.

FRCM – "AVALANCHEDRIVE"



Fig. 1

Understanding of **FRCM / avalanchedrive** is a challenge in itself. When you start to learn about FRCM you will find complete original problems to deal. **Free your mind basing on some mechanical and physics knowledge and then avalanchedrive will come to make a part of your life. Feel free to work.**

PATENT REQUIREMENT RELEASE

This patent requirement is basically the application of a new physical principle which could be defined and found at least 400 years ago, so simple it is. Surely it is one of such things which was let behind by human mind and concern. FRCM is odd and amazing. The key for this project is a special body that can behave like a solid and like a fluid, at the same time, with combined characteristics just as designed and required.

The mass potential of a specially designed segmented body is hold and managed, and throughout proper means is sequentially fractured while suspension balance is kept. This causes, after start, a constant and cyclic movement, since arrangement goes, and the conducting and forcing form of the mass is not interrupted.

Also called "avalanchedrive", this principle work is based on just three main parts or components: 1st is the special segmented body – a chain; 2nd is the stationary and external assembling to hold and conduce the chain; 3rd is the straight vertical, in order to achieve the maximal weight storage position in the arrangement.

The chain is an endless repetitive zigzag construction with weights and defined angles that looks like an entire and elongated ellipse. Its design makes easy the change of its profile and form (mutant profile) that will be contracted or elongated, according to the way it is organized, supported and driven. When contracted or expanded, the chain assumes its maximal or minimal weight, in comparatively the same heights and level, but at different cross sections (tunneling?).

For distribution of the chain track the external assembling forms a kind of duct or rail, which is also elliptical. It allows to the chain to be contracted and expanded, to change direction, move, and pass away, as desired. The chain follows the way that the rail allows, in four different zones: mass-united zone, or positive column, or weight capacitor; the lower reversion input zone; the liberation zone, or negative column, with same height of the positive one; and the upper reversion zone, and its "zero point", or non-resistance top.

Both reversion zones are composed mainly of wheels. However, while the lower zone has to hang, open and bolt the chain, in order to change its profile and natural falling-down trajectory, the upper has a very passive function, that is just to let the chain cross over, and avoid any turn back possibility.

Fact is that in all circuit the chain follows with passivity the "voids" of trails, but assumes a very strong positive and pressure action in mass-united zone, especially in the button, where to the wheel there is applied all the active potential weight of the device, formed by the entire stack of the full contracted state, forcing movement.



Photo of FRCM (Avalanchedrive)

It is easy to understand how and why FRCM works. Weight of the positive column is directly connected – as a compressed spring – against the relatively lighter negative column, through lower reversion wheel, where happens a kind of flux (the "solid flux") of the chain, that never can find a state of rest. Cycles of "breaking" of the chain can beconsidered as the instant of touch of each corner of the chain to the lower step wheel. To complete the circuitry, the chain excess, which is much lighter, passes over the upper wheel and turns back to the positive column top. It is impossible to turn the full subtracted potential to its source but mechanically the easier job to be done in FRCM.

FRCM manages and converts mass in energy...

The chain flows from the positive column, naturally finds changed profile and reverses to opposite way, and then it is pushed up to the negative column and to top. Finally it is collected, friendly, to restore the potential, at non-stop run! The only alternative to the chain is to move and move, and apply the positive surplus of weight to wrench under axle of the wheel.

This FRCM principle allows develop the equipment which is going to be able to take energy, work and force from gravity potential, so as it happens from wind and water at electrical generator machines, today. The potential is kept in such critical situation, that the only way for it is to escape and move. Besides in consequence of the suspending mass state the linear constant repetition of event will suffer. Water and other fluids do not offer "mutant profile" with fixed value of pressure, just as solid materials. There are many arguments for this view.



Fig. 2
Segment of a chain

Considering all mechanical losses, a part of the mass will be very active and applied in eccentric, or radial position to the wheel, even with the risk to cause too high speed. FRCM manages and converts mass in energy.

See a non-scale schematic draw (Fig. 2) and photo of a chain segment to compare densities between columns at right and at left.

A theoretical case can be calculated: at total chain weight - 100, general losses - 20, total negative resistance - 30, active or positive surplus is 50 – 30 = 20. This surplus that may be of 2kg, 200kg or 2,000kg, depending on scale, will force and free edge of the wheel, while the total weight keeps confined in the device. In the above case the difference of balance is 1.66. This means that the flowing velocity of the negative pile is 1.66 times higher than the falling of opposite positive pile. Just like a "solid venture", this change and relation is fixed, and in other cases may be varied or calculated to 3, 4 or even more! In all cases the speed must be hold that is not very easy job while one faces gravity acceleration.

The author of FRCM conceptions feels like these ideas have been around for many centuries, and that they are now discovered just like old draws. And this can be the bigger and the best moment to release this. Many thousands of different designs and solutions are coming in the future at looking for the better performance, costs and durability. Author thinks it to be strange that previous guesses could not reach this macro-physical concept. To build FRCM circuits, even re-applied or used old pieces, for example from ships and trains, will be useful.

This is only a start to a "new-old" development and clue to the sources of the modern mechanical engineering. Certainly some oppositions should be overcome. It is expected that other names are also going to be created and proposed to FRCM, but "avalanchedrive" seems to be a good one.

Author expects to get the invention and concept credits but not royalties and would also be glad to keep working on this concern. So, this message is a kind of invitation...

Editor: Unfortunately we have no photo or video documents of the operative device. We wait for readers' comments on this invention.

Complete text of the patent is avaible in Pourtuguese only.

ELECTRIFY
an online and published
magazine about Electric,
Hybrid, Fuel Cell Vehicles,
advanced batteries, ultra capacitors,
fuel cells, microturbines, free energy systems,
EVents and exhibitions worldwide

63600 Deschutes Mkt Rd,
Bend Oregon, 97701
541-388-1908 fax 541-388-2750
etimes@teleport.com
www.electrifyingtimes.com
Subscription $13/3 issues

Institute for Planetary Synthesis

P.O. Box 128, CH-1211 Geneva 20,
Switzerland
Tel. 41-022-733.88.76, Fax 41-022-733.66.49
E-mail: ipsbox@ipsgeneva.com
website: http://www.ipsgeneva.com

Hydrogen-Powered Vehicles at Least a Decade Away

Peter Behr
Greg Schneider

Washington Post
http://www.washingtonpost.com/wp-dyn/articles A635122003Jan29.html
Thursday, January 30, 2003; Page A09

This information is forwarded as a courtesy from:
http://www.integrityresearchinstitute.org

President Bush's vision of a hydrogen-powered, non-polluting "Freedom" car for the next generation of American motorists pulled out silently from a Newport Beach, Calif., garage with Gregg Kelly at the wheel, bound for his office 10 miles away.

Kelly, president of a California robotics company, happens to drive a Toyota prototype of a hydrogen-fueled car, one of a handful in the United States today.

It will take at least a decade before a host of technological, economic and political barriers are overcome, permitting a fleet of these revolutionary vehicles to appear on U.S. highways, industry experts said. But by including the goal of hydrogen fuels in his State of the Union message Tuesday, Bush has opened the door to a fledgling movement that has already attracted a surprising coalition of supporters.

Environmentalists, automakers, oil companies and coal producers, engineering labs and strategists have seized on hydrogen as an almost too-good-to-be-true power source. It is abundant in water and air, it burns cleanly and it could free the nation from its dependence on Middle Eastern oil.

"For President Bush to frame the goal as he did is significant," said Jeremy Rifkin, consultant and author of a book advocating a transition from oil and gas to hydrogen. "How much is made of this, time will tell."

The president said he hoped that Americans born today would learn to drive in hydrogen-powered cars, a schedule that auto experts said could technically be met. But whether these vehicles will be commercially available depends on a huge array of variables.

First, the technology is still incomplete and unaffordably expensive. The specially equipped Toyota Highlander that Kelly drives has no price tag. The Japanese manufacturer, after investing millions of dollars in research, lent the vehicle to a University of California research project that Kelly's company supports. "My checkbook isn't fat enough," Kelly said.

The car is powered by electricity generated in a fuel cell by chemically combining hydrogen and oxygen. The engine spits out water drops instead of the carbon dioxide and other pollutants generated by burning gasoline.

With foreign manufacturers committed to press ahead, Detroit's carmakers have had to accelerate their research programs. In June, Ford Motor Co. will unveil a prototype car that uses hydrogen to power an internal combustion engine – part of a "bridging strategy" to help ease hydrogen into the marketplace until fuel cells are fully developed.

General Motors Corp. has developed a fuel cell-powered, car-sized "skateboard" – four wheels attached to a platform less than a foot thick, to which any kind of car body could be buckled.

Rather than use fuel cells, BMW has refitted 10 of its $70,000 Model 745 sedans with hybrid engines that burn either gasoline or liquid hydrogen directly. It could be mass producing them by the end of the decade at a "reasonable" cost for its customers if there were enough hydrogen fueling stations to power them, said spokesman Gordon Keil. "We're trying to get [fuel suppliers] interested in hydrogen. We've not met with a lot of enthusiasm."

As daunting as the engineering challenge is the need for a national hydrogen fuel infrastructure – factories to produce the fuel, pipelines and trucks to distribute it and stations to store and sell it. Environmentalists dream of a totally "green" strategy in which solar or wind power is used to separate hydrogen from water – an approach whose costs now would be prohibitive. A nearer prospect is producing hydrogen from natural gas or coal, however in either case, the carbon dioxide byproduct would have to be injected underground to avoid a huge increase in greenhouse-gas emissions, experts say.

Rifkin argues that an eventual scarcity of oil and gas, decades ahead, will push prices of these fuels up to a point where hydrogen becomes cost-competitive. "It isn't a problem that will yield to technology alone," agreed David M. Nemtzow, president of the Alliance to Save Energy.

While all the major automakers are developing fuel-cell technology, most are cautious about hyping it. "We don't want to get too exuberant about it in that sense, overselling it," said Greg Dana, vice president for environmental affairs at the Alliance of Automobile Manufacturers.

Fresh in some minds is the experience of the Clinton administration, which launched a high-profile, $1.5 billion research venture with the

Detroit automakers a decade ago to produce an 80 miles-per-gallon family car. No cars emerged, and the Bush administration halted the venture in favor of its hydrogen strategy.

Some of the president's political opponents contend the hydrogen option is a way of deflecting criticism over administration policies favoring energy production over conservation. "The president seems content with the auto industry's approach: 'Don't make us do anything today'," said the Sierra Club's Daniel Becker. Others say it does not go nearly far enough. Sen. Byron L. Dorgan (D-N.D), chairman of the Democratic Policy Committee, said recently, "It's moving in the right direction. But his proposal is rather timid. I think we need a bolder plan."

Bush's spending plan for the hydrogen project, $1.5 billion over five years, represents a $500 million increase over his current budget. The administration proposes to earmark $273 million for the 2004 fiscal year, but did not offer many specifics yesterday. The funding would support research on fuel cells, vehicle technology and distribution issues.

The magnitude of the goal demands an effort on the scale of the Apollo Moon project, Dorgan said yesterday. "You have to set benchmarks for five, 10 years out."

UNUSUAL PERMANENT MAGNET MOTORS

Thomas Valone

Integrity Research Institute,
www.integrityresearchinstitute.org
1220 L St. NW, Suite 100-232, Washington, DC 20005
Email: iri@erols.com

Abstract

Permanent magnet motors that try to achieve unusual overunity efficiencies with changes in wiring geometry, electronic switching schemes and magnetic configurations often are not successful. There are some designs that should be regarded as conventional and others as promising. Hopefully this article will help the reader to tell the difference before investing or accepting investment. Note: patents can be viewed for free at www.uspto.gov and also http://gb.espacenet.com/espacenet.

Introduction

An article about permanent magnet (PM) motors would not be complete without first reviewing the basic configurations that are present on the market today. Commercial PM motors are necessarily DC motors since their magnets are permanently polarized before assembly. Many PM motors which use brushes are switching to brushless motors that promise less friction and wear. Brushless motors include electronic commutation or step motors. A step motor, often used in the automotive industry, offers more continuous duty torque per unit of volume than any other electric motor but it is often a lower speed motor. The electronic commutation design is applicable to the switched reluctance (SR) motor. The SR motor substitutes soft iron in the place of higher cost permanent magnets for the outer stator and instead has an inner PM rotor. Brushless motors in general produce torque from current in the armature by the application of Faraday's Law. The ideal PM motor has a linear torque vs. speed curve. There are both outer rotor and inner rotor designs that are standard in PM motors.



Fig.1

Lenz's Law
Induced B-field opposes motion.

To point out the focus of many of the problems with analyzing motors, the *Motion Control Handbook* (Designfax, May, 1989, p. 33) says that there is a "very important relationship between torque and back emf that is sometimes not understood." This relates to the electromotive force (emf) that is produced by the application of a changing magnetic field (dB/dt). In engineering terms, the "torque constant" (N-m/amp) equals the "back emf constant" (V/radian/sec). In physics, the motor terminal voltage

Detroit automakers a decade ago to produce an 80 miles-per-gallon family car. No cars emerged, and the Bush administration halted the venture in favor of its hydrogen strategy.

Some of the president's political opponents contend the hydrogen option is a way of deflecting criticism over administration policies favoring energy production over conservation. "The president seems content with the auto industry's approach: 'Don't make us do anything today'," said the Sierra Club's Daniel Becker. Others say it does not go nearly far enough. Sen. Byron L. Dorgan (D-N.D), chairman of the Democratic Policy Committee, said recently, "It's moving in the right direction. But his proposal is rather timid. I think we need a bolder plan."

Bush's spending plan for the hydrogen project, $1.5 billion over five years, represents a $500 million increase over his current budget. The administration proposes to earmark $273 million for the 2004 fiscal year, but did not offer many specifics yesterday. The funding would support research on fuel cells, vehicle technology and distribution issues.

The magnitude of the goal demands an effort on the scale of the Apollo Moon project, Dorgan said yesterday. "You have to set benchmarks for five, 10 years out."

UNUSUAL PERMANENT MAGNET MOTORS

Thomas Valone

Integrity Research Institute,
www.integrityresearchinstitute.org
1220 L St. NW, Suite 100-232, Washington, DC 20005
Email: iri@erols.com

Abstract

Permanent magnet motors that try to achieve unusual overunity efficiencies with changes in wiring geometry, electronic switching schemes and magnetic configurations often are not successful. There are some designs that should be regarded as conventional and others as promising. Hopefully this article will help the reader to tell the difference before investing or accepting investment. Note: patents can be viewed for free at www.uspto.gov and also http://gb.espacenet.com/espacenet.

Introduction

An article about permanent magnet (PM) motors would not be complete without first reviewing the basic configurations that are present on the market today. Commercial PM motors are necessarily DC motors since their magnets are permanently polarized before assembly. Many PM motors which use brushes are switching to brushless motors that promise less friction and wear. Brushless motors include electronic commutation or step motors. A step motor, often used in the automotive industry, offers more continuous duty torque per unit of volume than any other electric motor but it is often a lower speed motor. The electronic commutation design is applicable to the switched reluctance (SR) motor. The SR motor substitutes soft iron in the place of higher cost permanent magnets for the outer stator and instead has an inner PM rotor.

Brushless motors in general produce torque from current in the armature by the application of Faraday's Law. The ideal PM motor has a linear torque vs. speed curve. There are both outer rotor and inner rotor designs that are standard in PM motors.



Fig.1

Lenz's Law
Induced B-field opposes motion.

To point out the focus of many of the problems with analyzing motors, the *Motion Control Handbook* (Designfax, May, 1989, p. 33) says that there is a "very important relationship between torque and back emf that is sometimes not understood." This relates to the electromotive force (emf) that is produced by the application of a changing magnetic field (dB/dt). In engineering terms, the "torque constant" (N-m/amp) equals the "back emf constant" (V/radian/sec). In physics, the motor terminal voltage is equal to the back emf minus the IR drop due to internal resistance. (Example: V = 8.3 v, back emf = 7.5 v, IR drop = 0.8 v.) This physics principle, also referred to as **Lenz's Law**, was discovered by Friedrich Lenz in 1834, three years after Faraday invented the homopolar generator. The oppositional nature of Lenz's Law, and its back emf, is built into a physical law called **Faraday's Law**, which is at the root of motor drive. The back emf is the reaction of the changing current in the coil. In other words, the changing magnetic field naturally creates a back emf because they are equivalent.

Therefore, it is recommended that Faraday's Law be carefully reviewed first before proceeding. An article such as "Faraday's Law—Quantitative Experiments" (*Amer. Jour. Phys.*, V. 54, N. 5, May, 1986, p.422) will help convince the valiant new energy experimenter that the change in flux which causes a back electromotive force (emf) is INHERENTLY equal to the back emf. It cannot be avoided or circumvented for excess energy benefit, unless the amount of magnetic flux change per time is also altered. They are two sides of the same coin. The energy into an inductive coil style of motor will naturally equal the energy out. Also referred to as "electrical induction," the changing flux "induces" a back emf.

Switched Reluctance & Field Switching Motors

To explore an alternative method for inducing motion, the "Permanent Magnet Motion Conversion Device" by Ecklin, patent #3,879,622, uses rotatable shutters for alternately shielding the poles of a horseshoe magnet. Repeated again in the Ecklin #4,567,407 "Biased Unitized Motor Alternator with Stationary Armature and Field," the idea of switching the magnetic field with a "flux switch" is common to these types of motors. To illustrate the underlying principle, Ecklin states, "The rotors of most of today's generators are repelled as they approach a stator and are attracted back by the stator as soon as the rotor passes the stator in accordance with Lenz's law. Thus, most rotors face constant nonconservative work forces and therefore, present generators require constant input torque." However, "the steel rotor of the unitized flux switch alternator actually aids the input torque for half of each rotation as the rotor is always attracted and never repelled. This construction makes it possible for some of the current or power fed to the motor windings to magnetically feed through a solid magnetic path to the AC output windings ..." Unfortunately, Ecklin still to this day has not achieved a self-running machine.

Also related is the Richardson patent #4,077,001 which discloses a low-reluctance keeper physically moving in and out of engagement with the ends of a magnet (p.8, line 35). Lastly, the Monroe patent #3,670,189 uses a related principle but accomplishes gating with the passing of rotor poles between permanent magnet stator poles. Monroe's claim 1, seems by its length and detail, to have almost guaranteed its patentability but of course its utility remains questionable.

It seems unlikely that as a closed system the Field Switching Motor can become self-running. In many examples, a small electromagnet will be necessary to help push the keeper into a synchronized rhythm. The Magnetic Wankel from Popular Science (June, 1979) can be compared in a basic manner to this type of invention. Also, the Jaffe patent #3,567,979 can also be compared (see abstract). The Minato patent #5,594,289 is also of a similar type as the Magnetic Wankel and quite intriguing to many people.

It has been found with inventions such as the Newman motor (U.S. Patent Application Serial No. 06/179,474), a nonlinear effect such as an impulse voltage is advantageous for overcoming the Lorentz force conservation effect of Lenz's Law. Also similar is the mechanical analog of the Thornson inertial propulsion device which uses nonlinear impact to transfer momentum along an axis perpendicular to the plane of rotation. A magnetic field contains angular momentum which only becomes apparent under certain circumstances such as Feynman's Disk Paradox, where it is still conserved. The impulse technique may possibly be used to advantage in this Field Switching Motor if the field switching can be done fast enough, with a rapid rise time, but more research is needed.



Fig. 2
Switched Reluctance Motor (*IEEE Spectrum* 1/97)

The best Switched Reluctance Motor that also has full accommutation is the Dr. Harold Aspden patent #4,975,608 which optimizes the performance of the coil input and operating above the knee of the B-H curve. Switched reluctance motors are also explained and praised in *IEEE Spectrum* (1/97).



Fig. 3

Adams Motor

The Adams motor has attracted many followers including an endorsement from *Nexus* magazine as the best free energy motor they have seen. The performance of the machine, however, can be fully explained by Faraday's Law. The pulsing of adjacent coils which moves a magnetized rotor is actually following the same configuration as a standard switched reluctance motor. The delay that Adams speaks of in an Internet posting of his motor can be understood from the exponential voltage (L di/dt) of the back emf. The latest addition to this category, which gives credit to the Adams motor, comes from down under with PCT WO 00/28656 awarded to Brits and Christie in May, 2000. The simplicity of this motor is immediately obvious with the switchable coils and permanent magnet on the rotor. The patent also makes it clear that the "input DC current as supplied to the stator coil produces the magnetic repulsion force and is the only outside input to the overall system for total movement…." It is a well-known fact that all motors work on this principle. The key to their design is on p.21 of their patent where the inventors want to "maximize the influence of back EMF which tends to maintain rotation of the rotor/armature in a single direction." All of the motors in this field-switching category try to achieve this effect. Figure 4A of Brits and Christie disclose the voltage sources "VA, VB, and VC." Then, on page 10 it is stated, "At this time current is applied from the power source VA and continues to be applied until the brush 18 is no longer in contact with one of the contacts 14 to 17." There is nothing unusual about this design compared with the more sophisticated attempts listed previously in this section. All of these motors require an electrical power source and none of them are self-running.

When pulsing a coil with the passing of a permanent magnet, a suggestion that would help prove the claim for free energy is not to use battery power for the coil current. Instead, the amazing Weigand wires are recommended (*Pop. Sci.*, May, 1979) that exhibit a huge Barkhausen jump of magnetic domain alignment and a very well-defined pulse shape. Having a coil wrapped around a Weigand wire produces a substantial pulse of several volts with a changing external magnetic field passing a certain threshold. No electrical input power is required for this pulse generator.

Toroidal Motor

As compared to motors on the market today, the unusual design of the toroidal motor is similar to the Langley patent #4,547,713 with a two-pole armature in the center of the toroid. If a single-pole design is chosen, with for example North poles at each end of the armature, this would resemble the radial magnetic field for the armature which the VanGeel patent #5,600,189 uses. The Brown patent #4,438,362 assigned to the Rotron company, utilizes varying magnetization segments for a rotor in a toroidal air gap. The best example of a carousel toroidal motor is the Ewing patent #5,625,241, which also resembles the Langley patent mentioned above. Based upon magnetic repulsion, the Ewing invention uses a microprocessor-controlled carousel, basically to try and take advantage of Lenz's law and get a jump ahead of the back emf. The Ewing invention may be seen in operation, with co-inventor David Porter, in the commercial video, "Free Energy: The Race to Zero Point." Whether it may be more highly efficient than other motors on the market remains an open question. As the patent states, "it is also possible to operate the device as a motor using a pulsed direct-current power source" (col. 7, par. 30). It also contains a programmable logic controller and power control circuit which the inventors thought would send it over the top of 100% efficiency.

Unless a prototype proves to be successful in achieving a torque or force conversion linkage, the internally propelled magnet may be left without a practical application. Commercialization of these types of motors may not be favorable, since many competing designs are currently available on the market, with high flux linkage.

Linear Motors

The area of linear induction motors is well known in the literature. Schaum's Outline Series, *Theory and Problems of Electric Machines and Electromechanics* (McGraw Hill, 1981), explains that these are the same as cutting the rotor and stator of a standard induction motor and laying them out flat. The late Dr. Laithwaite, author of

Motion Without Wheels, was famous for monorail designs for trains in England based on linear induction motors.

The Hartman patent #4,215,330 is an example of one that achieves a linear motor transportation of a steel ball up a magnetized incline of approximately 10 degrees. Another invention in this category is the Johnson patent #5,402,021, which uses permanent arc magnets on a four-wheel cart, exposed to a parallel track of alternating permanent magnets which are in a fixed position. An even more amazing permanent magnet patent is the Johnson #4,877,983 which an eye witness has seen operating at the Johnson home in a closed loop for hours. It is reasonable to assume that a pickup coil could be positioned nearby so that each trip would result in a pulse of electricity to charge a battery. The Hartman patent could also be arranged in such a circular track so that perpetual motion of the first kind can finally be demonstrated.



Fig. 4

Hartman patent #4,215,330

The Hartman patent is based upon the same principle as the famous electron spin experiment in physics called the Stern-Gerlach experiment. With an inhomogeneous magnetic field (one that is non-uniform) the force on an object with a magnetic moment is the gradient of the potential energy. Every physics textbook points out that this type of field, that is strong at one end and weak at the other end, will result in a unidirectional force on the magnetic object equal to dB/dx. That is exactly what the Hartman patent possesses (note spacing of magnets). Therefore, the resulting force propelling the ball up a ten degree incline, in the x direction, is in keeping with the laws of physics.

With state-of-the-art magnets, including ambient temperature superconducting magnets which are now finishing the development stage, a demonstration of impressive cargo weight will be shown to be transportable without maintenance electricity costs. Superconducting magnets have the unusual property of retaining the initial magnetized field for years, without the need for periodic energization to restore the initial field strength. Examples of the state of development of the superconducting magnet market can be found in the Ohnishi patent #5,350,958 (lack of cryogenics and lighting system output) as well as the reprinted article from *IEEE Spectrum*, July, 1997 on magnetic levitation.

Static Electromagnetic Angular Momentum

In a provocative experiment with a cylindrical capacitor, Graham and Lahoz (*Nature*, V.285, No.15, May, 1980) have expanded upon the proof published by Einstein and Laub in 1908 that the Lorentz force needs an additional term to preserve action and reaction. The article they cite has been translated and published in my book, *The Homopolar Handbook* (described below). Graham and Lahoz emphasize that there is a “real angular momentum density to r x (E x H)/c^2” and suggest how to see this energy effect in permanent magnets and electrets.

This is encouraging work, with an impressive source of Einstein and also Minkowski for its information. It is possible that it may have a direct application for the homopolar generator as well as the magnetic energy converter mentioned below since both have an axial magnetic field and a radial electric field like the cylindrical capacitor experiment of Graham and Lahoz.

Homopolar Motor

My book, *The Homopolar Handbook* (HH), covers experimental tests and history of the Faraday discovery, including Tesla’s contribution to it. Recently however, there have been new developments into a multi-rotor design of a homopolar generator, similar to the invention of John R. R. Searl.

Recurring interest in the Searl device, as pictured on the cover of *Antigravity*, the biography of Searl by John Thomas, should also center on the homopolar generator (HG). Preliminary analysis reveals that there are actually two separate HG phenomena occurring simultaneously, one which can be called the "revolution" effect (#1) and the second that could be called the "rolling" effect (#2). The first effect can be visualized as magnetized segments of an imaginary solid ring revolving around a common center. As suggested by drawings in HH, p.141-2, there are precedent designs that allow for segmenting an HG rotor.

With this model in mind, the #1 effect can be calculated, for 1 Tesla strength magnets, magnetized axially, adjacent to a single ring 1 meter in diameter, to produce more than 2 volts emf across each roller, (E-field directed radially from outer diameter of rollers to outer diameter of the adjacent ring) with say, 500 RPM. Note that this #1 effect is independent of any rolling of the magnet. The magnetic field in an HPG is tied to space and not to the magnet so rolling will not affect this large scale homopolar generator's Lorentz force effect (HH, p.10).

The #2 effect, located within each roller magnet, is the one noted in *Electric Spacecraft Journal*, Issue 12, 1994, (HH, p.160) where each roller, is a small homopolar generator. This effect is found to be somewhat weaker as it generates electricity from the center of each roller to its periphery. This design is like Tesla's HG (HH, p.81) where a rolling belt is contacting the outer edge of a circular magnet. With rollers in the vicinity of a tenth of a meter in diameter rolling, without slipping, around a 1 meter ring, approximately a half of a volt will be generated. The Searl design of ring magnetic material will normally strengthen the roller's B field.

It is important to realize at this point that the principle of superposition applies to these two effects. The #1 effect is a uniform E field across the diameter of the roller. The #2 effect is a radial effect as stated above (see HH, p.6-8). However, only the emf in the section of a roller between the two contacts, say at the center of the roller and its edge which contacts the ring, will actually cause current flow in any external circuit. This realization means that the effective voltage from the #1 effect will be half of the available emf, or a little more than 1 volt, which is still about double of the #2 effect. Upon applying superposition in the limited region indicated, we also find that the two effects oppose each other and the two emfs must be subtracted. The result of this analysis is that approximately one half of a volt of regulated emf will be present to generate electricity from a single set of rollers and one ring about 1 meter in diameter. As current is drawn, a Ball Bearing Motor effect will also take place (HH, p.54) that actually pushes the rollers along, assuming the roller magnets have a reasonable conductivity *(Thanks to Dr. Paul La Violette for this reminder)*.

In a related work, (*Tech. Phys. Lett*., V. 26, #12, 2000, p.1105-07), Roshchin and Godin have published experimental results of their one-ring device, called a "Magnetic Energy Converter," with rolling magnets on bearings. It was designed as an improvement to the Searl device. Though my above analysis does not depend upon the ring being made of magnetic material, Roshchin and Godin did so. Their findings are encouraging and detailed enough for researchers to find renewed interest in this type of magnetic motor.



Fig.5

Magnetic Energy Converter in the experiment
by Roshchin and Godin (Russia)

Conclusion

So far, a couple of permanent magnet motors may have achieved perpetual motion, which exceeds 100% efficiency. Of course, conservation of energy concepts have to be considered and the source of the alleged extra energy examined. If permanent magnet field gradients do offer a unidirectional force, as the textbooks predict, then it is about time for its conversion toward useful work. The roller magnet geometry, now called a "magnetic energy converter" is also a unique style of magnetic motor. Exemplified in the Russian patent #2155435 by Roshchin and Godin, it is a magnetic motor-generator that shows potential for excess energy output. Since it relies upon the circulating cylindrical magnet rolling around a ring, the design is actually a generator rather than a motor. However, as they utilize the torque produced by the self-sustained motion of the magnets to run a separate electrical generator, it is working as a motor.

Reprint from Proceedings of Institute for New Energy Conference, 2001

Hydrogen Energetics

Review by Alla Pashova

A Russian writer Ludmila Ulitskaya, who is rather far from energy problems, says: "I'm quite sure that cheap electric energy sources have been already worked out and are hidden in oil king's safes. However such projects won't be taken out of the safes until the last oil drop is combusted. They don't want redistribution of money, world, power, and soon". Experts are sure to agree with the writer.

Now only ideas which can coexist together with the traditional oil power engineering and with a system of world oil distribution can escape the safes. Some expensive scientific toys promising future universal welfare are created to reassure ecologists, viz automobiles equipped with hydrogen engine. According to estimation of Japan representatives of motor car industry, installation of the hydrogen engine into such a car as a classical Sedan now comes to about $700 000. Approximate cost of a hydrogen bus named Kitaro achieves the astronomic amount of $1.25 million.

The hydrogen engine consists of several fuel elements, which are known as fuel cells. Hydrogen under pressure of 1.5-2.7 atmospheres comes to an anode. A cavernous catalyst splits the molecules into electrons and protons. The electrons set the electric engine in motion, and the protons come through a membrane acting to a cathode as an electrolyte. Here the catalyst combines them with the working electrons and with atmosphere oxygen into water molecules. It should be noted that the Europeans and the Americans are extremely charmed by this water streamlet which is exhausted instead of poisoning gases. Moreover, output of the fuel cell is 3-5 times more than output of the petrol engine.

The first hydrogen power station inaugurated in Las Vegas, Nevada, in 2002, (see Fig.1, 2) represents a system of the fuel cells with the proton penetrable membrane as an electrolyte (they are designed and produced by experts of Plug Power Inc.). The station produces hydrogen transforming and cleaning natural gas and generates electric power combining hydrogen stored in reservoirs with atmosphere oxygen. The USA Energy Department and Air Products Inc. together paid $ 10.8 million for this project.

It is necessary to note that the priority branch of the hydrogen engineering is providing new means of transport with fuel, and electric power production is just the second aim. The mentioned station produces electric power in addition to its main function. Nevertheless, if fuel market begins to decrease then the electric power payments will provide the "hydrogen magnates" with stable profit.



Fig. 1

Hydrogen power station

Nowadays the hydrogen automobiles allow oil kings keep the system of centralized fuel distribution and the infrastructure of service stations which will provide the means of transport with methanol, natural gas with hydrogen blend, and liquefied or gaseous hydrogen. Thus interested companies control the hydrogen engineering and scientific thought.

Moreover, oil can be applied as it is useful for board reforming (conversion), i.e. it can be used as a hydrogen source. The systems based on conversion have been known for a long time but there was need to work at them.

Russian experts improved the conversion system by replacement of the catalyst by plasma. Thus the conversion occurs in gas discharge of HVF appearing in the blend which needs to be converted. According to experts' opinion the Russian system is portable and has high output. In 2001 a group of experts of Russian Centre of Automobile Engine represented experimental prototype basing on Chevrolet Pickup S 10.

The ideal of modern hydrogen engineering is the following: "There should be minimal changes in the system of fuel distribution, non-polluted air, and thin streamlet of distil exhausted". However, evidently, the exhausted water is an ideal source for hydrogen fuel reproduction by means of high effective electrolyzing. If the closed system is worked out we would obtain an energy source powered by continuous chain of electrolyzing and recombination whose efficiency would be more than 100 %.

What are the known ways of hydrogen production? The greatest amount of the gas is produced on the base of catalytic conversion of hydrocarbon with water vapor. Temperature of the process depends on the catalyst composition. It is known that temperature of propane reaction can be decreased to 370° using bauxite as a catalyst. Approximately 95% of by-product carbon monoxide is further used in the reaction with water vapor.

A significant part of the total hydrogen production is given by a method of water gas. The essence of the method lies in reaction of water vapor with coke that is followed by the producing of carbon monoxide with hydrogen mix. The reaction is endothermal, it occurs at 1000°C. The heated coke is processed by the vapor; extracted purified mix of gases contains some hydrogen, some carbon dioxide, and great share of carbon monoxide. Further vapor processing of the carbon monoxide at 370°C increases the hydrogen extraction. The amount of carbon dioxide increases as well however it is easy to be removed by passing the gases mix through a scrubber sprayed by a water contraflow.

AIR PRODUCTS

Fig. 2

There is a well-known iron-vapor method according to which vapor is passed above iron at 500-1000°C. Hydrogen obtained by this method is usually applied to hydrogenise fats and oils. Composition of the iron oxide depends on the process temperature. Iron-3 oxide (Fe_3O_4) prevails at the temperature below 560° C. If the vapor is passed above the iron at the temperature above 560° C then iron-2 oxide (*FeO*) share increases. A slight admixture of carbon monoxide is removed when the heated mix passes above a catalyst. At this time the carbon monoxide is transformed into methane.

In the processes of oxidation and thermal cracking of hydrocarbons at soot production hydrogen is produced as a by-product.

The next effective method is methanol-vapor one. It is an endothermal reaction which is proceeds in common iron reactors at 260° C temperature and at 20 atmospheres pressure.

There should be also mentioned a catalytic reaction of ammonia decomposition at which nitrogen and hydrogen is produced. The reaction can be profitable if it is necessary to produce great amount of hydrogen. The method is useful if the obtained hydrogen is directly applied.

Electrolysis is the oldest method to produce hydrogen. Direct current comes to electrodes, the cathode collects hydrogen, and the anode accumulates oxygen. The technology makes hydrogen to be too expensive energy carrier. There is often used a technology of hot processing of water vapor at 700-900° C accompanied with light petrol and heavy liquid fuel which bleeds oxygen. This method is quite expensive as well.

As it is known, **wasteful power consumption of classical electrolysis** is caused by the fact that it is used to overcome forces of hydrate bound of ions with water molecules and to compensate endothermal effect of water decomposition. Therefore, ions reduction at corresponding electrodes requires more current intensity than in the case of absence of this physical phenomena. Hence production of 1 cubic meter of hydrogen requires 18-21.6 MJ, and total power consumption exceeds 50 MJ (taking into account the electric power production). Therefore hydrogen becomes too expensive.

In 1888 D.A. Lachinov patented a method of non-contact electrolysis. Improvement of this method promises huge amount of cheap hydrogen and appearance of high effective energy source operating as a closed cycle. The main problem of Lachinov's method is a gas layer covering the electrode in some time and impeding the reaction. It was proposed by I. A. Goryachev to prevent the gas layer using pulsating electric field. A.V. Frolov has proposed to increase electrolysis efficiency by means of rotation. Centrifugal force causes more swift detach of gas blebs from electrodes surfaces. Power consumption to overcome frictional force in the construction and to generate potential electric field is insignificant as compared with output. Hence efficiency of the system may exceed 100%.

There is also described the experimental device for production of hydrogen and oxygen from water where modulated voltage (not dc voltage) is applied to the electrodes. Modulation frequency is in connection with proper oscillation frequency of water molecules as well as with spatial structure. Possible efficiency of water electrolysis in spark discharge which removes oxygen admixture should be investigated . Water electrolysis at the radiation by electromagnetic waves of light range needs to be investigated as well.

Ikar Research Centre informs that plasma electrolysis can be the most probable source of cheap hydrogen. In 1987 a group of Russian scientists patented the first plasma-electrolytic reactor. Since the reactor had been worked out at a defense establishment then the patent was restricted and not covered by press. The patent contains a structural scheme of the reactor and some results of cleaning and disinfection of water by plasma. The patent does not represent any information of additional energy generated by plasma or hydrogen production.

In April of 1989 American scientists Pons and Fleishman published their experimental results on additional energy production at common water electrolysis. They claimed cold fusion to be source of this energy. However there is no reliable proof for this phenomenon.

In 1996 Yu. Beklyamishev, one of the co-authors of the first plasma-electrolytic reactor, published his experimental results. They demonstrated that there was additional energy in the plasma-electrolytic process. However he did not explain the energy source.

In 1998 there were published new experimental issues of appearance of additional energy in the plasma-electrolytic process. A group of Russian scientists tested one of the plasma-electrolytic reactors and officially fixed the additional energy. A report of the testing session was published in issue #22 of "Infinite Energy" magazine. In May of 1998 the third edition of a book named "Crisis of Theoretical Physics" was published by Prof. F. M. Kanarev. It contains data of additional energy production at plasma electrolysis of water defining the energy source. Soon Ohmori and Mizuno (Japan) published their results in works of Vancouver conference on cold fusion and in issue #20 of "Infinite Energy". Ohmori and Mizuno observed neutron radiation occurring at a plasma process as well as iron, chrome, nickel, and carbon appearance on a wolfram cathode. That seemed to be a strong evidence of cold nuclear fusion at plasma electrolysis of water. Ohmori and Mizuno have explained neutron radiation as a result of electrons captured by protons. Nevertheless their conclusions raise doubts as cold fusion would have produced much more additional energy than it was fixed.

In 1996 there appeared the first publications where hydrogen atoms fusion instead of nuclear fusion was supposed as the additional energy source at usual electrolysis as well as at plasma source. In Russia first experimental results demonstrating energy consumption decrease for hydrogen production at plasma electrolysis of water were published in 1999 by Prof. F.M. Kanarev. (See F.M. Kanarev's article in this issue of NET).

HONDA
FCX-V3

Fig. 3

Honda FCX-V3 uses hydrogen as a fuel. Hydrogen is fed under high pressure in the engine.

Nevertheless we have to note that high efficiency electrolysis is possible! O. Hvolson in his "Physics" (Berlin, 1923) explains a method of designing of a machine which can produce heat due to positive difference between energy of hydrogen combustion and energy consumed to hydrogen production by means of water electrolysis. In this case we do not consume energy to split the atoms. It occurs due to intermolecular forces at water dissociation by sulphuric acid ions. Energy is consumed only to neutralize charges of existent hydrogen ions and acid residue ions. Hydrogen combustion produces the energy which would have been consumed to split the atoms in the air. **Hence 67.54 Kcal of energy can be produced at 5 Kcal consumed. (F. Lepehin)**

High effective electrolysis application is clear future of energetics. Nowadays Stuart Energy Inc applies water electrolysis as a hydrogen source in a frame of hydrogen-fuel project. Experts of Stuart Energy Inc have designed a refueling unit which produces hydrogen and stores it in a 104-pound reservoir. Thus several auto are provided with fuel and it takes a couple of minutes to refuel.

It is quite simple to predict social and economical consequences of innovation of high effective energy source operating as a closed cycle energy system. Economic activity and private life of people will be independent of cities, of their industry and power engineering. People will move out of the cities and they will use compact and powerful energy sources there. Hence, decentralization of world economics will happen.

Regions of any country become more free from the central authority, the power of which nowadays is based on centralized fuel energetics.

On the Longitudinal Electromagnetic Waves

Alexander V. Frolov

General Director, Faraday Lab Ltd
Phone/fax: 7-812-380-3844
Email: office@faraday.ru

Concerning acoustic waves, we deal with longitudinal oscillations of the medium, since degree of air (medium) compression and rarefication changes along the direction of the wave spreading. Notion of the medium of electromagnetic waves propagation, i.e. notion of "aether", as well as the very possibility of the existence of longitudinal electromagnetic waves is disputable for some scientists. Let's clarify the situation and demonstrate that usual photon is longitudinal wave of energy density, which can be described as Umov-Poynting vector.

The transverse character of electromagnetic waves means that vector of electric field and vector of magnetic field are directed across the wave line. However, these vectors are just our subjective way to describe the process. Notions of electric and magnetic fields can be replaced by the notion of **unified helical field**, since to describe the motion of the point along the helical line there should be concerned the linear transfer (it is detected as electric field) and the process of rotation (it is described with the magnetic field). Thus notions of electrodynamics are just one of the ways to describe reality. Energy density of the given point of space is the real (objective) parameter of the wave. This energy density is described by the known Umov-Poynting vector $\overline{S} = \overline{E} \times \overline{H}$.



Fig.1

Let us consider electromagnetic wave in classical representation (Fig.1). Then we discover that direction of Umov- Poynting vector coincides with the wave line. The vector is unidirectional and "pulsating", because its quantity changes from zero to some maximal value and then it is reduced to zero, besides it takes place at half of the period of transverse wave. So, it is the explanation of the fact that frequency of longitudinal oscillations is twice as much than frequency of transverse oscillations (Fig. 2). **Previously it was known from the mechanism of energy interchange between longitudinal and transverse plasma oscillations and from the phenomenon of parametrical resonance. However the physical meaning of this phenomenon was not disclosed.**

From the presented here conception it follows that from the physical point of view, electromagnetic waves are **longitudinal oscillations of energy density**. In usual case these oscillations are unidirectional pulsations that determines the ability of the photon to be moving unidirectionally. Practically it is possible to create other types of photons, i.e. types of oscillations of energy density with qualitative new physical properties. It can be achieved by setting of definite functions and superposition of $\overline{E}$ and $\overline{H}$ vectors.

For example, in 1996 a conference "New Ideas in Natural Science" was organized by us in Saint-Petersburg, with the participation of 30 foreign guests and more than 100 Russian scientists. The report made by Academician Ignatyev, Krasnoyarsk, aroused great interest. During the experiments with rotating of crossed vectors $\overline{E}$ and $\overline{H}$ (see Fig. 3) there was created Poiting's vector, which corresponds to propulsion force of 60 N (about 6 kg).



Fig. 2

The experiment is demonstrated on the photo (see Fig. 4), where the diameter of the device is equal to 4 meters and ends of the coils are to toroidal capacitors. This experiment was made in Krasnoyarsk.



Fig. 3

Since it is impossible to consider vacuum, where some form of energy can exist, as "emptiness" then we can speak about vacuum as about some medium. Faraday and Maxwell, classics of electromagnetic theory, wrote exactly about deformations, stresses and expansion of aether. From this point of view electromagnetic waves are analogues of the waves of longitudinal deformation of elastic medium. More than 60 years ago Nicola Tesla wrote: "I showed that the universal medium is a gaseous body in which only longitudinal pulses can be propagated, involving alternating compressions and expansions similar to those produced by sound waves in the air. Thus, a wireless transmitter does not emit Hertz waves which are a myth, but sound waves in the ether, behaving in every respect like those in the air, except that, owing to the great elastic force and extremely small density of the medium, their speed is that of light." [1]

Nowadays, the development of engineering and the new views upon the phenomena of electromagnetism, impel us to consider physical **vacuum as material medium of the special type**, which has the well-known properties, in particular electrical and magnetic properties. Moreover, this medium has energy, and energy density can be changed in case of propagation of any photon. Thus, as Tesla stated in his article "The True Wireless": "The Hertz wave theory of wireless transmission may be kept up for a while, but I do not hesitate to say that in a short time it will be recognized as one of the most remarkable and inexplicable aberrations of the scientific mind which has ever been recorded in history".



Fig. 4

References

1. "Pioneer Radio Engineer Gives Views on Power", New York Herald Tribune, Sept. 11, 1932.

“OUTSIDE THE BOX” SPACE AND TERRESTRIAL TRANSPORTATION AND ENERGY TECHNOLOGIES FOR THE 21ST CENTURY

Theodore C. Loder

tedloder@aol.com

Institute for the Study of Earth, Oceans and Space
University of New Hampshire
Durham, NH 03824

Abstract

This paper reviews the development of antigravity research in the US and notes how research activity seemed to disappear by the mid 1950s. It then addresses recently reported scientific findings and witness testimonies - that show us that this research and technology is alive and well and very advanced. The revelations of findings in this area will alter dramatically our 20th century view of physics and technology and must be considered in planning for both energy and transportation needs in the 21st century.

Historical Background

Townsend Brown’s Technology of Electrogravitics [1]

In the mid 1920’s Townsend Brown [2] discovered that electric charge and gravitational mass are coupled. He found that when a capacitor is charged to a high voltage, it has a tendency to move toward the positive pole. His findings, which became known as the Biefeld-Brown effect, were opposed by conventional minded physicists of his time.

The Pearl Harbor Demonstration. Around 1953, Brown conducted a demonstration for military top brass. He flew a pair of 3-foot diameter discs around a 50-foot course tethered to a central pole. Energized with 150,000 volts and emitting ions from their leading edge, they attained speeds of several hundred miles per hour. The subject was thereafter classified.

Project Winterhaven. Brown submitted a proposal to the Pentagon for the development of a Mach 3 disc shaped electrogravitic fighter craft. Drawings of its basic design are shown in one of his patents. They are essentially large-scale versions of his tethered test discs.

Review of Issues from the 1950s

In 1956, a British research company, Aviation Studies (International) Ltd. published a classified report on Electrogravitics Systems examining various aspects of gravity control. They summarized the pioneering work of Townsend Brown and then described the use of electrogravitic thrust as follows:

“The essence of electrogravitics thrust is the use of a very strong positive charge on one side of the vehicle and a negative on the other. The core of the motor is a condenser and the ability of the condenser to hold its charge (the K-number) is the yardstick of performance ” [3].

In one of their conclusions, based on Brown’s work, they suggested that: “Electrostatic energy sufficient to produce a Mach 3 fighter is possible with megavolt energies ” [4].

In spite of Brown’s solid research, they later stated that, “One of the difficulties in 1954 and 1955 was to get aviation to take electrogravitics seriously. The name alone was enough to put people off” [5]. It seems that is as true today as it was in the 1950s.

A report by another British company, Gravity Rand, Ltd. in 1956, agrees with this assessment and states: “To assert electrogravitics is nonsense is as unreal as to say it is practically extant. Management should be careful of men in their employ with a closed mind or even partially closed mind on the subject.” [6]

However, a trade press magazine, The Aviation Report, made numerous references to antigravity projects and listed many of the companies pursuing research in this area. Quotes from The Aviation Report listed in the Aviation Studies (International) Ltd. Report [7] are suggestive of what was going on behind the scenes.

In 1954 they predicted that: “… progress has been slow. But indications are now that the Pentagon is ready to sponsor a range of devices to help further knowledge.”… “Tentative targets now being set anticipate that the first disk should be complete before

1960 and it would take the whole of the 'sixties to develop it properly, even though some combat things might be available ten years from now." (Aviation Report, 12 October 1954) [8].

During this time period many of the major defense and technology companies were cited as either having research projects or activities in this new field. For example: "Companies studying the implications of gravitics are said, in a new statement, to include Glenn Martin, Convair, Sperry-Rand, and Sikorsky, Bell, Lear Inc. and Clark Electronics. Other companies who have previously evinced interest include Lockheed, Douglas and Hiller." (Aviation Report, 9 December 1955) [9].

Others of these reports mention: AT&T, General Electric, as well as Curtiss-Wright, Boeing and North American as having groups studying electrogravitics.

During the same time period, the Gravity Rand report notes that: "Already companies are specializing in evolution of particular components of an electogravitics disk." [10]

However, in the area of predictions, the Aviation Report stated the following based on an extrapolation of technology development: "Thus this century will be divided into two parts – almost to the day. The first half belonged to the Wright Brothers who foresaw nearly all the basic issues in which gravity was the bitter foe. In part of the second half, gravity will be the great provider. Electrical energy, rather irrelevant for propulsion in the first half becomes a kind of catalyst to motion in the second half of the century." (Aviation Report, 7 September 1954) [11].

Looking back it is easy to say that they missed the mark. Did they really miss it by a half a century? Reading through these reports it is quite obvious that there was much interest in antigravity among a number of very high profile companies, as well as in the Department of Defense. What happened to this interest and why was it all downplayed during the following four plus decades? After all, T. Brown had shown that there is a demonstrable connection between high voltage fields and gravity. Why has it taken until the 1990s for more than just a few scientists to look at these results and publish on them in the open literature? A review of recent statements by former military personnel and civilians connected to covert projects begins to shed light on research activity in these areas over the last half century. **And it appears that there had been significant breakthroughs during this time period, well shielded from both the scientific and public eye.**

Recent Scientific Developments

In this section we consider developments in the antigravity field since the late 1980s and why the confluence of scientific findings and the testimony of witnesses associated with the military and covert groups indicates that a gravity solution with technological implications has been found.

Although general relativity has not been able to explain Brown's electrogravitic observations, or any other antigravity phenomenon, the recent physics methodology of quantum electrodynamics (QED), appears to offer the theoretical framework to explain electrogravitic coupling. Recent papers by members of the Institute for Advanced Study Alpha Foundation are putting a solid theoretical foundation onto the antigravity effects within the theory of electrodynamics and include papers by Evans [12] and Anastasozki et al [13].

Earlier in a 1994 breakthrough paper, Alcubierre showed that superluminal space travel is, in principle, physically possible and will not violate the tenants of the theory of relativity [14]. Puthoff [15] later analyzed these findings in light of the present SETI (Search for Extraterrestrial Intelligence) paradigms that insist that we could not be visited by extraterrestrial civilizations because of the speed-of-light limitations dictated by the general relativity theory. He suggests that superluminal travel is indeed possible. This leads to reduced-time interstellar travel and the possibility of extraterrestrial visitation, which our limited understanding of physics and scientific arrogance has "forbidden" in some sectors for most of the 20th century.

The second aspect of these physics findings deals with the zero point or vacuum state energy shown by the Casimir effect [16], which predicts that two metal plates close together attract each other due to imbalance in the quantum fluctuations. The implications of this zero point or vacuum state energy are tremendous and are described in several papers by Puthoff [17] starting during the late 1980s. Bearden [18] and colleagues have also written extensively on the theoretical physics of zero point energy and additionally have described various technological means of extracting this energy (for example see the recent paper by Anastasozki et al [19].). A theoretical book on zero point energy (and antigravity) was published by Bearden in 2002 [20]. There is significant evidence that scientists since Tesla have known about this energy, but that its existence and potential use has been discouraged and indeed suppressed over the past half century or more [21].

The coupling of the electrogravitic phenomena observations and the zero point energy findings are leading to a new understanding of both the nature of matter and of gravity. This is just now being discussed in scientific journals (though some evidence suggests that it has been understood for decades within the black project covert community). The question that is being addressed is: what keeps the universe running? Or more specifically, where do electrons get their energy to keep spinning around atoms? As electrons change state they absorb or release energy, and where does it come from? The simplistic answer is that it is coming from the vacuum state. Puthoff [22] describes the process as follows: "I discovered that you can consider the electron as continually radiating away its energy as predicted by classical theory, but **simultaneously absorbing a compensating amount** of energy from the ever-present sea of zero-point energy in which the atom is immersed. An equilibrium between these two processes leads to the correct values for the parameters that define the lowest energy, or ground-state orbit (see "Why atoms don't collapse," NEW SCIENTIST, July 1987). Thus there is a DYNAMIC EQUILIBRIUM in which the zero-point energy stabilizes the electron in a set ground-state orbit. It seems that the very stability of matter itself appears to depend on an underlying sea of electromagnetic zero-point energy."

Furthermore, it appears that it is the spinning of electrons that provides inertia and mass to atoms. These theories, linking electron spin, zero point energy, mass, and inertia have been presented in a number of recent papers, such as those by Haisch [23] and colleagues and provide us with a possible explanation of the Biefield-Brown effect. It appears that an intense voltage field creates an electromagnetic barrier that blocks the atomic structure of an atom from interacting with the zero point field. This slows down the electrons, reducing their gyroscopic effect, and thus reducing atomic mass and inertia, making them easier to move around.

Evidence of Extensive Antigravity Technology

The B-2 Advanced Technology Bomber

In 1993, LaViolette wrote a paper [24] discussing the B-2 bomber and speculating on its probable antigravity propulsion system, based on a solid understanding of electrogravitics, [25] the aircraft's design and the materials used in its manufacture. It appears that the craft is using a sophisticated form of the antigravity principles first described by T. Brown. Support for this thesis came from the Aviation Week and Space Technology (March 9, 1992), which reported that the B-2 bomber electrostatically charges its leading edge and its exhaust stream. Their information had come from a small group of former black project research scientists and engineers suggesting the B-2 utilizes antigravity technology. This information was supported by Bob Oechsler, an ex-NASA mission specialist who had publicly made a similar claim in 1990. These findings support the contention that there have been major developments in the area of antigravity propulsion which are presently being applied in advanced aircraft.

LaViolette later states the obvious that "the commercial airline industry could dramatically benefit with this technology which would not only substantially increase the miles per gallon fuel efficiency of jet airliners, but would also permit high-speed flight that would dramatically cut flight time." [26]

The Hunt for Zero Point [27]

This recent book contains some of the strongest evidence yet for major efforts and success in the field of antigravity technology. The author, Nick Cook, who for the past 15 years has been the Aviation Editor and Aerospace Consultant for Jane's Defense Weekly, spent the last 10 years collecting information for the book. This included archival research on Nazi Germany's antigravity technology and interviews with top officials at NASA, the Pentagon and secret defense installations. He shows that America has cracked the gravity code and classified the information at the highest security levels. **Because antigravity and its allied zero point energy technologies potentially offer the world a future of unlimited, non-polluting energy it has been suppressed because of the "huge economic threat".** His findings support those reported by many of the Disclosure Project witnesses cited above.

Antigravity Technology Demonstrations

Although T. Brown reported many of his findings nearly a half century ago, other experimenters have just recently begun to reproduce his work and report on it in the open literature and on the WWWeb. For example, Davenport [28] published the results of his work in 1995 supporting the findings of T. Brown, while Bahder and Fazi [29] in 2002 described their assessment of the forces associated with an asymmetric capacitor. Transdimensional Technologies [30] in the USA and J. Naudin [31] labs in France have posted on the WWWeb: diagrams, web videos, and data on their versions of antigravity "Lifters" based on an extension of Brown's work. It is a sad commentary on this whole area of research to see that public science is requiring us to demonstrate principles that were demonstrated nearly fifty years ago.

There have also been a number of other demonstrations of "antigravity" phenomena by researchers throughout the world. This includes the work of Brazilian physics professor, Fran De Aquino, and such devices as: the Searl Electrogravity Disc, the Podkletnov Gravity Shield and Project Greenglow, the Zinsser Kineto-baric Field Propulsion and the Woodward Field Thrust Experiments on Piezoelectrics. All of these are described in more detail by Greer and Loder. [32]

Implications of This Research

Antigravity and zero point energy research and their applications are finally being addressed by some of the open scientific community. This means there will have to be a rewriting of textbooks in this area so our new generation of students can apply this "new knowledge." Its application will lead to major breakthroughs in transportation technologies both earthside and in outer space. The implications are that we have the potential for human exploration of our solar system and beyond, if we have the will, within our lifetimes. It also means that the majority of 20th century space technology will be obsolete and in fact may already be so.

The zero point or vacuum state energy source is seen as a totally non-polluting energy source, which has the potential to replace all the fossil fuels on this planet. It also will provide the energy needed for long range space flights. This means that fuel cells and solar cells in common use today for space flight energy applications will only be needed until we transition to these new energy technologies.

Based on an analysis of trends in antigravity research over the last half-century and the information provided by numerous witnesses, it appears that there is both good and bad news. The good news is that it appears that we (at least covert projects) have already developed the theories of antigravity, and additionally have developed working spacecraft based on these principles. The bad news is that these technologies have been developed for at least several decades, at the public's expense and that human kind has been deprived of these technologies, while continuing to waste energy using less efficient and pollution enhancing technologies.

Supporting this contention is the following quote from Ben Rich, former head of the Lockheed Skunkworks. Just prior to his death, he stated to a small group after a lecture [33] that: "We already have the means to travel among the stars, but these technologies are locked up in black projects and it would take an act of God to ever get them out to benefit humanity…" He further went on to say that, 'anything you can imagine we already know how to do.' Strong words from a knowledgeable deep insider and words that support what a number of the witnesses stated as well.

As the reality of this knowledge begins to be understood, there will be an outcry among space scientists not on the inside for release of these technologies to allow all of us to explore space. There will be major changes in the way that NASA does its business, though predicting these changes is difficult.

Not only has space exploration in the public sector suffered, but our planet's environment has suffered as well. Thus as this knowledge begins to sink in there will be an outcry among all concerned citizens on this planet for release of these technologies to allow all of us to reduce and ultimately eliminate global warming and environmental pollution that so threatens our way of life. These technologies will not only affect space travel technologies, but will also have a profound effect on transportation and energy production on the earth's surface.

In conclusion, we might consider the observation made by Halton Arp [34]: "We are certainly not at the end of science. Most probably we are just at the beginning!"

Acknowledgements

I thank the following people for many discussions while preparing and writing this paper including: S. Greer, A. Craddock, T. Bearden, P. LaViolette, M. McCandlish, D. Hamilton, T. Valone, E. Mallove, T. Loder, C. Loder, S. Patel and many of the courageous Disclosure Project witnesses.

References Cited

1. Quoted from: LaViolette, P. A. 2000. Moving Beyond the First Law and Advanced Field Propulsion Technologies. In T. Loder (ed.), "Outside-the-Box" Technologies, Their Critical Role Concerning Environ-mental Trends, and the Unnecessary Energy Crisis. Report prepared for The U.S. Senate Environment and Public Works Comm. www.senate.gov/~epw/loder.htm.
2. Brown, T. T. 1929. How I control gravity. Science and Information Magazine, Aug. 1929. Reprinted in Psychic Observer 37 (1): 66-67.
3. Aviation Studies (International) Ltd. 1956. Electro-gravitics Systems: An examination of electrostatic motion, dynamic counterbary and barycentric control. p. 14. In Valone, T. (ed.), 1994. Electrogravitics Systems: Reports on a new propulsion methodology. Integrity Research Institute, Washington, DC 20005.
4. Ibid. p. 27.
5. Ibid. p. 19.
6. Gravity Rand Ltd. 1956. The Gravitics Situation. p. 54. In Valone, T. (ed.), 1994. Electrogravitics Systems: Reports on a new propulsion methodology. Integrity Research Institute, Washington, DC 20005.
7. Aviation Studies (International) Ltd. 1956. Electrogravitics Systems: An examination of electrostatic motion, dynamic counterbary and barycentric control. p. 11. In Valone, T. (ed.), 1994. Electrogravitics Systems: Reports on a new propulsion methodology. Integrity Research Institute, Washington, DC 20005.
8. Ibid. p. 34.
9. Ibid p. 41.
10. Gravity Rand Ltd. 1956. The Gravitics Situation. p. 47. In Valone, T. (ed.), 1994. Electrogravitics Systems: Reports on a new propulsion methodology. Integrity Research Institute, Washington, DC 20005.
11. Aviation Studies (International) Ltd. 1956. Electrogravitics Systems: An examination of electrostatic motion, dynamic counterbary and barycentric control. p. 32. In Valone, T. (ed.), 1994. Electrogravitics Systems: Reports on a new propulsion methodology. Integrity Research Institute, Washington, DC 20005.
12. Evans, M. W. 2002. The link between the Sachs and O(3) theories of electrodynamics. In Evans, M.W. (ed.), Modern Nonlinear Physics, Pun 2. 2nd ed., Advances in Chemical

Physics 19:469-494.
13. Anastasovski, P.K., T.E. Bearden, C. Ciubotariu, W.T. Coffey, L.B. Crowell, G.J. Evans, M.W. Evans, R. Flower, A. Labounsky, B. Lehnert, M. Mészáros, P.R. Molnár, S. Roy, and J.-P. Vigier. 2001. Anti gravity effects in the Sachs theory of electrodynamics Foundations of Physics Letters. 14(6):601-605
14. Alcubierre, M. 1994. The Warp Drive: Hyper-fast travel within general relativity. Classical and Quantum Gravity, 11, L73.
15. Puthoff, H. E. 1996. SETI, The Velocity-of-Light Limitation, and the Alcubierre Warp Drive: An Integrating Overview, Physics Essays 9:156.
16. Lamoreaux, S.K. 1997. Demonstration of the Casmir force in the 0.6 to 6 μm range. Physics Review Letters. 78:5.
17. Puthoff, H. 1989. Gravity as a Zero-Point Fluctuation Force." Phys. Rev A., 39(5):2333-2342. Puthoff, H. 1989. Source of Electromagnetic Zero-Point Energy." Phys. Rev A, 40(9):4597-4862.
18. See the Tom Bearden web site for an extensive listing and copies of his papers at: www.cheniere.org.
19. Anastasovski, P.K., T.E. Bearden, C. Ciubotariu, W.T. Coffey, L.B. Crowell, G.J. Evans, M.W. Evans, R. Flower, A. Labounsky, B. Lehnert, M. Mészáros, P.R. Molnár, J.K. Moscicki, S. Roy, and J.P. Vigier. 2001. Explanation of the motionless electromagnetic generator with 0(3) Electrodynamics. Foundations of Physics Letters, 14(1):87-93.
20. Bearden, T. 2002. Energy from the Vacuum: Concepts and Principles. Cheniere Press, Santa Barbara, CA.
21. Valone, T. 2000. The Right Time to Develop Future Energy Technologies. in T. Loder (ed.). "Outside-the-Box" Technologies, Their Critical Role Concerning Environmental Trends, and the Unnecessary Energy Crisis. Report prepared for The U.S. Senate Environment and Public Works Comm. www.senate.gov/~epw/loder.htm.
22. Puthoff, H. 1990. Everything for Nothing. New Scientist, 28 July 1990, pp. 52-55.
23. Haisch, B., Rueda, A. and Puthoff, H. 1994. Beyond E =mc2; A First Glimpse of a Postmodern Physics, in which Mass, Inertia and Gravity Arise from Underlying Electromagnetic Processes. The Sciences, 34:26. Haisch, B., Rueda, A., and Puthoff, H. 1997. Physics of the Zero-Point Field: Implications for Inertia, Gravitation and Mass. Speculations in Science and Technology, 20:9. Haisch, B. and Rueda, A. 1998. An Electromagnetic Basis for Inertia and Gravitation: What Are the Implications for 21st Century Physics and Technology? in El-Genk, M.S. (ed.), Space Technology and Applications International Forum-1998, DOE CNF-980103, CP420, p. 1443. Haisch, B. and Rueda, A. 1999. The Zero-Point Field and the NASA Challenge to Create the Space Drive. Proc. NASA Breakthrough Propulsion Physics Workshop, NASA/CP-1999-208694, p. 55.
24. LaViolette, P. 1993. The U.S. Antigravity Squadron. p. 82-101. In Valone, T. (ed.), 1994. Electrogravitics Systems: Reports on a new propulsion methodology. Integrity Research Institute, Washington, DC 20005.p.82-101.
25. LaViolette, P. A. 1992. Electrogravitics: Back to the future. Electric Spacecraft, Issue 4, pp. 23-28. LaViolette, P. A. 1993. A theory of electrogravitics. Electric Spacecraft, Issue 8, pp. 33-36
26. LaViolette, P. A. 2000. Moving Beyond the First Law and Advanced Field Propulsion Technologies. in T. Loder (ed.). "Outside-the-Box" Technologies, Their Critical Role Concerning Environmental Trends, and the Unnecessary Energy Crisis. Report prepared for The U.S. Senate Environment and Public Works Comm. www.senate.gov/~epw/loder.htm.
27. Cook, N. 2001. The Hunt for Zero Point: Inside the World of Antigravity. Broadway Books, NY. 256pp.
28. Deavenport, L. 1995. "T.T. Brown Experiment replicated. Electric Spacecraft Journal. Issue 16. Oct. 1995. (Reprinted in: Valone, T. (ed.), 1994. Electro-gravitics Systems: Reports on a new propulsion methodology. Integrity Research Institute, Washington, DC 20005)
29. Bahder, T.B. and Fazi, C., "Force on an Asymmetric Capacitor," Army Research Laboratory, v51 ARL-TR.nb. Avail. at: http://xxx.lanl.gov/abs/physics/02110. 2002.
30. Transdimensional Technologies, 906-E Bob Wallace Ave., Huntsville, AL 35801.
31. http://jnaudin.free.fr
32. Greer, S.M. and T.C. Loder III. 2001. Disclosure Project Briefing Document, 492 pp. Available on CD from: The Disclosure Project, P.O. Box 2365, Charlottesville, VA 22902. Also available from: www.disclosureproject.org.
33. Lecture given at UCLA Engineering Department on March 23, 1993
34. Arp, H. 1998. Seeing Red: Redshifts, Cosmology and Academic Science. Montreal, Aperion. (p. 249).

Congress "The Time Machine"

Faraday Labs Ltd invites to participate in scientific congress devoted to experiments on changing of space-time properties. It is planned April 12, 2003, Moscow. Main topics of the congress are time and gravitation in the context of eatherodynamics, experiments and applied aspects of these technologies. The main report is "Method to Control Temporal Parameters of Physical Processes" by Alexander V. Frolov.

Organizing committee: Vadim A. Chernobrov (KOSMOPOISK research center) and Alexander V. Frolov (Faraday Labs Ltd). The registration fees are not required.

Please, contact us http://www.faraday.ru or **email** congress@faraday.ru **Phone/fax 7-812-380-3844**

Please send this pre-registration form by post: P.O. Box 37, St. Petersburg, Russia 193024 **or e-mail:** congress@faraday.ru

PRE-REGISTRATION FORM for participation in the congress "The Time Machine"

Last name:
First name:
Title/ Function:
Company/ Organization:
Address:
Postcode:
City:
Country:
Tel.:
Fax:
e-mail:

☐ I would like to submit an oral presentation (report). (Please, enclose one-page abstract).

☐ I intend to participate as a guest

☐ I'm interested in further information.

Date Signature

COMMERCIALISING the "SEARL EFFECT" for ENERGY and PROPULSION SYSTEMS

Review from web site http://www.sisrc.com/
Email address: admin@sisrc.com

The "Searl Effect", discovered by J.J.R. Searl, is a method of extracting energy. Some current expressions for the source of this energy being The Space Fabric, Quantum Space Field, and Zero Point Energy.

SISRC Ltd has been formed to develop and license Searl Effect Technology (SET) on a global basis.

THE COMPANY

SISRC Ltd is the company formed to administer the implementation of the Searl Effect Technology, (SET) invented by J. R. R. Searl. SISRC Ltd designs, develops and implements Searl Effect Technology as it is initiated in various applications and territories. SISRC Ltd is the administrative hub of the group and will continue to be based in the UK. SISRC Ltd will grant production and marketing licenses for Searl Effect Technology applications to different companies in specific territories. Currently proposed related companies include:

* SISRC -Germany, SISRC -Iberia, SISRC - Sweden, SISRC - Australia, SISRC New Zealand.
* SISRC -AV (Audio Visual) provides computer graphics presentations of the SET.

BACKGROUND

The Searl Effect Generator (SEG) technology, as applied to the commercial market, had been previously developed to the point where a few prototype SEG generators were made, and used for electricity generation and motion. Commercial interest at that time focused on the SEG's transport potential and, under commercial pressure to deliver a fully functioning system, the original generators were used and lost in a series of vehicular propulsion experiments and demonstrations. Funding was insufficient to continue with the manufacture of the required larger-scale pressurized cabin machines - resulting in the termination of the project at that time.

Although all the operating principles, precise proportions and weights of the required materials are known for three of the four required operating materials, the precise data of the original magnetic layer is uncertain. The objective of the current R&D programme is to re-establish the original magnetic layer using modern and more efficient materials.

Originally, the layered materials were constructed and magnetized by the now-defunct Midlands Electricity Board under the direction of John Searl (see colored photo of the experimental craft construction on the cover page).

Modern magnetic materials have advanced considerably, and old ones discontinued, so a series of tests need to be conducted to establish the optimum materials and processes. These tests need to comply with the working criteria required and must lead to a cost-effective manufacturing process.



Fig.1
Experimental ring and rollers

In recent times SISRC has been re-establishing the original research. Due to the very limited funding that has been available, only a partially functioning demonstration prototype of the SEG principles has been possible. This prototype consists of the innermost of the three composite rings required and several rollers.

We would like to hear from anyone who worked on or was involved with Searl Technology prior to 1983. Also anyone who has any old technical data, photographs or films relating to the technology. Such information could greatly assist this technology to reach the marketplace for the benefit of all and would be dealt with in the strictest of confidence.

TECHNICAL DESCRIPTION

Physically the Searl Effect Generator (SEG) consists of three concentric rings each made of a composite of four different materials which are also concentrically attached to each other. The three rings are fixed to a base. Surrounding each of the rings, and free to rotate around them, are rollers - typically 10 on the first ring, 25 on the next and 35 on the outer ring. Surrounding the rollers on the outer ring are coils which are connected in various configurations to supply either AC or DC current at a variety of voltages.

Multiple magnetic poles are imprinted on the rings and rollers to form frictionless magnetic bearings. These also arrange the static charge into opposing charge clusters which cause the rollers to rotate around the circumference of the ring (as shown in Fig. 2).

Some expressions currently in use to describe the source of the energy for the SEG are The Space Fabric, Quantum Energy field of Space or Zero Point Energy. This is an unlimited and constant source of energy which can be made to flow when the correctly proportioned masses concerned are stimulated by the correct frequencies creating an 'open system'.

The idea of utilising this source of energy is currently the subject of various devices and experiments such as the 'Lamb shift', 'Casimir Effect' and the work of the Russian Nobel Prize winner Ilya Prigogine. However these devices and experiments tend to only prove the existence of the energy and not a method to create a coherent, ordered flow to produce useful power.



Fig. 2

15 KWt Searl Effect Generator (SEG)

In contrast, John Searl has discovered that, in order to create a steady and stable flow, all the masses of the device (and the stimulating frequencies) must conform to precise values determined mathematically by the 'Law of the Squares'. A machine constructed to these principles produces a stable and useful power output.

DEFINITION OF A SURFACE OPERATING S.E.G. (J. Searl) 15.09.00

A Linear motor operating on a magnetic bearing with the characteristics of an auto-transformer. The S.E.G. is defined as a device, which is constructed from 2,124 component parts, which make up 3 plates and 66 roller sets (see figures on the cover page). 12 of the 2,124 components create the 3 plates, which act as reaction components. 2,112 components are employed to create 66 roller sets, which act as active components. Each roller set consists of 8 segments constructed from 32 components. Each segment cannot be less than 34 grams in weight, as the law of the squares defines that value as the lowest value suitable for the reasonable generation of electricity. Therefore the smallest roller set must weigh 272 grams, making a grand total of 2,244 grams per roller set for the smallest surface bound SEG.

Tolerance should be about 0.05 gram per roller set. The larger the error the greater is the loss of power within the unit. Therefore the total tolerance for the smallest SEG roller set must not be greater than 3.30 grams - above this factor the SEG will not function. **For the best results, the tolerance across the total 66 roller sets should not exceed 0.05 grams!**



Fig.3

The S.E.G. is a step up rotary transformer. In fact it's a 'three rotary transformers' operational system, within a unit. The inner transformer output is fed in to the input of the second plate which increases the output of the second unit, which output feeds as an input to the final unit, thereby increasing its finaloutput to a very high voltage. Therefore the S.E.G. is just a prime mover for the production of clean electrical energy. The output windings must be designed to step down this output to 240 volts at 15KWt's.

During 1968 it being upon this issue, as development progress both here and in the USA, new findings are being created, and updates will be added to this page, as they are certified. When the SEG rollers are brought into close proximity to the SEG Ring, the Searl Effect resonant magnetic field causes negative ions and electrons to be drawn into and accelerated through the machine. This process is assisted by the highly electron-attracting rare earth metal Neodymium.

The unique mechanical and material arrangement of the SEG pulses the neodymium to continually release and replace the surplus electrons to provide electrical or mechanical power, or both.



Fig.4

DEVELOPMENT

Prior to the production of complete 15KWt Searl Effect Generators (SEGs), a minimum of two demonstration Ring & Roller prototypes are to be produced.

The "Ring" is typical of the innermost of the three rings required to make a complete SEG. The 69-roller sets in a complete three ring SEG are identical. Six roller sets will be made for the prototype inner rings so that the Searl Effect can be demonstrated.

The production of a self-running Ring & Roller prototype will establish the precise sequence and parameters of electrical, magnetising and material processes required for the SEG and will demonstrate electrical power generation. An operating single inner ring with 1-8 rollers will also determine if a particular material will function correctly and at what level of power output.



Fig. 5
Demonstration ring and rollers

The five phases of the development programme that commenced in October 1999 have been completed and the rollers successfully magnetised with 'Searl Effect' magnetic fields. A sixth phase is now required to apply the technology developed in Phase five to the "Ring". This sixth Phase resulting in a demonstration Ring & Roller prototype has duration of 6 months.

NEWS REVIEW

Scientific Breakthrough Liberates Energy Users from Fossil Fuel Dependence

Information from
http://www.genesisworldenergy.org/genesis_world_energy.htm

Story originally published by Diana Echeverria, USA

Director of Public Relations
Guy Rome & Associates, Inc.
208-345-4143 208-602-0325 (cell)

Technology breakthrough harnesses energy from the molecular structure of water

BOISE, ID - Dec. 5, 2002 - Genesis World Energy, a privately funded consortium created by a group of military and space program research and development specialists, today unveiled a scientific breakthrough that allows consumers to easily access the energy contained within the hydrogen and oxygen molecular structure of ordinary water. This scientific breakthrough provides a limitless, low cost and environmentally clean source of energy that can be implemented with minimal cost and effort. The viability of using water as an energy source, previously a theoretical concept, is now a reality. "Water has always been the source of life on this planet, now it will also transform the way we create energy" said Charles Shaw, corporate counsel and spokesperson for Genesis World Energy. "The implications for worldwide energy generation and consumption are nothing less than staggering."

The Edison Device

The first application of this technology is represented in the "Edison Device", a self-contained, self-sustaining energy generation unit. Roughly the size of an outdoor air conditioning system, the power source can be quickly and easily installed in any home or business to provide virtually unlimited energy from any available water source. The Edison Device utilizes the existing electrical wiring and natural gas plumbing in a home or business to replace the energy provided by utility companies. The home version of the Edison Device produces approximately 30 kWtt of combined gas and electrical energy per day. By comparison, the typical home uses between five to six kilowatts per day. The commercial model is capable of producing 100 kilowatts of energy per day. The energy generation portion of the devices has no moving parts. In fact, the only "mechanical" aspects of the equipment are small circulation pumps and micro-valves, making the Edison Device both silent and virtually maintenance-free. A minimum amount of water is used over an estimated 20+ years of service life.

Interesting Publications of the Last Year

Discovery by a Group of Scientists Headed by Valerian Sobolev

Some time ago mass media announced that a sensational discovery was made by a group of Russian scientists headed by Valerian Sobolev. This discovery aroused ambiguous attitude of physic community. We have written about this fundamental and, to a certain extent, revolution discovery. Let us revise the fact that Sobolev claimed 7 scientific discoveries which were made, i.e. the process of depletion (a special electrochemical process), magnetic discharge, a new energy source, a method of low temperature plasma generation and superconductor. A laboratory system of the experimentally disclosed process as well as its industrial prototype is easy to be realized in practice for creation of new energy sources and wide-ranging production of ultrastrong materials. In many cases these materials can replace existing constructional materials.

The materials produced as a result of the process are multielement chemical compounds which are new states of matter. This new state of matter has **a time-changing magnetic field that can be EMF source in a coil of a generator.** Ordered structures of matters which are in the new modified state are nothing but a magnet charge. Materials containing the magnet charge and representing a continuous matters are **new energy sources.** Due to the new state matters become able to produce electric power as well as to generate low temperature plasma. It is easy to be realized in the process of common technological procedures. That promises designing of propulsors for "unsupported" transportation systems in near future.

Basing on realization of the disclosed process and using new materials the group of Russian Scientists headed by Sobolev together with American businessmen has created superfine and flexible glass for packing. The glass was called as "strong glass". It seems to demonstrate higher pressure stability than steel. A method of production of these materials was patented in 1999. In the patent the scientists of Valerian Sobolev's group are represented as authors of this new method, and the owner of the patent is Dynelec Corp (Columbus, Ohio, USA). You can read about the patent at the Web-site of http://patft.uspto.gov/netahtml/srchnum.htm (patent #5,964,913, October 12, 1999).

Sobolev's group has appeal to the Russian government for sponsorship; however only foreign investors have provided funds for new energy sources developing. According to Russian Information Agency "News", Sobolev's group has signed a $168 million contract with one of Canadian companies for developing industrial production of energy sources. Manufacturing of such energy sources **can change energy supply system all over the world**. According to the contract the Canadian company is going to finance building of at least two plants. One of the plants is going to be built in Russia, and the other one is planning to be established in Canada. Each plant is supposed to produce 70 thousand of the self-running energy sources a year. Power output of the sources will come to 3-10 kWt. In other words, in the nearest future every person will be able to buy such an energy source and to apply it in household.

Single-Wire Electric Power System

(see photo on the cover page)

Experimental Results of Russian Scientists

Scientists of the All-Russia scientific research institute of electrification of agriculture (VIESH) academician D.S. Strebkov, engineer S.V. Avramenko, dr., A.I. Nekrasov, post-graduate student O.A. Roshchin developed a new method and the equipment for transmission of electric energy on a single-wire line using resonant idle operation mode and reactive capacitive currents for transmission of active electric power. Tesla transformers and frequency converter were used at the experiments.

First there was created the experimental sample of single-wire electric power system (SWEPS) with **10 kW** electric capacity and 3000 V voltage. As a result, obtained SWEPS electric parameters a hundred times exceeded parameters of a usual two-wire or three-wire alternative and direct current line.

In the end of 2002 there was made an attempt to increase transmitted capacity by using of more powerful condensers, which were installed in resonant circuit. There was developed the electric technique of **20kW** single-wire electric power system (SWEPS) with two Tesla transformers. As a result parameters of a low-voltage winding of the step-down transformer were changed. They **exceeded parameters of a usual two-phase or three-phase ac line or dc line in two hundred times.** At room temperature effective specific transmitted electric power was 4 MW/mm^2 and specific current density was 600 A/mm^2. These parameters could be achieved for existing methods of electric energy only at use of special materials in a mode of low temperature superconductivity. The measurements which were made at wire with diameter of 1mm, 100 microns and 80 microns, demonstrated that parameters did not depend on diameter of a wire. There was also experimentally confirmed the property of a single-wire line to transfer active power without essential losses on line resistance. Irradiation losses at low frequency 3,4 kHz were small. In single-wire power system the 80 microns wire plays a role of directing system for an electromagnetic energy flow, which runs from the generator to the load.

"Lifter" Project

We present update information on the experiments with Lifters or asymmetrical capacitors, which use High Voltage to produce a thrust. ***By Jean-Louis Naudin it was demonstrated with "****Maximus****" experiment, that a Lifter can be scaled up and also that such a device is able to lift up to 60 g of payload (total weight: 194 g). According to Naudin, it is now possible to build a craft which will use the Biefeld-Brown effect to fly silently and without moving parts only powered by electrical energy.*** *It was also declared that on January 8th, 2003, there was successfully done two historical flights with a mouse as a test pilot of the Lifter "Maximus"* ***(propellantless electrokinetic craft)****. Below there is an analysis of electrogravitation experiments made by Jean-Louis Naudin and Tim Ventura. (See color photos on the cover page).*

Review of Electrogravitation Experiments made by Jean-Louis Naudin and Tim Ventura

Tim Ventura

Tim Ventura Website: http://www.americanantigravity.com
Email: TVentura@seattle.telecomsys.com, tventura6@atbi.com

There is a spreadsheet containing a jpeg-snapshot of data that I have assembled based upon Jean-Louis Naudin's published results (JLN Labs Website: http://jnaudin.free.fr. and http://www.jlnlabs.org). In the graphs that I've created, it seems to indicate that current plays more of a role in propulsion than voltage does — i.e.: for a given amount of power in watts, raising the current and decreasing the voltage seems to create a higher level of thrust.

In light of this, I have been increasing the thrust of my own Lifters by creating an electrical-bypass of the "load-resistor" on my power-supply's high-voltage output. This has an interesting result:

I use a current-driven power-supply, which means that if no load is connected to it the voltage will build up on the high-voltage output until arcing occurs. In my case the voltage will build up to around 65kV, at which point the power-supply will automatically shut down. Conversely, if a very light load (such as a short circuit) occurs, the opposite effect happens and the power-supply will deliver much higher current at a much lower voltage until the supply is overdrawn and once again shuts down.

Normally the output load-resistor constrains the current, and in doing so it maintains the voltage on the high-voltage output at the nominal 50kV output level. However, bypassing the output load-resistor allows the power-supply to deliver voltage and current that are based almost entirely on the type of load connected to it.

When I connect a normal Lifter to the bypassed power-supply, the voltage will build across the air-gap until ions begin to flow in a conduction-current across the air-gap. Although this begins to happen at approximately 15kV, it seems to have some type of "peak efficiency' at approximately 22.5 kV. The amount of current climbs to approximately 11mA at this voltage.

This method of experimental setup seems to allow the Lifter to "find its own sweet-spot" for operation, instead of using the output-resistor to "force" a specific voltage on it for operation. This appears to maximize the thrust output during operation.

Lifter Efficiency Spreadsheet

Description	Lift capacity (grams)	Length (cm)	Efficiency (g/m)	Lifter Weight (grams)	Voltage (kilovolts)	Corona Air-Gap (centimeters)	Current (mA)	Power (watts)
Lifter 1	3.3	60	5.5	2.3	41.9	3	0.57	23.9
Lifter 2	9.6	180	5.3	6.6	43.35	3	1.12	48.5
Lifter 3	20	360	5.6	16	27.5	3	2.53	69.5
Lifter 4	36	720	5	32	44	3	2.01	132.9
3-Stage Lifter 3	54	1080	5	24	30	4.5	8.06	240
Coliseum Lifter	90	2160	4.16	50	31.769	4.5	8.06	254.15

New Electric Fire Technology

Valery D. Dudyshev

Doctor of Technical Science, Professor,
Corresponding Member of Russian Ecological Academy
ecolog@samaramail.ru
http://www.intrasoft.ru/nizot

Abstract

The article proves importance and prospects of development of combustion technologies. In particular there is considered application of a new electric fire technology for environmentally appropriate combustion of any matters and gases. The technology uses electric fields as combustion catalyst. There is observed application of technology in heat-and-power engineering, transport heat engines, disposal units etc. [1, 2]. It is demonstrated that the new technology allows intensify combustion processes and increase their controllability (i.e. the control of temperature, gases pressure, gradient of heat conductivity, and so on). There is made a conclusion about availability of the technology to solve critical energetic and ecological problems of the civilization.

We hope that this article will excite interest of a wide circle of readers, i.e. of professionals in the area of combustion and heat technologies, physicists, ecologists, and those people who are interested in new scientific ideas.

Global Ecological Problems are the Problems of Ineffective Combustion of Hydrocarbon Fuel

The ecological problems become more and more serious and threaten to grow into world ecological catastrophe. The main cause of the atmosphere pollution in megapolises is imperfection of combustion technologies (of heat-and-power engineering, heat machines, transport engines, waste combustion…). It has been proved that their share of pollution of the planet atmosphere comes to 70-80%. The combustion technologies mean any technologies of combustion of fuel, matters and gases. The combustion technologies are the most popular technologies in the world. The modern civilization without the combustion technologies is impossible. There are many industries, which apply these technologies, such as heat-and-power engineering, transport, metallurgy, food industry, oil-and-gas refining industry, chemical industry, waste combustion neutralization.

Therefore the global ecological problems will not be solved until the mankind develops the combustion technologies. The article describes and discloses the essence of the new technology of ecologically appropriate and effective combustion of fuel and wastes of any type.

Why is it difficult for ecologists to conserve nature?

Modern methods and technology used for solving of the ecological problems consist in **analysis** of extent and sources of the environment pollution (ecological monitoring), and, moreover, in **refinement of atmosphere, water and soil, which are used in different technologies or have been polluted due to the imperfection of the technologies** (it is refinement from such toxic components as drinking and run-off water, exhaust and waste gases etc.).

Unfortunately, methods of measuring of the huge spectrum of toxic matters, which are thrown into the atmosphere at matters combustion, as well as the methods of their utilization are impartially difficult, expensive and imperfect. Even using of an ideal technics for measuring of the atmosphere pollution is not effective since it is a struggle with **consequences** of the combustion and other technologies imperfection but not with **causes** of the atmosphere pollution.

Ecological and energetic effectiveness of the known combustion technologies

It is known that real effectiveness of transformation of chemical energy of fuel in the combustion process is low. For example, in heat engines it comes to 25%, effectiveness of transformation of heat energy into electric energy in thermoelectric power stations does not exceed 40%. If energy consumptions of mining, processing and delivery of the fuel to consumers are taken into account then the summary efficiency of the existent combustion technologies (of heat machines and devices) comes to no more than 10 – 15%! It means that more than the half of chemical energy of the fuel is transformed into heat and different toxic matters and waste gases, which pollute the planet atmosphere. They cause acid precipitation, a global “greenhouse” effect, which threaten to cause the climate warming, the world flood, and final poisoning of the living nature. Thus the share of imperfect power engineering in the nature pollution comes to 70 – 80%! How is it possible to cleanse the planet atmosphere, especially the environment of world megapolises, in the situation when the amount of toxic matters produced by transport and industries is comparable with the amount of rest pure air?

Until the mankind learns burn matters and gases by effective and ecologically appropriate way the planet atmosphere will remain polluted and in near future it can become uninhabitable. Thus we will not solve the ecological problems until we gain the understanding of the combustion processes and processes of combustion transformation of matter chemical energy into heat energy, and then into other useful types of energy (i.e. electric energy, mechanical energy, light energy).

Physical Essence and Problem of Classical Combustion of Matters

Combustion is one of the most difficult phenomena, which are known by the humankind. From the scientific point this phenomenon is a chain reaction of sequential fragmentation of fuel particles into smaller charged radicals; it is physical chemical processes of transformation of chemical energy of intermolecular connections as well as combustion also includes physical processes of transformation of energy into heat and light on molecular and atomic levels. Many other processes, which proceed simultaneously, are involved.

From school years we know that combustion is a process of interaction of fuel with an oxidant that is accompanied by heat and light energy generation. In higher school the words of “as well as by cryptic energy of chemical connection of waste gases” are added to the school definition. The combustion processes are studied and improved by scientists and experts of different areas (chemists, physicists, heat-and-power engineering specialists, thermalphysicists etc.). There are known fundamental investigations of combustion chain reactions made by such Russian scientists as N.N. Semenov, Ya.B. Zeldovich and their followers.

Until now intensiveness of fuel combustion is increased by air blowing into the combustion zone that increases the amount of waste toxic gases thrown into the atmosphere. **Let us arouse several questions, which seem naive at first sight. Why is an oxidant (air or oxygen) needed for matter combustion? Is it possible to do it without any oxidant?** How does the combustion process begin and proceed? There are a lot of vague questions in physics of combustion. For example, how can the temperature and the intensiveness of the combustion be regulated? Can the heat conductivity of the flame be controlled? How can heat motion of particles be regulated in the flame and in the waste gases, and what can it cause? There is another problem of combustion. It is the very hydrocarbon fuels, which are applied at modern heat processes. The great Russian scientist, D.I. Mendeleev stated that to use oil is the same thing as to stoke a stove with banknotes.

Since the hydrocarbon fuels are complicated chemical matters and the combustion processes are imperfect then in the process of their combustion a great amount of different by-product matters and toxic gases are produced. They waste unused self-energy of fuel into the atmosphere and pollute our planet.

Physical essence of the new electric combustion technology

How is it possible to burn the hydrocarbon fuel by environmentally appropriate way? How can this environmentally appropriate technology be realized in practice? A brief answer is following**: it is necessary to make such conditions of combustion of organic fuel, and to introduce such a combustion catalyst that the energy of intermolecular and intramolecular connections of the organic fuel becomes absolutely free. At that the chemical energy can be transformed into energy of electromagnetic radiation, for example, into light energy and heat energy without generation of by-product polluting matters and gases. Then a working body (for example, water) is effectively heated by this directed concentrated electromagnetic radiation. In this process effects of electromagnetic waves reflection and concentration are used, or the electromagnetic radiation is directly transformed into electric energy.** In this case there is a new opportunity to regulate flame temperature and to extremely decrease quantity of the oxidant, i.e. to create organics combustion with minimal quantity of waste gases.

Is it principally possible to burn organic matters and gases without the atmosphere pollution using electric field as a catalyst? It is possible if parameters of this field are correctly chosen. More precisely it is possible if huge Coulomb forces of the electric field are correctly regulated by interaction of electrically charged particles of the fuel and the oxidant with force lines of the electric field.

One variant of an experimental device is represented in Fig. 1.

Devices for approbation of the new electric combustion technology



Fig.1 a
Plan of the experimental device



Fig. 1 b
Photo of the experimental system

A structure chart of the experimental device, which was designed to investigate the new electric combustion technology, is demonstrated in Fig.1a. The device contains a body (1) equipped with flat electrodes, which are insulated from the body (2), (they can be placed in either horizontal flat or vertical flat). The electrodes (2) are located on opposite inner walls of a combustion chamber (3). The device is equipped with a mixer (4) with a device for supplying of blended fuel to the zone of combustion. At the same time the device (5) is used for electrical combustion of the blend. The described device is equipped with an air track (6), which contains an oxidant activator (7) joined with a regulator (8) by a control circuit and with the mixer (4) by an air pipe (9). The regulator (8) serves for regulation of the oxidant activation extent. At the end of the air pipe it is possible to place a vortex device (it is not shown in the figure). Also the device is equipped with a fuel track (10) containing a fuel activator (11) and a regulator (12) of the activator and consumption of fuel. The block (11) is joined with the mixer (4) by a fuel pipe. The device is equipped with an electric combustion activator (14) containing a high-voltage transformer (15) of intensity and frequency joined to its regulator (16) by a control circuit. An electric outlet of the block (15) is joined to one of the electrodes (2), and the second outlet is safely electrically grounded by a grounding mat (17). The high-voltage wire of the outlet of the block (15) is connected with the electrode (2) through a bushing insulator (it is not demonstrated in Fig.1a). The device is equipped with a gas toxicity calculator (18) joined to the inlet of a mode optimizer (19), which is a control system for interacted regulating of all the parameters of combustion. For that the outlet of the mode optimizer (19) is joined to the inlets of control of the regulators (8), (12), (16).

The device operates in the following way. At first an activated oxidant of O1 is applied through the air track (6), activator (7) and air pipe (9) to the mixer (4). Then an activated fuel of F1 is applied through the fuel track (10) and the activator (11) to the same mixer (4). A blended fuel is prepared in the mixer (4) and then is atomized and combusted by a sparkle of the block (5). In the combustion chamber (3) flame and waste gases are processed by strong alternating electric field, which is generated by the block (14) in a gap between the electrodes (2). In the process of combustion waste gases toxicity is measured by the special toxicity sensor (18). Depending on current toxicity the parameters of flame combustion are regulated by the mode optimizer (19). More precisely the oxidant consumption and the extent of its activation are changed by the regulator (6), the fuel consumption and the extent of its activation are changed by the regulator (12), the intensity and frequency of the alternating electric field generated by the block (14) in the combustion chamber (3) is changed by the regulator (16). Let us note that the electric field in the combustion chamber (3), viz in the gap between the electrodes (2), catalytically influences on both the flame and the waste gases. The essence of the process lies in the fact that the processes of fragmentation and oxidation of fuel radicals and of toxic oxide molecules are accelerated. Intensiveness of combustion and of toxic gases refinement increases as well as the intensity of this field and its frequency do. As a result of the interconnected regulation of all the listed parameters fuel of any kind can be fully, intensively, “cleanly” combusted.

In Fig.1b there is a photo of the operating experimental device designed to investigate the processes of influence of electric field on the process of matters combustion and of cleaning of waste gases. The photo represents following things.

1. In the left side there is a furnace with a high-voltage electrode in a higher part of its body.
2. In the centre there is a vertical column of the electric combustion cleaning (after-burning) of toxic gases in the electric field; on the top of the column a high-voltage electrode can be seen. Gas pipes designed for toxic gases supply–withdrawal are connected with the column and located to the right and to the left from it.
3. A regulable blower is represented in the upper right side of the picture. It is designed for toxic gases withdrawal and connected with the gas pipe by the column.
4. At the foot of the picture there is a regulable high-voltage tension source (the electric field source), which is connected with the furnace and the column of toxic gases cleaning by high-voltage wires.

It is experimentally proved that combination of two stages of the combustion activation (i.e. in the furnace and the column) ensures ideal cleaning of toxic gases at combustion of any toxic matters.

Some Results of Experiments

Our experiments and investigations of many-sided influence of electric and high-voltage electromagnetic fields on the combustion process have proved that such practically ideal condition of fuel and matters combustion is possible to be realized in practice [1].

Low-powered static and alternating electric fields (i.e. the fields of constant sign and of variable sign) of more than 1kV/cm intensity were used as combustion catalysts as well as high-frequency electromagnetic fields of low power with some frequency of oscillations of molecules in the flame (flame power is 0.1 – 1% of heat power of the flame of the combusted organic fuel).

Peculiarities of Oxidants Application in the New Technology

It is known from the thermodynamics and combustion theory that optimal ratio of the oxidant mass, for example air, and the fuel is approximately 1:16 in an average combustion process. In our experiments with the electro-field catalyst the ecologically appropriate combustion of the hydrocarbon fuel (mazut, straw oil) was achieved at oxidant deficiency (for example, at the ratio of oxidant mass and the fuel of 1:1). For experts it means that there is a real possibility for 10 – 15 times decrease of amount of waste gases of any heat machines and to while their former power is the same. As the experiments demonstrate carbon and hydrocarbon are absolutely removed from the waste gases. In the experiments oxides of hydrogen and nitrogen were 4 – 8 times decreased and flame existence was 5 – 10 times increased.

The issues of the experiments prove the hypothesis about possibility of effective environmentally appropriate combustion as a process of direct transformation of chemical energy of organic fuel into electromagnetic radiation energy of the flame (including heat and optic diapasons). The transformation is accompanied by removal of polluting toxic components from the waste gases that occurs due to many times intensification of the combustion process under action of electromagnetic catalysts.

Operations of regulable activation of fuel oxidants (simultaneous or separate), which are introduced into the combustion technology, ensure additional improving of the combustion process. Especially it occurs at heavy oil fuel combustion and water-fuel emulsion combustion that was experimentally tested by us. The process becomes especially effective if the flame of the combusted activated blended fuel is additionally processed by alternating electric field. Due to introduction of the operation of all the combustion parameters regulation (of consumption of fuel, oxidant, of their activation extent, and of their combustion intensiveness extent), according to the information of the waste gases toxicity, it is possible to achieve effective combustion of fuel and waste products of practically all kinds.

Our experiments demonstrate that combination of the very flame procession with procession of the waste gases and air (i.e. an oxidant) by electric field is very effective for the waste gases cleaning. The essence of this additional cleaning of the waste gases lies in fragmentation of carbon particles and exhaust opacity by electric forces of an alternating field as well as in after-oxidation of some toxic oxides in the medium of an ozonized oxidant. Energy consumption for activation of the flame combustion by strong electric fields is small and does not exceed 1–3% of heat energy of the flame. Advantage of this invention is universality of the application for combustion of any inflammables. It is possible due to widening of the diapason of the electric field parameters regulation (of intensity and frequency), especially in the mode of their interconnected regulation.

The essence of catalytic action of the alternating electric field on the flame combustion process consists in effective breaking of dipole radicals of fuel by an activated (dipole) oxidant. Moreover, the essence lies in better mixing of layers of combusting flame with the oxidant that occurs due to removal of a doubled electric layer from the limit line of the flame. Thus this technical solution allows achieve new positive effects due to its significant peculiarities, i.e. extending of application area of the known electric combustion method over the combustion process of any inflammables as well as it allows significantly increase controllability of the flame combustion process.

Let us note that in the experiments on the combustion of organic fuel in strong electric fields the regulation of the flame temperature and of its existence was achieved at unchanged consumption of fuel and of oxidant. That was achieved by changing of the parameters of the combustion electric-field catalyst (intensity and frequency) of a longitudinal electric (electromagnetic) field. Rotation and stabilization of the flame was achieved by a rotating transversal electric field. Changing of the flame height was realized by the longitudinal electric field.

The investigation, which has been performed by us, proves that directly acting on the flame the very electric field which directly influences on the flame and emission of electrons flow (ideal type of oxidation) into the flame can most effectively intensify the combustion process and make it harmless for the humankind and for the environment!

It has already been experimentally proved that energy consumption required for generation and regulation of this electric field and of the electrons flow for intensification and environmental appropriateness of the combustion is quite small relatively the combustion energy and comes to fractions of a percent of the flame energy. Thus our experiments prove that the best **"oxidants" and combustion catalysts are** not superfluous air but **the electron and the electric field!**

Regulation of Heat Conductance of the Flame and the Heat Flow

As our experiments have demonstrated, the electric field can act as an effective combustion catalyst as well as a regulator of its intensiveness; moreover, it can control even a vector of heat conductance. It is proved by the experiments that the parameters of this field can be regulated as well as temperature of the flame and gradient of the flame heat conductance. Interesting experimental results were obtained measuring full heat of combustion of the same quantity of fuel at the usual method of fuel combustion and at the method, which uses combustion electric catalysts, even in the case of oxidant deficiency. In the last case the energy of fuel combustion almost 1.5 times increases that can be explained by fuller transformation of fuel chemical energy into electromagnetic radiation. At the usual combustion methods the chemical energy of the organic fuel was not completely used and remained as a cryptic summary chemical energy of intermolecular connections of many toxic waste gases, which were exhausted into the atmosphere by heat devices. Basing on the performed experiments it may be supposed that, evidently, specific heats of matters are 20-50% higher at this method than at their usual combustion method. The essence of the new electric combustion technologies consists in this new physics of combustion.

The author has already got patents for invention of Russian Federation [3 – 12] for the methods of regulation and intensification of matters combustion processes.

Some peculiarities of atomization, inflammation and combustion of organic fuel in electric fields

We have not discussed all the potential capabilities and advantages of the new electric combustion technology for different areas of technics. Let us demonstrate them in more details.

One of characters of the new electric combustion technology is **effects of oxidant ozonization, of electrostatic atomization and electrostatic injection of electrically charged particles of fuel and the oxidant that is followed by generation of the finest aerofuel opacity on a molecular level in a combustion chamber**. Naturally, such fine atomization of the fuel causes its easier evaporation, inflammation and combustion especially in the medium of the ozonized oxidant. **The mechanism of fuel electrostatic fragmentation is physically explained by Coulomb interaction of repulsion from each other of electrically likely charged fuel drops (particles) that is accompanied by their progressing fragmentation and corresponding decrease of their mass and electric charge**. As the experiments have shown the extent of the fuel drops (particles) fragmentation depends on initial electric potential of fuel charging and initial size of injected fuel drops (particles), which for their part depend on configuration and size of a fuel-injection nozzle as well as on pressure occurring in a fuel line of the heat machine.

Generated by dipolar high-voltage potentials catalyzing electric field can be introduced into the atomization zone or (and) the combustion zone of the combustion chamber of an engine. Its Coulomb forces accelerate motion of electrically charged particles of fuel and oxidant to an opposite electric potential, which is connected with, for example, a piston of an engine. Thus electric field acts as an electrostatic pump that allows decrease pressure in a fuel line as well as allows practically ideally atomize the fuel and mix it with the oxidant. Moreover, it lets simplify and improve the systems of injection and inflammation of the blended fuel in heat machines and devices, for example, in internal combustion engines or in boiler plants. Their application can cause additional improving of energetic and ecological characters of the combustion technologies. According to our information, such high-performance fuel-injection nozzles have yet been unknown in technics therefore they have not been applied in heat machines (injector internal combustion engine).

Is it possible to combust water?
Water as a fuel!

More amazing experimental results were obtained at 40-80% dilution (emulsification) of liquid organic **fuel**, for example diesel oil, with **habitual water**. Summary energy as heat and light, which is generated in the process of such blend combustion, was not practically changed that can be explained by liberation of energy of chemical connections of water as well as of fuel. In the process of the experiments on combustion of the emulsion at first **it was transformed into the finest water vapor on the molecular level by means of capillary electroosmosis and of electrostatic atomization. Then dipolar water molecules, which had been electrified by field, were fragmented into hydrogen and oxygen, and then the hydrogen was effectively combusted in the medium of the ozonized oxygen.** Let us note that at this mechanism of water "evaporation" and of following splitting of water molecules into hydrogen and oxygen the electric field expends energy, and heat of organic fuel combustion just accelerates (catalyze) this process.

Editor: It is necessary to note that electric field can not expend energy. If there are no conduction currents then the field source does not decrease difference of potentials. Hence it can be concluded that effectiveness of such power systems is possible to be UNRESTRICTEDLY HIGH. The author writes about it below as about an "incomprehensible phenomenon".

The most amazing and incomprehensible fact is that the electric field transforms water into "vapor" and breaks the water molecule into hydrogen and oxygen practically **without any expenditure at minimum of energy consumption**. Electric power of the intensity high-voltage transformer, which is necessary for strong field generation, lies in the interval from several watts to tens of watts. As the experiments have demonstrated electric consumption of the high-voltage source practically is not changed at correct shunting of the flame by the electric field (i.e. through an air gap). Current consumption practically did not increase depending on mode of fuel atomization and its combustion (of flame height, of combustion intensiveness...).

There are only two conditions of effective work of static electric field as an electrostatic pump-atomizer of fuel and as a catalyst of blended fuel combustion. The first one is intensity of the field in the zone of fuel atomization and in the zone of flame combustion. The second one is enough emission of electrons into the blended fuel flow. In this mode Coulomb forces make work of electrostatic pressure generation and of electrostatic fragmentation of particles and molecules of fuel and water. The forces repulse likely charged drops of water. Heat motion of fuel radicals, which are combusted and fragmentized in the flame, impedes their chemical recompounding into water molecules in the zone of combustion. Moreover, it causes proceeding of a very physical chain reaction of hydrogen combustion in the flame.

Therefore additional light and heat energy, which is generated in the flame by combustion of hydrogen generated from water molecules that occurs in the ozonized oxygen, does not decrease summary energy of combustion of blend of fuel with water but increases it.

Thus using of electric and electromagnetic fields as the strongest catalysts of combustion of organic fuels and any matters clears great **prospects** of combustion technologies improving. Moreover it allows create ecologically appropriate heat machines and devices and 20-50% increase their effectiveness due to fuller transformation of chemical energy of inflammables into heat or light energy.

Ways of radical improvement of heat machines or about a new mechanism of transformation of heat energy into mechanical energy and into kinetic one

For clear realization of causes of extremely low output of modern heat machines that has generally lead the civilization to the ecological catastrophe it is necessary to understand their common principle of operation as well as a cause of heat energy non-effective using in them.

A mechanism of transformation of heat energy, which is generated by fuel combustion, is the same for all known heat machines. It consists in generation and transformation of superfluous pressure of a heated working body (i.e. gas, vapor etc.) into kinetic energy of a working element of the heat machine (i.e. a piston of an internal combustion engine, a turbine of an aviation engine, a reaction jet flowing out a rocket nozzle etc.) in special chambers of the machines.

It is also known that the higher the temperature of the heated working body, for example of a gas, the higher initial pressure in the working chamber of a heat machine. **Why output of heat machines is so low?** Any expert of thermal physics, thermodynamics, and heat machines can answer that efficiency (output) of heat energy transformation into mechanical one is defined by the second law of thermodynamics and is clearly illustrated by Carno heat cycle. According to these postulates, **output** of an ideal heat engine does not depend on a working matter and on the engine construction but is defined by temperatures of the working body in the starting point and in the final point of the cycle, i.e. by the temperatures of the heater and of the refrigerator of the **heat machine**. Real output of the heat machines is limited by heat stability of materials and by imperfection of engine constructions.

Nevertheless known thermodynamic processes and lows of heat motion of particles and molecules are significantly changed in strong electric fields and demonstrate new prospects for improving of heat machines.

A solution of the problem can be briefly formulated as: to increase output of heat machines it is necessary to use a new mechanism of redistribution of heat energy into energy of directed pressure of a compressed working body (i.e. gas, vapor, etc.) on the working element of the heat machine. At the minimal pressure it should be redistributed on sidewalls of the working chamber.

Can it be realized in practice? On the face of it the technical solution is unrealizable nevertheless it exists. It is possible to redistribute and to regulate heat motion (pressure) of heated gas inside a closed reservoir and, hence, its temperature in a certain direction. To achieve this aim **it is necessary to introduce static electric field into the combustion chamber of a heat machine and to orient heat motion of electrically charged and dipolar molecules of expanding working bodies (i.e. gas, vapor) along force lines of the electric field by electric Coulomb forces**. Something similar occurs, for example, in liquid crystal cells of electronic timer, in Kerr cells (electric optic effect) at periodical application of electric field to them that causes dipolar molecules turn along a field vector as well as change of light penetrability of these matters.

There is a difference between this known in electrooptics phenomenon and our case. The difference lies in the fact that polarized gas molecules remain movable along force lines of the electric field in contrast to liquid crystals, which do not. This fact causes redistribution of parameters of heat energy (i.e. pressure, temperature, and heat penetrability) of dipolar molecules of heated gas just along force lines of the field. The more the intensity of the field at the initial temperature of the working body is the more the difference of pressures on the sidewalls of the chamber and on the working element, for example, on an engine piston.

Heat motion of polarized particles of heated gas can be decelerated by combination of three electric fields of constant sign in accordance with all three coordinate axes; hence it is possible to significantly and quickly decrease temperature and pressure of the gas. In this case the heat energy of the heated gas makes jump transformation into electromagnetic radiation.

Editor: Historically this method, i.e. plasma retention by electric field, was proposed by Oleg Lavrentiev in 1948. He had 7-grade education and served as a sergeant in Armed Forces in Sakhalin. After he sent Stalin a letter containing a phrase, as "I know a secret of hydrogen bomb creation" he was invited to Moscow to set his ideas out to academicians. His ideas were not lost nevertheless the scheme of plasma electrostatic retention was not applied ("Expert" magazine #23, 18 of July of 2001). In 1950 Sakharov and Tamm proposed a scheme of a toroidal magnetic thermonuclear reactor which has been developed until now. Why is it so? It is difficult, expansive and practically unreal…

Thus introduction of strong electric fields into heat machines allows significantly increase effectiveness of transformation of heat energy of a working body into mechanical and kinetic energy of working elements of the machines by means of directed regulation of temperature and pressure of heated gas, for example, in the starting point and in the final point of a working stroke of a piston. In other words it allows increase output of the machines.

APPLICATION AREA OF NEW ELECTRIC COMBUSTION TECHNOLOGY

Practical application of the new combustion and thermal technologies

The new technology is universal and applicable in practically all spheres of technics. Therefore we believe that further development and application of this new technology of fuel and waste products combustion is very important for radical improving of all the heat machines and of all thermal technologies. As the civilization uses hydrocarbon fuel and matters in its life circle then just this new technology can solve critical ecological and energetic problems of the civilization.

It is impossible to view in details all proposed perspective technical solutions based on this technology [1-25] within one article. Therefore we give only one striking example.

Environmentally appropriate engine for motor transport

Since the transport, which uses thermal internal combustion engine (ICE), is most harmful for the environment then let us discuss ways of their ecological and energy improving. Several years ago the author patented "method of intensification of ICE operation" [7]. The essence of the invention consists in introduction of controllable electric field into combustion chambers during the whole operation period of an engine by special monoelectrode spark-plugs (Fig.2).



Fig.2a

Plan of an environmentally appropriate ICE (for transport)

1. – combustion chamber;
2. – piston, 2a –heat-resistant surface of the piston (zone of electric-spark discharge)
3. – admission valve (its canal is not indicated)
4. – exhaust valve (its canal is not indicated)
5. – combined mono-electrode spark-plug; 5a – fuel nozzle with hollow central electrode and end disk electrode
6. – electric insulator of the spark-plug – fuel nozzle
7. – fuel pump (for example, an electrostatic one)
8. – high-voltage regulable transformer (electric field source)
9. – force block of tension high-voltage transformer (=12V/25kV)
10. – system of regulation of electric field source (9)
11. – board current network =12V (SB is a storage battery of an automobile).

This structure chart briefly demonstrates basic components of a new ICE, where there is directed pressure of gases on a piston. In particular, many inventions of the author are realized in practice here, i.e. semi-digital spark-plug, electrostatic fuel nozzle (5), electrostatic fuel pump (7). A new mode of volume inflammation of blended fuel has been realized in practice, i.e. "a spark coming from a disk electrode (5-a) to a piston (2-a)". Since it is possible to regulate the electric field intensity generated by a high-voltage source of tension then an advance angle of blended fuel inflammation can be regulated, gases pressure on the piston at explosion stroke of ICE operation can be regulated as well.



Fig.2b
Photo of a simplified construction of the new ICE

Fig.2b demonstrates simplified three-dimensional construction of the proposed energetically and ecologically perfect ICE. There are observable elements such as a combustion chamber, a piston, valves, a monoelectrode spark-plug, and an electrostatic fuel nozzle (in the centre on top), which is connected with the spark-plug. In the centre of the combustion chamber it can be seen volume inflammation of the blended fuel at spark appearance from end electrode to the piston.

As a result a summary positive effect of ecological, construction and energetic improving of ICE is achieved, i.e. effective cleaning of exhausted gases directly in the combustion chambers of the engine, significant simplification and perfection of a fuel injection system, improvement of system of distribution and electric inflammation of the blended fuel. In this engine a distributor (as well as its analogues) is removed at all since sparking and intensive inflammation of the blended fuel automatically appears between central electrode of the spark-plug and the piston which comes to the upper "dead" point. The central electrode of the spark-plug is constantly under high tension. The advance angle of ignition is regulated by change of the electric field intensity. Powerful multipoint ignition causes simultaneous intensive inflammation of the blended fuel that occurs throughout the whole chamber. The electric field as a powerful combustion catalyst intensifies the process of the blend combustion at the explosion stroke of the engine and at after-burning of waste gases directly in the combustion chambers at the following output stroke of the engine operation. Directed along the axis of the piston in the combustion chambers this electric field serves as a transformer of gases heat energy into mechanical energy of the thermal engine pistons. That is caused by the fact that the field orients heat motion of the expanding gases along the axis of the pistons in combustion chambers of the engine at explosion stroke of ICE just. It causes redistribution of heat energy and increase of the gases pressure on the very pistons that significantly improves effectiveness of transformation of heat energy of the fuel combustion into mechanical energy of the piston motion (theoretically the improvement is by two-three times), i.e. it two-three times increases output of a classical thermal engine making it come to 70-80%.

The electric field, which is introduced into the combustion chambers of an internal combustion engine, ensures significant economy of fuel (up to 30-40%) at saving of its working characteristics. It occurs due to fog electrostatic spray of fuel and to the fuel electrization as well as due to oxide ozonization. Moreover it occurs as a result of deep after-burning of hydrocarbon components of fuel, combusting blend and waste exhaust gases. This method allows effectively regulate temperature of the blend combustion in the chambers while required compression in cylinders is the same, for example, to minimize nitric oxide generation in the exhaust gases. As a result there is no necessity in external devices for cleaning of exhaust gases of internal combustion engines; ecological appropriateness improvement can be simultaneously achieved. Additional aerosol hydro-alkaline processing of these gases can allow totally clean **exhaust gases** of the transport, which operates on thermal engines.

Workability of such an environmentally appropriate engine in two-stroke and four-stroke variants is experimentally demonstrated. There are also experimentally shown decrease of all toxic components in exhaust gases, 20-30% increase of useful power of the engine, and simultaneous decrease of fuel consumption. Thus practical application of the new electric combustion technology can exert revolutionary influence upon propulsion engineering development and upon increasing of ecological compatibility and effectiveness of the transport, which operates on thermal engines.

Diagram of operations of technology of effective using of refinery wastes in heat-and-power engineering


Refinery wastes
1
2
Combined activation of liquid oil-alimes (in electric and magnetic fields)
3
4
5
Heating and evaporating of water
Furnace
Waste gases
Special fuel nozzle
water
1. Mixing of oil products combustion with water
2. Combined activation of oil emulsions
3. Electrostatic atomization of water-fuel blend
4. Electric and waste gases cleaning

Fig.3

Technology of environmentally appropriate combustion of refinery wastes as fuel for boiler plants

The author has patented other technical solutions of improvement of different devices, which are based on these technologies. These solutions concerning boiler plants, gas turbine engines and jet engines and many other heat machines and devices allow increase their effectiveness and simultaneously significantly improve their ecological factors. As an example of application of this technology in heat-and-power engineering there is a diagram of operations of the technology of the environmentally appropriate combustion of refinery waste as a fuel for boiler plants (Fig.3). Unfortunately the limits of one article do not allow discuss these inventions in details nevertheless the author will realize it in practice in future works.

Conclusions:

1. The existent methods of solving of the ecological problems are ineffective as well as work of organizations, which deal with ecological and nature conservation activity. It is caused by the fact that they are oriented to search and remove consequences of ecological pollution of the nature instead of their causes.
2. The article demonstrates real causes of global ecological problems, which consist in imperfection of technologies of generation and transformation of energy.
3. Using of strong electric and electromagnetic fields of low power as combustion catalysts allow significantly improve ecological factors of combustion technologies and of devices, which realize the technologies in practice. In other words it allows realize in practice “clean combustion of fuels and wastes and possible existence of “clean” heat technics”.
4. Application of electric and electromagnetic fields in the combustion technologies allows significantly increase effectiveness of transformation of chemical and heat energies of fuel into mechanical and electric energies.
5. The electric combustion technology allows realize in practice principally new ways to control combustion process as well as to control many thermal and kinetic processes (i.e. processes of pressure, heat conductance, temperature, etc.), i.e. allows increase output of heat machines.

6. The new electric combustion technology is a universal method of solving of ecological and energetic problems of the civilization and a universal way of radical improvement of technics (i.e. of the transport, boiler plants, oil-and-gas processing plants, combustion wastes recycling plants, etc.).

References

1. V.D. Dudyshev Electric combustion technology is an effective way to solve energetic and ecological problems //"Ecology and Industry of Russia" ("Ekologia I Promyshlennost Rossii") magazine, #3 1997;
2. V.D. Dudyshev How is it possible to save the civilization and the nature from global ecology pollution? //"Ecology and Industry of Russia" ("Ekologia I Promyshlennost Rossii") magazine, #11 1997;
3. V.D. Dudyshev Method of combustion control. Patent of Russian Federation #2071219 of 19.04.1994;
4. V.D. Dudyshev Method of intensification and regulation of combustion. Patent of Russian Federation #2125682 of 06.06.1995;
5. V.D. Dudyshev Method of electric combustion of refuse and wastes. Patent of Russian Federation #2117870 of 06.06.1995;
6. V.D. Dudyshev Method of electric combustion cleaning of waste gases. Patent of Russian Federation #2125168 of 15.11.1995;
7. V.D. Dudyshev Method of combustion intensification in a fire-chamber of a boiler plant. Patent of Russian Federation #2079766 of 14.06.1995;
8. V.D. Dudyshev Method of flame extinguishing, Copyright of USSR #1621234 of 12.03.1988;
9. V.D. Dudyshev Method of decrease of toxicity of exhaust gases of motor transport. Patent of Russian Federation #2117179 of 20.02.1996;
10. V.D. Dudyshev New method of environmentally appropriate matter combustion as a radical way of solving of global ecological problems. // Collected reports of II international congress of "Environment for us and future generations: ecology, business and human rights in new conditions", Russia, Samara, 1997;
11. V.D. Dudyshev New method of refuse electric combustion // Collected reports of III international congress of "Environment for us and future generations: ecology, business and human rights in new conditions", Russia, Samara, 1998;
12. V.D. Dudyshev Problems of ecological education and upbringing of the youth // Collected reports of II international practical conference of "Pedagogical activity as a cultural activity", Russia, Samara, 1999;
13. V.D. Dudyshev Environmental safety of motor transport //"Ecology and Industry of Russia" ("Ekologia I Promyshlennost Rossii") magazine, #5 1997;
14. V.D. Dudyshev Perspective technical works out and inventions of ecological improvement of motor transport. //"Ecology and Industry of Russia" ("Ekologia I Promyshlennost Rossii") magazine, #12 1998;
15. V.D. Dudyshev Method of ICE exhaust gases cleaning, i.e. electric combustion cleaning and electric filter at ICE output. Patent of Russian Federation #1404664;
16. V.D. Dudyshev Problems and ways of ecological improving of native motor transport. //"Ecology and Industry of Russia" ("Ekologia I Promyshlennost Rossii") magazine, #11 1998;
17. V.D. Dudyshev Method of internal cleaning of exhaust gases of ICE. Patent of Russian Federation #2165031;
18. V.D. Dudyshev Method of intensification of ICE operation. Patent of Russian Federation #2135814;
19. V.D. Dudyshev Method of decreasing of toxicity of ICE exhaust gases and a device of its application. Patent of Russian Federation #2135814;
20. V.D. Dudyshev Method of intensification and regulation of combustion. Patent of Russian Federation #2125682;
21. V.D. Dudyshev Method of heat machine control. Patent of Russian Federation #2134354;
22. V.D. Dudyshev Environmentally appropriate ICE. // "New technologies" ("Novye tekhnologii") magazine #2 2001 Samara;
23. V.D. Dudyshev New electric combustion technologies. // "New technologies" ("Novye tekhnologii") magazine #3 2001 Samara;
24. V.D. Dudyshev New electric combustion technologies. // "New technologies" ("Novye tekhnologii") magazine #4 2001 Samara;
25. V.D. Dudyshev New electric technology of fire non-contact extinguishing and ignition prevention. // "New technologies" ("Novye tekhnologii") magazine #9 2002 Samara;

Infinite Energy Magazine

* Cold Fusion * New Energy
* New Science * New Technology

Subscriptions, 6 Issues Per Year
$29.95 North America
$49.95 Foreign
Single Sample Copy
$5.95 North America, $10.00 Foreign

Infinite Energy Magazine
P.O. Box 2816-FV
Concord, NH 03302-2816
Phone: 603-228-4516 Fax: 603-224-5975
http://www.infinite-energy.com

EAGLE-RESEARCH
Energy Solutions
since 1984

A Research Organization that Develops & Distributes Practical Energy-Saving Methods & Devices

4 Energy Way, P.O. Box 118
Porthill, Idaho 83853
FAX: 250/492-7480

Technical questions to:
wiseman@eagle-research.com

New Effect of “Cold” Evaporation and Dissociation of Liquids Based on Capillar Electroosmosis

Valery D. Dudyshev
Doctor of Technical Science, Professor,
Corresponding Member of Russian Ecological Academy

ecolog@samaramail.ru
http://www.intrasoft.ru/nizot

There is discovered new electric physical effect of intensive “cold” evaporation and dissociation of liquids and aqueous solutions into fuel gases **without any energy consumption** due to high-voltage capillar electroosmosis [1].

Prospects and problems of hydrogen engineering

Effective obtaining of hydrogen from water is a long-standing tempting dream of the civilization. That is connected with the fact that there is a huge amount of water on the planet, and hydrogen engineering promises the possibility to obtain unlimited quantity of “free” energy obtained from water. All the more, the very process of hydrogen combustion in oxygen medium, which is obtained from water as well, ensures ideal high-calorie and environmentally appropriate combustion.

Ecological and energetic problems are very actual nevertheless they have not been effectively solved. All known methods and devices of production of hydrogen and other fuel gases are ineffective since there is no a real high-performance technology of evaporation and splitting of liquid molecules. The main cause of ineffectiveness of the analogous consists in their difficulty and in energy consumption for breaking of intermolecular connections at dissociation of water liquid fractions.

Physical-chemical structure of even habitual tap water is quite complicated since there are numerous intermolecular connections, chains and other molecular structures in water. In particular, in habitual tap water there are different chains of oriented water molecules, which are peculiarly connected with admixture ions (cluster formations), its various colloidal compounds and isotopes, mineral matters as well as various dissolved gases and admixtures.

It is a paradox but in the living nature there is a long-standing effective way of electric capillar delivery and “cold” evaporation of liquid, which allows transform it into gaseous state without heat energy and electric energy supply line. This natural effect is realized in practice by plants, which deliver aqueous solution and make its “cold” evaporation by capillar electroosmosis. It is quite comprehensible that this natural energetically perfect technology is applicable in methods of liquids transformation into fuel gases. The author of this article has designed such experimental devices of cold electric capillar evaporation of liquids according to electric pumps of trees (Fig.1-3).

The simplest operating device, which experimentally realizes in practice the effect of high-voltage capillar electroosmosis of the “cold” evaporation and dissociation of water molecules, is demonstrated in Fig.1.

New Electroosmotic Capillar Method of Obtaining of Fuel Gas from Water



Fig.1
Simplest device of capillar electroosmosis of liquids

First experiments on the electric capillar dissociation of liquids were made with using of habitual water as well as its solutions and water-fuel emulsions of various concentrations as liquids. In all these cases fuel gases were successfully obtained in spite of the fact that these gases greatly varied due to their composition and heat capacity. The experiments on the electroosmotic evaporation and dissociation of liquids are realized in practice by the following way. First a wick (3) and a porous evaporator (4) are moisten with a water-fuel blend (emulsion) (2) then the blend (2) is poured into a reservoir (1). Then a high-voltage source of tension (6) is switched on and high-voltage difference of potentials (about 20 kV) is supplied to the liquid at some distance from the capillaries (i.e. from the wick (3) and the evaporator (4)). The source of electric field is joined to the device by electrodes (5-1) and (5). A plate perforated electrode (5) is placed above the evaporator (4) surface at a distance, which is enough to prevent an electric breakdown between the electrodes (5) and (5-1). Electrostatic forces of longitudinal electric field acts on the liquid. As a result dipolar polarized molecules of the liquid move along capillaries of the wick (3) and evaporator (4) from the reservoir to an opposite electric potential of the electrode (5) (i.e. electroosmosis occurred). Liquid molecules are detached from the evaporator (4) surface by these forces and transformed into a visual fog, i.e. the liquid is transformed into another aggregative state at minimal energy consumption of the electric field source (6). After that they provide electroosmotic elevation of this liquid. In the process of detaching and collision of evaporated liquid molecules with molecules of air and ozone as well as with electrons there is occurring partial dissociation between the evaporator (4) and the upper electrode (5) in an ionization zone. At the process a fuel gas is produced, which can come thorough a gas collector (7), for example, into combustion chambers of motor transport engine.

It has been experimentally shown that change of intensiveness of process of evaporation and dissociation of vapor molecules depends on change of distance from the electrode (5) to the evaporator (4). Moreover, this dependence is conditioned by the following factors, viz by changing of the evaporator area, kind of the liquid, quality of capillar material of the wick (3) and the evaporator (4), parameters of the electric field as well as the source of intensity (of power) (6).

The author's first experiments on this simplest device, which were organized in 1986, demonstrated that "cold" water fog (i.e. gas) appears in capillaries from liquid (i.e. water) at high-voltage electroosmosis without any observable energy consumption but just using potential energy of the electric field. This conclusion is evident since in the process of experimenting consumed electric current of the field source was the same and equal to the consumed current of the source idling. This current was not changed depending on the appearance of the liquid evaporation.

The experiments demonstrated that capillar electroosmosis evaporated quite significant quantity of water (1 liter) without any energy consumption for 10 minutes at a 10-centimeter-diameter capillar cylinder. That is to say that the consumed electric power (10 Watts) of the electric current source, i.e. of the tension high-voltage transformer (20 kV), was unchangeable and did not depend on mode of its operation. It has been experimentally stated that the whole consumed energy supplied by the current network is insignificantly small comparably with the energy of liquid evaporation. It can be explained by the fact that power was consumed only to generate the electric field and did not increase at liquid capillar evaporation that occurred due to work of an ionic pump and of a polarized pump. Hence the effect of cold electric-capillar evaporation of liquid is very economical in respect to the process energy consumption.

In spite of the fact that energetic essence of this process has not been disclosed it is evident that both "cold evaporation" and water dissociation are realized in practice by potential energy of the electric field. More precisely, the visual process of evaporation and water splitting into H_2 and O_2 at the capillar electroosmosis is realized by powerful Coulomb forces of this strong electric field.

Editor: It is not the most surprising fact. The most astonishment is aroused by school-day stereotypes that work of a field at a closed cycle is equal to zero. These stereotypes have been kept in mind of people for a long period of time. Everybody understands that a field can do work but if a body falling from some height is accelerated in a potential field and its kinetic energy increases then it requires energy consumption to relevate the body up to this height. Nevertheless, the analogy of a gravitation field with an electric one is not one-valued since the electric field may be generated only at a part of trajectory of the accelerated body motion. An electric field can be pulsating, it can be screened or it is possible to change its direction at the reverse part of the trajectory in such a way that the field constantly accelerates the body. Hence a principal conclusion can be made: summary work of a potential field may not be equal to zero. This conclusion has earlier been proposed by A.V. Frolov in his article published in the USA (Newsletter of the Institute for New Energy. May 1994. p. 1-4).

In principle this uncommon electroosmotic pump-evaporator-splitter is an example of the perpetual motion machine of the second type. Thus the high-voltage capillar electroosmosis of aqueous liquid provides really intensive and energetically free evaporation and splitting of water molecules into the fuel gas (H_2, O_2, H_2O) by means of using of potential energy of the electric field.

To produce more complete dissociation of water molecules into the fuel gas it is necessary to make the whole water molecules collide each other and be split into molecules of H_2 and O_2 in an additional transversal alternating field (Fig.2).



Fig.2
Device for production of fuel gas by electroosmosis. The device is equipped with an additional high - voltage splitting center of liquid molecules by electric alternating field.

At the second stage of water dissociation the energy of the second electric field is used, more precisely, powerful electrostatic forces are used to intensify oscillation resonant process of "collision-repulsion" of electrified water molecules represented as water gas. The result of this process is complete breaking of liquid molecules and generation of fuel gas molecules.

Conditions of optimal dissociation vary due to a kind of the liquid, to capillaries properties, and to the field parameters. These conditions are caused by required productivity of the process of dissociation of concrete liquid. Fig.2 demonstrates in details functional structure and composition of the device equipped with two sources of the electric field.

In the case of preliminary division of initially chemically neutral water into chemically active fractions (i.e. acid fraction and alkaline fraction) realization of the technology of production of fuel gas from water becomes possible at temperature below zero (up to –30°C). In winter it is quite important and useful for motor transport. This "fractional" electrically activated water does not freeze at degree of frost; hence the device designed for hydrogen production from such activated water can operate at environment temperature below zero and at degree of frost.

This principle of additional chemical activation of water (or liquid) is realized in practice in the device

(Fig.3). In contrast to the devices mentioned above (see Fig.1, 2) this device is supplied with an electrochemical activator of liquid (3) with evaporators (4).



Fig.3

Hybrid device equipped with two sources of electric field and liquid electric activator



Fig.4

Productivity of the method increases as well as oscillation frequency of the second transversal electric field (A) and evaporating area (B) increase.

There is a known and low-expenditure progressive electric technology by Stanly Mayer, which has been worked out to obtain fuel gas from water (Mayer cells). Our technology is more progressive and ensures higher productivity than Stanly Mayer's technology does [3]. It can be explained by the fact that this electroosmotic effect of evaporation and liquid dissociation combined with a mechanism of the electrostatic pump and the ionic pump ensures intensive evaporation and dissociation of liquid as well as effective detachment of gas molecules from the dissociation zone. The process of gas molecules detachment is accompanied by acceleration from the upper end of the capillaries. Therefore in our case the effect of screening of the working zone of molecules electric dissociation is not produced. All these processes proceed at minimal energy consumption, which is similar to analogous energy consumption. Moreover, the process of fuel gas production does not slow down as the process in Mayer's technology does therefore gas productivity of our method is significantly higher than that of this progressive analogue at similar minimal energy consumption.

Some technical and economical aspects of the new technology realization

In the near future production run of these high-effective electroosmotic generators of fuel gas from practically any liquids (including tap water), which are based on the proposed new technology, can be established. At the first familiarization level it is especially easy and economically appropriate to realize in practice a variant of the device of transformation of water-fuel emulsion into fuel gas. A prime cost of the production-run device for generation of fuel gas from water of 1000 m^3/hour productivity comes to approximately 1 thousand of US dollars. Consumed power of such an electric generator should come to no more than 50-100 Watts. Therefore such compact and effective fuel electrolyzers can operate practically in any motor car. As a result heat engines can work on any hydrocarbon liquid or even on habitual water. Mass application of these devices for the motor transport can cause immediate energetic and ecological perfection of the motor transport as well as designing of an environmentally appropriate and economical heat engine. Approximate financial expenditures for working out and designing of the device for fuel gas obtaining from water, and for bringing the investigation of the first testing device of 100 m^3/sec productivity to an experimental-industrial model come to about 450-500 thousands of US dollars. That contains the expenditures for projecting and investigation, for designing of the very experimental device and of a testing bed, which is necessary for approbation and engineering development of the device. The author is interested in business and creative cooperation with those companies, which can provide this project with investments to bring the device to the experimental-industrial model and introduce the perspective technology into practice.

Conclusion

Electroosmotic "cold" evaporation and dissociation of water and aqueous solutions through capillaries is a perspective way of highly productive fuel gas production at minimum of energy consumption.

References

1. V.D. Dudyshev New electric combustion technology is an effective way of solving of energetic and ecological problems // "Ecology and Industry of Russia" ("Ekologia I Promyshlennost Rossii") magazine #3 1997;
2. "New Energy News" magazine, May 1994. P. 1 – 5;
3. Stanly Mayer Method of production of fuel gas. Patent of the USA #4.936,961;

Conceptual Hurdles to New Millennium Physics

Donald Reed

E-mail: torsionpower@yahoo.com

Abstract

Time, space, energy and mass form the four-fold conceptual basis for gauging physical reality. The following paper, as a follow-up to a previous exposition [1] which focused on the necessity to change the current paradigm for time, continues in this same vein, but will also consider in greater depth the interrelations of this phenomenon with the other three yardsticks cited above. Again, information garnered from a wide variety of sources will be considered. We hope to provide, through just such a unique eclectic format, the beginnings of a possible fresh understanding of the workings of nature and perhaps ultimately furnish a conceptual basis for extending the structure of current physical theory to compatibly encompass the elements of a unified framework of physics and metaphysics.

Introduction

In the former article cited above, by investigating the following varied sources and research [2-17], we came to the inescapable conclusion that the phenomena of time and space are considerably more intimately related than is currently suspected by modern science, and will require a drastic re-working to fit the conclusions of the various evidence cited. Towards this end, the adoption of a more expansive paradigm for these yardsticks was suggested, which incorporates a fluid-field nature for time and space where both are derivatives of the fundamental ground-form of energy in flux or oscillation. These new approaches involve the inclusion of a Kozyrev-type of "substantial"(active) time-flow as opposed to the conventional "relational"(passive) concept of time, where it is used as a static parameter signifying duration. The substantial aspect of time pre-supposes that it is an essence which can and does affect physical processes, and that those same physical systems can cause a reverse action on time [8]. Such active fluctuating (deformable) types of time or space, implies the establishment of a revolutionary notion: positing completely *non-scalable* metrics for both time and space. This is in direct contrast to all contemporary orthodox models for physical reality, either in Einsteinean relativity (Special or General theory), quantum field theory, or even superstring/supersymmetric theory, all of which continue to consider both of these yardsticks from their relational (length or durational) standpoints. Consequently, all these formalisms require scalable metrics of some sort for their proper description (for refreshing viewpoints on this matter, see [7]). For instance, in the standard equations of quantum theory, time is regarded merely as an unchangeable static parameter. When we later consider applying these novel substantial aspects of time to the edifice of quantum theory, we will see that time must then become a "hidden variable". It will be seen that by considering time in this manner, a clearer and more tractable explanation of the inevitable probabilistic aspects of quantum theory, evidenced in the signature Uncertainty Principle, complementarity and non-locality will arise, without having to invoke the counter-productive and ill-conceived Copenhagen Interpretation.

Oscillatory Models for Time and Space

Upon accepting non-scalable metrics for time and space, we observe that a similar field nature for **energy** and **mass** must in turn also be postulated. Moreover, from the Killick description of how (sub-atomic) tachion-pairs operate [6], shuttling their energy back-and-forth in a free-wheeling but purposeful manner and creating oscillatory features of time and space by their action, we should consider the possibility of another unprecedented concept: a "value-motivated" energy might be at the foundation of the structural integrity of physical matter. This is conceivable when considering Killick's description of the tachion-pair dynamic/evolutionary cycle as necessarily including the 3-step process of observation – reflection – action (**trinitivity** of motion). Along the same lines, from the Smith book **The New Science** [5], we learn that a so-called "tempic field" energy exists, which could be described as the parent structure out of which our standard conception of "clock-time" (entropy changes) results. The tempic field is essentially a scalar (but not static) function which has vectorial nature only in terms of its distribution or *gradient* in space. Because of the nature of the tempic field, its derivatives – the electric and magnetic fields can operate on each other in a specific geometric/topological manner, to produce a local change in the *time-frame* of matter, to use a term coined by the entity Kryon [4]. This theoretical description of the alteration of inertial/gravitational mass and time-frame has possibly seen recent actual demonstration in the dramatic experiments of John Hutchison [10] and Rudolf Zinsser's "kinetobaric" effect [11], as well as unpublished research of both Wilbert Smith and Ken Killick with electric caduceus-wound coils [5,6].

New Models for Relativistic-Fluidic Vacuum-Structure and Possibility of its Manipulation

All of this evidence allows us to conclude that measurable changes in relativistic parameters of time, space, mass and energy might not only be a feature accompanying rapid uniform movement of physical objects (Special Relativity), or representative of large gravitating astrophysical objects (General Relativity). Indeed, by relying on current limited paradigms, contemporary physics may have missed ascertaining the possibility of being able to alter these same relativistic parameters by the artificial technological manipulation of the tempic (vacuum) fields of sub-atomic particles in stationary matter, by use of specific electromagnetic fields. Tom Bearden, for one, has articulated on these various "futuristic"-type technologies in his many writings over the years [15]. We have recently seen that some of the novel theoretical conceptions of the more visionary physicists such as David Hestenes on the zitterbewegung (vacuum "jitter") phenomenon exhibited by the electron [12-14], has finally caught up with some of these advanced ideas by presenting new mathematical demonstrations (using geometric Clifford-algebraic) manipulations of the Dirac equation. In summary, the Hestenes' study concludes that the Dirac wave function and its properties, including the Dirac equation and relations to physical observables such as energy-momentum, spin and position probability current, all possess heretofore obscured important geometric relations. These results imply that probabilistic features of the quantum theory of the electron/positron arise principally from the electromagnetic interaction of the accompanying zitterbewegung-spin field of these particles with the ambient dynamic vacuum. This is, of course, in direct contrast to the conventional received view that ascribes wave-particle duality as a property of matter that is completely independent of the nature of its interactions. This revolutionary geometric interpretation of electron dynamics incorporates in its model an electron spin which arises from a helical or spiral world-line in space-time. The essential unprecedented feature of the Hestenes' zitterbewegung idea is the association of the spin with the local circulatory-helical motion characterized by the *phase* of the electron wave function. Thus, we reach the conclusion that the complex phase factor of the electron wave function can be directly associated with an objective helical motion of the electron which is, in turn, a derivative of the zitterbewegung. One intriguing feature of this structure is a frequency of oscillation that is inversely proportional to the scalar radius of curvature of the particles' helical world-line. Moreover, the Clifford-algebraic analysis reveals that this oscillation frequency is identical to electron/positron *mass*, revealing a possible key variable particle mass-energy (*frequency measure*), which is in inverse relationship to particle size. It is clear that this new model has important classical implications not yet considered by established physics which nevertheless directly correspond to some of the key features of sub-atomic behavior enumerated above and previously. Here, we refer to the tachion-pair dynamics [1,6], and also to the microscopic dynamics of elementary particles revealed by the selected esoteric sources previously considered [1-5].

Another researcher who echoes many of these conclusions is C. Sano [21]. Sano built on the work of A.P. Smirnov [22] who postulated that Newton's Third Law of action/reaction actually modeled "screw" structures, implying that elementary particles (specifically electrons/positrons) possess chiral-spiral field configurations. Accordingly, Sano posited that all actions/reactions are transmitted between actors and reactors by parallel or perpendicular clutching of the rotating chains of electromagnetic spirals of the hidden electrons and positron-pairs of the vacuum. Also, similar to the Hestenes' development cited above, Sano postulated that the radius of the outer electromagnetic spiral surrounding the electron/positron pair can change, oscillating in size around either particle, and thus producing the particles' electric or magnetic character. Supporting his theory, Sano cites the key research of I.M. Shakhporanov [23] whose experiments claimed that magnetic monopoles were generated, by employing an electrical circuit based upon Moebius band topology. Some of the unusual phenomena demonstrated by this apparatus, tending to support the magnetic monopole hypothesis, was transformation of diamagnetic substances into paramagnetic, the ferromagnetization of normally non-magnetizable materials (graphite, etc.), acceleration of chemical reactions, acceleration or deceleration of the decay of radioactive materials, etc. Sano also claimed that extraction of energy from the vacuum was possible using rotational action/reaction using magnetic monopoles.

Referencing this research to the current exposition, we recall that the key element of Killick's hypothetical tachion-pair operation was the similar non-linear/non-orientable Moebius-type dynamic cycle which results in the corresponding deformation (compression or rarefaction) of time/space/energy parameters [1,6]. In this regard, the remarkable similarity of this model to the research of Sano and Shakhporanov may be much more than mere coincidence. In fact, later we shall examine new research outlining an apparatus (yet untested), which claims to overcome the Coulomb barrier in low energy nuclear reactions (LENR), and achieves nuclear fusion by producing local time-dilation of soft photons in proximity of the deuteron reactants.

Additional Key Russian Research

To motivate the reader's sensibilities towards consideration of some of these unorthodox ideas, we defer to the previous article [1] in which many of these notions and mentioned research are explored in greater depth, as well as consider the following corroborative research.

One intriguing example of such experiments is the work of V. Chernobrov, from which he has claimed to demonstrate both acceleration and deceleration of local time-rate, within a small spherical enclosed volume conducted since 1988 [18]. The experimental system to produce these effects, was a set of electromagnets, connected in series and parallel and installed inside the globe-shaped surface in several layers. In various arrangements including up to 3 to 5 of such layers, these electromagnetic working surfaces (EWS) of various diameters were installed inside each other (similar to the Russian toy doll "matrioshka") with the maximum EWS diameter was about 1 meter, and the minimum (internal) diameter of 115 mm. With this configuration, Chernobrov claimed to measure small but detectable deceleration (-30 sec/hr.) and acceleration (+30 sec/hr.) of time within the sphere to time monitored outside its field of influence. One interesting difference was noted between the slowing down vs. the speeding up of time. The deceleration occurred considerably more smoothly and steadily whereas with acceleration, sharp discontinuous jumps were observed. These instabilities accompanying time-acceleration was observed in connection with cycles of the moon, diurnal fluctuations, and also operator presence. Chernobrov also noticed another phenomenon that also was reported in connection with the alleged legendary Philadelphia experiment, where matter in different time-frames apparently exhibited strange relative optical phenomena [see 1,4]. Specifically, the human eye in the time-frame exterior to the experiment perceives matter within the time-frame created by the apparatus as either transparent or surrounded by a vague white mist. We note with interest that transparent "shimmering" effects of substances in the target area were also occasionally a feature of Hutchison effect [10].

Academician A. Chernetsky produced what he termed a self-generating discharge (SGD) in a plasma that exhibited longitudinal energy density waves from a structured vacuum. Some unusual effects noted were over-unity energy generation (C.O.P. > 1), as well as change of the electrical conductivity of matter (reduction of the resistance of resistor) placed between the capacitor plates of the SGD. A local structured vacuum was definitely produced since the resistance value remained unchanged even when the generator was turned off. Here reference must be made to the Kozyrev experiments [1,8], in which a type of similar *memory* process was activated ostensibly within the vacuum. Specifically, it turned out that in experiments with a vibrating torsion balance (or pendulum), at points of support the emerging additional forces did not disappear when the irreversible process (vibration) was stopped, but remained in the system for an appreciable time. The SGD plasma device may have also produced a detectable change in local time-flow rate as evidenced by decrease in frequency of a quartz oscillator placed in the discharge of the generator. The Chernetsky generator thus possibly caused anomalies in time-rate at a local space position. There were also basically anecdotal phenomena where psychic ability of personnel in proximity to the SGD was apparently enhanced [19]. The latter effects are not inconceivable once the intimate connection of consciousness to space and time is ascertained, from consideration of not only hypothetical "value-motivated" tachion-pair dynamics, but from the more prosaic studies as we shall see next.

Pathological Studies in Time-Perception

We can motivate further understanding for the claimed intimate connection of time to space by considering the results of a recent study of patients possessing a disjointed sense of time by Metod Saniga of the Slovak Academy of Sciences [20]. Saniga discovered the brain is hard-wired to perceive space and time as interconnected. Specifically, time pathology is apparently always accompanied by space pathology, in a sense that space either loses dimensions or acquires other dimensions. To quote Saniga "When time seems to stop, people often feel as if space becomes 2-dimensional. On the other hand, when the subject feels they perceive the past, present and future all at once, they simultaneously have the impression that space has infinite dimensions". This phenomenon is apparently not culturally endemic since Saniga illustrates that both pathologies cross cultural lines, evidencing similar studies cited from Italian, German and English psychological journals. In his report, Saniga combined mathematical models ("pencil-conics") and pathology reports of schizophrenic, drug-induced and other abnormal perceptions of time. His current work also encompasses studies of near-death experiences. He found that most of those who claim to have allegedly crossed over to the "other side" and back, tell similar tales. For that brief moment of near-death, the universal subjective experience of all individuals in this state of consciousness is that time loses its meaning. Although such evidence can at best be considered as anecdotal, since subjective conscious experience transcends the possibility of scientific proof, nevertheless perhaps these results from pathological and near-death studies also give us a hint towards new conceptions of time and space that necessitate both phenomena to be inextricably linked.

Investigation of the Possible Internal Properties of Time

One inescapable conclusion that results from all the above varied studies, either scientifically or psychologically based, and which cries out for future experimental verification, is the possible existence of an internal structure for time. Such a structure also implies the necessity for constructing a new edifice for physical reality that incorporates non-scalable metrics for the four fundamental yardsticks. We shall first investigate supporting evidence for internal time structure and subsequently the various implications of space, time, energy or mass that is non-scalable.

First, accepting an internal time structure, we are led to conclude that in quantum theory, time must then attain "hidden variable" status. One recent study that brilliantly articulates this notion, is the thought-provoking paper by X. Chen [24]. By positing 3 time variables as quantum hidden variables, Chen derives the Dirac equation classically. Moreover, he demonstrates that the non-intuitive property of "spin" of an electron or positron , arises naturally as a topological property of 3-dimensional time + 3-dimensional space. By extrapolating from this model, Chen then concludes that the inherent probabilistic aspects of quantum theory itself, as evidenced in wave-particle duality, Uncertainty Principle, quantum non-locality ("entangled" particles), etc., can be interpreted as the behavior of a single particle in 3 + 3 time-space. Chen postulates that the three dimensions of time geometrically form a "time sphere", with a generic point on the sphere possessing the following 3 coordinates: time radius, and two "time angles". The mathematical formalism arising from the process of stereographic projection from the north pole of this sphere, having radius of one-half, to any point on the spherical surface, incorporates both the positive-energy (north hemisphere) and negative-energy (south hemisphere) solutions to the Dirac equation (see Fig. 1 for clarification; note Z is a four-component spinor wave function). Also, by considering the evolution of a single particle, from the standpoint of this model of internal time-space, we can derive a picture of different paths on the time sphere of different weights, and on each path causality is satisfied. Through this process, Chen derives a purely classical explanation of the originally quantum-mechanically canonized Feynman Path Integral concept. This result emerges since each path from the time-sphere center to the surface corresponds to each Feynman path, and the surface of the sphere corresponds to the "surface" of the wave function. Chen also classically explains the processes inherent to Bose-Einstein-condensation (BEC) and superconductivity with this model. In such phenomena, two particles with the same spatial coordinates, cannot possess the same time angle, and thus will not have any interaction with each other and occupy the same quantum state as evidenced in BEC and superconductivity. Finally, Chen's solutions of the Dirac equation for a free particle correspond to Hopf bundles in monopole theory, and each Hopf fiber corresponds to each plane wave with different momentum states. This picture corresponds to wave packet diffusion in quantum theory. When a particle is in a fixed momentum state, each space point can contain only one Hopf bundle (one time angle), and various different time angles will be distributed in the whole space but with the same Hopf bundle. Consequently, that particle can be found everywhere. This picture appears to describe the Uncertainty Principle classically using 3 + 3 dimensional time-space. Along similar lines R. Kiehn [25] has also recently underscored the important but overlooked classical connection between spinors, minimal surfaces and the Hopf map.

Recently, Chen's work has been further developed by H. Kitada [26] who, by introducing both 3-dimensional time and energy operators, sheds new classical light on the uncertainty relation that holds between these two parameters as well. Moreover, Chen is not the only reseracher to derive the Dirac equation classically. R.A. Close has published a paper which presents a classical mathematical description of circularly-polarized waves in 3-dimensions [27]. It turns out that these chiral space waves are satisfied by a four-component wave function which satisfies a Dirac equation. Furthermore, much like the Hestenes' zitterbewegung interpretation of quantum theory, the term normally associated with electron mass in the Close equation, introduces a rotation or oscillation frequency of the propagation direction.

Classical models for nuclear processes have also recently been proposed which incidentally also imply internal time structure. Notable among these, C. Cagle claims to have developed a fusion energy device employing LENR based upon such a classical theory [28]. Normally, Deuterium nuclei are diffuse in momentum space (having high relative velocities). The process Cagle outlines produces a compactification of their momentum space (low relative velocities), so that the deuterons develop a common de Broglie wavelength that is greater than or equal to the inter-particle distance. This is claimed to be accomplished by passing soft x-ray photons near the region of two deuterons in a lattice structure of Lithium Deuteride. **The soft x-ray, when absorbed , produces a region of total *time-dilation*, causing two effects: first, ionization of atoms by strongly repelling any associated electrons in the area, and secondly and most importantly, the physical extent of the time-dilation causes two adjacent normally repelling Deuterium nuclei to overlap in a common momentum space; that is, their relative velocities achieve very low values.** Consequently, due to the time dilation, for a very short time their common de Broglie wavelength exceeds their inter-particle distance. Thus, they become strongly attractive and undergo nuclear fusion.

Cagle also claims to clarify misconceptions about the fusion process in a thermonuclear bomb. He maintains that it is not due to extreme kinetic energies (high temperatures) of particles as supposed in current paradigms, but due to nuclear processes caused by absorption of a time-dilated soft photon flux, produced by Compton scattering of hard x-rays from a fission igniter, passing through a foil of depleted Uranium. Again, just like the controlled nuclear fusion process, this causes overlapping of deuterons in momentum space (low kinetic energies) for a few pico seconds, and subsequent fusion with normal exothermal processes ensuing.

Furthermore, as a fundamental component of his LENR fusion device, which ostensibly produces time dilation and controls energy production from the fusion process, Cagle incorporates a topological field structure termed an electromagnetotoroid. The toroidal field current oscillates between toroidal and poloidal modes in a dynamic cycle which is amazingly virtually identical to Killick's description of the oscillation dynamics of a single unit toroidal tachion [1,6](also see Cagle's website for animated simulation).

Regarding dynamics of astrophysical structures, Cagle further claims that the stellar jet core star of HH30 is also a gigantic electromagnetotoroid. During the poloidal current mode, vast quantities of matter are produced and ejected along the poloidal axis when the mode changes from poloidal to toroidal. This leads one to consider the possibility that the source of superluminal gamma ray bursters, which have heretofore mystified astrophysicists and defied explanation in terms of current paradigms, might be the result of large- scale abrupt changes in the time-frame of celestial vacuum regions, subsequently causing a boost in light velocity.

Implications of Non-scalable Metrics

When postulating fluid-field natures for the four yardsticks of physical reality: time, space, energy and mass, we must assume the existence of a *non-scalable* metric for our vacuum structure. Such a non-scalable vacuum, absent of a defined reference frame, must of necessity possess a *dual* nature. That is, the primary feature of a dual vacuum structure implies that infinitely small quantities must be treated on an equal footing with those that are infinitely large. In other words, information encoded into infinitesimal elements, is also instantly present in the unbounded infinite extents as well. This is tantamount to the existence of a holographic information encoding and transmitting vacuum field, which would structure events in space and time as a non-Markovian chain. In a non-Markovian chain of events, the prediction about the next link in the chain, requires a knowledge of **all** links, not just the one preceding it.

Metod Saniga's research into mystical perceptions of superconscious reality appears to support such a primordial non-Markovian holographic mapping of time and space. To quote from a transcript of such a vision: "I wake up in a whole different world…a different space…This space was distinct from the one we all know. It had different dimensions, everything contained everything else. One was situated in a state of being in which the 'will be' (future) and the 'vanishing' (past) were already included, and this being was my consciousness. It contained it all. The 'being contained' was present very vividly in a geometric way in the form of circles of different sizes which again were all part of a unity since all of the circles formed exactly one circle. The biggest circle was a part of the smallest and vice versa."[20].

Such a structure of time and space can best be topologically encoded in a non-orientable structure such as the Moebius band or Klein bottle. Similar to the data presented in the above mystical revelations and in the previously treated Killick tachion-pair dynamics [1,5], in such configurations "inside" and "outside" lose their meanings and meld into one another; ordinary dichotomic relations distinguishing thesis from antithesis are sublated and supplanted by a higher unity defining the evolutionary process of the system. In the mathematical edifice abstracted from such a vacuum structure, duality rather than exclusivity of field structures holds sway. This in turn, presupposes a static-dynamic triality of fundamental field structures, characterized by the three magnitudes: zero, infinity and the mediating factor of unity, the latter being an indication that each of the other two field extremes are in perfect balance. Accordingly, we will assume that the stability (coherency) of non-scalable fields results whenever more than half their reality is in common.

Further development pertaining to a specific algebraic-geometric structure that would inherently incorporate this field model, will be carried out in a future paper. Nevertheless, the interested reader can skirmish on this frontier by consulting the relevant recent references to a Clifford-algebraic structure which encodes the projective duality of "space" and "counterspace" into a model for mechanics on the quantum level [29]. This promising model accounts classically for the phenomenon of quantum non-locality. It also heralds a new version of quantum field theory which, by treating electron-positron pairs as topologically non-orientable, is free of the detrimental divergences in self energy and charge, thus obviating the necessity for the ad hoc prescription of renormalization so endemic to current theory [30].

However, due to the limited scope of the current treatment, here we shall only make general comments on the significance of the above-mentioned concept of field triality. Although this model may appear foreign to current physical theory, we underscore that exactly such a system was delineated by W. Smith in the book, The New Science [5]. Observing, as we have [1], that this book in some parts of its exposition can cause confusion, we carefully choose the following selected passages that are most instructive in clarifying the notion of non-scalable metrics and in pointing the way to new paradigms (my comments in parentheses). General comment on non-scalable metrics: "Unity is half way between zero and infinity and always remains the fulcrum about which all other values regardless of scale pivot". On the electric field: "Between the two limits of zero and infinity and through unity there is divergence which we recognize as the electric field, but with the exception that there is no point charge at zero. Our awareness establishes the charge at radius unity with exactly half of it being 'inside' and the other half being 'outside'". On tempic field dynamics: "The tempic field being purely scalar in nature merely contributes to the manner in which changes can occur in the system. If, however, through some characteristic of configuration, the tempic field within a composite particle displays some irregularity, this will manifest as a 'vibration', and if the magnitude of the vibration is sufficient as to cause the interpenetrating fields to exceed the half-and-half point , the whole system will come apart: radioactivity. When a system does come apart, those field which were coherent and interpenetrating in the correct proportion will remain so and take off down the tempic field gradient and become radiated energy". On velocity of light/Planck's constant: "Within the universe we perceive, we are reasonably satisfied that the maximum value of all the coherent fields involved in our particles and radiated energy have the same value. Planck's constant is the numerical expression of this value, and the velocity of light is the expression of the numerical value of the (local) tempic field intensity". On nuclear fusion: "If a region is selected in which there are two fields of the same kind, same magnitude, same direction, such that very nearly half the reality of each is within the region, then the two fields are just on the verge of becoming coherent. If the fields are not coherent, the total energy in the region is the sum of the energies of the two fields; i.e., twice the square of the field intensity of each integrated over the region, or twice the energy of the two fields incoherent. This represents the 'packing energy' of bits and pieces of atomic nuclei, and also points the way to the precipitation of energy out of the cosmic background (vacuum engineering)". Notice how this description, written 45 years ago, of how a tempic field gradient (time-stress) operates between atomic nuclei to produce coherency (half-in half-out condition), perfectly parallels the recent Cagle view, which claims the fusion process takes place only as a function of time-dilation [28]. Finally, on gravitation: "With the exception of skew electric fields (electric field possessing tempic field gradient) all the other fields of an aggregate mass may be considered as static because they have no component of the tempic field at right angles to them. The skew fields (spiral-helical?) on the other hand, are dynamic because they do have a quadrature tempic field component. Furthermore, skew fields are largely incoherent (gravitation cannot normally be shielded) simply because the usual almost random orientation precludes their meeting the half-in requirement of form to become coherent. Since the gravitational field is due to the skew electric field, or stated differently, to the induction from the 'motional magnetic field' (longitudinally moved magnetic field), this is the logical region to explore for the mechanism by which fields may be produced to combine with the gravitational field (of Earth) to produce a resultant more to our liking (alteration of local gravitational potential)".

This last quote describes the gravitational field of a mass as a residual field phenomenon, similarly to the Sakharov and Puthoff conclusions which attribute gravitational and inertial mass to the interaction of accelerated or gravitating matter with the zero-point-vacuum-fluctuations (ZPF) causing a vacuum reaction force [31]. Moreover, similar to the Hestenes' claims, in their recent papers [32], Haisch/Rueda/Dobyns propose that, via this new interpretation of inertial mass as an acceleration-dependent electromagnetic (Lorentz) force, that a former postulate of quantum mechanics appears to be derivable classically via the interpretation of rest mass as the energy of the ZPF driven zitterbewegung; that is, the de Broglie wavelength of a moving particle, may be derived from Doppler shifts of the Compton frequency oscillations associated with zitterbewegung that occurs when a particle is placed in motion.

For further studies of physical theories with non-scalable metrics, the reader is directed to the excellent work of A.A. Nassikas [16]. Like few theories hitherto postulated, Nassikas posits a fundamental probability density function for vacuum energy, out of which oscillatory-deformable sub-atomic level physical aspects of time and space then emerge. This is the reverse to most contemporary paradigms, which view energy as a derivative of matter, time and space, even at the quantum level. Finally, A. Frolov has used Nassikas' theory to explain over-unity energy generation that has been demonstrated in some LENR electrolytic cells of the Pons-Fleischmann variety [17].

Editor: Actually Prof. Nassikas wrote in this patent that the idea which is described in the patent was proposed by Alexander Frolov. In 1996 these questions were discussed by us in Saint-Petersburg. Specifically, a Palladium cathode over-saturated with protons produces an imbalance of the vacuum engine in this area, with an accompanying change in the local time-rate and subsequent breakdown in the Coulomb barrier of the nuclei as per schemes articulated by C. Cagle [28] and T. Bearden [15].

Conclusions

In this journey through the latest research and speculations involving new interpretations of the four physical yardsticks: time, space, energy and mass, we hope the reader and technical specialists/theorists have been inspired to continue research along the lines suggested in the above dissertation. In this regard, certain open-ended questions present themselves that focus squarely on the viability of technological future developments in the new energy field. First, could the missing element in our eventual understanding of all devices featuring documented over-unity energy generation, change in mass (gravitational potential), LENR-based transmutation of elements and the amelioration of radioactivity, etc., be due the alteration of local time-flow in sub-atomic vacuum fields within the apparatus? Secondly, could the frustrating feature of the capriciousness of over-unity power and the like to yield to testable replication in many cases, be due to currently unperceived uncontrollable aspects of time and the vacuum which must be addressed in order to solve these problems? Thirdly, could incorporation of non-orientable topological structures such as the Moebius band, Klein bottle, etc. in new models of electrodynamic field structure, be instrumental in finding the answers to both of the previous questions? With sufficient probing for possible answers to such questions, the present author has the firm belief that new paradigms are certain to soon result that will crystallize these thoughts into viable scientific hypotheses subject to experimental testable verification. As an offshoot and definite bonus of this process, possibly a new more expansive understanding of the role of the vacuum in both nature and consciousness will be in the offing.

References

1. D. Reed, "A New Paradigm for Time: Evidence from Empirical and Esoteric Sources", Explore!-for the Professional, vol. 4/5 July/Sept., 2002.

2. J. Roberts, unpublished remarks as transcribed by W.H. Kautz.

3. J. Roberts, The Seth Material, Prentice-Hall, Inc., 1970, pp. 292-298.

J. Roberts, The "Unknown" Reality, Prentice-Hall, Inc., 1986.

4. L. Carroll, Alchemy of the Human Spirit (Kryon Book III), The Kryon Writings, 1995.

L. Carroll, Letters From Home (Kryon Book VI), The Kryon Writings, 1998.

L. Carroll, Passing the Marker (Kryon Book VIII), The Kryon Writings, 2000.

5. W. Smith, The New Science, Fern-Graphic Pub., 1964.

6. D. Reed & K. Killick, "Tachion Energy Theory", Energy Unlimited, 1978-1983.

7. A. Correa & P. Correa, "Consequences of the Null Result of the Michelson-Morley Experiment: The Demise of the Stationary Aether, the Rise of Special Relativity and the Heuristic Concept of the Photon", Infinite Energy, no. 38, July-Aug. 2001, pp. 47-64. A. Correa & P. Correa, "The Sagnac and Michelson-Gale Experiments", Infinite Energy, no. 39, Sept.-Oct. 2001, pp. 32-49.

8. N. Kozyrev, "On the Possibility for the Experimental Investigation of the Properties of Time", Time in Science and Philosophy, Prague, 1971, pp. 111-132.

N. Kozyrev, "An Unexplored World", Soviet Life, 1965.

A.P. Levich, On the Way to Understanding the Time Phenomenon (Part II: The Active Properties of Time According to N. A. Kozyrev), World Scientific, Singapore, 1996.

9. D. Reed, "Torsion Field Research and Implications for New Physics and Energy Technologies", Jour. New Energy, vol. 4, no. 2, Fall, 1999, pp. 151-164.

10. J. Hutchison, "The Hutchison Effect Apparatus", Proc. of the 1st Symp. On New Energy, Denver, May, 1994, p. 199. J. Hutchison, "Inside the Hutchison Effect", Extraordinary Science, vol. III, issue 4, Oct-Dec. 1991, pp. 23-26.

11. T. Valone (ed), Mechanical Energy from Gravitational Anisotropy, Integrity Research Institute, Washington, DC, 1996.

W. Peschka, "Kinetobaric Effect as Basis For a New Propulsion Principle", Raumfahrt-Forschung, Feb, 1974 (in German); trans. By D. Reed, Infinite Energy, vol. 4, issue no. 22, 1998, pp. 52-56.

D. Reed, "Translator's Analysis and Comments on the Zinsser Effect Device, Infinite Energy, vol. 4, issue no. 22, 1998, pp. 57-59.

12. D. Hestenes, "Quantum Mechanics from Self-Interaction", Found. Phys., vol. 15, no. 1, 1985, pp. 63-87.

13. D. Hestenes, "The Zitterbewegung Interpretation of Quantum Mechanics", Found. Phys., vol. 20, no. 10, 1990, pp. 1213-1232.

14. D. Hestenes, "Zitterbewegung Modeling", Found. Phys., vol. 23, no. 3, 1992, pp. 365-387.

15. T. Bearden, Extracting and Using Electromagnetic Energy from the Active Vacuum, Association of Distinguished American Scientists, Huntsville, Alabama, 2000.

T. Bearden, "Giant Negentropy in the Common Dipole", Proc IC-2000, St. Petersburg, Russia, 2000(in Press)

16. A.A. Nassikas, " The Hypothesis of the Unified Field and the Principle of Its Dual Interpretation", Proc. Of III Int. Conf. On Problems of Space Time and Gravitation, Russian Academy of Sciences, St. Petersburg, Russia, 1996.

17. A. Frolov, "The Work Created by Means of a Potential Field", Proc of III Int. Conf. On Problems of Space Time and Gravitation, Russian Academy of Sciences, St. Petersburg, Russia, 1996.

18. V. Chernobrov, "Experiments on the Change of the Direction and Rate of Time Motion", Proc. Of III Int. Conf. On Problems of Space Time and Gravitation, Russian Academy of Sciences, St. Petersburg, Russia, 1996.

19. A.V. Chernetsky, "Processes in Plasma Systems with Electric Charge Division", Deutsche Vereinigung fur Schwerkraft-Feld Energie e. V. no. 25, Mar. 1991, no. 27, Feb. 1992.

20. M. Saniga,"Unveiling the Nature of Time-Altered States of Consciousness and Pencil-Generated Space-Times", Int. Jour. Of Transdisciplinary Studies, vol. 2, no. 2, pp. 8-17.

21. C. Sano, "Twisting and Untwisting of Spirals of Aether and Fractal Vortices Connecting Dynamic Aethers", Jour. New Energy, vol. 6, no. 2, Fall 2001, pp. 178-184.

22. A.P. Smirnov, "Hyper-Physics - Physics of Reality", Kneeling Before the Truth, pp. 62-100, Materials of the 2nd Int. Scientific Clarification Conf.-2000, St. Petersburg, Russia,(2000).

23. I.M. Shakhparonov, "Interaction of Kozyrev-Dirac Emanation Methods of Detection and Interaction with Matter", Proc. Of III Int. Conf. On Problems of Space Time and Gravitation, Russian Academy of Sciences, St. Petersburg, Russia, 1996, pp. 175-187.

24. X. Chen, A New Interpretation of Quantum Theory – Time as a Hidden Variable, Apr. 2001, xxx.lanl.gov/abs/quant-ph/9902037.

25. R.Kiehn, Spinors, Minimal Surfaces, Torsion, Helicity, Chirality, Spin, Twistors, Orientation, Continuity, fractals, Point Particles, Polarization, the Light Cone and the Hopf Map, www.uh.edu/~rkiehn.

26. H. Kitada, Three Dimensional Time and Energy Operators and an Uncertainty Relation, July 200, xxx.lanl.gov/abs/quant-ph/0007028.

27. R.A. Close, "Torsion Waves in Three Dimensions: Quantum Mechanics with a Twist", Found. Phys. Lett., vol. 15, no. 1, Feb. 2002, pp. 71-83.

28. C. Cagle, (2001), www.singtech.com/.

29. O. Conradt," Mechanics in Space and Counterspace", Jour. Math Phys., vol. 41, no. 10, 2000, pp. 6995-7028.

30. B. Fauser "Projective Relativity- Present Status and Outlook", Gen. Rel. Grav, vol. 33, 2001, pp. 875-887.

31. H.E. Puthoff, Phys. Rev. A, vol. 39,(1989), p. 2333. B. Haisch , A. Rueda & H.E. Puthoff, Phys. Rev. A, vol 49,(1994), p.678.

32. B. Haisch, A. Rueda & Y. Dobyns, "Inertial Mass and Quantum Vacuum Fields", Annalen der Physik, (Sept. 2000). B. Haisch & A. Rueda, "On the Relation Between a Zero-Point-Field-Induced Inertial Effect and the Einstein-de Broglie Formula", Phys. Lett. A, vol. 268, (Apr. 2000), pp. 224-227.

Resonant Phenomena Occurring in Alternating Current Circuit

Alexander V. Frolov

Tel/fax: 7-(812)-380-38-44
E-mail: office@faraday.ru

There is a classical (according to manuals) notion that resonant phenomena can not influence on efficiency of a transformer or a motor as in a capacitive circuit or in an inductive circuit power produced at minimal power at the input of an oscillation circuit is reactive (let us remind that active power is measured at active resistance).

At the beginning of the last century this aspect was viewed differently. Advantages of a resonant case in alternating current circuits were used in practice. Let us appeal to a rare book by J. Claude-V. Ostwald named "Electricity and its applications by popular language" (I.N. Kushnerev Press, Moscow, 1914, p. 463).

"The phenomenon proceeds in a corresponding electric circuit as well as it occurs in hydraulic model: if self-induction and capacity parallel connected with each other are under influence of an alternating electric propulsion force then the total current coming through the system is equal to the difference of currents which pass two certain paths.



Fig.1

… join ammeters to the general circuit (M) and to either path (P and N). If P demonstrates 100 Amperes and N demonstrates 80 Amperes then the total current will be equal to 20 Amperes instead of 180 Amperes. Thus alternating current has its own "summary" so we should consider its condition. …capacity introduction compensates self-induction action in some way… let us begin to change the self-induction by moving a core into. What will happen if the current coming through the coil achieves 80 Amperes, i.e. is equal to the current observed in the path with a capacitor?

As you guess, since the total current is equal to difference between currents passing the paths then now it will be equal zero. It is an incredible case:the device produces zero current dividing into two paths and in each of these paths current is equal to 80 Amperes. It is a good example for the first acquaintance with alternating current, isn't it?"

Andrey A. Melnichenko (Moscow) is one of modern investigators who research this phenomenon. Any motor of alternating current can be considered as inductance. A circuit consists of motor coils and some capacitor connected in series with the motor winding. Thus if we take the circuit, consisting of motor coils and a capacitor which is connected in series to motor winding and adjust it in resonance, then mechanical power occurring on the motor shaft is produced at zero (minimal) power consumption of an alternating current source.

Melnichenko applied a simple method of voltage increase by meanse of resonance: he succeeded in obtaining of normal voltage for operation of standard motors of 50 Hz 220 V from a source of 50 Hz 110 V and 70 V. The circuit consumption for overcoming of its active resistance (of coils) can be considered as insignificant. Low frequency currents require a large capacitor. Nevertheless even at higher frequency, for example at 400 Hz, the system can be compact and effective. This method is worth to be applied in a scheme consisting of an alternating current motor in resonance mode and an electric generator which has a stable load. Change of load causes change of rotation speed therefore the system requires to be readjusted for resonance.

Experiments with powerful alternating current motors (about 100 Amperes as J.C. Ostwald wrote) working in resonance mode should demonstrate all advantages of the resonance mode application.


Situation of Alternative Power Engineering
Experimenters
Engineers
Press
Theorists

BOOKS REVIEW

Space Power Generator and Paramahamsa Tewari Update

Submitted by Toby Grotz, USA

http://www.tewari.org

A new generation of Space Power Generators is being built by Paramahamsa Tewari. The new design is expected to achieve substantial gains over previous models which has been measured over unity by experts in the utility industry as well as by independent consultants. Details are presented on the web site http://www.tewari.org.

From the Electron to a Perpetual System of Motion

Paramahamsa Tewari, B.Sc. Engg

As is well known, an electron, despite high-speed interactions with electric and magnetic fields and other particles of matter, remains unaffected structurally—maintaining its mass, charge, inertia, and locality after the interactions. This single fact itself is sufficient to postulate on the existence of some unique universal entity constituting the electron, such that the structure explains the known properties and behavior of the electron – as to how it sustains the collisions with the other particles and, yet, remains permanently indestructible without any reduction in the quantities of its basic properties. A theory that explains this enigmatic fact is framed and described in detail elsewhere. It reveals that the electron is a perpetually rotating system, a space-vortex (vortex of absolute vacuum) that through the process of motion in electric current, and interaction with external magnetic field can also lead to the development of a system partially violating Lenz's law and, thereby, capable of achieving perpetual motion in a machine. Such a conclusion has a new theoretical basis, as well as experimental confirmation – briefly outlined in this paper.

The basic understanding of the interaction of electric current with magnetic fields requires deeper knowledge of the fundamental nature of the electric current as well the magnetic field; this, in turn, leads to an inquiry on the nature of "electric charge" and its distribution in the electron structure. The origin of electron mass and charge, electrostatic and electrodynamic forces are described below with the vortex structure of electron, which further facilitates explanation of atomic structure and, thereafter, an over-unity efficiency generator. Due to brevity, predominantly qualitative-descriptions of the physical processes involved have been presented.

The full theory and diagrams are presented in From the Electron to a Perpetual System of Motion at http://www.tewari.org.

Universal Principles of Space and Matter
(A Call for Conceptual Reorientation)

A new book, *Universal Principles of Space and Matter* has just been published by Paramahamsa Tewari. Arangements are being made with the publisher to provide these books outside of India. The price is expected to be about $30 depending on shipping costs from India.

A new theory of matter, that confronts with the existing concepts of space in the contemporary physics.

The basic phenomena dealt with are:

* Structural interrelationship between space and matter
* Origin of mass, inertia, and electric charge
* Creation of the electron from space



* Discovery of new fundamental equations on mass and charge
* Derivation of the presently known universal constants (gravitational, Coulomb's constant, dielectric, magnetic permeability, electron charge, electron mass, Planck's constant etc.) with the postulate of a single universal costant – the speed of light in the absolute vacuum
* Discovery of an inward force in nuclear structure against the Coulomb repulsive forces, hitherto unknown
* Relationship between light and gravity
* Theoretical derivation of the surface gravity of the Earth, Sun and the planets
* Discovery of electrical repulsive forces between the Sun and the planets, unknown in celestial mechanics
* Derivation of the planetary orbits
* Prediction of the continuous creation of universal matter at glactic centers and existence of electrical forces of interaction btween the stars and galaxies, so far least suspected
* Identifying the fundamental particle of matter
* Revelation of conceptual errors in the modern understanding of the basic nature of light
* Vindication of Einstein's conclusion of the speed of light as the limiting speed
* Vindication of Descartes' principle of property-less ether.

New Reviews of P. Tewari's work

New reviews of P. Tewari's work have been received from Dr. John A. Wheeler and Prof. Umberto Bartocci. A copy of Universal Principles of Space and Matter was forwarded this summer to Dr. John A. Wheeler at his summer residence in Maine.

Dr. Wheeler saw the development of modern physics while working with Neils Bhor at age 27 and was a colleague of Albert Einstein's at Princeton. Credited with being the "father of the Black Hole Theory", Dr. Wheeler is well schooled in quantum mechanics and relativity.

After receiving his copy of Universal Principle of Space and Matter Dr. Wheeler called the book "a unique gift". Further reviews of P. Tewari's work by Dr. Wheeler can be found at: http://www.tewari.org/Critical_Reviews/critical_reviews.html.

Prof. Umberto Bartocci

Universita' di Perugia
Dipartimento di Matematica e Informatica Via Vanvitelli
06100 PERUGIA - ITALY
Tel.: (39)-075-5002494
E-mail: bartocci@dipmat.unipg.it

This is a very singular book, in front of the current paradigm of contemporary Physics, a "cartesian-inspired" work which calls for reorientation in the foundations, by wisely warning that:

The conclusion of the modern physics that absolute space, time, simultaneity, and space filling media are discredited ideas is certainly premature (p. 178).

The books deals with arguments such as: Discovery of Charge and Mass Equations; Fundamental States of Cosmic Energy, Fields and Forces; Gravitation; Universal Constants; Motion of Electron; Atomic Structure; Light; Creation of Cosmic Matter (about Tewari's physical conceptions see also the second section of this Episteme's special issue http://www.dipmat.unipg.it/~bartocci).

JNET

**New Energy Technologies
collection of articles
Japanese Version**

Collection of articles from New Energy Technologies magazine, 2001-2002 is published in Japan.

On purchasing of the book, please, contact

Eiichi Yamamoto,
President Yama Trans Co. Ltd.

Email: admin@yamatrans.co.jp or
eyama@yamatrans.co.jp

raum
&
zeit
Laser harmonisiert
Blut und Wasser
El Niño

Raum&Zeit

EhlersVerlag GmbH,
Geltinger Str.14e,
82515 Wolfratshausen
Telephon: 08171/41 84-76,
Telefax: 08171/41 84-66
Internet:
http://www.raum-und-zeit.com

Institut fur Raum-Energie-Forschung (IREF) i.m. Leonard Euler

- Global Scaling Theory - Hydrogen-Helium Energetic
- Gravitation theory - Information technologies
- Mathematic Biology - Telecommunication technologies
- Gravitation energetics- Transport technologies

Rotating device powered by permanent magnets

Minato Wheel

http://fdp.hemsida.net

Experiments made in Sweden

by Eric Vogels



Read about launch vehicle "Lightcraft" in the review "Commercial exploration of space"

http://www.lightcrafttechnologies.com

"Lightcraft" is made
for space flights
by means of megawatt
laser beam

Lightcraft Technologies, Inc.

Ball Lightning control

Experiments by Russian scientists



Anton I. Egorov

The standard ball formation

Read in this issue!

Tilley Foundation, Inc.

http://www.tilleyfoundation.com

K. Tilley
Electric Vehicle
(TEV) - automobile
of the future generation

ISSN 1684-7288

New Energy Technologies

Printed version ISSN 1684-7288
Online version ISSN 1684-9698

Published by Faraday Laboratories Ltd. *Issue #2 (11), 2003*

Research on advanced aerospace systems and new energy sources

Commercial exploration of space



Also in this issue:

- New experiments on magnetic motors
- Ball lightning in laboratory environment
- Alternative aircrafts and space propulsion systems

NEW ENERGY TECHNOLOGIES #11

1. Minato Wheel. E. Vogels (Sweden)
2. Mechanism of Drive-Free motion. S.A. Gerasimov (Russia)
3. Production of Ball Lightning in Laboratory Environment. Report by A. Pashova (Russia)
4. Electric Discharge Produced into Air Half-Space. G.D. Shabanov, O.M. Zherebtsov (Russia)
5. Free Energy. A.V. Frolov (Russia)
6. Some General Properties of Matter and Energy Sources. E.D. Sorokodum (Russia)
7. Commercial Exploration of Space. Review by O. Leontyeva (Russia).
8. Prospects of Hydrogen Energetics. Ph.M. Kanarev (Russia)
9. Heater Producing Healthy Effect. A.L. Belyaeva and others (Kirghizia)
10. Inertial Propulsion Device. V.E. Senkevich (Russia)
11. Unlimited Accelerated Nonreactive Motion. Review.
12. Revolutionary Current. S.K. Baliyan (India)
13. Tilley Electric Vehicle. Review.
14. Trends in the Application of Motor-Generators. A. Akau (USA)
15. Electric Vehicle in Russia. Review by A. Pashova (Russia)
16. The Richard Clem Motor and the Conical Pump. R. Koontz (USA)
17. Spontaneous Flow Heat Pump. J.-L. Brochet (France)
18. Registration of Gravitational Waves. V.N. Petrov (Russia)
19. High-Energy Hyper-Low-Frequency Electric Field. Yu.V. Ivanko (Ukraine)
20. To the Question of Work Made by Electrostatic Field. A.V. Frolov (Russia)
21. Comments to Electro-Reactive LIFTER News.
22. Letters from Readers.
23. Advertisements (books)

Perfect Energy Source

Minato wheel. Experiments in Sweden

Eric Vogels, Sweden

E-mail: fdp@hemsida.net
http://fdp.hemsida.net

The self-running bicycle wheel was shown to the public at the First International New Science Symposium in 1997, held in Korea. The inventor of the wheel, Mr. Kohei Minato, was a speaker during the symposium. On www.keelynet.com you can find the quote of an eye-witness:

"The motor is actuated by moving the N pole of a large permanent magnet (the drive magnet) toward the wheel. As this magnet is moved toward the wheel, the wheel starts to spin. As the magnet is moved closer to the wheel it spins faster.

The acceleration of the wheel is rapid. So rapid in fact, as to be startling. To put it another way I was very impressed. The motor works. And it works very well. In the film clip (see http://fdp.hemsida.net) a slight pumping action of Minato's hand holding the magnet is apparent. When I braced my hand so that there was no pumping action, the motor still ran. In fact it seemed to run better.



Fig. 1



Fig. 2

Pumping action by the hand held magnet **is not** the power that drives the motor. When the drive magnet is moved away from the wheel it coasts rather quickly to a stop and comes to rest in a manner typical of any spinning bicycle wheel. Again when the wheel is at rest and a large magnet is moved up to the wheel it starts to spin. At no time it is necessary to touch the wheel to get it rotating."



Fig. 3



Fig. 4

Since the symposium in 1997 and the first publications in the Internet several people have tried to replicate the wheel, as it seemed to be a **perfect energy source for the future**. Some claims are made that replication was successful but no proof in the form of pictures or video clips are given.

Because I have a great interest in magnets and free energy and the fact that I did a lot of experiments to find a device that could be rotated only by means of permanent magnets, I decided to try to replicate the wheel by myself.

This journey started by searching on the Internet and collecting all the material that was available. A good way to sort all the found material was building my own website at http://fdp.hemsida.net where all my findings are presented.

One of the devices I build was made from a 'how to build a Minato wheel'-manual that I found on the Internet.



Fig. 5

Unfortunately this wheel did not show any movement at all. I mounted the magnets at several angles and distances from the rim without achieving any positive results. Since the size of the wheel (1 meter diameter) was not very practical to handle and since the results were negative I searched for an easier way for testing. I found that the use of Styrofoam, an old turntable and Neodymium disc magnets kept the whole project within the edges of my kitchen table. I developed a computer program to help me design wheels, since I want to be able to replicate my own wheel, in case I find a model that works. I do not believe in an engine that works after several weeks of tuning and that fails to function as soon as one magnet is replaced. Individual tuning is okay to optimise a working design but if a design does not show the potential to rotate by itself it's a flawed design.

After optimising the way to build the small wheels, I could design and make a wheel in 30 minutes. I made a test scenario and the results for every test were posted on the web site.



Fig. 6

I searched for the 'perfect' angle, number of magnets and position. The set-up with the strongest thrust was used as the base for the other experiment. By this time I realized that I was not really trying to rebuild the Minato wheel but that I wanted **a rotating device, powered by permanent magnets.**

When for the first time I decided to split a track of magnets that covered 180 degrees of the wheel in a number of smaller tracks, **the results became much better**.



Fig. 7

By using this way of placing the magnets, every track differs a little bit from the next track, depending on its place on the wheel. The angle of the magnets influences on the thrust that is given by the stator magnet, depending on the speed that the track is entering the magnetic field of the stator. In other words: the track at the beginning of the wheel, with magnets covered side of the wheel, gives less thrust than the track at the end. This is important since a track with a lot of thrust has a big 'sticky spot' that should pass the stator. This 'sticky spot' stops the wheel during its rotation just before the first track enters the magnetic field of the stator.

During the last experiments the stator magnet changed place and pushed against the magnetic fields of the tracks from above. Simply because more thrust was developed by this way. The next wheel will have the tracks mounted on a different level. It means that the first track will have a bigger distance to the stator magnet than the last track. This should make the sticky spot weaker and the final 'kick off' stronger. The final wheel will be mounted vertically, like the Minato Wheel.

Thanks to the invention of the Neodymium magnet in 1983, magnets became much more powerful while the size and length decreased. Before 1983 a lot of the experiments could not be done since the size of the magnets made the positioning of several magnets in tracks like this was impossible. It is my personal believes that the strength of these magnets will lead to results that are impossible according to the physical law books, because these magnets did not exist when those books were written.

Until the moment I write this I have not found the perfect energy source yet but by exploitation all the material and findings on my web site I hope that more people get interested and will help searching for a great energy device that will not pollute the air which our children and grand children have to breath.

Mechanism of Drive-Free Motion

Sergey A. Gerasimov, Russia

Physics Department, Rostov State University, Rostov-on-Don, 344090
Email: GSIM1953@mail.ru

The article presents results of the experimental study of the motion created by vibrations of an internal mass of the system of bodies accompanied by impacts of the unbalanced load with the external body. This type of propulsion drive is known by a number of names. Among these are the ***vibrational propulsion device*** *and* ***reactionless machine****. Sometimes it is called the* ***inertioid*** *[1, 2]. The vibrational transposition is proved to go on by means of internal forces of a system of bodies [3-5]. The Tolchin's inertioid [6] is considered to be the first device that used the forces of inertia to create the reactionless infinite motion in space. We are not in a position to be a judge of this. There exist a number of projects of such machines but experimental results concerning such kind of motion are very limited. Below there are the experimental results on average velocities of such a motion and the description of a propulsion device a main particularity of which is absence of wheel-drive.*



Fig. 1

Scematic representation of a vibratory-impact self-transposition

The unbalanced load in this device is an electric motor *E* of mass *m* that executes undumped vibrations relative to a platform *P* of mass *M* with four wheels *W* which can roll on a horizontal surface *L* with rolling friction the coefficient of which is *k*. The frictional force is determined to be a force which adjusts to keep the cart from motion across a surface. A disk cam *C* at one end of the axle of the motor ensures a prescribed character of the vibrations and elastic impacts between the load *m* and the follower *B* of radius *a*. In present experimental device, the cam *C* consists of two semicircles of different radii *r* and *R* as it is shown in Fig.1. In this experiment r=0.03m, R=0.05m and a=0.01m. The electric motor and the platform are coupled by a connecting spring *S*. The force *F* by means of which the electric motor is pressed to the follower varies linearly from F=4N at x=0.04m to F=4.8N at x=0.08m. The compressed spring *S* is necessary not only for creating close contact between the cam and the follower. The restoring force of the spring produces the transposition of the cart in a direction opposite to **F** when the follower moves without contact from x=2R-r+a up to an impact at x=r+a. The impact suppresses the transposition. Another mode of transposition is also possible when the impact of the cam on the follower is a reason of the transposition of the cart in the direction of the force **F**. In this case the frictional force extinguishes the transposition of the cart.

Friction between the load of mass *m* and the cart is negligible since the corresponding effective coefficient is less than 0.001. The same is for the friction between the cam and the follower. The mass of the spring is m_S=0.007 kg , and the mass of the cam is m_C=0.019 kg. The total mass of the wheels is m_W=0.082 kg. This value can be useful for a theoretical

During the last experiments the stator magnet changed place and pushed against the magnetic fields of the tracks from above. Simply because more thrust was developed by this way. The next wheel will have the tracks mounted on a different level. It means that the first track will have a bigger distance to the stator magnet than the last track. This should make the sticky spot weaker and the final ‘kick off’ stronger. The final wheel will be mounted vertically, like the Minato Wheel.

Thanks to the invention of the Neodymium magnet in 1983, magnets became much more powerful while the size and length decreased. Before 1983 a lot of the experiments could not be done since the size of the magnets made the positioning of several magnets in tracks like this was impossible. It is my personal believes that the strength of these magnets will lead to results that are impossible according to the physical law books, because these magnets did not exist when those books were written.

Until the moment I write this I have not found the perfect energy source yet but by exploitation all the material and findings on my web site I hope that more people get interested and will help searching for a great energy device that will not pollute the air which our children and grand children have to breath.

Mechanism of Drive-Free Motion

Sergey A. Gerasimov, Russia

Physics Department, Rostov State University, Rostov-on-Don, 344090
Email: GSIM1953@mail.ru

The article presents results of the experimental study of the motion created by vibrations of an internal mass of the system of bodies accompanied by impacts of the unbalanced load with the external body. This type of propulsion drive is known by a number of names. Among these are the ***vibrational propulsion device*** *and* ***reactionless machine****. Sometimes it is called the* ***inertioid*** *[1, 2]. The vibrational transposition is proved to go on by means of internal forces of a system of bodies [3-5]. The Tolchin's inertioid [6] is considered to be the first device that used the forces of inertia to create the reactionless infinite motion in space. We are not in a position to be a judge of this. There exist a number of projects of such machines but experimental results concerning such kind of motion are very limited. Below there are the experimental results on average velocities of such a motion and the description of a propulsion device a main particularity of which is absence of wheel-drive.*



Fig. 1

Scematic representation of a vibratory-impact self-transposition

The unbalanced load in this device is an electric motor E of mass m that executes undumped vibrations relative to a platform P of mass M with four wheels W which can roll on a horizontal surface L with rolling friction the coefficient of which is k. The frictional force is determined to be a force which adjusts to keep the cart from motion across a surface. A disk cam C at one end of the axle of the motor ensures a prescribed character of the vibrations and elastic impacts between the load m and the follower B of radius a. In present experimental device, the cam C consists of two semicircles of different radii r and R as it is shown in Fig.1. In this experiment r=0.03m, R=0.05m and a=0.01m. The electric motor and the platform are coupled by a connecting spring S. The force F by means of which the electric motor is pressed to the follower varies linearly from F=4N at x=0.04m to F=4.8N at x=0.08m. The compressed spring S is necessary not only for creating close contact between the cam and the follower. The restoring force of the spring produces the transposition of the cart in a direction opposite to **F** when the follower moves without contact from x=2R-r+a up to an impact at $x=r+a$. The impact suppresses the transposition. Another mode of transposition is also possible when the impact of the cam on the follower is a reason of the transposition of the cart in the direction of the force **F**. In this case the frictional force extinguishes the transposition of the cart.

Friction between the load of mass m and the cart is negligible since the corresponding effective coefficient is less than 0.001. The same is for the friction between the cam and the follower. The mass of the spring is m_S=0.007 kg , and the mass of the cam is m_C=0.019 kg. The total mass of the wheels is m_W=0.082 kg. This value can be useful for a theoretical analysis. Thus, the total mass of the unbalanced body is chosen to be much larger than the mass of the cam or the spring: $m = m_E + m_C + m_S \approx m_E$.



Fig. 2
Frictional coefficient dependence of average velocity of the platform at the period of vibrations $T=1$s for various mass ratios m/M:
(*a*) $M=0.9$ kg , (*b*) $m=1.2$ kg , (*c*) $m=1.6$ kg

At least in the case of irreversible mode, one could expect that the value of average velocity of transposition $<v>$ must be proportional to the number of impacts per unit of time. In the other words the path traveled by the cart per one impact must not depend on frequency of vibrations. This is a reason why the dependence of the product $<v>T$ versus the value of the friction coefficient *k* and ratio of masses d = m/M is investigated in this work. Measurements were carried out for two magnitudes of rotation period $T=$ 1s and $T=$6s of the cam. The obtained results are presented in Fig. 2 and Fig. 3. First of all, the assumption mentioned above is not confirmed.



Fig. 3
Average velocity of the platform $<v>$ as a function of frictional coefficient *k* at $T=6$s for various mass ratios m/M: (*a*) $M=0.9$ kg , (*b*) $m=1.2$ kg , (*c*) $m=1.6$ kg

The value $<v>T$ for the period of the rotation $T=1$s sufficiently differs from that for $T=6$s measured at the same conditions. Besides, when the mass ratio is large the cart can change its direction of transposition. The reason of these results is not clear but this device provides a challenge to explain and investigate this kind of motion that enables us to discover the reactionless motion if it is probable. One should pay attention to a fact that the infinite transposition of the platform takes place even if the friction coefficient *k* is small.

References

1. Gulia N.V. *Inertia.* // Moscow: Nauka. 1982.
2. Aspden H. Anti-gravity Electronics. // *Electron and Wireless World.* 1989. V. 95. No 1635. P. 29-31.
3. Nappo F. Sulla Influenza Indiretta Delle Forze Inertne sul Moto del Baricentro. // *La Ricerca Scientifica (Rendiconti).* 1965. V. 8. No 1. P. 3-14.
4. Gerasimov S.A. Anisotropy of Frictional Force and Vibrational Transposition. // *Problems of Applied Physics.* 2001. V 7. P. 85-88.
5. Gerasimov S.A. Self-Similarity of Vibrational Motion in a Resistant Medium. // *Journal of Applied Mechanics and Technical Physics.* 2002. V. 43. No 1. P. 90-92.
6. Tolchin V.N. *Inertioid.* // Perm: Perm Book Publisher. 1977.

About the Author

Sergey A. Gerasimov graduated from Faculty of Experimental and Theoretical Physics of Moscow Physical Engineering Institute in 1976. Received Degree of PhD in Physics and Mathematics in 1987. Author of about 70 articles on Astrophysics, Atomic and Radiation Physics, Classical Electrodynamics and Mechanics. In present - Associate Professor of Department of General Physics of Rostov-on-Don State University. The fields of scientific interests are questionable problems in physics: self-interaction, self-transposition, unipolar induction.

ELECTRIFYING TIMES
an online and published
magazine about Electric,
Hybrid, Fuel Cell Vehicles,
advanced batteries, ultra capacitors,
fuel cells, microturbines, free energy systems,
events and exhibitions worldwide

63600 Deschutes Mkt Rd,
Bend Oregon, 97701
541-388-1908 fax 541-388-2750
etimes@teleport.com
www.electrifyingtimes.com
Subscription $13/3 issues

Production of Ball Lightning in Laboratory Environment

Report by our correspondent Alla Pashova

Three years ago a working device producing a ball lightning in laboratory environment was designed in Saint-Petersburg Institute for Nuclear Physics (SPINP). The produced ball lightning is accessible for detail investigation and quite stable. The lifetime of the ball lightning comes to about one second that is rather significant for alike artificial formations. The experiments on the device made by scientists of SPINP, i.e. A. E. Egorov, G. D. Shabanov, S. Stepanov, are not supported or financed. Let us note that every scientist of the group searches proofs for his own hypothesis of nature and structure of the ball lightning at all.

A leading expert of SPINP, Anton I. Egorov, pays attention to dethronement of scientific myths:

— There is a myth of ball lightning that is created by mass media. The mythical ball lightning is a concentrate of mysterious energy which is extremely dangerous for a human. It destroys houses, kills animals, pursues people. After meeting it a human can lose his hair or teeth and different misfortunes begin to happen. Supposing a simple story of a farmer-eyewitness: "It thundered, and a fist-sized fire ball rolled down along a drainpipe. It fell into a barrel of water, the water gurgled. I came up to it and put my hand into the water. The water seemed to become warmer…". After republishing of the story by several newspapers a dramatic story about a ball lightning which has evaporated a barrel of water appears. No wonder that such familiar attitude to facts causes hundreds of hypotheses of ball lightning nature.

— **What is your hypothesis about ball lightning structure?**

— At the beginning of 90th I. D. Stakhanov, a member of Institute of Magnetism (IZMIRAN), developed a special method to interview eye-witnesses that resulted a right notion on ball lightning phenomenon. According to Stakhanov, ball lightning is a clot of hydrated plasma which is generated in wet air at electrical discharge.

Water as a chemical compound is remarkable for its anomalous properties: combining of two lightest elements does not generate gas but produces a high-boiling liquid. This is caused by extremely irregular distribution of electrons in a water molecule. Due to this property it acquires properties of an electric dipole. Water molecules interact with charged ions, aerosol particles, and with each other in a special way.

If a positive ion and a negative ion are introduced simultaneously into a puff of warm wet air then water dipoles immediately produce hydrate shells around the ions. When the hydrated positive ion approaches the hydrated negative ion additional water molecules are drown into gaps between them. As a result, there is a stable cluster in which the charged ions are conserved. The cluster consists of two ions of opposite charges and the hydrate shell. Water molecules prevent the ions' approaching and recombination, hence, lifetime of the ions in the cluster increases up to tens of minutes, i.e. in 12-13 orders. Interaction of clusters causes open-chain structures followed by space structures. That is to say, there is appeared a clot of cold hydrated plasma that accumulates great energy (up to 1 kylojoule per liter). The clot of plasma loses this energy at recombination of ions.

— **Could you, please, tell about the design of the device? What processes proceed when the device is operating?**

— Our task is to introduce an abundant population of ions into a puff of warm air saturated with water vapors. A base of the device for laboratory reproduction of ball lightning is a capacitor bank which is able to be charged up to 5.5 kV. The positive pole of the capacitor bank is connected to a ring electrode by means of a copper bar. The ring electrode is placed on a bottom of a polyethylene reservoir filled with water. The negative pole of the capacitor bank is connected to a carbonic electrode which is placed in the centre of the reservoir near water surface. A quartz pipe encloses the electrode in such a way that it is possible to drop water or to put some natural matter on it.

To generate a ball lightning 2-3 drops of water are put on the electrode. When impulse discharge occurs a bright plasma spout escapes the centre of the electrode that is accompanied by a quiet plop. A glowing plasmoid which is an artificial ball lightning parts from the plasma spout. It comes up slowly in the air and then disappears falling to pieces in 0.2-0.3 seconds.

We have made thousands of experiments for investigation of ball lightning properties, i.e. defining size, lifetime, colour, average temperature, excessive charge, content of a dust component.

It was ascertained that the artificial ball lightning is generated in a narrow interval of breakdown tensions. The average size of such a ball lightning is 12-20 cm, and its lifetime comes to 1 second. Temperature of the ball lightning is not very high, i.e. 50° C. This can be defined if to take into account speed of rising of the ball lightning. If the plasmoid is accepted as a puff of warm wet air of 14-centimeter diameter which in atmosphere comes up at 293 K at speed of 1-1.2 m/sec then, consequently, its temperature should not exceed 330 K.

Colour of the lightning varies greatly and depends on presence of aerosol of matter trapped in the moment of discharge. Usually the lilac central part of the plasmoid is surrounded by a diffusive yellowish layer. Some admixture of natrium salt and calcium makes the core of the plasmoid yellow or orange.

If the central carbonic electrode is replaced by an iron or copper or aluminum one then the fundamental character of the phenomenon does not change. However, colour of the plasmoid depends on a radiation spectrum of excited atoms of the electrode, i.e. iron plasmoids are whitish, copper plasmoids are greenish, aluminum ones are white with reddish shimmer.

— **A generated ball lightning exists for about 1 second. How can it be made more stable?**

— Lifetime of an artificial ball lightning depends on many conditions, i.e. size and geometrical form of the central electrode, voltage between the electrodes, value and duration of a current impulse, temperature and electroconductivity of water which is put on the central electrode. Besides, lifetime of the plasmoid can be changed by introducing an additional dispersive phase into it. We have tested tens of matters and begun to investigate suspensions of colloidal graphite and fine-dyspersated ferric oxide.

A suspension of 3 g of colloidal graphite, 8-10 ml of acetone (which played role of penetrating agent), and 90 ml of water is put on the central carbonic electrode. When an electrical discharge occurs a layer of the suspension forms a flying spherical plasmoid. It comes up slowly and disappears in 0.3-0.8 seconds. The core of the plasmoid has a colour of flame, i.e. colour of burning carbon.

To prolong the existence of the generated ball lightning without application of aerosols it will be possible to use the so-called "Faraday's cylinder" whose production has been already begun. For the same purpose G.D. Shabanov proposes to put a stopping potential on a probe of detention.

— **There is an opinion that physical nature of ball lightning is similar to the process of controlled thermonuclear fusion. In this case, if your work on generation of a stable ball lightning is successful then you will be a competitor of the expensive project of controlled thermonuclear fusion**.

— I think that it is totally incorrect. Hydrated plasma is the first enemy of the thermo-nuclear fusion as water molecules do not allow neutrons approach each other. Effective cold fusion should be realized in organic liquids, for example, in heavy acetone or in a water-free medium. Somehow, it should be an absolutely "dry" process. No experiments on real "dry" cold fusion have been realized in practice. It has not been also examined the surfaces on which the combination of heavy hydrogen atoms produces maximal heating.

Scientists should pay attention to two most effective cold fusion processes. The first one expects association of two atoms of deuterium occurring on a totally dry deuterated surface which consists of, for example, zirconium deuteride. In the moment of fusion of a deuterium molecule local heating appears, and neutrons depart. The other perspective method of realization of the cold fusion process requires an absolutely "dry" organic liquid, i.e. liquid acetone in which hydrogen atoms are replaced by deuterium atoms (C_3D_6O) or by atoms of cyclic compound of $C_6(D_2)_6$. A tellurium or zirconium tip of an ultra-sonic dispersant is placed into a reservoir of this liquid. Cavitation blebs are formed on the surface of the dispersant. Neutron output comes to 10^4 particles. Maximal neutron output, which was achieved by Lipson, an American experimenter, consists of 10^8 neutrons at a desired result of 10^{13}. Certain quantity of neutrons can be obtained during ultrasonic cavitation which is accompanied by a phenomenon of sonoluminescence. Due to sound resonance the only cavitation bleb is generated in acetone. When the bleb collapses weak glowing is observed. The cause of this phenomenon consists in gas heating occurring in the bleb that is the result of high pressure produced by its collapse. The burst can last from 1/20 up to 1/1000 sec. Light intensiveness depends on quantity of gas in the bleb. If gas is absent in the bleb then the glowing does not occur. Light emission of the bleb is very weak, it becomes visible if it is strengthen or in absolute darkness.

— **Is it rightful that cold fusion is the future of world power engineering?**

To my mind another direction seems to be more perspective, i.e. extraction of uranium from sea water and then its burning in heavy hydrogen reactors like one which exists in Canada. Photo voltaic accumulators can also become a successful approach of the alternative traditional fuel engineering. By the way, a working model of such a device to utilize free solar energy has recently been created in our Institute (official web site: http://www.pnpi.spb.ru).

Editor: Read the publications on this theme in following issues of our magazine. Below there is a description of other attempts to generate a ball lightning in laboratory environment or at home. Besides, we publish an article dedicated to the problem of laser control of ball lightning. In the article there are photos (also see the cover page) and a scheme of the working device designed by this scientific group.

Ball Lightning Experiments

Information from
http://www-personal.umich.edu/~reginald/ball_l.html

Ball Lightning in the Microwave

This is a great experiment to try at home. It requires a microwave oven, a candle, a toothpick and a lighter. First you put the candle (~1-2 inches in height) in the microwave (remove glass plate from bottom so candle sits on metal). Put the toothpick in the candle sticking straight up. Light the toothpick on fire so that flames are leaping off the tip. Shut the door quickly and turn on oven full blast. There will be loud popping noises and then balls of fire will leap from the toothpick and fly around inside the microwave while making a buzzing sound like a bee. If it doesn't work at first try to move the position of the candle in order to find the "hot spot" in the oven for it to work.

Real Ball Lightning Generated by Pulsed Power Inductor

This experiment is very DANGEROUS. The author did this one a few years ago. The Idea was got from an article about a guy generating ball lightning using a high current transformer (TBA). The author had an idea of using an inductor to store large amounts of electrical energy. The conductor on the end of the stick touches the metal ring. This completes the circuit, and start the inductor. Then there was used the air compressor nozzle to blow out the arc as the wire was pulled away. The copper wire explodes and creates rapidly rotating and burning molten balls of copper. These 'Balls of Fire' exhibit many of the properties of real ball lightning.

Electric Discharge Produced into Air Half-Space

Gennady D. Shabanov, Russia

Tel. +7(271)46477
E-mail: discharge@gtn.ru

Oleg M. Zherebtsov, Russia

Tel. +7(271)46272
E-mail: omzher@mail.ru

In the article a possibility of streak lightning control by means of low intensive laser emission is observed.

During investigation of an electric discharge into air half-space [1] it was noticed that this discharge can be controlled by a low intensive laser beam. Now there is a problem of laser control of lightning discharge [2]. However, numerous works on this approach demonstrate that "the hope to get a quick solution of the problem of lightning control by laser emission has not been confirmed" [3].

Careful observation of this problem in [2] has shown ways out the situation. The authors of [2] consider plasma channel produced (by means of laser) in free atmosphere at a possible greatest height to be of doubtless interest of the science of lightning. Finally, creation of the plasma channel should be of benefit for lightning protection. The authors of [2] give notice that "there are many difficulties of fundamental and practical importance on this path".

Weak theoretical understanding of lightning generation causes pessimistic estimations of solution of the problem. The article [2] notes particularly that "there are neither adequate theory, nor numerical calculations and qualitative understanding of the phenomena defining the speed of a leader… The situation of a theory of the leader channel is little better (from quantitative point of view)…".

Realistically the following statement can refer to the lightning discharge: "The electric discharge appeared to be very "unhandy" for theoretical description but the most interesting phenomenon in the experimental aspect" [4].

Experimental Part

In this work a capacitor bank with 0.6 mF capacity, which can be fed up to ~5 kV, was used to produce impulse discharge into air half-space. A scheme of the device is presented in Fig.1. At connection/disconnection of a discharger 5 a "spout" is let out of an electrode 3. The spout carries the potential of the cathode (virtual cathode) at a significant height into air half-space. A probe placed at the height of ~15 cm fixes a potential which is similar to the potential occurring at the cathode. The researches have demonstrated that the produced formation continues to glow for several hundreds of milliseconds (the glow is fixed from a zone located at 15-45 cm above the cathode). Typical time of the discharge comes to 100±20 msec and depends on the cathode material. Electric field generated in the spout comes to less than $8\ \text{V cm}^{-1}$.

Ball Lightning Experiments

Information from
http://www-personal.umich.edu/~reginald/ball_l.html

Ball Lightning in the Microwave

This is a great experiment to try at home. It requires a microwave oven, a candle, a toothpick and a lighter. First you put the candle (~1-2 inches in height) in the microwave (remove glass plate from bottom so candle sits on metal). Put the toothpick in the candle sticking straight up. Light the toothpick on fire so that flames are leaping off the tip. Shut the door quickly and turn on oven full blast. There will be loud popping noises and then balls of fire will leap from the toothpick and fly around inside the microwave while making a buzzing sound like a bee. If it doesn't work at first try to move the position of the candle in order to find the "hot spot" in the oven for it to work.

Real Ball Lightning Generated by Pulsed Power Inductor

This experiment is very DANGEROUS. The author did this one a few years ago. The Idea was got from an article about a guy generating ball lightning using a high current transformer (TBA). The author had an idea of using an inductor to store large amounts of electrical energy. The conductor on the end of the stick touches the metal ring. This completes the circuit, and start the inductor. Then there was used the air compressor nozzle to blow out the arc as the wire was pulled away. The copper wire explodes and creates rapidly rotating and burning molten balls of copper. These 'Balls of Fire' exhibit many of the properties of real ball lightning.



Electric Discharge Produced into Air Half-Space

Gennady D. Shabanov, Russia

Tel. +7(271)46477
E-mail: discharge@gtn.ru

Oleg M. Zherebtsov, Russia

Tel. +7(271)46272
E-mail: omzher@mail.ru

In the article a possibility of streak lightning control by means of low intensive laser emission is observed.

During investigation of an electric discharge into air half-space [1] it was noticed that this discharge can be controlled by a low intensive laser beam. Now there is a problem of laser control of lightning discharge [2]. However, numerous works on this approach demonstrate that "the hope to get a quick solution of the problem of lightning control by laser emission has not been confirmed" [3].

Careful observation of this problem in [2] has shown ways out the situation. The authors of [2] consider plasma channel produced (by means of laser) in free atmosphere at a possible greatest height to be of doubtless interest of the science of lightning. Finally, creation of the plasma channel should be of benefit for lightning protection. The authors of [2] give notice that "there are many difficulties of fundamental and practical importance on this path".

Weak theoretical understanding of lightning generation causes pessimistic estimations of solution of the problem. The article [2] notes particularly that "there are neither adequate theory, nor numerical calculations and qualitative understanding of the phenomena defining the speed of a leader... The situation of a theory of the leader channel is little better (from quantitative point of view)...".

Realistically the following statement can refer to the lightning discharge: "The electric discharge appeared to be very "unhandy" for theoretical description but the most interesting phenomenon in the experimental aspect" [4].

Experimental Part

In this work a capacitor bank with 0.6 mF capacity, which can be fed up to ~5 kV, was used to produce impulse discharge into air half-space. A scheme of the device is presented in Fig.1. At connection/disconnection of a discharger 5 a "spout" is let out of an electrode 3. The spout carries the potential of the cathode (virtual cathode) at a significant height into air half-space. A probe placed at the height of ~15 cm fixes a potential which is similar to the potential occurring at the cathode. The researches have demonstrated that the produced formation continues to glow for several hundreds of milliseconds (the glow is fixed from a zone located at 15-45 cm above the cathode). Typical time of the discharge comes to 100±20 msec and depends on the cathode material. Electric field generated in the spout comes to less than 8 V cm^{-1}.



Fig 1
A scheme of a device made for producing of long-living plasmoids

1 – a polyethylene reservoir, 2 – a ring electrode, 3 – a central electrode, 4 – a capacitor bank of 0.6 mF capacity, 5 – a discharger, 6 –water or aqueous suspension drop, 7 – a quartz pipe, 8 – a carbonic or metal electrode, 9 – a copper bar.

The spout was acted by weak laser emission of less than 1 mW at 22-centimeter height. The laser beam was directed perpendicular to the discharge axis, the spout achieving the laser beam moved along the beam towards the laser.

In Fig.2 the spout has moved ~8.5 cm along the laser beam, and a usual sphere formation was generated. Due to the horizontal motion it was distorted if to be compared with usual sphere formation. The usual sphere formation is represented in Fig.3 (also see the cover).



Fig. 2
Motion of the leader channel (spout) along the laser accompanied with the sphere formation



Fig.3
The standard ball formation

Discussion

As it is evenly mentioned in [5], results of model experiments are difficult to be applied directly to laser control of lightning because in short intervals characteristics of the discharge differ from characteristics of lightning discharges. Actually, at comparing considered current and the field existing in a lightning (i~100 A, ~3 V cm^{-1}) with these phenomena occurring in a laboratory spark (~1 A, ~300 V cm^{-1}) incorrectness of modeling of this process becomes obvious. From the other hand the authors of [2] note that "the leader channel is like a channel of electric arc… At current strength of ~100 A plasma of the channel of the arc is supported by fields the densities of which come to several volts by a centimeter. The lightning has such leader currents".

Even an air arc of atmosphere pressure has a field of about 100 V cm^{-1} at currents of about 1 A. The generated discharges (spout) accompanied by the field of less than 8 V cm^{-1} (maximal current appearing in the discharge gap is 50-60 A) are more appropriate for modeling the leader channel of the streak lightning than typical discharges used for investigation of these processes, for example, like [6].

At first approximation the leader channel is considered as an ideal conductor in the article [2]. We make research to define the field in the discharge (spout) more exactly. The article [2] makes the following consideration about a cause of occasional generation of new leader heads: "the surface of *equipotential* plasma conductor (channel) *has* a property of *instability*. There is an occasionally generated sharp jut. An intensified field appears at the jut along the edge. Under the influence of the field the jut becomes to grow in any direction including at the significant angle to the weak outer field". The aforesaid seems to explain why our leader channel changes its direction and runs at right angle to its initial motion. (Fig.2). Weak harmonic action of the laser beam to the leader channel causes generation of a new head which continues motion "on the significant angle".

The effect of plasma motion towards a light beam is a demonstration of a general tendency of propagation of the discharges to an incident electromagnetic field [7]. “Area occupied by plasma usually increases towards the laser emission” [8]. Leading character of motion of this formation is confirmed in [9] as well as the interaction with the laser beam is confirmed in [10]. It should be taken into account that in the works [9-10] experiments were performed at devices which generated such a discharge. However, that discharge was by 2 orders weaker than the discharge generated by the device represented in this work. Naturally, the results were less defined. Comparison of the discharges is presented in [11].

According to our data, the leader channel (spout) has a very abrupt bound (less than 1 mm). In this layer the field can come to $\sim$30 kV cm^{-1} (at height of 15 cm).

Conclusions

Due to the assumption [2] about *instability* of the surface of the *equipotential* leader channel there has been successfully performed the “control” action on an electric discharge which models a streak lightning. It has been achieved by means of weak harmonic oscillations made by the laser. This mechanism is supposed to be applied for streak lightning control.

References

1. G. D. Shabanov. Optical properties of glowing formations // Letters in the Magazine of Technical Physics. 2002, V.28, I.4, P. 81-86;
2. E. M. Bazelyan, Yu. P. Rizer. Mechanism of attraction of lightning and problem of lightning laser control (Nowadays Physics) // the UPS. 2000. V. 170, #7, P.753-769;
3. A.D. Starikov, Yu. A. Rezunkov. Lightning discharge control by laser emission. // the Optic Magazine. 1999, V. 66, #3, P. 15-16;
4. B. E. Meyerovich on the path to realization of electromagnetic collapse // the UPS. 1986. V. 149, #2, P.221-257;
5. Miki Megumu, Uada Acushi, Shindo Takatoshi. Characteristics of laser controlled discharges occurring in long air gaps // the Optic Magazine, 1999, V. 66, #3, P. 25-29;
6. P. Rembo, J. Biggert, V. Kubechek, J. Schwartz, A. Berstein, J. Dilet, R. Bernstein, K. Shtalkopff. Laboratory investigations of lightning discharge initiated by laser // the Optic Magazine, 1999, V. 66, #3, P. 30-35;
7. Yu. P. Rizer Laser spark and distribution of discharges. Moscow: Science (Nauka), 1974. P.308
8. A. A Mak, N. A. Solovyev. Introduction into physics of high temperature laser plasma. Leningrad: Publishing House of Leningrad University. 1991. P. 152;
9. S. E. Yemelin, A. L. Priozersky, V.S. Semenov, G. E. Skvortsov Characteristics of dynamic state propagation in stream of capillary discharge. // Letters in the Magazine of Technical Physics. 1997, V.23, I.19, P. 54-59;
10. R. F. Avramenko, A. Yu. Gridin, A. I. Klimov, V. I. Nikolaeva. Experimental investigation of power-consuming compact plasma formations. // Collected articles Ball lightning in laboratory. Moscow: Chemistry. 1994;
11. G. D. Shabanov, O. M. Zherebtsov, Experimental modeling of ball lightning analogue. // Theses of 10th Russian conference on ball lightning. Moscow (Dagomys). 2002. P. 17-20.

New Energy Technologies

PRINT EDITION ADVERTIZING RATES

Full Page Ad
B/W - $400
Color - $800

Half Page Ad
B/W - $200
Color - $400

Quarter Page Ad
B/W -$100
Color- $200

New Energy Technologies is distributed in the leading Scientific Laboratories in Russia and has subscribers in more than 20 countries all over the world

To advertise contact us:
Faraday Labs Ltd, Phone/fax: 7-812-380-3844
http://www.faraday.ru, office@faraday.ru

Free Energy

Alexander V. Frolov, Russia
Faraday Laboratories Ltd
http://www.faraday.ru, tel/fax 7-812-3803844

In general the conception was formulated in 1995 and today we can say that the concept of physical vacuum, which is a new source of energy, finds more and more supporters. The fundamental works about nature of "zero point energy" are published, for example, Andrew D. Sakharov [1], Hal T. Puthoff [2] and many other interesting works. It is clear now that space or "physical vacuum" has its internal structure, therefore it can be used as a new source of energy if we organize the process of changing of this structure. Moreover, according to some theories, the existence of reality (i.e. the World of some certain parameters of space and time) is defined by the function of probability of energy density. For example, Dr. Nassikas, Greece [3], proves that it is not possible to consider the space without its energy, and there is no space without energy. The internal structure of reality is coexistence of two forms: gravitational energy and electromagnetic energy. Any local increase of the first one should produce decrease of the second one, so the sum amount of the change is zero.

In some other articles about energy transformation processes (gravitational form of energy into electromagnetic heat radiation of mass, for example) we can find that both increase of entropy and the inverse processes (decrease of entropy) are possible and in this case the electromagnetic energy can be converted into the gravitational form, that is shown in details in the works of Nobel laureate I. Prigozhin, Order and Haos. Man's new dialog with Nature, London, 1984. Since **the direction of time** (the time course) **and direction of the entropy change** (increase or decrease) are related notions then free energy technologies are considered by Kozyrev as methods of practical application of natural time course [4] that is presented in aether-dynamics by Frolov as aether flow of some density and this aether density determines the time rate as hardness of cause-effect connections for any process, and also for the process of existence of matter in space-time of this aether density.

According to this theory, in any point of space it is possible to get power by means of energy transformations without any consumption of mass-fuel. We can say also that in this case some change of the energy density of space should be detected.

Let's clarify some determinations:

1. The Potential (lat. Potentia that means "force"). In physics this is scalar parameter, it's gradient expresses the intensity of field of a certain force. In common sense, the potential is possibilities, which exist for execution of some task, for completion of some work.
2. The Work is a quantitative parameter of energy transformations. The transformation means here change of form.
3. The Energy (Greek "Energie" means "action, activity") is a quantitative characteristic for different forms of motion.
4. The Power is amount of work per unit of time.

According to the given determinations by The Soviet Encyclopedic Dictionary, edition of 1988, Moscow, **the fact of presence of potential (scalar) field, for example, electrical or gravitational filed, is real possibility to produce some work if we can organize change of energy forms. Let's note that power source is not required to keep the potential field in force. It is free.**

...the potential (scalar) field can produce real work!

The example of this work, which is produced by the field: body falls in gravitational field and when it strikes on the ground then some part of its potential energy is transformed to heat, that is the work as transformation of energy forms. So, there is a conclusion: the potential (scalar) field can produce real work! But we have considered only a half of cycle and in classical case in the second half of the cycle it will be necessary to produce the same work against the field to raise the body to the initial point.

Let's formulate the task to produce the work periodically and to get the power in load from this process. Usual mistake is to accept the particular case (the same body returns back in the same field) as a single possible case. But in special case changes of the system are possible, for example, the field intensity is not a constant but some variable value (alternating or pulsing), or the body changes its own parameters. In this case in each of half-cycle of the process the field can produce real positive work to accelerate the body.

The main technological solutions are obvious: **it is necessary to create gradient of field in space** (full or partial screening of trajectory of the body, which is moving in the field) **or gradient of field in time** (pulsing mode of field). This is quite easy for electric and magnetic fields, but for system, which uses gravitational field to produce the work, we can assume changes of parameters of the body only.

It is possible to understand why professional physicists dislike the question about possibility to use scalar (potential) fields to produce useful work in a load since they think about The Law of Energy Conservation. To find mutual understanding it is necessary "to upgrade" this Law for 4-dimentsional case of real physical system. It is necessary to introduce **the notion of the structure of space-time** where the considered process is created. In other words, for real practical engineering tasks it is necessary to consider **space-time of the real process** but not an abstract space-time. Usually the energy density of technical processes is small in comparison with natural energy density of space (aether density), which is a result of real astrophysical processes, i.e. motion of planet, star, galaxy. If we discover structure of this real rhythm of the space-time of our planet then we'll be able to design it in our technical devices to use aether-dynamics as theoretical basis.

So, in orthodox physics there is the unchallengeable formulation: the work of potential field on closed trajectory of motion is equal to zero. Yes, it is right for only case: if one part of work is positive (the acceleration) and another part is negative (the deceleration). But one part of the trajectory or a part of periodic process with the negative work can be excluded by different methods: by means of spatial superposition, pulsing mode and change of interaction polarity or by the screening of electromagnetic interaction.

For example, minor changes in vacuum tube design (the grid is located under cathode) allows increasing the kinetic energy of electrons and to increase emission current by means of the potential on the grid only. Also vector potential of magnetic field or gravitational potential can be used by similar way.



Fig. 1

Besides this way it is possible to use pulsed mode and switch-off the primary energy source before the emission electrons will reach the anode, Fig.2. In this case there is not the conductivity current between anode and cathode and the primary source is not discharging during its work.

Therefore, it is not a news that potential field can produce real work. In any textbook there are examples of positive and negative half-cycles that result to zero net work. But for the case of consequent execution of two processes the parameters of one of the processes can be changed, that **the work, which is produced on the closed trajectory can be formed as two or more parts of positive work.** Important aspect is following: it is necessary to determine the point (moment) of change the sign of the interaction and at that point (moment) to change the parameters of the process accordingly.



Fig. 2

The good sense requires the answer: what is the source of the power to produce this work if this proposed concept is right? Let's notice that before the considered examples, the existence **of power interactions of potential fields** must make the same question. For example, how the ordinary permanent magnet (i.e. its vector potential) holds a piece of metal making work against force of gravity without any fuel? How the potential field can move and accelerate ions, i.e. kinetic energy of ions can be increased without any fuel? What provides the forces of elasticity? Let's try to find answers from consideration of inner structure of electric and magnetic field, especially let's develop **our understanding of the notion of gradient, which describe properties of space-time design in area of this field.**

The concept of potential as bi-directional flow of photons and anti-photons was proposed by English mathematician E. Whittaker, and then it was developed by Dr. Thomas E. Bearden [5]. In this concept, the generalization of the Third Newton's law looks as the requirement of complementary pair to the process of the electromagnetic radiation. Since "process" means a change of information in time, this paired anti-process is reversed in time. Of course, it is development of process to its own future, but from our point of view, it goes from future to past. According to generalized Third Newton's law the radiation of photon is paired with anti-photon. In this case, the internal space-time structure of electric potential field is formed by two contrary flows of energy: photons spread from charge source and the anti-photons "inflow" into the charged mass. Let's notice that this concept defines the relationship of charge and mass. The charge without mass does not have any sense.

The flow of energy outgoing from charged mass is responsible for all phenomena of radiation. Incoming flow of energy is responsible for the gravitational interaction. Therefore, the notions "radiation" and "gravitation" can be considered as complementary pair; that is considered in details in concept of Josef Hasslberger [6].

...it is impossible to get "something" from "nothing"

There is a quite correct question: since "something" can not be created from "nothing" then what and where will be changing if we create the process of free power dissipations in local area of our space-time by means of asymmetrical potential interaction?

Let's try to present a "process" as some change of "information" in time and from this point we'll get the conclusion about results of this energy disbalance of the natural internal structure of potential field: in this case the entropy process in direct time (heat dissipation in load) should be balanced with equal anti-entropy process in reversed time. In other words, the disbalance is change of the space-time curvature and changes in the time rate.

So, it is impossible to get "something" from "nothing" but if we have understanding of the balance (process in time and anti-process in reversed time) then in the Universe the 4-dimentsional balance is not violated. It is assumed here that it is impossible to create one process but it is possible to create two opposite balanced processes, and each of them produce real work in the load. In astrophysical consideration it was stated in 1964 by Academician Gustav Naan, Estonia, Tartu. He wrote [7]:

"In our real world we could extract any amount of energy from vacuum if some technology provides at the same time the extracting of the same amount of energy for anti-world. Total sum value of energy is equal to zero."

Let's note also that similar conception of "dynamical zero" was applied in ancient India mathematics, i.e. "zero" is not "nothing" but it is hidden possibilities (balance of forces).

One more interesting question appears: what is about reality of the particle of matter after we have claimed that its mass-parameters are parameters of certain process? With this idea the material world as a whole is certain process and "stability" is not a property of some object but a parameter of its existence, which is a process in space-time of some certain energy density and some certain structure. By analogy the vortex in liquid is a process but it is not a liquid.

Thereafter, as electron was presented by Shredinger as wave packet and by Whittaker as function of two scalar potentials, the old idea of instability or **dynamic structure of matter** has the possibility of experimental testing and development as a teleportation technology. This idea is technology of space-time engineering, i.e. creation of the space-time with some certain parameters where curvature (or rate of time) determined rate of existence of the matter in space. It is related with some energy density, which can be increased or decreased. Since by this way it is possible to consider any material particle of substance as certain process, which is balanced by corresponding time-reversed process, so there is no theoretical difficulties to develop technologies of chemical transmutation, materialization, dematerialization, teleportation etc.

So, the using of potential energy to create a process of dissipation of power in load does not violates the Law of Conservation, and this Law can be generalized: the total energy of four dimensional system is amount of energy of processes in time and energy of processes in reversed time, it is constant and it is equal to zero.

Now let's try to review some free energy projects (the systems to produce work without consumption of fuel). Russian Peter the Great had intention to visit Germany in 1725 to test the Orferius' device. There is a very old description of "perpetually rotating wheel", which was made in India by inventor Bhaskar in 1150! From that times the mind of inventors is developed to other modern systems but due to the efforts of scientific groups, which are interested to keep in force the ideas of primitive materialism, the great idea of free energy transformation is distorted to such extent that any person, who began to speak about free energy, had a chance to get the name of "mad". Why? The reason is common understanding of the "power", which is "some work per unit of time" and generally it can be presented only as result of some transformation of matter structure, i.e. disintegration, chemical reaction, nuclear decay, nuclear synthesis or any change of structure of a matter. In any case, a material (the firewood, oil products or nuclear fuel) is considered as the fuel, regardless of its transformation method.

Some concepts did not consider the fields (electromagnetic, gravitational and others) as a kind of matter. So hypotheses, and even successful experiments on transformation of "non-material" type of energy in energy of material object (into the work) were not taken into consideration. The physics is a study about measurable and tangible quantities. New measurement methods let us work with a new physical phenomenon. So, we can see that **real situation in alternative energy is changing due to experimenters efforts** but not from the great theoretical team.

Some time ago the electric energy was not considered as a material object, but gradually people have been able to refuse the gas pipes, which were real material source of power for the gas light lamp, in favor of electric wires for electrical illumination. In a short time, I think, it will be possible to refuse the wires and we'll consider the aether (physical vacuum) as unlimited energy source if we organize **the process of transformation of space-time parameters.** It will be necessary to drop the old conception of "primary source of power", which should be connected with the consumer by some method and to develop conception of free energy source in any place "on-demand".

Let's consider, what the term "free energy" means today. The energy in general sense means the "ability of body to produce some work". The energy of closed system is constant. Certain device can look like "perpetual mobile", but nobody will be shocked because the way of energy "inflow" is known. For example, solar panel battery is obtaining its power from external source of light. But in general case, 3-dimensional observer can see nothing similar to the inflow of energy into the system if multi-dimensional energy balance is not analyzed. In other words, "perpetual mobile" is a right name since for its description it is necessary to use notions of "Time", "Eternity", "Causality" and other categories, which are more related with philosophy and religion but not with modern physics.

The "perpetual mobile idea" is really value to be the purpose of serious scientific work. In the book "Great experiments in physics" published by "World", 1973, Professor G. Lipson wrote: "Joule was the person of a very practical kind of mind and he was enthusiast of the perpetual mobile idea". I hope that it is not necessary to explain here who was Joule. However, "practicality" of free energy generators is obvious only for energy customers, but not for energy producers, who created the centralized system of energy distribution. This is the main reason of absence of alternative fuel-less energy systems in the modern market.

Let's consider the existing classification of "perpetual mobiles":

1. "Perpetual mobile" of the first kind is a design, which can "create energy". It is disputable aspect and all patent offices refuse to consider the patent claim of such type. They answer that "energy can not be created or destroyed" but energy can be transformed from one type into another type.

2. "Perpetual mobile" of the second kind is the collector of environmental heat. It is not a "thermo-pair" which uses temperature difference to produce electricity, but it is the "heat pump". This type of devices works with negative entropy, or more exactly, with sintropy. The terminology still is not defined but we can say that in entropy systems the produced work is equivalent to the dissipated heat and the work, which is produced by sintropy systems is equivalent to some absorbed environment heat.

3. The "perpetual mobile" of the third kind is a demonstration of perpetual motion without friction. The analogue is electric current in superconductors. Development of this idea is creation of systems with negative friction. In electromagnetic systems it corresponds to the known cases of the "negative conductivity", i.e. some electrical circuits in this mode can generate output power.

Additionally, let's show that "creation of energy" is possible in theory, for example: two processes of equal power compensate each other $A + B = 0$. Let's assume that some technology creates another (inverse) process as: $0 = A + B$ i.e. two processes of some power in sum create zero result. In general principle, also there is possibility to use many processes balanced situation as $A + B + C + \ldots = 0$ and this interesting conception is known as theory of multipolarity.

Let's consider some quite real (to my mind) examples from the history of development of free energy technologies. Nikola Tesla's investigations are not well known to modern scientists and engineers. In his works on development of wire-less telecommunication Tesla used flat spiral coils as a secondary winding of transformer. The magnetic field of such coil is radial and it is placed in the plane of the coil. In 1995 the author of this article experimented with similar flat spiral coils. I have to claim that when such coil is operating as secondary winding and the solenoid is the primary winding of the transformer then we can measure asymmetrical mutual induction, i.e. connection of active load (lamp) to output circuit of the transformer is free from input power in the primary winding. It is the simplest example of technical realization of the asymmetrical cause-effect connection, described by Kozyrev in his theory of active properties of time.

... "creation of energy" is possible in theory...

Another Tesla's invention is his resonance transformer. Modern electrical engineering describes transformer with forced electrical oscillations and radio engineering considers operation of resonance systems mainly. Tesla put the question on transformation of power in resonance transformer and by this way the efficiency can be more than 100%. With high frequency currents and high power level Tesla used single-wire terminals as loads, i.e. the lamps and other single-wire receivers of power (motors) were powered from high frequency changing electric field. Such single-wire terminal does not consume any power from primary source because it uses the change of potential in point of connection to conductor (let's note also that for maximum efficiency this point of connection should be one of the maximums of standing wave).

The notion about "free vibrations" belongs to Tesla and this term describes sinusoidal oscillations in electric circuit that is created after short non-sinusoidal impulse due to real vibrations of the free electrons. Resonance mode of the free vibrations can be the real way to excess power output.

Original Tesla's approach to electrodynamics allowed him to build in 1934 fuel-less car with electromotor, which was powered from some 12 vacuum tubes generator of unknown design.

The standing waves of electric field that were observed by Tesla during thunderstorm brought him to conclusion about possibility of the system to power remote energy consumers from energy generator without any transmission lines and without radiation methods. He assumed that it is necessary to create special standing wave of electric potential (or variable in time electric potential field) around the generator, then the unlimited number of loads (lamps, motors) in area of this potential field can be powered if they are tuned in resonance with oscillations of the generator. Let's notice that in each receiver the power can't be more than power of this generator but it is possible to install many independent "receivers" without mutual interference.

The modern investigations on these problems sound as sensation, because Tesla's works are unknown for the modern generation of scientists. Of course, modern electronics components and the tools facilities allow to create real "miracles" in comparison with the past age experiments. For example, engineer Avramenko described his work on single-wire power transmission in Journal of Russian Physical Ideas, 1991, No.2, and in journal "Inventor and rationalizator" 1992, No. 5, 6. The light bulb (or ventilator) was used as load of the single-wire power transmission line. This line can be made of high resistance material, for example, tungsten, but the power can be transmitted without heating of wire! It is possible to say that in this experiment a wire does not transmit power from the generator to the load, but the wire is the conductor of information signal, which is created by polarizational current opened and described by M. Faraday.

It is not difficult to repeat the experiments with single-wire line: it is necessary to place two diodes on the end of a line, which is connected to secondary windings of high voltage transformer (I used television set high voltage unit) by such a way that different poles of the diodes are connected to the line, Fig.3.



Fig.3

Two other poles of diodes create the source of potential difference (voltage), from what it is possible to charge the capacitor or to power the load (luminescent bulb). This diodes scheme is named as "Avramenko's diodes plug". In my experiments it was determined that high efficiency mode is resonance mode in real line and in this case the maximum change of potential is created in the point of connection of the "Avramenko's diodes plug". There is well known formulas to calculate this resonance as quarter-wave antenna vibrator system. Of course, high frequency and high potential allow creating high power in the load. In 2001-2003 New Energy Technologies magazine have published new experimental results on single-wire power transmission reported by research team from Moscow (Prof. Strebkov, Avramenko, Nekrasov and others). For example, they built and tested lines from 20 to 100 Kwtt power level!

... the electric potential field can create non-compensated force in the system and to produce a work without any power input.

One more well known researcher on the subject of free energy was Thomas Townsend Brown. He considered creation of reactionless propulsion force by means of electric forces only. Ionization is not considered here! According to his works, the electric potential field can create non-compensated force in the system and to produce a work without any power input. English patent by T. T. Brown #300,311 of August 15, 1927 describes the method to create propulsion force and power from electric energy source only. In this first patent it was claimed that in ordinary flat electric capacitor (two flat plates and dielectric between them), which is charged up to 50 kilovolts and more, Brown discovered propulsion force. This force moves the capacitor to positively charged plate direction. It is only one of his ideas and in his other patents of 1930 - 1965 Brown has described many new methods to create propulsion force and free power in load by means of electric field only (scalar potential field as a source!).

... the efficiency of "electric system can be million to one"

We have to exclude ideas on electrokinetic apparatus since it is just a reactive method and propulsion force is result of ionization flow. Especial case is Brown's **idea to create the asymmetry of electrostatic forces** by means of some special form of surface, USA patent #3187206 of June 1, 1965, application of May 9, 1956 (Fig 4).

The schemes and descriptions by the Brown's patents are undoubtedly the work of great practical value. As was mentioned by Brown, the efficiency of "electric system can be million to one" because the potential field can produce real work, for example, rotate some electro generator, but it does not change the primary source of field.

In 1927 T. Brown demonstrated the devices in Ohio, later he worked in France. His works in France were stopped and he returned in the USA. Detailed information on his works can be received from descriptions of patents http://www.soteria.com/brown and from the book “Electrograviticis Systems” by Thomas Valone, Integrity Research Institute, USA.


June 1, 1965
T. T. BROWN
3,187,206
ELECTROKINETIK APPARATUS
Filed May 9, 1958
−
+
+
+
power supply
power
supply
+

Fig. 4

Electrokinetic apparatus by T.T. Brown

Besides, there is the simplest example of creation of real work by means of potential field that is also resulting from the Brown's works. Usually two plates of electric capacitor are equal to each other. However, if one of the plates is small and another one is large then the electric field between them is not isotropy field and in this case there is some **gradient of intensity of the field**. In such field any dielectrical object, for example a ball, will be polarized unevenly and due to this fact some force should make it to be moving aside, where the field has the greater intensity. I have to note for mathematicians that since the intensity is "gradient of potential" then gradient of intensity is the **gradient of the gradient**, i.e. it is the second derivative of potential. This idea is an example of the well-known rule: the change gives the new quality.

The example of creation of the propulsion force by means of potential field is also connected with "perpetuum mobile" task, since conductivity currents in the capacitor are very small and it almost does not require power consumption (after being charged once time) and the system can produce mechanical work permanently, in this case it is the work against the gravity force. In general case, if the design allows asymmetrical energy transformations, then the surplus output power and reactionless propulsion force can be created in this system.

Most likely future aerospace systems, which are based on the electrogravity, are the most perspective direction of free energy technologies. Why not for the power engineering? It is clear that now there are some existing fuel heating systems, heat stations and power industry to provide by some traditional way all current needs of the society and due to this fact the innovation of any free energy technology is related with hard competition. However, for commercial programs for cosmos the reactive rockets principles are not acceptable more. Each satellite during its operation should produce profit to compensate large expenses for the rocket-carrier. Only fuel-less propulsion systems can allow developing space commercial programs that are new infinite market. Let's note that the gravitational (reactionless propulsion) technologies are not related with cosmodrome and their cost can be quite acceptable to realize the project with private funds.

... future aerospace systems, which are based on the electrogravity, are the most perspective direction of free energy technologies.

There are some known examples of free energy systems.

In 1921 The Seattle Times, as well as Denver Post of August 8, 1921 published the articles about inventions of Alfred Earl Hubbard. His device included the central core with coil and eight remote coils placed around the central core. After primary impulse, the impulses in all coils were powered and rotating magnetic field was created in central coil. The power produced in the central coil was quite sufficient for self-excitation of the system and for producing of useful work in the load (motor). The boat and the car with electromotor, which was powered from the Hubbard's generator, were demonstrated.

In 1928, Lester Hendershot invented the electric generator of 300-Watts power. This device was designed of details used in radio-receiver to get oscillator (500 kilohertz) and non-inductive coil. Later, in 1970, William Cooper experimented with non-inductive bifilar coils. He used induction phenomenon in the case of zero magnetic component (two-wire winding or flat spire coil).

The Cooper's USA patent 3610971 of 1971 describes **the principle and the device to create power in secondary circuit without reaction on primary circuit**, as well as method to get reactionless propulsion force for aerospace application. Cooper also has found that specially designed coils can produce the field, which can not be screened and this field has some common parameters with the gravitational field.

The gravitation is considered by Cooper as a polarization of atoms in gravity field of planet. So he declares in description of his patent: "the electronic generator... of super high frequency creating the pulsing electric field of single polarity... acting in opposite direction to the Earth gravitational field... that to depolarized the atoms and to release them from the gravitation".



Fig.5

By the way, the gravitational field itself can be used to get a power. "Unbalanced wheel" is a well known design. The weights on the one side of the wheel, which is rotating in vertical plane, can be organized to be moving to axis, but on the another side the same weights can be organized to be shifted from the axis to the periphery of the wheel. By this way there is some constant shifted center of gravity in the system and it can be permanently rotating system. One of the inventors who built such wheel is Hugo R. Fraga, Havana, Cuba (The Perpetual Motion Mystery. R.A. Ford, Lindsay Publications Inc., Bradley, IL 60915, USA, 1987, see Fig. 5).

The earliest information about such systems is dated of 1150 and the name of inventor is Bhaskar, India. He used the tangential disposed pipes, which were half-filled with water. In France (1235-1240) William de Onnecure demonstrated self-rotation wheel with seven weights. In Italy (1438) Mariano de Jacopo has built the system made of eight bars disposed in the plane of rotation, and the bar can be fold up in the middle like elbow joint to provide rotation. One of the well-known and documented events of real demonstration of perpetual rotation wheel was mentioned in 1620. Edward Somerset (Second Marquis of Worcester), author of the book "Century of Inventions", 1963, has built and tested the wheel of about 4 meters in diameter, 14 weights of 25 kilograms each. The test of this machine was organized in London, in witness of King Karl, Grand Duke Hamilton and Grand Duke Richmond, and there are files in royal archives about this test. The descriptions of these and other systems are published in the book "Perpetual mobiles: past and present time" by Brodiansky, Moscow, Energoatomisdat, 1989.



Fig.6

In different idea, which is known from Leonardo Da Vinchi drawings, lifting of water is produced by the helical "Archimedes' screw" of small diameter with large centrifugal acceleration, which reduces weight, but lowering of water was organized with the screw of other (large) diameter, so the force of weight is working to rotate this screw by the weight of the falling water. The paradox of these systems will be removed if to consider them as systems of variable topology, as it was done at the beginning of the present article. Practically, the **cycle is separated here into two processes** (the lifting and falling of mass) in the system with different parameters (the topology) for the first stage and the second stage of the cycle, but herewith **it is necessary to consider two different physical systems, not one and the same.** In that case, the classical theory can explain the work created by potential gravitational field of our planet as energy exchange between two different systems.

Other well known topic is research projects by John Searle, i.e. the "Searle's disks" (Fig. 6). It is necessary to note that the inventor mentioned in his articles anti-gravitational effect and free energy output also. The address is: John Searle, 13 Blackburn Lower Strand, Graham Park Estate, London MW9 5 NG, United Kingdom.

In several words we can say that rotor makes free electrons to be displaced to the peripheries of the system. With sufficient velocity it was mentioned that there is phosphorescence and ionization around the disk. It is possible to assume that main effect is based on well known Lorenz forces and understanding of the Poynting vector, which is circulating in this system. The ionization currents are closed through the space from periphery to the center, and self-rotation of the disk is provided by the classical Lorenz force, since the current interacts with magnetic field of the rollers.

In Russian experiments of 1992 Roshin and Godin built similar system of 7KWtt power output and they claimed that 100 kg axial force and areas of decreased temperature in environmental also were detected. Fig.7 demonstrates main parts of the system by Godin and Roshin.

It is necessary to note that similar anti-gravitational effects appearing for the case of over-unity operation were observed by different inventors independently. For example, in 1990 Floyd Sweet demonstrated his invention named as "vacuum triode amplifier" VTA. The barium magnets were pre-conditioned by special method to be used in special "trigger mode". This "bi-stable condition of magnet" provides possibility of transition from one direction of field to another direction due to the weak control signal, which was provided from external generator. It is known that if the material was pre-conditioned by the magnetic switching of 60 Hz frequency then its control signal must have the same 60 Hz frequency. A part of output power was closed to provide feedback and additionally some power can be used in output coil for the load. Tom Bearden studied the scheme of vacuum triode amplifier and confirmed that it demonstrates the work with negative energy. It means that the work in the load is connected with use of negative time. In this negative time, according to Bearden, the gravity is repulsing force. The experiments on VTA demonstrated that VTA decreased its weight according to level of the power, which is extracted from vacuum. Additionally we can



Fig.7

say that permanent magnets and coils of VTA were self-cooling during operation and the temperature difference was about 20 degrees in contrast with the environmental temperature.

One of VTA schemes includes two sets of magnets 4 x 6 x 1 inch, placed on two walls of frame. The attraction is created between them. Output and controlling coils are located between them. The axes of output coils are parallel to the magnetic field lines, but the axis of control coils are placed under 90 degrees angle. The secret of system is the "conditioning process", which "brings the magnets to the special condition". It is necessary to create great number of micro-cracks in the magnet due to re-orientations of magnetic domains. In such "half-magnet" the domains get the ability to be orientated in the same direction in a weak "control" magnetic field. In fact, they are not domains but large parts of magnet's material, separated by micro-cracks, that is to say acoustic domains. Many researchers repeat Floyd's works. Let's note that arc discharge of alternating current through magnet barium ceramics directly can provide the best results of the "conditioning" process. The coil of "conditioning" is not necessary in this case. The frequency of alternating current must be corresponded to the frequency of the control signal. Thereby, Sweet was creating **the bi-stable solid-state condition of magnetic substance.** The acoustic resonance is the reason of oscillations with the frequency according to the control weak magnetic field. Floyd Sweet died on July 5, 1995 at age of 83 years old. It is known, that his widow sent the archives to some great Automobile Corporation.

... the extraction of space energy is result of transformation of vacuum energy but from the other hand the energy density in this case determines so called "time rate"

It is interesting to note again that the magnets of VTA demonstrated self-cooling during operation, up to 20 degrees difference in comparison with the environmental temperature. It is one more example of relation between notion "density of time" and "energy". We can say that the extraction of space energy is result of transformation of vacuum energy but from the other hand the energy density in this case determines so called "time rate".

Kozyrev's articles [4] on causal mechanics theory and experiments describe possibility to use "time course for producing of useful work". Kozyrev introduced notion "density of time" and he demonstrated experimentally several methods how to change the density of time, which depends on irreversible processes intensity. Powerful "generator" of such processes is biosphere of our plane and it creates **season and daily changes of the density of time**. It is known that VTA power output also was variable in different time of day and night. It can be explained by Kozyrev. Next step in logical development of this idea is **to change notions from the "density of time" to "density of aether"** [10].

Relation between magnet phenomena and aether circulations was known from the beginning of the electrodynamics and now we can assume that VTA was real example of asymmetrical cause-effect connection, where the hardness of this connection depends on the density of aether. In this case the season and daily variation of the aether density are reason of VTA output power variations. So, we can make a conclusion: conception of **asymmetrical cause-effect connections** should be used as theoretical basis of all over-unity systems.

Generation of extra power in nonlinear materials (ferrites and dielectrics) was considered by Nikolay E. Zayev, Journal of Russian Physical Ideas, #1, 1991. Discovery was claimed as "Cooling of some dielectrics by changing electric field with generation of energy", Russia discovery #32-OT-10159, November 14, 1979; the inventions were also claimed as "Method of transformation of heat energy of dielectrics into electric energy", Russian patent claim #3601725/07 (084905), of June 4, 1983 and "Method of transformation of heat energy of ferrites into electric energy", Russian patent claim #3601726/25 (084904), of April 3, 1983. This theory is not about some transformation of space-time structure but in any case the practical application of conversion of environmental heat is very important because this work is real basis of free energy systems.

In one of Zaev's articles, which were published in Journal of Russian Physical Ideas, he quoted from K. Zialkovsky: "If the heat can be transmitted from cold body to hot body, then it must have enormous importance, and not only philosophical or scientific, but also practical importance. The Clausius postulate is not confirmed in this case. The gravitational force, as well as other reasons (number of the reasons is unknown) break this postulate... heat can be transmitted from cold body to hot body but only as the result of some exclusive conditions", published in Russian, "The Second beginning of thermodynamics", Kaluga, Russia, 1914. So, the inventor of free energy system should provide this "exclusive conditions" to organize collection and transformation of environmental heat in his free energy system.

Another well-known free energy system is Swiss electrostatic machine. In spiritual commune Methernitha, Linden in Switzerland, since 1980 several free energy devices have been generating total power of 750 kilowatts. From the technical point of view, these devices are modernized electrophore generator. Permanent magnets also included into design of these devices. The machine of 20 cm diameter produces about 200 watts, and a big machine has the disk of 3 meters and it produces about 30 kilowatts, Fig. 8.



Fig.8

One of the modern technical decisions, which are very close to this Swiss machine is patent USA No. 4897592 by William Hide, January 30, 1990. This device is "system to generate power from electric field". It is one more example of work, which can be produced by potential field, in particularly by means of electric field that can be used as free source of power. The energy (the potential energy) is the possibility to produce work and the power is a work per unit of time, i.e. it is a process. The properly organized process, for example acceleration of rotor in Hide's machine, uses the potential field on the part of positive work (acceleration) and the author of the patent provides meta screen on the part of the trajectory, where the field decelerates the rotor.

... it is "perpetuum mobile" and it can not be patented even if it really works!

One more example is Reed's motor, which uses energy of permanent magnets. By the description of 1991 it is made of four disks (two immovable discs and two rotating discs), and eight magnets are placed on them. Howard Johnson used similar method, USA patent #4151431, Fig.9



Fig.9

Journal "Science & Mechanics" of 1980 describes this invention. Hovard filled the application in 1973 but he has got the confirmation only in 1979! The reason of delay is very clear: it is "perpetuum mobile" and it can not be patented even if it really works! Johnson found clear and simple description of generation of power in his device and explained it as "extraction of power from inner energy of electron spin in ferromagnetic material".

From text of his description it follows that USA patent #4,151,431 of April 24, 1979, "Permanent magnet motor", author Howard R. Johnson, application #422,306 December 6, 1973 was developed from the prototype that is USA patent #4,074,153 of 1978, class of international classification H02K 41/00E:

"The invention is directed to the method of utilizing the unpaired electron spins in ferromagnetic and other materials as a source of magnetic fields for producing power without any electron flow as occurs in normal conductors, and to permanent magnet motors for utilizing this method to produce a power source. In the practice of the invention the unpaired electron spins occurring within permanent magnets are utilized to produce a motive power source solely through the superconducting characteristics of a permanent magnet and the magnetic flux created by the magnets are controlled and concentrated to orient the magnetic forces generated in such a manner to useful continuous work, such as the displacement of a rotor with respect to a stator. The timing and orientation of magnetic forces at the rotor and stator components produced by the permanent magnets to produce a motor is accomplished with the proper geometrical relationship of these components."

...conception of asymmetrical cause-effect connections should be used as theoretical basis of all over-unity systems.

It is reported that functioning Johnson's model produced about 5 kilowatts power free of any primary source of energy. Let's note that Johnson writes in his patent about permanent magnet as about system with "super conductive parameters". The currents of electrons in permanent magnet are manifestation of real superconductivity and for this case it is not necessary to provide the cooling for zero ohmic resistance. Moreover, the "resistance" must be negative since the magnet could save and renew its magnetized condition. Thereby, any permanent magnet is the example of perpetuum mobile of the third kind on the micro level. Also we can say the same about each atom.

Also, let's note that in general case motion (rotation) can be created due to the discussed above gradient of field, which in Johnson's device is result of asymmetry in "rotor-stator" system. By the similar way the gradient of velocity of airflow above and below wing creates the gradient of pressure and this fact produces great lifting power in airplanes.



Fig.10

Well-known variant of permanent motor-generator is Adams motor, Fig.10. The rotor with radial orientated (the same pole outward) permanent magnets is rotating and creating inducted currents in stator coils, which are placed around rotor in the plane of rotation. From the point of traditional electrical engineering, any motor-generator without closed magnet flux is not high efficient device. However, exactly open magnetic flux of the Adams motor allows to take off power without deceleration of the rotor. We can assume that in this case phenomenon of electromagnetic induction is not important but in this design there is magnetic induction only, i.e. magnetization and demagnetization of cores in the field of the moving magnet. It is a perfect analogy with phenomena of electric induction that is "electrization by influence". Similar "magnetization by influence" differs from electromagnetic induction and secondary magnetic field in winding of generator is not related with deceleration of the rotor. Robert Adams works with Harold Aspden under patenting of their system. Adams is more than 70 years old but from our correspondence with him we can say that he is going to build demonstration version of 10 Kwtt generator.

...any permanent magnet is the example of perpetuum mobile of the third kind on the micro level.

There is also special name "alternators" for this class of devices, which use interruption of magnetic flux, for example it is the device by USA patent of John Echlin #4567407.

The experiments to investigate the alternator principles were organized also by the author of this article and it was demonstrated that ferrite core of the generator coil is self-cooling. The simplest experiment is based on electro motor, which rotates iron plate and it periodically appears in the gap between magnet and coil. But it is necessary to note that change of the flux in the coil area should be organized by such a way to decrease the flux of the field in the rapprochement half-cycle and to increase the flux for the moving off half-cycle. In this case the rotor is accelerated by the secondary field (back-EMF). From 1994 to 2003 several experiments were produced and main principles were claimed in the patent description, Fig.11.



Fig.11

One more topic is "extraction of power from air" and Josef Swenson has conducted the series of simple experiments to develop it. The frequency of natural pulsations of electric field of planet is about 7.5 Hz and it is well known from Tesla's age. Swenson works with frequency 375 kilohertz and antenna of 10 meters. Please, contact for more details: Josef Swenson 423 North 15th Street, Moorhead, Minnesota 56560, USA. However, everybody remembers from the school story about simplest electrical experiments by Lomonosov and Rihman, who investigated arc discharge in gap between iron wire from a roof ("antenna") and ground wire. Let's include the resonance circuit "inductance-capacity" and diode rectifier to get some useful work in the load "from atmospheric electricity", Fig.12.



Fig.12

In 1900-1930 a lot of articles were published in technical press about Henry Moray. His demonstration systems produced more than 50 kilowatts free power output. It is known that Mr. Yakovlev (from USSR Foreign Department headed by Mr. Molotov) visited Morey in November of 1929 in New York to test his devices. The devices consist of capacitors, coils and special electronic-vacuum lamps.

In 1990 journal "Magnets", 2 (3) published article, which describe analogy between Moray's devices and Hubbard's coils, which can extract power by means of inner energy of nucleuses of materials if special resonance is created. In 1978 Cospray Research Institute has published the well-known book "The Sea of Energy" by T. N. Moray, in which theory of Moray is presented most completely.

RQM Raum-Quanten-Motoren Corporation (Schmiedgasse 48, CH-8640 Rapperswil, Switzerland, fax 41-55-2125209) offers for free energy devices of different power level: RQM 25 kilowatt and RQM 200 kilowatt. The principle of work is based on an invention by Oliver Crane and his theory. Web site http://www.rqm.ch. But I have to note that in present time they are developing capitalization of the company mainly (actives are above 650 million dollars) than innovation of the new technology.

One more historical example: in 1925-1945, Hans Koler demonstrated his free energy devices. The system was built in Germany and it produced 60 kilowatts of free power. The description includes six permanent magnets and coils, which were superposed in plane of hexagon form. Each magnet is core of the coil.

Another interesting topic is unipolar induction effect, which is well-known from Faraday. This effect creates electro motive force (EMF) in rotating disk if axial magnetic field is applied to the disk. One of the well-known practical developments in this area is device by Bruce de Palma. In 1991 he has published the results of his tests, from which it follows that deceleration of the rotor due to back EMF in the case of unipolar induction is less than in traditional electro generators. So output power of system can exceed the power, which is necessary to rotate the rotor.

Really, motion of electrons in magnetic field, which is perpendicular to plane of rotation, is the reason of the Lorenz force and this force acts in radial direction that can not be the reason of deceleration. Indian research on this topic is developing by P. Tewari. In New Zealand there is research group headed by Dr. Ashley Gray. In 1994 the leader of Japanese market MITI published report about progress in 40 KWtt unipolar generator, which uses superconductors for its electromagnets. The interest of Japan to alternative energy projects can be explained by the position of Japan on fuel market.

There is a well known rule: Demand is related with Proposals. It is easy to imagine the prospects of local introducing of free energy systems in one or several countries, if some producers of product will be able to exclude expenses on electricity and fuel from cost sales. Other countries of their own rich natural resources (for example, oil) will be in problematic position on the new international market, mainly due to the fact that their industry and transport are oriented to conversion and consumption of oil fuel that increase the cost of all products.

... increase of the spark gap produces more surplus power in the load of the circuit.

One more modern free device was invented by Wingate Lambertson, USA. In his device free electrons get the additional energy passing through the number of thin metal-ceramic composed layers. The units were designed by the authors and each unit can generate 1600 watts, and it is possible to connect them in parallel. The address of author: Dr. Wingate Lambertson, 216 83rd Street, Holmes Beach, Florida 34217, USA.

Especially the researches on free energy with plasma processes should be noted here. In 1980-1990 Alexander Chernetsky, Yury Galkin and others have published the results of experiments on creation of "self generated discharge" SGD. The electric arc was placed consecutively into secondary circuit of electromagnetic transformer and it produces real increase of power in load and reduction of consumption power in primary circuit of transformer. The author of the present article produced simplest experiments to investigate the arc (electric discharge) in electric circuits and possibility to create the mode of "negative resistance" in this circuit was confirmed. One of the effects was demonstrated in 1996 during the conferences "New Ideas in Natural Science", St.-Petersburg.

Adjusting parameters of arc (distance between two electrodes) it is possible to see that consumption current is decreasing until zero and then it can change its direction i.e. this system begins to generate the power. During similar experiment of 1971 by Dr. Chernetsky substation transformer in Moscow Aviation Institute was destroyed in result of strong "reversed current" impulse, which exceeded consumed power in 10 times more. According to Chernetsky's concept, the reason of this mode is well known phenomenon of plasma instability and **pinch-effect for great currents.** However, the author of this article tested device, which demonstrated similar effect (switching on the load in secondary circuit of transformer and in the presence of arc in this circuit, consumption power does not increase, but reduces) for small currents about 300 mA.

Since for pinch-effect it is necessary hundreds Amperes then it was offered another explanation: the surplus power in this circuit appears due to the acceleration of electrons in the gap between electrodes, i.e. particles of plasma are **accelerated by means of electric potential field between two electrodes**. It is noted during the experiments that increase of the spark gap produces more **surplus power in the load of the circuit.** To avoid mistakes the measurements of the consumed power were organized in DC (direct current) battery circuit and therefore there is no any reason to speak of phase shifts mistakes to try to explain skeptically this effect.

... waves of density of time are used by organisms for their vital activity.

Today theory and experiments on self-generating discharge are quite well developed to build free energy systems of any power scale. The reason of delay in its practical development is a complex problem: this work leaves the frames of classical physics. In his book "About physical nature of bio-energy and its simulation", Moscow, Publ. VZPI, 1989, Dr. Chernetsky considered the structure of biological fields and bio-energy processes in living organisms from the point of **longitudinal waves conception.** Self-generating discharge in the mode of negative resistance produces such longitudinal waves and they are self-sustaining (self-powered energetically) and it is considered as field of living object.

Really experimentators of the Chernetsky's group, who worked with SGD device detected influence of biologically active radiations and fields, which can be not screened by usual methods. It was reported by Chernetsky that parameters of this radiation can be selected to accelerate the development of plants and biomass or to suppress it. So, we should speak about artificial living biological system or biological form of energy for this class of free energy devices. Perhaps by the same plasma oscillation way all living organisms provide its vital activity, since long time ago it was known that metabolism and food can not provide enough energy for vital processes.

Nikolay A. Kozyrev also wrote about "reason of life" and he confirmed that waves of density of time are used by organisms for their vital activity. Between "waves of density of time" and "waves with longitudal component" there is a clear analogy. Kozyrev and Chernetsky experimentally demonstrated methods of creation of such waves.

...any free energy system should change the causality in surrounding space-time.

New Energy News magazine, March 1996, wrote about attempts to innovate for American aerospace stations special power source, which uses similar plasma technology: anomalous electric discharge. The USA patents #5416391 and #5449989 belong to Dr. Paulo Correa and Dr. Alexandra Correa, Canada. In their report on free energy Denver conference it was claimed that efficiency is about 483% .

Let's note one more free energy topic: high efficient electrolysis. Classical electrolysis as decomposition of electrolyte in electric field is a wonderful example of work, which is produced by field and it can be organized by such a way to be free from the primary energy source (battery). The traditional scheme uses closed circuit of current through electrolyte and the battery, so the battery is discharged during the operation with electrolytic cell. However any physics textbook confirms that **ions in electrolyte are moving due to electric field only, i.e. work to organize the displacement of ions and heat power, which is connected with this work, are produced by the potential field and expenses of the primary power are not required.**

The current through the battery, which is created in usual closed electric circuit destroys the primary difference of potentials in the battery but it is not some necessary condition. For correct organization of the experiment the products of electrolysis (gases) can be created almost free and their utilization (burning) can provide more heat power than input electric power.

Prof. Latchinov, the real member of Russian Physic-Chemical Society, who patented his method of electrolysis in 1888, mentioned that in some cases the electrolytic cell is freezing during its operation. This is an effect of the law of Conservation, which forces to return the surplus power by means of heat environmental energy. In the experiment by Latchinov the electrolytic cell can create gases of high pressure and consumed power is the same as for the case of low pressure gases. However, it is clear that high pressure gases can produce more work than low pressure gases do. This question was sensational problem in scientific societies of 1888 and it is not solved yet completely.

One of other variants of high efficient electrolysis was investigated by Igor Goriatchev, Russia. Instead of usual 3 Volts level of electrolysis, Goriatchev uses 0.2 Volt pulsing mode. He claimed ratio output/input as 1500% efficiency and he hopes to increase this value twice in more perfect design.

Professor Kanarev from Krasnodar wrote about his experiments on plasma electrolysis and has proved that in electrolysis of water output power can be more than input power.

Real example of "perpetuum mobile of the second kind" is invention by Russian engineer Albert Serogodsky (Moscow) and German engineer Bernard Sheffer (Berlin). They have patented new system for direct transformation of environmental heat into electricity, Germany patent #4244016. Retro-condensation of mixture of benzine and water is organized in closed system under temperature of 154 ^{0}C degrees. You can try to get more info from: Werkstatt fur Dezentrale Energleforschung, Pasewaldtstrasse 7, 14169 Berlin, Germany.

The fundamental theoretical researches on direct transformation of environmental heat to useful work were provided by Real Member of The Russian Physical Society Mr. Gennady N. Buynov, St.-Petersburg. The description of his project on "The Mono-thermal device" was published in journal "Russian Ideas" #2, 1992.

In 1995 the scientific journal of Russian Physical Society #1-6 published article "Perpetuum mobile of the second kind (paired gas-chemical cycle)". The author Gennady N. Buynov proposed to consider that **entropy function can be abortive**, i.e. it can be undetermined in some place if reversible chemical reactions are presented in the system.

Herewith, the circular integral of entropy is not a zero and in this case the heat function but not entropy function (according to the Gess law) becomes the function of condition.

Buynov offers to use four–oxide of nitrogen as working matter for this cycle. His works are excellent example of scientific enthusiasm, which (in combination with financial interest of the customers) could produce real results for Russia many years ago. Let's note that priority of this discovery belongs to Russia in spite of attempts of other scientists to claim and develop this idea now as their own work.

We can make a very interesting conclusion if we analyze history of so called "cold fusion" discovery. According to de-classified materials of 1960, priorities of Russia in this topic are obvious. In 1989 Pons and Fleshman have reported about results of their experiment. In 1995 Russian Journal "Inventor and Rationalizator", #1 has published article about invention made by Ivan S. Filimonenko that was named in 1957 as "warm nuclear syntheses". In 1957 he detected **extra power output in process of heavy water electrolysis** and he mentioned several applied aspects, for example, propulsion force and possibility to reduce radioactivity by means of this process. In 1960 Kurchatov, Korolev and Zhukov have supported the ideas of the author. Russian Government adopted secret resolution on this work:

1. Investigation of energy generation.
2. Development of propulsion without reactive mass flow.
3. Research on protection from radioactivity.

But in next several years this work was suppressed by people of nuclear power plant team. The only system of such type named as TOPAZ was innovated for Russian aerospace systems. World-wide innovation of this technology is a real way to introduce "warm reactors of syntheses" and it is not necessary to wait for results of high-cost "Tokomak" project and other thermonuclear researches. Let's note that secondary effects (propulsion force and influence on radioactivity) are possible due to using of "free energy" aspect if output power is result of change of space-time parameters.

In 1994 Journal "Russian Ideas", #1-6, it was published an interesting document "Conclusion of The Moscow City Council Commission on the question about Ivan Filimonenko's discovery and its development". In this document it was recognized that it is vitally necessary to renew this works. But in 2003 we still have nothing new on this topic. Why? It can be assumed that the Problem of innovation for this technology is possible military application of the methods since influence on radioactivity (for example, remote reduction of radioactivity of some object) is area of interests of the Defense Department. The fact that energy generators by Filimonenko can be used for quick restoration of the present ecological balance is not so important in this case. The same conclusion is about propulsion method, which was proposed by Filimonenko. Mr. Korolev knew about this method; however present space programs are still based on rockets and reactive principles, and anti-gravity flying machines we can see only in fantastic movies.

At the same time, development of commercial cold fusion projects was started in some countries, for example: Patterson Power Cell is introduced in Texas, USA (Clean Energy Technologies Inc., Dallas, Texas, fax 214-458-7690). More than thirty patents were owned by ENECO Corporation, which is collecting the main technological solutions in this area. The production of electrolytic thermal cells was started by Nova Resources Group., Inc., Colorado.

In August of 1995 Atomic Energy of Canada, Ltd. Company, which is member of The Planetary Association for Clean Energy, has published the review on modern methods of conversion of nucleus wastes and deactivation. Two new technologies were offered for introduction: contact processing by "Brown's gas" and remote processing by scalar (torsion) fields. Let's note that the technology proposed by Canadians and Filimonenko's technology demonstrate the effect of influence on the rates of radioactive decay.

These examples are only small part of real situation. Main references on publications are foreign and it can lead to wrong conclusion that Russia is delayed in this direction of new technologies development. In fact, Russia has more talented inventors and researchers than any other country. However, condition for work, patenting and publications of ideas are not the same, and usually Russian technologies cannot reach the level of international market. This problem depends only on real and official state policy with respect to inventors and scientists. In real life financial support of scientific institutes is mainly subsidy for management of the institutes, but not for science. The inventions and discoveries always were made by a certain real person, but not by Institute or some scientific team.

In Russia of last age and in the other world on the whole the institutes and laboratories have been creating for a new scientific problems, discoveries or new directions in science. It was necessary to claim about discovery and provide priority for own country to get official support. Main schools of thought appear by this natural way. By the same natural way the necessary in existing of some scientific institute can be removed when the idea grows up to serial production stage. If there are no any fresh ideas in this school then the institute should be transformed in design office of the production plant on this topic. It is almost impossible to create a new research institute in modern Russia, so really new ideas (if they are not ranged in frames of some existing scientific directions) can not be developed and they can not create a new school of thought in Russia.

... it is possible to make a conclusion about grandiose misinformation of society...

People (carriers of the new ideas) have to leave Russia to realize their sensational ideas on free energy and antigravitation topics. Why they do not work with Russian Academy of Sciences? It is the rhetorical question. Usually after many years of correspondence with patent office or with official science bodies the authors can find that their ideas are published in "serious scientific magazines" but without any respect to their names...

Attachment 1 presents some information about patented technologies. When we study old and modern patent documents, it is possible to make a conclusion about **grandiose misinformation of society**, which leads to appearance of two different Worlds, separated by the level of knowledge: evident and hidden knowledge. The achievements of the second hidden world could change our planet, give a chance to remove all energy and ecological problems. Besides, we have discussed that some free energy systems (for example, self generated plasma discharge) have also the medical-biological aspects. This "influence" from free energy system is related with negative entropy processes in area of the operation of the system so some components of biological systems can be changed to less entropy. The design of free energy system defines the type of this influence. It was noted before that operation of any free energy system should be considered in high topology space-time as multidimensional system to see what the reason of the effect is.

So, since the rate of time course is determined by Nikolay A. Kozyrev as rate of cause-effect transformations, then any free energy system should change the causality in surrounding space-time. In this case we can assume that it creates quantum physics effects on the macro level. It is interesting to assume Heisenberg's uncertainty, tunnel effect and manifestation of wave characteristics (up to diffraction of objects) for macro level.

Some experimental data by Kozyrev is related with quantum effects, which were detected in his experiments with rotating and vibrating gyroscopes. This technology is the basis to design real teleportation systems, which will change parameters of space-time to allow changes of position of some material object from one point of space to another point of space (without transference on the distance between these points) by means of combining these points in the same place of space for some time.

The process of study of new technologies in alternative power industry and gravitation is developing actively in the world. Besides secret programs and institutes, it is possible to make a conclusion that activity of this work in countries of limited fuel resources is more efficient. Now Russia has rich **natural materials and oil resources but in the short time this advantage will not play any role in development of economy.**

Industrial and defense power of any country will depend on free energy technologies, knowledge on the biologically active energy and reactionless propulsion methods.

The new technology creates not only a new technical systems but also **new economical systems**. It is not physics but policy... Development of great Russian territories with industry of free energy technologies for home and commercial application is the way to change world economical balance in favor of Russia. It is difficult to say now what financial-economical group of modern Russia is most interested in development of this direction of science. The purpose of any financial-economical group is power on the market of energy resources, but when the free energy technologies are developing, then people and industrial or agricultural producers will be more independent from centralized system of energy and oil distribution, therefore, they will be more independent from influences of central authorities.

From the point of view of serious business, there is only one real argument in favor of developments of any really new technology: it should lead to increase of profit and expansion of the market. In this sense, it is possible to compare the new energy technologies with beginning of the steam machine age or with appearance of electric machines and illumination. This means the super profits and serious fight with competitors. To develop this way any efforts of scientists are not sufficient work. It is necessary to join them with the efforts of large business structures, which are interested to create new market of energy and power engineering in parallel to present monopoly fuel-energy market or to develop commercial exploration of space by means of new propulsion principles. In particular, telecommunication space satellites and projects on colonization of space could be the nearest commercial directions of the new market.

References

1. Sakharov A.D. "Quantum Fluctuations of Vacuum in Curved Space and Theory of Gravitation", Reports of Academy of Sciences USSR, vol. 12, 1968, page 1040.
2. Puthoff H.T., Ph. Review E, vol.48, num.2, p.1562-1565, "Extracting energy and heart from the vacuum"; Physical Review A, vol. 39, num. 5, "Gravity as a zero-point-fluctuation force".
3. Nassikas A.A., The Hypothesis of the Unified Field and the Principle of its Dual Interpretation, III International Conference "Problems of Space, Time, Gravitation", St.-Petersburg, 1994.
4. N.A. Kozyrev, Selected works, published by Leningrad State University, 1991, p.202, in Russian.
5. Gravitobiology, by T.E. Bearden, 1991, Tesla Book Company, P.O. Box 121873 Chula Vista, CA 91912, USA. Library of Congress Catalog Card Number 86-50553.
6. Hasselberg Josef, New Beginning of Thermodynamics, http://hasslberger.com, Hasslberger, Josef "The inventor and society" in Raum&Zeit #4, October 1989, Hasslberger, Josef "Vortex, the natural movement" in EXPLORE, No.5, Vol.3, 1992.

7. Gustav Naan, Symmetrcial Universe, Tarty Astronomical Observatory, Vol. XXXIV, 1964.
8. New Results of Development and Testing of Single-Wire Electric Power System, Prof. Dmitry S. Strebkov, Eng. Stanislav V. Avramenko, Dr. Aleksey I. Nekrasov, Eng. Oleg A. Roschin, New Energy Technologies, #5(8), 2002.
9. An Experimental investigation of the Physical Effects In a Dynamic Magnetic System. V.V. Roschin and S.M. Godin, New Energy Technologies, #1, 2001.
10. Practical application of time rate control theory. Alexander V. Frolov, New Energy Technologies, #3, 2001.

Attachment 1

Methods and devices to create power without external sources and reactionless motion systems

3913004 October 14, 1975, Method and equipment to increase electric power, Robert Aleksander.
4975608 December 4, 1990, Motor with switchable magnetic resistance, Harold Aspden.
5288336 Converters of heat into electricity, Harold Aspden, see also patents 5,065,085 and 5,101,632
4622510 November 11, 1986, Parametric electric machine, Ferdinand Kap.
2912244 1959, Gravitational System, Ottis Karr.
4006401 February 1, 1977, Electromagnetic generator, V. Rivas
3811058, 3879622 Motors with permanent magnets.
1835721 December 8, 1931, Motor with permanent magnets, A. Povel.
1963213 June 19, 1934, Magnetic motor, G. Pose.
1859643 May 24, 1932, Motor with permanent magnets, G.L. Worsington.
1859764 May 24, 1932, Magnetic device, G. Baugon.
2982261 Mac Klintok's Air motor.
4595843 June 17, 1986, Transformer of rotation magnetic flux, Robert Del Vechio.
4567407 January 28, 1986, Motor - alternator, John Eklin.
3368141 January 6, 1968, Transformer in combination with permanent magnets, K. Garon.
3890548 June 17, 1975, Motor with pulsing capacitor discharge, Edwin Gray.
4595852 June 17, 1986, Electrostatic generator, Robert Gandlach.
4831299 May 16, 1989, Homopolar generator of alternating current, Enakishy Khasaka.
4249096 February 3, 1981, Electric dynamo, Barbara Nikoks.
3610971 October 5, 1971, Electromotive generator of electric field, Williams Couper.
4897592 January 30, 1990, System producing power from energy of electrostatic field, Williams Hyde.
4151431 April 24, 1979, Motor with permanent magnets, Hovard Johnson.
4806834 February 21, 1989, Electric circuit of inductive conductors, transformers and motors, Erl Kening.
3374376 March 19, 1968, Electric generator, Raymond Kromry.
3977191 August 31, 1976, Power source, Robert Brett.
3670494, Method of converting of atomic energy in kinetic energy.
4709323 November 24, 1987, Converter of parallel resonance, Charles Lien.
5146395 September 8, 1992, Power source using two accumulating circuits, Richard Mac Kee.
4210859 June 1, 1980, Inductive device with two orthogonal windings, Paul Meretsky.
4500827 February 19, 1985, Linear electric generator, Thomas Merit.
4904926 February 27, 1990, Electric generator of magnetic motion, Mario Patsishinsky.
4945273 July 1990, High effective electric machine, Josef Pinkertone.
4883977 November 28, 1989, Converter of magnetic power, Dennis Regan.
4077001 Electromagnetic converter, Frank Richardson.
5018180 May 21, 1991, Conversion of energy, Kennet Shoulders.
4652771 March 24, 1987, Transformer, Theodore Speach.
477 2816 September 20, 1988, Conversion of energy, Jefry Spens.
4748311 May 31, 1988, Inverter, Fridrikh-Verner Thomas.
International patent H02K 31/00, 39/00 dated June 24 1982, Closed part of unipolar machine, Adam Trombly.
4687947 August 18, 1987, Electric circuit for conserving of power, Melvin Kobb.
4772775 September 20, 1988, Generation of plasma flux in electric arc, Sam Lich.
The USA patents 5416391 and 5449989, Paulo Correa.
4432098 and 4429280, Transmission of information by means of magnetic vector potential, Raynolds Gelinas.
Great Britain, #547668, January 30 (September 7) 1942, Motor with permanent magnets, Stenly Hichkok.
Great Britain, application # 2282708A, Motor with permanent magnets, Robert Adams, Harold Aspden.
4394230 USA patent, July 19, 1983, Henry K. Pukharich.
2251775 Great Britain patent, April 20, 1994, Thermoelectric conversion, Harold Aspden.
5288336 USA patent, Thermoelectric conversion, Harold Aspden.

The USA patents on electrogravitation

1363037 Goddard, December 21, 1920;
2004352 Simon, June 11, 1935;

2210918 Karlovitz, August 13, 1940;
2588427 Stringfield, March 11, 1952;
2231877 Bennet, 18 February, 1941;
2279586 Bennet, 14 April, 1942;
2305500 Slayter, December 15, 1942.
English patent 300,311 August 15, 1927, Townsend Braun.
French patent 1003484 November 1951, Electrogravitation;
3187206 June 1, 1965, Electrokinetic equipment, Townsend Brown.
3022430 February 20, 1962, Electrokinetic generator, Townsend Brown.
3018394 January 23, 1962, Electrokinetic converter, Townsend Brown.
2949550 August 16, 1960, Electrokinetic equipment, Townsend Brown.
1974483 September 25, 1934, Electrostatic motor, Townsend Brown.

Attachment 2

Organizations

- Faraday Lab Ltd, Lev Tolstoy Str. 7, St. Petersburg, 197376, Russia.
- The Russian Physics Society, 141002, Moscow reg., Mytishy, B. Sharapovskaya str. 3. Fax 095-2926511
- Academy for Future Sciences, P.O. Box FE, Los Gatos, CA 95031, USA.
- AERI, Advanced Energy Research Institute, 14 Devonshire Mews West, London W1N 1Fp, Great Britain.
- ADAS, Association of Distinguished American Scientists, P.O. Box 1472, Huntsville, AL 35807, USA.
- Borderland Sciences Research Foundation, P.O. Box 429, Garberville, CA 95440-0429, USA.
- Center for Action, P.O. Box 472, HCR 31, Sandy Valley, NT 89019, USA.
- Electrodynamics Gravity, Inc., 35 W. Tallmadge Ave., Akron, Ohio 44310, USA.
- Fusion Information Center, P.O. Box 58639, Salt Lake City, Utah 84158-0369, USA
- Gravity Power Research Association, 36 Mountain Road, Burlington, MA 01803, USA.
- GRI, Group Research Institute, P.O. Box 438, Nelson, New Zealand. Dr. Ashley Gray.
- High Energy Enterprises, P.O. Box 5636, Security, CO 80931, USA. Fax 719-4750582.
- Institute for Advanced Studies at Austin, 4030 Braker Lane W., Suite 300, Austin, TX 78759, USA.
- INE, Institute for New Energy, 1304 South College Avenue, Fort Collins, CO 80524, USA.
- Integrity Institute, 1377 K Street, NW, Suite 16, Washington DC, USA. Fax 202-543-3069.
- Orgone Biophysical Research Laboratory, Inc., P.O. Box 1395, E1 Cerrito, CA 94530, USA.
- Quantum Biology Research Laboratory, P.O. Box 60653, Palo Alto, CA 94306, USA.
- SEA, Space Energy Association, P.O. Box 11422, Clearwater, FL 34616, USA.
- Tesla Book Company, P.O. Box 121873, Chula Vista, CA 91912, USA.
- Tesla Incorporated, 760 Prairie Av., Craig, CO 81625, USA. Fax 303-824-7864.
- Journal Explore, P.O. Box 1508, Mount Vernon, Washington 98273, USA.
- Electric Spacecraft Journal, P.O. Box 18387, Asheville, NC 28814, USA. Fax 704-683-3511.
- Nexus New Times Magazine, P.O. Box 30, Maplepton Old, 4560, Australia. Fax 074-429381.
- Journal Cold Fusion Times, P.O. Box 81135, Wellesley Hills MA 02181, USA.
- Journal Infinite Energy, P.O. Box 2816, Concord, NH 03302-2816, USA.
- Journal 21st Century Science & Technology, P.O. Box 16285, Washington, DC, 20041, USA.
- Journal Cold Fusion, 70b Route 202N, Petersborough, NH 03458, USA.
- Brown's Gas International, 5063 Densmore Av., ENCINO, California 91436 USA.
- ENECO Inc., 391-B Chipeta Way, Salt Lake City, Utah 84108, USA. Fax 801-5836245.
- "Robert Adams and Company" 46 Landing Road, Whakatane, Bay of Plenty, New Zealand. Robert Adams,
- Methernitha, 3517 Linden, Switzeland. Manager Francis Bosshard.
- Swiss Association for Free Energy, P.O. Box 10, 5704, Egliswilli, Switzeland.
- Space Research Institute, Box 33, Uwajima, Ehime 79, Japan. Dr. Shinichi Seike. Fax 895-24-7325.
- Nuclear Power Corporation, 581 400 Karnataka, India. Project Director Dr. Paramahamsa Tewari.
- Cosmic Energy Foundation, Neptunuslaan 11, 3318 E1 Dordrecht, Netherlands. Dr. Martin Holwerda
- Sabberton Research, P.O. Box 35, Southampton S097BU, England, Dr. Harold Aspden.
- Labofex, Experimental and Applied Plasma Physics, Ontario, Canada, Dr. Paulo N. Correa.

Raum&Zeit

EhlersVerlag GmbH,
Geltinger Str.14e,
82515 Wolfratshausen
Telephon: 08171/41 84-76,
Telefax: 08171/41 84-66
Internet:
http://www.raum-und-zeit.com

Institut fur Raum-Energie-Forschung (IREF) i.m. Leonard Euler

- Global Scaling Theory
- Gravitation theory
- Mathematic Biology
- Gravitation energetics
- Hydrogen-Helium Energetic
- Information technologies
- Telecommunication technologies
- Transport technologies

raum
&
zeit
Laser harmonisiert Blut und Wasser
El Niño

Some General Properties of Matter and Energy Sources

Devoted to memory of Academician A.A. Harkevich



Dr. Eugene D. Sorokodum

Volochaevskaya Street, 40-b, Flat 38,
111033, Moscow, Russia
Telephone: (7) - (095) -362 80 84
Email: e40dum@dol.ru http://vortex.viptop.ru

Introduction

Nowadays there are appear more and more attempts to disclose new methods of obtaining energy from the ambient space, i.e. from heat, electromagnetic, gravitational fields, physical vacuum, aether, etc. (See, for example, publications in New Energy Technologies [1-3]). The publications demonstrate that researchers meet various incompletely investigated physical processes. These scientific areas are difficult to be investigated. All this makes obstacles for development of works on creation of new energy sources. **In this work there is made an attempt to demonstrate general properties of energy sources of any physical nature. This attempt is based on a general analysis of properties of matter.** A theory of transformers is used to investigate general properties of matter.

Action of all physical, technical and biological systems is expressed in energy transformation. Numerous theories based on particular (specific for some system) methods are applied for description of these systems. However, if the number of degrees of freedom and of elements inside a system increases then many theories are not able to describe operation of the systems. First these problems appeared in electrical engineering, radio engineering, automation and acoustics. The theory of transformers is applied to these fields of science. The theory represents a complicated system as a "black box" having several inputs and outputs. Operation of the numerous elements occurring inside the box is represented as some equivalent functions reduced to the inputs and outputs.

In the last decades methods of solution of mechanical dynamic tasks by the method of complex resistances are developed as well as representation of elements as linear transformers [11] and finite elements in liquid [14]. This tendency can be applied to the mechanics of liquids and gases. Now there are successfully developed those concepts which assume observation of models having very few degrees of freedom to be enough for analyzing processes in hydrodynamic systems [10]. However, a mathematical apparatus for description of transformers operation which is well-developed in these areas of science and engineering has a special view and is applicable only for these scientific areas.

Academician A.A. Harkevich developed a theory of a linear transformer up to the level of the general theory of transformers which is applicable for transformation of any types of energy [24]. The general theory of transformers proposed by A. A. Harkevich is applicable for description of various energy sources, flying and swimming objects, functioning of different animals' organs, and technological processes. In this work some general properties of matter and energy sources are investigated, according to the general theory of transformers.

General theory of energy transformer

The whole ambient space, from the microworld to the macroworld, is filled with energy. According to different theories, space is represented as a compact medium (i.e. having distributed parameters) or a medium consisting of a limited number of discrete elements (i.e. having concentrated parameters). On the analogy of hydrodynamics [10, 14] the compact medium can be represented as an equivalent system with a limited number of degrees of freedom. Hence, the whole space can be represented as some system consisting of elements and communications between the elements with a limited number of degrees of freedom. Energy exchange occurs due to the degrees of freedom. Energy transmission occurs if energy gradient is presented in the ambient space. Due to the energy gradient a force tends to realize transmission in the space [4]. The elements can be systems as well.

Hence, the more we observe dividing the elements on the systems and the systems on the elements the more we will penetrate into the microworld (i.e. atoms, elementary particles, physical vacuum, aether, etc.). The more we combine the elements in the systems, and the systems in the new larger systems the more we observe the macroworld (the Solar System, galaxies etc.). All the systems and the elements are interconnected. The systems and their elements are transformers of energy. Energy motion occurs in the smallest part of space. Consequently, the whole space can be represented as a system consisting of the energy transformers. In the general case due to every type of energy limits of a transformer consist of outer limits (i.e. communications with the macroworld) and inner limits (i.e. communications with the microworld). Dividing into the macroworld and the microworld occurs in relation to the size of a transformer for every type of energy. Types of energy coming through communications of a transformer and inside it may differ, i.e. mechanical, heating, electromagnetic, chemical and other known and unknown types of energy.

The processes in which a great number of interacting elements and different types of energy participate are very complicated and do not allow describe the processes accurately by modern mathematical methods. Hence, there is a problem to find such methods of solution of the tasks which without disclosing all the communications inside the element can give the understanding of the way an element moves in the system. The following premises can be made for the method of solution of the task of a system and its elements' motion:

1. Motion of all the elements in the space is characterized by energy exchange occurring among them;
2. We are interested in a certain limited area for every individual type of energy. The chosen limited area will be called as **a transformer**;
3. The transformer has degrees of freedom both on its limits (sides) and inside it (inner degrees of freedom);
4. Further this limited area (the transformer) which has or is able to have a limited number of degrees of freedom (sides) at its limit will be observed;
5. Interaction between this transformer and the ambient space occurs only through these degrees of freedom (sides) by means of energy exchange;
6. Motion of energy between the elements of the transformer occurs according to its degrees of freedom inside the transformer. There can be a limited or unlimited number of degrees of freedom.
7. All the space is full of the transformers. All the transformers adjoin each other without gaps. Energy exchange between the transformers occurs through their sides which do not have a size but reflect general kinematical and dynamic characteristics of the energy transferred through these sides.

Editor: The full variant of the article includes mathematical description of operation of energy transformers which is followed by these conclusions:

- There can be any number of different types of elements having a corresponding number of degrees of freedom and any type of energy inside the transformer. However, on every side of the transformer a generalized force has the same value and depends only on change of energy according to this degree of freedom. Therefore, two transformers are considered to be equal if the generalized forces (energy changes) on all the sides are equal. In this case it is not necessary for the inner structure of the transformer, number of inner degrees of freedom, and energy types of these two transformers to be equal. This is **a principle of equivalency of transformers at the equivalency of the forces acting at the sides of transformers**.

- In the general case the generalized force at any side depends not only on energy exchange occurring at this side but on energy exchange occurring among the sides or at other sides of the transformer. The generalized forces are produced by energy distribution in the space.
- A transformer is characterized by the fact that there are different types of energy at its different input sides (or the energy can be of the same type but having other characteristics of motion).

Resistances of the interaction provide information about physical properties of the transformer, in particular, about physical interaction between the sides. At that a number of inner degrees of freedom in this transformer as well as the reactions at the other sides do not play any role. Proper resistances of the sides and resistances of the interaction provide information about inner physical characteristics of the transformer reduced to equivalent values at the sides. Hence, it is possible to have two transformers having equal equivalent resistances of interaction for all the sides. However, according to their geometrical and constructional characteristics and types of energy, the transformers will be different. The resistances may be a function of kinematical characteristics **(a nonlinear transformer)** or of time **(a parametrical transformer)**. Moreover, it can have constant values **(a linear transformer)**.

It is appropriate to consider physical properties of matter included in the volume of a transformer only due to resistances at the sides of the transformer.

Structure of the transformer

Every inner degree of freedom can be represented as a series circuit. By analogy with electric circuits [6, 7, 11, 16-18] the transformer can consist of various circuits. An unlimited number of degrees of freedom allows represent a transformer consisting of an unlimited number of chains. The circuits have series, parallel, or mixed junctions. A part of a circuit whose elements have the same generalized displacement is called as a branch. The branch can consist of one or several elements. A place where three or more branches are joined is called as a multiple junction. A circuit is considered to be a closed path including several branches and multiple junctions. All the elements of a chain connected in series have equal generalized displacement (as well as equal speed and acceleration). The generalized force acting on the whole circuit is equal to the sum of forces acting on the elements of the series circuit.

The elements connected in series can be replaced by one element in such a way that the generalized displacement and the summary generalized force would not change. In the case of a parallel connection all the branches of the circuit are joined to the same pare of multiple junctions and are under influence of the same generalized force. Parallel circuits can be replaced by series equivalent circuit and vice versa [6, 7, 11, 17, 18]. Hence, a number of inner degrees of freedom and a quantity of chains may be decreased as well as increased. In this case resistances occurring on all the sides will be constant.

Structure of the linear transformer

The simplest transformer is a one-side transformer having one inner degree of freedom…

If to the input of the transformer we deliver generalized displacement (or force) which depends on time as a pure sinusoidal signal then the linear transformer will have sinusoidal reaction of the same frequency. For the sinusoidal signal with fixed frequency the linear transformer (including a transformer having an unlimited number of inner degrees of freedom) can be represented as an equivalent transformer reduced to this input as one chain. An equivalent transformer placing at this input at other fixed frequency of sinusoidal disturbance will be represented as a chain having one degree of freedom but different values of chain elements.

If the signal at the input of the transformer is of complicated time-periodical form then it can be decomposed to Fourier series. Every harmonics of the Fourier series will produce its own chain. The general complicated signal will produce the complex chain consisting of compound sum of elementary series chains. This complicated chain consists of elementary chains interconnected in series or in parallel and combined in multiple junctions and circuits. The construction principles of this complicated chain can be based on methods of identification and synthesis which are well developed in electrical engineering, automation for linear and non-linear transformers [9, 12, 13]. These principles are formally useful for transformers which transform energy of any physical nature. Identification produces so much elementary chains as the number of inner degrees of freedom. Every elementary chain reflects motion by one inner degree of freedom. Physical analogy occurring among motions of different nature is actual here [11, 16, 18]. Values of the generalized masses, elasticities, dissipative and active elements can depend on kinematical variables (non-linear chains), on time (parametrical chains), or they can be constant (linear chains).

If a series circuit includes mass and elasticity then it will have resonant frequency. At this frequency reaction of mass and elasticity will be absent in the summary reaction. It is equal to the fact that we will know nothing about the value of mass (and elasticity) and, moreover, about its presence at all. The mass can have huge value, but it will be absent for us. Hence, if we assume a transformer as an atom then the atom may include elementary chains having huge masses (much more than the mass of the Earth), but we will not know about it until we apply such frequency to the input which explicates this mass.

Any energy transformer including a transformer with distributed parameters can be represented as a system of elementary series and parallel chains connected in a certain way. A concrete transformer can have various types of these connections. All of them can be included into another combination of connections that is accompanied by change of values of masses, elasticities, dissipative and active elements. However, in this case equivalency of reaction should be fulfilled at a certain diapason of frequencies on all the sides of the transformer.

There is a special spectrum of resonant frequencies for every combination of connections of the transformer. There will be an unlimited number of degrees of freedom and, hence, an unlimited number of resonances for the transformer with distributed parameters (for example, an elastic nail, a compressible fluid having a limited size). Our influence on the transformer usually has a certain diapason of frequencies. As the result of a limited diapason of excitation frequency the transformer will represent a system having a limited number of inner freedom, even if the transformer has distributed parameters.

Values of equivalent elements depend on oscillation frequency. Moreover, according to known laws, several parallel circuits can be transformed into a series one and vice versa. Taking it into account the following conclusions can be made:

1. The generalized mass, elasticity and dissipative elements do not have constant values in nature. Their value depends on frequency of the process, i.e. they depend on the character of time-change of the disturbance acting on the transformer.
2. The generalized mass, elasticity and dissipative elements are products of time-space change of energy.

Types of energy transformers

Transformers can be nonlinear, parametrical and linear. The transformer can be **active** (having an internal source) and **passive** (having an external source). The passive transformer can never be an energy source (by definition). A transformer can accept or transform one type of energy (monoenergetic transformers) or several types of energy (polyenergetic transformers). The polyenergetic transformer includes a mechanism and corresponding elements and chains which allow transform one type of energy into another one. Fundamentally, all the transformers are polyenergetic transformers of energy, however many of them can be represented as monoenergetic ones since other types of energy participate weakly in them. Designing a transformer it is more convenient to put the energy source out the transformer. Let us further classify the passive transformers.

The passive transformers can belong to the following types:

1. Simple transformers

In this case energy is produced at the output due to transformation of energy coming to the inputs into energy of another type or having other characteristics. The following transformation can serve as the example.

An electric transformer: resistance of one value comes to the input, and the resistance of another value comes from the output (a type of energy is the same).

A furnace for combustion of fuel: energy of chemical connections comes to the input and heating energy comes from the output (energy of radiation may be neglected).

A Wind Generator, Hydroelectric Power Station: kinetic energy of moving air or water comes to the input, and electric energy comes from the output.

2. Energy intensifiers

In this case a transformer intensifies energy coming to one of the inputs due to energy coming to the other inputs (or to the other input). Below there is an example for a *monoenergetic transformer*. Energy (an electric signal having certain parameters) comes to the input of a transformer, and the output energy has the same characteristics but it is more intensive. It can occur due to electric energy coming to the other input of the transformer.

A heat pump represents an example for a *polyenergetic transformer*. Low potential heat energy of the ambient space (air, water, ground) comes to the input of the heat pump, and electric energy from a power network comes to the other input. The output heat energy has value which is equal to the sum of the coming heat energy of the ambient space and electric energy coming from the power network through the electric engine of the compressor. The output heat energy excesses energy coming from the power network by several times. The output energy is always lower than the sum of the low potential heat energy and the electric energy coming to the input. Hence, the output of a heat pump is always less than unit.

Efficiency of the heat pump consists in the fact that a consumer pays for electric power produced by power network only (use of the low potential heat of the ambient space is free). However, the output heat energy is several times more than the energy which can be produced by the electric power coming to the input.

3. Active oscillator

An active oscillator is a device of a certain type. Energy of time-constant characteristics comes to its input, and at output there is energy of time-periodical characteristics. Energy with time-periodical characteristics can come to the input as well since these characteristics are not connected with the time-periodical characteristics of the output energy. The transformer can operate in a mode of an active oscillator if it has the following features:

1. Indirect connection as a series circuit: one of the outputs is connected to an additional transformer whose output is connected to one of the inputs of the transformer. The additional transformer provides certain changes of the input signal (time delay).
2. Energy comes to the input (it can be time-constant or time-periodical).
3. The transformer must have a certain type of non-linearity.

Examples of the active oscillator

Internal combustion engine: the indirect connection is the system of combustion, the non-linear element is the system of admission and exhaust valves, and the energy source is energy of chemical connections of fuel.

Various electric generators: all of them have the indirect connection, the non-linear element, and the energy source.

The active oscillators differ from the electrical intensifiers qualitatively. The difference consists in the fact that the active oscillator can operate and receive energy from the ambient space without additional energy coming to it (from a power network, for example).

Theorists and experimenters try to create a self-supporting self-organizing system in their works on creation of alternative sources. This fundamentally correct tendency requires using theory of active oscillators. There is the developed theory in electrical engineering, automation, and other scientific fields [25]. To simplify application of these theories it is necessary to use analogy between equal processes which take place in different physical fields.

4. Rectifiers

Time-periodical energy comes to the input of the transformer. The output energy has time-constant or practically time-constant characteristics. If the transformer has a non-linear element or elements of a certain type (a diode or a one-sided valve) then it can operate in the mode of a rectifier. The examples are electrical rectifiers and pumps of a valve type.

Properties of energy transformers

General properties:

1. A transformer can transform energy of one type as well as transform one type of energy into another type.
2. The generalized kinetic, potential and dissipative energies are specific peculiarities of energy change in the space and time.
3. The generalized masses, elasticities and dissipative elements are products of energy change in space and time.
4. Values of the generalized masses, elasticities and dissipative elements (existing inside the transformer as well as reduced to the equivalent values on the sides of it) depend on a temporal character of changes of kinematical or dynamic disturbances. Values of the generalized masses and elasticities at the sides of the transformer are lower than the corresponding values inside the transformer.
5. Energy interchange between macrostructures and microstructures can occur through a transformer.
6. One area of space can "know" about another area of space through energy exchange only, i.e. through generalized dynamic and kinematical interactions. In the light of the fact that chains of different transformers can have similar physical properties (for example, an equal resonant structure) interference of these transformers seems to be possible including interference occurring at a great distance.

Properties of the passive monoenergetic transformer:

1. Transformation of characteristics of the same energy type.
2. The output energy can be both equal or lower than the sum of energies coming to all the inputs. The sum of the output energies decreases due to dissipative losses occurring inside the transformer.

Properties of the passive polyenergetic transformer:

1. One energy type coming to an input can be transformed into another energy type coming from the output.
2. The sum of energies of all the outputs can be equal to the sum of energies of all the inputs or less than it. The sum of the output energies decreases due to dissipative losses occurring inside the transformer. The output will always be lower than unit. If the energy coming from certain of the outputs (within the limits of one output) is considered as a positive effect then the output will be less than the mentioned value.
3. Energy of one and the same type comes to the input and from the output while other energy types can come from other outputs. This property can allow increase one type of energy coming from an output at the expense of the other types of energy coming to the inputs.

Analysis

This article is aimed to provide general properties of the energy transformers and to analyze some problems of creation of renewed energy sources, according to these properties. There are made various attempts to design a renewed energy source which would produce energy without fuel consumption. In the light of the above mentioned results, the researches on creation of the renewed energy source may be represented by the following way. Energy can be produced from the macrostructures and the microstructures.

In the case of the macrostructure, energy can be produced by a simple transformer, an electric intensifier or an active oscillator. Methods of production of energy from the ambient space by means of simple transformers (thermoelectric and hydroelectric power stations, wind generators, etc.) are developed sufficiently by the humankind. Works on producing energy from the ambient space by means of energy intensifiers are on its initial stage. Heat pumps, which utilize low potential heat energy by means of Freon-compressor heat pumps, are successfully introduced. One of the perspective approaches is replacing such a heat pump by a vortex oscillating heat pump which does not contain Freon and a compressor [3, 5, 19, 22]. In future it will be possible to replace the energetic pump by a new energy transformer of the type of an active oscillator. In this case the energy source will always obtain energy from the ambient space without using additional energy from a power network. Energy sources of the type of the active oscillator are internal and external combustion engines, stream engines, etc.

In the general case a transformer can contain different energy types and has communications with **outer microstructures**. It should be noted that the outer microstructures can be included in the geometrical size of the transformer. Energy of this microstructure can be huge; hence, this energy can be obtained from them for a very long period of time. Atomic reactors can serve as an example for this fact. The types of energy in these microstructures can be represented by known types (electromagnetic energy, nuclear energy) and unknown types (whose numerous quantity can be considered). These energy types exist in the ambient space. However, almost all the transformers of energy produced by a human (except the nuclear reactors) do not interact with the energies, and we do not obtain energy from these microstructures.

The task of creation of a new energy source consists in designing such an energy transformer which could obtain energy from the microstructures and transform it into the type of energy which is needed to a consumer. In this case all the designed transformers will not have over unit output. Efficiency of these transformers will be defined by the cost of the energy produced by them. This energy depends on a ratio of energy coming to one of the inputs (electric power) (for example, in heat pumps) to the output energy. If the output energy is much more than the artificial energy which comes to one of the inputs then this transformer can be very useful for a consumer.

New high effective energy sources are often claimed to be created. According to the observed facts, existence of such sources is practically possible. Nevertheless, realization of this source will depend on our knowledge of physics of the microstructures and methods of transformation of energy of the microstructures into such type of energy which can be used by a consumer. Physics of microstructures is investigated badly, and many types of energy are totally unknown. Therefore, modern scientists try to create the new energy sources at random. In this case the following results can be achieved:

1. The high effectiveness of an energy source (over unit output) does not correspond to reality.
2. The output energy of the energy source is actually higher than the input energy (the source of the energy intensifier type).
3. The energy source actually produces energy without artificial input energy (the source of the active oscillator type). It can occur if an inventor failed to recognize the source of energy coming from the microstructures. It can be connected with particular or total lack of exploration of physics of the microstructures. Moreover, the fact is caused by transcendent difficulty of disclosing energy sources from the macrostructures.

Conclusions

It is principally possible to create an energy source whose output energy would be higher than its input energy (an energy intensifier) or an energy source which would produce energy without additional input energy (an active oscillator).

1. Various energy sources or transformers of energy of the macrostructures and microstructures can be designed.
2. Practical value of the energy source is defined according to cost of its output energy instead of the output value.
3. Designing new energy sources it is useful to consider them from the point of view of transformers. It is worth to define all the communications of the transformer and to state experimentally energy at all the accessible communications of the transformer.
4. Developing theories of sources it is expedient to use physical analogy and to take into account ready results of works on theories of transformers, chains, etc. of electrical engineering, radio engineering, automation and other scientific fields.
5. In the light of the fact that it is planned to obtain energy from the microstructures it is necessary to pay attention to new probable types of radiation and to their influence on a human.

References

1. Frolov A.V. The work Advanced Energy and Propulsion Systems based on Chronal Reaction Method // New Energy Technologies. - 2001, 2. p.51-55.
2. Frolov A.V. Reactionless Propulsion and Active Force // New Energy Technologies. - 2001, 2. p.56-58.
3. Sorokodum E. Recycling of energy of the atmosphere by means of vortex // Russian technologies for industry "Renewable Energy" IWRFRI'2001,may 28-30, 2001, Saint-Petersburg. Abstracts. - 2001, p. 92-93.
4. Sorokodum E. On general nature of forces. New Energy Technologies. 1(4), 2002, p.30-36.
5. Sorokodum E. D. Vortex heat-generators. New Energy Technologies Issue. Vol.2(5), 2002, p.17-76.
6. Andreev V.S. Theory of nonlinear electric circuits. M.: Radio and Communication. 1982, p.280
7. Atabekov G.I. Theory of linear electric circuits. M.: Soviet Radio. 1960, p. 712
8. Berezkin E.N. Lectures on theoretic mechanics. Part 11. Dynamics of the system, dynamics of solid body, analytical dynamics. M.: MSU - 1968, p.314
9. Blakyer O. Analysis of nonlinear systems. Transl. from English. Edited by Hohlov R.V. M.: Mir. – 1969, p. 400
10. Gledzer E.B., Dolzansky F.V., Obuhov A.M. Systems of hydrodynamic type and their application. M.: Nauka – 1981, p. 366
11. Druzinsky I.A. Mechanical circuits //L.: Mashinostroenie. – 1977, p. 240
12. Kononenko V.O., Plahtienko N.P. Methods of identification of nonlinear mechanical oscillating systems
13. Zakrzhevsky M.V. Oscillations of essentially-nonlinear mechanical systems. Riga, "Zinatne". – 1980, p.190
14. Ladikov Yu.P. Stabilization of the processes in continuums. M.: Nauka. – 1978, p. 432
15. Merkin D.R. To the question on forces' structure // Applied mathematics and mechanics. - 1975, 39, 35. p. 929-932
16. Oltson G. Dynamic analogies. M.: State Edition. Foreign Literature. - 1947, p.223
17. Popov E.P. Theory of linear systems of automatic regulation and control. M.: Nauka. – 1989, p.302
18. Puhov G.E., Vasilyev V.V., Stepanov A.E., Tokareva O.N. Electrical modeling of the tasks of structural mechanics. Edition of Academy of Science of Ukrainian SSR. - 1963
19. Rodionov B.N., Sorokodum E.D. Vortex energetic. Constructional materials, equipment, technologies of the XX century. 3 (26). 2001, p. 28, 29
20. Sorokodum E.D. Theory of transformers for nonlinear biomechanical oscillating systems. Taganrog institute of radio engineering. – Dep. in VINITI, 7.05.1980, #1948-80 Dep. – 1980, p. 38
21. Sorokodum E.D. On the application of theory of nonlinear transformers for the calculation of complex mechanical oscillating systems. Reports at the scientific conference "Problems of nonlinear oscillations of mechanical systems". Kiev. - 1978
22. Sorokodum E.D. Vortex source of energy. International scientific and social conference. Prospects of preservation and developing of the united civilization of the planet. Culture. Ecology. Space. 26-31 of May, 2002
23. Strelkov S.P. Introduction to the theory of oscillations. M.: Nauka. – 1964, p. 440
24. Harkevich A.A. Theory of transformers. State Energetic edition, M.-L.: 1948, p. 191
25. Harkevich A.A. Auto-oscillations. / Harkevich A.A. Selected works in 3 volumes, V. 2, M.: Nauka – 1948, pp. 253-379.

Commercial Exploration of Space

Review
by Olga Leontyeva, Editor
http://www.faraday.ru

Of late years the mankind has greatly advanced in space exploration. New spaceships are created, automatic apparatus are launched to the planets of solar system, space stations are orbited. A man has passed to outer space and begun exploring the planets of solar system. More and more specialists and people of different professions are involved in the development of space industry. However to present day only a few of them has succeeded flying into space.

At the present state of affairs space flight is very expensive and a serious reason should exist to forward a man into space if he or she does not relate to the aims of professional cosmonautics. However in last years there has appeared a certain breakthrough in the solving of the problem. Nowadays space technologies gradually turn from the sphere of experimental and scientific researches to the area of practical application. The time has come for a man to realize the real space flight without being the professional cosmonaut.

What are the ways to solve the problem? No doubt that special attention should be paid to the development of new space technologies, search of new types of fuel and attraction of investments to the sphere of space tourism.

April 28, 2001 can be considered as official date of birth of space tourism, when there was launched the space ship “Soyuz TM-32” with the first space tourist aboard. Almost in a year, on April 25, 2002 the space tourist #2 South African Republic person Mark Shattlword started on his space journey.

Today many companies give the opportunity to make a real space flight for all comers who have enough money and health. It is promised the providing of the most modern space technologies and the most perfect space equipment. It can be created a furor by the “Minimum program” of the Russian company “Atlas Aerospace” which is made by the members of Yu.A. Gagarin Center of training of cosmonauts.

In recent years at the international market there appear more and more companies which deal with search and encouragement of inventors who work on creation of alternative propulsion systems. Activity of “X Prize Foundation” company can be considered as an example.

The X PRIZE Foundation

722-A Spirit of St. Louis Blvd
St. Louis, Mo. 63005
Tel: 636-519-9449, Fax: 314-533-6502
http://www.xprize.org
E-mail: press@xprize.org

The X PRIZE is a $10,000,000 prize to jumpstart the space tourism industry through competition between the most talented entrepreneurs and rocket experts in the world. The $10 Million cash prize will be awarded to the first team that:

- Privately finances, builds & launches a spaceship, able to carry three people to 100 kilometers (62.5 miles)
- Returns safely to Earth
- Repeats the launch with the same ship within 2 weeks

The X PRIZE competition follows in the footsteps of more than 100 aviation incentive prizes offered between 1905 and 1935 which created today’s multibillion dollar air transport industry.

For more than 30 years, the general public has waited for an opportunity to enjoy the space frontier on a first-hand basis. The X PRIZE Foundation is working to make space travel possible for all. The spaceships that compete for the X PRIZE are designed to carry passengers.

Since its inception in May 1996, the X PRIZE Foundation has registered more than 20 teams from seven countries to compete for the prize. The X PRIZE is fully funded through January 1, 2005, through private donations and backed by an insurance policy to guarantee that the $10 million is in place on the day that the prize is won. Additional funds are still being raised by the X PRIZE Foundation to implement the competition (judging, media, event management, etc.) and continue the Foundation’s education mission.

The X PRIZE was inspired by the early aviation prizes of the 20th Century, primarily the spectacular trans-Atlantic flight of Charles Lindbergh in The Spirit of St. Louis which captured the US $25,000 (US$) Orteig prize in 1927. Through a smaller, faster, better approach to aviation, Lindbergh and his financial supporters, The Spirit of St. Louis Organization, demonstrated that a small professional team could outperform a large, government-style effort.

The Societal Benefits of the X PRIZE include:

* Creation of a new generation of heroes
* Inspiring and educating students
* Focusing public attention and investment capital on this new business frontier
* Challenging explorers and rocket scientists around the world; and,
* Vehicles built for the X PRIZE will eventually serve four different industries:
- Space Tourism
- Low-cost satellite launching
- Same-day package delivery
- Rapid point-to-point passenger travel.

In Fig. 1 it is demonstrated the typical X Prize trajectory.



Fig. 1

Editor: Below we publish photos and brief comments about some official X PRIZE registrant teams. More detailed information you can find at http://www.xprize.org/imagefacts/photo1.html.

The Da Vinci Progect

http://www.davinciproject.com



Fig. 2
“Wild fire”

The **da Vinci Project** will launch its spacecraft (“Wild Fire”) from the world’s largest helium balloon. The 3,270 kg (7,200 pound) rocket will be tethered 720 meters (2,400 feet) below the balloon and lifted over the course of an hour to an altitude of 80,000 feet. The 10,000 pound thrust, liquid oxygen, kerosene engines will fire the first stage and the rocket will fly an initial angular trajectory to clear the balloon. The spacecraft then will transition to vertical flight to its apogee of 120 km in space. The rocket will reach a maximum speed on both its ascent and re-entry of Mach 4, or 4,250 kph (2,650 mph).

An innovative ballute will protect and stabilize the rocket on re-entry. A flyable parachute will be deployed at 25,000 feet and the rocket will descend under control, guided by GPS, to a predetermined landing zone. The da Vinci Project has already successfully conducted full-scale rocket motor test and has built a full-scale mockup of their vehicle.

“Discraft” corporation

http://www.xprize.org/teams/teams.html

John Bloomer, the team leader, is an aerospace engineer and he has worked on many aerospace progects, including Apollo and holds more than 60 patents on a disc plattorm aircraft. Bloomer’s ship utilizes “Blastwave” Pulsejets.

Flight Sequence

Fixed, 7850-ft^2-area, laminar-flow wing take-off at about 60 mph within about 150 ft, featuring climb with gradual air-breathing acceleration (according to a fixed program) at fixed angles, to exit the atmosphere at Mach 10 on an unpowered ballistic arc to reach 75-mi. altitude: return on down-leg of same unpowered arc to gradual power-on flare-out re-entry of the atmosphere in simple reverse sequence of the take-off velocity profile. Range above 100,000 ft is about 480 mi. which is covered in about 5 minutes.

"Kelly Space & Technology"

http://www.kellyspace.com



Fig. 3
"LB-X"

The vehicle is a rocket-powered delta wing glider with a liquid oxygen and kerosene liquid rocket engine. The spacecraft is prepared and fueled at the takeoff airport. The spacecraft is towed to release altitude behind a conventional jet powered aircraft such as Boeing 747 aircraft. Upon release from the tow aircraft, the main engine is throttled up for boost phase. The vehicle nominally coasts to an apogee altitude of 100 kilometers. The vehicle then glides to a landing at the takeoff airport for checkout and refueling prior to the next flight.

Flight Sequence

The lifting body will be towed to launch altitude behind another aircraft, and the rockets will be ignited. The craft will return to the landing site and make an unpowered, horizontal landing.

"Lone Star Space Access"

http://www.dynamicar.com

The Cosmos Mariner employs air-breathing jet propulsion for take-off and landing from conventional airports and rocket propulsion for ascent from cruise flight in the stratosphere to 30 or 40 nautical miles altitude. From there, the vehicle coasts to a target altitude of around 65 nautical miles. The air frame is designed to interface with two jet engines (turbofan or turbojet) each with 20,000-lbs static thrust or less. For rocket propulsion, the Cosmos Mariner will use the Aerojet AJ26-NK31A, a staged-combustion kerosene engine. The vehicle is designed to take off and land from conventional runways.



Fig. 4
"Cosmos Mariner"

*Along with X Prize Foundation it should be mentioned **ALLTRA** Company (Germany). ALLTRA consists of a small group of space experts. The main objective of ALLTRA is to 'sell' the space idea to a broad public and to identify future commercial opportunities in the space sector.*

On the official ALLTRA website http://www.alltra.de you can find collection of artist's views of the projects which are aimed at decrease in space ships value by means of using of new types of engines. Besides the Company deals with the development of space hotel projects.

JNET

**New Energy Technologies
collection of articles
Japanese Version**

Collection of articles from New Energy Technologies magazine, 2001-2002 is published in Japan.

On purchasing of the book, please, contact

Eiichi Yamamoto,
President Yama Trans Co. Ltd.

Email: admin@yamatrans.co.jp or
eyama@yamatrans.co.jp

Alternative Aircrafts and Space Propulsion Systems

Editor: Nowadays all over the world there are made numerous attempts to create new types of aircrafts and alternative space propulsion systems. Below we publish the review of some interesting devices which are presented in the modern market.

"Arbortech Pty.Ltd"

http://www.airboard.com.au



Fig. 1
Airboard 2000

General Technical Specifications

Total payload, including rider — 100 kg (220 lb)
Operating time — 1 hour on full tank of fuel
Construction — Fiber glass/High-impact plastic shell, Aluminum frame, Rubber skirt
Starting — Electric key-start, Battery included
Engine — Briggs & Stratton 4-stroke
Fuel tank capacity — 5 litre (1.3 US gal)
Fuel type — 85 Octane unleaded

How does it work?

Airboard uses Hovercraft air cushion principles to glide just above the ground. The air cushion is generated from a purpose designed engine and fan which are suspended below the Airboard shell. In addition to providing an air cushion for the Airboard to ride on the fan also provides a fast stream of air exiting from the rear of the craft to provide forward thrust – just like a hovercraft. To help provide better acceleration the Airboard also includes a unique friction drive wheel at the rear. When the rider wishes to accelerate forward, weight transfer is used to bring the friction drive into contact with the ground. By engaging the friction drive clutch the Airboard can be accelerated forward without losing the feel of hovering above the ground. The control of the Airboard is provided by weight transfer of the rider, similar to surfboards, skate boards and snow boards. In operation the Airboard can be started, stopped and steered in a controlled manner and this means that riders can perform stunts, trick maneuvers and race around tight tracks against each other. In this unique way the Airboard is the first ever vehicle to deliver the advantages of hovercraft vehicle without the disadvantages of proof acceleration and handling.

"Trek Aerospace, Inc."

http://www.solotrek.com



Fig. 2

Trek Aerospace

Preliminary Specifications and Predicted Performance

Normal Gross Take Off Weight	800 Lbs.
Fuel (15 U.S. Gallons)	98 Lbs.
Mission Payload, net of fuel	352 Lbs.
Takeoff/Landing Distance	0 (VTOL)
Maximum Speed	70 Mph
Range	120+ Miles
Hover/Loiter Endurance	2+ Hours
Engine Type	Advanced Int. Combustion
Fuel Requirements	Heavy-Fuel or Gasoline

Special Features: 100% fly-by-wire control system with electronic stability augmentation; Intuitive, easy to fly safely; Minimal field service requirements; Rugged, efficient power train.

DM AeroSafe

http://dmaerosafe.freeservers.com



Fig. 3

EAGLE vertical take-off and landing aerial rescue platform

DM AeroSafe is a small research and development team, which has developed a totally new high-rise rescue technology to retrieve trapped people from areas which cannot be reached by conventional aerial ladder, conventional helicopter or a helicopter equipped with a Heli-Basket.

This technology could give rise to a new class of air transportation means, used for safe close-in maneuvering around tall structures, even inside the highly populated areas.

Eagle Aerial Rescue Platform's Performance Summary

Dimensions:

Length - 42 feet (12.8 m)
Width - 42 feet (12.8 m)
Height - 16 feet (4.8 m)

Weights:

Max. Gross weight - 5000 pounds (2268 kg)
Payload (Crew of two plus 10 rescued people) - about 2000 pounds (about 900 kg).

Propulsion System:

Four (4) variable collective pitch Ducted Propellers
Propeller Diameter - 7.8 feet (2.4 m)
Engines - four (4) four-cylinder radial piston aero engines with forced air cooling system 250 hp each (1000 hp total)

Performance:

Max. Duration - about 5 hours without refueling
Max. Airspeed - 40 knots (75 km/h)
Max. operating altitude - about 7000 feet (about 2200 m).

"LTAS/CAMBOT, Inc."

http://www.lvcm.com

Passenger Craft "Ltas 30-Xb"

The ships have rigid monocoque hulls, hybrid powered vectored thrust control and full active buoyancy control. (LTAS US Patent Pending).

This small 2-3 person craft at 70 to 80 feet in diameter will demonstrate ALL production systems and is designed for the LTAS FAA Type Certification program.

NASA's Langley Research Center

http://science.nasa.gov

NASA researchers are studying insects and birds, and using "smart" materials with uncanny properties to develop new and mind-boggling aircraft designs.

The "personal aircraft" that replaces the beloved automobile in people's garages may still lie in the realm of science fiction or Saturday-morning cartoons, but researchers at NASA's Langley Research Center (LaRC) are developing exotic technologies that could bring a personal "air-car" closer to reality.



Fig. 4

And air-cars are just the beginning! Self-healing wings that flex and react like living organisms, versatile bombers that double as agile jet fighters, and swarms of tiny unmanned aircraft are just a few of the science-fiction-like possibilities that these next-generation technologies could make feasible in the decades ahead.

Laser Beam Flight

Lightcraft Technologies, Inc. (LTI)

http://www.lightcrafttechnologies.com

Lightcraft Technologies, Inc. is a new company committed to providing low-cost access to space through the use of beamed energy propulsion. (See color photos on the cover page).



Fig. 1

In 2000 at the High Energy Laser Systems Test Facility (HELSTF), Lightcraft Technologies, Inc. (LTI) set a new world's altitude record of 233 feet (71 meters) for its 4.8 inch (12.2 cm) diameter laser boosted rocket - in a flight lasting 12.7 seconds. Although much of the flight was spent hovering at 230+ feet, the Lightcraft sustained no damage and will fly again. Besides setting the new altitude record, the craft demonstrated the longest ever laser-powered free flight and the greatest "air time" (i.e., launch-to-landing/recovery). LTI launched a total of seven vertical flights between 8:30 am and 11:30 am with three Lightcraft weighing less than 1.8 ounces (51 grams). Two of the flights by Lightcraft #3 reached 159 and 184 feet with the same propellant load!

...set a new world's altitude record of 233 feet!

The record flights were powered by the 10 kW pulsed carbon dioxide laser named "PLVTS" by the organization that owns it: the Directorate for Applied Technology, Test and Simulation (DATTS). Even though PLVTS was suffering from an arcing or grounding problem that caused it to run erratically, the laser power was still adequate to propel the craft to record altitudes.

What is a Lightcraft?

A Lightcraft is a 1kg launch vehicle, made from high temperature ceramic materials, that flies into space on a megawatt laser beam.



Fig. 2

The Lightcraft is both a single-stage-to-orbit launch vehicle and a satellite. If you have any further questions or comments, write or call LTI headquarters in Bennington,VT. The company representatives would be delighted to send you more information, or answer any inquiries over the phone.

How does it work?

A ground based laser is the power source that propels the Lightcraft into orbit. Lightcraft can deliver payloads into space for a fraction of the cost of traditional rockets because most of the engine stays on the ground, thereby unburdening the craft from having to lift the energy source for its propulsion system.



Fig. 3

The back side of the craft is a large, highly polished parabolic mirror that is designed to capture the laser beam projected at it from the ground. The mirror focuses the beam, rapidly heating the air to 5 TIMES the temperature of the sun, creating a blast wave out the back that pushes the vehicle upward. As the beam is rapidly pulsed, the vehicle is continuously propelled forward, on its way to orbit.

History of Lightcraft

1987 — Prof. Leik Myrabo invents Lightcraft for SDIO.

1997 — First successful wire-guided tests at WSMR. Solved flight stability difficulties, much like the Wright brothers did with the airplane.

1997 — Lightcraft broke Goddard's 41 ft., 1926 first successful rocket flight - but this time with no on-board fuel.

1998 — Record flight of 99 ft. with air breathing Lightcraft engine.

1999 — Record flight of 128 ft. with first rocket Lightcraft engine.

2000 — LTI sets new world record for highest flight (233 ft), longest flight time, and heaviest vehicle.

How can LTI reduce launch costs?

Conventional Launch — $175,000,000
The Lightcraft — $46,000

Chemical Rockets:

- carry massive propulsion source on board
- are expendable
- extremely costly
- prone to explosion due to fuel on board

Laser Propulsion:

- propulsion energy source remains on the ground!
- Lightcraft are inexpensive to manufacture and extremely light weight
- highly reusable power source is never subjected to the risks of flight

Lightcraft Technologies, Inc.

1914 Walloomsac Rd.
Bennington, VT 05201
Office: 802-447-6275
FAX: 802-447-8216
E-mail: tmyrabo@lightcrafttechnologies.com

Alternative space propulsion systems Star Drive

Mark R. Tomion, USA
http://www.stardrivedevice.com

Re: U.S. Patent **6,404,089** for the **Electrodynamic Field Generator**, **(EDF),**
issued June 11, 2002 to Mark R. Tomion.

The 'official' name of the "StarDrive device", per the U.S. Patent and international PCT Applications, is **Electrodynamic Field Generator.** The EDF Generator uses banks of permanent magnets and rotating Field Coils to produce a very-high DC rotor voltage, and plane-parallel ring electrode arrays to electrostatically expand and control that voltage *as applied to the hull*, so that huge quantities of external Field electrons may be accelerated to energy levels that are usually reached only with a particle accelerator! It's somewhat like a glorified arc welder whose output is deliberately shorted to its own housing, and the DC voltage and current across the emitter and collector housing sections can be thermionically increased to values that are generally observed only in lightning: but the Field's *current density* is limited to a value which falls short of damaging the hull!



Fig. 1
StarDrive device hull & electrodynamic
Field configuration

As depicted above (Fig. 1), electrons circulating in the external Field envelope can achieve an impact velocity at the central collector sections which is very nearly that of light, and applied magnetic fields allow broad modulation of the Drive Field current's properties. The *Primary Arrays* shown in the generalized schematic diagram below (Fig. 2) have control grids which allow an arc resistance imbalance to be imparted to the otherwise symmetrical Field current, so that they *render the two relativistic current impulses variably non-isometric:* thereby yielding thrust that is essentially **reactionless**! And the simple DC *Primary Power System*, like the early Faraday disk dynamo, *is wholly rotor-based* **. . .**

Note: It can be seen that the propulsive thrust developed by a StarDrive vessel is essentially brute-force in nature – it's produced simply by means of a controlled variable imbalance in the continuous *physical impact* of the two external hemitoroidal electron current streams with the collectors! If these two Field currents were of equal magnitude, no net force would be developed. However, if the "lower" current stream is stronger than the "upper", the vessel will be propelled away from the stronger current – in the "upward" direction. Since there's no 'backward' exhaust produced in the process, this type of thrust is truly and demonstrably reactionless in nature.



Fig. 2
Generalized schematic of rotor & dual induction ring assemblies

Needless to say, tremendous quantities of heat are produced in the StarDrive device's electron "targets" or collector housing sections, and liquid sodium must be pumped through each Primary Array's ceramic resistor network as a coolant. However, this excess heat in ground-based units may be used in the *commercial generation of electric power and desalinization of seawater*.

In fact, because an intense arc discharge field has the unique capacity to absorb vast quantities of quantum background energy, the EDF Generator is so efficient that the latter task may become truly cost-effective for the first time! And not only will large ***over-unity*** StarDrive Dynamo units be able to produce electric power at 60 to 720 MW output levels, they'll be able to do so for many years before the permanent magnet banks must be remagnetized!! *The only truly external input energy required* in the interim *is that necessary to initially bring the rotor up to speed . . .*



Fig. 3
A denumbered version of Fig. 1
from the EDF Generator Patent

Those of you who find this advanced technological prospect for the 21st century as exciting and fascinating as we do should consider making the inventor's book *StarDrive Engineering* a valuable addition to your personal or reference library.

A Layman's Description of the StarDrive Device

Nearly anyone who endeavors to gain an initial understanding of the *Electrodynamic Field Generator*, even a scientist or engineer, is likely to ask for a concise layman's explanation of "how it works". This isn't easily accomplished, for this device represents an unorthodox and multidisciplinary technology. However, the overview provided below will discuss the operative characteristics of the machine's simplified *electric power generation variant* in what is hoped to be the most direct manner possible. In this case, when people ask the question above, what they generally mean is: "By what means is *over-unity* operation achieved in a 'StarDrive' Dynamo?". It is assumed here that the reader has not only already become acquainted with certain basic aspects of the design, but also understands that over-unity operation is an absolute prerequisite for any viable system of light-speed interstellar propulsion.

By way of further background, the formative mechanical design basis of the EDF Generator is of course the original Faraday disk dynamo. For whatever reason, no one seems to have bothered trying to develop this simple machine into a more sophisticated *and patentable* form before now. The principal limitation of Faraday's disk dynamo in its original form was that, when one or more permanent magnets were used to pass flux directly through the plane of a solid conductive rotor, a rather high-loss heavy current at very low voltage was produced. The first design improvement was therefore to use rotor-mounted toroid field coils in order to generate a much higher-voltage primary current, and to segment the rotor to reduce "eddy current" losses. Also, the toroid coil configuration absolutely minimizes Lenz losses, or the magnetic "drag" that is experienced by any conventional generator's rotor.

To eliminate the use of brushes, it was necessary to apply traditional vacuum tube design and operating principles. Fortunately, most of the original patent work in this field has passed into the public domain, so incorporating certain aspects of that work into the EDF Generator presented no impediment to its patentability. By using plane-parallel electrode arrays instead of brushes to charge the rotor, it is possible to limit that portion of the induced rotor current which passes through the field coils to a very low level – effectively isolating them from the actual output circuit. More importantly, however, it then becomes possible to thermoelectrically charge the Generator's housing itself in such a way that *it* carries the device's full output circuit current instead!

The reason for this unorthodox design parameter is that it was desired to actually incorporate a standing electric arc field into the output circuit, to take advantage of the electron's inherent ability to absorb quantum background energy [including *zero point energy*, if and as necessary]. As a result of a thorough study of lightning, the inventor of the StarDrive device reasoned that the electrons comprising any naturally-occurring bolt of lightning had to *recover* (or absorb) an amount of ambient photonic energy equal to that which they expended in transit – in order to satisfy the conservation of energy principle. In such a case, it is not necessary that "we" do the *work* of moving charge *against* a potential gradient; the work may be done by the charge itself in being attracted *along* the potential gradient (or voltage level).

And since it is known from the field of welding that it takes less energy to sustain an arc than it does to initiate it, it therefore becomes possible to create an electrical circuit that outputs more energy than it requires as input. This is exactly what the EDF Generator does – by incorporating a standing arc field in its output circuit. Using the StarDrive device as our mechanism, "we" only provide the work-energy required to establish and maintain the external field's potential gradient, by initiating rotor rotation and bringing the thermoelectric elements up to temperature. The electrons in the electrodynamic field do all the rest . . .

Further Notes from the Inventor

In conjunction with one of our *StarDrive Generator* prototype project funding proposals, we are presently working on an interim proof-of-concept experiment for our proposed 24 kW air-cooled EDF Generator prototype. This full-scale mock-up of the 30"-dia. Generator's rotor and dual induction ring assemblies is intended to demonstrate the fundamental design principal discussed at the close of the Technical Overview (linked to our website's Method of Operation Summary page), whereby the voltage electrostatically induced on the rotor anode rings which power each Primary Array should be roughly one-third (1/3) of the Field Coil voltage (because of the capacitive dual induction ring geometry of the Primary Power System). For safety reasons, the Field voltage in all *air-cooled* StarDrive *Generators* will be limited by design to 850 VDC, and to 1,400 VDC in the larger *liquid-cooled* StarDrive *Dynamos*.

The experiment will also assist greatly in the derivation of remaining production model specifications, and will in fact incorporate production-quality rotor segments and electrode rings. Should this proof-of-concept experiment be successful, not only will the ability of our over-unity 24 kW Generator prototype to deliver large-scale DC output that's compatible with standard AC inverters (for utility grid distribution or off-grid conventional use) be virtually assured, but a major milestone incentive in our existing funding proposals will have been fulfilled as well. Further updates like those below will be forthcoming on the *News* page of http://www.stardrivedevice.com.

01/28/03 - International Patent Filings Secured!: We are very pleased to report that we were successful in our efforts to secure numerous international (PCT) Patent Application filings for the *Electrodynamic Field Generator* by the final deadline of January 21, 2003! These important filings were effected in Australia, Canada, the People's Republic of China, the European Union (including France, Germany, Italy, Spain, and the United Kingdom), India, Japan, Mexico, the Russian Federation, and South Africa.

The securing of these key Patent Application filings adds immeasurable value to our StarDrive Engineering Project overall, as it will greatly protect and enhance our investors' upside global market potential (assuming, of course, that our *24 kW StarDrive Generator prototype* is successful)! Be sure to check back from time to time for further updates as we proceed into the development phase of the Project.

11/07/02 - Academic Reference: Those of you kind visitors to our website who would like to have the benefit of an informed and unbiased academic opinion regarding the Electrodynamic Field Generator are welcome to contact John J. Tulip, Ph.D., Exec. Vice-Pres. of *American International University*. This consideration also applies of course to those parties who may be interested in securing a direct participation in our forthcoming EDF Generator Prototype Project. Dr. Tulip has not only expressed much-appreciated support of our efforts to introduce this important new technology, but has also had the opportunity to review our technical manual *StarDrive Engineering*. You may contact Dr. Tulip via e-mail at TulipJJ@aiuniversity.edu although we ask that you expect him to field serious and respectful inquiries only. Should you desire to speak with him by telephone, please be assured that he will endeavor to return your call whenever circumstances permit if you provide him with the proper phone number.

10/07/02 - Joint Venture Agreement Announced!: Mark Tomion, founder and president of Archer Enterprises and inventor of the recently-patented *Electrodynamic Field Generator*, is very pleased to announce that he has signed a Joint Venture Agreement with Affirm Technology Partners of Carlsbad, California to build a working prototype of his over-unity 'StarDrive' device's electric power output variant. The co-developers are planning to commence construction of a small air-cooled **StarDrive Generator** unit with a projected output rating of 24 kW and a housing diameter of only 30 inches, at a total weight of under 50 lbs., before the end of November 2002.

Should this exciting project be successful, it would represent an historic milestone in the development of over-unity electric power generation technology. Not only is this small prototype EDF Generator expected to demonstrate *a minimum Coefficient of Performance in excess of 20:1*, but the design employed is completely linearly-scalable in a very broad range of sizes that would include liquid-cooled ***StarDrive Dynamo*** units with output ratings of up to 1 gigawatt! The most remarkable feature of these large Dynamo units is that an amount of recoverable thermal energy comparable to their respective electrical outputs will be made available for desalinating seawater, or for use in centralized municipal and industrial hydronic heating systems. And this capability would make the large-scale desalinization or distillation of water truly cost-effective for perhaps the first time ever.

Interested parties are welcome to contact Mr. Tomion at office@stardrivedevice.com (585-526-6817) for further information.

INFINITE ENERGY
Cold Fusion and New Energy Technology
Including Conventional and Renewable Energy

Infinite Energy Magazine

* Cold Fusion * New Energy
* New Science
* New Technology
Subscriptions, 6 Issues Per Year
$29.95 North America
$49.95 Foreign
Single Sample Copy
$5.95 North America, $10.00 Foreign

Infinite Energy Magazine
P.O. Box 2816-FV
Concord, NH 03302-2816
Phone: 603-228-4516 Fax: 603-224-5975
http://www.infinite-energy.com

Institute for Planetary Synthesis

P.O. Box 128, CH-1211 Geneva 20, Switzerland

Tel. 41-022-733.88.76,
Fax 41-022-733.66.49
E-mail: ipsbox@ipsgeneva.com
website: http://www.ipsgeneva.com

Prospects of Hydrogen Energetics

Ph.M. Kanarev, Russia

E-mail: kanphil@mail.kuban.ru

Hydrogen is the only pollution free and inexhaustible energy carrier. But the implementation of such attractive properties of hydrogen is restrained by large expenses of energy for its production from water. Modern level of knowledge gives the opportunity to reduce these expenses [1], [2], [3].

It is known that a gram-atom is equal numerically to atomic mass of the substance, and a gram-molecule is equal numerically to molecular mass of the substance. For example, the hydrogen gram-molecule in the water molecule is equal to 2 grams, and the oxygen gram-atom is equal to 16 grams. The gram-molecule of water is equal to 18 grams. As the mass of hydrogen in the water molecule is 2x100/18=11.11% and the mass of oxygen atom is 16x100/18=88.89%, the ratio between quantity of hydrogen and oxygen is preserved in one litre of water as well. It means that 1000 grams of one litre of water contain 111.11 grams of hydrogen and 888.89 grams of oxygen.

One litre of hydrogen has mass of 0.09 grams, one litre of molecular oxygen has mass of 1.47 grams. It means that from one litre of water it possible to produce 111.11/0.09=1234.44 litres of hydrogen and 888.89/1.47=604.69 litres of oxygen. Thus, one gram of water contains 1.23 litres of hydrogen [1].

Now energy consumption for production of 1000 litres of hydrogen from water is 4 kWh and of one litre – 4 Wh. As it is possible to produce 1.234 litres of hydrogen, then 1.234x4=4.94 Wh are spent for production of one gram of water now.

Instruments and Equipment Used for the Experiment

A special experimental low current electrolyzer, a voltmeter of the highest accuracy (accuracy class 0.2, GOST 8711-78), an ammeter of the highest class of accuracy (accuracy class 0.2, GOST 871160), a balance with value of a division of 0.10 grams and 0.010 grams, and a stopwatch with value of a division of 0.1s.

Experimental Results

Indices	Sum
1 – duration of electrolyzer operation connected to the supply line, in 6 cycles t, min	6x5=30.0
2 – readings of voltmeter V, volts	13.6
3 – ammeter readings I, amperes	0.02
4 – power consumption (P=VxIxτ/60), Wh	0.136
5 – duration of electrolyzer operation disconnected from the supply line, in 6 cycles t, min	6x55=330.0
6 – solution mass change m, grams	0.44
7 – mass of evaporated water m', grams	0.02x6=0.12
8 – mass of water converted into gases m''=m-m', gram	0.320
9 – power consumption per gram of water converted into gases P'=P/m'', Wh/grams of water	0.425
10 – existing power consumption per gram of water converted into gases P'', Wh/grams of water	4.94
11 – reduction of power consumption for hydrogen production from water, K=P''/P', times	11.62
12– quantity of released hydrogen, ΔM =0.320x1.23x0.09=0.035, grams	0.035
13 – power content of hydrogen being produced (E=0.035x142/3,6)=1.397, Wh	1.397
14 – energy efficacy of water electrolysis process (Ex100/P), %	**1027**

Note: Gas output is clearly observed during many hours after the electrolyzer is disconnected from the electricity supply.

Conclusion

Low ampere water electrolysis is a way for production of inexpensive hydrogen from water and hydrogen energetics.

References

1. Ph.M. Kanarev. The Foundation of Physchemistry of the Micro World. Krasnodar, 2002. 320 pages
2. http://book.Kanarev.innoplaza.net
3. hppt://www.n-t.org/tp/ns/if.htm.

Heater Producing Healthy Effect

The First Device of Healthy Life Support in Fuel-Energy Industry

A. Belyaeva, L. Savelyeva, O. Bondarenko, Kirghizia

http://www.leteco.h1.ru
Email: leteco@mail.ru

Nowadays problems of rational use of resources including energy resources are very important. Lack of energy-efficient technologies causes consumption of great amount of electric power, coal, and mineral oil. From another hand, in the XXI century one of the main approaches of human society development is turned to healthy life-style and development of ecologically appropriate technologies. Hence, basic direction of heating systems development should correspond to, at the least, two requirements, i.e. effectiveness (energy-saving) and ecological appropriation (ecological functioning). Moreover, it is necessary to take into account additional requirements for modern works:

- Relatively low prime cost of the systems;
- Minimal operating costs;
- Availability of a system of temperature mode control;
- Use of domestically produced materials for the systems.

The aim of the work is creation of a universal electric device of natural ecologically appropriate materials. The device should maintain relative air humidity of natural atmosphere in a quarter, make its ecology healthier, meet all the listed requirements, and represent new generation energy-saving system designed for heating of industrial and domestic areas according to features of technical solution.

A.L. Belyaeva is the author of this work. The invention of this heating device was acknowledged as the best invention of Kirghiz Republic of the last two years. A.L. Belyaeva was called as a laureate of a competition of “The Best Inventing in Kirghiz Republic in 2001-2002”.

Solving this problem the author based on work experience existing in the area of semi-conductors production. Actually, the model was worked out in the common area of electric engineering and industrial crystals growing. Using of knowledge and skills of the both areas made creation of this device possible.

It should be noted that initially the invention of the heating device, which is discussed here, was connected with necessity to improve microclimate and air atmosphere in a semi-conductor shop since the industrial process required optimal conditions. Hence, the device was observed as an element of the industrial process. However, soon other positive characteristics of the device were disclosed, i.e. when it was installed in a quarter all visible mould disappeared. Laboratory investigations stated that the operating device annihilated all pathogenic microflora. This rediscovered feature allowed using the device both in domestic and industrial area. After series of following laboratory investigations and bench tests construction of the device was changed and improved that allowed prepare it for line production.

Ceramic electroconvector: general characteristics

The working name of the final version of the model is *Ceramic Electroconvector TY 2971-006-22997241-2002.* Ceramic Electroconvector is an industrial and domestic electric heater of direct stationary action. It has high effective heat emission and satisfies ecological, sanitary, medical, and fire-prevention requirements.

At the same time it should be mentioned that by several characteristics this electroconvector differs from other known models of electroconvectors as well as from other existent heaters. It may be observed as a representative of an independent, specially created group of heating devices.

One of the main characteristics of the electroconvector is presence of constructive heating carbonic elements made of ecologically appropriate natural *non-metal* materials. Essentially, the electroconvector construction does not contain metal (the only metal part of the device is its supporting construction).

Production of heat of physiologically comfort zone requires 0.3 kW/h energy consumption which is 3-10 times less than energy consumption of known models of heating engineering. The Ceramic Electroconvector influences positively on ecology of a room. Room heating occurs better and more softly as conducting carbonic elements can be heated maximally up to 100° C. As a result oxygen is not burnt, and air is not overdried in a room. Achieved minimization of metal content in the constructive elements of the device increases the level of ecological compatibility both of electroconvector constructions and operation.

The device accumulates no static electricity, neutralizes harmful magnetic field generated by alternating current in the conducting element (it is typical for all the other electrical household appliances). Therefore, **the additional positive effect** is produced and higher ecological characteristics of functioning of this electroconvector are confirmed.

Insulating strength of ceramics prevents electrical shock accidents. Ecological compatibility of the electroconvector is provided by materials of the construction. The base of the device is a studied natural silicate fiber which has quantitative and qualitative content of useful chemical elements which are the closest ones to the group of medical adsorbents listed in a medical encyclopedia. The ceramics is adjusted to emit electromagnetic waves only in infra-red spectrum.

The electroconvector produces heat waves in the average IR spectrum (8.4-8.6 mkm) which is maximally approximated to the diapason of heat waves generated by a human (9.37 mkm). It annihilates humidity of buildings independently of outer space humidity. At the same time it neither burns oxygen nor overdries air.

Healthy effect is produced by all the constructive elements made of ecologically appropriate natural materials. Electric power is transformed into heat emission by conducting elements. This process causes a mode of generation of a continuous heat spectrum of radiation. The heat radiation is similar to heat spectrum of radiation generated by a human. At the same time, this feature together with resonant oscillations of the crystal lattice of the ceramic cylinders produces a destroying effect on pathogenic and conditionally pathogenic microorganisms.

From the point of view of room ecology the proved healthy effect of the operating electroconvector becomes very significant. The effect considers continuous presence of a human in the room, i.e. risk of pathogen infection through respiration objectively decreases.

Application of the ceramic electroconvector is especially actual in patient care institutions and children's institutions, in special precision industries and space technologies. It can also be used in saunas with dry vapor.

The ceramic electroconvector is designed for unsupervised continuous work.

Structure of the electroconvector producing the healthy effect

Shortcomings of known electric heaters are: great electric power consumption (0.75-3.0 kW/h), big number of metal details, complex technical performance, and use of a necessary additional blower as a ventilator. Big number of metal details decreases ecological compatibility and productivity of the heaters. The listed devices have to use high temperatures on heat-release surfaces for warming up rooms up to the level of physiological comfort. This causes increase of energy consumption. Moreover, using of metal heating elements influences on air and relative humidity in the room. According to available data, no existent electroconvectors have healthy influence on ecology of a room.

The represented ceramic electroconvector contains a carrying frame with horizontal boards which have convective gaps. The carrying frame has heat-release monolithic hollow ceramic cylinders whose walls contain longitudinal through holes. Heating carbonic conducting elements and de-energized carbonic rods are built in the through holes. The heating conducting elements are connected in parallel-series circuit at the output of the cylinders with it's ends placed into insulating supports of the carrying frame.

Constructive heating elements are the main differences of the device. All the heat generating constructive elements, i.e. conducting and de-energized heating elements, as well as heat-release surfaces of ceramic cylinders have contiguous spectra of infra-red radiation.

Energy-efficient effect

The electric scheme of connection of the conducting elements provides different modes of work of the device. According to these modes, energy consumption is in the interval of 0.05-0.3 kW/h. The mode of 0.05 kW/h is calculated on a supporting level of warming-up of a room. Maximal energy consumption (0.3 kW/h) corresponds to the superior limit of the temperature mode of heating of working heat-release surfaces of the ceramic cylinders. In this case temperature of the heat generating elements, i.e. de-energized carbonic rods and conducting carbonic elements) lies in the limit of max 100°C. This produces a significant potential resource of electric strength and of durability of the used elements. The de-energized carbonic rods function as heat accumulators at switching on and switching off the device. Heating the conductors the de-energized rods accumulate heat through the ceramic walls of the cylinder till their temperature becomes equal to the temperature of the conducting elements. Appearing electromagnetic resonance between the conductors and the de-energized carbonic rods intensifies infra-red radiation of the ceramic wall. Accumulative heat potential of the de-energized carbonic rods allows maintain uniform radial heating of the heat-release ceramic surface of the cylinder without decreasing energy consumption. In this case additional conducting elements of infra-red radiation become unnecessary.

The heating efficiency of the ceramic electroconvector was estimated by independent experts. Surface density of the radiation flow was calculated by formula of Stefan-Boizmann distribution law. Taking into account heating of the cylinders' surfaces up to 70° C this value came to 727 W/m^2. **Total heat generated by the electroconvector per hour comes to 600 kcal or 698 W** at the total area of the radiation surfaces of 0.96 m^2 (on the basis of 1 kcal=1.163 W/h according to [1]). The electroconvector consumes 300 W/h and produces 698 W/h. That is to say that it effectively transforms electric energy into heat energy. Operational modes of the electroconvector are based on analysis of the heating effect produced by different devices, i.e. a tube metal heater (TMH) having a conducting metal element of Nichrom, a ceramic cylinder having a Nichrom conducting element, and a ceramic cylinder having a conducting element of carbonic ribbon. The carbonic ribbon produces high heating efficiency. Temperature on the surface of the ceramic frame is up to 80° C and temperature on the conducting element is 100° C. Hence, the device equipped with the conducting element of the carbonic ribbon does not produce excessive heat radiation.

The electroconvector consumes 300 W/h and produces 698 W/h.

After one-year operation of the preproduction models in a private school it was noticed that number of respiratory illnesses and influenza among the pupils slumped, condition of skin became better, attacks of bronchial asthma among the teachers stopped, and allergic itch left the patients who suffered from allergy. A side effect was that flowers began to grow better, and those which had not blossomed began to blossom at least. Obviously, a combination takes place there: air cleaning of microorganisms, humidity normalization, warming comfort, and influence of pyramidal ceramic structures on water vapors which are transported by warm blasts.

Applied Know How

Ambient air in rooms is a complex substance including various chemical compounds, ions, dust parts, water vapors, infectious and potentially infectious microflora, etc. The electroconvector is represented by a ceramic hardphase crystal structure. Cold air blast moves close to the ceramic surface. It meets combined oscillation of crystal microlevel structures of ceramics. *Filtering electromagnetic screen* appears that breaks shell of pathogens and potential pathogens. It is a performance of **sanitation properties**. Atmospheric water contacts with structures of ceramics, then it is cleaned and structured. After that water cleans air which is breathed in by a human. Hence, the organism becomes healthier. It is a performance of the **healthy effect**. A clean room warmed uniformly improves human's health.

Main Performance Attributes of the Ceramic Electroconvector Producing Healthy Effect

Nominal required power	0.05-0.3 kWt/h
Voltage of the feeding network	220 ± 22 V
Frequency of alternating current	50 Hz
Temperature of the conducting element in operation mode	50…110° C
Temperature of the heat-release surface of the cylinder	39…90° C
Surface density of radiation flow	727 Wt/m^2
Quantity of radiated heat	600 kcal/h
Class of protection	1
General area of heat-release surfaces of the cylinders	9600 cm^2
Sizes	410 x 400 x 75 mm
Weight	18-21 kg
Durability	30 years

The ceramic electroconvector is designed as a floor construction for repetition work.

References

1. Heat Engineering Reference-book, Moscow, Energy (Energia), 1975, V. 1, p. 12.

About the author

After graduating from Polytechnic University of Frunze city Alexandra L. Belyaeva (1953) participated in launching of semiconductor production. She was given a rank of Perfect Inventor and Rationalyzer for invention and rationalization action. In 1987 her invention named Method of Production of Monosilicon Seed Crystals was introduced into manufacture, according to close copyright of USSR. Since that year this introduction has allowed grow monosilicon having better semiconductor properties. She was given a rank of Inventor of USSR for the invention.

Alexandra L. Belyaeva has acknowledged and given a rank of Inventor of Kirghiz Republic. Since 1994 in collaboration with Russian specialists of ceramics she has been dealing with organization of ceramic productions in Kirghizstan. Here are the inventions by Belyaeva: Method of Production of Seed Crystals and Its Variants (Patent #42 KG), Ceramic Mass for Insulators' Production (Patent #43 KG), Ceramic Mass Having Heat-Radiating Properties (Patent #464 KG).

In 1992 Belyaeva was rewarded with a Silver medal of VDNH (Exhibition of Achievements of National Economy, Moscow) for development of technologies for production of constructive nitride-cadmium items of semiconductor wastes.

Her Method of Production of Nonexpendable Seed Crystals is at introduction stage. The seed monocrystals produced by the new method will allow grow ribbon monocrystals having certain properties. It will be possible to produce items made of the monocrystals which will meet requirements of energy-saving and ecological appropriation. These devices represent non-aging powerful energy sources, various semiconductive devices with no inner microdeffects and with unlimited durability, structural water filters.

Since 2002 she has been dealing with organization of production of ecologically appropriate industrial-domestic appliances causing healthy effect. The invention of Ceramic Electroconvector Producing Healthy Effect is now introduced. Energy-saving of the new ecologically appropriate electroconvector exceeds energy-saving of all the existent heating systems.

Belyaeva is a laureate of competition of The Best Inventing in Kirghiz Republic in 2001-2002.

Inertial Propulsion Device

Vitaly E. Senkevich, Russia

E-mail: hhhhha@mail.ru

A body is at rest or moves linearly and uniformly until it is not influenced by an external force.
(School course of physics)

Forget everything that you were taught at school.
(Arkady Raykin)

This propulsion device consists of an engine and a body. The engine (see Fig.1) is remarkable for its movable stator (S) which can make free rotation as well as a rotor (R). When the engine starts the stator and the rotor begin to rotate in opposite directions. Thus the engine has two ends and one of them is connected to a flywheel (F). This flywheel begins accelerated rotation.

A cross-beam (CB) is connected to the second end of the engine where a rotating momentum appears. Under the influence of this momentum the cross-beam presses down one of the supports placed on the body (for example, Sup.1). As a result a force which is compensated by acceleration of the flywheel (F) appears on the support. When the flywheel is accelerated up to certain speed a control system (CS) switches the windings of the engine to change the direction into the opposite one (reverse). At that the cross-beam also tends to turn to the other side and presses down the second support (Sup.2). Thus the cycle repeats. It should be noted that forces acting at the supports are **codirected** and they move the whole device.



Fig.1

About the author

After graduating from Polytechnic University of Frunze city Alexandra L. Belyaeva (1953) participated in launching of semiconductor production. She was given a rank of Perfect Inventor and Rationalyzer for invention and rationalization action. In 1987 her invention named Method of Production of Monosilicon Seed Crystals was introduced into manufacture, according to close copyright of USSR. Since that year this introduction has allowed grow monosilicon having better semiconductor properties. She was given a rank of Inventor of USSR for the invention.

Alexandra L. Belyaeva has acknowledged and given a rank of Inventor of Kirghiz Republic. Since 1994 in collaboration with Russian specialists of ceramics she has been dealing with organization of ceramic productions in Kirghizstan. Here are the inventions by Belyaeva: Method of Production of Seed Crystals and Its Variants (Patent #42 KG), Ceramic Mass for Insulators' Production (Patent #43 KG), Ceramic Mass Having Heat-Radiating Properties (Patent #464 KG).

In 1992 Belyaeva was rewarded with a Silver medal of VDNH (Exhibition of Achievements of National Economy, Moscow) for development of technologies for production of constructive nitride-cadmium items of semiconductor wastes.

Her Method of Production of Nonexpendable Seed Crystals is at introduction stage. The seed monocrystals produced by the new method will allow grow ribbon monocrystals having certain properties. It will be possible to produce items made of the monocrystals which will meet requirements of energy-saving and ecological appropriation. These devices represent non-aging powerful energy sources, various semiconductive devices with no inner microdeffects and with unlimited durability, structural water filters.

Since 2002 she has been dealing with organization of production of ecologically appropriate industrial-domestic appliances causing healthy effect. The invention of Ceramic Electroconvector Producing Healthy Effect is now introduced. Energy-saving of the new ecologically appropriate electroconvector exceeds energy-saving of all the existent heating systems.

Belyaeva is a laureate of competition of The Best Inventing in Kirghiz Republic in 2001-2002.

Inertial Propulsion Device

Vitaly E. Senkevich, Russia

E-mail: hhhhha@mail.ru

A body is at rest or moves linearly and uniformly until it is not influenced by an external force.
(School course of physics)

Forget everything that you were taught at school.
(Arkady Raykin)

This propulsion device consists of an engine and a body. The engine (see Fig.1) is remarkable for its movable stator (S) which can make free rotation as well as a rotor (R). When the engine starts the stator and the rotor begin to rotate in opposite directions. Thus the engine has two ends and one of them is connected to a flywheel (F). This flywheel begins accelerated rotation.

A cross-beam (CB) is connected to the second end of the engine where a rotating momentum appears. Under the influence of this momentum the cross-beam presses down one of the supports placed on the body (for example, Sup.1). As a result a force which is compensated by acceleration of the flywheel (F) appears on the support. When the flywheel is accelerated up to certain speed a control system (CS) switches the windings of the engine to change the direction into the opposite one (reverse). At that the cross-beam also tends to turn to the other side and presses down the second support (Sup.2). Thus the cycle repeats. It should be noted that forces acting at the supports are **codirected** and they move the whole device.



Fig.1

Unlimited Accelerated Nonreactive Motion

by G.P. Ivanov

Information from http://tts.lt/~nara/ruspopul.htm

Bias of centre of inertia of the closed system is a phenomenon exceeding the bounds of modern scientific conceptions. At the same time it is a way to the new marvelous world of earlier unknown laws and phenomena of nature. Researches made by G.P. Ivanov, Russia, have allowed him come to the following conclusion: it is a quite realizable task to create technical devices which can move under the action of nonreactive forces. However a purposeful scientific-research spade-work is required for the reliable registration of them by modern experimental facilities. According to the author during the whole XX century the known idea of latent impulse were misleading the scientists from the serious research of impulse-energy processes existing in systems at the presence of quasi-stationary electric and magnetic fields. According to G.P. Ivanov, it is related with the fact that the notion of "latent impulse" has nothing in common with the real momentum, since the very existence of "latent impulse" and "latent energy" which attends it, would make it impossible, for example, to adjust radio equipment since all effective capacitances change their value a hundred and thousand times as much (it depends on their orientation with respect to the magnetic field of the Earth).

Fig. 1, 2 demonstrate the patented by G.P. Ivanov method of realization of nonreactive motion (G.P. Ivanov, Yu.G. Ivanov. Method for production of propulsion. Patent #2172865, M., 2001). Fig. 1 demonstrates a device which consists of magnetized core with the attached metal electrodes.



Fig. 1
The simplest "nonreactive" element

When alternating voltage is applied the device together with the center of inertia of the whole system (including power source and lead) will oscillate under the action of nonreactive force. It will move along the direction which is perpendicular to the vectors of electric and magnetic fields inside the core.

On Fig. 2 there is an analogous device supplied with a cylinder core. Magnetization of the core is defined by current of the coil which is wound around it (see Fig.2).


Coil of the core remagnetization
Internal electrode
Core made of magnetic dielectric
External electrode

Fig. 2
Diagram of the device which can be in unlimited accelerated nonreactive motion

Let us supply the electrodes of the device with such voltage which is enough to change field density in the core (for example, according to the law $E = E_0 \sin\omega t$), and the coil with voltage enough to change the magnetization (according to the law $M = M_0 \cos\omega t$). Then nonreactive force which is constant in its direction will act on the device along the axis of the cylinder. The average of the force is $F_{cp} = \pi f E_0 M_0 V/c^2$, where E_0, M_0 are the amplitudes of density values of the electric field and amplitudes of the core magnetization, **f** is frequency, **V** is core capacity. As a result the device can either move with acceleration or act against external forces. The researches allow the author to prove the validity of the following theorem: **At motion of the open-loop system (device) the work made by nonreactive force could not be realized by means of decrease of energy of the proper (appurtenant to the system) power source.** Where this energy comes from if there are no artificial power sources outside the device? However everywhere there is such form of matter as electrovacuum. It allows us come to a conclusion that nonreactive forces make work by means of decrease of electrovacuum energy.

Existence of electrovacuum does not contradict to the modern physical picture of the world. On the contrary providing the realization of laws of momentum and energy conservation, this idea originates from and organically supplements it. The theory of electrovacuum opens quite realizable prospects in different fields of human activity which seem to be fantastic and impossible. It also proposes unusual ways to solve many problems which are considered as insoluble. For example, it becomes possible to create nonreactive cosmonautics and private aircrafts. Energetics will be changed beyond recognition since power sources which require no material fuel will occupy the place of big and small modern electric power stations. The analogous list could be continued. There are presented quite realizable prospects related to inexhaustible reserves which are hidden in the ambient space.

Revolutionary Current

Suresh Kumar Baliyan, India

E-mail: suresh_baliyan@rediffmail.com
suresh_baliyan@yahoo.com

*Electricity is one of the most wonderful inventions of the 18th century. It can be produced by various methods in which different types of energy are used such as mechanical or chemical energy. In this article we discuss a new type of methods in which **electrostatic energy** is used.*

In this method we use **electrets** as an energy source. Electrets are permanent polarized dielectric material which is made by cooling dielectric material in a high intensity electric field. When we place an electron in the electric field of a point charge, it is influenced by a force. If the direction of the force is such that the electron moves in a closed path then it represents a current in the opposite direction along the closed path. Here closed path means a metal wire loop in which the electron movement is responsible for the current.

The charge of the electrets remains constant for many years (100) and there is no loss of energy because we use only the property of electrets that they apply force when a charge is placed in its electric field. Since here we create energy in the form of electric current then it violates the Law of conservation of energy.

Let us discuss the method in three steps:

1) Fundamental
2) Equivalent circuit
3) How we can use it as a potential source of electricity.

1. When we put a metal rod in the electric field of a point negative charge then the electron is influenced by repulsion force which moves in arrow direction and the electric field is cut by putting an earthed metal plate from any direction. When we place four charges on the corner of the metal frame and shield the electric field in particular direction as shown in Fig.1 then the force on the electron which is placed in metal frame will be in the direction of arrow and this makes a loop. The force influencing on the electron will be continuous, so the current which moves in direction opposite to the electron movement will induced in the metal frame.

2. The equivalent circuit of Fig.1 is shown in Fig2. It demonstrates that a 'V' volt battery and a resistance 'R' can be replaced by an arm of the metal frame. The polarity of the battery is shown in Fig. 1. A current of magnitude (V/R) will be induced in the circuit by this method.



Fig. 1a



Fig. 1b



Fig. 2



Fig. 3

3. We can use another device as a potential source (see Fig3.). Let us take an electret and make a hole at the centre. A hollow thin walled metal cylinder is fitted in the hole and a metal frame is taken as shown in the Fig. 3. We can use this metal cylinder as an electric field shield which may affect the direction of the force influencing on the electron. We may use this device as a potential source of electricity which will give electricity until the charges on the electrets vanish. The charge on the electrets remains constant for many years. Thus we can create energy and the problem of energy shortage can be solved by this method forever. We are trying to make a prototype of this but due to lack of equipment facility we are not able to demonstrate a working model. However we are trying to modify it.

NEWS REVIEW

Russian scientists are preparing new application of energy of geothermal waters

http://www.sciteclibrary.ru

A way for economical use and utilization of energy of geothermal waters was found in the Institute of Geothermal Problems (Russian Academy of Sciences). The new technology can be applied for heating in different purposes, and can compete with the power engineering, which uses the conventional energy carriers.

Geothermal springs are ideal for generating electricity by means of using of their permanent heat. This is especially important for Kamchatka, which is rich in these springs; however they are almost never used in mass power engineering, but only serve as an attraction for tourists, who admire beauty of Kamchatka geysers. At the same time the region itself freezes every year because of shortage of fuel for electric power stations.

What prevents us from using the geothermal springs?

The problem is that the storages of most of geothermal water fields have low and medium temperatures. This does not allow providing their competitiveness as regards conventional energy carriers. During tens of years this fact was an obstacle to the development of geothermal energy.

A solution was found in the Institute of Geothermal Problems. It was brought out that at many exploited geothermal fields wellhead overpressure exceeds 5-10 MPa and more. These waters contain fair quantity of dissolved organic gases. The scientists have found out that methane content of these waters exceeds 90 %. And until now at exploitation of the fields these types of energy have not been properly utilized.

The scientists of the Institute of Geothermal Problems have developed a technology of the optimum utilization of energy of geothermal waters and have increased the thermodynamic effect of the process.

This aim was fulfilled by means of transmission of thermal energy of geothermal water through the intermediate heat exchangers to the secondary heat carrier. Chemical energy of dissolved gases was used as an additional source of energy. The transmission was held by the use of primary and secondary separators. The distinctive feature of their technology is that associated potential energy of geothermal water is used as an additional source of energy. Expander and compressor placed on the same shaft are used as potential energy converters. Gas-holder and gas control point are used for utilization of energy of dissolved gases.

Thus on the bases of this technology geothermal energy can be effectively developed that will be competitive with fuel hydrocarbon energy.



Tilley Electric Vehicle

Tilley Foundation, Inc.

131 Hiwassee Road
Lebanon, TN 37087
http://www.tilleyfoundation.com
E-mail: cktilley@bellsouth.net

Editor: The advantages of electric vehicles were proved more than once. No fuel is required to set them in motion. Along with evident advantages of electric vehicles, such as their powerful characteristics and harmlessness for environment there is a side benefit, i.e. much less maintenance as compared with gasoline or diesel-fueled vehicles is required. Moreover it is easier to manufacture such vehicles.

In the previous issues of New Energy Technologies magazine we have already acquainted our readers with Tilley Electric Vehicle designed by Carl B. Tilley (USA). Below there is some up-to-date information and photos from the inventor. Besides we also publish an article devoted to the similar types of fuel-less motors.

After several years of personal accomplishments in the alternative energy industry, Carl B. Tilley was convinced that it was possible to build an electric car that could be powered without the help of external power to keep the battery charged.

The concept to produce a useful electric performance car that would last more than a few hours and would be economical to run, safe to drive around town or across the United States and never use a drop of fuel challenges the future of transportation as we know it today.

With the establishment of the Tilley Foundation, Inc., in the year 2001, Carl Tilley set out to prove it could be done. It was an ambitious project and it broke ground on the facility in Tennessee that would build the first self generating electric car.

...you have no need for fuel and you do not have to stop the vehicle to charge it after driving.

Construction of a 1,800 square foot building, that was powered with another recently developed electric device, began in the year 2002. Electricity from the building built the car from a different energy invention, that was void of any outside power supply. It is ironic that one alternative energy device actually built the invention to power and build the electric car.

From the selection of the proper car to be converted, to the advanced technology which is on board , the **Tilley Electric Vehicle TEV** performs comparably to gasoline powered vehicles. The difference is you have no need for fuel and you do not have to stop the vehicle to charge it after driving. There is no pollution and you can cruise the highways at the same speed as any other vehicle.

The rear mounted electric motor provides over 130 SAE net horsepower at 5,500 rpm. It offers a 3 speed automatic transmission that is smooth shifting and totally silent running. All this is combined with rack and pinion steering and a 35/65 rear weight bias that enables fast, sensitive handling and needs no power assistance.

...battery system will be fully charged at all times while in use.

It has 4 wheel disc braking for fast progressive, fade-free stopping. Counterbalanced gull-wing doors need only 14 inches of clearance. The rear sporty louvers are aerodynamic designed so that it almost eliminates any drag effect. All this with a stainless steel body makes for a great car.

Control center for the battery bank only allows what is needed to keep the batteries charged while in operation no matter what the speed or discharge from the battery bank. Your battery system will be fully charged at all times while in use. Simply get in, start the car and drive like any other vehicle.

A 1981 DeLorean was converted as the Tilley Electric Vehicle.Conversion of the car began in late June of 2002. State of the art metal fabrication to construct support for the electric motor, battery bank, control center and the TEV device was completed in July of 2002.

Several tests were made to validate the TEV technology. One of the last tests was made on September 7th, 2002. It has been demonstrated that after 17.3 miles driven on the Superspeedway at speeds ranging from 80MPH to 96MPH independent engineer certified batteries were full.

Assembly Pictures (see also the cover page)

Photos by Robert Gaither



Fig. 1
Removing Gas Motor



Fig. 4
Fitting Parts



Fig. 2
Fabrication



Fig. 5
Transmission Work



Fig. 3
Drive Motor



Fig. 6
Motor Mounted



Fig. 7
Making Connections

Fig. 8
About Ready



Fig. 9
Special Wiring &Guages

Fig. 10
Car Unveiling

Trends in the Application of Motor-Generators

Adrian Akau, USA

E-mail: adrianakau@aol.com

If the Tilley generator-motor should enter into the world market, some curious consequences may result, the most important being the transition of the Honda and Toyota hybrid cars into full fledged electrics.

First of all, a comparison should be drawn between the Tilley and the two hybrid cars presently being sold, the Honda Civic and the Toyota Pirus should be made.

The Honda Civic and the Toyota Pirus both use charging systems with a gasoline motor for better milage. The Tilley motor-generator is a stand-alone electric vehicle. The Honda motor-generator is just 60mm thick and provides (10kW or 13hp). The Toyota Pirus has a 44hp unit (American Version) which feeds power into electric motors at the wheels. Both Honda and Toyota gasoline motors are off at 0 mph. Only the electric system is used until the power demand reaches 10 kW; then the gasoline motor automatically kicks in. The Pirus is able to get higher milage in city driving than in country driving from the fact that the ratio of the power from the electric part to power to the gasoline part of the motor is greater at lower than at higher speeds, that is, less power is needed to run the car in city driving than in country driving because of the lower speeds and air resistance.



Fig. 7
Making Connections



Fig. 8
About Ready



Fig. 9
Special Wiring &Guages

Fig. 10
Car Unveiling

Trends in the Application of Motor-Generators

Adrian Akau, USA

E-mail: adrianakau@aol.com

If the Tilley generator-motor should enter into the world market, some curious consequences may result, the most important being the transition of the Honda and Toyota hybrid cars into full fledged electrics.

First of all, a comparison should be drawn between the Tilley and the two hybrid cars presently being sold, the Honda Civic and the Toyota Pirus should be made.

The Honda Civic and the Toyota Pirus both use charging systems with a gasoline motor for better milage. The Tilley motor-generator is a stand-alone electric vehicle. The Honda motor-generator is just 60mm thick and provides (10kW or 13hp). The Toyota Pirus has a 44hp unit (American Version) which feeds power into electric motors at the wheels. Both Honda and Toyota gasoline motors are off at 0 mph. Only the electric system is used until the power demand reaches 10 kW; then the gasoline motor automatically kicks in. The Pirus is able to get higher milage in city driving than in country driving from the fact that the ratio of the power from the electric part to power to the gasoline part of the motor is greater at lower than at higher speeds, that is, less power is needed to run the car in city driving than in country driving because of the lower speeds and air resistance.

American car companies are beginning to develop their own starter-generators to "save an extra 10% on the gas milage". Are they doing this because they don't want to be left behind in the milage competition or because they really understand the nature of the starter-generator motors used by the companies producing the hybrids?

With the advent of the Tilley motor-generator, a new factor enters into the situation. If the system proves valid, does this mean that Honda and Toyota are out of the running? Hardly not! It is likely that these companies have allowed or even planned for this contingency with larger capacity motor generators which would do a similar job. With their fine cars and superb engineering, the transition from a hybrid to a pure electric might be costly but not too difficult to engineer. Each of the two hybrid companies may already have been built, tested vehicles of this nature. However, since the primary purpose of the car companies is to make money it is doubtful if this full-fledged fossil fuel-less type will be placed on the market unless competition so requires. A car using the Tilley motor-generator might certainly push them in this direction.

Should the Tilley remains undeveloped, one might expect the second level hybrid car to arrive in a few years from Honda and Toyota. These cars should have greater electric generator-motor capacities and smaller gasoline engines. These systems could give small cars much higher gas milage and could also be placed in larger, more elegant vehicles such as the Honda Accord and the Toyota Camrey.

The transition to fuel-less motors should hopefully be slow and painless for both the pocket book as well as the human psych. If scientists cannot be convinced by studying conventional scientific laws on how these motors work, perhaps they will better see the need for the promulgation of new laws in this area.

We know that at the present time, both Honda and Toyota motor generators (M.G.) have a powers assist function while the Tilley stands alone. Let us look at the present situation (we will use the Toyota U.S. M.G. because it is the more powerful version):

Honda and Toyota classify their M.G.'s as permanent magnet types; Carl Tilley says his is and advanced D.C. motor.

Power output:

Honda is given at 10 kW at 3,000 rpm or 13 hp
Toyota is 33 kW at 1,040-5,600 rpm or 44 hp
Tilley is up to 135 hp depending on rpm's

Voltage/Battery (Ni-MH=Nickle Metal Hydride, AH=amp hours)

Honda: 144V, 120 Ni-MH cells@1.2V ea., 6.5 AH
Toyota: 274V, 228 Ni-MH cells@1.2V ea.
Tilley: 144V,12-12V lead acid (Wal-mart), 1200AH

Physical Characteristics of each M.G.

Honda: 60 mm wide
Toyota: unknown
Tilley: 9" dia., 146 pounds

The main effort should be to implement the transition away from the use of fossil fuels. We know this can be done but it takes proper attitude. Proper attitude takes knowledge and knowledge takes willingness to learn. Willingness to learn takes desire to learn and desire to learn takes humility. Unfortunately, humility is a characteristic that many people, especially learned ones lack. *Editor's: Carl Tilley's comments are also given below.*

Very Good...you seem to know what we already were aware of...before we could mass produce our Tilley car I am sure some auto company would come out with basically the same thing...I do believe they already have it and they are just waiting for the right time. The good news is that at least the Tilley car lighted their fire to get them started.

Carl Tilley

Read in the next issue!

In April 12 of 2003 scientific conference "The Time Machine" was organized by Faraday Laboratories Ltd in Moscow. There were presented the reports by V.A. Chernobrov, A.V. Frolov, A.V. Rykov, E.D. Sorokodum, V.J. Kosyev, A.N. Solonyi, V.A. Atsukovsky. There was discussed design of the device made by Faraday Laboratories Ltd. as well as main principles of control on temporal characteristics of physical processes by changing of density of space energy, i.e. aether density according to patent claim.
Details are in the next issue!

Electric Vehicle in Russia

Review by Correspondent Alla Pashova, Russia

The director of *EV* (*Electric Vehicles*) company located in Tolyatti (Russia), Alexander Mukhanov states: “If during 2 centuries intellectual efforts of a scientific thought were concentrated on an electric engine instead of the internal combustion engine then now we would have driven electric vehicles, and the greenhouse effect would not have exist”.

The electric vehicle has driving-wheels which are set in motion by an electric engine, and it is powered by an electric battery. The electric vehicle appeared in Great Britain and France in 1880 and it is significantly older than the automobile equipped with the internal combustion engine.

At the beginning the speed and the fuel distance of the electric and gasoline vehicles were approximately the same. The main disadvantage of electric vehicles was a complicated system of recharge since there were no usual transformers of alternating current into direct one. Hence, the electric vehicle was recharged in a quite difficult way. An electric engine operated on alternating current was used to recharge it. The electric motor rotated a shaft of the generator which was connected to batteries of the electric vehicle. However in 1906 a rectifier which was simple to operate was invented. Despite its principle of operation was quite complicated (mercury vapor was used for transformation of alternating current into direct one) it has given a great stimulus for development of automobile industry.

There were no essential proves of advantage of gasoline vehicles as compared with electric vehicles. Nevertheless, even at that time there was an opinion that electric vehicles run more slowly and to shorter distances. However “gasoline” records were also insignificant and comparable with results produced by the electric vehicles. At the same time producers of electric vehicles did their best to demonstrate the advantages of these vehicles. If you remember, Walter Baker, one of the most famous American constructors and producer of the electric vehicles, achieved the speed of 130 km/h driving his car. An electric vehicle produced by Borland Electric company run from Chicago to Milwaukee (the distance of 167 km/h along non-asphalted road) without recharge. Next day after recharging the electric vehicle returned to Chicago by its own power without meeting any incidents. During the journey its speed came to 55 km/h.

In 1899-1900 a hereditary Russian nobleman Ippolit Romanov made an experiment on designing of the first Russian electric vehicle. Since these vehicles had been designed to run in Saint Petersburg then the city council required to produce them in the same place. In 1899 Romanov’s first electric vehicle was made. Its general design was borrowed from English cabs in which a cabman sat on a high dickey placed behind passengers. Romanov’s electric cab had two passenger seats situated in front of the dickey in a half-cabin having side and back windows. The cabin was equipped with a hood. The seat of a driver was placed behind and above the cabin; a box containing an accumulator was located under the driver’s seat. The vehicle was four-wheeled. Diameter of the front wheels was smaller than those of the rear wheels. The front wheels were fixed by elliptical springs and were driving ones. They were connected to two independent electric motors by a roller chain drive. The regulated rear wheels had a smaller diameter and were fixed by spiral springs.

This first electric vehicle was equipped with lead accumulator which had 36 banks. It required recharging every 60 versts (1 verst – 3500 feet). The total power of both the electric motors was equal to 4 hp. Design of the vehicular part of Romanov’s electric vehicle was borrowed from the models produced by an American company named *Morris-Salom*. This company had produced electric vehicles since 1898; however those models had wheels of greater diameter as they were equipped with pneumatic tires, while Romanov’s vehicle had wheels with light rubber rims. Both the electric vehicles had two electric motors, but the distinction of Romanov’s electric vehicle consisted in the presence of 6-row ball bearings in the wheels.

Romanov’s second cab was built in 1900. This model had entirely closed and glazed cabin for passengers. The chain drive was replaced by a gear; however the basic sizes remained the same. This model was equipped with an accumulator designed by Romanov. The general weight of the electric vehicle was 45 poods (750 kg), and the weight of the accumulator came to 22 poods (362 kg). It should be noted that weight of American and French electric vehicles exceeded these figures. The speed of both Romanov’s models of the electric vehicles came to 15 km/h.

Romanov’s first electric bus was built in the same 1900. The electric bus weighted 100 poods (1600 kg) could make speed up to 10 km/h. For reasons beyond Romanov’s control, traffic of the electric vehicles in Saint Petersburg was not organized.

A vehicular company named *“Frezer and Co.”* participated directly in production of Romanov’s electric vehicles, i.e. a running gear of these vehicles was created by this company. In January 1900 *The Cyclist* magazine reported that this company had built an electric vehicle which had already been tested. A picture of this first electric vehicle by *"Frezer and Co."* can be found in advertising publications of those years. Various firms proposed the innovation for sale and described its technical characteristics.

Frezer electric vehicle was four-seated, had two engines whose total power came to 7 hp. The advertisement booklets reported as following: "The accepted system of accumulator is remarkable for its solidity and life-time. Capacity of the elements is about 15 Amperes/ hour per a kilogram of electrodes. The size of the battery is defined according to calculation of 120 W/h per one ton and per one-kilometer of the distance; its weight is equal to 30-40% of the total weight of the vehicle including a payload". Weight of Frezer electric vehicle came to 70 poods (1120 kg). It made the speed of 15-18 km/h and required recharging every 35-50 versts of the path. The second variant of Frezer electric vehicle differed from the first one for less weight of the accumulator which was located above the rear axle.

In addition to the four-seated vehicles, *Frezer* Company produced two-seated electric vehicles equipped with engines of 3.5-hp power. The two-seated electric vehicle was remarkable for its more perfect steering tube. There is known one specimen of this model purchased by somebody from Riga (Latvia). Moreover, on the territory of *"Frezer and Co."* there was a station for recharging accumulators of the electric vehicles.

In the period of the Soviet Union pilot batches of electric vehicles began to be produced only after the II World War. In general there were small lorries applied for transportation inside great buildings, for example, in a main post office or an airport.

Now there is a great probability that Moscow will be the first Russian city where the electric vehicles can find mass application. Russian capital suffers from gas pollution which is especially heavy in the center of the city. At the same time the budget of the city allows acquire own ecologically appropriate transport. Now financing of production of the electric vehicles is realized through the Fund of Ecologization of Moscow Transport. The means are assigned due to income taxes coming to the budget of the city.

To tell the truth, citizens of big cities know electric vehicles very well, i.e. usual trolleybuses and trams are electric vehicles despite they are not autonomous. An autonomous public electric transport has one advantage which is especially valuable in the conditions of the cities overcrowded by cars. This advantage is their mobility. Trolleybuses are inseparable with their wires that causes decrease of their maneuverability. For example, they cannot pass several cars which have been parked wrongly. In this case a maneuverable and autonomous electric vehicle will run to the center of the road and pass the obstacle with ease.

A Moscow company named *Eltran* which deals with exploitation of electric transport has developed a model of EV which runs the distance of 60 kilometers without recharging. Total recharging of this electric vehicle takes about 5 hours, however a half of required energy they can obtain for 1 hour. Hence, if the accumulators are recharged before their full discharge then this vehicle can operate constantly. However, a developed infrastructure of charging stations is necessary for this aim.

From the economical point of view, EV does not yield to trolleybuses and trams which house more passengers but run twice more slowly than the autonomous and compact EV. Therefore EV does not experience difficulties in jams in the conditions of the traffic of the city. It maneuvers easily in thick traffic current.

Unfortunately, now EV cannot replace automobiles equipped with internal combustion engines. Imperfection of its accumulator batteries does not allow it to become a public vehicle. The battery imperfection causes a small run on one recharging, long cycle of recharging, and high price of the electric vehicle.

To tell the truth, EV has important advantages. Maintenance charges of EV are lower than the charges of the standard automobile requiring expenditures for support of cooling systems, powering systems and exhausting systems. The lifetime of the electric engine comes to 10 thousands hours. Quantity of operations for maintenance of the engine is minimal. For example, it is necessary to change brushes in the dc motor from time to time. As for a modern three-phase electric motor and synchronous ac motor they are practically maintenance-free.

EV is easy to drive. To start the car you should only insert the key, turn it and press the accelerator pedal. You do not need to make any manipulations with adherence or gearshift.

Use of EV is justified in so called zones of higher environmental requirements that are cities, parks, vacation resorts. Electric buses, developed by *Eltran* run in the public green space of All-Russia Exhibition Center. There are about ten compact commercial EV operating in Moscow.

Taking care of environmental sanitation the management of AZLK (big automobile plant) has developed EV on the basis of two production automobile models "Moskvich-2141" and "Moskvich-pikup-2335". "Moskvich-Elektro" (Fig. 1-2) at fully loaded mass of 2060 kg accelerates up to 60 km/h at 15 seconds. Maximum speed of the load-free vehicle is 110 km/hour. Cruising range at one battery charging is 100 km, and it comes to 80 km with 400 kg of load. At present Electrical Vehicle "Moskvich" is filled with imported component parts, which are cheaper but functional. In time it will be supplied with Russian equipment that will make it cheaper.



Fig. 1



Fig. 2



Fig. 3

The model of truck equipped with electric motor "ZIL-Electro", the authors of which being called "AVEKS" and "Optimum-electro", also enjoys the support of the Fund of Ecologization of Moscow Transport. Various privileges and free passage to any location in public green zones are promised to the future owners of "ZIL-Electro".

Forty-eight lead-acid traction batteries of roll type (Optima battery) are hanged in pairs along the ramps of the truck. They are united into 4 sections (Fig.3). Capacity of these batteries is enough for 70 km running. Probable charging station for these machines is the loading/unloading point. Charging time varies from 30 to 60 minutes. Substantial disadvantage of the model is that batteries take away a great percentage of carrying capacity. Among the advantages of the model there are small internal resistance, fast recovery (to 400 A), discharging to zero level without serious consequences.

A traction induction unit "ATAD-Optimum 50/120" serves as the engine for "ZIL-Electro". Its weight is only 100 kg and it doesn't require any diesel generator or transmission that compensates a little the loss of carrying capacity.

The engine is very simple. It is a non-contact rotor of a "squirrel cage" type rotating on the bearings. No brushes are used. Thus expensive maintenance is postponed for uncertain date. On the other hand there is asynchronism. It means that some equipment is needed for converting into three-phase current and further frequency and amplitude adjustment. However it is expensive and complicated.

In spite of all existing disadvantages, Electric Truck is considered to have a bright future ahead of it. There several reasons for that:

1 The vehicle is manufactured from cheap production component parts.
2 The system of optimum vector control of the drive is introduced. (The torque and shaft speed of rotation is regulated precisely, energy of the batteries is used rather efficiently.)
3 Microprocessor system with feedback coupling and great number of sensors (current sensor, heat sensor, velocity sensor, voltage sensor) minimizes losses, prevents the motor and batteries from overheating, protects mains from short circuit in case of an accident.
4 The vehicle is reasonably priced (for such an exotic object) – about $26 000 USD subject to serial production.

Volzhsky automobile plant has already been engaged in research of EV for a quarter of a century. Over 10 original models have been designed and produced for these years. They have been appreciated abroad as well as in Russia. These are electric vehicles "Poni", "Oka", "Elf", "Gnom", "Niva", "Rapan" "Lada-golf", etc.

The models manufactured on the basis of VAZ-1111 "Oka" became the most popular among them. These EV received many different rewards, and became world-renowned. For example, VAZ-111E "Oka", manufactured in 1993, kept all merits of a production midget car. Use of electric motor makes it a non-toxic and noiseless vehicle. Efficient fast-acting short circuit protection eliminates current rush, providing absolute car operating safety.

In EV of VAZ manufacture two direct-current motors are commonly used as a power-generating set. The first is a 25kW capacity motor with torque of 110 Nm.

Another one has 40 kW capacity and torque of 190 Nm. Motors of the first type are usually mounted on light vehicles, such as "Golf", "Oka-Electro", "Elf", while high-power motors are usually used for VAZ-2108, VAZ-2109, "Niva".

The first models of electric vehicles used to be equipped with nickel-zinc batteries. But as life time of these batteries is not long, it was decided to start using nickel-cadmium batteries, manufactured at Saint-Petersburg plants "Rigel" and "Istochnik". Nickel-cadmium batteries are power-consuming, they withstand temperature of –40°C. The only drawback of these batteries is their cost, and as a consequence a high cost of the vehicle itself. Because of that the final choice has been made in favor of lead-acid storage batteries, which were mounted at "Gamma Golf" in particular, thus reducing its price by several times. The batteries are located under the driver and passenger seats. They allow discharge of 80-85% and provide cruising range without recharge of up to 100 km within city area and several times more on a highway. Power current is transmitted from the electric motor to the front wheels through single-reduction gear unit, which substitutes the transmission.

For the present time electric vehicles are not developed to take the place of automobiles with internal-combustion engine in all industries and spheres of application, but only as a specific vehicle for highly specialized utilization. They are utilized when use of internal-combustion engine is objectionable or impossible.

It is considered that so-called hybrid models of EV would be able to replace automobiles with internal-combustion engines. These are vehicles with two motors, an electric motor and an internal-combustion engine usually running on diesel oil. In this case the combustion engine works constantly, but under the operation modes of little air pollution. Besides, fuel consumption is also much reduced.

In this direction real commercial success is possible. For example, "Toyota-Pirus" has already been chosen as a personal vehicle by tens of thousands of customers, this being a good result for such an original construction.

Nowadays three circuits of hybrid propulsion system are generally known. The simplest one is a series circuit, in which combustion engine operates together with a generator, and battery or generator powers electric motor providing propulsion. Actually this is the same circuit of electric transmission that is used at quarry trucks. Its main disadvantage is great losses of energy at transmitting the torque to the wheels. In parallel circuit the output shafts of the motor-generator and combustion engine are rigidly bound, and it doesn't allow working in steady-state mode (i.e. with permanent rotations and load).

In the third circuit, which is also the most commonly used there are an electric motor, combustion engine and a generator. The output shafts of all these units are bound by planetary differential. This allows almost lossless distribution of power between the units, and provides sustained performance of the combustion engine. The disadvantage of this circuit is the extreme complexity of coordination of units operating.

A hybrid EV was produced in Russia by automobile plant "Izhmash" though it has not been put in mass production yet. At the developing of the propulsion system instead of unique components there were used units of Russian mass automobile production that is one of the fundamental design solutions. "Orbit" Izh-21261 was used as a base for the device. It was equipped with gasoline engine (of 30 hp power and 650 cm^3 capacity), drive dc motor ПТ-125-12 (of 120V voltage and 49 H/m torque) and eight accumulators 6CE-55. Twin-engined propulsion system works according to the parallel circuit of engine joint. Electromotor serves as starter and at the acceleration it operates simultaneously with internal-combustion engine. On reaching some definite speed the electromotor changes its operation mode to the mode of generator and charges the accumulators. When the loads at gasoline engine increase then the electromotor begins to operate together with it. Operation of the hybrid propulsion system is controlled by starting regulation electronic equipment. Control unit, speed transducer of crankshaft of the internal combustion engine, detector of the accelerator pedal etc. are responsible for coordinated work of the engines.

During the tests fuel consumption of the hybrid vehicle "Orbit" was less by 20% than that of the usual model. For Russian prototype it is a good qualitative characteristic, however foreign designers reach better results, for example, "Crysler ESX3", which was presented in 1998 at Geneva auto show, consumes 3.3 liter of diesel oil per 100 km of path.

Representatives of specialized Moscow companies producing EV assert unanimously that these are hybrid electric vehicles which should change public transport with internal combustion engine. To encourage the automakers it is useful to create the proper laws drawing on foreign experience. For example, in California, USA, automakers whishing to present their production in the state market should put out 2% of automobiles with null blast. Legal system also supports an automobile user who is provided for free parking and free or cheap recharge. The user is granted with maximum of discounts to encourage him buying EV which is still twice as expensive. However it is said that in one of the villages situated near Moscow where the so called new Russians live, everybody drive electric vehicles leaving their cars with gasoline engine outside the gates. It would be quite good if EV turns to the real vehicle from the extravagancy of nouveau riches and beloved creation of ecologists.

The Richard Clem Motor and the Conical Pump

An Investigation of the Clem Motor

Robert Koontz, USA
rdkoontz@attbi.com

In December of 1992 Jerry Decker posted an article on the KeelyNet BBS, about a self-running motor that developed excess useable power. The information, gathered from newspaper and individual sources, gave an anecdotal account of the motor invented in 1972 by Richard Clem of Flower Mound, Texas. New information has since been added and can be found on http://www.keelynet.com/energy/clem1.htm.

Richard Clem worked with heavy machinery for the city of Dallas. He used asphalt-spraying equipment, which pumped liquid asphalt. He noticed the asphalt pump would continue to run for up to 30 minutes after the power was turned off. It was this discovery that led to the development of the motor. Modifications he made eventually resulted in a substantial 350 horsepower output from a 200-pound motor. Clem is said to have often driven a car, powered by this motor, up and down Central Expressway in Dallas. He claimed it didn't use any fuel, and only needed a change of oil every 150,000 miles.

The motor had only one moving part, a cone shaped rotor mounted vertically on a hollow shaft. Spiral channels cut into the cone wound around its length and feed into peripheral nozzles at its large end. When fluid flowed through the spiral channels it was ejected out the nozzles and caused the cone to spin. At a certain velocity, the rotating cone became independent of the starter pump and began to operate by itself. At an operating speed of 1800 to 2300 RPM the fluid heated up to 300 F, requiring a heat exchanger. Vegetable oil was used because at 300 F water boils and conventional engine oil breaks down. A 12-volt battery was the only other power source. Clem never applied for a patent because his motor design was derived from the asphalt pump that was already patented. Fifteen companies turned him down before a large coal company offered to back him and signed contracts to sell the motor. Soon after the deal was signed, Richard Clem died of a heart attack

The above account contains only what I considered to be relevant for analysis of the Clem motor. Visit http://www.keelynet.com/ for the original material.

The gear pumps, typically used for asphalt spraying, do not match the description of the pump used by the city of Dallas back in 1972. There should be public records showing what equipment manufacture the asphalt sprayer was purchased from. Since the asphalt pump was patented, I searched for a pump patent that met the following criteria:

1) Patent issued on or before 1972.
2) Delivered pressure equivalent to a positive displacement gear pump.
3) Cone shaped rotor with spiral channels.
4) Self-propelling action.
5) Capable of pumping a viscous fluid like asphalt.
6) Large heat transfer to pumped fluids.

The following illustration (Fig.1) is from US Patent 3,697,190 (Truncated Conical Drag Pump). The patent was issued October 10, 1972 (criteria 1) and appears to match the description of the asphalt pump that Clem converted into his motor.



Fig.1

Housing 11, Conical interior wall 12, Conical rotor 13, Inlet chamber 14, Inlet pipe 15, Outlet chamber 16, Outlet pipe 17, Support feet 19, Detachable end cap 20, Rotor shaft 21, End cap wall 22, Boss 23, Packing 24, Adjustable gland nut 25, Bracket arms 27, Bearing boss 29, Bearing 30, Snap ring 31, Inner race 32, Sleeve 33, Shoulder 34, Retainer nut 35, Reduced diameter outer end 36, Coupling 37, Packing 39, Retainer 40, Gland nut 41, Bearing boss 43, Integrally formed bracket 44, Shaft reduced diameter 45, Bearing sleeve 46, Bearing 47, Snap ring 48, Inner flanged 49, Inner race 50, Nut 51,Shaft reduced diameter 53, Lock nut 55, Flat faces 56, Snap ring 57, Washer 59, Nut 60, Helical channel 61, Channel base 63, Channel sidewalls 64.

This is a high-pressure, low volume drag pump that can be used in place of conventional positive displacement pumps (criteria 2). It has a conical rotor that has a close fit clearance with the stationary housing wall. Delivered pressure is limited by back flow across the radial clearance and is inversely proportional to the square of the clearance. As a result, even a small increase in radial clearance would rapidly reduce pressure. The rotor is cone shaped so that the clearance can be controlled by axial adjustment of the rotor relative to the housing wall.

The conical rotor has two helical channels (criteria 3), in the form of square threads, spaced 180 apart for balance. The channel depth decreases as the rotor diameter increases. Fluid enters the channels at the small end of the rotor. The fluid is induced to rotate with the channel by boundary layer drag. The boundary layer is the thin layer of fluid adhering to the channel surface. Molecular cohesion tends to drag the adjacent fluid with the boundary layer. The fluid is also in contact with the housing wall. The boundary layer drag against this stationary wall slows the rotation of the fluid in the channels. Because the fluid rotates slower than the rotor, it is forced through the channels towards the large end of the rotor. In addition the fluid is forced towards the large end by centrifugal force.



Fig.2

The above drawing illustrates the proportional decrease in channel depth as the rotor diameter increases. Why was this done? Note that as the diameter doubles so does the circumference. This means the fluid has to travel twice as far in the same time to maintain a constant slip velocity. By reducing the channel depth in half (cross-section area = depth x width) the fluid velocity is doubled thereby keeping the slip constant.

The spiral channels could be thought of as very long convergent nozzles. The increase in fluid velocity is in the opposite direction of the rotor spin. We should expect a reaction force from the acceleration of the fluid. This thrust would be directed tangent to the circumference and would increase the spin torque on the rotor. Even without the peripheral nozzles, that Clem later added, the pump rotor experiences a thrust force in a direction that would self-propel it (criteria 4).

Because fluid drag is the primary pumping force, it is well suited for viscous fluids like asphalt (criteria 5). The long channels also represent a large sliding surface area with frictional losses that would transfer heat to the pumped fluid (criteria 6).

All six of the patent search criteria have now been met. Of course this doesn't prove that it is the asphalt pump Richard Clem worked with.

A peculiar condition indicated by the patent is that as the velocity increases in the channels the pressure also increases. Bernoulli's Law requires the pressure to drop proportionally as the velocity increases. Assuming an ideal fluid without losses, when the channel depth is reduced in half, the cross section area is also half and this doubles the fluid velocity and the fluid pressure should drop in half. So what is going on here? There is a centrifugal component that would add to the fluid pressure.

My guess is it's too small to overcome the predicted pressure drop. Here is what I think may be going on. As the diameter and velocity increases the drag force propelling the fluid through the channel is proportionally greater. Energy is being added all along the length of the channel. Whatever the reason, if this high-velocity, high-pressure fluid is feed into tangent peripheral nozzles at the rotor large end, the energy will be converted to shaft horsepower.

The Clem motor is producing 350 shaft-horsepower and a large heat energy component. Where is this huge amount of energy coming from? Recent quantum mechanics zero-point field (ZPF) theories may point to the answer. From an article available at "BEYOND $E=mc^2$" Bernhard Haisch, Alfonso Rueda & H.E. Puthoff [1]:

"Our work suggests inertia is a property arising out of the vast, all-pervasive electromagnetic field we mentioned earlier, which is called the zero-point field (ZPF). The name comes from the fact that the field is held to exist in a vacuum-what is commonly thought of as "empty" space-even at the temperature of absolute zero, at which all thermal radiation is absent."

ZPF researchers theorize that mass, inertia and gravity are not intrinsic properties of matter but the interaction of matter with the zero-point field. By all pervasive it is meant that the ZPF exists not only in empty space but it is passing through your body right now and everywhere else. When you throw a stone you are interacting with this field since the ZPF resists change in motion. In essence the ZPF is the modern day aether.

The amount of energy making up the ZPF is thought to be enormous. Is the fluid acceleration in the Clem motor interacting with the ZPF in such a way as to rectify it and draw energy from it? Is it a hydraulic aether-diode? The fluid, in the Conical Drag Pump, flows through long convergent channels. Disregarding the boundary layer, is this accelerated flow laminar? Would such a long orderly flow entrain the aether energy?

From the perspective of the rotating channels the fluid appears as the discharge from a long nozzle. To exaggerate, if the fluid was held fast to the housing wall, the rotating channel would travel through the stationary fluid. This would be equivalent to achieving 100% efficiency. In reality the fluid is slipping against the stationary housing wall so that the rotating channel (nozzle) is moving faster than the fluid discharge velocity. Assuming the reaction thrust as the only propelling force, this would give efficiency greater than 100%. So, as the slip increases the reaction thrust decreases, but the efficiency increases.

Assuming the Conical Drag Pump is the pump Clem used, can it answer the following?

1) Why was a hollow shaft used?
2) Why was the cone mounted vertically?
3) Why was a starter pump needed?
4) How were the peripheral nozzles added?
5) How was the motor RPM regulated?
6) How did a large coal company get involved?
7) Was this kind of pump ever used in asphalt sprayers?



Fig.3

Clem motor shown in start mode
The arrows show oil flow

The above drawing shows a hypothetical Clem motor based on the Conical Drag Pump. The motor is mounted vertically so that the check valve on the hollow shaft is submerged down in the oil tank. The hollow shaft extends from the oil tank through the rotor into the inlet chamber. The start pump draws oil from the tank and forces it up the external feed line connected to the inlet chamber at the small end of the rotor. This fills the hollow shaft and forces the check valve closed. The oil flows into the spiral channels and out the peripheral nozzles. The reaction thrust of the nozzles spins the rotor. The oil flows through the return line, through the valve, filter, and heat exchanger and back into the tank. The start pump is most likely a standard hydraulic gear pump. It continues to pump until the rotor spins up to its operating speed. The combinations of a start pump and check valve would be a simple way to both prime the motor and spin up the rotor.



Fig.4

Clem motor shown in operation mode
The arrows show oil flow

Once the start pump is shut off the check valve is free to open. Oil is drawn up into the hollow shaft to the inlet chamber at the small end of the rotor. The spiral channels pump the oil down towards the large end of the rotor. A plate is attached to the large end of the rotor and fits with a close clearance with the housing wall. Nozzles attached to the outer edge receive high-pressure oil from the spiral channels. The jet reaction thrust from the nozzles delivers shaft horsepower to the power takeoff at the shaft top. Adjusting the valve to create hydraulic backpressure regulates the motor RPM. Closing the valve stops the motor.

When I first read about the Clem Motor I found it odd that a deal had been made with a coal company. Was there a connection with the pump? After finding the Conical Drag Pump patent, I wanted to contact the inventor Walter D. Haentjens of Barrett, Haentjens & Co., Hazleton, Pennsylvania. Otto Haentjens founded Barrett Haentjens & Co., in 1916. The business began in the coalmines of Pennsylvania with Otto Haentjens original patent on the balanced opposed impeller multi-stage volute pump. The company still supplies pumps to the coal industry. They have expanded to other markets and their pumps are installed in many industries worldwide. It is now known as Hazleton Pumps Inc., after its acquisition by The Weir Group.

I contacted Peter Haentjens, the VP/General Manager of Hazleton Pumps, by e-mail to find out if this pump had ever been put into production. He replied that they had not done anything with the patent.

An unusual pump design would have a tough time competing in the market with an industry standard like gear pumps. The Dallas asphalt sprayer may have been a one of a kind field test of the pump design. Or the pump manufacturer offered it for testing to an asphalt equipment company in the hopes of generating interest in it.

References

Bernhard Haisch, Alfonso Rueda & H.E. Puthoff, "BEYOND $E=mc^2$" //The Sciences, Vol. 34, No. 6, November / December 1994, pp. 26-31 copyright 1994, New York Academy of Sciences.



Spontaneous Flow Heat Pump

PACES : The Alternative Energy

Jean-Luc Brochet, France

http://www.new-energy-paces.com
Email: brochet.jean-luc@wanadoo.fr

"Paces" is a new high performance electronic process. It is not a traditional heat pump fitted with some electronic gadgets to improve its output, but a truly revolutionary process totally unused up to now. There are no moving parts, not even a moving fluid in it. "Paces" is an electronic process because for its development the pump's fundamental element uses micro-electronic techniques.

...an average of 9000MW could be produced, that is to say the equivalent of several nuclear power stations.

The principle consists in attracting the gas neutral molecules onto a so-called "electrostatic" plate, to accelerate them and heat the plate. An intense electric field is applied in a capacitor with micro-pores covering the plate. The neutral molecules are polarized and accelerated when they penetrate these micro-pores where the intense electric field exists. Each molecule accelerates and absorbs electrical energy when it enters into a pore. But in turn it decelerates and gives off an equal amount of energy upon its exit from the pore.

The molecules, by going back and forth between the plates, continually give off and take energy, thus resulting in a total consumption equal to zero.

The gas fluid does not undergo any change of thermodynamic state, contrary to all other heat pump processes. A thermodynamic cycle remains at the level of each gas molecule, but not at the level of the entire set of molecules.

There is more to this new process, it is not just heat pump process added to an already long list: **these new characteristics also enable some new applications.** Besides the traditional heat pump applications, due to its excellent coefficient of performance this process makes it possible **to produce electricity by cooling the environment.**

For instance, if the Rhine was equipped with heat exchangers into which diverted water could flow, thus cooling its temperature by just one degree, an average of 9000MW could be produced, that is to say the equivalent of several nuclear power stations. Please note that this process would also enable **both electricity and fresh water to be produced from seawater,** an interesting application for areas of the world where water is a scarce resource.

Thus we have at our disposal an ecological process for producing electricity, it would become conceivable to produce hydrogen in great quantities; vehicles would be hydrogen powered. Ozone, CO2 or any other type of pollution would become a thing of the past.

It will most probably be the energy source of future generations, ecological and excellent, inexhaustible, powerful yet completely harmless, stable and steady (contrary to the sun and wind); an invention capable of re-launching the world economy, in particular giving impetus to the currently depressed new technology sector.

However, you have probably noticed that this invention requires advanced technology, and the few French laboratories capable to develop this process have proven inaccessibility to do it for independent researchers such as the author of the article. Besides, the invention's claimed qualities, the revolutionary aspect was very often interpreted by examiners as 'utopian', even before they read the document! Having tired of battling against concept fixed for the past two centuries, the author of the article **has now decided to place this project within the hands of the international scientific and technological community,** in order to give the best chance of success to the invention.

It will most probably be the energy source of future generations!

Initial development requires the construction of a prototype; three possibilities are described on the website (http://www.new-energy-paces.com). As there is no longer legal protection abroad, anyone is free to experiment and to market, as he or she wishes, in all other countries outside of France.

Please help me to spread the word about this project, for example through scientific forums on the Internet. This will allow you to receive feedback and gather other opinions. Your participation, even the most modest, will be of use. To those of you who help this project to see the light of day, all of humanity will be indebted.

Registration of Gravitational Waves

Vladimir N. Petrov, Russia

173001, apt. 76, 10 Bolshaya Saint-Peterburgskaya st., Veliky Novgorod
E-mail: petvn@km.ru

Registration of gravitational waves is one of fundamental problems of physics. At the beginning of the last century A. Einstein's works predicted existence of these waves. Nevertheless, despite numerous attempts are made in different countries of the world these waves have not been fixed up today. Josef Veber, an American physicist working in 60th of the XX century, is sure to be called as the first experimenter who disclosed gravitational waves. Nowadays lots of many-million projects on registration of gravitation waves are developed and realized (LIGO (USA), GEO-600 (Germany-England), VIRGO (Italia), and TAMA (Japan)). However no positive results were achieved.

Failures in registration of gravitational waves can be explained by the fact that researchers have erroneous notion of the essence of these waves. This erroneous notion is laid in an experimental project that causes negative results.

Many researchers believe that influence of gravitational waves on the bodies should be resulted in deformation of these bodies (i.e. in change of mutual place of particles of a material body). All the attempts to disclose the gravitational waves are based on this notion. Now two types of ground gravitational antennas are supposed as priority.

The first type supposes the registration of mechanical oscillations of a massive test body that is initiated by influence of gravitational waves on it.

The second can register changes of a distance between space-apart free masses when gravitational waves act upon them. Great attention is paid to the second type of antennas in the developed projects. Failure attempts of registration of gravitational waves can be explained by their low intensiveness and insufficient accuracy of existing measuring equipments. Therefore, now there are made various attempts to register gravitational waves produced by such great cosmic phenomena as confluence of black holes. More accurate instruments and measuring equipments, for example, a laser interferometer, are developed. Nevertheless, positive results are hardly to be obtained.

Here is one of the fallacious explanations of action of gravitational waves on a body: *"Passing of gravitational waves changes an interval between objects transferring them one from another like two boats sometimes are approached sometimes moved from each other by sea waves".*

Following this example to explain influence of the gravitational waves on bodies placing on the Earth, it can be said that all bodies are in one boat and raising or sinking of the boat on sea waves does not cause change of the distance between the bodies. However, this example seems to be very simplified for explanation of influence of the gravitational waves on bodies. In fact, the case is much more difficult.

According to A. Einstein's theory, bodies moving with variable acceleration will radiate gravitational waves. **Gravitational waves represent the essence of changes of gravitational field occurring at light speed.** Since the gravitational field is a deformed space-time then the gravitational waves cause change of deformation of the space-time. Change of deformation of the space-time is accompanied with change of deformation of geodesic lines (i.e. lines by which all the bodies move).

A body moving by a geodesic line whose deformation is changed changes its acceleration. Change of acceleration of the body will change gravity applied to the body in this area of space. Hence, influence of gravitational waves on the body occurs through gravity which influences on it.

It is known that a fundamental difference between gravity and other forces appearing at a direct contact with a body consists in the fact that gravity provides all the elements of the body (all its points) with equal acceleration (deformation can not occur), and other forces influence on certain parts of the surface of a body and so cause its deformation.

Hence it is senseless to try to measure deformation of a body or change of a distance between test bodies occurring under influence of gravitational waves. It is necessary to note that, in particular, when a body is placed on an unmovable support relatively to the Earth, value and the direction of gravity coincides with weight of the body. Therefore, in this case gravitational waves can be registered at measuring of changes of the body weight.

An experiment on registration of the gravitational field of the Earth by measuring change of weight of a test body was made. Before the beginning of the experiment there was set a problem to register gravitational waves produced by the Mercury and the Venus at approaching to the Earth. The gravitational field in which the Earth moves changes due to superposition of gravitational waves of other planets on it. These changes were necessary to be registered.

The experiment was as follows: a test body (a 100 grams weight) was weighted on an electronic balance in equal time intervals of 14 days. The experiment was lasting for 12 months. In the experiment it appeared that change of a distance between the Earth and the mentioned planets causes change of weight of the test body. The change of weight of the body occurred in proportion to the distance between the planets. The test body was weighted in the same conditions and in the same place. The performance of the experiment is so easy that every person can made it.

It is known that weight of a body changes (decreases) at moving along the Earth surface from its pole to the equator. Change of weight of a body locating in the same place has not been fixed until now.

The fixed change of weight of the test body proves change of gravity applied to it and, consequently, change of the gravitational field in which the test body moves as well as the Earth does. **These changes of the gravitational field were caused by motion (superposition) of the gravitational waves produced by the mentioned planets at their approaching towards the Earth at the distance of the existent gravitational field.**

Hence, the Earth and all the bodies locating on it move in the constantly changing gravitational field, therefore, constantly change their weight. Nevertheless, as it is known, change of the gravitational field is the influence of gravitational waves on it. Hence, measuring changing of weight of bodies we can speak about registration of gravitational waves.

In search of the 4th dimension



From http://home.ural.ru/~meop/index.html

High-Energy Hyper-Low-Frequency Electric Field

Yury V. Ivanko, Ukraine
E-mail: ux01w@hotmail.com

The article represents a practical and theoretical research on possibility of existence of a high-energy hyper-low-frequency electric field which is interpreted by modern measuring instruments and subjective perception as a static field. Besides there are observed a problem of the field registration, a hypothesis of relic origin of the registered field and a hypothesis of wave nature of the Universe.

A passenger on board a ship sailing in the ocean will never notice action of waves of high and low tide. At the same time, weathering waves of several numbers produce a dangerous storm. However, an ocean liner is designed for such a storm therefore the passenger would just experience some discomfort. It is another case if tide wave hides reefs… I wish our ship, i.e. the Earth, the Solar System, the Galaxy, and the Universe, not to be lead to such a place by any ignorant "navigator"!

One of the most mysterious persons in the history of electricity physics was an outstanding inventor Nicola Tesla (1856-1943). When the majority of scientists developed researches of microworld particles he followed the opposite scientific path. He was interested in the electrical potential of the whole Earth. He researched ways to influence on it, control its state and methods of its regulation. Therefore many of his patents, experiments as well as a purpose of constructions and devices built according to his ideas arouse perplexity and misunderstanding of modern scientists.

a test body was made. Before the beginning of the experiment there was set a problem to register gravitational waves produced by the Mercury and the Venus at approaching to the Earth. The gravitational field in which the Earth moves changes due to superposition of gravitational waves of other planets on it. These changes were necessary to be registered.

The experiment was as follows: a test body (a 100 grams weight) was weighted on an electronic balance in equal time intervals of 14 days. The experiment was lasting for 12 months. In the experiment it appeared that change of a distance between the Earth and the mentioned planets causes change of weight of the test body. The change of weight of the body occurred in proportion to the distance between the planets. The test body was weighted in the same conditions and in the same place. The performance of the experiment is so easy that every person can made it.

It is known that weight of a body changes (decreases) at moving along the Earth surface from its pole to the equator. Change of weight of a body locating in the same place has not been fixed until now.

The fixed change of weight of the test body proves change of gravity applied to it and, consequently, change of the gravitational field in which the test body moves as well as the Earth does. **These changes of the gravitational field were caused by motion (superposition) of the gravitational waves produced by the mentioned planets at their approaching towards the Earth at the distance of the existent gravitational field.**

Hence, the Earth and all the bodies locating on it move in the constantly changing gravitational field, therefore, constantly change their weight. Nevertheless, as it is known, change of the gravitational field is the influence of gravitational waves on it. Hence, measuring changing of weight of bodies we can speak about registration of gravitational waves.

In search of the 4th dimension



From http://home.ural.ru/~meop/index.html

High-Energy Hyper-Low-Frequency Electric Field

Yury V. Ivanko, Ukraine
E-mail: ux01w@hotmail.com

The article represents a practical and theoretical research on possibility of existence of a high-energy hyper-low-frequency electric field which is interpreted by modern measuring instruments and subjective perception as a static field. Besides there are observed a problem of the field registration, a hypothesis of relic origin of the registered field and a hypothesis of wave nature of the Universe.

A passenger on board a ship sailing in the ocean will never notice action of waves of high and low tide. At the same time, weathering waves of several numbers produce a dangerous storm. However, an ocean liner is designed for such a storm therefore the passenger would just experience some discomfort. It is another case if tide wave hides reefs… I wish our ship, i.e. the Earth, the Solar System, the Galaxy, and the Universe, not to be lead to such a place by any ignorant "navigator"!

One of the most mysterious persons in the history of electricity physics was an outstanding inventor Nicola Tesla (1856-1943). When the majority of scientists developed researches of microworld particles he followed the opposite scientific path. He was interested in the electrical potential of the whole Earth. He researched ways to influence on it, control its state and methods of its regulation. Therefore many of his patents, experiments as well as a purpose of constructions and devices built according to his ideas arouse perplexity and misunderstanding of modern scientists.

Having formulated my own hypotheses I often think why such a Great Genius as Nicola Tesla took his invention away with him.

Danger of this invention lies in simplicity of production of devices for generating (detecting) energy.

Practical Prerequisites

Prerequisites of this and other hypotheses were some undeclared effects occurring in practical wireless communication as well as investigation of devices for distant transmission of electric power.

Distant energy transmission was demonstrated by Nicola Tesla in 1892 in London and in 1893 in Philadelphia. However, even now the way he did it remains unknown.

In 1977-1985 I had to work a lot with radio transmitting equipment of different power of middle-wave (MW) and short-wave (SW) diapasons. According to fundamentals of physics, intensive electromagnetic field is produced around antenna curtain connected to a radio-frequency transmitter. There are brightly glowing gas-discharge electrovacuum devices at the distance up to several meters in this field. Attention was paid to the fact that more than ten daylight lamps of 80 W were successfully "glowed" at 40 W power of a transmitter. In this case a distant correspondent did not note significant decrease of a level of a received signal at the indicator of the receiver. It had to return to this fact in many years. The data of this experiment are represented in a particular document.

There is one more interesting effect which is disclosed when transmitting equipment (TX) and antennas (ANT) are adjusted. An incandescent lamp, which is connected to a certain place of a break of the antenna curtain or of a power feeder (L), glows brightly. The antenna circuit is not closed as galvanic element. (See Fig. 1).



Fig. 1

Hence, the power line of the incandescent lamp is as if it is single-wire. It also had to return to investigation of this effect in many years. The data of this experiment are represented in a particular document. As in the case of the incandescent lamps, the correspondent did not note significant decrease of the level of the received signal at the indicator of the distant receiver.

S. V. Avramenko designed a plug of semiconductor diodes. Connecting this plug to a generator of alternating voltage of 10-10000 V by means of a single-wire line in the load of the plug he discovered current, which was continuous by the direction but pulsating by the value. Electric current measured in the single-wire line is very little, hence, the impression of superconductivity is produced, i.e. it is possible almost to avoid energy losses in the wires.

My experiments also represent a visual demonstration of the effect. For example, several links of light-emitting diodes connected inverse-parallel glow in the single-wire line. Garlands of light-emitting diodes and lamps having a single-wire power line can be produced. It is interesting that in this case power consumed by the generator do not increase practically (See Fig. 2, 3, 4). It was noted that if a standing wave is created around the generator "then an unlimited number of consumers would be able to apply a change of a value of this field to produce power in a load in their place" *(Editor: This phrase is in inverted commas since it is a part of the well-known article "Free Energy" by Alexander V. Frolov (Read in this issue, p. 15)).*



Fig. 2



Fig. 3



Fig. 4

Russian scientists investigated this phenomenon and proposed an explanation of producing active power in the load by means of reactive capacitive current. This was made applying resonant properties of the single-wire line made of a metallic conductor. Further, possibilities of application of nonmetallic conducting mediums for transmitting electric power were investigated. However, the researchers pay attention for the fact that this explanation is insufficient.

A task group named "Analysis" from Voronezh city (Russia) made a qualitatively new explanation of results of S. V. Avramenko's experiment. The works of this group from Voronezh are devoted to the comparison of properties and characteristics of so-called inertial and inertialess currents occurring in circuits at low frequencies. Their general and particular features have been disclosed. In the works there are demonstrated conditions at which conductivity caused by inertialess discharges predominates in conductors and conditions at which currents caused by conduction electrons predominate. There are demonstrated a description of S. V. Avramenko's experiments and the conclusions made by the researchers. The authors cite data of their test experiments which prove a part of conclusions made by S. V. Avramenko and his colleagues.

However this explanation does not have a right to exist as it does not have variants for practical application.

Results of my theoretical and experimental researches allow provide a **fundamentally new (!)** explanation of energy "transmission" having occurred in the experiments performed by S. V. Avramenko, investigations by D. S. Strebkov, V.A. Kuligin and other investigators. *(Editor: See publications of these works in previous issues of our magazine*). Moreover, they allow explain origin of many physical phenomena and processes including the origin of non-inertial charges and currents and their visualization.

First Hypothesis

Recently a number of scientists all over the world have declared a thought that surplus power is produced in the systems having overunit output due to inability to identify correctly all the existent energy sources. And a so-called phenomenology is observed due to the inability to deal with different types of energy (or fields).

In physics a negation of an overunit device follows a well known state which is considered to be true in other fields of knowledge, i.e. energy conservation law. It should be noted that it is formulated for isolated (closed) systems. I have devoted some time to the investigation of this state and to practical experiments and come to the following conclusion: there are **no isolated (closed)** systems in the nearest cosmos which can be observed by us!

Particular physical, chemical and other processes may actually be observed in closed circuits for making calculations with sufficient approximation.

Show me an isolated system, and I will prove that it is open.

Hence, according to fundamental physical laws, energy does not appear from nothing and not disappear to nowhere. However, the source of oscillations, i.e. our generator, does not provide a load with energy; nevertheless, power is produced in the load. Energy conservation law must be fulfilled! The classical formulation of the energy conservation law is as following: total energy of an isolated system is not changed in the course of time. According to this, the only fact remains valid, i.e. the single-wire system is not isolated from outer influence, hence, energy is consumed from some other source which is outer in relation to the system?! In this case our generator is one of sources of information about an amplitude, frequency, and phase.

Calculations and experiments have allowed made a following supposition. Avramenko's diode plug is a particular case of a device known in radio engineering for a long time, i.e. AM detector (a peak-detector, a limiter, a frequency mixer). I have examined the other known circuits of AM detectors and frequency mixers. The investigations are continued and by this time the supposition has been confirmed.

Let us accept an artificial generator (Tesla's transformer or any other one) as a main generator (or a main oscillator) and a hyper-low-frequency (HLF) oscillation of a huge amplitude as an envelope curve. Let us name it as RW ("relic wave") without placing emphasis on the sense of the name.

Let us suppose that the field can be of:
- local origin (artificial radio transmitters);
- atmospheric origin;
- geomagnetic Earth origin;
- the Moon – the Earth;
- the Sun – the Earth (the Sun as a nuclear reactor producing electromagnetic radiation, the Solar System);
- galactic origin;
- Universal origin – the Relic Wave; in contrast to the relic radiation occurring in the diapason of SHF (i.e. in

contrast to the convenient notion) it is the diapason of HLF.
- Etc.

The researches have demonstrated that the field of local and atmospheric origin may be excluded. The other variants require to be developed. Nevertheless, the variant of the Universal scale seemed to be the most probable. There is some reason for this supposition: the modern notion of the birth and the state of the Universe, i.e. the Big Bang and the expanding Universe. The known variants of scenarios of the Big Bang are based on a nuclear explosion of enormous power. The nuclear explosion is accompanied by an electromagnetic impulse (disturbance). It can be supposed that the Big Bang caused forming of a field having enormous amplitude values and long (great) period of oscillations. Probably, we deal with this field.

The second hypothesis about inconstancy, i.e. about wave nature of the Universe

A Russian proverb says: “Everything passes, everything changes”. Constant electric voltage does not exist (!). That, what is considered as the constant voltage, really is a constant component (occurring at a certain time interval). This component is formed by combining of variable sinusoidal oscillations and/or is a quite low frequency fundamental. Hence, it is a non-sinusoidal “changing” having amplitude linear part at the time interval of the observer.

For example, in reality a usual storage battery of “direct current” can not support invariable voltage, i.e. when a discharge appears the voltage decreases (changes in time, oscillates with a non-sinusoidal oscillation and a quite low frequency fundamental), when a charge appears the voltage increases.

It is necessary to observe the constant voltage occurring after a rectifier and even a stabilizer as a constant component existing in the time interval from switching on to switching off. This will correspond to that is proposed by Fourier!

Show me a device producing constant voltage, and I will prove that the voltage is not constant.

Conclusions

If the supposition is totally confirmed then the statement that an electric field plays a fundamental role in the Universe will be valid.

We live in an electric field of a huge potential but we do not notice it. Since **our reference point is the amplitude value of RW field in our point of space** then the potential is equal to zero for our perception and for measuring instruments. Besides, **RW has an amplitude linear part at the time interval of the observer**. Hence, we consider RW field existing as unrevealed or as weak interactions in natural processes. Nevertheless, this influences directly on the whole surrounding material world.

Artificial production of heterogeneities in the RW field can cause its significant visualization.

According to the concept of the physical field, which was called by Einstein as the most important discovery in physics since Newton’s time, every body generates a force field in the ambient space (for example, the electric field occurring if the body has an electric charge). This force field becomes apparent when a test body located in a certain point is influenced by a force.

Discovery of the fields of this scale allows define this concept more accurately. I would like to restate the information mentioned above in the following way: every non-homogeneity of physical vacuum (aether), which is registered by our perception or by measuring instruments as a physical object or a physical field, interferes with RW (according to other interpretations, it absorbs or rereflects RW, or becomes excited) producing new wave fields. This perceived physical field has frequency which is higher than RW frequencies. It is perceived as static in the time interval of observation. Hence, the field generates a charge and not the reverse. Any linear or non-linear transmission (motion) of a material or field object changes non-homogeneity which is generated by this object.

A question about measuring of parameters of the Universe remains open. Can an oscillation of the period of $T=14$ billions years and of the amplitude of $A \sim T$ be seen, perceived, registered or measured?

The used literature and references are not cited in the article due to its great volume. The reader can familiarize with them at the web-site of http://www.efir.com.ua. The complete text of the article and other materials can be received from the author.

EAGLE-RESEARCH
Energy Solutions
since 1984

A Research Organization that Develops & Distributes Practical Energy-Saving Methods & Devices

4 Energy Way, P.O. Box 118
Porthill, Idaho 83853
FAX: 250/492-7480

Technical questions to:
wiseman@eagle-research.com

To the Question of Work Made by Electrostatic Field

Alexander V. Frolov, Russia

General Director, Faraday Lab Ltd
Tel./Fax.: 7-812-380-3844
Email: office@faraday.ru

We know some simple examples of work making due to the forces, which appear in electrostatic field. Since the field itself does not require energy consumption from the source (not taking into account the charge leakage), then free energy can be received with these forces. The first phenomenon that we are going to consider is a phenomenon of **electrostriction**. Mechanical forces appearing in dielectric under the influence of electrical field tend to deform it. Sometimes these forces are small, but they can be huge in special dielectrics. The character of deformation also depends on non-linearity of electrical field. Suffice it to remember that heating of a body takes place during deformation, and we can make a conclusion on possible using of the given effect in practice. Periodical deformation can be created due to the rotor or any other methods to change the field.

The second effect is not so popular. It was found by Hertz in 1881 that there is a rotation of dielectrical cylinder (or ball) in permanent electric field if it is created in some liquid or in gas (see Fig.1).



Fig.1

Here **$\varepsilon1$** is a dielectrical permittivity of the liquid, **$\varepsilon2$** is a dielectrical permittivity of the rotor, **$\gamma1$** is a conductivity of the liquid and **$\gamma2$** is a conductivity of the rotor. This effect was discovered by Hertz, then it was described by G. Quincke, Germany. Also Japan scientist I. Sumoto studied the effect in 1955. Modern research work was made by K.M. Polivanov, Moscow. There is the so called equation by Polivanov describing special conditions, which are necessary to begin rotation (**$\varepsilon1/\varepsilon2=\gamma2/\gamma1$** is the Polivanov's condition).

Forces of electrostatic field produce this rotation and it is a real free energy system that can trap energy from inner structure of potential field. Let's try to describe the mechanism of this effect and then we'll be able to increase the power of the system up to the level of industrial application. So, why does it work? To my mind, there are some differences in conditions for polarization of the rotor and molecules of liquid or gas those are surrounding the rotor since there is a difference in permittivity and conductivity.



Fig.2

Due to this reason the molecules are polarized both by the field of electrodes and by the field of rotor. The rotor is polarized in the electrical field of electrodes, and molecules of liquid on its surface are polarized by the electric charge of the rotor, but not according to direction of the field. So, the rotor is surrounded by "screen" of molecules on its surface. The electric charge of this screen partially compensates the field of electrodes.

When some angle is created by the first initial turn, there is some part of the rotor surface, where molecules of liquid on the surface of the rotor are attracted to electrodes and it is the reason for future rotation. After some angle of the turn the polarization in this point of the rotor surface is changed but new molecules are incoming in the so called "sector of attraction" and the rotation is always accelerated. This well-known effect of 1881 is a very good example of possibility to produce useful work in load by means of electrostatic field only.

One more interesting effect is known as Faraday effect. In 1836 Faraday noted that raising of liquid upwards takes place in condenser with liquid dielectric (plates are installed vertically). During this process electrostatic field makes the work against gravity. A. Gyemant in 1926 established that value of this force is proportional to the square of voltage on condenser. Later in 1955 this phenomenon was studied in details by I. Sumoto, Japan. That's why in physical encyclopedias this effect is called "Faraday-Sumoto effect". In Tareev's book [1] it is pointed: "Under high voltage this phenomenon leads to flowing and turbulent boiling of liquid". I should remember for those, who see nothing unusual here, that it does not necessary to consume the power from initial source. Creating an initial field in electric capacitor, then we can use the received mechanical work. It is evident that the gradient of electrical field creates the conditions for movement of liquid dielectric. A task to create conditions for liquid circulation is more complex, but it has solution, if we take into account the presence of one more static field, i.e. gravitational field. Joint action of electrostatic and gravitational fields stipulates the circulation of liquid dielectric even in the simplest constructions. Besides, electrostatic filed can be partially screened.

The analyzed examples should draw attention of experimenters to these obvious ways of how to create useful work by means of electrostatic field.

References

1. Tareev B.M. Physics of dielectrical materials, Moscow, Energoisdat, 1982, p.199 – 200.

Editor: Below we publish the comments of our reader.

Letter On
Hertz-Quincke-Sumoto Effect

from Doug Marett
Email: doug.marett@sympatico.ca

…As far as I can tell, the original reference by Hertz is "On the Distribution of Electricity over the Surface of Moving Conductors", Wiedemann's Annalen, 13, pp.266-275,1881. Hertz's discussion of this phenomenon is cursory at best, having very little experimental work included. The real phenomenon appears to have been discovered by W. Weiler in 1893 (Zeitschrift fur den Physikalischen und Chemischen Unterricht, Vol.6, pp194-195). Weiler observed that a glass cylinder placed in a poorly conducting liquid between two spherical electrodes began to rotate when the electrodes were connected to an electrostatic generator. In 1896, George Quincke reported the same phenomenon and published a comprehensive report on it. This was in Annalen der Physik, Ser.3, Vol. 59, pp.417-486. Subsequent investigators have tended to attribute the discovery to Quincke, when in fact Weiler was the first to pioneer the work.

I do know that P.E. Secker et al. performed work on this field, references of which are available in the English language. These are:

P.E. Secker, et al., (1968) Journal of Applied Physics, Vol. 39, pp.2957-2961, and
P.E. Secker, et al., (1970) Journal of Physics D: Applied Physics Vol.3, pp 216-220.

I hope that this information might be of use to you.

BOOKS REVIEW

The Foundations of Physchemistry of Micro World

Ph. M. Kanarev

The Second Edition

The book was published in Russian and English; you can also read it at http://book.Kanarev.innoplaza.net

The new axiomatic of natural sciences is given in the book; on its basis, quantum physics and quantum chemistry have been returned to the classical way of development. The first steps are made on this way, which have led to discovery of the structure of the photon, the electron, and the principle of the formation of the atomic nuclei, the atoms and the molecules.

The Planck's Law of radiation of perfect blackbody is given on the basis of classical concepts, and the connection of quantum phenomena with the laws of classical physics is proved.

The application of the new theoretical results to the solution of practical energy tasks on the basis of plasma electrolysis of water is shown. Due to this electrolysis, additional heat energy and the energy containing gases (hydrogen and oxygen) are generated. Cold Nuclear Transmutation of the atomic nuclei of alkaline metals and the atomic nuclei of the cathode material takes place during plasma electrolysis of water.

The book is intended for physicists, chemists and other specialists who are seeking the new directions for understanding the foundations of the micro world and the new energy sources.

Comments to Electro-Reactive LIFTER News

Alexander V. Frolov, Russia

General Director, Faraday Laboratories Ltd
E-mail: office@faraday.ru
http://www.faraday.ru

March 21, 2003 we got news from France about electro-reactive propulsion system.

Blaze Labs reached 100g PAYLOAD level.

You will find all the details of the Saviour's experiment at: http://blazelabs.com/exp14.htm.

This electro-reactive ionization-flying model requires 46 kVolt, 4 mA, i.e. about 200 watts to fly with 100 g useful load.

It is interesting to note that Jean-Louis Naudin's previous opinion of 1997 – 1999 about priority of the Frolov's asymmetrical capacitor now is changed. Sometimes people wish to re-write the history. It is possible and it is easy. Naudin's web page about http://jnaudin.free.fr/lifters/story.htm (see Fig. 1) is not started from the real beginning of the story. He forgot our discussion of 1997 and also photos and MPEG video I have send to him when he has started his way in electrograviticis.

If you remember the name of Naudin's first asymmetrical capacitor "Frolov's Hat" (see Fig.2) then you know why there is this name of this technology. But really it is not important to try for some serious reply from Jean since he has no personal post address, phone, or his photo on the web site...

Also it can be useful to visit this page http://www.faraday.ru/t-cap.html to know about something **more important than electric ionization flying models (Lifters),** since it is just a reactive ionization way, which is similar to rockets.

Ideas now developing by us are not aimed to increase the power level (from 1 gram to 100 gram propulsive force). It is **a qualitatively new idea**; it is really electrograviticis instead of "electro-reactive Lifter".

So**, what is about real "history of the question" instead of the French version?** The question here is not about a priority, it is nonsense after T.T. Brown's patents. As an example the NASA patents on asymmetrical capacitors can be mentioned since the ideas were opened before the NASA patent and there is nothing new in it. The problem is that people who develop reactive ionization Lifters develop only primitive reactive technology. **It is not essence of T.T. Brown research but it is the distortion of his ideas.**

So, the team in France is working to develop and support ideas of secondary and wrong method. Why? Perhaps they either do not see the real way or have payment for the wrong way **to mask a real work.**



Fig. 1



Fig. 2

Questions & Answeres

Josh Werrmann (Email: jsh111@yahoo.com): I wanted to ask you a few questions about an article titled “Highly Efficiency Electrolysis” by A.V. Frolov. In this article it is stated that Dmitry A. Latchinov patented a method for electrolysis, where one of the electrodes is insulated completely from the water. It is also stated that another scientist, Igor Goryachev, used a method of pulsed electric fields. I don’t know if you know, but inventor Stanley Meyer has a patent that covers both of these processes together, in a way. His patent is U.S. patent number: 4936961. Take a look at this. In the patent it states EXPLICITLY that there is a pulsed electric field, where a condition of NO CURRENT is preferred. This is very similar to the above to Russian scientists, except that the patent states a condition of resonance is necessary. I am wondering do the two scientists that are described require resonance in their devices? Or just plain pulsed electric fields, where one electrode is insulated from water.

Another patent I would like to refer you to is Archie Blue’s electrolyser, U.S. patent number: 4124463. This device is similar to A.V. Frolov’s idea, to get the oxygen and hydrogen bubbles off the electrodes, except he uses a blower to blow air in the cell, instead of rotating the cell like A.V. Frolov does. His invention also uses the conductivity current to work.

Alexander V. Frolov: As far as I know resonance is not created in this case. The main idea is the removal of gaseous film which appears on the surface of electrodes by rotation or some other methods.

NEWS REVIEW

Giant magnets lead the world to the new source of energy

http:// www.sciteclibrary.ru

The system of 150-tons magnets which have been developed by scientists of the USA, Japan and Russia opens a new era of safe and unlimited energy. In this system nuclear fusions serve as a source of energy. They accumulate heavy chemical elements not by means of nuclear reactions but by ultrahigh plasma pressure.

After supplementary research is held which aims to reduce manufacturing costs of the giant magnet weighing 925 tons, this magnet will be produced and demonstrated at the opening of the International Thermonuclear Experimental Reactor (ITER). This magnet in its turn will become a part of a bigger system, that is combined into a magnet weighing approximately 10 000 tons. The task of ITER is the demonstration of the process of nuclear fusion, as an energy source. During the process of nuclear fusion the light elements are combined by immense pressure, thus producing heavier elements. During this production process a lot of energy is emitted. The task of giant high-power magnets is to create magnetic fields, which must hold and control plasma, or to charge electrically the gas, in which the fusion is being held.

In Japan the system of 150-tons magnets serves as adjustment system of 925-tons magnets, which will be finally put into operation and heat up the ITER plasma. Two additional giant magnet systems will confine the plasma and will control its form. The model for one of them is presently being examined in Germany; the model of the other is in project.

Cylindrical 150-tons magnets have three main parts: external module, built by the Japanese team, internal module, built by the American team and a thin rod in the core which is equipped with process control equipment. Three different rods were separately checked, two of them were built in Japan, another in Russia.

Harnessing the Wheelwork of Nature

(340 pgs. Adventures Unlimited Publishers, 2002)

Thomas Valone
Email: iri@erols.com



It is a new book by **Thomas Valone**, who edited this anthology in time for the **Wardenclyffe Tower Centennial (1903-2003)**. This book presents for the first time, the feasibility argument for Tesla's most ambitious dream, the wireless transmission of power. Pictured on the book's cover near his feet, the 187-foot Wardenclyffe Tower was Tesla's means to deliver natural 8 Hz electricity anywhere in the world, by longitudinal waves.

Unknown to most electrical engineers, Nikola Tesla's dream answers the energy crisis worldwide, saves electrical conversion losses, and provides a real alternative to transmission lines. In Dr. Corum's contributed papers, he explains Tesla's magnifying transmitter, which Tesla compared to a telescope. Corum points out that "the tuned circuit of his magnifying transmitter was the whole earth-ionosphere cavity resonator." This fact helps explain why Tesla stated, "When there is no receiver there is no energy consumption anywhere. When the receiver is put on, it draws power. That is the exact opposite of the Hertz-wave system...radiating all the time whether the energy is received or not." Thus, with Tesla's futuristic transmission of power, source dissipation will only be experienced when a load is engaged in a tuned receiver somewhere on the earth. This fact alone represents **a major leap forward** in electrical transmission efficiency, even one hundred years later.

Why wasn't the prototype of Wardenclyffe finished in 1903? Tesla offered this visionary conclusion: "The world was not prepared for it. It was too far ahead of time. But the same laws will prevail in the end and make it a triumphal success... Let the future tell the truth and evaluate each one according to their work and accomplishments. The present is theirs; the future, for which I really worked, is mine."

Up until now, there has been a general malaise regarding the lack of scientific comprehension of Tesla's greatest dream. For example, the Serb National Federation notes, "With the exception of the first biography of Tesla by John J. O'Neill, science editor of the *New York Herald Tribune*, and published in 1944, unfortunately no biographer since has had the necessary scientific/engineering academic credentials to discuss Tesla's work in the various fields." Contributors to ***Harnessing the Wheelwork of Nature*** are primarily physicists and engineers who are experts in Tesla technology. Their wealth of knowledge demonstrates their mastery of this extraordinarily progressive and technical subject. Finally, the best academic credentials have been brought to bear on the world's greatest electrical futurist.

This is a very readable and profusely illustrated reference volume on wireless transmission of power, besides being an excellent biographical gold mine of Tesla history. Nick Cook, editor of *Jane's Defence Weekly* and author of *The Hunt for Zero Point* says, "Tesla is one of the great overlooked geniuses of science and electricity. His full story deserves to be told. Tom Valone sheds important new light on his life and work."

Integrity Research Institute will hold a Tesla Energy Conference & Expo on November 8-9, 2003 to celebrate the Wardenclyffe Tower Centennial (1903-2003) in conjunction with the Tesla Wardenclyffe Project, Inc. (www.teslascience.org).

See www.IntegrityResearchInstitute.org for more details.



Experiment on the generation of gravitational field

by Dmitry Yu. Tsipenuk

Sergey S. Abramov



Model of Adams Motor-Generator

Новая Энергетика

Electrolytic photoaccumulator for the XXI century energy systems

Read the new article by Anton I. Egorov

Flynn Generator



Original version of photomaterials is presented at http://www.flynnresearch.net

Joe Flynn Laboratory, USA





Electric generator by Joe Flynn

More than 350% efficiency generator operating on permanent magnets

ISSN 1684-7288
9 771684 728801

Read the article by Tim Harwood in this issue

New Energy Technologies

Printed version ISSN 1684-7288
Online version ISSN 1684-9698

Published by Faraday Laboratories Ltd. **Issue #3 (12), 2003**
Research on advanced aerospace systems and new energy sources

Time Machine

Conference in Moscow: discussion of the patent application on the method and device to control temporal parameters of matter

Time Machine

Experiments by research group "KOSMOPOISK"
Summer, 2001

Device designed
by Faraday Lab Ltd, 2002

Alexander V. Frolov
Vadim A. Chernobrov
April 12, 2003, Conference hall
Hotel "Cosmos", Moscow

NEW ENERGY TECHNOLOGIES #12

1. Works on the Designing of Time Machines. Vadim A. Chernobrov (Russia)
2. Control of Temporal Parameters of Physical Processes. Alexander V. Frolov (Russia)
3. Etherodynamics as a New Field of Physics. Vladimir A. Atsukovsky (Russia)
4. Electromagnetic Gravitational Interaction Vadim Ya. Kosyev (Russia)
5. Medium For Existing of Matter in Nature. Anatoly V. Rykov (Russia)
6. Adams Motor. Sergey S. Abramov (Russia)
7. Field Transformation in the Model of Extended Space. Dmitry Yu. Tsipenyuk (Russia)
8. Joe Flynn’s Parallel Path Magnetic Technology. Tim Harwood (USA)
9. Flynn Laboratory Photos
10. Flux-machine and Its Analogies. Review
11. Russian Patents on Alternative Energetics.
12. Gravitational Spaceships. Gregory R. Uspensky (Russia)
13. On Velocity Of Drive-Free Motion. S.A. Gerasimov , V.V. Stashenko (Russia)
14. Electromagnetic Self-Action. S.A. Gerasimov, A.V. Volos (Russia)
15. Uranium Photoaccumulator. Anton I. Yegorov (Russia)
16. Global Energy Prize (reportage)
17. Teleportation. Alla V. Pashova (Russia)
18. “Mass Defect” in Home Conditions. Prokofy V. Sherbak (Russia)
19. Aether as Unified Field. Alexander M. Mishin (Russia)
20. Global Energy. Philip M. Kanarev (Russia)
21. Fusion Processes Of Molecules Of Oxygen, Hydrogen And Water. Philip M. Kanarev (Russia)
22. Plasma Energy Power Generation. Bruce A. Perreault (USA)
23. News
24. The Marcus Device Controversy. Tim Ventura (USA)
25. Systems of conversion of thermal energy to mechanical one. Review
26. I. Prigozin
27. Letters

Editorial: On April 12 of 2003 a scientific conference "The Time Machine" was organized by Faraday Laboratories Ltd in Moscow, Russia. It was devoted to the experiments on control of space-time physical properties. At the conference there were discussed problems of time and gravitation in the context of etherodynamics, experiments and applied aspects of these technologies. Below we publish a review of the main reports presented at the conference.

The First Results of the Works on the Designing of Devices to Control Parameters of Physical Processes (of Time)

Further Plans on Designing of the Time Machine

Vadim A. Chernobrov, Russia

"KOSMOPOISK", Nagatinskaya 19A, 111533,
Moscow, Russia
E-mail: chernobrov@kosmopoisk.org

To conduct the experiments on the influence upon physical Time (density of space energy) some special devices were used as a general method of such influence. These devices can create converging waves which can cause the appearance of quasi-monopole in the confined space. *Quasi-monopole* is a part of space which has some parameters of hypothetical unitary monopole or bunch of such particles (in particular, it allows registering one magnetic pole by means of measuring equipment from the outside at some distance from this pole).

The pilot experiments have shown that it is very difficult (if not impossible) to create long-living quasi-monopole by means of permanent magnets or electromagnets operating on direct currents (in this case quasi-monopole represents a space with one outer and one inner magnetic pole). It can be explained by the fact that lines of force of the "inner pole" invariably find a weak spot in the heterogeneous surface of magnets and break out. As a result, at the device along with one "outer" magnetic pole there is a local output of magnetic lines of the "inner" pole.

During the designing of new devices there was a task to create a quasi-monopole situation in the confined space. This situation should be created not uniformly but transiently by pulsation method. Frequency of work of electromagnetic oscillators first of all was selected depending on linear dimensions of the devices. Selection of the frequency was made in such a way that one period of pulsation does not exceed the period of time which is necessary for electromagnetic waves to reach the center and opposite waves of the device.

At the designing of laboratory devices, which generate converging longitudinal waves, several different principles to obtain required parameters were considered in the multi-layer quasi-monopole, which works in high-frequency mode. Several types of the devices were realized at different degrees of development and with different success. It was shown that the simplest devices were that ones which used electromagnetic (solenoid) oscillators connected in series and in parallel. In different experiments between 3 and 5 such surfaces were used. These surfaces were called electromagnetic work surfaces (EWS). All layers of EWS of different diameters were mounted in series in each other (like matreshka). The outer layer was either mounted at force shell or simultaneously represented such a shell by itself.

The size of the maximal EWS was about 0.9 m, the diameter of the minimal (inner) EWS was equal to 115 mm that was enough to place laboratory animals inside the control detection devices. Laboratory animals were used to determine the consequences of the influence of converging spherical electromagnetic waves. Payload, (i.e. that which was directly used for transfer in Time-Space), included the afore-mentioned detection devices and (occasionaly) laboratory animals. The term "payload" was coined by analogy with the term which is used in cosmonautics. Volume of payload section was placed in the center of symmetry of the Time Machine (TM). In all the earliest Machines (except the 7th model) this volume still has not exceeded the volume of a football. The device with an outer diameter of 2.1 m and inner payload section of 1 m has the maximum size. It allows making human-aided experiments.

At different stages of the experiments the calculations were made by all available known modern methods to fix time. All types of electronic, quartz, mechanical and several specially made doubled quartz generators were used (there were compared frequency readings of measuring and etalon heat-insulated generators which were placed at a distance). Certain experiments used lightguiding diodes and some other methods. Before and after the experiment (more rarely during the experiment) readings of measurement clocks were periodically compared with those of an etalon clock and with signals of exact time which were transmitting by radio. Other physical factors causes side effects upon some types of measuring devices, for example, upon quartz-crystal clocks. However, doubling of measurement methods allowed essentially decreasing inaccuracy of measurements.

At some operating modes (which were not always predicted) the change of Time speed was attained (Prof. Nikolay A. Kozyrev called it density of Time t/t_0). This change came to about a fraction of a second per an etalon hour. Let us take usual "etalon" earth time as $t_0=+1$ then it becomes clear that it is speed range of $+0.99<t/t_0<+1.01$ which is researched in the experiments. Thus being placed inside the device, the inanimate objects and animals were transferred in the Future (with "above-zero" speed) more slowly or faster than those around them. It occurred at all operational modes of the device (deceleration or acceleration).

Difference of Time (gradient of Time speed or curvature of Space-Time field) was observed not only inside the TM, though there is no doubt that a maximal value of changed Time was registered inside the smallest "matreshka". As was expected, during the experiments Time change was also registered outside the device. However such change which had an opposite sign was smaller than the change inside the device approximately by an order of magnitude. It entirely corresponds to geometric laws, i.e. in proportion to the cube of the distance).

In other words, TM influences not only its inner part and pay load but also the environment. It bears a strong resemblance to jet propulsion but in Time and not in Space. It is a flight which is realized by rejection of Time instead of mass.

Thus it was determined that the processes of deceleration and acceleration of Time distinctly differ in their nature and consequences. In such a way the deceleration was considerably smoother and more stable. During acceleration there were observed sudden changes in readings and this operational mode was characterized by general instability and dependence on any (or many) external factors. Particularly, acceleration instability also consisted in the following: at fixed power the value speed of Time depended on the time of day and situation of the Moon. Possibly it also depended on some other factors including the presence of an operator or other people near the device. Even insignificant external influence, for example, mechanical shaking, caused the change of speed value which sometimes was rather significant.

Inside the laboratory devices there was also registered that **Time can change with some sluggishness**. After the changed Time speed influenced some physical object (for example, soil) then residual effects were observed at it for some period of time. These effects can be eliminated only by the influence of another speed of Time.

Preliminary general conclusions

The Present is the transfer or transformation of the polyvariant easily changeable Future into the univariant unchangeable Past. Thus flights in the Past (at "negative" density-speed t/t_0) and in the Future will happen in different ways. They can be compared with the motion of an ant along the tree: from any point of the tree (i.e. from the Present) there is only one way downwards open to the ant (i.e. in the Past) and many different ways upwards (i.e. in the Future). However among all the ways to the Future undoubtedly there are most probable, low-probable and almost improbable variants for development of the Future. The less probable this variant of the Future the more unstable and energy-intensive the motion to the Future will be. According to the "law of the crown of tree", return to the Present is possible only if when being in the Past the traveler does not interfere in the course of events and does not change the course of the past History. Otherwise the chronotraveler will return to the parallel Present from the Past by another branch of History. Penetration to the Future from the Present is hampered by the choice of the branch for transference. However return from any variant of the Future into the Present is possible at any scenario if there are no fusions of different variants of History…

In other words, we have a circumstantial evidence of the assumption that Time has more than one dimension. Thus there is an affirmation of the theoretical inferences of R. Bartini who believed that Time has 3 dimensions. Hence we can consider our terrestrial globe as 6-dimensional where the dimensions are: length; width; height; age or date of Time; variant of History or blur of Time; density or speed of Time. Thus the notion of "Arrows of Time" is completely absent in the fourth dimension (date of Time) but it is a special case of the notion of the sixth dimension i.e. speed of Time. At the same time the notion of speed of Time also relates to the physical notions of gravitation and energy. Thus the notion of "Einstein-Rosen bridge", which was introduced in 1916, or notion of "worm course", which was introduced by John Willer in the end of the fifties, are connected with transference in the 5th and 6th dimensions.

◆

Method and Device to Control Temporal Parameters of Physical Processes by Means of Changing of Energy Density of Space

Alexander V. Frolov, Russia

General Director, Faraday Lab Ltd
Tel./fax: 7-812-380-3844
Email: office@faraday.ru

This invention belongs to the methods and devices to provide control on rate of physical processes (that includes the process of the existence of matter in space-time) by means of increasing or decreasing of energy density of space (i.e. energy density of physical vacuum or density of the aether).

Let us consider the history of the invention:

Earlier there were proposed some methods and devices to influence the rate of physical and chemical reactions, biological processes or period of oscillation of the system. In the works by N.A. Kozyrev [1] there is a description of the experiments on the influence of some process (for example, process of evaporation or crystallization of matter) upon the period of another process, which serves as a detector and can be compared with reference oscillation process. In one case, the rate of oscillations of the detector decreases in the surrounding area near the process of matter evaporation. In another case, the rate of detector oscillations increases in the surrounding area near the process of matter crystallization. If we use a term of "entropy" then it is possible to say that the processes which are accompanied with entropy increasing (for example, conversion of matter from solid state into liquid one) influence on the matter (surrounding processes) in such a way that entropy of systems decreases. In another case, for example, near the process of crystallization, entropy of systems increases in the surrounding area near this process. Kozyrev used the term "wave of density of time" and he made a conclusion that in addition to "directivity" of time (time course) there are active properties of time, for example, "density of time".

To develop this approach for applied purposes it is necessary to use in-depth analysis of the physical sense the "law of the crown of tree", return to the Present is possible only if when being in the Past the traveler does not interfere in the course of events and does not change the course of the past History. Otherwise the chronotraveler will return to the parallel Present from the Past by another branch of History. Penetration to the Future from the Present is hampered by the choice of the branch for transference. However return from any variant of the Future into the Present is possible at any scenario if there are no fusions of different variants of History…

In other words, we have a circumstantial evidence of the assumption that Time has more than one dimension. Thus there is an affirmation of the theoretical inferences of R. Bartini who believed that Time has 3 dimensions. Hence we can consider our terrestrial globe as 6-dimensional where the dimensions are: length; width; height; age or date of Time; variant of History or blur of Time; density or speed of Time. Thus the notion of "Arrows of Time" is completely absent in the fourth dimension (date of Time) but it is a special case of the notion of the sixth dimension i.e. speed of Time. At the same time the notion of speed of Time also relates to the physical notions of gravitation and energy. Thus the notion of "Einstein-Rosen bridge", which was introduced in 1916, or notion of "worm course", which was introduced by John Willer in the end of the fifties, are connected with transference in the 5th and 6th dimensions.

◆

Method and Device to Control Temporal Parameters of Physical Processes by Means of Changing of Energy Density of Space

Alexander V. Frolov, Russia

General Director, Faraday Lab Ltd
Tel./fax: 7-812-380-3844
Email: office@faraday.ru

This invention belongs to the methods and devices to provide control on rate of physical processes (that includes the process of the existence of matter in space-time) by means of increasing or decreasing of energy density of space (i.e. energy density of physical vacuum or density of the aether).

Let us consider the history of the invention:

Earlier there were proposed some methods and devices to influence the rate of physical and chemical reactions, biological processes or period of oscillation of the system. In the works by N.A. Kozyrev [1] there is a description of the experiments on the influence of some process (for example, process of evaporation or crystallization of matter) upon the period of another process, which serves as a detector and can be compared with reference oscillation process. In one case, the rate of oscillations of the detector decreases in the surrounding area near the process of matter evaporation. In another case, the rate of detector oscillations increases in the surrounding area near the process of matter crystallization. If we use a term of "entropy" then it is possible to say that the processes which are accompanied with entropy increasing (for example, conversion of matter from solid state into liquid one) influence on the matter (surrounding processes) in such a way that entropy of systems decreases. In another case, for example, near the process of crystallization, entropy of systems increases in the surrounding area near this process. Kozyrev used the term "wave of density of time" and he made a conclusion that in addition to "directivity" of time (time course) there are active properties of time, for example, "density of time".

To develop this approach for applied purposes it is necessary to use in-depth analysis of the physical sense of the "time density" notion. Connection of notions about "time directivity" and "entropy of the system" was demonstrated in the work "Introduction into thermodynamic of irreversible processes", 1964 by Ilya Prigozhin [2]. In the work "Quantum fluctuations of vacuum in curved space and theory of gravitation" by A.D. Sakharov [3] the conception of vacuum structure was suggested. In the USA the work "Can the vacuum be engineered for space flight applications?" by H.E. Puthoff [4] is well-known. The author considered the applied aspects for study of vacuum structure and described the method and device to obtain propulsive force by means of changes in vacuum properties.

A substantive conception of time and methods for creation of waves of energy density were also considered by Prof. K.P. Butusov in the work "Time is a physical substance", 1991 [5]. In the book "What is The Time?" by Yu. G. Belostotsky [6] the connection between the notions of time and aether was demonstrated. This connection was considered from the point of view of astrophysics there.

We can also say that the modern conception of aether is successfully developed by V.A. Atsukovsky in his works [7].

In my articles, for example, "Physical principles of the Time Machine" [8], it was demonstrated that to develop experimental works on the topic it is useful to clarify the terminology and to consider **"waves of time density" as longitudinal waves of energy density in space.** In this case the notion of "time density" has a physical sense of energy density (aether density).

This approach can be realized practically by means of classical electro-technical and radio engineering methods and it is a development of aether-dynamical conception on the nature of electricity and magnetism by M. Faraday, "Experimental researches on electricity", volume 3, [9].

Let us consider a usual bipolar magnet from the point of view of aether-dynamics. Then it is possible to say that it is inflow and outflow of aether, i.e. it is a balanced energy system which does not change energy density in space. In this case it is evident that creation of magnetic monopole or modeling of quazi-monopole by means of electro-dynamical methods is a technical basis to create some local change of energy density in space.

Electric processes could also be used alongside with the magnetic phenomena. For example, in another book "Symmetrization of Maxwell-Lorenz equation" by Prof. Butusov [10] the creation of longitudinal wave was also considered. It was demonstrated that an electrically charged sphere can radiate longitudinal wave when the sphere radius is changing, i.e. when its surface is changing while the value of electric charge is constant.

One more well-known method is described in the book "Experimental gravitonics" by Polyakov [11]. There is a consideration of the generation of gravitational waves at the high-frequency magnetization and demagnetization of ferromagnetic material, i.e. at the powerful volume magnetostriction. Since at this phenomenon there are changes of matter density (i.e. changes of energy density in space, which is occupied by matter), then volume magnetostriction is a special case of changes of energy density.

Earlier Vadim A. Chernobrov had described a method and device to control temporal characteristics of physical and chemical processes by means of creation of the magnetic monopole (quasi-monopole). In this magnetic mono-pole there is a convergent wave, which is created by several sources situated in the spherical frame. According to this method in the multilayer spherical structure where every layer (the so called "electromagnetic work surface") is an assembly of electromagnets, by means of series connection of the layers the wave is created, which converges to the center of the device. The device has the same outside magnetic poles of the electromagnets (and the same inner poles) and thus a model of macroscopic magnetic monopole is created.

We assume that at in-phase operation of all sources of waves, interference of longitudinal waves provides some change of value of energy density of space in the focus of the system.

Experimental facts prove that detectors installed in the center of the device (for example, mechanical or electromagnetic oscillators) show change of period in their own oscillations. We have protected them by shielding them from heat radiation as well as from other kinds of electromagnetic influence. Thus it is possible to assert that the detectors decelerate or accelerate their oscillation period depending on the energy density, which is generated in the center of the device.

However for the experiments made by means of such a device, accurate adjustments of all wave sources are required to provide their in-phase operation. At the same time, operational stability of the system depends on the operational stability of each of the wave sources. Increase of the impulse frequency causes increase of the effect; however, it is limited by the parameters of electromagnets and generator of impulses. Besides, to increase the effect it is necessary to use more powerful energy sources since the current in the windings of electromagnets determines the value of the magnetic field of the created quasi-monopole.

Since the efficiency of such systems directly depends on the frequency and the value of changes of energy density in space, then in the next version of realization of this technology we suggest using of plasma shells instead of electromagnetic working surfaces. This will allow significant improvment in the specific parameters of the device.

Thus let us consider general engineering principles of operation and outline the ways to develop this method. Fig. 1 represents a three-layered electromagnetic emitter. This electromagnetic emitter is designed according to the invention in which the directed radiation of wave of energy density is created along the axis of the device.



Fig. 1
Three-layered electromagnet



Fig. 2
Three-layered electromagnet with ferrite core

The device is designed according to the idea by Vadim A. Chernobrov for creation of the directed wave of energy density by means of phase shift in propagation of impulse front in three current branches, namely i_1, i_2, i_3. These branches are displaced along the electromagnet axis at some distance ***d***.

The device works in the following way. When the pulsed generator is activated, front of current pulse i_0 appears at the output 4. Impulse front at branch 1 advances impulse front at branch 2 that is caused by spatial shift of current branches 1, 2, 3 relatively to each other along the electromagnet axis at the distance ***d***. Impulse front at branch 2 in its turn advances impulse front at branch 3 for a certain time ***T***. The second output of the electromagnet 5 is placed in such a way that impulse front at branch 1 will phase lag behind the impulse front at branch 2 (which in its turn will phase lag behind the impulse front at branch 3) for the same period of time ***T***. Therefore at branch 5 the united impulse front is generated again.

Time ***T*** can be calculated in the following way:

$$T=d/c \text{ (seconds)} \qquad (1)$$

where ***c*** is a constant of propagation of impulse front. This constant is known as velocity of light.

At each impulse the ***T*** (i.e. the value of relative lag of impulse front) is a constant value. Thus high-frequency consequent excitation of layers of the electromagnet appears at each impulse. The frequency of the excitation is calculated in the following way:

$$f=1/T \qquad (2)$$

where T is relative lag of impulse front in seconds.

There is an example of frequency calculation: for the shift distance d=7 mm we can calculate a lag $T = (7/2.997924)\text{x}10^{-11}=2.335\text{x}10^{-11}$ (seconds) and frequency f=1/T approximately comes to $4.28\text{x}10^{10}$ (Hertz).

Thus this design of three-layered electromagnetic emitter allows creating the waves of super-high-frequency band (for example of millimeter range) without the use of a semiconductor or other radio components.

It is very expedient to use the electromagnets designed with magnetostrictive material cores, that will significantly increase energy density of the longitudinal wave, which is generated by the multilayer electromagnet. In Fig. 2 there is an emitter with the core. In the case of high-frequency ferromagnetic magnetostrictive materials 6 the efficiency of emitter operation significantly increases.



Fig. 3
Spherical design

Fig. 3 represents the spherical distribution of emitters 7 at the upper 8 and lower 9 hemisphere of the frame which could be opened in order to place detectors and different objects inside. It can also allow to establish in what way the changes of density of space energy influence the properties of different materials, velocity of physical and biological processes as well as chemical reactions. The installation of detectors 10 inside the device is shown on Fig. 4.



Fig. 4
Detectors inside the system

Another version of design is represented in Fig. 5, where the suggested method is realized by means of a spherical electric capacitor with three coats 11, 12, 13. Each capacitor coat is connected to the outlet of three-phase pulsed generator 14.



Fig. 5
Three-layered spherical capacitor

In this case the wave of energy density is created without electromagnetic emitters and this principle is not related to the modelling of magnetic quasi-monopole. The device operates due to the control unit, which provides the high-frequency changes of electric potential at each coat in such a way that the mode of high-frequency converging or diverging wave of energy density is created. In fact it is a standard three-phase generator but it produces not the rotation of the rotor of some electromotor but **"compression" or "decompression" of aether.** Aether is "pumped" in the center of the device or "pumped out" of the center.

In this case there is no need to tune separate sources of waves to make the device work in in-phased mode. It ensures reliability of the device operation if to be compared to the quasi-monopole. Besides, much less energy is necessary for the processes of charging and discharging of multi-layer spherical electric capacitor than for creation of magnetic field by means of conductivity currents.

Since the efficiency of such systems directly depends on the frequency and value of changes of energy density in space, we suggest the use of plasma shells instead of electromagnetic work surfaces for the next version of the device. It will allow significantly improvment in the specific parameters of the device. For that it is enough to place the electrodes of the multi-layers capacitor in a low-pressure gas area and these electrodes should be made as gauze electrodes. At that the wave is created in plasma, which is excited layerwise by several gauze electrodes placed in a spherical space between the inner and outer spherical bodies of the device. Therefore this version of design of the device can be considered as **the manipulation of the plasma method**.

Fig. 6 is a plan of one more design version. It is made as an inner frame 15 and outer frame 16, the space between them is filled with some gas 17. Three electrodes 18, 19 and 20 are connected to the three-phase pulsed generator 21. **Consequent excitation of plasma layers by electrodes 18, 19 and 20 creates the wave of energy density.** Propagation of this wave can be directed both to center of the device and from the center of the device.



Fig. 6
Wave in plasma



Fig. 7
Schematic electric circuit

In Fig. 7 there is a schematic electric diagram of the design.

To conclude. The work on time control has just started. We have clearly determined the main physical principles of operation of such devices, which can change the aether density in some given volume of space and thus influence temporal parameters of any physical process. The small experimental results today allow us to make real positive conclusion on availability of this method and on the possibility of its practical application in applied aspects. The first aspect is antigravitation propulsion technology and we are developing the methods to detect mass (weight) changes in the time control experiments to prove this applied possibility. Another area is medical applications of the changes in the aether density.

Russian Federation patent claim #2003110067 was filled April 9, 2003. At present time we are interested in marketing for this technology as well as in search of additional investment and partners.

References

1. N.A. Kozyrev, Selected works, Leningrad State University, 1991
2. I. Prigozhin, Introduction in thermodynamics of irreversible processes. M., 1964
3. A.D. Sakharov, Quantum fluctuations of vacuum in curved space and theory of gravitation, Reports of USSR Academy of Sciences, vol. 12, 1968, p. 1040
4. "Can the vacuum be engineered for space flight applications & Overview of theory and experiments", Dr. H.E. Puthoff, Infinity Energy, July-November, 1997
5. K.P. Butusov, Time as physical substance. Collection of articles "Problems of space and time in modern natural science", Issue 14, L. 1990, pp. 301-311
6. Yu.G. Belostotsky "What is The Time?" Saint-Petersburg, 1991
7. V.A. Atsukovsky "General etherodynamics", M., 1990
8. A.V. Frolov, Physical Principles of The Time Machine, New Energy Technologies #3(6), pp. 8-10, Saint-Petersburg, 2002
9. M. Faraday, Experimental researches on electricity, vol. 3, M. 1959
10. K.P. Butusov, Symmetrization of Maxwell-Lorenz equation. Problems of Space and Time in modern natural sciences, vol. 15, L. 1991
11. S.M. Polyakov, O.M. Polyakov "Introduction in experimental gravitonics", pp. 58-59, M. 1991
12. V.A. Chernobrov "Mysteries of Time", M. 1999

Aetherodynamics as a New Field of Physics

Theory and Experiments

Vladimir A. Atsukovsky, Russia
Email: atsuk@dart.ru

A crisis exists these days both in Natural science on the whole, and, in its basis, i.e. physics. This situation is caused by fundamental errors in the methodology of its theory. The postulate method and predominance of mathematics above physical sense can be also considered as the reasons for this. Crisis situation has also taken place in the past and the way out was always to use a deeper level of matter organization than the accepted one.

A large amount of material on elementary particles of matter is collected in physics. It was discovered that all these particles can be transformed in each other. Besides that, there was discovered the ability of vacuum to create such particles at strong electromagnetic fields. In this connection it becomes clear that all these particles and vacuum have a common building material, i.e. a physical medium which fills all the world space. This medium was renamed **aether** and the element of the medium was renamed **amer**.

The worked out methodology of aetherodynamics allowed determining that aether is a usual viscous coercible gas for which all laws of usual dynamics of gases are valid. It has allowed to determine its characteristics for near-Earth space and then to describe the structures of primary stable elementary particles (i.e. proton, neutron, electron, photon, atomic nuclei, atoms and some molecules) as well as physical essence of general fundamental interactions (i.e. strong and weak nuclear interactions, electromagnetic and gravitational interactions) and some physical phenomena.

Also developed was the model of aether circulation in the Universe within the limits of perpetually existent matter, usual Euclidean space, and evenly flowing time. Formation and decay of matter, formation and decay of celestial bodies and galaxies as well as functional classification of galaxies are also included there.

To confirm some theses the author and his research team conducted several experiments mainly on electromagnetism that gave positive results. The research was conducted on testing of the presence of aether wind. These research works have confirmed the results obtained by D. Miller in 1925.

Report by Vladimir A. Atsukovsky

Electromagnetic Gravitational Interaction

Vadim Y. Kosyev, Russia

http://uft.h1.ru; http://uic.nnov.ru/~kovy2
Email: uft@inbox.ru

In the article some mechanisms of electromagnetic gravitational interaction will be considered in the view of the Unified Theory of Field, Space and Time. See the complete description of The Unified Theory of Field, Space and Time at http://uic.nnov.ru/~kovy2; http://uft.h1.ru or in the book [1] which has the same title.

First of all, let us consider the structure of Space-Time where the radiation propagates. In our World gravitation is the unique substance which exists everywhere and gets over any obstacles. There are no known methods of insulation of gravitational field in modern science. It is impossible to imagine space and gravitation separately. Gravitation exists everywhere where there is some space. The gravitational field created by all masses of our metagalaxy is the aether in which cosmic objects moves and electromagnetic oscillations are propagated. The space surrounds us since the whole matter carries gravitational charge of only one sign. From astronomical research of cosmic space it follows that radius of metagalaxy is equal to the critical (gravitational radius) and hence gravitational potential is equal to $c^2 \sim 10^{17}$ $[m^2/c^2]$ in each point of space.

In our space the sum potential of the electric field is equal to zero. All bodies and space-time as a whole are electrically neutral. This assertion follows from two unique properties of gravitational space-time:

1. Values of electric charges of different signs of elementary particles are exactly equal.
2. There is an equal number of elementary particles which carry electric charges of different signs.

If electric potential is equal to zero in the given point of space then energy of alternating magnetic field passes entirely to the electric field and radiation gains the parameters of electromagnetic oscillations. However electric potential of positive and negative signs can prove its properties at the simultaneous charging of different local spatial regions. In the electric field the character of radiation differs from that one which is observed in ideal gravitational space-time (without electric potential).

In the presence of electric potential some part of magnetic energy is spent to create gravitational alternating field. Radiant energy is absorbed. Electrically charged spatial regions are perceived by us as filled with a strong absorbing substance. At the same time if the potential of the electric field can be compared to the potential of the gravitational field then spreading of radiation becomes impossible.

Change of both electric and gravitational field results in the creation of a magnetic field in the region of space-time which has a dual electrogravitational nature. Change in the magnetic field results in the creation of both electric and gravitational fields. The amplitude of electromagnetic and magnetogravitational constituents of the unified electromagnetic gravitational oscillations depends on field potential of opposite nature. The electromagnetic constituent is determined by gravitational potential and the magnetogravitational one is determined by electric potential. Transference of gravitational masses of matter in electrogravitational field-aether causes the creation of the proper magnetic field. Coming from the direction of magnetic field some force influences upon the moving electrically neutral masses. This force is similar to Laurence force.

Electromagnetic gravitational converter designed according to the Searl Effect (Fig. 1) visually demonstrates the mechanisms of electromagnetic gravitational interaction. A detailed description of the experiment is presented in the article [2] by Vladimir Roshschin and Sergey Godin (see http://www.n-t.org/tp/ts/dms.htm).

The device consists of a cylindrical stator of about 1 meter in diameter which is surrounded by 24 cylindrical rollers. Stator and rollers are made of magnetic material and they are magnetically linked (there is no contact between them). Vector of the magnetic field of the stator and rollers is vertically oriented along the axis of the cylinder but it has opposite direction. Rollers are mounted on the movable separator which circles round the stator. Each roller rotates on its axis in the same direction. The weight of the device is 350 kg. During rest, the device is electrically neutral and has proper gravitational charge, inertial mass, magnetostatic field of the stator and rollers.

On rotating of the magnetic system the following effects were observed:

- Depending on the frequency (up to 35%) the weight of the device was decreased.
- At a frequency of 550 rpm there is a spontaneous acceleration of the system and turns of the rotor abruptly increase (in quadratic dependence). To stabilize the mode it had to take off the excess energy to active load (up to 7 kWtt) by means of electromagnetic transducers.
- Magnetic field was distributed in a room as concentric surfaces of 5-8 cm thickness and 50-60 cm period. Depending on speed of rotation of the magnetic system there was a fixed temperature decrease from 0 to 8° within the regions of space which were curved by magnetic field.
- The glowing (corona discharge) appeared around the working converter.

Appearance of all mentioned effects is caused by the simultaneous presence of electric, magnetic and gravitational fields in the area of the converter.



Fig. 1
Electromagnetic gravitational converter

Because of the Searl Effect a very complicated configuration of electric, magnetic and gravitational fields appears in the device. Rollers having their own field ***B*** rotate around the stator which has its field ***B***. Cycloidal motion of numerous magnets which are built in the rollers causes change in the magnetic flux. EMF ***E*** appears in the area of rotation of the rollers. EMF is directed along the perimeter around the device. The electric field creates stationary waves which are registered around the device as concentric electromagnetic gravitational walls. Magnetic rollers should be made non-conducting in such a way as to allow electric field penetrating inside. In the presence of the electric potential change of the magnetic flux causes appearance of gravitational field ***G***. This field is directed along the perimeter around the device. In the presence of electric potential the Lorenz force influences the gravitational masses of the rollers. These gravitational masses move in the external magnetic field of the stator. The Lorenz force is directed transversely to the velocity along the cycloid and in the direction of the field ***B***. The value of the Lorenz force depends on the electrical potential, magnetic intensity, mass of the rollers and their traverse speed. The electric potential in its turn depends on speed of rotation of rotor of the magnetic system. As a result the Lorenz force depends on speed according to square law. Rotating gravitational masses of the rollers generate magnetic field B_2. Field B_2 generates derived fields E_2 and G_2 etc.

Spontaneous acceleration of the system does not depend on the direction of rotation. Directions of fields and forces change at change of the direction of rotation that corresponds to acceleration in the opposite direction. When the direction of rotation is changed the weight of the device changes. When rotation is in one direction the field G_2 is directed upwards (decrease of weight), when rotation is in another direction, it is directed downwards (increase of weight). In the presence of electrical potential many other interesting but still unstudied phenomena are observed (for example, curve of space, change of speed of time-flow, changes of ambient temperature…). Magnetogravitational converter transforms gravitational energy of space-time into energy of electric field which in its turn is transformed into mechanical energy of the rotating magnetic system and electric energy of the load. Energy resources of the future are not coal and gas reserves or nuclear power. They are in the inexhaustible energy of gravitational aether of our space-time.

Reference

1. V.Ya. Kosyev. Unified Theory of Field, Space and Time. Nizniy Novgorod, "Arabesk", 2000.
2. New Energy Technologies #1, 2003, p.35.

Medium For Existing of Matter in Nature

Anatoly V. Rykov, Russia
Email: rykov@uipe-ras.scgis.ru

By medium for existing of matter in Nature we understand physical vacuum which is a category determining all spheres of matter "life" (from particles of microworld to gravitational interactions in the Universe). Matter can not exist without this medium. Thus a question emerges, viz: how physical science can be developed without taking this fundamental aspect into consideration?

According to the Einstein postulate, in a void light always propagates with limited speed, which does not depend on the motion mode of a radiating body. It is a statement of deep physical sense which lies in the fact that only some physical medium can possess such a property. Indeed, if velocity of light, which was radiated by a body, further does not depend on speed of this body then it is possible only in a certain medium. For example, in air sound propagates with a certain speed which does not depend on the speed of the source and is determined only by density and volume elasticity of air. Thus, according to the Einstein postulate, there is a physical medium instead of void and velocity of light depends on the parameters of this medium (as is well known, velocity of light is equal to the square root from the product of inverse values of electrical and magnetic conductivity of vacuum).

The author of this article made an attempt to research this physical medium [1]. The author used a well-known experimental fact that at interaction of a photon with a charged real particle this photon transforms to electron-positron pair. Besides, it was taken into consideration that photon is an electromagnetic phenomenon. The research allows the following conclusion: the medium named in physics as vacuum (before the XX century it was called aether) is created by electric dipoles from (+) and (-) elementary charges. These dipoles are surrounded by magnetic (mass) continuum. There were determined dipole intervals, elasticity of decompression and ultimate strength of this interval. What does this model of medium mean?

1. This model is a physical validating for the "birth" of electron-positron pair at energy which is necessary to break dipole and create the "clot" of mass of these two particles. A certain model for the "birth" of mass must exist. It is not clear as yet but can be represented as a vortex of magnetic continuum inside the charge shell of electron and positron.

2. Let us suggest that values of (+) and (-) charges differ at $7.848981\text{x}10^{41}$ Coulomb, then this difference is sufficient for the medium to be a source of gravitation and inertia. According to Newton's law of gravity, a weak electric charge of medium (all material bodies exist in this medium) causes all bodies to attract one another (under Coulomb's law). On the other hand, weak medium charge of a like sign creates repulsive forces which manifest themselves in the form of the expanding Universe. Thus it becomes clear the amazing uniformity of gravity and forces of negative pressure for the Universe. The mentioned difference of values of (+) and (-) charges of medium dipoles is not used as arbitrary parameter but it logically follows from its electrical structure [2].

3. Hypothesis of nature of gravitation is confirmed by calculations of the deflection angle of electric waves by the Sun. Calculated angle differs from the experimental value only in the fifth sign, which depends on the accuracy of several physical values used in calculation formula. There is practically an absolute coincidence with Einstein's theory. The difference is that it is a concept of space and time (i.e. geometry) which prevails in the general theory of relativity while in the nature of gravitation physical basing is used. Velocity of light is unstable and determined by medium state which depends on electric, magnetic and gravitational potentials.

4. The existence of "black holes" relates to medium structure and nature of gravitation. At the edge of "black holes" the ultimate acceleration from gravity is realized. It causes breakdown of connections in electric dipoles of medium, creation of matter and antimatter (the so called "evaporation" of black holes which was theoretically predicted by E. Hoking, England). However at the border of a black hole the velocity of light is equal to zero since its propagation

medium disappears. According to Einstein's theory it is such a deceleration of time that electromagnetic oscillations gain zero frequency.

5. Naturally the medium is a carrier of all types of electromagnetic radiation, beginning at stationary electric voltage and ending with super-high-frequency "photons", which can be determined not as electromagnetic but as magnetoelectric phenomenon. In the latter case magnetic continuum of medium has a crucial importance since it determines very small degrees of magnetoelectric disturbance. These degrees are thousands of times less than those of a hydrogen atom. It is reasonable that such small degrees creates illusion that a photon possesses properties of particles.

6. Medium structure directly leads to the notions of Quantum Mechanics, beginning at quantification of electronic "orbits" in atoms. This medium determines the "allowed" spots for electrons to be placed around a nucleus. Thus medium is a necessary place for the existence of all matter or matter of the Universe. The so called Compton length of electron wave is one of the validations of this statement. It is directly calculated to a high accuracy according to electric structure of vacuum.

7. Thus Plank's constant is not a mysterious "quantum of action", on the contrary it is entirely determined by medium parameters. Thereby the crisis (which conventional physics is accused of) can be logically overcame by the introduction of medium which is capable to take radiation in electromagnetic region only by quanta. Plank's constant is always presented at all quantum approaches. It is additional evidence in favor of the necessity to take into account the medium as natural place for existence of all the matter in Nature.

8. It is still a question what processes take place in the centers of galaxies. The observations show that the centers of galaxies create star matter. They often flow out the centers and settle themselves at approximately the same plane. It is an evidence of the fact that centers of galaxies quickly rotate and the favorable conditions for stars to reject matter are created. Similarly planetary systems are created around the rotating stars. It is thought that centers of galaxies are gigantic black holes. In the context of the concept of medium for matter existence it can be set up a hypothesis that being at some special state the medium creates stellar systems, i.e. galaxies.

9. Astrophysicists more and more trend to accept the existence of unknown "dark" matter, which occupies approximately 70% of all matter. It is said that due to antigravitation property this dark matter is responsible for the expansion of the Universe. Hypothesis on the nature of gravitation gives the affirmative replies to such suggestions as: expansion of the Universe is caused by weak electric charge of the medium and distributed mass of magnetic continuum is the very dark matter.

10. All elementary particles (electrons, positrons, mesons, protons, neutrons etc.) are in the medium and interact with it. In the case of electrons and positrons this interaction causes the great extension of dipoles of medium which directly adjoins to borders of particles. This extension helps photons to break the particles. In case of protons, there is such a breakdown of the medium at their borders that protons turn to be dressed in "coats" of virtual electrons and positrons. And medium is shown to be in entire state only when reaching the first Bohr orbit. This interaction of the medium and particles leads to the factors which determine the life time of some of them. Thus life time of a neutron is up to 30 minutes depending on the state which it has while leaving the nucleus. For mesons "the tearing" Coulomb forces, which exist between the medium and particles, are very powerful that makes the life time of mesons very short. However if the particles moves with a high speed relatively to the medium, then these forces noticeably decrease and if the speeds of motion is close to velocity of light then these forces become very small. The life time of such particles noticeably increases. In Einstein's theory it is said about "deceleration" of time. Finally the life time of particles is determined by the inner steadiness and outer influence of the medium. Protons have fantastic binding energy and they cause such great external destructive effect that their life time becomes immense.

11. When particles move in medium with high speeds, there is a concentration of magnetic continuum which is recognized as increase of mass of particles at increase of their speed. Evidently, we can continue the list of physical phenomena which relate to the presence of medium for existing of matter in Nature. However it seems to be enough to admit that medium (physical vacuum, aether) is of a great importance for the very existence of the Universe and for the processes which take place there. "Mechanism" of gravitation and inertia has a special importance since

it is the only thing which can make clear the real mechanism of Nature. It is possible that the methodology, which is accepted in physics, is necessary for more accurate description of phenomena but it is not enough for understanding of the nature of "space" and matter. Research of the medium for existing of matter will be able to meet the conditions sufficiency.

The understanding of vacuum structure, which is created by electric lattice from charge dipoles, surrounded with magnetic continuum, gives an opportunity to control the forces of gravitation and inertia. The medium of vacuum can be influenced by:

1. The radiation which has frequencies coming to the frequency from point #11 of the list of parameters.
2. Electric voltages which exist in vacuum (it is not very promising because of real matter breakdown).
3. Magnetic intensities (magnetic flux density). It is the most promising influence method (1-10 Tesla is enough to compensate terrestrial gravity).
4. Transformations of low accelerations to high accelerations of impact type.

Potential electric and magnetic energy is immense in vacuum medium. Reasoning from energy of one dipole, which is equal to 1.6x10 (-13) Joule, we will derive the value of electric energy equal to about 10 (+31) Joule per one cubic meter of the medium that is equivalent to mass annihilation of 10 (+15) kg!

References

1. Rykov A.V. Foundations of aether theory// RAS, M., 2000, p. 54
2. Rykov A.V. Hypothesis on the nature of gravitation// MSU, M., 2001, pp. 59-63

◆

Spartak M. Polyakov

(09 January, 1931 – 04 June, 2003)

Spartak M. Polyakov, a legendary physicist-experimentalist, known for his research in the field of gravitation, has died. Polyakov was the author of more than 50 research works, among them "Introduction into experimental gravitonics». Polyakov was the creator of the new model of photon. He also conducted numerous research in the field of electrodynamics, gravitational phenomena and superlight connection.

Spartak M. Polyakov graduated from Kishinev State University with degree in "General Physics". For many years he worked at the top secret military engineering department "Istok" (Russia).

Plyakov's alternative physical theory allows explaining such phenomena as magnetostriction and optical magnetization. The basic postulate of this theory states that the speed of propagation of gravitational waves is dozens of times faster than velocity of light regarded by the traditional science as the limit. In his experiments Polyakov demonstrated such methods of generation of gravitational waves as precession of gyroscope and remagnetization of ferromagnetic.

While working for "Istok", Polyakov designed on his own a device which is possibly the first gravitational motor in history. Total specific thrust produced by rotation of gravitating mass comes to 2.5 kg/kWt. This index is close to that produced by the engines of modern helicopters, which is equal to 8 kg/kWt. Practical application and further development of Polyakov's ideas can provide humanity with new kinds of communication, gravitational engines and free energy devices.



Adams Motor

Principle of Operation and Experimental Data

Sergey S. Abramov, Russia

Email: a_serge@cards.lanck.net

Adams' motor-generator represents the type of devices which use, as their creators claim, so-called "free energy". The term "Zero point energy" is also used in some sources [1, 2]. Due to quanta-mechanical fluctuations, this energy exists even at zero temperature. Adams' motor-generator belongs to the group of Switch reluctance motors [3]. Robert Adams, **former Chairman of the Institute of Electrical Electronics Engineers, USA (New Zealand section)**, designed this machine in the late sixties of 20th century. Similarly to all the devices utilizing free energy (referred to in come sources as "overunity devices"), Adams' device remains practically unknown to the general public. **The device is rather simple to assembled even at home, which I experimentally proved. However, it is necessary to be very careful while choosing the model parameters. As to the latter I have managed to collect quite a big number of instructions from existing sources; the summary of these instructions is presented below in this article. Based on these instructions, a low-power model can be assembled even without a mathematical analysis and modeling of electromagnetic field. Such model would certainly facilitate optimization of the device.**

Adams' motor is most frequently a DC machine; however, it can also use an AC source through a rectifier. In the latter case only the adjustment of the device and its control system can be provided.

Editorial: We disagree with some assertions of the author; however this article is of great interest.

My experiments on my own model do not yet allow me to make an unambiguously positive conclusion concerning the possibility to generate excessive energy. Experiments with my new control system designed on the base of AVR controller AT90s2313-10PI (it is produced by Atmel company (http://www.atmel.com) will allow to be more specific. Below there is a general analysis of the motor principle of operation and a number of recommendations concerning the construction and technology. I do not propose to take this as compulsory rules to follow; other technical solutions are possible.

Basing on the principle described in this article, R. Adams (the link to his articles is available at: http://www.aethmogen.com/wri/intro.shtml) created a few DC motor-generators which operate on permanent magnets. Some of them, according to information found on the Internet, have manifested 690% electrical efficiency and 620% mechanical efficiency. These devices operate at room temperature without overheating. My device has shown between 1 and 3 degrees overheating after an hour of functioning. However, it is easy to prove that such overheating is predictable for an average current of 0.15 A in coils of 35 mm long and 25 mm in cross sectional diameter. I have not been able to prove the data published on the Internet concerning the Adams motor capability to operate when the stator temperature is a few degrees lower than that of the environment. The temperature of the coil and of the power transistor is a good indicator of correctness of the circuit set-up and of functioning of the control circuit. There were cases when transistor and coil were noticeably heated after adjustment. Usually this was explained by a bad choice of points of transistor switching or by too extensive current impulses in the stator (which must amount to approximately 25% of period length). After the required adjustment the motor continued to operate almost without overheating.

Adams' motor was first mentioned in Australian Nexus Magazine in 1992. Later, Harold Aspden (Britain) proposed a slightly improved version of the motor and received Great Britain patent No. 282708 [4], which strongly reminds of the original version published by the above magazine. **Adams' device** represents an electrical motor and/or generator consisting of a rotor with radially directed permanent magnets and of a stator also constructed with a few radially directed and periodically magnetized cores with winding. (Fig. 1). In some models axial orientation of magnets and coils are also used.

Permanently magnetized poles of rotor can include any number of poles, even an odd number. Analogous poles of the magnets (all N poles or all S poles) are directed outside. A version with alternating poles is also possible; such model allows the torque to increase. In this case, after passing a rotor pole the stator is demagnetized by the current impulse and begins to be attracted by the magnet of different polarity. This circuit requires a more complicated control; on the other hand, it manifested rather good results in certain models.



Fig. 1

Poles with winding placed on the rotor are radially oriented in order to obtain a supply of energy emerging as a result of the influence of counter emf from the rotor poles. Steel or iron cores are used for the poles of the stator with winding. It is also possible to use other materials, at that the core must have high magnetic inductivity and low level of magnetization reversal losses. The stator winding consists of a few hundred turns. The current inducted by the magnet in this winding will have the polarity which will cause repulsion of the magnet. Since the electromagnetic state of stator changes quite significantly and quite fast, then the stator core can be considered to be the most crucial element of the device. Ignoring this fact was one of the most frequent mistakes made by those who tried to reproduce Adams motor.

The current inducted in the stator is the function of:

- field size,
- number of winding turns,
- speed of flux changes.

Resultant parameters of this device cause each pole to be attracted or repulsed by stator poles when the rotor is in certain position in case when the rotor is unbalanced. To achieve this effect it is required to switch the input current in control coils after the signal from sensor of rotor position. R. Adams used a mechanical switch as a sensor. My device and a number of other devices use the signal from two Hall sensors. However, according to experimenters' information, better results are achieved if a position optical sensor is used.

Time of switching of impulses is determined by the size of the motor itself, i.e. the speed of motor rotation, location of rotor magnets towards the stator windings and the distance the rotor magnets pass while moving by the poles with stator winding.

It is necessary to take into account that any part of this motor can be modeled based on the existing electromagnetic theory and no part of the motor is in conflict with any laws of electromagnetism. There are so many ways to construct Adams' motor that any version may be considered to be correct.

One can say that the frequently pulsating electromagnetic process in the stator core is what allows Adams' device to function as a kind of diode which borrows energy from the field of permanent magnet but then does not return that energy in full.

5 stages can be defined in the periodical process which takes place in stator:

1. The magnet is attracted to the stator core. The permanent magnet is attracted to the iron core of the stator with winding. While doing so no consumption of electrical current takes place. It is as if kinetic energy is borrowed from an internal ferrite magnetic source and is supposed to be returned into the stator.
2. Stator core is magnetized. During the period when the magnet is positioned in front of stator core they both comprise a single magnetic conductor with an air gap and the stator core becomes an extension of the magnet side it faces. It is usually supposed that the energy "borrowed" on the first stage is getting back now.
3. Stator core is demagnetized. When the stator core becomes rotor magnet extension, the circuit closes and current impulse gets to stator windings. I have seen the instructions saying that the angle between

stator axles and rotor magnet must amount to 7-8 degrees as shown in Fig. 1. However, my model made it clear that at increase of speed of rotation it is necessary to start the coil a little earlier, when the magnet axle has not reached the stator axle. Probably this applies to the circuit with a Hall sensor only and if an optical switching is used the making angle will be different.

Magnetic field of this current acts to compensate magnetization of the stator, which is caused by the field of rotor magnet. Consequently, the summed current significantly compensates attractive force between rotor and stator and the rotor can freely rotate by using the inertia obtained at stage 1. This process is characterized by the fact that this current impulse is amplified by the current inducted in the stator winding by rotor magnet which, in accordance with Lentz law (1834), counteracts the power which induced it. Consequently, kinetic energy obtained as a result of attraction of the rotor to the stator at stage 1 is transformed into electrical demagnetizing impulse in stator winding during the period when the rotor and stator directions are congruent. This is the unique overunity characteristic of this model. However it is obvious that instead of returning this energy the motor transforms it into electromagnetic demagnetizing field.

4. Restoration: when the rotor is removed from the stator attraction zone the latter looses energy and returns to its initial demagnetized state. Decreasing electromagnetic field creates a current wave of reverse polarity which can be stored in the capacitor.
5. Reiteration of the process: This periodical process is renewed as described in stage 1 during the next magnetization of the stator, excluding the fact that emf preliminarily stored in the capacitor, on term of presence of suitable electrical circuit, can be used for facilitating stator demagnetization or even used to supply the load.

It may be briefly summarized that the frequently pulsating electromagnetic process in the stator core is what allows Adams device to function as a kind of diode which borrows energy from the field of the permanent magnet but does not return that energy in full. The important characteristic of such motors is that the stator windings are used for demagnetizing and not for magnetizing as it could seem from the first sight.

It is noteworthy that there is a small pause between attraction to the stator and repulsion from the stator. The effect of attraction to the core takes place a split second before the repulsion effect manifests clearly. This pause being the reason of electromagnetic asymmetry creates conditions necessary for achieving overunity effect. If the attraction to the core and repulsion by means of Lentz currents were taking place simultaneously and with the same power there would not be any overunity characteristics. That is why the rotor must be as lightweight as possible. From this point of view, T. Harwood's model is the most lightweight of the known models. In Harwood's device the magnets are mounted between two CD disks fixed on the shaft by means of plastic washers and glue. My model is heavier, which can be considered as one of its disadvantages.

The principle of operation of Adams' motor is based on the balance, which creates the electromagnetic asymmetry. To get the motor to operate the magnet must be attracted to the stator core which must have a smaller cross-section area in order to create attraction without any significant repulsion effect from the stator windings mentioned above. When stator and rotor axles are congruent the Lentz induced current must be sufficient for compensating the natural attraction of the magnet to the stator core. Consequently, stator windings must have enough turns for demagnetizing effect, but not to the extent that this effect fully manifests before the rotor reaches the stator axle when Lentz current has its maximal value.

During my experiments at 12 V voltage and on using two independently controlled stator coils the speed of rotation reached 3400 rpm. Please note that while reproducing such device it is necessary to take certain measures in order to ensure safety in case of possible breakdown. **The magnet disconnected from the rotor may be dangerous!**

Technological recommendations are as follows:

1. The device must be low power. It is better not to try to begin with a motor functioning in kilowatt range. This is feasible only on condition of having all necessary technological documentation which is not available at the moment.
2. The preferable voltage for the first model is 12 V. If the voltage is less the speed of rotation is too slow for indicating the expected characteristics of the device.
3. The best magnets are ferrite ones with dimensions 4x4x5 (where 5 is the magnet length). The practice has shown that at 12 V voltage neodymium-iron-boric (NdFeB) magnets cause a jerky rotation of the rotor.
4. The side of the stator core facing the rotor must

Control circuit with hall sensors



Fig. 2



have the size which is 4 times smaller than the corresponding side of the magnet. If cross-section area of the stator is larger, a bigger part of magnet field comes to the stator core when their axles coincide and thus there is nothing to induce Lentz' currents in the stator windings. It is a common point of view that it is necessary to try to minimize the volume of a device and to obtain the maximum efficiency at minimal material expense. In practice, it has always been the goal while designing electrical machines to decrease losses in stator I^2R. As for the Adams motor, it requires not only the use of disproportionate magnets but also stator windings with disproportionate number of turns specially designed to obtain maximum Lentz' currents that is achieved by hundred of turns of winding.

5. It is necessary to define approximately the effective zone of the magnet field. If practically applicable magnet field is equal to, for example, 8 cm, and the stator has a 10 cm long winding, then more than 20% of turns will not be efficiently crossed by magnetic force lines and will only create an excessive mass of the device. To define the degree of effective action of the magnet we can put a paperclip on the table and move it gradually in direction of the magnet until the paperclip is attracted to it. Actually if we take into account friction losses then the magnet influence zone will be a little larger. That is why the stator winding in the axle direction can be 10% larger than that in this experiment. The description of this test has been found on Tim Harwood's website (http://www.geocities.com/theadamsmotor/cdmotor.html).

6. The air gap clearance between the stator and the rotor must not exceed 1 1.5 mm.

7. Use as little metal in the device as possible. It is preferable that the metal is used in the core and stator windings only.

In order to increase the efficiency of this motor, it is necessary to build it in a manner, which allows removing the counter emf from the stator windings. To do that, this emf may be taken off and stored in the capacitor. The article published by Nexus magazine and Great Britain patent No. 282708 consider special generator windings; however, no sufficiently detailed data on operating rules are provided. Michael Smith (Australia, http://www.Fortunecity.com/greenfield/bp/16/content1.htm) has unequivocally informed me in one of his letters that


XP1
From the computer LPT via the serial programming interface (SPI) to program the controller A1
Circuit
1 Miso
2 Mosi
3 Sck
4 Reset
5 +5V
6 Gnd
A1
Reset
PD0
PD1
XTAL2
XTAL1
(INTO)PD4
PD3
(TO)PD4
PD5
Gnd
+5V
VCC
PB7(SCK)
PB6(MISO)
PB5(MOSI)
PB4
PB3
PB2
PB1(AIN1)
PB0(AIN0)
PD6
Y1
C1
C2
A1- At90s2313-10PI
ZQ1-6-10Mhz
Q1-TP3691
Q2-2SD729H
C1, C2-20-30 pF
SCR1 - opto thyristor
Controller's I/O ports can provide the output current about 20mA
R1
D7
+5 V
XP2
Circuit
1 Gnd
2 +5 V
3 Hall sensor 1
4 Hall sensor 2
5 +12V
A2(Hall sensor)
Internal resistor (30 kOhm)
A3(Hall sensor)
1-st battery (1.3 Ah)
S1
+12 V
Stator coil
R3
R2
VT1
D1
R4
VT2
D2
D3
D4
D5
D6
C3
R5
SCR1
2-nd battery 5Ah

Fig. 3

he has not achieved generation of excessive energy in such a system. During his experiments a two-battery circuit proved to be more effective. In this circuit, during a part of periodical process the energy is stored in the capacitor and then a command is transferred to a thyristor, which discharges it into the second battery. At that capacity, the second battery must be no less than 4 times more than the capacity of the first one. Otherwise the excessive energy does not have enough time to be stored during the discharge. I have also managed to provide the charge of the second battery, but the control circuit has not been assembled fully yet, as it is shown below in Fig. 4. Better results are expected when its final adjustments together with AT90s2313 controller program have been made.

In order to increase the efficiency of this motor, it is necessary to build it in a manner, which allows removing the counter emf from the stator windings.

I managed to start my first model of the motor in April, 2002. Afterwards, I spent approximately six months increasing its rotational speed from 750 to 3200-3400 rpm, decreasing vibrations and improving control circuit. In order to achieve a better rotor balance I had to re-construct it twice. It is very important to align the axles of the bearings with maximum precision; otherwise a considerable decelerating torque will manifest. The shaft penetrates the lower moving base. It is possible to rotate the base at a small angle for the precise alignment of axles and then to fix it with screws and nuts.

In order to decrease aerodynamic losses, two veneer parts are mounted between the magnets. Thus I managed to increase the speed, although the rotor weight has also been increased.

Stator cores are made of plates taken from a disassembled radio transformer. Tim Harwood used nails with winding, however, my own results with such core proved to be poor. Dimensions of the core are 10x11x50 mm.

The type of power source is also important. First, I connected a 9 Volt accumulator of "Krona" type in series with three metal-hydride 1.2 V accumulators. The speed of rotation did not exceed 1500 rpm. But when I used a lead/acid accumulator with 1.3 Ah capacity, the speed increased to 2600 rpm if there was one coil on the stator.

Four magnets mounted on the rotor have the dimensions of 20x20x35 mm and are fixed on a 105 mm glass fiber laminate disk. The current impulses proved to be too wide, by up to 40%. In order to make them shorter (down to 25-30%), I had to use the control circuit (Fig. 2) with two Hall sensors. At the signal from the first sensor the stator current is started, the second sensor switches it off. Many experimenters used a timer to control the impulse length while working with Adams' motor that is more practical since impulses are supposed to be wider during the start. I took this factor into account while designing the controller circuit. Current impulses are shown in Fig. 3. Their fronts are supposed to be shorter; it is probable that the coil has more inductivity than necessary. The impulses amplitudes are slightly different which is explained both by the difference in volume of induction of the magnets and by difficulty in achieving similar air gaps while working at home.

I have provided the charge mode of the 2-nd battery at my two-battery design. After 75 minutes of operation of the device the source lost 0.17 Volt whereas the second battery was charged at 0.36 Volt. The capacity of both batteries in this experiment was equal. Besides after such charging the second battery started to discharge quickly. The circuit where stator current charges the battery directly has to be considered ineffectual (see Fig. 1). To evaluate the charge, which is gained in non-hermetic accumulators, the density of electrolyte can be measured.

To obtain a more uniform torque I added the second stator which is controlled independently. This required installing two more Hall sensors and an additional power transistor. The angle between axles of the coils amounts to 135 (180-90.2=135) degrees. When the current is present in one part of the stator it is absent in another and vice versa. The speed has increased up to 3200-3400 rpm, and I deemed the further increasing of this characteristic unnecessary.

Increasing the number of circuit elements does not seem a good idea. Futhermore the adjustment process becomes more complicated. In order to improve the circuit of battery charge adding a timer circuit is required. Thus, I decided to use a controller circuit. A simple Basic program has been developed for AVR controllers. This program operates in mode similar to transistor circuit, but its capability can be significantly increased due to the built-in processor timers. Today program improvement is the most efficient way to solve the task of generation of excess energy in this circuit.

This article is meant to elucidate the principles of operation of one of the simplest devices which pretend to become an "overunity device", "free energy machine", "perpetual motion machine", whatever you call it. Probably someone will try to create such motor-generators on their own. I hope that my article will serve as a guide and will help to avoid the mistakes made by many experimenters (including myself) before they managed to build their own model.

References

1. Puthoff H.E. Source of vacuum electromagnetic zero-point energy. Phys. Rev. A 40.4857-4862; also 44. 3385-3386
2. Bernard Haich, Alfonso Rueda, Puthoff H.E. Physics of the zero-point field: implications for inertia, gravitation and mass. Speculation in Science and Technology, Vol.20, p.p. 99-114, 1997 (preprint version)
3. Miller, Switched Reluctancy Motors & Their Controls, ISBN: 10881855-02-03
4. Patent No. GB 2,282,708 (from NEN, Vol. 4, No. 8, December 1996, pp. 1-7).

INFINITE ENERGY
Cold Fusion and New Energy Technology
Including Conventional and Renewable Energy

Infinite Energy Magazine

INFINITE ENERGY
The "Lifter" Phenomenon

* Cold Fusion * New Energy
* New Science
* New Technology
Subscriptions, 6 Issues Per Year
$29.95 North America
$49.95 Foreign
Single Sample Copy
$5.95 North America, $10.00 Foreign

Infinite Energy Magazine
P.O. Box 2816-FV
Concord, NH 03302-2816
Phone: 603-228-4516 Fax: 603-224-5975
http://www.infinite-energy.com

Prediction and Experiment on Field Transformation in the Model of Extended Space

Dmitry Yu. Tsipenyuk, Russia

119991, Vavilov str., 38, Moscow
E-mail: tsip@kapella.gpi.ru

A series of preliminary experiments on checking the possibility of generation of gravitational field at deceleration of charged massive particles in matter was carried out.

Introduction

In previous works [1-3] generalization of the special theory of relativity (STR) for the five-dimensional extended space with metric (+;-,-,-,-) was offered.

The model of extended space (ESM), combining electromagnetic and gravitational interactions, was made. For this, there was made (1+3)-dimensional space extension $M(T;\vec{X})$ of Minkovsky to (1+4)-dimensional space $G(T;\vec{X},S)$. Let us call it extended space. As the 5-th additional coordinate the value already existing in Minkovsky space, i.e, S interval

$$s^2 = (ct)^2 - x^2 - y^2 - z^2 \qquad (1),$$

is used.

Let us note that attempts to combine gravitation and electromagnetism have a substantial background.

Modern approaches to this problem trace back to the work of F. Klein [10] in which he proved that classical Hamiltonian mechanics can be represented as optics in the space of a great number of dimensions.

Then T. Kaluza tried to generalize Einstein's theory of gravitation to include electromagnetism in this theory as well [11]. He proposed to consider (1+4)-dimensional space with metric depending on potentials of the electromagnetic field. Kaluza's idea was evolved by O. Klein [12], G. Mandel [13] and V. Fock, and the model they had created got the name of the Kaluza-Klein theory. They proved that the trajectory of a charged particle has the form of a geodesic line with zero-length in 5-dimensional space.

In his works on 5-optics Y. Rummer [15] proposed to assign action dimensionality to the new dimension and to consider it periodical with the period equal to Plank's constant. Note that rest mass of particles in all these constructions unlike the model of extended space evolved in the works [1-7] was considered a fixed value. Subsequent development of multidimensional theories is given in the monograph [16].

A separate approach is represented by multidimensional constructions in the theory of strings and superstrings [17].

Approach to construction of (1+4) dimensional space evolved in [18] is close to the proposed model of extended space. Here it is proposed to use mass (matter) as the 5-th coordinate. However, in this model, as its originators admit, it is impossible, for example, to create the energy-pulse tensor. There is no such disadvantage in the extended space model [8].

Mechanics of a material point [1, 2, 7] and electrodynamics [1, 8] were made in the introduced extended space. Besides Lienar-Vihert potentials [6, 19] corresponding to such a model were also considered and properties of solutions of Maxwell augmented system of equations which are in conformity with these potentials were analyzed there.

Gravitational effects in extended space, such as the second orbital velocity, red shift and light deflection [4, 20, 21] were considered. It is proved that the formulas received in the general theory of relativity for calculation of values of these effects can be received by an absolutely different method within the framework of the extended space model as well.

It was proved [6, 19] that the fields in the model of extended space can change their signs. Such change of field-intensity sign and, consequently, change of sign of Lorenz force can be associated with radiation reaction of these fields which occurs when charged particles move with acceleration.

Thus, on the one hand, it was proved in the model of extended space that it is possible to get certain formulas describing gravitational effects of the general theory of relativity [4,20] using the technique of turns in extended space. On the other hand, it was proved that the electromagnetic field can be a source of gravitational field [6, 19].

Besides, a moving massively charged particle under deceleration can create a variable gravitational field around itself [9, 6, 19]. The following experiment was offered for experimental check of the latter assumption. In this experiment probable occurrence of gravitational field at deceleration of relativistic electrons was determined by change of oscillations of a massive torsion pendulum.

Experimental device

A narrow bunch of relativistic electrons from a microtron 1 (average power of the bunch is 450 Wt, electrons energy is 30 MeV) was directed to a brake target (position 2 or 3) made of wolfram exactly where deceleration of accelerated electrons took place.

A special torsion pendulum suspended on a vertical suspender 5 made of a springy metallic string with 1,8 mm diameter was placed near the brake target to register gravitational field which could probably appear at electrons deceleration. The length of the suspender made is 85 cm. The pendulum could rotate freely on the suspender only in horizontal plane.

The pendulum consisted of a light aluminum rod 4 (with a length of 120 cm) on the ends of which massive loads 6 and 7 made of non-magnetic material were fixed. The weight of each load was equal to 4kg. In the center a pendulum was fastened to a vertical suspender 5 by a special mounting preventing slippage during turns. To reduce the influence of magnetic inducings the pendulum was grounded and additionally screened by metallic grid from all sides. The period of free oscillations of the pendulum made were about 40 s.

Rigidity of the pendulum vertical suspender could be changed by means of limiting the length of effectively operating part of the suspender. As a result, the period of oscillations could be continuously changed within the limits of 40 to 27 s.

To reduce the influence of mechanical noise and to introduce additional attenuation in pendulum oscillations two liquid dampers 10 and 11 located near the pendulum massive loads were used.



Fig. 1
Experimental device
1 – microtron, brake target made of wolfram – positions 2 or 3, 4 – rod, 5 – vertical suspender, 6 and 7 – massive loads, 8 – mirror, 9 – He-Ne laser, 10 and 11 – liquid dampers, 12 – optical system, 13 – concrete protection, 14 – observation channel, 15 – video system, 16 – screen.

Pendulum deflections were observed on a graduated screen by deflection of a laser beam reflected from a flat mirror 8. For this, the beam from a continuous He-Ne laser 9 through the optical system 12, which constricts the divergence angle of the laser beam, was directed to the mirror through a special narrow channel 14, located in concrete protection 13 around the microtron. By means of a video system 15 the beam reflected by the mirror was registered on the screen 16 located at a distance of 500 cm from the mirror. The video system allowed remote checking of vibrations of the laser spot and additionally enlarged the visual angle up to 12 times. The diameter of a focused laser beam on the screen was made 0.15 mm. The maximum turn angle of pendulum for the reflected beam to remain within the receiving channel was approximately 2 degrees. The accuracy of turn angle registration of the whole system was $5x10^{-4}$ degrees.

The pendulum was placed in such a way that one of the massive loads were close to the brake target at a distance of about 20 cm. There was also an opportunity to move the brake target from one end of the pendulum (position 2) to the other (position 3). This allowed changing the place of deceleration of electron bunch at constant parameters of all unaccounted mechanical noise and magnetic inducing. Thus, direction of pendulum torsion was changed under probable exposure of occurring gravitational radiation.

Below there is a photo of the experimental plant (see also the colored photo on the cover page).

Calibration Measurements

To make measurements it was necessary to select optimal parameters of the pendulum (masses of loads, suspender rigidity and the value of oscillations attenuation). On the one hand, while carrying out the measurement it is desirable that the amplitude of pendulum oscillations should be as maximal as possible. On the other hand, the beam reflected from the mirror should not go outside the limits of observation, restricted by the diameter of the narrow observation channel in radiation protection around the accelerator. Besides, the typical operating time of the loaded accelerator usually is 10-15 minutes. Necessity to accumulate the minimum of sufficient statistical data within this time limited oscillations period and the time of setting of the pendulum in a new equilibrium position at outside influence. All these requirements were as far as possible taken into account during selection of the final setting parameters.

An example of free oscillations of the pendulum in the presence of minor mechanical vibrations caused by the operating of vacuum pumps is given in Fig. 2, series I (the experiment took place on 31 May, 2001). The diagram shows the amplitude of laser beam oscillations on the screen 16 (upper and lower rows of values) depending on the number of oscillation. The laser beam is reflected from the mirror 8 which was fixed to the pendulum. The diagram also shows the current central equilibrium position (the central row) calculated by these amplitudes. Series I represents oscillations at influence of the background mechanical noise. Series II represents the response of the pendulum to minor permanent outside force. Accuracy in determination of position of the center of a light spot was 0.1 mm.



Fig. 2
Calibration Measurement 31 May, 2001

Measurement was carried out with one liquid damper in service and with increased rigidity of suspender (it was made by means of limiting the effectively operating suspender length). The period of free oscillations in these series was 29 sec. In this case there were set continuous oscillations of the pendulum around the average value of balance of 2.2 mm with the average amplitude of values fluctuation of about 0.2 mm.

Air cooling of one of the massive loads by a very light continuous air flow was carried out to study response of the pendulum to a minor constant external force. In this case (Fig. 2 Series II) noticeable change of pendulum oscillations already took place after 3-4 periods. Absolute setting of a new balance took place after 7-8 oscillations.

In the case of another series of calibration measurement (held on 7 June, 2001) both liquid dampers were used and rigidity of suspender was decreased. The period of free oscillations of pendulum was about 40 sec.

Addition of the second damper and decrease of suspender rigidity caused, on the one hand, increase amplitude of pendulum oscillations at influence of the external force and, on the other hand, in that case noticeable change of the equilibrium position of the pendulum took place after 1-2 oscillations.

Periodical checking of the invariability of initial central position of pendulum balance in time was also carried out. Thus, for example, in the series of measurement of 7 June 2001 measurement of equilibrium position was checked not only before the start of the main series of measurement, but also 2 hours after completion of the main works.

Experimental Results and Their Analysis

Within the period from 17 May, 2001 to 7 June, 2001 7 measurement series were carried out at various operation modes of the accelerator and at various pendulum parameters.

A record of check of equilibrium position of the pendulum was carried out before and after switching off the electron bunch (as well as during calibration measurement). At the same time, all electric inducing and mechanical noise remained stable within the whole measurement period. This was achieved by means of additional switching on all the devices which were used during measurement (water and vacuum pumps, magnetron, deflecting magnets, etc.) and their switching off only on completion of the measurements.

In Fig. 3 there are results on measuring the central position of the pendulum when brake target is in position 3 (see Fig. 1). Series I and III on the diagram correspond to check measurement directly before switching on and several minutes after switching off the electron bunch. Series II-A and II-B totally reflect pendulum oscillations at the time when the accelerator is operating (for about 10 minutes) and for some time after the bunch is off. Additionally, a trend line is drawn (averaging by 3 points).



Fig. 3
Measurement of central position of pendulum equilibrium when brake target is in position 3.

Results of a similar experiment are given in Fig.4. The only difference in this experiment is that the brake target is in position 2. Also a trend line is added (averaging by 3 points). Series I and III are check measurements made directly before switching on and after switching off the electron bunch. Series II are pendulum oscillations at the time when accelerator is operating.



Fig. 4
Brake target in position 2

From qualitative comparison of trend lines (Fig. 3 and Fig. 4) it can be derived **that there is a correlation between switching on the electron bunch and the average deflection of the pendulum from equilibrium position if compared to checked series before and after switching on. At that, direction of deflection changes depending on what pendulum load the brake target is close to.**

Unfortunately, due to circumstances beyond the control of the author it seems to be difficult to improve experiments accuracy or to accumulate much of statistical data by now. Estimate of the value of the force which may cause such a shift of position of pendulum equilibrium was carried out. In the experiments this deflection did not exceed 1-2 mm (in the units of registering scale). Calibration of a rigid suspender (if it applies to a massive load at a pendulum end) gives the upper boundary of this force of not more than 10^{-6} N.

Conclusion

A series of experiments were made on checking the possibility to generate a field at deceleration of charged massive particles in matter.

Electrons accelerator was used as a source of charged particles. A narrow bunch of relativistic electrons (average beam power is 450Wt, electrons energy is about 30 MeV) was directed at a brake target made of wolfram where deceleration of accelerated electrons took place.

Measurement proved appearance of statistically reliable deflection of a torsion pendulum, one of massive loads of which was located close to a brake target by the time of deceleration of relativistic electrons.

Change of direction of pendulum torsion at shift of a brake target from one end of the pendulum to the other was also registered. The value of the force which causes pendulum deflection has the upper boundary of N.

Of course, these first experimental results on checking the predictions made on the basis of development of the model of extended space are of preliminary nature and need more thorough checking. That will be the basis of future experiments.

References

1. Tsipenyuk D. Yu. Andreev V. A, "Extended space and model of combined interaction", Short reports on physics FIAN, No.6, pp. 23-24, (2000); gr-qc/0106093
2. Tsipenyuk D. Yu., Andreyev V. A., "Explored in Russia" E-magazine,60, (1999); http://zhurnal.ape.relarn.ru/articles/1999/060.pdf
3. Tsipenyuk D. Yu., Andreyev V. A., "Structure of extended space", Preprint IOFAN, 5, 25p., Moscow, (1999)
4. Tsipenyuk D. Yu., "Field transformation in the model of extended space: prediction and experimental test", Gravitation&Cosmology, Vol.7, No.4(28), pp336-338, (2001); physics/0203017
5. Tsipenyuk D. Yu., "Field transformation in the extended space model: prediction and experimental test", Short reports on physics FIAN, No, 7 p.39-49, (2001); physics/0107007
6. Tsipenyuk D. Yu., Andreyev V. A., "Lienar-Vihert potentials for the extended space model", Short reports on physics FIAN, No 6 p.3-15, Moscow,(2002); physics/0302006
7. Tsipenyuk D. Yu., "Explored in Russia" e-magazine, 81, p.907-916, (2001); http://zhurnal.ape.relarn.ru/articles/2001/081.pdf
8. Tsipenyuk D. Yu., Andreyev V. A., "Electrodynamics in extended space", Preprint IOFAN, 9, 26p., Moscow, (1999)
9. Tsipenyuk D. Yu., Andreyev V. A., "Interaction in extended space", Preprint IOFAN, 2, 25p., Moscow,(2000)
10. Klein F. Zeits.f.Math.a.Phys., 375, (1901) (see translation in collection "Variation principles of mechanics", M.: Physmatgis, 1960)
11. Kaluza Th. Sitz.d.Preuss.Akad., 966, (1921) (see translation in collection "Albert Einstein and gravics", M.: Mir, 1979)
12. Klein O. Zeits.f.Phys., 37,895, (1926)
13. Mandel H. Zeits.f.Phys., 39,136, (1926)
14. Fock V. Zeits.f.Phys., 39,226,1926
15. Rumer Yu. B. Investigations on 5-optics, M., Gostehizdat, 1956
16. Vladimirov Yu. S. Dimensionality of physical space-time and integration of interactions. M., MGU, 1987.
17. Green M., Schwartz G., Vitten E. Theory of superstrings, v.1, 2, M.: Mir, 1990
18. Wesson P.S. Space, time, matter: Modern Kaluza-Klein theory. Singapoure, World Scientific publishing Co.Pte.Ltd, 1999
19. Tsipenyuk D. Yu., Andreev V.A., "Lienar-Vihert potentials and Lorenz force in extended space", Preprint IOFAN,1,20p., Moscow,(2001)
20. Tsipenyuk D. Yu., Andreev V. A., "Gravitational effects in extended space", Preprint IOFAN, 4, 15p., Moscow,(2001)
21. Tsipenyuk D. Yu., "Field transformation in the model of extended space: prediction and experimental test", Preprint IOFAN, 5, 24p., Moscow, (2001)
22. "Tsipenyuk D. Yu., report "Electromagnetic and gravitational interaction in extended space" at the Conference of Nuclear Physics Department of the Russian Academy of Sciences (RAN) "Physics of Fundamental Interactions", 27 November-1 December 2000, ITF, Moscow, http://www.itep.ru/
23. Tsipenyuk D.Yu. and Andreev V.A., "Interval as the fifth coordinate" proc. of 5-th Int. Conf. on Gravitation and Astrophysics of Asian-Pacific Countries, PFUR, Moscow, 2001, pp.29-30. http://rgs.da.ru/
24. Tsipenyuk D.Yu., "Direct transformation of the electromagnetic field to gravitational field in the model of extended space: predictions and possible way of its experimental test", proc. of 5-th Int. Conf. on Gravitation and Astrophysics of Asian-Pacific Countries, PFUR, Moscow, 2001, p.28. http://rgs.da.ru/
25. Tsipenyuk D.Yu., "Model of extended space: Prediction and test experiments on possible transformation of electromagnetic field into gravitational field", proc. of XVIth Workshop on High Energy Physics and Quantum Field Theory (QFTEP), Moscow, Russia, 2001, pp.398-405. http://theory.sinp.msu.ru/~qfthep/2001/Proceed2001.html
26. Tsipenyuk D.Yu., "Model of extended 5-d space and possible checking experiments", presented at 5-th Moscow international ITEP school of physics (30-th ITEP winter school of physics), 20-28 Febr., Moscow, 2002, http://www.itep.ru/
27. Tsipenyuk D.Yu., report "Second experiment on checking prediction on field transformation in extended space" at the scientific conference of nuclear physics section OFN RAN "Physics of Fundamental Interactions", ITF, 2-6 December 2002, Moscow, http://www.itep.ru/
28. Urbah V. Yu., Mathematical statistics, M., USSR Academy of Sciences Publishers, 1963.

Joe Flynn's Parallel Path Magnetic Technology

Tim Harwood, USA

Email: timharwood@usa.net

There is a widespread opinion common to the mainstream academic community and also to various alternative scientific forums, that some kind of exotic new physics will be required to design and implement over-unity technologies. That is to say electrical motors, electrical generators, or other apparatus, which produce an excess of magnetic force or energy above the value actually inputted.

However, this has recently been experimentally demonstrated not to be the case, as I have validated myself in simple $20 experiments undertaken at home with parts bought from the local hardware store. It is the purpose of this article to educate readers that with care, thought, and a little work, it can be demonstrated that existing textbook physical law, freely allows for the extraction of excess electrical energy from magnetic systems.

The Flynn Research Project

Joe Flynn has been engaged in magnetic flux research for over 25 years now. His work is long standing, comprehensive, and in later years, well funded. It is reported $7m has been spent to date, with over $1m alone developing a revolutionary high performance magnetic motor. His equipment is validated, and apparently already in mass production for select customers. Yet few researchers have heard of Joe Flynn. This surprising situation will hopefully shortly be changed, and Joe Flynn awarded the scientific accolades he deserves, for being the genius master mind behind one of scientific history's most outstanding research projects. Since many lines of research have been formulated and explored by Joe Flynn, the following article presents only a brief summary of some of his best art apparatus, but is nonetheless sufficient to convey the basic ideas.

The first illustration (Fig. 1) is taken from Joe Flynn's US patent 6,246,561, and explains a simple magnetic force multiplication experiment, which forms the basis for the Flynn magnetic art. If the windings on either side of the central magnet, which are normally connected in series, are properly pulsed, the field of the permanent magnet in the center will be diverted to the opposite side of the core flux path provided. Or in alternative language, the side of the core that is pulsed is demagnetized, relative to the field of the permanent magnet used in the apparatus. This is elementary textbook physics anyone can understand.



Fig. 1

1.75 times more force is delivered to the legs of the core than is provided by the electrical input to the control coils

So what is surprising about this apparently simple apparatus is that the armature on the side of the flux core will contain 1.75 times more units of magnetic force, that could be manifested by the electrical input to the apparatus alone. Since the ability to arbitrarily move the force from one point to another is the basis for motion or work, however simplistic, we therefore have a basis for a system that can be developed for practical technological purposes. Expressed in alternative language, we also have the capability to engineer a time varying magnetic field, without the need for moving parts, which will allow development of systems that output electrical energy. Both capabilities are highly desirable, and offer substantial opportunity for technical development.

Following on from this basic experiment, there is a second simple and logical improvement in layout illustrated in Fig. 2, which should be obvious, but has been shown not to be the case. In this instance, the pulse is centrally located, and a dual flux field layout employed, which both demagnetizes the core relative to one magnet, and magnetizes it relative to the other. Since the two actions are complementary, the input required to manifest the flux switching effect is halved, therefore doubling 'efficiency.'



Fig. 2

3.47 times more force is delivered to the legs of the core than is provided by the electrical input to the control coils

It should be noted that while the efficiency is doubled, the absolute output may not be significantly improved. This is because the major weakness of this effect and technology is flux saturation of the core, with values depending upon the specific properties of the B-H curve of the core material employed, limiting the absolute output of both layouts the same.

The previous statements are not required to be taken on trust, and simple experiments have been proposed by Joe Flynn, such that anyone can validate this effect for themselves. Figure 3 is a simple experiment taken from the Flynn website (http://www.flynnresearch.net), that can be used to validate the principals put forth in this article.

Simple Magnetic Force Multiplication Experiments



Fig. 3

Parallel Path can deliver 3.47 times more force to the legs of cores than any competing conventional technology

An even simpler non electrical flux experiment was proposed by GM in the Parallel Path Egroup. My apparatus is illustrated below in Figure 4. It is no more than magnets and steel staple strips, bought from a local hardware store for a total of under $10. The Parallel Path effect can be replicated with identical apparatus, at only a slight increase in cost and complexity, with the addition of a simple 12V polarity reversible power supply, such as those commonly sold to power computer speakers, among other applications.

Simple Magnetic Force Experiments



Fig. 4

Relatively small changes in layout produce large changes in force

Conservation of Energy / Field Potential

One of the aspects of the Flynn technology people find most difficult to understand, is how you can have a device that delivers 3.47 times more magnetic force than is electrically inputted, yet not violate accepted principals of text book physics, as stated in the introduction. The key point here is conservation of energy. Magnetic fields do not gain energy – they are conservative. You can only ever obtain less energy from a magnetic field minus losses, than is in fact present. I feel this apparent puzzle can not be better explained, than by reference to Joe Flynn's own words:

"Since the Parallel Path System produced 3.47 times more force than the conventional system, with the same electrical input, it appears to violate conservation, this is only true when observed from a traditional view point. The system contains three flux producing sources (2 magnets and an electromagnet) which together are capable of producing a far greater force than is actually produced. All of the flux sources together can produce a force of 13.11 units, therefore in the physical sense a loss of 1 - (9.01 / 13.11) = 31% is realized."

So the system is 350 % efficient, in terms of delivered magnetic force compared to net electrical input, yet still conforms to the accepted physical principals of energy conversation, by being only 69 % efficient, in terms of the fields present in the system. However surprising this result may appear, the analysis presented is in outline correct, with the difference between fields present in the system, and net electrical input, being the important concept presented.

Losses in the System and Optimisation



Fig. 5

In order to properly optimise flux cores, an appreciation of the physics that underlies the transfer of flux within a core is required. The normal magnetization curve, or B-H curve, is a mathematical relationship between applied field intensity H, and resultant flux density manifested in the core B. It varies according to core material, and the curve will shift, if there is a starting magnetism within the core, such as that provided by the field of a permanent magnet. If the start magnetism is excessive, the core is saturated, and will not properly respond to the applied force H. A simple B-H curves is illustrated in Fig. 5.

Hysteresis is a delay between applied magnetic force H, and resultant flux density B, that again varies according to material type. It also manifests as a delay between the termination of force H, and the manifestation of flux density B. So, the system will not turn on instantly, and will not turn off instantly, in simple terms. This is because the magnetic memory of the core, means a flux vector remains within it, even when the application of magnetic force H has been terminated. If we apply a reversed force H to the core, the basic B-H curve is now expanded as in Fig. 6, with the memory effect also illustrated.



Fig. 6

Thus as can be seen, to return to the initial switched state, the remnance magnetism must now be overcome, hence input once in operation, will be greater than that required for the very first pulse. The area within the hysteresis curve gives a rough estimate for the amount of wasted energy, and along with other conventional sources of losses resultant in flux transfer within a core, is what reduces the efficiency of flux cores from maximum values of 2, or 4, down to values such as 1.75 or 3.47, typically.

Motor Apparatus

Simple Parallel Path Technology Demonstrator Motor



Fig. 7

Designed to demonstrate core principals, not provide over-unity

Although numerous practical applications abound for this effect, electric motor design remains the most outstanding opportunity. To this extent, again a few simple images, should be sufficient to explain how the basic flux switching apparatus, can be turned into a highly efficient electrical motor.

The first motor shown in Fig. 7 is one I have proposed to validate the flux switching effect at a most basic level. It illustrates the point made in the Flynn patent, that the armature of the core can be removed, and replaced with a motor flux path. This first motor is not claimed to be highly efficient, but it helps one to understand how the transition from simple flux core to motor takes place.



Fig. 8
Magnetic force is alternately switched from one leg to the other, imparting motion to the rotor sections

The next motor shown in Fig. 8 is again taken directly from the Flynn patent, and illustrates the next intermediate step to motor design. The fields of the permanent magnets are alternatively switched from one side of the surrounding flux cores to the other, alternately interacting with N and S poles on the rotor, imparting motion to the central rotor shaft.

With proper financial support, and the facilities to have metglas cores custom moulded, Joe Flynn was able to develop his final best art, shown in Fig. 9. No detailed performance numbers have been released for this motor, whose precise performance characteristics remain proprietary to Joe Flynn at this time. But the optimisation is so expert, it is stated to posses certain exotic properties, such as cool ambient operation, even during prolonged periods of continuous load. This 'cold running' is said to be of great interest to the American military, as it offers excellent stealth performance characteristics.



Fig. 9
Optimal Flux Core Motor Construction

Electrical Apparatus

Many readers will no doubt have noticed the similarity of the first illustration presented in this document, to the so called 'Tom Bearden MEG.' This is fair comment, and Joe Flynn has always highlighted this issue. However, it has been commonly stated Joe Flynn has simply developed mechanical apparatus, and the MEG with its electrical functionality, is distinct art, more advanced than the mechanical Flynn apparatus. However, this is shown not to be the case by a careful examination of the Flynn patent, in which the following is stated in the 'Power Conversion' section:

'The construction (shown in Fig.10 A) utilizes four control coils and a single permanent magnet and the construction (shown in 10 B) uses two control coils and two permanent magnets. The flux that would normally be supplied by a primary winding is supplied by the static flux of the permanent magnet or magnets and the control coils convert this static flux into a time varying flux in a novel way. Both arrangements use two secondary coils, the secondary coils are placed in the region of the continuous flux path that would be occupied by an armature or rotor in the linear or rotary arrangements. The regions of the flux paths that perform work are the same in all cases.'

'By alternating the polarity of the control coils during one cycle, one working region experiences an increasing flux and the opposite region experiences a decreasing flux and during the next cycle the opposite occurs. This results in the induction of a voltage in the secondary coils that is decided by the magnitude of the change in flux in the working region and the time in which this change occurs. The novelty of this discovery is that the primary flux inducing the voltage in the secondary coils is supplied by the permanent magnet or magnets and is far greater than the flux supplied by the control coils.'



Fig. 10

Fig.10 taken directly from the Flynn patent makes the point even clearer. As can be seen, the device illustrated is in all functional respects absolutely identical to the so called 'Tom Bearden MEG.' This identical prior art, therefore calls into question the intellectual property rights of Magnetic Energy LTD, as the same invention can not be patented more than once. Joe Flynn has also stated that his intellectual property rights will be robustly defended, by legal action if necessary, and he regards himself and his company as being in possession of exclusive rights to the so called 'MEG' unit.

the input and output circuits must be closed in series. The disclosure of this technique amounts to putting the basic MEG methodology fully into the public domain.

As regards replication of electrical output orientated flux core devices, certain important details need to be stated. For example grade 8 ceramic magnets should be used, so as to avoid flux saturation of the core. A basic error, many early experimenters wasted time on. The requirement for strong magnets to obtain over-unity results, is as much of a myth, as the idea new physics is required.

But perhaps the greatest trade secret of the electrical devices, one which several lengthy non disclosure agreements are required to be signed before it can be disclosed, is that the input and output circuits must be closed in series. The disclosure of this technique amounts to putting the basic MEG methodology fully into the public domain.

The reason for this circuitry requirement is obvious enough, with only a little analysis. If the output circuit is closed when the input circuit is activated, then the input energy simply leaks into the output circuit, as in an ordinary transformer. So no flux switching effect is manifested, and the field of the permanent magnet is static in time. Thus you have an ordinary transformer, with reduced efficiency, because of the core flux saturation effect provided by the permanent magnet.

This is one of the most important point to make about the Flynn apparatus. If you approach it as if it is a normal piece of scientific equipment, then proper optimisation is not greatly problematic. For example more turns on the output coils, simply means more voltage and less current, exactly as standard textbook equations predict. Generally, problems only occur, if you imagine the effect is based upon exotic scalar type or vacuum energy physics, when in fact it is ordinary flux manipulation within a core.

Present Status of the Flynn Project

Initially Joe Flynn was remarkably open about his work and research. However, since performing a working demonstration of various advanced hardware samples for the American Department of Defence, little has been heard.

I want to clearly emphasize I do not speak for Flynn research, nor am I in any way connected with Flynn research, and by consequence, have no inside information whatsoever as to the present status of the project. But we all sincerely hope, that the project has not been swallowed whole by the American deep black military industrial research complex.

However, even if this is the case, it does not mean the technology is lost. Extensive and generous details have been provided by Joe Flynn of his research, both in his patent deposition, website, and other comments, such as to enable persons of scientific training and skill, to replicate the effects stated.

While replication of the electrical effect remains extremely demanding, the mechanical apparatus is very easy both to understand and replicate. There is no reason why scientists and home tinkers together, can not build Flynn type flux core motors, and explore over-unity flux manipulation for themselves. The future has arrived, and it is simpler and cheaper than anyone imagined to be possible.

Raum&Zeit

EhlersVerlag GmbH,
Geltinger Str.14e,
82515 Wolfratshausen
Telephon: 08171/41 84-76,
Telefax: 08171/41 84-66
Internet:
http://www.raum-und-zeit.com

Institut fur Raum-Energie-Forschung (IREF) i.m. Leonard Euler

- Global Scaling Theory
- Gravitation theory
- Mathematic Biology
- Gravitation energetics
- Hydrogen-Helium Energetic
- Information technologies
- Telecommunication technologies
- Transport technologies

Flynn Research Company

http://www.flynnresearch.net



Photo 1

3.3" 1.2" stack height 1/2 hp weight 59 oz



Photo 2

Dynamometers, Power Analyzer etc.

Editor: Below we publish information and photos, represented on Flynn Research Company website (http://www.flynnresearch.net), and a description of the patent on methods for controlling the path of magnetic flux.

Flynn Research is dedicated to research focused on the novel application of permanent magnet and electromagnetic technology. Magnetism is a field that has potential for tremendous growth from both a science and application perspective. The researchers of Flynn Research Company believe that magnetism is one of the least understood and most misinterpreted of the natural forces, with the exception of gravity.

> ***Everything known about magnetism is based on "effect and relationships" without a clear understanding or provable definition of what is a line of magnetic flux.***

Even though much work has occurred in the advancement of magnetic materials, little advancement has occurred in the basic understanding of magnetism. The field of magnetism is based on both theory and 'myth' and is generally described as a 'phenomenon'.

We still do not know what a line of flux is and how it travels through space. We know flux "appears" to originate within a permanent magnetic material, forms a loop from one end to the opposite end of the magnetic material, appears to occur without a time constant, produces a force (attractive and repulsive) between other permanent magnets and "magnetically permeable materials and has a relationship to current flow. Everything known about magnetism is based on "effect and relationships" without a clear understanding or provable definition of what is a line of magnetic flux.

The research is based on the "magnetic force of attraction effect" that is related to magnetic flux by the number of lines of flux occupying a given area or flux density squared. The simple fact that if the number of lines of flux occupying a given area "doubles" the force of attraction becomes four

Photo 3

8" dia x 8" height motor presentation

Photo 5

Technology Discussion



Photo 4

8" X 8" motor testing



Photo 6

Parallel Path Test Apparatus

times greater. The basic model shows that with specific structures electromagnetism acting with permanent magnet materials can divide and multiply force in a manner that cannot be explained with conventional physics.

Rotary devices, linear devices, reciprocating devices and power conversion devices are now a patented product of this research. The goal of the Company is to commercialize their devices for use in an energy dependent world. Flynn Research is a research & development company and in cooperation with Magnetic Revolutions LLC licenses their technologies for use in the electric motor and power conversion industries.

The researchers do not construct their own test equipment nor write capture and data evaluation programs but use industry / scientific accepted products. Close to $1.5 million has been expended developing, protecting and evaluating the technology. Many fine minds have been involved in the development and evaluation of the technology. Many presentations have been given both to motor companies and academic groups. The prototypes have all been professionally built, which include a 1/2 hp 3.3" dia 1.2" stack height, the assembled motor weighs 59 oz and a motor 8" dia with a stack height of 8" currently undergoing testing.

United States Patent No. 6,246,561
June 12, 2001

Methods for controlling the path of magnetic flux from a permanent magnet and devices incorporating the same

Inventors: **Flynn; Charles J.** (Greenwood, MO)
Assignee: **Magnetic Revolutions Limited, L.L.C** (St. Louis, MO)
Appl. No.: **127056**
Filed: **July 31, 1998**











A permanent magnet device includes a permanent magnet having north and south pole faces with a first pole piece positioned adjacent one pole face thereof and a second pole piece positioned adjacent the other pole face thereof so as to create at least two potential magnetic flux paths. A first control coil is positioned along one flux path and a second control coil is positioned along the other flux path, each coil being connected to a control circuit for controlling the energization thereof. The control coils may be energized in a variety of ways to achieved desirable motive and static devices, including linear reciprocating devices, linear motion devices, rotary motion devices and power conversion.

Editorial: The principle of designing of the device (two counter parts of the flux are used) resembles Φ-machine or Gramm's generator. Read in this issue more details on these devices.

Flux-machine And Its Analogues

Review prepared by correspondent **Alla Pashova,** Russia

Flux-machine (or Φ-machine, since configuration of its field resembles the Russian letter "Φ") was designed by Alexander V. Frolov during the first half of 1990s. Φ-machine description was published more than once on the pages of scientific periodicals (1994, Institute of New Energy, Newsletter, June 1994, p.9.; 2002, New Energy Technologies, 2002, p.3), and it is well known to many researchers concerning themselves with such kinds of engineering.

Let us consider the arrangement of Φ-machine; see Fig. 1 (first published in 1994). A report was presented at the conference «New ideas in natural science», 1996 in Saint Petersburg (see photo in Fig. 1). The primary coil is mounted in the center of generator; two secondary ones are diametrically wound on a ring core. An air gap between ring and central magnetic circuits are of particular importance. **Two magnetic fluxes from two coils are balanced, and, thereby, there is no reaction in the primary circuit.**







Fig.1
See also Fig. 7, p.29 – the analogy is evident

The device bears some similarity to the Gramm's generator (Zenob Theophyl Gramm, 1826-1901, Belgium-France, took out a patent for an electric ring-rotor generator in 1869). In Gramm's generator (Fig. 2) the ring rotor with a toroidal winding rotates. The toroidal winding touches two diametrically located conducting brushes. It turns out that in the ring of the rotor all winds of one rotor half create a field which is directed towards a field created by the other rotor half.



Fig. 2

An example of analogous device is represented in Fig. 3 (information is from the website: http://www.skif.biz/energy/arhiv1-6.shtml), and also in Fig. 4 (we have written about this invention in New Energy Technologies, Issue #5 (8), 2002, article by V.I. Boryak, Email: spin@i.com.ua).



Fig. 3



Fig. 4

In August 1999, according to Stephen Hartman (Hartman Multimedia Service, Email: hart@harti.com, info@ccard.net), a German research team designed a toroidal generator. As stated by the researchers, it obtained more than 1.200 W by load while efficiency exceeded 100%!

This subject has become very popular among different researchers. Fig. 5 illustrates a design with a magnet rotating in the center (designer - Olaf Berens, Email: olaf.berens@prognost.com).



Fig. 5

One more example from the USA: in February, 2003 Donald Hofmann (USA) filed an application for patenting "Generators and transformers with toroidally wound stator winding». Below we publish the description of the patent.



Fig. 6

Inventors: **Steven L. Sullivan, USA; David L. Goulet, USA; Donald Hofmann ,USA.**

Electrical generators are provided with toroidally wound stator windings electrically connected in series; a high permeability stator core, preferably an amorphous magnetic alloy material, glassy metal or HYPERCO™ 50 laminations; and a rotor. The toroidally wound stator coils and the stator core trap essentially all of the flux fields generated by the stator coils within the stator core. Since there is essentially no magnetic field leaving the stator, there is essentially no flux field interaction with the field generated by the rotor. The reduction of flux field interaction also reduces counter torque.

According to another embodiment of the invention, open positions of a rotor may be filled with magnetic material, preferably iron. Filling open portions of the rotor may assist in reducing undesirable flux leakage from the rotor. By trapping substantially all of the flux within the rotor, interaction between rotor and stator flux is reduced. In this manner, counter torque is reduced thereby increasing the overall efficiency of the device.

A prototype of this embodiment was constructed using a standard 10 kWtt gas-powered generator. The stator was removed from the generator and its housing. The stator windings were removed from the stator and rewound by hand using a No. 10 size copper wire with 180 winds wrapped in a toroidal fashion around approximately 180 degrees of the stator. The stator was then reinstalled in the modified housing and re-attached to the gas-powered generator. A standard 12 volt car battery was attached to the input of the rotor. A 12.92 volt input with 0.8 Amps was measured as the input to the rotor. The output was measured as 6.5 volts with a 40 Amp output. A series of input and output measurements were taken for various inputs.

Editor: Thus input power is 10 Wt, and output power is 260 Wt.

So, the old well-known ideas have found new ways of embodiment, though their essence remains unchanged. Let us note that Faraday Labs Ltd has been working on creating a prototype of ▯-machine with a toroid of 200 mm in diameter.

Please, read more about this in the next issue!

Editorial: We publish the specification of several interesting patents, which were taken out by Russian inventors for recent years.

Russian patents on alternative energetics

- №93001754, 1996.06.27, Converter of gravitational forces into energy, V.V. Mironov and others
- №92008720, 1995.02.10, Slavic method to produce energy by conversion of gravitational forces, V.V. Mironov
- №93006696, 1995.04.30, Supporting converter of gravitational forces into energy, V.V. Mironov
- №2001121071, 2003.04.10, Method to create energy in liquid, heat-generator and heat-and-power device, A.Yu. Baurov and others
- №2132109, 1999.06.20, Generator of mechanical energy, A.Yu. Baurov and others
- №2001125794, 2003.05.10, Generator of static electricity, S.I. Danilov
- №2001120796, 2003.04.10, Electric power device, D.M. Beliy
- №98116077, 2000.05.10, Heat engine (monotherm, "perpetual mobile of second-type"), V.I. Likhachov and others
- №93048971, 1996.04.20, Float engine, I.P. Tchinarev
- №94023174, 1996.03.27, Gravitational-hydrostatic engine, I.P. Tchinarev
- №98112650, 2000.03.20, Water engine, V.A. Gylchuk
- №2001115953, 2003.03.20, Potential engine by Prokopenko, V.F. Prokopenko
- №2001115954, 2003.03.20, Potential amplifier by Prokopenko, V.F. Prokopenko
- №2001124364, 2003.04.20, Drum of gravitation (gravity), I.A. Strelnikov
- №95107181, 1997.02.20, Method to convert energy of physical vacuum into energy of physical space, O.K. Polev and others
- №92008695, 1995.04.20, Method to get overunity efficiency, Yu.V. Karasev and others
- №93006851, 1995.04.30, Principle, method and device for circulation of mass by force of gravitation and inertia, G.S. Kirichenko
- №93039885, 1996.05.20, Hydro-gravitational electric power station, L.S. Konkov
- №93036371, 1995.11.27, Method to convert energy created in result of interaction of earth's gravity force and air bearing capacity into electric energy, V.I. Kovalenko
- №93025690, 1996.07.27, Method and device to convert heat energy into mechanical one, A.I. Lendyaev
- №2001122885, 2003.04.20, Rotary method to convert magnetic energy into mechanical one, L.N. Mezentsev
- №2001106783, 2003.02.10, Gravitational source of energy, A.D. Yurik and others
- №2001115968, 2003.03.20, Method to convert energy, V.S. Gorelyuh

According to another embodiment of the invention, open positions of a rotor may be filled with magnetic material, preferably iron. Filling open portions of the rotor may assist in reducing undesirable flux leakage from the rotor. By trapping substantially all of the flux within the rotor, interaction between rotor and stator flux is reduced. In this manner, counter torque is reduced thereby increasing the overall efficiency of the device.

A prototype of this embodiment was constructed using a standard 10 kWtt gas-powered generator. The stator was removed from the generator and its housing. The stator windings were removed from the stator and rewound by hand using a No. 10 size copper wire with 180 winds wrapped in a toroidal fashion around approximately 180 degrees of the stator. The stator was then reinstalled in the modified housing and re-attached to the gas-powered generator. A standard 12 volt car battery was attached to the input of the rotor. A 12.92 volt input with 0.8 Amps was measured as the input to the rotor. The output was measured as 6.5 volts with a 40 Amp output. A series of input and output measurements were taken for various inputs.

Editor: Thus input power is 10 Wt, and output power is 260 Wt.

So, the old well-known ideas have found new ways of embodiment, though their essence remains unchanged. Let us note that Faraday Labs Ltd has been working on creating a prototype of Φ-machine with a toroid of 200 mm in diameter.

Please, read more about this in the next issue!

◆

Editorial: We publish the specification of several interesting patents, which were taken out by Russian inventors for recent years.

Russian patents on alternative energetics

- №93001754, 1996.06.27, Converter of gravitational forces into energy, V.V. Mironov and others
- №92008720, 1995.02.10, Slavic method to produce energy by conversion of gravitational forces, V.V. Mironov
- №93006696, 1995.04.30, Supporting converter of gravitational forces into energy, V.V. Mironov
- №2001121071, 2003.04.10, Method to create energy in liquid, heat-generator and heat-and-power device, A.Yu. Baurov and others
- №2132109, 1999.06.20, Generator of mechanical energy, A.Yu. Baurov and others
- №2001125794, 2003.05.10, Generator of static electricity, S.I. Danilov
- №2001120796, 2003.04.10, Electric power device, D.M. Beliy
- №98116077, 2000.05.10, Heat engine (monotherm, “perpetual mobile of second-type”), V.I. Likhachov and others
- №93048971, 1996.04.20, Float engine, I.P. Tchinarev
- №94023174, 1996.03.27, Gravitational-hydrostatic engine, I.P. Tchinarev
- №98112650, 2000.03.20, Water engine, V.A. Gylchuk
- №2001115953, 2003.03.20, Potential engine by Prokopenko, V.F. Prokopenko
- №2001115954, 2003.03.20, Potential amplifier by Prokopenko, V.F. Prokopenko
- №2001124364, 2003.04.20, Drum of gravitation (gravity), I.A. Strelnikov
- №95107181, 1997.02.20, Method to convert energy of physical vacuum into energy of physical space, O.K. Polev and others
- №92008695, 1995.04.20, Method to get overunity efficiency, Yu.V. Karasev and others
- №93006851, 1995.04.30, Principle, method and device for circulation of mass by force of gravitation and inertia, G.S. Kirichenko
- №93039885, 1996.05.20, Hydro-gravitational electric power station, L.S. Konkov
- №93036371, 1995.11.27, Method to convert energy created in result of interaction of earth’s gravity force and air bearing capacity into electric energy, V.I. Kovalenko
- №93025690, 1996.07.27, Method and device to convert heat energy into mechanical one, A.I. Lendyaev
- №2001122885, 2003.04.20, Rotary method to convert magnetic energy into mechanical one, L.N. Mezentsev
- №2001106783, 2003.02.10, Gravitational source of energy, A.D. Yurik and others
- №2001115968, 2003.03.20, Method to convert energy, V.S. Gorelyuh

- №2002131190, 2003.04.20, Method to convert heat energy into useful work, G.R. Umarov and others
- №2001122676, 2003.05.27, Device to get energy by conversion of energy from one state to another, T.A. Trushina and others
- №2131636, 1999.06.10, Fuel-less engine, V.E. Alekseenko
- №5037775, 1996.10.10, Magnetic engine, V.E. Alekseenko
- №94003087, 1995.12.27, Gravitational engine, A.A. Voznyukov
- №93058095, 1996.06.27, Perpetual mobile, Yu.S. Parshutin
- №93056706, 1996.07.27, Perpetual mobile, A.V. Remezovich
- №93039002, 1996.01.20, Gas-dynamic perpetual mobile, A.I. Lendyaev
- №94011000, 1995.11.27, Perpetual mobile by Makagyan, V.S. Makagyan
- №97114829, 1999.06.27, Perpetual mobile by Makagyan, V.S. Makagyan
- №95114965, 1997.08.10, Electric perpetual mobile by Abrakitov, V.E. Abrakitov
- №9512209, 1998.02.20, Perpetual mobile, V.V. Sharov
- №99111572, 1999.09.27, Perpetual mobile, N.M. Rotar
- №98116343, 2000.05.10, Engine-electric saw (perpetual mobile), V.V. Smirnov
- №2000101256, 2001.11.20, Perpetual mobile, V.D. Rykov
- №2000120592, 2002.07.20, Perpetual mobile, K.I. Harazov
- №2001117783, 2003.03.20, Magnetic perpetual mobile, S.N. Verevkin
- №2001123502, 2003.04.20, Magnetic engine, A.E. Ryumin
- №5032711, 1995.02.20, Ferromagnetic engine, V.P. Levkin
- №94019782, 1996.01.10, Device for demonstration of conversion of permanent magnet energy, M.F. Ostrikov and others
- №95103846, 1996.11.27, Magnetic generator, M.F. Ostrikov and others
- №95112010, 1997.06.27, Method to convert permanent magnet energy into rotary motion, A.V. Starostin and others
- №2143170, 1999.12.20, Method to convert energy of mechanical loading into energy of repeated transference, V.I. Rahovsky and others
- №2000119415, 2002.06.20, Method to convert energy of fields of permanent magnets into mechanical work, Yu.S. Pilipkov
- №2001109811, 2003.02.27, Method to capture and convert energy of physical vacuum into electric energy, S.N. Kovalev
- №99121374, 2001.11.10, Perpetual mobile, E.M. Volodin
- №94026259, 1996.05.20, Device to convert magnetic field energy into kinetic energy, P. Imrish


PATENT OFFICE
Really "free energy"?
What about a latent battery?

Device for conversion of magnetic field energy into kinetic energy

No. 94026259, 1996.05.20

Author: Pavel Imrish

The invention refers to a device for conversion of magnetic field energy into kinetic energy. The device has a rotating wheel with at least two radially opposing non-magnet holders used as guide ways for at least two permanent magnets, respectively. The permanent magnets are mounted in the holders so that there is a possibility to remove them. From the both sides of the wheel plates made of magnetic material are mounted axially; the plates surround the wheel partially. Depending on direction of the both poles, namely on location of the similar and opposite poles towards each other, compression element is situated on the holders, or between the wheel and the outer end of the permanent magnet located at the furthest radial distance from the axle of the wheel, or between two permanent magnets. (The device operation principle is obvious from Fig. 1).



Fig. 1

Editor: We have found an example of a similar device whose description is presented in the book by R.Ford The Perpetual Motion mystery [1].

In this case, there is an analogous process, during which half of the cycle is screened and the rotor is supposed to rotate permanently (see Fig. 2).

1. R.A. Ford, The Perpetual Motion mystery. Lost Technology Series, p.23.



Fig. 2

Gravity spaceships

Review on Grigory R. Uspenskiy's works, Russia

http://space21.boom.ru/gravity.htm

The level of development of modern astronautics is primarily determined by the energy capabilities of space carriers. So, nowadays, the single-mission carrier rockets equipped with chemical engines allow space exploration within the solar system. These carriers have delimited the near-earth space in the form of a geostationary orbit, where the practical-purpose space complexes operate.

Newer and higher levels of quality will be reached by cosmonautics upon its mastering gravity power engineering. Flights towards the nearest stars will become possible and by the end of the next century this will be followed by travels throughout Galaxy.

Gravity engines are structurally simple (**two bodies of different density are rigidly connected**). To form some practicably significant value of thrust it is required to use absolutely new technology regarding creation and retaining of matter of high density which can be compared to that of atomic nuclei. For instance, at an engine mass of about 2 t, it is possible to attain 10 N thrust using bunches of aluminum and lead nuclei. The nuclei are approached to each other at a distance comparable with sizes of these bunches.



Fig. 1

Use of matter which is denser than nuclei bunch, increase of mass of the gravitating bodies, and reduction of the distance between the bodies causes increase of thrust. So, for a level of density of gravity holes (i.e. for extremely dense state of matter in which it is not attracted by other bodies) limit value of acceleration of the gravity engine reaches the order of 10^{100} ms^{-2}.

In engineering, we usually use units of distance as meters, centimeters, millimeters, and microns. Let us consider one of them – millimeters. With such a size of the gravitating bodies and distance between them, it is possible to obtain substantial thrust forces of the gravity engine and, accordingly, accelerations of its motion.

So, using an engine of 20 ton mass we will get the thrust of 2x10^4 N, with mass of 200 ton we will get the thrust of 2x10^6 N, and so on. Thus, by increasing the engine mass by one order of magnitude, we obtain increase of thrust by two orders, while sizes of the bodies remain unchanged. But acceleration, in this occasion, remains constant and equal to approximately 1 m/s^2.

Decrease in size of gravitating bodies of the engine leads to the corresponding increase of thrust by an order. Decrease of size is realized by increase of density of these bodies by 3 times up to 0.3 mm at the same masses. The acceleration they produce is increased by an order as well, i.e. up to 10 m/s^2. Decrease of sizes of the gravitating bodies and the distance between them down to 0.1 mm results in further increase of engine thrust by one more order and also increase of acceleration up to 100 m/s^2. If size of the bodies is 1 micron then acceleration increases up to 10^6 m/s^2.

It is apparent that even with up-to-date technological possibilities of miniaturization the gravity engine with masses of dozens and hundreds of tons is capable to create great thrust forces and form accelerations considerable enough to fly across the Galaxy. Therefore, the problem of creating a gravity engine is, mainly, the problem of producing and retaining the high-density matter. It will be possible after studying the mechanism of interaction between matter & gravitational substance followed by developing techniques for synthesizing of high-density, large-mass, and small-size substance from this matter.

It is possible to control the value of thrust of the gravity engine changing the distance between gravitating bodies. Thrust direction can be changed by turning the rigid connection of the gravitating bodies. The engine can be activated by bringing the gravitating masses together, and switching-off by moving them apart.

In a 24-hour period, such a ship can reach a speed of 10^6 m/s and cover a distance of about 10^{10} m. In a month, with a top speed of 3x 10^7 m/s the ship will cover the distance of 10^{13} m; in a year, with a speed of 4x 10^8 m/s the ship will cover a distance of 10^{15} m; in 10 years - 4x 10^9 m/s and 10^{17} m, respectively. Apparently, the ship with sufficient over-load can be used for flights within the solar system and for manned flights towards the nearest stars.

When transporting unbreakable and non-urgent cargoes, the acceleration can be increased up to a few dozens of unities. The flight duration might be also increased by several tens of years. This extends the area of utilizing the gravity ships with over-loads of several unities. Besides these ships can be used for transporting operations within near vicinities of the Galaxy.

The high-speed flight will demand protection against approach flow of matter. So, per second (with a ship speed of 10^{10} m/s) 10^{-12}kg of matter will approach the ship. At that density of interstellar material is 10^{-24} kg/m^3 and midship area is 10^2 m^2.

The great speed of approaching matter will create a substantial resisting force. At a speed of 10^{10} m/s, this force will come to the order of 10^{-2} N, whereas with a speed of 10^{18} m/s it will come to 10^{14} N. This is a great value, but as compared to thrust of such a ship which is to equal to 10^{17} N, the former value is a small one. That is why it is possible to overcome such resisting force.

Intercommunication with these ships might be, most likely, realizable by means of distortion of gravitational field. It is possible that the gravitational field distortion will be formed, on the contrary, by generating the matter from the gravitational field, and, most probably, by a method as yet unknown.

New books and DVD

Monograph **"General Etherodynamics. Modeling of matter structures and fields on the basis of conception of gas-like aether" by Vladimir A. Atsukovsky.** 2nd edition, M., Energoatomizdat, 2003;
Brochure **"12 experiments on etherodynamics**" Zhukovsky, Publisher "Petit", 2003.

On questions about purchasing, please, refer to Email: atsuk@dart.ru

◆

Floyd Sweet Bench Test DVD

In order to demonstrate the reality of tapping free energy from the vacuum, we have now made available a very reasonably priced DVD of the bench tests of the late Floyd Sweet's Vacuum Triode Amplifier, with commentary by Tom Bearden.

During these two tests, the unit, which weighed about 6 lbs., can be seen to be putting out well over a million times more power than was put into it.

This DVD makes an excellent educational or instructional tool, and is priced at USD 9 including US domestic shipment. Running time is about 20 minutes.

Note: the full length Sweet DVD, which includes Sweet's proprietary conditioning process for the magnets, is also still available.

Order from http://www.cheniere.org/sales/order_by_credit_card.htm

On Velocity of Drive-Free Motion

S.A. Gerasimov , V.V. Stashenko, Russia

Physics Department, Rostov-on-Don State University,
Zorge St. 5, 344090, Rostov-on-Don, Russia

***Editorial:** We publish a summary of the article. The original text you can receive from the authors.*

A drive-free system made on the basis of a planar mechanism is described. The experimental results on average velocities of the drive-free propulsive system are presented in a scaled view.

During usual motion, a system is repealed from the surface in the case of its motion on a plane or from the medium when it moves in a resistance medium. This kind of motion is achieved by using a drive mechanism. In contrast to the usual motion, the drive-free propulsive system moves due to interaction of a body of a system with another body of the same system. Sometimes such machines are called inertioids [1] or vibration propulsive devices [2]. To produce such kind of motion it is sufficient to provide anisotropy of the resistance force [3-5] or asymmetry of the internal force [6]. One of the simplest ways to do it is to use a simple two-link planar mechanism. A device for such a motion is shown in Fig. 1.



Fig. 1

Experimental device

This device with a total mass of M+m consists of a platform P on which an electric motor E rotating a drive rod R of length r is mounted. This is only one part of the planar mechanism. Another link is the connecting rod C of length c which connects the unbalanced load L and the drive rod R by means of two bell bearings B. The unbalanced load L of mass m on the rod I slides in guide G. The basic distinction of this mechanism is in that this variant of drive-free machine allows us to analyze the experimental data on average velocities of motion. Actually the only forces, which act on the platform and are collinear to the moving direction, are the force **F** caused by vibrations of the load L and the frictional force $\mathbf{F}_f$. The platform starts to move when the force acting on the platform becomes greater than the frictional force.

Let us discuss possibilities of the real propulsive system shown in Fig. 1. Measurements were made at r=0.01 m and at three mass ratios m/M. The values of frictional coefficients were measured for each parameter of the system and vary from k=0.25 to k=0.4. The system starts moving when theoretically the drift does not take place. When motion becomes reversible, the velocity of drive-free drift does not decrease.

Thus drive-free motion is possible even if the frictional coefficients are very small. When increasing the frequency of vibrations velocity does not decrease. We can not discuss the existence of some third force acting on the platform (we can suggest the existence of frictional force $\mathbf{F}_f$ and the internal force **F** caused by vibrations). Let somebody else take the liberty of making such a conclusion!

References

1. Tolchin V.N. Inertioid. // Perm: Perm Book Publisher. 1977. Blekhman I.I. Vibrational Motion. // Moscow: Nauka. 2000. Nappo F. Sulla Influenza Indiretta Delle Forze Inertne sul Moto del Baricentro. // La Ricerca Scientifica (Rendiconti). 1965. V. 8. No 1. P. 3-14.
2. Gerasimov S.A. Anisotropy of Frictional Force and Vibrational Motion. // Problems of Applied Physics. 2001. V 7. P. 85-88.
3. Gerasimov S.A. Self-Similarity of Vibrational Motion in a Resistant Medium. // Journal of Applied Mechanics and Technical Physics. 2002. V. 43. No 1. P. 90-92.
4. Gerasimov S.A. A Real Model of Vibratory-Impact Propulsive Device. // Problems of Applied Physics. 2000. V 6. P. 117-118.
5. Langhaar H. L. Dimensional Analysis and Theory of Models. // New York: Willey. 1951.

ELECTROMAGNETIC SELF-ACTION

S.A. Gerasimov, A.V. Volos, Russia

Physics Department, Rostov-on-Don State University,
Zorge St. 5, 344090, Rostov-on-Don, Russia

The torque of a self-action exerting on the mobile part of the reactionless engine is measured. It is shown that there exists a value of the height of the mobile electrode at which the torque of self-action is maximal.

There is an opinion that a body can not act on itself [1]. The existence of the so-called force of self-action is believed to contradict to the law of conservation of momentum. This is nothing but prejudice. Though the experimental confirmations of existence of self-action [2-4], conventional science is ready to refuse modern electrodynamics and make up a new theory of electromagnetism [1, 5] in order to save Newton's third law in use. It is comprehensible. First of all, these are the theoretical [5] and experimental [3] errors. The equivalence [5] of the Biot-Savart force is mathematically coarse since in this case the highest terms of expansion of force of self-action are cast out. This equivalence violates law of action and reaction and Ampere force law for which the principle of equality and collinearity of action and reaction forces is valid. Non-linearity of dependence of the torque of self-action on the current intensity [3] makes us doubt in the validity of these results. Moreover, typical values of force [2, 4] and torque [3, 6] are too small even if direct current in the circuit is significant. It is required to pass through the direct current of hundred amperes to produce the considerable displacement or turn of a body. As a result, small values of the effect caused ambiguity in the explanation of the phenomenon [1].

In fact, searching the reactionless propulsive devices we usually forget about the magnetic self-action which arises when a body consisting of a magnet and incomplete electric circuit can move violating law of action and reaction [7]. This violation is proved theoretically [8] but peculiarities of this motion are not well discussed. The principle of such a motion is shown in Fig. 1. This is the magnetic interaction between two current elements one of which is a part of a closed circular loop ***L*** and another is perpendicular to the first one. Since the force $d\mathbf{F}_{jm}$ acting on any current element of the loop ***L*** is perpendicular to the density of current $\mathbf{j}_m$ then the **Z**-component of the torque $d\mathbf{N}_m = [\mathbf{r}_m x d\mathbf{F}_{jm}]$ is equal to zero while torque which exerted on the second current element by the magnetic field of the loop, does not.



Fig. 1

Violation of law of action and reaction.
The force $d\mathbf{F}_{jm}$ with which the magnetic field $\mathbf{B}_j$ of another current element acts on the current of density $\mathbf{j}_m$, is not equal nor opposite to the force $d\mathbf{F}$ with which the magnetic field **B** of the first current element acts on the current of density **j**.

An experimental device is shown in Fig. 2. A commercially available ring-shaped carbon-steel magnet ***M*** (inner radius – 20 mm; outer radius – 55 mm, height – 25 mm) of $2.2x10^5$ A/m magnetization is located on the cover of a cylindrical electrode ***E*** suspended by thread ***T***. The electrode ***E*** is furnished with a central electrode ***C*** of the same height ***h*** and 5 mm diameter. The radius of the electrode ***E*** is 130 mm. The open end of electrode ***E*** and the central electrode ***C*** are submersed in a conducting liquid L_+ and L_- placed in two volumes of a vessel ***V*** so that the depth of submergence of these parts is about 5 mm. In this experiment the conducting fluid is 10% solution of copper sulfate ($CuSO_45H_2O$). The vessel ***V*** consists of two thin coaxial plastic cylinders of 2 mm thickness. The radii of the plastic cylinders having the common bottom are equal to 10.5 cm and 18 cm. The height of the vessel is 12.5 cm. A disk and a ring-shaped electrodes S_+ and S_- of 1.5 mm thickness are placed on the bottom of the vessel to supply the direct electric current of intensity *I*. All conducting parts of the device are made of copper. The thickness of the electrode ***E*** is 1.5 mm.

When the direct current ***I*** of density **j** flows through the electric circuit, the magnet and the electrode ***E*** rotate in the direction of the magnetic force ***d*F** which is proportional to the vector product [**j**x**B**] as shown in Fig. 2. This is a force of self-action by means of which the mobile part of this device consisting of the magnet ***M*** and the electrode ***E*** acts on itself. However there is no force of reaction which could cause such a rotation. This is really true since a ring-shaped magnet is equivalent to two cylindrical surfaces with the surface current of density $\mathbf{j}_m$. The force of self-action ***d*F** acting on the cover of the electrode is compensated by the force of self-action $d\mathbf{F}_*$ acting on the cylindrical part of the electrode ***E***. Magnetic induction field $\mathbf{B}_*$ "does its part" as shown in Fig. 2. Therefore, it would be appropriate to find out how the height of the electrode ***E*** influences the value of the torque **N**. Such an influence is demonstrated in Fig. 3.



Fig. 2
Experimental device
(•) and (x) – directions of magnetic forces acting on various parts of the mobile electrode ***E***



Fig. 3
Dependence of the torque ***N*** on the height of the electrode ***h*** at various values of the direct current ***I*** in the circuit

Thus there exists the value of the height ***h*** at which torque of self-action is maximal. This is the first result of the present work. At ***I***= 1 A and ***h***= 2 cm the electrode ***E*** turns at angle of 2.2 radian (126 °) with respect to the equilibrium position. Such a turn corresponds to $3.4\text{x}10^2$ gxcm²/s²rad, i.e to the constant of torsion of the thread. The second result is that the maximum value of the torque of self-action ***N*** at the current ***I***= 1 A is even larger than the value of the torque produced by the traditional unipolar device [3] at the current 50 A.

In fact, this work represents an attempt to draw attention to a more effective and simple practical application of the self-action. It remains only to transfer electric current in an unclosed electrical conductor and such a possibility really exists.

References

1. Graneau N. The Finite Size of the Metallic Current Element. // Physics Letters A. 1990. V. 147. N. 2-3. P. 92-95.
2. Sigalov R.G., Shapovalova T.I., Karimov H.H., Samsonov N.I. Magnetic Fields and Their New Applications. // Moscow: Nauka. 1976.
3. Das Gupta A.K. Unipolar Machines. Association of the Magnetic Field with the Field-Producing Magnet. // American Journal of Physics. 1963. V. 31. N 6. P. 428-430.
4. Cavalleri G., Bettoni G., Tonni E., Spavieri G. Experimental Proof of Standard Electrodynamics by Measuring the Self-Force on a Part of a Current Loop. // Physical Review E. 1998. V. 58. N 2. P. 2505-2517.
5. Christodoulides C. Equivalence of the Ampere and Biot-Savart Force Law in Magnetostatics. // Journal of Physics A. 1987. V. 20. N 8. P. 2037-2042.
6. Serra-Valls A., Gago-Bousquet G. Conducting Spiral as an Acyclic or Unipolar Machine. // American Journal of Physics. 1970. V. 38. N 11. P. 1273-1276.
7. Gerasimov S.A., Volos A.V. On Motion of Magnet in Conducting Fluid. // Problems of Applied Physics. 2001. V. 7. P. 26-27.
8. Gerasimov S.A. Self-Interaction and Vector Potential in Magnetostatics. // Physica Scripta. 1997. V. 56. N 3-4. P. 462-464.

JNET

New Energy Technologies
collection of articles
Japanese Version

Collection of articles from New Energy Technologies magazine, 2001-2002 is published in Japan.

On purchasing of the book, please, contact

Eiichi Yamamoto,
President Yama Trans Co. Ltd.

Email: admin@yamatrans.co.jp or
eyama@yamatrans.co.jp

Uranium Photoaccumulator

Anton N. Yegorov, Russia

St.Petersburg Institute of Nuclear Physics, Russian Academy of Sciences, Gatchina, 188350, Leningrad region, Russia
http://www.pnpi.spb.ru, Email: bti@isppd.pnpi.nw.ru

Photoaccumulators are galvanic elements consisting of two communicating vessels, one of which is exposed to light and another is kept in darkness. Ionic composition of electrolyte, which fills these vessels, depends on intensity of illumination. If an inexpensive electrode is placed in each vessel, then a potential difference will appear. If the electrodes are closed at external working resistance the electron stream will begin to equalize ionic composition and the difference in illumination intensity will tend to disbalance it. As a result, a certain working mode will be established which will allow to utilize the photoaccumulator for production of industrial electrical energy. As distinct from the solar battery, which works while exposed to the light, the photoaccumulator stores some part of solar energy in its electrolyte which is supplied with electrical energy after sunset too.

The idea of photoaccumulator is not a new one. It was established in the end of 19th century that it is feasible to create a photoaccumulator containing electrolyte made of the following mixture: $Fe^{2+} + Hg^{2+} = Fe^{3+} + Hg^{+}$.

This photoaccumulator was not adopted in practice because of high toxicity of the electrolyte and very low EMF (approximately 0.018). Development of technology is accompanied by a widening range of materials and matters which can be used in large scale production and power industry. Among such materials are, in particular, titanium, depleted uranium and rare-earth elements. Nuclear power industry uses U235 isotope only. Naturally occurring compound contains only 0.72% of U235. Hundreds of thousands of U238 from which U235 has been extracted are kept as useless stock.

In the end of sixties in one of radiochemical laboratories of LINP (Leningrad Institute of Nuclear Physics) P.N. Moskalyov repeated the same experiment over a long period of time. In the morning he placed a tightly closed retort filled with uranyl-chloride soluted in compound of water, spirit and hydrochloric acid on the window-sill. The solution in the retort changed its color from yellow to emerald-green. Before leaving the laboratory Moskalyov removed the retort with green solution from the windowsill to a closed chest. In the morning Moskalyov retrieved the retort with the solution (which was already yellow) from the chest and placed it on the sill. The solution became green again and the whole process repeated daily.

Chemical processes in uranium electrolyte are rather complicated: first, under the light influence the uranyl ion oxidizes ethyl alcohol, which is then transformed to aldehyde: $UO_2^{+2} + C_2H_5OH^+ = U^{iv} (OH)_2 + C_2H_4O$.

In the dark ions of urany-4 interact with aldehyde and are transformed to UO_2 uranyl ion and spirit again. Thus, **this cyclic process can take place over a significant period of time being supported by the energy provided by light quanta of visible light which are transformed into the heat.**

The idea of utilizing this process in order to obtain electrical energy emerged in the late nineties. The mechanism of uranium photoaccumulator is very simple (Fig. 1): two glass vessels, one made of transparent glass and another of non-transparent glass, are connected with a black acid-proof rubber tube. The communicating vessels are filled with aqueous electrolyte containing 40% of spirit, 80-100 g/l UO_2Cl_2 and 0.2 m HCL. The electrolyte is previously activated by multiple cycles of exposing it to light and then placing it in darkness in order to obtain a significant volume of aldehydic fraction. The major difficulty of designing uranium photoaccumulator is connected with the choice of the material for electrodes. In galvanic elements carbonized platinum electrodes are usually used. For practical use platinized titanium gives the best fit. Titanium foil covered with superfine layer of platinum is currently widely used in electrochemical industry and is procurable.



In the transparent vessel the titanium petal-shaped electrodes are parallel the light flow, so the light quanta move freely through the solution.

In working condition each photoaccumulator produces 10 mA of current at 0.3 volt voltage, so they are to be connected in large batteries, both in series and in parallel.

It is also necessary to consider the aspect of safety. Until now, the depleted uranium has been used for one purpose only, namely, for manufacturing of cores for armor-piercing shells. When used in this manner, the uranium is pulverized, which leads to environmental damage. The battery of photoaccumulators is placed in hermetic metal chest; the front panel of the latter must be made of solid safety glass. Such a system will protect the photoaccumulator battery from malicious intent and the security staff from weak uranium radioactivity.

International Prize on Power Engineering "GLOBAL ENERGY"



Zhores I. Alferov

International Prize "Global Energy" was first presented in St. Petersburg on June 15, 2003. The bonus fund of $900,000 was shared between three scientists "whose work has been and is still important both to the last century and future research", said Zhores Alferov, Chairman of the Global Energy Prize Award International Committee.

Nick Holonyak, Professor at the University of Illinois (USA), was awarded for "fundamental contributions to the development of power silicon electronics and invention of the first semi-conducting light-emitting diodes in a visible part of the spectrum". Thyristor invented by Holonyak allows the transformation of direct current into alternating and vice versa, to direct this process, to store and accumulate energy. This device is used for every electric locomotive, for frequency transformation. Such devices help to save significant amounts of energy, thus, about 30 percent of all energy produced in the world is processed through thyristors.

Nick Holonyak's other invention, i.e. semi-conducting light-emitting diodes in a visible part of the spectrum, has led to development of a new field of the modern power engineering. Supposedly, efficient and safe light-emitting diodes will replace daylight lamps in the next ten years.

"Although Nick Holonyak's invention dates back to the end of the 50ies of the last century, it remains current" said the Chairman of Expert Commission, Academician Vladimir Fortov. "This is one of the key inventions leading to the search of new ways of sustainable energy saving".


Глобальная Энергия

Диплом

Diploma of Global Energy Prize laureate

Gennady Mesyats, Academician of Russian Academy of Sciences, and **Ian Douglas Smith**, Senior Scientist at The Titan Pulse Science Division, were awarded for giving birth to a new direction in the field of power engineering, i.e. power pulse energy. Due to their research, commutation of high-level currents at megavatt levels of voltage has become possible; a number of powerful current choppers have been created, futhermore, there have been developed transformer constructions which allow avoiding energy loss in power transmission lines. These research and innovations resulted in the creation of a number of unique pulse power machines and devices widely used in Russia and abroad ("Aurora", "Helia" (USA), "Sinus", "Gamma", "Maus", "Pik" (Russia) and others).

Глобальная
Энергия Global
Energy
Геннадий МЕСЯЦ
Gennady MESYATS
Жорес АЛФЕРОВ
Zhores ALFEROV
Михаил МАТЫЦИН
Mikhail MATYTSIN

Teleportation

Review prepared by correspondent Alla Pashova, Russia

For conventional science, the term "teleportation" is not worthy of serious consideration unless ascertained by compulsory "quantum" teleportation. Thus, teleportation is unconditionally referred to microworld phenomena and, in fact, comes to distant information transfer. Spatial transference of a macroobject of definite mass has been excluded.

Teleportation of states

What does **quantum teleportation** mean? During active development of quantum theory, in 1935, the so-called EPR-paradox (Einstein-Podolskiy-Rozen paradox) was formulated in the well-known work "Can quantum-mechanical description of reality be full?" written by Albert Einstein, Boris Podolskiy, and Natan Rozen.

The gist of the paradox is as follows. There are two particles interacting for some time, thereby forming a common system. From the position of quantum mechanics, this coupled system can be described with a certain wave function. When interaction is over and particles scatter within arbitrarily large distances, they still will be described by the same function as before. At that, state of each separate particle cannot be known in principle that is apparent from uncertainty relation. Only when one of the particles enters a receiver, which records its parameters, the relevant characteristics of the other one emerge (exactly emerge, but not become known!). Thus instant unlimitedly distant "transmission" of quantum state of the particle is possible. Therewith, teleportation of the particle itself and transference of mass do not take place.

Einstein and his colleagues believed that existence of such particles predicted by quantum mechanics prove theory incompleteness. Thereof, the scientists inferred the necessity of other parameters (besides wave function) to describe quantum states. Otherwise, from the local viewpoint, correlations between elements of such a system could not be understood. It was far much later, when Bell showed that some of measurements could define these correlations and exclude any local hidden parameters. It was not until early 1980-s that famous experiments were performed finally eliminating a possibility of local hidden parameters.

In 1980, Alan Aspect experimentally proved that EPR-paradox in quantum world takes place indeed. Special measurements of state of EPR-particles indicated that EPR-pair not only has a common origin, but in addition, that one of the photons somehow "get to know" the way the second one was changed. In further experiments, existence of EPR-paradox was affirmed, even if particles of EPR-pair were removed from each other over a distance of 10 kilometers or so.

In 1993, Charles H. Bennett and his colleagues worked out a method to transfer the quantum state of some object of the microworld to another quantum object by means of EPR-pair and called this method "quantum teleportation". In 1997 a group of experimentalists under the direction of Anton Zeilinger for the first time implemented quantum teleportation of the photon state in the University of Innsbruck.

In such a way, researchers keep on improving the process of quantum teleportation. In 2001 Danish scientists managed to link gas particles spaced at a substantial interval from each other, by transmitting information about quantum state from one particle to another by means of laser. The quantum teleportation between two gaseous clouds were attained by Eugene Polzik and his colleagues in Orkhus University. They succeeded in coupling about million of cesium atoms, whereas the previous record was only four atoms.

Scientists of Australian National University destroyed a laser beam and nearly instantly recreated it in another point in space; in other words, they teleported photons of the laser beam. In contrast to previous similar experiments, the physicists managed to obtain the required result in 100 percents of cases. Ping Koy Lam, the head of the task group of Australian University, claimed that the first atom of solid substance was likely to be teleported within near three to five years. However, as most scientists admit, a task to teleport a human remains almost impracticable. Even teleportation of atoms, as compared to that of photons, is much more complicated process. It is even harder when dealing with molecules. It is basically possible (though practically very difficult) first to transfer a molecule to a minimum-energy state (ground state) causing it to radiate a certain sequence of photons. These photons will find themselves in a certain superposition containing all the "quantum" information, which was available in the molecule. Thereafter, it is possible to teleport photon states by means of EPR-pairs. Moreover, it is also required that the classically measured information about a molecule. If molecule of minimum-energy state is present in the receiver, then this molecule, by interacting with teleported photons in a required order, will transform to the quantum state identical to that of the initial one. Consequently, the quantum state of molecule of a certain material will be transmitted, actually with velocity of light. When that happens, the quantum state at the transmitting side will be destroyed.

The human organism comprises about 10^{27} atoms. To save and transmit information on properties of that number of particles seems to be practically unachievable. "Theoretically, nothing prevents us from doing that, but complexity of the problem is such that now no one seriously thinks about the solution" – states Ping Koy Lam.

Being a method of information transmission, quantum teleportation has found its application in quantum computers, whose information is stored in the form of a set of quantum states. Impossibility to wiretap and copy transmitted information is considered to be an advantage of such computers. Those researchers, who, nevertheless, wish to answer the question of "How to teleport matter, but not its state?" have to seek for more perspective theories and techniques.

Teleportation of material objects

Those people, who really want to realize instant spatial transportation of objects, i.e. teleportation, should refer to studying properties of Space and Time. Quantum teleportation has a certain finite velocity that cannot exceed that of light. The genuine teleportation assumes that an object should set off from a starting point to a finishing point (these points differ by a certain distance X), at that the transference time comes to zero. The object to be teleported is not changed or taken to atoms to be gathered later at a distant point of space according to information transferred to this point. (Fig.1).

The object disappears from one place and simultaneously appears in another place. How is that possible? A body will disappear from point A and appear in point B if to bend space in such a way as to let point A and point B coincide. Then the object will instantly appear in point B since there is no interval between points A and B. Teleportation could be realized by a device, which would make it possible to superpose points A and B.



Fig. 1

Space is supposed to be unbendable without enormous energy consumption. However, Alexander V. Frolov points out that this issue is not so unambiguous: "Normally we consider space in connection with "natural" course of time existing in it. That is some degree of space curvature. Let us assume that it can be changed. The space curvature can be considered as acceleration or deceleration of time. Acceleration always demands, for instance in mechanics, some energy consumption. But if we "decelerate" time, energy is liberated and it can be accumulated for subsequent use".

K.Z. Leshan suggests surrounding a transferred object with a closed surface consisting of vacuum holes. Inside such a "hole sphere" there is geometry similar to that of a black hole. This place is absolutely isolated from the external Universe. No radiation is able to penetrate through the hole in space and time. For an observer, who is inside the hole sphere, the distance between sphere center and its border is infinitely large, since spatial metrics is ever-varying from the center to the border. Distances between the points is continuously shortened so that the distance between any couple of points comes to zero at the very hole surface. A matter transmitter can have inner or outer hole surface. In the first case a teleportation station has a spherical chamber to place the object. Equipment to produce holes should be located upon the outer side of the sphere. Such a station is capable to provide hundreds of launches a day by instantly expulsing spaceships to deep space over distances of millions of light years.

From microcosm towards macrocosm

Simeon Bocharov (member of Chemistry and Biochemistry Department, University of Delaver, Newark, USA) considers teleportation phenomenon using microobjects as an example and applying an interesting conception of protomatter.

In S. Bocharov's opinion, many paradoxes of the present-day science could be solved under condition of considering the whole existing matter to be a single continuum, i.e. protomatter. At this approach, the microcosm objects are not independent ones, being represented in the form of distortions of the very continuum and its manifestations here and now. Protomatter, whose distortion degree is beyond modern possibilities of detection, corresponds to vacuum. In the present-day paradigm redistribution of protomatter distortion corresponds to motion of particles. The important peculiarity is a refusal of such concepts as structure, dimensions, mass and other macroscopic characteristics with respect to microcosm objects, since here they are not considered as separate entities.

For experimental justification of his theory, S. Bocharov suggests to consider teleportation of microobjects incorporated in fullerens under low temperatures and pressure.

As a basis for reasoning he takes the fact that identical or similar conditions, whereon distortions are located, bring them to the state of identical or similar by lability/diffuseness. And vice versa, distortions, which are similar by lability/diffuseness, influence their near surroundings, creating, as a result, similar macroscopic states. In such a case protomatter distortion (in some spatial domains and under similar conditions) will cause appearance of similar distortions in another domain, whose degree of removal depends on presence of other distortions and their characteristics. In other words matter will be teleported from one spatial domain to another.

Possibility to realize teleportation of microobject causes the well-known phenomenon, which is nowadays described as embedding of particles into inner hollows of spheroid fulleren molecules without reacting with them. As object of teleportation there can be used distortions classified as elementary ones, such as hydrogen, helium or stable matters (noble gases). In both cases the influence of objects upon surroundings is minimized.

The researcher believes that in case of successful experiment, new pattern of matter structure will be confirmed, and valuable teleportation of microobjects (with prospects of such possibility for macrocosm objects) will be demonstrated.

One more approach to teleportation of physical macroobjects was considered in the work "Practical application of time rate control" (New Energy Technologies No. 3, 2001) by Alexander V. Frolov. It is assumed that density of space (aether) energy determines rate of passing of any processes including the very process of matter existence. Changes of aether density (increase or decrease) must result in the emergence of a force analogous to that of buoyancy, though acting towards the fourth dimension. This "chrono-motive force" (CMF) is also an analogue of electromotive force (EMF) and can be generated by analogy with electrodynamics. According to Alexander V. Frolov, laws of quantum mechanics as to discretization of levels of energy of material system, which exist in the domain of increased or decreased aether density, are valid in the macrocosm as well. Teleportation (as a transition from one state of the system to another one) can be studied with electron transference from one orbit to another as an example with the only difference that for the teleported object not only its location, but also the very spatial properties are changed. In aether of different density (after discrete transition) the same object will have different space around it, wherein time is decelerated or accelerated. Experiments of this field have already been in development stage.

Therefore, modern theoretical physics has handed the problem of teleportation to researchers-experimentalists, who possess sufficient breadth of mind. Perhaps, using teleportation technologies, they will manage to fundamentally alter the process of space exploration and raise our civilization up to radically new development level.

ELECTRIFYING TIMES

an online and published
magazine about Electric,
Hybrid, Fuel Cell Vehicles,
advanced batteries, ultra
capacitors,
fuel cells, microturbines, free energy systems,
events and exhibitions worldwide

63600 Deschutes Mkt Rd,
Bend Oregon, 97701
541-388-1908 fax 541-388-2750
etimes@teleport.com
www.electrifyingtimes.com
Subscription $13/3 issues

“Mass defect” in Home Conditions

Prokofy V. Sherbak, Russia

Mitinskaya Str., 40-1-244, Moscow, 123430, Russia
Tel.: (095)950-4135
Email: Prokofy@mail.ru

The idea to conduct experiments on “mass defect” demonstration appeared after a cycle of seminars, which took place in1993-1996 at the Moscow Aviation Institute under the direction of V. I. Patrushev, Doctor of Technical Sciences, Professor of “Designing of aerohydrodynamic systems” Department (the author of the article is also a graduate of the Department). At the seminars, an enterprising group studied and developed an applied theory of “Displacing fields” by Alexis V. Murlikin and an associate “Theory of energy exchange processes”. Later the group was called **“Group studying non-inertial transference”** (non-inertial natural processes).

The experiment was aimed to test some theoretical suppositions, namely, that it is possible to influence on existent energy flows which input and output to the matter. At that the simplest way to influence indirectly is to change the medium the flows come through. In general, optic experiments on luminous flux refraction show the same. But light refraction and change of speed of light propagation at passing through different mediums is one thing; and change of mass of a material body is something new that has not ever been dealt with. Moreover you can consider light (i.e. electromagnetic radiation) to be the secondary manifestation of output energy flow. Besides mass defect is very important for nuclear physics because it “helps” to develop this branch and stimulates drawing “energy dividends” in splitting reactions, decay reactions and nuclear fusion reactions. But unfortunately we can not touch element nucleus and even million nuclei while we can easily touch metallic balls of 1 gram weight.

Let us note that a concept of mass is one of the most uncertain in physics. We can not measure mass directly. It is possible to do it only indirectly, by gravity, using scales (it does not matter what kind of scales are used), or by kinetic momentum (in this case mass is a measure of inertia) by means of dynamometers.

Thus it is evident that change of WEIGHT shown by scales is not MASS change as measure of matter quantity. Since one of the most important points of the theory of “Displacing fields” is creation of a vehicle of new generation, then one of the major tasks is to overcome gravity (to decrease weight). And this “home experiment” shows the way to solve it. However we can call it “home” only in part, because for weighing there were used electronic scales (mass-comparator with measurement accuracy of 0.1 microgram. (See Fig. 1).



Fig. 1

Precision scales METTLER TOLEDO allows making:
High-accuracy weighing in the range
from 0.1 microgram to several tones
Measurement with resolution up to milliard points

Two sets were designed for weighing. The first one had an aluminum (Al) ball-kernel which weighed 1 gram and a lead (Pb) casing-shell consisted of two parts (half-spheres) which also has weight of 1 gram. The second set had on the contrary a lead kernel and an aluminum casing. The sets were disassembled and then hermetically assembled to make a single device with no gaps (See Fig. 2).

Since it had to be done with great accuracy and it was a piece article, not a Moscow product company undertook to produce it. And only one of the students, Nicholas Sorokin, a young boy with skilful fingers, had helped. He invented a technology which allowed making balls of the necessary size at home conditions. He was literally pickling every micron of metal with acid and finally got the necessary size and weight.

So, the weight of a non-assembled set was: 1 gram (weight of kernel) and 1 gramm (weight of shell). Weight of an assembled set, according to the "Theory of energy exchange processes" by Murlikin, is not equal to the simple sum of the non-assembled components, and mass defect would be different for various sets right up to the change of sign.



Fig. 2

Set of experimental balls

More than 50 experiments was carried out on weighing for every set. Assembled sets as well as non-assembled sets were weighed. **It was confirmed that there was an interaction between input and output flows for MATTER MAINTENANCE. It became apparent in the form of mass defect. Defect appeared in the sixth sign, i.e. it comes to the range from 0.0002% to 0.0007% of "kernel" mass (or "shell" mass). At that the lesser mass defect corresponds to aluminum shell, while the greater one corresponds to lead shell. Accuracy of weight measuring by the mass comparator exceeded the acquired result by 10 times. So we could not tell about inaccuracy of measurements.** So we had to apply to the "Russian center of testing and certification" which was very famous all over the world (Rostest-Moscow).

In general that is all, we have got an answer for ourselves, and the period of testing is behind. We have to advance; very much is still to be done. In addition let us mention one more surprise we got during the experiments. The matter concerns some time delay in receiving final results of every weighing. A qualitative picture of it is represented in Fig. 3. We did not expect that this effect would appear at such a rough level of measurement of energy exchange processes.



Fig. 3

Time stabilization of the process for receiving final weight

The subsequent report and detailed discussion of the experimental results by specialists (including physicists of various specializations) resulted in an unexpected non-recognition of facts and distrust. The main argument was a demand to increase the number of experiments up to 5-10 hundreds. And only then scientists would be ready to accept facts. It was quite a predictable reaction for the orthodox science in the middle of 90s. It remains to hope that if the discussion took place today it would have a paved way. However it is not a fact.

In conclusion let us note that this experiment on revealing mass defect ranks with famous experiments, in which rotating gyroscopes also demonstrate mass defect (decrease of weight) and even one of higher order than in our experiment. But in return we have no rotation, no chemical and nuclear reactions, while mass defect is presented.

Let us add that it is possible to complicate the task: to make a double casing and to choose other materials for "kernel" and "shell". (See Fig. 2). In our case low prices and availability made us use Al and Pb. The results will be more interesting, for example, with Li and Os (and with other supertransuranic elements).

Aether as Unified Field

Alexander M. Mishin, Russia

Planernaya Str., 79-208, St.Petersburg, 197373 Russia
E-mail: samish@mail.ru

Based on the original observations and experiments, the article gives more precise definitions of aether model, than which was previously elaborated. General laws of the Universe aetherodynamic are considered. There is described a new physical reality in the form of quasi-real aetherodynamic structures (“topological harmonics”) generated by dynamics of the substantial world.

At the present-day stage of physics development words of Maugham, an English philosopher, take on particular topicality: “The great verities are too important to be new”. Indeed, we are increasingly making certain that our remote ancestors were familiar with fundamental laws of the Universe; furthermore, they knew these better than we do. But which methodology of cognition of Nature and what kind of information sources did the ancient scientists have? Today, we can openly say: they had not ordinary experience only, but also esoteric, pretersensual one, without feeling any necessity to be divided into materialists and idealists. For more details on evolution of physical ideas, refer to work [1].

In discovering all over again, I also had to elaborate a “cellular taction” strategy, which enables the most important characteristics of aetherodynamic processes to be sensually perceived and evaluated. The main thing is that all my sensory observations are definitely reproduced at laboratory experiments while the simplest physical equipment is used.

We may get reliable knowledge about Nature from Nature itself only. Thus foundation of classical physics describing usual substantial world is also based on empirical facts studied by Galilei, Newton, Faraday and many other physicists-natural philosophers. I also would like to defend great Newton against attacks on his adherence to inductive methods which really brought imperishable values into science.

A new convolution of cognition is possible on condition of introduction into science of new concepts based on empirical study of physical entities previously unknown. Thereupon, I share the thought of Elena Ventzel, professional mathematician: “Mathematical methods are not useful, but harmful until phenomenon is not studied at a pre-mathematical, humanitarian level”. It is ideological and logical language that may be used today to discuss the aether problem, whose solution calls for comprehension of natural-science facts, which are beyond traditional notions settled over centuries.

The long-term investigations have confirmed that exhaustive definition of a fundamental natural entity was given by Rene Descartes: “Universe does not contain anything but aether and its vortexes”. This is not merely a postulate; this is an objective summary of empirical observations of Nature phenomena. In any academical model of microcosm there is no answer to the question: what kind of substance are electrons, quarks, strings made of? That is the very substance our forefathers called aether. Aether is unified field indeed; and it appears that for nearly his whole life Einstein had been searching for something that was under his foot.

It must be recognized that there is no undistorted, quiescent aether in Nature; as well as no zero-size vortexes exist. Therefore, in a customary sense, the aether concept is pushed behind transcendental horizon and turned into an inconceivable entity whose mystique is tantamount to religious ideas. However, all quantum vortex-wave distortions of the superfluid three-dimensional aether, which have an appearance of tori, threads, solitons and occupy spatio-temporal spectrum from zero to inter-universe scale, are material and contain energy under scientific interpretation. Any spaces such as turbulent fields, physical vacuum, gravitational fields and, of course, matter are material. All of them are etherodynamic structures of the real world. Spatial hierarchy of aether vortices is referred to as quantum stairs, fractal structure or “matreshka” [2-5].

To understand basic laws of aetherodynamics it is necessary to give a general definition for classical matter and other aether states. As a first approximation, let us give the name of matter to aether microscopic **left-screw** self-oscillating vortex-wave systems (elementary particles), whose existence and parameters are conditioned by higher hierarchical systems. This is our displayed world, with its electromagnetic fields and fundamental constants. Let us refer to vortex-wave structures of any vortex size, which in the considered space domain are **balanced** by a number of left- and right-screw vortices corresponding to matter and antimatter with prefix "quasi" to a free aether. Stable vortex lattices with alternating direction of helicity can be also considered in this case. Under natural conditions everything but classical matter or electromagnetic and gravitational fields can be related to the free aether. In the first place, these are the so-called physical vacuum and vortex fields, which attend gravitation. They represent anisotropic nonlinear subspaces and occupy definite places on spatio-temporal spectrum of the world aether. Particular free subspace creates an aggregate of topological harmonics [5] attending all the physical processes. Satellite of the gravitational field is distinguished because it belongs to specific class of stable vortex lattices.

Apparently, in general case, energy of free aether is virtual for our world due to its helical symmetry and quasi-matter, from the view of difference in sizes of typical vortices which correspond to protomatter. But this is not the entire point. There is also superfluidity of aether, whose vortex viscosity has marvellous properties. As a result, there are created phenomena of inertia and energy-information barrier separating material world from constant influence of quasi-real structures or turbulated space.

Classical inertia, as vortex viscosity, arises in the microscopic and more fine-structure free aether (in Newtonian space) and ever regularly reveals itself during acceleration of material bodies. However everything is different at stage of macrovortex aether, where inertia has properties of adaptation. Here it is affirmed that inertia phenomenon is "spread" throughout the spatial-temporal spectrum of vortex distortions of aether field. At that nature of inertia is changed. Within topoharmonic subspace in laboratory scales, the inertia law "diminishes" in time according to exponential dependence, whose time constant is determined by specific conditions and varied over wide limits (from seconds to many days). On the expiry of this time, inertial intercoupling transforms to the law of flicker effect. It may be said that flicker effect specify penetrability of energy and information barrier after expiry of time of paraphysical regular phenomenon [6]. Consequently, most of time the interaction with free macroaether is of random character and should be evaluated by mean observation.

To extend conceptual scope of our investigation it may be added that in classical hydrodynamics a liquid, along with ordinary inertia, has determined vortex macroinertia, which is created by vortices of the liquid itself. Therefore, it is necessary to keep on comparing processes at all levels of the unified field of aether. For instance, electric inductance is a kind of specific inertia, and topological harmonics of electromagnetic and other phenomena are subjected to the energy-information barrier (under laboratory conditions).

In the above arguments, the principle of relativity is latently and unconsciously presented. However, this complicated question needs to be separately considered. Physical nature of the energy-information barrier and reason for dependence of the inertia properties upon the size of vortices of free aether remain unclear, too. However, it can be supposed that classical elementary particles, as distinct from protomatter, have self-oscillating properties and are commensurable with vortices of the surrounding free world; and that the above-mentioned energy-information barrier does not exist for them on microscopic section of the spectrum. The gist of the barrier itself comes to "memorizing" topoharmonic processes by Earth's gravitational fields and laboratory equipment. Turbulent fields (physical vacuum) do not have such a "memory".



Fig.1

Fig.1 depicts diagrams of spectral density of vortices' energy; diagrams of rate of interaction transfer v and circular frequency ω depending on sizes of vortices of the world aether Λ (in picometers). As we can see, velocity of distortions propagation v is equal to velocity of light C in the physical vacuum, i.e. in electron sizes, exceeds C in nanocosm and tends to zero toward megacosms. Circular frequency of vortices rotation and course of physical time have the analogous qualitative dependence. However, vortices energy W has a feature and grows toward both ways from the lab scales; the aether numbers have been assigned conditionally, but all the specified phase states reflect some physical reality.

One of the most complicated questions is a definition of vortex matter in each particular case. The diagram demonstrates energy of free aether in the form of protomatter (simplest elementary particles – vortexes), and energy of classical elementary particles as helically definite self-oscillating emissions of aether field is localized in the most nonlinear subspace (physical or substantial vacuum). Unification of the elementary particles into atoms and macrobody does not denote direct transition to parallel world with different fundamental constants, whereas change of vortex size in the diagram exactly implies such a transition, though at a level of protomatter. This is a very intricate and crucial point. For example, a star is, unconditionally, an elementary particle of the relevant level of the Universe, even though comprising the ordinary matter.

Left wing of energy spectrum reflects property of the turbulent field of aether to gravitate, to sink down to the "bottom" transferring energy to the vortices of lesser scales. This phenomenon of distributed "gravitation" is available in every space point and explains a least-action principle. An illustrative analogue of this regularity is represented by the Earth's gravitational field and structure. Dense plasma assumed as iron core is situated in the center, and higher - there are magma, solid crust, water and air. These phase states exist in free aether within universe scales as well. Consequently, in femtocosm, and maybe at an even deeper energetic "bottom", there must be a plasmic subspace; evidently, it is assignable that aether translated from Greek means "fire".

Increase of energy to the right is connected with extending a dynamic band of the vortices spectrum, as the scale increases. In our world, this increase follows the flicker effect law, but this is only what we perceive across the energy-information barrier. Actually, at this section the vortex energy must increase well more strongly, because **our observation capabilities are limited** by accessible matter processes. Turning back to stars, one may affirm that modern science is unable to evaluate their real energy (evaluations are considerably underrated). The Galaxy vortex entrains such deep levels of multidimensional space-aether to its rotation that this causes violation of the Newton's law of inertia. Notion of "hidden mass" is unnecessary for explaining dynamics of galaxies. It is quite enough to take into account that differential rotation entrains the fine-structure aether (inertial subspace), and this process results in decreasing the inertia and external centrifugal forces. Unfortunately, Fig. 1 reflects only a characteristic size of the galactic vortex and does not visually demonstrate its active band of the spectrum. The finer is the space structure, the more inertial and closer to the absolute reference frame is the space. Obviously, the non-homogeneous, stereodynamically multidimensional and multiphase aether requires a perfectly new theory of random fields, which would also make allowance for the phenomenon of the material world.

Energy motion processes or spectral energy-cascades along abscissa axis are of decisive importance for existence of our world and the Universe. These processes have unusual properties. The "violet" cascade is attended with reduction of vortices size, absorption of matter energy and tends to increase energy concentration at the "bottom" of the world aether (near ordinate axis on Fig.1). This regularity experimentally confirmed in both spatial and temporal domains is a direct consequence of the above-mentioned phenomenon of distributed gravitation and clarifies an existence of the left wing of the spectrum. In classical physics "the violet" cascade effect is reflected in the least-action principle as well as in the thermodynamics laws.

The "red" energy cascade (right wing of the spectrum) corresponds to increase of vortices size and is accompanied with energy liberation. To start it up under earthy conditions special technologies are called for [7]. This has been confirmed with laboratory experiments and underlies the "perpetual motion" theory, where energy is pumped from nanocosm to the classical material world. Conception of artificial biofield [6], I have developed, considers methods of creating the aether vortex-wave macroscopic-scale distortions in physical systems. As a matter of fact, we deal with **ways of extending of natural spatio-temporal spectrum of aether (which settled into itself) by creation of a subspace of the topological subharmonics of the classical elementary particles, atoms and molecules**

(physical bodies), within the context of the etherodynamics fundamental law [5].

Even within action of fluctuating energy-information barrier, the spectrum right wing exhibits existence of natural processes in Nature that, supposedly, violate the known laws of thermodynamics [8]. But, as far as Nature cannot conflict with itself, we have to recognize that there is another physics, which "works" in geographic and greater scales, where role of the energy-information barrier demands to be reappraised. To all appearance, the universe vortex partialyl entrains plasmic subspace of aether into its rotation, and conditions for realizing "red" energy-cascade and generating matter are created on the sections of the maximum density gradient ("spectral" non-linearity). But the same way as a fish in ocean does not know reasons for storms and currents, we will never learn which force untwists the Universe handwheel, whose energy feeds our substantial world.

There are two components of free aether field that are the most essential for the present-day physics. The first one (left wing) is positioned on the spectrum beside the "bottom" in the form of dense liquid-crystalline "plasmatic" medium transforming to the Newtonian inertial subspace (physical vacuum). Since inertia is as regular as electric inductance is, the first subspace proves to be especially material and not such free, because it has properties which were imposed by the Universe rotation and distributed "gravitation". Let us conventionally limit the spatial spectrum of the first component with a nucleon size. The second component of aether space (right wing of the spectrum) stretches towards larger scales.

Except for known cosmic objects, this is an unknown ocean of the macrovortex and really free aether, or topoharmonics, which are born by dynamics of the substantial world. It is an experimentally proven fact that topoharmonics are generated by photons, electrons, and all the moving bodies [5, 9].

The second component has an ability to conversely affect the matter it was generated by as well as other material objects via "flickering" forces [10, 11]. This special subspace turns out to be doubly virtual, a genuine phantom. That is why, it has been winning the status of a real physical entity with such a difficulty, while Chinese philosophers were familiar with the same thousands years ago, separating entities "yang" and "yin".

The laboratory experiments indicate that topoharmonics have not only properties described in [5], but also an ability to interact with the space, creating a static domain of the excited aether in the course of propagation of the vortices-waves. At that physical bodies placing within this space volume are "charged" [2, 9]. The mentioned active domain (horizontal route) is "separated" by the Earth's gravitational field as follows: quasi-substantial constituent rapidly settles down creating vertical flow, but some phase structures are disintegrated very slowly (days, months, years).

The surprising thing is that biosystems equally belong to both aether components, not experiencing any constraint from the side of the energy-information barrier. The so-called human biofield is a topoharmonic part of physical body. It occupies its place on the spatio-temporal spectrum (Fig. 1). Quasi-substantial constituent (yang) and antiquasi-substantial one (yin) are strictly balanced, and acupuncture points and chakras are an analogue of Hartmann's geophysical grid, which is well-known to paraphysicists.

Conceptual generalization of physical ideas in the context of unified field of aether gives a constructive, cognitive impulse in solving of different problems, such as Nature's choice of exclusive laws for existence of "left-screw" material world as well as the problem of flicker-effect. At that, researching into the physical processes responsible for proton positive charge is of fundamental importance.

In conclusion, let us take note of conventional character of dividing the aether field into two components by the form of energetic spectrum. As a matter of fact, topoharmonics are generated by matter towards both larger spatial frequencies (subharmonics) and smaller ones (harmonics) and fill all levels of the Universe. The aforesaid is aimed at making perception of the most studied aspect of the **new physical entity** (vague due to diversity of hypothetical descriptions which exist in publications on this subject) more accessible.

Reference

1. A.P. Smirnov, I.V. Prokhortsev. Order principle. – Saint-Petersburg: ZAO «P and K», 2002. - 296 p.
2. A.M. Mishin. The aether model as a result of the new empirical conception. New ideas in natural sciences. (On materials of International Conference). Part 1 "Physical". - St.-Petersburg: RAS, 1996, p. 95-104.
3. A.M. Mishin. Fundamental properties of aether. Fundamental Problems of Natural Science. Series «Problems of the Universe research», fascicle 21 – Saint-Petersburg: RAS, 1999, p. 176-176.
4. A.M. Mishin. Physics of parallel worlds. / Fundamental Problems of Natural Science and Technics. Series «Problems of the Universe research», fascicle 23 - Saint-Petersburg: Publishing

House of the Saint-Petersburg State University, 2001, p. 258-269.

5. A.M. Mishin. Etherodynamics basic law. / Fundamental Problems of Natural Science and Technics. Series «Problems of the Universe research», fascicle 26, part III. - Saint-Petersburg: Publishing House of the Saint-Petersburg State University, 2003, p. 206-218.

6. A.M. Mishin. Physical system with artificial biofield. / Fundamental Problems of Natural Science and Technics. Series «Problems of the Universe research», fascicle 23, - Saint-Petersburg: Publishing House of the Saint-Petersburg State University, 2001, p. 258-269.

7. V.F. Zolotarev, V.V. Roschin, S.M. Godin. About space-time structure and some interactions. - Moscow: Publishers «PREST», 2000. - 309 p.

8. V. Starr. Physics of phenomena with negative viscosity. - Moscow: MIR, 1971.

9. V.V. Kvartalnov, N.T. Perevozchikov. Discovery of a "non-physical" component of OKG radiation. Journal «Parapsychology and Psychophysics». - Moscow: 1999, No. 2 (28), p. 64-67.

10. A.M. Mishin. Longitudinal thermomagnetic effect. / Fundamental Problems of Natural Science and Technics. Series «Problems of the Universe research», fascicle 26, part III. - Saint-Petersburg: Publishing House of the Saint-Petersburg State University, 2003, p. 219-228.

11. A.A. Efimov, A.D. Shpitalnaya, Y.A. Zakoldaev. Eruptive prominences and earthquakes in the view of global space anisotropy. / «New Ideas in Natural Science». Series «Problems of the Universe research», fascicle 19, part II. – Saint-Petersburg: RAS, 1996, p. 403-413.

GLOBAL ENERGY

Philip M. Kanarev, Russia

The Kuban State Agrarian University, Department of Theoretical Mechanics
13, Kalinin Street, 350044 Krasnodar, Russia
E-mail: kanphil@mail.kuban.ru

Lately, the notion "Global energy" has become widely spread as a prize corresponding to this notion has been instituted in Russia. Since the Euclidean times, an unwritten law exists in science: to give definition to the notions, which are involved in scientific analysis. It is done for the purpose that everybody who uses this notion can understand the sense implied in it.

The Global energy problems have been discussed for a long time; they are well known. Depletion of natural energy carriers (oil, gas and coal) is the first problem. Environmental safety of energy carriers is the second problem. It is generally recognized that the solution of the issues connected with the aggregate of these two problems is of a global character. The results of scientific research, which should deal with global energy, originate from it. First and foremost, they are such scientific investigations, which result in the possibility to use an inexhaustible and environmental friendly energy carrier. It has been known for a long time. It is hydrogen produced from water.

Why hydrogen and why from water? At combustion of hydrogen, water is regenerated; thus, the energy carrier is inexhaustible. As far as inexhaustibility and environmental safety are concerned, hydrogen has no competitors. However implementation of these qualities is restricted by large energy expenses for hydrogen production from water. For hydrogen production, modern electrolyzers use from 10 to 20% more energy than it is produced at combustion of hydrogen.

It is easy to imagine what financial and intellectual resources of the world are included in the search of the ways to reduce energy expenses for hydrogen production from water. In Russia many scientific institutions of applied research and educational institutions deal with this problem. There is a Research Hydrogen Institute.

The associations of scientists on hydrogen energetics have been established in USA and Europe. This year, they carry out their regular scientific conferences, to which the author of this article has been invited.

Editorial: Let us note that it is not necessary to coin new scientific term "global energy", since quite for a long time the notion of "free energy" is used. This term represents the idea of the possibility to freely use energy by a consumer.

Energy problem is global not due to depletion of oil and gas, but due to their environmental unsafeness. However the confirmations exist that the world owners of energy resources do not bother about the problem of environmental unsafeness of modern energy carriers.

House of the Saint-Petersburg State University, 2001, p. 258-269.
5. A.M. Mishin. Etherodynamics basic law. / Fundamental Problems of Natural Science and Technics. Series «Problems of the Universe research», fascicle 26, part III. - Saint-Petersburg: Publishing House of the Saint-Petersburg State University, 2003, p. 206-218.
6. A.M. Mishin. Physical system with artificial biofield. / Fundamental Problems of Natural Science and Technics. Series «Problems of the Universe research», fascicle 23, - Saint-Petersburg: Publishing House of the Saint-Petersburg State University, 2001, p. 258-269.
7. V.F. Zolotarev, V.V. Roschin, S.M. Godin. About space-time structure and some interactions. - Moscow: Publishers «PREST», 2000. - 309 p.
8. V. Starr. Physics of phenomena with negative viscosity. - Moscow: MIR, 1971.
9. V.V. Kvartalnov, N.T. Perevozchikov. Discovery of a "non-physical" component of OKG radiation. Journal «Parapsychology and Psychophysics». - Moscow: 1999, No. 2 (28), p. 64-67.
10. A.M. Mishin. Longitudinal thermomagnetic effect. / Fundamental Problems of Natural Science and Technics. Series «Problems of the Universe research», fascicle 26, part III. - Saint-Petersburg: Publishing House of the Saint-Petersburg State University, 2003, p. 219-228.
11. A.A. Efimov, A.D. Shpitalnaya, Y.A. Zakoldaev. Eruptive prominences and earthquakes in the view of global space anisotropy. / «New Ideas in Natural Science». Series «Problems of the Universe research», fascicle 19, part II. – Saint-Petersburg: RAS, 1996, p. 403-413.

GLOBAL ENERGY

Philip M. Kanarev, Russia

The Kuban State Agrarian University, Department of Theoretical Mechanics
13, Kalinin Street, 350044 Krasnodar, Russia
E-mail: kanphil@mail.kuban.ru

Lately, the notion "Global energy" has become widely spread as a prize corresponding to this notion has been instituted in Russia. Since the Euclidean times, an unwritten law exists in science: to give definition to the notions, which are involved in scientific analysis. It is done for the purpose that everybody who uses this notion can understand the sense implied in it.

The Global energy problems have been discussed for a long time; they are well known. Depletion of natural energy carriers (oil, gas and coal) is the first problem. Environmental safety of energy carriers is the second problem. It is generally recognized that the solution of the issues connected with the aggregate of these two problems is of a global character. The results of scientific research, which should deal with global energy, originate from it. First and foremost, they are such scientific investigations, which result in the possibility to use an inexhaustible and environmental friendly energy carrier. It has been known for a long time. It is hydrogen produced from water.

Why hydrogen and why from water? At combustion of hydrogen, water is regenerated; thus, the energy carrier is inexhaustible. As far as inexhaustibility and environmental safety are concerned, hydrogen has no competitors. However implementation of these qualities is restricted by large energy expenses for hydrogen production from water. For hydrogen production, modern electrolyzers use from 10 to 20% more energy than it is produced at combustion of hydrogen.

It is easy to imagine what financial and intellectual resources of the world are included in the search of the ways to reduce energy expenses for hydrogen production from water. In Russia many scientific institutions of applied research and educational institutions deal with this problem. There is a Research Hydrogen Institute.

The associations of scientists on hydrogen energetics have been established in USA and Europe. This year, they carry out their regular scientific conferences, to which the author of this article has been invited.

Editorial: Let us note that it is not necessary to coin new scientific term "global energy", since quite for a long time the notion of "free energy" is used. This term represents the idea of the possibility to freely use energy by a consumer.

Energy problem is global not due to depletion of oil and gas, but due to their environmental unsafeness. However the confirmations exist that the world owners of energy resources do not bother about the problem of environmental unsafeness of modern energy carriers.

In history of science, the facts of annihilation of the scientists who have won success in reduction of energy expenses for production of hydrogen from water have already been registered. The requesters of these actions think that they will lose their profits with the coming of hydrogen energetics. They do not understand that this process cannot be abrupt. It is impossible to replace the infrastructure of the existing energy carriers by infrastructure of hydrogen energetics within one or even ten years. Besides, infrastructure of hydrogen energetics will not be created on a blank place. It will be integrated into the existing infrastructure of energetics gradually; and its owners will automatically become the owners of hydrogen energetics. The first step has already been made in this direction. In the USA, a decision has been taken to equip all filling stations with pumps to fill the cars with hydrogen.

It is known that a priority of results of theoretical investigations is their publication in press. Usually, such priority is a personal one. Generally a patent is a priority of the results of experimental investigations. As a rule, this patent belongs to a group of authors. A published patent is a genie released from a bottle. No finesse of the authors to hamper a reproduction of experimental data given in a patent without the participation of the authors can stop the process of their implementation. Thus, the authors or a group of the authors who have filed an application for a patent are deprived automatically of the opportunity to influence the process of practical realization of their ideas.

In Russia, the state is a main patent holder of the global patents. Due to the well-known reasons, it has proved to be unable to control the course of scientific investigations and to forecast significance of their results.

It is known that if it becomes possible to reduce energy expenses for hydrogen production of water fivefold, it will be the cheapest energy carrier. Russia has already got technology, which reduces these expenses tenfold and more. However another way of looking is more perspective. Is there any use to decompose water into hydrogen and oxygen and to use hydrogen as fuel for heating, for example, of water in heating systems? Is it possible to make water generate heat? It turned out that, it is possible.

In Russia, three firms (“Yusmar”, “Termovikhr” and “Noteka”) sell cavitation heating equipment with energy performance index up to 150%. Official science looks awry at this activity, since such results conflict with one of the main laws of physics: law of conservation of energy. But market profit is stronger than this law.

Meanwhile, engineering practice has already proved that additional energy in the form of heat is generated in the ventilation systems and in the systems of water cavitation. Thorough scientific analysis of this problem shows that physical vacuum is the most probable source of additional energy in the systems of ventilation and water cavitation. Valence electrons of destroyed molecules of water take energy from physical vacuum and release it during repeated fusion of these molecules.

Why is additional energy generated in the air systems of ventilation and in systems of water cavitation? Because they are mechanical systems and mechanical destruction of chemical links requires half energy as compared with thermal destruction of these links. This is the main reason why one fails to increase energy performance index of cavitation processes over 200%.

Certainly, an increase of efficiency of any process by 30 or 50% is a good result; if it is obtained, it is possible to get even better one. But what if a water molecule is destroyed not mechanically, but electrodynamically? In this case, it becomes possible to find resonance frequencies of influence on the molecules and therefore to reduce considerably expenses of electrical energy for their destruction. Subsequent fusion of destroyed molecules will release determined quantity of energy unavoidably. It is a simple idea, and it has already been implemented. At electrodynamic influence on water molecules, electrical energy is converted into thermal energy with tenfold energy performance index. It means that if we spend 1 kWh of electric energy, we will get 10 kWh of thermal energy. To obtain such results, it is necessary to have knowledge of physchemistry of the microworld, which corresponds to knowledge of the 21st century, and it has already been published. Every month more than 1000 foreign scientists become familiarized with this knowledge at
http://Kanarev.innoplaza.net and
http://book.physchemistry.innoplaza.net.
The Russian speaking readers get this information from:
http://www.n-t.org/tp/ns/if.htm,
http://www.ikar.udm.ru/sb28-2.htm and
http://www.n-t.org/tp/ts/eb.htm.

I hope that now the readers will know the essence of the notion “global energy” and will understand those results of scientific researches which can really solve the related problems.

Energy Balance of Fusion Processes of Oxygen, Hydrogen and Water Molecules

Philip M. Kanarev, Russia

The Kuban State Agrarian University, Department of Theoretical Mechanics
13, Kalinin Street, 350044 Krasnodar, Russia
E-mail: kanphil@mail.kuban.ru

There is revealed the cause of appearance of additional energy during formation of covalent bonds in the fusion processes of oxygen, hydrogen and water molecules, besides the source of this energy is described.

Introduction

Engineering practice connected with servicing of ventilation systems allows revealing appearance of excessive thermal energy in circulated air. Similar phenomenon has been registered in systems of water circulation with the devices for its active cavitation. The results of our investigations explain not only a cause of these phenomena, but they give an opportunity to perform quantitative calculations for energy processes, which generate additional thermal energy [1], [2], [3], [4], [5].

Theoretical part

An oxygen atom is the eighth element of the periodic table. It is situated in the sixth group. The structure of its nucleus is given in Fig. 1 [1], [2], [3].



Fig. 1
Diagram of nucleus of oxygen atom: light – the protons, dark and grey – the neutrons

In Fig. 2 a diagram of the oxygen atom originating from the structure of its nucleus is given (Fig. 1). It has eight electrons. The electrons situated on the axis of symmetry are the most active ones (1, 2). Other six electrons situated in the plane, which is perpendicular to the axis line (a line of symmetry), by means of their total electric field remove electrons 1 and 2 from the nucleus at a large distance at that forming conditions for their large activity during the interaction with the electrons of the neighbouring atoms [1], [2], [3].



Fig. 2
Diagram of the oxygen atom

The least ionization energy of the electron of oxygen atom is equal to E_i =13.618 eV. Binding energy of this electron with the atomic nucleus corresponding to the first energy level is equal to E_1 =13.752 eV. Let us call this electron the first one. The calculation of energy indices of this electron, including its binding energies E_b with the atomic nucleus, according to the formulas (1) and (2), gives the following results (Table 1) [1], [2], [3].

$$E_{ph} = E_i - \frac{E_i}{n^2} = E_i - \frac{E_1}{n^2} \tag{1}$$

$$E_b = \frac{E_1}{n^2} \tag{2}$$

Table 1
Spectrum of the first electron of the oxygen atom

Values	n	2	3	4	5	6
E_{ph} (exp.)	eV	10.18	12.09	12.76	13.07	13.24
E_{ph} (theor.)	eV	10.16	12.09	12.76	13.07	13.24
E_b (theor.)	eV	3.44	1.53	0.86	0.55	0.38

The oxygen molecule structure is given in Fig. 3, a. It is formed by means of a connection of unlike magnetic poles of axis electrons of two oxygen atoms [1], [2], [3]. It is known that the fusion process of the oxygen molecules is accompanied with a release of 495 kJ/mole of energy, or in calculation for one molecule

$$E_b = \frac{495 \cdot 1000}{6{,}02 \cdot 10^{23} \cdot 1.602 \cdot 10^{-19}} = 5.13eV. \quad (3)$$

What principle does the Nature follow by distributing energy of 5.13 eV between the electrons of oxygen molecule (Fig. 3, a)? Energy of 5.13 eV is a thermal binding energy between the electrons 1 and 2' of two oxygen atoms (Fig. 3, a). When the oxygen molecule is formed, it is emitted in the form of the photons by the electrons, which enter into the bond. Hence it is equal to an amount of energies of two photons emitted by these electrons. Consequently, each contacting electron emits a photon with energies of 5.13/2=2.565 eV=E_b (Fig. 3). According to Table 1, in this case the valence electrons are situated between the second energy level and the third one [1].



Fig. 3
Diagram of binding energy distribution between the electrons in the oxygen molecule

Two oxygen atoms are combined into a molecule in an excitation state. The excitation state is the state of an atom when its valence electrons are situated at such distances from the nuclei when the binding energy E_b between them is reduced to the thousandth of fractions of an electron-volt. In such state the atom can loose an electron and become an ion. Otherwise, without loosing electrons it is combined with an electron of the neighbouring atom by the valence electron, and a process of formation of oxygen molecule begins. It is an exothermic process when the axis valence electrons 1 and 2' emit photons, descend on lower energy levels and release 2.565x2=5.13 eV.

Let us pay attention to the fact that energy 5.13 eV is released by two electrons, which form a bond with energy of E_b=2.56 eV. In modern chemistry this bond is called a covalent bond. In order to break this bond it is necessary to use 2.56 eV of mechanical energy. For thermal cleavage of this bond, double quantity of energy is required, i.e. 5.13 eV. It is explained by the fact that the photon energy of 5.13 eV is absorbed by two electrons simultaneously. Only in this case, both electrons will be transferred to the highest energy levels with minimal binding energy E_b when they are disconnected, and each oxygen atom becomes a free one.

Thus, energy expenses for destruction of oxygen molecule depend on the method of influence upon the bond. During thermal action upon the bond it is destroyed when energy is 5.13 eV. During mechanical effect upon the bond, it is necessary to spend 2.56 eV of energy in order to destroy this bond. Therefore energetic of fusion process of the oxygen molecule depends on method of its destruction.

After thermal destruction of the oxygen molecule process of its formation begins from emission of the photons with energies of 2.56 eV by both valence electrons, and the previous electrodynamics binding energy (E_b=2.56 eV) is restored between the electrons of both atoms.

Thus during thermal destruction of the oxygen molecule the same amount of thermal energy is spent than that which is released during its further formation. No additional energy appears during thermal dissociation of oxygen molecule and at its further fusion.

If oxygen molecule is destroyed by a mechanical method, then it is necessary to spend 2.56 eV of mechanical energy for this purpose. Valence electrons of oxygen atoms are in a free state at lack of energy, which corresponds to such state, as there is no process of absorption of 2.56 eV of energy by each of them. The electrons cannot remain in such state; they should replenish immediately the energy, which they have failed to receive during a mechanical break of the bond between them. Where should they take it from? There is only one source: the environment, i.e. the physical vacuum filled with aether. They convert aether into energy of 2.56 eV immediately. The next stage is a connection of two oxygen atoms, whose valence electrons have replenished the reserves of their energy by means of aether. This process is accompanied by emission of the photons with energies of 2.56 eV by two electrons. Thus energy of absorbed aether is converted into thermal energy of the photons. If we spend 2.56 eV of mechanical energy for destruction of oxygen molecule, we will get double quantity of energy (2.56x2=5.13) eV during further fusion of this molecule. Additional energy is equal to 2.56 eV.

Much experimental data show that in ventilation systems thermal energy of circulated air exceeds electric energy spent for a fan drive. Now we know that this energy is generated at mechanical destruction of covalent bonds in the molecules of gases, which the air consists of.

Using the above-mentioned method, let us analyse energetic of water molecule, which sometimes generates additional thermal energy. A water molecule consists of one oxygen atom and two hydrogen atoms. Binding energies E_b of the hydrogen atoms with its nucleus are given in Table 2 [1], [2], [3].

Table 2

Spectrum of hydrogen atom

Values	n	2	3	4	5	6
E_{ph} (exp.)	eV	10.20	12.09	12.75	13.05	13.22
E_{ph} (theor)	eV	10.198	12.087	12.748	13.054	13.220
E_b (theor.)	eV	3.40	1.51	0.85	0.54	0.38

It is known that combination of hydrogen and oxygen is accompanied by an explosion, but its cause remains unknown. Let us try to find it.

Energy of fusion of hydrogen molecule is equal to 436kJ/mole, or 4.53 eV per a molecule. As the molecule consists of two atoms, then the above-mentioned energy is distributed between them. Thus energy of one bond E_b between the hydrogen atoms is equal to 2.26 eV (Fig. 4). At mechanical destruction of this bond 2.26 eV is enough. At thermal destruction of this bond double quantity is required (2.26x2=4.53 eV) [1].



Fig. 4

Hydrogen molecule

In order to form two water molecules, it is necessary to break two hydrogen molecules and one oxygen molecule into atoms. At mechanical destruction of covalent bonds 2.26x2=4.53 eV is required to break two hydrogen molecules and 2.56 eV to break an oxygen molecule. Sum of these energies is equal to 7.13 eV. If the destruction processes of the above-mentioned molecules are carried out with a thermal method, then 4.53+4.53=9.06 eV is required for the destruction of two hydrogen molecules, and 5.13 eV is required for the destruction of one oxygen molecule. In total, it is equal to 14.19 eV. The difference between the energy spent for mechanical and thermal destruction of covalent bond of hydrogen and oxygen molecules is almost double.

It is known that during fusion of one mole of water 285.8 kJ or $285.8x1000/6.02x10^{23}x1.6x10^{-19}$=2.96 eV per a molecule are released. As a water molecule consists of one oxygen atom and two hydrogen atoms, 2.96/2=1.48 eV falls per the bond (Fig. 5). Hence the electrons of hydrogen and oxygen atoms in water molecule are between the forth energy level and the fifth one at the usual temperature (1.48/2=0.74 eV = E_b), Table 1,2 [1].



Fig. 5

Diagram of water molecule:
1, 2, 3, 4, 5, 6, 7, 8 are the numbers of the electrons of oxygen atom; P_1, P_2 are the nuclei of the hydrogen atoms (the protons); e_1 and e_2 are the numbers of the electrons of hydrogen atoms

Thus when two hydrogen molecules $2H_2$ and one oxygen molecule O_2 are destroyed by the thermal method, 14.19 eV are spent. As a result of fusion of two water molecules ($2H_2O$), 2.96x2=5.98 eV is released. There is some disbalance here since fusion process of water molecule is an exothermic one and 2.96 eV is released by one molecule. The given calculation shows that (14.19-5.98)/2=4.10 eV is absorbed during fusion of one water molecule. What is the cause of this contradiction?

The oxygen atom in the water molecule should reduce its volume when the transition from gaseous state into liquid state takes place. It will happen when the ring electrons of oxygen atom descend on lower energy levels (nearer to the nucleus). They will emit the photons and their total energy will be equal to energy spent to destruction of two hydrogen molecules and one oxygen molecule, i.e. 14.19 eV. Since two water molecules have 12 ring electrons, each of them will emit 14.19/12=1.18 eV=E_b (Fig. 5). It is more than energy (E_b=0.74 eV) of binding of axis electron with the nucleus, and it shows that the ring electrons are situated nearer to the nucleus than the axis ones.

In this case quantity of energy produced due to fusion of two water molecules (14.19+5.98) eV exceeds energy, which was spent for the destruction of two hydrogen molecules (9.06 eV) and one oxygen molecule (5.13 eV). Energy difference of 5.98 eV is divided between two water molecules. It means that 5.98/2=2.99 eV or 285.8 kJ/mole fall per a molecule. It corresponds to the existing experimental data completely [1].

The above-mentioned facts clarify a cause of the explosion, which takes place when hydrogen is combined with oxygen. Simultaneous transition of six ring electrons of each oxygen atom in the nascent water molecules to lower energy levels is accompanied by simultaneous emission of the photons, which generate explosion phenomenon.

Let us pay attention to the fact that two binding energies E_b between valence electrons e2 and 2 and between 1 and e1 are shown in Fig. 5, b. Energy of one electrodynamics bond is equal to E_b= 0.74 eV. If this bond is destroyed by the thermal method, 0.74x2=1.48 eV is required. This energy will be released during further fusion of the water molecule from hydrogen atom H and hydroxyl ion OH^-. In this case, no additional energy is generated.

Therefore the given bond is destroyed by the mechanical method spending 0.74 eV per a bond, each electron will have energy deficit equal to 0.74 eV after bond destruction. This energy will be immediately absorbed from the environment and will be emitted during the repeated fusion of the water molecule from the hydrogen atom H and the hydroxyl ion OH^-. At mechanical destruction of one bond of water molecule, the covalent chemical bond forms E_b= 0.74 eV of additional thermal energy, which is registered in systems of water cavitation constantly (as we have already noted) [1], [2], [3].

It is known that water molecules combine and form clusters. If the bonds between the molecules in the clusters are covalent ones, mechanical destruction of these bonds should be accompanied by a release of additional thermal energy as well [1], [2], [3].

Experimental Part



Fig. 6

Diagram of the experimental device: 1 - reservoir for solution; 2 - thermometer; 3 - electronic scales; 4 - solution supply duct; 5 - rotameter; 6 - feed solution regulator; 7 - a special thin plasma reactor is in the process of patenting; 8 - thermometer; 9 - discharge of heated solution; 10 - inlet reservoir

Thus, chemical bonds between the atoms in the molecules and the molecules in the clusters can be destroyed mechanically, by electrodynamic and thermal influence. We have already shown that the mechanical way of destruction of such bonds requires half energy as compared with thermal energy. It appears from this that energy expenses for electrodynamic destruction of these bonds should be less than thermal expenses as well. Electrodynamic impact on the bond gives the opportunity to form the resonance modes where energy expense for the destruction of these bonds is reduced to greater degree. In order to check this hypothesis a special experiment was carried out. It was connected with electrodynamic destruction of chemical bonds of water molecules with a changing frequency of impact. To test this hypothesis the check experiment was prepared and carried out by (besides the author of this article) A.I. Tlishev, G.P. Perekotiy, D.A. Bebko, D.V. Korneev. A diagram of the experimental device is given in Fig. 6. The results of this experiment are given in Table 3.

Table 3

Protocol of control test

Indices	1	2	3	Mean
1 – mass of the solution, which has passed through the reactor m, kg.	2.112	2.153	2.118	2.128
2 – temperature of solution at the input of the reactor t_1, degrees	24	24	24	24
3 – temperature of the solution at the output of the reactor t_2, degrees	33.5	33.5	33.5	33.5
4 – differential temperature of the solution $\Delta t = t_2 - t_1$, degrees	9.5	9.5	9.5	9.5
5 – durability of the experiment $\Delta\tau$, s	300	300	300	300
6 – reading of voltmeter V, B	25.0	25.0	25.0	25.0
7 – reading of ammeter I, A	1.40	1.40	1.40	1.40
8 – electric power consumption according to indices of voltmeter and ammeters, $E_2 = I x V x \Delta\tau$, kJ	10.50	10.50	10.50	10.50
9 – power spent for heating of the solution, $E_3 = 4.19 x m x \Delta t$, kJ	84.10	85.70	84.31	84.70
10 – reactor efficiency index according to the reading of voltmeter and ammeter $K = E_3/E_2$	**8.00**	**8.16**	**8.03**	**8.06**



Fig. 7

Photo of heat reactor

In the Russian market three firms (Yusmar, Termovikhr and Noteka) sell cavitation water heating equipment with energy efficiency index of 150%. Soon, an air heating devices with the same efficiency will be produced. The processes of mechanical destruction of covalent bonds of the air gas molecules, molecules and clusters of water and their further fusion serve as a source of additional energy generated by these devices [1], [2], [3].

Conclusion

Analysis of energy balance of the molecules with covalent bonds shows the possibility of additional thermal energy formation during mechanical and electrodynamics destruction of these bonds.

References

1. Ph.M. Kanarev. The Foundation of Physchemistry of Micro World. Krasnodar. 2002. 320 pages. (In Russian).
2. Kanarev Ph.M. The Foundation of Physchemistry of Micro World. The second edition. (In Russian). http://www.ikar.udm.ru/sb28-2.htm
3. Kanarev Ph.M. The Foundation of Physchemistry of Micro World. The second edition. (In English). http://book.physchemistry.innoplaza.net
4. Kanarev Ph. M. Energy Balance of Fusion Processes of Molecules of Oxygen, Hydrogen and Water. (In English) http://Kanarev.innoplaza.net
5. Kanarev Ph. M. Energy Balance of Fusion Processes of Molecules of Oxygen, Hydrogen and Water. (In Russian) http://www.n-t.org/tp/ts/eb.htm.

The Fourth State Of Matter (Plasma Energy) Power Generation

Bruce A. Perreault, USA

http:// www.nuenergy.org
Email: nuenergy@cyberportal.net

Under the proper configurations and in the correct pre glow discharge environment more electrons can be released than what is required to trigger the release. This release of energy attains a high frequency oscillation that is indicative of the metal or metals involved in its release.

The release of high frequency energy from metals and semi metals (semi conductors) through the mechanism in the pre-glow discharge leads to the generation of radiant energy. This correlation has been identified through my findings. The release of high frequency energy from the atoms of electrical conductors is credited to my identification of the mechanism in the pre-glow discharge, or fourth state of matter. This has lead to extremely efficient alternative energy circuits.

The release of high frequency energy from the atoms of electrical conductors is credited to my identification of the mechanism in the pre-glow discharge, or fourth state of matter. This has lead to extremely efficient alternative energy circuits.

The pre-glow discharge condition occurs when a sufficient amount of charge difference is applied across the gap of two electrical conductors. It makes a hissing sound if the electrodes are surrounded by air. The electrical properties between this gap change: electrons become "stripped" from their respective atoms and are liberated. In this state, air is **ionized** and is transformed into a **plasma** and is no longer a gas. It is now in the fourth state of matter, the other three being solid, liquid, and vapor (gas). The fourth state of matter is a good conductor of electricity, its average resistance being much lower than that of the same substance in its gaseous state.

A good readily available spark gap combination is lead and iron. This combination generates plenty of radiant energy and causes noise to be heard on a radio in its vicinity. As a general rule, the better the thermoelectric difference between the dissimilar couple the more radiant energy that will be generated when it is exposed to a plasma field.

Early in the summer of 1981, the pre glow had first caught my attention. This is where I had observed it between two plastic insulated hook-up wires from radio shack. The plasma between the two wires was called into existence because of a high voltage power supply that I had obtained for my electrogravitic experiments. The two wires were twisted together and given a charge of around ninety kilovolts.

It was not until 1989 when I observed a high frequency signal on my oscilloscope coming from the pre-glow discharge phenomenon. These signals were coming from across the room and originated from a crude component that I had built. This crude component consisted of a guitar wire that was centered through a section of PVC tubing. Around this tube was wrapped a coil of insulated transformer wire. This was my first ion-valve. It was excited with the same power supply where I had observed the plasma effect several years previous.

I knew that my ion valve was generating high frequency oscillations using air ions but did not find any practical applications for it until six years later. It was in this year (1995) when I realized the importance of the ion valve and its associated high frequency ion field, known as radiant energy to Moray, it being the essential principle behind his energy receiver.

In one experimental set-up, it was confirmed that when a charged capacitor is discharged through a spark gap that the stored energy is transferred by way of high frequency electrical oscillations. It was found that these oscillations occur directly before the discharge of the capacitor, thus the term, pre-glow discharge. It was found that during the pre-glow discharge plateau, energy is transferred from a primary to a secondary electrical coil. Directly after pre-glow discharge, a surge of current is measured. At the point of current surge is where most of the stored energy in the capacitor is released as wasted heat. It was apparent that by maintaining the pre-glow discharge plateau a very efficient mode of energy transfer and conversion can be obtained. Logically what is required is a control mechanism. This is where my ion valve finds its niche. Upon further investigation, it is found that it keeps pre-glow discharge oscillations at their plateau, and suppresses current surge in a spark gap. It is a self-regulating quenching device. When it is placed in series with an air-core transformer and arc gap, its plasma hisses smoothly, the arc in the spark gap is almost silent and is very small. Continuous oscillations can be seen on an oscilloscope. A light bulb connected to the secondary will glow brightly. This result is not possible without the ion valve included in the circuit. The ion valve has the added feature of preventing back electromotive force, generated from inductive loads, from being discharged back through the circuit. Without the ion valve, energy is normally lost when it is discharged and is transformed into heat. Using the ion valve therefore has the effect of conserving energy.

Fundamental Radiant Energy Device

“Standard” scientific principles are not being violated. There is no fringe science involved with radiant energy power generation. This is a very old source of energy being extracted and harnessed in a unique way through my discoveries. What I have discovered is practically a limitless source of energy. Radiant energy has existed since the beginning of time. What I hold claim to is an improved method to generate and to convert radiant energy, kinetically active ions, cosmic energy, call it what you will, into useful electrical power. Think of the radiant energy power generator as a type of energy detonator that liberates great quantities of energy with only a small exciting spark. No laws of physics are being violated. No new laws are being implied. They are being expanded. The concept is not that much different from how a lighted matchstick is able to start a bonfire.

The power generated from my circuits comes from the transformation of matter into radiant electricity. It does not come from the splitting of atoms. To obtain high wattage from a spontaneously radioactive substance would require unsafe amounts of radioactive material.

Under the right conditions, ordinary matter can be made to generate intense surges of radiant energy that can be heard on a radio receiver as static noise. Build a device that can efficiently capture this energy and convert it into useful electrical currents and you will have yourself a powerful source of electrical power. This device will be powered by artificially disintegrating matter as described by Gustave Le Bon in his book “The Evolution of Matter” and in his book “The Evolution of Forces”.

Energy and matter are two distinct entities of the same manifestation. Matter represents a stable condensed form of energy. Heat, light, electricity, etc., are uncondensed vibrations of matter oscillating at differing rates. “Cosmic Energy” is the term that Le Bon used to define matter and energy as being one and the same manifestation. He theorized that when stable matter is disintegrated it is transformed into energy that we recognize as heat, light, electricity, radioactivity, etc.

Semiconductors will generate intense surges of electron oscillations that become powerful sources of radiant energy. A simple **ion valve**, or call it what you will, can be used to generate and convert this form of radiant energy into useful electromagnetic oscillations. A tuned transformer can be used to directly convert these oscillations into to a practical voltage and amperage. This unique valve is shown in Fig. 1. Before it can function it must be connected to a suitable voltage source. The circuit in Fig. 2 demonstrates the full working concept. Other embodiments are also possible. The proof of concept circuit reveals how radiant energy can be generated and converted into useful electrical currents. Many additional stages can be added for more power. Many other circuit and component configurations can also be used but the fundamental conversion principle remains the same. The circuit and components shown should give you a very clear idea of how the technology works. The actual mechanics and electronics of building and validating a radiant energy prototype are relatively simple. Contrary to what some people might think, dangerous levels of radioactivity are never used in my devices.

Ion-valve Converter Technology Explained

The ion-valve converter (ion-valve) shown in Fig.1 has an axial negatively charged tungsten cathode wire that extends the length its cylinder and is capable of emitting secondary electrons. The anode cylinder is positively charged and is made from a semiconductive material that will readily capture electrons.

Within a few milliseconds the accumulated negative ions are attracted to the positively charged onrushing atomic ions. When the negative and positive charges collide they neutralize each other generating high frequency electrical oscillations.

There appears to be a common thread shared between several alternative energy devices. It is the pre-glow discharge. The report on the **Hans Coler** device released by the British Government indicates that there is excess energy released when electrical contacts are opened and closed. The **Lester Hendershot** device utilized a buzzer circuit that opened and closed its electrical contacts. In the **Alfred Hubbard** coil pre-glow discharge flowed through electrical contacts, a distributor cap and radium soaked spark plug. The **Joseph Newman** motor used a sparking commutator. **Thomas Moray** invented a glowing, cold cathode discharge tube that was the heart of his radiant energy device. **Hermann Plauson** was granted U.S. Patent No. 1,540,998 that used spark gaps to convert atmospheric energy. **Frank Wyatt Prentice** was granted Canadian Patent No. 253,765 that detailed his invention, which lighted 50 sixty-watt carbon lamps with an input of only 500 watts. His invention utilized a spark gap driven high frequency tuned resonant system. **Chancy Britten** used ion-valves constructed with a central wire that was surrounded by a coil of wire which is described in his US Patent No. 1,826,727. Britten's valve was said to have lit up his home in the 1930's according to a local newspaper article of that time period. **Alexander Chernetski** experimented with what appears to have been a type of ion-valve that was filled with hydrogen gas. It is said that he got up to five times more energy out of his device than what he put into it. **Edwin Gray** was granted U.S. Patent No. 3,890,548 for his efficient spark gap driven capacitive-discharge motor. He improved on this patent by replacing the spark gaps with a pre-glow discharge switching tube. His U.S. Patents No. 4,595,975 and No. 4,661,747 describes this tube in detail. Gray's patents claim to conserve battery power by sending unused energy back to the supply batteries. On close examination, we also find that his switching tube is actually a quenching device.

Radiant energy was generated during the pre-glow discharge cycle that also contributed to recharging the batteries. **Paulo N. Correa** and **Alexander N. Correa** obtained patents to a pulsed pre-glow discharge system that recovers energy and recharges a battery.

I have found that radiant energy is generated when a plasma field is in contact with the atoms of an electrical conductor. Most importantly, the quantity of radiant energy is greatly increased when the plasma field occurs between the inter-electrode couple of two differing electrical conductors. That, the wattage produced will depend largely on the type of electrode materials that are used. I do not suspect that the above referenced inventors were aware of this amplifying mechanism.



Fig. 1

Ion Valve

In the embodiment in Fig. 1 the negative charge on the wire in the ion-valve negatively ionizes any gas that contacts it. These ions rush towards the positively charged cylinder. When a metal ion that carries an excess electron hits head-on with an elementary differing positively charged onrushing metal ion a violent union of the two metals occurs. This causes the newly formed bimetallic alloy to violently oscillate, break up (dissociate) and to liberate a burst of electrons. The **"sea electron model"** helps to explain this effect. According to the sea electron model metals are bonded to each other through electron sharing. The model suggests that metal atoms be bathed in a sea of valence electrons. If this model is taken one step further it can be seen that when metallic atoms are dissociated from each other excess electrons are released in the form of electrical oscillations of high frequency (radiant energy). This occurs because the electrons no longer take part in the inter-atomic binding force that existed before the dissociation took place. It becomes clear that the freed electrons will add amperage to the output circuit to which it is connected. Henceforth, the equation **I x E = P** holds true in this system. Where, "I" represents the electrons (amperage), "E" electromotive force (ionic voltage), and "P" the power generated.

Obtaining Electrical Energy from the Transformation of Cosmic Energy

Matter is cosmic energy in a condensed state according to Le Bon and Moray. What this means is that matter can be excited its plasma state and caused to rapidly disintegrate transforming itself into electricity.



Fig. 2

Proof of Concept

The proof of concept shown will obtain energy from the dissociation of matter bringing the circuit to life. It does this by creating a plasma field between differing electrical conductors. Electrons are unleashed and feedback to the circuit where they are converted into useful power.

> ***the excited fourth state of matter (plasma) causes condensed energy (solid matter) to become uncondensed (radiant energy). The reaction will be far superior to the force that invoked it in the first place because the energy stored in matter is released***

Plasma oscillating on the correct wavelength will act like a spark on a mass of explosive material but releasing electrical particles instead of heat. This is to say that the excited fourth state of matter (plasma) causes condensed energy (solid matter) to become uncondensed (radiant energy). The reaction will be far superior to the force that invoked it in the first place because the energy stored in matter is released. The energy that is condensed in the elements of matter is immense. The result is that an enormous amount of energy is released with only a slight loss of matter. Gustave Le Bon proved this when he demonstrated that the action of solar light and from electric arcs on bodies produced electric particles similar to those of uranium. He showed that it caused all bodies to disintegrate to different degrees.

According to the law of conservation, when we give to a material body a determined quantity of energy, this energy might be transformed, but the body will never give back a quantity in excess of what it received. This principle is considered too self-evident to be disputed. It makes sense that matter can only give up energy that is given to it and is unable to create excess energy. Without violating this law, matter can be excited into giving up its stored inter-atomic energy. Condensed matter can become uncondensed if its oscillations become violent enough and henceforth transforming itself into radiant energy. No laws have been violated. They have been expanded. The first law of thermodynamics describes the principle of the conservation of energy. It states that "energy is not created or destroyed; it merely changes form". The fact is that the creation or destruction of energy is a result of matter being broken down or built up. They both go hand in hand.

Naturally occurring radioisotopes were created through the billions of years of **cosmic ray** bombardment of ordinary matter. Their matrixes became unbalanced. The correct trigger will cause these isotopes to seek their original balanced state. Enormous amounts of electrical energy can be obtained from the transformation of stored cosmic energy. These isotopes contain a very old energy reserve that can be released in a unique way with my discoveries.

Have you ever wondered about spontaneous radioactive decay? Is it really a super charged state of matter? If an atom can become ionized by either gaining or by losing electrons then why can there not be a nuclear ionization too? I hypothesize that atoms do become ionized on the nuclear level by gaining or losing neutrons. This may appear incidental but could be at the very heart of an ultra-chemistry. It is highly probable that this hypothesized phenomenon is behind natural spontaneous radioactive decay and explains many unanswered questions about nuclear science.

Liberated Energy

With a slight excitement from a pre-glow discharge in a spark gap, or even with no excitement at all, as we observe in spontaneously disintegrating radioactive bodies, such as U235, we can obtain large quantities of energy. Clearly, we did not create this liberated energy, since it already exists in matter, but we release it under the right conditions. This is being done without violating the law of energy conservation. The idea that matter could be transformed into energy was absurd before the acknowledgement of nuclear transformations.

A Nu Science is on the horizon. It involves the means of transforming matter into energy without splitting atoms. This science recognizes several isotopes of matter that spontaneously liberate energy as observed in naturally occurring radioisotopes. My research indicates that it is also possible to artificially speed up the natural decay process of condensed energy (matter) using a minute plasma field, as from a pre-glow discharge, etc… With a very small quantity of energy, we will be able to produce a very large quantity of energy without splitting the atoms.

Capture Capacitor

Nature offers us cosmic energy that manifests itself in many different forms. Electricity is only one of its manifestations. From this knowledge, we can obtain electrical power with no moving parts. The natural world contains many storehouses of this cosmic energy. Energy is all around us just waiting to be transformed. The capture capacitor is one such example. It is called a capture capacitor because it captures and transforms electrical charge into electrical current. It does this with the aid of naturally occurring radioactive matter (N.O.R.M.). Put a pair of dissimilar metal electrodes together with a porous ceramic dielectric material sandwiched between them, along with a weak electrolyte and you have built a capture capacitor. In a low power capture component there exists a minute impurity of N.O.R.M. It is always present in clays and is usually present in ceramic materials.

If you want a capture capacitor to generate more power all you have to do is to add additional amounts of radioactive material to the dielectric. Lead–210 is the optimum choice because it has a half-life of around 22.3 years and is a pure beta (electron) emitter. Its half-life is almost twice as long as tritium. This means that it is feasible to build a component that will put out power for several years with little maintenance. Lead-210 is a decay product of radon gas. The parent source of radon is uranium. Therefore, uranium ore can be powdered and mixed into the ceramic material.

The atomic ions emitted from naturally occurring or artificially induced radioactive transformations can be directly converted to electrical power. The circuit shown can be used to convert radiant energy into useful electrical currents. Additional stages can be added for more power. The circuit shown gives a general idea of how such an energy conversion device functions. By no means is this technology limited to this one circuit, configuration, or source of radiant energy.

EAGLE-RESEARCH
Energy Solutions
since 1984

A Research Organization that
Develops & Distributes
Practical Energy-Saving
Methods & Devices

4 Energy Way, P.O. Box 118
Porthill, Idaho 83853
FAX: 250/492-7480

Technical questions to:
wiseman@eagle-research.com

NEWS REVIEW

◆ A new type of high field superconducting magnet from Oxford Instruments has enabled physicists at the University of Nottingham to balance the force of gravity and levitate heavy and dense materials such as lead, gold and diamonds. The patented Minimum Condensed Volume™ (MCV™) Cryofree™ superconducting magnet, developed and manufactured by Oxford Instruments in collaboration with the University of Nottingham, is the first of its kind in the world. Unlike conventional superconducting magnets, the MCV magnet never needs to be refilled with liquid helium and yet can generate a field over 300,000 times stronger than the Earth's magnetic field. MCV has a very small footprint and, operating at 4.2 K with a room temperature bore, can generate highly stable magnetic fields up to 16 Tesla.



http://www.oxford-instruments.co.uk

◆ Polish inventor Zygmunt Orlowski called attention of the scientific society to his perpetual motion machine **METOZ**, which according to the author after further improvement will be able to extract energy from the earth's gravitation.



http://www.nets.pl/~metozor/perpetual_motion_machine.htm

◆ It is necessary to change behavior of people in order to decrease environmental damage. This was the message of **"Green Week 2003"** which took place since June 2 through June 5 in Brussels.

The conference's key issues were three aspects of United Europe environmental policy: sustainable production and consumption, renewable energy and water supply.

Green Week is the first environmental forum of such a scale. Three thousand participants from all over the world represented governments and funds, industry and mass media. The exhibition organized in the framework of Green Week included 62 displays from 14 European countries and were dedicated to the newest environmental technologies and projects. During the Green Week 26 conferences and seminars took place, as well as a great number of press conferences and actions for young people.

◆ **British researchers (**Gardner Watts company) **believe that they have made a groundbreaking scientific discovery after apparently managing to "create" energy from hydrogen atoms.**

The device represents "thermal energy cell" which appears to produce hundreds of times more energy than that put into it. If the findings are correct and can be reproduced on a commercial scale, the thermal energy cell could become a feature of every home, heating water for a fraction of the cost and cutting fuel bills by at least 90 per cent.



http://www.telegraph.co.uk

◆ **Gravity Conversion Rotary Device**

The below figure is from http://www.theverylastpageoftheinternet.com/newclaims/GravityMotor/gravity_motor.htm



Does it really work?

THE MARCUS DEVICE CONTROVERSY

Tim Ventura, USA

Email: tventura6@attbi.com
http://www.americanantigravity.com
http://www.americanantigravity.com/marcus.html

Editorial: This overview is devoted to the fantastical device created by inventor Marcus Hollingshead that encountered more than its share of publicity and controversy between November 2002 and March 2003. You can participate in discussion on aggroup@yahoogroups.com.

The problem with Marcus has been that he was pressured by too many people to produce too fast results. I started talking to him in November, and he is always sounded like an honest, rational man with a good heart. The problem is that once people started to hear his private claims that he could lift something like 2 tons of weight, things kind of went south.

While people in general have been very well-meaning, they are desperate to solve many of our current energy-problems, and when Marcus appeared with a potential solution it got out of control. Pretty soon film crews were showing up at his house unannounced, and he was getting unwanted phone calls from people who had looked up his number online.

In my opinion, it is really a problem of a "social dynamic" at work here – too many people, with too much access, all at once. This also correlates to the type of person that different people are. For instance, I am a very open person, and I really do not value my privacy a heck of a lot — therefore, when TV crews drop by with 5 minutes notice (and they have), I tend to just let them in for a demo. However, Marcus, who is much more of a private person, seems to have become a bit overwhelmed at this proposition.
Also, keep in mind that I had initiated working with the media because I felt that it was time for the excellent work in the Lifters groups to see the light of day. There was some debate about this, but the Lifters group as a whole has greatly benefited from being about to tell people about this new technology.

Marcus had not actually "gone public" about his work. He had leaked information about his research to a few people, and from there it was leaked to several others, who in turn told their friends about it. Unlike the Lifter technology, which has hundreds of people that can talk about how it works and where it came from, Marcus technology was represented solely by himself. That means that everything surrounding his device came back ultimately to him alone. Without any real group ownership of the expertise behind the device

As I said before, Marcus was new to the publicity, and did not have time to prepare the resources that the rest of us have had to answer questions, provide demo materials, etc. Naudin and Saviour have a masterful manner with regard to teaching people about Lifter technology, but they have had years to prepare this information and perfect a method of presenting it to people.

Most of us in the AG groups tend to proselytize for the technologies that we believe in. I know that I do, and if you haunt the newsgroups much you will notice that everybody there believes in something and can go on for months non-stop telling the world about it (again, I do this). Marcus, however, does not really have this personality — he is more of a "take it or leave it" type of person.

For me, this was another indicator that he was the "real deal". You have to understand that I have never seen working prototype pictures of the Marcus device, and all that I had to go on was the feeling that I got from interacting with him on the phone and online. The fact that he did not try to "sell me" on the idea was a big plus. He told me about the device, and his story was always consistent. The other people that he talked to also had a consistent story – I have not talked to anybody and heard a different version than I heard from Marcus himself. That is a big plus from the credibility perspective.

Marcus initial goal (from when I started talking to him in November) was to gradually ease into working with the public to tell them about the technologies he was working on. Unfortunately, I probably aggravated the issue a great deal, because his early descriptions of the technology might have gone unnoticed if it had not been for some of the things he had mentioned about his research.

When I read Marcus' firsts posts on the device, my very first thought about his claims was that they were bogus. Judging from the reaction of the Antigravity newsgroup, I gathered that a few other people also had the same initial reaction. The reason might be a little selfish – after you hear claims but do not see results for a long enough period of time, you tend to protect yourself emotionally by becoming skeptical to the idea that somebody can be lifting hundreds of pounds of weight using a completely new and revolutionary technology.

Nonetheless, something that Marcus had said resonated with me. I remember that he was talking about his results being based on a study of the Earth's fields, which is something that I had read about myself during the college years. Telsa had done a lot of work involving the Earth's electrical and magnetic-fields, and I had always felt that this research might come in handy later as a potential basis for Antigravity research. However, I did not have any specific ideas, and began asking Marcus questions offline to find out more about his research.

In reality, I am nobody special, so I think that perhaps this would have happened in any event no matter what my reaction would have been. Certainly I am not the only person that took an early interest in his work, and from what I learned later he had already been a little bit too honest in the BBC online newsgroup before he ever became involved with the Antigravity newsgroups.

From January to mid-February Marcus became like somewhat of an addiction in the newsgroups. This was a strange phenomenon to watch, but if he did not answer questions in the newsgroups for even a day people started asking whether he had been kidnapped or the government had assassinated him.

You have to understand that most inventors tend to segregate their time into "public" and "private". I do, Naudin does, and everybody does this. When you talk to the public about what you have built, you really get into it — but when you are actually working on it, you tend to hole up in the garage and put the entire world on "ignore" until you have finished with whatever it is that you are doing.

Marcus really started to get publicity in late November 2002, and it built up over a few week period of time. By mid-December, he had a healthy following in the Antigravity newsgroup and people in the 5 or 10 other AG newsgroups were developing more than just a passing interest. Great stuff for Marcus – he had thought that he was the only person doing this research, and it turned out that lots of people shared this common interest with him. We had lots of really valuable and productive exchanges.

Marcus bided his time working on the projects – he had initially stated that he could lift around 200 pounds of weight with his November version (prototype #161, if I remember correctly). He did not have a digital camera, and he did not want to publish photos until he had a better prototype anyways. That was OK with me – I am used to work with a variety of inventors and came to realize a long time ago that everybody has their own style. I was content to wait until Marcus had additional data, and the only thing that I insisted upon was that sooner or later he ante-up and provide some photographic evidence.

Despite lacking photos or video evidence, Marcus did have documentation. In fact, he wrote more documentation about his device than I had ever hoped to receive. He cranked out about the equivalent of 30-pages of "real" documentation in a very detailed form within 1-month, and had the email equivalent of many more pages in postings about how the device worked online. Marcus had already been publishing details online for about 2.5 months.

Despite the incredible amount of published data that Marcus was able to complete, in some ways it made things worse for him than not having anything at all. The reason was the nature of his research. My work, currently focused on Lifters, was in a technology that is easy to explain – the device is built like this, it works like that, and it can be described in a manner similar to some other thing ....basic, easy to explain, and easy to compare.

After all, Lifters have been accused by science of being ion-wind devices. If nothing else, rebutting this claim gives us someplace to start – something to compare against to provide people with an idea about how the device works. Additionally, we had tons of video and photographic evidence to back up our claims. In Marcus case, the documentation that he provided made things worse because his technology is so utterly different. It is not ion-wind, nor the Biefeld-Brown effect, nor apparently the Searle effect. In fact, the more than you tried to pin down exactly what it was, the harder it became to describe it.

Also, its not like he could simply fall back onto describing the construction of the device **– reason being that it contained a series of interrelated coils with a unique configuration that were intrinsically tied to the operation of the device.** Every time he wrote a detailed summary of the construction of the device, we had come away with more questions than we had started out with. After a time I gave up trying to understand how it was constructed, because I only had bits and pieces.

Marcus was using an arrangement of 6-coils, and what are described as "bifilar windings". Essentially, this means that you wind two wires together around a coil and then tie one of the ends to another, making the two wires essentially one long wire wound "against itself" down the length of the armature its on. There are 6 of these armatures on the device, mounted around a central RP (or reference point).

Marcus created all of the terminology for these parts – this lends additional credibility to the idea that he had had 7 years of experience with it. These are ideas that you just do not "make up" for publicity. For instance, the bifilar windings on the armature-coils are self-cancelling fields, and even a basic-electronics education will tell you that. However, the interesting thing is that once you really start to get into the advanced "post-scientific" research on magnetic fields you start to see self-cancelling magnetic coils all over the place. The reason is apparently that while the "B-field" *(Editor: i.e. magnetic field)* of the coils cancels, the "A-field" *(Editor: i.e. vector potential)* that Tom Bearden keeps talking about does not, which means that you can isolate the really interesting effects from the coil without having to deal with the high field-intensity effects from normal electromagnetism.

Marcus had described these six armatures as being activated in a series, or order, to obtain results. Each of the coils was spun by an electric motor mounted on the armature, and when the coil was spun up to a certain speed and "stubs" mounted a periodic intervals on the side of the armature were fired in sequence the antigravity effect was created.

Marcus Antigravity effect was a directional force that was applied in a unique manner depending on which coils were activated. This means that by activating (for instance) coils 1 and 3, he could create an antigravity effect and move the device left – or something to that effect. Turning on and off each set of coils gave him movement on one axis of thrust, which corresponded to X, Y, or Z in a standard 3-D geometric graph. Since you can move in either direction down any given axis of thrust, this means that you have 6 axis of movement height (up and down), width (left or right), and depth (forward or backward). His device provided movement on any axis by either one coil or an arrangement of coils.

For a while Marcus did not want to talk about side effects, but I pressured him into it. The reason was that I have seen side-effects that were pretty darned strange in a number of different experiments, and I was willing to bet that if I pressured him a bit he would talk about what he had seen but did not want to reveal (for fear that people would not take him seriously). It turns out that I was right.....

Marcus had talked about the RP, or "Reference Point" upon several occassions. This is a multi-layered device that acts somewhat like a capactive element. It sits in the direct center of the Marcus device, and it is the reference-point for the entire device. The RP is manufactured from cast-iron, and Marcus says that he has a local company build them for a few bucks each by pouring iron into a mold based on one of his designs.

You can active the RP at the same time that you activate the coils. You have coils rotating around the RP, with "stubs" on the coils firing periodically at points corresponding to spots on the surface of the RP. Meanwhile, you also have an electrical charge on the RP itself, which means that there are a lot of elements interacting at once to create a very complex dynamic.

One of the interesting side effects was a darkening and "blurring" effect of the RP, as if light was being reflected off it. Another was a Star-Trek like "force shield" around the RP. These only occurred when all of the coils were activated at once. Also note that since the coils are opposing in nature (one for each direction on each axis), that when you are creating the force field effect the device cannot be levitating. However, the device is operational, and you have a force-field that you can apparently bounce a heavy hammer off without being able to penetrate it (Marcus description).

Another interesting note is that the force-field effect can be modified to create a vacuum. I am not sure how

Marcus noticed this, but he had said that it appeared to create a vacuum inside of the field's boundaries during operation. Interestingly, it also ran very cold – apparently down to a hundred degrees below zero, but only within the localized boundaries of the field.

I am not a professional physicist, but this is something that has been reported with the Searl effect and several other experiments, and the reason that I believe it occurs is because you are taking the kinetic energy of the device as well as some of the kinetic energy of its molecules (i.e.: heat energy), and injecting it into another dimension. After all, anytime we directly modify a gravitational field we are creating a dimensional effect, but in normal life we do not notice it because the boundaries between gravitational fields are very gradual.

the energy input is used only in putting the device into another frame of reference, but that any interaction between us and our "normal" frame would have to be modified for any interactions with the "modified" frame.

Well, in the Marcus device the boundary between gravitational fields is not a several thousand mile-long gradient like the Earth's field is – instead of you have a gradient perhaps 10-times more intense focused within a 3 to 4 inch area. That means that you are creating essentially a rift in time and space (self-healing) that is kept open by the energy that you are pumping into the device.

To the best of my knowledge, this is the most accurate description that I have seen yet for why his device does this. Marcus himself could not explain why these effects occurred, and to be honest I scared him more than a little when I told him my theory.

In the hypothesis that I just put forth on the origin and functionality of the Marcus device effect, the interesting this is that there really is not a direct correlation between input energy and the effect itself. That is because you are not using the input energy to actually cause an effect – you are essentially using the input energy to translate the device into another dimension (although it is still partially within ours).

Einstein called these "frames of reference". The idea is that the energy input is used only in putting the device into another frame of reference, but that any interaction between us and our "normal" frame would have to be modified for any interactions with the "modified" frame.

Again, this takes place in normal physics – but usually it involves motion, and normally it takes place over a vastly larger gradient of time/space/whatever. The difference between two frames is the difference between two locomotives moving at different speeds – the energy input goes into accelerating each locomotive up to that speed, but the actual work is performed if those two trains interact is solely a product of the frame of inertial reference (mass & velocity = energy).

Another excellent example is a helium-balloon. You put the energy into condensing the helium and pumping it into the balloon, but it is not the helium that creates lift – it is the surrounding atmosphere. In a very real sense a helium balloon gets its energy from the surrounding environment. The energy that you put into "maintaining flight" in a helium balloon is only the strain on the fabric used in holding the helium into the confines of the bag that encloses it. With the Marcus device, I would bet money that it is not the input energy creating these effects – it is instead the difference in frames of dimensional/inertial reference between "our" environment and the "device's" environment, whatever that difference may be.

You see, even though this sounds like a load of BS, magnetism is not real. This is not an idea that I am making up – in fact, it is an entire chapter in the physics 101 textbook kicking around downstairs in my house. Take two magnetic fields, and project them in the same direction at the same speed. Field A can not interact with Field B, because neither of the fields really exists – they are merely ripples on a pond, and that pond is the background of the time-space continuum. People that believe in relativistic gravitational effects take for granted that things like this happen – after all, gravity is not a force per se in relativity – only a modification of the dimensions of time-space. Well, most people do not realize that Einstein based his theory of gravitational force on his study of magnetism. Magnetism is the same thing – it is a modification of the fabric of time-space.

Take two magnetic fields that did not interact from a moment ago, and now change the direction that one of them is traveling in. Suddenly, the two fields that could not even see each other a moment ago now create an incredible "torque" – this is the same thing that we see in bar-magnets and electric motors. This is the "torsion field" research.

Bar magnets are different than pure fields because they are composed of the discrete fields of thousands of tiny magnetic "domains". That is why the fields from bar-magnets are never "invisible" to each other – it is because that the fields in bar magnets are too jumbled to ever really "line up" to the point of being invisible. Pure fields can do this, however, reinforcing the supremacy of Einstein's relativistic effects with relation to electromagnetism.

Anyhow, that is about it for now – I will try to come up with a more detailed picture for you on this if you like, but I expect that you will probably have more questions about Marcus theory and device in near future. It is a very complex idea underlying his research, but the basis of it is the idea of "rotating magnetic fields".

If you want to do additional research on your own into related fields of study, I would definitely look up "relativity and magnetism" – it provides an excellent example of how to visualize relativity theory in the study of magnetic field interactions. This is something that electronics engineers are not taught, which is why you have never heard of this in an engineering sense before. However, in physics is a well-known concept, although most physicists prefer to work with quantum mechanics rather than relativity these days.

In terms of rotating magnetic fields, you can look up "torsion fields" – again, the Russians have the best understanding of advanced torsion field physics, although their best material probably has not been translated yet. Additionally, rotating magnetic fields are the basis for the Searle Effect and the Hamel device.

Marcus was intrigued by Searle's claims, because they appear to have matched many of his own results. Interestingly, Marcus had developed his work within an "intellectual vacuum" and had never heard of Searle before I told him about the similarities. Nevertheless, force-fields, ice-cold operating temperatures, and antigravity seem to be a pervasive similarity between all manners of experiments that have been reported using rotating magnetic fields. I had assumed that Searle's claims were bunk, but after hearing about similar effects from Marcus research it led to reconsider some of the criticism surrounding Searle lately.

One a final note – one group that may lend additional credibility to this research is Godin and Roshchin in Russia. They obviously benefit from the years of knowledge that the Russians accrued in magnetic field systems theory, and they attempted a replication of the Searle effect device some years back (and claimed to get some results). I hear that they have been working on a revised version of their experimental setup recently and hope to have even better results in the very near future.



Fig. 1

Magnetic flow for a bifilar-wound toroid that is split at four points on the toroid. This configuration occurs when the coils in the nubs are charged to match the charge on the toroidal coil. The configuration is a quadra pole with a minimum magnetic field at the center

Fig. 2

Marcus recommends the Kikusui 6000L and 18000L multipurpose AC power-supplies



Fig.3

A scale-model mockup of the ring-arrangement within the Marcus device, showing the interlinking coils

History pages

Systems of conversion of thermal energy to mechanical one

Review prepared by correspondent Alla Pashova, **Russia**

There is a wide class of closed-cycle heat engines using differential temperature of water and ambient air. This kind of systems enables thermal energy to be directly converted to mechanical one so as to perform a useful work. We publish patent specifications of two analogous devices of this kind.



PATENT FOR INVENTION

Specification

of the engine, which uses differential temperature of water and ambient air.

To the patent by **P.I. Dobrokhotov** filled on October 22, 1928 (#34248).

Patent grant is published on March 31, 1930.
Patent is valid during 15 years from March 31, 1930.

In 1928 **P.I. Dobrokhotov** proposed a design of such an engine. It represents an endless chain thrown over a pair of blocks and partly immersed into water. The chain consists of coiled pipes filled with a volatile liquid (such as sulfurous anhydride or ammonia). One end of each coil is fastened to a frame, while another end is fastened to a cylinder piston mounted on the same frame. When overwater elements are heated by means of ambient air, the liquid inside the coil evaporate. Vapor put pressure upon the pistons which being in motion compress air in the cylinder, and thereby reduce volume of each element. When submerging, the element gradually cools down, thereupon causing a decrease in pressure of vapor of the liquid, which is enclosed within coils. The pistons move in backward direction, and the volume of air available inside the cylinder increases. Increase of volume results in increase of water buoyancy force that sets the device in motion.

In 1980, **Y.S. Grigoriev** developed his forerunner's idea by improving the system described above. The inventor aspired to enhance the effectiveness of this method of conversion of heat energy to mechanical one. He suggested fixing the volume of chambers filled with a heat-sensitive actuating medium at its minimal magnitude before immersing of those chambers into warm water. In water the actuating medium heats and partially evaporates. At a maximum depth of submersion, the chambers are released from fixation to be expanded during emersion. Thus one may avoid expansion of the chambers during their submersion. Futhermore, there is a possibility to activate the device and get the useful work without preliminary spinup from an external drive.



INVENTION SU1404681 A1

23.06.88
Yu.S. Grigoryev
Prototype: USSR patent #13534
F 03 G 7/06, 1928

Iliya R. Prigozhin

(25 January, 1917 – 28 May, 2003)

Iliya R. Prigozhin, aged 86, Nobel Prize Winner, Belgian scientist of the Russian origin, died on 28 May in Brussels. Prigozhin made a number of prominent discoveries in the field of thermodynamics and statistical mechanics of nonequilibrium processes. In particular, he developed a concept of irreversibility as applied to thermodynamics. Prigozhin was studying time as a physical phenomenon. In 1977, he was awarded the Nobel Prize for chemistry "for works on thermodynamics of nonequilibrium processes".

The scientist formulated one of the major theorems of the theory of nonequilibrium processes. This theory was later named after him. According to Prigozhin's theorem, stationary state of the system corresponds to minimal entropy generation. The outstanding physicist was also an initiator of applying methods of theory of nonequilibrium processes in biology.

Thermodynamics principles were enunciated in the middle of the XIX century after the invention of a steam-engine, when interaction of heat, electrical, and mechanical work aroused a higher interest. In accordance with the first law of thermodynamics representing an energy conservation principle, energy neither disappears nor appears in any closed system, but transforms from one form to another.

The Prigozhin's theorem sounds as follows: stationary state of the system (under conditions impeding attainment of equilibrium state) corresponds to the minimal generation of entropies. If there are no such impediments, then production of entropy reaches its bare minimum, i.e. zero. The theorem was proved by Prigozhin in 1947.
In thermodynamics the nonequilibrium specifically open systems were of most interest for Prigozhin. In such systems either or both (matter and energy) interchange in reactions with an environment. At that, quantity of matter and/or energy increases or decreases in the course of time.

It is obvious that human society as well as the biological environment is an example of dissipative and nondissipative structures. In the 60s and 70s, Prigozhin developed his theory of dissipative structures and described the formation and development of embryos. Critical points of bifurcation in his mathematical model are correlated with a point, where a biological system becomes consecutive and stabilized.

For his scientific career time, the physicist was awarded over 40 scientific rewards and admitted as an honorary member into national academies of many countries all over the world.

◆

New Energy Technologies

PRINT EDITION ADVERTIZING RATES

Full Page Ad
B/W - $400
Color - $800

Half Page Ad
B/W - $200
Color - $400

Quarter Page Ad
B/W -$100
Color- $200

New Energy Technologies is distributed in the leading Scientific Laboratories in Russia and has subscribers in more than 20 countries all over the world

To advertise contact us:
Faraday Labs Ltd, Phone/fax: 7-812-380-3844
http://www.faraday.ru, office@faraday.ru

Russian Academy of Sciences
Russian Physical Society
Nuclear Society of Russia
Mendeleev Chemical Society of Russia
Moscow Lomonosov State University
Russian People's Friendship State University

The 11th Russian Conference on Cold Nuclear Transmutation of Chemical Elements and Ball-Lightning (RCCNT&BL-11) is to be held during September 28- October 5, 2003. The place of the Conference is in Dagomys near the city of Sochi.

The program of the Conference includes the following subjects:
- Experimental research in cold nuclear transmutation (fusion) and ball lightning;
- Theoretical models with respect to cold nuclear transmutation (fusion) and ball-lightning effects;
- Applied to these problems technologies and devices.

The Organizing Committee of the Conference is pleased to invite you to attend the Conference. The terms of your participation are as follows:

The full cast is $900, which will include the registration fee, hotel reservation and living, three daily buffet meals, conference proceedings, transportation from the Sochi airport and back, social dinner and special excursion or entertainment.

The languages of the Conference are Russian and English.

The total cost can be reduced to $800 if transferred before August 10 to the account of the Organizing Committee, which is to be announced on having received from you a confirmation about your decision to attend the Conference.

If you make a decision to take part in the Conference, please, let us know before July 1 about the title and abstract of your report.

Contact telephone: (7) (095) 196-9476 (ask Mr. Igor Goryachev), Fax: (7) (095) 196-6108
Email: gnedenko@kiae.ru; Bazhutov@erzion.madi.ru; bazhutov@izmiran.rssi.ru; bychvl@orc.ru
Address: I. Goryachev, Russia, 123182 Moscow, 1 Kurchatov Sq.,
Research Institute of High Technologies at RC "Kurchatov Institute"

Letters from our readers

Thank you for publication of my article. Your magazine becomes more and more popular.

My special thanks to Editor-in-Chief Alexander V. Frolov. Whatever they say or write in the press, he has done a great work and it is not only my own opinion. He has managed to do that everybody had been waiting for a long time. My colleagues (not only from Rostov-on-Don State University but also from other Rostov Institutes of higher education) ask me personally send the best regards to the editorial staff of your magazine.

Sergey A. Gerasimov

Free energy?

The scientific community says that it cannot exist. Where did we hear that before? Academician Valery Sobolev from the Academy of Sciences, the head of the research group working on the experiment says: "This is not some new physics, but just experiments that have been performed very seriously. Make surge of electrons from the environment, remove them, deplete the fused electrolyte with basic typical metals; what you derive from it is what cannot be produced by chemical methods. This is a new state of substance." As the researchers say, first they discovered a particular electrochemical process where high-temperature materials in a new state are the product. This in its turn allowed to discover a new state of substance, new class of materials, a new source of energy, a new method of cold plasma generation, a new superconductor. See whole article at: http://english.pravda.ru/science/19/94/379/9675_energy.html

Josef Hasslberger

Personal home page on physics, energy technology, social and economic issues: http://www.hasslberger.com

Interference disc generator with permanent magnets

inventor Alan Francoeur, Canada


Carl Reich
Bud Johnson

Vortex heat pump



Efficiency 200% and more!

Inventor: Vladimir Susorov
(812) 342-2652
8-901-976-5151
susorow@rol.ru



ISSN 1684-7288

Gravity-heat power system





Author: Vladimir Sukhanov Wladimir.Sukhanov@soros.ksu.ru

ISSN 1684 - 7288

New Energy Technologies

Published by Faraday Lab. *Special Christmas Issue #5-6, 2003*
Research on advanced aerospace systems and new energy sources

In this issue:

- atomic hydrogen in power engineering
- magnetic generators
- capillary perpetuum mobile
- Hutchison effect

Photos from Faraday Laboratory:
test bench for measuring the effectiveness of
hydrogen dissociation and recombination processes



Bogomolov's Invention

Over-unity from elastic forces of spring, compressed by rotation.

Read in this issue!



Spin Wave Laser of Ines Espinoza, USA



Spin Wave Technology
INITIAL RELEASE

George J Bugh



Precession
N
Spin
S
Electron Symbolic Diagram



NEW ENERGY TECHNOLOGIES #14-15

1. News from our company
2. Novozhilov's motor, Y. Novozhilov, Russia
3. Self-action in the case of magnetic rotation, S. Gerasimov and others, Russia
4. Capillary motor, I. Elshansky, Russia
5. Gravity-heat energy system, V. Sukhanov, Russia
6. Modern perpetual mobile, Review
7. Free energy and antigravitation, (spin wave lasers), Ines Espinosa, USA
8. Mechanical analogies, Y. Ivanko, Ukraina
9. Cell of fine-plasma electrolyses, Ph. Kanarev, Russia
10. Smith Generator, Review.
11. Strategy of Over-unity Devices Marketing, R. Wood, USA
12. Hutchison effect, Mark Solis, USA
13. Heat energy conversion by means of non-linear dielectric, A Ries and others, Brasil
14. Gates motor, A. Akau, USA
15. "Cold electricity", A.Akau, USA
16. Gravity conversion rotary device
17. Torsion technologies, China
18. News
19. Antigravitation, B.Smith, USA
20. Electric levitation, MacLeod, Canada
21. Perpetual mobile, V. Likhatchev, Russia
22. Interference Generator, A.Francouer, Canada
23. New Paradigma of Time, D. Reed, USA
24. On the rotating permanent magnet system, A.Frolov, Russia
25. Inventor's week, USA
26. Patents on inertial drive topic
27. Bogomolov's experiment with spring drive, Russia
28. History of perpetual mobile
29. Tesla Energy Science Conference, USA
30. Perendev company, Review
31. Internet pages about free energy
32. Matveev's electrical generator, Russia
33. Perpetuum motor with magnets, France
34. The most interesting of 2003
35. Hydrogen power engineering, Review
36. News on hydrogen fuel cells
37. Electric discharge as part of the over-unity device, Review
38. Subscription page

Faraday Lab News

One of the most interesting research projects of our company in the year 2003 has been the research on hydrogen dissociation and recombination processes. It has taken us about half a year to build a special vacuum tube and in October, 2003 we obtained some experimental results on the heat output and efficiency of the system. The system we designed in our laboratory is shown in Fig.1 and also on the cover. The water-cooling system and the heat measurement system make it possible to measure the heat output within the range of 100 W to 5 kW with pinpoint accuracy. In the year 2004 we are planning to go on with our research work.



Fig.2

We have completed the second stage of designing and developing a high-efficiency magnetic generator with the neodymium permanent magnets of 1.25 Tesla. We confirmed the possibility of double output increase from the usage of two magnetic induction counter fluxes produced by the two coils wound on the generator core (Fig.2).



Fig.1

Our laboratory continues designing and perfecting a powerful "alternator"-type generator with permanent magnets and a drum-type rotor. We will give our readers more detailed information after we are aware of the patent examining result.

Our research on "The Control of Temporal Characteristics of Physical Processes by means of Ether Energy Density Change" is also awaiting the results of the patent examining group. This research on time and the construction of the "time machine" is not a pure theory but it has quite real prospects of being applied to the aerospace industry as a propulsion method.

It is worthy to note that now the alternative energy prospects in Russia do not entirely depend on financial factors. The cooperation is important between researchers, investors and organizations interested in the innovative development of Russian industry rather than in the development of Russia as the world primary natural resource is also important. Progressive political and public organizations should develop and introduce alternative energy programmes as well as render support to local researchers. The successful innovation of new technologies is impossible without this support and lobbying government. Let us hope that the year 2004 will bring along new opportunities and promising contacts.

Alexander V. Frolov
General Director Faraday Laboratory Ltd
http://www.faraday.ru

Novozhilov's Motor

Yury N. Novozhilov, Russia
Bratislavskaya Str., 25-6, 390035, Ryazan,
Tel.: (80912) 72-12-72

An interesting but a very simple motor has been designed. It operates on the basis of heating differences of its components due to temperature variations of contacting environments or due to variable radiation intensity.

Motor structure

The motor structure (see Fig.1) includes a metal or plastic wheel (1). In the center of the wheel there is an axis (2), on which spoke ends are fixed (3). Other spoke ends come through a hole in the wheel rim. On the spoke end there are weights, for example, in the form of small balls (4).



Fig.1
Motor

The structure peculiarity is preconditioned by a loop-shaped part placed on each spoke (5), which has a form of a metal strip or core. An arched bimetal component is built in the center of each loop-shaped part (6). Joints can be fixed at the joining point of loop-shaped parts and spokes to simplify the motor movement (7).

In the motor structure described arched bimetal components become straight when heated. The motor axis ends are placed in bearings (8).

To initiate the motor movement the loop-shaped parts need to be in mediums (zones) with different temperature. For instance, the lower part of the wheel may be placed into hot water (9) and the upper part will stay in the air (10).

Motor operation

When the motor is in a medium with identical temperature, for example, in the air, the temperature of all bimetal components will also be the same; therefore, they have identical form. In this case all spokes will similarly project over the wheel rim and all weights have similar distance from the wheel axis.

This state makes the whole system balanced and immovable. But if the motor wheel is partly placed into water with the temperature exceeding that of the ambient air **the bimetal components in water will become straight and shift the axis weights from the wheel axis.** This phenomenon initiates motor operation.

Let us consider this process in more detail.

On touching water, the bimetal component in the loop-shaped part becomes straight and shifts a weight from the wheel axis. The wheel becomes unbalanced, obtains torque and turns clockwise. This rotation makes the following bimetal component on the next loop-shaped part of the following spoke touch water. This bimetal component also becomes straight and shifts a weight from the wheel axis, generating an increased torque that turns the wheel clockwise.

At the same time a bimetal component comes from hot water on the left side of the wheel in zone “A”. The component cools and restores its initial form, i.e. it curves more and pulls the weight on the spoke to the rotation axis. This leads to a decrease of its counterclockwise torque that affects the wheel.

The loop-shaped parts on the left side (A) and the right side (B) of the motor wheel will cause asymmetry in the number of weights projected by the spokes. On the motor left side (A) the weights will be projected from the wheel axis when the spokes are located in corner “C”. On the right side (B) the weights on the spoke axes will be shifted from the axis when the spokes are located in corner “D”. Fig.2 shows that corner “D” is far larger than corner “C”. This means that more weights will be shifted on the right side of the wheel in zone “B” than on the left side in zone “A”.

Fig.2 shows that the wheel weights generating a clockwise torque are projected on the right side. On the left side in zone “A” only one weight is projected and it generates a counterclockwise torque. More weights shifted from the wheel axis on the right side will generate a greater clockwise torque than the weights shifted from the wheel axis on the left side. This is the cause of the wheel clockwise rotation.

This interesting effect is achieved due to the loop-shaped parts on the wheel spokes with bimetal components placed on them. When the next wheel spoke reaches corner “D”, the bimetal component connected with it touches hot water, becomes straight and shifts the corresponding weight further from the wheel rotation axis. The motor wheel continues rotation, making the next bimetal component touch water. It is also heated, becomes straight and shifts the corresponding weight from the wheel rotation axis. The wheel continues rotation. Bimetal components are touching water in succession. On the left side, in zone “A”, the bimetal components successively come out of hot water, cool in comparatively colder air, return to the initial sharply curved form and pull the weights on spokes to the wheel rotation axis. This is the reason for the wheel torque to decrease.

Mass movement from the axis in a rotating object commonly causes reduction of rotation speed. And, on the contrary, the rotation speed increases when the mass comes close to the axis. In motor zone “A” the weights come close to the rotation axis after the corresponding bimetal components come out of hot water, and the same number of weights move from the center in zone “B”, i.e. these effects on the rotation wheel compensate each other.

In essence this is a heat machine. The heat transfer from a warmer medium – water – to the cold medium – air – is achieved owing to the heat capacity of the band-form bimetal component. This is the reason for fast heating and cooling processes. Due to the fact that bimetal components are not large, not so much heat is needed for their heating.

The motor will operate when the air temperature exceeds that of water but in this case it rotates counterclockwise.

There is another model of this motor when nitanol components are used instead of bimetal ones. Nitanol is a memory metal alloy that changes shape when reaching certain temperature. In this instance, the nitanol component is normally curved but becomes straight when heated (for example, up to 50^0 C), and the weight on the spoke end moves from the wheel rotation axis initiating rotation of the wheel. That means similar operation of a nitanol-based and bimetal-based motor.

The motor structure is very simple and its operation does not require power or fuel supply: it is enough to place its wheel into the water the temperature of which is different from that of the air.

The motor structure may be further developed: for example, a focused sun ray can be used for the heating purposes; the bimetal component can be heated with a common electric lamp on one side of the wheel, the required heat may come from a heating radiator, stove or burning gas-jet. Such motor may be heated when installed on a mantelpiece, etc.

This article describes the motor model that can be used as a toy. Being supplied with looking-glass units it may be applied to get various luminous effects or may be installed in the shop showcases, or else at exhibitions. This motor is also able to operate in a gravity force environment, even on the Moon. There direct sun rays may heat bimetal components to 200^0 C, and the temperature of the components located in the shadow almost reaches absolute zero, i.e. the temperature difference in this instance is over 400^0 C, which enables constant efficient motor operation.



Fig.2
The motor in operation

Self-Interaction in Electromagnetic Rotation

S.A. Gerasimov , V.V. Stashenko, Russia
Physics Department, Rostov State University, Rostov-on-Don, 344090
Email:GSIM1953@mail.ru

Introduction

The electromagnetic rotation is the motion of a magnetized body ina direction perpendicular to both the vector of magnetization J_m and the direction of the electric current j in a liquid inside which the magnet is located (Fig. 1).

Editor: Readers can compare this vector composition and the device scheme of Godin and Roschin with the Searl experiments. The similarity is evident. *A. V. Frolov*



Fig.1
Electromagnetic rotation. A magnet M of magnetization J_m that is partly or entirely submerged in a conductive liquid L with a direct current of density j is moving in the direction of the force F_a+F_r

The force producing such a motion is sufficiently weak and, normally, the phenomenon is observed at rotation. Although, this is quite a well-explored phenomenon [1-6], nobody knows what makes the magnet rotate [4]. There is an opinion [2,3] that the motion of the magnet in the conductive liquid is caused by the forces of attraction $\mathbf{F}_a$ and repulsion $\mathbf{F}_r$ between currents of density $\mathbf{j}$ flowing in the liquid and surface magnetization currents $\mathbf{j}_m$ of the magnet, often called the Ampere currents as shown in Fig. 1.

The external magnetic field of a long cylindrical magnet originating far from either pole is zero. Therefore, no force is exerted on charges moving in the liquid far from the ends of the magnet. Nevertheless, the magnet still moves in the liquid with the direct current even if it is only a thin magnetized needle [5]. Thus, the deeper the magnet is immersed in the conductive liquid, the more liquid gathers around it. The deeper the immersion is, the higher the total force must be. That should be so.

In reality, it is quite different. During intermediate immersions when the magnet is partly submerged in the liquid, the torque N does not depend on the depth of immersion, in the other words, currents flowing round the cylindrical magnet do not influence the exerting force acting [6]. Moreover, during shallow immersions, the magnet moves together with the liquid. **This is none other than *the self-interaction* [7].** The conductive liquid under the magnet experiences the magnetic action. The direction of this force coincides with the direction of the magnet motion. **Thus, the part of the conductive liquid moving in this direction under the action of the magnetic field B, affected by the frictional forces in the liquid causes the motion of the magnet in the same direction.** The only way to find out the role of the self-interaction in this phenomenon is experimental investigation. It would be appropriate to exclude the currents flowing under the magnet. In this case the magnet must rotate in the opposite direction.

Experimental system

A commercially available cylindrical magnet M of magnetization J_m=1,95•10^5 A/m and a balanced load *P* connected by a rocker R are suspended by a thread *T* as shown in Fig. 2.



Fig.2
The experimental set and its parameters: h=50 mm, r=35 mm, d=25 mm, v=70 mm, the diameter of the central electrode E is 5 mm, the thickness of the bottom G is 2 mm. (×) and (·) are directions of the force acting on current elements of current density j in the magnetic field of inductance B

The magnet is immersed in the 5% copper sulfate solution ($CuSO_4$) so that the depth *z* of immersion can vary. A vessel containing the conductive liquid *L* is large enough for the magnet to be almost entirely immersed. The cylindrical surface *C* of the vessel and the central electrode *E* of the system are made of non-magnetic materials. The bottom of the vessel *G* is, of course, insulator. The magnet is coated with an insulating moisture-proof varnish. The length of the electrode *E* equals the height h of the vessel. A direct current of strength *I* passing through the cylindrical electrode *C*, the conductive liquid *L*, the central electrode *E* and the disk electrode *D* generate a torque of electromagnetic origin which results to the rotation of the magnet. The disk electrode *D* is intended to provide the system with the symmetrical supply of the current.

Experimental results

The size of this experimental device differs from that described previously [6]. **As a result we have obtained the torque N, which is about ten times more intensive than the former one.** But the main result is that the torque does not change its sign when the magnet is being immersed in the conductive liquid (Fig. 3).



Fig.3
A typical experimental dependencies of the torque N
acting on the magnet depending on the depth of immersion z

When the magnet is almost entirely submerged in the liquid the depth of which equals the height of the magnet, no currents are flowing under and above it. In this case the rotation of the magnet is expected to be the result of drag action of the rotating liquid located in the intermediate field relative to the magnet. This part of the conductive liquid is rotating in the direction opposite to that of the motion of the magnetized body. It seems to be the right way. The magnet pushes the liquid away and, therefore, is moving in the opposite direction. No, this is wrong. If it was correct, this effect would also occur during the shallow immersion. At small z the magnet and the liquid rotate together. So far we still do not know what makes the magnet rotate.

S.A. Gerasimov

References

1. Faraday M. Experimental Researches on Electricity. // London: Ed. by R. and J.E. Taylor. 1839.
2. Ampere A.M. Theorie Mathematique des Phenomenes Electrodynamiques. // Paris: Blanchard. 1958.
3. Sigalov R.G., Shapovalova T.I., Karimov H.H., Samsonov N.I. // Magnetic Fields and Their New Applications. // Moscow: Nauka. 1976.
4. Gerasimov S.A., Ershov A.V. What Makes a Magnet Rotate? // Physics Education (Moscow). 2002. V. 22. P. 70-75.
5. Grabovsky M.A., Mlodseevsky A.B., Telesnin R.V., Shaskolskaya M.P., Yakovlev I.A. Lecture Demonstrations on Physics. // Moscow: Nauka. 1965.
6. Gerasimov S.A., Ershov A.V. Mechanism of Electromagnetic Rotation. // Problems of Applied Physics. 2001. V. 7. P. 34-35.
7. Gerasimov S.A. Self-Interaction and Vector Potential in Magnetostatics. // Physica Scripta. 1997. V. 56. N 3-4. P. 462-464.

Capillary Motor

Iosiph I. Elshansky, Russia
Koshtoyantsa St., 1a - 75, 119454 Moscow
Email: ewrik@bisinter.ru

For several decades the author has been organizing a contest for young inventors on the radio, television, in mass media and the Internet. There have been accumulated thousands of engineering solutions that belong to schoolchildren and youth. There are many original ones, including perpetual mobile. Though unfeasible in principle, they have interesting structure and competent engineering solutions.

For example, a child's dream to create an oblique roof over a city or field and direct the rain flow to a turbine to obtain mechanical work is of little use. But it's quite another matter if this child takes a pencil, a sheet of paper and tries to make a sketch or a drawing of such construction. Even if the construction is primitive and unfeasible, the child will get his first engineering experience and self-reliance.

I can still remember one peculiar case. Once the editors were instructed (it was in the times of the USSR) to assist an honored inventor of new machines. It was a Stalin Prize laureate, creator of a special type of lime that was widely applied in construction (I will not disclose his name). The inventor was given (that was not common practice) a large room in a shared apartment situated in a prestigious block of apartments in Moscow. It turned out that all room space, except for narrow passages at the walls, was occupied by a huge table. On the table up to the ceiling there were some pipelines, glass and metal vessels, retorts and other laboratory ware. The most impressive thing was retorts heated by gas coming through a hose from the shared kitchen. All that staff was bubbling, hissing and steaming. The inventor was creating a perpetual mobile!

I will give one more example of a situation common for the editors of the "Inventor and Rationalizer". Once we had a respectable-looking visitor who made an odd request to get the President of the French Academy of Sciences to respond to his letters about a perpetual mobile plan. The essence of Alexander Rodionov's (Maloyaroslavets, Russia) invention was that "in accordance with Newton's and Guerin's laws fluid flows up through capillaries and turns a wheel when flowing down (see Fig.1).



Fig. 1
Perpetuum-mobile

There are many similar projects in the history of engineering. Hence, this case may be considered as typical. We all know that the molecular adhesion forces (moistening) that push the fluid upwards will stick to it and the capillary motor will never work. But is the idea totally unfeasible? Since false modesty is inappropriate when it comes to perpetual mobile, I will present my ideas on this not so honorable subject for the reader's judgment.

It seems that all perpetual mobile inventors start not with a pencil and a sheet of paper but with experimenting on magnets, oblique plane, wicks, wheels, springs and other materials at hand. My first heat (perpetual) motor was also the result of an experiment.

The "Capillary" idea of Alexander Rodionov haunted me. I recalled that the great Lomonosov devoted lots of time to studying molecular adhesion and capillarity. They are present in everyday life, let alone the nature, especially in plants that would not be able to exist without them. How else would moisture flow up the trunks and stems? But, on the other hand, according to Mikhail V. Lomonosov's data, water flows up only for the maximum of several dozens of millimeters even through the thinnest capillary. But trees may have the height of several dozens of meters! If, as it is customarily considered, moisture flows from one capillary to another of its own accord, why not suppose that a capillary perpetual mobile is feasible? Explanations that moisture in plants flows up due to root pressure do not sound plausible. So where is the truth?

Years have passed since that visit of A. Rodionov. Now, just like I used to sympathize with, as it then seemed, a rather odd inventor, now my relatives sympathize with me. One can not blame them: for weeks and months there have been flowerpots all around the apartment - on the tables, window-sills and bookstands. With bottles, tubes and self-made water manometers to follow.

Once, when I was assembling a device, I could not find two similar glass tubes and had to put in the tube of thin polyethylene. But no matter how hard I worked the water in the communicating vessels was at different levels. In the glass tube the water level was always higher. It could not be otherwise, if you come to think of it, but isn't it the right time the words "made of equally wettable material" were inserted into the communicating vessels law?

Here is a primitive experiment: make a hole in the bottom of a plastic flowerpot containing soil and a plant, and insert there one end of an elastic tube. The other end is inserted into the bottom of a plastic bottle containing water (see Fig. 3). In accordance with the communicating vessels law, the water will flow from the bottle into the flowerpot. When we see that the soil has been made wet, the experiment shall get more complicated: elevate the flowerpot so that its bottom is higher than the liquid level in the bottle. In some days we shall notice that the soil has not dried up and the water level in the bottle has lowered. One should not be a Solomon to guess that the soil or the roots of the plant transfer the water from the lower to the higher level. Here is a typical natural perpetual mobile!



Fig. 2
Motor

It is no use referring to the molecular adhesion forces since they can not be applied at such height differences. What is it then? A molecular collision as in a boiling kettle? But a leaf has neither high temperature nor much space. Nevertheless, water evaporates both from the soil and leaf surfaces. At the same time there is rarefaction under the evaporating surface. Can it be the rarefaction that pulls up new portions of water?



Fig. 3
Rarefaction

Let us make the experiment still more complicated. Put the leg pipe of a liquid manometer into the bottle cork. (Fig. 3) Almost immediately the water level in the closest leg to the bottle will start rising. It means that there is rarefaction in the bottle. Can it be the rarefaction that "rules" the plants?

Most likely, the essence of the mistake made by Rodionov and other authors of capillary motors consisted in attempts to get the water outflow from the capillary. **If it is not flowing out but evaporating, as it is common for the soil or plants, then, probably, vacuum will manifest itself and the capillary perpetual mobile will start working.**

I made my first capillary perpetual mobile many years ago (see Fig. 4). And it worked: though slowly, the wheel was steadily turning. No doubt, it was due to the heat inflow from the air. Therefore, such motor will work if there is a temperature difference and relative humidity of surrounding air is below 100%.



Fig. 4
Capillary Motor

The heat motor operating principle is clear from this figure. The disk (many disks on the common axis) is divided into isolated sections. Their surface is covered with a moisture-proof piece of material (filtered paper, cloth, etc.). The part of each section somewhat gets under the base of the next one. Hence, a small part of the base of one section and a part of the part following the section can get into water simultaneously. Due to the capillary moistening the section and the part will start to absorb water. Since the section is shifted about the center of gravity, the turning moment is bound to appear. The section that is out of water starts to dry up, the moment will increase and the wheel will start turning.

Having determined that, though slowly, the motor is turning, the author applied to a patent authority for a patent on the invention of the "Perpetual mobile", meaning it as a joke. I hoped that the experts (I knew some of them personally) will understand this joke. But, unexpectedly, the device was considered an invention, though under the name of the "Heat motor" (certificate of authorship USSR # 1455040).

Basically, the motor is similar to the project of A. Rodionov. I would not be surprised if he protested. The same capillaries and the spontaneous rise of liquid on the moisture-proof material. The only difference is that the liquid does not flow out but evaporates from the capillaries.

Almost without any reason - one can not predict his eccentricities - I have recently made one more capillary motor (see Fig. 3). Perhaps, it resulted from my experiments with plants. This motor directly and spontaneously lifts water to a higher level, which is more convincing. Moreover, water flows in the form of drops (or a stream) and turns the propeller! The motor is quite operable and has even been shown on TV. But do not try to verify it on your own - such work is useless without certain know-how. The author would not like to disclose the "secret" yet. I could still make a patent application.

NEWS

The Continuous Rotation Device

The essence of this invention is that in a closed circle the rotation of the object occurs without any outer influence or any power sources (electric energy, oil, diesel oil, etc.), which results in the rotation of the rotating part of the device. The torque can be easily enhanced by means of transmitting it to the reduction system. At that rate, the necessary rotation speed and rotation power can be acquired.

The device is small, easy to transport, mobile (both, in operation and switch-off), simple and inexpensive to make and assemble. It is economical, ecological and weather independent.

The device can be used in any industrial or household appliance field where the continuous rotation is required. It is especially important to note that this device can be used to generate energy on a large industrial scale as well as in small laboratories, in mountains and remote districts, in tunnels, at sea, etc. for it does not require any power lines.

Patent Claim Priority:
#20030059, April 19th 2003

For more information
contact
the author of the invention:
Eldar Sariyev,
Azerbaydzhan, Baku,
Tbilisskiy Prospekt, 75-26;
Tel: + (994 12) 92-47-73, 98-95-02;
Email: eldar_sariyev@yahoo.com

Gravity-heat Power System

Vladimir N. Sukhanov, Russia
Kosmonavtov Str., 35-39, 420061 Kazan
Email: Wladimir.Sukhanov@soros.ksu.ru

Natural hydrologic cycle is a widely recognized phenomenon. Water evaporates from the ground and water reservoir surfaces, generally, due to the Sun heat, then moves to the superstructure atmospheric layers where it is condensed, and precipitates onto the ground surface, but on higher levels compared with evaporation surfaces. In this process water is also purified and desalted. From the higher levels water flows to its main evaporation points, forming streams like brooks and rivers where water power plants could be established. Flowing to the lower surface layers with lower potential energy, water in the Earth's gravitational field performs work that can be utilized.

Natural hydrologic cycle principle is used in the gravity-heat power system (USA patent No. 3953971, International class. F03G7/04 of May 4, 1976).

In this system the temperature difference between ground surface layers (the mountain foot and its top) is used to produce electric power and obtain fresh water. The temperature difference does not change much with change of height, and the system effectiveness is quite moderate, which can be named as its drawback.

The system utilizes free environmental energy. Its efficiency (converted to the process maintaining energy) tends to infinity.

The author proposes a new gravity-heat power system that can substitute modern heat power plants. It contains all installation components as per USA patent No. 3953971 except for the heat exchanger on the ground surface whose functions are performed by a conventional steam boiler.

Gravity energy component **G** in the proposed system:

$$G = X_m \cdot T g H,$$

where

- ♦ X_m – fluid flow,
- ♦ **T** – time of operation,
- ♦ **g** – acceleration of gravity,
- ♦ **H** – tower height between the steam boiler and the freezer (condenser).

This formula does not allow for vapor density of operating fluid.

The vapor density is insignificant as compared with the operating fluid density.

Energy **P**, required to maintain operation:

$$P = X_m \cdot T q,$$

where **q** – specific fluid vaporization energy

Efficiency **K** – of the system should not be lower than 80%

To obtain efficiency that equals 120% the following is required:

$$H = 2{,}2q/g$$

Or **H** = 25,4 kilometers.

Construction of such towers is too complicated for modern technology. Therefore, a stratospheric balloon that is linked to the ground surface by a flexible twin-core hose rope may be used. One core is designed to send down fluid and the other to send up vapor. Flowing down to the ground surface through the hose, the fluid will generate fluid column pressure. The fluid will cross water-turbine generator cascades, after each of which the fluid pressure will decrease and the fluid will continue its way down.

There is an alternative. To make the tower several times lower the evaporation (at the tower foot) and condensation (at the tower/mountain top) should be phased (in the form of cascade) at various pressure values and with utilization of the same heat energy. For this purpose a heat carrier is used that will transfer heat from the tower (mountain) top to its foot. This operation will enable the tower height segmentation into **H/n** sections where **n** is the number of grades in a cascade.

Cascade structure is shown in Fig. 1



Fig. 1
Cascade

where

1 – ground surface,
2 – tower component or the smoke-stack of the steam boiler,
3 – steam boiler,
4 – steam pipe,
5 – heat exchanger and condenser,
6 – pressure pipeline,
7 – water-turbine generator,
8 – heat exchanger and evaporator,
9 – circulation pump,
10 – pipeline of the heat carrier circulation.

Cascade (operating fluid, water) with 500 meters of height can contain several dozens of grades (50 and more). **In this case the cascade efficiency may approach 120%.**

Decreasing the tower height to 500 meters (for water) will allow for utilization of conventional water-turbine generators and standard equipment.

In the proposed cascade the heat energy is required to maintain the cascade working capacity when Earth's gravitational field energy is utilized. In the author's opinion there are still other ways to use gravitation.

The system scale is its main drawback. Therefore, partial utilization of the proposed principle may seem more attractive. The proposed engineering solution was simple.

In a thermal power station the condenser is installed on the top of the tower (mountain). After the condenser the water lift in the water tower finished at the steam boiler pressure pipe (omitting the pump that was no longer necessary). Energy required for pressure pipe operation was saved. In other words, the water tower was utilizing the Earth's gravitation at the conventional juncture of vapor condensation in the steam plant.

Such proposal was made on June 17, 1982 in the patent application USSR N3453603/06, (101161) expert code 060701KH. However, the utilization of free and environmentally friendly gravity energy did not arouse interest even on the part of patent experts.



Fig. 2
System

The author is looking for serious partners.

The Alternative Energy Potential in Russia

According to the International Energy Agency (IEA) calculations, total investments into the energy industry constitute approximately 330 billion dollars annually. Almost half of this sum (150 billion annually) is allotted to the development of the electric power industry. This information only partially reflects the potential of the alternative energy development and does not include the market growth factor upon the introduction of autonomous power system technologies. Vast territories of the planet have not been sufficiently developed yet due to the absence of local energy resources and power lines. From this point of view, Russia is the country with an enormous consumer demand potential provided that the mass production of autonomous fuel-less energy systems guarantees low production prices.

Alexander V. Frolov
Editor-in-Chief

Faraday Lab Ltd

Fuel-less energy R&D
R&D in alternative astronautics

Read our
New Energy Technonlogies
magazine

Lev Tolstoy Str. 7-601
St.Petersburg
197376, Russia
Tel: 7-812-3803844
www.faraday.ru

Modern Perpetual Mobile

Review prepared by correspondent Alla Pashova, Russia.
Based on the Internet pages and other information sources

It is common knowledge that any experimental information, which is against a conventional scientific paradigm, is considered to be false, extracted from the society and finally is turned into something **classified and elite.**

Politics-oriented science as a whole and natural science in particular often result in misrepresentation and falsehood of **popular knowledge** that turns it into the fighting weapon of socio-political organizations, states and their groups.

World-outlook and political contradictions of any society often determine science development strategies. In 1885 Nicola Tesla presented his transformer in action by means of which he lit carbon lamps in a 25 miles circle without any cords, conductors or switches using the 5000-HP turbine of the Niagara hydroelectric power station. Afterward, he obtained financial support for one of his energy projects.

On a special testing ground Nicola Tesla built vacuum-energy systems. However, in 1885 the systems, as well as the testing ground, were destroyed as it became evident that if they went on the mankind would never need organic fuel again. But the destruction of the systems and testing ground does not at all mean the destruction of papers and documents...Ever since that moment people have been trying to find "free energy".

The experiment of distant lighting of carbon lamps without using any cords was repeated only once by the physicist Filippov. He managed to light the lamps in Tsarskoe Selo employing the electric generating systems in St. Petersburg. Filippov died in 1914 under mysterious circumstances.



In 1917 the Portuguese American Andres invented non-convetional fuel for an internal combustion engine. The essence of his invention was in some inexpensive chemicals, which he dissolved in water (some drops of chemicals per pail of water). A special state committee tested the new fuel during the New York - Washington - New York automobile races. After the races one of the largest oil monopolies in the U.S. offered Andres 2 million dollars in cash for the documents and all rights for his invention and later locked all the information in their safes. Two days later after getting the money Andres disappeared. (The information was disclosed by V. Vasilevsky, the former chief of the scientific and technical intelligence department of the KGB of the USSR, who had been in charge of the department since 1930).

The above-mentioned examples show that there were a lot of attempts to develop revolutionary energy technologies. But what then are the grounds for the 'energy crisis' complaints? The answer is simple: the desire of a group of financial and energy multinational corporations for an economic, political and, finally, for a total control of the world. That is why there is no room for "free-energy" hunters in our science, not even as laboratory assistants, not to mention some higher positions.

Practice often negates scientific dogmas, especially when it comes to the efficiency of different devices. In general, the traditional understanding of efficiency is quite limited and should be forgotten. Instead of the traditional notion "efficiency" we should consider the notion "energy-conversion efficiency" (ECE), which has no limits. In 1974 in the USA a six-stroke internal combustion engine was designed which had a double ECE. The fifth stroke of the engine operation included water injection; the sixth was characterized by the water vapor introduction. Firstly, the engine had a higher ECE than that of the Carnot cycle. Secondly, taking the 55 % ECE of the contemporary internal combustion engine, the ECE of a six-stroke engine exceeds 1.

Practice often negates scientific dogmas, especially when it comes to the efficiency of different devices.In general, the traditional understanding of efficiency is quite limited and should be forgotten. Instead of the traditional notion"efficiency" we should consider the notion "energy-conversion efficiency"...

Before the war there appeared "studebekkers" with the fuel consumption of 5.5 l per 100 km. But the fuel-economy record was set by the Japanese. In 1986 they built up an automobile, which used only 0.055 l of fuel per 100 km (about 44 g). Unfortunately, now we do not have plants, which could manufacture automobiles of the kind.

In 1832 Tomson came up with the idea of **a heat-pump unit**. Stating the unity and interconvertibility of substance movements, he proved that the mechanical energy consumption can restore stray heat. At that time cross-Atlantic ships had low-temperature steam engines, which employed exhaust steam and ether vapors. The efficiency of those engines was already higher than the Carnot cycle efficiency.

Now with the help of the facts acquired during the last century we will prove the scientific inconsistency of the orthodox model of the second stage of thermodynamics. In 1941 the English physicists O. Hougen and K. Watson published their work featuring the experimental fact that the ammonia-saturated vapor pressure in liquids was higher than the general pressure. For example, with the general pressure of 50 atm and the temperature of 0^0 C, such pressure was 17 % higher. This means that having placed a semitransparent partition and a turbine between two containers it could have been possible to build up a natural-heat vapor-converter. This method was used by **von Platen, the Nobel prizewinner from Sweden, who constructed a self-rotating centrifugal machine, which provided a 1000 atm pressure when ammonia interacted with water. The heat emitted was enough to compensate friction losses**. It is also known that the Carnot principle cannot be applied to closed cycles. W. Vielstich, 'Combustion Cells', 1968: **"If an entropy change of a reaction is negative, it can exceed 1**. It means that a certain amount of energy can be obtained from the natural heat. Such an effect is possible in electrochemical generators, which employ a direct oxidation process before oxidation and dioxidation".

A demonstrative example of scientific experiments withdrawn from science is discovery # 13 "The knock power-transfer regularity" made on December, 18th, 1962, which makes it possible to create a mechanical "perpetual mobile". The experiment shows that the conventional "knock theory" does not work in practice: **the bouncing energy of a body after it has been knocked can be higher than its energy before it has been knocked**.

Trying to get some recognition, **E. Aleksandrov, Doctor of Engineering Science, made his demonstrative experiment in front of many different commissions: a chilled-steel ball when falling from a 10 m height onto a firmly-fixed chilled-steel plate made a 14-15 m-high bounce**. That was the notorious 'perpetual mobile' as it is. It went on like this until somebody decided to explain the result of the experiment by a metal lattice internal energy. At once, everything was clear. Since that moment the above-mentioned principle has been successfully employed in percussion-action machines. This principle can also be used in simple electric-power systems.

Now we can see that electro-technicians had already constructed demonstrative 'perpetual mobile' machines 10 years before politicians and economists started to speak about the 'energy crisis'.

In 1921 the mass media wrote about A. Hubbard who invented an electromagnetic generator without any external energy supply. The Hubbard generator was used as a boat motor.

> *...now we can see that electrotechnicians had already constructed demonstrative 'perpetual mobile' machines 10 years before politicians and economists started to speak about the 'energy crisis'...*

In 1928 L. Nidershot invented a 300 W electric generator, which did not require any external energy supply. The device consisted of a radio-technical oscillation generator (500 kHz) and a coil. After 68 years there appeared publications about A. Melnichenko who repeated the experiment.

In 1927 T. Brown (England) obtained a patent on the ways of originating a moving power and energy using an electric field. Later, in 1955 while working in France, he presented a system with the speed-capability of several miles per hour using a 2000 eV field. After that he had to stop his experiments and was sent to the USA.

In 1943 N. Tesla presented an electric-motor automobile. The energy was generated by a previously-unknown generator.

In 1960 Stovbunenko (whose research work results were subject to a special verdict of the Military-Industrial Complex) presented his motor, which made it possible to move in his old automobile 'Moskvich' around the city for the whole day utilizing the power of a standard automobile battery.

In 1980 there was a qualitative break through in electro-technical "perpetual mobiles". Baumann's electrostatic machines of the total capacity of 750 kW started functioning in the religious community of Liden (Switzerland), serving all daily needs of the village. (See the photos below)







The photos are taken from www.free-energy.cc

Thus, in 1980 there appeared a community with no energy problems, no need for organic fuel and no fear for the 'energy crisis'.

In 1881 N. Sluginov discovered an energy imbalance that occurred in the water electrolysis process. In his experiments he got that the output energy was 30 % higher than the input energy. In 1980 American scientists recreated this energy imbalance and proved that while employing the steam turbine rejected heat, the water electrolysis efficiency reaches 120%.

This information introduces a story about an energy system invented in 1957 under the guidance of I. Filimonenko. The system did not simply generate energy in the form of a high-pressure vapor and output hydrogen and oxygen but also absorbed radiation. In 1960 the USSR Central Committee and Cabinet Council gave a special secret ruling, known as “The Three 'K's'” (Keldysh, Kurchatov, Korolyov) to go on with the research in this system. However, after Kurchatov's death the project was "oppressed" and later on after the death of Korolyov the project was completely cancelled. The special committee of the USSR Academy of Sciences stated that the system was functioning against "the Law of Nature". I. Filimonenko was dismissed and expelled from the party. Later, in 1980-1991 the experiments were partially renewed. Several testing systems were constructed in the Chelyabinsk region but the construction was never finished and the use of a mobile system for eliminating the damage caused by the Chernobyl accident was refused. This story is a demonstrative example of the traditional rejection of promising projects by science, which could be very beneficial for Russia.

Theoretical Background of 'Perpetual Mobile'

Originally, the term 'entropy' was used only in connection with the reasoning about limited or eternal nature of the Universe. Later it came to be used to describe the functioning principles of thermal machines. Now there exist more than 600 contradictory definitions for 'entropy', which are actually the results of a long and unfinished discussion between the supporters of Dekart and Leibnitz, who defined 'motion' in different ways. It is these permanent contradictions in the theoretical fundamentals of physics that make it impossible to explain the existence of a 'perpetual mobile'. However, standard physics has never denied the possibility of creating energy technologies allowing the ECE higher than 1.

We should remember that the basis of the so-called variational calculation is the mathematical apparatus technique of the conventional mechanics. It seems that if system behavior equations directly depend on time, this system cannot fall under any conservation laws. **This is the proof of a complete failure of the conventional energy conservation law!**

> *It is these permanent contradictions in the theoretical fundamentals of physics that make it impossible to explain the existence of a 'perpetual mobile'*

In time-independent thermodynamics the existence of 'perpetual mobile' can be explained by the system internal energy usage. There exist two kinds of thermodynamic systems. Some of them when being heated or affected in some other way start increasing their internal energy while other systems show the internal energy decrease. The latter are called negative absorption systems. The standard version of the first law of thermodynamics does not cover all the processes occurring in such systems. The output of a negative absorption system can be higher than its energy. The additional output is acquired by the gradual internal energy loss.

To cap it all, there are more than a hundred experimental facts that show the limited nature of the Maxwell theory. They were obtained by scientists from different research institutes and construction bureaus, were tested and registered. Thus, for example, in 1973 in the USSR the acoustic magnetoelectricity effect was discovered. The author of the discovery proved the interaction of electrons with ultrasonic waves with a 1000-times energy increase. This is against the Maxwell theory, which absolutely denies effects of the kind. But the limited nature of the theory was never accepted.

However, the examples of the machines in action prove that since 1834 when the first refrigerator was invented, when the cross-Atlantic ships were equipped with low-temperature ether-vapor steam-engines, the contemporary science had no right to introduce 'the second holy principle', especially in the orthodox form of 'the Carnot cycle efficiency'. The modern theoretical physics cannot provide grounds for the negation of creating over-unity devices. That is why we should rely on the physicists-experimentalists who develop the science in a practical rather than theoretical way.

Alekseenko's Fuel-less Motor




РОССИЙСКАЯ ФЕДЕРАЦИЯ

ПАТЕНТ

НА ИЗОБРЕТЕНИЕ

№ 2131636

БЕСТОПЛИВНЫЙ ДВИГАТЕЛЬ

Алексеенко Василий Ефимович

Алексеенко Василий Ефимович

Patent # 2131636
Vasiliy E. Alekseenko

Aerospace Defense Research Finds Free Energy and Antigravity Possible

Dr. Ines Espinoza, USA
email: dr.ines@vasantcorporation.com

Editor: it is worth mentioning that the first gravitational-wave physical mechanism and the mechanism of spin-effect "grazer" (gravitational lasers) designing were described by S. M. Polyakov and O.S. Polyakov in the book "An Introduction to the Experimental Gravitational Studies", Moscow, 1991.

After a 7-year research study, a senior staff aerospace defense engineer, George J. Bugh, concludes economically free energy and even antigravity are possible.

A 7-year study of "free energy" devices, sometimes called "over unity" devices, was done to determine if any of these devices generated power by transferring energy from unknown sources and if so to determine where the energy was coming from. Included in the study is research of related devices with claimed antigravity effects. The study attempted to determine validity of claims, commonalities of device characteristics and to determine how these devices could work. **The results conclude that some devices can generate economically free energy. This study also concludes there is a possible link between gravity and electromagnetism that can be exploited to generate antigravity or electrogravity effects.**

The majority of the study was to come up with a theory to explain how the devices could work. In his research, Mr. Bugh used mostly classical electrodynamics rather than quantum electrodynamics. In Quantum theory, the wave-like characteristics of matter are described using abstract probability waves. However, Bugh proposes that the wave characteristics of matter may also be described as coming from a very real sea of unseen electromagnetic standing waves among all matter. There is a slide show presentation at the website that explains the differences between the Quantum and Classical way of explaining particle interactions.

According to classical electrodynamics, all electrically charged particles, like quarks of protons and neutrons as well as orbital electrons for example, **should radiate away energy from precessional and precessional plus orbital motion**.



Fig.1
Electron motion

If in fact this really happens then all electrically charged particles can be radiating away energy all the time. However, all particles can also absorb just as much energy from all other radiating particles. The absorbed energy applies electromagnetic forces that naturally move all similar type particles into harmonious precessional motions with all other particles. This results in a vast sea of electromagnetic standing waves among all matter. Even free particles would move into precessional motions that are in sync with the established sea of standing waves.


Symbolic Electron Process in an Opposing External Magnetic Field
N
Z
t0
t1
t2
t3
t4
t5
t6
t7
t8
N
X
Y
S

Fig. 2
Electron precession

There can be a hidden yet strong tendency towards harmony among all matter in the universe due to these unseen standing waves and spin interactions among all matter. This tendency can overcome to a great extent the tendency towards chaos and heat death of the universe. This tendency can also be exploited to perform work.



Fig. 3
Spin wave

This is an interaction among all matter that Ernst Mach alluded to as necessary to cause matter's characteristic of inertia. Einstein later called this Mach's Principle. Einstein studied Mach's ideas while developing his theory of General Relativity.

Bugh describes inertial resistance to acceleration as caused by electromagnetic forces. Changes in position of a mass will cause phase differences to develop between the precessional motions of the particles of that mass relative to the sea of standing waves. This in turn causes electromagnetic force that resists a mass from changing its position.

The research papers are published in a book and a CD titled "Spin Wave Technology Initial Release".


Spin Wave Technology
Z1
Z2
X
N
S
Y1
Y2
Electromagnetic interaction among uncompensated electron spins from gyroscopic precession in an opposing external magnetic field
Z1
Z2
X
N
S
Y1
N
S
Y2
Electromagnetic interaction among compensating electron spins from gyroscopic precession in magnetic fields manifested from apparent relative motion of protons of the nucleus

Fig. 4.
Spin wave technology

At the end of the book it suggests that it should be possible to create computer simulations of particle interactions using classical electrodynamics to demonstrate both inertial resistance and gravitational attraction and it should be possible to simulate devices that manipulate these particle interactions to demonstrate antigravity effects.


C
L
Resonant Cavity
Ferromagnetic material
Antenna & Field Coil
C
L
Distance between resonant cavity and the ferromagnetic lasing material where both the antenna emissions and emissions reflected off the cavity walls provide the maximum re-enforcment of coherent electron precession and coherent spin waves
8.0"
Distances that will allow an integer number of EM waves between opposite resonant cavity walls at the coherent electron pression frequency
TBD
TBD

Fig. 5
Spin wave laser

More information is available about the research results at the website: www.vasantcorporation.com.

On Physics of Electromagnetism
Mechanical Analogue or Pure Mechanics?

Yury V. Ivanko, Ukraine
E-mail: ux0lw@hotmail.com

After publication of the article "Study of possibility of a high-energy hyper-low-frequency electric field" in the "New Energy Technologies" magazine, Issue #2, 2003 I am often asked why I have mentioned the Big Bang in my hypothesis.

I would like to reassure atheists since I do not back the Big Bang hypothesis. But I had to base myself on something. At present the origin of the Universe as a result of the Big Bang has priority and is recognized by the academic science.

Both theorists and experts have long noticed a deep analogue between vortex motion of air currents and electromagnetism. My vision of the physics of electricity and electromagnetism is fully based on existence of a vortex capable physical environment. What is considered to be and is measured **as electric voltage, electric current, magnetic or gravitational interactions is nothing but similar-originating phenomena - the result of vortex flow environment affecting our detectors - dissimilar formations for these vortex flows**.

For instance, let us consider three vectors for the flow along the skin-layer of the line conductor - aerial emitter, together with alternating voltage attached to it (Fig.1):

1) longitudinal - showing as electric voltage, the gradient of potentials between the emitter feeding point and the emitter cold end, U;

2) tangential - showing as amperage - electric current, I;

3) radial - showing as the interacting force of two flows - magnetic field (attraction/repulsion), H (not to be mixed with the commonly used term of magnetic intensity).



Fig.1
Interaction of two left-handed homogeneous parallel flows.

Let us consider it step by step:

Consider line conductor AB with length L in free space (Fig. 2).



Fig.2
Line conductor in free space.

Let us assume that he is not affected by and fields. Then the gradient of potentials between A and B equals zero. Let us apply sinusoidal voltage from the generator output to point A (Fig. 3).



Fig.3
Sinusoidal voltage at the generator output.

Let us consider the initial time point t_0. The generator output voltage is $U=0$. At time point t_1 the generator output voltage has changed and took on value U_1.

It is necessary to note that (See Fig. 2) the propagation speed is finite: c=300000 km/sec. Point B will "learn" about the voltage alteration only in time $t_B=t_1+L/c$. Therefore, at time point t_1 between points A and B appears gradient of potentials $\Delta\varphi = U_1$. So what is the direction of vector U_1? Right, along conductor AB.

What practice says

One should not be a physicist or radio mechanic to notice small electro-shock of ungrounded metal objects close to aerials of powerful transmitters. Specialists term them as "electromagnetic inducers". Has an expert ever measured the actual characteristic of the field intensity distribution along a line conductor? Why should he? Everyone knows from school lessons how alternating voltage is distributed along the conductor, the length of which is comparable with the wave length (Fig. 4).



Fig.4
Classical representation of voltage distribution along a linear vibrator a) for λ, b) for λ/2, c) for λ/4.

Now let us consider what experimental measurements suggest.

An experiment of measuring the field intensity distribution along the line conductor is shown below. A classic field indicator (FI), assembled as per scheme in Fig.5, was used as an intensity measuring instrument.



Fig.5
Field indicator principle diagram.

FI was located in immediate proximity to the vibrator but had no galvanic contact with it. Experimental frequencies were selected in accordance with the standing wave coefficient minimum (SWC) for λ, $\lambda/2$, $\lambda/4$. Sinusoidal signal generator was connected to one end of the vibrator (Fig. 6a).



Fig.6
Measured field intensity
along a linear vibrator.

To better understand diagrams in Fig. 6 curves are drawn at the upper and lower ends of each axis L that corresponds to the vibrator location. The curves were run with FI horizontally located on both sides of the vibrator.

From Fig. 6d it is clear that the diagram is axisymmetric and looks like a conic funnel.

Meanwhile, the vibrator directional diagram measured by the monitor receiver far more distant than λ, shows the characteristic that coincides with the simulated one through the Matlab-6 system (See Fig.7). As you can see from this figure, the spatial characteristic of the directional diagram is in the form of a toroid.



Fig.7
Matlab-6-simulated directional diagram of the semi-wave vibrator

A series of alterations was made to explore vortex ether dynamic processes with variable wave length and frequency in line conductors, solenoidal and flat coils, etc.

For certain purposes the solenoidal coil may be considered as a shortcut linear vibrator. On respective frequencies the field intensity distribution along the solenoid corresponds to the linear vibrator. This data may prove useful to many modern engineers of the Tesla transformers and generators. To increase voltage on the cold end a toroid capacitor is set in the Tesla transformers. Nuclear physicists use the hemisphere capacity for the particle accelerators. Thus, a voltage of millions of volts may be achieved.

Flat coils are best explored in terms of field intensity distribution (See Fig. 8)



Fig.8
Field intensity distribution for a flat coil in a closed resonance circuit.

Field intensity distribution on a resonance frequency is correct.

The practical experiment for the case in fig. 6d has shown that the neon lamp that is connected with the vibrator end will be off. And this is with a 100 W generator! It is a paradox, one would say. The measurement diagram shows a "splash" of the field intensity at the vibrator end but we feel nothing. Indeed, when the FI is located as shown in Fig.9 for $\lambda/4$, the "electrodynamic vacuum" will generate. The device showed "0" intensity, which conforms neither with the diagram in Fig.6 nor with the diagram in Fig.7.



Fig.9
Field indicator shows "0" - "electrodynamic vacuum".

The same "vacuum" in the center of tornado was observed by people in the epicenter.

Remember what is measured with the field indicator (an ampere meter) along the linear vibrator. The Ampere force!

So, both people and their environment are in rotation process. The Earth rotates around its axis and around the Sun. The Sun rotates around the Galaxy center. The Galaxy rotates around the center of the Universe. The Universe rotates...

Every space point has an inceptive rotation impulse (torque). Let us remember the analogy. Water flowing out of the tub rotates counterclockwise in the northern hemisphere and clockwise in the southern hemisphere. If you set a right-handed torque in the northern hemisphere, the water will continue to flow counterclockwise.

The electromagnetism is the same. It has a natural left-handed rotation. Nevertheless, practical radiotechnology is familiar with right-handed fields artificially generated by transmitters.

The commonly used term of magnetic interactions is easier to understand if we consider the electromagnetic field as a vortex flow. Two left-handed homogeneous parallel flows are shown in Fig.1. At the point of interaction A of vector projection, the speeds of flow propagation on section plane **A-A** have opposite direction and compensate each other. The actual flow density is $\rho_1 < \rho_2 < \rho_3$. Reduced pressure occurs at point A. The flows are attracted. The resulting attraction vector for the whole flow is radially directed. The counter parallel flows will have composition, i.e. overpressure, and will repel.

One should note that graphic presentation in Fig.1 for vectors H and I for the etherdynamic systems is possible only in special cases. In dynamic vortex flows the current intensity vector is actually directed towards the flow movement and coincides with the vector direction of its propagation speed (V). The resulting vector H remains a radius-vector only for the considered point of interaction of two flows. The flow energy parameters are defined by its propagation speed V (Fig.1).

I am convinced of existence of ether vortex flows in the Universe. Modern astronomic and cosmological surveys confirm my hypotheses of aether Hyper-fields existence on a Universal scale.

The commonly used term of magnetic interactions is easier to understand if we consider the electromagnetic field as a vortex flow.

Even an amateur in aerodynamics and dynamic of gas vortex may make cosmological conclusions:

♦ vortex initiation implies the initial gradient flow of at least two counter flows;

♦ energy parameters of the emerging vortex flow can not exceed those of the parent flows

♦ there exist ether flows with energy exceeding that of our Universe

♦ our Universe has not originated from a point and is not finite. It is the spiral (vortex) structure of our Universe that testifies against the Big Bang hypothesis.

Conclusions:

Practical radiotechnology is familiar with the key difference between the field intensity distribution diagrams of aerial emitters in near and far zones. After combining diagrams 6d and 7b (Fig.10) it is possible to draw certain conclusions.

When transverse waves (radio waves) are formed around the aerial vibrator, the double transformation of the initial flow geometry starts:

♦ **the first flow is a homogeneous spiral flow on the conductor skin-layer;**

¨ **the second flow is a non-homogeneous vortex flow of the near zone;**

¨ **the third flow is a toroidal flow of the far zone.**

The toroid volume alteration in the far zone (as per the transmitter vibration frequency) forms volumetric planar transverse vibrations (spherical waves) that are called electromagnetic or radio waves. The gradient of potentials alterations (as per the transmitter vibration frequency) provoke changes of the Coulomb plane, which form longitudinal vibrations with a narrow directional diagram.



Fig.10.

The longitudinal flow is assumed to be formed as a chain of toroids (like smoke rings)

Ether-dynamic approach provides grounds for more substantial conclusions and assumptions. A new approach to energy and communication systems is made real. Further results of the experiments with transmitters and aerials, assembled on ether-dynamic principles, enabled to draw the following conclusions:

- all reasons, preventing transformation of the transmitter power into the power of transverse radio waves, are evident;
- all reasons for the transverse wave phase lagging with the increase of distance from the emitter, are also evident;
- besides the toroid that forms the transverse wave, the second flow generates a crucially new radiation that has a very narrow directional diagram along its longitudinal axis;
- the aerial ignores wave geometry for the second flow and its longitudinal derivative;
- the radiation along the second flow axis has a very high penetrating power;
- the radiation along the second flow axis has no signs of polarization.

The list of references is not shown in this article due to its size. It can be looked up at **www.efir.com.ua.**

NEWS

In October 2003 the second stage of the research on the “time control” was completed. In the photo below you can see Chernobrov V. A. and Frolov A. V. in the laboratory, October 31st 2003.

The second stage conclusions are quite interesting, however the usage of timers (chronometers) as detectors is proven to be inappropriate for they are subject to magnetization and their indication variations cannot be reliable in this case.

The next stage will feature the following method of detection of the time rate changes (the rate of the matter existence) that is the radiation wave-length measurement. If it is possible to achieve significant results then we will be able to detect the change of the laser ray colour in the area of the effect and its linear path deviations. The experiments will be held to register the weight changes of the detector at the expected influence of the produced effect on the ether density.

Our company looks for cooperation with corporations, which are interested in the application aspects of these technologies.

Frolov A. V.
General Director, Faraday Lab Ltd
7-812-3803844
http://www.faraday.ru

CELL OF THE THIN PLASMAELECTRIC HEAT GENERATOR

Ph. M. Kanarev, A.I. Tlishev, Russia
E-mail: kanphil@mail.kuban.ru

EC
28 / 1!

The main task of the experiment was to check the hypothesis: "Electrodynamic influence on the water molecules gives the possibility to significantly reduce energy expenses on destruction of their chemical bonds; further fu-sion of these molecules considerably increases the output of additional energy in the form of heat".

In order to solve this task, special experiments were carried out as regards the electrodynamic destruction of chemical bonds of water molecules by electric pulses of various frequencies.

Photo of the Thin Plasmaelectric Heat Generator

CHECK TEST RECORD FOR PLASMAELECTRIC HEAT GENERATOR

Table 1

	Indices	1	2	3	Avg.
1	mass of the solution, which has passed through the reactor m, kg.	0.470	0.432	0.448	0.450
2	temperature of solution at the input of the reactor t_1, degrees	22	22	22	22
3	temperature of the solution at the output of the reactor t_2, degrees	66	66	65	65.67
4	temperature difference of the solution $\Delta t = t_2 - t_1$, degrees 44	44	43	43.67	
5	durability of the experiment $\Delta\tau$, s	300	300	300	300
6	reading of voltmeter V, V	4.50	4.50	4.50	4.50
6'	**Reading of oscillograph , U', V**	**4.47**	**4.47**	**4.47**	**4.47**
7	reading of ammeter I, A	2.1	2.1	2.1	2.1
7'	**Reading of oscillograph , I',** A	**2.2**	**2.2**	**2.2**	**2.2**
8	electric power consumption according to indices of voltmeter and ammeters, $E_2 = I \cdot V \cdot \Delta\tau$, kJ	2.84	2.84	2.84	2.84
9	power the heated solution, $E_3 = 4.19 \cdot m \cdot \Delta\tau$, kJ	79.64	80.01	80.72	80.46
10	**reactor efficiency index $K = E_3 / E_2$**	**28.04**	**28.17**	**28.42**	**28.21**

Supply voltage and current were measured with the help of a voltmeter, an ammeter and an oscillograph (Fig. 1-4)



Fig. 1
Voltage



Fig. 2
Voltage



Fig. 3
Current



Fig. 4
Current

Process parameter calculation according to the oscillograms (Fig. 1-4) to the check test record (Table 1) gave the following results:

♦ Pulse scale 10.

♦ Average voltage amplitude according to Fig.1 and Fig. 2: Ua_{av} = (23+25+28+10+26+29) x 10/6 = 235 V.

♦ Average current amplitude according to Fig. 3 and Fig. 4: Ia_{av} = (20+6+17+7+10+19+3) x 10/7 = 117 A.

♦ Pulse repetition period T = 7.4 ms. Pulse duration t_p = 0.28 ms.

♦ Pulse frequency f = 1000/7.4 = 135.1 Hz. Relative pulse duration S = 7.4/0.28 = 26.32.

♦ Space factor Z = 0.5/26.32 = 0.019.

♦ Average pulse voltage U_{av} = 0.019 x 235 = 4.47 V.

♦ Average current in pulses I_{av} = 0.019 x 117 = 2.22 A.

Thus, it is possible to consider that the experimental test of energy efficiency of the water electric heat generator with the help of two methods gives practically identical results and confirms the above-mentioned hypothesis concerning the possibility to generate additional energy in the processes under consideration. It should be noted that as during measurements the pointer instruments of high class of accuracy of 0.2 have been used (relative conventional gauging error does not exceed 0.2%), and oscillographic measurement accuracy is much lower (usually, about 5%), the readings of the voltmeter and the ammeter should be considered more accurate.

Commercial efficiency of the water electric heat generator will depend on pulse generator economy. Since efficiency of powerful pulse generators can be near one unit, energy efficiency in industrial plants that use the considered heat generators should not differ greatly from the data obtained during laboratory research.

Simplicity and one hundred per cent reproducibility of the described experiments open a prospect for quick commercialization of the water electric heat generator.

REFERENCES

1. Kanarev Ph.M. The Foundation of Physchemistry of Microworld (the second edition). (In Russian) http://www.ikar.udm.ru/sb28-2.htm
2. Kanarev Ph.M. The Foundation of Physchemistry of Microworld. The second edition. (In English). http://book.physchemistry.innoplaza.net
3. Kanarev Ph.M. Water Electric Generator of Heat. http://Kanarev.innoplaza.net

Professor Kanarev looks for co-projects with prospective investors.

• Fantastic Projects •



Smith's Generator

Review

TransWorld Energy,
8110 Bent Oak Lane Spring, Texas 77379, USA
Email: donsm1@earthlink.net
http://altenergy-pro.com

Don Smith is a University degreed professional in science & engineering. Served in three wars; WWII, Korea and Vietnam. He has enjoyed a long and successful profession as an executive in the petroleum industry. His life long outside interests include electronics and engineering. A popular walk on substitute for University Professors in physics, chemistry, biology and computer assisted drafting. Teaching style similar to Richard Feynman. He enjoys celebrity status in Japan and Saudi Arabia.

About 20 years ago, the book "Inventions, Researches and Writings of Nicola Tesla", resulted in his reconstructing, as a way of understanding the many theories and devices shown in the book. From this encounter, a very strong bonding resulted. The object then became putting his thinking inside that of Tesla, such that expanding upon and extrapolating areas not yet reached by Tesla. Technological advances in materials provide sourcing for devices not possible at earlier periods. For example, magnetic permeability which is the counter part of negative resistance is an open field for experimentation today.

Don does not sell his inventions, but trades licenses for shares in companies which then incorporate the new technology into their marketing systems. As such, he is on the Board of directors of several well established ventures located in Japan, Brazil, Mexico and Saudi Arabia.

Successful reproductions of Don's technology are present in Finland, Saint Petersburg - Russia, Yugoslavia, Romania, Japan, Hong Kong, and numerous other Countries. His book "Resonance Energy Methods" has a circulation of 40,000 copies in worldwide in many languages.

generators can be near one unit, energy efficiency in industrial plants that use the considered heat generators should not differ greatly from the data obtained during laboratory research.

Simplicity and one hundred per cent reproducibility of the described experiments open a prospect for quick commercialization of the water electric heat generator.

REFERENCES

1. Kanarev Ph.M. The Foundation of Physchemistry of Microworld (the second edition). (In Russian) http://www.ikar.udm.ru/sb28-2.htm
2. Kanarev Ph.M. The Foundation of Physchemistry of Microworld. The second edition. (In English). http://book.physchemistry.innoplaza.net
3. Kanarev Ph.M. Water Electric Generator of Heat. http://Kanarev.innoplaza.net

Professor Kanarev looks for co-projects with prospective investors.

• Fantastic Projects •



Smith's Generator

Review

TransWorld Energy,
8110 Bent Oak Lane Spring, Texas 77379, USA
Email: donsm1@earthlink.net
http://altenergy-pro.com

Don Smith is a University degreed professional in science & engineering. Served in three wars; WWII, Korea and Vietnam. He has enjoyed a long and successful profession as an executive in the petroleum industry. His life long outside interests include electronics and engineering. A popular walk on substitute for University Professors in physics, chemistry, biology and computer assisted drafting. Teaching style similar to Richard Feynman. He enjoys celebrity status in Japan and Saudi Arabia.

About 20 years ago, the book "Inventions, Researches and Writings of Nicola Tesla", resulted in his reconstructing, as a way of understanding the many theories and devices shown in the book. From this encounter, a very strong bonding resulted. The object then became putting his thinking inside that of Tesla, such that expanding upon and extrapolating areas not yet reached by Tesla. Technological advances in materials provide sourcing for devices not possible at earlier periods. For example, magnetic permeability which is the counter part of negative resistance is an open field for experimentation today.

Don does not sell his inventions, but trades licenses for shares in companies which then incorporate the new technology into their marketing systems. As such, he is on the Board of directors of several well established ventures located in Japan, Brazil, Mexico and Saudi Arabia.

Successful reproductions of Don's technology are present in Finland, Saint Petersburg - Russia, Yugoslavia, Romania, Japan, Hong Kong, and numerous other Countries. His book "Resonance Energy Methods" has a circulation of 40,000 copies in worldwide in many languages.

Abstract

Mr. Don Smith has discovered that Ohm's Law of Resistance does not apply to Magnetic Resonance that travels unrestricted for great distances. Therefore, multitudes of electrons are disturbed. The Magnetic moments are translated into usable electric energy. The Magnetic Dipole provides an unlimited source of electrical current. Mr. Smith's "Dipole Transformer" has been pending since last September.



Fig.1
Smith's Energy Receiver

Useful energy occurs as the result of imbalances of ambient background energy and it is a transient phenomenon. In conventional circuits, the electrical field is in a closed system that is damped out with heat loss, which severely limits its utility. **The flip side of the electron generates magnetic waves, which is an open system, not subjected to heat loss. These being unrestricted are the universal source of energy. Universally present electrons are flipped to their electrical position, resulting in useful energy.** When properly constructed an electrical circuit can become self sustainable once started. An obvious corollary would be that the number of radio or television receivers in operation does not deplete the magnetic wave source providing the service. The key source of unlimited energy is Magnetic Resonance. To understand this requires putting a stake through outdated physics. An obvious example is the piano where the key impacts the one note giving one sound, which resonates with its two side keys providing a much higher level. Magnetic Resonant Energy clearly amplifies demonstrating more energy out than in. **Excess energy consequent to a reaction is called Free Energy and can be very large as is in the case of Magnetic Resonance.** The intentionally ignorant physicist makes a habit of ignoring this fact.

Useful electricity is obtained from disturbed electrons, which radiate magnetic fields and waves. The generator disturbs and collects this



Fig.2
D. Smith's Energy Receiver

emitted electron energy. These electrons remain fully in tact and undiminished until the end of time. This Energy is free and the cost of accessing it depends on the ignorance of the collector. With an appropriate collector system an unending source of environmentally benign, inexpensive, available energy everywhere, is provided.

Editor: in September 2003 Donald Smith took part in the annual "Inventor's Week-end" Conference where he presented the report on his invention. In this issue you can find more details on the conference.

*It is worth of a note that we have received **a number of negative comments on this inventor's work**. However, we thought his articles to be quite interesting and decided to publish them. We would be glad to get readers' comments, who are familiar with the work and inventions of Donald Smith.*

NEWS

News from Farady Lab



Disk permanent-magnet generator
Faraday Lab Ltd



In our lab we are still working at the optimization of the alternator design (electromagnetic generator with the permanent magnets). We have introduced the drum rotor instead of the disk rotor into the new design of the alternator. The operation mechanism is the same, namely, the alternation of the magnetic flux near the generator coils occurs as a result of the rotating elements operation of the rotor, which "shunt" the magnetic flux.

Frolov A.V.

Strategies for Launching a New Over-Unity Device

Ryan S. Wood, USA
14004 Quali Ridge Drive, Broomfield, CO 80020

Problem description: With any singly successful over-unity energy device comes a host of business, technical and financial problems and opportunities. A public announcement permanently will lead to a "Pons & Fleishman" effect that at best delays public success and at worst derails the entire technological effort. Careful attention needs to be applied to the marketing launch, replication, patents, legal defense and finances.

Potential Solution: With a few working devices that generate100-500 horsepower it is relatively easy to hook these units to the electrical gird and generate monthly checks from the utilities. The law states that major utilities must purchase electricity from any supplier at "cost avoidance" rate now typically, between 6 and 10 cents per kilowatt-hour. This law, California Public Utilities Commission - Rule 21, for example, is designed to help small hydro-electric producers and solar or wind farms. There is a safety requirement of grid transfer switches, but they are not terribly complicated or expensive. The entire equipment set-up must be approved by the utility, however, if you start with a diesel electric generator or small hydro plant it can be approved, operating and stable before the clandestine switch or hybrid operation with an over-unity machine. The law is strongly supportive of the energy producer and disconnection for non-safety or maintenance reasons is exceeding rare.

A key benefit of this approach is that you have established repeatability by having multiple working sites, you have established that it can generate money and the technology does real work and you have created several independent locations where press and scientists can visit to validate the over-unity effectiveness in-situ.

Typical revenues would be as follows:

Generator Horse Power	100	200	300	400	500
Annual $, 90% uptime @ 6 c/kWh	$ 35,100	$ 70,199	$ 105,299	$ 140, 398	$ 175, 498
Monthly payment @ 6 c/kWh	$ 2,92	$ 5,850	$ 8,775	$ 11,700	$ 14, 625
Annual $, 90% uptime @ 10 c/kWh	$ 58,499	$ 116, 999	$ 175, 498	$ 233,997	$ 292, 496
Monthly payment @ 10 c/kWh	$ 4,875	$ 9,750	$14, 625	$ 19,500	$ 24, 375

It will take money without the strings of investors to champion and defend a new breakthrough technology into the energy marketplace and this strategy offers a quiet way to prepare for the ultimate launch and resulting scientific and media frenzy that will ensue. It will take years for the business to form, products to be built and marketing and acceptance and industry confidence to be established. All during those years this strategy can generate cash to support engineering and operations.

Please call if there are questions at 303-941-9663 (cell),
Home: 720-887-8071
Ryan S. Wood

The Hutchison Effect – An Explanation

Mark A. Solis, USA
http://www.geocities.com/ResearchTriangle/
Email: your_neighbor_2000@yahoo.com

People often ask, "What exactly is the Hutchison Effect?" This brief essay is an attempt to answer that question to the satisfaction of the majority. First of all, the Hutchison Effect is a collection of phenomena which were discovered accidentally by John Hutchison during attempts to study the longitudinal waves of Tesla back in 1979. In other words, the Hutchison Effect is not simply a singular effect. It is many.

The Hutchison Effect occurs as the result of radio wave interferences in a zone of spatial volume encompassed by high voltage sources, usually a Van de Graff generator, and two or more Tesla coils.

Editor: We can call this effect "The H. Wells Effect" because he was first to describe it in his book "The Invisible man". The main character of the book used two sources of electro-magnetic vibrations and Wells said that they were not Hertz waves but something else. "But the essential phase was to place the transparent object whose refractive index was to be lowered between two radiating centers of a sort of ethereal vibration..."("The Invisible Man", chapter 20).

A. V. Frolov



The effects produced include levitation of heavy objects, fusion of dissimilar materials such as metal and wood, the anomalous heating of metals without burning adjacent material, spontaneous fracturing of metals (which separate by sliding in a sideways fashion), and both temporary and permanent changes in the crystalline structure and physical properties of metals.

Fig.1 represents the proof of Hutchison Effect based on metal blocks. Deformation occurred at room temperature as a result of complex interaction of electromagnetic fields.

The levitation of heavy objects by the Hutchison Effect is not - repeat not - the result of simple electrostatic or electromagnetic levitation. Claims that these forces alone can explain the phenomenon are patently ridiculous, and easily disproved by merely trying to use such methods to duplicate what



Fig.1

Cold melting of metals

The upper left: steel, The lower left: aluminium with coin prints and with a coin inserted in a partially open split; The lower right: fully torn aluminium bar; The middle upper and right: a section part of the aluminium block, into which a wood block is fused (brown matter)

http://www.rumormillnews.com/JOHN-HUTSHISON2.htm

the Hutchison Effect has achieved, which has been well documented both on film and videotape, and has been witnessed many times by numerous credentialed scientists and engineers. Challengers should note that their apparatus must be limited to the use of 75 Watts of power from a 120 Volt AC outlet, as that is all that is used by Hutchison's apparatus to levitate a 60-pound cannon ball.

The fusion of dissimilar materials, which is exceedingly remarkable, indicates clearly that the Hutchison Effect has a powerful influence on Van der Waals forces. In a striking and baffling contradiction, dissimilar substances can simply "come together," yet the individual substances do not dissociate. A block of wood can simply "sink into" a metal bar, yet neither the metal bar nor the block of wood come apart. Also, there is no evidence of displacement, such as would occur if, for example, one were to sink a stone into a bowl of water.

The anomalous heating of metal without any evidence of burning or scorching of the adjacent materials (usually wood) is a clear indication that possibly the nature of heat may not be completely understood. This has far-reaching implications for thermodynamics, which hinges entirely on the presumption of such knowledge. It should be noted that the entirety of thermodynamics is represented by the infrared portion of the electromagnetic spectrum, which is insignificant in a context of 0 Hz to infinite Hz. The anomalous heating exhibited by the Hutchison Effect shows plainly that we have much to learn, especially where thermodynamics and electromagnetism meet.

The spontaneous fracturing of metals, as occurs with the Hutchison Effect, is unique for two reasons: (1) there is no evidence of an "external force" causing the fracturing, and (2) the method by which the metal separates involves a sliding motion in a sideways direction, horizontally. The metal simply comes apart.

Doctor John Hutchison

Some temporary changes in the crystalline structure and physical properties of metals are somewhat reminiscent of the "spoon bending" of Uri Geller, except that there is no one near the metal samples when the changes take place. One video shows a spoon flapping up and down like a limp rag in a stiff breeze. In the case of permanent changes, a metal bar will be hard at one end, like steel, and soft at the other end, like powdered lead. Again, this is evidence of strong influence on Van der Waals forces.

The radio wave interferences involved in producing these effects are produced from as many as four and five different radio sources, all operating at low power. However, the zone in which the interferences take place is stressed by hundreds of kilovolts.

It is surmised by some researchers that what Hutchison has done is tap into the Zero Point Energy. This energy gets its name from the fact that it is evidenced by oscillations at zero degrees Kelvin, where supposedly all activity in an atom ceases. The energy is associated with the spontaneous emission and annihilation of electrons and positrons coming from what is called "the quantum vacuum." The density of the energy contained in the quantum vacuum is estimated by some at ten to the thirteenth Joules per cubic centimeter, which is reportedly sufficient to boil off the Earth's oceans in a matter of moments.

Given access to such energies, it is small wonder that the Hutchison Effect produces such bizarre phenomena. At the present time, the phenomena are difficult to reproduce with any regularity. The focus for the future, then, is first to increase the frequency of occurrence of the effects, then to achieve some degree of precision in their control.

> *The spontaneous fracturing of metals, as occurs with the Hutchison Effect, is unique for two reasons: there is no evidence of an "external force" causing the fracturing, and the method by which the metal separates involves a sliding motion in a sideways direction, horizontally. The metal simply comes apart.*

Editor: On November 17th 2003 we got to know that the inventor John Hutchison can eventually lose his home laboratory. The property can be confiscated upon court order due to neighbours' complaints. Apparently, it is dangerous to conduct experiments of the kind at home and even within a town. We wish him success!

A. V. Frolov

A SIMPLE DEVICE FOR HEAT TO ELECTRICAL ENERGY CONVERSION BY MEANS OF FERROELECTRICS

A. Ries, A. Z. Simoes, M. A. Zaghete, J. A. Varela,
Institute of Chemistry, Universidade Estadual Paulista, Rua Prof. Francisco Degni s/n,
14801-970 Araraquara-SP, Brazil
Email: ries@posgrad.iq.unesp.br

E. Longo,
Department of Chemistry, Universidade Federal de Sao Carlos, Rodovia Washington Luis - km 235, 13565-905
Sao Carlos-SP, Brazil

Introduction

A few years ago, Zaev [1, 2] demonstrated experimentally the possibility of heat to electrical energy conversion by means of ferroelectrics. A capacitor filled with a ferroelectric material was charged and discharged periodically at a temperature just a little lower than the Curie point. According to Zaev, the capacitor must have a nonlinear capacitance $dC/dV > 0$, which means the capacitance increases with rising voltage. Besides these experimental results, it was proven by a theoretical calculation that the electrical energy obtained during discharging can reach up to 1.35 of the energy introduced to charge the capacitor. The present paper presents an inexpensive and simple electric circuit which can be used to prove heat to electricity conversion experimentally. Moreover, the physical mechanism of heat to electricity conversion is explained in the form of a thermodynamic cycle.

Thermodynamic cycle for energy conversion

The following thermodynamic cycle is composed of four reversible steps. It works only at a temperature just a little lower than the Curie point, where the dielectric constant is highly temperature dependent. Fig. 1 shows the relative dielectric constant of a representative ferroelectric ceramic as a function of temperature.



Fig. 1
Relative dielectric constant versus temperature for a barium strontium titanate ceramic (80% Ba, 20% Sr) prepared by the author. Curie point = 55° C.

As it can be seen, just below the Curie point in the range from 50 to 55^{0}C, small changes of the temperature cause high changes of the dielectric constant.

Furthermore, to understand the conversion mechanism, it is necessary to understand the electrocaloric effect. When an electric field is applied to a dielectric medium, the latter is polarized. For ferroelectric materials, the parallel domain alignment is the most important part of the total polarization. During the successive alignment of the domains, some material parameters in particular entropy, heat capacity and temperature change. Since the material possesses less degrees of freedom in the polarized state, its entropy and heat capacity are reduced. As a consequence, provided that no heat exchange with the environment is possible (adiabatic conditions), the temperature increases. It is very important to understand that the energy for warming of the dielectric is not taken from the polarizing electric field. The increase in temperature is a result of the decreased heat capacity only.

From this, it can be derived easily what means "nonlinear capacitance".

When a capacitor is charged adiabatically which means its voltage increases faster than any heat exchange with the environment is possible, due to the electrocaloric effect, the temperature of the dielectric must also increase. As it can be seen from Fig.1, below the Curie point, an increasing temperature leads to a higher dielectric constant. Assuming that both temperatures, the one before charging and the other after charging are still below the Curie point, one can say that the dielectric constant increases with an increase in voltage.

Since the capacitance is proportional to the dielectric constant, the capacitor has a nonlinear characteristic $dC/dV > 0$. In the same way it can be concluded that adiabatic charging just a little above the Curie point reveals a nonlinear capacitor characteristic with $dC/dV < 0$.

Quantitative experimental measurements on the electrocaloric effect in some representative ferroelectric and antiferroelectric materials were published by Thacher [3].

STEP 1: Adiabatic charging of the capacitor

We consider a capacitor filled with a ferroelectric medium at an environmental temperature a little lower than the Curie point.

An adiabatic charging of a capacitor (no heat exchange) effects an increase in temperature and capacitance due to the electrocaloric effect. We assume that this increase in temperature is so small that the temperature remains below the Curie point. Finally, the capacitor is completely charged while the dielectric medium has a higher dielectric constant and therefore a higher capacitance than it posseses at the environmental temperature.

To go further to step 2, the capacitor is hold under conditions where no discharge is possible, e.g. it is disconnected from the power supply.

STEP 2: Thermal equilibration

After a short time, the charged capacitor has cooled down to the environmental temperature. While cooling down, the dielectric constant and capacitance decrease. But the charges of the capacitor plates remain constant. As a consequence, the voltage and the electrical energy increase. This can be readily recognized from the general capacitor equation $q = C V$ (q = charge, C = capacitance, V = voltage):

$$q = \text{constant} = C_1 V_1 = C_2 V_2$$

STEP 3: Adiabatic discharging of the capacitor

While discharging the capacitor the temperature and capacitance decrease (again heat capacity changes) due to the electrocaloric effect, leading to a further increase in the available electrical energy. The ferroelectric medium posseses now a final temperature below the temperature of the environment.

STEP 4: Thermal equilibration

In order to proceed with step 1, it is necessary to reach the environmental temperature. An inflow of heat from the environment to the dielectric material is required.

Electric circuit to observe energy conversion



Fig. 2
Electric circuit for testing the energy conversion effect. The connections to the square wave generator are labeled with 0V and +/- 5V, the resistors Rb are to adjust the maximum base current of the transistors.

Assuming the experimenter has a nonlinear capacitor, the set-up shown schematically in Fig. 2 is proposed as a possible conversion device. The circuit contains two different types of transistors (NPN and PNP) which fulfill here the function of a switch.

The NPN junction transistor consists of two n-type semiconductors (called the emitter and collector) separated by a thin layer of p-type semiconductor (called the base). On the other hand the PNP junction transistor consists of a thin layer of n-type semiconductor lying between two p-type semiconductors. The base is the ON/OFF switch for the transistors. If a current flows to the base, there is a path from the collector to the emitter, where a current can flow (switch is ON). If there is no current flowing to the base, then no current can flow from the collector to the emitter (switch is OFF).

The charging-discharging process is controlled by a square wave generator which produces an output signal switching from +5V to -5V. The switching frequency is adjustable from 0.1 Hz up to at least 10 kHz. This output signal is applied to the bases of both transistors.

During the time the square wave generator output signal is +5V, a base current flows through the base-emitter junction of the NPN transistor which creates a low resistance path between the collector and the emitter. As a consequence, the capacitor is charged by the battery. The collector-emitter junction of the PNP transistor has a very high resistance, because here no base current flows. Therefore the capacitor is not discharged at the same time. When the output signal switches to -5V, a current flows to the base of the PNP transistor and not to the base of the

NPN transistor. Now the capacitor is discharged.

In order to understand the function of the inductance in Fig. 2, we analyze the thermodynamics of the charging process.



Fig. 3
Simple circuit for charging a capacitor

If a linear capacitor of capacitance C is charged to a voltage V through the load R according to Fig. 3, the energy $W = 0.5\ C V^2$ is stored in the capacitor. During the charging process, a time-dependent current I(t) flows:

$$I(t) = V/R \exp(-t/RC)$$

This current develops the heat Q in the load:

$$2Q = R \int I^2(t)dt = 0{,}5CV^2$$

Here the integration limits are from zero to infinity. This calculation shows, that the energy taken from the battery is the energy stored in the capacitor after charging plus the heat produced in the load, also 2•C V2. One can see that the heat Q is not dependent on the resistance value R.

The above used equations are only valid in case of a one-step charging process.

If the capacitor is charged stepwise to the final voltage V, e.g. using a ramp generator, and each voltage step effects a voltage increase , the total heat produced in the load is (N = number of voltage steps):

$$Q = N\ 0{,}5\ C\ (V/N)^2 = 0{,}5\ C/N\ V^2$$

Now the energy taken from the source is:

$$W = 0{,}5 \cdot (1 + 1/N)1/2\ CV^2$$

If the number of steps N tends to infinity, the heat Q tends to zero.

This energy loss in the load dramatically influences the efficiency of any conversion device and must be taken into account, otherwise all experimental attempts to observe energy conversion would fail.

A more detailed discussion on charging a capacitor and the unavoidable energy losses was given by Heinrich [4] and Gupta et al. [5].

The inductance in the circuit (Fig. 2) effects a slower rising of the current during the charging process (due to self induction) and can reduce the heat generated in the load dramatically.

Acknowledgments

Financial support of this work was provided by the Brazilian agency FAPESP (www.fapesp.br) and the German Academic Exchange Service (DAAD), (www.daad.de).

References

1. N.E. Zaev, Yu.S. Spiridonov, Capacitance as a converter of heat to electrical energy, Russian Electrical Engineering, Vol. 69, (2000) pp. 69-72
2. N.E. Zaev, Research on the Capacitance Converter of Environmental Heat to Electric Power, New Energy Technologies, issue 2, (2001)
3. P.D. Thacher, Electrocaloric effects in some ferroelectric and antiferroelectric Pb(Zr, Ti)O3 compounds, Journal of Applied Physics, Vol. 39, (1963), pp. 1996-2002
4. F. Heinrich, Entropy change when charging a capacitor: A demonstration experiment, American Journal of Physics, Vol. 54, (1986), pp. 742-744
5. V.K. Gupta, G. Shanker, N.K. Sharma, Reversibility and step processes: An experiment for the undergraduate laboratory, American Journal of Physics, Vol. 52, (1984), pp. 945-947

• Fantastic Projects •

The Gates Motor

A. Akau, USA
Email: adrianakau@aol.com

The Gates motor company has produced a motor that does not run on fossil fuel or on electricity. It comes in a 28 HP and a 5,000 HP version. When linked to an electric generator, the larger motor will produce 2,200 kW.

My name is Adrian Akau. I am a recently retired school teacher, having taught science and math in the public school system, state of Hawaii for the past 36 years. One of the classes I taught was on energy.

Our world should be reaching the half-way mark in easily accessible oil by about the year 2016. Since the rate of oil usage is becoming higher each year, it is unlikely that the oil supply will last as long as the 140 years since the first well was drilled in Pennsylvania. We will become more dependent upon OPEC with all the political pressures and problems that accompany this type of dependency. As the easy oil is consumed, we must look for ways to extract less accessible oil such as from shale. The added expense will be passed on to the consumer.

The burning of coal is not the answer either because coal cannot supply convenient energy as does oil. An oil-based economy cannot transfer over readily to natural gas; there is not enough natural gas available and it is again, not a convenient and concentrated source as is oil. We also have serious pollution problems with the burning of fossil fuels (natural gas being the exception) but the burning of all fossil fuels have contributed to the serious problem of global warming.

It may take all of 50-80 years to transfer to a non-fossil fuel economy. The transfer must be made slowly so as not to disturb the infrastructure of our economy which is presently based upon fossil fuels. We must gradually create a new infrastructure that is non-fossil fuel dependent.

> *The motor incorporates a unique spring configuration to provide rotation*

The production model of the motor is 24 inches high by 48 inches in length. Connected to a generator it will provide sufficient power for about eight hundred US homes. It is designed to be tough and to last a long time. It uses a high grade airplane synthetic engine oil to prevent friction and the build up of heat. Only the oil filter needs to be changed. The motor has special needle bearings and portions of the motor are made of high quality steel.

The Gates motor is designed to run 24 hours/day, 365 days/year without incurring any fuel costs. The larger size motor would come in pairs; the spare motor being used as a back-up unit should the regular motor be turned off for maintenance such as to change the oil or in case there should be any problems with the first motor. The company is willing to enter into a contract for maintaining the motor after installation.

The Gates motor represents a major breakthrough in motor design technology and provides practical solutions to environmental and fuel conservation concerns. **Finally, a completely mechanical motor has been developed.** It can deliver the power needed in a wide variety of service applications without any waste products or emissions to adversely affect the environment. This revolutionary new motor utilizes spring power technology. Unlike conventional motors which must reach a maximum rpm level before the desired horsepower, the Gates motor provides maximum horsepower instantly by virtue of the torque stored in the springs.

The basic operating principle of the Gates motor involves a series of springs configured to provide the required motor rotation and power delivery. Consider, if you will, the operating principle of a grandfather clock. Once the clock is wound, it continues to operate until it runs down and stops. The springs must then be rewound so it will operate again. Suppose the clock is continually being rewound as it operates. Then the clock would run continuously. This condition is what forms the basis for the operating principle of the Gates motor. The motor incorporates a unique spring configuration to provide rotation. The springs inside the motor are wound and preset at the factory at the time the motor is assembled. The amount of torque wound into the springs at the factory determines the horsepower of the motor. Inside the motor are a multiple of springs positioned horizontally in a circular arrangement. As the motor operates, the springs are unwound a set number of degrees. A double ratchet system at one end of the motor rewinds the degrees used back into the springs. As the springs are unwinding, **the power generated from all the springs reset each spring (one at a time) during each revolution of the motor**. It is this reset action that produces and delivers power from the springs to the flywheel located at the opposite end of the motor. The flywheel serves to ensure the smooth operation of the motor and to convert the springs into useable horsepower. The smaller motor has 50 foot pounds of torque at a shaft speed of 3000 RPM and will produce 28 HP. The HP can be altered by factory adjustment. The speed of the engine is controlled by a hydraulic pump which provides pressure upon the power shaft.

Contacts: Gates Motor Corporation,
P.O. Box 715, Hauula, HI, USA 96717
Email:gagates@earthlink.net

Editor: We tried to get the video of this device operation from Gates Motor Co., but after a long consideration it was not provided since the authors are competitor-conscious.

Alexander V. Frolov

Longitudinal Waves

Cold Electricity

Adrian Akau, USA
Email: adrianakau@aol.com

Dr. Peter Lindemann in his book "The Free Energy Secrets of Cold Electricity" presents the story of this type of electricity which really is not electricity as electricity is normally meant to be understood. Cold electricity behaves differently than normal electricity. Regular electricity may be used in the process to generate this cold form but this transformation is not the type of change in voltage and current that occurs in a transformer. Rather, it is the extraction of a form of current from "normal" electricity by a process that uses high voltage.

In discussing the Edwin Gray motor, Dr. Lindemann relates a demonstration by Gray. Gray used a 6 volt car battery with lead wires running to a system he had devised using a voltage booster and a series of capacitors which raised the voltage to 3,000 volts. He then closed a switch that ran the high voltage into two electromagnets which caused a loud popping sound and cause the top electromagnet weighing a pound and a quarter to be propelled over two feet into the air. Gray claimed that only 1% of the system's energy was used with 99% going back to the battery. He said that he had 'split the positive' with his system.

Other evidence of using this fractionated electricity was Gray's use of a small motorcycle battery (15 amps which would normally produce W=V x A = 6 V x 15 A= 90 watts) to run concurrently six 15-watt electrical light bulbs, a portable 110 volt T.V. set and two radios. A glowing 40 watt light bulb running off the system was dropped into water without the glass breaking; the bulb gave off light but not the heat that accompanied a bulb run by regular electricity. This would mean that tungsten in the filament of the light bulb was not resisting the flow of this fractionated electricity and that this "cold electricity" was causing the luminous glow by some other means.

According to Gray's Patent #4,595,975, low voltage was chopped into pulsating DC by passing it through a multi-vibrator (buzzer like a door bell). Then the pulsed DC was sent through the low voltage winding (primary) of a transformer which changed it to pulsating high voltage DC current at the secondary side. The pulsating high voltage DC was rectified by a full wave bridge and changed into high voltage DC.

The high voltage DC was used to repeatedly charge a capacitor as the current was sent to briefly discharge across a spark gap (rated at 3000 volts). The discharge of the spark across the gap had to be in one direction only and its duration was controlled by the size of the capacitor and by the strength of a magnetic field encompassing the gap. This magnetic field had a quenching effect because it caused a back EMF each time the discharge occurred. The current from the discharge across the gap was then sent through a resistor and then to a vacuum tube (the conversion switching element tube).

Another of Edward Gray's patents "Efficient Electrical Conversion Switching Tube Suitable for Inductive Loads" (April 1987, patent 4,661,747) described the switching tube. It utilizes a low voltage anode (positive plate), a low voltage anode (positive plate) and one or more electro-static or charge receiving grids (located between the positive plates and the cathode or negative plate supplying the electrons). This tube's function was to 'split the positive'. A normal vacuum tube usually uses only a single anode at a particular voltage to control the voltage flow within the tube. The function of the charge-receiving grids was to collect the "cold electricity".

The most unusual part of this Power Supply circuit consisted of devices specifically designed to remove excess energy when the Switching Tube was functioning. A spark-gap protection device, served to "protect the inductive load and the rectifier elements from unduly large discharge currents". As stated, the rectifier elements are the two anodes and the grids in the Switching Tube. In a normal vacuum tube, no protection would be necessary because the maximum power of the tube would be based upon the electricity provided to heat the tube filament and to charge the anode (voltage x amps). Therefore, the excess energy comes from the process occurring as the spark gap affected electrical pulses pass through the Switching Tube. The process of extracting the "cold electricity" places danger of overload upon the system. (Please take note that the "electricity" from the Switching Tube is no longer the normal type of electricity we have from our batteries or from an electrical outlet but rather a completely new form with entirely different characteristics.)

The description continues, "Should the potentials (voltages) within the circuit exceed the predetermined values fixed by the mechanical size and spacing of the elements within the switching tube, the energy is dissipated (bypassed) by the protective device to the circuit common (electrical ground)" by two strategically placed diodes (devices that permit the passage of electricity in one direction only). The question now arises "What is the cause of this large amount of excess energy which must be dumped to ground through device acting like a lightning rod in order to prevent the circuit from burning out?"

To examine the cause of the excess energy source, we must go back over a hundred years to 1889. Heinrich Hertz had just announced in 1887 that he had discovered electromagnetic waves and Nicola Tesla was attempting to duplicate Hertz's experiments. Tesla used abrupt and powerful electric discharges produced with banks of capacitors charged to very high potentials and was able to explode thin wire (copper bus bars). He came to the conclusion that Hertz had mistakenly associated electrostatic inductions (electrified shockwaves in air) for true electromagnetic waves.

The explosion of the copper bars by means of the "disruptive discharges" from the capacitor bank produced sharp shockwaves which struck Tesla with great force across the entire front of his body. Tesla said they felt more like powerful gunshots rather than electrical sparks. They produced effects similar to lightning or to those produced by high voltage DC generators previously discussed; the simple closing of a high voltage DC generator caused a stinging shock. AC generators were not in use in this pre-AC era and it was shown, later on, that AC generators did not produce these effects.

This shock was first assumed to be the result of residual static charging. It stood straight out of highly electrified conductors, seeking ground paths which included workmen and switchboard operators. In long cables, Tesla estimated that this electrostatic concentration was several orders in magnitude greater than any voltage the DC generator could actually produce. It caused a hedge or crown of bluish needles or spicules to point at right angles to the cable or straight from the electrical cable line into the surrounding space. The bluish needles appeared the very instant the switch was closed and disappeared a few milliseconds later, after which the system functioned normally. However, anyone through whom the blue needles passed, especially in large regional power systems which used high exceptionally high voltages, usually did not survive. Generators rated at a few thousand volts produced hundreds of thousands or even millions of electrostatic volts during the start-up pulse. Highly insulated, heavily grounded relay switches had to be installed to protect workers from certain death.

Engineers at this time assumed **the effect to be caused by a "bunching" action which occurred when a powerful force was not able to move charge sufficiently quickly through a system.** (A similar "choking effect" also happened with large steam engines; if steam was introduced too rapidly, the steam engine could explode.) The metal of which the wire was composed somehow offered resistance to the charge carriers before they were able to move away from the generator terminals. It seemed that the wire acted as a blocking force to the electrons or to some unknown part of the electrons for the first few milliseconds, rather than as a conductor. The powerful, deadly bluish spikes sprang from the line until the current charges actually "caught up" with the applied electrical field. It was as if the spicules were a form of relieving pressure on the system by converting the voltage impulse into some other form.

Tesla began wondering why the electrostatic field moved faster than the actual charges. He believed that this effect could help him find electric waves better than his capacitors because the line resistance caused the electrostatic charges to bunch together into a density much greater that obtainable with his capacitors.

Tesla understood that ordinary capacitor discharges were oscillating currents or spark currents which "bounced" between each capacitor plate until their stored energy was dissipated. The high surge voltage of the DC generator exerted such a high one way pressure on the dense line charges, due to the millisecond resistance of the metal, that possible voltage "bounces" were also oscillations of current as was true with the capacitors. Tesla used every means possible to block the "back-rush" (bouncing) of the oscillating current in order to prevent the supercharge to prematurely decline; he wanted to maintain this powerful "bunching" effect as long as possible in order to study it and to make use of it.

His face and hands experienced a penetrating shockwave; a sharp pressure and an electrical irritation were brought on at the sudden closing of the switch. His face and hands were especially sensitive to these shockwaves which caused a "stinging" effect at close range. Tesla believed that he was being struck by material particles approaching the vapor state as they were thrust from bluish crowned wire.

Later on, he was to discover they were not gas particles. **He placed himself behind a glass shield but to his amazement, he still felt the shockwaves and stinging effects; the glass shield did not protect him.** These stinging rays could be felt at great distances from their sources and, to his amazement, would penetrate shields of both glass and copper. Tesla knew that normal electrostatic charges spread over the surface of a metal (copper, for example) shield so that the stinging effect could not have an electrostatic origin and therefore was not electrostatic in nature but was from some other yet unknown source.

Joseph Henry in 1842 had noticed the magnetization of steel needles by the discharge of a Leyden Jar (type of primitive condenser made with a glass bottle). The Leyden Jar was at the top floor of a building while the needles were in the basement. Dr. Henry, noting the passage of these magnetizing rays through brick walls, oak doors, stone and iron flooring and tin ceilings believed that the spark given off by the discharge released "light-like rays" that passed through the material obstacles with ease before magnetizing the needles.

Elihu Thomson, a physics instructor in 1872 had been attempting to make sparks from a Ruhmkorff Spark Coil more clearly visible for his physics students. He attached one pole of the coil to a cold water pipe and noted that the previously blue spark changed to white. He then attached the other pole to a large metal table top and produced a silver-white spark that would be clearly visible to all attending his lecture. He went to the door of the room to notify his colleague but received a strong shock from the door knob. Turning off the Ruhmkorff coil prevented the brass knob on the oak door to stop shocking. He returned with his friend, again turned on the coil and discovered that all metal objects in the entire building, no matter how distant from the coil or insulated from the floor, produced long and continuous white sparks upon the touch of a penknife or screwdriver.

The device Tesla perfected was far superior to the Ruhmkorff Spark Coil. The effect of his disrupter device was so strong that a single wire placed in an oil bath produced what he had originally but mistakenly thought to be gaseous streams so powerful that they visibly depressed the oil into a depth of about two inches. Tesla concluded that "besides the air, another medium is present".

> *...he placed himself behind a glass shield but to his amazement, he still felt the shockwaves and stinging effects; the glass shield did not protect him. These stinging rays could be felt at great distances from their sources and, to his amazement, would penetrate shields of both glass and copper...*

Tesla had been able to perfect his device by placing a capacitor between the switch and the D.C. generator thus increasing the power and protecting the generator windings in much the same manner as the diodes Edwin Gray's Switching Tube protected Gray's circuit. Tesla also raised the voltage and quickened the "make-break" rate of the switch to increase the power level by placing a powerful permanent magnet crosswise to the discharge path of the high voltage output of the DC generator wires. The magnetic field caused the discharge arc to automatically "blow out"; the charge passing through the wires in the presence of the magnetic field built up reverse emf (electromotive force or voltage).

Tesla believed he had discovered a new type of electricity with special characteristics. This form of electricity did not consist of alternating waves. **They were longitudinal waves** composed of successive shocking waves with effects that could be seen and felt at a distance. **Vector components of these shock waves were unidirectional. They were able to force charges in the direction of their propagation.** In his patent #787,412, "Art Of Transmitting Electrical Energy Through The Natural Mediums" (April 18, 1905), Tesla calculated the mean velocity of the waves propagated by his device to be 471,240 Km/sec. Knowing that the velocity of light is 300,000 Km/sec would indicate that the type of transmission to which Tesla is referring is different than standard electromagnetic radiation; these special longitudinal "Radiant Energy" waves moved faster than the speed of light.

After conducting hundreds of experiments, Tesla found that "Radiant Energy" longitudinal waves **could penetrate all materials and cause "electronic responses" in metals such as copper and silver.** Impulses exceeding 0.1 millisecond duration produced effects such as pain, mechanical pressures, explosion of thin wires and vibration of objects. Impulses of 1.0 microseconds caused the sensation of physiological heat; at still shorter lengths white light would fill the room. Impulses less than 100 microseconds were safe to work with and Tesla planned to use them for his power broadcast system since they could pass through all matter.

In 1890, Tesla discovered that placing a long single turn copper helix near his magnetic disrupter became covered with an envelope of white sparks. Effects were strongest when the helical coil was placed within the disrupter wire circle. In this "shockzone", the coil was surrounded by a blast of long, fluid like silvery streamers which clung to the surface of the coil, flowing over the coil at right angles to the windings. Tesla hypothesized the electrostatic-like effect was due to radiant transformation rules requiring measurements of discharge lengths and attributes of the helix used (number of turns, diameter, etc.). (Editor: resonance)

The new induction law he discovered showed that radiant shockwaves became much stronger when encountering segmented objects. The radiant shockwaves "flashed over" the outer skin of the helix from end to end without passing through the windings of the coil; shockwaves of 10,000 volts introduced to a 24 inch coil rise to 240,000 volts. The greater the resistance in the helix turns, the higher the maximum voltage. This was completely different from magneto-induction. Remember that he was not working with electricity but with radiant shockwaves.

> *Aether particles were incompressible and could easily pass through space and matter with a speed much greater than the speed of light. This was pure radiant matter but, at the same time, pure Radiant Energy. Cold electricity is one of the forms of this Radiant Energy*

This transformer he invented used radiant shockwaves to produce pure voltage without current. Each transformer had to be "tuned" by adjusting the disrupter to a specific impulse duration. At that point, voltage impulses could flow smoothly, flowing over the copper surface much like a stream of water in a pipe. No amperage could be detected but if the stream was aimed at a distant metal plates, "current" was produced which reached several hundred or even thousands of amperes. Tesla then began to wonder what made up this white, currentless stream.

Tesla determined that normal charge carriers (electrons) could not travel as quickly as the radiant pulse; no current moved the coil because the electrons were choked in the metal lattice of the coil. **The radiant pulse moving over the surface of the coil was not electronic in nature.** He placed the legs of a heavy U-shaped copper bus bar directly to the disrupter primary and then connected the short-circuited system to several incandescent lamps. These lamps glowed with a brilliant cold white light as with Gray's light bulb, proving that the power for the light was not electrical in nature. Tesla believed that the electrons were blocked from flowing through the wire while the radiant pulse was released over the coil surface as a "gaseous" pulse (splitting the positive, according to Gray).

Tesla came to believe that voltage could be viewed as streams of aether under various states of pressure and that his transformers affected the aether as to produce the luminous effects he observed. In his patents, he describes his "light-like rays" as tightly constricted aether streams propelled from his transformers along infinitesimal ray lines along which an incompressible movement occurs instantly through space on all points along its path. Aether streams were being drawn in through his transformer at higher natural pressure and then accelerated in the electrical discharge. The voltage in his transformer could control the brilliance of light in a room but this type of light was almost impossible to register on film. He could heat up a room or cause cool breezes by controlling the voltage in impulse duration in his transformer.

Tesla saw electrical current was really a complex combination of aether and electrons. Through the application of a disrupter, the electrons were removed from the gap by the magnetic field while the aether steams continued to flow through the circuit. He considered aether particles highly mobile with infinitesimally small mass and cross-section as compared to electrons. They were incompressible and could easily pass through space and matter with a speed much greater than the speed of light. This was pure radiant matter but, at the same time, pure Radiant Energy. Cold electricity is one of the forms of this Radiant Energy.

Edwin Gray, Dr. Nicola Tesla and Dr. Thomas Henry Moray all used radiant energy technologies. It is important to understand that the Laws of Thermodynamics and Maxwell's equations do not pertain to "Radiant Energy" technologies.

• Fantastic Projects •

Gravity Conversion Rotary Device

Review is prepared by editor Tatiana Ezhova

Here another fuelless perpetuum mobile is presented.



The system design

The design includes a wheel with spring spokes. Pegs may be fixed inside the wheel to balance movement of weights on springs. All parts should be homogenized as to dimension and weight. The author used 4 oz. lead balls and the 3/16" springs. The wheel measures 9" in radius as measured from hub center to center of each lead ball at outer periphery. This device is actuated and stopped by the hand. Its speed is self governing, it ramps up to speed quickly and simply stays there.

Note: you can find more detailed information about the device at http://www.greaterthings.com/News/FreeEnergy/Directory/GravityMotors/photos/. Also read in this issue article "Novozhilov's motor" that describes another wheel motor that does not require any fuel for its operation.

Torsion Technollogies

Xing-liu Jiang, Xiong-wei Wen, China
Science School,
Beijing University of Aeronautics and Astronautics, Beijing 100083
and
Li-jun Han, China
Department of Materials Science and Engineering,
Beijing University of Aeronautics and Astronautics, Beijing 100083

ABSTRACT

Highly localized nuclear activation in electrochemical systems and other electrical discharge processes have been observed by many laboratories in the world. This report is an attempt to explain such anomalous phenomena by using torsion field theory and axion model. Anisotopic behaviours of radiation products, burst character, "heat after death" of excess energy release in electrical discharge systems are considered to be interpreted by the torsion coherence of vortex dynamics with the zero-point energy induced by localized intense field emission of micro-protrusion of the cathode, and the dynamic Casimir effect of transient evolution of triple region of gas, liquid solution, and electrode protrusion. Axion model and Primakoff's effect are proposed for explanation of nuclear transmutation without noticeable gamma radiation.

Nuclear products with high concentration, unidentified tracks with highly collimated lines of low energy nuclear reactions in the electrochemical systems were recorded by CR-39 solid detectors and photo-films, and localized spots with chemical alterations were observed at our laboratory. It is suggested to carry out intensive study of vortex dynamic for explaining the anomalous phenomena in wide area of nature and laboratories. Analysis of vortex dynamics with wide range from pitting corrosion of electrochemical system, laboratory plasma, tornado, to quasar spiral model with extremely high energy cosmic rays in the center region, leads to a conclusion for that vortex dynamics creates torsion fields responding to the anomalous effects.

I. INTRODUCTION

Many laboratories in the world have observed nuclear reactions and **excess heat** in electrochemical systems. The mechanism of such anomalous phenomena is not being well understood according to normally accepted physics.

Nuclear products with high concentration and tracks with highly collimated lines of low energy nuclear reactions in the electrochemical systems were recorded by CR-39 solid detectors and films at our laboratory [1,2]. These facts suggest that quasar model with spiral structure and extremely high enrage cosmic rays in the center could be used to explain the mechanism. It is supposed to use the concept of torsion field to interpret the observed phenomena, typically, the properties of axion acceleration, memory effect, and the polarized nuclear reactions with torsion effect [3].

II. PHENOMENA IN NATURE AND AT LABORLATORIES

The vortex and spiral structures are the archetype that appears at all levels of nature and laboratories, for example, atom structure, vortex lattice in superconductors, dense plasma focus, lightning, quasar etc.

Recent report of dark matter annihilation at the galactic center describes that the cold dark matter near the galactic center is accreted by the central black hole into a dense spike [4]. Particle dark matter annihilation makes the spike to be a compact source of photons, electrons, positrons, protons, antiprotons and neutrinos. It reminds us for that there is a similarity among pitting corrosion with electrochemical noise, laboratory plasma pinching (dense plasma focus, for example), fast laser induced ion beams [5] and quasar spiral model with high-energy cosmic rays in spiral center in spite of large dimension difference. Comparing the experimental results of electrochemical cells with excess heat and nuclear transmutation to astrophysics phenomena, it is supposed that the investigation of vortex dynamics of torsion coherence with the zero-point energy is essential for tapping the zero-point energy.

As it is predicted by quantum mechanics that the vacuum is seething with active energy, even at temperature of zero point Kelvin. This zero-point energy (ZPE) can be thought as an infinite number of virtual photons that are popping out of the vacuum and going back in, but should be a measurable effect en masse. To exam the origin of ZPE background, the interaction of matter with the ZPE can be treated on the basis of charged point particles interaction with a background of electromagnetic zero-point radiation with spectral-energy density.

Based on observation in the experiments, the following features are considered in order to understand the experimental results with electrical discharge systems.

A. ELECTROCHEMICAL DOUBLE LAYER

In an electrolytic cell, the electrolysis with high conductivity and the electrochemical double layer with large layer-capacitance lead to a typical structure of the cathode potential distribution similar to the cathode drop of glow discharge in low gas pressure. For a compact layer the thickness of the double layer is equal to one ionic layer, across which there is a linear fall of potential. Thus, high electric field exists in some regions on the surface of the cathode. The local enhancement of the electric field on the cathode surface with the double layer is related to the protrusions and cracks similar to the tip discharge in air or in a vacuum. The current distribution depends strongly on the surface roughness and the work function of the electron emission. A high transient current density ($> 10^8$A/cm^2) could be expected due to enhanced field.

B. ENERGY CONCENTRATION

On the cathode surface, the high persistent electrical fields ($>10^7$V/cm) and large equivalent capacitance ($>25\mu$F/cm^2) lead to a high energy concentration in the double layer [6]. The concentrated field on the tips of the protrusions or cracks after a long-loading period with deuterium on the palladium cathode surface creates a high transient electron flux because of the large distributed capacitance and the negligible inductance in a localized discharge mini-network. The experimental data show that the reactions take place only in some restricted areas that have specific properties. The idea of micro fusion due to the results of energy concentration and the high deuteron flux could be used to explain the nuclear transmutation.

C.TORSION FIELD AND THEIR EXPERIMENTAL MANIFESTATIONS

Elementary particles have the moment of quantity of motion, i.e. spin. If in any substance the spins of particle have a preferable direction, then it is interpreted as spin polarization of the substance. Every substance creates a torsion-field (or called spin-field or axial field) in the space surrounding it when polarized by spins [7]. The superposition of torsion field, generated by the atomic and nuclear spins of each molecule, determines the intensity of torsion field in the space surrounding each molecule. Torsion field has strong penetration ability and does not interact with the crystal lattice of substances. The torsion field created by rotation of some sort of matter is concentrated in two opposite beams propagating along the rotation axis. The intensity of torsion-field with some lower constant value can be retained for several weeks after the rotation is stopped. Such property of vortex mater has been recently observed in type II superconductors with magnetic flux line lattice [8]. The studies of vortex matter of type II superconductors have shown a number of puzzling phenomena associated with vortex motion, including: low-frequency noise and slow voltage oscillations; a history-dependent dynamic response, and memory of the direction, amplitude duration and frequency of the previously applied current.

Some behaviors of the torsion-field effect have been observed in the experiments of electrolysis regarding the so-called cold fusion, such as when the gas bubble chains come out from the protrusions of the cathode surface a long time after switching off the electrolysis potential. The more surprising thing is the heat after death, which has been recorded by many labs. This phenomenon could be explained by the persistence effect of the torsion-field produced by vortex dynamics of tip effect.

D. EXPERIMENTAL RESULTS IN THE ELECTROCHEMICAL CELL

CR-39 plastic films possessing with a high degree of optical clarity and isotope in track response, and are sensitive to neutron, proton, tritium, alpha, and other charged particles, were used to detect the products of nuclear reactions. The films of CR-39 were immersed in the NaOH electrolyte of heavy water and placed adjacent to the tips of the cathode [9]. After 110 hours, electrolysis experiment with the applied voltage 1 V and current 2 ma, the solid detector was etched by 6.25 N NaOH solution in 70^0C for 11 hours. The photomicrograph shows the cluster of tracks with a cycle crater of 100 μm in diameter and 25 μm in depth. According to the etching condition, the energies of the most of the particles, P, T, α are estimated roughly to be in the range of 1-4 MeV. On the backside of same region of the CR-39 film detector, one can clearly see a few of tracks in the circle area or nearby. Such tracks are believed to be created by recoil-protons of forward incident neutrons. High concentration of the cluster of nuclear tracks could be explained by the quasar spiral model and by the crystal channeling effect [Fig.1]. The experimental results of the generation of tritium with single crystal metal of Pd show that none of the generation of tritium has been revealed by using non-single crystal electrodes [10]. The importance of the crystal channeling effect for nuclear reactions in the electrochemical systems can be inferred.



Fig.1
Schematic presentation of a micropinch spiral by tip effect in the electrolysis cell:
a) tip of the electrode; b) spiral structure of micropinch; c) electron beam; d) crystal channel; e) ion beam

To determine the spatial distribution of radiation active sites (RAS), Black-white 135 films of 27 DIN have been used to image the position of the RAS. After a 1,5 year of deposition in glass tube of finishing electrolysis experiments with light water electrolyte for more than 200 hours running, the patterns of RSA were clearly formed on the films after exposure of 100 hours [2]. The bright spots corresponding to the tips of palladium cathode edges can be seen due to the tip effect. The effect of magnetic field on the traces of the charged particles has been observed while the Pd samples exposing to the films, which were folding and wrapping up the sample, were inserted between couple magnets. The tracks stretching along the film surfaces confirm that the tracks were created by charged particles, electrons for example, with low energy about some keVs. Highly oriented tracks can be observed by autoradiography by using normal films locally[Fig.2].



Fig.2
Autoradiography of charged particle tracks of beta delay isotopes on the surface palladium cathode. Some tracks of beta particles are paralleling the cathode surface.

E. SONOLUMINESCENCE AND "BUBBLE NUCLEAR FUSION"

Some scientists of Oak Ridge National Laboratory in America reported their articles of bubbles experiments in Science. Experimental results show that the radiation lights of sonoluminescence possess three characters: short duration with picoseconds; wide continual spectrum; highly oriented thin beams. **Based on those characters, vortex dynamics with axial acceleration of bubble collapse could be inferred.** Nuclear reaction with abnormal gamma radiation was observed [11]. Dr.Claudia Eberlein describes her conclusion on sonoluminescence that only the ZPE spectrum matches the light emission spectrum, which must be a ZPE phenomena [12]. The effect of torsion field on nuclear reactions along the axis of vortex should be taken into consideration for the low ratio of the nuclear products of n/T due to spin polarization of reaction particles.

Axion model and the Primakoff effect are proposed for explanation of nuclear transmutation without noticeable gamma radiation. Many laboratories in the world have been engaged in several experiments to search for axions, light neutral pseudoscalar particles yet to be discovered. The axion would be produced in the solar core through the Primakoff effect if its mass is a few electronvolts and could be detected in the laboratory.

III. CONCLUSION

Researchers of new energy study of "cold fusion" type should pay great attention to the general processes of electrolysis to find the key points, which could play a major role in the transit from the electrochemical processes to processes of torsion and the nuclear processes. From the authors' point of view, the evolution of double layers is of importance to understand the anomalous effect, typically on the protrusions of cathode. The change of space-time near the tips due to torsion field generated is expected to delivery the zero-point energy, and dynamic Casimir effect for the evolution of gas bubbles on the tips are expected to generate photons and excess heat [1]. The yields of transmutation products are related to the current distribution on the cathode surface. The cathodes of thin wire were benefit to the generation of nuclear reactions and excess heat for electrochemical systems. Careful examination of the evolution of electrochemical double layer will lead to a good understanding of pitting corrosion with electrochemical noise, and further to recognize the anomalous excess heat and nuclear reactions.

Heat after death was observed at many laboratories. It is believed that the persistence behaviors of torsion field can be used to explain such anomalous phenomena.

The contact between beads coated with a thin metallic layer or multilayered film and palladium black particles could be regarded as point-contact similar to the tip-effect [13].

We may say that it is expected to reveal the puzzles of the mechanisms of high-Tc superconductivity with pinning vortices by the torsion field theory [14,15].

REFERENCES

[1] Xing-liu Jiang, Jin-zhi Lei, Li-jun Han, Dynamic Casimir Effect in an Electrochemical System, J. New Energy, Vol.3, No. 4, 47(1999).
[2] Xing-liu Jiang, Chang-ye Chen, Li-jun Han, Tip Effect and Nuclear Active Sites, Proc. of the 7th Intern. Conf. on Cold Fusion, Vancouver, April, 1998, pp.175.
[3] Don Read, Excitation and Extraction of Vacuum Energy Via EM-Torsion Field Coupling Theoretical Model, J. New Energy, Vol. 3, No. 2/3, p.130(1998).
[4] P.Gondolo, J.Silk, Dark matter annihilation at galactic center, Phys. Rev. Lett. 83, 1719(1999).
[5] BPS, Laser light in , stream of protons out, Physics Today, Jan.2000,p.9.
[6] G.Korluem and J.OM. Bookris, Textbook of Electrochemistry Vol. II. Elsevier Publishing company Amstorsan , 1951. P.364
[7] A.E.Akimov, G.I.shipov, Torsion fields and their Experimental Manifestations, Journal of New Energy, 2(2), 67(1999).
[8] Y.Paltiel, E.Zeldov Y.N.Myasoedov el. al. Dynamic instabilities and memory effects in vortex matter, Nature 403, 398 (2000).
[9] X.L.Jiang, L.J.Han and W.Kang. Concentrated energy and Micro Nuclear Fusion, ICCF6, Oct 1996, Japan p.580.
[10] R.L.Matlock, F.E.Collins, G.R.Bancher, Anomalous tritium found in the recombined off gasses during electrolysis using crystal cathodes. Elem. Energy(cold fusion), 26, 28(1998).
[11] Taleyarkhan R P, West C D, Cho J S, Lahey Jr R T, Nigmatulin R I, Block R C. Evidence for Nuclear Emissions During Acoustic Cavitation. Science, 2002 295:1850~1862.
[12] Claudia Eberlein. Theory of quantum radiation observed as onoluminescence, Phy.Rev.Lett.53,2772(1996)
[13] G.H. Miley, G.Narne, M.J.Williams, J.A.Patterson, J.Nix, D.Cravens, and H. Hora, Quantitative Observation of Transmutation Products Occurring in Thin-Film Coated Microspheres During Electrolysis, Proceedings of ICCF-6, OCT. 1996, Japan, p. 629.
[14] T. Matsuda, K. Harada, H. Kasai, O. Kamimura and A. Tomomura, Observation of Dynamic Interaction of Vortices with Pinning by Lorentz Microscopy, Science, 271, 1393(1996).
[15] G.W. Crabtree and D.R. Nelson, Vortex Physics in High Temperature Superconductors, Physics Today, April 1997, p.32.

New Energy Technologies
PRINTED EDITION ADVERTIZING RATES

Full Page Ad
B/W - $400
Colour - $800

Half Page Ad
B/W - $200
Colour - $400

Quarter Page Ad
B/W - $100
Colour- $200

New Energy Technologies is distributed in the leading Scientific Laboratories in Russia and has subscribers in more than 20 countries all over the world

To advertise contact us:
Farady Labs Ltd, Phone/fax: 7-812-380-3844
http://www.faraday.ru, office@faraday.ru

Fantastic Projects

The Invention of Roman Solomyanny

Our previous issue featured an article about Roman Solomyanny who came to our office and told us amazing things. He said that during his army years (according to his words, he was in the military intelligence) he made a radio technology invention and later on built a free energy generator. The inventor claimed that his device had been working for a certain period of time without any fuel and had been producing power enough for heating and lighting his countryside house. We could not ignore such an intriguing piece of information. Moreover, Roman promised to build and present his device in 2003. We paid him for this interesting story to be published in the issue and prepared for the continuation... Alas, to no avail... His mobile phone was silent and we started to worry about the inventor's health. Fortunately, we managed to contact his parents on his home telephone (Roman lives in St. Petersburg) and they told us that the chap was OK. It seems he's lost his interest in us. But we still hope that Roman did invent something really exciting and not only polished up his talent for writing science fiction articles. Those people, who want to know the details about this invention or discuss it with the inventor himself, can get in touch with us for his contact information. Anyway, we will be very pleased to see him again full of new exciting stories. We have already introduced the 'Humour' section into the magazine and are planning to start the 'It Just Can't Be So' section.

Editor

Physicists are Joking





Anti-Gravity: The Holy Grail of the 21st Century

Bruce A. Smith, USA
PO Box 1676, Yelm, Washington 98597
Email: brucesmith@rainierconnect.com

A Primer on the Role of Electromagnetic, Electrostatic, and Torsion Fields in Anti-Gravity and Field-Effect Propulsion

Before visiting a University of Washington physics professor to talk about electrostatic propulsion, and hopefully anti-gravity, I realized: *Birds defy gravity. So do 747's for that matter. They apply the laws of physics and lift off the ground. That's anti-gravity, isn't it?* Yes, that's true, I suppose, in a metaphorical sense. But seagulls, jumbo jets and space crafts manifest anti-gravitation effects strictly speaking. What I want to address here is not the overcoming of gravity but the neutralizing of it.

Dr. Eugene Podkletnov, one of the foremost researchers in anti-gravity, and whose work is sought by NASA, Boeing and British Aerospace (now known as BAE Systems) describes the hunt for anti-gravity the greatest scientific quest of this century. He calls for an international effort, akin to the Manhattan Project that developed the atomic bomb, to conquer the secrets of anti-gravity, and usher in a new era of scientific understanding whose technological development will be at a scale so vast that the potential outcomes are merely hinted at by our previous achievements.

Just getting such a project off the ground will require unprecedented international cooperation, and public disclosure as well; the potentials are that vast, that scary, and that dangerous. Dr. Dan Marckus, noted British avionics expert, states in The Hunt for Zero Point, the seminal work-to-date on anti-gravity written by Jane's Defence Weekly aviation editor Nick Cook, that the secrets of anti-gravity in the wrong hands will make thermonuclear weapons look like firecrackers.

The secrecy surrounding anti-gravity research is phenomenal. Boeing refuses to publicly acknowledge any activity in anti-gravity development despite the fact that its competitor and sometime sub-contractor, British Aerospace (BAE Systems) is, the latter providing funds for four university research efforts as part of its Project Greenglow, one of which was a Podkletnov replication experiment headed by Dr. Clive Woods at the University of Sheffield,. Further, Nick Cook publicly, and privately to me in an email, states quite directly that George Muellner, former director of Boeing's ultra secret Phantom Works, claims Boeing sought the services of Dr. Podkletnov to unlock the secretes of his gravity-shielding research. Cook says that Muellner states Boeing was denied Podkletnov's services due to the objections of Russian officialdom, which the Russian-born Podkletnov must pay attention to, apparently, despite the fact that he works in Tempere, Finland. Dr. Podkletnov, wisely perhaps, chooses not to clarify these particulars despite our several emails.

Perhaps Boeing can deny any activity on anti-gravity because NASA is doing its own research, and as a prime contractor to NASA, such as by running the Space Shuttle Program, Boeing probably knows what NASA knows. NASA spent $600,000 recently in its Breakthrough Propulsion Physics program (BPP) to purchase Podkletnov replication equipment. Inexplicably, that equipment sits in boxes in NASA's Marshall Research Center in Huntsville, AL, awaiting more funding; according to an email I received from NASA propulsion researcher, Ron Koczor.

But enough with this business; what do we know about anti-gravity?

The search for that answer has taken me to some exciting and obscure places in this world, like the Aeronautics and Astrophysics lab at the Seattle campus of the University of Washington. I called those folks because Nick Cook in The Hunt for Zero Point, mentions that UW received a NASA contract to study theories of inertia as part of its BPP program. *That's a good place to start,* I thought, but it took backtracking to BPP Project Director Marc Millis at NASA's Glenn Research Center in Cleveland to find Dr. John Cramer at the UW Physics Department. His mission was to confirm with Dr. James Woodward the latter's 1996 preliminary research into the loss of gravitational mass in a targeted piece of metal from oscillating capacitors. Although Woodward's initial data appeared encouraging, NASA's Millis told me that their funding dried up before completing their research. Furthermore, the entire BPP became unfunded in 2002 and now in 2003 has become a hazy, privatized version of its former NASA subset self.

However, UW is continuing related research, such as magnetically confined fusion energy generators and that, for me, by using electromagnetism to contain an inner field makes it a close cousin of anti-gravity and field-effect propulsion. I spoke with Professor Uri Shumlak who told me that he and other UW staff from the Department of Aeronautics and Astronautics, along with a bevy of their grad students, are building a prototype of a fusion generator called HIT, which stands for Helicity Injected Torus.

This donut ring-shaped torus encloses a roundish chamber. Within that chamber a vacuum is first created, and then a volume of hydrogen gas is introduced and heated to a few million degrees Celsius, which separates the electrons and protons from their atoms turning the whole stew into a quasi-neutral foam of plasma. Then the torus envelopes the plasma with a magnetic field to keep it away from the sides of the chamber enabling the plasma mass to stay hot, and keep the rest of Seattle cool. (While I was standing next to his little eight foot long gizmo, Prof. Shumlak assured me there was no danger of a couple million degrees of heat escaping. The heat density of the plasma was "too low" for me to, well, break a sweat over. His quote was, "There's no more heat mass inside that chamber than what's contained in a cup of coffee." I sure hope you're right, Doc.)

Then, once the plasma field is contained, the magnetic field squeezes the plasma, fusing the nuclei of one hydrogen atom into another. As the hydrogen couples combine, a helium atom is created and a neutron is released, along with lots of energy in the form of heat. One day, such a generator will give us unlimited amounts of electricity, as the heat can produce electric voltage.

Lots of electrical power on the cheap the UW predicts; and the Department of Energy agrees, once the details of building reliable magnetic field generators are solved. What does magnetic fusion have to do with anti-gravity? Two things: first, magnets. Electromagnetism seems to be one of the major players in anti-gravity, particularly the use of electromagnetic fields to contain other fields, such as plasma fields in the HIT, or torsion fields, but more about that later. Secondly, the HIT works, or is about to. It's real and mainstream science embraces it, while anti-gravity is, well, a little more out there and reliable data is harder to obtain. So the technology of HIT lays a base that other research can build upon, such as not only containing other fields, but also building field effect propulsion systems, the most elementary of which is electrostatic propulsion, and aspects of that are already being applied by NASA.

Electrostatic propulsion uses electrical fields differently than electromagnetism does. In EM a current flows and creates a field, while in electrostatic systems the current is static and a charge builds up a field, such as in a capacitor.

These theories are utilized on NASA's Deep Space I, a probe bound for the outer reaches of our solar system. On Deep Space I, the propellant, a tankful of xenon gas, is excited electrostatically into positive ions. The engine has a negative charge at the exit end, so the charged xenon rushes out the tail pipe with a greater thrust than if it was just using conventional chemical propellants. In fact, the electrostatic propulsion system on Deep Space I allows it to fly at 60,000 mph, or 10,000 mph faster than it would with a conventional rocket. In addition, only 82 kg of xenon is needed for its entire mission, so with its smaller mass and weight Deep Space I will fly along side its intended target, a comet, and drag race on equal footing while filming and conducting studies. Again, not anti-gravity per se, but electrically charging Deep Space I's fuel-field sets the stage for a closer look at electrostatic propulsion.

Taking that closer look is Tim Ventura and his fellow researchers at American Antigravity, an organization based in Kirkland, WA. Ventura and his crew use electrostatic asymmetrical capacitors to create a field that levitates objects, such as their small, kite-like "lifters." These lifters are very light, weighing only a few ounces, and have balsa wood struts that support the capacitors. When two capacitors of different size receive their share of a 30,000 volt charge, the lifter lifts- no motors or wings.

How, no one really knows in my judgment; and the phenomenon is replete with controversy and mystery. But as one who has seen a lifter fly, let me tell you what one looks like and what I saw when Tim Ventura's took off.

Tim has been building lifters since he was a kid and has perfected a four-foot, by-four-foot, by four foot triangular lifter which has flown so many missions in his garage that the silver aluminum foil has turned white. The thin, chopstick-like balsa wood ribs that hold the aluminum foil in place are joined every few inches by a vertical strut (much like a telephone pole on a HO model railroad set) which sticks up and secures the copper or stainless steel wire of the upper capacitor. The ribs are intersected every ten inches or so by the strut of an interior triangle, since the whole lifter is composed of interconnected isosceles triangles which give the necessary strength to the balsa wood frame. All told there is about 30 linear feet of aluminum foil and a similar run of wire.

The lower and larger capacitor is a strip of aluminum foil stretched between the horizontal balsa wood struts. The second capacitor is a thin strip of 50 gauge wire mounted about one inch above the aluminum foil. As capacitors they store electrical charge but don't pass it on in a current.



Fig. 1
Lifter

The negative lead goes to the lower aluminum foil and the positive lead is attached to the upper wire. The three corners of the lifter are tethered to the work table so that the electrical leads from the power source are not broken off in flight.

The power source kicks out 15,000 volts at 250 watts. Tim uses a voltage generator made by Information Unlimited, Inc, but before the current reaches the capacitors, the voltage is stepped up to 30,000 volts by Tim's homemade voltage multiplier stack. At full throttle the lifter is straining at the tethers, bending the balsa wood frame near the point of fracture.

Throw the switch and at around 17,500 volts the lifter begins to quiver in take-off. At the full power of 30,000 volts the lifter is roaring and a noticeable downward breeze is observed. Many physicists call it "ion wind," and say that it is how the lifters fly. But what exactly is ion wind, and can it be the cause of flight?

"Ion wind is the movement of ionized air particles," according to Ventura, "which flow downward according to electrical charge." Here's his theory:

The positively charged wire on the top part of the lifter steals elections from the surrounding air, leaving the effected air molecules positively charged. These positively charged air molecules, or ions, then head downward toward the large source of negatively charged electrons generated by the aluminum foil. These air molecule ions are bigger and heavier than the electrons seeking them, so there is a net thrust downward pushing the whole lifter up. That's the theory, and frankly all I can do to verify the theory is to tell you what others tell me. Before I do that, though, let me tell you what I experienced standing next to a levitating lifter.

In flight the lifter emits a high whining, hissing buzz, and I could feel a good breeze coming up at me from the work table underneath the lifter. Also, standing next to the lifter but not touching it, the hair on the back of my head started to rise up in electrostatic-like fashion.



Fig.2
Lifter

To analyze the air currents Tim blew baby powder at the top of the lifter. The majority of the particulate cloud was drawn into the middle area of the lifter and then sucked downward. A kind of vortex was created at times, for intermittently I could see a cloud forming into an organized column beneath the lifter and then spreading out in 360 degrees once it hit the work table surface.

> *Electrostatic propulsion uses electrical fields differently than electromagnetism does. In EM a current flows and creates a field, while in electrostatic systems the current is static and a charge builds up a field, such as in a capacitor*

Is that ion wind? Well, there certainly was a breeze, and it sure felt like air, but how would I know if it was ionized? Something definitely sucked the baby powder down, but was it more than just regular air blowing past me? Again, I don't know.

Is the movement of wind why lifters fly, regardless of whether it is ionic or not, or is the wind just a by-product and not the propulsion? Could the capacitors be creating a field that neutralizes gravity, allowing the craft to levitate? Or are they creating some kind of new field that is localized and the surrounding ambient field pushes this "field-bubble" up, much like a helium balloon is pushed up by the surrounding heavier air trying to fill the emptier "field" of the lighter helium?

Ventura thinks at least two phenomena are at work. Ion wind is definitely one he feels, for the breeze is self-evident. However, he thinks a second effect is at work, too, and many agree with him. Most speculation concerns what is called the Biefeld-Brown effect, the "Brown" being T. Townsend Brown, whose name is well known in early quantum research and whose work is prominently discussed in Nick Cook's The Hunt for Zero Point.

The Biefeld-Brown effect, according to Ventura, is the theory that high voltage, air-gapped capacitors with different or asymmetrical capacities generate a net directional force upwards from the larger element to the smaller element, which on the lifter is from the aluminum foil to the wire. This force then pushes against the ambient energy field of the surrounding area, perhaps pushing against a more rigid energy field of the zero point energy field.

Brown apparently made his case for these electromagnetic effects, receiving patents in the 1960's for his research. NASA's Dr. Jonathan Campbell at Marshall Research Center in Huntsville confirmed to me that he also, has received a patent recently for his research into the thrust effects of asymmetrical capacitors.

Editor: By the way, this patent is meaningless from the point of view of a prime claim. Before that there had been many publications on the subject.

A.V. Frolov.



Fig.3
Lifter

However, prominent physicist Hal Puthoff, whose research is a broad swath across the fields of the 'new physics', featured in both The Field and The Hunt for Zero Point, and who was also the military's "Top Psychic" as the twelve-year director of the CIA's remote viewing squadron, has a different perspective: "I'm quite certain at this point that the so-called 'lifter' phenomena is just an electrostatic ion wind phenomena, not 'antigravity.'"

But Dr. John J. Rusek, Adjunct Professor of Aeronautics and Astronautics at both Purdue University and the United States Air Force Academy, says that "Initial findings of 'classroom' experiments with lifters show ionic wind to be way too small a factor, by three orders of magnitude." Dr. Rusek has formed a technological company, Swift Enterprises, to continue this research and bring it to the level that is "presentable to the mainstream physics community."

Along these lines, Jean-Louis Naudin shows on his extensive web site, not only how to build a lifter, but also several photos of research into the ion wind issue. Naudin's team has wrapped test lifters in plastic yet they still produce anti-gravitational effects.

Others may have a clue to the second or even a third force at work. Researcher Fran De Aquino, professor of physics at Maranhao State University in Sao Luis, Brazil, is described in the literature as showing that "bubbles of localized space-time" can exist in variance to the surrounding fields. Anecdotal experience suggests that the lifters may be undergoing such space-time anomalies.

Editor: At this point we need to interrupt the author as he has already completely confused the reader. I would recommend referring to Thomas T. Brown's patent: USA patent #3,187,206, 1965.

Alexander V. Frolov

The Hunt for Zero Point states that NASA sought the services of Dr. Eugene Podkletnov, and although their replication research languishes, The Hunt claims that researcher Ning Li, of Huntsville, AL is pursuing this line of research as a private contractor to NASA.

Another Huntsville operation, Transdimensional Technologies, is exploring these multi-faceted phenomena as well, and its extensive web site shows it to be a frequent contractor to NASA, including research into "asymmetrical capacitive propulsion," and capacitor-based devices to test "ion wind" forces. Jeff Cameron, of Transdimensional, is said by Ventura to be "the father of the lifter," having developed them while exploring anomalous torsional effects of high energy lasers. The lasers twisted and at the time it was considered a nuisance. But the unknown forces at work later led Cameron to found Transdimensional, develop lifter technology to a commercial level, and subsequently patent many pieces of related technology. Unfortunately, I have been unable to reach Jeff

Cameron or anyone at Transdimensional for any kind of confirmation.

Nevertheless, how would gravitons be blocked, or gravity shielded?

Dr. Hal Puthoff says there are two ways of looking at it. First, one can look at the issue from a quantum point of view, that there is a particle exchange between the gravitons and something else, and the net effect is anti-gravity. The how's and why's of that are speculative, so Puthoff turns to a classical approach for answers. He prefers looking at "engineering the vacuum." To do that one must first look at the vacuum.

As I understand it we are all in the vacuum, everything is. The "vacuum" is the matrix that contains all matter and all energy. It is the engineering perspective of the zero point energy field, or the *"Field"* as popularized by Lynn McTaggart in her masterpiece The Field. Puthoff shared with me statements from fellow researcher Dr. T. D. Lee that state: "The vacuum is the seat of energetic particle and field fluctuations, and ... is the seat of space-time structure ... that encodes the distribution of matter and energy.... The vacuum is energetic in its own right."

Thus energy can be drawn from the field; and spacecraft can have "vacuum propulsion systems, or propellant-less propulsion," in other words, field effect propulsion.

At any rate, more and more physicists are thinking that the vacuum can give them a whole lotta oomph, enough to propel spacecraft; and when they learn how to corral it, a whole bevy of new phenomena may be encountered, including anti-gravity. This new potpourri of research is being called by many the "new physics." And although his approach is classical, Dr. Hal Puthoff seems to be sensing what's out there waiting to be discovered.

Puthoff's current research as been to explore "the perturbation of atomic or molecular ground states, hypothesized to be equilibrium states involving dynamic radiation/absorption exchange with the vacuum fluctuations. In this model atoms or molecules ... are expected to undergo energy shifts that would alter the spectroscopic signatures of excitations involving the ground state." Puthoff says he's had no success so far with this approach, but his words remind me of De Aquino's speculation that objects lose mass as they absorb energy. Pull energy from the field around you and you lose weight. Bingo, lift-off. **But how does one pull energy from the field?**

Editor: Some solve this problem by means of the ether density changes, which are performed with the help of vortex longitudinal-wave technologies.

A.V. Frolov

Torsion fields might play a role here according to many, and the literature on anti-gravity is filled with the phrase, "torsional effects." But what exactly is a torsion field? "It has something to do with spin," Nick Cook told me on the phone. "You have a torsion field when you spin something. Add a little electromagnetism and you might have anti-gravity." That's the short-hand version of it and here's a deeper look.

Mike Wright, resident physics expert at BeyondTheOrdinary.Net web stream radio, told me this: "When forces create curvature (such as rotation) in more than two planes, a torsion field results. Not only does the object go around, but it goes around and 'down' or 'up', and the up/down movement is an additional acceleration in that dimension. EM and gravitational fields differ by having a magnitude of force and only one direction of movement.

"A tornado is a structure of air in air. A whirlpool is a structure of water in water. So, because more than two planes are involved, objects can be created from 'nothing'; that is to say that objects can be created from the medium of the environment, such as a tornado from two air masses of differing temperature."

So spin plus movement is the key. Again, Tim Ventura is on the hunt. He demonstrated to me **that spinning magnets will cancel out their magnetic fields sufficiently so that two magnets facing each other with like poles will not push each other away if one of the magnets is rotating**

perpendicular to the force of opposition. It's not anti-gravity, but it gets us closer to the heart of the matter.

Further, Russian physicists have been researching the torsional effects of both subatomic particle spin, and the loss of gravitational mass in planets from the angular momentum of their orbits. Spinning makes something happen, but what? Tornadoes and Mother Nature might have a few clues.

Tornadoes spin, in a sense, although no one is Oklahoma who has spent a night in a storm shelter during an F5 event would describe the tornadoes in the night sky as *spinning*. Nevertheless, tornadoes have anomalous effects that are legendary: blades of grass stuck into mirrors, a piece of straw embedded flawlessly into a tree trunk. How? It seems as if the laws of mass, gravity and inertia are melted as winds swirl at speeds up to 300 mph in an organized vortex pattern. Is this a clue to melting the pull of gravity?

Getting information to this question has not been easy. Many scientists claim not to have even heard of torsion fields, including particle physicists at major US universities. So, again I turn to Nick Cook and The Hunt for Zero Point

Dr. Dan Marckus says that if "you generate a torsion field of sufficient magnitude the theory says you can bend the four dimensions of space around the generator. The more torsion you generate the more space you perturb. When you bend space you also bend time."

Marckus continues, "If you dipped ...one of these whirlpools ... into the zero point energy field, the seething mass of latent energy that existed on an almost undetectable level all around us [in the field would] ... react in an almost magical way by directing that energy."

The torsion field, in effect, is "a pump, a 'coupling' device that could dip into, and then direct, energy out of the zero point energy field." "But," Marckus continues, "the vortex wasn't a three-dimensional phenomena or even a four-dimensional one. It couldn't be. For a torsion field to be able to interact with gravity and electromagnetism it had to be endowed with attributes that went beyond the three dimensions of left, right, up and down, and the fourth-dimensional time field they inhabited; something that the theorists for convenience sake labeled a fifth dimension-hyperspace."

Cook concluded that the torsion fields "bind with gravity ... to produce a levitation effect -- an antigravity effect," but "it wasn't doing so in the four dimensions of this world, but somewhere else." That somewhere else is hyperspace. **So how do we activate torsion fields and enter hyperspace?**

Dr. Eugene Podkletnov may have a clue.

Podkletnov, the Russian researcher working in Finland, has studied the gravity shielding effects of superconductors. Again, Nick Cook in The Hunt, relays vital information. Cook says Podkletnov claims, "If the superconductors are rotated considerably faster than 5,000 rpm ... the disc experiences so much weight loss that it actually takes off." Thus, torsion field creates levitation. I emailed Dr. Podkletnov to find out more about this issue. He replied: "[A] fast rotating object can, under certain conditions, cause the polarization of the volume that it occupies in space and around it. This polarization causes the gravitational effect as it modifies [the] local gravity field. The vortex of the polarized particles will create a vertical thrust with a certain force and spatial momentum. Some scientists call these polarized particles gravitons. The term graviton is an artificial one and at present we are not sure if it is a wave or a particle and what type of particle. Maybe it is a usual tachyon or a superluminal neutrino (a faster-than-light-particle). Polarization of the media means that the spins of electrons, protons, neutrons and of small subatomic particles that constitute the fabric of space or vacuum would be parallel. Then a kind of gravity well is formed and the objects tend to fall into this well. We observe this picture as an object rising to the sky. Polarization of the media (of space) causes some glow around the object as it acquires additional energy and because of it, the glow around some objects is observed."

What I understand from Dr. Podkletnov is that gravity is the effect of spin -- the spin of all subjected particles, from the sub-atomic level and up being parallel; thus they are all aligned to fall into the gravity well of earth. And spinning objects, such as his superconducting discs, when influenced additionally by an electromagnetic field, will experience a shift in the spin of the sub-atomic and atomic elements. They will be turned and not be aligned in parallel. Thus, they are able to levitate.

But how to polarize the media and get things spinning? Enter Dr. Marcus Hollingshed, an enigmatic figure allegedly from Cambridge University. Dr. Hollingshed claims to have built a six-ringed toroidal coil antigravity device, which achieved great effect using rotating magnetic fields. In January 2003 he announced on the Internet that he has developed a 160kg vehicle able to lift in excess of 2000kg and that it has both horizontal and vertical drive features. His device cannot only go up and down and sideways, but it can push things away and pull objects to it.

In addition, the field that the device purportedly generates is capable of being broadened and weakened, or narrowed and amplified in a lensing effect, with the field producing an absolute vacuum of 2.2m spherical diameter. Best of all, when it's cranked up the core of it goes invisible, although the term Dr. Hollingshed uses is that there is a "loss of reflected light." There are no reports of independent confirmation, and Nick Cook says he hasn't been invited to see it, so, he's skeptical.

Where does this leave us? Perhaps Dr. Podkletnov's words sum up our current situation."Modern theoretical physics cannot give you the direct answer to your questions (levitation, torsion fields, etc.,) and a scientist who would agree to give you the answer cannot be regarded seriously, softly speaking. If you had asked Dr. Einstein if he were an expert on gravity, the answer would be NO. I can repeat his words: No, I am not a magician, yet; I am still learning."

ELECTRICAL LEVITATION

Wayne Macleod, USA
Email: dynamars2100@yahoo.ca, cwleod@shaw.ca

Gravity is the incremental slowing of time as we move closer to its source. If we imagine panes of glass stacked on top each other, one pane slightly denser than the one immediately above, a ray of light coming from above will constantly refract in a curved beam downward as it enters the stack. The same is true of a ray of light entering a gravity field. The analogy is not too far fetched because refraction is caused by a slowing of light in the denser medium. Of course, gravity affects material objects as well as light, but this is explained by every object traveling on a 'world line' in spacetime. We can use light as in the glass example because light is its own world line.

Why the world lines of objects take the paths they do can best be understood by compressing our normal 3 dimensional space into 2 dimensions, length and height only. When we throw a stone into the air it rises and falls in a parabolic arc in these two space dimensions. That path in space is a complete mystery until we consider another dimension, time, a dimension we can imagine measured at a right angle to the plane of the 2 space

energy and because of it, the glow around some objects is observed."

What I understand from Dr. Podkletnov is that gravity is the effect of spin -- the spin of all subjected particles, from the sub-atomic level and up being parallel; thus they are all aligned to fall into the gravity well of earth. And spinning objects, such as his superconducting discs, when influenced additionally by an electromagnetic field, will experience a shift in the spin of the sub-atomic and atomic elements. They will be turned and not be aligned in parallel. Thus, they are able to levitate.

But how to polarize the media and get things spinning? Enter Dr. Marcus Hollingshed, an enigmatic figure allegedly from Cambridge University. Dr. Hollingshed claims to have built a six-ringed toroidal coil antigravity device, which achieved great effect using rotating magnetic fields. In January 2003 he announced on the Internet that he has developed a 160kg vehicle able to lift in excess of 2000kg and that it has both horizontal and vertical drive features. His device cannot only go up and down and sideways, but it can push things away and pull objects to it.

In addition, the field that the device purportedly generates is capable of being broadened and weakened, or narrowed and amplified in a lensing effect, with the field producing an absolute vacuum of 2.2m spherical diameter. Best of all, when it's cranked up the core of it goes invisible, although the term Dr. Hollingshed uses is that there is a "loss of reflected light." There are no reports of independent confirmation, and Nick Cook says he hasn't been invited to see it, so, he's skeptical.

Where does this leave us? Perhaps Dr. Podkletnov's words sum up our current situation."Modern theoretical physics cannot give you the direct answer to your questions (levitation, torsion fields, etc.,) and a scientist who would agree to give you the answer cannot be regarded seriously, softly speaking. If you had asked Dr. Einstein if he were an expert on gravity, the answer would be NO. I can repeat his words: No, I am not a magician, yet; I am still learning."

ELECTRICAL LEVITATION

Wayne Macleod, USA
Email: dynamars2100@yahoo.ca, cwleod@shaw.ca

Gravity is the incremental slowing of time as we move closer to its source. If we imagine panes of glass stacked on top each other, one pane slightly denser than the one immediately above, a ray of light coming from above will constantly refract in a curved beam downward as it enters the stack. The same is true of a ray of light entering a gravity field. The analogy is not too far fetched because refraction is caused by a slowing of light in the denser medium. Of course, gravity affects material objects as well as light, but this is explained by every object traveling on a 'world line' in spacetime. We can use light as in the glass example because light is its own world line.

Why the world lines of objects take the paths they do can best be understood by compressing our normal 3 dimensional space into 2 dimensions, length and height only. When we throw a stone into the air it rises and falls in a parabolic arc in these two space dimensions. That path in space is a complete mystery until we consider another dimension, time, a dimension we can imagine measured at a right angle to the plane of the 2 space dimensions. By multiplying the time of the object in flight by the speed of light, we have a three-dimensional coordinate system, not of space but of spacetime. We can then graph the world line of the object. So why does the object fall? It is because spacetime near massive bodies is curved. A remarkable fact is that the curved world lines of all objects in the same gravity field, whether of a thrown ball or fired bullet, have the same radius of curvature. Hence all objects fall with the same acceleration.

To neutralize gravity we must somehow 'straighten' the world lines of objects traveling in curved spacetime. It would be as if we had in our stack of glass panes a bubble, around which the density of glass became less on approach to the bubble. Then the ray of light, when close to the bubble, would refract opposite to the path it would normally take when traveling thought the rest of the glass. Similarly, if we could manufacture a 'time bubble' in a gravity field opposite to the time slowing known as gravity, we would have any object embedded in the time bubble isolated from that gravity field.

The Electrical Levitation theory can best be understood by first considering an analogy. Let us imagine a wheel spinning on an arm like a child's propeller toy. The arm also rotates, in a direction opposite to the spinning wheel. We consider the rate of spinning of the wheel from the point-of-view of two observers, one observer stationary on the ground, the other observer rotating with the arm. Obviously the two observers will not see the same rate of spinning on the wheel. Because the arm is rotating opposite the spin of the wheel, its rotation must be subtracted from the rate of wheel spin as seen by the stationary ground observer. This is not true of the observer rotating with the arm, who will see the spin of the wheel as if there were no arm rotation.

The concept is easier to envision with linear motion, such as of a man throwing a ball on a moving train. The velocity of the ball seen by the pitcher on the train will not be the same as its velocity seen by a stationary observer on the ground. As the stationary observer sees it, that velocity will have the train's velocity subtracted from it if thrown against the train's velocity. It is the same with rotary motion: the velocity of the wheel for the stationary observer is slower because the arm's rotation is subtracted from it.

But suppose the wheel rotation is *the same* for the two observers! Something must be different between them, and that is time. As explained by Special Relativity for linear motion, time is not a universal constant; it differs between observers depending on their relative motion. The property of nature that *is* constant, that produces this relative time difference, is the speed of light. So we must look for a similar constant in nature for a relative time difference between observers in our rotary example. We have one in electron angular momentum, known as electron "spin," $h/4\pi = 5.28 \times 10^{-35}$ kg-m^2/sec, where h is Planck's constant. Like the speed of light, this quantity is constant for all observers, whether the observer is on a rotating system or stationary on the ground. Here is the tool for producing our time 'bubble'.

Let us now imagine a series of concentric rings, all rotating in the same plane and in the same direction. Electric current is pushed through these rings in the same direction as the ring rotation. (Current here is considered the flow of electrons, not conventional positive current.) The rotating rings are sandwiched between two magnetic plates, the function of which is to maintain the angular momentum of the current electrons oriented properly with ring rotation.

Analogous to the above example, each electron takes the place of the spinning wheel and the rotating arm is replaced by the rings. Thus, because electron angular momentum is a universal constant, an observer of the electrons in this rotating system will not have the same time as a stationary observer outside it. If each current electron has its "spin" oriented opposite the rotation of the rings, time on the rotating system would run faster than for a stationary ground observer, the same as in empty space relative to the Earth. The rotating system would therefore have the world line of empty space, not that of the gravity field. Its spacetime would not be curved. Since gravity is a time phenomenon, such a system in a gravity field could not have the behavior of a normal object. This conclusion may seem erroneous considering that ring rotation could never reach relativistically significant velocities, but we have an analogy with magnetism that is caused by a Lorentz contraction of the distance between moving electrons. If we considered the diminutive drift velocity of electrons alone we would never conclude that magnetism was possible, but the effect is *accumulative* over trillions of electrons. The hypothesis here is that the same is possible with the trillions of free electrons oriented with a spinning ring, to produce an accumulative time effect.

We now come to the controversial part of this theory because the above treats electron angular momentum the same as angular momentum of a normal physical object, whereas the electron is a quantum particle and quantum particles have their own realities with bizarre consequences when analogized with our macro universe. For instance, the electron has quantum spin number 1/2, and such a particle would have 720 degrees in one rotation, not 360. Nevertheless, the electron *does possess* di-pole magnetism. It *does behave* as a spinning ball with negative charge. Electrical Levitation is therefore an empirical theory. The property of the electron that gives electron di-pole magnetism cannot be an actual physical rotation, but whatever that quantum property, if it produces di-pole magnetism there is reason to expect it to produce other macro physical phenomena as if it were.

The theoretical finding of General Relativity that time runs slower in a gravitational field was confirmed by the Pound-Rebka experiment in 1959. **It is not that gravity causes time slowing, gravity *is* time slowing.** Since time and energy are reciprocal, more time on our rotating ring system would mean less energy seen by an observer in that frame of reference than seen by a stationary observer on the ground, the opposite of the red shift of a gravity field. This energy difference must equal the energy of the mass in a gravity field that is to be levitated, its energy of weight, and lost. Experimenters should therefore be aware that their device might radiate. But this is not a free energy machine. The energy of levitation comes from its magnetic field, and the electron magnetic moment energy turns out to be $V_e = mc^2$ divided by the electrical current, m is the mass to be levitated and c is the speed of light. This is an enormous amount, but becomes practical if enough electrical current can be sent through the rings. That means the electrical resistance of the ring material must be very low. For copper it is not. No material currently exists with sufficiently low electrical resistance at room temperatures, but **superconducting materials** exist that at cryogenic temperatures experience a dramatic loss of electrical resistance.

An experimental device can therefore be envisioned using a superconducting disc substituting for the electric rings. The disc would serve as a conductor for an electric current and would therefore need to be sliced along one radius with an insulator placed in the notch. Both edges of the notch would be connected to a power source by brushes rotating with the disc. With a counterclockwise disc rotation as seen from the top, to have clockwise electron "spin" the magnetic field between the plates would have to be up. Only the moving free electrons of the current will be available for any time alteration effect. These will also **produce a magnetic field, which it is reasonable to assume would be of the same time alteration effect as the electrons, thus producing the required alternate time "bubble".**

The resources required for an experiment using superconducting material at cryogenic temperatures are beyond this writer's means and an experiment has not been attempted, but an experiment at the Tampere University, Finland, 1992, using a superconducting disc suggests that gravity shielding is possible. Owing to the immense advantages gravitational shielding would give to the present interest in space exploration, effort toward its development would be logical. This essay may offer clues on how to begin.

Editor: I find the article by Wane McLeod quite interesting as his approach is very similar to the idea I first presented in my report at the "Space, Time and Gravitation" Conference which took place in St. Petersburg in 1998. The report was included into The Proceedings of the Conference, Part I, 1999. Before that the brief version of the article was published in English in the 'ELECTRIC SPACECRAFT' magazine, Leicester, North Carolina 28748 USA, Issue 27, 1997 p.30-31.

I managed to demonstrate that the ideas of Thomas T. Brown, especially his USA patent # 3,187,206 of 1965, are something more than just the force asymmetry in the electric capacitor. According to the concept presented in my report, by creating a matter property gradient (in particular, the dielectric permittivity gradient) we actually change the curvature of the electric force line in space. Normally, the natural space curvature accounts for the electric field potential decrease with the distance increase from the surface of the charged object. By creating the dielectric permittivity gradient (described by T.T. Brown in his patent of 1965) we change the natural distance potential gradient law. We can both increase and decrease this change and even reverse it. With the dielectric permittivity change square function, the natural space curvature is completely compensated and with more extent it is reversed and can be turned to negative. At that rate, the potential is not decreased but increased with the increase of the distance from the surface of the charged object. This is the essence of my concept that has never been considered before by any author. By creating the gradient described by the quartic function we get the same distance potential gradient law as in the natural conditions only with a different sign!

T.T. Brown, who discovered a force in capacitors with a special dielectric, offered the practical application of this concept. However, he did not find the source of this force, which, according to my concept, is conditioned by two factors: the corresponding dielectric property gradient function and the elastic properties of the dielectric material, which is of no less significance. Normally, dielectric particles are attracted to the charged surface but when the reversion of the curvature of electric field force lines occurs, they are repulsed from it and we can use this propulsion force. Elastic deformations (including those occurring during the pulsating operation of the field) account for the reaction forces equivalent to the generated propulsion force. Thus, the momentum conservation law is in action, however, the device is still moving.

T.T. Brown also considered other ways of generating a force, such as the material magnetic property gradient. Logically, by analogy with the electric field we can consider the gravity field, which can be "designed" and "reversed" by means of creating a matter with the density gradient. At that rate, the gravity potential must change in accordance with a certain law when the distance from the gravity field source being increased.

We should also note that the local space volume levitation effect with the accelerated or decelerated time rate was first described in my articles "Physical Principles of the Time Machine", NET #3 (6), May-June 2002 and "Practical Application of the Time Rate Control (TRC) Theory", NET #3, November-December 2001.

Our company conducts experimental researches on creating new materials that possess the properties described. We are interested in serious business contacts with companies in the aerospace industry to further discuss eventual cooperation projects in this field, including *co-patenting*.

Alexander V. Frolov

Perpetuum Mobile Not in the Past but at the Present

Vladimir I. Likhachev, Russia
Krasnodarskaya str., 38/20-34, Moscow, 109386

In several issues of the "Nature and man. Light" magazine in 1995-97 my colleague E.Oparin and I wrote on the unscientific character of absolutizing the law of degradation of energy, on the important issue of creating the perpetuum mobile of the second kind utilizing infinitely available *environmental heat energy*. We even send a letter to Yury S. Osipov, the Russian Science academy President, but received no reply. Notwithstanding many official discussions, there are no well-reasoned objections to our arguments or proof on the part of "high" official science, because, in fact, we are right.

I have recently received one more confirmation: bright and feasible data on the negentropy cycle (the cycle with spontaneous reduction of entropy) with a chemically active working substance that will be described later.

After the publication of Victor M. Brodyansky's book "Perpetuum Mobile in the Past and at Present. From Utopia to Science and from Science to Utopia", Second Edition, one can not but return to these issues. More so because the foreword of V.A. Fabricant, member of the USSR Academy of Pedagogical Sciences, claims the law of degradation of energy to be the "law of nature" and supports shamefully the deformation of the monothermists, especially P.K.Oschepkov, by academicians P.Kapitsa, L.Artsimovich and I.Tamm ("Pravda" of November 22, 1959), followed by E. Velikhov, A.Prokhorov and V.Sagdeyev ("Pravda" of June 22, 1987).

After the publication of Brodyansky's book I met the author several times (notably at a special seminar in The Moscow Energy Institute) and expressed my opinion about his book: the book avoids serious discussion of the monothermists, stresses their failures which are quite normal in the initial development of perpetuum mobiles of the second kind.

For example, Brodyansky knew about Tsiolkovsky's discovery. Guay's book "On the Little-Known Hypothesis of Tsiolkovsky" is listed among the First Edition references. But Vladimir Brodyansky avoided analyzing this discovery both "in the past" and "at present". The Second Edition references even list the "Physical Thought in Russia" magazine, issue #1 of 1991, that contained for the fist and only time the modern edition of the "Law of Degrading of Energy" by Tsiolkovsky. "At present" V. Brodyansky knows my analysis of Boltsman's mistakes but he paid no scientific attention to my analysis either.

In Brodyansky's book the description level of chemical reaction cycles is even lower than that of Schpilrine. Schpilrine at least tried to present his arguments but here we see unsupported statements "justified" by the phrase "the detailed discussion would take too much space". Vladimir Brodyansky's analysis of anti-Stokes luminescence (pp.216-219) is also superficial. Dissipative and entropy processes prevail in it. But if there is evidence supporting higher frequency quanta than the frequency of radiating flux, **it is the evidence of negative entropy**. Vladimir Brodyansky not only is familiar with it and also shows it by the example of investigating the Sun and the Earth (p.247).

Vladimir Brodyansky's analysis of Rank's tube (pp.235-237) displays the same tendency. In the Rank's tube the dissipative processes also prevail. Its effectiveness as a refrigerator is lower than in the traditional schemes.

But one can not deny the existence of negentropy processes in it. It is these processes that "originate" the cold gas flow. And Brodyansky's "origination" on p.236 "The vortex tube in fact divides the coming gas into two fluxes: heated and refrigerated" - is totally false. That can be performed only by "Maxwell's demon" that does not exist in substance.

The refrigerated flux in the Rank's tube is formed by the "Tsiolkovsky's flux" by way of heat transfer "from cold to hot", from the tube center to its circumference by **centrifugal accelerations**. On its basis (to be more exact, on the basis of Finko's tube) the perpetuum mobile of the second kind can be created. And we have this engineering solution. E.Oparin and I made the corresponding patent application for an invention but the Federal Institute of Industrial Property again refused to consider such applications. Here one can see similarity with the causes of re-edition of Vladimir Brodyansky's book. And one need not be a big politician to admit the reality and understand the sources.

Environmental and, especially, anti-nuclear movement is invincibly expanding. Danger to human life and threat of ecological catastrophe are quite real. The Second Edition of Brodyansky's book protects behind scientific arguments those who use Russia as a source of easy money and then flee.

But we like our country - vast and austere. This austerity and space form REAL PEOPLE and support humanity and materialistic humanism of the energetic and talented, not just the rich.

In modern Russia the powerfully spread alcoholism, debauchery and drugs are the instruments of slavery. But the monothermy and development of alternative power engineering will become basis for Russia's revival and unprecedented prosperity.

Russians learn slowly, sometimes, very slowly, even disgracefully slowly. But we will learn. And then no one will stop us. The following tips are meant for those who are ready to risk their efforts and facilities in order to build alternative energy knowledge base: dissipative and negentropy processes are inseparable and very often their mechanism is the same. In our environment the dissipative processes are more effective and hide the negentropy ones. No dissipative process combination can generate the negentropy cycle. Look for examples in Brodyansky's book. To create the negentropy cycle and use the environmental energy at least one negentropy process is required that has effectiveness and negentropy exceeding entropy growth at all levels of the cycle.

News from “IntAlek” Company

William Alek [alekws@intalek.com] has updated the latest and greatest ZPOD system drawings:

hhttp://www.intalek.com/Index/Projects/SmartPAK/Projects/ZPOD/ZPOD_System05.pdf

This is release 5.0

Here is the latest electrical schematic: http://www.intalek.com/ZPOD/ZPOD_System05.gif

Based upon his "preliminary" tests thus far, he estimates the COP is around 2.0. This estimate is interpreted from the following scope traces:

http://www.intalek.com/ZPOD/in.GIF

Alan Francoeur's Generator
Canada

Alan L Francoeur, Canada
Email: al.f@shaw.ca

This is my writing and development about the Interference disc generator, and the permanent magnet dynamo machine, and other related inventions. I have always been intrigued with electricity and magnetism and aetheric energies starting at a young age. Back in 1980 I wanted to do something to help get my large vehicles better fuel economy. With this goal in mind, I experimented and designed my first heat exchanger vaporizer system to do my part to clean up our cars and trucks, fig. 1, 2, and 3 are two earlier vaporizer units under construction. For more information about this fuel system, please refer to my vaporizer fuel system report. The main body of this writing is referring the permanent magnet dynamo system that has been in the making since 1987, starting after the development of the interference disc generator.

Fig. 1

Fig. 2

Fig. 3

I invented the Interference Disc generator concept while I was employed at Giant Yellowknife Mines NWT from 1983 to early 1986. The idea of using metal blocking plates to shield magnetic fields stirred in my mind while working around heavy electrical mining equipment, and 1000hp and other electric motors with exposed coils that have heavy metal around the outer casing. I did a search at the time and found John Ecklin's work very interesting with his application of the shielding effect. During my off time in Yellowknife, I was experimenting with the interesting effect of producing induction with a stationary coil mounted beside a stationary magnet with a small air gap maintained between the magnet and the coil. During the construction of my first disc machine, I called it the Interference Shielding effect because of the interference the blocking disc does to cause induction, thus the Interference Disc Generator fits the description. The first transformer coils I used to test the interference shielding effect were used from old radios, and the magnets were alnico types. Back in 1986 in Calgary Alberta, a friend Bud Johnson and I constructed the first test disc generator model using alnico magnets, fig. 4, and later ceramic magnets were installed. Months later I designed and began construction of another larger Interference Disc machine with horseshoe shape neodymium 35 grade magnets mounted on the outside, and with the N and S magnetic poles facing toward the coils in the center portion of the machine. The coils and magnets in this larger machine are mounted in reverse of the first Interference Disc generator, fig. 5, 6.

Fig. 4



Fig. 5



Fig. 6

General description of the interference disc generator

The Interference Disc electrical generator is made of a stator (114) consisting of an array of even number parallel mounted bar magnets (112) arranged and supported (114) in a circular fashion equidistant from each other, where the polarity of the magnets (112) are alternating when viewed at either end. Fig. 7



Fig. 7
Magnetic bars assembly (rotor)

Also in the stator fig. 8, (102) there are twice the number of coils (111) as bar magnets (112) wound in pairs on U-shaped cores (110). One half of the coil pairs mounted at one end of the bar magnets (112) in the same circular fashion, each corresponding to and aligned opposite to a pair of bar magnets (112) and separated from it by an air gap. On the other end of this pair of bar magnets (112) there are another set of coils (111) aligned likewise.

The rotor is made of two magnetically susceptible circular plates (109A or 109B) (such as iron or steel) Fig. 9, centrally mounted on an axle (107) fig. 7, which is in respect to the array of magnets and coils Fig. 9a.



Fig. 8



Fig. 9

The interference discs (109A or 109B) are separated from each other so that they can rotate in the air gaps between the magnets (112) and the coils (111). The interference discs (109A or 109B) have a number of **equidistant opening, either more or less in number than the number of the bar magnets (112)**.

The arrangement and size of the openings are such that when the discs (109A or 109B) are rotated by an outside motive force, they open the magnetic field between adjacent bar magnets (112), and the opposing coils (111) at both ends of the stator (114) simultaneously. Hence inducing an alternating electric current in the stationary coils (111) fig. 10.

By opening and closing the magnetic influx to the core (110) of the coils (111), an alternating current will be generated in the coils



Fig. 9a
Magnetic bars assembly (stator)
Option II: multable magnetic coil-disk assembly



Fig. 10

(111) in a retro-order to the rotational direction of the interference discs (109A or 109B). Depending on the number of magnet-coil assemblies three phase AC current can be obtained. The regulation and attenuation of these currents can be achieved by known electric engineering methods (Fig. 10).

The efficiency of the unit would vary greatly depending on the speed of rotation, the width of the air gap, the strength of the magnets, and the materials used to construct the coils. I used nickel base amorphous metglass in the coils in both the smaller and larger machines, which as a result, shows greater efficiency as compared to conventional core laminates. Less energy is needed to spin the balanced disc rotor while causing a larger moving magnetic field to cause induction in the stationary coils. With this effect, it is easy to visualize the advantages this design has over conventional generators and motors. New testing of the coils will be conducted after the machine goes through all the upgrades to eliminate the problems with the warping interference discs.

The Interference Discs Generator described in this document **has the potential to produce more than unity effects** by easy turning of a magnetically balanced (non-warping) interference disc. Optimizing the device with closer tolerances and correctly selected materials and incorporating internal magnetic balancing, will add to the success and improved performance of this unique generator design.

Improvements can be made with this design while the operating principal remains the same. Looking at the photographs included you will see the 1st proof of concept generator frame is constructed mainly from aluminum, this metal was used only because it was inexpensive material and easy to work with fig. 11. Non magnetic and non-conductive materials should be used to construct the generator frame supports to eliminate the eddy current losses. All of the nuts and bolts used to hold the disc generators together worked well for making the test machines capable to have adjustable air gaps, however, they can all be eliminated with design changes that preset the gaps and tolerances to optimize the conditions of the interference disc effect.



Fig. 11

Many improvements were adopted in the next larger #2 version of the Interference Disc generator fig. 12. Phanolic materials (non conductive and non magnetic) were used in the frame supporting the magnets and the coils, thus eliminating eddy current losses within the frame support. Large aluminum E bars were used to support the magnet frame support and the coil frame support with no noticeable eddy current losses. The aluminum used is positioned further away from the coils and magnets in the larger generator so as not to be affected by the magnets. Larger more powerful neodymium magnets and I shaped transformer coils were installed and tested in the larger machine which showed an increase in output power over the 1st machine fig. 13. Using more powerful neodymium magnets in this larger disc machine created some problems with the interference discs. Not only did they warp the discs they caused them to vibrate and chatter causing the fins to hit the magnets and the coils. I increased the air gap to over half an inch and moved the disc further away from the magnets to prevent damage. The effect was a reduction of magnetic flux reaching the coils that reduced the power output. The discs must be constructed much stronger and rigid if using neodymium magnet grade 35 or greater, then the air gap can be closed so more magnetic flux will reach the coils allowing for a greater electrical output.



Fig. 12



Fig. 13

The wiring of the coils circuit can be constructed by known engineering methods to achieve AC or DC power, and like any conventional transformer, wind the coils with heavy wire for more amps and more turns for more volts. The coils are stationary in this machine which makes it easy to harness AC power directly from the coils without brushes. All coils that are in phase can be wired in series or parallel, the number of the blocking plates on the interference disc determines the phasing of the coils.

The diagram in fig. 14, 14a shows the path of the magnetic flux movement in relation to the position of the blocking plates of the interference disc. The magnetic field in the core/coil is switching polarity as the interference disc fins alternately moves in and out of the air gaps on each side of the coil. As you can see, depending on the position of the disc, positive and negative induction takes place for AC output of the coils. John Ecklin has achieved this effect using rotating blocking plates. I have achieved the same effect using balanced rotating interference discs with multiple stacks of isolated coils and poles mounted in a circle equal distance from each other.



Fig. 14



Fig.14a

The effect I reproduced with Gary Wesley's permanent magnet motor is related to the Interference Disc generator in the fact that blocking plates are used to shield the magnetic field, only we differ on methods to balance the blocking shields. Gary Wesley used springs to carefully balance the blocking plate, and I used a different number of interference fins working with the magnets to balance the blocking plates. The magnets in my Interference Disc machine become the springs.

More photos of both Interference Disc machines are shown in fig.15, 15a and 15b below.



Fig. 15



Fig. 15a



Fig. 15b

Closing comments on the disc generator

In closing this discussion of the Interference disc generator, I would like to go over and point out some of the concepts that I incorporated into the design of my permanent magnet dynamo.

As I made further progress and completed the later stages of the Interference disc generator, it became clear to me to use certain concepts of the machine and incorporate them into the design of my multiphase permanent magnet dynamo. Some of these concepts are explained here.

I have constructed several interference discs that have a different number of blocking shields, some with 10 blocking fins and some with 11 blocking fins and others with 12 blocking fins. They are all interchangeable on the machine to change the phase relations between all the isolated coils. The 12 finned disc will produce a single-phase dynamo with all the coils in phase, and the 10 finned disc on the machine will produce a three phase dynamo. One phase represents four groups of isolated coils, and the second phase represent the other four coils, and the four coils left are the third phase, for a total of twelve coils. All just by changing the number of fins on the interference disc and or adding more layers. Using 12 magnet poles and the 10 or 11 interference fins on the disc, the rotor discs becomes magnetically balanced and easy to rotate in spite of the load on the coils. The 12 finned disc has a larger holding force because of the same number of fins as magnetic poles. However, it can be reduced to almost nil by adding more layers of interference disc and balance them against each other. Many in phase coils can then be added in series or in parallel to build your power levels to any desired potential.

Both machines have stationary coils, and the disc generator has 12 magnetic poles (6N and 6S), and the permanent magnet dynamo also has 12 magnetic poles (6N and 6S). The disc generator uses 10 or more fins on the interference shielding plate per rotor, and the permanent magnet dynamo has 10 or more coils around each rotor. There is the same number of interference blocking plates as there are induction coils on each of the two difference machines and the number of blocking fins and or coils are interchangeable. The back emf effects are different on both machines, the Interference disc generator demonstrates easy turning of the discs while the stationary coils are loaded, and when producing alternating current the permanent magnet dynamo rotor slows down when a load is placed on the stationary coils. Both machines produce AC power out of the coils and the Interference Disc generator has a closed magnetic circuit through the coils, and the permanent magnet dynamo has open magnetic circuit through the coils.

The Permanent Magnet Dynamo

I would like to begin this topic at this point by describing my permanent magnet dynamo machine.

I designed this machine to be completely interchangeable into many different motor generator combinations. These combinations involve different number of magnetic poles and different number of interchangeable coil poles in the same machine, two versions are possible, one with isolated coils and another with the coils that share a common core fig. 16.

We can change the magnetically balancing effect (*holding force*) by changing the number of coil poles or (*interference disc fins*) in relation to the magnetic poles. This turns the machine into a multipurpose, multiphase, variable output, and variable frequency ac dc permanent magnet motor generator system. I first designed this unique multi purpose dynamo in 1987 after I built my third Interference Disc generator.



Fig. 16

Dynamo description:

Rotor:

It is well known that a bar magnet has its magnetic field concentrated at the N and S pole ends, and the half way line between the poles of a magnet is the neutral zone, this is the region where the magnetic field is canceled or neutralized. The *ferrous* keeper ring I designed for this rotor is mounted near the axle and it has machined flat decks so the magnets attach flush to the deck of the



Fig. 17

keeper ring. Because of this feature, flux leakage is reduced at the keeper ring and the magnetic field concentrates at the rotor poles. With the poles of the magnet positioned near the axle and attached to the keeper ring in the rotor, the magnetic field that was there is now forced to add magnetic field density to the outer magnetic poles on the rotor rim. The density of the magnetic field at the poles is now greatly increased which makes a very powerful small size rotor. The *ferrous* inner keeper ring (*active iron*) that is installed inside this rotor design, is also the *neutral zone* of the magnetic field when viewing all the combined permanent magnets in the rotor. Shown is a cut away view diagram of the rotor, fig. 17.

I utilize rare earth rectangular shape neodymium grade 35 bar magnets with the dimensions of 3" long and 1"x1" on the end poles. There are 12 bar magnets mounted 30 degrees apart in NSNS configuration, and the bar magnets are attached to a precision machined inner keeper ring which makes the active iron the region of the middle of the magnetic field (the neutral zone). Another way to view this is to imagine two 3" long bar magnets attached together, you now have a 6" long magnet. Bend this magnet in half and install iron at the U and it now becomes a horseshoe magnet with two 3" long pole ends. It's a powerful rotor design in the fact that each of the 3" long bar magnetic poles has the field strength of a 6" long bar magnet. More poles on the rotor will allow for higher frequency ac generation at lower rpms, twelve magnetic poles on each rotor is shown in fig. 18, 19.



Fig. 18



Fig. 19

The drawing in fig. 20 and picture in fig. 21, shows twelve magnet poles in each rotor in relation to the position of the coils. Ten *amorphous* cores are shown mounted around each of three rotors before they were wound with magnet wire fig. 21. The machine I have constructed houses a total of three rotors side by side that are mounted 10 degrees apart in relation to their *magnetic poles*, each rotor has twelve magnets installed for a total of 36 magnetic poles shown infig. 20. This dynamo concept can be constructed to any size with unlimited numbers of rotors and coil combinations to fit any power requirements.



Fig. 20



Fig. 21

It is well known that a magnet exerts a force of attraction to iron bringing them closer together, after they have come together, they are in their **static position**. A force must be exerted to either the magnet or the iron in order to pull the magnet and the iron apart, removing them from their static position. The term **static position** is used to describe the point when the magnet and the iron bar are at their nearest point.

As in the Interference Disc Generator, this Permanent Magnet Dynamo I am describing also uses an internal magnetic balancing effect which reduces startup torque on the rotor.

In this system, one set of magnets is in their static position in relation to the coils, such as the impulse coils. Another set of magnets on one side of the rotor is not in the static position, and there is another set of magnets that is not in its static position on the opposite side. One side is half in to the coils, and the other side is half out the coils, allowing the rotor to have minimal start up torque in turning the rotor. The magnets function in two jobs, the first with its velocity is to cause induction into the transformer coils producing ac power.

The second function, is the opposite pair magnetic fields on the rotor balancing each magnet out of their static position in relation to the coil positions at any given time, they cancel their holding force which puts the rotor at equilibrium. This reduces the amount of start up energy required to rotate the rotor resulting in higher efficiency. It allows the rotor and or multiple rotors to turn easily and efficiently despite the inherent powerful holding force of the rare earth neodymium magnets. With the three rotor machine configuration, I have connected 6 impulse coils in three phase to function as the motor impulse circuits with a hall effect brushless motor controller fig. 22.

Star wound three phase motor impulse coils.



Fig. 22
Star wound
three phase motor impulse coils



Fig. 23



Fig. 24

Two more pictures of the one rotor dynamo option are shown with a 1hp dc motor turning the rotor with an 800 watt load on the coils, six 100 watt AC light bulbs, and two 100 watt 12 volt DC light bulbs, Fig. 25, 25a.



Fig. 25



Fig. 25a

The efficiencies of this dynamo are so far inconclusive with regards to producing an endless self running machine. Our research is continuing to improve the efficiency by eliminating all conventional type ac and dc motors from this dynamo, and incorporating high voltage dc impulses of very short time duration's as Ed Gray did with his technology years ago. However, a description of my early self running attempts is included near the end of this dynamo report. These tests have manifested an abundance of heat in the 24 volt dc drive motor.

Another picture of the three-rotor dynamo configuration is shown with 12 regenerating ac to dc coils, and with the motor impulse coils removed fig. 26.



Fig. 26



Fig. 26a

Another close up of the regenerating coils and three phase motor impulse coils is shown on the dynamo fig. 27.



Fig. 27

Tests to produce an abundance of heat

I have testing the machine so as the output coils are connected to regenerate a 12 volt battery as the motor is turning the rotors. I used a bran new conventional permanent magnet 1/4 hp 24 volt dc motor that is running on 12 volts to turn the 110 pound 3 balanced rotors, and or the 35 pound 1 balanced rotor version.

The regenerating output coils produce AC to DC power with no noticeable ripple on the scope. The generated direct current from the coils is connected to go back into the battery, in which the motor uses to produce the torque needed to rotate the rotor. As this happens, the regenerated dc power from the coils is again going back into the battery first, and then to the motor. The result is that the battery supplies less power to the motor when the regenerating DC current is going into the battery. The motor takes on a load from two sources, one is from free wheeling the rotor with out loading or drawing current from the coils, and the other is the load induced on the motor when the coils are loaded to produce current.

The dc permanent magnet motor has shown that during one of many switch mode tests, it consumes 15 amps at 12 volts from the battery while a chosen number of regenerating coils supply ? the amount of current going back to the battery. The battery supplies 50% of the amps and the regenerating coils supply the other 50% amps. This effect can be changed depending on how many open isolated regenerating banks of coils are activated and loaded.

This test shows a 15 amp draw the motor while it is turning the rotors under load while regenerating current from the coils. It may be they balance each other and both battery and coils supply 7.5 amps each that make the total 15 amps draw on the motor. This accounts for the 15 amps total load that is shown on the dc drive motor. It produces an excessively large amount of heat in the dc motor that is useable output energy. On a larger scale the heat generated in a given motor can be enormous. More accurate measurements are needed to determine the true energy in verses energy out.

However, this electric heat pump effect can be altered to produce more or less heat depending on the size and type of the drive motor, and the amount of regenerating coils that are placed under load. Cooling tubes wound around the motor with water flowing through them is a way to pull the heat out for useful applications. Hot water from the drive motor and electric power from the coils at the same time.

After running the machine, the amorphous regenerating coils remain cool to the touch where as the conventional dc motor gets very hot with higher amps going through it. The machine also has a longer running time when the coils are regenerating the battery, as compared to running an outside equal load with the same amp draw, in that case the battery drains much faster.

This sheds light with the observation of high heat build up in the motor side (less efficient side) of the circuit while being cooler on the generator side (amorphous side) of the circuit. After hours of run time the battery begins to drain, when this happens, the battery begins to show tangible temperature changes from one side of the battery to the other. The whole negative side of the battery remains cool to the touch (temperature drop), while the whole positive side of the battery gets warmer to the touch (temperature rise). The effect is repeatable and only happens when the regenerating coils are connected to charge the battery as it is running. It may be approximately 20 degrees difference in temperature, depending on how many regenerating coils are activated sending its current to the battery. There must be exothermic reactions and endothermic reactions going on inside the battery motor generator combination that is causing this temperature difference. The load and heat generated can be changed the on the motor from the flick of a switch that activates and loads the output coils, which in turn dumps it's energy back into the battery pack or outside load. The efficiency ratio of the machine changes depending on how many and which banks of regenerating coils are activated, which again also effects the temperature difference manifesting on each side of the battery, motor, and amorphous coils.

Other tests

An Automotion dc brushless 3 phase motor controller with hall sensors was used to test the machine in fig. 26a. Tests have shown the 1hp dc motor and the three phase brushless dc motor controller will not be the answer to closing the loop on this motor generator machine. The brushless controller has a 50% duty cycle which will not manifest the electro radiant effect, and it also has a constant draw on the battery as a regular dc motor does. It is much less efficient than using very fast and short unidirectional dc impulses in the motor impulse coils to kick the rotor around. This brings the subject of Nikola Tesla's magnifying transmitter and Ed Gray's radiant energy impulse motors to light, and a possibly answer to closing the loop for a real auto-rotating machine.

Before I go further with this, I want to point out the many phase possibilities this dynamo has. If you look at the coil arrangements in the 10 coil machine, you can clearly see the coils that are in phase with each other. When a second and third rotor is installed with all the coils attached, one pair of coils on the first rotor is in phase with another pair of coils on the second rotor, and another pair of coils is in phase on the third rotor. With the ten coil to twelve magnet pole rotor assembly, the machine has five phases of isolated banks of coils. If twelve coil mounting bars are attached around the three rotors, and the three rotors are spiraled off set by 10 degrees, you will have a powerful three phase dynamo. If the rotors are not off set by 10 degrees and are lined up in phase with each other, all the coils on the machine will be in phase for a powerful single phase dynamo. The volts and or amperage can be tailored for an application by the winding of the transformer coils, and the machine produces 60hz at 600 rpm. This dynamo machine concept is also interchangeable into many other motor generator combinations, and sizes, and any volts or amps requirements, it all depends on the needs of the end user.

Cooling tubes wound around the motor with water flowing through them is a way to pull the heat out for useful applications. Hot water from the drive motor and electric power from the coils at the same time.

It is possible to have super efficiencies with this system using unidirectional hv dc impulses of very short duration's at the make brake contact at the closure of the switch.

I have acquired two of Ed Gray's radiant energy impulse motors #4 and #5 to revive an almost lost technology. I am proposing to combine a special permanent magnet dynamo with less back EMF that is tailored to produce 5kv dc under 2000rpm. This dynamo will energize a 5kv dc capacitor bank and replace Gray's 12 volt to 5kv dc converter. The energized capacitor bank will discharge through the conversion tubes in the very same manner as in Gray's original circuit, only the capacitors will get energized from the high voltage dc dynamo instead of from a battery through an inverter. This version of a high voltage dc dynamo will be connected to and turned by Ed Gray's EMA motor, a starter motor will disengage after it begins running.

There are three banks of high voltage coils that are connected 120 degrees out of phase from each other, each bank represents 12 - 100 watt coils for a total of 1200 watts per phase. All isolated coils in each phase are wired in series to produce the high voltage dc potential to energize the capacitor bank. The isolated capacitor bank will discharge their potential through its conversion tubes in 120 degree increments each time the impulse coils are at their closes point toward each other. One isolated capacitor bank will discharge through the conversion tube with it disconnected from the dc dynamo circuit. The second isolated capacitor is at this point beginning to receive its charge from the dc dynamo, while the third capacitor phase is fully energized just before the switching circuit disconnects it from the dc dynamo for it discharge phase. This fully aligns all the isolated 3 coil phases in this permanent magnet dynamo system to the 120 degree three phase radiant energy impulse system of Ed Gray's EMA motor #5.

The plan is to eliminate all the batteries and converter and use a rotating high voltage dc dynamo in its place. Nikola Tesla used high voltage dc dynamos with capacitors as part of his magnifying transmitter to produce radiant electricity. So it seems logical to do the same thing, merging Ed Gray's radiant energy motor and our version of a high voltage dc permanent magnet dynamo. Could it regenerate a car, or power a home, and or a factory?

Shown below are pictures of Ed Gray's motors in fig 28, 29.



Fig. 28



Fig. 29

I would like to acknowledge two friends of mine who have helped make the Interference Disc machine possible, Bud Johnson 1986 shown in fig. 30 and the late Dr. Carl Reich shown 1987 in fig. 31. I would also like to acknowledge Wilbert Griffith and Brian & Rose Langan for their contribution in helping us make these projects possible, and there are others who wish to remain anonymous. Bud Johnson also an inventor, was one of the first people who I met after relocating to Alberta from the NWT, he made arrangements for us to construct the first disc machine in a machine shop.

Fig. 30
Bud Johnson

Fig.31
Dr. Carl Reich

Dr. Carl Reich was a pioneer in the alternate medical field and he published a book along with Robert R. Barefoot called "The Calcium Factor", copyright 1992. Through Carl's dedication and hard work with alternate health and energy, Dr. Carl Reich contributions have also helped made the Interference Disc machine and our Permanent Magnet Dynamo possible.

I also would like to thank my wife Jan Francoeur for being part of making this research possible, she has spent countless hours to prepare this report and assist in the reconstruction of these machines.

The test results and hypothesis I have written are not complete, and the research and development of the described magnetic energy machines is on going, and as such, the potential and performance and true efficiencies of these machines are still yet to be determined. This author knows that the aether is real and free energy systems are possible, and I will continue to work until I have completed the integration of Ed Gray's radiant energy motors with our larger version dc dynamo machine. When this happens, a new round of testing will begin with our attempts to run the two machines together in closed loop regenerating mode.

I hope I explained these energy machines in a way that you all can understand, and more information will be released as progress is made. ***You may find this information useful with your quest to be energy independent. However, if you profit from any of my ideas I have described in this writing, then in all fairness, please remember to reward the inventor so research and development can continue.***

This is my gift to humanity.

Interesting Information









New Propulsion Letter
from Paul Toomer <jorjencar@leeds322.fsnet.co.uk>

Please take a look at this new web site on how to challenge Newton's third law of motion at

http://magnetic.propulsion.mysite.freeserve.com

A NEW PARADIGM FOR TIME

EVIDENCE FROM EMPIRICAL AND ESOTERIC SOURCES

Donald Reed, USA
1032 Borden Road, Depew, NY 14043
Email: torsionpower@yahoo.com

The author of this article
presents an experimental approach
to the teleportation problem
and time pace control
and
space regularity questions.

Part I of II

ABSTRACT

The following essay seeks to establish awareness, through a far-ranging careful examination of various empirically documented anomalous research results in the field of new energy, the long-suspected evidence provided by associated key legendary secret government project work in the USA and former USSR, maverick new theoretical models in foundational physics for elementary particles/fundamental electromagnetic wave-field structures, as well as remarkably corroborative related information from esoteric (psychically channeled) sources, of the necessity for the development of a new paradigm for mass, energy and especially time. After having been guided through this process, the reader will hopefully be motivated to acknowledge the importance of this imperative for a new understanding of the workings of nature, as well as gain hints for the associated future development of new viable sustainable energy sources and related technologies.

Introduction

When we come to examine the annals of physics over the past century, we find them replete with several competing core theories of the physical world, each attempting to demonstrate a unified conception of space, time, energy and matter. Notable among these, the most successful and formally canonized in academia, are special and general relativity, and quantum theory, the latter of which includes quantum electrodynamics and quantum chromodynamics as recent offshoots.

However, even these fundamental theories have fallen short in achieving this coveted goal, due to many reasons, not the least of which is their failure to account for the anomalous but substantial documented evidence continually presented over the years by new energy research and other related empirical evidence considered outside mainstream science. In this author's opinion, these weaknesses in current physics and its relative ignorance and/or selective omission of the findings of non-orthodox scientific research, stem primarily from an ill-conceived institutionalized conception of **time**, as an immutable linear flow against which everything involving **change** can be measured. This "relational" concept of time treats it as a specific passive property of physical systems and changes happening to them. It is a one-dimensional continuous and homogeneous entity geometrically describing the property of duration. This antiquated relational view of time is abstracted from our unique prejudiced viewpoint as sentient beings whose particular point of waking conscious focus is this camouflage physical reality, which is apprehended through the limitations circumscribed by the physical senses.

Accordingly, modern physics is built on the basis of this relational conception of time. However, the use of this conception has not so far resulted in resolving all the problems associated with time. Moreover, so far even an essential definition of time has not been formulated in physics, there are only operational definitions indicating different methods of measuring time intervals.

In contrast, the "substantial" conception of time, advanced in this paper, implies that time is an independent phenomenon of nature existing side by side with matter and physical fields, whose active essence can and does affect objects and processes occurring in the universe. Moreover, the following dissertation argues, by positing that active substantial **change** is the basic concept and relational **time** is its derivative, that those objects and processes can also have a reverse action on time.

Accordingly, we will attempt to show, through a wide-ranging examination of new energy research and other information, the necessity for the establishment of a fluidic, elastic, field nature for true active time which is malleable; one in which even the local pace of time, and mass and energy content can be influenced artificially by intelligent technological control, or naturally by conscious intent, or by a combination of these two methods. To help motivate the reader's awareness for this imperative, we will also examine several esoterically-based sources from key selected psychically channeled transcripts. These will be taken from the following sources: unpublished comments by Jane Roberts on an altered state of consciousness[1] (indicated in this manuscript by J.R.), or published transcripts from **The Seth Material** and The **"Unknown" Reality** (indicated in the manuscript by UR)[2], published chronicles from the entity Kryon, channeled by Lee Carroll [3], and concepts from Wilbert Smith's legendary discourse: **The New Science** (NS) [4]. For easier reference, all psychically channeled transcripts will appear in italics, with my additional explanatory comments in regular type within parentheses.

Granted, our unique investigative foray, ranging as it does from the concrete arena of knowledge represented by the cutting edge of visionary science to the intangible arcane realms bordering on the spiritual, will of necessity lack the exacting logic of scientific rigor.

Nevertheless, we hope to provide, through just such a unique eclectic format, the beginnings of a possible fresh understanding of the workings of nature and perhaps ultimately furnish a conceptual basis for extending the structure of current physical theory to compatibly encompass the elements of a unified framework of physics and metaphysics.

As "unscientific" as this proposed venture may appear, especially to the contemporary physicist or theoretician, we unabashedly press on, secure in the belief that the currently perceived "mutually exclusive" bodies of knowledge defined through psychic means and that of orthodox physics are more closely linked than is currently suspected. Indeed, it will be demonstrated that that some of the psychically defined data bears a striking resemblance to the tenets of present empirical knowledge.

New Research

Theories Indicate Necessity for Novel Time Concept

A body of work which postulates a fluid-field substantial nature for time, is the esoterically-based book written by Wilbert Smith in the early sixties, **The New Science**. Here, Smith outlined a unified theory of all physical interaction by positing that an active mass-free field energy he termed the *tempic field* exists, and is the parent field structure out of which our passive relational linear clock time emerges. To be sure, this book and its specific format of exposition has its weaknesses, not the least of which is a writing style which taxes one's comprehension to the limit. All researchers who have attempted to connect Smith's knowledge with the frontiers of current scientific knowledge, new energy research, etc., have been frustrated by his introduction of terms which may or not have the same meaning as the corresponding terms in mathematical science. This practice causes many passages to appear so vague as to cause total bewilderment on the part of the reader.

> *...the establishment of a fluidic, elastic, field nature for true active time which is malleable; one in which even the local pace of time, and mass and energy content can be influenced artificially by intelligent technological control, or naturally by conscious intent...*

In coming to investigate the source of Smith's theory 25 years ago, I came into contact with Kenneth Killick of Canada. Killick was the individual who served as the original mentor and for a time a colleague of Smith in the mid-1950's. Smith, whose background was in electrical engineering, found it very difficult to accept or understand the philosophical overtones of Killick's thought. Consequently, he resorted to the use of psychic mediums to try to verify the information provided to him by Killick. This is the origin of Smith's association with discarnate entities known to those familiar with his work as "the boys topside". Thus Smith's subsequent writings promote such confusion perhaps because he only obtained a partial understanding of these cosmic ideas, and he opted to writing in a kind of code basically to try to hide his own confusion. Through my own association with Ken, I discovered that The New Science is able to be put into reference with known facts once the spiritual-philosophical elements of Killick's teachings are duly integrated. When this is done, "Wib" Smith's book can teach much and can become a cornerstone to new energy science. Otherwise, it remains at best, a fragmentary enigma.

The work by Smith and Killick is pertinent to the theme of the present paper, since they both showed through experimentation with a special caduceus-wound coil, that so-called relativistic parameters of mass and gravity, energy, and time-flow, can be altered through intelligent artificial control. Adequate delving into some of the elements of these theories will enable us to glean new insight for transforming the current paradigm of time. Further details on Ken's so-called tachion energy theory can be found in this author's earlier expositions on this subject in issues of **Energy Unlimited** (1978-1982)[5].

Smith's main error is in postulating a fundamental "spin" dynamics based upon conventional continuous rotation. As Killick points out, such a concept of spin on the microscopic level, precludes any possibility of true evolutionary change, in the cosmic sense.

Also, as we shall see presently, the continuous spin concept obviates expression by anything in the universe, of its personal moral responsibility. However, with tachion energy theory intact and untrammeled, the impersonal dualistic concept of interaction between two polar entities, such as is expressed not only in ordinary classical Newtonian physics, but its 20th century successors, relativity and quantum theory, is supplanted with the omnipresent workings of a **trinity** at all levels and manifestations of reality.

Indeed, the fundamental tachion field (mass-free) energy has **three** components: two polar opposite entities (a positive "charge" and a negative "charge"), and the ability for these two to be in what is called "static-dynamic balance". The static-dynamic balance completes the trinity.

A simple physical macroscopic manifestation of static-dynamic balance can be seen in two people arm wrestling. As the energy of one participant is brought to bear against that of the other, we will see a vibration or oscillation once a balance of their energies is obtained. As more effort is expended, the vibrations will increase in frequency and decrease in amplitude. At this point we will see a static state relative to the two arms; neither causes loss of arm position of the other. But simultaneously we also have a dynamic situation in the rapid oscillation which maintains, and is in turn sustained by the muscular energy which produces the static state of the arms. Both states mutually support each other's existence. The two component entities (the arms) resonate together, but without losing their own identity.

The implications of this last statement, missing in current physical theory, is unique to the system of tachion energy. We will see in the following that the dynamic functioning of these sub-atomic tachions is such that by their inherent ability to manipulate space and the time-frame of matter through static-dynamic balance, they do not harm anything else in their environment, nor are they affected (forced to lose their own identity) by the ambient environment. Accordingly, inertial mass is not an inherent component of tachion energy, but is a derivative of certain tachion field modes.

We spoke earlier of tachion "charge". We keep the word in quotes to underscore that this is not to be equated to electrical charge, but merely signifies two polar energy states of the primordial ground-form, out of which all known physical forces come to be manifest. These tachion energy states can be defined in terms of "rotational" motion. Again "rotation" must also be placed in quotes as it does not signify the common idea of continuous spinning. Such a concept was suggested above in connection with evolutionary progress in its cosmic interpretation.

The tachion-pair could be described as executing a "back-and-forth" ratcheting movement. The tachion-pairs are analogous to the ends of a drum majorette's baton. But unlike the twirling motion of the baton, the tachion-pairs do not demonstrate the classic macroscopic continuous spin motion, but oscillate in a 3-component "clocking" action.

In Fig. 1 we have drawn a circle and have divided it into three 120 degree arcs. The first motion in the tachion cycle is an arc from the 0^0 -360^0 location, to the 240 degree position. This movement is stated philosophically as the question, "Can I go?" In the second phase it swings back from the 240 degree position to the 120 degree point, and then returns to the 240 degree position. This graphically represents an analysis of the first question, and can be phrased as the "Let me think" component. Finally, then it proceeds forward another 240 degrees taking it past the 360 degree point to 120 degrees. This last stage is the action motivated from the analysis in stage two, and is entitled, "Yes I can". In this activity it will be observed that all path lengths are 240 degrees.



Fig.1
The 3-Component Tachion Movement

However, as representative of true evolutionary progress, the tachion-pair does not remain confined to the plane in its 3-phase cycle. After each "Let me think" stage, the entire pair unit could be considered to advance "upward", perpendicular to its plane of "rotation". The combined motions can be viewed as an elevation up an inclined ramp, screw-fashion (Fig. 2).



d) 240° Rotation, "Yes, I Can"



c) 120° & 120° Forward.
"Let Me Think"



b) 240° Rotation, "Can I Go?"



a) Initial Position

Fig.2
Tachion "Ratcheting"

Thus, while they clock themselves backwards in the plane, they never go back to where they were originally but only seem to do so from the point of view of an observer in the plane. This entire activity can be visualized as a diametrically opposed pair "rotating" in a plane, but there must still be considered an upward ratcheting movement. They execute the clocking motion simply because they adhere to the three principles of observation, analysis and motivation. A meaningful application of this idea to the structure of physics would eliminate the necessity for a totally impersonal type of interaction governed solely by force. Unlike all current theories of elementary particles, the tachion-pair, by its unique activity, thus expresses a personal moral responsibility. So this elemental energy of the universe never goes where it is not wanted, but only where it will not disturb its immediate environment.

The topological structure of each tachion in the pair is also significant in regards to this "ethical" modus operandi. First, tachions in their primordial state are massless, toroidal shaped fields which always occur in pairs. Like toroids, tachions will singly exhibit three motional degrees of freedom, to wit;

1. rotation around its major axis.
2. inner (P), or outer (N) rotation about its cross-sectional (poloidal) axis.
3. expansion and contraction of the field (each toroid pulsates radially about its cross-sectional axis).

As a pair-unit, the combined motions will give rise to the following possible orientations: two identical (N) rotations; (N) rotation - (P) rotation; two identical (P) rotations (Fig. 3).



Fig.3
The Three Tachion Modes

The dual (P) or (N) rotations will always lie in the same plane, whereas in the "mixed" rotation mode, the orientations of the tachions will be mutually perpendicular. In the pair unit, the energy will shuttle back and forth between the tachions by virtue of their harmonious expansion and contraction. The contraction of one pair partner is immediately compensated for by an equal amount of expansion in the other. When one is fully expanded and the other completely contracted, they will reverse roles executing the second portion of the cycle. There will be two points in the clocking cycle where the tachions will share an equal amount of energy ("field equity") stage. In each cycle of a tachion-pair the field equity stage is passed twice, a fact which is significant when topology of the field dynamics is considered (see [5]). Now, looking at the field geometry for the tachion-pair unit at the two field equity stages of the cycle, we observe that the two geometries are not identical but are *mirror images* of one another via a non-orientable field structure. See Fig. 5, which shows the isomorphism between the dynamics on a Moebius band (a non-orientable topological structure) and the tachion pair clocking cycle.


Moebius Cycle: Flags move in direction of arrows in 180° stages

Legend: Flag labeled R/L on Moebius corresponds to right/left tachion; (0°-360°). Flag pointing up/down corresponds to expansion/contraction in resp. tachion; (360°-720°) situation is reversed (U/D — cont./exp.); Flag masts pointing in same/opposite directions corresponds to max. field disparity/field equity for tachion-pair.

Fig.5

This suggests the remarkable idea that the space time points that the pairs generate are not, as commonly assumed, identical, static, and bereft of intrinsic character, but exhibit *enantiomorphic* topologies, which by virtue of their mirrored relationship exert upon one another a potential for dynamic interaction. For now we present a second diagram to illustrate the three pair energy modes: N-N, N-P, P-P, as well as one sequence of oscillation of the N-P pair (Fig. 4).


a) Three types of pairs:

b) Stages in clocking cycle of N - P pair (I thry V)

Fig.4

In this figure we note a unique trinity of field operation: two stages of maximum field disparity (I and III) connected by the intermediate condition of field equity (II). Upon postulating the additional requirement that the pair will create a new space-time location every time the field equity state is reached, we see that with each cycle the unit will not return to its original state with respect to the environment, but will advance to new evolutionary states with each pulsation. In accordance with the above comments, the tachion-pair unit "ascends" the evolutionary spiral via this unique action we have termed "clocking" motion. In acccordance with the description in Fig. 4A, in Fig. 4B, stage I represents "Can I go?", stage II represents "Let me think", and stage III represents "Yes I can".

Now, in this regard, the previous analogy of the tachion-pair as likened to the ends of a baton, where the baton rises and falls as it rotates, is quite apt. However, unlike the ends of the baton tachions are not rigidly connected but possess much freedom of movement outlined above. On the other hand, much like the baton ends, they are mutually supportive of each other's activity and requirements, never seeking to overpower, or to be eclipsed by the identity of their partner. In this manner they exhibit personal moral responsibility, as we have previously stated. By their mutual harmonious action tachion-pairs will progress in a true evolutionary fashion, while never harming anything else in the universe by their action.

> *...the dynamic functioning of these sub-atomic tachions is such that by their inherent ability to manipulate space and the time-frame of matter through static-dynamic balance, they do not harm anything else in their environment...*

Now, the above is an inherent characteristic of tachion-pairs as long as they go about their business individually- that is, in their pre-physical state. Now, when the three fundamental tachion-pair energy modes described above exhibit a slow clocking frequency, there is opportunity for them to join together whereupon we begin to see matter being formed. The element of mass, or inertia is provided by the binding activity of the (N-P) mode, which is a function of the slow oscillation of the pair unit. Besides the clocking frequency, the factor of inertial mass or density of physical substance is also dependent upon the amount of separation between the two pair components in each individual sub-atomic tachion-pair unit. In general, the denser or more massive an object is, the slower its microscopic tachions will clock, and the farther apart will be the individual toroid components. This is a classic push-pull situation, i.e., there is a key inverse static-dynamic balance relationship between tachion-pair pulsation frequency and their area of operation (density of field). The rest mass that any physical substance displays to macroscopic observation, is thus a direct function of the amount of energy supplied by the master field to sustain the oscillation of the pair-unit. Thus, a primary feature of tachion dynamics is the following: if we change the energy, we must expect to observe a corresponding change in the manifestation of the mass, and vice versa. Consequently, in tachion dynamics there is a built-in interchangeability of energy and mass, an idea which concurs with similar conclusions in Einsteinean relativity (notably, $E = mc^2$).

But here is where tachion theory and relativity part company. We have seen that our postulated "clocking" pulsation of the pair is the factor, which determines both space and time. Both **space** (area of pair operation), and **time** (frequency of pulsation) are mutually dependent on what **we shall call the master field of thought and intention, which determines the clocking frequency**. From the dynamic influence of the master field arises subsidiary conditions of time and space which are truly "fluid" qualities of tachion operation. This is indeed consonant with the assumptions of a proper unified field theory in which all the factors of our objective world as apprehended by the physical senses, are subsumed under the relative state of a guiding master field. Moreover, under the geometrical constructs of such a theory neither space nor time should be subservient to the other but should retain their unique qualities in a mutually supportive relationship. This is guaranteed in tachion theory under the fluid give-and-take of the pair operation. Relativity, on the other hand, despite its logical consistency, does not meet the above requirements. To his great credit Einstein recognized the need to integrate time with space in a synthesis that would retain the distinctive qualities of both. The result was a theory, which extended the classical Euclidean concept of 3-dimensional space as a kind of "cosmic container" of matter, to embrace a structure of space, which arises from the laws interrelating its material content. Thus, for instance, in his General Relativity theory gravitation became interpreted as a distortion of the spatial fabric by sources of mass-energy in a non-Euclidean framework. Unfortunately, as a foundation of his theory, Einstein mistakenly assumed a subservient role of time to space. He tried to "freeze" time down into spatial-like dimensions utilizing metric equations, which were variants of a basic form. Before a true understanding of gravitation is developed, the rationale for applying such metrics to this end should be seriously re-appraised. In short, instead of freezing time down into a spatial dimension in order to make it fit a world ruled by nothing but gravity, we must develop a conception of space sufficiently fluid to let true time have its proper place therein.

These and other similar ideas are articulated by Andrea and Paulo Correa in their recent insightful essay on the various serious shortcomings of relativity theory. They write: "Time is not treated by relativity as distinct in nature or in quality from the set of topological locations or lengths between points. Whether in the SR (Special Relativity) form of a flat Minkowski spacetime or in the GR (General Relativity) form of a curved Riemannian spacetime, the essence in relativity lies in its treatment of time as the fourth length of a 4-dimensional space. As the actual metric of a length of time is not fixed, only the intervals being invariant, one can no longer speak of the reality of timelines or of synchronicity" [6].

In their second installment, the Correas even imply the existence of a mass-free energy, which is an integral element of the Killick tachion energy theory: "From a strict physical viewpoint, only an energeticist position can make sense. While space and time may be considered to exist outside the function of matter, independently from it, *they cannot be conceived outside the function of energy*...the field remains conceptualizable (in Einsteinean relativity) only by the pseudo-Riemannian manifold, which, on its own, fails to analytically treat the difference in dimensionality between Space and Time, fails to differentiate between them as distinct manifolds, and fails to account for them as the intrinsic properties of energy in flux".

The tachion theory is such a model that delineates the functions of time and space in terms of a basic mass-free energy substratum. Now as we have seen, since tachion dynamics pre-supposes a static-dynamic balance feature connecting frequency of the pairs (fundamental time elements) with their area of operation ("fluid" space configurations), it represents such a foundation upon which to construct such a theory which will harmoniously treat time and space on an equal footing without neutralizing the unique structural features of each. Since the decrease/increase in the clocking frequency of the tachion-pairs will result in a corresponding increase/decrease of area of operation, the local *pace of time* will also decrease/increase at that space-time location. This is due to the push-pull relationship between energy and time. The intrinsic energy of a tachion-pair will be defined to be its energy of "motion" (energy in the "convergent", pre-physical state). Thus we see that an increase/decrease in the clocking frequency also implies that the intrinsic energy of the pair will also follow suit. Consequently, the intrinsic energy available for a manifestation will increase/decrease as time pace allotted for this purpose decreases/increases. Moreover, the product of intrinsic energy and time interval will always be constant due to the perfect trade-off between both factors in the tachion clocking action. This relationship is remarkably similar to the quantitative statement of the Uncertainty Principle in quantum mechanics in the form: $E \cdot t = h$. This formula states that the product of the energy exchange of a quantum mechanical particle and the time interval required for that exchange to take place, is equal to the so-called "quantum of action", or Planck's constant.

Thus, as a concomitant of tachion dynamics, which is argued could also be the basis of electron spin geometry among other things (see [5]), *time* is made malleable; no longer continuous, or rigidly uniform as in Newtonian conceptions, or subservient to space as in Einsteinean relativity, time "flow" can go to zero, and can even reverse under the application of certain electrodynamic field configurations such as provided by the caduceus coil and other devices [5]. With tachion dynamics even the laws of causality will no longer hold. This is due to the fact that tachions have a much broader field of operation than the purely physical realm. Thus, many unusual demonstrated features relative to quantum theory, such as the principle of Indeterminacy, quantum nonlocality (EPR experiment), "entangled particles" as well as hypothesized qualities of an *aether* of space, can find their source in this microscopic non-linear electrodynamic clocking oscillation attributed to the tachions. In fact, the ultimate expression of time as well as space to our sensory perception, could be a direct function of these substratum pulsations. From this consideration there emerges a new dynamic model for **fundamental time** as a "fluid-elastic" field effect arising from the unique ratcheting oscillatory motion of tachion-pair entities. Ultimately, it will be seen that tachions may even form the structural essence of consciousness itself, thus providing the long sought-for unifying link between physics and metaphysics.

N. Kozyrev

Other Recent Russian Research Implying New Dimensions for Time

Another key researcher who postulated an active substantial role for time was the Russian astrophysicist Nikolai Kozyrev [7]. He argued that the gap between the exact (physical) sciences and the natural sciences will not vanish until the principle of causality differentiating cause and effect is placed at the basis of the exact sciences. This implies the objective directionality of time or its flow. We encounter numerous manifestations of this principle in our life and in natural science. Yet this principle is new in both mechanics and physics as a whole. The natural scientist's time is not Minkowski's geometrical time, nor is it the time of mechanics, theoretical physics, etc.

> *Nikolai Kozyrev argued that the gap between the exact (physical) sciences and the natural sciences will not vanish until the principle of causality differentiating cause and effect is placed at the basis of the exact sciences*

As Kozyrev argued, mechanics has been using only the "geometrical" property of time, its duration size, i.e., the intervals between the events under study. Timed, these intervals acquire the same passive properties as the interval measured between two points in space. It is only this property of time that the objective sciences assumed to be existing objectively, postulating that all other time properties are subjective. However, if we want to differentiate causes and effects, in reality the *flow of time* must be a physical quantity, duly expressed mathematically and entering the equations of mechanics. The physical meaning and mathematical expression of the flow of time can be obtained from the space-time properties of causality. Thus, processes in the world occur not only in time, but also *with the aid* of time. Time flow is an active property owing to which time may act on a material system. Consequently, it is in the properties of time that the source maintaining the vital processes of the world must be sought.

From these arguments, we can also derive a fundamental property of time. Let us assume that we have changed by a certain technique the flow of time in a material system. In this process we have perhaps changed the stresses within the system and hence its energy.

However, it is impossible to change the total amount of motion of the system, i.e., to obtain a momentum equivalent to an external action. In other words, time may carry energy but no momentum. Time is a non-momentum material reality. From the above property of the flow of time, Kozyrev concluded that it follows directly that the rotation of a body may be used as a device for changing the flow of time in a system. Time flows into the system in the cause-effect direction, the rotation increases the flow, and hence the system obtains additional energy.

In attempt to verify his theories, in the 1950s, Kozyrev thus performed experiments with spinning gyroscopes and discovered, in agreement with his predictions, that the weight of the spinning system changes slightly depending upon the magnitude of the angular velocity and the direction of rotation. Although the effect detected was not large, the nature of the arising forces could not be explained by existing theories. By applying a vibrating framework to the gyroscope, Kozyrev also found that not only does time deliver an energy, but that near the cause-effect system *time density* changes. Time is rarefied near the generator and becomes denser near the receiver. In other words, time becomes stretched by cause and compressed by effect. In addition, the variation in time intensity is in inverse ratio to the first degree of the distance. This can be seen by the following consideration: Time is expressed by rotation and hence involves planes passing through a pole of the rotating system with any orientation in space. **In the case of lines of force issuing from a pole, their density decreases in inverse ratio to the square of the distance, while the density of planes can readily be shown to decrease with the first degree of the distance.**

Kozyrev discovered another property of time when investigating irreversible processes such as crystallization of a substance, condensation, or evaporation. This influence can be effected by any irreversible process and is registered by a measuring system without any preliminary excitation, i.e., when the cause and effect positions are not separated. In other words, apart from flow and density, time seems to have another property, causal orientation, resembling in a way the polarization of light [8]. This property proves to be so variable that even the sign of the observed influences may change and hence the reciprocal cause and effect positions become reversed.

Continuing his studies on the properties of time, Kozyrev (with V.V. Nasonov) conducted astronomical observations using a receiving system of a new type. When the telescope was directed at a certain star, the special detector positioned within the telescope registered the incoming signal even if the main mirror was shielded by metal screens. This fact implied that electromagnetic waves (light) had some component that could not be shielded by metal screens. When the telescope was directed, not at the visible but at the true position of the star, the detector registered a signal that was much stronger. The registration of the true position of different stars could only be interpreted as the detection of star radiation that had velocities billions of times the velocity of light. It was concluded that the radiation from stellar bodies hence had a component, which was non-electromagnetic. Kozyrev also found that the detector measured an incoming signal when the telescope was directed at a position symmetrical to the visible portion of the star relative to its true position. This fact was interpreted as a detection of the future positions of stars [9].

From the 1960's onward, additional Russian research groups continued and expanded upon the work began by Kozyrev on the unique non-electromagnetic radiation that was apparently a concomitant of all rotating bodies, whether accompanying macroscopic spinning objects of great mass (cosmological or terrestrial), or at the quantum level exhibited by elementary particles possessing recorded anomalous spin features which were not accountable by standard theories. This emanation which was exhibited by rotating bodies was termed torsion radiation [10]. Subsequently it was learned that this unique radiation was a part of all living or inert substances. This so-called "torsion field" research was carried on mainly in secret in the former Soviet Union, and only became known to the Western nations after the fall of the Iron Curtain. Many effects attributable to alterations in time and gravity have been reported through this research. For more information on this topic the reader is directed to this author's review in reference 10 and references therein.

Part II of II

Summary of Part I

It is the intention of this multi-part dissertation to motivate an imperative for considering the eventual establishment of a more expansive paradigm for the phenomenon of time, one which views time from the "substantial" as opposed to the orthodox "relational" standpoint. The substantial concept of time implies the existence of an **active** essence which can and does affect objects and processes occurring in the universe. Furthermore, approaching time from such a fundamental basis implies that by positing active substantial change as the ground form **prime mover** and relational time (**passive** "clock-time", or entropy changes) as its derivative, that those objects and processes can also have a **reverse** action on time.

Towards this end in Part I (hereinafter referred to as I), we considered the key research of the late astrophysicist N.A. Kozyrev who, in carefully controlled experiments which were subsequently successfully replicated, recorded phenomena which have hitherto been unexplainable by standard contemporary received knowledge- whether from the standpoints of Newtonian, Relativistic or Quantum physics. Kozyrev pointed out that only by considering time as an active essence, could these cited "anomalous" phenomena, which are virtual conundrums from the viewpoints of a relational (passive) concept of time, be duly formulated on a logical basis. Accordingly Kozyrev's associated "causal mechanics" incorporates an objective directionality of time flow, implying differentiation between "cause" and "effect". **Consequently, by applying a thermodynamically irreversible process to a physical system (example: vibration to a spinning gyroscope), the rotor in this instance would be observed to lose (or gain) a small but detectable percentage of its weight, depending upon the direction of rotation.** Moreover, in this process **linear momentum** (linear speed of rotation) is not changed, but energy is nevertheless delivered to the system by additional forces directed along the axis causing a change in **angular momentum**, and that near the cause-effect system of the irreversible process, **time density** is altered - rarefied near the generator and concentrated in proximity to the receiver. Kozyrev concluded that time is a non-momentum material reality.

Other experiments of an astrophysical nature showed that registration of the true position or future position (as opposed to visual-present-position) of different stars via the non-electromagnetic component of star radiation, demonstrated the existence of an energy essence, which was apparently instantaneous, or had a propagation velocity of at least a billion times the velocity of light. In this regard, Kozyrev opposed the conventional astrophysical paradigm, which posits energy generated/ emitted by stars is a physical consequence of thermonuclear conversion. Instead he maintained that via rotation, stars converted time essence into non-physical (or pre-physical) energy. The latter was nevertheless detectable on Earth by transduction through reflecting telescopes shielded by metal screens, of stellar radiation by a Wheatstone bridge. Hence the "impact" of time was detected by resistor electric conductivity changes (see I and references therein).

Leaving no stone unturned in our investigation, we also took up a discussion of the related Killick-Smith tachion energy model for fundamental (pre-physical) reality. Here we coined a new term- a **trinitivity** of action, which was underscored as a key feature of the operation of tachion-pair entities. Accordingly, we posit the existence of two polar topologically orthogonal toroidal fields, with the unique ability, by the mutual shuttling back-and-forth of their energies, to exist in a third auto-generated state called "static-dynamic balance". Now, since tachions are hypothesized to transfer energy instantaneously, inertial/gravitational mass is not a primordial component of tachion operation (see I). Here we see a striking similarity to the Kozyrev conception of the operation of time in interaction with a physical system - where energy changes are manifested without linear momentum alterations delivered. Likewise, the Smith book, **The New Science** (see I) treats **the hypothetical tempic field as a scalar quantity, which only has direction in relation to its distribution (or "density" change). Only through establishing what Smith termed a *tempic field* gradient does the tempic field possess vectorial nature.** Similarly, Kozyrev viewed time like space as possessing both geometrical and physical properties. The geometric property of time is duration (its scalar component), while physically the course of time is similar to vectorial field propagation and the density of time to field intensity. Although Smith and Kozyrev apparently never were aware of each other's research, the following quote from Kozyrev reveals that they both made key profound discoveries about nature which indeed bear more than a superficial similarity: "Time density is a scalar quantity, just the one observed in the above experiments. Time density decreases with increasing separation from the process creating it. Therefore, a vector property corresponding to density gradient and tractable as time obtaining, should also be observed"[7]. However, in I we also enjoined the reader to observe caution and selectivity when attempting to separate the wheat from the chaff in Smith's book.

Accordingly, the previous ideas are substantially correct, whereas his concept of "continuous spin" of tempic field energy is basically flawed. Killick replaces this outmoded counter-productive notion with a key ratcheting motion, like the escapement of a watch, which is performed by the tachion entities composing a pair-unit. Through this unique "clocking-motion", a cycle of tachion-pair operation exhibits what could only be described as an **ethical modus operandi**, passing through the three stages of observation - reflection - action. By virtue of this 3-stage process, tachion-pairs demonstrate in their individual activity and in interaction with their environment - *personal moral responsibility*.

This is indeed an unprecedented notion which implies that a type of conscious thought process can be ascribed to tachion operation. This can be related to current notions from quantum physics, relative to quantum coherence of states - such as wave-function collapse, Indeterminacy, quantum non-locality (EPR experiment), "entangled" particles, etc. This may be an indication that in such cases, whenever the Principle of Causality is breached or at least compromised, we may be witnessing the unique effects of the inherent conscious microscopic non-linear clocking oscillation of the tachions.

Along these lines, although Kozyrev did not report observing any effects of time energy, which could be considered as "value-motivated", he did report on an equally mysterious "after-effect" in many experiments, which could only be construed as signifying a **memory** process. For instance, it turned out that in experiments with a vibrating torsion balance (or pendulum), at points of support the emerging additional forces did not disappear when the vibration was stopped, but remained in the system for an appreciable time. Interestingly, **their relaxation times were found to be independent of the mass of a body but were dependent on its density**. The largest effects with maximum preservation times were observed on porous materials like brick or volcano tuff. In enumerating on this unusual preservation action Kozyrev observed: "...a body placed for a certain time near an (irreversible) process and then brought to a torsion balance, produced the same effect on it as the process itself...aluminum showed no memory. The largest memorizing effect for processes of both signs has been shown by sugar"[7]. Also, his colleague Danchakov later observed in conjunction with biological experiments that water with decreased viscosity due to having been subject to the action of a process, exerted a distant action on water that had not been under such an action, causing its viscosity to decrease as well.

In this second part of the current dissertation, we will examine other important related information gleaned principally from esoteric sources, referenced in I. These have been obtained from books by Jane Roberts: **The Seth Material**, **The "Unknown" Reality** (UR) [2], unpublished transcripts (J.R.)[1], and transcripts from the entity Kryon channeled by Lee Carroll [3]. This information is remarkably corroborative with that from Kozyrev research and the tachion energy theory. Finally, we will cap off our exposition with a brief examination of a bold new maverick physical theory of subatomic electron structure, featuring variable time/mass attributes, which could be the catalyst for bringing the cited elements from esoteric knowledge and empirical physics research (Kozyrev, etc.) out from their hitherto relative obscurity, to the forefront in our ongoing mainstream investigations in probing the cutting edge frontiers of not only physics, but those of the natural sciences as well.

Other evidence

When one compares the transcripts from various esoteric sources it's remarkable how similar is their description of nature's fundamental operations at the pre-physical level. For instance, a careful reading of the Jane Roberts' channeled transcripts from the entity Seth, reveals a remarkable close connection with the particles termed EE (electromagnetic energy) units and the above Killick teachings on tachion pair dynamics. But first a word of caution to the reader. We should resist the tendency to put into the frame of reference of our sentient physical experience, structures whose essence is fundamentally non-physical. The customary physical characteristics of duality and dichotomy of fields, and the related yardsticks of mass, length and time, for the most part, may not apply in this situation.

It would be impossible, however, to formulate a comprehensive model for the EE unit dynamics were none of the factors for gauging physical reality to be able to be applied to higher dimensional realms. Fortunately, one characteristic does survive the transition to the non-physical framework- the element of **pulsation**. Seth reports in [2] how EE units, much like tachion-pairs are built up and dynamically pulsate in response to thought patterns. First, depending upon the relative intensity of the emotional energy, they will instantly be drawn together in clumps or may just as quickly disperse. Furthermore, being of a pulsating nature, these units can expand and contract. Theoretically, there is no limit to their size or frequency of pulsation. Seth describes their operation in the following manner: **Now, there are electromagnetic structures, so to speak, that are presently beyond your instruments, units that are the basic carriers of perception. Their size varies. Several units may combine, for example. To put this as simply as possible, it is not so much that they move through space, as that they use space to move through. There is a difference**.

On this point, if our conceptions remain "earthbound" we will not perceive any difference between these actions, but once we cast our mental gaze beyond physical experience, an important distinction becomes apparent. To understand this, we need only reflect on the similar non-classical logic that is the basis for the non-orientable Moebius topology that we have seen governs the dynamics of the tachion-pair unit [5]. Tachions, whose translational movement is governed by the relative pulsation frequency, apparently enter and leave our level of reality at two times (field equity stages) during each pulsation cycle. Before leaving our plane, the tachion-pair constitute what we call a space-time point.

Upon returning to our level, due to the Moebius topology of the clocking cycle, their essence creates a new space-time point with enantiomorphic (mirror image) characteristics to the first. The resulting progress of the units in physical reality is thus manifested by a "jerkily discontinuous" movement. Summing up, since the units **are** the point they create, it can now be understood that the units **use** space (or the nature of the space-time points) to move through, rather than the case of macroscopic matter which moves continuously (or appears to) through space.

Seth continues his description of the EE unit dynamics: *Laws of attraction and repulsion are used and, in a manner of speaking, thermal qualities are involved, and this is the only hint that your scientists have received of them so far. The units charge the air through which they pass, and* *draw to them other units. The units are not stationary in the way that, say, a cell is stationary. These units have no "home". They are built up in response to emotional intensity. They are one form that emotional energy takes. They follow their own rules of attraction and repulsion. As a magnet will attract with its filaments, so these units attract their own kind and form patterns which appear to you as perception. They are electromagnetic, in your terms, following their own patterns of positive and negative charge. In this instance, like definitely attracts like. The units are just beneath the range of matter. None are identical. However, there is a structure to them. The structure is beyond the range of electromagnetic qualities as your scientists think of them. Consciousness actually produces these emanations, and they are the basis for any kind of perception, both sensory and extrasensory. These emanations can also appear as sounds and you will be able to translate them into sounds long before your scientists discover their basic meaning. One of the reasons they have not been discovered is precisely because they are so cleverly camouflaged within* ***all*** *structures.*

Being just beyond the range of matter, having a structure, but a non-physical one, and being of a pulsating nature, they can expand and contract. They combine qualities of a unit and a field, in other words. Since they are beyond the range of matter, upon which matter is formed, they will not follow the laws of matter, although at times they may ***mimic*** *the laws of matter. It is almost impossible to detect an individual unit, for in its dance of activity it constantly becomes a part of other such units, expanding and contracting, pulsating and changing in intensity, in force, and changing* ***polarity****. It would be as if the positions of your north and south poles changed constantly while maintaining the same relative distance from one another, and by their change in polarity upsetting the stablility of the planet- except that because of the greater comparative strength at the poles of the units, a newer stability is almost immediately achieved after each shifting.* Even the altruistic motives of the tachion-pair as cited by Killick parallels similar behavior of these EE units.

Again from J.R.: *The behavior of these units changes in the following manner. When a unit is in the act of combining with another, it aligns its components in a characteristic way. When it is separating itself from other units, it will align its components in a different way. The polarities change in each case, within the units. The unit will alter its polarities within itself, adapting the polarity-design of the unit to which it is being attracted; and it will change its polarity away from that design on breaking contact*.

Ken Killick has described the mutual action of several tachion-pairs bonding, as the origin of standard sub-atomic particles possessing features known to modern science such as mass, charge, spin angular momentum, magnetic moment, etc. Thus, according to tachion energy theory, the electron attains its validity, and maintains its structural integrity, by virtue of relations between the component pair dynamics [see [5]). Since for the bulk of their independent existence, tachion pairs are in the pre-physical state, we can speculate that they may actually be superluminal entities. Remarkably, J.R. echoes this view with similar notions: *...the electron achieves its validity because of these* (possibly superluminal) *orbital units* (tachions?). *What we see as an electron is not made of the same things as the orbital units, however; it is an* ***effect****... when you change the structure of the electron, you are changing the relationships between the orbital units. This change will require an application of energy. It may be possible to construct a chamber that would give the electron more freedom.*

Whatever we do now in the handling of electrons is not giving them enough freedom and we are structuring the way in which they can appear. The next observation made by Seth could prove to be essential in clarifying the true nature of time: ... *If electrons were given more freedom they would affect* **our notion of time in perceiving them. The way the measurements (on electrons) are made forces the electron to appear**

in a particular way, but actually it's flitting around, seemingly in many places in rapid succession (pulsing in and out of physical reality). Turning to the structure of elementary particles in [2], Seth offers a similar observation in which he describes the electron as commonly perceived by scientific measurement apparatus, as merely a shadow or facade of the actual electron entity which constitutes a multi-dimensional structure.

In terms of a structural model for the electron, Seth says it would be more appropriate to view these units as composed of *interrelated fields* rather than as the current conception of a particle or a wave. Correspondingly, both of these criteria are key elements of the tachion theory, which posits the electron as composed of two-pair tachion fields. The electron achieves its stability-integrity from the interaction of these free-wheeling units.

Electron Spin and Structure of Fundamental Time

The electron "spin" feature is also claimed to be integral to the exhibit of "time's arrow" in UR [2]: *The electron spin determines time "sequences" from your viewpoint. In those terms, then, a reversed spin is a reversed time motion... electrons, however, spin in many directions at once, an effect impossible for you to perceive. You can only theorize about it. There are "electromagnetic momentums" thus achieved and maintained- certain stabilities that operate and maintain their own integrity, though these may not be "equal" at all portions of the spin. There are equalities set up "between" the inequalities... time, in your terms, then, is spinning newly backward as surely as it is spinning newly into the future. And it is spinning outward and inward* (pulsing inward and outward of physical reality) *into all probabilities simultaneously.*

It is vital that you understand this inward and outward "thrust" of time, however, and realize that from this flows the consecutive appearance of the moment. The thrusting gives dimension to time that so far you have not even begun to realize... This inward and outward thrusting allows for several important conditions that are necessary for the establishment of " relatively" separate, stable universe systems. Such a system may seem like a closed one from any viewpoint within itself. Yet this inward and outward thrusting condition effectively sets up the boundaries and uniqueness of each universal system, while allowing for a constant give-and-take of energy among them. By their unique operation , the EE-units, which form the elementary particles such as the electron, serve as the conduit for this energy flow once it is transduced by elements of thought that Seth terms "consciousness units"(CUs). Continuing in UR on this subject Seth **describes how time can be alternately created or "broken down"**: *The consciousness units serve as source points or "holes"* (Black holes or White holes?) *through which energy falls into your system or is attracted to it- and in so doing, forms it. The experience of forward time and the appearance of physical matter in space and time and all the phenomenal world, results. As CUs leave your system, time is broken down. Its effects are no longer experienced as consecutive, and matter becomes more and more plastic until its mental elements become apparent*. These observations are corroborated by Kryon in his dissertations to follow.

Specifically, in the Kryon channelings, further insight on this electron "freedom" is given in the context of change of frequency: *...There is something we call the electron haze which is around the nucleus of the atom. The space between the energy haze and the nucleus (which is great), varies more than you think in matter. As the space varies, the speed (*frequency*) of the haze must change. It is in the physics where the speed of the haze is strong and fast that you have a different time-frame than your own... you have not yet accepted that an object can seem to be stationary- yet traveling (*vibrating*) very fast. Not in a linear time from point A to point B, but in the electron haze of its vibrating parts.*

J.R. corroborates these comments in this dissertation: *Einstein considered relationships of this sort that hold in the far universe as one increases velocity towards the speed of light,* *but there are also "inner" situations (*altered **stationary** states*) that relate these quantities, and that are much easier to get into.* In regards to atomic structure to allow for frequency changes, Kryon adds: *What is it that makes the distance between the parts change? This is the puzzle for the scientists. For the area between the nucleus and the energy haze although vast, is not void. It is a patterned soup of energy (*the so-called "vacuum"*), and it is within the pattern of this null that changes the distance, and therefore the speed (*frequency*) of the haze.*

Mass, gravity and time are intimately related to this frequency change in the atom. Witness the comments from J.R.: ***Time exists as an invisible drag on matter and this is interpreted as gravity. Time exerts a definite force like gravity, and this is connected with the behavior of the electron.*** *However, since we always look at electrons in a certain way and gravity in a certain way, we miss the connection.* And this related comment as well: *There is another equation to be discovered that expresses the relation between time, mass and gravity.* Kryon reiterates this sentiment, along with relatively detailed scientific information: *Gravity is an absolute product of the characteristics of mass and time... one of which you may change.*

*What has been missing so far in your thoughts is how gravity is related to time, and that the entire issue of gravity, mass and time is non-linear. You have yet to develop the formula of physics. It is not here yet, and we are going to give you three attributes of the formula, but without the formula. These attributes are understood but the way they relate are misunderstood. Your science is just now beginning to see the shadows of them, however. The first attribute of the formula is the ability to understand the **density** of mass. Why is the electron haze so far from the nucleus? We have told you that you can change this distance, and in doing so, the density will change in the mass that is defined by the atoms being shifted. The electron haze will have to vibrate faster (this is possibly the "freedom" referred to earlier by J.R.), the closer it is to the nucleus; when the electron haze vibrates faster, its **time-frame** will shift. Therefore, the second attribute of the formula is a time-shift, and they go together. Also, be aware that you make an erroneous assumption that the actual speed (frequency?) of the electron haze must always be the same no matter what the distance. This is not understood yet either. There is a difference between speed (velocity/translatory rate) and vibratory rate, and it has to do with the actual physical definition of the **electron haze**.*

Mass discrimination is the ability to control the density of mass. With a density shift will come a time-shift, and with a time-shift will come a third attribute...we will call the **reality of location**, or where the matter is... in which dimensional reality it goes to when shifted. Here is an axiom: **shifts in dimensionality when matter is changed in this fashion create a reality where the matter has to be to exist in its new form**. It might be inches from where you changed it or miles. That depends on how much it got changed. The difficult thing to explain to you is a concept that has not been recognized... that matter has a **reality index**, and that its core attributes are linked to where it exists in time and space. Therefore, the three attributes that must work together are **density, time-frame and location**.

Electromagnetic Field Manipulation of Cosmic Lattice and Time-Space-Matter

In regards to tapping this (mass-free) energy-haze-soup, between the atomic nucleus and electron shells, Kryon speaks thusly: *There's something we are going to call APD (atomic phasic displacement). This is a term that is going to refer to the ability to tap the (Cosmic) Lattice for unlimited energy. The Cosmic Lattice is balanced, but it is not quiet. The Lattice has astounding power. It has a flow of energy that I cannot explain to you, for there is no paradigm model for it yet in your thinking. Therefore, you would not easily understand. The Lattice has vents that we can best describe as necessary for the flow of energy. It balances the slight inequity of the* *polarity. The vents also have to do with time...you will always find two vents together. One will be prominent, the other will be secondary. You might graphically and clearly see one, but you will have to look carefully to see its partner. There are always two. This is an axiom or physical rule of the Lattice energy, and of the universe:* This information remarkably parallels Killick's teachings on tachion energy pairs.

Witness this Kryon pronouncement:*Hiding within common atomic structure is a marvelous peek at something that will totally and completely mystify you, for it will seem to break all the laws of time and space. The" twins" are a pair of atomic parts that always relate to each other, and are always found in pairs. You will discover that when stimulated correctly, they will always move together as a pair. When you start separating them by distance to experiment, they will continue to move exactly together. If one's energy is converted, then the other will do the same. This will cause you to totally reexamine your ideas of time and space, for this condition will not follow the "ultimate speed" of transmission that you thought was correct... that of the speed of light. You will have discovered something that travels faster than you can ever measure*. Compare this statement with the torsion energy claimed by the Russians to travel at a billion times light speed [10].

In returning to the discussion on how to tap the Cosmic Lattice for energy, Kryon continues: *The vents are very necessary for the balance of your universal energy. The vents are also energy portals, (drains, to you), and are where the front of each Lattice cell touches the back...Like so many other physical processes, however, its going to take a tremendous amount of energy in order to unbalance even one cell's null attribute...Once you understand how to" prod" the null to unbalance itself, you will be rewarded with a steady flow of energy, far beyond what you put into it. This is accomplished since you create your own tiny "vent". An unbalanced cell creates a situation where the other cells around it will try to" feed" energy to the one that is unbalanced. This creates a tap that will pull upon the Lattice indefinitely, as long as your work matches the properties the Lattice expects to see.* Kryon further expands on the specific method to accomplish this...*Here's how it works. Two magnetic fields together, postured in the correct way- a way that is very three-dimensional in your thinking process- will create a "designed magnetic field" that is very specific. It's one you have never seen, and does not exist naturally. Start with trying several magnetic fields postured against one another- of unequal force and pattern, and at right angles. Don't make any assumptions. Think freely. Done in the right fashion, these two fields will create a third pattern which is unique and is the product of the original two. This third custom-created pattern is the one that you want to deal with, and is the one that has the potential of manipulating the Lattice. Once you have created it, you will know of its special qualities by how dramatically it changes the physics around it. And this important admonishment is given:* Here is a caution. *Keep this experiment away from your body. Keep the experiment in check with your scientific methods. Go slowly. Understand what you're seeing before you go on to the next step. Do not expose yourself to any magnetic fields. Remotely conduct all energy experiments. Remember that magnetics also plays an important part within your body (DNA components).*

> *...your math told you that there might be a possibility of invisibility and that was your goal. This was again because you did not understand that because the distance between the parts change, it doesn't necessarily mean that the overall size will dramatically change or that it might vanish...*

Here is another. Understand that if you unbalance the Lattice too grandly and too greatly, you will have a ***time displacement****,* *for the process also involves the property of* ***time****... One of the actual physical players in the creative process of unbalancing the Lattice is the manipulation of the time-frame of matter.* ***This is not time travel, but time displacement.*** *It is where you are actually addressing tiny parts of matter, and changing the time-frame they are in. When the inequity of time-frames meet one another (*matter mixed up with differing time attributes*), the result is a displacement of distance (*reality of location*). Although there is no horrendous danger for Earth within this time displacement, it can and will affect the local situation within the experiment. In other words, it can create a matter-distorting effect, completely stopping the experiment, and actually dislocating the parts. We are not going to say any more about this at the moment, but the more astute scientific minds reading this will go to the next obvious step... and the answer is "yes", the Lattice is also the key to quick travel of large physical objects... even of very short distances.*

Possible Documented Demonstrations of Time-Space Warping

Such fantastic transformations were possibly evident in the Hutchison experiments [11], in which metal samples were catastrophically fractured when exposed to radiation from the unique electromagnetic field effect. It was also noticed that many physical objects of different composition which were separate in space before the electromagnetic field was applied, became inexplicably embedded in each other once these objects were radiated by the field effect. For instance, **pieces of wood contained metal knives**, etc. Other metal samples were catastrophically fractured in their molecular-atomic crystal arrangement, producing a substance which was uniform and geometrically symmetrical at one end but appeared to have the resemblance of corrugated cardboard at the other.

Also, similar to Kryon's assertion of the inevitability of time-shift with mass altering phenomena, in Hutchison's work anomalous inertial impulses were recorded on film, sometimes resulting in the complete lift/levitation of various substances of different mass. We notice also anomalous inertial impulses were a feature of the Zinsser "kinetobaric" effect [12], in which due to excitation by **sawtooth microwave impulses with very fast rise time**, a sample attached to a torsion balance, deflected the balance for days and weeks after the original excitation was extinguished. Notice the similarity between these results and those of the Kozyrev experiments, some of which reportedly featured a memorizing preservation effect on a torsion balance, etc.

We also find additional confirmation from the basically anecdotal evidence from the alleged legendary Philadelphia Experiment in 1943, which apparently caused either large time- or space (teleportation) shifts in a Navy ship. In fact, in another piece Kryon himself possibly speaks directly about the Philadelphia Experiment, providing us with further insight into important possible new paradigms for time, mass and energy: *In all your questions regarding magnetics and the massless condition, you have never asked about what happened in your year 1943. You tried to create a massless condition with coarse equipment and little understanding of what you were doing. In the process you actually did create an unstable massless condition for a moment. Its instability created a situation where, instead of a true massless condition, you received one where the time-frame changed but the parts within the sphere of the time change did not have the fine-tuned synchronicity needed for a massless object. The result was an actual distance displacement of the object instead of a true massless condition. Indeed, humans were involved on the large object and their biology was damaged greatly. Your experiment was done in an atmosphere of desperation, and your goal was flawed. For your math told you that there might be a possibility of invisibility and that was your goal. This was again because you did not understand that because the distance between the parts change, it doesn't necessarily mean that the overall size will dramatically change (or that it might vanish).*

Although this may seem like a paradox to you, the internal mechanics of small particle behavior supports this. The change is measurable but very small, much like what happens with heat and chill...Many of you have guessed correctly that ***magnetics and electricity play a critical role in the determination of the real attributes of mass****... and the magnetic variables that determine the mass product, are often working within very small particles to create the density of an object and also its time-frame. The time frame of a massless object is slightly different than your own, making you to appear slightly slower than the massless object. Its reaction to more traditional mass molecules around it is also predictable: because of the very slight time displacement, it tends to change the number of electrons within the atoms directly in contact with it. This is a clue on how to detect a massless object even if you can't see it.*

*The reason you felt the object (*ship*) would vanish was that you were able to simulate a "vanishing" in the laboratory with smaller objects. This observation was not consistent however, so you again were in desperation to try this experiment on a larger object. The "vanishing" was an illusion and was due to a distance displacement rather than an "in place" vanishing... does this give you a clue to long distance travel using magnetics and the vibratory rate of matter?... Only one human on the planet has ever captured a true massless condition, and even this was a coarse one and lasted for only for a few moments that were uncontrollable in scope. This massless condition was created in the primitive workshop of a great electrical scientist in your culture on the American continent not too long ago. If you were able to visit his workshop, you would note the holes in the ceiling and the patched glass-covered light port where his massless objects took off and wildly flew everywhere. If he had been born 50 years later he would have been able to control the attributes of the experiment. As it was, he did not have the precision tools you have now to direct and control such an experiment. It was his great passion to understand this phenomena, but because it was so uncontrollable and sporadic, he was never able to bring others to see it work, for he could not accurately create it consistently. This depressed him in his later years, for his was a great three-dimensional mind...* When asked the identity of this scientist Kryon replied: *The inventor of your multi-phase current, born in the land you now call Yugoslavia.*

From the above information, there emerges a remarkably consistent picture suggesting that atomic structure may not be as rigid or immutable as formerly thought. Changing the fundamental frequency of vibration of atomic structure can perhaps apparently not only change the density of matter by altering the distance of electron shells from the nucleus, but in so doing alter the time-frame of that object, its mass and also the reality of location of that substance. Certainly, the implications of the Kozyrev research, among others, can possibly form the basis for the eventual technological implementation of these futuristic principles. Perhaps those experimenting with the relatively detailed data provided by Kryon on APD can actually realize this coveted goal.

Maverick New Theories in Physics Suggest Fluid Nature for Time, Space, Energy

The Dirac theory is to be understood as a theory of the electron with electromagnetic interactions. It consists of the Dirac wave function and its properties, including the Dirac equation and relations to physical variables such as energy-momentum, spin and position probability current. In spite of its indisputable mathematical successes, the Dirac theory is still without a completely satisfactory physical interpretation. In particular, the so-called *zitterbewegung* ("jitter motion") is a distinctive feature of the Dirac theory which continues to be the subject of conflicting interpretations in the standard scientific literature. The concept of zitterbewegung was introduced by Schrodinger to interpret high frequency oscillations in free-particle wave packets of the Dirac theory. These oscillations with angular frequency $2mc^2/h$ arise from interference between positive and negative energy components of a wave packet. Schrodinger interpreted the oscillations as fluctuations in position of the electron about an average motion. However, this concept has not been interpreted in the bulk of the literature as having an objective significance, but has erroneously been viewed by standard theory as a mathematical artifact of the one-particle Dirac theory which does not appear in a correctly formulated quantum field theory.

However, as noted theoretical physicist David Hestenes suggests in the first of his recent article series in the journal, **Foundations of Physics** [13], it is only by interpreting the zitterbewegung literally and objectively as point particle motion, that a complete and coherent interpretation of the Dirac theory can be achieved. Moreover, this model has implications that have not yet been previously considered by established physics that relate directly to some of the key features of sub-atomic behavior enumerated in the tachion energy theory and also in the microscopic dynamics of elementary particles revealed by the selected esoteric channelings that we have previously considered in the present exposition.

In particular, it implies that the electron is the seat of a fluctuating electromagnetic field which oscillates with the DeBroglie frequency of the electron (1.6 x 10^{21}cycles/sec).

Thus, it tells us that a kind of electromagnetic wave-particle duality is implicit in the Dirac theory. Of course, this contradicts the conventional view that wave-particle duality is a property of matter which is completely independent of the nature of its interactions. If the zitterbewegung is an objective phenomenon, then it originates from electron self-interaction, since it persists in the absence of external fields. In this new theory which considers the zitterbewegung as an objective physical phenomenon, the electron mass and spin can be identified with the energy and angular momentum of electromagnetic interaction. It suggests that the self-interaction is such that there exist certain stable, non-radiating but accelerated states of motion; in particular, for a free particle, this implies motion in a circle with the radius of a Compton wavelength- the zitterbewegung. The zitterbewegung implies that some of the mass, at least, is kinetic self-energy associated with a spin, and it reconciles the mass with a zero mass of the bare electron. Thus, according to this bold new theory, the electron spin arises from a helical world-line in spacetime. To be sure, some researchers have previously postulated such a helical electron dynamics. Unfortunately, such models have failed to explain why a helical motion for spin should depend on interference between positive and negative energy states or why the zitterbewegung should depend on the way a wave packet is constructed, or even how the zitterbewegung can be the origin for electron spin despite the fact that it vanishes for plane wave states that certainly describe a particle with spin.

The Hestenes model does offer an explanation for such effects and accounts for the ubiquitous feature of spin angular momentum as a function of the zitterbewegung. The essential unprecedented feature of the Hestenes' zitterbewegung idea is the association of the spin with a local circulatory-helical motion characterized by the phase factor of the electron wave function.

Thus, we reach the conclusion that the complex phase factor of the electron wave function can be associated directly with an objective helical motion of the electron, which is, in turn, a derivative of the zitterbewegung. Although the idea of helical motion connected with the electron has been considered before, it has not previously been related to electron phase to produce a complete interpretation of the Dirac theory.

Moreover, in the next installment of his dissertation [14], Hestenes argues that the zitterbewegung is not only an objective dynamical phenomenon associated with the electron, but is a ubiquitous phenomenon, with manifestation in every area of quantum mechanics, even in the non-relativistic domain. For instance, by showing that spin angular momentum can be regarded as angular momentum of the zitterbewegung fluctuations, the zitterbewegung interpretation of the Dirac theory begun by Hestenes in reference 13 provides an explanation for the electron spin and magnetic moment in the physical circulation of momentum and charge. It also explains the mass as the energy of this circulation. Thus, the origin of the zitterbewegung is attributed to self-interaction of the electron with its own electromagnetic field. The relations derived by Hestenes in this article suggests that the interaction is of magnetic origin, since it has the form of a Larmor precession energy if spin angular momentum is proportional to a self-generated magnetic field. The so-called "rest mass" of the electron is thus a kinetic energy of self-interaction. It is this that gives the electron its inertial properties, and the flywheel-like nature of this inertia may be the ultimate origin of spin dependence in electron scattering. And the Heisenberg Uncertainty relations can now be attributed to the "zitterbewegung fact" that an electron cannot be confined to a region smaller than a Compton wavelength. Also, the stationary states of a bound electron exhibit a resonance of the orbital frequency with harmonics of the zitterbewegung frequency, which is imposed formally in the standard theory by requiring single-valuedness of the wave-function. Evidently, such resonances, so prominent in quantum mechanics, can be interpreted as zitterbewegung resonances. This leads to a new explanation of penetration of a potential barrier by sub-atomic particles as due to zitterbewegung fluctuations in momentum, and the Aharonov-Bohm effect as a shift in zitterbewegung phase. The zitterbewegung phase factor literally represents a physical rotation. The rotation rates of this phase in time and space directions are the source of the electron's energy, mass and momentum.

In his third paper [15], Hestenes draws a closer relation of the zitterbewegung dynamics to the Dirac theory by suggesting that the latter actually describes a statistical ensemble of possible electron motions, which are actually governed by the zitterbewegung sub-structure. Since the energy-momentum of the electron can now be interpreted in terms of a rotation rate in the spin-plane, Hestenes then derives a corresponding relation which defines a variable mass for the electron-another unprecedented idea which is in agreement with the information given by Kryon in his dissertations and Ken Killick's tachion theory. The mass m, the scalar radius of curvature r and the zitterbewegung frequency all covary with changes in the rotation rate in the electron spin-plane. Hestenes obtains a relation demonstrating that the electron mass is inversely proportional to the zitterbewegung frequency. This conforms to the relativistic concept of mass as a measure of energy content. But here, mass is concluded to be primarily a **frequency** measure. This also conforms to DeBroglie's original idea that the electron contains an internal clock with frequency determined by its mass, though for a free particle, the zitterbewegung frequency differs from the DeBroglie frequency by a factor of 2. Moreover, the new key relation derived by Hestenes: $m \cdot r = 1/2h$ (h, Planck's constant), says that this frequency measures the radius of curvature of the electron world-line, so it is a thoroughly geometrical quantity. Thus, as mass increases the radius of curvature decreases, in concert with the tachion dynamics as well. All this suggests that the electron mass relates our externally imposed time scale to a time scale intrinsic to the electron.

The reader can see that the information transmitted by J.R. is also remarkably similar in this connection. It should be evident that there is introduced a new concept of mass here, though, to a certain extent, it was already implicit in the Dirac theory. The formerly vague concept of mass as some kind of material stuff is completely gone. Also, no longer is vanishing mass a distinguishing feature of particles moving with the speed of light.

Corroborating Research on Oscillatory-Fluid Nature for Time

In his recent thought-provoking dissertation [16], Tom Bearden relates of the dynamic influence of time on a material system: "But we can also legitimately state that 'time is energy' and be rigorously accurate...Time is extremely compressed EM spatial energy...Without further elaboration, we speak of a 'mass' in which a small portion exists as 'masstime' rather than mass, as having been 'time-charged' or 'time-excited'.

The t-polarization wave in the time dimension is quite unique: The *spatial* energy of the wave is in equilibrium and not vibrating at all; instead, the photons comprising the wave are vibrating in their **time**-components... In short, mass m is changed into masstime mt by photon absorption... Rigorously, a mass does not really 'travel through time' continuously, per se, but proceeds with an overall serial change mechanism, driven by its total virtual and observable photon interactions, as m→ mt→ m→ mt→...We propose that this may account for the duality of particle and wave...The particle actually oscillates at a high rate between the m and mt states... Mass 'travels through time' by an extremely high oscillation between corpuscle-like state and wave-like state". Notice how Bearden's description of the macroscopic operation of time on a physical system closely parallels Hestenes' proposed model for of the zitterbewegung dynamics at the sub-atomic level which provides the electron (and possibly photons, etc.), with a time-substructure (its internal "clock").

We can see many other places in Bearden's treatise where the unique terminology chosen can now be put into direct reference with equivalent concepts and unique phraseology employed by many of the researchers examined in the current exposition. This cross-referencing certainly provides much needed clarification about key ideas for researchers currently involved with the development of this fledgling discipline that we shall term causal mechanics, after Kozyrev's designation.

All such efforts will help to place investigative endeavors currently scoffed at by establishment science on a firm rational foundation, as well as assist in synthesizing seemingly disparate but surprisingly related "anomalous" phenomena. For instance, to implement the science he has termed "vacuum engineering", Bearden often speaks of the necessity of establishing a "local time-stress of the **vacuum potential**". This process, which as we hope to have shown here is completely legitimate, is identical to what Smith calls creating a "tempic field gradient", Kozyrev's "alteration of time-density", or Alexander Frolov's "change in the local time-rate".

It can clearly be seen that such ideas can only be perceived as science fiction fantasy, if we observe strict adherence to all current received paradigms (even in superstring theory), which consider space and time purely from their relational standpoints. These theories must of necessity involve models employing scalable metrics for their proper description. However, once we embrace the novel view posited here that vacuum energy is primary and both local space and time are derivatives of this mass-free non-scalable dynamic non-local oscillating substratum, then we can conceive of space and time properly as complementary aspects of non-local conscious reality, neither fixed in a scalable manner or subservient to the other, but fluid and mutually interdependent features of energy in constant flux (see the related ideas voiced by A. Correa and P. Correa in I).

With this approach we will then come to acknowledge the technological feasibility of many of the "futuristic" claims made in the channeled transcripts. For instance, we can see that it will no longer be necessary to propel elementary particles to relativistic velocities, or to probe astrophysical systems possessing large gravitational fields, to recognize alterations in space, time and mass parameters, since these phenomena can equally as well be accomplished in the laboratory by modifying atomic structure of stationary matter through electromagnetic means. Once again, peruse the Kryon dissertations on this process, for it may be key to future technology.

For those who wish to further investigate these theoretical possibilities, the papers of **A. A. Nassikas** are recommended. Nassikas has postulated what very few researchers before him have theorized: the existence of a ground-form probability density function for energy, as a necessary precursor to the malleable (deformable) characteristics of time and space [18]. One of Nassikas' conclusions is significant in light of ideas articulated in the present exposition concerning the hypothetical tachion-pair model for reality (see I). Here we refer to the key push-pull oscillatory ("breathing") operation between space and time, which may be responsible for the structural integrity of matter as we know it (again re-read the Hestenes zitterbewegung model).

Researcher **Alexander Frolov** has taken Nassikas' theory even further to suggest an explanation for the **anomalous over-unity effect** that has continually been demonstrated in low-energy nuclear reactions (LENR) over the past decade [19]. In such so-called "cold fusion" cells the Palladium cathode is over-saturated with protons, producing a local imbalance in the vacuum engine, causing a local alteration in the time-frame of the experiment to compensate the local change in energy density. **Subsequently, as Frolov claims, this time-frame change converts non-local time-energy directly into heat energy, similar to Kozyrev's description of energy production by stars.** Perhaps this observation might provide the hitherto missing key in our understanding of fusion by electrolytic action.

Conclusions and Prospects

In the preceding paper it is sincerely hoped that the author has demonstrated ample evidence that will spur on researchers of a kindred spirit towards the development of new paradigms for space, energy, mass and especially time. All these concepts, as well as the foundations of current classical electromagnetic theory, are in need of a drastic overhaul before we can fully appreciate and understand the operations of nature as it interrelates the metaphysical-mental realms with the physical level of reality.

At any rate, the continual appearance of research results, such as the Kozyrev effect, which up to present apparently resists explication in terms of conventional scientific paradigms, certainly offers clear evidence of the incompleteness of our knowledge of nature, even in this enlightened era since the dawn of the new millennium.

Accordingly, hints as to how the Kozyrev effect arises in association with the postulated active properties of time, and how the latter interacts with known physical forces, can assist us towards the development of a more comprehensive paradigm which embraces a wider spectrum of human knowledge - one in which the current conundrums rampant in the foundations of theoretical physics, and biological science disciplines as well, which have hitherto prevented the establishment of a unified model of all physical interaction, can find satisfactory solution. Also, such empirical evidence which generally flies in the face of current scientific wisdom, presents the greatest challenge to our ongoing search for new sustainable energy sources which will be of absolute necessity in the future.

In this light, if formally integrated into scientific thought, the tenets of tachion energy theory, which is based on an altruistic modus operandi, also may hold profound implications for the status of our very social, political and religious structures as well. Indeed, unlike the impersonally motivated interactions believed to be the basis for force interactions in modern sub-atomic physics, which help sustain our illusory belief in the supremacy of the ego, the philosophical basis of tachion dynamics is an able reminder of the humility of purpose which should be the guiding force whatever our walk of life. Like tachion-pairs, in the ideal social structure individuals will work side-by-side, yet achieving a common accord. United in the circle of their activity they will work together joyfully in freedom, each with his own task, yet always conscious of the common bond.

With the full import of these simple truths appreciated, tachions may afford a rational justification of the formerly "unprovable" mystical doctrine of the omnipresent intelligent plan behind the working of the universe at all levels of conscious reality. We will come to realize the profound truth of Einstein's vision of ultimate reality couched in his heretofore cryptic statement, *"God is subtle, never malicious"*.

REFERENCES:

1 J. Roberts, unpublished remarks as transcribed by W.H. Kautz.
2 J. Roberts, **The Seth Material**, Prentice-Hall, Inc. 1970. Pp. 292-298.
The "Unknown" Reality, Prentice-Hall, Inc., 1986.
3 L. Carroll, **Alchemy of the Human Spirit**, (Kryon Book III), The Kryon Writings, 1995.
Letters from Home (Kryon Book VI), The Kryon Writings, 1998.
Passing the Marker (Kryon Book VIII), The Kryon Writings, 2000.
4 W. Smith, **The New Science**, Fern-Graphic Pub., 1964.
5 D. Reed & K. Killick, "Tachion Energy Theory"(Parts I-IV), **Energy Unlimited**, 1978-1983.
6 A. Correa & P. Correa, "Consequences of the Null Result of the Michelson-Morley Experiment: The Demise of the Stationary Aether , the Rise of Special Relativity and the Heuristic Concept of the Photon", **Infinite Energy**, no. 38, July-Aug 2001, pp. 47-64.
"The Sagnac and Michelson-Gale Experiments", **Infinite Energy**, no. 39, Sept.-Oct. 2001, pp. 32-49.
7 N. Kozyrev, "On the Possibility for the Experimental Investigation of the Properties of Time", **Time in Science and Philosophy**, Prague, 1971, pp. 111-132.
"An Unexplored World", **Soviet Life**, 1965.
A.P. Levich (ed), **On the Way to Understanding the Time Phenomenon (Part II: The Active Properties of Time According to N.A. Kozyrev)**, World Scientific, Singapore, 1996 (rare English language excellent critical review of Kozyrev research and theories).
8 M. Lavrentiev, "Detection of the Reaction of Matter to an External Irreversible Process", **Sov. Phys. Dokl.**, Mar 1991, vol. 36, no. 3, p. 243.
9 M. Lavrentiev et al., "Remote Effects of Stars on a Resistor", **Sov. Phys. Dokl.**, Sept 1990, vol. 35. No. 9, p.818.
"Detection of the True Position of the Sun", **Sov. Phys. Dokl.**, Nov 1990, vol. 35, no. 11, p. 957.
"Scanning the Celestial Sphere with a Kozyrev Detector", **Sov. Phys. Dokl.**, Apr. 1992, vol. 37, no. 4, p. 163.
10 D. Reed, "Torsion Field Research and Implications for New Physics and Energy Technologies" **Jour. New Energy**, vol. 4, no. 2, Fall 1999, pp. 151-164 (and references therein).
11 J. Hutchison, "The Hutchison Effect Apparatus", **Proc. Of the 1st Symp on New Energy**, Denver, May 1994, p. 199.
"Inside View of the Hutchison Effect", **Extraordinary Science**, vol. III, issue 4, Oct-Dec 1991, pp. 23-26.
12 T. Valone(ed), **Mechanical Energy from Gravitational Anisotropy**, Integrity Research Institute, Washington, DC, 1996.
W. Peshka, "Kinetobaric Effect as Basis for a New Propulsion Principle", **Raumfahrt-Forschung**, Feb 1974 (in German); trans. By D.Reed, **Infinite Energy**, vol. 4, issue 22, 1998, pp. 52-56.
D. Reed, "Translator's Analysis and Comments on the Zinsser-Effect Device", **Infinite Energy**, vol. 4, issue 22, 1998, pp. 57-59.
13 D. Hestenes, "Quantum Mechanics from Self-Interaction", **Found. Phys.**, vol. 15, no. 1, 1985, pp. 63-87.
14 D. Hestenes, "The Zitterbewegung Interpretation of Quantum Mechanics", **Found. Phys.**, vol. 20, no. 10, 1990, pp. 1213-1232.
15 D. Hestenes, "Zitterbewegung Modeling", **Found. Phys.**, vol. 23, no. 3, 1992, pp. 365-387.
16 T. Bearden, **Extracting and Using Electromagnetic Energy From the Active Vacuum**, Association of Distinguished American Scientists, Huntsville, Alabama, 2000.
"Giant Negentropy in the Common Dipole", **Proc IC-2000**, St. Petersburg, Russia, 2000 (in press).
17 A.A. Nassikas, **The Hypothesis and the Equations of the Unified Matter Field**, in New Ideas in Natural Sciences (Part I: Physics), St. Petersburg, Russia, 1996.
18 A. Frolov, **Work Created By Means of the Potential Field**, in New Ideas in Natural Sciences(Part I: Physics), St. Petersburg, Russia, 1996.



an online and published
magazine about Electric,
Hybrid, Fuel Cell Vehicles,
advanced batteries, ultra capacitors,
fuel cells, microturbines, free energy
systems, events and exhibitions worldwide

63600 Deschutes Mkt Rd,
Bend Oregon, 97701
541-388-1908 fax 541-388-2750
etimes@teleport.com
www.electrifyingtimes.com
Subscription $13/3 issues

On the Rotating Permanent Magnet System

Alexander V. Frolov, Russia
7 Lev Tolstoy Str., St. Petersburg, 197376, Faraday Laboratory Ltd.

In one of our issues we published an article about the results of the experiment conducted by S.M. Godin and V.V. Roschin. They started in 1990 at Moscow Aviation Institute (MAI) when a technical physics laboratory was created in Machine Industry Projects Institute at the "Aeropromservice" Association. Their research work was financed by private investors and was continued in close cooperation with Chair 310 of MAI, especially with Prof. PhD. L.K. Kovalev, Prof. PhD. V.V. Rybakov and PhD. K.V. Ilyushin. By 1991 "a device for inner energy of matter conversion" had been designed and tested (according to the Technical Design Assignment). The prototype was finished in the middle of 1993 (Fig.1).



Fig.1

The experiments resulted in the possibility of creating a 7 kW output power in load after the rotor was sped up to 10 rps, but in the autumn of 1993 the laboratory was closed due to the investors' financial problems. Now their research work is continuing in Moscow and we hope the scientists will obtain new experimental results.

You can email S.M. Godin for more information at: smgodin@online.ru

Considering the theoretical basis of the functioning of these systems I should suggest a number of interesting details for prospective researchers.

S.M. Godin, V.V. Roschin et. al. (Physics of Negative Viscosity Phenomena. Prof. Victor P. Starr. Massachusetts Institute of Technology) spoke of vacuum (quantum medium) as **a physical medium possessing negative viscosity.** At that rate, it is worth making assumptions that can be useful to the developers of this topic. I think that standard (positive) viscosity of matter, from the physical point of view presupposes the presence of positive friction and a "work-to-heat" entropy transformation. Consequently, **negative viscosity** should correspond to the **negentropy cycle** "heat is converted to work". This is exactly the stray heat conversion once described by Tsyolkovsky in 1914. Apparently, **the medium of the kind supports self-sustained vortices** characterized by the surrounding medium heat absorption, which was mentioned yet not explained by S.M. Godin and V.V. Roschin.

It is possible that all the elements of matter are the self-sustainable vortex structures. To mathematically describe these physical mechanisms, the notions "heat-work-heat" transformation and "time" or "gravitation" should be interrelated. Russian philosopher Pavel D. Uspenskiy had been making related research since the year 1910.



Fig.2

From the conventional point of view, this device (Fig.1) creates a circulating energy flux described by the Umov-Pointing vector (toroidal vortex) as the roller magnet field vector is vertical and the electric field is radial.

S.M.Godin (on the left) and A.V.Frolov (on the right), St. Petersburg, June 2001.

Inventor's Week Conference 2003, USA

Review is prepared by Editor Tatiana Ezhova

This year the annual Inventor's Week-end Conference was held on September 19-20 in Seattle, Washington. The conference featured several interesting inventions, including MEG.

Bill Alek demonstrated a device that he believed could let him detect Vortex-Energy. It was attached to a meter, and his belief was that if he walked into a naturally-occurring energy vortex carrying the device it would show him changes in gravitational and other energies. He cited the Vortices in Santa Cruz and Oregon as examples that might be good for experimentation.



Bill Alek



Z-Pod, Bill Alek

In his report "Introduction to Parametric Mass Fluctuation - a breakthrough in Energy and Inertialess Field Propulsion" Bill Alek presented the Z-Pod, developed to test a theory of solid-state parametric mass fluctuation. Here is the URL for a good overview of the device that he published online at www.intalek.com:

http://www.intalek.com/Index/Projects/SmartPAK/Projects/ZPOD/ZPOD_System03.pdf

Rio Von Sternberg

Rio Von Sternberg was presented as the original inventor of the MEG. He apparently has a patent on the device; however, from his presentation I understand that his configuration is somewhat different than the model that J.L.Naudin and T.E.Bearden have been experimenting with.

Alexander Peterson had a very interesting presentation on optical-mirror magnetic field systems. The crux of his presentation involved cutting precise notches into magnetic coils to separate them into identical optical-isomeric shapes. Apparently, by cutting a thin line directly down the center of the transformer-core is believed by Peterson to increase the efficiency of electric motors by up to 50%.



Alexander Peterson

Mark Plotkin, a well-known Washington DC attorney also took part in the conference. He is interested in new energy technologies and works with new technologies in collaboration with Mark Whitford at www.awetec.info. The photo of Mark shows him rotating a steel coil apparatus that was passed around the conference by Slim Spurling.

Mark Plotkin

Slim Spurling is an inventor from the Southwest, shown holding a helical-wound coil that he claims provides health benefits through an interface with zero-point energy. Spurling's belief is that this specific circumference of the coils provides a "Casimir-like Effect" that concentrates the energy.



Slim Spurling

Donald Smith

Note: Donald Smith, a well-known inventor, also took part in this year's conference. His work is described in more detail in a separate article of this issue.

Full information on the conference and reports is presented at http://ionvalve.com/iw/2003/conference2003.htm.

USA "Inertia" Patents

Information from www.rexresearch.com/inertial/



№ 6,290,622 (7/18/01)
Mechanical Force Generator
Murray, Lawrence D.



№ 5,890,400 (4/06/99)
Apparatus for Generating
a Propulsion Force
Oades, Ross A.



№ 6,089,511(7/18/00)
Method & Apparatus
for Propulsion
Rasmussen, James K.



№ 6,259,177 (7/10/01)
Motion Imparting System
Deschamplain, Daviv



№ 5,937,698 (8/17/99)
Centrifugal Propulsi
on System
Kunz, William T.



№ 5,966,986 (10/19/99)
Propulsion System
Laul, Virgil R.



№ 5,673,872 (10/7/97)
Apparatus for Energy
Transformation & Conservation
Shimshi, Ezra.



№ 3,492,881 (2/3/70)
Prime Mover
Auweele, Albert J. v.



№ 5,860,317 (1/19/99)
Gyroscopic Propulsion System
Laithwaite, Eric R. &
Dawson, Wm.



№ 5,831,354 (11/03/98)
Bootstrap Propulsion
System
Stopplecamp, Timothy J.



№ 5,410,198 (4/25/95)
Propulsion System
Butka, Kemal



№ 5,685,196 (11/11/97)
Inertial Propulsion
Plus Device &
Engine
Foster, Richard E.



№ 5,167,163 (12/1/92)
Energy Transfer Device
McMahon, John C.



№ 5,557,988 (9/24/96)
Centripetally Impelled
Vehicle
Claxton, John C.



№ 5,156,058
Converting Rotary Motion
to
Lineal Motion
Bristow, Theodore R., Jr.



№ 5,182,958 (2/2/93)
Non-Linear Propulsion &
Energy
Conversion System
Black, James W.



№ 5,782,134 (7/21/98)
Electromagnetically Actuated
Thrust Generator
Bouden, James D.



№ 5,488,877 (2/6/96)
Centrifugal
Inertia Drive
Lieurance, Richard L.



№ 5,024,112(6/18/91)
Gyroscopic Apparatus
Kidd, Alexander D.



№ 4,801,111(1/31/89)
System for Propulsion &
Positioning
Rogers, Charles E., et al.



№ 4,991,453(2/12/91)
Centripedal Device for
Concentrating
Centrifugal Force
Mason, Lyle M.



№ 4,784,006(11/15/88)
Gyroscopic Propulsion
Device
Kethley, Lancelot I.



№ 5,111,087(5/5/92)
Propulsion System
Butka, Kemal.



№ 5,090,260(2/25/92)
Gyrostat Propulsion
System
Derloy, M.S.& Derloy M.



№4,884,456(12/5/99)
Centripedal Device for Concentrating Centrifugal Force
Zachystal, George J.



№ 5,042,313(8/27/91)
Conversion of Rotational Output to Linear Force
Montalbano, Paul J.



№4,770,063(9/13/88)
Universal Propulsion Powerplant & Impulse Drive Unit
Mundo, James D.



№4,788,882(12/6/88)
Flywheel
Fulop, Charles.



№ 5,054,331(10/8/91)
Controllable Gyroscopic Propulsion Apparatus
Rodgers, A.T.



№4,856,358(8/15/89)
Conversion of Rotational Output to Linear Force
Montalbano, Paul J.



№4,744,259(7/17/88)
Apparatus for
Producing a Directional
Unit Force
Peterson, Oscar F.A.



№4,712,439(12/15/87)
Apparatus for Producing a Force
North, Henry.



№4,242,918(1/6/81)
Mechanical Propulsion System
Srogi, Ladislaw G.



№4,674,583(6/23/87)
Impulse Drive
Peppiatt, Alvin C., et al



№4,409,856(10/18/83)
Propulsion System
de Weaver, Fred, III.



№4,579,011(3/1/86)
Propulsion Apparatus
Dobos, Elmer M.



№4,577,520(3/25/86)
Mechanical Propulsion System
Colla, Joseph.



№4,631,971(12/30/86)
Apparatus for
Developing a Propulsive
Force
Thornson, Brandson R.



№3,889,453(6/17/75)
Propulsion System
Mast, Oscar.



№4,726,241(2/23/88)
Continuous Force & Impact
Generator
Melnick, Harry S.



№4,238,968(12/16/80)
Conversion of Centrifugal Force
to Linear Force &
Motion
Cook, Robert L.



№4,261,212(4/14/81)
Unidirectional
Force Generator
Melnick, Harry S.



№ 3,968,700(7/13/76)
Converting Rotary Motion
into a
Unidirectional Linear Motion
Cuff, Calvin I.



№ 4,347,752(9/7/82)
Converting Rotary Motion
to
a Rectilinear Force
Dehen, Frederick L.



№ 3,998,107(12/21/76)
Converting Rotary Motion
into
a Unidirectional Linear
Motion
Cuff, Calviv I.



№ 3,979,961(9/14/76)
Propelling an Object by an
Unbalanced Centrifugal
Force...
Schnur, Nicolas J.



№ 4,398,431(8/16/83)
Mechanical Power Transmitting
System
Melnick, Harry S.



№ 3,555,915(1/19/71)
Directional Force Generator
Young, Hersey W., Jr.



№ 3,750,484(8/7/73)
Centrifugal
Thrust Motor
Benjamin, Paul M.



№ 3,863,510(2/4/75)
Inertia Engine
Benson, Everett H.



№ 3,756,086(9/4/73)
Propulsion System
McAlister, Roy E., et al.



№ 3,916,704(11/4/75)
Vibratory Motion
Gaberson, Howard A.



№ 3,810,394(5/14/74)
Centrifugal
Mechanical Device
Novak, Leo J.



№ 3,807,244(4/30/74)
Device for Transforming Kinetic Energy
Estrade, Fernand.



№ 3,584,515(6/15/71)
Propulsion Apparatus
Matyas, Laszlo B.



№ 3,196,580(7/27/65)
Toy Vehicle Having...Self-Contained
Drive Means
Rakestraw, Robert G.



№ 3,177,660(4/13/65)
Propulsion
Apparatus
Haller, Paul.



№ 3,266,233(8/16/66)
Inertia Propulsion
Device
Farrall, Arthur W.



№ 3,653,269(4/4/72)
Converting
Rotary Motion
into
Unidirectional Motion
Foster, Richard E.



№ 3,683,707(8/15/72)
Propulsion
System
Cook, Robert L.



№ 3,182,517(5/11/65)
Variable
Oscillation System
Dean, Norman L.



№ 4,087,064(5/2/78)
Orbital
Propulsion
Apparatus
Knap, George.



№ 2,886,976(5/19/59)
System for
Converting Rotary Motion into
Unidirectional Motion
Dean, Norman L.



№ 4,095,460(6/20/78)
Converting
Rotary Motion into
Unidirectional Motion
Cuff, Calvin I.



№ 2,639,777(5/26/53)
Method & Device for Imparting
Lateral Movement
Dull, Marshall L.



№ 3,203,644(8/31/65)
Gyroscopic
Inertial Space Drive
Kellogg, H. Dudley



№ 2,636,340(4/28/53)
Direct Push Propulsion Unit
Llamozas, Juan D. M.



№ 5,150,626(9/29/92)
Translational Force Generator
Navarro, T. L.


JOURNALED TO A VEHICLE AT EACH END OF THE SHAFT

№ 3,238,714(3/8/66)
Thrust Motor
Schur, George O.



№ 2,009,780(7/30/35)
Centrifugal Variable Thrust Mechanism
Laskowitz, Isidor B.



№ 2,088,115(7/27/37)
Reaction Motor
Neff, Tom.



№ 3,404,854(10/8/68)
Apparatus for Imparting Motion to a Body
di Bella, Alfio.

The Free Energy Centrifugal Force Experiment

**This experiment is conducted by Faraday Lab Ltd
in cooperation with V. I. Bogomolov**

In the previous issue we wrote about the invention of Bogomolov V. I. The device shown in Fig.1 (and also on the cover) was constructed and tested in our laboratory.

Fig. 1
The Device

The simplified diagram is known as "Maxwell's Pendulum" (Fig.2). This is a disk set onto the horizontal axis with two attached strings. The upper ends of the strings are fixed to the crossbar.



Fig. 2

If we wind the strings about the axis, the disk will lift (the height h) and store the potential energy of the Earth's gravitational field E = mgh (m - mass of the flywheel; g - free fall acceleration; h - the height of the mass fall). If we let the pendulum go, we can observe periodic "up-and-down" damped oscillations: first, the string spins and potential energy converts into rotation kinetic energy; upon reaching the lowest point the disk, still rotating, goes up using rotation kinetic energy and then converts it again into potential energy. This device is interesting: due to the energy conservation law we can observe the usage of rotation kinetic energy of the flywheel, measuring only the h-parameter, the lift height of the flywheel strings in the second semi-oscillation compared to the height with which the pendulum started falling in the first semi-oscillation, the difference h1 - h2 of the two semi-oscillations is directly proportional to the losses of rotation kinetic energy for air resistance work and friction.

We have made "Maxwell's Pendulum" more complicated by substituting the flywheel disk for the Watt centrifugal governor in accordance with its description in the article (1). The main difference of the device from Maxwell's flywheel is that the flywheel inertia momentum changes by the centrifugal force operation at the lever transferring of weights (the total weight - 1200 g) from the minimum radius position (40 mm) to the maximum radius position

(90 mm). At that, the levers compress the string with the force of about 16 N.

There have been three stages of the experiments. During the first stage we define the necessary lift height of 1100 mm at moment when the string winds around the axle. When the flywheel falls from this height, the rotation speed and centrifugal force are achieved, which move apart the loads to the maximum radius (90 mm) and which **completely compress the string**. During the second stage the loads are fixed at the minimum radius position (40 mm), thus the compress string centrifugal forces are not involved any more and we can measure the air resistance and friction **losses of kinetic energy**. At this stage the flywheel lifts up to 980 mm losing 120 mm. During the third final stage the load fixing rods are taken away and ***centrifugal forces are applied***. Just like during the second stage the Watt governor starts spin-falling from the height of 1100 mm. It compresses the string and lifts up to the height of 1030 mm thus **exceeding the second stage height by 50 mm**!

The experiment conclusions of the author:

1. At the third stage the flywheel exceeds the "loss height" h=980 mm. This means that the compression of the string was performed "for free".

2. At the third stage the flywheel converted kinetic energy into potential energy and lifted up 50 mm more. This means that in accordance with the principle of conservation of moment of momentum, the **outer compressed string energy force** has caused the moment of momentum change of the rotating masses, thus giving the additional acceleration to the flywheel and **increasing its kinetic energy "for free"**!

3. For the practical application of the Bogomolov generator in order to generate free energy it is necessary to achieve a high rotation speed (more than 10 000 rpm) and involve centrifugal forces to transfer the rotating mass to the less possible inertia radius difference.

The described centrifugal regulator diagram is not sufficient for larger experiments. For the industrial generator the author has a hydraulic-principle pneumatic string device drawing (know-how).

Editor: Also in this issue: the article on "Glen Gates Motor" by A. Akau. The principle is almost the same. The further implementation of this ideamay soon design purely mechanical power-generating systems, which use inertia and centrifugal forces.

References:

1. Bogomolov V.I. "The Bogomolov Generator", New Energy Technologies, Issue # 4, 2003.

Magnetic Power Inc. (MPI) is developing Self-Powered Generators. Together with its subsidiary, Room Temperature Superconductors Inc., (see the website www.ultraconductors.com), MPI has raised a total of more than $7 million from Angel investors to date.

Due to a pleasant surprise, solid-state electric power generators might be fabricated by modifying off-the-shelf utility hardware. If confirmed in coming weeks, this could result in serial fabrication by this time next year, since large devices of the type needed for conversion are presently manufactured worldwide.

Multiple modules may prove able to replace power plants. Smaller units appear practical for powering homes. Later, optimized designs might replace engines in every variety of vehicle. These generators may make possible very rapid utilization of fuel and pollution free electric power --a revolutionary, new, renewable energy alternative.

Accredited Angel investors can help speed the work needed to bridge into major capital, and accelerate this remarkable alternative. Multi-million dollar funding is on the horizon. Additional information is available privately. We welcome due diligence by qualified parties.

History of Perpetual Motion and Free Energy Machines

Web site http://www.phact.org/e/dennis4.html

Hundreds of people for centuries have attempted to solve the holy grail of energy production - **Perpetual Motion Machines**. Still to this day Eric Kreig gets weekly emails from people who feel they are about to get one working. Eric is very skeptical about free energy. But his collection of information is very interesting. Eric offered a special prize for those who will agree to publicly test their over-unity devices.

♦ **Villand de Honnecourt** 13th century had a drawing of one.

♦ **Leonardo da vinci** made a number of drawings of things he hoped would make energy for free.

♦ Jesuit priest, **Johanes Taisnerius** worked on a magnetic based perpetual motion machine.

♦ **Mimara** in 1518 designed a "self-blowing windmill".

♦ **John Dee** of 16th century reported seeing one - but wasn't allowed a closer look.

♦ **Cornelis Drebbel**, 1610, was an alchemist and magician supposedly made one.

♦ **Robert Fludd** 1630 proposed many machines -people were trying to patent variations of Fludd's device in the 1870's.

♦ **Edward Somerset** 1638 demonstrated many free energy water wheels to the king of France.

♦ **1635** - first of many English perpetual motion machine patents granted. - By 1903, 600 such patents had been granted. Free energy claimants love impressing people with patents.

♦ **Ulrich von Carnach** in 1664 in Germany designed a perpetual ball-moving machine.

♦ Scientist **Jean Bernoulli** (1667 - 1748) proposed a fluid energy machine.

♦ **Bockler** in 1686 made designs for self powered water mills.

♦ In 1712 **Johann Bessler aka Orffyreus** investigated 300 different perpetual motion models and claimed he had the secret of perpetual motion and got much investment money.

♦ **Dr Conradus Schiviers** in 1790 made a belt driven wheel.

♦ **Sir William Congreve** in 1827 tried a machine running on capillary action.

♦ Britisher **Henry Prince** 1866 described the first partially submerged perpetual motion machine.

♦ **Mark Zimara** of Italy had a huge air powered machine that never worked.

♦ **Horace Wickmam** of the USA got a patent to a machine with many balls that just rotate around.

♦ Austrian, **Alois Drasch** patented a machine in the US in 1868.

♦ German, **George Andreas Bockler** proposed 'self operating mills' using variants of Archimedes screws.

♦ **E. P. Willis** of Connecticut made money off a perpetual motion machine in 1870 - people eventually found out a secret source of power to it.

♦ **Charles Redheffer** in 1812 in **Philadelphia** made much money on a perpetual motion machine, tried to restrict scientific evaluation, but was eventually debunked.

♦ Scottish shoemaker **Spence** designed a magnetic based machine, which was debunked.

♦ **John Worrel Keely** of Philadelphia in 1872 (he also had a traveling show of exhibitions). He fooled many scientists with a machine, which appeared to run on water.

♦ **John Gamgee** in 1881 got considerable support for a machine very similar to Dennis Lee's, which used liquid ammonia - it got vaporized from heat readily available, thus expanding it would drive a piston. Gamgee thought the vapor would condense to liquid to start the cycle over again. The Navy appeared to have been fooled and showed it to president Garfield - it never went anywhere Tom Napier agrees that Dennis Lee may have resurrected Gamgee's engine.

♦ **J. M. Aldrich** was arrested for getting investors for his free energy machine in 1899 - he some how was able to avoid conviction and conned many investors. One of whom was finally able to inspect the machine found a hidden spring.

♦ **T.H. Moray** in the 20's demonstrated a "radiant energy device" to many people who were unable to find a hidden power source. Some how, the secret was said to have been forgotten.

♦ **Lester Hendershot** in 1928 got an Army commandant to endorse his free energy machine - but it was later found to have a hidden power source in the motor. His sons believe Lester lost his notes and that maybe they can rediscover how to get it to work.

♦ **Viktor Schauberger** claimed to have discovered some special vortex energy in water. Since he died in 1958, I don't know if his claims have been replicated, but people are still studying his works.

♦ **Mr Papf** in 1966 was a conspiracy believer alternative car engine got a few investors but killed someone during a demo. He tried to blame the problem on an investigating skeptic. He disappeared and became part of urban legend of scores of people, which the big conspiracy has been silencing for generations.

♦ **Guido Franch** was convicted of fraud in 1954 and 1973 of selling rights to distribute little green pills that would convert water into gas. He hid behind conspiracy theory and secrecy to avoid fair testing. A number of people have run this scam and many people still believe there are pill repressed by the oil companies.

♦ **Garabed T.K. Giragossian** in 1917 claimed to have a free energy machine. He was one of the early frauds to hide behind conspiracy theory. Woodrow Wilson signed a resolution offering him protection from some kind of conspiracy. After much fanfare, and delaying tactics his machine turned out to be a giant flywheel, which was charged up with energy slowly and put out a lot of energy for just a second. In spite of lack of proof of anything significant his followers still bothered the US congress for recognition.

♦ **Otis Carr** in 1958 sold stock for a company to manufacture UFO's and free energy machines from Oklahoma. He claimed inspiration from Tesla.

♦ **Edgar Cayce** even babbles about "Motor's with no Fuel".

♦ **McClintock** was claimed to use air as a fuel and had a patent.

♦ The **Evgray** machine scammed many investors (who didn't know how to test 'depleted' batteries).

♦ **Arnold Burke** in 1977 collected $800,000 of investor money (again, mostly from bible believing farmers) for a 'self acting pump'. He tried to hide behind religion. He called his device Jeremiah 33:3' Finally, an open test was done in 1979 and found a hidden source of electricity. His believers (with an infinite supply of denial) still raised $250,000 to get out of a fraud conviction. He still went on making lots of claims with no evidence.

♦ **Robert Adams** in 1977 made all kinds of conspiracy and OU claims in New Zealand. Many still believe in the Adams Motor. - He had the obligatory battles over patents, debates over theory, debates over power measurement and dabbling in other areas of alt physics. He's 80 years old and said to have a scientific education. He has a lot of theories about Aether. Skeptical information.

♦ **Robert Stewart** in 1978 got over $3,000,000 of investment money (much from farmers) for a closed cycle engine using freon rather than water. This 'engine' used the same scheme John Gamgee tried to sell the navy in 1882. -Eric Krieg thinks this is the same approach Dennis Lee's free energy machine works on. I think he just faded away (people claim he was silenced).

♦ **Rory Johnson** of Elgin Illinois, claimed to have invented a cold fusion, laser activated, magnetic motor that produced 525 HP, weighed 475 lbs, and would propel a large truck or bus 100,000 miles. After signing a number of dealers, he moved all his equipment out of his labs, moved to CA and died. (To this day, folks say he was silenced by OPEC).

♦ **RJeseph Maglich** was a physicist and claimed to have a device in 1978, which harnessed fusion power from seawater. They say they put power in and get more power out. I've never heard of them since.

♦ **Howard Johnson** got a patent for a device that claimed to make free energy from a motor like device. As of 11/02, Stephen was claiming he would soon mail out samples of working ones. By 12/12/02, Stephen dropped out of contact.

♦ **Keith Kenyon** had a device claimed to produce more energy than consumed. Calculations seemed to not take power factor (also known as phase angle) into account. It never openly had its output hooked up to its input. Even Dennis Lee tells his followers that all the *over unity motors* (claim to make more electricity than consumed) usually just fool people who can't measure power factor.

♦ **Muller:** Bill Muller and Carmen Muller of Germany raised money on an over unity motor and got a few followers, but never actually demonstrated one working.

♦ **Dennis Lee** Since 1988 has been promising to demonstrate free electricity "in a month or two". He is much like Newman in his mixture of religion & extremist politics, evasion of qualified investigators, endless promises, threatening detractors, etc. He had a Fischer engine, a CRD device and now, and OU motor device. Dennis has invested in Searle and Stanley Meyer and joined Pantone in 2001 in a 50 state tour.

♦ **Stanley Meyer** 1996 claimed to have a water powered car and was also big on mixing Christianity and patriot politics in with fringe science. Meyer was found guilty of fraud after his Water Fuel Cell was tested before an Ohio judge. It is rare for an inventor to be prosecuted for an invention that does not work, but Meyer's problem was that he had been selling "dealerships", offering investors the "right to do business" in Water Fuel Cell technology. Meyer refused to allow anyone else to measure his device. Dennis Lee invested in him. He died in early 1998.

♦ **Joseph Newman** in 1984 claimed to have a free energy machine based on alternative physics. Like many perpetual motion inventors, he sued the US patent office. Many people wrongly measured the true power output of this machine, (they didn't realize you must specially calculate power for non sinusoidal current consumption). He now refuses to ship a unit for testing. Ten years ago, inventor Joseph Newman gave an open week-long demonstration in the Super dome in New Orleans. Over 9,000 people attended from across the country (including Dennis Lee who reportedly wanted to join his ideas with Newman). Newman is suing some former investors he claims are trying to steal his invention. I give more information. Evan Soule of Newman's organization offers a rebuttal.

♦ **Bruce De Palma** had a machine in 1986, which appeared to one Electrical Engineering professor to put out 4 times more power than consumed. Turned out it was just a measurement error. (We could go on and on with such examples).

♦ **Dr. Potapov** sold a device that was claimed to produce more energy than consumed.

Editor: Eric's skeptical remarks can be tolerated but sometimes he writes about the things he does not know. Potapov and his team have created a technology, which have been replicated and sold by dozens of companies in Russia (see the cover picture of the Susorov heat generator). There are several devices in St. Petersburg to be tested. The efficiency is 200 % and more. The operation principle: electric motor rotates in water and causes the heating of water. We have also received the information about another Russian invention, namely the close cycle vortex generator: "water rotation – vapour – turbine – electric power " (the power is from 100 kW).

Alexander V. Frolov

♦ **John Bedini** claims to have a free energy device.

♦ **Mr. Finsrud** is a Norwegian artist who made a sculpture where a metal ball moves for weeks apparently with no outside influence.

♦ **Don Watts** of Las Vegas in around 1990 had a patented **CEACU**, which stands for Centrifugal Energy Amplification and Conversion Unit - it turned out to be one more investment fraud.

♦ **Stephan Marinov** claimed to have proven much alternative physics and to have contacted a Methernitha that claims to have a Free Energy Machine. He committed suicide on July 15, 1997 but he left behind some intense rants.

♦ **Greg Watson** sold kits for a rolling ball and track that were thought to have over unity in 1997. Attempts of replication I know of have failed.

♦ **CETI** These people have claimed to have a device that puts out anomalous yet small amounts of heat - maybe cold fusion. They raised millions. As of 10/97, they have not been willing to have me come over and see for myself. They have said, *we want people to think it doesn't work so we won't have competition.* I've wondered if the energy may have come from not accounting for friction effects from the cooling flow through the pellets. (**Jed Rothwell**, a rational editor of Infinite Energy Magazine says "*however, tests with CETI cells at Motorola, SRI and the French Atomic Energy Commission show no measurable friction*"). Milton Rothman has a response: "I openly admit that I have not followed all the history of cold fusion claims and am generally ignorant on the subject".

♦ In January 1998 **Barbara Hickox** allegedly has a patent dating from 1981 for a fusion powered free energy system.

♦ **Paramahamsa Tewari** of India claims to have a device that is 200% efficient.

♦ **RQM** is a Swiss company selling FE machines found at www.rqm.ch.

♦ **Ted King** is looking for people to buy stock for a car he plans to drive across the country using just 2 12-volt batteries. You can contact Ted if you want to buy shares.

♦ **Bruce Perreault** has claimed to have discovered a new element, the plasmatron, ion pump, radiant energy device, etc.

♦ **Daniel Pomerleau** of Canada claims to have something that works, but he isn't interested in releasing it (as 12/97).

♦ **Entropy Systems** of Ohio 1999 Sanjay Amin got 1.6 million investment dollars for a device that would violate the 2nd law of thermodynamics. I've asked them to apply for my prize for proof. - They seem to have folded. See a rational review of Amin's claims.

♦ **Brian Collin** of Australia claims revelation from God *(like most of these people)* to make a free energy device. A Stephen Mark claimed he invented it.

♦ **Kawai** and **Takahashi** - both of Japan claimed in the 90's to have overunity devices.

♦ **Carl Cella** claimed to have one of the many cars said to run on water.

♦ **Robert LeBreton** in 1999 claimed to be making a 600 hp free energy machine.

♦ **Renzo Boscolio** in 1999 in Italy claimed to have low-energy nuclear reactions but refused to supply real proof that he promised to people who came out from Infinite Energy Magazine.

♦ **Doug Konzen** of Seattle says he has an overunity motor in Jan of 2000 that anyone can see.

♦ **Troy Reed** of Oklahoma was ready to issue licenses for manufacturing his permanent magnet motor etc. He's taking investment money for a device he claims puts out more heat energy than input energy. He says he's dumped a few million into his designs over the last 10 years and had little interest in my prize offer when I contacted him in 2001.

♦ **Kipper Motor.** In 10/00, Steve Elswick thought it was overunity. But David Sligar who paid $175 for plans could not get it working.

♦ **Ludwig Brits and Victor Christie** in 2001, claim the **Lutec** free electricity over unity motor/generator will soon be in Australia.

♦ **Jasker** in 2002, an Irish company has claimed to have free electricity. (Some have said it is just a joke).

♦ **Confidential Technology -Wayne Cochran** died 12/29/02 Crazy Jack Carey took over. They have been promising FE soon for about 20 years now.

♦ **Tom Bearden's MEG device:** many articles on the Internet.

♦ **Gurbakhsh Singh Mann of India** claims to have invented gravity and buoyancy perpetual motion machines.

♦ **Michael J. Marshall** in Las Vegas has a device called QSFG , which stands for quick start fuel-less generator he says 64 nations have asked him to build factories.

♦ **Carl Tilley and Robert Kibbey** in 6/2001 in Tennessee have claimed some over unity device and other stuff. Their demonstration failed in 9/02 and as of 11/02, they have been evading proper demonstrations.

♦ **Stephen Walker** in 9/2002 promised to send me and several others a free energy machine in mail.

♦ **PerEnDev** promised to make some kind of free energy by means of magnets.

♦ **Bill Muller** of Canada in 2003 claimed to have some kind of OU device. Independent tests found it under unity.

♦ **Energie:** In 2003 this Greek company promised a homopolar magnet (De Palma design) FE design by June of 2003. They actively seek investors.

♦ **GWE Genesis World Energy** In 2002 this group claimed to have 400 people who developed some device that sounds like it separates water into H2 and O2 using less energy than mainstream science says is possible. As of 2003, they have evaded independent confirmation. More information is available.

♦ **Steven Greer (Disclosure Project)** In 02.2003, Steven announced he had discovered some real sources of Free energy, which he promised to make sure get proven to the general public.

Tesla Energy Science Conference and Exposition

1220 L Street NW, Suite 100-232 Washington DC 20005
Tel: 800-295-7674
Fax: 301-513-5728
www.IntegrityResearchInstitute.org
Email: iri@erols.com

Saturday, November 8, 2003

Wireless Electricity Seminar

9:30 AM 10:15 AM

Opening Address: “Space Solar Power” – Dr. **Paul Werbos** Program Director, National Science Foundation

10:15 AM 12:15 PM

Special 2-Hour Presentation: “Nicola Tesla and the development of RF Power Systems” - Dr. **James Corum**, Physics Professor, research Scientist and Inventor and **Kenneth Corum**, Physicist, teacher, consultant.

2:00 Pm 3:00 PM

“Power Engineering Scalar Field Theory: Faraday vs. Maxwell and Longitudinal Wave Demonstration” – Professor **Konstantin Meyl**, Engineer, Author, Inventor of the Demo-Set, Professor at the University of Berlin

3:15 PM 4:15 PM

“Wireless Energy Through the Earth-Ionosphere Cavity” – Dr. **Elizabeth Rauscher,** Nuclear and Astrophysicist, Inventor of the ELF Earthquake Predictor and Triangulator.

4:15 PM 5:15 PM

“Masters of the Ionosphere HAARP Modifies the Polar Electrojet” – **BBC Video on Tesla Technology**, with Wiliam Terbo, demonstrating ionospheric excitation by radio waves.

6:30 PM 7:15 PM

Masters of the Ionosphere – BBC Video Presentation **repeated** for the Special Tesla Evening Event attendees

7:30 PM 8:30 PM

“The Wardenclyffe Dream: Tesla’s Plan for Wireless Worldwide Distribution” – **Dr. Marc Seifer** Professor, Author of the best-selling book *Wizard, The Life and Times of Nikola Tesla*, presents an illustrated historical account.

8:30 PM 9:00 PM

High Voltage Tesla Coil Demo – **High Voltage Device** with **Music**: The Tesla Tower wind ensemble composition by Prof. **Holland**, Skidmore College

Sunday November 9, 2003

Electrotherapeutic and Tesla History Day

9:30 AM – 10:30 AM

“A Family Perspective on the Personality of Nikola Tesla. Review of the Popular Interest in this Scientific Icon” with Q and A Session – **William Terbo**, Engineer, Closest living relative of Tesla (Grand-nephew). Founder and Director of the Tesla Memorial Society.

10:30 AM 11:30 AM

“The Search for Free Energy: Genius, Vision and Psychology of Invention” – **Keith Tutt**, British Writer and Author of the book *The Scientist, The Madman, The Thief and their Lightbulb* that includes Tesla.

11:30 AM 12:15 PM

“Electrotherapy with Tesla Coil Design: Intorduction to Bioelectromagnetics” – Dr. **Thomas Valone** Physicist, Professional Engineer, Author of the new book, Bioeletromagnetic Healing: A rational for its Use.

12:15 PM 1:00 PM

Exhibitors Presentations – **Brief Presentations by exhibitors** (5-10 minutes each)

2:00 PM-3:00 PM

“Emerging Opportunity: cancer Electromagnetic Frequency Therapy” – Dr. **Mark Neveu** President, the National Foundation for Alternative medicine.

3:00 PM 4:00 PM

“Turn of the Century Electrotherapy Discoveries” – **Jefrey Behay** Director, The Turn of the Century Electrotherapy Museum.

4:00 PM 5:00 PM

“How a Crushed Leg Helped Me Discover High Voltage Electromagnetic Healing Device” – **Ralph Suddath**, Third generation Tesla Electrotheraphy Inventor, radio Host, Entrepreneur.

5:00 PM 5:15 PM

Closing Remarks – **Thomas Valone** Program Coordinator

The Conference Report Compilation can be purchased from T. Valone, Integrity Research Institute.

“Nornikel” and Alternative Energy

“Norilsky Nikel”, the largest Russian non-ferrous metal producing company has announced the beginning of the cooperation with the Russian Academy of Science. Metallurgists are planning to invest into the development of the hydrogen energy and fuel cell R&D projects of the Russian Academy of Sciences. Accordingly, last week an agreement was signed. **Mikhail Prohorov**, the General Director of “Nornikel” said that they are ready to invest 20-40 million dollars annually into R&D projects of the Academy in this field.

“Expert” magazine, # 43, November 17-23, 2003

PERENDEV Magnetic Motor

Review

www.perendev.co.za/products/magnetic_motor/index.html

Shown below is a Magnetic Motor with Alternator (Patent Pending):



Fig.1

This is the "PerEnDev" (Perpetuum Energy Devices) company latest motor predicted to deliver some 60 kW. Motors can be built up to 4 mW.

Background of the Magnetic Motor

The Company started in 1969 with the development of a magnetic motor to drive an alternator to produce electricity. The concept was sound but the problem they faced was that the magnets that were available at the time (ferrite magnets) were not very powerful. The unit ran but had very little power and the project was abandoned.

In 1996 the "Perendev" company started to investigate the possibility of reviving the original idea, magnets had now come a long way and were very powerful (rare earth).

Fig. 2
Rare earth magnets

After the engineers successfully designed a new model, the company developed a 3 rotor system producing 6 kW, coupling this to an alternator through an 11:1 gearbox to produce electricity in 220volt and 380volt, single or 3 phase.



Fig.3

The units will be ideal for the small and large user, such as emergency, military, farms, plots, industrial and large users... in fact any application requiring power.

Key Benefits Foreseen:

- ♦ No fuel costs
- ♦ Constant running
- ♦ Reliable
- ♦ Cost Effective
- ♦ Portable (6kw-120Kw)

> Editor: In 2002 "Faraday Lab" got an offer from the company to buy their 6 kW generator for testing at the price of about $6,000. However, no contract was signed. The company is currently engaged in redesign of their motors and is looking for regional partners but they are not yet ready to produce on the line. In our issues we will try to inform the readers on their activities. Alexander V. Frolov

Internet Pages



Lutec 1000

Jasker Power System

Electric Radial Motor

industrial and large users... in fact any application requiring power.

Key Benefits Foreseen:

- ♦ No fuel costs
- ♦ Constant running
- ♦ Reliable
- ♦ Cost Effective
- ♦ Portable (6kw-120Kw)

Editor: In 2002 "Faraday Lab" got an offer from the company to buy their 6 kW generator for testing at the price of about $6,000. However, no contract was signed. The company is currently engaged in redesign of their motors and is looking for regional partners but they are not yet ready to produce on the line. In our issues we will try to inform the readers on their activities. Alexander V. Frolov

Internet Pages



Lutec 1000

Jasker Power System

Electric Radial Motor

18 Meter Perpetual Wheel



Minato Wheel, E. Vogel, Sweden



Generator from James W. German



Konzen
Pluse Motor



200-300 percent over-unity energy Space
Power Generator



Adams Motor, Robert Adams

The RotoVerter

94.0
WD-40
KELVIN 400

Bendini Pulse Motor



Motor based on Flynn Technology

Finsrud Device



The Muller Unit



Alte Olsen Generator

Vladimir Matveev's Electrical Generator

Entirely New Kind Of Generator Invented!

(1-26-2003) TASHKENT, Uzbekistan (UPI) – An Uzbek inventor said he has created a type of electrical generator that does not rely on the principle of electromagnetic induction – on which all existing generators are based.

The new generator employs a concept called **magnetic conductivity modulation** and it has potential applications in industry, communications, households and even the military, explained Vladimir Matveev, the inventor, a specialist in electronics.

Matveev said he is convinced he has created a fundamentally different machine.

"All electrical machines I know are based on the principle of interaction between the magnetic fluxes (lines of force) of their rotor (rotating member) and stator (portion that remains fixed)," he explained.

Such machines, Matveev said, are based on electromagnetic induction, a property of energy discovered by Michael Faraday, an English physicist and chemist, in the 19th century. The machines produce electrical current either by moving a conductor across a magnetic field or by regulating the flux of that field.

"My machine has a principal difference," Matveev told United Press International. "The magnetic field of its stator does not interact with the magnetic field of the rotor (because) its rotor is not a magnet – the rotor only changes the magnetic resistance of the stator," he said.

The stator in Matveev's generator contains a magnetic core with a permanent magnet and a detachable winding. A rotor with changeable magnetic resistance is placed at a cutoff point in the core's magnetic field. It is composed of alternating magnetic and air parts and can operate in either linear or rotary form.

When the rotor is set in motion, its alternating components pass through the magnetic core's cutoff point. When the magnetic part passes through the cutoff point its magnetic resistance decreases. When the air part passes through, its resistance increases.

This pulsing of resistance results in changing the magnetic conductivity of the magnetic core, which in turn produces an alternating electrical current in the core's winding. The frequency of the winding's current can be controlled by regulating the rotor's speed or by changing certain qualities of its magnetic or air parts. Also, the generator's electrical



The Muller Unit



Alte Olsen Generator

Vladimir Matveev's Electrical Generator

Entirely New Kind Of Generator Invented!

(1-26-2003) TASHKENT, Uzbekistan (UPI) – An Uzbek inventor said he has created a type of electrical generator that does not rely on the principle of electromagnetic induction – on which all existing generators are based.

The new generator employs a concept called **magnetic conductivity modulation** and it has potential applications in industry, communications, households and even the military, explained Vladimir Matveev, the inventor, a specialist in electronics.

Matveev said he is convinced he has created a fundamentally different machine.

"All electrical machines I know are based on the principle of interaction between the magnetic fluxes (lines of force) of their rotor (rotating member) and stator (portion that remains fixed)," he explained.

Such machines, Matveev said, are based on electromagnetic induction, a property of energy discovered by Michael Faraday, an English physicist and chemist, in the 19th century. The machines produce electrical current either by moving a conductor across a magnetic field or by regulating the flux of that field.

"My machine has a principal difference," Matveev told United Press International. "The magnetic field of its stator does not interact with the magnetic field of the rotor (because) its rotor is not a magnet – the rotor only changes the magnetic resistance of the stator," he said.

The stator in Matveev's generator contains a magnetic core with a permanent magnet and a detachable winding. A rotor with changeable magnetic resistance is placed at a cutoff point in the core's magnetic field. It is composed of alternating magnetic and air parts and can operate in either linear or rotary form.

When the rotor is set in motion, its alternating components pass through the magnetic core's cutoff point. When the magnetic part passes through the cutoff point its magnetic resistance decreases. When the air part passes through, its resistance increases.

This pulsing of resistance results in changing the magnetic conductivity of the magnetic core, which in turn produces an alternating electrical current in the core's winding. The frequency of the winding's current can be controlled by regulating the rotor's speed or by changing certain qualities of its magnetic or air parts. Also, the generator's electrical output – its voltage – can be controlled by changing the configuration of the rotor's components, Matveev explained.



Electrical machine assembly - FEDORO V F 1996.10.10 1996RU-119822 (1998.09.27) G01R 31/34, 31/02

Addnl.Data: VOROBEI V K MATVEEV V A

NOVELTY - Device has electrical machine, non-brush field exciter with diode rectifier, two dynamics double-winding transformers, which primary windings are located on rotor and secondary windings on stator. One end of primary winding of second transformer is connected to rotor housing; another end is connected to common point of conductor which is connected between capacitor and cathode of semiconductor diode, which other terminals are connected to direct current terminals of diode rectifier. Semiconductor diode is connected to cathode group of rectifier; capacitor is connected to anode group. Secondary windings of transformers are connected to actuating member through generator of signal, which is proportional to resistance of insulation in excitation winding circuit.

USE - Electric power production

Matveev said his generator is different from an invention by Howard Johnson of the United States. Johnson discovered how to build motors that can run without input of electricity or any other kind of external energy. He obtained a patent in 1973 for describing electrical generation using only the energy contained in the atoms of permanent magnets.

Matveev also said some Russian inventors have experimented with a generator similar to his. Their generator changes its magnetic conductivity by changing temperature. However, the machine requires a lot of time to be heated and cooled alternately and results in a current frequency much lower than what generally is used in industry. Moreover, the Russian generator requires high steel density and greater mass.

Matveev's machine generates electric energy of industrial frequency. Furthermore, he said his machine is simple, reliable and requires less steel and mass than conventional generators. It also can be adapted to flows of low speeds, such as weak water or wind streams. Matveev tested the generator in his former household in Kazakhstan before he patented it in Uzbekistan.

"I want to pass the invention on to all mankind," he said.

Boris Abdurakhmanov, director of the Uzbek Koinot (Cosmos) design office and head of the laboratory of semiconductors and photoelectricity of the Institute of Electronics of the Uzbek Academy of Sciences, told UPI: "Matveev has offered a fundamentally new approach to a problem of the creation of electric power generators."

Utilization of the Gravity Force in Power Engineering

Editor: In the previous issue we made a review of Mikhail Smeretchanski's invention "Perpetual motor with magnetic control elements" (# 4, 2003). This invention was patented; shown below are some pages from the patent itself. You can contact the author by e-mail: smeretchanski.mikhail@wanadoo.fr, or the postal address: 13 av. Rochambeau 3800 GRENOBLE FRANCE









PATENT



The Most Interesting Articles - 2003

In the year 2003 we have published more than 120 articles, mainly on the alternative energy, new propulsion principles and the development of ether dynamics.

"Cold fusion", low energy nuclear reactions (LENR) and highly-efficient electrolysis were represented by the works of Professor Kanarev, E. Storms, P. Hagelstein, T. Chubb and E. Cartlidge.

Almost every "New Energy" issue features articles on highly-efficient permanent magnet motor or generator experiments or patents of the kind. The articles by T. Valone, E. Vogel, A. Akau, T. Hardwood, A. Francouer and S. Abramov are of great value for engineers and researchers in this field.

The interesting articles by M. Filo, R. Koontz and V. Bogomolov reveal several principles of designing and building purely mechanical energy generating systems. All these systems possess one common feature: namely, the fact that a substance (a solid or fluid working mass) is accelerated in the gravitational field or in the centrifugal force field. The design characteristics of the system make it possible to obtain free energy.

We have published several articles by S. Gerasimov and his colleagues on the reaction-less propulsion device experiments. We hope that in the future we will keep in touch with these researchers.

The article by D. Reed on the new physics development concepts is worth mentioning too. The article by E. Sorokodum on new energy sources and the article by V. Chernobrov on the research into the active properties of time are of no less importance.

A. Egorov's article on the ball lightning makes it possible to form a number of experimental approaches to the problem of creation multi-purpose stable plasma objects.

Electrogravity questions, water-powered vehicles, longitudinal electromagnetic wave technologies, the Searl effect commercialization, capillary engines, resonance high-efficiency power-engineering, single-wire power lines, heat pumps and other similar research works were presented to our readers in the year 2003. We have minimized theoretical articles and we hope that the magazine has become more interesting and useful for the new energy practice development.

Alexander Frolov
St. Petersburg, Russia

There is interesting newsgroup of the site: http://www.overunity.com,
Stefan Hartmann, email: harti@harti.com

Stefan Hartmann writes: This is the answer I got from Finsrud; it seems that the film they have done about him will be shown [on Discovery Channel] in 2004 when [if] I interpret this norwegian text right...

Subject: Documentary Film
Reidar Finsrud,

Dear Sir,

The Australian Broadcasting Company together with The Discovery Channel, have funded my company to make a documentary film entitled 'A Machine To Die For', the story of Perpetual Motion and the search for 'Free Energy'.
I have read extensively about your Perpetual Motion sculpture and we would be interested in traveling from Australia to Norway in order to film this now famous piece of work. At the same time we would request an interview with yourself.
If you are in agreement with this it is our intention to be in Norway on the 10th and 11th of July 2003. This documentary will be released worldwide and should produce considerable interest in your Gallery.

Mark Eliot
Catherine Jarvis and Mark Eliot
Romany Mill Studios

Hydrogenics Secures $3 Million from Japan Auto Makers

Letter from RemyC remyc@prodigy.net
Contacts: investors@ hydrogenics.com

Hydrogenics Secures $3 Million in Test Equipment Orders Japanese Auto Makers Select Greenlight Power for Fuel Cell Testing Equipment

TORONTO, Sept. 30 – Hydrogenics Corporation (Nasdaq: HYGS; TSX: HYG), a developer and manufacturer of fuel cell products, announced today that its wholly owned subsidiary, Greenlight Power Technologies (Greenlight) has received orders totaling US $3 million for fuel cell test stations from two leading Asian automotive customers. Both are repeat orders for multiple machines.

Cumulatively, Greenlight is providing seven Fuel Cell Advanced Test Stations (FCATS) to two major customers. The first order is for three 3 kW PEM FCATS L-Series test systems. The second is for three 12 kW PEM FCATS H-Series test systems and one 60 kW PEM FCATS HX-Series testing station. The stations are expected to be delivered over the next two quarters.

"Our decision to open an office in Tokyo, Japan over three years ago continues to pay dividends," said Pierre Rivard, President and CEO of Hydrogenics. "The Japanese market is advancing quite aggressively towards the commercialization of fuel cell technology, as evidenced by our growth in test equipment sales to the region over the past three years. We are delighted to secure these major contracts with customers who are clearly setting the pace in fuel cell development."

Greenlight fuel cell testing systems provide high precision instrumentation, combined with full-featured software. They deliver fuel cell testing results that prove the reliability, repeatability and versatility required for world-leading fuel cell development programs.

About Hydrogenics Corporation

Hydrogenics Corporation (Nasdaq: HYGS; TSX: HYG) is a leading clean power generation company, engaged in the commercialization of fuel cell technology and test stations for fuel cells. The company is building a sustainable business, in a potentially "game changing technology" for transportation, stationary and portable power. Hydrogenics, based in Mississauga, Ontario, Canada, has operations in British Columbia, Canada, Japan, the United States and Germany. For more information, please visit www.hydrogenics.com .

About Greenlight Power Technologies, Inc.

Greenlight Power Technologies Inc. (http://www.greenlightpower.com), a wholly-owned subsidiary of Hydrogenics Corporation, is a leading global supplier of testing and diagnostic equipment to the fuel cell industry. It has supplied fuel cell test equipment to the world's premier fuel cell stack manufacturers, component manufacturers, system integrators and research organizations. Greenlight provides a full suite of test equipment for fuel cell stack, stack component, reformer and system testing for companies focused on portable, stationary, and transportation fuel cell applications.

Hydrogen Fuel Cells

Anuvu Incorporated

3980 Research Drive
Sacramento, CA 95838
USA
Tel: (916) 921-7040
Fax: (916) 921-7044
Email: anuvu@anuvu.com

www.anuvu.com/home.html

Now our readers can get familiar with some hydrogen fuel cell development photos. It is worth of a note that the prices are high for the majority of people. For example, a hydrogen fuel cell car costs 100 000 dollars FOB Sacramento, CA. The next picture features a fuel cell van, which costs 150 000 dollars.









EXCESSIVE OUTPUT BY MEANS OF AIR IONIZATION

We have received an interesting article from California. Here is the short version of the article.

The Mechanism of The Electric Spark

Review of the research
by Leonard B. Loeb
Professor of Physics, University of California at Berkeley
and
John M. Meek, Research Engineer
Stanford University Press, Stanford University, California

Dedicated to Professor J. S. Townsend whose pioneer research and theory laid the whole foundation for the study of the mechanism of the electrical spark discharge.

Although the electric spark has been known to mankind in its various manifestations from time immemorial, its mechanism has to date been little understood. The initial clarification of the mechanisms involved is due to J.S. Townsend as a result of his brilliant researches in the early nineteen hundreds. On the basis of his theory of ionization by collision by electrons and positive ions, the fundamental mechanisms active and especially the coefficients required in their application were made available.

In 1936 the present senior author was forced to describe the mechanism of spark discharge in terms of a modified but distinctly unsatisfactory Townsend theory. In 1935 the discovery of photo-ionization in air by corona discharge indicated a solution was not far off. The turning point of a more successful theory came in the discovery of streamers in positive point to plane corona in 1936. The quantitative analysis of the self-propagating positive streamer in all breakdown phenomena became clearly evident as a result of the data concerning electron avalanches. As a result a qualitative mechanism of sparking by streamer propagation from anode to cathode functioning by means of photo-ionization in the gas was established.

The Townsend Sparking Criteria

It will not be necessary here to derive the famous equation of Townsend for the current [i] in a gap between electrodes as a function of the photoelectric current [io] from the cathode, the gap length [x] and the coefficients [a] and [B]. For this the reader can go to any standard text. *(Editor: the equation is omitted)*

In this equation the first Townsend coefficient [a] represents the number of new electrons created in the gas by an initial electron in its advance of 1 cm along the field axis from the cathode.

The second Townsend coefficient [B] in Townsend's original theory was the number of new electrons created by a single positive ion in its advance of 1 cm along the field from the anode.

The quantity [a] has been extensively studied in various gases. It varies with the ratio of field strength to pressure, X/p, where [X] is in volts per centimeter and [p] is in millimeters of Hg.

Note: the reason we are going through this is to determine the actual increase in current provided by the spark gap, and thus be able to design the circuit to avoid blowing out semiconductor components. It also provides a sound and already proven scientific theory to work from giving us a good foundation and the confidence to proceed with technical design work.

The quantity [B] has been evaluated, albeit rather inaccurately, from the variations of [i] with [x] at various higher values of X/p, by many observers in different gases. Inasmuch as it has now been shown that there are numerous other mechanisms other than impact with positive ions, which can liberate the secondary electron, needed in discharge.

There has been an inclination to give up the mechanism of impact ionizations by positive ions in gas. The discovery of measurable photoelectric ionization in gas has now made it possible to explain such cases. The exact way in which photo-ionization in the gas could operate to cause a spark, was not clear until the development of the present **streamer theory**.

The Streamer Theory of Spark Discharge Anode Space-Charge Field Due to an Avalanche

Assume a spark gap of 1 cm in length. Assume that in air at atmospheric pressure the potential across the plates is 31,600 volts, which is the conventionally observed sparking potential [Vs].

Let us then calculate what happens in the field to one of those electrons. It starts across the gap, quickly acquiring an average random energy of some $E=1/2mC^2= 3.6$ electron volts and a drift velocity [v] in the field direction of about 1.5 to 2 times 10^7 centimeters per second. As it moves it creates new electrons at a rate of [a] per centimeters in the field direction so that in a distance [x] it and its progeny amount to e(ax) electrons, forming what is called an **electron avalanche**.

Therefore, e(ax) positive ions have been left behind by the electron group, virtually where they were formed in the 10^{-7} second of advance for the electrons in the distance x=q across the plates. As the electron avalanche advances, its tip is spreading laterally by the random diffusive movement of the electrons.From these data it is possible to compute the density of positive-ion space charge left behind at any point [x]. The value of [a] under these conditions is about 17, making e(aq)=e(17). The first ion pair is created at 0.0407 cm from the cathode. At 0.5 cm from the cathode there are 4914 ions, at 0.75 cm there are 3.66 times 10^5 ions, and within 0.0407 cm from the anode there are 1.2 times 10^7 ions. **Most electrons will be drawn to the anode except for some few that are bound by the positive ions, making a sort of a conducting discharge plasma in the avalanche.**

Such a distribution of ions does not make a conducting filament of charges across the gap, and hence in itself an avalanche that has crossed does not constitute a breakdown of the gap. Thus one must look further for the mechanism of the spark.

If Loeb and Meek are correct then if we assume a spark gap of 3 mm and a voltage of 5,000 voltsthere are roughly 2,000 electrons created by avalanche for every one electron leaving the cathode. They state that most of these 'free electrons' are absorbed by the anode. [This would certainly explain why the semiconductor components cannot handle the current gain.]

NOTE: Loeb and Meek make little reference to initial amperage. There are only two values they refer to 10^{-5} ampere and 10^{-12} ampere.

In conclusion: Sparks and Arcs are two different beasts. My initial research into the amperage necessary to form an arc does not apply to spark and the process of avalanche where this huge gain mechanism is possible.

Photoelectric Ionization in Gas as a Secondary Mechanism

Accompanying the cumulative ionization there is produced by electrons from four to ten times as many excited atoms and molecules. Some are excited to an energy exceeding the ionizing potential of some of the atoms and molecules present, either by excitation of an inner shell, by ionization and excitation, or in a **mixed gas like air by the excitation of molecules of higher ionizating potential, e.g., N2**. These excited atoms or molecules emit radiations of very short wave length in some 10^{-8} second. This short ultraviolet radiation is **highly absorbed** in the gas and leads to ionization of the gas. In fact, the whole gas and the cathode as well are subjected to a shower of photons of all energies traveling from the region of dense ionization with the velocity of light. Thus nearly instantaneously in the whole gap and from the cathode new photoelectrons are liberated which almost at once begin to ionize cumulatively.

The Mechanism of Positive Streamer Formation

The photoelectrons created at points in the gas and at the cathode at any great radial distance from the avalanche axis will merely create other avalanches. Those in the gas will be short and those coming from the cathode region will be long and like that of the initial avalanche. Being smaller and, in any case, later in creation than the parent avalanche, such avalanches will be of no interest in breakdown. However, those photoelectrons created near the space-charge channel of positive ions, and especially near the anode, will be in an enhanced field, which exerts a directive action drawing them into itself. If the space-charge field [X1] is in the order of magnitude of the imposed field [X], this action will be very effective. In addition the values of [a] will be much enhanced.

The electrons from the intense cumulative ionization of such photoelectron avalanches in the combined fields [X] and [X1] which are drawn into the positive space charge feed into it, making it a conducting PLASMA which starts at the anode. The added fields will be most effective along [X] and so will the ionization. The positive ions they leave behind will therefore extend the space charge towards the cathode. These electrons also create photons, which produce electrons to continue this process. **In this fashion the positive space charge develops toward the cathode from the anode as a self-propagating positive space-charge streamer.**

As the streamer advances towards the cathode it produces a filamentary region of intense space-charge distortion along a line parallel to the field. The conducting streamer of a plasma consisting of electrons and ions extending to the anode thus makes a very steep gradient at the cathode end of the streamer tip. As this advances toward the cathode the photoelectron avalanches produced by radiation at the cathode, especially at the intercept of the extended streamer axis at the cathode, it begins to produce an intense ionization near the cathode. Hence the positive ions created there may increase the secondary emission. Thus, as the space-charge streamer approaches the cathode a cathode spot is forming which may become a source of visible light.

When the streamer reaches the cathode there is a conducting filament bridging the gap. As the streamer tip reaches the cathode the high field produces a rush of electrons towards the end of the streamer. This if followed by a current of electrons, gives a high-potential wave, which passes up the preionized conducting channel to the anode, **multiplying the electrons present by a large factor**. The channel is thus rendered highly conducting. If the metal can emit a copious supply of electrons because of the formation of an efficient cathode spot, the current of electrons continues the channel maintaining its high conductivity and **ever increasing in it**. This current, unless limited by external resistance, will then develop into **an arc**. It is, however, the intense increase in ionization by the potential wave, which gives the highly conducting channel characterizing the spark.

Conclusion: According to Loeb and Meek there are three means by which a spark in open air will provide a very large current gain. If this is true, it should be fairly easy to prove with inexpensive and unsophisticated equipment. Once the actual amount of current gain has been determined for the design parameters of the spark gap, then the rest of the circuit can be designed for the increased current value.

Editor: It is worth of a note that the current gain by means of ionization was patented by Pavel N. Yablotchkov (the patent of France # 120684, October 11th 1887). Some two years ago one of our issues featured an article about him. We think it is worth being published again.

PATENT of 1877 by Pavel N. Yablotchkov

Alexander V. Frolov
Faraday Lab Ltd,
Lev Tolstoy St., 7 St. Petersburg, 197376 Russia
Tel: 7-812-380-3844

Pavel N. Yablotchkov was born in 1847 near Saratov, Russia. He graduated as a Military Engineer in 1866 and spent several years in the Russian Army.

In 1872 he came to Moscow and started his activities in electrotechnical field. Since 1875 he had been working in Paris with the famous Louis Breget and his first French patent # 110479 of November 29th, 1875 was dedicated to an electromagnetic transformer. Then he developed and patented a lighting system (the well-known Yablotchkov electrical candle). In 1876 he patented a new electromagnetic transformer for industrial purposes, France # 115793 of November 30th, 1876.

The most interesting patent claim on over-unity devices by Pavel N. Yablotchkov is known as France patent # 120684, October 11th, 1877, "The system of distribution and amplification of electrical currents by means of atmosphere electricity..." The patent describes special capacitors connected in series with the load to increase the output current by means of ionization. Experiments were conducted together with the well-known physicists such as Dr. Maskar, Dr. Varren-Delaru and others and **they confirmed the 200 % efficiency of the circuit**. Now we will try to explain the method.



Fig.1 features a schematic drawing taken from Yablotchkov's patent. The Leyden jar is an asymmetrical capacitor, i.e. it is different in principle from a two-plate flat capacitor. The inner electrode of the jar should be connected to a high-voltage source and in this case the changes of the potential have an effect on the potential changes on the external electrode. It does not work in the opposite case and if you connect a high-voltage source to the external electrode no potential changes will be detected on the inner electrode. Connection to the ground or to a special plate (which is covered with many needles to increase air ionization) is necessary to attract the maximum number of electrons to the plate surface or to return the maximum electrons from the plate surface when potential changes on the external electrode are produced by means of electrical induction in the Leyden jar.

In conclusion I should mention one more supposition of the secrets of the well-known Swiss M-L converter (Methernitha). The main elements of the design are Leyden jar capacitors, which have the external surface made of perforated metal.

The other known fact is that great ionization of air is observed when the converter is in operation. So, the electrostatic machine can produce pulses of a very high voltage (potential difference) but it cannot be used as a source of a powerful current. In order to increase the current in the circuit we should apply a certain method and Yablotchkov's technology seems to be appropriate. A large surface of the external electrode of the Leyden jar can be a good solution to the problem. Maximum strong ionization allows us to obtain the output current several times stronger than the weak current generated by the electrostatic machine.

SUBSCRIPTION 2004!

To subscribe for
New Energy Technologies
please visit our web site:

http://www.faraday.ru/net.htm

One-year subscription
price for 2004 is $46.00

World-wide airmail delivery
included.

In 2004 we will publish
5,000 copies, 4 times per year.
Each printed issue will include
100 pages of printed information.
Alongside the English version
there is the Russian version
available.

CD "New Energy Technologies"

Back issues of 2001 - 2003 are
available on a CD with PDF files.
The price is $26.00.
You can order a CD from the same
web page:
http://www.faraday.ru/net.htm

Contact information for additional requests:

Faraday Lab Ltd,
New Energy Technologies magazine,
Lev Tolstoy Str. 7 -601,
St.Petersburg,
197376, Russia.
Tel/fax 7-812-3803844

TeslaTech, Inc.

296 E Donna Dr, Queen Valley, AZ 85218

Visit our site!.... http://www.teslatech.info

Benefits

- 1 yr *ExtraOrdinary Technology* (qtly)
- Mail Order Discounts
- Conference Fee Discounts

ExtraOrdinary Technology... our magazine containing news about *the leading edge of our Scientific Revolution*.

...an invaluable resource to track leading edge research!!!


EXTRAORDINARY TECHNOLOGY
N. TESLA.
APPARATUS FOR PRODUCING OZONE.
Patented Sept. 22, 1896.
NIKOLA TESLA'S MOST AMAZING PIERCE-ARROW CAR PROJECT OF 1931 IN BUFFALO, NY!
AIR PURIFICATION USING TESLA'S IONIZER AND OZONATOR!
THE HOTEL NEW YORKER... TESLA'S FINAL RESIDENCE!
The official magazine of TeslaTech, Inc.
www.teslatech.info
TeslaTech

ExtraOrdinary Technology focuses on:

Tesla Technology
Low temperature plasma
Electrogravitation
Electrified water
Magnetic healing
Electromedicine
New Health Supplements
...and much, much more!

JOIN TODAY!
(520) 463-1994

Annual Membership Rates: $30 - United States • $35-Can/Mex · $55-Else

Advanced Energy • Alternative Medicine • Future Technology

Konstantin Meyl

Scalar waves



From an extended vortex and field theory
to a technical, biological and historical use
of longitudinal waves.

Edition belonging to the lecture and seminar
„Electromagnetic Environmental Compatibility"

Preface to the lecture, 1st Edition 1996

The theme encloses the electromagnetic compatibility of both technical and biological systems. Only part of the electromagnetic wave can be considered for function troubles, namely the part that was absorbed and has rolled up to a vortex. The activity depends on the number of created vortices and of their lifetime, their decay.
The eddy current only manifests in conducting materials. In the air and in dielectric materials on the other hand the vortex of the electric field will form, also called the potential vortex. To calculate and to measure this vortex is our goal.

First we'll carry out a survey of the problems and the usual methods. From the analysis of unsolved problems the need for the introduction of the new vortex phenomena is deducted and an adequate field-theoretical approach will be chosen. Afterwards the potential vortices are calculated and their properties are discussed and interpreted. For the purpose of proving their existence, on the one hand the Schrodinger equation will be derived and on the other hand the quantum properties of the most important elementary particles will be calculated and compared with the well-known measured values. Measurement and calculation are in excellent agreement for weight, charge, magnetic moment and spin. So the theory not only proofs it's correctness, in addition it demonstrates it can achieve much more. The theory takes us to the unification of the well-known interactions and physical phenomena and shows itself as an unified theory. In the practical conversion and usage of the theory there will not only be informed but by all means also be provoked as an entrance in a fruitfully discussion. Fundamental questions will be taken up like: What is information, energy, temperature or smell? The connection to the theme of the electromagnetic environmental compatibility is formed by the technical and the biological usage of the potential vortices, the energy transmission of Nikola Tesla exactly like the in a similar way functioning nerve conduction. Here we already can expect biological reactions.

This lecture, held for the first time in the winter semester of 1995/96, is available in book form, as an edition belonging to the lecture. This lecture will not deliver ready recipes or instructions. The goal is reached when the critical sense of the listeners and readers has been inspired and discussions have been set going. Everybody has to draw the consequences out of such a theory by him- or herself.
In addition to this lecture a seminar is offered, wherein several themes are supplemented or deepened, different theories are compared and possible consequences are discussed. The appearance of an edition belonging to the seminar has started in 1998<i>. Regarding the conversion of consequences both politicians and scientists are equally addressed, because the electromagnetic environmental compatibility has developed to one of the most urgent problems of today's world. But in last consequence all of us bury the worldwide responsibility for our environment.

<i>: K. Meyl: Electromagnetic environmental compatibility, Part 2 and 3 of this book, Edition belonging to the seminar.

Table of contents
Page

Preface to the Lecture. 1st Edition 1996 III

Table of contents IV

Part 1 edition belonging to lecture "Electromagnetic environmental compatibility"

1. Introduction 1
1.1 Discussion about limits 3
1.2 Wireless telephones 5
1.3 Absorption of waves 7
1.4 Overlap effect 9

2. Tasks 11
2.1 Tasks of the electromagnetic environmental compatibility 11
2.2 Tasks of the electromagnetic compatibility (EMC) 13
2.3 Declaration of conformity 15
2.4 EMC-techniques to measure the emission of interference 17
2.5 Electro smog 19
2.6 EMC-techniques to measure the stability against interference 21
2.7 Tasks of the biological compatibility 23
2.8 Natural fields 25
2.9 Electricity of the air 27
2.10 Biological effects 29
2.11 Artificial fields 33
2.12 Protection against artificial fields 35
2.13 Unsolved tasks 37

3. Approach 39
3.1 Principle of causality 41
3.2 Field-theoretical approach 43
3.3 Duality 45
3.4 Flow vortices 47
3.5 Rankine vortex 49
3.6 Vortices and anti-vortices 51

4. Properties 53
4.1 Concentration effect 53
4.2 Duality of the vortex properties 55
4.3 Derivation of the electron as an elementary vortex 57
4.4 Quanta as field vortices 59
4.5 The photon 61
4.6 Pair creation 63
4.7 Noise 65
4.8 Condenser losses 67
4.9 Vortex lines and vortex streets 69

Page

4.10 Water colloids as vortex balls 71
4.11 Transport phenomenon 73

5. Derivation and interpretation 75
5.1 Fundamental field equation 77
5.2 Mathematical interpretation 79
5.3 Physical interpretation 81
5.4 Phenomenological interpretation 83
5.5 Atomistic interpretation 85
5.6 Derivation of the Klein-Gordon equation 87
5.7 Derivation of the time dependent Schrodinger equation 89
5.8 Derivation of the time independent Schrodinger equation 91
5.9 Interpretation of the Schrodinger equation 93

6. Theory of objectivity 95
6.1 Proof 95
6.2 Law of conservation of energy 97
6.3 Radius of the electron 99
6.4 Maxwell's field equations 101
6.5 Transformation equations 103
6.6 Field overlap 105
6.7 Field dependent curvature of space 107
6.8 Electromagnetic interaction 109
6.9 Gravitation 111
6.10 Field dependent speed of light 113
6.11 Universality 115
6.12 Aether 117
6.13 Spin and tunnel effect 119
6.14 Interpretation of the measured faster than light speed 121
6.15 Definition of the speed of light 123
6.16 Relativity and objectivity 125
6.17 Transformation 127
6.18 Transformation table 129
6.19 Interpretation of the transformation table 131
6.20 Particle decay 133

7. Proof 135
7.1 Elementary vortices 137
7.2 Matter and anti-matter 139
7.3 Positronium 141
7.4 Dipole moment 143
7.5 Myon 145
7.6 Calculation of the vortex fields 147
7.7 Calculation of the proton 149
7.8 Strong interaction 151
7.9 Magnetic moment of the proton 151

Page

7.10 Structure of the neutron 153
7.11 Calculation of the neutron 155
7.12 beta-decay 157
7.13 "Weak interaction" 159
7.14 Tau particle 161
7.15 Pions 163
7.16 Table of vortices of the Mesons 165
7.17 Table of vortices of the Baryons 167

8. Unified theory 169
8.1 Structure ofthe field theory 171
8.2 Unification of the interactions 173
8.3 Temperature 175
8.4 Heat 177
8.5 Sound 179
8.6 Basic principle of cybernetics 181
8.7 Structure of adaptive regulatory circuits 183
8.8 Information 185
8.9 Philosophy of nature 187

9. Usage 189
9.1 Longitudinal electromagnetic waves 191
9.2 Medical technical usage 193
9.3 Flying objects 195
9.4 Electro gravitation? 197
9.5 Free energy? 199
9.6 Nerve conduction and action potential 201
9.7 Wireless energy transmission technology 203
9.8 Measuring and switching technique of Nikola Tesla 205
9.9 Energy technical usage 207
9.10 Environmental compatibility 209
9.11 Ecologically fairusage 211
9.12 Claims concerning the environmental compatibility 213
9.13 Epilogue belonging to the lecture (part 1) 215
Abstract belonging to scalar waves, part 1 218

Page

Part 2, edition belonging to the energy technical seminar 219

10.0 Preface to the seminar, part 2 220
10. Oscillating interaction 221
10.1 Kepler's laws 221
10.2 Unknown interaction 223
10.3 Harmony of the alternating current engineers 225
10.4 Four fundamental interactions 227
10.5 Resonating interaction 229

11. The growing globe 231
11.1 Long-distance effect of the neutrinos 231
11.2 Model of expansion 233
11.3 Ancient Egyptian legend of Genesis 235
11.4 Inner structure of the earth 237
11.5 Earth's core as a converter of neutrinos 239
11.6 Speed of growth 241
11.7 Conservation of angular momentum 243
11.8 Set of difficulties concerning the change of magnetization 245
11.9 The weakly damped moon..247
11.10 Calculation of celestial mechanics 249
11.11 The biblical age 251

12. New cosmology 253
12.1 Concerning the formation of our solar system 253
12.2 The birth of the planets 255
12.3 The derivation of the Titius-Bode law 257
12.4 The hollow planet 259
12.5 Concerning the formation of the universe 261
12.6 Counter examples concerning the 2nd law of thermodynamics 263
12.7 Entropy destroying potential vortices 265

13. Recording of space and time 267
13.1 The measuring technical debacle 269
13.2 The clock paradox 271
13.3 The Tamarack mines experiment 273
13.4 Field dependent linear measure 275
13.5 Experiences from space travel 277
13.6 Spherical aberration 279
13.7 Step by step understanding of the measuring technique 281
13.8 Discussion of the cosmological insights 283

14. The way towards free energy 285
14.1 The liberalization of the energy markets 285

Page

14.2 The consequences of the liberalization 287
14.3 The chances of the wind energy 289
14.4 The chances of being self-sufficient concerning energy 289
14.5 The space energy technology of nature 291
14.6 The gap in the energy balance of man....293
14.7 Carl Freiherr von Reichenbach 293
14.8 Cold fusion and Genesis 295
14.9 Photosynthesis 297
14.10 How nature materializes 299
14.11 Lightning 301
14.12 Ball-lightning....303
14.13 Discussion concerning the neutrino conversion....305

15. Principle of funtioning of space energy 307
15.1 The course of the field lines 307
15.2 Gravitation....309
15.3 Systematizing the interactions 311
15.4 Magnetic force converter....313
15.5 The railgun 315
15.6 Unipolar induction....317
15.7 Tendency to instability 319
15.8 Unipolar field configuration 321
15.9 The Testatika 323
15.10 The secret of the Testatika....325
15.11 The key to free energy....327

16. Space energy technology (SET).... 329
16.1 The unipolar generator 329
16.2 Derivation of Maxwell's field equations.... 331
16.3 SET-devices with rotating magnetic fields....333
16.4 Commentary concerning magnetic SET-devices.... 335
16.5 RQM and the space quanta manipulator....337
16.6 SET-devices with pulsed magnetic fields....339
16.7 SET-devices with Mobius winding 341
16.8 Mobius converter of Seike and Coler 343
16.9 Tesla's flat coil 345
16.10 The secret of the flat coil 347
16.11 Discussion concerning the technology of the neutrino collectors 349

17. Technical use of the weak interaction __ 351
17.1 Radioactivity caused by neutrinos.... 351
17.2 Nikola Tesla, the discoverer of the neutrino radiation 353
17.3 Transmutation and reduction of radioactivity 355
17.4 The Patterson Power Cell 357
17.5 Report concerning the cold fusion.... 359
17.6 Water-Fuel-Cell technology 361
17.7 Unconventional electrolysis 363

Page

17.8 Materialization of neutrinos 365
17.9 Oscillation of size and luminescence 367
17.10 Phosphorescence and sonoluminescence 369
17.11 Discussion concerning the use of the weak interaction 371

18. Physical phenomena 373
18.1 Water as a catalytic converter for neutrinos 373
18.2 Background and zero point radiation 375
18.3 The Casimir effect 377
18.4 Effects under high tension 379
18.5 Flying discs 381
18.6 Propulsion with neutrinos 383
18.7 Antigravitation or levitation 385
18.8 Discussion concerning the effect of closed field lines 387
18.9 Concerning the determination of the stand of today's energy technique 389

19. Own experiments 391
19.1 Concerning the rating of experimental physics 391
19.2 The charge amplifier from the workshop of handicrafts 393
19.3 Interpretation of the observations with the charge amplifier 395
19.4 High-tension experiments in the laboratory for performance electronics 397
19.5 Measurement of dielectric capacitor losses in the HF laboratory 399
19.6 Analysis of the measured capacitor losses 401
19.7 Microwave oven for testing in the laboratory of electrical engineering 401
19.8 Microwave heating by decay of vortices 403
19.9 The Tesla coil from the workshop of handicrafts 405
19.10 Biological effectiveness of the Tesla coil 407
19.11 Wrestling for measuring technical insight in the Transfer Centre 409
19.12 Neutrinolysis, the alternative splitting of water 411

20. Cosmic experiments 413
20.1 Millions of voluntary test subjects at 11 August 1999 413
20.2 Model of calculation for the cosmic experiment 415
20.3 Physical technical consequences 417
20.4 Biological consequences 419
20.5 Epilogue to 11 August 1999 421
20.6 Dropping of the neutrino radiation 423
20.7 Analysis and comparison of the occurrences 425
20.8 Radioactive decontamination with the help of a supernova 427
20.9 Free energy from the Orion constellation 429
20.10 Interaction of the neutrinos with the core of the earth 431
20.11 Changing of polarity and apocalypse 433
20.12 Scalar wave gauges for the prediction of earthquakes 435
20.13 Calculation of future occurrences 437
20.14 Epilogue belonging to the energy technical seminar (part 2) 439
Abstract belonging to scalar waves, part 2 442

Page

Part 3, edition belonging to the information technical seminar 443

21.0 Prefaces to the seminar, part 3 444
21. Derivation of the scalar wave 447
21.1 Lord Kelvin in a delicate mission 449
21.2 Helmholtzian ring-like vortices in the aether 451
21.3 Taking apart of the wave equation 453
21.4 Derivation of the scalar wave equation 455
21.5 Derivation of a plasma wave 457
21.6 Mistakes of the HF technology 459
21.7 Coupling of the wave parts 461
21.8 Set of difficulties of the near-field 463
21.9 Transition to the far-field 465
21.10 Scalar wave model 467
21.11 Double-frequent oscillation of size 469
21.12 Electric and magnetic scalar wave 471

22. Properties of scalar waves 473
22.1 Wave-particle compromise 473
22.2 Concerning the measurement of light 475
22.3 Comparison of the parts of Tesla and Hertz 477
22.4 Noise, a scalar wave phenomenon 479
22.5 Neutrino radiation 481
22.6 Parallel instead of serial image transmission...483
22.7 Comparison of the properties 485

23. Research of scalar waves 487
23.1 Frequency diagram 487
23.2 The reverse of the HF medal 489
23.3 Radiesthesia 491
23.4 Prediction of earthquakes with the help of scalar waves....................................493
23.5 Searching water with the help of scalar waves 495
23.6 Receiving scalar waves with the Lecher antenna...497
23.7 Assignment according to wavelength 499

24. Medicine of oscillation 501
24.1 Mediation of information with the help of scalar waves 501
24.2 Systems with positive feedback 503
24.2.1 The Synchrometer..503
24.2.2 The sound therapy 503
24.2.3 The colour therapy 505
24.2.4 The aromatherapy 505
24.2.5 The gem therapy 505
24.2.6 Meditation and self-therapy..505

Page
24.3 Systems with negative feedback.. 507
24.3.1 The homeopathy 507
24.3.2 The bioresonance 507
24.3.3 The frequency therapy 509
24.4 The Zapper 511
24.5 Discussion concerning the medicine of oscillation 513

25. Contributions to the discussion concerning the information technical use 515
25.1 Window of the sensuous perception.. 515
25.2 The sense organs (nose, eye, tongue) 517
25.3 The nerve conduction 519
25.4 The brain, a scalar wave computer 521
25.5 Concerning signal engineering 523
25.6 Stability against interference and repair mechanisms 525
25.7 The microwave window.. 527
25.8 Discussion concerning scalar wave medicine 529

26. Recapitulation from the viewpoint of textbook physics 531
26.1 Common misinterpretation of the antenna losses... 531
26.2 Wave damping by field vortices 533
26.3 Laplace versus Maxwell 535
26.4 Error term in the wave equation 537
26.5 Interim result...539
26.6 Failure of the Maxwell theory 541
26.7 Concerning the evidence situation 543

27. Faraday versus Maxwell 545
27.1 Energy out of the field..545
27.2 Vortex and anti-vortex..547
27.3 Vortices in the microcosm and macrocosm 549
27.4 Faraday's law and Maxwell's formulation..551
27.5 The discovery of Faraday 553
27.6 Different formulation of the law of induction 555
27.7 Contradictory opinions in textbooks 557
27.8 The field-theoretical approach 559
27.9 Derivation of Maxwell's field equations 559
27.10 Derivation of the potential vortices 563
27.11 Derivation of the fundamental field equation" 565
27.12 The Maxwell field as a derived special case 567
27.13 Derivation of the wave equation 569
27.14 The new field approach in synopsis 571

28. Objectivity versus relativity 573
28.1 The question concerning the aether.. 573
28.2 Vortices, an overlap of the overlap... 575
28.3 Field overlap.. 577

Page
28.4 The derivation of the length contraction 579
28.5 The dependence of the Lorentz contraction on the field 581
28.6 Boscovich and the respiration of the Earth 583
28.7 Derivation of the gravitation 585
28.8 From subjectivity to objectivity 587
28.9 The objective standpoint 589

29 Mathematical gleanings 591
29.1 General and special theory of relativity 591
29.2 Transformation table 593
29.3 Discussion concerning the root of Lorentz 595
29.4 Mathematical derivation of the neutrino 597
29.5 Universal constants and constants of nature 599
29.6 The fundamental number e 601
29.7 The pentacle 603
29.8 The vortex, which is rolling up 605
29.9 The Golden Proportion 607

30. Scalar wave technology in antiquity 609
30.1 Thesis 609
30.2 Prerequisites 611
30.3 Approach 613
30.4 Circumstantial evidence 615
30.5 Radio technical concepts 617
30.6 Wireless telegraphy 619
30.7 AM temple technology 621
30.8 Modulation of acoustic signals 623
30.9 Broadband FM broadcasting technology 625

30.10 Epilogue 627

Contacting address and information 634

Table of formula symbols 635

References 636
A: Publications concerning the theory of objectivity (primary literature) 637
B: Publications about the theory of objectivity (secondary literature) 641
C: Literature concerning physics in general 643
D: Literature concerning geophysics, geology, geography and astronomy 644
E: Literature concerning the EMC and biological compatibility 644
F: Literature concerning Tesla and criticism of textbook physics 644
G: Literature concerning free energy 645
H: Literature concerning medicine, biology and chemistry 646
J: Literature concerning history and more peripheral subjects 646

Appendix 647

1. Introduction

Here the extremely controversially discussed question of the environmental compatibility of electromagnetic fields will be persuaded. Limits should inform what is incompatible and what is compatible. But there are as many limits as there are commissions and specialists. And besides that differ the results from each other for several powers of ten. In course of time the legitimate doubts become unmistakable and the representatives of science slowly get to feel the burden of proof.

For the sake of efficiency, the actual discussion concerning the theme of electro-smog is analysed and the necessity to involve an until now unnoticed field phenomenon in the discussion about limits is derived: It concerns vortices of the electric field. These potential vortices, as they are called, have the corresponding properties to show biological effects even at the lowest field strengths. In any case it is not possible to exclude that at present the wrong physical phenomena are measured and made responsible.

A parable should bring clarity.

Lets imagine that the to us well-known and over our sense of touch understandable physical phenomenon of the temperature is unknown to us, neither measurable nor perceptible. Our weather station only exists of a barometer that could show us the air pressure and deliver us indications if good or bad weather is to be feared. We ready realize that there exists a connection between the air pressure and our health and make the to us well-known phenomenon responsible. When the pointer points to good weather we can go out lightly dressed. With bad weather we should take a coat, so we know from experience.

"Now we imagine the realistic situation that in winter we have a weather situation of high pressure but it's stone-cold outside. The weather station will display high temperatures with the result that some people will walk around with short-sleeved and open shirt, only to lie in bed with a cold in the evening. Of course the air pressure was to blame! Logically the "pressure sensitive", as they are called mocking, demand the limits for the allowed pressure to be reduced so far that no consequences for health are to be feared. Concerning the theme of allowed limits, science is asked and science proceeds in a systematic way: the pressure is investigated in the laboratory, isolated from all other parameters and so it is discovered that man catches no cold even at a substantially higher air pressure, so there is no reason to alter the limits.

Actually we would expect these at any time reproducible results to have a calming effect on the minds of the participants of the discussion and on the population. Instead the pressure sensitives time and again cite new knowledge that won't fit in the scheme. So is for instance stated that draught causes the same health problems although this pseudo effect has nothing at all to do with the air pressure. So owing to incomprehensibility and emotions the discussion about limits becomes a farce.

The fact that sensitive people react to effects of air electricity and possibly get ill without proof that some today measurable physical quantities are responsible should make us think. It is little calming watching our scientists poking at the dense fog whereas at the same time among the runners of the new telecommunication networks there spreads something like a gold-digger mood.

To introduce a new technology is not difficult, but to abolish it for reasons of the electromagnetic environmental compatibility is almost impossible!



Fig. 1.1: Discussion about limits

■ Limits for professional exposition (electronics engineers) and
▨ Limits for non-professional exposition (population in general)
according to the Recommendation of IRPA/INIRC<ii>.
▒ Limits according to VDE 0848 / 1989
▓ Limits according to VDE 0848 / 1992
⊛ experimentally determined threshold values of reactions of biological systems <i>:

1 Increase of the activity of movement of birds
2 deflection of divining-rods
3 influence on the time of reaction of men
4 conditional reflexes of fish without electrical organs
5 conditional reflexes of fish with electrical organs
6 conditional muscular reflexes of men

taken from:
<i>: H.L. Konig: Unsichtbare Umwelt (Wetterfuhligk.), 5. Aufl., Bild 111, S. 123 Verlag Moos & Partner Munchen, ISBN 3-89164-O58-7
<ii>: Habiger u.a., EMV, Verlag Technik, Berlin 1992, S. 152

1.1 Discussion about limits

Whoever follows the public discussions concerning electro smog always sees two arguing parties, whose standpoints lie so far apart that they inevitably talk at cross purposes and there can be found no consensus.

On one side the "affected" find together who maintain to have found the electromagnetic radiation as the damaging cause for their problems. They are to be taken serious, even when only their personal sensitivity serves as means of measurement and proof and a more or less distinct sensitivity against electromagnetic phenomena. This group occasionally finds support of homeopaths who can base on reproducible laboratory results that fit as few into the view of life of science as the empirical statements of affected and possibly hurt people.

On the other side stand the representatives of the energy-supply companies and the runners of radio networks who argue with the needs of our modern industrial society and give "limits" prescribed to them by scientists. These, for their part, proceed according to strictly scientific methods. Their presented results are reproducible and there's no doubt about them.

The limits after all are fixed far below those that are recommended from a scientific viewpoint. Nevertheless both groups are separated from consensus by powers of ten. When we want to know how deep the ditch is we want to bridge, we should take a look at the determined limits (Fig. 1.1).

The limits stem from the 1RPA (International Radiation Protection Association) an organ of the World Health Organization that in turn has appointed the INIRC (International Non Ionizing Radiation Committee). These now state to have used all available scientific research results as basis for the given guidelines.

Moreover a safety range was worked into them. So the limits were fixed at substantially lower levels to guarantee that no health damage arises. In this way first the limits were determined for the people who for reasons of profession are exposed to electromagnetic fields.

For the population in general the limits for the so called non-professional exposition were reduced further to one half till one fifth for reasons of caution and care. In Fig. 1.1 these limits are registered. Thereby is distinguished between magnetic fields and electric fields that appear stationary or at extremely low frequencies (ELF describes frequencies between 1 Hz and 100 Hz). Moreover limits for low-frequency (1-10 kHz) and high-frequency (1-10 MHz) alternating electromagnetic fields are given.

The graph should serve as a rough orientation and show us the proportion of scale. As further information some thresholds of measured reactions of biological systems are registered (after Konig*[1]*). Because a logarithmic scale was chosen to fit all the values on one graph it becomes clear that between the first reactions and the recommended limits there lie up to five powers often. The ditch seems to be insurmountable.

Fig. 1.2: Set of problems of environmental compatibility by means of the example of the handheld wireless telephones (handy).

<i>: L.v.Klitzing: Neurophysiologische Einflusse durch elektromagnetische Felder wahrend und nach der Exposition, Med. Universitat zu Lubeck

1.2 Wireless telephones

Measuring technical surveys with regard to the influence of brain currents by digital radio signals by the university hospital in Lubeck have startled handy manufacturers and users equally <i>. Although in this case measurement errors could be detected, the „bugaboo on the wall" remains that we are sitting unsuspecting in a restaurant and a neighbour draws his handy out of his pocket to make a digital telephone call. Thereby synchronizing the brain currents within a radius of 100 meters on the broadcasting signal and occupying our brain useless with technical signals. The derivation will show that from the start this can't happen to all visitors, because as a prerequisite conditions of resonance must be fulfilled. But would there be an affected, he or she for sure would have considerable problems, because informations that are not picked up over the sense organs can neither be classified timely nor as regards content.

An affected whose brain has picked up technical signals not even is able to register by itself that it was fed with incorrect informations. It would be reasonable when the visitors of the restaurant would defend themselves and put the radio operator on the doorstep. The number of restaurants where apart from cats and dogs also handy's have to stay outside is increasing. How should we keep out of the way of electromagnetic fields? Should we walk around permanently with a steel helmet or even better in a knight's armour and even go to bed with them? It would be worse than in the dark middle ages.

Summarizing: it should be guaranteed that the operation of electro technical apparatus causes neither health damage nor unintentional influence or irritation. A systematic and scientific procedure should investigate in the laboratory all relevant physical phenomena individually for their interaction. Electro physics bases on two phenomena in connexion with electro-smog: on the one hand the radiation and on the other hand the thermal effect, but at a close look both factors prove to be of only little importance!

In radiation measurements the intensity of the electromagnetic wave at a certain place is determined. In laboratory experiments the field strength is increased so long till biological reactions are observed. Thermal limits are determined in a similar way. As said, the values lie about powers of ten above those that possibly bother you when you hold a handy to your ear. It is true that the microwave radiation penetrates into your head but we also know that it marches out again on the other side and this visit in your head happens with the speed of light.

Exactly like this are guest in your body constantly your local radio station, your local television station the satellites with hundreds of programs and anyway the whole radio technical world even when you did not invite them.

For an electromagnetic wave to become receivable, the field strength must lie clearly above the common noise signal and this can only be achieved by a permanent overlap, by standing waves, like in a cavity tuned to a specific frequency or an antenna. As long as people don't let themselves grow antennas on their heads they hardly have to fear direct biological effects of electromagnetic waves.

That leaves as the second phenomenon the thermal effect. With a handy held to your cheek there comes into being a local fever in your head. But that is not at all unusual or unnatural for the human body. Something like that happens to a far greater degree when you take a hot foot bath or let yourself be irradiated at one side from the sun at a tourist grill.


Power of waves:
irradiated
stored
(absorbed)
radiated
P_e
ΔP
P_a
local fever:
$\Delta\vartheta = f(\Delta P)$
absorbed power:
$\Delta P = P_e - P_a$
effectiveness:
$\eta = P_a/P_e$

Fig. 1.3: Damping of waves and ability to absorb of a body
(our head) if we are making a phone call with a handy.

a contribution to the theme dielectric losses

- capacitor
- high-frequency welding
- microwave oven

<i>: K. Meyl: Potentialwirbel Band 1 [Al] (only in German),
INDEL Verlag, Villingen-Schwenningen 1990, ISBN 3-9802 542-1-6

<ii>: K. Meyl: Potentialwirbel Band 2 [A2] (out of print),
INDEL Verlag, Villingen-Schwenningen 1992, ISBN 3-9802 542-2-4

1.3 Absorption of waves

The with the theme dealing physicians logically have to put up with criticism that they work only with two phenomena that not at all can be involved authoritative in the causes for biological effects. A third factor can be considered, a field phenomenon until now stayed unnoticed by science: the vortex of the electric field, the so called potential vortex. A vortex is to be considered as an oscillation around a fixed point. Through that a permanent overlap is caused, like what happens at an antenna only that the vortex is not bound to the dimension of an antenna. The potential vortex is contracting and in this way reaches extremely high energy densities at very little spatial measurement, densities that lie far above those that field strength measurements are pretending to us [Al]<i:>.

When again you take the handy at hand with which you ,,blow" the pulsed microwaves into your head. Don't worry, because with the speed of light and without provable damage almost everything comes out again on the other side, but only almost everything. A little damping of the wave has taken place and your head has absorbed this part of the irradiated wave (Fig. 1.3). Who claims this is already the thermal factor actually should realize that there exists no corresponding term in the wave equation. Here there are found merely two dual vortex phenomena as a possible damping term: the eddy current and the potential vortex. An eddy current damping is ruled out because of the bad conductivity of the head. But this favours his dual anti-vortex, the potential vortex [A1]<i>.

Seen physically the following is taking place in your head: the absorbed waves roll themselves up to vortices and through that become localized and overlap themselves permanently (Fig. 1.4b). In the course of time the vortices decay and produce the well-known eddy losses that lead to the measurable increase in temperature. When reactions or biological effects arise, simply and solely the vortex can be considered as the possible cause. Thereby play two points an important role: the number of the generated vortices and their lifetime that is determined by the time of decay.

In anticipation of the mathematical calculation of the potential vortices it is pointed out here that these are favoured not only by a low conductivity, but also by a high dielectricity. Because water has an unusual high dielectricity ($\varepsilon_r = 80$) and our head consists predominantly of water doubts in dealing with handy's are reasonable.

Also the relaxation time constant representative for the lifetime can be calculated [A2]<ii>. We must proceed from the assumption that both the number of the vortices and their lifetime, that is all the at a fixed point in time in our head existing and effective vortices, can be a cause and therefore have to be considered and investigated scientifically.


a) standing wave
electro-
magnetic
wave (λ_1, f_1)
amplifier
for f_1

b) localized vortex = noise


electro-
magnetic
wave (λ_1, f_1)
$\lambda_1 > \lambda_2$
$f_1 < f_2$
($\lambda \cdot f = c$)
Vortex centre
(λ_2, f_2)

c) broadband antenna for EMC-measurements


λ_2
λ_1

Fig. 1.4: Measurement of localized waves and vortices

1.4 Overlap effect

The graph at the left (Fig. 1.4) should clarify once more that only the in space localized and permanently overlapping field appearances can be considered as a cause for biological effects. This can concern an over an antenna standing wave (a) or a vortex (b) which is to be taken as localized by nature.

It would be allowed to in general speak only of a vortex because the standing wave can by all means be understood as a special case of the vortex. The essential difference is that the vortex is not bound to the size of a fixed antenna and can contract itself at any time to achieve in this way a substantial higher energy density. As a result this than will lead to an increased biological effectiveness.

It should be pointed at a further omission. In the discussion about limits, without exception, the absolute field strength of the broadcasting signal is valued and not the type of modulation. The last mentioned should actually not at all play a role according to the prevailing scientific opinion.

Totally different is the case with a vortex that acts damping. Such a vortex shows near it's centre a considerable smaller wavelength than more to the outside and through that it has a big frequency bandwidth [A5]<i>. It is to be expected that in the extremely broadband pulsed signals of the digital networks the creation of vortices (or eddies) will be favoured considerably stronger than in amplitude- or frequency-modulated signals (AM/FM/C-network). In connexion with analog modulated radio- or handy-signals until now there never has been reported of any synchronization of the brain currents with handy-signals from a comparison of the EEG with the broadcasting signal.

Interestingly the for EMC-measurements usual stepped broadband antennas have exactly the construction that certainly would be favourable to the measuring technical registration of vortex phenomena (Fig. 1.4c).

With the dipole antennas of different lengths for different wavelengths there still are measured waves and not vortices but these measuring techniques is certainly accommodating to the until now unnoticed and stayed undiscovered vortex phenomenon. So there are some good reasons that the vortex is a dominating influential factor for EMC-problems.

By means of the example of the handheld wireless telephones can be studied and discussed with which set of problems the very young discipline of science of the environmental compatibility has to fight in the future. And in which ways there can be found approaches towards a solution of the problem. When the comfortable and trodden out ways of textbook physics do not lead to the goal than we will have to force our own way through the jungle of science.

At first we'll have to obtain a short overview of the actual level of research and knowledge. From the criticism to this we than can derive the tasks of the electromagnetic environmental compatibility and in particular the unsolved tasks.

<i>: K. Meyl: Wirbel des elektrischen Feldes, eine neue Storquelle? EMC Journal 1/95, 6. J, S. 56-59.



is the ability of a biological/technical system <i>,

- to fulfil a certain function (task of operation)
- under given conditions of usage (aspect of compatibility: irradiated interference radiation)
- *during its life / time of use (aspect of reliability)* stressing its environment and other systems/objects which exist in it by electromagnetic interferences (aspect of compatibility: emitted interference radiation)
- endangering such systems/objects (protection of health and safety at work)
- or even threatening them (case of damage).

EC
environmental compatibility
EMC
(electromagnetic compatibility)
BC
(biological compatibility)
artificial sources of interference
natural sources of interference
technical device
biological systems

Regulations of the German Post Office since 1992: EMC-law<ii> from 1996: EU -regulation	called EMEC thirties: radio operator disease today, E-Smog, HF-, SW-therapy diathermy, etc.	know how of druids magic esoteric medicine biology

Fig. 2.1: Overview concerning environmental compatibility

<i>: E. Habiger: EMV-ubergreifende Aspekte zu benachbarten Problemfeldern, Elektrie 48 (1994), Heft 5/6, Seite 163-161

<ii>: EMVG: Gesetz uber die elektromagnetische Vertraglichkeit von Geraten, Bundesgesetzblatt Teil I vom 9.11.1992, S. 1864

2. Tasks

2.1 Tasks of the electromagnetic environmental compatibility

The environmental compatibility (EC) forms the generalization that includes both the electromagnetic compatibility (EMC) and the biological compatibility (BC). Besides the technical and functional goals of an undisturbed functional course it also pursues ethical and moral goals.
Technology should benefit to humanity and at the same time be in accord with nature. This goal will not be reached when this technology directly or indirectly is endangering humanity.
A direct attack on the health of people poses for instance the military usage of technical apparatus or the negligent usage, by pretended ignorance and unsuspicion.
Is a technology posing a danger to the environment so humanity endangers itself indirectly with this technology. After all are human beings a product of their environment. We always should reckon on the environmental sins taking revenge on us sooner or later.

In fig. 2.1 a formal definition is given that in particular concerns the claims for an undisturbed functional course: it concerns the compatibility aspects of unallowed emitted and irradiated interference radiations, the reliability and quality safety with which a function and task is fulfilled and finally the questions of the protection of health and the safety at work.

Moreover fig. 2.1 provides an overview and the structure of the 2nd chapter. First we'll treat the electromagnetic compatibility (EMC) that first of all deals with the influence of artificial but also natural interference sources on technical apparatus.
After that we'll throw a glance at the appearing fields in nature. The biological compatibility (BC) deals with the influence on biological systems.
An especially sensitive area of the environmental compatibility (EC) than describes the with a cross-link hinted influence of artificial interference sources on biological systems that is popularly described as „electro smog".

The numerous aspects of the environmental compatibility for instance in the areas of chemistry and biology that certainly are important, but do not fall in the area of electromagnetism, can't be treated in the here marked framework.



Fig. 2.2: Classes of limits according to VDE 0871 (since 1-1-96: VDE 0875)<i>

<i>: Anton Kohling: Grundlagen der Funkentstorung in der Bundesrepublik Deutschland, etz Bd. 108 (1987), Heft 10.

2.2 Tasks of the electromagnetic compatibility (EMC)

First of all the EMC (electromagnetic compatibility) is concerned with the function of technical apparatus. Correspondingly rational and dry sounds the official definition: "electromagnetic compatibility (EMC) describes the ability of an electrical setting-up (i.e. of a construction element, of a construction group, of an apparatus or of an installation) to function in an electromagnetic environment without stressing this environment by electromagnetic effects in an unallowed fashion ".

Actually it concerns an old need for protection that should be as old as the usage of electro technical apparatus. But in the beginning no one cared about it. The spark gaps with which Heinrich Hertz 1888 in Karlsruhe has carried out the first radio technical experiments were genuine „polluters", that would have been detectible at several hundreds of kilometres distance with modern receivers. For these installations that he had assembled in the lecture room with his students, today he would hardly get a permission of operation and the since 1996 required declaration of conformity he would get not at all.

1925, as in Germany the number of radio listeners had exceeded the limit of one million, for the first time a need for protection appears in the certificate of approval for radio receivers: "The public telegraphs and telephone installations must not be disturbed by the radio receiver".
Later on every backside of the good old steam radios there was found the following hint (translated): "This apparatus meets the interference radiation regulations of the German Post Office". So the manufacturers were urged to measure the emission of their apparatus and in particular to screen the HF-oscillators in the superhet-receivers.

Since the fifties, in the VDE-institute EMC-examinations in the present day sense are taken. The main point of the measurements and the by the VDE recommended limits, however is about interferences bound to a circuit. On the supply lines of the network the prevailing conditions are reproducible so that standards can be put through (Fig. 2.2).

For measurements of interference radiation maybe the time was not ripe enough or the necessity was not big enough. The usual argumentation was: what we can't measure reproducibly, can not be forbidden and certainly not be put under punishment. Therefore merely recommendations were issued or impositions weak as wax were made like: "the interference field strength ... must be so small that an undisturbed reception is guaranteed as soon as the minimum field strength for utilization exists at the place where the antenna is mounted"<i>.

In common parlance that means something like: "as long as no one bleats, everything is allowed". Within a connected industrial area there even existed an officially legitimized fools freedom. Merely at the fence of the industrial area limits had to be fulfilled.

Specially for the line-frequency of the screen one has decided to build a loophole in the law so that one didn't have to throw the TV sets, that so successfully had conquered the living rooms, out of the window. Of course the flickering screens did interfere exactly as before but this EMC-interference now was officially approved.


EMC-Law
specifications:
(basic-, generic-product-standards):
household, business,...
industry
stability against interference:
DIN EN 50082-1
DIN EN 50082-2
against emission of interference:
DIN EN 50081-1
DIN EN 50081-2
test procedure:
stability against interference:
and
against emission of interference:
DIN EN 61000-4
(IEC 1000-4, resp. IEC 801)
DIN EN 550..
DIN EN 60555
document:
EU- declaration of conformity

Fig. 2.3: The way to EU conformity

2.3 Declaration of conformity

In the EMC times seem to have gone as the standardizers had to fit in with the insufficiencies of technology. Meanwhile the conditions have turned up. We owe this circumstance first of all the EMC-law of 1992 that doesn't name any limits but it states the political intention to demand from technical apparatus and installations an appropriate stability against interference and at the same time limit the sent out interference. As a consequence of this law the measurement facilities and measurement processes had to be standardized to get reproducible measurement results that are not influenced by the electromagnetic environment. That goes so far that even the floor covering of a measurement hall is dictated because the conductivity of the floor influences the degree of reflexion. Normally the examinee is situated on a revolving plate that is turned around for 360° during the measurement of the radio interference field strength. Is it however not possible to turn the examinee than the antenna has to be led around it, thereby again increasing the dimensions of the measurement hall. The distance to the antenna should be up to 10 meters. Moreover it must be possible to move the antenna, up till a height of 4 meters to register the influence of the reflexions on the floor.

Moreover there is to plan a reflexion free zone around the measurement track (in elliptical form) that depends on the reachable damping of reflexions of the used absorber. Used are pyramids of foam material soaked with carbon and increasingly tiles of ferrite or shieldings of wallpaper.

Taken all together for a measurement hall doing justice to standards there result considerable measurements of for instance 18 m length x 10 m width x 7 m height. Let's again come to talk about the EMC-law with which only the intention but not the way is fixed. To form the claims catalogue in a way that is fulfillable in general, some concrete prescriptions, the so called standards, have to be worked out. This task was transferred to the European committee for electro technical standardization CENELEC, which has established the workgroup TC 110 to at first work out some standards: The basic standards deal independent of product with general questions of the EMC, of the testing process and of the measurement environment.

The generic standards likewise deal independent of product with the so called fundamental technical standards for apparatus in their dependence of the respective electromagnetic environment (protected computer room or medical room, environment of the house, office or industry).

The product standards concern the EMC-standards referring to products (7 product families / approx. 50 products).

In Fig. 2.3 the arduous way through the jungle of paragraphs for a technical apparatus is outlined. Corresponding to the requirements of use, first the relating ES-standards for the apparatus have to be determined and than have to be measured according to own test standards based on the fundamental technical standards. When the allowed limits for stability against interference and for sending out interferences are not exceeded, the EC-declaration of conformity is handed out. Since 1.1.96 that declaration is needed when apparatus are commercialized or - stated more exactly - "put in circulation" and operated. When still further EC-guidelines are met in the end the CE-hallmark is awarded. Since 1.1.96 only with this hallmark the access to the common market of the EC is possible. Violations can be punished with fines and if need be with imprisonment. But there are great national differences in the EC. The Federal Republic of Germany with fines of up to 50.000 Euro counts as expensive for criminals.

Simulation of network for the measurement of the interference voltages U_{st1} and U_{st2}.


simulation of network
L
N
PE
C_k
$I_{s\,t2}$
$I_{s\,t1}$
C_K
Z_N
Z_N
U_{st1}
U_{st2}
low-pass
output of interference voltage
test object
impedance Z_n of the simulation of networks for industry networks in the range of 0.15 to 30 MHz
1 Ω
5 μH
50 Ω

Fig. 2.4: Simulation of network for the measurement of interference voltages.<i>

<i>: acc. to Ernst Habiger: EMV, Huthig Buch Verlag Heidelberg (1992), ISBN 3-7785-2092-X

2.4 EMC-techniques to measure the emission of interference

Actually we already can be glad that it came to an europe-wide agreement for the regulation of the EMC-set of problems. But the question if we can be satisfied with what we have reached is still outstanding. All too often the lowest common denominator of the measurable and checkable was sought and not so much the technical possible was taken into consideration.

The main emphasis is put on the measurement of the emission of interferences. Traditionally the interferences bound to a circuit are registered in a frequency range up to 30 MHz. The corresponding wavelengths thereby can correspond with the length of the supply lines and form standing interference waves. Primarily the spectrum of the interference currents is measured e.g. over a HF-current converter. These currents produce a voltage drop over the internal resistance of the feeding network. Because the properties of the networks can vary very strong, a standardized end-resistor is required for the measurement of the interference voltage. For this purpose an imitation of the network is switched between the network and the examinee. This imitation in addition has the task to keep away the interference signals that come from the supplying network with the help of filter-elements (Fig. 2.4).
The measurement of the interference radiation, the field-bound interference emission, lakes place between 30 MHz and 1 GHz. For that a free field or an absorber-hall with little or no reflexions is required. The standardized distances of measurement are 3, 10 and 30 meters. The electric field strength is determined with dipole broadband antennas, the magnetic field strength with frame antennas. It must be possible to both vary the receiving antenna between horizontal and vertical polarization and to adjust the receiving antenna in the height and the position to the test object.

Typical measurement set up to measure the emission of interferences bound to a conductor<i>

A:	shielded link conductor
B:	bundle of conductors folded like a meander
C:	connection to the reference mass
ME:	receiver of interference signal
NNB:	Simulation of network
PO:	test object


reference mass with a large surface
B
C
40 cm
PO
NNB
ME
80 cm
A
> 80 cm

Fig. 2.5: Measurement set up to measure the emission of interferences bound to a conductor,<i>

<i>: Ernst Habiger: EMV, Huthig Buch Verlag Heidelberg (1992), ISBN 3-7785-2092-X

2.5 Electro-Smog

There is almost no end to the possibilities of variation and one needs already a lot of overview and experience to determine the field strength maximum. Nevertheless we have to ask ourselves if in this way really all emissions of interference are understandable, that popularly are described as „electro smog".

Smog is the combination of the terms Smoke and Fog. It therefore describes a pressure on the environment with fog like smoke. When for instance in the case of smog alarm all interference sources are switched off, which means all kilns are brought to a stop and all automobiles are stopped, than the fog like smoke therefore still is not vanished from the air. It just distributes itself and dissolves only very slowly.

The transfer of the smog idea on the electromagnetic interference radiation is bound to fail because, when the test object is switched off no emission of interference at all is detectable with the usual measurement means. Nevertheless the rainbow-press is trying to enumerate almost all electromagnetic field phenomena under the term „electro smog" without consideration of the fact that this term is not at all a collection term. From the sight of an expert one can only speak of smog when something like smog remains and stays active further after the switching off of an electro technical apparatus. It should be a phenomenon that is not understandable by the standardized measurements of interference radiation. Such a phenomenon would be e.g. the vortex of the electric field. However vortices are virtually not measurable in a direct way because they have the unpleasant property to whirl about around the measurement probe. But they will be detectable by their eddy losses and in the case of the electric field vortex appear as noise. Until now the standardizer however haven't planned to investigate the influence of an apparatus on the noise in the environment. Here we still grope in the dark.

At least the vortex shows a storing property that would justify the use of the idea "smog". We'll have to investigate the phenomenon.


filter
input network
Test object
L
50 µH
0,1 µF
PE
0,1 µF
50 µH
N
input:
symmetrical
unsymmetrical
asymmetrical
test generator

Fig. 2.6: Picking up of interference voltages in network lines.<i>

<i>: Ernst Habiger: EMV, Huthig Buch Verlag Heidelberg (1992), ISBN 3-7785-2092-X

2.6 EMC-techniques to measure the stability against interference

The question is: what kind and what intensity of an electromagnetic interference can an apparatus cope with without limiting it regarding its technical function. For that test generators are used and with their help interference signals are produced in the test object. Fig. 2.6 shows the possibilities of a symmetrical, of an unsymmetrical and of an asymmetrical production of interference voltage signals in the power supply lines of an examinee. Over and above that the testing possibilities and testing methods are numerous. In principle the following processes are used:

1. The simulation and production of interference factors typical for the network like harmonic waves on network voltages, overlapping signal voltages, changes of network voltage, decrease of network voltage, network interruptions, network unsymmetries and network frequency changes.
2. The production of both energy-poorer and energy-richer interference impulses like they can form in energy-networks by switching acts or by the effect of lightning (burst).
3. The simulation of the course of events when static electricity discharges.
4. Low-frequency magnetic fields like those that can form by network frequency operating and loading currents or by short-circuit and lightning currents in the form of a pulse.
5. The stability against interference against the influence of an electromagnetic field also called radio interference firmness. For this purpose high-frequency generators and broadband antennas are used to expose the examinee to electromagnetic fields in a frequency range between 10 kHz and 18 GHz. At the moment tests are only performed between 27 and 500 MHz. The modulation of the carrier wave should be possible to be able to imitate the interferences by radio technology as realistic as possible. Thereby the field strength values can by all means reach up to several 100 V/m.

In accordance with expectation the result of this irradiation with an outside field is that every conduction path and every wire can act as an antenna and therefore can produce high-frequency currents and measurable potentials. Building parts of the analog technology as a consequence battle with problems of drift whereas with digital logic parts and computer parts the danger exists that switching states change unintentionally. Let us remember again the overlap effect of fig. 1.4. The electromagnetic wave itself marches with the speed of light through the examinee. When a small part of the wave finds an object that it can use as an antenna than the localized overlap comes into play. This than as a cause is responsible for the effective and measurable antenna currents. Until here the text books help us to explain the problems that happen and to remove them logically.

However time and again cases are reported where textbook physics can't help us any further. Spectacular cases even came to court like e.g. the ABS (Antilock Braking System) of a truck that had failed due to EMC-interference radiation. As a consequence the brakes had failed. When after that the local radiation pollution is measured no anomaly at all can be discovered. The measurable field strength is not higher as is usual in the whole area. Maybe you also have made the experience that often the causes can't be found when your computer suddenly "crashes" out of the blue.

Here the mentioned vortex of the electric field is capable to deliver plausible explanations because it is not bound to the geometry of an antenna and in addition is highly active without being detectable with the usual EMC measurement methods of the interference radiation measurement!



Fig. 2.7: Intensities of natural electromagnetic fields
(electric, magnetic and electromagnetic fields) ▒

In addition to fig. 1.1, page 3,
magnetic field in Gauss (= 10^{-4} T),
electric field in V/m.

<i>: A.S. Presman: Electromagnetic Fields and Life. Plenum Press, New York - London, 1970

2.7 Tasks of the biological compatibility

The second leg of the environmental compatibility (EC) forms the biological compatibility (BC) besides the electromagnetic environmental compatibility. Whereas the interests of the EMC are looked after by electrotechnical engineers and electrophysicists, with the BC also doctors, biologists and architects are addressed.
Moreover this leg is already very old and already existed long before artificial interference sources could be created by mankind. The interaction between the arising interference sources in nature and the biological systems in general and specially men always interested the doctors, the priests, the druids and geomants, that not seldom looked after several functions in personal union equally. Unfortunately they as a rule have kept their knowledge and capabilities as secret knowledge, didn't make any recordings and merely initiated and trained their respective successors. Through that a great deal got lost and today non-medical practitioners, homeopaths and esoterics trouble themselves to take up to the far-reaching buried knowledge.
Because this concerns pure knowledge by experience, often the with the topic occupied persons themselves are not capable to say anything about the physical backgrounds and causes. One concentrates entirely on the under certain circumstances reachable results and only in rare cases on reproducable effects. In some areas the scientific assignment already has succeeded, have parascientific phenomena managed their admission in the so called "exact sciences", but in most experience disciplines the assignment is still due. There still is a lot to do here.

In the time as there not yet were operated any artificial interference sources on our planet, the senses of man naturally were a whole lot sharper for his electromagnetic environment as today. Today, where there scarcely is a place on earth where we are not irradiated by terrestrial transmitters, by satellites or by the netfrequency that is measurable everywhere. In the bluntness of our senses perhaps the hybris of modern man is founded, with which he wants to rise himself above esotericism, geomancy and other sciences of experience and thereby dispute the electric and magnetic fields their biological effectiveness.

The fields of natural origin form an electromagnetic environment for men, that they have adapted to and that they probably need for a life in accord with nature. The evolution has taken care for a corresponding adaptation.
In fig. 2.7 in addition to the limits from fig. 1.1 the intensities of natural electromagnetic fields are registered<i>. They lie clearly lower as the recommended limits but exactly in the area wherein the first reactions of living beings are observable.

When we ask us how much electromagnetism is good for us and how much harms us so the obvious answer is: exactly as much radiation as nature dictates in the fluctuations between day and night, between the months, years and in the end between the cycles of sunspots of 11 years. Here the guide value is found that man and nature have adapted themselves to. In fig. 2.7 the corresponding area between the natural minimum and maximum values is given.

Irradiation strengths of the field radiation in the biosphere and how the optical windows are situated in the atmosphere<i>.



Fig. 2.8: Absorption dependent on frequency in the atmosphere

---

<i>: entnommen aus: H.L. Konig: Unsichtbare Umwelt (Wetterfuhligk.), 5. Aufl., Bild 8, Seite 14, Verl. Moos & Partner Milnchen, ISBN 3-89164-058-7

2.8 Natural fields

Our electromagnetic environment has something to offer:
From the magnetic north pole to the magnetic south pole of the earth run the field lines of the earth's magnetic field that we are exposed to. With a compass we use the vector character of the magnetic field to fix our position. The induction averaged over time is approx. 50 uT. But it is overlapped by short-time fluctuations caused by geomagnetic storms in the ionosphere.

These storms again are caused by the eddy currents and the currents of charged particles that come from the sun. At the same time these eddy currents in the ionosphere together with the earth's magnetic field form a protective shield with a excellent screening effect for us inhabitants of earth.
In several layers like for instance the ozone and Heaviside layers a filtering and damping until the complete suppression of the very broad cosmic spectrum is caused. This extraterrestrial spectrum of radiation doesn't leave a single frequency out and has a lethal intensity for us.

Only for a little window in the frequency spectrum, radiation can pass almost undamped, as can be seen in fig. 2.8: the light with the spectrum of the colors. For this nature has donated man a sense organ so that man can protect himself against too high dose values. After all, who will look voluntarily into the sun? We only get into trouble when our sense organ doesn't function any more (for instance in the fringe range of the visible spectrum, the UV-range).

For other frequencies of electromagnetic radiation man neither has a sense organ but that doesn't mean that he is not influenced by these. Here, as in the UV-range he only indirectly notices that he has got too high a dose when he has to discover some influences on his well-being and his health. Without the help of neutral measurement apparatus he himself by no means is in a position to make a connection between an excessive exposition to radiation and his health problems.

When natural field strengths should be used as a measure for technical limits, so there should be paid attention to the fact that nature doesn't know intense continuous irradiation. The values are subject to powerful fluctuations that leave men and nature the chance to regenerate.
The television stations not even think it is necessary to reduce their broadcasting power after the end of broadcasts and further sprinkle the sleeping population with test signals, with senseless pictures of going by underground or nonstop program advertisements.
People need the intermissions. That again shows how good nature means it with us.



Fig. 2.9: Spectrum of frequency of one lightning, measured field strength at a distance of 1.6 km from the place of origin. See Watt and Maxwell:<i,ii>

---

from:
<i>: H.L. Konig: Unsichtbare Umwelt (Wetterfuhligk.), 5.Aufl., Bild 38, Seite 27, Verl. Moos & Partner Munchen, ISBN 3-89164-058-7, see <ii>.

2.9 Electricity of the air

The electrostatic field strength of the earth lies between 50 and 500 V/m. That is a whole lot considering that voltages off 60 Volts can be lethal for man. But a living person distorts the terrestrial E-field for reason of his own field and his electric conductivity, so that there exists no danger for him as long as he doesn't grow into the sky.

Maybe the dinosaurs had to become extinct because they were to big and for instance the E-field near the ground had risen with a jump by a meteorite that brought a high charge from the cosmos. That would explain why the smaller living beings could survive the natural disaster.

Also the thunderstorm electricity can become life-threatening. Burns, heart and brain failures are the most common consequences. After all the probability to be struck by lightning is four times higher as to have six right ones in the lottery.
Over the lightning channel of approx. 1 meter in diameter charges between 10 and 200 C are transported what results in current strengths of 2000 up to 200,000 A. The main discharge lasts between 10 and 50 usec. With the preceding and all the following discharges it lasts over a second.
Field strengths on the scale of 4,000 V/m are typical but in a distance of 5 km these wear off to 8 V/m. The frequency spectrum of a lightning reaches 4 powers of ten into the range of the radio waves. In fig. 2.9 is shown the field strength measured in a distance of 1.6 km from the place of origin<i,ii>.

The origin of lightnings is still an unsolved problem after the well-known models (Wilson) arc not in a position to explain the reason for the origin of the potential difference of more than 100 million Volts required for the ionization of the air. Also the lightnings that struck in the direction of the ionosphere still are mysterious. We'll have to come back to this<iii>.

<i>: H.L. Konig: Unsichtbare Umwelt (Wetterfuhligkeit), 5. Aufl., Bild 38, Seite 27, Verlag Moos & Partner Munchen, ISBN 3-89164-058-7, according to <ii>.

<ii>: A. D. Watt and E. L. Maxwell: Characterisic of Atmospheric Noise from 1 to 100 Kc/s. Symposium on the Propagation of VLF Waves, Boulder, Col., Paper 35, Jan. 1957.

<iii>: see Part 1, chapter 5.4 and part 2, chapter 14.11.



Fig. 2.10 A: Effect of a static magnetic field of 100 kA/m (0,12 Tesla) on the root (I) and on the plant (II) of barley seeds.
plants in the magnetic field: dotted line
plants for checking: drawn line
according to Novitskii[iii]

<iii>: Novitskii, Yu.I.: Effects of a magnetic field on the dry seeds of some cereals. Proceedings of Conference on the Effect of Magnetic Fields on Biological Objects, Moscow, p. 52, 1966.
Taken from: H.L. Konig: Unsichtbare Umwelt (Wetterfuhligkeit), 5. Aufl., Bild 72, S. 73, Verlag Moos & Partner Munchen, ISBN 3-89164-058-7

2.10 Biological effects

The in fig. 2.1 indicated connection between the EMC and the BC, by some authors inofficially described as EMC-environment (EMCE), describes the effect of artificial fields on biological systems. This concerns the sensitive range of tasks that is discussed extremely controversially in the public. The problem thereby is that the artificially produced field strengths lie above the natural field strengths for several scales. In the thirties first reports about troubles were provided by navy radio operators that complained about headache, dizzyness, concentration failure and indisposition. Besides these negative reports concerning the so called "radio operator disease" at the same time medical usages concerning high-frequency therapy were tested. In the beginning this diathermy called healing method still was a short wave irradiation. Today it is extended into the microwave range and uses the thermal effect of electromagnetic rays. The increased temperature of the tissue causes an increased local blood flow. This supports healing processes, loosens cramped muscles and can help in case of rheumatic fever. The advantage of the HF-irradiation compared to contact heat by a hot-water bottle or by infrared rays is the higher penetration depth. Herein short waves are superior to microwaves. But microwaves can be better focussed on a certain part of the body. Is the temperature further increased, so the tissue is damaged. This is used for the treatment of cancer and is called hyperthermy. Because cancer cells as a rule are flowed with blood worse than healthy cells, they are more sensitive to heat and therefore are faster destroyed than healthy cells at a correspondingly increased temperature. In this way for Instance in the USA cattle with a so called cancer eye are treated. For that the spot suffering from cancer is irradiated with 2MHz-waves for 30 seconds with a handheld apparatus of 10 Watts broadcasting power. The rate of succes is given to be 90%! The method of hyperthermy has not yet been able to establish in the area of the medicine for humans. Also at our college corresponding research work is carried out in co-operation with the radiological clinic of the university of Freiburg (Germany)<i>.

The thermal effects of high-frequency fields are therefore well-known and subject of scientific research. On the other hand and in spite of numerous publications, non-thermal effects even today are denied by some scientists as non-existent<ii>. Here only a few counter-examples will be listed.

Fig. 2.10 A shows the effect of a static magnetic field of 0.12 Tesla on the root (1) and on thc plant (II) of barley seeds. The readable effect is an acceleration of the growth of the treated seeds (dotted line) compared to the plants for checking (drawn line)<iii>.

<i>: H. Schulz, W. Oppitz: Lokale Hyperthermie durch hochfrequente Wirbelstrome, Medizin Technik 1, 1987.

<ii>: G. Nimtz: Mikrowellen, Einfuhrung in Theorie und Anwendung. 2. Aufl., BI-Wissenschaftsverlag 1990, ISBN 3-411-03203-0

<iii>: Novitskii, Yu.I.: Effects of a magnetic field on the dry seeds of some cereals. Proceedings of Conference on the Effect of Magnetic Fields on Biological Objects, Moscow, p. 52, 1966; taken from: H.L. Konig: Unsichtbare Umwelt, fig.72, p. 73, Verlag Moos & Partner Munchen, ISBN 3-89164-058-7



Fig. 2.10 B: Measured increase in the production (K) of colicin by colibacteria as a microwave effect

a) as a function of the wavelength,
b) as a function of the intensity of the microwaves,

according to Keilmann[i].

---

taken from:

[i]: H. L. Konig: Unsichtbare Umwelt (Wetterfuhligkeit), 5. Aufl., Bild 106, S. 111. Verlag Moos & Partner Munchen, ISBN 3-89164-058-7

A static field naturally produces no induction and hence no heating will arise. In the case of alternating fields the thermal effect in experiments is excluded by working with cxtremly low stimulations. The example after fig. 2.10 B shows the measured increase in the production (K) of colicin by colibacteria at only 0.01 mW/cm^2 microwave power<i>.

In addition the example provides the interesting information that obviously only a certain frequency and it's harmonic waves increase the production, other frequencies on the other hand remain inactive. Because only minimal field strengths are used it more likely concerns an information-technical as an energetic effect (curve a). This statement is supported by the observation that an increase of the intensity not at all necessarily as a consequence also increases the production (curve b). What the colibakteria need is obviously neither energy nor heat but only a certain frequency that stimulates the colicin production or the growth.

Should it really be confirmed that biological effects of electric and magnetic fields can be produced by certain frequencies and can't happen by an energy transition so the discussions about limits must seem ample meaningless.

Maybe the one or the other in thought already draws a connection to the acceleration, the acclerated growth of kids, which is observed world-wide and stronger in cities than in the country. It started for approx. 100 years simultaneous with the electrification of the homes in the towns. In Asia the acceleration and also the electrification have started later. Other growth stimulating effects like radio waves, X-ray examinations, atomic tests and provable also the nourishment with vitamin B6 happened only until much later and at the most could support the actual effect.

But how should a proof be offered when anyway the field strength not at all can have a decisive influence on the growth of man after the statement of fig. 2.10 B? Which information is authorative? Where lies the responsible frequency window? Does the information actually manifest as frequency? Is the authorative influential factor also in this case not at all noticed and measured?

A lot of pressing questions are still outstanding. But in any case the numerous influential factors detected in experiments do not at all let themselves reduce to a sole factor, for instance the nourishment. For a family doctor it may be comfortable to be able to give an easy explanation: „Cause is the nourishment!" With such a reductionism on the other hand the actual cause stays in the dark and the asked questions in this way won't let themselves be answered.



Fig. 2. 11: ____ profile of the 50-Hz-field on the ground at 380kV/1kA in each circuit.<i>
a) electric field,
b) magnetic field.

____ taken from: ________________________________

<i>: E. Habiger u. a.: Elektromagnetische Vertraglichkeit, fig. 7.3, page 147 and Fig. 7.1, page 146, 2nd Ed., 1992. Berlin, Miinchen: Verlag Technik.

2.11 Artificial fields

The scepticism of people feeling close to nature is especially directed against artificial fields that man can't see nor hear nor smell. Objects of doubt are first of all the installations for the creation, distribution and conversion of electric energy.

An essential role plays the fact how close the supplying and the draining conductors are to each other, so that the respective fields can compensate each other. The worst solution one can think of is realized at the electrified railway. Here the rails and the earth are used as the draining conductor for the current while there exists an ample large distance to the supplying conductor. A compensation is almost impossible thus causing gigantic interference fields that are detectable even at a distance of 10 kilometers. The increased putting on of railway engines feeded by rectified current is likely to aggravate the set of problems because the non-sinusoidal absorption of current is strongly afflicted with harmonic waves.
With high tension transmission lines (fig. 2.11) the interference field strength is reduced when the three cables are suspended with only little distance between them. But even the selected phase order can play a role. Of course the optimal compensation effect is guaranteed with cables in the earth. But these are expensive and technically not realizable for such high voltage levels.

In the eighties also the computer screens got in the headlines. The terminals are furnished with a cathode ray tube and have a very broad radiation spectrum that already starts at 0 Hz. Here already static maximum values of 64 kV/m are measured<i>!

I'requency range	Measured maximum values E_{max} resp. H_{max}	30 cm in front of the screen
static field (0 Hz)	64 kV/m	
30 Hz. 60 Hz	10 V/m and	
	0.2 - 1 A/m	
5 Hz - 1 kHz	1800 V/m and	10 V/m and
	4 A/m	0,6 A/m
50 Hz - 0,5 MHz	1 A/m	
15 kHz-220 kHz	50 V/m and	15 V/m and
	1.1 A/m	0,17 A/m
3 MHz -300 MHz	< 0,2 V/m	

Fig. 2.11: Electromagnetic fields from screens<i>

system about	used frequency	measured value
radio broadcasting station (MW 2O kW)	6OO kHz	2...17 V/m
radio broadcasting station (SW 1OO kW)	15 MHz	1...25 V/m
SOS-transmitter on a ship (1OO W)	41O kHz	1...3 V/m
Epitaxiedevice (induction oven)	45O kHz	37...4OO V/m
HF-welting press (welding of plastic foils)	27,12 MHz	70...85 V/m
radar on a ship (TRN 311)	9,3 GHz	1...3O uW/cm^2
radar of an airplane	9,2 GHz	45O... 28OO uW/cm^2
domestic appliances measured in a distance		of 3O cm:
hand mixer	5O Hz	5O V/m
refrigerator	5O Hz	6O V/m

Fig. 2.12: ____the electric field strength resp. Power density in our environment.<i>

____ taken from:
<i>: E. Habiger u. a. : Elektromagnetische Vertraglichkeit, Fig. 7.2, page 146, 2. Ed., 1992, Berlin, Munchen: Verlag Technik, ISBN 3-341-00993-0

2.12 Protection against artificial fields

Artificial fields more or less always occur in the neighbourhood of electric apparatus and installations. Especially problematic are those that work with the free radiation of electromagnetic fields, that is all the radio broadcasting stations, handheld and radar transmitters.

Herewith it is important that not needed parts of the antennas are shielded, that antennas with little close by field pollution are used and that the stand should be situated at least 3 km remote from inhabited areas. For instance at radar installations damping values of 10 dB and more can be obtained only by using a corresponding tree growth.

This obviously concerns a damping of the waves in a dielectric manner. We'll have to come back to this because textbook physics does not know a corresponding damping term in the wave equation.

The radiation leaking out in case of the high-frequency welding of plastic foils and of the microwave oven should be minimized.

In the case of induction ovens or of motors an active shielding often causes problems so that for simple domestic appliances like a hand mixer and especially for the electric hair-dryer non proportionally high field strength values are measured. Fig. 2.12 informs about it.

Protective measures for the operator are hardly possible. To protect uninvolved people not only the apparatus but also the rooms and eventually whole parts of buildings had to be shielded and grounded.

Sometimes also fairly simple possibilities are helpful like e.g. the usage of a remote control. By clearing away the cable salat at the workplace and at the sleeping place induction loops can be removed. Alarm-clocks operated by batteries should have preference over those operated by the network. Mattresses with metal in them and spring-beds which clearly act as an antenna should be avoided. In extreme cases even so called "current-free switches" and shielded network lines are recommended (fig. 2.13).

In the area of the network supply lines a choking coil can help decrease the spreading of high-frequency interference radiation. It is especially important that all the conducting metallic objects like e.g. water pipes, heatings, steel racks, machines, switching racks, steel armaments and metallic windows should be grounded properly, because otherwise extremly high static charges could result instead of a shielding. Construction biologists recommend to when possible do without metals when building houses and furnishing, what of course is only realizable with limitation.

In any case numerous measures are known that to a lesser extent find their legitimation in classical physics, but more likely in precaution. As long as we do not know which phenomenon causes the electrosmog and we don't have a measuring-instrument at our disposal, precaution is really the only thing we can do irrespective of the effectiveness of the measures and of the arising costs!


transmission line
used voltages:
10/30/110/220/380kV
Transformer
Neutral earthing
(N = PE) !
L1
L2
L3
N
underground cable
3 x 400 V
to the consumer loads
main fuse
recommendation:
reactor with current compensation
Standard (!):
grounding of the
neutral conductor
Electric
meter
PE
L1
N
to the installation
of the house
fuse (bedroom)
power supply
(i.e. 12 V DC)
contactor
measurement of current
with amplifier
(glow lamp)
consumer load
(bedroom)

Fig. 2.13: About the circuitry and the problems involved with a "current-free switches" installation

2.13 Unsolved tasks

The report concerning the actual state of research could be continued at will. But the expositions should suffice, to understand what are the tasks of the electromagnetic environmental compatibility (fig. 2.1) and which questions still have to be supplied with a solution. One can get deeper into every of the addressed points and then discover that some questions can be expressed sharper and maybe conceivable answers can be found, but at the same time and unavoidable the number of new questions increases faster.

Let us again take up the example of the handheld wireless telephones (chapter 1.2). At least it now is clear to us that the usage of the built-in microwave antenna of a handy is problematic. In the interior of an automobile it never should be used. If, however, one uses the antenna installed on the outside on the sheet metal then the damping and screening effect of the sheet metal chassis is advantageous at least for the handy user.

With that of course the central question is not answered. The question of what the cause is for the interfering and at worst health endangering effect of the HF-radiation. Field freedom we can't find anywhere on this world. Possibly we even need the fields. But then the question is how much is necessary, how much is healthy and how much makes us ill.

The gap of explanation especially gets clear in the case of the static or of the low-frequency magnetic field: away from technical interference sources normally fields on the scale of 10 nT are measurable. Construction biologists say that 20 nT, so twice that value, should not be exceeded at the sleeping place and maybe 50 nT at the desk. These values however are determined purely empirical.

When a person is examined in a nuclear magnetic resonance tomograph that person is exposed to a field that lies between 0.2 and 1.5 Tesla. that is a value 7 till 8 powers often higher than before mentioned without this leading to the death of that person. Entirely on the contrary this method is regarded as especially caring and safe compared to the X-ray examination.

Here again the legitimation of the thesis put forward is entirely comfirmed. The thesis that the well-known physically measurable and controllable phenomena can not be considered as a cause and that possibly a until now undiscovered field phenomenon should be called to account.

Should such a phenomenon exist it should be derived, calculated and proved. We must go to endless troubles and try everything. The actual difficulties wherein the electromagnetic environmental compatibility is stuck are a challenge.


fundamental physical
principle
(God)
cause
effect
= cause
effects
= causes
effects + effects
= causes + causes
effects + effects + effects
= causes + causes + causes
effects + effects + effects + effects
= causes + causes + causes + causes
nothing than effects (orderless chaos)

Fig. 3.0: pyramid of causality

vortices are a consequence of the principle of causality

3. Approach

In the question, if there exists a still unknown phenomenon that influences the electromagnetic environmental compatibility, we must fall back far until upon the roots of our physical understanding. Here we find a fundamental principle that until today is not doubted and that is regarded as elementary, the principle of causality. Every result of a measurement, every interpretation is checked for causality and only after passing this examination it is accepted and published.

This principle of cause and effect has established, not only in physics but also in many other disciplines of science. Is an effect observed, so there immediately is asked for the cause. This principle encounters us in daily life<i>.

When all observable and measurable effects ever can be assigned to a cause without force and without exceptional regulations then the logical result is a pyramid of causality. On top a fundamental physical principle is found, that is regarded as given by nature or as given by god and that with its properties is responsible as the cause for different effects. These effects again appear as the cause for new effects and so on (Fig. 3.0). Sometime we have removed us so far from the top of the pyramid that a direct reference to the describable effects can't be made anymore, so the impression could arise that it concerns an isolated and independent discipline. We should take care not to think in such a monocausal way, because both delimitation and avoidance of interdisciplinary working methods will inevitably steer us into a dead end!

This pyramid of causality stands for the vision of a "unified theory", like it is demanded and sought-after by numerous research scientists. But as long as it is not found, we'll have to do with unsolved problems of causality. About this any number of examples can be given.

A physical principle based on the principle of causality is the vortex. This the eddy current demonstrates us clearly. The cause for its origin is an alternating field. According to Faraday's law of induction this induces a voltage that in a conducting medium results in a current according to Ohm's law. Around this current according to Ampere's law an alternating field forms, that points perpendicular to the current and overlaps the original alternating field. This induced field first of all is an effect that overlaps the cause and itself becomes the cause. The effect that follows from that further overlaps and forms a new cause etc. In this way vortices form.

Vortices quasi represent the principle of causality.

<i>: When for instance a woman complains: "Doctor, my left knee hurts" (effect). The doctor diagnoses the cause: "Yes, that comes with age!" With that causality is established. "But doctor", says the woman, "my right knee is exactly as old as my left knee!" And already the doctor has a new problem of causality.

Principle of Causality:



	cause		effect
quantum physical approach:	quanta	→	fields
field-theoretical approach:	fields	→	quanta

---

violations of the principle of causality:

1. monopoles exist
2. starting point for the strong interaction
3. fields and quanta are a cause at the same time
4. hypothetical particles (gluons, quarks, etc.)
5. transmission of information with speeds faster than light
   - with photons (University of Berkeley)
   - with microwaves (University of Cologne)
   - with laser beams (Technical Univ. of Vienna)
6. transmission of energy with speeds faster than light
   - with scalar waves (Nicola Tesla)

Fig. 3.1: Causality or the principle of cause and effect

3.1 Principle of causality

Our physical view of life strictly obeys the rules of causality, the principle of cause and effect. But there are numerous cases, where causality at first could not be fulfilled anymore. Here alternate solutions had to be found to not endanger this very successful principle. A few examples should clarify this:

1. Technically it is impossible to produce a magnetic monopole. When a north pole is produced then the accompanying south pole is also formed. In the same way only the positive and negative pole can be assembled as the so called dipole. In the microcosm however we find monopoles. Electrons are such particles. To restore causality we must grant the microcosm its own laws that are not valid in the macrocosm! But this monocausal hypothesis contradicts the observation that the microcosm represents an image of the macrocosm and vice versa. Doubts if this assertion is allowed are reasonable.
2. Like charges repel each other and that the more the smaller the distance gets. In an atomic nucleus positively like charged protons are together at the smallest possible room without any repulsion happening. Arithmetically seen all atomic nuclei would have to explosively fly to pieces. But because this doesn't happen, shortly a new and supposedly fundamental interaction, the strong interaction, was introduced to save causality. Nevertheless this interaction now holds the like particles in a not explained manner together. Causality could be obtained only by the introduction of a new fundamental phenomenon.
3. When causality should hold as the supreme principle, it should be demanded with priority for the fundamental phenomena of physics. Instead, in quantum electrodynamics the particle is attributed the same physical reality as the field. With the wave-particle duality Heisenberg has given out the corresponding formula of compromise. This slaps the face of the principle of cause and effect.

Causality on principle allows only two approaches for a solution: the quantum physical approach. which holds the quanta as the cause for the fields, and the field-theoretical ašproach. wherein only the fields act as the cause. For both approaches there are good arguments. The field theorists cite that fields can exist also in the vacuum, so that there exist fields without particles but never particles without fields. Against that the quantum physicists hold that somewhere, even when quite far away, there exist particles and that the measurable fields merely are their action at a distance.

Both approaches first arouse the impression to be fully equal. In the course of the discoveries in the area of quantum physics, the corresponding approach has been able to establish. But it demands that all phenomena have to be understood as a consequence of particles. So should gravitons make gravitation possible, should gluons hold everything together and the quarks form the basic building parts. Meanwhile there is only worked with hypotheses. Out of poverty quantum physics meanwhile has said goodbye to strict causality, after the number of the violations of causality has risen that much and in every respect there is a lack of models of explanation. It seems as if the end is reached, as if the quantum physical approach to a large extend is exhausted.

Field-theoretical approach:



3rd Maxwell equation

$$\boxed{\mathrm{Div}\,\mathbf{B} = 0} \quad (3.3)$$

4th Maxwell equation

$$\boxed{\mathrm{Div}\,\mathbf{D} = \rho_{el}} \quad (3.4)$$

With the relations of material:

$$\boxed{\mathbf{B} = \mu \cdot \mathbf{H}} \quad (3.5)$$

$$\boxed{\mathbf{D} = \varepsilon \cdot \mathbf{E}} \quad (3.6)$$

$$\mu \cdot \mathrm{Div}\,\mathbf{H} = 0 \quad (3.3^{*})$$

$$\varepsilon \cdot \mathrm{Div}\,\mathbf{E} = \rho_{el} \quad (3.4^{*})$$

H: source free vortex field

E: non-vortical source field

New field-theoretical approach: $\boxed{\mathrm{Div}\,\mathbf{D} = 0}$ (3.7)

thus: $\mathrm{Div}\,\mathbf{H} = 0$ (3.3**) and $\boxed{\mathrm{Div}\,\mathbf{E} = 0}$ (3.7*)

H and **E**: source free vortex fields!

Einstein:

"Is it conceivable, that a field theory permits us to understand the atomistic and quantum structure of reality? This question by almost all is answered with No. But I believe that at the moment nobody knows anything reliable about it"<i>.

Pauli:

"The electric elementary quantum e is a stranger in Maxwell-Lorentz' electrodynamics"<ii>.

Fig. 3.2: The field-theoretical approach

<i>: A. Einstein: Grundzuge der Relativitatstheorie, S 162, Anhang II; 5. Aufl., Vieweg, Braunschweig 1974.

<ii>: W. Pauli: Aufsatze und Vortrage uber Physik und Erkenntnistheorie. Vieweg, Braunschweig 1961, entnommen aus:
H. G. Kussner: Grundlagen einer einheitlichen Theorie der physikalischen Teilchen und Felder. Musterschmidt-Verlag Gottingen 1976, S. 161.

3.2 Field-theoretical approach

The field-theoretical approach is the very much older one. Until the last turn of the century the world in this respect still was in order. Max Planck, by the discovery of quanta, has plunged physics into a crisis.
Albert Einstein, who, apart from his lightquanta hypothesis, in his soul actually was a field theorist, writes: „Is it feasible that a field theory allows us to understand the atomistic and quantum structure of reality?". This question by almost all is answered with No. But I believe that at present nobody knows anything reliable about it[i]".

By the way the "No" can be justified by the fact that the field description after Maxwell is by no means able to the formation of structure so that it is not possible for quanta to appear as a consequence. The field-theoretical approach could, obstructed by Maxwell's field theory, not further be pursued and to this until today nothing has changed.
Nevertheless it would be an omission to not at least have tried this approach and have it examined for its efficiency. Maybe the above mentioned problems of causality let themselves be solved much more elegantly. For this however the Maxwell theory must be reworked to a pure field theory. With the well-known formulation it offends against the claim of causality, since it is field theory and quantum theory at the same time. To Maxwell himself the quanta were still unknown, but today we know that the fourth Maxwell equation is a quantum equation:

$$\operatorname{div} \mathbf{D} = \rho_{el} \quad (3.4)$$

After this the electric field is a source field whereby the individual charge carriers, like e.g. electrons, act as sources to form in their sum the space charge density p_{el}. The other three Maxwell equations are pure wave equations. In this way the third equation identifies the magnetic field as source free:

$$\operatorname{div} B = O \quad . \qquad (3.3)$$

This for Pauli probably was the reason to call, "the electric elementary quantum e^- a stranger in Maxwell-Lorentz' electrodynamics"[ii].

Let's return to the principle of causality according to which in the field-theoretical approach the fields should act as a cause and not the particles. In a corresponding field description quanta logically have not lost anything. It is only consistent to likewise demand freedom of sources of the electric field:

$$\operatorname{Div} D = O \quad . \qquad (3.7)$$

When the electric field is not a source field, then what is it? The magnetic field is a vortex field. Hence it would be obvious to also conceive the electric field as a vortex field. Numerous reasons speak for it:

1. A non-vortical gradient field, like it is formed by charge carriers, merely represents a special case of the general vortex field. Only by the generation of quanta a source field can form as a special case.
2. The electromagnetic wave teaches us the duality between the E- and the H-field that are directed perpendicular to each other and are in a fixed relation to each other. If one of them is a vortex field then also the dual field must be a vortex field.

Duality:



$\int_a^b \mathbf{H}\,\mathbf{ds} = I$ (3.1*)

$\int_a^b \mathbf{E}\,\mathbf{ds} = -U$ (3.2*)

Circulation along the closed path ds:

Ampère's law (3.1)

$$\oint \mathbf{H}\,\mathbf{ds} = I_{ein}$$

acc. to Maxwell: (3.2)

$$\oint \mathbf{E}\,\mathbf{ds} = O$$

new: (3.8)

$$\oint \mathbf{E}\,\mathbf{ds} = -U_{ein}$$

3rd Maxwell eq.

$$\mathrm{Div}\,\mathbf{B} = O \quad (3.3)$$

4th Maxwell eq.

$$\mathrm{Div}\,\mathbf{D} = \rho_{el} \quad (3.4)$$

new:

$$\mathrm{Div}\,\mathbf{D} = O \quad (3.7)$$

With the relations of material:

$$\mathbf{B} = \mu \cdot \mathbf{H} \quad (3.5)$$

$$\mathbf{D} = \varepsilon \cdot \mathbf{E} \quad (3.6)$$

Fig. 3.3: The dual field description

Dual approach according to Jackson[i] or Lehner[ii]:

$\mathrm{Div}\,B = \rho_{magn}$ because of the 4th Maxwell equation: Div D = ρ_{el} (3.4)

ρ_{magn} = magnetic monopoles should exist,
otherwise dual extension (3.8) not allowed!

Caution: closed loop conclusion!
Maxwell theory proves the correctness of the Maxwell theory.
Result: search for magnetic monopoles unsuccessful.

---

[i]: J. D. Jackson, Classical Electrodynamics, 2nd Ed. , John Wiley, New York, 1975, S. 251 - 253

[ii]: G. Lehner, Elektromagnetische Feldtheorie, Springer-Verlag Berlin, Heidelberg 1990, S. 35 - 36 und S. 533 ff.

3.3 Duality

Duality is a fundamental physical principle. Opposite, but one another complementing phenomena can be assigned to each other in pairs, like e.g. (see fig. 8.8):



	Yin (female)	——		Yang (male)
	south pole	——		north pole
	⊖	——		⊕
R [Ω]	resistance	——	R^{-1} [Ω^{-1}]	conductance
U [V]	voltage	——	I [A]	current
E [V/m]	electr.field strength	——	**H** [A/m]	magnet.field strength
Q [As]	charge	——	ϕ [Vs]	magnetic flux
D [As/m^2]	electr.displacement	——	**B** [Vs/m^2]	magnetic induction
ε_0 [As/Vm]	electr.field-constant	——	μ_0 [Vs/Am]	magnet.field-constant
ρ_{el} [As/m^3]	electr.charge density	——	ρ_{magn}[Vs/m^3]	magnet.charge density
	induction law	——		Ampère's law
	potential vortex (vortex of the electric field)	——		eddy current (vortex of the magnetic field)

First of all we find the duality confirmed in the case of the electromagnetic wave spreading in a homogeneous medium. Here the field pointers of E and H are directed perpendicular to each other and are in a fixed relation to each other. But if the wave is damped in the presence of matter, for instance by eddy currents, then by basing on Maxwell's field theory the duality will vanish.

A good example for perfect duality provides the integral of a field strength vector along the path from a to b:

$$\int_a^b \mathbf{H}\, ds = I \qquad (3.1^*) \qquad \text{and} \qquad \int_b^a \mathbf{E}\, ds = U \ . \qquad (3.2^*)$$

Urn if the integration takes place along a closed path then the circulation yields:

$$\oint \mathbf{H}\, ds = I_{eing} \qquad (3.1) \qquad \text{and} \qquad \oint \mathbf{E}\, ds = 0 \ . \qquad (3.2)$$

According to Ampere's law (3.1) the magnetic field can thus form enclosed currents and spatially spreading eddy currents. The electric field on the other hand should be irrotational (3.2).

Let's take the case that the electromagnetic wave is damped by eddy currents and the magnetic field in this way becomes a vortex field. The electric field itself that, as said, is in a fixed relation and perpendicular to the vortex field H, will show all the vortex-typical properties. Hence nothing would be more obvious as to also grant the electric field a formation of vortices:

$$\oint \mathbf{E}\, ds = -U_{eing} \ . \qquad (3.8)$$

Critics of this dual approach, like for instance Jackson<i> or Lehner<ii>, point out that with reference to the fourth Maxwell equation the electric field should be understood as a source field:

$$\operatorname{div} \mathbf{D} = \rho_{el} \ . \qquad (3.4)$$


v (velocity)
R (radius)

Fig. 3.4a: Velocity distribution v(R) for a vortex with rigid-body rotation


v (velocity)
R (radius)

Fig. 3.4b: Velocity distribution v(R) in a potential vortex (see Lugt[i]).

---

[i] Lugt, Hans J.: Vortex flow in nature and technology. Krieger publishing company, Florida 1995; page 30 and 31, ISBN 0-89464-916-7

For a complete duality from the existence of electric monopoles, individual in the space charge density ρ_{el} contained charge carriers, the claim for magnetic monopoles is derived.
In spite of intensive search such north or south pole particles however until now could not be found. Herein from the sight of criticism is seen a confirmation for the assumption that Maxwell's field theory is self-contained and hence in principle may not be extended. The critics have a problem of causality: They postulate source fields that at the same time should be vortex fields. But if one asks how one should imagine such a field that is scalar and at the same time vectorial, then it looks as if no one has ever made any thoughts about it.

The from causality derived solution of the problem of lacking duality requires to extend the Maxwell theory in one point, by introducing the potential vortex of the electric field here and at the same time make a cut in another place:

$$\text{div } D = 0 \qquad (3.7)$$

With this formulation, the assumption of a freedom of sources in principle, the complete duality already is reached: Now neither magnetic nor electric monopoles exist (Fig. 3.3)!
At first we have to accept the loss of the electron hoping that the calculation in the end works out: the "exchange" vortices against particles, by which the quanta can be banned from the field theory, suggests that the elementary particles themselves are nothing else as spherical vortices that have found to an own physical reality.

3.4 Flow vortices

In fluid engineering convincing and strong indications for the correctness of the chosen approach can be found. It benefits us that hydrodynamic vortices are visible or can be the injection of smoke, e.g. in a wind-tunnel.
Already Leonardo da Vinci had observed at liquids that there exist two dual basic types of plane vortices: "Among the vortices one is slower at the centre than at the sides, another is faster at the centre than at the sides."
A vortex of the first type, also called "vortex with rigid-body rotation", is formed for instance by a liquid in a centrifuge that due to its inertia of mass is pressed to the edge because there the largest velocity exists. In an analogous way the electromagnetic vortex in electrically conductive material shows the well-known "skin effect" (Fig. 3.4a).
To explain the other vortex Newton describes the experiment where a rod is dipped into a liquid as viscous as possible and then is turned. In this potential vortex the velocity of the particle increases the closer to the rod it is (Fig. 3.4b).
The duality of both vortex phenomena becomes obvious when we make ourselves clear that in the experiment with the centrifuge the more liquid presses to the edge the less viscous the medium is. And that on the other hand the potential vortex forms the stronger the more viscous the medium is. As conclusion we read in text books that the viscosity of the liquid decides whether a vortex with rigid-body rotation or a potential vortex is formed.



Fig. 3.5: Combination of a vortex with rigid-body rotation and a potential vortex (Lugt[i]).

---

[i] Lugt, Hans J.: Vortex flow in nature and technology. Krieger publishing company, Florida 1995; ISBN 0-89464-916-7

3.5 Rankine vortex

When we, in a third experiment, immerse the centrifuge filled with water into a tough medium and let the centrifuge rotate, then inside the centrifuge a vortex with rigid-body rotation forms and outside the centrifuge a potential vortex forms (Fig. 3.5).

It is obvious that one vortex always causes the other vortex with the opposite properties and so the existence of one causes that of the other. So in the first case, that of the vortex with rigid-body rotation, outside the centrifuge potential vortices will form in the surrounding air, whereas in the second case, that of the potential vortices, the turning rod itself can be interpreted as a special case of a vortex with rigid-body rotation. Hence in all conceivable experiments the condition always is fulfilled that in the centre of the vortex the same state of "peace", that we can fix as "zero", prevails as in infinity.

When we take a tornado as an example, thus a whirlwind. In the "eye of the cyclone" there's no wind at all. But when I go away from this spot, then I'm blown to the outside. I can really feel the vortex with rigid-body rotation in the inside. If. however, I am standing on the outside, then the potential vortex tries to pull me into the vortex. This potential vortex is responsible for the structure and in the end also for the size of the tornado.

At the radius of the vortex, the place with the largest speed of the wind, an equilibrium prevails. The vortex with rigid-body rotation and the potential vortex at this point are equally powerful. Their power again is determined by the viscosity, which thereby fixes the radius of the vortex!

Therefore meteorologists pursue with interest whether a tornado forms over land or over water. Over the ocean for instance it sucks itself full with water. In that way the potential vortex increases in power, the radius of the vortex gets smaller and the energy density increases dangerously.

If the knowledge from hydrodynamics is transferred to the area of electromagnetism, then the role of the viscosity is taken over by the electric conductivity. The well-known current eddy occurs in the conductor, whereas its counterpart, the postulated potential vortex, forms in the bad-conducting medium, with preference in the dielectric. The duality of both vortices is expressed by the fact that the electric conductivity of the medium decides whether current eddies or potential vortices can form and how fast they decay, i.e. convert their energy into heat.



Fig. 3.6: Kirlian photograph of leaves[i] structured corona discharges

---

<i>: (produced by students of electronics in the laboratory for power electronics of the Author, University of Applied Sciences Furtwangen 1991)

<ii>: Kupfmuller, Karl: Einfuhrung in die theoretische Elektrotechnik, Springer-Verlag Berlin, 12. Auflage 1988, page 453

<iii>: Kupfmuller, Karl: Einfuhrung in die theoretische Elektrotechnik, Springer-Verlag Berlin, 12. Auflage 1988, page 208

3.6 Vortex and anti-vortex

Fig. 3.5 shows that vortex and dual anti-vortex mutually cause each other. In high tension transmission lines we find a striking example for the combination of current eddy and potential vortex. Within the conductor current eddies are formed. Thus the current density increases towards the surface of the conductor (skin effect). Outside of the conductor, in the air, the alternating fields find a very bad conducting medium. If one follows the text book opinion, then the field outside the conductor should be an irrotational gradient field! But this statement causes unsolvable problems.

When vortices occur inside the conductor, then for reasons of a detachment of the vortices without jumps at the interface to the dielectric, also the fields in the air surrounding the conductor must have the form and the properties of vortices. Nothing would be more obvious as to also mathematically describe and interpret these so-called gradient fields as vortex fields. When looking exact this argument even is mandatory!

The as laws of field refraction known boundary conditions<ii> in addition demand steadiness at the interface of the conductor to the dielectric and don't leave us any other choice. If there is a vortex field on one side, then also the field on the other side is a vortex field, otherwise we offend against the law! Here an obvious failure of the Maxwell theory is present.
Outside the conductor, in the air, where the alternating fields find a very bad conducting medium the potential vortex not only exists theoretical; it even shows itself. Dependent among others on the frequency and the composition of the surface of the conductor, the potenial vortices form around the conductor. When the thereby induced potentials exceed the initial voltage, then impact ionisation takes place and the well-known corona discharge is produced. Everyone of us can hear this as crackling and see the sparkling skin with which high tension transmission lines cover themselves.
In accordance with the text books also a gradient field increases towards the surface of the conductor, but an even shining would be expected and not a crackling. Without potential vortices the observable structure of the corona would remain an unsolved phenomenon of physics (Fig. 3.6).

But even without knowing the structure-shaping property of the potential vortices, that in addition acts supporting and that we'll have to derive, it can be observed well that especially roughness on the surface of the conductor stimulate the formation of vortices and can produce vortices. If one is looking for a reason why with large frequency the very short impulses of discharge always emerge from roughness<iii>, then very probable potential vortices are responsible for it. By means of a Kirlian photograph it can be shown that the corona consists of structured separate discharges (Fig. 3.6).

With this the approach is motivated, formulated and given reasons for. The expositions can't replace a proof, but they should stand a critical examination. Mathematical and physical evidence will be furnished later.


copper cable
fibre optic cable
|j| (current density)
(intensity) I
R (radius)
R (radius)
distribution
of the current density
(eddy current)
distribution
intensity of light
(potential vortex)

Fig. 4.1: The distribution in principle of the intensity of light within a fibre optic cable[i] compared to the distribution of the current density in a copper cable

---

[i] Meyl, Konstantin: Potentialwirbel, Band 1: Diskussionsbeitrage zur naturwissenschaftlichen Deutung und zur physikalisch-technischen Nutzung, basierend auf einer mathematischen Berechnung neu entdeckter hydrotischer Wirbel, INDEL GmbH, Verlagsabteilung, Villingen-Schwenningen 1990, ISBN 3-9802-542-1-6

4. Properties

4.1 Concentration effect

It can be assumed that until now there does not yet exist a technical application for the here presented potential vortex theory unless the phenomenon was used by chance and unconsciously. About this the transmission of optical light signals over fibre optic cable can be given as a typical example.
Compared to a transmission of energy impulses over a copper cable fibre optic cables show a considerable better degree of effectiveness. The derived potential vortex theory provides a conclusive explanation for this phenomenon and therefore is put here to discussion: If we cut through a fibre optic cable and look at the distribution of a light impulse over the cross-section, then we observe a concentration in the centre of the conductor (fig. 4.1).

Herc the duality between the vortices of the magnetic and of the electric field comes to light. Whereas the current eddies in a copper conductor cause the "skin effect" as is well-known, potential vortices show a "concentration effect" and align themselves with the vortex centre. The measurable and in fig. 4.1 shown distribution of the light intensity in a fibre optic cable may confirm this phenomenon, the orientation of the potential vortex on the vortex centre.

For instance the calculation of the resistance of a copper cable provides as an important result an apparent decrease of the resistance directed towards the conductor surface. There the associated better conductivity as a consequence causes an increased current density. In the reversed direction, towards the centre of the conductor, consequently a decrease of the effective conductivity would be present, and this result is independent of the used material. According to the rules of duality this is a condition for the formation of potential vortices. As already said the conductivity is responsible for it, if the expanding eddy current with its skin effect or the contracting potential vortex with its concentration effect is predominant.

Usual fibre optic materials possess not only a small conductivity, but in addition a high dieletricity. This additionally favours the formation of vortices of the electric field. If one consciously or unconsciously supports the potential vortices, then there is a possibility that the life of the fibre optic cable is negatively influenced because of the concentration effect. Of course it can not be excluded that other effects, like e.g. reflections or the modes of the light are involved in the concentration effect. But it should be guaranteed that this actually concerns is causal phenomena and doesn't concern only alternative explanations out of ignorance of the active vortex phenomenon.

The formal mathematical reason for the concentration effect provides the reverse sign in Faraday's law of induction compared to Ampere's law (see also equation 3.1 and equation 3.8 in fig. 3.3).


magnetic
field strength
H
eddy
current
N
I
S
magnetic
dipole
electric
field strength
E
potential
vortex
+
U
–
electric
dipole
vortex of the
conductor
vortex of the
non-conductor
ideal case:
superconductor
vacuum
material properties which act amplifying:
permeability
dielectricity
result:
„skin effect“
„concentrations
effect“

Fig. 4.2: The acting as a dipole of
current eddies and potential vortices

4.2 Duality of the vortex properties

The rules of duality dictate for the vortex of the electric and of the magnetic field the following characteristics:

1. Whereas currents and eddy currents demand a good conductivity, potentials and potential vortices can only form with bad conductivity, thus in a dielectric and best in the vacuum.

2. Eddy currents run apart, strive towards infinity and thus show the well-known "skin effect" with a spatially limited arrangement of the conductor. According to the rules of duality the potential vortex will strive towards the vortex centre and in this way will show a "concentration effect".

3. Another property of vortices is shown in fig. 4.2.
On the left side a plane eddy current is indicated. Since the discovery of Ampere's law it is well-known to us that such a circular current (I) forms a magnetic dipole standing perpendicular to the vortex plane.
On the right hand side the dual phenomenon is sketched. Here charges are piled up circularly to a planar potential vortex (U). Thereby an electric dipole forms, standing perpendicular to the vortex plane. This relation directly follows from the equations of the field-theoretical approach.
Whereas circular currents and current eddies produce magnetic dipoles, the postulated potential vortices will form electric dipoles.

With these three interesting properties some key questions of quantum physics, that until now have stayed a mystery to science (fig. 4.4), can be answered conclusively and without compulsion e.g.:

I.Why are there no magnetically charged particles?
The better the conductivity of a medium is, the higher as a consequence the number of free charge carriers is. the more strongly eddy currents are formed. The answer to question I is inferred from the opposite case:
In the ideal vacuum no charge carriers at all are present, why no currents, no current eddies and consequently no magnetic poles can exist.
With this well-known fact the first question already is answered. The question why in the microcosm there can not exist magnetically charged elementary particles, why the search for magnetic monopoles doesn't make any sense. Let's ask further:

II. Why are there only electrically charged particles?
Let us for that consider the dual conditions. The worse the conductivity of a medium is, the more the potential vortex -will be favoured that because of this property also can be understood as the vortex of the dielectric.
In the mentioned extreme case of the ideal vacuum, no electric conductivity is present for reason of the missing charge carriers. But this circumstance favours the potential vortex and that, according to fig. 4.2, forms electric poles and with this also the second question would be answered clearly.
It can be traced back to the boundary conditions of the microcosm that without exception electricallv charged particles are entitled to exist; a realization derived from the field-theoretical approach, that covers all experiences.



the positron e⁺



the elektron e⁻

Fig. 4.3: Elementarv particles as configurations of potential vortices

4.3 Derivation of the electron as an elementary vortex

The next key question necessarily has to be brought to a conclusive answer to save the principle of causality, so that we no longer have to postulate an own physics with its own laws for the microcosm:

III. Why do these particles show as monopoles?

More concrete the question has to read:
Where is the positive pole in a negatively charged electron, if it should be an electric dipole?
The only possible answer is:
In the centre of the particle!

Thus in the centre of the electron its positive pole is hidden and in the centre of the positron its negative pole is hidden. But we only observe these particles from the outside and for reason of the field conditions of the electron we measure a negative charge and for its antiparticle, the positron, a positive charge. If in each case we wanted to measure the electric fields included in the inside, we had to destroy the particle. Then a proof would not be possible anymore.

Here also a persistent mistake is eliminated by the for a long time known axiom that monopoles can not exist at all if one considers continuity! By means of technical-physical experiments this axiom is sufficiently secured.
The quantum physical approach is standing on uncertain ground if it is postulated that other laws of nature should apply to particle physics, if a second approach, the field-theoretical approach, is conceivable that does not know these problems!

The discussed concentration effect gives the potential vortex a structure shaping property. With that also the fourth key question can be answered:

IV. Why do the particles have the form of spheres?

The potential vortex is favoured in the particle-free vacuum of the microcosm because of the missing conductivity. In connection with the concentration effect the following conclusion can be drawn:
The extremely mighty potential vortex exerts a high pressure on the microcosm and on each particle.

With that also the fourth key question, why stable elementary particles are spherical, can be answered by the potential vortex theory:
Only the sphere is able to withstand a high outside pressure.
All other forms, like e.g. dipoles formed like a rod or a club would be instable in the presence of the extremely concentrating potential vortex. They would be immediately destroyed by the pressure of the potential vortex.

I. Why are there no magnetically charged particles?
(the vacuum has no conductivity!)

II. Why are there only electrically charged particles?
(in the vacuum only potential vortices can exist!)

III. Why do these particles show as monopoles?

(the other pole is locked up in the inside of the vortex oscillation!)

IV. Why do the particles have the form of spheres?

(for reason of the outside pressure by the concentration effect!)

V. Why is the elementary quantum stable?

(without conductivity no decay of vortices takes place!)

VI. Why does for every particle of matter exist an antiparticle?

(there are two swirl directions with equal rights!)

VII. Why are particles and antiparticles incompatible?
(contrary swirl directions!)

Fig. 4.4: Key questions of quantum physics

4.4 Quanta as field vortices

The fied-theoretical approach demands removing the electron from the field equations (eq. 3.7) and at the same time introducing the potential vortex of the electric field. With this vortex phenomenon there now is a possibility that the electromagnetic wave spontaneously rolls up to a vortex in case it is disturbed from the outside. The vortex particle that is formed in such a way owes its physical reality on the one hand the concentration effect of the potential vortex, that compresses this particle to the dimension of a tiny sphere and on the other hand its localization for reason of the oscillation around a fixed point.
The spherical elementary particles are being compressed to inconceivably small dimensions. Therefore they are capable to bind a comparatively high energy in their inside. This is confirmed by the mass-energy relation $E = mc^2$. (4.1)

The fact that the energy is dependent on the speed of light can be judged to be a clear indication that quanta actually are nothing but oscillating electromagnetic packages, vortical oscillations of empty space!
The next question reads:

V. Why is the elementary quantum stable?
The worse the conductivity is, the more the potential vortex will be favoured, the more strongly the concentration effect will form, the smaller the spherical phenomena will get - the larger the authoritative relaxation time will be, i.e. the slower the decay of vortices and with that the more stable the vortex phenomenon will be.
In the microcosm, that comes the ideal case of a particle-free vacuum very close, the spherical vortices because of the missing conductivity have an absolute stability.

VI. Why does for every particle of matter exist an antiparticle?
Since every vortex can also oscillate in the opposite direction, there always exist two forms of formation of spherical vortices with equal rights, one of them is assigned to the world of matter and the other to the world of anti-matter.

VII. Why are particles and antiparticles incompatible?
For reason of the contrary swirl direction they are incompatible to each other. They have the tendency to destroy each other mutually, like two trains that want in the opposite direction on a single-tracked distance.

The quantum physical approach does not have an answer to these key questions. Until now scientists have merely thought about to what the observable contraction in the microcosm and the macrocosm can be traced back. Because the approach was not able to furnish an answer, without further ado some new matter was introduced: the sluons. These binding particles should be able to exert the necessary pressure. But until now no one has been able to observe or detect this fabulous matter. Nobody knows its structure and its composition. Despite missing evidence it is stated that this matter is mass less and at the same time lumped; it is invisible because it can't interact with any other matter, not even with the supposed building parts of the atomic nuclei, the quarks. But at the same time there should be exerted a pressure on the quarks, for which reason quarks again should be able to interact with gluons!



Fig. 4.5: Two coaxial oscillating vortex rings (Lugt<i>).

<i> Lugt, Hans J.: Vortex flow in nature and technology. Krieger publishing company, Florida 1995; page 42, ISBN 0-89464-916-7

4.5 The photon

The ability to form structures as a consequence of the concentration effect gives the potential vortex a number of highly interesting properties. To derive these properties we can make work easier when we fall back upon the observations and experiences of flow dynamics.

Here the vortex ring takes a special place. Its vortex centre is not closed, for which reason it is not stationary and propagates in space with a constant speed. It can be observed that the velocity of propagation increases with the ring diameter becoming smaller. By means of the vortex rings, that skilful smokers can produce with pointed lips, these properties can be made visible.

Now if two vortex rings run into each other with the same axis and direction of rotation then both oscillate around each other, by one vortex attracting the other vortex, thereby accelerating and thus contracting it. The second vortex then slips through the core opening and gets again slower and larger. Now the first vortex accelerates and plays the same game (fig. 4.5).

It would be obvious for the vortex of the electric field to have a corresponding property. The electron e- and with the opposite swirl direction the positron e+ will form such a potential vortex corresponding to the derivation. Two electrons, as like charged particles, would repel each other and surely will be out of the question for such a configuration. An electron and a positron however will attract each other and because of their incompatibility they will mutually destroy unless they open their vortex centres to form a vortex ring. Now the e- shows its positively charged centre that shows the same swirl direction as the e+ seen from the outside. Therefore the vortices don't hurt each other, when the positron slips through the opened vortex centre of the electron and vice versa.

This oscillating electron-positron pair has strange properties: seen from the outside one moment it is negatively charged and the next moment it is positively charged. Therefore over time on the average no charge will be measurable and no electromagnetic interaction will take place.

One moment the particle is matter and the next moment it is anti-matter. Hence no mass at all can be attributed to the particle. Interactions primarily takes place between both dual vortices. We can predict, the particle has neither mass nor charge. The environment merely sees a fast oscillating particle that only within every half cycle is capable of an interaction.

The centre of the oscillating particle is open, for which reason it is not stationary anymore. Instead it propagates in z-direction with the swirl velocity, which is the speed of light, in this way preventing a rotation around the x- or y- axis (fig. 4.6). In this way a polarizability is present.

The only possible and, as we will see, necessarily taking place rotation around the z-axis gives the particle a spin of the magnitude of a quantum of angular momentum. After all the rotation for e^- and e^+ is of the same magnitude with a spin of each time $\frac{1}{2} \cdot \hbar$.There should be paid attention to the fact that for the case of an opposite sense of direction of the respective rotation around the common z-axis the spin on the average will be zero.

In addition the particle is characterized by an outstanding property: a periodically taking place oscillation with any frequency, but that frequency has to be constant. We now only have to take a table of particles to hand. Actually we will find a corresponding particle that has all these properties: the γ-quanta,also called photon.



Fig. 4.6: The photon as oscillating electron-positron pair

The decay of the γ- quanta (photon)[i]
(= pair creation = Bethe-Heitler-process 1934):

$$\gamma \longrightarrow e^- + e^+$$

(4.2)

---

[i] Nachtmann, Otto: Phanomene und Konzepte der Elementarteilchenphysik, Vieweg, Braunschweig 1986, S. 135, ISBN 3-528-08926-1

4.6 Pair creation

Proof for the correctness of the model concept provides the decay of the photon in an electron and a positron in the presence of a strong field, as for instance in an atomic nucleus. This observable decay is called pair creation or Bethe-Heitler process<i>:

$\gamma \longrightarrow e^- + e^+$ (4.2)

In this process the elementary vortices for a short time get back their localization and are therefore detectable. Otherwise the electron and positron have the form of a sphere, the photon however rather has the form of two oscillating discs.

The photon doesn't participate in the electromagnetic interaction, because the electric field lines run from one disc to the other (from + to -). The field lines are not open as they are for e^- or e^+ (fig. 4.3). To open up the field lines an energy is necessary that corresponds to the sum of the two formed particles. But from this it by no means follows that this amount of energy will be released in the reversed and much better known process, where matter and anti-matter annihilate under emission of γ-quanta. At the end of the derivation the vortex model will provide us the desired answers on questions of the energy of photons.

Here first of all only the properties will be concerned. Experiments, in which light shows as a particle, are the photoelectric effect, the Compton effect and a lot more. According to the by Maxwell developed classical theory of light however is light an electromagnetic wave that is not quantized in any way, neither as sphere nor as disc, the wave nature of light as well has a physical reality and is secured by experiment. This is witnessed by the interference patterns of overlapping coherent light beams.

A concept in which light could exist at the same place and the same time both as wave and as corpuscle could never be brought into accord with the principle of causality. Formulas of compromise, like the uncertainty principle of Heisenberg that refers to the point of view of the observer, can't change anything about this dilemma. The dual nature of light, that in this context is gladly spoken of, rather consists of the fact that dependent on the local field conditions, any time and spontaneously the wave can roll up to a vortex.

As an example of a violation of the principle of causality it has been indicated under point 3 (fig. 3.1) that both fields and quanta at the same time should be the cause of something. This concept was formulated by Maxwell and written down in modern quantum electrodynamics by Dirac but in the field-theoretical approach we have dropped this concept because it violates all rules of causality in an elementary manner. Therefore it only is consistent, if we hold the view that the light is either wave or particle but never is both at the same time!

In the spontaneous transition of the wave to the particle all the important properties are conserved: the propagation with the speed of light, the characteristic frequency of the oscillation and the mentioned polarizability.

The process of rolling up possibly takes place already in the laboratory, in a bubble chamber and at the latest in our eyes. To receive the electromagnetic wave, we had to have antennas. We actually see the photons. It therefore would be obvious if our cells to see only could perceive vortices, in this case photons. We don't possess a sense organ for fields and waves.



Fig. 4.7: The power density shown against frequency for noise
(a) according to Kupfmuller[i],
as well as for dielectric losses of a capacitor (also a) and for eddy current losses (b) according to Mevl[ii]
(b in visible duality to a).

---

[i] Kupfmuller, Karl: Einfuhrung in die theoretische Elektrotechnik, Springer-Verlag Berlin, 12. Auflage 1988, ISBN 3-540-18403-1

[ii] Meyl, Konstantin: Dreidimensionale nichtlineare Berechnung von Wirbelstromkupplungen, Dissertation Universitat Stuttgart 1984

4.7 Noise

If, according to the field-theoretical approach, there exist electric field vortices then they will not only form the elementary particles in the vacuum, but will also macroscopically form and have an effect in larger dimensions.

Assuming a wave that rolls up to a plane vortex it would be obvious if polarization and velocity of propagation are conserved in the process. But how does it stand about the frequency?
The wave now will walk round a stationary point, the vortex centre. The propagation with the speed of light c will remain existent as the swirl velocity. For a plane circular vortex, where the path for a revolution on the outside is very much longer than near the vortex centre, there arises a longer wave length and as a consequence a lower frequency on the outside as more to the inside. With this property the vortex proves to be a changer of frequency: the vortex transforms the frequency of the causing wave in an evenly spectrum, that starts at low frequencies and stretches to very high frequencies (fig. 1.4). Exactly this property we observe in "white noise". The consistent conclusion would be that this concerns the vortex of the electric field. Anyone can, without big expenses, convince himself or herself of the localization, of the property to change the frequency and of the circumstance that vortices can be very easily influenced, that they avoid or again whirl about a place of disturbance, for instance an antenna. For that one only needs to tune a radio receiver to a weak and noisy station and move oneself or some objects around, then one is able to directly study the influences from the manipulation of the receiving signal.
But already the fact that the using and measurability of signals is limited by noise makes clear. which attention the potential vortex should be given.

Within a limited frequency range the power of the Nyquist or resistance noise is independent of frequency (fig. 4.7). This should be clarified particularly by the term "white noise" analogous to white light, where all visible spectral ranges independent of frequency have the same energy density.

But this relation doesn't hold for high frequencies of any magnitude. Here another noise-effect appears, that is said to have its cause in the quantum structure of energy<i>. Untouched by possible interpretations an increasing power of the noise is measured, that more and more turns into a being proportional to frequency (fig. 4.7, curve a). Interestingly this curve shows a remarkable duality to the power curve of eddy currents, likewise shown against the frequency, that for instance can be measured at eddy current couplings<ii> (fig. 4.7, curve b). This circumstance suggests a dual relation of the potential vortex of the electric field in bad conducting media on the one hand and the eddy current in inductive materials on the other hand <iii>.

<iii>: Meyl, Konstantin: Wirbel des elektrischen Feldes,
EMC Journal 1/95, 6. J, ISSN 0945-3857, S. 56 - 59.


metallized film of polypropylen
glass plate
glass plate

a) measurement set up according to Yializis and others<i>



b) after 40 hours c) after 52 hours

Fig. 4.8: Measurement set up (a) and photo of vortex structure in a metallized polypropylen layer capacitor (at 450 V/ 60 Hz/ 100°C)
Observation of the formation of a vortex (b) and (c). (110 fold magnification), according to Yializis et al.<i>

<i>: A. Yializis, S. W. Cichanowski, D. G. Shaw: Electrode Corrosion in Metallized Polypropylene Capacitors, Proceedings of IEEE, International Symposium on Electrical Insulation, Bosten, Mass., June 1980;

4.8 Capacitor losses

Next the dielectric losses in a capacitor fed with an alternating voltage are measured and likewise put on against the frequency. At first the course is independent of the frequency, but towards higher frequencies it increases and shows the same characteristic course of the curve as the before mentioned power of the noise (fig. 4.7, curve a).

This excellent agreement suggests the assumption that the dielectric losses are nothing but eddy losses.
These vortex phenomena, caused by time-varying fields, are not only found in ferromagnetic and conductive materials, but equally as dual phenomena in dielectrics and non-conductors.

As examples of practical applications the induction welding or the microwave oven can be mentioned. The process can be described in other words as follows: in both examples the cause is posed by high-frequency alternating fields that are irradiated into a dielectric as an electromagnetic wave, there roll up to potential vortices and eventually decay in the vortex centre. The desired and used thermal effect arises during this diffusion process.

The striving in the direction of the vortex centre gives the potential vortex of the electric field a structure shaping property. As a consequence of this "concentration effect" circular vortex structures are to be expected, comparable to the visible vortices in flow dynamics (e.g. tornados and whirlwinds). At the same time the dual anti-vortex arises, the diverging eddy current. It takes, as is well-known, the given structure of the conductor, so in the technical literature one correspondingly talks of a "skin effect". Now if conductor and non-conductor meet as they do in a capacitor, then at the boundary area visible structures will form. Circles would be expected, if the eddy current in the inside and striving to the outside is equally powerful as the potential vortex that comes from the outside and concentrates.

Actually such circular structures are observed on the aluminium of high tension capacitors, when they were in operation for a longer period of time. The formation of these circles, the cause of which until now is considered to be unsolved, is already experimentally investigated and discussed on an international level by scientists (fig. 4.8) [i, ii].

These circular vortex structures can be seen as a visible proof [iii] for the existence of potential vortices of the electric field.

<ii>: D. F. Taylor, On the Mechanism of Aluminium Corrosion in Metallized Film Capacitors, IEEE Transactions on EI-19,August 1984,No.4,pp.288-293.

<iii>: Meyl, Konstantin: Wirbel des elektrischen Feldes, EMC Journal 1/95, 6.J, ISSN 0945-3857, S. 56-59.



Fig, 4.9: Motion of two point vortices. (Lugt<i>)
A. with opposite direction of rotation
B. with the same direction of rotation
1. for equal vortex strength
2. for unequal vortex strength

Example from practice for case A1:
vortex pair behind an airplane



4.9 Vortex lines and vortex streets

It can be assumed that the vortex of the electric field is relevant with regard to the electromagnetic environmental compatibility. This then holds not only for microcosmic and microscopic vortices, but also for macroscopic and larger dimensions. The individual vortices can join together to balls and lines. For the study of this process it is useful to again fall back upon experiences of flow dynamics.

The co-operation of individual point vortices has been investigated thoroughly in flow dyamics. Without any outside manipulation an individual vortex rotates on the spot. That changes in the case of two neighbouring vortices. Now it depends on their mutual strength and sense of rotation. If they have the opposite sense of rotation and equal strength then their centres of rotation move straight forward in the same direction. If however the direction of rotation is the same then both vortices rotate around each other (fig. 4.9).

In this way a multitude of point vortices is capable, to form in the first case whole vortex streets and in the second case spherical vortex balls. In principle a vortex string can also consist of a multitude of potential vortices pointing in the same direction; but it has the tendency to roll up to a vortex ball in case it is disturbed from the outside, as can be shown very clear by means of computer simulations<i>.

As a starting-point for a discussion the thesis can be put forward that also electric field vortices, in nature usually consisting of a multitude of individual point vortices, appear as vortex strings and vortex balls.

Perhaps historians see in this property an answer to the question, how it was possible for the Romans to build streets straight as a die in the wilderness. Their land surveyors, the Augures, had at their disposal neither laser, nor any other suitable gauges. Their most important tool was the Lituus, the crook, that at its upper end was rolled up like a vortex in the sense of a flat coil shaped like a spiral.
The question poses what this strange object was used for. Perhaps the roman land surveors tracked down any vortex lines with this crook and then used them to orientate themselves?
History still holds a lot of secrets, but for now only this indication is given. The following seminar will give enough opportunities for speculations and discussions<ii>.

<i>: Lugt, Hans J.: Vortex flow in nature and technology. Krieger publishing company, Florida 1995; p.38, fig. 3.25, 3.26 and 3.27, ISBN 0-89464-916-7

<ii>: K. Meyl: Elektromagnetische Umweltvertraglichkeit Teil 2 und 3 Seminarumdrucke, INDEL Verlag VS; see part 2 and 3 of this book.





Fig. 4.10: The rolling up of a vortex chain to a vortex ball for the smallest disturbance
(case Bl in fig. 4.9) (Rosenhead<i>).

<i>: L. Rosenhead: Formation of vortices from a surface of discontinuity. Proc. Roy. Soc. A 134, 1931, 170. taken from:

Lugt, Hans J.: Vortex flow in nature and technology. Krieger publishing company, Florida 1995; page 39, figure 3.29, ISBN 0-89464-916-7

4.10 Water colloids as vortex balls

We have to realize that in the biosphere we are staying in a relatively ideal dielectric. The two "capacitor plates" are being formed by the ionosphere and the earth. The potential vortex will, as said, be favoured by a bad conductivity and by a high dielectricity. Consequently it will dominate and take effect in the biosphere. In which way it takes effect is the central theme of the electromagnetic environmental compatibility.

Life in this world consists predominantly of water and water has a very high dielectricity! With that the effectiveness and the long life of the potential vortex increases. The human head for instance contains 7O% and plants contain over 90% water! But it does not simply concern H_2O, but structured water in a colloidal form. These water colloids could be vortex balls because they consist of a large number of water molecules in a spherical arrangement They form independent and insoluble particles with a negative electric charge (fig. 4.11). Water is not equal water thanks to this structure. One can buy healing water and corresponding sources are well-known and famous. Many an effect can be explained by means of a chemical analysis but not everything.

The highest age in this world is reached by the inhabitants of Hunza, in the mountains of norhern India at the foothill of the Hindu Kush, at an altitude of 2500 meters. They drink some muddy glacial water that is strongly colloidal. Hence it would be obvious that plants and also we ourselves need such water for our physique. Processes are known with which the advantageous vortex balls, say colloids, are produced artificially by mechanic or chemical treatment<i>. Levitated water, as it is called and as it is for sale nowadays, is said to be more healthy. Unfortunately people predominantly work empiric in this area, because science occupies itself with this topic only little or not at all.

Another problem is the fact that the colloids again fall apart quickly. The like negative charge favours this process. The liquid crystals have to be stabilized from the outside. In the case of the Hunza-water the colloids are surrounded by a vegetable layer of fatty acid and are protected in this way <ii>. It possibly is very obliging to nature, if the water colloids also in biological systems are stabilized in that way.

Everyone of us knows that fresh spring water tastes much better than stale, bottled water, even if the chemical analysis turns out of be absolutely identical. For this fact classical science is not able to give a cause - a further problem of causality. In any case should potential vortices with their structure shaping property be considered as a cause for the formation of water colloids. It surely causes no difficulties at all to interpret the colloids as vortcx bulls.

<i>: V. Schauberger: Die Entdeckung der Levitationskraft, Implosion 1995 Nr. 112 und:
N. Harthun: NaturgemaSe Technik - Wege fur die Forschung nach Viktor Schauberger, Verlag Delta Design, Berlin 1996.

<ii>: Flanagan: Elexier der Jugendlichkeit, Waldthausen Verlag Ritterhude 1992, orig.: Elixir of Ageless



H_2O: the angle of the bond between 2 H molecules = 104,5°
angle of the bond in excited state = 109,5°



electron orbital diagram of energy (excited H_2O) = tetraeder
most stable liquid crystal = 8 tetraeder = star of octaeder


unprotected colloid
artificially protected colloid (soap molecule)
Colloid protected by albuminoids or fatty acids (in living systems)

Fig. 4.11: Water molecules and water colloids

4.11 Phenomenon of transport

The vortex principle is self-similar. This means that the properties of an individual vortex also for the collection of numerous vortices again appear and can he observed in a similar manner. That's why a vortex ball behaves entirely similar as an individual isolated vortex. The same concentration effect, that keeps the vortex together, shows its effect for the vortex ball and keeps it together also.

Something corresponding holds for a basic property of potential vortices, being of a completely different nature. It is the property to bind matter in the vortex and carry it away with the vortex. Well-known are the vortex rings that skilful cigarette smokers can blow in the air. Of course also non-smokers can produce these air eddies with their mouth but these remain invisible. Solely by the property of the vortex ring to bind the smoke it becomes visible to the human eye.

If out potential vortex transports something then it rather should be a dielectric material, so preferably water. Therefore if in the environmental air we are surrounded by potential vortices that we can detect for instance as noise, then they are capable with their "phenomenon of transport", to pick up water and to keep it in the vortex. In this way the atmospheric humidity is explicable as the ability of the air particles to bind comparatively heavy water molecules. If the vortex falls apart then it inevitably releases the water particles and it rains. This is merely a charming alternative for the classical representation without claim to completeness.

Already the Romans have made use of this phenomenon to find water and sources. About this Vitruv<i> (from 23 BC) in his 8th book about architecture writes: "Before sunrise one has to lie down on the earth at the places, where to search for water,... and one has to look at the area... Then one has to dig at the place where there appears curling and in the air rising moist steam. Because this characteristic can not occur at a place where there is no water". The at a certain time of day and in certain seasons occasional in meadows and corn fields observable streaks or circular mostly moist places with differing vegetation, have to be judged as an infallible sign for the existence of this phenomenon.

This phenomenon of transport again appears for the discussed water colloids. The involved water molecules form a spherical object with a negative charge. They turn their negatively charged side to the outside and point with the positively charged end in the direction of the middle of the sphere. There, no longer discernible from the outside, a negatively charged ion can be, that is stuck, that no longer can escape and that gives the whole colloid a characteristic property. In this way nature knows various water colloids that constitute plants and animals. But starting at a temperature of 41°C the liquid crystals fall apart. This not by chance is the temperature at which a person dies. Already 10 millivolts per liquid crystal suffice for the electrically induced death.

The to a colloid identical structure we find in the structure of the atoms. Here the atomic nucleus is held in the inside of a vortex-like cloud of electrons, the atomic hull. We'll hit the phenomenon of transport a last time, when we derive the elementary particles. For the photon is already discernible the tendency of an elementary vortex, to take another vortex in its inside. Merely because the electron and positron are evenly matched a stable configuration is prevented for the photon.

<i>: Vitruvius Pollio, Marcus: Ten Books about architecture, WBG 1987

In chapter vortex calculation used differential operations:



field pointer (vector = **bold**):

$$\mathbf{A} = \mathbf{e}_x \cdot A_x + \mathbf{e}_y \cdot A_y + \mathbf{e}_z \cdot A_z$$

Gradient of the scalar function of position V:

$$\text{grad } V = \mathbf{e}_x \cdot \delta V/\delta x + \mathbf{e}_y \cdot \delta V/\delta y + \mathbf{e}_z \cdot \delta V/\delta z \qquad \text{(R1)}$$

Divergence of the vector **A**:

$$\text{div } \mathbf{A} = \delta A_x/\delta x + \delta A_y/\delta y + \delta A_z/\delta z \qquad \text{(R2)}$$

Curl (vortex density) of the vector **A**:

$$\begin{aligned} \text{rot } \mathbf{A} = {} & \mathbf{e}_x \cdot (\delta A_z/\delta y - \delta A_y/\delta z) + \\ & + \mathbf{e}_y \cdot (\delta A_x/\delta z - \delta A_z/\delta x) + \\ & + \mathbf{e}_z \cdot (\delta A_y/\delta x - \delta A_x/\delta y) \qquad \text{(R3)} \end{aligned}$$

Laplace operator Δ:

$$\Delta \mathbf{A} = \delta^2\mathbf{A}/\delta x^2 + \delta^2\mathbf{A}/\delta y^2 + \delta^2\mathbf{A}/\delta z^2 \qquad \text{(R4)}$$

arithmetic rules:

$$\Delta \mathbf{A} = \text{grad div } \mathbf{A} - \text{rot rot } \mathbf{A} \qquad \text{(R5)}$$

$$\text{div rot } \mathbf{A} = 0 \qquad \text{(R6)}$$

$$\mathbf{A} \times \mathbf{B} = -\mathbf{B} \times \mathbf{A} \qquad \text{(R7)}$$

$$\text{div } (\mathbf{A} \times \mathbf{B}) = \mathbf{B} \text{ rot } \mathbf{A} - \mathbf{A} \text{ rot } \mathbf{B} \qquad \text{(R8)}$$

$$\text{rot } (\mathbf{A} \times \mathbf{B}) = (\mathbf{B} \text{ grad})\mathbf{A} - (\mathbf{A} \text{ grad})\mathbf{B} + \mathbf{A} \text{ div } \mathbf{B} - \mathbf{B} \text{ div } \mathbf{A} \qquad \text{(R9)}$$

$$\mathbf{A} \times (\mathbf{B} \times \mathbf{C}) = \mathbf{B} \cdot (\mathbf{A} \cdot \mathbf{C}) - \mathbf{C} \cdot (\mathbf{A} \cdot \mathbf{B}) \qquad \text{(R10)}$$

* important equations are given in a box
* new equations are underlined twice.

Fig. 5.0: Collection of formulas for vector analysis

5. Derivation and interpretation

Vortices cause big problems to every measuring technician. They have the unpleasant property to whirl around the sensor even if it is as small as possible. Vortices avoid the smallest disturbance and then can hardly be detected reproducibly.

From the well-known eddy current we know of this problematic. Instead of the vortex, we are forced to measure and analyse any effects that arise from the vortex. These can be measurements of the eddy losses or effects back on the stimulating field. But only provided that the effect actually occurs.
The prerequisite for an increase in temperature by eddy losses is that the vortex falls apart. In an ideal medium it unfortunately will not do us this pleasure.

As vrtex of the dielectric the potential vortex will find fairly ideal conditions in air or in water. How should a vortex be detected, if it does not produce any effect? The classical measuring technique is here at its wits' end.

From the duality to the well-known eddy current and by means of observation in the previous chapters numerous properties of the potential vortex have been derived. But these are not all the properties. The mathematical calculation of the electric vortex field, that we want to turn to now, will reveal still further meaningful and highly interesting properties.

The observation is important, but it can't replace an exact calculation. A strictly mathematical derived result has occasionally more expressiveness than a whole book full of explanations. It will be a big help to derive and to discuss the field equation that all considerations are based on.

We facilitate the mathematical work by vector analysis. Therefore it is useful that we choose the differential form (equation 5.1 and 5.4) instead of the integral form (equations 3.1 and 3.2 resp. 3.8).



1. Ampère's law:

$$\mathrm{rot}\,\mathbf{H} = \mathbf{j} + \delta\mathbf{D}/\delta t \qquad (5.1)$$

with $\mathbf{H} = \mathbf{H}(\mathbf{r},t)$

and Ohm's law: $\mathbf{j} = \sigma \cdot \mathbf{E}$ (5.2)

dielectric displacement: $\mathbf{D} = \varepsilon \cdot \mathbf{E}$ (3.6)

relaxation time: $\tau_1 = \varepsilon/\sigma$ (5.3)

$$\boxed{\mathrm{rot}\,\mathbf{H} = \varepsilon \cdot (\mathbf{E}/\tau_1 + \delta\mathbf{E}/\delta t)} \qquad (5.1^*)$$

2. Faraday's law of induction (extended according to duality rules)

$$-\,\mathrm{rot}\,\mathbf{E} = \mathbf{B}/\tau_2 + \delta\mathbf{B}/\delta t \qquad (5.4)$$

with $\mathbf{E} = \mathbf{E}(\mathbf{r},t)$

and the flux density: $\mathbf{B} = \mu \cdot \mathbf{H}$ (3.5)

$$\boxed{-\,\mathrm{rot}\,\mathbf{E} = \mu \cdot (\mathbf{H}/\tau_2 + \delta\mathbf{H}/\delta t)} \qquad (5.4^*)$$

$$-\,\mathrm{rot}\,\mathrm{rot}\,\mathbf{E} = \mu \cdot (1/\tau_2) \cdot \mathrm{rot}\,\mathbf{H} + \mu \cdot \delta(\mathrm{rot}\,\mathbf{H})/\delta t \qquad (5.5)$$

insert equation 5.1*:

$$-\,\mathrm{rot}\,\mathrm{rot}\,\mathbf{E} = \mu \cdot \varepsilon \cdot (\mathbf{E}/\tau_1\tau_2 + (1/\tau_2) \cdot \delta\mathbf{E}/\delta t + {} + (1/\tau_1) \cdot \delta\mathbf{E}/\delta t + \delta^2\mathbf{E}/\delta t^2) \qquad (5.5^*)$$

$$-\,\mathrm{rot}\,\mathrm{rot}\,\mathbf{E} = \Delta\mathbf{E} - \mathrm{grad}\,\mathrm{div}\,\mathbf{E} = \Delta\mathbf{E}\,, \qquad (R5)$$

if: $\mathrm{div}\,\mathbf{E} = 0$ (3.7*)

abbreviation: $\mu \cdot \varepsilon = 1/c^2$ (5.6)

3. fundamental field equation:

$$\boxed{\underbrace{\Delta\mathbf{E}\cdot c^2}_{a} = \underbrace{\delta^2\mathbf{E}/\delta t^2}_{b} + \underbrace{(1/\tau_1)\cdot\delta\mathbf{E}/\delta t}_{c} + \underbrace{(1/\tau_2)\cdot\delta\mathbf{E}/\delta t}_{d} + \underbrace{\mathbf{E}/\tau_1\tau_2}_{e}} \qquad (5.7)$$

Fig. 5.1: Derivation of the fundamental field equation.

5.1 Fundamental field equation

We'll start from Ampere's law which provides a value for the current density at any point pace and this value corresponds to the vortex density of the magnetic field strength



$$\text{rot}\,\mathbf{H} = \mathbf{j} + \delta\mathbf{D}/\delta t \qquad (5.1)$$

We'll use Ohm's law: $\mathbf{j} = \sigma \cdot \mathbf{E}\,,$ (5.2)

the dielectric displacement: $\mathbf{D} = \varepsilon \cdot \mathbf{E}$ (3.6)

and the relaxation time: $\tau_1 = \varepsilon/\sigma\,,$ (5.3)

that indicates how fast the current eddies decay. So far we can fall back upon well-known relations.

The result is: $\boxed{\text{rot}\,\mathbf{H} = \varepsilon \cdot (\mathbf{E}/\tau_1 + \delta\mathbf{E}/\delta t)}$ (5.1*)

The new electric field vortices demand the introduction of a corresponding time constant tau$_2$ that should describe the decay of the potential vortices, as an extension. The extended Faraday law of induction now provides a potential density, that at any point of space corresponds to the vortex density of the electric field strength:



$$-\text{rot}\,\mathbf{E} = \mathbf{B}/\tau_2 + \delta\mathbf{B}/\delta t \qquad (5.4)$$

with the flux density $\mathbf{B} = \mu \cdot \mathbf{H}\,.$ (3.5)

The result fulfils the required duality to equation 5.1*: $\boxed{-\text{rot}\,\mathbf{E} = \mu \cdot (\mathbf{H}/\tau_2 + \delta\mathbf{H}/\delta t)}$ (5.4*)

If we again apply the curl to equation 5.4*

$$-\text{rot}\,\text{rot}\,\mathbf{E} = \mu \cdot (1/\tau_2) \cdot \text{rot}\,\mathbf{H} + \mu \cdot \delta(\text{rot}\,\mathbf{H})/\,\delta t \qquad (5.5)$$

and insert equation 5.1*, we obtain:

$$-\text{rot}\,\text{rot}\,\mathbf{E} = \mu \cdot \varepsilon \cdot (\mathbf{E}/\tau_1\tau_2 + (1/\tau_2) \cdot \delta\mathbf{E}/\delta t + (1/\tau_1) \cdot \delta\mathbf{E}/\delta t + \delta^2\mathbf{E}/\delta t^2) \qquad (5.5^*)$$

which according to the rules of vector analysis can still be further simplified: = rot rot E = $\Delta\mathbf{E}$ - grad div E , where we should remember that the divergence has to vanish (div E = O. fig. 3.2, equation 3.7), should the corresponding field vortex be inserted!

Furthermore the following well-known abbreviation can be inserted: $\mu \cdot \varepsilon = 1/c^2$ (5.6)

With that the relation with the speed of light c simplifies to the sought-for field equation:



$$\boxed{\underbrace{\Delta\mathbf{E} \cdot c^2}_{a} = \underbrace{\delta^2\mathbf{E}/\delta t^2}_{b} + \underbrace{(1/\tau_1) \cdot \delta\mathbf{E}/\delta t}_{c} + \underbrace{(1/\tau_2) \cdot \delta\mathbf{E}/\delta t}_{d} + \underbrace{\mathbf{E}/\tau_1\tau_2}_{e}} \qquad (5.7)$$

This equation describes the spatial (a) and temporal (b, c, d) distribution of a field vector. It describes the electromagnetic wave (a, b) with the influences that act damping. As dumping terms the well-known eddy current (c) and in addition the newly introduced potential vortex (d) appear.

Field vector: ψ = E, H, j, B or D

1. elliptic potential equation:
(stationary: $t \longrightarrow \infty$ resp. $\delta/\delta t = 0$)

$$\boxed{\underbrace{\Delta\psi \cdot c^2}_{a} = \underbrace{\psi/\tau_1\tau_2}_{e}} \tag{5.8}$$

2. hyperbolic equation:
(undamped wave equation)

$$\boxed{\underbrace{\Delta\psi \cdot c^2}_{a} = \underbrace{\delta^2\psi/\delta t^2}_{b}} \tag{5.9}$$

3. parabolic equation:
(vortex equation)

$$\boxed{\underbrace{\Delta\psi \cdot c^2}_{a} = \underbrace{(1/\tau) \cdot \delta\psi/\delta t}_{c/d}} \tag{5.10}$$

decay time of the eddy currents =
relaxation time: $\tau_1 = \varepsilon/\sigma$ (5.3)

decay time of the potential vortices =
relaxation time: $\tau_2 \sim \mu \cdot \sigma$ (5.11)

Fig. 5.2: mathematically divisible individual cases.

5.2 Mathematical interpretation of the fundamental field equation

Every specialist will be surprised to find the Poisson equation (a, e) again as a term in the wave equation. This circumstance forces a completely new interpretation of stationary fields upon us. The new damping term, that is formed by the potential vortices (d), is standing in between.

Let us start with a mathematical analysis. We have applied the curl to equation 5.4*, then inserted equation 5.1* and obtained a determining equation for the electric field strength E. Of course we could as well have applied the curl to equation 5.1* and inserted equation 5.4*. This would have resulted in the determining equation for the magnetic field strength H.

If we insert Ohm's law (5.2) and cancel down the specific conductivity, or we put in the relations of material (3.5) or (3.6) and cancel down by u respectively ε, then the field equation can likewise be written down for the current density j, for the induction B or for the dielectric displacement D.

It just is phenomenal that at all events equation 5.7 doesn't change its form at all. The field vector is thus arbitrarily interchangeable! This circumstance is the foundation for the claim of this field equation to be called fundamental.

It does make sense to introduce a neutral descriptive vector ψ as a substitute for the possible field factors E, H, j, B or D.

The fundamental field equation 5.7 consists of three different types of partial differential equations: a hyperbolic (b), a parabolic (c and d) and an elliptic (e) type. On the left-hand side each time the Laplace operator (a) is found which describes the spatial distribution of the field factor.

The potential equation of the elliptic type (e) is known as Poisson equation. It describes the stationary borderline case of a worn off temporal process ($t \rightarrow \infty$, resp. $\delta/\delta t = 0$).

With this equation potentials and voltages can be calculated exactly like stationary electric currents (5.8).

The hyperbolic equation (b). known as wave equation, shows a second derivative to time. which expresses an invariance with regard to time reversal; or stated otherwise: the direction of the time axis can be reversed by a change of sign of t, without this having an influence on the course of frequency. Wave processes hence are reversible. Equation 5.7 makes clear that a wave without damping by no means can exist in nature. For that both time constants (τ_1 and τ_2) would have to have an infinite value, which is not realizable in practice. Seen purely theoretical, undamped waves could withdraw themselves from our measuring technique (5.9).

Both vortex equations of the parabolic type (c and d) only show a first derivative to time. With that they are no longer invariant with regard to time reversal. The processes of the formation and the decay of vortices, the so-called diffusion, are as a consequence irreversible. Seen this way it is understandable that the process of falling apart of the vortex, where the vortex releases its stored energy as heat e.g. in form of eddy losses, can not take place in reverse. This irreversible process of diffusion in the strict thermodynamic sense increases the entropy of the system (5.10).

Because it poses an useful simplification for mathematical calculations, often the different types of equations are treated isolated from each other. But the physical reality looks different.

field vector: ψ = E, H, j, B or D

1. Borderline case: no conductivity (vacuum)
$(\sigma = 0; \quad 1/\tau_1 = \sigma/\varepsilon = 0)$:

$$\underbrace{\Delta\psi \cdot c^2}_{a} = \underbrace{\delta^2\psi/\delta t^2}_{b} + \underbrace{(1/\tau_2)\cdot \delta\psi/\delta t}_{d}$$

(5.12)

(damping by potential vortices)

2. Borderline case: ideal conductivity (superconductor)
$(1/\sigma = 0; \quad 1/\tau_2 = 0)$:

$$\underbrace{\Delta\psi \cdot c^2}_{a} = \underbrace{\delta^2\psi/\delta t^2}_{b} + \underbrace{(1/\tau_1)\cdot \delta\psi/\delta t}_{c}$$

(5.12*)

(damping by eddy currents)

3. Diffusion equation

$$\underbrace{\Delta\psi \cdot c^2}_{a} = \underbrace{(1/\tau)\cdot \delta\psi/\delta t}_{c/d} + \underbrace{\psi/\tau_1\tau_2}_{e}$$

(5.12**)

(vortex)

Fig. 5.3: Two borderline cases of the damping of waves and the diffusion equation for the decay of vortices

5.3 Physical interpretation of the fundamental field equation

In nature the different types of equations always occur in a combined manner.

1. Let's take the concrete case of the particle-free vacuum. Here the specific conductivity is zero. The relaxation time constant $\tau_1 = \varepsilon/\sigma$ responsible for the decay of vortices tends towards infinity according to equation 5.3 and the terms (c) and (e) are cancelled from the field equation 5.7. What remains is the by potential vortices (d) damped wave equation (b) (equation 5.12).

2. The reversed case (with $\tau_2 \longrightarrow \infty$) will consequently occur in materials without resistance, super conducting materials. We now are dealing with the well-known case of the wave damped by eddy currents (equation 5.12*).

Virtually all in nature existing materials however don't fulfil these boundary conditions, from which it follows that both damping terms always occur together and in addition the stationary term (e) becomes active.
It is true that every antenna demonstrates that the electromagnetic wave is convertible in high-frequency alternating currents and voltages, which then are amplified in the receiver. But until this fundamental equation was written down it however was not understood that this transition takes place by means of a vortex. Used are either antennas from well conducting material, or wave guides and horn radiators, which only have a minimal conductivity, because they are filled with air. Actually the wave can be converted in two dual ways; by means of the rolling up to current eddies or to potential vortices (fig. 1.4). Now we finally are capable to explain, why wave guides make possible a better degree of effectiveness: Owing to the concentration effect of the potential vortex the HF-power is bound in the inside and not emitted until the antenna is reached as happens for a wire for reason of the skin effect.
Therefore, physically, one has to imagine this relation, which describes the transition of an electromagnetic wave into a vortex, in the way that the wave spontaneously can roll up to a vortex in case it is disturbed from the outside. The more vortices are generated, the larger consequently is the damping of the wave (equations 5.12 and 5.12*).

3. The life span of the vortices is limited and is determined by the electric conductivity. The at first stored vortices decay with their respective time constant τ. This process is described by the diffusion equation 5.12**. The final stage of the decaying vortices finally is described by the Poisson equation (a, e: equation 5.8).

If the vortex falls apart, it converts the in the vortex stored energy in heat. These processes are known from the eddy current. We speak of heating losses, that the stationary currents cause in the conductor material.
But new is the concept that such vortex phenomena can occur as dielectric losses in capacitors or in the air. The microwave oven or induction welding are good examples of this.



Fig. 5.4: The dependency on height of the ionisation in the ionosphere for medium latitudes .<i>

left curve: for a minimum of sun spots

right curve: for a maximum of sun spots

<i>: H.L. Konig: Unsichtbare Umwelt (Wetterfuhligkeit), 5. Aufl., Bild 6, Seite 11, Verlag Moos & Partner Milnchen, ISBN 3-89164-058-7

5.4 Phenomenological interpretation of the fundamental field equation

How does a damping by vortices take effect in practice? First of all we notice that the reception of broadcastings gets worse. "The information signal is neglectable regarding the noise" explains the radio engineer and means, the number of vortices increases at the expense of the wave intensity.
Why, does the pupil ask, is it so cold in space? There the sun shines day and night and in addition much more intensely than on earth! The correct answer would have to read that because of the extremely small conductivity no diffusion process can take place. We owe the warmth on our earth solely the here taking place decay of vortices. Responsible is the conductivity of the atmosphere.
In 60 km to 500 km height over the earth's surface, the region which is called the ionosphere, the gases predominantly exist in ionized form. There a very good conductivity prevails and eddy current losses are the result. Correspondingly high are the measurable temperatures. Besides the diffusion process the eddy currents carry out a damping of the cosmic radiation. We say the sunlight is filtered and reduced to a for nature bearable intensity.
But not all frequencies are damped in the same way (fig. 2.8). We observe a blue shift, if we look into the actually black sky. The blue sky doesn't show any spots or clouds. The reason is to be sought in the skin effect of the eddy currents, which strive outwards. Since no edge of a conductor is present here, no skin can form. The vortices spread evenly over the ionosphere.
The potential vortex however is able to structure. It merely needs a bad conductivity and this it finds in lower heights between 1 km and 10 km. It damps the wave and with that also the light, for which reason we say it becomes darker, the sun disappears behind clouds.

The clouds well visibly form the discussed vortex balls and vortex strings. Clouds can form virtually from the nowhere during intense solar irradiation, i.e. the waves can roll up to vortices. But as a rule this takes place above the oceans. Here also the phenomenon of transport has an effect. Because of the high dielectricity the water surface favours the formation of potential vortices. So the vortices bind individual water molecules and carry them away. If a diffusion process takes place, in which the vortex decays, then it rains.
This can happen in two different ways:
1. Either the conductivity increases. If for instance during intense solar irradiation air ions form, the sun is able to break up clouds and fog. Or when the air is raised in higher layers with better conductivity, because a mountain forces this, then it rains at the mountain edge.
2. For potential vortices the electric field is standing perpendicular to them. If at one point an exceptionally lot of vortices join together, which let the cloud appear particularly dark to black, then the danger exists that the ionization field strength for air is reached, in which case a conductive air channel forms along which the stored up charges discharge. Also lightning is a diffusion process, in which potential vortices decay and rain can form.
In connection with the electromagnetic environmental compatibility great importance is attributed in particular to the storage and the decay of electric vortices. There not only is an academic-scientific interest in the question, how many potential vortices are generated, how many are stored and how many decay, if we make a telephone call with a handy, if we are staying under a high-tension line or if we are eating food, which has been heated up in a microwave oven. The necessary mathematical description is provided by the fundamental field equation 5.7.


force of attraction
Proton p⁺
Elektron e⁻


atomic-
nucleus
atomic hull

Fig. 5.5: The structure of atoms in the view of the fundamental field equation

condition for equilibrium: $$\boxed{\tau_1 = \tau_2} \qquad (5.13)$$

5.5 Atomistic interpretation of the fundamental field equation

Let's again turn to the smaller, the atomistic dimensions. Here positively charged protons and negatively charged electrons are found. Both are matter particles and that means that seen from the outside both have the identical swirl direction. For reason of the unequal charge conditions they attract each other mutually and according to fig. 4.9 rotate around a common centre of mass as differently heavy pair. Chemists say: "the light electron orbits the heavy atomic nucleus". With small balls they try to explain the atomic structure.
But the model is no good: it contradicts causality in the most elementary manner. We are dealing with the problem that according to the laws of electrodynamics a centripetally accelerated electron should emit electromagnetic waves and continuously lose energy, to eventually plunge into the nucleus.
Our experience teaches that this fortunately is not true - and Niels Bohr in order to save his model of the atom was forced to annul the laws of physics with a postulate founded in arbitrariness.
Actually this state only exists for a very short time and then something unbelievable happens: the electron can't be distinguished as an individual particle anymore. "It is smeared over the electron orbit" do certain people say; "it possesses a dual nature" says Heisenberg. Besides the corpuscular nature the electron should in case of its "second nature" form a matter wave, "the position of the electron is to be looked at as a resonance which is the maximum of a probability density", do explain us de Broglie and Schrodinger.

These explanations can hardly convince. If the electron loses its particle nature in its second nature, then it also will lose its typical properties, like for instance its mass and its charge. but this is not the case.
THE vortex theory provides clear and causal answers: if the electron were a ball it continuosly would lose energy, therefore another configuration forms that does not know this problem. Here the phenomenon of transport takes an effect. The electron opens its vortex centre and takes the tiny protons and neutrons as atomic nucleus up into itself. The Bohr electron orbit with that is not a path anymore, but is occupied by the whole particle as spherical shell. This is confirmed by the not understood measurements exactly like the photos of individual atoms with the scanning electron microscope.
But now an electron does in its inside have the opposite swirl direction as the proton seen from the outside. As a consequence a force of repulsion will occur, which can be interpreted as the to the outside directed current eddy, the force of attraction for reason of the opposite charge works in the opposite direction and can be interpreted as the potential vortex effect.
If both vortices are equally powerful: $\tau_1 = \tau_2$ (5.13)
or if both forces are balanced, as one usually would say, then the object which we call an atom is in a stable state.
It probably will be a result of the incompatible swirl direction, why a very big distance results, if the electron becomes an enveloping electron. On such a shell not too many electrons have room. Because of the rotation of their own, the electron spin, they form a magnetic dipole moment, which leads to a magnetic attraction of two electrons if they put their spin axis antiparallelly.
As a "frictionless" against one another rotating pair they form two half-shells of a sphere and with that occupy the innermost shell in the hull of an atom. If the positive charge of the nucleus is still not balanced with that, then other electrons is left only the possibility to form another shell. Now this next electron takes the whole object up into itself. The new shell lies further on the outside and naturally offers room to more as only two vortices.



approach:

$$\boxed{\mathbf{E}(\mathbf{r},t) = \psi(\mathbf{r},t) \cdot e^{-\omega t}} \qquad (5.17)$$

with

$$\omega = 1/\tau = (1/\tau_1 + 1/\tau_2)/2 \qquad (5.18)$$

we insert the approach 5.17 and its derivations:

$$\delta\mathbf{E}/\delta t = -\,\omega \cdot \psi \cdot e^{-\omega t} + (\delta\psi/\delta t) \cdot e^{-\omega t} \qquad (5.17^*)$$

$$\delta^2\mathbf{E}/\delta t^2 = \omega^2 \cdot \psi \cdot e^{-\omega t} - 2\omega \cdot (\delta\psi/\delta t) \cdot e^{-\omega t} + (\delta^2\psi/\delta t^2) \cdot e^{-\omega t} \qquad (5.17^{**})$$

into the fundamental field equation 5.7:

$$\boxed{\Delta\mathbf{E} \cdot c^2 = \delta^2\mathbf{E}/\delta t^2 + (1/\tau_1) \cdot \delta\mathbf{E}/\delta t + (1/\tau_2) \cdot \delta\mathbf{E}/\delta t + \mathbf{E}/\tau_1\tau_2}$$

and divide by $e^{-\omega t}$:

(5.19)

$$\begin{aligned} \Delta\psi \cdot c^2 = {} & \psi/\tau_1\tau_2 && \text{(a) = (e)} \\ & -\,\omega \cdot \psi \cdot (1/\tau_1 + 1/\tau_2) && \text{(c, d)} \\ & +\,(1/\tau_1 + 1/\tau_2) \cdot \delta\psi/\delta t && \text{(c, d)} \\ & +\,\omega^2 \cdot \psi - 2\omega\delta\psi/\delta t + \delta^2\psi/\delta t^2 && \text{(b)} \end{aligned}$$

insert the frequency according to equation 5.18:

(5.19*)

$$\begin{aligned} \Delta\psi \cdot c^2 = {} & \psi/\tau_1\tau_2 && \text{(a) = (e)} \\ & -\,(\psi/2) \cdot (1/\tau_1 + 1/\tau_2)^2 && \text{(c, d)} \\ & +\,(1/\tau_1 + 1/\tau_2) \cdot \delta\psi/\delta t && \text{(c, d)} \\ & +\,(\psi/4) \cdot (1/\tau_1 + 1/\tau_2)^2 && \text{(b)} \\ & -\,(1/\tau_1 + 1/\tau_2) \cdot \delta\psi/\delta t + \delta^2\psi/\delta t^2 && \text{(b)} \end{aligned}$$

summarized with equation 5.18:

$$\boxed{\Delta\psi \cdot c^2 = \psi/\tau_1\tau_2 - \omega^2 \cdot \psi + \delta^2\psi/\delta t^2} \qquad (5.20)$$

Fig. 5.6: Derivation of the Klein-Gordon equation (5.20) from the fundamental field equation (5.7)

5.6 Derivation of the Klein-Gordon equation

The valid model of the atom today still raises problems of causality, as has been explained. An improvement was provided by an equation, which was proposed by the mathematician Schrodinger 1926 as a model description. This equation in this way missed the physical root, but it nevertheless got international acknowledgment, because it could be confirmed experimentally. Looking backwards from the result then the physical interpretation of the probability density of the resonance of the waves could be pushed afterwards.

$$i \cdot \hbar \cdot \delta\psi/\delta t = U \cdot \psi - (\hbar^2/2m) \cdot \Delta\psi \quad (5.14)$$

The Schrodinger equation is valid for matter fields (of mass m), while the interaction with a outside force field the energy U indicates. It can be won from a wave equation by conversion, which possibly is the reason why it usually is called a wave equation, although in reality it is a diffusion equation, so a vortex equation!
For the derivation Schrodinger gives the approach of a harmonic oscillation for the complex wave function ψ:

$$\boxed{\psi(\mathbf{r},t) = \phi(\mathbf{r}) \cdot e^{-i\omega t}} \quad (5.15)$$

if the entire time dependency can be described by one frequency $f = W/h$ (de-Broglie relation):

$$\omega = 2\pi f = W \cdot 2\pi/h = W/\hbar \quad (5.16)$$

The high-put goal is: if the structure of the atom is determined by the fundamental field equation 5.7 then one should be able to derive the experimentally secured Schrodinger equation and to mathematically describe the discussed special case. Also we select at first an approach periodic in time:

$$\boxed{\mathbf{E}(\mathbf{r},t) = \psi(\mathbf{r},t) \cdot e^{-\omega t}} \quad (5.17)$$

with

$$\omega = 1/\tau = (1/\tau_1 + 1/\tau_2)/2 \ . \quad (5.18)$$

We insert the approach 5.17 and its derivations into the field equation 5.7 and divide by the damping term e^{-wt}:

$$\Delta\psi \cdot c^2 = \psi/\tau_1\tau_2 - \omega \cdot \psi \cdot (1/\tau_1 + 1/\tau_2) + (1/\tau_1 + 1/\tau_2) \cdot (\delta\psi/\delta t) + \\ + \omega^2 \cdot \psi - 2\omega\, \delta\psi/\delta t + \delta^2\psi/\delta t^2 \quad (5.19)$$

If as the next step the angular frequency according to equation 5.18 is inserted, then summarized the provisional intermediate result results:

$$\boxed{\Delta\psi \cdot c^2 = \psi/\tau_1\tau_2 - \omega^2 \cdot \psi + \delta^2\psi/\delta t^2} \quad (5.20)$$

The derived equation 5.20 represents formally seen the Klein-Gordon equation, which is used for the description of matter waves in quantum mechanics and which particularly in the quantum field theory (e.g. mesons) plays an important role. Even if it often is regarded as the relativistic invariant generalization of the Schrodinger equation, it at a closer look is incompatible with this equation and as "genuine" wave equation it is not capable of treating vortex problems correctly, like e.g. the with the Schrodinger equation calculable quantization of our microcosm.



$$\boxed{\text{Schrödinger approach}\quad \psi(\mathbf{r},t) = \phi(\mathbf{r}) \cdot e^{-i\omega t}} \tag{5.15}$$

with: f = W/h; de-Broglie relation:

$$\omega = 2\pi f = W \cdot 2\pi/h = W/\hbar \tag{5.16}$$

the derivation:

$$\delta\psi/\delta t = -i\,\omega \cdot \psi$$

rewritten for ψ:

$$\psi = (i/\omega) \cdot \delta\psi/\delta t \tag{5.21}$$

2. derivation:

$$\delta^2\psi/\delta t^2 = -i\,\omega \cdot \delta\psi/\delta t \tag{5.22}$$

inserted in equation 5.20:

$$\boxed{\Delta\psi \cdot c^2 = \psi/\tau_1\tau_2 - 2\,i\,\omega \cdot \delta\psi/\delta t} \tag{5.23}$$

= sought-for Schrödinger equation (usual notation):

$$\boxed{i \cdot \hbar \cdot \delta\psi/\delta t = U \cdot \psi - (\hbar^2/2m) \cdot \Delta\psi} \tag{5.14}$$

comparison of coefficients is needed:
Einstein relation (with the speed of light c):

with (5.16): $$W = m \cdot c^2 = \omega \cdot \hbar \tag{5.24}$$

coefficient of the imaginary part: $$-2\,i\,\omega = 2(\omega/i) = 2mc^2/i\hbar \tag{5.25}$$

comparison of coefficients for the real part: $$\boxed{1/\tau_1\tau_2 c^2 \overset{!}{=} U \cdot 2m/\hbar^2} \tag{5.26}$$

kinetic energy of a particle moving with the speed v:

$$\tfrac{1}{2} \cdot m \cdot v^2 = W - U \tag{5.27}$$

v = group velocity of the matter wave:

$$v = hf/mc = \hbar\omega/mc \tag{5.28}$$

Eq.5.27: $$U = W - \tfrac{1}{2} \cdot m \cdot (\hbar\omega/mc)^2 \tag{5.27*}$$

Eq.5.24: $W = \omega \cdot \hbar$; $(\hbar\omega/mc) = c$; resp.: $m/\hbar = \omega/c^2$

In eq.5.27* the sought-for coefficient reads (according to eq. 5.26):

$$U \cdot 2m/\hbar^2 = 2\omega/c^2\hbar \cdot [\omega \cdot \hbar - \tfrac{1}{2} \cdot m \cdot c^2]$$

$$= 2\omega/c^2\hbar \cdot [\omega \cdot \hbar - \tfrac{1}{2} \cdot \omega \cdot \hbar] = \underline{\underline{(\omega/c)^2}} \tag{5.29}$$

Fig. 5.7: Derivation of the time dependent Schrodinger equation

5.7 Derivation of the time dependent Schrodinger equation

With the Schrodinger approach 5.15 and its derivations the derivation is continued:

$$\boxed{\psi(\mathbf{r},t) = \phi(\mathbf{r}) \cdot e^{-i\omega t}} \;, \qquad (5.15)$$

$$\delta\psi/\delta t = -i\omega \cdot \psi \,, \quad \text{bzw.} \quad \psi = (i/\omega) \cdot \delta\psi/\delta t \qquad (5.21)$$

$$\delta^2\psi/\delta t^2 = -i\omega \cdot \delta\psi/\delta t \qquad (5.22)$$

The for a harmonic oscillation won relations according to equation 5.21 and 5.22 are now inserted into equation 5.20:

$$\boxed{\Delta\psi \cdot c^2 = \psi/\tau_1\tau_2 - 2i\omega \cdot \delta\psi/\delta t}$$

This is already the sought-for Schrodinger equation, as we will see in a moment, when we have analysed the coefficients. Because, besides equation 5.16 for the total energy W, also the Einstein relation is valid (with the speed of light c):

$W = m \cdot c^2 = \omega \cdot \hbar$, (5.24)

we can replace the coefficients of the imaginary part by:

$2(\omega/i) = 2mc^2/i\hbar$ (5.25)

To achieve that equation 5.23, as required, follows from the Schrodinger equation 5.14, a comparison of coefficients is carried out for the real part:

$$\boxed{1/\tau_1\tau_2 c^2 \overset{!}{=} U \cdot 2m/\hbar^2} \quad (5.26)$$

If thc kinetic energy of a particle moving with the speed v is:

$\tfrac{1}{2} \cdot m \cdot v^2 = W - U$, (5.27)

then acccording to De Broglie this particle has the wavelength h/mv. The consideration of the particle as matter wave demands an agreement with the wave length c/f of an electromagnetic wave (with the phase velocity c). The particle hence has the speed v, which corresponds with the group velocity of the matter wave:

$$v = hf/mc = \hbar\omega/mc \;, \qquad (5.28)$$

if we insert v into equation 5.27 :

$U = W - \tfrac{1}{2} \cdot m \cdot (\hbar\omega/mc)^2$ (5.27*)

According to equation 5.24 on the one hand the total energy is $W = w \bullet h$ and on the other hand the relation 5.28 gives $(\hbar\omega/mc) = c$ resp.: $m/\hbar = \omega/c^2$

Inserted into equation 5.27* the sought-for coefficient reads (according to eq. 5.26):

$$\begin{aligned} U \cdot 2m/\hbar^2 &= 2\omega/c^2\hbar \cdot [\omega \cdot \hbar - \tfrac{1}{2} \cdot m \cdot c^2] \\ &= 2\omega/c^2\hbar \cdot [\omega \cdot \hbar - \tfrac{1}{2} \cdot \omega \cdot \hbar] = \underline{(\omega/c)^2} \qquad (5.29) \end{aligned}$$



comparison of coefficients 5.26 is fulfilled if:

$$1/\tau_1\tau_2 c^2 \overset{!}{=} U \cdot 2m/\hbar^2 = (\omega/c)^2 \tag{5.30}$$

the angular frequency is given by equation 5.18. Therefore has to be valid:

$$1/\tau_1\tau_2 \overset{!}{=} \tfrac{1}{4} (1/\tau_1 + 1/\tau_2)^2 \tag{5.31}$$

resp.:

$$\sqrt{1/\tau_1\tau_2} \overset{!}{=} \tfrac{1}{2} (1/\tau_1 + 1/\tau_2) \tag{5.32}$$

arithmetic average = geometric average, if:

$$1/\tau_1 = 1/\tau_2 \text{ and: } \boxed{\tau_1 = \tau_2} \tag{5.13}$$

is valid. Eq. 5.23 is divided by c^2 and eqs. 5.30 and 5.25 are inserted:

$$\boxed{\Delta\psi = U \cdot \psi \cdot (2m/\hbar^2) + (2m/i\hbar) \cdot \delta\psi/\delta t} \tag{5.14*}$$

= *time dependent Schrödinger equation* 5.14.

replace $\delta\psi/\delta t$ acc. to eq. 5.21 with $\omega = W/\hbar$ acc.to eq. 5.24:

$$\Delta\psi = U \cdot \psi \cdot (2m/\hbar^2) + (2m/i\hbar) \cdot \psi \cdot (-i) \cdot W/\hbar \tag{5.33}$$

Schrödinger approach 5.15 for the function of position $\phi(\mathbf{r})$:

$$\Delta\phi = (U 2m/\hbar^2 - W \cdot 2m/\hbar^2) \cdot \phi \tag{5.34}$$

$$\boxed{\Delta\phi = -2m/\hbar^2 (W - U) \cdot \phi} \tag{5.35}$$

= *time independent Schrödinger equation.*

Fig. 5.8: Derivation of the time independent Schrodinger equation

5.8 Derivation of the time independent Schrodinger equation

The goal is reached if we are capable to fulfil the comparison of coefficients 5.26:

$$U \cdot 2m/\hbar^2 \overset{!}{=} (\omega/c)^2 = 1/\tau_1\tau_2 c^2 \qquad (5.30)$$

The angular frequency w is given by equation 5.18. Therefore has to be valid:

$$\tfrac{1}{4}\,(1/\tau_1 + 1/\tau_2)^2 \overset{!}{=} 1/\tau_1\tau_2 \quad (5.31)$$

$$\tfrac{1}{2} \cdot (1/\tau_1 + 1/\tau_1) \overset{!}{=} \sqrt{1/\tau_1\tau_2} \quad (5.32)$$

As is well-known the arithmetic and the geometric average only correspond in case the variables are identical. In this case, as already required in equation 5.13:

$$\tau_1 = \tau_2 \,. \quad (5.13)$$

has to hold.
From this we can draw the conclusion that the Schrodinger equation is just applicable to the described special case (according to eq. 5.13), in which the eddy current, which tries to increase the particle or its circular path and the potential vortex, which keeps the atoms together and also is responsible for the stability of the elementary particles, are of identical order of magnitude.

As a check equation 5.23 is divided by c^2 and equations 5.30 and 5.25 are inserted:

$$\boxed{\Delta\psi = U \cdot \psi \cdot (2m/\hbar^2) + (2m/i\hbar) \cdot \delta\psi/\delta t} \quad (5.14^*)$$

This is the time dependent Schrodinger equation 5.14 resolved for $\Delta\psi$.

Next we replace $\delta\psi/\delta t$ according to equation 5.21 with $\omega = W/\hbar$ acc. to equation 5.24:

$$\Delta\psi = U \cdot \psi \cdot (2m/\hbar^2) + (2m/i\hbar) \cdot \psi \cdot (-i) \cdot W/\hbar \quad (5.33)$$

If we separate the space variables $\phi(\mathbf{r})$ from time by the Schrodinger approach 5.15 we obtain:

$$\Delta\phi = (U\,2m/\hbar^2 - W \cdot 2m/\hbar^2) \cdot \phi \quad (5.34)$$

This quation 5.34 for the function of space coordinates $\phi(\mathbf{r})$ is the time independent Schrodinger equation:

$$\boxed{\Delta\phi = -2m/\hbar^2\,(W - U) \cdot \phi} \quad (5.35)$$

The solutions of this equation which fulfil all the conditions that can be asked of them (of finiteness, steadiness, uniqueness etc.), are called eigenfunctions. The existence of corresponding discrete values of the energy W, also called eigenvalues of the Schrodinger equation, are the mathematical reason for the different quantum postulates.


1s m=0
2p m=1
2p m=0
3d m=2
3d m=1
3d m=0
4f m=3
4f m=2
4f m=1
3s m=0
2s m=0
3p m=1
3p m=0
4d m=2
4d m=1
4d m=0
5f m=2
5f m=1
5f m=0
4p m=1

Fig. 5.9: Photographs of models of the probability densities for different states of the hydrogen atom. The densities are symmetrical if rotated around the vertical axis<i>

taken from:

<i>: U. Gradmann/H. Wolter: Grundlagen der Atomphysik, AVG, Frankfurt a. M. 1971, P. 190.

5.9 Interpretation of the Schrodinger equation

The interpretation of the Schrodinger equation is still disputed among physicists, because the concept of wave packets contradicts the corpuscular nature of the elementary particles. Further the difficulty is added that wave packets at a closer look never are connected, run apart more or less fast, and really nothing can hinder them doing that. But for a particle the connection represents a physical fact. Then there can be no talk of causality anymore. The monocausal division into two different levels of reality, in a space-timely localization and in an energetic description, does not represent a solution but rather the opposite, the abolition of the so-called dual nature. As has been shown, the potential vortex is able to achieve this with the help of its concentration effect.
But from the introduction of this new field phenomenon arises the necessity to interpret the causes for the calculable and with measuring techniques testable solutions of the Schrodinger equation in a new way. Laws of nature do not know a possibility to choose! If they have been accepted as correct, they necessarily have to be applied.

Three hundred years ago the scholars had an argument, whether a division of physical pheomena, like Newton had proposed it, would be allowed to afterwards investigate them in the laboratory individually and isolated from other influences or if one better should proceed in an integrated manner, like for instance Descartes with his cartesian vortex theory. He imagined the celestial bodies floating in ethereal vortices. One absolutely was aware that the whole had to be more than the sum of every single realizaton, but the since Demokrit discussed vortex idea had to make room for the overwhelming successes of the method of Newton. And this idea after 2100 years was stamped, to in the meantime almost have fallen into oblivion.
Today, where this recipe for success in many areas already hits the limits of the physical possibilities, we should remember the teachings of the ancients and take up again the vortex idea It of course is true that only details are calculable mathematically and that nature, the big whole, stays incalculable, wherein problems can be seen.
If we consider the fundamental field equation 5.7, we find confirmed that actually no mathematician is capable to give a generally valid solution for this four-dimensional partial differential equation. Only restrictive special cases for a harmonic excitation or for certain spatial boundary conditions are calculable. The derived Schrodinger equation is such a case and for us particularly interesting, because it is an eigenvalue equation. The eigenvalues describe in a mathematical manner the with measuring techniques testable structures of the potential vortex .
Other eigenvalue equations are also derivable, like the Klein-Gordon equation or the Lionville equation, which is applied successfully in chaos theories. So our view opens, if chaotic systems like turbulences can be calculated as special cases of the same field equation and should be derivable from this equation.
The in pictures recorded and published structures, which at night should have come into being in corn fields, often look like the eigenvalues of a corresponding equation. The ripe ears thereby lie in clean vortex structures flat on the soil. Possibly potential vortices have charged the ears to such high field strength values that they have been pulled to the soil by the Coulomb forces.

Consequences resulting from the derivation of the Schrodinger equation from the fundamental field equation 5.7:

1. *Any experiment which confirms the Schrödinger equation is with that able to confirm at the same time the existence of the newly discovered potential vortex and the correctness of the field-theoretical approach.*

2. *Properties of the atomic hull and of the atomic nucleus, which can be described with the Schrödinger equation, can as of now be interpreted as an electromagnetic phenomenon.*

3. *There exist no particles or wave packets from matter waves, but only configurations consisting of potential vortices and current eddies.*

4. *There exists no matter! What we call matter is nothing but an electromagnetic state of oscillation of empty space.*

The relation between the energy of oscillation and the mass is described by the relation named after Albert Einstein

$$E = mc^2 \quad . \qquad (6.1 = 5.24)$$

Fig. 6.1: Derivation of the Schrodinger equation, power of proof and consequences

6. Theory of objectivity

6.1 Proof

A new theory only has chances on acknowledgment if it is provable. For that physical phenomena in the sense of the new theory are calculated and independently of this experiments are being carried out. If the calculations are confirmed by reproducible measurement results, then with that the correctness of the approach is proven.
In the here presented case we have chosen the field-theoretical approach instead of the usual quantum physical approach. As a consequence of this we had found as a new phenomenon the vortex of the electric field. With regard to the normally used Maxwell theory this resulted in changed field equations in a dual formulation. If both equations, each of which describes a source-free vortex field, are inserted into each other the result is an only in time and space formulated, generally valid and hence fundamental field equation (5.7, fig. 5.1).
This equation has many special cases; one of them, the Schrodinger equation, could be derived by using an approach which was harmonic in time. We renounced to give special solutions of the Schrodinger equation, because these are printed in numerous text books. On the other hand experiments are known, which are capable to confirm the theoretical solutions and thus to prove the Schrodinger equation. The eigenvalues of the equation describe for instance the shell-shaped structure of the atoms with the by Niels Bohr given radii.
Now this already proven equation was derived from the new field-theoretical approach. Thus for the special case, the area where the Schrodinger equation is valid, the new theory can be said to be proven (fig. 6.1).
We still are not content with that and put another stone on top: we will calculate the quantum properties of the elementary particles for ourselves. These until now have only been measured. Today is merely sought for symmetries and for models of explanation, like e.g. the quark-hypothesis. From a calculation science is miles and miles away. We will compare the calculation results with the measurement values. Then everyone can check and compare for him or herself.
The conditions in an elementary particle are completely different. Here it concerns the vortex itself, whereas the model of the atom merely describes vortex properties, so-called actions at a distance. The differences in size and distances for an atom lie more than five powers of ten over those of a particle!
Here a new problem of causality comes to light, at which we now must have a critical look: the question of the by Einstein postulated constancy and universality of the speed of light. Seen from a relativistic and subjective point of view of an observer, Einstein by all means may be right. But may such a theory be generalized? How are the measurements concerning the speed of light and the relativity of space and time to be judged when looking at them objectively?
The current measurements of speeds faster than light speak a clear language and represent a challenge (fig. 3.1, violation of the principle of causality no. 5).

The electron as a spherical capacitor (see fig. 4.3):



with circumference

$U = 2\pi r \sim c$

is valid:

$$\boxed{r \sim c} \qquad (6.2)$$

field theoretical approach (vortex particles):
The amount of energy bound in the inside of the particle is identical with the free and measurable amount of energy on the outside of the particle.

(If the number of particles is left unchanged):
In an isolated system the sum of the energy is constant

(particle = electromagnetic vortex)
Energy is a state description of electromagnetism.

Fig. 6.2: Derivation of the law of conservation of energy

6.2 Law of conservation of energy

Let the starting-point for our considerations be the electromagnetic wave in a particle-free vacuum. Here no vortices appear, so that the plane wave can propagate undamped with the speed of light, and in this way a transport of energy takes place. Electric and magnetic energy each are the same magnitude.

Let's now imagine the symmetry is disturbed as the wave is "slowed down" on one side. As a possible result the wave rolls up to a spherical vortex.

As we will see such a process is possible, for instance at impact on a strong field. Thus part of the energy is bound in the inside. This part from now on withdraws itself from every possibility to measure it. We can only measure the second part of the field energy, with which the particle interacts with its neighbourhood.

We can assume that:

The amount of energy bound in the inside of the particle is identical with the free and measurable amount of energy on the outside of the particle.

The same energy W_e = 0,51 MeV, we attribute to the electron for reason of its mass with the help of the Einstein relation (6.1), is also bound in its inside. This conclusion is also applicable to other elementary particles and with that to all matter.

We here again recognize the principle of the duality between the to the outside striving eddy current in the inside of the elementary vortex and the concentrating potential vortex on the outside. Thus also seen energetically both are of the same magnitude. Whereas in the case of the electromagnetic wave it concerns a symmetrical oscillation around "zero", by the process of quantization, by the rolling up to a spherical vortex, there forms an energetic state of space different from zero. The order of magnitude is determined by the number of elementary vortices, of which the particles and all matter consist.

Anti-matter forms the opposite energetic state and this again is for the particles of matter available in their inside in a bound form.

As long as we do not artificially produce new elementary vortices and thus keep the number of available vortices constant, the energetic state will not change, or as it is formulated in text books:

In an isolated system the sum of the energy is constant.

THE law of conservation of energy is not an axiom, but follows without compulsion from the vortex theory. It is not elementary, but a consistently derivable consequence of the field-theoretical approach, according to which solely the field acts as cause for all other physical phenomena, also for the conservation of energy! Because the cause of it is the electromagnetic field, the following has to hold:

Energy is a state description of electromagnetism.

Now we finally can explain why energy can be converted. Different forms of energy only are different forms of formation of the same phenomenon!

Of course this statement of the field-theoretical approach does not yet explain what, for instance, the temperature has to do with electromagnetism. I ask for some patience; no question will be left unanswered.

From

$$\boxed{c \sim r} \qquad (6.2)$$

follows:

The speed of light determines the size of the elementary particles.

Energy of a capacitor:

$$W = Q^2/C, \qquad (6.3)$$

written down for the electron (with the Einstein relation):

$$W_e = e^2/C_e = m_e c^2 = 0{,}51\ \mathrm{MeV} \qquad (6.1)$$

Capacity of a spherical capacitor:

$$C_e = \varepsilon_0 \cdot 4\pi r_e \qquad (6.4)$$

"classical" radius of the electron[i] is:

$$r_e = e^2/\varepsilon_0 \cdot 4\pi \cdot W_e \qquad (6.5)$$

$$r_e = 2{,}82 \bullet 10^{-15}\ \mathrm{m} \qquad (6.6)$$

in the case of Kuchling[ii] the radius of the electron is:

$$r_e = 1{,}41 \bullet 10^{-15}\ \mathrm{m}\ . \qquad (6.7)$$

Fig. 6.3: Calculation of the radius of the electron.

---

[i]: Mende, Simon: Physik, Gl. 10.39, VEB-Leipzig, 4. Aufl.

[ii]: Kuchling: Physik, Gl. At4, VEB-Leipzig, bis einschl. 11. Auflage 1974

6.3 Radius of the electron

For the crucial process, in which the electromagnetic wave rolls up to a vortex, it is for reasons of continuity to be expected that the velocity of propagation remains equal that thus for the vortex oscillation exactly like for the electromagnetic wave the speed of light is determining. The direction of propagation in the case of the vortex takes place perpcndicular to the in fig. 6.2 shown field direction of the electric field strength. Not even in that both field-phenomena differ.

Summarizing: the propagation takes place with the speed of light c along a circular path with the perimeter $U = 2\pi r$. Therefore holds:

$$\boxed{c \sim r} \quad (6.2)$$

According to this equation the radius and with that the size of the electron is determined by the speed of light. Therefore the question of the size of the electron is raised.

The energy interpretation predicts that for the theoretical case of a change of size the energy density in the inside of the particle is influenced that however the quantity of the included energy remains unchanged. We therefore can further proceed from the assumption that the bound amount of energy is independent of the size of the particle!

Consequently for the elementary quantum the energy W_e = 0,51 MeV is assumed, which it has acccording to the Einstein relation $W_e = m_e c^2$. For the electron of mass m_e the with measuring techniques determined value is inserted.

The spherical electrode of a spherical capacitor with the above given energy W_e (according to eq. 6.1) and the capacity C_e (according to equation 6.4, fig. 6.3) represents a very realistic model of the negatively charged particle.

In this manner the classical radius of the electron is calculated to be<i>: $r_e = 2{,}82 \cdot 10^{-15}$ m.

But in the case of Kuchling it only is half this size<ii>, what according to equation 6.2 would mean that in the case of Kuchling the light would be on the way only half this fast <iii>. Therefore if one is careful, one prefers to be silent concerning this delicate theme and if one is honest, one admits not to know anything exact.

Not only the electron but also all the other elementary particles are according to the field-theoretical approach formed from concentrated potential vortices. For these equation 6.2 hence has to hold in the same manner, so that more generalized we can conclude:

The speed of light determines the size of the elementary particles.

This statement is incompatible with the assumption of a constant speed of light! Because then all elementary particles would have identical size. As is known, however, are the building parts of the atomic nucleus, the protons and neutrons very much smaller than individual electrons. The constancy of the speed of light is to be questioned. This question is of such an elementary importance that we are not content with these considerations and in addition undertake a mathematical derivation in the sense of the field approach.

<iii>: Difference = Thomas factor



The Maxwell laws, source free (figures 3.2 and 3.3):

$\mathrm{Div}\,\mathbf{D} = 0$ (3.7) and $\mathrm{Div}\,\mathbf{B} = 0$ (3.3)

Faraday's law of induction | and Ampère's law

$\mathbf{E} = \mathbf{E}(\mathbf{r},t)$ with $1/\tau_2 = 0$: | $\mathbf{H} = \mathbf{H}(\mathbf{r},t)$ with $\mathbf{j} = 0$ resp. $1/\tau_1 = 0$

$\boxed{\mathrm{rot}\,\mathbf{E} = -\,\delta\mathbf{B}/\delta t}$ (5.4) | $\boxed{\mathrm{rot}\,\mathbf{H} = \delta\mathbf{D}/\delta t}$ (5.1)

with: $\mathbf{B} = \mu \cdot \mathbf{H}$ (5.5) | and $\mathbf{D} = \varepsilon \cdot \mathbf{E}$ (3.6)

if we again apply the curl to equation 5.4 and insert equation 5.1 (cf. fig. 5.1, eq. 5.5):

$$-\,\mathrm{rot}\,\mathrm{rot}\,\mathbf{E} = \mu \cdot \delta(\mathrm{rot}\,\mathbf{H})/\delta t = \mu \cdot \varepsilon \cdot \delta^2\mathbf{E}/\delta t^2 \qquad (5.5)$$

thanks to missing divergence: $\mathrm{div}\,\mathbf{E} = 0$ (3.7*)
(fig. 5.2):

= wave equation: $\boxed{\Delta\mathbf{E} \cdot c^2 = \delta^2\mathbf{E}/\delta t^2}$ (5.9*)

with the speed of light c: $\mu \cdot \varepsilon = 1/c^2$ (5.6)

Hertz' wave = transverse wave = plane wave with:
direction of propagation: $\boxed{v = dx/dt}$ (6.8)

$\boxed{\mathbf{E} = E_z}$, $\boxed{\mathbf{D} = D_z}$, $\boxed{\mathbf{H} = H_y}$, $\boxed{\mathbf{B} = B_y}$ (6.8*)

curl operation (in y-direction): with equation 5.4:

$$\mathrm{rot}\,\mathbf{E} = -\,d\mathbf{E}/dx = -\,d\mathbf{B}/dt \qquad (6.9)$$

with 6.8: $d\mathbf{E} = (dx/dt) \cdot d\mathbf{B} = v \cdot d\mathbf{B}$ (6.9*)

or generally: $\boxed{\mathbf{E} = \mathbf{v} \times \mathbf{B}}$ (6.10)

Fig. 6.4: Derivation of the laws of transformation

<i>: Prof. G. Bosse in his text book in reversed direction derives the Faraday law of induction from the law of transformation 6.10, which he again derives from considerations about the Lorentz force. G. Bosse, Grundlagen der Elektrotechnik II, BI 183, Hochschultaschenbucher-Verlag, Mannheim 1967

6.4 The Maxwell field equations

The laws of transformation of the electromagnetic field shall form the starting-point for the coming up considerations. To exclude any doubts with regard to the interpretation, the equations will be derived from the Maxwell laws under the assumption that no sources or charge carriers are present (fig. 3.2 and 3.3) and as a consequence no current density ($j = 0$) is to be expected.
This corresponds to the vanishing of the time independent terms, which consequently are responsible for the occurring of force effects like e.g. the Lorentz force. Only at the end of this derivation we can understand the sense of this assumption (with $1/\tau_1 = 0$ and $1/\tau_2 = 0$). The procedure at first corresponds to that of fig. 5.1. Here the fundamental field equation had been derived from Faraday's law of induction and Ampere's law. With the assumptions made this time the in fig. 5.2 treated undamped wave equation is left (5.9, here 5.9*). Whom the derivation is still present can go in at this point.
In a sufficiently great distance from the source we are dealing with a plane wave, in which the field factors only depend on the direction of propagation x. The Hertz' wave is a transverse wave, in which the field pointers oscillate perpendicular to the direction of propagation and in addition stand perpendicular to each other:

$$\boxed{v = dx/dt} \quad (6.8), \qquad \boxed{\mathbf{E} = E_z, \quad \mathbf{D} = D_z, \quad \mathbf{H} = H_y, \quad \mathbf{B} = B_y} \quad (6.8^*)$$

The curl, applied to the electric field pointer, itself points in the y-direction:
$\mathrm{rot}\, E = - dE/dx$. This for the transverse wave carried out curl operation is now compared with Faraday's law of induction (5.4):

$$\mathrm{rot}\, E = -dE/dx = - dB/dt \qquad (6.9)$$

The relation won in a mathematical way, with the speed fixed by (6.8), reads:

$$dE = (dx/dt) \bullet dB = v * dB \qquad (6.9^*)$$

The result of this derivation at first only is valid for the introduced simplification, for instance for the case of the transverse electromagnetic wave. Better known is apart from that the generalized formulation, which among others by G. Bosse<i> is called law of transformation.

$$\boxed{\mathbf{E} = \mathbf{v} \times \mathbf{B}} \qquad (6.10)$$

With Ampere's law (5.1) we now should proceed in an analogous manner. The result is:

$$\boxed{\mathbf{H} = -\mathbf{v} \times \mathbf{D}} \qquad (6.10^*)$$

This equation 6.10* is given among others by Simonyi<ii>. Now that we know, under which circumstances these equations of transformation can be derived from the Maxwell equations, the actual work can start.

<ii>: K. Simonyi, Theoretische Elektrotechnik, 7. Auflage VEB Verlag Berlin 1979. pp. 921 - 924; In addition see chapter 27.8 in part 3 of this book.

Laws of transformation:



$$\boxed{\mathbf{E} = \mathbf{v} \times \mathbf{B}} = \mathbf{v} \times \mu \cdot \mathbf{H} \qquad (6.10)$$

$$\boxed{\mathbf{H} = -\mathbf{v} \times \mathbf{D}} = -\mathbf{v} \times \varepsilon \cdot \mathbf{E} \qquad (6.10^*)$$

and

We experience the magnetic field as an electric field and the electric field as a magnetic field simply and solely for reason of the same relative motion!

The component of the direction of motion perpendicular to the area defined by the field pointers:



$$E = v \cdot \mu \cdot H \qquad (6.11)$$

and

$$H = -v \cdot \varepsilon \cdot E \qquad (6.11^*)$$

with the relations of material:

$$B = \mu \cdot H \qquad (3.5)$$

$$D = \varepsilon \cdot E \qquad (3.6)$$

with the speed of light:

$$c = 1/\sqrt{\mu \cdot \varepsilon} \qquad (5.6)$$

additional field:

$$E_z = -v^2 \cdot \mu \cdot \varepsilon \cdot E = -(v^2/c^2) \cdot E \qquad (6.12)$$

resp.

$$H_z = -v^2 \cdot \varepsilon \cdot \mu \cdot H = -(v^2/c^2) \cdot H \qquad (6.12^*)$$

basic field: E resp. H (at v = O)

measurable overall field: (if $v \neq O$)

$$E_o = E + E_z \qquad (6.13)$$

resp.

$$Ho = H + H_z \qquad (6.13^*)$$

Fig. 6.5: Properties of transformation of the electromagnetic field.

6.5 Equations of transformation

As a consequence of the in fig. 6.5 again written down laws of transformation of the electromagnetic field (6.10 and 6.10*) magnetic phenomena can be traced back to electric phenomena and vice versa. The mathematical formulation reveals us the two sides of the same medal and points to a perfect duality between both fields and their factors of description.

Because a way exists, as is shown here, in which the equations of transformation can be derived from the Maxwell field equations, the same generally valid and extensive importance should be attributed to them. They can with the same right be called the foundation of electromagnetism. Wherein does lie its message for physics, the always curious researcher will ask? For that the relations of material 3.5 and 3.6 are completed:

$$\boxed{\mathbf{E} = \mathbf{v} \times \mu \cdot \mathbf{H}} \quad (6.10) \qquad \text{und} \qquad \boxed{\mathbf{H} = -\mathbf{v} \times \varepsilon \cdot \mathbf{E}} \,. \quad (6.10^*)$$

The here presented equations state, that we measure an electric field strength E, if we are moving with regard to a magnetic field H with the speed v and vice versa. The electric and the magnetic field therefore prove to be an experience of the observing person and we can say:

We experience the magnetic field as electric field and the electric field as magnetic field simply and solely for reason of the relative motion!

Let's assume, v is the component of the relative velocity (6.8), which stands perpendicular to the area defined by the field pointers (6.8*), then the equations of transformation (6.9* with 3.5) now read:

$$\mathrm{E} = \mathrm{v} \cdot \mu \cdot \mathrm{H} \quad (6.11) \qquad \text{and} \qquad \mathrm{H} = -\mathrm{v} \cdot \varepsilon \cdot \mathrm{E} \,. \quad (6.11^*)$$

If we are moving with the velocity v in a basic field which is present with the field strength E, then according to equation 6.11* we observe a magnetic field, which again according to equation 6.11 is to be interpreted as an additional electric field E_z:

$$\mathrm{E}_z = -\mathrm{v}^2 \cdot \mu \cdot \varepsilon \cdot \mathrm{E} = -(\mathrm{v}^2/c^2) \cdot \mathrm{E} \quad (6.12)$$

In duality equation 6.11 inserted into equation 6.11* provides for the magnetic field strength a corresponding additional field H_z:

$$\mathrm{H}_z = -\mathrm{v}^2 \cdot \mu \cdot \varepsilon \cdot \mathrm{H} = -(\mathrm{v}^2/c^2) \cdot \mathrm{H} \quad (6.12^*)$$

We obviously owe the measurable overlap fields in a laboratory simply and solely to the relative velocity v with which the laboratory is moving. But now we must pay attention to the fact that a terrestrial laboratory rotates along with the earth, that the earth orbits the sun and the sun again rotates around the centre of the milky way. Eventually the whole milky way is on the way in the cosmos with a galactic, for us hardly understandable speed. If we further take into consideration that for every subsystem an additional field occurs as a consequence of the relative motion with regard to the super ordinate system, then one additonal field follows after the next and overlaps this one.

Let's imagine, the relative velocity could be reduced towards zero - and maybe we are moving around such a cosmic point - then here no overlapping field would be measurable.

<*>: A derivation using vectors is written in chapter 28 (part 3).

Additional field (from fig. 6.5):

(6.12)
(6.12*)

$$\boxed{\begin{aligned} E_z &= -(v^2/c^2) \cdot E \\ H_z &= -(v^2/c^2) \cdot H \end{aligned}}$$

and

Superposition of the fields:
The additional field (E_z resp. H_z) overlaps the basic field (E resp. H) to produce the measurable overall field (E_0 resp. H_0):

(6.13)

$$\boxed{\begin{aligned} E_0 &= E + E_z = E \cdot (1 - v^2/c^2) \\ H_0 &= H + H_z = H \cdot (1 - v^2/c^2) \end{aligned}}$$

(6.13*)

transformed:

$$(1 - \frac{v^2}{c^2}) = \frac{E_0}{E} = \frac{H_0}{H}$$

(6.14)

for the Lorentz contraction holds apart from that:

(6.14*)

$$(1 - \frac{v^2}{c^2}) = (\frac{1}{l_0})^2$$

From the comparison
Follows

(6.14**)

$$\frac{E_0}{E} = \frac{H_0}{H} = (\frac{1}{l_0})^2$$

the proportionality:

$$\boxed{E, H \sim 1/l^2}$$ and $$E_0, H_0 \sim 1/l_0^2$$ (6.15)

Fig. 6.6: The field dependency of the Lorentz contraction

6.6 Field overlap

Field vectors can be superpositioned. In this manner the additional field E_z resp. H_z which depends on the velocity, according to equation 6.10, overlaps the respective basic field (E resp. H) to produce the measurable overall field (E_0 resp. H_o):

$$\boxed{E_0 = E + E_z = E \cdot (1 - v^2/c^2)} \quad (6.13)$$

$$\boxed{H_0 = H + H_z = H \cdot (1 - v^2/c^2)} \quad (6.13^*)$$

In the result something surprising the factor $(l-v^2/c^2)$ appears, which is well-known from the special theory of relativity and for instance appears in the Lorentz contraction.
If we rewrite both equations for the characteristic factor and compare with the in a purely mathematical way, over the Lorentz transformation, won length contraction $(1 - v^2/c^2) = (l/l_0)^2$, then it becomes clear that the Lorentz contraction physically seen should have its cause in the changed field conditions which a with relativistic speed moving body finds with regard to a resting body.

$$1 - \frac{v^2}{c^2} = \frac{E_0}{E} = \frac{H_0}{H} \overset{!}{=} \left(\frac{l}{l_0}\right)^2 \quad (6.14)$$

The equation is a compulsionless consequence of known physical laws. In this derivation actually no new factor was introduced and nevertheless a completely new picture for the natural scientific reality results[i].

In our observer system, where the field E_o exists, a rule has its proper length l_0. In another system, which is moving with the speed v relative to the observer, as a consequence of the here prevailing field E the corresponding rule has a length 1. In which relation the factors stand to each other, is described by equation 6.14. Accordingly the following proportionality holds:

$$\boxed{E, H \sim 1/l^2} \quad \text{and} \quad \boxed{E_0, H_0 \sim 1/l_0^2} \quad (6.15)$$

If we are exterior to a very fast moving body with velocity v, we immediately can observe how this body for reason of its relative velocity experiences the calculated additional field and in this way experiences a length contraction. If the observer is moving along with the body, then he purely subjective seen doesn't detect a length contraction, because he himself and his entire measuring technique is subjected to the same length contraction. From the axiomatic approach what would be, if the field, which itself only represents an experience, would determine perceptible space and its dimensions, quickly a fundamental realization can develop if the described experiences should coincide with real observations.

---

[i] : Because in this point of view the subjective status of the observer is determining, it is not completely impossible that there is an error in the interpretation of the equations of transformation (6.10 and 6.10*). But because we started from the same point of view of the observer for the derivation of the length contraction from the Lorentz transformation, here the same error is to be expected. In putting both results equal (6.14), a like constituted error on both sides will cancel out in any case and the result stays above all doubts!

$$\boxed{E, H \sim 1/l^2} \quad \text{and} \quad \boxed{E_0, H_0 \sim 1/l_0^2} \qquad (6.15)$$



(Model):

Two particles of matter each in the field of the other particle.

Two elementary particles or two accumulations of matter consisting of these are able to reduce the distance to each other for reason of their fields, which we interpret as a force of attraction.


Uranus
Venus
Erde
Sonne
Merkur
Jupiter
Mars
Saturn

B: (Example): The orbits of the planets in the field of the sun.

Fig. 6.7: The influence of the field on interactions.

6.7 Field dependent curvature of space

Let's assume, an accumulation of matter, as big as our earth, wanted to fly past the sun in the distance earth-sun. But it would not succeed. Because the fields arising from the sun decreases with increasing distance and according to equation 6.15 as a consequence the size of the particles of matter increases. The planet hence is more strongly contracted on its side turned towards the sun, as on the turned away "night side". It bends towards the sun and its flight path becomes a circular path around the sun. That is the interaction known as gravitation!

To an earth inhabitant this curvature reveals itself merely in the observation that the duration of sunshine at daytime is longer, than it would be expected to be under the assumption of the earth as a homogeneous sphere. In this context one willingly speaks of a curvature of space. Actually it is a curvature of matter under the influence of the field dependent length contraction.
Exactly this contraction the planets owe their circular orbits around the sun and by no means the equilibrium of forces between the force of attraction and the centrifugal force (fig. 6.7 B). It obviously is a fundamental mistake to think that gravitation would causally be connected with a force effect!
If, in this context, we speak of a force of attraction for the sake of our subjective observation, then we must realize that it merely can concern an auxiliary term founded in usefulness.

A thought experiment should bring us clarity (fig. 6.7 A). The field, which surrounds every particle of matter, reaches till infinity but becomes less effective with increasing distance. If the distance between two particles is 1, then one particle is in the field of the other particle. As a consequence of the field the length 1 reduces and in this way the size determining field increases, which again leads to a further reduction of length etc. As a consequence it can be observed that both particles are moving towards each other. We speak of a force of attraction, because we can't register the influence of the field with our senses.
In this way the consistent result that we and our environment at daytime must be smaller than in the night will as well remain hidden. We experience the effect only indirectly as gravitational pull of the earth.

Because we don't see the cause of a subjectively observed force effect, for the electromagnetic interaction, just as for the gravitation, the field dependency of the length contraction will be responsible. Hence the following conclusion holds for both interactions equally way.

Two elementary particles or two accumulations of matter consisting of these are able to reduce the distance to each other for reason of their fields, which we interpret as a force of attraction.

Now the question still is open, why gravitation only knows forces of attraction, whereas the electromagnetic interaction also permits forces of repulsion and which are the causal fields for each.



A: The field lines of the E-field for unlike charged particles



B: The field lines of the E-field for equal charged particles

---

The electromagnetic interaction of a particle is a result of the influence of the open field lines arising from it on the dimensions of space.

Fig. 6.8: The influence of the open field lines of the E-field

6.8 Electromagnetic interaction

A convincing answer to the open question provides us the analysis of the course of the field lines, on the one hand for charged particles and on the other hand for uncharged particles, which do not participate in the electromagnetic interaction.
If at first we consider electrically charged particles, like e.g. electrons, protons or ions.
Then all in common is that the towards infinity running field lines of the electric field are open. With this field the particle is able to interact with its environment. We measure a charge and an electromagnetic force effect. In the case of unequal charges, as is well-known, a field amplification and attractive acting forces are observed whereas for equal charges a field reduction results and repulsion is observed.

If we make a connection between the field conditions and the electromagnetic interaction in the sense of the proportionality (6.15), then the particle in reality is able to influence the distance to other particles merely with the help of its electric field. For unequal charges a compression of field lines arises, in which one particle stays in the focussed field of the other and vice versa. In this way a contraction of all lengths occurs and the observable attraction happens (fig. 6.8 A).
For equal charges the opposite case is present, in which even a local field freedom can occur (fig. 6.8 B). If the field tends towards zero on the dashed line, then the distance will go to infinity (according to eq. 6.15). Consequently, the observable effect that both bodies go away from each other, will reach to infinity.

Actually the electromagnetic interaction proves to be a result of the field dependent length contraction.

The electromagnetic interaction of a particle is a result of the influence of the open field lines arising from it on the dimensions of the space, in which it is.

It is important that the field lines are open, for which reason they are bent away from like charges and are directed towards unlike charges. Subjectively seen we find out that as a consequence of the field reduction repulsive force effects and as a consequence of the field compression attractive acting force effects are observed (fig. 6.8).
The consequence of is every electric field is, as is well-known, a magnetic field standing perpendicular on it. The field lines of the magnetic field run parallel to the surface of the particle and have a closed course (fig. 6.9 A)!
Therefore no magnetic poles form, which would be measurable. Seen from the outside the particle behaves neutral magnetically seen, because of the closed course of the field lines.
An artificial field reduction and as a consequence observable forces of repulsion, like in the case of the electromagnetic interaction, hence in principle are impossible.

The effect of the magnetic field thus is limited to a geometrical manipulation of the environment, namely the curvature of space, with which we have founded the phenomenon of the attraction of masses and of the gravitation.



A: The open field lines of the E-field and the closed field lines of the H-field of an electrically charged particle (e.g. e-)



B: The closed field lines of the E-field and H-field of an electrically uncharged particle (e.g. of the neutron n°).

Gravitation is a result of the influence of the field lines with a closed course running parallel to the surface of the particles on the dimensions of the space, in which they are.

Fig. 6.9: The influence of the closed field lines of the H-field.

6.9 Gravitation

For uncharged, neutral particles (neutron, atom, molecule etc.) both the magnetic and the perpendicular on them standing electric field lines have a closed course. Now both run parallel to the surface of the particle (fig. 6.9 B).

As is said, the density of field lines with a closed course can't be influenced from the outside. If we approach a particle, the consequence of an increase of the density without exception is a decrease of the linear measures and thus a larger force of attraction. For this case of field lines with a closed course, for which in general it doesn't give a field attenuation and no forces of repulsion, there holds:

Gravitation is a result of the influence of the field lines with a closed course running parallel to the surface of the particles on the dimensions of the space, in which they are.

Both interactions logically have an infinite range. Both form a whole in the influence of the fields on the size conditions.

It surely is of the greatest importance that for this derivation of the field dependency of the Lorentz contraction from the known equations of transformation of the electromagnetic field we could do completely without the introduction of new factors of description or neglects.

Solely by consistent derivation and interpretation of the result the unification already has suceeded and the electromagnetic interaction and the gravitation could, with the derived field dependent Lorentz contraction, be traced back to a single basic phenomenon. Doing so we have to pay attention to the fact that the observer is subjected to the same Lorentz contraction as his measuring technique and therefore he can't see the field dependency at all. Merely as being an exterior observer it in rare cases will be possible to him to see the curvature of space in the presence of strong fields.

From this for an astronaut practical consequences result. If he namely would land on Jupiter, he would think flat hills to be gigantic mountains, that small he would be! Vice versa if he landed on the moon, high mountains would appear to be insignificant hills, not because of wrong altitude readings of the terrestrial mission control and measurement centre, but only because of his own body size. The astronauts of the Apollo missions were not prepared for this circumstance and after their landing on the moon were completely surprised, how little validity learned textbook physics has, hardly has one left the earth. They have brought photographs with them which prove the Lorentz contraction to depend on the field and therefore on gravitation.

The fact that force effects should arise from the interactions is an auxiliary concept and auxiliary description of the observing person founded in pure usefulness. The Lorentz force therefore shouldn't be regarded as cause anymore. It actually appears only as property of the field factors. Seen this way it only would be consistent to do without space charges and currents as a result of moving charges and to assume a source-free and quanta-free field description (fig. 6.4: $j = 0$).

From an unified theory it is demanded that it besides the electromagnetic interaction and the gravitation also is able to integrate the strong and the weak interaction. We will also solve this problem.


shining star:
Strong gravitational field:
observer:

Fig. 6.10: Diversion of the light by a strong gravitational field.

Speed of light of the wave: $c = \lambda * f$ (6.16)

For the wavelength λ holds (because of eq. 6.15): $E, H \sim 1/\lambda^2$

From equation (6.16) follows (with f = constant):

$$E \sim 1/c^2 \quad , \quad H \sim 1/c^2 \tag{6.17}$$

The speed of light depends on the field!

6.10 Field dependent speed of light

But not only matter is bent towards a gravitational field. If we only think of the much cited phenomenon that the ray of light of a star is diverted towards the sun, if it passes very close to the sun on its way to us, like this has been observed for the first time during an eclipse of the sun in 1919 (fig. 6.10).
Quite obviously the field of the sun also slows down the speed of light. On the side of the ray of light which is turned towards the sun, the field is somewhat larger and the speed of light correspondingly is slower than on the side which is turned away, and with that the ray of light changes its direction in the observable manner. Exactly this relation willingly is interpreted as a consequence of a curvature of space.
The extremely strong field of a black hole can divert the light down to a circular path, in order to in this way catch and bind it. The light now orbits the black hole like planets the sun.

At this point the open-minded reader already might have tapped the confirmation of the proportionality 6.2 ($c \sim r$), which has been derived from the vortex model (fig. 6.2).
The sceptic is offered still another derivation: for the borderline case that the relative velocity v tends towards the speed of light c (fig. 6.6), according to equation 6.13 the measurable overall field E_o (and also H_o) will go to zero and equation 6.12, with $E_{z.} = - E$ (and $H_z = - H$), will again turn into the wave equation (5.9*) after double differentiation (fig. 6.4).
The speed $v = c$ so to speak forms the escape velocity, with which the electromagnetic wave runs away from the cosmic field. Under these circumstances of course neither an attraction of masses nor an electromagnetic interaction can be exerted on the wave.
If E_0 goes to zero at the same time l_0 tends to infinity (equation 6.15, fig. 6.6): i.e. the wave spreads all through space. This result entirely corresponds to the observations and experiences.

For the wave length λ and in the end for the velocity of propagation c only the self-field of the wave E resp. H is responsible. Because of

$$\boxed{c = \lambda \cdot f} \quad (6.16)$$

and the proportionality from equation 6.15: $E, H \sim 1/\lambda^2$ (6.17*)

obtain the new relation: $\boxed{E, H \sim 1/c^2}$ (6.17)

If the speed of light in the presence of matter decreases, then we now also know why. It is the field, which surrounds matter, that slows down the speed of light. Therefore a gravitational field is able to divert a ray of light in the same manner as matter which flies past. Finally moves the speed of light in the proportionality 6.17 to the place of the linear measure (in 6.15).
But if the rule fails one will try to replace by an optical measurement arrangement. In this manner the field dependency of the Lorentz contraction should be measurable; but it isn't!

From the comparison of the derived proportionalities:

$$\overset{(6.15):}{E, H \sim \frac{1}{l^2}} \sim \overset{(6.17)}{\frac{1}{c^2}}$$

follows:

$$\underline{l \sim c} \qquad (6.18)$$

The speed of light is proportional to the measurement path.

The variable speed of light is being measured with itself.

The result at all events is a constant value.

The constancy of the speed of light is based on a measurement which is faulty from the principle!



Because of c ~ r: physical length contraction

Fig. 6.11: Derivation of the length contraction (field dependent Lorentz contraction)

6.11 Universality

Why can't the rule be replaced by an optical measurement arrangement? The crucial indication provides the comparison of both derived proportionalities 6.15 and 6.17. According to them holds the same field dependency for both the Lorentz contraction and the speed of light:

$1/l^2 \sim 1/c^2$ or $1 \sim c$ (6.18)

If the rule has proved to be useless, then we will experience the same disaster if we measure optically, i.e. with the speed of light.

Obviously both, the length 1 and the speed of light c as a length per unit of time, depend in the same manner on the respective local field strength. On the one hand do both measuring methods lead to the same result; but on the other hand will anything which can't be measured with one method, neither be measured with the other method.

If now the speed of light is being measured optically, then the measurement path will be proportional to the speed of light and as a result will the unknown factor be measured with itself. The result of this measurement, which is faulty from the principle, at all events is a constant value, because here two variables which stand in direct proportionality to each other are related to each other.

Was the famous experiment of Michelson and Morley unnecessary, the result trivial? And how does it stand about the postulate of the universality of the speed of light?

If we for that consider a cube (fig. 6.11). And we assume that the speed of light is a vectorial quantity, which in our experiment is for instance in one direction twice as large, as in the direction of the other two space axes. By means of the mentioned influence of the speed of light on the spatial length is, as a consistent consequence, the cube along this edge pulled apart to a cuboid. We however register this spatial body with our eyes, which is with the speed of light and that has increased proportionally to the length of the edges, for which reason we as subjective observer still see a cube in front of us and not a cuboid.

If we trust an apparent objective measurement more than our sense organ and measure the three lengths of the edges of the cuboid again with a rule then we get three times the same length, which is a cube.

We probably are dealing with an optical deception using the true meaning of the word.

If the by Einstein postulated universality and constancy of the speed of light in reality doesn't exist at all, we in no way would be capable to register this; neither to observe nor to measure it!

The Galilean theorem of the addition of speeds objectively seen still is valid, even if the fact that the speed of light apparently is independent of the speed of the source pretends us the opposite.

If for instance a light source is moved towards a receiving device or away from it, then the speeds will overlap, like for the passenger, who marches in a driving train against or in the driving direction through the corridor. For the ray of light also the fields, which influence the speed of light and the measurement equipment, overlap. As a consequence will a measuring technician, who himself is exposed to this overlapping field, always observe and "measure" the identical speed of light. The observer as a result imagines, there is an universality of the speed of light.

The field takes over the function of the aether.



Fig. 6.12: Experiment of Michelson and Morley to detect an aetherwind<i>

<i>: A.P.French: Special Relativity, Massachusetts Institute of Technology, 1966.

<ii>: Nikola Tesla: "This is the same as writing a business letter and forgetting the subject you wish to write about". To Einstein's Theories, Rare Book and Manuscript Library, Columbia University, 15.4.1932.

<iii>: Einstein proceeds in the same manner with the time dilatation, by assuming a time constant by definition for the derivation to present at the end of his derivation a variable time. And with that he presents a result which contradicts his approach completely.

6.12 Aether

Important experiments like the one of Doppler concerning the redshift or the one of Bradley concerning the aberration of the stars show only to clear, where the influence of the speed of light subjectively still is perceptible, or for laboratory experiments like the one of Michelson and Morley, where the influence isn't perceptible anymore, because the length of the interferometers always changes proportionally to the speed of light. The look in the stars at the same time is a look in cosmic areas, where completely other field conditions prevail and as a consequence completely other values for the speed of light and for the dimensions of space are present. The mentioned observations suggest that we together with our measuring station are moving through the cosmos and therefore a relative velocity has to be present with regard to an aether which determines the respective speed of light.

If we however constrict our range of vision and retire in a laboratory, then we no longer are capable to observe the influence of the field on the speed of light. The experiments of Michelson which Maxwell had prompted to and which Morley with a higher precision had repeated with the goal, to detect the aether, inevitably had to turn out negatively. The laboratory experiments resulted in the misleading picture, as if the earth was resting in the aether.

The not understood measurements will suggest any observer, he forms the centre of the universe and everything rotates around him, entirely in the sense of the Ptolemean view of life, which, although long ago abolished, here belated has experienced support. With a Swabia caper Albert Einstein has prevented a relapse into the dark Middle Ages and removed the open contradiction in the question of the aether, which once is measured as moving and another time as resting, by without further ado abolishing the aether. With that he undoubtedly has solved a central problem of physics and at the same time created a new one. As is known does the speed of light have a certain value, and therefore the question is raised, what determines is size. Exactly for this purpose a luminiferous aether had been introduced, however it is constituted.

Scientifically it does make little sense, to make an assumption, if at the end of the derivation the prerequisite is deleted without substitute. In such a case either in the approach or in the derivation is a principal error*[1]"*. Nikola Tesla comments on the working method of Einstein with the applicable comparison, as if Einstein had, while he was writing a business letter, forgotten completely the subject he wanted to write about (fig. 6.12<ii>).

The answer, which removes all contradictions and is entirely in accord with all observations and measurements, is obvious. Naturally a luminiferous aether exists, which determines the velocity of propagation and of course it by no means is bound to the observer.

As has been derived in figures 6.5 and 6.6, will for a relative velocity v arise a field, which according to proportionality 6.17 determines the speed of light. With that we have derived completely.

The field takes over the function of the aether.

The equations 6.10 also answer the question, why no aetherwind is being observed, although such a wind actually is present: we experience, as we have discovered, an E-field with „head wind" as a resting H-field and vice versa and therefore we aren't capable to detect the head wind in the aether!

Key questions of quantum physics (fig. 4.4 + continuation):

IV. Why do the particles have the form of spheres?
(with increasing E-field decreases c)

VIII. Why is the elementary quantum localized?
(in the vortex centre: c = 0, see figures 4.3 and 6.2)

IX. Why do the elementary particles have a spin?
(spherical form demands field compensation)

X. Why is the magnitude of the spin quantized?
(cosmic basic field determines the need of E_z)

XI. Why can speeds faster than light occur in a tunnel? ______________________________
(a reduction of the cosmic basic field can only be realized locally in a tunnel)

to XI:



Fig. 6.13: Consequences concerning the field dependency of the speed of light: spin effect and tunnel effect <i,ii>

<i>: Nimtz,G.: Instantanes Tunneln, Tunnelexperimente mit elektromagnetischen Wellen, Phys.B1.49, VCH Weinheim (1993) Nr.12, S. 1119-1120<*>
<ii>: Thoma, P., Weiland.T.: Wie real ist das Instantane Tunneln? Phys.Bl.50, VCH Weinheim (1994) Nr.4, S. 359-361<*>
<*>: The measurement results are in accord with the theory of objectivity, not however the contradictory attempts to interpret them <i> and <ii> et al.

6.13 Spin and tunnel effect

Only with the field dependency of the speed of light (6.17) we can understand, why the elementary quanta can form as spheres, like is drawn in the figs 4.3 and 6.2. In the centre the field lines run together, i.e. the field increases and the speed of light decreases. Only in this way it will be possible for the vortex oscillation to everywhere occur with the speed of light, even in the inside of the particle! In the centre of the vortex particle the field in theory will become infinitely large and the speed of light zero. This circumstance again is the foundation why the elementary particles are localized and it answers key question VIII of quantum physics. The absence of a speed after all is the characteristic of an immobile thing.

The field dependency of the speed of light answers also further basic and up to today unanswered key questions of quantum physics, like why the elementary particles have a spin (IX) and why the magnitude of the spin is quantized (X).

A vortex particle after all does not exist alone in the world, but it is in the field of other particles. We can call this the cosmic basic field (E resp. H). This basic field overlaps the self-field and takes effect the strongest in the area of the spherical shell, where the self-field is correspondingly small. In order to keep the form of a sphere, this influence of the basic field has to be compensated. The additional field (E_z resp. H_z according to eq. 6.12) necessary for the compensation is produced by the particle, by rotating in a spiral around itself with a speed v which increases towards the outside of the spherical shell. Therefore does the elementary particles have a spin. The electron spin is therefore determined by the cosmic basic field.

Another effect of the field dependent speed of light is the tunnel effect. As an example we consider the two differently charged particles shown in fig. 6.8 A. The open, outside of the particles running, field lines of the electric field are predominantly bent towards the each time oppositely charged particle. If another particle wants to pass between the two, then it gets into an area of increased field strength. As a consequence it will be slowed down, because here a smaller speed of light is present.

Water molecules show with their polar nature exactly this property. Water has a remarkably high dielectricity e and slows down the speed of light correspondingly according to equation 5.6 ($\varepsilon\cdot\mu = 1/c^2$). The refraction of light at the water surface is an observable result of the reduced speed of light in the presence of matter.

If we now examine the case in which the two particles have the same charge as is shown in fig. 6.8 B (and fig. 6.13 belonging to XI). The field lines repel each other, so that exactly in between the two particles a field free area forms, in which the speed of light goes to infinity! This area acts like a tunnel. If we send through a particle exactly here, then purely theoretically seen it won't need any time to run through the tunnel, and for a short time the signal becomes infinitely fast.

If a particle hits only slightly besides the tunnel, then it will one-sidedly be slowed down and diverted by the respective field. We call this process reflection or scattering. Only the few particles, which exactly hit the tunnel, arrive behind the hurdle and in the ideal case even almost without loss of time!

The current measurements of speeds faster than light demonstrate in a convincing manner the superiority of the field-theoretical approach with regard to the nowadays normally used quantum physical approach.


micro-
wave
trans-
mitter
micro-
wave
trans-
mitter
wave guide:
tunnel:
microwave-
detector
microwave-
detector
Signal: with 1,7c
... 4,7c
with c
analysation at the oscillograph:
V = amplification
V · A
A
Δt
t

Fig. 6.14: The microwave experiment at the II. Physical Institute of the University of Cologne to measure speeds faster than light.<i>

<i>: Nimtz, G. : New Knowledge of Tunneling from Photonic Experiments, Proc. of the Adriatico Research Conference, 1996, World Scientific Publishing Company

6.14 Interpretation of the measured speed faster than light

Now the attempt can be undertaken, to interpret the spectacular experiments, in which a speed faster than light has been measured. It is reported<i> that in experiments with photons at the University of California in Berkeley on an average a speed of 1.7 times the speed of light has been measured by Prof. Raymond Chiao and his co-workers. At the Technical University of Vienna Prof. Dr. Ferenc Krausz already has obtained 2.4 times the, according to Einstein at maximum obtainable, speed of light with tunnelling laser light.

The first measurements of speeds faster than light have been carried out with microwaves at the University of Cologne<ii> by Prof. Dr. Gunter Nimtz and co-workers. They at first had published the measurement of a speed 2.5 times the speed of light. In the meantime they even have transmitted a symphony of Mozart with a speed almost 10 times the speed of light and with that have contradicted Einstein's hypothesis, according to which the speed of light in vacuum would be the highest possible speed for the transmission of signals. The different experiments only resemble each other in the point that the particles have to tunnel, because one has put a barrier in their way. This "tunnelling" apparently is the cause for obtaining speeds faster than light. With the prevailing physical view of life these measurement results are incompatible.

In the measurement set up in Cologne the microwaves are sent through a wave guide, which they pass with the speed of light. If a parts with narrowed cross-section is inserted, where the microwaves actually don't fit through at all, then the signal gets damped strongly. Now however arrives nevertheless a small part of the signal at the other end of the wire, but much faster than allowed, namely with the measurable speed faster than light.

The answer of the here presented potential vortex theory reads as follows: the waves picked up by the wave guide run up to the entry of the tunnel, in order to find out that they don't fit through. They are reflected or absorbed. A small part however rolls up to potential vortices and these fit through the tunnel. They however have to be compressed additionally. In the derivation of the photon (fig. 4.5 and 4.6) we had seen that the inner vortex always is faster than the bigger one, through which it slips through. The compression therefore causes an increase in speed. In flow dynamics is known an analogy: the Venturi-tube. The flow-technical potential vortices also confirm exactly this property. One can as well start with the Lorentz contraction (fig. 6.6, eq. 6.14*). This states that a particle moving with a higher speed actually becomes smaller and not only appears to be smaller as an optical deception of the observer. Because only smaller particles fit through the tunnel, the particles, measurable at the other end, must be correspondingly faster: quod erat demonstrandum. In the same manner also the experiments of Berkeley can be explained physically, because here is worked with photons from the start<i>. With that the process of rolling up the wave can be left out. The tunnel lets pass only compressed and therefore faster light particles.

<i>: R.Y.Chiao, P.G.Kwiat, A.M.Steinberg: Schneller als Licht? Spektrum der Wiss. 10/93

<ii>: B. Schuh, Gespenstisch fixe Wellen, DIE ZEIT Nr. 45, 5.11.93, S. 43.

<ii>: Enders, A., Nimtz, G.: Photonic-tunneling experiments, Physical Review B, Vol. 47, No. 15 (1993), pp. 96O5-96O9.

<ii>: Enders, A., Nimtz, G.: Evanescent-mode propagation and quantum tunneling, Physical Review E, Vol. 48, No.l (1993), pp. 632-633.

"The theory of relativity is not a physical theory... it is a mathematical poetic idea, a deduction from impossible premises."<i>
Oskar Kraus

"The theory of relativity is a mathematical masquerade, behind which is hidden an inextricable ball of a mixing up of ideas, contradictions, fallacies, arbitrary assumptions and ignoring of healthy logic."<i>
Erich Ruckhaber

"The theory of relativity not only is fantastic, but also of an inconsistency which in the history of science not yet has been present."<i>
Harald Nordenson

"A physics of hybrids, of contradictions and fantastic confusions, nonsense!"<ii>
Johann Marinsek

"This is absurd."<iii> (regarding mass-energy interpretation)
Nikola Tesla

"In my experiments I have destroyed billions of atoms, without having observed any emissions of energy. "<4i>
Nikola Tesla

Fig. 6.15: Some statements regarding the theory of relativity.

<i>: Walter Theimer: Die Relativitatstheorie, Seite 7, Francke Verlag, Bern, 1977, ISBN 3-772O-126O-4
<ii>: Johann Marinsek: Rationale Physik, S. 163, dbv-Verlag TU Graz, 1989, ISBN 3-7O41-O176-1
<iii>: Nikola Tesla, To Einstein's Theories, Rare Book and Manuscript Library, Columbia University, 15.4.1932. Entnommen aus J.T.Ratzlaff: Tesla Said, Tesla Book Company, pp. 238, ISBN O-914119-OO-1
<4i>: Nikola Tesla, Franz Ferzak World and Space Publications 1985.

6.15 Definition of the speed of light

If a light signal propagates in space, then as a consequence of the velocity of propagation c, it at a certain point in time t is in a distance r of the light source:

$r = c * t$ (6.19)

Should the speed of light become smaller for instance by Δc, then the light signal obviously has covered a distance less by Ar or the time interval has changed by Δt:

$r + \Delta r = (c + \Delta c) \cdot (t + \Delta t)$ (6.20)

This equation describes purely mathematically the most general case which can be assumed. By writing out the multiplication and subtraction of equation 6.18 the change in distance considered for itself is:

$\Delta r = c \cdot \Delta t + t \cdot \Delta c + \Delta c \cdot \Delta t$ (6.21)

The answer of mathematics is that the change in distance can have its cause in a change in time, in a change of speed or in both. We now want to turn to the physical interpretation and have a closer look at the two possibilities, in which either c or t is to be taken constant (see fig. 6.16).

In the first case the speed of light c is constant and as a consequence the change Δc = zero. The mathematical formulation (according to eq. 6.21) therefore reads:

case 1: $\boxed{c = \frac{\Delta r}{\Delta t}}$ (relativity) (6.22)

If in this conception world a change in distance is observed, for instance the Lorentz contraction, then in order to save this relation inevitably a change in time, for instance a time dilatation, has to make the compensation. Einstein in an applicable manner speaks of relativity, because according to his opinion in the case of both variables, the length contraction and the time dilatation, it only concerns observed changes.

For the time dilatation experiments are given. But for the measurement of time always only atomic clocks are available and their speed of running of course could also be influenced by the Lorentz contraction. In any case it can't be claimed the time dilatation is proven experimentally as long as we do not know the mechanisms of decay of atoms. Otherwise the statements of the theory of relativity are familiar to us, for which reason further remarks seem unnecessary.

In the second case the time t is constant and consequently the change At = zero. At a closer look this case is much more obvious, since why should time change. After all time has been stipulated by definition.

After all, we are the ones who tell, what simultaneity is!

The mathematical formulation for this case reads (eq. 6.21 with $\Delta t = 0$):

case 2: $\boxed{\Delta c = \frac{\Delta r}{t}}$ (objectivity) (6.23)

This equation does open up for us an until now completely unknown and fundamentally other way of looking at the physical reality.



Concerning the definition of the speed of light c [m/s]:

r [m] = distance of the light source:

$$\boxed{r = c \cdot t} \qquad (6.19)$$

For changes, observed or measured:

$$r + \Delta r = (c + \Delta c) \cdot (t + \Delta t) \qquad (6.20)$$

$$= c \cdot t + c \cdot \Delta t + \Delta c \cdot t + \Delta c \cdot \Delta t$$

Change in distance:

$$\boxed{\Delta r = c \cdot \Delta t + t \cdot \Delta c + \Delta c \cdot \Delta t} \qquad (6.21)$$

2 possible causes:

with $\Delta c = 0$ | with $\Delta t = 0$

case 1: | case 2:

$$\boxed{c = \frac{\Delta r}{\Delta t}} \quad (6.22) \qquad \boxed{\Delta c = \frac{\Delta r}{t}} \quad (6.23)$$

c = constant | t = constant

$$\Delta r \sim \Delta t \quad (6.23) \qquad \Delta c \sim \Delta r \quad (6.25 = 6.2)$$

= time dilatation | = universality

Δr = observable length contraction | Δr = physical length contraction

Theory of relativity | Theory of objectivity

Fig. 6.16: Theory of relativity and theory of objectivity, derivation and comparison.

6.16 Relativity and objectivity

New to the second case (equation 6.23) is particularly the proportionality contained in it:

$\boxed{\Delta c \sim \Delta r}$ (6.25 = 6.2)

But to us it is not new, because we have derived the same proportionality from the model conept (equation 6.2, fig. 6.2), in which the elementary particles are understood as spherical vortices.
Equantion 6.25 unconcealed brings to knowledge that any change of the speed of light c [m/s] in the same way leads to a change of the radius r [m], the distance between two points in space or even the length of an object, e.g. a rule. Such a rule after all consists of nothing but spherical atoms and elementary particles and for their radius r again the proportionality 6.25 holds. Therefore it is to be set:

$$r \sim 1 \qquad (6.26)$$

and taken both together we already had derived as equation 6.18 (fig. 6.11) from the field dependency. Here the vortex model as well finds a confirmation of its correctness, as in the derivation from the equations of transformation of the electromagnetic field. Because all three, the derivation according to the model, the physical and the mathematical derivation, lead to the same result, this second case should be called "objective".

With that the first case, which describes the subjective perception of an observer, is not supposed to be devaluated. It contains the definition of reality, according to which only is real what also is perceptible. The theory of relativity of Poincare and Einstein is based on this definition.

With the second case, the case with a variable speed of light, we however get serious problems, since we observe with our eyes, and that works with the speed of light. If that changes, we can't see it, as already said. If we could see it, then "reality" would have a completely different face and we surely would have great difficulties, to find our way around. In this "objective world" neither electromagnetic interactions nor gravitation would exist, so no force effects at all. Because all distances and linear measures depend on the speed of light, everything would look like in a distortion mirror.
The concept of an "objective world" at first has not a practical, but rather a theoretical and mathematical sense. The distinction between an observation domain and a model domain is founded in pure usefulness.

The observation domain should correspond to case 1 and the model domain to case 2. The mathematical derivation tells us, how we can mediate between both domains (equation 6.21): This mediation amounts to a transformation, which provides us the instruction, how a transition from the observation into a not perceptible model concept, from the relativity into an objectivity has to.


Theory of relativity
Theory of objectivity
speed of light:
c = constant
absolute time:
t = constant
$c = \frac{\Delta r}{\Delta t}$ (6.22)
$\Delta c = \frac{\Delta r}{t}$ (6.23)
consequences:
time dilatation and
length contraction
observable
consequences:
universality and
length contraction
real
model-transformation:
observation domain
(measurable)
model domain
(only calculable)
x(r)
M{x(r)}
I. approach
II. transform
III. calculate
IV. transform back
V. result
VI. compare

Fig. 6.17: Model-transformation between theory of relativity and theory of objectivity.

6. 17 Transformation

The observation domain is, as the name already expresses, perceptible (observable) with the help of our sense organs and measurable with corresponding apparatus. The special theory of relativity for the most part provides us the mathematics needed for that. And in that is assumed a constant speed of light. Because a length contraction is being observed and can be measured, a time dilatation must arise as a consequence. Such is the consistent statement of this theory. Because we already could make us clear that it concerns a subjective theory, of course caution is advisable if generalizations are being made, like the one of the inductive conclusion of the length contraction on the time dilatation. We'll come to speak about that in this chapter (fig. 6.20).

The model domain however is not observable to us and only accessible in a mathematical manner. Here the time is a constant. On the other hand do the radii of the particles and all other distances and linear measures stand in direct proportionality to the speed of light. If that changes, then does that lead to a change in length. The length contraction occurs physically, which means actually. We propose the name "theory of objectivity" for the valid theory which is derivable with this prerequisite and independent of the point of view of the observer.

The importance of this model domain and of the possible model calculations is founded in the circumstance that many physical relations within our observation domain aren't recognized by us and can't be mathematically derived. Besides is only all to often worked with unallowed generalizations and with pure hypotheses. Such a thing does not even exist in the model domain.

The model domain can be tapped over a transformation. For that we select an approach x(r) in the to us accessible observation domain. This then is transformed into the model domain by a calculation instruction M{x(r)}. Here we can calculate the sought-for relation In the usual manner and transform back again the result according to the same calculation instruction M^{-1}\{x(r)\} but in the reversed direction. After being returned in our familiar observation domain, the result can be compared and checked with measurement results (fig. 6.17).
In this way we will derive, calculate and compare the quantum properties of the elementary particles with the known measurement values. Here we remind you of the fact that all attempts to calculate the quantum properties conventionally, without transformation, until now have failed. Not even a systematization may succeed, if it concerns for instance explanations for the order of magnitude of the mass of a particle.

A transformation at first is nothing more than an in usefulness founded mathematical measure. But if a constant of nature, and as such the quantum properties of elementary particles until now have to be seen, for the first time can be derived and calculated with a transformation then this measure with that also gains its physical authorization. We now stand for the question: how does the instruction of transformation M{x(r)} read, with which we should transform the approach and all equations from the observation domain into the model domain?

general relations:	special theory of relativity	theory of objectivity
domain of validity:	observation domain	model domain
speed of light c [m/s]:	$c = c_o$ $= \text{constant}$	$c \sim r$ (6.25)
field strengths (6.15)	(6.15) + (6.18)	
H [A/m] :	$H \sim 1/r^2$	$H \sim 1/r$ (6.27*)
E [V/m] :	$E \sim 1/r^2$	$E \sim 1/r$ (6.27)
because of eq. (5.6) $\varepsilon \cdot \mu = 1/c^2$ is valid:		
μ [Vs/Am] :	$\mu_0 = \text{const.}$	$\mu \sim 1/r$ (6.28*)
ε [As/Vm] :	$\varepsilon_0 = \text{const.}$	$\varepsilon \sim 1/r$ (6.28)
relations of material: $B = \mu \cdot H$ (3.5): B [Vs/m^2]	$B \sim 1/r^2$	$B \sim 1/r^2$ (6.29*)
$D = \varepsilon \cdot E$ (3.6): D [As/m^2]	$D \sim 1/r^2$	$D \sim 1/r^2$ (6.29)
e.g. spherical capacitor capacity: C [As/V]	$= \varepsilon 4 \pi r$ (6.4)	$C = \text{const.}$ (6.30)
charge: Q [As]	$= C \cdot U$ (6.31)	$Q = \text{const.}$ (6.32)
energy: W [VAs]	$= Q^2/C$ (6.1)	$W = \text{const.}$ (6.33)
with energy-mass relation: (5.24) and (6.1)	$W = mc^2$	
mass	m [kg = VAs^3/m^2]	$m \sim 1/r^2$ (6.34)
relaxation time	τ_1 [s]:	$\tau_1 = \text{const.}$ (6.35)
with	$\tau_1 = \varepsilon/\sigma$ (5.3)	
specific conductivity	σ [A/Vm]:	$\sigma \sim 1/r$ (6.36)

Fig. 6.18: Transformation of the dependencies on radius

6.18 Transformation table

The attempt to write down at this point already a closed mathematical relation as instruction of transformation, would be pure speculation. Such an instruction first must be verified by means of numerous practical cases, i.e. be tested for its efficiency and correctness. But we not even know the practical examples necessary for this purpose, if we apply the transformation for the first time!
For his reason it unfortunately is not yet possible, to calculate absolute values in a direct
We have to be content to work with proportionalities and to carry out comparisons.
In fig. 6.18 the proportionalities are compared in the way, how they would have to be transformed: on the left side, how they appear and can be observed in the view of the special theory of relativity, and on the right side, how they can be represented and calculated in the theory of objectivity.
The change, which here would have to be transformed, is the physical length contraction, which is the change in length as it depends on the speed of light. For spherical symmetry the length 1 becomes the radius r (eq. 6.26), of which is to be investigated the influence. In the observation domain we had derived the proportionality (6.15 + 6.18):

$E \sim 1/r^2$ and $H \sim 1/r^2$.

The field of a point charge or of a spherical capacitor confirms this relation:

$$E = Q/\varepsilon 4\pi r^2 .$$

Because the speed of light in our observation is constant, also both constants of material which are related to it (eq.5.6: $\varepsilon \cdot \mu = 1/c^2$), the dielectricity ε and the permeability μ, are to be taken constant.
With that the same proportionality as for the field strengths also holds for the induction B and the dielectric displacement D:

$$B \sim 1/r^2 \quad \text{and} \quad D \sim 1/r^2.$$

In the model domain everything looks completely different. Here the radius and any length stands in direct proportionality to the speed of light. In this way we get problems with our usual system of units, the M-K-S-A-system (Meter-Kilogram-Second-Ampere). The basic unit Meter [m] and as a consequence also the unit of mass Kilogram [kg = VAs^3/m^2] appear here as variable. It would be advantageous, to introduce instead the Volt [V] as basic unit.
But in any case does the dimension of a quantity show us, in which proportionality it stands to the unit of length. This in the model domain then is authoritative! As an example does the speed of light have the dimension Meter per Second. In the model domain there consequently has to exist a proportionality to the length r [m].
The speed of light determines with equation 5.6 again the constants of material:

$$\mu\,[Vs/Am] \sim 1/r \quad \text{and} \quad \varepsilon[As/Vm] \sim 1/r \qquad (6.28)$$

According to the model holds unchanged:

$$B\,[Vs/m^2] \sim 1/r^2 \quad \text{and} \quad D\,[As/m^2] \sim 1/r^2. \qquad (6.29)$$

But if we insert the proportionalities 6.28 and 6.29 into the equations of material 3.5 and 3.6, then holds for the field strengths:

$$H\,[A/m] \sim 1/r \quad \text{and} \quad E\,[V/m] \sim 1/r. \qquad (6.27)$$

Further dependencies of the radius can be read in the same manner either by inserting into well-known laws or immediately from the dimension.



In the observation domain:

energy density of a field:

$$w = (\varepsilon \cdot E^2 + \mu \cdot H^2)/2 \quad \sim \quad 1/r^4 \qquad (6.37)$$

energy: $W \sim 1/r$ (6.38)

with c = constant and $W = m \cdot c^2$: $\boxed{m \sim 1/r}$ (6.39)

e^- is bigger and lighter than p^+ or n^0!

$$\boxed{\frac{m}{m_0} \overset{(6.39)}{=} \frac{r_0}{r} \overset{(6.26)}{=} \frac{l_0}{l} \overset{(6.24^*)}{=} \frac{1}{\sqrt{1 - (v/c)^2}}} \qquad (6.40)$$

In the model domain:

e.g. spherical capacitor

capacity: C [As/V] $= \varepsilon 4\pi r$ (6.4) | $C = \text{const.}$ (6.30)

charge: Q [As] $= C \cdot U$ (6.31) | $Q = \text{const.}$ (6.32)

energy: W [VAs] $= Q^2/C$ (6.1) | $\boxed{W = \text{const.}}$ (6.33)

(6.33) means: law of conservation of energy!

relaxation time τ_1 [s]: | $\tau_1 = \text{const.}$ (6.35)

with $\tau_1 = \varepsilon/\sigma$ (5.3)

specific conductivity σ [A/Vm]: | $\boxed{\sigma \sim 1/r}$ (6.36)

(6.36) means: elementary vortices are indestructible!

Fig. 6.19: Interpretation of the dependencies on radius

6.19 Interpretation of the transformation table

The transformation should tell us, what we would see if the variable speed of light would be observable to us. Doing so highly interesting results come out.
The energy density of a field is as is known $w = (\varepsilon \cdot E^2 + \mu \cdot H^2)/2$. (6.37)
In the observation domain will, according to fig. 6.19, decrease the energy density w proportional to $1/r^4$. Multiplied with the respective volume we obtain for the energy itself the proportionality: $W \sim 1/r$. (6.38)
If we make use of the Einstein relation $W = m \cdot c^2$
with c = constant holds also for the mass m: $m \sim 1/r$. (6.39)
In this manner we finally find out, why the small nucleons (protons and neutrons) subjectively seen are heavier than the very much larger electrons. As a consequence does a relativistic particle experience the increase of mass (with the length contraction according to equation 6.24*):

$$\boxed{\frac{m}{m_0} \overset{(6.39)}{=} \frac{r_0}{r} \overset{(6.26)}{=} \frac{l_0}{l} \overset{(6.24^*)}{=} \frac{1}{\sqrt{1-(v/c)^2}}} \qquad (6.40)$$

This result is experimentally secured. Our considerations therefore are entirely in accord with the Lorentz-transformation. There at least is no reason to doubt the correctness.
In the model domain we with advantage assume a spherical symmetry. As easily can be shown with equations 6.4 and 6.31, are the capacity and charge of a spherical capacitor independent of the radius (6.30 and 6.32). In that case also the from both values calculable energy (6.1) must be constant. We come to the same conclusion, if take we the above equation 6.37 for the energy density of a field or if we carry out a verification of dimensions:
W [VAs] = konst. . (6.33)
This simple result is the physical basis for the law of conservation of energy! With that we have eliminated an axiom.
The result states that the energy stays the same, even if the radius, the distance or the speed of an object should change. To the subjectively observing person it shows itself merely in various forms of expression. Consequently is the energy, as is dictated by the here presented field theory, formed by binding in the inside of the quanta the same amount of energy but of the opposite sign. The amount of energy therefore is bound to the number of the present particles, as we already had derived.
Under the assumption of a constant time (6.35) there results for the electric conductivity σ, by calculating backwards over the equation of the relaxation time (5.3), the proportionality: (6.36)

$$\boxed{\sigma\,[\mathrm{A/Vm}] \sim 1/r} \qquad (6.36)$$

Maybe the result surprises, because it can't be observed. Actually we know that the (microscopically observed conductivity in reality only represents an approximated averaged measure for the mobility of free charge carriers. In a particle-free vacuum however this well-known interpretation doesn't make sense anymore. Hence it is recommended, to only work with the relaxation time constants. Who nevertheless wants to continue to work with σ as a pure factor of description, can do this. But he mustn't be surprised, if in the model domain with decreasing radius the conductivity suddenly increases. But this is necessary, because otherwise the elementary particles would collapse. Only by the increase of the conductivity, which is produced by the spherical vortex itself, will the expanding eddy current build up in the inside of the particles, which counteract the from the outside concentrating potential vortex.

Approach:

a.The particles don't decay by themselves, but only by a corresponding disturbance from the outside.

b.The decay time is the statistical average in which such a disturbance can occur and take effect.

c.The elementary particles consist of an integral and finite number of elementary vortices, which can't decay anymore for their part.

d.If the compound particles get into the disturbing range of influence of high-frequency alternating fields, then they are stimulated to violent oscillations and in that way can be torn apart into individual parts.

e.As disturbing factor the high-frequency fields of flying past neutrinos are considered primarily.

f. Authoritative for the threshold of decay and with that also for the rate of decay is the distance, in which the neutrinos fly past the particle.

g.The distance becomes the larger, the smaller the particle is. If the particle thus experiences a relativistic length contraction, then it will, statistically seen, to the same extent become more stable!

That has nothing to do at all with time dilatationl

We are entitled to demand a simultaneity, after all we are the ones, who tell what that is!

Fig. 6.20: Proposal for an interpretation of the particle decay

<i>: Walter Theimer: Die Relativitatstheorie, Seite 106, Francke Verlag, Bern, 1977, ISBN 3-772O-126O-4

6.20 Particle decay

We still have to get rid of a fundamental misunderstanding. It concerns the problem of the time dilatation. Here the model domain doesn't give us any difficulty, because it dictates a constant and therefore by us definable time. In the relativistic view however should in moving systems clocks go wrong! But how does one want to explain a time dilatation physically, if it merely represents a purely mathematical result of the actually taking place length contraction on the one hand and the postulate of a constant speed of light on the other hand?

Nobody has troubled more about the physical interpretation than Einstein himself. But he had as less as we nowadays the possibility to verify the so-called phenomenon experimentally, by accelerating a laboratory clock to values close to the speed of light. Only atomic particles can, e.g. in accelerator systems, be brought on such high speeds and then be observed for their properties. But also these experiments don't have any power of proof, as long as we don't know the atomistic structure of the particles and there exists the danger of misinterpretations.

So the slowing down of the rate of decay of instable. particles at high speeds willingly is cited as "proof for time dilatation[i]. "The most cited example for the time dilatation is the "long-living" meson. The μ-meson is a charged particle, which exists only 2,2 * 10^{-6} seconds if it is observed in rest. Then it decays ... About 10 % of the mesons reach the earth's surface. Even if they fly with approximately the speed of light, they at least must have used 30 • 2,2 * 10^{-6} seconds, in order to reach the earth. Their "life" therefore by the movement has been extended for a multiple... to the supporters of the theory of relativity here the time dilatation is revealed..."

This "proof however is worthless, as long as "the structure and the mechanism of decay of the particle are not known", like W. Theimer[i] expresses himself.

On the basis of the new field theory the approach standing on the left page is dared (fig. 6.20). Accordingly the particles don't decay by themselves, but only by a corresponding disturbance from the outside, which for instance is triggered by the high-frequency fields of flying past neutrinos. The closer the neutrinos fly past the particle, the sooner it will decay. But the distance becomes the larger, the smaller the particle is. If the particle thus experiences a relativistic length contraction, then it will, statistically seen, to the same extent become more stable!

That has nothing to do at all with time dilatation, as this proposal for an interpretation shows (fig. 6.20). The same effect of course also occurs, if atomic clocks are taken for a fly in a plane and compared to identically constructed clocks on earth.

The time was stipulated by us and therefore should be able to keep its universal validity. We are entitled to demand a simultaneity, after all we are the ones, who tell what simultaneity is!

An interesting technical use would be the acceleration of the rate of decay in order to dispose of radioactively contaminated waste. For that the waste has to be irradiated by collecting and focussing free neutrinos or with the help of a neutrino transmitter, like one which will be discussed in chapter 9. After such a neutrino shower dangerous radioactive waste would be reusable or at most be harmless domestic refuse.



Fig. 7.0: The comparison with power of proof:
▨ the measured particle mass
■ the calculated particle mass

7. Proof

Ample evidence is available for the correctness of the theory of objectivity. The field dependent change in length is observed and used as magnetostriction or electrostriction. If a ferromagnetic material, e.g. a nickel rod, is brought into an alternating magnetic field, then field dependent longitudinal length oscillations are observed. In the same manner barium titanate or quartz crystal oscillates in the electric field if a high-frequency alternating voltage is applied.
A practical application forms the production of ultrasound.

In this chapter are, as already announced, the quantum properties of the elementary particles calculated and in this way is furnished perhaps the most convincing proof for the existence of potential vortices and for the correctness of the field-theoretical approach and the theory which is based on it.
A special challenge represents the calculation of the particle mass. This mass stretches from 207 electron masses of the myon over 1839 of the neutron into the order of magnitude of 18513 electron masses (Y°). Doing so not only can be tested, if the calculated values correspond with the measured ones. Also the gaps have to correspond, i.e. where there doesn't exist a discrete mathematical solution also no particle should exist. The fig. 7.0 standing on the left page anticipates the result and shows that even this strict condition is fulfilled! The agreement of the calculated with the measured results is excellent. If in individual cases small deviations become visible, we always have to bear in mind that the measurements as a rule are analysed statistically and the results are falsified if small particles creep in unrecognized. Particle physics nowadays has at its disposal extremely precise gauges, but even here remaining errors can't be excluded.

Quantum physics is occupied with further taking apart the elementary particles into hypothetic particles, the quarks, and to sort these according to properties and symmetries. Seen strictly causal this procedure thus corresponds to the quantum physical approach. We however have taken the field-theoretical approach, and this excludes the introduction of hypothetic particles from the start. It should be our goal to derive and to explain the quantum structure as a field property. Yes, we even want to calculate it, with which we would have overtaken quantum physics in the scientific competition with one leap!

Strong support our approach has experienced by current experiments, in which matter was transformed in electromagnetic waves - practically the reversal of the rolling up of waves to vortices. To do so at the Massachusetts Institute of Technology (David Pritchard and others) sodium atoms were dematerialized in waves by lattice scattering<i>. According to Einstein one surely could have blown the whole M.I.T. in the air with the occurring mass defect; but don't worry, no emission of energy whatsoever has been observed, entirely as predicted by the vortex theory.

<i>: J. Teuber: Materie und Energie, Ganze Atome wurden zu Energiewellen,
Illustrierte Wissenschaft Nr. 7 (1996), S. 56

With the classical radius of the electron $r_e = 2{,}82 * 10^{-15}$ m:

$$C_e = \varepsilon_o \cdot 4\pi r_e = 3{,}135 \cdot 10^{-25}\mathrm{F} \tag{6.4*}$$

$$U_e = e/C_e = 511\mathrm{kV} \tag{6.31*}$$

(constant independent of r_e)

Formation forms (vortex properties):

I. Amassing (formation of vortex balls):



II. Overlapping (phenomenon of transport)



Fig. 7.1: The amassing and overlapping of elementary vortices

7.1 Elementary vortices

We had derived the electron and the positron as elementary vortices (fig. 4.3). Before we can go in the calculation, we must gain a clear picture of the possible configurations of vortices, which for reason of the derived properties are possible. For that we start with the elementary vortex and afterwards we predict the behaviour of interaction which can be expected.

Actually only one single particle is really elementary. According to the realizations of the new theory it is an elementary vortex in the form of a sphere. Its size is determined by the speed of light and this again by the local field strength; its stability is founded in the concentration effect of the potential vortex. The whirling takes place everywhere with the speed of light, even in the vortex centre, where all field lines run together, where the field increases infinitely and the speed of light goes to zero. This last circumstance owes the elementary vortex its localization.

We can attribute a charge to this vortex for reason of the field lines which on the outside run towards infinity and which we can measure (fig. 4.3). This is the smallest indivisible unit, the elementary charge e. Structure and course of the field lines suggest to understand and to calculate the elementary vortex as a spherical capacitor. By basing on the classical radius of the electron r_e given in fig. 6.3 the capacity according to equation 6.4 is calculated to be:

$$C_e = \varepsilon_0 \cdot 4\pi r_e = 3{,}135 \cdot 10^{-25}\,\mathrm{F} \quad (6.4^*)$$

Here the theory of objectivity has provided us the realization that even for a change of the radius of the electron the capacity remains unchanged constant (6.30), and this entirely corresponds to our observation.

Between the hull of the elementary vortex, measured at the radius r_e, and its centre, respectively also with regard to infinity, there exists according to equation 6.31 the tension voltage of:

$$U_e = e/C_e = 511\ \mathrm{kV} \quad (6.31^*)$$

It as well is constant and independent of the size of the elementary vortex.

Since a different solution is refused, we'll have to assume that all elementary particles consist of an integer multiple of elementary vortices. For that the amassing, like closely packed tennis balls, or the overlapping of individual vortices in the form of shells, like in the case of an onion (phenomenon of transport) can be considered.

The among each other occurring forces of attraction can be traced back to the fact that every elementary vortex is compressed by the field of its neighbour as a consequence of the field dependent speed of light. This field as a rule is for the small distances considerably larger than the field on the outside. Therefore do compound elementary particles not have the twofold or triple mass, but at once the 207-fold (myon) or the 1836-fold (proton) mass. After all there is no other explanation for the fact that there don't exist lighter particles (with a mass less than 207 electron masses)!

a. The electron-positron pair


+
-
e⁻
e⁺
„ green “
„ red “

b. . The e^- - e+ pair for a small distance:


+
-
e⁻
e⁺
„ green “
„ red “

Fig. 7.2: The electron-positron pair annihilation

7.2 Matter and anti-matter

For the amassing or overlapping of elementary vortices several cases must be distinguished, because two inverse forms of formation are possible for the elementary vortex: the negatively charged electron and the positively charged positron. Whereas in the case of the electron the vortex produces a component of the electric field which points from the inside to the outside, has the field in the case of the positron the opposite direction for reason of a reversed swirl direction.

This statement can be generalized: if we consider the elementary particles from the outside, then we assign the particles with a swirl direction identical to that of the electron to the world of matter and call the particles with the opposite swirl direction anti-matter. It now is strongly recommended, to take colours to hand, in order to optically clarify the properties of vortices. The electron will be marked as a green sphere and the antiparticle, the positron, as a red sphere.

If we now look into the world of matter, then appears our world of matter to us "green", the world of anti-matter however "red". The uniform green colour of all the in our world existing elementary particles however doesn't exclude that red anti-vortices can exist hidden in the inside of the green vortices, where we can't discover them. But they must be completely covered, otherwise a disastrous reaction occurs, the pair annihilation, as a consequence of the oppositely directed property of the vortices which cancel out. By means of the pair annihilation a dematerialization can occur, because every elementary vortex keeps in its inside the same amount of energy with opposite sign and the fusion of two inverse particles can result in a zero sum of the energy. The best known example is the annihilation of an electron-positron pair under emission of radiation discovered by Klemperer in 1934. In the upper representation (fig. 7.2a) the elementary vortices still are symmetrical, but the outside field lines already are "bent" and linked together in such a way that, with the exception of the ones in the direction of the axis, no interaction takes place which can be measured.

The two particles for reason of the different charge approach each other quickly, and the closer they are, the larger the mutual force of attraction becomes; a vicious circle, which leads to the asymmetry shown in the lower sketch (fig. 7.2b) and only comes to rest, if both particles have destroyed themselves mutually.

The electron and the positron had the same amount of, but oppositely directed swirl activity, so that purely arithmetically seen a zero sum of the rest energy results. But it should be paid attention to both particles having some kinetic energy on the occasion of the relative motion to each other and if they rotate around their own axis also rotational energy. An emission of annihilation radiation occurs, is the explanation of particle physics.

With the knowledge of the photon (fig. 4.6) we can interpret the annihilation radiation as a consequence of the phenomenon of transport. The faster and consequently smaller vortex, for instance the green one, slips into the red one and sees the green inside, which is compatible for it. Unfortunately it only can remain there, as long as it is smaller, thus is faster, and therefore it shoots out on the other side again. Now the electromagnetic force of attraction fully takes effect. It is slowed down and the red vortex correspondingly accelerates. The process is reversed.

These around each other oscillating vortices, so we had derived, have a characteristic frequency (colour), are polarizable and are moving forward with the speed of light as a consequence of the open vortex centre. It therefore concerns the photon.


−
+
positron
(red)
electron
(green)
−

Fig. 7.3: Theoretical final state of the positronium = static γ-quant (photon).

7.3 Positronium

But before the two elementary vortices, the electron and the positron, are annihilated under emission of radiation, they will for a short time take a shell-shaped, a bound state, in which one vortex overlaps the other.
Its formation we can imagine as follows: an electron, flying past a resting positron, is cached by this for reason of the electromagnetic attraction and spirals on an elliptic path towards the positron. In doing so its angular velocity increases considerably. It will be pulled apart to a flat disc for reason of the high centrifugal forces, to eventually lay itself around the positron as a closed shell.
Now the red positron sees the electron vortex so to speak "from the inside" and doing so it sees as well red; because the green vortex has a red centre and vice versa! The result is the in fig. 7.3 given configuration.

The number of field lines, which run from the red border of the positron in the direction of the centre, is identical to the number, which point towards the green border of the electron. Here already the same state has been reached as in the centre, which corresponds to the state at infinity. That means that no field lines point from the green border to the outside; seen from the outside the particle behaves electrically neutral. It doesn't show any electromagnetic interaction with its surroundings.

If the particle were long-living, then it undoubtedly would be the lightest elementary particle besides the electron; but without stabilizing influence from the outside the positronium can't take the in fig. 7.3 shown state at all. The positron takes up the kinetic energy which is released if the electron becomes a shell around it. But before the bound state can arise, which would identify the positronium as an elementary particle, the equal rights of both vortices comes to light. With the same right, with which the electron wants to overlap the positron, it itself vice versa could also be overlapped.
If the stabilization of the one or the other state from the outside doesn't occur, then the stated annihilation under emission of y-quanta is the unavoidable consequence (fig. 4.6).

a. The electron pair:


H
N
S
e⁻
e⁻
S
N
Spin: + ½ π
− ½

b. The electron pair for a small distance:


H
e⁻ (green)
e⁻ (green)

Fig. 7.4: Two electrons with oppositely directed spin

7.4 Dipole moment

As electrically charged spheres elementary vortices have a magnetic dipole moment along their axis of rotation as a consequence of the rotation of their own (fig. 7.4). This is measurable very precisely and for the most important elementary particles also known quantitatively. In contrast to the angular momentum the magnetic moment can't be constant according to the here presented theory. It should slightly change, if we increase the field strength in the laboratory.

In a particle consisting of several elementary vortices the vortices mutually increase the local field strength. Therefore we measure at the proton, which consists of three vortices, not the triple, but only the 2,793-fold of the nuclear magneton which can be expected for reason of its mass. Also the neutron has instead of the double only the 1,913-fold nuclear magneton. The deviations therefore are explicable as a consequence of the surrounding fields.

Prerequisite for this point are two other, still unanswered, key questions of quantum physics:

> XII: Why is measured for the proton approximately the triple of the magnetic dipole moment which can be expected for reason of the charge?
>
> XIII: Why does the neutron, as an uncharged particle, actually have a magnetic moment?

These questions can only be brought to a conclusive answer, if we have derived the vortex structures of the respective particles.

The elementary vortex, as a consequence of the spin along its axis, forms a magnetic north pole and a south pole. Another possibility to interact with an external field or with other particles is founded on this property. This shall be studied by means of two electrons. which form an electron pair.

For reason of the equal charge the two electrons at first will repel each other. If they rotate of their own they however will mutually contract, which, seen from the outside, is interpreted as a force of attraction. And in addition will they align their axes of rotation antiparallelly. While they now rotate in the opposite direction, a magnetic force of attraction occurs.

As is shown in fig. 7.4, the magnetic dipole field in this way is compensated towards the outside, as is clarified by the field line (H) with a closed course. Between both electrons a space free of E-field stretches. If both vortices are a small distance apart they lay themselves around this space like two half-shells of a sphere. A particle forms which seen from the outside is magnetically neutral, but it carries the double elementary charge (fig. 7.4b).

The exceptional affinity is always restricted to two vortices of equal charge with an opposite direction of rotation. Further vortices can't be integrated anymore and are repelled. This property of vortices covers the quantum condition (Pauli's exclusion principle) for the spin quantum number perfectly.


⊕
e⁻
e⁺
e⁻
radius r:
r₁
r₂
r₃
electric field strength E:
E(x)
E₂
c
r₁
r₂
r₃
x,y,z
d
b
a
E₁
E₃
a: theoretical course of the field of a single negative charged body
b: actual course of the field of a μ⁻
c: field of an e⁺
d: field of an e⁻
▨: : difference between the vortex calculation (b) and the classical calculation (a).

Fig. 7.5: The mvon and the electric field E(x) of the three elementary vortices

7.5 Myon

We now have discussed all conceivable possibilities, which two elementary vortices can form: the creation of a pair for like charge and the annihilation under emission of photons via the formation of the positronium as an intermediate result for unequal charge. Next another elementary vortex shall be added and all different possibilities and configurations will be derived, which can be formed by amassing or overlapping.

The positronium can, as said, only take the in fig. 7.3 shown bound structure, if it is stabilized from the outside. This task now a further electron shall take over. According to the shell model the innermost elementary vortex an electron (e^-), is overlapped by a positron (e^+) and that again overlapped by an electron (e^-).
With an in the sum single negative charge, a completely symmetric structure as well as a half-integer spin this particle will show a behaviour corresponding to a large extent to that of the electron. Merely the mass will be considerably larger, because every vortex each time compresses the other two.

It therefore concerns the myon (μ^-), which also is called "heavy electron". The myon was discovered 1937 in the cosmic radiation (Anderson and others).
In fig. 7.5 are drawn above each other the shell-shaped structure of the myon and the electric field E(x) of the three elementary vortices.
It is visible that merely in the proximity of the particle the actual course of the field deviates from and is smaller, than the course which theoretically can be expected for a single negatively charged body. The difference is marked by a hatching.

We now can tackle the calculation of the myon. For that the following considerations to begin with are useful:
Mass is an auxiliary term founded in usefulness, which describes the influence of the electromagnetic field on the speed of light and with that on the spatial extension of the "point mass".
Without exception the local cosmic field E_o has an effect on a free and unbound elementary vortex, thus on an individual e^- or e^+, and determines so its size and its mass. But as long as we haven't determined this field strength, the calculation of its quantum properties won't succeed.
Instead the masses of compound particles will be compared to each other, which are so heavy that the field strength of the neighbouring vortices is predominant over the basic field E_0, so that a neglect of E_o seems to be allowed. The course of the calculation is made for all elementary particles in the same manner, which is explained hereafter.



Spherical capacitor: (r_i = inner radius; r_a = outer radius)

$$U = \int_{r_i}^{r_a} E\,dr \qquad (7.1)$$

Electron ($r_i = 0$ and $r_a = r_e$): $U = 511\ \text{kV} = \text{const.}$ (6.31*)

$$U_1 = U_2 = U_3 = U_4 = \ldots = U_n \qquad (7.2)$$

At The radius r_1 is valid: $E(r_1) = E_1$ and

$$U_1 = \int_0^{r_1} E_1\,dr = E_1 r_1 = U_2 \overset{!}{=} \int_{r_1}^{r_2} E_1\,dr = E_1 (r_2 - r_1) \qquad (7.1^*)$$

At the radius r_2 is valid for the 2nd and 3rd shell $E(r_2) = E_2$:

$$U_2 = \int_{r_1}^{r_2} E_2\,dr = E_2 (r_2 - r_1) = U_3 \overset{!}{=} \int_{r_2}^{r_3} E_2\,dr = E_2 (r_3 - r_2) \qquad (7.1^{**})$$

comparison of the radii:

$$\Delta r = r_1 \overset{(7.1^*)}{=} r_2 - r_1 \overset{(7.1^{**})}{=} r_3 - r_2 = \ldots = r_n - r_{n-1} \qquad (7.3)$$

resp.:

$$r_2 = 2 \cdot r_1; \quad r_3 = 3 \cdot r_1; \quad \ldots ; \quad \boxed{r_n = n \cdot r_1} \qquad (7.4)$$

comparison of the field strengths: (7.1* with 7.1** with Eq. (7.2):

$$E_1 = E_2 = E_3 = \ldots = E_n \qquad (7.5)$$

Theory of objectivity, fig. 6.18: $\boxed{E \sim 1/r}$ (6.25)

see fig. 7.5:

$$E_1(r_3) = E_{31} = -E_1 \cdot (r_1/r_3)$$
$$E_2(r_3) = E_{32} = E_2 \cdot (r_2/r_3)$$
$$E_0 = \text{cosmic basic field} \quad \text{(negligible)}$$

$$E(r_3) = E_{31} + E_{32} + E_0 = E_1 \cdot (r_2 - r_1)/r_3 + E_0 \qquad (7.6)$$

$$\boxed{\frac{E(r_3)}{E_1} = \frac{2 \cdot r_1 - r_1}{3 \cdot r_1} = \frac{1}{3}} \qquad (7.7)$$

Fig. 7.6: Calculation of the electric field strength E(r) of the myon from its dependency on radius

7.6 Calculation of the vortex fields

The tension voltage of an elementary vortex, like for a spherical capacitor, is determined by integrating over the electric field strength from the inner radius r_i up to the outer radius r_a:

$$U = \int_{r_i}^{r_a} E \, dr \quad (7.1)$$

For the electron ($r_i = 0$ und $r_a = r_e$) we already have carried out the integration and determined the tension voltage to be 511 kV (equation 6.31 *).
Doing so we further had discovered that it won't change, if the radius r varies. Even for a shell configuration, in which electrons and positrons alternately overlap, the approach is valid:

$$U_1 = U_2 = U_3 = U_4 = \ldots = U_n \qquad (7.2)$$

At a certain radius all elementary vortices show the same density of field lines and with that also the identical field strength, so that we can solve the integral (7.1) for the each time neighbouring vortex shells and can compare the results:
At the radius r_1 with $E(r_1) = E_1$ the agreement, according to equation 7.1* (fig. 7.6), is valid for the innermost and the overlapped vortex shell.
At the radius r_2 with $E(r_2) = E_2$ the agreement according to equation 7.1** (fig. 7.6) is valid analogously for the 2nd and 3rd shell.
If still more shells are present, then we can arbitrarily repeat this procedure. For the radius of each shell we always obtain relation 7.3, which, related to the innermost radius, provides the following simple expression for the individual radii:

$$r_2 = 2 * r_1 ; \quad r_3 = 3 \bullet r_1; \quad \ldots ; \quad r_n = n * r_1 \qquad (7.4)$$

From the comparison of the integration results 7.1* and 7.1** follows further that all elementary vortices produce the same field strength:

$$E_1 = E_2 = E_3 = \ldots = E_n \qquad (7.5)$$

We infer from the transformation table (fig. 6.18, eq. 6.27) that the field strengths E and H decrease with 1/r. In fig. 7.5 the decrease of the fields with 1/r is shown. Up to the radius r, the field of the innermost vortex E_1 has worn off to the value $E_{31} = - E_1 \bullet (r_1/r_3)$. This field is overlapped by $E_{32} = E_2 * (r_2/r_3)$ as well as the cosmic basic field E_o:

$$E(r_3) = E_{31} + E_{32} + E_0 = E_1 \bullet (r_2 - r_1)/r_3 + E_o \qquad (7.6)$$

The local basic field E_o is not known, but it is very small with regard to the field of the neighbouring vortex shells, so that a neglect seems to be allowed. From equation (7.6) in this way follows with the radius relation (7.4):

$$\frac{E(r_3)}{E_1} = \frac{2 \cdot r_1 - r_1}{3 \cdot r_1} = \frac{1}{3} \quad (7.7)$$

For the shell-shaped configuration of the myon (fig. 7.5) relation (7.7) indicates, which field the outside vortex shell is exposed to. From this can already be seen, how much it is compressed thanks to the field dependent speed of light and how much its mass as a consequence is increased.

Structure of the proton p^+:



Calculation:
structure consisting of two shells, inner vortices with $2 \cdot E_1$,
field strength at the outer radius r_2:

$$E(r_2) = 2 * E_{21} = 2 * E_1 (r_1 / r_2) = E_1 \qquad (7.8)$$

Comparison of p^+ (7.8) with u^- (7.7) (z_e = number of the elementary vortices being involved with) in building up the structure, here each time $z_e = 3$):

Comparison of the radii with $E \sim 1 / r$ (6.27)

$$\frac{r_p}{r_\mu} = \frac{z_{e\mu}}{z_{ep}} \cdot \frac{E_\mu(r_3)}{E_p(r_2)} = \frac{3}{3} \cdot \frac{1/3}{1} = \frac{1}{3} \qquad (7.9)$$

Theory of objectivity (fig. 6.18): $m \sim 1/r^2$ (6.34)

$$\frac{m_p}{m_\mu} = \frac{z_{ep}}{z_{e\mu}} \cdot \left(\frac{r_\mu}{r_p}\right)^2 = \frac{3}{3} \cdot \left(\frac{3}{1}\right)^2 = 9 \qquad (7.10)$$

$$m_p/m_e = 9 * (m_u/m_e) = 9 * 207 = 1863 \qquad (7.11)$$

Measurement value, proton mass: $m_p = 1836 \cdot m_e$
Resp.:
measurement value myon mass $m_u = 207 * m_e$
myon calculated value: $m_p = 204 * m_e$. (error = 1,5%)

Since we, by using this calculation method, for the first time succeeded in deriving the mass of an elementary particle from that of another particle, the particle mass isn't a constant of nature anymore!

Fig. 7.7: Calculation of the proton

7.7 Calculation of the proton

If we again remember the affinity of two elementary vortices, which rotate with opposite spin. They align their axis of rotation antiparallel and form a very probable, but not particularly tight bound pair (fig. 7.4).

If we this time start with a positron pair, then does this pair have a double positive elementary charge. The two e^+ hence exert a particularly big force of attraction on electrons flying past them. If they have cached one and put it round as a shell, like a coat, then they will never again give it back! To again remove the electron, a triple positive charge would be necessary. But such a particle can't exist at all. The new particle therefore has an absolute stability and a very big mass, because the positron pair is considerably compressed by its outer shell. The total charge is single positive. With these properties it actually only can concern the proton. Its structure is shown in fig. 7.7. We can start from the assumption that both positrons are very close together in the inside and thus each forms the half of a sphere. For the calculation of the proton mass we then can assume as an approximation a structure of two shells, in which the inner vortex will have the double charge and the double field ($2 * E_1$). With equation 7.4 the field strength at the outer radius r_2 is:

$$E(r_2) = 2*E_{21} = 2*E_1*(r_1/r_2) = E_1 \qquad (7.8)$$

If we want to compare the results of the p^+ (7.8) and the μ^- (7.7), then it should be considered that the field of the innermost elementary vortex E_1 only is equal, if the number z_e of the elementary vortices involved in building up the particle is identical. Here with each time $z_e = 3$ this is the case. Because of equation 6.27 ($E, H \sim 1/r$) now also the radii are comparable:

$$\frac{r_p}{r_\mu} = \frac{z_{e\mu}}{z_{ep}} \cdot \frac{E_\mu(r_3)}{E_p(r_2)} = \frac{3}{3} \cdot \frac{1/3}{1} = \frac{1}{3} \qquad (7.9)$$

The mass of a particle first is determined by the number of the elementary vortices z_e. According to the theory of objectivity (fig. 6.18) however also the radius has an influence on the mass:

$$m \sim 1/r^2 \qquad (6.34)$$

This proportionality should be applied to the p^+-μ^-- comparison.

$$\frac{m_p}{m_\mu} = \frac{z_{ep}}{z_{e\mu}} \cdot \left(\frac{r_\mu}{r_p}\right)^2 = \frac{3}{3} \cdot \left(\frac{3}{1}\right)^2 = 9 \qquad (7.10)$$

The calculation provides a nine times bigger mass for the proton with regard to the mass of the myon. Therefore the mass of the proton related to the mass of the electron is:

$$m_p/m_e = 9*(m_\mu/m_e) = 9*207 = 1863 \qquad (7.11)$$

It would be favourable, to start from the with measuring techniques determined value for the mass of the proton $m_p/m_e = 1836$ and calculate backwards the related mass of the myon.

Then we obtain 204 as the calculated value instead of the measurement value $m_\mu/m_e = 207$.

The reason for the deviation of 1.5 percent is caused by the neglect of the cosmic field E_o with regard to the field of the neighbouring elementary vortex. This neglect takes very much less effect for the relatively heavy proton than for the light myon.

The cosmic field therefore will compress the myon more strongly and increase the mass more strongly as is calculated here, in agreement with the measurement results.

Summarizing: since we, by using this calculation method, for the first time succeeded in deriving the mass of an elementary particle from that of another particle, the particle mass isn't a constant of nature anymore!


Z
E(e⁺)
E_z
e⁺
e⁺
e⁻
} = p⁺
z
x
y
d
e
b
c
a
r₁
r₂
E(x,y)
E₁(e⁺,e⁺)
d,e
a
b
x,y
r₁
r₂
c
E₂(e⁻)
a: theoretical course of the field of a single positive charged body
b: actual course of the field of the p⁺
c: field of an e⁻
d,e: field of both e⁺
▨: discrepancy between the measurement (b) = the vortex calculation (b) and the classical calculation (a)

Fig. 7.8: The proton and the electric field of the three elementary vortices in x-, y- and z-direction

7.8 "Strong interaction"

A central question of nuclear physics concerns the forces which keep the atomic nucleus, which consists of many neutrons and protons, together and give it its very good stability in spite of the like positive charge (key question XIV fig. 7.13).
According to today's textbook opinion (course of the field indicated with a in fig. 7.8) the forces of repulsion between the individual protons increase further as the distance gets smaller, to obtain immense values within the nucleus. They theoretically had to be overcome by new and unknown nuclear forces. Therefore physicists assume the hypothesis of a "strong interaction". But they are mistaken.
The answer to this open question is provided by the course of the field (b) for the proton, sketched in fig. 7.8. We see that the electric field at first indeed still increases if we approach the proton, but in the proximity it contrary to all expectations decreases again until it is zero. With that then also any force of repulsion has vanished! But the course of the field follows without compulsion from the overlap of the three individual elementary vortex fields.
The field direction in the z-direction even is reversed! In this topsy-turvy world, in theory, an electromagnetic force of attraction between two like charged protons can occur. We conclude:
A strong interaction doesn't exist at all. The usually given values for "range" and "strength" just represent a misinterpretation. The hatched drawn area marks the difference which is misinterpreted by quantum physics. The model concept over and above that answers another mysterious property of the proton. As an electrically charged particle with a spin it first of all should form a magnetic moment for reason of the rotating charge. But until now the measurable order of magnitude couldn't be explained.

7.9 Magnetic moment of the proton

If the inner positrons rotate around each other with oppositely pointing spin, then the magnetic field line is already closed within the particle and no effect in x- or y-direction is observable from the outside.
As pair they however still can rotate together around the z-axis and they'll do that. The overlapping electron for reason of its rotation of its own will likewise build up a magnetic dipole moment along its axis of rotation. It also will align its axis in the z-direction, so that now all three elementary vortices have one field axis. Being comparable to individually "elementary magnets" aligned in the same direction they produce a triple magnetic moment (key question XII fig. 7.13).
If we namely would start with a single positively charged body according to the theory of quantum mechanics, then we would have expected the value of the nuclear magneton<i> p_m as the magnetic moment for the proton $p_m = e \cdot \hbar/2m$. Opposite to that provide experiments with protons the approx. threefold value as already predictable by the new vortex theory. In addition does the direction of the vector p_{mp} correspond with the spin-axis, so as if the proton were negatively charged. The reason for that is that only the outermost elementary vortex determines the spin of the particle, and that is actually a negatively charged electron! Also this excellent agreement in the case of the proton can be judged as proof for the correctness of the vortex model.

<i>: The nuclear magneton has the value of: $p_{mk} = 5{,}0508 \cdot 10^{-27}\ Am^2$

a. n^0 if the e^- amasses to a p^+.


-2 · p_mk
H
N
S
e⁻
+
-
e⁻
-
e⁻
e⁻ } = p⁺
S
N
e⁻
+
p⁺ = n⁰

b. n^0 if the e^- is overlapped by an e^+ of the p^+


-2 · p_mk
H
-
e⁺
+
e⁻
e⁺
e⁻ } = n⁰

Fig. 7.10: The neutron with magnetic dipole field H

7.10 Structure of the neutron

Until now could not be solved, why despite its missing charge also the neutron n° has a magnetic moment. The experimentally determined value is approx. the double of the nuclear magneton. Further was with measuring techniques an only 0,14% bigger mass with regard to the proton determined. The difference is approximately two and a half electron masses. And how reads the answer in the view of the potential vortex theory? It is obvious that a positively charged proton and a negatively charged electron mutually attract and amass together (fig. 7.10a). A pair annihilation can't occur, because the electron, which jackets both positrons, prevents this. The formation of an outer shell is not permitted by the high stability of the proton. It would have to be a positron shell, which instead of neutrality would produce a double positive charge. Conceivable is however the configuration, in which one of the two e^+ of the proton takes up the e^- in its inside and overlaps it (fig. 7.10b).

At first appears the amassing of p^+ and e^- to be the obvious answer to the structure of the neutron also in view of the small increase in mass. Since both elementary particles (p^+ and e^-) have a spin, will they align their axes of rotation antiparallelly and rotate against one another, exactly like an electron pair. But we now have unequal conditions: the proton brings the triple magnetic moment, the electron however only the single, and its field line will be closed by the proton. The difference which remains is the measurable double nuclear magneton, with which key question XIII (fig. 7.13) would be answered exhaustively.
This structure is shown in fig. 7.10a and has as rest mass the by only one electron mass increased proton mass, but it will deviate from this value, when the unequal partner come closer. Doing so the electron will be more strongly compressed by the heavier proton as vice versa.
Mass, magnetic moment and charge thus correspond to a large extent with the measurement values. Problems are seen concerning the spin and the stability.
Set of problems concerning spin: both the e^- and the p^+ have a half-integer spin, for which reason this configuration should have an integer spin.
Set of problems concerning stability: the neutron decays as is well-known in a p^+ and an e^- , but this object should be shorter-lived as determined by experiments. If namely the partner come each other very close, then the field strength of the p^+, contrary to expectation, doesn't increase but decreases, as is shown in fig. 7.8. The e^- therefore can only be bound very, very loosely; in z-direction it even will be repelled!
For these reasons is the open structure, which is shown in fig. 7.10a, not feasible as an isolated elementary particle, but only in a spatially extended network, like it is present in an atomic nucleus. In this case the neutron is, as is well-known, lighter by the mass defect, which is interpreted as binding energy.
Possibly it only concerns an intermediate stage. The heavier final product of the n° then could look like is shown in fig. 7.10b. For this version the line of the magnetic field already is closed partly within the particle, so that also here the approx. double nuclear magneton remains as a rest with a sense of orientation, as if the neutron were negatively charged.
Without charge and with the 1/2 spin it in this configuration fulfils all important quantum properties of the neutron, even that of the stability.

the field of the e^-: $E_{31}(-) = - E_1 (r_1/r_3)$,

the field of the e^+: $E_{32} = E_2 (r_2/r_3) = E_1 (r_2/r_3)$

and in addition the e^+: $E_{3\,1} = E_1 (r_1/r_3)$.

$$E(r_3) = E_{31}{}^{(-)} + E_{32} + E_{31} + \underset{\searrow\text{negligible}}{E_0}$$

With the radius relation (eq. 7.4): $r_2 = 2 * r_1$ und $r_3 = 3 * r_1$
The total field is:

$$\frac{E(r_3)}{E_1} = -\frac{r_1}{r_3} + \frac{r_2}{r_3} + \frac{r_1}{r_3} = -\frac{1}{3} + \frac{2}{3} + \frac{1}{3} = \frac{2}{3} \qquad (7.12)$$

With $z_{en} = 4$ elementary vortices

$$\boxed{\frac{r_n}{r_p} = \frac{z_{ep}}{z_{en}} \cdot \frac{E_p(r_2)}{E_n(r_3)} = \frac{3}{4} \cdot \frac{1}{2/3} = \frac{9}{8} = 1{,}125} \qquad (7.13)$$

n_0 is 12,5% bigger than p±

$$\boxed{\frac{m_n}{m_p} = \frac{z_{en}}{z_{ep}} \cdot \left(\frac{r_p}{r_n}\right)^2 = \frac{4}{3} \cdot \left(\frac{8}{9}\right)^2 = 1{,}05} \qquad (7.14)$$

n^0 is 5% heavier than p±

Fig. 7.11: Calculation of the mass of the neutron

7.11 Calculation of the neutron

The calculation of the mass for the structure of the neutron according to fig. 7.10b has still remained open.

Because in this book for the first time has been shown, how the mass can be calculated, if the particles are understood as potential vortices, we also in this case again want to make use of this possibility.
We have, like for the μ^-,a structure of three shells with the radii r_1, r_2 and r_3. At the outer radius r_3 the fields of the elementary vortices on the inside have an effect on the electron On the outside: like is the case for the μ^-

the field of the e^-: $E_{31}^{(-)} = -E_1(r_1/r_3)$,

the field of the e^+: $E_{32} = E_2\,(r_2/r_3) = E_1\,(r_2/r_3)$

and in addition the e^+: $E_{31} = E_1\,(r_1/r_3)$.

The total field is, with the radius relation equation 7.4:

$$\frac{E(r_3)}{E_1} = -\frac{r_1}{r_3} + \frac{r_2}{r_3} + \frac{r_1}{r_3} = -\frac{1}{3} + \frac{2}{3} + \frac{1}{3} = \frac{2}{3} \quad (7.12)$$

If we compare the neutron, in which now $z_e = 4$ elementary vortices are involved, with the proton:

$$\frac{r_n}{r_p} = \frac{z_{ep}}{z_{en}} \cdot \frac{E_p(r_2)}{E_n(r_3)} = \frac{3}{4} \cdot \frac{1}{2/3} = \frac{9}{8} = 1{,}125 \quad (7.13)$$

then we infer from the arithmetically determined result that the neutron according to the radius is 12,5% bigger than the proton. The mass is calculated to:

$$\frac{m_n}{m_p} = \frac{z_{en}}{z_{ep}} \cdot \left(\frac{r_p}{r_n}\right)^2 = \frac{4}{3} \cdot \left(\frac{8}{9}\right)^2 = 1{,}05 \quad (7.14)$$

The particle therefore has a mass which is 5% larger than for the proton, slightly more as has been measured for the neutron. The difference is acceptable. The particle after all is structured very asymmetrically, in which the reason is to be seen, why the uncharged particle, looked at from close up, nevertheless shows an observable charge distribution.

Decay equations if neutrinos are involved:

$$n^0 \longrightarrow p^+ + e^- + \bar{\nu}_e \qquad (7.15)$$

$$n^0 + \nu_e \longrightarrow p^+ + e^- \qquad (7.15^*)$$

$$\mu^- \longrightarrow e^- + \bar{\nu}_e + \nu_\mu \qquad (7.16)$$



Fig. 7.12: The electron-neutrino as a ring-like vortex

7.12 ß-decay

In the case of the calculated quasistable particles, the μ^- and the n°, the verification by means of the well-known decay processes is still due. Also free neutrons, those which are not bound in an atomic nucleus, decay. But with an average life of 918 seconds they are by far the longest living among the quasistable elementary particles. Should the neutron decay be triggered by neutrinos, then obviously a distant flying past does not suffice. For that the electron is bound in the proton too tight. There probably has to occur a direct "crash", in which a neutrino is used, since the decay equation reads:

$$n^0 \longrightarrow p^+ + e^- + \bar{\nu}_e \quad (7.15)$$

As could be expected a proton p^+, an electron e^- and the mentioned electron-antineutrino ν_e are formed. What here is written down as the emission of an antiparticle, is equivalent in the absorption of the particle[i], in this case of the neutrino. The reaction equation 7.15 can be reformulated accordingly[i]:

$$\boxed{n^0 + \nu_e \longrightarrow p^+ + e^-} \quad (7.15^*)$$

Also for the decay of the myon an electron-neutrino is used. In both cases it provides the energy necessary for the decay. But we can really understand the β-decay only, after we have got to know these particles better.

Without charge and without mass neutrinos show hardly any interactions with matter and as a consequence they possess the enormous ability of penetration - as is well-known. They are said to participate in the „weak interaction", which should trigger a conversion of the concerned particles, which is their decay. Pauli already has postulated the neutrino 1930 theoretically, because the transition from a half-integer spin to an integer spin for the n^0 -decay otherwise wouldn't have been explicable.

If we imagine an elementary vortex is being born, but the local field strength and energy isn't sufficient for obtaining a quantized state. The result is an incomplete potential vortex, which has an open vortex centre and as a consequence shows no localization at all. In the form of a vortex ring it oscillates around itself, while it continually turns its inside to the outside and then again to the inside.

One moment the vortex ring is green, then it is red again, one moment matter, then anti-matter, one moment positively charged and the next moment negatively charged. In contrast to the photon the number of the involved elementary vortices z_e for the neutrino is odd (for the ν_e z_e= 1). Perpendicular to the direction of propagation the neutrino has a spin $(s/\hbar = \frac{1}{2})$ for reason of a rotation, which overlaps the pulsating oscillation. This vortex ring is, as said, not a member of stationary matter, because it doesn't form a "black hole" in its centre, where the speed of light becomes zero. But it has an absolute stability like every elementary vortex, even if it only occurs incomplete and hence not in any quantized form,. This concept of the electron-neutrino as an open oscillating elementary vortex in the form of a ring-like vortex covers the experimentally determined realizations unexpectedly well.

---

[i] Kussner, H.G.: Grundlagen einer einheitlichen Theorie der physikalischen Teilchen und Felder, Musterschmidt, Gottingen 1976, S.155

A strong interaction doesn't exist. The electric field in the proximity of the proton goes to zero within the range which is determined with measuring techniques.

A weak interaction doesn't exist. That interaction only is a special case of the electromagnetic interaction which appears in a weakened form.

XII: Why does the proton have approximately 3 times the magnetic moment which can be expected for reason of the only single charge?
(3 elementary vortices)

XIII: Why does the neutron as an uncharged particle anyway have a magnetic moment?
(Structure of the n°)

XIV: What owes the atomic nucleus, which consists of like charges, its stability?
(Course of the field of the p^+, instead of "strong interaction")

XV: Why does the free neutron decay, although it is stable as a particle of the nucleus?
(Interaction with neutrinos)

XVI: Why do neutrinos nevertheless participate in the "weak interaction", although they have no mass and no charge?
(Oscillating charge)

XVII: How can be given reasons for the finite range of the "weak interaction"?
(Reaction cross-section for particle decay)

Fig. 7.13: Further key questions of quantum physics (Continuation of figures 4.4 and 6.13)

7.13 "Weak interaction"

Let's now look again at the β-decay of the neutron, in which a neutrino ν_e is used. But this by no means will be a process of the weak interaction. Instead will neutrinos, contrary to the textbook opinion, participate in the electromagnetic interaction. They after all are one moment positively charged and the next moment negatively charged. With slow-acting gauges this it is true can't be proven, because the interaction is zero on the average. But this charged oscillating vortex ring can exert a considerable effect while approaching a neutron, which is based solely on the electromagnetic interaction.
The neutron is stimulated to synchronous oscillations of its own by the high-frequency alternating field of the neutrino, until it in the case of the collision releases the bound electron, which takes up the energy provided by the neutrino and transports it away. The interaction obviously is only very weak due to the oscillation. But a physical independency of it has to be disputed.
The finite range, which is given in this context, indicates the reaction cross-section around the n°-particle, within which the "crash" and as a consequence the β-decay occurs. This range is considerable larger as the particle itself. The electromagnetic interaction for such small distances after all is so violent, even if it only occurs in pulses, that the neutrino is thrown out of its path and can fly directly towards the neutron.

Perhaps we now understand also the β-decay of the myon. It actually were to be expected that without outside disturbance an absolute stability could exist because of the ideal symmetry of the μ^-. On our planet we however are in every second bombarded with approx. 66 milliard (billion) neutrinos per cm^2 <i>. Obviously it takes 2,2 μs on the average till a neutrino ν_e flies past a myon so close that it decays. In doing so it stimulates the outside elementary vortex to violent oscillations by trying to synchronize it. In this case the electron-neutrino ν_e carries away with it the two outer, and therefore weaker bound, elementary vortices of the myon, which meanwhile are oscillating synchronously. The innermost vortex, an electron e^-, is left behind. The decay of the myon which takes place with a probability of almost 100 % reads:

$$\mu^- \longrightarrow e^- + \bar{\nu}_e + \nu_\mu \qquad \text{resp.} \qquad \mu^- + \nu_e \longrightarrow e^- + \nu_\mu \quad (7.16)$$

Thus a different neutrino ν_μ, is formed which can be distinguished from the ν_e and is called myon-neutrino since it forms from the μ^-. Actually it even has a similar structure of three shells, as is shown in fig. 7.5. But the vortex centre is open and the particle isn't stationary anymore. In the picture now only a momentarily state is shown, in which the ν_μ appears green on the outside and red in its open centre. As already for the ν_e oscillates also here the inside to the outside and vice versa, this time merely as a packet of three shells, so that also this particle shows all the typical neutrino properties discussed for the example of the ν_e.
The for potential vortices typical and already discussed phenomenon of transport here has an effect. In particular in connexion with vortex rings this property is known from hydrodynamics. It thus can be observed, how vortex rings bind matter and carry away with them. Because the neutrino is not quantized, it neither is restricted with regard to its ability to transport elementary vortices. Consequently even bigger configurations are conceivable, like configurations of 5 shells, 7 shells etc..

<i>: "Zeugen aus der Sonne", VDI-Nachrichten Nr. 45 vom 9.11.90, Seite 26

a: the structure of the tau-neutrino with 5 shells


colour of the elementary vortices
from the outside to the inside
gn/rd/gn/rd/gn
i.e.
$e^-/e^+/e^-/e^+/e^- = \nu_\tau$

b: the heavy and stable variant of the tau particle


(gn/rd + gn/rd)gn
resp.
$(e^-/e^+ + e^-/e^+)e^- = \tau^-$

Fig. 7.14: Tau-neutrino and tau particle

7.14 Tau particle

In the table of the leptons after the e^- and the μ^- as the next particle the tau particle τ^- is found with its accompanying neutrino ν_τ.The obvious solution for the tau particle is the structure of five shells, as is shown in fig. 7.14a. With that the electron would have another particularly heavy relative with otherwise very similar properties.
For the myon the neutrino was stable, the particle itself however instable. We after all huve explained the particle decay as a consequence of an outside disturbance, and disturbances always are based on interactions. Correspondingly should, with the small possibility for an interaction, also the neutrino ν_τ of the tau particle have a better stability than the particle τ^- itself.
Without doubt this structure of 5 shells fulfils all known quantum properties like spin, charge etc. Merely the check of the mass is still due. This we now want to calculate for the structure shown in fig. 7.14a.

$$m_5 = m_p \cdot \left(\frac{Z_{e\tau}}{Z_{ep}}\right)^3 \cdot \left(-\frac{r_1}{r_5} + \frac{r_2}{r_5} - \frac{r_3}{r_5} + \frac{r_4}{r_5}\right)^2 \quad (7.17)$$

$$m_5 = 1836 \cdot \left(\frac{5}{3}\right)^3 \cdot \left(\frac{2}{5}\right)^2 \cdot m_e = \underline{\underline{1360 \cdot m_e}} \quad (7.17^*)$$

But the for the tau particle measured value is considerable higher!
Even if this structure is the only possible in the case of the neutrino ν_τ for reason of the complete symmetry, will the tau particle however change its structure by itself if another structure exists, which is more stable, thus in which the particle can take a bigger mass. Such a maximum provides the structure shown in fig. 7.14b after checking all possible configurations with five elementary vortices:

$$m_\tau = m_p \cdot \left(\frac{Z_{e\tau}}{Z_{ep}}\right)^3 \cdot \left(\left(-\frac{r_1}{r_3} + \frac{r_2}{r_3}\right) \cdot 2\right)^2 \quad (7.18)$$

$$m_\tau = 1836 \cdot \left(\frac{5}{3}\right)^3 \cdot \left(\frac{2}{3}\right)^2 \cdot m_e = \underline{\underline{3778 \cdot m_e}} \quad (7.18^*)$$

This value now lies 8% above the measurement values. It would be obvious, if unbound tau particles predominantly would take the structure shown in fig. 7.14b. The remaining error becomes explicable, if a very small number of tau particles in the lighter structure according to fig. 7.14a are involved with a correspondingly smaller probability.

The enormous variety of kinds of decay, and not a single one of the dominating ones has a probability of over 50%, makes it more difficult for us, to be able to directly infer the inner structure of a particle from the decay products. It nevertheless should be mentioned that after all 35% of all decays take place by taking up and using a neutrino ν_e or ν_τ, entirely in accordance with the model of the myon decay (equation 7.16).



name	mass (m/m_e) measured	mass (m/m_e) calculated	el.-vortices z_e	charge Q	radius r/r_p	inner structure of The elementary vortices, colour: (gn=green; rd=red) from the inside to the outside
e^-	1	-	1	-1	-	Fig. 4.3 gn
γ^0	-	136	2	0	3	Fig. 7.3 rd/gn
μ^-	207	204	3	-1	3	Fig. 7.5 gn/rd/gn
η^0	1072	1088	4	0	1,5	rd/gn/rd/gn
(ρ^-)	1509	1360	5	-1	1,5	Fig. 7.14a gn/rd/gn/rd/gn
D^0	3650	3672	6	0	1	rd/gn...rd/gn
D^+ or F^+	3658 till 4188	4284	7	+1	1	gn/rd...rd/gn
(B^0)	10321	8704	8	0	0,75	rd/gn...rd/gn

7.15 Table of vortices of the calculated leptons and mesons compared with measurement values (Part 1).

7.15 Pions

Unlike the leptons, which we could derive and calculate fairly completely, the mesons don't have a half-integer spin. With this characteristic property they therefore can't represent an individually overlapped elementary particle and they probably will consist of the amassing in pairs of individual configurations of potential vortices. This kind of bond can't be particularly tight. Consequently we don't know any stable mesons.

The most important basic building part of the mesons we have got to know over the positronium in fig. 7.3. It necessarily has to amass to another particle, otherwise it annihilates under emission of a γ-quanta, as already mentioned. This γ^0-particle, as it will be named here, has the mass of:

$$m_{\gamma 0} = (2/3)^3 \cdot (1/2)^2 \cdot 1836 \cdot m_e = 136 \cdot m_e \quad (7.19)$$

which only can be determined arithmetically. As a partner, to which the γ^0-particle can amass, first of all another γ^0-particle should be considered. Because both partner will rotate against one another, this new particle would not have a spin and moreover would be uncharged. The mass now would be twice as big with:

$$m_{\pi 0} = 2 \cdot m_{\gamma 0} = 272 \cdot m_e \,. \quad (7.19^*)$$

But the two γ^0-particles will come very close together and mutually feel the local, in the same direction orientated, distribution of the field, which will lead to a weakening of the field and as a consequence to a slight reduction of the mass.

With these properties it probably concerns the uncharged pion π^0. This model concept finds an excellent confirmation in the two possible kinds of decay, which can be regarded as equivalent:

$\pi^0 \longrightarrow \gamma + \gamma$ with a probability of 99%

and

$\pi^0 \longrightarrow \gamma + e^- + e^+$ with a probability of 1%

Also in the case of the charged pion $\pi^{\pm}$ the observable decay offers a big help, which will take place with a frequency of almost 100 %:

$$\pi^{\pm} \longrightarrow \mu^{\pm} + \nu_\mu$$

The equation doesn't state anything about the fact, if a neutrino v_e is used in the process. But it points at the circumstance that the partner of the γ^0-particle for the $\pi^{\pm}$ most likely is a myon $\mu^{\pm}$. The mass will be smaller than the sum of both building parts:

$$(204+136) * m_e = 340 * m_e.$$

name	mass (m/m_e) measu-red	masse (m/m_e) calcu-lated	elem.-vorti-ces z_e	char-ge Q	inner structure of The elementary vortices, colour: (gn=green; rd=red) from the inside to the outside
B^-	11194	9793 +?	9 +?	-1	 $r/r_p = 0{,}75$ gn/rt...rt/gn
(Y^0)	18513	17001 +?	10 +?	0	 $r/r_p = 0{,}6$ rt/gn...rt/gn

Some compound configurations

π^0	264	272	4	0	 2 x fig. 7.3 $\gamma^0 + \gamma^0 = \pi^0$
π^-	273	340	5	-1	 fig. 7.3 + fig. 7.5 $\mu^- + \gamma^0 = \pi^-$
τ^-	3487	3778	5	-1	 fig. 7.14b (2x gn/rd)/gn
(K^0)	974	918 +?	6 +?	0	 $r/r_p = 2$ (2x rd/gn)/ rd/gn
(K^-)	967	939 +?	11 +?	-1	 (rd/gn + gn)/ rd/gn + 3 γ^0

Fig. 7.16: Table of vortices of the calculated leptons and mesons compared with measurement values (Part 2).

7.16 Table of vortices of the mesons

The numerous kinds of decay for K-mesons suggest that these strange particles will consist of various combinations of amassed together and in pairs rotating γ^0- and $\mu^\pm$-particles. The possibilities of combination now already have increased in such a way that for every kaon and other mesons several solutions can be proposed. To avoid unfounded speculations, only a few clues will be given.

Besides the γ^0-particles also heavier arrangements should be considered as partner for the spin and as a building part for kaons and other mesons.
If for instance a π^0 is overlapped by a γ^0, then this particle has an arithmetically determined mass of 918 m_e. It therefore can concern a building part of the uncharged kaon K^0.

The likewise with three γ^0 formed configuration of 6 shells however, if it actually would staystable for the duration of a measurement, would have the mass of 3672 electron masses[i].

A very much better detectability must be attributed to the configuration of 4 shells which consists of two γ^0, so to speak a heavy relative of the γ^0 and the π^0. It among others should be able to decay like a π^0.With this property and with an arithmetically determined mass of 1088 m_e it actually only can concern the η^0-meson. Solely according to the numeric value the η^0-meson could also consist of four π^0-mesons; but the decay in only two light quants speaks against it.

The kaon-puzzle in addition is made more difficult by the spontaneously possible ability to change of the involved γ^0-particles during a process of decay, as is made clear by the numerous kinds of decay. These dependent pion halves can be "swallowed" or "spit out" by neutrinos in the process, they can form from incident light or be emitted as photons and eventually they even can break up in their individual parts.

In fig. 7.16 the possible configurations of potential vortices are sketched and the respective, according to the new theory calculated, mass is given. If above that the other decay products and quantum properties, which can be given for the vortex structures, are added, like e.g. charge, spin and if need be magnetic moment, then an assignment without doubts to the until now only from measurements known elementary particles is possible. In order to better be able to assess the efficiency of the potential vortex theory, the measurement values are compared to the calculated values.

Some terms are put in brackets, because it can be assumed that the calculated part only concerns the dominating part, to which further γ^0 or other small configurations of vortices will amass for reason of its high mass. Correspondingly should the mass in that case be corrected slightly.

<i>: It could e.g. concern the D°-meson.



name	way of decay	mass (m/m_e) measured	mass (m/m_e) calculated	elem.-vortices z_e	charge Q	Inner structure of the baryon vortices
p^+	stable	1836	- (reference value)	3	+1	fig. 7.8 $r/r_p = 1$ $(2x\ e^+)/e^-$
n^0	$p^+ + e^- + \bar{\nu}_e$ (100%)	1839	1837	4	0	figure 7.10a $p^+ + e^-$
			1934	4	0	figure 7.10b n^0 $r/r_p = 1,13$
Λ^0	$p^+ + \pi^-$ (64%)	2183	(2176)	8	0	$\gamma^0 + p^+ + \mu^-$ (64%)
			2187			
	$n^0 + \pi^0$ (36%)		(2206)	8	0	$\gamma^0 + n^0 + \gamma^0$ (36%)
Σ^+	$p^+ + \pi^0$ (51%)	2328	(2108+?)	7 + ?	+1	$\gamma^0 + p^+ + \gamma^0$ (+?) (51%)
			2142+?			
	$n^0 + \pi^+$ (49%)		2177	9	+1	$\gamma^0 + e^+ + p^- + \mu^0$ (49%)
Σ^-	$p^+ + \pi^-$ (100%)	2343	2274	9	-1	$\gamma^0 + n^0 + \mu^-$ (100%)

Fig. 7.17: Table of vortices used for the calculation of the most important barvons with suggestions for the structure (Part 3).

7.17 Table of vortices of the baryons

The number of possibilities of combination quickly increases, if only a few elementary vortices extend the structure of a particle. This probably is the reason for the large number of observable hyperons, which recently have been produced artificially and observed with the help of particle accelerators.

Both the neutron and the lambda particle can exist in a lighter and a heavier variant. At the moment of the decay, as it for instance is observed in a bubble chamber, according to expectation the state with the smaller mass takes the bigger probability. But in the amassing with further particles as building part of bigger and heavier hyperons the heavier structure is more likely. This circumstance should be considered in calculating the mass of the hyperons.

In figures 7.17 and 7.18 the most important baryons are listed, which are characterised in the way that one of the amassed together packets of vortices is a nucleon, thus a proton or a neutron.

The given, from measurements known, kinds of decay are able to confirm the inner structure pretty good. Of course an infinitely lot of combinations are conceivable and numerous predictions are possible. But speculations are unnecessary from the time on where we are able to calculate the particles!
The restriction to the few in the table listed particles seeming to be important hence doesn't limit the universal importance of the theory of objectivity in any way!



name	way of decay	mass (m/m_e) measured	mass (m/m_e) calculated	elem.-vortices z_e	charge Q	Inner structure of the baryon vortices
Σ^0	$\Lambda^0 + \gamma$ (100%)	2334	2342	10	0	$n^0 + \gamma^0 + \gamma^0 + \gamma^0$ (100%)
Θ^0	$\Lambda^0 + \pi^0$ (100%)	2573	2478	12	0	$n^0 + \gamma^0 + \gamma^0 + \gamma^0 + \gamma^0$ (100%)
Θ^-	$\Lambda^0 + \pi^-$ (100%)	2586	2546	13	-1	$n^0 + \gamma^0 + \gamma^0 + \gamma^0 + \mu^-$ (100%)
(Ω^-)	$\Lambda^0 + K^-$ (69%)	3273	3172 +?	17 +?	-1	$n^0 + \gamma^0 + \gamma^0$ + ? (31%: ? = div.)

Fig. 7.18: Table of vortices used for the calculation of the most important baryons with suggestions for the structure (Part 4).

8. Unified theory

With the theory of objectivity the longed for goal of a "theory of everything" (TOE), of an universal theory, seems to have moved within reach. If in the nineteenth century still promising field theories and approaches were being discussed, then has at the latest Einstein's theory of relativity destroyed all hopes in such a theory. Science as a consequence has become very much more modest and understands a TOE only as the unification of all known interactions.

Einstein has stated the minimum demand so: "a theory should be favoured by far, in which the gravitational field and the electromagnetic field together would appear as a whole" <i>. It is evident that a subjective or relativistic observer theory never is able to achieve this.

The presented theory of objectivity made it possible that the unification here for the first time actually has succeeded. This undoubtedly brings science a whole lot further, but it still is not sufficient to lie one's hands in one's lap being content with oneself. After all we still know very much more phenomena, which likewise should be unified. After all it is no accident that both Maxwell and Einstein, to name only two prominent representatives, after completion of their well-known works have struggled for the question, what sort of phenomenon it concerns in the case of the temperature and how this could be integrated in their theory.

The requirement reads: We must be able to derive all basic factors, which influence our system of units with their basic units, as a compulsionless result from the new theory. Besides the dimensions of space and time which determine our continuum, the explanation and unification of the basic factors mass and charge has to be tackled. If we have succeeded in doing so, we'll also tackle the problem of the fifth and last basic factor, which until now has put itself in the way of any unified theory as the question of fate, the problem of the temperature!

<i>: Einstein, A.: Grundziige der Relativitatstheorie, Vieweg+Sohn, Braunschweig 1973, 5. Aufl., WTB 58. Seite 97.

"A theory should be favoured by far, in which the gravitational field and the electromagnetic field together would appear as a whole"<i>.


The hydromagnetic field
charge: e = 0
mass: m = 0
force: F = 0
The electro-magnetic field
relaxation time constant: τ1 = ε/σ
charge: e ≠ 0
force: F = Q · E
The hydro-gravitational field
relaxation time constant: τ2 ~ μ · σ
mass: m ≠ 0
force: F = ϕ · H
The electrogravitational field
charge: e ≠ 0
mass: m ≠ 0
force: F = Q · E + ϕ · H

Fig. 8.1: Structuring of the fields and definition of terms

<i>: Einstein, A. : Grundziige der Relativitatstheorie, Vieweg + Sohn, Braunschweig 1973, 5. Aufl. , WTB 58.

<ii>: derived from the Greek hydro (= water).

8.1 Structure of the field theory

In contrast to Maxwell's theory the new field theory, which we derived from duality, is also able to describe fields, in which no particles and no quanta exist. It probably is justified and useful in the sense of a clearer communication, to give the new field a name of its own.

The author recommends the introduction of the term "hydrotic field". In it should be expressed, which importance water has for both the like named potential vortex and this field<ii>.

As we already have worked out, the hydrotic field is favoured particularly by polar materials and by a high dielectricity. Water is a corresponding and in the biosphere of our planet dominating material.

Whereas we had to correct the concept of a vortex free electric field, we had until now, considerable, we can take over the description of the magnetic field unchanged. This then should also be valid for its name. The new field which consists of both correspondingly is called hydromagnetic field.

In fig. 8.1 we recognize the structure. At the top stands the "hydromagnetic field", which is described mathematically by the equations of dual electrodynamics in fig. 3.3. It does not know quanta and as logical consequence neither charge nor mass! If we insert these equations, Ampere's law and the dual formulated Faraday law of induction, into each other, then there results as a mathematical description of our space-time-continuum the fundamental field equation (5.7, fig. 5.1). As a new physical phenomenon the potential vortex appears, which gives the hydromagnetic field a new and important property: this field can be quantized!

Starting-point is the wave, which for corresponding interference effects can spontaneously roll up to a vortex, which as highly concentrated spherical vortex finds a new right to exist and finds to a new physical reality.

The in the described manner formed particles show specific properties of their own. We now are able to attribute them for instance a charge or a mass. And these properties also can be investigated and described individually and isolated from each other. Thus are formed the two special cases, strange by nature, on the one hand the well-known, with the help of the Maxwell equations describable "electromagnetic field" and on the other hand the new "hydrogravitational field".

If we overlap the results of the two special cases, e.g. by adding the force effects of electric charges and accelerated masses, then we summarized obtain a field, which we accordingly should call "electrogravitational". This case is not at all unknown. Already Niels Bohr in this way has calculated the radii of the electron orbits in the hull of his model of the atom, to mention only one example. We can summarize:

The hydromagnetic field is the all encompassing and with that most important field. Apart from that the electromagnetic field of the currents and the eddy currents and the hydro-gravitational field of the potentials and the potential vortices merely describe the two possible and important special cases. For reasons of pure usefulness for every special case a characteristic factor of description is introduced, the charge and the mass!

Auxiliary terms (description of quantum properties):
* mass * charge * temperature * Planck's quantum of action

The hydromagnetic field does not know any quanta!

Structure of the fundamental field equation 5.7 (fig. 5.1):


electromagnetic wave:
electric field
magnetic field
$\Delta \mathbf{E} \cdot c^2 = \frac{\delta^2 \mathbf{E}}{\delta t^2}$ (5.7 a,b)
potential vortex: (a,d)
$\Delta \mathbf{E} \cdot c^2 = \frac{1}{\tau_2} \cdot \frac{\delta \mathbf{E}}{\delta t}$
eddy current: (5.7a,c)
$\Delta \mathbf{E} \cdot c^2 = \frac{1}{\tau_1} \cdot \frac{\delta \mathbf{E}}{\delta t}$
Poisson equations:
potentials
currents
$\Delta \mathbf{E} \cdot c^2 = \frac{\mathbf{E}}{\tau_1 \tau_2}$ (5.7 a,e)

Fig. 8.2: Unified theory

*electromagnetic interaction (open field lines)
*gravitation (closed field lines)
*strong interaction (does not exist)
*weak interaction (only special aspect)

The interactions are a result of the
field dependent speed of light!

8.2 Unification of the interactions

The discovery and introduction of the hydromagnetic field makes the desired unification possible, because the electromagnetic resp. Maxwell field, which describes the electromagnetic interaction, and the hydrogravitational field of the gravitation can be derived from this field as a consequence of the formation of quanta.
The kind of the interaction is caused by the course of the field lines of the field quanta which form as spherical vortices: the open field lines make the electromagnetic interaction possible. And the field, lines with a closed course lead to gravitation. Both are a direct result of the field dependent speed of light. A more perfect unification seems hardly possible.

As the next step the unification with the strong and the weak interaction is required, but it could be shown that those don't exist at all. It just concerns misinterpretations with much fantasy, which should help explain the difference between a wrong theory and the physical reality.

Numerous auxiliary terms for the description of the quantum properties exist, like for instance mass, charge or Planck's quantum of action. The prerequisite for their usability naturally is the existence of the quanta. But until these have found to a physical reality, the auxiliary terms are unnecessary. The hydromagnetic field does not know quanta, quantum properties or auxiliary descriptions. It will be shown that, according to expectation, also the temperature is a typical quantum property, which comes within the group of the auxiliary terms. In this way also the temperature is fitted into the unified theory without compulsion.

Without the by us for reasons of usefulness introduced auxiliary terms the fundamental field equation is left with its description of a spatial-temporal principle. If a world equation should exist, then this field equation 5.7 has the best prerequisites. For the fundamental field equation the division in four parts is repeated like already for the hydromagnetic field (fig. 8.1). It likewise consists of four individual parts, the wave (b), the two vortex phenomena (c and d) and the time independent term (e) (fig. 8.2). Whereas the duality still is combined in the wave, it comes to light clearly for the vortices to again be combined in the fourth case. Here arise however potentials and currents, which again can react and oscillate with each other, for instance as L-C-resonant circuit in an electronic circuit, with which the principle is repeated.
This principle is shown clearer for the phenomenon of the temperature as in all other cases. If we start at the top in the picture in fig. 8.2 we have an electromagnetic wave, which is absorbed and thus becomes a vortex. If the vortex falls apart, then eddy losses are formed. We observe that the temperature rises and propagates in the well-known manner. We have arrived in the bottom box, but this again can be taken as the top box for the now following process, because the equation of heat conduction is a vortex equation of type c or d! We discover a self-similarity:

> The spatial-temporal principle formulated mathematically by the fundamental field equation can be carried over into itself time and again.

Temperature is the oscillation of contraction of the elementary vortices resulting from the speed of light depending on field strength.

a. at absolute zero temperature:



b. if thermally excited:



Fig. 8.3: Temperature as an oscillation of size for the speed of light depending on field strength

8.3 Temperature

Following the atomic view, in the case of heat it concerns kinetic energy of the molecules, which carry out more or less violent oscillations. In the case of gaseous materials with this concept, basing on mechanical models, actually successful calculations are possible, like for instance the speed distribution of gases won by Maxwell from theoretical considerations concerning probability.

But the attempt to apply the formulas of the kinetic theory of gases to solids and liquids only succeeds, if additional supplements and improvements are introduced. Since at all events it concerns temperature, thus the same physical quantity, of course also an uniform interpretation should be demanded, which in addition should stand in full accord to the presented design of an integrated theory (TOE).

Against the background of the new theory of objectivity we consider, what happens, if for instance the local field strength is increased by a flying past particle. The matter located at this point is contracted for a short time. By coming closer to each other, the individual elementary vortices mutually reinforce their field and are further compressed. Sometime this process comes to a standstill, is reversed and swings back.

At the same time every single particle, which in this way carries out an oscillation of size, has an effect on its neighbours with its field, to also stimulate these to the same oscillation, but delayed by some time. This phenomenon spreads in all directions. The propagation only will become stationary, if all neighbouring elementary vortices pulsate with the same amplitude. It now should be recorded:

The oscillation of contraction of the elementary vortices we call temperature.

Also this thermodynamic state variable therefore is a result of the variable speed of light. At the absolute zero of temperature no oscillation takes place anymore, whereas the upper limit lies in infinity. Since the cause for temperature represents an oscillation of the local electromagnetic field strength around the cosmic field strength, the following phenomena must be considered as excitation and cause, as dictated by the fundamental field equation 5.7:

1. Electromagnetic waves (b) are able to stimulate matter particles to synchronous oscillations of contraction by their alternating field. In doing so energy in form of heat is transferred to the particles, with the result that their temperature is increased. The wave is absorbed completely, if the thermal oscillation corresponds with the frequency of the wave.

We speak of thermal radiation.

2. But also the two dual vortices, the eddy current (c) and the potential vortex (d) can cause oscillations of contraction. This immediately becomes clear, if we consider a vortex as the special case of the wave, in which the oscillation takes place around a more or less stationary vortex centre. In the case of the decay of vortices, of the transition of energy from vortices to matter, the increase in temperature is measurable.

In the case of this process of diffusion we speak of eddy losses and of loss heat.

Answers to open questions of thermodynamics:

1. Temperature occurs independent of the state in which the matter is (unified theory).

2. Temperature even occurs in solids, where a purely kinetic interpretation fails (unification).

3. Each elementary particle is carrier of a temperature.

4. Expansion with increasing temperature because of the increasing need for room for larger amplitude of oscillation (principle: bi-metal-thermometer).

5. For solids the thermal oscillation of size is primarily passed on by the electrons in the atomic hull. Good electric conductors therefore at the same time also have a high thermal conductivity. (principle: electrical resistance thermometer).

6. For gases the entire atoms carry out this task, for which reason a kinetic auxiliary description becomes applicable.

7. For extreme amplitudes of oscillation the atoms partly or entirely lose their enveloping electrons, when they change into the plasma state.

8. The second law of thermodynamics loses its claim to be absolute and at best reads: with today's technology we are not capable, to design a cyclic working machine, which does nothing else, as to withdraw heat from a heat container and to convert it into mechanical work.

Fig. 8.4: Questions concerning thermodynamics

3. Flying past particles, in particular unbound and free movable charge carriers (e) produce an alternating field for other fixed particles. Doing so kinetic energy can be transformed in temperature, thus in energy of pulsation. A good example is the inelastic collision. But it can also be pointed to numerous chemical reactions. Whoever searches for a concrete example, takes two objects in his hands and rubs them against one another. In that case the particles which are at the frictional surfaces are being moved past each other in very small distance, in this way causing oscillations of pulsation, which propagate into the inside of the objects according to the thermal conductivity. We speak of friction heat.

This model concept provides sound explanations for a whole number of open questions (fig. 8.4), i.e. why the temperature occurs independent of the state (1) and even in solids, where a purely kinetic interpretation fails (2). Every single elementary particle after all is carrier of a temperature (3).
With increasing temperature most materials expand, because the need for room, purely geometrically seen, increases for larger amplitude of oscillation (4). This principle is used in the case of a bi-metal thermometer.
In the case of solids the thermal oscillation of size is passed on primarily by the electrons in the atomic hull (5). Good electric conductors therefore at the same time also have a high thermal conductivity. An example of an application is the electric resistance thermometer.
In the case of gases the entire atoms carry out this task, for which reason a kinetic theory becomes applicable as an auxiliary description (6).
For extreme amplitudes of oscillation the atoms partly or entirely lose their enveloping electrons, when they change into the plasma state (7).
Finally the model concept even limits the second law of thermodynamics, which contains the postulate that it is impossible to design a cyclic working machine, which does nothing else, as to withdraw heat from a heat container and to convert it into mechanical work (8).

8.4 Heat energy

The discussed oscillation of contraction shows two characteristic properties, which must be looked at separately: the amplitude and the frequency.

Temperature describes solely the amplitude of the oscillation of size.

The heat energy however is determined by both,
by the amplitude as well as by the frequency.

Consequently the ideas of temperature and heat energy should be kept strictly apart. It therefore isn't allowed to set this oscillation equal to the electromagnetic wave in tables of frequency.
To be correct two tables should be given, one for the wave, characterized by a propagation with the speed of light, and another one for oscillations of contraction, thus for stationary phenomena and phenomena bound to matter. The latter indeed can likewise propagate relatively fast by fluctuations of pressure in the case of acoustical sound frequencies or by free movable charge carriers in the case of heat conduction, but the velocity of propagation for sound or heat is as is well-known still considerably smaller than the speed of light. Thus an assignment without doubts can be made as to which kind of oscillation it concerns.



Temperature *describes the amplitude of the oscillation of size of all spherical vortices.*

The ***heat energy*** *however is determined by both, the amplitude and the frequency.*

thermal radiation
(infrared radiation)
contraction -
- expansion
vortices of temperature
$\Delta T \cdot a = \frac{\delta T}{\delta t}$ (8.1)
$T_2 - T_1 = \Phi \cdot R_{wärme}$ (8.2)
vortices of heat current
$\Delta \Phi \cdot a = \frac{\delta \Phi}{\delta t}$ (8.3)
a = conductivity of temperature
stationary temperature
(asynchronous oscillation of size)
temperature T
heat current Φ
spezial case:
sound
(synchronous oscillation of size)

Fig. 8.5: Heat conduction resp. sound

8.5 Sound

The close relationship of longitudinal sound waves with the oscillations of contraction of thermally heated matter becomes particularly clear for ultrasound, where the arising heat in the inside of the body which is exposed to sound can be measured directly. The fundamental difference consists of the fact that the produced sound waves not only have the same frequency, but also the same phase, what needs not be the case for the temperature. The apparently uncoordinated occurring oscillations of size of the temperature, which as a rule occupy more space if the intensity increases, form a "thermal noise".

The oscillation of size with the same phase is not realizable at all in a spatial formation of particles, with one exception, the case that all particles expand and afterwards again contract simultaneously and in the same time. We can observe such a synchronization of the pulsation oscillations of all elementary vortices in the case of a pulsar. For us a pulsar looks like a "lighthouse" in space which shines with a fixed frequency. In reality it as well can concern a constantly shining sun, which carries out a synchronized, thermal oscillation of size, like a gigantic low-frequency loudspeaker. During the phase of contraction of the star its emitted light stays back. To us the pulsar looks dark. In addition the field strength is extremely increased and the light becomes correspondingly slow. During the phase of expansion the conditions are reversed and we observe a light flash. Exactly the pulsar unambiguously confirms the here presented theory of the variable, field dependent speed of light.

The well-known fact that the microcosm represents a copy of the macrocosm, already suggests that each atom is capable of the same oscillation of size as a pulsar: if next to the oscillating atom a resting one is placed, then does this one see a smaller field during the phase of contraction because of the increasing distance. It hence becomes bigger itself. If the pulsating neighbouring atom afterwards expands, it however becomes smaller. The at first resting atom in this way becomes a "pulsar" oscillating with opposite phase. The oscillating atom has stimulated the neighbouring atom as well to an oscillation of size, and this process will be repeated with the closest neighbouring atom. We speak of heat conduction.
To which extent the average distance between neighbouring atoms is influenced while a material is heated, solely depends on the structure of the atomic lattice. For matter with a fixed lattice according to expectation a smaller heat expansion will occur, as for the unordered structure of gases, in which we find confirmed well-known relations.

In a for potential vortices characteristic property sound waves and thermal waves of contraction correspond:

The propagation of potential vortex fields takes place as a longitudinal wave.

In this point vortex fields clearly differ from the transverse propagating electromagnetic waves!



1. Ampère's law (see fig 5.1):

$$\boxed{\mathrm{rot}\,\mathbf{H} = \varepsilon \cdot (\mathbf{E}/\tau_1 + \delta\mathbf{E}/\delta t)} \quad (5.1^*)$$

with relaxation time $\tau_1 = \varepsilon/\sigma$ (5.3)

transformed: $\delta\mathbf{E}/\delta t = (1/\varepsilon) \cdot \mathrm{rot}\,\mathbf{H} - \mathbf{E}/\tau_1$ (5.1**)

integrated: $\mathbf{E} = \int [(\mathrm{rot}\,\mathbf{H})/\varepsilon - \mathbf{E}/\tau_1]\, dt$ (5.1***)

2. Faraday's law of induction (in analogy):

$$\boxed{-\mathrm{rot}\,\mathbf{E} = \mu \cdot (\mathbf{H}/\tau_2 + \delta\mathbf{H}/\delta t)} \quad (5.4^*)$$

transformed: $\delta\mathbf{H}/\delta t = -(1/\mu) \cdot \mathrm{rot}\,\mathbf{E} - \mathbf{H}/\tau_2$ (5.4**)

integrated: $-\mathbf{H} = \int [(\mathrm{rot}\,\mathbf{E})/\mu + \mathbf{H}/\tau_2]\, dt$ (5.4***)

3. Signal flow diagram of the field equation 5.1***:

H
rot
1/ε
w
x
∫dt
F11
E
1/τ1
adaptation of driving factors
comparator
I-controller
control path

Fig. 8.6: Control technical analysis of the dual equations of the hydromagnetic field.

8.6 Basic principle of cybernetics

Surely can be attributed also information to the potential vortex. But how should information be formed? Is information a form of energy? Energy occurs as a consequence of the formation of potential vortices. Without this phenomenon there wouldn't be any energy!

Can information be described by means of a mathematical equation?

To be able to answer these questions, we subject the fundamental field equation to a control technical analysis. If it actually concerns a world equation, then an answers should be possible.

We again take up Ampere's law 5.1* from fig. 5.1 and remodel it according to the time derivative (5.1**). If the equation now is integrated over the time (5.1***), a signal flow diagram can be drawn (fig. 8.6).

The structure of a regulatory circuit is clearly visible. The individual paragraphs are described in an analogous way as for a technical control system. The execution of the curl operation on the field pointer of the magnetic field strength H and the multiplication with $1/\varepsilon$ accordingly form an adaptation of driving factors. In the comparator the difference for control from driving factor w and controlling factor x is formed and supplied to an integral controller. The control path has a purely proportional behaviour and consists of the processing of the measurement value of the electric field strength E with $1/\tau_1$, in which τ_1 describes the relaxation time of the eddy currents.

In technical control systems such a structure is found remarkably seldom, although it has an invaluable advantage: it possesses a stability in principle. Not a single adjustment of the controller exists, in which the closed regulatory circuit could become unstable, because it shows a proportionally delaying behaviour of first order. Possible changes of the adjustment of the controller or of the control path merely take effect on the speed, with which the regulatory circuit is able to follow changes of the driving factor.

This control technical basic principle convinces by its simplicity and efficiency. It meets us again in identical form in the second field equation 5.4*, the extended Faraday's law of induction. In dual formulation the electric field strength now appears as input factor and the magnetic field strength as output factor. Both regulatory circuits are coupled and connected with each other, by deriving their driving factor each time from the controlling factor of their dual partner. Is this structure actually efficient and meaningful?

Every regulatory circuit needs a target value, which is dictated from the outside. Let us think of the numerous control systems in nature. At all events a higher intelligence would be necessary for all the target values. This problematic is comparable to the question, what existed first: the egg from which a hen hatches or the hen without which no eggs can exist. Without a given target, evolution would not exist.

The connected regulatory circuit structure provides the matching answer: cybernetic systems, which usually and as is well-known strive to a state of balance, get their target value from their dual "partner". It is crucial that correspondingly dual systems are self-sufficient and can form and develop independently out of themselves without target values of a third side. This basic principle of cybernetics undoubtedly is brilliant.


rot
– w
∫dt
– x
F12
1/τ2
c2
rot
w
∫dt
– x
F11
1/τ1
adaptation of driving factors
comparator
I-controller
control path

Fig. 8.7: Signal flow diagram of the fundamental field equation
with adaptive structure.

8.7 Adaptive regulatory circuit structure

If out of the nowhere something like the cosmos or like life on earth should form, then the connected regulatory circuit structure basing on duality probably is the only possible and conceivable. Thus it merely concerns the control technical representation of the fundamental field equation.

The question for the efficiency not only concerns the stability, but equally the possibility of both systems, to oscillate and to communicate with each other by the coupling and the associated exchange of information.

Fig. 8.7 shows the signal flow diagram of both regulatory circuits. These are switched in line and form a coupled circuit, which itself can be interpreted as a third regulatory circuit. Also this one shows a change of sign in the circuit like the other two circuits.

The information technical interpretation could turn out as follows: information about a regulatory process in the lower regulatory circuit F_{11} caused for instance by a disturbance is communicated over the coupled circuit to the upper regulatory circuit F_{J2}. In this case F_{11} acts as transmitter and F_{12} as receiver of the information. Afterwards both exchange their places, because F_{12} for its part reacts by a regulatory process and reports to F_{11}. The regulatory circuits adapt to each other. Obviously it concerns the basic structure of an adaptive regulatory circuit.

To analyse the coupled circuit the examination of individual special cases is recommended. If the regulatory circuits F_{11} and F_{12} are opened up in the way that the time constants tau$_1$ and tau$_2$ go towards infinity, then the double integral effect is left. Analyses of technical regulatory circuit teach us that such systems always tend to instability. Because in addition the target value is zero, an oscillation around zero will arise, which we call electromagnetic wave.
If one of both time constants becomes finite, e.g. τ_2, then damping of the waves will occur. The "subordinate" cascade regulatory circuit F_{12} will adjust itself and now has a proportional delaying behaviour of first order. Together with the integral controller of the open F_{11}- circuit the coupled circuit will show the typical and more or less optimal regulatory behaviour of a damped oscillation.

These special cases correspond with the mathematical (fig. 5.2) and the physical (fig. 5.3) interpretation of the fundamental field equation. In addition a spatial rotation, a swirling will occur because of the double execution of the curl operation.

If interpreted control technically then vortices are the temporally stable, spatial swing of a field pointer around a centre, the vortex centre.

Without potential vortices no stability, no matter, no energy nor information would exist!

As can be looked up in Goethe's Faust, it always has been a desire of humanity, to find out, "what keeps the world together in the heart of hearts".



electric field	——	magnetic field
potential	——	current
capacitor	——	coil
Faraday's law of induction	——	Ampère's law
potential vortex	——	eddy current
convergence	——	divergence
dielectricity	——	permeability
non-metal	——	metal
isolator	——	electric conductor
tuned cavity	——	antenna
cold	——	hot
Yin	——	Yang
female	——	male
minus	——	plus
introverted	——	extroverted
stability	——	dynamics
water	——	fire
implosion	——	explosion

Fig. 8.8: Table of dual correspondences
(as a supplement to chapter 3.3 and fig. 4.2).

8.8 Information

The search for an answer for numerous philosophers and physicists was tantamount to the search for a world formula. Of course mustn't be forgotten that a formula only is a mathematical description and never the physical reality itself. It is a mathematical tool in the hand of a person and not the world or the cosmos itself, which he tries to understand. What keeps the world together in the heart of hearts, has to be more than only a pure apparatus of formulas. Actually the fundamental field equation tells us more. It reveals us a basic principle basing on duality in which the dual partners mutually dictate target values and goals. This principle convinces by its simplicity and efficiency. Apart from the "self regulation" it obviously also has the fundamental possibility of a "self organization" and the "generation of information". The field equations of the hydromagnetic field thus are the starting-point for the formation not only of matter and energy, but also of information. Accordingly holds:

Information is nothing but a structure of electromagnetic vortex fields!

This statement is new and to a large extent incompatible with the conception world of Norbert Wiener, who goes as the founder of cybernetics. From N. Wiener stems the sentence: "information is information, not matter and not energy".

We hold against it that obviously a fairly direct connection exists. We have worked out that only the vortex can show a stable adaptive regulatory circuit structure. Only the vortex and not the wave exists in two forms of formation dual to each other, and the principle of duality again is the prerequisite for the formation of information, of self organization and finally for the evolution. In fig. 8.8 well-known dual partnerships are listed. From it follows in a consistent way that for the production of information without exception the electromagnetic vortices should be considered.

But how can this so important duality occur, how can it form? This question is closely associated with the question of the formation of vortices. The signal flow diagram (fig. 8.7) to that says that the dual regulatory circuits F_1 and F_2 can only exist by the coupled circuit, which provides them the necessary target values and at the same time forwards the respective information. In this way of the oscillations and the more or less damped wave F_1 and F_2 communicate with each other.

The electromagnetic wave serves solely the mediation of information and energy.

With that falls a central role upon the wave, so that vice versa is valid:

Without wave no vortices, no duality and consequently no evolution can exist.

According to the to date state of knowledge the basic principle of cybernetics forms the basis for matter and energy as well as for information. Since the wave can only serve the transmission of information, the principle of duality and the vortex will function as carriers of information. We are entitled, to speak of vortex information, this by no means is characterized by special frequencies or modulations of frequencies. This is prevented by the property of the vortices which allows them to change the frequency. On the other hand various configurations of vortices are possible and numerous combinations and modulations are conceivable.

If technical apparatus generate vortices, then they produce information. Here a serious danger with regard to the environmental compatibility can not be excluded!

Equivalent things:

- elements of the fundamental field equation 5.7
- elements of the Greek philosophy of nature
- temperaments
- (impulses of growth)


wave + oscillation:
air (light)
sanguine person
(blossom)
potential vortex :
water
phlegmatic person
(leaf)
eddy current:
fire (heat)
choleric person
(fruit)
potentials:
currents:
earth
wood
metal
melancholic person
(root)

Fig. 8.9: The theory of four elements of the old Greek philosophy of nature (Aristotle and others)

8.9 Philosophy of nature

Seen in the view of the philosophy of nature now two dual points of view are possible.
The optimistic one would be:
We and our environment on the one hand are a result of the cybernetic principle and on the other hand of our observation point of view which should be valued relativistically.
If really everything should be electromagnetism, a phenomenon which can't be grasped directly by humans, then the pessimist would come to the conclusion: everythins is nothing. What we observe is nothins but a deception of the senses. Perhaps therefore famous philosophers of antiquity, like Empedokles or Demokritos have ended their life in the crater of the Etna. According to the theory of the atom of Demokritos (470 to 380 B.C.) the formation of matter, earth and celestial bodies will occur by means of formation of vortices!
Empedokles (482 to 420 B.C.) was the first to develop a theory basing on four elements, which was continued and improved by Plato (428 to 348 B.C.) and Aristotle (384 to 322 B.C.). Accordingly these elements are changeable into each other and mixable with each other. From them all bodies are build up.
The terms "air, water, fire and earth", with which the philosophers have described the four elements, are of course not identical with the ones in our translation and conception world, but they were used in a philosophical sense as a substitute for the description of the respective basic principle.
There also have been different approaches, to translate these terms differently, e.g. by an assignment to the four states of matter (solid, liquid, gaseous, plasma). But the ancient texts don't get easier to read in that way.

Fig. 8.9 shows the obvious assignment to the four building parts of the fundamental field equation 5.7. It would be worth an attempt, to exchange the terms in the translations of ancient texts and to translate air with wave, water with potential vortex and fire with eddy current. The term earth has two sides, which should be translated with potential instead of wood and current instead of metal.

Let's try the translation this way with the theory of Plato<i>, by correspondingly translating anew the talk of Timaios about the formation of the world. The perception of smell then is described as follows: "...as the potential vortex turns into waves (or) the wave into potential vortices, the smells are formed during this transition, and smells are smoke or fog. But fog is the transition of waves into vortices, the transition of the vortex into waves however smoke".
Plato here provides an indisputable and conclusive interpretation of the fundamental field equation. In this equation the potential vortex acts as damping term in the wave equation, what in the case of waves rolling up to vortices will show to the observer in the way that the electromagnetic waves and therefore also the light will be damped. We say, the visibility gets worse and speak of fog. If the damping phenomenon disappears again, as the potential vortices break up, then Plato speaks of smoke.
Numerous ancient texts, which until now only could be "interpreted" philosophically, in this way turn out to be a rational textbook description of natural scientific phenomena. They anyway only get readable and understandable for the general public with the modern technical terms.

<i>: Platon: Samtliche Werke 5, Rowohlts Klassiker Nr. 47, S. 188, 66e

Optimist:

We and our environment on the one hand are a result of the cybenetic principle and on the other hand of our observation point of view which should be valued relativistically.

Pessimist:

Everything is nothing. What we observe is nothing but a deception of the senses.

Plato<i> (talk of Timaios about the formation of the world) description concerning the perception of smell:

"...as water (the potential vortex) turns into air (waves) or air (the wave) into water (potential vortices), the smells are formed during this transition, and smells are smoke or fog. But fog is the transition of air (waves) into water (vortices), the transition of water (vortex) into air (waves) however smoke"

changed translation with the technical terms:

air______ = ____wave
water = ___ potential vortex
fire______ = ____ eddy current

As a consequence:

smell is vortex information

Fig. 9.0: The explanation of Plato concerning the formation of smell, smoke and fog<i>

<i>: Platon: Samtliche Werke 5, Rohwohlts Klassiker Nr. 47, S. 188, 66e

9. Usage

If the newly discovered vortex phenomenon of the vortex of the electric field exists, then it will be possible to practically use it. Whereas we still think about possibilities for technical usage, there by all means exists the possibility, that nature already is successfully using the vortex for a long time. We should look precise at things. We can only learn of nature!

Remarkable about the passage of Plato (fig. 9.0) is not only the fact, that the potential vortex already was known for two and a half thousand years and was taken into consideration for an interpretation, but also the realization of Plato, that during the described transition the smells form. Smell thus would be a vortex property!

After all vortices are able to bind information as can be inferred from the basic principle of cybernetics. With this vortex property and the statement of Plato smell obviously would be nothing else than pure information which by potential vortices is stored, distributed and eventually is caught by the hair cells for smell of the nose.
If now a dog takes up a track, does it then run after vortices which remained behind or does it analyse, according to the encyclopaedia, the chemistry left behind, or does it combine both? Does the bloodhound for instance interpret the vortical oscillations of chemical substances like lattice oscillations or the movements of the electrons in the atomic hull? A lot of work awaits the research scientist of vortices here. The seminar will offer opportunity, to deepen this topic<i>.

Only if technicians exist, who put an electronic box on the table with a button, at which they adjust the wanted scent of rotten eggs to lavender, we honestly can claim to have understood the phenomenon of the smell.

For the majority of the people a theory only wins its sense by the practical applicability, and therefore we'll have to develop and present a technical usage on the basis of the vortex theory.

<i>: Suggestions for appropriate seminar themes: the meaning of smell, taste, the aroma therapy, the homeopathy or the effect of aetheric oils. (To that in part 3, INDEL Verlagsabt. 2003)


Antenna
The basic experiment
with the Tesla coil:
50 kV
5 kHz
600 kV
2 wndg.
primary
coil
24 wndg.
secondary
coil
network
high tension
transformer
capacitor
spark
gap
ground

Fig. 9.1: High tension transmitter of Nikola Tesla

9.1 Longitudinal electric waves

It is important, that experts struggle for problem solutions. Only if the discussion about limits doesn't come to a result which can be grasped and verified, then also in the environmental compatibility the willingness will grow, to accept a not yet known phenomenon as a further and possibly crucial influential factor.

Already for a hundred years there has been a dispute of experts. At that time scientists all over the world were trying to verify the experiments of Heinrich Hertz. Then from America the message came, Hertz had been mistaken and the electromagnetic wave would have completely other properties. The scientists in Europe were indignant, but they had to take the message seriously, because it after all came from the important experimental physicist Nikola Tesla (1856-1943), who with his inventions of the rotary field and of the asynchronous motor has stamped today's electric energy technology as no other.

As a result Lord Kelvin boarded a steamship as a mediator and sailed 1897 to New York to convince Tesla from the opposite. But the experiments, which Tesla presented his Lordship, didn't give rise to any doubts<i>, and thus Kelvin returned to Europe with the message: "Both are right, Tesla as well as Hertz! Whereas the electromagnetic wave which Hertz has detected, is a transverse wave, does Tesla work with a longitudinal wave"!

Lord Kelvin as a result started to draw most different vortex models, because it was clear to him, that a propagation as a longitudinal standing wave analogous to the sound wave only is conceivable, if quantized structures exist, which knock each other mutually. Kelvin therefore assumed vortex structures of the electromagnetic field. His vortex models were published and landed in the curiosity box of orthodox science.

Heinrich Hertz did have a big advantage. He could refer to Maxwell and calculate his wave with the field equations. For modern technology the mathematical calculability is almost an indispensable prerequisite!

For Tesla wave there however neither was a mathematical nor a physical theory. The only thing Tesla had, were presentable experiments.

In Colorado Springs he had build a 10 kW transmitting installation and lighted 200 fluorescent lamps of 50 Watt each on a mountain in the Rocky Mountains in a distance of 25 miles. With that he had completely transmitted the transmission power of 10 kW, as can be inferred from the press reports at that time. With Hertzian waves, which propagate spatially, this experiment even today, after over 100 years, wouldn't be realizable technologically. According to the law of the square of the distance one isn't even able to let glow a tiny little lamp in such a distance.

For sure his rotary field theory was a big help for Tesla in all experiments. Actually a rotary field can be seen as the special case of a planar vortex.

Thus Tesla obviously was able, to use the potential vortex without even knowing it. Tesla has stimulated a loosely coupled high tension coil wound like a spiral to self-resonant oscillations and emitted the produced vortices over an antenna (fig. 9.1). On the receiver side the process was then reversed.

<i>: N. Tesla: III. The Singular Misconception of the Wireless (Famos Scientific Illusions), Electrical Experimenter, Feb. 1919, p. 732.


zinc-plated sheet-steel
steel wool
steel wool
steel wool
wooden box
wood-wool or
glass fibre wool

Fig. 9.2: Orgone accumulator according to Wilhelm Reich.<i>

<i>: Dr. James DeMeo: The Orgone Accumulator Handbook, ISBN 0-9261855-0-7

9.2 Medical technical usage

Nikola Tesla at his time was extremely popular in the area of medicine. With his inventions injuries were cured and pain eased. Modern diathermy goes back to his work. But Tesla at that time has treated the patients with vortices, whereas today, possibly out of ignorance, electromagnetic waves are used. These however have in contrast to potential vortices only a small penetration depth. Today in addition only the effect of heat is considered and in no way the information technical effect of electric vortices. Here we are missing the comparison, to be able to say. if the treatment with a Tesla apparatus was more successful than with modem microwave radiators.

The experiments of Wilhelm Reich (1897-1957) aimed in the same direction. Exactly as Tesla 55 years before also Reich emigrated to America in 1939. He had specialized in catching and collecting vortices, which he called "orgone", from the air. In this way he could store up high energies over time and then use them purposeful. With his "orgone accumulator" he was able to cure wounds faster and to ease pain. He also treated cancer and a lot of forms of anaemia. Technically Reich could demonstrate, that charged capacitor plates discharge faster under the influence of his apparatus. His orgone accumulator for instance is a wooden box, filled with wool of steel and wood, which alternate in layers. He said that the reason for this construction is, that metals repel the orgone energy, whereas organic materials become charged and accumulate it. That holds in his opinion to a particularly high degree for water.

Reich concludes that no material and no device are known, with which the orgone energy could be shielded. This with regard to the environmental compatibility of the vortex phenomenon should make us thoughtful.

As a supplement it should be mentioned, that Reich already at the end of the forties has pointed to the dying of the forests and he has made a direct connection to the orgone energy. Reich was slandered and mocked and died in the prison of Connecticut, while his writings were burned publicly.

Not much better fared the Austrian forester Viktor Schauberger (1885-1958), who also can be described as visionary. He was able to produce water with a particularly good conductivity. His water in addition goes for medicinal and healthy. Also to him travelled cancer patients of far away to get this water.

Schauberger spoke of the natural treatment of the water, whatever he meant with that. In any case he build with great success installations to transport wood by floating it and even installations to mine ore with so-called double twist pipes, which made possible a transport without friction even of materials, which are heavier than the "means of transport" water. It could be proven that no contact with the pipe took place. This was scientifically investigated and confirmed at the university of Stuttgart 1952 by Prof. Popel. Quite obviously in the double twist pipe vortices have formed, which have bound the material to be transported (see phenomenon of transport).

Today you can buy levitated water at over 100 selling points in Europe, of which is claimed, that it is prepared according to instructions of Schauberger. Unfortunately we aren't able to ask him anymore, if he agrees with such a "centrifuged" water. Thus the test of the effectiveness has to be left to everyone himself or herself.

A: Concerning the functioning of the Faraday generator ($E = v \times B$):



B: Construction of the flying disc:



Fig. 9.3: Applications of the Faraday generator<i> in the flying disc of Prof. John Searl

9.3 Flying objects

The medium of Viktor Schauberger always was the water. He could produce light effects and very high temperatures with it with only minimal excitation in the form of impulses. An installation, which had been built according to his plans at the company of Siemens, eventually melted at 4000°C by improper operation, as he himself stated. According to that the machine would have released more energy than used, thus a perpetuum mobile. The authorities of the state in the Third Reich were impressed and put Schauberger in a concentration camp, where he was instructed to build a "flying saucer" under permanent supervision together with fellow prisoners. For him it's all about the concentration effect and the usage of the as a result occurring implosion in contrast to our today's " technology of explosion and fire" as Schauberger was accustomed to express himself. It is not known, if Schaubergers "repulsine" ever has took off.

A disc, which has proven its suitability to fly, was constructed and built by the english technician John R. R. Searl, although he said he can't explain the effect. He also had big difficulties, to get the apparatus under control. A disc broke through the ceiling and the roof of his laboratory and disappeared to never be seen again. Five other flying discs, which he after this experience started in the open, went lost in the same manner. Without knowing the effect, he of course neither could assess the dangers. His experiments have claimed serious injuries and a casualty. While he 1985 was put in prison under a pretext, his laboratory and his house were burned down and all documents destroyed. Now he works on a technical usage. According to the principle it concerns a Faraday machine. Thereby a permanent magnet, magnetized in axial direction, is turned. Now the magnetic induction B for a relative velocity v is measured as an electric field strength E according to equation 6.10: $E = v \times B$. (6.10)

Because the vectors are arranged as standing perpendicular to each other, will arise a tension voltage in radial direction (direction of E-field) which can be taken off. Apart from the friction no further force of reaction occurs in the case of the Faraday generator. Because of the small gain of energy until today no application ready for the market exists. But this principle, to convert magnetic field energy into electric, already has moved the nature of many inventors. Professor Searl has reversed this old principle. Whereas normally the component of the velocity towards the centre of rotation decreases, it increases in Searls case. For that he works with roller pivoted concentric rings, which he drives by a small electric motor (fig. 9.3). Doing so something inexplicable for him happens: After switching off the motor the revolutions per minute don't decrease again, but increase audibly and increase further, until the produced electric field shows the well-known high tension phenomena: corona discharges, formation of ozone, ionisation of the air and production of a vacuum in the inside of the disc.

The rings and rollers consist of several layers, which are built up similar to a bi-metal. The only explanation I can think of is that a change in structure would occur as a result of the physical length contraction which is caused by the increase of the E-field in the direction of the centre of rotation. The bi-metals try to withdraw themselves from this change by an increase of their rotation of their own (fig. 6.5). To compensate the field the disc builds up a spin, as also the elementary particles do (fig. 6.13). While the formation of vacuum prevents sparking in the inside of the flying disc, and the revolutions per minute further increase because there is no air friction whatsoever, the disc weighing 5 tons all of a sudden lakes off the ground and according to reports of eyewitnesses shoots vertically upwards.


high tension
−
+
+
−
−
+
+
−
atom
(air)
direction of movement
(charged capacitor)
atom
(air)

Fig. 9.4: Capacitor experiment concerning the so-called electro-gravitation according to Prof. Biefeld / Dr. Brown

9.4 Electro gravitation?

Wild speculations circulate about the mechanism of the flight of a "flying saucer", which should function without sound and without combustion, and for which no sound barrier exists, as pilots have observed. The talk is about cancelling gravitation or about an "electro gravitation".

Reproducible in any case is an experiment, which has been systematically investigated by the american professor Biefeld and his pupil T. Brown from 1925. Accordingly does a body charged to high tension show a force effect in the direction of its positively charged note. As a check for oneself a capacitor can be suspended on its connection wires and it can be observed, how it moves visibly in the direction of the positive pole in case it is charged (fig. 9.4).

Because the Biefeld-Brown effect depends on direction, it actually can't concern gravitation at all but merely a not understood electromagnetic interaction. In the neighbourhood of the capacitor pole air molecules are found, and their negatively charged atomic hull is attracted by the positive pole. At the same time the atomic nucleus is repelled. By that the air atoms in the presence of the high tension capacitor become unsymmetrical, causing the force of attraction due to the smaller distance to exceed the force of repulsion. At the negatively charged end the conditions are exactly reversed. There a repulsion occurs. Because the polarized air atoms and molecules are sucked in, no pressure can build up and as a result no sound barrier can occur. Experiments with charged and uncharged rockets have brought the interesting result, that the electrically charged rockets flew many times as far as the uncharged ones (5-6 times as high)<i>.

Many a person now perhaps starts to dream of the flying carpet but, as said, it isn't an "effect of antigravitation". Does "free energy" actually exist, we have to ask ourselves? From the gravitation the soviet physicist Landau calculates an energy density of 16 megawatt hours per cubic meter for the earth's surface. Immediately inventors are found, who want to use this gravitational energy.

Nikola Tesla in his laboratory in Manhattan has incidentally built resonators, of which he could bring all electric, magnetic and mechanic factors in resonance. On an evening stroll he fastened a battery operated vibrator to the tubular steel scaffolding of a new building and let everything shake and wobble. In his laboratory such a device once got out of control by inattentiveness and triggered an earthquake. In that way the road surfacing and pipes were burst and window panes got broken. The police penetrating his laboratory only could see, how Tesla forcible finished the experiment with a sledge-hammer.

The experiments which got out of control of Tesla, Searl and Schauberger have one thing in common: it concerns constructions with an unipolar arrangement of the field.

Tesla had arranged the magnetic field in a unipolar way, as he has reported himself, Searl had realized electric unipolar fields in a construction similar to the electron, and Viktor Schauberger had specialized in producing unipolar structures with water vortices.

In the case of the corresponding technical usage, which can be interpreted as making use of the occurring "spin coupling", therefore in principle utmost caution is imperative.

<i>: Rho Sigma (Dr. Rolf Schaffranke): Forschung in Fesseln, das Ratsel der Elektro-Gravitation, Ventla-Verlag, Wiesbaden, 1972, Page 67.

Nikola Tesla: „Ere many generations pass our machinery will be driven by power obtainable at any point in the Universe This idea is not new, we find it in the marvellous myths of Antheus, who derives energy from the earth... Everywhere in the universe there is energy. Is this energy static or kinetic? If static, our hopes are in vain; if kinetic, and this we know it is for certain, then it is a more question of time when men will succeed in attaching their machinery to the very wheel work of nature". New York, the 20th may 1891, American Institute of Electrical Engineers.



Fig. 9.5: Energy transmission bound to a wire, Patent No. 593,138 (1897) of Tesla.

<i>: Philadelphia Public Ledger, Nov. 2, 1933

<ii>: Dr. Nikola Tesla: Complete Patents, Tesla Book Company, New Edition 1983, Compiled by J. T. Ratzlaff, ISBN 0-960356-8-2, page 301-304.

9.5 Free energy?

Furthermore is reported of Tesla, he would have developed a "converter for space energy" and 1931 have built it in a luxury car (Pierce Arrow)<i>. The car was a 145 km/h fast, doing so the asynchronous motor (presumably built by Westinghouse) furnished 80 HP at 1800 Rpm. The "free energy" the converter, build by Tesla himself, got from a 1.8 m long antenna. Because the motor ran without adaptation of frequency in slipping operation, it had to be cooled correspondingly. It was on the way in trial run for over a week. Now we of course want to know, of what this "free energy" consists, which Tesla will have used and of which he already 1891 had spoken in the American Institute of Electrical Engineers.

For the electron as a spherical vortex we have calculated an electric tension voltage of 511 kV between its surface and its centre respectively infinity (equation 6.31*, fig. 7.1). The highest level of tension voltage normally used for the high tension transmission lies at 380 kV (effective value); for a direct current transmission it is 500 kV. Although still higher tension voltages would be desirable, they are avoided. This is no accident. Experiments with higher tension voltages namely have resulted in inexplicable high losses. We have an explanation: the electrons are taken apart on the way! Their inner energy amounts with the outer energy to zero. The charge carrier, which in the power station as result of an energy conversion has been sent on a journey, is in danger to vanish into thin air (e.g. corona) for tension voltages above 511 kV. The transmitter of Nikola Tesla however (fig. 9.1 and 9.5) worked with 600 kV and more. He said, with his experiments he had destroyed billions of particles without being able to observe an emission of energy and made fun of the misinterpretation of Einstein of the already at that time well-known mass-energy relation $E = mc^2$.

For the purpose of a one wire or a wireless energy transmission the tension voltage therefore has to be higher than 511 kV. With Teslas equipment however the electrons shouldn't be destroyed, but merely be pulled apart to plane circular vortices with help of the today is Tesla coil known winding. These then could be sent on a journey over the antenna, to again be caught and formed back in spherical electrons by the receiver antenna. As long as the electrons don't fall apart, they keep their structure and quantum property. Quanta pass on an excitation, for instance a bump, in form of a longitudinal standing wave, by one particle bumping the neighbouring particle, analogous to sound waves, where one gas molecule passes the bump on to the neighbour. The transmission hence takes place as longitudinal scalar wave.

Electrons pulled apart to planar vortices in addition haven't got a closed vortex centre anymore on their journey. For the by Tesla in his laboratory used and publicly presented one wire energy transmission (1897, Patent Nr. 593,138) the transmission hence doesn't take place in the wire, but as vortices around the -wire. That explains, why only a relatively thin conductor, which normally should have melted, was necessary for a demonstrated power transmission of 10 kW. Tesla however could show, that the wire stayed cold and virtually no heating losses were measurable<ii> (fig. 9.5). He himself said, that this one wire transmission technology is much better than the alternating current technology full of losses, which stems from him as well. Tesla must have known the limit of 511 kV very exactly, because on several photographs one can see, that he changed the coiling technique off this value!

<i>: Philadelphia Public Ledger, Nov. 2, 1933

<ii>: resp. Tesla's lost inventions, VAP, page 36 and page 48, 49.


Nerve cell:
"Action potential"
Synapse
(= amplifier)
(= electrical signal)
(= diode + memory)
cell body (soma)
nerve fibre (axon)

Nerve conduction with 120 m/s

Fig. 9.6: Nerve cell and message processing (neurons)

- Material information conduction: at plants
- Information conduction with hormones: at simple animals
- Electrical information conduction: at higher developed creatures
- Analog transmission: from 10% and more difference in potential, and
- Digital transmission: number of the action potentials
- Modulated information: i.e. complex modulation of the action potential (the potential vortices)

9.6 Nerve conduction and action potential

Technical solutions often are only a suboptimum and many times they are anything but an optimum. In many cases the feasibility stands in the foreground. In the question of the current distribution at that time the decision was made for the worse system, the full of losses three phase system, because no current meters were available for the free of losses one wire technology. Without being able to collect money from the consumer, it wouldn't have been possible for the energy distribution installations to pay for themselves. Compared to that is nature with its selection principle merciless and without compromises. Only the most efficient system has a chance to survive and to spread. If it's about transmittining information in an electric way and two different principles present themselves, then in nature only the better one will be brought into action.

Let's take a look at the nerve conduction in the human body. In the synapses ion concentrations and electric potentials of 70 to 90 mV arise. Here with conventional gauges the activity of a nerve can be detected. From a measurement of the transmission time of synapse to synapse the velocity of the signal is determined. If we however want to measure between the switch points on the line, then we have to find out, that for instance with an ammeter actually nothing is measurable. In addition the nerve fibre has a miserable conductivity.

The biologist calls the electric signal just "action potential" and draws a vortex-like ring around the nerve fibre and speaks of a mixed digital and analogue information transmission.

The doctor on the other hand knows two different types, fast and slow nerves. In the inside both are built up virtually identical. A characteristic difference consists of the fact, that the fast nerves are jacketed with a thick fat layer.

The technician would say, they are better isolated, but why they therefore should be faster, he hardly would be able to answer. If we however assume, that the action potentials or OUT potential vortices oscillate around the conductor, thus exactly in the isolation layer and are forwarded there, then possibly an explanation would have been found.

The nerve conduction moreover has much in common with the one wire system of Tesla:

1. Charges and electric potentials are transmitted
2. Doing so a transport of charge carriers, thus an electric current on the line, isn 't detectable.
3. Consequently no losses worth mentioning occur.
4. Decisive for the functioning is the dielectric insulator material which surrounds the conductor and not the electric resistance of the conductor.
5. In contrast to electric circuits a draining conductor is unnecessary.

It looks as if the one wire system is not new at all, as would nature use it already for ages in the highest perfection. We realize immediately, why our head does without a ventilator and how the high of signal processing density can be explained. Compared with our brain modern personal computer (PC) with their backward cable technology are far less than a suboptimum.

With regard to the pressure on the environment by interference radiation we had derived, that currents and eddy currents with the skin effect direct their radiation to the outside, whereas potential vortices with their concentration effect direct it to the inside. Probably for this reason the radiation field of a person is environmentally better compatible than that of a PC.



Fig. 9.7: Wireless energy transmission, Patent No. 645,576 (1900) of Testa.<i>

<i>: Dr. Nikola Tesla: Complete Patents, Tesla Book Company, page 311-321.

9.7 Wireless energy transmission technology

Tesla still went a step further. He has cut the wire connection between transmitter and receiver (fig. 9.5) and instead has installed each time a spherical electrode (fig. 9.7). With this facility he now was able, to transmit energy completely wireless (1900, Patent No. 645,576). Building on this principle Tesla already 1890 had built a radio remote control for a battery operated submarine and had presented his patented system the navy. But they weren't able, to recognize the strategic importance of the radio technology and rejected with the words: "It's too advanced!" (fig. 9.8).

Tesla further had proven with this technology the mentioned proof concerning the existence of longitudinal electromagnetic waves. There exist descriptions, partly of Tesla himself, how he, inside or also outside his laboratory, goes in search of oscillation nodes of the standing wave with a measuring receiver<i>.
He names several conditions for the wireless energy transmission:

1. "perfect resonance" (same frequency) of transmitter and receiver
2. Installation of the receiver on an "oscillation node" (maximum).

Important is also the measurement of the velocity of propagation, and that isn't constant from the start for a wave, which oscillates in the direction of propagation. From the research of earthquakes we know, that the longitudinal waves are faster than the as well occurring transverse waves. Usually the distance to the epicentre is determined from the difference in transmission time.

In the patent specification the measurement is described<i>. Tesla has sent longitudinal radio signals from his transmitter in Colorado Springs once around the earth along the earth's surface and determined a transmission time of 0,08484 seconds. This corresponds to a frequency of approx. 6 Hz. He saw his result confirmed, as he could find the oscillation node of the standing wave again (according to $\lambda/2$) in his laboratory (on the ground plate).

For the full wave length λ the Schumann resonance, which describes a standing wave of an around the earth running Hertzian wave, lies as is well-known at 7.8 Hz! Tesla calculates for his wave a speed 1.6 times the speed of light assuming the polar radius of the earth to be 6363 km.

Also this measurement result confirms, that Tesla didn't use the Hertzian wave. Tesla found the off-beat concept of Einstein, the speed of light would be the fastest possible velocity of signal transmission, only funny. If however today is claimed, 1993 in tunnelling experiments for the first time a speed faster than light has been measured, then this just isn't true. Possibly also the Tesla wave tunnelled, as the vortices for a small conductivity of the air contract and as a result of the length contraction become correspondingly fast.

Later Tesla after several goes in vain even succeeded in building a high tension tube as a tunnel, with which the velocity of the signal could be increased arbitrarily. Tesla with that pursued the goal to be able to make radio contact with other worlds<ii>.

<i>: N.Tesla: Art of Transmitting Electrical Energy Through the Natural Mediums, US-Patent No. 787,412, 18.4.1905, Complete Patents pp. 397-402.

<ii>: M. Cheney: Tesla, Man out of Time, Barnes & Noble Books, New York, 1993, und S. 309, Omega-Verlag, 1996, ISBN 3-930243-01-6


radio
transmitter
and
radio
receiver

Fig. 9.8: Energy wave broadcasting system,
Patent No. 787, 412 (1900) of Tesla.

In today's switching technical notation:


(sphere)
antenna
bridge rectifier
ironless
Transformer
~
HF-
generator
charging
capacitor
-
+
timed load

9.8 Measuring and switching technique of Nikola Tesla

As an important and accepted experimental physicist with 14 doctor titles and carrier of the Edison medal Tesla always has held on to his measurement results. Not a theoretical interpretation but exclusively correct carried out measurements have shown him the physical reality. But the by Tesla won measurement results were already for 100 years hard to digest and couldn't be brought into accord with any theory. Therefore a switching technical analysis of the by Tesla described and carried out experiments should give us now information over the nature of the free energy, the tachyon energy, the orgone, or however fantastic the terms may read.

The Tesla coil, according to the instructions of the inventor, is a flat coil wound like a spiral in contrast to the copies today on sale which, surely out of ignorance, are mostly cylindrical. Its peculiarity probably is to be seen in the circumstance, that charges moved through the wire of the coil inevitably increase their angular velocity towards the centre, In this way the electrons, which at first are spherical elementary vortices, are pulled apart to vortex rings like planar discs.

Tesla switches the "secondary" called flat coil between two "terminals". Following he sends, stimulated by his "primary", charge carriers from one terminal to the other and back again and produces a standing resonant oscillation.

Mostly replaces Tesla one of both terminals by the earth. He thus assumes, that now the earth as a spherical electrode takes over the function of one terminal. That he again infers from the observation, that a by the transmitter wireless fed little lamp goes out, if he cuts the connection to the ground. Doing so the oscillation collapses. Radio sets on the other hand can also be operated without grounding, as we know!

The degree of effectiveness of today's distribution technology of current due to the heating losses lies clearly beneath 100 per cent. Without the losses of the wiring it lies close to 100 per cent for the discussed one wire energy transmission. There the vortex rings are guided nicely one after another along the line like beads drawn over a string. This result even is to be expected, as far as no vortex "jumps off the wire or "falls apart". For the wireless version Tesla however to his own surprise had to find out that more energy could be received, than his transmitter produced. The measured degree of effectiveness lay above 100 per cent! He therefore called his transmitter a "Magnifying Transmitter" (fig. 9.10). The further transmitter and receiver were away of each other, the further the received energy increased. Tesla inferred from this, that there had to exist free energy and that he had caught that too.

Consequently he had built a receiver for free energy and registered for patent (1901, Patent No. 685,957, fig. 9.9). Tesla states that the amount of energy depends on the size of the "terminal". Of today's sight we could be willing, to describe this receiver plate as a solar panel, but we should know, that the apparatus produced energy even at night! In addition the energy gain was considerable higher than for today's solar panels. Tesla spoke of "radiations ", of an unknown radiation and he in his lifetime has in vain sought-for help of explanation.

The vortex model will also in this question be a valuable help to us.


receiver plate
P
T
capacitor
switch
C
T'
load
P
P'
ground
contact
T
ratchet motor
C
b
a
t
t'
T
ω
M
P'
ground plate

Fig. 9.9: Receiver for "free energy",
Patent No. 685,957 (1901) of Tesla

9.9 Energy technical usage

The answer of the potential vortex theory could turn out as follows:
If at the transition of the one wire to the wireless transmission the ring-like vortices is purloined the guiding wire the vortices immediately begin to turn around each other, as is observable for flow-technical ring-like vortices,. In this way the ring-like vortex the next moment shows its inside. If it before was an electron vortex (fig. 4.3), then it now shows as positron, if it was negatively charged, then it now is positively charged. Following it oscillates back again, etc. Wit that the ring-like vortex on the average has no measurable charge and no mass, because it alternately forms matter and anti-matter. Without interaction it has an enormous ability of penetration . In physics such particles are called neutrinos.
Tesla thus had, apart from his transmitted energy wave, which turned out to be neutrino radiation, by chance also caught neutrinos which oscillated synchronously.

According to the actual level of knowledge do neutrinos penetrate the earth and appear also on the night side. The order of magnitude in every second amounts to approx. 66 billion neutrinos per square centimetre. It is a true bombardment. If we would be able, to collect and convert all neutrinos, the won energy would be entirely sufficient, to cover the need for energy of the world population (approx. 27 W/m^2). We merely have to materialize them, thus give them mass, charge and the necessary localization. Tesla was able to do that experimentally! Let's record:
The ring-like vortices, which Tesla with his transmitter has sent on a journey as electrons with an open vortex centre, are neutrinos (fig. 7.12). Tesla requests that transmitter and receiver operate in resonance, thus with the same frequency. Under this condition the receiver collects in all oscillating vortices, so that no one is lost.
If the neutrinos for instance are just positively charged when leaving the transmitter electrode, then an electromagnetic force of attraction takes place, if the receiver electrode at the same time is negatively charged. The required operation with the same frequency and opposite phase guarantees that also the next moment, if both, the neutrino and the receiver, have changed their polarity, the electromagnetic attraction is preserved.
It is obvious, that strange neutrinos which fly past and by chance oscillate synchronously are as well attracted. In that way the power collected in the receiver capacitor will increase further and degrees of effectiveness of over 100% are obtainable. Tesla discharges the receiver capacitor timed with the frequency of resonance (fig. 9.9) and points to the difficulty of an exact keeping of the condition of synchronisation.
Tesla indeed did work on a theory of his own, but never published it. The patent office and his lawyers had to proceed from the Maxwell theory, although Tesla knew only too good, that his apparatus in no way could be described with this theory. It therefore can't be excluded, that important facts in his patent specifications haven't been mentioned at all - or even worse - consciously or unconsciously in an inapplicable manner have been explained with the Maxwell theory.
Perhaps this is the more profound reason, why the numerous Tesla imitations don't want to function quite so well. With the new theory there should be some changes, and we should accept the challenge for the sake of humanity.

The transmitter tower of Tesla (57 m high with a spherical electrode of 21 m) for the transmission in multiplex mode of operation (according the inventor) of:

- telephone calls
- telegraph services
- teleprinter services
- radio programmes
- navigation signals
- time signals
- video signal



Fig. 9.10: The planned transmitter Wardencliff of Tesla on Long Island, 7.5 MW (1902).

9.10 Environmental compatibility

We now can summarize the different observations and try to find answers for the in the first chapter raised questions concerning the electromagnetic environmental compatibility.
The by Tesla used longitudinal energy wave is a potential vortex wave in the sense of the vortex model of Kelvin, which we again could identify as neutrino radiation (Dirac).
Also other, partly quite fantastic terms, are known like "radiations" (Tesla), "orgone radiation" (Reich), "tachyons" (Feinberg), "grid radiation" (Hartmann), "bioradiation" or "water veins".
Actually these rays have nothing to do with water as a cause. Water with its high dielectricity however favours and influences the course and the local distribution of the radiation. The maximums of the standing wave considered for themselves result lines in straight as a die in the landscape. Of Tesla is known, that he measuring technically could detect the cross points of the lines, which he called oscillation nodes. There exist so-called dowsers, who can make these standing waves out even without technical aids. For that they hold a fork in their hands, which suddenly moves over such lines.
Let's remember that the same potential vortices are used at the nerve conduction as reaction potentials to conduct stimuli. If ring-like vortices arrive at a muscle, it contracts without knowing, if the signal was sent from the brain over the spinal cord or picked up from the environment over the fork and the hand.

Thus if the same signals, which we use for the tasks of controlling and thinking, are also produced by technical apparatus, then this touches the question of the environmental compatibility in a direct way. Above extremely strong points of resonance, which are called "geopathic zones", now and then even is warned about "psychotronics", a function trouble of the brain, which can show in a disturbance of the waking consciousness.
A possible explanation would be that the brain is occupied with so much vortices picked up from the outside, that it isn't able anymore to accomplish its actual tasks. For muscle cramps or an inexplicable crash of a PC an correspondingly interpretation would be obvious.
As long as no gauges are available, the highest caution is imperative!

If Tesla had been able to put into operation his transmitter tower for longitudinal waves ("World Telegraphy", Wardenclyffe, Long Island, s. fig. 9.10) with the estimated power of 7.5 Megawatt and thus had been able to realize his dream of a world-wide wireless communication, then this could have had hardly estimable consequences for the health of the world population.
Shortly before the completion of the project, in the year 1905, Tesla without notice let stop all work. He to that never made an explanation to anyone. Officially it was said, his financial backer J. P. Morgan would have withdrawn his financial means. In any case was Tesla financially ruined with this step.
Perhaps also T. A. Edison was behind it, who was his opponent at that time. Edison committed himself engaged for the use of direct current. Against the alternating current, preferred by Tesla, Edison argued with unhealthy risks, and with that he perhaps wasn't so wrong at all.


N. TESLA.
APPARATUS FOR TRANSMITTING ELECTRICAL ENERGY.
APPLICATION FILED JAN. 18, 1902. RENEWED MAY 4, 1907.
1,119,732.
Patented Dec. 1, 1914.
P
D
V
P
D
B'
D'
H
F
F
B
A
G
F'
C
E
secondary winding:
A = 8,5 windings
B = 40 windings
primary winding:
C = 4 windings
Transformer transmission ratio:
= 12 times
WITNESSES:
M. Lawson Dyer
Benjamin Miller.
Nikola Tesla,
INVENTOR,
BY Kerr, Page & Cooper,
his ATTORNEYS.

Fig. 9.11: Concerning the technology of the Wardencliff transmitter (fig. 9.10).<i>

<i>: Dr. Nikola Tesla: Complete Patents, (J.T.Ratzlaff), Tesla Book Company (1983), ISBN 0-960356-8-2, P. 435.

9.11 Ecologically fair usage

Tesla not only has stimulated ecologically fair usages of the energy radiation. To that can be counted the use of a Tesla transmitter as a radiation weapon<i> as well as the mentioned building of a Tesla interferometer, the low-frequency interferences of which can lead to mighty gravitational waves and with help of which it should be possible, to produce earthquakes, to sink ships or to shoot down planes from the sky<i>. Against the background of two world wars it can be understood, why Tesla has drawn attention to the possibilities of a use of his system for the purpose of defence.

In today's sight a technology like Tesla's wireless energy transmission (fig. 9.11) hardly would have any chance of a large technical use, because it should be reckoned with enormous problems of environmental compatibility. After all had come out in our considerations, that entirely in contrast to the Hertzian wave just of the Tesla energy wave direct biological effects are to be expected. A purposeful medical use of the Tesla rays however can be imagined.

The collecting of "free" energy waves with a neutrino receiver at first undoubtedly would be a clean and ecologically fair alternative to the present energy technology, with which we heat or nuclearly contaminate our environment. But even the use of free energy converters has limits. Should it turn out that the Photosynthesis uses such a materialization, in which the necessary free electron for the chemical reaction actually is produced from a caught neutrino in the so-called reaction centre and thus the reaction energy is won, then for an as usual excessive use by men it can't be excluded anymore, that the plants on earth die and nothing grows anymore!

I in contrast attribute big chances to the one wire transmission technology. Because for an use of alternative and regenerative energy sources, like the sun in the desert or the geothermal energy in Iceland, the transport of energy has to be made over large distances through the oceans the small losses and the possibility to be able to use sea cables, play a big role. In the residential areas and conurbations on the other hand it has a positively effect, that by the concentration effect of the potential vortices the interference radiation is directed inward. Laid on the bottom of a sea or of a river, such a line in addition is protected against the effects of lightning and sabotage, and it neither spoils the countryside, as the old-fashioned high tension pylons do.

For transportation tasks the mentioned making use of the spin coupling would surely be the most suitable drive. The denser the medium, the more efficient would be the driving effect, for which reason not only flying objects, but quite particularly also ships and submarines could be operated non-polluting in this way without combustion and without exhaust fumes. Build up effects by the water pressure or the sound barrier don't occur. But control might not be entirely unproblematic. If for the reason of a unipolar arrangement of the field a relative velocity to compensate the field becomes necessary, then a correspondingly build up arrangement will do so without considering losses. It is no accident that most apparatus which got well-known have flown the builder sooner or later "past his ears" (note of the translator: broke into pieces). Till a commercially utilizable flying saucer has been built, many technological hurdles have to be taken.

Claims to an up-to date environmental policy
in view of longitudinal electromagnetic energy waves
= Tesla waves = neutrino radiation = scalar waves
= potential vortex waves:

1. Gauges must be developed and built, with which the energy waves can be measured.

2. All technical apparatus should be tested regarding the emission of energy waves. Harmful radiation should be avoided.

3. Only such transmitter antennas may be brought into action, which emit a minimum of energy waves.

4. The ability of biological systems to absorb energy waves should be determined. To that also belongs the question, how many vortices collect locally and how fast they fall apart.

5. Limits for allowed pressure produced by artificially energy waves should be fixed, regulations and laws enacted.

6. The in nature available energy waves should be brought to a technical use, with the goal of a natural energy production.

Fig. 9.12: Catalogue of claims concerning the environmental compatibility in the view of the new field theory.

9.12 Claims concerning the environmental compatibility

Now we still not know, if the using of a handy or another electronic device poses a danger to the user. Now, we surely can't exclude a danger, and the statement of the manufacturer, it is safe because all limits have been met, is worth nothing, as long as the part of longitudinal waves isn't measured. Therefore stands at the very top of the list of the catalogue of claims (fig. 9.12) the development and the building of gauges to measure Tesla radiation. More than half the 700 patents of Nikola Tesla concern the building of transmitter and receiver installations for energy waves. Here a lot of valuable clues are found, especially as he himself has built and used some of the switching circuit designs. In the seminar a rebuild is discussed, with which 1995 the existence of longitudinal waves could be proven [A7].

For an earthquake always both, the transverse and the longitudinal wave, occur simultaneously and, taken exact the same is valid for the sound wave, even if the transverse part doesn't get too far in the air. The emission of both parts in analogy is almost to be expected of an electromagnetic wave generator or transmitter. Actually both waves are detectable at the receiving point: The useful transverse wave and the longitudinally propagating vortices, which show as noise (fig. 4.7). If the vortices are predominant and the useful signal goes under in the noise, then a interruption of the radio operation occurs. Also small gardeners immediately near a radio station have made experiences as e.g. in a distance of one kilometre from the transmitter of RIAS-Berlin. They were able to light their allotments day and night with a neon tube, to which they merely had tied a free wire. The radio station immediately insinuated, that they in an illegal manner had tapped their useful wave and damped it. But it can't be excluded, that the transmitter has sent a longitudinal part in the ether too, which was responsible for the energy transport. But that suggests, that also at other transmitter antennas, thus for the mobile phones, the unwelcome parts is transmitted even than, if we don't use it at all.

Still another problem is added. If in a modern receiver radio waves arrive, then they roll up to a standing wave and according to fig. 1.4 to a vortex over the antenna. According to that we aren't able anymore to distinguish, if the transmission took place as Hertzian wave or as Tesla wave. The separation of both sorts of waves has to take place before the antenna is reached.

An up-to date measurement arrangement would look as follows: In front of the receiver antenna a path with a tunnel, which represents an insurmountable obstacle for the transverse waves (fig. 6.14), is placed. Then only the longitudinal waves pass the tunnel, and these at the end of the tunnel can be recorded and analysed with conventional technology. The tunnel is an elegant possibility, to make use of the part of Tesla waves. After all only this part is relevant with regard to the electromagnetic environmental compatibility. Concerning the above asked question we can take home at least one important realization. The probability is quite high, that you actually notice nothing of the handy radiation, because not every system react in the same manner to certain vortices. The resonance conditions regarding frequency, phase and position always have to be fulfilled, if an absorption of energy waves should occur. (fig. 2.10 B, E. coli bacteria). On the other hand it however can't be excluded, that just you or me synchronize according to frequency and collect 100 % of the transmitted energy radiation. In contrast to the Hertzian wave plays for that the distance to the source of interference only a secondary role! Seen that way worries would by all means be entitled ...

From Indian mysticism:


it neither is
this nor that
it is
not this
it is
not that
it is this
and it is that

Fig. 9.13: The structure of the world equation, an example from Indian mysticism

9. 13 Epilogue belonging to part 1

The correctness of a new theory not by all means guarantees, that it also is accepted! A new theory must be used. Only if a concrete need exists then an acknowledgement is to be expected if at first only by the direct beneficiaries.
In november 1994 in Munich the trade fair "Electronica" took place. Here invited by the Deutschen Gesellschaft fur EMV-Technologie (German association for EMC-technology, note of the translator) the books about potential vortices [Al, A2] were honoured with a prize by an internationally renowned EMC-scientist. The number of people, who the potential vortex theory helps further to find answers to problems, which until now aren't explicable, grows further.
Nevertheless, nobody should believe that something will be changed to the content of the text books in the shelves that fast. Habit and laziness encourage to further use the to date interpretation, even if a new theory has ready a better and convincing answer. It will take some time, to give an example, till the heating of water in a microwave oven is explained as eddy losses, as is described sound by the potential vortex theory already today. The discovery of a physical phenomenon may happen in a fright second. Its acknowledgement on the other hand as a rule is a lengthy procedure. If we look back in history we find out that even in the past it hasn't been otherwise.

Of the four fundamental phenomena in fig. 8.2 at first the tension voltages and the charges have been discovered by Coulomb (5.7e).
(5.7c): An effect of the eddy currents was observed already 1825 by the French physicist Arago. He discovered that a magnetic needle suspended above a rotating disc tends to rotate along. Out of ignorance he named the effect "rotational magnetism".
But the eddy currents could only be mathematically described with the help of two laws, the law of Ampere (1820) and the law of induction of Faraday (1831). Because the effect due to the eddy current losses rather was regarded as disturbing, technical applications or patents at first have stayed out. At first Riidenberg has carried out fundamental calculations for eddy current brakes in 1906. The discovery and usage of the "skin effect" is to be attributed to Tesla.
(5.7b): The electromagnetic wave for the first time was mathematically described by Maxwell (1864). He had aimed to calculate the light and he could show, that his theory actually could correctly describe all properties of the light. With that he was able to prove the correctness of his theory. But he had to deal with many sceptics, because he had postulated the dielectric displacement, without however in his lifetime being able to measure it because of its smallness.
This may be the reason, why the discovery is attributed to Heinrich Hertz and was and is spoken of the Hertzian wave. Neutrally seen Hertz at first was nothing more than a enthusiastic pupil, who had worked through the "Treatise"<i>, Maxwells books. All results, which Hertz could observe experimentally, already were contained in the Maxwell-theory and published.

<i>: James Clerk Maxwell: A Treatise on Electricity & Magnetism, vol. 2, Chapter XX: Electromagnetic Theory of Light. Dover Publ. New York

But the great mathematical description of Maxwell at first had a purely academic importance. The interest of the general public on the other hand concentrates on the practical applicability. Hertz had experimented with antennas and has laid the foundations of the building of a gauge for electromagnetic waves (1888). The wireless transmission of invisible waves was convincing. It was an entirely new technology, which stimulated fantasy in view of a technical usage. A practical man, who was stimulated by the theoretical realizations, was Marconi. He goes for the inventor of the radio (1895, Nobel prize: 1909).

Between the three summits, first the calculation and at the same time discovery, second the measurement and third the usage of the wave phenomenon lay 31 years, and the radio technology is developing still further, even today. In the area of the cellular phone network and the telecommunication even a kind of gold mining mood prevails, which can't be impressed much even by hints of an electromagnetic environmental compatibility.

In the euphoria of the past 100 years is fallen into oblivion completely, that besides the by Hertz detected transverse wave in the wave equation according to Laplace and according to the original version of Maxwell also a longitudinal wave was described mathematically. This one was discovered and detected by Tesla in numerous experiments. With reference to his discovery Tesla initially had asserted publicly, Hertz had been at fault, with which he undoubtedly was wrong and had incurred the wrath and the scorn of the scientific community. As a result of this development his experiments haven't been reproduced and the discovery of the scalar wave could fall into oblivion.

Not enough with such sanctions against the inconvenient freethinker Tesla a series of professors like Gibbs and Heaviside have made cuts and discarded all parts from the original version of the Maxwell equations, which by that time weren't considered to be experimentally proven by experiments of Ampere, of Faraday, of Ohm and Hertz. With that the scalar waves fell victim to the axe, what, though it had encountered severe criticism, finally entered as textbook opinion into all textbooks, after Hertz also had sanctioned this measure.

If the field equations according to Maxwell in today's revised version don't describe scalar waves anymore, then all orthodox scientists, who want to bear reference to that, have to bear one thing in mind: discarding a term of an equation is the same as neglecting it. But the term only may be neglected if it is sufficiently small. The first thing every student learns in the physical practical training is that this first has to be tested. For that the term has to be measured and its order of magnitude must be determined. Then it is little helpful and extremely unscientific, if at first is neglected and on the basis of the revised field equations, which have put all scalar waves to zero, is demonstrated that the neglect was allowed or even necessary.

A practical example are the longitudinal wave parts, like they occur and are proven in the near-field of a transmitter antenna. Considering the order of magnitude a neglect is out of the question. On the other hand they should not exist at all according to textbook physics, because they had fallen victim to the axe. Since most scientists in present time do not know about the cutting action anymore, they are postulating field vortices anew in the proximity of an antenna. Field vortices, which are propagating longitudinally in the direction of a field pointer as a scalar wave.

With that they calculate their own arbitrary assumption<i>.
If in the practical training of physics a student unevaluated neglects an essential factor of influence, then his experiment goes as not passed. The experiment must be repeated so long until according to the approved methods of scientific soundness all used neglects have been tested individually and have undergone an error consideration.
Do we now have to deny the cutting action, which had been plotted by Gibbs, Heaviside and others, having the necessary scientific soundness? Do we have to review and rework all textbooks concerning the illegal neglect? Since the cutting action a gap gapes in the field theory!

(5.7d): The potential vortex fills the remaining gap in fig. 8.2. Several research scientists and scientists can be named, who already could observe this phenomenon: in front of all goes Nikola Tesla for discoverer of the Tesla currents, very weak currents which are said to cause extremely high potentials. Here presumably cause and effect have been mixed up, because weak currents never can produce high potentials. Actually the potentials prove to be a result of the potential vortices, whereas the currents aren't more than a result, nothing but leak currents. At least Tesla could use the vortex, but without a usable theory he neither could calculate nor adequately explain it. Besides Tesla Wilhelm Reich should be mentioned, who has collected the vortices in his orgone accumulator.
Mostly only certain aspects were observed and investigated: by Tesla the planar vortex, by Reich the influence on the weather, by Schauberger the water vortices and by all three the medical and biological aspect. The list of names is incomplete and could arbitrarily be continued.

With the discovery of the potential vortex (1990) the basis for the building of a gauge and the technical usage of the physical phenomenon is laid [Al]. It not only concerns the search for water, but also the detecting of the vortex balls and vortex streets, of the standing waves of the energy radiation in the air, at the workplace, at the bedroom, in clinics, in recreational areas and hotels. As explained at the start, neither the field strength of a Hertzian wave nor the arising heat development can be made responsible for biological or technical harm.
It primarily are the newly discovered vortices of the electric field, which take effect. The effects can, as we have seen, as well be good for health as bad for health. Intensity, plane of polarization, vortex configurations and many other characteristics play a role here. To research these influential factors gauges for vortices will be needed as well.
We have to realize that in the technical domain the electromagnetic compatibility of an apparatus is determined by its sensitiveness to vortices, thus by the fact how many and which vortices can cause a function trouble. To determine the environmental compatibility of a product the emitted vortices, the energy radiation, have to be measured. Limits for high tension lines, for screens or handheld phones must be given in units of the potential vortices. The potential vortex has shown us the way to a unified theory and has brought along a new picture and understanding of our environment. It with that wants to show us the correct way for an ecologically compatible dealing with nature.

<i>: Zinke, Brunswig: Lehrbuch der Hochfrequenztechnik, 1. Bd., 3.Aufl. 1986 Springer-Verlag Berlin, Seite 335

Part 1: Edition belonging to the lecture:
"Electromagnetic Environmental Compatibility"

Prof. Dr.-Ing. Konstantin Meyl

Scalar waves

Abstract:

1. Auflage 1996, 4. Auflage and 1st English Edition 2003

Both technical and biological systems can be influenced by electromagnetic fields, whereby numerous questions still are open, like e.g. concerning limits and the nature of physical interference fields. The book shall do justice to the circumstance, that a fact oriented discussion about „electrosmog" implies an analysis of possible reasons, a mathematical derivation and a physical argumentation.

We proceed from the assumption, that only that part of the electromagnetic wave should be considered for malfunctions, which has been absorbed and which has rolled up to a field vortex. The effectiveness depends on the amount of the produced vortices and on the life span, the decay of vortices.

Analogous to the sound wave vortices in space are propagating as longitudinal waves. In this context is pointed to numerous effects. Examples for the technical and biological use of these standing waves are the energy transmission of Nikola Tesla as well as the nerve conduction, which functions in a corresponding manner. If the same vortices, which man uses for conduction of information, are emitted by technical devices, then biological reactions can't be excluded anymore and worries with regard to „electrosmog" seem to be justified.

Causes, phenomena and natural scientific consequences

INDEL GmbH, Verlagsabteilung, Fax: +49-7721-51870
Tel: +49-7724-1770
Postal and ordering address:
l.TZS, Prof. Dr. K. Meyl, Leopoldstr. 1, D-78112 St. Georgen/Schwarzwald
www.k-meyl.de meyl@meyl.de

Scalar Waves

From an extended vortex and field theory to a technical, biological
and historical use of longitudinal waves.

Part 2

by

Professor Dr.-Ing. Konstantin Meyl

Edition belonging to the lecture and seminar "Electromagnetic environmental compatibility"

(Original title: "Elektromagnetische Umweltvertraglichkeit")

Translated out of the German language
by Ben Jansen
(2000-2003)

* * *

Part 2: Edition belonging to the energy technical seminar

Free energy and the interaction of the neutrino radiation

***

INDEL GmbH, Verlagsabteilung

Villingen-Schwenningen 1996-2003

ISBN 3-98O2 542-4-0

Preface to the seminar

The point of a seminar is, to deepen, to practise and, as far as possible, to practically appy the material of a lecture. The knowledge of the content of the lecture hence is a prerequisite for the participation.
For the reader of this book that's tantamount to the recommendation, to have read the first part, the edition belonging to the lecture, before*[1]*. Here the questions concerning the „electromagnetic environmental compatibility" are asked and the necessary bases for their answering is laid. Also practical consequences for various areas of science are indicated. The deepening most suitable should be made in form of a seminar, subdivided into the here presented part 2 to the energy technical seminar and a part 3 to the information technical seminar. Part 2 correspondingly concerns the energy technical aspect of electric or magnetic longitudinal waves, whereas part 3 is dedicated to the information technical aspect<ii>. Because it concerns a book which merely for reasons of usefulness is published in three parts, the chapters are consecutively paginated. References to chapter 1 to 9 hence automatically relate to part 1. The numbers of the figures and tables as a rule are identical with those of the chapters, in which they are discussed.

The seminar should lead on over the pure reading, consuming or listening and should stimulate to join in. All involved persons may and should give ideas and ask questions, even if these may sound little orthodox. The scientific working method takes, that is struggled for answers and even is argued, if necessary. To reach this goal, it mustn't exist any obligation or censorship, neither for the leader of the discussion nor for the participants of the seminar.

The seminar is being carried out since the summer semester 1997. The works of the seminar written by students treat the knowledge of text books of the respective theme. Following the lecture the answers are discussed and compared to those of the theory of objectivity<i> and other models of explanation. This procedure in this edition belonging to the seminar is reflected at some points, if for instance a chapter is completed with a „discussion".

The first edition of this 2nd part still was incomplete and has been handed out to the participants of a congress in Switzerland instead of a manuscript belonging to the lecture the 17th of Nov 1998. The here presented second edition in the meantime to a large extent is complete, but surely not yet perfect. In accordance with the experience made with the first part of the book also for this 2nd part a third and revised edition, in which the ideas of the participants of the seminar and of the readers find consideration, will be due to be dealt with after a year. The reader of the second edition has to console himself with the fact that a lively seminar constantly is changing and developing further. And that has to be so!

Villingen-Schwenningen, January 1999

<i>: Electromagnetic environmental compatibility, Part 1, Edition belonging to the lecture, INDEL Verlagsabteilung, 1996, see page 1-218 of this issue.

<ii>: Electromagnetic environmental compatibility, Part 3, Edition belonging to the information technical seminar, 2002, see page 443 - 625 of this issue.

10. Oscillating interaction

A theory is not an end in itself, even if it sounds very convincing. It has to be measured by its applicability. As an entry into the practical consequences, which result from the theoretical part[i], the question about the validity of Kepler's laws is raised.

10.1 Kepler's laws

The "radius vector", a line drawn from the sun to a planet, sweeps out equal areas in equal periods of time. At least has teached us Johannes Kepler it that way (fig. 10.1). The balance of forces, the gravitation on the one and the centrifugal force on the other hand results in the innermost planets of our solar system orbiting the sun very much faster than the outer planets (Mercury in 88 days, the Earth in 365 days, Jupiter in 4333 days and Pluto in 90465 days!).
For the inner planets as well as the big planets Jupiter and Saturn Kepler's laws are still found confirmed. But that shouldn't apply anymore for the outermost planets of the solar system. Beyond Saturn should prevail changed rules as is said, based on observations of the Voyager spacecrafts[ii].

If we direct our view to an unknown galaxy, then does it rotate around its centre and in doing so to a large extent keeps its form. Despite rotation of its own an elliptic, a barred or even a spiral galaxy virtually doesn't change its characteristic form. From this follows, that the inner stars of a galaxy are considerably slower on their way than the outer stars! But we expected exactly the opposite.
According to Kepler's regularity the outermost stars would have to orbit extremely slow, In order not to be hurled into space as a result of the centrifugal force. But then a galaxy wouldn't keep its structure. The spiral form, as it already has been observed and classified by Hubble (fig. 10.2), merely would be an accidental exception as a momentary picture, but by no means the rule.
We have to take note, that the structure and in particular the cohesion of a galaxy can't be explained with Kepler's laws[iii].

<i>: Konstantin Meyl: Electromagnetic environmental compatibility, Part 1 of this book: Causes, phenomena and natural scientific consequences.

<ii>: Kendrick Frazier: Das Sonnensystem, Time-Life Bucher, Amsterdam (1991)

<iii>: The basic laws of the universe start to rock: ,,What is the matter with the galaxies? They rotate in their fringe ranges much faster, as is allowed by the laws of physics. Or is something wrong with these venerable laws? The astronomers and physicists stand for the dilemma to have to decide between the two alternatives: feign the observations us an other world or do we calculate wrong since centuries?" (translated), Bild der Wissenschaft Nr. 2, 1989

Kepler's 1st law:

The planets move in elliptical orbits, with the sun at one focus.


planet
perihelion
sun
aphelion

Fig, 10.1: Kepler's 2nd law (concerning the conservation of angular momentum):

The line drawn from the sun to the planet sweeps out equal areas in equal periods of time.

Kepler's 3rd law:

The ratio of the squares of the revolutionary periods of two planets is equal to the cube of their average distance to the sun:

$$\frac{t_1^2}{t_2^2} = \frac{r_1^3}{r_2^3} \qquad (10.1)$$


normal spiral galaxy
Sa
Sb
Sc
sphere
disc
E0
E3
S0
SBa
SBb
SBc
elliptic galaxy
Barred spiral galaxy

Fig. 10.2 The classification of the galaxies according to Hubble<i>

<i>: according to H. J. Lugt: Vortex Flow in Nature and Technology, page 223

10.2 Unknown interaction

So which interaction keeps a galaxy together? We today believe to know four different sorts.

I. The gravitation<i>: But since Kepler's law isn't valid in this case anymore, the gravitation is ruled out from the start. Obviously for the distances in a galaxy it hardly is effective.

II. The electromagnetic interaction: It is responsible for the structure of the atoms. Looked at from the outside atoms carry no charge, i.e. the charge conditions are balanced. A binding of our sun to the centre of the Milky Way by an electromagnetic interaction thus is ruled out as well.

III. The strong interaction: Since for the proton another charge distribution is measured, as a single positively charged particle should have according to the normally used theory, the strong interaction was introduced as a nuclear force, to explain the big error, the grave difference between measurement and calculation. The good advice hence reads: instead of giving birth to postulates at random, first of all the fault should be searched for in the normally used theory<ii>!

IV. The weak interaction: It quite obviously is involved in the particle decay<ii>. Both, the weak and the strong interaction, only have an extremely short range. With this property they consequently won't be able to keep a galaxy together.

Conclusion: In a galaxy a still unknown interaction takes effect, and science is requested to search it.

Both interactions with infinite range, the electromagnetic interaction and the gravitation occur as a result of static fields, therefore assume a constant charge or a constant mass. Considered more exactly in that case it merely can concern special cases. Gravitational waves, which reach our earth and which are detected in very costly experiments<iii:>, already show that the existence of alternating fields can't be excluded and oscillating interactions by all means are conceivable! The physical research at present probably is on the right track. The researchers however don't have ready an usable explanation yet. We accept the challenge!

<i>: Derivation of Kepler's 3rd law in fig. 11.10

<ii>: Konstantin Meyl: Potentialwirbel, Band 2
INDEL-Verlag, Villingen-Schwenningen 1992, ISBN 3-98O2542-2-4

<iii>: Gero v. Randow: Wenn kosmische Katastrophen Raum und Zeit verbiegen, zum Thema Gravitationswellen-Detektor, VDI Nachrichten Nr.9, 1.3.91, S.32

Analogy:


for direct current
for alternating current
I
I_d
t
I
$I_d = 0$
(10.2)
t
Measurement:
mean
(moving-coil instrument)
effective value
(moving-vane instrument)

Fig. 10.3: Direct current and alternating current

constant charge: **Electromagnetic Interaction**	oscillating charge: **Resonant Interaction**
constant mass: **Gravitation**	oscillating mass: **Levitation**

Fig. 10.4, a: The four fundamental interactions

10.3 Harmony of the alternating current engineers

Today's situation can be clarified by the following picture: you engage a "direct current engineer" to measure the tension voltage in the socket of our power supply system. The „dyed-in-the-wool direct current engineer", who never has heard anything of alternating current, reports: „No tension voltage is measurable". If he for reason of your doubtful expression looks still more exact he will realize: ,,The pointer of my moving-coil instrument strangely fidgets around zero, but the swing is so small that one confidently can touch it", (fig. 10.3)
Modern science is accustomed to say, without a valid theory and without technical measurability nothing can exist, what mustn 't exist. If you drop dead after the experiment, then you probably had a weak heart or other afflictions. In such cases as a rule the victim himself is to blame and by no means theoretical physics!

In the case of our power supply system the answer is known: The mean of the alternating voltage of the network is approximately zero. The pointer of a moving-coil instrument for reason of its inertia can't follow the fast changing anymore and only fidgets on the spot. The effective value however amounts to around 230 Volts. But to measure it you need another device, for instance a moving-vane instrument. Seen so, direct current describes the special case of alternating current with frequency zero.

The properties of alternating current can be depicted best by an extraterrestrial observer. He will tell us: Seen from a distance at least at night a great harmony seems to prevail on earth. All lights in the streets and cities twinkle completely synchronously. All generators are in resonance among each other and with all consumers. There are two big races: The 50 Hertz race and the 60 Hertz race, which appear if the earth turns further and the 50 Hertz race is switching off again its twinkling lamps.

The synchronization necessary for an exploitation of alternating fields is so obvious for us, that hardly anybody realizes, that a consumer operated with only one Hertz difference to the frequency of the network can't be supplied with power anymore. Apart from the correspondence in frequency it even depends on the correct phase. The phase angle must be between 0 and +90°. This corresponds to an efficiency factor $\cos\varphi$ between 1 and 0. The cable connections serve both the transport of current and the synchronization of all the generators and consumers connected to the network. The frequency is kept so constant that simple clocks, switching stations and even old record-players can be operated synchronously with the frequency of the network.
The synchronization of the feeding in power stations is supervised by a station of its own, which dictates the time. It is true that we aren't capable of seeing the twinkling of the lamps anymore for reason of the inertia of our eyes, but it can be detected and filmed with high-resolution cameras. Even if we can't perceive the harmony of the alternating current engineers, it nevertheless exists.


The effect of open field lines<i> ⇒ **charge**
E
constant charge:
electromagnetic interaction
oscillating charge:
resonant interaction
The effect of closed field lines<i> ⇒ **mass**
constant mass:
gravitation
oscillating mass:
levitation

Fig. 10.4, b: Explanation of the fundamental interactions

<i>: Konstantin Meyl: Potentialwirbel, Band 2, INDEL-Verlag (1992)
see also in Part 1, chapters 6.8 and 6.9

10.4 Four fundamental interactions

These considerations suggest, that also gravitation and electromagnetic interaction merely describe the special case of oscillating interactions with frequency zero. To avoid confusions, we'll have to think of new names.

The electromagnetic interaction can be clarified by means of open field lines, which start at a charged body and end again at another body of unequal charge. In physics classes it is normal to make the field lines of a magnet visible with iron filing. Between the unlike poles a force of attraction is observed<i>.

If we this time assume that both magnetic poles change their polarity at the same time, then the force will decrease for a short time during the changing of polarity, to afterwards be active again in full magnitude and in the same direction. Therefore a force of attraction is observed again even for a reversed polarity.

The generalization hence reads: The electromagnetic interaction will occur also in the oscillating case, but in weakened form, if both bodies involved in the interaction change their polarity synchronously and if they are in resonance. A name by analogy would be "resonating interaction" (table 10.4).

It is known of the electromagnetic interaction, that its effect is larger than that of the gravitation by powers often. This presumably has to do with the described and observable bundling up of the open field lines, whereas closed field lines can't be bundled up. The gravitation hence is linked with the closed field lines, which surround all elementary particles, every atom and every body<i>.

The opposite of the bundling up is the repulsion of open field lines, for which reason here also forces of repulsion can occur. For the gravitation however no repulsion is observed, because closed field lines virtually can't be influenced.

Apart from the circumstance that the effect generally will be smaller in the oscillating case, similar properties are to be expected. Also its range will be infinite as well. It is recommended to call the case of oscillating charges, as already said, "resonating interaction" and the case of oscillating masses, the oscillating gravitation, „levitation" (table 10.4).

The term „levitation" is very appropriate, but not new. Unfortunately until now no generally binding definition existed, what should be understood by that, for which reason misinterpretations and irritations can't be excluded. Mostly levitation is linked to a cancellation of gravity, up to a state of free floating, but we will see that quite other phenomena become describable with this term.

10.5 Resonating interaction

The question, what keeps a galaxy together, now can be answered unambiguously. The well-known interactions already have been excluded. If for the enormous distances the gravitation can't keep the outer stars anymore in accordance with the Kepler rule, then the levitation won't be able at all.

Example: central star S_z with 3 planets P_1-P_3
and with 4 neighbouring stars S_1-S_4


S_1
S_2
P_1
(fast neutrinos)
P_2
S_z
(slowed down neutrinos)
P_3
S_4
S_3

Fig. 10.5: The invisible threads of a resonant interaction

milky way-radius: 15000pc*3*10^9 = 45*10^{16} km
sun system-radius: 50 a*15*10^7 = 7,5*10^9 km

$\frac{45\cdot10^{16}}{7{,}5\cdot10^{9}} = 1{,}27\cdot10^{8}$	the resonant interaction is more than eight decimal powers bigger than the gravitation!

Therefore the oscillating charge is left. Actually the resonating interaction will reach to the outermost areas of a galaxy. The bundling up of the field lines results in the centre of the galaxy and one of its stars to stand in an exclusive resonance to each other, what looked at from the outside looks like, as if the star hangs at an invisible string or a "rubber band" and thus turns around the centre.
Because quite a few stars hang at the centre of a galaxy, it can be assumed that it provides correspondingly many resonance. The centre perhaps is comparable with an extremely broad banded transmitter, which operates on all channels simultaneously. The stars then pick as a receiver the for them suitable channels and hang themselves by „rubber band" at the heap (fig. 10.5).

Should there exist any particles with an oscillating charge, which synchronize between centre and star with the resonating interaction, then they will mediate between both partners. If we assume that the centre at one channel just is positively charged, then all at the same time negatively charged particles will be attracted, the positively charged particles however repelled. Whereas the unlike particles in the centre participate directly in the production and maintaining of the oscillation, the like positively charged particles will be hurled into space.
But at the same time does a star, which clings to the centre, have to be negatively charged. It hence attracts the repelled particle. The particle thus drifts from the centre to the star, even then if all three, the centre, the star and the particle, change in polarity. The result is, that the stars grow in diameter by collecting the particles. Only because our sun actually grows, it has the chance, to sometime become a red giant!

Since the sun radiates, as is well-known, in every second a radiation equivalent of 5 million tons, it permanently has to be supplied with a substantially greater amount of matter. If a resonating interaction should occur, then our sun will get its „material" supplied from the centre of the Milky Way and that is a black hole!
But no particle with a mass comes out of such a hole, yes not even light. For a particle to be able to leave the black hole, it should have neither charge nor mass. At most an oscillating charge and mass would be allowed. Such a particle would have an enormous ability of penetration as a result of the missing static interaction. It would be able to rush through the earth unhindered.

According to actual knowledge only neutrinos have the described properties. One also knows that the centre of our Milky Way represents a mighty source of neutrinos. From this derivation follows:

1. As mediators of the resonating interaction serve synchronously oscillating neutrinos.
2. Starting with the proof of the neutrinos it should be able to backwards also prove the existence of the resonating interaction.
3. If, as a practical consequence, we imagine that the centre of the Milky Way wouldn't supply neutrinos anymore. Then the whole galaxy would fall apart and not one of its stars would shine anymore.



Fig. 11.1: The Atlantic ocean floor<i>

<i>: Miller, R.: Driftende Kontinente, Time-Life, Amsterdam 1991, S. 79

11. The growing globe

11.1 Long-distance effect of the neutrinos

The long-distance effect thus lies in the circumstance that the neutrinos, in the case of a resonance of the source of neutrinos and the receiver, span an invisible „rubber band" between both, which is called resonating interaction and keeps the two together.

As a transmitter of neutrinos functions for instance a supernova, the death of a star, in which 98% of the mass annihilates under emission of neutrinos or a black hole, which continually swallows light and matter and spits them out again as neutrinos after a still unexplored „process of digestion". The process, which in the case of a supernova takes place as a singular occurrence, in a black hole possibly takes place permanently.
The hurled out neutrinos on the other hand serve the sun as a source of energy.
A receiver of neutrinos then for instance is our sun. So that the hard and very fast cosmic neutrinos become utilizable for the sun, they at first have to be slowed down. But that is only partly successful:

1. Some very fast ones manage to pass through the sun and fly out again on the other side of the sun. The compared to the cosmic neutrinos strongly slowed down neutrinos then are called solar neutrinos.
2. Another part can be further slowed down and materialized. As a result of the oscillating mass of the neutrinos as well particles of matter as also some particles of anti-matter are formed. The particles of matter make the sun grow.

i. The with matter incompatible anti-matter annihilates under emission of light as is well-known. For this and for no other reason our sun shines!

Also the planets have such a neutrino reactor at their disposal. Only so the heat in the inside of the earth is explicable! It can be assumed that the planets materialize less the fast and hard cosmic neutrinos and that they are served more by the slowed down solar neutrinos, which our sun releases again unused.
As is well-known radiates the planet Jupiter already today twice as much radiation energy, as it from the sun receive. In this typical encyclopaedia type balance the involved neutrinos of course are not considered. But it shows that Jupiter is on the best way to become a sun itself. Its moons then will become planets.
From this the example we also see that with increasing mass the crust of the planet becomes thinner and thinner at the expense of the neutrino reactor in the inside, until it finally is eaten up and the celestial body openly starts to shine. Astronomers report for reason of their observations of the formation of more and more new stars.

One part of the collected neutrinos thus is materialized by the planet. In the case of our earth it contributes to its growth.
Who doesn't want to believe that the earth becomes bigger, should look at modern maps of the oceans, on which the topography of the ocean floor is shown. According to the theory of Alfred Wegener concerning the continental drift North and South America on the one hand and Europe with Africa on the other hand steadily drift apart since 200 million years. The result can be read at the atlantic ocean floor. The gaping, chequered rift zones to the right and left of the Mid-Atlantic Ridge show how the earth is torn apart (fig. (11.1).



Fig. 11.2: The pacific ocean floor<i>

<i>: Miller, R.: Driftende Kontinente, Time-Life, Amsterdam 1991, S. 78

11.2 Model of expansion

Geographers assume that at another point to the same extent continental plates are subduced and molten. That thus has to happen in the Pacific Ocean. But the sea maps tell one just the opposite (fig. 11.2). At the ocean floor of the Pacific Ocean the same rift formations are found as in the Atlantic Ocean (fig. 11.1). That means that America drifts away from Australia and Asia exactly as from Europe, without being crushed or molten in doing so!
The only possible answer thus is: the earth grows.
The characteristic rift zones in addition are found around the Antarctic. From this the conclusion can be drawn that the 7th continent slowly is moving away, while the biggest habitable mass of land predominantly stays behind on the northern hemisphere, by Eurasia and North America forming a clip around the North Pole.

Concerning the evolution of the earth there are and were numerous approaches in various directions. Paul Dirac[i] at his time postulated, the brightness of the sun should decrease as a result of a decrease of the gravitational constant as well. In contrast to that Astrophysicists today observe just the opposite (Ingersoll 1987). According to the hypothesis of Carey[ii] energy will transform in matter in the universe. According to the idea of Oesterle[iii] aether particles are absorbed, which make our globe grow. Also other research scientists share the idea of the growth of the earth with him in their reports[i4,5,6]. As a geologist Oesterle[iii] cites his colleague Herzig: „The at the Mid-Oceanic Ridge newly produced oceanic crust has to be consumed again at other points, because otherwise the earth would expand" and criticizes the „plate tectonicians" that they would postulate their model without physical grounds.
He gives some arguments for the correctness of the model of expansion [iii]:

a) Subduction: The already discussed missing of zones of subduction and of melting of continental plates to the assumed extent.

b) Paleomagnetism: errors and mistakes in the hypothesis of the migration of the poles.

c) Continental depth drillings: They brought much higher temperatures in depths from 4000 meters, as expected and calculated according to models.

d) Stand of the sea water: Only if the water can spread in newly forming oceanic basins it can be explained, why the covering with water on earth continually is going back. This argument we want to investigate with a derivation of our own.

<i>: Dirac, P. A. M. Nature 139, p. 323 (1937)
<ii>: Carey, S. W.: Theories of the Earth and Universe.
Stanford University Press: 1-413, Stanford, California
<iii>: Oesterle, O.: Goldene Mitte: Unser einziger Ausweg,
Universal Experten Verlag, Rapperswil (1997), ISBN 3-9520261-9-0
<i4>: Hilgenberg, O. C: Vom wachsenden Erdball, S. 1-56, Eigenverlag,
Berlin (1933) und Neues Jahrb. Geol. Palaont. Abh. 116, 1, Berlin (1962)
<i5>: Jordan, P.: Die Expansion der Erde. Vieweg 1-180, Braunschweig (1966)
<i6>: Giancarlo Scalera, K.-H. Jacob: Why expanding earth? Institute Nationale di Geofisica e Vulcanogia, Roma and Technical University of Berlin 2003

Today's earth:



equatorial radius: $R = 6378$ [km]

earth's surface: $O_E = 4 \cdot \pi \cdot R^2$
(sphere) $= \underline{\underline{5{,}112 \cdot 10^8}}$[km²]

29% of this area is land and 71% is water
for an average water depth of $t_w = 3.8$ [km] results a

water volume of: $V_w = 0{,}71 \cdot O_E \cdot t_w = \underline{\underline{1{,}38 \cdot 10^9}}$ [km³] (11.1)

The earth **200 million years ago** (super continent: **Pangaea**):

today's land area (29%) was 100% of the earth's surface!

Pangaea surface area: $O_p = 0.29 \cdot O_E$
$= \underline{\underline{1{,}48 \cdot 10^8}}$ [km²]
$= 4 \cdot \pi \cdot r_p^2$ (11.2)



Pangaea radius: $r_p = \sqrt{O_p/(4 \cdot \pi)}$
(corresponds to $= \underline{\underline{3435}}$ [km]
the radius
of the sphere of shelf): = 54% of today's radius

Pangaea volume: $V_p = \frac{4}{3} \cdot \pi \cdot r_p^3 = \underline{\underline{1{,}697 \cdot 10^{11}}}$ [km³] (11.3)

Pangaea was covered with water h [km] high:

volume: $V = V_p + V_w = \frac{4}{3} \cdot \pi \cdot (r_p + h)^3 = \underline{\underline{1{,}71 \cdot 10^{11}}}$ [km³] (11.4)

= 15,7% of today's volume of the earth

$r_p + h = (3 \cdot V / 4 \cdot \pi)^{1/3} = 3443{,}8$ [km] (11.5)

Pangaea water-level h above the NN (sea-level) at that time:

$$\boxed{h = \underline{\underline{8{,}78}} \text{ [km]}} \quad (11.6)$$

Fig. 11.3: The calculation of the covering with water on earth 200 million years ago

11.3 Ancient Egyptian legend of Genesis

We don't have to search long for evidence. If we go back 200 million years in the history of the earth, as all continents still were united and formed the super continent Pangaea, as the 29% landmass of today thus constituted 100% of the earth's surface. At that time the diameter of the earth was almost half of today's diameter (exactly 54%). But if one distributes the amount of water of our oceans of today over the smaller earth, then possibly the water stood the young earth up to its ears in a first rough estimate. We now want to calculate how high the water stood.
For that we determine at first the water volume of today's oceans, by multiplying 71% of the earth's surface O_E with the average water depth. In doing so it is supposed that the water volume has not changed in the course of time. As an approximation this assumption could be correct if the factors, which influence the water volume, mutually compensate. On the one hand it has to be taken into account that in the process of fusion in the inside of the earth apart from other materials also juvenile water is formed, but on the other hand the water volume is reduced by photosynthesis and by the splitting of water molecules. In the case of the newly formed water it should concern roughly one cubic kilometre per year<i>. The photosynthesis however possibly can be estimated by means of the formed oxygen of the air just as the splitted water by the content of oxygen of the waters and the seas. Since the processes are subject to temporary fluctuations, the exact estimate is difficult. At least should an effect of compensation more or less be taken into account.

Next we calculate the surface of the earth 200 million years ago, the super continent, which Alfred Wegener called Pangaea. If the 29% continental land mass of today at that time constituted the whole surface, then the diameter of the earth at that time was determined at 54% of today's diameter, then the volume together with the water volume would amount to only 15.7% of today's volume and the water stood 8.78 kilometres high above the level NN at that time (fig. 11.3). With that even the highest peaks were under water.

Consequentially stands in the legend of Genesis of the ancient Egyptians:

„ They tell us that the earth was completely covered with water and that the earth rose from the water. It is talked about a primeval hill, of which creation took its start, on which the first sunrise and sunset was observed<ii>.

If at that time life only existed in the water, of which we today still can detect the remains in excavations in mountains and plateaus, then it surely wasn't because the evolution had forbidden living on the land. There existed no land! All land was lying under water. But if, looked into the future, the land area increases further at the expense of the surface of the sea, then our earth sometime will dry up, as already other planets before us, e.g. our neighbouring planet Mars.

<i>: Oesterle, O.: Goldene Mitte: Unser einziger Ausweg, Universal Experten Verlag, Rapperswil (1997), ISBN 3-9520261-9-0

<ii>: Robert Bauval und Graham Hancock: Der Schlussel zur Sphinx, List Verlag (1996), S. 253 and in der Sendung: Die grossen Ratsel VII am 25.5.97 in S 3



a. **Today's earth**:

earth's crust
earth's mantle
30-70 km
2800 km
2200 km
1300 km
outer core
inner core

b. The earth **200 million years ago** (super continent: **Pangaea**):

earth's crust
(d_k = 94 km)
earth's mantle
(d_m = 2800 km as today)
94 km
2800 km
earth's core
(R_p = 541 km)

Fig. 11.4: The inner structure of the earth on an average

11.4 Inner structure of the earth

Next the question is raised: How fast does our earth actually grow? The calculated growth, distributed over the 200 million years, results in a yearly increase in the diameter of the earth of less than 0.1 mm. Carey[i] assumes 0.04 mm per year and Owen[ii] only 0.01 mm per year.

Actually the young earth must have been somewhat bigger than calculated, because as a result of the smaller gravitational acceleration the density of the matter must have been smaller. But this changes nothing to the relations, because the less dense earth was surrounded by likewise less dense water, the water-level nevertheless reached the peaks, as already calculated.

For indicating absolute linear measures and the calculation of the gravitational accleration the respective density should be considered. In most calculations the density is cancelled out, so that as well can be calculated with an unchanged density.

A grave error however lies in the assumption of a linear growth. Hilgenberg assumes an exponential growth[iii] and gives as a reason for the empirical approach of the e-function the „law of organic growth". In order to now not to speculate or to postulate in the same manner, we will derive and found our approach.

If namely the earth grows, then its core of fusion also grows, which causes the growth to take place accelerated, etc. A customer of a bank, who sees his amount of money grow according to such a regularity, will be given information immediately about the growth rate with a compound interest calculation.

But how big is the growing fusion reactor of our planet? According to today's level of knowledge about the structure of the earth the inner core is surrounded by the outer core and that again by the earth's mantle. On top floats the thin, but firm earth's crust, on which we live. The inner core has a radius of nearly 1390 km, the outer core stretches to a radius of 3500 km, whereas the crust is only between 10 and 78 km thick, dependent on the geographical latitude[i4] (fig. 11.4).

<i>: Carey, S. W.: Theories of the Earth and Universe. Stanford University Press: 1-413, Stanford, California

<ii>: Owen, H. G.: Has the Earth increased in size? - In: New Concepts in Global Tectonics, Texas etc. University Press (1992), p. 289-295, Lubbock

<iii>: Hilgenberg, O. C: Vom wachsenden Erdball, Berlin 1933, Eigenverlag, Seite 31 und 32

<i4>: Mitton, S. (Herausg.): Cambridge Enzyklopadie der Astronomie (The Cambridge Encyclopaedia of Astronomy), Orbis Verlag (1989)



Fig. 11.5: The change in the radius of the earth and of the core in the course of millions of years until today.

calculation: (see fig.11.6)

$$\boxed{R^* = 2879{,}5 + 541 \cdot q^{n/3} \text{ [km]}} \quad (11.7)$$

t years ago: with: $\boxed{t = 2 \cdot 10^8 - n \text{ [a]}}$ and: $\boxed{q = 1 + 28 \cdot 10^{-9}}$

correspondents to the approximation:

$$\boxed{R^* = 2880 + (6378 - 2880) \cdot e^{-t/\tau} \text{ [km]}} \quad (11.8)$$

with the time constant: $\tau = 107{,}1$ Mio. Jahre

11.5 Earth's core as a converter of neutrinos

I proceed from the assumption that the conversion of neutrinos and materialization in elementary particles takes place in the inner core. For the conversion no energy at all is used, because the inner energy together with the outer energy of the particle amounts to zero. The neutrinos merely have to be remodelled into another structure and for that they at first have to be slowed down with the help of the oscillating interaction.

During this process of slowing down, as said, no heat is formed because in the case of a mass less particle no energy can be set free in the domain where the classical law of conservation of energy is valid. Only after completion of the process of materialization we are able to detect mass and energy of neutrinos.

But if the oscillating interaction is taken as a basis, the oscillation with opposite phase between particle and earth's core, then contrary to all expectations a cooling down takes place. If the particle has reached its region of destination in the core, then the oscillations are overlapping. Mathematically seen they are added with reversed sign; they thus are subtracted. The result of the mutual compensation is the decrease of the thermal oscillation and the cooling down of the region which was expected.

In addition the formed particles with a mass mutually contract (see part I, chapter 8.3 and 8.4) and in doing so are further cooling down, as we will derive (chapter 12.7 with fig. 12.8). The physical limit of the process of contraction and cooling down is formed by absolute zero, at which no thermal oscillation at all occurs anymore, so that superconduction becomes possible with the result of giant electric currents and magnetic fields, which can be detected even at the earth's surface in damped form, for instance with a compass.

The necessary heat energy is flowing towards the quick-frozen inner core from the outside, principally from the outer core. Here, in the core, from the neutrinos slowed down to the speed of light various elementary particles are formed. Most of them immediately fall apart, to form other configurations. In the end only electrons and protons are preserved, which, as the only stable particles, can't fall apart anymore. These again are trying hard to take the state of an atom, which however needs very much space with the large distance between atomic nucleus and hull. Under the high pressure the enveloping electrons therefore will time and again fall into the nucleus to form neutrons together with the protons.

The neutrons need no atomic hull and can, as is well-known of neutron stars, take an extremely high density. In the case of the earth's core the neutrons however cannot be stabilized. The contraction to a neutron is accompanied by a corresponding drop in pressure, so that the neutron falls apart again. A continual oscillation of size is formed, with which the neutrinos again interact. With that also the high density of the earth's core would be explicable simultaneously.

In earth's outer core the various atoms and isotopes are formed, which in the sum release more energy than they absorb in their fusion processes. Here the fusion oven rages, which supplies the inner core with heat energy.

The formed matter is pushed further to the outside, rolls as a viscous mass through the earth's mantle and collects the surplus radiation and heat from the fusion oven.

With this model of explanation we now can tackle the calculation of the growth of the earth (fig. 11.6).

Growth in volume in analogy to the compound interest calculation:

duration: $n = 200$ million years

starting capital: $V_p =$ Pangaea volume $V_p = (4/3)\cdot\pi\cdot r^3$

final value: $V_h =$ today's volume $V_h = (4/3)\cdot\pi\cdot R^3$

savings bank formula: $V_h = V_p * q^n$ (compound interest) (11.9)

with „interest rate": $q = (V_h/V_p)^{1/n}$ (11.10)

radius of the core of the Pangaea sphere:

$R_p = r - d_m - d_k = 541$ [km] (11.11)

with

Pangaea radius: $r = 3435$ [km]

earth's mantle: $d_m = 2800$ [km]

earth's crust: $dk = 94$ [km] (incl. covering with water).

core radius today: $Rh = R - d_m - d_k = 3500$ [km] (11.12)

earth's crust today: $d_k* =$ 34-78 [km].

From $V \sim r^3$ the growth factor q is calculated to be

$$\underline{\underline{q}} = \left(\frac{V_h}{V_p}\right)^{\frac{1}{n}} = \left(\frac{R_h}{R_p}\right)^{\frac{3}{n}} = \left(\frac{3500 \text{ km}}{541 \text{ km}}\right)^{\left(\frac{3}{2\cdot 10^8}\right)} = \underline{\underline{1 + 28\cdot 10^{-9}}} \quad (11.13)$$

core radius after n years: $R_n = R_p * q^{n/3}$ (11.14)

radius of the earth after n years: $R* = R_n + d_m + d_k*$ (11.15)

Fig. 11.6: The calculation of the growth rate of the earth

11.6 Speed of growth

200 million years ago in the centre of the globe a core of fusion has formed and taken up its operation, probably under the influence of a cosmic occurrence connected with a high neutrino radiation. As a result the thin crust of the earth was torn apart and the oceanic basins were formed.

If we assume that the might of earth's mantle (with d_m = 2800 km) and crust (with less than 100 km) haven't fundamentally changed, then earth's core at that time had a radius of only 541 km. The „savings bank formula" now only may be applied for the core and only for its volume. On the condition of a constant neutrino density the volume of the core in every year will grow for one order of magnitude, which again depends on the respective volume itself. There results the in fig. 11.5 presented course of the radius of the core and of the earth.

According to our calculation the earth at present grows every year for $915*10^{11}$ tons, which corresponds to an increase in volume of 16500 cubic kilometres and an increase of area of 5.2 square kilometres. The earth momentarily grows for 6.5 cm per year in diameter, from which follows that the perimeter increases pi-fold and a continental drift of 10.2 cm per year is to be expected across both the Atlantic Ocean and the Pacific Ocean. Geologists today actually measure a plate movement of typically 10 cm, at individual points of up to 12 cm per year<i>!

Whoever likes to do handicrafts, can build together a globe of shells by himself. Hilgenberg for that gives a handicraft instruction<ii>. He draws the continents of a globe of today and cuts them out. Doing so, not the coast line of today is authoritative, but that of the edge of the shells, at which the mainland plates are breaking off into the deep sea. He hence also speaks of a sphere of shells and helps the handcrafters with the words: ..Because the paper shells of the sphere of shells owing to their strong curvature are difficult to nestle, we cut slits in the paper, which suitably lie there, where mountain ranges stretch and now can start with the gluing". Doing so it shows that the slits in particular in the case of the Ural and the Himalayan gape far apart, that in reversed direction in the case of the enlargement of the sphere of shells the lifting out of the mountains necessarily had to occur at these points by means of upsetting. Under these circumstances our model concept should be further rendered more precisely, If the change of the curvature of the growing surface of the earth is the cause for the lifting out of the mountains, then the surface of the earth 200 million years ago was structured merely by impact craters and by volcanic cones, then the amount of water may have been correspondingly smaller. The additional water of the oceans of today was collected by the earth either from the cosmos, by crossing the flight path of a comet with a water tail, or by the here discussed idea of a core of fusion in the inside of the earth it has produced the water itself!

How ever such detail aspects may have had an effect, it therefore nevertheless changes nothing to the model concept on the whole. Hilgenberg's globe of shells<ii> in my opinion to still makes more sense as all the models of explanation, as they are spread in today's text books.

<i>: Miller, R.: Driftende Kontinente, Time-Life, Amsterdam 1991, S. 78

<ii>: Hilgenberg, O.C.: Vom wachsenden Erdball, Berlin 1933, Eigenverlag



Actual data[i]:

mass of the sun $m_s = 1.99\cdot10^{30}$ [kg]

radius of the sun $r_s = 696\,000$ [km]

distance to the earth $r_e = 149\,597\,870$ [km] (averaged)

mass of the earth $M = 5.976\cdot10^{24}$ [kg]

moment of inertia $\boxed{J_e = M\cdot r_e^2}$ (of the earth orbit) (11.16)

orbital velocity $\boxed{v_e = \omega_e\cdot r_e = 2\pi r_e/t_e}$ (11.17)

averaged[i]: $v_e = 29.79$ [km/s] = constant (11.18)

revolutionary period $\boxed{\begin{array}{l} t_e = 365.25637 \text{ [days]} \\ t_e = \text{sidereal year} \end{array}}$

equatorial radius $R = 6378$ [km]

moment of inertia $\boxed{J = (2/5)\,M\cdot R^2}$ (of the rotation of its own) (11.19)

rotational velocity $\boxed{v_E = \omega_E\cdot R = 2\pi R/t_E}$ = 0.465 [km/s] (11.20)

sidereal time of rotation $\boxed{t_E = 1 \text{ [day]} = 86\,164.1 \text{ [s]}}$

distance to the moon $r_m = 384\,390$ [km] (averaged)

radius of the moon $R_m = 1738$ [km]

mass of the moon $m_m = 7.350\cdot10^{22}$ [kg] = constant (11.21)

moment of inertia $\boxed{J_m = m_m\cdot r_m^2}$ (of the moon orbit) (11.22)

orbital velocity $\boxed{v_m = \omega_m\cdot r_m = 2\pi r_m/t_m}$ (11.23)

of the moon averaged: $v_m = 1.026$ [km/s] = constant (11.24)

revolutionary period $\boxed{\begin{array}{ll} t_m = 1 \text{ sidereal month} & \text{(from fixed star} \\ t_m = 27.322 \text{ [days]} & \text{to fixed star)} \end{array}}$

observed revolutionary period $\boxed{\begin{array}{ll} t^*_m = 1 \text{ synodic month} & \text{(from new moon} \\ t^*_m = 29.53 \text{ [days]} & \text{to new moon)} \end{array}}$

Fig. 11.7: The data of sun, earth and moon of today[i]

[i]: Mitton, S. (Herausg.): Cambridge Enzyklopadie der Astronomie (The Cambridge Encyclopaedia of Astronomy), Orbis Verlag (1989)

It is an exciting matter, if one can experience for oneself, how the pieces of the puzzle fit together, how the southern end of America is wound around the Cape of Good Hope and the Falkland islands surface for the east coast of South Africa, in the vicinity of Australia how the Antarctic occupies the Pacific basin as a neighbour of Australia, von South, Middle and North America, run through by the equator, etc.
The corrections to the view of life of Alfred Wegener and the geographical evidence, which Hilgenberg gives, are sound, well founded and even after 65 years still highly actual. The physical statements of the geologists however, for instance the earth in the course of time would rotate faster and faster, cannot be followed.

11.7 Conservation of angular momentum

The question about the rotation of the earth is raised. Is it not changing at all, is it getting faster or slower? In the case of a with time growing earth there is only one possibility: The rotation of its own will decrease and not increase, as Hilgenberg supposes. For that you only need to place yourself on a turntable, to turn and if possible with weights in your hands stretch out your arms sideways, to feel, how the rotation of the table is decreasing. It surely would have done the geologist Hilgenberg good, to leave his desk for a short time for a stroll to the most nearby playground, for the purpose of the described physical experiment with himself.

In this case the law of conservation of momentum authoritatively has an effect in the formulation of the law of conservation of angular momentum for the rotating motion. According to that all angular momenta in the solar system should amount to zero. If we look at the planets which have no moon, then is remarkable that these need an eternity for a revolution around their own axis (Venus for instance needs 243 days). According to the law of conservation of angular momentum our earth owes its rotation of its own primarily the moon.

For reason of this relation we can assume a proportionality between the angular momentum of the moon J_m*w_m and that of the rotation of its own of the earth J*w_E (eq. 11.39, fig. 11.10). They even have to be identical, if the partner of rotation earth and moon are seen as a closed system.
If the earth would be approached as a homogeneous, spinning sphere, the angular momentum at first would be too small for a factor 4.1 (eq. 11.29, fig. 11.9). The law of conservation of angular momentum dictates as a necessary result, that the dense core of the earth must rotate faster than the earth's crust! From the correspondence of orbital angular momentum of the moon on the one hand and the sum of the angular momenta of their own of earth's mantle and earth's core on the other hand results a 31 fold higher angular velocity of the earth's core compared to the rotation of the earth's surface (eq. 11.38, fig. 11.9).

Does our earth owe its geomagnetism this rotation of the core? At least the possibility exists that there exists a causal relation between the rotation of the earth's core and the geomagnetism. We'll further collect arguments and put the question concerning the formation of the geomagnetism under consideration.



Concerning unipolar induction (Faraday): $\boxed{\mathbf{E} = \mathbf{v} \times \mathbf{B}}$ (11.25)
(see part 1, eq. 58, fig. 6.4)

with $\mathbf{E} = 2$ [V/m] } earth magnetic field $\mathbf{B} = 67$ [µT] calculated
11.18: $\mathbf{v}_e = 29{,}79$ [km/s] } on the average approx. $\mathbf{B} = 50$ [µT] measured<i>

with $\mathbf{B} = 67$ [µT]
eq. 11.20: $\mathbf{v}_E = 465$ [m/s] } 10 km high:
and $h = 6378+10$ [km]

$U = \mathbf{E} \cdot h = \mathbf{v}_E \cdot \mathbf{B} \cdot h$ (11.26)
U = 199 [kV] calculated
U = 200 [kV] measured<i>

Fig. 11.8: The magnetic and the electrostatic field of the earth
as a result of an unipolar induction

<i>: Measurement values in chap. 2.8, e.g. reference entry <i> (Prof. Dr. L. Konig)

11.8 Set of difficulties concerning the change of magnetization

Now investigations of the polarity of the magnetization of rocks have resulted in the fact that in irregular intervals, on an average every 500,000 years, a change of polarity of the geomagnetism has occurred and no one knows why.
If the rotation of the core should produce the magnetism, then it in any case also is responsible for the process of change of magnetization. That purely theoretically is possible in two ways: Either the core tilts out of its plane of rotation for 180° and rotates suddenly in the opposite direction or earth's mantle together with earth's crust, on which we live, is turned upside down.
It surely isn't my intention to produce any panic, but from a physical point of view only the second case is possible. Usually not the tail wags with the dog, but vice versa, the dog with the tail. The high rotational velocity of the earth's core exerts an extremely stabilizing influence. After all its angular momentum is 4.85 times larger than that of the mantle (eq. 11.33, fig. 11.9). Therefore the rotation of the core and the direction of earth's magnetic field always are preserved seen from the sun.

I further proceed from the assumption, that an electrostatic field arises from the sun accompanied by a particle flux, the solar wind, through which the earth flies through in a perpendicular direction. According to the Faraday law of induction E = v x B (eq. 11.25)
it experiences, as a result of the unipolar induction, a magnetic field which stands perpendicular on the ecliptic and thus dictates the orientation of earth's magnetic field. With that also the direction of rotation would be determined. The core thus by no means can tilt!
On the condition that the core doesn't rotate completely frictionless, the earth's mantle will in the case of the same direction of rotation be accelerated, in the case of unequal direction, after a changing of polarity, it will be slowed down again. If the process, for reasons of conservation of angular momentum, takes place alternatingly with a certain regularity, then the inhabitants of the earth for every changing of polarity might experience, how the North Pole in the shortest time turns over the equator to the South Pole, how the sun sets at the point, where it before had risen. As said, after a changing of polarity our earth is standing on its head! In the Bible corresponding clues are found<ii>. It can be taken from the media that one reckons with such a changing of polarity in the foreseeable future. When and if it actually takes place, stands however in the stars.

If magnetism thus is produced by the rotation of the core, or by electric currents in the earth's core as a result of the superconduction or by both, then the earth is aligned in the field of the sun like the magnetic needle in a compass. If we take as a cause a solar wind with an electric field strength of just 2 V/m, then this would not only determine the direction of earth's magnetic field, but also the order of magnitude, and that at present lies at 50 uT averaged over time (chap. 2.8).
With the same mathematical relation an electrostatic field around the earth of 199 V/m results as a result of the rotation of the earth. That fairly exact corresponds to the measured values!<i> Quite obviously all is related to each other. In the question for the „how" at this point consciously no definite answer is strived for. It rather should be discussed and worked to together in the seminar.

<ii>: The Bible, OT, The 2nd book of kings 20,9-11 (king Hezekiah) and Joshua 10,12-14, literally cited on the page after the next page (chap. 11.9), note<ii>

Angular momentum $J_m \cdot \omega_m$ of the orbiting moon (with eq. 11.22 + 11.23):

$$J_m \cdot \omega_m = m_m \cdot r_m^2 \cdot \omega_m = 29 * 10^{33} \ [\mathrm{kgm^2/s}] \qquad (11.27)$$

Angular momentum $J \cdot \omega_E$ of the rotation of the earth (eq. 11.19 + 11.20, same direction of turning):

(theoretically) $J \cdot \omega_E = (2/5)\ M \cdot R^2 \cdot \omega_E = 7 * 10^{33} \ [\mathrm{kgm^2/s}]$ (11.28)

$$\frac{\text{Orbital momentum moon}}{\text{Angular momentum earth}} = \frac{J_m \cdot \omega_m}{J \cdot \omega_E} = \frac{29}{7} = 4{,}1 \qquad (11.29)$$

Angular momentum $J_M \cdot \omega_E$ of earth's mantle and crust (R_h = core radius)

$$J_M \cdot \omega_E = (J - J_K) \cdot \omega_E = (2/5) \cdot (MR^2 - M_K R_h^2) \cdot \omega_E = 6 * 10^{33} \ [\mathrm{kgm^2/s}] \quad (11.30)$$

$$\text{conservation of angular momentum:} \quad J_m \cdot \omega_m = J_K \cdot \omega_K - J_M \cdot \omega_E \qquad (11.31)$$

Angular momentum $J_K \cdot \omega_K$ of the earth's core

$$J_K \cdot \omega_K = J_m \cdot \omega_m + J_M \cdot \omega_E = 35 * 10^{33} \ [\mathrm{kgm^2/s}] \quad (11.32)$$

$$\frac{\text{Angular momentum core}}{\text{Angular momentum mantle}} = \frac{J_K \cdot \omega_K}{J_M \cdot \omega_E} = \frac{35}{5} = 7 \qquad (11.33)$$

$$J_K \cdot \omega_K = (2/5)\ M_K \cdot R_h^2 \cdot \omega_K \quad (11.34)$$

With the mass of earth's core $M_K = \rho_K \cdot V_K = \rho_K \cdot (4/3) \cdot \pi \cdot R_h^3$ (11.35)

and the averaged core density $ro_k = 12000 \ \mathrm{kg/m^3}$

the angular velocity

of earth's core amounts to: $\omega_K = 3{,}3 * 10^3 \ [s^{-1}]$ (11.36)

and that at the earth's surface: $\omega_E = v_E/R = 0{,}073 * 10^{-3} \ [s^{-1}]$. (11.37)

$$\frac{\omega_K}{\omega_E} = \frac{3{,}3}{0{,}073} = 45 \quad (11.38)$$

Fig. 11.9: Calculations concerning the conservation of angular momentum and the rotation of earth's core (One turn of the earth's core lasts 32 min. It results contrary to the earth rotation. Of the surface of the earth a period duration of 31 min should be observable.)

11.9 The weakly damped moon

The increasing angular velocity in the direction of the centre of the earth surely has something to do with the set of difficulties concerning the conservation of the spherical structure, comparable to the reason for the particle spin (chapter 6.13). The increasingly missing radial component of the gravitational field has to be compensated by an additional field produced by the rotation (according to part 1, equation 62, fig. 6.5).

The moon apparently doesn't know this set of difficulties. We can assume a constant mass for it (eq. 11.21). On the one hand is the moon smaller than the earth 200 million years ago, as it started to grow. On the other hand are doubts concerning the existence of an active core of the moon legitimate. In the Apollo-15 mission seismic gauges had been installed at the ground of the moon and at the start from the moon the produced seismic waves had been recorded<i>. The surprisingly small damping as the lunar module fell back onto the ground of the moon more likely allow the conclusion that the moon is hollow inside!
Also the small density of the moon points in the same direction, and finally no clues at all can be seen on the surface of the moon, which would point to a growth of the moon.

Apart from the mass also the orbital velocity of the moon is taken constant, what surely is true, as long as nobody and nothing drives the moon extra (eq. 11.24). The analysis of the law of conservation of angular momentum provides the in fig. 11.10 derived provisional result (eq. 11.41).

<i>: Moonquakes ever more mysteriously: „The by Apollo 12 triggered moonquake by „bombardment" of the surface of the moon with the clapped-out Lunar Module „Intrepid" at thursday evening puts scientists for bigger and bigger mysteries. An exact analysis of the measurement data now resulted in the by the astronauts Conrad and Bean installed „seismic station" on the moon ... to have recorded and to have sent to the earth 55 minutes long. ... The seismologist Dr. Gary Latham spoke of „important information about the structure of the moon" and meant, one now can „throw away the text book". One had reckoned that the impact of the Lunar Module on the moon would trigger a quake of at best some minutes", (translated) Frankfurter Rundschau vom 22.11.1969

---

concerning reference entry <ii>, chap. 11.8:

<ii>: The Bible, OT, Joshua 10,12-14: There stands in the „book of Jasher ": So the sun stood still in the midst of heaven, and hasted not to go down about a whole day. And there was no day like that before it or after it, ...

The 2nd book of kings 20,9-11: king Hezekiah: This sign thou ... let the shadow return backward ten degrees. And Isaiah the prophet cried unto the LORD: and he brought the shadow ten degrees backward, by which it had gone down in the dial of Ahaz.



For the proportionality of the angular momenta of the earth:

$$J \cdot \omega_E \sim J_M \cdot \omega_E \sim J_K \cdot \omega_K$$

With: $$J \cdot \omega_E = (2/5)\, M \cdot R^2 \cdot 2\pi / t_E \qquad (11.28)$$

and the orbital momentum of the moon:

$$J_m \cdot \omega_m = m_m \cdot r_m^2 \cdot v_m / r_m \qquad (11.27)$$

is valid the

$$\boxed{\text{conservation of angular momentum:} \quad J \cdot \omega_E \sim J_m \cdot \omega_m \qquad (11.39)}$$

or: $$M \cdot R^2 / t_E \sim m_m \cdot r_m \cdot v_m \qquad (11.40)$$

with m_m = constant (11.21)
and v_m = constant (11.24): $\boxed{M \cdot R^2 \sim t_E \cdot r_m}$ (11.41)

centrifugal force = gravitational force

$$\boxed{\frac{m_m \cdot v_m^2}{r_m} = \frac{G \cdot M \cdot m_m}{r_m^2}} \qquad (11.42)$$

or with eq. 11.22: $$v_m^2 = G \cdot M / r_m = (2\pi r_m / t_m)^2 \qquad (11.43)$$

if M = constant: $\boxed{r_m^3 \sim t_m^2}$ (10.1)

Kepler's 3rd law.

Here M ≠ constant, instead v_m = constant (11.23) and therefore follows from eq. 11.43:

(month) $\boxed{t_m \sim r_m \sim M}$ (11.44)

with eq. 11.41:

(day) $\boxed{t_E \sim R^2}$ (11.45)

and for an analogous derivation: (year) $\boxed{t_e \sim r_e \sim m_s}$ (11.46)
with v_e = constant

Fig. 11.10: Calculation of dynamic celestial mechanics

11.10 Calculation of celestial mechanics

We still need a further relation and try the balance of forces between the centrifugal force and the gravitational force. Both the to the outside directed centrifugal force and the to the inside directed gravitational force depend on the mass of the moving body, here the mass of the moon m_m, so that it is cancelled from equation 11.42.
As determining mass only that of the earth is left and that is taken constant in accordance with the knowledge of text books. The result of this assumption is Kepler's 3rd law (eq. 10.1). But beware, it here merely concerns a momentary picture! In the course of time, according to the derivation, the mass of the earth increases so that this assumption is untenable.

Instead, as already said, the average orbital velocity of the moon, one kilometre per second, can be taken constant (eq. 11.24). Since the orbital velocity is calculated from the proportion of the perimeter of the circular orbit $2\cdot\pi\cdot r_m$ with regard to the revolutionary
period of a month (11.43, left page), and at the same time from the balance of forces a dependency of the mass of the earth M and the radius of the orbit of the moon follows (11.43, right page), the interesting relation (11.44) results:
Here the mass M, the radius r_m and the revolutionary period t_m stand in a direct proportionality to each other, and that means: if the mass of the earth increases in the course of time, then the moon will go away from us to the same extent, then also every month will get correspondingly longer.

Clarified with numeric values follows from a growth of the earth for $915*10^{14}$ kg per year a going away of the moon for yearly 5.88 meters (fig. 11.11). The going away of our satellite could be confirmed by means of measurements with laser reflectors, which had been put up on the moon by Apollo astronauts, according to dpa message<i>.

In addition every month lengthens for 3 milli seconds. That is valid for the sidereal month (= 27.322 days), for which a fixed star serves as a reference point for the measurement of a revolution, as well as for the synodic month, as it is observed from the earth from new moon till new moon (= 29.53 days). The synodic month today is longer than four weeks. But 3.7 million years ago it once actually lasted exactly 28 days, as we can calculate easily (fig. 11.11).

But now also the length of a day is changing. If we insert the proportionality (11.44) from the balance of forces in that of the conservation of angular momentum (11.41), then it is shown that a day depends quadratic on the radius of the earth (11.45), that a lengthening of every day for $4.5*10^{-9}$ s can be determined with the help of the growth curve of the earth (fig. 11.5). This is really very small, but 200 million years ago the day had just 19 hours, if extrapolated to 900 million years only 18.04 hours! The result of the american geologists around Dr. Charles Philip Sonett of the University of Arizona in Tucson also is 18 hours in their analysis of correspondingly old sediment formations, as the US science magazine Science has reported<i>. The correspondence of this measurement with our calculation without doubt has force of evidence!

<i>: 900 million years ago a day had 18 hours, Washington (dpa) 1997



Going away of the moon per year with $\boxed{M \sim r_m}$ (according to eq. 11.44): for

$\Delta r_m = r_m \cdot \Delta M/M = 384390[km] \cdot 9.15 \cdot 10^{16}[kg/a] \,/\, 5.976 \cdot 10^{24}[kg] = \underline{5.886\ [m/a]}$

lengthening of month per year with $\boxed{M \sim t_m}$ (11.44) (sidereal): for

$\Delta t_m = t_m \cdot \Delta M/M = 27.322\ [days] \cdot 86164\ [s/day] \cdot \Delta M/M = \underline{36\ [ms/a]}$

synodic month (from new moon till new moon) of 28 days:

$\Delta t_m = 29.53\ [days] - 28\ [days] = 1.53\ [days] \equiv 132 \cdot 10^6\ [ms]$

linearly calculated $132 \cdot 10^6\ [ms]/36\ [ms/a] = \underline{3.6674\ \text{mio. years ago}}$.

Day length 200 mio. years ago, with $\boxed{t_E \sim R^2}$ (11.45) amounted to t* hours

shortening: $\Delta t_E/t_E = \Delta R^2/R^2 = (R-R^*)^2/R^2 = (6378-3420)^2/6378^2 = 21.5\%$

$\Delta t_E = 0.215 \cdot 24\ [h] = 5.16\ [h]$ and $t^* = 24\ [h] - \Delta t_E = \underline{18.84\ [h]}$

Day length 900 mio. years ago, (R^*=3200 km) amounts to 18.04 hours

present lengthening per day amounts to: $\Delta t_E/t_E = 4.5 \cdot 10^{-9}\ [s/day]$

but: the year increases 130,000 times faster than the individual day!

according to the measurement of Aristarchos 2300 years[ii] ago

is $\Delta t_e = 365.25637\ [days] - 365.25062\ [days] = 0.00575\ [days]$

and $\Delta t_e/t_e = 0.00575 \cdot 24 \cdot 60 \cdot 60 \cdot 1000 \,/\, 365.25637 \cdot 2300 = \underline{0.59\ [ms/day]}$

going away of the earth from the sun per year, with $\boxed{t_e \sim r_e}$ (acc. to eq. 11.46)

for: $\Delta r_e/t = r_e \cdot \Delta t_e/t_e \cdot t = 149.6 \cdot 10^6\ [km] \cdot \Delta t_e/t_e \cdot t = \underline{1.024\ [km/a]}$

growth of the sun per year/second, with $\boxed{t_e \sim m_s}$ (according to eq. 11.46)

for:

$\Delta m_s/t = m_s \cdot \Delta t_e/t_e \cdot t = 1{,}99 \cdot 10^{27}\ t \cdot \Delta t_e/t_e \cdot t = \underline{1.36 \cdot 10^{19}\ [t/year]}$

resp. in a second for: $= \underline{4.3 \cdot 10^{11}\ [t/s]}$

and at the same time a loss due to radiation of: $\underline{5 \cdot 10^6\ [t/s]}$

Fig. 11.11: Figures according to analysis of some examples concerning dynamic celestial mechanics

11.11 The biblical age

We therefore owe the growing diameter of the earth that every day gets longer and longer (eq. 11.45) and from the going away of the moon a lengthening of the month results (eq. 11.44). Not only the months and the length of the days increase, but also the whole year. A corresponding derivation for the revolution of the earth around the sun, as it has been carried out for the revolution of the moon around the earth (eq. 11.44), delivers analogous results (eq. 11.46): The sun determines the length of the year and the distances to the planets. To the extent, to which the sun grows, the solar system increases in extension. Also the distance to the earth increases proportionally with the mass of the sun. By the going away from the sun the temperature on the planets however not necessarily decreases, because at the same time the radiation intensity of the growing central star increases. According to measurements it has increased for 30% since the formation of the solar system<i>.

If both the rotation of the earth and the revolution around the sun get slower, then by all means is conceivable, that the number of days per year approximately stays the same and mankind nevertheless gets less old. If we take the 2300 years old writing of the Greek Aristarchos about the sizes and distances of the sun and the moon<ii>. He determined, assuming a heliocentric view of life, the year to be 365.25062 days. Because the correction taken by Aristarchos concerned even the fifth place after the comma, we must assume that correspondingly precise gauges were available in Alexandria already 310 BC.
The today measured sidereal year with 365.25637 days has lengthened for whole 0.00575 days. From this follows that the year increases considerably faster than the individual day.
It of course would be nice, if we could calculate the lengthening of the year, but unfortunately no data about the growth of the sun are available.
If we proceed from the measurement of Aristarchos, without being able to verify or reproduce its reliability, then from that would result a going away of the earth from the sun for yearly one kilometre, then the sun should grow for $4.3*10^{11}$ tons per second. In any case the sun materializes mass considerably faster, as it loses mass in the same period as radiation equivalent, and that surely is correct (fig. 11.11). Today one generally assumes that „since its formation the earth has gone away from the sun for in total 30,000 km"<i>.

But if in the past the year consisted of less days and every day moreover was shorter, if therefore the biological life time was divided in shorter periods, then mankind could get older, then obtaining a biblical age possibly by no means was unrealistic. If Adam still should have got 930 years old, according to the 1st book of Moses, then his lifetime already must have been quite long ago. While Abraham still did get 175 years old, no successor of him has reached his age anymore. In the Bible it is said: „And the LORD said, My spirit shall not always strive with man, for that he also is flesh: yet his days shall he an hundred and twenty years "<iii>. Today even the limit given by the LORD isn't reached anymore!

<i>: Is the sun loosing her Gravitation? Illustrierte Wissenschaft, Nr.l, 1995
<ii>: Hermann Wild: Technologien von gestern, Chancen fur morgen,
Jupiter-Verlag Bern (1996), ISBN 3-906571-13-0, Seite 22
<iii>: The Bible, King James Version, Genesis 6.3

The balance of forces (equation 11.42 generalized):

$$\boxed{\begin{array}{ccc}\text{centrifugal force} & = & \text{gravitational force}\\ \dfrac{M\cdot v_k^2}{r} & = & \dfrac{G\cdot M\cdot m}{r^2}\end{array}} \qquad (12.1)$$

results in the cosmic velocity v_k:

$$\boxed{v_k^2 \quad = \quad G\cdot m/r} \qquad (12.2)$$

independent of the mass M of the satellite or planet!

For	$v<v_k$	falling back into the central mass m
For	$v>v_k$	taking the leave into space
For	$v=v_k$	stationary orbit

written down for the nth planet in the solar system:

with $r(n) = r_n$ average orbital radius of the planet

and $v(n) = v_n$ average orbital velocity

as well as: m_s mass of the sun

$$\boxed{v_n \quad = \quad \sqrt{G\cdot m_s/r_n}} \qquad (12.3)$$

or:

$$\boxed{v_n \quad = \quad G\cdot m_s/v_n\cdot r_n} \qquad (12.4)$$

Fig. 12.1: The first cosmic velocity v_k

12. New cosmology

Astronomy still hasn't satisfactorily solved the question of the formation of the solar system. It thereby however concerns a central problem, because it includes the origin of the earth. But as long as we not yet have understood the relations in our nearest environment, the processes, which we observe with giant telescopes in the depths of pace, will remain a book with seven seals, will lose models of explanation concerning the Big Bang and concerning the so-called unavoidable heat exitus every reliability.

12.1 Concerning the formation of our solar system

2-8-1972 the observatories of the sun reported an unusual high solar activity and 6 days later a slowing down of the rotation of the earth occurred, which was recorded as the lengthening of a day for more than 10 milliseconds. This effect hardly can be explained by the tidal friction alone already just concerning the energy balance. Instead this observation makes clear two things to mankind. On the one hand, how much our earth depends on the solar processes and on the other hand, that the changes by all means can occur not continuously, but periodically and if need be even sporadic.

If, as a result of the conservation of angular momentum, the sun determines the orbital velocity of the earth, if it dictates the rotation of the earth by its neutrino activity and the growth of the earth and if the earth in the same manner determines the orbit of the moon, then it would be obvious that the moon originally has been a part of the earth and this in turn sometime a part of the sun. As it came off, the necessary angular momentum then has been passed on proportionately to the celestial companions, with which the cause for evolution and rotation of their own would be clarified. In addition the moon goes away from the earth and the earth again from the sun, so that looking back it by all means would be obvious, if they once had belonged together.

If we assume that cosmic dust particles meet and accumulate, then all collected rubble contributes to the rotation of its own of the forming celestial body. The more matter finds together, the larger its force of attraction gets, the faster it will grow like a celestial vacuum cleaner. In the course of time this process however is slowed down again and eventually comes to a standstill, because as matter condenses, volume and spherical radius decrease and the rotation of its own increases to the corresponding extent. The celestial body rotates faster and faster and reaches at its surface the cosmic velocity vk, which is given by the mass m and the radius r of the star (eq. 12.2). Now the centrifugal force has reached an order of magnitude, for which the celestial body hurls exactly as much matter into space, as it on the other hand collects by its gravitational effect.

Our sun was lucky to have been supplied with neutrinos in the range of influence of our galaxy. It went in resonance and started to grow, this time from out of the inside. It however could not yet shine, because a crust had formed on its surface around its core of fusion and its mantle, a crust on which permanently was falling cosmic matter from the outside. The increasing viscosity of the sun becoming compressed caused a slowing down of the core of the sun and the corresponding acceleration of the mantle and crust.



Titius-Bode law of 1766:

$$a = 0{,}4 + 0{,}3 \cdot 2^{v} \qquad (12.5)$$

in astronomical units a with:

$$r_n = a \cdot r_e \qquad (12.6)$$

(r_e = 149 598 000 [km] average orbital radius of the earth)

Planet	orbital radius acc. to the law:		measurement value.
Mercury:	$v = -\infty$	$a = 0{,}4$	0,39 (measured)
Venus:	$v = 0$	$a = 0{,}7$	0,72 (measured)
Earth:	$v = 1$	$a = 1$	1 (by definition)
Mars:	$v = 2$	$a = 1{,}6$	1,52 (measured)
Asteroids:	$v = 3$	$a = 2{,}8$	-
Jupiter:	$v = 4$	$a = 5{,}2$	5,2 (measured)
Saturn:	$v = 5$	$a = 10$	9,54 (measured)
Uranus:	$v = 6$	$a = 19{,}6$	19,2 (measured)
Neptune:	$v = 7$	$a = 38{,}8$	30,1 (measured)
Pluto:	$v = 8$	$a = 77{,}2$	39,4 (measured)
circumsolar cloud of planets:	$v = 9$	$a = 154$	-
etc. ... :	$v = 10$	$a = 308$	-

Table 12.2: The Titius-Bode series of the planets (the theoretical values compared to the measurement values)

Sometime our like mad spinning sun had increased that much, that the crust came off like the „tread of an old car tyre" and was catapulted into space. The repulsion was achieved by the centrifugal force exceeding the gravitation for the force of cohesion, which at the moment of the separation of crust regions suddenly tears off. Like snowballs the planets lulled off the sun's surface in this process and were hurled away. Their velocity of rotation at this time was identical to the cosmic velocity of the sun v_k and with that for many a planet large enough to produce its own satellites out of its own surface, which perhaps was not yet completely ideally spherical.

With every planet, which the sun gave birth to, it gave away a part of its own angular momentum to its child as orbital momentum. Only from this time on the sun reduced its angular velocity steadily until this very day. By losing the crust it also started to shine openly. Thus at least could our solar system have been formed.

12.2 The birth of the planets

From this observation various consequences result. If stars are observed, which are rotating very fast, then they either are very young, or they have no planets. Stars, which compared to our sun are rotating less fast, have given away the angular momentum to their planets and such, which hardly are rotating, have their planets already sent away into space. But if the last planet leaves its solar system and the sun stops to rotate, then the sun, which meanwhile has grown to a red giant, without a, the spherical form stabilizing centrifugal force, will collapse. The supernova is the death of a star and thereby neutrinos are set free, the material for new life.

After the coming off of the planets these first clear free their flight paths, by together with the sun collecting the flying around matter. Even whole planets thus can collide, are slowed down and form bigger units. Finally only some few planets in very particular orbits are left. Their average distance to the sun obeys in an until now completely inexplicable manner the Titius-Bode series (equation 12.5, table 12.2).
In the case of the by the german scientist Titius 1766 formulated regularity it concerns a rule of thumb founded purely on experience. But it is remarkable, that the planet Uranus could be predicted (Bode 1772) and after systematic searching also be found (Herschel 1781) with it.

The most distant planets Neptune and Pluto however don't obey the law. Their distance should be very much larger. But this circumstance we already had given reasons for with the fact, that for them the resonating interaction already overlaps and exceeds the gravitation in its effect (chap. 10.1 note<ii> and chap. 10.5).

The arbitrary seeming series of numbers 0, 3, 6, 12, 24, 48, 96, 192, 384, ... with a respective doubling of the value, starting with the 3, the addition of 4 and the following division by 10 at first are nothing but pure acrobatics of numbers, which now really has nothing to do with physics (table 12.2). A physical background can be supposed however because of the tried and tested applicability and that should be fathomed.



Orbital angular momenta $J\cdot\omega$ of the n^{th} planet
with: $J = m\cdot r_n^2$ and $\omega = v_n/r_n$: $\boxed{J\cdot\omega = m\cdot r_n\cdot v_n}$ (12.7)

By using	equation 12.3:	equation 12.4:	
amounts the orbital angular momentum to: $J\cdot\omega$	$= m\cdot\sqrt{G\cdot m_s\cdot r_n}$	$= G\cdot m\cdot m_s/v_n$	(12.8)
dependent	on r_n	on v_n	
change of the angular momentum (1^{st} derivation) with the ordinal number n			
$\frac{d(J\cdot\omega)}{dn}$	$= m\cdot\sqrt{G\cdot m_s}\,\frac{d(\sqrt{r_n})}{dn}$	$= G\cdot m\cdot m_s\,\frac{d(v_n^{-1})}{dn}$	(12.9)
$\frac{d(J\cdot\omega)}{dn}$	$= \frac{m\cdot\sqrt{G\cdot m_s}}{2\cdot\sqrt{r_n}}\cdot\frac{dr_n}{dn}$	$= -\frac{G\cdot m\cdot m_s}{v_n^2}\cdot\frac{dv_n}{dn}$	(12.10)
with eq. 12.8: $\frac{d(J\cdot\omega)}{dn}$	$= \frac{J\cdot\omega}{2\cdot r_n}\cdot\frac{dr_n}{dn}$	$= -\frac{J\cdot\omega}{v_n}\cdot\frac{dv_n}{dn}$	(12.11)
By comparison of the left and the right solution (of eq. 12.11), after introduction of the constant: $\frac{1}{N}$	$= \frac{1}{r_n}\cdot\frac{dr_n}{dn}$	$= -\frac{2}{v_n}\cdot\frac{dv_n}{dn}$	(12.12)
the differential equations read:	$\boxed{\frac{r_n}{N} = \frac{dr_n}{dn}}$	$\boxed{\frac{v_n}{2\cdot N} = -\frac{dv_n}{dn}}$	(12.13)
and the general solutions:	$r(n) = r_n = r_o\cdot e^{\lambda\cdot n}$	$v(n) = v_n = v_o\cdot e^{\lambda\cdot n}$.	(12.14)
The 1^{st} derivation:	$\frac{dr_n}{dn} = r_o\cdot\lambda\cdot e^{\lambda\cdot n}$	$\frac{dv_n}{dn} = v_o\cdot\lambda\cdot e^{\lambda\cdot n}$	(12.15)
and the comparison with eq. 12.13 and eq. 12.14:	$\frac{dr_n}{dn} = \frac{r_o}{N}e^{\lambda\cdot n}$	$\frac{dv_n}{dn} = \frac{-v_o}{2N}e^{\lambda\cdot n}$	(12.16)
determine the coefficient λ:	$\lambda = 1/N$	$\lambda = -1/2N$.	(12.17)
The result is for a planet in the n^{th} orbit:	for the average orbital radius $r(n) = r_n$ $r(n) = r_o\cdot e^{n/N}$ (12.18)	for the average orbital velocity $v(n) = v_n$ $v(n) = v_o\cdot e^{-n/2N}$ (12.19)	

Fig. 12.3: Calculation of the distances and orbital velocities of the planets

12.3 The derivation of the Titius-Bode law

Even if Bohr's atomic model should be wrong, it gladly is compared to the system of the planets. The radii of the electron orbits mathematically result as eigenvalue solutions of the Schrodinger equation, and that we have derived from the fundamental field equation (chap. 5.1, eq. 15) (chap. 5.5 - 5.9). The orbital radii are calculated in increasing order in accordance with the sequence of whole numbers with n = 1, 2, 3, 4, ...

From the same sequential regularity of the planetary orbits can be derived, that they also obey the eigenvalues of the same fundamental field equation, which isn't called a world equation in vain. The quantitative distances from the sun are determined by the size of the sun: if the sun increases, then also all distances increase to the same extent.

Now result identical distances between the orbits from Bohr's model, whereas this distance in the case of the planets with increasing distance from the sun gets larger. The reason for this unevenly grading can be calculated just like that (fig. 12.3).

We arbitrarily pick a planet, which occupies the orbit n, where n again represents the sequence of whole numbers (n = 0, 1, 2, 3, ...). If the orbit of this n^{th} planet changes, then also its distance to the sun $r_n = r(n)$, its orbital velocity $v_n = v(n)$ and the orbital momentum $J \cdot \omega$ (12.7) are changed.
We try (as in equation 11.42, fig. 11.10) the balance of forces between centrifugal force and gravitational force (eq. 12.1, fig. 12.1) and solve equation 12.2 for the orbital velocity. The orbital angular momentum of the planet written down once in its dependency on r_n and in the right column next to it on v_n (eq. 12.8, fig. 12.3), is derived for the orbital ordinal number n, to record the change in angular momentum (equations 12.9 to 12.11).

In fig. 12.3 the paths to the solution for both cases are given. For the average orbital radius r(n) as well as for the average orbital velocity v(n) of the planet an exponential course (eq. 12.18 and 12.19) and in logarithmic representation a straight line (fig. 12.4) results.

Even the orbits of the distant planets Neptune and Pluto, for which the Titius-Bode series fails, now are correctly recorded, so that with good cause can be claimed, to correctly have derived the regularity of the distances of the planets physically and mathematically.



Fig. 12.4: Representation of the distances of the planets

result of the calculation: $\boxed{r(n) = 0{,}3332 \cdot e^{\left(\frac{n}{1{,}82}\right)} \quad [AE]}$ (12.20)

12.4 The hollow planet

The numerous accompanying moons of the big planets obey in the same manner as the planets this regularity, so that for the found result every coincidence is excluded. The orbits of the moons of Jupiter (fig. 12.5), of the moons of Saturn (fig. 12.6) and of the moons of Uranus (fig. 12.7) in logarithmic representation lie almost on a straight line. Some orbits certainly are occupied several times, while many an orbit has remained unoccupied. Other orbits again are occupied by a ring of countless chunks of rock, so-called planetoids. Best known representative is the asteroid belt (n = 4) between the orbit of Mars (n = 3) and that of Jupiter (n = 5). The Titius law requested the planet "Aster", but what one found (Piazzi, 1801), at first only was Ceres, the biggest representative of the small planets.

As a second asteroid, as they are called, was found (Olbers 1802) its discoverer proposed the explanation that both, Ceres and Pallas, could have formed in a cosmic catastrophe, which a bigger celestial body had suffered.

Perhaps the sought-for planet Aster actually had imploded after a collision and had been torn apart in countless fragments, of which today still more than half a million pieces are flying around. Most of the fragments however have been collected by the neighbouring planets Jupiter and Mars. Also in the case of the moons of Mars and the outer moons of Jupiter it could concern scrap of Aster. Some presumably fell on the young earth and triggered natural disasters and left deep scars.

It can be imagined that the planet Aster was hollow from the inside and thus was built up similar to the moon. Such a hollow sphere could have formed, if the sun, or in the case of the moon, the earth still was rotating with the cosmic velocity and as a result of the centrifugal force at the perimeter parts of the crust came off as connected sheets and rolled up to a tube.

The fast spinning tube then remodels into a hollow sphere with openings at the poles. In the inside of the sphere, near the equator, protected conditions and the best prerequisites for an undisturbed development, for instance of intelligent living beings, are found by the way. Apart from the advantages the hollow sphere however has as a fundamental disadvantage, that the normally protecting shell in the case of a collision with a bigger celestial body can becomes instable and can implode.

In the case of the moon the pole openings in the meantime are closed and a presumed gas pressure in the inside in addition provides stability. The wall of the spherical shell however is not evenly thick, so that the moon all the time turns the same, namely the heavier, side towards the earth. In view of the seismic measurements of the Apollo-missions, which revealed an extremely small damping of the ground of the moon (chap. 11.9, note <i>), we should look after our moon well, because a comet, which lets the moon implode, would be able to bring about more damage on earth, than if it would hit the earth directly.

Should there exist a hollow and possibly even on the inside habitable planet in our solar system, then surely Saturn should be considered. Its density is smaller than that of water, so that water would be distributed over the inside area of the hollow sphere, if it would be existent. One should examine more detailed the extremely flat pole regions of Saturn for possible openings! Also Uranus and Neptune are possible candidates. This only is thought as an idea.



in position n = 9 stand: Leda, Himalia, Lysithea and Elara
in position n = 10 stand: Ananke, Carme, Pasiphae and Sinope

Fig. 12.5: The distances of the moons of Jupiter

Result of the calculation: $$r(n) = 67608 \cdot e^{\left(\frac{n}{1{,}743}\right)} \quad [\text{km}] \tag{12.21}$$

<i>: Note to chapter 12.5:

What we observe as and call cosmos, is nothing but a structured state of space.

12.5 Concerning the formation of the universe

The widespread concept of an expanding universe bases on the observation of a red shift of the spectral lines of galaxies, which increases with their distance. As the physical explanation for the discovery of Hubble, the Doppler shift for a light source, which is moving away from us, is used. But this concept of an against the attraction of the gravitation taking place expansion is nothing more than a work hypothesis.

The by Christian Doppler in acoustics investigated effect treats the observable shift in frequency, if the source of sound or the receiver is moved with regard to the medium of propagation. But according to today's version there doesn't exist such a medium at all for light, because Einstein has abolished the concept of the aether. According to that the Doppler effect neither can be applied to changes in light frequency. In the case of the expanding universe, for a decrease of the density and the tracing back to a Big Bang, it therefore should concern a misinterpretation!

Here another effect has to take effect, which one is not yet clarified. Perhaps the changing field relations of the observer environment play a role, after the earth moves away from the sun. But perhaps the galaxies only influence the propagation of their own light, or the light ray on its millions of years lasting way through space slightly loses energy, what is expressed by gradually increasing its wavelength and shifting its spectrum towards the red frequencies.
The hypothesis of the Big Bang moreover contradicts every causality. It is not able to give an answer concerning the origin and the future of the universe and on the question of the origin of the energy and the particles. With that its physical value of explanation goes towards zero.

If we again hold the theory of objectivity against the theory of relativity (part 1), we come to quite other answers. Here apart from the waves also vortices are found. Specially in the case of the spherical vortex a part of the wave power is enclosed in the inside, so that looked at from the outside a from zero differing energetic state results, which even is accessible measuring technically (chapter 6.2).
Wave and vortex are two possible forms of state, so that for the conversion of one state in the other state at first no energy is necessary. The change of state depends on the local field relations.
If we assume that in the beginning the cosmos was free of energy and particles. Then the first vortex was a possible product of chance with an infinite extension. This first spherical vortex, which was contracted under the potential vortex pressure, gave structure to space, gave it energy and field and took care for the rolling up and formation of new vortices[i].
It can be assumed, that even today new particles continually are being formed in the fringe areas of the infinitely extended cosmos, which fly towards us and in doing so contract. They are attracted and at the same time shrunk by the fields of the celestial bodies. They form the source of all matter and energy for our observable universe, which permanently is changing its structure. Because the same oscillation with reversed sign is enclosed in the inside of the spherical vortex, the sum of the energy present in the cosmos is exactly equal to zero. With that the question concerning the causality is superfluous.



Fig. 12.6: The distances of the moons of Saturn

Note to chapter 12.6 (2nd law of thermodynamics<i>):

Heat cannot completely be transformed into mechanic or electric energy.

<i>: see Electromagnetic environmental compatibility, Part 1, fig. 8.4

The formation of the universe also can be explained causal and completely without a hot Big Bang, even if a supernova surely represents something like a "local Big Bang" for the concerned celestial bodies. According to the observations of the sky expansion and contraction, explosion and implosion occur everywhere in form of oscillations.

On the whole the expanding universe, which once was in thermodynamic equilibrium with matter, should cool down further and further. But stop, the 2nd law of thermodynamics teaches one just the opposite. If the entropy only increases, as the law dictates, then the whole universe should end in a heat death, just as mysteriously and inexplicable, as it should have been formed with the Big Bang. Perhaps something is wrong with the law (fig. 8.4)?

12.6 Counter examples concerning the 2nd law of thermodynamics

Most likely a small experiment convinces us. We heat two spheres, one somewhat less, the other somewhat more. Then we focus the heat radiation of the less hot sphere with help of a parabolic mirror and point it to the hotter one of both. That as a result becomes hotter, whereas the colder is cooled down. The heat thus has flown from the colder to the hotter sphere. Is it allowed to do that?
According to the 2nd law of thermodynamics it of course isn't. There the heat always can only flow from the hot to the cold sphere. But in this primitive experiment it measurable and verifiable flows in the wrong direction. Here the entropy, which is said to always only increase, actually decreases. Here entropy is being destroyed!
Shall we now let the carrying out of the experiment be forbidden under threat of penalty or shall we secretly put the law of entropy to sleep? It can't be denied that this law until now has quite well helped us along, at least for terrestrial processes, at least if one dispenses with the poor inventors, whose inventions offend against the since 100 years tried and tested 2nd law of thermodynamics. They haven't really arrived at the patent office at all, then they already are outside at the door again. Such inventors with their illegal behaviour even today must feel like criminals.

Just what that observed experiment can, each refrigerator and each warmth pump is using as well. And it is not an isolated case: also our sun clearly functions and operates illegally! The surface temperature amounts to only 5800 degrees Kelvin and supplies the atmosphere of the sun with energy. The energy thus flows from the sun to the corona, and that is with values above 1,000,000 degrees Kelvin for some powers of ten hotter!

Only the vortex concept resolves the many question marks without compulsion. In the case of the sun certainly vortices are at work. Here the high temperature in the corona arises as a result of vortices falling apart. We also speak of eddy losses. The transport takes place by heat radiation, exactly as in the experiment with the two spheres.
The possibility exists therefore in vortex processes as well as in technical circle processes that heat could flow from the colder to the hotter sphere. Whether this is an offence against the 2nd law of thermodynamics, is in the end a question of interpretation of the law and up to the opinions of the scholars.



Fig. 12.7: The distances of the moons of Uranus

Note to chapter 12.7 (law of entropy):

The entropy of a closed system never can decrease. It is increased in the case of all irreversible processes. In the case of reversible processes it remains constant.

12.7 Entropy destroying potential vortices

Vortices in addition can amalgamate to balls and to planar vortex systems (4.9 and 4.10). In that case similar consequences, as they can be observed in flow-technical potential vortices in hydrodynamics, can be expected. As a result of the concentration effect (4.1) and because of the conservation of angular momentum an increase of the velocity of rotation of the vortex occurs. Like in the case of the pirouette in figure skating a spontaneous acceleration of its own is observed. In that way the kinetic energy of the system is increased, and that has to come from somewhere.
If we don't supply the contracting vortex with any additional energy for the increase of its rotation of its own, then as a source of energy only the heat energy is left. For this reason every contracting vortex generally converts heat in kinetic energy, it therefore cools down its environment! It moreover destroys entropy and offends against the 2nd law of thermodynamics (fig. 12.8).

It isn't an accident, if in the inside of a tornado it starts to hail. The whirlwinds really furnish visual instruction of the contraction and acceleration of their own of ring-like vortices. If then, even in tropical regions, hail stones are formed, the cooling effect has to come from somewhere, and it can be assumed that the vortex withdraws the heat energy from its environment (calculation in fig. 12.8).

If in specialist books is talked about matter or stars condensing, then vortex physics teaches us that they in reality are contracting and by doing that cooling down. That also is valid for whole galaxies. We owe solely the vortex laws that the continual heating by absorption of radiation is prevented and our sky in the night is dark and doesn't shine as light as day.

The cosmic background radiation, which as a result of vortices lies at almost 3° Kelvin, actually can only be given account for with a contracting of vortices of the Milky Way galaxy. If the cooling down in a compression resp. condensation process has arrived at absolute zero, the vortex becomes stationary, the contraction becomes dependent on the irradiated energy or it wholly comes to a standstill without supply of energy. An example for that is earth's inner core, which at zero Kelvin can't contract further.

From the point of view of causality it is suggested that we galactic and perhaps even cosmic to a large extent are in thermodynamic equilibrium, completely without Big Bang and heat death<i>.

Numerous inventions, as mentioned, are based on the principle of converting environmental heat in useable energy by contraction of vortices. If however the inventors don't know the vortex laws and if they have developed their concept empirically and less physically, then it very often happens that erroneously gravity is made responsible, then is talked of gravitational converters, of the use of a gravitational field energy. But the inventors don't do themselves a favour with that.

<i>: In the seminar it is desired to think about this. Doing so the philosophical faculty may feel as well addressed, as the sandpit of physics, in which completely unsuspecting is played and juggled with Big Bang hypotheses by ignoring all physical regularities and every common sense.



Evidence to counter:
planar, contracting ring-like vortex

conservation of angular momentum: $\boxed{J \cdot \omega = m \cdot r \cdot v = \text{constant}}$ (12.7)

conservation of energy: $E_{kin} = ½\, m \cdot v^2 = \text{constant}$ (12.22)

before (r_1, v_1) | afterwards (r_2, v_2)

contracted $(r_2 < r_1)$: $m \cdot r_1 \cdot v_1 = m \cdot r_2 \cdot v_2$ (12.7*)

with the consequences: $v_2/v_1 = r_1/r_2$ (12.23)

and:

kinetic energy: $E_{kin1} = \frac{1}{2} \cdot m \cdot v_1^2 \neq E_{kin2} = \frac{1}{2} \cdot m \cdot v_2^2$ (12.24)

increase of the kinetic energy:
$$\boxed{\frac{Q_2}{Q_1} = \frac{E_{kin2}}{E_{kin1}} = \frac{v_2^2}{v_1^2} = \frac{r_1^2}{r_2^2}} \qquad (12.25)$$

notice: *Because of the change in energy/heat* ***no adiabatic change of state!***

change of volume:
with $V = \pi \cdot r^2 \cdot h$
$$\boxed{\frac{V_1}{V_2} = \frac{r_1^2}{r_2^2}} \qquad (12.26)$$

notice: *Because of the change of volume* ***no isochore change of state!***

assumption: ***isobar change of state*** *(with $p = const.$, Gay-Lussac):*

result:
(vortices of gas)
$$\boxed{\frac{T_1}{T_2} = \frac{V_1}{V_2} = \frac{v_2^2}{v_1^2} = \frac{r_1^2}{r_2^2}} \qquad (12.27)$$

involved with the:

* ***acceleration*** $v_2 > v_1$ *is the contraction of vortices* $r_2 < r_1$, $V_2 < V_1$

* ***the cooling***: $T_2 < T_1$ and $\Delta T = T_1 - T_2 = T_2 \cdot \left(\frac{r_1^2 - r_2^2}{r_2^2}\right)$ (12.27*)

* ***withdrawal*** *of heat* $Q_2 - Q_1 = \Delta Q = Q_1 \frac{\Delta T}{T_2} = Q_1 \cdot \left(\frac{r_1^2 - r_2^2}{r_2^2}\right)$ (12.28)

* *and* ***entropy destruction***: $\Delta S = C_p \cdot m \cdot \ln \left(\frac{T_2}{T_1}\right) = C_p \cdot m \cdot \ln \left(\frac{r_2}{r_1}\right)^2$ (12.29)

Fig. 12.8: The cooling and entropy destroying effect of contracting potential vortices (calculations concerning chapter 12.7)

13. Recording of space and time

If observations should force us to touch the sacred physical laws, then we should first of all judge our measuring technique critically of all sides and bring it in an usable state. I suggest, we start completely from the beginning with the devices, with which the dimensions of space and time are recorded, with the tape measures for the measurement of length and the chronometers, our clocks.

We must find out, why comets are slowed down if they approach the sun like by the hand of a ghost and in going away again are accelerated, although no forces at all act on the celestial bodies from the outside.

We must find out, why in mines deep under the earth another value for the gravitational constant is being measured as on the surface of the earth<i>. The results hardly can be imagined, if an universal constant should lose its constancy.
Thereby can Newtonian mechanics and the well-known laws be used very successfully from today's point of view, as the derivations in the last chapters have shown. We even could verifiably and mathematically correct calculate the growth of the earth and the solar system with them. The physical laws in the normally used formulation in spite of that seem to be bound to certain limits. Some observations contradict all experience<ii>.

<i>: H. Schuh: Eine Konstante verliert ihre Konstanz; neue Experimente nahren Zweifel an Newtons Gravitationsgesetz, Die Zeit Nr. 40 vom 25.09.97. From it the following quotation (translated):
„It already is suspected for several years, that a fifth force could exist, this suspicion goes back to exact measurements of the gravitational constant G in Australian mines and shafts. Physicists of the University of Queensland in Brisbane had determined, that G for measurements underneath the earth is about one percent larger than the corresponding, since centuries in laboratories determined size. Their proposal for explanation, namely a fifth repelling force, at first met with sharp disapproval. But an at 21 august in the journal Science (Bd. 237/87, P. 881) published work, which bases on measurements in a drilling hole in Michigan, confirms the Australian data".

<ii>: Already the nobel prize winner of physics, Lenard, pointed to the circumstance, that the relativistic representation of the astronomical aberration is incorrect, after no distinguishable aberration could be observed at binary stars, as it had been expected. With that Lenard by the way also has confirmed the existence of an aether.
P. Lenard, Annalen der Physik, Bd. 73, S. 89 (1924)


S-V: indication of month (rotating).
A: inlet
G: swimmer
E: outlet
T
U
S
V
F
A
B
C
G
K
L
Q
D
E
R
P
M
N
O

Fig. 13.1: The water meter of the Ktesibios (approx. 250 BC)
(with regulation of the water-level)

13.1 The measuring technical debacle

We are standing for a measuring technical debacle, because we have fixed our calendar to the rotation of its own of the earth. We call a 360° turn a day, divide it in 24 hours of 60 minutes each and every minute in 60 seconds. With that we determine the duration of a second.
A clock according to this definition only then is exact, if it follows the changes of the earth to the same extent. Obviously this in particular is the case for atomic clocks. An objectively seen precise going clock however would land at the waste disposal site as completely unusable.
Alter all nobody wants to know, how late it really is. Everyone only wants to find confirmed his subjective feeling, and our experience of time simply is directed after the course of the sun, thus after the rotation of the earth!

For the moment and as an approximation also for the life time of a person, this determination of time may be sufficiently exact, but seen over larger periods of time, one doesn't get around a conversion. Actually the 200 million years since the beginning of the Creation on the mentioned primeval hill are considerably less long ago. The earth and the whole solar system are very much younger, than was assumed until now!

If we as an example again take the cited research group of the University of Arizona (chap. 11.10<i>), which by means of an analysis of sediment formations have found out, in accordance with our calculation, that 900 million years ago a day only had 18 hours<i>. Such traces in geological deposit layers can be very informative, if they are analysed correctly, since here the measurement technician himself is not subject to the process. He stands outside and hence can exactly measure the time difference.
If a geologist of that time had looked at his watch during the formation of the layers, then a day obviously would have had 24 hours, and he wouldn't have been able to understand the whole excitement at all. The accusation, he would suffer from chronic blindness caused by his job, he of course would repel resolutely. Can you now imagine, from which disease our science of today suffers?

Our chronometers are nothing but the improved model of a sundial<ii>.

We live in the dimensions of space and time, but we quite obviously have the biggest possible difficulties with the dimensioning of both. Possibly we already aren't capable of that at all by principle. Most suitably we clarify the situation by means of examples concerning the two problem spheres.

Let us at first stay at the dimension of time. It may have become clear, how problematic the chosen determination of the time scale in seconds is and which contradictions can result if larger periods of time are considered. More and more often science fiction authors romp about on the playground of time, fantasize about some time travel, or they occasionally make jokes about it<iii>.

<i>: 900 million years ago a day had 18 hours, Washington (dpa) 1997.

<ii>: There also exist models, of which is asserted, they go according to the moon.

<iii>: A passenger, who got on the 10 o'clock bus, passes by the church steeple clock, which only reads 5 to 10 and curses: Damn, I took the bus in the wrong direction!

Centrifugal force $\boxed{F_{1,2} = (m/R)\cdot(v_E \pm v_f)^2 = m\cdot R\cdot(\omega_E \pm \omega_f)^2}$ (13.1)

with: $R = 6378$ [km] (radius of the earth),

$v_E = \omega_E\cdot R = 0{,}465$ [km/s] (rotational speed of the earth), (11.20)

$v_f = \omega_f\cdot R = \pi\cdot R/t_o$ (speed of the plane) (13.2)

and: t_o [s] (duration of journey)

energy of the moving steering quanta:

$$\boxed{\begin{aligned} E_{1,2} &= \int_O^R F_{1,2}\, dR = m \int_O^R R\cdot(\omega_E \pm \omega_f)^2\, dR = \quad (13.3)\\ E_{1,2} &= \frac{1}{2}\cdot m\cdot R^2\cdot(\omega_E \pm \omega_f)^2 = \frac{1}{2}\cdot m\cdot(v_E \pm v_f)^2 \quad (13.4)\end{aligned}}$$

energy balance (generally of a quantum of radiation):

$\boxed{E_{1,2} + E_q = E_{ges}}$ resp. $\boxed{E_{ges} - E_q = E_{1,2} = \Delta E}$ (13.5)

in general: $E = h\cdot f = m\cdot c^2$ resp. $m = h\cdot f/c^2$ (13.6)

(Gl. 13.4 mit 13.6):

and specifically: $\boxed{\Delta E = h\cdot\Delta f} = \boxed{E_{1,2} = h\cdot f\cdot(v_E \pm v_f)^2/(2c^2)}$ (13.7)

$\Delta f/f = \Delta t_{1,2}/t_o$ resp. $\Delta t_{1,2} = t_o\cdot\Delta f/f$ (13.8)

(eq. 13.7 inserted into eq. 13.8)

resulting in: $\boxed{\Delta t_{1,2} = t_o\cdot(v_E \pm v_f)^2/(2\cdot c^2)}$ (13.9)

time of travel around half the earth: $t_o = \pi\cdot R/v_f$ (13.2)

results in a difference in going of: $\Delta t = \Delta t_1 - \Delta t_2$ (13.10)

$$\Delta t = [(v_E + v_f)^2 - (v_E - v_f)^2]\cdot\pi\cdot R/(v_f\cdot 2\cdot c^2) \quad (13.11)$$

result calculated: $\boxed{\Delta t = 2\cdot v_E\cdot\pi\cdot R/c^2 = \underline{207}\ [\text{ns}]}$ (13.12)

measured by Hafele and Keating<i>: 214 [ns]! (13.13)

Fig. 13.2: The difference in going of two atomic clocks
(caesium resonant clocks)

<i>: Hafele-Keating-Experiment, Oktober 1971; s. a. W. Bauer: Klassische Physik, Graphia Druck, Salzburg (1975), Eigenverlag

13.2 The clock paradox

The theme „time dilatation" in connexion with the particle decay already has been treated (part 1, chapter 6.20). It has been shown, that a fast moving and with that length contracted particle to exactly the same extent (Lorentz's square root) becomes more stable and longer-living. If relativists pack an atomic clock based on radioactive decay in a plane and detect a difference in going between the one, which has been flown around and a second identically constructed clock, which has stayed at the ground, then they have with that detected experimentally a very small length contraction, which really occurred, and by no means a time dilatation, as they claim.

Now we in addition owe Einstein, that the aether has been abolished and from that follows, that it can't play a role in which direction the plane flies. If therefore both clocks are taken along each in a separate plane, one plane flying to the west and the other to the cast, both planes meeting again for the first time on the other side of the globe, then according to Einstein's theory it shouldn't be possible to determine a difference in going, if both planes constructed identically were on the way with the same velocity. But this is not the case!

Actually a difference in going is measured, which however can't be calculated with the theory of relativity, yes, which is completely incompatible with this theory and clearly brings anyone to the eye, that the effect actually can't have to do anything with a time dilatation, that the moving clocks merely go wrong and we have to ask us, why<1>.

These experiments were carried out with atomic clocks, which are constructed as caesium resonators and work with an exactness of one second in 300000 years. As a resonator serves a quartz crystal, which is controlled by an ion current of caesium atoms, which have lost their outermost enveloping electron. The system is fed back, because the oscillating quartz controlled by the caesium ions again adjusts the caesium vapour by radio wave and finally its own atomic controlling current (fig. 13.7).

The reason for the measured difference in going is seen in the field and here specially in the different gravitational field. The centrifugal force directed opposite to the gravitational force at least is not the same, because for a westward flight along the equator the speed of the plane v_f should be subtracted from the velocity of rotation of the earth v_E, whereas in eastward direction it should be added (eq. 13.1).

For the steering quanta supplied by the caesium resonator now the energy balance is put up (13.5 with 13.4) and the change of the reference frequency is calculated (13.7). With the change in frequency is connected directly a change of the at the two clocks readable times $t_{1,2}$ (13.8). For a journey around half the earth, where one clock is flown westwards and the other one eastwards, the difference in going should, according to the calculation, amount to 207 ns. Interesting of the result (13.11) undoubtedly is, that the velocity of the planes doesn"t play a role. It is cancelled out.

October 1971 caesium atomic clocks were sent around the world in scheduled planes in the Hafele-Keating experiment. To be able to estimate the inaccuracy in going of the clocks and with that the measurement error, four clocks were used. Between the westward journey (273 ±7 ns) and the eastward journey (59 ±10 ns) a difference in time of 214 nanoseconds was determined. This under strict scientific conditions determined result once more proves the correctness of the theory of objectivity by confirmation of the calculated value. That however is not valid for the special theory of relativity, because that doesn't appear in the calculation at all!

Who now believes, we would have less problems with the dimension of space, I must disappoint. The determination of the linear measures equally ends in a fiasco.


radius
of the earth: R = 6378 km
shaft depth: a = 1,3 km
measured change in
length: x* = 20,9 cm
(lengthening)
expected: a/R = b/(R-a)
b = a - x = a(R-a)/R
x = a - a + a²/R =
x = 26,5 cm
(shortening)
(13.14)
R*
a
a
shaft I
R
shaft II
linking gallery
b
x
b*
measurement: b* = a + x*
expected: b = a – x
error: Δa = x* + x
Δa = 47,4 cm
(13.15)
The centre of the earth

Fig. 13.3: Expectation and measurement in the Tamarack mines
(The curvature of the earth and the length of the shaft a are drawn strongly exaggerated for clarification)

13.3 The Tamarack mines experiment

As long as the „foot measure" depended on the shoe size and the „cubit" on the forearm of the tailor, the world still was OK. The sciences however request a reproducible quantity for comparison, and that can be fetched at the Bureau International des Poids et Mesures in Sevres near Paris. The original meter is a Platinum alloy. Because the length of the metal always depends on temperature, it is stored at a constant kept temperature of 0° Celsius. Now there in addition still exists a field dependency, an electrostriction resp. magnetostriction. And how is the measurement bar behaving, if the earth grows and the density increases? Is it then shrinking just like other objects in its environment? At this point already chaos is proliferating.

The newest definition of the length measure meter acts as a blow for liberty and thus marks the abyss, at which we are standing: The length is determined by means of a measurement of transmission time of an electromagnetic wave, e.g. of a light signal. It is said that with this determination a higher reproducibility should be obtained. Actually a photo optical facility to measure length is as exact as the built-in facility to measure time, and there we use it again, our sundial. In addition a constancy of the speed of light is taken as a prerequisite, and that is given in meters per second. From a change of the speed of light for forinstance 10% a change in length for 10% as well would result<i>. Because we see this process with the help of our eyes as well with the speed of light, we never can see the change. We neither can technically measure it, because all gauges we construct are built up corresponding to our sensory impression. We ourselves have shovelled the hole, in which we fall.

Only if we succeed in taking a neutral standpoint outside of the events, the true relations will become visible to us. For the field dependency of the space measures a very clear experiment has been carried out, of which I now want to report<ii>.

1901 the French government was offered the possibility to carry out an experiment in the shut down Tamarack mines near Calumet (Michigan) with the goal to determine the diameter of the earth more exact. For that the geophysicists let down two plumb-lines of 27.2 kg each in two perpendicular winding shafts, which were at a distance of 1.3 km from each other. The plumb-lines were tied to hardly expandable piano wires of as well 1.3 km length. It now was expected, since the plumb-lines hung in direction of the centre of the earth, that in a linking gallery between the two shafts a length of (1.3 - x) km should be measurable. From the shortening x one wanted to infer the diameter of the earth (fig. 13.3). But it came completely different.
Instead of a shortening a lengthening for x* = 20.9 cm was measured in the gallery! The point of intersection of the lines through the two shafts had to be not in the inside of the earth, but in space! Immediately „hollow earthers" appear, who claim we would live on the inside of a hollow world<ii>. Perhaps one should shoot them to the moon, because from there the earth without doubt is seen as a sphere. Obviously we aren't dealing with a surprise of a fair, but with a fundamental measuring technical problem.

<i>: for that see also part I, chapter 6.11 and 6.12
<ii>: http:/www.t0.or.at/subrise/hollow.htm



Volume of the globe: $V = (4/3)\cdot\pi\cdot R^3$ (13.16)

and of the inner sphere in depth a: $V_a = (4/3)\cdot\pi\cdot(R-a)^3$ (13.17)

resulting in the relative change:

$$\boxed{\frac{\Delta V}{V} = \frac{V-V_a}{V} = 1-(\frac{R-a}{R})^3 = 1-(1-\frac{a}{R})^3} \quad (13.18)$$

from $m = V\cdot\rho$ for a constant density ρ (13.19)

and<iii>: $m = \phi/\sqrt{G\cdot 4\cdot\pi\cdot\mu} = A\cdot\mu\cdot H/\sqrt{G\cdot 4\cdot\pi\cdot\mu}$ (13.20)

follows: $\boxed{m \sim V \sim H}$ (13.21)

resp. the relative change:

$$\boxed{\frac{\Delta H}{H} = \frac{\Delta m}{m} = \frac{\Delta V}{V} = 1-(1-\frac{a}{R})^3 = \underline{0{,}061\%}} \quad (13.22)$$

According to the theory of objectivity the length of the measurement wire is field dependent<ii> with:

$$\boxed{H \sim 1/a^2} \quad \text{and} \quad \boxed{H_a \sim 1/(a-\Delta a)^2} \quad (13.23)$$

and the relative change:

$$\boxed{\frac{\Delta H}{H} = \frac{H_a-H}{H} = (\frac{a}{a-\Delta a})^2 - 1} \quad (13.24)$$

Shortening of the rule Δa is calculated from the comparison of equations 13.22 and 13.24:

$$\boxed{\frac{\Delta H}{H} = 1-(1-\frac{a}{R})^3 = (\frac{a}{a-\Delta a})^2 - 1} \quad (13.25)$$

$$\Delta a = a\cdot(1-1/\sqrt{2-(1-a/R)^3}) \quad (13.26)$$

$\underline{\Delta a = 40}$ [cm] (result of the calculation)

$\underline{\Delta a = 47}$ [cm] (measurement value for comparison, 13.15)

Fig. 13.4: Calculational verification of the measured shortening

13.4 Field dependent linear measure

If a measurement result delivers just the opposite, as was expected by the experimentators, then the layman is amazed and the expert is surprised, at least at first. But then, out of a feeling of panic, the whole view of life could collapse, as many as possible scientists and renowned professors are being informed and integrated, if they want it (Prof. Mc.Nair) or not (Prof. Hallock, Columbia University) and eventually the matter is buried third class and a guise of silence is spread over it. The censorship of the scientific making of opinion in advance doesn't permit publications, which are not in accord with our view of life, out of the animal survival instinct<i>.

A science, which deserves this name, should look different. There it must be permitted, to ask questions and to publicly discuss about it.

I proceed from the assumption, that the earth is a sphere, which we inhabit from the outside; I have no doubts about that. With this as a prerequisite there is only one possible answer to the Tamarack mines experiment: The 1.3 kilometres long measurement wire, which in the gallery in a depth of 1.3 km had to jut out for 26.5 cm, instead is too short for 20.9 cm, from which immediately follows that it, howsoever, is shrunk for 47.4 cm in the depth.

At first of course the experiment was checked for possible measurement errors. The shafts were covered to exclude any draught. The measurement path was optically checked, but the result remained unchanged. But if the cause for the unexpected result doesn't lie in the experiment, then theoretical physics is addressed, after all it is still the experiment which shows us the physical reality and not some theoretical model concept.

In the 1st part of the book already the derivation of a useful explanation is found: The speed of light and with that also the linear measure depends on the field<ii>. The measurement wire accordingly gets shorter, if it is exposed to a larger field strength (eq. 13.23). We can verify the measured shortening calculative (fig. 13.4).

For that we at first determine the change of the field strength, as it is to be expected in a depth of 1.3 km. We here are dealing with the closed H field lines, which are responsible for the gravitation. In a past derivation it has been shown, that a gravitating mass can be converted into a magnetic field<iii>. Between a mass m and a field strength H hence exists a proportionality (13.21), in the same way as between the same mass and its volume, if a constant density is present (13.19).

The result accordingly is a relative decrease of the volume of the earth and the corresponding mass being under the measurement place, as well as a relative decrease of the radial component of the field strength, but a corresponding relative increase of the tangential component of the field for 0.061% (13.22 with 13.18).

In the gallery the measurement wire however is spread out in the direction of the tangential component of the field lines, and that shortens the measurement wire as a result of the field dependency of the linear measures<ii> (13.23). From the above increase in field the calculational shortening of the rule for 40 cm results, which compared to the measurement result also should be rated as a confirmation of the theory of objectivity which was taken as a basis<ii>!

<i>: Example: K. Meyl: Potentialwirbel, Bd. 1, reference entry /5/

<ii>: for that see also part 1, chapter 6.6, equation 65 and chapter 6.10

<iii>: K. Meyl, Potentialwirbel Band 2 (1992), page 27, equation 20



Fig. 13.5: Rise of the earth over the horizon of the moon""

<i>: Mitton, S. (Herausg.): Cambridge Enzyklopadie der Astronomie, Orbis Verlag (1989), note: No star is seen!

<ii>: see also the references in part 1, chapter 6.9

13.5 Experiences from space travel

The good correspondence of the calculated shortening of the measurement wire and the until now not understood measurement in the Tamarack mines shows both qualitatively, and quantitatively the correctness and useful applicability of the theory of objectivity of the field dependency of the linear measures. Our measurement laboratories normally are situated on the earth's surface and there everywhere are found approximately identical field relations. But if we leave the usual measurement environment and move the laboratory for instance in the sky, then we experience a complete mystery. Here however prevail the reversed conditions as in the mines experiment, in which in the inside of the earth. for an increase of the field strength, a length shortening was measured. In the sky the field strengths decrease and the linear measures correspondingly increase.

This experience astronaut Roosa made in the Apollo 14 mission. While he alone in his capsule orbited the moon, he depicted mission control, he could see the lunar module and observe his two colleagues at their work on the moon. Nobody wanted to believe the astronaut, since he was flying in a height of 180 km!

Commander Armstrong (Apollo 11) at the first landing on the moon indicated, the target crater Mackensen, 4.6 km in diameter measured from the earth, just has the size of a soccer field! Astronaut Scott (Apollo 15) called Mount Hardley, which is said to be 4.8 km high, a practice hill for skiing. Perhaps they somewhat have exaggerated, but a true core in the statements always is present!

Actually the gravitational field of our satellite is very much smaller than that of the earth. On the surface of the moon there is only one sixth of the gravitational pull of the earth. If we, to be able to compare, stick to the details of size, as they are measured by our laboratory on earth, then the astronauts on the way to the moon together with the lunar module and their rover had grown for a factor $\sqrt{6}$,then the first footprint is 2.5 times as large as on earth, then the astronauts were moving like giants in the scenery of a model of the railroad (eq. 13.23 and note<ii> at fig. 13.4).

On the moon there exists almost no atmosphere, for which reason the astronauts had imagined a wonderful view of the star-spangled sky, at least before they started. After the landing they were bitterly disappointed. The sky was black and not one single star could be seen! They have brought many photographs, but nowhere stars have been photographed, they apparently have moved outside the range of vision (fig. 13.5 and 13.6).

Many will still remember that the first pictures, which the space telescope Hubble supplied 1990, were completely blurred. The problem obviously was, that the mirrors had been adjusted on earth and not in space. Only after the optics had been given glasses in 1994, sharp pictures could be radioed to earth. Somehow the distance to the stars had changed. The telescope had become short-sighted, resp. the distance to the star-spangled sky appeared to be gotten larger. We already know why. If we remove us from the gravitational field of the earth, the field strength decreases and the observable distances increase! The highly sensitive telescope already sufficed the 5% deviation, with which should have been reckoned for the near earth orbit, to be fatal.

One should have familiarized the astronauts before with the laws of physics. Then this disappointment would have been spared to them, and in the case of the Hubble telescope the NASA and the european ESA could have saved a lot of money for the sake of the tax-paying population<ii>.

Warum sieht man am Himmel keine Sterne?

Fig. 13.6 a: Illustrierte Wissenschaft Nr. 11 (1997) Page 62

1st example: landing on the moon
gravitational ...

$$\frac{\text{...pull of the earth}}{\text{...pull of the moon}} = \frac{g_E}{g_m} = \frac{M / R^2}{m_m / R_m^2} = \frac{M}{m_m} \cdot \frac{R_m^2}{R^2} = 6{,}0375 \qquad (13.27)$$

in space everywhere on the surface of a sphere is valid: $A = 4\pi R^2$

eq. 13.20 (fig. 13.4<iii>): $m \sim \phi = A \cdot B = 4\pi R^2 \cdot \mu H \sim R^2 \cdot H$

as well as eq. 13.23 (fig. 13.4<ii>) for the field dependency: $H \sim 1/l^2$

and further:

$$6{,}0375 = \frac{g_E}{g_m} = \frac{H_E}{H_m} = \frac{l_m^2}{l_E^2} \qquad (13.28)$$

resulting in the length dilatation (expansion) on the moon:

$$\boxed{l_{m\,(\text{Mond})} : l_{E\,(\text{Erde})} = \sqrt{6{,}0375} = \underline{2{,}457}} \qquad (13.29)$$

2nd example: communications satellite in a geostationary orbit (at h = 36000 km above the equator, R = 6378 km).

$$\boxed{\frac{l_h}{l_E} = \sqrt{\frac{H_E}{H_h}} = \frac{R+h}{R} = \underline{6{,}64}} \qquad (13.30)$$

Fig. 13.6 b: Examples of calculation for length dilatation<i>

<i>: If the theoretical value of 6.64 could be quantitatively confirmed by observations from off the earth with a telescope at a corresponding magnification, then with that would have been proved, that in the case of the spherical aberration it actually concerns the calculated influence of the field.

<ii>: U. Seiler-Spielmann: Das Marchen vom toten Mond, Zeiten Schrift 5/94,S.39

13.6 Spherical aberration

It is true that the problem of the changed length relations is known to the experts under the term of a "spherical aberration". But with that it is neither qualitatively nor quantitatively understood. Only the theory of objectivity soundly gives reasons for, why the astronaut Roosa has seen his colleagues almost 3 times as large, why weather satellites in a height of 1500 km are approx. 25% larger and why communications satellites in a 36000 km high geostationary orbit even increase to the 6.64 fold of their original size[i]. It also explains, why the neutral point between earth and moon, at which the attraction of masses of both celestial bodies mutually cancel, wasn't reached at the point where it had been expected by the moon rockets[ii].

We, the inhabitants of the earth, are adapted completely to the conditions on the earth's surface. If we find our way well in the dimensions of space and time, as we observe them, then that must not be valid by all means for science, because that has made it its business to find out the secrets of nature.

If it wants to deserve the name science, then it on the one hand has to consider, that we, the organic materials, as well as all inorganic materials are assembled from the same atoms and molecules and with that are exposed to the same length relations. If changes in length between day and night (as a result of the gravitational field of the sun (see chap. 6.7), between summer and winter or as a result of changes in field occur, then we aren't able to register this at all. That even today the „foot" is used as a measure, for instance in the air traffic, shows only too clearly, how man raises itself to the measure of all things. Science asks for modesty!

On the other hand it should be paid attention to the fact, that man eyes everything with speed of light with the optics of his eyes, and that speed by no means has to be constant. Solely the definition of the speed of light c as a linear measure per unit of time points to the direct proportionality between c and a length 1 (see chapter 6.3):

$$\boxed{c \sim 1} \qquad (13.31)$$

If a rule has proven to be unusable for measuring a distance, then we'll experience the same disaster, if we measure optically, i.e. with the speed of light. Obviously both, the length 1 and the speed of light c depend in the same manner on the respective local field strength. On the one hand both measurement techniques lead to the same result, but on the other hand what can't be measured with one method, neither can be measured with the other.

To prove the constancy, it is normal to measure the speed of light optically. But since there exists a proportionality between measurement variable and measurement path (53), the unknown variable is being measured with itself. This measurement faulty by principle in all cases delivers a constant value. In contrast to the textbook opinion of today by no means a constancy of the speed of light can be assumed. In the case of the in a vacuum measurable 300,000 km/s it concerns a capital measurement error, at best a constant of measurement, but never ever a constant of nature!

With the postulate and the misinterpretation of a constancy of the speed of light as a universal constant of nature Einstein already let several generations of physicists run into the same dead end, in which they today are stuck altogether. It surely is no accident, that the big time of discoveries abrupt came to an end with Einstein.


The radio waves change the direction of rotation of the enveloping electrons of the Cs atoms
polarizer: magnet sorts out atoms with unwanted direction of rotation ■
analyzer: magnet sorts out again ■ wrong atoms
B-field
⊗
L
filter and ioniser produce ion current
caesium oven sends Cs-atoms on a journey
magnetic shielding
resonator of length L
frequency control
electromagnetic wave adjusts the atomic clock
The quartz oscillator oscillates with 9 192 631 770 Hertz
quartz-crystal

Schematic representation concerning principle of functioning
L = length of resonator determining the exactness
The B-field is a weak magnetic field, which eliminates the influence of magnetic stray fields.
The arrangement in addition is situated in a vacuum tank.

Fig. 13.7: Set-up of a caesium atomic clock

13.7 Irony of the measuring technique

Let's record: The linear measure is determined and defined by a measurement of transmission time. As a reason is given, that with today's clock technology a higher precision and reproducibility can be obtained, as with a rule or original meter. The exactness of going of the atomic clocks again depends on the free flying path (L in fig. 13.7) of the atoms. For the caesium clocks of the Physikalisch Technischen Bundesanstalt in Braunschweig the resonator length amounts to several meters! The clock is used world-wide as a standard.

The irony thus lies in the fact, that a geometric length dictates the measurement of time and the measurement of time again determines the measurement of length - poor science!

How does one free oneself from a capital closed loop conclusion? Why and how do signal transmission times or clocks actually depend on the gravitation? Who once got stuck in a dead end, knows that he only can get out in the reverse gear.

A possible way goes back to the roots of classical physics and to the theory of objectivity in the 1st part of the book, which is free from the limits of a subjective and relativistic observer standpoint. That isn't a dead end and in addition explains, why all atomic clocks react sensitive to magnetic fields (magnetostriction) and what these fields have to do with gravity (see chap. 6.9)!

Today's clocks are so exact, that even differences between a clock stationed on a mountain and one at sea-level can be recorded. Even more clearly was the depending on gravitation determined at an atomic clock, which was shot in a rocket 10000 kilometres high into space. The result of the analysis without doubt was, that the clock in that case doesn't „tick" correctly anymore.

But what does theoretical physics say about it? It claims, here the „red shift" has been measured; it thus concerns a confirmation of the special theory of relativity. But since it concerns a clock experiment and not a light signal, it clearly contradicts this theory, which isn't able to describe any gravitational effect at all, as is well-known. For this case in the spheres of theoretical physics one helps oneself with the general theory of relativity, with which actually only would be proven, that the two theories from the legacy of Einstein completely incompatible contradict each other. We come to the following conclusion:

Whoever gives details about length or time, is obliged to also indicate the reference system.

He also has to inform where his laboratory is situated and with which devices he measures!

With the conclusion also the discussion would be opened. Throughout the last four chapters a main idea can be found. It should be worth, to again think about the brought forward arguments and to dare a comparison with text books.

In the text books there doesn't exist such a thing as an oscillating interaction. Here no answer is found to the question, why the solar system isn't hurled out of the galaxy as a result of the high velocity, why the inside of the earth is hot, how the geomagnetism is formed, why the continents drift and why the ocean floor nowhere is older than 200 million years, as samples from the ocean floor prove<i>. How would you answer these central questions?

<i>: Kendrick Frazier: Das Sonnensystem, Time-Life Bucher, Amsterdam (1991).


p
$^{12}\mathrm{C}$
γ
e^+
$^{13}\mathrm{N}$
$\bar{\nu}$
$^{4}\mathrm{He}$
p
$^{15}\mathrm{N}$
$^{13}\mathrm{C}$
p
$\bar{\nu}$
$^{15}\mathrm{O}$
γ
e^+
$^{14}\mathrm{N}$
γ
p

Fig. 13.8: The Bethe-Weizsacker cycle (concerning the sun's fire)
(meaning of: $^{12}\mathrm{C}$ = carbon nucleus, $^{4}\mathrm{He}$ = helium nucl., γ = gamma quant, $^{14}\mathrm{N}$ = nitrogen nucleus, p = proton, e^+ = positron, ν= anti neutrino, $^{16}\mathrm{O}$ = oxygen nucleus



Fig. 13.9: The top of the unfinished obelisk in Assuan<i>

<i>: Hermann Wild: Technologien von gestern, Chancen fur morgen, Jupiter-Verlag Bern (1996), ISBN 3-906571-13-0

13.8 Discussion of the cosmological insights

The numerous models which are offered, of a geodynamo, an iron core, of assumed zones of subduction and of plate tectonics may be helpful for the explanation of individual isolated phenomena. But they physically don't give a uniform picture and partly contradict each other.

Lord Kelvin had calculated a period of shining of 5000 years on the basis of a sun consisting of coal<i>. The german physicist Hermann von Helmholtz landed at 15 million years, in which case the sun yearly should shrink for 100 meters. He already assumed a temperature of 15 million degrees centigrade, as also the Bethe-Weizsacker cycle has as a prerequisite, which according to today's concept should describe the process of nuclear fusion taking place in the inside of the sun (fig. 13.8). The only thing is that this extreme temperature is completely incompatible with the high density in the core of the sun! There are more than good reasons to assume the opposite of the widespread textbook opinion and assume that the core of the sun is cooled by the collected neutrinos in the same manner as the inner core of the earth and that superconducting areas are formed, which powerful fields even cause the protuberances on the surface of the sun. Since in the sun no measurement is possible, with which a model could be verified or disproved, terrestrial arguments naturally suggest themselves. Here the pieces of evidence for the growth of the earth can be taken in the hand and photographed. We already have discussed some facts. But there are found a multitude of other ones, for instance from the domain of archaeology, for which text books of today until now as well provide no explanation.

Possibly the stones and monoliths weighing several tons, as they were used for prehistoric buildings, should be linked with the growth of the earth. If the earth was smaller at the time they were build, then they perhaps by no means were as heavy as today!
Then the stones for reason of the smaller density in addition were softer and with that easier to work on. Dr. Wild points to the building technical peculiarity, that the stones formed like cushions originally must have been soft. He proves with the photograph of the top of the unfinished obelisk in Assuan (fig. 13.9), that the traces of working stem from a spatula in a plastic mass.
Also the perfect fitting of the stones used for the building of the pyramids can only be explained in this way. In the joints not even a knife point can be inserted!

If even stones in the course of time increase in density and hardness, then it is easier for us to comprehend, how small rivers in past time could dig large deep valleys in the earth's crust, then we perhaps also understand, why very old bones today are petrified<ii>. It is obvious, that also bones in the course of time increase in density and hardness. Even if science should succeed in breeding living dinosaurs, then their chance to survive in spite of that would be equal to zero, because the dinos would collapse under their weight of their own of several tons. Their bones would be much too thin and brittle for their weight of today!

<i>: Kendrick Frazier: Das Sonnensystem, Time-Life Bucher, Amsterdam (1991)
<ii>: The indication to petrified bones stems from a participant of the seminar.

25-07-1996: Assistant head of government department
Acceptance of the common standpoint.

11-12-1996: European parliament
Resolution of the guideline.

commission
Statement concerning proposals of change of the european parliament.

19-12-1996: Assistant head of government department
Resolution of the guideline.

19-02-1997: Coming into effect of the guideline
Publication in the official paper of the EC.

19-02-1999: Period of translation of two years

Reduction of the threshold values for current consumers:
19-02-1997: to 40 million kWh (opening of the market 23%)
19-02-2000: to 20 million kWh (opening of the market 28%)
19-02-2003: to 9 million kWh (opening of the market 33%)

until 2006: „Anti imbalance clause"
A nine years period of transition to preserve equal opportunities in the competition.
Report of the commission.

19-02-2006: Further stage of the liberalization
European commission tests by means of the made experiences, if the current market should be opened further.

Fig. 14.1: Timetable of the EC single market guideline electricity<i>

<i>: Grawe, S. Thiele: Vorbereitung der Stromversorger auf den Wettbewerbsmarkt, ATW Atomwirtschaft-Atomtechnik 43. Jg. 1998, Heft 1, S. 10 - 13

14. The way towards free energy

Can energy actually be produced? No energy supply enterprise is capable to do that. Fact is, that energy only is converted and not produced. For that the available resources on earth are tapped and brought into a utilizable form of energy. As different the conversion processes may be, finally always heat is formed. We thus gradually burn the globe, on which we live. How long can something like that go right?

Science gives all-clear: „stock of energy is sufficient for the next 100 years. Newest calculations disprove the fear of a scarcity of energy on earth. There exist large stocks of coal and oil"<i>.

But what are 100 years compared to the age of the earth? How will our descendants judge our thinking and acting? They will condemn it and curse us, that much is clear already today.

We have an obligation to preserve the environment, and we only will be able to fulfil it, if we look to nature, how it covers its need of energy, if we finally understand and meaningfully copy nature.

We still are miles away of the goal.

14.1 The liberalization of the energy markets

It is important in the interest of a member of the executive that the stock of energy doesn't draw to an end, as long as he carries the responsibility for the enterprise of the economy of energy. The interest in the environment and the environmentalists for obvious reasons is less distinct. The problems are more of a commercial kind. Concerning that an actual example is given.

A special kind of problem is the meanwhile Europe wide valid decree of the EU concerning the liberalization of the energy markets (fig. 14.1). The list of the consequences starts with the fact, that the concluded licence contracts for power supply between energy supply enterprises and the communities, which are valid till 1997, are only wastepaper. Every customer of electricity as of now can conclude an individual contract with every "producer of electricity".

So an environmentally aware Black Forest person decides to obtain his power from a wind power station, which is situated in Denmark. That truly sounds very liberal. But how should that function, if there is no wind at all in Denmark for a week, or the connection is interrupted by a flash of lightning? The windmill further delivers power and the runner writes its bill truly believing, its power has arrived. The consumer then reads the bill at candlelight and puts with understandable anger his claim for compensation together. Pointing to the fact that such difficulties can be solved by book-keeping, the consumer again is calmed down; but that the not by contract obtained power will cost him dear, is another story.

<i>: Illustrierte Wissenschaft Nr. 6, Juni 1996, page 48-51.



Fig. 14.2: Average time of paying for itself for the spent energy (return of energy)

14.2 The consequences of the liberalization

With the EU decree the monopoly only has shifted towards the runners of the distribution nets, after all only one net is present. Competition however would require at least two nets, thus a doubling of all house connections and all high-tension pylons, but that fortunately is unrealistic.

To prevent fleecing of the consumers by means of the net monopoly, politics introduces in the place of the free market economy dirigisme and plan economy with the well-known concomitants: no-one will look after the existing nets, no-one feels responsible anymore, because after all they have become public good by decree. One thus lets the pylons rot slowly and repairs only in emergencies. This possible development really can't have been the good intention of the EU.

In the next few years we however will be able to observe for the producers of energy exactly the development, which the EU-commissioners have imagined: Total competition contest, price war and a struggle for power to survive economically. A chance only has the nuclear power station, which gets rid of its refuse cheaper and if need be even illegally or which lives of indirect state subsidies, or the brown coal power station, which increases its efficiency at night, when no-one watches, by switching off the expensive filters.

The first power stations, which are selected out by the liberalized energy market, are the hydro-electric power stations which stand closest to nature. They simply are too small and too intensive of personnel, to be able to survive.

Gas turbine power stations, which deliver the power for half the price, than are ranking first. Then there is no place for regenerative systems anymore.

Solar energy, how many roofs a supporting program may have, stays a toy supported by the state. For a photovoltaic installation the „Return of Invest" still lies at more than 80 years, whereas is reckoned with a theoretical life of 20 years. In practical use on the other hand photovoltaic installations occasionally already have failed after seven years, after the photocells had gone blind. In this case not even can be talked of an ecologic energy, because the return of energy lies still above that. The supposed Idealist who spoils his roof with photovoltaic to reassure his ecologic conscience, would have spared the environment more, if he had covered his need of power from the socket, because already the production of the photovoltaic installation gobbles up more energy than can be produced with it. With regard to the environmental compatibility the ecologic balance sheet of a power station is attached a central importance (fig. 14.2).

With the law of feeding in power the state intervenes dirigiste, supposedly to protest the consumers. With this law the state orders, that not it, but the energy supply enterprises have to take the subsidizing of the regenerative energy, that they have to take over the power delivered at the inappropriate time in exactly so less suitable amounts at a price, which exceeds the market value by a factor of two and for falling prices of power even by a factor of four. With the law the politicians very fast and without agreement of the effected enterprises have shifted the „black Peter" further to these, which will get problems to preserve their competitiveness in the international comparison with the subsidy duty. It can't have been the intention of the EU-commissioners, that on a national level the price of power increases to finance some energy technical playground.



Fig. 14.3: Power interruption and not being at disposal

<i>: ETG, Energietechnische Gesellschaft im VDE: Qualitat der Stromversorgung, Dialog Nr. 1, Jan./Feb. 1998, S. 21

14.3 The chances of the wind energy

Meanwhile, as a result of the law of feeding in power, no longer the politicians but the energy suppliers are the ones, who around the North Sea look out of the window every day with the worry, some wind could blow and the mills could turn, because every kilowatt hour of a windmill must be subsidized strongly. Every windless day however reduces the power bill, with that helps the consumer and raises the chances of competition of our economy.

If it should be neglected, to tip over the law of feeding in power in due time with help of the EU, then the consumers will get their power in future abroad, then at the Preussen Elektra, damaged most by wind energy, as the first the lights will go out, then economic power and prosperity in Germany in future are dictated from abroad.

But if the law is dropped, then with that the duty to subsidize the regenerative energy carriers drops back to the state. Now all tax payers may foot the bill, even those, who don't use any power at all. The well-known Justice of subsidy" comes into effect.

Without support by the state only few types of power stations will be left behind. In addition are overcapacities being reduced, because they only cost money. But both is at the expense of the reliability of the delivering of energy and of the safety of the consumer. We owe the high stability of our network of today the large number of most different providers of power, which cover the basic load up to the peak load according to their suitability (fig. 14.3). But let us not talk of the golden past. The network after all isn't able to store power. From that follows, that without redundancy and without free power station capacities which can be activated at any time a short overload is sufficient, to let the network collapse.

Once the EU guideline concerning the liberalization of the energy markets is in effect, when persons selling power wend their way from front door to front door, to convince the housewives to obtain the power from them and not from other hawkers, when the power stations only live of stock and the depreciated overhead power lines only are entered in the hooks with the scrap value, then we should be dressed warmly and always have ready sufficient candles [i].

14.4 The chances of being self-sufficient concerning energy

The only way out is the decentralized energy supply, the getting out of the large energy union and the way towards being self-sufficient. The argument sounds convincing in view of missing alternatives. But now it no longer is possible to plug the plug in the socket and then switch on whenever it pleases us. First it has to be calculated, if the windmill or the installation for solar energy supplies sufficient power or if a cold meal should be made. In contrast to today's consumer habits the runners of such installations will have to adapt their need of energy to the prevailing weather conditions.

<i>: A baby-Boom, like after the big power failure in New York, would be the smaller evil. The inhabitants and shopkeepers in the New Zealand metropolis Auckland will long and frightened remember the power failure in february 1998, which lasted weeks and was a result of not carried out maintenance works of high-tension pylons.



Fig. 14.4: At maximum obtainable power density of different carriers of energy

<i>: ETZ, Heft 19/1995, S. 40

Block heating power stations, propagated as stand-alone solution for people being self-sufficient, deliver power and heat at the same time. But if I don't need any heat on a hot summer day, then also no power is available or I uselessly heat into the open. For that one may leave all electric consumers switched on in winter, even if they aren't used at all, only to get the hut warm. Does a stand-alone solution look like that?

The situation truly is demotivating. Even the energy suppliers meanwhile may have realized that the energy politic way is a dead end. But for real alternatives in energy technology the pressure by suffering still doesn't seem to be big enough.
The intention to learn of nature is present in principle. The solar fire one wants to kindle on earth in a fusion oven, but the oven does not as it should.
Obviously the sun functions completely different, as physics imagines today (see fig. 13.8).
Before copying stands understanding, and in there seems to be a hitch!

14.5 The space energy technology of nature

Also nature needs energy, even very much. But it hasn't got any connecting pieces for tanking and no oven lid to fill in the fuel, it doesn't know our ecologically harmful combustion technology and environment destroying explosion technology at all. Nature rather works with the opposite, with implosion and fusion.
The sun, we have derived, materializes the matter which it needs for growing and shining from the neutrino field. The earth and other planets imitate the sun.
The concept is simple and convincing. The source of energy lies in the air and mustn't be dragged about in tanks. Collected and materialized is just as much, as is needed at the moment. In that way the resource energy is spared. In addition there can be done without any sort of storing. In addition it can show a substantially higher power density, than all today known and used energy carriers (fig. 14.4).
Such a source of energy solves all described energy problems at once. Nature wouldn't be as we know it, if it wouldn't have this ideal energy, also called „free energy". The balance sheet of energy alone brings it to light, because as a rule it doesn't work out for biological systems. Often more energy is released than is taken up by the food.
In that case some migratory birds materially seen should have completely used themselves up before reaching their destination, if the energy necessary for the flight would be of purely material nature. From a concrete example the following is reported<i>: „migratory birds have - depending on kind - a maximum range velocity between 24 and 83 km/h and at their Atlantic flights no opportunity for an intermediate landing. They are thousands of kilometres on the way and hardly lose weight. For instance an Albatross with a body length of up to 1.20 meters and a wing span of up to 3.50 meters uses per kilometre only 8.5 grams of weight at a non-stop flight. How is that possible without additional supply of energy?"

<i>: K. E. Rathgeb: Wie man die freie Energie anzapft: Vogel machen es uns vor, Raum & Zeit 79/96, S. 74

Fig. 14.6: Freiherr von Reichenbach (76 years old)



Fig. 14.7: Odic emanations of magnets according to pictures of sensitives .<i>

<i>: H.-P. Thietz: Tatort Erde, VAP (1996), ISBN 3-922367-62-3, Seite 13 und 15

14.6 The gap in the energy balance of man

Even man appears to tap an additional source of energy, because for reason of scientific tests with recruits these over longer periods of time are able to physically release more than twice the amount of energy they take of calories with the food. Obviously living beings don't rely on one source of energy alone. Possibly the taking up of food predominantly serves the metabolism, and the energy aspect plays only a secondary role.

This interpretation at least would be obvious, since we scoff several times a day, sort the necessary and useful building-materials out and hand over the rest to the purifying plant and nature, where some bacteria and organisms search the sorted out again for useful things. "Food chain" we call this kind of building-material trade.

If the whole had anything to do with energy or with a „ combustion process without fire ", then no animal nor any human being could do without the taking up of food for longer periods of time. But Franciscus of Assisi could fast 90 days, as is handed down to us <ii>. There exist numerous examples, which reach into the time of today.

The mitochondria, the energy centres of each cell, by no means are capable of the "combustion process", which man ascribes to them. Here in all probability a taking up of space energy independent of food takes place.

A research scientist only has to look at nature with open eyes, what unfortunately happens rarer and rarer, because the laboratory scientist always is troubled, to keep the disturbing factor ,,nature " away from the experiments.

14.7 Carl Freiherr von Reichenbach

In this context no-one can go past two natural scientists: Carl Freiherr von Reichenbach (1780-1869) and Dr. Wilhelm Reich (1897-1957).

Reichenbach called the by him investigated life energy „ Od-energy " in the style of the Teutonic God Odin. He worked with test persons, who could perceive actually invisible light phenomena and worked out the special properties of this Od-energy field with the "sensitives", as he called them.

A quotation from his work shows however that the knowledge about the life energy must be a lot older<iii> than his own discoveries: „On paintings saints often are shown with a ring-like aureole around their head, something I before this would have dismissed as a pure figment of imagination. But it was shown that this glowing ring actually can be perceived by the sensitives as an Od-phenomenon and so the aureole obviously can be traced back to real impressions of particularly sensitive persons."

Reichenbach also found out that water has a big endeavour to take up this Od-energy or in the language of the present day, to absorb the field energy. This circumstance we find confirmed in technology, since water absorbs high-frequency waves, whereas an insulator or a vacuum lets them pass through. But without vortex physics it however remains entirely unclarified, why!

<ii>: H.-P. Thietz: Tatort Erde, VAP (1996), ISBN 3-922367-62-3, page 110

<iii>: H.-P. Thietz: Tatort Erde, VAP (1996), ISBN 3-922367-62-3, page 16



Fig. 14.8: Wilhelm Reich and the model of an Orgon accumulator
for applications of the whole body.[i]

---

[i]: taken from: H.-P. Thietz: Tatort Erde, VAP (1996), ISBN 3-922367-62-3, pages 38 and 89.

14.8 Cold fusion and Genesis

Chronologically the doctor and psychologist Wilhelm Reich followed in the footprints of Reichenbach. He merely altered the name for Od and spoke of Orgon. His speciality was the accumulation of Orgon radiation, I would say the focussing of neutrino radiation. Actually the properties like e.g. the missing possibility to shield Od, Orgon and the neutrinos are identical, so that we can proceed from assumption, that it also concerns the same physically.

We already talked about Wilhelm Reich (part 1, chapter 9.2). He could show that the measurable temperature in a closed box, constructed like an „Orgon accumulator", is increased in a mysterious manner without supply of energy from the outside. He even could prove, that this energy actually concerns the sought-for life energy, as he observed the creation of life in the laboratory under the microscope. For that he cooked muscle fibres, vegetables or other cells so long until the cell structure had been destroyed entirely. But from the educts entirely by itself new living beings, like protozoa or algae, were formed[i].

Reich at his microscope actually followed the transition of dead to living matter. What is of interest here, at first only is the energy technical aspect of this conversion. Later we will occupy us with the at the same time occurring information technical aspect.

Worth mentioning seems to me the experiment with the „silly" chickens, which have at their disposal astonishing abilities besides the laying of eggs[ii].

The test chickens were handed chicken food, from which to a large extent all calcium had been extracted. But the chickens showed themselves unimpressed and further laid keenly their eggs. The experimenters were surprised, where the chickens actually got the lime for the egg shells. How solves such a chicken the problem of raw materials? For that further materials were extracted from the food and look, at the removing of silicon the laying of eggs was over. The experiment actually only allows the conclusion, that the "stupid" chicken is capable of a cold fusion, that it itself „produces" the necessary calcium from silicon presumably by using carbon. Every alchemist here has to go pale with envy. But what says the research scientist of fusion to that, who actually should know, how fusion functions? After all he is paid for it by the tax payer! The chicken uses the fusion already today and the other living beings presumably also, but for that energy is needed and the balance sheet should work out!

The neutrino radiation therefore has to be factored into the balance sheet of energy. If the balance sheet then works out, it could be proven with that, that here neutrino energy is put to use. In addition the process of the conversion of neutrinos has to be investigated, which surely has something to do with the frequency and the wavelength of the radiation. After all a child has cells exactly as big as an adult. It only has less cells! So that an interaction can occur, the cell size has to fit in with the wavelength, which obviously is very small, presumably in the range of the radioactive radiation, with which circumstance the biological incompatibility with this electromagnetic wave would be explicable.

---

[i] H.-P. Thietz: Tatort Erde, VAP (1996), ISBN 3-922367-62-3, S. 39

[ii] Louis Kervran: Biological Transmutations, s.a. J. Heinzerling: Energie, S.278

1. Primary reaction
   (light reaction in the centre of reaction):

   ring-like vortices/neutrinos are being collected
   electrons are formed
   energy is produced
   e^- is attracted by the water dipole
   water molecule is being splitted (photolysis):

2. Secondary reaction (dark reaction):

   carbon dioxide is reduced with the hydrogen splitted off from the water to carbohydrate

Reaction equation of photosynthesis:

	6 mol CO_2	(carbon dioxide)
+	12 mol H_2O	(water)
+	675 Kcal	(vortex energy, light)
	1 mol $C_6H_{12}O_6$	(glucose)
+	6 mol O_2	(oxygen)
+	6 mol H_2O	(water)

Fig. 14.9: Concerning photosynthesis

14.9 Photosynthesis

The materialization of free electrons is a prerequisite to start the photosynthesis. The normally used explanation, the free electron necessary for the splitting of the water molecule was knocked out an atom by light, doesn't seem to be correct, after until now all attempts of a technical realization according to this model concept have failed. At the photosynthesis the plants obviously help themselves with the neutrino radiation, which according to an estimation of today with 66 billion particles per second and per square centimetre might be more than sufficient for a green earth.

If we put a seed in a water glass, then a plant grows from it and forms small leaves, which get bigger and bigger. A wonder of nature, we say. Where does it actually get its building-materials? From the water or from the air? Necessarily the plant obviously produces a part of the matter itself!

Experts think they have understood the process of photosynthesis: Take light and water and carbon dioxide and handicraft from that sugar and oxygen. But from where does the plant take the necessary energy for the rebuilding and the splitting of the water molecule, the photolyse? The taken up solar energy hardly is sufficient for that, especially since the plants only absorb about 1% of the photosynthetic utilizable sunlight incident on earth<i>. By means of reception molecules, which look like small antennas, pigments less than 30 nm in diameter, such is the level of knowledge, the sunlight is collected and led into a photochemical centre of reaction. Here the reaction should take place, provided that an electron set free by the light jumps into the middle of the centre of reaction. But exactly this favour the electron doesn't make the research scientists, who want to imitate the process. Copying nature still doesn't succeed.

The mistake presumably lies in the circumstance that the light doesn't set free any electron at all. The electron actually first of all is produced in the centre of reaction. By means of the antennas a neutrino vortex is collected, which at first occupies the entire space, to afterwards contract to an electron, which as a result automatically is centred in the centre of reaction.

In the process of materialization at the same time the necessary energy of the process is formed. The reaction equation after all also has to work out energetically, because the plants doing so get neither hot nor cold (fig. 14.9).

Because curiously the light reaction even can be observed in the dark<ii>, one could be inclined to in principle call into question the influence of light on the photosynthesis. But such an influence nevertheless seems to be present, after all does a plant react on the irradiation of light and changes its spectrum of absorption through its colour. But it for sure is another influence and not the one, which one attributes the green plants today! It would be important to finally understand the way of functioning. The plants and particularly the algae are the ones, which actually first have made possible life on this planet with the photosynthesis, the most original form of a production of matter and energy.

<i>: Luttge, U. u.a.: Botanik, VCH, Weinheim (1994) ISBN 3-527-30031-7, S. 136

<ii>: Luttge, U. u.a.: Botanik, VCH, Weinheim (1994) ISBN 3-527-30031-7, S. 126


Chlorophyll a
bei
Chl. b
System of
conjugated
double bindings
phytylrest: a
hydrophobe tail

Fig. 14.10: Formula of structure and spatial model of the photosynthesis pigment chlorophyll.<i>

<i>: Luttge, U.et al.: Botanik, VCH, Weinheim (1994) ISBN 3-527-30031-7, p. 118

14.10 How nature materializes

The structure of the receiver antenna allows us a deeper insight into the manner, how free energy is tapped during the photosynthesis. For the dimensions determining the frequency of the photosynthesis pigments, as the antennas are called, we have to go down to the molecular structure. Fig. 14.10 shows the formula of structure and next to it also the spatial model of the pigment chlorophyll[i].

Two points point at the function for free energy conversion. On the one hand is situated in the centre of the molecule a double positive ionised Mg atom, surrounded by four nitrogen atoms and a carbon ring consisting of 20 atoms, from which arises a polarization of the entire molecule. This in addition is oscillating because the electron cloud of the enveloping electrons, which hold the molecule together, perform swirl oscillations depending on the temperature. With that chlorophyll is able to go into resonance with oscillating neutrinos.
A role play the unipolar field configuration and the effect of resonance of the molecular oscillation of its own forming as a result of the polarization. A further role in addition seems to play the spatial structure.

The model of the „receiver antenna" chlorophyll taken out of a textbook[i] and shown in fig. 14.10, consists of a stalk and a spirally wound head, which resembles a Lituus or crook, which Etruscan and Roman Augurs have taken in the hands for land surveying, a precursor of the crosier (see fig. 16.10). This again has the form of a Tesla coil and that, as already derived, is able to withdraw rotational energy from the collected neutrinos (chapter 9.8). Doing so free electrons are materialized, and these then start the process of photosynthesis. An explanation concerning the way of functioning of the antenna pigments here for the first time is getting available.
By the way also the mitochondria, which form the energy centres in every cell, have as well the form of a Tesla coil. Whoever wants to understand the energy economy of a cell or the photosynthesis first should occupy himself with the Tesla coil (chapter 9.8).

The open question, how land surveying should be possible with a Tesla coil, we at first still have to shelve, because in this chapter it concerns the way towards free energy and the chance to learn of nature. Examples to be looked at are on the one hand the core of fusion in the inside of the earth and on the other hand the humus layer on the surface of the earth, which has been materialized in the course of time with the help of photosynthesis.

The goal seems to be worth striving for. If we in the first place have learned to produce energy exactly like nature, then we'll further try to produce matter purposeful, with which ageold alchemist dreams could be fulfilled. We wouldn't need to scrape and to search in some mines any longer. We would materialize the products without refuse, naturally and just for the environment, direct in the final form. I admit that at present it sounds pretty futuristic.

With another example, the lightning and particularly the ball-lightning, the collection concerning the use of free energy in nature shall be completed.

---

[i] U. Luttge, M. Kluge, G. Bauer: Botanik, 2. Aufl.- Weinheim, VCH (1994) ISBN 3-527-30031-7, S. 118


Lightning flashes, if the contact has been closed
Lightning between clouds and the earth is distinguished in four groups. But lightning also can be triggered inside a cloud
Tension voltage differences in the cloud arise from ice grains and rain drops
A. Negativer Wolke-Erde-Blitz
B. Positiver Wolke-Erde-Blitz
C. Negativer Erde-Wolke-Blitz
D. Positiver Erde-Wolke-Blitz
A. triggered from the the negative cloud basis
B. triggered if the wind has blown the cloud basis away
C. develops mainly at high points in the open country
D. forms like C. neither C nor D can be explained until now

Fig. 14.11: Concerning lightning.<i>

<i>: taken out of: Illustrierte Wissenschaft Nr. 8, August 1995, Das unverstandene Phanomen der Blitze, S. 13

14.11 Lightning

Lightning is a spectacle of nature just as imposing as unsolved. It concerns an electric process of discharge, in which to the amazement of all experts arrive for several powers of ten more charge carriers at the surface of the earth, than hefore were contained in the cloud! Furthermore unsolved is, why lightning glows. Let us start with the open question for the difference of potential necessary so that the air is ionised and a lightning channel is formed.

If at first the electric tension voltage of 200,000 volts between the surface of the earth and a height of 10 kilometres is available, which according to our calculations results from the rotation of the earth and the magnetism of the earth (fig. 11.8). Another source of tension voltage is not known. By air movement and supposed processes inside a cloud locally an additional accumulation of charge carriers may occur, so that in the case of a thunderstorm the by Tesla assumed, twice as big value doesn't seem unrealistic<i>.
On the other hand a tension voltage between 4,000 and 10,000 volts is necessary so that a blow can occur for an air gap of one centimetre depending on the atmospheric humidity<ii>. Linearly projected the thunderstorm cloud theoretically should hover just one meter above the earth if there is lightning.
Here somehow a huge gap gapes between theory and practice!

At the latest at the spikes, the mysterious lightning, which strike out of a thunderstorm cloud upwards in the direction of the ionosphere and the still more mysterious ball-lightning it has to get clear, that the actual source of tension voltage of a lightning by no means is known. Without knowledge about the cause we'll never understand lightning.

The potential vortex theory offers an useful approach, according to which the necessary difference of potential is formed from a formation of vortices<iii>. The vortex again, as damping term in the wave equation, occurs as a result of intense sun irradiation. That explains why lightning always strike from the part of a cloud, which is the darkest, where the most sunlight is absorbed and the damping is the largest.

The possible formation of ice in a lightning channel is a further confirmation for the correctness of the vortex explanation. After all it has been derived that contracting potential vortices withdraw heat in principle (fig. 12.8).

But now we also want to know from this efficient theory, why photons and electrons are formed during the lightning and where they come from. Here obviously energy is formed by means of materializing of vortex particles.

<i>: R. L. Clark: Tesla Scalar Wave Systems, The Earth as a Capacitor, The Fantastic Inventions of Nikola Tesla, ISBN 0-932813-19-4, S. 265

<ii>: Karl Kupfmuller: Einfuhrung in die theoretische Elektrotechnik, Springer-Verlag Berlin, 12. Auflage 1988, ISBN 3-540-18403-1, S. 221

<iii>: K. Meyl: Potential vortices, Part 1: Discussion contributions to the natural scientific interpretation and concerning the physical-technical usage, basing on a mathematical calculation of newly discovered hydrotic vortices, (only in german) INDEL GmbH, Verlagsabteilung, Villingen-Schwenningen 1990.



Fig. 14.12: Contemporary representation, how 1753 lightning research scientist Prof. Richmann is struck deadly by ball-lightning in his laboratory.<i>

<i>: Illustrierte Wissenschaft Nr. 8, August 1995: Das unverstandene Phanomen der Blitze, page 13

I proceed from the assumption that lightning collects and converts neutrinos. The process corresponds to the one at the sun, but on a smaller scale and only for a very short time. The lightning channel is polarized by the charge carriers. Change of temperature and field lead to a spatial oscillation, which by the way also functions as a source of sound, as anyone can hear. Taken both together lightning, seen from the outside, becomes an unipolar resonator, which is capable to attract neutrinos and to go into resonance with them. Now the predominant part is converted into electrons, because also the air molecules and air ions in the lightning channel belong to the world of matter. But it can't be avoided that a small part of antiparticles is formed, which then annihilate with particles of matter under emission of radiation. Doing so photons are emitted and lightning glows, as anyone can see!

14.12 Ball-lightning

If in the case of lightning there still exist excuses, the difference of potential preferably is traced back to neither understandable nor measurable processes inside a cloud, then at the latest in the case of ball-lightning most experts are at their wits end. Only for very simple natures explanations circulate in the direction that here for instance the organic remnants of a bird struck by lightning are burnt off.

Actually ball-lightning is observed very seldom. It is a ball flashing with reddish till blue-white colour. Its diameter lies between 10 and 50 centimetres. The glowing phenomenon can last several seconds to minutes. Doing so ball-lightning rolls over a street, temporary floats in the air, goes apparently unhindered through every wall and disappears from time to time without a trace or discharges with loud moise and formation of sparks. Some stink of poisonous gases and some also cause noise.

Famous has gotten the ball-lightning, which 1753 of all people should have struck the lightning research scientist Professor Georg Wilhelm Richmann in St. Petersburg. In his laboratory during a thunderstorm a ball of fire as big as a fist should have jumped from a iron tube to his head and should have hunted him down, so eye witnesses have reported (fig. 14.12).

Since ball-lightning has a closed structure, it has to drag about its source of energy with it. If this however consists of organic or other matter, the ball wouldn't be able to float, after all the brightness of a spherical vortex and with that the need of energy is enormous! We have to proceed from the assumption that just ball-lightning covers its need of energy from free energy and serves itself from the neutrino field.

The spherical form is a consequence of the structure shaping property of the potential vortex[ii]. Scientists are increasingly interested in this not understood phenomenon. In their experiments they try to artificially produce ball-lightning with more or less great success in the laboratory. By means of the experiment they then want to learn to understand, what the textbooks don't give away.

If we want to learn of nature something about free energy, lightning in the laboratory offers us in the form of a blow or of a spark gap relatively good possibilities. It surely is no coincidence that the father of free energy, Nikola Tesla, in his experiments almost all the time has worked with spark gaps!

[ii] for that see in the 1st part the chapters 4.8 till 4.10



Fig. 14.13: Fork bent by „pure manual work".[i]

[i]: Whoever has to eat with bent flatware in the Hotel Adler in Waldkatzenbach (Odenwald, Germany), mustn't believe that the food didn't taste well to some rude fellow here. It is the host himself, who in a sociable round shows his guests from time to time that he not only can cook well. I could personally convince myself from the fact that Robert Hartmann doesn't use any aids. The picture shows the title page of the magazine „Wetter Boden Mensch" 4/97. A comment concerning this on page 3: Robert's 50ieth birthday.

14.13 Discussion concerning the neutrino conversion

In nature two different principles for the use of the neutrino radiation can be observed. In one case of use a glowing phenomenon occurs, in the other cases not.

The glowing lightning should be assigned to the first case. Here not only the neutrinos crossing the lightning channel are used, but also neutrinos from the environment oscillating in resonance are collected. Around the lightning channel a kind of reaction radius is formed, inside of which all synchronously oscillating neutrinos are attracted under the resonant interaction. During the discharge process the radius can increase like an avalanche, to collapse again with the transition into the stationary discharge current. A corresponding technical concept, which is discussed in the next chapter (15.5), is very efficient, but almost uncontrollable. A characteristic is the formation of antiparticles, of positrons, in the course of the materialization, which then annihilate under emission of radiation and cause a shining. Also spark gaps and fluorescent lamps possibly help themselves from the neutrino field, as still has to be to worked out.

In the second case nature works without any avalanche effect and without any glowing phenomenon. To this counts for instance the photosynthesis or the mode of operation of the mitochondria, the energy centres of a cell. All cells, whether vegetable, animal or human, only use the neutrinos which just that moment pass by them and only in those amounts, as they just are needed. They thus handle their energy very caring. Without exception electrons are materialized and no positrons.
If nevertheless unwantedly an avalanche effect occurs, something which happens fortunately only very seldom, then a self-inflammation and self-burning occurs, then it should happen, that a person burns off himself<ii>. This risk also is known of hay.

There also exist rare talented persons, who can control and regulate the process of materialization by concentration. These people can bend spoons or other metallic objects<i>. For that they concentrate themselves some time and send the materialized charge carriers into the object, which they hold in their hands. Since the metal lattice solely is kept together by the enveloping electrons of the individual atoms, the additional electrons make the metal structure sodden. Now for a short moment the metal can be bent and distorted at will. Doing so neither heat is produced nor is the colour changed. The result of the process can be produced neither by cold working with raw force nor under a flue. Also here nature shows us a technology for an ecologically compatible metal processing (fig. 14.13).

The way from the conventional over the regenerative towards free energy is predrawn. It only has to be gone! After the existence of the neutrino radiation goes as proven and 1998 for the first time concrete amounts have been determined measuring technical and published by a Japanese team of research scientists, with that also the question for an energy technical use of the particle radiation has been answered clearly. Now only the question of the mechanics is open. The Japanese research scientists by the way have found out that at night only half as much solar neutrinos can be detected than at daytime. The other half according to that is absorbed in the inside of the earth. This in the meantime published measurement result in brilliant manner confirms the working hypothesis of a growing globe (chapter 11).

<ii>: Zu Asche pulverisiert, Illustrierte Wissenschaft 6/ 1997, S. 61 acc. to an examination of the American SCI-COP in 1984.

cause/ field lines	interaction	F = force effect *mediation:*	**see chapter:** effect/ *application*
1. open **H**-field lines	magnetic (static)	F_{M0} = magnetic force (permanent magnet)	**chapter 15.4** *E.-engine, solenoid*
2. open **H**-field lines	resonant (oscillating)	F_{MS} = magnetic force (AC-magnet)	**15.4 + 15.5 - 15.7** lightning, *railgun*
3. open **E**-field lines	electric (static)	F_{E0} = Coulomb force *by charge carriers*	**15.9 + 15.10** atomic bond, *Testatika*
4. open **E**-field lines	resonant (oscillating)	F_{ES} = Coulomb force *by neutrinos*	**chapter 16 + 17** weak interact. galaxy bond *Tesla converter*
5. closed **H**-field lines	gravitation (static)	F_{MG} = gravity *by particles with mass*	**chapter 6.9 + 7** elementary particle mass
6. closed **H**-field lines	levitation (dynamic)	F_{ML} = reduced gravity	**chapter 18.3** gravit. waves *Casimir effect*
7. closed **E**-field lines	gravitation (static)	F_{EG} (force hardly detectable)	**chapter 18.7** *superconducting ring*
8. closed **E**-field lines	levitation (dynamic)	F_{EL} (no longer detectable)	**18.5 + 18.6** *Keely-/Searl-flying devices*

electromagnetic and resonant interaction		gravitation and levitation
$F_{M0} = 1{,}4 \cdot F_{MS} > F_{E0} = 1{,}4 \cdot F_{ES}$	$\gg$	$F_{MG} = 1{,}4 \cdot F_{ML} > F_{EG} = 1{,}4 \cdot F_{EL}$
for reason of open field lines		resp. closed field lines

Table 15.1: The force effect of interactions, ordered according to size, with examples

15. Principle of functioning of space energy

In this chapter we want to turn us towards the technical concepts and techniques concerning "space energy", which occasionally here and there already should have existed or have been operated with quite different success. After Nikola Tesla having pointed the direction more than 100 years ago, the way towards free energy appears to be predrawn. Never before the public interest in the topic of space energy was as big as today. Unfortunately this concerns more the collecting and gathering of rumours and speculations. As in every branch of science also here hunters and collectors can be found. But obviously the hunters, the inventors and theorists have bigger problems, to put something useful on the table. They are fighting against their own not knowing, unuseful textbooks, general ignorance, intolerance and an all-powerful energy lobby. What the collectors on the other hand come up with does make appetite but not full.

An useful and efficient theory might be the most important prerequisite just with regard to the reproducibility of an effect and the product liability of a SET-device. That's why one mustn't expect a complete list of devices of that kind in this chapter, because in the foreground stand the physical and technical explanations concerning the way of functioning, the understanding for constructive and guiding details and the learning from the mistakes and errors of the inventor.

For a better survey the possible courses of the field lines according to the theory of objectivity are listed in detail (table 15.1) and discussed from the top one after another, starting with the strongest known interaction. To complete examples and concepts are presented.

As is well-known there exist electric (E-) and magnetic (H-) field lines. Further exist open and closed field lines and finally is distinguished between the oscillating and the static case. The results are two to the third power, thus eight possibilities of combination in total. In table 15.1 all eight versions are given, even if one or another case is of more theoretical nature. For the objective of a systematizing of different concepts concerning space energy technology the taking apart in any case is helpful. The figure opposite is survey and structure at the same time for the following chapters.

15.1 The course of the field lines

In chapter 6 a relation between the course of the field of a body and its observable interaction has been made (part 1, chapter 6.7 till 6.9). Here a point of approach is offered. For instance to maximize the force effect a magnet or to optimise an electric motor, the engineers nowadays help themselves with costly programs working according to the method of finite elements. In this way they obtain a picture of the field lines, the course of which makes possible conclusions concerning the production of force or torque. The relation without doubt is given, the only question is in which order of magnitude.


for like poles:
repulsion
for uncharged bodies:
no influencing of field lines
for unlike poles:
attraction
E, H ~ 1/a²
(15.1)
a (distance)

Fig. 15.2 A: The course of the field lines leads to a force effect (repulsion or attraction)


repulsion
like poles
attraction
unlike poles

Fig. 15.2 B: The course of open field lines

$$\boxed{\frac{F_{\text{Coulomb force}}}{F_{\text{magnetic force}}} = \frac{Q \cdot E}{\phi \cdot H} = \frac{\mu \cdot Q^2}{\varepsilon \cdot \phi^2}} \quad \text{with} \quad E = Q/\varepsilon \cdot A \quad \text{and} \quad H = \phi/\mu \cdot A \qquad (15.2)$$

i.e. e^-: where $\phi^2 = m^2 \cdot G \cdot 4\pi \cdot \mu$ (Gl.13.20)

$$\boxed{\frac{F_{el}}{F_{magn}} = \frac{e^2}{\varepsilon \cdot m_e^2 \cdot G \cdot 4 \cdot \pi} = \underline{4{,}2 \cdot 10^{42}}} \qquad (15.3)$$

Fig. 15.2 C: The proportion of forces at the example of the electron.

The theory of objectivity answers the question from the equations of transformation with the proportion 13.23 (fig. 13.4). According to that the electric or the magnetic field strength stand in inverse proportion to the square of a length or of a distance:

$$E, H \sim 1/a^2 \qquad (13.23) \text{ bzw. } (15.1)$$

Less mathematically expressed this, for two bodies in the distance a, where one body is situated in the field of the other, means nothing else as that the distance is reduced. Nearer to the body the density of the field lines again increases, in that way the distance further decreases and we observe an approximation.

Usually the idea of force is introduced as a factor of description and there is spoken of a force of attraction. But that not necessarily is required, because the force only represents an auxiliary description. The cause for the observed attraction rather is the spatial distribution of the field strength.

In this case the two bodies come closer and the mutually active fields get bigger and bigger, until the parts eventually run into each other (fig. 6.7 A). There one comes the thought to increase the force of attraction by an artificial compression of the field lines. In the case of the electromagnetic interaction such a compression actually takes place, since the field lines arise from one pole and end at an unlikely charged pole, which so to speak collects and bundles up the field lines (fig. 6.8 A).

At last we find out the reason, why electromagnetic forces of attraction are bigger than gravitational forces for many powers of ten (between 10^{30} and $4.2\text{-}10^{42}$ for the electron, derivation see fig. 15.2 C)! For table 15.1 this means, at the top have to stand the open field lines, which bundle up at the poles. Then very long nothing comes and after that the effects of closed field lines are being found.

For open field lines however also the opposite of a bundling up is possible. In the case of like poles the fields run away of the other pole (fig. 6.8 B). Between both a space is formed, which is free of field lines, where thus the field tends towards zero, whereas the distance between the poles according to the proportion 15.1 grows towards infinity. In this case we observe, how the bodies are going away from each other. We speak of a force of repulsion, which actually reaches until infinity. This gives reasons for the occurring of both forces of attraction and forces of repulsion in the case of the electromagnetic interaction.

15.2 Gravitation

In the case of closed field lines in principle no repulsion can occur, since no pole, neither north pole nor south pole, neither positive pole nor negative pole is able to influence the position of such a field line. This circumstance as well as the order of magnitude of a possible force of attraction suggest, to settle gravitation here.

It gladly is forgotten, that the field pointers of E- and H-field normally occur together and like in the case of the electromagnetic wave stand perpendicular to each other. It is normal to calculate only the electric field pointers for a charge carrier, without paying attention to the circumstance that the H-field is present as well. The textbooks as a rule remain silent about this dark chapter or they lapidary remark, the dual field lines are closed in themselves and hence inactive anyhow, which however is incorrect.



Fig. 15.3: The transition of an oscillating into a static interaction

But, according to the proportion 15.1, they actually develop a force of attraction, even if this is relatively small. No one really needs to be surprised that gravitation is not understood until today, if a whole group of fields simply is overlooked by science! We now also can explain, why there don't exist any massless charge carriers. Namely only the E-field or the H-field can form open field lines and never both at the same time. Otherwise they wouldn't be able to stand perpendicular to each other anymore. The each time other field, in the case of electrically charged bodies it is the H-field, then is wrapped perpendicularly around the E-field lines, independent of the circumstance if electrically an attraction or a repulsion occurs and without exception it forms a weak force of attraction, the gravitation.

15.3 Systematizing the interactions

Next we should know, from which field is to be expected a larger force effect: from the E or from the H-field? At the example of an electromechanical converter this question can be answered concretely.

The forces which occur and form the torque in an electric motor customary in trade are produced by magnetic poles in stator and rotor, which repel each other in the case of like charge and attract each other in the case of unlike charge. Now there in principle exists the possibility to build a motor which works with Coulomb forces, thus with positive and negative poles, instead of the magnetic forces. About such designs numerous patent specifications exist, but no customary version on the market.

The reason very simple is that a magnetic motor for the same torque is many times smaller and better priced. From this the conclusion can be drawn that for the same construction volume a magnetic force F_M is considerably larger than a Coulomb force F_E, which for instance binds together atomic nucleus and atomic hull.

Thus in table 15.1 the magnetic forces are ranked before the Coulomb forces.

Finally we have to distinguish between the static and the oscillating case, which are distinguished in the frequency. In fig. 15.3 an oscillation is shown, which by chance just at the moment of the vertex value changes into the steady state, thus takes the frequency zero. In this case the effective values between a static and a sinusoidal oscillating interaction are distinguished by the factor $\sqrt{2} = 1.4$.
If we operate an universal motor with direct current, then it releases more power, than for a corresponding feeding with alternating current. Even a high-tension line, which stands at maximum 511 kV, is operated with alternating current up to 380 kV, with direct current on the other hand up to 500 kV. Consequently in table 15.1 the static interactions stand before the oscillating interactions.

The strong interaction naturally isn't found in the list, after it has been derived that it doesn't exist at all (see chapter 7.8), whereas the weak interaction is hiding behind the oscillating interaction. It shakes other particles so long till they fall apart (see chapter 7.13).

We now would be as far, to discuss the 8 cases listed in table 15.1 one after another by means of practical examples.

The principle of the side-pole machine



Fig. 15.4: Alternating current dynamo, according to the inventor (Kromrey) a magnetic converter for free energy with a degree of effectiveness of more than 100 %.[i]

---

[i] Raymond Kromreys Molekularstromrichter, NET-Joumal 6/98, S. 5

15.4 Magnetic force converter

As a result of the systematizing of all eight possible interactions, the largest force effects are to be expected as a result of static and of open magnetic field lines. It is questionable, if this statement is generally valid and is true everywhere in space. But it is valid at least for a terrestrial laboratory and only here, on earth, a solution for the energy problem is strived for. No wonder therefore, if the electric energy technology nearly without exception is using these force effects. We find them at a solenoid, at a relay coil, at a magnetic tuning cylinder and equally between the stator field and rotor field of an electric motor.

The motor however takes a special position, because its rotor is turning. In that way a switching of the winding and commutating of the currents is necessary or the field of the stator winding is being turned, for instance in the case of an alternating current motor. This is necessary, so that in the air split of the motor the fields from the stator and rotor always are standing opposite like for the solenoid and a driving force can be formed. For the operation therefore oscillating currents are necessary, so-called alternating currents, which are fed in into the winding with the right frequency and phase. There can be spoken of an operation in resonance. It surely is no coincidence, that Nikola Tesla, the founder of the rotary field theory and inventor of the alternating current motors at the same time is the discoverer of the neutrino radiation!

The electric motor slides already into the second column from the top in table 15.1, as we see, and should be assigned to the case of the oscillating interaction of open magnetic fields. The frequency for motors usually is very small.

But also at high frequencies there can't be reckoned on some free energy which would show or even be utilizable, as can be heard from the inventors who tinker with magnets, mostly with permanent magnets (Fig. 15.4). The reason very simple is that there exist no physical particles, which could mediate this interaction. Magnetic monopoles would be necessary, thus north pole or south pole particles, so that an interaction with the open H-field lines can occur.
Such particles could form as a result of currents and eddy currents, but for that a good conductivity would be necessary and that isn't present in the vacuum. Therefore magnetic monopoles can't exist at all! This point we already had worked out (fig. 4.4, question I). The same statement then also applies to the oscillating case.

If nevertheless something like free energy should show in the case of some magnetic field converters, then unnoticed by the inventor still other physical effects are added. By means of concrete concepts this circumstance can be studied and discussed. The meanwhile well-known railgun is a corresponding example, for which besides the used magnetic force unintentionally a further principle is used. A more detailed occupation with this device is worthwhile, because here some fundamental concepts of space energy get clear.



A: Shining railgun in action<i>

B: Structure<i>

C: Concerning the way of functioning of the railgun

current i
B: flux density
rails
Lorentz force
i
projectile
q·(v × B)
i
B
pulse generator
slide (short-circuit bar)

Fig. 15.5: Structure and way of functioning of the railgun

<i>: in the internet under: www.glubco.com/weaponry/railgun.htm

15.5 The railgun

The engineers and physicists involved in the SDI-project were quite astonished, as they had a close look at the bent rails of their gun. During the test operation the equipment was really flying around their heads.
They were very sure to only have fed in 16.7 MJ of energy, from the rotation of a homopolar generator, because more was not available for the experiment by any means. The projectile with mass m_0 = 0.317 kg lying on the rails thereby should have been accelerated to the velocity of 4200 m/s. Instead huge forces were at work here, which the construction couldn't counteract at all. There is talk about the released energy having amounted to 399 GJ, what corresponds to an over-unity effect of 24000<ii>. This factor describes the proportion of the released to the taken up power or energy.
If these details should be correct then this would be the most efficient converter for free energy, which has been developed until now.

Behind the project name SDI (Strategic Defence Initiative) is hiding the by the United Slates prepared "Star wars". But how one fares a war, which nobody can pay anymore and no-one wants, entirely according to the motto: There is a war and no-one goes there? This war undoubtedly the strategists and initiators themselves have lost, who even had to watch, how their space gun appears in the internet with design drawings and rich visual material to be called by anyone<i>.
Today, where we are surrounded by nothing but friends, where in Russia and at other potential opponents is fought more against internal problems and one lets the expensive space toy rot for lack of money, the coat of the military secrecy obviously no longer can be held over such an explosive project as the railgun.

Thus informative details have reached the public. In the pictures a bright lightning can be seen at the moment of launching (fig. 15.5 A). Here presumably is being materialized, in which the part of anti-matter annihilates with the particles of matter under emission of light. There thus takes place the same process as in the case of lightning or the shining of the sun.
In addition is being reported that heat energy is withdrawn from the environment, a circumstance, which is typical for all functioning converters for space energy. We thereby are reminded of the possible formation of ice in a lightning channel.

Like for a lightning also the railgun is stimulated with a very high excitation voltage and with extreme speeds of change of the tension voltage (high du/dt) (fig. 15.5 C). From the setup it concerns a bridge of Ampere, which in various respects appears to be superior to the rocket engines, after the costly transport of the propellant into space isn't necessary, since the capacitor batteries can be recharged by solar power.

<i>: e.g.: www.glubco.com/weaponry/railgun.htm

<ii>: Galeczki, G., P. Marquardt: Requiem fur die Relativitat, Verlag Haag + Herchen (1997), S. 139


A:
magnetic field B_A of a conductor through which current flows
B_A
B:
constant excitation field B_E
N
B_E
S
C:
conductor in the excitation field
N
F
B_{sum}
S
D:
force effect F on a conductor through which current flows
excitation field
B_E
force
F
current flux into the plane of drawing
(left hand rule)

Fig. 15.6: ____ The distribution of field lines and force effect on the slider of the railgun through which current flows in a permanent magnetic field

The projectile has the form and the function of a short-circuit bar and is guided slidable between both rails of the railgun. The high-tension capacitors are switched on both rails at the moment of launching, so that in a very short time an extremely high short-circuit current of several thousands of Ampere flows through the bar.
Since the bar in addition is situated in a static magnetic field, there acts an accelerating force on it (fig. 15.6 D). It is the force effect of a conductor through which flows a current in a magnetic field, like it is active in every electric motor. If we overlap the fields of the conductor (fig. 15.6 A) and of the magnetic field (15.6 B), then we observe a bending and lengthening of the field lines (15.6 C). There exists the effort to re-establish the original state, which represents the smallest magnetic resistance, and for that the conductor is shifted out by means of the arising force. In the sketch it is accelerated to the left. That far the explanation concerning the bridge of Ampere. That has nothing to do with free energy. For the enormous degree of effectiveness, as it has been determined, further effects have to be added.

15.6 Unipolar induction

The projectile, or from the function let us rather speak of the short-circuit bar or the slider, at first is entirely conventionally accelerated and experiences, mathematically expressed, a dv/dt. The magnetic field B stretching perpendicular to the movement is constant, so that according to the Faraday relation<i> E = v x B from the velocity v an electric field strength E results and from the acceleration dv/dt a field change dE/dt. These open field lines along the length of the slider, in particular the oscillating part, appears to interact with oscillating particles and to collect these particles<ii>. It concerns presumably neutrinos, which primarily materialize in charge carriers. These contribute to the current flux in the slider and to the acceleration, whereupon still more neutrinos are collected.
A hardly controllable avalanche effect is formed. Only if the change in tension voltage has worn off and the capacitor is completely discharged, also the resonant interaction will again collapse.

The inventors, who want to construct a civil version of the railgun, is given a warning on the way which should be taken seriously. At first it doesn't take particularly much imagination to imagine a rotating arrangement of the gun, a construction with one axis, whit which a generator driven, which produces power. A small part is supplied the system again as supply for itself. The rest would be available free to the consumers as non-polluting, regenerative energy.
That really sounds good, if there wouldn't be this one obstacle.

<i>: The equation of transformation concerning the unipolar induction already was treated more detailed in chapters 6.4 and 9.3

<ii>: It is the resonant interaction according to table 15.1, line four


„Neutrino sea"
ν −/+
ν +/−
(+/−)
(−/+)
slide
S
N
magnet
rail:
outward
current
rail:
current
back
switch resp.
spark gap
high-tension
capacitor

Fig. 15.7: The collecting of neutrinos by oscillating open field lines

15.7 Tendency to instability

In a continuously working machine the discharging of the capacitor cannot remain a single event as in the case of the gun. The discharging and the recharging has to take place cyclic depending on the revolutions per minute. To obtain a rotating movement even to a certain extent ignition has to follow ignition. But if the new ignition takes place, although the avalanche effect of the last one still hasn't worn off, then inevitable a catastrophe will occur, then the work of wonder is taken apart under the eyes of its creator. Numerous inventors already have had to collect such painful experiences. It is assumed that not even Nikola Tesla had escaped, as he had to put away again his stately luxury car with electric motor and energy converter in a barn near Buffalo already after one week of test operation in the year 1931<i>.

Of course also for this problem solutions in accordance with engineering are offered. Meaningful would be a restriction of the revolutions per minute and a power regulation. Only most inventors don't think that far. On the one hand, because they handicraft without an useful physical model and on the other hand they think they already have reached the goal, if they observe something like free energy for the first time. Just as fast as the joy then the disillusionment comes, because a converter which doesn't work, is not able to convince anyone.

Tesla already was aware of this set of difficulties. He fastened his converter to the dashboard and not in the engine compartment, presumably to adjust the coupling of the coils from the drivers seat during the drive by means of two metallic rods, which he pushed into the case. But sometime even this regulation by hand has to go wrong, because the collected neutrinos on their part collect further neutrinos (fig. 15.7), so that in the case of an unfavourable order of ignition an additional amplification is possible. For a reliable operation according to that directly or indirectly the phase of the ignitions to each other should be checked.

At the example of the railgun space energy technologists and inventors can study the relations and the way of functioning very concretely and even calculate these relatively simple. It is a big relief, that all three vectors stand perpendicular to each other: the E-field, the B-field and the velocity v. Ideal conditions both with regard to a maximizing of the wanted accelerating force and for the resonant interaction, increase at the same time the collecting of space quanta, which probably may be set equal to the neutrinos. This is made possible by the Faraday's law of unipolar induction. In that way at the right and left end of the slider a positive a negative pole each are formed. The further the two poles are away of each other, the more the field lines are opened and the more neutrinos can go into resonance. In this place still considerable improvements and optimisations are possible.

In addition to the two discussed the phenomenon of the electrostriction is added as a third phenomenon, which authoritatively contributes to the conversion of neutrinos into electrons. It is a field dependent change of length, which in the case of lightning takes care of the thunder and in both cases, therefore also here, is active as a charge carrier producer.

<i>: see also chapter 9.5 Free energy,
A. Schneider: Energien aus dem Kosmos, Jupiter-Verlag 1989, Kap.11, S. 20 and H. Nieper: Revolution, MIT-Verlag 1981, S. 194

A: electric dipole (e.g. electrostatics, see also fig. 6.8)



B: electric monopole (e.g. electron e~, see also fig. 4.3)



C: Mixed form in the case of cylindrical symmetry



Fig. 15.8: Dipole fields with unipolar parts

15.8 Unipolar field configuration

If we again go back to fig. 5.1 and continue our considerations with examples concerning line 3. The obtainable force effect of open electric fields indeed is for powers of ten smaller than that of magnetic fields, but then particles are mediated, an invaluable advantage and an indispensable prerequisite with regard to the generation of space energy. As long as the particles are considered in the balance sheet of energy then in addition by no means can be claimed, space energy converter are perpetuum mobiles.

In the question, why only electric particles can be mediated, has to be pointed to the repeatedly mentioned circumstance that only electric particles can be formed as a result of the concentration effect of potential vortices. Magnetic particles however plain and simple cannot exist, since for missing conductivity in the vacuum no eddy currents are possible (see fig. 4.4).

In the case of the arising Coulomb forces again is distinguished between the static and the oscillating case. We want to start with electrostatics.

The range of technical applications of static electricity is large. It stretches from varnishing technologies and filter technologies till the fly grill in the arbour. In all cases the field is built up by charge separation. By means of a high-tension generator a positive pole and a negative pole are produced, between which the field is stretching. The field lines now start at one pole and end at the other, unlike pole (fig. 15.8 A).

In this manner almost no open field lines are available, which point to the outside and could interrelate with free particles. If one for instance intends to attract and collect charged particles from the solar wind, from the cosmic radiation or from the electricity of the air, then the design in one point has to be changed fundamentally.

A unipolar field configuration is necessary. What is meant with that, answers a glance at the spherical vortex model of the electron (fig. 15.8 B resp. fig. 6.2). Here it as well concerns a formation of dipoles as a result of the charge separation, but one pole is hiding in the inside of the other pole . In that way its field lines are captured and don't have a chance anymore to come out, to reach the other pole.

But if the pole lying on the outside for its part can't close its field lines any longer, then these point helpless into space and search in their neighbourhood, in the distant world and if need be even in the infinity of the universe an unlike anti-pole, which as a result interacts and is attracted.

The measuring technician analyses these open field lines and falsely calls the construction then a monopole, only because he isn't able to reach the locked up pole. To blame is the unipolar field configuration, which with that probably would be explained to a certain extent.

The designer and inventor as well might have realized how he has to construct his device, with which he generates open field lines to collect space quanta. He has to lock in one of the two poles as good as possible. Optimal would be of course a spherical symmetric construction like in the case of the elementary vortex. Compared with that a cylindrical symmetry indeed is suited far less good, but it offers constructive advantages (fig. 15.8 C).

We now will report of such a functioning device.



Fig. 15.9: Demonstration converter "Testatika".<i>

<i>: A. Schneider: Energien aus dem Kosmos, Jupiter-Verlag 1989, S. 29,
I. Schneider: Neue Technologien zur Freien Energie, Jupiter-Verl. 1994, p. 13 and in the NET-Journal, Heft 8/9, 1997, S. 16 as well as iss. 12, 1997, p. 6.
D. Kelly. Der Schweizer ML-Konverter, Raum & Zeit Special 7, S. 164

15.9 The Testatika

An electrostatic device, which produces open electric field lines, is situated in Linden in Switzerland. It optically is very imposing and belongs to a religious community, which has called it Testatika and is of the opinion that it is a free energy converter. Inexplicably the Testatika does not serve the community, which generates their electric power conventionally and to a large extent by itself, as a source of energy. Instead the 2 kW device only very seldom is demonstrated for special occasions or to select groups of visitors. The religious community after that explains the astonished observers humanity not yet is mature for the technology.

Perhaps just the opposite is correct and the technology not yet is mature. According to my personal assessment such an electrostatic device in principle is entirely unsuitable for the continuous operation.

It can be expected that the open field lines sooner or later will interrelate with the electricity of the air and thunderstorms are being attracted by the infernal machine so long until lightning strikes and the demonstration with that has finished. That's why the Testatika may be switched on only for a short time, only at sure weather situation and not too humid air, and many a registered visitor has been sent away without having seen the "thunderstorm machine".

As an object of demonstration and study the Testatika however is well suited. Alone the circumstance that no cable leads to the device and it nevertheless releases energy in the order of magnitude of 1 till 2 kW, surprises all visitors. At least the impression is mediated as if the machine would violate the law of conservation of energy, which is not correct. The Testatika is similar to an induction machine, which works with friction electricity. Thereby the unlikely charged bodies do not have to unconditionally touch and rub at each other, it already is sufficient, if they are brought in the immediate vicinity of each other. In the case of the Testatika the electrostatics of two against one another rotating discs is taken off by brushes.

The excitation energy presumably is taken out of the natural E-field, which just like that can amount to 200 Volts per meter (see chapter 2.9). The large diameter of 80 cm of the discs and their bad conductivity (acrylic glass) permit this conclusion. The charge taken off by the brushes afterwards is temporarily stored in two capacitors of 2 Farad at 300 Volt, so-called Leyden jars. This far one actually is reminded of a Wimhurst generator, in which the energy is supplied the system by turning the disc. Large powers cannot be drawn by that. Plans to build such an induction machine by yourself have been published<i>.

In the case of the Testatika however two discs are used and by hand stimulate to rotate oppositely. This rotational energy in this case isn't used to produce power, otherwise the discs quickly would stand still again, but that doesn't happen.

Until now apparently no-one has discovered the secret, which is kept strict by the members of the community. In my opinion the energy situation on our earth however is too serious, as that we would be able to afford playing hide-and-seek and egoistical secretiveness.

<i>: I. Schneider: Neue Technologien zur Freien Energie, Jupiter-Verl. 1994, S.14


STANDARD WHIMSHURST CAPACITOR
TWIN DISK
STEEL SEGMENTS FOR 60HZ DC OUTPUT AT 60 RPM
COLLECTOR BRUSHES
POGENDORF MOTOR BRUSHES
SIDE VIEW
HORSHOE PERMANENT MAGNET WITH COIL
HORSHOE PERMANENT MAGNET WITH COIL
DIODE CAPACITOR
low voltage output
HV input
LEYDEN JAR
LEYDEN JAR
SPARK GAP
RADIUM DOPED INDUCTOR-CAPACITOR THAT MAKES NUCLEAR BATTERY

Fig. 15.10: Sectional drawing of the Testatika according to Don Kelly, (Clearwater, Florida, USA)

<i>: Der Testatika generator, NET-Journal, Dezember 1997, page 6 similar picture is found in Raum & Zeit Spezial 7, page 164

15.10 The secret of the Testatika

The crucial point is the opposite direction of rotation of both discs. If we assume the static earth electric field is the cause and serves as an excitation field, then as an effect a field arises, which stands perpendicular to that. The axial component now points out of the centre of the disc.

In the case of only one disc the field lines in front and behind the disc again are closed, so that no open lines can form. With one disc or with two discs rotating in the same direction hence no unknown charges can be attracted.

In the case of two oppositely rotating discs however shows one component along the axis of rotation to the observer, that of the other disc exactly in the opposite direction. In that way between both discs a pole is „pinned", which no longer is able to close all field lines on the outside around the machine. Thus open field lines and a, however incomplete, unipolar arrangement are formed.

The charge carriers sucked from the electricity of the air as a result support the natural electrostatics and speedy recharge the capacitors, even if up to 10 Amperes are taken out by the consumers.

The ingenious thing of the machine is its extremely simple construction and the simple concept.

If one includes the collected particles also in the balance sheet of energy, then it thus will turn out that the law of conservation of energy is not violated at all. There thus can't be talked of free energy. In this context the Testatika may rather be given as a counterexample. Air ions are the carriers of the electricity of the air and not carriers of free energy.

Negative air ions are indispensable for our welfare. One should only remember the first men in space, who after the landing were pulled out of their capsule more dead than alive, after they had to stay in the unhealthy atmosphere of the capsule for a longer period of time. Only the installation of ionising devices for negative air ions made possible longer staying in space.

The taking out of the air of negative ions hence is not unproblematic and not particularly ecologically compatible. An atmosphere harmful to life is formed which Dr. Wilhelm Reich has called DOR-state. He by the way has designed a Cloud-Buster, with which he could take static electricity, forming above the desert sand, out of the air. In that way the negatively charged rain clouds no longer are repelled and driven away. Reich has tested his weather machine 1954 in the desert of Arizona. After he had freed the atmosphere of the „DOR-strain", as he expressed himself, in the desert area the atmospheric humidity steadily increased from 15% up to 95%, there grew prairie grass and everything started to turn green, and eventually after many years for the first time rain fell again.

Static electricity, as far as the right polarity is chosen, may conditionally be used for the mechanics of rain making. For free energy concepts it however isn't suitable. Already Nikola Tesla has pointed to the circumstance that our hopes will be in vain if the free energy would be of static nature (see fig. 9.5). He in his speech, which he gave 1891 before the AIEE, has left no doubt that free energy exists, which is kinetic and with that energy technically usable for us,. Chapter 16 will be occupied solely with this case<i>.

<i>: according to point 4 in table 15.1



Fig. 15.11: The Cloud-Buster of Dr. Wilhelm Reich 1954.<i>

<i>: H.-P. Thietz: Tatort Erde, VAP (1996), ISBN 3-922367-62-3, page 122
<ii>: Part 1, fig. 9.3; concerning the unipolar induction see also fig. 6.5 and 11.8

Fig. 15.11 shows the weather machine of Reich, the Cloud-Buster. It can be understood only hard, why Reich directs a 3-4 m long metallic pipe with a diameter of 4 cm to the sky and connects the rear end with a deep well or with flowing waters. The effect should have been increased considerably with a few milligrams of radium. An indication that he must have worked with static electricity, delivers however a tragic accident, in which one of his collaborators was lamed on one side. He carelessly had touched the charged apparatus and suffered an electric shock<i>.

15.11 The key to free energy

As a contribution to the discussion the individual principles of functioning of space energy again are collected and the attempt is undertook to value them.

In the case of an oscillating dipole configuration, for instance the railgun, open field lines are present only along the mutual line of connection (fig. 15.8 A). With that not particularly many space quanta can be reached. It hence has to be operated with gigantic excitation powers in the range of many thousands of Ampere, so that further field lines fling open and interact. The wanted over-unity effect therefore can only be reached at an enormous expense of technical apparatus.

An unipolar arrangement here is considerably more advantageous, where holds: the more unipolar, the fewer excitation power is required. But in that way it can take longer until the collecting of neutrinos like an avalanche again has worn off. In the case of an ideal spherical arrangement (fig. 15.8 B), as the ball-lightning takes, the process can even last for minutes. This explains why unipolar systems can be kept under control only very hard. If the neutrino avalanche is rolling then it purely theoretical only can be stopped with a still larger excitation power, for instance by phase shifting, what can hardly be realized in practice. The rolling avalanche can't be stopped anymore by normal means. A synchronous operation between the neutrino oscillation and the converter can, apart from the technologically hardly realizable high frequency, by no means really be recommended. As a rule one single steep flank of the change of the excitation voltage is sufficient to start the avalanche. By means of the repetition frequency or by means of the duty cycle of the excitation voltage then resonances to the neutrino field can be made or avoided. On the other hand can't be done without the avalanche effect. The utilizable power of the neutrino converter otherwise would be much too small. This case should be pursued further in the design of a longitudinal wave gauge.

All converter systems at first work based on a well-known and tried and tested physical principle of functioning. In the case of the railgun it is the bridge of Ampere. The thus used force effect on a conductor through which flows current is advantageous due to the obtainable order of magnitude and as a basic concept extremely recommendable. But also Coulomb forces or other physical principles can be used.

Despite that a further relation still must be added, which produces the interaction with the neutrinos. Closely associated with the unipolar arrangement it is the unipolar induction, which in virtually all space energy concepts is put to use. It already could be shown that the railgun uses the effect as well as John Searl in the case of his flying disc<ii>. The Faraday law of induction turns out to be the key to free energy.


+
V
S N/S N/S N/S N
–
bronze-axis
ferrite ring-like magnets
revolving, conducting ring
ferrite ring-like magnets

Fig. 16.1: The Faraday generator, which with rotating magnets is called N-machine.[i]

According to chap. 6.5, eq.60 the equations of transformation are:

$$\boxed{\mathbf{E} = \mathbf{v} \times \mathbf{B}} \quad \text{and} \quad \boxed{\mathbf{H} = -\mathbf{v} \times \mathbf{D}} \qquad (16.1)$$

where: $\mathbf{v} = dx/dt = v \cdot \mathbf{e}_x$ = component of the direction of motion perpendicular to the area being stretched by the field pointers $\mathbf{H} = H \cdot \mathbf{e}_y$ and $\mathbf{E} = E \cdot \mathbf{e}_z$.

Thus in addition to the basic fields E and H (at v = 0) additional fields E_z and H_z, depending on motion, occur and the overall fields E_o and H_o are measured (which corresponds to eq. 63 in chapter 6.5):

$$\boxed{E_o = E + E_z} \quad \text{and} \quad \boxed{H_o = H + H_z} \qquad (16.2)$$

(which corresponds to eq. 62 in chapter 6.5):

with: $$\boxed{E_z = v \cdot B} \quad \text{and} \quad \boxed{H_z = -v \cdot D} \qquad (16.3)$$

Table 16.2 A: The equations of transformation of the electromagnetic field.[ii]

16. Space energy technology (SET)

It quite concretely concerns the question for a technology concerning the use of the resonant interaction (according to line 4 in fig. 15.1). For that open and at the same time oscillating electric field lines are needed, which mediate neutrinos and pass them on to a receiver working in resonance. The sun, some planets and other celestial bodies, as we already have worked out, use the effect. Even an entire galaxy is kept together in this way. This interaction plays the crucial role for the theme of space energy and the question is asked, with which technology it can be produced artificially.

16.1 The unipolar generator

The most direct way obviously leads over the Faraday relation concerning the unipolar induction. With the classic Faraday generator, where a permanent magnet is turned along its axis, at first a static electric field can be produced. By rotating in opposite direction or magnets rotating in the same direction but oppositely poled, relatively simple one pole can be „pinned" between the magnets and an unipolar construction can be built. Numerous research scientists already have worked in the area of the Faraday machine more or less successfully (fig. 16.1)<i>. There is reported of instabilities and of the picking up of unknown energy at high revolutions per minute. In the majority of the cases it in a sense of the Testatika will concern collected electricity of the air.

The Faraday relation in addition also appears to be hardly understood correct physically by anyone. A scientific magazine in this context takes the opinion: "Faraday proves Einstein wrong", and the production of electricity with Faraday's unipolar inductor violates the laws of physics !<ii>

<i>: A. Schneider: Energien aus dem Kosmos, Jupiter-Verlag 1989, S. 44

<ii>: „Faraday in his experiment did let rotate a copper disc above a resting cylinder magnet; as expected in a loop of wire a tension voltage was created (F-machine). Than he let the magnets rotate, and the disc stood still; now again a tension voltage should have resulted - but there was no voltage. In the third experiment the magnet rotated with the disc in the same direction and with the same speed. Because there was no relative motion between both, an induced tension voltage wouldn't have been expected - but it was measurable! (N-machine, see fig. 16.1).
What does that mean? If the relative movement between magnet and disc is not always crucial for the formation of an induced tension voltage, then also the absolute movement has to play a role - because something has to move, for a current being formed. But an absolute movement according to the theory of relativity can't be detected - thus Faraday's experiment proves Einstein wrong! Therefore you won't find anything about this experiment in the textbooks".

Taken out of the article: Faraday widerlegt Einstein, PM-Magazin 11/ 1998, P. 133

from table 16.2 A:

$$\boxed{H - H_o \overset{(16.2)}{=} - H_z \overset{(16.3)}{=} v \cdot D} \qquad (16.4)$$

with the velocity $v = dx/dt$,
not accelerated $dv/dx = 0$ (inertial system) and derived for x:

$$\boxed{\frac{dH}{dx} - \frac{dH_o}{dx} = \frac{dx}{dt} \cdot \frac{dD}{dx} = \frac{dD}{dt}} \qquad (16.5)$$

The curl of the H-field pointer points in the z-direction:

$$\boxed{\text{rot}\,\mathbf{H} = \frac{dH}{dx} \overset{(16.5)}{=} \frac{dH_o}{dx} + \frac{dD}{dt} \overset{!}{=} \mathbf{j} + \frac{d\mathbf{D}}{dt}} \qquad (16.6)$$

comparison of coefficients with Ampère's law:

$$dH_o/dx = \mathbf{j} \;, \qquad (16.7)$$

integrated over dx and ds and formulated generally valid:

$$\boxed{\oint \mathbf{H_o}\, \mathbf{ds} = I_{ein}} \qquad (16.8)$$

thus follows from that: magnetic field = vortex field!

Faraday's law of induction (analogous derivation):

$$\boxed{\text{rot}\,\mathbf{E} = \frac{dE}{dx} = \frac{dE_o}{dx} - \frac{dB}{dt} \overset{!}{=} - \frac{d\mathbf{B}}{dt}} \qquad (16.9)$$

cause for measurable electric field E_o is missing:

$$dE_o/dx = 0 \;, \qquad (16.10)$$

integrated over dx and ds and formulated generally valid:

$$\boxed{\oint \mathbf{E_o}\, \mathbf{ds} = 0} \qquad (16.11)$$

thus follows from that: the electric field = irrotational (according to Maxwell)!

Table 16.2 B: The derivation of Maxwell's field equations (Ampère's law and Faraday's law of induction) from the equations of transformation of the electromagnetic field

The author of the article proceeds from Maxwell's formulation of Faraday's law of induction, according to which arises a tension voltage in a wire if the wire cuts magnetic force lines, thus is moved relative to a magnet.
If he had read my books, then he would know that Faraday not only has found the older, but also the more comprehensive law, whereas Maxwell only describes a special case. Starting-point for the by me developed theory of objectivity are on the one hand Faraday's law of induction and on the other hand the regularity dual to that, which both together are called equations of transformation of electromagnetism (fig. 6.5, eq. 60 and fig. 16.2 A, eq. 16.1).

16.2 Derivation of Maxwell's field equations

For the derivation we assume, as already in fig. 6.5 for sake of simplicity, that the movement $v = v_x$ takes place perpendicular to the area stretched by the field pointers $H = H_y$ and $E = E_z$. If we derive the equation of transformation, written down for a field component depending on motion, for the coordinate x by using the equations of material and compare the result with Ampere's law resp. Faraday's law of induction, then it becomes clear that the comparison is successful only under certain prerequisites. This circumstance proves that the Maxwell equations only describe a special case and that the equations of transformation are more general valid and causal (table 16.2 A and B).

But in this place is crucial that Faraday's law of induction according to Maxwell only is able to describe a formation of dipoles. For the formation of unipolar field structures however must be fallen back upon Faraday's law concerning the unipolar induction. Whoever wants to understand or even develop by himself concepts concerning space energy, first must have understood Faraday's law in its whole range.

Usually the Faraday generator is, like in the original building shape, equipped with permanent magnets and operated in a steady operating state. Doing so consequently only static electricity is formed. We however need oscillating fields, and for that either the rotation, or the magnet should be changed in polarity with high frequency. Expressed with the precision of mathematics, the first case is described by: $E(t) = v(t) \times B$ and the second case by $E(t) = v \times B(t)$. Both cases have to be investigated and discussed, because both $v(t)$ and $B(t)$ are possible in principle. It is added that in both cases mechanically moving, as a rule rotating, designs but just as well resting designs are conceivable, in which only the moving charge carriers themselves realize the component of velocity v.

This time the crucial point is, that in both cases equally a change of the electric field strength E(t) is produced, with the help of which neutrinos should be collected. Because of the extremely high oscillation frequency of the neutrinos large field changes dE(t)/dt and associated with that large changes of tension voltage dU/dt seem to be the optimal solution, which can be handled with today's technology. Apart from that further difficulties are added, which require a managing in accordance with engineering. If we namely work with a large acceleration dv(t)/dt, then the inertia of the accelerated masses should be overcome, then only very small and light projectiles can be launched like in the case of the railgun. If we however work with fast changes of the magnetic field dB(t)/dt, then the inductance acts slowing down.



A: Suggestion from the patent specification of John W. Ecklin

B: For instance the „Stationary Armature Generator“

59
53
49
57
51
55
61
S
N
N
S
45
47
49
51
S
N
N
S
45
47
57
AC OUT
AT RPM OF
N
S
27
29
31
1
S
6
N
3
27
29
31

Fig. 16.3: Principle of the Ecklin generator.<i>

<i>: A. Schneider: Generatoren mit Ferritkernumpolung, NET-Journal 6/98, S. 9
Ecklin: Permanent Magnet Motion Conversion Device, U.S.Pat. 3'879,622

16.3 SET-devices with rotating magnetic fields

If we again come to speak of the Faraday generator, which can be built up in two variants. In the case of the F-machine the magnets rest and only the disc rotates, whereas in the case of the N-machine the magnets rotate along. In this case can't be avoided that some of the induced charge carriers roam about in the magnets and sensitively disturb the structure of the material. One only thinks of the bending spoon effect!

The consequences stretch from a loss of the permanent magnetism, over a shattering and bursting up to a pulverizing of the magnets. Adventurous rumours and alarming reports in this direction are sufficiently available.

An improvement could be obtained by an isolation layer between the conductive disc and the magnets, but against induced charge carriers inside the rotating magnets this measure is not able to achieve anything.

Anyhow the best thing to do will be to completely do without permanent magnets in neutrino converters! If we replace them at least in our minds by electromagnets, then a feeding with alternating voltage is possible. That also is necessary if oscillating neutrinos and not air ions should be collected.

As a result of the alternating voltage at first large eddy currents occur in the disc. The losses can be reduced by radial slits in the disc. The induced currents then only can, as wanted. flow radially to the outside.

Bigger headaches causes us on the other hand the inductive and with that current storing effect of the excitation coils. If a too large excitation inductance should prevent a fast increase in current, then also the induced electric field will increase correspondingly comfortable and hardly be able to persuade a single neutrino to stay. A coil core of iron or dynamo sheet metal with that is ruled out from the start. Even ferrite would be suitable at most conditionally. Usable are air coils with as possible as few turns. In an advantageous design the slit copper disc rotates between two air coils, if need be flat coils built in the way Tesla did, which are fed with pulsed tension voltage. The highest speed of change in current surely is obtainable by means of a spark gap, like already Tesla has used (fig. 9.1). But also other techniques are thinkable as pulse driving. For instance semiconductor power amplifiers with MOS transistors not only can be switched fast and hard, but in addition frequency and duty cycle can be adjusted freely with reproducible exactness. These are niceties, which will gain importance in connection with the control and regulation of a converter.

Und the heading "generators with magnetic flux variation" Mr Adolf Schneider has collected and commented on some concepts[i]. The generator of the american research scientist John W. Ecklin registered for patent at 22-4-1975 thus stands as an example of a whole group of inventions, in which the magnetic conductivity in the magnetic circuit and with that the flux is changed with a jump.

Fig. 16.3 B shows a building form consisting of two horseshoe magnets (1, 3) with a likewise resting coil in between (6). In rest the magnetic circuit experiences no change and consequently no tension voltage is induced in the coil. The trick is that an axis (31) is pinned right through the arrangement which is turned with two soft iron anchors, which magnetically short-circuit alternating the left (27) and the right (29) horseshoe magnets.





Fig. 16.4: Bedini magnetic converter.<i>

<i>: A. Schneider: Generatoren mit Ferritkernumpolung, NET-Journal 6/98, S.10

Besides the moment of reluctance, which should be compensated by the physical principle, and the friction of the bearing actually no further moment of reaction can occur which would have to be gotten over, not even then if current is taken out of the coil. If the flux change is large enough, purely arithmetically it should be possible to take off an electric power which is considerably larger than the friction power. John Bedini has 1985 measured an over-unity effect of up to 12.6 at a similar constructed generator, where with increasing strain also the factor could be increased (fig. 16.4).

16.4 Commentary concerning magnetic SET-devices

I judge these measurements rather sceptical, after I already in three cases had to break the message gently to the inventors, that their device unfortunately was nothing but an energy destroying machine and they merely had measured wrong, where admittedly the measuring of pulsed tension voltages and currents is not quite simple. So that you don't become a victim of wrong hopes and self-deception, I recommend all SET inventors to realize the closed-loop. If in the continuous operation power can be taken out of such an arrangement without supply of energy from the outside, and be it as small as possible, then that convinces everyone even any journalist and any non-expert.
Unfortunately in the case of numerous concepts at this place already the end is reached. As charming the variation of the magnetic circuit may be, in most cases I miss the unipolar arrangement of the fields. Perhaps here no neutrinos are needed at all and energy merely is withdrawn from the environment heat? I'm not able to answer this question and I surely don't need to, as long as no magnetic converter is demonstrated to me as closed-loop. such a converter, if it can be realized, presumably will at least partly hide one of its poles and produce some open field lines; that at least would be expected.

a still bigger measuring technical problem represent the neutrinos bound to a line, which oscillate around the conductor in the form of ring-like vortices. We have become acquainted with these in the case of the single-wire transmission technique of Tesla (fig. 9.5). They are formed, if neutrinos are slowed down and collected, but not yet have materialized to charge carriers. Tesla did use them for his loss-free energy transmission technology, but he couldn't supersede the alternating current technology full of losses, which also stemmed from him but which he called the worse technology, from the market because there were no power meters available for the single-wire-technology.

Today we still aren't one step further. The energy supply enterprises still decline this technology, as I had to learn myself, although this would be the only way to transport solar energy from the desert or energy from the geothermal energy of Iceland by a sea cable to Central Europe, where it is needed.
Today still no gauges exist for such neutrinos bound to a line. Therefore will every measuring technician experience his Waterloo at SET-devices, in which they occur! I now will report of such a converter and the odd measuring problems.


1
2
3
4
5
9
10
14
15
19
20
24
25
28
29
21
18
16
13
11
8
6
30
7
12
17
22
excitation coils
26 isolation
27 steel sheet
FD
FD
FD
FD
FD
Lamps
Lead battery
-
+
24 V

Fig. 16.5: Space quanta manipulator of the Firma ROM AG<i>

<i>: Gibas, Greilinger, Lehner, Rusterholz: Strom aus dem All, Mega Link, Fachzeitschrift fur Elektronik, Nr. 6, Marz 1998, S. 18-23 resp. Bau: Glaube kann Berge versetzen, Bulletin SEV/VSE 25/97, S. 31

16.5 RQM and the space quanta manipulator

If an employee or one of the numerous shareholders of the Swiss Firma RQM AG in Rapperswil speaks of space quanta, then he with that presumably means the neutrinos. An oscillating source of neutrinos is called central Space Oscillator and an operation in resonance of the energy receiver, the so-called space quanta manipulator, is required. Mr Ludwig Sigrist, the creator of this world of imagination, was not a physicist but crane operator (pseudonym Crane O.) and inventor, whom textbook physics couldn't help further in his considerations anyhow. His concept, if it can be translated into a scientific comprehensible language or not, at least helped him personally and gave him the position to create the space quanta manipulator (fig. 16.5).

It consists of several pot coil systems, which are build up and boxed into each other according to the Matrjoschka principle of scaling down. The ferromagnetic core material of the pot spheres (1, 6, 11, 16, 21) should show magnetostrictive properties as distinct as possible. As we will see, this measure gains its actual importance first in connexion with the interaction with neutrinos!

Each pot sphere carries an excitation winding (2, 7, 12, 17, 22), through which alternatively flows a current in opposite direction. By means of this measure, which seems useless according to classic design concepts, one of both field poles is pinned in the centre, in which way the necessary open field lines are produced.

The individual pot spheres are insulated from each other, where the isolation layers (3, 8, 13, 18, 26, 28) should have a high dielectricity. The pot spheres thus in addition form capacitors with each other; even the ending plates at both sides (27, 29) function as capacitor plates.
This construction, the core piece of the planned RQM converter, is driven by a transistorised power amplifier with excitation impulses as steeply flanked as possible. According to patent specification<i> the pulse widths are freely eligible in steps of 5 ns betweeen 200 nanoseconds and one second. Besides the frequency also the polarity and DC voltage offset are adjustable.

Every visit of the laboratory leaves a lasting impression: Carefully the engineers grope forward, turn at the frequency and the duty cycle, until the effect suddenly occurs and neutrinos, the space quanta, are being collected. One realizes that tuning parameters with still stronger reactions would be possible, but entirely without any regulation and limitation of power that can't be controlled anymore. The avalanche effect would destroy everything, and so one is further dangling along the brink of the abyss in the development laboratory of the RQM, all the time trying hard to gain control of the hardly understood effect.
Concerning the setup and the mode of operation of the pot system the inventor did let his posterity have explanations, but why a diode in free operation FD suddenly loses its rectifying function, for that neither the employees nor specialist visitors of as high as possible scientific rank in the laboratory until now had ready an answer.

<i>: Gibas, Lehner, Greilinger: Vorrichtung und Verfahren zur Erzeugung elektromagnetischer Pulse, Patentschrift CH 687 428 A5 vom 7.5.1996


Load
Power Elektronics
Control Elektronics
RQM
Charging Unit
Accu
Watt
800
700
600
500
400
300
200
100
0
0 60 120 180 240 300 360 420 480 540 600 660 720 780 840 900
Output Energy
269.344,50 Ws
Recharged Energy
45.705,15 Ws
sec.
0 60 120 180 240
Factor 5,89
Without Battery - Efficiency
Factor 7,52
Incl. Battery - Efficiency
Battery - Efficiency = 0.7835

Fig. 16.6: The RQM test installation of 23-9-1996<i>

<i>: F. Greilinger: Der Weg zur erfolgreichen, stabilen Energieauskopplung, RQF Magnetik, Sonderausgabe 1996, page 10

As said, the neutrinos no longer are free but bound to a line, if they leave the pot system. They oscillate around the wire, even around every semiconductor and rove through the entire switchboard. Doing so they can cause quite something, also bring about quite some disaster.

Lead batteries are being recharged, which without doubt is desirable, but in the continuous operation they are destroyed by the same vagabonds. In normal light bulbs for instance some of them materialize to charge carriers, so that according to a gauge more current leaves the light bulb, as on the other side flows in to it. It indeed glows completely normal, but measuring technical for the installation nothing is normal anymore.

The visitor can be shown by means of a high precision measuring facility of vibrations that the pot coils oscillate not only electrically and magnetically, but also mechanically. But the effects alone don't make a converter, which can be produced and which await already numerous buyers of options and licenses.

On the one hand measures for the purposeful conversion of the roving space quanta in utilizable charge carriers here still are missing. On the other hand any controlling facility is missing, to adapt the power taken up from the neutrino field to the momentary need of the consumers. The brave engineers of the RQM still have quite some way in front of them. but the line of approach is right and the reached can be looked at.

16.6 SET-devices with pulsed magnetic fields

In the case of the space quanta manipulator mechanically nothing is moving. In the copper coils the charge carriers merely are on the way with the velocity v. We here have present a typical example of a SET-system with pulsed magnetic field. Compared to the before discussed SET-devices with rotating magnets, for instance the N-machine, the space quanta manipulator clearly has its nose in front. Without brushes, without friction and wear and tear it theoretically has a unlimited life.

In addition it is simpler to produce the necessary large steepness of the flanks in an electronic way as by a mechanical variation of the magnetic field. By means of electronically driving the process it also can be checked, controlled and regulated easier.

The question for an optimisation of the concept still remains. At present one already can be satisfied with a study of possibility, but sometimes one will question the design. There as an example the eddy current losses in the iron pots will be at discussion. About sheeted or sintered materials could be thought, if not at the same time the inductance of the coil would increase in that way, which slows down the increase in current. Ferrite materials again are very brittle and would crumble to dust under the mechanical oscillations of size. I proceed from the assumption, that also here an arrangement with air coils could turn out to be an optimum. It does make sense, if Tesla at higher frequencies always did experiment with air coils.

Now it still depends on the coiling technique. One single conductor loop doesn't provide any open field line. For this purpose if need be two loops have to be supplied with current in opposite direction, like it is the case for a so-called Mobius winding. In this way possibly just as many neutrinos interact as in the case of the pot coils of the space quanta manipulator, which are alternatively supplied with oppositely phased current. To clarify the situation we now should occupy us with the coiling technique.



Fig. 16.7 A: The Mobius band



Fig. 16.7 B: The Mobius strip


60
62
68
66
70
72
60
62
64

Fig. 16.7 C: Bifilar wound flat coil



Fig. 16.7 D: Mobius winding arranged like a cross

16.7 SET-devices with Mobius winding

In connection with space energy devices often is talked about the use of a Mobius winding. That is traced back to the Mobius band, which one obtains, if one for example one end of a long paper strip after a half turn glues together with the other end. The result is a strip, which has neither top side nor underside and neither right nor left border. This object with only one side and only one border is a creation of the German mathematician August Ferdinand Mobius (1790 - 1868), fig. 16.7 A.

A distant relative of the Mobius band is the strip with the same name, where the magnetic field lines mutually cancel out. It is the same compensation, as we know of a two core electric cable, where the supply and return cable are run close together. For that the sense of winiding of a conductor loop simply is reversed (fig. 16.7 B).
If the magnetic field vector is wrapped right-handed around the supply cable and left-handed around the return cable, then both amount to zero, so that measuring technical no rest field can be detected anymore at some distance.
THE pointer of the electric field stands perpendicular to the magnetic field vector and points in the direction of the conductor and the movement of the charge carriers. From the coupling of magnetic and electric field follows, that the compensation of one of them also leads to the compensation of the other one. But if the electric field actually is compensated, then there may not flow any current in the winding!
There however flows a current if an electric tension voltage is supplied to the Mobius winding. As a result of this forced current flow both electric and magnetic fields have to occur, which are not compensated! Some field lines will fold outward the expected direction and stand in space as open field lines. These we, in the oscillating case, owe the interaction with the neutrinos.

A perfect compensation would be expected for a two core, bifilar winding. The American physicist William Hooper was able to obtain interesting effects with a bifilar wound flat coil. With help of a balance he could detect attracting or repelling force effects on different, electrically or magnetically neutral discs (fig. 16.7 C)<i>.
But he feeds the flat coil with direct current, so that a contribution of neutrinos can't be expected. Such effects only will occur, if one works with pulsed signals, because the bifilar wound flat coil quite obviously is able to form wanted, open field lines.

<i>: Schneider, Adolf: Energien aus dem Kosmos, Jupiter-Verlag 1994, page 28, taken out of:

Mielordt, Sven: Tachyonenenergie, Hyperenergie, Antigravitation, kaum & Zeit Verlag 1984



Derivation:

The Möbius strip has only one border.

Let an electron run all along the border

and connecting the lines one with the next, the result will be the Möbius strip according to Prof. Seike.

（第93図

Fig. 16.8 A: Derivation of the Mobius strip acc. to Seike<i>


右メビウス巻
鉄
十三回トウラス
左ピッチ
15k
150k
5k
アンプ（120db）
0.1
0.1
2SB56A
ダイオード
20k
右ピッチ十一回
左メビウス巻
バリコン
15Ω
0.1
銅
右メビウス巻（13回）

Fig. 16.8 B: Scalar wave radio according to Prof. Seike<i>

<i>: Seike, Shinchi: The Principles of Ultra Relativity, Space Research Institute 1990, ISBN 915517-1

16.8 Mobius converter of Seike and Coler

Concerning construction it can be an advantage to wind a Mobius coil not purely bifilar and in that way to do without a perfect compensation. It often already is sufficient, if two conductors cross and only individual components of the field vectors partly cancel out. In the case of the coil, which is pulled apart and wound like a cross, drawn in fig. 16.7 D the conductor current and the fields of supply and return cable belonging to it stand under an angle of almost 90°. This in individual cases should already be able to cause the formation of open field lines.

Similar field conditions are formed, if after every turn the wire is looped under the last winding. At the knots again the angle conditions of approx. 90° occur. The Japanese professor Shinichi Seike preferably works with this kind of winding, which he directly derives from the Mobius band (fig. 16.8 A)<i>. He has designed an electro-gravitation motor basing on this principle. He also speaks of weight reduction and of an artificial anti-gravity field. It could be confirmed experimentally, that his setup cooled down slowly during the operational tests, despite the expected heating up by the copper losses of the current<ii, S.29>. Unfortunately I don't known anything more exact.

In his book further is found the wiring diagram of a radio for the reception of scalar waves (fig. 16.8 B). He thereby quite simply replaces all coils in the high-frequency part with his Mobius coils. If longitudinal waves already are measurable and receivable with this simple measure, first has to be checked.

The German captain Coler more than 50 years ago has developed another Mobius converter. His "Magnetstromapparat", with approximately 6 kW power and an at least four-fold over-unity effect uses six coils with permanent magnetic core. As a peculiarity he in addition runs the coil current through the core under an angle of 90° with regard to the coil current (fig. 16.8 C).

More detailed details can be seen in the footnote<ii, S. 22>.

<ii>: Adolf Schneider: Energien aus dem Kosmos, Jupiter-Verlag 1994

S.22: "Scientists of the Technical University Charlottenburg in Berlin and Munich confirmed that the device functioned without objections, but they didn't find a theoretical explanation for the production of energy. The professors Kloss and Franke of the Technical University of Berlin found a degree of effectiveness of 450%. Prof. Schumann confirmed that 4.8 to 6.7 times more energy came out, than was put into the device. Prof. Schumann excluded a deception entirely as the records prove.
But it wasn't simple to set the device going and the stability for longer periods of time wasn't guaranteed. The war confusion set an end to further research. After the end of the war the British secret service confiscated all available documents and apparatus. Part of the report was declassified in 1962".


15
15
35
20
15
mm.
binding
soldered & bound
binding
Note: Paper insulation between magnet and coil.
B
A
C
D
N
S
I
IV
(Right)
(Right)
VI (Left)
(Left) III
II
V
(Right)
(Right)
OUTER (Right).
INNER (Left).

Fig. 16.8 C: The Coler converter

16.9 Tesla's flat coil

In the category of the unconventional coiling techniques without doubt the Tesla coil may not be missing. If in schools and high schools such coils were standing in the laboratory for teaching purposes, then as a rule it are cylindrical coils. In reality Tesla worked with flat coils but that, so is said, isn't necessary anymore today, since we have at our disposal better isolating materials than 100 years ago. Actually Tesla contended with problems of osilation, which he could solve with the help of the flat coil, but it should turn out that the coil geometry is attached a crucial importance.

Everything had started with Tesla having to leave the Technical Highschool in Graz without diploma. He ran out of money and he had dared to criticize the venerable Professor Poeschel and his sparking Gramm dynamo. With that he had put himself under compulsion to succeed. Two years later he had ready the solution. In the year 1882 he discovered the rotary field in Budapest.
In the time to come he designs and builds an alternating current motor, but no-one wants to have it and surely Thomas Alva Edison not. Tesla after this disagreement very fast gives up his job at the Edison Company again and again stands under pressure to succeed. With that the eternal bachelor Tesla urges himself to ever higher efforts. He wants to prove himself and the rest of the world that his alternating current system is superior to the direct current system.
Direct current, as is well-known, can't be transformed, and thus the advantage of Teslas alternating current lies in the possibility of power transport by high-tension cable over large distances. But for that the high-tension transformers first had to be developed and thereby the said problems of isolation occurred.
With each turn the tension voltage at the transformer winding increases. The distance to the grounding point lying on the outside has to be chosen bigger with each turn, so that no blow inside of the high-tension winding occurs. A consistent solution of the problem in accordance with engineering is the flat coil used by Tesla, wound spirally from the inside to the outside (fig. 16.9 A)<i>.

It thus is correct that isolation technical reasons led to the flat coil, since Tesla himself was completely surprised as he had to find out that this coil can lose its self-induction, that scalar waves can be detected with it and that it is cooled down during operation in an inexplicable manner.

This cooling effect Tesla has investigated more detailed and after all even used. In his patent specification concerning the superconductivity he describes, that the flat coil also loses its Ohmic resistance, if he in addition previously cools it with liquid air. The remaining cooling down to absolute zero his flat coil obviously has carried out entirely by itself with help of the neutrinos (fig. 16.9 B)<ii>.

<i>: Nikola Tesla: Coil for Electro-Magnets, Patent No. 512,340 (1894)

<ii>: Nikola Tesla: Means for Increasing the Intensity of Electrical Oscillations, Patent No. 685,012 (1901)


singly wound flat coil
(Tesla coil)
bifilar wound flat coil
(from the patent specification of Tesla)
A
A
A
B
B

Fig. 16.9 A: Coiling techniques of Tesla's flat coil.<i>



Fig. 16.9 B: Patent specification of Tesla concerning Superconductivity.<ii>

<i>: Nikola Tesla: Coil for Electro-Magnets, Patent No. 512,340 (1894)

<ii>: Nikola Tesla: Means for Increasing the Intensity of Electrical Oscillations, Patent No. 685,012 (1901)

16.10 The secret of the flat coil

The technical function could be explained in the way that the charge carriers of a flat coil by induction are set into motion for excitation from the outside. The transmitted energy shows in form of kinetic energy. The spiral flat coil becomes narrower and narrower towards the inside, the length of each winding shorter and shorter, so that the kinetic energy inevitable has to decrease in favour of a rotational energy. The faster and faster rotating spherical vortices are pulled apart to flat discs and eventually to ring-like vortices by the centrifugal force. The electrons at first become neutrinos bound to a line and finally free neutrinos. Tesla has technically used the first ones in the single-wire-transmission technique (fig. 9.5) and the last ones in his wireless energy transmission (fig. 9.7).

Like many other inventors, Tesla owes also the inventions, which he counts his greatest, like the radio technique and the Magnifying Transmitter, first of all his industriousness. his persistence and a great deal of inventor luck. A magician, as he is called in his most important biography, he by no means was<i>. The flat coil, to which led him chance and which plays a central role in all these inventions, gave him the lucky position, to collect neutrinos and materialize them to charge carriers or in reversed direction to dematerialise electrons to neutrinos.

The technology however is everything else but new. Already the Lituus of the Etruscan and Roman Augurs and the crook of the priests had the same spiral structure (fig. 16.10). In the case of the devices, which the Augurs for instance served at land surveying, it clearly concerns flat coils according to Tesla. We will go into this strange „gauge" more in detail in part 3 of the book<ii>.

The trick probably is, that one component of the electric field pointer is directed towards the centre of the coil and as a result some open field lines are generated, which then collect neutrinos from space.

In this process the neutrinos thanks to the resonant interaction are slowed down to the speed of light and following, as discussed, materialized by means of the flat coil, as in addition rotational energy is withdrawn from the neutrinos. Since the receiver oscillates resonant with opposite phase, in addition the thermal oscillations are reduced and the receiver becomes cold!

If one compares the Mobius coil with the Tesla coil, then besides numerous properties in common the strength of the first coil lies in the production of open field lines and the collection of neutrinos, whereas the special and additional property of the flat coil lies in the materialization, in the conversion of neutrinos into charge carriers. But the advantages of the flat coil have to be bought at the expense of having to work with very high tension voltages (above 511 kV) and with large changes in tension voltage (du/dt). With this set of difficulties we will have to deal in more detail.

<i>: Margaret Cheney. Nikola Tesla, Erfinder, Magier, Prophet (Orig.: Man Out Of Time, 1981), Omega-Verlag Diisseldorf 1995

<ii>: K. Meyl: Electromagnetic environmental compatibility, part 3, edition belonging to the information technical seminar, INDEL Verlagsabteilung 2003.


The Etruscan Lituus
the Roman Lituus

Fig. 16.10: The Lituus or crook of the Augurs in ancient Rome

16.11 Discussion concerning the technology of the neutrino collectors

Let us again collect the facts for the discussion: A SET-device is distinguished by a more or less unipolar design and open field lines, with which interact neutrinos, which are oscillating in resonance. These then are slowed down and collected. For the transient process a large change in tension voltage (dE/dt) is required, which can be obtained directly, for instance by means of a spark gap, or indirectly by means of Faraday's law concerning the unipolar induction (E = v x B).
The discussed possibilities concern the acceleration of a machine part (dv/dt), the variation of the magnetic field (dB/dt) by pulse-like excitation signals (16.5) or by magnetic flux variation (16.3) and the railgun. which even can be operated without foreign magnetic field (fig. 15.5 C) and for which in that case occur both a dv/dt and at the same time a dB/dt.
For resting arrangements the velocity v is that of the charge carriers moving in the conductor. So that Faraday's law thereby doesn't lose its influence, the pointers of E and v mustn't point in the same direction, as in the case of "normal" coils. Unconventional windings, which for instance can be knotted like Mobius strips (16.7), take remedial action. Also the ancient crook, rediscovered as flat coil of Tesla (fig. 16.10), proves to be suitable in principle. Here one component of the electric field pointer points in the direction of the centre so that the wanted, at least partly, unipolar arrangement can be formed.

The first step, the collecting of space quanta, shouldn't pose an insurmountable obstacle anymore in view of the numerous possibilities and the detailed explanations. A real difficulty we still have before us, because in most cases some ring-like vortices bound to a line are formed, for which no electronic construction element exists and for which functioning converters hardly are known.
There spoons are bending, some lumps are flying through space, radioactivity is disappearing without a trace, light phenomena are formed and the device suddenly is becoming cold. Almost all inventors, who have arrived in this place, are enthusiastic about the not understood effects or with that are wanting to get attention, but hardly anyone really starts something with that. Until now the necessary system and an useful theory were missing.

Only too often isn't considered, that only an indirect conversion into charge carriers is possible, that during the materialization of neutrinos a intermediate product is formed, which can be described with the model concept of a neutrino bound to a line or of an oscillating ring-like vortex. The technologies collected in this chapter concerning the collecting of neutrinos only form the first step from the free to the bound ring-like vortex. The coming chapter is dedicated to the second step. Here we should try to understand the properties of space quanta bound to a line and loudly think about for which purpose we could use them in practice[i].

<i>: Reference: Both chapter 16 and chapter 17 treat point 4 according to table 15.1 concerning the resonant interaction (page 86).


mirror
E, v
$\bar{\nu}$
antineutrino, right-handed
E, v
ν
neutrino left-handed
E, v
$\bar{\nu}$
antineutrino, left-handed
E, v
ν
neutrino right-handed

Fig. 17.1: Application of the mirror transformation to the neutrinos

---

<i>: Kleine Enzyklopadie Atom, Verlag Chemie GmbH, Weinheim 1970, S. 119: „For the neutrinos the quantum number parity isn't defined, because they have a fixed association of the direction of momentum and spin; the sense of rotation of the spin and the direction of momentum in their case form a left-hand wound screw, in the case of antineutrinos a right-hand wound screw. By the shown mirroring the direction of momentum is reversed, but the sense of rotation remains unchanged; i.e. reactions, in which neutrinos occur, are not mirror invariant, they violate the law of conservation of parity". (translated)

Note of the author:, an antineutrino by no means can be assigned to the anti-matter, since it exactly like every neutrino alternatingly takes the matter state and the anti-matter state, by oscillating around itself (see fig. 7.12). The description merely follows a definition founded in usefulness.

17. Technical use of the weak interaction

17.1 Radioactivity caused by neutrinos

Neutrinos are standing in a weak interaction with other elementary particles. This circumstance is known in general. According to the considerations and derivations expressed in the book the neutrinos mediate the resonant interaction, what leads to the conclusion, that the weak interaction represents a partial aspect of the resonant interaction, in which case it merely concerns the proximity.
Efforts are further being undertaken, to combine the weak interaction with the electromagnetic to an electroweak interaction, after it was remarked that a certain coupling constant corresponds in both cases. We of course aren't surprised, because the electromagnetic interaction anyhow describes only the special case of the resonant interaction with the frequency zero.
The weak interaction concerns with the very small range of just 10^{-16} meters only the proximity of the neutrinos, for instance the ß-decay, where the neutrinos for the reason of their oscillating charge a free neutron rattle and shake so long, until it eventually decays. on the average after approximately a quarter of an hour.

The Austrian physicist Wolfgang Pauli had remarked, that half the decay energy after a beta-decay is missing and the balance sheet of energy isn't working out. In addition also the balance sheet of angular momentum isn't working out, because the nuclear spin is being changed for a whole unit. Pauli as a result 1930 has introduced a hypothetical particle without mass and without charge, which he called neutrino.
With that Pauli and his co-working Italian colleague Fermi it is true are the givers of the name of the neutrinos, but not by all means the discoverer. If Cowan and Reines 1956 have detected these particles with large expenditure of devices, then also that by no means was a premiere, as falsely can be read in textbooks and encyclopaedias. After all Nikola Tesla already decades ago had demonstrated, that the neutrino radiation not only exists, but even can be used energy technically.

Now the radioactive decay a ß-radiation occurs, triggered by the conversion of neutrons in protons or vice versa. This obviously takes place under the influence and participation of neutrinos in the atomic nucleus. The ß-radiation to a special extent consisting of electrons and positrons, as it occurs in the case of nuclear fission, is quite unhealthy and by no means ecologically compatible. Under the influence of free charge carriers not only metal lattices become soft and spoons can be bent, but also an electrolysis takes place, where the water molecules are splitted into their parts. That isn't a good prerequisite for the flora and fauna on our planet, which predominantly is built up of water structures.



Fig. 17.2: Einstein, Tesla and Steinmetz[i] (from left to right)

---

[i]: Franz Ferzak: Nikola Tesla, Eigenverlag, S. 103

17.2 Nikola Tesla, the discoverer of the neutrino radiation

The discoverer of the neutrino radiation himself will best be able to explain the connexion. In the New York Times Tesla writes, that he has discovered and investigated the phenomenon of the cosmic radiation, long before others started their researches<i>:
"According to my theory a radioactive body is only a target, which constantly is being bombarded by infinitely small balls (neutrinos), which are projected from all parts of the universe. If this, at present unknown, cosmic radiation could be interrupted completely, then no radioactivity would exist any longer.
I made some progress regarding the solution of the mystery, until I in the year 1898 attained mathematical and experimental evidence, that the sun and similar celestial bodies emit energy-rich radiation, which consist of inconceivable small particles and have velocities, which are considerable faster than the speed of light. The ability of penetration of this radiation is so large, that it penetrates thousands of kilometres of solid matter, without their velocity being reduced noticeably. "
It must be admired how Tesla guided by experimental observations and a reliable instinct comes to the correct result. He merely with the conclusion, because of the missing interaction the neutrinos have to be inconceivably small, isn't quite right. Their size rather depends on the velocity, because the overfast neutrinos are being length contracted stronger. Tesla however hits the nail exactly on the head, if he on the occasion of the press conference for his 81st birthday declares, the radioactivity is a clear proof of the existing of an outer radiation of cosmic origin<ii>. „ If Radium could be shielded against this radiation in an effective way", Tesla writes in an essay of 1934, „then it wouldn't be radioactive anymore". At this occasion he contradicts Albert Einstein, without thereby pronouncing the name and is indignant at the wrong working method of the scientists<iii>.

Me personally fascinates, how here until now ignored results have been presented, which I first had to work out theoretically myself with difficulty. Tesla, to the best of my knowledge, hasn't taken theoretical derivations, at least none have been handed down. As a brilliant experimental physicist he must have reached his conception world by means of the measuring technique. The perfect correspondence of his experimentally determined and the by me theoretically won insights should be judged as evidence for the correctness of this view.

<i>: Dr. Tesla Writes of Various Phases of his Discovery, New York Times, Feb. 6, 1932, P. 16, col. 8

<ii>: Tesla Said (J.T. Ratzlaff), Tesla Book Company, ISBN 0-914119-00-1, P. 272

<iii>: "The scientists of today think profound instead of clear. One has to be mentally sane, to be able to think clear, but one can think profound and nevertheless be completely insane. The scientists of today have substituted experiments by mathematics, and they travel from one equation to another and eventually build up a construct, which has absolutely no relation to reality"...

taken from N. Tesla: Radio Power will Revolutionize the World, Modern Mechanics and Inventions, 7/1934, (Tesla Said, P. 264)



Fig. 17.3: The Magnifying Transmitter of Nikola Tesla
Would the research station in Colorado Springs (1899 - 1900) have been suitable for transmutation?

17.3 Transmutation and reduction of radioactivity

If we are capable to collect and bundle up neutrinos, then should with that an influencing of the radioactive decay become possible, then also a decontamination of radioactively contaminated material and a so-called transmutation should be possible. We here have a concrete possibility before us, to use the produced ring-like vortices directly for the benefit of humanity. Dangerous transports with Castor containers, permanent and temporary storage and the contamination of whole areas by radiation, like around the nuclear power station Tschernobyl, which got out of control, wouldn't be necessary at all. If namely burned out fuel rods and objects contaminated by radiation have undergone a concentrated neutrino shower, then the radioactive decay takes place accelerated, so that the half-life can be drastically reduced. After the treatment the dangerous special waste would have been changed to harmless domestic rubbish. Even recycling or reuse are feasible.

The topic is at least as explosive as the energy question and as well completely unsolved. That's at different places and in some companies is already feverish researched about technologies concerning transmutation. Often it are the same people, who also work at the theme of space energy. The reason quite simple is that in both cases neutrinos have to be collected and bundled up. In the case of transmutation however the necessity of materialization can be dropped, so that the goal can be obtained faster and simpler. Consequentially is reported of more cases of a successful decontamination and of transmutation, than of functioning energy converters. Until now most techniques however still hardly are suitable for bringing into action technically on a large scale, but they carry clues of a solution of the problem already in them.
At the congress "New Energy technologies from USA" 6.12.1997 in Zurich I have lectured concerning the theme<i>: „Presumably as the first one the doctor Dr. Wilhelm Reich has carried out corresponding experiments with his „Orgon accumulator" (fig. 9.2). From him also stem warnings about biological effects, which should be taken serious, if radioactive material is put under his Orgon accumulator and the process of decay takes place accelerated".
If one dares an interpretation of his experiments with only 1 mg radium, then numerous charge carriers materialized at hitting upon his sample of the bundled up neutrino radiation with the consequence of high electrostatics in the environment, which Reich has called DOR-state (Deadly ORgone) (chap.15.11).

Another way would be the rebuilding of a neutrino transmitter according to the plans and patent specifications of the experimental physicist Nikola Tesla (fig. 9.11). He 100 years ago had realized a real neutrino-broadcasting and for that developed an unconventional switching technique. Tesla called his transmitter a „Magnifying Transmitter" (fig. 17.3). He choose the name „Magnifying Transmitter", after he had received more energy than he had transmitted in experiments and this effect moreover was increased with increasing distance to the transmitter. He obviously also had collected free and synchronously oscillating neutrinos, and that would be the best prerequisite for a successful transmutation and decontamination of radioactive material!

<i>: Konstantin Meyl: Die Wechselwirkung der Neutrinos; uber Massnahmen, die Halbwertszeit beim radioaktiven Zerfall herabzusetzen. NET-Journal Jg. Nr. 3, Jan./Feb. 1998, S. 14-20


Exit Temperature Reading
Static In-Line Mixer
Platinum Contact Anode (+)
O-Ring
Industrial Strength Glass
Platinum Screen
Nylon Screen
Microsphere Beds
Coated Microsphere
Platinum Screen
O-Ring
Platinum Contact Cathode (-)
Input Temperature Reading
Static In-Line Mixer
CETI

Fig. 17.4: 1 kW Patterson Power Cell.<i>

<i>: Patterson, J. A.: System with electrolytic cell and method for producing heat and reducing radioactivity of a radioactive material by electrolysis. US Patent No. 5.672.259 of Sept. 30, 1997, as reprinted in Infinite Energy, July-Nov.1997, pp. 13-16

17.4 The Patterson Power Cell

As an example worth paying attention to, the Patterson Power Cell should be mentioned, which not only can be used for generation of energy but, how could it be otherwise, also for reduction of radioactivity and for transmutation. The energy cell invented by the chemist Dr. James A. Patterson is researched and developed further by the company CETI (Clean Energy Technologies Inc.) in Sarasota (Florida, USA). According to latest reports such a device supplies at most one kilowatt of heat energy at an over-unity of up to 4000; thus 4000 times the energy is released than is taken up as required for the operation!
In fig. 17.4 one single cell of the energy converter is shown. The glass container consists of three chambers of approx. 4 cm height each time and about 1.9 cm in diameter and works like a continuous-flow water heater. From the bottom tapwater or distilled water is supplied and at the top connection again taken away in heated form. The excitation takes place electrostatically by means of two platinum electrodes. The anode situated at the top is connected with the positive pole and the cathode with the negative pole of the source of direct current.
In the three chambers are situated tiny, filmy coated small balls, which form the real principal item of the cell. Production method and structure of the beads are oriented to the task to be mastered. In the case of a variant conceived for the generation of energy the barely one millimetre in diameter small synthetic beads carry after each other a thin layer of palladium, a layer of nickel and once again one with palladium<i>.

The small balls remind with their layered structure at first of the Orgon accumulator of Reich. They also seem to function as collectors of neutrinos, but for smaller wavelengths and much higher frequencies. In addition is chosen a concentric arrangement with the spherical form, which with the electrically conductive surface and the dielectric core fulfil the function of a cavity resonator. Resonance actually is possible with flying past neutrinos, which have a wavelength which amounts to an integer multiple (1,2,3,..) of twice the diameter of the sphere.
The arising resonant oscillation however concerns not only the electric and magnetic fields, but by means of electrostriction and magnetostriction also a mechanic oscillation of size. The oscillation of size in reverse causes again oscillating electric and magnetic field pointers, which are partly open along the spherical structure and can interact resonant with further neutrinos. In this repercussion field the actual secret of the functioning of a Patterson-cell is hidden.

The president of the German association of space energy, Prof. Dr. Dr. Josef Gruber on the occasion of his visit at the company CETI and of a conference about „cold fusion" in Vancouver has published a report<ii>:

<ii>: Gruber, J.: Kalte Fusion und Raumenergie, report concerning the 7th international conference about "cold fusion" of 19.-24.4.1998 in Vanvouver, B.C., Canada (Infinite Energy, Issue 19, 1998) and report concerning "International Symposium on New Energy" of 23.-26.5.1997 in Denver, Colorado, USA (Denver-report of the remote University Hagen)



Fig. 17.5: Low Energy Nuclear Transmutation Cell,[i]
the kit for experiments LENT-1
(Showing Temperature and Pressure Gags)

---

[i] taken from the NET-Journal, 10/11 1997, S. 7

17.5 Report concerning the cold fusion

"In the case of the Patterson transmutation cell it concerns a special electrolysis cell, in which the radio nuclides are charged. During the electrolysis the decay activity measured by means of a Geiger-Muller counter decreases drastically. Within a few hours reductions of up to 80% are obtained. In such an electrolysis system with electrodes consisting of specially coated beads low-energetic nuclear reactions can be observed. In this case elements are detected in the metallic layers of the beads, which before were not contained in these. Further are measured changed (unnatural) proportions of isotopes. From these transmutation can be inferred, which is used in the cell for the conversion of radioactive elements.
Until now natural uranium and thorium were used as radioactive material. The reproducibility already now is very good. The applicability for commercial purposes, for the reduction of the radioactivity of burnt up fuel elements and for the conversion of plutonium is easy to see".
At his visit in the laboratory of CETI in Sarasota 28.5.97 Prof. Gruber has witnessed an experiment to annihilate radioactivity with the Patterson transmutation cell. He reported about it: "In the presence of N. J. Olson from Pacific Northwest Laboratory (operated by Batelle for the U.S. Department of Energy) a team of the television station ABC conducted by the science journalist Dr. M. Guillen made recordings for a television program, which meanwhile has been broadcasted all over the country. The original tension voltage - among others a Geiger counter rattled - subsided as the expected success became apparent in the experiment: After one hour 50% of the radioactivity stemming of uranium nitrate were removed, in another half an hour further 13%. Doing so also a considerable lot of surplus heat was produced.

New techniques of this kind to reduce radioactivity have an important advantage: One brings the SET-device there where the radioactive material is situated and reduces the radioactivity on the spot. For the conventional technique, still being in research, in contrast to that the radioactive material first is wrapped in a complicated manner and then transported to a special factory, where radioactivity is reduced at great technological expenditure and use of energy - altogether a procedure which is relatively costly and politically only hard to carry through".

Patterson cells already can be obtained commercially for research purposes. The same goes for a demo-kit[<i>] of the company Trenergy, Inc. of Hal Fox, who has built up the biggest database of the world concerning the theme "Low Energy Fusion" in the "Fusion Information Center" at the university of Salt Lake City. He is editor-in-chief of the "Journal of New Energy".
If one believes the statements on their web-site[<ii>], then one is capable of converting 10 g of radioactive thorium in 900 mg titanium and some copper in less than an hour with the kit for experiments LENT-1. Under a pressure of 3200 psi sodium already is said to have fusioned to gold, something of which alchemists dream, as an unintentional side effect, as researchers in Cincinnati/Ohio say[<iii>].

<i>: NET-Journal, Jan. 1997, S. 24
<ii>: see Internet: http://www.hal-fox@slkc.uswest.net
<iii> : NET-Journal, 10/11 1997, S. 7


high-temperature flame
25
connection for ignition
7
connecting piece for filling in water
13
2
8
20
19
15
3
resonant cavity
9
9a
Connection for the (−)
electrical power supply (+)

Fig. 17.6: The water-fuel-cell according to Stanley Meyer<i>

<i>: H.-J. Ehlers: Stan Meyers Wasser-Zellen-Technik, Raum & Zeit special 7, p. 201, taken from the Canadian patent specification 1234 773 of 5-4-1988

17.6 Water-Fuel-Cell technology

The United States are, just what concerns spectacular techniques like the removal of radioactivity or the transmutation of new materials, obviously still the land of unlimited possibilities. Nowhere the list of researchers of cold fusion is as long as in North America.
But there also in many places only is tried and tinkered without visible system or usable theory. Then in many cases unfortunately only a show-effect is to the fore, while construction plans and details concerning the way of functioning, as far as they actually exist, are kept secret. In total there, besides a lot of hot air and wrong hopes, is left behind little to be used and cited.
By the way, in my opinion cold fusion has to do very much more with space energy and neutrinos than with hot fusion. How much disaster a wrong referring to and an unusable theory can bring about, has become clear at the example of the "cold fusion researchers" Fleischmann and Pons. They have placed themselves into the scientific offside with their misinterpretation concerning cold fusion.
Moreover are both primarily scientists and theorists. Practice however is, according to general definition, "if in spite of all it functions!" The American Stanley Meyer is such a practical man and his water-cell-technology actually seems to function, although he in his 18 patent specifications gives theoretical explanations, which he just as well could have saved himself. With that his effect isn't explained.
An usable interpretation would be that this device, comparable to a cell of a plant during photosynthesis, splits water molecules into its parts by putting on neutrinos. Even without knowledge about space quanta the buggy of Stanley Meyer already runs with a air-cooled 1500 cc VW-engine, and it consumes no gasoline at all. The tank is filled with water; it even may be sea water. The consumption of water lies at 2.8 litres at 100 kilometres and thereby is formed predominantly hot steam again as a combustion product.
If thus cold water is converted into hot water and at the same time mechanical energy is available. then inevitably another source of energy must be involved. According to my interprelation it must concern the neutrino field. If the here presented details are correct then the over-unity effect lies at approx. 100, the degree of effectiveness thus at 10000 percent.

American companies, with which Stanley Meyer had concluded contracts, should make the "Water-Fuel-Cell technology" mature for series. Also the financing seemed secured. But then per internet the message came, he 21.3.1998 was having supper in a restaurant in Grove-City, as he suddenly jumped to his feet from the table and called out, he had been poisoned. He died on the spot<i>.

Alarge number of inventors is known, who tap space energy with the help of water. It concerns an increase of the content of oxygen or of the content of colloids, thus an improvement of the water quality. Or it concerns formation of vortices as already in the case of Walter Schauberger, glowing phenomena or also the generation of free energy from the neutrino field. In this concert the concept of Stanley Meyer takes an outstanding place, as particularly efficient, instructive and clearly understandable for us, for which reason we cast our eyes over the design (fig. 17.6 and 17.7).

<i>: Zum Hinschied von Stanley Meyer", NET-Journal April/Mai 1998, S. 25; see: obituary in Infinite Energy Magazine

A. The pattern of the pulses of the excitation voltage:



B. The wiring diagram:


GATED PULSE TRAIN
50% DUTY-CYCLE PULSE
GATE TIME
RESONANT CHARGING CHOKE
BLOCKING DIODE 1N1198
D.C. POWER SUPPLY
PULSE GENERATOR (VARIABLE)
INDUCTOR
A
FUEL CELL WATER CAPACITOR
PRIMARY COIL AND CONTROL CIRCUIT
VARIABLE INDUCTOR
B
VOLTAGE AMPLITUDE CONTROL (VARIABLE)
TOROIDAL CORE
ISOLATED CIRCUIT FROM SECONDARY COIL
PULSE GATE (VARIABLE)

Fig. 17.7: Wiring diagram for the driving of the water-cell<i>

<i>: Stanley, A. Meyer: Process and Apparatus for the Production of Fuel Gas and the Enhanced Release of Thermal Energy from such Gas, 15.06.89, US-Pat. 207,730; International Publ. WO 89/12704; Int.Appl. PCT/US89/02622

17.7 Unconventional electrolysis

Numerous of the by Stanley Meyer used construction principles already have been treated, be it the excitation with pulses of electric tension voltage or the spherical structure of the resonant cavity (fig. 17.6). As a spherical capacitor with the positive pole in the centre and the negative pole at the outside edge it corresponds to the model of the electron and fulfils in an almost ideal way the conditions of an unipolar arrangement according to fig. 15.8 B. The use of certain patterns of the pulses and steep flanks of the pulses (large dU/dt) make possible effects of resonance at frequencies starting at ten kilohertz, in which neutrinos participate increasingly. First the series resonant circuit, consisting of the adjustable, external inductance and the spherical capacitor, is stimulated by means of the current rectifying wiring (fig. 17.7). In the case of resonance, which is carried out by comparison of the inductance, the excitation current drops, whereas the tension voltage at the same time teaches values of more than 1000 Volts. If in addition a neutrino resonance occurs, then the known avalanche effect will occur. The equipment then takes up virtually no current.

As a dielectric serves water, with which the container is filled permanently. The dimensions are oriented after the velocity of movement of the water molecules according to details of the inventor. Also the oscillating water molecules should go into resonance. Then they can help to materialize the neutrinos. Their rotational energy partly passes to the water molecules and as soon as the neutrinos have been converted to charge carriers, they will take the water molecule from the oppositely charged side and split it without further ado. The oxygen and hydrogen gases leave the capacitor through fine openings at the upper edge of the spherical chamber, which are so small, that no ignition back can occur, and in the simplest case reach a combustion chamber, where they burn again to water as a high-temperature flame (fig. 17.6).
The gases of course also can be guided into the cylinder of a Otto engine and be ignited there, as in the case of the experimental buggy. In the sectional drawing can be seen a filler by means of which, according to the consumption, water is refilled. The round resonant cavity not necessarily has to be spherical. Stanley Meyer more frequently differs from the ideal form and works with a cylindrical symmetry (fig. 17.8), with which obviously in spite of that the goal can be obtained, if perhaps not quite so good. To this compromise the explanations of fig. 15.8 C apply.
If we, to conclude, cast our eyes over the wiring diagram which Stanley Meyer discloses in his patent specification (fig. 17.7 and 17.8)[i]. In the centre is a transformer, which should produce an if possible high tension voltage. A rectifying diode, which takes care that only positive tension voltage pulses serve the excitation, is switched in series with the reaction capacitor, which is filled with water, a fixed and a variable inductance. In that way the positive pole is always situated in the centre of the reaction chamber. If both connections would be exchanged or the diode be turned over, then the neutrinos presumably would materialize in positrons and not in the wanted electrons. But if one leaves out the diode entirely and one has a tension voltage changing both in positive and in negative direction, then maybe electrons and positrons are equally generated, which annihilate each other under emission of gamma quanta. Doing so no gas is formed, but at most light, as long as the effect of collecting neutrinos isn't lost also. The concept should be worth to be examined more detailed already of pure scientific interest.

A: The high-tension transformer:


GATED 50% DUTY CYCLE PULS TRAIN
FUEL CELL WATER CAPACITOR
PRIMARY COIL (A)
STEPUP SECONDARY COIL (B)
PULSE INDICATOR PICKUP COIL (C)
POLARITY ALIGNMENT
IONIZED GAS OUTPUT
RESONANT CAVITY
G
SWITCHING DIODE
RESONANT CHARGING CHOKE
RESONANT CHARGING CHOKE
LASER INJECTION
ELECTRICAL INSULATED HOUSING
COIL (D)
COIL (E)
WATER INLET
ISOLATED ELECTRICAL CIRCUIT

B: The driving:


61
VARIABLE D.C. POWER SUPPLY
A
Q10
H11D1
OPTO COUPLERS
VOLTAGE INTENSIFIER CIRCUIT
GAS RESONANT CAVITY ASSEMBLY
VARIABLE ALTERNATE GATE CIRCUIT
62
Q11
BLOCKING DIODE
POT 59
H11D1
ELECTRICAL LOAD (LIGHT BULB) RESISTIVE WIRE

Fig. 17.8: High-tension transformer and driving of the cylindrical water-cell<i>

<i>: Stanley A. Meyer: Process and Apparatus for the Production of Fuel Gas and the Enhanced Release of Thermal Energy from such Gas, 15.06.89, US-Pat. 207,730; International Publ. WO 89/12704; Int.Appl. PCT/US89/02622

17.8 Materialization of neutrinos

In the centre of attention of the water-fuel-cell of Stanley Meyer is on the one hand the unipolar arrangement (according to fig. 15.5 B or C) to collect the neutrinos and on the other hand the water for slowing down and materializing. Over and above that a lot was tinkered and tried, as can be inferred from the patent specifications (fig. 17.8). That starts at the. coiling technique of the transformer and concerns the experiments with laser stimulation as well as the top part, which according to the inventor should extract the electrons (Electron Extractor Grid). The measures may bring an improvement, but are insignificant for our considerations.

At this place it primarily concerns the question of the materialization of neutrinos. But if such a materialization has to be made complete, if water molecules must be splitted, depends on how long the process lasts. If everything goes very fast, then perhaps it is sufficient that a neutrino for a short time is showing as an electron, before it again oscillates back. In this short time the splitting process already could have taken place. The used neutrinos for that had to be very low-frequent and very slow. They after that could again leave the reaction chamber and fly on as neutrino.

Possibly the fishes, which live in stagnant waters or in the deep sea, owe the slow neutrinos the content of oxygen in the water. Because here no bundling up takes place, the splitting of water takes place rather by chance. The volatile hydrogen atoms escape very swiftly, whereas the big oxygen atoms are left behind in the water.

Now we still don't know how charge carriers can be won. At the RQM unit resonant oscillations of size had been measured and that can be judged as an important clue. If namely a space quantum is slowed down then it becomes bigger. The inverse case we already had made us clear: If a particle is correspondingly fast then it is sufficient length contracted to fit through the tunnel (fig. 6.14).

To slow down neutrinos according to that the target area should carry out an oscillation of size with opposite phase. Organic material and biological systems are excellently suited for that. Every contraction of a muscle brings that to mind. Inorganic matter and our technology however normally don't know this phenomenon. Technical energy converters simply are built up fundamentally else than biological muscle machines.

In historical sources at certain places is pointed to the fact that priests had experimented with quartzes and miraculous phenomena were observed. Of course the question is asked, if such experiments today still can be reproduced. Because the density of the earth slowly increases due to the growth in volume, also the wavelength of these oscillation quartzes is changed. The same neutrino radiation therefore today can't be active anymore. It thus would be completely inappropriate wanting to reject a historical source only because a described effect today doesn't want to function anymore.

Magnetostrictive or electrostrictive material could be a solution. For instance a piezocrystal, which contracts under the influence of an outside field. As an ultrasound converter an applied alternating voltage leads to the emission of a sound wave. If we reverse the function, then a received longitudinal wave should lead to an electric tension voltage and then at last the materialized charge carriers could be taken off,!



Fig. 17.9: The course of the field in the case of a glow-discharge<i>
(The numeric values indicate the active field lines, as they can be read from the representation).

<i>: K. Kupfmuller: Einfuhrung in die theoretische Elektrotechnik, 12. Aufl. Springer-Verlag (1988), S. 197

17.9 Oscillation of size and luminescence

There exist substances, which at high temperatures start to glow. In the sense of the theory of objectivity presented in the first part of the book in the case of temperature it actually concerns an oscillation of size of the involved elementary particles (fig. 8.3). If this oscillation of size lies in the visible frequency range, then we can directly perceive it and it can be used for instance in a light bulb for the purpose of lighting.
In the case of an arc. fluorescent tubes or glow-discharge lamps light is formed as well even without a thermal effect. These glowing phenomena are called luminescence. They can be caused by chemical processes, by friction, by crystallization or by electric fields. As can be shown speedily, in these cases it also concerns an oscillation of size.

If we for that consider the model on the left (fig. 17.9). Between two electrodes there is a non-conducting gas, e.g. air. If now a tension voltage is applied then, under the influence of the electric field, some gas atoms are splitted into positively charged ions and negative electrons (case A) and pulled apart (case B). This process of enlargement of the glow-discharge fast as lightning comes close to that of the thermal oscillation of size and obviously in the same way is perceived as light.
The ionised gas parts are attracted by the unlike poled electrodes and move towards these (case C, D). Whoever takes the effort to count the number of the field lines, will find out that between both electrodes the electric field drops, whereas it at the same time increases at the electrodes. The first thing causes that the process of ionisation is stabilized by itself and a state of equilibrium will result; the resulting current takes a constant value.
The increase of the tension voltage at the electrodes on their behalf causes that an arc remains standing or the glow-discharge lamp glows on, even if the feeding voltage is reduced. For this reason a fluorescent lamp needs a starter, since the network voltage is too small to start the effect of luminescence.

We indeed know, that the gain of light of a fluorescent lamp is at least three times better than that of a light bulb. As a rule a degree of effectiveness in spite of that can't be given, since it merely concerns a comparison measurement in the case of the measurement of the lighting intensity with a luxmeter. It hence can't be excluded, that we already are dealing with an over-unity effect in individual cases and neutrinos are involved in the effect of glowing.
A necessary oscillation of size would be present, as the perceivable noises of open spark gaps prove. Also in the case of lightning the thunder occurs as a consequence of a longitudinal oscillation of size and at the same time a glowing phenomenon occurs as a consequence of materialized neutrinos (fig. 14.11). It almost is obtruding a scientist that here the same principles are at work.

One however hardly can prove that neutrinos are involved in the luminescence, because the configuration is symmetrical with regard to the resonance of neutrinos and just as much particles materialize as anti-particles, which afterwards again annihilate completely as an impulse of light. They hence can't be measured directly. It gets interesting if an asymmetrical arrangement with unipolar character is chosen.



Fig. 17.10: Tesla with a wireless light bulb[i]

<i>: A Sarony-Portrait from 1894, Tesla-Museum, Belgrad

<ii>: R. Hiller, K. Weninger, S. J. Puttermann, B. P. Barber: Effect of Noble Gas Doping in Single-Bubble Sonoluminescence, University of California, Los Angeles, USA, Science, Vol. 266, 14.10.1994, P. 248-250

and: D. Lohse: Wenn sich der Schall in Licht verwandelt, Mechanismus liegt noch im dunkeln; (University of Twente, NL) Mitteilungen der DFG 4/98, S. 19-21

17.10 Phosphorescence and sonoluminescence

Let us first look at the observable after-glowing at fluorescent lamps or at a screen, the phosphorescence. It presupposes a storing effect, and that in accordance with prevailing textbook opinion can be traced back to the excited state of some atoms. Doing so electrons in the atomic hull change from one level of resonance, an instable state of energy, to another orbit, which represents the ground state. Doing so the difference in energy is emitted in the form of light. The process obviously not only takes place as luminescence during the switching on of the excitation voltage, but also as phosphorescence after the switchng off.

An enveloping electron now doesn't fly as a tiny planet around the nucleus, but occupies the entire orbit as an inflated spherical vortex (fig. 5.5). Seen from the outside it is a matter vortex. It however sees the enveloping electrons on the further on the outside lying orbit from the inside and there they are showing as anti-matter vortices. As long as the distance of respect is kept, nothing happens. If however an inner spherical vortex presses to the outside or the outside one to the inside, then the incompatibility of the vortices takes effect and both annihilate under emission of a photon. In this respect the explanations of the vortex model are very helpful.

But now, after this flash of light, two electrons are missing in the atomic hull. The positively charged atomic nucleus never would allow this loss. Replacement has to be fetched and that actually only can stem from the neutrino field. Therefore the enveloping electron doesn't change the orbit immediately, but instead has to wait, until a suitable neutrino passes by, with help of which the game of changing places can be executed. This explains the time delay and gives reasons for the observable after-glowing.

The form of the unipolarly charged sphere (according to fig. 15.8 B) forms almost ideal prerequisites for an interaction with neutrinos and the step-like change of size from one orbit to the next ideal prerequisites for their materialization. The longitudinal wave connected with the change of orbit without doubt can be called a high-frequency sound wave. It however can't be detected because of missing gauges for such high frequencies.

But if we take the frequency down into the range of the ultrasound, which can be handled technically, then effects arise which brilliantly prove this interpretation and the participation of neutrinos in the luminescence.

The not understood phenomenon is called sonoluminescence and at present is researched at numerous high schools primarily for academic interest. The structure is conceivably simple. One takes a ball of glass filled with water and positions at the edge one piezocrystal next to another. Then one with the piezo loudspeakers, operated with the same phase, sounds the whole with ultrasound and see there, the water glows mysteriously! The sound waves change the pressure. Inferring from the observations, during the phase of low pressure small bubbles are formed, which at the following rise of pressure collapse and emit a ultrashort flash of light. There thus takes place an oscillation of size, which leads to the luminescence phenomenon! So far so good; but such a flash of light is much shorter than the collapsing of the gas bubble lasts. With less than 50 picoseconds it is faster than the otherwise usual atomic transitions of electrons. The whole thing obviously has nothing to do with this kind of luminescence. Also the spectrum doesn't fit and finally the over-unity effect lies at one trillion, the light energy thus is 10^{12} times larger than the energy part which is taken up from the sound wave by every atom<ii>!



Fig. 17.11: Light bulbs according to plans of Tesla<i>

<i>: N. Tesla: Experiments with Alternate Currents of High Potential and High Frequency, Lindsay Publications Inc, ISBN 0-917914-39-2, Fig 18, P. 70+103

17.11 Discussion concerning the use of the weak interaction

In the case of the luminescence the conditions lie similar like those for lightning. The science of today it is true has some problems of explanation at detail aspects, but again and again manages to protect the ivory tower of physics from collapsing, with supporting auxiliary explanations. But at the latest in the case of an unipolar arrangement, in the case of a ball-lightning or the sonoluminescence, the participation of the neutrinos clearly comes to light, the auxiliary concepts prove to be unusable.

It surely is no accident that the discoverer of the neutrino radiation also was the first, who has experimentally investigated the luminescence. The lamps of Tesla (fig. 17.11) all were without wear and didn't have filaments like those of Edison. They however had to be operated with high tension voltage and relatively high frequency. Both a single-wire and a wireless transmission technique were possible (fig. 9.5 and 9.7). In his laboratory Tesla only needed to hang a fluorescent lamp without any return cable on a wire, then he had light. Famous also are the pictures on which he holds a lamp in his hand, which glows entirely without any connection, but only if he takes it in his hand! (fig. 17.10).

If we again turn through the chapter, then it is remarkable that in most cases, from the transmutation to the luminescence, neutrinos can be used for reason of their resonant interaction which in the proximity can be put equal to the weak interaction. A real materialization however poses an enormous difficulty. If namely the translatoric motion of the space quanta is slowed down, then the risk exists that for balance the rotation increases. But that as well has to be slowed down for a materialization! Only if both processes of slowing down take place, the goal can be reached. In that case the described cooling down effect occurs.

For a measurement technical check it therefore offers to record the slowing down of the translatoric motion and the collecting of the neutrinos by means of the measurement of the radioactive decay of a sample. And to read the materialization as the slowing down of the rotation from a measurement of temperature. In addition are helpful proofs about oscillations of size, glowing phenomena and deviations in the balance sheet of energy. With that it should be able to obtain a system for the exploration of these phenomena with the goal of a practical exploitation of the neutrino radiation for the benefit of humanity.


Abb.1.
Abb.4.
Abb.3.
Abb.2.
A:
Floating installation for wood according to Viktor Schauberger<i>
B:
Ancillary part for shower according to graduate engineer Wilhelm Martin.<ii>

Fig. 18.1: Mechanical whirling of water

<i>: N. Harthun: Naturgemasse Stromungsfuhrung nach Viktor Schauberger Analyse einiger seiner Patente und Zitate; MuT Nr. 4, 1980; s.a. Kap. 9.2
<ii>: O.Alexandersson: Lebendes Wasser; W.Ennsthaler Verlag Steyr, 1993, S.156
<iii>: V. Schauberger: Die Entdeckung der Levitationskraft, Implosion 112, S. 39.
<i4>: Do we owe the taste of bubbling spring water to neutrinos?

18. Physical phenomena

In this chapter it on the one hand concerns indirect effects of the resonant interaction and on the other hand effects of gravitation and levitation.

18.1 Water as a catalytic converter for neutrinos

Already the Austrian forester Viktor Schauberger has pointed to glowing phenomena at whirled water. He first had observed such in nature at torrents and waterfalls in the Alps. Later he was capable, to produce and to demonstrate this effect even artificially<iii>. One could speak of hydroluminescence, where still the question would be left open, how it actually functions.

Already in chapters 4.10 and 4.11 has been talked about the special properties of water. It here at first concerned the property of transport of a vortex, which even is capable to bind particles in the vortex, which are heavier than the whirling medium itself. Schauberger had become famous by letting build floating installations, in which not only tree-trunks, but also gravel could be transported down to the valley, without the sides of the channel actually having been touched by the rubble. This phenomenon has been examined and confirmed on the scientific side <i>.

Basing on this principle today different devices for processing water are offered and sold, which bind lime, mineral materials and suspended matter in the vortex and in this way prevent deposits in the pipes. The methods, to whirl the water, are however very different. Some whirl the water mechanical, others magnetically and again others electrically. Here the dipole nature of the H_2O-molecules has an effect. If I turn a water molecule with its electric charge distribution, then from the moving charge a magnetic field results. If thus in the pipe a hydrodynamic flow vortex is produced, then an electric and a magnetic vortex, the potential vortex and the eddy current, are the result (see fig. 4.2). The wanted flow vortices vice versa also can be obtained, by guiding bubbling whirled water past permanent magnets, or by feeding in alternating magnetic fields with the help of coils, or finally by working with pulsed electric potentials. Each of these systems, operated passively or actively, has its specific advantages and disadvantages (fig. 18.1 B and C).

It can be assumed that with the vortices also the water quality is changed. As a rule the content of colloids increases, due to which the surface tension falls. In the colloids negative ions are bound, for which reason also the electric conductivity decreases. Finally the content of oxygen increases and that actually only can come from an electrolysis. The neutrinos thereby are suspected <i4>.

As an extreme dielectric medium water favours the formation of potential vortices, which immediately after their formation contract swiftly. This oscillation of size of the electrically charged potential vortices makes possible actually an interaction with neutrinos, and that on the one hand has as a consequence the water splitting and the increase of the content of oxygen in the water and on the other hand the above depicted, observable glowing phenomenon, the hydroluminescence.


a. using magnetic field:
x
y
1 mm Ø
15 Wdg.
tube
b. using electric field:
x
y
ca. 15 wdgs.
ca. 15 wdgs.
+
12 V
3k3
33k
4
8
Reset
Vcc
Timer-IC
Output
NE 555
3
+
100µ
16V
7 Discharge
2 Trigger
6 Threshold
220 Ω
GND
Control
1
5
x
y
100n
10n
100n

Fig. 18.1 C: Wiring diagram for a simple water processor
with pulsed field (2 kHz rectangular signal)
a: for magnetic field excitation
b: for electric field excitation



Fig. 18.2: The spectrum of frequencies of light and of the zero
point radiation.<i>

<i>: A. Waser: The Puzzling Nature, AWVerlag Luzern 1996, p. 88

To complete in fig. 18.1 C the wiring diagram of a simple water processor is shown, which works with pulsed electric (b) or magnetic (a) fields.

If we temporarily again leave the theme water and take along the notion, that it must be attributed a great importance in connexion with the interaction and the materialization of neutrinos

18.2 Background and zero point radiation

Whathappens really, if cold matter or interstellar gas molecules are hit or touched by the everywhere present neutrinos? Then it can be expected that oscillations are being stimulated and as a result the temperature slightly increases. If we thus at a space flight hold a thermometer out of the shuttle window, then we will measure everywhere such a remaining temperature of a few degrees Kelvin, which is called cosmic background radiation.

By popular scientific small talkers the background radiation is called remnant of a so-called Big Bang. It even is misinterpreted as evidence for the Big Bang. Even if a certain value of entertainment can't be denied, the Big Bang from a physical view until now only has raised questions and contradictions.

If we stay at the fact that oscillating neutrinos depending on their radiation density and velocity of propagation produce a thermal oscillation, which can be detected as a slightly increased lemperature. To measure that we don't need immediately to undertake a space flight. We also can install the thermometer in an artificially produced vacuum. In vacuum physics out of ignorance of the relations the neutrino radiation then is called zero point radiation.

In the case of the neutrinos it of course concerns an oscillation around a mean value, which for a symmetrical form of oscillation has the value zero. The term nevertheless is misleading and chosen very unfortunate. After all we don't speak of zero point current in the case of alternating current!

Since every supernova and every black hole emits neutrinos and correspondingly in physical experiments until now no preferred direction could be determined for the zero point radiation, it is taken as homogeneous and isotropic in space. From the Lorenz invariance again is inferred a cubic course of the zero point spectrum, an increase of the radiation intensity with the third power of the frequency. With this assumption the radiation density of the vacuum however strives with increasing frequency towards infinity. Here an error has to be present in the considerations!

I proceed from the assumption that in the case of the spectrum of the neutrino radiation it rather concerns a spectrum of resonance, the maximum value of which lies above the frequency range measurable with devices of today. It of course would be very important to find out, where the radiation maximum lies, but without being able to measure it that lies unfortunately in the range of pure speculations (fig. 18.2).

Half the wave length in any case should be tuned to the length of the antennas of the energy centres of the cells, the mitochondria and the chloroplasts which are capable of photosynthesis. In both cases the head diameter of the ATPhases amounts to approx. 5 nanometer. It would be obvious, if the resonance point would lie here. But it could as well lie at still smaller wave lengths in the domain of molecular dimensions.


quantum theory:
metal plate a
metal plate b
– F
F

outside cause<i:>: pressure force by bombardment of quanta?


theory of objectivity:
metal lattice a
metal lattice b

inside cause<i>: levitational force by resonance effects?

Fig. 18.3: The Casimir effect

18.3 The Casimir effect

If this zero point radiation actually would be the cause of the Casimir effect, which is generally assumed today, then neutrinos would have to be involved, if the zero point raditation would be to put equal to the neutrino radiation. The effect even is quoted as evidence, but I have my doubts.

The experiment is relatively simple and functions also in a vacuum. Two absolutely plane and smooth polished metal plates are placed very close to each other. Doing so the distance should only amount to one thousandth till one millionth of a millimetre. If the force, with which both plates are attracting mutually, is measured then it exceeds by far the gravitational force. We are dealing with an unknown force, neither electric nor magnetic.

Because the force of attraction still arises near the absolute zero of temperature, some make the zero point radiation responsible. In our translation that would be tantamount to the neutrinos exerting a pressure from the outside on the metal plates, if need be with their small rest mass, as far as this should not be based on an offset-error of the detecting devices. For that the plates would have to damp the neutrino radiation effectively and by mutual shielding reduce the radiation pressure from the split. The question is asked, if the from the outside hitting bombardment of quanta, as it is called, actually can exert a pressure which would be compatible with the nature of the neutrino radiation.

If we now try an entirely other interpretation, which does without the postulating and designing of new force effects. Now the from the unified theory won interactions according to table 15.1 form the basis. In the Casimir effect, as said, neither magnetic nor electric forces are involved, so that open field lines and the corresponding force effects (1 till 4) are ruled out. It has to be the work of closed field lines and that in the static case we know as gravitation (5). Now the mass of the metal plates is too small, as that an acceptable force of attraction of masses could result.

The measurable force is much larger, even if it according to its nature could be a gravitational force. Here oscillations, as they actually take place in the hull of the metal atoms, seem to play a role. If between the oscillations of the two plates standing opposite occurs resonance, then a levitation is possible (6), which describes an oscillating interaction, produced by closed magnetic field lines<i>.

At extremely low-frequency signals this interaction is known as gravitational wave and object extravagant and costly physical experiments.

<i>: The question, which interpretation is correct and which one should be rejected, could be verified as follows: at first the force between two plates of a certain metal and afterwards that of another metal has to be measured. If in a third experiment a plate from the first and one from the second experiment are brought together and the force effect goes back measurably, then the quantum physical interpretation would be wrong clearly. With that would have been shown that here resonance effects are used, which presuppose an identical metal lattice structure of both plates.
If the force effect however doesn't go back, then both statements are possible, then one has to think up another experiment.


(engl.: DREAM OF HUMANITY:)
Wunschtraum der Menschheit:
FREIE ENERGIE
(engl.: FREE ENERGY)

Fig. 18.4: The flying disc of Searl on a german title page.<i>

<i>: Special 7, Raum 8s Zeit Dokumentation aus dem EHLERS Verlag

18.4 Effects under high tension

It crackles in the laboratory of high-tension. The air smells electrically charged. Only in a corner someone sits and waits with much perseverance and patience, until something happens. Then he lets thunder down lightnings of several millions of Volts on a small sample. It flashes and crashes and still nothing happens.
No, it doesn't concern Tesla! Tesla has worked purposeful. In addition has Tesla only called himself inventor. But the man in the corner feels himself a discoverer and as it is proper for a discoverer, he has immediately named the effect after himself. As a real American he lets market himself and his discovery by the media and a video tape.
Doing so he obviously doesn't know at all, what he wants to have discovered, of what this Hutchison effect actually consists. It perhaps is an event of pure chance, for which he sometimes has to wait hours. If it very suddenly would occur, then it is a real potpourri of all already discussed effects: metal spoons are bending (fig. 14.13), massif steel rods are breaking, light effects are being observed (chapter 17.9 PP), water starts to dance and to cook (chapter 18.1), without getting hot and finally do some samples take off and fly crosswise through the room. He then speaks of anti-gravitation.
In the video tape can be seen, how he brings about a physical length contraction as a result of a locally produced field concentration with two as an interferometer configured Tesla coils. In a bottle for instance the air volume is changed. This confirms the correctness of the here presented theory of objectivity (chapter 6.6 PP).
In any case no-one is amazed more about the results of chance than John Hutchison himself. Overwhelmed by the magic, the charm of the effects and the feeling to be able to move freely outside the trodden out ways of physics, he still sits in his corner with the video camera and waits, until finally something happens again.

There is worked with tension voltages, which are considerably higher than 511 kV, the calculated tension voltage of their own of the charge carriers (fig. 7.1). One thus by no means has to be amazed, if under the influence of several millions of Volt electrons are taken apart and metallic objects are breaking or bending.
The extreme tension voltage and field change we owe an oscillation of length and of size, which spontaneously can lead to an interaction with neutrinos. Materialized neutrinos again are responsible for glowing phenomena and for the electrolysis of water, which under the impression of the rising gas bubbles seems to dance and to cook. For my readers and participants of the energy technical seminar therefore models of explanation are available.

One effect we still haven't discussed and analysed more in detail: the antigravitation resp. the levitation. As long as no reproducible field conditions are present and the chunks are accelerated in any arbitrary direction, it will be difficult to understand the physical course of a levitation.
In chapter 9.3 we already had become acquainted with and discussed a levitation device with the flying disc of John Searl. for which the field conditions are comprehensible. This time we should have a somewhat closer look at the flying device (fig. 18.4)<i>.

<i>: Some reports can be found in Special 7 „Freie Energie", Raum & Zeit Dokumentation aus dem EHLERS Verlag, Seite: 141 bis 157 und 174 bis 185


−
+
disc rebuild to a power generator
Emission plate
ring
magnetic roll
Upper emission plate
ring
needle
lower emission plate
switch

Fig. 18.5: Concerning the controlling of the flying discs according to Searl.<i>

<i>: H.Schneider, H.Watt: Dem Searl-Effekt auf der Spur, Special 7, Raum & Zeit Dokumentation aus dem EHLERS Verlag, Sauerlach, 1. Aufl. (1994), S. 183

18.5 Flying discs

The Searl-disc can be calculated relatively good with the Faraday equation concerning unipolar induction. To estimate the order of magnitude, we just suppose the roller magnets produce an induction of one Tesla and the radius is one meter, then between the centre of the flying disc and its edge 511 kV is applied, if the revolutions per minute has reached the value of 80000 revolutions per second. As soon as the revolutions per minute is reached, the neutrino conversion can start.
The at the edge of the disc arising corona, which consists of individual electrostatic discharge flashes, takes care for the necessary dU/dt, by every blow and every spark is drawing the potential for a short time towards ground. The tension voltage jumps in swift order between values of above 511 kV and zero Volt to and fro. In connection with the already discussed unipolar field configuration neutrinos are being collected in this way.

A technological challenge represents the layered construction of the roller magnets and the rings, which have to withstand extreme centrifugal forces (fig. 18.5). Friction however is not a theme, since on the one hand the air inside the disc ionises and a vacuum is formed and on the other hand the air split between rollers and discs increases by the field dependent contraction of the metal parts.

Actually one in this case by no means can speak of antigravitation, because the gravitation isn't really vanishing. The disc even in flight still is heavy tons. Here merely a resonant interaction is built up which is larger than the gravitational pull of the earth. The disc is attracted by the cosmic source of neutrinos, with which it has built up the resonance.
Exactly there it will fly!

The by Searl designed controlling<i> in my opinion actually can't have functioned satisfactorily. He uses emission plates, as he calls them, which alternatively are switched on by means of switches and are able to form electrostatic forces with some air charge carriers. In reality the drive probably is comparable to that of a sailing ship, for which the wind always blows from one direction. The ship isn't pushed by the wind, as one erroneously could think, but rather by the under pressure behind the sail pulled forward. Without steering facility the object always is driven in direction of the drain. The sailor would say, the ship without helmsman drifts towards lee.
Searl in this way has lost all flying discs which were started. By using solar neutrinos they presumably have fallen into the sun and burnt. The controlling should function analogous to a sail, then one would stand a chance, by "traversing" against the "wind", to sometime again come back to the starting-point.

<i>: H. Schneider, H. Watt: Dem Searl-Effekt auf der Spur, Special 7, Raum & Zeit Dokumentation aus dem EHLERS Verlag, 1. Aufl., Seite: 183


Start of a Searl flying disc
John Searl in his controlling headquarters

Fig. 18.6: The remote controlled flying discs of John Searl.<i>

<i>: Special 7, Raum & Zeit Dokumentation aus dem EHLERS Verlag, S. 152

18.6 Propulsion with neutrinos

In search for an ideal propulsion system for spacecrafts the flying discs of John Searl still have demonstrated a further possibility. After the start occasionally were left strange particles on the ground, which hadn't be there before. The flying device obviously had materialized them and dropped them at the start.

With this materialization of neutrinos the chance is showing of a very efficiently working recoil propulsion. If namely the neutrinos are converted into matter then they by that gain back their rest mass. If this takes place in flight then the materialized particles also bring along kinetic energy. It then works as ajet engine for which the direction of the jet can be directed and in that way the vehicle can be controlled comfortable.

In the case of the Searl-disc the materialization of neutrinos rather happens as a not understood side effect. In the case of a systematic use however the principle will show a characteristic property. Instead of a vapour trail a beam of light will shine out of the flying object in the direction of the emitted particles, but it will break off abruptly after a cartain distance.

To blame is the part, which has become anti-matter, which it is true as well contributes to the recoil, but simultaneously annihilates with incompatible particles of matter under emission of particles of light. If in some distance all antiparticles are used up then also the beam of light comes to an end.

It here concerns necessary properties of a corresponding propulsion technology for spacecrafts, which don't have to drag their propelling energy along with them. Our space technicians finally could handle another than the "hammer throwing method", in which case the "hammer" by means of terrible fuel consumption after a phase of acceleration only staggers uncontrollable through space under the influence of its inertia.

With a neutrino propulsion on the other hand one at any time can accelerate or brake. It will strongly influence the field around itself, so that can be reckoned that for every acceleration a field dependent change of size should be perceptible by an outside observer.

If therefore a corresponding flying device is accelerating then it will suddenly become smaller and that then looks so as if it would have moved away with a jump without temporal delay, but that isn't the case at all.

The jerky movements only would be a result of the perception with our eyes by means of the propagation of the light. Since the passengers are exposed to the same field, they change their body size along with that of the vehicle. They actually notice nothing of an apparently infinite acceleration, which only observers on the outside would observe and which indeed no living being could stand.

Nowhere the explanation crisis is larger than in space travel! The theory of objectivity represents a real help, because it perhaps as the only one puts us in a position to conceive and understand not understood observations as necessary technological consequences.

Only by uncovering parascientific as purely physical phenomena man of today will be able to free himself from the constraints of magic and his own illusions.

Is the until now discussed cases resonant or other force effects are being used, whereas the gravitation remains unchanged. Closed field lines after all cannot be influenced, normally at least. Perhaps an indirect possibility exists to have an effect on the gravitation?


A. Test facility<according to i>
6.35 kg weight, which becomes almost 2% lighter
1st
ring of superconductive ceramics (yttrium-barium-copper-oxide)
turns per min.: 5000 min^{-1}.
Cooled by liquid nitrogen
diameter altogether ca. 12 cm
excitation coils, (to magnetize the ring)
three coils as magnet bearing, (to carry rotating ring)
B. The measurement setup<according to ii>
to check the shielding properties of superconductive ceramics $YBa_2Cu_3O_{7-x}$
electronic balance
sample
superconductive disc
2 rotary field magnets
excitation magnet
liquid nitrogen resp. liquid helium

Fig. 18.7: Experiment for the manipulation of the gravitational pull of the earth.

<i>: Schneider: Anti-Gravitation im Labor nachgewiesen?, NET-Journal Januar 1997, S. 14,15; s.a. Internet: http://www.keelynet.com/gravity/fingrav.htm

<ii>: E. Podkletnov, R. Nieminen: A possibility of gravitational force shielding by bulk $YBa_2Cu_3O_7$-x Superconductor, Physika C 203 (1992), P. 441-444

<iii>: Force field Implications of Anti-Gravity, The Journal of Ideas, Art.191, 7.9.95

18.7 Antigravitation or levitation

The night already had fallen over Finland, but at the University of Tampere the light still was on. Then a scientist put his beardy head through laboratory door and with a "hello folks" blew the smoke of his pipe over the cryostat for the examination of superconductive materials. The scientists were speechless, because the smoke seemed to hit an invisible wall and was drawn upwards in direction ceiling almost at a right angle.
After having aroused the curiosity, Dr. Eugene Podkletnov also has held other materials above his rotating disc and had to discover that these as well lose weight, and that he actually influences the gravitation with his experiment. Even the air pressure at the corresponding place in a lying above floor was smaller[i].
With a superconductive disc of 30 cm diameter cooled by liquid nitrogen a reduction of gravity for 2% to 4% can be obtained, if the disc rotates with more than 5000 revolutions per minute. With the revolutions per minute also the effect increases, but it is independent from the excitating field[ii]. Finally the fields of the superconductive currents in the ring remain existing unchanged even after switching off the excitation and it only depends on these fields.

The shielding effect of the arrangement on electromagnetic fields already had been known before and should be examined closer in the laboratory. One only was surprised that the gravitation could be shielded as well, that obviously both interactions are related. According to the prediction of the theory of objectivity the closed magnetic field lines gravitate and the field components directed towards the centre of the earth cause the measurable force of weight. By the very strong superconductive fields obviously field overlaps and possibly a local driving out of field occurs, like one has long known for eddy currents (Meissner effect).
With that the earth gravitational field of course is not cancelled, but merely spatially moved, or it partly has changed its direction. If only a small part of field pointers turns out of their orientation towards the centre of the earth, then at that point the force of weight is reduced to a corresponding extent. The theory of objectivity requires that!

By the way reports exist, according to which even without rotation a weight reduction can occur for superconductive rings, and others, where is worked even entirely without superconduction. As core material for the ring ferrite or a strong permanent magnet is used. In that case depends on the circumstance that the ring-like coil is operated in self-resonance and always in the right moment again is excited anew by induction. The ring core then stores the fields up over time, exactly as the superconductor.
Stricktly speaking it are the atomic nuclei and in the end all elementary particles, which are aligning in the high field. Dr. Ning Li wants to artificially produce gravity, by directly influencing the quanta. With that she comes the phenomenon very close[iii]. The possibilities of this effect nevertheless are very limited, since two percent more or less are not exactly much, and the dream of the complete cancelling of gravity or even inertia possibly stays just a dream. It stricktly speaking just concerns influencing the gravitation and not antigravitation!



cause/ field lines	interaction F	= force effect *mediation:*	**see chapter:** effect/ *application*
5. closed **H**-field lines	gravitation (static)	F_{MG} = gravity *by particles with mass*	**chapter 6.9 + 7** elementary particle mass
6. closed **H**-field lines	levitation (dynamic)	F_{ML} = reduced gravity	**chapter 18.3** gravit. waves *Casimir effect*
7. closed **E**-field lines	gravitation (static)	F_{EG} (force hardly detectable)	**chapter 18.7** *supercon-ducting ring*
8. closed **E**-field lines	levitation (dynamic)	F_{EL} (no longer detectable)	**chap. 18.5 + 18.6** *Keely-/Searl-flying devices*

Table 18.8 A: The interactions of closed field lines.[i]



Fig. 18.8 B: Test models of the "flying saucer" according to Viktor Schauberger.[ii]

---

[i]: according to fig. 15.5, cases 5 to 8

[ii]: O.Alexandersson: Lebendes Wasser; W.Ennsthaler Verlag Steyr, 1993, S.103

18.8 Discussion concerning the effect of closed field lines

If we now direct our eyes exclusively to the lower half of fig. 15.5, in which the consequences of closed field lines are listed. Without the possibility of a direct focussing like for open field lines, the caused force effects turn out extremely small. With that they are less suitable for an use of free energy. The considerations in that context rather aim at technologies to reduce weight, like they would be worth striving for for flying devices.
If we allege that here in the same way the force effects of magnetic H-fields exceed those of electric E-fields for three to four powers of ten. Then it will hardly play a role for the force of weight of a body with or without additional electric charge, if its E-field lines are closed as well or are open. The increase in weight of an uncharged body only will have an effect in the third till fourth place after the decimal point. Seen so in the case of the gravitation it primarily concerns an effect of the magnetic field, more strictly speaking the effect of closed magnetic field lines (chapter 6.9).
If one succeeds in influencing these magnetic fields for instance by the influence of extremely strong fields of a superconductor, then also the gravitation will change, as has been shown (chapter 18.7). Let's imagine, in the case of a systematic procedure we would succeed in a perfect influencing, for which no component of the H-field lines points into the direction of the centre of the earth anymore, then an uncharged body would only have one tenthousandth of its original weight, whereas a charged body actually would weigh nothing anymore. This state of the weightlessness supposes that all E-field pointers point into the direction of the centre of the earth or diametrically in the opposite direction, since E- and H-field are standing perpendicular to each other. Unfortunately such a field distribution technically hardly can be realized and so the ,,flying carpet" furthermore remains reserved to the fairytales.
An effective reduction of weight of planes and other flying objects however seems by all means feasible, and so slowly the number of research facilities increases, which more or less officialy have a critical look at the cancelling of gravity and the levitation. The theories on which they are basing, however often sound very bizarre and moreover are completely unphysical. Maybe a look at the distribution of field lines, as proposed here, helps to get further.

In the case of the levitation, which occurs strictly speaking only in the case of oscillation for closed field lines, resonance again plays the crucial role for the coming about of the interaction. In connection with neutrinos the resonance can serve less the collecting; we rather need it for the materializing, for the production of mass, charge and energy.
For the artificial production of a levitation either a mechanical oscillation in the atomic or molecular domain is needed, like for instance is produced by a rotating water molecule, or a resonant oscillation of size takes place by use of electrostrictive or magnetostrictive materials, like piezocrystals or oscillating quartzes.
In this context surely is of great importance that also the temperature could be identified as a particle immanent oscillation of size (chapter 8.3). That's why besides a cold materialization or cold fusion also exists, at least theoretically, the possibility of a hot materializatin or hot fusion.



Fig. 18.9: The increasing number of free energy inventors.<i>

<i>: only the inventors mentioned in the text are entered. Literature for that: A. Schneider: Energien aus dem Kosmos, Jupiter-Verlag (1994), S. 77

18.9 Concerning the determination of the stand of today's energy technique

An analogy to the production of matter forms the production of light. At high temperatures as is well-known is formed thermal light and at low temperatures cold light, the discussed luminescence. An oscillation of size of the light source in all cases of the formation of light is the cause, be it as an electromagnetic wave or as photon vortex, be it in whirled water or as sonoluminescence. We at last see ourselves put in a position to understand the various light phenomena as something which is related.

The call for new energy carriers and an ecologically compatible energy technology can't be ignored anymore. The number of inventors at present increases fast (fig. 18.9). It is legitimate and worth recommending, to observe for this purpose first of all nature, how it solves its energy problem. Doing so we should realize that in contrast to the technology of today no combustion and no explosion takes place, but rather principles of a cold fusion and of an implosion as a result of contracting potential vortices are being used. Actually nature may point the way out of the energy technical dead end. We only have to accept the offer, be open and show being ready, to invest in the development of methods in accordance with nature.

Directed at the address of the distributors of supporting funds for energy research the claim in plain English reads: to grant no money anymore for ecologically harmful concepts, like nuclear fission or for not understood and not realizable developments like hot fusion. to immediately stop the fruitless works and to provide the money for an ecologically compatible energy research.

Immense saving potentials moreover are found in all domains of physics, where instead of costly experiments just as well the things could be calculated with an usable theory. To check the theory then only few experiments would be necessary. After all all important discoveries have come about in this manner. Nobody should think, he had understood a matter, once he has filled himself up with sufficiently much measurement data.

The root of the evil lies already in the education, where students of physics want to understand everything and therefore are trying hard to grasp with their view and hands for everything. Abstract thinking or mathematical derivations however are too uncomfortable for most; they have the erroneous opinion, understanding (German: begreifen) would have to do more with grasping (German: greifen), and for that the head after all can't be used.

One reason for this development can be seen in the relativistic point of view of Albert Einstein, who proceeds from the assumption of a subjective observability and has raised the relativity between a physical principle and the observation to the basis of physical thinking. The arrogant motto prevails: what I can't observe with my sense organs or register with corresponding gauges also isn't physics, but esoterics or parascience.

But if we want an ecologically compatible technology, then this can't be reached with this point of view. Then we only hinder ourselves with our own arrogance and intolerance. We have to leave the erroneous quantum physical way and again learn to think abstractly by taking up tried and tested principles of classical physics. An objective point of view forces us to register the phenomena, which lie outside the observable range, with mathematical MEANS (see chapter 13). Only if we have learned that, we will understand and realize the true relations in physics!


EWR1
DC
MICROAMPERES
An
2,5Hz
Abfrage-
frequenz
1
100
Null-
punkt
Kopf-
hörer
ohne mit
Speicher

Fig. 19.1: A self-built charge amplifier.

19. Own experiments

The opposite of the theoretical considerations form practical experiments. If we want to register and understand physical and natural scientific phenomena, then we shouldn't entirely forget the aspect of handicraft. Doing so it can't be avoided that it goes on very personally, if about the laboratory work is being reported, not even then, if the experimenter is at pains to exclude every influencing of the carrying out of the experiment and the result. After all does anyone have to execute the experiments himself, since a good sceptic anyhow only believes, what he has observed with his own eyes.

19.1 Concerning the rating of experimental physics

There already have been scientists, who have requested to reject a measuring technical determined result for the case that textbook physics doesn't produce it. This attitude even today still is taken by an uncounted community of believers of science, entirely after the motto: "Nature kindly has to fit in with the dogmas of theoretical physics!"

This wrong thinking is reflected in the scientific journals, which reject to print discussions. Controlled by a tester board, which only has the task to prevent dissenters from the publication of their ideas, they are the sad proof, how widespread this erroneous attitude today is in the university scene.

Actually solely the scientific experiment shows us the physical reality! The theoretical models, like the here presented vortex model merely should help to understand nature and its laws. The representatives of theoretical physics are in the role of a helper and that requires modesty and openness.

For the case that a professor of theoretical physics imposes a pledge of secrecy on an experimenting colleague, if this one wants to report publicly about his amazing tunnelling experiments, then the public nevertheless should have the right to find out, if a tunnelling experiment reveals speeds faster than light, even if it doesn't suit the theorist and he in inappropriate arrogance only should consider the experimental physicist as his assistant.

If universities only are occupied with preservation of property and the industry only with the increase of its productivity, if future research consists of hiding public research funds internally in such a way that nobody realizes the fraud of support and in reality nobody thinks of the future anymore or wants to work for it, then we will be able to observe how discoveries and inventions migrate from the industry and the universities with their controlled central organs and increasingly will take place again in garage, cellar, solitary study room or in privately organized circles.


antenna
zero point
10K
10K
10K
100nF
P
N
V
11
12
10
I
II
III
IV
1nF
1nF
470pF
470pF
30K
30K
30K
30K
30K
30K
⊕
⊖
amplifying
25K
180
Ω
30K
10K
tuning
50K
display
D
D
50 μA
V
13
15nF
15K
14
P
N
100pF
N
30K
with
without store
clock
P
M
N
10μF
10μF
4,5V
4,5V
P
P
VI
555
100K
2M2
P
frequency
1K
220nF
100nF
22nF
x1
x10
frequency
IC I bis IV: CA 3130; IC V: 4066B; IC VI: NE555; D: AA119

Fig. 19.2: Wiring diagram of the self-built charge amplifier

19.2 The charge amplifier from the workshop of handicrafts

Is connection with my vortex theory in this book time and again clues to experiments can be found. I am aware of their importance and I always, to verify my theoretical working out, have accompanied it with practical experiments. Doing so not the proof, which can be published and reproduced by anyone at any time, stood in the foreground. With the experiments in my workshop of handicrafts I only wanted to check for myself, if my derivations still can be verified.

Consequently was at first done without a publication in the first and second edition of the second part concerning the "electromagnetic environmental compatibility". For the addition of the here presented chapter about own experiments from the third edition there are several reasons: first; I have been asked for it by several readers, second; from every experiment is coming a piece of physical reality to meet one and third are here latent some useful ideas and approaches which get us somewhere.
Of course can't be read much from a handicrafts self experiment, but perhaps one or another reader, who has better laboratory technical possibilities at his disposal than me, is stimulated to carry out own experiments.

To chase after the potential vortices in the air, I 1989 at first have built together a charge amplifier. I connected differently formed antennas at the particularly high-ohmic difference input. Corresponding the in nature arising static electric field a tension voltage should arise between both antennas, which my gauge should amplify and indicate on a moving-coil instrument.
To be able to register local changes, a measurement cycle is gone through, which periodically is repeated: It starts with the measurement time, during which entirely by itself between both antenna a charge is building up. The value afterwards is stored analogue in a Sample-And-Hold link and displayed by means of a moving-coil instrument. Then the input clamps are short-circuited, the antennas again discharged and the game starts from the beginning.

Measurement time, zero and amplification can be adjusted at the device (fig. 19.1). Whoever has fun to rebuild it, finds the by me realized wiring diagram in fig. 19.2.

It is true I did realize other designs, but technically the here shown design proved to be the most useful solution.



Fig. 19.3: The bath tub drain vortex;
shown is a tidal vortex near St. Malo.<i>

<i>: Photograph from the magazine „Life" of 4.7.1969, resp. from: H. J. Lugt: Wirbelstromung in Natur und Technik, Seite 371

19.3 Interpretation of the observations with the charge amplifier

The practical use of the device at first proved to be extremely difficult, because the pointer seemed to perform a wild dance. At a more close look I however could make exactly those observations, which I had sought-for as proof for the existence of potential vortices.

First I did find confirmed the known high field strength. We after all live between the ionosphere and earth's surface right in the middle of the dielectric of a "spherical capacitor". Because the values of the electric field reach very much closer to the maximum value, which is lethal for living beings, than the value of earth's magnetism, I did draw from that the conclusion that biological effects primarily can be expected from the E-field.

If the E-field, as Maxwell's field theory specifies, actually would be irrotational, then we would be dealing with a gradient field. My device would have to display everywhere to a large extent the same value. But that was not the case.

Maybe the building is responsible for the chaotic display and the wild swings of the pointer, so I thought. Doing so I had thought of the auxiliary explanations of the high-frequency engineer about so-called reflections in closed rooms. Therefore I stormed with the gauge, which had gone wild, into the open air and walked different ways, which should have been reflection free, but the picture stayed the same. In any case the E-field is not a gradient field. I had to find out.

Following I could, what required much patience, find certain places, at which for the same movement from the same direction could be seen a reproducibility of the swing of the pointer, it even could be arbitrarily often repeated. 1 marked the point exactly. Then I tried to move the device from another direction towards the marking and had to find out that the point had moved away.

If I sit in the bath tub in the evening and pull the plug, then I each time am enthusiastic about how sensitive the drain vortex reacts, how I can send it from one corner into the other by the snipping of a finger without it falling apart (fig. 19.3). Doing so one easily can imagine with a bit of phantasy how difficult, yes, almost impossible it would be to measuring technically register the vortex for the case that we could not see it. The gauge it is true would display violent wave movements. But a reproducibility we would not be able to obtain, exactly as for my self-built charge amplifier.

Now I knew that the by me at 2.1.1990 at first purely theoretical derived potential vortex actually exists as vortex of the electric field!


Copper plate
ca.20KV
50V/5A
motor vehicle
ignition coil
1N4148
1N4148
230V
50 Hz
Network
12V~
12V~
50V/5A
1N4148
240V/1W
47Ω
1 W
BD 242
BU111
BC547
1K2
33Ω
10 W
33Ω
10 W
1N4148
10000 µF
25 V
10 µF
10 V
8,2 V
400 mW
47 µF
10 V
transistorised
ignition system
22K
47K
2K2
100Ω
1 W
3
+
7
P
741
6
2
-
4
BC557B
BC 141
1N4148
10K
frequency
100K
10K
1 K
1 K
100 Hz -
500 Hz
12 Hz -
120 Hz
560 nF
100 nF
clock generator
driver

Fig. 19.4: Wiring diagram concerning the Kirlian device.<i>

<i>: Elektor, Fachzeitschrift fur Elektronik, Mai 1977, S. 22-25: KirlianfotogralV

19.4 High-tension experiments in the laboratory for performance electronics

At first the students of electronics, with which I had to do daily, were infected by my discovery. With true enthusiasm they soldered together one circuit after another. In my laboratory something like a mood of setting out could be felt. One student brought along and old ignition coil of a motor vehicle, then the control circuit for it was built, plexiglas organized, an aluminium plate glued under it and the whole box dragged into the photographical laboratory<i>. Three students made a detour along the outside grounds of the polytechnic and picked the necessary visual aids of trees and bushes.
Following the leafs were laid on photographical paper and by means of the self-built high-tension generator charged to 20000 Volt. Doing so at all edges and particularly at the tips of a leaf corona discharges arise, which expose the photographical paper. We then developed the photographs ourselves and discussed the results <ii>.

The indication, for a second photograph the whole leaf would appear even if half the leaf is torn apart after the first experiment and only one half is put on, occupied us in particular. Eventually we didn't put on a leaf at all in the second experiment and found out that nevertheless the leaf put on last became apparent on the photograph. Now only one physical interpretation was possible: The potential vortices of the leaf stimulated by high-tension still were in the plexiglas disc in weakened form! Here they swirl further and under high-tension furthermore produce corona discharge impulses.

Now also the students were convinced of the existence of the potential vortices.

This experiment stimulated the brain cells of the entire team: If potential vortices under high-tension cause electric blows, since the corona discharge is nothing else, then in this way the local vortex distribution in space should be measurable? One student immediately got down to work and build from the horizontal diversion unit of an old television a high-tension generator with an adjustable spark gap. Following he walked with his flashing and crashing device all through my laboratory and others walked with him and dragged the gauges behind them. But to their big disappointment they were not able to see an influence dependent on place.

Then it suddenly was clear for me: It would have done the students well, if they before would have had a bath and observed the drain vortex, "it suffices the famous wing stroke of a butterfly", I explained my team, "and instead come up with this infernal machine and chase away all the vortices, which we actually want to register ". We had to realize that as a rule phase of disillusionment follows the euphoria.

<i>: Klektor, Fachzeitschrift fur Elektronik, Mai 1977, S. 22-25: Kirlianfotografie; fig. 19.4 shows the wiring diagram and fig. 19.5 A the self-built device.

<ii>: The Kirlian photographs from the darkroom of the polytechnic are shown in fig. 3.6.



Fig. 19.5 A: A self-built high-tension device for Kirlian photography



Fig. 19.5 B: Kirlian photograph of the right hand

19.5 Measurement of dielectric capacitor losses in the HF laboratory

My convincing work clearly was shaped more complicated with my professor colleagues. Most pretended to understand nothing about it and kept themselves out. But there also are exceptions. „something like that has never been there at our polytechnic, that a colleague puts forward an own field theory ",a physicist colleague remarked after my lecture public to the polytechnic[i] at 3.7.1990 and meant, that must be celebrated. He festively let me cast my eyes in his store room, got out a few bottles of wine, which then some of my colleagues of physics emptied with me in their official room. Doing so we small talked about the sense or nonsense to fix on the education of physics to the Coulomb charges.

The head of the high-frequency laboratory showed likewise impressed. At last he now knew, why capacitors at microwave frequencies can become so hot that they solder themselves out of the circuit by themselves and can fall out, why PVC-films can be welded with HF, etc. „We have to prove that not the dielectric is to blame, as stands in the textbooks" he came towards me.
At least following my idea potential vortices are the ones, as I expressed myself, which are behaving dual to the eddy currents. It concerns vortex losses, thus a physical phenomenon. Eddy currents now can be damped as is well-known, by for instance sheeting the iron circuit for engines and transformers. The insulation between the sheets prevents the formation of eddy currents in that direction and the degree of effectiveness increases.
"I would suggest", I told my colleagues, „to "sheet" a capacitor in a dual manner and to measure the losses". Because eddy current losses increase with the square of the frequancy, we picked microwave frequencies. In the HF-laboratory a card with an L-C resonant circuit was made, we should be able to quite precisely determine the losses by means of its quality. The inductance was formed as a microstrip line and for the capacitor a socket was planned.
The carrying out of the experiment consisted of using single layered ceramic capacitors, so called trapezium capacitors, with a vapour deposited silver coating on both sides as a package and to measure the quality of the resonant circuit as a measure for the dielectric losses. According to the rules of duality the dielectric (as nonconductor) thus corresponds to the permeable transformer sheet (conductor) and the silver coating (conductor) to the sheet insulation (nonconductor). In a second experiment the silver coating now was removed and the same capacitor material measured at identical conditions this time uncoated. Will the losses increase or isn't changing anything?
Tension and nervousness suddenly could be felt, even among the students, who followed the experiment from the second row. All looks were pointed at the monitor of the network analyser, on which slowly the bell-shaped curve of the measured resonant circuit quality became apparent. The result was surprisingly clear. I first looked at my colleagues and then at the students and had to realize that all eyes were pointed at me. The first measurement was a bull's eye! The vortex losses "uncoated" were considerably larger.

<i>: K. Meyl: Die mangelnde Dualitat der Maxwellschen Gleichungen with contributions concerning the theme of magnetic space poles, the mathematical calculation and the technical-physical interpretation of newly discovered potential vortices. Invited by the rector of the FH Furtwangen at 3.7.1990

- experiment 1: quality of resonant circuit with coated capacitors

from a series of 5 separate experiments averaged: Q = 48

- experiment 2: silver coating removed with diluted nitric acid

possibly the acid has damaged the dielectric: Q = 9

- experiment 3: silver coating polished off mechanically.

low quality means high dielectric losses! averaged: Q = 28



- resonance sharpness (quality number):

$$Q = \frac{f_0}{\Delta f} \quad \frac{\text{(Resonance frequency)}}{\text{(Resonance frequency rang}}$$

at a resonance frequency f0 of approx. 400 MHz.



Quality number Q of the L-C resonant circuit

the dual ,,sheeted" capacitor has the lowest losses,
the resonant circuit with that the highest quality (experiment 1).

Fig. 19.6: Measurement of the dielectric capacitor losses over the quality of a resonant circuit in the HF laboratory at 11.06.1990.



Fig. 19.7: Measurement curve of the water temperature over time
at 22.10.1996 in the electrical engineering training

Observation: for the microwave oven the container despite the "after cooking-effect"
remains colder than in the case of a hotplate. Sensor: PT 100.

19.6 Analysis of the measured capacitor losses

First of all the colleague spontaneously prompted a common publication.

But a certain disillusionment had to await us. For the next measurement hardly a differemce could be detected. We varied the contacting and removed the silver coating. once with hydrochloric acid, once with fine sandpaper. Every measurement we repeated umpteen times and in the end had to draw the conclusion that the results for our somewhat unprecise construction fluctuated extremely.

Averaged over all measurements and methods, indeed a reduction of the dielectric losses for alayered capacitor resulted, but at a critical consideration of the errors the results seemed to "drown" in the mean variation. In the opinion of my colleague the visible trend wasn't sufficient to convince dyed-in-the-wool sceptics, whereupon he withdrew with the indication, I should try at the people of microelectronics, they more likely would be capable to reproducibly gain control of a layered construction.

The experiment at least let a legitimate chance open that the vortices of the electric field actually exist, and in the case of the delectric losses of a capacitor it concerns vortex losses<i>.

19.7 Microwave oven for testing in the laboratory of electrical engineering

"Volunteers first" was said at 22.10.1996 in the electrical engineering practical training and two students got down to work. I had brought along from our kitchen the microwave oven, a portable immersion heater, a kitchen stove plate and different containers. In the laboratory of the polytechnic I in addition had got hold of a Bunsen burner. In the sense of the "Stiftung Warentest" (institution to protect consumers in Germany, note of the translator) it concerned the question for differences in heating water; or following the public discussion, is cooking with gas more healthy than cooking with the microwave oven?

We wanted to know. So we cooked water, filtered by inversion osmosis, once with the gas burner. once with the hotplate and finally with the microwave oven. Switched off always was at the same moment at the same temperature, and the cooling down curve was recorded with an x-t-time recorder (fig. 19.7).

Between gas and electric cooker virtually no difference could be detected, but the microwave oven at switching off still showed an odd temperature increase. I already had remarked this earlier. If one takes a water glass out of the microwave oven, then the water again really bubbled off, although the container itself had remained relatively cold. If one on the other hand takes a water pot off the gas cooker, the water suddenly stops cooking. From where comes this difference, which also the experiment could confirm?

<i>: A result of my dual way of looking at the vortex losses is the representation in fig. 4.7.

A: damped wave equation:

$$\Delta \mathbf{E}\, c^2 = \delta^2\mathbf{E}/\delta t^2 + (1/\tau)\cdot\delta\,\mathbf{E}/\delta t$$

(wave) + (vortex)

B: open chain of reasoning in the physics of electromagnetism:


electric field strength
Faraday's law of induction
Potential density
E
rot E = - δB/δt - b
b
= 0 ?
without proof
Ohm's law
relations of material
dual law (not provable)
j = σ·E
D = ε·E
B = μ·H
?
j
j + δD/δt = rot H
H
current density
Ampère's law
magnetic field strength

C: for the stationary case $(\delta/\delta t = 0)$ in general representation:


B
A
open chain
relation not provable!
C
D

Fig. 19.8: ____ Contribution to the discussion about the impossibility, to prove, according to scientific methods, in a chain of reasoning (A-B-C-D) the last link (D-A), which closes the chain.

19.8 Microwave heating by decay of vortices

It has to concern a storing effect. In the case of an normal cooker the heat transfer takes place by convection. In the case of a microwave oven we however are dealing with an electromagnetic wave.

But in the wave equation nothing can be read about heat; here merely vortices can be found as a damping term (fig. 19.8 A)<i>! Therefore as the only possible interpretation is left that the microwaves roll up to vortices to fall apart themselves after a certain time.

Only at the vortex decay heat is formed.

The irradiated microwave power according to that is stored over a longer period of time as vortex in the water and the food. The vortex decay takes place according to an e-function with the calculated relaxation time constant tau<ii>.

From the circumstance that particularly water is heated up in the microwave oven despite the small electric conductivity but with high dielectricity, I infer that it has to concern mainly potential vortices, from which a biological effectiveness can be expected. The question if this should be valued positively or negatively, I have to leave up to the doctors and therapists. At least physically seen a difference is measurable. Thus a vortex decay will occur for a meal prepared in the microwave oven even if we already have consumed it.

Conclusion: I wish all: your health!

But what do I write about vortex losses, if every sceptic knows half a dozen alternative interpretations. Inevitably I have to bear in mind that also the eddy current heating owes its acknowledgement only the circumstance of the discovery of the corresponding laws. If Othm hadn't discovered his law and formulated it in the known form and instead the dual formulation would have been discovered, then we today would attribute the dielectric losses in a capacitor and in the microwave oven to the potential vortices, in the case of the transformer however the material would be responsible for the heating and not eddy currents, for which there then also wouldn't be a theory (fig. 19.8 B).

It actually is pure coincidence that at first Ohm's law and not the dual formulation had been discovered and acknowledged. But because both are equivalent, we also have to assume the correctness of both, even if the last link of a chain of reasoning A-B-C-D back from D to A in principle can't be proven anymore, since it already is explained by the chain A-B-C-D (fig. 19.8 C).

There I thus had discovered a potential vortex, without a possibility for a direct proof of existence. For that the textbooks are full with auxiliary explanations, with which physics successfully cheats past this important field phenomenon. I was frustrated. There had to be a way to measuring technically register the vortex in some way.

<i>: Fundamental field equation 15 in fig. 5.1 or equation 21, fig. 5.3

<ii>: Relaxation time constant: see equation 10 in fig. 5.1 or fig. 8.1


spherical electrode
antenna rod
coupling coil (1 winding)
Tesla coil (spirally wound flat coil)
oscillograph
adjustable capacitor (0 ... 500 pF)
L = λ/2
(wire length L of the spherical electrode to the earth = half the wave length)
grounding
(the earth as opposite electrode)

Fig. 19.9: Proof of scalar waves with the Tesla coil.<i>

<i>: The inverse use for a high-tension transmitter according to fig. 9.1

19.9 The Tesla coil from the workshop of handicrafts

I again retired in my workshop of handicrafts and wound flat coils or I pondered in my study over Tesla books. 1995 from several sides my attention had been drawn to the circumstance that the inventions of Nikola Tesla can be organized in three categories:

The first third has made him world-famous. It concerns the rotary field theory, the asynchronous engine and the today normally used alternating current technology, which we owe him.

The second third concerns technologies and inventions, which were rediscovered by other people partly only years later or even were only pinched and distributed as novelty under another name. Electron microscope, superconduction, electrolyte capacitor, fluorescent lamp, fuse. coaxial cable and a lot more count among that.

The last third however concerns inventions, which until the day of today still aren't understood and await their scientific explanation and technological use. Tesla himself called these achievements his most important inventions, but still owes us a scientific explanation. The scientific world also hasn't got a theory ready and doesn't know to do anything with it. Public research doesn't take place or is prevented by lobbyists.

What remains, are tinkerers of various educational background and qualification, who are trying hurd to comprehend the buried experiments of Nikola Tesla off their own bat in the garage or in the hobby cellar.

I felt like one of these, by winding one winding after the next from the inside to the outside. Then I soldered an antenna wire at the inner end of the flat coil, which I in Tesla manner connected electrically with a spherical electrode hung up under the ceiling. The opposite electrode should be connected to the outer end of the winding, it is said, and the distance between both should be as big as possible. If namely an electrode just is collecting, then the opposite electrode is repelling the same space quanta. According to Tesla's recommendation I did use the earth as opposite electrode and for that tapped the central heating or the grounding of the foundations.

To take signals only one to two windings as secondary winding were necessary. I connected them with an adjustable air capacitor from an old steam radio to a frequency determining parallel resonant circuit and looked at the taken tension voltage at the oscillograph (fig. 19.9),

I still had problems with the statement of Tesla, the coupling had to be made loose. Thus the question is asked, how loose? I after that organized two toilet paper rolls of different size, (after the toilet paper had been used, naturally) and pushed them into each other. The smaller toilet paper roll carried on the gable-end the flat coil as primary winding of the air transformer and the bigger one the coupling coil. Now by shifting any wanted degree of coupling could be adjusted to (fig. 19.10).

I was astonished myself. Tesla actually was right with his discovery of the scalar waves. With my arrangement they can be clearly distinguished from the Hertzian waves.

The following procedure is recommended:


spherical electrode
flat coil
coupling
adjustable capacitor

Fig. 19.10: The experimental configuration

First of all I seek a source of interference with the adjustable capacitor and tune to maximum amplitude. Then I change the coupling and further optimise in this way. If now the amplitude again decreases from a certain point while approaching the coupling coil, then it concerns the sought-for longitudinal waves. If namely the coupling is too tight, then the received vortices again are driven away by the effect back on the fiat coil. They make way.
At last I had found a method to catch the vortices in such a way that they not immediately "ran away" from me again. At once I presented them in the technology centre in St. Georgen. In the time following I improved the technology further and further, used bigger toilet paper rolls and eventually even turn up garbage cans, I varied wire length, wire diameter and the sense of winding (fig. 19.10).

I had very different success. Sometimes, if at the same time in my workshop of handicrafts the radio worked, it would look as if the received signal would synchronize with the sound waves. Both are longitudinal waves after all. With transverse waves something like that would be unthinkable.
One moreover could observe, how a resonance builds up: first slowly and then faster and faster, so that I sometimes got terribly afraid. Several times we had to repair our oscillograph, after the protective diode at the input amplifier had blown, and that for signals of 50 to 100 millivolt!
That was entirely impossible. Only individual spikes, which were too fast to be seen at the screen, could be to blame. In the case of distant thunderstorm activity I obtained maximum values of more than half a Volt. After that I undamped the grounding as fast as possible, so that no lightning would be caught, since I didn't have the intention to burn off my workshop.

19.10 Biological effectiveness of the Tesla coil

Also the biogical effectiveness of the Tesla radiation I could impressively prove with this device. 14.06.1997 a woman, who called herself extremely electrosensitive, participated in the weekend seminar about electrobiology, which I took over from Prof. H.K. Konig (TU Munich) after his death. That I wanted to test.
I hung up my device in the lecture auditorium and installed the oscillograph in such a way that all could see it. The voluntary test subject however could see neither the public nor the screen. One person every 5 seconds said "now" and the female candidate should say, if I had clamped or undamped the grounding, if therefore scalar waves were received or not. After a training round her proportion of hits was lying at 100 percent!

According to her statement she could feel it. A further test subject achieved even at the back of the room with a pendulum the correct answer. I myself was surprised by this and I already have repeated this experiment several times with different success. It without doubt depends on the sensitiveness of the test subjects. Every person after all reacts to other signals.

What however has astonished all participants and can't be emphasized enough at all, is the circumstance that it in this case concerns a receiver and not a transmitter!



```
20-Dec-99
16:52:07
2
50 ns
4.00 V
3
50 ns
50 mA
A: 3*2========
50 ns
200 mW

pkpk(A)          0.49 W
mean(A)          233 mW
sdev(A)          169 mW
rms(A)           287 mW
ampl(A)          0.49 W
50 ns
1 10 mV  DC
2 .2  V  DC
3 50 mV  DC            2  DC 5.12 V
4  2  V  DC
```

```
20-Dec-99
16:53:47
2
50 ns
4.00 V
3
50 ns
50 mA
A: 3*2========
50 ns
200 mW

pkpk(A)          0.46 W
mean(A)          223 mW
sdev(A)          148 mW
rms(A)           267 mW
ampl(A)          0.46 W
50 ns
1 10 mV  DC
2 .2  V  DC
3 50 mV  DC            2  DC 5.12 V
4  2  V  DC
```

```
20-Dec-99
16:47:08
2
50 ns
2.00 V
3
50 ns
20.0 mA
A: 3*2========
50 ns
50 mW

pkpk(A)          104 mW
mean(A)         49.1 mW
sdev(A)         36.1 mW
rms(A)          60.7 mW
ampl(A)          104 mW
50 ns
1 10 mV  DC
2 .1  V  DC
3 20 mV  DC            2  DC 2.56 V
4  2  V  DC
```

Measurement record

System resonance:
f = 6,7 MHz, Sinus.

distance transmitter-
receiver: approx. 2 m

transmitter coil with
HF-braid identical
to receiver coil:
38 Windings wound
spirally and
33 Windings wound
cylindrically.

Load for receiver:
metal layer resistor
(100 Ohm)

Gauge: Quad 200
MHz Oscilloscope:
LeCroy 9304C

Current sample:
LeCroy AP015
(DC-50MHz)

Differential sample:
LeCroy AP032
(Attenuation
Rate: 1/20)

Top: transmitter
power consumption
with receiver turned
on (at 100 Ω-load):
233 mW

Middle: transmitter
idle power: (without
receiver) 223 mW

Bottom: receiver
power output:
49,1 mW

Fig. 19.11 A: Measurement record for scalar wave transmission line

19.11 Wrestling for measuring technical insight in the Transfer centre

In the central question who should be believed more, the famous experimental physicist Nikola Tesla or his critics, my experiments with the Tesla coil were the visible proof that we have to take Tesla's statements seriously. Now not only at myself, but also at the students of the polytechnic and the colleagues of my Transfer centre a true Tesla euphoria broke out.
In every free minute the patents and original writings were studied, which I had myself send from the Tesla Society in Colorado Springs in the USA. In particular my trainees and diplomands developed a incredible ambition in making a historical Tesla concept work. They built a whole series of various high-tension generators. In the laboratory one could hear crashing and there was a smell of ozone.

22.1.1998 at a presentation of the works for a degree the candidate looked after by me very proudly held a fluorescent lamp in his hand, which in the field of his self-built high-tension generator glowed even without any wire connected, entirely according to the great mode (fig. 17.10). At all efforts we however laboratory technical weren't able to reach tension voltages of above 511 000 Volt. But at this tension voltage the actual Tesla effects actually start!

Perhaps it was tough luck, but possibly also a chance that we in the laboratories, which I had at my disposal, were forced to work with lower tension voltages and that meant that we gradually had to beak away from the Tesla designs.
Moreover we hadn't at our disposal the precisely controllable spark gaps, which Tesla had developed and used. If one wants to obtain an if possible high tension voltage change (du/dt) for an interaction with neutrinos, then according to today's technology considerably more favourable concepts are offered, for instance with hard switching Power-MOS-Transistors. 50 Kilovolt per microsecond were to meet.
Therefore we changed the technology and worked from now on with fast semiconductor switches. From the laboratory radio now only a hissing and crashing came out of the loudspeaker, if our experiments were running.

At 12.10.1999 we for the first time succeeded to build up a transmission line for Tesla radiation. Doing so the transmitter and receiver were situated in different rooms of my transfer centre. The transmitter coil was operated in self-resonance and fed only from a small function generator with 10 Volt. But if the diplomand held a fluorescent lamp near the spherical electrode, then it started to glow!
Following I observed at the oscillograph the signal of the receiver coil, which as well was operated in resonance. If the diplomand switched off the transmitter, also no receiver singnal was present anymore. But if it concerned radio waves according to Hertz or Tesla radiation, with that still wasn't answered.
Therefore I prompted still another experiment. This time the colleagues observed at the transmitter the signal at the function generator, while I undamped and again clamped the receiver. The shouting with joy from the adjoining room indicated that it had been observed, how the receiver reacted upon the transmitter and both are in resonance with each other. Such an effect characteristic for scalar waves, is a radio technical impossibility! In the case of radio with Hertzian waves an effect back from the receiver on the transmitter is unthinkable by principle.


spherical electrodes
receiver, tied to a carriage
transmitter

Fig. 19.11 B: Scalar wave transmission line according to Tesla
f.l.tr.: M.Andresen (diplomand), author (TZ-head), Dipl.Ing.M.Rehm (project leader)

In the next step we let glow the famous little lamp on the side of the receiver. As a consumer served a small light-emitting diode, of which the light intensity remained unchanged in the case of resonance. To prove this, we placed the receiver on a carriage and rolled the corridor in the TZ up and down with it. If the receiver was only slightly out of tune, then from the then arising fluctuation the standing wave nature could be observed perfectly.

With the setup it can be demonstrated well, how the law of the square of the distance, of the decrease of the field strength with the square of the distance, known from radio technology hasn't got validity anymore for scalar waves. Very clear also was the energy transmission of scalar waves out of a closed Faraday cage.

In the end we have determined the degree of effectiveness of the scalar wave transmission line. An output power of 49 mW resulted from the measurements of the current and tension voltage for a loading of the receiver with a 100 Ohm resistance. Simultaneously the power taken up by the transmitter amounted to 233 mW. If we however subtract the idle power consumed by the transmitter from this, and that was determined to be 223 mW for switched off receiver, then actually only 10 mW are available for the wireless energy transmission. The degree of effectiveness according to that would be 490%!

If we here really have obtained an over-unity of 4.9 then the receiver must have collected along free space energy, or did some parts evade our power measurement? The sceptics I recommend an own rebuild, since alone the proof of the scalar wave properties inevitably has to lead to every Maxwell burdened HF technician breaking with the old belief.

19.12 Neutrinolysis, the alternative splitting of water

Free after the plans of Stan Meyer we filled diverse containers with water and let it "crash". If then bubbles raised and it got exciting, we changed the frequency and exactly paid attention to the effect remaining the same or if it increased as well with increasing frequency, thus if we only watched a classical electrolysis, or already the wanted "neutrinolyse", as we were accustomed to term the splitting of water in its parts under the influence of neutrinos in the laboratory. Typical for that is a bubbling and "cooking" of the actually cold water produced by the rising gas bubbles (fig. 19.12).

We also have reversed the principle. Doing so we have switched the container as neutrino receiver and measured the forming charge carriers. The passive system proved to be really moody. On the one hand tension voltages of several hundred millivolts at a load resistance of 10 megaohm can be realized, on the other hand the charged gas particles and the as secondary reaction in the water set free ions continually change the electric conductivity, so that the cause to be measured, the neutrino radiation, hardly can be reproduced on the displayed result. The water hence has to be changed more often and also the developers found themselves between jubilation and disillusionment subject to continually changing feelings.

<i>: A. und I. Schneider: Neutrino-Power - Energie aus dem Kosmos, Bericht zu Vortrag und Demonstration des Autors am 25.11.99 in Villingen, NET-Journal 12/99, S. 4-6; Interview mit Prof. Dr.-Ing. Konstantin Meyl: Durchbruch in der Freien-Energie-Forschung, NET-Journal 12/99, S. 7-9



Fig. 19.12: Experimental constructions for the „neutrinolyse“.


Neutrino radiation from the sun
moon
(acts like a
focussing lens)
focussing of the
neutrino radiation
N
15,1°
focus
earth

Fig. 20.1: Course of the neutrino radiation focussed by the moon on the occasion of the eclipse of the sun at the 11th August 1999.<i>

concerning the calculation of the position of the sun at 11.8.99:



at 21.6. after 0 days is	$23.4° \cdot \cos 0° = 23.4°$	northern latitud
at 21.9. after 92 days is	$23.4° \cdot \cos 90° = 0°$	= equator
at 11.8. after 51 days is	$23.4° \cdot \cos \frac{51 \text{ days}}{92 \text{ days}} 90°$	$= 23.4° \cdot 0.644$ $= 15.1°$ n. lat.

At 11.8.1999 the sun at noon stands above latitude 15.1.

<i>: Konstantin Meyl: Zur Brennglaswirkung des Mondes bei einer Sonnen-

20. Cosmic experiments

As long as no usable technical gauges are available, we should observe and study nature and all celestial phenomena. Here the scalar waves with all their properties are presented to us. That is valid in particular for the case that the cosmos makes an experiment with us and with the entire earth. Such a situation offered the eclipse of the sun of August 11 1999 as an unique "bulk experiment" to which travelled millions of spectators, to participate in the cosmic experiment as voluntary test subjects.

My warning for possible influences proved to be absolutely justified afterwards, even if only comparatively few took note<i>. In view of strong changes in the EEG of individual test subjects and a proven temporary acceleration of the rotation of the earth science once more stands before insoluble problems.

To answer the open questions I want to start with my indications, which 1 have published in anticipation of the cosmic event of August 11<i>. Afterwards a revision and the attempt of an interpretation from the scalar wave view follows. Perhaps this way leads to a reliable prediction of of earthquakes and other cosmic events. After that we perhaps know more about origin, availability and further important parameters of the sought-for space energy.

20.1 Millions of voluntary test subjects at 11 August 1999

Astronomically seen, it concerns a harmless natural spectacle as it already was observed more often, if the moon glides between sun and earth and its shadow in broad daylight immerses parts of the earth in a dark night. The special thing about the eclipse of the sun of August 11 1999 however was, that the sun activity just strived for its maximum value in its eleven year cycle, and the orbital distance to the moon simultaneously reached a minimum value. In addition we must pay attention to the special situation of the angles (fig. 20.1). Due to the extremely rare constellation the area of complete shadow at first was larger and darker than normal. On August 11 it had a width of 110 kilometres.

The sun besides the light also sends us solar neutrinos and for those the moon is transparent. It with regard to them acts like a glass ball, which lets the light it is true pass through, but in doing so refracts it. The glass ball acts like a convex focussing lens, which focuses the arriving rays behind the ball in a focus.

To slow down and collect neutrinos the moon it is true is too small, but it will be able to influence the flying direction. Very fast neutrinos, which run through the moon, hardly will be diverted. The slow and biologically active ones however will be bent stronger.

At this point it would be of utmost importance to know, in which distance from the moon the rays run together and combine into a focus.

<i>: Konstantin Meyl: Zur Brennglaswirkung des Mondes bei einer Sonnenfinsternis, NET-Journal, Jg. 4, Heft Juli/August 1999, Seite 13-17


focussed neutrino
radiation
Ulm
N
scattering 51 km
area
X
northern tropic
(at 21.6.):
position of the sun
(11.8.):
33,3°
15,1°
6378 km
equator (21.9.)
3500 km
inhabited
surface
of the earth
earth's
core
earth's mantle with
earth's crust

Fig. 20.2:_____The course of the focussed neutrino radiation at 11.08.1999 for 48.4° northern latitude. (this corresponds to the line Ulm-Augsburg-Freising)

calculation of the critical latitude:

$$\sin \alpha = \frac{3500\ \text{km}}{6378\ \text{km}} = 0.5488 \quad \text{resulting in the angle} \quad \alpha = 33.3° + 15.1°$$

The neutrino rays touch the earth's core at: 48.4° n.lat.

minimum distance to the moon: $r_m{}^* = 358000$ km
radius of the moon: $R_m = 1738$ km
radius of the earth: $R = 6378$ km (at the equator)
length of the Tangente: $X = 3500$ km/tan 33° = 5332 km

$$\text{scattering radius: } r_x = X \cdot \frac{R_m}{r_m{}^* + X} = \underline{25.5\ \text{km}} \text{ around the centre line}$$

Focussing without scattering on earth's surface increase to
$R_m / r_x =$ 68 times , resp. with scattering to
68 * 0.5* 0.8 = 27 times the natural neutrino radiation!

For that we again bear in mind that neutrinos as particle radiation propagate in space in the sense of a plasma wave. Since the oscillation of such a longitudinal wave takes place in the direction of propagation, it neither knows a distinct velocity of propagation nor an upper limit.

The sea of neutrinos in which we swim, is a combination of differently fast particles. The slow ones are bent stronger by the moon, with the property of a convex focussing lens, so that the focus should be looked for near the moon, whereas the fast ones hardly are diverted. Their focus lies further distant from the moon than the earth, up to the extremely fast cosmic neutrinos, which experience almost no diversion, because they, as a result of the Lorentz contraktion, are small enough to tunnel through any kind of matter.

If neutrinos, depending on their velocity of propagation, have their focus partly before and partly behind the earth at an eclipse of the sun, then it comes up to a conclusive logic that there actually exist such, of which the focus lies exactly in the centre of the complete shadow on earth's surface. But thereby the question is asked, which biological effectiveness these neutrinos have or which damage they bring about.

20.2 Model of calculation for the cosmic experiment

More than a year ago the results of an international neutrino experiment have been made public. Thereby for the first time the order of magnitude of the natural radiation density was recorded. after the detector before having been calibrated at an artificial source of neutrinos. As the perhaps most important result at night only half as much solar neutrinos could be detected as during the day with the immense Super-Kamiokande detector in a Japanese mine. With that the here taken interpretation, that earth's core collects neutrinos, meanwhile even is proven experimentally! For that it has to interact with the particles and that means, it has to exert a force of attraction on them. Thus the earth's core during an eclipse of the sun will further amplify the effect of focussing if the konzentrierte neutrino ray is directed on earth's core. This critical point we have to calculate (fig. 20.2).

The proportion of the radii of earth's core (3500 km) and the entire earth (6378 km) results in the sine of the sought-for angle and that amounts to 33.3 degrees northern latitude. At August 11 moreover is added that at noon the sun with regard to the equator is standing at 15.1 degrees. so that a first extreme focussing should be expected, if the centre of the complete shadow intersects latitude 48.4. This would be the case for the latitude of Ulm in direction Augsburg and Freising.

Now we would like to know more about the amplitude of the focussed radiation, about the spatial extension and the period of time. Without concrete data material we have to proceed from several simplifying assumptions. If we therefore assume, 50% of the at earth arriving and biologically relevant neutrino radiation stems from the sun, which in the case of an eclipse of the sun is focussed to 80% and scattered to 20% by the moon. If we further assume the focus just touches earth's core, then between Ulm and Augsburg a sphere of action of 50 km can be expected, within which the neutrino radiation on the average reaches 28 times the value of the natural radiation. The intense irradiation under these assumptions will last one minute.



Fig. 20.3: ____ The spatial distribution in the case of focussing of the neutrino radiation by means of the burning glass effect of the moon on earth's surface.

Of course the calculated values only are valid to the extent, as also the assumed boundary values apply. After August 11 we know more about this cosmic experiment, about the spatial distribution and indirectly about the interaction with earth's core, about the physical properties and the biological effectiveness of the at present available neutrino radiation.

20.3 Physical technical consequences

The neutrino radiation is a scalar wave radiation which, as mentioned, can be perceived by sensitive people even without aids. Who hasn't at his disposal this sensitiveness, is recommended a simple setup.

For that one hangs up a fluorescent lamp, connects the one end with a piece of wire, as it were as antenna, and the other end is grounded. For a scalar wave radiation which increases fast, the lamp should start to glow by itself. Under big transmitting installations this method already has been successfully applied by many allotment gardeners thousandfold. I hence recommend all research scientists of eclipses to test themselves the possible field fluctuations in this simple way.

From a technical viewpoint first of all the atomic reactors and their nuclearly contaminated waste will be concerned by a fluctuation of the neutrino radiation. In view of present eclipses of the sun an accident can be expected less, since the neutrino radiation it is true for a short time reaches an extreme maximum, which averaged temporally and spatially over the whole event again is relativized somewhat. The relations shall be clarified with an example (fig. 20.3).

Whoever places himself in the centre line of the complete shadow on August 11, at first will detect a decrease of the neutrino radiation to 50 to 60 percent, then a steep increase to 2800 percent and from the summit again the whole backwards, while standing on the earth he turns by under the moving moon shadow. The ring with half the radiation, which reaches us first, doesn't pose a problem since, as said, we only have half the radiation in every night. Some animals and plants as aresult erroneously will set out for sleep.

The wave distribution one can imagine like that in the case of a pool, in which was thrown a stone. But we still don't know the resonance frequency, for which reason the length of the cycle depicted in fig. 20.3 is chosen arbitrary. The actual deviation from the distribution given by nature is the peak in the focussed ray centre. Living nature must stand large fluctuations of the solar radiation, since every supernova sends us a relatively short batch of fresh neutrinos. Where we have difficulties is the question, how much fluctuation still can be tolerated by mankind.

The question for possible biological consequences is due to be dealt with in view of the announcement of a complete shadow tourism causing concern, as it is awaited for August 11. At the incomplete state of knowledge about the properties of neutrinos, every trip to the complete shadow remains a journey into the unknown.



Fig. 20.4 A: The course of the complete shadow for the ancient eclipse of the sun at 28.5.585 B.C.


Kaiserslautern
Mannheim
Saarbrücken
Heidelberg
Nürnberg
Heilbronn
Karlsruhe
Stuttgart
49°
Regensburg
Ettlingen
Rastatt
PF
LB
WN
Aalen
Baden Baden
Calw
ES
Göppingen
Donauwörth
Ingolstadt
Straßburg
Sindelfingen
BB
HDH
Landshut
Pass
48,4°
Offenburg
Tübingen
NT
K/T
Geislingen/Steige
Augsburg
RT
Ulm
Günzburg
Freising
Erding
Mühldorf
Rottweil
Dachau
Altötting
48°
Garching
Waldkraiburg
Freiburg
VS
Sigmaringen
FFB
LL
München
Memmingen
Starnberg
Weilheim
Rosenheim
Bad Tölz
Salzburg
Basel
Konstanz

Fig. 20.4 B: The course of the complete shadow over south Germany at August 11 1999 (grey) and the possible course of the focussed neutrino radiation (white).

20.4 Biological consequences

In the case of an eclipse of the sun effects on the biology, like problems with the heart among affected, at least can't be excluded. If the scalar wave density increases above the density which is normal, then this has a positive effect on the economy of energy, as long as the body is capable to regulate the amount taken up. If the regulatory process however should fail. then the risk of a self-inflammation exists. Also straw bales and other organic and inflammable materials could thus go up in flames.

But before that happens, first the information technical influence of the scalar waves will show. Here we have to expect a psychotronic influencing, which is showing in a limited ability of perception. History teaches us as an example<i> that a by Thales of Milet predicted total eclipse of the sun at 28.5.585 B.C. compulsorily has ended a battle in Asia Minor between the Medes and the Lydians, because the soldiers apparently most literally had gone out of their mind (fig. 20.4 A).

Actually all in connexion with the free energy addressed phenomena are conceivable. from the "neutrinolyse" up to the acceleration of the radioactive decay. It would be understandable, if in a water glass bubbles should rise, even if no carbonic acid is contained in the water at all. After man not having at his disposal a sense organ for his own energy source, the brave in the complete shadow of an eclipse of the sun are recommended smaller technical experiments and observations. The cautious however will avoid the area from the start.

As counter movement to the complete shadow tourists there will also be refugees, who believe in the predictions of Nostradamus, who in his quatrains has predicted a messenger of fright over Europe for 11.8.1999. He mentions Lyon, Ulm and Moskau, which actually lie on one line<ii>.
The line of the complete shadow however will run under another angle from Plymouth in South England over Ulm to Bukarest and further into Turkey. Maybe Nostradamus wasn't a clairvoyant at all, but merely a good calculator, or he knew someone who could calculate excellently, after all he has indicated the time and even Ulm as the centre correctly. Apart from the small angle error, in addition the direction is correct (fig. 20.4 B).

Worth paying attention to also is, that he contrary to his habit here gives a concrete date which astronomically can be calculated unambiguously, that he simply skips the numerous eclipses of the sun of the past and only points to the one of 11.8.1999, which runs crossways through South Germany. Extremely sinister are his forecasts, which mustn't commented on further, since he speaks of "Mort et Tombe", of death and grave<ii>.

<i>: Merodot: Historien, Kroners Taschenausgabe 224, S. 33 (cf. page 586 and the modern misinterpretation note 9 on page 754); further sources: dtv-Atlas zur Weltgeschichte S. 45; resp. Propylaen-Weltgeschichte I, S. 168.

<ii>: Michel de Notredame (1503 bis 1566), Mathematiker, Astrologe, Leibarzt von Konig Karl IX: Centuries (1558) X, Vers 72.


Eclipse of the sun
Eclipse of the sun of
-160 -140 -120 -100 -80 -60 -40 -20 0 20 40 60 80
-20
-40
-60
-80

Fig. 20.5 A: The total eclipses of the sun of 18.4.1539 and 21.8.1560



Fig. 20.5 B: Under the impression of the last two eclipses of the sun over Europe death and war play dice about the fate of mankind during the eclipse of the sun of 1562.<i>

<i>: Werner Raffetseder: Sonnenfinsternis, Hugendubel Verlag, Munchen 1999, ISBN 3-89631-302-9, Seite 156.

20.5 Epilogue to August 11th 1999

My indications have been published two weeks before the cosmic event in the NET-Journal[i]. The public interest was immense. Now, after the spectacle is over, it is time for an analysis[ii].

Besides numerous very subjective descriptions of eyewitnesses, which scientifically hardly can be analysed, at numerous polytechnics over the world has been observed, how Foucault pendulums suddenly and completely unexpected have deviated from their normal swinging direction. With this device 150 years ago the rotation of the earth had been detected in Paris.
Since according to prevailing textbook opinion an eclipse of the sun is a purely optical phenomenon, the scientists world-wide are having a big problem. Which force here has teared at our earth and caused relative accelerations of the kind that the pendulums could turn out of their usual plane and changed into an elliptic orbit, while the shadow of the moon ran over us? The gravitational force isn't even roughly capable to that. That merely has brought a 50 cm higher flood. The enormous force effect, which even puts the gravitation in the shade, actually only can come from the interaction of the neutrinos.

Different reports are present concerning the influencing of the radioactivity. In the cases, in which measurement samples have been used, almost no change could be observed. This is confirmed by a video tape, which northeast of Munich directly in the centre of the complete shadow documents an experiment, in which during the whole time the radioactivity of 1 kg crude granite is monitored with a professional dosimeter. The background might be that calibrating samples are chosen in principle under the aspect of being influenced the least by outside interference sources. It therefore would have been better, if we instead had put a lettuce as a biological and broadband sample in front of the device. Because there, where one anyway hadn't expected deviations and thus neither were measured calibrating samples nor unfortunately were made recordings, is said to temporarily have occurred a visible increase.
Even in the case that somewhere accidentily should exist recordings, the increase is too small, to help explain traditions from the Middle Ages, according to which is talked about "stinking log" and about "aggressive damps, which fall from the sky". Other sources speak of harmful radiations, which one regarded as the trigger of plagues.
It is said: "They poison the drinking water and the crops and make people sick"[iii]. Crops after an eclipse of the sun either should not be harvested at all or only after a violent shower. The warnings for a poisoning "without adding poison", which reach back into the 19th century, suggest the assumption that it concerns results of a radioactive contamination.

<i>: Konstantin Meyl: Zur Brennglaswirkung des Mondes bei einer Sonnenfinsternis, NET-Journal, Jg.4, Heft Juli/August 1999, Seite 13-17

<ii>: From the third and extended edition of this second part concerning Electromagnetic Environmental Compatibility the following chapters are completed.

<iii>: Mark Littmann/Ken Willcox: Totality - Eclipses of the Sun, Honolulu 1991, Kapitel 4: Eclipses in Mythology; nachzulesen bei Werner Raffetseder: Sonnenfinsternis, Hugendubel Verlag, Munchen 1999, Seite 130/131.


1. fist point of intersection
Second point of intersection
complete shadow at 5.5.840
projection of earth's core with 7000 km diametre

Fig. 20.6 A: Eclipse of the sun of 5. 5. 840 AD.

Fig. 20.6 B: Nostradamus announces catastrophes for 1999 in the Centuries of 1558.<i>

<i>: Bryan Brewer: Eclipse, Chapter 1: Eclipses Throughout the Ages, Seattle WA 1991, S. 20, cited in Werner Raffetseder: Sonnenfinsternis, Hugendubel Verlag, Munchen 1999, ISBN 3-89631-302-9, Seite 130, Bild Seite 159.

20.6 Dropping of the neutrino radiation

Plagues of that kind, which in the Middle Ages have claimed lives as a result of an eclipse of the sun, hardly are verifiable, unless a prominent victim was among them, like e.g. the son and successor of Charlemagne, emperor Ludwig I. He 5.5.840 witnessed an eclipse of the sun with a totality of five minutes. Further it is said: „The fright which this experience gave him, little later shall have torn him to death"<i>.

According to that there must have existed times, in which the radioactivity present in the countryside and stored in the body of a person during an eclipse of the sun could be set free and be the undoing of the affected. At the same time such a decontamination of radiation acts cleaning for nature.

In this case only the interpretation of Nikola Tesla provides us an explanation, which states that the neutrino radiation causes the radioactivity<ii>. Textbook physics however doesn't know this causality. For that the primeval fears of humanity are pure superstition. The prophesies of Nostradamus even are referred to as counter evidence.

But the question remains open, why his predictions concerning August 11 didn't happen, Obviously, so has shown us the cosmic experiment, the neutrino radiation relevant for the setting free of radioactive radiation drastically has decreased since the Middle Ages.

Nostradamus personally has occupied himself with the translation and interpretation of hieroglyphs and has written down his insights - surely out of fear of the inquisition - in the form of encoded quatrains. According to that he has based his considerations on considerably older sources, which presumably stemmed from a time, in which a considerably higher radiation prevailed.

We have to proceed from the assumption that the scientists of the Semitic- Aramean people of the Chaldeans, which ruled Babylon from 626 B.C., were just as capable as astronomers of today, to exactly calculate an eclipse of the sun even centuries and millenia in advance.

After all the Saros-cycle to determine eclipses of the sun is a discovery of the Chaldeans. What they however couldn't know and we ourselves still can't indicate today, is the prevailing density of the cosmic radiation at a future time. But that obviously has changed considerably.

The natural magnetic field strength for instance is recorded at the baking of earthenware jugs and vases, by strengthening along the parts containing magnetite. From the measurement of ancient earthenware goods we know that in antiquity a field strength must have prevailed which was 3 to 4 powers of ten higher.

According to the here presented theory the earth owes its magnetism its core and that again draws its energy from the neutrino field. According to that also the neutrino radiation should be subject to the same decrease.

If therefore the Babylonians out of the radiation situation at that time in the interpretation of Nostradamus and other fortune-tellers, who presumably all more or less have written each other off, have predicted a catastrophe for 11.8.99, then this scientifically is just as untenable, as the today widespread hubris, with which the knowledge and the reports of experience from ancient times are dismissed as superstition.

<ii>: cf. chapter 17.2 Nikola Tesla, the discoverer of the neutrino radiation, p. 133


1st.point of int.
second point of intersection!
complete shadow 11.8.1999
projection of earth´s core

Fig. 20.7 A: Eclipse of the sun of 11.8.99 (declination: 15°)


In comparison: complete shadow 26.2.1998
second point of intersection!
projection of the earth´s core

Fig. 20.7 B: Eclipse of the sun of 26.2.98 (declination: - 9°)

<ii>: Particularly violent earthquakes since 11.8.1999 (excerpt):
Turkey 17.8. (strength 7.8) till 19.8. (5,0), 31.8. (5.2), Greece 7.9. (5.8). Turkey 13.09. (5.8) and finally Taiwan 20.9.99 (strength 7.6) in a rythm of 6 to 7 days! Complete list in the internet under:
http://www-seismo.hannover.bgr.de/ermos_listing.html

This "superstition" mentions tremendous natural disasters like floods like the Flood or destructive earthquakes often as a direct result of an eclipse of the sun, and as the worst consequence the end of the world<i>.

Almost all reporters and newsreaders in the evening of August 11 full of irony pointed at the non-occurrence of the end of the world and spread the conviction that according to prevailing physical ideas something like that isn't possible at all. They at that time couldn't know that the anatolic plate, which the complete shadow had crossed, had gotten into motion. The relatively weak earthquakes, which 11.8. shook Cyprus and at the same time Iran, only were spontaneous harbringers.

In the following weeks the staggering core of the earth made us clear that there had been done force to it. Severe earthquakes with thousands of aftershocks followed each other and one message of terror chased the next<ii>. Public authorities however take care not to of decline to make a reference to the eclipse of the sun.

20.7 Analysis and comparison of the occurrences

If we for comparison consult the total eclipse of the sun of 26.2.1998, for which the complete shadow of the moon coming from the Pacific Ocean had run over the Caribbean into the Atlantic Ocean. Exactly the moment it crossed the Caribbean island Montserrat, the volcano Soufriere erupted.

Pure coincidence says science, which hasn't got an explanation model at all for a relation with the supposedly purely optical phenomenon. But this argumentation is relativized, if according to fig. 20.2 the tangential collecting of solar neutrinos by earth's core is considered. This process best can be compared with photon radiation, which is tangentially collected and directed into an orbit by a black hole inside the radius of Schwarzschild.

Since the shadow of the moon always draws a straight line on the earth, two points of intersection are present with the circle of the projection of earth's core on earth's surface, for which the radiation focussed by the moon just touches earth's core and in that way experiences an additional concentration. The first point of intersection at that time was situated in the Pacific Ocean; but the second one was situated exactly at the Caribbean island Montserrat (fig. 20.7 B).

This time, at August 11 1999 the first point of intersection was situated in South Germany, the second in Iran, and again the focussing at the second point of intersection has shown a devastating effect. The entire continental plate has gotten in motion (fig. 20.7 A).

Another strange phenomenon has occurred in the USA at the same time as the eclipse of the sun. A tornado swept with its destructive force right through Salt Lake City. It is remarkable that no meteorologic indications were showing before and hence official observation authorities had no possibility of warning for the tornado. Had here part of the focussed neutrino radiation been redirected at earth's core and given a rotation, to again screw out into the sky on the other side of the earth at Salt Lake City?

<i>: Werner Raffetseder: Sonnenfinsternis, Hugendubel Verlag, Miinchen 1999, ISBN 3-89631-302-9, Seite 120.

<ii>: Collection of particular violent earthquakes since 11.8.1999: see fig. 20.7.


Ekliptik
Hyaden
Milky Way
(Betelgeuse)
Belt of Orion
Observation horizon
(M42)
Dahschur
Memphis
Ayan
Nile
Gizeh
Latitude 30°

A: The constellation of Orion B: The sanctuary of Osiris

Fig. 20.8 A and B: The ancient Egypt pyramids, a terrestrial model and copy of the starry sky?<i>


Betelgeuse
Zeta Orionis
Sirius
Beta Ursae Minoris
Alpha Draconis
South
North
Pyramid of Cheops

Fig. 20.8 C: The orientation of the four shafts of the Pyramid of Cheops to four different stars around the year 2500 B.C.<ii>

<i>: Robert Bauval, Graham Hancock: Der Schlussel zur Sphinx (Keeper of Genesis), List Verlag Munchen 1996, ISBN 3-471-77188-3, S. 286 und 287.
<ii>: dito page 86.

20.8 Radioactive decontamination with the help of a supernova

A mighty source of neutrinos forms the black hole in the centre of the Milky Way. For us, on an outer spiral arm of the galaxy, the distance to the centre is gigantic as well, so that a relatively equally distributed spectrum of differently fast neutrinos arrives at our world, which represents a kind of basic energy technical supply for the solar system and our world. For the fluctuations between day and night, or the focussing by the moon or other planets the "participants" in the solar system are responsible themselves.

In contrast to that a supernova, the explosion of a star, is a considerably smaller source of neutrinos, which however also is possible less distant to the earth. In addition it is a singular event, in which all neutrinos are set free simultaneously within a fraction of a second. They arrive at us one after another. First the fast and hard radiation reaches us as it were as harbringer. In the course of time the arriving neutrinos then become slower and shower, until they sometime become biologically relevant. If in the end everything is over, we can see the cause, only now the supernova is showing in the telescope.

If we assume such an event takes place, with perceptible might and in a distance of 500 light years. then this neutrino radiation overlaps with the general background radiation and a characteristic over-intensification of neutrinos of a certain velocity of propagation occurs. This problem then occupies us for 500 years, where the respective radiation situation permanently is changing depending on the time after the explosion.

If we in this way of looking dare a judgement of the cosmic events in historical time, so makes believe much the assumption that the radiation in the last hundred years has worn of completely. Edgar Cayce treats in the book "Our Ancestors" different cultural circles from the old Indian up to the Hopi, in which still is talked about an energy technical use of quartzes and other materials<i>.

We indeed can theoretically comprehend that the neutrino radiation can let an oscillating quartz glow, if it is stimulated in its resonance frequency, but technically the technology foday can't be realized anymore. Possibly the chance for technological use only existed for a few years or decades.

Presumably also the pyramids originally have been built as resonators, to slow down fast neutrinos to a technically utilizable speed. But in the course of time the original function was unnecessary and the neutrinos had gotten so slow that in antiquity alternatively an use as electrostatic lightning generator or as Nekropolis took place. Today they only stand in the countryside as unusable monuments of a gone epoch.

Many ancient techniques, to which I will come to speak in the third part, in this way just as unexpected become plausible as the radioactive decontamination described in the Middle Ages.

<i>: Hermann Wild: Technologien von gestern, Chancen fur morgen; Jupiter-Verlag Bern 1996, ISBN 3-906571-13-0, (z.B. S. 77 und 145 bis 163).


Constellation at 23.9. around 10500 B.C. at sunrise:
Gemini
Leo Minor
Ekliptik
(Betelgeuse)
Cancer
Canis Minor
Orion
(M 42 Orion-nebula)
Leo
sunrise
Osten
Süden
Sphinx-complex
Gizeh
Westen
Norden

Fig. 20.9: The orientation of the pyramids of Giza makes believe
an operation of the installation around 10500 B.C.[i]

[i]: Robert Bauval, Graham Hancock: Der Schlussel zur Sphinx (Keeper of Genesis), List Verlag Munchen 1996, ISBN 3-471-77188-3, S. 324.

The two research scientists take the hypothesis of an orientation of the ancient Egypt pyramids after the starry sky around 10500 B.C. This however is not compatible with their thesis of the aligning of the shafts to individual stars around 2500 B.C. (fig. 20.8 C). How should the precise worked shafts later have been integrated? It would correspond a certain logic, if an orientation of the buildings to the energy source at that time would have taken place; but doing so it should be taken into consideration that the stars are exploded as supernovae and today hardly might be observable.

Despite several good ideas more questions are raised by the book, than are answered. Have the technicians 2500 B.C., after making restorations, experimented with the buildings and sought-for alternatives of use?

20.9 Fre energy from the Orion constellation

After all hundred years ago still the last unreliable rests of the wearing off neutrino radiation were available to Tesla, Moray, Keely and other inventors for the experimental proof of free energy, of which we today aren't able to rebuild and show in function one single model. And that, although the technical aids have gotten better for many times. But for the free energy inventors that isn't a reason, to immediately stop their efforts, because the next supernova already is announced by the actual swings of the Foucault pendulum. It could concern the explosion of the giant red star Betelgeuse in the constellation of Orion in a distance of 500 light years<i>. It well may be possible that it already shortly has exploded and that it will supply us with fresh and free energy for scarcely the next 500 years and at the same time will give the earth a good shake, thanks to its might and a not too great distance.
The reaction, which happened after August 11, of earth's core, which is the first to interact with the fast particles, should make every astrophysicist clear that here something is coming towards us!
It would be obvious, if the reactions of earth's core still increase. Every year particularly around 21.6., if the sun is standing in the Orion constellation, deviations can be expected. But then the supposed source of neutrinos, Betelgeuse, the sun and the earth don't exactly form a line, because the giant red star lies 7.4° below the ecliptic. Because of that the rays slowed down and focussed by the sun run away over the earth. At the earth then rather would be expected a dropping of the radiation.
If the phase of shakes of the earth sometime should be over, a decontamination due to an increased radioactive decay and various biological effects should be expected. Then, perhaps in 200 years, also many concepts concerning free energy, today still dismissed as hopeless, suddenly will function entirely by themselves.

The relatively free possibility of development of the human mind and the present sciences we possibly owe the special circumstance to be able to live in a time of minimized field strengths. Strong fields however can lead to psychotronic influencing of the consciousness and to an outside determining of mankind. This circumstance seems to have caused Tesla to compare man with a robot, and to call him an independent machine controlled from outside<ii>.

<i>: Freek Reijmerink: Sternenatlas Deutschland, Weltbild Verlag 1990, S.12 (ein sterbender Riese) und Illustrierte Wissenschaft, Nr. 9, 1999, S. 7, Brennen die grossen Sterne in den Sternbildern je aus? Die Entfernungsangaben schwanken zwischen 270 Lichtjahren (Meyers Lexikon), 310 (Sternenatlas), 500 (Ill.Wiss.) und 652 Lichtjahren (Cambridge Enzyklopadie d. Astronomie).

In the observable domain of the starry sky one statistically seen has the chance, to experience every second a supernova.

<ii>: Nikola Tesla: How cosmic forces shape our destinies, New York American, 7.2.1917, and Edition Tesla (1997), Bd. 6, ISBN 3-89539-245-6 der Mensch als machine, S. 65.


Projection of
Earth´s core
complete
shadow
1st point of
intersection
2nd point of
intersection

Fig. 20.10 A: Eclipse of the sun of 13.11.2012 (decl.: 18.1°)


comparison:
Projection of
Earth´s core
complete
shadow
1st point of
intersection
2nd point of
intersection

Fig. 20.10 B: Eclipse of the sun of 11.11.3799 (decl.: -17.3°).<i>

<i>: The eclipse of the sun of 7.7.3797 is harmless compared to that of 11.11.3799. Have they been mixed up or is a calculation error present?

20.10 Interaction of the neutrinos with earth's core

A strong neutrino field still doesn't make a catastrophe. Only in connection with one of the regularly happening eclipses of the sun should one be expected under certain circumstances. Only, which eclipses of the sun can get dangerous, we have to ask us, and why warns e.g. Nostradamus only for very particular dates?
The check of the respective eclipses of the sun results in a critical constellation every time for the cases, where the line of the complete shadow and the circle of the projection of earth's core intersect under a very flat angle and both points of intersection lie very close together. In the extreme case finally the lines only are touching and the points of intersection fuse to a line of intersection.
A corresponding constellation the next time is expected at 13.11.2012. For 7.7.3797, at similar conditions Nostradamus foretells the end of the world; but why?

From the interaction of the neutrinos arises as from every other interaction a force effect. If the points of intersection lie far apart, then earth's core is pulled once to the East and a short time later again to the West by the focussed neutrino radiation. On the average this will hardly influence earth's mantle and earth's crust because of the immense moment of interia. The possible earthquakes will remain regionally restricted to the area around the two points of intersection.
But if a line of intersection forms, then no compensation of the force effects takes place anymore, then during the whole time one-sided is pulled at earth's core and that can have fatal results. It is the same as for a spinning top, which is given a blow from the side: it staggers several times, until the gyroscopic forces have stabilized it again.

But if earth's axis staggers, then the sun describes strange orbits in the sky, it goes backwards again, for a longer time doesn't set or it doesn't show for the same period of time for the people living on the other side of the globe.
Such an event already is described in the Bible<i>. For the twenty hours, in which in Europe the sun didn't set for a day, again describe the chroniclers of the inhabitants in the South American Andes, how at their place the sun didn't show for twenty hours<ii>.

As a further example from the Greek mythology is mentioned the description of the poet Apollodoros. according to whom Hercules for the solution of his 10th task let the chariot of the sun bring to a standstill. "He turned his vehicle round and raced the way back, dragging along the Pleiaden and all stars, so that the sun set in the East"<iii>. But if all stars take part in the same backwards motion, then this example proves the assumption of the staggering earth's axis.

<i>: Josua 10.13-14 and the in chapter 11.8 cited passages.

<ii>: nach Montesinos, zitiert in Zecharia Sitchin: The Lost Realms (Versunkene Reiche), Knaur Verlag Miinchen 1992, ISBN 3-426-04827-2, S. 203

<iii>: Werner Raffetseder: Sonnenfinsternis, Hugendubel Verlag, Milnchen 1999, ISBN 3-89631-302-9, Seite 18.



A: Map of the world

B: Globus

60
-160 -140 -120 -100 -80 -60 -40 -20 0 20 40 60 80
-20
-40
-60
-80
Line of intersection !
complete shadow at the time of the biblical flood
Projection of the earth´s core
20

Fig. 20.11: Eclipse of the sun of 27.07.2281 B.C. (angle of the sun = declination: 19.3°) The trigger of the biblical Flood?

20.11 Changing of polarity and apocalypse

The pulling at earth's core, which shows as a wobbling of the magnetic axis and in damped form can lead to a tilting of the axis of rotation of the earth, still doesn't make an apocalypse, no end of the world. This only can be expected, if after a tilting of the axis of rotation of earth's core a change of polarity on the surface of the earth occurs. Doing so the new magnetic poles, like a compass needle in the field of the solar wind, again align in such a that the North Pole will be lying "up" in the ecliptic. Because earth's surface will keep it direction of rotation, the sun will, after the process having stabilized, as usual again rise in the East and set in the West. But the inhabitants of the earth, which before still were having midsummer, find themselves again in the midst of midwinter and vice versa.

Truly apocalyptic processes can be expected during the phase of a change of polarity of the earth. Thereby occur unusual relative accelerations and violent earthquakes. The largest destructive potential however is present in the waters of the oceans, which are set in motion.

As is well-known the earth at the equator is measuring a radius which is 21 kilometres larger than at its poles. If only a part of the waters temporarily flows in the direction of the poles of the earth, then the biggest part of the habitable land in Middle and North Europe sinks in the floods; then indeed also the statement of Noah makes sense, who as the first thing saw the mountain of Ararat rise from the floods, after the water again flowed back into its usual ocean basins. The mountain of Ararat after all measures a height of 5137 meters above sealevel!

At comparing historical events with details from the Bible the Flood should have taken place in the year 2245 B.C.<i>. According to the description of the position of the stars Dr. Wild calculates July 2281 B.C. as time for the Flood. The Arabic historical writer al-Makrizi again shifts the event into the year 3094 B.C.<i>. Who is right? We must verify the eclipses of the sun in this time and determine the position of the points of intersection, then we perhaps find the correct answer. Possibly earth's axis has wobbled more than once, have occurred several catastrophes in different regions. At 27.7.2281 B.C. in any case there actually has occurred an extremely critical constellation, whereas the other two years are ruled out. Here no total eclipse of the sun took place (fig. 20.11).

According to the calendar of the Ugha Mongulala 6110 years before this Flood a still much more devastating one should have occurred. That therefore would have been 8391 B.C., while Scott-Elliot dates the catastrophe in the year 9564 B.C.<ii>. According to Plato it would have been about 9500 B.C. For such long periods of time a check however isn't quite easy anymore, because the meantime changes of the earth sum up considerably.

<i>: Wild S. 231, 229 and 225.

<ii>: Wild S, 219, 218 and 210, among others cited from Scott-Elliot: Atlantis und das untergegangene Lemuria, Bauer Verlag Freiburg 1977.


1st point of intersection
2nd point of intersection (Crete)
complete shadow at 29.3.2003
Force effect on earth's core
Projection of earth's core

Fig. 20.12 A: Eclipse of the sun of 29.03.2006 (decl.: 3.2°)



Fig. 20.12 B: Cave painting from Minateda (Spain).<i>

<i>: Laviosa-Zambotti: Origini e Diffusione della Civilta, Marzorati, Milano 1950,

Besides the constellation of sun and moon is crucial the occurring of a relevant neutrino radiation and the question if both is sufficient to tilt the earth and change its polarity. Some experts expect a change of polarity for the time coming, since it takes place with a certain regularity and measured in earth historical periods of time in addition fairly often!
This circumstance the earth presumably owes the river valleys cut deep in the countryside and other topographic phenomena. One presumably can only survive such a catastrophe in an ark (Noah), in the air bubbles of large caves (the walls of which painted children and artists out of pure boredom, see fig. 20.12 B) or in the highland, preferably in the area of the equator (Central Africa, highland of Mexico, Andes, Himalaya).

20.12 Scalar wave gauges for the prediction of earthquakes

We urgently need gauges, to be able to judge the neutrino situation. At first we with that pursue the same goal, as with the building of a free energy converter, however with the difference that the converter should maximize the collected amount of energy, whereas the gauge should minimize the taken up energy, to not too much load the source and not to change the local radiation situation.
In addition the neutrino radiation should be registered distinguishable in its velocity of propagation, what means that the building of a gauge will be very much more costly than that of an energy collector. That's why it can be expected that an usable measurement instrument might be available only many years later and we that long only can base on our own power of observation.

We for instance can statistically analyse, how the earth after an eclipse of the sun reacts to the neutrino radiation focussed by the moon. At August 11 the second focal point was situated in the East, and from that an acceleration of the rotation of earth's core can be predicted. Corresponding observations actually have been made on the surface of the earth with the help of the Foucault pendulum.
The relation the next time can be checked at the eclipse of the sun at 29.3.2006. This time the inverse case is present. A first focussing takes place in the West, so that pendelum swings in the reversed direction would be expected, which indicate a slowing down of the rotation (fig. 20.12 A).

But if the rotation of the earth should change, then the balance sheet of angular momentum of moon, earth's mantle and earth's core isn't correct anymore. As a result a force of difference occurs, which lets the spinning top stagger. But if earth's core staggers inside of earth's mantle, then it powerfully stirs the liquid magma, and in this way releases its surplus energy again. As a result earth's mantle is heated up somewhat. We, on our wafer-thin earth's crust, then time delayed feel the effects of the staggering of the core as an earthquake. The period seems to lie at approximately 6.5 days, as far as this can be read from reactions to the last two eclipses of the sun.


11.8.1999
2.9.2035
21.8.2017
12.9.2053
13.11.2012
5.12.2048
25.11.2030
17.12.206

Tafel 20.13 A: Eclipses of the sun of 2 Saros cycles.



Fig. 20.13 B: The „Astronomicum Caesareum“ served around 1540 the determination of the positions of the moon nodes.<i>

<i>: Werner Raffetseder: Sonnenfinsternis, Hugendubel Verlag, Munchen 1999, ISBN 3-89631-302-9, Seite 134.

20.13 Calculation of future occurrences

From the analysis of past and present cosmic events with a strict scientific procedure can be predicted to a certain extent also future events. It thereby by no means concerns prediction, but exclusively the result of an analysis.

After the mentioned eclipse of the sun of 29.03.2006 there once more exists danger of earthquakes (approx. 4.4.2006) for the Island of Crete and Asia Minor. From the eclipse of the sun of 13.11.2012 as well no good can be expected, even if the points of intersection, situated close together, lie far away from populated land in the south-west Pacific basin. The Maya calendar by the way ends to this time. At 21.8.2017, 18 years or a Saros cycle after the eclipse of the sun at 11.8.1999 and correspondingly 120° further to the west, the corresponding complete shadow runs crossways through the USA. The thankless role of Turkey at the second point of intersection this time takes over South Carolina. One only can hope that the houses in Columbia are built more stable than in Izmit.
In fig. 2013 A the two eclipses of the sun of 11.8.1999 and of 13.11.2012 with their respective Saros cycles until 2066 are shown. The as critically to value tendency of the course of the complete shadow is visible, which wants to nestle against the circle of the projection of earth's core to form a line of intersection.

I here break off, since anyone with my indications and an eclipse of the sun-CD can analyse at home all further events personally. I value that if possible many analyses are made and controversially discussed, because possible cosmic catastrophes concern us all somewhat.

What good is the building of gigantic fusion ovens, if the runners by no means have understood the process of the fusion themselves? Why build ring accelerators for billions of dollars, if elementary particles can be calculated at the desk? How is the expenditure for gravitational wave detectors justified, if the actual music plays at entirely other velocities of propagation? Why is half the annual production of the world of Gallium used for an indirect proof of neutrinos, if every self-wound Tesla coil is able to collect more neutrinos?

Our scientists, for whom I as a colleague quite often must be ashamed, have the primary task to draw attention to cosmic and other risks and to calculate them in advance. In any case it is extremely unpardonable to leave this core duty up to some fortune-tellers and self-appointed prophets.
One should more often remind them that the Chinese Kaiser Tschung-Khang let sentence his court astronomers Hi and Ho to death, after the two not having predicted an eclipse of the sun. It thus certainly didn't concern a missed spectacle or a missed tourism business, but presumably the need for safety of the Kaiser and his subordinates, for which the two astrophysicists in ancient China had to take responsibility!



Fig. 20.14: The difference in going of two caesium atomic clocks positioned in different directions, but in the same laboratory in Harbin, China, during the partial eclipse of the sun of 24.12.1992.<i>

<i>: Shu-wen Zhou: Abnormal Physical Phenomena Observed When the Sun, Moon, and Earth are Aligned, 21st Century Science & Technology, Fall 1999, Vol. 12, No. 3, pp. 54-61. Comments concerning Figure 9: Straight lines AB and CD show that the rate of change of the time difference between the two clocks is constant in non-eclipse periods, but becomes irregular around the time of the eclipse.

20.14 Epilogue to the energy technical seminar

Very slowly the word goes round that the energy source of the future has got a name: "Neutrinopower". Unfortunately fundamental physics, which is financed with public money, still does know almost nothing about the nature of the neutrino radiation. In addition hinder useless model concepts any progress in this direction and so the responsible fundamental research steps on the spot.

Considerably more extensive were already 100 years ago the insights of the experimental physicist Nikola Tesla, the discoverer of the neutrino radiation and father of the free energy. The space energy however is showing most clearly in nature, which only uses this advantageous form of energy. In particular during eclipses of the sun and other cosmic experiments it openly comes to light and can be detected by us for a short time.

The physicist Prof. Shu-wen Zhou of the University of Huazhong in Wuhan, China, systematically has investigated the effects, if sun, moon and earth are aligned<i>. Doing so he has proven inexplicable physical anomalies in experiments. Stimulated by the discoveries of Maurice Allais with the Foucault pendulum he built an arrangement specially flor proving horizontal forces of acceleration, and actually he with that could measure face effects during the total eclipse of the sun of 24.10.1995. He even speaks of an oscillating force!

Further he could determine changes in the spectral wave length of various elements, which under normal conditions go as constant and even as characteristic for the respective element. The relative change of size of the wave length during the ring-like eclipse of the sun over China of 23.9.1987 resulted in the 100-fold value compared to the difference in the spectrum analysis between surface of the earth and surface of the sun! This comparison reveals an immense discrepancy between theory and practice and puts us for a solid problem.

For that six different models of spectrometers were installed in several laboratories of different polytechnics and a photograph was taken of the emission spectra of H, D, Ca, CN, Ni, Ti, etc. Also other reasons than that of an eclipse of the sun could be excluded unambiguosly. In the results of these, at artificial light carried out conventional measurements, in any case abysses yawn. The from spectrum analyses won "insights" about the composition of strange celestial bodies now for sure can be done away with without knowledge about the respective prevailing neutrino radiation.

Spectacular also is the proof of differences in going of atomic clocks of various constructions. During the partial eclipse of the sun of 24.12.1992 seven caesium clocks in four cities of China and in three planes were used. The analysis of the differences in going resulted in, as is shown exemplary in fig. 20.14, changes of the gradient during the eclipse. The results for the atomic clocks in the planes and for two further time measurements turned out with similar clarity<i>.

<i>: Shou-wen Zhou: Abnormal Physical Phenomena Observed When the Sun, Moon, and Earth are Aligned, 21st Century Science 6s Technology, Fall 1999, Vol. 12, No. 3, pp. 54 - 61.





Fig. 20.15: Long-term measurement between 1989 and 991 of the difference in going of two atomic clocks at the U.S. Naval Astronomical Observatory.[i]

The in the 1000 days occurred eclipses of the sun have been entered later. In addition is recorded, if the northern hemisphere (N-H) or the southern hemisphere (S-H) of the earth was involved.

<i>:Shu-wen Zhou: Abnormal Physical Phenomena Observed When the Sun, Moon, and Earth are Aligned, 21st Century Science & Technology, Fall 1999, Vol. 12, No. 3, pp. 54 - 61. Figure 8.

A connection to the neutrino radiation Prof. Zhon doesn't draw, but it almost is obvious.

From the U.S. Naval Astronomical Observatory (LC/7970) long-term measurements over 1000 days between 1989 and 1991 are present (fig. 20.15). The difference in going between the two atomic clocks positioned at different places shows a permanent up and down. The reason goes as completely unknown.
But if the eclipses, which took place in this time, are entered then one immediately sees the assignment to a maximum or a minimum value. If an eclipse of the sun namely concerned the southern hemisphere of the earth, then the difference in going each time reached a maximum, but if the shadow of the moon run over the northern hemisphere, then each time a minimum occurred. Chance here probably is out of the question!

Let us record: The effect of an eclipse of the sun, to which for instance a Foucault pendulum reacts, can equally be traced back to the interaction of the neutrinos as the free energy. That's why the here presented book carries the title "Free energy and the interaction of the neutrinos". It has appeared in the series concerning the "Electromagnetic environmental compatibility", and also for that there are good reasons. Our energy technology must become more ecologically compatible and we come the goal closer, if we emulate nature, understand and copy it.

That it further concerns electromagnetism, likewise is explained from the interaction of the neutrinos, which concerns the oscillating and resonant case of the electromagnetic interaction. In this respect the reference to the series of books therefore would be given.

It only indirectly has to do with "electrosmog", or what otherwise is understood under environmental compatibility in general. It however could be shown that also the earth radiation is a form of neutrino radiation, and that it poses a biological effectiveness, after it turned out that it serves nature as an energy source. With that the conflict with space energy devices already is predetermined if the same scalar wave radiation should be used. Then one system takes away the other system the energy basis and the existence basis.
This environmental compatibility problem can be solved, if care is taken that both don't get in each others way with regard to the frequency and the wave length. We for that need a deep understanding concerning the topic of the space quanta and the neutrinos, their physical properties and the corresponding device technology. The book should make a contribution to that.

The other side of the medal is the information technical aspect of the scalar wave radiation and the environmental compatibility problem connected with that. The third and last part of the series of books is dedicated to this theme.

Part 2: Edition belonging to the energy technical seminar: "Electromagnetic Environmental Compatibility"

Prof. Dr.-Ing. Konstantin Meyl

Scalar waves

Abstract:

1. Auflage 1998, 4. Auflage and 1st English Edition

With regard to the environmental compatibility a decentralized electrical energy technology should be required, which manages without overhead power lines, without combustion and without radioactive waste. The liberalization of the energy markets won't on any account solve our energy problem, but only accelerate the way into the dead end. New, ecologically compatible concepts are collected and discussed in the book.

A useful energy source could be represented by space quanta, which hit upon the Earth from the sun or from space. They however only are revealed to the measurement technician, if they interact. It will be shown that the particles oscillate and an interaction or collection with the goal of the energy technical use only is possible in the case of resonance.

Since these space quanta as oscillating particles have almost no charge and mass averaged over time, they have the ability of penetration proven for neutrinos.

In the case of the particle radiation discovered 100 years ago by Tesla, it obviously concerns neutrinos. We proceed from the assumption that in the future decentral neutrino converters will solve the current energy problem. Numerous concepts from nature and engineering, like on the one hand lightning or photosynthesis and on the other hand the railgun or the Tesla converter are instanced and discussed.

Free energy and the interaction of the neutrino radiation

INDEL GmbH, Verlagsabteilung, Fax: +49-7721-51870
Tel: +49-7724-1770
Postal and ordering address:
l.TZS, Prof. Dr. K. Meyl, Leopoldstr. 1, D-78112 St. Georgen
www.k-meyl.de meyl@k-meyl.de

Scalar Waves

From an extended vortex and field theory to a technical, biological
and historical use of longitudinal waves.

Part 3

by

Professor Dr.-Ing. Konstantin Meyl

Edition belonging to the lecture and seminar "Electromagnetic environmental compatibility"

(Original title: "Elektromagnetische Umweltvertraglichkeit")

Translated out of the German language
by Ben Jansen
(2003)

* * *

Part 3: Edition belonging to the information technical seminar

Scalar waves and the technical use of longitudinal waves and vortices

* * *

INDEL GmbH, Verlagsabteilung

Villingen-Schwenningen 2003

ISBN 3-9802 542-4-0

Preface to the seminar, part 3

With the appearing in print of the 3rd part of the series of lecture notes of the electromagnetic environmental compatibility, the collection of material can be considered to be completed for the time being. By now almost all aspects concerning the theme of the potential vortices of the electromagnetic field and their propagation as a scalar wave should have been addressed or at least indicated.

And that's what it is about in the case of the editions belonging to the seminars: In the seminars, taking place inside and outside the university, questions about the phenomena and the biological effectiveness of the fields, which surround us, are discussed. The scientifically correct procedure asks as a preparation for the seminar a voluminous collection of material and a compilation of theses with the pros and contras to them. The argumentation, which is denoted as „textbook physics" and is generally accepted, the participant of the seminar can work out himself by means of the available journals and books. The potential vortex, which completed the field equations, however makes possible a counterstatement, which for most participants at first will be unusual. The old dispute between quantum and field physics rekindles. What is missing is a voluminous collection of material concerning the refined field physics, and this gap the editions belonging to the seminars should close.

In the case of this book the primary concern is to make sure, that all facets, properties and physical consequences of the new and unified field physics are addressed. The question, if all points can bear a strict verification, remains reserved to the seminar and its participants, of whom each should form its own judgement. The series of books should be understood as a stimulation, to make own thoughts about the various points. Who has no opportunity to participate in a seminar, by means of the lecture at least gets an idea of what is discussed here and how is struggled for scientific insights.

The herewith completed collection of material by no means may be compared or confused with a basic work about the theory of objectivity. That the editions cannot and want not afford at all. They together with the discussions at best form the basis for a scientifically basic work, at which I am working.

In the case of the collection of material concerning the electromagnetic environmental compatibility consisting of three parts, again and again new aspects have emerged, which found entrance into the book, at which I was working at that particular time, whereas the rough structure has been controlled precisely: part 1 with the chapters 1 to 9 treats the basics, part 2 with chapters 10 to 20 the energy technical aspect and part 3 with the chapters 21 to 30 the information technical aspect of scalar waves.

The here presented 3rd part starts with the wave equation and the two comprised parts of a transverse and a longitudinal wave. The historic dispute between Heinrich Hertz and Nikola Tesla with the experimental evidence of the each time used wave part is continued over the wave-particle uncertainty compromise up to the dispute about the right field description: that of Maxwell or the new dual and at the same time unified description, which builds upon Boscovich and Faraday. The aspects, which seem so irreconcilably thereby only are two parts of a single equation, which is much older and can be traced back to Laplace: the wave equation.

Until now no derivations of this equation, which contains both wave parts, are known This for the first time succeeds from the new and extended field approach in the summary from chapter 26. At first however is attempted to make the world of the scalar waves plausible with models, calculations and observations. For that are used examples from high-frequency engineering, like the ground wave or the near-field area of an antenna, and from nature and medicine, which are granted two chapters. The comparison of the nerve conduction with Tesla's one wire technology is bringing it to light that scalar waves equally are used in both cases. In a frequency diagram the insights are entered concisely and is shown that considerably more unexplored domains occur than already is known, that in most cases not even gauges are available. With the design for building a scalar wave gauge the scientific verification of until now only empirically won results is stimulated, like for instance the results the radiesthesia wants to have determined with the help of the sensitivity of man as a biosensor.

Many relations will be revealed to the reader only, if he has worked through the summary, which follows. From Maxwell's field equations only the well-known (transverse) Hertzian waves can be derived. (Longitudinal) scalar waves however in the result are zero. This is a flaw of normally used field theory, since scalar waves exist for all particle waves, like e.g. as plasma wave, as photon- or neutrino radiation. Because the field pointer, in the direction of which longitudinal waves are propagating, is oscillating, the frequency will oscillate like the velocity of propagation, which again is measured as a noise signal. Any antenna noise proves the emission of scalar waves in space. But scalar waves, or whatever should be subsumed under the by mathematics minted generic term free of any value judgement, surely are more than only noise.

Starting from Faraday's discovery - instead of the formulation of the law of induction according to Maxwell - an extended field theory is derived, which goes beyond the Maxwell theory with the description of potential vortices (noise vortices) and their propagation as a scalar wave, but contains the Maxwell theory as a special case. The new field theory with that doesn't collide with the textbook opinion, but extends it in an essential point with the discovery and addition of the potential vortices.
Also the theory of objectivity, which follows from the discovery, is compared in the form of a summary with the subjective and the relativistic point of view and the consequences for variable velocity of propagation of the scalar waves, formed from potential vortices, are discussed. Like already in part 1 the unification of the electromagnetic interaction with the gravitation succeeds impressively.

Besides the mathematical calculations this book contains a voluminous material collection concerning the information technical use of scalar waves, if e.g. the useful signal and the usually interfering noise signal change their places, if a separate modulation of frequency and wavelength makes a parallel image transmission possible, if it concerns questions of the environmental compatibility for the sake of humanity (bioresonance, among others) or to harm humanity (electrosmog). With that the book again finds back to the starting point, to the open task, which made necessary an excursion through all domains of physics to answer it. I hope, the long march was worthwhile.

Villingen-Schwenningen december 2002

Preface to the 2nd edition of part 3

In favour of chapter 30 as a complement, an introduction into the ancient broadcasting technology of the gods, the 1st edition wasn't printed anymore in the year 2002 as originally planned. Instead the individual chapters have been prepublished in different places. The chapters 21 to 25 are found among others in the book "scalar wave technology", which has been published as an instruction for an experiment to demonstrate scalar waves in 2001. Excerpts from it, as also from the chapters 26 to 28 have appeared in form of individual essays in different journals.

Again experimental successes had been intervening, which caused a renewed deferring of the date of appearance of the 3rd part of the series of books. In my laboratory the bi-directional transmission of music and of data by scalar wave was successful. We thus also can transmit information backwards from a receiver to the transmitter or to a second receiver, whereby the receivers work purely passive, thus without own power supply. The operating energy is as well supplied to them by the transmitter by scalar wave. The demonstrated technology opens completely new possibilities of a technical application. Conceivable are telemetry installations where measurement signals have to be transmitted from rotating or otherwise inaccessible places of a machine. The energy for the measurement electronics can be transmitted wirelessly by scalar waves and the signal can be sent back along at the same time, by modulating it onto the energy carrier. In this way dozens of measurement stations can be connected wireless with a single central transmitter, which supplies them all with energy.

The question was asked: Is the technology really entirely new? The answer is amazing: No, it here concerns the oldest technology of humanity, which had developed to a peak in antiquity, to send receive engineering of the gods. For this claim even a mathematical proof is available. For that the authoritative transition, the unrolling of a vortex to a wave (the transition from the near-field to the far-field) or in the reversed case the rolling up at a receiver antenna (usually denoted as standing wave) is calculated with help of the extended field theory. The result is, that at this transition the velocities of propagation resp. the wavelengths of the transverse and the longitudinal wave stand to each other in the ratio of the Golden Proportion.
With regard to the optimization of a transmitter or receiver antenna the Golden Proportion has an effect on the construction resp. the architecture of corresponding buildings . Which ones, with that deals the complementing chapter 30. But it mustn't be missing either, since after all it concerns a grandiose practical information technical use of scalar waves, from which we technologically can learn a lot<i,ii>.

Villingen-Schwenningen march 2003

<i>: Note: chapter 30 provides an introduction into ancient broadcasting technology of the gods. The working off of history with respect to the use of scalar waves is so voluminous, that for that a book of its own is published with the title:

<ii>: K. Meyl: Sendetechnik der Gotter, historischer Sciencefictionroman (2003), Villingen-Schwenningen, INDEL Verlagsabteilung, ISBN 3-98O2 542-5 9

21. Derivation of the scalar wave

WilliamThomson, who called himself Lord Kelvin, after he had been knighted, already in his lifetime was a recognized and famous theoretical physicist. The airship seemed him too unsafe and so he went aboard a steam liner for a journey from England to America in the summer of 1897. He was on the way in a delicate mission.

Eight years before his German colleague Heinrich Hertz had detected the electromagnetic wave in experiments in Karlsruhe and scientists all over the world had rebuilt his antenna arrangements. They all not only found confirmed the wave as such, they even could show the characteristic properties.
It was a transverse wave, for which the electric and the magnetic field pointers oscillate perpendicular to the direction of propagation. This can be seen as the reason, that the velocity of propagation is showing itself field independent and constant. It is the speed of light c.

With that Hertz had experimentally proven the properties of this wave, previously calculated in a theoretical way by Maxwell, and at the same time proven the correctness of the Maxwellian field theory. The scientists in Europe were just saying to each other: "well done!" as completely other words came across from a private research laboratory in New York: "Heinrich Hertz is mistaken, it by no means is a transverse wave but a longitudinal wave!"

Such a screwball most said and did as if they hadn't heard the criticism at all. But then one couldn't ignore it completely, because on the one hand claimed the private research scientist to have experimental proof and on the other hand it wasn't just anybody, who here reported. It was nobody but Nikola Tesla, the Croat experimental physicist who emigrated to America
Him we owe the modern alternating current technology from the high-tension network for energy transmission over the alternating current transformer to the asynchronous machine.
With his magnificent inventions he had earned enough money, to be able to afford a private laboratory, in which he could research and invent uncensored and free. The key to his success was lying in his purposeful, concentrated and efficient working method.
He was fast! Whereas in Europe still was being discussed about properties and theoretical possibilities of application of the wave, Tesla already presented the armed forces a remote controlled scaled-down submarine in Madison Square Garden (fig. 21.1 A). To convince such a man, who only holds valid what his experiments reveal, from the opposite, should be a hopeless enterprise.
Lord Kelvin was aware of that, as he made the decision to go on the journey. He could not and did not want to put his head into the ground, as many of his colleagues, because on the one hand scientists are curious by principle and on the other hand he travelled as an official representative of science. He had been instructed to free, as Mr. Clean, the undamaged world of sciences from erroneous teachings. But it came completely different.



Fig. 21.1 A: The first radio remote control of the world.<i>



Fig. 21.1 B: Patent specification concerning the remote controlled submarine.<i>

<i>: Nikola Tesla: Method of and Apparatus for Controlling Mechanism of Moving Vessels or Vehicles, US-Pat. 1898, Nr. 613,809. Complete Patents: P. 351

21.1 Lord Kelvin in a delicate mission

The first day of his visit at Tesla Kelvin spoke the admonishing words he had been instructed to speak. He recommended Tesla warmly to publicly retract the remarks concerning the Hertzian mistake and to contribute himself to the settlement of the dispute. Seen from a specialist viewpoint they talked at cross-purposes.

But at night in his hotel room the Lord again thought about the experiments, which had been shown to him. The standing wave nature had been visible unambiguously: the oscillation nodes, the effect back on the transmitter, the high degree of effectiveness and many other things more. Such properties the Hertzian wave indeed doesn't know. Also Tesla didn't work with dipole antennas, but with flat coils, with spark gap oscillators and with a very unconventional switching technique, set up different in principle.

The next morning Lord Kelvin appeared in the laboratory again and greeted Tesla with the words: "Then you don't use Hertzian waves?" "Certainly not", Tesla answered," it are radiations. By waves no energy could be economically transmitted over a larger distance. My system works with true conduction, which theoretically seen can take place over a larger distance, without bigger losses occurring."
In the article of the "Electrical Experimenter" is noted further, that the doubting critic Kelvin suddenly turned into one of the biggest followers<i>.

Kelvin deduced very fast: according to that there exist two different sorts of wave propagation. So Hertz with his transverse wave is just as right, as Tesla with the longitudinal wave.
As a represantative of theoretical physics he however could pull out Tesla a decayed tooth. Maxwell had based his field description on an aether concept, which at that time in the world of sciences triggered violent discussions. Since Tesla saw such an aether as a prerequisite for longitudinal waves, he thought he and not Hertz had proven the Maxwell wave in experiment for the first time. By stating this the magnificent experimental physicist however revealed weaknesses in the area of theory. Maybe he had not read exact enough or understood the books of Maxwell, which without doubt were formulated mathematically only arduously comprehensible in the original version.
In this point Tesla had to learn otherwise by Kelvin. Maxwell's field theory provides without exception a mathematical description for the Hertzian wave. For the Tesla radiation however no field description exists! This by the way is the circumstance, why this wave could disappear from the textbooks and again fall into oblivion. Tesla himself had problems to theoretically imagine, what happens at his wave. His models in some points perhaps were even better than the official textbook opinion, but not without contradiction to accepted regularities. That's why Tesla did without a publication of his ideas, although he in his lifetime had filed away at an own theory.

<i>: Nikola Tesla: Famous Scientific Illusions, III. The Singular Misconception of the Wireless, Electrical Experimenter, Feb. 1919, printed in Tesla Said, p. 197

Figure 21.2 A:

William Thomson, 1846 becoming Professor at Glasgow University with the age of 22 years. From 1892. on he was called Lord Kelvin.<i>



Fig. 21.2 B: Vortex rings from a smoke vortex gun.<i>

<i>: David Ash, Peter Hewitt: Science of the gods, Gateway Books, Bath, 1990

21.2 Helmholtzian ring-like vortices in the aether

Tesla told Kelvin at his visit from the meeting with the German Professor Hermann von Helmholtz on the occasion of the World's Fair in Chicago 1893. Kelvin knew him very well and had cooperated with him in the past. Now the vortex concept of his colleague and his model of stable vortex rings were very obliging.
In the case of a standing wave the impulse is passed on from one particle to the next. In the case of acoustics for instance we are dealing with a shock wave, where one air molecule knocks the next. In this way sound propagates as a longitudinal wave. Correspondingly the question is raised: What sort of quanta are the ones, which in the case of the Tesla radiation carry the impulse?

Lord Kelvin was already on the way back to Europe on the steamship and he deduced:
The Tesla experiments prove the existence of longitudinal standing waves in space. In the question, what passes on the impulse, Kelvin comes to the conclusion: it are vortices in the aether! With that he had found an answer in experience. With his students he built boxes, with which he could produce smoke rings, to be able to study and demonstrate in experiments the special properties of ring-like vortices in their flow technical analogy (fig. 21.2<i>). But he didn't have ready a suitable field theory.

The from Germany to the Isles exported vortex physics for a short time could establish in England, before it was slaughtered and buried by the German quantum physicists. A main advocate has been James Clerk Maxwell, who held the vortex theory for the best and most convincing description of matter<ii>. As his successor at the Cavendish laboratory in Cambridge J. J. Thomson was appointed, who already as a young man had got a price for a mathematical treatise about vortices<iii>. He discovered the electron and imagined it, how could it be otherwise, as a field vortex.

The crucial weakness of vortex physics, the lacking of an usable field theory, was of benefit to the emerging quantum physics. This could change fundamentally with the discovery of the potential vortex, the vortex of the electric field<i4>!
In addition is the experimental proof of a vortex transmission as a longitudinal wave in air or in a vacuum, as it has been furnished by Tesla already 100 years ago, neither with Maxwell's theory nor with the today normally used quantum theory explicable or compatible. An urgent need is present for a new field theory!

<i>: David Ash, Peter Hewitt: Science of the gods, Gateway Books, Bath, England 1990.

<ii>: James Clerk Maxwell: "...the vortex rings of Helmholtz, which Thomson imagines as the true form of the atom, fulfil more conditions than any other previous concept of the atom."

<iii>: J.J. Thomson: "the vortex theory is of much more fundamental nature than the usual theory of solid particles."

<i4>: Konstantin Meyl: Potentialwirbel Band 1 (1990) and Band 2 (1992), INDEL-Verlag, Villingen-Schwenningen.

Scalar waves, a mathematical reasoning (I)

1. prerequisite: wave equation (textbook-formulation)

$$\boxed{\Delta \mathbf{E} = \frac{1}{c^2}\cdot\frac{\delta^2 \mathbf{E}}{\delta t^2}}$$

taking apart of the delta operator mathematically (Laplace operator) according to the rules of vector analysis (fig. 5.0):

$$\boxed{\begin{array}{lcccc} \Delta \mathbf{E} & = & \text{grad div } \mathbf{E} & - & \text{rot rot } \mathbf{E} \\ \text{wave} & = & \text{longitudinal} & + & \text{transverse} \end{array}} \qquad (21.1)$$

---

2. State of the art of technology: Hertzian wave = transverse wave
special case: = solution of Maxwell's field equations
no sources:

$$\boxed{\text{div } \mathbf{E} = 0} \quad \text{and} \quad \boxed{-\text{rot rot } \mathbf{E} = \frac{1}{c^2}\cdot\frac{\delta^2 \mathbf{E}}{\delta t^2}} \qquad (21.3)$$

transverse wave:
field pointers oscillate crosswise to the direction of propagation
The propagation occurs with the speed of light c.

---

3. claim: Tesla radiation = longitudinal wave
special case:
irrotationality:

$$\boxed{\text{rot } \mathbf{E} = 0} \quad \text{and} \quad \boxed{\text{grad div } \mathbf{E} = \frac{1}{c^2}\cdot\frac{\delta^2 \mathbf{E}}{\delta t^2}} \qquad (21.4)$$

longitudinal wave, shock wave, standing wave:
field pointer oscillates in the direction of propagation.
Velocity of propagation is variable!

Fig. 21.3: The special cases of the wave equation

21.3 Taking apart of the wave equation

Before one plunges into the adventure of an entirely new field theory, it first of all should be traced and analysed, what the latest textbooks say about scalar waves.

There some scalar or vector potentials are introduced; there the constant of dielectricity e is written down as a complex variable, although it physically seen concerns a material constant, only to be able to calculate with this trick artificially a loss angle, which should indicate the losses occurring in a dielectric, where in reality it concerns vortex losses. Of course one can explain the dielectric losses of a capacitor or the heating in a microwave oven entirely without vortex physics with such a label fraud, but it should be clear to anyone, that in a complex constant lies buried an inner contradiction, which is incompatible with physical concepts.
We are used to such auxiliary descriptions so much, that the majority of today's physicists tend to attribute physical reality to this mathematical nonsense. As pragmatists they put themselves on the standpoint if with that experimental results can be described, then such an auxiliary description can't be so wrong after all. Doing so the circumstance is forgotten that here the ground of pure science is abandoned and is replaced by creeds.

We find everything already in the wave equation, as it can be found in all textbooks.

$$\boxed{\Delta \mathbf{E} = \frac{1}{c^2}\cdot\frac{\delta^2\mathbf{E}}{\delta t^2}} \quad (21.1)$$

Behind this formulation two completely different kinds of waves are hiding, because the used delta operator consists of two parts according to the rules of vector analysis:

$$\boxed{\begin{array}{lll} \text{grad div } \mathbf{E} & - \text{ rot rot } \mathbf{E} & = \Delta \mathbf{E} \\ \text{longitudinal} & / \text{ transverse} & \text{wave} \end{array}} \quad (21.2)$$

We want to discuss two special cases.
If we put the left part (in eq. 21.2) to zero (div E = 0) which is tantamount to no sources of the field then the well-known radio wave remains, which also is called Hertzian wave, after Heinrich Hertz, as said, had experimentally detected it in Karlsruhe 1888:

$$\text{div } E = 0 \qquad \text{and} \qquad \boxed{- \text{rot rot } \mathbf{E} = \frac{1}{c^2}\cdot\frac{\delta^2\mathbf{E}}{\delta t^2}} \quad \text{(special case)} \qquad (21.3)$$

It concerns the transverse wave, described by Maxwell, for which the field pointers oscillate crosswise to the direction of propagation. The propagation again occurs with the speed of light c. So much concerning the state of the art of technology.
But as we see, in the mathematical formulation of the wave equation is hiding, yes, even more than only the generally known electromagnetic wave. The no sources approach is a neglect, which only is valid under certain prerequisites!

Scalar waves, a mathematical reasoning (II)

3. claim: Tesla radiation = longitudinal wave

$$\boxed{\mathrm{rot}\,\mathbf{E} = 0} \quad \text{and} \quad \boxed{\mathrm{grad}\,\mathrm{div}\,\mathbf{E} = \frac{1}{c^2}\cdot\frac{\delta^2\mathbf{E}}{\delta t^2}} \tag{21.4}$$

special case:
source field, because div E ≠ 0

=> sources = charge carriers (plasma waves)
=> sources = vortex structures

---

4. approach: (div E ≠ 0) is a scalar! => scalar wave
=> E-field vector can be derived from a scalar potential φ:

$$\boxed{\mathbf{E} = -\,\mathrm{grad}\,\varphi} \tag{21.5}$$

and $$\mathrm{div}\,\mathbf{E} = -\,\mathrm{div}\,\mathrm{grad}\,\varphi \equiv -\,\Delta\varphi \tag{21.6}$$

inserted in eq. 21.4: homogeneous scalar wave equation

$$\boxed{\Delta\varphi = \frac{1}{c^2}\cdot\frac{\delta^2\varphi}{\delta t^2}} \tag{21.7}$$

---

5. proof: For the case of an additional space charge density ρ_{el} should be considered: div D $= \rho_{el}$
and div E $= \rho_{el}/\varepsilon$ (21.8)

inhomogeneous scalar wave equation = plasma wave!

$$\boxed{\Delta\varphi = \frac{1}{c^2}\cdot\frac{\delta^2\varphi}{\delta t^2} - \frac{\rho_{el}}{\varepsilon}} \tag{21.9}$$

Fig. 21.4: Derivation of the plasma wave as an example of a scalar wave

21.4 Derivation of the scalar wave equation

Making neglects by all means is normal and legal in science. But it may not be carried out at will and untested. In any case an error consideration is necessary, the result of which should be, that the neglect indeed is sufficiently small.
In the here presented case of the wave equation I haven't found one single textbook, in which this error consideration has been carried out. As a result of this inexcusable negligence there is the danger that exactly the aspect is neglected, which it actually concerns. This could lead to catastrophical results, e.g. that the causes for electrosmog, for numerous EMC-problems, for biological and technical effects aren't seen and understood anymore, that pure science once more dilapidates to a creed!

In the case of the wave equation the assumption of no sources describes only one side of the medal. The other side, which for the electromagnetic wave occurs as an error term, we get if we this time put the right part in equation 21.2 to zero (rot E = 0).
In this case a divergence of the field is present, which requires a source field. As sources some charge carriers, quanta or at least particle structures, e.g. vortex structures have to exist. Their propagation occurs, as we know it from the sound propagation, as shock wave in longitudinal manner. The air molecules, the quanta or particle structures thereby oscillate in the direction of propagation. Also the field pointer has a component in this direction

$$\text{rot}\,\mathbf{E} = 0 \quad \text{and} \quad \boxed{\text{grad div}\,\mathbf{E} = \frac{1}{c^2}\cdot\frac{\delta^2\mathbf{E}}{\delta t^2}} \quad \text{(special case)} \qquad (21.4)$$

The occurring divergence of the field pointer (div E) is a scalar, for which reason this wave preferably is called scalar wave.

In the special case of a scalar wave (rot E = 0) the E-field vector can be derived from a scalar potential φ:

$$\boxed{\mathbf{E} = -\,\text{grad}\,\varphi} \qquad (21.5)$$

On the one hand this term is used in the wave equation 21.4 on the right-hand side without forming the gradient on both sides of the equation. On the other hand the divergence of the approach 21.5:

$$\text{div}\,\mathbf{E} = -\,\text{div grad}\,\varphi \equiv -\,\Delta\varphi \qquad (21.6)$$

is applied in equation 21.4. The result is the homogeneous scalar wave equation:

$$\boxed{\Delta\varphi = \frac{1}{c^2}\cdot\frac{\delta^2\varphi}{\delta t^2}} \qquad (21.7)$$

Scalar waves, a mathematical reasoning (III)

Proof: plasma wave =
inhomogeneous scalar wave equation

$$\boxed{\Delta \varphi = \frac{1}{c^2} \cdot \frac{\delta^2 \varphi}{\delta t^2} - \frac{\rho_{el}}{\varepsilon}} \quad (21.9)$$

one solution<i>: $\omega^2 = c^2 \cdot k^2 + \omega_p^2$ (= Langmuir waves).

Fig. 21.5 A: Derivation of the plasma wave as an example of the existence of scalar waves in the wave equation


Hertzian
oscillator with
much energy at
low degree of
effectiveness
Grounded oscillator
(according to Tesla)
with little energy at
high degree of
effectiveness

Fig. 21.5 B: Nikola Tesla explains the difference between his radiation and the Hertzian wave.<ii>

<i>: The solution describes dispersion relations of plasma waves; longitudinal wave movements + Langmuir oscillations of the electron density.

<ii>: Nikola Tesla: The Problem of Increasing Human Energy, The Century Monthly Magazine, June 1900, ISBN 1-882137-00-0, Page i-15

21.5 Derivation of a plasma wave

Doing without formation of the gradient for the derivation of the homogeneous wave equation is tantamount to an integration of the equation. We hence under certain conditions must expect the occurring of an integration constant.
This is the case, if in addition a space charge density ρ_{el} occurs as source of the field, which according to Maxwell equation 4 can be considered as the divergence of a dielectric displacement D (fig. 21.4): $\operatorname{div} \mathbf{D} = \rho_{el}$,

resp. with the relation of material $\mathbf{D} = \varepsilon \cdot \mathbf{E}$: $\operatorname{div} \mathbf{E} = \rho_{el}/\varepsilon \equiv -\Delta \varphi$. (21.8)

If we complete this contribution with possible present field sources, then the inhomogeneous scalar wave equation results:

$$\boxed{\Delta \varphi = \frac{1}{c^2} \cdot \frac{\delta^2 \varphi}{\delta t^2} - \frac{\rho_{el}}{\varepsilon}} \quad (21.9)$$

For these equations solutions have been published<i>. They have the same form, as the well-known dispersion relations of Langmuir waves. That is electron plasma waves, thus longitudinal wave movements associated with Langmuir oscillations of the electron density.

With that it has been proven that scalar waves and longitudinally propagating standing waves are described by the wave equation and are contained in it. This in any case is valid in general just as in the special case of a plasma wave, as mathematically could be derived here.

From the example of the derivation of plasma waves from the wave equation 21.1, we see that scalar waves by all means are known and their existence isn't casted doubt on at all. After all the mathematically won solution is secured by numerous experiments. Why do textbooks concerning high-frequency engineering then ignore the scalar wave parts in the wave equation?
Our specialists seem to concentrate so much on their branch, that they are losing the view on the Big Whole. They practice one-eyed physics, where the plasma physicist keeps one eye shut and the radio technician the other eye. What the other one does and researches, they don't understand anymore for ages. It is necessary to point them to their common root.

The perhaps most important statement of the wave equation is that every emitted wave contains both longitudinal and transverse parts! Both parts in addition occur jointly, so that for corresponding boundary conditions it can be expected that one part is transforming into the other part. The HF technician then suddenly measures less field strength and comes to the conclusion that his radio wave has been damped or partly absorbed. Doing so heat is created, he says, although the wave equation by no means contains a corresponding term for the necessary thermodynamic description. He simply hasn't understood the wave equation!
Absorption means nothing but transverse waves in the case of a disturbance rolling up to vortices, to become a scalar wave in this way (fig. 1.4 and 5.3). With that they are evading every field strength measurement and what can't be measured doesn't exist in one-eyed physics! Therefore can't exist, what shouldn't exist.


spatial wave
= Hertzian wave
?
ground wave = scalar wave
transmitter
receiver
earth

Fig. 21.6: Ground waves, which follow the curvature of the earth and radio waves reflected at the ionosphere.<i>

<i>: Meinke, Gundlach: Hochfrequenztechnik, 4.Aufl. Springer-Verlag Berlin 1986, Seite R 18: „Lang-, Mittel- and Kurzwelle breiten sich einerseits entlang der Erdoberflache als Bodenwellen, andererseits unter Mitwirkung der Ionosphare als Raumwellen aus."

21.6 Mistakes of the HF technology

The devastating judgement of Tesla, Hertz was mistaken, was rash. His claim of having detected the Maxwell wave himself, proved to be untenable. With this claim in particular Tesla hud the scientific world against him. If one opens encyclopedias or textbooks then one gets the impression, until the day of today science still hasn't forgiven Tesla, what once more shows how persistent prejudices are kept.

Just as little does a verdict of the American Supreme Court justice to the true circumstances, with the decision of the highest judges that Tesla and not Marconi is entitled the right to be the inventor of the radio. As we see, have both inventors in reality used completely other kinds of waves. The available transmitters of 100 years ago we would from today's viewpoint call ,,broadband dirt slingers". These spark flying monster have blown both parts of the wave equation, the transverse as well as the longitudinal part, into the air to ample extent. What distinguished the wave pioneers was their receiver technique, was eventually the question, which wave part they have filtered and utilized.

Marconi worked with dipole antennas, as already Heinrich Hertz. With that both could preferably track down and detect the radio wave. So they also should be entitled the right to be pioneers of radio technology. The verdict of the highest judges doesn't justice to this circumstance and should rather be judged as a nationalistically coloured political issue. Tesla however worked with two spherical electrodes, in which he preferably replaced one electrode by the globe, by grounding his devices. In this way he could receive the scalar wave parts. But that are not radio waves! Scalar waves have completely other properties, one even could be inclined to call them opposite properties.

To improve the degree of effectiveness of the transmission stretch one naturally was trying to also optimise the transmitting installation with regard to the respectively used wave part. Tesla optimised the scalar wave part and could record reactions of biological beings. His part represents a set of difficulties of the environmental compatibility, which should be taken serious. In the beginning the Marconists on the ships, as the radio operators were called, suffered from the so-called radio operator disease, which is unsolved until today. This phenomenon only disappeared after the radio devices on board had been optimised in favour of the used radio wave. The reached and measuring technically verifiable increase of the degree of effectiveness, primarily obtained by an improved antenna adjustment, simultaneously means a reduction of the scalar wave part, which endangers health.

But a received signal hides the receiver technician, if it has been on the way as a transverse or as a longitudinal wave. The coupling in one and the same equation leaves open both possibilities. Every radio amateur knows the so-called ground waves, which arrive faster at the receiver, than the Hertzian waves mirrored at the ionosphere, which propagate in a straight line. Allegedly the ground waves follow the curvature of the earth[1], so it is written in expert books. This explanation hurts, since who can see along the curvature of the earth with a pair of field glasses. He would see the back of his head! No, the explanation the ground waves would run along the earth's surface is pure nonsense. The interference and the fading with which the radio amateur is fighting, are a result of the differently fast arriving wave parts, and doing so the scalar wave part tunnels as a straight line right through the earth (fig. 21.6)!



Fig. 21.7 A: Longitudinal and transverse earth quake waves.



Fig. 21.7 B: Analysis according to the Richter scale.
(e.g.: 40 s duration between S- and P-waves for 5 mm amplitude means an earthquake of strength 5 in a distance of 220 miles.)

21.7 Coupling of the wave parts

The set of difficulties of ground waves makes clear the coupling of longitudinal and transverse waves as two aspects or parts of a wave. As the corresponding equation 21,1 mathematically taken apart into 21.2 dictates, does every transmitter emit both parts.

Exactly this circumstance the owners of allotments have used, which directly near a transmitter had illuminated their estate with freely hung up fluorescent lamps. The transmitter runners after that wanted to present them the power bill.and they could obtain, that this kind of illumination technique was prohibited.
Nowadays anyone may operate a high-frequency technical installation, even if he hasn't understood at all the wave equation used by that. Actually one should have been grateful to the allotment owners, if they withdraw the scalar wave radiation, which is incompatible with the environment and biologically harmful, with their fluorescent lamps. Taken exact it even is the task of the transmitting technician to pay attention to it. that only radio waves are sent into the air, since only those should be used. The time has come to reverse the burden of proof to protect the environment, nature, the consumer and the unasked and not involved persons, which are irradiated.

From other areas, for instance from flow dynamics or for body sound is generally known that both wave parts exist and in addition occur jointly. In the case of a propagation through the earth, like for an earthquake, both parts are received and utilized. Because their propagation is differently fast, the faster oscillations arrive first and that are the longitudinal ones. From the time delay with which the transverse waves arrive at the measurement station, the distance to the epicentre of the quake is determined by means of the different velocity of propagation. For geophysicists this tool is part of everyday knowledge (fig. 21.7).

Only who keeps one eye shut, could mean that the electromagnetic wave is purely transverse and sound purely longitudinal. It is true that a transverse sound wave doesn't get too far in air, for which reason sound as a rule is considered as a purely longitudinal wave by neglecting this part, but such a neglect may not be carried out in general, it must be checked if it is legitimate from case to case and an error consideration should be carried out.

Further examples for the coupling of the wave parts are furnished by the latest tunnel experiments. Here so-called pure transverse waves are sent into a tunnel, through which they don't fit through at all. The Maxwell-theory then dictates that behind the tunnel no signal should be measurable.
But a signal is being measured, which in the tunnel in addition was faster than allowed.

In conferences again is being discussed about the wave equation. The imagination of the specialists reaches from phase velocities of an electromagnetic wave, which isn't present at all up to instantaneous tunnelling, during which the clocks should stop<i>.
The wave equation however supplies the only possible answer: The tunnel filters out the scalar wave parts and lets pass from them only those, which are sufficiently small and correspondingly fast!

<i>: see Part 1, Chapter 6.14



Fig. 21.8 A: The fields of the oscillating dipole antenna



Fig. 21.8 B: The planar electromagnetic wave in the proximity

<i>: Zinke, Brunswig: Lehrbuch der Hochfrequenztechnik, 1. Bd., 3. Aufl. Springer-Verlag Berlin 1986, Seite 335

<ii>: dpa-message in the Sudkurier of 25.11.2000: „Gefahr furs Herz" (Translated:) Patients with a cardiac pacemaker produced in the Netherlands have been warned by the producer of the device (Vitatron) to be careful when passing anti-theft installations in stores. For devices, which were implanted between 1992 and 1998, there is the danger of the implant failing.

21.8 Set of difficulties of the near-field

In high-frequency technology is distinguished between the near-field and the far-field. Both have fundamentally other properties.

Heinrich Hertz did experiment in the short wave range at wavelengths of some meters. From today's viewpoint his work would rather be assigned the far-field. As a professor in Karlsruhe he had shown that his, the electromagnetic, wave propagates like a light wave and can be refracted and reflected in the same way. It is a transverse wave for which the field pointers of the electric and the magnetic field oscillate perpendicular to each other and both again perpendicular to the direction of propagation. It hence would be obvious, if in the case of the Hertzian wave it would concern the far-field. Besides the propagation with the speed of light also is characteristic that there occurs no phase shift between E-field and H-field.

In the proximity it looks completely different. The proximity concerns distances to the transmitter of less than the wavelength divided by 2*pi. Nikola Tesla has broadcasted in the range of long waves, around 100 Kilohertz, in which case the wavelength already is several metres. For the experiments concerning the resonance of the earth he has operated his transmitter in Colorado Springs at frequencies down to 6 Hertz. Doing so the whole earth moves into the proximity of his transmitter. We probably have to proceed from assumption that the Tesla radiation primarily concerns the proximity, which also is called the radiant range of the transmitting antenna.
For the approach of vortical and closed-loop field structures derivations for the near-field are known<i>. Doing so it must be emphasized that the structures don't follow from the field equations according to Maxwell, but the calculations are based on assumed rotation symmetrical structures. The Maxwell theory by no means is capable of such a structure shaping by principle. The calculation provides as an important result<i> that in the proximity of the emitting antenna a phase shift exists between the pointers of the E- and the H-field. The antenna current and the H-field coupled with it lag the E-field of the oscillating dipole charges for 90° (fig. 21.8). These charges form a longitudinal standing wave the antenna rod or antenna dipole. For this reason also the fields produced by high-frequency currents at first have the properties of a longitudinal wave in the proximity of the antenna.

The near-field already is used in practice in anti-theft devices, as they are installed in the entrance area of stores. The customer walks through the scalar wave transmitters. If the coupling coil has not been removed at the cash point, then a signal from the alarm system sounds. The coils work purely passive, i.e. they are supplied with electric energy per scalar wave and stimulated 'to oscillate for their part. Then the effect back on the transmitter is being utilized. Even if the principle is functioning, people still should be warned not to use a technology, which has not been understood completely. Then not explained catastrophes are inevitable <ii>.

<i>: Zinke, Brunswig: Lehrbuch der Hochfrequenztechnik, 1. Bd., 3.Aufl. Springer-Verlag Berlin 1986, Seite 335

<ii>: dpa-message in the Sudkurier of 25.11.2000: ,,Gefahr furs Herz". (quoted at the left, fig. 21.8)



Fig. 21.9 A: The coming off of the electric field lines from a dipole
The forming vortex structures found a longitudinal electric wave carrying impulse!

electromagnetic wave (transverse)



Fig. 21.9 B: The planar electromagnetic wave in the far zone

21.9 Transition to the far-field

In sufficient distance to the transmitting antenna as far-field the transverse electromagnetic wave results (fig. 21.9 B). It is distinguished by not occurring a phase shift between E- and H-field anymore. Every change of the electric alternating field is followed immediately and at the same time by a change of the magnetic alternating field and vice versa.
In the proximity however the phase shift amounts to 90°. Somewhere and somehow between the causing antenna current and the far-field a conversion from a longitudinal into a transverse wave occurs. How should one imagine the transition?

In the books the coming off of a wave from a dipole is represented according to fig. 21.9 A. The fields come off the antenna, the explanation reads. If we consider the structure of the fields coming off then we see field vortices, which run around a point, which we can call the vortex centre. Such field structures naturally are capable of forming standing waves and to carry an impulse. The scalar wave field in general and the near-field in special we only will understand with suitable vortex physics and with a field theory extended for corresponding vortices we also will be able to calculate it. Postulates cannot replace field physics!

Be that as it may, the vortex, after having left the antenna, for bigger getting distance at some time seems to unroll to propagate further as an electromagnetic wave. There takes place a transition from longitudinal to transverse, or spoken figuratively, from vortex to wave. How complete this conversion takes place, how big the respective wave parts are afterwards, on the one hand depends on the structure and the dimensions of the antenna. Information is given by the measurable degree of effectiveness of the antenna.
The vortex structures on the other hand are the stabler, the smaller and faster they are. If they are as fast as the light or even faster, then they become stable elementary particles, for instance neutrinos. Slower vortex structures however are predominantly instable. They preferably unwind to waves. Vortex and wave prove to be two possible and under certain conditions even stable field configurations.

Let's emphasize: A Hertzian dipole doesn't emit Hertzian waves! An antenna as near-field without exception emits vortices, which only at the transition to the far-field unwind to electromagnetic waves. A Hertzian wave just as little can be received with a dipole antenna! At the receiver the conditions are reversed. Here the wave is rolling up to a vortex, which usually is called and conceived as a „standing wave". Only this field vortex causes an antenna current in the rod, which the receiver afterwards amplifies and utilizes.
The mostly unknown or not understood near-field properties prove to be the key to the understanding of the wave equation and of the method of functioning of transmitting and receiving antenna. The question is asked, how one should imagine the rolling up of waves to vortices and vice versa the unrolling? How could an useful vortex mode) look like?

Circularly polarized wave (transverse)



Fig. 21.10 A: Left-circular polarized wave (as explanation for the transition to a vortex and to a scalar wave)

electric wave (longitudinal)



Fig. 21.10 B: Magnetic ring-vortices form an electric scalar wave.

vortex and wave = two stable field configurations
electromagnetic wave = transverse wave propagating in a straight line
ring-like vortex = transverse wave running in circles
vortex velocity = speed of light c
change of structure = if the field is disturbed without expense of energy

22.10 Scalar wave model

The light, as electromagnetic wave, in the presence of a heavy mass or of strong fields is bent towards the field source (fig. 6.10). The wave normally propagating in a straight line thus can be diverted. The square of the speed of light further is inversely proportional to the permeability and dielectricity, short, in presence of matter it is more or less strongly slowed down. If this slowing down of the wave occurs one-sidedly, then a bending of the path can be expected as well. At the end of the antenna a reflection and a going back of the wave can occur, which at the other end again hits itself. Now the wave has found a closed-loop structure, which can be called vortex. The figures 21.10 B and 21.11 A show the two possible structures.

In technical books this vortex with the properties of a „standing wave" is explained gistly. Near-field and standing wave are two examples, how the textbooks succeed in describing mathematically right a small part of the scalar wave properties, without having to have a good look at vortex physics. With such auxiliary descriptions however the end is reached fast, if for instance it concerns understanding a pure scalar wave transmission according to Nikola Tesla (fig. 19.11) and the special properties of this wave type. With the vortex concept of an extended field physics new horizons are opening.

If we direct our look again to the sketches (fig. 21.10 B and 21.11 A). In both cases electromagnetic waves are represented which propagate with the speed of light, only that the wave doesn't go forward in a straight line but instead runs around in circles. It also furthermore is transverse, because the field pointers of the E-field and the H-field oscillate perpendicular to c. By means of the orbit the speed of light c now has become the vortex velocity. Wave and vortex turn out to be two possible and stable field configurations. For the transition from one into the other no energy is used; it only is a question of structure. The vortex structure thus stabilizes itself by means of the field dependency of the speed of light.

By the circumstance that the vortex direction of the ring-like vortex is determined and the field pointers further are standing perpendicular to it, as well as perpendicular to each other, there result two theoretical formation forms for the scalar wave. In the first case (fig 21.10 B) the vector of the H-field points into the direction of the vortex centre and that of the E-field axially to the outside. The vortex however will propagate in this direction in space and appear as a scalar wave, so that the propagation of the wave takes place in the direction of the electric field. I call this an electric wave.

In the second case the field vectors exchange their place. The direction of propagation this time coincides with the oscillating magnetic field pointer (fig. 21.11 A), for which reason I speak of a magnetic wave.

The vortex picture of the rolled up wave already fits very well, because the propagation of a wave direction of its field pointer characterizes a longitudinal wave, because all measurement results are perfectly covered by the vortex model. It even is clear that no energy has to be spended for the conversion, since merely the structure has changed. If it becomes a vortex the wave just doesn't run in a straight line anymore but in circles, to either wrap around the magnetic field vector (fig. 21.10 B). or the electric field vector (fig. 21.11 A).

magnetic wave (longitudinal)



Fig. 21.11 A: The magnetic scalar wave



Figure 21.11 B: Wave propagation in a coaxial cable, (Example for waveguide, horn radiator, etc.)<i> Cross-section of coaxial conductor and field distribution in the direction of propagation.

<i>: H. Armbruster, G. Grunberger: Elektromagnetische Wellen im Hochfrequenz-

21.11 Double-frequent oscillation of size

Because a longitudinal wave propagates in the direction of the field, the field pointer also will oscillate with the velocity of propagation v. This hence isn't constant at all, it can significantly differ from that of the light and can take arbitrary values. According to the theory of objectivity the field oscillating with it determines its momentary size:

$$E, H \sim 1/v^2 \qquad (21.10).$$

The velocity of propagation v of the scalar wave thus oscillates double-frequently and with opposite phase to the corresponding field. A detailed description would mean, if the field strives for its maximum value, the velocity v of the wave reaches its smallest value. In the field minimum the scalar wave vice versa accelerates to its maximum value. For longitudinal waves therefore only an averaged velocity of propagation is given and measured, as this for instance is usual for the sound wave, and this can vary very strong as is well-known (body sound compared to air sound, etc.).
The two dual field vectors of E and H, the one in the direction of propagation and the one standing perpendicular to it, occur jointly. Both oscillate with the same frequency and both form the ring-like vortex in the respective direction. As a result the ring-like vortex also oscillates in its diameter double-frequently and with opposite phase to the corresponding field (fig. 21.10 Band 21.11 A).
This circumstance owes the ring-like vortex its property, to tunnel. No Faraday cage is able to stop it, as could be demonstrated in experiments<i>. Only therefore the ground wave runs through the earth and not along the curvature of the earth. A further example is the coaxial cable (fig. 21.11 B). Also this acts as a long tunnel and so it isn't further astonishing, that the electric field lines have the same orientation, as for a magnetic scalar wave. As a practical consequence in this place there should be warned of open cable ends, wave guides or horn radiators with regard to uncontrolled emitted scalar waves!

At present in the press is being discussed, if the cable network runners for some channels the mission to operate again should be withdrawn, because the airline radio traffic is being disturbed. The original opening for cable frequencies, which actually are reserved for the airline radio traffic, based on the erroneous assumption, that conflicts are unthinkable. But then the planes were disturbed in their communication. As the cause TV-cables made out, which hadn't been closed according to the rules with a resistor, as it by all means can occur on building sites and during renovation works.
On the other hand is being argued with the small current, which flows through the coaxial cable, and the large distance to the planes also is cited. According to that it actually can't concern Hertzian waves. It presumably are scalar waves, which escape from the open cable ends and which are collected by a receiver in the plane. It indeed is very little field energy, but because it again is being collected and bundled, the scalar wave is able to exceed the part of the radio wave by far just at large distances and to cause problems.
For such examples from practice the scalar wave theory is fully taking effect.

<i>: Adolf und Inge Schneider im Interview mit Prof. Dr.-Ing. Konstantin Meyl: Durchbruch in der Freien-Energie-Forschung, NET-Journal 12/1999, S. 7-9.

1. H. Hertz: electromagnetic wave (transverse)


y
H_y
H-field
c
x
z
E_z
E-field

2. Nikola Tesla: electric wave (longitudinal)



3. magnetic wave (longitudinal)



Fig. 21.12: The three basic types according to the wave equation
(21.1), (electric, magnetic and electromagnetic wave).

21.12 Electric and magnetic scalar wave

Let us record: For the wave propagation there thus are three possible and stable states (fig. 21.12): the transverse electromagnetic wave according to Heinrich Hertz (fig. 1), the longitudinal electric wave according to Nikola Tesla (fig. 2), and a longitudinal magnetic wave (fig. 3), which isn't connected yet with a name of a discoverer. The last one is a pure product of my theoretical derivation. The question is asked, which practical meaning the magnetic wave could have.

It is formed by individual electric field vortices, which I have discovered and called potential vortices 1990. I proceed from the assumption that the youngest of the three waves will play the by far biggest role in the future, because its properties are unattainable, both with regard to the energy technical and to the information technical use. One example for each should support this thesis.

The experiments concerning the electric wave according to Nikola Tesla, where is being worked with electrically charged spheres, don't show a particularly high power. Magnetic converters, so the experiences of my laboratory activities, are superior to an electrostatic converter as a collector for free energy by far. That even can be expected, because a magnetic engine is much smaller than an electrostatic engine of the same power as is well-known.

At a congress of medicines was given a talk on the basic regulation of the cells, on the communication of the cells with each other. Professor Heine in his decades of research work has found out that the cells for the purpose of communication build up channels for instance in the connective tissue, which after having conducted the information again collapse. Interestingly the channels have a hyperboloid structure, for which no conclusive explanation exists.

The structure of the data channels however is identical with the one of a magnetic scalar wave, as shown in fig. 3. Through a channel formed such, which functions like a tunnel or a dissimilarly formed waveguide, only one very particular scalar wave can run through. Waves with different frequencies or wavelengths don't fit through the hyperboloid formed tunnel at all in the first place. Through that the information transmission obtains an extremely high degree of safety for interference.

To the biologist here a completely new view at the function of a cell and the basic regulation of the whole organism is opening. The information tunnel temporarily forms more or less a vacuum, through which only potential vortices can be conducted, and that without any losses - simply perfect! From this example is becoming clear that nature is working with scalar waves namely with magnetic waves.

One other point should be recorded: The mentioned tunnel experiments, in which speed faster than light is being measured with most different devices, impressively confirm the presence of scalar waves. But if scalar waves exist which are faster than light and other ones, which are slower, then it almost is obvious that also such ones will exist, which propagate exactly with the speed of light. These then will have all the properties of the light and won't differ from the corresponding electromagnetic wave in the observable result. As scalar wave it however is formed by vortex configurations, which unambiguously have particle nature. Nothing would be more obvious than to equate these quantum structures with the photons.

Question: Is the light wave or particle?


Seen strictly causal, i.e. physically in the period between 1600 and 1900:
Descartes (1596-1650)
Huygens (1629-1695)
Newton (1643-1726)
Young (1773-1829)
Frauenhofer (1787-1826)
Fresnel (1788-1827)
Maxwell (1831-1879)
Planck (1858-1947)
Hertz (1857-1894)
Einstein (1879-1955)
dual nature of the light
Turning away from classical physics: (removing of the principle of cause and effect)
Heisenberg (1899-1975)
de Broglie (1891-1981)
Dirac (QED) (1902-1984)

Fig. 22.1: The view of some physicists concerning the nature of the light as wave or as particle.

According to the wave equation the light is a mixture of wave and photon radiation!

22 Properties of scalar waves

For the light quanta hypothesis the Nobel Prize for physics was awarded 1921. But it only was a hypothesis, an idee fixe, which was honoured here. It is quite odd, if such an important prize is awarded to a research scientist, who hasn't got the slightest idea what light quanta are anyway, of what they consist and how they are built up. Albert Einstein cleverly used the embarrassing situation, by in his celebration speech on the occasion of the awarding of the Nobel Prize giving a talk on the theory of relativity. After the speech a member of the committee found it necessary, to point to it, that this wasn't object of the awarding of the prize and that the theory of relativity concerns a pure theory, which can't be proven by principle. A theory hence neither could be awarded the Nobel Prize.

Such words on the occasion of awarding a prize for a daredevil hypothesis give the whole event really grotesque characteristics. But it came still worse.

22.1 Wave-particle compromise

Physicists of name and rank had come together. It concerned the question if the light is wave, or particle or even both at the same time? For both variants experimental proof was present, the discussion became inflamed and the things boiled over. Finally they were as smart as before, as Werner Heisenberg presented his ideas concerning the uncertainty principle. This compromise, on which one eventually came to an agreement, with good cause may be called the worst in the history of physics. It dictates me, what I shell see and how exact I may look. With it the contradiction should be overcome that the light contrary to every causality should be wave and particle at the same time.

Such fixings not only have a funny, but also a tragic side. Since it were authorities, which have approved the compromise and the whole community of science has confidence in the statements of its authorities, which immediately and unfiltered is entered in all textbooks. At the meeting it simply and solely concerned the wave equation and only that could have supplied the correct and only possible answer: It falls apart into two parts and this explains, why the light one time appears as an electromagnetic wave and the next time as a vortex particle, which is called photon. The conversion can take place at any time spontaneously and without putting on energy, so that depending on the used measuring technique the particle appears as wave or as particle, but of course never as both at the same time!

Looking back one can say that the funny thing about the situation was that all discussed about the wave and its properties known at that time, that all should know the wave equation. An equation as is well-known says more than a thousand words and one look would have sufficed entirely, to answer the controversial question once and for all. It would have saved us a lot.


light
source
first slit
refractive slit
detector
sample picture

Fig. 22.2 A: Light forms interference patterns at the slit (light stripes are formed, where the waves oscillate in phase, dark stripes, where they oscillate out of phase).


electrons
electroscope
+
+
monochromatic light

Fig. 22.2 B: The photo-electric effect

<i>: Atome als Energiewellen. Physiker wandelten einen Strom von Natriumatomen in Wellen um. III. Wissenschaft 7/1996, Seite 56 + 57

22.2 Concerning the measurement of light

The uncertainty principle with the interpretation of Heisenberg, the light is wave and particle at the same time, is incompatible with the wave equation. Heisenberg puts an equal sign, where in the wave equation in reality is present an addition of both wave parts. Fortunately in mathematics there is no need of speculating, there a derivation is right or wrong. Nothing is changed to that even if all physicists of the world should go in the wrong direction following the prevailing opinion. The wave equation exert an influence on the interpretation of the light experiments, on the one hand the ones concerning the interference and refraction of the light, where electromagnetic waves are becoming visible (fig. 22.2 A) and on the other hand the photo-electric effect, as proof of light quanta (fig. 22.2 B).

Already the wave theory of Huygens requires interference patterns of light rays, as they for instance are observed behind a slit, and demonstrates with that the wave nature. If on that occasion the particle nature is lost, if thus the photons present before the slit can't be detected behind the slit anymore, then plain and simple the measuring method, thus the slit is to blame for that. The vortices have unrolled themselves at the slit to waves. Corresponding experiments also have been carried out with matter. At the Massachusetts Institute of Technology whole sodium atoms were converted into waves. At the detector pure interference patterns were observed, which go as evidence for the successful dematerialization[i]. But the vortex physicist they show still more: they reveal, that atoms merely are waves rolled up to spherical vortices, which at any time and spontaneously can again unroll to waves at a lattice (chapter 5 and 7).
The common interpretation, the wave nature detectable behind a slit must have been present in the same form already before the slit, is untenable and in the end wrong, as makes clear the experiment with the sodium atoms.

The photo-electric effect, which on the other hand shows the quantum nature of the light, has been discovered by Heinrich Hertz, further investigated by Lenard and finally rendered more precisely by Millikan 1916 (fig. 22.2 B). It bases on the circumstance that light of higher frequency, thus blue light, has more energy than red light of lower frequency. But if electrons are knocked out a metal plate by light, then that occurs, by the waves rolling up to vortices. Now indeed photons are at work, which are detected with an electroscope indirectly.
In the same way a photon ray in a bubble chamber can be photographed. But also here the measuring method is responsible for what is being observed.

A good example is the human eye, the rods and cones of which merely can pick up potential vortices and pass them on to the nerves as so-called reaction potentials. Incident waves can only be detected, if they first have rolled up to vortices in the corpus vitreum of the eye. For us seeing, it doesn't play a role of how many percent vortices and waves the light is consisting.
Behind a sheet of glass for instance a larger vortex part can be expected and still the light has the same brightness as without sheet; the sheet of glass is perceived as transparent. We nevertheless must assume that light with a large wave part has another quality, than such light behind glass or artificial light with a large part of photons.



wave equation:

$$\Delta \mathbf{E} = \operatorname{grad}\operatorname{div}\mathbf{E} - \operatorname{rot}\operatorname{rot}\mathbf{E} = \frac{1}{c^2}\cdot\frac{\delta^2\mathbf{E}}{\delta t^2}$$

Nikola Tesla:	*Heinrich Hertz:*
• **scalar wave** (electric or magnetic) =	**electromagnetic wave** =
• **longitudinal wave**	**transverse wave**
form (each time for velocity of propagation v):	form (each time for frequency):
• ($v > c$): neutrino radiation, morphogenetic fields,...	• cosmic radiation • X-rays, • UV radiation,
• ($v = c$): photons,	• light,
• ($v < c$): plasma wave, thermal vortices, biophotons, earth radiation,...	• infra-red radiation, • microwaves, • radio waves,
• ($v = 0$): noise,...	• VLF, ULF,...

Fig. 22.3:____ The two parts of the wave equation

22.3 Comparison of the parts of Tesla and Hertz

Light as a rule always is formed as photon radiation, even on the sun. If in the end only waves arrive on earth, then the vortices sometime on the way to us must have unrolled to waves. Photon radiation after all is a scalar wave radiation, which generally is predominant in the near-field of the source of radiation. There is no reason, why the light should act in another way than the wave radiated by a radio transmitter, which as well forms vortices in the near-field area, as we already have discussed. For different interpretations of wave properties of one and the same physical phenomenon there is no place in a unified theory.

If we stay at the comparison then it is not an individual case that an experimental setup is responsible for what is being measured and observed. A parallel case to the experiments concerning the nature of the light is the one concerning the wave propagation. Hertz has received and utilized the transverse part and Tesla the longitudinal part and either one claimed, only he is right. There doesn' t exist an other equation, which has been and is being ignored and misunderstood so thoroughly, as the wave equation.

Fig. 22.3 shows in a survey the two parts of the wave equation in the assignment to the terms and forms: Right hand side the electromagnetic wave according to Heinrich Hertz and left hand side the scalar wave according to Nikola Tesla. The terms, like on the one hand transverse wave and on the other hand longitudinal wave relate to the kind of wave propagation.

If the field pointers oscillate crossways to the direction of propagation, then as a consequence the velocity of propagation is decoupled from the oscillating fields. The result in all cases is the speed of light, and that in our observation is constant.
It is usual to make a list for increasing frequency, starting at the longest waves (ELF and VLF) over the radio waves (LW, MW, SW, UHF), the TV channels (VHF, UHF), the microwaves, the infra-red radiation, the light, the X-rays up to the cosmic radiation.
It really is interesting that it concerns one and the same phenomenon despite the different forms! As long as Maxwell only had published a theory for the light, in the world of science 24 years long at first nothing at all happened. Only Heinrich Hertz with his short wave experiments opened the eyes. Now all suddenly started at the same time to research into various phenomena on the frequency scale, from Madame Curie over Konrad Rontgen up to Nikola Tesla, who primarily researched the area of long waves.

With regard to the scalar waves until now a corresponding booster detonation has failed to appear. The immense area is new ground scientifically, which is awaiting to be explored systematically. I try to make a contribution with my historic rebuild of a scalar wave transmission line according to the plans of Tesla<i>.

<i>: Im Gesprach mit dem Fernsehmoderator und Buchautor Johannes von Buttlar weise ich auf die Chancen und technischen Moglichkeiten hin: Johannes von Buttlar im Gesprach mit Prof. Dr. Konstantin Meyl: Neutrinopower, Argo-Verlag Marktoberdorf, 1. Aufl. (2000).


electromagnetic wave
rolling up vortex
λ_1
λ_2
λ_3
λ_4
λ_5

Fig. 22.4: The wave rolling up to a vortex.
wavelength of the wave: $\lambda_1 = c/f_1$
wavelength of the vortex: λ_n (n = 1,2,3,4,5) $\leq \lambda_1$
$f_5 > f_4 > f_3 > f_2 > f_1$ $\lambda_5 < \lambda_4 < \lambda_3 < \lambda_2 < \lambda_1$

22.4 Noise, a scalar wave phenomenon

Longitudinal waves can take arbitrary velocities between zero and infinity, because they propagate in the direction of an oscillating field pointer and as a consequence of that their velocity of propagation oscillates as well and by no means is constant. It does make sense to llist the forms of scalar waves according to their respective velocity of propagation (fig. 22.3, left column).

If we start with a localized vortex, a wave rolling up, which further is contracting. Doing so the wavelength gets smaller and smaller, whereas the frequency increases. An evenly frequency mixture distributed over a broad frequency band is observed. This phenomenon is called noise (fig. 1.4). But besides the localized noise, noise vortices can also be on the way with a certain velocity as a scalar wave, e.g. for the radio noise. In this case they show the typical properties of a standing wave with nodes and antinodes.

Also the earth radiation is said to have standing wave nature, which can be interpreted as slowed down neutrino radiation. If it is slowed down on the way through the earth, then the neutrino properties are changing, as this was measured in the Kamiokande detector in Japan recently. Unfortunately the proof occurs only indirect, because there still don't exist measuring devices for scalar waves. We'll talk about this problem area later and are content with the clue that already within living memory the standing wave property has been used to find water and deposits of ores and still is used today (fig. 22.4).

If we continue our considerations concerning the forms of scalar waves, as they are listed in fig. 22.3. The scalar waves, which are slower on the way than the light, are joined by the plasma waves. This is confirmed by measurements and calculations.

For thermal vortices, as they have been investigated by Max Planck and for biophotons, as they can be detected in living cells by colleague Popp, the velocity of propagation however is unknown. It was not and still is not measured at all, now more than ever. The research scientists have confidence in the assumption that all waves go with the speed of light, but that is a big mistake.

For all wave kinds there at least exists also one vortex variant, for radio waves for instance it is the radio noise, which propagates with a velocity different from c. The velocity is the product of frequency and wavelength:

$$\boxed{v = f \cdot \lambda} \quad (22.1)$$

From the three variables v, f and λ at least two must be measured, if one has a suspicion that it could concern scalar waves. At this place most errors are made in the laboratories. Countless experiments concerning the biological compatibility, concerning medical therapy methods and similar experiments must be repeated, because as a rule only the frequency is being measured and it has been omitted to at least check the wavelength or the velocity of the wave. Countless research scientists must put up with this accusation. Much too blind the scientists, who now again may start from the very beginning with their work, have had confidence in the predominance of the speed of light.


v » c
hard neutrino radiation
(small ring-like vortex)
v > c
weak neutrino radiation
(large ring-like vortex)
c
c
photon radiation (light =
individual ring-like vortex or
as an oscillating pair).
v < c
c
c
c
plasma waves,
noise,
earth radiation
(vortex balls,
consisting of
a multitude of
ring-like vortices).

Fig. 22.5: ____The ring-like vortex model of scalar waves.

22.5 Neutrino radiation

The neutrino physicists make the same error. They proceed from the assumption that their particles are on the way with a speed somewhat less than the speed of light c. This contradicts the observation according to which black holes should represent strong sources of neutrinos, which are black only for the reason that no particle radiation is able to escape them, which is on the way with c or even slower. If a black hole does hurl neutrino radiation into space, than that must be considerably faster than c, as normal neutrino physicists still by no means can imagine it today.

But the neutrino radiation only can be detected after it has been slowed down to a value, which is smaller than c. If the slowing down occurs slightly assymmetrical, then as a consequence a mean of the mass different from zero appears. The „measurement" of such a rest mass, as it at present is propagated and celebrated, is a classical measurement error! As long as a neutrino on the way to us still is faster than the light, the mean of its mass is generally zero. The effective value of the mass of a neutrino is however considerable. Only it is able to give account for the sought-for dark matter, as far as it must exist in the today supposed form anyway.

The Tesla radiation, that the discoverer Nikola Tesla already in own experiments had found out, is faster than light (chapter 9.7 and 17.2). Since this Tesla radiation according to the description is identical with the neutrino radiation, since it so to say forms a subset, I will call neutrino radiation all the scalar waves, which are faster than the light. This stretches from the weak radiation at low frequencies up to the hard neutrino radiation of cosmic origin. But the hardness of the radiation does not only increase with the frequency, it in particular increases with the velocity.

The neutrino radiation first of all is carrying energy. On top of this basic wave radiation in addition information can be modulated. Doing so extremely complex modulation variants are offering. Of this kind we must imagine thoughts, as being complex modulated vortices, which can propagate as scalar wave in space. Rupert Sheldrake calls this vortex field a morphogenetic field. At this place merely is pointed at his very interesting research results<i>.

Thoughts can be standing in space, in the form of localized noise, but they also can move with speeds faster than light. According to that a communication with intelligent beings from other star systems by all means wouldn't be an Utopia anymore.

Every fast neutrino forms an individual ring-like vortex (fig. 7.12). The slower the scalar wave is, the more dependent the vortices become. The photon already can consist of two ring-like vortices (fig. 4.6), whereas plasma waves and other slow scalar waves can form from a multitude of individual vortices, which are rotating around each other, to form vortex balls and vortex streets (chapter 4.9 - 4.11). From this circumstance already results very different scalar wave behaviour in the different areas of the velocity of propagation. This trend for small velocities can as well be observed towards lower frequencies. For a certain wavelength the frequency after all (according to eq. 22.1) is proportional to the velocity of propagation.

<i>: R. Sheldrake: Seven experiments that could change the world. New York: Riverhead 1995



scalar wave = energy wave: = *Tesla radiation*	• **electromagnetic wave** = *Hertzian wave*
• can be modulated in a complex way	• can only be modulated linearly
• fast, parallel image transmission	• slow, serial image transmission
• focussing, transmission without losses	• scattering, transmission losses
• positive use: mobile, directional radio, energy converter	• positive use: radio, TV, information distributor
• negative use electro smog, radiation weapons	• negative use: mobile, directional radio

Fig. 22.6: Scalar waves and radio waves, comparison of the properties.

22.6 Parallel instead of serial image transmission

We continue with our considerations concerning the special properties of scalar waves, represented in the left column, and compare these with the well-known behaviour of electromagnetic waves in the right column (fig. 22.3 is now followed by fig. 22.6). If we again take up the possibilities for modulation and the transmission of information, then it becomes very clear from the comparison that we today work with a technology, which we it is true master more or less, but which is everything else but optimum. For the Hertzian wave the velocity of propagation is constant. With the frequency therefore at the same time also the wavelength is being modulated. But that strongly limits the information transmission. An image for instance must be transmitted serially point after point and line after line. The serial image transmission takes place very slowly, for which reason the velocity of the PCs permanently must be increased, so that the amount of data can be managed.

With the clock frequency on the other hand also the losses increase, so that in the end the CPU-cooler limits the efficiency of modern PCs. Something our engineers obviously do wrong, as a comparison with the human brain clarifies. Our brain works without a fan. For it a clock frequency of 10 Hertz is sufficient. It needs neither Megahertz nor Gigahertz frequencies and despite that is considerably more efficient.

Nature only works with the best technology. The second best technology, as it is put to use in our machines, in the evolution wouldn't have had the slightest chance of surviving. The strategies to optimize of nature are merciless. In a free economy that goes completely different. There the „bunglers" are joining together to companies dominating the market, buying up the innovative ideas without further ado, to let them disappear in the drawer, so that they can bungle further in the way they did until now. It after all have been the lousy products, which have made them to the companies they are today. The ego of power is incompatible with the interests of nature.

Nature works with scalar waves and their velocity of propagation is arbitrary. Wavelength and frequency now can be modulated and information can be recorded separately. In this manner a whole dimension is gained to modulate, the image transmission can take place in parallel, which means considerably faster, safer and more reliable. As anyone of us knows by own experience, assembling the image takes place all at once, the memory of past images takes place ad hoc. Nature is indescribable more efficient than technology with the scalar wave technique.

If we again take the right-hand side of fig. 22.6 with the properties of the Hertzian wave. In the opinion of Nikola Tesla it is a gigantic waste of energy. The broadcasting power is scattered in all directions and the transmission losses are enormous. At the receiver virtually no power arrives anymore. To receive a radio signal the antenna power has to be amplified immensely. It is a wave, which actually only can be used as radio wave, thus as a wave with which arbitrary many participants should be reached.

This wave however is completely useless, if it concerns a point-to-point connection. If I want to call someone, to talk only with him, a radio wave is the entirely wrong method, because I with that bother hunderds and thousands of people that I don't want to call at all!


Hertzian wave propagation (transverse waves):
E
c
transmitter
receiver

Tesla radiation (radiations) = scalar wave, longitudinal wave propagation:


(+/−)
v, E
(−/+)
transmitter
receiver
with grounding:

Fig. 22.7: Comparison of radio waves according to H. Hertz and electric scalar waves according to Nikola Tesla.

22.7 Comparison of the properties

The course of the field lines clarifies the difference. For the scalar wave all field lines going away from the transmitter run together again. As long as no scattering field occurs, there also won't be any transmission losses. It is an energy wave, for which the full broadcasting power is transmitted wirelessly and which arrives at the receiver, by that focussing the field lines again.

Here one at once numerous technical applications come to mind, if energy should be transmitted wirelessly. A TV, which supplies its remote control with energy itself, lelemetric installations, which are fixed at difficult accessible or rotating machine parts and which can't work without energy supply.

For a mobile with 3 Watts of broadcasting power only a few microwatt arrive at the ground station. If I would have a scalar wave mobile, which functions with resonance, then a broadcasting power of some microwatt will be completely sufficient, to carry out a telephone call right through the earth. This minimum broadcasting power suffices, because everything, what is being transmitted, arrives at the receiver - crucial is that the conditions of resonance are fulfilled. That means, both must have the same frequency and the opposite phase. In addition the modulation has to fit, so that on the one hand not several participants in the conversation are getting in each other's way. For a purely carrier wave transmission on the other hand there would be the risk of natural fields being collected also and the power at the receiver taking inadmissibly high values. This is prevented effectively by a correspondingly complex modulation. Nature solves the problem in exactly this manner.

Mobile phone technology with scalar waves of course still is a pie in the sky. A big challenge for the engineers poses the adjustment condition of opposite phase and the fitting modulation, which Tesla called .,individualisation"<i>. Entirely by the way the network runners and the telephone companies are getting quite superfluous.

Telephone charges, so one perhaps can read in the history books in a hunderd years, were the indication of a century of rigorous exploitation of man and nature. With scalar waves a direct, more dimensionally modulated information transmission directly with the partner of conversation is possible and sufficient energy is available to humanity any time and any place, without being dependent on any companies! This notion is not new, but it is inconvenient for the rules; already Nikola Tesla has written about it, but obviously no-one wanted to listen to him<ii>.

Scalar waves are able, that is made clear by the properties, to revolutionize both the energy technology and the information technology fundamentally. It is more than only a technology for the new century. Scalar waves are a chance for the whole millennium!

<i>: N. Tesla: Transmission of electrical energy without wires, Electrical World and Engineer 7.1.1905; Edition Tesla Vol. 4, P. 131.

<ii>: N. Tesla, New York Times of 15.9.1908; Edition Tesla Vol. 6, P. 241.


f [Hz]
frequency
speed of light c
wave length λ
[m]
cosmic radiation
10^{24} Hz
10^{23} Hz
10^{22} Hz
10^{21} Hz
10^{20} Hz
10^{19} Hz
10^{18}Hz
10^{17}Hz
10^{16}Hz
10^{15}Hz
10^{14}Hz
10^{13}Hz
10^{12}Hz
10^{11}Hz
10 GHz
1 GHz
10^{8} Hz
10 MHz
1 MHz
100kHz
10 kHz
1 kHz
100 Hz
10 Hz
hard neu- trino radi- ation
γ- radia- tion
X-rays
UV
light
IR
μW
UHF
VHF
SW
MW
LW
VLF
ELF
photons
weak neu- trino radia- tion
stan- ding waves and loca- lized vorti- ces/ noise
noise
ultra- sound
air- sound
body sound
10 pm
0,1nm
1 nm
10 nm
0,1μm
1 μm
10 μm
0,1mm
1 mm
1 cm
10 cm
1 m
10 m
100 m
1 km
10 km
10^{5} m
10^{6} m
0 [m/s] 1 10 10^{2} 10^{3} 10^{4} 10^{5} 10^{6} 10^{7} 10^{8} 10^{9} 10^{10} 10^{11} 10^{12} 10^{13}
velocity of propagation v [m/s] = λ·f

Fig. 23.1: Frequency diagram of longitudinal and transverse waves as they depend on the velocity v.

23. Research of scalar waves

Scalar waves are still unexplored area, scientific new ground as it were. Individual research scientists already have selectively ventured forward in this area and have described properties of the scalar wave investigated by them in their special research area mostly in measurement technical manner. But as a rule they lack the physical relation, as it is derived in this book for the first time. If we don't proceed from individual measurements, but from the wave equation and the mathematical physical derivation of scalar waves, then we have the great chance to understand as something belonging together on the one hand noise, photons, neutrinos and lots of other known phenomena as well as on the other hand still unknown phenomena, which are called parascientific. We should remember that we without theory of Maxwell and the representation in a frequency band today still wouldn't know that the radio waves (LW, MW, KW, UHF), the microwaves (μW), the infrared thermal radiation (IR), the light and the X-rays concern just the same phenomenon. The graphic representation of both waves in one diagram in this place is extremely helpful.

23.1 Frequency diagram

In fig. 23.1 the frequency f is shown against the velocity of propagation v with the wavelength λ as parameter. The broad line at $3*10^8$ m/s represents the speed of light c. Here the frequency band of the transverse waves can be found again in the well-known one-dimensional representation.

Crosswise to that, somewhat unusual, the longitudinal waves run. These start at the left at localized noise, over the sound as it propagates in air, in water and in metal, over a large, to a large extent still unexplored, range of the bio photons, the heat vortices and of the dowsing rod effects and end on the other side of the speed of light at the neutrinos. Between that the special case is settled that the particles, or said better vortices, propagating as a scalar wave have exactly the speed of light. It gives reasons for the circumstance, as already mentioned, that light can appear as wave or as photon radiation. It. according to the wave equation, after all always consists of a combination of both forms. At very high frequencies, e.g. the cosmic radiation, this combination is shifted in the direction of vortices and their distribution as a scalar wave, at low frequencies the tendency inversely goes in the direction of the normal wave.

If we assume that for the transverse wave over all frequencies a dozen of specialized gauges is necessary, each of them also can be switched over in range several times, then we can project that to record a scalar wave of a certain frequency over all velocities of propagation likewise 12 devices and for the whole field shown in fig. 23.1 approximately 12x12 = 144 devices will be necessary. Of these 144 gauges today just 12 are available. There thus still are missing 132 pieces, which should be developed. With these gauges, so I am convinced, the many white spots in the diagram can be tapped scientifically little by little if a systematic procedure is used. My vortex theory thus will be attached a central importance.



Fig.23.2: Frequency diagram with entries concerning Wust waves,
Tesla transmitter and various not understood effects.

23.2 The reverse of the HF medal

The diagram possibly may settle disputes, like the ones between the „Wustlingen" (note of the translator: the author here is playing with words, Wustlingen literally means lechers) and the „high-frequency engineers".

Professor Wust of Munich already 1934 had proven, that the Wust waves named after him in air have a velocity of propagation of approximately 10 m/s<i>. He investigated them in the frequency range between 16 Hz (λ= 60 cm) and 500 Hz (λ= 2 cm). The high-frequency technicians immediately have converted to the speed of light, since they don't know anything else, and on the spot have shifted the phenomenon into the range of the microwaves between 0.5 GHz (λ=60 cm) and 15 GHz (λ= 2 cm). In the diagram now can be found, at which place this phenomenon belongs actually. It presumably concerns the same „energy ray", which Dr. Soeder has observed and proven already at velocities of propagation of 55.2 km/s and wavelengths around 10 cm<ii>.

Furthermore follows from the diagram (23.2), why ultra sound can be calibrated in heat degrees, and why radio reception of signals from a completely other frequency range is possible by principle, if for identical wavelength a velocity of propagation different from c occurs. Further the range of operation used by Tesla at approx. 1.6 times the speed of light is depicted.

Also the noise is such a book with seven seals. It concerns, it is true, a fixed chapter of high-frequency engineering, but without visible connection to the other chapters. That might be based on the circumstance that the relation, as it is dictated by the wave equation, isn't recognized.

Every high-frequency signal is accompanied by a noise signal; every antenna produces more or less noise. HF engineering dictates the measures, how the noise can be suppressed resp. the signal-noise distance be increased. The goal is to make the electromagnetic wave stand out in such a way from the noise that it can be received. For that the measurement setup must be choosen correspondingly, are the measurement cables dictated, and must be paid attention to power adaptation and corresponding termination resistors. For measuring HF correctly all interference influences should more or less disappear.

But what are the interference influences, which the HF-technician suppresses? According to the wave equation it are the scalar wave parts, and to that also is counted the noise. Every HF-technician thus knows the scalar parts as interfering noise signal, but doing so he completely fails to notice the technical advantages and chances, which e.g. are present in the noise.

If by means of an autocorrelation function a noise signal is compared to itself then often a hidden message comes to light. According to that, informations can be hidden in the noise and of course transmitted wirelessly. This important circumstance is known, but it is hardly used. The noise vortices thus can be modulated in an extremely complex way. There can be transmitted a lot more information in the noise as scalar wave, than with the radio wave.

<i>: J. Wust: Physikalische und chemische Untersuchungen mit einem Rutenganger als Indikator. Further references in W-B-M 3/ 1991, S. 57.

ii>: A. Soeder: Ohne Strom lauft neuer Energiestrahl rund um den Erdball. Raum & Zeit 59/92 Seite 62-67.



Fig. 23.3: ___ Dowsers dowse an ore vein.<i>
From: Speculum metallurgiae politissimum, Rossler, Dresden 1700.

<i>: Ludeling, Hartmut: Handbuch der Radiaesthesie, Verlag Eike Hensch 1994, S. 145, ISBN 3-927407-09-7.

The possibility of more dimensionally modulating and parallel image transmission make scalar waves superior to the radio waves in such a way that one should seriously think about the reversed procedure, in which the noise is conceived as useful signal and the radio wave as interference signal.

In the frequency diagram (23.1 and 23.2) can be read like in a diary, in which most pages it is true still are empty, but in which some very informative marginal notes can be found for different points of difficulty. It mostly are parascientific phenomena, which, not understood and excluded by textbook physics, are waiting to be taken up in the building of physics. As an example we'll pick out an extensive area of alternative research.

23.3 Radiesthesia

A particularly broad spectrum of scalar waves is provided by the already several times mentioned earth radiation. An ancient science of experience, which troubles the exploration of the earth radiation, is the geomancy. The Roman land surveyors, the Augures, used as an aid a flat coil like also Tesla did to receive scalar waves. The Lituus, as the device was called, resembles so much that of the Etrusks that we must proceed from the assumption that the method is much older (fig. 16.10).
This part of the scalar wave research, also called radiesthesia, is derived of ,,radiare", which can be translated with "send out rays" resp. ,,perceive". It describes the doctrine of the sensitivity to radiation of man. Doing so the radiation sensitive uses his own nerve framework as a biosensor.

The nerve conduction could be derived as a biological variant of the Tesla one wire transmission, for which ring-like potential vortices are passed on as action potentials in form of standing waves (fig. 9.6). Of this kind are also the control commands, which cause a muscle to contract. If now corresponding vortices are picked up by means of a dowsing rod or similar aids in our nerves, then the contract addressed muscles contract, because they can't distinguish, from where the command comes. This unconscious nerve twitch leads to a swing of the dowsing rod and to the well-known dowsing rod phenomenon. But man can't replace a technical gauge. Hence one speaks of dowsing and not of measuring. To this should be added the condition of resonance, which must be fulfilled. Since every person however builds up other resonances, dowsed results of others often can't be reproduced. But from this particular difficulty one cannot draw the conclusion that the phenomenon does not exist and radiesthesia is not a science. Series surveys and statistical analyses here in any case don't lead any further. It always only are individual talented dowsers, who have at their disposal really fantastic abilities and find with great certainty water, ores and even oil.
With the perception of a physical phenomenon it mostly starts. Cultural man looks after his discovery as cult, whereas modern man, guided by the wish for reproducibility and more objectivity, is troubled to design and to build a technical measurement work. With regard to the scalar wave in general and the radiesthesia in special we still are at the stage of the Stone Age.



Fig. 23.4: Nets dowsed at latitude 49.<i>

I. net: „global net" according to Dr. E. Hartmann;
orientation: N - S: 2 m distance and E - W: 2.5 m distance

II. net: „diagonal net" according to Dr. M. Curry;
orientation: NE - SW and NW - SE: 3.54 m = 2.5 m * sqrt(2)

[III. „lightning net" according to R. Schneider; orientation like I.]

[IV. net acc. to Benker; like I. but: N - S: 10 m and E - W: 10 m]

[V. sun/planet net acc. to W. Auer; with 3.66 m orientation S./P.]

According to Prof. E.G.Hensch et al.:

<i>: Hensch: Radiaesthesie im landlichen Bauen und Siedeln, Arbeitskreis zuf Landentwicklung in Hessen, W4, Wiesbaden 1987; resp.: W. Auer: Erdstrahlen?... AWGEO 199, Eigenverlag 1998; resp.: Mayer/Winklbaur: Biostrahlen, 5. Aufl. ORAC Verlag, Wien 1989, Seite 168

23.4 Prediction of earthquakes with the help of scalar waves

The standing wave character of the earth radiation is a help. There are dowsed points and lines of maximum radiation intensity, which form nets, which encompass the whole world. On the one hand we are dealing with a net oriented in direction north-south and east-west (Hartmann net) and on the other hand with a net standing diagonally to that under 45° (Curry net). Because the angle of 45° can be derived as borderline angle from a vortex field calculation[ii], I already early have pointed to the circumstance that it here presumably concerns a vortex phenomenon[iii].
Because the nets in addition are dowsed in air, it must be vortices of the electric field, so-called potential vortices[iii], which here form regular structures. The formation of vortex lines and complete vortex streets (chapter 4.9), which consist of countless individual vortices, can be explained as follows:
Electric scalar waves propagate in the direction of the electric field strength and mediate field vortices, e.g. neutrinos. If at a certain moment the transmitter carries a positive and the receiver a negative charge, then all the particles which are positively charged are repelled by the transmitter and attracted by the receiver. All run at the same time towards the same goal, although all mediated particles carry the same charge and repel each other! This incompatibility can be compensated partly, by the vortices rotating around each other. In this circumstance can be seen the reason for the structure shaping, the formation of some lines in the countryside (fig. 23.3). The distances between the lines have characteristic values, which allow conclusions about the wavelength of the standing waves. We must assume that they dictate the structure shaping and that the spatial vortex distribution aligns with the nodes and antinodes of the respective standing wave. The distance between the lines, which corresponds to half the wavelength, becomes smaller and smaller towards the North Pole and the South Pole of the earth, the net thus narrower and narrower. Also is the net said to change strongly before an earthquake. This all are clues for the circumstance that the structure shaping radiation comes from the earth, that the cause must be sought in the earth radiation.
It should be noted marginally that with scalar wave detectors, which permanently scan the nets, a just as effective as inexpensive earthquake prediction should be possible. Such a facility would be an enormous relief and help for all earthquake warning services. It even should be possible to determine in advance the future epicentre, if there is measured at the same time at if possible many stations and the respective deviations are compared.

A further influential factor is the composition of the subsoil; e.g. ores and metals influence the earth radiation. Water shows a special affinity for the earth radiation. It does collect the radiation and after bundling it up releases it again. To blame is the high dielectricity of water ($\varepsilon \cong 80$), which again favours the formation of potential vortices .
A technical use of this effect would be the neutrinolyse (see fig. 17.6-17.8 and 18.1), the splitting of water molecules by neutrinos if these take the state of an electron, hydrogen escapes and the oxygen content in the water increases. If a neutrino however shows as a positron, then it annihilates and there is formed a light flash, which serves the „experts" in neutrino detectors as proof.

[ii] Meyl, K.: Wirbelstrome, Dissertation Universitat Stuttgart 1984

[iii] Meyl, K.: Potentialwirbel Band 1, INDEL Verlagsabt. 1990

Spectroid of the radiation field of a subterranean flowing water veign (according to P. Schweizer)[i]:


main zone
main emphasis zone
announcement zone
announcement zone
2.
1.
1.
2.
3.
3.
Subterranean flowing water,
fault, fissure, cracks, caves, etc.,
but also ore veins, oil, coal, etc.

Fig. 23.5: Radiaesthetic search for water[i], (dowsing of the earth radiation)

---

[i]: Ludeling, Hartmut: Handbuch der Radiaesthesie, Verlag Eike Hensch 1994 S. 145, ISBN 3-927407-09-7.

23.5 Searching water with the help of scalar waves

Faults of earth's crust lead to fissures and cracks in the rock, which often fill up with standing or flowing water. Potential vortices of the earth radiation are attracted by the high dielectricity of water and are radiated again in slowed down and focussed form. On the surface of the earth the mixture of various scalar waves arriving there can be dowsed as main emphasis zone. For reason of the broad radiation spectrum the results of proficient dowsers in the main emphasis zone more often coincide.

At both sides in addition spectroids are forming, which are dowsed as parallel running vortex lines. Because every harmonic wave produces other lines and every dowser reacts to other resonances, a profound ability is required, if from the distance of the so-called announcement zones the water depth should be inferred (fig. 23.5). Some specialists indicate besides the place and the depth also the amount of deposit and if need be the water quality. For that they analyse the radiation intensity, but unfortunately many all too often overrate their abilities.

Already the Augures, the land surveyors in the age of the Romans have aligned their streets and the castles with the nets and the lines in the countryside. Even today new evidence about the central importance of the standing wave character of scalar waves can be found at excavations (fig. 16.10). Since every scalar wave also occurs coupled with a radio wave by means of the wave equation, earth rays originally could be detected conventionally with field strength gauges. But the intensive use by radio stations has made it necessary to change from the short wave range to the VHF-range and further to the UHF-range. It were indirect measurements, which could be interfered easily. Today geologists work with ELF scanners in a range between 15 and 30 KHz if they search for water. They analyse the emitted signals of submarine transmitters, because these are attracted and amplified by water carrying layers.

Experiments also are carried out with noise receivers or unused broadband TV channels. Others analyse influences of the earth radiation on the magnetic field of the earth, but for this method the expressiveness is controversial.

Again others walk along a path with a scintillation counter measuring the inverse profile. At the places of maximum earth radiation a minimum of gamma radiation is measured. This stunning relation only can be interpreted as follows: the natural radioactive decay at these places takes place accelerated and that proves:

1.. that earth radiation sets radioactivity free and causes it in the first place (chap. 17.1 pp).

2. that in the case of earth radiation it actually concerns slowed down neutrino radiation.

But also this method works indirectly. It only functions in the open air and then only in the case of unspoiled nature, which sometime was covered with an even layer of radioactive dust. By cultivation or plantation the „radioactive layer" very often is changed and mixed up, whereupon the measurable profile hardly allows conclusions.

For indirect measurement methods of that kind, for which the measurement variable stands in a relation, which isn't known in more detail, to the scalar wave of interest, generally caaution is advisable. Too often a message is seen in a wonderful 3-D diagram of the magnetic field strength or the radioactivity distribution, which has much more mundane causes.

Lecher air antenna according to W. Busscher<iii>:



short-circuited end of the Lecher conductor
short-circuit slider
can be displaced
handle
(man as
termination
resistor
and biosensor)
L
handle
n = 1
L = λ/2
n = 2
L = λ
n = 3
L = 3·λ/2
n = 4
L = 2·λ

The tuning length L of the Lecher antenna determines the resonator length for standing waves. There is valid:

$L = n \cdot \lambda/2$ with $n = 1,2,3,\ldots$

Therefore the wave length is ambiguously determined; e.g. for:

Fig. 23.6: Lecher conductor as scalar wave antenna.

Can be read at Prof. Dr. Ing. Christof Rohrbach:

<iii>: Rohrbach: Radiasthesie, Physikalische Grundlagen und Anwendung in Geobiologie und Medizin, Haug Verlag Heidelberg 1996, Seite 100.

23.6 Receiving scalar waves with the Lecher antenna

In the case of technical gauges it is normal to change the frequency tuning. For that the capacity of a capacitor is being varied, which is part of a resonant circuit. This method can simply be realized with the today available construction elements. Biological systems on the other hand, for instance a person, work primarily with a variation of the wavelength. In this case (according to eq. 22.1) the frequency is directly proportional to the velocity of propagation.

So provide for instance radiaesthetic dowsings clues for the wavelength. The frequency however can't be given, because that oscillates along with the velocity of propagation and at present the forming noise signal still can't be analysed. There can't be bought electronic construction elements, which like a body cell would be able of oscillations of length. Oscillation quartzes and piezo elements, on the basis of which scalar wave detectors could be constructed, form an exception.

Similar to the Lecher conductor different forms of tunable Lecher antennas have been developed. which are used for dowsing. Such a frame antenna, developed strictly according to the rules of high-frequency technology stems from W. Busscher (fig. 23.6)<i>. With the short-circuit slider a closed-loop antenna circuit in the upper part is tuned to half the wavelength or an integer multiple of it ($L = n \cdot \lambda/2$ with n = 1,2,3...). The person, who holds the Lecher antenna with both hands, forms the termination resistor for the attached antenna circuit. At the same time he prevents the occurring of an effect back on the tuned resonant circuit by means of damping of the Lecher conductor. The sense of this arrangement is lying in the circumstance that man as a „biosensor" should feel if standing waves, which I call vortices, are formed in the Lecher antenna.

A modification of the Lecher air antenna is the Lecher dowsing rod according to R. Schneider<ii>. It is produced as an etched board, which has a dielectricity of approx. 4. As a result the velocity of propagation and the wavelength are only half their normal value. In addition a shortening factor V is introduced, which depends on the construction of the Lecher dowsing rod<iii> ($L = V \cdot n \cdot \lambda/4$ with V = 0.952 and n = 1,2,3...).

In fig. 23.7 some published tuning values have been drawn up. The values for want of corresponding technical gauges it is true still haven't been confirmed, but they allow a certain insight into the world of the scalar waves, as they are influenced and radiated by water, by metals, by oil or even by other planets, the sun and the moon. Doing so some questions remain open: We for instance don't know, if the corresponding wavelength concerns the basic wave or only an m^{th} harmonic wave. The details not only are unreliable, they moreover also are ambiguous. If however several tuning values L' are present for which resonance occurs, then if need be an integer divisor can be sought and the wavelength can be determined. But that doesn't function always.

<i>: Will Busscher: Die Luft-Lecher-Leitung als Wunschelrute. Eine Methode um die Wellenlangen zu bestimmen. Wetter-Boden-Mensch 3/ 1991, Seite 46-57.

<ii>: R. Schneider: Einfuhrung in die Radiasthesie Teil II: Leitfaden und Lehrkurs ..., Oktogon-Verlag, Wertheim, 2. Aufl. (1984) S. 136.

<iii>: Rohrbach: Radiasthesie, Physikalische Grundlagen und Anwendung in Geobiologie und Medizin, Haug Verlag Heidelberg 1996, Seite 100.



Supposed wavelength λ of the transmitted scalar wave radiation in

[cm] λ	of:	(with the different tuning values L´)
32	water	(L´ = $15.5_{n/m=2}$; $10.8_{4/3}$; $7.8_{n/m=1}$; $3.1_{2/5}$)
18	fault	(L´ = $12.9_{n/m=3}$; $8.65_{n/m=2}$; $4.3_{n/m=1}$)
13.6	net I 4 m = 16 x 25 cm 5 m = 20 x 25 cm	(L´ = $12.2_{n/m=4}$; $9.6_{n/m=3}$; $6.1_{n/m=2}$; $3.05_{n/m=1}$ $1.7_{n/m=1/2}$) (N-S direction) (E-W direction)
14.7	net II 7.08 m = 30 x 23.6 cm	(L´ = $11.4_{n/m=3}$; $6.9_{n/m=2}$; $3.5_{n/m=1}$; $2.2_{n/m=2/3}$) (NE-SW + NW-SE direction)
13.2	net III	($12.6_{n/m\,4}$; $9.4_{n/m=3}$; $8.2_{5/2}$; 6.15_{2}; $4.1_{4/3}$; $2_{2/3}$)
16.4	radon	(L´ = $7.8_{n/m=2}$)
28.6	oil	(L´ = 13.5 to $13.8_{n/m=2}$; 3.3 *to* $3.5_{1/2}$)
17.2	gold	(L´ = $8.2_{n/m=2}$; $4.1_{n/m=1}$; $2_{n/m=1/2}$)
13.9	silver	(L´ = $6.6_{n/m=2}$; 3.2-$3.3_{n/m=1}$; $1.6_{n/m=1/2}$)
7.20	quartz	(6.9_{4}; $4.1_{5/2}$; $3.85_{9/4}$; $2.9_{5/3}$; $2.5_{3/2}$; $2.2_{5/4}$)
4.35	sun	(L´ = $4.15_{n/m=4}$)
15.3	moon	($3.65_{n/m=1}$. thermal spectral lines: 11; 21 cm)
4.25	Mars	($4.05_{n/m=4}$, thermal spectral line at 3.14 cm)
4.90	Jupiter	($4.65_{n/m=4}$, ther. spectral lines: 3; 3.2; 3.3 cm)
5.36	Saturn	($5.1_{n/m=4}$, thermal spectral line at: 3.45 cm)

Fig. 23.7: Details of not confirmed wavelengths.<i>
(derived from tuning values of a Lecher antenna
$L' = .\ V\cdot\lambda\cdot n\ /4\cdot m$ with $V = 0.952$
and n = 1,2,3... for λ/4, λ/2, 3λ/4, λ, ...
and m = 1,2,3... for 1 the basic wave
and the 2nd, 3rd, ... harmonic wave

---

according to:

<i>: Ludeling, Hartmut: Handbuch der Radiaesthesie, Verlag Eike Hensch 1994, S. 161 ff. The author gives the clue: ,,The values have been determined empirically by different persons and predominantly could be confirmed by the author and his co-workers. There however always can occur deviations caused by different dowsing methods. Every value therefore always should be checked with own measurements."

23.7 Assignment according to wavelength

As said, the methods to determine the wavelength by means of the Lecher antenna are ambiguous and unreliable. So water should have a wavelength twice as long as a fault. But since water often is collecting or subterranean flowing in faults, one is entitled the suspicion that here $\lambda/2$ was taken, where in reality the full wavelength λ acts. The rest of the table after that should be looked at with the same scepticism. The table nevertheless is not wholely uninteresting, because it points to certain trends and is able to furnish clues, which if need be can represent a help of orientation in the systematic research of scalar waves.

At the planets is remarkable that the Lecher conductor reacts to values, which correlate with the respective thermal spectral lines. If these spectral lines propagate with c and it actually should concern the same cause, the frequency thus should be identical, then the planets would emit scalar waves, which are faster than the light. In the case of Mars 1.35 times the speed of light c would be present, in the case of Saturn 1.55 times and in the case of Jupiter the values would lie between 1.46c and 1.63c. In the case of the moon two thermal spectral lines are being measured, which on the one hand have as a result 1.39c and on the other hand 0.73c. At this place still ample research tasks should be solved.

In the case of scalar waves the wavelength is the most important factor to refer to. The frequency however varies continually, which in electrical engineering is called noise. That again is connected to the circumstance that frequency and velocity of propagation oscillate, so that merely an average value can be given at a time. But that hardly can be measured, which again makes the assignment more difficult. We thus still aren't capable to enter the table values from fig. 23.7 into the frequency diagram of fig. 23.1.

A technical gauge for scalar waves is necessary. A practical solution could look as follows: A noise transmitter tunable in frequency and wavelength operates on top of a carried along noise receiver. The arrangement with that comes the Tesla transmission path for scalar waves very close. If the transmitted noise signal hits upon a likewise one in the surroundings then overlapping occurs, which at the receiver causes a change of the displayed value. If doing so a subtraction (extinction) or an addition (amplification) of the signals occurs is unimportant.

With this arrangement in any case statements are possible about frequency, wavelength, velocity of propagation and about the amplitude of the scanned signal, without withdrawing energy and strain the signal in doing so<i>. With such a gauge radiation conditions depending on location could be measured as well as technical devices checked lor the emitted scalar wave parts (fig. 24.1).

An important use over and above that would be given in medical diagnostics. Every living being „produces noise" the technician would say, it „emits scalar waves" I would say, whereas following general usage is talked about the „aura of man". The value of an aura diagnosis still is completely unknown to most doctors and therapists, especially as the scanning of the aura at present only is possible by dowsing. But the patient expects that a doctor works with a technical gauge and not with a dowsing rod!

<i>: First experiments, which I carried out with students in the laboratory, look very promising. Unfortunately the works at present rest for reason of lack of money.


natural
radiation field:
display
f
λ
noise
trans-
mitter
noise
re-
ceiver
+/−
−/+
coupling of phase (via the ground line)

Fig. 24.1: ____ Concept for a device to detect scalar waves

24. Medicine of oscillation

24.1 Mediation of information with the help of scalar waves

If for the discussed scalar wave gauge the transmitted comparison signal in addition deviates from the form of a sinus, if the signal is modulated in some way, then even the transmission of information by means of the noise as scalar wave can be realized. If we as an example again take the aura of man, which is more than only a radiation field, it carries information for instance about the state of health of man. Kirlian photography is one form of making it visible (Fig. 3.6).

Not only the nerve conduction and the brain work with scalar waves. Man in this way also corresponds with his fellow people, some more, others less. There are people who „beam" and that should be interpreted in the true meaning of the word. Others opposite to that are more „receiver characters", who pick up more scalar wave radiation than they give away. But because they not only pick up positive radiation energy, they are susceptible to information, which makes sick. That's why a healthy equilibrium in the exchange of thoughts, feelings and the different forms of scalar waves is very important. All that is reflected in the aura of man. If we technically are capable to scan the aura of man, than this can be a blessing for humanity and for the public health.

The possible abuse however must not be overlooked. Unbiased research results, which can be used for the benefit of humanity, in many cases just as well can be used to harm humanity.

A connector of both these worlds is the Russian psychologist Prof. Smirnov, who has shown publicly in television, how a spoken sentence can be transformed in a noise signal, which is taken up directly by the brain as information, with the help of a computer program <i>. He with that is capable to "sodden" individuals, as he says, he in this way can take the fear away from soldiers before a combat mission and can operate the disease out of drug addicts without bloodshed. In the television film such an „operation at the open subconscious"' is shown life. The patient hears the noise signal over headphones and is cured already after few minutes treatment time.

We here are getting in the domain of ethical and moral problems of scalar wave research, which aren't solved by us looking away and leaving the field up to others. According to the words of Prof. Smirnov the only thing, which can stop the research scientist, is his own moral. He doesn't say any more and that isn't exactly reassuring! One here is working with „signals resembling sound", is said in the report of the Zweite Deutsche Fernsehen<i>, thus with longitudinal waves and that shows, that already more knowledge about scalar waves is present than is generally known by the masses.

Another way is leading over the bioresonance. Also here at first the possibility and chance to cure diseases is to the fore. The bioresonance is a central aid in the area of the medicine of oscillation, which is increasing in importance permanently.

<i>: Die Zombies der roten Zaren (Besta Film Warschau im Auftrag d. ZDF 1998)


transistor amplifier
(pnp type)
tension voltage supply
(battery)
+
+
4 - 5 Volt
10µF
e.g.
2N3906
150 Ω
transformer 11:1
4,7nF
100nF
headphones output 8Ω
handle
(signal)
reference probe
(mass)
Bio-Feed-Back:
The test subject
with headphones
(input of the signal)
and hand electrodes
(taking off of
the signal)

Fig. 24.2 A: Wiring diagram of the Syncrometer.<i>

<i>: Wiring diagram taken from: H. Clark: The Cure for All Cancers (1993) New Century Press, USA, Page 434

<ii>: Flanagan: Horen mit der Haut anstatt mit den Ohren, Sonnenwind 1/97, S.13-17.
s.a.: N.Begich: Towards A New Alchemy, The Millenium Science, Earthpulse Press 1996

<iii>: Dr. Bodo Kohler: Biophysikalische Informations-Therapie, Gustav Fischer Verlag (1997), Kap. 11.6 Der individuelle Grundton, S. 239 ff.
s.a.: Dr. Bodo Kohler: Die bipolare Farb-Ton-Therapie, CO'Med 2/2000, S.10 - 15

24.2 Systems with positive feedback

The field of oscillation of man easily can be influenced, because it concerns a vortex field. A technical measurement with the gauges available at present is almost impossible and highly inaccurate. There however exists the possibility, to apply electrodes to a person and to integrate him in the circuit of a technical device. The two of them form a feedback system with man in the return loop. The operation can take place in two different ways, depending on the sign of the feedback (Fig. 24.3):

For positive sign it concerns positive coupling. In this case the signals released by a person sum up, for which reason already minimum amplitudes are sufficient to produce violent reactions in the case of resonance. For resonance to occur, the system must either search independently the suitable frequency and phase, or the therapist searches the points of resonance.

24.2.1 The Syncrometer.

An independently working system is e.g. the Syncrometer. By means of two electrodes, which are held with the hands or are attached directly to the head, the noise signal emitted by a person is called off and supplied to a broadband amplifier. The test subject again hears the amplified signal via headphones, so that the circuit is closed.

Apparently unspecific and still reproducible during operation certain signals capable of resonance are emerging stronger by amplifying and swinging themselves up. The aura starts to extend or expressed in the words of a radiation sensitive, the so-called reaction distance is increasing, with which he means the distance in which he detects a dowsing rod reaction.

The test subject now increases his radiation, so this method can be valued. By strengthening his own radiation power, he works more as a transmitter and less as a receiver for scalar waves. In the last point the therapeutic use seems to iie, because by that the patient can get rid of resonances to any unpleasant persons or to technical transmitters, which are burdening him. The device consequently also is sold as aid or protection against electrosmog.

The amplified signal also can be picked up directly by the skin instead of by the headphones and still being „heard". The reports stretch from a harmonizing and balancing effect up to "electronic telepathy" and states similar to ecstasy of the test subject<i>.

24.2.2 The sound therapy.

The controlled variant of this method for instance is the sound therapy. Now the sounds, which the patient picks up by means of headphones, do not stem from him but from a sound generator. The therapist goes through the scale and tries to find out at which sound the aura swings up. If the eigenfrequency is found, then the patient can therapize himself, by again and again playing or humming his eigentone<iii>.

It concerns here only a physical statement on the used methods of alternative medicine and not therefore, whether healing successes are actually possible.

sound frequency equally tempered [Hz]		wavelength [cm]	colour	wavelength [run]
F sharp"	740	46,4	(purple)	-
F"	698	49,1	(crimson)	-
E"	659	52,0	(violet)	-
D sharp"	622	55,1	indigo	421
D"	587	58,4	bleu	446
C sharp"	554	61,9	turquoise	472
C"	523	65,6	green	500
H'	494	69,5	yellowgreen	530
A sharp'	466	73,6	yellow	562
A'	440	78,0	orange	595
G sharp'	415	82,6	orangered	630
G'	392	87,5	red	668

Table 24.2 B: Scale of the colour range.<i>

colour		chakra	sense organ	planet type
purple	7.	(crown chakra)	epiphysis	Jupiter
indigo	6.	(brow chakra)	hypophysis	Saturn
bleu	5.	(throat chakra)	hearing	Mars
green	4.	(heart chakra)	feeling	Sun
yellow	3.	(solar plexus)	seeing	
orange	2.	(sacral chakra)	taste	Venus
red	1.	(root chakra)	smell	Moon

Table 24.2 C: Assignment of colours to chakras and planets.<i>

colour		metals	gems (selection):
purple	7.	tin	amethyst, fluorite
indigo	6.	lead	indigo-sapphire, azurite
bleu	5.	iron	sapphire, lapis lazuli
green	4.	gold	emerald, malachite, jade, gr. tourmalin
yellow	3.		topaz, amber, citrine
orange	2.	copper	carnelian, fire opal
Rot	1.	silver	ruby, coral, garnet, red jasper

Table 24.2 D: Assignment to a selection of gems.<i>

<i>: Dr. Bodo Kohler: Biophysikalische Informations-Therapie, Gustav Fischer Verlag (1997), Kap. 11.6 Der individuelle Grundton, S. 190 - 194

24.2.3 The colour therapy.

Analogous to acoustics also colours each time can be assigned a wavelength and also here can be detected that every person responds to certain colours, thus wavelengths, in particular which can stimulate his aura to resonant oscillations. In practice sound and colour therapy often are used coupled<i>, even succeeds more or less an assignment to each other. That in last consequence leads to a "scale of the colour range" (table 24.2 B)<ii>. According to statement of the treating doctors does a patient, who responds to a certain colour, also react to the corresponding sounds and vice versa.

24.2.4 The aroma therapy.

If according to that it depends less on the circumstance if sounds or colours are used, but the wavelength of an oscillation is crucial, then a stimulation also should be possible by means of the remaining sense organs, e.g. the nose, the tongue or the skin. The smell after all already could be identified as vortex information (fig. 9.0). Fragrances of natural essences can significantly influence the frame of mind. But as long, as we still haven't understood the physics behind it, we technically hardly are capable to generate equivalent vortex modulations artificially.

24.2.5 The gem therapy.

Already the holy Hildegard von Bingen (1098-1179) knew and used the beneficial effect of gems. Physical background of this at first purely empirical form of therapy is the characteristic eigenfrequencies of the gems, which are picked up as stimulation over the skin. Because gems represent a mixture of various molecules, the oscillations in the atomic hull will overlap, so that overlapping and beat frequencies can form with wavelengths in biological relevant areas. There even can form modulations, which are carrying information. The effectiveness again is linked with the resonance condition, which must be fulfilled between the gem and his carrier.

24.2.6 Meditation and self-therapy.

There even exist people, who don't need any technical aid at all to get rid of unpleasant resonances. Some meditate and go into resonance with themselves, whereas others prefer to love a person, to whom they feel „attracted" or with whom they are „on the same wavelength", which means as much that they go into resonance with this person. In the Catholic Church for instance the priests are not allowed to get married, because they should be in a resonance with the church and with God.

<i>:: Dr. Bodo Kohler: Die Coloroma-Therapie, Der aussergewohnliche Einsatz von Aromen, Co'Med 4/2000, S. 48-52

<ii>: Cousto: Die kosmische Oktave, Synthesis Verlag Essen 1984


medicine of oscillation
measure:
technical goal:
medical goal:
positive coupling
amplification
strengthen aura and immune system
negative coupling
effacement
fight centres of disease
regulation or control:
closed circuit
open control chain
closed circuit
open control chain
in chapter: Ausführungs-beispiele:
24.2.1 Synchro-meter
24.2.2-6 sound therapy
24.3.1 bio-resonance
24.3.2 frequency therapy

Fig. 24.3 A: Structure concerning the medicine of oscillation


phase shifter
(+/−)
positive coupling: +
negative coupling: −
amplifier stage
headphones/ loudspeakers
control signal
feedback: electrode/human/ear

Fig. 24.3 B: Regulation or control?
Positive or negative coupling?

24.3 Systems with negative feedback

For negative sign it concerns negative coupling. In this case the signals are subtracted. The signals released by a person are played back to him with opposite phase. This method lies in the domain of the bioresonance.

24.3.1 The homeopathy

The concept, which is pursued by the medicine of oscillation in the case of the bioresonance, is that harmful or ill making oscillations should be effaced. Not the direct, but rather the indirect strengthening of the immune system is to the fore, which should be reached by relieving it. The approach with that pursues the same goal as the pill medicine, where oscillations, which should produce a wanted effect and which are bound by means of substances are supplied to the body.

The disadvantage of the administration of pills is the often toxic effect of the carrier substance. The German doctor Samuel Hahnemann (1755-1843) has demonstrated a way, in which to make the helpful and important information for the body to go over from the carrier substance to the water by diluting with water and by shaking. The water molecules now oscillate in time of the carrier molecules. Interestingly in doing so not even the information gets lost, the modulation thus is preserved. By constantly shaking there even occurs an amplification or a „potentiation", as Hahnemann expressed himself, because now every carrier molecule reaches and modulates countless water molecules. Thus the amount of water informed is bigger than the amount of the original chemical substrate. In the case of homeopathy like is treated with like. If for instance a poison causes certain complaints at a healthy person, then in "homeopathic" administration this information helps a sick person with similar complaints. There thus occurs a disturbance activation with opposite phase, as the engineer uses to express himself. Despite a widespread scepticism the method of homeopathy indeed seems to function, and it has stood the test in countless cases.

24.3.2 The bioresonance

A technical realization is represented by the bioresonance. For that endogenous oscillations are called off by means of an ECG (electrocardiogram), an EEG (electroencephalogram) or a MEG (magnetoencephalogram) at the surface of the skin. The technical device then shifts the phase for 180 degrees and amplifies the signal to the extent that pathological frequencies are extinguished for reversely directed input. This very reasonable theoretical concept in practice of course only is as efficient, as the empirical determined pathological frequencies are the cause of a disease and not only represent an unimportant symptom as side effect.

To that technical problems are joining. Prof. Heine blames the constantly changing reaction diversity and the thermal noise for the circumstance that the „frequency spectrum permanently is fluctuating", as he writes if*. That hardly can realize the necessary phase inversion. We meanwhile know that vortices have a fluctuating frequency spectrum, that in the case of biosignals it concerns such field vortices, which result in a noise signal unspecific in frequency.

With this knowledge we should be able to significantly improve bioresonance procedures, and even the inversion of phase shouldn't represent an insurmountable difficulty anymore.



Fig. 24.3 B: Frequency spectrum of parasites according to Clark.<i>



Fig. 24.3 C: Diagram of frequency ranges for some living beings.<i>

<i>: Dr. Hulda Clark: The Cure For All Diseases (1995), Page 604-643

A further problem, which Heine addresses, can't be denied[ii]: „For communicative molecule oscillations the microwave range of 1 GHz up to above 10000 GHz is crucial. A calling off of endogenous interference oscillations in this range with the help of normally used electrodes is not possible"[iii]. It thus could happen that essential frequencies, which are directly related to a disease, aren't recorded at all and as a consequence also not treated. There even is the risk of informations being brought in, which additionally stress the immune system instead of relieving it, that the patients after a treatment are worse off than before. The doctor or therapist is burdening himself with a big responsibility, when, how and at whom he applies methods of bioresonance or if he better does without them. For the mentioned reasons the method in the therapy only plays a secondary role. The bioresonance on the other hand is quite often and with great success used in the diagnosis (Nosoden), if it for instance concerns the determination of an incompatibility or an allergy - but that is a completely different theme. For the bioresonance the transition of diagnosis to therapy is however floating.

24.3.3 The frequency therapy

If using a frequency therapy the problems are standing similarly. If we separate the closed and negatively fed back circuit of a bioresonance and form an open control chain consisting of a technical control device and the patient, then we get the structure, as it is put to use in a frequency therapy. The goal still is the same: parasites or pathogenes, which stress and burden the immune system should be fought.

But a disadvantage of every open control chain is that the treatment at first occurs blind due to the missing feedback.

The natural healer Dr. Hulda Clark has examined as support various pathogenes and parasites under the microscope, while she has varied the frequency and at the same time applied a low-tension voltage. Doing so she could observe the dying of bacterias and parasites at certain frequencies. Correspondingly she publishes tables, in which the in each case „mortal" frequencies are listed[i].

Hut without being able to verify the success of a treatment in the living organism, she proceeds from the assumption that by applying a low tension voltage (5-10 Volt), as it is produced at the output of a commercially available frequency generator, if a sinusoidal signal is set with the appropriate frequency exactly the associated parasites and leeches will be destroyed. Doing so a fixed rhythm of pauses and treatment times must be adhered to (7 min on, 20 min off, 7 min on, 20 min off and 7 min on).

The doctors and therapists treating with this particularly inexpensive method report amazing results, inexplicable spontaneous cancer cures, like of HIV-positive patients, who after the treatment were tested HIV-negative. But also the inverse case already should have occurred, that a HIV-negative patient afterwards was HIV-positive! Here too clear the limits of this method appear, which in practice unfortunately turns out to be relatively unspecific.

<ii>: Prof. Dr. H. Heine: Grundregulation und Extrazellulare Matrix - Grundlagen und Systematik, Lehrbuch der biologischen Medizin, (1991) 2.Aufl. Hippokrates Verlag Stuttgart, Seite 63

<iii>: U. Warnke: Bioresonanztherapie - Wunsch und Wirklichkeit. Medizin transparent Nr.2 (1996) S. 36-37


8
4
Vcc
R
1k
switch
timer
MC 1455
D
3
5
CV
DIS
7
+
battery
9 V
GND
TR
THR
1
2
6
3,9 k
1 k
3,9k
10 nF
4,7 nF
2 mA LED
reference probe
(mass)
handle
(signal)
control:
The test subject with hand electrodes (for picking up the signal) without return

Fig. 24.4: Wiring diagram of the Zapper.<i>

Wiring diagram taken from:

<i>: H. Clark: The Cure for All Cancers (1993) New Century Press, USA, Page 507, resp.:

Dr. Hulda Clark: The Cure For All Diseases (1995), Page 48

24.4 The Zapper

From the point of view of physics of today the frequency therapy actually shouldn't be able to function at all. The electromagnetic waves penetrate only few millimeters into the skin at the used frequencies and wouldn't have the slightest chance, to reach a parasite, which is staying somewhere in the body. But it is said that it is possible to cure athlete's foot, by the patient taking the electrodes in his hands. How, we ask the question, does the signal of the function generator know where it should go?

It quite obviously concerns a resonance phenomenon. The likewise emitted scalar wave part tunnels undamped at those places in the body, with which it can build up a resonance and that for proper tuning are the unloved parasites. The scalar wave radiation is bundling up at the resonant receiver, so that despite the low transmission power as a consequence of the bundling up the energy density for the parasite becomes very high. It as a result is destroyed by its own ability to go into resonance. Once it is killed, the next one goes into resonance, logs off as well etc. In this way the parasites are destroyed one after another and not all at once. That's why the specified treatment cycle makes sense.

The copper electrodes should not be taken in the hands directly, Dr. Clark recommends, but before be wrapped with moist paper. By means of this insulating layer, so is my interpretation, the conventional wave part, for which the skin functions as a wave guide, is reduced whereas the desired scalar wave part is increased. Such measures crucially contribute to the success of a therapy method, even if they were determined purely empirical.

If one wants to address every possible parasite individually, then the treatment takes correspondingly long. If one on the other hand sends all relevant frequencies at once by overlapping them, then the treatment can be abbreviated to the duration of one session. If the therapist goes still further and replaces the sinusoidal signal by a rectangular signal, then infinitely much sinus functions are hidden in it, as a Fourier analysis shows. With a rectangular signal, as it is delivered by the Zapper, one as it were catches everything, Good as well as Bad. There the helpful intestine bacterias break exactly like the wrongdoers.

The treatment with the Zapper is simple, inexpensive and exactly as controversial. It is the shot with the shotgun in the forest. One always hits something. We nevertheless must ask the question, why one only hits parasites and bacterias and not the vital organs? Aren't those damaged also?

Now then, the signal of the function generator is not modulated; it doesn't carry information. That's why only monocellular parasites, which don't know information exchange, are capable of a resonance. Human cells and more than ever whole organs on the other hand work with complex modulations, which effectively prevent any formation of resonance with the technically generated basic wave, with which the question would be answered so far.

That however also means that immune reactions can be expected: If the first treatment with the frequency therapy still is successful and all simple parasites could be hit, then only further evolved parasites have been spared, which modulate their information. They now breed and can't be reached anymore in further sessions. The method suddenly doesn't function anymore, the therapist finds out, the body apparently has become immune.



scale:		diatonic	chromatic	spiral
sound:		•1/C =	equally tempered	(medieval)
octave	C´	2/1 = 2.0	2.00	2/1 = 2
		1.07 = 16/15		1.33 = 4/3
seventh	H	15/8 = 1.88	1.89	3/2 = 1.5
		1.125 = 9/8		1.125 = 9/8
sixth	A	5/3 = 1.67	1.68	4/3 = 1.33
		1.11 = 10/9		1.07 = 16/15
fifth	G	3/2 = 1.5	1.5	5/4 = 1.25
		1.125 = 9/8		1.04 = 25/24
fourth	F	4/3 = 1.33	1.33	6/5 = 1.2
		1.07 = 16/15		1.03 = 36/35
third	E	5/4 = 1.25	1.26	7/6 = 1.17
		1.11 = 10/9		8/7 = 1.14
second	D	9/8 = 1.13	1.12	9/8 = 1.125
		1.125 = 9/8		10/9 = 1.11
first	C	1/1 = 1.0	1.00	11/10 = 1.1

Fig. 24.5: Harmonic spiral built on the first Gregorian scale.<i>

<i>: Dr. Manfred Doepp: Naturgemasse Frequenztherapien, Die Harmonie der Snirale. CO'Med 10/2000. S. 46 - 49

24.5 Discussion concerning the medicine of oscillation

The textbook medicine in its explanations and treatment methods is basing on the models, which it can measure and analyse and which it understands. Doing so man and whole nature is reduced to a handful of chemical reaction formulas. The whole pharmaceutic industry lives on this misleading path, which long ago has revealed to be a dead end, medical as well as financial. This health service cannot be paid anymore and we should ask the question if it actually is worth the money, if with electric signals of minimum power can be obtained effects comparable to the effects of the pill medicine.
We need a new medicine, a potential vortex medicine. First of all we should research how an organism covers its energy needs and how it communicates. There leads no way past the scalar waves and the newly discovered potential vortices. Chemical processes as they are being observed, occur by the way, that is beyond doubt, but they by no means are the cause. Hence of pills and other chemical means at most a treatment of symptoms and a case of side effects may be expected but not a cure of a disease. Once the potential vortex medicine will be systematically explored and be put to use in practice, healing successes can be expected, which we at present can't imagine at all.
The amazing results, which already today are obtained in the medicine of oscillation and of which some doctors can report<i>, dictates the direction in which the textbook medicine should develop. In the question, which kind of oscillation or which „sequence of sounds" (Fig. 24.5) is the right one, still exists considerable need for research.
Some doctors even already work with my new theory and cite whole passages from my publications until now about this theme<ii>.

<i_a>: Dr. Bodo Kohler: BITsyn, der neue Weg in der Informations-Medizin, Jubilaums-Schrift der Internationalen Arzte-Gesellschaft fur Biophysikalische Informations-Therapie, Bad Nauheim den 6.-8.10.2000, Seite 48 - 56.

<i_b>: Bioenergetische Messverfahren in Theorie und Praxis, Vortragsband der Gesellschaft fur Energetische und Informationsmedizin e.V., Universitat Stuttgart am 17.7.1999.

<ii_a>: Dr. Johann Lechner: Storfelddiagnostik, Medikamenten- und Materialtest, Teil 2 aus der Reihe: Praxis der Ganzheitlichen Medizin und Zahnmedizin, Verlag Dr. E. Wuhr (2000), Kap. 2.4.2 Beruhrungslose skalarwellentragende Informationsubertragung S. 173 ff., bes. Kap. 2.4.2.3 Seite 175, 176.

<ii_b>: Dr. Reichwein, Peters: Zellulare Elektromagnetische Systemsteuerung, Der Freie Arzt 5 (2000) im Wissenschafts-Forum (Anhang, S. IV - XXIII).

<ii_c>: Dr. M. Doepp: Tesla-Wellen, Neue Studien, CO'Med 5/2000, S. 94 - 95

Frequency spectrum of the human organism:



Fig. 25.1: The measured frequency spectrum of man.[i]

---

[i]: Dr. P. Bembenek: Akupunktur und (Bio-) Resonanz, CO'med 6/98, S. 50-58

25. Contributions to the discussion concerning the information technical use

The medical research predominantly takes place with statistical methods. This might be changed fundamentally, if only the physical relations have been realized and their causes found out. Only then a basic research will be possible also in the area of medicine, as it today already is usual in other disciplines.

In this chapter it concerns the question of the medical basis in general, and specifically the question of the use of the newly discovered potential vortices in biological systems. Doing so very aware is attempted to put the normally used medical view at the back and to derive the answers from the perspective of the engineer and the physicist. This approach is unfamiliar, so that some textbook physicians will have difficulties to follow. It however will prove to be very helpful. Medicine in addition needs new impulses and that justifies a new approach, like the unconventional one proposed by me.

In this connection gladly is fallen back upon the comparison of biological with technical systems, although here exist differences in principle and fundamental It can be expected that nature has developed very appropriate strategies to solve certain tasks, as it also is teached in engineering and used in practice. At this place not only medicine benefits from new insights, engineering vice versa also can learn of nature, because natures optimization strategies are much much older and correspondingly perfect.

25.1 Window of the sensuous perception

To clarify the inner processes in man we consider his sense organs, which function as interface to the outside world. Technically seen in the case of the sense organs it concerns measurement converters to record and process certain physical values in our environment and their adaptation to pass on the information by means of the nerves. The measurement converters thereby are built more or less complex, which is related to the circumstance that the measurement factors, which a living being needs to orient itself and to be able to survive, are quite different.

It concerns little windows within the frequency spectrum shown in fig. 23.1, which should be analysed. Man for instance chooses the visible frequency window and interpretes it with an assignment to the colours, because in this range the sunlight can reach the surface of the earth and the ionosphere doesn't exert an excessive damping (fig. 2.8).

The acoustic window depends on the sound propagation in air, whereas dolphins work with ultrasound, which carry considerably further in water. The associated measurement converters, the ear and the eye, have a very complex structure. From this can be inferred that here the received signal must be transformed into a different physical measurement signal, that the perceivable signals are of other nature than the signals, which our nerves are able to pass on.


refractive secretion
sight cells
pigment cell
nerve

Fig. 25.2: ____ The hollow eye of the snail

25.2 The sense organs (nose, eye, tongue)

If we want to find out something about the nature of the nerve signals, then we should more detailed consider a sense organ, which is constructed if possible simple. In that case it is possible that no signal transformation is necessary at all anymore, because the perceivable variable is exactly of the kind the nerves can process.

The primary and perhaps most ancient sense organ of the living beings is the nose. It is constructed extremely simple. On the one hand according to encyclopaedias it is a chemical sense for the perception of smell materials. Man on the other hand can distinguish several thousands of scents. For that a huge analysis factory with correspondingly much receptors would be necessary, which one searches in vain in the nose between the nasal hairs and the nerves. We from that infer that scent should consist of particles, which are to a large extent identical with the reaction potentials. It thus will concern potential vortices. These ring-like vortices of the electric field again are modulated and carry information, which our brain is able to analyse.

According to the derivation in chapter 9.0 Plato already 2400 years ago knew such relations. The conclusion is obvious that smell is vortex information, which according to the explanation of Plato forms at the transition of waves in potential vortices and vice versa. At the natural philosophers in antiquity the circle of the insights is closed. Modern science just isn't that far.

The hollow eye of the snail functions both as nose and as eye (fig. 25.2). This very ancient combined organ points to a relatively close affinity between both measurement sensors. Possibly in the course of evolution both organs have developed from such a common original form.

In the case of man the smell rods occupied with the nasal hairs of roughly 2 micrometer in length, actually remember of the rods and cones in the eye, with which photons are collected. In both cases, so we can explain the mode of action in accordance with model, the ring-like vortices settle on the rods and run as reaction potentials along the nerve to the brain, which then analyses the modulation.

In the case of the highly developed human eye the light rays first have to traverse the vitreous body and afterwards a pigment layer, before they reach the rods and cones. In this way the electromagnetic wave parts must roll up to vortices, since our nerves can only pass on vortices. The photons can be interpreted as corresponding vortices.

If we compare the eye with a bubble chamber, in which the tracks of ionized particles can be observed and photographed as thin white fog stripes. Here in collision experiments it can be proven that it concerns particles carrying impulse and not waves. But the measurement setup by no means does answer the question if it already concerned particles before they entered the bubble chamber, or if these have formed spontaneously in the presence of the saturated vapour.

It would be obvious, if for our eye the chamber water being under the inner eye pressure would take over the function of the bubble chamber and would take care of the rolling up of the light waves to light quanta.

Example tongue:


taste hairs
nerve bundles

Fig. 25.3: Taste bud of the human tongue

We optically can't detect a difference, if the light while passing through a thick glass plate increases its part of photons. At the latest in the eye in any case all the light is transformed in photons and usable vortices, so that we mustn't detect a loss of brightness. The glass plate seems transparent to us, even if the sunlight should change its composition and its biological quality, if it passes the plate.

If the tongue while tasking responds to dissolved substances, then it not by all means needs to be a chemical excitation. Instead fine hairs, the taste hairs resp. sense pins, serve as receiver like in the case of the nose. The similar structure of the receptors and the circumstance that for most invertebrates sense of taste and sense of smell can't be distinguished of each other at all and consist of the same primary sense cells, suggest that the tongue doesn't analyse the chemistry as such, but only the molecular oscillation patterns, that also the taste is nothing else but vortex information!

25.3 The nerve conduction

For the collection of the potential vortices and the extraction of their information fine hairs in the sense cells obviously play a central role. They are connected more or less directly with the end of a nerve and pass on the information without big transformation. Even in the organs of equilibrium sense hairs work.

From the comparison with the technique developed by Nikola Tesla I could show that the nerve conduction concerns a single-wire transmission, a kind of waveguide, for which the transport of the excitation information takes place in the insulation layer and not in the conductor itself (fig. 9.6). As proof I quoted that the thickness of the insulation determines the velocity of propagation, that as is well-known the nerve conductors with thick fat layer pass on their action potentials faster than those with thin insulation. Particularly interesting is the observation, how the fat layer is constricted in fixed intervals, like for Wiener sausages (fig. 25.4 A). These nodes of Ranvier prove that only longitudinal waves are being transported, which are standing waves with nodes and antinodes, if the distance from node to node exactly corresponds to the distance from one node to the next. With that nature with the use of the potential vortices is far ahead of our power engineering. The nerve-cables determine with their structure, which signal will be transported and which not!

The technical cables on the other hand are stupid and conduct everything, the useful signal just as well as any arbitrary interference signal. Anyone, whom the computer crashes every few minutes, knows what I'm talking about.

Man isn't able to afford a crash of his think computer. It would be lethal for him. His nerve costume even tolerates short-circuits. The acupuncture is such a short-circuit technique by means of electrically conductive needles. There even is given a therapeutic benefit and a relaxing effect for the body.

Cut through nerve fibers even can partly regenerate again, even without a cut through nerve again growing together with its other end. The nerve conductors are so intelligent, that only the matching information arrives at the end by passing on informations from one fiber to the corresponding next with the same node interval.

A. Nerve conduction with nodes of Ranvier (to transmit standing waves):


magnified:
λ/2 ≈ 1mm
axon
action potential (potential vortex)
nodes of Ranvier
Schwann cell
insulator = Myelin hull (wound as Tesla coil)

B. Single-wire transmission according to Nikola Tesla<i>:


transmitter
sequential insulation
receiver
consumer
ground
ground

Fig. 25.4: ____ Selective scalar wave signal transmission

The brain works with scalar waves! Reasons are:

1. Lacking of a signal transformer between the nerves and the brain.
2. High performance density of the think apparatus.
3. The brain activity measurable from the outside with the EEC
4. Spark formation and corona discharges at open top of the skull.
5. Insulation defect occurring in the case of epileptics.

<i>: Original sketch of Tesla is situated in the Nikola Tesla Museum, Belgrade.

Nerves represent an intelligent and at the same time interference safe wiring, which is superior to any technical solution by far, or you can try to acupuncture a cable cord of your computer. You will have little pleasure of it.

Nikola Tesla also in this point was ahead of the times. He has experimented with a single conductor technology, for which the insulation layer is constructed like for a nerve fiber (fig. 25.4 B). We'll have to learn to handle such aids in the future, if we in engineering want to emulate nature and as well want to send informations as scalar wave. A normal power cable as said conducts everything, useful as well as interference signals. If however the signal should be accomodated in the noise, a selective cable is required, which should be constructed according to the example of the nerve conductors. Before a scalar wave technology can be introduced and successfully used according to that completely other cables, coupling elements, amplifiers and other components should be developed. The trouble should be worthwhile at the chances, which this genial technology offers us!

25.4 The brain, a scalar wave computer

The brain cells (neurons) are of the same kind as the nerve cells. Hence can be done without a signal transformer, can the informations transmitted by the nerves to the brain directly be processed further. From that follows that also the brain without exception works with potential vortices. There are several reasons for this hypothesis:

1. as said, the lacking of a signal transformer.
2. the high performance density of the think apparatus. (As a result of the concentration effect of the potential vortices the efficiency of the human brain is in such a way high concentrated compared to the much more space claiming computers functioning on the basis of currents).
3. the brain activity measurable from the outside with the EEC
4. spark formation and corona discharges at open top of the skull. (Brain surgeons can report of such observations).
5. The insulation defect occurring in the case of epileptics. (During a fit instable potential oscillations of the nerve cells occur, which lead to strong electric blows).

With the „exciting" and the inhibiting"' synapses as separation point between the neurons both a ,.high-active" and a „low-active"' method of operation is possible and with that a redundant, particularly interference safe signal transmission.

Safety for interference is very important not only in nature. In the operating instructions of a PC can be read: „operate only at room temperature, keep dry, don't throw or shock, take cure for sufficiently cooling air, ground apparatus, pay attention to mains voltage, etc". A comparison with the range of operation of man is like scorn.

Nevertheless the consequences if errors occur are quite similar: a garage door, which opens if a mobile is switched on, by all means can be compared with a light phenomenon, which we perceive after a blow on the eye at the biological level.



Concerning signal technology:

The **comparison** of	**man** and	**engineering**
signal line:	**nerves**	**cables**
transmission:	selective (nodes of Ranvier)	indiscriminate (with interferences)
of:	scalar waves	currents
by:	potential vortices	charge carriers
running of cables:	1-wire technology	2-wire technology
over:	wave guide	supply and return cable
signal transport:	in the insulator	in the conductor
signal form:	concentrated	expanded
the conductor:	stays cold	gets hot
result, transmission:	without losses	with losses
error signal:	muscle cramp	malfunctions
metal pins:	**acupuncture**	**short-circuit**
cause:	relaxation	destruction
directional signal by:	synapses	diodes/ amplifier
redundancy by:	exciting and inhibiting synapses	high-active and low-active drivers
precaution:	skin resistance	shielding
by:	salt	metal case
strategy:	vortex decay	field displacement

Fig. 25.5: ____Comparison of the signal technology

25.5 Concerning signal engineering

By means of a technical analysis of biological relations completely new interpretations result also for the occurring of a disease. We permanently and everywhere are surrounded by noise signals, but as a rule they can't touch us, because the body has developed perfect strategies for defence. The nodes of Ranvier on the nerve bundles here are just as helpful as the diode effect of the synapses. By means of the salt content and the skin resistance the body in addition controls the uptake of potential vortices from its surroundings, by using that the vortex decay is determined by the conductivity.

The specialties of the by humans used signal technology come to light particularly clear if compared with the cable technology used in the technical world (fig. 25.5). So is worked with only one wire instead of with supply and return cable, are mediated potential vortices instead of charge carriers, does the transmission take place in the insulator without losses and not in an electric conductor, which as a result gets hot and produces current heat losses. Nerves thanks to their ability of selection represent an intelligent form of signal transmission, by helping to filter the asked information from the noise. This surely is necessary since with cables, which indiscriminately transmit every signal, an use of scalar waves hasn't succeeded yet. We should try to learn of nature!

A special challenge is the protection against error signals. A passive shielding by a metal case however is not possible, because scalar waves can't be shielded by principle, so that the precaution should be taken actively by means of the conductivity. That's why we sweat salt if we strain us physically, whereby the vortex decay is determined by the conductivity, which depends on the salt content of the body liquids. In the case of a sweating activity the body reduces its conductivity, so that the needed potential vortex energy will reach the cells.

If the body sometime isn't able to defend itself against interference signals, then malfunctions or pathological reactions are a possible result. During having a bath for instance a muscle cramp can occur, if the body doesn't defend itself fast enough or sufficiently against the high potential vortex activity in the water. Now vortices can be picked up in the nerves, which are of the same kind as the ones emitted by the brain, only that both muscles, biceps and triceps at the same time get the signal to contract. The result is a cramping of both muscles.

Thus the brain has developed intelligent strategies to protect itself of interspersed misinformations. It weighs the incoming signals and forgets again all unimportant ones more or less fast. We speak of the ability to learn and that means that signals rise in the valuation scale and with that are stored longer, the more frequent repeated our brain receives them. This strategy assumes that interference signals only occur sporadic, for which reason they are rated unimportant and fast are again forgotten.
A PC on the other hand doesn't have such a property. It notices everything indiscriminately and sometime will crash of overload, if not the user will constantly foster it and will administer the available memory. A PC is and stays stupid.

Concerning the stability against interference:

The **comparison** of	**man** and	**engineering**
in the	**brain**	**computer**
control technical interference signals:	light phenomena	miscontrol, program fault
precautions:	active, i.e. weighing of the Info by learning (repetition)	passive, i.e. shielding. (no evaluation of the input values)
unimportant (interference signal)	is forgotten	is stored
danger exists for signals	recurring interference patterns (see mobile telephony)	interference of all kinds (s.EMC-standardization)
remedy:	self-cure	restart (reset)

Concerning set of difficulties of wear and tear:

The **comparison** of	**man** and	**engineering**
repair	self-repair	in the workshop
by:	cell division permanently	exchange parts at maintenance resp. in the case of damage
required building materials:	nourishment	material / oil
waste:	compost	rubbish

Fig. 25.6: Strategies against interference signals, for damages linked with operation and for wear and tear.

25.6 Stability against interference and repair mechanisms

The interference signals present in our natural environment as a rule are distributed stochastic, but not so artificial interference signals like for instance transmitters emit. If for instance in the case of mobile telephony there occur time and again identical signal patterns and if a person perceives these, then because of the continual repetitions a high importance is pretended and precious storage space in the brain is allocated. This to a special extent applies for the permanent stand-by signals, which are emitted by mobiles and cordless phones even then, if we don't phone at all. Such misdevelopments thereby would be technically avoidable just like that!
If still no gauges are available and as a result there exist neither guidelines nor limits for the radiation exposure of scalar waves, then such devices must be developed and built. For the requested electromagnetic environmental compatibility not engineering, but man should be in the centre of attention!

Let us throw a short glance at the set of difficulties of wear and tear. Most technical devices find the way into the workshop only, if they already are defect. Some aren't repaired anymore in principle and immediately sent to the rubbish, because they are worn-out and a repair isn't worth the effort anymore one says, whereas other, mostly expensive systems are being serviced by exchanging all wearing parts.

Nature has brought to perfection the last principle. It allows the body a permanent maintenance; by permanently producing new cells and replacing consumed ones. It with that obtains a considerably longer operating time and even is capable to heal wounds. Just imagine dents in our cars would disappear from alone after a few weeks and the bodywork would look like new. Such an optimal maintenance is costly and it has its price. By means of the cell division the building plan for the spare parts is copied. The task on the other hand is transmitted to the new cells „by radio" by means of waveguide channels, as proves the matching structure of scalar wave and waveguide (chapter 21.12 and fig. 25.7). The cells hence have a kind of „decentral intelligence", which technical matter lacks completely. A comparison with engineering nevertheless makes sense, because wear and tear occurs for all systems in continuous operation. Thus strategies must be developed to provide the necessary material for operation, building-material and exchange parts.

By sizing of the hyperboloid structures of the matrix channels it should be possible to determine the wavelength of the scalar waves to enter them in the frequency diagram (23.1).

Tunnel structure of the basic substance according to Prof. Heine<i>:


H$_2$O
H$_2$O
λ/4 = ϕ =
5 - 80 nm
CH$_2$O
CH$_2$OH
HO
OH

Fig. 25.7: ___ Information channels in the intercellular matrix.<i>

<i>: Hartmut, Heine: Lehrbuch der biologischen Medizin. Grundregulation und Extrazellulare Matrix, 2. Aufl. 1997, Hippokrates Verlag Stuttgart, S. 56

25.7 The microwave window

There still is lacking information about the frequency or the velocity of propagation to be able to specify and enter in figure 23.1 the cell information. Let's take to hand the book about "Biostrahlen"[i]. In there is explained how for individual cells the emission of electromagnetic signals already could be measured, which are interpreted as circularly polarized waves (fig. 21.10 A). It is said that thereby their polarization plane is rotating with the speed of light, whereas the wave itself is propagating in longitudinal way relatively slow and according to the authors with the speed of sound.
The occupation with the potential vortex theory in the explanation lets immediately recognize the vortex, for this is rotating with the speed of light in circles as rolled up wave (fig. 21.10). If it is bound to the surrounding matter with closed vortex centre, then it can be expected that the propagation actually takes place with the speed of body sound.
It could concern the same signals, which Prof. A. Popp calls biophotons and detects measuring technically in living organisms[ii]. He however considers the phenomenon for the same wavelength with the speed of light and lands at light frequencies, even then if nothing is glowing visibly! The question is asked: Does it concern the frequency of the light or only the corresponding wavelength or actually both, thus light, as is expressed in the name biophotons?
The photomultipliers, which Prof. Popp uses as „light amplifier", however can only be tuned to certain wavelengths and not to frequencies. Even if the detected biophotons have the wavelength of the light, then nevertheless nothing will glow if the velocity of propagation and as a result also the frequency differs from that of the light for several powers of ten. In the case of the immense number of cells also the number of photons should correspondingly sum up and the body as a whole should start to glow, which is not the case.

The waveguides in the intercellular matrix serving the cell communication, which Prof. H. Heine observes microscopically, have wavelengths between 20 and 300 nanometer, which corresponds to the range of the ultraviolet radiation[iii]. But if the propagation is slower than the light for 6 powers of ten, then also the frequency will only amount to one millionth and be situated into the range of the microwaves. Here a biological window seems to be present, to which we should turn our attention for reasons of the electromagnetic environmental compatibility!

The thermal radiation, which reaches the earth from the sun and the planets, lies in the microwave range between 2 and 20 cm. If the sun does well to us, if we need the radiation, then it could be because of the identical frequency. But that also means that the sun and the planets are capable to have an effect on the cell communication, that they for instance could function as clock for the heart.

<i>: H. Mayer, G. Winklbaur: Biostrahlen, Verlag ORAC, Wien 1989, 5. Auflage S. 97: Messung von der DNS eines Gurkenkeims abstrahlenden Photonen.

<ii>: A. Popp: Neue Horizonte in der Medizin, 2.Aufl. Haug Verlag Heidelberg 1987



Fig. 25.8: Frequency diagram with entries concerning biologically relevant areas (Tinnitus, nerve conduction, etc.).

25.8 Discussion concerning scalar wave medicine

In the sensitive range of the supposed microwaves window however are also situated the mobile phones and their harmonic waves, which occupy a broad spectrum in particular for pulsed operation in digital nets. The D-net for instance has a wavelength of 32 cm, the E-net lies at half that wavelength. But to which frequency does this correspond at the speed of sound? Now, the frequency is 6 powers of ten smaller and now lies at 1 kHz resp. 2 kHz. To that are added the numerous harmonic waves, which form a noise signal and lie above that. With that these signals are situated completely in the audible range, there where our ears are most sensitive!

This cause we probably owe the disease of modern civilization „Tinnitus". Every charged particle will follow this electromagnetic oscillation and produce corresponding sound oscillations, which can hear not „sick ", but completely on the contrary „healthy" people, who as a result possibly get sick. The objection, in this range also cosmic radiation for instance from the planets is present, is legitimate. It however should be considered that planets also are going away from the earth again and in addition is present a fluctuation according to the time of day due to the rotation of the earth, while the mobile telephone masts in our vicinity radiate in continuous operation.

In this window in addition the clocking of the brain currents takes place at 10 Hz. I would recommend blocking the acoustic relevant range between 2 cm (16 kHz) and 3 m wavelength (100 Hz) for all technical use. Every operation of a transmitter in a biological window harms all people and cannot be answered for by any institution.

It further should be considered that the biological window of the plants and animals as a rule correspond to that of man, but sometimes are shifted significantly upward or downward in wavelength. We are not entitled to judge nature. The immune system of the animals now obviously has reached the breaking point and also that of man doesn't seem to be that anymore, which it originally was.

We must proceed from the assumption that many diseases on the one hand and therapy methods on the other hand partly direct and partly indirect have to do something with scalar waves. (E.g. the occurring of cancer<4i>).

<i>: H. Mayer, G. Winklbaur: Biostrahlen, Verlag ORAC, Wien 1989, 5. Auflage, S. 97: Messung von der DNS eines Gurkenkeims abstrahlenden Photonen.

<ii>: A. Popp: Neue Horizonte in der Medizin, 2.Aufl. Haug Verlag Heidelberg 1987

<iii>: Hartmut. Heine: Lehrbuch der biologischen Medizin. Grundregulation und Extrazellulare Matrix, 2. Aufl. 1997, Hippokrates Verlag Stuttgart, S. 56

<4i>: K. Meyl: Skalarwellenstrahlung. Welche Bedeutung haben Skalarwellen fur die Medizin? GNP-Vortrag am 29.04.2001, Rhein-Main-Halle Wiesbaden, see: Co'med Fachzeitschrift fur Komplementarmedizin, 6/2001, pp.55-60.

I. According to the Maxwell theory:

1. Faraday's law of induction:

$$\boxed{\mathrm{rot}\,\mathbf{E} = -\,\delta\mathbf{B}/\delta t} \quad (26.1)$$

with $\quad E = E(r,t)$

and $\quad H = H(r,t) \quad :$ $\qquad \mathbf{B} = \mu \cdot \mathbf{H} \qquad (26.2)$

$$\boxed{-\,\mathrm{rot}\,\mathrm{rot}\,\mathbf{E} = \mu \cdot \delta(\mathrm{rot}\,\mathbf{H})/\delta t} \quad (26.3)$$

2. Ampere's law:

$$\boxed{\mathrm{rot}\,\mathbf{H} = \mathbf{j} + \delta\mathbf{D}/\delta t} \quad (26.4)$$

with:

Ohm's law: $\qquad \mathbf{j} = \sigma \cdot \mathbf{E} \qquad (26.5)$

dielectric displacement: $\qquad \mathbf{D} = \varepsilon \cdot \mathbf{E} \qquad (26.6)$

relaxation time: $\qquad \tau = \varepsilon/\sigma \qquad (26.7)$

$$\boxed{\mathrm{rot}\,\mathbf{H} = \varepsilon \cdot (\mathbf{E}/\tau + \delta\mathbf{E}/\delta t)} \quad (26.8)$$

3. Inserting equation 26.8 into 26.3 yields:

$$-\,\mathrm{rot}\,\mathrm{rot}\,\mathbf{E} = \mu \cdot \varepsilon \cdot (1/\tau \cdot \delta\mathbf{E}/\delta t + \delta^2\mathbf{E}/\delta t^2) \quad (26.9)$$

with the abbreviation: $\qquad \mu \cdot \varepsilon = 1/c^2 \qquad (26.10)$

4. Field equation of a damped transverse wave:

$$\boxed{\underbrace{-\,\mathrm{rot}\,\mathrm{rot}\,\mathbf{E} \cdot c^2}_{\text{transverse}} = \underbrace{\delta^2\mathbf{E}/\delta t^2}_{\text{wave}} + \underbrace{(1/\tau) \cdot \delta\mathbf{E}/\delta t}_{\text{vortex damping}}} \quad (26.11)$$

Fig. 26.1: ____ Derivation of the wave damping by means of the formation of vortices!<i>

<i>: see also EMC, part 1, chapter 5.3, 2.borderline case.

26. Recapitulation from the viewpoint of textbook physics

Now that we in the meantime have accumulated innumerable mosaic parts as inspiring contributions to the discussion for the information technical seminar, it is time to sort the ideas and to put the parts together to an overall picture.
Sceptics and orthodox scientists can only be convinced, if we start from textbook physics and completely do without postulates. Those demands will be fulfilled!

26.1 Common misinterpretation of the antenna losses

The mathematical description of physical relations leads to the well-known laws, which shouldn't be doubted anymore as soon as they are accepted to be correct. But what about the interpretation? Although a law dictates the interpretation and there is no choice, because laws must be adhered to, yet textbooks from time to time violate the mathematically dictated interpretation, a circumstance, which can't be accepted. I would like to illustrate this with an example.

Let us assume that the measured degree of effectiveness of a transmitting antenna amounts to 80 percent. There exist better antennas, but also distinctly worse antennas, but I'm not aiming at a certain construction. The statement simply says, that 80% of the fed in HF-power is transformed into Hertzian waves. Thus there arises a loss of power of 20 percent, and the question follows: of what do those 20% consist?

The answer, which is usual among experts and is supported by the textbooks, reads: the antenna wire gets hot and also the air around the antenna is heated by dielectric losses. In short, heat is formed.
But I have to point out and will furnish proof that this interpretation is predominantly wrong! It in any case isn't in accord with the laws of Maxwell. Who namely obeys the laws, comes to an entirely different result!

A short derivation brings it to light (fig. 26.1).
We start with the formulation of Faraday's law of induction according to the textbooks (26.1), apply the curl-operation to both sides of the equation (26.3) and insert in the place of rot H Ampere's law (26.4-26.8). The generally known result describes a damped electromagnetic wave (26.11)[i].
It on the one hand is a transverse wave, which represents 80% of the antenna power for our example. On the other hand a damping term can be found in the equation, which obviously corresponds to the sought-for 20%. With that the answer would have been found. We realize that because of a damping of the wave 20% antenna losses arise. These losses can't concern heat at all, since the damping term in the equation has got nothing in common with thermodynamics. In the equation doesn't stand anything about heat! Such a mistake!


E-field
H-field
E-field
H-Feld
-
+
+
-
0°
90°
180°
270°

Fig. 21.8 A: The fields of the oscillating dipole antenna.<i>



Fig. 21.9 A: The coming off of the electric field lines from the dipole.

<i>: Repetition belonging to chapter 21

26.2 Wave damping by field vortices

- Mathematically seen the damping term describes vortices of the electromagnetic field. This term for instance forms the basis of all eddy current calculations<ii>.
- Physically seen some waves - in our example it is 20 percent - roll up to field vortices, with which the wave damping and the antenna losses would be explained.

In the course of time a substantial part of the generated vortices will fall apart. These thereby will produce eddy losses in form of heat. Thus eventually still heat is produced - agreed. The criticism of the textbooks consists of the circumstance that we by no means can proceed from the assumption that all vortices spontaneously fall apart and a total conversion into heat will take place. The process in addition takes place with a temporal delay. The time constant x gives information in this respect. Field energy is buffered in the vortex, where some vortices live very long and it can't be ruled out that a few even exist as long as you like.

To find out more about these field vortices and their behaviour, one has to get deep into vortex physics. Unfortunately nothing can be found about vortex physics in the textbooks. The mistake is systematic. The following short compendium should help close the gap:

- Mathematically seen a closed-loop electromagnetic field vortex will show as a scalar. Such field vortices, which are mediated by a scalar field, are propagating exactly as charged particles in longitudinal manner as a scalar wave.
- Physically seen a closed-loop field vortex has got particle nature. If one particle kicks off the next one then an impulse is mediated, then a shock wave is occurring, a longitudinal undulation of the particles.

From the vortex physical view the interpretation of the antenna example now sounds entirely different:
The charge carriers in an antenna wire oscillating with high-frequency form a longitudinal shock wave. Between current and tension voltage usually a phase shift of 90° is present. The fields produced by these charge carriers form a scalar wave field in the immediate vicinity of the antenna, the so-called near-field zone, which likewise contains longitudinal field components and shows a phase shift of 90° between electric and magnetic field (fig. 21.8 A). As in textbooks is clarified by field lines, the generated fields actually form vortices, where one structure kicks off the next one (fig. 21.9 A).

The vortices in the near-field zone of an antenna consist of standing waves, which obviously are transforming with increasing distance. In our example 80% of these are unrolling and turn into transverse waves, whereby the characteristic phase angle between E- and H-field at that occasion becomes zero.
Let's turn again to those 20 percent loss.

<ii>: s.a.: K. Meyl: Wirbelstrome, Diss. Uni. Stuttgart 1984, INDEL Verlagsabt.

I. According to the Maxwell theory:

The consistent application of textbook physics

- Longitudinal waves run in the direction of a field pointer.
- The field pointer oscillates, the vector of velocity oscillates along!
- At relativistic velocities field vortices are subject to the Lorentz contraction.
- The faster the oscillating vortex is on its way, the smaller it gets.
- The vortex permanently changes its diameter (see fig. 21.10 B).
- With the diameter the wavelength decreases (see fig. 22.4).
- The swirl velocity is constant (= speed of light c).
- The eigenfrequency of the vortex oscillates with opposite phase to the wavelength.
- The vortex acts as a frequency converter!
- The measurable mixture of frequencies is called noise.

leads to the statement:

- The antenna noise corresponds to the antenna losses!

II. Mathematical description of a wave by the inhomogeneous Laplace equation:

$$\underbrace{\Delta \mathbf{E} \cdot c^2}_{\text{Laplace operator}} = \underbrace{- \text{rot rot } \mathbf{E} \cdot c^2}_{\text{transverse (radio wave)}} + \underbrace{\text{grad div } \mathbf{E} \cdot c^2}_{\text{longitudinal (scalar wave)}} = \underbrace{\delta^2 \mathbf{E}/\delta t^2}_{\text{wave}} \qquad (26.12)$$

Divergence E is a scalar!
The corresponding term founds a scalar wave.

Fig. 26.3: Mathematical description of a wave according to Laplace.

26.3 Laplace versus Maxwell

Longitudinal waves as is well-known don't know a fixed velocity of propagation at all. Since they run in the direction of an oscillating field pointer also the vector of velocity will oscillate. For so-called relativistic velocities in the range of the speed of light c the field vortices are subject to the Lorentz contraction. That means, the faster the oscillating vortex is on its way, the smaller it gets. The vortex, as a mediator of a scalar wave carrying impulse, permanently changes its diameter.
Since, in the case of the vortices, it should concern rolled up waves, the vortex velocity will continue to be c, with which the wave now runs around the vortex centre in a circle. From that follows that if the diameter gets smaller, the wavelength of the vortex as well will decrease, whereas the eigenfrequency of the vortex accordingly increases. If the next moment the vortex oscillates back, the frequency again decreases. The vortex acts as a frequency converter! The mixture of high-frequency signals distributed over a broad frequency band formed in this way, is called noise. A noise signal indeed is measured from the outside with the help of broadband receivers.. We also speak of antenna noise and with this knowledge we can further specify the 20% antenna losses: The antenna produces 20 % noise, which can be put equal to the generated vortices because of the wave damping.

At this point the Maxwell theory doesn't leave us room for interpretation at all. If in the textbooks the impression is aroused, as if the noise were an independent discipline, than that is not true at all. How much the noise is connected with the electromagnetic waves, proves a short look at the wave equation.

The wave equation found in most textbooks has the form of an inhomogeneous Laplace equation. The famous French mathematician Laplace considerably earlier than Maxwell did find a comprehensive formulation of waves and formulated it mathematically (eq. 26.12), which until today is still accepted as valid.

On the one side of the wave equation the Laplace operator stands, which describes the spatial field distribution, and which according to the rules of vector analysis can be decomposed into two parts. On the other side the description of the time dependency of the wave can be found as an inhomogeneous term.

If the wave equation according to Laplace (26.12) is compared to the one, which the Maxwell equations have brought us (26.11), then two differences clearly come forward:

1. In the Laplace equation the damping term is missing. It doesn't describe the formation of vortices, and that means vortices do not exist at all, or present vortices have been there from the beginning.
2. With divergence E a scalar factor appears in the wave equation, which founds a scalar wave.

At this point at once hot tempered discussions concerning the question of the existence of scalar waves blaze up. But this question has already been answered clearly with the vortex consideration. Since an accepted description of longitudinal and scalar waves exists with the plasma wave and the plasma wave can be derived directly without postulate from the term of the wave equation (chapter 21.4/21.5), which founds scalar waves, there are further arguments present for their existence.

I. According to Maxwell:

$$\underbrace{-\text{ rot rot }\mathbf{E}\cdot c^2}_{\text{transverse}} = \underbrace{\delta^2\mathbf{E}/\delta t^2}_{\text{wave}} + \underbrace{(1/\tau)\cdot\delta\mathbf{E}/\delta t}_{\text{vortex damping}} \qquad (26.11)$$

Description of electromagnetic waves with vortex damping
Example: sunlight and the damping in the ionosphere (bleu sky).

II. According to Laplace:

$$\underbrace{\Delta\mathbf{E}\cdot c^2}_{\substack{\text{Laplace}\\ \text{operator}}} = \underbrace{-\text{ rot rot }\mathbf{E}\cdot c^2}_{\substack{\text{transverse}\\ \text{(Hertz)}}} + \underbrace{\text{grad div }\mathbf{E}\cdot c^2}_{\substack{\text{longitudinal}\\ \text{(Tesla)}}} = \underbrace{\delta^2\mathbf{E}/\delta t^2}_{\text{wave}} \qquad (26.12)$$

Description of transverse electromagnetic waves (Hertzian waves) and longitudinal scalar waves (Tesla radiation).
1st example: propagation of light as a wave or as a particle.
2nd example: useful signal or noise signal of an antenna.

III. Mathematically seen (comparison of coefficients):

$$\underbrace{(1/\tau)\cdot\delta\mathbf{E}/\delta t}_{\text{vortex}} + \underbrace{\text{grad div }\mathbf{E}\cdot c^2}_{\text{scalar}} = 0 \qquad (26.13)$$

IV. Physically seen
(from the comparison of equation 26.12 with equation 26.11):

Vortices propagate longitudinally as a scalar wave!

Fig. 26.2: _____ Comparison of the two wave descriptions.

26.4 Error term in the wave equation

From the comparison of coefficients of both wave descriptions follows even more:

- Mathematically seen the damping - resp. vortex term according to Maxwell can be put equal to the scalar wave term according to Laplace.
- Physically seen the generated field vortices form and found a scalar wave.

Here also doesn't exist any room for interpretation, as long as we work with the wave equation according to Laplace and at the same time adhere to the Maxwell theory. If however the scalar wave part is put equal to zero, as is common practise in the textbooks, then as a consequence neither vortices nor noise may exist. But that contradicts all measuring technical experience! Since every antenna produces more or less noise, the textbooks obviously only show half the truth. Science however gropes for the whole truth and that should be fathomed.

If in the case of the antenna example the vortex part amounts to 20%, then that's tantamount to 20% scalar wave part, resp. 20% noise. The scalar wave part constitutes with regard to the Hertzian useful wave something like an error term in the wave equation. The part definitely is too big, as that it might be put equal to zero. Even so all error consideration in the textbooks is missing, if the scalar wave term is assumed to be zero. That violates all rules of physics and of taught scientific methodism.

In practice this shows by a useful signal going under in the noise and reception not being possible anymore as soon as the scalar wave part gets out of control. Even in this case, for which the degree of effectiveness tends towards zero, it still is common practise to put the error term, which is dominating everything, equal to zero. But who in this point follows the textbooks, disregards with that the wave equation and doing so by no means can refer to the circumstance that all colleagues make the same mistake.

The building of physics behaves like a house of cards, where the cards mutually support each other. Perhaps that is the deeper reason why those, who have discovered a marked card, don't pull it out immediately. In addition they are hindered by the self appointed guardians of the ,,pure doctrine", since everyone knows what happens with the house of cards if the marked card is pulled out. Only, do we want to and can we live with that in the long run? Is it a solution of the problem, if the so-called experts among the physicists and technicians look away and don't deal with the foundation of their branch anymore? If universities crash their basis education into the wall and choke off every contradiction?

Please allow me to pull out the marked card now and place it on the table!

It concerns the question: what is the nature of the field vortices, which form a scalar wave in space. Eddy currents in the iron parts of the antenna are explained with the field equations, but not the noise, which is measured especially in the air. If an antenna on the one hand produces field vortices and as a consequence eddy losses and on the other hand dielectric losses, then we can assume that besides the eddy currents in the conductor also vortices in the dielectric must exist. Let's search for them!

Interim result (comparison of arguments):

The Maxwell equations on the one hand dictate that as the reason for a wave damping only field vortices should be considered.	On the other hand the same laws merely describe eddy currents, which can only occur in the electrically conducting parts of the antenna.
On the one hand the field vortex interpretation makes it possible to explain the noise of an antenna perfectly.	On the other hand does the noise appear in the neighbourhood of the antenna, thus in the air and not in the iron parts!
The mathematical formulation reveals, how wave and vortex, resp. noise, co-operate and how one should imagine the conversion of one form into the other form.	In field physics on the other hand is missing a useful description of electric field vortices in a dielectric, which could found the noise signal.

Table 26.5: Arguments pro and contra.

26. 5 Interim result

It shouldn't be a disadvantage, to interprete physical laws more consistently than usual, even if in the present case orthodox science through that at first should fall into a deep crisis. If the way is worthwhile, only will show at the end.
Let us try to work out the contradictions in form of a comparison of arguments:

- The Maxwell equations on the one hand dictate that as the reason for a wave damping only field vortices should be considered.
    - On the other hand the same laws merely describe eddy currents, which can only occur in the electrically conducting parts of the antenna. .
- On the one hand the field vortex interpretation makes it possible to explain the noise of an antenna perfectly. .
    - On the other hand does the noise appear in the neighbourhood of the antenna, thus in the air and not in the iron parts!
- The mathematical formulation reveals, how wave and vortex, resp. noise, co-operate and how one should imagine the conversion of one form into the other form.
    - In field physics on the other hand is missing a useful description of electric field vortices in a dielectric, which could found the noise signal.

The most obvious among all conceivable solutions is the one that we have to assume the existence of dielectric field vortices, so-called potential vortices. We are challenged to search for a corresponding description. If the quest should be successful, then the contradictions would be overcome. In addition there is the promise of a whole number of simplifying explanations of various phenomena in the dielectric (see fig. 26.5 and fig. 26.7).

The phenomenon of noise becomes an aspect of wave physics, which is more than merely a field disturbance, which makes the reception of the useful wave more difficult. If the scalar wave nature is realized, then applications can be imagined, in which the noise is used as useful signal. In the way that the scalar part in the wave equation doesn't have to be put to zero anymore to obtain freedom of contradiction, even optimizations of antennas or of capacitors are possible with regard to the dielectric losses by means of the calculation of the scalar part.

New in any case is the idea that the dielectric losses of a capacitor are eddy losses and not a defect in material of the insulating material. With that the capacitor losses correspond to a generated noise power. We also can say, every capacitor more or less produces noise! The electric field lines point from one capacitor plate to the other plate. If one plate radiates as a transmitter and the other plate functions as a receiver, then the field propagation takes place in the direction of the electric field pointer and that again is the condition for a longitudinal wave. Here the circle closes in the conclusion, the capacitor field mediates dielectric field vortices, which following the field lines found a scalar wave because of their scalar nature. The heating of the capacitor results from the decay of vortices.

Potential vortices explain div. phenomena in the dielectric:



1. The **noise** no longer is factored out of the field theory.
2. The scalar (noise) part in the wave equation no longer has to be put to zero ($\text{div}\,\mathbf{E} \neq 0$).
3. The wave descriptions according to Maxwell (26.11) and according to Laplace (26.12) are consistent and free of contradiction.
4. The dielectric losses of an antenna can be found physically and even can be calculated with the wave equation.
5. **Also the dielectric losses** of a capacitor are **eddy losses** (and not a defect in material of the insulating material).
6. The **capacitor losses** correspond to a generated **noise power**.
7. The **dielectric constant** ε doesn't have to be written down complex as until now to give reasons for the occurring losses, and so the inner contradiction is solved, which is hidden in a complex constant. One should only remember the definition of the speed of light $c = 1/\sqrt{\varepsilon\mu}$ (eq. 26.10) and the insurmountable problems in the textbooks, which are brought by a complex ε!
8. The field lines point from one capacitor plate to the other plate. If one plate radiates as a transmitter and the other plate functions as a receiver, then the field propagation takes place in the direction of the electric field pointer and that again is the condition for a **longitudinal wave**.
9. The capacitor field mediates dielectric field vortices, which following the field lines found a **scalar wave** because of their scalar nature.
10. As an inhabitant of a dielectric between two capacitor plates (earth and ionosphere) also **man** is a product of these field vortices.
11. Scalar waves can be modulated moredimensionally and be used as **carrier of information**, as Prof. Sheldrake has proven with his proof of the existence of morphogenetic fields[i].

Fig. 26.6: Advantages of a field description extended with potential vortices.

<i>: Rupert Sheldrake: Seven Experiments That Could Change the World. Riverhead Books, 1995

26.6 Failure of the Maxwell theory

If the capacitor losses or the antenna noise should concern dielectric losses in the sense of vortex decay of potential vortices, which don't occur in the Maxwell theory at all, then we are confronted with a massive contradiction:

- For the description of the losses the Maxwell; theory on the one hand only offers field vortices and those only in the conductive medium.
  - On the other hand do the dielectric losses occut in the nonconductor and in the air.

- In conductive materials vortex fields occur, in the insulator however the fields are irrotational. That isn't possible, since at the transition from the conductor to the insulator the laws of refraction are valid and these require continuity! Hence a failure of the Maxwell theory (Fig. 26.7) will occur in the dielectric.
  - As a consequence the existence of vortex fields in the dielectric, so-called potential vortices, should be required!

In electrodynamics as a help the approach of a vector potential A is used, which leads to a complex formulation of the dielectric constant ε and in this way makes it possible, to mathematically describe the dielectric losses of a capacitor by means of the load angle, which stretches in the complex plane. But which physical value does this approach have? How can now the inner contradiction be explained, which is hidden in a complex constant of material? One should only remember the definition of the speed of light $c = 1/\sqrt{\varepsilon\mu}$ (eq. 26.10) and its dependency of ε. For a complex ε here are resulting insurmountable problems in the textbooks.
From the viewpoint of mathematics the introduction of the vector potential at first may represent a help. The before mentioned contradictions however fast raise doubts to the model concept, which from a physical viewpoint eventually will lead to errors, if the speed of light isn't constant anymore and even should be complex.

These considerations should be sufficient as a motive to require potential vortices, even if for their description the field theory according to the textbooks has to be revised. As a supplement there is pointed to the following points:

- As an inhabitant of a dielectric between two capacitor plates also man is a product of these field vortices.

- Scalar waves can be modulated moredimensionally and be used as carrier of information, as Prof. Sheldrake has proven with his proof of morphogenetic fields<i>.

The dielectric vortices moreover provide an explanation for natural events. They form the key to numerous disciplines of science, from physics over biology up to medicine.

<i>: Rupert Sheldrake: Seven Experiments That Could Change the World. Riverhead Books, 1995



Problem of continuity in the case of the coming off of vortices

Example: hightension cable

In ***conductive materials vortex fields*** *occur in the* ***insulator*** *however the fields are* ***irrotational****.*
That isn't possible, since at the transition from the conductor to the insulator the ***laws of refraction*** *are valid and these require* ***continuity!***
Hence a ***failure of the Maxwell theory*** *will occur in the dielectric!*

Conclusion: ♦ According to the Maxwell theory there exist no vortices of the electric field *(no potential vortices)* and therefore *no scalar waves.*

♦ Without theory it is impossible to design a usable *scalar wave gauge* and to furnish *evidence*. ⇒ **Classic closed loop conclusion:**

♦ The missing of scientific evidence again „proves“ the assumption of the irrotationality and „confirms“ the correctness of the Maxwell theory.

♦ Hence it cannot be, what shouldn't be!

Fie. 26.7: Concerning the failure of the Maxwell theory

26.7. Concerning the evidence situation

In the question, if a physical phenomenon should be acknowledged as such, experimental, mathematical and physical evidence should be shown. In the case of the potential vortices, the vortices of the electric field and their propagation as a scalar wave, the historical experiments of Nikola Tesla<i> and the modern clone of these can be judged as experimental evidence<ii>.

With the well-known wave equation a mathematical description for this phenomenon has been specified and discussed<iii>. It will be shown that both transverse and longitudinal wave parts are contained alongside in the wave equation, i.e. both radio waves according to Hertz and scalar waves according to Tesla. Doing so the mathematically determined scalar wave properties are identical with the experimental results!
The wave equation is an inhomogeneous Laplace equation and the first and oldest description of scalar waves. It thereby is unimportant, if the famous mathematician Laplace himself already may have realized and discussed this circumstance or not. The description fits perfectly and that is what counts!

At this point the third point should be put on the agenda, the physical evidence. This is connected very closely with the question for a suitable field theory and that again is basing on a corresponding approach.

<i>: N. Tesla: Apparatus for Transmission of Electrical Energy, US-Patent-No.: 649,621, New York 1900, Dr. Nikola Tesla: Complete Patents pp318-321.

<ii>: Johannes von Buttlar im Gesprach mit Prof. Dr. Konstantin Meyl: Neutrinopower, Argo-Verlag, Marktoberdorf, l.Aufl. 2000.

<iii>: K. Meyl: Scalar Waves: Theory and Experiments, Journal of Scientific Exploration, Vol. 15, No. 2, pp. 199-205, 2001

(* * * Task Schedule * * *)

1. Neutrino radiation => energy radiation!
   (acc. to Pauli: ν cares for missing energy in the case of the ß-decay)
2. High neutrino density => high energy density!
3. Neutrino = particle without charge or mass (mean), but because of oscillations: effective value of charge and mass ≠ zero!
4. Interaction only in the case of resonance (e.g. weak interaction)!
   (same frequency, 180° phase shift)
5. Neutrino radiation is an energy source which can be used (not a question of physics, only a question of technology!)
6. Particle radiation (neutrino) => shock wave (like sound)
   => longitudinal wave
   => scalar wave (mathem.)
7. Interaction/resonance of the v = scalar wave problem
8. Scalar waves are a problem of the field theory!
9. Maxwell theory neglects scalar waves.

- Search for a new approach (chap. 27.8)
- Derivation of the Maxwell equations as a
- Derivation of scalar waves (chap. 27.13)
- Derivation of the gravitation and more

Table 27.1: Task schedule belonging to chapter 27

27. Faraday versus Maxwell

Numerous phenomena of the electromagnetic field are described sufficiently accurate by the Maxwell equations, so that these as a rule are regarded as a universal field description. But if one looks more exact it turns out to be purely an approximation, which in addition leads to far reaching physical and technological consequences. We must ask ourselves:

- What is the Maxwell approximation?
- How could a new and extended approach look like?
  - Faraday instead of Maxwell, which is the more general law of induction?
- Can the Maxwell equations be derived as a special case?
- Can also scalar waves be derived from the new approach?
- Can the gravitation as well be derived and a lot else more?

On the one hand it concerns the big search for a unified physical theory and on the other hand the chances of new technologies, which are connected with an extended field theory. As a necessary consequence of the derivation, which roots strictly in textbook physics and manages without postulate, scalar waves occur, which could be used manifold. In information technology they are suited as a carrier wave, which can be modulated moredimensionally, and in power engineering the spectrum stretches from the wireless transmission up to the collection of energy out of the field.

27.1 Energy out of the field

Neutrinos for instance are such field configurations, which move through space as a scalar wave. They were introduced by Pauli as massless but energy carrying particles to be able to fulfil the balance sheet of energy for the beta decay. Nothing would be more obvious than to technically use the neutrino radiation as an energy source.

But for a technical exploitation a useful model description of the particles and their interaction is imperative. For the sake of simplicity we imagine the neutrino to be an oscillating particle, which permanently oscillates back and forth between the state of an electron and that of a positron. With that the polarity changes from positive to negative and back again and the charge averaged over time is zero. Because of the change from a state of matter to the state of an anti-particle also next to no mass can be measured anymore.

A technical oscillator operated in resonance, which oscillates with the same frequency but opposite charge, will interact with the particle and build up an oscillating electromagnetic interaction, with which we already are familiar as the weak interaction in the proximity of a neutrino.

Tubular vortices

- Examples: drain vortex (bathtub vortex)
  whirlwind and waterspout, tornado (image).



Inside: expanding vortex
Outside: contracting anti-vortex
Condition for coming off: equally powerful vortices
Criterion: viscosity
Result: tubular structure

Fig. 27.2: ____Vortex and anti-vortex - a physical basic principle

<i>: Lugt: Wirbelstromung in Natur und Technik, G. Braun Verlag Karlsruhe 1979, Bild „Tornado" von Tafel 21, Seite 356

The propagation of particle radiation as a longitudinal shock wave however can't be described with the normally used field theory and the Maxwell equations, so that the field theory at this point must be reworked. Connected with this is the question of what is oscillating here, a question, which often is answered with an aether of whatever nature. I speak of field vortices and call the aether a property of the field. With that the set of difficulties is shifted into the domain of vortex physics.

27.2 Vortex and anti-vortex

In the eye of a tornado the same calm prevails as at great distance, because here a vortex and its anti-vortex work against each other. In the inside the expanding vortex is located and on the outside the contracting anti-vortex. One vortex is the condition for the existence of the other one and vice versa. Already Leonardo da Vinci knew both vortices and has described the dual manifestations (chapter 3.4).

In the case of flow vortices the viscosity determines the diameter of the vortex tube where the coming off will occur. If for instance a tornado soaks itself with water above the open ocean, then the contracting potential vortex is predominant and the energy density increases threateningly. If it however runs overland and rains out, it again becomes bigger and less dangerous.

The conditions for the bathtub vortex are similar. Here the expanding vortex consists of air, the contracting vortex however of water. In flow dynamics the relations are understood. They mostly can be seen well and observed without further aids.

In electrical engineering it's different: here field vortices remain invisible and not understood. Only so the Maxwell theory could find acceptance, although it only describes mathematically the expanding eddy current and ignores its anti-vortex. I call the contracting anti-vortex potential vortex" and point to the circumstance, that every eddy current entails the anti-vortex as a physical necessity.
Because the size of the forming structures is determined by the electric conductivity, in conducting materials the vortex rings, being composed of both vortices, are huge, whereas they can contract down to atomic dimensions in nonconductors. Only in semiconducting and resistive materials the structures occasionally can be observed directly (fig. 4.8).

Spherical vortices

Examples:	expanding vortex	contracting vortex
• quantum physics	collision processes (several quarks)	gluons (postulate!)
• nuclear physics	repulsion of like	strong interaction (postulate!)
• atomic physics	centrifugal force of the enveloping electrons	electrical attraction Schrodinger equation
• astro-physics	centrifugal force (inertia)	gravitation (can not be derived?!)

Example: elementary particles as electromagnetic field vortices

Inside: expanding eddy current (skin effect)
Outside: contracting anti-vortex (potential vortex)
Condition for coming off: equally powerful vortices
Criterion: electric conductivity (determines diameter)
Result: spherical structure
(consequence of the pressure of the vacuum)

Fig. 27.3: Spherical structures as a result of contracting potential vortices.[i]

Demokrit (460-370 BC) equated the vortex concept with „law of nature“!
= the first attempt to formulate a unified physics.

---

[i]: see Part 1, chapter 4.3

27.3 Vortices in the microcosm and macrocosm

The approximation, which is hidden in the Maxwell equations, thus consists of neglecting the anti-vortex dual to the eddy current. It is possible that this approximation is allowed, as long as it only concerns processes inside conducting materials. If we however get to insulating materials the Maxwell approximation will lead to considerable errors and it won't be able to keep it anymore.

If we take as an example the lightning and ask how the lightning channel is formed: Which mechanism is behind it, if the electrically insulating air for a short time is becoming a conductor? From the viewpoint of vortex physics the answer is obvious: The potential vortex, which in the air is dominating, contracts very strong and doing so squezes all air charge carriers and air ions, which are responsible for the conductivity, together at a very small space to form a current channel.

The contracting potential vortex thus exerts a pressure and with that forms the vortex tube. Besides the cylindrical structure another structure can be expected. It is the sphere, which is the only form, which can withstand a powerful pressure if that acts equally from all directions of space. Only think of ball lightning. Actually the spherical structure is mostly found in microcosm till macrocosm. Let's consider some examples and thereby search for the expanding and contracting forces (fig. 27.2).

- In quantum physics one imagines the elementary particles to be consisting of quarks. Irrespective of the question, which physical reality should be attributed to this model concept, one thing remains puzzling: The quarks should run apart, or you should try to keep together three globules, which are moving violently and permanently hitting each other. For this reason glue particles were postulated, the so-called gluons, which now should take care for the reaction force, but this reaction force is nothing but a postulate!

- In nuclear physics it concerns the force, which holds together the atomic nucleus, which is composed of many nucleons, and gives it the well-known great stability, although here like charged particles are close together. Particles, which usually repel each other. Between the theoretical model and practical reality there is an enormous gap, which should be overcome by introducing of a new reaction force. But also the nuclear force, called strong interaction, is nothing but a postulate!

- In atomic physics the electric force of attraction between the positive nuclear charge and the negatively charged enveloping electrons counteracts the centrifugal force. In this case the anti-vortex takes care for a certain structure of the atomic hull, which obey the Schrodinger equation as eigenvalue solutions. But also this equation irrespective of its efficiency until today purely is a mathematical postulate, as long as its origin is not clear.

- In astrophysics centrifugal force (expansion) as a result of the inertia and gravitation (contraction) as a result of the attraction of masses are balanced. But the "gravitation" puts itself in the way of every attempt to formulate a unified field theory. Also this time it is the contracting vortex, of which is said it can't be derived nor integrated.



Michael Faraday,
the experimentor (1791-1867)

James Clerk Maxwell<i>,
the mathematician (1831-1879)



unipolar generator

e.g.: transformer

Fig. 27.4: ____The fathers of the law of induction

<i>: J.C. Maxwell: A treatise on Electricity and Magnetism, Dover Publications

It is remarkable how in the domain of the contracting vortex the postulates are accumulating. But this hasn't always been the case. In ancient Greece already 2400 years ago Demokrit has undertaken an attempt to formulate a unified physics. He traced all visible and observable structures in nature back to vortices, each time formed of vortex and anti-vortex. This phenomenon appeared him to be so fundamental, that he put the term "vortex" equal to the term for „law of nature". The term „atom" stems from Demokrit (460-370 BC).

Seen this way the physicists in ancient times already had been further than today's physics, which with the Maxwell approximation neglects the contracting vortex and with that excludes fundamental phenomena from the field description or is forced to replace them by model descriptions and numerous postulates.
What we need is a new field approach, which removes this flaw and in this point reaches over and above the Maxwell theory.

27.4 Faraday's law and Maxwell's formulation

In the choice of the approach the physicist is free, as long as the approach is reasonable and well founded. In the case of Maxwell's field equations two experimentally determined regularities served as basis: on the one hand Ampere's law and on the other hand the law of induction of Faraday. The mathematician Maxwell thereby gave the finishing touches for the formulations of both laws. He introduced the displacement current D and completed Ampere's law accordingly, and that without a chance of already at his time being able to measure and prove the measure. Only after his death this was possible experimentally, what afterwards makes clear the format of this man.
In the formulation of the law of induction Maxwell was completely free, because the discoverer Michael Faraday had done without specifications. As a man of practice and of experiment the mathematical notation was less important for Faraday. For him the attempts with which he could show his discovery of the induction to everybody, e.g. his unipolar generator, stood in the foreground.
His 40 years younger friend and professor of mathematics Maxwell however had something completely different in mind. He wanted to describe the light as an electromagnetic wave and doing so certainly the wave description of Laplace went through his mind, which needs a second time derivation of the field factor. Because Maxwell for this purpose needed two equations with each time a first derivation, he had to introduce the displacement current in Ampere's law and had to choose an appropriate notation for the formulation of the law of induction to get to the wave equation.
His light theory initially was very controversial. Maxwell faster found acknowledgement for bringing together the teachings of electricity and magnetism and the representation as something unified and belonging together[i] than for mathematically giving reasons for the principle discovered by Faraday.
Nevertheless the question should be asked, if Maxwell has found the suitable formulation, if he has understood 100 percent correct his friend Faraday and his discovery. If discovery (from 29.08.1831) and mathematical formulation (1862) stem from two different scientists, who in addition belong to different disciplines, misunderstandings are nothing unusual. It will be helpful to work out the differences.

Law of induction



unipolar generator	e.g.: transformer
discovery of Faraday	2nd Maxwell equation
$\boxed{\mathbf{E} = \mathbf{v} \times \mathbf{B}}$ (27.1)	$\boxed{\text{rot } \mathbf{E} = - d\mathbf{B}/dt}$ (27.1*)
unipolar induction	law of induction generally

Fig. 27.5: Two formulations for one law
As a mathematical relation between the vectors of the electric field strength **E** and the induction **B** (= magnetic flux density)

Consequences

(the physically mean of the „field concept“):

• The **Faraday approach** describes a field physical principle	• **Maxwell equations** describe the fields of charged particles
• field = experience: We experience the electric as a magnetic field and vice versa as a result of a relative velocity • Particles do not occur in the Faraday approach	• the electric (**E**-) field = static field of charges, • the magnetic (**H**-) field = field of moving charges. • The origin of the particles remains unsettled (postulate)
• Perfect duality between **E**- and **H**-field.	• No duality in the field description
• **v** leads to dual permutation of **E**- and **H**-field.	• Charge carriers=el. monopoles • No magnetic monopoles!

27.5 The discovery of Faraday

If one turns an axially polarized magnet or a copper disc situated in a magnetic field, then perpendicular to the direction of motion and perpendicular to the magnetic field pointer a pointer of the electric field will occur, which everywhere points axially to the outside. In the case of this by Faraday developed unipolar generator hence by means of a brush between the rotation axis and the circumference a tension voltage can be called off<i>. The mathematically correct relation E = v x B I call Faraday-law, even if it only appears in this form in the textbooks later in time<ii>. The formulation usually is attributed to the mathematician Hendrik Lorentz, since it appears in the Lorentz force in exactly this form. Much more important than the mathematical formalism however are the experimental results and the discovery by Michael Faraday, for which reason the law concerning unipolar induction is named after the discoverer.

Of course we must realize that the charge carriers at the time of the discovery hadn't been discovered yet and the field concept couldn't correspond to that of today. The field concept was an abstracter one, free of any quantization.

That of course also is valid for the field concept advocated by Maxwell, which we now contrast with the „Faraday-law" (fig. 27.4). The second Maxwell equation, the law of induction (27.1*), also is a mathematical description between the electric field strength E and the magnetic induction B. But this time the two aren't linked by a relative velocity v. In that place stands the time derivation of B, with which a change in flux is necessary for an electric field strength to occur. As a consequence the Maxwell equation doesn't provide a result in the static or quasi-stationary case, for which reason it in such cases is usual, to fall back upon the unipolar induction according to Faraday (e.g. in the case of the Hall-probe, the picture tube, etc.). The falling back should only remain restricted to such cases, so the normally used idea. But with which right the restriction of the Faraday-law to stationary processes is made?

The vectors E and B can be subject to both spatial and temporal fluctuations. In that way the two formulations suddenly are in competition with each other and we are asked, to explain the difference, as far as such a difference should be present.

<i>: Part 2, INDEL 1996, Chap. 16.1

<ii>: among others in R.W. Pohl: Einfuhrung in die Physik, Bd.2 Elektrizitatslehre, 21.Aufl. Springer-Verlag 1975, Seite 76 und 130



law of induction

unipolar generator

e.g.: transformer

discovery of **Faraday**

2nd **Maxwell** equation

$$\boxed{\mathbf{E} = \mathbf{v} \times \mathbf{B}} \quad (27.1)$$

$$\boxed{\mathrm{rot}\, \mathbf{E} = -\, d\mathbf{B}/dt} \quad (27.1^*)$$

Difference, e.g. in the (quasi-) stationary case ($d\mathbf{B}/dt = 0$):

$$\mathbf{E} \neq 0 \qquad\qquad \mathbf{E} = 0$$

Electric and magnetic field in the stationary case are:

coupled: $\xrightarrow{} \mathbf{E}$, $\mathbf{B}$ ($\perp$)

mag. induction

decoupled: $\xrightarrow{} \mathbf{E}$, $\mathbf{B}$

neglectible

Only **E** or **B** can form an open field line.
The other field line is a closed-loop field line

Closed-loop field lines have no effect, can't be influenced and are neglected (Maxwell approximation!)

Fig. 27.6: Law of induction according to Faraday or Maxwell?

27.6 Different formulation of the law of induction

Such a difference for instance is, that it is common practice to neglect the coupling between the fields at low frequencies. While at high frequencies in the range of the electromagnetic field the E- and the H-field are mutually dependent, at lower frequency and small field change the process of induction drops correspondingly according to Maxwell, so that a neglect seems to be allowed. Now electric or magnetic field can be measured independently of each other. Usually is proceeded as if the other field is not present at all.

That is not correct. A look at the Faraday-law immediately shows that even down to frequency zero always both fields are present. The field pointers however stand perpendicular to each other, so that the magnetic field pointer wraps around the pointer of the electric field in the form of a vortex ring in the case that the electric field strength is being measured and vice versa. The closed-loop field lines are acting neutral to the outside; they hence need no attention, so the normally used idea. It should be examined more closely if this is sufficient as an explanation for the neglect of the not measurable closed-loop field lines, or if not after all an effect arises from fields, which are present in reality.

Another difference concerns the commutability of E- and H-field, as is shown by the Faraday-generator, how a magnetic becomes an electric field and vice versa as a result of a relative velocity v. This directly influences the physical-philosophic question: What is meant by the electromagnetic field?

The textbook opinion based on the Maxwell equations names the static field of the charge carriers as cause for the electric field, whereas moving ones cause the magnetic field. But that hardly can have been the idea of Faraday, to whom the existence of charge carriers was completely unknown. The for his contemporaries completely revolutionary abstract field concept based on the works of the Croatian Jesuit priest Boscovich (1711-1778). In the case of the field it should less concern a physical quantity in the usual sense, than rather the experimental experience"' of an interaction according to his field description. We should interprete the Faraday-law to the effect that we experience an electric field, if we are moving with regard to a magnetic field with a relative velocity and vice versa.

In the commutability of electric and magnetic field a duality between the two is expressed, which in the Maxwell formulation is lost, as soon as charge carriers are brought into play. Is thus the Maxwell field the special case of a particle free field? Much evidence points to it, because after all a light ray can run through a particle free vacuum. If however fields can exist without particles, particles without fields however are impossible, then the field should have been there first as the cause for the particles. Then the Faraday description should form the basis, from which all other regularities can be derived. What do the textbooks say to that?


Faraday-law
or
2nd Maxwell equation
(unipolar induction)
E = v × B
(27.1)
rot E = – dB/dt
(27.1*)
resp.
U_i = – dØ/dt
(27.1**)
Discordance at the Technical University of Darmstadt
• According to Prof. Küpfmüller<i>:
special formulation
general formulation
of the law of induction
• According to Prof. Bosse<ii>:
„equation of transformation"
Maxwell = special case
Different order in the derivation
• Acc. to the TU Darmstadt (Prof. Küpfmüller<i>/Prof. Bosse<ii>)
follows from F = Q · E
and F = Q · (v x B)
E = v x B
unipolar induction can be derived !
• According to the University of Göttingen (Prof. Pohl<iii>)
follows from F = Q · E
and E = v x B
F = Q · (v x B)
Lorentz force can be derived !

Fig. 27.7: Different opinions and derivations

<i>: K. Kupfmuller: Einfuhrung in die theoretische Elektrotechnik, 12. Auflage, Springer Verlag 1988, Seite 228, Gl. 22.

<ii>: G. Bosse: Grundlagen der Elektrotechnik II, BI-Hochschultaschenbucher Nr. 183, l.Aufl. 1967, Kap. 6.1 Induktion, Seite 58

<iii>: R. W. Pohl: Einfuhrung in die Physik, Band 2 Elektrizitatslehre, 21. Auflage, Springer-Verlag 1975, Seite 77

27.7 Contradictory opinions in textbooks

Obviously there exist two formulations for the law of induction (27.1 and 27.1*), which more or less have equal rights. Science stands for the question: which mathematical description is the more efficient one? If one case is a special case of the other case, which description then is the more universal one?

What Maxwell's field equations tell us is sufficiently known, so that derivations are unnecessary. Numerous textbooks are standing by, if results should be cited. Let us hence turn to the Faraday-law (27.1). Often one searches in vain for this law in schoolbooks. Only in more pretentious books one makes a find under the keyword "unipolar induction". If one however compares the number of pages, which are spent on the law of induction according to Maxwell with the few pages for the unipolar induction, then one gets the impression that the latter only is a unimportant special case for low frequencies. Kupfmuller speaks of a „special form of the law of induction"[i], and cites as practical examples the induction in a brake disc and the Hall-effect. Afterwards Kupfmiiller derives from the „special form" the „general form" of the law of induction according to Maxwell, a postulated generalization, which needs an explanation. But a reason is not given[i]. Bosse gives the same derivation, but for him the Maxwell-result is the special case and not his Faraday approach[ii]! In addition he addresses the Faraday-law as equation of transformation and points out the meaning and the special interpretation. On the other hand he derives the law from the Lorentz force, completely in the style of Kupfmuller[i] and with that again takes it part of its autonomy. Pohl looks at that different. He inversely derives the Lorentz force from the Faraday-law[iii].

By all means, the Faraday-law, which we want to base on instead of on the Maxwell equations, shows „strange effects[i4]" from the point of view of a Maxwell representative of today and thereby but one side of the medal (eq. 27.1). Only in very few distinguished textbooks the other side of the medal (eq. 27.2) is mentioned at all. In that way most textbooks mediate a lopsided and incomplete picture[i,ii,i4]. If there should be talk about equations of transformation, then the dual formulation belongs to it, then it concerns a pair of equations, which describes the relations between the electric and the magnetic field.

If the by Bosse[ii] prompted term „equation of transformation" is justified or not at first is unimportant. That is a matter of discussion.

<i>: K. Kupfmuller: Einfuhrung in die theoretische Elektrotechnik, 12.Aufl., Springer Verlag 1988, Seite 228, Gl. 22.

<ii>: G. Bosse: Grundlagen der Elektrotechnik II, BI-Hochschultaschenbucher Nr.183, l.Aufl. 1967, Kap. 6.1 Induktion, Seite 58

<iii>: R.W.Pohl: Einfuhrung in die Physik, Bd.2 Elektrizitatslehre, 2 l.Aufl. Springer-Verlag 1975, Seite 77

<i4>: G. Lehner: Elektromagnetische Feldtheorie, Springer-Lehrbuch 1990, 1. Aufl., Seite 31 Kommentar zur Lorentzkraft (1.65)

The new and dual field approach consists of equations of transformation

of the electric and of the magnetic field[i]

$\boxed{\mathbf{E} = \mathbf{v} \times \mathbf{B}}$ (27.1) and $\boxed{\mathbf{H} = -\mathbf{v} \times \mathbf{D}}$ (27.2)

unipolar induction equation of convection

- Formulation according to the rules of duality
  - Grimsehl[ii] speaks of the ,,equation of convection", according to which moving charges produce a magnetic field and so-called convection currents (referring to Rontgen 1885, Himstedt, Rowland 1876, Eichenwald and others)
- Pohl[iii] gives examples for the equations of transformation,
- he writes the equations beneath each other

$\boxed{\mathbf{E} = \mu \cdot \mathbf{v} \times \mathbf{H}}$ (27.3) and $\boxed{\mathbf{H} = -\varepsilon \cdot \mathbf{v} \times \mathbf{E}}$ (27.4)

- and points out that for $v = c = 1/\sqrt{\mu \cdot \varepsilon}$ one equation changes into the other one!

The new and dual approach roots in textbook physics!

Fig. 27.8: The new and dual field approach

<i>: see Part 1, chapter 6.5

<ii>: Grimsehl: Lehrbuch der Physik, 2.Bd., 17,Aufl. Teubner Verl. 1967, S. 130.

<iii>: R.W.Pohl: Einfuhrung in die Physik, Bd.2 Elektrizitatslehre, 21.Aufl. Springer-Verlag 1975, Seite 77

27.8 The field-theoretical approach

The duality between E- and H-field and the commutability asks for a corresponding dual formulation to the Faraday-law (27.1). Written down according to the rules of duality there results an equation (27.2), which occasionally is mentioned in some textbooks. While both equations in the books of Pohl[i] and of Simonyi[ii] are written down side by side having equal rights and are compared with each other, Grimsehl[iii] derives the dual regularity (27.2) with the help of the example of a thin, positively charged and rotating metal ring. He speaks of „equation of convection", according to which moving charges produce a magnetic field and so-called convection currents. Doing so he refers to workings of Rontgen 1885, Himstedt, Rowland 1876, Eichenwald and many others more, which today hardly are known.

In his textbook also Pohl gives practical examples for both equations of transformation. He points out that one equation changes into the other one, if as a relative velocity v the speed of light c should occur. This question will also occupy us.

We now have found a field-theoretical approach with the equations of transformation, which in its dual formulation is clearly distinguished from the Maxwell approach. The reassuring conclusion is added: The new field approach roots entirely in textbook physics, as are the results from the literature research. We can completely do without postulates.

Next thing to do is to test the approach strictly mathematical for freedom of contradictions. It in particular concerns the question, which known regularities can be derived under which conditions. Moreover the conditions and the scopes of the derived theories should result correctly, e.g. of what the Maxwell approximation consists and why the Maxwell equations describe only a special case.

27.9 Derivation of Maxwell's field equations

As a starting-point and as approach serve the equations of transformation of the electromagnetic field, the Faraday-law of unipolar induction and the according to the rules of duality formulated law (eq. 27.1, 2). If we apply the curl to both sides of the equations then according to known algorithms of vector analysis the curl of the cross product each time delivers the sum of four single terms. Two of these again are zero for a non-accelerated relative motion in the x-direction with v = dr/dt.

One term concerns the vector gradient (v grad)B, which can be represented as a tensor. By writing down and solving the accompanying derivative matrix giving consideration to the above determination of the v-vector, the vector gradient becomes the simple time derivation of the field vector B(r(t)) (eq. 27.10, according to the rule of eq. 27.11).

---

[i] R.W.Pohl: Einfuhrung in die Physik, Bd.2 Elektrizitatslehre, 21.Aufl. Springer-Verlag 1975, Seite 76 und 130

[ii] K. Simonyi: Theoretische Elektrotechnik, 7.Aufl. VEB Berlin 1979, Seite 924.

[iii] Grimsehl: Lehrbuch der Physik, 2,Bd., 17.Aufl. Teubner Verl. 1967, S. 130.

As approach serve the equations of transformation (fig. 27.5) of the electric and of the magnetic field:

$$\boxed{\mathbf{E} = \mathbf{v} \times \mathbf{B}} \quad (27.1) \text{ and } \quad \boxed{\mathbf{H} = -\mathbf{v} \times \mathbf{D}} \quad (27.2)$$

If we apply the curl to the respective cross product:

$$\boxed{\text{rot } \mathbf{E} = \text{rot } (\mathbf{v} \times \mathbf{B})} \quad (27.5) \text{ and } \quad \boxed{\text{rot } \mathbf{H} = -\text{ rot } (\mathbf{v} \times \mathbf{D})} \quad (27.6)$$

then according to the algorithms<i> four sum terms are delivered:

$$\text{rot } \mathbf{E} = (\mathbf{B} \text{ grad})\mathbf{v} - (\mathbf{v} \text{ grad})\mathbf{B} + \mathbf{v} \text{ div } \mathbf{B} - \mathbf{B} \text{ div } \mathbf{v} \quad (27.5)$$

$$\text{rot } \mathbf{H} = -[(\mathbf{D} \text{ grad})\mathbf{v} - (\mathbf{v} \text{ grad})\mathbf{D} + \mathbf{v} \text{ div } \mathbf{D} - \mathbf{D} \text{ div } \mathbf{v}] \quad (27.6)$$

where 2 of them are zero because of: $\boxed{\mathbf{v}(t) = d\mathbf{r}/dt}$ (27.7)

- the divergence of v(t) disappears: $\text{div } v = 0$, (27.8)
- and will be zero as well: $\partial \mathbf{v}(t)/\partial \mathbf{r} = \boxed{\text{grad } \mathbf{v} = \mathbf{0}}$. (27.9)
- there remain the vector gradients:

$$\boxed{(\mathbf{v} \text{ grad})\, \mathbf{B} = \frac{d\mathbf{B}}{dt}} \quad \text{and} \quad \boxed{(\mathbf{v} \text{ grad})\, \mathbf{D} = \frac{d\mathbf{D}}{dt}} \quad ,(27.10)$$

- according to the rules<i> in general (with eq. 27.7):

$$\frac{d\mathbf{V}(\mathbf{r}(t))}{dt} = \frac{\partial \mathbf{V}(\mathbf{r}=\mathbf{r}(t))}{\partial \mathbf{r}} \cdot \frac{d\mathbf{r}(t)}{dt} = (\mathbf{v} \text{ grad})\, \mathbf{V} \quad (27.11)$$

- A comparison of the coefficients of both field equations

$$\text{rot } \mathbf{E} = -\, d\mathbf{B}/dt + \mathbf{v} \text{ div } \mathbf{B} = -\, d\mathbf{B}/dt - \mathbf{b} \quad (27.12)$$

$$\text{rot } \mathbf{H} = d\mathbf{D}/dt - \mathbf{v} \text{ div } \mathbf{D} = d\mathbf{D}/dt + \mathbf{j} \quad (27.13)$$

with the Maxwell equations results in:

- for the potential density $b = -v \text{ div } B = 0$, (27.14)
  (eq. 27.12 = law of induction, if b = 0 resp. div B = 0)

- for the current density $j = -v \text{ div } D = -v_x \cdot \rho_{el}$, (27.1a
  (eq. 27.13 = Ampere's law, if j = with v moving negative charge carriers (ρ_{el}= electric space charge density).

Fig. 27.9: Derivation of Maxwell's field equations as a special case of the equations of transformation

---

<i>: Bronstein u.a.: Taschenbuch der Mathematik, 4.Neuaufl. Thun 1999, S. 652

For the last not yet explained terms at first are written down the vectors b and j as abbreviation. With equation 27.13 we in this way immediately look at the well-known law of Ampere (1st Maxwell equation). The comparison of coefficients (27.15) in addition delivers a useful explanation to the question, what is meant by the current density j: it is a space charge density ρ_{el} consisting of negative charge carriers, which moves with the velocity v for instance through a conductor (in the x-direction).

The current density j and the to that dual potential density b mathematically seen at first are nothing but alternative vectors for an abbreviated notation. While for the current density j the physical meaning already could be clarified from the comparison with the law of Ampere, the interpretation of the potential density b still is due. From the comparison with the law of induction (eq. 27.1*) we merely infer, that according to the Maxwell theory this term is assumed to be zero. But that is exactly the Maxwell approximation and the restriction with regard to the new and dual field approach, which roots in Faraday.

In that way also the duality gets lost with the argument that magnetic monopoles (div B) in contrast to electric monopoles (div D) do not exist and until today could evade every proof. It thus is overlooked that div D at first describes only eddy currents and div B only the necessary anti-vortex, the potential vortex. Spherical particles, like e.g. charge carriers presuppose both vortices: on the inside the expanding (div D) and on the outside the contracting vortex (div B), which then necessarily has to be different from zero, even if there hasn't yet been searched for the vortices dual to eddy currents, which are expressed in the neglected term.

Assuming, a monopole concerns a special form of a field vortex, then immediately gets clear, why the search for magnetic poles has to be a dead end and their failure isn't good for a counterargument: The missing electric conductivity in vacuum prevents current densities, eddy currents and the formation of magnetic monopoles. Potential densities and potential vortices however can occur. As a result can without exception only electrically charged particles be found in the vacuum (derivation in chapter 4.2 till 4.4). Because vortices are more than monopole-like structures depending on some boundary conditions, only the vortex description will be pursued further consequently. Let us record: Maxwell's field equations can directly be derived from the new dual field approach under a restrictive condition. Under this condition the two approaches are equivalent and with that also error free. Both follow the textbooks and can so to speak be the textbook opinion.

The restriction (b = 0) surely is meaningful and reasonable in all those cases in which the Maxwell theory is successful. It only has an effect in the domain of electrodynamics. Here usually a vector potential A is introduced and by means of the calculation of a complex dielectric constant a loss angle is determined. Mathematically the approach is correct and dielectric losses can be calculated. Physically however the result is extremely questionable, since as a consequence of a complex s a complex speed of light would result (according to the definition $c \equiv 1/\sqrt{\varepsilon \cdot \mu}$). With that electrodynamics offends against all specifications of the textbooks, according to which c is constant and not variable and less then ever complex.

But if the result of the derivation physically is wrong, then something with the approach is wrong, then the fields in the dielectric perhaps have an entirely other nature, then dielectric losses perhaps are vortex losses of potential vortices falling apart?

- Maxwell's field equations:

$$\mathrm{rot}\,\mathbf{E} = -\,\mathrm{d}\mathbf{B}/\mathrm{d}t \qquad \text{(law of induction)} \qquad (27.1^*)$$

$$\mathrm{rot}\,\mathbf{H} = \mathrm{d}\mathbf{D}/\mathrm{d}t + \mathbf{j} \qquad \text{(Ampère's law)} \qquad (27.13)$$

- describe the special case for b = 0 resp. div B = 0

$$\mathrm{rot}\,\mathbf{E} = -\,\mathrm{d}\mathbf{B}/\mathrm{d}t + \mathbf{v}\,\mathrm{div}\,\mathbf{B} = -\,\mathrm{d}\mathbf{B}/\mathrm{d}t - \mathbf{b} \qquad (27.12)$$

$$\mathrm{rot}\,\mathbf{H} = \mathrm{d}\mathbf{D}/\mathrm{d}t - \mathbf{v}\,\mathrm{div}\,\mathbf{D} = \mathrm{d}\mathbf{D}/\mathrm{d}t + \mathbf{j} \qquad (27.13)$$

The physical meaning of the introduced abbreviations b and j is:

- the current density $\mathbf{j} = -\,\mathbf{v}\,\mathrm{div}\,\mathbf{D} = -\,v_x \cdot \rho_{el}$, (27.15)
- with Ohm's law $\mathbf{j} = \sigma \cdot \mathbf{E} = \mathbf{D}/\tau_1$, and (27.16)
- the potential density $\mathbf{b} = -\,\mathbf{v}\,\mathrm{div}\,\mathbf{B} = \mathbf{B}/\tau_2$,(27.17)
- with the eddy current time constant $\tau_1 = \varepsilon/\sigma$ (27.16*>
- and with the potential vortex time constant τ_2

The complete field equations (27.12 and 27.13) read, with the time constants (τ_1 and τ_2)of the respective field vortex:

- completely extended law of induction (with $B = \mu \cdot H$): (27.18)

$$\mathrm{rot}\,\mathbf{E} = -\,\mathrm{d}\mathbf{B}/\mathrm{d}t - \mathbf{B}/\tau_2 = -\,\mu \cdot (\mathrm{d}\mathbf{H}/\mathrm{d}t + \mathbf{H}/\tau_2) \qquad (27.20)$$

- and the well-known law of Ampere (with $D = \varepsilon \cdot E$): (27.19)

$$\mathrm{rot}\,\mathbf{H} = \mathrm{d}\mathbf{D}/\mathrm{d}t + \mathbf{D}/\tau_1 = \varepsilon \cdot (\mathrm{d}\mathbf{E}/\mathrm{d}t + \mathbf{E}/\tau_1) \qquad (27.21)$$

Fig. 27.10: The extension of the law of induction for vortices of the electric field (potential vortices].<i>

<i>: see also fig. 5.1

27.10 Derivation of the potential vortices

Is the introduction of a vector potential A in electrodynamics a substitute of neglecting the potential density b? Do here two ways mathematically lead to the same result? And what about the physical relevance? After classic electrodynamics being dependent on working with a complex constant of material, in what is buried an unsurmountable inner contradiction, the question is asked for the freedom of contradictions of the new approach. At this point the decision will be made, if physics has to make a decision for the more efficient approach, as it always has done when a change of paradigm had to be dealt with. The abbreviations j and b are further transformed, at first the current density in Ampere's law $j = -v_x \cdot \rho_{el}$ (27.15), as the movement of negative electric charges. By means of Ohm's law $j=\sigma \cdot E$ and the relation of material $D=\varepsilon \cdot E$ the current density j also can be written down as dielectric displacement current with the characteristic relaxation time constant $\tau_1 = \varepsilon / \sigma$ (eq. 27.16) for the eddy currents. In this representation of the law of Ampere (eq. 27.21) clearly is brought to light, why the magnetic field is a vortex field, and how the eddy currents produce heat losses depending on the specific electric conductivity σ. As one sees we, with regard to the magnetic field description, move around completely in the framework of textbook physics.

Let us now consider the dual conditions. The comparison of coefficients (eq. 27.12 + 27.17) looked at purely formal, results in a potential density b in duality to the current density j, which with the help of an appropriate time constant τ_2 founds vortices of the electric field. I call these potential vortices (in eq. 27.20).

In contrast to that the Maxwell theory requires an irrotationality of the electric field, which is expressed by taking the potential density b and the divergence B equal to zero. The time constant τ_2 thereby tends towards infinity. This Maxwell approximation leads to the circumstance that with the potential vortices of the electric field also their propagation as a scalar wave gets lost, so that the Maxwell equations describe only transverse and no longitudinal waves. At this point there can occur contradictions for instance in the case of the near-field of an antenna, where longitudinal wave parts can be detected measuring technically, and such parts already are used technologically in transponder systems e.g. as installations warning of theft in big stores.

It is denominating, how they know how to help oneself in the textbooks of high-frequency technology in the case of the near-field zone<i>. Proceeding from the Maxwell equations the missing potential vortex is postulated without further ado, by means of the specification of a ,,standing wave" in the form of a vortex at a dipole antenna. With the help of the postulate now the longitudinal wave parts are ,,calculated", like they also are being measured, but also like they wouldn't occur without the postulate as a result of the Maxwell approximation.

There isn't a way past the potential vortices and the new dual approach, because no scientist is able to afford to exclude already in the approach a possibly authoritative phenomenon, which he wants to calculate physically correct!

<i>: Zinke, Brunswig: Lehrbuch der Hochfrequenztechnik, 1. Bd., 3. Auflage 1986 Springer-Verlag Berlin, Seite 335

- Under the assumption: $E = E(r,t);\ H = H(r,t)$,
- using the relations of material:

  $\boxed{\mathbf{B} = \mu\cdot\mathbf{H}}$ and $\boxed{\mathbf{D} = \varepsilon\cdot\mathbf{E}}$:
- the complete and extended law of induction reads:

$$\mathrm{rot}\,\mathbf{E} = -\,\partial\mathbf{B}/\partial t - \mathbf{B}/\tau_2 = -\,\mu\cdot(\partial\mathbf{H}/\partial t + \mathbf{H}/\tau_2) \tag{27.20}$$

- and the well-known law of Ampere:

$$\mathrm{rot}\,\mathbf{H} = \partial\mathbf{D}/\partial t + \mathbf{D}/\tau_1 = \varepsilon\cdot(\partial\mathbf{E}/\partial t + \mathbf{E}/\tau_1) \tag{27.21}$$

---

if we again apply the curl operation to eq. 27.20 and insert eq. 27.21:

$$-\,\mathrm{rot\,rot}\,\mathbf{E} = \mu\cdot\partial(\mathrm{rot}\mathbf{H})/\partial t + (\mu/\tau_2)\cdot(\mathrm{rot}\,\mathbf{H}) \tag{27.22}$$

$$= \mu\cdot\varepsilon\cdot[\partial^2\mathbf{E}/\partial t^2 + (1/\tau_1)\cdot\partial\mathbf{E}/\partial t + (1/\tau_2)\cdot\partial\mathbf{E}/\partial t + \mathbf{E}/\tau_1\tau_2] \tag{27.23}$$

$$= (1/c^2)\cdot[\partial^2\mathbf{E}/\partial t^2 + (1/\tau_1 + 1/\tau_2)\cdot\partial\mathbf{E}/\partial t + \mathbf{E}/\tau_1\tau_2] \tag{27.24}$$

with the definition for the speed of light c:

$$\boxed{\varepsilon\cdot\mu = 1/c^2} \tag{27.25}$$

the fundamental field equation reads:

$$\underbrace{-\,c^2\cdot\mathrm{rot\,rot}\,\mathbf{E}}_{a} = \underbrace{\partial^2\mathbf{E}/\partial t^2}_{b\ \text{(electromagnetic wave)}} + \tag{27.26}$$

$$+ \underbrace{(1/\tau_1)\cdot\partial\mathbf{E}/\partial t}_{c} + \underbrace{(1/\tau_2)\cdot\partial\mathbf{E}/\partial t}_{d} + \underbrace{\mathbf{E}/\tau_1\tau_2}_{e}$$

+ eddy current + potential vortex + I/U

Fig. 27.11: Derivation of the fundamental field equation from the equations of transformation of the electromagnetic field.<i>

<i>: The fundamental field equation mathematically describes a wave damped with the vortices of the electric and the vortices of the magnetic field. It is formulated only in space and time. From it can be deduced numerous eigenvalue equations, (i.e. the equation of Schrodinger, fig. 5.1).

27.11 Derivation of the „fundamental field equation"

The two equations of transformation and also the from that derived field equations (27.20 and 27.21) show the two sides of a medal, by mutually describing the relation between the electric and magnetic field strength (between E and H). We get on the track of the meaning of the „medal" itself, by inserting the dually formulated equations into each other. If the calculated H-field from one equation is inserted into the other equation then as a result a determining equation for the E-field remains. The same vice versa also functions to determine the H-field. Since the result formally is identical and merely the H-field vector appears at the place of the E-field vector and since it equally remains valid for the B-, the D-field and all other known field factors, the determining equation is more than only a calculation instruction. It reveals a fundamental physical principle. I call it the "fundamental field equation".

The derivation always is the same: If we again apply the curl operation to rot E (law of induction 27.20) also the other side of the equation should be subjected to the curl. If for both terms rot H is expressed by Ampere's law 27.21, then in total four terms are formed (27.26): the wave equation (a-b) with the two damping terms, on the one hand the eddy currents (a-c) and on the other hand the potential vortices (a-d) and as the fourth term the Poisson equation (a-e), which is responsible for the spatial distribution of currents and potentials<i>.

Not in a single textbook a mathematical linking of the Poisson equation with the wave equation can be found, as we here succeed in for the first time. It however is the prerequisite to be able to describe the conversion of an antenna current into electromagnetic waves near a transmitter and equally the inverse process, as it takes place at a receiver. Numerous model concepts, like they have been developed by HF- and EMC-technicians as a help, can be described mathematically correct by the physically founded field equation.

In addition further equations can be derived, for which this until now was supposed to be impossible, like for instance the Schrodinger equation (chapter 5.6-5.9). This contrary to current opinion isn't a wave equation at all, since the term (b) with the second time derivation is missing. As diffusion equation it has the task to mathematically describe field vortices and their structures.

As a consequence of the Maxwell equations in general and specifically the eddy currents not being able to form structures, every attempt has to fail, which wants to derive the Schrodinger equation from the Maxwell equations.

The fundamental field equation however contains the newly discovered potential vortices, which owing to their concentration effect (in duality to the skin effect) form spherical structures, for which reason these occur as eigenvalues of the equation. For these eigenvalue-solutions numerous practical measurements are present, which confirm their correctness and with that have probative force with regard to the correctness of the new Held approach and the fundamental field equation. By means of the pure formulation in space and time and the interchangeability of the field pointers here a physical principle is described, which fulfills all requirements, which a world equation must meet.

<i>: see also fig. 5.1

Comparison:



• The **Faraday approach** is universal	• **Maxwell's field equations** can be derived!
• It reveals a **physical principle**	• The field equations describe only a **special case**!
• The field is the cause for the particles • (Principles of causality are preserved)	• Particle and field are cause and effect at the same time • (Violation of the rules of causality)
• Particles probably are **field configurations** • Quanta can be calculated as **field vortices** (without any hypothesis) • All **quantum properties** can be **calculated** likewise	• Particles consist of hypothetic subparticles • **Quark-hypothesis** must replace missing calculation • Sorting und systematizing of the properties in the **standard-model**
• **Potential vortices** form electric field vortices (the E-field is a source free vortex field)	• The electric field is **irrotational** (the E-field is an irrotational field of sources)
• Field vortices carry momentum and form a scalar wave • Longitudinal wave with arb. velocity of propagation v	• Electromagnetic wave is a transverse wave • Constant propagation with the speed of light c
⇒ **theory of objectivity**	⇒ **theory of relativity**

Fig. 27.12: Comparison of the field-theoretical approaches according to Faradav and according to Maxwell.

27.12 The Maxwell field as a derived special case

As the derivations show, nobody can claim there wouldn't exist potential vortices and no propagation as a scalar wave, since only the Maxwell equations are to blame that these already have been factored out in the approach. One has to know that the field equations, and may they be as famous as they are, are nothing but a special case, which can be derived.

The field-theoretical approach however, which among others bases on the Faraday-law, is universal and can't be derived on its part. It describes a physical basic principle, the alternating of two dual experience or observation factors, their overlapping and mixing by continually mixing up cause and effect. It is a philosophic approach, free of materialistic or quantum physical concepts of any particles.

Maxwell on the other hand describes without exception the fields of charged particles, the electric field of resting and the magnetic field as a result of moving charges. The charge carriers are postulated for this purpose, so that their origin and their inner structure remain unsettled and can't be derived. The subdivision e.g. in quarks stays in the domain of a hypothesis, which can't be proven. The sorting and systematizing of the properties of particles in the standard-model is nothing more than unsatisfying comfort for the missing calculability.

With the field-theoretical approach however the elementary particles with all quantum properties can be calculated as field vortices (chap. 7). With that the field is the cause for the particles and their measurable quantization. The electric vortex field, at first source free, is itself forming its field sources in form of potential vortex structures. The formation of charge carriers in this way can be explained and proven mathematically, physically, graphically and experimentally understandable according to the model.

Where in the past the Maxwell theory has been the approach, there in the future should be proceeded from the equations of transformation of the field-theoretical approach. If now potential vortex phenomena occur, then these also should be interpreted as such in the sense of the approach and the derivation, then the introduction and postulation of new and decoupled model descriptions isn't allowed anymore, like the near-field effects of an antenna, the noise, dielectric capacitor losses, the mode of the light and a lot else more.

The at present in theoretical physics normal scam of at first putting a phenomenon to zero, to afterwards postulate it anew with the help of a more or less suitable model, leads to a breaking up of physics into apparently not connected individual disciplines and an inefficient specialisthood. There must be an end to this now! The new approach shows the way towards a unified theory, in which the different areas of physics again fuse to one area. In this lies the big chance of this approach, even if many of the specialists at first should still revolt against it.

This new and unified view of physics shall be summarized with the term "theory of objectivity". As we shall derive, it will be possible to deduce the theory of relativity as a partial aspect of it (chapter 6 and 28).

Let us first cast our eyes over the wave propagation.

- Starting-point: the fundamental field equation

$$-\, c^2\cdot\text{rot rot }\mathbf{B} = \frac{d^2\mathbf{B}}{dt^2} + \frac{1}{\tau_2}\,\frac{d\mathbf{B}}{dt} + \frac{1}{\tau_1}\,\frac{d\mathbf{B}}{dt} + \frac{\mathbf{B}}{\tau_1\tau_2} \qquad (27.26^*)$$

- with a magnetic flux density $B = B(r(t))$.

1st condition for eq. 27.26*:
the special case, if $\sigma=0$ and $\sigma/\varepsilon = \boxed{(1/\tau_1) = 0}$. (27.16*)

The remaining vortex term is transformed by applying already used relations (eq. 27.10 and eq. 27.17):

$$\boxed{\frac{1}{\tau_2}\cdot\frac{d\,\mathbf{B}}{d\,t} = \mathbf{v}\cdot\text{grad}\,\frac{\mathbf{B}}{\tau_2}} \;(27.10) \qquad \boxed{\frac{\mathbf{B}}{\tau_2} = -\,\mathbf{v}\cdot\text{div}\,\mathbf{B}}\;.\;(27.17)$$

If the velocity of propagation: $v = (v_x,\ v_y=0,\ v_z=0)$; $v = dx/dt$, then the simplified field equation (if the coordinates are orientated on the vector of velocity) results in the general wave equation (involved with the x-component) in the form:

$$\boxed{\|\mathbf{v}\|^2\ \text{grad div }\mathbf{B}\ -\ c^2\ \text{rot rot }\mathbf{B}\ =\ d^2\mathbf{B}/dt^2} \qquad (27.27)$$

longitudinal	transverse	wave
with v = arbitrary	with c = const.	velocity of propagation

2nd condition for eq. 27.28: $v = c$.

The wave equation in the usual notation (= inhomogeneous Laplace equation, = purely a special case!) now reads:

$$\boxed{\Delta\mathbf{B}\ =\ \text{grad div }\mathbf{B} - \text{rot rot }\mathbf{B}\ =\ (1/c^2)\cdot d^2\mathbf{B}/dt^2} \qquad (27.28)$$

Fig. 27.13: Derivation of the wave equations (inhomogeneous
Laplace equation) as a special case of the equations of transformation of the electromagnetic field.

27.13 Derivation of the wave equation

The first wave description, model for the light theory of Maxwell, was the inhomogeneous Laplace equation:

$$\boxed{\Delta \mathbf{E} \cdot c^2 = d^2\mathbf{E}/dt^2} \quad \text{with} \quad \boxed{\Delta \mathbf{E} = \text{grad div } \mathbf{E} - \text{rot rot } \mathbf{E}} \qquad (27.28^*)$$

There are asked some questions:

- Can also this mathematical wave description be derived from the new approach?
- Is it only a special case and how do the boundary conditions read?
- In this case how should it be interpreted physically?
- Are new properties present, which can lead to new technologies?

Starting-point is the fundamental field equation (27.26). We thereby should remember the interchangeability of the field pointers, that the equation doesn't change its form, if it is derived for H, for B, for D or any other field factor instead of for the E-field pointer. This time we write it down for the magnetic induction B and consider the special case, that we are located in a badly conducting medium, as is usual for the wave propagation in air. But with the electric conductivity σ also $1/\tau_1 = \sigma/\varepsilon$ tends towards zero (eq. 27.16*). With that the eddy currents and their damping and other properties disappear from the field equation, what also makes sense. There remains the potential vortex term $(1/\tau_2)*dB/dt$, which using the already introduced relations (eq. 27.10 and 27.17) involved with an in x-direction propagating wave ($v = (v_x, v_y = 0, v_z = 0)$) can be transformed directly into:

$$-\|\mathbf{v}\|^2 \cdot \text{grad div } \mathbf{B}$$

The divergence of a field vector (here B) mathematically seen is a scalar, for which reason this term as part of the wave equation founds so-called „scalar waves" and that means that potential vortices, as far as they exist, will appear as a scalar wave. We at this point tacitly anticipate chapter 28, which provides the reason for the speed of light losing its vectorial nature, if it is correlated with itself. This insight however is valid in general for all velocities ($v = dr/dt$), so that in the same way a scalar descriptive factor can be used for the velocity ($v = dx/dt$) as for c.

From the simplified field equation (27.26*) the general wave equation (27.27) can be won in the shown way, divided into longitudinal and transverse wave parts, which however can propagate with different velocity.

Physically seen the vortices have particle nature as a consequence of their structure forming property. With that they carry momentum, which puts them in a position to form a longitudinal shock wave similar to a sound wave. If the propagation of the light one time takes place as a wave and another time as a particle, then this simply and solely is a consequence of the wave equation. Light quanta should be interpreted as evidence for the existence of scalar waves. Here however also occurs the restriction that light always propagates with the speed of light. It concerns the special case $v = c$. With that the derived wave equation (27.27) changes into the inhomogeneous Laplace equation (27.28). The electromagnetic wave in both cases is propagating with c. As a transverse wave the field vectors are standing perpendicular to the direction of propagation. The velocity of propagation therefore is decoupled and constant. Completely different is the case for the longitudinal wave. Here the propagation takes place in the direction of an oscillating field pointer, so that the phase velocity permanently is changing and merely an average group velocity can be given for the propagation. There exists no restriction for v and $v = c$ only describes a special case.

• From the dual field-theoretical approach are derived:	From Maxwell's field equations can be derived:
=> Maxwell's field equations	=> 0
=> the wave equation (with transverse and longitudinal parts)	=> only transverse waves (no longitudinal waves)
=> scalar waves (Tesla-/neutrino radiation)	=> 0 (no scalar waves)
=> vortex and anti-vortex (current eddy and potential vortex)	=> only eddy currents
=> Schrodinger equation (basic equation of chemistry)	=>0
=> Klein-Gordon equation (basic eq. of nuclear physics)	=>0

Fig. 27.14: Comparison of the efficiency of both approaches.

(as an interim result, if it concerns the question, which approach of the two is the more efficient one and which one better should be discarded. The final balance is made in chapter 28).
It here concerns partial aspects of the following theories:

=> theory of objectivity	=> theory of relativity

27.14 The new field approach in synopsis

Proof could be furnished that an approximation is buried in Maxwell's field equations and that they merely represent the special case of a new, dually formulated and more universal approach. The mathematical derivations of the Maxwell field and the wave equation disclose, of what the Maxwell approximation consists. The anti-vortex dual to the expanding eddy current with its skin effect is neglected. This contracting anti-vortex is called potential vortex. It is capable of forming structures and propagates as a scalar wave in longitudinal manner in badly conducting media like air or vacuum.

At relativistic velocities the potential vortices are subject to the Lorentz contraction. Since for scalar waves the propagation occurs longitudinally in the direction of an oscillating field pointer, the potential vortices experience a constant oscillation of size as a result of the oscillating propagation. If one imagines the field vortex as a planar but rolled up transverse wave, then from the oscillation of size and with that of wavelength at constant swirl velocity with c follows a continual change in frequency, which is measured as a noise signal.

The noise proves to be the in the Maxwell equations neglected potential vortex term, which founds scalar waves. If at biological or technical systems, e.g. at antennas a noise signal is being measured, then that proves the existence of potential vortices, but it then also means that the scope of the Maxwell theory has been exceeded and erroneous concepts can be the result.

As an answer to the question about possible new technologies is pointed to two special properties.

1st potential vortices for reason of their particle nature carry momentum and energy. Since we are surrounded by noise vortices, an energy technical use of scalar waves would be feasible, where the noise power is withdrawn of the surroundings. There is evidence that biological systems in nature cover their need for energy in this way. But at least an energy transmission with scalar waves already would be a significant progress with regard to the alternating current technology of today.

2nd the wavelength multiplied with the frequency results in the velocity of propagation v of a wave $(\lambda \cdot f = v)$, and that for scalar waves by no means is constant. With that wavelength and frequency aren't coupled anymore; they can be modulated separately, for which reason for scalar waves a whole dimension can be modulated additionally compared to the Hertzian wave. In that the reason can be seen, why the human brain with just 10 Hz clock frequency is considerably more efficient than modern computers with more than 1 GHz clock frequency. Nature always works with the best technology, even if we haven't yet understood it.

If we would try to learn of nature and an energy technical or an information technical use of scalar waves would occur, then probably nobody wanted to have our today still highly praised technology anymore. In the course of the greenhouse gases and the electrosmog we have no other choice than to scientifically occupy us with scalar waves and their technical use.

Equations of transformation

of the electric and of the magnetic field<i>

$\boxed{\mathbf{E} = \mathbf{v} \times \mathbf{B}}$ (27.1) and $\boxed{\mathbf{H} = -\mathbf{v} \times \mathbf{D}}$ (27.2)

with: $\mathbf{B} = \mu \cdot \mathbf{H}$ (28.1) and $\mathbf{D} = \varepsilon \cdot \mathbf{E}$ (28.2)

$\boxed{\mathbf{E} = \mu \cdot \mathbf{v} \times \mathbf{H}}$ (27.3) and $\boxed{\mathbf{H} = -\varepsilon \cdot \mathbf{v} \times \mathbf{E}}$ (27.4)

Experience/observation is dependent on the relative velocity v !



Written down in general with field vectors:

Written down in components in Cartesian coordinates: (unit vectors $\mathbf{e}_x$, $\mathbf{e}_y$, $\mathbf{e}_z$)

in $\mathbf{e}_x$-direction: $\mathbf{v} = v_x(x(t)) = dx/dt$

$\mathbf{H} = -\varepsilon \cdot \mathbf{v} \times \mathbf{E}$ in $\mathbf{e}_y$-direction: $\mathbf{H} = -H_y = -\varepsilon \cdot v_x \cdot E_z$

$\mathbf{E} = \mu \cdot \mathbf{v} \times \mathbf{H}$ in $\mathbf{e}_z$-direction: $\mathbf{E} = E_z = \mu \cdot v_x \cdot H_y$

inserted into each other: (28.3)

$\mathbf{E} = -\varepsilon \cdot \mu \cdot [\mathbf{v} \times (\mathbf{v} \times \mathbf{E})]$ in $\mathbf{e}_z$-direction: $E_z = \varepsilon \cdot \mu \cdot v_x \cdot v_x \cdot E_z$

$\mathbf{E} = -(1/c^2) \cdot [\mathbf{v} \cdot \underbrace{(\mathbf{v} \cdot \mathbf{E})}_{= 0,\ \text{since} \perp} - \mathbf{E} \cdot (\mathbf{v} \cdot \mathbf{v})]$ $E_z = (1/c^2) \cdot v_x^2 \cdot E_z$

$\mathbf{E} = +(\mathbf{v}^2/c^2) \cdot \mathbf{E}$ resp.: $E_z = (v_x^2/c^2) \cdot E_z$ (28.4)

result:<ii> $\boxed{v = c}$ (28.5)

Fig. 28.1: The equations of transformation,<i>

<i>: see part 1, chap. 6.5, eq. 60

<ii>: R. W. Pohl: Einfuhrung in die Physik, Bd. 2 Elektrizitatslehre, 21. Aufl. Springer-Verlag 1975, Seite 77, s.a. Kommentar auf Tafel 27.8

<iii>: chapter 28 is a repetition of chapter 6

28. Objectivity versus relativity

The new and field-theoretical approach contains the Maxwell-equations, but goes over and above these in one point. It describes potential vortices and their propagation in space as a scalar wave. With that can also a conclusive answer be given to the often-asked question for the medium and the mediated particles, which is a prerequisite for every longitudinal wave. Mediated are vortex structures with particle nature and the field itself functions as a medium. Is with that also answered the question concerning the aether?<iii>

28.1 The question concerning the aether

Do you know the Maxwell-experiment? No, you wouldn't be able to, since the intellectual father fast did make a backdown, after it didn't work out. Today one speaks of the Michelson-experiment and it may be connected with any other names (Morley, etc.). Remember: In his light theory Maxwell had determined a particular and constant value for the speed of light and for that there should be a physical reason, which should have its cause in the aether. By means of proving this aether Maxwell wanted to prove his theory, but this enterprise thoroughly went wrong.
The consideration was as follows: If the Earth is spinning and is moving through the cosmos, then one should be able to detect an aetherwind and different values for c in the different points of the compass. Maxwell found support for his project at the observatory, since with the aberration of the stars Bradley previously had described an observation, which could be considered as evidence for an aether. The director of the observatory charged his assistant Dr. Michelson with the task, to carry out a corresponding proof of an aether this time in a terrestrial experiment. But such an aether couldn't be proven, what Maxwell had to accept as a severe strike against his light theory. Seven years later Maxwell got the acknowledgement, however from a completely other corner by means of the experiments concerning the radio transmission of Heinrich Hertz.

Until today the question has remained open why astrophysics can prove the aether, whereas the detection in a terrestrial laboratory fails and it looks like there doesn't exist an aether. But as definition for the cause of c the aether can't be abolished as long as it is unsettled why the light is propagating with c of all possible velocities. The question is asked, what determines the propagation of light from today's point of view? Now, by means of outside fields the light can be slowed down. At present the world record lies at less than 65 kilometers per hour in a Bose-Einstein condensate. If electromagnetic fields determine the speed of light, if in addition field or gravitational lenses should confirm this, then the field takes over the task of the aether!

At this place the new field-theoretical approach shows its capabilities. The equations of transformation say nothing but that a moving H-field transforms to a resting E-field and vice versa, that thus in the place of a moving aether, the aetherwind, a resting aether is found. Doing so the dual field partners merely exchange their places. Therefore it is a wild-goose chase, wanting to measure an aetherwind with gauges, which underlie the same field (fig. 28.2).
Michelson had to fail.

The equations of transformation say:

$$\boxed{\mathbf{E} = \mu \cdot \mathbf{v} \times \mathbf{H}} \quad (27.3) \text{ and } \quad \boxed{\mathbf{H} = -\varepsilon \cdot \mathbf{v} \times \mathbf{E}} \quad (27.4)$$

- Experience/observation depends on the relative velocity v!
- The field takes over the function of the aether (determines c) and
- an aetherwind v x H is measured as a resting aether E and vice versa!

- for $v = c$ the equations of transformation turn into each other and are identical $[v = v_x(x(t))]$.
- for $v < c$ a motion field E_v depending on v is resulting

$$\boxed{E_v = E \cdot (v^2/c^2)} \quad (28.6)$$

- for $v = 0$ also $E_v = 0$.
- the motion field overlaps the E-field
- in the case of vortex fields the effect overlaps the cause and itself is the cause for a new effect.
- The overlap reaches to infinity, where each time is valid:

$$E_{n+1} = E_n \cdot (v^2/c^2) \quad (28.7)$$

- the field Eo overlaps the motion field E_v

$$E = E_0 + E_v = E_0 \cdot (1 + v^2/c^2) \quad (28.8)$$

- for infinite overlap:

$$E = E_0 + E_1 + E_2 + E_3 + E_4 + \ldots + E_n + E_{n+1} + \ldots \quad (28.9)$$

- results in the power series:

$$E = E_0 \cdot [1 + (v/c)^2 + (v/c)^4 + (v/c)^6 + \ldots + (v/c)^{2n} + (v/c)^{2(n+1)} + \ldots] \quad (28.10)$$

Fig. 28.2: Power series as a result of a vortex overlap.

<i>: Grimsehl: Lehrbuch der Physik, 2.Bd., 17.Aufl. Teubner Verl. 1967, S. 130.

<ii>: R.W.Pohl: Einfuhrung in die Physik, Bd.2 Elektrizitatslehre, 21.Aufl. Springer-Verlag 1975, Seite 72 und 76, bzw. 130.

<iii>: K. Simonyi: Theoretische Elektrotechnik, 7.Aufl. VEB Berlin 1979, Seite 924.

<i4>: E. Friebe: Die Vektorprodukte der Maxwell'schen Elektrodynamik, DPG-Didaktik-Tagungsband 1995, S.396

28.2 Vortices, an overlap of the overlap

Not with any approach until now the question concerning the aether could be solved. Only the new field-theoretical approach proves with the unambiguous and free of contradiction clarification of the question concerning the aether its unmatched superiority. We hence without exception work with this approach, which is anchored tightly in textbook physics. The two equations of transformation on the one hand are the law concerning the unipolar induction according to Faraday (27.1) and on the other hand the dual formulation (27.2), which Grimsehl[i] calls convection equation. Grimsehl goes around the question for the correct sign by means of forming a modulus. Pohl draws detailed distinctions of cases and dictates the each time relevant formulation of the dual law[ii]. The sign eventually should be chosen according to the definition of the orientation of the field pointers. Also Simonyi gives both equations and the each time appropriate experiments[iii].

If we assume the carrier of an electric field is moving with the not accelerated relative velocity v with regard to the reference system used by the observer, then a magnetic H-field is observed, which stands perpendicular both to the direction of the E-field and to the direction of v. If the motion takes place perpendicular to the area stretched by E- and H-field, then the H-field again is observed and measured as an E-field. There will occur an overlap of the fields.

In spite of that we first consider the theoretical case, that no overlap is present, and the observer as it were sees himself. The result is trivial: the relative velocity v must be the speed of light $v = c$. (28.5) If considered at the speed of light, the two equations of transformation turn into each other. They now are identical both mathematically and in their physical expressiveness. For this case it actually is possible, to derive the dual law straight from the Faraday law. For a wave propagating with the speed of light, to name an example, the field strength propagating along is always equal to the causing field strength, which depends on position.

If besides the evaluation of the values also the circumstance is considered that it concerns vectors, then at this place a problem as a matter of principle of the Maxwell theory gets visible, to which has been pointed occasionally, e.g. at the German Physical Society[i4]. The derivation of the speed of light from two vector equations requires, that c also has to be a vector. The question is: How the velocity vector v suddenly becomes the scalar and not pointing, in all directions of space constant factor c? Is therefore for mathematical and physical reasons "the Maxwell theory in essential parts erroneous", according to a statement of the German Patent Office[i4]?

Now, the constancy of the speed of light is a fact, which even can be derived. We at first will be content with the clue that for every observation with the speed of light, with the eyes or a gauge constructed corresponding to our perception, the vector in all its components each time is correlated to itself, by what actually the orientation of direction gets lost. Under these for c and with equal rights also for v relevant circumstances we are entitled to calculate further with the values.

An observer, who is moving with v slower than c, will besides the original E-field also observe a motion field E_v depending on the velocity v, which disappears, if v becomes zero. What he catches sight of and is able to register with gauges in the end is the overlap of both field components.

- concerning the development of the power series:

$$E = E_0\cdot[1 + (v/c)^2 + (v/c)^4 + (v/c)^6 + \dots + (v/c)^{2n} + (v/c)^{2(n+1)} + \dots] \qquad (28.10)$$

- for $q < 1$ the power series with $q = (v/c)^2$ will converge (28.11)

$$\boxed{\sum_{n=0}^{\infty} q^n = \frac{1}{1-q}} \qquad (28.12)$$

- for $(v/c)^2 < 1$ resp. for $v < c$ therefore is valid:

$$E = E_0\cdot[1/1 - (v/c)^2] \quad \text{resp.} \quad \boxed{E_0 = E\cdot[1 - (v/c)^2]} \qquad (28.13)$$

The square root of Lorentz appears in squared form[i]:

$$\boxed{\left(1 - \frac{v^2}{c^2}\right) = \frac{E_0}{E}} \qquad (28.14)$$

The derivation for the magnetic field strength analogous to that provides the identical result[i]:

$$\boxed{\left(1 - \frac{v^2}{c^2}\right) = \frac{H_0}{H}} \qquad (28.15)$$

Fig. 28.3 The field dilatation depending on velocity

<i>: see part 1, chap. 6.6

<ii>: Prof. Dr. H.-J. Runckel, Abteilung fur Mathematik IV der Universitat Ulm

28.3 Field overlap

But it doesn't abide by this one overlap. In the case of vortex fields the effect overlaps the cause and itself becomes the cause for a new effect. The overlapped cause produces a further effect, which for its part is overlapping (see chap. 3).

Vortices thus arise, if overlaps for their part are overlapping and that theoretically reaches to infinity, to which I already repeatedly have pointed (fig. 3.0). In addition do vortices represent a fundamental physical principle. The Greek philosopher Demokrit has traced back the whole nature to vortex formation and that already 2500 years ago!

In the field-theoretical approach this interpretation seems to experience a mathematical confirmation, since also the fields are overlapping in vortex structures. According to that we owe our observations and our being the relative movements and the vortex formation. If reversed there wouldn't be any movement, then there also would not exist fields, light nor matter. If we observe the sky, then everything visible follows the movement of its own of the Earth, of the solar system and the whole galaxy, which is on its way with unknown galactic velocity, and all movements take place in vortex structures (fig. 10.2).

The field overlap dictated by the Faraday-approach as well reaches to infinity, what has stimulated my colleagues of mathematics to also mathematically put into practice this physical requirement[ii]. This leads to an infinite power series, which converges under the condition that $v < c$.

As a result of the power series development the well-known square root $\sqrt{1-(v^2/c^2)}$ of Lorentz occurs in squared form (see also fig. 6.6). It determines the relation of the observed and the causing field strength of the electric or the magnetic field. Physically the found relation describes a dilatation field depending on velocity. The field strength thus increases, if the relative velocity v increases, or inversely no difference is observable anymore, if v tends towards zero.

Whoever wants to compete with Albert Einstein (1879-1955), who has developed the theory of relativity from the length contraction, which depends on velocity, could be inclined to derive a new field physics from the field dilatation. But I must warn of such a step. The derivation of the length contraction by the mathematician Hendrik Lorentz (Lorentz contraction) assumes a number of limiting conditions. The relative velocity v for instance may not experience any acceleration. Actually however almost all motion takes place as circular vortex motion, so that due to the occurring centripetal acceleration the conditions for the theory of relativity aren't fulfilled anymore. Neglects or generalizations thereby can lead to considerable errors, of which I would like to warn. It in general is a delicate enterprise, if one wants to provide a physical interpretation for a purely mathematically won result.

This warning to the same extent also is valid for the here shown derivation of the field dilatation. The limiting conditions practically are the same as for Einstein and the problems with a provided physical interpretation won't be less. Also here lots of paradoxes will occur, which are nothing but errors of the theory. So we won't reach our destination.

There now only one further mathematical step is necessary, which links the theory of relativity with the new notion of a field dilatation depending on velocity.

Example:
Measurement of length by means of a measurement of propagation time (sound or light) with c = L/t in a vehicle moving with v.


transmitted
impulse (t = 0)
received
impulse (t = 2x/v)
observer
system
(moving)
v
x = vt
x
at distance L
L₀
L
L₀
reference system
(„resting“)
reflector (mirror)

From driving time t:

$t = 2\frac{x}{v}$ = signal propagation time: $t = 2\frac{L_o}{c}$ follows $\boxed{\frac{x}{v} = \frac{L_o}{c}}$

According to Pythagoras: $L_o^2 = L^2 + x^2 = L^2 + L_o^2 \cdot (v^2/c^2)$

$$L_o^2 \cdot (1 - v^2/c^2) = L^2$$

the shortening of the rule results in:

$$\boxed{(1 - \frac{v^2}{c^2}) = (\frac{L}{L_o})^2} \quad (28.16)$$

Fig. 28,4: ______Derivation of the length contraction

Examples: contraction according to Lorentz transformation, measurable length shortening, curvature of space.

Counterexample: unsuccessful aether detection (Michelson experiment)

28.4 The derivation of the length contraction

The Lorentz transformation is the result of a purely mathematical problem. Stimulated by the surprisingly result of the Michelson experiment the Dutchman Hendrik A. Lorentz 1891 asked himself, how the equations of the Galilei-transformation would have to look like, if the propagation of light wouldn't be infinitely fast but finite and constant. He thereby proceeds from the assumption of two inertial systems moving against one another with a not accelerated velocity v, in which the laws of Newtonian physics are equally valid[i]. As a result of the relative motion a change of the length measures will occur.

This at first can be explained as a purely geometric effect in the context of nonrelativistic physics. We imagine a vehicle, which is on its way with constant velocity, and emits an optical or acoustical signal. Sideways in the countryside is standing in a perpendicularly measured distance L a reflector (mirror), which sends the signal back again. The velocity of the signal however isn't infinitely fast and from that follows that the vehicle during the propagation time of the signal as well has moved a bit further. The actual way, which the signal had to cover now amounts to L_o (> L). The distance measure thus is observed smaller as it is in reality, to be specific for the factor of the square root of Lorentz (fig. 28.4).

$$L = L_o \cdot \sqrt{1-(v^2/c^2)} \quad (28.16)$$

According to the principle of relativity it doesn't play a role, if the vehicle is driving or if it is standing still and the mirror is moving with a linear uniform velocity.

Initially Einstein also only spoke of an observable length contraction, which must not necessarily occur in reality, an optical deception so to speak. Lorentz however proceeded from the assumption of a physical length change, thus a length change existing in reality, what in practice at first makes no difference. If e.g. at relativistic velocities a rocket becomes smaller, then the pilot equally shrinks, so that it would not be possible to notice a present difference.

If however the observer stands outside the events and takes a „neutral standpoint", then he will be able to see, which interpretation is the right one. Today some examples are known. In accelerators particles at relativistic fast velocities actually get smaller for the factor of the square root of Lorentz. That has been proven and this result afterwards gives the Dutchman Lorentz right! The followers of the physical length contraction also are called Neo-Lorentzians.

In the vicinity of a gravitational mass the speed of light becomes so slow, that the shortening factor plays a role and space is curved towards the mass. To understand this shortening of scale, the influence of the field also should be considered.

<i>: Example: In a closed lift physical experiments are being carried out. Accelerations of the lift have an influence on the experiments. However no influence can be detected, if the lift is standing still or is moving with constant velocity. It with that fulfills the conditions of an inertial system. The question is: what do the experiments show someone standing outside, whom the lift passes by?

From the comparison of the Lorentz contraction (28.16) with the field dilatation (28.14 and 28.15)

$$\left(1-\frac{v^2}{c^2}\right) = \left(\frac{L}{L_o}\right)^2 \quad \overset{!}{=} \quad \left(1-\frac{v^2}{c^2}\right) = \frac{E_o}{E} = \frac{H_o}{H}$$

follows

$$\left(1-\frac{v^2}{c^2}\right) = \boxed{\left(\frac{L}{L_o}\right)^2 = \frac{E_o}{E} = \frac{H_o}{H}} \qquad (28.17)$$

the proportionality (length measures depending on field):

$$\underline{E,\ H \sim 1/L^2} \qquad \text{and} \qquad Eo,\ Ho \sim 1/L_0^2 \qquad (28.18)$$

Experimental examples<i>:

- Electrostriction (piezo speaker)
- Magnetostriction
- Field or gravitational lenses
- Curvature of space, deflection of light

Conclusion<ii>:

- The field determines the length measures (what is 1 meter)
- The field determines the velocities v (in m/s)
- The field determines the speed of light c [m/s]
- Measurement of the speed of light is made with itself:

$$\boxed{c \sim r} \quad (28.19)$$

- Measured is a constant of measurement c = 300.000 km/s
- The speed of light c is not a constant of nature!

Fig. 28.5: The dependence of the Lorentz contraction on the field

<i>: see part 1, chap. 6.10

<ii>: see part 1, chap. 6.11

28.5 The dependence of the Lorentz contraction on the field

The two results of the field dilatation (28.14 and 28.15) and of the Lorentz contraction (28.16) must be brought together and compared (28.17). Doing so the mathematical expression of the square root of Lorentz is cancelled out. That is of utmost importance, since with that also all limits disappear and there remains a purely physical relation, a proportionality of utmost importance (28.18).

What was the sense of the limits associated with the introduction of so-called inertial systems, which are the basis of the Lorentz transformation and which were adopted for our derivation of the field dilatation? They now only are auxiliary considerations according to model. We have chosen a very simple model, which can be described mathematically, in which an observer holds in his hand gauges for distances and field strengths and with that gauges a system flying by with constant velocity. He on the one hand determines a length contraction and on the other hand a field dilatation. He compares both with each other and comes to the conclusion: The field determines the dimensions!

This statement is purely physical and it is generally valid. It is independent of the relative velocity and all other mathematical conditions. A centrally accelerated circular motion e.g. will falsify the length contraction to the same extent, as the at the same time occurring field dilatation. It can be expected, that in addition to the square root of Lorentz also other errors will mutually efface, so that a generalization in this case actually seems to be allowed.

The won proportionality is of most elementary importance. We use it in the case of the piezo speaker and know it from the curvature of space and deflection of light in presence of extreme fields. If we ourselves however are exposed to the field as an observer, in which also the object to be observed is situated, then we are in the dilemma, not being able to perceive the influence. If we, to stay with the example, would sit in a rocket and this would become smaller at faster velocity, then we would notice nothing, since we also would shrink along to the same extent.

That concerns every measurement of velocity in general and the speed of light c in particular, which as is well-known is measured in meters per second. But if the field determines c and in the same way the length measure, which is given in meters, then both stand in a direct proportionality to each other, then we won't have the slightest chance to measure the speed of light. If namely c is changed, then this concerns the measurement path in the same way. Now the variable is measured with itself and as a result appears c, a constant value. We neither can see the change, since our eyes scan all objects optically and that means with c.

It is the nightmare of each and every measurement engineer, if the gauge depends on the factor to be measured. No wonder, if the theorem of addition of the velocities apparently loses its validity and always the same c is being measured, independent of the direction in which the source of radiation is moving (chap. 6.11). The result is:

The speed of light is a constant of measurement and not a constant of nature!
If however the light is scanned with the speed of light, then also all components of the light vector correlated with themselves result in the same constant value c, then actually the vector of the speed of light loses its orientation in space and becomes a scalar factor. The Maxwell equations already anticipate this circumstance, but without providing an explanation why this is correct. Only the new field approach can answer the open question. With the derivation an axiom of physics - one also can say stumbling block - has been overcome.



The field strength determines the length measure:
(the distance L between the spheres)<i>

$$\boxed{E, H \sim 1/L^2} \qquad (28.18)$$


Orbital curvature depending on field
v_{inside}
v_{outside}
sun
Earth

Fig. 28.6 A: The curvature of the Earth in the gravitational field of the sun



Fig. 28.6 B: Force of attraction and reduction of the distance L as the mutual field influence of two masses.

<i>: Repetition of part 1, chapter 6.7

28.6 Boscovich and the respiration of the Earth

Who has got a good idea, fast will find that some other scientist had the same idea already before, and for his part possibly already had to make the same experience. If in spite of that the track fast loses in history, it as a rule is because of the insufficient citing and the vanity of the discoverers, who in reality only are rediscoverers of a much older knowledge.

The dependence of the length measures on the field (eq. 28.18) in the mathematical form of the derivation however should still be quite new. But the physical consequence already was described by the Jesuit priest Roger Joseph Boscovich from Dalmatia in 1755<i>. He was Professor for mathematics and theology in Rome and spoke about the world on the one hand being deformable, similar to rubber, but on the other hand we aren't able to perceive this, since our body is made of the same material and follows all changes. „We in an absolute way can recognize neither the place, nor distances or orders of magnitude", writes Boscovich in his book about space and time and writes how these are perceived by us<ii>. He suspects that the Earth unobservable for man „is respiring".

Actually a terrestrial observer at daytime is situated closer to the sun than in the night. He by day is exposed to a slightly stronger field and as a result correspondingly smaller. He himself and all objects in his neighbourhood are subject to an identical fluctuation of size, so that this „respiration" of the Earth cannot be detected. It can be detected neither with a tape measure nor with an optical measurement and still is present in reality. Only from a neutral standpoint we can succeed to recognize the actually existing curvature of space (fig. 28.6 A).
An example is the duration of the sunshine at the equator, which is longer than can be expected from the spherical form of the Earth. This reveals, how the Earth is bending towards the sun (see also chapter 6.7).
A further example is the influence of the field on the orbital velocity of the Earth measured in meters per second. Here also the meter at daytime is smaller than in the night, for which reason the Earth is moving slower on the side turned towards the sun, like a track vehicle, which drives a turn, if the chain at the inside runs slower than on the outside. If the Earth describes an orbit around the sun. then this circumstance has to do nothing at all with centrifugal force or with a force of attraction of the sun. The circular motion simply and solely is a result of the field influence of the sun<iii>.

The force idea proves to be a pure auxiliary description. In the context of Newtonian mechanics the force plays a central role. Without question it is a very efficient and subjective perceptible description, which still isn't able to reproduce the physical reality in an objective manner. What keeps the planets into their orbit is only the field of the sun, which we call gravitational field and not some force! But of which kind is the gravitation and the field, which causes masses to come closer together and following our subjective observation attract each other (fig. 28.6 B)?

<i>: O. E. Rossler: Endophysics, the World as an Interface, World Scientific Publishing Co. 1998, Kap. 10, S. 87-112, mit Ubersetzungen aus <ii>:

<ii>: R. J. Boscovich: De spatio et tempore, ut a nobis cognoscuntur, 1755.

The length measure (the distance L between the spheres)<i> is determined by the field strength:

$$\boxed{E, H \sim 1/L^2} \quad (28.18)$$

A. Charged mass points (electrons, positrons, ions,...):



B. Uncharged mass points (neutrons, atoms, ...):



Fig. 28.7: Observation of a mutual force of attraction because of the effect of the fields on the distance measure.

<i>: Repetition of part 1, chapters 6.7 - 6.9 and part 2, chapters 10.4 and 15.2

28.7 Derivation of the gravitation

In fig. 28.6B the relation between the field influence and the observed force of attraction of two mass bodies is represented. If I in my mind for instance "switch on" the field lines of both bodies, which are placed at distance L, then the fields according to equation 28.18 reduce the measure L and optically come each other closer. With increasing proximity the field line density increases, so that L further decreases. We observe a mutual attraction, which lets both bodies move towards each other.

In fig. 28.7A the two bodies carry an electric charge. For different polarity the field lines as is well-known run from the positive pole to the negative pole, to bundle up there. As a matter of principle also here an attraction can be expected, which is called electromagnetic interaction. For the reason of the bundling up of the field lines this effect however will turn out to be considerably stronger. Hence the electromagnetic interaction is for many powers of ten more powerful than the gravitation.

Furthermore there also can occur repulsion, if in the case of like charge the field lines are bent aside and between the two bodies an area is formed, where the field tends towards zero and the distance measure L (according to eq. 28.18) as a result towards infinity. The electromagnetic interaction theoretically indeed reaches to infinity. Responsible are the open field lines arising from a charged body.

Now every charged body in addition has a mass, with which it takes part in the gravitation. Let's remember the comparison of the derivations. The Maxwell theory teaches us that in the static case E- and H-field are decoupled, because each time the other field disappears. Even if as a result of the unipolar induction for every open field line the other one is taken to be standing perpendicular to the open field line, then this other line just wraps around the open field line and forms a closed-loop field line. In that way it can't be influenced anymore from the outside and can be neglected, so goes the doctrine, which is drawn from the Maxwell theory (fig. 27.5).

This is a fatal error in reasoning! The equation 28.19 naturally is valid for open field lines in the same manner as for closed ones. These fields also lead to an observable force of attraction. If of course exactly those fields are neglected, which are responsible for the gravitation, then we need not wonder, if we don't understand the gravitation and the nature of this interaction!

The influence of the closed field lines responsible for the gravitation is due to the missing bundling up of the lines correspondingly weak. Secondly these can't exist a force of repulsion due to the missing ability to influence closed field lines from the outside and third it can be recorded that all charged bodies also have a mass. All three statements of the field lines model perfectly cover the physical reality.

Fig. 28.7 B shows uncharged bodies, for which both the field lines of the E-field and of the perpendicular to them arranged H-field are closed-loop. Such bodies, like e.g. neutrons or whole atoms without charge behave electrically neutral to the outside, but have a mass for the reason of the closed field lines, whereby the field lines of the H-field dominate those of the E-field[i].

<i>: Repetition of K. Meyl: EMEC part 1, chap. 6.8 + 6.9, part 2 chap. 15.1

Dual field approach / The Maxwell field



E = neglectible,

B = constant.

E and **B** are coupled / decoupled (approximation)

The closed field lines by no means are without influence: They cause the **gravitation** !	If the Maxwell field neglects the field factor, which leads to the gravitation, it isn't astonishing, if the gravitation remains not understood!

• The following physical standpoints can be distinguished:		
subjectivity (laboratory physics, observable)	**relativity** (mediator role) (transformation)	**objectivity** (not observable)
• Exemplary theories and their representatives:		
Newton Maxwell	Poincaré Einstein	Boscovich *(dual approach)*
• With the associated transformation:		
Galilei-transf. for $c = \infty$	Lorentz-transf. c = constant	*(new transf.)* c = variable

Fig. 28.8: Physical standpoints

28.8 From subjectivity to objectivity

With the field lines interpretation, which by the way already preferably was used by Faraday, the gravitation proves to be an until now neglected influence of the electromagnetic field. With that for the first time also the grand unification of the interactions was successful. The long sought-for unified theory with that for the first time comes within reach.
The derivation has made it possible to mathematically secure the theoretical working model of Boscovich. Already 1755 Boscovich points out the optical deception, which our observation underlies, if absolute orders of magnitude in our neighbourhood should change and our perception would change along. Then also all metric and optical measurement results would underlie this change. Following the idea of Boscovich I distinguish between subjectivity and objectivity.

The relativity is a compromise lying between both points of view, where a neutral standpoint is strived for, which lies outside the events. And from this standpoint the objectively taking place events are being observed. The theory of relativity consequently is a pure observer theory with strongly restricted scope on the basis of the Lorentz-transformation.

Theories of classic physics, like e.g. Newtonian mechanics, fall in the domain of subjectivity. The results and regularities are won in a terrestrial laboratory if possible isolated from the environment, where they have absolute validity. Here the Galilei-transformation is valid.
But if these subjectively won laws are applied to the microcosm in quantum physics or to the calculation of cosmic observations, one fast hits limits. The better the resolution of the microscopes and telescopes gets, the clearer the „outside" observer realizes, how much the laws of classic physics lose their validity.

Astrophysics successfully reaches for the theory of relativity, which with the curvature of space in the vicinity of mass centres delivers useful explanations. Here the dependence of the spatial dimensions on the field already could be established. In contradiction to that this fundamental relation is said to play no role whatsoever in quantum physics, or in all terrestrial laboratory experiments. But with which right may physical regularities from one domain be ignored in others? There only can exist one physics and that should be sought for!

What we need is objectivity! Behind all the apparently disconnected phenomena of physics work quite simple laws, which can't be observed and are until now not recognized by us. Objective physics in the words of Goethe is the one, which holds the world together in the heart of hearts. I call this, already by Boscovich suggested point of view, theory of objectivity. The access to the model domain of objectivity must be made mathematically by means of a transformation, since it is blocked for us by means of measurements or observations (see chapters 6.15-6.19). The transformation back into the observation domain must be made according to the same mathematical relations (fig. 28.9). In this way the quantum properties of the elementary particles can be calculated with high accuracy and agreement with the values, which until now only could be measured (chapter 7).



Approach: $\boxed{r = c \cdot t}$ (determine distance by signal prop. time)
(27.23)

$\boxed{dr = c\cdot dt + t\cdot dc}$ (total differential for a change)
(27.24)

$$\boxed{c = \frac{dr}{dt} - t\cdot \frac{dc}{dt}} \quad \text{resp.} \quad \boxed{t = \frac{dr}{dc} - c\cdot \frac{dt}{dc}} \qquad (27.25)$$

$$c = \frac{dr}{dt} - t\cdot\frac{d^2r}{dt^2} + t^2\cdot\frac{d^3r}{dt^3} - t^3\cdot\frac{d^4r}{dt^4} + t^4\cdot\frac{d^5r}{dt^5} - \dots \qquad (27.26)$$

resp.

$$t = \frac{dr}{dc} - c\cdot\frac{d^2r}{dc^2} + c^2\cdot\frac{d^3r}{dc^3} - c^3\cdot\frac{d^4r}{dc^4} + c^4\cdot\frac{d^5r}{dc^5} - \dots \qquad (27.27)$$

The Taylor-series (27.26 and 27.27) breaks off after the first term, if

c = constant	resp.	t = constant	
$dr = c\cdot dt$	resp.:	$dr = t\cdot dc$	
$\Delta r = c\cdot\Delta t$	resp.:	$\Delta r = t\cdot\Delta c$	(27.28)
theory of relativity		**theory of objectivity**	
$\Delta r \sim \Delta t$	resp.:	$\Delta r \sim \Delta c$	means:

from:	length contraction	variable speed of light
follows:	time dilatation	dependency of meter measure
	for absolute speed of the light	for absolute time

observation domain
(measurable)
model domain
(can only be calculated)
x(r)
M{x(r)}
Model transformation of the length measures

Fig. 28.9:____ Theory of relativity and theory of objectivity and the model transformation between both physical standpoints

---

<i>: Repetition of part 1, fig. 6.16

28.9 The objective standpoint

The question is asked how one gets to an objective physical standpoint, which in addition evades every observation? The way leads over a transformation, to which all perceptible and measurable relations must be submitted.
If we for instance measure the distance r to a point light source, then the propagation of the light c and the propagation time t determine the distance measure r = c*t
If there occurs a little change of the distance, then two causes should be considered: Either the propagation time or the speed of light have changed somewhat. With that the two possible standpoints already would have been found.

The relativistic standpoint, which proceeds from the assumption of the speed of light being constant, says: the propagation time varies and we are dealing with a clock problem. If namely for relativistic velocities a length contraction occurs, then from that necessarily follows a time dilatation.
But actually no specific statement can be made about the constancy of the speed of light, besides that we look at, measure and scan everything with c and hence only observe the constancy. With that the theory of relativity remains a pure observer theory, exactly as Einstein originally called it into existence. This standpoint follows the motto: What can't be observed also doesn't need to interest the physicist.

The objective standpoint strives for more, for a description of the actually taking place processes. This time we proceed from the assumption of a universal and constant time with the argument: The time measure is an immutable definition and the physicist, who dictates this, himself determines what is simultaneousness. Then there also is no place for time travel and for clocks going wrong.
Therefore the speed of light can take all possible values always in strict proportionality to the length measures. Thus the measured length and distance measures should be transformed and that in the end is the unit ,,meter", which should be replaced by an objective measure.

With that the necessary transformation for variable c would be outlined. This transformation will be enqueued in the file of the big transformations. From it the Lorentz-transformation for c = constant emerges as a special case, like already from that transformation the Galilei-transformation follows for $c = \infty$. How now the relation of the subjective to the objective ,,meter" should be determined; by means of the relation of the relevant fields (eq. 28.17) or by means of the square root of Lorentz (eq. 28.16), over that should be worked and spoken. We already have successfully gone through it in a concrete example (chapter 7).

Every theory is judged according to its expressiveness. Ending this chapter the statements and derivations hence again are compared. On the one hand the Maxwell theory and from that the theory of relativity can be derived from the new approach, on the other hand a long list follows, which can't be connected with the Maxwell equations, like e.g. the gravitation. For instance the neutrino and all other elementary particles with all their specific quantum properties are derived (chapter 7), free and easy fundamental laws result, like the law of conservation of energy, and even the temperature spills its until now kept secret (chapter 8.3). Remains the conclusion: With no other approach according to the textbooks until now the efficiency of the new approach could be obtained.

• From the dual field-theoretical approach are derived:	• From Maxwell's field equations can be derived:
=> Maxwell's field equations	=>0
=> Quantum properties of the elementary particles	=>0
=> Neutrino (as an oscillating ring-like vortex)	=>0
=> Gravitation (as a result of closed field lines)	= > 0
=> Unified theory (grand unification of all interactions)	=>0
=> Temperature (as an oscillation of size depending on field)	=>0
=> Law of conservation of energy (and many other fundamental laws of physics)	=>0
=> Theory of objectivity	=> Theory of relativity

Fig. 28.10: Comparison of the efficiency of the approaches (final balance)

29. Mathematical gleanings

If, proceeding from the new field-physical approach, well-known and accepted theories are derived as special cases, this on the one hand can be valued as evidence for the correctness of the approach. On the other hand the new approach in part significantly influences the interpretation of the derived theories. That can involve a rethinking, with which not insightful people have difficulties, if for instance quantum physics, thermodynamics or the gravitation become partial aspects of electromagnetism. Over and above that are hidden many new thing in the new approach, which are there to discover. To that are counting among others the potential vortices and the scalar waves. One can work out these phenomena physically or mathematically, where the latter way as a rule is the faster one. Hence the summary shall be concluded with a kind of mathematical gleanings.

29.1 General and special theory of relativity

Albert Einstein distinguishes between general and special theory of relativity. Whereas the special (SRT), still is linked tightly with the prerequisites of the Lorentz-transformation, the general (GRT), deals with an extension to arbitrary systems, which mustn't be inertial systems. I would like not to dwell upon the GRT, as Einstein designed it, and merely notice that every generalization represents a possible source of errors and has to be well founded.

In the case of our derivation, the general case as it were resulted of its own accord. Let's turn back: If the root of Lorentz still was a component of the derived field dilatation (28.15) and equally of the length contraction (28.16), then it fell out in the comparison of both results (28.17). With that the important result, the proportionality (28.18), which among others results in the gravitation, becomes independent of the speed of light and the relative velocity v. This last step is obvious and still completely new. It cannot be found at Einstein, who in another way finds his GRT and his description of the gravitation. Even if here is striven for the same goal, then deviations in the result cannot be excluded because of the differences in the derivation, for which reason I additionally mark the by me derived general relativity (GRT'), to avoid confusion.

Influence of the Lorentz-transformation in the:
SRT (special theory of relativity): one-dimensional,
GRT' (general theory of relativity): three-dimensional, to a large extent corresponding to the GRT of Albert Einstein,
GOT (general theory of objectivity)



Discussion of the root of Lorentz $\sqrt{1 - v^2/c^2} = \sqrt{1 - \beta^2}$ with $ß = v/c$
resp. the γ-factor: $\gamma = 1/\sqrt{1 - v^2/c^2}$ (29.1)

Being transformed are:		SRT	GRT'	GOT
Length measures (length contraction eq. 28.16)	L [m]	$\sim 1/\gamma$	$\sim 1/\gamma$	$\sim 1/\gamma$
Areas (circular motion)	A [m^2]	$\sim 1/\gamma$	$\sim 1/\gamma^2$	$\sim 1/\gamma^2$
Volumes (vortical motion)	V [m^3]	$\sim 1/\gamma$	$\sim 1/\gamma^3$	$\sim 1/\gamma^3$
Time measures	t [s]	$\sim 1/\gamma$	$\sim 1/\gamma$	= const.
Velocities	v [m/s]	= const.	= const.	$\sim 1/\gamma$
($v = L/t$)	c [m/s]	= const.	= const.	$\sim 1/\gamma$
Constants of material	ε [As/Vm]	= const.	= const.	$\sim \gamma$
($\varepsilon \cdot \mu = 1/c^2$)	μ [Vs/Am]	= const.	= const.	$\sim \gamma$
Relativistic mass (increase in mass)	m [kg] [=VAs^3/m^2]	$\sim \gamma$	$\sim \gamma$	$\sim \gamma^2$
Energy	W [VAs]	$\sim \gamma$	$\sim \gamma$	= const.
Energy density ($w = W/V$)	w [VAs/m^3]	$\sim \gamma^2$	$\sim \gamma^4$	$\sim \gamma^3$
E-, **H**-field strength	**E** [V/m]	$\sim \gamma$	$\sim \gamma^2$	$\sim \gamma$
($w = (\varepsilon \cdot E^2 + \mu \cdot H^2)/2$)	**H** [A/m]	$\sim \gamma$	$\sim \gamma^2$	$\sim \gamma$
Power density (Poynting vector $\mathbf{p} = \mathbf{E} \times \mathbf{H}$)	**p** [VA/m^2]	$\sim \gamma^2$	$\sim \gamma^4$	$\sim \gamma^2$
D-field, **B**-field	**D** [As/m^2]	$\sim \gamma$	$\sim \gamma^2$	$\sim \gamma^2$
($\mathbf{D} = \varepsilon \cdot \mathbf{E}$; $\mathbf{B} = \mu \cdot \mathbf{H}$)	**B** [Vs/m^2]	$\sim \gamma$	$\sim \gamma^2$	$\sim \gamma^2$
Power	P [VA]	$\sim \gamma$	$\sim \gamma^2$	= const.

Fig. 29.2 Transformation table between SRT, GRT' and GOT

29.2 Transformation table

Let's speak again about the difference to the special relativity (SRT). This so to speak deals with the one-dimensional case of the uniform motion of a reference system in x-direction ($v = v_x$), as specified by the Lorentz-transformation, where only the x-components and not those in y- or z-direction are being transformed. As already mentioned this is a purely theoretical case, which in practice occurs next to never. Normal is circular and vortical and with that accelerated motion, where the velocity component permanently changes its direction.

The derived result of the general relativity (GRT') does justice to this circumstance. Even if this at first only has been derived for the x-direction it nevertheless is valid equally in y- and z-direction. It even remains valid for the case that we base on a path of arbitrary form of a spatial field vortex. In this case some components continually occur in all directions of space, so that the relative velocity v as already the speed of light c loses its vectorial nature. With that the transition of the SRT to the GRT is carried out. By means of the spatial swirling the electric and magnetic field pointers at the same time turn into scalar factors, by taking over the function of the aether. Let us remember that even Einstein in his GRT was forced to again introduce the aether, which in the SRT still was unnecessary.

It therefore makes a difference in the transformation of physical factors, if we base on a one-dimensional (SRT) or a three-dimensional spatial description (GRT). Length measures in x-direction in both cases must be converted using the root of Lorentz. Usually the relativistic γ-factor is introduced, which is inverse to the root of Lorentz

$$\gamma = 1/\sqrt{1-v^2/c^2}) \qquad \text{with } x_o/x = \gamma \quad (29.2)$$

If thus individual length measures would be subject to a length contraction following the γ -factor, then a volume V according to the SRT must be transformed with γ, according to the GRT' however with γ^3.
As is well-known a relativistic increase in mass is converted with the γ-factor and in the same manner the to that proportional energy $E = m\ c^2$. If we however correlate the energy to the volume V and in that way determine an energy density w, then the difference between SRT ($w \sim \gamma^2$) and GRT' ($w \sim \gamma^4$) again has its maximum effect.
A relation to the field factors of E- and H-field is for instance provided by the energy density of a wave field
$$w = (\varepsilon \cdot E^2 + \mu \cdot H^2)/2 \quad (29.3)$$

According to that the field strengths in the one-dimensional case of the SRT should be converted with the γ-factor, in the case of the GRT' however with γ^2, in accordance with the derivation in chapter 28. This circumstance willingly is overlooked, although it only concerns the textbooks and the today valid theory of relativity. I however point to the difference, since it does make a difference if we start with the SRT or the GRT when we change to the general theory of objectivity (GOT).

In the domain of the GOT all length measures should be transformed. The respective dimension gives information with which power the γ-factor occurs (fig. 29.2). The unit meter is responsible for that.



Discussing the root of Lorentz $\sqrt{1-\beta^2} = 1/\gamma = \sqrt{1-(v^2/c^2)}$

mathematical consideration:	$v = 0$	$v < c$	$v = c$	$v > c$
Abbreviations: $\beta = v/c$	$0 <$	$\beta < 1$	$\beta = 1$	$\beta > 1$
and: $\gamma = 1/\sqrt{1-\beta^2}$	$1 <$	$\lvert\gamma\rvert < \infty$	$\gamma = \pm\infty$	imaginary
and: $\gamma^2 = 1/(1-\beta^2)$	1	positive	$\gamma = +\infty$	negative
and: $\gamma^4 = 1/(1-\beta^2)^2$	$1 <$	positive	$\gamma = +\infty$	positive
Examples: Increase in mass, energy $\sim \gamma$ for SRT and GRT	1	positive	$\pm\infty$	complex
Field strength in GRT': $\mathbf{E}, \mathbf{H} \sim \gamma^2$ and mass in GOT: $m \sim \gamma^2$	$1 <$	$\mathbf{E}, \mathbf{H} < \infty$ positive	$+\infty$	$\mathbf{E}, \mathbf{H} < 0$ negative
Energy-, power density $\sim \gamma^4$ (Poynting vector) in GRT:	$1 <$	$\mathbf{P} < \infty$ positive	$\mathbf{P} = +\infty$	$\mathbf{P} < \infty$ positive

Fig. 29.3 Discussion concerning the root of Lorentz

- The special theory of relativity SKT only is defined for $v < c$
- For v • c particles with a complex mass, but with a real energy density (according to GRT') would result.
- From the point of view of the theory of objectivity (GOT) the mass should be taken negative-real (neutrino?).

29.3 Discussion concerning the root of Lorentz

Fig. 29.2 forms the basis for the transformation in the domain of the GOT, the general theory of objectivity, where it plays a role, if a subjectively measured factor should be converted from the laboratory domain or a relativistic factor according to the SRT or the GRT'. The given proportionalities thereby should be put in the respective relation. In this way results the respective valid instruction for transformation on the basis of the root of Lorentz.

Let's take a critical look at the root of Lorentz. The velocity v occurring in it, of whatever this may consist, is depending on the field according to equation 28.14 + 28.15. It strictly speaking wouldn't be constant anymore and wouldn't belong in a general instruction for transformation at all. Only, what is valid for v, is valid to the same extent for c. Since only the proportion of v/c occurs in the root of Lorentz every influence depending on field or of other nature will have no effect on v/c and the value of the root of Lorentz. It in any case will retain its value. It fulfills for itself the condition of the Lorentz invariance. According to that in the case of the relative velocity v it doesn't depend on the absolute value, but only on the relation to the speed of light. In addition the restriction to values of $v < c$ is normal, if the speed of light is seen as an upper limit. Let's first purely mathematically draw a case distinction for different velocity domains of v. For $v = 0$ the root of Lorentz becomes one and the Lorentz transformation turns into the Galilei transformation.

Connected to this is the today well-known and technically used domain up to the limit of $v = c$. It virtually is impossible to accelerate a mass particle to the speed of light, since mass, field and energy would grow towards infinity, as is clear from the table (fig. 29.2). Particles as fast as light, like photons, hence cannot have a mass. At $v = c$ a singularity is present.

In a field theory, which also deserves this name, however an upper limit must not be present. Hence also the case for $v > c$ should be required theoretically. Only later we will be able to judge if this makes sense physically. We at first only want to examine the case mathematically. Mass, field and energy now again have a finite value, there however results a complex, purely imaginary mass, a negative field and doing so, as already before a positive energy and power density.

There sometime has been the textbook opinion that it is physically impossible to fly faster than sound. This erroneous statement even could be proven „scientifically", because such a supersonic airplane would fly off the observation space and with that wouldn't be real anymore, thus from a mathematical viewpoint would be complex. Anyone, who in New York gets off a Concorde, can confirm that everything at any moment of the flight was real. Only the observer is deceived, if the airplane flies somewhere else, than he perceives it. Is the speed of light also such a „sonic barrier", which by the majority of the scientists since Einstein until today still is thought to be insurmountable?

How should one physically imagine a complex mass? Let us remember the alternating current teachings, where it is normal to work with complex values, since the mean values of the oscillating alternating currents, tension voltages and fields are zero. Calculating with mean values would result in zero energy and power. Hence complex factors are introduced and the root mean square values are calculated and measured instead of the mean values. Could a complex mass analogously not concern an oscillating particle, a particle, which in addition is faster than the light?

- Physical example:

neutrino = mean of the oscillating mass ≈ zero
RMS value of the complex mass ≠ zero
E- and H-field with inverse sign
carrier of positive energy and power
ν -model: ring-like vortex oscillating from e^- to e^+ [i]



Examples from the general theory of relativity (GRT):

(28.16): length contraction $L \sim 1/\gamma = \sqrt{1-(v^2/c^2)}$

(6.19): increase in mass $m \sim \gamma = 1/\sqrt{1-(v^2/c^2)}$

(6.6,28.15) field dilatation $\mathbf{E} \sim \mathbf{H} \sim \gamma^2 = 1/(1-v^2/c^2)$

Fig. 29.4: Root of Lorentz for speeds faster than light (v > c)

29.4 Mathematical derivation of the neutrino

In the domain of speeds faster than light, for v > c, the power series (28.12) does not converge anymore and every observer theory and every observation (fig. 28.4) will fail, because particles faster than light run away of their own visible appearances. Every measurement and every observation inevitably is behind and hardly can be assigned to the actual cause. That way for instance measured neutrino events are being connected with celestial observations, with which they haven't got anything to do at all.
If we however describe the domain v > c in the complex plane, then astonishing results are found, which could be verified physically: a complex length dilatation with increasing velocity goes along with a loss of complex mass. The oscillating fields, energy and power density however would be real with negative sign.
Thus there would result particles carrying energy with an oppositely poled field, with an oscillating mass and if necessary also an oscillating charge. Without static mass and charge these particles hardly would interact with normal matter, which leads to an enormous ability of penetration. The only physical particles, which have such a property, are the neutrinos. With that a usable and an extremely efficient model description has been found for these particles. Also the energy of these particles can be calculated, which has considerable orders of magnitude and is available as an energy source everywhere and any time.

If for instance in a converter for space energy a neutrino should be converted into a resting charge carrier (with v = 0), then two steps are necessary (see part 2 of this series of books):

1. First the neutrino must be slowed down to 1.414 times the speed of light (fig. 28.9). Doing so energy is spent and not won! The converter for instance can cool down.

2. Afterwards the characteristic rotation of its own, with which the ring-like vortex spins around itself by permanently putting its inside to the outside and vice versa, has to be taken away from the neutrino. In that way the vortex centre is closed and the particle acquires localization. It becomes a charge carrier.

Even if the representation in the complex plane represents only an auxiliary description, the model nevertheless seems to be efficient, because despite its complex mass and charge the neutrino nevertheless carries a real energy. It in any case is represented in that way to an observer, who measures the relation with the speed of light, who in the relativistic scheme of things scans the relation.

Today, as already said, even the sonic barrier has become permeable and no scientist dares to physically deny this fact and even prove his mistake mathematically anymore. No, on the contrary, he always did know that as an expected consequence the sonic barrier runs after the supersonic plane. The once physically unthinkable and scientifically fought has become normality.
What should hinder an oscillating particle, like a neutrino, to be faster than the light? Some time one also will accustom to that.

- Starting-point:
  the fundamental field equation
  (derivation in chapter 27.10)

$$-c^2 \cdot \mathrm{rot}\ \mathrm{rot}\ \mathbf{B} = \frac{\partial^2 \mathbf{B}}{\partial t^2} + \frac{1}{\tau_1}\frac{\partial \mathbf{B}}{\partial t} + \frac{1}{\tau_2}\frac{\partial \mathbf{B}}{\partial t} + \frac{\mathbf{B}}{\tau_1 \tau_2} \qquad (27.26)$$

- Example:



Spherical propagation of an electromagnetic wave in space

- The number π: $\pi = 3.14159$

straight	$\pi \cdot$	**circular**		**spherical**
r	$\cdot\ \pi \cdot 2 =$	$2r \cdot \pi$	$\cdot\ 2r =$	$\pi \cdot r^2 \cdot 4$
line		**circumference**		**surface**
r	$\cdot\ \pi \cdot r =$	$r^2 \cdot \pi$	$\cdot\ r \cdot 4/3 =$	$\pi \cdot r^3 \cdot 4/3$
line		**area**		**volume**

(29.4)

Fig. 29.5: The number π

29.5 Universal constants and constants of nature

Strictly speaking fundamental or universal constants can't exist in pure field physics at all. For the example of the speed of light has been shown that it merely are measurement constants (fig. 6.11). The numerical size is a consequence of the definition. The speed of light for instance has the today well-known value as a consequence of the fixing of a length unit and a time unit. If we change a unit, if we take „feet" instead of ,.meters", then another value results. If however the velocity changes, then the reference measure of our gauge changes along and we get the identical reading. Electric and magnetic field constant depend directly on the speed of light c $(\varepsilon \cdot \mu = 1/c^2)$, which solely by the fixing of the electric units takes a certain value. The inner structure of the potential vortices leads from Planck's quantum of action, to the elementary charge and to the countless atomic „constants", which all objectively seen aren't constants at all. They virtually all can be derived (chapter 7).

Sooner or later even the last natural scientist will realize, that nature does not provide "constants" at all. If „constants of nature"' did exist, as listed in textbooks and encyclopaedias, then they aren't consistent with causality, since we don't know the cause, why the factor should have exactly this size and no other. Behind every so-called constant of nature unnoticed is hiding a physical closed loop conclusion.

Fundamental constants only exist in mathematics. This can be shown very nicely for the example of the „fundamental field equation" (eq. 27.26), which has been derived from the new field theoretical approach (fig. 27.10). It is the description of waves and vortices in space and time, which indeed carries features of a „world equation". If one searches this equation for fundamental constants, then one altogether can find three: the number π, the number e and the Golden Proportion Φ. The speed of light c however occurs only as the mathematical factor characterizing the wave as a result of the defined units. If one would choose the units different, c as well could be made 1. With the fundamental numbers that procedure won't work. They don't depend on the definition of the units!

Let's consider the number π. The number π occurs every time as a proportionality factor if we transition from a straight line to a circle or further to a sphere, from a line to the circumference or further to the surface of a sphere and exactly so from a line to the area of a circle or further to the volume of a sphere. Since for all the special cases, which are derived from the fundamental field equation (the structure of the elementary particles, the atomic structure and in the same way again in the universe), the spherical symmetry dominates, the mathematical solution is determined by a corresponding spatial configuration of the number π. It has its cause neither in a physical relation of interactions, nor in the choice of the units, but only in the geometry.



The number e: $e = \lim_{n \to \infty} (1 + 1/n)^n = 2.71828$ (29.5)

for $n = 2$ is $(1+1/n)^n = 1.5^2 = 2.25$

for $n = 1$ is $(1+1/n)^n = 2^1 = 2$

for $n = 0.5$ is $(1+1/n)^n = \sqrt{3} = 1.73$

for $n = 0$ is $(1+1/n)^n = \infty^0 = 1$

for $n = -0.25$ is $(1+1/n)^n = 1/(-3)^{0.25}$ *gives a complex solution!*

for $n = -0.5$ is $(1+1/n)^n = 1/\sqrt{-1} = -i$, thus again complex!

for $n = -0.75$ is $(1+1/n)^n = 1/(-3)^{0.75}$ as well complex!

for $n = -1$ is $(1+1/n)^n = 1/0 = \pm\infty$

for $n = -2$ is $(1+1/n)^n = 2^2 = 4$

Fig. 29.6: Forming the limiting value of the number e

29.6 The fundamental number e

In the fundamental field equation (27.26) a further irrational number is concealed, the number e. Whereas the left side of the equation (a) gives the spatial distribution, the right side (b-e) describes the temporal course of events. Besides the term constant in time (e) also first time derivations (c and d) and a second time derivation (b) occur.
For a solution of this differential equation a function should be found, the derivations of which are again the function itself. This condition strictly speaking is fulfilled only by one single function, the e-function.
We used this property of the e-function already for the derivation of the Schrodinger-equation in chapter 5.6 and 5.7. There with the help of the e-function an approach was chosen, which leads to the well-known solutions of the Schrodinger-equation, which are considered to be secured experimentally. With that the number e controls the temporal relations of the fundamental field equation.

It might be helpful to take a closer look at the origin of the number e. It results from a consideration of limiting values: _

$$e = \lim_{n \to \infty} (1 + 1/n)^n = 2.71828 \qquad (29.5)$$

If one varies n and allows different values between $-\infty$ and $+\infty$, then a strange behaviour is showing. One indeed more and more approaches the well-known value of e = 2.72, as dictated by the definition of limiting values according to equation (29.5), the larger n is chosen. But in the opposite direction it looks less tidied:

$$\begin{array}{llllllll}
 & \text{for} & n = 1 & \text{is} & (1+1/n)^n & = 2^1 & = 2 & \\
 & \text{for} & n = 0{,}5 & \text{is} & (1+1/n)^n & = \sqrt{3} & = 1.73 & \\
 & \text{for} & n = 0 & \text{is} & (1+1/n)^n & = \infty^0 & = 1 & \\
 & \text{for} & n = -0{,}5 & \text{is} & (1+1/n)^n & = 1/\sqrt{-1} & = -i\text{, thus complex!} & \\
\text{and} & \text{for} & n = -1 & \text{is} & (1+1/n)^n & = 1/0 & = \pm\infty & (29.6)
\end{array}$$

Since the e-function inside the fundamental field equation is responsible for the temporal sequence, the interpretation of my colleague Prof. Dr. Preussker<i> gets a deeper sense. He says, it starts outside our imagination (at n = -1). Afterwards at first big chaos prevails. Mathematically seen some imaginary solutions arise. Finally the system is putting in order (from n = 0), to more and more approach the value e = 2.72 .

The number e is of fundamental importance and thereby holds unforeseen secrets. More mysterious and until now entirely misunderstood is the meaning of the Golden Proportion. Also this indivisible number can be found in the fundamental field equation. Since it is less known and more complicated to handle, it first shall be introduced.

<i>: H. Preussker: Der Wirbelring, Halstenbeck 2002


Graphical construction at a right-angled triangle (Pythagoras):
h
x
$\frac{a}{2}$
x
y
a
Golden Proportion of length a = x + y :
$\frac{x}{a} = \frac{y}{x}$
with the proportion:
$\frac{x}{a} = \Phi = 0.618$ (29.9)
and
$\frac{a}{x} = \frac{1}{\Phi} = \Phi + 1 = 1.618$ (29.10)
The pentacle
x
y
x
a

Fig. 29.7: Constructions for the Golden Proportion

29.7 The pentacle

During his visit of the Egyptian pyramids already two and a half thousand years ago the history writer Herodotus by his guide had been called attention to the circumstance that the Golden Proportion has been realized for the proportions of scale.
In the case of the pyramid of Cheops it even has been taken into account manifold, as we know today, but we hence still don't know why. There must be an intention behind it.
Anyway a coincidental use can be eliminated, since the Golden Proportion cannot be handled in an easy way, neither graphically nor mathematically.
The Golden Proportion in addition plays an important role in the whole ancient architecture and not only there. It for instance occurs in the case of a very old symbol, the five edged star, which we can draw with one line without taking off. The well-known symbol also is called pentacle.

In the case of the Golden Proportion a straight line a is divided into two unequal halves. The larger half x thereby is 61.8 % of the straight line a. Already Pythagoras has researched and teached about this. Maybe he did know more about the purpose of this classification than all the mathematicians, archaeologists and art historians of today together.
For a graphical solution we assume a right-angled triangle. The task is to divide one leg of length a = x + y according to the Golden Proportion into two parts, the larger part x and the smaller part y. The second leg has the length a/2. According to the theorem of Pythagoras the length of the hypotenuse h is

$$h = \sqrt{a^2 + (a/2)^2} = (a/2)\cdot\sqrt{5} \quad (29.7)$$

If the length of the second leg (a/2) is subtracted from the hypotenuse, then this is the sought length x = h a/2:

$$\boxed{x = (a/2)\cdot(\sqrt{5} - 1)} \quad (29.8)$$

The proportion of both length measures gives the constant Φ, which is characteristic for the Golden Proportion:

$$\boxed{\Phi = x/a = (\sqrt{5} - 1)/2 = 0.618} \quad (29.9)$$

This proportional number has a special property. If one adds 1 to the number and forms the reciprocal value of that, then the same number comes out again, thus:
with Φ = x/a : with a = x + y :

$$\boxed{\Phi + 1 = \frac{1}{\Phi}} \quad \text{and} \quad \boxed{\frac{x}{a} + 1 = \frac{a}{x}} \quad \text{resp.} \quad \boxed{\frac{x}{a} = \frac{a - x}{x} = \frac{y}{x}} \quad (29.10)$$

With that the ratio of the length a and the larger section x is the same as the ratio of x and the smaller section y.



- Starting-point: the fundamental field equation

$$\boxed{-\,c^2\cdot\text{rot rot }\mathbf{E} = \frac{\partial^2\mathbf{E}}{\partial t^2} + \frac{1}{\tau_1}\frac{\partial\mathbf{E}}{\partial t} + \frac{1}{\tau_2}\frac{\partial\mathbf{E}}{\partial t} + \frac{\mathbf{E}}{\tau_1\tau_2}} \quad (27.26)$$

- for the special case: because of missing conductivity ($\sigma = 0$)

e.g. in air no eddy current damping: $\sigma/\varepsilon = \boxed{(1/\tau_1) = 0}$

- and no currents (eq. 27.15+27.16): $\mathbf{j} = \sigma\cdot\mathbf{E} = -\,\mathbf{v}\cdot\varepsilon\cdot\text{div }\mathbf{E} = 0$
- resp. $\Delta\mathbf{E} = \text{grad }\cancel{\text{div }\mathbf{E}} - \text{rot rot }\mathbf{E} = -\,\text{rot rot }\mathbf{E}$

$$\Rightarrow \quad \boxed{c^2\cdot\Delta\mathbf{E} = \frac{\partial^2\mathbf{E}}{\partial t^2} + \frac{1}{\tau_2}\frac{\partial\mathbf{E}}{\partial t}} \quad (29.11)$$

Standard case of a wave damped with potential vortices

In the case of a perturbation this wave rolls up to a vortex, with

- the vortex radius r
- the swirl velocity $c = \omega\cdot r$
- the angular velocity $\omega = 1/\tau_2 = c/r$

The vortex itself runs with the velocity $v(x(t)) = dx/dt$ as a longitudinal wave in direction of the **E**-field: $\Delta\mathbf{E} = \partial^2\mathbf{E}/\partial x^2$

$\Rightarrow \quad \partial\mathbf{E}/\partial t = (\partial\mathbf{E}/\partial x)\cdot(dx/dt) = v\cdot\partial\mathbf{E}/\partial x$ and

$\partial^2\mathbf{E}/\partial t^2 = v^2\cdot(\partial^2\mathbf{E}/\partial x^2)$; ($\partial v/\partial t = 0$, since not accelerated)

$$\Rightarrow \quad \boxed{c^2\cdot\partial^2\mathbf{E}/\partial x^2 = v^2\cdot(\partial^2\mathbf{E}/\partial x^2) + v\cdot(c/r)\cdot\partial\mathbf{E}/\partial x} \quad (29.12)$$

- with the exponential approach: $\mathbf{E} = \Psi\cdot e^{-x/r}$ are:

$\Rightarrow \quad \partial\mathbf{E}/\partial x = -\,(1/r)\cdot\mathbf{E}$ and $\partial^2\mathbf{E}/\partial x^2 = (1/r^2)\cdot\mathbf{E}$

$$\Rightarrow \quad \boxed{(c^2/r^2)\cdot\mathbf{E} = (v^2/r^2)\cdot\mathbf{E} - (v\cdot c/r^2)\cdot\mathbf{E}} \quad (29.13)$$

- resp.: $\boxed{c^2 = v^2 - v\cdot c}$ (29.14)

Fig. 29.8: The calculation of an electromagnetic wave, which is rolling up to a potential vortex.

The big mystery concerning the harmony of the Golden Proportion gets a sober technical-physical dimension with the theory of objectivity. It determines within the fundamental field equation" (27.26) the rolling up of a wave into a vortex and vice versa. The Golden Proportion mathematically describes the process known as wave damping, as we can make ourselves clear.

29.8 The vortex, which is rolling up

For the case of a wave propagation in air or in vacuum, if no electric conductivity is present (σ = 0), the fundamental field equation is reduced to the two parts: the description of the electromagnetic wave and the potential vortex as a damping term. Now a solution of this partial differential equation (29.11) is sought. This only succeeds for a very particular course of spatial and temporal field.

If a wave for a field perturbation rolls up to a vortex, which we had worked out as a model concept, then the field oscillation continues to run with the speed of light, but this time in circles. With this consideration the relation between the angular velocity resp. the time constants and the radius of the circular vortex has been described (τ_2 = r/c).

v(x(t)) = dx/dt is the not-accelerated velocity of propagation of a vortex. In that case v points in the x-direction radially to the outside. For the time derivation of the field vector E(x(t)) the chain rule should be applied. With that the field equation (29.11), defined in space and time, can be converted into an equation determined in v and x (29.12).

Finally we use the mentioned property of the e-function, which for first and second derivation again turns into itself, by choosing the approach of an exponential damping with $e^{-x/r}$ There remains a quadratic equation to determine the velocity v (29.14 and 29.15). From the two solutions of the quadratic equation only the one with positive velocity should be considered (29.17) and that would be 1.618 times the speed of light! (29.18).
If we subtract 1 from this value or form the reciprocal value, then in both cases the factor Φ = 0.618 results, which is called the Golden Proportion (29.19).

Behind this clear, mathematically won result is hiding a deeper physical meaning. Obviously nothing can hinder a longitudinal wave and its vortices to be slower or faster than just with v = 1.618*c. Let us take the case that v = c, for which there even exist calculations in some textbooks[i]. Then as a result gets out that the longitudinal parts decrease very quickly and already can be neglected after $\lambda/2\pi$. I in any case interpret the near-field zone of an antenna (fig. 29.9) such that within one sixth of the wavelength the vortices to a large extent have decayed.

---

[i]: Zinke, Brunswig: Lehrbuch der Hochfrequenztechnik, 1. Bd., 3.Aufl. Springer-Verlag Berlin 1986, Seite 335

- The quadratic equation 29.14: $\boxed{v^2 - v\cdot c - c^2 = 0}$ (29.15)
- has the solution: $\boxed{v = c/2 \pm\sqrt{c^2/4 + c^2}}$ (29.16)
- for the proportion v/c: $\boxed{v/c = (1 + \sqrt{5})/2 = 1.618}$ (29.17)
- The result $v/c = \underline{1.618}$ (29.18)
- resp.: $c/v = \Phi = \underline{0.618} =$ „Golden Proportion"(29.19)
- acc. to that is: $1 + \Phi = 1.618 = 1/\Phi = 1/0.618$(29.18*)

- Concerning the physical meaning of $v/c = 1.618$ (29.17)



In the domain:	vortex decay:	description:
$v = c$	within $\lambda/2\pi$	near-field zone
$v < 1.618\cdot c$	only later	noise
$v = 1.618\cdot c$	stability limit	direct conversion
$v > 1.618\cdot c$	stable, no decay	neutrino radiation

=>In the ideal case at 1.618 times the speed of light at the stability limit, the natural and spontaneous conversion from vortex to wave and vice versa occurs.

=> Scalar wave antennas have their optimum degree of effectiveness in the Golden Proportion!

Fig. 29.9: Derivation of the Golden Proportion from the fundamental field equation.

For larger velocities, as Tesla has produced already 100 years ago, the stability of the vortices, but also their biological effectiveness increases. From a high-frequency technical viewpoint this is the domain of the noise, the domain of instable oscillating noise vortices. From a biological and medical viewpoint especially here the answers should be sought to questions concerning the electromagnetic environmental compatibility. This domain stretches from v = c to v = 1.618*c, the boundary case, where a spontaneous conversion of the wave into the vortex is possible. The Golden Proportion describes the stability limit, where the field vortices after they have been formed, don't decay anymore. From this velocity on the antenna resp. radiation source hasn't got a limited near-field zone anymore, since that now reaches to infinity. Only from this distinct velocity on I give the field vortices the name "neutrino".

29.9 The Golden Proportion

Whereas traditional antennas, which should emit electromagnetic waves, are optimized for signals with the speed of light, do scalar wave antennas have their optimum degree of effectiveness in the Golden Proportion. Thereby the goal of an emission of oscillating ring-like vortices is pursued. Vortices, which with a velocity of propagation of v = 1.618-c remain stable and make possible a spatially unlimited transmission of energy and information by scalar waves.

The velocity of propagation v is calculated from the product of wavelength times frequency. $v = \lambda \cdot f$. If the frequency of a transmitter is prescribed, then the geometry of the transmitting antenna decides on the degree of effectiveness of the antenna and on how many parts of transverse waves are emitted in relation to longitudinal waves. In the case of a broadcast antenna usually λ or $\lambda/2$ is chosen. For a scalar wave however the optimum is reached with

$$\boxed{\lambda_{\text{vortex}} = 1.618 \cdot \lambda_{\text{wave}} = 1.618 \cdot c/f.} \quad (29.20)$$

With that the electrotechnical problem becomes a geometrical one, if it concerns the use of scalar waves. Crucial is the antenna geometry, and the Golden Proportion provides the necessary constructional instruction. Were the buildings in antiquity, which were constructed according to the Golden Proportion, technical facilities for scalar waves<i>? Did the builders have physically explainable and mathematically provable guidelines? At this place, by the derivation of the Golden Proportion from the fundamental field equation, there arise completely new aspects for the judgement and interpretation of buildings especially from antiquity. If we have understood their way of functioning, then we will be able to learn much from that for our own future and for the future construction of scalar wave devices. Concluding the seminar we hence deal with antiquity.

ancient temple = short wave station

dedicated to one god = fixing of the frequency

supreme god Zeus, = range of the short wave,
father of all gods = all SW wave bands

priest, representative of the god = amateur radio operator, with licence to transmit

high priest = chief intendant

Pontifex Maximus, „topmost bridge builder" = chairman of the authority and the telegraph offices

oracle<i> = telegraphy receiver

runes, cuneiform writing = telegraphy symbols

metre, hexameter = increase of redundancy

oracle priest = telegraphy interpreter

tripod<ii> = reception key, electro-acoustical converter

looking at intestines, rite of sacrificing = reading off convulsions, electro-optical converter

temple books = news-notes

seer, who looks into the god world = amateur radio operator, at telegraphy reception

Homer = ancient radio reporter

Fig. 30.1: ____Little dictionary for ancient radio engineering (1).

<i>: Lamer: Worterbuch der Antike, Kroner Verl. Bd.96 under "oracle" stands: „Lat. oraculum = site of speaking; particularly: site, where a god speaks; then: that, what the god says". According to the encyclopaedia oracle priests inspired by a god „simply were frauds, who lived of the ignorance of the public".

30. Scalar wave technology in antiquity

The end of the book about potential vortices and their propagation as a scalar wave shall form an impressive example, where as many of the derived wave aspects as possible have an effect. It shall be proven that already in antiquity radio engineering based on scalar waves has been used. The proof starts with a thesis.

30.1 Thesis:

The temples in antiquity all were short wave broadcasting stations. And energy from the field served as an energy source, so e.g. the earth radiation in the case of temples of terrestrial gods. In the case of the solar god the radiation of the sun was used, whereas for the temples, which were dedicated to the planetary gods, the neutrino radiation arriving from the planets served as an energy source.

If the temple was dedicated to a particular god, then the name of the god was representing the used frequency of the broadcasting company. The corresponding wavelength, resp. the respective god, understandably was "immortal".

Not so the broadcasting technicians on duty, who as human beings naturally were mortal, who took turns in the studio as members of the priest council and who merely had to impersonate the god Apollo, Poseidon etc. by the name of the broadcasting company, if they went on air. Only for the news editor Homer and for few of his colleagues we actually know the names of the persons behind the scenes.

In the temple books the texts have been recorded, which a god and its broadcasting company have received. The chosen metre served the easier detection and correction of transmission errors.

Here often a lot of fantasy was necessary, for which reason the reception facilities commonly were described as oracle<i>. The reception of the news as a rule took place on an altar. Thereby the direct effect of scalar waves on man e.g. in the case of the so-called temple sleep or the indirect influence on biological systems, e.g. on the intestines of slaughtered animals, was evaluated.

A further development of the telegraphy was the tripod technology<ii>, in which case by turning of the polarization plane individual symbols and letters were transmitted up to the transmission of the spoken word with the help of a special wavelength modulation. That far the thesis reaches, which now should be proven.

<ii>: Lamer: Worterbuch der Antike, Kroner Verl. Bd.96 under "tripod" stands: „the tripod is a dedication gift to gods, a honorary gift for winners. That one pleased them with the gift of a cooking pot, is strange; one has tried to find the reason, but until now without success". In the encyclopaedia further is advised: „tripod as a means for spiritual insight?!"

godology = high frequency technology
god name = RDS, station identification
members of a family of gods = broadcasting studios of a broadcasting company
Pantheon, temple of all gods = extremely broadband FM broadcast station
crown = antenna netting
gifts for sacrificing = broadcasting fees
place of sacrificing = place of a node of the standing wave
earth radiation = power supply
homage of a weekday = time restriction of the operation of the station
Zeus „forges" thunderbolts = electrostatic blows, when a temple is oscillating
ritual act = technical provision for transmission and reception
Pythia of Delphi<i> = radio telephone operator, receptionist
Cella (marrow of temple) = tuned cavity
obelisk<ii> = antenna rod

Fig. 30.2: ____ Little dictionary for ancient radio engineering (2).

<i>: Lamer: Worterbuch der Antike, Kroner Verl. Bd.96, under „Pythia"(gr.=the asker): In the temple of Delphi was a chasm. A tripod was standing over it, on which the Pythia was seated, if she gave oracle. Comment: "It was flashy how odd the Pythia was sitting; inconveniently enough, on the cooking pot of the tripod. Ancient pictures, which show her that way, still weren't proven, that it was this way ..."

<ii>: Lamer: under „Obelisk" stands; „The obelisks probably were clocks".

30.2 Prerequisites

The argumentation has to be made on mathematical-physical foundation. The prerequisite for that are the 29 chapters of before. The following points could be demonstrated and derived:

1. The wave equation (inhomogeneous Laplace equation) describes the sum of two wave parts, where
2. every antenna emits both parts,
3. the transverse part, known as electromagnetic wave (Hertzian wave)
4. and the longitudinal part (Tesla radiation) termed scalar wave by the discoverer, better known as antenna noise.
5. The wave equation mathematically describes the connection of both wave parts in general and the conversion of one part into the other in particular, thus
6. the rolling up and unrolling of waves in field vortices (measurable as noise).
7. The transition takes place proportionally to the Golden Proportion, as resulted from the derivation (chapter 29.7 - 29.9)

With the last point the electrotechnical problem becomes a geometrical problem, if it concerns the use of scalar waves. The geometry of the antenna is crucial. Thereby the Golden Proportion provides the necessary direction for construction.
That justifies the assumption that the buildings in antiquity, which were built according to the Golden Proportion, were technical facilities for scalar waves. Maybe the builders had specifications that had physical reasons and could mathematically be proven.
At this place there result completely new aspects for judging and interpreting buildings especially from antiquity through the derivation of the Golden Proportion from the fundamental field equation. If we have understood their way of functioning, then we will be able to learn much from that for our own future and for the future construction of scalar wave devices.

As a further prerequisite for the ancient broadcasting technology enough field energy should be at disposal. We proceed from the assumption that

1. the earth magnetism and the cosmic neutrino radiation are tightly hanging together by the processes in earth's core,
2. the earth magnetism in antiquity verifiably was approx. thousandfold stronger than today (proven by gauging of pieces of broken pot),
3. as a consequence the neutrino radiation in antiquity as well must have been thousandfold stronger and
4. the cosmic neutrino radiation has served the transmitting plants of antiquity as an energy carrier,

any thought is absurd to reject the technical function of a temple only because it today can't be reproduced anymore. The artistic and aesthetical viewpoints, which are put into the foreground by art historians because of ignorance about the true function, rather are secondary.

The terms used to describe the broadcasting technology in antiquity in the last 2000 years have experienced a shift of meaning, so that a translation in our linguistic usage of today is necessary. The adjacent dictionary should help in that case.


Φ·L
L/2
L
L/2
Φ·L
BASIS
L
Φ·L
0
5
10
15
20 M
Cella-Length: L = λ/2 = 30 m
frequency: f = c/λ = 5 MHz
Constr.: 470-456 B.C.
gold. Prop: Φ = 0,618

Fig. 30.3: The Golden Proportion of Zeus-temple in Olympia.<i>

<i>: K. Schefold: Die Griechen und ihre Nachbarn, Propylaen Kunstgeschichte Berlin Bd. 1, Abbildungen von Seite 249

30.3 Approach

Let's to some extent proceed from the knowledge of textbook physics currently present in high frequency engineering and give a well trained engineer the following task, which he should solve systematically and like an engineer: He should build a transmitter with maximum range at minimum transmitting power, thus a classic task of optimization. Doing so, the material expenditure doesn't play a role!

After mature deliberation the engineer will hit upon it that only one solution exists: He decides on a telegraphy transmitter at the long wave end of the short wave band, at f = 3 MHz, which corresponds to a wavelength of $\lambda = 100$ m. There less than 1 Watt transmitting power is enough for a radio communication once around the earth. That also has something to do with the conditions of reflection of the radio waves at the ionosphere. Our engineer learned:

the index of refraction $n = \sqrt{1 - K \cdot N/f^2}$ (30.1)
with: $K = 80.5 * 10^{-6}$ [cm^3/sec^2] (= constant)
N = electron concentration [$electrons/cm^3$]
f = frequency of the transmitter [MHz]

Put into words: the refraction of a radio wave in the range of the short waves is the larger, the smaller the frequency is. The end of the short wave range is reached at 3 MHz. That thus explains the choice of frequency.

And he optimises further. Next the engineer remembers that at high frequencies, e.g. for microwave radiators, not cables but waveguides are used, since these make possible a considerable better degree of effectiveness. In the case of the waveguide the stray fields are reduced by an alignment and concentration of the fields in the inside of the conductor. In the case of antennas however the fields scatter to the outside and cause considerable stray losses. He draws the conclusion that his transmitter should be built as a tuned cavity and not as an antenna!

As a result the engineer puts a building without windows in the countryside with the enormous dimensions of 50 m length ($=\lambda/2$) and 25 m ($=\lambda/4$) resp. 12.5 m ($=\lambda/8$) width. The height he calculates according to the Golden Proportion to increase the scalar wave part. Those approximately are the dimensions of the Cella without window of Greek temples.

For the operation of such a transmitter in antiquity apparently the noise power of the cosmic radiation was sufficient, which arrived at the earth starting from the sun and the planets. By increasing the floor space also the collected field energy and the transmitting power could be increased, so that also from the perspective of the power supply the temple with the largest possible wavelength at the same time promised the largest transmitting power, so at least in antiquity.

Our engineer further determines, that he will switch the carrier frequency on and off at a predetermined clock pulse. Thus he decides for radiotelegraphy. The advantage of this technique is a maximum increase of the reception range. For that the signals at the transmitter have to be coded and at the receiver again deciphered. By means of the encryption of the contents these are accessible only to the „insiders", who know the code; prerequisite for the emerging of hermetism and eventually a question of power!



7,5 MHz transmitter frequency
λ = 40 m wave length
L = 20 m cella-length (= λ/2)
b = 10 m cella-width (= L/2)
Φ = 0,618 golden proportion

Fig. 30.4: Example Tegea, temple of Athena Alea.[i]
Built 350/340 B.C.

---

[i]: G. Gruben: Die Tempel der Griechen, Wissenschaftliche Buchgesellschaft Darmstadt 1986, 4. Aufl. Seite 130

[ii]: E. Horst: Konstantin der Grosse, Eine Biographie, Classen Verlag 1985 Dusseldorf, 2.Aufl., S. 89.

[iii]: E. Horst: Konstantin der Grosse, Eine Biographie, Classen Verlag 1985 Dusseldorf, 2,Aufl., S. 33.

30.4 Circumstantial evidence

Not everyone, somehow participating in send receive engineering, at the same time also was inaugurated in the entire secret knowledge. Most priests only knew as much as they necessarily needed to know to fulfill their tasks. Thus a temple priest, who was presented an enciphered text and who should bring this on the air, not necessarily at the same time needed to know the content of the text or the code. The same of course also was valid for the sacrificing priest acting in the receiving station. The Vestal virgins for instance had to present the received text to the Augures, by whom they were supervised and controlled.

But who wanted to introduce a new god in the gods heaven and perhaps even himself be worshipped as a god, should have complete command of both the broadcasting technique and the reception technique. In ancient Egypt the Pharao at least once a year had to prove, that he still was in command of the technique. Otherwise he was replaced. For a person with security clearance that at the same time was a death sentence.

In the historical facts numerous pieces of circumstantial evidence can be found, which can be considered to be evidence for the thesis of the operation of send receive engineering in antiquity. One now perhaps understands, why the rulers were put an antenna netting over their head, a so-called crown, or why the Augures could survey the land with a flat Tesla coil in their hands (fig. 16.10).

Direct evidence is present as well. It can be found in ancient texts. But it is questionable if historical texts concerning ancient radio engineering have been translated correctly. The talk is about oracles, mystery cult and earth prophesy if the receiver is meant. The predominantly technically uneducated historians attest the Romans a defective sense of time, because their couriers surely could not cover the long ways across the Roman empire so fast at all, if they read in the Latin texts: "They sent by courier to the emperor in Rome and got for answer...". The answer of the emperor namely already arrived at the squad at the latest in the following night. The correct translation should read: "they cabled" or "they broadcasted to the emperor in Rome and got for answer..."[ii].

Such a big empire as the Roman Empire actually only could be reined by means of an efficient communication. Cicero coined the word: "We have conquered the peoples of the earth owing to our broadcasting technology...[iii]"! The term broadcasting technology from ignorance is translated with piety. If engineers however rework the incorrect translations, then one will discover that numerous texts tell of the broadcasting technology, that thus correspondingly much direct evidence exists concerning the practical use of this technology.

For the Roman military transmitters, which formed the backbone of the administration of the empire, the reading off of the information from observations of nature like the bird flight or from felt signals of a geomanter was too unreliable. They read off the information from the rhythm of the convulsions of the intestines of freshly slaughtered animals. In the case of the dead animals on the altar every extrinsic influence was excluded. But the enormous need of slaughter cattle was a disadvantage. Who wanted to have information, first of all had to bring along an animal, which then was „sacrificed" the god, or better say, which was abused as a receiver for a particular transmitter. Thereby the innards served as a biosensor and as a receiver for the news.



Cellular phone.

• *Network:*	All „telephone cabins“ are transmitter and receiver at the same time.
• *Advantage:*	Anyone can communicate with every network participant.
• *Characteristic:*	The stations are strikingly similar in form and size of building.
• *Power structure:*	All stations as a rule have equal rights among each other.
• *Disadvantage:*	Innovations hardly are possible. The system is inflexible.
• *Examples:*	Temple towers (Iraq); cellular phone network.

Broadcasting.

• *Network:*	Many receivers listen to the news of one powerful transmitter.
• *Advantage:*	The system is very flexible and permanently experiences improvements.
• *Characteristic:*	Monotheism. Big diversity among the receiver constructions.
• *Power structure:*	Central power concentrated in the hands of the chief intendant.
• *Disadvantage:*	Feedback from receiver to transmitter is not desired.
• *Examples:*	God Ammun Re (Egypt); ABC daily news.

Dispatch service.

• *Network:*	Network of broadcast stations supplies an agency (receiver) with information.
• *Advantage:*	Optimal financing, since information is given away only for broadcasting fees in cash.
• *Characteristic:*	Treasury stores have to be built because of the immense riches.
• *Power structure:*	The power is concentrated in the hands of the receiver-agency.
• *Disadvantage:*	In the case of overcharge or overload a system crash is impending.
• *Examples:*	Pythia (Delphi); German Press Agency (dpa).

Fig. 30.5: ____ Three radio technical network structures, with an example from antiquity and from present time.

30.5 Radio technical concepts

In planning and constructing radio technical networks only a few possible concepts exist. It is interesting that at least one historical example can be specified for every concept. That shows that all possibilities were tried at least once. The three most important concepts are presented here:

A. Cellular phone.

Every bigger city between Euphrates and Tigris, which thought the world of itself, had at its disposal already in antiquity a temple tower. Such a temple tower was a „telephone cabin" in the form of a pyramid as a transmitter and a receiver temple at the top, to where the receptionist adjourned to the so-called temple sleep. Discipline was required, since all the time only one priest was allowed to broadcast. All others could listen to him doing so. If he was ready, he closed his contribution with a fixed symbol or term („over") and the next one could continue. This is a classic link-up, where anyone communicates with every network participant.

The stations all were strikingly similar in form and size of building, like one phone box resembles another. In that way a further development of the cellular phone system hardly was possible and that has a technical reason, as the building of a tower in Babylon has shown us. This tower namely had gotten the ambitious builders too big, so that the frequency of the Mesopotamian radio network had been left and instead a foreign network could be received, the code of which no-one could understand. The result was a confusion of language and the order to stop the building.

B. Broadcasting.

Millions of TV spectators every evening look in the ABC news or another daily journal of a TV Channel. In the case of broadcasting thus many receivers listen to the news of a powerful transmitter. With that the whole plenitude of power is concentrated in the hands of the chief intendant. In antiquity he called himself high priest. If he went on the air, he used the logo of the god that he had to represent. Today the logo of the broadcasting company is shown in a corner of the TV screen. Even this very day feedback from the receiver to the transmitter hardly is possible contingent on principle. The problems with nationally controlled broadcasting, with politics controlled by the media all are not new. The monotheism in ancient Egypt with the claim of lordship of the main god Ammun Re is an example from antiquity.

C. Dispatch service.

In ancient Greece the technical structures and with that also the power structures had been turned around. At that time a big network of broadcast stations, which continually was extended by a policy of settlement ordered by the gods, supplied a central and correspondingly powerful agency with information per radio.

Who wanted up to date news, could call for these in the agency with seat in Delphi, but he had to pay for it. To accommodate the broadcasting fees in form of gold and gifts whole treasury stores had to be built. Measured by the commercial success the ancient news network has remained unmatched, and can't be compared with pay-TV or todays dispatch services, like dpa. If the network however becomes too big, uncontrollable and it lacks discipline, then it sometime will crack and the system crashes.


L
[¾]L
[¼]L
L
[¾]L
L
L/2
0
10
20
30
40
50 M

Fig. 30.6 A: Hera-temple of Selinunt 460-450 B.C.<i>
(Corresp. to the plans of the Roman architect Vitruvius)


[¾]L
Φ·L
L
Φ·L
2ΦL
Φ·L
Cella length L
L = λ/2 = 16,7m
0
5
10
15
20 M
frequency f = 9 MHz
about 540 B.C.

Fig. 30.6 B: Apollo-temple of Korinth<i>
(Alternative interpretation, use of the Golden Proportion Φ).

<i>: K.Schefold: Die Griechen und ihre Nachbarn, Propylaen Kunstgeschichte Berlin Bd. 1, Abbildungen von Seite 241, 250

<ii>: Vitruvius (Marcus Vitruvius Pollio): Zehn Bucher uber Architektur, Ubers. von Dr. K. Fensterbusch, Wissenschaftl. Buchges. Darmstadt 1987, 4. Aufl., 3. Buch, 1. Kap.: Von den Symmetrien der Tempel, Seite 137

<iii>: Vitruvius (dito), 4.book, 4.Chap.: Vom Tempelinnern und dem Pronaon, p. 187

30.6 Wireless telegraphy

Radio engineering 100 years ago also started with telegraphy. Thereby the high frequency carrier is switched on and off. With this technique Marconi succeeded in a radio transmission over the English Channel (1899) and over the Atlantic Ocean (1901).
As next step the amplitude modulation (AM) followed. Thereby the HF-carrier is overlapped with the low-frequency signal of a sound carrier in such a way, that the amplitude fluctuates on the beat of the LF-signal. As a disadvantageous effect, also noise signals will overlap, from which the quality of reception will suffer.
Only the frequency modulation (FM), where the LF-signal is transmitted as temporal fluctuation of the frequency, brings an improvement. The annoying amplitude noise hence has no effect in the case of FM.
It easily can be recognized, how the development of the modulation techniques follows the urge for technical improvement and optimization. That in antiquity hasn't been different, for which reason the progress of development took place in the same order.

The broadcasting technology of the ancient gods started with the wireless telegraphy. This is expressed in the architecture. Since electric resonant circuits or other frequency determining equipment weren't at the disposal of the engineers in antiquity, the determination and allocation of the broadcasting channels had to take place by means of the wavelength. The formation of a standing wave in the Cella, the innermost sanctuary of a temple, occurs if its length corresponds to half the wavelength of the HF-carrier. The Roman architect Vitruvius calls the wavelength the „basic measure", from which results "the system of the symmetries". He writes: „The design of the temples bases on symmetry, to which laws the architects should adhere meticulously. "[ii]. „The length of the temple is partitioned in such a way that the width is equal to half the length, the Cella itself including the wall, which contains the door, is one fourth longer than wide. The remaining three fourths, which form the Pronaon, should protrude until the antae of the wall and the antae should have the thickness of the pillars"[iii].
If we recalculate ourselves, then the partitioning in 3/4 to 5/4 produces a proportion, which conies quite close to the Golden Proportion. In building a temple nothing is left to chance, after all it concerns the construction of a tuned cavity, capable of self-resonant oscillations with favourable emission behaviour.
From the outside one can't see if a telegraphy transmitter has been changed over to speech transmission with AM. The HF-carrier merely isn't switched off anymore, i.e. the priests let the temple oscillate without interruption. Newly added for AM is an electroacoustic coupling. For that many temples were retrofitted with a mouthpiece. Newly built AM transmitter temples conclude the Cella with a round apse. Because of this acoustically conditioned construction the Cella length didn't have a fixed value anymore and the transmission frequency had become variable. Measured in the middle of the apse the wavelength was larger than at the sides, so that on the beat of the spoken word not only the amplitude of the field distribution in the interior of the temple, but in addition also the frequency of the selfresonant oscillation was changed.
A typical example of such an architectonic hybrid form of AM and FM is situated in Rome. Because due to the frequency variation more than only one wave band was occupied and the temple consistently carries the names of two deities. It is the temple of Venus and Roma.



Diameter bigger circle D_1= 22 m (6,8 MHz),
small circle D_2 = 11 m; und L = D_1 + 1/2 D_2 = 27,5 m (5,5 MHz)



Fig, 30.7: Temple of Venus and Roma; Rome 136/37 A.D.[i,ii]

<i>: A. Springer: Das Altertum, A. Kroner Verl. Leipzig 1915, 10. Aufl., S. 518
<ii>: T. Kraus: Das romische Weltreich, Propylaen Kunstgesch. Berlin Bd. 2, S. 161
<iii>: Lamer: Worterbuch der Antike, Kroner Verl. Bd.96 unter "Tempel", Haufigkeit

30.7 AM temple technology

The low-frequency signal (LF), which should be transmitted by a transmitter with amplitude modulation, lies in the range between 16 Hz and 16 kHz. If it only concerns the transmission of speech information, then the bandwidth can be reduced to 300 to 3000 Hz. In the case of mixing the low-frequency useful signal with the HF-carrier, thus in the case of the modulation of the carrier in the rhythm of the LF, two side bands arise. These lie close to the carrier frequency and are formed from this once by the addition and once by the subtraction with the frequency of the LF-signal. Let's take the temple of Venus and Roma with a transmission frequency of 6.8 MHz. If sound of 3 kHz should be transmitted clearly understandable, then the dimensions of the Cella had to be varied for just 8 mm for a corresponding Cella length of $\lambda/2$ = 22 m. As a curiosity the niches in the side walls in the case of this temple however allow a considerably larger bandwidth of more than 10% instead of the necessary 0.04% in the case of AM.

In the case of the Greek originals, the Cella however has smooth walls, from which follows that the temples were designed ideally narrow band. The Greeks apparently operated predominantly telegraphy transmitters, for which the side bands coincide with the carrier.

The argumentation indeed has remained unchanged: The modulator being narrow band and simple to realize speak in favour of the telegraphy being the "original form" of all modulation techniques. Also the rediscovery of the broadcasting technology by Heinrich Hertz succeeded as telegraphy signal. In addition the range is bigger than for any signal modulated with sound frequency.

As the calculation example has shown, also pure AM transmitters work very narrow band, and this is particularly important for low transmission frequencies, if many transmitters want to use the favoured SW band between 3 and 10 MHz at the same time. With AM one thus accommodates the maximum number of broadcasting channels in a particular frequency range, for instance the 80-meter band, without these interfering with each other too much. But that also was badly needed. Conclusions about the everyday life of broadcasting in antiquity by all means are possible because of the enormous number of temple installations, which logically were permanently used. Only in Rome there existed up to 200 temples[iii]!

Who goes in search of broadcasting stations with a modern short wave receiver, for instance in the 80 m band between the countless telegraphy transmitters, fast gets an idea of what had been up in the air already 2000 years ago. No ancient city would build several temples on a single Acropolis, if only one single one could have been used. All temples broadcasted with each time another carrier frequency because of different dimensions. For this reason the temples, which stood side by side, as a rule were dedicated different gods. An acknowledgement, "the air just being free", in addition hardly was possible, because of the often-found spatial distance between the temple installations and the respective oracle. Between the transmitter of the god Apollo in Didyma and the receiver, the oracle of Milet, for example lie approx. 20 kilometres. The only possible conclusion is that in antiquity there was broadcasted on all channels simultaneously regardless of other gods and their transmission frequencies. As is well-known there rather prevailed a situation of competition between the gods, since like today a large number of listeners meant great importance, influence and power and eventually also worship, more gifts and more receipts from broadcasting fees.



Fig. 30.8: Comparison of a magnetron (A), a microwave radio tube<i> and the temple (B) in the palace of the emperor Diokletian, Split.<ii>



Fig. 30.8.C: Temple of Minerva Medica, Rome, 320 A.D.<ii>

<i>: K. Simonyi: Physikalische Elektronik, 8.4 Das Magnetron, S. 665

<ii>: T. Kraus: Das rom. Weltreich, Propylaen Kunstgesch. Bd. 2, S. 194, 196

<iii>: If one however wants to verify this, in antiquity already common manner of PM broadcasting technology, then we need a broadband short wave receiver with phase-demodulator. With such a receiver even today any time a conclusive argumentation should be possible that this sort of SW-PM technology actually works.

30.8 Modulation of acoustic signals

In the case of sound it in essence concerns longitudinal waves, which propagate in all directions in space with the velocity of sound. But this merely is an average velocity, since the air molecules strictly speaking oscillate with the sound frequency in the direction of propagation. In this way the velocity of sound one time is increased and the next moment to the corresponding extent reduced. If the molecules already carry out oscillations of themselves, e.g. thermal motion, then both oscillations overlap; i.e. the motion of itself is modulated with the sound frequency.

Following the here presented derivation potential vortices are formed in every dielectric, thus also in air, and these are modulated if overlapped with sound waves. Vortices however do not form a distinct frequency, but entirely on the contrary a uniform frequency mixture in the form of white noise.

The overlap thus also is noise unless certain noise frequencies are favoured. This can be effected by means of a spatial body tuned to a certain wavelength. To be considered are cuboid cavities, as in the case of Greek temples or waveguides and cylindrical objects as in the case of round temples or magnetrons. The building form causes the favouring of a certain frequency and the integer harmonic frequencies belonging to it.

If this frequency now lies in the high frequency range, then it is emitted by the spatial body as an electromagnetic wave, in the case of waveguides and resonant circuits for reason of the small dimensions as microwave radiation and in the case of the Greek temples as short wave radiation. If one in addition produces an acoustic signal in the frequency determining spatial body, then this signal automatically will modulate the high-frequency signal.

The result of the modulation is the overlapping of the sound wave with the high-frequency carrier wave. The change of the active length, thus the wavelength of the HF-carrier causes a change of frequency. Such a change on the beat of the sound frequency is called FM (frequency modulation). For that we imagine a spatial body being excited because of its length by potential vortices to a high-frequency oscillation at the self-resonant frequency.

From flow dynamics is known, how easy the distribution of vortices in space can be disturbed. Already words spoken in space are able to influence the potential vortices, which in the case of the temples were used as energy carrier. The longitudinal sound waves reflected at and thus returning from the Cella wall rigid for sound of a Greek temple will push these potential vortices back on the beat of the sound and with that shorten the active length. This means, that the carrier frequency is modulated with the sound frequency. The carrier oscillation thus permanently changes its phase on the beat of the sound signal, for which reason this particular kind of modulation is described as PM, as phase modulation.

Nowadays PM is used only seldom and in the SW-range not at all because of the big need of wave bandwidth. Merely at higher frequencies PM occasionally is used in radiotelephony. In the case of the frequency modulation usual in broadcasting (e.g. UHF), the change of frequency takes place on the beat of the sound amplitude and not of the sound frequency as with PM. Therefore it is not possible to receive phase modulated signals, which are produced by means of the acoustic coupling of appropriately formed spatial bodies<iii> with commercial FM receivers.


Diameter
D ≈43,2 m
Via della Rotonda
Via della Palombella
Pantheon
D
= 43,2 m
Φ·D
Via della Minerva
Minerva
0
10
20
30
40
50 m
100

Fig. 30.9: The Pantheon in Rome, the „temple of all gods".<i>
Diameter D = 43,2 m, Golden Proportion: Φ= 0.618
Pronaon-(atrium-)length: Φ·D= 0.618 • 43.2 = 26.7 m
Built under emperor Hadrian 118/ 119-125/128 A.D.

30.9 Broadband FM broadcasting technology

If I speak against a flat wall, then every point on the wall has another distance to my mouth. The sound waves thus aren't reflected simultaneously, what leads to big modulation distortions. Therefore the sound wall should be curved in such a way, that all signal paths are the same length (barrel vault, apse, etc.). In the case of point sound sources there results as an optimum a hemisphere, for instance a dome. The building hence even today tells us, which frequency and which modulation method had been put to use. The architecture of sacral buildings, e.g. pointed arch or round arch, thus hardly has been a question of aesthetics.

For his temple of Venus and Roma designed by himself emperor Hadrian had to listen to severe criticism among others of Apollodor of Damascus. The temple was too broadband for an AM transmitter, however with a modulation depth of just 11 percent not broadband enough for a phase modulated FM transmitter.

Emperor Hadrian however also had the courage to build midst in Rome a temple calculated completely new and designed as a pure FM transmitter, the Pantheon, which means temple of all gods. In the language of the technician it is a transmitter for all frequencies.

This domed structure indeed doesn't leave out one single frequency. With a modulation depth of almost 100 percent it is designed for maximum loudness. With that the Pantheon uses all available frequencies, for which reason the name temple of all gods really is no exaggeration. Into the Pantheon exactly fits a sphere with a diameter of 43.2 meter. That corresponds to a minimum frequency of 3.47 MHz, situated in the range of the short waves. The floor however is not domed, but horizontal. That, up to the basis of the dome, results in exactly half the height and a maximum frequency of 6.94 MHz.

The construction ensures that between the simple and the double diameter any desired wavelength can be produced. Above the given maximum frequency of the basic oscillation the harmonic waves, which are produced as well and can't be avoided at all, are attached without a break. These occupy the wave bands up to the double, triple, quadruple frequency and so forth.

For this and only for this reason a maximum frequency was chosen, which corresponds to exactly the double value of the minimum frequency. The operation takes place to the limit, where the transmitter would interfere with itself, in the way that the used basic oscillation would overlap its own harmonic waves. That then sounds like two people talking at the same time. The voices would be distorted out of recognition, as can't be expected else in the range of the harmonic waves.

The Pantheon has been planned and built as a phase modulated basic wave transmitter according to purely academic rules of Hadrian. The temple impressively demonstrates the precise engineering detailed knowledge of the Pontifex Maximus and his broadcasting priests in ancient Rome<ii>.

<i>: A. Springer: Die Kunst des Altertums, A. Kroner Verl. Leipzig 1915, 10. Aufl., S. 517/518, daraus: die Zeichnungen ram Pantheon in Rom, 115-125 n.Chr.

<ii>: The collection of material concerning scalar wave technology here is aborted and continued in an own book in narrative and with that easier to read writing style. The title is: "Broadcasting Gods".



approach	derivation	result
b:= postulate [potential vortices Vol.1]	what if $\mathbf{b} \neq 0$?	**derivation** of the **Schrödinger eq.**
duality vortices replace quanta [potential vortices Vol.2]	from $\mathbf{H} \Leftrightarrow \mathbf{E}$ from $\mathbf{j} \Leftrightarrow \mathbf{b}$ [and chapter 3.3]	**calculation** of the **quantum properties** [potential vortices V.2]
causality [see chap. 3]	*gen.* ⇔ *special case* **field** ⇔ quanta cause ⇔ consequence (instead of: quanta ⇔ field)	vortex field free of quanta (instead of: irrotational field of quanta)
vortex physics analogous to flow dynamics [chap. 3.4 - 3.5]	**vortex + anti-vortex** (Demokrit/cosmology) [chap. 3.6 + 27.2]	coming off of vortices if $\tau_1 = \tau_2$ **model of atom** [chap. 5.5 + 5.8]
equations of transformation: $\mathbf{E} = \mathbf{v} \times \mathbf{B}$ $\mathbf{H} = -\mathbf{v} \times \mathbf{D}$ [chap.6.5 + 27.8]	for $\mathbf{E}(\mathbf{r}(t))$ and for $\mathbf{H}(\mathbf{r}(t))$: $\text{rot}\,\mathbf{E} = \text{rot}\,(\mathbf{v} \times \mathbf{B})$ $\text{rot}\,\mathbf{H} = \text{rot}\,(\mathbf{D} \times \mathbf{v})$ [chap. 27.9]	extended **field equations:** $\text{rot}\,\mathbf{E} = -\mathbf{b} - \partial\mathbf{B}/\partial t$ $\text{rot}\,\mathbf{H} = \mathbf{j} + \partial\mathbf{D}/\partial t$ [chap. 27.10]
equations of transformation: $\mathbf{E} = \mathbf{v} \times \mathbf{B}$ $\mathbf{H} = -\mathbf{v} \times \mathbf{D}$ [s.a. chap. 16.1]	**wave equation** inhom. Laplace eq. $\Delta\mathbf{E} = \text{grad div}\,\mathbf{E} - \text{rot rot}\,\mathbf{E}$ $\Delta\mathbf{E} = (1/c^2)\cdot\partial^2\mathbf{E}/\partial t^2$ [chap. 27.13] [chap.22.4]	transverse + longitudinal wave parts: **scalar waves,** noise, etc.
equations of transformation: [chap. 28]	vortex overlap **length measures depending on field**	**gravitation,** **temperature,** **theory of objectivity**

Fig. 30.10: (All) Many roads lead to Rome.

30.10 Epilogue

The preparation for a seminar or a lecture always starts with a collection of material. This should be considerably more detailed than the material to be communicated, since it doesn't get well at the students and also other participants, if the state of knowledge of the lecturer already is exhausted with the scope of his lecture. For this reason the collection of material must also include alternative derivations and areas of knowledge, which thematically rather are marginal, about which mustn't be reported, which possibly not even can bear criticism but still are in the public discussion. For a collection of material, which wants to be considered to be comprehensive and complete, it is important that no area and no theme has been overlooked.

The here presented collection of material with its 650 pages has become correspondingly voluminous. After all the material has been collected over an 8 year period and has been strung into the book in the order of working. That of course complicates reading the book, because individual aspects are repeated several times, but often also in a different context and each time lighted from another side. If the reader somewhere has the feeling, he only has turned in a circle, then has deceived himself. He indeed moves spirally in a circle, like in real life, but he doesn't come out there, where he started. After one turn he is richer with the experience of this spiral turn. In whole science the advancement takes place as a spiral movement and one can count oneself fortunate, as long as the spiral has an ascending slope! This notion should solace the reader, who has undertaken the torture to work through the complete collection of material.

Students also have reported, they had devoured my book like a thriller and a colleague, who had acquired it at a conference in Switzerland, was digging so much in the lecture that he forgot to get off the train timely.

It is a special concern to give reasons for the necessity of an extension of available field theory. To achieve this goal several derivations (fig. 30.10) can be found in my books: from a postulate, from causality, from duality, from vortex physics, from the equations of transformation, etc. added are at least a dozen derivations of other authors from various publications, who at most are cited. With that the goal is pursued that all approaches, which are conceivable and worth discussing, can be put side by side and tested for their efficiency.

Since it isn't the task of a collection of material to answer this question, this must be done by the hearer resp. the reader of the books. He is prompted to find the answer himself! That leads to an intense contention with the theme and that exactly is the reason for the otherwise rather unusual step to make a collection of material open to the public. Objections and criticism of the content of a relation of matters or also only of the representation of the context is wished explicitly. This also isn't valued as criticism of the author or of the superordinated set of difficulties, which in principle isn't possible at all for a collection of material.

Honorary functions of

Prof. Dr.-Ing. Konstantin Meyl



President
of the **Society for the Advantage of Physics** e.V.
(Gesellschaft zur Förderung der wissenschaftlichen
Physik, Köln)

Präsident
der **Europäischen Kommission interdisziplinärer
Wissenschaften**, Hechingen,
Gesellschaft freier Wissenschaftler, Forscher und Praktiker
(Schirmherrin: Herzogin Margarete zu Mecklenburg,
Prinzessin von Hohenzollern).

Zweiter Vorsitzender im Vorstand
der Deutschen Gesellschaft für Energetische und
Informationsmedizin e.V.,
D.G.E.I.M, Stuttgart

Vice President
in „The **German Association for Space Energy**",
(**DVR**, Deutsche Vereinigung für Raumenergie,
Hannover)

Wissenschaftlicher Beirat
im **VDE** Schwarzwald-Baar-Heuberg
im Bezirksverein Südbaden, Freiburg

TZ-Leiter
vom 1. **Transferzentrum** für Skalarwellentechnik
im Technologiezentrum von 78112 St. Georgen
im Schwarzwald

Fig. 30.11: Honorary functions of the author (December 2003, selection).

There in principle is no necessity at all to discuss with everybody a collection of material, which I have compiled exclusively for own events. It is absolutely sufficient, if few, but then qualified experts have thoughts about the content and communicate them to me. They can feel certain that I don't hand down their judgement to other persons. For that I also have been blamed by ignorant colleagues, who in complete self-overestimation have the opinion, they should be informed about everything. Right is rather, that my private correspondence is of no concern to anybody, since I find it important that as much readers as possible express themselves frank, what only functions, if they can feel certain that they afterwards won't be involved in public mud-wrestling. Therefore I keep still as regards other persons however curious they might be.

Indeed over and over again pseudo scientists turn up, who have the erroneous opinion that scientific arguments would take place on some internet-forums, where one can descant at will and anonymous, hidden behind an alias, where the intellectual firebug can feel safe, not afterwards being blamed for his crimes.

No, science takes place entirely different. A new theory will be able to establish, if it is right and important and if it is used for practical uses. Losers are those authors of a theory, for the elaboratation of which nobody is interested. What does a publication in a journal, however renowned, mean, if nobody reads it and nobody needs it? Most new ideas and approaches go under without notice in today's flood of publications, for who has got the time to read all essays in full?

Desperate they turn to me hoping, at least I could understand their concern. I then invite these scientists to a congress of the „Society for the Advantage of Physics", of which I am the president and offer them a forum, where they are able to present their ideas to an expert public. Not all lectured ideas prove to be sound, but not seldom a physical concern, which should be taken very serious, is behind it.

For a long time the real scientific controversy doesn't take place anymore at the universities and their congresses, where hardly someone dares to lecture arguments against the convention. Too fast he would be expelled as outlaw from the honourable society. From time to time however also from these circles colleagues dare anonymously or privately, as they emphasize, into the alternative events of lobbies or clubs, to astonished find out that real science there still is practised and that there is discussed about ideas, which they have given up thinking or have forbidden themselves to think about. The employment activity, so they excuse their thinking prohibition, allegedly doesn't allow it.


Taken from textbook physics:
equations of transformation
E = v x B
H = - v x D
can not be derived
derived with
E(r(t))
and
H(r(t))
new: extended field theory
law of induction extended with b
Ampère's law
with: b=0 resp.
with b ≠ 0
div B = 0 3rd Maxwell eq.
potential vortex τ2
vortex structure τ2 = τ1
eddy current τ1
div D = ρel 4th Maxwell equation
field physics
free of postulates!
quantum physics
everything postulates!
law of induction, 2nd Maxwell eq.
standard model of elementary particles
neutrino (ring-like vortex)
unification of all interactions
temperature
gravitation
law of conservation of energy
law of Ampère 1st Maxwell equation

Fig. 30.12: Derivations of postulates and axioms (part 1).

Be that as it may, the approaches and derivations contained in my collection of material are considered to be controversial, and that is good that way! The public takes notice and professional circles are occupied with the ideas. With that half the way to success already is brought off! It now concerns to knock off all points for their soundness individually, because the next step will be to search a way to the goal as unassailable as possible, which is able to convince also the biggest sceptic. The final version, which then should appear in accredited peer-reviewed journals and in a scientific book concerning the theory of objectivity, goes in this direction. From the numerous approaches in the end only one will be used, and from the countless, in the collection of material listed aspects only the noncontentious ones will remain.

The dispute, which in the current stage can't be avoided, yes even is desired, however shouldn't deceive about the fact that it here doesn't concern persons, improper vanity or some image cultivation, but simply and solely concerns the matter!

In fig. 30.12 and 30.13 is represented, what it concerns. Field physics and quantum physics don't form, as in common practise, an insurmountable opposite, but even complement each other! Below the stripline a little selection of the today in current use quantum physical postulates can be found. The number of newly introduced „constants of nature" and postulates permanently is increasing, a circumstance, which hardly can be mediated to the common sense. The bracket is missing, which interlinks all postulates, or the common source from which they can be derived causally.

In the progress of the three-part edition in this question, essential for physics, already a satisfying and in addition real efficient answer has been found in the domain of field physics. The coupling marked by individual derivations can be found above the stripline and it is entirely new, apart from the dashed indicated derivation (fig. 30.13), as given by Prof. Bosse (TU Darmstadt) in his textbook.

An approach in principle can be chosen freely. In the case of the superordinated field theory two equations of transformation form the approach, which already is laid down in textbooks and secured experimentally. That's why the whole field theoretical derivation manages without one postulate! It is pointed to the fact that these equations on their part can't be derived and should be interpreted rather philosophically than physically. From this approach the extended field theory is derived directly, without a need to add or discard a term. The extended field theory consists of the well-known law of Ampere extended with the dielectric displacement D by Maxwell, and of Faraday's law of induction, which experiences an extension with the vector of potential density b by means of the derivation. Doing so we assume that the field pointers of the electric and the magnetic field strength depend on the spatial coordinate r and through this indirectly also on the time t: E(r(t)), H(r(t)).


Taken from textbook physics:
equations of transformation
E = v x B
H = - v x D
can not be derived
derived with E(r(t)) and H(r(t))
new: extended field theory Meyl: b (without postulate!)
law of induction extended with b
Ampère's law
extended by Maxwell: D
derived with E(r,t) and H(r,t)
new: world equation:
fundamental field equation
derivation of Prof. Bosse
field physics
free of postulates!
quantum physics
everything postulates!
wave-equation
Laplace
law of induction
law of Ampère
Maxwell's field eq. of charged particles
Klein-Gordon equation
Sturm-Liouville equation
Schrödinger equation
scalar wave, (Tesla) longitudinal
el.magn. wave, (Hertz) transverse
eddy currents
potential vortex
vortex structures
basic eq. of nuclear physics
chaos theory
basic equation of quantum physics + chemistry

Fig. 30.13: Derivations of postulates and axioms (part 2).

If the somewhat more general case is counted up, in which case apart from the spatial a direct temporal dependency is present (E(r,t) and H(r,t)). then further additional terms appear in addition to the extended field equations, which need an explanation also for the case that they are zero. The physical interpretation would implicate a longer treatise, which however can be circumvented, as shown here, by constraining the field pointers, which absolutely is allowed according to the slogan: for the case E(r(t)) and H(r(t)) chosen from many possibilities the extended field equations come out exactly in the form, as they are required and suitable for the further calculations. Who has got to calculate other cases, can do that as he likes, but doing so he should not get lost. Maxwell's field equations are contained in the solution and with that also continue to be valid. Their disadvantage however is that without the extension b not a single quantum physical postulate can be derived. If we add this extension and insert the equations into each other without addition and without cuts also this time a central solution is the result, which is called fundamental field equation.

The derivation is known as well from the Maxwell theory, in which case it is common practise, to use the general approach (E(r,t) and H(r,t)), what we in accordance with the textbooks can do in the same manner. The extension however brings two additional and extremely significant terms. Since the fundamental field equation has eigenvalues under certain boundary conditions and describes structures, various quantum postulates come out from it, from the quantum properties of the elementary particles over the Schrodinger equation and the inhomogeneous Laplace equation up to the derivation of the Golden Proportion. That justifies the assumption that this possibly is the long sought-for world equation!

Even I, as the initiator, was totally surprised by the found derivation of the most important quantum physical postulates and axioms. One just is doing it the right way and already everything fits together! I am not aware of any theory, which would be able to achieve something roughly comparable. The since long sought-for „Theory of Everything", the big unification theory really falls into ones lap. The known interactions are the free and easy result of analysing the field lines of electric and magnetic field strength (fig. 30.12). Physical phenomena, which until now were considered to be incompatible, like e.g. waves, noise or the temperature with the utterly insufficient concepts of the mechanisms for the conversion of one form of energy into another, can be represented consistently with the fundamental field equation as the rolling up of a wavelike field oscillation to a vortex oscillation and as conversion of the noise vortices in the case of a vortex contraction down to atomic dimensions as thermal oscillation, which we treat as vortex losses. There exists no alternative to such unified schemes of things, as makes it possible in abundance the theory that I have founded, considering the two conditions, that on the one hand in the case of the derivation only known regularities are used, by completely doing without postulates and that on the other hand laws are applied and adhered to, also physical laws.

The new schemes of things, which sound unfamiliar, thus already were contained in the laws of physics. After this now having been realized, the tables turn. Now the explanations by postulates, as they at the moment still are being taught, should be replaced by the newly derived ones, if one doesn't want to become a breaker of the law! There doesn't lead a way past the overdue reform of physics anymore.

If you want to correspond with me or if you want to get one of my books from the bibliography, then please consult my Transfer Centre in the Technology Centre of St. Georgen (Black Forest, D).

Address: 1st Transfer Centre for Scalar wave Technology
Prof. Dr. Konstantin Meyl
Leopoldstralsse 1
D-78112 -St. Georgen /Germany
Fax.: +49-7721/51870

email: meyl@k-meyl.de or: meyl@fh-furtwangen. de
Internet: http://www.k-meyl.de or www.meyl.eu

The list of deliverable books (for ordering books over the above given address, Fax, Mail or postcard suffices):

- * Wirbelstrome, Diss. University Stuttgart 1984, ISBN 3-9802 542-0-8, 14
- * Potentialwirbel Band 1, 1990, ISBN 3-9802 542-1-6 (German), 14
- * Potentialwirbel Band 2, 1992, ISBN 3-9802 542-2-4 (not available)
- * Elektromagnetische Umweltvertraglichkeit, Teil 1, 2 and 3 (German), ISBN 3-9802 542-8-3, 3-9802 542-9-1 and 3-9802 542-7-5. Each 16
- * Scalar wave technology, 2003, documentation and manual to the demonstration-kit and to the experimental-kit (translated and copied).
- * Sendetechnik der Gotter, historischer Sciencefictionroman, (in German) 1 .Aufl. 2004, ISBN 3-98O2 542-5-9, 12
- * Neutrinopower, Johannes von Buttlar im Gesprach mit Prof. Dr. Konstantin Meyl, (Discussion in German) Argo-Verlag 2000,

(A bill is enclosed in the delivery.)

Fig. 30.14: Contacting address and list of deliverable books

Table of formula symbols

Electric field			Magnetic field		
$\mathbf{E}$	V/m	Electric field strength	$\mathbf{H}$	A/m	Magnetic field strength
$\mathbf{D}$	As/m^2	Electric displacement	$\mathbf{B}$	Vs/m^2	Magnetic induction
U	V	Tension voltage	I	A	Current
ε	As/Vm	Dielectricity: $\varepsilon = \varepsilon_r \cdot \varepsilon_o$	μ	Vs/Am	Permeability: $\mu = \mu_r \cdot \mu_o$
Q	As	Charge	ϕ	Vs	Magnetic flux
e	As	Elementary charge	m	kg	Mass
τ_2	s	Relaxation time constant of the potential vortices	τ_1	s	Relaxation time constant of the eddy currents: $\tau_1 = \varepsilon/\sigma$

other symbols:

A	m^2	Area	Q	Nm = J	Heat energy
a	m	Distance	r, R	m	Radius, radius of the earth
b	m	Width			
c	m/s	Speed of light	r_e	m	Radius of the electron
c_o	m/s	Speed of light in vacuum	s	Nms	Spin
C_e	As/V	Capacity of the electron	t	s	Time, time to orbit
C_p	J/K	Heat capacity	T	K	Temperature
d	m	Thickness	U	Nm	Potential energy
E,W	Nm	Energy	U_e	V	Tension voltage of the electron
f	1/s	Frequency			
F	N	Force	v	m/s	Velocity
G	$m^3/kg{\cdot}s^2$	Gravitational constant	V	m^3	Volume
g	m/s^2	Gravitational acceleration of the earth	W	Nm	Energy
			w	N/m^2	Energy density
h	m	Height	W_e	Nm	Energy of the electron
h	Nms	Planck's quantum of action	z_e	-	Number of the involved elementary vortices
$\hbar$	Nms	Quantum of angular momentum: $\hbar = h/2\pi$			
			λ	m	Wave length
j	A/m^2	Current density	ω	s^{-1}	Angular frequency, angular velocity
J	$kg{\cdot}m^2$	Moment of inertia			
$J{\cdot}\omega^2$	$kg{\cdot}m^2/s$	Angular momentum	σ	Vm/A	Specific electric conductivity
k	Nm/K	Boltzmann constant			
l	m	Length	ρ	kg/m^3	Density $\rho = m/V$
m	kg	Mass	ρ_{el}	As/m^3	Electric space charge density
M	kg	Mass of the earth			
n, ν =	1,2,3..	Running parameters	ψ ($\mathbf{r}$,t)		Complex wave function
N	-	Constant	ϕ ($\mathbf{r}$)		Function of space coordinates
O	m^2	Surface area			
p_m	Am^2	Magnetic moment	Φ		Golden Proportion

Definitions:

Speed of light	$c = 1/\sqrt{\varepsilon \cdot \mu}$	m/s
Speed of light in a vacuum	$c_o = 1/\sqrt{\varepsilon_o \cdot \mu_o}$	m/s
Moment of inertia (orbit)	$J = m{\cdot}r^2$	$kg{\cdot}m^2$
Mom. of i. (homogeneous sphere)	$J = (2/5)m{\cdot}r^2$	$kg{\cdot}m^2$
Angular velocity	$\omega = v/r = 2{\cdot}\pi/t$	1/s
Surface area of a sphere	$O = 4{\cdot}\pi{\cdot}r^2$	m^2
Volume of a sphere	$V = (4/3){\cdot}\pi{\cdot}r^3$	m^3

Concerning vector analysis:

Bold print = field pointer (vector); further information in fig. 5.0 in part 1

Prof. Dr.-Ing. Konstantin Meyl:

Scalar wave technology

for the transmission of electric scalar waves

Abstract:

1. Auflage 2000, 2. Auflage and 1st English edition 200

This book is recommended to people, who search the entry into the world of the by the author discovered potential vortices and their propagation as a scalar wave by experimental means. It starts with the instructions to six extraordinary experiments. Doing so an electric radiation is proven, which transmits energy, and that even faster than the light. Also more energy can arrive at the receiver then is put into the transmitter. Who entertains a doubt, will be able to understand the experiments with this book in his hand, to afterwards test the experiments with the gauge, which he is familiar with.

The 1st edition in English at first only includes the instructions for the experiments. In a subsequent edition it will be complemented with a collection of test protocols and progress reports. These are organized into three groups: one group is striving to explain the behaviour of the transmission line conventionally, a legitimate concern, which in a number of points also is able to convince. A second group only is interested in those phenomena of the experiment, which can't be explained conventionally and which prove the existence of scalar waves, whereas the third research group continually strives for new spectacular experiments and practical applications.

Documentation

Belonging to the experimentation and demonstration kit for the transmission of electric scalar waves

INDEL GmbH, Verlagsabteilung, Fax: +49-7721-51870
Tel.: +49-7724-1770
Postal and ordering address:
l.TZS, Prof. Dr. K. Meyl, Leopoldstr. 1, D-78112 St. Georgen/Schwarzwald
www.k-meyl.de mevl@k-meyl.de

Bibliography

A. Primary literature (Publications concerning the theory of objectivity):

[1] K. Meyl: Potentialwirbel, Band 1, INDEL Verlagsabt. Villingen 199O, ISBN 3-98O2542-1-6
[2] K. Meyl: Potentialwirbel, Band 2, INDEL Verlagsabt. Villingen 1992, ISBN 3-98O2542-2-4
[3] K. Meyl: Wirbelstrome, INDEL Verlagsabt. Villingen 1984, ISBN 3-98O2542-O-8 / Dreidimensionale nichtlineare Berechnung von Wirbelstromkupplungen, Diss. Uni. Stuttgart 1984
[4] K. Meyl: Einheitliche Theorie bei feldstarkeabhangiger Lichtgeschwindigkeit, Forschungsbericht der Fachhochschule Furtwangen 1992, l.Aufl. Seite 41-43
[5] K. Meyl: Wirbel des elektrischen Feldes, eine neue Storquelle? EMC Journal 1/95,6. J, S. 56
|6] K. Meyl: Gefahrdungspotential und Umwelrvertraglichkeit elektromagnetischer Felder am Beispiel der Funktelefone, Waerland 2/96 (1996), S. 21-23.
[7] K. Meyl: Wirbel des elektrischen Feldes, ein Beitrag zum Thema Uberlichtgeschwindigkeit; Wetter-Boden-Mensch 1/1997, ISSN 0940-5984, Seite: 79-89.
[8] K. Meyl: Physikalische Grundlagen einer Frequenztherapie, W.-B.-M. 6/1997, Seite: 8-15.
[9] K. Meyl: Die Wechselwirkung der Neutrinos, uber Massnahmen, die Halbwertszeit beim radioaktiven Zerfall herabzusetzen; intern.Tagung „Neue Energietechnologien aus USA", Zurich am 6.12.97, abgedruckt im NET-Journal (Neue Energietechniken), ISSN 1420-9292, Heft 1/2-1998, S. 14-20
[10] K. Meyl: Objektivitatstheorie, Ein Weg aus der quantenphysikalischen Sackgasse, 1. Beitrag: Der Ather und die Einsteinsche Fehlinterpretation, W.-B.-M. 3/1998, ISSN 0940-5984, Seite 39-44
[11] K. Meyl: Objektivitatstheorie, Ein Weg aus der quantenphysikalischen Sackgasse, 2. Beitrag: Die Vereinigungstheorie, Wetter-Boden-Mensch 4/1998, ISSN 0940-5984, Seite: 31-38
[12] K. Meyl: Longitudinale elektrische Wellen und Wirbel, Vortrag der „Internationalen Gesellschaft ftir interdisziplinare Wissenschaften" in Frankfurt am 21.3.1998, veroffentlicht im Vortragsband des "Bundesverbands gegen Elektrosmog e.V." ISBN 3-00-003124-3, Hohenstein, S.79-91
[13] K. Meyl: Biologische Wirksamkeit elektromagnetischer Wellen, Fluch (Elektrosmog) Oder Segen (Frequenztherapie)?, CO'MED, Fachmagazin fur Complementar-Medizin Nr. 10, Dez. 1998, S. 51-55
[14] K. Meyl: Elektrosmog, die physikalischen Grundlagen, Magazin 2000 plus Nr. 134,12/1998, S. 32-37
[15] K. Meyl: Freie Energie und die Wechselwirkung der Neutrinos, W.-B.-M. 3+4/1999, Seite: 21-29
[16] K. Meyl: Skalarwellen und ihre biologische Wirksamkeit, Vortragsband der Deutschen Gesellschaft fur Energetische und Informationsmedizin, Universitat Stuttgart am 17.07.1999, S. 47-52
[17] K. Meyl: Zur Brennglaswirkung des Mondes bei einer Sonnenfinsternis, NET-Journal (Neue Energietechniken), ISSN 1420-9292, Heft 7/8-1999, S. 13-17, sowie INET-Kongress-Vortrag dazu: Freie Energie im nachsten Jahrtausend, am 9.10.1999, Holiday Inn Heidelberg (Walldorf)
[18] K. Meyl: Raum-Energie-Technologie, Wechselwirkung der Neutrinos und energietechnische Nutzung der Teslastrahlung, Teil 1, Magazin 2000 plus Nr. 144, Dezember 1999, S. 62-67
[19] K. Meyl: Raum-Energie-Technologie, Teil 2, Magazin 2000 plus Nr. 145, Jan./Feb. 2000, S. 60-65
[20] K. Meyl: Teslastrahlung, W.-B.-M. 4/2000, ISSN 0940-5984, S. 31-43
[21] K. Meyl: Skalarwellen, Hagia Chora 5/2000, ISSN 0940-5984, S. 31-43
[22] K. Meyl: Teslastrahlung - die drahtlose Ubertragung von Skalarwellen, Kongressband Bregenz vom 15./16.4.2000, S. 181-196, Jupiter-Verlag, ISBN 3-906571-18-1
[23] K. Meyl: Skalarwellentechnik, INDEL Verlagsabt. Villingen-S. 2000, 1. Aufl, ISBN 3-98O2542-6-7
[24] K. Meyl: Nichtoptische Sonnenfinstermsphanomene Teil 1, Magazin 2000 plus/148,6/2000, S. 10-13
[25] K. Meyl: Nichtoptische Sonnenfmsternisphanomene Teil 2, Magazin 2000 plus/150, 8/2000, S. 26-29
[26] K. Meyl: Nichtoptische Sonnenfmsternisphanomene Teil 3, Magazin 2000 plus/151,10/2000, S. 12-17
[27] K. Meyl: Longitudinalwellen-Experiment nach Nikola Tesla, Vortragsband der Deutschen Ges. fur Energetische und Informationsmedizin, Universitat Stuttgart am 6.+.7.10.2000, S. 4.1-4.9
[28] K. Meyl: Skalarwellen und ihre Bedeutung fur die Medizin, Kolloquium vom 6.-8.10.2000 Bad Nauheim der BIT-Arztegesellschaft Vortragsband, Seite 87-96.
[29] Johannes von Buttlar im Gesprach mit Prof. Dr. Konstantin Meyl: Neutrinopower, 1. Auflage 2000, Argo-Verlag Marktoberdorf, ISBN 3-98O6584-8-1
[30] K. Meyl: Skalarwellen-Ubertragung, NET-Journal, ISSN 1420-9292, Heft 12-2000, S. 31-34
[31] K. Meyl: Longitudinalwellen-Experiment, DVR-Info im NET-Journal, Heft 12-2000, S. 21-24
[32] K. Meyl: Erdbeben und Vulkanausbrtiche, GA-Magazin, Heft 6, 2000, S. 11-14
[33] K. Meyl: Atomuhren, die falsch gehen, GA-Magazin, Heft 8, 2001, S. 10-13
[34] K. Meyl: Umpolungsproblematik und Sintflut, GA-Magazin, Heft 10,2001, S. 10-14

The suitcase for experiments from Transfer Centre St. Georgen:

Scalar wave transmission according to Tesla

Bidirectional signal and energy transmission with longitudinal
waves faster than light in a resonant circuit

Get to know the Tesla radiation and its fantastic properties personally. Demonstrate, what no textbook of physics is able to explain!
The experiments, which 100 years ago still were extremely complicated, today fit into an aluminium suitcase, which can be acquired by purchase. Test yourself the historic statements and perform the following experiments:

- transmission of energy and information
- effect back from the receiver on the transmitter
- proof of free energy (1 to 3 times over-unity)
- scalar wave transmission with app. 1.5 times the speed of light
- tunnel effect or the lacking to shield the waves
- disproval of the near-field interpretation.

The kit is offered in two versions:

As a demonstration-kit for 800.- Euro (incl. VAT)
With this the 6 experiments can be carried out without further aids. (Target group are judges, doctors, architects, interested laymen, etc.)

and as an experimentation-kit for 1400.- Euro (incl. VAT) with three different Spulensatzen, Frequenzzahler and zusatzlichem material. (Target group are physicists, engineers, handicraft enthusiasts who like to experiment, etc.)

Weitere Informationen zum Set und zu den Biichern, zu deren Inhalt und zu Vortragsveranstaltungen im Internet unter: http: / /www.k-meyl.de and www.meyl.eu

INDEL GmbH, Verlagsabteilung, Fax: +49-/0- 7721-51870
Tel.: +49-/0- 7724-1770
Postal and ordering address:
l.TZS, Prof. Dr. K. Meyl, Leopoldstr. 1, D-78112 St. Georgen/Schwarzwald

[35] K. Meyl: HF-technische Hinweise zum Skalarwellen-Ubertragungs-Set, DVR-Mitgliederjournal Nr. 45, 1/2001, S. 20-22 und NET-Journal, ISSN 1420-9292, Heft 3/4-2001, S. 44-45

[36] K. Meyl: Stellungnahme zum Artikel im Spiegel, DVR-Mitgliederjouraal Nr. 46, 2/2001, S. 43-44

[37] K. Meyl: Stellungnahme zu dem Beitrag ,,Skalarwellenubertragung", W.-B.-M. 2/2001, Seite: 77-79

[38] K. Meyl: Scalar Waves: Theory and Experiments, Journal of Scientific Exploration, Vol. 15, No.2, June 2001, ISSN 0892-3310, pp.199-205.

[39] K. Meyl: Skalarwellenstrahlung. Welche Bedeutung haben Skalarwellen fur die Medizin? , CO" MED, Fachmagazin fur Complementar-Medizin Nr.6, Juni/2001, S. 55-60.

[40] K. Meyl: Advanced Conzepts for Wireless Energy Transfer, High efficient Power Engineering with Scalar Waves, International Congress-Publications, Weinfelden, 23/24.6. 01, Jupiter- Verl., pp. 41-49

[41] K. Meyl: Fortschrittliche Konzepte zur drahtlosen Energieubertragung, Hocheffiziente Energietechnologie mittels Skalarwellen, Kongress ,,Neue Wasserstofftechnologien und Raumantriebe" 23.-24. Juni 2001 CH-Weinfelden, Kongressband S. 25-40, Jupiter-Verlag, ISBN 3-906571-20-3

[42] K. Meyl: Schwingungsmedizin, Physikalisch-technische Aspekte komplementarmedizinischer Diagnose- und Therapieverfahren, G.E.I.M.-Vortrag am 6.10.2001 Universitat Kaiserslautern, GZM-Praxis und Wissenschaft, ISSN 1430-4554,7Jahrg. 1/2002, S. 50-55

[43] K. Meyl: Skalarwellen Teil 1: Grundlage einer erweiterten Feldtheorie und prakrische Konsequenzen der Maxwell-Naherung, NET-Journal, ISSN 1420-9292, Heft Juli/August 2002, S. 31-47

[44] K. Meyl: Skalarwellen Teil 2: Weltgleichung und Wellengleichung als Konsequenz der erweiterten Feldtheorie, NET-Journal, ISSN 1420-9292, Heft September/Oktober 2002, S. 44-47

[45] K. Meyl: Wirbelstrukturen als Element der Informationsubertragung in biologischen Systemen, Kolloquium vom 3.-5.10.2002 Bad Nauheim der BIT-Arztegesellschaft, Vortragsband, Seite 77-96.

[46] K. Meyl: Skalarwellen, Grundlage einer erweiterten Feldtheorie, Vortrag am VII.Kongress des IAG vom 18.-20.10.2002 in Mainz-Finthen, Kongressband ISBN 3-9804228-3-6 l.Aufl.2002, S. 118-135.

|47] K. Meyl: Nutzungsmoglichkeiten der Skalarwellentechnik, Neutrino-Power als Chance fur das neue Jahrtausend, Magazin 2000 plus I Nr.177, November/Dezember 2002, S. 60-63.

[48] K. Meyl: Schwingungsmedizin, Bioresonanz durch Skalarwellentechnik, Magazin 2000 plus I Nr. 178, Medizin Spezial 13,2002, S. 52-57

[49] K. Meyl: Die Wellengleichung, Grundlage der Skalarwellen-Physik, Magazin 2000 plus I Nr.179, Januar/Februar 2003, S. 6-12

[50] K. Meyl: Elektrische bzw. magnetische Skalarwellen im Kreuzfeuer der Kritik. Prof. Dr.-Ing. Konstantin Meyl nimmt Stellung zu kritischen Fragen, CO'MED, Nr. 1, Januar/2003, S. 52-54.

[51] K. Meyl: Freie Energie und Neutrinopower, Vortrag am 26.10.2002 in Bensheim auf dem Kongress: (Vom Band abgetippt von I.Schneider) Neue universale Energielosungen, Sammelband der Kongressbeitrage, Jupiter Verlag 2003, ISBN 3-906571-22-X, S.57-79

[52] K. Meyl (D.NeubronnerV. Die Rundfunkgotter, Teslawellen im Altertum, Matrix 3000 Band 16, 7/8-2003, ISSN 14394154, S.40-43

[53] K. Meyl: Erdwachstum durch Neutrinopower, Magazin 2000 plus Nr.188, Extra 3, 9/10-2003, S. 6-13

[54] K. Meyl: Faraday vs. Maxwell, Nikola Tesla Energy Science Conference, Washington DC 8.11.03, IRI

[55] K. Meyl: Physikalische Grundlagen fur die Informationsverarbeitung im Menschen, Kongressband zu den Festspieigesprachen 2002, (Hg. Simma Kletschka) Facultas Verlage Wien 2003, Band 27, Wiener Internationale Akademie fur Ganzheitsmedizin, ISBN 3-85076-648-9, Seite 38-59

by Prof. Dr.-Ing. Konstantin Meyl:

Sendetechnik der Gotter

Konstantin the Great is inaugurated in ancient send receive engineering by his teacher in the Roman emperor palace 304 A.D.

Abstract: 1.Auflage 2004(in German)

- Has god Apollo in Delphi broadcasted at 5.4 MHz?
- Were the Greek temples telegraphy transmitters?
- Were the temple priests amateur radio operators?
- Was Homer radio reporter by order of the gods?
- Were the oracles receiving stations?
- Have oracle interpreters deciphered the transmission code?
- Which bridges did the Pontifex Maximus build?

All are questions, which are dealt with and explained in detail in 30 lessons. In the year 304 A.D. we witness, how the later Roman emperor Konstantin the Great is inaugurated in the secret broadcasting technique of the gods by his teacher. It is an exciting time of upheavel, because the old telegraphy is almost dead. The intestines of animals to sacrifice, from the convulsions of which the radio signals are read off, are scarce goods. Instead radiotelephony should be introduced, which had been tested successfully with the Pantheon in Rome by emperor Hadrian.

But new dispute is initiated: should broadcasting be introduced or rather cellular phone? But those, who tamper around without licence, are chased and fought as always.

When the book is available in English, you will be informed per internet:

www.k-meyl.de www.meyl.eu

INDEL GmbH, Verlagsabteilung, Fax: +49-7721-51870
Tel.: +49-7724-1770
Postal and ordering address:
1.TZS, Prof. Dr. K. Meyl, Leopoldstr. 1, D-78112 St. Georgen/Schwarzwald

B. Secondary literature (Publications about the theory of objectivity):

[1] P. Schellenberg: Buchbesprechung zu K. Meyl: Potentialwirbel, Bd. 1, Efodon News 6 (1992), S. 11

[2] Dr. R. Wohlleben: Buchbespr. zu K. Meyl: Potentialwirbel, Band 2, Frequenz 50 (1996) 1-2, S. 10

[3] Steinbeis-Stiftung fur WirtschaftsfOrderung: Technologiepreis fur STZ-Leiter, Transfer Zeitung 3/94 (1994), S.6

[4] A. Waser (Herausg.): Die ratselhafte Natur - The Puzzling Nature, AW Verlag, Luzern (1996), ISBN3-9521O59-O-2

[6] K. Lorek: Buchvorstellung in "Implosion", Biotechnische Nachrichten Nr. 116 (8/1996), S. 64

[7] Dr. H. Lumpe: Potentialwirbel, neues Weltbild; Raum & ZeitNr. 86, Marz/April 1997, S. 102-103

[8] Inge Schneider: Buchbesprechung zu K. Meyl: Elektromagnetische Umweltvertraglichkeit, Teil 1, NET-Journal, ISSN 1420-9292, Jg. Nr.2, Heft 3, Marz 1997, Seite 23

[9] W. Martin: Buchbesprechung zu Teil 1, Wetter-Boden-Mensch 2/1997, ISSN 0940-5984, S. 62-63.

[10] RTL: Prof Dr.-Ing.Meyl zu Gast bei der RTL-Talkshow von Ilona Christen am 30.5.97, abgedruckt im NET-Journal, ISSN 1420-9292, Jg. Nr.2, Heft 6/7 1997, Seite 30-31

[11] Inge Schneider: zu „Prof. Dr.-Ing. Konstantin Meyls Buch Elektromagnetische Umweltvertraglichkeit", NET-Journal, ISSN 1420-9292, Jg. Nr.2, Heft 6/7 1997, Seite 32-33

[12] W. Heidrich: Geht die Expertentagung 1997 in die Geschichte ein? W.-B.-M. 6/1997, S. 3-4

[13] J. Heinzerling: Die Technik des dritten Jahrtausends, Magazin 2000 plus Nr.125, Marz 1998, S. 57/58

[14] Inge Schneider: Buchbesprechung zu K. Meyl: Elektromagnetische Umweltvertraglichkeit, Teil 2, NET-Journal, ISSN 1420-9292, Jg. Nr.4, Heft 3, Marz 1999, Seite 35

[15] W. Martin: Buchbesprechung zu Teil 2, Wetter-Boden-Mensch 2/1999, ISSN 0940-5984, S. 46+59.

[16] P.Rosch: Glanzend, Prof. Meyl zu Elektrosmog, Leserbrief, Magazin 2000 plus Nr.136, 2/1999, S. 77

[17] Portrait der Kongress-Referenten, zu Prof. Meyl: Energie aus dem Weltraum, 5. internationaler Kongress vom 26.-28.2.1999 in Dusseldorf, Magazin 2000 plus Nr. 136, 2/1999, S. 2 + 16 mit:

[18] P.Wiesner: Bericht zum 5. internationalen Kongress „Dialog mit dem Universum", zum Beitrag Prof. Meyl:„fordert eine dezentrale elektr. Energietechnik", Magazin 2000 plus Nr.136, 2/1999, S. 38-41

[19] I. Schlotterbeck: Bucher, die wir empfehlen, Magazin 2000 plus Mr. 142, Sept./Oktober 1999, S. 96

[20] H.-J. Ehlers: Freie Energie, Meyls Neutrino-These; Raum & Zeit Nr. 101, Sept./Oktober 1999, S. 94

[21] I, Schneider: Bericht zum Kongress vom 9.+10.10.99, Heidelberg, zu K. Meyl: Freie Energie im nachsten Jahrtausend, NET-Journal, ISSN 1420-9292, Jg. Nr.4, Heft 10/11, Okt./Nov. 1999, S. 8 ff.

[22] Sabine Krummer: Weltpremiere, Magazin 2000 plus Nr.145, 1+2/2000, S. 59 und im Schwarzwalder Bote vom 19.11.99: TP-Forum eroffhet mit Weltpremiere, Prof. Meyl berichtet iiber Teslawellen.

[23] Diermar Schindler: Neutrinos - Energie aus dem Kosmos, Schwarzwalder Bote Nr. 275 vom 27.11.99

[24] Schneider: Neutrino-Power - Energie aus dem Kosmos, Bericht zu Vortrag und Demo von Prof. Dr. K. Meyl am 25.11.1999 in Villingen, NET-Journal, ISSN 1420-9292, Jg. Nr.4, Heft 12/1999, Seite 4-6

[25] Schneider: Durchbruch in der Freien-Energie-Forschung; Interview mit Prof. Dr.-Ing. Konstantin Meyl, NET-Journal, ISSN 1420-9292, Jg. Nr.4, Heft 12, Dezember 1999, Seite 7-9.

[26] Dulling: Professor Meyl und die Freie Energie, TZ-Journal 1999/2000, Seite 5.

[27] Ulrich Arndt: Das Phanomen der Wirbel, Buchbesprechung zu Elektromagnetische Umweltvertraglichkeit Teil 1 und Teil 2, Esotera 1/2000, Verlag Hermann Bauer, S. 50,51

[28] Rainer Borgmann: Energie aus dem Kosmos, Magazin 2000 plus Nr. 145, Januar/Feb. 2000, S. 58-59

[29] Sabine Krummer: Wissenschaftler sprechen von Sensation, Im Villinger Technologie-Forum fuhrte Konstantin Meyl seine Skalarwellen vor, Schwarzwalder Bote vom 7.2.2000

[30] Dr.B.Tausendfreund: Uber biologische und medizinische Auswirkungen von elektrischen Potentialwirbeln und elektromagnetischen Longitudinalwellen,, CO'MED, 2/2000, S. 92

[31] Dr. H.Hantsche: Neues aus Physik und Technik, Info-Blatt der Feien Akademie, Berlin 3/2000, S.3

[32] A.Milinkovic: Weiterer Nachweis der Skalarwellen, NET-Journal, Jg. Nr.5, Heft 3, Marz 2000, S. 26

[33] Vorstellung des Referenten Prof Dr.-Ing. Konstantin Meyl, Kongressband Bregenz vom 15/16.4.2000, S. 180, Jupiter-Verlag, ISBN 3-906571-18-1

[34] Dr. Kunze: Leserbrief zu K.Meyl: Raum-Energie-Technologie, Magazin 2000 plus 147, 4-2000, S. 93

[35] Schneider: Teslastrahlung, die drahtlose Ubertragung von Skalarwellen von Prof. Dr.-Ing. Konstantin Meyl, NET-Journal, ISSN 1420-9292, Jg. Nr.5, Heft 4/5- 2000, Seite 14-15.

[36] Dr. Reichwein, Peters: Zellulare Elektromagnetische Systemsteuerung, Der Freie Arzt 5 (2000) im Wissenschafts-Forum (Anhang, S. IV - XXIII)

[37] Ulrich Arndt: Die Energie aus dem Nichts, Esotera 7/2000, Verlag Hermann Bauer, S. 62-66

[38] Besprechung zum Video „EMUV" von Prof. Dr. Meyl, Esotera 7/2000, Verlag Hermann Bauer, S. 30

[39] A.Manthey: Bericht zur Berliner Tagung fur neue Energietechnologien (8.7.2000), zu Theoretische Ansatze (u.a. K. Meyl), NET-Journal, ISSN 1420-9292, Jg. Nr.5, Heft 7/8 2000, S. 14 ff.

[40] Schneider: Uber das Experimentier-Set zur Ubertragung von Skalarwellen von Prof. Dr.-lng. Konstantin Meyl, NET-Journal, ISSN 1420-9292, Jg. Nr.5, Heft 9, September 2000, Seite 4-7.
[41] Buchbesprechung zu Prof. Dr.-Ing. Konstantin Meyl: Elektromagnetische Umweltvertraglichkeit, Teil 1 und Teil 2, Schweizerische Zeitschrift fur RGS, ISSN 1420-4894, Nr.233, Heft 4-2000, Seite 54-56
[42] Adolf und Inge Schneider: Energie aus dem All, ll.Kap.: Drahtlose Ubertragung von Skalarwellen durch Prof.Dr.-Ing.Konstantin Meyl, S.312-324, Jupiter Verlag 9/2000, l.Aufl. ISBN 3-906571-17-3.
[43] Dr.J.Lechner. Starfelddiagnostik, Medikamenten- und Materialtest Teil2, Kap.2.4.2 Beruhrungslose skalarwellengetragene Informationsubertragung, S. 173-178, Verlag Wtlhr 2000, ISBN 3-927344-44-3
[44] Dr. B. KOhler: Nachlese zum Jubilaumskolloquium der BIT-AG vom 6.-8.10.2000 in Bad Nauheim: Einen weiteren Hohepunkt stellte das Referat von Prof. K. Meyl dar,... COMED, 12/2000, S. 104
[45] Schneider: Buchbesprechung zu ,,Neutrinopower", NET-Journal, Jg. 5, Heft 12, Dezember 2000, S. 39
[46] Fachhochschule Furtwangen: Vorlesungsangebot fur das SS 2001, S.8, Prof. Dr. K. Meyl: EMUV.
[47] Vill: Die elektrophysikalische Mauerwerksentfeuchtung, EV.Verl.2001, ISBN 3-934139-04-3, S.26-33
[48] Kraft: Eroberung von physikalischem Neuland, Buchbesprechung zu ,,Neutrinopower", und
[49] Rattcher: Sind morphische Felder Neutrinos?, Zeit Geist, Heft 3,2001, S. 29 und S. 9.
[50] Dr.R.Kra6nigg: Skalare Wellen, Regulations Medizin 6, Heft 3, 2001, S. 89-96.
[51] Dr.A.Rossaint: Physikalische Grundlagen und biologisch-medizinische Schlussfolgerungen fur den beruhrungslosen Resonanztest Teil 1, Zeitschrift Hier & Jetzt, 3/2001, S.22-27 +Teil2,4/2001, S.22-25
[52] GZM-Kongress Berlin, 13.5.2001, zu dem Vortragenden Prof.Dr.K.Meyl: Skalare-/Teslawellen zur zellularen Energie- und Info. , GZM-Praxis und Wissenschaft, ISSN 1430-4554, 6,Jahrg. 1/2001, S.36
[53] Dr.P.Reichert: Die Medizin der Zukunft - Schwingungen start Pillen, Berlin Nachlese zum 6. Europaischen Kongress fur Ganzheitliche Zahn-Medizin 10.-13.5.2001, GZM-Praxis und Wissenschaft, ISSN 1430-4554, 6.Jahrg. 1/2001, S.56 zuK.Meyl: Schwingungsmedizin und Zellkommunikation.
[54] M.Dworschak: Schwarzwalder Kopernikus, Spiegel-Artikel vom 21.5.01, S. 198-199, abgedruckt im DVR-Mitgliederjournal 2/2001, Seite 41-42
[55] F.Lutz: Bis jetzt unwiderlegt, Wissenschaftler nehmen Professor Meyl in Schutz, Sudkurier Nr. 136 vom 16.6.2001 und Badische Zeitung vom 19.6.2002, Seite 22.
[56] S.Scheurer: Kopemikus untersucht Skalarwellen, Schweizerisches Bodensee Tagblatt Turgau, 21.6.01
[57] Schneider: Introduction of the author Prof.Dr.K.Meyl: Advanced Conzepts for Wireless Energy Transfer, International Congress-Publications, Weinfelden, 23./24.6.2001, Jupiter-Verlag, pp. 23-24.
[58] R.Schmid: Neues aus der Homoopathie-Forschung, zur Tagung der Samuel-Hahnemann-Stiftung vom 6.-8.4.2001 in Simmerath-E., Globuli 11/2001, S.11-12.
[59] Ralph Netzker: Jurassic Quark, Holden, Wegener, Meyl, ein theoretischer Dreisprang, im Internet unter http://home.t-online.de/home/ralph.netzker/quark.htm vom 25.10.01
[60] H.-P. Studer: Neue Energien fur die Zukunft, Vita Sana Magazin fur Dialog und Ges., 9/2001, S. 6-9
[61] Harro Wilke: Leserbrief zu Schwarzwalder Kopernikus, Magazin 2000 plus Nr. 164,10/2001, S. 92
[62] Dr. R.Krafinigg: Skalare Wellen, Arztezeitschrift fur Naturheilverfahren, 43, 1/2002, S. 19-27.
[63] Dr.C.Bollkampen: Bewusstsein im EnergetischenKontinuum, 10/2002, ISBN 3-8311-4016-2.
[64] A. und I. Schneider: Bericht vom Kongress ,,Universale Energielosungen", 26727.10.2002 in Bensheim, zu dem Beitrag von Prof.Dr.K.Meyl: Freie Energie und Neutrinopower, NET-Journal, Jg. 7, Heft 11/12 November/Dezember 2002, S. 21-28.
[65] Dr. P. Rothdach, Dr. H. Boiler u.a.m: Leserbriefe zum Beitrag: Elektromagnetische Skalarwellen im Kreuzfeuer der Kritik. COMED, 1/2003, S. 4-5 und COMED, 11/2002, S. 4: "Facit (Rothdach); Die Meylsche Theorie ist weder mathematisch, noch theoretisch-physikalisch noch experimentell widerlegt"!
[66] D. Schindler: Kopemikus aus dem Schwarzwald, Professor Meyl stellt neue Erkenntnisse der Teslastrahlumg vor, Bericht im Schwarzwalder Bote Nr. 46 VS, vom 25.02.2003
[67] H.-H. Gimbel: Neue Energielo'sungen, Kongressbericht, Wohnung + Gesundheit 3/03 Nr. 106, S. 60
[68] C. Nack: Umstritten aber begehrt. Viele Akademiker kamen Zum Experimentalvortrag von K. Meyl am 14.03.2003 im Technologiepark von Villingen-Schwenningen, Sudkurier 63/TG v. 17.03.03, S.27
[69] G. Hauser: ,.Gebaude der Physik wankt", Meyl sieht seine Theorie durch neueste Berichte bestatigt, Siidkuner Nr. 93/V, 23.04.2003
[70] Prof. Dr. J. Gruber: Grosser experimenteller Erfolg von Prof. Meyl, Energie aus dem Feld nachgewiesen! DVR-Mitglieder-Journal 1/03 Nr. 51 vom 4.4.03, ISSN 1435-0815, S. 101-102
[71] Dr. H. Kersten uber K. Meyl's Forschung: Erdwachstum durch Neutrinoabsorbtion, Technische Universitat Berlin, Internationales Kolloquium: Erdexpansion - eine Theorie auf dem Prufstand, Schloss Theuern am 24.+25.05.2003, Umdruck der TU Berlin Sekr. BH4 Lagerstattenforschung, s.a. Amberger Zeitung vom 28.5.03 und Amberger Nachrichten vom 29.5.03

[72] Dr. P. Rothdach: ,,Skalarwellen gibt es nicht und die Welt ist eine Scheibe", GeoForum 24, 6/2003, Seite 20-22

[73] Inge Schneider: zu Prof. Dr.-Ing. K. Meyls Forschung: Antiker Gotterfunk und futuristische Skalarwellenkommunikation, NET-Journal, Jg. Nr. 8, Heft 7/8 2003, Seite 31 (mit Ankundigungen zu Seminaren von Prof. Meyl in Munchen, an der Universitat Stuttgart und in Washington DC, Seite 42)

[74] J.K.Klasmann: Elektrosmog, Gefahrliche Felder? Gesundheit 9/2003, S.103-104.

[75] Gesundheitsrisiko Handy", Hauptreferent Professor Meyl..., Zollern-Alb-Kurier, 8.10.2003 und K.-H. Schlenker, Leserbrief vom 30.9.2003, s.a. Siidwest Presse: Kommission fordert Absenkung von Grenzwerten, Hohenzollerische Zeitung vom 7.10.2003.

[76] Dr. H.-J. Klose: Die Grundregulation des Menschen, Kongressband zu den Festspielgesprachen 2002, Simma-Kletschka (Herausgeber): Ganzheitliche Zahnheilkunde, Facultas Verlage Wien 2003, Band 27, Wiener Internationale Akademie fur Ganzheitsmedizin, ISBN 3-85076-648-9, Seite 95-98

[77] Dr. Valone, Integrity Research Institute: Nikola Tesla Energy Science Conference, Washington DC November 8th.+9th.2003, Conference publications, speakers biographies and abstracts.

C. Literature concerning the electromagnetic and biological compatibility

[1] R. O. Becker: Heilkraft und Gefahren der Elektrizitat (Cross Currents) 2. Aufl.Scherz Verlag (1994)

[2] P. Brodeur: Mikrowellen (The zapping of America) Augustus Verlag Augsburg (1989)

[3] EMVG: Gesetz uber die EMV von Geraten, Bundesgesetzblatt Teil I vom 9.11.1992

[4] Flanagan: Elixier der Jugendlichkeit, Waldthausen Verlag Ritterhude 1992, 1. Aufl.

[5] E. Habiger u. a.: Elektromagnetische Vertraglichkeit, 2. Aufl. Verlag Technik, Munchen 1992

[6] E. Habiger: EMV, Huthig Buch Verlag Heidelberg (1992), ISBN 3-7785-2O92-X

[7] E. Habiger: EMV-ubergreifende Aspekte zu benachbarten Problemfeldern, Elektrie 48 (1994), H. 5/6, S. 163-167

[8] N. Harthun: Naturgemasse Technik - Wege fur die Forschung nach Viktor Schauberger, Verlag Delta Design, Berlin 1996.

[9] H. L. KOnig: Unsichtbare Umwelt (Wetterfuhligk.), 5. Aufl., Verlag Moos & Partner Munchen

[10] Anton Kohling: Grundlagen der Funkentstorung in der Bundesrepublik Deutschland, etz Bd. 108 (1987), Heft 10.

[11] G. Nimtz: Mikrowellen, Einfiihrung in Theorie und Anwendung. 2. Aufl. Mannheim/Wien/Zurich: BI-Wissenschaftsverlag 199O, ISBN 3-411-O32O3-O

[12] Novitskii, Yu. I. : Effects of a magnetic field on the dry seeds of some cereals. Proceedings of Conference on the Effect of Magnetic Fields on Biological Objects, Moscow, p. 52, 1966.

[13] Plato: Samfliche Werke 5, Rowohlts Klassiker Nr. 47, S. 188,66e

[14] A. S. Presman: Electromagnetic Fields and Life. Plenum Press, New York - London, 197O

[15] V. Schauberger: Die Entdeckung der Levitationskraft, Implosion 1995 Nr. 112

[16] H. Schulz, W. Oppitz: Lokale Hyperthermie durch hochfrequente Wirbelstrome, Medizin Technik 1, 1987.

[17] G. A. Ulmer: Wellen- und Elektrosmog, Ulmer Verlag (1994) ISBN 3-924191-73-5

[18] Vitruvius Pollio, Marcus: Zehn Bucher uber Architektur, WBG 1987

[19] A. D. Watt and E. L. Maxwell: Characteristic of Atmospheric Noise from 1 to 1OO Kc/s. Symposium on the Propagation of VLF Waves, Boulder, Col., Paper 35, Jan. 1957.

D. Literature concerning physics in general (particle physics, etc.)

[1] H. Armbruster, G. Grunberger: Elektromagnetische Wellen im HF-Bereich, Huthig und Pflaum Verl.

[2] W. Bauer: Klassische Physik, Graphia Druck, Salzburg (1975), Eigenverlag.

[3] K. Bethge, U. E. Schroder: Elementarteilchen, Wissenschaftliche Buchgesellschaft Darmstadt (1986)

[4] G. Bosse, Grundlagen der Elektrotechnik II, BI 183, Hochschultaschenbuch-Verlag, Mannheim 1967

[5] Bronstein u.a.: Taschenbuch der Mathematik, 4.Neuaufl. Thun 1999

[6] A. Einstein: Grundztlge der Relativitatstheorie, S. 162, Anhang II; allg.Bemerkungen C, 5. Aufl., Vieweg + Sohn, Braunschweig 1973.

[7] A. P. French: Special Relativity, M.I.T. (1968) / Vieweg Verlag (1971) ISBN 3-528-O3546-3

[8] G. Galeczki, P. Marquardt: Requiem fur die Spezielle Relati vitat, Verlag Haag+Herchen (1997)

[9] U. Gradmann/H. Wolter: Grundlagen der Atomphysik, AVG, Frankfurt a.M. 1971.

[10] Grimsehl: Lehrbuch der Physik, 2.Bd, 17.Aufl. Teubner Verl. 1967
[11] J. D. Jackson, Classical Electrodynamics, 2nd. Ed., John Wiley, New York, 1975.
[12] Kleine Enzyklopadie Atom, Verlag Chemie GmbH, Weinheim 1970
[13] K. Kupfmuller: Einfilhrung in die theoretische Elektrotechnik, Springer-Verlag Berlin, 12. Aufl. 1988
[14] H. G. Kussner: Grundlagen einer einheitlichen Theorie der physikalischen Teilchen und Felder, Musterschmidt-Verlag, Gottingen 1976, ISBN 3-7881-6O35-7
[15] Kuchling: Physik, Gl. At4, VEB-Leipzig, 11. Aufl. 1974
[16] G. Lehner, Elektromagnetische Feldtheorie, Springer-Verlag Berlin, Heidelberg 1990.
[17] H.-J. Lugt: Vortex flow in nature und technology. Krieger publishing company 1995
[18] J. C. Maxwell: A Treatise on Electricity & Magnetism, vol.2,
Chapter XX: Electromagnetic Theory of Light. Dover Publ. New York
[19] Meinke, Gundlach: Hochfrequenztechnik, 4.Aufl. Springer-Verlag Berlin 1986
[20] Mende, Simon: Physik, Gl. 10. 39, VEB-Leipzig, 4. Aufl. 1974
[21] G. Mierdel: Elektrophysik, Huthig Verlag Heidelberg (1972) ISBN 3-7785-O243-3
[22] O. Nachtmann: Phanomene und Konzepte der Elementarteilchenphysik,
Vteweg, Braunschweig 1986, ISBN 3-528-O8926-1
[23] W. Pauli: Aufsatze und Vortrage uber Physik und Erkenntnistheorie, Vieweg + Sohn, Braunschw. 1961
[24] R.W. Pohl: Einfuhrung in die Physik, Bd.2 Elektrizitatslehre, 21.Aufl. Springer-Verlag 1975
[25] H. Preussker: Der Wirbelring, Halstenbeck 2002
[26] Shu-wen Zhou: Abnormal Physical Phenomena Observed When the Sun, Moon, and Earth are Aligned, 21^{st} Century Science & Technology, Fall 1999, Vol. 12, No. 3, pp. 54-61.
[27] K. Simonyi, Theoretische Elektrotechnik. 7. Aufl. VEB Verlag Berlin 1979. S. 921 - 924.
[28] K. Simonyi: Physikalische Elektronik, Kap.: 8.4 Das Magnetron
[29] K. Stierstadt: Physik der Materie, VCH, Weinheim 1989.
[30] D. F. Taylor, On the Mechanism of Aluminium Corrosion in Metallized Film Capacitors,
IEEE Transactions on EI-19, August 1984, No. 4, pp. 288-293.
[31] Jean-Pierre Vigier and the Stochastic Interpretation of Quantum Mechanics, selected and edited Stanley Jeffers, Bo Lehnert, Nils Abramson, and Leve Chebotarev. Montreal: Apeiron, 2000.
[32] A. Yializis, S. W. Cichanowski, D. G. Shaw: Electrode Corrosion in Metallized Polypropylene Capacitors, Proceedings of IEEE, Int. Symposium on Electrical Insulation, Bosten, Mass., June 1980;
[33] Zinke, Brunswig: Lehrbuch der Hochfrequenztechnik, 1. Bd., 3.Aufl. Springer-Verlag Berlin 1986

E. Literature concerning Tesla and criticism of textbook physics

[I] M. Cheney: Tesla, Man out of Time, Barnes & Noble Books, New York, 1993,
ISBN O-88O29-419-1 und Omega-Verlag (1996) ISBN 3-93O243-O1-6
[2] D. H. Childress: The Fantastic Inventions of Nikola Tesla, Adventures Unlimited Press (1993)
[3] J. DeMeo: The Orgone Accumulator Handbook, ISBN O-9261855-O-7
[4] G. Galeczki, P. Marquardt: Requiem fur die Spezielle Relativitat, Haag+Herchen (1997),
[5] J. K. Kowalczynski: Critical Comments on the Discussion about Tachyonic Causal Paradoxes and the Concept of Superluminal Reference Frame, Intern. Journal to theoretical Physics, Vol. 23, No. 1, 1984
[6] J. Marinsek: Rationale Physik oder wissenschaftliche Science fiction?
dbv-Verlag fur die Technische Universitat Graz (1989) ISBN 3-7O41-O176-1
[7] H. C. Montieth: The Unified Field Theorie, MUFON Symposium Proc, Seguin, Texas, 1980
[8] F. Moser: BewuBtsein in Raum und Zeit - Grundlagen einer holistischen Weltauffassung auf
wissenschaftlicher Basis, Leykam Graz, 1989
[9] H. A. Nieper: Revolution in Technik, Medizin, Gesellschaft; MIT Verlag Oldenburg (1982)
[10] O. Oesterle: Ausweg aus der Sackgasse, Ein ganzheitliches naturwissenschaftliches Weltbild,
1. Aufl., Jupiter-Verlag, Bern 1996, ISBN 3-9O6571-16-5
[11] Rho Sigma (Dr. Rolf Schaffranke): Forschung in Fesseln, das Ratsel der Elektro-Gravitation.
Ventla-Verlag, Wiesbaden (1972)
[12] N. Tesla: III. The Singular Misconception of the Wireless (Famos Scientific Illusions), Electrical
Experimenter, Feb. 1919, p. 732.
[13] Tesla's verschollene Erfindungen, VAP, Wiesbaden (1994) ISBN 3-922367-93-3
[15] N. Tesla: Complete Patents, TeslaBook Company (1983) ISBN O-96O356-8-2, daraus:
[16] N. Tesla: Apparatus for Transmission of Electrical Energy, US-Patent-No.: 649,621, New York 1900,
Dr. Nikola Tesla: Complete Patents pp318-321.

[17] Nikola Tesla: Method of and Apparatus for Controlling Mechanism of Moving Vessels or Vehicles, US-Pat. 1898, Nr. 613,809. Complete Patents: S. 351
[18] Nikola Tesla: Famous Scientific Illusions, III. The Singular Misconception of the Wireless, Electrical Experimenter, Feb. 1919, printed in Tesla Said, p. 197
[19] Nikola Tesla: The Problem of Increasing Human Energy, The Century Monthly Magazine, June 1900, ISBN 1-882137-00-0, Page i-15
[20] N. Tesla: Die Ubertragung elektrischer Energie ohne Drahte..., Electrical World and Engineer vom 7.1.1905; Edition TeslaBd. 4, S. 131.
[21] N. Tesla, New York Times vom 15.9.1908; Edition Tesla Bd. 6, S. 241.
[22] Tesla Said (J.T.Ratzlaff), Tesla Book Company, ISBN 0-914119-00-1
[23] N. Tesla: Experiments with Alternate Currents of High Potential and High Frequency, Lindsay Publications Inc, ISBN 0-917914-39-2
[24] W. Theimer: Die Relativitatstheorie, A.Francke AG Verlag Bern (1977) ISBN 3-772O-126O-4

F. Literature concerning geophysics, geology, geography and astronomy

[1]: Kendrick Frazier: Das Sonnensystem, Time-Life Bucher, Amsterdam (1991).
[2] Carey, S. W.: Theories of the Earth and Universe. University Press: 1-413, Stanford, California.
[3] Oesterle, O.: Goldene Mitte: Unser einziger Ausweg, Universal Experten Verlag, Rapperswil (1997)
[4] Hilgenberg, O. C: Vom wachsenden Erdball, Berlin 1933, Eigenverlag. und Neues Jahrb. Geol. Palaont. Abh. 116, 1, Berlin (1962).
[5] Jordan, P.: Die Expansion der Erde. Vieweg 1-180, Braunschweig (1966).
[6] Robert Bauval und Graham Hancock: Das Geheimnis der Pyramiden, Der Schlussel zur Sphinx, List Verlag (1996) und in S3 (Die grossen Ratsel VII) am 25.5.97
[7] Mitton, S. (Herausg.): Cambridge Enzyklopadie der Astronomie (The Cambridge Encyclopaedia of Astronomy), Orbis Verlag (1989).
[8] Miller, R.: Driftende Kontinente, Time-Life Bucher, Amsterdam (1991).
[9] Hermann Wild: Technologien von gestern, Chancen fur morgen, Jupiter-Verlag Bern 1996
[10] Zecharia Sitchin: The Lost Realms, Knaur Verlag Munchen 1992, ISBN 3-426-04827-2
[11] Werner Raffetseder: Sonnenfinsternis, Hugendubel Verlag, Munchen 1999, ISBN 3-89631 -302-9

G. Literature concerning free energy

[1] R. L. Clark: Tesla Scalar Wave Systems, The Earth as a Capacitor, The Fantastic Inventions of Nikola Tesla, ISBN 0-932813-19-4
[2] H.-P. Thietz: Tatort Erde, VAP (1996), ISBN 3-922367-62-3
[3] Louis Kervran: Biological Transmutations, s.a.:
[4] J. Heinzerling: Energie aus dem Nichts, Bettendorf'sche Verlagsanstalt, 1. Aufl. 1996
[5] J. Manning: The Coming Energy Revolution - The Search For Free Energy, Avery Publishing Group, New York, USA, 1996 und Omega-Verlag, Dusseldorf 1997.
[6] G. Hilscher: Energie fur das 3. Jahrtausend, VAP-Verlag Wiesbaden 1996
[7] A. Schneider: Energien aus dem Kosmos, Jupiter-Verlag 1989
[8] I. Schneider: Neue Technologien zur Freien Energie, Jupiter-Verl. 1994, S. 14
[9] Dr. H. A. Nieper: Revolution in Technik, Medizin, Gesellschaft; MIT Verlag Oldenburg (1982)
[10] Prof. Shinchi Seike: The Principles of Ultra Relativity, Space Research Institute, 1990, ISBN 915517-1
[11] M. Cheney: Nikola Tesla, Man out of Time, Barnes & Noble Books, New York, 1993, ISBN O-88O29-419-1 und Omega-Verlag (1996) ISBN 3-93O243-O1-6
[12] Prof. J. Gruber: Kalte Fusion und Raumenergie, Bericht zur 7. Internationalen Konferenz uber "kalte Fusion" vom 19.-24.4.1998 in Vanvouver, B.C., Kanada (Infinite Energy, Issue 19, 1998) und Bericht zum "International Symposium on New Energy" vom 23.-26.5.1997 in Denver, Colorado, USA (Denver-Bericht der Fern Universitat Hagen)
[13] H.-J. Ehlers: Special 7, Raum & Zeit Dokumentation, EHLERS Verlag, Sauerlach, 1. Aufl. (1994)
[14] O. Alexandersson: Lebendes Wasser; W.Ennsthaler Verlag Steyr, 1993
[15] V. Schauberger: Die Entdeckung der Levitationskraft, Implosion 1995 Nr. 112
[16] A. Waser (Herausg.): Die ratselhafte Natur - The Puzzling Nature, AW Verlag, Luzern (1996), ISBN 3-9521O59-O-2

H. Literature concerning medicine, biology and chemistry

[1] U. Luttge, M. Kluge, G. Bauer: Botanik, 2. Aufl.- Weinheim, VCH (1994) ISBN 3-527-30031-7
[2] N.Begich: Towards A New Alchemy, The Millenium Science, Earthpulse Press 1996, dt. Ubers.: Auf den Spuren einer neuen Alchemie, Omega-Verlag 1997
[3] Couto: Die kosmische Oktave, Synthesis Verlag Essen 1984
[4] Prof. Dr. H. Heine: Grundregulation und Extrazellulare Matrix - Grundlagen und Systematik, Lehrbuch der biologischen Medizin, (1991) 2.Aufl. Hippokrates Verlag Stuttgart, Seite 63
[5] U. Warnke: Bioresonanztherapie - Wunsch und Wirklichkeit. Medizin transparent Nr.2/1996, S.36-37
[6] Dr. H. Clark: The Cure For All Diseases (1995), dt. Ubers.: Heilung ist moglich (1997) Knaur Verlag
[7] Dr. Hulda Clark: The Cure for All Cancers (1993) New Century Press, USA, dt.Ubers.: Heilverfahren aller Krebsarten
[8] Dr. Bodo Kohler: Biophysikalische Informations-Therapie, Gustav Fischer Verlag (1997)
[9] Dr. Bodo Kohler: BITsyn, der neue Weg in der Informations-Medizin, Jubilaums-Schrift der Intern. Arzte-Gesellschaft fur Biophysikalische Informations-Therapie, Bad Nauheim, 6.-8.10.2000.
[10] Bioenergetische Messverfahren in Theorie und Praxis, Vortragsband der Gesellschaft fur Energetische und Informationsmedizin e.V., Universitat Stuttgart am 17.7.1999 und am 7.10.2000
[11] Dr. Johann Lechner: Storfelddiagnostik, Medikamenten- und Materialtest, Teil 2 aus der Reihe: Praxis der Ganzheitlichen Medizin und Zahnmedizin, Verlag Dr. E. Wuhr (2000)
[12] M. Luscher: Der 4-Farben-Mensch, W. Goldmann, Munchen 1977
[13] M.Luscher: Das Harmoniegesetz in uns, Econ-Verlag 1993
[14] FA. Popp: Neue Horizonte in der Medizin, 2.Aufl. Haug Verlag Heidelberg 1987
[15] M.Bischoff: Biophotonen, das Licht in unseren Zellen, 2001

J. Literature concerning history and more peripheral subjects

[1] David Ash, Peter Hewitt: Science of the gods, Gateway Books, Bath, 1990.
[2] T.E.Bearden: Skalar Technologie, Michaels Verlag 2002, ISBN 3-89539-250-2.
[3] Thomas Valone: Das Unipolarhandbuch, Michaels Verlag 2001, ISBN 3-89539-295-2.
[4] R. Sheldrake: Sieben Experimente, die die Welt verandera konnten. Goldmann Verlag 1994
[5] R. Sheldrake: Das schopferische Universum. Meyster Verlag Munchen 1983.
[6] H.Ludeling: Handbuch der Radiaesthesie, Verlag Eike Hensch 1994, ISBN 3-927407-09-7.
[7] Hensch: Radiaesthesie im landlichen Bauen und Siedeln, Arbeitskreis zur Landentwicklung in Hessen, W4, Wiesbaden 1987
[8] H. Mayer, G. Winklbaur: Biostrahlen, Verlag ORAC, Wien 1989, 5. Auflage
[9] Rohrbach: Radiasthesie, Physikalische Grundlagen und Anwendung in Geobiologie und Medizin, Haug Verlag Heidelberg 1996.
[10] R. Schneider: Einfiihrung in die Radiasthesie Teil II: Leitfaden und Lehrkurs ..., Oktogon-Verlag, Wertheim, 2. Aufl. (1984).
[11] Lamer: Worterbuch der Antike, Kroner Verl. Bd.96
[12] K. Schefold: Die Griechen und ihre Nachbam, Propylaen Kunstgeschichte Berlin Bd. 1
[13] T. Kraus: Das romische Weltreich, Propylaen Kunstgeschichte Berlin Bd. 2
[14] G. Gruben: Die Tempel der Griechen, Wissenschaftliche Buchgesellschaft Darmstadt 1986
[15] E. Horst: Konstantin der Grosse, Eine Biographie, Classen Verlag 1985 Dusseldorf, 2.Aufl.
[16] Vitruv (Marcus Vitruvius Pollio): Zehn Bucher uber Architektur, Ubers. von Dr. K. Fensterbusch, Wissenschaftl. Buchges. Darmstadt 1987,4. Aufl.
[17] A. Springer: Das Altertum, A. Kroner Verl. Leipzig 1915, 10. Aufl.

உ

Time = Space

Supreme scientific secrets in ancient India

(God's particle, Language, Arts, Temples & Sacred Geometry)

(Shatkona Yantra – Created by Sri Bhogar Siddhar currently in a temple in Sri Lanka, taken once in a year for rituals, believed to emanate supreme subtle divine energies.)

Thinking Hearts (Raguram Gopalan)
(raguramg@hotmail.com)

உ

Thoughts from Thinking Hearts:

"Curious by nature, in a life so uncertain
Thirsty for the truth, which is so certain
I sought for some water in our Vedas - the fountain
Though I can't understand fully what it contains
I am amazed & speechless with what I could ascertain
This is just a speck of dust from that golden mountain
Thankful to my family for helping me in what I could attain
Grateful for the wisdom and works from all the chieftains
Wish I repay every atom of it through my gratuitous tearstains"

This effort is to share what I read, understood and enjoyed about the scientific aspects in ancient India which are codified in our language, arts and in 1000s of temples. The quotes and examples are predominantly in Tamil but I have tried to give the meaning which can enable a reader to grasp the meaning and progress. Any shortcomings you notice are purely reflective of my abilities to understand and express. There was not even an iota of intention to hurt any sentiments or beliefs of others. A piece of my mind is available @ http://ragsgopalan.blogspot.com

I initially thought that I shall reproduce a prayer from one of the books which I had read but at one fine moment I decided to capture my feelings in my own words. So I scribbled few lines in English summing up my feelings as above, few lines for the Sage of Kanchi and a prayer in Tamil with its meaning in English. You may understand this prayer better after you read this book.

January 2012, Version 1.0

Please feel free to copy and reproduce in whichever form or shape as you deem fit without any acknowledgements. In fact see how much of this can you share to dispel the ignorance. The more you share the better. ☺

If I have acknowledged any books or authors please recognize them and ensure that you either buy their books or donate to their cause. They deserve all the credits.

உ

A divine soul
With a noble goal
Walked this earth
When divinity was dearth
Beyond any treasure's worth
To avoid our death & rebirth
Seek his guidance & grace
For he shall ever embrace!

உ

முதல் வணக்கம் (Prayer)

உள்ளமே மூலமாகி, பரம்பொருள் கோலமாகி
விண்ணே ஒளியென்றாகி, ஓமே உணர்வென்றாகி
உணர்வே ஓமொளியாகி, ஓமொளி ஓமொலியாகி
ஆடலன் ஆட்டமன்றோ, அசைவுறுக் காலமாகி

(Mind is the source, primordial god’s particle as the form,
The luminescent space, the Pranava as consciousness
Consciousness as the Om’s Light, Om’s Light as Om’s sound
Isn’t time a pulsation that’s the dance of Lord of Dance?)

காலமே சீலமாகி, சீலமேக் கோலமாகி
கோலமே ஞாலமாகி, ஆதியும் அந்தமாகி
ஞாலமே மூலமாகி, அறிவுடன்ஆ னந்தமாகி
நடுவிலே நன்று நிற்கும் நாதன் தாளே நாட்டமாகி

Time creates Rhythm & order, Rhythm creates shapes
Shapes become universe, the beginning and the end
Universe merges with source, it is awareness & bliss
Ever searching for the feet of the divine & graceful mean

விண்ணிலே மண்ணுமாகி, மண்ணிலே விண்ணுமாகி
விண்ணிலே எண்ணமாகி, எண்ணமே எண்ணுமாகி
என்னிலே என்னைக்காண என் கண்ணிலே மணியுமாகி
நிர்மலப் பொருளாய் ஓங்கும் நிமலனடி போற்றுவோமே!

The mass in energy (Space), the energy in mass(earth)
The energy as thoughts, our thoughts as numbers (octets)
To me find me within me, he who stands as my eye’s pupil
Beseech his feet who is devoid of may blemish

அம்பலத்தில் ஆடும் அவனை, அரங்கத்தில் துயிலும் அவனை
அரவத்தைச்சூடும் அவனை, அரவம்மேல் ஆடும் அவனை
பைரவித்துணைவன் அவனை, திருமகள் தலைவன் அவனை
நம் அறிவுக்கு இருளின் நமனை, பொற்பாதம் போற்றுவோமே!

The one who is dancing in the microbode, the one who is sleeping in arangam
The one who is wearing snakes, the one who is dancing on a snake
The one who is consort of Goddess Bhairavi, the one who is the Lord of goddess Lakshmi
Beseech his feet, the one who kills our mind’s tamasic darkness

உ

TABLE OF CONTENTS

1. Time = Space Series. Part 1 - Introduction 6
2. Time = Space Series. Part 2 - Sound merges in light 9
3. Time = Space Series. Part 3 – Vaak-Artha - Importance of word 11
4. Time = Space Series. Part 4 – Scientific languages – Tamil & Sanskrit 14
5. Time = Space Series. Part 5 – Energy & matter conundrum 16
6. Time = Space Series. Part 6 – The Unfolding Self - Universe has evolved and was not created 19
7. Time = Space Series. Part 7 – The Chidambara ragasyam & the God's particle 21
8. Time = Space Series. Part 8 – Characteristics of the God's particle (Paramaanu) 24
9. Time = Space Series. Part 9 – Light, God's particle and God 27
10. Time = Space Series. Part 10 – Lord Nataraja and The String theory 30
11. Time = Space Series. Part 11 – Vastureva Vaastu and $E=mc^2$ 34
12. Time = Space Series. Part 12 – Vedic Concept of time & its measurements 38
13. Time = Space Series. Part 13 – South American Mayan & South Indian Maayan 40
14. Time = Space Series. Part 14 –Mayan, Tamil, Pleiades & iCHING 43
15. Time = Space Series. Part 15 – Shiva Lingam is not a Phallus 45
16. Time = Space Series. Part 16 – Seelam - The Primordial circular force - Ganapthi & Mathematics 50
17. Time = Space Series. Part 17 – Seelam - The Primordial rhythm & fundamentals 53
18. Time = Space Series. Part 18 – Seelam - Significance of √2 & √3 56
19. Time = Space Series. Part 19 – Seelam –Vesica Piscis, √5, & Golden mean (Φ) 58
20. Time = Space Series. Part 20 – Sankhya yoga and Sage Kapila 63
21. Time = Space Series. Part 21 – 5 and 8 the Universal rhythm 65
22. Time = Space Series. Part 22 – Eight (Octet) and the 5 sacred arts 67
23. Time = Space Series. Part 23 – Nanotechnology in ancient india & size of god's particle 69
24. Time = Space Series. Part 24 – Octet, Octave and the Gandharva veda (Classical Music) 72
25. Time = Space Series. Part 25 – Adi Tala, Nava Tala and Sthapatya veda (Sculpture) 74
26. Time = Space Series. Part 26 – Sabda Veda, Chandas & Poetry (Ma Nishaada…) 78
27. Time = Space Series. Part 27 – Architecture – The Zenith of mathematics (Vaastu) 82
28. Time = Space Series. Part 28 – Capturing the divine energy – Squares & Circles 87
29. Time = Space Series. Part 29 – Heaven & Earth – Lord Nataraja & Lord Ranganatha 91
30. Time = Space Series. Part 30 – Temples and Idol worship 95
31. Time = Space Series. Part 31 – Mayan & his works 101
32. Time = Space Series. Part 32 – Conclusion 105

உ

1.Time = Space Series. Part 1 - Introduction

As a wise man said, **“Indians are the most ignorant about their rich past and scientific traditions.”**

“Abheda Darsanam Gnanam*”. Nothing defines what **wisdom is** better than these 3 words. **Experience of unity / oneness in all is wisdom.** The roots of Indian wisdom are captured in these 3 words that everything in this universe is the manifestation from a single source, and we can call it God or Consciousness. This naturally leads us to one of the mahavakya ***“Pragyanam Brahma”*** which means **“Consciousness is god”.** But for people who are stingier with words and wants these 2 concepts to be put in just one word, then it is called **“Advaita”.**

It is not very often that nature reveals itself its absolute oneness and the un-manifested interconnections. You consider yourself fortunate when you come across such knowledge in however small measure, even if it happens very rarely and even if you have an illusion that you have understood something. It has been very overwhelming for me to come across some of the details I have been reading and hearing and the dots I could connect – some of which I had decided to write as a book.

If you are interested in knowing how scientific ancient Indian Sanatana Dharma is and how well we have codified nature’s secret in our languages, arts and temples and if you are interested in any of the following questions then you may like this book. Most of the aspects stated here as scientific proof has a reference to one or more of our scriptures and I would refer and quote them at various places.

- Would you be surprised to know that the size, shape, color and characteristics of God’s particle are very clearly documented in our scriptures at least 12000 years back? What the scientists at CERN are spending billions of $, is well documented and we will discuss the characteristics of God’s particle in this book.

- Would you want to know how **Time = Space** and more over time is nothing but the vibration of space? If I tell you that this was known us Indians at least 12000 years back and currently available in a written form would you believe?

- When you throw a stone in water / pond the ripples that form take the shape of a circle (in 2D) / sphere (in 3D). Can you guess what the shape of the ripple would be if you throw the same stone in space?

- What is the similarity between Poetry, classical music, Classical dance like Bharatanatyam, Sculpture and a building? Apart from the fact that we don’t clearly understand any of them in depth what is the similarity? Would you be surprised if I say that all are essentially the same and in fact a **well constructed building is nothing more than a frozen music** and the relationship between all the above confirms to a single grammar documented 12000 years + back ?

உ

- Would you be interested in knowing how $E = mc^2$ an equation stated by our great Einstein has been known to us for years and not just that but we know the root of this energy and how to engineer it with precise formulas? Would you be surprised that this is the basis our language?

- What if I say that the age of the universe, every astronomical unit of the bodies, big bang theory, string theory, God's particle etc are all documented and they are all codified in our temples?

- You would have heard about the golden ration Φ but do you know the philosophical significance of Φ and how it is derived? Moreover would be interested in knowing the significance of key numbers and ratio like 0, 1, 5, 8, 9 and $\sqrt{2}, \sqrt{3}, \sqrt{5}$? What is I say that $\sqrt{3}$ can be correlated with "**Iyengar Namam"?** Does it sound funny? What if there is a deep mathematical and philosophical significance? And how are all these ratios related?

- As a wise man said that **'Mathematics is the language of the gods".** What if this formula is codified in our texts from which we understand the God's particle, its shape, characteristics and its manifestation?

- What if I tell you that sound is a subset of light and sound merges with light at a point and that is at the root consciousness? Any non-takers for this?

- If you agree on the above then **Sabda Brahman** or the belief that sound is god merges with something higher, isn't this contradictory? Also why many religions did believed that "**Word is god".** Was it a mere belief or was there any scientific reason behind it?

- What is the correlation between Carnatic music and a human being's height?

- What if I say that the Mayan from South America and the Mayan from South India are one and the same?

These are some of the questions which might get addressed in this book. I am going to quote a series of references and books and links to understand and learn more about these topics and I would request you to utilize them if you are interested in these topics.

This may not only refer you to the experts but also can help you overcome any weakness I have in understanding and articulating some of these topics. Some of the topics may touch upon religious beliefs (mostly Hinduism) but if you read with an open mind you would notice the underlying science behind it.

உ

I would be happy if any of these blogs motivate and inspire you to explore the roots of our tradition and knowledge and give you an insatiable hunger for knowledge, wisdom to pursue the nature and its secrets.

May the ancient Sanskrit quote “May I meditate on the supreme truth “Satyam Param deemahi”, resonate within you as it does within me.

Happy reading!

PS:

Abheda Darshanam Gnanam, Dhyanam Nirvishayam Manam;
Snaanam mano mala thyagam, Showchamindriya Nigraham", says the Upanishad.

The real Gnana is seeing all as one, real Dhyana is controlling the Manas from all temptations, the real snana or Bathing is Cleansing of All Mindly impurities, not physical impurities alone and real Showcha or cleanliness is controlling the Indriyas, this controlling of Indriyas, emotions, weaknesses and temptations.

I am also quoting parts of Kahlil Gibran here,

Your hearts know in silence the secrets of the days and the nights.
But your ears thirst for the sound of your heart's knowledge.
You would know in words that which you have always known in thought.
You would touch with your fingers the naked body of your dreams.
And the treasure of your infinite depths would be revealed to your eyes.
But let there be no scales to weigh your unknown treasure;
And seek not the depths of your knowledge with staff or sounding line.
For self is a sea boundless and measureless.
Say not, "I have found the truth," but rather, "I have found a truth."

2.TIME = SPACE SERIES. PART 2 - SOUND MERGES IN LIGHT

What if I say that "**Sound is a subset of light".** Scientifically you may agree that both are electro-magnetic vibrations at different frequencies in the spectrum though one may not be the subset of another.

So, What if I say that every other frequency is the subset of light? I am sure many may disagree. Some of the religious pundits may claim that "**Sound is god**" which I am not disputing but "**light too is god"** and as we progress towards the primordial state sound merges into light.

Let me try to explain this with a simple exercise. Please sit in a place with a calm mind – few deep breaths may help.

- Imagine that I am TALKING to you and avoid thinking that you are reading this blog.
- I am going to TELL the following 5 words and you are going to LISTEN to it. Please just observe what happens within you.
    - CAT, BOAT, MOM, DEVIL, BEST FRIEND

The following are the fundamentals of perception as per Hindu scriptures:

- Every word has a meaning (Let us ignore the so called meaningless words for the time being.).
- Every meaning invokes a form or shape within our mind.
    - For example when I say "**MOM"** you associate this word with your mother and the picture / image of your mother is perceived inside. You need to be little more observant to understand this. **The fundamental principle is that**
    - **"Every word is first associated its meaning then the meaning is associated with a form. The form is associated with a Guna (Quality) and then the quality or Guna is associated with its experience. What is stored inside is just the experience.**

Let me TRY to explain the abstract concept of consciousness as below:

- **Consciousness / existence exist in 3 states (deeper explanation is 5 / 7 states but we will discuss the simpler alternative).**
    - **Formless state called Experience / feeling / bhava. This is the super conscious state.**
    - **Gross state with form which has physical attributes. This is the conscious state.**
    - **In-between state (Not formless and no form) called Guna state which has subtle quality attributes. This is the Subconscious state. If this is difficult to comprehend for you please imagine "Egg" which is in-between the formless and state with form.** Gotcha?

Let’s look at an example. Rose is a flower. When someone tells you **“ROSE”** then the following happens:

- The sound “rose’ associates with a flower usually. (I am ignoring it being a name of your girl friend ☺). So here the word is associated with its meaning.
- This flower is associated with red color and perhaps with thorns. Here the sound does not exist anymore but only a form. **Yo!, the sound has merged into light.**
- The third step is - this form is associated with a quality which is fragrance of a rose. For someone sensitive they can smell the rose when they think about it. How else could we salivate at the thought / smell of a favorite dish if this step does not exist?
- Now the last step is, this quality invokes an experience and hence a feeling. This rose may be associated with your inner self for love and hence the emotion of love surfaces. This is called **Bhava / Rasa** in Sanskrit.

If you are not clear about this then please do not move to the next part and think or discuss about it. A little contemplation would help you understand this **5 stage** process of perception.
‘SOUND – MEANING – FORM – QUALITY (GUNA) – EXPERIENCE (FEELING / BHAVA)’

Our ancient forefathers knew this science and interconnection. Let me now quote these Slokas as an example from Bharatnatyam, which talks about this linkage.

Kanteenaalambayet geetam, Hasteenaardham Pradarsayet,
Chakshurbhyaam darsayeet bhaavam, Paadaabhyam taalamaacharet.

According to Nandikeshara the dancer should sing with the mouth, express the meaning of the song with hand gestures, her eyes should express the emotions or bhava, the tala, the beat or rhythm should be done with her feet. Further he goes on to say –

'Yato hastas tato drushti, Yato drushitis tato manaha
Yato manahas tato bhavo, Yato bhavas tato Rasaha'

'Where the hand goes, there should follow the eyes, Where the eyes move, mind should follow it,
Where the mind follow, Bhava or emotion is created, & lastly when Bhava is created the sentiment or Rasa will arise.'

All the Mudras or gestures represent word when held at a particular position around the frame of the body and when used in a particular way.

Alas we Indians have ignored this great science & art and its linkages and are like ignorant fools following the meaningless western tradition and dances!

As a wise man said, **“Indians are the most ignorant about their rich past and scientific traditions.”**

Happy reading!

உ

3.TIME = SPACE SERIES. PART 3 – VAAK-ARTHA - IMPORTANCE OF WORD

‘SOUND – MEANING – FORM – QUALITY (GUNA) – EXPERIENCE (FEELING / BHAVA)’

In the **5 stage** process of perception, one important factor which I missed is the **“Self / EGO”** which interprets the **Guna** to an experience. For example when I say Dog, the **‘Self’** interprets Dog to a **loyal friend or a bike chaser or a rabbies generator.** Essentially what is the quality of dog mean to me? If you understand this process this explains the uniqueness between individuals or the root cause of differences in a society.

I am also going to add but not going to focus on the fact that the inputs are never limited to sound and when see a picture the process of perception starts with step 3. Just to poke the individuals who think “**Sound / Word is the only god – Sabda Brahman**, please tell me - when you see a picture and when there is no sound associated with it, where is **God as Sabda Brahman in this situation**?

Does that mean that the very important Hindu belief that the Sound **“Om is sabda Brahman or god”** does not hold any meaning? It certainly does and I shall share my thoughts on it – continue reading.

What is the importance of Word?

The greatest of Indian poet **‘Kalidas’** said

"Vaak artha viva samprakthov vaakartha prathipathaye
Jagadha: pitharov vandhe parvathe parameswarow"

he compared Lord Shiva and Shakti like sound (Shakti) and meaning (Shiva). Both sound and meaning are inseparable. You would now understand the wisdom behind this sloka since there is no sound without a meaning. Also **Sabda Brahman** merges with the **Artha Brahman** and both are inseparable. Here Artha Brahman is the light and the meaning of the word. Remember we say that **‘Throw some light”** when we don’t understand something.

In Tamil **பொருள் (porul)** means “a thing” and it also means “meaning”. We will see how **பரம்பொருள் (Paramporul)** is the Lord Shiva as a God’s particle and how he is referred to as the meaning too. The same applies to Sanskrit where **“artha”** means **wealth / things – remember Arthasastra?** And it also refers to **“meaning”** as in the above sloka. How rich these languages are?

And in **Abhirami Andadi, bhattar** sees devi as **"Arthanareswara"** and confirms us that the grace of devi will brings us both richness and mukthi. **"Sollum porulum ena nadamadum"...**

உ

A word is made up of letters called Akshara in Sanskrit. The meaning of Akshara is that which cannot be broken down further. ie. Word can be broken down to letters but it cannot be broken down further. A letter has a form like **"A"** and has a sound associated with it. This means the light and sound are merged in a letter. As per the principle stated above in the process of perception, the primordial state is one where light and sound is merged into each other.

If you don't dispute the philosophy that everything merges into god at the primordial state and at this state, sound and light are inseparable, and then you would agree that an Akshara is **God / Brahman.** Each letter has significance and meaning in Indian languages especially Tamil and Sanskrit. **A word is a combination of Form (Light), Sound and meaning and these are first 3 aspects of perception which takes us from a gross state to a formless subtle un-manifest state.**

Hence the statement from New Testament **"In the beginning was the Word, and the Word was with God, and the Word was God"** reflects the same principle.

But as per Hindu scriptures Veda is the breath of god (not word of god) or the aural vibration of consciousness cannot take you to the state of moksha. Words don't take you to God, it can help you in the process but has its limit, since the sound and meaning merges into something else as we move towards more subtle space.

This is what my friend Kambar said in Kambaramayanam as **"வேதமும் முடிவு காணா மெய்ப்பொருள் வெளிவந்தெய்தி மா துயர் துடைத்த வார்த்தை மறுப்பரோ!!.** This means that the supreme truth who could not be found by Vedas came and solved the problem of an elephant, can someone dispute this?

Every word or Akshara has four states **Para, Pashyanti, Madhyama and Vaikari. Vaikari** is the fourth state where the sound is audible to us. If I recite something mentally then the sound has 3 states only and these 4 states signify as to how a feeling (bhava) becomes thought and thought becomes form and then a sound. Just note here that as per Frank outlaw, it's the thoughts which are primordial but as per our scriptures it is feeling or Bhava or deep rooted desire or also known as vasanas which drive your thoughts. So Frank's quotes are half baked plagiarism.

In a work called Tarka Samgraha, we have classified 9 different physical attributes (substances / dhravyas) and 24 different qualities / GUNA in all. If you are interested reading more about this, please read these blogs or the original work.

http://ragsgopalan.blogspot.com/2010/09/vedic-perspective-matter-and-its_14.html This is a 3 part series.
http://ragsgopalan.blogspot.com/2008/11/part-1-perception-art-of-seeing-things.html This is a 2 part series.

To summarize this topic:

- Broadly consciousness exists in 3 states.
- The process of perception if understood well would throw a lot of secrets about nature.
- The 5 stage process of perception **“Sound – meaning - Form – Guna – Bhava”** is a simplistic way of portraying this.
- Sound merges into light and light is worshipped as God in most of the religions and belief. We can explore little more of this in the future sections.
- A word is a unique combination where Light, Sound and meaning merges and hence it is considered as god. This word represents **Arthenareeswara or yinyang or Star of David**.

In the future sections let us explore as to what is the relationship between Maths and God and some of the critical numbers and its philosophical and scientific significance.

As a wise man said, **“Indians are the most ignorant about their rich past and scientific traditions.”**

Happy reading

உ

4. TIME = SPACE SERIES. PART 4 – SCIENTIFIC LANGUAGES – TAMIL & SANSKRIT

One of the main reasons I believe as to why our wisdom has degraded so much in the last century is our ignorance and reluctance to learn our rich language. Our language offers richness not just in literary sense but is supremely scientific too. I am going to touch upon just 3 to 4 aspects of it which I knew and understand at a fundamental level and request you to learn your mother tongue well.

Many of my friends don't exhibit a sense of remorse when they say **'I can understand Tamil but can't read or write it**". I wanted to tell them how much in life do they miss in terms of knowledge and richness. This is not just about Tamil but every major Indian language is rich in its own way. Since my mother tongue is Tamil, I am going to articulate some of the science in it.

Vigyan / Vigyanam (விண் ஞானம்) means Science:

But most importantly for this series I wanted to take the word called Science as meant in Tamil and Sanskrit. A word always can be broken down to its dhatus for its exact meaning in Tamil and Sanskrit. Some examples below:

- Science in Tamil is **Vigyanam and in Sanskrit is Vigyan**. This is split as **Vin** and **Gnanam** / **Gyan**. **Vin means space and Gyan means knowledge. Hence according to Indian system science means it is the nature / knowledge of the space.** This has very deep significance since western science has not agreed the existence of space for a long time and their gross and materialistic approach prevented them from seeing the most subtle component and its nature. We were masters of it ages back. Most of the questions in Chapter 1 would be answered based on the knowledge of space – Vigyan.

- **Universe is called as Brahmanda** in Sanskrit. Brahma + Anda which literally means a big egg. This means we knew that the galaxy is elliptical in shape ages back and it required hubble telescope in 1950 to tell us that.

- **Bhoogol** means **Earth (Study of) / Geography – This Splits as Bhoo +Gol.** Bhoo means Earth and Gol means round. We did not throw stones at a scientist as late as 17th century when he said that earth is round and not flat. We would have laughed our heart out and ignored him.

Be it the age of the universe, all of the astronomical measurements, health, spirituality etc, many of us need a white skin with blue eyes to tell us that what we knew was right and they have certified it. When we decide to come out of this mentality then the process of reclaiming our rich heritage shall start.

Origin of Universe and linkage with Tamil:

The initial evolutionary process for the universe consisted of 5 stages states Aintiram. You can imagine that these are the movements of particles during the Big bang. They are அமிழ்தல், இமிழ்தல், குமிழ்தல், உமிழ்தல், தமிழ்தல்.

- Withdrawl (Amizhdal)
- Imizhdal (Overflowing)
- Kumizhdal (clustering round in an order)
- Umizhdal (Emitting)
- Tamizhdal (resulting into a well defined form)

These are the first stages from the Big bang till a well defined shape is formed. Now the last level is called Tamizhdal which results in a well defined form. This state has emanated from the Pranava and not been created by some one. Hence a language as rich with the sweetness of inherent order, originating from the luminosity of the original particle is called Tamil. Tamil is word based on the final resultant state called Tamizhdal (தமிழ்தல்).

I shall address the other 2 interesting aspects that include a Chicken and Egg analogy for Energy and matter conundrum in the next blog.

As a wise man said, **“Indians are the most ignorant about their rich past and scientific traditions.”**

Happy reading!

உ

5.TIME = SPACE SERIES. PART 5 – ENERGY & MATTER CONUNDRUM

Energy and Matter concept in formation of letters:

The concept of Energy and matter is not new to us and does not start with Einstein's days of $E=mc^2$. Let us look at how our letters are formed from Aksharas then people would know that the concept of Energy and Matter is old as our language. In Tamil there are two kinds of Aksharas **உயிர் எழுத்து - Uyir Ezhuthu (Life / Energy letters – 12 letters) and மெய் எழுத்து - Mei Ezhuthu (Body / Matter letters – 18 letters).** Both put together it is 30 letter pack for Tamil as alphabets. Now both have to combine to give letters called **"body with life"** which are called **uyir mei Ezhuthu**. This combines to form 18*12 which is 216 letters as **Uyir Mei Ezhuthu**. For example க்+ அ = க in Tamil and क़ + अ = क in Sanskrit.

So the formation of letters itself is a science where Matter (Body) combines with Energy (Life) and then the living organisms (Body – life letters) are formed.

I want to ask you a **Chicken & Egg** question here which is very relevant to today's scientists. Did the energy come first or is it the matter that came first? Modern science is still scratching its head. I can answer this question in 2 ways, first is obviously using language as a science.

- In the above example க்+ அ = க, க் is the body and அ is life. So as per our language sciences be it Tamil or Sanskrit the matter is formed first and then the life came and attached to it. This is very well documented in Tamil scriptures as follows:

உடம்புடன் உயிர் வந்து ஒன்றுவது இயல்பே - தொல்காப்பியம் . This is over 2500 years old which states that life comes and joins a body in language and this is nature.

மெய்யொளி உயிரொலி சிவணுதல் இயல்பே – ஐந்திறம். This is over 12000+ years old which states that same thing and adds that body is like light and life is like sound and they merge and this is siva's nature. **This certainly means that both Body and life are not formed at the same – as popularly believed. Life comes and joins the body to give a living being – in the above case the letters are the living beings.**

உ

The second reference I am going to take for the same concept is our **Yogic / Siddha / Ayurvedic** science as to how fetus is formed in mother's womb. As per our (Siddha) belief the conception of a child in a mother's womb happens as follows:

- **The first organ that is formed for the fetus is the cells of the Eyes (Single Eye)**. This eye cell starts vibrating due to its heat and multiplies as 2 eyes and then as the whole body. This is the vibration seen in the initial days of the fetus and not the heart beat. As per modern medical science the heart takes shape only by the end of the 8th week and not before. I am requesting someone to validate this.
- **Life comes to this body at the 3rd month of conception only**. This is the belief as per Ayurvedic and Siddha science.
- Instances of the third month natural abortions are very high than the later months based on the above reasons. This means that the life is not destined for that matter / life force is not sufficient enough.
- **How many of you know that the size of eyes never change as you grow and stays the same from the time we were born,** while all other organs undergo growth?
- Also the eyes hold a very important significance in the spiritual science which I shall address later. The eyes are the seat of Sun god and are characterized by heat and light.

It is through the heat in the eyes the subtle became a gross living being in this world and if the living being wants to merge back with the subtle – which is the process of Samadhi then the living beings should use their eyes, increase the heat in the eyes and start the devolution process. This is a supreme secret kept by the sages even in today's world. **You may want to ask any spiritual school as to why they recommend meditation with eyes fully or half open instead of closed eyes? Ask yourselves why the free masons and other secret societies use eye as one of their symbols?** We shall address this later.

Now you want to answer the Chicken and Egg analogy to the Energy and Matter conundrum based on the above 2 thoughts, we can conclude it is the matter which came first. We shall try to explain this based on Space sciences a little later.

Masculine and Feminine names based on ending letters:

I am also going to give you as to how Indians distinguished masculine from feminine names. **Kanchi Maha periyava, the Sage of Kachi** had explained this beautifully in his **"Arul Vakku"**. I am giving a gist of it here just to conclude this:

- **Masculine names:** All the names shall end with the phonetic a, im, in , ir, aha etc. Examples are Ram, Shyam, Raman, Kannan, Kishan, Vivek, Adam. So phonetically names like Catherine is a masculine name because it ends with "in" phonetically.

- **Feminine names:** All names ending with phonetics aa, e, I, oo etc. Examples are Radha, Ramya, Savithri, Gayathri, Uma, Rosy, Isabella etc. Same way phonetically Joshua is a feminine name.

Vishnu and Lalitha sahasranamam follows this rule and hence one invokes Shakthi as lalitha and the other invokes Purusha as Vishnu.

Just to conclude this part, I think we looked at how science is an integral part of our language formation and for us science has always been about the knowledge and nature of the space and we believed that space manifested itself as the physical world. So in the next few parts we shall look at how this manifestation has happened and other interesting aspects.

I would conclude this part with a earnest request that please encourage your kids to learn their mother tongue – to read and write and you would not have done anything better than this to advance their spiritual growth and adding richness to their life.

As a wise man said, **“Indians are the most ignorant about their rich past and scientific traditions.”**

Happy reading!

உ

6.TIME = SPACE SERIES. PART 6 – THE UNFOLDING SELF - UNIVERSE HAS EVOLVED AND WAS NOT CREATED

As per many scriptures in Hinduism this universe has evolved from itself and not created by someone. If you want to quickly ask as me as to what Brahma, Vishnu and Rudra mean – I would attribute them to different process heads in this evolution. They are all different aspects of the same consciousness based on their state of being in the process of evolution / devolution. This is my understanding but let us avoid this discussion here.

Here I am indebted and thankful to the nobel soul **Late. Dr. Ganapathi Stapathi,** (http://www.vastuved.com/life.htm) who not only unraveled the Vaastu science – the science of Space and time but also brought to light 2 important books which were over 12000+ years old written in Tamil by **Mahamuni Maayan.**

Mamuni Maayan is believed to be the same person who is popularly known in **South America as Mayan** and the 2012 phenomenon based on Mayan calendar. Dr. Ganapathi has established proofs that the pyramids in Middle East, the temple architecture in India and the structures in Mexico and Guatemala confirm to a single Science and Mathematics seen in all these works.

At the end of the blog I am listing few books which helped me understand this topic but most of the books (**Aintiram and Pranava Veda**) are out of print now and if you are lucky, you would get some of them. Now let us understand briefly how this evolution process has come about. According to Mayans' Aintiram:

- The free space is the unified field of energy and matter and source of all forms that we see in material world. That is why we were defined science as **Vingyanam**. This space consists of very minute particle called **Vinporul, nunporul, Sittrambalam, Paramanu, Oliporul, Microbode** (**விண்பொருள், நுண்பொருள், சிற்றம்பலம், பரமாணு, ஒளிப்பொருள்**) and in many names. You can pick what you like. I am going to use **Paramaanu** in the rest of the blog.

- The whole process of evolution is a 5 stage process. (Keep noting the importance of 5 and at the background remember Shiva is represented by Panchakshara mantra (Na~Ma~Si~Va~ya).

So what is the five stage process?

  - This space is called as Moolam (Source).
  - This Moolam starts vibrating and this vibration of the space is called Kalam (Absolute Time and not physical time. We will refer this as time only).
  - This Kalam (time) vibrates to a mathematical resonance called Seelam (Rhythm).
  - This Seelam as it resonates creates Kolam (Shapes – Circles, cubes etc).
  - This Kolam becomes our visible Universe which is called Gnalam.

உ

- So it is **MOOLAM (Source) – KALAM (TIME) – SEELAM (RHYTHM) – KOLAM (SHAPE) – GNALAM (UNIVERSE). மூலம் - காலம் - சீலம் - கோலம் – ஞாலம்**, these are 5 stages of evolution.

This means that the Space itself becomes spatial forms and time is the instrument that creates, sustains and destroys. Lord Siva in Tamil is also called as **Kalan (காலன்)** as to who controls time since Kalam **காலம்** is time.

To put it differently, un-manifest state when pulsates becomes absolute time and this is the creative energy. The process of pulsation confirms to a mathematical order and we will see this order in detail later. You may now understand the phrase that "**Time creates, sustains and destroys**". Since if there is no pulsation then nothing happens.

For those who need quote from a foreigner to convince themselves of this can be referred to the **Bertrand Russel's** quote "**What we perceive as qualities of matter are differences in periodicity".**

I shall quote some from the oldest literatures for reference below:
காலமே எவைக்கும் மூலம், காலமே மூல ஆற்றல்
காலமே கோலத் தோற்றம், காலமே ஞாலத் தோற்றம்… *Maha muni Mayan from Aintiram*

காலக்கூறே கணக்கியலாகி… Time splits as Maths in proportion it pulsates.
Vyasa says in Adi parva chapter 1, shloka 249, says the same thing that Time Creates, sustains and destroys everything.

kalah srijati bhutani kalah sanharati prajah
sanharantah prajah kalam kalah shamyate punah!!

The same is quoted as **"Vastur eva Vaastu"** which means the un-manifest Paramaanu which is called **Vastu** (with Single a) becomes **Vaastu (gross form – with two aa**). You can relate this **Vaastu** as the building science which is grossly misused and misrepresented and commercialized in today's TV programs. We will address the science in it later.

I shall leave this part with this thought, the space is considered as **Nataraja (Shiva) – subtle component and Ranganatha is considered as the Earth component**. So Shiva and Vishnu are two aspects of the same seed. We will see more scientific proof of this later.

"Shivasya hridayam vishnur, Vishnoscha hridayam shivah:" and
"Shivaya Vishnu rupaya Vishnave Shiva rupine"

Vishnu is the heart of Shiva and likewise Shiva is the heart of Vishnu and they both are the representation of each other.

Now if you are clear about the five stage process of evolution we can delve into each and every aspect of this in little more detail that would answer everything.

Ref: Check out all the ones here. Key recommendations are item 6, 11, 14 and 43. http://www.vastuved.com/publication.html

7. TIME = SPACE SERIES. PART 7 – THE CHIDAMBARA RAGASYAM & THE GOD'S PARTICLE

There were 2 questions I had confronted myself when I was reading these passages. They are:

- Why did the unmanifest space energy started pulsating and became absolute time?
- What did the unmanifest space energy contain? Was it a point of singularity as the modern scientists wanted us to believe? If so then how much mass was concentrated in that point which is obviously very difficult to believe.

The answer to the first question is here **"The self unfolds itself for its self – Bhagavad Gita".** There is no convincing answer to the rational mind as to what the reason that the consciousness which was passive decided to become dynamic and started pulsating. So let's leave this for the time being.

But the second question is answered very comprehensively. But before we get into the details of what it is, I want you to check Figure 1. This gives the overall picture of evolution and the five stage process. I also want you to recollect the "EGG" state which is called as the GUNA state where in the form and sound manifests. They say that this pulsation started with OM. This OM as popularly believed is just not an aural form but also has a visual form and that is light. We will discuss about this later in detail.

But let us focus on the actual second question as to what the contents of this Space energy were:

- The space is filled with **Paramanu or Microbodes** which are tiny particles. These are the **God's (Higgs Boson) particle** our CERN scientists are after. http://en.wikipedia.org/wiki/Higgs_boson

- Now, we are probably a year away before CERN publish the results when this blog is published. I would not be surprised to see the results of that experiment is closely aligned with what is available in our scriptures and produced in this blog.

- The primal manifest form of the unmanifest is a **square** (primal wave pattern). This is the shape of the **Paramanu or Microbode**. This is very luminescent, means filled with light and on a 3D plane this shape is a **Square Cuboid**.

- A **Square Cuboid** is a shape which is equal in all sides – say of unit measure which is the smallest measure possible and has **6 faces, 8 vertices, and 12 edges.** You can start figuring out in Hinduism, why the idols of Lord Shiva and Lord Muruga has six faces, 12 eyes, hands etc.

- You may want to note that 6 faces can be represented in 2 ways as below. Figure 3 is Lord Muruga's star or a Star of David in 3D which has 6 faces and 12 edges, popularly known as **Tetrahedron**. **So don't be surprised if the Boson Higgs particle is of the same shape.**

உ



* अचिन्त्य अव्यक्तरूपाय निर्गुणाय गुणात्मने ।
समस्त जगदाधार मूर्तये ब्रह्मणेनमः ॥

MAYONIC SCIENCE AND TECHNOLOGY
SCIENCE OF MANIFESTATION
THE PROCESS OF MANIFESTATION
OF SUBTLE ENERGY INTO EMBODIED ENERGY
(Science of form generation and form figuration)

MOOLAM/ENERGY

Vastu/பொருள்/Subtle energy/நுண்பொருள்/
Subtle substance/Essence of the Universe/
Brahman/Purushan/Vastu Brahman

Becoming Self Conscious
Pulsates / Vibrates / Blossoms into

KAALAM/TIME

Kaalam emerges as force of energy, from within the
energy and splits the energy into Paramanu particles
of energy causing into existence the vast subtle energetic space

GUNA (Quality)
EDAM/SPACE/FIELD
GUNA (Quality)

LIGHT
ARTHA PRAPANCHAM
(material universe)
Luminous material space

Unified field of Energy and Matter, Conscious
luminous space, it vibrates and turns into

SOUND
NADA PRAPANCHAM
(sound · universe)
Sonic material space

EDA VADIVAM/SPATIAL FORM

Material, visual form
ARTHA
with source in OM-LIGHT
अर्थब्रह्म्
பொருள்

Diverging into two
streams of self
expression namely

Material, aural form
VAAK
with source in OM-SOUND
शब्द ब्रह्म्
சொல்

VISUAL FORM - AURAL FORM
PAARKUM VADIVAM - KETKUM VADIVAM

Caused by the
well defined vibration of
light-space (light-rhythm)
quantified into TAALA-UNIT
(frequency of vibration)
(தாளம்)
(Measured Spatial unit)

TIME = SPACE
AURAL FORM = VISUAL FORM
Luminous Visual form occurs at Inner space
Vibrant aural form occurs at Inner space
The resultant
layout for all structures at
the level of Inner awareness.

Caused by the
well defined vibration of
sound-space (sound-rhythm)
quantified into TAALA-UNIT
(frequency of vibration)
(தாளம்)
(Measured Time unit)

Rhythm bound
spatial form.
(Architecture)
(Sculpture)
(Townplanning)

Vaastu Purusha Mandala
8 x 8 = 64

Rhythm bound
sound form.
(Music)
(Dance)
(Poem)

TRI-DIMENSIONALLY EVERY PARTICLE OF SPACE
IS A SUBTLE CUBE OF ENERGY, CALLED CHITRAMBALAM or MICRO-ABODE
within which there is a 'shaft of light' or 'shaft of consciousness' vibrating or
performing a 'rhythmic dance'. This is the dance of the DANCER, GOD SHIVA.

The whole universe is filled with subtle cubes of energy called KARU or BINDU or FOETUS.

---

* Brahman as defined by Mayan, in his astronomical treatise called 'Surya Siddhanta'.

Figure 1: Science of manifestation
(Courtesy: Pranava Veda by Mamuni Mayan – 12000+ years back, recreated by Dr. Ganapathi Sthapati)



Figure 2: A cube with all equal sides



Figure 3: A tetrahedron (from Internet)

- The free space is packed with cubical atoms of energy. They are building blocks of the structure of the universe. **So what is clear is that all these atoms existed in a "resonant state of non-vibration" before the so called "big bang" happened or the pulsation started.**

- **It did not burst out of a single point as popularly believed. Alternatively, in space every point is the center. When the pulsation started these cubical atoms underwent a shape change and manifested as shapes and forms.**

- This cube is called as **micro-abode called Sittravai / Chittrambalam** (mini hall in Tamil). This is **secret in Chaidambaram, Sage Appar** (**Chidambara ragasyam**) realized. Chidambaram is a Shiva temple associated with Space energy and when you go to sanctorum you would not find any idol but just empty space with some lights there. This is to signify this concept of **Paramanu** which is **luminescent and is a Cuboid in shape**. This is the smallest particle possible and can be called as **'God's particle".**

- The micro space, in the cubical shape is fetus or Garbha. This is known as **Vinkaru** in Tamil. This micro abode is the repository of light and sound.

- The free space is Light and the Light is Moolam or source of the universe and universal forms. Light is Brahman, Atman, Vastu Brahman – Nunporul in Tamil.

In the subsequent blogs we will correlate String theory, Brahma Sutra, Nataraja, Vishnu and how they are all contained in order and proportion in pulsation.

Happy reading!

Ref: A good read **Fabric of the universe, Jessie J Mercay**.

உ

8. Time = Space Series. Part 8 – Characteristics of the God's particle (Paramaanu)

This part is going to be a bit controversial hence read it with an open mind. Per our scriptures when analyzed deeply we can state that **"At the beginning it was just Consciousness (Pragnanam) that was luminescent with unmanifested potential energy and residing at resonant state of non-vibration. This energy was un-manifest and was present as Paramaanu or Microbode or Vinporul aka a subatomic particle. Yes! It was a particle without vibration and was at resonant state of non-vibration.**

The entire Space was supposed to be filled with these particles only and these were primal potential matter which is ever lasting.

Now let us ask few questions and see how our scriptures answer this:

1. **What was the shape of this particle?**

We have already answered that. In 2D it is square and in 3D it is a cuboid with all equal sides. Please note that in space it is always 3D and not 2D. It has 6 faces, 8 vertices, and 12 edges. This is known is current scientific community as **Tetrahedron**.

2. **What is inside the Microbode or Subatomic particle?**

This is a very interesting question. Our scriptures say that it is purely space inside but with an energy grid.

3. **What is this energy grid and what is its shape?**

It says that it is an 8x8 energy grid inside this microbode. This essentially means it is a square energy grid of 64 squares inside this Paramaanu.

4. **What is this color of this Paramaanu?**

It is luminescent and hence the golden color of the light is what it is associated with. **"Hiranyavarnnaam harineem**.." says Sri Suktha in the vedas, confirming the color of this Paramanu. Their variations exist but the fundamental one is of golden color.

5. **What is this size of this God's particle?**

It is calculated to be ~133 nm. We will see this in detail later.

6. **What is the significance of the energy grid?**

For the time being let me state that anything subtle is a function of 8 and anything gross is a function of 9. Let me also add that **iChing –** which is a Chinese divination book and the hexagram which deals with the Science of the subtle is in an 8x8 square matrix. **The mental game Chess is played in an 8x8 square.**

You would find 8 is the number or dimension for the subtle. We will see the importance of 8 and 9 and how beautifully these proportions adorn everything in nature in our daily life.

7. Are these particles faster than light?

Frankly I have not read a direct answer to this question but since this particle itself is light the velocity of this particle cannot be faster than light. This is my opinion. Modern experiments are suggesting that it could be faster than light. In **Mahabharatha, Yakshaprasna, the Yaksha will question this to King Yudhishtra as to "what is fastest thing in this world"**? King Yudhishtra would reply as **"mind"**.

Some of the sages have interpreted that since Consciousness is omnipotent and ever connected - the communication is seamless, instantaneous and not subjected to the concept of distance. The example given is if there is a pain in your leg, it does not take time to travel to your head. It is instantaneous and hence the whole universe should be considered as a living organism.

So to conclude on this question the particles are not faster than light but each particle is filled with intelligence and consciousness (just like a human cell) and their communication to anything is not subject to concept of distance. If our scientists come back and tell us that these particles are faster than light, then wait for someone else to tell us a little later that it isn't faster than light. ☺

8. Ok. Who has seen these particles and give me empirical proof?

परमानुरिति प्रोक्तं योगिनाम दृष्टि गोचरम ! **(Paramaanuriti proktam Yoginaam, drishti gocharam)** says **Mayamatham.** This means the **microspace** or **Paramaanu** is visible to the trained contemplatives and meditators only. One quick example as proof is the **Temple in Chidambaram** which represents **Space tattva** where the temple is built around the concept with enough documentation on it.

But we have been trained under Lord Macauly's education system and how can we accept this as proof which is subjective and superstitious. If I may ask please tell me how many of us have seen the electrons or protons? Do we not believe everything when someone tells us in English?

It is true that because of its existence we can see its manifestations and results of some experiments in our day today world. So we will look at tons of manifestations which we have been in nature as we progress. I would like us to be philosophically very clear as to what these things mean which we have been blindly following. For the time being please note down your questions and I am positive that this would be answered in due course.

Our sages have not only seen this, but have given the dimensions of this and the mathematical formula to manage this energy. We will see all of them. After reading all of them if you still don't want to believe in our scriptures, then may be CERN's result if it's in the same lines would prove it for you.

Happy reading!

உ



MANDUKA VAASTU MANDALA
8 × 8 = 64 modulated spaces

Brahma pada (the first belt around the central energy point) : 2×2=4 padas
Deivika pada (the second concentric belt) : 12 padas
Maanusha pada (the third concentric belt) : 20 padas
Paisachika pada (the fourth concentric belt) : 28 padas
64 padas

PARAMA SAAYIKA VAASTU MANDALA
9 × 9 = 81 modulated spaces

Brahma pada (the first belt including the central square field of energy) : 3×3=9 padas
Deivika pada (the second concentric belt) : 16 padas
Maanusha pada (the third concentric belt) : 24 padas
Paisachika pada (the fourth concentric belt) : 32 padas
81 padas

Figure 4: MANDUKA MANDALA – 8x8 (subtle form) & PARAMA SAYIKA MANDALA – 9x9 Gross forms
Courtesy: Dr. Ganapathi Sthapati

உ

9.Time = Space Series. Part 9 – Light, God’s particle and God

“At the beginning it was just Consciousness (Pragnanam) that was luminescent with un-manifested potential energy and residing at resonant state of non-vibration. This energy was self manifest and was ever present as Paramaanu or Microbode or Vinporul aka a subatomic particle. This is **omnipotent, omniscient and omnipresent**.

Ignore religion for the time being and just look at this particle’s characteristics scientifically. It is Eternal (**Anaadi**), primordial (**Aadi**), without any quality (**Nirguna**), it cannot be reached / grasped by thoughts (**Achintya** - since thoughts as energy are much more gross than this and we would see this), it cannot be measured (**Aprameya**), Luminescent (**Jyothi swaroopa**), its **omnipotence, omnipresence (Visvam) and Omniscience** is already known. So said the mahavakya **Pragnanam Brahma!**

All the characteristics of the particle are attributed to a personality or a state by the founders of religions. **Hindus called this state as Paramasiva or Purusha. Hence everything subtle is called Sivamayam.** The essential pulsation which started and the universal evolution began was called as **Parashakti or Prakruthi or Maya.** We will talk about the Shakti aspect later.

This subtle un-manifest energy evolves to become universe which is gross. This gross energy also known as **earth** is called as **Vishnu** and the subtle energy is called as **Space / Akash / Heaven**. So the term became “**Sarvam Vishnu mayam Jagat”.** Please note that it is just **Sivamayam** and there is not Jagat there. Since it is all subtle and there is no Jagat which is gross. But it is **Vishnu Mayam Jagat**.

I need to add that every sect in Hinduism has named this God’s particle with a different name. Narayana has replaced paramasiva in Vaishnavism and so on. In Hindu temples there are 2 prime idols – **Moolavar and Archakar** - The Moolavar does not undergo any archana or any decoration and it is always for the Archakar for which all poojas are performed. This god’s particle refers to the Moolavar and not Archakar.

To my knowledge, every religion and every sage / saint has agreed with the fact this fundamental particle or energy unit is **LUMINISCENT**. Note that there is no sound or word in this …**yet.** Let us see few quotes on this (there are thousands of quotes):

- **Be it vedic culture, Zoroastrians, Greek or any major culture fire / sun god which represents light is worshipped.**
- **“Om Jyothi rasaha” says Vedas**
- **In Gayatri mantra you meditate on the supreme light to illuminate you.**
- Vallalar said **“Arutperumjyothi, Arutperumjyothi”** which means **mighty graceful light**.

- If therefore your eye be single, your whole body shall be full of light. Mathew 6:22
- Thirumoolar states brilliantly that who realizes that the light (physical light which means the world) merges with light (subtle light), he has realized SIVA.

  ஒளியில் ஒளிபோய் ஒடுங்கிய வாறும்
  தெளியும் அவரே சிவ சித்தர் தாமே - 124

So what has happened to the **Sabda Brahman** here? It has merged with the **Artha Brahman** which is the light. What can you use to represent this state?

Light represents Form and our eyes represent Light / Form. So obviously sound is represented by ears. When sound has merged with light then it means Eyes and ears are merged together.

Can you think of anything that represents this state? This concept is captured by representing a **Manduka (Frog) or Sarpa (Snake)** always. Since for a frog and a snake the ears and eyes are merged. **Manduka Upanishad,** represents a knowledge of this state. And obviously the 8x8 square / cube represent the most subtle energy as an energy grid is called as **Manduka Pada / Mandala..**

Now the same aspect when it is applied to a gross form / body or a building then it is a 9x9 energy grid and it is called as **Paramasyika Mandala**. **At the gross level the same concept as applied is the WORD where Light (form) and sound and meaning merged into one. You cannot separate them**. We will look at this later.

Unfortunately we have lost the science and we neither understand the philosophy nor the symbolism behind this supreme science but we made fun of the fact that the supreme science is named after an absolutely menial creature like frog which is used only for zoological lab studies across the world or ends up in the dinner plate as it does in far eastern countries.

I would like to conclude this section by stating (may be a little controversial) that **First it was Consiousness as the Vinkaru, Microbode, Sittrambalam, Nunporul, subatomic particle which was luminescent. Later the concept of God evolved out of it.**

So God is not light, but the right of saying it is “the primordial aspect of “luminescence” has been adopted as God…

So, of the 5 fold evolution process we are still at the source (Moolam). We will see the concept of time and the mathematical science in the subsequentparts.

MOOLAM (Source) – KALAM (TIME) – SEELAM (RHYTHM) – KOLAM (SHAPE) – GNALAM (UNIVERSE). (மூலம் - காலம் - சீலம் - கோலம் – ஞாலம்)

Happy reading!

உ


8 Time Units
8 Time Units
SUBTLE DIVINE FORM
Vin-Porul

Figure 5: Lord Nataraja in the Manduka Mandala (8x8 grid) (Courtesy: Dr. Ganapathi Sthapati)

Our next topic is Nataraja and String theory!, so check out this picture. I want you to note the light / fire in the left hand and sound / damru in the right hand. If you notice little closely, you would find a central line along the picture's sternum and all the parts have minute measurements from the central line.

உ

10. TIME = SPACE SERIES. PART 10 – LORD NATARAJA AND THE STRING THEORY

“The self unfolds itself for its self – Bhagavad Gita”.

This self unfolded itself with a pulsation and this pulsation is the **start of Absolute time** (**KAALAM**). As I said nothing to my knowledge tell us clearly as to why this pulsation happened. This is the point of singularity in the scientific language and the event is termed as **Big Bang.** Just as I expressed earlier it was an event of primordial pulsation and not of an explosion which threw away mass because of the explosion into the space.

The entire space existed with its subatomic particles and this pulsation made the space to vibrate and this vibration was rhythmic and led to the evolution of this universe. **Popularly known as “That one became many”… and ..Vastur eva Vaastu.**

This pulsation happened because of the **Pranava** or the first pulsation resulted in the **Pranava -** both conceptually right. So at the time of this primordial pulsation 2 things happened:

- The absolute time started. This is called **Kaalam.**
- Primordial and the most sacred **Pranava** emerged.

Both these happened simultaneously and it is futile to ask whether **Kalam created Pranava or Pranava created the pulsation.** In many of the texts it offered as **Pranava that created the pulsation**. So let’s go by that.

- This is the reason that **Pranava / Primordial Om is so sacred in Hinduism.**
- This Pranava had manifested in 2 forms:
    - **Luminescent form as OM the Light. This is the source of all visual forms. The primordial form is represented as ஓம் in Tamil and ॐ in Sanskrit.**
    - **Aural form as Om the sound. This is the source of all aural forms. I should say that this is more popular form compared to the luminescent form.**

Now this concept is very important, since in the Pranava meditation they say us to meditate on the silence after the word OM and also mediate **OM as light, OM jyoti rasaha in vedas.**

So, when I say that sound merges into light, it is all the aural form merges into **ITS** luminescent form. All luminescent forms merge with the **Paramaanu** which is also luminescent. I am reproducing this passage again for emphasis and clarity.

- **Sage Thirumoolar** states brilliantly that who realizes that the light (physical light which means the world) merges with light (subtle light), he has realized SIVA.

  ஒளியில் ஒளிபோய் ஒடுங்கிய வாறும்
  தெளியும் அவரே சிவ சித்தர் தாமே - 124

I have read many times over to understand this concept and I would suggest that you allow this concept to sink in.

Now let's come to the 8x8 energy grid of the **Paramaanu** and imagine that it is pulsating because of Pranava and this **Pranava has both light and aural form**.

- They say that this **pulsation is rhythmic and symmetric**.
- When something is Symmetric, then there has to be a central line along with the Symmetry comes. For example if our right and left sides are symmetric then the body is divided along the sternum & backbone.
- Within the 8x8 energy grid / hall there is a **vertical luminous shaft** called **Brahma Sutra (Oli nool)**. Sutra in Sanskrit and Nool in Tamil means **Thread / String**.
- This **Olinool / Brahma Sutra is a shaft of consciousness also called Moolathoon / Moolasthambham**.
- **This shaft of consciousness vibrates in a particular order called rhythm.** This is the order of nature.
- **This rhythmic vibration of the shaft of consciousness is the dance of Shiva, the CELESTIAL DANCE / THE COSMIC DANCE / THE DANCE OF EVOLUTION of the LORD NATARAJA.**

Look again at the picture of LORD NATARAJA, he is drawn inside a 8x8 Manduka mandala (now you know what it is), his left leg is raised suggesting a movement from left to right. Imagine that he is going to land the left leg to his right side.

Why should he suggest that he is moving from left to right?

His left hand holds light / fire and his right hand holds Drum / Damru / Sound. The process of Evolution which starts with the absolute time and Pranava is fantastically represented pictorially. It suggests that the evolution process starts with the rhythmic dance of the PARAMAANU in a 8x8 energy grid and this process evolves first as light and then as sound. This light and sound creates further forms and the entire universe.

It is very easy to answer as to why sound evolves from light? We all know that the light is at a higher frequency and velocity than sound. This is the same reason we see lightning first then hear the thunders.

So let's summarize the DANCE OF EVOLUTION of LORD NATARAJA:

- From being un-manifest the **Pranava** emerges. Or the Pranava evolves the un-manifest to the manifest and starts the cycle of evolution.
- This leads to a pulsation which is called as the **COSMIC DANCE / CELESTIAL DANCE / DANCE OF EVOLUTION**.
- This pulsation is **rhythmic and symmetric**.
- The luminescent shaft of consciousness is called as **Brahma Sutra** or popularly called as String theory in the modern science.
- The process of creation evolves from the dance as light then sound evolves from light and then all the visual and aural forms in this universe.

If this is so then the process of dissolution should be that Lord Nataraja's right leg should be lifted suggesting a movement from right to left isn't?

Look at the majestic picture suggesting the **DANCE of EVOLUTION** and the **DANCE of DISSOLUTION** as below:



Figure 6: LORD NATARAJA / DANCE OF EVOLUTION



Figure 7: DANCE OF DISSOLUTION

In my opinion there is nothing more scientific in this world that is pictorially represented about the evolution of universe. You should read a book called **"The Tao of Physics" by Frijat Capra** where as physicist he explains how he experienced this and highlights the dance of the quantum particles in space corresponds to the dance of **Lord Nataraja**.

Now this central shaft of Consciousness is called **Brahma Sutra** and according to our scriptures every Paramaanu has this string, which means every being, matter, inanimate things in this universe including the tiniest of subatomic particles have this string / sutra. In the future parts we will see the Maths behind this sutra and the pulsation but let us look at what the modern science says about **Superstring theory** here, http://en.wikipedia.org/wiki/String_theory. You can read it how many times ever you want but this theoretical postulation is a direct adaptation of the cosmic dance and our Brahma Sutra and nothing more.

Now check out Lord Nataraja at the CERN http://www.fritjofcapra.net/shiva.html

As a wise man said, **"Indians are the most ignorant about their rich past and scientific traditions."**

உ

Now you may understand as to why I started this series with the above line. We have a very rich past that is most scientific and it is left codified in a form across thousands of temples in India. Let us just open your eyes and understand the scientific meaning around it.

If you are so far surprised at our richness and advancement, please wait till we will get into real hard core mathematics and geometry of our nature in the subsequent parts.

May that “**Sutradhaari”** dispel our ignorance and reveal to us the secrets of nature.

Happy reading!

11. TIME = SPACE SERIES. PART 11 – VASTUREVA VAASTU AND E=MC^2

We have seen that the universe in its un-manifest state is filled with luminescent cuboids and there was a trigger in the form of Pranava which started the absolute time and gave forth visual forms and aural forms.

This process of evolution is depicted very nicely in the following diagram:



Figure 8: Transition forms of Brahman (Coutesy: Dr. Ganapathi Stapathi)

The square (in 2D) which is an 8x8 energy grid became a 9x9 energy grid which is manifest / gross. The transition forms were an octagon and a circle. **Aintiram** suggests how this transition takes place. Current physics accepts that a pulse and a sine wave can be created from each other and this happens because of simple addition of harmonic frequencies.

The primordial pulsation initiates a rotational force and this rotational force as it gains momentum converts the square into a circle and if you notice that the octagon is just an in between state between a square and a circle.

We see confirmation of the details of this manifestation process in Chapter 9, verse 8 of the Bhagavad Gita where Lord Krsna describes His manifestation process to Arjuna:
“prakritim svaam avastabhya visrijaami punah punah”, meaning “Curving back onto myself, I create again and again…”

What it suggests is that the essential shape of every gross form in its natural state is a circle (in 2D) and a sphere in (3D). **This is the reason we find every planetary body is almost spherical in shape and this is also the reason as to why the ripples in a water body when we throw a stone in the water are in circles.**

Be it the center of a tornado or the shape of a hurricane or a tsunami it always a circular force. The supreme secret in martial arts is that the Chi moves in a circular fashion and hence Tai Chi is the most deadly form of martial arts. Lord Vishnu has Chakra as his weapon to suggest not only light but also the rotational force.

The process of manifestation is captured in these 2 pictures at all the significant stages. If you notice that a single dot becomes multiple dots, then a line, then a pulse and then goes on to becoming a 8x8 energy grid and then to a 9x9 energy grid. 8x8 is un-manifest and 9x9 is manifest. These aspects are very well captured as sutras in the book **Aintiram and Pranava Vedam.**


Dots
Line
Pulse
Absolute Space, time
Om light, Sound
Air element
Air
4x4 Matrix
Fire
Fire Element
6x6 matrix
Water
Water Element
8x8 Matrix with
4 elements
Hexagonal shape
Near Circle
Circle

Figure 9: Transition forms of Brahman in detail (Coutesy: Fabric of the Universe)

If you look at the Fig 10 conceptually the following things happen:

- Subtle Energy becomes gross universe and the fundamental 5 elements are created in the process.
- It is said that 1/10th of the space becomes Air, 1/10th of air becomes Fire, 1/10th Fire becomes Water and 1/10th of Water becomes Earth.
- So we can conclude that we are living in a **Space delineated world.**

உ


MECHANICS OF SUBTLE ENERGY TURNING INTO GROSS ENERGY
(The turn of subtle into gross.)
E = mc²
E
mc²
SUBTLE ENERGY
(8 = 9)
GROSS ENERGY
½ MODULE
8 MODULES
8 MODULES
8 MODULES
½ MODULE
AREA: 8x8 = 64 modular spaces
(Subtle scale : 8 Units)
GRID OF SUBTLE ENERGY IN VIBRANT STILLNESS
INTERIM GROWTH OF FORM DUE TO SELF - SPIN
GRID OF FULL FLEDGED MATERIAL ENERGY
SUBTLE ENERGY IN DORMANCY

THE PRIMAL MANIFEST FORM OF THE PRIMORDEAL VASTU.
IT IS SQUARISH AND OF MINUTEST PARTICLE OF SPACE.
TRIDIMENSIONALLY IT IS THE STRUCTURE OF OM - LIGHT AND OM - SOUND.

TO PUT IT IN MODERN TERMINOLOGY, THESE ENERGY CUBES ARE BUILDING BLOCKS OF THE UNIVERSE AND INFACT, THOSE ARE THE MATERIAL FORMS OF THE UNIVERSE AS WELL.

From Dr. V. Ganapati Sthapati, Kauai, 2005

Figure 10: Subtle Energy to gross (Courtesy: Dr. Ganapathi Sthapati)

This wisdom was so succinctly captured by my good friend **Lao Tzu** in "**Tao Te Ching**" as follows: (Read heaven as un-manifest space and Earth as manifest gross)

"Heaven and Earth last forever.
Why do heaven and Earth last forever?
They are unborn, so ever living….

Thirty spokes share the wheel's hub;
It is the center hole that makes it useful.
Shape clay into a vessel;
It is the space within that makes it useful.
Cut doors and windows for a room;
It is the holes which make it useful.
Therefore benefit comes from what is there;
Usefulness from what is not there…."

But I wanted to highlight more important aspects to this process of manifestation.

- **Advaita** philosophy states that there is no duality. If you note that the **Parammanu** is what is present every living being and inanimate thing. What is within you is what is within me and hence the mahavakya **“Tat Tvam Asi”… You are that**.
- **Vastureva Vaastu** – Vastu which is unmanifest and subtle becomes Vaastu which is manifest and gross.
- **If we assume that Paramaanu is God’s particle and hence it is divine, then everything in this world is divine**. This is the most important philosophy in **Hindusim**. See **the oneness in all** and see “**All in one”**.
- That’s why Hindus saw divinity in everything. Trees, snakes, animals, insects, birds, human beings etc. There is nothing without that divine energy or particle – however you call it.
- This philosophy is **UNIVERSAL, OPEN SOURCE, ALL COMPASSING and the highest state of consciousness**.

But let’s look at something even more important:

- We all note that Subtle has become Gross. Hence conceptually Gross = Subtle or both are proportionate.
- We all note that Space has become Earth. Hence conceptually Space = Earth or both are proportionate.
- We all note that 8 have become 9. Hence conceptually 8 =9 or both are proportionate.
- We all note that ENERGY has become MATTER. Hence conceptually ENERGY = MATTER or both are proportionate. This is represented by $E = mc^2$ by our great scientist Einstein. While we did not have this specific formula, the concept and the associated texts were very much with us for ages.

So this is what Einstein quoted after reading Bhagavad Gita.

"When I read the **Bhagavad-Gita** and reflect about how God created this universe everything else seems so superfluous." ~ Albert **Einstein**

Now let’s try to answer this question:

- When you throw a stone in water / pond the ripples that form take the shape of a circle (in 2D) / sphere (in 3D). Can you guess what the shape of the ripple would be if you throw the same stone in space?
- **You would have probably guessed the answer. The ripples in space should be and would be in square /cube in shape.**

As a wise man said, **“Indians are the most ignorant about their rich past and scientific traditions.”**

Happy reading!

12. TIME = SPACE SERIES. PART 12 – VEDIC CONCEPT OF TIME & ITS MEASUREMENTS

The importance of time (**Kaalam**) is so high in the Vedic tradition that they ensured that the accuracy, continuity of time and the easy measurability of it is maintained for who knows how many years. **Time creates, sustains and destroys** everything and this is very nicely captured in these 2 lines:

காலமே எவைக்கும் மூலம், காலமே மூல ஆற்றல்
காலமே கோலத் தோற்றம், காலமே ஞாலத் தோற்றம்

The god of time is **Kaala Bhairava** – a form of Shiva and hence both **Shiva** and **Yama the lord of death both were** known as **Kaalan.** The time is represented by **number 13** and it belongs to Kala bhairava. We will see the interesting linkage between Vedic system and the Mayan calendar found in Guatemala and Mexico later.

Swami Chinmayananda states that "**Time is the periodicity between 2 thoughts**". Nothing captures the concept of time more wisely. What is clear from our scriptures and Swami Chinmayanda is that time is the pulsation that creates this universe. It is the vibration with very accurate periodicity and our sages suggested that you can live beyond time provided you manage to escape the effects of that pulsation.

Einstein's view on time and its relativity is very realistically captured in this quote **"When you are courting a nice girl an hour seems like a second. When you sit on a red-hot cinder a second seems like an hour. That's relativity."** More than relativity I found that the root cause of relativity is the pulsation of mind as time. Einstein on a serious note proved that our view of time is not absolute, it is relative and it is a continuum with space. We will in the next few parts of this blog would see that time and space are the same or Time = Space.

Aintiram states that there are 5 things that vibrates which have a common root and are not under our control. They are Space, Earth (vibration of earth is gravity), Eye lids, thoughts and Musical notes and very nicely put in Tamil as (Vin)**விண், மண்(man), கண்(Kan), எண்(Yen), பண்(Pan). Pan is musical metre / chandas and Yen is the yennam or thoughts.**

Correlate this with the first line of **Patanjali Yoga Sutra** which says **"Yoga Chitta Vrtti Nirodah",** means **Yoga is one which stops the vibration of mind / pulsation of mind and hence is a killer of thoughts.** The meditation techniques of keeping your eyes opened without battling the eyelids is another way of overcoming this pulsation instinct that is primordial and inherent in our nature.

Let's look how intricate our measurements time are in Vedic system. Check out the image below.

- The smallest unit of time is approximately 2 micro second.
- The largest unit is about 155 trillion years…. YET.
- Brahma's linear age is 50 years and in currently in his 51st year which makes the universe to be 155+ trillion years. Brahma's life time is 100 years which means it would be 300 trillion+ years of universal life which follows a cycle.

- After 100 years of pulsation cycles Brahma stays as dormant energy for the same period and then pulsates again for the next life of 100 years.
- A **Brahma's** life is also known as a Para. Each half Param is referred to as a *parardham*. This second half is termed as **'*dviteeya paraardhe*'** (the second half of Brahma's term) is stated in all vedic rituals.
- After every Chatur yuga, the world recycles. After every 2000 years / a Brahma day the world dissolves and remerges. The important point to note is that there is no CONCEPT OF CREATION here. It evolves and dissolves as per the science of pulsation. We also note that this pulsation expands and contracts. This cyclical nature of time as believed in Indian mythology refers to time as '*anaadi*' or that without a beginning.



Unit	Reference	Value	Metric
1 Talpara		1.85	Micro second
1 para	60 Tatpara	111.11	milli second
1 Viliptam	60 Para	6.67	milli second
1 Liptam	60 Viliptam	0.40	seconds
1 eyelid blink	100 Viliptam	0.67	seconds
1 Kaashta	18 eyelid blinks	12.00	Seconds
1 Kshanam	10 kashta	120.00	Seconds
1 nazhigai	12 Kshanam	24.00	minutes
1 Muhurtham	2 Nazhigai	48.00	minutes
1 hour	2.5 Nazhigai	60.00	minutes
1 Day	60 Nazhigai	24.00	hours
1 week	7 days		
1 Paksha	15 days		
1 Month	2 Pakshas	30 days	
1 year	12 months	360 days	
Yugas:			
Krita		1728000	Years
Treta		1296000	Years
Dwapara		864000	Years
Kali		432000	Years
Chatur Yuga		**4320000**	**Years**
1 brahma day	2000 Chatur yuga	8640000000	
1 Brahma Year	360 Brahma days	3110.4	Billion Years
50 Brahma Years		155.52	Trillion Years

Figure 11: Time measurements in Ancient India

While doing Vedic ritual the time and space coordinate is invoked to say that you are doing this ritual at this place in the universe and at this time – with reference to Brahma's age to the time and star of the day. This tradition is unbroken and the Indian Almanac can predict the position of astronomical objects without any error for thousands of years without any sophisticated instruments and space ships.

On the contrary just read the history of the Gregorian calendar which we are following here, http://en.wikipedia.org/wiki/Gregorian_calendar. There is neither accuracy nor continuity and to top it up there are authorities who reform the calendar as if time stops and waits for them to affect that reform. Why should we ignore the best of time science that we have for an inaccurate, discontinuous reformed calendar?

As a wise man said, **"Indians are the most ignorant about their rich past and scientific traditions."**

Happy Reading!

13. TIME = SPACE SERIES. PART 13 – SOUTH AMERICAN MAYAN & SOUTH INDIAN MAAYAN

Since we are discussing about time, let us address the **Mamuni Maayan** and the **South American Mayan**.

A lot has been talked about Mayan calendar and the imminent destruction to planet earth in the year 2012. I would recommend **'The Mayan Factor – Path beyond technology" by Jose Arguelles** if you are interested in this topic.

In this part I am interested in highlighting that the **South American Mayan** and the **South Indian Mamuni Maayan** who wrote **Aintiram and Pranava Veda** are one and the same. Extensive research have been conducted by many and I found, both the works of **Jose Arguelles and late Dr. Ganapathi Stapathi** who has spent about 3 decades each, very impressive. Dr. Ganapathi concluded that they both are the same and he has shown some interesting linkages.

I am going to present what impressed me in both these great researcher's works.

- First let me state that the doomsayers of 2012 phenomenon picked up Mayan's calendar which started in 3113 BC ran for 5125 years and the calendar ended in year 2012. Since the calendar ended they thought this signified that the world is ending. Jose argues that this is wrong and most probably the human race is entering into the next phase of evolution and the next cycle would begin. If you strongly believe that this is not true and the world would certainly end by 2012, then please ensure that you transfer all your assets and savings to my name effective 22, Dec 2012. ☺

- Mayan in his calendar in South America used very unique numerals in his calendar that is given below:



Figure 12: Mayan's numeral system (Courtesy: Wikipedia, Internet)

Now let me reproduce a Tamil poem written by Mamuni Maayan in his work called "**Kanithamaa sennool**". This song is part of the book written by Maayan in Tamil during his time – 12000 years+. This song expresses how the numerals are formed till 10. It says,

  - 1 is one dot, 2 is 2 dots, 3 is 3 dots, 4 is 4 dots, 5 is a line and 10 is a double line.

மாப்புள்ளி ஒன்றே அன்றோ ஒன்றுமா எண்ணே காட்டும்

உ

மாப்புள்ளி இரண்டே யன்றோ இரண்டுமா எண்ணே காட்டும்
மாப்புள்ளி மூன்றே யன்றோ மூன்றுமா எண்ணே காட்டும்
மாப்புள்ளி நான்கே யன்றோ நான்குறு எண்ணே காட்டும்

மாப்புள்ளி ஐந்தே யன்றோ ஐந்து மா எண்ணே காட்டும்
மாப்புள்ளி கோட்டினாலே இரண்டுரு மாக்கங் காட்டி
மாவியல் திறத்தினாலே பத்தறு மாக்கங் காட்டி
மாவியல் திறத்தினாலே எண்முதற் பொருளு மாவாய்!! (கணிதமா செந்நூல் - மாயன்)

- Among the books written during Mayan's time in Guatamala are Popol Vuh, The annals of cakchiquels and the **Book of Chilam Balam**. The resemblance of **Chilam Balam to Chidambaram** with which S. Indian Maayan was so involved is very striking.

- Be the pyramids that were built in the jungles of S. America that has a striking resemblance to the viamanas from south India, the earth's revolution around the sun measured within 1/1000th of the decimal point which is available in a book called **Surya Siddhaanta – In Sanskrit** by Mayan and the identical measurements available in South America – the similarities are difficult to ignore.

- Jose Arguelles makes a compelling argument about the shift in consciousness in 2012 due to a major galactic synchronization. But what impressed me are the following:

    - Comparison between **iChing (8x8 hexagram) and Mayan's Tzolkin which is 13x20 matrix**. In fact there is a Franklin's magic square which is based on the 8x8 grid of iChing that adds upto 260 which is the galactic constant of Tzolkin. This was amazing.

    - He refers to **Radiogenesis – Universal transmission of information through or as light** or radiant energy which is very much relevant to our discussions of light and sound.

    - The revelation he received from a Maya Humbatz men belonging to the universal great brotherhood organization revealing that our universe is the 7th such system which Maya has charted in the universe. So, we are not alone ☺

Would conclude this topic in the next part…

Happy reading!


HUNAB KU
EK CHUAN: STAR TRAVELLER GLYPH
GALACTIC CIRCUIT
AHAU
KIN
SOLAR CIRCUIT
GENETIC CODE
KUXAN SUUM
PLANETARY CIRCUIT
TZOLKIN GALACTIC CODE
MEN: PLANET MIND
OC: MAMMAL BRAIN
CHICCHAN: REPTILE BRAIN
EARTH GLYPH
GALACTIC CHANNEL, RESONANT FIELD MODEL

Figure 13: Galactic Communication Channel to Hunab Ku (Courtesy: The Mayan Factor, Jose Arguelles)


TZOLKIN & BUK XOK PERMUTATION TABLE

1	8	2	9	3	10	4	11	5	12	6	13	7
2	9	3	10	4	11	5	12	6	13	7	1	8
3	10	4	11	5	12	6	13	7	1	8	2	9
4	11	5	12	6	13	7	1	8	2	9	3	10
5	12	6	13	7	1	8	2	9	3	10	4	11
6	13	7	1	8	2	9	3	10	4	11	5	12
7	1	8	2	9	3	10	4	11	5	12	6	13
8	2	9	3	10	4	11	5	12	6	13	7	1
9	3	10	4	11	5	12	6	13	7	1	8	2
10	4	11	5	12	6	13	7	1	8	2	9	3
11	5	12	6	13	7	1	8	2	9	3	10	4
12	6	13	7	1	8	2	9	3	10	4	11	5
13	7	1	8	2	9	3	10	4	11	5	12	6
1	8	2	9	3	10	4	11	5	12	6	13	7
2	9	3	10	4	11	5	12	6	13	7	1	8
3	10	4	11	5	12	6	13	7	1	8	2	9
4	11	5	12	6	13	7	1	8	2	9	3	10
5	12	6	13	7	1	8	2	9	3	10	4	11
6	13	7	1	8	2	9	3	10	4	11	5	12
7	1	8	2	9	3	10	4	11	5	12	6	13

Figure 14: Tzolkin table (Courtesy: The Mayan Factor, Jose Arguelles)

14. TIME = SPACE SERIES. PART 14 –MAYAN, TAMIL, PLEIADES & ICHING

Jose Arguelles was also mentioning that the pyramid structures of Mayan civilization in South America with the **Tzolkin** calendar matrix communicates with 2 constellations – **Pleiades and Arcturus**. Jose mentions that he is sure about communication with Pleiades constellation.

Why did Pleiades interest me?

- According to Tamil history, Tamil is a divine language and the Lord associated is **Lord Muruga**. He is the Tamil deity and he is from the **Constellation Pleiades** which is called **Kritika nakshatra**.
- This emphasis that the South American Mayan could be a Tamilian from India, as many in the ET studies circuit opine that Pleiades is a constellation which is like our distant cousin where Tamil is spoken. There are many links but you can check this out.. http://22050hz.blogspot.com/2008/10/pleaidians.html

- Look at the Mayan calendar in Fig 14, it is a 13x20 Tzolkin matrix.
    - Please recall that we mentioned **13 is the number for Kala Bhairava**.
    - Tzolkin has a mystical central column around which 6 and 6 columns exist. The belief is that this central column is the frame of reference to the galaxy and it is believed to connect to **Hunab Ku – the center of the galaxy**.
    - This mysterious centre column is believed to be the road to the sky leading to the umbilical cord of the universe. I immediately correlated this with the **thread of consciousness** which is connected to the Hiranyagarba (the center of the galaxy as per Indian texts.) – Check Figure 13.
    - So understanding that this shaft of consciousness is connected to the center of the galaxy (**Hunab Ku / Hiranyagarbha**) at the one end and to **our solar plexus** at the other end with communication and galactic information transmission happening through resonance of light, opened many gates within me.

Nothing in this universe exists without purpose and the form and shape of any being / thing is explained as a state of consciousness at a particular resonant frequency adds to the Seelam (Rhythm) aspect of the Kaalam which we are going to see later.

For the space and time travel enthusiasts, Mayan has the following:

- All space travel is intelligence as information – transmitted through light by the principle of harmonic resonance.

- **Mayan says that Sun is the lens through which galactic information is transmitted from the galactic core and interpreting this with Gayatri Mantra where we meditate on the supreme light Savitr – an aspect of Sun god is amazingly striking.**

- Mayan highlights that time is a function of principle harmonic resonance and he attaches significant importance to the numerals which he states are the galactic harmonic constants. This is exactly what **Aintiram** states.

- **He interprets the iChing to contain the Genetic code of the human DNA as a hexagram in a 8x8 matrix which is a binary progression to the 6th power corresponding 64 six part words /codons. At the same time he interprets number 260 to be galactic constant and 360 which is the factor for a calendar year or the total angle in a circle to a harmonic calibrator.** His explanations more on this and on the mystical number 7 do not resonate in my tiny brain and I am begging for holy grace to expand my mind to understand these concepts.

- **When he says that flowers open to light just does not mean that it is sensitive to be light but deeply it aspires to be LIGHT.** I am not sure if you understand the depth of this statement as against the Sage molar statement which states gross light should merge with subtle light. I have been left speechless for days after understanding this correlation.

It is interesting to note that significance of numerals as per Mayan factor:

- **1 – The pulsation – Ray of Unity**
- **2 – The pulsation - Ray of Polarity**
- **3 – The pulsation - Ray of Rhythm**
- **4 – The pulsation - Ray of Measure**
- **5 – The pulsation - Ray of center**
- **6 – The pulsation - Ray of organic balance**
- **7 – The pulsation - Ray of mystic power.**
- **8 – The pulsation - Ray of harmonic resonance.** We will see more of this.
- **9 – The pulsation - Ray of cyclic Periodicity**
- **10 – The pulsation - Ray of Manifestation**
- **11 – The pulsation - Ray of Dissonant Structure**
- **12 – The pulsation - Ray of Complex stability**
- **13 – The pulsation - Ray of Universal movement**

In all 2 independent researchers working 6000 miles apart, conducting their studies independently seems to be pointing to just one person and one philosophy and science. What else we could do other than thanking our fortune to have read them and made this connection. I thought of writing just a page on this topic and I have ended up with 2 parts and I am stopping my temptation to write few more pages on this topic. For all of those interested, please read the book by Jose Arguelles.

It is amazing to find out how most of the ancient civilizations seem to have a common root and the communication between various geographies looks stunningly simple and the metrics on astronomical objects and other space sciences seems to be so accurate despite the absence of precision instruments and spacecrafts. One tends to believe that we had far advanced knowledge of nature which we seems to have lost and most certainly few thousand years back we were not nakedly roaming in the jungles of India and Africa hunting animals as the western experts wants you to believe but had a far superior & scientifically advanced civilization.

As a wise man said, **“Indians are the most ignorant about their rich past and scientific traditions.”**

Happy Reading!

15. TIME = SPACE SERIES. PART 15 – SHIVA LINGAM IS NOT A PHALLUS

If there is one part in the series I want you to read and talk about it with your friends then it is this topic. If I ask you as to what Shiva Linga stands for then more than 99% of the responses would be that it represents a **Phallus** symbolizing the male sex organ / creative energy with the female sex organ / creative energy - Yoni as the base and both together representing **inseparability and totality in the process of creation**.

Nothing is more misunderstood and misquoted than this concept of Hinduism. Every idiot including me who has read few books about Hinduism thinks that they are experts of Indology / Vedic studies. The wisest of sages who gave us Vedas and Upanishads did not boast that it is their work. At the end of every work they acknowledged that they are telling us what they have been told by their ancestors. It is 155 trillion+ years of universal knowledge available today in the richest of the languages Tamil and Sanskrit. This cannot be accurately interpreted in a foreign language. Lest in the weakest of all languages - English.

The other contributing factor to this misunderstanding has been the Sanskrit language or should I say the richness of the language.

We have already noted that the same word can have multiple meanings. This is not limited to Sanskrit, but the all the languages. For example,

- **Sutra means thread, Aphorisms** (the ability to express something in terse and concise manner). Ex. **Kama sutra** – the most understood of all the sutras. **Brahma Sutra** – The thread of consciousness in any form that runs in this universe – the most unheard of.
- **Artha** in Sanskrit means “meaning” and “wealth”, we have already seen this. As in Vaak-Artha and Artha Sastra (the science of wealth management).
- Same way Lingam means **Symptom, Proof**, **Gender, Male sex organ** etc. Hence it was very easy to get confused, associate the lingam with a Phallus and also to ignore the philosophy and the supreme science behind it. Even people who believed that it represented much more did not knew the philosophy and the science behind it. Let’s look at what it means.

I am going to request you to kindly refer to both the pictures below:



Figure 8 – reproduced here for convenience



Figure 15 – Shiva Linga – Shape and Significance (Courtesy; Dr. Ganpathi Sthapati)

We have already seen that the subtle energy is takes the form of a square and the gross energy takes the form of a circle with an in-between state it takes the shape of a **tetrahedron and octagon**. Now look at the Shiva lingam from the top. Its base is always a square and the top is always a circle.



Figure 16 – Shiva Linga



Figure 17 – Shiva Linga with shape of the God's particle (Star) engraved.

If I have to merge all the 3 shapes together and it naturally takes the shape of a Lingam with a round top. **Shiva Linga captures the overall process of evolution in one form and shape - subtle to gross state – it encompasses every state of consciousness that is possible in this universe.**

Why the figure above states that Square shape is Sattvic, circle is Tamasic and the in between state is Rajasic? Let's understand the definitions of all the three qualities.

- **Sattvic represents the perfect state of balance. When it is subtle it is luminescent and in a perfect state of resonant non-vibration. The energy levels were perfect so that the resultant vibration is nil and it is in absolute balance.**

- **Tamasic state represents a state where the height of evolution is reached and hence it is farthest away from the core.** This is a different explanation from the usual one available in the web and books. Let me explain this. The core is very subtle and the tamasic state is very gross and hence it is away from the core. Tamasic state then should be considered as the darkest state possible. Why?

  - Because the core is luminescent and if the gross state is farthest from the core hence it should be dark. This is the meaning behind the most famous statement **‘Tamasoma Jyothir gamaya”…** take me from darkness to light. It is not about just your mind but about the entire being aspiring to become a light and merge with primordial light.
  - **There is no evolution possible beyond the Tamasic state and it has to devolve to reach its core / subtle state.**

- **Rajasic is a state where the pulsation has resulted in a rotational force and hence things are set into action. This represents the evolution process and hence associated with action.**

Then the natural next question is, if Shiva Lingam is associated with the entire spectrum of consciousness then we should see it associated the elements and the light. Isn’t?

- There is a story in Indian Purana that Brahma, Vishnu and Shiva discussed who is the most powerful among them. Lord Shiva challenged Brahma and Vishnu to reach his head and feet respectively. Brahma tried to find Shiva’s head and Vishnu tried to reach Shiva’s feet, both of them failed. Most of us would have heard the story but would not have understood the philosophical and scientific significance.

  - Lord Shiva in the form of Linga stood there as a **PILLAR OF LIGHT**. This pillar of light is **the Brahma Sutra / light of consciousness** which spanned from the center of the galaxy (Hiranyagarba) to every being & non-being in the Universe.
  - Brahma could not find the head because; Brahma is always associated with intelligence in Indian texts. He gave the supreme wisdom - the Vedas and stands for Intelligence. He could not reach Shiva’s head signifies that Intelligence will not take you to God. Intelligence as an energy is too gross and cannot reach the most subtle state of light.
  - Vishu represents earthly life – Rajasic in character – this is the tetrahedron & octagon state. He could not reach Lord Shiva’s feet signifying you cannot reach the core through actions.

- Lord Shiva in the form of Lingam is represented as one of the elements (Earth, Water, Fire, Air, and Space) in the Hindu temples.

If you read the following Upanishad quote, you can probably understand the meaning:

na karmaNaa na prajayaa dhanena tyaagenaike amRitatvamaanashuH
pareNa naakam nihitam guhaayaaM vibhraajate yadyatayo vishanti

Not by work, not by progeny, not by wealth, they have attained Immortality. Some have attained Immortality by renunciation. That which the hermits attain is laid beyond the heaven; yet it shines brilliantly in the (purified) heart.

And this quote also brilliantly articulates the luminescent nature of the Paramaanu:

na tatra (not there) **suryo bhati** (sun shines) **na candra** (moon does not) **na tarakam** (nor the stars)
nema vidyuto (nor the lightning) **bhanti** (shines) **kuta ayam agnih** (how can fire shine)
tam (that) **eva** (alone) **bhantam** (shines) **anubhati** (thereafter shines) **sarvam** (everything)
tasya bhasa (in that light) **sarvam idam vibhati** (everything shines)

The sun does not shine there, nor does the moon, nor the stars or the lightning, much less this fire (deepam). When He shines, everything shines after Him; by His light alone everything is illumined.

The trick is to take the definition & meaning from Upanishads or any scripture and apply it to the God's particle and the process of evolution and you would understand it perfectly. Many a times the concept of God & faith obscures our mind to look beyond and rationally think about it. It is not the problem of religion but our system of education which has ruined our thinking. **Today the biggest challenge we have is to "Unlearn" than to learn.**

So to conclude:

- Shiva Lingam does not represent Phallus. To represent male and female totality and inseparability Hindus do have **Arthanareeswara** and it is not represented through Lingam.
- Shiva Lingam represents the **Pillar of Light and the entire spectrum of consciousness**. From the most subtle to the most gross.
- It represents an in-between **Guna** / **EGG** state (between un-manifest and manifest) and hence it is formless with a form.
- **While Lord Nataraja represented the rhythmic pulsation of this Brahma sutra, the cosmic dance / the dance of the evolution, Shiva Lingam represents the primordial light itself in all its state of consciousness.**
- By this analogy, our body itself is a lingam with the visible body as the gross part at one end and the most subtle body which is invisible and is part of the primordial light at the other.

Check out the picture below which represents most of the aspects we have discussed so far.

May Lord Shiva help us all to understand him better.. ☺

As a wise man said, **"Indians are the most ignorant about their rich past and scientific traditions." Yet wish that this quote isn't wiser any more.**

Happy reading!

உ


NANO SCIENCE AND TECHNOLOGY OF MAMUNI MAYAN, IN A NUTSHELL
Ever Existing (VASTU BRAHMAM)
LUMINOUS CELESTIAL ZERO SPACE
Celestial Vibrant Space
GENESIS
ஒளிப்புள்ளி
கோடுகள்
கோட்டுரு
Brahma Bindu
Lines
Devoloped into linear form
8
NAAGARAM
நாகரம்
நாற்கரம்
SAATVIC
Vibrant stillness
பிரம்மஸ்தானம்
POWER POINT
Nuclear energy field
மயநெறி
Energy Grid
வாஸ்து புருஷ மண்டலம்
புனிதமா நெறி
ஒளி நூல்
பிரம்ம சூத்திரம்
Linking Heaven and Earth cocreating all living forms.
Archetypal basic forms of Architecture.
Indicating Self Spin
DRAAVIDAM
திராவிடம்
திருவிடம்
RAAJASIC
Dynamic
பிரம்ம சூத்திரம்
Ultimate Self manifest material form (earth)
VESARAM
வேஸரம்
வீசுகரம்
TAAMASIC
Gross
9
VAASTU BRAHMAN
Terrestrial Space
END Product
VASTU REVA VAASTU
ENERGY = MATTER
Illustreated Geometrically
Energy metamorphoses into matter.
E= mc 2
Anoraneeyān mahato maheeyān
Therefore Macro = Micro

Figure 18 – Manifestation in a nut shell (courtesy: Dr. Ganpathi Sthpati)

This diagram represents everything we have discussed so far. The central red line is the Brahma Sutra which runs from the center of Galaxy to the terrestrial forms. Just correlate this with the Mayan Hunab Ku in the previous part.

This summarizes as to how Energy becomes matter, Subtle becomes Gross, Un-Manifest becomes manifest, how 8 becomes 9, and Square / Cuboid becomes a circle / Sphere. All represented in one formless form called SHIVA LINGAM.

உ

16. TIME = SPACE SERIES. PART 16 – SEELAM - THE PRIMORDIAL CIRCULAR FORCE - GANAPTHI & MATHEMATICS

In the last few decades the main stream western science has started accepting concepts like uncertainty principle, wave mechanics, quantum mechanics, and periodicity of the wave pattern. Most importantly it is about the fundamental wave pattern of any energy or matter and the harmonics of these wave patterns falling in a particular form and proportion which is dictated by geometry / mathematics. In all the western scientists are scratching their heads on the depths of science of the subtle aka the sacred spatial geometry.

Most of the eastern philosophies have mastered this science and have codified these natural laws as a part of their religion, which is often dismissed as superstition. I already highlighted that in Tamil and Sanskrit the definition for science is "**Knowledge of the space**".

Modern science is moving in the right direction albeit very slow and they are trying to understand as to how elements are bonded within a molecule in addition to what elements constitute them. For example **Chlorophyll** molecule consists of **Carbon, hydrogen, nitrogen and magnesium (Mg at its core)** has a complex 12 fold Pattern – just one such typical pattern which can convert sunlight into life substance. The same pattern exists in our **RBC** cells just that it has an **iron** at its core instead of magnesium.

The understanding about the human body especially, "the spatial awareness that exists in each and every cell is due to the different sensory organs tuned at frequencies", led the scientists to unravel the innate spatial geometry of life.

Be it living, non-living beings, abstract forces like gravity, nuclear force, electromagnetism, heat, movement of astronomical bodies it does not matter what, everything in this universe adheres to a vibration / periodicity and is reducible to a number or a ratio. As a wise man said, "**Mathematics is the language of gods". This primordial rhythm & its harmonics are captured under the topic "Seelam" by Mayan in ancient tamil texts. Let's look at this in detail.**

I have been finding it difficult to sequence the flow for this topic and let me try starting from the basics:

- We know that the **Paramaanu or God's particle is a cube.** This particle with the primordial vibration combines with other particles to create a shape. **The Paramaanu combines in the multiples of 8 to evolve the next structure**. Let us see the importance of 8 later, but remember 8 is the number for Lord Narayana and Om namo Narayana has 8 Aksharas.

- What do you call a cube called in Tamil? It is called **Ganam (கனம்**). This also means heaviness, gravity, honor, dignity, abundance, plenty. To indicate it is a square cuboid they call it **கன சதுரம்**.

உ

- The process of the addition of **Paramaanu** into bigger units is called as **Ganam (கணம்,** गणं). In Tamil both the Cube and the additive resultant are called as **Ganam** and the only difference being that in Cube it uses a **small "na" (ன)** as an alphabet. In the additive process / resultant it uses a **Big "na"(ண)**. The big "na" signifies that due to the additive process the small (na) becomes big (na).

- This additive process starts because of the **first rhythmic circular** force also called as a **Suzhi (சுழி)** in tamil which means "loop".

- Here comes the beauty. The Lord of or the energy associated with this **additive force (Ganam)** is called as **Ganapathi (கணபதி, गणपती)**. Note this is the bigger "**na**" used and not smaller **"na"**. He is associated with the first circular force - **Suzhi** (and hence he takes the first honor in any Vedic ritual. This means Lord Ganapati is the first process in the evolution and everything has to start with him. Even if it is Lord Shiva or Vishnu it does not matter, the very first honor goes to the **Lord of Ganas**. Many Indians when they start writing (atleast few decades back) they first start with this symbol at the top of the page before anything for a successful completion of that activity.



- If I add my own inferences to the above with a caveat that everything else I have written have a solid back up mostly from our own study of languages (as you can yourself see) and our scriptures.
    - The symbol above signifies that what was "a point" with untouched / non-interacting energies / resulted in the primordial first circular force out of a pulse and also signifying that every circular force shall also collapse back to a point.
    - Also the bigger / heavier things are formed or created by its smallest unit and hence symbolically the heavier ones are carried by the smaller units. To signify this may be a god in the form of an elephant is carried by a mouse.

- Now you know why every ritual starts with this Sloka to Ganapathi:

    - ***"GanAnAm tva Ganapati gum Havamahe, Kavim Kavinam Upamasra vastamam Jyestharajam Brahmanam Brahmanaspat aana Srnvan nuti bhissi dasadanam"***

      This means "May you the Lord of Ganas, Ganapati",... . so it goes.

- **Now what do we call the study of this additive force - Ganas? Mathematics – Ganith / Ganitham (கணிதம், गणित).**

- **So we Indians have codified:**
    - **the primordial God's particle as Paramaanu or microbode or Lord Shiva,**
    - **the rhythmic movement of the pillar of light as Lord Nataraja,**
    - **the first circular force as the symbol for Lord Ganapathi,**
    - **the lord of the additive force as Lord Ganapthi and**
    - **the Study of this additive force which leads to the formation of everything in the universe is Mathematics in Sanskrit and Tamil.**

- **Every possible state of consciousness and manifestation is represented in Shiva Linga**
- **We will see that the multiples of 8 in which the additive force moves is codified as Lord Narayana or Vishnu and the five state manifestation process as the five letters associated with Lord Shiva.**

Just forget that these names are the names of the Hindu gods, and tell me one religion or philosophy or one branch of science in this world which can capture the nature's primordial secret in this way and codify it for the common benefit of the world and carry it for thousands / millions of years.

These are just a start and please wait for the other interesting aspects to unfold.

As a wise man said, **"Indians are the most ignorant about their rich past and scientific traditions."**

Happy Reading!

17. TIME = SPACE SERIES. PART 17 – SEELAM - THE PRIMORDIAL RHYTHM & FUNDAMENTALS

Now, let us get into some real heavy stuff - Mathematics (**Ganitham** – the study of Ganam) that governs this rhythm and harmonics. My first concern is how to make it easily digestible for an average individual who hates Math? So I shall take the easiest route that I know. I shall first explain the concept, then the actual Math part of it and then go to the philosophy and significance of the same. Later we shall look at how these are codified in nature and our scriptures and available in front of our eyes which we have failed to recognize.

Let us be clear about the following terminologies like **Progression, Proportion, root, Diagonal and Pythagoras theorem**:

- Let us take a series as follows: 2, 4, 8, 16, 32…. In this we need to be clear about what is **Progression and proportion**. As many of you know that whole series is a geometric progression where the next number in the series is a function of the current number and a multiple. This multiple here is 2, so that 2*2 = 4, 4*2 = 8 and so on. **This multiple or the constant is called as proportion**. You derive the value of the proportion by dividing the number by its previous number – (n+1)/n : (n+2)/(n+1). Hope this is clear.

- We know that a square has 4 equal sides. Each side of a square is called as "**root**" and the line that connects the 2 opposite ends is called as '**Diagonal**". In the figure below sides AB, BC, CD, DA are called as "**Root**". Lines AC, BD are called as '**Diagonal"**.



Figure 19; Square



Figure 20: Pythagoras theorem

- **Pythagoras theorem** – This theorem gave us the formula to calculate the sides of a right angle triangle as given above. If you are not familiar with this, then please understand that if you know any 2 sides of the triangle the 3rd side can be calculated by the formula given above. I am not going to focus on the argument that this theorem was available in Indian scriptures before the Greek mathematician gave it. Let's look at the concepts and not which civilization gets credit as of now.

Since the fundamental structure is a square in 2D and Cube in 3D and also in the process of evolution one becomes many, let's ask ourselves the following questions:

- **How one square does create another square which is larger in size, progressively? What is the progression and proportion in this series?**
- **How one cube does create shapes which are polygonal (Hexagon, Octagon, decagon, dodecagon etc) progressively? What is the progression and proportion in this series?**

Now let us see Figure 21 where and consider the square ABGF. You can enlarge the image to see the alphabets clearly. Now as we know sides AB, BG, GF, AF are called "**root**" – remember this well and let us assume the smallest root possible is unity and hence each root is of unit length. AB=BG=GF=AF=1. Area of this square = 1*1 = 1.



Figure 21; Square



Figure 22: Cube

Line AG is called as the **"diagonal"** and as per Pythagoras theorem the length of **AG** should be **√2**. **AG = √(AF^2+GF^2).** So to summarize **the root of the square ABGF is 1 and the diagnol is √2**.

Now consider a larger square AGHJ, here AG, GH, HJ, AJ are the sides and hence called as root. AH, GJ are the diagonal in the 2nd square. We know AG = √2, then AH = GJ = 2 as per Pythagoras theorem. To sum up **the root of the square AGHJ is √2 and the diagonal is 2. Area of this square is 2.**

If you look at the ratio **root/diagonal** (root to diagonal ratio) of both the squares it is 1/√2 and √2/2 which results in 1/√2. This will progressively hold good. The magic proportion in this progression is **√2**.

What we can infer from this is if we consider a **progression of squares** from a unit square to larger squares, then the **proportion** of the progression is √2. But before we jump into its philosophical significance let's answer the second question.

Consider the cube above whose side is of unit length. We know a cube is made of squares. We know ABCD is a square of length (root) =1 and diagonal = AC = **√2**. If we want to find out the length of the diagonal of the cube which is AE, then ACE is a right angle triangle with AC = **√2**. And CE =1 and hence **AE = √3**.

What we can infer from this is if we consider a **progression of cubes** from a unit cube to larger ones, then the **proportion of the progression is √3**.

உ

I am going to handle the significance of √2 and √3 in the next part.

Happy reading!

18. TIME = SPACE SERIES. PART 18 – SEELAM - SIGNIFICANCE OF √2 & √3

Let’s look at the significance of **√2 and √3** but before that let’s capture the philosophical significance of **Progression** and **Proportion**:

- The whole world is conceptualized as wave harmonics of the primordial rhythm with a **progression and proportion**. Philosophically the **Proportion** which does not change / which is constant is the **immutable component** and the **progression** which changes / is volatile is called as the **Mutuable component** in the process of evolution. **The whole universe is the progression and God is the proportion**. So if I know the God’s proportion and the formula behind it I can create anything in this universe including a universe. This secret is called as the Brahma Vidya / Sree Vidya (Knowledge of Brahman, Sree) in Indian texts. What we are going to see further are very minor parts of the **Brahma Vidya**. ☺

- In the last part we saw, that the primordial square multiplied itself to be a larger square (**progression of squares**) using the **proportion √2. The diagonal of the square 1 (ABCD) forms the root of Square 2 (AGHJ)**. This is very profound if you get the concept**.**

- **If we consider square 1 as the cause then its diagonal is the effect. This diagonal is the root for the next square (AGHJ) and hence the effect of Square 1 is the cause of Square 2, this cause results in square 2’s diagonal which is its effect and this is how the progression or evolution happens.** If you can see glimpses of Cause and effect cycle and the famous law of Karma in this analogy then you can pat yourself. ☺

- A square halved by the diagonal (square 1 with area 1) produces a square twice its area (square 2, area = 2). **The mystery of biological growth from cellular division or the different musical notes from the base tone is contained in this**.

- **Robert Lawlor in his book “Sacred Geometry”** very nicely puts it as the root of a plant (like the root in a square) is causative and embedded in the earth (and embedded in the square). These are very heavy and profound concepts just let it sink into you.

- When you divide the full height of the human being considering the total height as unity then belly as called as **Hara in Japanese, Dantein in Chinese, Nabhi in India** which is below the navel will measure (**2- √2**) from the soles of the feet to belly and (**√2 -1**) from navel to the head. In Yoga, Zen and Chinese meditation techniques this point corresponds to the transformative and generative aspects of the individual that involves **rooting** techniques for **self transmutation**. **So Lao Tzu said, “To seek the root is the goal”.**

- **√2 signifies the power of multiplicity. Hence the Generative aspect of this rhythm is attributed to √2. This represents the principle of transformation.**

- Remember **√2** is a proportion in the progression of squares and a square does not become a higher form. We have seen that the diagonal of the cube (sides of unit length) is **√3. It is this √3 which divides the volume form of a cube and the diagonal of the cube becomes a root for the higher shapes like pentagon, hexagon etc.**

- Hence **√3 signifies the formative power of the rhythm while √2 signifies the generative power of the nature.**

We will touch the same using **Vesica Piscis** in the next part which shall take us to **√5 and the golden mean Φ.** I am not going to touch upon important topics like Gnomic spirals and the relation between various progressions and hence I would request you to Google them if you are interested.

Happy reading!

PS:
There are many books on this topic and I would recommend **“Sacred Geometry – Philosophy & Practice” by Robert Lawlor** which I found easy to read and understand.

You tube and Internet is replete with tons of images, articles and videos on this topic and you can learn a great deal from them.

19. Time = Space Series. Part 19 – Seelam – Vesica Piscis, √5, & Golden mean (Φ)

If you don’t know what is vesica piscis, please google and you would find it interesting. I am not going to explain it here and I would focus on the summary and aspects which are often left out. The philosophical aspect of Vesica Piscis, is a rotating point becomes as circle of unity. Two circle of unity (with its radius as unity) interacting / intersecting each other in a perfect manner offers an overlapping area which is considered to be sacred and fundamental to all the geometric forms in the universe. We will first see how **√2, √3 & √5** are part of this Vesica Piscis.



Figure 23; Vesica Piscis

Please look at 2 circles who radius is unity and AB = 1, intersecting as per the diagram. The overlapping area ABCD is the Vesica Piscis and we can see **√2, √3 & √5** all part of this Vesica Piscis.

ABPQ and ABRS are 2 squares and the side of the square is 1. **√5** is as significant as **√2 and √3.** In the diagram here **√5** is the diagonal of the rectangle PQRS / diagonal of 2 squares – one below the other.

√5 is the regenerative factor that binds 2 squares or that factor that transcends two worlds or the bonding factor for 2 cosmic entities. This **√5** shall take us to the most important ratio which is the **Golden mean** or the **God’s ratio**.

But before that let me share what stuck my mind when I was engrossed **with Vesica Piscis and √3**. Look at the pictures below. These are pictures of forehead marks of Hindu Brahmins sects called Iyengars and their supreme deity is Narayana. I correlated the striking similarity of the rectangle around the Vesica piscis and Iyengar’s namam. You just have to imagine the 2 overlapping circles are the right and left side of the face with the **Vesica Piscis** starting from the top tip of the nose. To me the **formative principle of √3 is in line with the “Bhootha krut” and “Vishwa karma manu stvashtha”** aspects of **Maha Vishnu** as per Vishnu sahasranamam. I had a good laugh on this correlation.



Figure 24; Iyengar Namam 1
(Courtesy: Internet)

Figure 25: Iyengar Namam 2
(Courtesy: Internet)

Coming to the **Golden mean,** If you have not heard about it, just Google or here is a quick link http://www.goldennumber.net/. Some of you might be even have fatigue repeatedly reading and listening about it, like I do. Hence I am not going to rewrite what is widely available. But let's look at the philosophical aspect of it, its relation to **√5** and its manifestation.

Now so far in **√2, √3 & √5** what we have seen is how Unity evolves as many. But if I am interested in geometrically dividing the Unity so that this proportion evolves as unity then how do I do it?



(Figure 26: Line andΦ)

Consider a line of unit length and also consider two segments a, b so that a+b =1.

A and B are such that it has to fulfill this condition of Proportionality that a/b : b/1.

This means what 'a" is to "b", is the same as what "b" is to the whole length which is 1.

Mathematically resolving this equation a/b : b/1, hence $b^2 = a$ and hence b= **√a.** This means **a + √a = 1.** The answer to this equation is only one value which is called the **Golden mean / God's ratio** denoted by Φ = 1.6180339… and a = 1/Φ. **Philosophically it is the division of unity and the only possible creative duality within the unity.**

You may ask as to why unity is not divided into 2 equal parts and why is should be **1/Φ** (**0.6180339..).** This is effectively answered by our Upanishad **"Whether we know it or not, all things take their existence from that which perceives them"**. **Adi Shankara said "the universe is an illusion / maya**" **because it is what we perceive**. **We tend to ignore them as philosophy or superstition.**

But let's look at it scientifically as we understand. When the unity is divided into equal parts there is no asymmetry and difference and hence there is no perceptual universe. **An asymmetric division is needed to create the dynamics necessary for progression and extension of unity**.

Let's summarize our understanding again:

- **√2 – the generative component and a multiplying factor creates multiple squares from a unity of square.**
- **√3 – the formative component that creates multidimensional polygonal shapes from a cube.**
- **√5 – the regenerative component or the binding component that transcends and binds both the worlds.**
- **Φ - Golden mean or the God's ratio,** which is an evolutionary principle that is guided from within and an indisputable mathematical evidence of the conscious evolution of this Universe.
- Φ - Is a self-similar variable which can be used to derive Unity and it is the only proportion by which the Primordial rhythm maintains it perpetual oscillation to sustain this universe.
- Relation between **Φ and √5 is, Φ = (√5+1)/2**

Now let's geometrically as to how Φ **and √5** are intricately linked. Consider the Pentagon picture whose side is of unit length. Ie.

AB = BC = CD = DE=AE = 1 and

EG = FB = CG = DF = 1 and

EB = Φ = 1.61803399 and BG = 1/Φ = 0.61803399 and hence all the ratios like AG = AF = EF = GB = 1/Φ.

Also FG = $1/\Phi^2$, which means **EB = EF+FG+GB =** $\mathbf{1/\Phi+1/\Phi+1/\Phi^2}$

Also GI = $\mathbf{1/\Phi^2}$ **and GJ =** $\mathbf{1/\Phi^3}$



5.5

(Figure 27: Pentagon & Φ, Courtesy: Internet)

If you are interested more please check out the Fibonacci series and its relation to Φ. **The importance of 5 is dominant in every living organism while 6 and 8 are the characteristic of mineral and inanimate structures. It used to be rule of thumb that any plants / flowers which has 5 petals is an edible plant and hence 5 and pentagon are the symbols of life which contains the God's ratio or the golden mean.**

Now let's also understand how a **√5** is related to **√2 and √3.** If we consider a right angle triangle with the base of **√2** and height of **√3** or vice versa then the hypotenuse is **√5.** Now let me draw the connection between √2, √3, √5, Φ and π. If you think they are all some random numbers which cannot be fixed to their 10th decimal and not related to each other, just see the following relationship.

$$\pi = \Phi^2 \times 6/5 \qquad \text{or alternatively} \qquad \Phi = (\sqrt{\pi} * \sqrt{5}) / (\sqrt{2} * \sqrt{3})$$

This is the binding factor. I shall produce below some pictures which are aligned based on pentagon and the web is replete with them for you to understand more.

These 2 parts were little heavy and I shall move to easier aspects on the universal rhythm from next blog. The point I was trying to make is that everything in this universe is subject to a proportion and its fractals and let's see the manifestation of it in our daily life.

Happy reading!



(Figure 28: Pentagon & Human shape, Courtesy: Internet)



(Figure 29: Pentagon & Human face, Courtesy: Internet)


E
13
8
5
3
16
48
32
3
2
1

(Figure 30: Human hand and Fibonacci Series Courtesy: Internet)

உ



(Figure 31: Bharatanatyam and body alignment (Courtesy: Robert Lawlor, The Sacred Geometry)

The positions of Hindu classical dance (Bharat Natyam) describe geometric relationships from the axis of the body and the alignment of center of gravity at “hara” invoking rooting and divine power of transformation. In Hinduism “hara” is one of the names of Lord Shiva as in “Hara Hara Shakara”

20. TIME = SPACE SERIES. PART 20 – SANKHYA YOGA AND SAGE KAPILA

Now, let's look at what **Sankhyakarika** one of the greatest scientific works by **Sage Kapila**. I need to highlight that the **Sankhya philosophy** is one of the most evolved philosophies about the secrets of nature; it contains only 72 verses of which 68 of them define the complete spectrum of universal manifestation. **This Sankhya Yoga is referred in Bhagavad Gita – Chapter 2 is called Sankhya Yoga and in Chapter 10, verse 26, Lord Krishna identifies himself with Sage Kapila**.

Sankhya in Sanskrit means numerals / numbers. Sage Kapila states:

- Any measurement is a relational process and only a change can be measured but it takes time. The difference between the yardstick and the measured object constitutes the measured variable, which in effect is an incremental change. Since the observer can detect or measure only a change then logically, **the incremental unit of measurement itself should form the basis to derive the whole. This is the genesis of Φ.**

- **Correlate the above statement with the equation $a + \sqrt{a} = 1$. The unity is derived from the proportion "a" or $1/\Phi$.**

- As an example, the arch of a bow has expansive stress on the outer side and compressive stresses on the inner side, while the string is in tension and all are balanced at every instant. The expansive, compressive and tensile stresses can be expressed by one law.

- Alternatively, a single variable describes the proportionality of three types of forces existing at the same time. **Such a variable should be scale invariant, self-similar and have an axiomatic relationship to the whole.**

- **So Sage Kapila called $1/\Phi$ as a self-similar variable from which the unity can be derived.**

- So he postulated if **x** is the value of a measured increment then the total value **$1+x$** must be related to the ratio of change as $1/x$ at the same instant of time or simultaneously. This means **$1+x = 1/x$**, and would lead us to **$X^2 + X = 1$**.

- He quotes that if the primordial rhythm has to be self sustaining then the proportion is certainly governed by $1/\Phi$. He gives the formula for this oscillations as follows:
  - **$X = 1/\Phi = 0.61803399$**
  - **Increment / Expansion = $1+x = 1.61803399 = \Phi$**
  - **Compression = $1-x = 0.38196601 = X^2$**
  - **Resonance = $X^3 = X - X^2 = 0.23606798$**

Resonance or X^3 is the factor which protects this rhythm from decaying and dying off. So **Φ or $1/\Phi$** is such an important ratio or proportion so it is called as the **Golden mean or God's ratio**.

I shall highlight some of the factors / ratio which are part of Sankhya Yoga and what is amazing and you find formulas for Tamasic, Sattwic and Rajasic Guna states. (Please refer “Secret of Sankhya Yoga” – G. Srinivasan in the web).

- **Kapila defines the four qualities of the unmanifested state as Aikaantha (Synchronized), Aathyanta (perpetual), Atho (Dynamic)and Abhavath (unmanifest).**
- Taking C as cyclic rate of oscillation or vibration and x as rate of change per cycle then the three Guna self similar interactive states are shown as vibratory counts per cycle by the formula. **Thaama = C^{1+x} . Rajasic = C^{x+x} . Sathwa = C^{1-x}.**
- Some of the numbers that Sankhya Karika deals with are **1/7 (0.142857), π/10 (0.314159), 1/Φ (0.618034), √2 (1.414), Φ(1.61803399), √3 (1.732), √5 (2.23), e (2.718282), π (3.14159) and declares that the unmanifested state (Abhavaat) can exist only when the oscillations are between π/10 (0.314159) and e(2.718282). This is simply amazing since the state of Abhavvat is the state of Brahman.**

Despite herculean efforts I am unable to understand the Bhashya for the 72 verses which is about 500 pages explaining the secrets of Sankhya in any significant measure. I wish someone can step in and help us by explaining Sankhya Yoga that is comprehensible to our level of intelligence.

We have a treasure of secrets and richness hidden in our scriptures and it seems we have already lost most of them and the fundamental reason being our indifference to Sanskrit and our mother tongue.

As a wise man said, **“Indians are the most ignorant about their rich past and scientific traditions.”**

Happy reading!

The passage produced below is just the summary of verse 1.

…The Sankhya view that evolves out of the complete theory is that only vibrations are detected by the observer... Since only relative changes can be be detected, any fundamental component that is not in a vibratory state cannot be detected. Vibrations are caused by components in an interactive state or a cyclic state of colliding and separating that is common to all interactions and wave phenomenon.

The interactions create three distinct modes of stresses. Collisions are compressive or inelastic. The resultant reaction is expansive or elastic. When the interacting components lack the freedom to move away the interactive state is maintained in a cyclic or shuttling mode in the same location in a resonant state.

This important Sutra lays emphasis that if the observed process of detection is dependant on vibrations, then fundamental space ***must*** *contain components with those four characteristics described as states, which makes it function in a holographic way. That is all vibrations remain in fixed relationship relative to each vibratory point in a coherent and resonant state.*

உ

21. TIME = SPACE SERIES. PART 21 – 5 AND 8 THE UNIVERSAL RHYTHM

Let’s summarize what we have seen so far and then move on to more interesting aspects.

We have touched upon the God’s particle and its characteristics. We also looked at the 5 fold manifestation process and in that we looked at how **Moolam** becomes **Kaalam** (time) and how time rhythmically (**Seelam**) vibrates with a proportion and creates forms and shapes (**Kolam**). We also touched upon some of the ways we had codified the secrets of nature like **Lord Shiva, Lord Nataraja, Lord Ganapati etc.**

Before we see how rhythm **(Seelam) and shapes (Kolam)** manifests itself as universe, let’s first look at one specific word from Tamil which has three significant meanings converging into one, Yen (**எண்**), means number **eight, generic term for Number / numeral** and also root for **எண்ணம்** which means thought. I shall explain the significance of this below.

Importance of 8 / Octet:

It is stated that these God’s particles combine in the multiples of **8 / octaves ONLY** and the states of manifestation from being subtle to gross is as given below.

Formless Un-manifest State	**0 (This is the Abhavaat state)**
Guna State	**$8^0 = 1$**
First stage	**$8^1 = 8$**
Second stage	**$8^2 = 64$**
Third stage	**$8^3 = 512$**
Fourth Stage	**$8^4 = 4096$**
Fifth Stage	**$8^5 = 32768$. This is the state with manifest form.**

This rule is applicable to both the visual and aural forms which mean we can see or hear anything only in the fifth stage of evolution. So as per **Pranava veda, the fundamental numbers are 0,1** and the key **numerals for proportions are 5, 8**.

Significance of 5 and 8:

Pranava Veda describes that 8 / octets is the essential harmonic oscillator for the manifestation of the universe since this generative force is the multiple with which the whole universe manifests and sustains. You many note that number 8 is associated with Lord Narayana and his Ashtakshara mantra **(Om NaMoNaRaYaNaYa**).

The principle of 5 / Penta, we have seen is the regenerative binding force earlier. It is always a 5 stage process. This is associated with **Lord Shiva (Om NaMaSiVaYa).** The un-manifest form comes to the Guna state with the force of 5 and in the multiples of 8. It is also important to highlight that 5 and 8 are part of the **Fibonacci series and their proportion is 8/5 = 1.6, which is Φ**.

உ

But it is important to realize that the building of octets is a 5 step process for manifestation. This highlights that one cannot exist without another and both are interdependent. Now let's recall:

"Shivasya hridayam vishnur, Vishnoscha hridayam shivah:" and
"Shivaya Vishnu rupaya Vishnave Shiva rupine"

Vishnu (8) is the heart of Shiva (5) and likewise Shiva is the heart of Vishnu and they both are the representation of each other.

If you have noted Tamil language stressed the importance of words and its meaning – this was addressed in the first few parts of this series. Here Tamil language gives the importance of numerals and its significance in the formation of universe. Both the great sages **Auvaiyaar** and **Thiruvallular** stated the importance of numerals and letters in an identical fashion. Both these lines mean, Numerals and letters are like eyes for living beings / equal to eyes.

எண் என்ப ஏனை எழுத்து என்ப இவ்விரண்டும் கண் என்ப வாழும் உயிர்க்கு!
எண்ணும் எழுத்தும் கண்ணென தகும்!

Now what should be noted here is that (**எண்**) importance of numerals precedes that of letters and we know why. The aural and visual forces become letters & its associated sound at the 5th stage but the numerals are from the Guna state. **Numerals were associated with 8 / Lord Vishnu and letters were associated with 5 / Lord Shiva**. Guess you can get the scientific knowledge and significance we have in our languages.

Since what is in macro is there in microcosm, taking the analogy to microcosm our mind becomes the Moolam (Source), our thoughts are the vibration, time is measured as the periodicity between thoughts, based on the rhythm of our vibration we perceive the world. This is given very nicely as **உள்ளமே மூலமாகி உணர்வுறும் கோலமாகி**! means **Our mind is the source and its awareness becomes forms.**

This wonderful concept is what is linked in the word Yen (**எண்**), which means number **eight, generic term for Number / numeral** and also root for **எண்ணம்** thoughts. **Just this one word in Tamil highlights the supreme secret that thoughts become form and words with the help of numbers and numerical proportion converts aural and visual forms to thoughts.**

As a wise man said, **"Indians are the most ignorant about their rich past and scientific traditions."**

Happy reading!

உ

22. TIME = SPACE SERIES. PART 22 – EIGHT (OCTET) AND THE 5 SACRED ARTS

எட்டே எட்டியல் எட்டெட் டியலே
எட்டின் நெறியே அளவை மாநெறி !!

The above lines from the work **Aintiram** means **"Eight / Octa (multiples of 8) is the fundamental numeral for any measurements**. We did see that the fundamental god's particle add up with each other in the multiples of 8 in the previous part.

In ancient India there were about 64 arts (http://en.wikipedia.org/wiki/Kal%C4%81) known as **Chatuhsasti kala ("ஆய கலைகள் அறுபத்துநான்கினையும்"** as popularly known in Tamil), but I am going to talk about 5 sacred arts.

We will look at the importance of numeral 8 and how this is fundamental to everything in this Universe. But let's again start again with etymology. The word arts in **Sanskrit** is **"Kala" (कला)** and **Time in Sanskrit is काला (Kaala).** So etymologically we can say that classical arts are all about variation of time (or harmonics of this pulsation of time in the multiples of 8).

After etymology let's get to the basics. Our understanding of the universe is that **"the primordial space manifests itself as spatial forms through pulsation (Time) and its periodicity (Rhythm & order).** This evolution started with **Pranava which came out as aural and visual form (Sound & light)**. When they say **"The one became two"** they refer to the Pranava which is light and sound from the unmanifested consciousness.

Aintiram states that the dual form of **Pranava** gave forth 5 sacred arts which are fundamental to most of the other arts. **The Aural form of Pranava gave forth Poetry and Classical Carnatic music, which can only be heard. The Visual form of Pranava gave forth Sculpture and Building architecture, which can only be seen. Both the aural and visual forms merged to create the classical dance (Bharatnatyam**), which involves both seeing and hearing.



Figure 32: 5 Sacred arts

உ

They were classified as 5 vedas:

- **Poetry – Sabda veda**
- **Classical music – Gandharva Veda**
- **Classical Dance – Naatya veda**
- **Sculpture – Sthapatya Veda *(Sthapati is a clan that is the master of this veda)***
- **Architecture – Pranava Veda**

Pendatic Tamil and its construction:

Pendatic Tamil is called as **ஐந்தமிழ்** (**Aintamizh**) which consists all the five above arts, **இயல், இசை, நடனம், சிற்பம், கட்டிட கலை**. It is these 5 arts which were formed out of the Tamil language and the language itself is created from the word Om. They say that it is not 12 basic vowels in Tamil but only 5. They are அ, இ, உ, எ, ஒ. These 5 letters combine to form the rest of the letters like

அ + அ = ஆ, இ + இ = ஈ, உ + உ = ஊ, எ + எ = ஏ, ஒ + ஒ = ஓ, அ + இ = ஐ,

அ + உ = ஔ

Here you may want to note that 5 has become 12. Same way in classical music they say that the basic svaras are 5 (ச, ரி, க, ப, த) – Sa, Ri, Ga, Pa ,Da which became 7 and then 12.

So 5 is the fundamental numeral for evolution and Tamil language has grown based on this philosophy and science. I am sure some of the other Indian languages have the same basics. The book which describes this phenomenon of evolution of language from Pranava and arts from language is **Aintiram (it means 5 works) (ஐந்திறம்)** authored by Mamuni Mayan dated 10000 BC.

You would agree that the aural forms are predominantly variations in time and visual forms are of spatial variations. But our ears stand for akash tatva ("space") and it can perceive variation of time and space and we will see this in detail. When we said **"Time = Space"** we will see that both of them are governed by the same laws and measurements and hence there is no difference between **Time and Space**.

Happy reading!

உ

23. TIME = SPACE SERIES. PART 23 – NANOTECHNOLOGY IN ANCIENT INDIA & SIZE OF GOD’S PARTICLE

Let me start with these questions:

- **What is the size of the God’s particle and how is it calculated?**
- **Does nature endow a standard measure for an average human being’s height?**

Before we proceed to the next section I want to give the very detailed space calculation table used in ancient India. Our rishis did not stop just with telling us that the **Paramaanu / God’s particle** is very small but went ahead and established its size.

If you have to see such minute particles then your sensory organs – Eye and mind should be tuned to it so that it can see things at that size. From the formula available in our ancient texts I was trying to reconstruct by working backwards to find out the size of the **Paramaanu / God’s particle should be.** Please refer the table below which I have arrived at.

ANCIENT SPACIAL MEASUREMENTS		
Unit scale	**Ancient metric**	**Current day Metrics**
1 Paramaanu =	Smallest particle	133 nano meters
1 Ther Thugil=	8 Paramaanu	1065 nano meters
1 Mayir nuni=	8 Ther Thugil	8526 nano meters
1 Eer=	8 Mayir nuni	68 Micro meters
1 Paen=	8 Eer	545 Micro meters
1 Yavai=	8 Paen	0.4365 cms
1 Angula=	8 yavai	3.4925 cms
1 Tala=	6 Angula	8.25 inches
1 Muzham=	24 Angula	33 inches
1 Muzham=	4 Tala	33 inches
2 Muzham=	8 tala	66 inches
Universal height of man	9 Tala	74.25 Inches

(Figure 33: Ancient Spatial measurements. Courtesy – Dr. Ganapathi Sthapati)

I have given the exact word used in Tamil for these measurements instead of translating it in English. Ther Thugil is the dust from chariot wheel, Mayir nuni is the width of a hair tip, Eer and Paen are the lice eggs and lice. Some of you may jump that most of the units were subjective and would have variations in normal life. I agree but there is a reference point – **Angula** and its exact measure based on which other values are derived backwards to arrive at the value of Paramaanu.

Now if you note the **smallest particle** aka **God’s particle / Paramaanu** is **133 nm** in size which is currently under study by the CERN scientists. Nanotechnologists today confirm that the width of a hair strand is about 25000 nm and our ancient texts give the size at the tip of the hair strand (and not the width) as 8526 nm. I see that to be a reasonable estimate when no such precision instruments were available in those days.

One Angula is 11/8 of an inch. This is the fundamental measure which is used in any of the worldly measurements. Now you can see that 6 Angula is 1 Tala which is about 8.25 inches and then comes the most important revelation. **Does nature endow a measure for an average human being’s height?**

The answer is yes. **As I said an average human being should be 9 Tala’s height and hence the nature endowed height for any human being is 74.25 inches.** This is the ideal height and the variation is attributed to our Karma, hereditary and lifestyle.

Now let me give few tips to find out your height from typical measurements:

- Measure the length of the face (from forehead to chin). Your total height should be 9 times that height. This is the principle of Nava tala. As an extension measure your thigh or legs length excluding the knee and feet and your total height should be 4.5 times that.

- Take your right hand middle finger (No. Don’t show it to anyone☺). You would notice that the finger is divided into 3 parts. Measure the length of the lowest part – from the end of the palm to the first subsection. Your height typically should be 54 times this measure. Since this measure for an average man with nature endowed length shall be 1 Angula. Hence your height shall be 54 times that measure.

- The length of the thumb from the base of the wrist should be about 3 Angula and hence 18 times of that should be your height. This can go on and on.

So, to sum up this section:

- Instead of looking them as Rishis or Sages or religious figures if we look at them as scientists in the field of nanotechnology, quantum physics and Astro dynamics we would accept most of the secrets without any prejudice.

- Not just the measure for the height of the man but they had formula for every object and this was the secret of their wisdom. For any astronomical object, they had formulas to measure body’s core (width) and also the width of the mantle. The roots of their wisdom lie in understanding that “many’ are just a harmonic variation of the “one” subject to a mathematical proportion. Hence there was no “rocket science” in those days and all of them were as simple as it looks like.

As a wise man said, **“Indians are the most ignorant about their rich past and scientific traditions.”**

Happy reading!

24. TIME = SPACE SERIES. PART 24 – OCTET, OCTAVE AND THE GANDHARVA VEDA (CLASSICAL MUSIC)

Let’s start with classical music where Octaves form the fundamental for it. There are seven svaras (Sa, Ri, Ga, Ma, Pa, Da, Ni) which is made into an octave with another Sa after Ni. So it becomes Sa, Ri, Ga, Ma, Pa, Da, Ni, Sa (*Do Re Mi Fa Sol La Ti Do*). The first rule of classical music is “**Shruthi Mata, Layam Pita**”, which means **Shruthi is the mother and this corresponds to the frequency or the spatial component and Laya is the Tala component which is a function of time compared as father**.

Tala	Anga Notation	Tisra	Chatusra	Khanda	Misra	Sankeerna
Dhruva	IOII	11	14	17	23	29
Matya	IOI	8	10	12	16	20
Rupaka	OI	5	6	7	9	11
Jhampa	IUO	6	7	8	10	12
Triputa	IOO	7	8	9	11	13
Ata	IIOO	10	12	14	18	22
Eka	I	3	4	5	7	9

(Figure 34: 35 types of Tala. Courtesy: Wikipedia, internet)

There are 7 fundamental Talas in carnatic music and each Tala has 5 different variation based on Jathi so in all there are 35 different Talas as given in the tabulation. These Talas are measured as the “matras” the unit duration of time. There is another concept called Nadai or Gati which we will not touch upon now. But let’s look at these 35 variations and can you tell me where the most famous “Adi Tala” is in this 35? Most importantly why it is also called as **“Adi Tala” – which is the primordial rhythm**?

The answer is **“Chatusra Jathi Triputa tala”** highlighted in the table is called as **“Adi Tala”** and it is called so since it gave the most primordial rhythm with 8 time units. But there are couples of more cells where we can see “8” in the table and why these are not called ‘**Adi Tala**”?

The primordial rhythm has a pattern of **1, 3, 2 and 2** which adds to 8. Further on we will see just the variation of this Adi Tala in anything and everything. Tisra Jati matya Thala has a structure of 3, 2, 3 and Kanda Jati jhampa Tala has a structure of 5,1,2, hence they are not classified as the primordial rhythm.

Let’s quickly touch upon the spatial variation or the frequency / pitch aspect of this divine art before we branch off to other topics. The image below gives the 16 levels of Savaras which includes tones and sub tones. The seven svaras become 22 tones based on the frequency variation / harmonics. Here 7 are fundamental svaras and 16 as given below is the most practiced variation and 22 is not popular.



Levels	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
Svaras	s	ra	ri	ru	ga	gi	gu	ma	mi	p	dha	dhi	dhu	na	ni	nu	s
Ratio	1	32/31	16/15	10/9	32/27	6/5	5/4	4/3	27/20	3/2	128/81	8/5	5/3	16/9	9/5	15/8	2
Factor	1.0000	1.0323	1.0667	1.1111	1.1852	1.2000	1.2500	1.3333	1.3500	1.5000	1.5802	1.6000	1.6667	1.7778	1.8000	1.8750	2.0000
Freq (Hz)	240.00	247.74	256.00	266.67	284.44	288.00	300.00	320.00	324.00	360.00	379.26	384.00	400.00	426.67	432.00	450.00	480.00

(Figure 35: Svaras and frequencies)

You can note that Sa starts with 240 Hz and the last Sa is 480 Hz doubling the frequency and hence an octave. While Sa has 240 hz and 480Hz levels, the tone Pa (P) or Sol does not have any variation and this is at 360Hz. I am going to correlate the Mayan studies with Carnatic music and instead of seeing the whole spectrum from “Sa”, I am going to see this spectrum from “Pa”.

You would note that “Pa” at 360 Hz corresponds to the **Harmonic osciallator constant number** and the whole spectrum is almost like a Sine wave from 360Hz to 480 hz and falling down to 240 Hz with a uniform gap of 120Hz above and below. All the tones would fall within this 240Hz centered around 360 hz. So the spatial variation in carnatic music can be summed as “It originates at a value (240Hz) and varies by the same measure (240Hz) centered on the harmonic oscillator”. Since the objective is about looking at the primordial rhythm we will not touch any other aspect on this topic.

We will see how this **Adi Tala** is the fundamental pattern / rhythm that manifests in every other art.

As a wise man said, **“Indians are the most ignorant about their rich past and scientific traditions.”**

Happy reading!

உ

25. TIME = SPACE SERIES. PART 25 – ADI TALA, NAVA TALA AND STHAPATYA VEDA (SCULPTURE)

Let’s look at how Octet and the primordial rhythm (Adi Tala) that defines Sculpture. Let’s recap some of the following:

- The process of evolution starts with Pranava which has aural and visual forms. We have also seen that anything subtle is represented in a 8x8 energy grid and anything gross is in 9x9 grid.
- The fundamental measure with which the particles bond is **Eight or** it’s multiple and hence the primordial rhythm is an **Octet.**
- The fundamental measure of time is **Tala** and the **primordial Tala is Adi tala** with 8 units and a pattern of 1, 3, 2 and 2.


¼
1
¼
1
1
1
2
¼
2
¼
1
3
2
2
NAVATALA
ADITALA
Gross Human Form
From micro- to macro- level
All gross forms are musically structured as the units are in musical octave.

(Figure 36: Human form – Adi Tala, Nava Tala Courtesy: Dr. Ganpathi Sthapati)

Now let’s see the measurement rules as to how to make a sculpture of a human being.

- **The overall human height is measured as 9 talas.** Yes the same time measurement is used to measure height. Pinch yourself now, since height is a space variation and not a time variation yet it is measured with a metric of time. This is a secret which is unknown to many and even some of the experts in this field. This is where Time and spaces merges without any difference and this is the fundamental rule with which we have been creating visual and aural structures in the universe.

- **Divide a man’s height as 9 units of which head, torso, thigh and legs would fall into the pattern of 1, 3, 2 and 2 which adds up to 8. This is the primordial rhythm – the Adi Tala now as a human form.**
  - Then how 8 became 9? No other branch of Vedas or science tells us this secret so explicitly to my knowledge. **The following parts, Top of the head to forehead, Neck, Knee and feet each measure 0.25 talas and hence add 1 additional tala to 8 and it becomes 9.** So Adi tala which is a subtle version of human becomes Nava Tala which is the gross version of human being. In the process of 8 becoming nine all the joints are formed in the body☺.

  - Let me add one more dimension to this. Our human body has a gross body (Sthula) and a subtle body (Sookshma sarira). **The Sthapatya veda tells us that the gross body is nava tala and sookshma sarira is Adi Tala**.

  - I fell off the chair when I understood this and the linkages. Check if you are still on your chair and maybe you should sit on the floor from now on☺.

Martial Arts and Lord Nataraja’s stance:

Let me ask you the following questions here:

- Look at the image of the Lord Nataraja below. If a gross image should have Nava Tala which is a 9x9 grid then why the human image of Lord Nataraja which is a Nava Tala fitted into a 8x8 square instead of a 9x9 square?

- Both in Classical dance and in martial arts why do they ask you to stand in a posture where the knee is slightly or significantly bent. Not all of the stances but most of the basic stances correspond to this why? Let me know if you have received a satisfactory answer for this question.

உ



(Figure 5 reproduced)

- The answer to this question reveals one more secret to us.
    a. **In Sthapatya veda each grid line is divided into 10 or 11 or 12 (usually 12) and hence a 9x9 grid has 9*12 = 108 blocks or levels of energy. This may explain why 108 is a sacred number from an energy perspective.** This covers the entire spectrum.
    b. When we create a gross image its always sculpted to 9 talas but when they sculpt image of the gods and in this case Nataraja, they fit the gross image to a 8x8 energy grid to invoke the subtle energies.
    c. How do they fit a 9 tala to 8 tala? The technique is not to change the proportion of nava tala but they ensure that 9 fits into 8 by making the image to bend it legs such that the height reduces by one unit.

- You can notice that Lord Nataraja’s right leg is bent to fit the image in 8x8 grid. This is believed to invoke the subtle energies corresponding to that image.
- This is the same reason why martial arts and in Bharatnatyam your teacher asks you to take a basic stance which reduces the height from 9 units to 8 to invoke subtle energies. Of course the other reason is the alignment and focus to Hara / Dantein with that pose.

உ

If I tell you that the science of nature and the associated philosophy codified in Hindu religious symbols are unmatched and amazing then I hope you would whole heartedly agree now. These religious texts and symbols offer the key to unlock the secrets of nature.

So to sum up, so far we have seen one variation of time as **Gandharva veda** that manifests as classical music and the primordial rhythm is **Adi Tala.** Next we saw that the **Sthapatya veda** in the form of sculptures offered the secret of space variation in **Adi Tala and Nava Tala**.

This is where Time and Space were equated with the same measure yet offered completely different arts.

The whole universe has these underlying and un-manifested interconnections and hence the **Hindu philosophy of "That one became many"…** is the supreme truth. Seeing the divinity in everything is the only truthful way of recognizing this science.

As a wise man said, **"Indians are the most ignorant about their rich past and scientific traditions."**

Happy reading!

26. TIME = SPACE SERIES. PART 26 – SABDA VEDA, CHANDAS & POETRY (MA NISHAADA…)

शुक्लाम्बरधरं विष्णुं

शशिवर्णं चतुर्भुजम् ।

प्रसन्नवदनं ध्यायेत्

सर्वविघ्नोपशान्तये ॥

Shuklaambaradharam Vissnnum Shashivarnnam Caturbhujam |
Prasannavadanam Dhyaayet Sarvavighnopashaantaye ||

Let's start with this Sloka as a sample to see how 8 and its harmonics are integrated with Poetry. In this sloka there are 4 lines (a line is called Pada and Pada means feet in Sanskrit) and each line has 8 Sanskrit Aksharas (Only vowels and vowels with consonants imposed on them should be counted and pure consonants are not part of the count.) This is usually written in 2 lines as shown in English.

This is the most popular way of creating a sloka or poem in most of the Indian languages. This "metre" resonates as 32 aksharas in 4 padas. You may want to correlate this with 1,3,2,2 where the last 2 stands for your feet. So feet (pada) measures 1/4th of the overall length of the subtle body (8 units) and 4 padas create the full blown subtle body. So such a constructed poem is a throbbing and vibrating energy body or a living organism and hence carries the power of the words it contains.

If all the padas have equal metre say 8 units then it is called **Sama Vrtta,** and if all are different it is called **Vi-Sama Vrtta** (not equal). **This 8 and 32 is the same as Adi Tala in carnatic music and ashta tala in sculpture. Can you make the connection now?**

In Sanskrit this metre is called as "**Chandas" and in Tamil it is called "Chandam**". **Chandas** is also one of the 4 important Vendagas and is called as the feet of the Vedas. **Let me ask you as to which language the Vedas are available in its primordial form?** The most popular and incorrect answer is Sanskrit. This is the level of awareness we have. Lets quickly look at these important points about Vedas and I shall correlate this with our topic of discussion.

- Unlike other faiths Hindus don't attribute the Vedas as word of god or given by some prophet. We consider Vedas as the breath of god (**"Nishwasitam"**) and not the word which means, Vedas are not created by god, but the breath. If there is no breath that person would not leave and hence it is associated with the very presence of god.

- Vedas are also **Apourusheya** which means it is not created by man and **Anaadi**, that does not have a beginning.

- But you can ignore them stating these are blind beliefs. Let's look at how this correlated with the science. Vedas are created by Pranava and these should be considered as the harmonics of the primordial vibration and nothing more.

  - If it is pure vibration then the “which language it is written?” sounds stupid isn’t. If it’s pure vibration it has to be expressed in “Hz or wavelength” equivalent in ancient India. This is what **Chandas or metre** is all about. This measures pure vibration and anyone capable of tuning themselves to those frequencies have **SEEN** the Vedas and not **created them.** Hence all our rishis are **Mantra Drishtas and not Karthas**.

Difference between Vedas and Poetry:

Vedas contains both **poetic verses (Padya) and prose (Gadya)**. All the poetic verses are called **Chandas** and it complies with the rule as stated above. The difference between normal poetry and Vedas are, Vedas contain tonal variations (high pitch and low pitch) apart from the time, space variations but in Poetry there are no tonal variations. What has tonal variations and are not part of Vedas are called Slokas. So to sum up:

- Vedas are both in Padya and Gadya. What is in Padya is called chandas and it has tonal variations in addition to the time space variations.
- What has tonal variations but not part of Vedas is called as slokas.
- What does not have tonal variation but comply with the chandas rules are called Poetry.

Harmonics and types in Chandas:

We saw every line to have 8 matras / units / aksharas. There are variations and these are the harmonics available.

- **Gayatri –** This is a very special chandas with the mantra where instead of 4 padas, there are only 3 padas and hence it is called Tripada Gayatri. Each pada has 8 Aksharas and hence 24 Aksharas in Gayatri Mantra. This is also the only chandas where a mantra is named after the chandas. Some people write it as 6 letters per line and 4 padas which makes it 24.
- **Ushnik Chandas –** 7 letters per pada and 28 letters in all.
- **Anushtub Chandas –** This is the fundamental and popular one with 8 matras per pada and 32 in all. Ramayana the first poetry was set in this metre.
- **Brihatee Chandas -** 9 letters per pada and 36 letters in all
- **Pangti Chandas -** 10 letters per pada and 40 letters in all
- **Trishtup Chandas -** 11 letters per pada and 44 letters in all
- **Jagti Chandas -** 12 letters per pada and 48 letters in all. This has a subtype called bhujangam which is split as 6-6 and that moves like a snake. (Ex. Subramanya Bhujangam)
- **Shikarini Chandas -** 17 letters per pada and 68 letters in all. In Soundarya Lahiri it is split as 6 and 11 by Adi Shankara.
- **Udkriti Chandas –** 26 letters per pada and 104 letters in all.
- **Dhandakam – above 26 per pada**. **Ex.** Garuda Dandakam by Vedantha Diskshitar.

The reason I have given all the above is to emphasis that nothing in our religious scriptures, literatures are without a grammar, order, form or proportion. Everything confirms to a mathematical proportion.

Just like **Vedas are the breath of god, Chandas is the breath of every mantra.** The mantra is powerful only if it is recited to this metre. This is the reasons some of the poem even if it is not related to religion stands the test of time. Also if you recite a mantra even without knowing its meaning but as per the chandas then the mantra shall bear its fruit.

“Ma Nishada” …..Origin of Poetry:

Would you believe that the first poetry in this universe started with a curse?

Sage Valmiki saw a hunter who killed one of the birds of a pair which were in love. The sage got enraged and cursed the hunter, ***O, Hunter, may you not fare well anytime as you killed one of pair of the Krouncha birds which were happily engaged in love”.***

mA niShAda pratiShThA.n tvamagamaH shAshvatI.n samAH |
yatkrauJNchamithunAdekamavadhIH kAmamohitam.h || (bAlakANDa 2.14)

The above sloka also meant ***“O Lord of Lakshmi, it will bring you eternal glory for having killed a male of a happy couple who lost his head completely in lust..”*** This male is Ravana who lost his head in lust despite being happily married with his wife Mandodari. The other interesting connection I have this sloka with this series is that the **Mamuni Mayan** is the father of **queen Mandodari** and father in law of demon king Ravana.

Once the sage realized that this curse also meant something very auspicious and referred to Rama avatar he wrote Ramayana which is the origin of poetry as known in the world and it is called **Adi Kaavya.** Valmiki Ramayana set in **Anushtub Chandas** which is an octet.

So if you look at both the poetry and classical music composition:

- The rhythm in which it is set is a pulsation of time which confirms to a divine proportion.
- The raga and the pitch variation is a pulsation of space / frequency which again confirms to a divine proportion. We did not discuss about ragas though.
- The words used are divine and we have seen the divinity of the letters and words.
- The meaning of the song / poem usually exhorts the qualities of the god and hence is divine.
- The classical music and poetry invoke the subtle divine energy in the aural form just as much the sculpture (when it confirms to the divine proportion) invokes the subtle energy from in its visual form.
- This is how we see that “**one became many”** and **binding factors** in this process of evolution being the numerals 5 and 8.

Alas! Today, we are the fanatic fans of musicians who lacks morality & humility, who is ignorant of any divine proportion, most of the music we hear is a cacophony and very mechanical, the words are indecipherable and lacks depth, the meaning of the song - if at all any are just suggestive of sexual emotions and nothing else and the dance movements we see are the gyrations of the hip with a great blend of fitness training exercises associated with it. This is not to negate some of the fine works we see even today but to stress that we had such high science and taste which we seems to be losing / lost for no good reason other than ignorance.

As a wise man said, **“Indians are the most ignorant about their rich past and scientific traditions.”**

Happy reading!

உ

27. TIME = SPACE SERIES. PART 27 – ARCHITECTURE – THE ZENITH OF MATHEMATICS (VAASTU)

Just look back in history and see what stands the test of time. Even if a civilization is completely extinct what stand beyond their time is the architecture of the civilization which stands tall as a witness to the richness and maturity of the civilization.

Aintiram states that **"Architecture (Space engineering) is the zenith of the mathematics**" in **"கட்டிட கலையே கணக்கியல் உச்சி**..." This space science is called as Vaastu Sastra in India.

There are few important concepts in Vaastu science which I want to present as below:

- The whole world is made up of **God's particle (Vastu, வஸ்து**) and nothing else. It is this God's particle which actually manifests itself as gross forms (**Vaastu, வாஸ்து**). You would note that Vastu (Subtle) has become Vaastu (gross) by addition of letter "a" and this difference is reflected in our languages too. **When அ / अ become ஆ / आ the subtle becomes gross**. Hence the most important statement for this science is "**Vastur eva Vaastu**", this means **the subtle becomes gross or energy becomes matter or the space becomes earth.** This is purely manifestation / evolution and there is no creation. This has nothing to do with religion but supreme science.

- Since it is all only one energy and it ever vibrates based on the harmonics and resonance, this vibration is called life and everything in this world, be it a living being or a non-living being as per our current definition – everything vibrates. The chair you sit and the vehicle you use are all living beings. **Everything throbs with energy and there is nothing which is a non-living being in this universe.** Without this vibration there would not be any difference between iron and cotton. The difference between particles is essentially the molecular constitution which is a function of its elements and its periodicity. This defines presence or absence of quality and sensory perceptions. This was put very nicely by **Poet Subramanya Bharathi** as எங்கு காணினும் சக்தியடா, **Where ever you see its just energy.**

- The above concept is very profound and this is called as **Science in our scriptures since it deals with Knowledge of the space** (விண் ஞானம், Vin-gyan).

- By the same concept when a subtle energy which is in the open space is converted to a gross form like a building then this body / building vibrates based on the design specifications and the material used for that building. It does not matter what is the measure and what is the material used, it vibrates. **When a structure is created with a divine proportion then we breathe life**

into it. Thus the structure becomes a living organism. This is how some of the structure stands the test of time for thousands of years.

- **Vaastu is that science which aligns the vibration of the building with the vibration of the dweller in the building so that both the living organisms (the building and the dweller) are in harmony and resonance.**

- It sounds simple but for this science we need to know includes the vibration pattern of the dweller, mathematics of space engineering, the knowledge of materials and its nature so that we can match it up to create harmony. This is precisely what Vaastu as a science does. Again it has nothing to do with religion. If you Google you would find thousands of Vaastu experts outside India who perceive and pursue this as a supreme spatial science.

- Let us look at the word **"vas"** which is the root. This means to shine; to grow bright, **to bestow by shining upon**, becoming light. **Vaas** is its derivative which means to perfume, an intoxicant, **dwelling place**, to assume the appearance of matter. This is the root for **SriniVAAS**, **SreeVAASan**, **VAASam** in Tamil means living. Most importantly the ability to feel this subtle thing (which cannot be touched) is called **VAASanai (**வாசனை, **in Tamil it means smell).**

- This spatial science includes knowledge on the following:
    - Nature of soil and material, and the qualities of its energy.
    - Measures for spatial engineering that best resonates with the environment and the dweller.
        - Note that the dwelling unit cannot be compatible to all the human beings universally. This varies with individual to individual and hence the Vaastu compatibility for the house is always seen for the housewife than the man with the assumption that what is compatible to the lady of the house would suit all others.

    - Accurate calculation of time and the position of astronomical bodies. The time engineering merges here with the space engineering. Consider the following to understand this:
        - In some temples you would notice that the sunlight falls on the deity on a specific day / time of the day. This is not possible if the future position of astronomical bodies at a given time is calculated very accurately.
        - When we build a house / temple the inauguration ceremony should be conducted at a specific time. So it's just not Space Engineering but time engineering also.

    - We see that the concept of space and time are not just a continuum but:

        - The measures of time and space merge and results in the same unit measure called Tala. It is Adi Tala in Poetry, Music and the same measure is used in building and sculpture dimensions.

- **Space is created because of the pulsation called Time** and hence the unit time measure (for pulsation) and the unit space measure (result of pulsation) are one and the same. This means the pulsation causes proportional displacement or creation of Space.

- It is the same concept used in meditation techniques. With Pranayama, Dharana and Dhyana you control the pulsation and align with it. In Samadhi you stop the pulsation and hence you are beyond time and space and you reach a luminescent state of resonant non-vibration.

Hence I named this book as **"Time = Space".**

We have seen that each subtle unit is represented in 8x8 energy grid and the gross unit is represented in a 9x9 energy grid. Mayan states that **"Each module or pada within the 8x8 / 9x9 structure resonates with a specific energy.** Based on Space, Time, Light, and Sound coordinates the frequency of vibration has its unique position in the Space/ Time continuum. **This energy level of frequency of vibration is called a luminous body or Devata**. This devata has particular attributes based upon its position and qualities in the Space/Time continuum (placement among the 64 / 81 sub-cubes or padas)".


4 12 20 28 = 64
4+8 =12+8 =20+8=28
1) Bindu point (central point at intersection of lines - energy source)
2) Brahma pada (first concentric belt around bindu point) = 4 modules
3) Deivika pada (second concentric belt) = 12 modules
4) Maanusha pada (third contric belt) = 20 modules
5) Paisachika pada (fourth concentric belt) 28 modules
The 8X8 Manduka Vastu Mandala formed of 64 vibrating Space Time units

Figure 37: 5 states of 8x8 Energy Grid (Courtesy: Dr. Ganapathi Sthapati)

Now what is evident here in this science is 8 and 5 merges and so does Space and time.

- **Manifestation occurs in additive values of eight and in 5 stages. You can note that the Bindu (Point) has become 4, then 12, then 20 and then 28. (4+8=12 +8=20+8=28 with a total additive factor of 64). Manifestation occurs in sequences of five steps known as the Pentadic Order.**
- **The mathematical calculation which gives form to consciousness / space / subtle matter is called "Ayadi Gananam". We know that Ganam as the additive process.**

Dr. Jessica Marcey in her Fabric of Universe states that:

- The subtle energy point in the center becomes a self effulgent energy generator pouring out waves of energy
- becoming a self spinning stabilized structure of four padas / modules then
- adding eight units of energy to manifest the 4X4 structure of 16 units or modules; then
- adding another eight units of energy to manifest the 6X6 structure of 36 units or modules; then
- Adds eight more units culminating in 64 units or modules strung concentrically around the Bindu point or central generator.

So a central point with 4 concentric square belts around, each has its own frequency, vibration and energy characteristics evolving into a 9x9 unit as a gross matter. While this knowledge is significant of itself, when these phenomena are viewed in light of material manifestation as built space in architecture, the significance becomes stunning and profound.


PHALASRUTI
(EFFECTS OF SUBTLE AND GROSS SPACES ON HUMAN SYSTEM)
NORTH
SOUTH
WEST
EAST
NW
NE
SW
SE
ORDER
Sadyobrahmanyam āpnuyāt
Frequent fear from serpent
Quick attainment of spiritual goal
Greatness multiplies
Acquires the benefit of having performed yajna
Death in water
Stomach disease
Destruction of women folk
Suffer from rheumatism
Skin disease
Physically emaciated but does not die
Daily fatigue
Fear from friends and thieves
Good qualities
Aparadvāram
Abundant profit
Absorption
Fire accident to house building
Loss of wealth
Victory
Aparadvāram
Name and fame
Demise of children
Rift among friends
Divorce from husband
Destruction
Death
Loss of Grains
Accident
Development of all activities
Toal destruction and death
Increase of riches
Death of husband
Depression
Death of head of family
Vāyuhu
Nāgaha
Mukhyaha
Bhallātaha
Somaha
Bhujagaha
Aditihi
Ditihi
Esaha
Pāpa yakshmaha
Rudraha
Prithvi dharaha
Apaha
Parjanyaha
Shoshaha
Yakshmā
Āpavatsaha
Jayantaha
Asuraha
Indraha
Varunaha
Mitraha
Brahma Padaha
Aryamā
Suryaha
Pushpa dantaha
Satyaha
Sugrivaha
Indraha
Vivaswān
Savitā
Brushaha
Dauwārika
Jayaha
Savitraha
Antarikshaha
Nirutihi
Mrugaha
Brungarājaha
Gandharvaha
Yamaha
Gruhak shataha
Vitataha
Pooshaha
Agnihi

Figure 38: 9x9 energy grid with corresponding energy levels for each grid.
(Courtesy: Dr. Jessica Marcey, Fabric of the Universe)

So, to sum up this section, we have seen that how every inanimate thing in this universe is still a living being and how with the spatial science we can pump throbbing energy into a building. This is the supreme science where Time and Space merges. This is the 4th sacred art we talked about which is a manifestation of the visual form of Om.

உ

As you would have noticed I have avoided talking about rituals and rules here but focused on the concept and philosophy. When we talk about rituals there are very many variations and we get into an unnecessary argument that whether it is rational or superstitious. Since most of the arts have become commercialized, the person’s qualification and his intentions are always questionable.

The objective of this book is to highlight the scientific aspects of the universe in a small way and emphasis that our culture is built on this science. Be it language or arts or religion all are built on scientific facts. They all were nourished and nurtured in thousands of Temples across India which is the container and protector of this subtle science and energy.

Let’s see some more interesting aspects of this in the next section.

Happy reading!

28. TIME = SPACE SERIES. PART 28 – CAPTURING THE DIVINE ENERGY – SQUARES & CIRCLES

It is told that the sanctorum of Lord Ranganatha's temple at Sri Rangam is circle from outside and square from inside. Why?

- Subtle energy is represented by 8x8 square grid and the perimeter of the square is 4r and the area of the square is r*r. When each grid length is 1 unit then r = 8, so perimeter is 32 and area of this square is 64.
- Gross energy is represented by 9x9 square grids and with the same measurements perimeter is 36 and area of this square is 91.

It has been an architect's dream to create and capture subtle energy in a gross structure. This is fundamental objective of spatial engineering. How do you go about to achieve this? It looks that they found that they would take the help of a circle either outside the square or inside the square to achieve this. Remember almost every yantra has a square and a circle component in it.

The measurements are so taken such that either the perimeter or the area of both the circle and the 8x8 square are matched. Most of the Hindu temples follow such rules to invoke the subtle energy in a gross structure like temple. This is one of the well kept secrets and this is the reason each and every temple is said to interact with your subtle body differently when you visit it.

This is why Lord Ranganatha's sanctorum in Sri Rangam temple is a circle from outside and square from inside. This secret is called as **Squaring a Circle**. This is all about to creating divine energies and this is the science that is implemented in all the Hindu temples which are built as per the Sastra. You need just basic math knowledge and patience to understand this supreme secret and I shall give below 2 techniques to match the area or the perimeter of the circle with that of the 8x8 square.

Perimeter match:



- Let's look at the image of a circle of unit radius. The **area of the large circle is π** (πr^2) and the **circumference is 2π**. Here r =1.
- Draw 2 circles inside as shown with half the radius. The area of each circle is π/4 and the **combined area of both the circles is π/2**. The circumference of each circle is π and the **combined circumference of both the circles put together is 2π**.

Figure 39: Squaring a Circle (Courtesy: Dr. Robert Lawlor, Sacred Geometry)

- Just note that when a larger circle divides itself as 2 smaller circles the area is halved but the circumference is the same. **This gives the first philosophical metaphor that "One has become two which are bipolar yet non-dual". This is one of the fundamental principles of Advaita and also in Chinese philosophy. This bipolar non-dual force is the basis of life and is represented as male / female and Yang / Yin.**

- Now draw 2 arcs NDM and NEM from A' and A with the radius as A'P and AQ as shown in the dotted line. You would note that point D and E would divide the radius of the circle by divine proportion – $1/\Phi$ and $1/\Phi^2$. **Radius of the arc AE is Φ. The Yin Yang symbol is based on this principle which embeds the divine proportion in it.**

- Now let me draw a square ABCD around this circle (Fig 40) where the side of the square is the diameter of the circle which is unit 2. Here OP =1, AB=BC=CD=DA = 2. **The perimeter of the square is 8 and the area of the square is 4.**

- Now draw a circle with O as the center and NO as the radius as shown in the figure. Here NO = $\sqrt{\Phi}$. You can take this figure as such if you find it difficult to follow but for those who are interested, the derivation to calculate radius "NO" is as below:



Figure 40: Squaring a Circle 2 (Courtesy: Dr. Robert Lawlor, Sacred Geometry)

  - Consider a right angle triangle OPN. We know OP = 1 and PN which is the radius of the arc = Φ. Hence as per Pythagoras theorem $PN^2 = OP^2 + ON^2$ which is $\Phi^2 = 1+r^2$. Let us say the radius is ON = r.
  - So $r = \sqrt{(\Phi^2-1)}$. We know Φ is 1.61803399 so **$r = \sqrt{\Phi}$.**

- We have got a larger outer circle with a radius **$\sqrt{\Phi}$** and hence the perimeter should be **$2\pi\sqrt{\Phi}$. This is numerically equal to 7.9924576, which is equal to 8. Now we have created a structure where a square whose perimeter and a circle whose perimeter are the same.** This technique is not limited to India but used in the same way for pyramid construction.

- **This is the perimeter match between 8x8 square grids and a circle around it**.

Area match:

- Vaastu has an easier way to get this done. Draw a circle inside a 9x9 energy grid whose diameter is equal to the side of the square. If each energy grid length is 1 unit, then side of the square is 9 units and the radius is 4.5 units.

- The area of this circle is πr^2 where r=4.5 and hence the area of the circle is 63.64 which is almost equal to area of the 8x8 square with unit grid length as 1 unit.

- This is the area match between a circle and 8x8 square. So as per Vaastu every building is divided into 9x9 grid and the energy level of each grid is used to design the living space.

Capturing the direction of Subtle energy flow:

The subtle divine energy flows is as per the diagram given below. It starts from the center and always flows clockwise. That is why Hindus always stick to clockwise flow of movements - be in their temples or anywhere else. This clockwise flow of movement is captured in the sacred symbol Swastik. Here 1 is the source / Moolam, 2 is Kaalam (Time), 3 Seelam (Rhythm), 4 Kolam (Form), 5 (Universe) Gnalam.



Figure 41: Clockwise flow of subtle energy



Figure 42: Swastik symbolizing energy flow

Relationship between √2, √3, √5, Φ and π:

- Now let me draw the connection between √2, √3, √5, Φ and π. Understanding this relationship is orgasmic and nothing less. If you think they are all some random numbers which cannot be fixed to their 10th decimal and not related to each other, just see the following relationship.

  $$\pi = \Phi^2 \times 6/5$$

  Philosophically 6/5 is the relation of a hexagon to a pentagon and the other way to express this relationship is

  $$\Phi = (\sqrt{\pi} * \sqrt{5}) / (\sqrt{2} * \sqrt{3}).$$

- This goes to prove that we did not just knew the numerals but divine fractions and proportions including their linkages. I am convinced, there is not even an iota of superstition in our temple and idol worship but they are supreme sciences codified and left for our benefits.

- The temple of **Sri Rangam** dates back from Ramayana, which is Treta Yuga that is 800000+ years back as per Hindu Scriptures. This is our rich past and supreme science is embedded in our culture and codified in thousands of temples across nook and corner of the country. Why should we ignore this? We have a lot more to offer this world which is struggling to understand the nature of nature.

As a wise man said, **“Indians are the most ignorant about their rich past and scientific traditions.”**

Happy reading!


MAYAN'S PYRAMID AS IN MEXICO
MAAYAN'S STEPPED PYRAMID EVOLUTION OF PYRAMID INTO VIMANA
MAAYAN'S PYRAMID AND MAYAN'S VIMANA

அடித்தளம் விரிந்ததாகி அவைமேலே குறுகிச் செல்ல
படித்தளம் போல்விளங்கும் படித்தளமாகி நின்று
குடித்தளம் அமைத்தலாலே, குணநிலை வடிவே கண்டு
அடித்தள நிலைக்கே ஏற்ற முடித்தளம் அமையும் காண்பீர்

முடித்தளம் குமைமயின் ஆட்சி, படைத்தளத் தன்மைக் கீழே
விடித்தளமாகக் கண்டு கீழ்வரும் நிலையைக் கண்டு
அடித்தள நுணுக்க மோர்ந்து, படைத்தலால் உணர்வேயோங்கி
நடைத்தளம் காண்டல் அன்றோ நலமுறும் சிற்ப மென்றார்.

முடித்தள வுச்சியன்றோ மூலத்தை நன்குணர்த்தி
முடிமுதற் பொருளேயாக்கி முழுப்பொருள் நிறைந்த மாட்சி
முடித்தளம் வெளியில் தேக்கி, முடித்தளம் வளியால் ஆக்கி.
முடித்தளம் ஒளியிசைக்க, முயல்வதே சிற்ப மென்றார்.

The base remains expanded while tapering upwards in a stepped pattern representing the form of the inner consciousness. The finial is in a proportionate order of the measurement at the base.

The top layer of energy is the ruling element. This surges forth upward and reaches the apex in a vertical column. This basic square is energy atom causing consciousness and the steps indicate its ascendancy. The whole form of the stepped pyramid is called ***sirpam*** *(sculpture).*

The crust which symbolizes a dense energy source, becomes a primal elemental energy and such energy is the ultimate source which causes first the air and in return it becomes the spiritual light and finally into sound. Even this is called Sirpam.

In other words, the pyramid with fire at the center symbolizes the mechanics of our inner spirit which turns into material pyramid, called ***SIRPAM*** *(Inner picture).*

Such pyramids exist even today not only in Maayan land but in Egypt, India, China and Japan. This means that the spiritual culture emanating from Kumari continent or Lumerian continent had spread, in the remote past, throughout the earth. So this Mayonic culture can be rightly called Universal culture not restricted to India alone. - Dr. V. Ganapati Sthapati

Figure 43: Similarity between Indian temples, Pyramids. The Tamil text states how the structure should be built. (Courtesy: Dr. Ganapathi Sthapati)

உ

29. TIME = SPACE SERIES. PART 29 – HEAVEN & EARTH – LORD NATARAJA & LORD RANGANATHA

Let’s stay with Lord Ranganatha and see the relationship between him and Lord Nataraja. Would you be surprised if one is the mirror image of the other? Look at the majestic picture of Lord Nataraja below. Wonder why this is always made in metal and not in wood or earth?



Figure 6 reproduced.

In Pancha bhoota (Space, Air, Fire, Water, Earth) Metal is always associated with Space and Wood is associated with Air. This system is reflected well in the Chinese system and it was not any different in our Vaastu system either. Since Lord Nataraja signifies Akasha tatva, **(Vin porul)** he is always made in metal – Copper or Gold or Bronze or a mix of it. The statues which were ancient had a generous amount of gold giving a luminescent look about the statues. The art and science of moulding metals to create divine forms with precise proportion dates back to thousands of years in India and the western experts think that this is a recent phenomenon. This is a complete surprise to the western world since they cannot believe that such sophistication existed before.

Dr. Ganapathi states, *“Lord Nataraja also signifies the primal image being expressive of the secret of creation in the process of which formless becomes instantaneously endowed with features and of perfect form. This is the reason why the statue of Lord Nataraja is called as* ***Silpa****, the primal image and everything else which is sculpted in this universe is called as* ***Pratima (replica)*** *and the original and one and only sculpture is the image of Lord Nataraja***”.**

Mamuni Mayan states, *"Bhumih pradhana vastu Syat"*, means Earth by virtue of being the very basic support of all things, this is the primal and dominant Vastu". Earth and space are manifestations of each other in the cyclical process of evolution. They both should always be considered to be in unison. This vibrant, energetic, manifest earth energy (**Prithvi Tatva)** is called as '**Vishnu**".

In Vaastu satra, the Vaastu purusha is Lord Vishnu and understandably Vishnu is invoked as Vaastu purusha in Srirangam temple and offered a seat in the heart of Lord Ranganatha even today as a ritual.



Figure 44: Lord Ranganatha in the reclining pose

Lord Ranganatha represents manifest earth energy **(Man porul)** and hence is always made out of seasoned earth only and it should be properly painted too. He is never to be made of metal. This earth form does not support frequent mobility and symbolizes stability and immobility. **This is the reason when Vibhishana kept the idol of Lord Ranganatha down at Sri Rangam it could not be moved.**

The energy that is in available in every universal form is represented as Vishnu and hence he is called as **Antaryami**. Once the subtle becomes grosser the vibration is reduced and the grossest form would not have any creative pulsation in it. It would still have the vibration based on its nature which ensures that it retains the form and shape. But it does not have any creative pulsation and it has reached the zenith of evolution. **This zenith is characterized by Lord Ranganatha in the reclining pose**.

The creative pulsation (Space) is the dance and the zenith of manifestation is a reclining posture (Earth).

உ

As we have seen, Lord Nataraja carries **Light in his left hand** and **sound in his right hand**. Lord Ranganatha carries **Chakra representing light in the right hand** and **Conch representing sound in the left hand.** The principle that the primal substance (space) has manifested as the universe (earth) and both of them are mirror images of each other is reflected in both the images.

In Chinese texts the Yang energy is associated with Heaven and the Yin as earth. Now associate the same heaven with Shiva, Earth with Vishnu and Tao with the God's particle - with some of the text below from **Lao Tzu's "Tao te Ching"**

"The Tao that can be told is not the eternal Tao.
The name that can be named is not the eternal name.
The nameless is the beginning of heaven and Earth.
The named is the mother of the ten thousand things.

Something mysteriously formed, Born before heaven and Earth.
In the silence and the void, Standing alone and unchanging,
Ever present and in motion, Perhaps it is the mother of ten thousand things.
I do not know its name. Call it Tao.

Man follows Earth. Earth follows heaven. Heaven follows the Tao.
Tao follows what is natural."

To sum up in the words of Dr. Ganapathi Sthapati:

- **Both the temples Chidambaram and Srirangam are south facing temples.**

- **Lord Nataraja signifies Akasha Tatva, outer space, macrocosm, subtle unmanifested energy is the Vastu purusha, is always in dancing pose, circumscribed in 8x8 square and made of metal.**

- **Lord Ranganatha signifies Prithvi Tatva, inner space, microcosm, manifest gross energy, is the Vaastu purusha is always in reclining pose, depicted in a circle or a 9x9 grid and made of earth.**

- **Lord Nataraja represents energy with matter and Lord Ranganatha matter with energy. In the equation $E = mc^2$, Lord Nataraja represents E and Lord Ranganatha represents mc^2.**

- Both these temples are a 'must see" and a "periodic see" types and you would be amazed that the qualitative change in your mental state even if you don't pray inside the temple but spend some time sitting or walking in the premises of the temple.

- **Both these temples are perfect symbols of ancient science codified for the benefit of the society and left for generations withstanding the test of time.**



Figure 45: Sri Chakra – The Supreme shape in sacred Geometry

Chidambaram and Sri Rangam should be ground zero for any lab that wants looks into the secrets of space and time as they represent supreme science as much as they represent spirituality. We now see that science was the basis of our spiritual faith unlike it being 2 completely different aspects today across the world.

As a wise man said, **“Indians are the most ignorant about their rich past and scientific traditions.”**

May we be blessed by the divine power to unravel unknown secrets about the nature!

Happy reading!

30. TIME = SPACE SERIES. PART 30 – TEMPLES AND IDOL WORSHIP

Let us forget Hinduism, its symbols and names of god for the time being and consider these aspects as pure science from a nanotechnologist and cosmologist called Mayan.

We have been told that the universe is full of luminescent particles and this particle manifests itself because of the primordial pulsation. We have had a sneak peek into the geometry and the mathematical proportion which is used in the creation of many things. We know that the universe rhythm confirms to a mathematical code to the extent that we can create divine energies in a temple based on that science.

If time is pulsation of consciousness and if it creates, sustains and destroys everything, then time is the architect sculpting the universe and every object in this universe should be a sculpture of time and this concept is very beautifully captured in ***"Jagat Sarvaram Silpameva'*** *meaning the entire universe is nothing more than a shilpa / sculpture (and it latently conveys that Time is the Shilpi).*

If all the above things are right then is it not right to say that "Man created the concept of God" or "Man can create divine energy around him"? Let me sum up my thoughts as below:

- The sages and rishis were essentially scientists and understood the secret of nature very well. They were understandably masters in **nanotechnology and cosmology.**

- They knew that "**One thing"** with which they could understand the nature and science of all other things in this universe. This is obviously supported by the mathematical knowledge they had.

- As per Vedas nothing is created by god including the Vedas, but universe is the manifestation of god. They also understood that man is the most evolved of this manifestation. This is why they created all the god forms in the image of a man.

- Be it language, poetry, classical music, classical dance, sculpture and architecture it was the manifestation of this divinity that was the underlying link. Sacred geometry and sacred proportions were used to generate the subtle energy that took us closer to divine.

Hindu temples were created to capture all these aspects in one place and which could sustain and grow for the benefit of mankind.

- Secret of nature heard through the vibrations of Vedas were codified as supreme science and weaved into a philosophy called **Sanatana Dharma.**

- Architecture of temples confirmed to divine proportions and space - time engineering was accurate to capture sunlight and moon light at the same position for thousands of years. The design of the temple cleaned the subtle energies and points of the human body.

உ



மூலாதாரக் கணபதித் திருமேனியின், படிமமான இலக்கணம்:

गुणरवि नयन रुद्रं द्वादशं षट् षडांशं
अनल रसगुण भागं केश वक्त्रं च कण्डं ।
हृदय उदरमेढ्रं ऊरुजानुंच जंरवा
पदमिति उदयमानं पञ्चतालं गणेशम् ॥

3,12,2,11,12,6,6,3,6,3 [=64 துடிப்பளவுகள்] முறையே, கேசம், முகம், கழுத்து, மார்பு, வயிறு, மேட்ரம், தொடை முட்டி முன்கால், பாதம் ஆகியவற்றின் உயர அளவுகளாகும். இவை பஞ்ச தாள கணேச உருவத்தின் [உறுப்புக்களின்] உயர அளவுகளாகின்றன. [இது கண்யம் என்று சொல்லப்படும்].

பட விளக்கம் பின்வருமாறு:

விநாயகர் [ஐங்கரத்தன்]

Figure 46: Ganapathi Idol (Courtesy: Dr. Ganapathi Sthapati)

The sloka above in Sanskrit gives the measure of different parts of this Idol which would confirm to total 64 units (resonance of 8). Hair (3), Face(12), neck(2), Chest(11), Stomach(12), Belly &Pelvis (6), Thigh(6), Knee(3), Legs (6), Feet (3). Total 64 units. Just as much a Sloka with right metre and letters becomes a living organism, an idol with right proportions becomes a living organism.

- Divine Idol forms confirmed to a mathematical proportion that invoked subtle energies within and around us. This is where the external forms were used to create energies internally to a human. **This is the basis of idol worship. If it is scientific to create a form with divine energies based on mathematical proportion then idol worship is the supreme proof for that science.**

- **This supreme mathematical law is called as Dharma (nature‘s law) and the unfolding of that law is the Karmic theory of cause and effect / law of karma.**

- Poetry, classical music and classical dance are intimately linked to this Hindu temple culture. Adi Tala and octaves were used to create subtle energies in poetry using words, and the same tala maana is used in classical music with rhythm and raga, in classical dance with light and sound and in sculpture as a visual form.



Figure 47: Human body as a representation of a temple
(Courtesy: http://www.salagram.net/sstp-mgpuja3.html)

A Hindu temple is a divine and yogic representation of a human being with the Deity in the temple representing the God as indweller in humans and all beings. In a temple the feet represents Rajagopura, the hands represent Praakaara, the abdomen represent Mandapa, the heart represents Antaraala and the crown of the head represents the sanctum sanctorum (garbha griha). The temple is used as a reminder that our inner spiritual journey is through internal yoga to realize the indweller God. This analogy is shown through the representation of various chakras namely Moolaadhara to Sahasraara in the body to various locations in the temple.

- It may be of interest to note that the same harmonics of 8 are reflected in every other domain. For example, if you have been practicing Pranayama then your master would have asked you to practice breathing based on some counts. The most popular counts are 6(inhale), 3 (Exhale) or 7(inhale), 2 (Exhale). If you notice this count 9, this cleans up your gross body. Advanced Pranayam students may be asked to stick to 1 (Inhale), 4 (Retain), 2(Exhale), 2(Retain outside) or as a variation 1,4,2,1 or 1,3,2,2. The counts which add up to 8 clean the subtle body.

- Till few decades back the fundamental dimension for money in India was "**Ana"** called as **Eight Anas (எட்டணா)** and this was equivalent to Rs. 0.5 as the fundamental measure.

- Thus a **"Poetry is an idol in aural form and a building is a frozen music"**. A Poet by the way of his mental frequency has first become the poem itself and then the actual poem was created in its aural form and an artist by the same frequency has become the idol first and then he gave a shape to the idol externally through this hands. This is very beautifully given as ***"Raso vai saha, So Vai rasikaha", which means he (god) is the enjoyer and he is the artist.***

- All of this reflects the supreme philosophy that **"Oneness in all and everything is just a manifestation of that one thing"**.

- Now in this light understand the meaning of this Upanishad prayer, *"Aum Poornamadah Poornamidam Poornaath Poornam Udachyathe, Poornasya Poornamaadaaya Poornameva Vasishyathe". This means God is perfect (infinite). This Universe is also perfect (infinite). If perfection (infinity) is taken from anything perfect (infinite) what remains is still perfect (infinite).* Isn't this is the actual reality today?

- Everything scientific is philosophically, mythological and ritually well interwoven that proves that Sanatana Dharma is the most ancient and supreme representation of science and nature's secret in our possession. Our temple worship which integrates all this science, 5 sacred arts with language and Math is the standing example of our understanding of the nature of god.

உ

- 

Figure 47: Layout of Sri Rangam temple with 7 Prakaras

It is the same Sugarcane but an elephant eats it from the field directly, a young adult peels the skin off and chews it, if a kid has to eat then someone has to peel the skin and cut it into pieces and an old man without teeth needs it to be made as sugarcane juice. Depending on one's ability to chew and digest the food has to be processed.

Same way depending on one's mental ability to grasp the supreme truth it has to be processed and presented. If someone is mentally well evolved then they can be fed with Upanishads and he can meditate on the formless Brahman. To a young adult Upanishads may not be palatable directly but they may have to start with Upavedas and Vedangas to mature to a higher level. For the less evolved kids, Itihasa and Purana like Ramayana and Mahabharata with stories may drive home the point and they can start with Shlokas and mantras. But for the least evolved it has to start with a personal deity with name and form, bhajans and songs to invoke the concept of Bhakthi.

In all the four cases temple culture forms the lowest common denominator. Even the most evolved relish the arts and architecture in the temples. We should be proud of our rich cultural and scientific heritage and be passionate about the science and philosophy and be rational about rituals and symbolisms.

Image / Idol worship is not deplorable or despicable. This is the highest scientific form of worship which enables us to see face to face the one which is beyond reach of sight and speech. This kindles devotion, community development and helps one to climb the steep walls of spirituality in the initial stages. Every religion in this world has some image or idol as symbolism to achieve this objective.

An idol is a god in form when made with the science of divine proportion and seasoned material is the highest product of our intelligence till today.

It should however be noted that this idol worship should not be lost in the din of rituals which does not reflect the very philosophy it had come to symbolize. So the advice I follow is *“Be passionate about our culture but be rational about the rituals.*”

The advancement of science can progress rapidly when the western scientists who are objective and empirical, partner with the pundits in India and learn the science of the subtle from our scriptures and temples. For this to happen we need to learn our own scriptures and past which is not possible without learning our mother tongue and Sanskrit. Else in the near future we may have to import knowledge of our culture and rich past from the western world.

As a wise man said, **“Indians are the most ignorant about their rich past and scientific traditions.”**

Happy reading!

உ

31. TIME = SPACE SERIES. PART 31 – MAYAN & HIS WORKS

Mahamuni Mayan was the father-in-law of Demon King Ravana and is referred in both Mahabharata and Ramayana. He is attributed with building the palace for Yudhishtar in Indraprasta and also the architect for Sri Lanka which Ravana ruled. His son Nalan helped Lord Rama build the Ramasethu – the bridge between India and Sri Lanka. He is believed to have lived in the **Ilamuridesam** popularly known as **Lemuria continent (Kumari Kandam**) which spanned 4500+ kms from Sri Lanka to Antartica connecting current Australia, Africa and Americas. Check out http://www.sacred-texts.com/atl/tll/index.htm

Understandably when this land mass was consumed by the sea their clan moved to different parts of the world including Guatemala, Egypt, and to current south Indian region. This explains as to how we find common science across India, South America and Egypt.



Figure 48: Kumari Kandam depiction

He has written books in both Sanskrit and Tamil and I am going to produce the list of technical works he has created and look at the contents of a specific book called Surya Siddhanta. Just the list of works and also the topics in Surya Siddhanta is amazing, highlighting the depth of science we had at that time. http://www.youtube.com/watch?v=PZKiCpFisoY

The Surya Siddhanta

The most ancient treatise on Astronomy is a treatise authored by Mayan. It is called *The Surya Siddhanta*. Included in this treatise are the following chapter topics following:

- The Motions of the Planets
- The Places of the Planets
- Direction, Place and Time
- The Moon and Eclipses
- The Sun and Eclipses
- The Projection of Eclipses
- Planetary Conjunctions
- Conjunction of the Stars
- Risings and Settings
- The Moon’s Risings and Settings
- Certain Malignant Aspects of the Sun and Moon
- Cosmogony, Geography, and Dimensions of the Creation
- The Gnomon
- The Movement of the Heavens and Human Activity

உ



Figure 49: Mamumi Mayan

Mayan is also attributed with the start and spread of Temple culture in India. The song below in Tamil states that since Mayan sat under the Banyan tree and taught this science of universe and also of the sacred arts, so that every town was endowed with Temples for social betterment. Because he was from the southern region and also he sat under the Banyan tree, he is also equated with Lord Dakshinamoorthy.

ஆலமா மரத்தின் கீழே அருள் மயன் அமர்ந்ததாலே
ஆலமா மரத்தின் கீழே அருட் கலை வளர்ந்ததாலே
ஆலமா மரத்தின் கீழே அறிவர்கள் வளர்ந்ததாலே
ஆலயம் ஊரும்தோறும் அமைந்தன செழிக்கநன்றே!!

The Mayan says in his Pranava Veda verse one:
*"Om Light and Om Sound are the Primal Source of all manifest forms. Om Light is aroused by its own effort in a state of disorder and appears as a flame. The state of Om Light and Om Sound in Space is a magnificent luminous six – faced Light form that is called "**murukoli**". The transformation of Om Light and Om Sound through the five stages is concealed in the five fold knowledge, of which, this is the first. This process of transformation of disorderly Om Light and Om Sound into orderliness is found in all five fold material forms."*

Sage Veda Vyasa says in the Bhagavatam, *"eka eva pura vedo pranavha sarva vangmayha" (9th skandha, 14th chapter, sloka 48 of Bhagavatam).* This means that there was only one Veda called Pranava Veda. It is believed that Sage Vyasa created 4 vedas from this Veda since he believed that the oncoming generations would not have the mental strength to master everything.

உ



Figure 50: Aerial view of Sri Rangam temple with 7 Prakaras

Technical works

The following are technical works written by Mayan and represent the 12 vowels of the Tamil language:

- Ovia Chennool - Treatise on Drafting and Painting
- Sirpama Chenool - Treatise on Iconometry
- Kattida Chennool - Treatise on Architecture
- Nilamanai Chennool - Treatise on House Building based on quality of land
- Manainila Chennool - Treatise on Land based on the nature of house building
- Baniyal Chenool - Treatise on Astro Physics
- Perunata Chenool - Treatise on Divine dance
- Muligai Chenool - Treatise on Herbs
- Ganitama Chenool - Treatise on Mathematics
- Arakkala Chenool - Treatise on Ship Building
- Vinkala Chennool - Treatise on Space Ship
- Elisai Chennool - Treatise on Science of Music

உ

MAYAN, in Aintiram *states that:*
"There exists an order in the Universe - subtle universe, and material universe. This power is attributed to the consciousness of the cosmic space as well as of the inner space of the animate beings. This consciousness, by its personal effort to express its own inner feelings, causes a kind of vibration or pulsation in the inner space, resulting in energy-grids. The vibration or pulsation, being the causal element of all these events, is called KAALA. This is actually the force of energy aroused by the inner consciousness, causing waves and contributing to the growth of living forms. This KAALA resides in all living beings. So, space is the offshoot of the vibration of the primordial energy. This is how the space was born. All forms of nature are manifest forms of subtle energy. For all to get manifested, the force is KAALAM. This wave-form frequency realm is the creative element of the universe."

There is no other treatise that we have in our possession today which is dated 10000 BC that depicts the secret of nature so explicitly and gives the unmanifested interconnections and mathematical proportions between everything in the universe.

As Dr. Ganapathi Sthapati rues "Unfortunately most of the Tamil experts don't understand the science in these texts and hence these books are idling without anyone extracting the truths from it". In the next few generations when we are less equipped in our own mother tongue we may lose this treasure completely just like the many we have lost so far.

Hence the first step we need to ensure is even if you are not equipped well in your mother tongue please make sure that your kids can read and write it well. This becomes our most important duty. And I find it worrisome when someone is indifferent to the fact that they can understand their mother tongue but cannot read and write.

With some significant efforts we can and we should prove that this man who said, **"Indians are the most ignorant about their rich past and scientific traditions."** is not wise any more.

Happy reading!

உ

32. Time = Space Series. Part 32 – Conclusion

What I have understood in a nutshell is as follows:

- The inner being of both - the individual and the universe is luminescent consciousness which has the ability to become aware of it. This luminescent consciousness is called by various names but it is essentially the only existent Vastu in this world. This Vastu manifests itself as time, space and spatial forms.

- ***"Aanor aniyaan mahato Mahiyaan!"*** this means what is in the atom is the same makes up the universe. That which is present in the atom is the Space energy and the meaning of the word Akasa is stated as ***"Aa kashayati aakasa ha!,*** That which imparts light to others or make others shine is called Akasa". This means that Space Vastu is luminescent. I am stressing the aspect of luminescent again and again for you to start perceiving God as light.

- Pranava is the causal element which triggers this evolution process and this manifests as visual and aural forms. Pranava results in the primordial pulsation and this pulsation is triggered and sustained by a divine progression and proportion which is called **Absolute time**.

- Absolute time creates Absolute Space. These 4 things – Absolute time, absolute space, Aural Pranava and Visual Pranava combine together to form spatial forms and hence this universe.

- The Vastu as God's particle, its characteristics, the Pranava, the pulsation, the rhythm, the progression, its proportion and the resultant energy states – all the scientific facts, theories and processes are captured and codified as a Dharma which is called as Hinduism today. The science behind this subtle energy is reflected in various art forms that includes Poetry, Classical music, dance, Sculpture and building architecture.

- All these manifestations are harmonics of 5 and 8 differentiated by the Golden proportion / God's ratio to reflect the various states of consciousness. **This intrinsic order is called Dharma and the cyclic nature of this evolution is the Karmic code embedded in the universe**. **Nothing in this universe is superior to the Dharma and Karmic code.**

- The divinity manifests in us and the space within us is nothing different from the macrocosm. Consciousness which exhibits itself as a state of being because of our mental vibration can evolve to a higher plane to devolve back into the luminescent core.

- Sanatana Dharma popularly today known as Hinduism is the repository of this supreme secret not just as a philosophy but integrated with every stage of our life. This can be understood better only if we can give due respect and attention to the language and scriptures, our spiritual tradition interwoven with arts and architecture that contains these treasures.

- The temple culture & Idol worship that we have symbolizes the best of science known to human beings and we need to understand this and preserve this in the best possible manner.


SATYA – JNANA – ANANTA
BRAMHAN
वेदाः
VEDAS
RIG VEDA
ATHARVA VEDA
YAJUR VEDA
SAMA VEDA
SMRITI
ITIHASA
PURANAS
SUB
VEDAS
उपवेदाः
AYUR VEDA
ARTHA VEDA
DHANUR VEDA
GANDHARVA
VEDA
VEDA
COMPONENTS
वेदाङ्गानि
JYOTISHA
SHIKSHA
CHANDAS
KALPA
VYAKARANA
NIRUKTA
SUB
COMPONENTS
उपाङ्गानि
NYAYA
VEDANTA
VAISESHIKA
SANKHYA
YOGA
MIMANSA
PRASTHANA
TRAYI
-UPANISHADS
-BRAHMASUTRA
-GITA

Figure 51: Vedic Knowledge as an inverted tree with Brahman as the roots signifying that everything has a common root. (Courtesy: Internet)



(Figure 52: Goddess Sarasvati. Courtesy: Internet)

She is the Goddess of speech, music and knowledge. She carries the rosary beads (akshamala) represents the alphabets of a language (Sanskrit), the musical instrument (Veena) and Vedas as palm leaf manuscript in her hands that denotes the knowledge. Thus we can see that idol worship signifies deeper scientific aspects of a common root between Language, Music, knowledge and arts.

Figure 52: Musical instrument Veena as a representation of Human Body (Sarira veena) (Courtesy: Internet)



உ

I am happy to note the coincidence that this book has 32 chapters with 108 pages – both being key universal numerals. Chapter 19 (the golden mean of this book) deals with the Golden mean or God's ratio of nature is again coincidental.

I would like to thank you for reading this book. I would like to state that I am neither adept in any of the topics discussed in this book nor an expert in any of the arts including the languages Tamil or Sanskrit language.

A curious mind driven by my passion to understand the underlying aspect in all things and my liking to reading has helped me to compile this book. My exposure as a student to Chinese martial arts, Indian yogic studies, Pranic healing and Siddha philosophy helped me to connect of the points I had articulated. Any authoritative statements in these books reflect my belief in the topic or from the author / teacher from whom I subscribed it and it is certainly not reflective of my abilities.

I am open to constructive criticisms on any of the topics and I can be reached at the mail ID shared in the first page of this book. My only request to you is *"Please share this book or parts of this book without any hesitation to your friends and family and help us dispel the ignorance about rich ancient Indian culture"*.

I shall end this book with some of my favorite quotes of Dr. Einstein.

"My religion consists of a humble admiration of the illimitable superior spirit who reveals himself in the slight details we are able to perceive with our frail and feeble mind. That deep emotional conviction of the presence of a superior reasoning power, which is revealed in the incomprehensible universe, forms my idea of God. We still do not know one thousandth of one percent of what nature has revealed to us."

Satyam Param Deemahi!
May we meditate on the supreme truth!

TIME & THE TECHNOSPHERE

The Law of Time in Human Affairs


2001
1973
1945
2000
1972
1999
1971
DECEMBER
JAN
12
11
1
10
9
8
7
6
5
4

José Argüelles, Ph.D.

Author of *The Mayan Factor*

MAYAN STUDIES/NEW CONSCIOUSNESS $20.00

"Time and the Technosphere *makes a vital contribution to the great paradigm shift in human cultures that is now accelerating. There is a higher dimension of natural time inscribed in the cosmos and a natural calendar that would help humanity mature into the awakening global consciousness that is now essential for future sustainability and well-being. This book is an important contribution to the awakening event that is now emerging on a planetary scale.*"

ASHOK GANGADEAN, PH.D., Professor of Philosophy, Haverford College

In *Time and the Technosphere,* José Argüelles presents a groundbreaking study that distinguishes the natural time of the cosmos from the artificial mechanistic time under which we currently live. Argüelles defines the actual nature of time as the frequency of sychronization. Applying this Law of Time to an understanding of the entire system of life on Earth, he shows that in order to not destroy Earth's ability to sustain life, we must change our definition of time and adopt a natural harmonic calendar based on the 13-moon 28-day cycle. Until the creation of the Gregorian calendar and the 60-minute hour, most of humanity lived by the 28-day cycle of natural time. The adoption of artificial time has subjected us to a 12:60 time frequency that governs the entire global industrialized civilization—the technosphere. With the collapse of the Twin Towers on September 11, a fissure was created in this artificial technosphere, opening up the noosphere (Earth's mental envelope).

Humanity has a golden opportunity to leave the strife of the past and enter a time of peace by adopting a harmonious natural calendar that will repair the damages caused by the irregular tempo of technospheric time. Our last best chance to adopt this natural time and step into the bright new future promised by the galactic shift of 2012 is the Great Calendar Change of 2004, a new discovery based on the author's mathematical research into the Mayan calendar first begun in his landmark work *The Mayan Factor.* In *Time and the Technosphere,* Argüelles reveals the clear distinction between third-dimensional astronomical time and the fourth-dimensional synchronic order of the Law of Time, which holds enormous potential for the future of humanity.

PHOTO BY BORIS VLADIMIROVICH

JOSÉ ARGÜELLES, PH.D., works full time on behalf of the World Thirteen Moon Calendar Change Peace Movement and is president of the Foundation for the Law of Time. He is the author of numerous works, including *The Mayan Factor, Earth Ascending,* and *Surfers of the Zuvuya.* He lives in Oregon.

BEAR & COMPANY
ROCHESTER, VERMONT

ISBN 187918199-1

9 781879 181991

Cover design by Peri Champine
Cover illustration by José Argüelles



Time and the Technosphere

The Law of Time in Human Affairs

JOSÉ ARGÜELLES

Bear & Company
Rochester, Vermont

Bear & Company
One Park Street
Rochester, Vermont 05767
www.InnerTraditions.com

Bear & Company is a division of Inner Traditions International

Copyright @ 2002 by Jose ArgUelles

All rights reserved. No part of this book may be reproduced or utilized in any form or by any means, electronic or mechanical, including photocopying, recording, or by any information storage and retrieval system, without permission in writing from the publisher.

Library of Congress Cataloging-in-Publication Data

ArgUelles, Jose, 1939-
Time and the technosphere : the law of time in human affairs / Jose ArgUelles.
p.cm.
Includes bibliographical references.
ISBN 1-879181-99-1
1. Calendar reform-Miscellanea. 2. Social evolution-Miscellanea.
3. Maya chronology-Miscellanea. I. Title.
BF1999 .A6398 2002
001.94-dc21
2002006082

Printed and bound in the United States at Capital City Press

10987654321

This book was typeset in Janson, with Eurostile as a display typeface

Time and the Technosphere

This book requires some attention from You. It is a complete, coherent, story for Humanity, on Earth, in the Universe. It is a radically different story than what is commonly disseminated by and through our global, dominating, culture. There is no need for You to *believe* this story, or any other. Trust yourself. trust your Self To say you must go into this with an open Mind, is a grand understatement. Start with trust. Simply allow the thoughts and concepts you read to "stew" for awhile. Make some headspace for them and have patience for what may grow there. It is a beautiful life...

Notes on the electronic PDF version

- There are errors! Nothing major...only superficial...
- Note the color plates (mentioned thorughout text) are the last eight pages.
- The page numbers Are the page numbers.
- Use Acrobat's bookmarks for navigation!

Arguelles, Jose - Time & The Technosphere v0.2.pdf

The Law of Time in Human Affairs


Solstice
Zenith
High Noon
Third Watch -
Antipode
Second Watch -
Guide
Twilight
Equinox
Equinox
Dawn
Stable -
Stable +
Dynamic +
Dynamic -
Fourth Watch -
Occult
First Watch -
Analog
Midnight
Nadir
Solstice
T(E)=Art
JANUARY
FEBRUARY
MARCH
APRIL
MAY
JUNE
JULY
AUGUST
SEPTEMBER
OCTOBER
NOVEMBER
DECEMBER
2001
1973
1945
2002
1974
1946
2003
1975
1947
2004
1976
1948
1977
1949
1978
1950
1979
1951
1980
1952
1981
1953
1982
1954
1983
1955
1984
1956
1985
1957
1986
1958
1987
1959
1988
1960
1989
1961
1990
1962
1991
1963
1992
1964
1993
1965
1994
1966
1995
1967
1996
1968
1997
1969
1998
1970
1999
1971
2000
1972
12
1
2
3
4
5
6
7
8
9
10
11

This book is dedicated to Adam J. Lewis—at work on the eighty-eighth floor of the South Tower when his mother called him from Spain as she watched television reports of the first hit on the North Tower—and to all the others who were sacrificed on that day. May the truth prevail, that the greater mystery might be made known—forever.

Contents

Acknowledgments ix

Preface xi
A Brief Literary Autobiography

1 9-11, The Inevitable Event and the Nature of Time: Introductory Reflections 1

2 Preliminary Definitions: Biosphere- Technosphere-Noosphere as an Evolutionary Continuum 18

3 Time and Human Consciousness: The Law of Time-What It Is and Where It Came From 35

4 The Law of Time in Human Affairs: The Analysis of History 54

5 The Climax of History, the Fifty-six Years of Hiroshima-Artificial Time Runs Out 76

6 The Solution of the Law of Time: Get a New Calendar 99

7 Humans-Noospheric Chips: Consciousness and Reality Redefined 121

8 Making the Transition to the New Time: A How-to Catalog and Guide to the *Pax Cultura, Pax Biospherica* 145

9 The Advent of the Noosphere: A Prayer and a Vision 176

Epilogue 197
Networking the New Time

Appendices

I Summary Critique of the Gregorian Calendar with Which Every Proponent of the Thirteen Moon Calendar Should Be Thoroughly Familiar 200

II The World Thirteen Moon Calendar Change Peace Movement and the Discovery of the Law of Time: A Brief Chronotopology of Transformation 207

III Telektonon Prophecy of Pacal Votan 212

IV The Nineteen Code 229

Notes 240

Glossary 245

Bibliography 254

Acknowledgments

AS ANY AUTHOR knows, to write a book and see it through to completion, from initial inspiration to final conclusion, is never an easy task. Though we are all guided, if we so choose, by the Supreme Creator, still it is one's Earthly helpers that must be counted first, even before oneself-for without their aid, where would one be?

First and foremost of my Earthly helpers whom I wish to acknowledge is my wife and faithful companion of twenty-one years, Lloydine Bolon Ik, my constant helper and chief inspiration of all I do. The faith and trust she put in me at times when all we had was blind faith are a touching memorial to a soul who has always believed that love is the greatest truth.

Assisting us greatly during the time since we arrived in Oregon and have continued to dedicate our lives to the fulfillment of the prophecy of Pacal Votan and the Great Calendar Change is our devoted helper and assistant Stephanie South, the Red Queen, Red Electric Serpent, who conscientiously read and edited this text in its final form, helped in numerous details, and so kept me from ever bogging down.

Of equal trust and value is that one from the immemorial rainbow to whom I owe so much, Kin 19, David Rinck, "the stalwart," whose enhancements of my artwork are ingenious and awesome. All three of these people share one thing in common: absolute belief in and dedication to the Law of Time as a living reality that gives breath to all we do.

I must also thank the incomparable Spectral Skywalker, Mark Comings, whose mind has been of inestimable value to me through our many memorable background discussions on time in modern physics in relation to the Law of Time. In this regard, I would also like to mention Irina Eganova of the Sobolev Institute of Mathematics of the Siberian Branch of the Russian Academy of Sciences, Novosibirsk, for her rigorous approach to N. A. Kozyrev-may she smile well when she reads this book.

For their unconditional support I would also like to honor and thank Brian and Deborah Haight of the Foundation for the Law of Time, and all the many friends and beloved kin of the Planet Art Network everywhere, but especially to the Russian kin who so ably understood the Law of Time and opened up gold mines of knowledge and friendship in the Russian Academy of Sciences in Novosibirsk, as well as the great pristine valleys of Altai, where the shamans await the next installment of *The Mayan Factor.*

Spirituality is at the core of the biosphere-noosphere transition, and in this regard the beings I have to thank are without number, yet some especially stand out and deserve mention: my Tibetan teacher, the Sakyong Dorje Dradul Chogyam Trungpa Rinpoche, through whose cremation he entrusted me with all; my son, Josh, who opened the doors of the fourth dimension for me so that I would never be satisfied with less; and Mother Tynetta Muhammad, who showed me the way of the Holy Quran with the guidance of the mystic master FM, and who introduced me to the great work of Dr. Rashad Khalifa, whose breaking of the Quranic nineteen code led to his martyrdom, leaving me to fulfill what he revealed.

The creation of a book, the coming into manifestation of an artistic conception, is a complex process involving numerous other eyes and minds in order to bring the effort into its final published form. In this process two people have stood out deserving of mention. First of all, there is Michael Moynihan, White Galactic WIzard, who very patiently and carefully copyedited the book-always with an eye on maintaining and enhancing the original artistic vision-and who stood by the integrity of its vision through the entire editorial process. His work was complemented by the efforts of project editor Lee Awbrey, Blue Lunar Eagle, who took on an increasingly engaging role and personality as we brought this book to its final stages. I am especially appreciative for her inspiration to rework the Preface and Chapter One, which I gladly did, and which I feel speak more immediately to the reader of this book. Thank you both, and may the success of this book redound to your consummate care for the truth.

Finally I would like to honor and thank my children: Tara, the golden one, my grandson, SamuelJoshua Sheps, andJeff of Engine Company Number Nine in Phoenix; also Paul Mecklenburg, who has always held the faith in our work, and Heidi Mecklenburg, that her dream of the Unicorn Princess may become true once again.

▼



Preface

A Brief Literary Autobiography

Time and the Technosphere: The Law of Time in Human Affairs is essentially a prolonged set of meditations occasioned by the one most powerful and overwhelming event of our time, the 9-11, the Inevitable Event of September 11,2001. Subsequent events may overshadow this one in horror and magnitude, but it was this event in particular, the destruction of the World Trade Center towers, that sent a signal that something very profound had occurred to change the way we think of ourselves and our future.

In presenting these meditations and reflections in the form of a book, I am painfully aware of the limitations of this medium in the information age. Keeping in mind that the volume of information has increased five times in the past century-with much of that increase occurring only in the past decade-I am very reluctant to put anything down to be published in the form of a book. I was raised well on the writings of Marshall McLuhan and his definitions of media and how they affect our senses. It is altogether obvious that a book in your hand is not the same as reading a text on a computer screen. A book is actually something made to last. Of course, the computer has made it possible and easy for virtually anybody and everybody to write a book, and so we encounter one of the great hazards of the information age: the decline in discrimination and the criteria of excellence. Who can now tell what is worth reading or not? These reflections, too, are very much to the point of the grand theme of this text. If a book is meant to last, how long will this book last? It should last until the New Time has established a new order of reality on this now anguished Earth. Whether or not destruction and the total collapse of civilization will occur first, we do not really know. That is a matter left to the Divine Mind of God alone.

Nonetheless, it is with faith that we continue on this Earth at this time. A pressing voice told me to go ahead and to write this book, regardless-but then, this is how I have always done it. Those who are at all familiar with any of my earlier books, will find that *Time and the Technosphere* is but a continuation of themes that have provoked me since I first considered literature as a medium of communication. It is important to know where the author is coming from, and how he got to this particular point of reflection. In this regard, *Time and the Technosphere* is the organic result of a lifelong pursuit of a study of the nature of art, time, and history. This study has been woven together by a dialectical process that defines the evolving nature of consciousness. So, for those who are interested, herewith follows a brief literary autobiography, the better to understand my point of view.

My earliest book, *Charles Henry and the Formation of a PsychophysicalAesthetic (1972),* states the grand theme of a holistic science that unifies body and mind, sense and nature, the harmonic pursuit of which has been at the root of all my endeavors. This pursuit was amply demonstrated in my second book, *Mandala* (1972), which, as a root text of the counterculture, was an artistic, philosophical, and cosmic plea for a harmonic resolution to the process of history. It is a sign of the times that *Mandala* is no longer in print, but instead a book bearing the same title, but which does not even include the original Mandala in its bibliography, is in print with the same publisher. Amnesia is one of the side-effects resulting from information overflow with no discrimination. Unfortunately, cultural amnesia is always accompanied by an increase in trivialization, and thus we arrive at the mediocrity and sensationalism of the present moment.

My next book, *The Transformative Vision: Reflections on the Nature and History of Human Expression* (1975, 1991), took the aesthetic and unitive themes of the first two books to the next stage of my visionary analytical process, elaborating on the meaning of time, history, and cosmos. In rereading the later chapters of *The Transformative Vision,* I am struck by their prophetic accuracy, as well as their sense of impending tragedy. It is hard to believe that only 26 years have gone by since that book was first published and now we are plunged into the maelstrom of what was then thought to be the worst scenario possible. *The Transformative Vision* also defined human consciousness as the cerebral-neurological dialectic of psyche (aboriginal, primal intuitive art) and techne (civilizational, rational science), emphasizing that only in their absolute synthesis would there be a harmonic resolution to the problem of history. Seen in this light, the technosphere represents the extreme, one-sided triumph of techne, while terrorism is the expression of the absolute repression of psyche. The crucial question then arises: how will we ever attain a balance or harmony?

Investigation of the ongoing dialectic of consciousness was continued in my next effort, the philosophically synthesizing work entitled *The Feminine, Spacious as the*

Sky (1977), which was written and artistically produced with my previous partner and wife, Miriam Tarcov, who also co-authored *Mandala* with me. The feminine aspect represents a deepening reflection of the psychic, intuitive side of human nature. Expressed through a whole range of images, symbols, and philosophies that describe both the aboriginal root and the final flowering of human consciousness, it is this feminine aspect that has been smothered by the historical process, resulting in the technosphere. Why and how did this occur? These questions drove me to the next stages of my visionary investigations.

From the beginning of my pursuits I have been moved by my intuitive awareness of our intrinsic wholeness as humans, and the knowledge that this wholeness is a reflection of the wholeness of Earth, the solar system, and the cosmos itself. Although this perception of reality is nowhere within the domain of the shibboleths of Western scientific thought as it has developed since Descartes, I have also come to understand that Western scientific thought is highly provincial, racially biased, and-because it is not informed by a perception of wholeness-incapable of solving the actual problems of life. In fact, Western scientific thought has been one of the key factors leading the human race onward to its great act of self-destruction-a self-destruction employed through the instrument of technology.

In my next book *Earth Ascending: An Illustrated Treatise on the Law Governing Whole Systems* (1984, 1988, 1996), I was able to make a profoundly radical break with the restraints of the Western scientific and academic modes of thought. Combining the artistic and aesthetic qualities of *Mandala* and *The Feminine, Spacious as the Sky* with the philosophical and scientific concerns of *The Psychophysical Aesthetic* and *The Transformative Vision,* I define and describe the human situation as a function of the geology, or biogeology, of Earth understood as a whole system. Without knowing it, I had defined the human presence in Earth's geology in a way very similar to that of the Russian biospheric scientist V. I. Vernadsky in his analysis of the biosphere. Culture, civilization, and even technology are seen as features and functions of the larger evolving biogeological process of the whole system Earth, while time and consciousness are defined as functions of a larger planetary regulating system called the psi bank. In the analysis of *Earth Ascending,* the feminine psychic side of consciousness is referred to as the AC, Aboriginal Continuity, while the male, rational techne side is defined as the CA, Civilizational Advance. The historical process represents the increasing dominance of the CA to the final exclusion of the AC-the triumph of industrial man over the indigenous peoples.

The most critical moment in history was the atomic destruction of Hiroshima, August 6, 1945, when through its technology the impact of human thought permanently affected the geological makeup of the Earth. The events before Hiroshima are chronologically defined as P.A., pre-atomic, and those after as A.H., After Hiroshima. But more than defining the process of history within the context of Earth's cosmogeology, *Earth Ascending* also describes the post-historic future as a condition of harmonic synaesthesia-harmony of the senses-defined by a new scientific system called radiosonics. The key to this new system of scientific endeavor is synchronicity or synchronization of our mind and senses in time. The problem left open by *Earth Ascending* was the precise nature of time and the timing of the radical break in the historic continuum, now known as the Inevitable Event-the culmination and dramatic conclusion of a process begun at Hiroshima. After the Inevitable Event we are liberated into post-history and the possibility of the radiosonic science of the future.

In *The Mayan Factor: Path Beyond Technology* (1987), I was able to supply the basic ingredients for an understanding of time and the timing of the radiosonic future. Going beyond the parochial limitations of Western science and the self-inflated progressivist thinking of the Western mind in general (that states "anything that advances technology is an absolute advance over anything that was thought of or occurred in the past") I was able to finally bring to light the synthesis of many years of study of the time science of the ancient Maya. Here, in the mathematical calculations of the Maya with their unique vigesimal mathematics-counting by twenty and not by decimal ten-lay the basis of a vast and grand science of time. So grand is this science that its conceptions of time dwarf anything the Western imagination could conceive.

While the Western concept of time is linear and predicates an unceasing ascent into a progressively technological and mechanistic future, Mayan time science is predicated on the knowledge of time as the universal factor of synchronization. The Western conception of time is not in accord with the actual cyclical and synchronistic nature of time, and so the whole apparatus of Western civilization is doomed to reach its own breaking point: the Inevitable Event. Mayan time science posits a precise measure of the historical cycle, the most recent and climactic stage of Earth's evolution, as a time fractal of thirteen baktun cycles, each 144,000 days in length, spanning the JulianiGregorian years 3113 B.C.-A.D. 2012. According to Mayan time science, the efforts based on an erroneous time conceptualization are bound to fail prior to the cyclic end-point of 2012. Thus, the Inevitable Event is also a consequence of the failure to understand or to even acknowledge the actual nature of time due to a totally false and mechanistic timing sensibility. In this lies the cause of the apocalypse of Western thought and theology.

The problem left unresolved by *The Mayan Factor* was the precise methodology for changing tracks, for switching Western dominated global civilization away from the track of an erroneous, mechanistic time-based technology and toward the natural order of time-the path beyond technology. Here my efforts took me to a point beyond reason. Why or how? Let me explain. As an exposition of Mayan time science, in preparation for the 2012 ending of the thirteen baktun cycle of history, *The Mayan Factor* is predicated on the occurrence of a real time event, the Harmonic Convergence "global peace meditation" of August 16-17, 1987. The timing of the Harmonic Convergence was prophetic. It augured the fulfillment of the prophecy of Quetzalcoatl (947-999) known as the Thirteen Heavens and Nine Hells. The Harmonic Convergence completed the ninth and last Hell cycle, and ushered in the final twenty-five years of the thirteen baktun cycle. The Harmonic Convergence was a Mayan wake-up call answered by millions of earthlings.

Exactly forty-two years and ten days after Hiroshima, and fourteen years and twenty-six days before the Inevitable Event, the Harmonic Convergence was located by time to occur precisely when it did. Prophecy transcends reason because it is totally of time, which is of the fourth dimension; prophecy nevertheless affirms with unerring logic that which has been, and that which will be brought about, as being of the same karmic cause and effect stream.

It was this matter of prophecy in the aftermath of *The Mayan Factor* that brought my literary efforts and my own life journey to another stage of development. Prophecy comes with a mantle-if not, then you are classified as a madman. The prophecy of the Harmonic Convergence, as well as of the entire text of *The Mayan Factor,* bore the mantle of the prophetic stream of the Chilam Balam, the jaguar priests, the wizard knowers of the "night script." By correctly fulfilling the prophecy of the Thirteen Heaven and Nine Hell cycles, 843-1987, and by writing and putting together the mathematical codes of *The Mayan Factor,* and before it, of *Earth Ascending,* **I,** Jose Argiielles, had assumed the mantle of the prophetic tradition of the Chilam Balam. Mind you, this was nothing overt nor the least bit conscious, for little did I then know that my next life task was to decode the essence of the Chilam Balam prophecies and to define the time science of which these prophecies are a manifestation.!

The Harmonic Convergence affirmed the karmic repercussions of Hiroshima by bringing forward the ancient Mayan prophetic tradition of the Chilam Balam. By precisely locating this prophetic tradition in a contemporary moment -a media event, no less-the unlocking of its final prophecies was triggered for the purpose of completing the cycle of history: 2012 and beyond.

Like any major media event, the Harmonic Convergence was an enactment within the noospheric unconscious of humanity-the telepathic whole that resides in Earth's mental envelope. So it was that on June 23, 1987, the *Wall Street Journal* ran the front page story on the Harmonic Convergence. Yet due to the mental obscuration accompanying the final stage of global industrialization, the Harmonic Convergence was an event that the *WillI Street Journal* and the rest of American media conveniently forgot when it came to their review of the century in the year 2000. Today, just weeks after the Inevitable Event, the collapse of the World Trade Center towers, the words of that article are most prophetic: "Mr. Argiielles says the choice between a 'new age' and all-out destruction is ours, and we had better decide."2 Though the prophecy was discounted, true to form, the words of the messenger remain to haunt those who spurned the message.

The prophets and sages of the Maya, and of the New World in general, are a complement to those of the Old World, a further manifestation of the planetary dialectic of poles and hemispheres. If the judgment day apocalypse is the focus of the Old World prophecies, especially those ofIslam and Christianity, those of the New World similarly pinpoint an end time whose denouement is chronicled as the date 2012. It was the prophecies of the sage and culture hero, Quetzalcoatl (947-999), that brought about the Harmonic Convergence, while it was the wisdom of Pacal Votan (603-683) that informed the actual text and scientific time mappings of *The Mayan Factor*, and the image of his tomb adorns the cover of the original book. In a similar manner, it was the tradition of the Chilam Balam that created the prophetic vision of the synchronic order to be realized as the Law of Time.

I was hardly aware of the personally transformative factors at work within me after the Harmonic Convergence media swell began to subside, when two events occurred that augured a major change in my perceptions, activities, and literary output: the Wall Street stock market crash of October 19, 1987, and the death of my eighteen-year-old son,]osh, ten days later, on October 29,1987. In analyzing why the 1987 stockmarket crash happened, the lead story in *USA Today* about this event concluded by posing the question: Was it the Harmonic Convergence that somehow caused the stock market to crash? As I pondered why the answer to this question must be in the affirmative, as well as the implications of this analysis-remembering full well that the breaking story on the Harmonic Convergence first appeared in the *TVtlllStreet Journal-news* came of my son's sudden death in an automobile accident.

Synchronically, the stock market crash and my son's death were part of one event continuum. As tragic as the circumstances of his death were, my son had liberated me from any further compunction to lead a normal life, and to pursue, instead, this matter of Mayan time science and its calendars of harmony. In homage to my son, I completed what I first thought would be a popularization of *The Mayan Factor*, a book entitled *Suifers of the Zuvuya* (1988). Instead of being a popularization or even a sequel to *The Mayan Factor*, Surfers turned out to be a series of autobiographical tales of interdimensional travel-zuvuya surfing in the fourth dimension. This "flight of fantasy," was my literary farewell to the limitations of reason and a life of comfort. Inner destiny pushed me to the next stage in my pursuit of the unitive science-the discovery of the Law of Time.

This journey of discovery, the findings of which are the underpinnings of the present work *Time and the Technosphere*, took me and my wife and partner, Lloydine, to physical and mental places that were far from anything we had once deemed conventional. Because of this, I had ample opportunity to write and to create, and I did so, freely and without any restraints. I no longer sought any conventional means to communicate. I was now operating prophetically, on behalf of the noosphere-Earth's mental envelope.

There is a consistency to the stream of prophetic revelation, summarized as the codes of the Law of Time. This revelatory stream begins with *Earth Ascending* and *The Mayan Factor*, comes to flower with *The Dreamspell: Journey of Times hip Earth 2013* (with Lloydine Arguelles, 1991), and is completed by all aspects of the Telektonon Prophecy, including the Thirteen Moon/28-Day calendar (1993-2000). This prophetic stream is emphatically a galactic revelation of the same base of know 1-edge that produced the Mayan civilization of ancient Mesoamerica. The new revelatory stream is known as the Wizard's Count, or "reformulated Chilam Balam." It was this prophetic stream and its year-bearer count that established the validity of a fifty-two year cycle correlated to the Gregorian July 26.

The purpose of the Chilam Balam year-bearer count was to establish a basis for understanding that there exists a synchronic order of time, completely apart from what is usually referred to as the Long Count, the linear count of days of the thirteen baktuns of the cycle of history, 3113 B.C.-A.D. 2012. After a long break in the tradition of the Chilam Balam, the year-bearer count was prophetically reformulated to prepare for the Harmonic Convergence and the subsequent revelation of the Telektonon prophecy of Pacal Votan. As the new Wizard's Count, this count was intuitively recalibrated precisely so that July 26, 1987, would be White Galactic Wizard; July 26. According to *The Mayan Factor*, July 26, 1987: White Galactic Wizard, marks the first of the twenty-six years of the Harmonic Convergence. This date marks the conscious ascendance of the prophecy of galactic culture and the coming of the Earth Wizards-the race of galactic wizards on Earth.

In 1988, the year following the Harmonic Convergence, in attempting to create an everyday "Mayan calendar," I came upon the next stage of the discovery of the synchronic order. On the Gregorian calendar, 1988 is a leap year. I perceived that to accommodate February 29 would throw the year-bearer count off by one day, ruining the harmony of the system. Reviewing the Chilam Balam texts, it was clear that leap year was never considered, much less counted in the year-bearer count. Without an intercalary leap year date, the four year-bearers-Seed, Moon, Wizard, and Storm-coded by the numbers 1-13, remained in sequence, maintaining and assuring the harmony of the system, where every fifty-two years equals seventy-three 260-day spins, no two days are the same, and the entire 18,980 days of the cycle repeat every fifty-two years in an upward moving spiral of time. For the first time in my work, the issue of the Gregorian calendar as a system came into question.

Following this observation came the discovery of the mathematical codes governing the synchronization of the 260-day cycle with the 365-day cycle, the consequent discovery of the artificial 12:60 and the natural 13:20 timing frequencies, the recognition and resurrection of the Thirteen Moon/28-Day calendar, and the full exposition of the Dreamspell codes of fourth-dimensional time. I presented these discoveries in *Dreamspell: Journey of Timeship Earth 2013.* The Dreamspell, being the manifestation of the knowledge base of galactic culture, completely encodes the Wizard's Count. *Dreamspell: Journey of Timeship Earth 2013,* the presentation of the codes of fourth-dimensional time as a "tool kit" with an accompanying "script" and guidebook, is a break of such radical form from the prevailing paradigm that, as of today, it is still unfathomable to many people.

The galactic Dreamspell tool kit is a primary tool for the galactic culture that is just now beginning to unfold in the wake and shadow of the collapse of the Twin World Trade Center towers. This text prompted me to write two more books. The first, *Arcturus Probe: Tales and Reports of an Ongoing Investigation* (1992, 1996), is a deep reverie that picks up where *Suifers of the Zuvuya* left off and documents the interstellar, interplanetary psycho-cosmological roots of the Dreamspell of fourth-dimensional time. The second book was written as *A Treatise on Time Viewed from its Own Dimension,* but first published in English as the *Call ofPacal Votan: Time is the Fourth Dimension* (1992, 1996). In this highly scientific, mathematical treatise I was able to accommodate the Dreamspell codes of the Law of Time to an analysis of the biosphere and the biosphere-noosphere transition. This work also represents my first integration of the actual thought and principles of V. I. Vernadsky.

Through the efforts that constituted the discovery of the Law of Time, much of which was assisted by my partner and wife, Lloydine, I was finally able to begin to understand the methodology for accomplishing the paradigm shift-or psychic pole shift-of which humanity was so in need, at least from the perspective of the biosphere. By providing the mathematical basis for establishing the "biomass constant," Seventy-three 5 day subcycles correlated to the measure of the solar year, I had found a way of grounding the fourth-dimensional mental order of time, the synchronic order, in the actual third-dimensional biogeochemical cycles of the biosphere. This was like casting a harpoon of time from the noosphere and landing it in a precisely measured form in the annual turning of Earth's biospheric mantle. And this was accomplished precisely because of the intrinsic harmonic cycles and patterns of the DreamspelllWizard's Count.

For this reason, by 1993, it was incumbent upon me to test the hypothesis of the Law of Time that the human race was destroying its biosphere due to operating according to an error in time, and that only a shift in its experience of and perception of time would save it from such destruction. This shift in time is defined as the calendar change. The Law of Time presents such a radical critique of Western science, of its concepts of time, and of the civilization which it supports, that I could not tackle the problem from its center, but from its periphery, moving inward to the point of the Inevitable Event. Beginning in Latin America, then spreading to Japan, Western Europe, Russia, and finally North America, we established a movement to change the everyday perception of time, instilling profound meaning behind the effort to reform the calendar. In this way, we took on the responsibility of organizing the World Thirteen Moon Calendar Change Peace Movement.

Part and parcel of this, beginning in 1993, was the decoding of the prophecy of Pacal Votan, the inspiration of *The Mayan Factor.* Known as the Telektonon, Earth Spirit Speaking Tube, this prophecy is the full realization of the Law of Time and the synchronic order. As much science as it is prophecy, the Telektonon defines the Tower of Babel as the root of the error in time, and the Inevitable Event as the necessary result of not relinquishing false time. At the same time, the Telektonon provides codes and tools of analysis which are in complete accord with an understanding of the technosphere-noosphere as an evolutionary continuum in which the Inevitable Event is an act of moral consequence and natural law revealing the basis of a new cycle of harmonic order.

I would also be remiss at this point if! did not inform the reader that, by prophecy's prerogative, this text is also literally punctuated by a perspective that can only be described as "Quranic." Late in 1993, my immersion in the prophecy ofPacal Votan became sychronically linked to my immersion in a study of the Quran, or Holy Quran as it is sometimes called. I have taken seriously the claim that the Quran is the final revealed text (A.D. 610-632) for humanity. I have studied it following the dictum: "Quran, the whole Quran, and nothing but the Quran,"3 as the basis of genuine Islam-submission to the will of God. I have found it more than sufficiently true that the Quran is a scientific text, and contains nothing that contradicts science. More profoundly, my study has given rise to my own personal ethic: duty to God is the highest cause. It is the cultivation of this attitude, combined with many years of practice of Buddhist meditation, that have brought me to my present point of view, which is visionary and spiritual throughout-and, as a result, has endowed me with my own view on the current global dialectic.

That the new, and final, global dialectic is found in the tension between the forces of globalization (materialism) on the one hand, and that of the civilization of Islam (spirituality) on the other, is now a well-documented fact.4 Of course, generally speaking, in the West, we see it only from the materialist side of the dialectic. The perspective which informs me, and consequently this book, is definitely from the other side of the dialectic. Though in no way condoning terrorism- I am a nonviolent pacifist by persuasion-the motives of the terrorists stem from a philosophy and worldview with which I am in sympathy. Yes, the Inevitable Event was also a profound theological moment, and what we are witnessing in the present World War is the battle between the religion of choice and the religion of submission. We cannot necessarily assume that the religion of choice will prevail. In fact, from the perspective of the biosphere-noosphere transition, it is the religion of submission that is most in accord with the spiritually-beckoning future.

As a preface to this book, I have found it mandatory to write this brief literary autobiography, often couched in a terminology that jumps ahead of the story, solely to demonstrate that the actualization of the noosphere corresponds to the stages of attainment and transcendence of one human's life journey in pursuit of the truth. Only in this way could I cultivate the noospheric perspective, voice, and point of view that was necessary for the writing of this text. In this perspective, the noosphere is a condition of non-anthropocentric consciousness. My journey, thus documented, is merely one way the noosphere has found to become conscious, asserting the Law of Time's purposive axiom: to make conscious what had been unconscious. The voice and method of the noospheric perspective are inseparable from the topic of this book, *Time and the Technosphere.* By analyzing the timing and structure of the technosphere, the noospheric point of view becomes conscious. WIthout understanding the nature and relation of time and the technosphere, there would be no truly sane way to comprehend the meaning of the Inevitable Event.

Crystal Moon Kali 11,
Kin 2: White Lunar WInd
Yellow Solar Seed year
Cascadia, North America

1

9-11, The Inevitable Event, and the Nature of Time

Introductory Reflections

Woe! Woe, O great city,
O Babylon, city of power!
In one hour your doom has come!
Woe! Woe O great city, dressed in fine linen
purple, and scarlet...
In one hour such great wealth has been brought to
ruin ...
"Woe! Woe, O great city,
Where all who had ships on the sea became rich
through her wealth,
In one hour she has been brought to ruin! ...
With such violence the great city of Babylon will be
thrown down!"
ST.JOHN OF PATMOS, BOOK OF REVELATIONS,
CHAPTER 18, *THE FALL OF BABYLON*

9-11. The Twin Towers of the World Trade Center gone in a veritable twinkle of the eye. Tragedy. Horror. Terrorism. The whole world brought to a halt. The aftermath? Patriotism, war, and an all-pervading uneasy feeling. What happened? What really happened? Was this the beginning of the Apocalypse?

Amidst the distraction of chasing after other people with smart bombs in faraway places like Afghanistan, and making everyone at the airports feel like potential terrorists, there are no answers forthcoming for what really happened. There is a good reason for that, too: The destruction of the Twin Towers of the World Trade Center and the attack on the Pentagon marked a point beyond the comprehension of the current belief system in every way. To say that the event was mind-blowing is an understatement. But if it was mind-blowing-which it truly was-that means that a whole belief system was knocked off of its foundations, and only a new belief system can supply the answer. A higher, more all-encompassing belief system-a new paradigm-is what is needed if we are to really understand what happened on 9-11.

Belief systems, believe it or not, are functions of time. What you believe defines the time you are living in. Any belief system is held in place by the calendar and sense of time in which it is encoded. 9-11 means September II-it also means 911 emergency, planetary emergency in this case. "9-11 we will never forget" was a common slogan appearing on bumper stickers and store windows after the event. The words or concepts "Tuesday, September 11," "9-11" and even "911" are all functions of the same belief system. So is "2001," the first year of the highly touted "third millennium." But the third millennium of what? The third millennium since the birth of Christ. This means that the belief system whose mind was blown was the Christian millennial belief system encoded in the Christian calendar, the Gregorian as it is properly called. Does this mean that the foundations of 2000 years of belief were blown away, shattered with the terrifying collapse of those Twin Towers? Easily that many years, maybe as many as 5,000 years, or perhaps even the entire history of civilization as we know it came unhinged that fateful day, the day of the 9-11, the day of the *Inevitable Event,* to borrow a phrase from the Holy Quran, the day the Apocalypse announced itself, showed up on the morning television, quite without warning. (See plate 1, The Invevitable Event and the End of History.)

In meditating upon the meaning of the Inevitable Event, it is natural to ask: What made this event so inevitable? It is not just from the perspective of American Foreign Policy, or that of its economic free market monetary politics, that this event was inevitable. More profoundly, this event was so inevitable because it seemed to smack of some form of retribution for the breaking of fundamental laws of nature, or even of Divine Law. And isn't the retribution for transgressing Divine Law a form of apocalypse, a standing naked, a revelation, an evocation of the fall of the Tower of Babel, no less?

Yes, that is why it was so shocking-it was the Inevitable Event because the apocalypse is as inevitable as it is without warning. But apocalypse- a word no one wanted to use to describe the event, because to use it would be to admit that it was all over-is only one side of the coin. There is another side to the coin of the Inevitable Event-and that is what this book is about. There is something beyond the Apocalypse, there is something larger going on, and that also scares people. Things are out of their control. Isn't this why, instead of looking at it, or contemplating the event, a policy of war was immediately instated as a principle of revenge-for what and against whom? What is going on is time-time is always going on, or time is always coming together. Or time is always changing. The apocalypse, too, is about time-the end of time-which is even more frightening to most people. But the end of whose time? The new paradigm we need to explain 9-11 should be a paradigm that is all about time.

I who speak know, because I have spent most of my life studying time, and the effects of human time which you call history. For many years now I have been living an experiment in time, but a time most of you do not know. So I have some answers that will put 9-11 in perspective for you. I am the stranger from the other side of the wall of mechanized time. I have come back to make you familiar with the time your clock and your calendar shield you from. Because I know about the other time, the larger time, the cosmic time that governs the cycles of all that exists, I can tell you that 9-11 was the Inevitable Event. It had to happen precisely when it did, not because nineteen terrorists planned it that way, but because the terrorists themselves were unconsciously programmed by the timing of Earth itself. Earth's timing process represents evolutionary forces as well as effects irreversibly set in motion by the human's own unconscious programs, programs governed by the human misperception of time and of its role in the cosmic order.

Yes, Earth has its program of which our human history and all of its endeavors are only a part. This larger meta-program of Earth is called the biosphere, the scientific designation given to what is commonly and inadequately referred to as "the environment." As such, the biosphere is a whole system composite of the sum of life and its organic and inorganic support systems spread out over the surface of Earth, hence bio = "life" + sphere = "having the form of a globe." In a word the biosphere is a vast but fragile process which has been evolving itself for some two billion years on this little planet as it spins around its local star, the sun. But we humans, who only in 1969 first saw ourselves as a planetary being-the whole Earth beamed back at us via television by a rocket hurtling toward the moon-we humans have been generally so self-involved in our own interpretation of things that we have missed seeing the larger picture of which we are a part. This larger picture is the entirety of the biosphere which encompasses the evolution of life on Earth as a whole system process. The amazing thing is that most of us have never even heard of the biosphere much less even know that we are a part of this whole system governed by laws and principles which we, in our self-made arrogance and ignorance, have but little understood.

From my experiment in time, seeing and studying the human as part of the larger self-evolving fabric of the biosphere, I came to the conclusion that the human is living in a time apart from the rest of the biosphere-an artificial time whose climax and termination is inevitable, for nothing artificial can withstand the force of truth. If the human is living in artificial time, the clock is an artifact whose system of measure has nothing to do with natural cycles but is a totally abstract standard, then there must be something called natural time. I will go even farther and state that not only is there natural time, but that there is a law governing natural time, and that is the Law of Time. Just as Newton only discovered gravity some 300 years ago, though gravity has always existed, so the Law of Time has always been in operation, even though it was just recently discovered. It is the Law of Time that governs the entirety of the biosphere and everything else in the universe according to principles which are only dimly known to us, principles like synchronicity and telepathic instantaneity. Yes, to understand what really happened on 9-11 you have to understand the Law of Time and how it governs the biosphere-of which our rampant human civilization is inescapably a part.

The Law of Time is formulated very simply, and in some people's way of thinking, rather unscientifically as T(E) = Art, "energy factored by time equals phenomena in the material world represent some state of energy, and every state of energy is governed by time, the resultant product of which is always something beautiful or elegant. Have you ever seen an ugly sunset? A hideous flower? Even if you examine a scorpion with some objectivity you will be amazed at the flawless and elegant manner in which its parts are organized. Yes, all of nature is organized by time to produce in you the sensation of beauty. And time itself, well, believe it or not, time is a frequency, and a frequency is not measurable by a clock. The Law of Time states that time is the universal frequency of synchronization. It is the nature of time to synchronize and to maintain all things in a condition of synchronization. Synchronicity, then, is the experience of real time. When we say that time is a frequency, we can be more precise and say that time is a universal constant expressible by the mathematical ratio 13:20. That is, the 13:20 ratio is the frequency of synchronization.

Of course, most people have never even heard of the Law of Time much less comprehend what the 13:20 ratio might mean. But then, that again gets to the root of the problem, or rather, the dilemma: If humans are living in their own time apart from the rest of the biosphere which is governed by the natural timing frequency, how could they ever know about the Law of Time? The humans are all a little like Mrs. Malaprop in the play by Moliere who learns to her surprise that she has been using grammar all of her life-though it is much more serious than that. So we humans are with the Law of Time-it has been operating throughout history without our awareness of it. Because of this, its way of making itself known to us was the infamous 9-11. Yes, in the analysis of the Law of Time, the 9-11 marked the end of artificial time.

Living in ignorance of the Law of Time and of the true nature of time, the human species constructed its own concept of time which is based on the clock with its 60-minute hour and the Gregorian calendar with its maddening array of unevenly numbered months. Hence, the paradigm of the artificial timing frequency is defined by the ratio 12:60 (twelve-month calendar, 60-minute hour) -in contrast to the 13:20 ratio of natural time. If the artificial mechanistic and irregularly measured time sets the human race apart from true or natural time, does this not also establish the fact that the human race is living an error in time? Only by living such an unconsciously assumed error could the human race arrive at such an apocalyptic moment as the Inevitable Event-inevitable because any deviation from the truth has an inevitable moment when the truth rebounds in some dramatic or even apocalyptic way. Is it possible that the entire construct of modern civilization, so devastating to the biosphere, is a function of this error in time? Is modern civilization like a time warp, a bubble of artificial time that suddenly got popped on the 9-11?

Back in the 1990s, now seemingly so long ago, I was traveling around the planet on behalf of the Law of Time and the biosphere, and making my observations regarding the effects of artificial time from a planetary whole systems point of view. I saw that even though the human species had evolved - or devolved, as the case may be-into a cultural hybrid which I call the planetary human, the object of the much touted "globalization," I saw that the consciousness of this cultural hybrid was anything but planetary. This schism between the propaganda of globalization and the actual sectarian and fragmented state of consciousness of the hybrid human was further exacerbated, I observed, by the potently unconscious effects ofliving an error in time. Ironically, if the Inevitable Event left many of us in the dark, it has brought the Law of Time into the light. To elucidate let me quote here from a text I wrote in 1996, and which I think will give us a point to expand upon in order to bring the Inevitable Event into sharper focus, while allowing me to define some of my terms:

"Through an error in time, the human species transforms its artificial construct, civilization, into a global technosphere: the sum product of industrial mechanization of its biological functions. Because of human adaptation to the irregular mechanized 12:60

timing frequency, the technosphere runs counter to the laws of the biosphere, creating a magnetic instability between the primal crystalline and vital organic processes."2

The current explosion of the world crisis, stemming from the destruction of The World Trade Center Twin Towers, demonstrates the hypothesis of the Law of Time that states: operating on artificial and mechanistic timing standards will cause the human to deviate from natural time to the point of its self-destruction, the end result of the magnetic instability referred to in this reference. But here we have some further definitions to make. Let us start with a definition of the technosphere, since that word is featured so prominently in the title of this book, *Time and the Technosphere: The Law of Time in Human Affairs.*

While the term biosphere defines the entirety of life as a single coherent unity, inclusive of its inorganic or semi-inert support systems such as the atmosphere and the hydrosphere, technosphere defines an artificial sheathe or membrane held together by industrial technology as a whole system. This technological mantle is the sum of the processes devised by humans resulting from the application of certain scientific and economic principles, especially during the last half century. The effects of the technosphere are to supplant the organic processes of the biosphere with totally industrialized ones, resulting in a severe imbalance in the biosphere. This imbalance, the "magnetic instability between the primal crystalline and vital organic processes" refers to the disruption of the delicate interaction between the inert (crystalline) and biological processes and structures which constitute the vibrant mechanisms and interactive cycles of the biosphere. Phenomena such as global warming and over-population are symptomatic of the technospheric disruption of the natural order of the biosphere.

The term technosphere, however, is actually just the middle term of a larger process defined as the biosphere-noosphere transition. According to the principle figure behind the elaboration of the laws of the biosphere, V. I. Vemadsky (1863-1945), as an evolving structure, the biosphere is inevitably being transformed into a new geological and evolutionary condition, the noosphere-Earth's mental envelope. In Vemadsky's analysis, the entirety of the biospheric process can be described as a single biogeochemical unity. According to Vemadsky, due to man's transformation of nature since the industrial revolution, this biogeochemical unity has entered a state of combustion-an accelerated process of transformation. It is this rapidly accelerating geochemical combustion-the net effect of industrialization and its waste -that accompanies an evolutionary shift, the transformation of the biosphere into the noosphere. But between the biosphere and the noosphere there is the technosphere, the intervening medium of transformation.

So when we speak of the biosphere and the noosphere we must take into account the technosphere. In actuality we must speak of the biosphere-technosphere-noosphere transition. In this context, the noosphere is the condition of the human mind purified of the error of time. And if the noosphere is the Earth's mental envelope, it could only be so because of a unified state of mind, the transformation of the hybrid planetary human into a genuinely spiritualized planetary being, the mind of the Earth no less-something that seems phenomenally utopian from the perspective of today's evening news. How could this come about, this noosphere of a telepathically unified human consciousness? Again, the Law of Time supplies genuine answers. To begin with, it says, change your calendar, get back to living in harmony with the natural cycles of the rest of the biosphere-and the universe. If you don't, well, the destruction of the Twin Towers was just the first stage of the Apocalypse. But we still have a choice. The other side of the coin of the Apocalypse shown to humanity on prime time television on the 9-11 is entry into the noosphere. But we must first understand what is really going on, and then act intelligently.

The mental climate in America is particularly difficult and strained now. In order to maintain a positive and constructive attitude of mind during this terrible time, I decided to write this book. As you can see, this book takes for its point of departure an analysis of the destruction of the World Trade Center (the actual hub of the technosphere) as the Inevitable Event defining the dynamic of the biosphere in its process of transforming into the noosphere. The analysis of the event in this light will give ample opportunity for presenting the key ideas of V. I. Vernadsky, in particular the concept of the biosphere which he so single-handedly amplified and defined, as well as the cosmic ideas of other Russian thinkers which are little known in the West. I have already written about and given much thought to this matter in general, summarized in part in the First Planetary Congress of Biospheric Rights, held in Brasilia, Brazil in 1996, but nowhere have I written for a wider public audience concerning the nature of the biosphere-noosphere transition.

I feel it is especially important at this time to present an analysis of this event in a scientific context that is beyond nationalism and ideology, so that human beings can begin to understand that they are a function of the biosphere, but not necessarily its controlling mechanism. Of course, the Law of Time is the key factor involved in this analysis, and understanding the biosphere in the context of the Law of Time is absolutely critical for establishing the basis of an entirely new worldview and hierarchy of values-the much awaited new paradigm.

Like my thoughts on the biosphere-noosphere transition, my investigations of the Law of Time have also not as yet been presented to the general public. In fact, you will find scarcely anyone who has even heard of the "Law of Time." This is because my researches and investigations over the past decade which resulted in the discovery of the Law of Time were not conducted in any formal academic way, nor through any corporate or government sponsored grant or officially recognized research institution. The discovery of the Law of Time has been, nonetheless, a rigorous, life-consuming pursuit. The laboratory for its study was to be found in a phenomenological and anthropological investigation of the effects of mechanized time on various population groups absorbed in what is called "modern civilization."

The premise of this investigation is simple: it is an undeniable fact that the time of human civilization, governed by the clock and the Gregorian calendar, is not the same as the time of the rest of the biosphere. Artificial time is not the same as natural time. Or rather, artificial time establishes a frequency which governs the human species totally apart from the timing frequency of the rest of life. What are the effects of artificial time and how do they define the nature of modern civilization? The answers to these questions open a perspective that has been scarcely considered. Yet this perspective is so clearly an essential factor in the description and definition of the human condition, that, in the wake of the tragic events and their ominous aftermath, it now begs to be presented in a proper manner. Hence this book. Suffice it to say that the Law of Time in every respect answers the question posed by my previous books and summarized in the single query: how will modern man escape the fatal consequences of the one-sided mechanization of his biological operations and the imminent destruction of his life-support system?

Defining a planetary whole systems approach to the analysis of time in human affairs, the first postulate of my book *A Treatise on Time* (1996) concerning the principles and nature of time as the fourth dimension is worth quoting here, since it introduces the fundamental problem informing the investigation of Time and the Technosphere:

> Just as air is the atmosphere of the body, so time is the atmosphere of the mind. If the time in which we live consists of uneven months and days regulated by mechanized minutes and hours, that is what becomes of our mind: a mechanized irregularity. Since everything follows from mind, it is no wonder that the atmosphere in which we live daily becomes more polluted, and the greatest complaint is: "I just don't have enough time!" Who owns your time, owns your mind. Own your own time and you will know your own mind.3

It must be understood that the events of 9-11 were so historically unprecedented, so mind-bogglingly dramatic, that they require a large lens through which to fully interpret their meaning. The Law of Time is such a lens. Quite simply, the destruction of the Twin Towers defines the limit of artificial time. If this is so, what can be expected following this world-shattering event? Because the Law of Time began with the premise of defining the difference between artificial time and the time of nature, the larger context of the biosphere was resorted to almost immediately. Being the study of an ongoing and evolving phenomenon, the investigation of the biosphere by its principle researcher, V. 1. Vernadsky, pointed to another imminent evolutionary stage: the noosphere, the "mental envelope of the planet." However, an intermediate stage was also perceived by researchers who followed Vernadsky, and it came to be called the technosphere, "the technological envelope of the planet." The end or limits of the technosphere define the birth or beginning of the noosphere.

With the events of 9-11, this is no longer just a theoretical concept but a vivid reality. As a species we are now undergoing this dramatic evolutionary moment, otherwise known as the biosphere-noosphere transition. It is for this reason that this book also presents novel definitions of time and pragmatic conclusions that can be employed by anyone if they so choose. If the root of the technosphere is artificial time and its proliferating mechanized constructs, then in the collapse of the technosphere, an event ordained by the laws of nature, there must be an orderly path or means for establishing the noosphere, also ordained by natural law. The Law of Time defines this orderly path as a conscious shift in the human timing frequency, away from artificial time and into universal natural time. This can only be accomplished by a universal reform of time, known as the calendar change. If there were no such path, the conclusion to the collapse of the technosphere would be an unbearable barbarism.

By its nature, the topic of the book is cross-disciplinary and provocative-it is visionary history. I have been described as a "spirituality historian" and "cosmic harmony researcher."4 I believe this description also characterizes *Time and the Technosphere*, which does present a solution, a new world paradigm, if you will. A new paradigm has been awaiting humanity ever since the notion of paradigms was first raised by Thomas Kuhn in 1964, in his book *The Nature of Scientific Revolutions*, or even earlier by Vernadsky and Pierre Teilhard de Chardin in their invocation of the noosphere. To be truly new, such a paradigm could hardly be expected to arise from traditional fields of thought or methods of research, be they quantum physics or microbiology. In fact, as I have often said, most people wouldn't recognize the new paradigm if it ran into them on the street. This is because people's consciousness and perceptions are basically very set and unexamined-as unexamined as the effects of the watch on their wrist or the calendar on their wall. In fact, one of the consequences of the technosphere is the limiting nature of consciousness which remains unchanged despite the fact that technology is changing all of the time. But with the occurrence of the Inevitable Event, history has been punctured. Perhaps now the new paradigm can be perceived: the paradigm of natural time as the universal factor of synchronization.

Although prompted by the stunning terrorist attack upon and consequent apocalyptic collapse of the World Trade Center Twin towers, these reflections are actually a synthesis of thoughts and explorations in the domain of time that I now find necessary to communicate in a coherent and organic form. The grand theme of this study is to understand how and why the collapse of the twin World Trade Center Towers was a biospheric event. Even so, the study of the Inevitable Event within the context of the evolution of the biosphere requires and leads us to still grander domains of thought-the historical, the theological, and the cosmological. The reason that these reflections and meditations spiral into ever grander domains of thought is due to the principle of analysis and the guiding factor employed in this study. This is the Law of Time, which is the fruit of a life-long research and pursuit of knowledge. It is the Law of Time that brings the biosphere into timely focus.

The biosphere is scarcely known even to most educated people. As a biogeochemical whole system in which the human is but one of the functioning components, the biosphere is an intricate unity with its own governing laws and principles. Without becoming conscious of how the human organism participates in the laws and principles of the biosphere, the human will continue to remain ignorant of the biosphere's existence and therefore will sooner than later reach a termination of its own evolutionary possibility. A demonstration of how the laws and principles of the biosphere, crystallized into a temporary and intermediate sheath called the technosphere, reached a climactic evolutionary point in the collapse of the World Trade Center towers will provide the means of educating in general concerning the biosphere. It will also allow us to elaborate on the meaning and nature of the technosphere, and the imminent transformation of the biosphere into the noosphere, the Earth's "mental envelope."

A fundamental purpose of the Law of Time is to expand upon the meaning and significance of the Inevitable Event, as well as upon the biosphere, technosphere, and noosphere in relation to the evolution of life and consciousness in the universe. To speak of an event being "inevitable" is to bring about a reflection on the nature of time, and even of the laws of cause-and-effect and karma. It is time that governs both cause-and-effect as well as the actions of karma. And it is time that dominates inevitability, because any such inevitable event is located in a very precise moment in time. But what actually is time? How does time "locate" events? And, once again, what is the Law of Time?

As the criterion of natural time in which synchronicity is the norm, the Law of Time is the key that unlocks the reason why the Inevitable Event occurred when it did. By precisely locating it within the evolutionary continuum of the biosphere and in relation to its point of mutational shift, the Inevitable Event is placed into a greater context of cosmic comprehension by the Law of Time. Through the lens of the Law of Time we will be able to understand the relationship between the biosphere, the intermediate state of the technosphere, and the imminent stage of the noosphere. Defining the Law of Time as the factor of universal synchronization, the law by which all events in the universe are maintained in synchronic relation to each other, we approach the domain of a hitherto undefined realm, that of the synchronic order.

As the unifying fourth-dimensional order of time in the universe, the synchronic order is measured and gauged by the 13:20 matrix. The mathematical coding of the Law of Time is entirely locked into this 13:20 matrix, otherwise known as the Harmonic Module or T zolkin, the basis of the sacred count of the ancient Maya. When we examine the Harmonic Module, a 13 x 20 matrix, we may well ask what does that have to do with time? It is obviously as different from a clock, as a tree is from a flagpole! When we examine the matrix carefully we see that there is a repetition of thirteen notations, the numbers 1-13, that occurs 20 times yielding 260 (13 x 20) units.

Holding the 13:20 matrix together is a pattern which I identified in my book *Earth Ascending* (1984) as the binary triplet configuration, and in the *Mayan Factor* (1987) as the Loom of Maya. This pattern consists of 52 units, 26 on either side of the central or seventh vertical column. **If** you contemplate this 52-unit pattern you will see it is characterized by binary radial symmetry. This quality characterizes the entire matrix and defines the quality of fourth-dimensional time as radial and instantaneous distinct from the current third-dimensional paradigm which defines time as being linear and sequential. The radial quality of fourth-dimensional time is what accounts for its being the factor of universal synchronization. This is very different from the sensation of the second hand as it sweeps around the clock, indicating the inexorability, not of time but of the mechanization of time! The 13:20 matrix becomes potently useful as the means of establishing the synchronic order when it is coordinated with a genuinely harmonic timing standard, the Thirteen Moon/28-Day calendar.

"Time is the fourth dimension," is the famous adage attributed to Einstein. This statement notwithstanding, the modern notion of time is bogged down in the minutiae


A
BIN
ARY
Ω
CONFIGURATION
TRIPLET
NORTH POLAR ZONE
ZONE OF DOUBLE HELIX CROSSOVER POLARITY
ZONE OF TRANSFORMATION
DNA INFORMATION TRANSFER MODEL
SOUTH POLAR ZONE
NORTHERN HEMISPHERE
EQUATORIAL LINE
SOUTHERN HEMISPHERE
MOVEMENTS 1–16
MOVEMENTS 49–64
MOVEMENTS 33–48
MOVEMENTS 17–32
BASIS OF QUADRIPARTITE DIVISION
AC TEMPLATE
CA TEMPLATE
O
CHROMATIC SHIFTS × 8
RED
ORANGE
VIOLET
PURPLE
BLUE
INDIGO
YELLOW
GREEN
THE CODE
BINARY-TRIPLET CONFIGURATION PRIMARY MATRIX =
260 units
− 20 mystic column
= 240 ÷ 8
(2 binary quadripart divisions)
= 30 units per 1/8 section
TOTAL PSI BANK MATRIX =
2080 (260 × 8) units
OR
64 1/8 Sections @ 30 units
double helix polarity pattern
= 52 units, 26 ●, 26 ⊛
OR
13 sets of 4 units each
Starting with 4 corners,
then moving inward
Each set of 4 units adds up to 28 (× 13)
Total adds up to 364
= Lunar year
The Configuration Describes
Underlying Pattern of
Number Relationship in the
BEN FRANKLIN MAGIC SQUARE
of 8 with a Pulse of 260
BINARY LANGUAGE
● = ▬
⊛ = +
0
1
AC
CA
ELECTRICAL CHARGE
I CHING/DNA BINARY INFORMATION CODE
COMPUTER CODE
PSYCHOCULTURAL PULSATION
MYSTIC COLUMN
AXIS OF ETERNAL PRESENT
140
PSYCHOCULTURAL PROCESS
= ABORIGINAL CONTINUITY
INFORMATION FLOW (FUTURE-TO-PRESENT)
= CIVILIZATIONAL ADVANCE
INFORMATION FLOW (PAST-TO-PRESENT)
RADIATION BELTS
= SOLAR ELECTRON OUTER BELT
= COSMOGALACTIC PROTON INNER BELT
PRIMARY MATRIX KEY
PRIMARY MATRIX Containing BINARY TRIPLET CONFIGURATION =
Tonal Pohuall: or *Tzolkin,* "Book Of Days"
Best known as the sacred calendar of the ancient mesoamerican civilization.
260-Day calendar based on numbers 1–13 (· , ≝)
and 20 place-units for total of 260 permutations/days.
The calendar meshes with solar calendar every 52 years. 16 cycles of the 260-day sacred calendar comprise 11.3 years, or
the cycle of binary sunspots from inception to point of reverse or crossover polarity
MAYAN NOTATION
1
2
3
4
5
6
0, PLACE BY 20s
CENTER OF MYSTIC COLUMN
= Ω
● = A
BINARY SUNSPOT CYCLE PATTERN
11.3 yrs
11.3 yrs
BASIC UNIT PATTERN
= ¼ PRIMARY MATRIX
= 13 UNITS
(¼ of 52)
78
73
109
104
= 364

13:20 Matrix-Harmonic Module with Binary Triplet Configuration

of quantum mechanics and cessium clocks, in a hair-splitting myopia that cannot see the forest for the trees. The fact is that only time governs the whole order of the universe in a manner that transcends all spatial limitations, even those of the relativistic MinkowskilEinstein four-dimensional universe, which is confined by the speed of light. As the universal factor of synchronization, time is instantaneous and transcends light. This novel perception of time defines a new reality, the synchronic, of which our experiences of synchronicity are but a foretaste. The synchronic order described by the Law of Time poses the order of an entirely new science of time.

To be realized and then applied, the science of time is dependent on two factors: a sudden and radical disruption of the historical continuum; and a genuine globalization or planetarization of consciousness. The break in historical continuity is necessary to jolt the human consciousness from its stagnant and entropic state-defined by the Law of Time as the delimiting 12:60 frequency consciousness of artificial, mechanistic time-while the globalization of consciousness, intimately connected with this sudden discontinuity, is necessary for the application of this law at a planetary whole systems level. Of course, the radical disruption of the historical continuum was provided by the collapse of the Twin Towers, and can actually be mapped in a description of the dialectical process of human evolution.

If one studies *Earth Ascending,* Map 19, "Binary Pulse of Psycho cultural Development," [shown on page 14] one can pinpoint the "Inevitable Event" of the radical historical discontinuity as the point at which the AC and CA currents cross over one another and switch polarity at the very top of the graphic depicting the "historical" process. What does it indicate, this point of psychic polarity switching currents?

The historical dialectic is understood as the interplay of two "currents" of consciousness, AC "Aboriginal Continuity" and CA, "Civilizational Advance." In the prehistoric phase, the consciousness is dominated by the Aboriginal Continuity or AC. This refers to the primary experience of the original human nature- life lived as a ritual or ceremonial round within the perimeter of the timeless present. But as the human enters the historical cycle, about which we will have more to say in later chapters, the CA becomes more predominant. As Civilizational Advance, the CA represents the tendency toward exclusive reliance on reason, logic and written means of communication. The Law of Time further defines the CA as being motivated increasingly by the artificial timing frequency of the 12:60 which gains in prominence until the final phase of the historical cycle, industrial globalization, when the CA has gained complete dominance of the biosphere.

During this final stage, the global mental condition is defined as the involvement in secondary or artificial means of experience, furthered by the planetary



INCIDENCE OF RELATIONSHIP BETWEEN
PSYCHOSENSORY ELABORATION (PSE)
AND
PSYCHOATMOSPHERIC DENSITY (PAD)

KEY:

- AC = ABORIGINAL CONTINUITY (YIN)
CONTAINS ENTIRE BLUEPRINT
OF PSYCHOCULTURAL DEVELOPMENT
OF TOTAL BIOPSYCHIC ORGANISM, MAN
POLARITY FLOW: "FUTURE" TO PRESENT = VISION
INFORMATION IN WHOLE PATTERNS
"CONSERVATIVE"

+ CA = CIVILIZATIONAL ADVANCE (YANG)
COMPLEMENTARY PULSE
DYNAMIC IMPLEMENTATION OF VISION
POLARITY FLOW = "PAST" TO PRESENT
INFORMATION IN
VERBAL SEQUENCES & MATHEMATICAL BITS
"PROGRESSIVE"

INTERACTION OF AC/CA
CREATES PSYCHOSENSORY ELABORATION (PSE)

ACTIVATION OF CA PULSE BEGINNING WITH
HIERATIC STAGE INITIATES
CUMULATIVE DEVELOPMENT OF *PSE*

INCREASE OF PSE PRODUCES INCREASE IN
PSYCHOATMOSPHERIC DENSITY (PAD)

AS PSE INCREASES, AC CURRENT
BECOMES MORE DISCONTINUOUS

MAXIMUM PSE, MAXIMUM PAD
MAXIMUM AC DISCONTINUITY
ARE ATTAINED AT CLIMAX
OF STAGE 4, GLOBAL INDUSTRIALIZATION

AS *PSE* ATTAINS MAX. CONDENSATION
(MAX PAD DENSITY)
ESP EXPERIENCED AS MAX ABERRATION

4 **GLOBAL INDUSTRIALIZATION**
CONSOLIDATION OF CA
MAXIMUM AC DISCONTINUITY

3 **STAGE OF SPIRITUAL REVITALIZATION**
REACTIVATION OF AC
SYNTHESIS OF HIERATIC
STRUCTURES

2 **EMERGENCE OF CIVILIZATION: HIERATIC STAGE**
DIFFERENTIATION OF
CA MEMORY PLATE
INTO 7 HIERATIC STREAMS

1 **ABORIGINAL STAGE**
AC = DOMINANT = PSYCHOSENSORY STASIS
MINIMAL PSYCHOATMOSPHERIC DENSITY
MAXIMUM PSI INFORMATION FLOW

AC = −
CA = +
"FUTURE"
HEAVEN
VISION
CA
AC
0 = 1945
500 PA
1000 PA
2000 PA
3000 PA
4000 PA
6000 PA
10000 PA
"PAST"
EARTH/PRACTICALITY
SUBDOMINANT
DOMINANT
AXIS OF ETERNAL PRESENT
SYNCHRONICITY =
CONGRUENCE OF AC/CA

Locating the Inevitable Event in the Holonomic Equation:
9-11, 2001 Climax of the Binary Pulse of Psychocultural Development
(from *Earth Ascending*, Map 19)

technosphere. The sum effect on consciousness of the advanced CA stage is defined as Psychosensory Elaboration or PSE, which in turn creates a psychoatmospheric density (PAD)-literally a mental cloud which obscures altogether the organic biopsychic reality of the human within the biosphere. From the point of view of a planetary pathology, this massive collective obscuring (CA) of the original nature (AC) defines a "suicidal crisis point," a moment at which the subconscious instinct of the human being programs its own self-defeat in order to ultimately return to the organic reality of the biosphere and the simultaneous advent of the noosphere. Hence, the Inevitable Event: the radical break in the continuum of history.

This moment of radical historical discontinuity occurred with the September 11,2001, terrorist attack on the twin towers of the World Trade Center-the very nerve center of late global industrialization-and the Pentagon, the supreme military fortress that defends globalization. If the fall of the towers symbolically augured the fall of Babylon and the Tower of Babel itself, the penetration of the Pentagon was no less symbolic. The fact that there was not one but two towers of Babel and a separation of some twenty minutes between the attack on each tower allowed the second attack to be viewed live on global television by about as many people on Earth as had ever witnessed anything at one simultaneous moment. By the end of the day, the scene had been repeated multiple times on virtually every television network on the planet.

The unbelievable shock of the moment and its simultaneous perception, coupled with the symbolism of what was actually occurring, effectively rendered the break in the historical continuum as a profound mental event-a rupture of 5,000 years of history from the first Babylon to the last. The witnessing of the event on television meant that it was received immediately into the nervous system of virtually the entire species. This in itself is a noospheric moment-the mental envelope of the Earth made collectively and globally conscious in one instant of history-shattering significance, and hence, the genuine entry into post-history. Archetypally, the images of the towers collapsing with people flying or jumping off the upper stories, is a pure reflection of the Sixteenth Major Arcana card of the traditional Tarot which shows a tower being shattered by lightning, with bodies falling down from it.

While the negative powers and forces grapple with their shattered dreams in the aftermath of the event, it is the time for the powerful luminescence of the noosphere to begin to activate the receptive cells of the human system within the now catalyzed biosphere. Fifty-six years after Hiroshima, the fall of the World Trade Center Towers is the fatal puncture in the technosphere which is intended to reorient the human within the biosphere. ESP (extrasensory perception)-the opposite of PSE (psychosensory elaboration)-is released in the instantaneity of the information reaching virtually every human being on Earth. This is the collective reactivation of the Aboriginal Continuity current that has been disengaged and disempowered for so long by the Civilizational Advance. Civilization has finally been checkmated. Now the Revolution of Time must be completed in order to stabilize the biosphere, anchor the noosphere, and de-structure the technosphere.

According to the Law of Time, the Inevitable Event was already embedded in the moment in which it actually occurred, like a flaw in a piece of glass that, upon concussion at the right pressure point, shatters all at once. In the case of the World Trade Center Towers and the Pentagon, we are also dealing with symbolic constellations of such potency that the very act of their shattering redefines the reality of human consciousness. In fact, the nature and problem of human consciousness as it has evolved historically is also at the root of this astonishing event. While it will take time for the collective human consciousness to fully grasp just how much its reality is being redefined, a vacuum now exists within the technosphere itself-a vacuum which awaits being filled by a new paradigm. Since the collapse of the Twin Towers actually represents the limits of artificial time, the new paradigm must rest on a redefinition of time altogether. This is the definition supplied by the Law of Time, the pragmatic application of which is the replacement of the irregular measure of the Gregorian calendar by the harmonic measure of the Thirteen Moon/28-Day calendar.

Because of its harmonic measure, the Thirteen Moon/28-Day calendar coordinated by the Harmonic Module is the new dispensation of time-reckoning for the human race. Rooted in the four recurring year-bearers of the Wizard's Count--:-which is not the same as the Mayan long count, nor the Julian count of modern science-the Thirteen Moon calendar exists for the establishment of the reality of the synchronic order as an entirely new method of knowledge and being for the entire human race as a cosmic medium operating within the biosphere. By Wizard's Count is meant the circulation of thirteen numbers and four different glyphs-Yellow Seed, Red Moon, White Wizard, Blue Storm-that code the July 26 Thirteen Moon/28-Day calendar synchronization date to create a master 52-year cycle, Anchored in the Thirteen Moon/2 8-Day calendar, the synchronic order is the means for manifesting the reality of the noosphere on planet Earth. Without such a basis in a lived mathematics of time correlated to the actual cycles of Earth, the noosphere could not be experienced nor fully realized. The successful completion of the biosphere-noosphere transition, then, is the triumph of the synchronic order, the conscious elevation of Earth into the cosmic frequency of fourth-dimensional time.

For all of this to come to be, however, is yet dependent on an analysis of the role of time in the creation of the technosphere and the subsequent comprehension of its limits and the potential for its de-structuring. This is not only a matter of theory or prophecy; it is a matter of putting into practice, making a coherent action out of the application of the Law of Time as it completes the pressing urgency of the biosphere-noosphere transition. The coherent action to bring us through this rite of passage is the Great Calendar Change of 2004. Ultimately, this book is presented to make us ready for this unprecedented time changing moment. May you, 0 reader, ponder deeply and then, if you so will, come join me in living on the other side of the wall of mechanized time.

▼



2

Preliminary Definitions

Biosphere–Technosphere–Noosphere as an Evolutionary Continuum

BY UNDERSTANDING that the Inevitable Event was a function of the biosphere-indeed, a necessary moment in the evolutionary trajectory of the biosphere-we are saying that this event was not just a human enactment, but that humans, inseparable from the biosphere, are effected to perform functions that relate to the process of the biosphere as a whole. Seeing the Inevitable Event and, in fact, the entire human drama from the perspective of the biosphere, we are actually lifting the cruel tragedies of contemporary reality above conflict and into a state where genuine laws of peace and harmony may shed their light of wisdom, illuminating the human drama with a higher understanding. One thing is certain: Unless we rise above our own humanity and cultivate a non-anthropocentric view-the view represented by the noosphere-there will be no release from the calamity that is now engulfing us. The point is not of maintaining the global economy, but of saving the biosphere.

For the multilayered task of bringing a new understanding to light, defining the technosphere, and then the Law of Time, we shall begin with the former: defining the technosphere in the context of the evolutionary continuum of biosphere-technosphere-noosphere.

VERNADSKY AND THE UNDERSTANDING OF THE BIOSPHERE

It is amazing that the name V. I. Vernadsky (1863-1945) is so little known in the West, and that the word *biosphere,* as well as the laws and principles pertaining to it, are scarcely more known. To a large degree, this ignorance is due to the great cleavage in human relations experienced as the Cold War. The biosphere, which was profoundly studied and scientifically articulated by the master Russian scientist V. I. Vernadsky, is actually the precise word for what in the West is vaguely referred to as the *environment.* But even more than being a precise and scientific description for what is meant by the use of the word *environment,* biosphere defines a whole system model of life on Earth, and because of that, also presupposes a whole system methodology and point of view. You cannot speak about the biosphere without entering into a world of discourse that is holistic or holonomic to the core.

If one looks for Vernadsky's work in English, one will find precious little available. His key work, *The Biosphere,* exists in two very different translations; the one published by Synergetic Press in 1986 is easier to read, while the other, the "complete annotated edition" published by the Far West Institute in 1998, is far more erudite, with a major bibliography and much supplementary information. The earlier translation was published in conjunction with the opening of the Biosphere II Project outside Tucson, Arizona. It is now a tourist site, with a bookstore that carries nothing by Vernadsky! Several other hard-to-find English-language books on the biosphere include the excellently informative *Traces of Bygone Biospheres* by Andrey Lapo (Synergetic Press and Mir Publishers, 1987), the flashy *Biosphere Catalog* (Synergetic Press, 1985), and the much more specialized *Energies: An Illustrated Guide to the Biosphere and Civilization* by Vaclav Smil (MIT, 1999). Of these books, only *Traces of Bygone Biospheres* contains significant information about Vernadsky and his ideas. This scant list of available texts in English is hardly proportionate to the vast reality of the biosphere as a complex terrestrial dynamic in the throes of evolutionary change.

The place and role of Vernadsky in Russian science is virtually equal to that of Einstein in Western science. A consideration of the achievement of each of these scientists also presents us with a dramatic contrast in perspectives, areas of interest, and consequent modes of analysis. The physicalist relativism of Einstein's legacy and its pursuit of the Big Bang is radically different in almost every way from the legacy of Vernadsky's work, which presents a biogeological worldview that is organically integrative and the basis of what in Russian science has come to be called *cosmism.* While the physicalist fascination of Western science has supported the materialism of modern Western thought and its way of life (which is actually an accelerating function of the biosphere's own internal processes), the whole system thinking of

Vernadsky—characterized by the conception of a "biogeochemical process"—ironically supports a cosmic rather than materialistic worldview.

To illustrate the Russian perspective and the influence of Vernadsky's work, we present the concluding thoughts of a book by another Russian scientist and philosopher, 1. Laptev:

> Each one of us requires the whole earth—today this is quite clear. But surely each one of us is required by the whole earth! And when these two mutually penetrating requirements, so distinctly revealed and intensified by the leap out into space, are satisfied, the new historical epoch will begin "in which mankind itself, and with mankind all branches of its activity, . . . will experience an advance that will put everything preceding it in the deepest shade." (Fr. Engels, *Dialectics of Nature)* And people, no longer burdened by the thirst for money, will remember something that many of our contemporaries have forgotten: The only important things in life are such intangible qualities as beauty and wisdom, laughter and love.
>
> Nothing remains for us, members of a society the ideals of which are in unison with elemental geological processes and the laws of nature, but to wish that people the world over would recognize this as soon as possible.!

Laptev's words—written twenty-eight years ago and precisely at the midpoint between Hiroshima and the Inevitable Event, as well as during the year in which the World Trade Center in New York City was finally completed and inaugurated (April 4, 1973)—simply and elegantly state the theme and point of view that we are pursuing. In fact, it is the Inevitable Event that prepares us for the new historical epoch. But first we must realize how we are organized by the biosphere in order that the technosphere may be transformed into the noosphere.

The root of Laptev's cosmic vision lies in Vernadsky's succinct definition of the biosphere: "The biosphere is the region on Earth for the transformation of cosmic energies." Although the word *biosphere* had been coined in the late nineteenth century, it was really only with Vernadsky's efforts that the biosphere became a viable description of the totality of life on Earth inclusive of its organic and inorganic support processes.

Vernadsky was trained as a geologist with a specialization in crystallography. He immediately absorbed the implications of Curies discovery of radioactivity (1896), and devoted many studies to the purpose of uranium and naturally occurring radioactivity within the Earth's geology. By the time of the First World War, Vernadsky had already written important texts such as *Fundamentals of Crystallog;raphy and Descriptive Mineralogy,* and, along with Madame Curie, proposed an "international radiography of Earth's crust." This was in advance of Alfred Wegener's definitive work on plate tectonics. During the time of the First World War and Russian Revolution, Vernadsky's attention turned toward the problem of living matter and its relation to the geochemistry of the Earth. From this was born Vernadsky's perception of the unitive biogeochemical process by which the biosphere maintains itself. In 1923 he published a "plea for the establishment of a biogeochemical laboratory."

In Paris, Vernadsky worked at the Insititut de Radium (Marie Curie) and became acquainted with Henri Bergson, who was then president of the International Commission of Intellectual Cooperation of the League of Nations. Through Bergson's circles, Vernadsky met often with the biologist Pierre Teilhard de Chardin (1881-1955) and the philosopher Edouard Ie Roy (1870-1954), with whom Vernadskyjointly coined the word and concept of the noosphere. Although Pierre Teilhard de Chardin is credited in the West with the concept of the noosphere, defined by him as the "mental envelope of the planet above and discontinuous with the biosphere," de Chardin's approach to the evolution of the noosphere as a natural consequence of vertebrate biology differs from Vernadsky's understanding in which it is the entirety of the biosphere that evokes the noosphere.

The chief fruit of this fertile time in Vernadsky's life was the publication of the little book titled *The Biosphere* (1926). Demonstrating the synchronic ordering principle of the noosphere, it is interesting that the same year that saw the publication of *The Biosphere* also witnessed the appearance of Jan Smuts noted book *Holism and Evolution.* Through most of the rest of his sometimes turbulent career (he often came under attack from hard-line bolsheviks), Vernadsky was to elaborate on the laws and principles of the biosphere, often expressed simply as problems in biogeochemistry. At the same time, his influence as a holistic thinker began to spread through the Soviet Academy of Sciences. A list of a few of his later publications gives some idea of the breadth of his thought, and includes: *Geochemistry, Problems in Biogeochemistry I* and *II, On the Boundaries of the Biosphere, Goethe as Naturalist, Scientific Thought as a Planetary Phenomenon, Some Words on the Noosphere,* and his never completed work, *The Chemical Structure of the Earth's Biosphere.*

Following the death of his wife in 1944, Vernadsky expressed the opinion that after the Second World War, American and Russian scientists should work more closely together. Early in 1945 *(*January 6), Vernadsky followed his wife to the grave. The Second World War ended, only to be followed by the Cold War (1947-1990). The critical collaboration between American and Russian scientists longed for by Vernadsky was soon to be buried in the ideological wasteland over which the superstructure of the technosphere would be constructed, a fact that in itself hastened the acceleration of the biogeochemical processes bringing about the climax of the technosphere.

Vernadsky did not live to witness the birth of the atomic era, which began only months after he died. But like Einstein in America, in 1940 Vernadsky-along with several other scientists, and mindful of the possible military applications-had prompted the Russian government to begin investigations into the possibility of deriving energy from nuclear fission. Yet it is most remarkable that by the time of his death, Vernadsky had almost single-handedly defined virtually every aspect of the laws and principles of the biosphere. This he always did with an eye to an imminent moment in the not-too-distant future when there would be a dramatic biogeochemical mutation or combustion, out of which the biosphere would somehow trigger the noosphere:

> Not at a crisis of nervousness do we stand now, not at a time for the vacillation of flabby souls; but at a great turning point in the history of scientific thought, at a crisis such as occurs but once in a thousand years, such as has not been witnessed for many generations. Standing at this point, with the vista of future achievements before us, we should be happy that it is our lot to live at this time and to participate in the creation of tomorrow.2

Undoubtedly his sense of the great moment of transition came from the very fact that during the span of his life from 1863 to 1945, some eighty-two years, Vernadsky was able to witness firsthand the accelerating effects of man's thought-in the form of industrial technology and the machine-and its turbulent and transformative impact on the terrestrial biosphere. After all, as a geologist, Vernadsky was familiar with the long history of the Earth, and the impact of human technology on the biosphere was inescapably the most significant aspect of any study of the biosphere to the present time. So wrote Vernadsky: "Only man transgresses the established order. . . upsets the equilibrium, though whether he materially cripples the transforming mechanism, or merely redistributes it, we cannot at the moment be sure."3

The "transforming mechanism" referred to is the biosphere itself, which Vernadsky had already defined as the medium or region for the transformation of cosmic energy on Earth. At its simplest level, the unity of the whole of living matter of the biosphere is the sum of its living organisms. These living organisms either directly or indirectly are continuously processing solar and cosmic radiation, transforming it into various chemical cycles that establish the atmosphere, most notably through photosynthesis and the oxygen and carbon dioxide cycles. The important point, however, in any consideration of the biosphere is the principle of unity: the biosphere is a unitive complex of cycles summarized as a single continuously transforming and slowly mutating biogeochemical process. In this single complex cyclical process, all of life-all of living matter-is a unity, a singular dynamic by which the biosphere can be considered as a living whole. From the plankton of the oceans to the trees in the forest and the human peering from his cave at the rising sun-all of this is a single unity.

It is the interaction of the living matter with the inert matter that creates and establishes the attributes and dynamics of the biosphere as a whole, all of which are now in a heightened state of acceleration and transformation, for as Vernadsky put it in the conclusion to *The Biosphere:* "The thought of the human species is a new fact which is turning the structure of the biosphere upside down after myriads of centuries." The structures and principles of the biosphere that man is now upsetting include: the continuity and invariance of life on Earth; vegetation as a transformer of the energy of the sun; multiplication as a manifestation of transformed solar energy; propagation of life and the forces resisting propagation; and the unique relations of life to the inert matter of the biosphere, including the composition of living matter into two orders, plant life and the various biological animal species, inclusive of man. The first order of plants and bacteria constitute the mechanism for capturing the solar radiation and introducing the energy of the sun into the biosphere. The second order of biological life is a manifestation of the process of the transmission of energy through the vegetable world; that is, at a primary and fundamental level, animal life is dependent upon plant life for its existence. (See plate 2, Life Is the Transformation of Solar Energy.)

All these principles for maintaining the equilibrium of the biosphere are functions of the dynamic of the different biochemical and geochemical cycles that maintain life both on land and in the ocean, all of which are subjected to processes that we refer to as evolution, both geological and biological. The evolutionary mechanisms of life include the principle of the biomass constant and the biogenic migration of atoms. Both of these mechanisms refer to and define the continuity and invariance of life on Earth. That is, the quantity of living matter has remained roughly unchanged since the origin of life on Earth-the biomass constant. Furthermore, the amount of oxygen in the biosphere is equal to the amount of biomass. It is the pressure of the different species on each other with the resultant interactions and changes that checks the infinite propagation of anyone species at the expense of the rest, and causes the mutation and evolution of the different life forms. It is through the intermediate structure of the technosphere that the human is wreaking the greatest havoc on these principles that are intended to maintain the biosphere as a stable dynamic, and by which the human constitutes a biomutation of unparalleled significance. The different stages of the mutation of life account for the biogenic migration of atoms: "The evolution of different forms of life throughout geological time increases the biogenic migration of elements in the biosphere."4 The metamorphosis of dinosaurs into fossil fuel is an example of the biogenic migration of atoms-and of the introduction of "free energy" (the term for industrial waste and by-products such as carbon monoxide) into the biosphere, while at a more mundane level, it refers to processes such as metabolism, circulation, breathing, and so forth.

To summarize, there are two biogeochemical principles. The first states: "The biogenic migration of chemical elements in the biosphere tends towards a maximum of manifestation"; this refers to the presence of life everywhere on Earth, as well as the principle of the pressure of living matter upon itself. The second biogeochemical principle states: "The evolution of species, in tending towards the creation of new forms of life, always move in the direction of increasing biogenic migration of the atoms in the biosphere. . . . The second biogeochemical principle regulates the course of evolution. A newly evolved species will survive in the biosphere only if it is sufficiently able and sufficiently active in furthering the migration of atoms. The organism cannot be considered apart from its medium. It is a part of the complex mechanism of the biosphere." Here Vernadsky concludes his study of the biosphere with a consideration of the laws regulating evolution that, for him, are to be sought in the mechanism of the biosphere and not in accidental circumstances. For this reason "evolution must proceed, namely, in the direction of increasing consciousness and thought, and of forms having greater and greater influence on their surroundings."5 This consideration leads Vernadsky to domains of philosophical or religious thought. Why?

"We are confronted with a new form of biogenic migration resulting from the activity of human reason. Human thought has changed in a brisk and radical manner the trend of natural processes and has even modified what we call *natural laws.* Consciousness and thought, despite the efforts of generations of thinkers, have never been defined, have never been given a physical basis, in terms of matter and energy."6 And here Vernadsky poses a question that remained unanswered for him but that also leads to a consideration of the noosphere: "How can processes which seem purely physical be affected by consciousness?"7

Although *The Biosphere* is the initial statement and underlying basis of all Vernadsky's later thought and work, his final major study, *Problems in Biogeochemistry II,* translated and published by his son, George Vernadsky, at Yale University in 1944, states the final conclusions of Vernadsky on the intriguing relation of human consciousness-via its thought and projected dynamic, the machine-on the biosphere. These reflections provide us with a means for defining more precisely the nature of the technosphere and noosphere.

FROM THE CREATION OF THE TECHNOSPHERE TO THE ADVENT OF THE NOOSPHERE

Vernadsky developed the biosphere into a full scientific description of the sum of life and its support systems on Earth, and was a co-originator of the concept of the noosphere, yet he seems never to have used the word or concept of the technosphere. In some of Vernadsky's descriptions of the relation of man and his thought on the biosphere, however, the technosphere is absolutely implied. In reading the following chain of Vernadsky's thought, we can discern what we refer to as the biosphere-technosphere-noosphere continuum:

> Man by his work and his conscious attitude toward life is remaking a terrestrial envelope, the geological domain of life, the biosphere. He is transforming it into a new geological state, the noosphere.
>
> He creates within the biosphere new biogeochemical processes that did not exist before. A planetary phenomenon, the biogeochemical history of the chemical elements is notably changed.
>
> An immense new form of biogeochemical energy is represented by the technological work of man, complexly guided by his thought. It is interesting that the increase, in the course of time, of machinery in the structure of human society also proceeds in geometrical progression, just like the reproduction of any kind of living matter, man included.
>
> Statesmen should be aware of the present elemental process of transition of the biosphere into the noosphere. The fundamental property of biogeochemical energy is clearly revealed in the growth of free energy of the biosphere with the progress of geological time, especially of its transition into the noosphere.8

In this sequence of thoughts, we understand that Vernadsky, in his precise location in time, was himself the necessary voice of the biosphere giving rise to the noosphere. Put in another way, the very process that Vernadsky is describing-the transition of the biosphere to a new geological state, the noosphere-necessitated a coming into consciousness of itself, a self-reflective medium and voice. This self-reflective medium and voice of the biosphere-noosphere transition was Vernadsky


Biospheric Cycles in Relation to Earth
Showing the biosphere as a function of a unitary beogeochemical process for the furtherance of the biogenic migration of atoms and in anticipation of the biosphere-noosphere transition.
Ozone Screen
70 Miles
Stratosphere
Solar Energy
CO_2
CO_2
CO_2
H_2O
H_2O
Highest Mountain
5.5 miles
Minerals
N
Transpiration
O_2
Photosynthesis
Minerals $(CH_2O)_n$
Organic
Respiration
Precipitation
Troposphere
5 miles
Region of instability
weather changes
Volcano
Limestone
Sea level
Fossil Fuel Combustion
Urea
Evaporation
Nitrogen-fixing bacteria
Ammonia
H_2O
Ammonia nitrate
Dead organic matter
and decomposers
Photosynthesis $(CH_2O)_n$
$Ca(HCO_3)_2$
Layer of granitic rock
9 mile
H_2O
O_2
Blue-green
algae
CO_2
Ammonia
$CaCO_3$ in
calcareous
shells
Mineral Particles
Tectonic Plates
Lithosphere
21 miles
Sediments
Hydrosphere - Ocean
7 miles
Crust
40 miles
Decomposers
Magmasphere
(vitreous)
Limestone
Fossil Fuels
Minerals
Boundary of stable regions
Sima Region – Stable Dense layer-like formation
1500 miles to core

Biospheric Cycles

himself. In this observation we may understand that, although unconscious until it was made precipitant by the accelerated biogeochemical combustion itself, the order of the noosphere is none other than what the Law of Time defines as the synchronic order. As the structure of fourth-dimensional time, the synchronic order is a fluid, radial chronomantic structure in which time, telepathy, and consciousness are united in ways unpredictable to even the most advanced Western systems of mathematics.

For Vernadsky the sum properties of the elements of the biosphere are the functions both of mathematics and of different kinds of geometries. It is of note that in the summation of the differences between inert and living bodies according to three factors, the first being energy and the second chemical manifestations, Vernadsky defines the third factor as "differences in regard to space-time." Of this factor, Vernadsky writes:

> In considering space-time, however, the situation becomes rather involved. Here we enter, on the one hand, a domain not studied scientifically, and on the other hand, that substratum of all natural phenomena, namely their geometry, which the naturalist in his scientific work is wont to dismiss without attention. This substratum, the geometrical state of physical space, underlies all physiochemical phenomena and perhaps has an even deeper reality than that of the phenomena themselves.9

This deeper reality is the phenomenon of time itself, expressed through various geometries or geometrical principles, which informs the manifest phenomena of life. This is an obviously aesthetic factor as well as a cosm.Qlogical principle.

The Dynamics of Time fully substantiates Vernadsky's perception of the geometrical ordering principle of the deeper reality of time:

> All geometric forms are radiative and derive from the fourth-dimensional radial matrix. All fourth-dimensional functions are radial in nature and imply a principle of center from which the structure is projected. . .
>
> Geometry is how fourth-dimensional time incorporates as third-dimensional form. The incorporation of time as geometrical form informs all of the inorganic and organic orders of the realm of instinct. Time incorporated as the geometry of form is the principle example of $T(E)$ = Art. All forms and species participate in varying orders of geometry of form, both in their bodily structure and their forms of process.1o

If the question is asked, Where is this deeper reality of fourth-dimensional time from whence the projective geometries are generated? then we must answer that it is here in the noosphere, the medium on Earth for the transformation of cosmic thought.

It is the noosphere that informs all of the forms of the biosphere, inert and living, as well as producing in all genuine thought a structure and an order that are continuously moving in the direction of greater consciousness. To even think about the noosphere is to be a reflection of it.

As a noospheric medium, Vernadsky's life span was precisely timed to end when the global structure of the technosphere was about to be unconsciously constructed. The ingredients of the technosphere are indicated in the above-quoted passages as the planetary phenomena altering the biogeochemical history of the chemical elements, transforming them into an "immense new form of biogeochemical energy represented by the technological work of man, complexly guided by his thought." It is the increase, over the course of time, of machinery in the structure of human society that proceeds in geometrical progression-just like the reproduction of any kind of living matter, man included-and that constitutes the general nature of the technosphere. The growth of "free energy," the often toxic by-products of the industrial transformation of raw goods into consumer products, becomes the hallmark of the technosphere, the transitional stage between the biosphere and the noosphere.

It is this very point of the elemental process of the production of "free energy" and what it signifies in terms of the transformation of the biosphere into the noosphere that causes Vernadsky to call statesmen to attention. Why? As we know today, fifty-six years after Hiroshima, "free energy" in various manifestations has been causing danger signals to go off throughout the biosphere-from ozone depletion to global warming to nuclear radioactivity. What these danger signals have been telling us is that the techno sphere is coming to a point of its own exponentially accelerating biogeochemical combustion. Statesmen and politicians are advised by Vernadsky because the domain of their political rulership actually encompasses the everyday governing of the technosphere. But, alas, most people, statesmen included, are still unconscious of the existence of the technosphere, much less its role in relation to the biosphere and the forthcoming geological state, the noosphere. Hence, the Inevitable Event.

During much of Vernadsky's life, the geochemical combustion and release of "free energy" was just coming into its own. At his birth in the middle of the nineteenth century, the world was not yet globally industrialized, and without a totally globalized industrial base there can be no technosphere. The critical span of the two world wars, 1914-1945, was for the purpose of establishing the world market-a total industrialized market and communications base for the expansion of technology and the creation of the unifying global structure of the technosphere. The inauguration of the atomic age at Hiroshima, August 6, 1945, marks the precise beginning of the dual factors: the commencement of biogeochemical transmutation and combustion of the biosphere by the impact of human thought, the atomic bomb and release of nuclear radioactivity into the terrestrial atmosphere; and simultaneously, the beginning construction of the technosphere.

The bomb created a point of critical self-awareness within the human organism as well as producing in that organism an unprecedented sense of its own power. It was this sense of power that necessitated the unconscious impulse toward putting into place the structure of the technosphere. Of course, at the outset the species was only responding to a new, uncharted world situation, fundamentally unaware both of what it was creating as well as of the fact that it was actually constructing something in the nature of a transition between two geological conditions, the biosphere and the noosphere.

It could be said that Hiroshima lit the fuse of the final stage of biogeochemical combustion, the technosphere being the inevitable structure needed for the fuse to detonate at just the right moment. In this regard the synchronic order of the Law of Time ordained a precise 56-year cycle for the existence of the technosphere: 1945-2001. It is important to grasp that in this 56-year cycle the human population quadrupled, expanding from 1.5 to more than 6 billion. The 56-year cycle divides into precise subcycles of twenty-eight years each. The first twenty-eight years, 1945-1973, begins with Hiroshima and ends with the completion of the World Trade Center towers in New York City. This marks the accomplishment of the creation of the "World Market," the actual transformation of the biosphere into the technosphere. The second 28-year cycle, 1973-2001, spans from the dedication of the World Trade Center towers to their destruction by an act of suicidal planetary terror, and marks the phase of "globalization" -the absolute dominance of the materialist market economics, inclusive of the dramatic end of the Cold War in 1990. The very midpoint of the second 28-year cycle is the Harmonic Convergence of August 16-17, 1987, exactly fourteen years after the dedication of the World Trade Center and fourteen years before the inevitable moment of their destruction.

A profound statement of the way in which the Law of Time governs the entire biosphere, inclusive of the artificial and transitional structure of the technosphere, lies in the fact that the Gregorian calendar-an otherwise irregular and confusing pseudostandard of measure-is nonetheless coordinated by the Law of Time to repeat its cycle precisely every twenty-eight years. What this means is that the days of the week and months for the Gregorian calendar year 1945 repeated again in 1973, and yet a third time in 2001. The program prefiguring the Inevitable Event was already tested at Trinity Site (July 16, 1945), and established as the atomic destruction of

Hiroshima (August 6, 1945) and Nagasaki (August 9, 1945). This program of mass destruction was sublimated in 1973 as the triumphant completion of the Twin Towers of the World Trade Center, only so that in 2001 they could be the apocalyptic target of the inevitable 9-11 planetary red alert and moral emergency catastrophe, the only rival of Hiroshima and Nagasaki in fifty-six years. We shall return to this point later in our discussion on the Law of Time and the role of calendars as macro-organizing, programming factors that control the functioning of the human in the biosphere.

It is of special note that the very last work published before Vernadsky's death was the essay "Some Words about the Noosphere." In his vision, Vernadsky could hardly have conceived of what was to occur first as the technosphere. Yet, he wrote in this last essay, published 1944:

> The historical process is being radically changed under our very eyes. For the first time in the history of mankind the interest of the masses on the one hand, and the free thought of individuals on the other, determine the course of life of mankind and provide standards for men's ideas of justice. Mankind taken as a whole is becoming a mighty geological force. There arises the problem of the *reconstruction of the biosphere in the interests of freely thinking humanity as a single totality.* This new state of the biosphere which we approach without our noticing it is the noosphereY

By contrast, Teilhard de Chardin, in his most famous book, *The Phenomenon of Man* (1959), defined the noosphere as a "new canopy," a "thinking stratum" that has been unfolding since the end of the Tertiary period, and has since been unfolding discontinuous with and above the biospheric world of plants and animals. Teilhard de Chardin also speaks of "planets with noosphere," those worlds where the enlightenment of humanity has become synonymous with the life of the planet as a whole system. The one path to the noosphere defined by a scientist in Marxist Russia and the other by a Catholic biologist both point to the same radically positive end vision of the evolution of humanity, a fact that in itself is a dissolution of any kind of contradictory dialectic. Only history is governed by the merciless dialectical movement of matter and thought, rich and poor, material and spiritual. Clearly, therefore, the noosphere is beyond or after history. In this regard then, the technosphere is the concluding stage of history, to be followed by the post-historical noosphere.

The establishment of the techno sphere after his death notwithstanding, it is still important to listen to Vernadsky's idealism with regard to the noosphere: "The problem of planned, consistent activities which will aid us in mastering nature and accomplishing the correct distribution of wealth, connected with the comprehension of the unity and equality of all people, of the unity of the noosphere, is now on the agenda. . . It has become clear, and is more deeply penetrating the consciousness of mankind, that we now have a real opportunity to obliterate malnutrition, starvation, and poverty, to greatly diminish the incidence of diseases, and prolong human life to the maximum."12 Other thinkers like R. Buckminster Fuller have uttered similar statements, that we have all that is needed to adequately take care of everyone on the planet. It is important to understand why this optimism has yet failed to be substantiated. If anything, the inequality in wealth between that of the several hundred billionaires in the world and that of the poorest one-third of humanity, two billion humans, was never historically more disproportionate than it was at the moment of the Inevitable Event. This inequality of wealth, too, is a situation endemic to the very processes of the technosphere, otherwise known as the military-industrial complex.

In 1970 an American scientist, G. E. Hutchinson, wrote in the *Scientific American*, "By noosphere Vernadsky meant the envelope of the mind that was to supersede the biosphere, the envelope of life. Unfortunately the quarter century since those words were written has demonstrated how mindless most of the changes wrought by man on the biosphere have been. Nonetheless, Vernadsky's transition in this deepest sense is the only alternative to mankind shortening its lifetime by millions of years."13

A similar assessment was put forward in 1979 by the Belgian ecologist P. Duvigneaud in his presentation "Noosphere and the Future of the Vegetation of the Globe." In his address regarding the extermination of natural ecosystems made to the Twelfth International Botanical Congress, Duvigneaud makes one of the earliest and most prescient uses of the word *technosphere:* "Thus, the noosphere, so dear to Vernadsky . . . is running the risk in reality of turning into the technosphere, or rather into 'the sphere of avidity,' governed by the spirit of fortune-hunting, by mediocrity, by the absence of social consciousness, by the ideal of destruction and by the egotistic doctrine of 'after me, the deluge.'"14

To be precise, it was in 1973, the same year of the Club of Rome's landmark publication *The Limits of Growth,* and of the establishment of the World Trade Center in New York, that the technosphere became a coherent structure smothering the biosphere, co-opting the noosphere, and coordinating the very processes of greed and destructive fortune-hunting abhorred by the ecologist Duvigneaud. Like it or not, the techno sphere was the inevitable result of the unloosing of the machine into the biosphere. It may be asked: if the machine is a projection of human biology, then what purpose does it actually serve in the biosphere, and what is it that actually produced it and keeps it going?

Before turning our attention to the answers to these questions, let us first define the technosphere as being the artificial structure replacing the human civilization,


Electromagnetic Field
Radiation Belts
Ionosphere
Stratosphere
Troposphere
Atmosphere
Biosphere
Technosphere
Hydrosphere
Crust
Tectonic Plates
Outer Mantle
Inner Mantle
Tympanum - Inner Mantle
Core
Octahedron Iron Crystal

Earth's Mantles

located mentally and physically *in time* as a force intermediate to and between the biosphere and noosphere. Defined by the *Biosphere Catalogue* (1985, p. 103), the artificial structure of the technosphere consists of five interlocking, coordinated systems that comprise an integral whole, both as a belief system and as an actual complex technological dynamic and its coordinating apparatus. The five components, which we shall discuss at length in later chapters, are: 1) commodity production, 2) the city, 3) energy, 4) transport, and 5) communication. And, according to the *Biosphere Catalogue,* the planetary core of this interlocking set of systems was none other than the World Trade Center's Twin Towers.ls

As a planetary sphere, the technosphere takes its place with the other spheres or mantles comprising the structure of the Earth as a whole system. Beginning at the outermost etheric realm and proceeding inward, these spheres or mantles include: the electromagnetic field with its radiation belts, then the ionosphere, stratosphere, troposphere, atmosphere, technosphere, biosphere, land-ocean crust, tectonic plates, lithosphere, outer and inner mantles, and finally the core, now known to consist of an outer tympanum, and within it a large octahedral iron crystal afloat in a sea of magma.

As a planetary sphere, the technosphere negates time and consciousness as organic realities and replaces them instead with mechanization and marketing. Yet the technosphere is a product of mankind, and mankind is a function of the biosphere. The organization of life into biomes, large macro-ecosystems, is still evident, though in diminishing and withering proportion to the conquest of the technosphere. With the Final War now upon us, the question we must ask is: will the technosphere collapse before the biosphere or not? As catastrophic as it might seem, the collapse of the technosphere would actually be a blessing in disguise from which the noosphere could finally be realized. But if the biosphere collapses first as the result of the Final War on Earth, then the technosphere will be futile, pointless, and dead as well. These are most dire thoughts in these most dire of times. Yet if we can now finally understand and accept our role within and subordinate to the biosphere as a whole, then our chances for survival will be greatly improved.

Let us consider again what Vernadsky has to say about the human's place in the biosphere:

> 1. Man, as observed in nature, like all living organisms, like any living matter, is a specific *function of the biosphere,* within its specific definite space-time.
>
> 2. Man in all his manifestations constitutes a regular part of the structure of the biosphere.
>
> 3. The *explosion* of scientific thought in the twentieth century *has been prepared for by the entire history of the biosphere* and has its deepest roots in the structure of the latter. The civilization of "cultured mankind," insofar as it is a form of organization of the new geological force which has formed in the biosphere, *cannot be interrupted or destroyed,* since it is a great natural phenomenon, historically, or rather, geologically corresponding to the established orderliness of the biosphere.16

If Vernadsky is correct, then the war we are witnessing is the inevitable conclusion of the biogeochemical combustion that consumes the technosphere and establishes the pristine reality of the noosphere. This is especially true if we understand this war to actually be a geopolitical struggle for the control of the oil reserves of the Persian Gulf, or even more broadly, as the war between matter (globalization) and spirit (Islam), or more grimly, as Oswald Spengler put it, the final war between blood and money. This being the case, it is more important than ever to answer the two unresolved questions in Vernadsky's definition of the biosphere, the question of consciousness and the question of time.

According to the Law of Time, the answers to the questions posed by Vernadsky are actually one and the same thing. "How can processes which seem purely physical be affected by consciousness?" The question asked by Vernadsky at the conclusion to *The Biosphere* is equaled by the unresolved issue of time discussed at the conclusion to *Problems of Biogeochemistry* JI.1n essence, Vernadsky declared, we know everything about the biosphere, its governing laws, principles, and functions, with the exception of the mysterious relation of time to the biosphere. Virtually alone among modern scientists, Vernadsky perceived that time actually has nothing to do with the metrics of space, and that "time is not a dimension of metric geometry." This means that time is not only its own dimension-the fourth dimension-but that time must also have its own metrics and system of measure totally apart from the metrics of space.

> Minkovsky's and his predecessors' concept of time as the fourth dimension of space is a mathematical abstraction having logically no ground in scientific reality. Time is not a dimension of metric geometry. In geometry, time may be expressed vectorially, but it is obvious that such an expression does not embrace all of its properties in natural phenomena studied by the naturalist. . . The time of the naturalist is not the geometrical time of Minkovsky, nor is it the time of mechanics and theoretical physics.[I?]

In Vernadsky's perception of time, there is a profound critique of the approach that has been established toward the measure-and hence understanding-of time in physicalist science. For Vernadsky, time is a function of an as-yet-unrealized geometry: "This geometry would reduce all space to a point supplied by an infinitesimal vector." Clearly time is a factor in all the functions of the biosphere, most evident in the biological life processes. Hence the Law of Time has been a regulating factor, the true nature of which we have been profoundly unconscious. Now here is an interesting reflection. If the biosphere as a whole system is tending toward a total whole system transformation into a state known as the noosphere, a fact perceived by Vemadsky during his lifetime, and the two unresolved issues are the issues of time and consciousness, both materially intangible dimensions, does it not seem correct that the resolution to these two issues will actually foster the manifestation of the noosphere, which is, after all, the mental envelope of Earth? And does it not also seem that as long as the two issues of time and consciousness remain in a state of ignorance or confusion within the mental functioning of the human order, that the vehicle of geochemical combustion, the technosphere, will tend toward its own dissolution until the issue of time and consciousness is resolved and clarified once and for all?

The perilous passage, the biosphere-noosphere transition, may actually be defined as the consequence of operating in ignorance of the actual nature of time and consciousness. In this way, the techno sphere may be defined as the artificial compromise in place of the true understanding of time and consciousness of the human order in the biosphere. Hence, the technosphere is the responsible intermediary agent creating the crisis of the noosphere. The solution to the questions of time and consciousness is thus the solution to the noospheric crisis, and the commencement of the grand new era, the true golden age of the whole Earth.

◆

3

Time and Human Consciousness

The Law of Time—What It Is and Where It Came From

HAVING DEFINED the technosphere as the intermediary stage in the biogeological continuum of the biosphere's evolution into the noosphere, we may now turn our attention to the unresolved issues of time and consciousness in the biosphere. These issues must not be seen as just the problems of humanity. Since humanity is a function of the biosphere, the issues therefore relate to the biosphere becoming more conscious. It is the conscious aspect of matter that directs the biosphere toward its transformation into the noosphere. It is the discovery of the Law of Time that complements and resolves the issues that were left unresolved in Vernadsky's definition of the biosphere and of its transformation into the noosphere. The question then arises: what is the Law of Time, and how does it define time and consciousness as mutually coordinating factors of the same cosmic dimension intersecting with the biosphere?

To say the least, time is such a vast and important topic in the orientation of human consciousness within the biosphere that we may declare that it is paramount in all human affairs. Indeed the cosmic order, of which the biosphere is the dynamic regulatory mechanism on planet Earth, is itself the expression of time as the medium of universal manifestation. Yet, as Vernadsky perceived in 1944, while we have defined space by its own systems of metrics and geometries, by applying these same standards to time we have not defined or known time at all. The cause for this quandary seems to lie in the fact that while space is perceptible as a sensory medium-we can see it, touch it, hear through it-and hence, it is evidently measurable, the same is not the case with time. Time is of the mind, and in this regard, time is inseparable from the issue of consciousness. In fact, you cannot know or experience time without becoming conscious.

Yet, as we shall see, there is a great confusion when we speak about time, which is actually at the root of the problem of the biosphere, and that is the matter of the clock. In human consciousness, the clock has become so second nature that very few people in industrial society can think of time without immediately associating it somehow with the clock, whether as an instrument or as a metaphor. This, as we shall see, is a major factor causing the general state of consciousness to remain static, especially in relation to the machine, which is continuously increasing in speed, as well as accelerating in the propagation and multiplication of itself. This factor of the clock-in other words, of mechanized time-is also at the root of the confusion concerning the nature of time in much of modern scientific thought. As we shall see, there is a stream of Russian thought after Vernadsky that represents a notable exception to the established view of time in modern thought and science. Suffice it to say that the evolution of modern Western thought and science has been programmed and predisposed to limit its consciousness of time to such a degree that it cannot even perceive of time outside its inherently mechanized perceptions about it. In this obviously also lies the problem of the delimitation of consciousness in the technosphere.

"The deepening crisis of the world outlook is rooted in the permanence of the dominating scientific paradigm," writes Russian scientist Maria Maroushkina. "Underlying the materialistic technocratic civilization is the Newtonian-Cartesian paradigm, formed in the Middle Ages, its nucleus being the laws of gravitation and movement, as well as the logical principles of proof, laid down by Descartes."! This "permanent" stratum of belief, a cultural metaprogram, locks every field of human endeavor into a conquest by mechanization. It is this metaprogram rooted in the simple unexamined device of the clock, and orchestrated by the equally unexamined effects of an irregular calendar, that keeps human consciousness unchanged and without any real solutions to its problems. As the problems worsen, the confusion of consciousness-which is really in a state of crisis-only deepens.

To illustrate the current state of confusion regarding time in Western thought, we have the report of the prestigious Seven Pines Symposium on Time held in Stillwater, Minnesota in June, 2001. The *New York Times* article regarding the Seven Pines Symposium is entitled "Physics' Big Puzzle Has Big Question: What Is Time?"2 First of all, the assumption that time is basically a topic of physics in itself is a problem, since time, as we have demonstrated, is actually mental in nature, and if any-



"Arrow of time" in modern scientific three-dimensional coordinate graphing, reinforcing illusion of linear time.

Arrow of Time

thing is most visibly manifest in the domain of biology or biogeology. But this headline is also reflective of the paramount role that physics plays in the Western intellectual hierarchy: if physics can't solve it, than what can?

Despite the prominence of physics and physicists, the Seven Pines Symposium included historians and philosophers as well. The hope of the symposium was to arrive at a unified theory that encompasses the effects of gravity as described by Einstein's general theory of relativity and the "fuzziness that occurs in the realm of tiny particles according to quantum physics."3 Here we have the problem of time as delimited by the self-imposed spectrum of modern physics. What then could we expect? Certainly no one here had considered the point made by Vernadsky that time is not a function of the metrics of space, which is the realm of physics. So it is not surprising that the symposium ended in a muddle, with the most prominent approach being that time could merely be a "psychological illusion" important to humans but not a fundamental part of any unified theory. It is also clear that few, if any, had considered that their views on time might be absolutely conditioned by the mundane and ordinary everyday micro- and macro-organizing factors: the mechanical clock and the Gregorian calendar with its second cousin, the Julian count of linear time.

From the point of view of the noosphere, of course, this grand Symposium on Time was reflective of very little of the entire human organism, much less of the biosphere itself. The symposium was a representation of the elite intellectual class of the dominant economic, military, and political power of the planet, and hence of the governing force of the technosphere, the United States of America. But if a realization that we are a function of the biosphere is critical to our success in launching the noosphere, and the issue of understanding the correct relation of time to the biosphere is crucial even to the ability to launch the noosphere, then the Seven Pines Symposium did not even approach the actuality of the current biospheric situation or the nature of time. In this regard it was only a contribution to further the psychoatmospheric density-clouded thought without clarity of purpose-and one more reason why the Inevitable Event was on the biosphere's agenda.

If one does not apply certain biospheric yardsticks to the analysis of what is reported as truth, then we will be sunk in a chaotic morass of half-truths that are really obscurations or even lies. The elite American nation, for instance, constitutes only 5 percent of the world's population, yet consumes 40 percent of its natural resources, and therefore has the wealth and power to maintain the military force (allotted a $318 billion budget for 2001-2002) to protect and even further as its right this disproportionate ratio, which is actually a violation of the dynamic balance of the biospheric processes. For this reason, through its official organs of propaganda such as the *New York Times,* America is able to muster the "influence" of whatever occurs within its confines as somehow having more merit than what might be generated in some other nation or country. So a human may read the story in the *New York Times* on the "Big Puzzle of Time," and most likely they will complacently accept its premise as absolute truth. Yet this social construct of symposium-and-newspaper-story is nothing but an aberrant mental form that obscures the actual nature of time and keeps the mental level at a constant state of "industrial dull-normal," far removed from-or at best, little more than a highly distorted reflection of-the reality of the noosphere.

Leaving aside this example of the mental confusion over time, it is necessary to understand from the investigations regarding the biosphere and according to Vernadsky's own judgment, that the biosphere in all its intricate and interlocking processes possesses and is guided by a great order and even a structural dynamic that, being manifestations of the laws of nature, can be given exact mathematical formulation. Why should we not expect that the nature of time in the biosphere should also be characterized by the same orderly quality? In fact, given that the biosphere is actually a life process, like all living matter it too must be governed by timing cycles. Thus the larger order of time that governs the cycles of the biosphere and of the noosphere must also exhibit a grand ordering principle. For if the three dimensions of space govern the domain of the physical world, then the fourth dimension of time-which governs the life not only of the biosphere but of planets, star systems, whole galaxies, and indeed the entire universe-must also consist of a simple, orderly formulation totally apart from the perception of time that governs the stunted consciousness of the technosphere. Such is the Law of Time.

THE FOURTH-DIMENSIONAL NATURE OF TIME

> *"Even though you do not measure the hours of the day as long or short, far or near, you still call it twelve hours. Because the signs of time's coming and going are obvious, people do not doubt it. Although they do not doubt it, they do not understand it. Or when sentient beings doubt what they do not understand, their doubt is not firmly fixed. Because of that, their past doubts do not necessarily coincide with their present doubt. Yet doubt itself is nothing but time."*
>
> -DOGEN, "THE TIME-BEING"4

These prescient words of a thirteenth century Japanese Zen master are more true today than they were when he wrote them. Comprehensive studies like the *Eranos Yearbook III: Man and Time* (1957), which included Carl G. Jung's ground breaking essay on synchronicity, or James T. Frazier's fascinating and monumental *Voices of Time* (1966), only expand the multidisciplinary breadth of the confusion about time. In the 1970s Frazier helped found the International Society for the Study of Time. The Society is still meeting annually but has yet to reach a definitive agreement on or understanding of the question of time. It is in the context of the enduring confusion over time that the Law of Time was discovered. To say that the Law of Time has been "discovered" only means that a principle and fundamental law that has always guided the order of the universe has finally been made conscious and articulated in a precise way that is recognizable to the present condition of the human mental nature, which is still dominated by the physicalist model.

In the whole of modern physics, Minkowski's fourth dimension of time has been misunderstood and treated as if it were a minor dimension, one that is just added on, but not really significant to the level of the three dimensions of space. This is due to the already space-oriented consciousness deriving from certain sets of perceptions established early in the history of civilization and standardized through certain programming models that are based on the metrics of space and not time, a topic to which we shall soon turn. It is for this reason that in the formulations of modern physics time is symbolized by a small *t* that runs in a horizontal line running from left to right at the bottom of any graphing of space with its *x* and *y* coordinates.

This graphing of small *t* time gives rise to the notion of the "arrow of time," which is virtually a bedrock dogma of much of modern Western physics. This is the much-touted notion of linear time that supports doctrines of economic inexorability, material progress, and the like. Of course to anyone versed in the ways of nature, linear time and the arrow of time can be seen as nothing more than artificial constructs, for the biological nature of time is perceptible at the very least through the great interlocking cycles of nature. Nor is there anything linear about the Earth's rotations around the sun, or of the moon around the Earth, all of which give lie to the physicalist and materially progressivist notion of linear time. Only the technosphere, sustained in its structure by the limited consciousness of time, is driven by this linear principle and for this reason is doomed to run aground on the shoals of its own artificiality.

TIME AS THE UNIVERSAL FACTOR OF SYNCHRONIZATION

The nature of time is grasped poetically in the form of cycles: "To every season there is a time. . ." Biorhythms can even be mapped and the cycles of the biological order of reality can be demonstrated as functions of a chronobiology. But the biological cycles only demonstrate the manifestation of time in the space ofliving matter. If the whole of nature is observed, then one can begin to grasp the masterful orderliness by which every least detail occurs in relation to all the other details in their various cycles-yes, one can grasp in this phenomenal order another deeper aspect of time, and that is time as the universal factor of synchronization. This is the synchronic order of time, the order by which everything in the universe occurs simultaneously in a masterful synchronization from moment to moment in an ever-changing kaleidoscope of infinite varieties of order and harmony.

Only historical man deviates from this masterful symphony of time, the synchronic order. Nonetheless, we speak of being "on time," "in sync," "in tune," "in resonance," "in harmony," or of being "tuned-in." All of these expressions refer to the attunement of time and the nature of consciousness as awareness in the present moment, in the here and now. This is possible because the same law governs both time and the relation of consciousness to the moment. To answer Vernadsky's question, "How can processes which seem purely physical be affected by consciousness?"- the physical is affected by consciousness, because consciousness is actually a function of time. When someone "discovers" a law of nature, it is because their consciousness is attuned to the natural process in time, and the law therefore "reveals" itself.

But this consciousness can be and most often is of a profoundly unconscious nature. Time is actually the governing principle of a higher self-existing consciousness that regulates the order of the universe, both in regard to its living and non-living matter. Because time continuously synchronizes everything into a single coherent whole from the micro to the macro levels, time accounts for the harmony of the universe. Only man deviates from the universal harmony, and the technosphere, a projection of the human mechanization of time, intrudes upon the intrinsic harmony to the point of its own demise, but man deviates for a purpose.

The harmony manifested by time as cosmos-which literally means "order" -gives rise to the great and simple formulation of the Law of Time: T(E) = Art; Energy factored by Time equals Art. This means that energy, any manifestation of the physical three-dimensional world, possesses order and is in harmony with its environment because it is factored by time. In the conception of the Law of Time, however, capital *T* refers to time as the universal factor of synchronization. As the universal factor of synchronization, time is defined by the self-existing and intrinsically perfect mathematical ratio 13:20. Derived from the mathematics of the ancient Maya, this ratio is a universal constant of time that organizes all of the universe as a radial sequence of synchronous moments reflecting different evolutionary phases simultaneously. Because everything perceived is an aspect of instantaneous universal synchronization, time is also the medium of instantaneous information transmission throughout the universe.

The noted Russian astrophysicist N. A. Kozyrev (1908-1983), whose work began half a century ago with the theory of the internal structure of stars, later conducted a famous series of experiments using telescopes, mirrors, and aluminum, in which he was able to confirm a receipt of information from distant galaxies prior to the time it took the information to arrive via light as a physical medium. In Kozyrev's own words: "The tests proved the existence of the effects through time of one material system upon another. This effect does not transmit a pulse (momentum), meaning it does not propagate but appears simultaneously in any material system. In this manner, in principle it proves possible to have a momentary relationship and a momentary transmission of information. Time accomplishes a relationship between all phenomena of nature and participates actively in them. . . . Time contains the entire universe of still unexplored phenomena."5 The results of these experiments led Kozyrev to various conclusions, among them that time and duration are not the same thing, and that the velocity of time is instantaneously infinite, formulated as

$$T_V \rightarrow \infty$$

Formulation: velocity of time is instantaneously infinite

This being so, time must also be the factor or medium that accounts for the experiences of telepathy or other paranormal phenomena. A second, most provocative conclusion derived from his experiments is that time is actually generated as an instantaneous and even simultaneously radial transmission of information from the core of stars, a fact confirmed by the Law of Time's description of the synchronic order of time as being radial in nature.

FURTHER EXPANSES OF FOURTH-DIMENSIONAL TIME: THE EVOLUTION OF TIME AS CONSCIOUSNESS

Leaving aside for the moment further discussion of Kozyrev's seminal work and its conclusions, at this point let us summarize the two chief qualities of time as defined by the Law of Time: 1) time is the factor of universal synchronization, and 2) time possesses an infinite instantaneity of velocity that is faster than the speed of light, and hence is correlated with telepathy. From these two determining features of the nature of time, two other corollary conclusions may be drawn: 3) the cyclic nature of third-dimensional biological phenomena is a function of the factor of universal synchronization which establishes harmonic ratios that determine the different life processes of different organisms, while 4) the ability of any species or organic whole to maintain its unity with itself and all of its members or parts is an instantaneous function of time as telepathy.

To better understand the Law of Time and its radical non-linear definition of time-which is actually the noospheric description of time-we may say that time, being synchronically instantaneous, is both "vertical" in relation to space (which is "horizontal"), and "radial" from the perspective of its own dimension, the fourth. Rather than being the small *t* line or arrow at the bottom of the physicist's graph, time as the fourth dimension is greater than and inclusive of the third dimension, much as the etheric atmosphere includes and surrounds the physical Earth in a radial "all-at-onceness." To try to measure this phenomenon with the metrics of space and its essentially linear yardsticks is to constrain time into definitions and descriptions that are totally alien to its nature.

In fact, from the point of view of the dynamics of time, it is space that is the moving line, or rather a set of points in a moving vector that can be described as line. Let us extrapolate from the important observation made by Vernadsky at the conclusion to *Problems in Biogeochemistry II:* if the geometry of time reduces space to a point supplied by an infinitesimal vector, then from the point of view of time, space is an infinitely locatable point. What is this point? It is the point of awareness at which an individual body becomes aware of time. Here, the "subjective" description or experience of time cannot be separated from the issue of consciousness. (See plate 3, Model of "Vertical Time" in Relation to Horizontal Space.)

In the description of time as vertical in relation to horizontal space, this point of awareness of a body in time is defined as the Locus of Consciousness, or L of C. In the flow of moment-to-moment instantaneity that is synchronous with the flow of space, the Locus of Consciousness is that point at which time vector and space perception connect. From this defining point of consciousness in the here and now, the flow of space creates a horizontal sensation: one direction flows to the "past," the other to the "future." This is what is normally defined as the sensation of time or the arrow of time. It is actually the definition of the horizontal flow of space in relation to vertical time. What is usually not considered is the vertical dimension of time that connects awareness to space at any given moment, creating sequences of Awareness Units, or AUs.

From the defining point of the Locus of Consciousness, there are essentially two spaces and two times: *near space* and *far space,* and *low time* and *high time.* Near space corresponds to low time and far space corresponds to high time. Near space is essentially defined by the perimeter of sense experience, inclusive of the extension of the senses through technological apparatus such as telescopes, microscopes, and the like. This is the domain oflow time. Far space is defined as that space beyond the perimeter of the sense perceptions, and is characterized by subliminal sensory perceptions. This is the domain of high time and the atemporality of space. In near space, low time is characterized by what appear to be "random events." The lower the time, the greater the increase of random events. Low time and near space define the qualities of the experience that are properly and purely third-dimensional. High time and far space are purely and properly the domain of the fourth dimension characterized by the dominance of the synchronic order of time.

The distinction between low time and near space and high time and far space is defined as the threshold of synchronicity. In high time, synchronicity (s) predominates and is greater than random events (re), or (s»(re). In low time, random events predominate and are greater than synchronicity, or (re»(s). Note that the realm of quantum physics occurs in the microrealm of far space. It is this factor that accounts for the "fuzziness" of the behavior of subatomic particles, quarks, tachyons, and so forth, which defy the limitations of linear time. These phenomena occur in the subliminal realm of the synchronic order. It is the human mind that is not accustomed to behavior in the pure realm of synchronicity that cannot grasp that these particles are moving according to radial laws of fourth-dimensional time, and so appear highly irregular and random to the sense perceptions of the observers that are totally conditioned by third-dimensional space perceptions. Similarly, the high time of the macro threshold of the synchronic order represents the "other side," the "hereafter," the realm of pure vision, which is also governed by strict laws of radial time, and which, to the conditioned experience of a perceiver on this side of the threshold, may appear as something from a distant future or past reality, or even as in a dream. The orderly explication of the Law of Time provides complete mathematical descriptions and principles that account for the radial order of time, even as it coordinates the near space and low time of random events.

In any case, the horizontal line of space in relation to the vertical line of time defining any given Locus of Consciousness describes the macroworld above and the microworld below. As we have noted, the higher threshold of synchronicity above the horizon of space defines the realm of *higher consciousness*; the lower threshold of synchronicity below the horizon of space defines the realm of *quantum physics.* Connecting the macro realm of atemporality and high time, and the lower or micro realm of atemporality and high time, is the vertical time vertice of the ever-present now. At the two far ends of this time vertice of the ever-present now is the Locus of God, the selfsame in each direction. These extreme points of the vertice of time return far space to the Locus of Consciousness through a process of toroidal sublimation. We are not really dealing with a description of a two-dimensional plane, but a dynamic four-dimensional model held together by a toroidal motion that is continuously returning the farthest space and the highest time, whether from above or below the threshold of synchronicity-" God" -to the Locus of Consciousness.

Depending on the clarity of mind at any given moment, the vertice of time constantly and instantaneously transmits information to the Locus of Consciousness. The discrete units of information thus transmitted are referred to as *celestialharmonics.* A celestial harmonic is described as the index of synchronic incidence defining different levels of co-occurrence. I can be in the present moment sitting in a room, and at the same time, by being fully present in the here and now, I can spontaneously experience any number of telepathic thoughts, memories, feelings of deja vu, and so forth. These experiences are the different levels of co-occurrence that define the index of synchronic incidence and are categorizable as celestial harmonics. The higher the time, the greater the density of celestial harmonics per AU (Awareness Unit). It is the vertical vertice of time and its power of transmission that account for the visionary or revelatory experiences of saints, poets, and mystics throughout the ages. It is the mathematics of the Law of Time that provides the "mapping" that explains, identifies, and even increases these different harmonic incidences of the synchronic order.

Because the vertice of time connects ultimately to the "Locus of God" -the mutually defining points that become One at the far ends of the toroidal motion of the vertex of time-this accounts for the existence of the *perennial philosophy*, the unitive nature of the most revelatory or ecstatic experiences of the great mystics and seers. It is also the relation of awareness in the Locus of Consciousness at any present moment that allows any random event of low time to trigger telepathic ascent into high time depending on the clarity of and duration of the Awareness Unit (AU). From this point of view, the random quality of events in near space is only relative in relation to the absolute nature of the synchronic order, and merely a function of the third-dimensional biological space orientation. For those accustomed to the actual nature of fourth-dimensional time, which includes and controls the third-dimensional order of near space, the random events constituting low time are actually "signs" that may be read as message bearing signals of the synchronic order of high time.

Brief reflection on this description of vertical time in relation to horizontal space will demonstrate the value of what is referred to as *meditation without an object* such as that cultivated in the Buddhist traditions, as well as affirm the One Divine Source of the purely monotheistic traditions. Without a clear mind of awareness in the present moment there can be no clear seeing of reality, nor can there be the realization that all of what our senses report to us is constructed in our own mind to conform to what we think is a universe outside of us. At the same time, if we can extend the duration of our awareness in the Locus of Consciousness indefinitely in the vertical direction of time, we come upon the ineffable experience that is an emanation of the Locus of God, however or in whatever "language" our senses may later report or define such experiences. Thus we return to the paradox of the definition of space as an infinitely locatable point-this point is none other than our own minds, in which the construct of space is created and dissolved from moment to moment. Such is the subjective description of time from the point of view of the Law of Time, a description that begs each one of us to take absolute responsibility for our own experience. But there is an "objective" description as well, in which time is also defined as inseparable from consciousness.

Implicit in the subjective here-and-now description of the experience of time is the radial matrix of time. At the experiential level it is the now-centered point in the Space-Locus of Consciousness which defines the center of a radial order of time.

Time radiates out from each here-and-now awareness moment. But the Law of Time also supplies an objective description in which the radial nature of time has two points of determining order: the point of infinite lucidity and cosmogenesis, which is the Locus of God; and the receptive locus of the infinitely locatable point, which is space as constructed by each individual consciousness. Intermediate between the two points-Locus of God and Locus of (individual) Consciousness-is the determining radial matrix of fourth-dimensional time, the universal frequency of synchronization.

Mathematically defined as the ratio 13:20 and described by the 13 x 20 matrix of the Harmonic Module, in this mathematical model of fourth-dimensional time we perceive the root of the Law of Time and its basis in the mathematics of the Mayan time science. It is important to understand very clearly that the 13:20 frequency and the mathematical matrix that defines the operations of this frequency of synchronization are the pure mathematics of time totally apart from the metrics and geometries of third-dimensional space. This is a point of profound significance to which we shall later return.

In the model of objective time, the dynamics of the Law of Time are demonstrated as the evolution of time as consciousness. Here the two unresolved issues of Vernadky's description of the biosphere are unified, the answers to which are the determining factors that allow the triggering of the noosphere: The evolution of time is inseparable from consciousness. Conversely, the evolution of consciousness is inseparable from time. Both time and consciousness are nonphysical fourth-dimensional factors coordinating the third dimension. Because consciousness is synchronized with or by time, it can affect physical third-dimensional processes, in whatever way, whether the acting agent is aware of this or not. Consciousness of the Law of Time, however, is only possible through a profound act of self-reflection. Once it has been made conscious, the discovery of the Law of Time affects the entire medium of planetary consciousness, the noosphere, at first imperceptibly, but then building to a great point of climax coinciding with the climax of the biogeochemical combustion. (See plate 4, The Dynamics of Time: Showing the Evolution of Time as Consciousness.)

This dramatic moment of the discovery of the Law of Time is evident in the graphic description of the dynamics of time, showing the evolution of time as consciousness. The dynamic of the universal, cosmically intelligent, and intelligible whole-the *galacticbrain-is* depicted as a circle encompassing the evolutionary spectrum, showing the index of energy-mind progression from the atomic cellular and biological levels to purely mental conditions of being, all of which are functions of the formulation T(E) =Art. From the point of God-Galactic Ordering Dynamic-the circle, or rather, sphere, is divided vertically and horizontally into four quadrants. The movement of the evolution of time as consciousness travels out of the God center, from right to left, and thence describes, in counterclockwise circular motion, the movement of time as consciousness passing through, or rather defining, the four quadrants, until it returns to the Source again as hyperdimensional time, or "pure mind." The left-hand side describes both the primary prelife, lower left-hand quadrant, and the primary post-life, upper left-hand quadrant. The right-hand side describes the secondary reflex life, the lower right-hand quadrant being the purely third-dimensional life (biosphere), and the upper right-hand quadrant being the evolved fourth-dimensional life (noosphere).

The lower half of the sphere beneath the horizontal line running through the God center refers to the Domain of Potentiality, the upper half to the Dominion of Time. The prelife quadrant of the Domain of Potentiality refers to the preconscious quantum dimensional space of pure energy. The lower right-hand quadrant refers to third-dimensional space, the locus of space travel and the realm of the cosmic unconscious. Within the Dominion of Time, the upper right-hand quadrant refers to the fourth-dimension time, the locus of time travel, and the realm of cosmic consciousness. Finally, the upper left-hand quadrant is the realm of hyperdimensional time, or "pure mind." By studying this graphic description, one can grasp the movement of time as consciousness from inorganic preconscious, where duration in time is virtually infinite, to the secondary reflex life, or living organic matter in the third dimension. Here time is unconscious and life builds on the cosmic unconscious as the slowly mutating and evolving biosphere. The cosmic unconscious comes to a climax in the creation of the 12:60 artificial civilization, which is really not true civilization, but rather the technosphere itself. At this point there are moments of consciousness, but only moments. True sustained consciousness is possible only in conditions removed from the technosphere.

In the evolution of time as consciousness, the discovery of the Law of Time is a product of the crisis of consciousness unable to sustain itself in the technospheric medium. That is because this medium is a pure function of artificial 12:60 time. Even though the extensions of the senses and the capacity of technology provide the human within the biosphere a holistic perspective of seeing the whole Earth from space, the consciousness is continuously subordinated to the care and maintenance of the machine (or its lifeblood, money), and so cannot remain in a sustained state of heightened awareness or continuing consciousness. Continuing consciousness is only possible with the discovery of the Law of Time, which the crises of the technosphere and of consciousness have themselves brought about. In this regard, the discovery of the Law of Time is the great point of human self-reflection that defines the advance from an exclusive third-dimensional operation and aberrant timing factor to a purely fourth-dimensional and conscious natural timing factor. It is the difference between the cosmic unconscious and cosmic consciousness, the biosphere and the noosphere-in other words, the very topic of this book.

DE CHARDIN AND THE PLANETIZATION OF CONSCIOUSNESS

The discovery of the Law of Time defines the point between the two stages of the noosphere as described by Pierre Teilhard de Chardin: "The first stage was the elaboration oflower organisms, up to and including man, by the use and irrational combination of elementary sources of energy received or released by the planet. The second stage is the super-evolution of man, individually and collectively, by the use of refined forms of energy scientifically harnessed and applied in the bosom of the Noosphere, thanks to the coordinated efforts of all men working reflectively and unanimously upon themselves. . . In becoming planetised humanity is acquiring new physical powers that will enable it to super-organize matter. And, even more important, is it not possible that by the direct converging of its members it will be able, as though by resonance, to release psychic powers whose existence is still unsuspected?"6 The identification of telepathy with the velocity of time emphatically underscores de Chardin's final point.

On the other side of the discovery of the Law of Time, civilization, having reached its climax as the technosphere, is replaced by an entirely new noospheric order of human organization defined as PAN: Planet Art Network. This is a structural definition of what Teilhard de Chardin refers to as the "planetization of consciousness." This organization (bionoospheric and not institutional) is "planet" because the human organism is self-realized as a planetary organism. It is "art" because functioning again in the natural timing frequency, the human is governed by the Law of Time, T(E) = Art, and hence the reality and the activities of everyday life are defined as art. And it is a "network" because the city, defined by civilization (literally living in cities) and which was a sustaining component of the technosphere, is no longer necessary or viable. Rather, the human becomes redistributed throughout the biosphere-what Teilhard de Chardin refers to as the "radiation of man "--connected by a telepathic network that greatly diminishes the reliance on much of the technology that characterized the technosphere. Hence Planet Art Network: the replacement of civilization with the fourth-dimensional social organization of the human functioning as the telepathically coordinating species of the noosphere. In this condition life evolves toward a hyperorganic stage, attaining a state of superconscious activity and self-reflection where time travel replaces the space travel of the phase known as civilization.

This evolutionary mode, coinciding with the evolving needs of the local star, conduces at some distant point in the future to the subliminal consciousness and the postorganic postlife that is necessitated by stars as they advance to the stage of supernova. According to the Law of Time, the nature of consciousness is actually a function of stellar evolution, planets being but harmonic nodes in greater heliospheric fields of resonance. Since time is inseparable from consciousness, this understanding would seem to affirm Kozyrev's hypothesis that time is generated from the stellar core. "Stars absorb energy from the motion of time," declares Kozyrev, "a star seems to be a time machine."7 *The Mayan Factor* further places the coordinating medium of time as emanating from the core of the galaxy, Hunab Ku, One Giver of Movement and Measure. In the Chilam Balam prophetic tradition, Hunab Ku is also the name given to the final religion of the One God that appears after the religion of the *conquistadors* has finally passed. Seen from the perspective of the Galactic Brain, the crisis through which we are now passing is but the final stage before consciousness bursts into a new radiance of biosolar-telepathic wonder where negative emotions and thought forms no longer have any place to cling or hide. The Law of Time purposively points to this great end.

The whole of the spectrum of the Galactic Brain is mediated by the universal frequency of synchronization, mathematically modeled as the 13:20 matrix, the organizing factor of the synchronic order. The technicalities of this evolutionary spectrum of the Galactic Brain have been defined in *The Dynamics of Time: 260 Postulates* (1996) so that the process of the evolution of time as consciousness may be studied and its coming stages prepared for. The mathematical model of this 13:20 matrix is a description of the fourth-dimensional timing frequency and is both the source of the time vector potentialities and the mathematical tool for mapping the order of synchronicity. Through the discovery of the Law of Time, the 13:20 matrix is realizable through tools that are in accord with its mathematics, and thereby it becomes useful to the everyday consciousness of the human. This too becomes a factor accounting for the noosphere's becoming conscious.

The fourth-dimensional "tools" made accessible through the Law of Time include the Thirteen Moon/28-Day calendar, the Dreamspell, and the Telektonon. They will be described more fully in Chapter 8, "Making the Transition to the New Time." With these tools one can begin to construct a map of the time vector potentialities contained in the synchronic order as it manifests on a day-to-day basis. Once the construct is made conscious and correlated to a point in third-dimensional time, then the body in time-the infinitely locatable point that is space-may be coordinated by the same common structure of fourth-dimensional time. Following this procedure the individual human consciousness begins to participate in the larger unfolding of the noosphere, and slowly but surely is realized as yet another manifestation of the formulation of the Law of Time, T(E) = Art. It is the human being itself that incorporates time, or rather wakes up within itself the order of time. Time is art, while art is actually a function of consciousness expressing itself.

THE MAYAN UNDERSTANDING OF THE LAW OF TIME

While we will have cause to turn our attention later in this book to the "how-to" of fourth-dimensional time, we may consider further the nature and meaning of the mathematics of the Law of Time and their origin with the mysterious civilization of the ancient Maya. The template or matrix of the 13:20 frequency, a 13 x 20 (260) unit structure, was the means for accommodating the base "calendar" used by both the ancient and present day Maya: the *Tzolkin,* or sacred calendar, a set of thirteen numbers and twenty signs that repeat their sequences of permutations every 260 days. While this 13 x 20 matrix accommodates the Tzolkin, it is not confined to being a calendar, as I amply demonstrated in *The Mayan Factor.*The 13:20 frequency is the universal constant of time from whose mathematics the Tzolkin is derived. Based on the permutation table, called the *buk xok* in the Chilam Balam tradition, this matrix is a Harmonic Module, a fractal yardstick of radial time with multiple applications, something analogous to the periodic table of elements, but of the synchronic order.

It is still a profound challenge to all modern Western scientific thought that the Maya would have possessed such mathematics, apparently inherited from the earlier and even more mysterious Olmec people, and that with this mathematics they would have evolved such a profound perception of time. This was most certainly a factor in the destructive attitude taken toward the Maya by the religious zealotry of the conquerors of Mexico. It is also astonishing that the mathematics in which the Harmonic Module is embedded is a vigesimal (20) count, utilizing a zero and a positional ordering system that accounts for larger or greater values that advance by binary exponentiality rather than a decimal sequentiality. But, quite simply, this system exists in this manner because it is the mathematics appropriate to time. This mathematics is a factor to which any disinterested researcher on the topic of time must now become accustomed.

It is by reason of this mathematics and its ability to "download" the 13:20 universal frequency of synchronization that the ancient Maya were able to construct a complex system of "calendars" and an astronomical knowledge that is precise not for its telescopes, of which there were none, but because of the nature of the mathematical system itself. More appropriately described as synchronization devices or synchronometers, the Maya used at least seventeen of these timing instruments simultaneously during the great age of their civilization, A.D. 435-830. This fact in itself tells us that the Maya understood time so radically differently from the perception that has evolved in the techno sphere that we must stand in awe that such a knowledge would have developed by a people whose technological development was so minimal, but whose artistic accomplishment was inseparable from their scientific achievement.

Harmonic Module



Yes, the Maya most definitely knew that time is the universal factor of synchronization, so their synchronometers must have been for the purpose of attaining a master synchronization with the cosmos. This presupposes such a different state of mind that all the values of the present day must be challenged. The mystery of it is that this mathematics and time science developed in the New World, remote from the saga of civilization in the Old World. The fact that the later Maya practiced ceremonies and blood rituals, the fascination of so many present-day archeologists, should not detract from the understanding that these ceremonial practices stem from a totally different perception of life-and death. Before we judge, we must consider the inescapable truth that nothing in history matches the terror of the different kinds of war and weapons of mass destruction that characterize the fifty-six-year cycle of the technosphere, 1945-2001. Who then is the more barbaric-the Maya, or modern man, *"Homo technosphericus"?*

It is the study of this vigesimal mathematics and its 13:20 Harmonic Module that has led to the discovery of the Law of Time. In this regard the Law of Time is a universal law independent of any culture or civilization, even that of the Maya, much like the law of gravity is also a universal law. However, if it had not been for the Maya, who evolved their understanding of the 13:20 frequency of synchronization to such a high degree, there would never have been a pursuit that led to the discov-

Galactic Notation, Dot-Bar (0–19) Code

Vigesimal count, 1–19, where in first order 1 = 1 and
0 = 20 position, so in next order 1 = 20, in third order 1 = 400, etc.



ery of the law underlying their knowledge of time. If with this law we may categorize the time vector potentialities in six stages of consciousness-preconscious, unconscious, and conscious, continuing conscious, superconscious, and subliminal conscious-then we may be certain that the ancient Maya were also familiar with the time science associated with the higher states of consciousness revealed by the Law of Time. With this time science and mathematics of higher consciousness, the Maya were able to bequeath a prophetic tradition mathematically coded in the Harmonic Module, which, among other matters, led to the discovery or making conscious of the Law of Time itself.

Once we appreciate the radically different perception of time and knowledge that is embodied in the Harmonic Module, the mathematical modeling of the 13:20 universal frequency of synchronization, then we may turn to its uses as the fractal radial measure of time applied to many levels of thought and knowledge. For instance, using the 13:20 matrix we may turn to an understanding of the Law of Time in human history, as is necessitated by these reflections. With the Mayan time knowledge and the placement of their civilization in the New World, we have a gauge and an alternative base of knowledge upon which to evolve a planetary perspective and an objective means of critique of the mainstream development of civilization in the Old World. We may then ask the questions: How did we become what we are now, and how was it that our civilization evolved into the technospheric medium?

▼



4

The Law of Time in Human Affairs

The Analysis of History

THE KEY to *The Mayan Factor* is the application of the Harmonic Module as a fractal measure that is descriptive of the cycle of thirteen baktuns, the Mayan measure of history. This measure of thirteen baktuns, a cycle extending from 3113 B.C. to A.D. 2012, had been deduced from the stone inscriptions of the Mayan monuments of the Classic period, most of which bear a date within the tenth baktun cycle, A.D. 435-830, or, in the transliterated vigesimal notation of the Mayan Long Count, 9.0.0.0.0-10.0.0.0.0. However, one of the principle discoveries of *The Mayan Factor* demonstrated that the thirteen baktun cycle was also a function of the Harmonic Module and identical with its mathematical mapping as the 13:20 matrix. There are very profound implications to this correlation of the cycle of history having a one-to-one identity with the 13:20 frequency matrix. For this reason the cycle of history is referred to as a *Wave Harmonic* of the galactic order of time. Even though history may appear to be a random, haphazard, and checkered advance of humanity from living in small agricultural communities to the present-day technosphere, this process has actually been an orderly program of the biosphere, the region for the transformation of cosmic energy on Earth.

The same principle of the analysis of the Law of Time applies here. That is, by analogy, the historical events analyzed from a political or economic perspective represent the perception of the random events of near space and low time, while the analysis of the thirteen baktun cycle Wave Harmonic of history represents the perspective of far space and high time. In this Wave Harmonic, the program of history is mathematically defined by 13 baktuns-each baktun consists of 20 katuns-13 baktuns x 20 katuns = 260 katuns = 13 x 20 matrix of the 13:20 frequency of synchronization. In the 13 x 20 matrix of the Harmonic Module each unit equals one kin, the base unit of fractal measure. By fractal equivalence, in the mapping of history one kin = one katun, one katun = 7,200 days; therefore one baktun = 144,000 (7,200 x 20) days. The mathematical perfection of the cycle of history matching the 260-unit model of the harmonic matrix means that history is a factor of synchronization of the higher order of time coordinating the human organism within the biosphere.

By means of the *thirteen baktun Wave Harmonic of history,* the incidence of human Civilizational Advance (CA) may be plotted in a very precise way as a progression going from a very dispersed and scattered state to the point of attaining its exponential climax in the final saga of geochemical combustion, the fifty-six-year cycle of the technosphere. In this regard we must ask: What do we mean by "history" from the Wave Harmonic point of view? As an organism that is a function of the biosphere, history defines that stage when that organism, humankind, enters a process of altering its biomes through increasingly artificial means or extensions of itself that exhibit a compulsive reordering of society into denser and denser clusters of habitations known as cities, hence civilization, "city-life."

In the stage before history, the human had created certain tools and had begun experiments in agriculture and horticulture, but the mental order remained in an aboriginal condition. Unconsciously absorbed as an integral mechanism within the cycles of the biosphere, the human wrapped his understanding of these cycles and of his place in them in the garb of myth and ritual. But with history, something different occurs. The artificial means or extensions of the senses are ordered by a different form of mentality. Those projections of thought and consciousness, though immaterial, affect the material surroundings, and take on an aggressive dynamic. The aggregate effects of these artificial extensions are maintained by a new mental dynamic that is contained and then conditioned by a new kind of macro-organizing thought structure, independent of the actual cycles of the biosphere. What is this new mentality? How can we most precisely define it?

Here are some points to ponder. The Mayan reckoning of the beginning of history is precisely dated to August 13, 3113 B.C., Long Count 13.0.0.0.0. The Hindu reckoning of the beginning of the Kali Yuga is dated to February 19, 3102 B.C. These dates are only eleven years apart. What cosmic event occurred at that time to initiate the Wave Harmonic of history? As we have seen, there is a perfect identity of the

13 Baktun Cycle: Wave Harmonic of History


GALACTIC SYNCHRONIZATION BEAM SHOWING 13-BAKTUN CYCLES AS THIRTEEN MORPHOGENETIC SUB-FIELDS
3113 B.C.
2718 B.C.
2324 B.C.
1930 B.C.
1536 B.C.
1141 B.C.
747 B.C.
353 B.C.
A.D. 41
A.D. 435
A.D. 830
A.D. 1224
A.D. 1618
A.D. 2012
400 TUN
BAKTUN OF THE STAR PLANTING
BAKTUN OF THE PYRAMID
BAKTUN OF THE WHEEL
BAKTUN OF THE WESTERN MOUNTAIN
BAKTUN OF THE HOUSE OF SHANG
BAKTUN OF THE IMPERIAL SEAL
BAKTUN OF THE MIND TEACHINGS
BAKTUN OF THE ANOINTED ONE
BAKTUN OF THE LORDS OF RED & BLACK
BAKTUN OF THE MAYA
BAKTUN OF THE HOLY WARS
BAKTUN OF THE HIDDEN SEED
BAKTUN OF THE TRANSFORMATION OF MATTER
One square is equal to 7,200 days, known by the Mayans as one Katun.
7,200
One column, 20 squares = 144,000 days, one Baktun
144,000
Key
A.D. 2012 GALACTIC SYNCHRONIZATION NEW HARMONIC FIELD BEYOND DUALITY

260-KATUN CYCLES
52-UNIT GAIA LIGHT BODY

	13.0.0.0.0	1.0.0.0.0	2.0.0.0.0	3.0.0.0.0	4.0.0.0.0	5.0.0.0.0	6.0.0.0.0	7.0.0.0.0	8.0.0.0.0	9.0.0.0.0	10.0.0.0.0	11.0.0.0.0	12.0.0.0.0	
DRAGON / IMIX	URUK, MENES	ZOSER, EGYPT CALENDAR	SARGON	ABRAHAM	SHANG DYNASTY, CHINA	KING WEN	GREEKS	ALEXANDER	ROMAN	FALL OF ROME	BOROBADUR	GOTHIC	DESCARTES	NEPTUNE
WIND / IK	KILNS	GREAT PYRAMID	BABYLON		AKHNATON	CHOU DYNASTY	KUSHITE	CELTS	EMPIRE	BYZANTIUM		EUROPE	SCIENTIFIC	URANUS
NIGHT / AKBAL	UNIFIED SUMER	GIZA		CRETE	HITTITE	CHINA		ASOKA	TEOTIHUACAN	RISE OF	VIKINGS	MONGOLS	MATERIALISM	SATURN
SEED / KAN	EGYPT				EMPIRE	KING DAVID, JERUSALEM	NINEVEH	SPREAD OF BUDDHISM		CLASSIC	HEIAN JAPAN	KUBLAI KHAN	CHING DYNASTY	JUPITER
SERPENT / CHICCHAN	OLD		CHARIOT	EGYPT: QUEEN	THERA EARTHQUAKE		PYTHAGORAS	ZAPOTECS		MAYA	CHIMU	MAYAPAN	NEWTON	A-BELT/MALDEK
WORLD-BRIDGER / CIMI	KINGDOM		WARFARE	HATSHEPSUT	OLMECS	VEDIC	BABYLON REBUILT	CH'IN DYNASTY	NAZCA	BUDDHISM IN JAPAN	XOCHICALCO	AZTEC	BAROQUE MUSIC	MARS
HAND / MANIK				VALLEY OF	CHAVIN	CIVILIZATION		HUANG-TI	GERMANIC	TIKAL	CE ACATL	BLACK PLAGUE	INDUSTRIAL	EARTH
STAR / LAMAT			EGYPT	KINGS		INDIA	LAO TZU	EARLY	INVASIONS	POPE GREGORY	TOPILTZIN QUETZALCOATL	INCA	REVOLUTION	VENUS
MOON / MULUC	HEIROGLYPHS	AKKAD	MIDDLE KINGDOM				PERSIAN	MAYA	MOCHE	MUHAMMED	RISE OF	MOGHUL / INDIA	AMERICAN &	MERCURY
DOG / OC		UR			JADE	HORSE WARFARE	EMPIRE	HAN		PALENQUE	TOLTEC	OTTOMAN TURKS	FRENCH REVOLUTION	MERCURY
MONKEY / CHUEN	CUNIEFORM				KING TUT		BUDDHA, MONTE ALBAN		END OF	PACAL VOTAN	MAYA		ROMANTICISM	VENUS
HUMAN / EB		HARAPPA			RAMSES		CONFUCIUS	DYNASTY	HAN DYNASTY		IFE	MING DYNASTY	EUROPEAN	EARTH
SKYWALKER / BEN		CIVILIZATION			ASSYRIA	JERUSALEM		TEOTIHUACAN	TIAHUANACO	COPAN	ANGKOR WAT		IMPERIALISM	MARS
WIZARD / IX		INDIA	ZIGGURATS				PLATO	RISE OF ROME		HEIROGLYPHIC STAIRWAY	CRUSADES	FALL OF CONSTANTINOPLE	ELECTRICITY	A-BELT/MALDEK
EAGLE / MEN				HORSES			CHUANG TZU			SPREAD OF ISLAM	BUDDHISM IN	PRINTING, CONQUEST	RUSSIAN REVOLUTION	JUPITER
WARRIOR / CIB			BRONZE	CENTRAL ASIA	VEDAS	LA VENTA	ZOROASTER	GREAT WALL	CONSTANTINE		TIBET	OF MEXICO, PERU	WORLD WARS	SATURN
EARTH / CABAN			TECHNOLOGY	HITTITES		ASSYRIAN		OF CHINA	BUDDHISM IN	T'ANG DYNASTY	SUNG DYNASTY	EUROPE EXPLORATION	HIROSHIMA	URANUS
MIRROR / ETZNAB			MENUHOTEP	EGYPTIAN	PHOENICIANS	IRON	BANTU, WEST AFRICA		CHINA	MISSISSIPPI CULTURE, BAGDAD	RUSSIA/KIEV	BENIN	NUCLEAR & SPACE TECHNOLOGY	NEPTUNE
STORM / CAUAC	STONEHENGE	PYRAMID	UR NAMMU, LEGAL CODE	EMPIRE	MYCENEANS	WEAPONS &	PELOPPONESIAN WAR	JULIUS CAESAR	GUPTA DYNASTY, INDIA	PADMASAMBHAVA	ANASAZI	QUEEN ELIZABETH	HARMONIC CONVERGENCE	PLUTO
SUN / AHAU	GILGAMESH	TEXTS	HAMURABI	ARYANS INVADE INDIA		WAR MACHINES	ARISTOTLE	CHRIST		CHARLEMAGNE	ZIMBABWE	GALILEO, KEPLER	EARTH REGENERATION	PLUTO

SOLAR MOVING INHALATION
GALACTIC/LUNAR MOVING EXHALATION

Wave Harmonic of history, as a fractal equivalence, with the Harmonic Module, itself a description of the universal 13:20 frequency of synchronization. This being so, both the calculation of the beginning of history as well as the duration of its entire cycle are functions of the Law of Time. This means that something within the Earth's noosphere occurred that triggered the Wave Harmonic, itself a manifestation of the Law of Time. Also, by most judgments and standards, history began at a very precise place as well-Sumeria, in the Mesopotamian basin of what is now called the Middle East. Why? And what relation is there between the precise event that triggered the Wave Harmonic of history and Sumeria, the site of the first city, Uruk? What event could have established a macro-organizing principle to propel the dynamic of human thought and technology into the trajectory concluded by the technosphere?

THE ORIGINS OF THE 12:60 FREQUENCY

In the recently published book *The History of the World-A 6,000 Year Chronicle of Time,* we find the point that establishes the definite artificiality of a new kind of macro-organizing principle, driving humankind toward the Inevitable Event; here we find the genesis of artificial time: "Ca. 3000 B.C. Sumerians divide day into 24 hours, 60 minutes, 60 seconds and circle into 360 degrees."! While this is a fact we may take for granted because it is the basis of mechanized time in the form of the clock, for precisely that reason it should give us pause. For one thing, this means that the measuring system of the clock was already established at the beginning of history, some 4,500 years before the clock as we know it was actually invented! This is quite an astonishing fact. It means that mechanization was implicit in the first intellectual act of history. Why or how would it have occurred at the precise point of the beginning of history in Sumeria?

The Law of Time defines this mechanistic organizing principle as the basis of the 12:60 artificial timing frequency (irregular twelve-month calendar combined with mechanical sixty-minute hour). Therefore, it was at this point at the beginning of history that artificial time and its progeny, mechanization, were actually registered as a thought form and thus became embedded in the as-yet-unconscious noosphere. Or, was it already embedded in the noosphere to be triggered at this precise point-and if so, why and how? The point is that history, as it has evolved as the mainstream of civilization from Sumeria to the World Trade Center, has always been driven by the organizing principle of artificial time. It is artificial time that separates history from prehistory-and, as we shall see, from post-history as well. It was due to the

The Error in Time

The measure of a two-dimensional plane in space has nothing to do with the experience or the nature of time.

"TIME WAS COMPRESSED INTO A FLAT CIRCLE..."
Dreamspell "Genesis"



Sumeria: Ca 3000 B.C.
Day divided into 24 hours,
60 minutes, 60 seconds
based on 360 degree circle—
two-dimensional plane in space—
divided into twelve parts

Earth's solar orbit = 365 days
360 degrees ≠ 365 days





Europe: 800-1600 A.D.
Clock—two-dimensional plane
in space—divided into twelve
parts each 30 degree of arc =
1 hour = 60 minutes
each minute = 60 seconds
A.M. = 12 hours
P.M. = 12 hours
= 24 hours

I - 31	II-28/29	III - 31
IV - 30	V - 31	VI - 30
VII - 31	VIII - 31	IX - 30
X - 31	XI - 30	XII - 31

Rome (Vatican): 44 B.C. - 1582 A.D.
Twelve-month Julian/Gregorian
calendar derived from twelve part
division of circle; irregular measure
due to fact that 365 is not divisible
by twelve.

genesis of artificial time at the beginning of history and its emplacement within the planetary noosphere that also generated the thirteen baktun Wave Harmonic of history. For the very purpose of the thirteen baktun Wave Harmonic of history is to encompass and coordinate the cycle of artificial time. Why?

The Wave Harmonic is a function of the 13:20 synchronization frequency. It is a function of cosmic time. In the higher knowledge of the Mayan understanding, it provided the perfect measure of the cycle of artificial time. From the perspective of the actual noospheric timing, which operates according to the natural 13:20 cosmic timing frequency, history is none other than a manifestation of artificial time. Civilization becomes organized by the principle of artificial time. But because it is artificial, it cannot endure. If the mathematical basis of mechanized time, and hence of mechanization, was already established at the beginning of history, then the end of history is the end of artificial, mechanized 12:60 time. And in the end, the Law of

Time codes and encompasses the whole of the cycle of artificial time through the thirteen baktun Wave Harmonic of history. What is important to grasp is that the entire cycle of artificial time was *already perceived* by the Mayans as a phenomenon that could not endure more than the length of the cycle of thirteen baktuns.

It is necessary for the reader to understand how this perspective was discovered. It was the result of a phenomenological experiment of living according to the synchronic cycles of the Mayan time science. After the death of my son in 1987, my wife and I began in earnest to follow the cycles encoded in the Mayan calendar: 13-day, 20-day, 52-day and 260-day cycles. Our life changed dramatically. At the same time, I endeavored to define the mathematical basis of these cycles. Once I resigned my academic position in early 1989, we were swept by a wave of time that took us from the Rocky Mountains to Southern California to the Hawaiian Islands in the middle of the Pacific Ocean. There, in relative isolation from the rest of the world, we plunged into our experiment. Before we had truly settled in, the time wave took us to Switzerland, where on December 10, 1989, in the Museum of Time in Geneva, we were able to put our phenomenological experiment to the test-although we did not consciously realize at the time that we were doing so.

There in the Museum of Time, essentially surrounded by examples of the history of the clock and mechanization, and because our perceptions had been altered by our living so completely by the various timing cycles encoded in the Mayan calendar system, we were able to spontaneously perceive the existence of two timing frequencies. The natural frequency-the one we had been living-we understood instinctively to be the 13:20 timing frequency. The other frequency-the one enshrined in this Museum of Time-we understood to be the artificial 12:60 timing frequency. This realization of artificial time was rooted in the evident proof that the clock is based on the twelve-part division of a flat circle, a spatial plane that clearly has nothing to do with the dynamics of time. It is a manifest error, but one that humanity has taken for granted and endowed with all of the characteristics of "truth."

We also immediately saw that the error of mistaking the division of a two-dimensional plane in space for a measure of time was transmitted not only through the clock, but through the twelve-month Gregorian calendar as well. With brief reflection upon what a gross error this was-substituting a twelve-part division of space as a measure of time, and then elevating this mistake as the truth of the measure of time-we understood how it could have actually led humanity away from the natural time of the universe. In making this observation, we immediately and intuitively grasped the necessary solution: replace the erroneously measured twelve-month Gregorian calendar with the perfect measure of the Thirteen Moon/28-Day calendar.

Our research into the mathematical codes behind the Mayan calendar now progressed rapidly, but our attention also turned to the question: Whence came the thought form of 24 hours, 60 minutes, and 60 seconds as a measure of a circle of 360 degrees? It was clear to us that this division of time based on the division of a circle in space occurred at what is the beginning of history, a fact later confirmed for us in the already cited *History of the World* (1997), which states that this division of 24 hours, 60 minutes, 60 seconds and the circle into 360 degrees was devised "Ca. 3000 B.C."

Once we had finished working out the mathematical codes, we turned to a consideration of the actual implications of the error in time. It was now also clear why the Mayan time science was so superior. It was based on the reality of time as a factor of synchronization. By contrast, the concept of time as it had developed in the mainstream of civilization was limited, linear, and totally third-dimensional, a fact that confirmed Vernadsky's analysis, as well, that our notions of time are a function of the metrics of space. By 1991, the experience in the Museum of Time had driven us into


What Difference Can a Calendar Make?
January - 31 days
February - 28/29 days
March - 31 days
April - 30 days
(sometimes)
"AND SO THE THIRTEENTH MOON WAS DISMEMBERED AND ADDED ON AS EXTRA DAYS TO THE CALENDAR OF TWELVE..."
Dreamspell "Genesis"
May - 31 days
June - 30 days
July - 31 days
August - 31 days
Extra days of Gregorian calendar make up the hidden thirteenth moon
September - 30 days
October - 31 days
November - 30 days
December - 31 days
June 27 to July 24
+1 Day-Out-of-Time
July 25
Day of Planetary Peace Through Culture Festival
Unequal Units of Measure
J F M A M J J A S O N D
31 days
28 or 29
31 30 31 30 31 31 30 31 30 31
inches
1 2 3 4 5 6 7 8 9 10 11 12

Gregorian Calendar and the Hidden Thirteenth Moon creating a full-blown psychomythic analysis and description of this moment of realization concerning the nature of time. The complete structure of the mathematical codes of time, as well as the psychomythic description of the causes and effects of the error in time, is known as the Dreamspell, which is defined as follows:

"DreamspeH: function of fifth-dimensional galactic-solar planetary regulation; 26,000-year renewable cycle and planetary castle genesis; any consensus reality; in disregard of interdimensional reality creates entropic spell of history; cure for loss of galactic memory."2 The *planetary castle genesis* refers to the *five castles of time* (each 5,200 years in length), divided into three *geneses-the* Dragon, the Monkey, and the Moon-that constitute the entire fractal panorama of the 26,000-year cycle of history that ends in 2012, and is meant to be renewed in 2013 (an obvious synchronic reference to the 13:20 timing frequency). In the Dreamspell analysis, the beginning of history occurs almost 5,200 years ago between the Monkey and the Moon geneses, and is marked by the imposition of the false 12:60 timing ratio.

In light of this analysis and definition it is worth quoting certain passages from the Dreamspell text that describe this precise moment at the beginning of history and that the Law of Time defines as the root error of civilization. First we quote from the "Dreamspell Genesis," and then from the descriptions of the "Dreamspell Journey and Mission of Timeship Earth 2013." The purpose of quoting these passages here is to establish a psychomythic context to explain the profound nature of what we refer to as the error in time compounded over 5,000 years of history:

> Imposters, male priests and warriors usurped the power of the thirteen moons. They hid the thirteen among themselves and attempted to banish all memory of the matrix dreamspell of magic. . . The planetary kin had imposed upon them the diminishing power ratio of 12:60. No longer the magic of thirteen moons but a twelve month calendar of uncertain meaning. No longer the timeless gyre of magical flight, but a sixty-minute hour to earn one's bread.
>
> Time was compressed into a flat circle. . .
>
> The 13:20 ratio is the base operating ratio of timeship Earth. . .
>
> In that vital moment during the magic flight. . . Toward the moon genesis, another spell was cast. Instead of the 13:260 ratio already stored deep within the crystal core of timeship Earth, the planetary kin received the 12:60 ratio, the dark dreamspell of history. . . And so the thirteenth moon was dismembered and added on as extra days to the calendar of twelve. . .

> The absorption of the thirteen by the twelve was called an improvement by the male imposter priests hypnotized by the combined powers ofJupiter and Saturn. It takes twelve years for Jupiter to orbit once around the sun. It takes sixty years for Jupiter and Saturn to be conjunct.
>
> Twelve times five equals sixty, one sixth of the flat three hundred sixty degree circle. The difference between twelve and five is seven. While the priests of the calendar of ancient Babylon banished the power of the thirteen moons, they replaced that power with the power of seven.
>
> While the twelve diminished the power of thirteen by one, the sixty raised the power of twenty by three. A seeming increase in power occurred, but an increase only on the flat plane of the third-dimensional time to which the planetary kin were now consigned.
>
> With the banishment of the thirteen moons, the fourth-dimensional time magic. . . became the property of the priest class. Setting up religions and governments to maintain the kin within the third dimension, the priests were assured that anyone having fourth-dimensional experiences either be appropriated or destroyed.J

So much for the psychomythic impression of the genesis of artificial time, the flat time of an exclusive third-dimensional reality called history. A few further quotations from the Dreamspell emphasize both the interplanetary and mathematical root of false time:

> At -3187 Dreamspell years the time bandits on the sixth and seventh orbits pulsed their beam. The 12:60 frequency of the memory virus took immediate effect on the third-dimensional space suits. . . The Dreamspell of history was cast.
>
> Imposter priests on Earth substitute the 12:60 ratio. . . Instead of the magic of following thirteen moons, a non-circulating twelve-month calendar is substituted; instead of the beauty and power of magical flight, the sixty-minute hour. The result is disastrous.
>
> The twelve-month calendar is the consequence of the 12:60 ratio imposed at -3187 Dreamspell years (3113 B.C.,Julian/Gregorian). With no basis in or capacity for measuring galactic time, the twelve-month calendar is actually a third-dimensional prison keeping the four root races separate and at war with each other.4

These descriptive explanations of the error in time define such a profoundly radical point of view that we must flesh out the implications and description of the course of artificial time according to the analysis of the Law of Time. From the outset of civilization in Sumeria, artificial time captures the human mentality in the order oflow time and near space (third dimension), separating it from high time and far space (fourth dimension). The registration of artificial time within the unconscious structure of the noosphere, which is intrinsically governed by the universal 13:20 frequency of synchronization, creates a conflict and a pressure in the noosphere, a time warp or taint that affects the entire biosphere.

Civilization-living in cities-increasingly becomes the human norm within the biosphere. Where there had been no civilization, at a few key places around the planet civilization now arises-a process that goes from the crystalline structures at the origin to the later phases of imperialism and empire building. This cycle is repeated again and again. Even in the New World where the 13:20 natural timing frequency prevailed, the later stages of civilization succumbed to the effects of the 12:60 already seeded in the noosphere. Ultimately, all humanity and the biosphere were to be governed by the artificial timing frequency that ends with the construction of the technosphere, the final and supreme expression of artificial time. Indeed, the technosphere is the absolute conclusion of what can rightly be called an artificial time warp in the biosphere.

Concerning the mathematical basis of the 12:60 frequency, V. A. Ponko of the Russian Academy of Sciences, Novosibirsk, has conducted extensive research and wave analysis on the mathematical properties of the cycles of history. He has concluded that as a mental coordinate, the number 12 is a strict construct of the angles of space. Since it does not correspond to the sinusoidal curvature of the cycles of time and the plotting of all organic phenomena, when used as a time factor the number 12 offers no "protection" from bombardment by any number of cosmic forces. The mathematical plotting of the 13:28 frequency that characterizes the Thirteen Moon calendar, on the other hand, is in alignment with the sinusoidal curve properties of organic phenomena, and therefore functions as an "umbrella" maintaining the organism in resonance with the biosphere.s

Here let us make a more precise definition of timing frequencies and the nature of calendars as the macro-organizing programming systems of the human in the biosphere. By defining time as the universal frequency of synchronization, we are saying that synchronization is the fundamental program to which everything adheres and which makes everything perceptibly coherent, hence synchronic order. Therefore, the natural timing frequency that is a universal phenomenon both regulates the phenomenal order of the cosmos, and in the human is absorbed as a mental frequency that unconsciously synchronizes the mind and senses with the natural order. The result is the normal sensation and experience of the harmony of reality. This defines both a fundamentally prehistoric perception of reality as well as the spiritual experience that is common when we are confronted with the awesomeness of nature-usually far away, it should be noted, from city life. This universal factor of synchronization we have identified as the mathematically precise ratio 13:20, a ratio constant embedded in the structure and order of the calendrical and astronomical system of the ancient Maya.

If we understand that this frequency of synchronization is a genuinely universal constant, then we may comprehend how not only the entire biosphere, but solar system and galaxy are also governed by the same frequency. This is how the Kozyrev experiments could show that there is instantaneous transmission of information throughout the universe, which in its entirety is a function of the formulation *velocity of time is instantaneously infinite.* Synchronization and infinite instantaneity of transmission are mutually defining-everything is always instantaneously synchronized. We can further say that synchronization "syntropizes" while dissynchronization "entropizes." There is no lag time in synchronization.

This being the case, we can then begin to understand how the acceptance and institutionalization of the artificial 24-hour, 60-minute, 60-second division of the 360 degree circle as the basis for defining time could be such a singular and ultimately disastrous deviation from the universal frequency of synchronization. Thus when we speak of the artificial 12:60 timing frequency, we are referring to the mental effect of the feedback program of the use of artificial and erroneous instruments of measure. Rather than allowing the mind to remain in the natural harmony of synchronization with nature, the artificial 12:60 standard and its instruments establish a feedback effect in the mind that accustoms it to the deviation from nature. This habituation results in the creation of an unconscious timing frequency that is accepted by the consensus reality as the actual norm. Separation of human order from the biosphere becomes accepted and acceptable, making civilization not only possible, but setting it up, as it were, as a parallel rival to "nature." In fact, it is the unconscious mental frequency of 12:60 artificial time that coordinates and maintains civilization as a belief system.

When we speak of the instruments of measure of artificial time, we are specifically referring to the Gregorian calendar as the macro-organizing principle and the watch or mechanical clock as the micro-organizing principle. The macro-organizing principle organizes our life into days, weeks, months, and years. The micro-organizing principle organizes our life into seconds, minutes, and hours. These two instruments have their common root in the error in time that occurred 5,000 years ago at the beginning of history. Try to think of life without these instruments and you will quickly realize how second nature they are-and yet there was a time when such instruments and their terminology did not exist. Before turning our attention to an analysis of these two instruments and their effects on human consciousness, we must view the entire cycle of the Wave Harmonic of history as a function of the macro-organizing principles of time that the human in the biosphere adopted for its uses and that, in turn, condition at a most profound level the worldview of the culture or civilization that uses it.

HISTORICAL CALENDARS AS INSTRUMENTS OF ASTRONOMICAL MEASURE

It may be rightly asked, What does a calendar measure? At a minimum, a calendar is or should be the measure of the Earth in its rotation around its local star, the sun. This rotation takes 365 days. The Earth's satellite, the moon, is the obvious synchronizing factor between the Earth and the sun. But here we encounter a difficulty. The moon can be measured by various cycles. The synodical cycle, from new moon to new moon, is 29.5 days. The sidereal cycle, the measure taken from where the moon appears at the same place in the sky, is just over 27 days. There is an apsidal cycle, however, taken from the measure of when the moon's axis is tilted farthest from the Earth, which is 28 days. This variance of measures is due to the fact that until the rise of rocketry, we could not really see the moon from space. In actuality the moon rotates around the Earth thirteen times during the time it takes the Earth to orbit the sun once.

If one were objectively seeking the proper measure of the Earth's orbit using the moon as the measuring device, we would therefore construct an instrument for time reckoning that consists of an even harmonic measure of thirteen cycles of twenty-eight days each. The 28-day cycle conforms, of course, to the female menstruation cycle, an obvious human biological cycle, and it also divides perfectly into four 7-day subcycles or weeks. Also, 13 x 28 = 364, the same number of days as thirteen moons multiplied by four 7-day weeks (a total of fifty-two weeks), with the 365th day being a free day, or Day Out of Time, no day of the week or month at all. We shall deal with the perceived extra quarter-day later in our discussion.

The point is this: If time is a factor of synchronization, then a calendar-as an instrument for measuring the count of time-should also be constructed so that it maximizes the factor of synchronization. This can only be done if the instrument of time reckoning is constructed on harmonic principles in conformity with the objective data of nature. Such an instrument would also conform to the orderly processes of the biosphere taken as a whole, and be a great assistance in bringing into consciousness the cosmic programs that organize the biosphere and noosphere. The Thirteen Moon/28-Day calendar is the perfect instrument for such a simple registration of harmony and synchronization. It should also be noted that in its mathematics the Thirteen Moon/28-Day calendar is a function of the 13:20 timing frequency. This in itself establishes the Thirteen Moon/28-Day calendar as a perfect instrument of the Law of Time and as a function of the synchronic order of reality.

Since the process of civilization represents a break from a long cycle generally undistinguished by the kind of perturbations that characterize history, the analysis of the Law of Time assumes that in prehistory humans lived in relative harmony, and therefore that the humans tended to use harmonic instruments of time reckoning. The humans living in greater harmony with the biospheric cycles would be disposed to be in greater unconscious or aboriginal attunement with the noosphere. Since the noosphere is regulated by the synchronic order of the universal 13:20 timing frequency, the humans would be more naturally disposed to devise, adopt, or intuitively utilize the time measure in greatest accord with this instinctual 13:20 noospheric timing ratio.

This instrument of time measure would, of course, be the Thirteen Moon/28-Day calendar. It should also be noted that this calendar is a perfect solar-lunar measure; that is, it uses the even, regular lunar cycle of28 days as the standard of measuring the 365-day solar cycle of the Earth. The balance of solar and lunar may also be taken as

Moon Circling Earth Thirteen Times per Year



Did you know the moon goes around the Earth thirteen times a year?

SEE: HTTP://WWW.TORTUGA.COM/WWW/ANIMATIONS/ANIM_MOON.HTM symbolic of human psychological characteristics and their balance or imbalance. A solar-lunar calendar will represent and reflect a balance of the solar-lunar, masculine and feminine qualities within the human being. It is important to bear in mind these considerations of calendars and their effect on shaping the human historical consciousness and its psychological makeup. From this perspective, history is, in fact, a process of falling away from the perfection of harmonic standards.

Evidence exists that the Thirteen Moon/28-Day measure was widely known in prehistory. We find evidence of its use as a prehistoric synchronic measure in the remote past of China, in Polynesia, and scattered across late neolithic Europe and the Middle East. Among the Maya it was known as the *Tun Uc,* literally "moon count" or count of seven, while the living tradition of the Thirteen Moon/28-Day calendar is still continued in South America and in the British Isles, where it is known as the Druid Tree calendar. While the Druid calendar has no year count attached to it that would definitively testify to its prehistoric ancestry, the South American calendar does. Known as the *Pachacuti,* the South American Thirteen Moon/28-Day calendar is currently in the year 5509, which places its origins at 3308 B.C., toward the middle of the fourth millennium before Christ, and several hundred years before the beginning of the thirteen baktun Wave Harmonic of history.

If we understand that calendars are genuine time-measuring devices meant to synchronize us with the cosmic order within the biosphere, and that calendars are thereby programming devices, we may then say that a calendar of perfect harmony can have no history. In other words, by its harmony such a calendar is always in tune with the cosmos, which is beyond history. History can only be a function of a disharmonic programming, not in sync or even at odds with the laws of natural time.

From the point of view of timing devices, there are two factors in the establishment of history. The first is the 12:60 program established 5,000 years ago with the division of the day into 24 hours, 60 minutes, 60 seconds, based on the 360-degree division of the circle. The other factor is the use of a purely lunar calendar that is difficult to reconcile with the actual measure of the solar year. The purpose of the 12:60 measure was to establish a timing standard that was actually a pseudosolar calendar to assert male intellectual dominance. The Babylonian (and later, Egyptian) calendar consisted of twelve 30-day cycles = 360 days = 360 degrees, plus an extra 5-day cycle. The 30-day measure is not actually a natural one, being a half day more than the synodic lunar measure, but one that conforms to the hexagisimal (6-based) mathematics of the circle. For this reason, this instrument of time reckoning is defined as *pseudosolar*. Its ultimate descendent, as we shall see, is the twelve-month Julian/Gregorian system.

By contrast, the Maya also had a 365-day solar calendar, the *Haab.* Its measure, however, is that of eighteen 20-day cycles (18 x 20 = 360) plus the 5-day cycle *(uayeb),* the 20-day cycle *(vinal)* being a mathematical function of the 13:20 frequency. In addition, the Maya had the measure of the *tun,* the 360-day count of which is precisely the same as that of the degrees of the circle. It was the tun that the Maya used to measure the thirteen baktun count, which actually consists of5,200 tun (5,125 solar years). The purpose of this measure was to provide an exact harmonic standard for the measure of history that, we may recall, is the duration of artificial time. It is very relevant that the harmonic standard of the thirteen baktun Wave Harmonic of history is the 360-day tun, the actual temporal equivalent of the degrees of a circle in space. The precise measurement of the cycle of artificial time, which turned out to be anything but harmonic, could yet be measured with a harmonic unit that reflects both the circle *and* the mathematical perfection of the Law of Time. How better to coordinate the entire cycle of artificial time than by the tun, a unit of measure that reflects the 360-degree circle, the basis of the original error in artificial time? As we will later observe, the fact that the Law of Time coordinates even the cycles of artificial time is also evident in the analysis of the timing of the fatal flaw of the Twin Towers apocalypse.

While the Babylonians began to apply a hexagisimal time-reckoning device based on spatial metrics of the circle, another factor became predominant in the Old World: the rise of the synodical lunar calendar as the exclusive measure of time. The synodicallunar calendar is purely lunar in that it is not evidently or perfectly harmonized with the 365-day measure of the solar cycle-a fact of great consequence for the development of mainstream civilization. The Babylonian calendar, with its abrogation of the thirteen perfect 28-day months, established the pseudosolar twelve-month measure. This twelve-month measure conformed to the lunar measure of twelve synodic lunations per lunar year. However, twelve lunations are only 354 days, eleven days short of the solar year. This required an intricate set of calculations to make the lunar calendar keep up with the measure of the Earth's solar orbit. And in reality, although we tend to think of the moon as feminine, the knowledge of the synodic measure, the cycle from new moon to new moon, became the exclusive province of a male priest class that used the lunar calendars to capture and control the feminine principle, and to oppress women in general. Whereas the Babylonian and Egyptian solar calendars fell into disuse over time, the lunar calendar persisted.

Since there is only one moon orbiting Earth, it should be kept in mind that all lunar calendars are essentially the same. One and the same moon in all its phases is apparent to all humans on Earth. So when we speak of different lunar calendars-most notably the Hebrew, the Islamic, and the Chinese-the measure is basically the same, from new moon to new moon, but New Year's Day falls differently in each of them, thus accounting in part for the various calendrical traditions. Within each of these lunar calendars, a different set of holidays is programmed. It is the programming of the different holidays and festivals of the calendars, along with the dating of their new year, that makes each lunar calendar tradition distinct and that also demonstrates how a calendar is a programming device. For instance, if one were to take out the different holidays programmed into the Hebrew lunar calendar, there really would be no such thing as Judaism. This demonstrates that the cultural conditioning of a people is totally dependent on the programming of the calendar they use. This also shows how a calendar is a feedback mechanism that maintains a group of people within the confines of its own self-established belief system.

Of the three lunar calendars we have mentioned, the oldest count of years is accorded to the Hebrew calendar. This year Rosh Hashanah, or Jewish New Year, occurred on the new moon, September 17, 2001, and marked the beginning of year 5762. This places the origin date for the Hebrew calendar in the year 3761 B.C., some 453 years prior to the commencement of the Pachacuti count. The Hebrew calendar (like the Chinese calendar, which we will discuss below) makes up for the slippage of eleven days per solar year by intercalating a thirteenth lunation cycle approximately every three years, or exactly seven such thirteenth moons every nineteen years. These numbers too-13, 7, and 19-are key harmonic factors of the synchronic order of time. This demonstrates that, at the very least, the synodical lunation calendars are calibrated in their larger cycles by the Law of Time. But the effect of being a purely lunar measure, at variance with the actual 365-day measure of the solar year, creates an interesting and one-sided approach. There is no question that the lunar calendar civilizations are the tool of powerfully patriarchal societies, the tables of the moons and the years being the possession of a dominant male priest class.

The Chinese lunar calendar differs from the Hebrew in one important distinction: from the most ancient times it has been embedded in a system known as the *five elements,* and is coordinated with a very elaborate mathematical system that bears some resemblance to the 60-60, 24-360 basis of the SumerianiBabylonian 12:60 frequency. This synchronizing system accounts for the Chinese cycles of years that are counted by the twelve zodiacal animals in combination with the five elements: earth, fire, wood, water, and metal, thus giving rise to 60 (12 x 5) year cycles. Three of these sixty-year cycles create a "group" or cycle of 180 years. We are now (in 2001) in the eighteenth year of the twenty-seventh group, or year 4,698 of the Chinese lunar calendar. So embedded is Chinese culture and civilization in this calendar, with its elaborate system, that to take away this calendar would virtually eliminate

Chinese culture altogether. Perhaps more than any other factor, this highly involved calendar also accounts for the longevity and tenacity of Chinese civilization as one continuous tradition for the duration of its history, which according to the reckoning of its calendar began in 2697 B.C., a date, interestingly enough, that coincides with the dedication of the Great Pyramid of Egypt.

Despite its marvelous system, the Chinese lunar calendar is still just that: a lunar calendar. The problem with this, from the point of view of the Law of Time, is that when it is not regulated by a proper solar count or measure, the lunar calendar leads people into one-sided developments of one kind or another, if only to the extent to which these calendars foster such profoundly patriarchal societies, of which the Chinese is certainly no exception. The influence and use of the Chinese lunar calendar system extends into southeast Asia, Tibet, Mongolia, Korea, and Japan. As a field of thought within the noosphere, the Chinese system is the equal in power base to the Babylonian and Indian systems, at least up to the time of the dominance of the Gregorian. Even today, the Chinese New Year exerts a powerful attraction worldwide.

While the Chinese and Hebrew lunar calendar systems maintain a powerful conservative strain of human society, the intercalation of the thirteenth moon, seven times every nineteen years, creates a kind of circulation within the system. Thirteen is the number of circulation, whereas twelve is that of a static, non-circulating spatial order. The taboo on the number thirteen-epitomized by the superstition about Friday the thirteenth-must certainly be related to the suppression of the solar-lunar Thirteen Moon/28-Day calendars in virtually all historical societies. This irrational repulsion of the number 13 serves psychologically in defense of the "rationality" of the number 12, a number that does not circulate time and is at the root of the linear conception of time. The illogical and irrational decisions that are made and then institutionalized into the human social fabric must at one point be discounted. Any illusion or error pursued for too long will always end in disaster.

The Islamic lunar calendar, used by some 1.3 billion humans, is distinguished by two factors:

1) It is based on a known historical incident, the *Hegira* or flight of the prophet Muhammad from Mecca to Medina, dated to the new moon or Muharram 1, Julian, July 16, 622 (Gregorian, July 26).

2) It is a pure twelve-month lunar calendar running on a cycle of pure lunar years of 354 days, with no intercalary lunations, and in this regard does not annually harmonize with the 365-day solar cycle.

For this reason, this year 2001 saw the beginning oflslamic lunar year A.H. *(M*-ter Hegira) 1422. But if we are to count the solar years since the Hegira, correlated to Gregorian July 26, then it is solar year A.H. 1379. We see here a discrepancy of some some forty-three years between the solar count and the lunar count. The lunar count continuously retrocedes so that it takes thirty-two years for one Muharram to occur at the same place in the cycle of the solar year. In essence, the Islamic lunar calendar creates a hermetic, retrocessing time bubble with no circulation of the power of the thirteenth moon, and that accounts for the highly conservative and patriarchal nature of much oflslamic society. Again, while there may be a virtue to maintaining a strict lunar calendar count, if it is not correlated to a harmonic solar or solar-lunar standard, the effects will be precisely of the nature that we see occurring in today's world, a point to which we shall later return.

Finally, in this brief consideration of calendars as the principle macro-organizing system for the programming of human society, a word should be said about the system of calendars in the predominant part of the Indian subcontinent. Long before they adopted the Babylonian solar zodiac and hexagisimal spatial principles for reckoning time, the Hindus also had a type of 28-day count, but one based on the course of the moon in relation to a set of stars called Nakhsastras; this created a kind of 28-part lunar zodiac. In this system, however, the Hindus divided the 360-degree lunar ecliptic into twenty-seven equal parts (27 days = sidereal cycle of the moon) each part equal to 13 degrees, 20 minutes of are, the precise measure of the 13:20 timing frequency. A complex variety of lunar calendars were developed early on, but were gradually displaced by what we call the pseudosolar Babylonian division of the Earth's ecliptic into twelve 30-degree segments, a fact that reflects the adoption to the unconscious 12:60 frequency program.

The Hindu (pseudo) solar calendars are all based on the same division into 30-degree arcs-a circle or plane in space! While the base count of the present era is taken from February 18,3102, the beginning of the Kali Yuga-the last and darkest age-exactly 5,104 years ago (dated from Gregorian year 2002), today there are at least six different calendars in use throughout the subcontintent, each essentially the same as the other, but characterized by different dynastic starting points. These differing counts, coupled with the distinct profusion of religious holidays, accounts for the jarringly conservative and colorful confusion that characterizes present-day Indian society-a neo-Babylonian time warp, its populace locked into place by complex systems of pseudo-solar calendars set in the context of earlier Hindu astronomical cycles of a vast and overwhelmingly cosmic nature.

"TIME IS MONEY": THE WATCHWORD OF THE 12:60 FREQUENCY

All of the aforementioned time-reckoning systems, with their various beginning points, can be mapped within the 5,200 tun/5,125 solar cycle of the thirteen baktun Wave Harmonic of history. While we can generally see how the Babylonian and lunar calendar systems shaped the mainstream civilizational orders of the Old World, in our time map we must also take into account the workings of the 12:60 artificial timing frequency within the unconscious noosphere. In this sense, the 12:60 frequency refers to the principle programs of control adopted and maintained through use of the twelve-month calendar systems in the Old World. (See plate 5, Noospheric Time Map-Wave Harmonic of History.)

Plotting the incidence of these calendrical streams on the time map, we must keep in mind that the calendar systems are the chief instruments for establishing and maintaining the human mind and social order within very specific programs of behavior. These programs, at least in the Old World, were characterized by the introduction of artificial systems of exchange called money, and accompanying programs of taxation. These systems were adopted to a greater or lesser degree by all the Old World societies. In this we find the root of the slogan, "time is money," where money is the artificial medium to negotiate artificial time. The end of history is the end of money and the end of artificial time. The word "calendar" itself is derived from a Latin word meaning "account book," the first day of every month being *calends* or the date of payment of debts.

Now, let us return to a consideration of the two principal and resultant 12:60 instruments dominating the end of historical time: the Gregorian calendar and the mechanical clock. We may note that toward the conclusion of the twelfth baktun cycle (A.D. 1618), the clock reaches its perfection at the very moment of the implementation of the Gregorian calendar reform (A.D. 1582), just after the act of global circumnavigation had been accomplished. Within the entire thirteenth baktun cycle, 1618-2012, the coincidence of these three factors-clock, calendar, and European global circumnavigation-induced what amounts to a 12:60 frequency capture of planetary time in the biosphere. What are the implications of this takeover of time by an irregular and irrationally measured Gregorian calendar and its accompanying micro-organizing device, the mechanical clock?

Plotting the growth curves of human population, machine, and money, we see that the complete infusion of the 12:60 artificial timing frequency creates an unprecedented acceleration, the exponential peak of which occurs at the moment of the Inevitable Event. For this reason, according to the Law of Time, it is important to comprehend even more deeply the nature of calendars and their effect, especially with regard to the current global standard.

Because the calendar is a macro-organizing principle, when accepted over time it establishes in the mind, individually and collectively, a set of perceptions that are automatically taken for granted as being "real" and "indisputable." These sets of perceptions define the paradigm by which a people, culture, or even an entire civilization operates. The Gregorian calendar, the current global civil standard, is the paradigmatic macro-organizing principle in which are embedded all the laws, customs, institutions, and scientific principles governing the present global civilization-not to mention all the holidays of the Vatican-ordained Catholic Church. According to the Law of Time, the current calendar is an irregular standard of measure; its units of measure do not correspond. This calendar represents, therefore, the institutionalization of disorder and entropy. Because it has existed for a sufficiently long duration in the human historical cycle-2,000 years, including its predecessor, the Julian calendar-the perceptions fostered by the unconscious acceptance of the Gregorian calendar are taken as the unshakable bedrock of nature and reality. All current beliefs-economic, political, and scientific, from democratic neo-liberalism to the special theory of relativity-are actually products of the underlying perceptions promoted by this calendar, and have no reality apart from the beliefs about time that the calendar engenders. *Change the macro-organizing principle and you change the paradigm.*

THE NEED FOR A TRULY "NEW MILLENNIUM"

As the global civil standard, the artificial, irregularly measured Gregorian calendar is a self-reinforcing feedback loop. As such, it furthers and maintains all linear time concepts, thereby establishing a host of entropic, disordered value concepts such as the violent universe, the degradation of matter, quantum physics, the arrow of linear time, the doctrine of techno-economic inexorability, and an attendant host of unresolvable problems-crime, drug abuse, terrorism, environmental deterioration, and so forth. Why? Because as an irregular standard of measure, the Gregorian calendar is incapable of producing harmony. Only harmony can unify. The Gregorian calendar is not a unifying harmonic standard. Lack of a unifying global standard exacerbates all current conflicts. Condition the mind to an irregular standard and the mind will adjust to disorder and chaos as normal conditions of existence.

The world's racial, tribal, historical, and religious conflicts are embedded in and a function of different timing systems (calendars), all now coordinated within a master irregular timing standard and macro-organizing principle, the Gregorian calendar. In this calendar's irregularity is embedded the view that the world of the inevitable degradation of matter is the exclusive object of all present-day science, and hence is also reflected in the entropic nature of global civilization and its deteriorating social processes. The Gregorian calendar conditions the mind to hopelessness of resolution. Without a unifying harmonic standard humanity is incapable of finding long-term resolutions for any of its problems. Disharmony can never produce harmony. Only harmony can produce harmony. All conflict can only be resolved by the application and within the context of a harmonic timing standard.

Now, following the attack on the Twin Towers and the Pentagon, we can say that the Gregorian calendar is bringing history to an end. The Inevitable Event was programmed into the Gregorian calendar, and the Gregorian calendar usurped the power of all calendars in the thirteenth and final baktun cycle of history. When the third millennium officially opened at the dawn of the year 2001, the pride of industrial man was at an all-time high. Would it be a millennium of peace or one of war? If the last century of the second millennium was the century of total war, was the third millennium going to do anything but inherit the unfinished programs of the old millennium? Could the Earth and the biosphere withstand a millennium of total war? Hardly. The Vatican "jubilee year," which ended with the beginning of the third millennium, turned sour with the Twin Towers apocalypse, as is vividly reflected in a photo of Pope John Paul II taken just after the Inevitable Event. The Gregorian calendar marks its inception with the birth of Christ, a date and moment that was never historically noted, and so is shrouded in speculation and conjecture. Now the twisted civilization of Gregorian time is locked in mortal combat against a terroristic specter that it alone could have projected into manifestation. Soon, by biospheric standards, the world of artificial time will be over and gone. And then the millennium will be truly new.

The very word *millennium* conjures possibilities of Earth-shattering events and cosmic prospects. If the inception of the Kali Yuga, 3102 B.C.,can be said to be the point where the historical process became irreversible, eleven years after history began in 3113 B.C.,then in counterbalance, the Inevitable Event, 2001, which had to occur eleven years before the end of the cycle of history, A.D.2012, was more than just millennial. It was the termination of more than 5,000 years of the irreversible motion of artificial time. Such symmetry-eleven years after the beginning and eleven years before the end of history-is the hallmark of the synchronic order. For 5,100 years the count of days has numbered the long and increasingly perilous saga of human civilization. How bright was the beginning and how grim will be the end?

There at the beginning of the cycle was the "first city," Uruk. There at the end of the cycle, the fallen Twin Towers of Babel of the "last city," New York (= New Uruk), the ultimate monument to history itself and the final event to initiate the actual closing of the cycle of history.

> *There it is, the city of Uruk. Urshunnabi, climb up on that wall, the outer all shining with the brilliance of burnished copper. The seven wise men laid the foundations. One third of the city is buildings, cunningly executed, one third of the city is garden with rose and bird, and one third of the city is field with the temple of Ishtar within. Goddess of love and struggle.*
>
> \- *THE EPIC OF GILGAMESH*[6]

If Uruk is the place where the seven wise men laid the foundations, those foundations were measured by the 24 hours, 60 minutes, and 60 seconds derived from the 360 degrees of the circle. Fifty-one centuries later, the gardens are all but gone, the fields themselves mechanized and chemicalized by the technosphere. Earth's inhabitants are in terror. Five weeks after the Inevitable Event, now known simply as 9-11, the end of history still smolders. After the struggle, will the goddess of love return?

▼



5

The Climax of History, the Fifty-six Years of Hiroshima—Artificial Time Runs Out

THE IMAGE of the Noospheric Time Map-Wave Harmonic of History on plate 5 of the color insert, showing the concurrent evolution of the different calendars of the major civilizations of the world (the illustration is by no means exhaustive), is intended to demonstrate the fact that the human race was not unified by a single coherent timing standard throughout twelve of the baktuns of historical development. It was only in the thirteenth and final baktun that humans became organized by a single timing standard. However, it was not a timing standard in accord with the synchronic order of the Law of Time, but the artificial 12:60 timing frequency as represented by its two organizing instruments, the Gregorian calendar and the mechanical clock.

The seeds of this moment had already been planted in the noosphere at the beginning of history. From both Sumeria and Babylonia the taint of the 12:60 frequency then spread through the noosphere and, by means of historical dissemination and conquest, throughout the Old World. By the time the historic moment arrived to ripen the 12:60 frequency into its full fruition-A.D. 1618, the beginning of the scientific revolution and the thirteenth baktun-there were virtually no longer any cultural traditions governed by the natural 13:20 timing frequency. The civilizations and peoples of the New World were now under the subjugation of the prevailing world order of European global imperialism. The stage was set for the brief but final phase of mechanization, of which the technosphere itself is the climax.

What the Noospheric Time Map also delineates is that the 13:20 frequency was the unconscious organizing factor of prehistory, and that, undoubtedly, a key timing system intuitively evolved among many prehistoric peoples independently of one another. This was the universal, harmonic solar-lunar standard of the Thirteen Moon/2 8-Day calendar. The defining point of history arrives with the establishment of a 12:60 timing standard within the noospheric unconscious. This frequency predominates in the development of twelve-month pseudosolar calendars, as well as the twelve-month synodicallunation calendars that are not the measure of a solar year. These two commingled systems are entwined throughout the ancient history of the Old World as the central thread of development shaping the conception of time and resulting in what were to become the two dominant instruments of human time reckoning, the Julian/Gregorian calendar and the mechanical clock.

Julius Caesar himself instituted the famous "calendar reform" that created the 446-day year of confusion in 45-44 B.C.,and established a calendar that was just as patently confusing. Julius Caesar's was not the only calendar reform in the ancient world. The Essene movement, founded by someone known simply as the Teacher of Righteousness and of which Christ was supposedly a member, began as a revolt against the Hebrew lunar calendar. The issue was the need for fixed holidays within the solar cycle, something that is virtually impossible in a lunar calendar that retrocedes eleven days every solar year. There is strong reason to believe that among other calendars, the Essenes favored the Thirteen Moon/2 8-Day calendar. This even leads to the question: did Christ himself follow a thirteen moon calendar? In any case, it is the 12:60 frequency transmitted through the irrational disorder of the Julian/ Gregorian calendar that captures the mind of the human race and the biosphere during the final years of the cycle of history. And it is precisely for this reason that the pace of human civilization becomes exponentially and entropically accelerated during the last few centuries of its development.

Shocked into higher consciousness by its own barbarism masquerading as civilization, at the end point of history the human has the opportunity to return to the natural 13:20 frequency of synchronization. This return would mark the emergence of humanity from the unconscious mechanistic compulsion of artificial time into the conscious field of post-history. The only possible option to unify humanity-once the yoke of the Gregorian calendar is removed-is the true solar-lunar calendar of Thirteen Moon/28 Days. With the possibility of this positive end in sight, we may turn to a more descriptive and definitive analysis of the technosphere. In this way understanding the modalities of the technosphere as a distinct and entire process, we

Gregorian Calendar 28-Year Cycles: 1945–2001, the Age of Terror

It takes twenty-eight years for the Gregorian calendar to run through its cycle of permutations. Every twenty-eight years, like a phonograph record of time—a chronograph—the Gregorian calendar guides its users through a mentally debilitating construct of unevenly measured and irrationally named months, paced by a system of 7-day weeks that bears little relation to the lengths of the months or years. In addition, every four years there is an extra day. Within this medieval mathematical jumble are kept the collective unconscious programs that repeat every twenty-eight years. What happened in 1945 will somehow repeat or have an effect again in 1973, in 2001, and then in . . . it's up to you. You can change this if you want to.

First day of the year	Tuesday	Wednesday	Thursday	Friday	Sunday	Monday	Wednesday	Friday	Saturday	Saturday	Monday	Thursday	Tuesday	Sunday
Hiroshima 1945 – 72						1945								
	1946													
		1947												
												1948		
										1949				
					1950									
						1951								
													1952	
			1953											
								1954						
									1955					
														1956
	1957													
		1958												
			1959											
				1960										
					1961									
						1962								
	1963													
							1964							
								1965						
									1966					
					1967									
											1968			
		1969												
			1970											
								1971						
										1972				
Twin Towers 1973 – 2000						1973								
	1974													
		1975												
												1976		
										1977				
					1978									
						1979								
													1980	
			1981											
								1982						
									1983					
														1984
	1985													
		1986												
			1987											
				1988										
					1989									
						1990								
	1991													
							1992							
								1993						
									1994					
					1995									
											1996			
		1997												
			1998											
								1999						
										2000				
Inevitable Event 2001 - ?						2001								
	2002													
		2003												

2004 Year of the Great Calendar Change

Where will you be? 2012

might then develop a deeper insight into where we have just been and why we need to go somewhere else.

The technosphere defines a 56-year cycle, 1945-2001, coordinated by two complete Gregorian 28-year cycles. For any Gregorian calendar year, the days of the weeks in their irregular monthly succession and in relation to the permutation cycle of leap years repeat precisely every twenty-eight years, during which time there are always exactly seven leap years. This means that Gregorian calendar years 1945, 1973, and 2001 possess the same exact annual arrangement of the days of the week in their monthly succession. If today is Sunday, November 11, 2001, so it was in 1973, and likewise in 1945. In this regard the Law of Time frames the cyclic recurrence of the otherwise irregular 12:60 Gregorian calendar by the intrinsic formulation 28:7. That is, just as the 19:7 factor coordinates the lunar calendars every nineteen years, there being seven intercalations of the thirteenth moon during that cycle, so in the Gregorian calendar every twenty-eight years there are always exactly seven leap days and years.

Understanding a calendar as the instrument that locks the conditioned programs of a given culture or people into place, we can now understand how the unconscious metaprogram of the macro-organizing principle of the Gregorian calendar cumulatively recycles all its millennial programs every twenty-eight years. Since its inception in 1582, the Gregorian calendar has been dragging forward a host of conditioned thought forms and perceptions, including those inherited from 1,500 years of the Julian calendar that it had reformed. At points of dramatic break in the continuity of human consciousness, a new set of cycles is set to recur. Such was the case in the year 1945, with the awesome blast of Hiroshima. The entirety of the mind field conditioned and held in place by the Gregorian calendar then reaches its full fruition during the two subsequent 28-year cycles, fifty-six years in all-thus bringing forward two millennia of conditionings, conflicts, and unconscious death wishes or apocalyptic programs. The first cycle was initiated in the year 1945, the year in which Vernadsky died, the atomic bomb was tested once and used twice, and the Second World War came to an end. That year, 1945, marks the beginning of the technospheric bubble. It is most telling that the Second World War was concluded at the beginning of this 56-year cycle of the technosphere, for it was a war concluded not with peace but with instruments of mass destruction and terror. Thus began the 56-year era of Atomic Terror.

The technosphere has its origins with the full capture of the human mental field by the 12:60 frequency in 1618. From 1618 onward, the noosphere is increasingly obscured by a mental field known as the *technospheric sheath.* Slowly but surely, the technospheric sheath replaces civilization. This is first done by the introduction of mechanistic linear time. It is important to note that the Julian count, the basis of all modern scientific calculations, is a scale created by Thomas Scaliger in 1583, twenty-one years after the 1562 Mayan book burning. This linear time scale, like the Gregorian calendar reform itself, was intended to co-opt the Mayan thirteen baktun Long Count by setting a count of days that begins the first of January, 4713 B.C., or some 1,600 years prior to 13.0.0.0.0, the beginning of the thirteen baktun count in 3113 B.C. This deliberate historical act, the Julian count, along with the Gregorian calendar and the mechanical clock, established the paradigmatic notion of the linearity of time in the ripening field of scientific thought. Reflected in the noosphere, this linear, irreversible time concept levels and stunts the realization of human mass consciousness. In fact, during the technospheric cycle, especially after 1754, the ceiling of human consciousness is maintained by a preoccupation with mechanistic third-dimensional operations while becoming increasingly alienated from the organic order of reality. This creates the 12:60 consciousness constant, a mental ceiling that actually diminishes in proportion to the increasing rates of multiplication, propagation, and intrinsic velocity of the machine.

With the actual rise of the Industrial Revolution, dated in the noosphere to A.D. 1754, the synchronic point at which mechanization becomes an irreversible factor of the biosphere, the technospheric sheath, henceforth enters its next stage, going from a purely mental sheath to the industrial sheath, the prelude to the proto-technosphere itself. The industrial sheath spreads throughout the biosphere between 1754 and 1901, the official beginning of the twentieth century. At this point we enter the forty-four years of the proto-technosphere, 1901-1945. During this critical stage of the proto-technosphere, the actions of human behavior interacting with machine technology make the expression of true culture increasingly difficult, if not impossible. Civilization becomes a set of symbols purveyed through museums, galleries, and theaters, and recorded and reproduced in ever more advanced technological forms. But what of culture, which is not the same as civilization-what becomes of culture?

To begin to answer that question, some further definitions are in order. The technosphere is defined by and based upon one key term: *technology.* According to the common dictionary definition, which already reflects the mass mind, technology is "the totality of the means employed to provide objects necessary for human sustenance and comfort."l Today virtually all the means employed are themselves mechanical in nature. In common parlance, therefore, technology refers to the complex apparatus of mechanization. In fact, technology *is* mechanization; it is the ability to convert human labor into processes carried out purely by machine-oriented or mechanical means. This is also inclusive of the entirety of computer technology, which represents the mechanization of the more purely mental processes of thought and communication.

Mechanization, we must remember, originated in the clock, in the mechanization of time. It is the mechanization of time that presupposes the tendency toward mechanization as a state of mind within the noosphere. Since artificial time is characterized by the illusion of an inexorable and irreversible linearity, the compulsion toward materialism is also experienced in the same way, an inexorable motion spearheaded by the advance of ever more improved machines. The machines themselves are the products and means of industrialization-the technological transformation of raw goods into consumer goods, a process accounting for much of the free energy introduced into the biogeochemical combustion of the biosphere.

Inseparable from mechanized technology, too, are materialism and the concept of the World Market and, more recently, of globalization. Materialism is implicit in the dictionary definition of technology as the means employed not only for human sustenance but also for human *comfort.* This comfort can only be of a material form or nature, hence the pursuit of comfort through mechanized technology can only be for the furtherance of a philosophy and exaggerated lifestyle of materialism-the belief that only the material things of this world have any value. Of course, the value of material goods and comforts increases when the value of money is put into the technospheric equation. The first stock market opened early in the eighteenth century, providing a place where money could be used as speculative capital to promote the advance of commodities and machine products. The entire sphere involving commodity production and its conversion into consumer products eventually came to be known as the World Market. Integral to the success of the World Market was the creation of the modern banking system, based on the institutionalization of interest rates and the principle of lending money to companies for the purpose of furthering the transformation of the biosphere into the technosphere.

While the concept of the World Market prevailed for a long time as the definition of the system for exploiting and extracting natural resources from the biosphere, and then converting them into industrial goods to be consumed by the human populace worldwide, globalization is far more recent. Globalization represents the absolute triumph of capitalism as the dominant economic doctrine of the human species in the biosphere, and the absolute basis of the technosphere in its final phase of development. As such, globalization is the economic system of neoliberal market economics that treats the whole world as the proper sphere of its policies and practices. It is a specialized form of monetary imperialism that gives rise to and is supported by the doctrine of monetary politics, the use of money as a means of coercion or even for the buying out of whole governments. Of course, the principle practitioner of monetary politics is the nation with the most money, the United States of America, home of the World Trade Center.

Fostering corporate multinationalism, globalization is inseparable from the consumer philosophy it promotes. Consumerism is the devaluation of the human into a link in the chain of the cycle of industrial production, the object of globalization being to inspire and promote a massive and wide-scale consumerism worldwide. This is what is meant by such phrases as "increasing consumer purchasing power" and "opening new markets." To promote and defend its interests, the all-pervading system of globalization first developed the World Trade Center, and in the last decade, following the end of the Cold War, the GAIT and the WTO, the global "Chamber of Commerce."

As a political hegemony, globalization is managed by the G-7 group of the seven most industrialized nations (the United States, Canada, the United Kingdom, France, Italy, Germany, and Japan-now, with Russia, sometimes referred to as the G-8). This organization, headed by the finance ministers of these seven countries-like the seven wise men of Uruk at the beginning of history-was secretly formed in 1974 by the CIA, one year after the completion of the World Trade Center Towers and the formation of OPEC. The first public meeting of the G-7 occurred in the summer of 1990, just prior to the Iraqi invasion of Kuwait. The doctrine and system of globalization-now overtly controlled by the G-7 and its chief ally, the Euromarket nations-is inseparable from industrial technology as the means employed to provide objects necessary for human sustenance and comfort. Implicit in the philosophy of globalization is the right of the G-7 to promote and defend its way of life, regardless of its ultimate effects on the biosphere and at the expense of ideologies and beliefs not consistent with it. To defend itself, globalization has at its disposal the U.S. military, the command of which is housed by the Pentagon, and the new technospheric multinational military cartel, NATO. In a word, globalization is the triumph of the military-industrial complex.

From the point of view of the biosphere, globalization is the cancer of the human species consuming non-renewable resources and, through the release of free energy, effecting the final critical increase in biogeochemical combustion. The planetary instrument for furthering the entire process and philosophy of globalization is the technosphere. The technosphere may be defined as the entire apparatus of mechanized technology and its support philosophy (globalization), understood as an artificial sphere encompassing the globe. As such, the techno sphere is discontinuously interspersed within the biosphere. More precisely, the technosphere is located physically and mentally between the biosphere and the noosphere, in other words, between the Earth's vital sphere and its mental envelope.

Being the description of an evolutionary stage, the technosphere is governed by the Law of Time as a 56-year event continuum along the lines of an artificial planetary cocoon. Insofar as it is the projection of human thought, the technosphere is the materialization of the sum mental processes denoted and conditioned by mechanization in all its aspects, and that have their primary root in the mechanization of time. It is the mechanization of time that essentially establishes the artificial timing frequency as the capacity to engender the machine and, consequently, an artificial structure, the technosphere. Because it is artificial, however, its duration is highly limited and is subject to the inherent inconsistencies and contradictions in human thought and social structures because of the aberrant effects of adapting to artificial time in the first place. The effect of adaptation to artificial mechanized time creates a social-political hierarchy known as the technocracy-rule according to the needs of technology. It is the effect of maintaining the technocracy and the technosphere itself that establishes the inability of human consciousness to do anything more than remain in a constant, servile, and unchanging state of machine dominance. All the while, by contrast to the unchanging condition of consciousness, the machines evolve exponentially in number and complexity. As Marshall McLuhan so correctly put it, the humans are the bees of the machine.

To be fully understood, the technosphere cannot be seen apart from its place in the biosphere-noosphere continuum. The technosphere represents the absolute control of the biosphere by artificial 12:60 time. Artificial time generates the artificial medium of money, hence the operating philosophy of the technosphere: "time is money." Money is the lifeblood of the technosphere. Servitude to money draws humans away from the biosphere in order to be devoured by Mammon-the technosphere as an all-consuming entity. In this process the humans get money in return for selling their bodies and souls to artificial time, usually eight hours a day, often to produce artificial goods or for service in maintaining the artificial system of money itself. This money gained from servitude is used to buy consumer goods, including more machines of every kind, and thus the human participates as a vital link in the cycle of biogeochemical combustion. In this way the mechanized lifestyle converts the human-the consumer-into the biomass necessary for maintaining the technosphere.

By 2013
Earth is galactically synchronized into a new biogeological epoch: the psychozoic Era.

As the mental envelope of Earth, above and discontinuous with Earth, the noosphere can only mean one thing: the advent of universal telepathy among the humans.

The difference between the new time and the old time is like the difference between heaven and hell.

Planetary 9-11, 2001
inaugurates biogeochemical combustion, biospheric means of transformation, and self-mutation.

Technosphere:
Biospheric agent devised for maximum biogeochemical combustion.

Built in an area known as "Hell's Bottom"

The Pentagon
1941–200?

Impregnable fortress of the American war machine, meant to protect "democracy" = American domination of world market and foreign/economic policy of globalization. "The form of the Pentagon . . . is that of a pentagram, the chief magical aid for gathering power. When a pentagram is drawn with its base toward the north, and its chief point to the south, it is useful for negative or black magic purposes."
—*Transformative Vision*, page 249

*Note: Gregorian calendar coordinated by Law of Time. Repeats precise order of days and weeks precisely every 28 years.

By 2012
Humans realize a permanant condition of peace through culture.

By 2009
Humans are reorganized by the Law of Time and begin the construction of a galactic culture on Earth.

Dismantling of the technosphere stabilizes the biosphere and reveals the noosphere—2005.

By leaving artificial time and returning to natural time via the Thirteen Moon calendar, humans advance the noosphere.

2004: Last opportunity for humans to change their macro-organizing principle.

Exhaustion of the Technosphere—2001–04.

Exponential growth curves of money, machine production, energy, and people climax.

Planetary 9-11: time runs out on the technosphere.

"New" millenium nipped in the bud; civilization R.I.P., 2001

Technosphere:
Interlocking interactive pentagon of five artificial systems - WTC = Nerve center and hub of the technosphere and its driving power, globalization.

Biosphere:
Controlled by artificial (12:60) time.
Time is Money—lifeblood of the technosphere.

Humans devoured by Mammon. Get money in return and create biomass to maintain technosphere.


NOOSPHERE
PAX CULTURA
PAX BIOSPHERICA
PERIMETER OF BIOGEOCHEMICAL COMBUSTION
Communication
Internet
Satellite
Television
Radio
Cell Phone
Commodity Production
Raw Goods
Forests
Agriculture
Minerals
Biospheric Depletion
Ocean
Industrial Goods
Biospheric Degradation
Transport
Truck
Automobile
Shipping
Air
Rail
Biospheric Degradation
Biospheric Depletion
Noospheric Obscuration
Planetary
World Trade Center
1973 2001
9-11
Inevitable Event
Energy
Hydroelectric
Fossil Fuel
Nuclear
City
$$$$$$
Nexus of Consumption (Market)
TECHNOSPHERE
BIOSPHERE
14 Years
28 Years
14 Years
28 Years
Globalization
World Market
1973 World Trade Center
1987 Harmonic Convergence
2001 The Inevitable Event
1945 Hiroshima

56-year cycle of Hiroshima
"Age of Terror"
Technosphere Replaces Civilization

Biosphere–Technosphere–Noosphere

As an operating planetary structure, the technosphere consists of five interactive components.

1. COMMODITY PRODUCTION

Commodity Production, the basis of the entire World Market as a biospheric system, refers to the transformation of natural resources through industrial means into consumer products. Commodity production alone accounts for the complex of industrialization that brings the World Market and the technosphere into existence. According to *The Biosphere Catalogue,* the post-World War II growth of the World Market necessitated the establishment of the World Trade Center, a global complex (114 such centers in 1985), but with its principle coordinating unit being the Twin Towers in New York City, home of the World Trade Institute and the corporate offices of the New York Stock Exchange, the key to the world money and commodities market.

2. CITIES

Cities, the second technospheric component, represent the human social organism or marketplace for accommodating the production and consumption of industrial goods. Civilization is city life as it has evolved from Uruk to New York (= New Uruk). While prior to industrialization the city depended on a healthy agrarian economy for its support, industrialization pushed the city to new heights of artificiality, not the least of which were round-the-clock lighting systems that allowed for 24-hour consumer markets. As such, the city is the nucleus of the technospheric system, the hub of its commodity production, of its energy consumption, and of its transport and communication empires. The growth of the cities around the world is exponential in the second half of the twentieth century, reflecting the triumph of the technosphere. It should be noted that in the fifty-six years of the technosphere, the human population almost tripled-from 2.2 to 6.2 billion, a growth demonstrated in the vast expansion of the large urban centers.

3. ENERGY

Energy is the third component of the technospheric complex. The tremendous needs of industrial production have transformed the natural energy processes of the biosphere into gigantic artificial complexes for the production of energy to maintain factory and city alike. The impact of the different artificial energy systems upon the biosphere has been enormous. These systems include coal, oil, and fossil fuels in general, as well as hydropower and nuclear energy. The whole syndrome of artificial time, artificial means, acceleration of the machine, and expansion of human population has required and created the enormous output of artificial energy into the biosphere and contributed greatly to the destabilization and loss of natural resources and atmospheric and hydrospheric contamination through the release of toxic "free energy" by-products.

4. TRANSPORT

Transport. Without the highly industrialized transport systems, the commodity production, the vitality of the cities, and the access to provisions of fuel required for the energy systems would collapse. No sooner had industrial production begun early in the eighteenth century than the first artificial transport systems came into being: the steam- or coal-driven locomotive, and the great transoceanic shipping lines. By the twentieth century, the railroad system and worldwide shipping industry were supplemented by the invention of the combustion engine, which made the trucking industry possible. Following World War II, rocketry and jet propulsion established the transportation might of the great airline companies of the second half of the twentieth century. It is no coincidence that commercial airplanes, the symbol of the technosphere's advanced transport systems, were used to bring down the Twin Towers and to penetrate the Pentagon.

5. COMMUNICATION

Communication is the fifth component that unifies the technosphere into one whole system in touch with itself everywhere. From telegraph to telephone, radio, television, and then finally fax, cell phone, and the Internet, the industrial-era technologies, with their electronic instantaneity, have created the vast communication networks and media empires that keep the world humming and promote globalization above all. When considering modern communication we must also bring into focus the chief method of globalization, which is marketing-propaganda on behalf of consumerism. Marketing is the use of means of mass communication to control the mind of the consumer. In the final stage of globalization, marketing replaces consciousness, or rather, marketing is the manipulation of consciousness-the latter already having been reduced to a stunted level-for purposes of consumerism, or for ideological needs such as patriotism and fear campaigns. The Internet, the marriage of computer and telephone technologies, represents the final stage of the Tower of Babel, and the completion of the process of globalization. The only place to go after the Internet is technology-free telepathy.



The Tower

From the biospheric perspective, this five-tiered complex of the technosphere is a whole unit. All the subsystems evolved together to establish the structure and operating procedures of the technosphere. When the technosphere goes, the entire system folds. This is what is now beginning to occur. Following the Inevitable Event, the whole technospheric system will be coming down slowly over the next few years, like a giant circus tent that has lost its central prop. How gracefully or gracelessly this happens is dependent on the response of the Pentagon-or the will of humanity to rouse itself in the face of even worse barbarisms.

Because it consists of five interactive components, the techno sphere can be graphically depicted as a pentagon, a five-sided figure. At the center of this pentagon of the technosphere are the World Trade Center Twin Towers. The actual Pentagon, which was attacked along with the Twin Towers, was designed in the late 1930s to house the U.S. Department of War. Its construction occurred in the years 1941-1943, in an old neighborhood of pawnshops and bars called Hell's Bottom.2 When it was built it was the world's largest office building in terms of actual space. Of course, when they were built, the Twin Towers of the World Trade Center were the world's tallest office buildings. The structure of the Pentagon is the prototypical morphology of the structure of the five systems that constitute the technosphere. The Pentagon was the impregnable fortress of the American war machine, protecting American interests and globalization around the world. If there were two central points-actual and symbolic-to what is known as the military-industrial complex, it was the Pentagon and the World Trade Center, and this is undoubtedly the reason why they were both targets of the Inevitable Event.

What is architecturally noteworthy about the Pentagon is that it is designed with five inner pentagonal corridors and office slabs, and that it is constructed with its odd point to the south. Since a pentagon is actually a pentagram, a five-pointed star with its points connected, the Pentagon represents an *inverted* pentagram, as its odd point faces south rather than north. In the traditional Tarot deck it is interesting that the Fifteenth Major Arcana, The Devil, contains an inverted pentagram between the horns of the Beast. Paul Foster Case writes, "This is a key to the whole meaning of the figure [of the devil]. For the Pentagram is the symbol of man, and an inverted Pentagram suggests the reversal of true understanding of man's place in the cosmos."3 While the Fifteenth Major Arcana contains the pentagon as the inverted pentagram, the next card, the Sixteenth Arcana, is The Tower, which shows the tower being struck and broken apart by lightning (fire of heaven), with humans falling or jumping out of the windows to their death-as accurate a symbolic depiction of the collapse of the Twin Towers as could be found.

What the startling conjunction of these symbolic correspondences points to is the profoundly archetypal nature of the Inevitable Event. It has been prefigured and prophesied, and has now come to pass. No matter how much America and its allies, many of them bought for a price, may strike back, the deed has been done. The Towers are gone; the Pentagon has been penetrated. While it will take several years for the full realization of the absolute magnitude of this archetypal event to sink into the



The Devil and the Pentagon

collective mind, it is important to demonstrate the actual structure in time of the techno sphere so that the finality of its end may be seriously considered, and the gate to the future, which has thereby been opened, can be made clearly visible.

As we have shown, the technosphere is a structure totally brought about by the 12:60 timing frequency, and thus is purely a function of the latter. As such, the technosphere is embedded in the global macro-organizing principle of the 12:60 frequency, the Gregorian calendar. Two 28-year cycles, each one divided into four 7-year subcycles, define the duration of the technosphere. Remember that the Gregorian calendar repeats every twenty-eight years. As we have pointed out, the 56-year cycle of the technosphere, 1945-2001, is preceded by the 44-year cycle of the proto-technosphere. The two World Wars were a function of the proto-technosphere, the final major act being the construction of the Pentagon, specifically for consolidating the American war machine-the world's largest office building means that the world's largest business is war, with a $318 billion budget for the year 2001-2002 alone!

The fifty-six years between Hiroshima and the Inevitable Event were the age of terror, for it was atomic terror that initiated the technosphere in a baptism of nuclear fire, and in the end, it was an unimaginable suicidal terror that brought down not just one, but both of the Twin Towers of Babel. The final collapse of the technosphere is also the final war between blood and money. Artificial time has run out. Only a new time will be able to regenerate the biosphere and spiritually revive mankind. What follows is a chronological description of the eight 7-year stages of the fifty-six years of the technosphere. Note the persistence of certain themes. (See plate 5, Noospheric Time Map-Wave Harmonic of History.)

GREGORIAN A, 28-YEAR CYCLE: TRIUMPH OF THE WORLD MARKET, 1945-1972

1. 1945-1951. CYCLE OF THE BOMB: ATOMIC TERROR AND THE DIALECTIC OF THE COLD WAR.

During the first dynamic 7-year cycle, with the triple event of the first test of the atomic bomb and its two detonations at Hiroshima and Nagasaki, the biosphere becomes irrevocably altered by the introduction of a constant, steady state background radiation into the atmosphere, the actual inception of the biogeochemical combustion. This act officially establishes the technosphere. The reality is that the humans also created their first weapon of mass destruction. It is this act that also immediately sets in motion a destabilization of the human consciousness in the noosphere.Within two years, Mahatma Gandhi, the world's foremost pacifist, is assassinated, as a "free" India is partitioned into three parts-India, Pakistan, and what is later to become Bangladesh. In the same year, 1947, the iron curtain between communist Eastern Europe and the West, epitomized by the Berlin Wall, turns the enmity between the two major powers, the Soviet Union and capitalist America, into the Cold War. The subsequent formation (1949) of the NATO military cartel counters the United Nations, which was founded in 1945 to replace the League of Nations. The UN now has the task of keeping World War III from happening by providing a forum where the "superpowers" can keep their cold war from heating up, and that will contain and manage the spread of nuclear power. Nonetheless, the terror of the Bomb as the ultimate deterrent engenders the arms race. Soon Russia, the United Kingdom, France, and eventually China get the Bomb. War in Indochina, the establishment of the Israeli state in Palestine (1948) at the expense of the sovereignty of the Palestinian people, and the completion of the Chinese Marxist Revolution under Chairman Mao are the highlights of 1949, followed by the Korean War in 1950. All this demonstrates the instability of the world. At the same time, 1949, commercial television production begins in the United States; the age of radio is replaced by the "tube." Americans also begin building freeways and the new system ofInterstate highways marking the triumph of "automobile culture," and the beginning of the suburban consumer lifestyle.

2. 1952-1958. CYCLE OF THE OPENING OF THE TOMB AND THE BEGINNING OF THE SPACE AGE.

In the summer of 1952 a Cuban archaeologist discovers the tomb of the Mayan sage, Pacal Votan. This unprecedented archaeological event marks the beginning of the final sixty years-three katun cycles-of the Mayan thirteen baktun cycle of history. In the following year, 1953, the superlethal H-bomb is tested. The DNA code is discovered, as are the Earth's radiation belts. The United States and Russia conduct numerous nuclear weapons tests in Nevada, Siberia, and the Pacific Ocean. Wars for independence occur in various African states, and in general the era of European imperialism is at an end, followed by the neo-colonialist (Third World) era of guerrilla warfare, poverty, and social instability. In 1956, the year the Russians launch the first sputnik and begin the space age, the United Nations tables the issue of calendar reform indefinitely, thus closing the chapter begun when the League of Nations proposed global calendar reform in 1931. The year 1956 also marks the beginning of the electronic pop culture of the technosphere, rock and roll. By the end of this cycle, the "space race" joins the arms race as a force in promoting the advance of the technosphere. Commercial airlines adapt to jet propulsion, and the great age of air travel begins, with the airport to become the centerpiece of globalization. Initial experiments in computer technology-Univac-and the first great computer corporation, IBM, announce the beginning of what is to become the major technology of globalization. A small fast-food franchise named McDonald's opens in the United States.

3. 1959-1965. CYCLE OF THE ATOMIC MIND EXPLOSION.

The July 26 Cuban Revolution of Fidel Castro, triumphant in 1959, establishes a communist state in the Americas and heightens the Cold War. That same year the Chinese communists bring to a definitive end the rule of the Dalai Lama in Tibet. In the Congo, the popular hero Patrice Lumumba is assassinated after only two months in office. Also in 1960, the human population hits three billion, an increase of one billion since 1930. In 1961 the Institute of Mathematics of the Siberian Branch of the Soviet Academy of Sciences begins the monumental mathematical analysis of Mayan hieroglyphic texts. The attempted 1961 Bay of Pigs invasion of Cuba is followed in 1963 with the assassination ofJohn F. Kennedy, an act that reflects a rising level of cultural turmoil in the United States. Martin Luther King Jr. emerges as a popular hero of nonviolence and civil rights, an issue that points to a more radical discontent in America, culminating in 1965 with the Watts race riots. Rachel Carson's book *Silent Spring* (1963) signals the rise of ecological awareness. The Beatles transform rock and roll into a world-class cultural phenomenon that foments a widespread countercultural movement and atomic mind explosion, fueled by Timothy Leary, LSD, hippies, and the new antiwar movement against the conflict in Vietnam. In 1961 Yuri Gagarin is the first man in space, and the Vatican II Ecumenical Council comes to the conclusion that the best way the Church will survive in the next century is through a strong Pope. The Vatican II document also includes an appendix on calendar reform, the wording of which makes it difficult for there to be any alternative but a watered-down version of the Gregorian calendar. This act seals the technosphere within the unquestioned confines of Gregorian time, ultimately turning the atomic mind explosion in on itself.

4. 1966-1972. FROM THE WHOLE EARTH TO THE WORLD TRADE CENTER: THE TRIUMPH OF THE WORLD MARKET.

In 1966 construction begins on the World Trade Center Twin Towers, while in 1968 World Trade Centers are independently established in Houston, New Orleans, and Tokyo. That same year, UNESCO hosts the first and only conference on the biosphere ever sponsored by the United Nations, "Man and the Biosphere" (MAE), but the program slowly dies on the vine. The cultural conflict in the United States and the entire world also reaches a fever pitch in the years 1967-1969. This ferment includes: race riots, antiwar riots, a march on the Pentagon, the assassinations of Martin Luther King Jr. and Robert Kennedy, and riots in major capitals around the world and on both sides of the iron curtain, as well as the Maoist cultural revolution in China. The excitement of the '60s climaxes in 1969 with the success of the Apollo XIII manned mission to the moon and the consequent feedback factor of the human race seeing itself instantaneously on television as the whole Earth beamed from space, an opening to the noosphere. Apollo XIII initiates the next phase of the space race, travel to other planets. Also in 1969, the Woodstock concert marks the apex of the early rock-and-roll culture and the visionary climax of the cultural revolution. The 1971 Concert for Bangladesh establishes rock and roll with a conscience. In 1970 the vision of the whole Earth is translated into the first Earth Day and the birth of the ecology movement. The United Nations follows two years later with the Stockholm Conference on the Environment. The revolutionary fervor of the previous years turns more violent, and repressive governmental police powers win the day. The first 28-year cycle ends with a whimper, the dynamic destabilization of consciousness reaches a plateau of normalcy-a normalcy to be increasingly punctuated by terrorist activity, as in the Palestinian takeover of the Olympic Village in September 1972. Both apart from as well as in reaction to such activity, the technosphere has now become all-dominant and all-powerful in human affairs.

SUMMARY, GREGORIAN A: 1945-1972

During this cycle, the dynamic of the accelerated geochemical combustion destabilizes the human consciousness while increasing the curve of the machine in human affairs. By 1973 the machine curve meets and surpasses the human population curve; this stabilizes human consciousness at a level of machine normalcy (MN). Human consciousness will remain stabilized at MN, largely through varying forms of terror and fear programming, for the duration of the second and final 28-year cycle. This normalization of human consciousness allows the diverse and rapidly evolving technological components of the technosphere to reach a point of consolidation. This stabilization of the World Market fosters its next and concluding phase: globalization and the triumph of marketing over human culture. It should be kept in mind that the instruments and weapons of mass destruction, of which there were none on January 1, 1945, have now proliferated to five different countries and provide the ultimate backdrop to these first twenty-eight years. The core of the UN's Security Council is formed by the five countries that possess atomic weapons. Geopolitically, the bio-

Machine Normal Consciousness in Relation to Technospheric Growth Curves

Human consciousness, overwhelmed by war—the ever-propagating machine and bondage to artificial time—succumbs to money and stabilizes at Machine Normal, the standard consciousness of the technosphere, which represents an ever-diminishing ratio of intelligence in relation to the growth curves of population, machine, money, and war.



sphere is in control of technocratic powers that are virtually all located in the Northern Hemisphere-whether it is the Pentagon, NATO, the World Trade Center, the United Nations, or the Soviet space program.

GREGORIAN B 28-YEAR CYCLE: CLIMAX OF GLOBALIZATION, 1973-2001

1. 1973-1979. CYCLE OF THE CONSOLIDATION OF THE TECHNOSPHERE: CLUB OF ROME, OPEC, AND THE G-7.

The dedication of the World Trade Center Twin Towers on April 4, 1973 (a repeat of the calendar year of the Bomb, 1945) is the counterpart to the construction of the Pentagon (1940-1941), which sponsored the bombing of Hiroshima and Nagasaki. The tallest buildings in the world when they opened, the 11O-story Twin Towers seal the position of New York as the "capital of the world," for on the other side of Manhattan is the glass tower of the United Nations. Simultaneous to the dedication of the Twin Towers is the formation of the Organization of Petroleum Exporting Countries (OPEC). With the exception of Venezuela, OPEC is largely an Arabic (Islamic) economic alliance that, for the first time in the history of the technosphere, brings a Third World influence into planetary politics. The subsequent "oil shortage" demonstrates the technosphere's vulnerability, which in turn causes a further "hardening of the arteries" of its consciousness-the covert formation by the CIA of the G-7. Also in 1973, after five years of study the Club of Rome issues *The Limits of Growth,* which in its analysis of trends foresees a major environmental (biospheric) crisis within one hundred years, yet nonetheless establishes and promotes the standard world model, a setting of production quotas at the 1973 level, to foster sustainable growth at least until 2020. The "standard world model" corresponds to the "normalization" of consciousness. The third war (previous ones having occurred in 1967 and 1949) between Israel and its neighbors occurs this year. By 1975, the world population is at four billion, up a billion since 1960. In 1976 Voyager II reaches Mars. In 1978 Karol Wojtyla becomes Pope John Paul II, the first global Pope, fulfilling the Vatican Council's requirements of a popular Pope to assure the survival of the Church into the next century. With Gregorian civilization triumphant, Mexico, home of the Maya, is the first country visited by the new Pope. In the same period, between 1978 and 1979, the Iranian Islamic revolution occurs, toppling the pro-Western Shah, signaling a heightened conservative Islamic resistance to Westernization and the technosphere. Japanese technology and corporate capitalist economy flourish, capped by the construction in Tokyo of the "New City" Shinjuku and, despite many environmental protests, the Narita airport. The mainstream global consciousness is now "comfortably numb" and on course to unprecedented materialism.

2. 1980-1986. CYCLE OF THE TRIUMPH OF THE TECHNO SPHERE.

The first cycle of the stabilized new normalcy establishes the triumph of marketing-the election of a second-rate American movie star for President, and the birth of the yuppie (young urban professional) generation of America. The rise of MTV signals the standardization of rock style as global culture; while the Live Aid global television concert on July 13, 1985, to raise awareness of AIDS in Africa, is the largest ever of its kind. The September 17, 1985 Mexico City earthquake, the worst in modern times to hit the world's largest city, demonstrates the continuing vulnerability of the techno sphere to natural catastrophe. The early 1980s witness the Intifadah uprising of Palestinians against Israel. The War on Drugs, an aggressive antidrug campaign waged by the West against narcotraffic, mostly from South America and the Middle East, heightens the new normalcy as world drug laws tighten, placing marijuana and psychedelics in the category of "hard drugs." Yet drugs continue to be a major social problem in the industrialized West. In 1986 President Reagan attacks Kadafy of Libya and invades Grenada, testing American ability to commit limited acts of aggression without inciting world censure. The construction of Biosphere II in Arizona, an effort to test the possibility of establishing an artificial biosphere on other planets, ends inconclusively. In 1985 in Bhophal, India, the worst modern industrial toxic chemical disaster occurs with more than 2,000 deaths, followed on April 26, 1986 by the Chernobyl nuclear power plant disaster, the worst since the beginning of the nuclear age. In America the suburban automobile culture gives rise to the super shopping malls. The personal computer (PC) is introduced, while electronic game arcades flourish. Sunday football becomes the major American television pastime, while television itself makes world soccer the number one competitive global sport; the broadcast of professional sports assumes the role of a primary noospheric diversion.

3. 1987-1993. CYCLE OF THE END OF THE COLD WAR AND TRIUMPH OF THE G-7.

On January 24, 1987 Voyager II sends back photos from Uranus; four days later, January 28, 1987, seven American astronauts die in a shuttle launch explosion. On August 16-17, 1987 the Harmonic Convergence peace meditation attracts hundreds of thousands who gather at sacred and natural sites around the world; later that year, October 19, 1987, the New York StockMarket crash occurs, the biggest point drop ever, and Russian Prime Minister Gorbachev initiates disarmament accord, or *glasnost.* By the end of 1987 the population is at five billion, up one billion since 1975. During 1988-1989, a rolling wave oflargely peaceful revolutions and civil uprisings throughout most of the Warsaw pact nations culminates on December 31, 1989 with the tearing down of the Berlin Wall-the end of the Cold War. At the same time, President Bush invades Panama to continue testing Drug Wars and limited-aggression capability. In the summer of 1990 an international bankers' reunion is followed by the first public meeting of the G-7. Every year henceforth, the G-7 meets publicly to set policy for globalization. Within a month of the first public G-7 meeting, August 1990, Saddam Hussein invades Kuwait, and Bush retaliates with the Gulf War, January-February 1991. In August 1991 Gorbachev is ousted in a putsch, marking the end of the Russian Marxist era. Destabilization, war, and genocide afflict the Balkans. A new wave of environmental concerns-ozone depletion, destruction of rain forests, and global warming-inspire a reactivation of Earth Day, 1990, followed two years later by the 1992 Rio Summit, the second United Nations Environmental Conference and the first in twenty years. The conference generates much paper, but the doctrine of sustainability (sustainable industrial growth) is the principle outcome. Meanwhile, with the absence of Marxist Russian economic influence, the neoliberal capitalist economics of America flourish as full-blown globalization, multinational corporations, and the prominence of the IMF and World Bank foment a uniform global corporate culture of cheap consumer services and franchised retail outlets for brand-name goods. This period also sees the rise of East Asian capitalist economies, although the Japanese economic bubble bursts in 1991. Early in 1993 a terrorist bomb explodes in the underground garage of the World Trade Center Twin Towers. The period 1989-1993 marks the beginning of the discovery of the Law of Time-the definition of the artificial 12:60 and natural 13:20 timing frequencies, the Dreamspell codes, and the decoding of the Telektonon Prophecy of Pacal Votan in 1993.

4. 1994-2000. CYCLE OF THE CLIMAX OF GLOBALIZATION.

In 1994, the GAIT Treaty is signed, the Levy-Shoemaker comet hits Jupiter, and a million Mricans die in the Rwanda massacre. The indigenous uprising in Chiapas, Mexico on January 1, 1994 provides a counterpoint to the triumph of globalization that is manifest through worldwide airport expansions, and an aggressive form of tourism that feeds the airline industry. Israel and Palestine enter the "peace process," while Yeltsin consolidates his power in Russia. This is the era of United Nations peace-keeping missions, mostly in the Balkans and Africa. Following the FBI/BATF -inflicted firestorm on a fundamentalist compound in Waco, Texas, a year later, in 1995, a terrorist bomb destroys the Oklahoma City Federal Building. The United States and the United Kingdom inaugurate control ofIraqi no-fly zones, enforced by regular bombing raids; the United States also conducts military actions in Somalia, as well as more successful ones in Haiti. This is the era of rapid expansion of computer and biotechnologies, exponential rise of New York Stock Exchange and the new specialized technologies exchange, the NASDAQ. Bill Gates of Microsoft typifies the rise of the new self-made billionaires of the Clinton era. In January 1995 the Kyoto earthquake occurs, followed by the Tokyo subway nerve-gas terrorist attack, while the Internet, the "information superhighway," is fully up and running. In 1996 in Brasilia, Brazil, the First Planetary Congress of Biospheric Rights signals rise of a new calendar reform movement with the proposal of the World Thirteen Moon Calendar Change Peace Plan, submitted to both the United Nations and the Vatican. In 1997 the Kyoto environmental conference on global warming sets policy, but the United States refuses to ratify it. In 1998 simultaneous U.S. embassy bombings in Kenya and Tanzania signal a new phase of war on terrorism, singling out a Saudi national, Osama Bin Laden, as the terrorist mastermind. By 1999 the world population is six billion, up one billion since 1987. In late spring 1999 NATO initiates a unilateral bombing campaign ofYugoslavia over the disputed region ofKosovo. The World Summit on Peace and Time, at the University for Peace, Costa Rica, sends emissaries to the Vatican and the United Nations with the Declaration of Thirteen Moon Calendar Reform; later in 1999 WTO has its first meeting in Seattle, which sparks anti-globalization riots. In 2000 the Y2K computer scare surrounding a bad time program fails to materialize. On Rosh Hashanah, September 28,2000, Hebrew year 5761, Israeli leader Ariel Sharon's presence at Temple of the Mount, Jerusalem, sparks a new Intifadah of Palestinians, which continues unabated through 2001, the official first year of the new millennium.

5. 2001-? *GOTTERDAMMERUNG* OF THE TECHNO SPHERE: FIRST YEAR OF THE THIRD MILLENNIUM, REPEAT OF GREGORIAN CALENDAR YEARS 1945 AND 1973.

In July 2001, G-7 meets in Genoa, Italy, as more than 100,000 anti-globalization protesters riot. In early September the United States and Israel walk out of the United Nations Conference on Racism in South Africa. Then, within ten days occurs the Inevitable Event, Gregorian 9-11, 2001, the cumulative synchronic pressure point where the technospheric bubble-the artificial time warp in the noosphere-bursts open, spawning in its wake the full-scale War on Terrorism-another name for World War III. The Inevitable Event exemplifies the built-in failure of the Gregorian calendar to commence another 28-year cycle as was done in 1945 and 1973. If the 1945 cycle began with the end of one world war, the 2001 cycle begins with the start of one. Since 2001 is also first year of the third millennium, the Gregorian calendar has created its own apocalypse, opening a noospheric fissure-the climax of the biogeochemical combustion of the biosphere. Now it is only a matter of time before the technosphere experiences total collapse. The nature and extent of the damage sustained during the collapse is in proportion to the intelligence that responds to the knowledge of its collapsing. If this 28-year Gregorian calendar cycle were to go unimpeded until 2029, it is not certain what would be left of the biosphere. But there is one thing of which we may be certain: *artificial, linear time has run out.* An American newspaper editorial at the end of 2001 sums up the crash of the dominant linear time paradigm: "History seems to have slammed into reverse gear around a world that was widely assumed a year ago to be moving in a straight line toward a more prosperous and secular future, one that would be shaped by stock markets and the Internet, not by turbaned zealots or theocracies that have or want nuclear trigger fingers."4

SUMMARY, GREGORIAN B: 1973-2001

With destabilization normalized, the technosphere replaces civilization and marks the end of culture-the new barbarism prevails, culminating in total war. The 9-11 is what actually completes the technospheric cycle. Henceforth it will be the advent of the noosphere, but not in the way predicted by the authors of *The Biosphere Catalog:* "The Noosphere as an active force consists in the harmonious synthesis of the Biosphere and the Technosphere by intelligence."5 By the analysis of the Law of Time, the intelligence is nowhere evident because there is no harmony of intelligence possible under the present timing standards that dominate all the major players in the present global conflict. Since the technosphere is totally a function of the artificial timing frequency, and since artificial time is now short-circuiting itself, there will be no techno sphere to harmonize when natural time is restored to the entire biosphere. Then the noosphere will commence, but only if there is world harmony. Only a harmonic standard will bring harmony to the world. The failure of the Gregorian calendar and its civilization, crystallized in the now-collapsing technosphere, must be quickly acknowledged. By adopting a harmonic standard as soon as possible, the shift to the noosphere can commence, rising and building itself up from the shards and ashes of the toppled technosphere.

▼

6

The Solution of the Law of Time

Get a New Calendar

> *"I am in favor of a standardized calendar for the whole world, just as I am in favor of universal coinage for all countries, and a supplementary artificial language (like Esperanto, for example) for all peoples. . . I am always ready to endorse any honest movement which will help unify the peoples of the world."*
>
> -MAHATMA GANDHI, QUOTED IN *THE JOURNAL OF CALENDAR REFORM,* 1931[1]

VIEWED FROM THE PERSPECTIVE of the noosphere, the failure of human civilization is the failure of the human being to become synchronized with itself in the correct time of universal nature. Instead of operating as a planetary organism in absolute synchronization with a knowledge of being coordinated by a common harmonic standard, humans race toward the end of history, dissynchronously operating under a plethora of calendars of differing measures enshrining competing belief systems, all globally coordinated by an instrument of irregular measure and obscure nomenclature-the Gregorian calendar. Dissynchronized and at odds with itself everywhere, humanity is broken apart into splintered mind fields, each controlled by a different timing standard, a fact about which the human race is virtually ignorant-to its own detriment.

India, with its different neo-Babylonian calendars, is at odds with Pakistan, which operates according to the Islamic lunar calendar; the Israelis, at odds with the Palestinians, hold as tightly to the Hebrew lunar calendar tradition as the Palestinians do to their Islamic lunar calendar traditions. In Asia, China follows its own complex and ancient lunar calendar tradition, and watches as the United States and its G-7 alliances, all dominated by the Gregorian calendar, get ready to spar with terrorists and militants who also follow the Islamic lunar calendar. India has the Bomb, Pakistan has the Bomb, China has the Bomb. The United States has the Bomb, the United Kingdom has the Bomb. France has the Bomb. Russia, the Ukraine, and other former Soviet nations have the Bomb. It is commonly assumed that Israel also possesses the Bomb. Does Iraq have the Bomb? Can a terrorist get access to materials to create the Bomb as well? The nuclear clock is ticking again.

The number of weapons and technologies of mass destruction has increased several thousandfold since 1945 when, at the time ofVernadsky's death, there were virtually none. This is not to mention the biological weapons of mass destruction, more ambiguous, more lethal, more hidden-none of which really existed in 1945 either. With the fallout from the Inevitable Event an anarchic planetary free-for-all is taking shape. From the noospheric point of view, the humans have run out of (artificial) time, and are now committing their last egoistic act of desperation to hold what they perceive to be their dominant place in the scheme of things. The fact is, however, that the planet belongs to the biosphere and not to the humans.

The inability of the Gregorian calendar to sustain another 28-year cycle, much less another millennium, means that an anarchy of time and a time of anarchy is loosed upon the planet. At the present rate, what would the world look like in 2029? One does not want to imagine. The anarchy of time is exemplified by the different competing powers that are unconsciously driven and motivated by programs stored in their differing calendar systems. This failure of artificial time to contain itself is truly the apocalypse. The apocalypse could occur only when the time program had become saturated. The two 28-year cycles, 1945-2001, carried forward not only the exponential advance of machine time, but the accrued karmic baggage of two millennia of the invented religion of Christ. Throughout the last millennium, the protagonists of this religion waged a type of holy war against an embattled world-a war waged by missionaries and conquistadors alike, down to this very day. The week before the Inevitable Event, the Taliban was deporting Christian missionaries from Mghanistan, while other Christian missionaries scour the jungles looking for one more indigenous soul to convert. This activity is inseparable from the Gregorian calendar that programs it.

Entropic Black Hole of Consciousness

A calendar is a mental instrument for holding the programmed patterns of thought and behavior of a given culture, people, or civilization. A people can rise no higher than the program of time their culture imposes on them as second nature. A program of time determines nature of consciousness. Different timing programs scheduled by synchronically inaccurate devices within a biospheric whole governed by a universal timing frequency apart from the deviant human standards can only result in an entropic black hole of consciousness: the clash of civilizations and cultures that precedes the mentally cleansing force of the noosphere and the inevitable return to natural time and the universal 13:20 timing frequency.



Now the default of the Christian program of the Gregorian calendar and its system of social organization, global civilization, is erupting in an entropic black hole of time. The result of this black hole of time is an entropic harmonic convergence, where all of the conflicting points of the differing timing programs that the Gregorian calendar attempted to synchronize, come into a common point of hostile impact. Seen in this light, the Final War is really the final battle in a long saga that we can properly call the Time Wars.

THE AGE OF THE TIME WARS

The Time Wars began with the application of the error in time at Uruk: the 24-hour, 60-minute, 60-second timing frequency derived from a 12-part division of the circle, a two-dimensional plane in space. Since this measure does not correspond to the reality of time as the universal (13 :20) frequency of synchronization, it creates a mental dissynchronization that manifests as the battle of the mind against itself, and against nature. The dynam'ic of the "progress" of civilization is really the dynamic of dissynchronization inherited by the human mind. The gradual encroachment of civilization into all aspects of human society and the biosphere increases the incidence of dissynchronization. The resulting aphasic mental states lead to belligerence and various attitudes of dominance over others and nature-but never to any satisfaction.

Viewed by the Law of Time, civilization is the institutionalization and embodiment of the dissynchronous artificial timing frequency. The dynamic of dissynchronization results in increasingly artificial technological means and reliance on the artificial medium of money to replace the biological or organic functions of our nature and of the biosphere in general. Not only does this process tend toward an "improvement" in the accuracy of the means of war, but also in the capacity of the latter for greater mass destruction. Set apart from the natural cycles by the dissynchronous frequency of mechanization, the Time Wars are also waged against the biosphere, which is viewed as a hostile force to be overwhelmed and plundered. Everywhere on Earth, nature is on the run. Everywhere on Earth, the human looks at his watch-what will he do next? Catch another plane? Fire another bullet? Press another button and let loose another bomb?

The 56-year cycle of the technosphere witnessed the greatest creation and stockpiling of lethal weapons, more than in all the previous history put together, enough to destroy the Earth many times over. The 56-year cycle of the techno sphere also witnessed the greatest plundering thus far of the biosphere, more than in all the previous cycles of history put together. Continued at the current rate, the biospheric plunder would bring extinction to virtually all life within another generation. These two facets of self-destruction-technospheric and biospheric-point again to the Inevitable Event. It is the Pentagon that has led in military spending and strategizing, just as it was the activity within the World Trade Center Twin Towers that dominated and coordinated from afar the plunder of the biosphere-both precedents for the consequent construction and expansion of the technosphere.

But now time has run out on the technosphere. The world has gone flat and valueless with no future vision beyond war. All the money in the world will not put it back together, nor will all the bombs in the world salvage it against its enemies. Who are the enemies of the technosphere, and what would cause thereto be enemies against the technosphere? And who or what is there that speaks for the biosphere? For if the biosphere is to become the noosphere, it must come about from an understanding of the intelligence of harmony. Clearly, such understanding of harmonic intelligence has not been nor will it be forthcoming from the technosphere-or from the Gregorian calendar that programs it. Only the Law of Time can supply the harmony necessary to complete this great movement from biogeochemical combustion to noospheric mind. The Law of Time replaces all that is artificial, while confirming all that is true, whether in human history or the universe.

Let us return to the analysis of the Time Wars and the clash of timing programs. The Twin Towers were the absolute triumph of the artificial 12:60 timing frequency, whose program is embedded in the Gregorian calendar and paced by the mechanical clock. Who steered the hijacked planes into their Gregorian targets? Nineteen militant Muslims, we are told. Why nineteen? And what are the religious backgrounds of the twenty-two most-wanted terrorists in the world? They are twenty-two Muslims. Why that number, and why are all the terrorists Muslims? In the noospheric analysis, the Inevitable Event was the suicide of the technosphere unable to sustain two clashing time programs. It was a program of the strict Islamic twelve-month lunar calendar that drove its belief system into the Twin Towers and the Pentagon, the two supreme monuments of the program of the twelve unevenly measured months of the Gregorian pseudosolar calendar. Is it Islam that is the enemy of the technosphere? Is it Islam that is the champion of the biosphere? Indeed what is Islam? Why is Islam the most resistant force against globalization and the technosphere? We know where the Vatican, the bastion of Christendom, is and who ordained the Gregorian calendar, but what do we know about Islam?

If we strip history away from the force known as Islam (1.3 billion Muslims in the world), and reduce it to its most essential point, then Islam is the teaching of the Holy Quran. What is the Holy Quran? It is the last whole revealed text for all humanity, received and recorded over a 23-year period by a single human being, Muhammad the prophet (570-632). While militant Muslims and terrorists have dominated the mass media image ofIslam for the past few decades, what is the Quran and what does it actually teach? It is also a function of the Gregorian program that scarcely anyone in the West really knows or is familiar with the Quran, since the West has been at odds with Islam since the time of Muhammad. As the supreme text of monotheism, the Quran is actually a psychoactive book that upholds Islam as the final religion for humanity. "He is the one who sent His messenger with the guidance and the religion of truth, to make it prevail over all other religions. God suffices as a witness." (Quran, 48:28) *Islam* means "peace, which is submission to the will of God."

Islam is also the law of nature. Within the vast system of intricate, mathematically based logic that constitutes the Quran-which is a profoundly ahistorical text as well-one feature stands out: the description and definition of nature and the natural order as the chief proof of God's design and guiding wisdom. From the Quranic point of view, the biosphere, inclusive of the creation of the human, is the overwhelming single proof of God's wisdom in establishing a life-support system for our indwelling consciousness to evolve our bodies on this Earth. The biosphere is Islam, or "peace, which is submission to the will of God," understood as the divine law of nature.

> In the creation of the heavens and the earth, the alternation of night and day, the ships that roam the ocean for the benefit of the people, the water that God sends down from the sky to revive dead land and to spread in it all kinds of creatures, the manipulation of the winds, and the clouds that are placed between the sky and the earth, there are sufficient proofs for people who understand. (2:164)
>
> He created you from one person, then created from him a mate. He sent down to you eight kinds of livestock. He creates you in your mother's bellies, creation after creation, in trimesters of darkness. Such is God your Lord. To Him belongs all sovereignty. There is no other god beside Him. How could you deviate? (39:6)
>
> Among His proofs is that you see the land still, then as soon as we shower it with water, it vibrates with life. Surely the One who revived it can revive the dead. He is Omnipotent. (41:39)
>
> He created the human from a tiny drop, then he turns into an ardent opponent. And he created the livestock for you, to provide you with warmth and many other benefits as well as food. They also provide you with luxury during your leisure, and when you travel. And they carry your loads to lands that you could not reach without a great hardship. Surely your Lord is Compassionate, most Merciful. (16:4-7)
>
> He sends down from the sky water for your drink and to grow trees for your benefit. With it, He grows for you crops, olives, date palms, grapes, and all kinds of fruits. This is sufficient proof for people who think. (16: 10-11)
>
> And He committed the sea to serve you; you eat from it tender meat, and extract jewelry which you wear. And you see the ships roaming it for your commercial benefits, as you seek His bounties, that you may be appreciative. And He placed stabiliz-

> ers (mountains) on earth lest it tumbles with you, as well as rivers and roads that you may be guided. And landmarks, as well as the stars to be used in navigation. Is One who creates like one who does not create? Would you now take heed? (16:14-17)

> As for the Earth, we constructed it, and placed on it stabilizers (mountains) and we grew on it a perfect balance of everything. We made it habitable for you, and for creatures you do not provide for. There is nothing that we do not own infinite amounts thereof. But we send it down in precise measure. And we send the winds as pollinators, and cause water to come down from the sky for you to drink. Otherwise you could not keep it palatable. (15:19-22)2

Viewed from its own context, the Quran is the criterion for evaluating the spiritual progress of human existence on this Earth inclusive of man's ability to read the proofs of nature as manifestations of God's wisdom and to comport himself within this nature, the biospheric life-support system, in a manner consistent with the truth. From the Quranic perspective, human freedom of choice is at the root of the biospheric destruction. Choosing anything but to be submissive to God, the human is in rebellion against nature-both his own and that of the biosphere. "We have offered the responsibility [freedom of choice] to the heavens, and the earth, and the mountains, but they refused to bear it, and were afraid of it. But the human being accepted it; he was transgressing, ignorant." (33:72)

The result of this ignorance on behalf of his own aims and intentions rather than that of a respect for the divine plan (biosphere) of the Creator, accounts for the human situation today, at odds with and surrounded by an increasingly out-of-control biospheric degradation and corruption of natural time: "Disasters have spread throughout the land and sea, because of what the people have committed. He [God] thus lets them taste the consequences of some of their works, that they may return [to the right works]." (30:41) Thus, the current techno spheric destruction actually points toward a return of humans to the path of right works.

The forces that created the phenomenon of historical Islam are the enclosing of the Holy Quran within the rigid system of a twelve-month, non-circulating lunar calendar, compounded and supported by the development of the *hadith* and *sunna* (non-Quranic) traditions. A profoundly conservative social order, Islam is nonetheless activated and motivated by a holy scripture that enunciates an attitude toward nature that is the direct opposite of the 12:60 system that produced the technosphere. In this regard, the precepts of the Holy Quran-as of many another holy scripture-make it the "enemy" of the technosphere. From the noospheric perspective, historically and culturally, however, the assault on the nerve centers of the techno sphere could only have been effected by humans whose belief system was rooted in the Holy Quran, which had been at odds with the Gregorian civilization for centuries. In this way, the Quran was the noosphere's weapon used to bring about the circumstances that would lead to the resurrection of the biosphere-the noosphere itself. But only if man consciously chooses the right return path: synchronized harmony in time. The problem is not so much the rigid lunar calendar ofIslam, but the irregular global standard of the Gregorian calendar, which, instead of standardizing all measures and perceptions of time, fosters a human social disharmony and an incessant antagonism against nature-and against Islam.

So then, how are we to return to the right works? Read and study the Quran, yes-but also make a fundamental change in the world. The solution of the Law of Time is: Get a new calendar! Humanity must take a long, hard look at its own timing systems and scrap what needs to be scrapped, no matter what kind of temporary inconveniences this may cause. Calendar reform is an issue that upsets many apple carts. Yet it is the only method that has not been commonly tried and the only step that has not yet been collectively taken. It is a characteristic of the dominant mindset that it writes history in the way that suits its own needs and supports its philosophy. In any of the reviews of the century carried by the mass media during the past year, you will find no mention of the World Calendar Reform Movement; nor will you find, for instance, any mention of the Roerich Peace Pact (1935); nor of the Harmonic Convergence-all buried by the marketing of history to suit the needs of globalization. What do these three phenomena have in common? A concern for peace based on an understanding that without harmony, the human cultural situation will only worsen. If humankind suffers from an excess of disharmony, in the noospheric analysis the only solution is a harmonic standard of time to synchronize all humanity simultaneously-the Law of Time refers to this as the Thirteen *Moon!* 28-Day frequency shift.

CHANGE YOUR CALENDAR, CHANGE YOUR MIND

> *"Since the advent of the Nuclear Age, everything has changed but the way people think, thus, we drift towards unparalleled catastrophe."*
>
> -ALBERT EINSTEIN[3]

To change how people think you must take a profoundly simple and universal element of everyday life, one in which all everyday thinking is rooted, and change it so radically that the way in which people think will itself be dramatically changed. If you want to know that something has really changed, change the calendar! This is the meaning of the replacement of the Gregorian calendar by the Thirteen Moon calendar. The calendar change is necessary because, as the pragmatic application of the discovery of the Law of Time, it brings into focus the essence of this discovery: Time is a frequency, the frequency of synchronization. If a calendar does not increase synchronization, it is not performing its highest function. This is the fundamental critique of the Gregorian calendar-and of all concepts of time based solely on physical, third-dimensional astronomical measurements. This discovery is so new and startling that it affects all human thought and is a matter to which all belief systems, religions, and methods of science must be cognizant. Yet nothing, it seems, is more difficult for humanity than to make this change from a manifest disharmony to a manifest harmony.

Historical man recoils at the prospect of actual harmony-harmony in natural time. This is because historical man defines his existence and thrives upon the disharmonies of his own invented time. The Gregorian calendar keeps the human mind entrained in a diabolical disorder of meaninglessly named months of uneven measure, while every day is tracked and driven by a relentless mechanism called a clock. This immersion of the mind of historical man in the frequency of his own artificial time, more than any other factor, condemns him to a world of inescapable horrors: traffic jams, poverty, terrorism, unresolvable historical and territorial disputes, global warming, environmental degradation, social disorder, insanity, and drug abuse. The problem of historical *human-Homo historicus-is* compounded by the unconscious nature of his acceptance of this timing sensibility, believing it to be the actual nature of time. Hence, all his public and economic policies are driven by and determined by the relentlessness of this perception that time is an arrow blindly pulling him into a future in which his only defense is the creation of more technology, the technosphere itself being a pure expression of the application of the mechanization of time.

THE SECRET HISTORY OF CALENDAR REFORM

When you went to bed on October 5,1582 you woke up on October 16. In this way Pope Gregory XIII promulgated his reform of the Julian calendar, from which the Gregorian calendar differs not one whit, except for the precise working out of the formula for leap year. When this "reform" occurred, the time sensibility of historical man was already crippled and disabled. The Gregorian calendar, by its moment of historicity, bound that crippled time disorder into its final institutional form, assuring that not only European man, but eventually all cultures and races dominated by European thought and conventions would assume and accept this deformed and deforming standard of time.

The mechanical clock, though evolved over many centuries, was perfected just after the Gregorian Calendar Reform of 1582 and promoted by Europeans as an example of the human triumph over nature. So it was that the human mind assumed as second nature its own invented time, encoded as a frequency that we have identified as the 12:60, an unconscious mental ratio determined by the irregular twelve-month calendar and artificial sixty-minute hour. The combination of these two factors in this one timing frequency have consigned historical man to a hopelessly debilitating mental disorder that is referred to as modern civilization, or nowadays, postmodern. But postmodern is not yet post-historical. Postmodernism is just the final convulsion of the time disorder that afflicts the human race as a virulent mental disease and encapsulates man in the technospheric cocoon of his own making. The only cure for such a profound and pervasive disorder is absolute harmony, the very harmony from which historical man so recoils.

In this light, it is well to know that through the first half of the twentieth century a vigorous and well-organized calendar reform movement flourished. Such was the character of this movement to reform the Gregorian calendar that in 1923 the League of Nations called for proposals for reform. More than 500 proposals were received; by 1931, these were narrowed to three:

> The International Calendar Organization, represented by Mr. Broughton Richmond, promoted a perpetual calendar based on the principle of five-five 73-day cycles = 365 days-and the year divided into twelve months of five 6-day weeks each plus a 5-day cycle [The Thirteen Moon calendar also includes the program of seventy-three 5-day periods-overtone chromatics-integrated with the fifty-two 7-day weeks: 52 x 7(+1) = 5 x 73.]
>
> The International Fixed Calendar League, represented by Mr. Moses Cotsworth, also supported by Eastman Kodak and the International Chamber of Commerce, promoted a perpetual Thirteen Month/28-day calendar, which was first presented by Auguste Comte (1842-1849), inclusive of the "day out of time." Though it was not backed by a more thorough mathematical science, which has now been supplied by the discovery of the Law of Time, this was by far the favored calendar, as it is the one that possesses a perfect structural harmony and obvious regularity of all its parts.

3. The World Calendar Association, represented by Elizabeth Acheles, promoted the World Calendar, a modified but perpetual version of the twelve-month Gregorian calendar, which also included the principle of a "day out of time" ("null day"). This group turned out to be the longest-lived and the most vocal, and was responsible for the publication of *The Journal Of Calendar Reform (1931-32).4*

It is instructive to read some of the early texts on the topic of calendar reform to see how the same issue of harmony and order brought up by the Law of Time was at the root of the call for the establishment of a perpetual, harmonic calendar. The base argument, as presented in Alexander Philip's *The Reform of the Calendar* (1914), is stated as follows:

> Suppose, for example, that by some strange convention the meaning of the figures we employ in numerical notation were to change every year; suppose the figure which this year represents 2 were next year to mean 3, next year 4, and so on; suppose again that our weights and measures were to fluctuate in a similar manner. . . then we affirm, without fear of contradiction, that the whole fabric of science and the mechanical arts could never have been raised at all. . . we should in such circumstances have been compelled to rest content today with the very simplest and most primitive appliances. Yet, strange as it may sound, such are the conditions under which, in modem society, human action is organized. For what is the framework. . . by which we arrange our actions? It is no other than the scheme under which we arrange our time-in one word, our calendar. . . [thus] the disorganized state of all social arrangements is ascribable to the calendar. . . The dislocation of our calendrical arrangements is due to two distinct causes. . . the incongruity of the week; [and] the irregularity of the lengths of the months. . .5

The argument made is a profound one, and was the motivating basis of the calendar reform movement in general, no matter which calendar was being promoted. It is fair to ask: Why do we expect a rigorous standard of uniformity in our measurements of space (size, weight, volume, etc.), but spurn or ignore the same requirement of uniformity in our measurement of time, especially the time that governs our everyday social arrangements and consciousness? How can we think that this would not have a profound underlying effect on the very nature and conduct of our society?

Most interestingly, as a movement calendar reform arose strongly during the proto-technosphere, between the two World Wars, only to be swept away by the clouds of war and the contradictory factions of disharmony in which modern civilization was already immersed. Any effort at altering or changing the direction and motion of modern civilization is treated as a threat or derided as ineffectual activity that is scientifically unprovable or that will cost humanity too many dollars to make the change. Such was the fate of the first great calendar reform movement that arose with such fervor in the late nineteenth century only to find its ignominious end when the final debate on calendar reform was adjourned indefinitely by the United Nations Social and Economics Committee in 1956. No one reads about the calendar reform movement in the history books. Because debate on the matter was effectively adjourned, it is assumed that calendar reform is a dead issue of no relevance to the development of postatomic, technospheric man. On the contrary, seen in the dim light of the still-smoking ruin of the Twin Towers, the calendar reform arguments concerning humanity's irrational behavior and its relation to the "immorality" of a skewed timing measure, the calendar, as well as to an inhuman timing device, the clock, were never more relevant.

Not the least import of calendar reform is the opportunity to create a new basis for unifying humanity. As was stated in the "Resolution Adopted by the Fourth General Conference on Communications and Transit of the League of Nations," which took up the issue of calendar reform: "A great number of delegations expressed the opinion that any reform of the calendar could only be put into practice if it came into force simultaneously throughout the world, or at least in a very great majority of States, and it was for this reason that the study of this question had been placed under the auspices of the League of Nations."6

The tragedy of the human inability to agree on a matter so obvious to logic and reason is a testament to the already crippling effects of having operated so long under parochial, sectarian, and often disharmonic timing standards. While the International Chamber of Commerce, the League of Nations, and various international scientific bodies supported the first effort at reform in 1914-1956, the second movement, 1989-present, arose as a purely populist effort, but with an entirely different information base. Recognizing instinctively that the calendar reform issue is more than merely a matter of mathematical order in relation to natural cycles, it is a profoundly theological issue as well, the second reform movement also developed from a non-Western inspiration: the Mayan calendar.

While the psychology of the dominator civilization all but blurs out any other considerations of calendar besides the prevailing Gregorian one, an objective study of the matter demonstrates that the latter is a primitive instrument that eschews both natural cyclic order and any mathematical harmony. In place of the anachronistic standard of the Gregorian calendar, the second calendar reform movement raised a new criterion, the Law of Time, a whole system principle that integrates the mathematical and the moral, the theological and the psychological, and the economic and scientific issues that are embedded **in** the entire topic of calendar reform. Precisely for the reasons of historical man's unconscious habituation to his own disharmonies and the accelerating and cumulative effect of this ignorance on the disorder of his own social life as well as the natural world around him, the second calendar reform movement has developed with a much greater moral and prophetic urgency.



Western Edge:
Tonal sum, set 1 = **7**
Tonal sum, set 2 = **14**

Northern Edge:
Tonal sum = **2**

Eastern Edge:
Tonal sum, set 1 = **28**
Tonal sum, set 2 = **13**

Southern Edge:
Tonal sum = **14**

Total tonal sum = **78** (6x13)

Sarcophagus Lid of the Tomb of Pacal Votan
Showing Disposition of Thirteen Clear Signs

The tonal sums (dot-bar code) of the thirteen signs are key to affirming the prophecy of the Thirteen Moon calendar. Note that the sums of the two sets on the eastern edge equal 28 and 13, while opposite the 13 set is the perfect 7. The tonal sums of the other two sets on the western and southern edge both equal 14, for a sum of 28. The northern edge has a single sign whose tonal sum is 2 twice 7 = 14, and twice 14 = 28; twice 13 = 26 fractal of 260 and code to the Gregorian date 7/26; while twice 28 = 56, the number of years from Hiroshima to the Inevitable Event.

"Consciously using the tool of the Thirteen Moon calendar to replace the erroneous measure of the artificial twelve-month calendar is, in itself, an unprecedented act of human self-reflective consciousness. Collective adaptation to the Thirteen Moon calendar is an intrinsic heightening of consciousness which rapidly awakens the telepathic programming inherent in human biology, frustrated for so long for not having been allowed development in the correct timing frequency."7

It was in 1987 that *The Mayan Factor: Path Beyond Technology* first brought to major public and international attention the possibility that a superior timing sensibility was developed by a thoroughly non-Western culture, the Maya. This book was published with scarcely any knowledge of the calendar reform movement that had gone into a debilitating coma in 1956. Yet, by pursuing the mathematical base of the Mayan calendar, the essence of the Mayan achievement, the Law of Time was extracted, a discovery that brought on the second calendar reform movement, the World Thirteen Moon Calendar Change Peace Movement. Prompted by a prophetic revelation concerning the Thirteen Moon!28-Day calendar decoded from the tomb of Pacal Votan, the premise of the second calendar reform movement was tested worldwide from 1993 to 2000, a time defined as the "seven years of prophecy." By the year 2001, the official beginning of the third Christian millennium, a loose, far-flung calendar reform movement, pioneering in the development of a new science of time and consciousness was promoting the Thirteen Moon!28-Day calendar worldwide.

A REVOLUTION IN TIME

> *"Fire in the lake, the image of revolution. Thus, the superior person sets the calendar in order and makes the seasons clear"*
>
> -*I CHING,* HEXAGRAM49, "REVOLUTION"8

By common consent, a calendar is a system for reckoning time. Virtually all current time-reckoning systems take account only of chronological or, better put, astronomical time-the movement of the Earth in relation to celestial bodies, the sun, moon, planets, stars, and constellations. This is a purely third-dimensional, physical consideration of time. The Law of Time affirms a higher order of time-the synchronic order. This is the time of the fourth dimension, which includes the chronological but enfolds it in a higher mental and mathematical order of reality. According to the Law of Time, what you don't know about the calendar you are using could kill you. By operating according to purely third-dimensional chrono-astronomical timing standards and without knowledge of the synchronic order of fourth-dimensional time, humanity subjects itself to a one-sided view of reality that is hazardous to the planet and jeopardizes the future existence of the human species as well as all life on Earth.

To correct this situation a radical solution is required-a new calendar embedded in the synchronic order revealed by the discovery of the Law of Time. This is the significance of the Thirteen Moon/28-Day calendar-it epitomizes the incorporation of the chrono-astronomical order of time into the synchronic order, and hence provides the vehicle for humanity to escape its otherwise certain plunge into disaster within the next decade. When a dogma is encountered while one is engaged in the pursuit of truth, it must be challenged and abolished. Such a dogma is the calendar in use as the world standard, the Gregorian calendar. That this calendar, originally a system of thought peculiar to one people or religion, should dominate all the peoples and even life of the planet makes it subject to the critique of planetary anthropology.

The discovery that time is a frequency mathematically expressed as the ratio 13:20 requires a profound reorganization of all thought about time and the consequent reorganization of human society as a planetary organism. As the unified field theory of time, the Law of Time calls for the human synchronization in time predicated on the establishment of the Thirteen Moon calendar as the global civil standard replacing the current erroneous timing standard, the Gregorian calendar. This is a matter of the utmost seriousness, since it is also recognized that all belief systems are the function of programs locked up or embedded in the calendars or time-reckoning systems used by a people. The fate of the species and the biosphere may well depend on whether or not humanity is able to understand this point.

What is it about the calendars in use that condemns their users to endless conflict and inability to unify as a species? What is at the root of their disharmony? It is the pursuit of astronomical time. All people today are bound by calendars based on a pursuit of accuracy of astronomical time-the length of the year being the object of this pursuit. Astronomical time is a losing game of an ever-changing and elusive order that results in an entropic reductionism that has little to do with consciousness or synchronization. The year's length (measure of the orbit of the Earth around the sun) calculated by Pope Gregory XIII at 365 days, 5 hours, 48 minutes, and 20 seconds, slows at the rate of *112* second per century, while the length of time in the Gregorian calendar is off from the "true" solar year by 25.9678 seconds per year! Obsessed with rectifying this discrepancy, in 1972 reductionist science came up with Atomic Time to replace Earth Time, and the atomic cesium clock replaced the measure of the year as 365.241299 days with 290,091,200,500,000,000 oscillations of Cs per year!

But what does this staggeringly astronomical figure mean, and of what value is it?

In profound contrast to this obsessive reductionism in which there is no place for spirit, mind, or consciousness, fourth-dimensional radial mathematics represents a mental order greater than and encompassing the astronomical order of the third-dimensional universe. According to the Law of Time, in time reckoning, consideration should be given to systems of the harmonic order of synchronic time that proceed from the radial mathematical order of the higher mind. The higher mind represents the evolved state of mind-the noosphere-that evolution on Earth tends toward, but that has not yet been attained. As long as the human concept of time is governed by the obsessive pursuit of the impossible to attain perfection of astronomical time, this pursuit and the civilization that it propels are doomed to failure. What is known as history is embedded in this pursuit of "fixing" astronomical time, which has culminated in the dogma of the Gregorian calendar and the microatomic measure of the cesium clock. When did this pursuit begin, why did it come to dominate the human species, and to what effect?

As we have seen, the values, customs, and norms of a nation, culture, or civilization are embedded in the calendar it uses. The Gregorian calendar, the current global civil standard-indeed, the foundation in time of globalization-is the calendar of the Caesars, of the Roman Empire, of the Catholic Church and the Vatican. To change this calendar is to change history itself. Can it be done? The League ofNations attempted this in the 1930s but failed. The United Nations tabled this effort in 1956. Since the United Nations adjourned the matter of calendar reform indefinitely, in 45 years the Earth's population has more than doubled, that is, it has increased by more than 3.2 billion people, a factor that is still out of control, and that may have much to do with the fact that humanity is actually in a fog about time.

The reasons for wanting to replace the Gregorian calendar are no less valid today. The Gregorian calendar is not a standard of measure. It lacks logic and reason. It numbs and befuddles the mind when trying to make calculations by it. It is shrouded in an arcane and medieval obscurantism. The net effect of the use of this calendar is to perpetuate a fundamental level of mental confusion and ignorance concerning the actual nature of time itself-an ignorance that is hardened into dogma by the unwillingness of habit to consider any other possibility, but rather to accept the entire system as second nature. The argument that it encodes the most accurate and scientific measure of the solar orbit of the Earth is irrelevant in relation to the effect of its irregular measure on the mind and its numbing power as the dogma of a conquering people. Indeed, the solar measure of365.241299 days per year has nothing intrinsically to do with "30 days hath September. . . ," and vice versa. In fact, the measure of the Earth's orbit is one matter; the purpose of calendars and time reckoning as factors of synchronization is a wholly other matter. But then, since the very nature of a culture or a civilization is determined by the calendar it keeps, the use of a deformed standard can only inhibit and skew even the questions one asks about time.

The failure of calendar reform by 1961, the year of the Vatican II Council, only promoted an increasingly complacent acceptance, however cleverly disguised, of a millennial dogma, the Gregorian calendar. In the conclusion to the "last word" on the subject, *Calendar: Humanity's Epic Struggle to Determine a True and Accurate Year,* David Duncan summarizes, "We take in stride a calendar [the Gregorian] that is flawed but endures, largely because it works just fine for most of us, and it is what we are used to."9 It is not at all objective to accept something because we are used to it. This attitude is anything but scientific. Rather, it is the smug basis of nothing more than a self-fulfilling dogma-and yet the civilization that bases itself on this aberrant timing measure prides itself as being the most scientific in all history!

THE CONFUSION OF IRREGULAR TIME

Due to this flawed time sensibility, it may be concluded that humankind today is little capable of moral reason or logic, which itself is a result of, or at least strongly reinforced by, habituation to a timing standard that is irrational and illogical. Anytime we overlook or dismiss a fault due to habit, or simply because we are accustomed to the use, say, of an instrument, even if that instrument is demonstrated to be flawed and irregular, is evidence of a moral laziness that will eventually contaminate the entire consciousness that accepts and accommodates itself to the flaw. The exercise of truth is a moral prerogative. The fact of the matter is that the Gregorian calendar is a hodgepodge of flaws and accretions, rationalized into a systematic formulization that has no basis in reality. The celebration of Easter is a case in point.

Easter is the celebration of the day Christ was resurrected from the dead. It may be logically assumed that this occurred on one and only one particular day, just as the celebration of his birth occurs on Christmas Day (although, similarly, no one really knows that this was the actual date of his birth). By the time the Christian religion had become an established force within the Roman Empire, however, no one knew precisely on what day the Resurrection had taken place. The Council of Nicea, convened by Constantine in A.D. 325, called for a debate on the matter in which various theories were presented. The debate was concluded with the victory of one conjectural system over the other. The winning system stated that Easter would be celebrated on the first Sunday after the first full moon after the spring equinox, except when the full moon was on a Sunday, in which case it would be celebrated on the following Sunday, and this was so that it would not be celebrated on the same day as Jewish Passover.

Over the centuries this conjectural theory regarding the date of Christ's resurrection was buttressed with a system of elaborate calculations for predicting when Easter would occur. These calculations were all made with regard to establishing an alignment of the synodic lunar cycle of 29.5306 days (which resulted in a lunar year of 354.3672 days) and the solar year of 365.241299 days! Being fortified with such elaborate mathematical calculations did not lessen the fact that the system was originally-and still is-a mere speculation of a highly clever but relative nature. Thoroughly embedded in the Julian-Gregorian calendar, the system of determining Easter is inseparable from the Gregorian calendar itself, and is one of the chief reasons for the resistance to its reform-as witnessed by a reading of the calendar reform arguments of the 1930s. The entire system of this calendar, inherited without question from the Caesars of the Roman empire, is actually nothing more than a form of self-perpetuation of a priestly hierarchy that includes in its support a host of bankers, industrialists, and scientists and the elaborate social system that is under their control-the technosphere of global civilization itself. Take away the calendar and the entire structure loses its foundation.

"If the Julian/Gregorian calendar was to be offered as a new device for measuring time, we, with our present knowledge and state of living, would reject it as something utterly impracticable, lacking in harmony and order, unbalanced and irregular, too clumsy a calendar to make calculations by, while the various sections are not comparable."10

A science or any scientist that unquestioningly follows the Gregorian calendar is, in reality, not worthy of the name. What is science? A concern for logic and precision of measure, we might answer, as well as standards of measure that utilize uniform units of measure in accord with what is being measured. Yes, the year is calculated as being 365.241299 days in length, but if the annual standard of measure that is used is irregular and unscientific, then it avails nothing, and indeed deforms the mind leading it down byways that may only end in self-destruction. Thus the pursuit of a true and accurate year in itself may be an illusory pursuit, blinding us to the actual nature of time, and leading us away from a genuine understanding of ourselves and our role and purpose on this Earth.

To change and replace the calendar with the thirteen moon standard is to return us to our original purpose, leading us back to pathways of harmony and natural health. According to the Law of Time, the damage already inflicted in the time humanity last hesitated and lost the chance to alter its timing frequency, forty years ago, has been incalculable. The final opportunity to change the calendar and the timing frequency is now upon us. Because of this we must be very clear and unshakable in our understanding and determination to expose and eliminate the current civil calendar for once and for all. Even apologist David Duncan's unabashedly pro-Gregorian book *Calendar* (1999) concludes with its time line on the date 2012, "Current Mayan Great Cycle will end."ll But will we also end? By 2012, it will be too late to change. We must begin to change now.

In reviewing the quirks and twists of history that constitute the Gregorian calendar, we must ask: Why do we continue to use such an instrument, and what are its effects? Is a calendar something more than a tool for scheduling the payment of debts *(calends),* or is it an instrument of synchronization? The harmony or disharmony of time is a profound matter rooted in the instrument of time reckoning that we use. There can be little question that we live more in a time of chaos than of harmony. We may also say in regard to the effect of standards of measure on the mind, that the chaos of the time is embedded in the calendar we use. If we are to leave this time of chaos and enter a time of harmony, then we must exchange the instrument in which the chaos is embedded for an instrument that is the very model of harmony-the Thirteen Moon/2 8-Day count. This is the choice humankind must now make.

The issue of the nature of time, or of the times in which we are living, cannot be separated from the issue of the calendar. The very nature of the calendar that the world follows has stunted the mind and warped the body's innate timing sensibility, reducing the understanding of time to being merely a matter of chronology. "Chronology is a register or reckoning of successive years, a time scale. It may also be described as a system of registering time massively."12 Virtually all time reckoning has proceeded from astronomical indicators, the major exception being the Maya, who actuated from a solely mathematical outlook. Yet with this mathematical outlook the Maya devised a chronological method that has never been surpassed, a fact attested to by many, including the architects of the Kitt Peak Observatory in Tucson, Arizona, where a mosaic mural depicting the civilization of the Maya asserts the superiority of their calendar over that of the Europeans.

It is significant that the earlier calendar reform movement, while occasionally acknowledging the brilliance of the Maya, made no use of the Mayan knowledge. But this was because the time sensibility was restricted to thinking of time solely in terms of chronology, or at best as a schedule for keeping good accounts, with little comprehension at all of the synchronic nature or order of time. And since the system of chronology was synonymous with the system of control embedded in the Gregorian calendar system, the earlier reform movement failed altogether to make any impact on the Vatican, much less on the global power structure itself.

All the thought, action, and good intention put into the years of calendar reform notwithstanding, the Gregorian calendar prevailed, and, tragically, not one of the proposals or recommendations was ever even considered for adoption by the papal authorities who maintain control over the calendar. In the 1930s, the propaganda of the Church was aimed at limiting any possibility of reform, for it would not give up the succession of the seven-day week. In any perpetual calendar, such as the Thirteen Moon/28-Day calendar, the observance of the Day Out of Time is necessary for maintaining the harmony of the fifty-two weeks that complete themselves in 364 days. The continuous succession of the week does not stand in a constant relation with the other elements of the calendar and is one of the main causes of confusion in the Gregorian calendar. Arguing that such a break as a Day Out of Time, no day of the week at all, would plunge the world more deeply into chaos, barbarism, and war, the Vatican effectively blocked all effort at reform. The completion of the century of total war, capped by the Inevitable Event, roundly refutes this point. It may just as easily be argued that because we did *not* change the calendar, we are now plunged into the final barbarism and unholy war.

When the Vatican II Council in 1961 affirmed in its backward and highly restrictive language that it was not opposed to reform, so long as such reform did not disrupt the seven-day week and respected the tradition of Easter as a "movable feast," the door to reform slammed shut. By this time all the early reformists had literally died out and the question of calendar reform appeared to have become one of the buried issues of history.

What the priests of the Catholic Church thought they had buried through an auto-da-fe in Izamal, Yucatan, 1562, and overcome through the imposition of the Julian-Gregorian calendar over the conquered Maya, returned with the precision of prophetic timing in 1987. The publication of *The Mayan Factor* not only opened the door to a new look at the Maya, but also to an understanding of time that was anything but chronological. A new dimension of time appeared-radial, fractal time, the synchronic order. And behind the reassessment of the nature of time was the provocative call of Mayan prophecy-the end of the thirteen baktun Long Count, 2012.

The Law of Time defines the human problem as being one of radical and destructive dissynchronization from natural time, resolvable only by a return to natural


Day Out of Time
July 25
1. Magnetic Moon
July 26 - August 22
2. Lunar Moon
August 23 - September 19
3. Electric Moon
September 20 - October 17
4. Self-Existing Moon
October 18 - November 14
5. Overtone Moon
November 15 - December 12
6. Rhythmic Moon
December 13 - January 9
7. Resonant Moon
January 10 - February 6
8. Galactic Moon
February 7 - March 6
9. Solar Moon
March 7 - April 3
10. Planetary Moon
April 4 - May 1
11. Spectral Moon
May 2 - May 29
12. Crystal Moon
May 30 - June 26
13. Cosmic Moon
June 27 - July 24
January - 31 days
February - 28/29 days
(sometimes)
March - 31 days
April - 30 days
May - 31 days
June - 30 days
July - 31 days
August - 31 days
September - 30 days
October - 31 days
November - 30 days
December - 31 days

I am in favor of a standardized calendar for the whole world, just as I am in favor of uniform coinage for all countries, and a supplementary artifical language (like Esperanto, for example) for all peoples.

I have been informed of, and I welcome, the international movement for calendar reform . . . I am always ready to endorse any honest movement which will help to unify the peoples of the world.

—Mahatma Gandhi

Wavespell of the Thirteen Moons in Relation to the Irregular Gregorian Calendar

time through the perfect and perpetual harmony of the Thirteen Moon calendar. With the analysis of the Law of Time, there is an even greater urgency and a more profound certainty. Reform is not only insufficient but also impossible. If the calendar is not changed within the next decade, it will be the end of civilization as we know it. There is a genuine and legitimate need to bring the issue of calendar reform into the public eye once again.

Yes, to change the calendar involves a frequency shift. The collapse of the technosphere will dispose the human mind to rethink its options. It may even reorient the human mind to a consideration of the biosphere as being the greater vehicle in which we, as humans, are being carried. Such a massive change in attitude, a mind shift and a paradigm shift, may arouse in the human breast a spiritual reawakening as well. Harmony is spirituality. By changing the calendar, humanity can know it has turned a page of destiny-an act that may cause it to appreciate what has already been written in a book it had not been inclined to study, the Holy Quran:

> God is the One who raised the heavens without pillars that you can see, then assumed all authority. He committed the sun and the moon, each running in its orbit for a predetermined period. He controls all things, and explains the revelations that you may attain certainty about meeting your Lord. He is the One who constructed the earth and placed on it mountains and rivers. And from the different kinds of fruits, He made them into pairs-males and females. The night overtakes the day. These are solid proofs for people who think. (13:2-3)

In this passage we can find ample evidence of the formal order of the Law of Time and the biosphere-solid proofs. As for the "people who think," do they not then constitute the noosphere?

◆

7

Humans—Noospheric Chips:

Consciousness and Reality Redefined

"And conquered by the sense of the earth and human sense, hatred and internecine st'ruggles will have disappeared in the ever-warmer radiance of Omega. Some S017:of unanimity will reign over the entire mass of the noosphere. The final convergence will take place in peace."

-PIERRE TEILHARD DE CHARDIN,
THE PHENOMENON OF MAN!

Once begun, the exhaustion of the technosphere is irreversible. The exponential growth curves of money, machine production, energy output, and population increase come to a climax. By 2004 the humans will be at another major crossroads: to go wholeheartedly into the harmony of the noosphere, or to suffer the rest of their decline in an ignominious twilight of terrorism, barbarism, and cultural anarchy. By 2004 the humans will have their last opportunity to change their macro-organizing principle. By relinquishing the artificial time held in place by the old calendar and becoming unified in time under a calendar that is a perfect harmony, humans will enact the coming of the noosphere. Only harmony will bring harmony; only harmony will cancel the errors of history, a manifest disharmony. Only an act of harmony can manifest the noosphere. Only this time-changing act, consciously carried forward by a significantly roused number of humans, will create a mental field so positive and constructive as to engender the radical break that leads to an entirely new cycle of existence of the life on Earth: the noosphere. Entrance into the noosphere of harmonic time through the calendar change will be much like going from a black-and-white movie to one in Technicolor. The difference between the new time and the old time is literally like the difference between Heaven and Hell.

September 11, 2001: the Twin Towers collapse, creating a rupture in the technosphere. Everything comes to a halt. The New York Stock Exchange is closed for four days-a virtually unprecedented event. All commercial airline traffic in America is halted for two days. Even the United Nations postpones the opening of its fifty-sixth General Assembly by three weeks. Six weeks after September 11 a new, sinister form of war is engulfing the technosphere. The Americans assert the right to mercilessly bomb Mghanistan in self-defense. The response of war is the final self-destructive impulse of the techno sphere to protect itself, but this will only widen the effects of the suicidal blow it has already sustained. The war will only make definite that it is the last climax of the biogeochemical combustion engendered by the pursuit of an error in time.

The rupture in the technosphere is the break in artificial time, and therefore amounts to the opening of a noospheric fissure-an inrush of cosmic consciousness and a moment of simultaneously heightened natural time. When the towers collapsed, belief systems shattered. Because it was viewed on global television, it was an event witnessed by all humanity and it entered through the optical cortex into the brain, arousing potent images from the subconscious. This is a noospheric act because it is the entire mind of the whole species that receives this single image in one simultaneous moment. In that shattering image, however unconscious, the noosphere immediately entered the field of human consciousness, much as a leak in a boat allows water to come rushing in. From the perspective of the noosphere, the technosphere is a medium of transformation resulting from the pursuit of a distorted perception of time. With the destruction of the Twin Towers, the transformation is complete; following the war, the technosphere can be creatively dismantled.

THE NOOSPHERE: RAINBOW BRAIN OF TIMESHIP EARTH

What is the noosphere? Can we define the noosphere more precisely so that it is a less nebulous term? Can we make the noosphere concrete enough so that it may be understood and accepted as the coming new way of a higher level of everyday normalcy? First of all, let us say that the noosphere has existed as long as life has existed on this Earth. In this sense, the noosphere is the sum of the mental interactions of all life. The mental interactions, or field of mind, exist as a great unconscious medium, inseparable from the Law of Time. That is, if all life and the phenomenal world of the biospheric medium are synchronized by the Law of Time, then the programs of the organization of life, from the periodic tables to the DNA code, will also be synchronized by and embedded in the mathematics of the Law of Time. Being a function of the whole system of the Earth and integral to the functioning of the biosphere as an interplay of cycles in which organic and inorganic interact with a set order of chemical transmutations, the noosphere must also be the mental coordinating field or program of this complex of vital interactions. It must, therefore, be a characteristic of biospheric evolution that the noosphere remains unconscious until a significant moment is reached-the climax of the cycle of biogeochemical combustion, the enactment of the biosphere-noosphere transition.

As the Earth's mental field, it must be an act of collective self-reflection that arouses the noosphere into functioning consciousness. By its definition as the mental envelope of the Earth, the noosphere can come into conscious manifestation only through an act of collective self-reflection, such as the proposed calendar change. Also, as the mental envelope of the Earth that is above and discontinuous with the biosphere, the noosphere-mind sphere--can mean only one thing: the advent of universal telepathy among the humans. The Internet can be seen as a third-dimensional reflection of the noosphere, a form of electronic proto-telepathy. But, ironically, as long as the humans hold on to the Internet, they cannot experience the true evolutionary potential of genuine universal telepathy. The point is that telepathy can only function in a field of reality that is synchronized by the natural 13:20 timing frequency. Time and telepathy are mutually defining factors dependent on unity of thought. The humans have chosen a path of disunity, so that their calendar programs clash and are at odds with each other and with natural time. This maintains the technosphere, destroys the biosphere, and keeps the noosphere in the unconscious. But now, with the Inevitable Event, the break has occurred and the shattering of the Dreamspell of History has begun. The noosphere's rainbow brain leaks back into human consciousness.

The rainbow brain of the noosphere-what is that? As the mental envelope of the Earth, the noosphere possesses a structure ordained by the Law of Time and congruent with the structure of the whole Earth. Within the noosphere are to be found the evolutionary control panel or programs, defined as the *psi bank-the* medium of information storage and retrieval for all the mental programs. The noosphere is the field of planetary consciousness in which humans are intended to participate and complete their evolution. However, operating by artificial time is like looking through a glass darkly. This being so, there is no noosphere to see. Humans generally experience consciousness through the chinks in their sensory prism, conditioned by separatist beliefs, making it most difficult to attain a perception or experience the field of consciousness as coextensive with the Earth. Indeed, if the biosphere is the region on Earth for the transformation of cosmic energies, the noosphere is that region of the Earth for the reflection of cosmic consciousness and its mental programs. Seen through the lens of universal synchronized time, the humans accommodating to a single instrument of time measurement are inherently sharing a single thought form. It is that act of self-reflective convergence that makes the noosphere conscious and draws it toward the resplendent omega point of2012 and beyond.

As with all the other geochemical structures and processes of the Earth that are planetary in nature, the noosphere, the rainbow brain of Earth, actually has a coherence and an order that we may define in a precise way. In so doing we shall redefine the nature of human reality and the human being itself. We must enlarge our lens of perception to encompass the whole Earth as a single being. In relation to this single being of the Earth, the individual human is hardly even a speck. The dimensions and proportions by which we commonly measure reality must also expand to accommodate the vast dimensions of the Earth as a single entity, a planetary geocosm within the solar field, the heliosphere. Since the sun is also a star, the heliosphere is a function and member of the galactic order of being. As the mental "thinking sphere" of this planetary being, Earth, the noosphere is above and discontinuous with the biosphere, the hydrosphere, and the atmosphere. It is contained by and functions within the vast invisible electromagnetic field of the Earth. Though the ionosphere is the lowest level of the electromagnetic field system of the Earth, the main structures of this field are the two radiation belts located 2,000 and 11,000 miles above the Earth. It is within the two radiation belts that the control panels of the noosphere are to be found-the psi bank.

KIN: BIPOLAR BASE MEASURE OF THE 13:20 MATRIX

> *"And He is the One who created the night and*
> *the day, and the sun and the moon; each*
> *floating in its own orbit."*
>
> -QuRAN,21:33

In the simplest aspect of our daily experience of time on Earth we have the full play of the law of alternation-day-night, sun-moon, north-south. Because we know the bipolar nature of the Earth, dividing it into two geomagnetic fields, north polar and south polar, we can then define the complementary bipolar field of time, which divides the cycle of the Earth as it makes one rotation on its axis into one day and night. This entire unit, day and night, is defined as a *kin,* the base unit of synchronic time measurement. From the perspective of the noosphere, day and night are a function of the two alternators-day alternator and night alternator-that operate as the phasic motion of the rainbow brain of the noosphere working in tandem with the electromagnetic field. The two phasic alternators regulate the activation of photons (day) and the regeneration of photons (night) within the entirety of the life process of the biosphere.

THE NOOSPHERIC FOURFOLD/EIGHT-PART STRUCTURE

> *"He created the heavens and the earth truthfully. He rolls the night over the day and the day over the night. He committed the sun and the moon, each running for a finite period. Absolutely he is the Almighty, the Forgiving."*
>
> -QURAN, 39:5

> *"We rendered the night and the day two signs. We made the night dark and the day lighted, that you may seek provisions from your Lord therein. This also establishes for you a timing system, and the means of calculation. We thus explain everything in detail. "*
>
> -17:12

Since the two alternators are also in interplay with the bipolar magnetic fields of the Earth, a four-part process is revealed that is magnetically distributed as an overall eight-part structure. The unit of one kin divides the rotational cycle of the Earth in its orbit into four distinct phases daily and annually. The four daily points are defined by: the dawn, when the part of Earth you are in first experiences the solar photonic activation; the high noon (zenith), when the part of Earth you are in is in closest direct relation to the sun; the twilight, when the photonic activation ceases and the sun disappears from view; and midnight (nadir), the point at which the point of Earth you are on has rotated to its farthest distance from the sun, the height of the cycle of photonic regeneration. This daily process is mimicked in the four points of equinox and solstice, where for either hemisphere the equinoxes are the same as the points of dawn and twilight and the solstices correspond either to high noon or to midnight. Because of the magnetic polarity of the Earth, the four-part process is


Solstice
Summer North, Winter South
Zenith
DAY
Third Watch
Antipode Kin
Stable -
Stable +
Second Watch
Guide Kin
"May the circle be unbroken"
" Know the daily oracle:
Choose your time"
NET
Minute
Destiny Kin
Dynamic +
Dynamic -
Twilight
Equinox
Spring
South,
Autumn
North
"May the center of the circle always be our home."
Dynamic -
Dynamic +
Dawn
Equinox
Spring
North
Autumn
South
End NET Minute
Begin NET Minute
Fourth Watch
Occult Kin
Stable +
Stable -
First Watch
Analog Kin
NIGHT
Nadir
Solstice
Summer South, Winter North
Guide
Antipode
Destiny
Analog
Occult
Daily
Oracle
Model

Four-Part Bipolar Kin:
Four daily watches,
Four annual seasons—
Two points of balance
Two points of return

Net Minute Model


0°
SPRING
90°
SUMMER
180°
AUTUMN
270°
WINTER
360°
60°
A
NORTH
Ω
30°
AC
0°
CA
30°
SOUTH
60°
60°
45°
30°
0°
30°
45°
60°
0°
AUTUMN
90°
WINTER
180°
SPRING
270°
SUMMER
360°

Psi Bank—Four Bipolar Plates Accommodating NET Time Autoregulatory System of the Noosphere
(from *Earth Ascending*, Map 1)

simultaneously experienced in opposite phases, that is, winter in the North is summer in the South-hence the four-phased process yields a bipolar eight-fold structure.

This four-part day-night seasonal process defines the structure of the four psi bank plates, which also coordinate the four-year cycles of the Earth. The psi bank plates, the "nervous system" and control panel of the noosphere, are a complete function of the 13:20 timing frequency and thus participate in the systematic regularity of the fourth-dimensional synchronic order. This means that the psi bank is the registration within the Earth's magnetic field of the 13:20 timing matrix by which all life and the planetary evolutionary process as a whole are regulated. Simulating the four-part process of the Earth rotating on its axis in time, four stages per day, four seasons per year, in four-year cycles-not to mention the four phases of the moon-four psi bank plates accommodating the bipolar field yield eight 260-unit 13:20 frequency information matrices.

That is, each of the four psi bank plates conforms to a mirror symmetry of the bipolarity of the Earth's magnetic field. Each plate is divided by mirror symmetry into a 260-unit Northern and a 260-unit Southern hemispheric half, for a total of two bipolar matrices and 520 units per plate, or 2,080 (520 x 4) units in all. These units are referred to as *psi chrono units* or *time-bearing information units.* The information for the different sequences of the Earth's biogeochemical evolutionary processes is all regulated by these time-bearing information units.

We have to understand that through the medium of universal cosmic time the Earth, the Sun, and every star, constellation, and galaxy is coordinated in this way by the synchronic 13:20 frequency of time. It is the 13:20 frequency that establishes holonomic consistency in time throughout the universe. The Earth's noosphere is a lens of time. All cosmic information is focused through this lens. It is this noospheric lens of time that makes Earth into a geocosmic thought form.

The noospheric lens of time and mind has been operating ceaselessly-but unconsciously-since the beginning of the evolution of the Earth. Since the noosphere is a function of the universal synchronic timing frequency, its conscious activation must also come about through a superior mental coordination with this correct synchronizing timing frequency. The psi bank 13:20 frequency is consciously activated and registered at the human level by the mental engagement of the 13:20 matrix as enacted through the 260-day cycle. The interaction of the 260-day galactic cycle with the 365-day solar biotelepathic cycle defines one noospheric year, or one solar-galactic cycle of fifty-two human years (= fifty-two 365-day solar orbits = seventy-three 260-day galactic cycles). This great noospheric coordination of fifty-two solar orbits with seventy-three galactic cycles is fractally present in a single solar orbit, where fifty-two 7-day weeks = seventy-three 5-day cycles known as chromatics. What is important in coming to understand the noosphere as Earth's geocosmic time lens and rainbow brain, is that we must change our perspective altogether from anthropocentric to noospherocentric, and in this way evolve into *Homo noosphericus.*

THE CYCLES OF NET TIME

For the noosphere, the rainbow brain of planet Earth, time is different-it is slower and longer. From the noosphere's point of view, what we call a year is a solar orbit. What we call a day is a single rotation of the Earth on its axis. The cycles of the moon are the lunar phasings that calibrate the synchronization of the Earth in time. The Earth is not a spaceship. The Earth is a Timeship. As a Timeship, the Earth is a function of the master synchronization frequency that coordinates and moves it in time through ever greater circles of inclusiveness and syntropic integration. Seen through the noospheric lens of time, the technosphere is a highly exaggerated acceleration of the biogeochemical continuum through highly artificial and resource-depleting means-it is but a smoking bubble whose fragile struts and frets are laced together by transport and communication systems that yield a cacophony rather than a harmony. And for this reason, the disharmony of the bubble ultimately explodes upon itself, releasing Earth from the prison of false time into the fresh air of real time and the advance into the geocosmic splendor of the noosphere. Synchronized with the galactic cycles, the noospheric mind of the whole Earth is reckoned far differently from the artificial units of measure that condition the anthropocentric notions of time evolved in the era of *Homo historicus.*

Here is how the fourfold process of Earth in time is reckoned by the noosphere. Please note that in Noospheric Earth Time (NET), time is universal synchronization. At any given moment, it is always the same noospheric moment in time on

Table of Noospheric Earth Time Units

1. One Noospheric Earth minute = 1 day-and-night rotation of Earth on its axis = 1 kin.
2. Twenty-eight Noospheric Earth minutes = 1 Noospheric Earth hour = one moon of 28 kin. where every 7-day week = 1/4Noospheric Earth hour = 7 kin.
3. Thirteen Noospheric Earth hours (moons) = 1 Noospheric Earth day = 365 kin (days) = 1 solar orbit. or 1 human year (= 13 NET hours x 28 minutes + 1 NET minute, "Day Out of Time:')
4. Four Noospheric Earth days = 1 Noospheric Earth week = 4 solar orbits (years) = 1,460 kin (days).
5. Three Noospheric Earth weeks plus 1 Noospheric Earth day = 1 Noospheric Earth season = 13solar orbits or 13human years.
6. Four Noospheric Earth seasons = 1 Noospheric Earth year = 52 solar orbits (52 human years) = 73 260-day galactic cycles = 18,980 kin (days).
7. Five Noospheric Earth years = 1 Noospheric time chord = 260 solar orbits.
8. Twenty Noospheric time chords = Vs Noospheric evolutionary subcycle = 5,200 solar orbits = 1 Noospheric Century of 100 Noospheric Earth years.
9. Five Noospheric evolutionary subcycles = 1 galactic evolutionary day = 26,000 solar orbits = 5 Noospheric Earth centuries or 500 Noospheric Earth years of 52 solar orbits each.

Earth. Whether that moment is experienced on the night or day side of the Earth, that moment is simultaneous and encompasses both sides of the Earth at once. This is true not only because time is the factor of synchronization- T(E) = Art, where art is the result of any synchronization-but also because the velocity of time is infinitely instantaneous. By thinking that the Earth really does conform to the 24 hours of the clock, the humans have retarded their time sensibility, and consequently their artificial processes have become increasingly artless. In considering the Noospheric Time measurements, remember that as a human you are but a cell in the biospheric organism-or, as we shall see, a chip of the noospheric rainbow brain.

As the measure of the mind of the Earth, the Noospheric Earth Time (NET) reckoning units coordinate consciousness as a planetary, or, more accurately, a solar-planetary phenomenon. For instance, if one NET day is a single 365-day solar orbit of the Earth, dawn of the noospheric Earth day is experienced as the spring equinox, but the noosphere is bipolar. So the dawn is also simultaneously the autumn equinox or twilight of the other polar magnetic half of the Earth. To fully engage and grasp such a thought is to expand the limits of consciousness. Like dolphins who never sleep but only rest half of their brain at a time, so it is with the rainbow brain of the noosphere. Such consciousness has nothing to do with the workings of the everyday egoistic human consciousness, which can understand things only according to a limited frame of reference defined by its own limited and highly conditioned ego needs. The geocosmic consciousness of the noosphere can be apprehended only as a single telepathic unity in and by which all members of any given species or organism are organized. To consider that the noosphere itself could become the organizing principle of the human species as a whole is to engage in conscious mental evolution.

Small aboriginal prehistoric bands of humans experience an unconscious level of this geocosmic noospheric mind. Dolphins, other mammals, and all animal species experience this noospheric mind. Even trees and crystals are organized by this noospheric mind of time.

Homo historicus, however, slowly but inexorably cut himself off from the noospheric mind of time by substituting erroneous instruments of measure, or instruments of measure that were incomplete in relation to the noospheric time cycles. The result was the exponential surge in biogeochemical combustion that characterized the final baktun cycle, culminating in the fifty-six-year blister of artificial time, the technosphere. The fact that the time blister popped eleven years before the end of the cycle of *Homo historicus,* 2012, means that *Homo noosphericus* is ready to emerge from the shattered cocoon of false time. Liberated from artificial time and from the technosphere itself, and enrolled in the natural time of telepathy, the human will experience

Noosphere Earth's Rainbow Brain

Magnetic Alternation - Night and Day Law Of The Ring

"The Psi Bank in Perfect Motion"


Mind Realizes Form
Time Concentrates Dominion
Psi Plate III + IV
1040 PCU
Psi Plate I + II
1040 PCU
Night Ring Rises in the East At Sunset Sets in West at Sunrise
Day Ring Rises in East at Sunrise Sets in the West at Sunset
Space Expands Matrix
Radiance Releases Conciousness
NIGHT RING
PRIMAL MATRIX
Night Telepathic
Magnetic Receiver
Transmitter
"Regenerates Dream"
Earth Rotates From West to East Sun Rises in the East Sets in the West
Axis "T" = 20 =
DAY RING
CREATIVE GENESIS
Day Sensory
Magnetic Receiver
Transmitter
"Accomplish Vision"

T(E)=ART

DAY ALTERNATOR
Photonic Activator

Radiation Belt x 2 =
2 Bipolar PSI Plates -
2 Phases

NIGHT ALTERNATOR
Photonic
Regenerator

Radiation Belt x 2 =
2 Bipolar Psi Plates =
2 Phases

2 Phases + Polarity =
4 Bipolar Psi Plates @ 13:20 =
Nervous System + Noospheric Control Panel



Harmonic Module

20 Solar Frequencies

13:20 Matrix Programs Four Phase Bipolar Psi Plates



Synchronic Map and Guide to the **Noosphere**


Year · One
0° SPRING
SEED 90° SUMMER
Year -- Two
MOON 180° AUTUMN
Year --- Three
WIZARD 270° WINTER
Year ---- Four
STORM 360°
60°
NORTH
30°
AC
0°
CA
30°
SOUTH
45°
60°
MEN
SUN
Moon
0° AUTUMN 90° WINTER 180° SPRING 270° SUMMER 360°

Four Psi Bank Plates

13:20. Ratio Constant of Universal Synchronization

Earth Wizard. *"Homo Noosphericus"*

13 Moon 28 Day + 1 Noospheric Regulator = 1 Noospheric Earth Day

Noospheric Earth Time (N.E.T.) Units

1 Day = 1 NET Minute
28 Days = 1 NET Hour = 1 Moon

13 Moon NET Hours = 1 NET Day =
1 Solar Orbit

4 Solar Orbits = 1 NET Week

3 NET Weeks + 1 NET Day =
1 NET Season = 13 Solar Orbits

4 NET Seasons = 52 Solar Orbits =
1 Noospheric Earth Time Year

Bipolar Oscillator and Crystal Transducer Earth Core

Activated by 1 Time Atom per ¼ Hour (7 Days) x 4 = 4 per Hour, 28 Days = 1 Moon-NET-Hour


N+P
Year 4, Storm
Crystal Solstice
Noon Midnight
Year 1, Seed
Electric Equinox
Twilight Dawn
ELECTRO
MAGNETIC
ALTERNATOR
PLATE I
PLATE II
IV
III
AXIS
CRYSTAL CORE
BIOPSYCHIC
PLATE
EQUI
NOX
GRAVITATIONAL
PSI
POLAR
DAY
Dawn Twilight
Solar Equinox
Year 3, Wizard
Midnight Noon
Rhythmic Solstice
Year 2, Moon
S - P

Four Phasic Noospheric Resonator

Timeship Earth Field

- Day Night Alternator - 4 phases
  Twilight Noon Dawn Midnight
- 1 Moon-NET-Hour = 4 weeks ¼ Hours
- Solar Orbit = 4 Seasons = 4 Phases NET Day
  [Electric, Solar Equinoxes; Rhythmic, Crystal Solstices]
- 4 Solar Orbits = 1 NET Week = 1 Seed Storm Year Bundle =
  Return of 4 Psi Plates, 1 per Year.

Planet Holon - 20 Day Cycle

1 Unit = 28 Days or 1 Moon


13 Unit
Wavespell
Constant
= 13 Moons
= 1 Solar Orbit
= 1 NET Day

Moons 6 and 12 = Solstices

Moons 3 and 9 = Equinoxes


20
13
260
Galactic Cycle
13 Moons
x28 days + 1
365
Solar
Biotelepathic
Cycle

Timeship Earth 2013

Coded by 20 Solar Frequencies in Time


Wrist
Wrist
Elbow
Elbow
Shoulder
Shoulder
Hip
Hip
Knee
Knee
Ankle
Ankle

13:20 Noospheric Chip
"Homo Noosphericus"
20 Fingers + Toes
4 Limbs
13 Main Articulations
Consciously synchronized in 13:20 time. Plays Psi Bank Control Panel, generates Earth's Rainbow Brain



Man in the Noosphere

noospheric organization into psychic biomes. Through the psychic biomes-collectives of communities coordinating their bioregional network according to the structure of the "thought moments" of noospheric time-the human will fully evolve the Earth as a planet with solar-galactic consciousness.

ELECTROMAGNETIC WORKINGS OF THE EARTH'S RAINBOW BRAIN

What we call the cycles of time are the thought moments of the Earth. These thought moments coordinate the complex orders of Timeship Earth, understood as a whole system. Because the operating mechanism of the noosphere that governs the Earth's cyclic thought moments is inseparable from the general structure and functions of the electromagnetic field in which it is located, we may refer to a *rainbow brain* of the noosphere. Why is this so?

Let us return to the structure of the noosphere, Earth's mind in time. Consisting of the four bipolar psi bank plates, these four synchronic time plates are located between the two radiation belts, that is to say between 11,000 and 2,000 miles above the biospheric surface of the Earth. With the location of its information time-bearing mechanism between the radiation belts, the noosphere must by necessity operate in tandem with the electromagnetic field as it is regulated by these two master radiation belts. What do these belts do? They emanate Earth's electromagnetic aura, and function as a protective shield around the Earth. They do this by trapping solar-cosmic radiation, keeping much of it from hitting the biosphere directly, channeling it instead through the Earth's magnetic poles into the Earth's core.

In the polar regions excess cosmic radiation, including electrically charged plasmas and solar discharges from coronal mass ejections, is released into the atmosphere as the auroras-aurora borealis (or northern lights) in the North, and aurora australis (or southern lights) in the South. The increased solar activity during the most recent and current sunspot cycles has enhanced and extended the auroral activity in recent years far beyond the polar zones. In addition, since 1987 great influxes of plasma into the solar system have intensified the incidence of spectral plasmic activity within the atmosphere itself. This amounts to an increase in rainbows, halos around the sun, and brilliantly colored clouds. While these phenomena may be explained to a certain degree as meteorological effects (the angle of the sun's rays, moisture in the atmosphere, and so on), is there more to a rainbow than meteorological side effects? And what relation is there between the noosphere, the electromagnetic field, and the increased plasmic-rainbow activity?

Again, seen from the perspective of whole Earth, the rainbows and spectral plasmic effects, including the auroras, are the free energy released by the noosphere. Rainbows are to the noosphere what toxic waste is to the technosphere. The noosphere itself implies a mental field that is interacting with the electromagnetic field. The Earth's electromagnetic field is actually the strongest of all the planets in the solar system. The only other planet that has a field approaching the strength of the Earth's field is Uranus. If the Earth's electromagnetic field is the strongest, is this an indication of the strength of the noosphere as well? If the rainbows, auroras, and other spectral plasmic activity are a demonstration of the free energy released due to the interaction of the noosphere and electromagnetic fields, and the noosphere is the mental envelope of the planet, inclusive of the as-yet-to-be-unified mind of the human species, what forms of free energy might be released if the human mental field were operating as a single unity in the correct timing frequency?

One other mechanism crucial to the entire system of noosphere and electromagnetic fields is the crystal core at the center of the Earth. In the 1970s Russian scientists put forth the idea that the Earth is crystalline in nature, an idea that extended Plato's notion of the Earth as a dodecahedron, one of the five "platonic solids." The idea was that the Earth's surface was held together by a field of resonance that corresponds to the crystal resonance of certain geometrical solids. R. Buckminster Fuller also gave play to this notion in his description of "spaceship earth." Then in the 1980s American seismologists confirmed that the core of the Earth is actually a gigantic iron crystal structure in the shape of an octahedron, elongated at its ends, which point to the North and South Poles.

From the point of view of fourth-dimensional time, the planet Earth is another manifestation of space as an infinitely locatable point, an orbiting body upon which all the vectoral programs of cosmic time may be unfolded. Understood as a Timeship, the Earth's structure is constructed to facilitate its travel in time on a particular route in space in conformity with its relation to the local star, the sun, to the other planets of the solar system or heliosphere, and in synchronization with the universal timing constant 13:20, which maintains the Earth in the synchronic order. The role of the magnetic octahedral crystal core is to function as the bipolar oscillator and crystal transducer whose purpose is to maintain the Earth in the synchronic order of the 13:20 timing frequency. Thus, if the Earth's noosphere contains the 13:20 timing programs of the psi bank, and the crystal bipolar oscillator is meant to maintain the Earth's space body in the synchronic order, obviously there is a resonant relation between the crystal core and the noospheric-electromagnetic field programs.

The transductive properties of the crystal allow it to transform energy from one state to another. The crystal core also stores electronic plasmas that travel to it from the

Earth's poles through an electromagnetic flux tube system. Within the crystalline core, the electronic plasmas are transduced into information. This is the information of time understood as cosmically transmitted thought forms. These plasmic thought forms conform to programs already established in the psi bank of the noosphere. These are the Earth's thought forms, the cycles of the Earth's brain waves, as it were, that allow it to maintain its biospheric programs and to evolve its mental field, the noosphere. The very descriptions of the Noospheric Earth Time (NET), and of time itself as a synchronous instantaneity inseparable from telepathy, are examples of the Earth's thought forms transduced through a human biocomputer and then transmitted into a form of human language for the purpose of communication. Keeping this description of the noospheric brain in mind, let us return to our analysis of the biosphere-noosphere transition.

MAKING THE NOOSPHERIC LEAP: TRANSFORMATION OF HUMANS INTO NOOSPHERIC CHIPS

The transition to the noosphere is experienced by Earth as a crisis because its systems are stressed. Since the Earth functions as a whole system, stress on one component of the system actually stresses the whole order. Let us review the cumulative stress points. Human 12:60 electromagnetic activity has perturbed and distorted the electromagnetic field. The release of free energy due to geochemical combustion adds to this stressful distortion through the depletion of ozone in the ionosphere and global warming. The radioactivity released into the atmosphere adversely affects the resonant field of the DNA, already driven by the 12:60 frequency to accelerate the multiplication and propagation of the human biomass throughout the biosphere. Through its artificial means, the machine, the human further upsets the inherent balance maintained by the pressure that the species exert upon each other, resulting in mass species extinction.

Yet all this is according to an evolutionary program that is intended to bring about an ultimate crisis by which the biosphere snaps into becoming the noosphere. Clearly, if the root of this crisis is the deviation of the dominant species operating according to an artificial timing mechanism at odds with the universal timing frequency, then the stabilization of the transition to the noosphere will come about through the dominant species consciously "returning" to the correct timing frequency. This it can only do by adhering to a macro-organizing program that puts the human species completely in the 13:20 frequency.

If the whole system analysis seeks to locate the flaw in the operation of Timeship Earth, then we must finally declare that this flaw is the human civilization in its entirety, as it is maintained by erroneous and artificial timing constructs. Since the noosphere, the mind of time on Earth, defines the next evolutionary cycle, and because the humans are following a course dictated by being in the wrong time, calendar reform is the eye of the needle through which humanity must pass in order to get to the noosphere. Only by fully manifesting the noosphere will the Timeship Earth be truly put back on course once again. The noosphere is the program of time on Earth. Time is all that the noosphere has to give us. In consideration that the artificial time of the technosphere has fundamentally run out, the noospheric time should be a welcome gift.

Science is always absolutely precise. It is not just calendar reform that is the eye of the needle through which to pass into the noosphere-it is the Thirteen Moon/28-Day calendar calibrated by the 260-day Wizard's Count, synchronized to the Gregorian calendar date, July 26, that provides the exact ticket of admission into the noosphere. And then this ticket must be used at just the right moment-when the show is ready to begin. To use another metaphor, there is a lock on the door to the noosphere, and there is only one key that will fit and unlock this noospheric gate. That key is the Thirteen Moon/28-Day calendar, correlated to July 26 on the Gregorian calendar. It is the precisely applied use of this Thirteen Moon/28-Day calendar that will make each human a noospheric chip of the rainbow brain. This is because the Thirteen Moon/28-Day calendar is the key with the precise design for not only opening but also for continuing to operate the noosphere through a matching of the everyday frequency of time with the frequency of the noospheric control panel, the psi bank.

It is because the daily program of the Thirteen Moon/28-Day calendar is embedded in the 13:20 frequency that the consciousness of the humans will finally change and rise above the stunted level by which it is currently maintained in the artificial world of the technosphere. Time is of the mind, and the natural time registered by the Thirteen Moon/2 8-Day calendar is the opening to the geocosmic mind of the universe, which adherence to artificial time has kept the human from experiencing. The noosphere is the fractal lens of this geocosmic mind on Earth. Since the geocosmic mind is purely a function of the Law of Time-energy factored by time equals art, where the 13:20 synchronizing ratio of time is characterized by infinitely instantaneous velocity-then the fundamental nature of this mind is telepathy.

The Thirteen Moon/28-Day calendar is, therefore, the perfectly designed instrument to make the noospheric leap into telepathy, the planetization of consciousness that establishes the daily reality of the noospheric mind. Since the noospheric mind interacts with the electromagnetic field, and because the ratios and cycles of the Thirteen Moon/28-Day calendar conform to the fractals and ratios of the NET, by using this calendar the human becomes transformed into a noospheric chip. The fractals and ratios of NET become the normative operating cycles of the human in its daily reality. This accounts for an increasing noospheric synchronization that allows the noospheric chip to attain its purpose: generating the Earth's rainbow aura. If the free energy of rainbows is to the noosphere what the free energy of toxic waste is to the technosphere, then the generation of the rainbow implies a type of activity on the part of the human to produce such free energy. To understand what this activity might be and how it works, we must first understand the morphic and holonomic relation between the human noospheric *chip-Homo noosphericus-and* the structure of the noosphere itself as it is programmed into the geocosmic measure of the Thirteen Moon/28-Day calendar.

HUMAN BEINGS AS FRACTAL REFLECTORS OF THE 13:20 MATRIX

From the noospheric perspective, the prototype human is an embodiment of the 13:20 synchronization factor. The human has four limbs. Each of the four extremities has five digits, for a total of twenty fingers and toes that distinguish the human's operational capacity. The four limbs conform to the fourfold phasic operation ofNoospheric Earth Time, while the twenty digits conform to the 20 (4 x 5) factor of the 13:20 ratio. The human also has thirteen main joints or articulations: two ankles, two knees, two hips, two wrists, two elbows, and two shoulders; these six pairs coordinate the four extremities with the body, while the thirteenth articulation, the neck and spinal column, coordinates the body proper. These thirteen main articulations plus the twenty digits of the hand and feet conspire to make the human the perfect exemplar of 13:20 timing frequency, that is, a perfect model of synchronization itself.

Add to this the fact that the human has a highly evolved and refined brain and nervous system that is maintained and expressed by the skeletal structure of the thirteen joints of the body and limbs, completed by the sensitive mechanism of the twenty digits, and we see that the human is the perfect biocomputer for processing the information of the instantaneously telepathic geocosmic mind. The means to process the geocosmic information, and also the means by which the human is transformed into the noospheric chip, is found in matching its factors of daily synchronization and intelligence with those of the psi bank, the noospheric control panel. This is called harmonic arrangement of the synchronic order.

Of course, this description of generalized structure, activity, and interaction of the *Homo noosphericus* with the noosphere as such presupposes an entire reorientation of the goals and methods of being human. Such a reorientation of the human is also a function of making the radical change from the erroneous measure of the twelve-month Gregorian calendar, in which are embedded all of the Babylonian programs of history, to the perfect history-less harmony of the Thirteen Moon/28-Day calendar- the mere change of calendars encompasses a mental frequency shift. The readiness to make this change depends on the degree of moral revulsion the human experiences during the collapse of the technosphere. This moral revulsion would then correspond to a turning in the deepest seat of consciousness, which would then dispose the human intelligence to a consideration of the untried solution-change the calendar!

The Thirteen Moon calendar is the NET instrument for daily synchronization and unification of the human species as a single organism in time. Once adopted to the correct measure of this instrument, the human will de facto trigger the noosphere as an operating system of absolutely higher consciousness and mental order. **In** fact, the purpose of human evolution is precisely to become the ignition of the noosphere,


Left
Thumb
Right
Thumb
Crown
Receive
Left Truth Hand
White Chromatic
Right Fire Hand
Yellow Chromatic
Throat
Transmit
Earth
Uranus
Human
Holon
Know your
fingers and toes
Heart
Transduce
Uranus
Earth
Solar
Plexus
Receive
Left Sky Foot
Blue Chromatic
Red Blood Foot
Red Chromatic
Root
Transmit
Left
Big Toe
Right
Big Toe

Human Noospheric Chip

and thence to become normalized as the noospheric chips that maintain the operations of the noosphere. As a truly planetized being and consciousness, *Homo noosphericus* will engage in an order and type of reflective activity undreamed of in the technospheric era that is now passing.

First, by adapting to the daily NET timing instrument, the humans will be utilizing a "calendar" that correlates both a 365-day solar biotelepathic cycle and a 260-day galactic synchronization cycle. When the lunar phases are added to the interaction of these two cycles, then the human is able to enjoy the harmonic richness of time-the noosphere. The synchronizing and interactive measures of the counts of the solar and galactic cycles yield multiple levels of harmonic orders of time (Earth's "thought moments") that will activate aspects and levels of consciousness hitherto dormant in the human mind. The very mental act of replacing the order of twelve by the order of thirteen is a profound one. How is this so? Could it be that the whole of civilized history itself is based on the fear of the number *thirteen-triskaidekaphobia,* epitomized in the superstition about Friday the thirteenth-and that, therefore, dealing with the true nature of time has been avoided altogether?2

Currently humans operate by a world standard whose measure includes: seven-day weeks, inclusive of the notions of the 5-day work week and the 2-day weekend; an irregular distribution of twelve months of either thirty-one, thirty, or, in one instance, twenty-eight days; all set within a longer annual cycle that concludes with its visionless moment of New Year's Eve. Many Gregorian calendars will include the phases of the moon, but because the months differ in length there is no way in these calendars of seeing how the phases of the moon might be synchronized with the measure of Earth's orbit around the sun, nor is there any reason to consider that the uneven measure of twelve months has anything intrinsically to do with the solar orbit. Within the twelve-month structure of the Gregorian calendar, weeks, months, and phases of the moon all appear to be haphazard and arbitrary. Such a disorderly order can only bode an undercurrent of uncertainty and fear for the human mind.

By contrast, in the measure of the thirteen moons of twenty-eight days each, the 13 corresponds both to a 13-day cycle and to the cycle of the number of months (moons) per year. The measure of the 7-day week (a NET quarter hour) becomes an orderly harmonic: four perfect weeks occurring each moon, fifty-two perfect weeks each year, each week always beginning and ending on the same day of the week, week after week, year after year, while in fact every day of every moon occurs on the same day of the week, year after year. The effect of such a harmonic regularity on the human mind is incalculable. This is what is meant by a *perpetual calendar.* And to maintain this perfect regularity, the 365th day of every year (solar orbit), is no day of the week at all, but a Day Out of Time, a day for the human to be refreshed in utter timelessness.

Realizing that a day is actually a kin or one NET minute, the measure of one rotation of Earth on its axis, a 4-day cycle of four NET minutes constitutes a harmonic, a 5-day cycle constitutes a chromatic, while the 13-day cycle corresponds to one *wavespell,* the time constant that accommodates the measure of thirteen. Hence, a wavespell can be either thirteen days, thirteen weeks, thirteen moons, thirteen years, or so forth. The point is that by making the change of calendars the foundations of the mind organized in time are irrevocably altered. From the noospheric perspective, there is nothing arbitrary about the laws of nature. The same lack of arbitrariness should be reflected in the instruments that we use to measure time. By adapting to the Thirteen Moon/28-Day measure, the humans are adapting to a measure in which there is nothing arbitrary because it is a pure expression of the Law of Time. Thirteen is not at all a harbinger of bad luck, but the gateway to harmony in time! And it is by using this thirteen-based harmonic instrument of measure that the human is realized as a noospheric chip, a fractal of the noospheric mind, the mind of time on Earth.

NOOSPHERIC CHIPS: WIZARDS OF GALACTIC TIME

In the noospheric construction of the operating mechanism of the Timeship, the human is a vital link, providing the biotelepathic medium for the synchronization of the geocosmic mind on Earth. If we look again at the structure of the noosphere, the components include: the crystal core bipolar oscillator, packed with Technicolor time beams and cosmic thought moments, waiting to be self-reflectively realized; the human noospheric chip, the representative of the biosphere to mentally engage the timing cycles of the NET; the electromagnetic field, which provides the medium of expression between the biospheric order, the human, and the noospheric mind of time; and the noosphere itself, the mind of time on Earth, whose articulation through the psi bank control panels and through the Earth's resonant field structure yields an enlarged measure of Earth consciousness, Noospheric Earth Time itself. In expanding our minds into the noosphere we will understand that what lives is the Earth and the Earth lives through us.

As a noospheric chip, the human is a fractal reflector of the 13:20 timing frequency. Midway between the bipolar oscillator and the noospheric psi bank plates, the human noospheric chip is designed to receive, transduce, and transmit programs from the crystal core by synchronizing these programs with the psi bank.


NP+
Midnight—Noon
Electromagnetic Resonator
Rhythmic Solstice
Year 2 - Moon
Electric Equinox
Year 1 - Seed
Twilight—Dawn
Psi Plate IV
Psi Plate III
Psi Plate I
Psi Plate II
Iron Crystal Core
Biopsychic Resonator
Night Alternator
Day Alternator
Bipolar Oscillator
Dawn—Twilight
Solar Equinox
Year 3 - Wizard
Gravitational Resonator
Crystal Solstice
Year 4 - Storm
SP-
Noon—Midnight

Four-Phasic Noospheric Resonant Field Model, Timeship Earth 2013

Three resonators establish the gravitational, electromagnetic, and biopsychic fields held in place by the crystal core, the bipolar oscillator.

Two poles extend the bipolar field of Earth, which, guided by the day-night alternators, create the four-phasic noospheric field model.

Four psi plates govern the four phases, from daily NET minute to seasonal NET day, and to the four-part NET week, or Seed-Storm year bundle.

This is a process that can occur only within the construct of the regular harmonic sequence provided by the noospheric timing gauge of the Thirteen Moon/28-Day calendar. Interaction with the crystal core can only be through telepathic means, and the human-as the midway point between the core and the electromagnetic fields-is like a sensitive piece of litmus paper. To understand the human in this way is to totally redefine the reality of what it means to be human on Earth. From this perspective, the human is a biocomputer whose information source feeds it programs stored and emanated by the crystal core. These programs are then brought into conscious registration through working the corresponding programs of the psi bank. Right now, we don't know what the crystal core is emanating, much less that such a structure exists within the Earth. Like a crystal radio-set, the noosphere is the antenna, the geocosmic programs are transduced and generated at the crystal core, the human is the biocosmic tuner, and the broadcast transmission is provided by the psi bank.

The 13:20 template of the human noospheric chip is defined as the human holon, its twenty digits and thirteen main articulations conforming perfectly to the geocosmic 13:20 synchronization frequency of universal time. It is the intrinsic resonance of this geocosmic structure that allows the human to be in resonance with the planet as a whole system. While the timing programs to be broadcast are all loaded in the psi bank control boards, the actual point in space of the physical Earth is coded by time into a twenty-part icosahedral structure called a planet holon. Being holonomic in nature, the planet holon has a perfect incidence of correspondence with the twenty digits of the human holon.

The twenty digits and twenty-part structure of the planet holon are both coded by the twenty icons or solar seals of the 260-day galactic synchronization cycle. The icons or seals are the manifestations of the 20 (4 x 5) factor of the 13:20 synchronization ratio. They are coded for human legibility as simple icons that conform to a postliterate alphabet. In time these twenty icons create a fourth-dimensional twenty-day solar cycle which interacts with the 13-day galactic cycle to create the 260 unit synchronization sequence or "galactic spin." The point is that when this galactic spin is synchronized with the 365-day solar-lunar measure of the Thirteen Moon count, there is a daily program for identifying the human with the planet holon, a factor that facilitates the planetary resonance of the noospheric chip.

As a noospheric chip, the human is in every way a holonomic reflection of the whole system Earth. As a system of resonators-gravitational, electromagnetic, and biopsychic-the human and the Earth both have bodies with a center of gravity; both exhibit electromagnetic fields; and both share in common a biopsychic resonance, the mutual interface of the noosphere or mind of time with the other two


Right Fire Hand
Left Truth Hand
Crown—Receive
Throat—Transmit
Yellow Chromatic
White Chromatic
Human Holon
Know your fingers and toes
Heart—Transduce
Solar Plexus—Receive
Root—Transmit
Red Blood Foot
Red Chromatic
Blue Sky Foot
Blue Chromatic

Planet Holon—Timeship Earth 2013

fields of resonance. The redefinition of the human according to the Law of Time and to the nature of the noosphere also redefines the human's reality. What will the human do when history has been eliminated from the calendar and the new calendar itself is actually operated as a synchronometer-a measure of synchronicity?

First of all, as the necessary prelude to galactic culture, the absolute synchronization of the human in geocosmic time, the technosphere will be dismantled. Reorganized by the Law of Time into psychic biomes, the dismantling will naturally phase into the genuine creation of the new culture of solar-galactic consciousness. "Path beyond technology" means path of telepathic harmony. With its goals absolutely reoriented following the mental pole shift of the calendar change, the hierarchy of human values will also undergo a profound reordering. What if money were no longer the first consideration in human affairs? What if the consideration were instead how artful or artistic that action or event might be? What if the diaspora of humanity through industrialization and mass transport came to an end and the humans willingly chose to live in smaller communities organized by gardening and other Earth-related activities, inclusive of the transformative dismantling of the technosphere and the regeneration of the biospheric medium? What if the study of time replaced the study of physics as the dominant mode for determining the nature of reality? And what if, due to the time shift, a spiritual awakening swept through the human race so that a moral orientation of values was organized around the preservation and furtherance of the biosphere, and an acknowledgement that only One Supreme Creator could have ordained something so perfect as the noospheric mind of time? What kind of world would that be? What kind of art would be practiced in that world and what kind of science would be known?

Organized by the NET, human existence would spiral into the collective telepathic mind. A type of Earth geomancy would become the science of the noosphere. Or perhaps a more accurate name for this science would be *Earth geochronomancy*-the study and investigation of Earth in relation to the cycles of cosmic time and telepathy with an end to perfecting the Earth as a work of art. With minds expanded toward accommodating the longer, slower measure of NET, geochronomancy would inspire an entirely new vision of the Earth within the heliosphere (the solar system) and the galactosphere (the galactic order of things). Making the Earth's rainbow brain visible and manifest would be only the beginning of a willingness to explore further untapped psychic energy sources and means, or what is referred to in *Earth Ascending* as the science of radiosonics. Key concentrations of human habitation and activity would be organized to occur at or close to those geomagnetic energy points or centers, the whole cultural process of which would correspond to making a map on Earth of the image of galactic being as it moves in its great patterns of time. Would this not make the human species into a race of wizards?

In this consideration we may find a reason why the 260-day unit galactic synchronization measure-a galactic spin-is the key to what is called the *Wizard's Count.* The perfect synchronization of the 260-unit galactic spin with the 365-day Thirteen Moon/28-Day solar orbit establishes the 52-year cycle, or one NET year. A NET year (fifty-two solar orbits) is a "wizard's measure," for on this measure the human can expand its consciousness to encompass the Earth in its greater cycles of development. The Wizard's Count is also given its name because of the set of the four solar icons or seals that code the July 26 synchronization date in 4-year cycles: year one, Yellow Seed year; year two, Red Moon year; year three, White Wizard year; and year four, Blue Storm year. An entire Seed-Moon-Wizard-Storm sequence of four NET days (four solar orbits) consists of fifty-two moons, or one NET week, the perfect fractal of the fifty-two 7-day weeks in one NET day and the fifty-two solar orbits in one NET year. This four-part sequence is also called a Seed-Storm year bundle, the harmonic essence of the wizard's measure. Thirteen Seed-Storm year bundles, where each of the four icons is coded by the thirteen galactic tones (4 x 13 = 52), yield one NET year. Please note that even the Gregorian July 26 synchronization date is a function of the synchronic order: July = 7, while 26 is 13 doubled, 7 and 13 being the two principle numbers governing the 13:20 matrix of the Harmonic Module!

In the symbolism of the iconic sequence it is the Seed that is planted, it is the Moon that coordinates the growth cycles, it is the Storm that generates the energy, and it is the Wizard who knows and acts upon what is given. It was a White Galactic Wizard that coded the date and coordinated the year beginning July 26, 1987-followed twenty-one days later by the Harmonic Convergence. Thus it was the White Galactic Wizard who opened the gates to the closing of the Mayan baktun cycle of history and the commencement of the coming cycle of galactic culture. And on July 26,2003, the year of the White Spectral Wizard will commence. This year will end with its Day Out of Time, coded by the White Spectral Mirror. The day following, July 26,2004, will begin the year of the Blue Crystal Storm. On the Wizard's Count, which is not a calendar but a synchronometer, these two dates, White Spectral Mirror and Blue Crystal Storm, are the point in time when the Gregorian calendar ticket to the old time will be eliminated and the new Thirteen Moon calendar ticket for admission to the new time of the noosphere will be validated. This is when the noospheric show will be ready to begin its prelude. (See plate 6, Noosphere-Mind of Time on Earth.) Will the humans also be ready?

◆

8

Making the Transition to the New Time

A How-to Catalog and Guide to the *Pax Cultura, Pax Biospherica*

BY THE TIME these words are read, the technospheric collapse will have generated several more devastations and disasters. The wound received by the technosphere on September 11 was a mortal one. The technosphere suffered cardiac arrest for almost a week. Not only did the towers collapse, an event that occurred via television within the central nervous system of the human species, but belief systems, too, came crashing down. No longer is America the unassailable fortress of "democracy," while democracy itself is a concept that joins monarchy, nation states, imperialism, colonialism, capitalism, communism, and a host of other outmoded systems of belief and thought constituting the saga of human history-that is, the history of civilization. But all that is now ending. The perimeter of biogeochemical combustion and the limits of the technosphere have coincided. It is the Earth's turn to speak. How will the Earth speak?

The Earth can only speak through the noosphere, and the noosphere can only speak from the center of time that is constructive peace. Peace is harmony. Peace is the culture of the biosphere. The conscious harmony of time in the biosphere is the culture of peace known as the noosphere. Through the noosphere, the Earth speaks in ever-widening circles of order and meaning. While sunrise and sunset mark the passage of solar time, observing the phases of the moon keeps us in tune with the mystery of time. One kin, one passage of night and day, one NET minute, synthesizes the experience of the whole Earth during a single rotation on its axis. The synchronic order supplies a 260-unit synchronization gauge that the mind may engage and employ in the construction of a harmonic vision of reality. Twenty-eight NET minutes make one moon, one NET hour, moon after moon. The pattern of one moon contains the construct and pattern of every moon. The harmonic perfection of the synchronic order of reality releases the mind through the center of time into a freedom it had not known in the dark passage of history. How are we going to make this transition? Can we really shake off the old and the obsolete that easily?

THE THIRTEEN MOON CALENDAR MOVEMENT: THE DAWN OF A NEW GALACTIC CULTURE

"Greetings Explorers on Timeship Earth!" reads the opening text of the pocket-size *13 Moon Natural Time Journal.* "Welcome to this 13:20 natural time portal and fourth-dimensional galactic time template. A solar-lunar Earth calendar of the 13:20 timing frequency that is expressed through the thirteen tones of creation and the twenty sacred solar tribes. Attuning to this calendar will help you awaken and align to the pulse of the Universe, the rhythm of the One heartbeat. 13:20 is the natural timing frequency that unifies planetary and galactic consciousness. . . It is the expression and remembrance that Time is Art . . . By attuning to the 13:20 frequency of natural time, we break out of the 12:60 time warp and activate the remembrance of our true human nature. Time is energy. It is a frequency of the fourth dimension; mind, telepathy, imagination, and creation. Time is an exploration of unlimited Universal potential. So let us begin the journey and return to the rhythm of nature's galactic heartbeat. . ."[1]

This is the Earth speaking through a noospheric chip. Produced in Canada, it is one of many Thirteen Moon calendars produced this Yellow Solar Seed year. Others have been produced in Germany, Austria, Italy, Russia, the Netherlands, Japan, Brazil, Argentina, Chile, Mexico, and the United States. One such example from the United States is known as the 13 *Moon Natural Time Calendar: Ancient Science for the Art of Now.* Going through its pages one is flooded with a wealth of information, summarized by a quote from traditional Hopi wisdom: "We now face the final test of human consciousness-to restore our oneness with creation. We are going home. It is a process. It is like the seed becoming the green shoot and then the flower."[2] To make the calendar change is to restore the oneness with nature. The break with the oneness with nature was codified and thence programmed into an irreversible reality by the Gregorian calendar and mechanical clock. Only the breaking of the pattern of time established by these two instruments will release us again into natural time. The Thirteen Moon/28-Day calendar exists as the tool to demonstrate the contrast between harmony and disharmony, and to assist us, as a species, into effecting this return. If we are going home then we must make a turn away from our present course.

> Through returning to natural Time, we return to our natural state of divinity, living in harmony with the Earth and each other. We return to the nature of our spiritual existence. Realigning with the rhythm of the universe through the 13 Moon Calendar allows us to lay the foundation for the new paradigm of love and unity, replacing the 12:60 paradigm of fear and separation. . . The World Calendar Change Peace Plan strives to establish a new culture of peace on Earth through returning humanity to natural time. It is the goal of the worldwide Foundation for the Law of Time to effect the calendar change by the Day Out of Time (July 25), 2004 . . . Join the global movement to effect planetary change and establish the new culture of peace on Earth! Return to divinity and creative existence. . . Walk the path of the sacred warrior.]

The movement to change the calendar is a living force, a force that is living the New Time. Its premises are so diametrically opposite to those of the technosphere that, especially in the power bases of America and the G-7, one will find scant mention or notice at all of this movement. Yet it is a cultural phenomenon. In Tokyo, San Francisco, Milan, or Moscow one may find signs of the presence of this movement in the underground dance events, the raves or the Earthdance. More and more young people take on the names of their galactic signatures, the 260-day kin code for their date of birth in the synchronic order, names like Lunar Storm or Spectral Night, Galactic Wind or Planetary Dragon. These are all signs of the beginning of galactic culture on Earth, a phenomenon that has only been increasing over the past decade. The point is that the New Calendar Change Movement is a grassroots phenomenon as well as an ideological strategy known as the Campaign for the New Time. These signs are all whispers of the noosphere blowing through the bleak industrial corners of the technosphere.

Behind the more populist front of the Natural Time Movement is the science of the Law of Time, a genuinely noospheric science of peace and harmony. This science is already being studied and put into preliminary practice. As the crisis of the biosphere began to crest in 1987, halfway through the second 28-year phase of the technosphere, the noosphere began to download its measure of time through the discovery of the Law of Time. Invisible to the predominant forces of the technosphere, the science of the Law of Time began to map out an entirely new domain of thought, the synchronic order, a domain that could only be entered and applied through the correct noospheric measure, the Thirteen Moon/28-Day synchronometer.

All science throughout history is based on evolutionary advances predicated on both the premises and limitations of its preceding stages. We are at such an evolutionary moment now. The issue of the calendar change is only the beginning of the emergence of a new whole system scientific order. Understanding the flaws that are built into the present system of purely materialist science, we can proceed to the establishment of the science of the synchronic order. Like the radical simplicity and perpetual harmony of the Thirteen Moon calendar itself, the noospheric science of the synchronic order is predicated on an equally radical mathematical base reflecting and embedded in the 13:20 universal timing frequency itself. And as the underlying order of a whole system science, this mathematics is reflective of the non dualistic premise of a superior moral order. The deviation from universal synchronic time is a moral deviation as well. It is this moral deviation that most strongly prompts the current calendar change movement.

As a profoundly nondualistic, unifying whole system premise, the Law of Time encompasses not only a scientific-mathematical basis of morality, but a theological-eschatological intention that reunifies the various disciplines scattered and separated by the rise and totalitarianism of modern secular science. Because of the historical dominance of the Gregorian calendar, in which modern science is embedded, the dethronement of the calendar-the "devaticanization" of the world, as it were-is an apocalyptic moment.

As the Law of Time defines it, this is merely the apocalypse of the 12:60 timing frequency and all its corrupted institutions, much as foretold in the Book of Revelations. This apocalyptic moment was stunningly supplied by the terrifying collapse of the Twin Towers. As the nerve center of the financial, commodities, and transport sector of the technosphere, and hence of the city itself, the collapse of the towers in hardly more than an hour's time is perfectly reflected in the vivid descriptions of the eighteenth chapter of the Book of Revelations, "Fall of Babylon." Yet as the Mayan prophecy of Pacal Votan also makes absolutely clear, the apocalypse of the 12:60 is the resurrection into the 13:20 timing frequency, the return to natural time, all to be accomplished by A.D. 2012, Teilhard de Chardin's "omega point." The advent of the noosphere is preceded by the post-apocalyptic harrowing of hell. In this harrowing of hell, defined as the span of time fromJuly 26, 2000-July 25,2004, humanity must make a crossing from one time to another. This crossing is much like those we hear


13 Moons of Peace
Fifth World
2012
Sipapu Tunnel Between the Worlds
EPTEMBER
Tu We T
4 5
11 12 1
18 19 20
Fourth World
Sipapu Tunnel to Thirteen Moons of Peace
Kokopelli the humpbacked flute player leads humanity from one world to the next

about in the cosmovision of the Hopi, a rite of passage from the fourth world to the fifth world that occurs through an interdimensional tunnel called *sipapu.* On the other side of that tunnel, there is an emergence into the new time called "thirteen moons of peace."

"Golden Age of Miracles and Heaven on Earth," a story in the *National Examiner* (November 29, 1988), begins: "A heaven of golden miracles or a hell of unspeakable horror is less than twenty-five years away for mankind. That's the shocking prediction of the man who was responsible for the gathering of hundreds of thousands of people in 1987 to celebrate the Harmonic Convergence. . ." The article makes its point by referring to the end of the 5,125 year cycle in 2012. "Argiielles said Mayan predictions have always come true. He said their prediction for the year 2012 is that if humanity learns to live in harmony with Nature, a new age of miracles and light will occur. Otherwise plagues, wars, terrorism, and finally, the breakup of the planet into asteroids, will take place."4

As for the Inevitable Event, it would appear that humanity has begun the worst of the prediction-plagues, war, terrorism-yet, from the noospheric perspective, two points mitigate the absolute plunge into hell. The first is that the Inevitable Event punctured a hole in the technosphere eleven years prior to 2012. What does this mean? It means that this is the time of hell on Earth. "Every single one of you must see it [hell]; this is an irrevocable decision of your Lord." (Quran, 19:71) This being so, we can potentially emerge from it before the 2012 omega point. The other mitigating factor is the existence of a 13:20 movement dispersed throughout humanity. Since the noosphereis the 13:20 mind of Earth, the Thirteen Moon Calendar Change Peace Movement is the advance presence heralding the transition from the biosphere to the noosphere. This passage through hell is of a four-year duration, 2000-2004. The exponential implosion of the technosphere has already begun. But to avoid a long, debilitating siege of barbarism, humanity must select a positive direction by 2004 so that it can make it to the 2012 deadline as a species returned to living in harmony with nature. This it can only do by the dramatic and radical break with the past time offered by the Thirteen Moon/28-Day calendar Change Peace Plan.



Campaign for the New Time

4:7::7:2013

7th Seer
Pacal
Votan

Blue Galactic Storm
2000–2001
Seed Cube Flowering

Tibetan
Lunar
Calendar

Japan
Mount
Fuji

Foundation for the Law of Time Established

Launching of the Campaign for the New Time

Preparation of Strategies
- PAN Peoples
- Mass Media
- Diplomatic

International Kin Gathering Prepare PAN Congresses

Listen Again — Tree shapes space

Stabilizing — Way of conduct informed by truth

Meditation/ The Temple — Telepathy establishes the temple

Measuring — Galactic octave limits space

Planetary Peace Through Culture Festival

First Seed-Storm Year Bundle Gathered

Afro-Eurasian • Plate - PNM 1-6

See the Rainbow

6th Seer
Quetzalcoatl

Yellow Solar Seed
2001–2002
Serpent Cube Sex (Life Force)

Chinese and
Islamic
Lunar Calendars

China
Iran
Saudi Arabia

Indigenous Peoples Councils

Organization
of PAN Peoples
New Time
Congresses

Banner of Peace returned to Altai

Colombia New Time Peace Congress

PAN Peoples New Time Congresses Develop Local Programs for Social Transformation

People Together — Tree evolves space

People Organized — Truth evolves way of conduct

Evolving — Telepathy evolves the temple

Inner Space — Galactic octave resounds as mind

Planetary Peace Through Culture Festival

Pacific Plate • PNM 19-24

See the Rainbow Round the Earth

4th Seer
St. John
of Patmos

Red Planetary Moon
2002–2003
World-bridger Cube Death

Africa

India

UR Council
for the
Integration
of all
Lunar Calendars
in 13 Moon
Calendar

PAN Peoples New Time Congresses Implement Strategies

Time of
Great Awareness
of New Time

People Apart — Tree defines life

Wisdom of the People — Conduct defines the way

Transcending — Temple incorporates telepathy

Inner Time — Galactic octave defines evolution

Planetary Peace Through Culture Festival

American • Plate PNM 13-18

Be the Rainbow Round the Earth

White Spectral Wizard
2003–2004
Hand Cube - Accomplishment

Vatican Put
on Notice

Wall Street Journal Ad Strategy

Calendar Reform Becomes Major World Issue

Harmonic Convergence of PAN

Media Diplomatic Strategies

Power of the People — Tree of time turns Earth

Way of the People — All points unify in conduct

Wisdom Arousing — Telepathy becomes time travel

Accomplished — Galactic octave universalizes space

Atlantic • Plate PNM 7-12

2nd Seer
Padmasambhava
Fulfillment of the
Cycle of
Seven Seers
1997-2004

Victory of
the New Time
Thirteen Moon
Calendar Reform
Attained
Thirteen Moons
Proclaimed and
Accepted as New
World Calendar

Circumpolar
Rainbow
Victory
Event

Sacred
Earth
Sacred
Order

Earth Wizards Define Spiritual Order of New Time Lay Foundations of Shambhala in Temple of Rainbow Plasmic Body

THE BIRTH OF THE CAMPAIGN FOR THE NEW TIME

> *"We inspired Moses: 'Lead My servants out,*
> *and strike for them a dry road across the sea.*
> *You shall not fear that you may get caught, nor*
> *shall you worry.*
>
> *"Pharaoh pursued them with his troops, but the*
> *sea overwhelmed them, as it was destined to*
> *overwhelm them."*
>
> -QURAN, 20:77-78

The Thirteen Moon/28-Day calendar is the dry path across the waters of the 12:60 chaos. Holding surely to this path, "Pharaoh's troops will be overwhelmed," as it is destined, for the truth always prevails and when falsehood is exposed, falsehood perishes. The 12:60 frequency enshrined in the Gregorian calendar represents an artificial, hence false notion of time. The Pharaoh's troops are the forces of the technosphere that, embedded in the artificial structure of the Gregorian calendar, are destined to be overwhelmed and overcome by the fury unleashed both by human nature and nature itself in response to decades, if not centuries, of irresponsible despoiling of the Earth. The dry path of the Thirteen Moon/28-Day calendar is the only path broad enough for all humanity to leave the ever increasing ocean of chaos that characterizes human existence bound in the collapsing 12:60 matrix born of Gregorian civilization, the technosphere. Yes, the dry path across the waters of the 12:60 chaos provided by the Thirteen Moon/28-Day calendar truly is for the salvation of life on Earth.

Ever since 1993, the Thirteen Moon Calendar Change Peace Movement has consciously been drawing from the infinite riches of the noosphere to create not only the mechanism for making a shift in the frequency and hence bring stabilization to the biosphere, but has been anticipating the biosphere-noosphere transition into the *Pax Cultura, Pax Biospherica.*

Foll{)wing in the footsteps of its predecessor, the new calendar movement has dutifully contacted the United Nations and the Vatican and convened various congresses and delivered ultimatums in an effort to draw attention to mankind's time malaise. Now that the Inevitable Event has fully disengaged the human mind from the reality it thought it was pursuing in the new millennium, the second definitive wave of the World Thirteen Moon Calendar Change Peace Movement has also been launched: the Campaign for the New Time.

New Globally Unifying Harmonic Standard



FOURTH DIMENSION: Pure whole number mathematical order—syntropy, synchronic order

Harmonic Solution

Calendar Change

Replace current irregular calendar with a harmonic standard

Paradigm Shift

Campaign for the New Time

13 Moons. 28 Days.

Regular Units of Measure

28+28+28+28+28+28+28+28+28+28+28+28+28+1 = Harmony

"Mental barrier" separating fourth-dimensional realm of conscious wholeness of synchronic order from third-dimensional realm of "hard science" physical plane of reality and materialism.

Line of inexorable technological progress: neoliberal economics, globalization = biospheric instability and destruction.

Coercion
Compromise
Money

Political Solution

Military Solution

Guerrilla Warfare
Terrorism
Convential War

IMF - World Bank
G-7 WTO
Security Council

"Secret Deals"

NATO
Nuclear war
Arms Industry

Linear Arrow of Time = line of inevitable degradation and entropy of manifestation (matter)

Gregorian Calendar Time Line = macro-organizing timing standard establishes irregular measure as basis of all dominating concepts of linear time, disorder, entropy, and the techno-economic inexorability

THIRD DIMENSION: Manifestation-matter entropy and disorder

Irregular units of measure:

31-28(29)-31-30-31-30-31-31-30-31-30-31 = Disharmony

If today is Sunday, July 8, what day of the week will August 8 be?
What is the meaning of the names of the months?
If *September* means "seven" why is it the ninth month?
August is named after Augustus Caesar, July for Julius Caesar, March for Mars, the god of war; could this be a reason why we are programmed for chaos and violence? Think about it.

This campaign consists of a preparatory four-year cycle, 2000-2004, the Harrowing of Hell, which is the duration of the campaign itself, plus a one-year trial period, 2004-2005. The goal of the four-year campaign is universal calendar reform, the replacement of the Gregorian by the Thirteen Moon Calendar, effective Blue Crystal Storm, July 26,2004. This final year of the Blue Crystal Storm, 2004-2005, also completes a Seed-Storm year bundle begun in 2001, fateful year of the Yellow Solar Seed, the year of the Inevitable Event. To ensure the success of this unprecedented move on the part of humanity, the calendar reform must include the one-year trial period, during which time the entire species must be operating by a new standard, the harmonic Thirteen Moon/2 8-Day synchronometer. "If you never try it, you'll never know what it is," is the slogan that describes the campaign's target year: July 26, 2004-July 25, 2005, an entire year without the Gregorian "30 days hath September. . . ," but instead, Thirteen Moons of Peace.

To realize its ambitious goal of universal calendar reform, the Campaign for the New Time must impress itself on the human consciousness as the all-unifying campaign for peace to overcome the destructive forces unleashed by the technospheric collapse. Fortunately, much groundwork has already been laid. The codes of the Law of Time have been formulated and compiled. Preliminary practices to engage the synchronic order of the noosphere have already enlisted humans from around the planet. What the Vatican has tried to ignore and what the United Nations has been unable to fully engage must now be brought to the forefront of all humanity as the harmonic solution. The harmonic solution is a set of logical arguments that should be studied and rehearsed by everyone who seriously wishes to even consider the possibility of a Campaign for the New Time. Let us contemplate the following set of logical arguments.

Premise

Currently all conflict resolution of a global scale is attained through one of two poles: a political solution or a military solution. No other alternatives are recognized. According to the Law of Time, there is a third solution, the harmonic solution. Without this third solution, no harmonic resolution is ultimately possible for any conflict on a global scale. The third solution defines the first two solutions as a polarity embedded within a timing standard that is hopelessly irregular and that, therefore, disposes the mind to disharmony. A mind predisposed to irregularity and disharmony is incapable of producing any long-term solution. The basis of the harmonic solution is to change the timing standard from an irregular to a regular one, thereby inducing a timing sensibility that disposes the mind to harmony rather than disharmony.

Thirteen Moon/28-Day Count and Global Conflict Resolution

The inability to attain global peace, much less the resolution of many localized conflicts that have become endemic, is due to a lack of a globally unifying timing standard-the macro-organizing principle of human sensibility. Present-day conflict resolution is represented by two poles, political and military. The military solution consists of guerrilla warfare, terrorism, and outright military conflict, all of which are engendered by problems of inequality; injustice; rampant nationalism; tribal, racial, or religious antagonism; and greed for control of natural resources. Underlying the military solution is an aggressive armaments industry that seeks to hold its own as a capitalist venture, always seeking new markets. The political solution is always fostered as the only cure for the military solution, and is administered through varying degrees of coercion, compromise, and the inevitable lure of money-the IMF and the World Bank are never far behind any political solution.

Neither the military nor the political represent any kind of morally satisfactory or enduring solution because both are functions of and embedded in a timing standard that has disharmony built into it. Even the local timing systems, themselves feedback loops holding in place various belief systems, are coordinated by the dominant disharmonic standard. As long as the current global standard, the Gregorian calendar, is the controlling timing factor, resolution on a global and local level is not only impossible, but increasing disharmony is guaranteed. The harmonic solution calls for the immediate establishment of a globally unifying harmonic standard, the Thirteen Moon/28-Day count. With its absolutely consistent units of measure, this macro-organizing principle is a paragon of harmony and thereby represents the positive, creative, and viable first step to enduring global conflict resolution.

Thirteen Moon/28-Day Paradigm Shift

The harmonic solution, the alternative to the polarity of the military and political solutions, calls for the immediate replacement of the current irregular measure with the harmonic standard of the Thirteen Moon/28-Day count. This replacement constitutes the long-awaited and long-prepared-for paradigm shift in human consciousness. The very analysis and concern that engendered the first movement to replace the Gregorian calendar-the effects of an irregular measure on human behavior-is now so dire that the concluding step must be taken. To quote Einstein once again, "Since the advent of the nuclear age, everything has changed but the way people think; thus we drift toward unparalleled catastrophe." With the analysis of the Law of Time we know why thinking has not changed-the human mind is the pawn of an aberrant timing mechanism. To change the way people think, make one little change in their everyday lives: Change the calendar. If we could send a man to the moon, we can change the calendar. This change will be the first step-the rest will come easily because with this one change we shall have changed our minds and entered into a New Time. To make this one little change a target date is needed, and the people need to mobilize as a force of synchronization for peace to mandate this change. The target date is July 26, 2004--the mobilization has already begun.

New Worldview of the Law of Time

The Thirteen Moon/28-Day count is the pragmatic application of the Law of Time. The discovery of the Law of Time was necessitated by evolution as the only way that could offset the deleterious effects of an erroneous timing standard on human consciousness. The Law of Time takes the radical view that time is a frequency, the universal frequency of synchronization; that the purpose of time is to synchronize; and that, therefore, a calendar is in harmony with the Law of Time to the degree to which it maximizes opportunities for synchronization. From the perspective of the Law of Time, the current macro-organizing standard is anything but synchronous, and hence contrary to the laws of nature. Synchronization produces harmony, harmony is a function of beauty, and beauty is the natural result of the Law of Time: $T(E) = Art$, energy factored by time equals art, where art is the entire spectrum of phenomenal reality in which even the most menacing-looking creature is elegantly constructed.

National Geographic recently stated: "Beauty seems to be an intrinsic part of nature and perhaps even the organizing principle of reality. Scientists in testing their theories, invariably find that the simplest, most elegant, most beautiful is the correct one. Rainbows, butterflies and the periodic table are some examples of intrinsic beauty. The world will be saved by beauty."5 The Law of Time agrees. The world will be saved by beauty, and the proponents of peace through culture will be in the vanguard. The Law of Time formalizes the perception of the intrinsic beauty of nature- $T(E) = Art$-and thereby provides a scientifically solid critique of the ugliness and social disharmony fomented by the irregular and artificial timing standards that control humanity today. By the same formulation, the Law of Time also establishes a vast and comprehensive definition of the fourth dimension, which was wanting until now precisely because of the embedding of all current perceptions in the erroneous timing standard.

The mathematical order underlying the universal frequency of synchronization, 13:20, describes a new order of reality, the synchronic order. The synchronic order governs the fourth-dimensional order of reality much as the laws of gravity, thermodynamics, and the special theory of relativity govern the third-dimensional order of reality. By taking into account the nature of the synchronic order, humanity's views of the third dimension will inevitably be altered to a greater conformity with the harmony of the fourth dimension. The fourth dimension is defined as the primary mathematical order of time, governed by a syntropic whole number system of ratios and fractals operating in a radial and nonlinear manner.

The third dimension is the world of manifestation and matter that inevitably entropizes. Losing sight of the inherent harmony of the synchronic order from which it is actually inseparable, the human fixation on the increasing entropic anomalies of the third dimension produces problems such as how to reckon what appear to be the extra hours, minutes, and seconds that occur every time the Earth orbits the sun. To this seeming dilemma, the Law of Time asserts that number precedes manifestation, harmony precedes materialization, therefore manifestation must accord with number, and materialization must reflect an original harmonic order. Entropy and degradation cause manifestation to deviate from number and mathematical law. But for mind to be stable, mind must accord with and conform to mathematical law rather than with entropy and degradation. The timing standard in use causes the mind to conform with entropy and degradation. This is what must be corrected.

Harmonic Solution-Harmonic Resolution

Harmony can only produce harmony. From order comes order. From disorder you can only expect chaos. From disharmony can only come disaster. Irregular measure entropizes. Harmonic measure syntropizes. These are the contrasting values brought into focus by replacing an irregular macro-organizing principle with a regular one. Implementation of a globally unifying harmonic standard is the only hope for resolving all conflicts in time. A harmonic standard lifts all conflicts to a higher level dialog of unification in time. The harmonic solution, the World Thirteen Moon Calendar Change Peace Plan, provides: the opportunity to call an immediate and universal cease-fire, as well as a halt to the otherwise inexorable process of entropic degradation of society and environment; and offers the resolution to establish new agreements, to renegotiate old treaties, and to create a new globally binding and unifying covenant for all people in a new time.

It must be understood that to change the calendar is to delegitimize all the institutions embedded in it. This radical but peaceful delegitimization of the old order is what is needed to break the deadlocks, stalemates, and historically outmoded treaties and agreements now binding on humanity. The new globally unifying standard, the Thirteen Moon/28-Day count, will legitimize and institutionalize harmony and thus create the advent of a synergistic order capable of resolving entropic disorder because it is reflective of and rooted in the primordial whole number structure of the synchronic order of reality. In its entirety, this represents a new step and direction for human evolution-a step without which there might not be any creative future for humanity and the planet.

How to Accomplish World Peace Now

The analysis, the historical precedents, and now the affirming authority of the Law of Time render the harmonic solution as the only way to immediately bring about World Peace. All that is lacking is the will to synchronization among all good-hearted people, groups, and organizations otherwise committed to peace, a better environment, and human spiritual well-being in general. How to accomplish World Peace is to galvanize the human will to synchronization on behalf of the establishment of a genuine time of harmony and peace. This can only come about through the simple but highly radical and paradigm-altering act of exchanging the current macro-organizing system of the Gregorian calendar for the harmonic order of the Thirteen Moon/28-Day count. All other localized calendar systems would be kept intact, but they would be coordinated by a new standard, a standard that promises harmony instead of disaster, order instead of chaos, peace instead of war.

Such is the harmonic analysis and solution of the Law of Time, which can be summed up by a simple demonstration of the irregular Gregorian calendar contrasted with the regular Thirteen Moon calendar, as well as the question: "Which do you prefer, harmony or disharmony?"

If you answer this question on behalf of harmony, and you agree with the foregoing premises and analyses, you must move into action. You need to get a new calendar, a Thirteen Moon/2 8-Day calendar and find out for yourself: noosphere or necrosphere, the choice is yours. The option opened by the Inevitable Event and the collapse of the technosphere is precisely that: necrosphere, the transformation of the biosphere into a sphere of death-a dead planet-or the noosphere, the mental envelope of the Earth, governed on the human plane by the Thirteen Moon/2 8-Day calendar. The difference between the necrosphere and the noosphere is the difference between a machine and the Earth as a whole system. You cannot even really say there is a comparison. But what we can say most emphatically is that the Thirteen

Moon/28-Day calendar and the shift to the 13:20 frequency is the pure manifestation of the Law of Time in human affairs. It is the only antidote to the destructive grip that the 12:60 timing frequency now has upon the biosphere through its thoroughly artificial instrument, the technosphere. (See plate 7, Necrosphere or Noosphere.)

THE FINAL DECISION: NOOSPHERE OR NECROSPHERE?

As these lines are being written, seven weeks have passed since the Inevitable Event. The analysis of this event from the perspective of the biosphere, the temporary structure of the technosphere, and the advent of the noosphere was a spontaneous inspiration. Each morning, often well before dawn, I would be called to this technospheric device, an iMac, to put the noospheric mandate down into words. In this process, the matter of prophecy kept occurring and could not be avoided. Even the issue of calendar change increasingly takes on the quality of a prophetic enactment. What is prophecy from the noospheric perspective?

Prophecy is the release of information according to the psi bank timing program and in relation to degrees or levels of consciousness positioned at different points in time. The points in time are human channels. That is, there are the prophets who declare the prophecies by whatever means or forms, and then there are the decoders of the prophecies, those able to read the signs according to the prophecies with the aid of different symbolic lexicons. Prophecy is always startling to the mass mind, which is ignorant of the true nature of time. A prophetic event may seem totally random, when it is not. Someone may design a plot, such as that of the Inevitable Event, with whatever fantastic notions and motives. Yet the occurrence may go beyond being merely a matter of human manipulation. The humans were but the instruments of sets of cause-and-effect chain reactions established within the structure and evolution of the biosphere and the playing out of human karma.

According to the psi bank timing program governed by the Law of Time, the technosphere could only have a limited duration. Two perfect 28-year cycles of the Gregorian calendar program, leading to the first year of the third millennium, marked the duration of the technosphere. Because this cycle concluded with the beginning of the third Christian millennium, a singular event was poised in time to attract and catalyze a host of prophetic moments long prepared for and sealed in the psi bank by Christian, Islamic, and even Mayan prophecies. Such was the Inevitable Event. Within the motivations of the perpetrators of the Inevitable Event, the biosphere found its perfect instrument of divine purpose. That there were nineteen hijackers conforms to the Quranic nineteen code expressed in the enigmatic verse, "Over it is nineteen."

(74:30) The following verse begins, "We appointed angels to be guardians of Hell, and we assigned their number [19] . . ." This verse ends by asking, "What did God mean by this allegory? . . . None knows the soldiers of your Lord except He. This is a reminder for the people." (74: 31)

Certainly in the success of their mission, whether they were conscious of it or not, the nineteen Muslim hijackers-who organized themselves as four leaders (pilots), three logistics people, and twelve "soldiers"-fulfilled their function of being the prophetic emissaries of the nineteen guardian angels who watch over Hell. And indeed the gates to Hell have been opened. In the world of the secular mind of the technosphere, no one wanted to talk about the apocalypse or Armageddon, though the jihad was brought up quite often as a factor in the thinking of the Islamic terrorists.6

Whether it is seen as a prophetic or karmic event, as we stated earlier, there is no question that the timing programs of two civilizations, the Gregorian and the Islamic, were on a collision course. "The civilization of Islam is radically so different from that of Western civilization which dominates the world today. The two are different in their description oflife as well as the foundation on which they base such a description. The difference between the two civilizations is so essential that they have developed in ways which are radically contradictory to each other."7 So wrote the eloquent Saudi historian, Muhammad Husayn Haykal in his essay "Islamic Civilization," as presented in his masterful biography, *The Life of Muhammad.* And what is at the root of this difference? A separation of church and state, which in the West led to a profound materialism and economic worldview.

Haykal continues, "The victory of materialist thinking was largely due to the establishment of Western civilization primarily upon an economic foundation. This situation led to the rise in the West of a number of worldviews which sought to place everything in the life of man and the world at the mercy of economic forces. . ." As for the sanctity of its economic beliefs, Haykal concludes that the West has tied its economic activity "hand and foot by public laws and commanded that every Western state and army prevent any violation of economic laws with all the power and coercive means at its disposal."8 Given this insightful assertion by an Islamic thinker written a half-century ago, it is not at all surprising that the terrorists concentrated their attacks on the most visible symbols of Western global materialism and economic and military imperialism, the Twin Towers and the Pentagon. It is also of note that one of the logistics men on the team of nineteen hijackers, Majed Moqed, had been a professor of economics at King Saudi University in Riyadh.

However we see this event, the most important point is that it actually happened, no matter who caused it or how. In this regard the collapse of the World

Trade Center towers and the penetration of the Pentagon was the Inevitable Event both from the point of view of the biosphere and from that of prophecy as mandated by at least two major timing programs, the Gregorian and the Islamic. Of course, prophecy is a matter far from the consideration of the technocratic mind, so the immediate aftereffect is a heightened nationalism, patriotism, and commitment to war. But what is going on from the noospheric point of view is not so much the combat of different armed camps defending or attacking competing ideologies, but an end game, the biomass of the technosphere maneuvering against time in a self-destructive process that is really nothing more than the continuing collapse of that which it is defending.

How long will this collapse take? With the weapons of mass destruction currently at the disposal of the combatants, it shouldn't take too long before the human race realizes that if it doesn't stop the self-destructive process, it will soon be curtains for all life on Earth. A more significant question, if we wish to make the transition to a new time, is: How will the self-destruction end, and how can it be stopped-or can it? It is easy to see how wars begin, but no one can tell how they will end.

THE SOLUTION TO WAR: PEACE THROUGH CULTURE, PEACE OF THE BIOSPHERE

At the end of the First World War, the League of Nations was formed to keep the Second World War from happening. The League of Nations was unable to both effect the calendar reform it promoted and keep the Second World War from happening. These are not unrelated events. The Second World War effectively eliminated the League of Nations, and toward its end a new organization, the United Nations, was formed. Like the League of Nations, the United Nations was formed to prevent the next world war from happening. Within eleven years, the United Nations tabled the calendar reform begun by the League of Nations. Coincident with the formation of the technosphere, the United Nations has now also completed fifty-six years of existence. With the expanding "war against terrorism," is its purpose now over as well? The only way the United Nations can survive is to maintain its humanitarian agencies, for the age of nationalist politics and nation-states is over, succeeded by the politics of terrorism, the last politics of history. What new kind of global organization will we need at the end of the War on Terror, or World War III?

What we will need is an entirely new agency, a Planetary Biospheric Assembly that will model and create a sustainable *Pax Cultura, Pax Biospherica.* Given the failure to enact a calendar reform on the part of both the League of Nations and the

United Nations and in consideration of the chaos now clearly embedded in the Old Time, only an agency or instrument that fully embraces and promotes the calendar change will be able to move into the genuinely peace-fulfilling role that such an organization must take. If the United Nations could accept the route of calendar change as the only way to bring all humanity to a new point of discourse, then it could take on a renewed life. But if it cannot rise to this occasion, then another organization must take its place, the Planetary Biospheric Assembly. Even so, when we speak of the *Pax Cultura, Pax Biospherica,* we are speaking of a new human covenant, one in which the biosphere takes precedence over all nationalist corporate interests, and in which peace as a manifestation of culture is the primary value of the new time. Such a covenant would be a biospheric covenant, an agreement and understanding that, first of all, the human is a member of the biosphere, and second, that in consciously accepting the calendar change, the human is also in the process of becoming *Homo noosphericus.* Henceforth, it will be art and not money, bioregions and not nation-states, that will be the cause of social organization. Only in this way will humanity be guaranteed a true post-historical future.

Assuming the calendar change occurs on Blue Crystal Storm 2004, the first step in ~ngendering the full manifestation of the noosphere will be the dismantling of the technosphere. This can only be accomplished if a full reorganization of the human in time, inclusive of an adjudication of inequalities and a redistribution of wealth, begins to occur during the 2004-2005 Crystal Storm year. The following four years, 2005-2009, a genuine First World Peace, would see the constructive transformation of the five-part technospheric system. All the apparatus of heavy industry, energy, and the transport system would be turned like compost, to be replaced by nonpolluting technologies and means of transport, while the cities would be transformed into urban gardens with the human race once more becoming decentralized. This process itself, a massive planetary engineering project with an eye on the full development of geochronomancy, would prove to be the greatest and most thoroughly positive transformation in human history. By 2009 humans reorganized by the Law of Time and having finally arrived at the "path beyond technology," will be enjoying universal telepathy, the noosphere-life beyond the Internet. By 2012 the humans will realize peace through culture as a permanent value, and by 2013 Earth will be galactically synchronized through a fully activated noosphere into the beginning of an entirely new geological era, defined by Vernadsky as the Psychozoic Era.

Pax Cultura, Pax Biospherica refers to both the new era of humanity following the devastation of the Final War and the governing body of bioregional councils (not nation-states) comprising the new world "government," the Planetary Biospheric

Arcturus Victory Strategy
Pax Cultura, Pax Biospherica

Telektonon, the Theater of Time, provides the journey through the Cube of the Law: Plane of Mind, Plane of Spirit, Plane of Will, and Divine Source Telektonon—each plane Seed-Storm year bundle, an entire universe of noospheric time!

Plane of Spirit: First Seed-Storm year bundle, NET week 9 Seed–12 Storm, 2001–05



Plane of Mind:
1997–2001
End of the Seven Years of Prophecy and the old millennium

2003–2004 11 Wizard Year	**2002–2003** 10 Moon Year	**2001–2002** 9 Seed Year
The Great Calendar Change	**Harrowing of Hell** Planetary catharsis—climax of biogeochemical combustion	
2004–2005 12 Storm Year **"New Time on trial"** First Bolontiku Lord of Time	**2011–2012** 6 Wizard Year **Harmonic Perfection** Eighth Bolontiku Lord of Time	**2010–2011** 5 Moon Year Seventh of Bolontiku Lord of Time
2005–2006 13 Seed Year **Pax Cultura, Pax Biospherica** Second Bolontiku Lord of Time	**2012–2013** 7 Storm Year **Triumph of the Noosphere** Ninth Bolontiku Lord of Time	**2009–2010** 4 Seed Year Sixth Bolontiku Lord of Time
2006–2007 1 Moon Year Third Bolontiku Lord of Time	**2007–2008** 2 Wizard Year Fourth Bolontiku Lord of Time	**2008–2009** 3 Storm Year Fifth Bolontiku Lord of Time

Divine Source Telektonon:
2009–13
Third Seed-Storm year bundle,
1 NET week

Plane of Will: Second Seed-Storm year bundle, 1 NET week, 13 Seed–3 Storm, 2005–09
Time of Transformational Destructuring—First World Peace

Assembly. The main purpose of the new governing body would be to monitor the advent of the noosphere. Overcoming Northern Hemisphere bias, the *Pax Cultura, Pax Biospherica* will not find any permanent seat, but will begin its existence as a planetary noospheric congress in the Southern Hemisphere. All of this could be made possible only because of the completion of the calendar change. So let us assume the best. The how-to of paradigm shift begins with the Thirteen Moon calendar.

If you follow the Thirteen Moon calendar or tell others to follow it with you, what is the payoff? The payoff is that you get to become a noospheric chip. Only a noospheric chip can bring Heaven on Earth, which is nothing more than full human participation in the noosphere. This is not at all a theoretical matter, but something that can be practiced and followed on a day-to-day basis. Fortunately, a path has been shown, complete with travel aids.

CONCISE *HOMO NOOSPHERICUS* HOW-TO TIME TRAVELER'S GUIDE TO THE BIOSPHERE-NOOSPHERE TRANSITION

This analysis of the Inevitable Event could never have occurred if the Law of Time hadn't been discovered and defined. The Inevitable Event simply supplied the Law of Time with precisely the right historical moment to provide a thorough analysis and explanation of time as the whole system in which we humans live and operate, inclusive of the biosphere, the technosphere, and the noosphere. As the chief discoverer of the Law of Time, assisted by my wife and an increasing number of other humans who have engaged the Law of Time, I have sought only to make a presentation of matters in which we, as a species, are thoroughly immersed, and thus find difficult to comprehend. Such is the technosphere, and such also is the medium of time. Since the publication of *The Mayan Factor* and my pursuit of the underlying mathematics of the Mayan calendar, I have remained outside the conventional arenas of discourse and communication, preferring instead to remain more anonymous in order to test the various hypotheses of the Law of Time.

In this process over the past twelve years, the Law of Time has precipitated from the noosphere various tools and didactic texts, all for the purpose of enabling us to make the shift from the old paradigm of the time of war to the new paradigm of the time of peace. These tools and principles are actually practiced on a daily basis, and so provide a pragmatic means of applying the Law of Time. Because of my vows and need for scientific "purity" of the experiment I have been living, I was involved at all times in doing my utmost to remain in the 13:20 frequency. For this reason, the tools and texts prompted by the noosphere to define the Law of Time were, for the most part, all produced outside the commercial mainstream. Now a great effort must be taken to make these tools and texts available to humanity in order to assist in the transition from *Homo historicus* to *Homo noosphericus*. By presenting a catalog of these tools and texts we only mean to suggest and define for the reader the scope and existence of a preliminary science of time and telepathy.

Part I. The Tools: Establishing Noospheric Earth Time (NET)

THIRTEEN MOON/28-DAY SYNCHRONOMETER

The harmonic standard of noospheric time, the Thirteen Moon/28-Day synchronometer, is a perpetual, harmonic calendar. It is called a Moon calendar because it is based on the female 28-day menstruation cycle, which is also the average lunar cycle. In actuality the moon goes around the Earth thirteen times a year. This means that the Thirteen Moon calendar is a genuine solar-lunar calendar that measures the Earth's orbit around the sun by the apsidallunation cycle of twenty-eight days. Thirteen perfect months of 28 days = 52 perfect weeks of 7 days = 364 days. The 365th day is called the Day Out of Time because it is no day of the week or month at all. This day, which falls on the Gregorian correlate date ofJuly 25, is a day for forgiveness and the artistic celebration of life and freedom. The synchronization or New Year's date of the Thirteen Moon calendar is July 26, and corresponds to the rising of the great star Sirius. This makes the Thirteen Moon calendar a tool for harmonizing ourselves with the galaxy. Of course, the Thirteen Moon calendar also synchronizes the phases of the moon in a pattern that demonstrates its regularity and order.

One of the great advantages of the Thirteen Moon synchronometer is that day/date calculations are amazingly simple. Any day of any week is the same for any Moon, any year. The first day of every Moon is always a Thirteen Moon Sunday (Dali). The last day of every Moon is always a Thirteen Moon Saturday (Silio). In the Thirteen Moon calendar the obscurely named Gregorian months are replaced by names that correspond to a fourth-dimensional cosmology of time. Each Moon also has a totem animal. The traditional names of the days of the week are replaced by galactic names that describe seven primary plasmas-electronically charged particles that activate our magnetic fields. The plasmas and their symbolic seals appear above the days of the week. The Gregorian calendar makes day/date calculations very difficult because the months are of uneven measure so the days and dates of the week vary from month to month and year to year. The Thirteen Moon calendar is truly unique because it is synchronized with the Harmonic Module, the measure of the universal 13:20 timing frequency.

THE HARMONIC MODULE

The basis of the Tzolkin or sacred 260-day count of the Maya, the Harmonic Module is the 13:20 synchronization gauge and permutation table that consists of thirteen sequences of twenty icons or solar seals and twenty sequences of thirteen galactic tones, 1-13. The resulting 260 permutations, combined with the perfect harmony of the Thirteen Moon calendar, give each day a unique quality of tone and icon known as a kin or one NET minute. The two cycles-Thirteen Moons/28 days and the 260-day Harmonic Module-perfectly mesh every fifty-two years to complete one NET year. In one NET year of 18,980 kin, no two days are the same! Each of the units in the Harmonic Module is called a kin, the base unit of synchronic measure. Articulating the Harmonic Module is a pattern of fifty-two Galactic Activation Portals. See if you can find the radial sequence of thirteen sets of four, counting inward from the corners. Notice that the numbers of each set of four equals 28. Thirteen sets x 28 = 364, the number of days in the Thirteen Moon calendar! (See image containing the Harmonic Module on page 170.)

WAVESPELL

The thirteen-unit form constant of fourth-dimensional time is the wavespell. It is important to see the Thirteen Moon calendar in this modular format, Planetary Service Wavespell, for then it makes more sense to speak of the calendar as a synchronometer. The wavespell's form describes the motion of time as a fractal fourth-dimensional cosmology. The numbers 1-13 in the dot bar notation that code the thirteen positions are known as tones. The names of the tones in sequence define the cosmology, which is also evident in the very structure of the wavespell. The thirteen tones give their names to the thirteen Moons. The structure consists of two gates, the Magnetic and the Cosmic, the first and the thirteenth moons/tones, which correspond to the two entrance and exit gates or portals. Complementing the two gates are the two towers, the fifth or Overtone tower and the ninth or Solar tower. The two gates and the two towers, tones 1, 5, 9, and 13, articulate the structure of the wavespell. Between the places of articulation are three sets of chambers. The first set, tones 2-3-4, helps establish the wavespell; the second set, tones 6-7-8, helps extend the wavespell; and the third set, 10-11-12, serves to convert the wavespell. (See plate 2, Planetary Service Wavespell.)

The structure of the wavespell also defines a four-dimensional geometry of time that connects different points of the wavespell over time. Each of these dimensional geometries is known as a pulsar. It is useful to know the pulsars in extending the mind synchronically over different timing sequences. The fourth-dimensional pulsar connects the four points of articulation, 1-5-9-13, or Magnetic, Overtone, Solar, and Cosmic Moon/tones, and is called the fourth-dimensional time pulsar. The first-dimension life pulsar connects the positions 2-6-10, or Lunar-Rhythmic-Planetary Moon/tones. The second-dimensional sense pulsar connects the 3-7-11, or Electric-Resonant-Spectral Moon/tones; and the third-dimensional mind-form pulsar connects the 4-8-12, or Self-existing-Galactic-and -Crystal Moon/tones. Remember, the wavespell accommodates any sequence of kin whose tones correspond to 1-13, and may be either a thirteen-day wavespell cycle, a thirteen-week cycle (one-quarter of an NET day), a thirteen-Moon cycle (one NET day), a thirteen-year cycle (one NET Season), and so on. Once you know the wavespell you have come to know the form in time of the noospheric mind.

THE WAVESPELL'S TONES AND THEIR PULSARS

1.	Magnetic tone of purpose-fourth-dimension	time pulsar
2.	Lunar tone of challenge-first-dimension	life pulsar
3.	Electric tone of service-second-dimension	sense pulsar
4.	Self-existing tone of form-third-dimension	mind-form pulsar
5.	Overtone tone of radiance-fourth-dimension	time pulsar
6.	Rhythmic tone of equality-first-dimension	life pulsar
7.	Resonant tone of attunement-second-dimension	sense pulsar
8.	Galactic tone of integrity-third-dimension	mind-form pulsar
9.	Solar tone of intention-fourth-dimension	time pulsar
10.	Planetary tone of manifestation-first-dimension	life pulsar
11.	Spectral tone of liberation-second-dimension	sense pulsar
12.	Crystal tone of cooperation-third-dimension	mind-form pulsar
13.	Cosmic tone of presence-fourth-dimension	time pulsar

DREAMSPELL

Described as the fourth dimensional tool kit, the Dreamspell also encodes a psycho-mythic cosmology known as the Journey of Timeship Earth 2013. It is this cosmology that makes the Dreamspell a psychoactive tool kit for personally engaging you in the fourth-dimensional synchronic order of time. The fundamental premise for making it psychoactive lies in finding your galactic signature, the color, icon, and tone that code your date of birth. This combination of factors-color, tone, and icon-establishes a mathematical code that allows you to use your galactic signature in mapping increasing orders of synchronicity. There are four colors, thirteen tones,


0–19 Dot-bar Notation
0
5
10
15
1
6
11
16
2
7
12
17
3
8
13
18
4
9
14
19
Yellow Chromatic
Red Chromatic
White Chromatic
Blue Chromatic

The Four Chromatics


Cell One Input
Cell Two Store
Cell Three Process
Cell Four Output
Cell Five Matrix

The Five Time Cells

and twenty icons. The four colors code each of five sets of icons and correspond to the base four-phasic function of the noospheric rainbow brain-red initiates, white refines, blue transforms, and yellow ripens. The icons themselves actually correspond to the mathematical code 0-19.

Colors and Icons with Their Corresponding 0-19 Code Numbers:

Red Family: Dragon (1), Serpent (5), Moon (9), Skywalker (13), and Earth (17)

White Family: Wind (2), World-bridger (6), Dog (10), Wizard (14), and Mirror (18)

Blue Family: Night (3), Hand (7), Monkey (11), Eagle (15), and Storm (19)

Yellow Family: Seed (4), Star (8), Human (12), Warrior (16), and Sun (20 = 0)

The mapping of synchronicity through use of the galactic signature is done through a set of tools: the Galactic Compass, Journey Board, Oracle Board, and Time Atom Cube. The point of engaging the Dreamspell is to learn of the infinite possibilities of fractal synchronic mapping of the events of your life and the lives of your family and friends, as well as current events and human history. The compass and boards describe the radial mathematics of fourth-dimensional time and also provide the means for fully engaging the synchronic order of the noospheric mind. The interactive complex of changing the family and clan relations to which the galactic signature entitles you also provides the basic patterns of social organization in time. The Dreamspell is indispensable for education concerning the radial, fractal nature of fourth-dimensional time and mathematics.

TELEKTONON

Meaning "Earth Spirit Speaking Tube," *Telektonon* is the name of the prophecy of Pacal Votan, and the definition of a complex program for establishing universal telepathy. It should be noted that the tomb of Pacal Votan was discovered in 1952, after 1,260 years, because of a tile tube, the Earth Spirit Speaking Tube, which ran from the top of the pyramid temple, down the secret stairwell, and into the wall of the elaborate tomb beneath the pyramid. The prophecy itself was decoded from the inscriptions and symbols of the elaborately carved sarcophagus lid of the tomb. Essentially defining a period of "Seven Years of Prophecy," (1993-2000), followed by a 13-year Cycle of Creation (2000-2013), the Telektonon is practiced on a daily basis by means of a board and various moving parts.

The purpose of the daily play is to learn how to operate by a set of coordinates that define the nature of telepathic consciousness as the interplay of five circuits that connect the ten planetary orbits (the Asteroid Belt, remnants of the lost fifth planet Maldek, is included as one of these orbits). The key interplanetary connection is between Earth, the third planet, and Uranus, the eighth planet, which creates the third or biotelepathic circuit. The Earth-Uranus circuit constitutes twenty-eight steps and thus corresponds to the 28-day measure of the Thirteen Moon calendar. Between days 7 and 22, one is


Tower Day 28 GAP
Tower Day 23 GAP
Day 13
Day 12
Day 11
Day 10
Day 14
Day 21
Day 20
Day 9
Day 15
Day 22
Day 19
Day 8
Day 16
Day 17
Day 18
Day 7
Tower Day 1 GAP
Tower Day 6 GAP

116 cube days per moon x 13 moons =
208 cube days or 208 kin per year

4 tower days per moon, each tower day =
1 GAP equivalent x - 13 moon =
52 GAP kin, or Loom of Maya

208 + 52 = 260 kin, or one Tzolkin grid
Two sets of teams, two polar Tzolkin grids =
1 psi bank plate = 260 x 2 520 kin or
520 psi chrono units per psi bank plate per year

The Telektonon Grid: Showing Psi Chrono, Loom of Maya, and Cube Journey Correspondences

Tower Day 1 (x 13)

Tower Day 23 (x 13)



GAP = Galactic Activation Portal, 52 of which create the Loom of Maya, or binary triplet configuration of the Harmonic Module (Tzolkin).

The 52 GAPs are the basis of the occult quartet; that is, starting from each corner and moving inward there are thirteen of these sets creating a radial matrix where the tones of each set always equal 28.

Harmonic Module 260 (13 x 20) unit universal standard of measure of fourth-dimensional time

13 x 28 = 364, the number of days in the Thirteen Moon calendar.

Each of these quartets codes the four tower days of the Telektonon every moon.

Tower Day 6 (x 13)

Tower Day 28 (x 13)

Telektonon - Rinri GAPs and Towers with Harmonic Module

able to take the "Warrior's Cube Journey" to uncover knowledge hidden by the Tower of Babel. The sixteen positions of the Cube of the Law (days 7-22) are the heart of the Telektonon play, which also includes a rehearsal of the thirteen baktun history with the intention of "redeeming the Babylon planet" as Timeship Earth 2013.

THE RINRI PROJECT

Described as a "four-year telepathic biosphere-noosphere transition Circumpolar Rainbow Bridge Experiment," the Rinri Project builds on the Telektonon play that establishes the biotelepathic circuit. On this circuit, two towers, days 1 and 6, define a four-day Earth Walk, and two towers, days 23 and 28, define a four-day Heaven Walk. Between the second and the third towers, days 6 and 23, are the sixteen positions of the Cube of the Law, days 7-22. The four towers every Moon correspond to one radial set of four Galactic Activation Portals in the Harmonic Module-thirteen moons x four towers = 52 Galactic Activation Portals (GAPs). Sixteen cube positions each moon x 13 Moons = 208, the remaining number of kin in the Harmonic Module once the 52 GAPs have been subtracted from the 260 units. Since the Harmonic Module is the basis of the psi bank, this formulation provides a way of coordinating the four psi bank plates of the noosphere to the Thirteen Moon calendar year on a daily and annual basis.

Since there are four plates, it takes four years, one year per plate, to open the psi bank. The first opening occurred between 1996-2000. The second opening, 2000-2004, is now occurring and is programmed by a coordination of the twenty-four runes of the Elder Futhark to the twenty-four psi membranes-6 runes per week every Moon x four weeks = 24. Since each psi plate is a mirror symmetry pair of Harmonic Modules, reflecting the North and South magnetic poles of the Earth, the Rinri project is practiced by telepathically interactive teams in the Northern and Southern Hemispheres. The Rainbow Bridge refers to making visible the dynamic of Earth's electromagnetic aura and extending it permanently from pole to pole. This is how the noosphere is visibly manifest.

Rinri is a Japanese word meaning "ethical enlightenment," and its application includes seventeen moral precepts that are studied during the sixteen-day cube journey, the seventeenth corresponding to the tower day 23.

260 POSTULATES OF THE DYNAMICS OF TIME

While the Telektonon is predicated on the fourth-dimensional tool kit, the Dreamspell, the 260 Postulates of the Dynamics of Time elaborate on the nature and theory of the biosphere-noosphere transition by providing a set of twenty systematic thirteen-part logics that describe and define the dynamics of time as the evolution of consciousness. Because there are 260 postulates corresponding to the 13:20 matrix, a postulate can be studied and meditated on each day over a 260-day cycle according to the code number of the daily icon combined with the number of its tone, for example, Red Lunar Dragon, where Dragon is 0-19 code number 1, and Lunar is tone 2, therefore the postulate to study for the day is 1.2. This daily programming, established by the Telektonon practice is how knowledge is reformatted according to the synchronic order. This in itself precipitates the noosphere.

TWENTY TABLETS OF THE LAW OF TIME, SIXTEEN-YEAR CUBE OF THE LAW

The Twenty Tablets can be described as a road map of the fourth dimension. By focusing on a sequence between the years 1997-2013, by fractal analogies, the telepathic engagement encompasses the 26,000-year cycle as well as the coming cycle of the Psychozoic future. The crux of the daily play of the synchronic order is called *cubing the codon.* The point is to telepathically reharmonize the DNA that has been adversely affected by the 12:60 timing frequency. There are sixty-four DNA codons whose six-part binary structure is identical to that of the sixty-four hexagrams of the I Ching when both are written with a simple binary language of broken or unbroken lines. Each of the codons establishes a precise thirteen-stage permutation sequence. 64 x 13 = 832 codon permutations. The sixteen years from 1997 to 2013 also constitute 832 weeks (16 x 52 = 832 = 64 x 13). Therefore, each codon has one-quarter year, thirteen weeks, to run its permutation sequence, one sequence per week. Since each codon consists of six lines, each week the codon is built one line per day for six days, each line adhering to one side of a cube. On the seventh day, the codon is cubed and sealed by one of sixty-four "UR Runes." The UR Runes are the master cosmic runes, each of which governs an entire thirteen-unit codon permutation sequence. The Twenty Tablets also contain much synchronic information for experiencing what is referred to as *fractal time compression,* the expanded mental ability to engage in different planes or levels of time simultaneously. All of this is to establish a mind training for fully engaging the fourth-dimensional synchronic order of reality and time travel.

7:7::7:7 TELEKTONON REVELATION

While the Twenty Tablets of the Cube of the Law synchronize the DNA Codons in all their permutations on a weekly basis over a sixteen-year cycle, the 7:7::7:7 Telektonon Revelation establishes the 28-day cycle as the basis for synchronizing



Three planes create the cube. The six faces of the cube code the six lines of the codon. Cube the codon according to the thirteen tones of creasion

THE THIRTEEN TONES OF CREATION
The thirteen codon permutations operate by principle of binary inverse symmetry. The 1st and 13th, are the base codon, e.g., 61, which triangulate the Inverse 7th = Magnetic-Resonant-Cosmic codon pulsar complemented by five sets of binary inverse pairs.

Tone-weeks 2 and 8, Lunar-Galactic codon axis
Tone-weeks 3 and 9, Electric-Sloar codon axis
Tone-weeks 4 and 10, Self-Existing-Planetary codon axis
Tone-weeks 5 and 11, Overtone-Spectral codon axis
Tone-weeks 6 and 12, Rhythmic-Crystal codon axis

13 TONE - 13 WEEK CODON WAVESPELL
Numbers = codon numbers. See 64 UR Rune and codon keys to the *Books of Universal Life*, inside and back cover, Bi-Phasic Earlier Heaven Arrangement; also Tablet Five, "Musical Score" side.

PLANE OF SPIRIT
x 2 sides = back and front
PLANE OF WILL
x 2 sides = right and left
7TH MYSTIC POINT
Divine Source Telektonon
PLANE OF MIND
x 2 sides = bottom and top
CUBE THREE INNER PLANES SIX FACES
CODON 61 INNER SPACE CUBED
= 1 micro hyperatom
13 per quarter
52 per year
832 = 16 years
SECOND LINE, RIGHT FACE
Build the binary, 2nd day
FOURTH LINE, BACK
Establish the fourth, 4th day
SIXTH LINE, TOP
Complete the sixth, 6th day
RUNE MEDITATED
At center, 7th day
THIRD LINE, LEFT FACE
Create the triplet, 3rd day
FIFTH LINE, FRONT
Sound the fifth, 5th day
FIRST LINE, BOTTOM
Lay the line, 1st day
PLANE OF:
MIND TOP
SPIRIT FRONT
SPIRIT BACK
WILL LEFT
WILL RIGHT
MIND BOTTOM
CODON 61 - INNER SPACE
Showing cube code for reading the master codon

Codon Cube Cosmology
Sounding the Thirteen Tones of Creation

the seven primary plasmas-electronically charged ions-into four aggregates called time atoms. The seven plasmas, which also replace the names of the days of the week, are in two sets of three, with the middle or fourth acting as a catalytic agent. The first three plasmas form a sensory quantum and the last three plasmas form a telepathic quantum. Activation of the plasmas releases radion, a telepathic lubricant; hence, the seven plasmas are also referred to as radial plasmas. The four plasmic aggregates are known as the Analog Time Atom (week 1), the Antipode Time Atom (week 2), the Occult Time Atom (week 3), and the Unified Field Time Atom, (week 4). Like the Twenty Tablets, the 7:7::7:7 Telektonon Revelation also involves principles of fractal time compression where each day during the first week is the equivalent of 260 moons or twenty years; the following two weeks, each day is thirteen

The Seven Seals, Seven Radial Plasmas



moons or one year; and the last week each day is one moon. Played on a board with cards containing affirmations from the Buddhist sage, Padmasambhava, the object of the 7:7::7:7 is to place the time atoms within the crystal octahedron at the center of the Earth so that each Moon a master time molecule is telepathically placed at the center of the Earth per one NET hour. In this way, Noospheric Earth Time is activated, the telepathic mind is engaged with the phenomenal reality represented by the plasmas, and the rainbow brain of the noosphere is hastened into everyday presence.

The seven daily plasmas constituting one thirteen-moon week, or one NET quarter hour are:

Dali (Sunday)-thermic charge

Seli (Monday)-luminic charge

Gamma (Tuesday)-luminic-thermic charge (these first three create one sensory quantum)

Kali (Wednesday)-luminic-thermic, thermic-luminic catalytic agent

Alpha (Thursday)-double-extended electron at the South Pole

Limi (Friday)-mental electron at the North Pole

Silio (Saturday)-mental electron-neutron at the center of the Earth (these last three create one telepathic quantum)

Part II. The Peace Plan: Establishing the *Pax Cultura, Pax Biospherica*

From the time of the formation, or rather, the calling into existence of the World Thirteen Moon Calendar Change Peace Movement, there had to be a *World Thirteen Moon Calendar Change Peace Plan.* The original of this Plan was submitted to the United Nations in 1995 for its fiftieth anniversary. The crux of the Peace Plan is that to change the world standard calendar is the opportunity for humanity to stop in its tracks and redirect itself. By stopping in its tracks to change its timing frequency, humanity can also use the opportunity to call a universal cease-fire and declare an emergency peace worldwide. Only in this way can the new time be experienced and fully engaged.

At the First Planetary Congress of Biospheric Rights (1996), this Peace Plan was extended to include the establishment of a new human covenant that would restore to humanity its intrinsic biospheric rights, the same as enjoyed by the rest oflife in the biosphere: free land, clean air, clean water. The premise of the Biospheric Covenant is that humanity is first and foremost a member of the biosphere, and not of any artificially constituted nation-state. The Biospheric Congress also mandated the revival of the Banner of Peace and Roerich Peace Pact (1935) as one of the emblems to be used to identify the biosphere as a zone of peace.

The World Congress on the Law of Time and Judgment Day Tribunal (1997) extended the Biospheric Congress to include an indictment of the Gregorian calendar as a crime against the biosphere-"the crime of the millennium"-and the establishment of the Law of Time, inclusive of the Twenty Tablets, as the new dispensation of knowledge awarded in compensation to humanity, based on the synchronic veracity of the Thirteen Moon Calendar Change Peace Plan.

By 1999, the World Summit on Peace and Time provided the Declaration of Calendar Reform and a set of People's Resolutions, which were presented to the United Nations and the Vatican. The Resolutions define a seven-part educational program, which, like the Biospheric Covenant, envisions a radical reorganization of human society.

The purpose of these documents and declarations is for the creation of a state of universal unconditional peace so that human society can be rebuilt as a harmonic unity in phase with the biosphere as a whole. The result of the Thirteen Moon Calendar Change Peace Plan would be the creation of a new order oflife on Earth-the *Pax Cultura, Pax Biospherica.*

▼

9

The Advent of the Noosphere

A Prayer and a Vision

IT IS MORNING once again, or, rather, it is predawn. It is still the first watch of the day. Outside there is a full moon. On the Gregorian calendar it is November 1, 2001, All Soul's Day, the sequel to Halloween, the day of honoring the dead. In another two weeks it will be the New Moon of Ramadan, Islamic lunar year A.H. 1422. On the Thirteen Moon synchronometer itis now the fifteenth day of the Self-existing Owl Moon, the moon of form, the moon to define, measure, and ask the question, "What form will my service take?" Well, my service will be to complete this book and prepare it for the world, for now it is the time of the advent of the noosphere, the reality of which Vernadsky said must be communicated to the world's politicians and statesmen. They didn't listen then. WIll they listen now? And on the 260-kin synchronization gauge it is kin 42, White Electric WInd. The WInd "communicates spirit," the Electric tone "activates service." WInd is the second of twenty solar seals that code each day in the synchronic order.

By its mathematical relationships to the other nineteen solar seals, the solar seal of the daily kin possesses a unique five-part oracle. In today's oracle the WInd is guided by the World-bridger, who brings the power of death. In the psi bank, the matching psi chrono unit for today, the fifteenth day of the Self-existing Owl Moon, is kin 66, Magnetic World-bridger, the first tone in the 13-kin wavespell of the World-bridger, which means today is very strongly penetrated by the power of death. What is death to the noosphere? An inevitable and unavoidable event, a critical and


Dragon
Nurtures
Birth
Serpent
Survives
Life-Force
Moon
Purifies
Universal Water
Skywalker
Explores
Space
Earth
Evolves
Navigation
Wind
Communicates
Spirit
World-bridger
Equalizes
Death
Dog
Loves
Heart
Wizard
Enchants
Timelessness
Mirror
Reflects
Endlessness
Night
Dreams
Abundance
Hand
Knows
Accomplishment
Monkey
Plays
Magic
Eagle
Creates
Vision
Storm
Catalyzes
Self-Generation
Seed
Targets
Flowering
Star
Beautifies
Elegance
Human
Influences
Free Will
Warrior
Questions
Fearlessness
Sun
Enlightens
Universal Fire

The 20 Solar Seals
Names, Actions, and Powers

equalizing stage in the recycling of biomass, a furtherance of the biogenic migration of atoms, the creation of biospheric compost, a release of consciousness back into the noosphere, an opportunity to consider the value of life. But to the ordinary mind of the artificial technosphere, death is the ultimate object of fear, and the fear of death is the chief object of manipulation by those who generate terror. It is of note that by his date of birth, March 10,1957, the galactic signature of Osama Bin Laden is White Solar World-bridger, kin 126, while for this, his forty-fourth year, his birthday was coded by kin 66, White Magnetic World-bridger, both signatures bearing the destiny seal of the power of death. This is an example of how the synchronic order is "read" on a daily basis.

It is a mistake to think that the terror is just the malevolent intention of a single human being. The terror is co-extensive with the technosphere. In fact, the technosphere is the age of terror. The terror was generated at Hiroshima, and repeated at Nagasaki fifty-six years ago. And the terror was compounded by the original perpe-

Daily Oracle, Dali 15
Self-Existing Owl Moon, 9 Seed Year
(Gregorian: November 1, 2001)


Guide
Antipode
Destiny
Analog
Occult
Kin 42
World-bridger Death
Human Free Will
Wind Spirit
Earth Navigation
Storm Self-Generation
Kin 66
World-bridger Death
Warrior Intelligence
World-bridger Death
Skywalker Space/Prophecy
Eagle Vision
Kin 126
Wind Spirit
Warrior Intelligence
World-bridger Death
Skywalker Space/Prophecy
Eagle Vision

Oracle for March 10, 2001,
Osama Bin Laden's 44th birthday

Oracle for March 10, 1957,
Osama Bin Laden's date of birth

Daily Oracle Matrix

trators of that terror many thousands of times over in the creation and stockpiling of weapons of mass destruction, an act soon imitated by the then archrival, the Soviet Union, and by other nation-states, namely, the United Kingdom, France, and China. Those called the "terrorists" today have nothing to compare to the stockpiles of these weapons by these five nation-states who constitute the permanent members of the United Nations Security Council-the "nuclear club." That is who rules the world today, the official possessors of the weapons of mass destruction, who jealously guard their secrets. If this is the ultimate ruling body of the planet, and the reason why they are the ruling body is their possession of these instruments of death, then why should anyone be surprised at the existence of "terrorists" in the rest of the world? And why, we may ask again, are these terrorists mostly, it would seem, from the Islamic world? In addition to the nuclear arsenals, there are the biological and chemical weapons of mass destruction. Those who live by the manufacture of terror must surely die by their own means. If other nations have developed the same systems of terror, it is only in self-defense or in imitation of the masters of terror.

Everyday for four weeks now, I have been waking up at this time to continue work on this text, *Time and the Technosphere*.I had at first thought that the book could be complete with eight chapters. People don't have time to read, and the topic warrants as brief and pithy an explanation as possible. After all, it is really a time of reflection-and then action. The masters of terror have cloaked themselves as the protectors of civilization and as the moral crusaders who will rid the world of evil. Yet what is civilization today but the resource-consuming cancer of the biosphere? Is this what is being protected-the right to promote the disease upon the biosphere? The terrorists who attacked the Twin Towers and the Pentagon clearly knew the symbolic and actual value of their targets. They also undoubtedly knew the depths of the death-fear of the superpower masters of terror, whose reaction would most likely foment a global war. But in such a war, who would win? In this regard, from the noospheric perspective, the Inevitable Event was the technocide-death by technospheric means-of the technosphere itself. The technosphere was created by and thrived on means of terror, and the means of massive terror as well as the economic imperialism perpetrated by the superpower managers of the technosphere could only have produced a reaction against itself known as terrorism. The end result is collective suicide. There are no flags in the blood of the dead, nor is there any evident religious belief. There is only human biomass ultimately indistinguishable and anonymous to the biosphere.

Eight chapters were needed in order to complete the information about the biosphere, technosphere, noosphere, and the Law of Time. Maybe a new spirit of the biosphere will arise from the considerations of my book. Maybe the noosphere will spark in others the need to allow the biosphere to reclaim us from the technosphere. Anyone who says this is "turning back the clock" is only betraying their immersion and unexamined belief in the reality of artificial mechanical time. Yes, eight chapters were necessary to unfold this analysis and solution. But I knew there had to be a ninth chapter for the testament to be complete. For this is a living testament, and if anything has been learned by living according to the synchronic order of fourth-dimensional time, it is the renewed power of number itself. There is a power and meaning to number understood as a universal, self-existing mental construct. The synchronic order is constructed of number. And as Pythagoras perceived, number is a kind of spiritual entity that can only be aroused by an act of meditative contemplation. Each whole number bears its own resonance. You can feel this in the contemplation of the difference between even and odd numbers.

The resonance of 8, an even number, is harmonic order and balance, geometrically evident in the octagon or the octahedron. But the resonance of 9, an odd number, is quite different. Nine months to give birth, three times three, a rhythmic triplicity-that is nine. The Germanic god-hero Odin, or Votan, spent nine nights hanging from a tree in order to gain knowledge of the mysteries of woman. When the tomb of Pacal Votan was opened on June 15, 1952, it revealed a large vaulted chamber beneath the pyramid of the inscriptions in Palenque, Chiapas, Mexico. Entering the tomb, in the center of which is the famous sarcophagus, one sees on the walls the beautifully sculpted figures of nine personages. Today these sculptures have almost completely worn away. But originally, these low-relief sculptures modeled out of limestone, depicted with great elegance, a series of figures commonly known as the Nine Lords of Night, or the Nine Lords of Time. Are the Nine Lords of Time, the Lords of Night who guard Pacal Votan in his tomb, the same as the nine nights of Odin/Votan? And who was Pacal Votan? With what mythic resonance are we dealing?



Nine Lords of Time Begin to Gather for a Council of the Earth

A Mayan seer, a sage-king of the seventh century of the Christian era, had deliberately created a mysterious tomb for himself, only to have it hidden, buried beneath a pyramid temple, but a tomb intended to be opened more than twelve centuries later, in the seventh year of the time of the terror, the time of the technosphere. How ingenious, how uncanny, that it would have been unknown for 1,260 years-a number also known in the thirteenth chapter of the Book of Revelations as the number of days of exile of the woman clothed with the sun, her feet on the moon, and twelve stars around her head. What does this allegory mean? Is it not the same as the exile of the human soul in the deadening world of 12:60 materialism? Sixty years remained from the opening of that mysterious tomb to the closing of the cycle of history, the omega point of 2012. How could the timing of the opening of the tomb have occurred so precisely-1,260 years from dedication to discovery, 1,320 years from its dedication to the closing of the cycle? How could those years be such a perfect reflection of the artificial 12:60 and the natural 13:20 timing frequencies? How could a Mayan sage in Central America so long ago be able to see, it would seem, into our future?

When we study the globe and consider things synchronically from the perspective of the noosphere, we find some interesting correspondences. Pacal Votan lived in the tenth baktun cycle, between the Christian years 603-683, on the opposite side of the world but at almost the same latitude as Mecca, and just after the time of Muhammad, 570-632. Today the religion that God commanded Muhammad to found, Islam, is at the center of the terrorist storm, while the prophecy of Pacal Votan and of the Mayan calendar in general has placed the end point of history at 2012, a mere eleven years after the Inevitable Event that placed Islam at dead center of the world mind. How could this be, the religion of the prophet Muhammad and the prophetic timing of the Maya so close at hand? Is this some revelation of the Nine Lords of Time, or of God speaking through them-and who are the Nine Lords of Time? Are they destined to return? Could it be that the Nine Lords of Time, like some higher dimensional Lords of the Ring, are a manifestation of time to be released, one by one, in an annual sequence during the last nine years of the Great Cycle, 2004-2013?

These Nine Lords of Time are known in Mayan as the Bolontiku; their counterparts are the Oxlahuntiku-the nine lords and the thirteen lords, respectively. The nine lords govern the underworld, the time of the third dimension, which is why they are depicted in descent to the sarcophagus of Pacal Votan, while the thirteen lords govern the heavenly realms. The nine govern the nine vigesimal orders of number, while the thirteen govern the form of time. The dedication of the tomb of Pacal Votan in A.D.692 corresponded to the Long Count baktun date of9.13.0.0.0.

The nine and the thirteen lords-Bolontiku and Oxlahuntiku-are present in the very numbers of the dedication date. And the nine and the thirteen also governed the prophecy of Quetzalcoatl, of Thirteen Heavens of decreasing choice and Nine Hells of increasing doom. This prophecy refers to the sequence of twenty-two 52-year cycles that began in A.D. 843 and ended in A.D. 1987. Six years later, in 1993, during the first year of the 260th and final katun cycle of history, I began to decode the prophecy ofPacal Votan, some forty-one years after the tomb had been opened.

Telektonon, the Prophecy of Pacal Votan, was meant to be decoded precisely and only at the moment of its absolute usefulness, kin 144: Yellow Magnetic Seed, July 26, 1993. This moment defined the Seven Years of Prophecy, 1993-2000. It also established the validity of the Dreamspell or WIzard's Count as the reformulated Year-Bearer Count of the Chilam Balam, the jaguar priests or night seers. That is, the Telektonon Prophecy could only have been triggered when kin 144 occurred as the Year Bearer, Yellow Magnetic Seed, kin 144, correlated to the Gregorian date of July 26, 1993.

The precise revelation of this prophecy on kin 144, July 26, 1993, was dependent on and could only have occurred because a prophetic count, the WIzard's Count, derived from the prophetic tradition of the Chilam Balam, had already been established. This "count" provided the basis of *The Mayan Factor* and was woven into the conclusion of the Prophecy of the Thirteen Heavens and Nine Hells, Harmonic Convergence, August 16-17, 1987. And the precise number of kin 144, the revelation date of the prophecy of Pacal Votan was meant to accord with the Book of Revelations number of the elect, 144,000 (Revelations 7:4). In fact, that very day I discovered that the number 144 transliterated from the vigesimal count into Arabic numbers is written 7.4, which is the same as the chapter and verse number where the 144,000 are first mentioned in the Book of Revelations (7 = 140, or 7 x 20, plus 4 units = 7.4). More uncanny stuff-but not so to the noosphere, the Earth's mind of time. In the noosphere everything is woven of number, and number is intrinsically synchronizing, which is why numerology has held such a fascination for the human mind throughout history.

When I first began to decode this "final prophecy of the Maya," or Telektonon, a prophecy that commands the return to natural time through the Thirteen *Moon!* 28-Day calendar, I was stunned and not a little frightened. I had already taken many steps to remove myself from mainstream society and conventional life. But now I was dealing with a genuine prophecy, and I was to be its messenger. This was not my invention. The world is filled with enough madmen and lunatics spouting their particular visions. How could I ever make the world understand that this vision, this prophecy, was real, that it was the fulfillment of a Mayan who lived and died thirteen

•• ▬ Vinal position, one dot = 20 kin, 7 = 140 (7 x 20)

•••• Kin position, one dot = 1 kin, 4 = 4

Written 7.4 = 144 (140 + 4)

7.4 = 144

centuries ago, and that his tomb was the vehicle of this prophecy, a prophecy meant precisely for this moment in time-the biosphere-noosphere transition?

I returned to the texts of the Chilam Balam, whose prophetic stream includes day prophecies, year prophecies, katun (twenty year), and *ahau* (260-year) cycle prophecies, prophecies of Quetzalcoatl, and finally the special prophecies of the mysterious Antonio Martinez and the coming religion of the Hunab Ku, "One Giver of Movement and Measure." I realized that the meaning and fulfillment of this entire prophetic stream was crystallized in the Harmonic Convergence and its 26-year aftermath. Chilam Balam, the jaguar priests, are the wizards of time, inspired by the guidance of the Bolontiku, the Nine Lords of Time, the Lords of Number. By command of the Supreme One (Hunab Ku), the wizards are directed to establish clear paths of rekindled knowledge. The ancient Maya prophesied their own destruction. Therefore, within the prophecies of the Chilam Balam they laid the seeds of their reconstruction-but not simply as Maya. The reconstruction had to be planetary, for their destruction in the sixteenth century was also an act of planetary consequence-the plunging of the entire world into the prison of artificial, mechanized time. The fulfillment of the prophecies along with the new dispensation of time had to occur before the end of the cycle, 2012.

For this reason, the master synchronic architect of the Mayan prophets, Pacal Votan, prepared the way with the discovery of his tomb in 1952. This phenomenal act of prophetic release meant that now the messenger of his prophecy of time had to be summoned to his task. This was to be my role and responsibility-one that I accepted, for I saw no other choice. The course of my life from the moment I had experienced an illumination atop the Pyramid of the Sun at Teotihuacan in 1953, to that moment forty years later, in 1993, when I first perceived that the meaning of the prophecy Telektonon was a single trajectory. The noosphere had found another chip. After all, if the noosphere is the mind of time on Earth, prophecy is just another way of radializing time, of bringing it around from one point in a cyclic motion to another. My preparation had been going on for a while.

Once I had received knowledge of the prophecy of the Thirteen Heavens and Nine Hells from Tony Shearer back around 1970, I prepared myself by study and meditation for the moment of the Harmonic Convergence. It may be asked: If the Harmonic Convergence concluded the cycle of the Nine Hells, then why are we experiencing the apocalyptic events of Hell on Earth now, some fourteen years later? What was the actual meaning of the Harmonic Convergence, and what does it mean for us today?

First of all, the Harmonic Convergence refers to the entire 26-year cycle from White Galactic WIzard to Yellow Galactic Seed, 1987-2013. The conclusion of the Ninth Hell refers to the release of humanity into the 26-year time zone of free will, choice, and decision in preparation for the completion of the cycle, omega point 2012, and the Galactic Synchronization, 2013. The full and true Harmonic Convergence will not be complete until the Earth itself becomes the Galactic Seed, 2013. If the twenty-six years are the free will zone of choice and decision, what are we to choose and decide? The choice is, as I was quoted in the *TVtlllStreet Journal* in 1987, " between a 'new age' and all-out destruction." The decision is to accept the knowledge of the error in time (12:60) and the choice is to return to natural time (13:20) by means of the Thirteen Moon!28-Day calendar. This the prophecy ofPacal Votan fully affirms.

In principle, the Harmonic Convergence refers to the converging of all aspects of reality in a great, all-unifying harmony. The initial moment of the Harmonic Convergence that witnessed hundreds of thousands of humans congregated at sacred sites worldwide at the dawn of August 16, 1987, Blue Electric Eagle, was a pure prophetic enactment of humanity being harmonically converged with the natural order of time. This visionary moment demonstrated that, indeed, Harmonic Convergence was possible. The wave of unconscious energy released through the collective psyche of the species as a result of this moment of prophetic purity reached a climax with the fall of the Berlin Wall and the end of the Cold War.

Early 1990, the role of the Harmonic Convergence in this process was echoed in the mass media as the question, "Did the Harmonic Convergence bring the world closer to peace?"l Before the question could be answered, the next phase of the prophetic end time began to unfold. Rather than determine how to make the choice to enter a genuine new age, the human race defaulted to an absolute materialism. It was this collective turn taken by the planetary leadership, now known as the G-7, that engendered the apocalypse we are now witnessing. In this turn, the Harmonic Convergence was forgotten, deleted as it were from the official public texts of contemporary history. The stage was thus set for the next revelation, the Telektonon of Pacal Votan.

In distinguishing the Seven Years of Prophecy, 1993-2000, Magnetic Seed-Resonant WIzard years, the Telektonon of Pacal Votan makes an absolutely clear analysis of the human condition at this time: unless the human race forsakes the false time governed by the instruments of the Gregorian calendar and the mechanical clock by the year 2000, then it will face its own destruction, biospheric collapse, and Hell on Earth. But ifby the year 2000 it can make the decision to reject the calendar of the false

12:60 time and adopt the perfect instrument of the natural 13:20 time, the Thirteen Moon!28-Day calendar, then humanity will have been able to make the choice of entering a new age. For the new age, so longed for, is actually only realizable as a new time. A new time can only come about by the rejection of the instrument that holds in place the hallucination of the old time, replacing it instead with an instrument of such perfect harmony that it has no history, but is truly post-historical.

For this, the messengers of time, myself and my wife, embarked on a course of being galactic gypsies, with no visible means of support, in order to warn the world of the meaning of the time and to offer to the world the opportunity of changing its course by changing its calendar. When the year 2000 rolled around, humanity remained unmoved. The Gregorian calendar, the Vatican, and the G-7 appeared to be as strong as ever. The prophecy did not fail, but humanity did fail to heed the message regarding artificial and natural time. In this process, as "messengers" my wife and I were only playing out an archetypal role. So beginning with the Blue Galactic Storm year, July 26,2000, thirteen years after the White Galactic WIzard year, humanity was placed in judgment. This is merely a matter of natural karmic law.

The four-year cycle, 2000-2004, became known as the prophetic cycle of the Harrowing of Hell. Just as Jesus was crucified and then experienced the Harrowing of Hell before his resurrection, so too humanity has been crucified on the technospheric cross of false time, and is now in the Harrowing of Hell awaiting the resurrection in natural time. For having failed to take seriously all its messengers and all its prophets of all times, humanity was now to pass en masse through hell. Since the Galactic Storm year, 2000-2001, completed a Seed-Storm Year bundle begun in the fifth year of prophecy (1997-1998), the 2000-2001 Blue Galactic Storm year was the year of evaluation. The full judgment was withheld until the Solar Seed Year, 2001-2002.

The Solar Seed year is the second year of the Harrowing of Hell, but the first year of the next four-year Seed-Storm Year bundle. The first half of the Yellow Solar Seed occurs during the second half of the first official year of the third millennium, 2001. The moment was now ripe for the Inevitable Event, for it was also the same Gregorian calendar year as 1945 and 1973. In the Telektonon Prophecy, verse 120, section 19, it is declared, "When the Lunar Moon has overflowed its banks, the G-7 will be no more." So it was on the twentieth day of the Lunar Moon (Blue Self-existing Monkey, galactic signature of Karl Marx), that the Tower of Babel, the World Trade Center, was struck a fatal blow, while the Pentagon, magical structure of the priests of the Dark Lords of Matter, built in "Hell's Bottom," Arlington, Virginia, during the Ninth Hell cycle, was mortally penetrated.

It is still the time of the Harmonic Convergence. The Harrowing of Hell represents the last cycle of respite for humanity. By July 26,2004, Blue Crystal Storm, humanity must make the "choice between a 'new age' and all-out destruction" when it will have the last opportunity to make the decision of rejecting the old time and calendar and replacing it altogether with the instrument of perfect harmony, the Thirteen Moon!28-Day synchronometer. Only such a harmonic organizing principle, universally accepted and applied, can ensure a time of harmony and the fulfillment of the Harmonic Convergence.

Is it possible that within the noosphere the Harmonic Convergence is awaiting its next climax on the Day Out of Time and the Thirteen Moon Synchronization date of the year 2004, that is, on Gregorian July 25 and 26, 2004? One reads through the *Journal of Calendar Reform* and the many texts and arguments for calendar reform that were put forth in the 1930s and feels the missed opportunity. Even Gandhi was in favor of a new universal timing standard as a principle means of unifying humanity in peace. Did World War II occur because the League of Nations failed to enact the calendar reform on January 1, 1933, as it had fully proposed? The League of Nations had promoted calendar reform as one of its major agendas since the 1920s. This world organization failed at calendar reform and at preventing World War II. Who or what prevented that reform from happening, and why?

Let us look at the matter again. In order to remain constant, any perpetual calendar ordered by the seven-day week requires the principle of a null day, a Day Out of Time that is no day of the week at all. This was a feature of the preferred Thirteen Moon!28-Day calendar proposed by the International Chamber of Commerce, as well as the other modified calendars of twelve months. Reading through archives and literature, pro and con, it is clear that what defeated the calendar reform was the conservative, Vatican-inspired objection to the null day, the Day Out of Time. To observe such a day, which is no day of the week at all, it was argued, would break the weekly succession of days set in motion by God at the beginning of creation-such a break would plunge the world into barbarism, chaos, and war. "The adoption of the weekly cycle was a triumph of Christianity to the detriment of paganism. The cult of Christianity is inextricably connected to the week whose origin reaches to the dawn of history."[2] Therefore, it was contended, to interrupt this weekly succession would destroy Christianity itself. As a result of such propaganda, the League of Nations faltered, no calendar reform occurred at all, and the world was plunged into war-a war that ended with the beginning of the age of terror. This terror is now running its course, like a fever sweeping through the biosphere. WIll it be possible to consider again what the League of Nations faltered on and what the United Nations simply chose to ignore?

Who really lost out when the calendar reform issue was tabled in 1956 at the United Nations? It was not God who invented the week as we know it, but more likely the Babylonians. Behind the week is the mystery of the whole number seven, recalled in the Epic of Gilgamesh as the seven wise men of Uruk. But the Babylonians clothed the seven-day cycle in the raiment of the sun, moon, and five principle planets-Mercury, Venus, Mars, Jupiter, and Saturn-to which the days of the week have no actual relation. Seen in this way, the seven-day week was intended to be a means on Earth for reenacting some remote mythic reality related to these seven heavenly bodies. What was that mythic reality, on what hidden knowledge is the count of the seven-day week presumed? Borrowing from Babylon, the ancient Hebrews incorporated the seven-day week into their purely lunar calendar. And it was thus from the Hebrews that the seven-day week entered the Julian and then the Gregorian calendars. It was not, however, the Romans who adopted the week, but the Christian successor to the Roman empire, the Church of Rome. What truly was the origin of the week? And what relation or meaning does it have in the first place? Even to F. H. Colson, a Christian scholar writing as late as 1926, the seven-day cycle is described as "that intruder the week, consisting indeed of a fixed number of days, but paying no regard to months or years."3

With its fixed number of days, the week makes sense only in a system of time reckoning that is synchronic rather than astronomical in nature. To those whose minds are set on the synodic lunation cycle as the absolute standard, as does the Gregorian calendar, the week is what ensures the greatest disorder in the calendar-and yet it is defended to the death. The week gains its power from the whole number 7, and not from the jumble of names in which the week is clothed. The seven-day cycle is the closest whole number that corresponds to the four phases of the moon, which, as whole numbers, are also seven days each. In fact, the fixed 7-day cycle only makes sense within the context of the Thirteen Moon calendar with its 28-day cycles divisible by four and seven, creating the annual cycle of fifty-two perfect weeks-plus the Day Out of Time, ensuring a perpetual harmony.

Was the Babylonian naming of these days-with only one name a reference to the moon-meant to be a cover-up of some earlier knowledge, a knowledge both more purely lunar and harmonic, such as the Thirteen Moon calendar? Is all of history, then, just based on a cover-up of harmonic time? What would really happen if there were a Day Out of Time, no day of the week or month at all? Would old belief systems dissolve? Would there be a psychic release, a sense of freedom? Since 1993, sixty years after the failure of the League of Nations to enact calendar reform, the Thirteen Moon Calendar Change Peace Movement has made certain that the

Day Out of Time is the day for forgiveness of debts, of release into timelessness, and for experiencing the full meaning of time is art. This day is now annually celebrated worldwide by increasing numbers of humans. All the while, the Gregorian world has arrogantly plunged blindly forward, locked into its mechanistically chaotic timing sensibility, only to receive the mortal wound of the Inevitable Event, causing it to fall through the seams of its own making, the technosphere. A Day Out of Time, it seems, might be a relief to a world now consumed by chaos, barbarism, and war.

> He sends down from the sky water for your drink and to grow trees for your benefit. With it He grows for you crops, olives, date palms, grapes, and all kinds of fruits. This is sufficient proof for people who think. And He commits, in your service, the night and the day, as well as the sun and the moon. Also, the stars are committed by His command. These are sufficient proofs for people who understand. (Quran, 16:10-12)

Yes, the biosphere is a set of proofs for people who understand, an immense order that reflects and transforms the cosmos through the very process of life on Earth. Who are the people who understand, and where are those people today? Who will speak for the biosphere? Who will take the message of the advent of the noosphere to the statesmen and the politicians that they may take heed and note that what is occurring is not really in their control at all, but is the climax of a phenomenal process known as biogeochemical combustion? And who will declare that this climax will inevitably shake all the towers to their foundations and level the mountains of industry to a flat plain from which the noosphere will manifest as the equality of telepathy for all?

This book, and this ninth chapter in particular, is like a long meditation, a vision, inspired by the dark tragedy of the Inevitable Event. As a vision, these thoughts are both those of one solitary individual, albeit a noospheric chip, and the continuation of the vision of that ancient seer, Pacal Votan. Could it be that Pacal Votan in his time knowledge rehearsed all these words, these thoughts, this entire vision itself? On the sarcophagus lid of Pacal Votan is a cross, not the cross of death as in Christianity, but the cross of life, a tree, a cosmic tree. Across that tree is a serpentine band with two dragonlike heads, one at each end. This band represents the galaxy. The head at each end represents the galactic vision that sees equally into the past and the future. Sometimes this is called the *zuvuya,* the reflex of cosmic memory. The entire galaxy, the Milky Way, is this reflex of cosmic memory. What if all of humanity is meant to be opened into this cosmic memory? This is what is meant by the advent of the noosphere, the mind of time on Earth, the mental envelope of planetary consciousness arising from the grave crisis of the biosphere through which we are now passing at this very moment.

Because we are now defining the noosphere does not mean that the noosphere was not known to those ancient Mayan time scientists like Pacal Votan, especially if the noosphere is defined as the mind of time on Earth. To such time scientists a NET year would be no time at all, or rather, it would be but a single, fifty-two solar orbit rehearsal of life. How many such rehearsals would be necessary before something was finally learned? The Prophecy of Thirteen Heavens and Nine Hells, for instance, was actually just the passage of twenty-two NET years. Is this how long was needed to see if the human race would learn anything? And if Pacal Votan and Muhammad were around today, what would they think and do?

Knowing the nature of the synchronic order of time, someone like Pacal Votan, obviously one of the most singular of all personalities of the Mayan world, would have possessed a consciousness like the two-headed galactic band, the consciousness of galactic memory. In the zuvuya of galactic consciousness, peering into the deep past is peering at the present from the future. This is possible in the radial time of the fourth dimension freed from the strict linear construct of past-and-future-time. From some higher state of mind, from a mind and consciousness identified completely with the galaxy, this has all been foreseen, this has all been written in a book. Now we who are in this present state of end-time consciousness are being asked to self-reflect. We are being asked if we can manage to hold the noospheric lens steady enough to see that the technosphere had to end, and that the technosphere could only end by the means by which it maintained all of the biosphere in its control, by terror itself.

Yes, we are all a bit like the frog at the bottom of the well whose vision and perception of the universe is circumscribed by what the opening of the well allows it to see. The well is the technosphere, both as a planetary apparatus and as a belief system. On the other side of that well is a vast world that we have actually never seen. This vast world is the noosphere and beyond. And what is beyond? Many of the traditional peoples say that we originally came from the stars. If we came from the stars, are the star people still out there? And what do the star people think of all that is happening on Earth today? And what do they think of their lost star children, many of whom now believe it is childish to think that we came from the stars? And if there are star people still out there, wouldn't they be too sophisticated to think they could get anywhere in a rocket ship, or even a UFO, subject to the en tropic degradation of the material plane?

No, they wouldn't rely on such primitive technology, but would be in tune, as is the rest of the universe, with the universal frequency of synchronization and the capacity of time to travel at an infinitely instantaneous rate of transmission. This being so, we could receive telepathic messages from the star people-if we were ready for it and knew precisely why, when, and how such communication occurs. In fact, as we have said earlier, the noosphere is the region on Earth for the receipt and transmission of messages of cosmic consciousness. This being so, the future of human evolution, of *Homo noosphericus,* would be nothing less than to become a medium of cosmic consciousness, adapting to the expanded measure of Noospheric Earth Time, traveling back to the stars but through the superior knowledge of the actual laws of time.

In writing this book, I have only a sense of duty, of responsibility to expand the vision of my fellow earthlings from the technosphere to the noosphere. In the Law of Time there are no arbitrary distinctions between reason and art, science and prophecy. The universe really is a giant radio transmitter. This book is as much an exposition of matters generally not thought about, as it is a personal testament and vision. In that regard this text is a portion of a broadcast transduced and received by me functioning as a noospheric chip, on behalf of the biosphere-noosphere transition.

In the tomb lid ofPacal Votan are impressed all the frequencies of this broadcast transmission called *Time and the Technosphere.* I know that Pacal Votan took an earthly form for just this purpose. He left his body in that tomb, a jade mask being the actual impression of his face. According to Chinese and ancient Mexican tradition, jade is the stone of immortality. Was Pacal Votan an immortal? Where did his consciousness and spirit go once his body was placed in the sarcophagus? Why did he leave the Telektonon, the Earth Spirit Speaking Tube, running from the tomb to the temple floor at the top of the Pyramid of the Inscriptions? Knowing the frequency of the synchronic order governing the psi bank of the mental envelope of the Earth, did he place his thoughts in the noosphere to be released at the precise moments of the opening of his tomb and the decoding of his prophecy? And then where did he go?

Beginning in 1980 I became conscious that, from time to time, I had been receiving telepathic transmissions. I soon identified these transmissions as coming from the star Arcturus. In *Earth Ascending,* originally written in 1983, the nature and program of the psi bank, the control panel and regulating mechanism of the noosphere, became known to me. This was followed by *The Mayan Factor,* and then the decoding of the Law of Time. At the moment when I had just finished writing *The Mayan Factor* in 1986, I received the inspiration for what is called the planet holon, the twenty-part structure accommodating the program of the twenty solar seals. When I received this image it was known to me as the program of the Arcturus Protectorate. As I understood it, the Arcturus Protectorate was established by the "star people" as a kind of protective time shield around the Earth. By means of the activation of this time shield, the star people would know that some of the earthlings were waking up to time and beginning the conscious activation of the noosphere. This is exactly what came about through the *Dreamspell,* beginning in 1990.

The *Dreamspell* is such a radical break from the past, and such a pure statement of the history-less fourth-dimensional future, that in order to comprehend it, in 1992 I wrote two other books, one called the *Arcturus Probe: Tales and Reports of an Ongoing Investigation* and the other *The Call of Pacal Votan: Time is the Fourth Dimension.* Some people will say that the *Arcturus Probe* is an exaggerated fantasy, yet I cannot deny what a purely telepathic process it was to write that book, which fills in many points of the psychomythic cosmology of *Dreamspell: The Journey of Timeship Earth 2013. The Call of Pacal Votan* was originally titled *A Treatise on Time Viewed from its Own Dimension,* and is a purely scientific description of the mathematical codes of the Dreamspell in relation to the biosphere-noosphere transition. The one text purely imaginal, the other purely rational, yet both were two sides of the same coin, a rendering of the Law of Time in its cosmological and mathematical comprehensiveness. Then came the even more abrupt break with my conventional past, the Telektonon Prophecy of Pacal Votan.

I bring up all of these personal details because people often ask where it all came from and where I got my ideas. But more importantly, I bring them up because, as I have been indicating, all of this was foreseen and known by a seer in another time, in another world-Pacal Votan. And this process of one person hiding a prophecy and another person in another time finding that prophecy, this is also a further revelation of how the noosphere functions. The French mathematician and philosopher Charles Henry (1859-1926) declared, "As the individual becomes more collective, the collective becomes more individual."4 As individuals, we humans are meant to grow into the collective mind known as the noosphere, while the noosphere, which is the collective, could only be known through its incorporating itself through the individual. I am one such individual, a noospheric chip. The noosphere could not be understood if it did not take on a personality or a number of personalities. Otherwise the noosphere would remain in the purely theoretical state or condition.

Now that the Inevitable Event has occurred, the noosphere is recruiting. The program of recruitment is called the Campaign for the New Time. This is a genuine campaign, but a peace campaign and not a military one. As a campaign it must reach its climax by mid-2004, a full eight years before the end of the cycle, northern winter/southern summer solstice 2012, the noosphere's omega point. The reason for this is that any later than 2004, the prophecy will be negatively fulfilled. A minimum of two Seed-Storm Year bundles-eight years-are needed to creatively destructure and then to reconstruct. The Inevitable Event was a sign of God showing us that the end had already occurred. Now all the forces of goodwill and harmony must be channeled into the conscious act that will coincide with the noosphere's readiness to manifest through all of us, and that is the calendar change-the untried solution, the most important unfinished business of the last millennium.

This is no longer a matter of debate. There is no other solution that hasn't been tried. There is no other way that the noosphere can become collectively conscious than through the human adoption of a timing system of perfect harmony. By meeting our deadline with the noosphere at the time of the Great Calendar Change in the middle of the year 2004-0n the White Spectral Mirror, Day Out of Time, the day of release from the old, and Blue Crystal Storm, the day of entering the new-then the biosphere will harmonically converge with the noosphere, and the *Pax Cultura, Pax Biospherica* may begin in all seriousness. Such is the advent of the noosphere.

What did the Maya foresee for 2012? What is Pacal Votan's vision? Pacal Votan's vision is the fulfillment of a prayer-a prayer that I have heard through the silence:

> o Hunab Ku, One Giver of Movement and Measure, be kind to the children of this Earth. We see how every year you give and how every year you take away. This is so the children of Earth can learn to be free and dwell only in your presence. Yet we know that the children of the Earth must undergo their lessons as well. And we know that they must enter the dark time of testing. 0 Hunab Ku, in their time of darkness, in their time of forgetting, do not forget them, spare those who are good, if you can. Prepare for them the Second Creation you have promised to the righteous among them. Break for them the spell of false time before they destroy this Earth! And show to them the splendors of the Second Creation, of the New Heaven and the New Earth. Show them these wonders before the Great Cycle is finished, so that they may yet wake up from the sleep of time. And 0 Hunab Ku, may the nine great Lords of Time return to Earth! May they teach the children of the Earth how to become a race of wizards, tilling the noosphere as they have tilled the Earth. 0 bring to these children of the Earth a good Time, a Time of Peace as long, at least, as was their time of history and war, and then let that Time of Peace be multiplied sevenfold!

> And here is the vision that fulfills the prayer:

> Planet Earth, Rhythmic Solstice, Blue Resonant Storm year, 2012 Omega Point. The Earth's axis is tilted so that the North Pole is at its farthest from the sun, and the South Pole is at its closest. High above the Earth an iridescent, thin rainbow band

> arches from one pole to the other. A second band does the same, but over the opposite side of the Earth. The Earth slowly rotates beneath these two rainbow bands that remain unchanging, constant in their positions, one of them directly opposite the sun, the other holding a position on the midnight side of the Earth's turning. The band facing the sun is the Earth's day alternator. The other band is the Earth's night alternator. If we glide across the surface of the Earth we see that everywhere there are small encampments, circular and radial in formation. Yurts, tents, adobe, and earthen structures-and gardens. The once-teeming cities are eerily silent, yet still inhabited, though with far fewer people than during the time of the technosphere. And everywhere in the small encampments people are reverentially gathered. This is the moment of the closing of the cycle. It is as if everyone is drawing in a single breath at the same time, and exhaling it at the same time. From wherever you are, even though there are clouds, you can see the shimmering iridescent rainbow alternator, either by day or by night. Clusters of people are gathered in circles of deep meditation. Around them the children laugh and play. "We are the noosphere," a voice is repeating, "we are the noosphere." This sets up a vibration and people everywhere stop in their tracks, they look toward the sky. They listen. "The galaxy is renewing our thought. The galaxy is renewing our mind. The galaxy is renewing our world, this Earth. Let us go home and learn some more." Drums and chanting fade into the twilight in one place and beckon the dawn in another. "Let us say the prayer again: '0 Hunab Ku, Allah, One Maker, Our Creator, we submit to You. Continue to keep us whole, continue to broadcast the noosphere through us, continue to let us listen to the higher collective voice that we are so that tomorrow we may register another kin, another NET minute in the glorious journey of Timeship Earth toward its goal of universal unification in your One Unending Thought, 0 Hunab Ku, do not forget us, now, and do not let us forget you! Thank you for the closing of the cycle! May what we have learned stay with us and become the inheritance of our children for seven times seven generations to come, and may you bring us another cycle for all our descendants to live in continuing peace and harmony!'"

This is the vision. I am a noospheric chip. Do not turn away from your visionaries. Your prophets are still calling you and teaching you, if you would pay attention. There is much to do and learn. There is nothing more joyful than the positive construction of harmony.

Time and the Technosphere, First Draft Transmission completed,
Self-existing Owl Moon Dali 15,
Yellow Solar Seed Year
Kin 42, White Electric WInd:

I activate in order to communicate
bonding breath
I seal the input of spirit
with the electric tone of service
I am ptided by the power of death

First draft edited, completed, and sealed,
Overtone Peacock Moon Seli 2,
Yellow Solar Seed Year
Kin 57, Red Overtone Earth

I empower in order to evolve
commanding synchronicity
I seal the matrix of navigation
with the overtone tone of radiance
I am guided by the power of life force

Second draft edited, completed, and sealed,
Rhythmic Lizard Moon, Seli 23, Navigation Tower
Yellow Solar Seed Year
Kin 106, White Lunar World-bridger
Pacal Votan Clear Sign

I polarize in order to equalize
stabilizing opportunity
I seal the store of death
with the lunar tone of challenge
I am guided by the power of endlessness
I am a galactic activation portal
enter me

May all beings be well and happy!

May this text and these words inspire by their truth.

If I have left out or omitted any logic or fact, or unnecessarily maligned any truth or being by my endeavor to convince through clear argument, may the Creator know that no such malice or oversight was ever intended. I am but a human transmitter, a noospheric chip. My ability is commensurate with the frailties attendant to one too long steadfast on a path too little comprehended by many of those around him.

May the truth prevail!

Jose Argiielles, Ph.D.
known in prophecy's light as
Valum Votan, the Closer of the Cycle
devotee of Bolon Ik

Brightwood, Oregon
Cascadia Bioregion
North American Plate

▼



Sarcophagus lid of the tomb of Pacal Votan 9.13.0.0.0 (A.D. 692)



Epilogue

Networking the New Time

TO READERS for whom the notion of calendar change, much less that of a Campaign for the New Time, is totally novel, yet who may have an interest in learning more about and participating in the preparation for the Great Calendar Change of 2004, there is a place to begin and a way of going about it.

The official coordinating agency for the Campaign for the New Time and the World Thirteen Moon Calendar Change Peace Movement is the Foundation for the Law of Time. As a nonprofit public charities educational corporation, the Foundation for the Law of Time provides the communications and information hub for the Planet Art Network (PAN). The Foundation also publishes calendars, tools, and literature about the Law of Time and sponsors various educational programs, periodic seminars and congresses, and projects such as the new time educational caravans and the development of garden-oriented land bases.

For general information on the Law of Time or the Campaign for the New Time and its educational programs contact:

Foundation for the Law of Time, World Headquarters
Post Office Box 513
Brightwood, Oregon 97011 U.S.A.
Tel: +1 (503) 622-1976
Fax: +1 (503) 622-0198

The Foundation for the Law of Time's outreach activity program is known as the Planet Art Network (PAN), the loosely knit and decentralized base of operations for the World Thirteen Moon Calendar Change Peace Movement. The PAN is organized into Bioregions, each with its PAN nodes (local chapters) and a governing Bioregional Council. The PAN nodes organize "crystal day meetings" once every thirteen-day wavespell-the crystal (twelve) tone day is the day to call a round table or court of the kin to review past actions and prepare for future ones. The PAN nodes also offer educational programs and disseminate calendars and other educational tools and literature provided by the Foundation, which constitute the information outreach of the World Thirteen Moon Calendar Change Peace Movement. The Campaign for the New Time is the coordination of the world PAN toward the goal of the Great Calendar Change of 2004. The PAN is also generally responsible for organizing the annual Day Out of Time events in its different localities and bioregions.

For information about local Planet Art Network (PAN) operations, contact:

Foundation for the Law of Time/Gnomicile Land Base
World PAN Coordination Center
PMB 267
105 North First Avenue
Sand Point, ID 83864-1301 U.S.A.
Tel: +1 (208) 255-1172
Fax: +1 (208) 265-9107

The official Web site for the Foundation for the Law of Time, Planet Art Network, World Thirteen Moon Calendar Change Peace Movement and Campaign for the New Time is:

www.tortuga.com

This Web site is continuously updated and offers a great range of both practical and theoretical information about the Law of Time, the Campaign for the New Time, ongoing and upcoming events and educational seminars, listings of major PAN nodes worldwide, Law of Time archives, and links to other relevant Web sites.

A major aspect of the Campaign for the New Time is the development of a program of "strategic alliances," information about which is also available at www.tortuga.com. If you belong to an organization that you feel could be in alignment with the goals of the Campaign you can check out the Strategic Alliance page of the Web site or directly contact the Foundation for the Law of Time, World

Headquarters. The goal of the Strategic Alliances is to establish a "synchronization for peace force"-a coalition of a wide spectrum of organizations that are in alignment with the calendar change and are willing to help organize local events and information dissemination for the Great Calendar Change of 2004.

See also Appendix II, "The World Thirteen Moon Calendar Change Peace Movement and the Discovery of the Law of Time: A Brief Chronotopology of Transformation. "



Appendix I

Summary Critique of the Gregorian Calendar

What Every Proponent of the Thirteen Moon Calendar Should Know

NOT ONLY is the idea of the calendar as an instrument to determine a true and accurate year misleading, but solely focusing on this purpose blinds us to any consideration of time apart from duration or measurement of motion in space. The Law of Time asserts that the actual nature of time is synchronic; hence the purpose of calendars is to synchronize us in time according to various cycles whose harmonic numbers extend from and return us to a higher mental order of reality. It is a fatal error to dismiss a mathematics of harmonic perfection when it is allied with the ordering and comprehension of cycles. The pursuit of a true and accurate year totally subordinates the cyclic nature of time to the ceaseless imperfection and change that characterize the phenomenal world when it is considered as the sole factor of existence. This defines the thoroughly materialist worldview of the 12:60 consciousness.

In order to prepare the ground for a proper consideration of the Law of Time and the evolutionary necessity of the synchronic order of time as the harmonic reorganizing factor of humanity in its post-historic phase, it is necessary to expunge from the mind the error known as the Gregorian calendar. To demonstrate and expose the illogical and irrational nature of the Gregorian calendar as a standard of measure, the following seven points are presented as a simple appeal to the intrinsic logic and intelligence of any human being.

1. We require of a standard of measure that its units of measure are regular and equal with one another.

This is not the case with the Gregorian calendar, whose base unit of measure, the month, proceeds in an irregular and uneven manner: 31 days, 28 days, 31 days, 30 days, 31 days, 30 days, 31 days, 31 days, 30 days, 31 days, 30 days, and 31 days. Why would anyone use a standard of measure with irregular units? Do you know what results when a crooked standard of measure is employed consistently for millennia? It might be noted that at the time of Augustus Caesar, August was called Sextile and had thirty days, while February then had twenty-nine days. In order to honor Augustus and make him the equal ofJulius Ouly) which had thirty-one days, the twenty-ninth day was taken from February and added on to Sextile, whose name was then changed to Augustus (August). By harmonic contrast, the Thirteen Moon calendar is perpetual in that all of its units of measure are equal-28 days each.

2. The names of the months are as illogical as their uneven numbering.

January is derived from the God of the doorway; February is an obscure word referring to an animal divinatory rite; March refers to Mars, the planet and the god of war; April and May refer to goddesses of the spring; June to the wife of Jupiter; July and August are named after the two most prominent Roman Emperors, Julius and Augustus Caesar. As for the remaining months, September, the ninth month, means seven; October, the tenth month, means eight; November, the eleventh month, means nine; and December, the twelfth month, means ten. Of course, having grown habituated to the crooked standard of measure, it is easy to overlook and dismiss as innocuous the irrational naming of the months. But is it so innocuous? What do the names of these months have to do with an order of time, or even a cosmology or culture of time, which we assume a calendar might reflect? By blindly accepting this irrational disorder of names, do we not predispose ourselves to accept irrational disorder in commonplace things around us, and even within the fabric of our society, thus reinforcing in us a tendency to accept a superficial treatment of the symptoms, while ignoring the roots?

3. Leap year and leap day is the most highly touted aspect of the Gregorian calendar.

Structurally, the Gregorian calendar is indistinguishable from the Julian calendar. The only thing that separates the Gregorian from the Julian calendar is the correction of the leap year day. Pope Gregory XIII "corrected the calendar" by deleting three leap days from the years that begin the centuries, except those divisible by the number four. Leap day is the extra day that accumulates every four years due to the length of the astronomical year being 365.241299 days and not 365. It can be seen that the fraction .241299 is not quite 1/4, which would be .25. The Julian calendar did nottake this into account, hence an error crept in that caused the spring equinox on the calendar to fall some ten days behind the solar moment of the spring equinox-a fact noted by the conquistadors when they encountered the Mayan calendar, which had no such discrepancy. Thus, in 1582, Pope Gregory XIII "improved" on Julius Caesar's calendar, some 1,627 years later, by adopting the rule that there would be no extra day on centuries-OO years-except on those that are multiples of four. Hence, there was no leap day in the year 1900, but in the year 2000, a multiple of four, there was.

What is not well known is that the Vatican does not recognize the leap day in its ceremonial calendar. Why is that? In most countries where Latin-derived languages are spoken, leap day and leap year are referred to as *bisiesto,* or "bisextile" day and "bisextile" year. If leap year is every four years, why is it referred to by a word that connotes six, *sextile?* On the official liturgical Church calendar there is no February 29! Instead, there are two February 24s, and the second February 24 is not counted. If there were to be an extra day that was counted, then the system of fixed feast days would be thrown off. Instead, on leap years, February 24, the Day of the Feast of St. Matthew, is counted twice-or extended to be 48 hours. And since in the Church tradition derived from the Romans the days are counted from the first of the next month, the first always being known as the calends, the date February 24 is technically referred to as the "sixth of the calends of March" (February 24 = sixth calends of March, February 25 = fifth calends, February 26 = fourth calends, February 27 = third calends, February 28 = second calends, and March 1 = calends of March). For this reason, the leap year is known as *bisiesto* because the sixth *(siesto)* calends of March is doubled, hence "bi." Thus, February 29 is not recognized by the official Church calendar of the Vatican, and it is also not counted as a day in its liturgical calendar. February 29 only arose out of popular tradition in the sixteenth and seventeenth centuries. The nemesis of accounting for the .241299 extra day per year reveals the fixation of astronomical time in seeking a "true" year and detracts from the possibility that the issue of an intercalary, or extra, day can logically and synchronically be handled in many other ways. In the end, it is the mystique surrounding leap day that further contributes to the numbing of the sensibility of time accumulated in the instrument known as the Gregorian calendar, "the little grid of boxes that rules so much of our lives."l

4. **The word we use to describe the instrument for measuring, the Earth's orbit around the sun, *calendar,* is derived from the word *calends.***

Calends was the Latin name given by the Romans to the first day of every month. What does it mean? *Calends* is the name of the account book, the book of payments recording the monthly debts and bills to be paid! No wonder we are ruled by the philosophy "time is money!" This philosophy is rooted in the very word we use to describe time reckoning, *calendar.* A more accurate word for time reckoning might be "chronometer," or even better, "synchronometer." But perhaps the word "count" is simpler. We might just say, for example, Thirteen *Moon!2* 8-Day perpetual count.

5. Dominicalletters code the years of the Gregorian calendar.

Scarcely known to anyone but Vatican insiders is the system of dominicalletters that is used to code the years according to the day of the week on which the first Sunday of the year falls. Since the week has seven days, there are seven and only seven dominical letters. These are the letters a-g, where a = 1, b = 2, c = 3, d = 4, e= 5, f = 6, and g = 7. Hence, G-7 (the group of the seven most industrial nations), the name given in 1974 by the CIA to the ruling oligarchy of globalization, is totally rooted in the system of the seven dominicalletters, a-g, to which the Gregorian calendar can be reduced. It works as follows: In 2001, the first day of the year was on a Monday, hence in this year all Mondays are coded by the letter a. Counting forward to the first Sunday, January 7, Sundays this year are coded g. The letter of the year, which is always a capital letter, is based on the lower case letter that codes the first Sunday, therefore, the year 2001 is coded as the capital letter G-it is truly a G-7 year! Not only that, but by this system of "G-7" dominicalletters, it can be demonstrated that the order of the Gregorian calendar year repeats within a cyclic structure of precisely twenty-eight years, where the days of the week and the month repeat once again. Hence, the cycle 1973-2001 is a repeat of the cycle 1945-1973, which is a repeat of the cycle 1917-1945, and so forth, where the years 1917, 1945, 1973, and 2001 are calendrically indistinguishable from each other. In any twenty-eight-year cycle, there are always exactly seven leap years! Thus, the key code numbers 28 and 7 of the Law of Time and of the perfect Thirteen *Moon!2* 8-Day calendar are hidden in and even govern the cyclic order of the Gregorian calendar, whose secrets pretend to lie concealed in the Vatican archives!

Expose these secrets and show that the true harmony of time is contained in the 13:20 matrix of the Harmonic Module, which is perfectly coded by 28 and 7. Within this matrix, any set of four tones radially opposite each other, an occult quartet, always adds up to 28. There are 65 (x4) such sets that constitute the Harmonic Module, while seven (multiplied by four), is the prime factor of 28, and is the key unit holding the 13:20 matrix in place, evident in the position of the seventh vertical column on either side of which is a perfect harmony of six columns each. The seven is also the implicit number in the ratio 13:20 (13 + 7 = 20: 20 - 7 = 13). But whereas the 13:20 matrix is a harmony in which the Law of Time is encoded, the Gregorian calendar is a disharmony, but one that is nonetheless governed by the Law of Time. What the Vatican attempted to destroy at the hands of Bishop de Landa in 1562, in the famous book burning at Izamal Yucatan, is redeemed by the Law of Time. Free of the obscuring, illogical irrationality of the inexact measure of the Gregorian calendar, the actual truth of the synchronic order of time may be discovered and revealed as the 13:20 mathematical code ofthe Harmonic Module, perfectly coordinated with the Thirteen Moon!28-Day count.

6. The Gregorian calendar makes day/date calculations difficult.

The twelve uneven months of the Gregorian calendar operate by a subsystem of fifty-two 7-day weeks, plus one day. Because of the irregularity of the numbering of the months, and because there are 365 and not 364 days in a year, it is almost impossible to make easy calculations month to month and year to year, while insistence on the unbroken succession of the week only compounds this issue. For example, if today on the Gregorian calendar it is Friday, May 4, 2001, what day of the week will June 4 be? What day of the week will July 4 be? There is an immediate mental block-a numbing of the mind. You have to stop and think about it. And in this numbing pause in which your cognitive brain has to be engaged, you lose your telepathic awareness, much as when you look at a clock to find out what time it is. Why should it be this way? Who benefits? The answer is, the priests (who know the tedious rules for stating that if it is Friday and it is 2001, then it is dominical e) and the bankers (who gather interest based on the confusion over the erratic disparity of days every month). By contrast, on the perpetual Thirteen Moon calendar, this day would be Spectral Moon Gamma 3-while every third day of every Moon is coded by Gamma. In fact, the third day of every week is coded by the name Gamma. Once the 28-day count is mastered, there is no need to engage the cognitive brain to figure out what day of the week Crystal Moon 3 or Cosmic Moon 3 will be-and in this way the mind is liberated into a telepathic knowing.

The system of the seven-day week was introduced into the Julian calendar at the Council of Nicea, A.D. 325, and was adopted from the Jewish calendar, which was derived from the Babylonians, for whom it was an astrological-astronomical construct. The fact that the week came from the Babylonians dissolves the argument used by the Vatican to counter the Day Out of Time. According to the Vatican, disrupting the succession of the seven-day week would disrupt an order set in motion by

God. The matter of the 7 and the 52 has a much deeper significance when understood in the higher-dimensional light of the Law of Time. A count of fifty-two 7-day weeks makes perfect sense if you have a count of thirteen 28-day months (7 x 52 = 13 x 28). The observance of the Day Out of Time, the 365th day of the year, produces a perfect and perpetual harmony. Knowing this, to continue to insist on fifty-two weeks while being unwilling to give up a twelve month count that does not have a Day Out of Time is to persist in an adherence to hopeless disharmony. Why do it?

7. What's in a name? Think about it.

What does it mean to follow calendars called the Julian and the Gregorian? A calendar is an instrument of control. The two most significant calendar reforms in history were the Julian calendar reform of 46-45 B.C., and its successor, the Gregorian, in A.D. 1582. Julius Caesar's motives had everything to do with his personal ambition and the conversion of Rome from a republican to an imperial form of government. Julius Caesar's calendar assured it to be the basis of imperial dominance. The course of the empire utilizing the Julian and later Gregorian calendar has prevailed as the dominant force now inseparable from the course of history itself. The 445-day "year of confusion" (46 B.C.), which attended Julius Caesar's reform, was matched by the second significant reform, the Gregorian, in which ten days were "lost forever," between October 5-16, 1582, so that the calendar could "catch up" with the sun.

While European Catholic countries easily accepted the reform, Protestant countries grudgingly acquiesced. Throughout the Americas, however, the Julian-Gregorian calendar was imposed as an instrument of power and symbol of dominance over the peoples the Europeans had conquered, including the high civilizations of the Maya, Inca, and Aztecs-all of whom happened to use, among other calendars, a Thirteen Moon!28-Day count. As with Julius Caesar, for Pope Gregory XIII the moment was politically ripe for a reform that would communicate itself as a means of expressing and extending power and control, but this time over the entire globe. As European dominance and control spread around the planet, even nations with their own established timing systems accepted, for the sake of "international policy," the Gregorian Oulian) calendar system for measuring the solar year. And so Western dominance over every aspect of global life became absolutely assured-until the moment of the Inevitable Event.

From its roots in the imperial ego of Julius Caesar to the timely "reform" of Pope Gregory XIII, it is not surprising that this calendar, "despite its odd quirks and the twists of history that produced it,"[2] has become the standard of global civilization. Given the irregularity of the Julian-Gregorian calendar and the pursuit of the accuracy of astronomical time, history could be nothing more than a compilation of odd quirks and twists, while global civilization itself is the triumph of artificial time over the natural world. Only a species whose time sensibility had been captured by instruments of artificial measure could have become so alienated as to have produced the monstrous conundrum known as the "fast world," a civilization where money and technological advance prevail over human sensibility and the natural order. It is toward the correction of this destructive momentum that all efforts of calendar reform must now be directed.

In light of this critique, it is worth reprinting the opening section of the "United Manifesto by Advocates of Calendar Reform" that was first published in 1914 at the beginning of the First World War-some ninety years in advance of the Great Calendar Change of 2004. It can be seen that the issues of irregularity that prompted reform then are still issues today. However, the effects of not attending to these issues have only become compounded and even more complex, resulting in the chaos of a world at war with terror. Such is the nature of an error gone uncorrected over time-it only becomes more entrenched and turns into the dogmatic and hopelessly conflicted thinking of the everyday mind and its way of life.

> United Manifesto by Advocates of Calendar Reform
>
> WHEREAS we, the undersigned, have for some time been interested in a Reform and Simplification of the Calendar now in use in Western Europe, America, and elsewhere, with a view to equalizing the four quarters of the year, alleviating the irregularities of the months, and establishing a perpetual correspondence between the day of the week and the day of the month, and have supported one or other of several proposals which have been formulated for effecting these reforms; and WHEREAS said proposals usually provide for placing the 365th day of every year and the 366th day of Leap Year without the weekly and monthly enumeration; and WHEREAS we have found that in certain quarters-both ecclesiastical and scientific-Dbjections, possibly often sentimental, but none the less firmly held, have been stated to the employment and adoption of these expedients. . . Therefore we have resolved to unite in urging and advising that the very simple changes under noted should now be made in the Julian and Gregorian Calendars by international agreement. . .[3]

If you have a crooked standard of measure, and follow it because your parents were also following it, you have become a crooked man. It takes a crooked man to walk a crooked mile and build a crooked house. The issue of calendar reform is both logical and moral. Bad logic leads to bad morality. An error in time dooms the mind. Apocalypses are the reward for bad timekeeping. To remove yourself from the fires of your own self-created apocalypse, change your calendar. In a world of harmony there is no apocalypse.

▼

Appendix II

The World Thirteen Moon Calendar Change Peace Movement and the Discovery of the Law of Time

A Brief Chronotopology of Transformation

IT WAS during the seven-year cycle (1993-2000) when the World Thirteen Moon Calendar Change Peace Movement was being aroused around the planet, that the Law of Time was articulated in its various aspects and particulars, and the synchronic order defined in its whole system fullness. This occurred through a number of key events accompanied by a number of publications detailing the mathematical, cosmological, theological, and scientific aspects and imperatives of the Law of Time.

By the standards of the synchronic order, all events form points in a radial time set that describe a geography of time defined as a chronotopology. Coined by the late philosopher and mathematician Charles Muses, the term *chronotopology* defines an event point of meaning that creates a root meaning from which time-formed, -blossomed, or -radiated meanings emerge above a horizon of meaning.[1] The Law of Time now gives a precise field in real time to illustrate Muses's notion of chronotopology in which Time is a radial power of profound interrelations.

The following chronotopological sequence-a resume of the events in a particular geography of time, the seven years of prophecy, 1993-2000-defines the conscious emergence and articulation of the Law of Time. In this chronotopology, the "root meaning" occurred in 1989 at the Museum of Time in the form of the discovery of the 12:60 and 13:20 timing frequencies, and the subsequent working out of the implications of this discovery. The "horizon of meaning" was reached July 26, 1993, kin 144, with the decoding of the Telektonon Prophecy and the consequent development of the World Thirteen Moon Calendar Change Peace Movement. The "source meanings," however, extend back to the seventh century with the origins of the prophetic traditions underlying the discovery of the Law of Time. The seven years of prophecy established the field of radiated meanings of the Law of Time as a set of radiated event points and a body of literature and tools. Here follows, then, a brief chronotopology of the key event points of this movement:

1989	Root meaning: discovery of the 12:60 and 13:20 timing frequencies, Museum of Time, Geneva, Switzerland.
1990	Realization of the Thirteen Moon/28-Day calendar in its wavespell form.
1992	Recognition and celebration of the Day Out of Time as a planetary event.
1993	Horizon of meaning: decoding of Telektonon Prophecy and birth of World Thirteen Moon Calendar Change Peace Movement.
1994	Launching of the Planetary Moral Emergency and World Thirteen Moon Calendar Change Peace Plan.
1995	80 Days Around the World for a New Time of Planetary Peace: Chile, South Africa, Egypt. Russia, India, Hong Kong, Japan, Hawaii, and Mexico.
1995	Day Out of Time Calendar Burning and Return of Natural Time Ceremony, Serpent Mound, Ohio.
1996	First Planetary Congress of Biospheric Rights, Brasilia, Brazil.
1996	Biospheric Awareness Day, Gotemba, Mt. Fuji, Japan.
1996	Four Corners Boundary Dissolving Ceremony, Four Corners, United States.
1996	Harmonic Convergence of Humanity, Mexico City, followed by Peace March, Teotihuacan, Mexico.
1996	United Nations, Planetary Moral Emergency Appeal.
1997	Judgment Day Tribunal and World Congress on the Law of Time, Tokyo, Japan.

1997-present	Ongoing movement in Brazil to make July 25, Day Out of Time, official "Peace and Culture Day;' based on recognition of the Banner of Peace (seventy cities so far).
1998	Special peace mission to the Vatican, Rome, Italy.
1998	Special mission to Guatemala to meet with Quiche Maya elders.
1998	UR Council for the Theology of Peace, Milan, Italy.
1999	world Summit on Peace and Time, University for Peace, Costa Rica, followed by the dispatching of Special Emissaries to the United Nations and the Vatican.
1999-present	Ongoing movement in Japan to declare Day Out of Time a "Day of Festival"; more than one hundred events occurring annually.
1999	Peace March, Teotihuacan, Mexico.
1999	Seven Week Earth Wizard Seminary, Picarquin, Chile.
1999-2000	Ongoing in South America, launching of "La Karavana;' Thirteen Moon educational caravans, and in Europe, from the United Kingdom to North Africa, the New Time Caravan.
2000	Initiation of Seven-Day Earth Wizard's Seminars: Japan, United States, Italy, Russia, South America.
2000	Circumpolar Rainbow Bridge Experiment, phase I, worldwide.
2000	Fruit of meaning: establishment of Foundation for the Law of Time, Oregon.
2001	Launching of the Campaign for the New Time, Brazil. Argentina, Japan, Altai region.
2001	Campaign for the New Time PAN Thirteen Moon Leadership Conference, Oregon.
2001	Seven-day special Congress on Time and World Peace, Medellin, Colombia.

During this chronotopological sequence of radially connected event points, key writings, publications, and tools describing and defining the Law of Time and the synchronic order include:

Dreamspell: The Journey of Timeship Earth 2013, 1990-91

Thirteen Moons in Motion and *Turtle of the Thirteen Moons,* 1993, 1996

The Story of Time: The Story of Turtle and Tree, 1993

Treatise on Time Viewed from its Own Dimension (Published as *The Call of Pacal Votan:*

Time is the Fourth Dimension), 1992, 1996

Telektonon of Pacal Votan and the *Telektonon, Game of Prophecy,* 1993-1995

World Thirteen Moon Calendar Change Peace Plan, 1994-1995

Pacal Votan and Judgment Day: The Second Quranic Dispensation, 1995-1996

First Planetary Congress of Biospheric Rights, 1996

The Galactic Culture Master Plan, New Time Economics, 1996

A Brief Guide to The Thirteen Moon Calendar Change Peace Movement, 1996

Rinri Project: Four-Year Telepathic Biosphere-Noosphere Transition Circumpolar Rainbow Bridge Experiment, 1996

The 260 Postulates of the Dynamics of Time and the Evolution of Time as Consciousness, 1996

The Discovery of the Law of Time, T(E) = Art, 1996

The Principia Mathematica of the Fourth Dimension, 1996

Twenty Tablets of the Law of Time: Sixteen Year Telektonon Cube of the Law, 1997

World Congress on the Law of Time and Judgment Day Tribunal, 1997

World Summit on Peace and Time, Summary, Review, and Conclusions, 1999

7:7::7:7, Telektonon Revelation and Plasma Universe Model, 1998-2000

The Rainbow Bridge Project: 28 *Meditations on the Law of Time,* 1999-2000

The UR Papers: Documents and Appeals for a Council of Universal Religion, 1996-2001

WIth the conclusion of the seven years of prophecy, marked by the rainbow bridge experiment, phase I, the greater part of the Law of Time had been uncovered, described, and defined. What emerges from consideration of all these events and accompanying literature is an entirely new model of the universe as well as a program for the reorientation of knowledge and the social reorganization of humanity-all based on a corrected understanding of time through the implementation of the calendar change. This was all to demonstrate that there is much more to a calendar change than the mere replacing of one calendar with another, for a calendar itself bears within it an understanding of time that tacitly and unconsciously shapes our very thinking about time. What the calendar change, then, really signifies is the end of one worldview and the birth of another. WIth the Law of Time, what was once unconscious is again made conscious, leading to a radical self-awareness of how wrong we have been about time, and what we might anticipate in changing our tools for navigating in time.

Because the growth of the Planet Art Network (PAN) as the social form of the World Thirteen Moon Calendar Change Peace Movement is inextricably involved with the unraveling by stages of the Law of Time, to define the constituent principles of the Law of Time is also to define the new worldview and the social organization appropriate to it. These constituent principles include: time is art; universal telepathy; holonomic consistency and reciprocity; synchronic order; fractal and radial mathematics of the 13:20 matrix; biosphere-noosphere transition; Banner of Peace; *Pax Cultura*, *Pax Biospherica;* the psi bank and the dynamics of the evolution of time as the evolution of consciousness; fourth-dimensional time and third-dimensional space. A mere consideration of these constituent principles will make one realize to what extent the calendar change is more than just an end to history, but the establishment of a new world, a New Heaven and a New Earth. This is precisely the promise offered by the Thirteen Moon calendar change and the discovery of the Law of Time. (See plate 8, Chronotopology of Transformation.)

▼

Appendix III

Telektonon Prophecy of Pacal Votan

THE REVELATION of the prophecy of Pacal Votan on July 26, 1993 was the culmination of the event that occurred on June 15, 1952, when the archaeologist Alberto Ruz Lhuillier pried open a large monolithic trapezoidal door beneath the Pyramid of the Inscriptions at Palenque, Chiapas, Mexico, and beheld what had not been seen by human eyes for 1,260 years: the tomb of Pacal Votan. A subsequent event, the lifting of the magnificent sarcophagus lid—measuring some four-by-three meters and weighing several tons—to reveal the human remains amidst a splendor of jade, including the jade mask, occurred on November 27, 1952. For some forty years afterwards, scholars debated the meaning of the tomb and the person buried within it. In the 1970s, the Russian scientist Knozerov dubbed the man in the tomb an "astronaut" or "cosmonaut" because of the similarity of the position of the figure sculpted on the sarcophagus lid to the positions of Russian cosmonauts in their little space capsules. This theory inflamed the imagination of some and was debunked by others, the end result being the enhancement of the awesome mystery of the tomb and the intention of its designer, the man buried in it.

The image of the sarcophagus lid is now world famous. Its symbolism has been interpreted to varying degrees by different archaeologists. In my book *The Mayan Factor,* the placement of Pacal Votan in his "time of power," 631-683, is defined and analyzed as occurring in the most harmonic and mathematically synchronic point of the entire thirteen baktun cycle, a point of fact that deepens the enigma of Pacal's knowledge and purpose. And herein lies the key question: What was his purpose, and why did he construct his tomb to be so elegantly buried for 1,260 years, to be discovered and opened just sixty years before the closing of the cycle, A.D. 2012? Clearly, the mystery of the tomb and its discovery had everything to do with the end of the cycle. At least this had come to be my surmise ever since the 1987 Harmonic Convergence. Like a hawk circling its prey, the meaning of the tomb finally came to my consciousness like a direct hit from the beyond. I was the prey, the hawk, the prophecy itself. Such was the revelation of the Telektonon Prophecy on the morning ofJuly 26, 1993.

The coded key was the tiled "speaking tube," by which the tomb was discovered in the first place. Suddenly, this tube spoke its meaning to me: Earth Spirit Speaking Tube, Telektonon by name. After four intense weeks of decoding the glyphs and symbols of the tomb while living in the pool house of an isolated estate in the wind-blown northern part of the main island of Hawaii, I knew that I had to abandon the dreamlike life I led in this Pacific paradise, and with my wife and companion head directly into the unknown, the first stopping point being Mexico, the source of the prophecy. After four months or so of traveling through Mexico, completing the decoding and announcing the prophecy, including a return to the tomb, we were finally directed to a converted carport in a field near the village of Ocotithin, not far from the birthplace of Quetzalcoatl. It was here where, for a period of nine mornings, I awoke dutifully two hours before sunrise to listen to the voice and write down by hand, in a specially prepared notebook, the words exactly as I heard them. Afterward, I numbered the 126 verses and distinguished the nineteen sections.

Because the prophecy itself is so inextricably connected with the Law of Time and the message of *Time and the Technosphere,* I feel it is important to present it as background information to the text of this book. In actuality, the text of the Prophecy is an integral part of the *Telektonon, Game of Prophecy,* where it is read, section by section, on a daily basis, according to the code number of the kin of the day.

THE TELEKTONON OF PACAL VOTAN

The Talking Stone of Prophecy That Unites the People of the Dawn with the People of the Book

"Then if they reject thee,
so were rejected apostles
before thee, who came with clear signs,

books of dark prophecies
and the Book of Enlightenment. "
-HOLY QURAN, SURA **III,** 19: 184

"All who obey God
and the Apostle
are in the company
of those on whom
is the grace of God,
of the prophets who teach,
the sincere lovers of truth,
the witnesses who testify
and the righteous who do good.
Ah, what a beautiful fellowship!

Such is the bounty
from God: and sufficient
is it that God knoweth all. "
-HOLY QURAN, SURA Iv, 9:69-70

● INTRODUCTORY VERSES: ONE LIVING PROPHECY

1. Pacal Votan's Gospel of the Telektonon
A Special Dispensation for the Day of Truth,
A.D. 1993-1994, kin 144.

2. Proclamation on behalf of the three messengers
of the awakening,
of the three special voices of prophecy,
the special witness of time and the last call.

3. Telektonon
the inner sun
the mother of all prophecy
message of the star witness, Bolon Ik
received and repeated by her servant in love,
Pacal Votan.

4. In the seventh year of Harmonic Convergence
the seven seals of the apocalypse
become the seven years of prophecy. . .
thirteen years in all.

Thirteen moons the path to walk;
thirteen moons the path to talk;
people of the dawn, one mind,
people of the book, one God;
one living prophecy, one people, one Heaven,
one Earth.

●● NAH CHAN: THE PALACE OF BOLON IK

5. o children of the people of the dawn, a children of the people of the book, I come as the special witness of time to remind you, especially on the day of truth, that in your origin you are one, and on the day of truth you are to make yourselves one again. For this I remind you of the Cube of the Law, Telektonon, and the 28-day, thirteen moon way that is the path of the righteous.

6. Nah Chan, Palenque, Xibalbay, Tollan, Xochicalco, Tepozteco, Amatlan: in these signs dwell my special agents, the witnesses of truth, 13.66.56 and Bolon Ik, Daughter ofJob.

7. For those with eyes, with open mind and sincere heart, this teaching is complete in every stone alignment and marking of the star command base now called Palenque.

8. New Jerusalem is the Palace of Bolon Ik, whose number is 1,728 (144 x 12), Cube of the Law. Seventeen is the power of Heaven, "solar Uranus," which is Earth in Heaven. Twenty-eight is the power of Telektonon, the Spirit Tower of the power of 7 times 4.

9. Never forget, children of the day of truth: All is number. God is a number. God is in all.

10. And everything there in the palace is laid out foursquare from the cord of Heaven, which is the command of the Telektonon. "Divine word never uttered until the Day of Truth." And in that palace, foursquare is the tower of the Cube of the Law.

●●●THE CUBE OF THE LAW AND THE TOWER OF BABEL

11. o children of the day of truth, before the separation that divided you into the children of the dawn and children of the book, there was only the Cube of the Law and the Law of the Cube.

12. Everyone and everything moved and lived within this Law: one mind, one spirit, one will.

13. Within the dimensions and measurements of the cube are all knowledge of Heaven and Earth. And in order to know, expand on, and delight in the sublime Law of the Cube, God created you, 0 children of the day of truth.

14. And though shaped of no more than mud and sounding clay, in you is the perfection of knowing the Cube of the Law, if only you remembered!

15. Children of the Day of Truth, just as the cube is the measure of the perfection of God's thought, so you are the measure of God's unceasing movement, which is called time.

16. In you the cube is the crown of perfect knowing of God's will in time. But true to his word, Iblis made wrong fair-seeming. To show himself man's enemy, Iblis split the cube. He drove a forgetting of time within the mind, separating mind from spirit, which is God's movement in all things.

17. And from this forgetting in man, mind and spirit became confused. The will weakened. Ego was born. Iblis's many-headed self triumphed. False authority arose. Babylon came to be and in its center the Tower of Babel, the monumental curse for no longer knowing time.

18. In the forgetting was the separation of the people of the dawn from the people of the book. Had there been no Tower of Babel, there would have been no book. The Tower of Babel was a deceit intended to show the Cube of the Law existing outside of the perfection of knowledge already formed within you, a children of the day of truth.

19. Product of the forgetting, the Tower of Babel has a shadow of ever-darkening and all-encompassing dimensions that spreads 5,000 years from Babylonia to all of Earth's most remote wildernesses and mountain retreats. Iblis's curse of Ego and false time are complete but hold only to the day of truth.

20. For God is gracious and most merciful. As long as He could, He kept the people of the dawn away from the Tower of Babel. And to both the people of the dawn and the people of the book, He sent many messengers, apostles of light, witnesses of truth, doers of the righteous way, which is always framed by the invincible Law of the Cube.

●●●● TELEKTONON: THE FRAME OF TIME

21. As the special witness of time, I, Pacal Votan, know the perfect count of days. I bow in the temple of the tower and the rock, the sanctuary of Bolon Ik. In my body, formed of the ultimate perfection of God's power of all movement and measure (Hunab Ku), is the recollection that is prophecy. Knowing this body as the measure of time, I had built this palace and this tower to correct and to also look for the Tower of Babel, a memory of the remembering. And in my ninefold temple, where, guarded by the nine powers of time, I had this body laid, I left this legacy for you, the Talking Stone of Prophecy.

22. Telektonon, the frame of time I left for you, is a mirror to show you your own truth of time for one last time. For now is the day of truth, the hour of judgment.

23. You, children of the dawn, and you, people of the book, unify yourselves the only way you can: in time, through time, as time.

24. Telektonon, the perfection of time, is the only way for you to escape the fire that consumes the unrighteous. If you who know, who have followed the straight way, the good path, now falter in this challenge of unification in time, Telektonon, which has already been prepared for you, you will perish forever in the fire that now consumes all unbelievers. God's command is in you. Do not listen to the evil one now.

MY COUNT OF DAYS IS PERFECT

25. Listen! My knowledge is this: My count of days is perfect, my knowledge of the Cube of the Law is unsurpassed. Twelve is the number of the temple, but thirteen is the number of God. Twelve times twelve, 144, is the number of the perfection of the temple as light. And twelve times 144, 1728, is the number of the Cube of the Law, Telektonon, the divine word unuttered until now.

26. "... To him that overcometh will I give to eat of the hidden manna, and will give him a white stone, and in that stone, a new name written, which no man knoweth, saving he that receiveth it." (Revelations 2:17) And that name is Telektonon, and that stone is crystal, and that hidden manna is knowledge of the revelation of time.

27. The number of the elect is 144,000. This was the number set aside by God to be free of Iblis's curse. Dispersed is this number among mankind, and always was it meant to multiply both among the people of the dawn and the people of the book.

28. But since a human kin is the measure of the perfection of time, 144,000 is also the number of days within a cycle of twenty generations.

29. Twelve times 20 generations is 1,728,000 days, the number of the Cube of the Law. But for God, one cycle more, 144,000 days more to entice Iblis to make his score, a total of 1,872,000 days, thirteen cycles of God's elect.

30. I am Pacal Votan, time's special witness, galactic agent of the Nine Great Lords of Destiny, by oath pledged to the honor of Bolon Ik.

31. In my body of time, thirteen star histories rehearse themselves for the day of truth. Each star history possesses its own knowledge keeper appointed by the Nine Great Lords of Galactic Destiny. Thirteen Wisdom Holders, Nine Great Lords, twenty-two in all, to each of whom I am bound by a luminous thread of knowing, sealed by oath to Bolon Ik, White Solar Wind, kin 22 in the Book of Destiny, the Book of Kin.

ALL IS NUMBER

32. All is number. God is a number. God is in all.

33. Child of the day of truth, listen: 20 is the number of totality. You have twenty fingers and toes because God has made you the totality of time. Thirteen is the number of God's cosmic wisdom, perfect in its power of unceasing change and circulation. Thirteen are the joints of your limbs and body. Seven is the difference between 13 and 20. Seven is the mystic perfection between one and thirteen. Seven is the erect spine of the vigilance in which are met the 144,000 mystic fibers of the body's thirst for prophecy.

34. 144,000 kin, 144,000 days, these are called a baktun. Thirteen baktuns, one perfect cycle to rehearse all thirteen star histories. Each baktun, twenty generations, each generation 7,200 kin. So it was that Bolon Ik ordained the sacred count of days, each day a sacred kin, each kin one of the elect, a turning in the twist of universal time, each kin ruled by the power of the nine, the power of the Nine Great Lords of Time.

35. So began the sacred thirteen baktun count, 3,113 years before the birth of the second of the special messengers, the Apostle Jesus Christ, who sent to you a Book of Dark Prophecies, twenty-two sacred chapters in all, through his appointed witness, John ofPatmos.

36. All this I know and declare to be true, for I am time's special witness to the day of truth, Pacal Votan, rehearser of the thirteen star histories, he who adds the 144,000 elect to the cubing of the cube, assuring not twelve baktuns, but thirteen to be the number to bring on the day of truth, God's judgment of your power of remembrance!

37. Children of the people of the dawn, in separating you from the people of the book, God meant you to be the reminder that wisdom is already perfect in your bodily form of time.

LORD BUDDHA

38. In remembrance, many messengers did he send you, many fires did he light high atop the mountain for you to see. And one special messenger did he send, one special witness of the dawn.

39. In India, at the midpoint of the seventh baktun, the very center of the mystic cycle, thirteen baktuns in all, Lord Buddha did awaken at the dawn, the morning star, the tree, the Earth, his witnesses of illumination. For seven weeks, he sat beneath that tree. Never moving, he traveled the seven directions and visited with his mind every realm of God's vast creation, only to learn the turning of the Wheel of the Law.

40. Withstanding all efforts of the evil one, he taught unceasingly for nine times five years more, until the age of eighty. All mind teachings did he give; the unwritten Book of Enlightenment did he leave with the Earth. His last turning of the Wheel of the Law was the teaching of the Wheel of Time. Given at the request of King Suchandra of Shambhala who traveled far from Central Asia to receive this teaching, the teaching of the Wheel of Time closed the life of Lord Buddha.

41. "All composite things are impermanent," declared Lord Buddha at his death, "Be a lamp and a refuge unto yourself, look to no outer authority but yourself!" The fire of Lord Buddha's illumination lit many lamps. The Book of Enlightenment he left with the Earth is a book for all to know in silence with the Earth.

42. In Shambhala did King Suchandra transmit the teaching of the Wheel of Time, Kalachakra, as it is called. Invoking the Nine Great Lords of Galactic Destiny, Shambhala prospered in abundance and wisdom. When came the seventh ruler after King Suchandra, Queen Visvamati, the people of Shambhala ascended as one into the paradise of the fifth dimension, where their wisdom continues to water the rivers that flow beneath the gardens of the righteous.

43. Integrating the power of the five, which is the center, with the power of twelve, which is the root of the cube, the Kalachakra is also the cycle of sixty years (5 x 12). By the Law of the Cube, which is the power of sixteen, foursquare or 7 plus 9, sixteen cycles

of sixty years is the appointed time of prophecy, the prophecy of Kalachakra, which is the time of the day of judgment.

44. So it was that after the arrival in Tibet of Buddha's special voice, Padmasambhava, late in the tenth baktun, that the Lords of Shambhala determined to release the teachings of the Wheel of Time among the people of the dawn inhabiting Tibet. Thus it was that the Wheel of Prophecy turned the first of these sixteen cycles in A.D. 1027 and completed the sixteenth of these 60-year cycles in A.D.1987, in partial fulfillment of the Harmonic Convergence of all prophecy.

45. 0 people of the dawn, do not doubt. The appointed day is come.

THE HEPTAGONON OF MIND

46. People of the dawn, people of the book, children of the day of truth. To safeguard as long as possible the teachings of the Original Ones from the confusion of the Tower of Babel, God divided the Earth by its one ocean into great island masses called continents. And most far from Babylon was Amerrikua, and also distant was Australia and the Island Kingdoms of Polynesia. Even in Africa, close to Babylon, for many great cycles were the people of the dawn protected in their natural wisdom.

47. But inexorable is my count of days, inexorable the rolling of the Wheel of Time, inexorable the Law of the Cube.

48. Telektonon is the name of the blessing received by those who master the Law of the Cube. Great is the power of God, whose power and blessing are ever close and near, foursquare the manifest action of radiance from the divine intersection of God's presence: divine mind, divine spirit, divine will, divine source from which the Cube is sprung. Foursquare the Cube, the measure of Telektonon, one vast, far-spreading word that is no word at all, but number multiplying itself from within God's unending meditation, which we choose to call creation.

49. From one intersection, six directions plus the seventh, the moving center of time, the navel of Heaven whose cord is a fiber called Kuxan Suum. From the navel of Heaven to the solar plexus runs the Kuxan Suum, highway that reaches to the roots of the stars, passing through each of the heavenly dimensions.

50. I who say this, know, for I am Pacal Votan, who left for you a talking stone, Telektonon. Time's special witness am I, God's spy holding vigil, keeping the sacred count of days, exposing to you the lie of Babylon, the falsification of the Cube into the Tower of Babel!

51. Who now but I can tell you that seven are the directions of the Cube, the Heptaganon of Mind: twelve are the gates, sixteen the powers; moved by the nine great powers of time, these sixteen powers become the number of the elect of the Cube, 144. Multiplied by the millennium, 144 becomes 144,000, sacred number of days I laid for prophecy to know during my first baktun count.

IMPERIAL BABYLON

52. Children of the book, even before the close of my first baktun, twenty generations from the year 3113 B.C.,the foundations of the Tower of Babel were laid. Captive now were the 144,000 within the Earthly prison of Babylon's materialism.

53. Yet, by my devotion and power of meditation, from deep within the Earth, aided by Bolon Ik's perseverance on far Uranus, Earth's harmonic twin, I kept the sacred count of days, I watched over the movement of the sacred march of kin.

54. Four more baktuns passed, and Babylon's power was swollen with the loot of Empire. Despite the righteousness of Abraham and the Law of Moses, the shadow of the Tower of Babel only increased in size and darkness.

55. Came the sixth baktun and Imperial Babylon was complete. Its seal of false time and power, taxation, and armed expanse had fulfilled Iblis's desire to degrade and ruin all humanity by making wrong fair-seeming. Fair-seeming now to amass wealth and power; fair-seeming to make a count of time by twelve months; and fair-seeming to regard the thirteenth moon with superstition and contempt! Fair-seeming to gather taxes and to pay them; fair-seeming to make war for the power of King's; fair-seeming that birth and death must be paid for; fair-seeming that all power come from the priests, Iblis's most cherished of men.

56. 0 people of the book, lost to you was all memory of the Law of the Cube, slavery became your lot! But I am Pacal Votan, time's special witness. Even before the coming of the second special messenger, Christ the Apostle of Love, by my free will and my knowledge of the power of seven, I laid claim to the Seven Seals of Prophecy that on the day of truth, Iblis's curse would be finished and the righteous would triumph. And now the day of truth is come. Telektonon, the talking stone, now speaks in a voice for all to hear.

57. By the seventh baktun, the Seven Seals of Prophecy were stored in Earth's special lodestone of truth, whose custodian am 1.

58. By the eighth Baktun, Iblis had caused the Tower of Babel to speak more tongues in a growing clash of empires. Into this confusion came the Apostle of Love, crucified for driving the moneylenders from the Temple, misunderstood by the people of the book, finally to be absorbed by the Priests of Babylon, now Roman by tongue, who use this Christ as their emblem to spawn Iblis's greatest evil, the total usurpation of Earthly Time.

THE BOOK OF DARK PROPHECIES

59. One special voice did this Jesus have, a man named Saint John ofPatmos, in whom the gift of prophecy was fulfilled. From my ark of universal time, Earth's special lodestone of truth, rock of Heaven, attained by thirteen tones, I guided Saint John's hand by the mystic power of seven. And so was sent to the world the Book of Dark Proph-

ecies, Revelations, the Apocalypse, twenty-two mystic chapters, the first thirteen mirroring my thirteen great baktuns, nine more for the Lords of Time, seven of these for each of Seven Years of Prophecy, and the last two to complete the visionary power of the righteous of the Cube: 144,000 times thirteen.

60. To those who can read they will find Iblis's numbers 1,260 and 666, well known on the day of truth, for 12:60 is the ratio of the false time that makes martyrs of the righteous, and 666 the number of the beast who captures my thirteenth baktun.

61. Children of the day of truth, children of the dawn, people of the book, all this can you hear in the stones of Palenque where in the tenth baktun I took pure human form. Of the twenty-seven books of the New Testament, the twenty-seventh is Revelations. Twenty-seven steps ascend to the Palace of Bolon Ik. This palace, New Jerusalem, is the mystic power of Telektonon, the twenty-eighth step, the power of seven sanctified foursquare.

62. Twenty-two chapters of Revelations are the twenty-two kin complete in Bolon Ik: thirteen for the power of time, nine for the Nine Lords of Time, whose forms still guard my ark of stone deep within the ninefold temple of the Cube of the Law. Perfect was the time of my coming, kin 1, 366, 560. Perfect was the time of my going, kin 1, 385, 540.

63. Installed in the House of the Serpent, my coming was commemorated by the departure of the third messenger, the special messenger of the day of truth, the Apostle Muhammad, who left for the righteous of the Earth the Book of the Righteous, the Holy Quran, clear signs to understand.

64. As Buddha taught so pure one mind, so Muhammad taught so pure one God. Submission to the will of God is at the center of the Law of the Cube. Truly for the righteous there is only the straight way, the path of basic goodness, laid out in the heart as obedience to God's will, the divine plan unfathomable to those who cry, "reason alone can save us!"

THE PROPHECY OF THE SEVEN GENERATIONS

65. I am Pacal Votan, witness of time. Telektonon is my gospel. The talking stone of unifying prophecy is my legacy intended for that special messenger who understands the meaning of my numbers.

66. By my symbolic channel of communication called Telektonon did I intend this prophecy to be discovered and recovered. Once forty years had elapsed from the time of the discovery of my Uranian crypt, then would come the recovery, the recollection by my special agent of the numbers rehearsed and repeated to announce the day of truth.

67. Perfect was the time of my coming. Perfect was my mission. Perfect was the time of my going. Perfect is the discovery of my prophecy. Perfect is the Telektonon, the little book the angel of the Lord made Saint John of Patmos taste and eat, which you now possess, a treasure for the day of truth.

68. What you witness by these words is the last message I gave to my people, the message of 9.13.0.0.0, heard from my ark of stone through the Telektonon, Earth Spirit Speaking Tube. To my people I declared:

69. "Seven katuns are there to follow me. Seven generations, each one guarded by a solar witness taking account of what you do, each solar witness sealing your time with a prophecy to be known as the Book of the Seven Generations. And this book is to be opened for the day of truth.

70. "After the seven generations, the end of the baktun. Ten baktuns gone, the glorious Age of Maya gone, the Long Count of my days to be completed at 1,440,000 kin, the mystic number of the elect multiplied by ten.

71. "Then will come the three baktuns of Babel, the coming exile of 12:60 time. Thirteen years after this tenth baktun shall come the last prophetic round: thirteen cycles of Heaven, each fifty-two years, followed by nine cycles of Hell, each also fifty-two years. When the third round of Heaven begins, the Messenger of the Last Call will come to you, Quetzalcoatl-Kukulkan, the prophet by name.

72. "And when the thirteenth Heaven cycle is over, then will come the complete destruction of all we are and know. Before the twelfth baktun is over, two priests bearing false witness, ornamented with the sacred numbers five and thirteen, will see to it that the thirteenth baktun will be the end of time.

73. "Unrelenting will be the roll of the Nine Hells into the abyss of fire and madness. In the time of the last Hell, though you will be declared free, free you will not be. Ten Kings in succession will mark the climax of time. Seven years will follow the ending of the last Hell. Then will sound the angel of the seventh trumpet, the seven thunders will roll, the beast of seven heads called G-7 will place his mark on your foreheads and hands, the false one from Babylon will return to be embraced by the 11 Serpent. Then the day of truth will come, the Seven Years of Prophecy."

TIME'S SPECIAL WITNESS

74. People of the dawn, people of the book, children of the day of truth, many messengers have been sent to you, many prophets have been given to you. A Book of Enlightenment has been placed in the Earth for all to read in communion with the Earth. A Book of Dark Prophecies has been left for you. A prophecy of thirteen Heavens and nine Hells to accompany the Book of Dark Prophecies has also been left for you. A great prophet and messenger has left you clear signs to understand and a book of unassailable righteousness, the Holy Quran.

75. As the special witness of time, I have left for you my talking stone, Telektonon, breath of precious Bolon Ik, and have sent you both a prophet, Quetzalcoatl of sacred Xochicalco, and for the day of truth I have appointed also a special messenger who can hear my talking stone and write and explain its numbers and its meaning for you, children of the righteous.

76. Do not doubt any of this. When the moment comes for him who is to be the eleventh in succession, to succeed the one, 11 Serpent, then join the believers and begin the prophecy that liberates from all Kings and successors.

77. Ten witnesses I place around my tomb, ten Uranian emissaries, one each for each of ten baktuns. Of these am I the eleventh. Who would be the eleventh in the final succession of the Kings of Mexico must own me as the eleventh, then will all go well.

78. Six messengers did I place on my talking stone of prophecy: three above, the messengers Lord Buddha, Muhammad, and Christ; and three below, Padmasambhava, Quetzalcoatl, and Saint John of Patmos. Of these am I the seventh.

79. Pacal Votan am I, time's special witness, messenger of the Telektonon, instrument of the seventh angel, I declare again and again: All is number. God is a number. God is in all.

WAR OF THE RIGHTEOUS

80. Look carefully at my stone and listen: ten messengers, 24 signs, for ten are the number of orbits of planets around this star, Kinich Ahau, your Sun. From my point of origin, your star is designated 24, number of the circuit of externalizing intelligence. If you are of the righteous, then in this is a sign for you of your star mission.

81. And from each of the three oracle mouths of the arms of the cross of my Kuxan Suum, you will find twenty-four rays repeated three times, one-half the number of the elect (3 x 24 = 72). Add to this 3 times 11 (33) and the number is 105, the difference between the number of days in your solar orbit, 365, and the number of kin in my sacred count, my galactic spin, 260.

82. 13:20 is the ratio of natural sacred time. 12:60 is the ratio of the false time of the Tower of Babel. 13:20, thirteen moons, twenty fingers and toes. 12:60, twelve-month year, sixty-minute hour. Children of the day of truth, in this is a sign for you to discriminate between the power of the evil one who seeks to trap you in his machine, and the power of the righteous who need nothing but that with which God has endowed them: their body of time and their natural path synchronized by thirteen moons.

83. Children of the day of truth this is your only decision, for God knows and sees all that is in your hearts. People of the dawn, people of the book, on the hour of judgment unify yourselves in the only way you can: in time, as time, through time. For this in the year of kin 144, Telektonon is revealed to you, God's plan for peace on Earth, the last and only hope for spiritual renewal and salvation, immediate acceptance and adoption of the twenty-eight-day, thirteen-moon way, the calendar Telektonon. "And he had a name written that no man knew but himself." (Revelations 19:12) And that name is Telektonon.

84. Children of the day of truth, people of the dawn, people of the book, foursquare is my talking stone, invisible its design, its crystal lacing of star histories met in my human form. Time's special witness am I seeking apostles of time to organize the day of truth

into the revelation of God's redemption. Universal forgiveness awaits those who understand God's plan, a common time of twenty-eight days, thirteen moons, begun together at the appointed hour, on the day called Lunar Moon, the first day of the second year of prophecy.

85. Two solar faces there are upon my talking stone, the one an icon of my solar shield, Galactic Sun, the other, Lunar Sun, an emblem of the perfect lunar timing of Earth's solar orbit.

86. Children of the day of truth, the hour of judgment has come for you. How much longer do you need to suffocate in the Babylonian exile of 12:60 time? My children are the oppressed. Is it not time for the war of the righteous to restore equality? Why not wage the war then that destroys altogether the old time? Why not smash the caskets of the Babylonian wine of fornication in a single stroke?

HOLY VICTORY MARCH

87. 0 children of the day of truth, people of the dawn, people of the book, in your origins you were one blood, today the hour of judgment demands you become one again, unified in time. Who among you will join my apostles of the Telektonon? Already the gift has been given. Already we left for you the 13:20 tool, my sacred count of days, 260 kin, to turn the solar-lunar wheel of365 days. And when prophecy was vindicated at the conclusion of the ninth Hell, we sent among you the perfect form of this gift, Dreamspell, containing the message of the thirteen moons.

88. But this was not enough, the seventh trumpet had yet to sound, and so it did in the fortieth year following the discovery of my Uranian ark of stone. And now my prophecies are revealed. The Mayan Apocalypse of kin 144, Yellow Magnetic Seed, turns the seventh year of karmic destiny into the opening of the first of my seven seals of prophecy.

89. In this seal foursquare, all prophecies converge. The Beast of the G-7 stands revealed. The Babylonian Vatican is exposed. In the rainbow dream vision 144,000 of the elect are called again to meet, gathering together in circles to listen, to sing, and to dance to the song Telektonon.

90. 0 children of the day of truth, people of the dawn, people of the book, seven is my sacred power. Foursquare seven is 28, the number that, perfectly followed, opens Heaven's gate. Walking together the sacred thirteen moon, 28-day way, you will be joined to God's command, a holy victory march of the righteous to restore sacred order to this troubled Earth and to recover your lost powers.

91. Four powers of seven are given to you to be your comfort in the Victory March, one power for each of four perfect weeks, every twenty-eight days. By the first power of seven, claim your power of prophecy, by the second power of seven, maintain your power of prophecy; by the third power of seven, proclaim the victory of prophecy; by the fourth power of seven, become the victory of prophecy!

92. 0 children of the day of truth, 144,000 times thirteen is an army of the righteous. Learn again the count of sacred time and join this army. 0 children of the day of truth, realize that everything about the old 12:60 time is now become a garment of false being, a moral corruption, a banquet feast for the evil one.

THE STORM OF NON-EGO

93. 0 children of the day of truth, children of the people of the book, in the Storm is the sign of God's power. To the Storm is assigned the power of nineteen, the mystic saturation of all number. One hundred fourteen Suras, nineteen times six, the power of the Cube, are the number of Suras in the Holy Quran. Twenty-two years after the finding of my Uranian crypt, Telektonon, came complete revelation of the Quran's power of nineteen, Allah's mercy. Nineteen more years then to unfold the karma of Allah's prophet besieged by Babylonian conspiracy. Then comes the destined year nineteen, kin 144, hour of prophecy's convergence, moment of the day of truth.

94. Let the 124,000 messengers call forth a remnant of 20,000 more; let each of these sound seven trumpets, seven times. Let these seven times seven trumpets call for a following of God's perfect plan. Mark seven times seven years since the evil one showed his fiery face at Hiroshima. Be honored by God's cancellation of Iblis's power of moral oblivion. Let the storm of God's power of nineteen cleanse with cosmic mercy the blood of all martyrs from the thrones of Kings, and let these thrones themselves be dissolved by the pure water of sacred time flowing through the gardens of the righteous.

95. I am Pacal Votan, time's special witness, revealer of the Cube of the Law, devoted patron of the mystery that is woman, the consummation of the telepathic power of twenty-eight, known to me by name of Bolon Ik.

96. Pacal Votan am I, enigma to your men of reason. My existence is proof of the workings of higher law. Telepathy is participation in God's knowing, but is no cause to claim full knowledge of His powers. Prophecy too is natural law, the complement to God's mercy.

97. 0-19 is my code. In it are all demonstrations of the wisdom that is always close and near, but that comprehends the web of galactic being and all forms of its natural orders in time. Just as nineteen is the power of God's mercy, so zero is the fullness and emptiness all at once that characterize the nature of mind and all it can know.

98. Lord Buddha called this power of zero Sunyata. The special voice of Buddha, Padmasambhava, whose life span followed mine, exactly as Muhammad's preceded it, knew this Sunyata to be the basis of non-ego.

99. If you would know me and all that I witness for you in this hour of judgment, children of the dawn, people of the book, then practice the being that is non-ego.

THE ECSTASY OF DELIVERANCE

100. Because I repose on Telektonon, the mother of all prophecy, mine is the ecstasy of deliverance. With a mind of non-ego clasped to the heart of God I have sent out my

message of the Mayan Apocalypse. By relinquishing the calendar of twelve and leaving the prison of mechanized time, God's mercy will come swiftly to you.

101. Thirteen moons, twenty fingers and toes, thirteen joints, four limbs, five senses do you already possess. God's knowing and power of movement are already in you like a mother pregnant with child.

102. Why tarry now? When a house is burning, scurrying for your possessions will only cost you your life. This house that is burning is Babylon, the 12:60 way of life, which is now destroying your biosphere and poisoning everything about your life. Do not linger now fondling your machines. This is the Day of Judgment. If you can remember, leave this burning house and know that a better way has already been prepared for you, a holy victory march, my seven years of prophecy, Telektonon, the sacred revelation of time.

103. The Cube of the Law is awaiting its construction through the collective mind, spirit, and will of you, 0 children of the day of truth. Iblis, Satan, the evil one is none other than your ego clinging to the fatal lures of Babylon. God knows nonetheless exactly what is in your heart. Why not, then, become an apostle of the holy victory march? The ecstasy of deliverance is meant to be shared by all.

THE PROPHETS OF PEACE ARE AWAKENING

104. Pacal Votan am I, time's special witness am I, who bequeaths to you a talking stone, a legacy of place, Nah Chan, House of the Serpent, by prophecy known as Palenque.

105. And at Xochicalco, too, you will find stone utterances of my gospel left by command of my apostle, Topiltzin Ce Acatl Quetzalcoatl, who closed Christ's first millennium, as now my prophecy is come to close Christ's second millennium.

106. 0 people of the dawn, people of the book, children of the day of truth, make yourselves as one again and do not doubt the accuracy of the appointed hour on the day Lunar Moon! Synchronize now, and in all humility accept God's plan, twenty-eight days, thirteen moons, plus one day for deliverance and forgiveness.

107. Pardon now in public your enemy's indiscretions, and make full confession of your own transgressions. If you are sincere, God will see this in your heart and by His mercy many will follow your way; and if you proclaim for the cause of righteousness and truth, a new beginning and a new time, Telektonon, the thirteen moon way, and you enjoin others to do likewise, then God will know this, too, and make you a great general in the holy victory march.

108. And, if you have means and wealth, and you hear these words, or have explained to you the curse of 12:60 time and the blessing of 13:20 time, then do not doubt it and practice charity. Provide for the children orphaned by war and provide for the reconstruction of the Earth, that the practice of art and culture may flourish once again. Practice such charity with zeal, for soon you shall see an end to money. No more will flow the drunken wine of Babylon's fornication, and then what will you be with your paper credits and your useless machines?

109. The prophets of peace are awakening. Truly, the hour of judgment is come. Among the angels am I known as the mysterious benefactor of the righteous. Will you throwaway this opportunity, too? Beware for now the fire that consumes all falsehood is raging.

THE WIZARD'S HOARD OF THE LORE OF DEATH

110. People of the dawn, people of the book, children of the day of truth, because I am time's special witness, everything about my talking stone of prophecy is in fulfillment of God's divine plan.

111. Mine is the teaching of the 12:60 way of exile and the 13:20 way of redemption. Exactly 1,260 years passed from the dedication of my temple and closing of my Uranian crypt, A.D.692, 9.13.0.0.0, to its discovery and reopening in A.D.1952, 12.17.0.0.0. Another five times seven years, the numbers of my sacred ratio passed before the closing of the ninth Hell, A.D.1987, commemorated by the sacrifice of 3 Monkey, the first of four sacred signs on the western edge of my great talking stone. In this sacrifice was a sign of the death and transcendence of the way of the people of the book, "Joshua," and the people of the dawn, "Maitreya."

112. Eleven sets of triple disks, thirty-three in all, will you find upon my stone, for 33 is the number of the initiate, the middle harmonic of 65 that constitutes the Tzolkin, my sacred count of thirteen times twenty. All clear signs have I left for you, two borders of stars, the host of the Nine Lords of Time repeated by number on each side, top and bottom of my stone, a ledger of star histories complete in my form.

113. But especially would I have you look at Mars and consider again the disposition of the thirteen sacred signs placed around the edge of my stone, from 8 Ahau, my seal of truth, to 13 Cimi, the galactic closing of the wizard's hoard of the lore of death.

114. Ten emissaries celebrate the glory of my gifts for you, signs of peace from other worlds that beckon you to awaken from your sleep of Earthly Hell to join yourselves to God's command, Telektonon, the 28-day, thirteen-moon way and find in that count of days a path that leads directly to the paradise that is the repose and reward of the righteous.

115. One hundred forty is the number of the Telektonon, perfect its ratio 5:7 (28 x 5 = 20 x 7), the same as my sacred ratio 260:364(+1)

116. All is number. God is a number. God is in all.

SEVEN PERFECT ORACLES

117. People of the dawn, people of the book, children of the day of truth, this completes my testimony, I, Valum Votan, holder of the solar shield, protected have I been by the perfect love of Bolon Ik, who has stored my prophecy until this moment of release.

118. Seven perfect oracles have I given you, a perfect calendar of thirteen moons, an instrument to renew your spirit and your powers of Prophecy, Telektonon, and a book

of knowledge for you to penetrate the forgotten history of your star, Dreamspell. Also have I sent two messengers who bear witness to my truth, and thirteen perfect signs.

119. Now is the time of my prophecy. Now is the day of truth. Now is the opening of the seven seals. Now is the sounding of the seven trumpets. Now is the hour of judgment. Now is the song of the 144,000, the seed army of the righteous.

120. When the Lunar Moon has overflowed its banks, the G-7 will be no more.

121. When the Electric Wizard arrives, gather in banners of righteousness.

122. When arrives the Self-existing Storm, you will be fortified with spiritual abundance.

123. When comes the Overtone Seed, neither money nor priests will besiege you any longer, but the Earth will sing in harmony with your righteousness, Babylon will be no more, the Law of the Cube will be fully rehearsed in the hearts of the righteous.

124. In the sign of the Rhythmic Moon, senses will open to the manna of Heaven; no where will you find any longer signs of the evil one; a cosmic race will you be once again.

125. And when comes the seventh year, the Resonant Wizard will seal the Heavens and the Earth with the glory of all prophecy, the redemption of all prophets, messengers, apostles, and witnesses of truth.

126. Five years then will you have to close the cycle ofthe Seed, and another eight, thirteen years in all, to prepare for the coming of the Galactic Seed, 2013 Arcturus Dominion, the fulfillment of the star cycle of Valum Chivim, witnessed by the special agent, Pacal Votan, to the glory oflove, Bolon Ik, and on behalf of the mercy of God's divine plan, Telektonon, Cube of the Law, the mighty talking stone of prophecy.

"Man is one. Culture is indivisible."
-ALBERTO Ruz, 1952, 12.17.0.0.0.

Transcribed 12 Seed, kin 64,
Resonant Moon Day 13,
Warrior's Cube 7, 0 Yax
Yellow Magnetic Seed Year, kin 144,
First Year of Prophecy

Blue Spectral Monkey/White Solar Wind
Tepoztlan, Morelos, Mexico

▼



Appendix IV

The Nineteen Code

THE MYSTERY of the motives of the hijackers, who were instrumented by divine will, if not by biospheric necessity, to catalyze the Inevitable Event, lies in their very number: nineteen. While the nineteen is related to the Quranic verse 74:30, "Over it is nineteen," and can be interpreted prophetically, the Law of Time confirms the Quran in demonstrating that the number nineteen possesses a supreme and indeed inviolable value. The Law of Time validates all that is true, and contains within it the mathematical confirmation of all systems of thought as different facets of the same synchronic order.

The Law of Time is based on the mathematical code of the Harmonic Module, itself a function and a demonstration of the 13:20 ratio. The vigesimal mathematics of the 13:20 frequency is known as the 0':'"19code, which is written with a simple dot-bar notation. As such the 0-19 code is a whole number system in which the count is not 1-9 but 1-19, and the positional zero represents a factor of 20 rather than of 10. As the demonstration of a radial mathematical code, the number 19 plays a singular role in the 13:20 matrix. As the largest compound prime number of the 0-19 count, within the context of this count 19 has certain unique properties and values. It may be asked: why 19?

First of all, let us consider the theological dimensions of the number 19 as hinted at by the Quranic verse 74:30. Long an enigma to scholars of the Quran, it was only through the genius of an Egyptian scientist, aided by a computer, that the meaning of the verse was finally revealed as the nineteen code-an intricate mathematical system based on the number 19 underlying the entire structure of the Holy Quran.

"For the first time in history we have a scripture with built-in proof of divine authorship-a superhuman mathematical composition."[1]

The contribution of Rashad Khalifa (1935-1990) to the role and meaning of the Holy Quran for the entire modem world is without parallel. The martyrdom of this genuine seeker and messenger needs to be redeemed and placed in its proper light. According to Dr. Khalifa, "Nineteen is the common denominator throughout the Quran's mathematical system." "This is one of the greatest miracles" (74:35). To summarize in his own words, Dr. Khalifa states:

> The Quran is characterized by a unique phenomenon never found in any human authored book. Every element of the Quran is mathematically composed-the suras, the verses, the words, the number of certain letters, the number of words from the same root, the number and variety of divine names, the unique spelling of certain words, the absence or deliberate alteration of certain letters within certain words, and many other elements of the Quran besides its content. There are two major facets of the Quran's mathematical system: (1) The mathematical literary composition, and (2) The mathematical structure involving the numbers of suras and verses. Because of this comprehensive mathematical coding, the slightest distortion of the Quran's text or physical arrangement is immediately exposed.[2]

Like the Law of Time, which could only have been discovered after the opening of Pacal Votan's tomb, in A.D. 1952, the nineteen code of the Quran could only be discovered and unveiled over a twenty-two-year period between 1968 and 1990. Why? Because only with a modem computer could Dr. Khalifa subject every last word and letter of the Quran, in its Arabic original, to the rigorous analysis necessary to expose its mathematical perfection. As Dr. Khalifa writes in his footnote to 10:20 ("They say, 'How come no miracle came down to him from his Lord?' Say, 'The future belongs to God; so wait, and I am waiting along with you.'"):

> 10.20: In retrospect we see now that the Quran's miracle, indeed "One of the greatest miracles" (74:35), was divinely predestined to be unveiled 14 centuries after Muhammad. In view of the current condition of the traditional Muslims, ifMuhammad had been given this miracle, those Muslims, who are already idolizing Muhammad beside God, would have worshipped him as God incarnate. Additionally, this miracle is obviously designed for the computer age, and to be appreciated by mathematically sophisticated generations.[3]

The phenomenon of the intricate patterning of the nineteen code as witnessed, for example, in the 19 x 142 (2,698) occurrences of the word *God* in the Quran, writes Khalifa, "alone suffices as incontrovertible proof that the Quran is God's message to the world. No human being(s) could have kept track of 2698 occurrences of the word 'God,' and the number of verses where they occur."4 One must bear in mind that the Quran was revealed in a time of primitive simplicity over a twenty-three-year period so that the suras and verses were separated in time and place, while the chronological order of the revelation of the suras is not at all the same as their final format. Moreover, the miracle of the nineteen code is not limited to the appearance of the word God, but is vast, intricate, and comprehensive. Dr. Khalifa lists a set of nineteen "simple facts" that confirm the Quran's mathematical coding. The "simple facts" are those not requiring a calculator or computer to be ascertained. We hereby reproduce these "simple facts," as they are presented in Appendix 1 of *Quran: The Pinal Testament* (all references to letters and words are to the Arabic original):

1. The first verse (1:1), known as *"Basmalah,"* consists of 19 letters.
2. The Quran consists of 114 suras, which is 19 x 6.
3. The total number of verses in the Quran is 6346, or 19 x 334. (6234 numbered verses and 112 unnumbered verses *[Basmalahs].* 6234 +112 = 6346. Note that 6 + 3 + 4 + 6 = 19.
4. The *Basmalah* occurs 114 times, despite its conspicuous absence from Sura 9 (it occurs twice in Sura 27). 114 = 19 x 6.
5. From the missing *Basmalah* of Sura 9 to the extra *Basmalah* of Sura 27 there are precisely 19 suras.
6. It follows that the total of the sura numbers from 9 to 27 (9 +10 + 11 + 12 . . . + 26 + 27) is 342, or 19 x 18.
7. The total (342) also equals the number of words between the two *Basmalahs* of Sura 27, and 342 = 19 x 18.
8. The famous first revelation (96:1-5) consists of 19 words.
9. This 19-worded first revelation consists of 76 letters, 19 x 4.
10. Sura 96, first in the chronological sequence, consists of 19 verses.
11. This first chronological sura is placed atop the last 19 suras.
12. Sura 96 consists of 304 Arabic letters. 304 = 19 x 16.
13. The last revelation (Sura 110) consists of 19 words.
14. The first verse of the last revelation (110:1) consists of 19 letters.

15. 14 different Arabic letters form 14 different sets of "Quranic Initials" (such as A.L.M. of 2:1) and prefix 29 suras. These numbers add up to 14 + 14 + 29 = 57 and 57= 19 x 3.

16. The total of the 29 sura numbers where the Quranic Initials occur is 2 + 3+ 7 + . . . + 50 + 68 = 822, and 822 + 14 (14 sets ofInitials) = 836, or 19 x 44.

17. Between the first initialed sura (Sura 2) and the last initialed sura (Sura 68) there are 38 un-initialed suras. 38= 19 x 2.

18. Between the first and last initialed sura there are 19 sets of alternating "initialed" and "un-initialed" suras.

19. The Quran mentions 30 different numbers: 1,2,3,4, 5,6, 7, 8,9, 10, 11, 12, 19,20,30,40,50,60, 70, 80, 99,100,200,300,1000,2000,3000,5000,50,000, & 100,000. The sum of these numbers is 162,146= 19 x 6534.

Apart from the "simple facts," through use of his computer, a Hewlett Packard HP-IOOO E-series, Dr. Khalifa demonstrated many more complex levels of the coding of the number 19 throughout the Quran. These findings are synthesized in the Appendices to *Quran: The Pinal Testament*, and are also available in his other texts detailing his research, such as *The Miracle of the Quran.* The net effect of the truly monumental research effort exerted by Dr. Khalifa was the promotion of a highly reformed Islam based on "the Quran, the whole Quran, and nothing but the Quran." It is for this reason that Dr. Khalifa's translations of the Quran are referred to as "the Final Scripture," (1980) and the revised translation (1992) as the "Final Testament." It was also Dr. Khalifa's insistence on the Quran as the sole basis ofIslam that earned him his martyrdom in Tucson, Arizona, on January 31, 1990.

NINETEEN IN THE TWENTY-COUNT POSITIONAL SYSTEM

The Law ofTime-T(E) =Art, where T equals the 13:20 timing frequency ratio-upholds the validity of the research of Dr. Khalifa and graphically demonstrates *why* 19 is the mathematical factor that underlies the Holy Quran.

The fact that the Mayan vigesimal system is known as the 0-19 code, and that in this code 19, and not 9, has the supreme value of being the highest number, absolutely enhances the power and significance of Dr. Khalifa's discovery concerning

74:30, "Over it is nineteen." The supremacy of the value of 19, imperceptible if we only follow the decimal 1O-count, is fully demonstrated when we examine the 0-19 number code in which the numbers 0-19 are reproduced in a 5 x 4 (= 20) matrix, beginning with 0 and ending with 19. In this number set, which also demonstrates the mathematics of the radial matrix, there are ten pairs of numbers radially arranged, each pair of which adds up to 19:

$0+19=19$
$1+18=19$
$2+17=19$
$3+16=19$
$4+15=19$
$5+14=19$
$6+13=19$
$7+12=19$
$8+11=19$
$9+10=19$

In other words, within the parameters of the mathematical matrix in which nineteen is the integer with the highest value, its value completely informs the radial order of the entire vigesimal system. "Over it is nineteen." This is truly astonishing confirmation of the value accorded to 19 in the Quran. If the Quran is the true word of God, then we must expect that even knowledge unknown to Muhammad or Dr. Khalifa would be contained or coded in the Quran. We are referring, of course, to the Law of Time in its mathematical particulars, beginning with its mathematical base of expression, the 0-19 code.

19 = 7: NINETEEN IN THE 0-19 DOT-BAR NOTATIONAL SYSTEM

Just as the number 19 takes on a supreme value in the vigesimal system inconceivable in the decimal system, so the vigesimal order commands its own notational system. The 0-19 dot-bar notational system substantiates the meaning and power of 19 as the prime mathematical, saturated value unit in the twenty count. The dot-bar notational order is a holographic system distinct from the alphabetic system of Arabic numerals by which we write 1-10.

The distinction between use of the two notational orders is profound. This notational order uses only three notational symbols to build up the holographic context of



0	5	10	15
1	6	11	16
2	7	12	17
3	8	13	18
4	9	14	19

Any radially opposite set of numbers always equals 19, e.g., 4 and 15, 0 and 19, 9 and 10, 2 and 17, 11 and 8.

Nineteen is the highest value and the most saturated notation, being the only one with seven notational symbols—three bars and four dots.



Nineteen in galactic notation.
3 bars (3 x 5 = 15) plus four dots (4) = 19

Dot-bar notation system, 0–19 code

the fourth-dimensional number. One dot represents one unit; one bar represents a five-unit order; and a positional zero completes the system. The vigesimal notational system reveals the entire radial sequence of the 0-19 code to be a highly streamlined and aesthetic pattern. Brief contemplation shows that there are two patterned orders consisting of four vertical sets of five units each, and five horizontal sets of four units each. It is seen that nineteen represents the maximum saturation of both the vertical and horizontal orders, and consists of the maximum number of dots (four) and the maximum number of bars (three). It is also visibly manifest that 19 = 7 notational units, the maximum number of units.

The fact that 19 is represented by seven notational units confirms Sura 1, which has seven verses and the first line of which consists of nineteen Arabic letters. However, from the point of view of the Law of Time, 7 is the key implicit mathematical unit in the absolute timing frequency ratio, 13:20-the difference between 20 and 13 is 7, and the midpoint between 1 and 13 is also 7. While Dr. Khalifa is responsible for determining the dominance of nineteen as the mathematical key underlying the patterning and meaning of the Quran, the Law of Time provides an even more profound lens through which to consider Dr. Khalifa's work, by placing nineteen in a superior (vigesimal) mathematical and theological context.



1	21	41	61	81	101	121	141	161	181	201	221	241
2	22	42	62	82	102	122	142	162	182	202	222	242
3	23	43	63	83	103	123	143	163	183	203	223	243
4	24	44	64	84	104	124	144	164	184	204	224	244
5	25	45	65	85	105	125	145	165	185	205	225	245
6	26	46	66	86	106	126	146	166	186	206	226	246
7	27	47	67	87	107	127	147	167	187	207	227	247
8	28	48	68	88	108	128	148	168	188	208	228	248
9	29	49	69	89	109	129	149	169	189	209	229	249
10	30	50	70	90	110	130	150	170	190	210	230	250
11	31	51	71	91	111	131	151	171	191	211	231	251
12	32	52	72	92	112	132	152	172	192	212	232	252
13	33	53	73	93	113	133	153	173	193	213	233	253
14	34	54	74	94	114	134	154	174	194	214	234	254
15	35	55	75	95	115	135	155	175	195	215	235	255
16	36	56	76	96	116	136	156	176	196	216	236	256
17	37	57	77	97	117	137	157	177	197	217	237	257
18	38	58	78	98	118	138	158	178	198	218	238	258
19	39	59	79	99	119	139	159	179	199	219	239	259
20	40	60	80	100	120	140	160	180	200	220	240	260

Nineteen Strand in Harmonic Module

Kin numbers beginning with 19, lower left, are advancing multiples of nineteen, the last being 19 x 13 (247). Actually, the difference between every kin number on this diagonal is a difference of 19.

19 = 260: THE TZOLKIN "OVER IT IS NINETEEN" STRAND

"All is number. God is a number. God is in all."
-DYNAMICS OF TIME, POSTULATE 19.13

The 0-19 code provides the order of 20 in the ratio 13:20. Like the 0-19 radial matrix, the 13:20 ratio is also organized as a radial matrix of 260 (13 x 20) kin or units. As a cycle of 260 days, the 13 x 20 timing matrix is the fourth-dimensional gauge that synchronically unifies the Thirteen Moon calendar. Known by the traditional and ancient Maya as the *Tzolkin* or "sacred count," the 13 x 20 gauge or Harmonic Module is the key to the mathematics of the fourth dimension, or the "Hereafter." Just as the mathematics of the third dimension is decimal-based, so the mathematics of the fourth dimension is vigesimal-based. Hence, the power of 20 as a self-existing proportion (4 x 5 = 5 x 4).

For any frequency to occur two proportions must be coincident. Thirteen, which is a function of the 7 factor, is the proportion that complements the 0-19 vigesimal proportion of 20. Hence the Tzolkin consists of twenty horizontal orders and thirteen vertical orders = 260 kin, which are also arranged in twenty sets of thirteen-kin wavespells, all numbered 1-13 in dot-bar notation. All of the kin in the 260-unit matrix are also individually numbered: kin 1, kin 2 . . . kin 259, kin 260.

Within the 13:20 order of260 kin, 13 sets of20 or 20 sets of 13, only two of the numbers in the vigesimal code 0-19 occur thirteen times: the number 19 and the number 20 (= positional zero). While 20 occurs precisely thirteen times, 19 occurs thirteen times with a remainder of thirteen (13 x 19 = 247 = 260 - 13).

The position and notational order of the thirteen occurrences of the number 19 in the 260-unit Tzolkin create a perfect strand of thirteen units. This 19 x 13 (19 = 260) strand demonstrates the supreme invariability and inviolability of the number 19 in the vigesimal code of fourth-dimensional time.

The purity of the movement of the 13 x 19 strand of the Tzolkin is further augmented by the vigesimal or 20-count manner of writing numbers. Even as transliterated into the Arabic system of writing numbers, it will be seen that in the vigesimal code every multiple of 19 always adds up to 19, a similar power held by all multiples of 9 in the decimal code. In vigesimal notation, the second order units are always multiples of 20 and not 10. Hence 38 = 1.18, where 1 = 20 + 18; or 5.14 = 114, where 5 = 100 + 14.

Finally, while the sequence 1-13 defines the thirteen galactic tones of fourth-dimensional time, the 0-19 matrix is represented by twenty icons and a four-color (4 x 5 = 20) permutation sequence. The combination of color, icon, and tone gives each of the 260 kin a "galactic signature." This completes the description of the Harmonic Modulerrzolkin.

We now present the thirteen multiples of 19 as defined by the 13 x 19 strand running from lower left to upper right in a perfect cross-stitch sequence that reverses the horizontal order of the 0-19 code frequencies. In other words, the first order represented is the order of (1 x 19) 19 (frequency 19, icon Storm), and the last is the



19 x 13 (19 = 260 code):

Each multiple of 19 is listed with a) kin number; b) vigesimal notation; c) galactic signature; d) 0–19 frequency order + tone number (Dynamics of Time Code); and e) number of units away from 20th position:

a. b.	c.	d.	e.
1 x 19 = kin 19 = 0.19	Blue Rhythmic Storm	19.6	1
2 x 19 = kin 38 = 1.18	White Crystal Mirror	18.12	2
3 x 19 = kin 57 = 2.17	Red Overtone Earth	17.5	3
4 x 19 = kin 76 = 3.16	Yellow Spectral Warrior	16.11	4
5 x 19 = kin 95 = 4.15	Blue Self-existing Eagle	15.4	5
6 x 19 = kin 114 = 5.14	White Planetary Wizard	14.10	6
7 x 19 = kin 133 = 6.13	Red Electric Skywalker	13.3	7
8 x 19 = kin 152 = 7.12	Yellow Solar Human	12.9	8
9 x 19 = kin 171 = 8.11	Blue Lunar Monkey	11.2	9
10 x 19 = kin 190 = 9.10	White Galactic Dog	10.8	10
11 x 19 = kin 209 = 10.9	Red Magnetic Moon	9.1	11
12 x 19 = kin 228 = 11.8	Yellow Resonant Star	8.7	12
13 x 19 = kin 247 = 12.7	Blue Cosmic Hand	7.13	13

What is sufficient is to contemplate the *formal inviolability of the number 19 as a constant (strand) within the Tzolkin matrix* as well as its *invariability of form when written in the vigesimal system.* That is, in the pure 0–19 notational system, any multiple of 19 always adds up to 19 and consists of 7 notational units, e.g., 8.11 (= 8 + 11 = 19) = 8 (= 1 bar 3 dots = 4 units) + 11 (= 2 bars 1 dot = 3 units) = 7 units (= 3 bars 4 dots = 19).

order of (13 x 19) 7 (frequency 7, icon Hand), showing again the intimate relation between 19, 13,6, 7, and 20, the key integers of the codes of fourth-dimensional time.

19 = 260, THE SIX SURAS THAT ARE MULTIPLES OF 19

In seeking proof of the Law of Time within the Quranic nineteen code, we need cite but a few examples that can demonstrate from within the nineteen code itself the key mathematical components of the Law of Time. In addition to the number 19, we must look for any of the factors involved in the 13:20 frequency, such as 260, 7, 6-the difference between 19 and 13-and, of course, 13 and 20, or any of the multiples of these integers.

Following the method of Dr. Khalifa, probability analysis of mathematical constituents based on the assumption that certain numbers will be self-verifying, we start our program with the six suras that are multiples of nineteen:

Sura 19	"Maryam"	98 verses
Sura 38	"Saad"	88 verses
Sura 57	"Iron"	29 verses
Sura 76	"The Human"	31 verses
Sura 95	"The Fig"	8 verses
Sura 114	"People"	6 verses
=399, total of sura numbers		=260 verses in six suras that are multiples of nineteen.

= 19.19 vigesimal code

As can be seen, the sum of the six numbers of the suras that are multiples of 19 is exactly 399, or 19 x 21, the maximum factor in the vigesimal 20 x 20 matrix. Expressed in the vigesimal code this number, 399 = 19.19 [19 (x 20 = 380) +19], the only multiple of 19 in the vigesimal code that is written with two 19s, whose sum is precisely twice nineteen, 38, and is written with fourteen notational symbols rather than seven. This unique number, 19.19 (399), verifies "nineteen is over all," by placing 19 over 19 itself. The unique qualities of this most unique of multiples of 19 also indicates why the Quran consists of exactly six times nineteen suras. Six is the difference between the Quranic 19 and 13, the prime number of the Law of Time.

More amazing than the sum of the six suras that are multiples of 19 being 19.19 is the fact that the sum of the verses of these same six suras is 260. This is incontrovertible evidence for the formulation 19 = 260, and substantiates the mathematical patterning of the Quran to include the principle factor of the Law of Time, 260 (= 13 x 20). We are certain that Dr. Khalifa added the verses of these same suras and may have been perplexed at the meaning of the resultant number, 260. Of course, Dr. Khalifa did not know that 260 is the sum factor of the two proportions that create the natural timing frequency, 13:20.

It is also interesting that discovery of the 13:20 timing frequency, December 10, 1989, was made at almost the precise moment as Dr. Khalifa had completed the introduction to *The Pinal Testament,* the summation of his research on the Quranic nineteen code, Ramadan 26, 1409 (December, 1989). This points to the mysterious movement of the Divine Will in establishing the mathematical proof of the Quran. Just as the work of Dr. Khalifa was terminated within a month of his completing the Final Testament, so the Law of Time, which would substantiate and vindicate the Quranic nineteen code, was ordained and propelled into its process of manifestation at exactly the same moment.

Now with the Law of Time the investigation begun by Dr. Khalifa is complete. Just as there are six suras that are multiples of 19 within the Holy Quran, so the key factor of the Law of Time, the number 260, is coded into the sum of the verses of these six suras. The door is opened for entirely new comprehension of the meaning and purpose of the Holy Quran. The Law of Time and the Holy Quran in mutual resonance will establish the proof of the advent and triumph of the Religion of Truth. (9:33,48:28; 61:9)

Most of the foregoing text of Appendix IV is taken from 19 = *260: The Holy Quran and the Law of Time* (1999), an unpublished manuscript by Jose Argiielles.

▼



Notes

Preface

I. Meg Sullivan', "New Age Will Dawn in August, Seers Say. . .," *Wall Street Jou17lal,* June 23, 1987, p. 1. Front-page story on the Harmonic Convergence.

2. For the prophetic tradition of the Chilam Balam, see *The Book of Chilam Balam of Chumayel,* edited and translated by Ralph L. Roys (Norman, Okla.: University of Oklahoma Press, 1967); *The Codex Perez and the Book of Chilam Balam ofMani,* edited and translated by Eugene Craine and Reginald Reindorp (Norman, Okla.: University of Oklahoma Press, 1979); and *El Libro de los Libros de Chilam Balam,* edited and translated by Alfredo Barrera Vasquez and Silvia Rendon (Mexico City: Fondo de Cultura Economica, 1948, 1986). The issue of being a "prophetic messenger" is a touchy one for many people. However, as it is written in the Quran, "In truth we are always sending messengers. . ." (44:5). Messengers, as often as not, are self-revealed and confirmed only by God. In my case, I have been able to trace back the prophetic lineage of the Chilam Balam to Pacal Votan, from whom I have received direct transmission. The method of transmission is similar to that of the *terma* tradition of Tibet. Terma, or "hidden treasure," is left by a sage or prophet to be "discovered" at a precise moment much later in time by one designated to do so. See Tulku Thondup Rinpoche, *Hidden Teachingsof Tibet: An Explanation of the Terma Tradition of Tibetan Buddhism* (Boston: Wisdom Publications, 1997).

3. This phrase is used often by Dr. Rashad Khalifa (1935-1990), whose groundbreaking translation and research of the Quran through the aid of the computer led to the discovery of the intricate nineteen-based mathematical code that underlies this unique text. His work is summarized in his translation of the Quran with its numerous appendices, *Quran: The Final Testament* (Fremont: Universal Unity, 1992). My own studies on this topic have resulted in two works: *Pacal TfJtIlrn and Judgement Day* (portland, Oreg.: Planet Art Network, 1999), and *19 = 260: The Holy Quran and the Law of Time,* unpublished, 1999. See also Appendix IV to this book, "The Nineteen Code."

4. See, for example, Samuel P. Huntington's *The Clash of Civilizations and the Remaking of the World Order* (New York: Simon & Schuster, 1996, 1997); Benjamin R. Barber's *Jihad vs. McWorld* (New York: Random House, 1995, 1996); and Yossef Bodansky's *Bin Laden: The Man Who Declared War on America* (New York: Forum, 1999,2001). These writers, of course, all express a pro-globalization perspective.

Chapter 1

1. John ofPatmos, "Book of Revelation," Chapter 18, "The Fall of Babylon," verses 10, 16-17, 19-20, *The Holy Bible, New International Version*(Grand Rapids: Zondervan Bible Publishers, 1989), 1419-20.
2. Jose ArgUelles, *The Call ofPacal Votan: Time is the Fourth Dimension* (Glasgow: Altaea, 1996), 37.
3. Jose ArgUelles, *The Dynamics of Time: 260 Postulates*(Portland, Oreg.: Planet Art Network, 1999),30.
4. Kareng Koshev, "The Great Rainbow Bridge." Altai: unpublished paper, 2001.

Chapter 2

1. 1. Laptev, *The Planet of Reason:A SociologicalStudy of the Man-Nature Relationship* (Moscow: Progress Publishers, 1973; English translation, 1977),220.
2. V. 1. Vernadsky, "L'etude de la vie et la nouvelle physique" in *Revue generale dessciences,* vol. 41: 695.
3. V. 1. Vernadsky, *The Biosphere*(1926), abridged version (Oracle, Arizona and London: Synergetics Press, 1986), 22.
4. Ibid., 76.
5. Ibid., 77-78, 81.
6. Ibid., 82.
7. Ibid.
8. V. 1. Vernadsky, "Problems in Biogeochemistry II," in *Transactionsof the Connecticut Academy of Sciences*(New Haven: Yale University Press, 1944),487-88,498.
9. v.1. Vernadsky, "Problems in Biogeochemistry II," Postulate 18, 511-12.
10. Jose ArgUelles, *The Dynamics of Time: 260 Postulates*(Portland, Oreg.: Pbnet Art Network, 1999), postulates 3.7 and 3.9, 24, 25.
11. V. 1. Vernadsky, "Some Words about the Noosphere" (1944), quoted in Andrey Lapo, *Tracesof Bygone Biospheres*(Moscow and London: Mir Publishers and Synergetic Press, 1987),69.
12. Ibid., 71.
13. G. E. Hutchinson, "The Biosphere," *Scientific American,* vol. 53, no. 3 (1970): 223. Quoted in Lapo, *Tracesof Bygone Biospheres,*77.
14. P. Duvigneaud, "Noosphere et l'avenir de la vegetation du globe," *Proceedingsof the XII International Botanical Congress,Bruxelles,* 1979, 78. Quoted in Lapo, *Tracesof Bygone Biospheres,* 76.

15. Tango Snyder, editor in chief, *The Biosphere Catalogue* (London and Forth Worth: Synergetic Press, 1985), 103.
16. V. 1. Vernadsky, "Scientific Thought as a Planetary Phenomenon," quoted in Lapo, *Traces of Bygone Biospheres, 73-74.*
17. Vernadsky, "Problems in Biogeochemistry II," 511.

Chapter 3

1. Maria Maroushkina, "Is a Path Beyond Technology Possible for the Western Culture?" Moscow: unpublished research paper, 2000.
2. James Glanz, "Physics' Big Puzzle Has Big Question: What Is Time?" *New York Times,* June 17,2001, p. D-1.
3. Ibid.
4. Dogen, "The Time Being," from *Moon in a Dewdrop: Writings of Zen Master Dogen,* edited by Kazuaki Tanahashi (New York: North Point Press, 1985), 76-77.
5. N. A. Kozyrev, "Possibility of Experimental Properties of Time," unpublished paper, 1967, 35. This paper was taken from the Web site www.kozyrev.ru. Virtually unknown in the West, Kozyrev's work has had an especially great influence on the Novosibirsk School of the Russian Academy of Sciences. See, for example, M. M. Lavrentiev, "Physical Theories (Mathematical Models) Adequate to the Reality-A Necessary Condition for Progress of Natural Science of the XXIst century," in *Searchfor Mathematical Laws of the Universe* (Novosibirsk: Sobolev Insititue of Mathematics, 2001) 29-51, and Irina Eganova, "On the Nature of the Stars: N. A. Kozyrev's Approach and His Results," in *Searchfor Mathematical Laws of the Universe,* 215-76; and M. M. Lavrentiev and Irina A. Eganova, "N. A. Kozyrev's Method of Astronomical Observations: Information from True Positions of Stars, Stellar Systems, and Planets," *Instantaneous Action at a Distance in Modern Physics: "Pro" and "Contra,"* edited by Andrew E. Chubykalo, Viv Pope, and Roman Smirnov-Rueda. (New York: Nova Science Publishers, 1999).
6. Pierre Teilhard de Chardin, *The Future of Man* (New York: Harper & Row, 1959), 183.
7. Quoted in V. P. Kaznacheev, "The General Pathology: Consciousness and Physics," Novosibirsk: Russian Academy of Medical Science, unpublished paper, 2000, 28.

Chapter 4

1. Christos Koneatis, *The History of the World-A 6,000 Year Chronicle of Time* (London: Christos Koneatis, 1997), no pagination.
2. Jose and Lloydine Argiielles, *Dreamspell: The Journey of Timeship Earth 2013,* (Hong Kong: Interlink Productions, 1991), 35.
3. Ibid., 5-9.
4. Ibid., 14-15,60,61.
5. V. A. Ponko, private conversation, Novosibirsk, August 18, 2001.
6. *Epic of Gilgamesh,* translated by Caravan of Dreams Theater, quoted in *The Biosphere Catalogue, 116.*

Chapter 5

1. *Webster's Ninth New Collegiate Dictionary,* (Springfield: Merriam Webster, 1987), 1211.
2. See Jose Argiielles, *The Transformative Vision: Reflections on the Nature and History of Human Expression* (Berkeley: Shambhala Publications, 1975),249.
3. Paul Foster Case, *The Tarot: A Key to the WISdom of the Ages* (New York: Macoy, 1947), 158.
4. Jim Hoagland, "The Faithful Come and Wars Erupt Worldwide," *The Oregonian,* December 24,2001, p. C-7.
5. *The Biosphere Catalogue,* 103.

Chapter 6

1. Mahatma Ghandi, "Gandhi on Calendar Reform," *The Journal of Calendar Reform,* vol. I (New York: The World Calendar Association, 1931): 143.
2. All quotes from the Quran used in this text are taken from Rashad Khalifa's translation, *Quran: The Pinal Testament* (Fremont, Calf.: Universal Unity, 1992). All numeration refers to sura number and verse, which are henceforth indicated in parentheses following the quote.
3. Popular quote attributed to Einstein, source unknown.
4. See Broughton Richmond, *Time Measurement and Calendar Construction* (Lei den, Netherlands: J. Brill, 1956), 19-20.
5. Alexander Philip, *Reform of the Calendar* (London: Kegan Paul, Trench, Triibner & Co., Ltd., 1914), 6-8.
6. "Resolution Adopted by the Fourth General Conference on Communications and Transit of the League of Nations," *The Journal of Calendar Reform,* vol I: 162.
7. Argiielles, *The Dynamics of Time,* postulate 6.4,34.
8. *I Ching or Book of Changes,* translated by Richard Wilhelm and Cary F. Baynes (Princeton: Princeton University Press, 1967), 189.
9. Richmond, *Time Measurements and Calendar Construction, 70-71.*
10. David Ewing Duncan, *Calendar: Humanity's Epic Struggle to Determine a True and Accurate Year* (New York: Avon Books, 1998),307.
12. Richmond, *Time Measurements and Calendar Construction, 16.*

Chapter 7

1. Pierre Teilhard de Chardin, *The Phenomenon of Man* (New York: Harper & Row, 1955),288
2. For an enlightening look at the subject of *triskaidekaphobia,* see Jonathon Cott, *Thirteen: A Journey into the Number* (New York: Doubleday, 1996).

Chapter 8

1. Star Roots, 13 *Moon Natural Time Journal* (Manson's Landing, British Columbia: 2001), no pagination.

2. Ben 4 and Ben 5, 13 *Moon Natural Time Calendar, Ancient Science for the Art of Now* (Newport, Oreg.: Skytime, 2001), no pagination.
3. Star Roots, 13 *Moon Natural Ttme Journal,* no pagination.
4. "Golden Age of Miracles and Heaven on Earth," *National Examiner,* November 29, 1988, p. 17.
5. *National Geographic Magazine,* publicity blurb, 2001.
6. "Tracking the Hijackers," *The Oregonian,* October 4,2001, p. A-12. See also Appendix Iv, "The Nineteen Code."
7. Muhammad Husayn Haykal, "Islamic Civilization as Depicted in the Qur'an," in *The Life of Muhammad* (Indianapolis: American Trust Publications, 1993),518.
8. Ibid., 518-19.

Chapter 9

1. See, for instance, Dan Oldenburg in the *Washington Post's* full-page article, "The Harmonic Convergence Revisited," May 4, 1990, p. D- 5.
2. *Nuestra Civilizacion Frente a la Reforma del Calendario* (Our Civilization Confronted with Calendar Reform) (Buenos Aires: Casa Editora Sudamericana, 1944), 6.
3. F. H. Colson, *The Week: An Essay on the Origin and Development of the Seven-Day Cycle* (Cambridge: Cambridge University Press, 1926), 2.
4. Quoted in Jose Argiielles, *Charles Henry and the Formation of a Psychophysical Aesthetic* (Chicago: University of Chicago Press, 1972), 128.

Appendix I

1. *San Jose Mercury News,* quoted on book cover of David Ewing Duncan's *Calendar, 1998.*
2. Duncan, *Calendar,* 289.
3. Philip, *Reform of the Calendar,* 101-2.

Appendix II

1. Charles Muses, *Destiny and Control in Human Systems: Studies in the Interactive Connectedness of Time (Chronotopology)* (Boston- Dordrecht- Lancaster: Kluwer-Nijhoff Publishing, 1984), 20-21.

Appendix IV

1. Rashad Khalifa, *Quran: The Final Testament,* (Fremont, Calif.: Universal Unity, 1992), 375. All further quotes from the Quran and from Rashad Khalifa are from this same work, which in addition to containing the complete Quran in translation also includes thirty-eight Appendices summarizing Dr. Khalifa's research.
2. Ibid., 375.
3. Ibid., 123.
4. Ibid., 375.

Glossary

THIS GLOSSARY IS constructed to aid the reader in developing a more systematic and technical comprehension of the Biosphere and the Law of Time. Though by no means exhaustive, it is hoped that the terminology used in the text is herein defined in a manner appropriate to cultivating a noospheric point of view.

13:20 timing frequency: Fourth-dimensional timing frequency mathematically expressed as the ratio constant .13:20; universal frequency of synchronization by which the universe is maintained in synchronic order; basis of Law of Time; codified as 260-unit 13:20 matrix of Harmonic Module, coordinates Thirteen Moon/28-Day calendar with synchronic order.

12:60.timing frequency: Artificial, purely third-dimensional timing frequency based on combination of irregular twelve-month calendar and mechanistic sixty-minute hour, adoption of which results in unconscious program within the human mental order, causing the species to deviate altogether from the natural biospheric order, resulting in the technosphere.

astronomical time: Measure of time in third-dimensional physical space without regard to intrinsic harmonics of the synchronic order, usually interpreted as duration and, based solely on matter that is in constant state of entropy, results in standards of measure characterized by infinitesimal.slippages of time and consequent fractional number sequences in need of periodic correction.

baktun: Fifth order of Mayan vigesimal number sequence; in time reckoning equals 144,000 kin (days), or 394.52 years; thirteen per great cycle, measure of human historical era or "great cycle": 3113 B.C.-A.D.2012.

biogenic migration of atoms: Biospheric principle by which evolution over time within finite quantity of living matter (biomass) is accounted for by changes of atomic.,cellular-molecular state and condition; occurring uniformly at periodic transitions accounts for major evolutionary mutations.

biogeochemical, biogeochemical combustion: Term used by V. 1. Vernadsky to refer to biospheric dynamic as whole system order unifyIDg living (bio) and inert (geochemical) matter in a single process; biogeochemical combustion occurs when exponential curve of acceleration of biogenic migration of atoms becomes absolutely vertical, precipitating advent of noosphere.

biomass, biomass constant: Sum quantity of living matter, which, according to Vernadsky, has remained relatively stable since the origin of life on Earth; as a constant, maintained by synchronic timing factor mathematically described as an annual orbital ratio of 73(5) = 365 days per solar orbit of Earth.

biosphere: Sphere or mantle oflife and its geochemical support system distributed throughout Earth's ocean-land surface

biosphere-noosphere transition: Description of the transformation of the general biospheric condition due to accelerated excitation of biogenic migration of atoms creating release of free energy and consequent biospheric destabilization, characterized as biogeochemical combustion, whose resolution is emergence of new evolutionary order, the noosphere; change from historical technosphere to post-historic, post-technological phase.

Bolontiku: Nine Lords of Time; in Mayan cosmology, nocturnal rulers of the underworld or *inframundo;* guardians of the passage of death and resurrection; keepers of time and the knowledge of time as noospherically registered in Earth's orbit.

calendar: Derived from the Latin *calends,* or account book, a day for making payments; generic word used to define systems of timekeeping based on measure of Earth's orbit around the sun, often utilizing synodic measure of the moon as a means of calculating.

Chilam Balam: "Jaguar priest," name of Mayan prophet *(ah bobat)* who lived just before the time of conquest, which he accurately predicted; name given to lineage of Mayan prophets extending from the end of tenth baktun (circa A.D. 830) up until the nineteenth century; name given to series of post-conquest texts in which the various categories of prophecies of this lineage are recorded.

chronomancy, geochronomancy: "Divination by time"; the science and art of fourth-dimensional time considered as a whole system where science is knowledge and art is practice; oracular method of reading the synchronic order; description of incipient "Earth time science" incorporating principles of whole Earth geomancy into time structures of the synchronic order.

chronosphere: Sphere of time that activates noosphere; fourth-dimensional field created by the planet holon in resonance with the rotation of the third-dimensional planet body; coded as movement of four chromatics (biopsychic field) across the planet holon, stitching together gravitational fields (five Earth families) and electromagnetic fields (four color families).

chronotopology: Term coined by Charles Muses to define any geography of time and consisting of an event point of meaning that creates a root meaning from which time-formed, -blossomed, or -radiated meanings emerge above a horizon of meaning.

Day Out of Time: The 365th day of the Thirteen Moon/28-Day calendar, no day of the week or month at all (52 x 7 day weeks = 13 moons times 28 days = 364); occurs on Gregorian correlate date July 25, and precedes Thirteen Moon "New Year's" or synchronization date, correlated to July 26.

Dreamspell: Any agreed-on consensus reality; a collective mind-set defining a noospheric epoch, such as "Dreamspell of history"; term given to proofs and tools demonstrating radial and fractal principles of fourth-dimensional mathematics; cosmo-mythic structure of Earth history and its future, otherwise known as *Dreamspell: The Journey of Timeship Earth 2013.*

free energy: Release into biosphere of gases (such as carbon monoxide) and other chemical by-products of industrialization that accelerate biogenic migration of atoms, resulting in biogeochemical combustion; in noosphere refers to release of spectral plasmic-atmospheric phenomena through human telepathic interaction with the electromagnetic field.

fourth dimension: Dimension of time greater than and containing three dimensions of space that it informs and governs.

galactic signature: Combination of one of thirteen galactic tones and twenty solar seals that constitute the harmonic module and that code any given day of the third-dimensional Thirteen Moon calendar.

geocosmic: Holonomic perception expressing unification of Earth whole with the cosmic order.

Gregorian (Julian) calendar: Current world standard calendar consisting of twelve irregularly numbered and obscurely named months coordinated by the 7-day week and intercalary leap year system establishing 28-year cycles; created by the reform of Pope Gregory XIII (1572-1583) in 1582, which "corrected" the Julian calendar (established by Julius Caesar, 45-44 B.C.)by lopping off ten days and refining the intercalary system so that only centuries that are multiples of four are leap years; supreme example of astronomical time measure; principle macro-organizing principle establishing 12:60 artificial timing frequency.

Hannonic Module: 260-unit mathematical matrix of 13:20 frequency, inclusive of a 52-unit binary triplet configuration or set of galactic activation portals; sometimes referred to as Tzolkin, 260-kin sacred count of the Maya; basis of fourth-dimensional vigesimal mathematics of time; coordinated with third-dimensional calendar of Thirteen Moons, establishes basis of 260 galactic signatures.

heliosphere: Sun and its system of planets considered as a whole organism; also known as heliocosm.

holonomics: Of or pertaining to the law governing whole systems.

holonomic consistency and reciprocity: Law by which any whole principle of reality is capable of evoking a like response or reflecting a fractal order at whatever level or through whatever structure.

holon: Any organic whole unit, fractally replicable; basis ofholonomics, law governing whole systems.

human holon: Fourth-dimensional structure of the human being conforming to the 13:20 frequency (twenty digits, thirteen main articulations).

Hunab Ku: "One giver of movement and measure"; in Mayan cosmology, can refer to God as the Supreme Creator.

Inevitable Event: Law of Time definition of the point in synchronic order when the artificial time generated curves of machine, human population, and money converge exponentially in one dramatic, prophecy-fulfilling moment, marking the conclusion oftechnospheric expansion; name given to the events of September 11, 2001 (9-11), epitomized by the collapse of World Trade Center Twin Towers (Fall of Babylon).

Julian Count: Established by Thomas Scaliger, 1583, the year after Gregorian calendar "reform," to establish a linear count of days beginning January 1, 4714 B.C.,some 1,600 years prior to commencement of thirteen baktun Long Count of the Maya; official modern scientific count, basis of linear time paradigm.

katun: Fourth order of vigesimal mathematics = 8,000 kin; in Mayan time count, where the second order vinal is 18 and not 20, a katun = 7200 kin, or 19.7 solar years; twenty katuns equal one baktun of 144,000 kin; 260 katuns per thirteen baktun cycle.

kin: In fourth-dimensional mathematics the base unit of measure, possessing fractal properties; one day and night or turn of Earth on its axis; any human being so designated by assuming the galactic signature of the date of birth.

Law of Time: T(E) =Art, Energy factored by Time equals Art, where T (time) is the fourth-dimensional universal synchronization frequency constant 13:20, E (energy) refers to any phenomenal manifestation, and Art to the fact that the synchronizing frequency of time harmonizes everything into a natural condition of beauty.

Long Count: Mayan count of days (kin) measured by thirteen baktuns of 144,000 days each for a total of 1,872,000 kin, the measure of history from Julian/Gregorian correlates August 13, 3113 B.C. to December 21, 2012; still maintained through use of Tzolkin by Quiche Maya, Guatemala.

lunar calendar: System of time measurement using synodical measure of the moon-from new moon to new moon, approximately 29.5 days; twelve lunar months equaling a total of 354 days, eleven days short of the measure of solar orbit; used by many of the Old World civilizations; with the exception ofIslamic lunar calendar, most lunar calendars intercalate a thirteenth moon, seven per every nineteen years.

machine: Capacity for the human to externalize its internal processes as well as motor functions into different means of mechanical reproduction, the sum possibilities of which establish a technological complex requiring constant maintenance, thus subordinating human consciousness to its level; the ultimate manifestation of the 12:60 timing frequency; any industrially produced tool believed to advance the level of human comfort and accomplishment.

noosphere: Earth's mental envelope or field, discontinuous with and above the biosphere; unconscious until the discovery and application of the Law of Time; activated by registration of the human biomass in correct 13:20 timing frequency via universal adoption of Thirteen

Moon calendar; description of transformed state of biosphere, coincident with the end of history; condition of universal telepathy subsequent to collapse of technosphere and application of Law of Time; functions in tandem with programs from Earth's octahedral core.

noospheric chip: Description of human operating in noosphere, holonomically resonant with intrinsic 13:20 codes of synchronic order, capable of interacting with the psi bank to participate in the creation of Earth's rainbow brain.

Noospheric Earth Time (NET): Time measure based on Earth in its orbit in relation to the sun and moon in heliospheric space, rather than from the perspective of human (astronomical time); base unit of measure is one rotation of Earth on its axis or one kin (one night and day), which establishes one NET minute; twenty-eight NET minutes per Moon, or one NET hour, 365 NET minutes, or Thirteen NET Hours plus one NET minute per solar orbit; takes into account that for any NET minute axial magnetic bipolarity of Earth is a changing dynamic reaching two peak points called solstices and two stable points called equinoxes; this four-part division is holonomically registered daily in two peak points, midnight (where day begins and ends) and noon, and two stable points, sunrise and sunset.

occult quartet: Demonstration of radial mathematics of Harmonic Module where the tones of any four kin radially equidistant from each other always equal 28; or the tones of any two kin radially opposite always equal 14.

octahedral core: Iron crystal structure at center of Earth; plasmic storage zone in resonance with the noosphere; in 7:7::7:7, telepathically coordinated by four time atoms (= one master time molecule).

omega point: In the work of Pierre Teilhard de Chardin, defines the climactic convergent point (harmonic convergence) of human evolution as the emergence of the hyper-personal; defined by the Law of Time as point of full superconscious establishment of universal telepathy as the norm of the human mental condition; dawn of omega point: winter-northern-summer-southern solstice, 2012, completion of omega point dawn, Yellow Galactic Seed (July 26,2013), otherwise known as Dreamspell of galactic culture.

oracle: For anyone of 260 kin of the Harmonic Module, a cruciform five-part structure demonstrating a uniform set of mathematical relationships in relation to the (0-19) code number of the daily solar seal (destiny kin) informing any day of the Thirteen *Moonl2* 8-Day calendar; consists of center, code number of destiny kin; right analog kin-always 19 when added to the number of destiny kin; left, antipode kin-always a difference of 10 from the destiny kin; below, occult kin-when added to destiny kin always equals 21; and above, guide, always the same color as destiny kin.

Oxlahuntiku: The Thirteen Lords of Time that govern the power of the cosmic order of time that is based on circulatory power of prime number 13 (as opposed to 12, which is static and non-circulatory); coded as thirteen 28-day moons that govern terrestrial solar orbit; basis of prophecy cycle of Quetzalcoatl, Thirteen Heavens (Oxlahuntiku) and Nine Hells (Bolontiku); in Telektonon prophecy, the thirteen-year cycle-2 000-2 013-in which the first four years, 2000-2004, establish self-existing power of time, and last nine years, 2004-2013 are coded by the Bolontiku, the Nine Lords of Time.

Pacal Votan: Mayan prophet (A.D.603--683), chief technician of Mayan synchronic time science; eleventh ruler of the dynasty of Palenque (Nah Chan), Chiapas, Mexico; assumed power in A.D.615, but key rulership occurred in critical 52-year cycle, 631-683 (seventy-third such cycle since commencement of thirteen baktun count); best known for the carved sarcophagus lid of his elaborately concealed tomb discovered in 1952, 1,260 years after its dedication in A.D.692, which was also 1,320 years before the closing of the cycle, 2012.

Pax Cultura, Pax Biospherica: Principle of new human social order following establishment of Thirteen Moon/28-Day calendar and inaugurating the advent of the noosphere (2004) in which nation-state is replaced by biospheric regionalism governed by a Planetary Biospheric Assembly; due to perfect harmony of new world standard calendar of thirteen moons/28 days, harmony, art, and aesthetic values elevate culture as the new operating norm of the human reintegrated within the biosphere, hence *Pax Cultura, Pax Biospherica.*

planet holon: Twenty-part icosahedral noospheric matrix superimposed on Earth's surface; corresponding to 0-19 code of twenty solar seals, creates three orders analogous to three planetary fields of resonance; gravitational field-horizontal order of five Earth families of four seals each; electromagnetic field-four diagonal bands, from lower left to upper right, of the four color families (red, white, blue, yellow) of five seals each; and biopsychic field-the four chromatics of five seals each moving diagonally from upper left to lower right, which coordinate the daily sequence of the motion of the chronosphere.

psi bank: Regulating mechanism of the noosphere consisting of four bipolar plates, each plate in mirror symmetry containing 520 (260 x 2) psi chrono units, 2,080 in all, which are the complete registrations of the universal fourth-dimensional 13:20 timing frequency governing all of the various evolutionary stages of the terrestrial biogeocosm; engine of the chronosphere, located between the two radiation belts 2,000 and 11,000 miles above Earth's surface.

psi chrono unit: Time-bearing information unit; base unit of the psi bank; codes and contains all information for anyone of the 260 galactic signatures of the 13:20 matrix or Harmonic Module; psycho activated through coordination with Thirteen Moon/Telektonon known as Rinri Project.

Psychozoic Era: Term coined by V. 1. Vernadsky defining the next geological era; meaning the era of the spiritualization of life, it is coincident with the noosphere in its full emergence after the omega point has been reached, 2012-2013.

Quetzalcoatl: Mexican prophet (A.D.947-999) who left the legacy of prophecy of Thirteen Heavens and Nine Hells, basis of Harmonic Convergence (1987) and commencement of the "Time of Prophecy," 1987-2013.

Quran, Holy Quran: Literally "recitation;" last revelation and moral-spiritual criterion for historic humanity; received over a twenty-three-year period by the Prophet Muhammad (A.D.570-632); proven by Dr. Rashad Khalifa (1935-1990) to be a radically nonlinear text rigorously constructed of a nineteen-based mathematical code.

radion, radial plasmas: Telepathic fluid or lubricant released through telepathic interaction with the seven primary plasmas, or electrically charged particles, hence radial plasmas; the names of the seven plasmas replace the names of the week in the Thirteen Moon/28-Day calendar; activated in the 7:7::7:7 Telektonon Revelation practice.

radiosonics: Name given to the new science based on synchronicity rather than causality and in which, as a consequence, synaesthetic experiences and syntropic values are normalized.

rainbow brain: Description of activated noosphere, where human telepathic interaction with the electromagnetic field triggers the release of the circumpolar rainbow bridge-Earth's day-night alternator system.

Rinri Project: Law of time practice for coordinating the opening of the psi bank, psi chrono unit per psi chrono unit, on a daily basis over a four-year cycle by means of the Thirteen MoontTelektonon.

synchronic order: Order of fourth-dimensional time, in contrast to third-dimensional astronomical time, that synchronizes all aspects of third-dimensional physical plane reality including its timekeeping systems; entirely new domain of human mental-spiritual experience coincident with the dawning of noosphere; characterized by absolute harmonic perfection, described by vigesimal 0-19 code, as distinct from decimal, hex, or duodecimal mathematics that govern third-dimensional timing codes.

synchronometer: Measure of synchronization or synchronicity; precise Law of Time definition of means and purpose of what is generically referred to as the "calendar."

technosphere: Global sphere of technology; artificial stage between biosphere and noosphere, representing the climax-biogechemical combustion-of acceleration of biogenic migration of atoms precipitating biospheric crisis as a prelude to the advent of noosphere; characterized by exponential curves of human population, machine, and money at expense of biospheric integrity and stability; defined as the specific fifty-six-year cycle (two Gregorian 28-year cycles) 1945-2001, in which war and terrorism are the governing features; complete manifestation of the 12:60 order of time; concluded on September **11,2001,** the Inevitable Event.

Telektonon: "Earth Spirit Speaking Tube," the name of the psychoduct leading from the tomb of Pacal Votan beneath the Temple of the Inscriptions to the temple floor atop the pyramid, the discovery of which, in 1949, led to the excavation and revelation of the long-concealed tomb in 1952; name given to the prophecy ofPacal Votan, decoded in 1993-1994, prophesying the Thirteen Moon/28-Day calendar as the only means to keep the human race from destroying the biosphere and itself; definition of the fourth-dimensional structure of the heliosphere in which consciousness is a function of the planetary orbits; basis of a board "game" coded to synchronic order via Thirteen Moon calendar for the awakening of telepathy; basis of the Cube of the Law, days 7-22, containing numerous principles of the Law of Time as a daily practice; basis of other practices for establishing synchronic order as principles of a new consciousness, including *20 Tabletsof the Law of Time* and the 7:7::7:7.

third dimension: Space; physical plane of reality coordinated and contained by time, fourth-dimensional order of reality.

Thirteen Moon/28-Day calendar: Pragmatic application of the Law of Time, perpetual harmonic perfection of which is intended to correct for disorder of human consciousness resulting from adherence to irregular, astronomical timing standards and mechanistic timing devices; coordinated with Harmonic Module and Telektonon establishes means for conscious human participation in synchronic order; 28-day measure based on female menstrual cycle, also corresponds to apsidal measure of moon from the point at which the polar axis is tipped farthest from Earth; prevalent in pre-history, all but eliminated by historical consciousness that made 13 taboo; perfect vehicle for establishing noosphere as daily consciousness in post-technospheric post-history.

time: Fourth dimension; universal factor coordinating space to manifest synchronically; traveling faster than speed of light, accounts for instantaneity of information transmission (telepathy) from distant points; expressed as formulation which states that the velocity of time is instantaneously infinite; fourth-dimensional structures that are radial and fractal in nature, third-dimensional cycles being manifestations thereof; expressed as T(E) = Art, accounts for universal harmony of the cosmos.

tun: Third positional order of vigesimal mathematics where one unit = 400 kin; in Mayan time count, because of second positional order, vinal, being 18 instead of 20, one tun = 360 kin; basis of measure ofkatuns and baktuns in Long Count, where 5,200 tuns = 260 katuns = 13 baktuns, or 5,125 solar years.

Tzolkin: "Sacred Count," 260-day calendar of the Maya, basis of Mayan time knowledge and the Long Count; temporal manifestation of Harmonic Module or universal 13:20 timing matrix.

UR: "Universal Religion," "Universal Recollection;" description of human spirituality in the noosphere or Psychozoic Era.

vigesimal, 0-19 code: Twenty-count based mathematics utilizing zero for positional orders that advance in exponential binary fashion; also known as 0-19 dot-bar code notational system, where dots equal single units, bars equal five units, plus positional zero; basis of mathematics of fourth-dimensional order of time, distinct from mathematical systems of third-dimensional space.

Wave Harmonic of history: Fourth-dimensional description of thirteen baktun cycle (3113 B.C.-A.D.2012) identified precisely with 260-unit Harmonic Module, where each of thirteen baktuns contains twenty katuns (13 x 20); basis of creating synchronic order out of entropic disorder of third-dimensional historical time.

wavespell: Thirteen-unit cosmological form-constant for coordinating fourth-dimensional timing cycles; consists of two gates, Magnetic first position and Cosmic thirteenth position; two towers, fifth and ninth positions; and three sets of chambers, nine chambers in all; when coordinating Thirteen Moon/28-Day calendar, known as Planetary Service Wavespell.

Wizard's Count: Name of count to establish synchronic order as manifestation of the Law of Time in order to transit from 12:60 technosphere to 13:20 noosphere; based on prophetically modified year-bearer count of the Chilam Balam tradition; correlated by the Dreamspell to July 26, 1987, White Galactic Wizard, every four years there are four year bearers: Yellow Seed, Red Moon, White Wizard, and Blue Storm (one four-year Seed-Storm Year bundle) that, combined with thirteen galactic tones creates 52-year solar-galactic cycle, or in NET time, one Earth Year, also known as a Wizard's Year.

▼



Bibliography

I. About the Biosphere, Technosphere, and Noosphere

Argiielles, Jose: *EJ:rh Ascending: An Illustrated Treatise on the Law Governing Whole Systems.* B~.~ldh: Shambhala Publications, 1984. Second and third editions, Santa Fe: Bear & Co., 1988 and 1996.

-. "Peace is the Culture of the Biosphere: Statement and Reflections." Brightwood, Oregon: Foundation for the Law of Time, unpublished paper, 1996.

Argiielles, Jose and Lloydine Argiielles. *A Complete Guide to the First Planetary Congress of Biospheric Rights.* Portland, Oreg.: Planet Art Network, 1996,2002.

-. *The World Thirteen Moon Calendar Change Peace Plan.* Portland: Planet Art Network. 1999.

Coats, Callum. *Living Energies: An Exposition of Concepts Related to the Theories of Viktor Schauberger.* Bath, England: Gateway Books, 1996.

"Global Consciousness Project: Registering Coherence and Resonance in the World," http://noosphere. princeton.edu.com.

Kaznacheev, V. P. "The General Pathology: Consciousness and Physics." Novosibirsk: Russian Academy of Medical Science, 2000.

Lapo, Andrey V. *Traces of Bygone Biospheres.* Moscow and London: Mir Publishers and Synergetic Press, 1987.

Laptev, 1. *The Planet of Reason: A Sociological Study of Man-Nature Relationship.* Moscow: Progress Publishers, 1973. English Translation, 1977.

Ponyko, V. A. *Vednie V Systemy "Ekoprognos": Metodologiya Prognosirovaniya Anomalii Ekosperi* (Ecoprognosis: Methodology for Making Prognosis of Anomolous Phenomena in the Ecosphere). Moscow: Institute Ustoychivogo Rasveteya, 2000.

Smil, Vaclav. *Energies: An Illustrated Guide to the Biosphere and Civilization.* Cambridge, Mass. and London: MIT Press, 1999.

Snyder, Tango, editor in chief, and the Institute of Ecotechnics. *The Biosphere Catalogue.* London and Forth Worth: Synergetic Press, 1985.

Teilhard de Chardin, Pierre. *The Future of Man.* New York: Harper & Row, 1964.

-. *The Phenomenon of Man.* New York: Harper & Row, 1959.

Vernadsky, V. 1. *The Biosphere.* Abridged version based on the French edition of 1929. Oracle, Arizona and London: Synergetic Press, 1986.

-. *The Biosphere: Complete Annotated Edition.* Revised and annotated by Mark A. S. McMenamin and Far West Institute. New York: Copernicus/Springer Verlag, 1998.

-. "Problems in Biogeochemistry 11." In *Transactions of the Connecticut Academy of Sciences,* vol. 35 (1944): 483-517.

II. About the Law and Science of Time

Acheles, Elisabeth. *Of Time and the Calendar.* New York: Hermitage House, 1955.

-. *The World Calendar Reform Since 1930.* New York: G. P. Putnam's Sons, 1937.

Alcala, Luis Alvarez. *El Calendario Azteca.* Edited by B. Costa-Amico Mexico City: 1970.

Argiielles, Jose. "Calendar Reform and the Future of Civilization: Preparatory Reflections for the World Summit on Peace and Time," San Jose, Costa Rica: University for Peace, unpublished paper, 1999.

-. *The Call of Pacal Votan: Time is the Fourth Dimension.* Glasgow: Altea, 1996.

-. "Campaign for the New Time: Science Demonstrates a New Time of Peace on Earth," Brightwood, Oregon: Foundation for the Law of Time, unpublished position paper, 2000.

-. *Earth Ascending: An Illustrated Treatise on the Law Governing Whole Systems.* Santa Fe: Bear & Co, 1984, 1988, 1996

-. *The Dynamics of Time: 260 Postulates.* Portland, Oreg.: Planet Art Network, 1999.

-. *The Mayan Factor: Path Beyond Technology.* Santa Fe: Bear & Co., 1987. Second edition, 1996.

Argiielles, Jose and Lloydine Argiielles. *Discovering the New Time.* Tokyo: Fuunsha, 1997.

-. *Thirteen Moons in Motion.* Portland, Oreg.: Planet Art Network, 1999.

Barbour, Julian. *The End of Time: The Next Revolution in Physics.* Oxford: Oxford University Press, 1999.

Ben 4 and Ben 5. 13 *Moon Natural Time Calendar: Ancient Science for the Art of Now.* Newport, Oreg.: Skytime, 2001.

Colson, F. H. *The Week: An Essay on the Origin and Development of the Seven-Day Cycle.* Cambridge: Cambridge University Press, 1926.

Cott, Jonathon. *Thirteen: A Journey into the Number.* New York: Doubleday, 1996.

Coveney, Peter and Richard Highfield. *The Arrow of Time: A Voyage Through Science to Solve Time's Greatest Mystery.* New York: Fawcett-Columbine, 1990.

Davies, Paul. *About TIme: Einstein's Unfinished Revolution.* New York: Simon & Schuster, 1995.

Deutsch, David. *The Fabric of Reality.* London: Penguin Books, 1997.

Dogen. "The Time-Being," from *Moon in a Dewdrop: Writings of Zen Master Dogen.* Edited by Kazuaki Tanahashi, New York: North Point Press, 1985. 76-83.

Duncan, David Ewing. *Calendar: Humanity's Epic Struggle to Determine a True and Accurate Year.* New York: Avonbooks, 1998.

Dunne, J. w. *An Experiment with Time.* Charlottesville, Va.: Hampton Roads, 2001.

Eganova, Irina. "On the Nature of the Stars: N. A. Kozyrev's Approach and His Results." In *Searchfor Mathematical Laws of the Universe,* edited by M. M. Lavrentiev, 215-276. Novosibirsk: Sobolev Institute of Mathematics, 2001.

Fraser, J. T. *Time, the Familiar Stranger.* Redmond, Wash.: Tempus-Microsoft, 1987.

Fraser, J. T., ed. *The Voicesof Time: A CooperativeSurvey of Man's Views of Time as Expressed by the Sciencesand the Humanities.* New York: George Brazilier, 1966.

Heath, Robin. *Sun, Moon & Earth.* Powys, Wales: Wooden Books, 1999.

International Society for the Study of Time (ISSO), www.studyoftime.org/index.html.

The Journal of Calendar Reform, vols. I and II. New York: The World Calendar Association, 1931,1932.

Koneatis, Christos. *The History of the World-A 6,000 Year Chronicle of Time.* London: Christos Koneatis, 1997.

Koshev, Kareng. "The Great Rainbow Bridge," Altai: unpublished paper, 2001.

Kozyrev, N. A. "Possibility of Experimental Study of Properties of Time," Novosibirsk: Russian Academy of Sciences, unpublished paper, September, 1967.

-. www.kozyrev.ru.

Landes, David S. *Revolution in Time: Clocksand the Making of the Modern World.* Cambridge, Mass.: Belknap Press, 1983.

Lavrentiev, M. M. "Interpretation of Astronomical Data Connected with N. A. Kozyrev's Discovery." In *Memoranda of Differential Equations of Mathematical Physics,* vol. 12, (1997): 135-41.

-. "Physical Theories (Mathematical Models) Adequate to the Reality: A Necessary Condition for Progress of Natural Science of the XXIst Century." In *Searchfor Mathematical Laws of the Universe,* 29-51. Novosibirsk: Sobolev Institute of Mathematics,2001.

Lavrentiev, M. M., and Irina A. Eganova. "N. A. Kozyrev's Method of Astronomical Observations: Information from True Positions of Stars, Stellar Systems, and Planets." In *Instantaneous Action at a Distance in Modern Physics: "Pro" and "Contra,"* edited by Andrew E. Chubykalo, Viv Pope, and Roman Smirnov-Rueda. New York: Nova Science Publishers, 1999.

Malmstrom, Vincent H. *Cycles of the Sun, Mysteries of the Moon: The Calendar in Mesoamerican Civilization.* Austin: University of Texas Press, 1997.

Man and Time: Papers from the Eranos Yearbook 3. Bollingen Series XXX. Edited by Joseph Campbell. New York: Pantheon Books, 1957.

Maroushkina, Maria. "Is a Path Beyond Technology Possible for Western Culture?" Moscow: unpublished paper, 2000.

Muses, Charles. *Destiny and Control in Human Systems: Studies in the Interactive Connectedness of Time (Chronotopology).* Boston- Dordrecht -Lancaster: Kluwer- Nijhoff Publishing, 1984.

Nuestra Civilizacion Frente a la Reforma del Calendario (Our Civilization Confronted with Calendar Reform). Buenos Aires: Casa Editora Sudamericana, 1944.

Penrose, Roger. *Shadows of the Mind: A Search for the Missing Science of Consciousness.* Oxford: Oxford University Press, 1994.

Philip, Alexander. *The Reform of the Calendar.* London: Kegan Paul, 1914.

Philosophy of Time. www.dna2z.com/projects/time.html.

Price, Huw. *Time's Arrow and Archimedes Point.* Oxford: Oxford University Press, 1996.

Reference Library Books. *The World of Time and Timepieces.* London: B. P. C. Publishing, 1972.

Richmond, Broughton. *Time Measurement and Calendar Construction.* Leiden: J. Brill, 1956.

Seabury, Rev. Samuel. *The Theory and Use of the Church Calendar in the Measurement and Distribution of Time.* New York: Pott, Young & Co., 1872.

Spinden, HerbertJ. *Maya Dates and What They Reveal.* Brooklyn: Museum of the Brooklyn Institute of Arts and Sciences, 1930.

Star Roots. 13 *Moon Natural Time Journal.* Manson's Landing, British Columbia, 2001.

The Study of Time: Proceedings of the First Conference of the International Society for the Study of Time, Oberwolfach, Black Forest, West Germany. Edited by J. T. Fraser,. F. C. Haber and G. H. Miiller. Berlin-Heidelberg-New York: Springer Verlag, 1972.

The Study of Time II: Proceedings of the Second Conference of the International Society for the Study of Time, Lake Yamanaka, Japan. Edited by J. T. Fraser, F. C. Haber and G. H. Miiller. Berlin-Heidelberg-New York: Springer Verlag, 1975.

Vanderkam,James C. *Calendars in the Dead Sea Scrolls: Measuring Time.* London and New York: Routledge, 1998.

Votan, Valum. *Principia Mathematica of the Fourth Dimension: Introduction and Annotated Bibliography.* Portland, Oreg.: Planet Art Network, 1999.

Whitrow, G. J. *The Natural Philosophy of Time.* New York: Clarendon Press, 1980.

Wolf, Fred Allen. *Parallel Universes: The Search for Other Worlds.* New York: Touchstone, 1988.

III.About the Inevitable Event: Prophecy, History, and Politics

Ahmad, Mirza Ghulam of Qadian. *The Philosophyof the Teachingsof Islam.* London: London Mosque, 1979.

America at War. New York: Profiles Presents, 2001.

Argiielles, Jose. *Pacal Votan and Judgement Day*.Portland, Oreg.: Planet Art Network, 1999.

Barber, Benjamin R. *Jihad vs. McWorld.* New York: Random House, 1995, 1996.

Bodansky, Yossef. *Bin Laden: The Man Who Declared War on America.* New York: Forum, 1999,2001.

The Book of Chilam Balam of Chumayel. Edited and translated by Ralph L. Roys. Norman, Okla.: University of Oklahoma Press, 1967.

Case, Paul Foster. *The Tarot: A Key to the Wisdom of the Ages.* New York: Macoy, 1947.

The Codex Perez and the Book of Chilam Balam ofMani. Edited and translated by Eugene Craine and Reginald Reindorp. Norman, Okla.: University of Oklahoma Press, 1979.

"Golden Age of Miracles and Heaven on Earth," *National Examiner,* November 29, 1988, p. 17.

Haykal, Muhammad Husayn. "Islamic Civilization as Depicted in the Qur'an." In *Lift of Muhammad.* Translated from the 8th edition by Isma'il Ragi A. al-Faruqi, 517-55. Indianapolis: American Trust, 1993.

Hoagland, Jim. "The Faithful Come and Wars Erupt Worldwide," *The Oregonian,* December 24,2001, p. C-7.

Huntington, Samuel P. *The Clash of Civilizations and the Remaking of the World Order.* New York: Simon & Schuster, 1996, 1997.

I Ching or Book of Changes. Translated by Richard Wilhelm and Cary F. Baynes. Princeton: Princeton University Press, 1967.

Izquierdo, Ana Luisa. *Alberto Ruz Lhuillier Frente al Pasado de los Mayas.* Mexico City: Secretaria de Educacion Publica, 1987.

Jenkins, John Major. *Maya Cosmogenesis 2012: The True Meaning of the Maya Calendar End-Date.* Santa Fe: Bear & Co., 1998.

John ofPatmos, "Book of Revelation," Chapter 18, "The Fall of Babylon." *The Holy Bible, New International Version.* Grand Rapids: Zondervan Bible Publishers, 1989.

Katchongva, Dan. *From the Beginnings of Lift to the Day of Purification: Teachings, History & Prophecies of the Hopi People.* Los Angeles: Committee for Traditional Indian Land and Life, 1972.

Khalifa, Rashad. *Quran: The Final Testament.* Fremont, Calif.: Universal Unity, 1992.

Kyipchakoba, P. v., ed. *Altai U Drevnue Maya* (Altai and the Ancient Maya). Gorno-Altaiski, 2001.

Landa, Fray Diego de. *Yucatan Before and After the Conquest.* Translated by William Gates. New York: Dover, 1978.

El Libro de los Libros de Chilam Balam. Edited and translated by Alfredo Barrera Vasquez and Silvia Rendon. Mexico: Fondo de Cultura Economica, 1948, 1986.

Mahmud, Sayyid Fayyaz. *A Short History of Islam.* Oxford: Oxford University Press, 1960.

Mano, Galactica Azul. "La Profecia Maya y las Torres Gemeles" (Mayan Prophecy and the Twin Towers). Manzaneles, Colombia: unpublished research paper, October, 2001.

Oldenburg, Dan. "The Harmonic Convergence Revisited," *Washington Post,* May 4, 1990, p. D-5.

The Roerich Pact and the Banner of Peace. New York: The Roerich Pact and Banner of Peace Committee, 1947.

Ruz, Alberto. *Palenque, Official Guide.* Mexico City: Instituto Nacional de Antropologia e Historia, 1978.

September 11,2001: The Day that Changed America. New York: God Bless America, 2001.

September 11,2001. New York: Time-Warner, 2001

Shearer, Tony. *Beneath the Moon and Under the Sun: A Reappraisal of the Sacred Calendar and the Prophecies of Ancient Mexico.* Albuquerque: Sun Books, 1975.

"Tracking the Hijackers," *The Oregonian,* October 4,2001, p. A-12.

Tulku Thondup Rinpoche, *Hidden Teachings of Tibet: An Explanation of the Terma Tradition of Tibetan Buddhism.* Boston: Wisdom Publications, 1986, 1997.

▼

Books of Related Interest

THE MAYAN FACTOR
Path Beyond Technology
by Jose Argiielles

EARTH AsCENDING
An Illustrated Treatise on Law Governing Whole Systems
by Jose Arguelles

SURFERS OF THE ZUVUVA
Tales of Interdimensional Travel
by Jose Arguelles

MAYA COSMOGENESIS 2012
The True Meaning of the Maya Calendar End-Date
by John Major Jenkins

GALACTIC ALIGNMENT
The Transformation of Consciousness According to Mayan, Egyptian, and Vedic Traditions
by John Major Jenkins

THE MAYAN ORACLE
Return Path to the Stars
by Ariel Spilsbury and Michael Bryner

SECRETS OF MAYAN SCIENCEIRELIGION
by Hunbatz Men

THE LOST REALMs
by Zecharia Sitch in

Inner Traditions. Bear & Company
P.O. Box 388
Rochester, VT 05767
1-800-246-8648
www.InnerTraditions.com

Or contact your local bookseller

www.foundationforthelawoftime.org

www.tortuga.com

The Inevitable Event and the End of History

The end of 12:60 Gregorian Time
Pope John Paul II after the Inevitable Event

Planetary 9-11, 2001. First Year, third Millenium

"Woe! Woe, O Great City, O Babylon
in one hour your doom has come!"
—Revelations, 18:10

11 Years Before



-3113
Baktun 1
Star Planting
-2718
Baktun 2
Pyramid
-2324
Baktun 3
Wheel
-1930
Baktun 4
Sacred Mountain
-1531
Baktun 5
House of Shang
-1141
Baktun 6
Imperial Seal
-747
Baktun 7
Mind Teachings
-353
Baktun 8
Annointed One
+41
Baktun 9
Lords of Red and Black
+435
Baktun 10
Maya
+830
Baktun 11
Holy Wars
+1224
Baktun 12
Hidden Seed
+1618
Baktun 13
Transformation of Matter
+2012
+2012

13 Tone Wavespell
as Thirteen Baktun
Wave Harmonic
of History

B.C. 3113



1	21	41	61	81	101	121	141	161	181	201	221	241
2	22	42	62	82	102	122	142	162	182	202	222	242
3	23	43	63	83	103	123	143	163	183	203	223	243
4	24	44	64	84	104	124	144	164	184	204	224	244
5	25	45	65	85	105	125	145	165	185	205	225	245
6	26	46	66	86	106	126	146	166	186	206	226	246
7	27	47	67	87	107	127	147	167	187	207	227	247
8	28	48	68	88	108	128	148	168	188	208	228	248
9	29	49	69	89	109	129	149	169	189	209	229	249
10	30	50	70	90	110	130	150	170	190	210	230	250
11	31	51	71	91	111	131	151	171	191	211	231	251
12	32	52	72	92	112	132	152	172	192	212	232	252
13	33	53	73	93	113	133	153	173	193	213	233	253
14	34	54	74	94	114	134	154	174	194	214	234	254
15	35	55	75	95	115	135	155	175	195	215	235	255
16	36	56	76	96	116	136	156	176	196	216	236	256
17	37	57	77	97	117	137	157	177	197	217	237	257
18	38	58	78	98	118	138	158	178	198	218	238	258
19	39	59	79	99	119	139	159	179	199	219	239	259
20	40	60	80	100	120	140	160	180	200	220	240	260

A.D. 2012

Baktun 13 - Katun 260 - 1993 - 2012
End of Second Christian Millennium A.D. 2000

Harmonic Module
13 Baktun
260 Katun
13:2 Matrix of History
1 Kin = 1 Katun
1 Baktun = 20 Katuns

Nostradamus Prediction
of nuclear destruction of
New York in Year 2000

THE END OF THE WORLD
O FIM DO MUNDO

Cover of "Istoe" (Brazil) May, 1996. "End of the World."

16. The Tower



The total mass of living matter has never differed considerably from the present value.

The Continuity and Invariance of Life on the Earth

Living matter today is genetically connected with all the living matter of preceding ages, and conditions favorable to life on Earth have never differed vastly from those of the present.

Multiplication as a Manifestation of Transformed Solar Energy

The movement of living matter resulting from the multiplication of organisms operates with an astonishing regularity.

The rate of production of new living matter is proportional to the amount already produced.

Whatever may be the phenomena of life, the energy evolved by organisms is mainly (perhaps entirely) the radiant energy of the Sun

Vegetation as a Transformer of the Energy of the Sun.

We may regard living matter in its entirety as the peculiar and unique domain for the accumulation and transformation of the luminous energy of the Sun.

Throughout all geological ages the chemical effects of living matter on its surroundings have not changed, so that the composition of the crust and of the living matter are the same today as they have always been.

The Biosphere as a Region for the Transformation of Cosmic Energy

LIFE IS THE TRANSFORMATION OF SOLAR ENERGY

Planetary Service Wavespell

YEAR OF THE RED PLANETARY MOON

© 2002.7.26 ~ 2003.7.25


MAGNETIC MOON
LUNAR MOON
ELECTRIC MOON
SELF-EXISTING MOON
OVERTONE MOON
RHYTHMIC MOON
RESONANT MOON
GALACTIC MOON
SOLAR MOON
PLANETARY MOON
SPECTRAL MOON
CRYSTAL MOON
COSMIC MOON
DAY OUT OF TIME
7/25
PLASMA
DALI
SELI
GAMMA
KALI
ALPHA
LIMI
SILIO
TOOLKIN
HUMAN HOLON
PLANET HOLON
Left Hand
Right Hand
Left Foot
Right Foot

Original Copyright © 1990 José & Lloydine Argüelles   Design © 2002 [illegible]



Locus of God

*L of C=
Locus of Consciousness
Point at which time
vector and space
perception connect.
Result = AU
(Awareness Unit)

The higher the time
the greater the density
of celestial harmonics
per AU

Celestial Harmonic:
Index of synchronic incidence
(levels of co-occurances)

"Atemporality"

High Time
4 D

Domain of Synchronic Order

(S) > (RE)

Zone of Higher Consciousness

Threshold of Synchronicity

Low Time
3 D

The lower the time the greater
the increase of random events.
However, any random event
can trigger telepathic ascent
into high time depending on
clarity and duration of AU

"Temporality"

(RE) > (S)

Horizon of Space

*L of C

Near Space

Low Time
3 D

(RE) > (S)

Electron shells of element 79, Gold (AU)

Zone of Quantum Physics

Threshold of Synchronicity

Near space defined by
perimeter of sense organs
(and their technological
extensions)

(S) > (RE)

High Time
4 D

Far space is beyond all
but subliminal sensory
perception

High time = (S) > (RE)
Synchronicity (S) predominates

Low time = (RE) > (S)
Random Events (RE) predominate

Far space returns
to Locus of
Consciousness
via toroidal
sublimation

Locus of God

Model of "Vertical Time" in Relation to Horizontal Space

A Presentation of the Foundation for the Law of Time
T(E)=ART. Energy factored by Time equals Art.

The Dynamics of Time

Showing the Evolution of Time as Consciousness - T(E)=Art

GALACTIC BRAIN, or evolutionary spectrum showing index of energy-mind progression from atomic-cellular biological to purely mental conditions of being, T(E)=Art. Energy factored by time equals art.



Primary Post-life

Secondary Reflex: Life

Dominion of Time

Fourth-Dimension: Time

Hyperdimensional Time
Pure Mind

Locus of Time Travel

Subliminal Conscious

Super Conscious

Cosmic Conscious

Post-organic

Hyperorganic

Telepathy

13:20 PAN

Supernova

Continuing Conscious

Mind Returns to Source

GOD

Discovery of The Law of Time

Energy Released from Source

Conscious

12:60 Civilization

Stellar Mass

Instinct

Unconscious

Cosmic Unconscious

Preconscious

Quantum
Dimensional
Space
Pure Energy

Inorganic

Organic

Locus of Space Travel

Atomic

Cellular

Third-Dimension: Space

Domain of Potentiality

Primary Pre-life

Secondary Reflex: Life

13:20
Fourth-Dimensional
Timing Matrix
Source of
Time Vector
Potentialities

13:20 Matrix
Realizible Through
Fourth-Dimensional
Tools:
13 Moon Calendar,
Telektonon,
Dreamspell

Time Vector Potentialities:
Preconscious
Unconscious
Conscious
Discovery of the Law of Time
Continuing Conscious
Super Conscious
Subliminal Conscious

Vector Point Potentiality
Body in Time = Space

T(E)=Art

Noospheric Time Map - Wave Harmonic of History





260 Kin
4th Dimensional
Wheel of
Synchronic
Order =
Factor of
Synchronization=
1 G-Spin =



73 G-Spins = 52 Years

July 24, 2004
July 25, 2004
July 26, 2004
July 27, 2004
July 28, 2004

365-Kin
1 NET Day
3rd Dimensional
Biotelepathic
Wheel =
Factor of
Life Experience
(73:5)
(7:52)


Magnetic Moon 7.26-8.22
Lunar Moon 8.23-9.19
Electric Moon 9.20-10.17
Self-Existing Moon 10.18-11.14
Overtone Moon 11.15-12.12
Rhythmic Moon 12.13-1.9
Resonant Moon 1.10-2.6
Galactic Moon 2.7-3.6
Solar Moon 3.7-4.3
Planetary Moon 4.4-5.1
Spectral Moon 5.2-5.29
Crystal Moon 5.30-6.26
Cosmic Moon 6.27-7.24
July 25
1 2 3 4 5 6 7
8 9 10 11 12 13 14
15 16 17 18 19 20 21
22 23 24 25 26 27 28

Wavespell = 13 Tones
1 Tone = 1 Moon = 28 Kin
1 Kin = 1 NET Minute

◐ = 1 NET Minute
x 28 = 1 NET Hour.

7 NET Minutes =
$^{1}/_{4}$ Hour =
1 Week ◔

13:20 Matrix
Harmonic Module
Universal Synchronization
Gauge =
260 Kin = 1 Galactic Spin =
260 NET Minutes
13 NET Minutes =
1 Wavespell (13 Tones)
20 Wavespells =
9 NET Hours, 8 NET Minutes

NET
Noospheric
Earth
Time =
Earth = Body in Space =
Unit of measure of
index of synchronicity

T(E) = Art
T=13:20 Frequency of
Synchronization
where $T_v \rightarrow \infty$

E= Earth
Art= Blossomed Noosphere,
Earth consciousness
synchronically
unified



1 NET Hour = ◐
1 Moon

1 Moon (NET Hour)
= 1 Lunar Orbit

◐ =1 NET Hour x 13
= 1 NET Day
(13 NET Hours)
= 1 Solar Orbit
= 13 Lunar Orbits

52 NET Days
= 52 Solar Orbits
= 1 NET Year

= 73 Galactic Spins
= 13 Seed-Storm 4-Year
Bundles

1 4-Year Bundle =
1 NET Week

13 NET Days=
1 NET Season

1 NET Week=
4 Solar Orbits

1 NET Season=
13 Solar Orbits

Noosphere—Mind of Time on Earth


Noosphere
2013
2012
2011
2010
2009
2008
2007
2006
2005
2004
Magnetic
Lunar
Electric
Self-Existing
Overtone
Rhythmic
Resonant
Galactic
Solar
Planetary
Spectral
Crystal
Cosmic
Thirteen Moons of Peace
T(E)=Art
Necro
Sphere
The Choice
December 31
January 31
February 28/29
November 30
October 31
September 30
August 31
July 31
June 30
May 31
overhead
corporate stake
global warming
car payment
gain
budget
internet
ozone
AIDS
interest rates
G-7
terrorism
stock market
technology
investment
loss
television
OPEC
WTO
marketing
war
profit
taxes
insurance
Vatican
Hemi
Sphere
Biosphere

Necrosphere or Noosphere?

A Chronotopology of Transformation


Noosphere
Mind of Time on Earth
2012 and Beyond
Time-Formed Blossomed or Radiated Meaning
T(E)=ART
Great Calendar Change of 2004
Campaign for the New Time
PAN
PAN
The Inevitable Event 9-11 2001
Foundation for the Law of Time
On Peace and Time
Vatican Alert
Congress Law of Time
Biospheric Rights
Emergency UN
Change Peace Plan
Analysis of Artificial Time
Irregular Calendar
13 Moon Calendar
Planetary Moral Congress
First Planetary Day Tribunal
Judgment
UR Council
World Summit
2000
1999
1998
1997
1996
1995
1994
AD 1993
Seven Years of Prophecy
Discovery of
The Law of Time
Horizon of
Meaning
TELEK
TONON
Desert Storm
Kuwait
End of Cold War
Berlin
Wall
Roots of Meaning
13 Heaven 9 Hell Prophecy of Quetzalcoatl
Chilam Balam
1945
Hiroshima
Mechanization of Time
Gregorian Calendar
Conquest of Mexico
Pope Gregory I
Crusades
Muhammad
Pacal Votan

"Law of Time.
Making conscious
what was unconscious"

World Thirteen Moon
Calendar Change
Peace Movement and
The Discovery of the
Law of Time

1992. The Time Shift. Thirteen Moons in Motion; Turtle of Thirteen Moons; Treatise on Time.

1991. Dreamspell.

1990. Thirteen Moon Wavespell Calendar.

1989 Museum of Time.
13:20 - 12:60 Discovery
Root Meaning.

1987. Harmonic Convergence Root Source.
[Mayan Factor]

1984. Charles Muses "Studies in the Interactive Connectedness of Time. Chronotopology"

1971. NA. Kozyrev - $T_V\infty$"

1952. Discovery of tomb of Pacal Votan

Chronotopology:

A geography of time or radial time set defined by an event "Law of Time—Telektonon," which creates a root meaning from which time-formed, -blossomed, or -radiated meanings emerge.

Source meanings
of the Law of Time
radially resonated
toward seed point
creating horizon of
meaning

Paul J. Nahin

Time Machine Tales



The Science Fiction Adventures and Philosophical Puzzles of Time Travel

Springer

Science and Fiction

Editorial Board

Mark Alpert
Philip Ball
Gregory Benford
Michael Brotherton
Victor Callaghan
Amnon H. Eden
Nick Kanas
Geoffrey Landis
Rudi Rucker
Dirk Schulze-Makuch
Rüdiger Vaas
Ulrich Walter
Stephen Webb

More information about this series at http://www.springer.com/series/11657

Science and Fiction – A Springer Series

This collection of entertaining and thought-provoking books will appeal equally to science buffs, scientists and science-fiction fans. It was born out of the recognition that scientific discovery and the creation of plausible fictional scenarios are often two sides of the same coin. Each relies on an understanding of the way the world works, coupled with the imaginative ability to invent new or alternative explanations - and even other worlds. Authored by practicing scientists as well as writers of hard science fiction, these books explore and exploit the borderlands between accepted science and its fictional counterpart. Uncovering mutual influences, promoting fruitful interaction, narrating and analyzing fictional scenarios, together they serve as a reaction vessel for inspired new ideas in science, technology, and beyond.

Whether fiction, fact, or forever undecidable: the Springer Series "Science and Fiction" intends to go where no one has gone before!

Its largely non-technical books take several different approaches. Journey with their authors as they

- Indulge in science speculation – describing intriguing, plausible yet unproven ideas;
- Exploit science fiction for educational purposes and as a means of promoting critical thinking;
- Explore the interplay of science and science fiction – throughout the history of the genre and looking ahead;
- Delve into related topics including, but not limited to: science as a creative process, the limits of science, interplay of literature and knowledge;
- Tell fictional short stories built around well-defined scientific ideas, with a supplement summarizing the science underlying the plot.

Readers can look forward to a broad range of topics, as intriguing as they are important. Here just a few by way of illustration:

- Time travel, superluminal travel, wormholes, teleportation
- Extraterrestrial intelligence and alien civilizations
- Artificial intelligence, planetary brains, the universe as a computer, simulated worlds
- Non-anthropocentric viewpoints
- Synthetic biology, genetic engineering, developing nanotechnologies
- Eco/infrastructure/meteorite-impact disaster scenarios
- Future scenarios, transhumanism, posthumanism, intelligence explosion
- Virtual worlds, cyberspace dramas
- Consciousness and mind manipulation

Paul J. Nahin

Time Machine Tales

The Science Fiction Adventures and Philosophical Puzzles of Time Travel

Springer

Paul J. Nahin
Department of Electrical Engineering
University of New Hampshire
Durham, NH, USA

ISSN 2197-1188 ISSN 2197-1196 (electronic)
Science and Fiction
ISBN 978-3-319-48862-2 ISBN 978-3-319-48864-6 (eBook)
DOI 10.1007/978-3-319-48864-6

Library of Congress Control Number: 2016957723

© Springer International Publishing AG 2017
This work is subject to copyright. All rights are reserved by the Publisher, whether the whole or part of the material is concerned, specifically the rights of translation, reprinting, reuse of illustrations, recitation, broadcasting, reproduction on microfilms or in any other physical way, and transmission or information storage and retrieval, electronic adaptation, computer software, or by similar or dissimilar methodology now known or hereafter developed.
The use of general descriptive names, registered names, trademarks, service marks, etc. in this publication does not imply, even in the absence of a specific statement, that such names are exempt from the relevant protective laws and regulations and therefore free for general use.
The publisher, the authors and the editors are safe to assume that the advice and information in this book are believed to be true and accurate at the date of publication. Neither the publisher nor the authors or the editors give a warranty, express or implied, with respect to the material contained herein or for any errors or omissions that may have been made.

Printed on acid-free paper

This Springer imprint is published by Springer Nature
The registered company is Springer International Publishing AG
The registered company address is: Gewerbestrasse 11, 6330 Cham, Switzerland

Also By Paul J. Nahin

Oliver Heaviside (1988, 2002), Johns Hopkins
Time Machines (1993, 1999), Springer
The Science of Radio (1996, 2001), Springer
An Imaginary Tale (1998, 2007, 2010), Princeton
Duelling Idiots (2000, 2002), Princeton
When Least Is Best (2004, 2007), Princeton
Dr. Euler's Fabulous Formula (2006, 2011), Princeton
Chases and Escapes (2007, 2012), Princeton
Digital Dice (2008, 2013), Princeton
Mrs. Perkins's Electric Quilt (2009), Princeton
Time Travel (1997, 2011), Johns Hopkins
Number-Crunching (2011), Princeton
The Logician and the Engineer (2013), Princeton
Will You Be Alive Ten Years From Now? (2014), Princeton
Holy Sci-Fi! (2014), Springer
Inside Interesting Integrals (2015), Springer
In Praise of Simple Physics (2016), Princeton

Frontispiece: The Pioneers of Time Travel

The scientific pioneers were Albert Einstein (1879–1955) and Kurt Gödel (1906–1978), good personal friends who are shown here in 1954 at the Institute for Advanced Study in Princeton, New Jersey, in a photo taken by Richard Arens. It was Einstein's 1916 general theory of relativity (theory of gravity) that Gödel used as the basis for his 1949 paper that was the first to show that the general theory does **not** forbid time travel into the past.

The literary pioneer of time travel was of course Herbert George Wells (1866–1946), who is shown here as a college freshman cut-up around 1885. The photograph was taken as a prank by an unknown friend while Wells was a student in a biology course given by Thomas Huxley, at the Normal School of Science in

South Kensington (a branch of the University of London). A far too thin and impoverished Wells was then still a teenager, and *The Time Machine* lay a distant 10 years in the future.

Einstein/Gödel photograph courtesy of the American Institute of Physics Emilio Segré Visual Archives of the AIP Niels Bohr Library. Wells photograph courtesy of the rare Books and Special Collections Department of the Library of the University of Illinois at Urbana-Champaign.

A Note on the Story Citations and Science Fiction History

> "You will find it a very good practice always to verify your references, sir."
> —advice given in 1847 to a young scholar by Martin Joseph Routh, President of Magdalen College, Oxford

Most of the pulp science fiction stories I've cited in this book, in their original form as ink on paper, have long since vanished from our region of spacetime and exist today only (alas) on microfilm reels in scholarly vaults. I am especially indebted to Texas A & M, the Claremont Colleges, the California State Universities at Northridge and Fullerton, Mount Holyoke College, the New York City Public

Library, and the University of Delaware, for giving me access via Inter-Library Loan (through my home institution, the University of New Hampshire) to their extensive archives of ancient science fiction magazines.

A number of the really good stories *have* been anthologized, however, and so are still readily available today in book form. In essentially all cases, though, for historical reasons, I've given the original publication information (magazine and date). You can find which of the stories cited are available in one or more anthology reprints by going to an immensely useful, searchable database on the Web, at: http://www.isfdb.org, and I gratefully thank all those in the science fiction community responsible for creating and maintaining that database.

The following two books by science fiction historian Sam Moskowitz (1920–1997), who lived through what Isaac Asimov called the 'Golden Age of [magazine] Science Fiction,' may be difficult to find today but, if you are interested in the early history of *magazine* science fiction (beyond simply the subgenre of time travel), the hunt for them will be well worth your time:

Science Fiction by Gaslight: a history and anthology of science fiction in the popular magazines, 1891–1911 (World Publishing Company 1968);
Under the Moons of Mars: a history and anthology of "The Scientific Romance" in the Munsey Magazines, 1912–1920 (Holt, Rinehart and Winston 1970).

Some First Words

> Is time travel in principle (never mind the difficulties) a possibility? It has received some thought in the past and deserves some more.
>
> —David Park, in his 1980 book *The Image of Eternity*

> He used to have quite a reputation, but the last couple of years he's been working on time . . . You know, time travel, that sort of rot. An A-1 crackpot.
>
> —a character (discussing a colleague) disagrees with Park, in Mack Reynolds' "Advice from Tomorrow," *Science Fiction Quarterly*, August 1953

In 1993 the first edition of my book *Time Machines* was published by the Press of the American Institute of Physics. In 1999, after Springer acquired AIP Press, the second edition of that book appeared. So, is this the third edition? Well, yes *and* no. It *is* because large chunks of the 1999 edition are still here, along with new discussions of the advances by physicists and philosophers that have appeared in the intervening 18 years. The prime example of that centers on the time travel paradoxes. Those discussions contain mostly what is in the second edition, but they have also been brought up to date with the latest thinking on the paradoxes, by physicists and philosophers.

And yet this book is *not quite* the third edition because the emphasis is now on the philosophical and on science fiction, rather than on physics as it was when written for AIP Press. In that spirit there are, for example, no Tech Notes filled with algebra, integrals, and differential equations, as there are in the first and second editions of *Time Machines*. That's because I wish to avoid having this book seem to be simply a long physics treatise. I have, in fact, some sympathy with the following views, expressed by two philosophers:

"There is one metaphor in the physicist's account of space-time which one would expect *anyone* to recognize as such, for metaphor is here strained far beyond the breaking point, i.e., when it is said that time is 'at right angles to each of the other three dimensions.' Can anyone really attach any meaning to this—except as a recipe for drawing diagrams?"[1]

and

"This is from the outset a study in descriptive metaphysics. In consequence, I shall have nothing to say about twice-differentiable Lorentzian manifolds, Minkowski diagrams, world-lines, time-like separations, space-time worms [a 'thick' world-line], or temporal parts."[2]

I don't *completely* endorse these sentiments, however, and so please understand that I am not denying the ultimate importance of *physics* when it comes to achieving a deep understanding of time travel. To quote yet another philosopher,

"Arm chair reflections on the concept of causation [are] not going to yield new insights. The grandfather paradox is simply a way of pointing to the fact that if the usual laws of physics are supposed to hold true in a chronology violating space-time, then consistency constraints emerge. *[To understand these constraints] involves solving problems in physics, not armchair philosophical reflections* [my emphasis]."[3]

I could not agree more. So, in *Time Machine Tales* you *will* find some physics. In support of time travel to the future (and in how to make a wormhole time machine for travel into the past), for example, I'll show you a high school level derivation of the famous time dilation formula from special relativity. There are some spacetime diagrams, some simple algebraic manipulations, and here and there just a touch of freshman calculus; even the metric tensor gets a few words, too. But it is, admittedly, pretty light-weight stuff.

So, while certainly saluting the premier position of physics, *Time Machine Tales* is not a scholarly, in-depth treatment of time travel physics. Rather, it is an examination of how science fiction writers (and many philosophers, too) have viewed time travel. (Even in the physics discussions, science fiction will regularly appear.) Those views, by their very nature, are far more romantic than are those of hardcore theoretical physicists. History has shown, of course, that the results of the work of theoretical physicists may, in the end, prove to actually be far more astonishing than anything fiction writers cook-up—and if there is any scientific subject for which that may again prove to be true it's time travel—but for us, here, it will be the fiction writer who has center stage.

The philosophers will be only slightly less important in this book. While much of the early philosophical literature on time travel and backwards causation reads like imaginative fairy tales spun out of vacuous vapors (more on this soon), many modern philosophers have shown themselves to be quite sophisticated. What they have written deserves serious consideration by anyone interested in time travel, and that includes physicists. However, while the time travel interests of philosophers and physicists have a lot of overlap, those interests are *not* in total agreement. For example, while both groups talk of the grandfather paradox, the philosophers worry in particular about motivation (*why* the murderous mission?), while physicists have *never* to my knowledge asked themselves that question[4] (other than to figure out how to avoid it!). After all, philosophers talk of flesh-and-blood humans as time travelers, while the physicists send only billiard balls (with no personal identities or memories) on time trips into the past for the *expressed purpose* of avoiding the messy human issues of 'motivation' and free will. This approach by physicists isn't because they are cold and emotionless. It is a useful strategy because, if it can be shown that a mere billiard ball can travel into the past then, as one *philosopher* pointed out long ago, "It is implausible that it should be possible for some physical systems to travel back in time, and not others. Thus, if we suppose that simple objects can time-travel . . . then we must suppose that more complicated systems, e.g., human beings, can also time-travel."[5]

---

[1] C. W. K. Mundle, "The Space-Time World," *Mind*, April 1967, pp. 264–269.

[2] J. F. Rosenberg, "One Way of Understanding Time," *Philosophia*, October 1972, pp. 283–301.

[3] John Earman, "Recent Work on Time Travel," in *Time's Arrows Today: recent physical and philosophical work on the direction of time* (Steven F. Savitt, editor), Cambridge University Press 1995, pp. 268–310. We'll discuss the idea of *consistency constraints* in some detail later in the book. Earman is Professor Emeritus of History and Philosophy of Science at the University of Pittsburgh.

For the most part, philosophers and physicists have worked at the extreme, opposite points of the time travel spectrum. Much better, I think, would be to adopt the following, more balanced position advocated recently: "The study of time machines is a good opportunity for forging a partnership between philosophy and physics. Of course, philosophers have to recognize that in this particular instance the partnership is necessarily an unequal one since the mathematical physicists have to do the heavy lifting. But it seems clear that a little more cooperation with philosophers of science in attending to the analysis of what it takes to be a time machine could have led to some helpful clarifications in the physics literature."[6]

In the past, philosophers gained a reputation for being just a bit too 'unconstrained by the facts' for scientific tastes—as the English mathematician Augustus De Morgan (1806–1871) wrote in an 1842 letter, "There are no writers who give us so much *must* with so little *why*, as the metaphysicians"[7]—but I do think today's physicists would do well to reexamine that harsh opinion.

Philosophers of the 'old school' may look askance at a non-philosopher (me!) leveling criticism at them, and so let me step aside and quote from a member of the

---

[4] Nicholas J. J. Smith, "Why Would Time Travelers Try to Kill Their Younger Selves?" *The Monist*, July 2005, pp. 388–395. As Smith writes, "[Motivation] does not impact upon the possibility, or even the likelihood of backwards time travel. Yet it is deeply puzzling, and we will have no idea what time travel would actually be *like* until we explore it." See also Peter B. M. Vranas, "Can I Kill My Younger Self? Time Travel and the Retrosuicide Paradox," *Pacific Philosophical Quarterly*, December 2009, pp. 520–534.

[5] P. Horwich, "On Some Alleged Paradoxes of Time Travel," *Journal of Philosophy*, August 1975, pp. 432–444.

[6] John Earman, Christopher Smeenk, and Christian Wüthrich, "Do the Laws of Physics Forbid the Operation of Time Machines?," *Synthese*, July 2009, pp. 91–124.

[7] D. J. Cohen, *Equations from God: pure mathematics and Victorian faith*, The Johns Hopkins University Press 2007, p. 119.

'modern school' of philosophical thought: "Space-time is the basic spatiotemporal entity. Many philosophers have mouthed this truth, but few have swallowed it, and very few have digested it . . . An appreciation of this truth is crucial to what is commonly referred to as the philosophy of space and time . . . In large measure the lack of progress in this area can be traced to the fact that philosophers have not taken seriously the corollary that talk about space and time is really talk about the spatial and temporal aspects of spacetime."[8] This is a polite way of telling philosophers that they had better learn some physics!

What provoked those harsh words was that 'modern' philosopher's perception that 'old school' philosophers were not talking science when they wrote of space and time, but rather were in the business of telling each other irrelevant stories and myths, a curious philosophical approach involving the 'telling of tales' that reached its peak in the early and mid-1960s. Spacetime story telling seems to have started with a paper by the Oxford philosopher Anthony Quinton (1925–2010), who argued[9] that although there can be multiple, disjointed spaces, there can only be a single time that is the same for everyone, everywhere. The issue is *not* the truth or not of that assertion (Newton believed it, modern physicists don't), but rather Quinton's technique for arriving at it: myth construction.

Myth construction strikes those trained in the technical sciences as, while perhaps interesting—even physicists, after all, can enjoy a good fairy tale now and then—something quaint and totally beside the point. In his paper Quinton tells a fairy tale about how he thinks someone can live continuously in time and yet, via dreaming, be in two different spatial worlds; when awake he is in one world, while when the person is asleep he is in the other. Quinton argues that this multispatial myth is plausible, but that a search for an analogous multitemporal myth is doomed. This prompted a reply[10] from another 'old school' philosopher who rebutted Quinton with an even more outlandish counter-myth involving "the warring tribes of Okku and Bokku"!

It was this back-and-forth spinning of hypothetical tales that caused the 'modern' philosopher to write in his paper (note 30) that "the procedure for arriving at answers to these questions [about space and time] adopted by Quinton and most other ['old school' philosophers] is, to say the least, a curious one: a story is told about a mythical land—usually called something like the land of Okkus-Bokkus [which is now seen to an outrageous pun]—and then we are asked what we would say if confronted by experiences like those of the Okkus-Bokkusians. As often happens with such a question, people have said all sorts of things, not all of which are interesting or enlightening."

Another modern philosopher was even less gentle in his rejection of the fairy tale approach to spacetime physics: "Quinton [and others of a similar approach invite us] to say what we should think in certain strange circumstances which they describe within common-sense language [as opposed to scientific terminology]. I must say that if I found myself in the circumstances which they describe I just would not know what to think. Probably I should simply conclude that I had gone mad . . . It looks as though these writers are inviting us to consider *what we should say if we knew no science* [my emphasis]."[11]

---

[8] J. Earman, "Space-Time or How to Solve Philosophical Problems and Dissolve Philosophical Muddles Without Really Trying," *Journal of Philosophy*, May 1970, pp. 259–276.

[9] A. Quinton, "Spaces and Times," *Philosophy*, April 1962, pp. 130–147.

[10] R. G. Swinburne, "Times," *Analysis*, June 1965, pp. 185–191.

Even before the modern philosopher (note 30) wrote in 1970 to complain about myth-making, another had already done so: "Whenever a human being produces an argument which opens 'Suppose I had 23 senses . . .,' 'Suppose I were God . . .,' 'Suppose I experienced objects extended in four spatial dimensions . . .,' we can protest that the argument is worthless. For in supposing that he has transcended our human point of view, he has also transcended the limits of our understanding."[12] As this author concluded his very funny paper, such opening sentences are the signatures of myths from "The Philosopher's Fairy Tale Book."

The strained relationship between myth-making philosophers and physicists, especially concerning time travel, has a historically interesting antecedent in the 1920s negative reaction among many over Einstein's theories of relativity (the very theories that give apparent life to time travel). To illustrate my point, consider the October 1913 letter Oskar Kraus (1872–1942), a philosophy professor at the German University in Prague, sent to Ernst Gehrcke (1878–1960), a physics professor at the Reich Institute of Physics and Technology in Berlin. Both men were opponents of Einstein but, as Kraus wrote in his letter, it was only Gehricke among the physicists he considered to be sympathetic to him: "[I] would not know . . . anyone else but you who as a specialist would not reject the intervention of a philosopher from the start."[13]

So, I think Earman's proposal a sound one, an echo in fact of similar words that the physicist Kip Thorne wrote (in the Foreword to the second edition of *Time Machines*) concerning science fiction writers: "Smart physicists seek insight everywhere, including from clever science fiction writers who long ago began probing seriously the logical consequences that would ensue if the laws of physics permitted time travel."[14]

To emphasize this new, combined, diversified focus (but also to retain some connection with my earlier books) is the reason I have altered the title, just a bit. In addition, each chapter now concludes with several open-ended questions, suitable for motivating either classroom discussions or more extensive essay responses.

---

[11] J. J. C. Smart, "The Unity of Space-Time: Mathematics Versus Myth Making," *Australasian Journal of Philosophy*, (no. 2) 1967, 214–217.

[12] M. Hollis, "Times and Spaces," *Mind*, October 1967, pp. 524–536. Hollis ends by saying he is prepared to accept the failure of his paper to convince many of his colleges to change their ways, and he is waiting for one of them to write a paper opening with "Twice upon a time in another space no distance in any direction from here . . ."!

[13] Quoted from the Introduction to Milena Wazeck, *Einstein's Opponents: the public controversy about the theory of relativity in the 1920s*, Cambridge 2014 (published in German in 2009).

[14] Thorne is Professor Emeritus of Physics at the California Institute of Technology.

Teachers, in particular, may find this a useful feature if using the book in an academic setting. The book ends with reprints of two of my own published time travel stories (one from *Analog* and the other from *Omni*), with each serving as an illustration of technical issues raised in the book. From my own teaching of an undergraduate honors class in time travel at the University of New Hampshire, I think the assigning of story writing to be an excellent tool for teachers to use. I found reading student stories to be a lot of fun, and students may well surprise teachers with innovative ideas.

Now that I've mentioned story writing, let me say something about the heavy presence of time travel science fiction stories in this book, the majority of which originated in the often maligned pulp magazines of the 1920s through the 1950s. 'Pulp' has long been burdened with a bad literary reputation. As the editor of one anthology of pulp fiction bluntly put it, "Pulp equated with rubbish. Crap of the basest nature."[15] Part of the reason for that was cosmetic; as I wrote in an earlier book, "The term *pulp* came from the use of inexpensive wood-pulp—you could *feel* the lumpy wood chips in each ragged, untrimmed page—to make paper that was far too crummy for the use by any publisher of 'words meant to last.' Such paper quickly yellowed, turned brittle, and finally, amid billowing clouds of bits and pieces, entered into eternal oblivion. Think of the paper used in your newspaper before its final contribution to civilization in the bottom of your cat's litter box; pulp was worse."[16]

And then a little later, in the same book, "The stories in *Amazing* [*Stories* magazine] were 'read it in the morning, forget it by dinnertime' adventure fiction, the stuff you'd put inside a newspaper if on a crowded train or bus so fellow passengers wouldn't know what a low-grade mind you had. The transient nature of pulp fiction was independent of its literary quality, as the cheap acid-based paper that the stories were printed on began to oxidize and literally burn-up as soon as it rolled off the press. In the introductory essay to a 1950 collection of pulp-detective Philip Marlowe stories (*Trouble Is My Business*), mystery writer Raymond Chandler commented on this when he wrote 'pulp fiction never dreamed of posterity.' Pulp fiction was synonymous with trash fiction, and the nature of much of early pulp SF has been aptly described as 'scientific pornography for the mechanically minded,' and 'writing which drooled over descriptions of technology.'"

When publisher Hugo Gernsback (1884–1967) brought out the first issue of *Amazing Stories* in April 1926, it was the first pulp devoted totally to science fiction. With its masthead motto of "Extravagant Fiction Today—Cold Fact Tomorrow," and with the illustration on the contents page of each issue showing a muscular Jules Verne bursting from his grave in the heroic, up-up-and-away pose made famous years later by Superman, there could be no doubt as to what kind of fiction the reader would find under the dramatic, multi-colored cover art. It was fiction populated with mad scientists, and half-naked woman about to be ravished by alien invaders from outer space; all in all, stuff of interest only to teenage boys and imbecilic adults.[17]

---

[15] Maxim Jakubowski, *The Mammoth Book of Pulp Fiction*, Carroll & Graf 1996.

[16] P. J. Nahin, *Holy Sci-Fi!: where science fiction and religion intersect*, Springer 2014.

How else, after all, to explain the publication of one tale[18] that was given the following heart-stopping editorial introduction: "Professor Lambert deliberately ventures into a Vibrational Dimension to join his fiancée in its magnetic torture-fields"? In defense of many of the readers of early pulp science fiction, however, not all were attracted by such nonsense. Just 2 months later (June 1931) one reader wrote to the same magazine to complain of masculine heroes saving weeping women from ungodly horrors: "Just why do you permit your Authors to inject messy love affairs into otherwise excellent imaginative fiction? Just stop and think. Our young hero-scientist builds himself a space flyer, steps out into the great void, conquers a thousand and one perils on his voyage and amidst our silent cheers lands on some far distant planet. Then what does he do? He falls in love with a maiden—or it's usually a princess—of the planet to which the Reader has followed him, eagerly awaiting and hoping to share each new thrill attached to his gigantic flight. But after that it becomes merely a hopeless, doddering love affair ending by his returning to Earth with his fair one by his side. Can you grasp that—a one-armed driver of a space-flyer! ... We buy A.S. for the thrill of being changed in size, in time, in dimension ... not to read of love ... I wish ... for plain, cold scientific stories sans the fair sex."

Here's another example, this one of the sort of tale that gave an aroma of the sophomoric to 'golden age' time travel science fiction. It was a story of a young man of the far future, with access to a time machine, who wants to see a dinosaur before he dies. So back he travels, back, back, until he at last finds himself in a "subterranean cave, dark and foul-smelling." At first he is puzzled (did dinosaurs live underground?), but then suddenly he hears a thundering roar and sees a huge black shape in the gloom. There can be no doubt now; it *is* a dinosaur, and he sees its red, gleaming eyes just as it crushes him into a pancake. But that's okay; he saw a dinosaur before he died. Then comes the dénouement. He hadn't really gone back quite as far as the Jurassic period, but only to the twentieth century, where he has been run down by the local express train in a subway tunnel![19]

---

[17] This was particularly thought to be the case for readers of the romance pulps, written for young women in the 1930s and 1940s (a separate and distinct audience from that of the science fiction pulps). As one commentator wrote on that genre, the heroes and heroines of such tales often displayed the "mental equipment of a banana split," with the implication that the same might be said of the readers, themselves. (See Margaret MacMullen, "Pulps and Confessions," *Harper's Monthly Magazine*, June 1937.) I don't think, however, that this particular complaint generally applied to the pulp science fiction readership. I'll have much more to say about Gernsback and early pulp science fiction speculations concerning time travel, in Chap. 4.

[18] T. Curry, "Hell's Dimension," *Astounding Stories*, April 1931.

[19] R. G. Thompson, "The Brontosaurus," *Stirring Science Fiction*, April 1941. In the editors of *Stirring*'s defense, notice the month: maybe this story was *meant* to be a joke. If so, it was an admirable success.



Vibrating into new dimensions was, apparently, a popular idea in 1930s pulp science fiction. This 'super science' gadget operated by vibrating an object faster than light, whereupon the Lorentz-FitzGerald contraction formula (see Chap. 3) predicts an *imaginary* size for the object—which means (so we are told) that the object has entered "another plane of existence." The inventor (the fellow with the gun) is inviting his grim-faced assistant to give the gadget a try. The original caption reads "Get into that vibrator! Get in, I say!"

Illustration for "Into Another Dimension" by Maurice Duclos, *Fantastic Adventures* November 1939 (art by Kenneth J. Reeve), © 1939 by Ziff-Davis Publishing Co., reprinted by arrangement with Forrest J. Ackerman, Holding Agent, 2495 Glendower Ave., Hollywood, CA 90027

Today, however, the need to apologize for science fiction tales about time travel isn't quite so necessary. Now and then, in fact, you'll even find one of the better pulp stories cited in highly mathematical papers on time machines in the *Physical Review D*, one of the most important scholarly physics journals. Even those physicists and philosophers who mostly ignore science fiction—except perhaps to make slightly condescending remarks—would, if honest, admit that their early teenage interest in time travel was sparked by reading a really good science fiction story, and not by working their way through a physics textbook. Yes, when the physics eventually came later, it was very good—but the science fiction came *first*, and it was pretty good, too.[20] It's in a 1937(!) tale, for example, that we find the claim for consistency around a closed loop in time, *decades* ahead of the physicists and philosophers.[21] And when you get to the final section of Chap. 4, I think you'll find it difficult to believe that Everett's many-worlds interpretation of quantum mechanics, dating from the late 1950s (which avoids the standard paradoxes of time travel) wasn't inspired by some youthful reading of science fiction from the 1930s and 1940s.

In a number of places in this book you'll find my comments on how science fiction has occasionally anticipated physicists on the subject of time machines and time travel. This is *not* to be interpreted as some sort of 'gotcha' in favor of science fiction. Far from it. When push comes to shove, physics *always* wins. This situation was specifically addressed by Joe Haldeman, in an afterword to his 2007 novel *The Accidental Time Machine*. There he wrote, about when he started in 1971 to write his earlier, now classic novel *The Forever War*, "I needed a way to get soldiers from star to star within a human lifetime, without doing too much violence to special and general relativity. *I waved my arms around really hard* [my emphasis] and came up with the 'collapsar jump'—at the time, collapsar was an alternate term for 'black hole,' though I was unaware of the latter term [because John Wheeler had invented it only 4 years before, as discussed in Chap. 1 and note 106]." And then Haldeman admitted "It's a truism of science fiction that if you predict enough things, a few of them are going to come true. . . . What I think it actually demonstrates is that *if you wave your arms around hard enough* [my emphasis], sometimes you can fly."

Now, there is one feature common to all books on time travel to the past (which is the central topic treated here, of course) that I would like to clearly state. It's obviously a subject of vast interest to physicists, and yet it offers (as far as I know) *absolutely no hope of suggesting even a single experiment for study*. (As far as I know, nobody is building a time machine in their basement.) A suggestion *has* been made that it may be possible to detect, in the *present*, the effects of the *future* operation of "man-made time machines, which could be of a size traversable by humans," that is, machines with a 1-m spatial extent offering a one second trip into the past.[22] With the best technology available today, however, the calculated effects on the proposed two-particle scattering experiment are orders of magnitude too small to measure.

---

[20] The view expressed by Vladimir Voinovich's time traveler in his 1986 novel *Moscow 2042* (Science fiction ... is not literature, but tomfoolery like the electronic games that induce mass idiocy.) is, I think, wrong. For an interesting presentation on the role of science fiction in exciting an interest in science among youngsters, see the paper by Frederik Pohl (1919–2013), "Science Fiction: the stepchild of science," *Technology Review*, October 1994, pp. 57–61. In this essay Pohl, a well-known writer of science fiction and editor of *Galaxy Science Fiction* and *If* magazines, writes "Science fiction is [the ultimate protection] against future shock . . . if you read enough of it, nothing will take you entirely by surprise." Not even time travel.

[21] P. S. Miller, "The Sands of Time," *Astounding Stories*, April 1937.

[22] S. Rosenberg, "Testing Causality on Spacetimes with Closed Timelike Curves," *Physical Review D*, March 15, 1998, pp. 3365–3377.

This situation is really unprecedented in the history of science.[23] To cynics, it may seem to be a bit like writing learned papers on the thermodynamics of fire-breathing dragons (which, like other mythological entities—and time machines, too—have yet to be seen)! This one fact has opened the doors—and has kept them open for decades—for philosophers and science fiction writers, who can endlessly debate back and forth on all aspects of time travel to the past with nary a single experimental fact to complicate their lives. For physicists the situation is naturally frustrating, but for philosophers and science fiction writers it's a dream come true. This isn't to say it's *all* basically theological in nature. Both the physicists and the philosophers *have* written many fascinating papers and books and, of course, so have science fiction writers. Mathematical physics *has* been advanced.

Still, despite all of the theoretical work done in the last 30 years, work that has made it reasonable to seriously talk of 'time travel' and 'time machines,' I suspect many would nonetheless agree with these words from more than 75 years ago: "Of all the fantastic ideas that belong to science fiction, the most remarkable—and, perhaps, the most fascinating—is that of time travel . . . Indeed, so fantastic a notion does it seem, and so many apparently obvious absurdities and bewildering paradoxes does it present, that some of the most imaginative students of science refuse to consider it as a practical proposition."[24] For some, time travel is an even more unlikely possibility than (as declared by Robert Lewis Stevenson) is the "welding of ice and iron." Not all physicists and philosophers view the time travel/paradox arguments as convincing, however. Provocative, yes, of course, but many are not yet prepared to write 'signed, sealed, and delivered' at the end.

So, keep reading and I think you'll discover why there *are* those who are not so quick to dismiss the possibility of following the fantastic world line of H. G. Wells' intrepid Time Traveller[25] into the future. And, just maybe, into the distant past, too.

---

[23] Perhaps, however, I am too hasty. More recent theoretical calculations suggest that wormholes connecting our universe with other universes would, after converting into time machines, have characteristic thermal signatures. See P. F. González-Díaz, "Thermal Properties of Time Machines," *Physical Review D*, 2012, pp. 105026-1 to -7 which, however, concludes that a search for such signatures would be "quite difficult [with the] instruments available."

[24] I. O. Evans, "Can We Conquer Time?" *Tales of Wonder*, Summer 1940.

[25] The Time Traveller is never named in Wells' 1895 novel *The Time Machine*. An earlier (1888) attempt at a time machine story, with the awful title *The Chronic Argonauts* (the "chronic" was apparently inspired by the word *chronology*), so embarrassed Wells that he later called it "imitative puerile stuff," "clumsily invented, and loaded with irrelevant sham significance," and "inept," and so he hunted down and destroyed every copy of it that he could find. You can find *The Chronic Argonauts* reprinted in *The Definitive Time Machine* (H. M. Ceduld, editor), Indiana University Press 1987. The hero in that work *was* named: Dr. Moses Nebogipfel. There is one passage in *The Time Machine* that does tantalize; as the Time Traveller explores a museum of "ancient" artifacts in the Palace of Green Porcelain (they are, of course, artifacts of our *future*) he reveals that "yielding to an irresistible impulse, I wrote my name upon the nose of a steatite monster from South America that particularly took my fancy." Thus, the Traveller *has* given his name, but his signature exists only in the future, in a museum of the past that is yet to be built.

For Further Discussion

For time travel to the past to make any sense, the past must in some sense ‘still be there.’ This is a concept that we’ll find later in the book to have significant support in relativistic physics, but for now let’s limit ourselves to a purely romantic view. As an example of this, consider this passage by Canadian writer Grant Allen (1848–1899), from the Introduction to his 1895 time travel novel *The British Barbarians*: “I am writing in my study on the heather-clad hill-top. When I raise my eye from my sheet of foolscap, it falls upon miles and miles of broad open moorland. My window looks out upon unsullied nature. Everything around is fresh and pure and wholesome . . . But away below in the valley, as night draws on, a lurid glare reddens the north-eastern horizon. It marks the spot where the great wen of London heaves and festers.” I personally find it quite tempting to imagine Allen somehow still there in his study of 1895, and of heaving and festering late-Victorian London, too, with H. G. Wells himself in the middle of it, still reading the first rave reviews of *The Time Machine*. In Wells’ novel The Time Traveller journeys into the far future, while in Allen’s work the protagonist is a twenty-fifth century anthropologist who has traveled back to the past of the late nineteenth century to study the ‘British barbarians.’ Read Allen’s novel (it’s available on the Internet, for free, as a Project Gutenberg book) and comment on the significance of its appearance at virtually the same time as Wells’ great work. Why do you think Wells’ novel is remembered, and Allen’s is not?

In the opening paragraph of his paper “The Conundrum of Time Travel” (*Croatian Journal of Philosophy*, No. 37, 2013, pp. 81–92), Anguel Stefanov writes “Needless to say . . . the problems concerning time travel are being still tackled by science fiction only, but resolved by science proper neither theoretically, nor practically.” Do you think this is correct?

Eventually every genre of writing becomes the target for parody, in which the *form* of the genre serves as the framework for what (it is hoped) is a humorous mockery. The most famous example of this, perhaps, is the annual

(continued)

Edward Bulwer-Lytton contest in writing a take-off on the long-winded opening line of the 1830 novel *Paul Clifford*, by Bulwer-Lytton (1803–1873). That opening line *is* a wonder (a masterpiece of purple prose): “It was a dark and stormy night; the rain fell in torrents—except at occasional intervals, when it was checked by a violent gust of wind which swept up the streets (for it is in London that our scene lies), rattling along the housetops, and fiercely agitating the scanty flame of the lamps that struggled against the darkness.” Here’s a recent (from the 2015 contest) spoof: “The Contessa’s heart was pounding hard and fast, like an out-of-balance clothes washer, which can get that way if you mix jeans with a lot of light things, though the new ones have some sensor thing to counteract that or shut off, but the Contessa’s heart didn’t have anything like that, so she had to sit down and tell Don Rolando to keep his hands to himself for a while.” Science fiction isn’t immune to such fun, and a good example of that can be found in the September 14, 2015, issue of *The New Yorker*, which has (on p. 50) “Eight Short Science-Fiction Stories” by Paul Simms. Here’s the one I laughed hardest at: “The Gene-Splicers had tinkered with the DNA, producing a race of warriors who craved just two things: the thrill of battle and the taste of their own feet. They hungered for battle. They literally ate their own feet. None survived to reproduce, and within a few short years they were all gone. The Gene-Splicers chalked it up to experience, and decided to try harder the next time.” That, and the other seven spoofs by Simms, cut across a wide swath of science fiction, but one theme noticeably absent was that of time travel. Try your hand at writing a *short* (fewer than 500 words) time travel spoof, and be prepared to read it aloud to an audience of your peers.

The tale “Through the Dragon Glass” by Abraham Merritt (1884–1943) appeared in the early pulp magazine *All-Story Weekly* of November 24, 1917. It described the discovery of a passage through an ancient Chinese mirror into an alternate world. One *might* think of this as an early conception of a wormhole, but more likely it may remind you mostly of Lewis Carroll’s *Through the Looking Glass*. More interesting for us, in this book, is a story written 75 years ago that describes a gadget connecting two regions of spacetime, with a time shift of a week between the two regions. (See “Time Locker” by Lewis Padgett, in the January 1943 issue of *Astounding Science Fiction*.) The gadget falls into the hands of a crooked lawyer who, not understanding what he has, ends up accidently killing himself. As the story ends, the inventor of the gadget ruefully muses to himself that the lawyer

(continued)

"must have been the only guy who ever reached into the middle of next week—and killed himself!" The gadget is, in everything but name, a wormhole time machine. Speculate on how such a spacetime structure could appear in a *science fiction magazine*(!) decades before there was any discussion of such a possibility in the physics world.

Adjectives used to describe many of the stories in the science fiction pulps included *primitive*, *trashy*, *tawdry*, *silly*, *absurd*, *crummy*, *ludicrous*, and *cheap*. One early pulp magazine actually boasted, of its contents, that they contained "sensational fiction with *no* philosophy." Speculate on how such a low-level 'literary' form could have been so successful in finding an enthusiastic audience for time travel paradox tales, tales that are in fact by their very nature simply *stuffed* with philosophical issues. As an example of the tremendous emotional power a particularly well-written time travel story can deliver, read Isaac Asimov's "The Ugly Little Boy" (*Galaxy Science Fiction*, September 1958). Asimov rated this story as among his most favorite of all the many he wrote. If you can read it without ending in tears, well, …. An excellent modern historical work on the pulps (of all genres, not just science fiction) is by Lee Server, *Danger Is My Business: an illustrated history of the fabulous pulp magazines, 1896–1953*, Chronicle Books 1993.

A literary fascination with time was already 'in the wind' when Wells wrote his *Time Machine*, as with Oscar Wilde's 1890 novel *The Picture of Dorian Gray*. Even decades earlier than that one can find a hint of time travel of a sort in Edgar Allen Poe's 1841 short story "Three Sundays in a Week." And just 4 years later Henry Wadsworth Longfellow wrote his haunting poem "The Old Clock on the Stairs," with these opening words:

Somewhat back from the village street
Stands the old-fashioned country-seat.
Across its antique portico
Tall poplar-trees their shadows throw;
And from its station in the hall
An ancient timepiece says it all,—

"Forever—never!

(continued)

Never—forever!"

The most interesting of all pre-Wells time travel fiction to appear in a mass-audience publication was, I think, the short story "The Old Folks Party" by Edward Bellamy, printed in the March 1876 issue of *Scribner's Monthly*. In this story a group of teenagers, who belong to a weekly discussion club, agree that at their next meeting they will all come dressed and behaving as they believe they will be dressing and behaving 50 years in the future. Also attending will be the grandmother of one of the young ladies. The meeting of the "old folks" takes place, and it invokes such powerful feelings of mortality that, at last, one of the young men can stand it no more: "Suddenly Henry sprang to his feet and, with the strained, uncertain voice of one waking himself from a nightmare, cried:—'Thank God, thank God, it is only a dream,' and tore off the wig, letting the brown hair fall about his forehead. Instantly all followed his example . . .." The young people then began to laugh with relief at once again being young, until they notice the grandmother is crying. Her granddaughter instantly knows what is wrong and says, "Oh, grandma, we can't take you back with us." Read, compare, and contrast, these works by Wilde, Poe, Longfellow and Bellamy, with the 'scientific' presentation of time travel by Wells.

Acknowledgements

My name is on *Time Machine Tales* as the author, but there are many others without whose help I could not have written it. For this, the revised and updated third edition of the original 1993 book *Time Machines*, I am enormously grateful to the publisher, Springer Science + Business Media, and to my physics editors at Springer, Dr. Sam Harrison and his assistant Ho Ying Fan in New York City. They made an intellectually demanding and inherently lengthy project (one that could easily have turned into a nightmare) a pleasant one. Springer's New York City-based editorial assistant Irene Bruce smoothly handled the administrative details of transforming the book from typescript to print. And to Serguei Krasnikov in Russia, Frank Arntzenius and Roberto Casati in England, Francesco Gonella in Italy, and Geoff Goddu and Archille Varzi in America, I offer grateful thanks for permission to reprint from their publications.

But the story of this book actually begins long before 1993.

Nearly four decades in the past, in 1979, when time travel was still mostly just a nutty idea used by science fiction writers and a few rogue philosophers—proposing to give a serious seminar on time travel at the weekly college *physics* seminar would almost certainly have resulted in getting the bum's rush out the nearest door, or maybe even tossed through the closest window (or, God forbid, *off the roof*!)—I wrote my first time travel tale for *Analog Science Fiction* magazine. Bought by then editor Ben Bova (you can read it in Appendix A), he also bought another time travel tale from me soon after he had become the fiction editor at the newly created *Omni Science Fiction* magazine (you can read it in Appendix B). (Years later, Ben's successor as *Omni*'s fiction editor, Ellen Datlow, bought a third time travel story from me—"The Invitation"—which you can read if you can locate the July 1985 issue.)

Those fictional experiences, and my discovery of Princeton philosopher David Lewis' seminal 1976 essay on the *logical* possibility of time travel, led me to plunge into a deeper study of the *physics* of time travel, to the point where as the 1980s ended (1988, to be precise) I thought a book should be my next writing project. Alas, nobody else shared that thought. I spent the next 3 years looking for a

publisher among numerous university presses; as I looked, the pile of rejection letters, like entropy, grew steadily larger.

The editor at one well-known university press, in fact, simply laughed at the idea of a scholarly time travel book when I called him on the telephone (e-mail was then still in its infancy) to ask, after a long period of no response to my written proposal, if he had gotten it. (Perhaps, I told myself, the mail truck carrying my precious document had fallen into a hyper-dimensional spacetime warp: how pathetically desperate is the anxious academic writer!) Later, I published a number of math/physics books with that same press (but now with new editors) and so there were no lasting hard feelings.

That laughing, unresponsive editor wasn't alone in his opinion, I have to admit, and it wasn't until 1991 when Maria Taylor, the publisher at the Press of the American Institute of Physics (AIP Press), decided to take a chance (a *big* chance) and publish the first edition of *Time Machines*. She made that decision in large part because of two extremely supportive reviews of my proposal from the academic physicists Edwin Taylor (MIT, and a former editor of *The American Journal of Physics*) and Gregory Benford (University of California, Irvine, as well as being an award-winning writer of science fiction who occasionally used the time travel theme). After the original *Time Machines* appeared, Ben Bova asked me to use it as a guide to writing a book on time travel for the new Writer's Digest series on science fiction that he was editing, aimed specifically at would-be story writers; that book came out in 1997 as *Time Travel*. Later, Trevor Lipscombe, then editor-in-chief at the Johns Hopkins University Press (and my former math editor at Princeton University Press), reprinted *Time Travel* (with a new Preface) in 2011.

After Springer acquired AIP Press (and all of its books) in 1995, and Maria Taylor herself went over to Springer, she and I collaborated again on bringing out the second edition of *Time Machines* in 1999. And now, 18 years later, here (with a title slightly altered for reasons I give in "Some First Words") is its successor.

To Sam, Ho Ying, Irene, Ben, Ellen, Maria, Edwin, Gregory, and Trevor, thank you for your support. But my greatest debt of all, one I can never even begin to repay, is to my wife of 55 years, Patricia Ann, a woman of infinite tolerance. Who else would put up with someone who plays first-person-shooter video games at midnight (the bigger and the louder the explosions, the better!) and writes books on time machines, all the while claiming not to be crazy?

University of New Hampshire, Exeter, NH, USA Paul J. Nahin

Introduction

> Over the last few years leading scientific journals have been publishing articles dealing with time travel and time machines. . . . Why? Have physicists decided to set up in competition with science fiction writers and Hollywood producers?
>
> —John Earman (see note 25 of *Some First Words*)

Writing about time travel is, today, a respectable business. It hasn't always been so. After all, time travel, *prima facie*, appears to violate a fundamental law of nature; every effect has a cause, with the cause occurring before the effect. Time travel to the past, however, seems to allow, indeed to *demand*, backwards causation, with an effect (the time traveler emerging into the past as he exits from his time machine) occurring *before* its cause (the time traveler pushing the start button on his machine's control panel years *later* to start his trip backward through time).

Thus, when H. G. Wells published his breakout masterpiece, *The Time Machine*, in 1895, even those readers who loved it as a *story* (and not all did) were still quick to dismiss it as a *romantic fantasy*. It was, in their view, certainly an emotionally powerful tale of pure imagination, but nothing more. Reviewers of the day used such words as "hocus-pocus" and "bizarre," and called the work a "fanciful and lively dream."[26] Any one of the novels by Wells' contemporary, Jules Verne (even such super-technology ones like the 1865 *From the Earth to the Moon*) would have been ranked *far* above Wells' novella in terms of 'it could actually happen.'

Wells himself always denied that his time machine was anything more than a literary device[27] to get his Time Traveller into the far future. Indeed, in 1934, in the preface to *Seven Famous Novels* (published by Knopf), a collection of his novel-length scientific romances (as science fiction had been known before the term *science fiction* came into use), including *The Time Machine*, Wells made his position perfectly clear: "These stories of mine collected here do not pretend to deal with possible things; they are exercises of the imagination . . . They are all fantasies; they do not aim to project a serious possibility; they aim indeed only at the same amount of conviction as one gets in a good gripping dream." Wells then went on to say in that same preface that all attempts before at writing fantastic stories depended on magic. But not in his works. "It occurred to me that instead of the usual interview with the devil or a magician, an ingenious use of scientific patter might with advantage be substituted." Wells' great contribution to time traveling story-telling was his introduction of a *machine*; science instead of magic, drugs, dreams, blows on the head, or suspended animation.[28] Not all modern science fiction writers have followed Wells' lead, however.

---

[26] These reviews are reprinted in P. Parrinder, *H. G. Wells: The Critical Heritage*, Routledge & Kegan 1972. A modern reviewer has applied such negative characteristics to the Time Traveller, himself, calling him "a kind of Trickster figure" and "a quack and magician." See Robert J. Begiebing, "The Mythic Hero in H. G. Wells's *The Time Machine*," in *Essays in Literature*, Fall 1984, pp. 201–210.

[27] Wells was not the first to use a machine to enable time adventures, as the Spanish writer Enrique Gaspar (1842–1902) used one in his 1887 story *The Time Ship: A Chrononautical Journey*. It's Wells' tale we remember, however.

A science fiction tale by Clifford Simak (1904–1988), for example, the 1978 novel *Mastodonia*, incorporates an alien creature marooned on Earth (because of a spaceship crash centuries earlier) who 'makes time tunnels.' One of the characters in the story, who is attempting to start a time-travel agency using these tunnels, explains why not having a time *machine* is causing her difficulties with prospective clients: "The whole trouble was that I couldn't tell them about some machine—a time-travel machine. If I could have told them we'd developed a machine, they'd have been more able to believe me. We place so much trust in machines; they are magic to us. If I could have outlined some ridiculous theory and spouted some equations at them, they would have been impressed." I think that's off the mark. We trust in machines not because they are magic, but for precisely the opposite reason. They are *not* magic, but rather are *rational*. And to dismiss mathematics is to say that some non-natural—some supernatural—influence is at work.

But is a time *machine* actually possible? Or is the idea of a time machine simply "Nonsense" and "A bilgeful of crap," as a character bluntly puts it in the 1972 novel *The Dancer from Atlantis* by Poul Anderson (1926–2001). Wells, himself, addressed this point in an autobiographical essay (published in the *Cornhill Magazine*) that he wrote in July 1945 (just 13 months before his death) in even blunter words. Writing under the name of "Wilfred B. Batterave," he penned a very funny summary of his life titled "A Complete Exposé of This Notorious Literary Humbug." There he described *The Time Machine* as "[A] tissue of absurdities in which people are supposed to rush to and fro along the 'Time Dimension.' By a few common tricks of the story-teller's trade, Wells gets rid of his Machine before it can be subjected to a proper examination. He cheats like any common spook raiser. Otherwise it is plain commonsense that a man might multiply himself indefinitely, pop a little way into the future and then come back. There would then be two of him. Repeat *da capo* and you have four, and so on, until the whole world would be full of the Time Travelling Individual's vain repetitions of himself. The plain-thinking mind apprehends this in spite of all the Wellsian mumbo-jumbo and is naturally as revolted as I am by the insult to its intelligence." Funny, yes, but still pretty harsh stuff.

---

[28] Examples of 'non-machine' time travel stories of the last four types are, respectively, H. G. Wells' "The New Accelerator" (1901), Charles Dickens' *A Christmas Carol* (1843), Mark Twain's *A Connecticut Yankee in King Arthur's Court* (1889), and Edward Bellamy's *Looking Backward, 2000–1887* (1888).

As one writer has argued,[29] Wells was, rather than presenting a scientific discovery, simply attempting to refute the nearly suffocating, unjustified (in his mind), smug optimism of the well-to-do of the Late Victorian Age. And so, on his journey to the year A.D. 802,701, the Time Traveller finds the awful decay of humanity in the cannibalistic subjugation of the Eloi by the Morlocks, the end result of class warfare between the working class (Morlocks) and the idle, parasitic upper class (Eloi).

The German social philosopher Karl Marx, if he hadn't already been dead for 12 years in 1895, would surely have nodded in vigorous agreement as he read *The Time Machine*, even as he would have regretted Wells' decision to have the victory of oppressed workers take so long. (What irony that he is buried in London's Highgate Cemetery, the Victorian Valhalla where he has spent the last century and more quite literally mingling with many of the capitalistic ancestors of the Eloi!) What Marx would have thought of *time travel* as a possibility is, however, far less certain.

How things changed in the years that followed *The Time Machine*. There was, at first, admittedly a 'slight' decline in literary merit as the newly developing pulp science fiction magazines picked-up and ran with the time travel genre. Many of the magazine time travel tales of the 1920s, 1930s, and 1940s were, frankly, simply awful. BUT—some were pretty good, too. And some were, in fact, *very* good. From the 1950s on, there have been ever more sophisticated time travel tales from ever more sophisticated writers.

In the academic communities of philosophers and physicists, too, big events occurred. I give the philosophers the edge, in fact, with the 1976 publication of a hugely important paper that opened with these dramatic words: "Time travel, I maintain, is possible. The paradoxes of time travel [to the past] are oddities, not impossibilities. They prove only this much, which few would have doubted: that a possible world where time travel took place would be a most strange world, different in fundamental ways from the world we think is ours."[30] That writer wasn't the first philosopher to write on time travel to the past, but none had expressed themselves in such powerful and unequivocal words in unmistakable support of the concept.

---

[29] R. M. Philmus, "*The Time Machine*; Or, the Fourth Dimension as Prophecy," *Publications of the Modern Language Association*, May 1969, pp. 530–535.

[30] David Lewis, "The Paradoxes of Time Travel," *American Philosophical Quarterly*, April 1976, pp. 145–152. Lewis (1941–2001) was a Princeton University philosophy professor.

Lewis' paper is also notable because it gives what seems to be a clear definition of just what it means to say one has 'traveled in time,' either to the past *or* to the future:

> What is time travel? Inevitably, it involves discrepancy between time and time. Any traveler departs and then arrives at his destination; the time elapsed from departure to arrival (positive, or perhaps zero) is the duration of the journey. But if he is a time traveler, the separation in time between departure and arrival does not equal the duration of the journey.

To understand this, we need to appreciate the distinction between the *personal time* of the time traveler and the *external time* of remote observers of the time traveler. A time traveler's personal time is measured, for example, either by the time kept by his wrist watch or, perhaps, by a burning candle. (This distinction had actually appeared earlier in Horwich's paper—see note 27 in *Some First Words*—published the year before Lewis' paper.)

I say I 'give the edge to the philosophers' because, while the first *physics* time travel paper had appeared decades earlier, its author wasn't really a physicist at all but rather was Einstein's friend, the world-famous mathematical logician Kurt Gödel. Gödel's paper was, in retrospect, a pivotal event in establishing the 'respectability' of *scientific* time travel; it's worthwhile to take some time here to explain this important point. For physicists (and for philosophers and science fiction writers, too) a 'time machine,' one either constructed by intelligent beings or occurring naturally, manipulates (all the while obeying the known laws of physics) finite amounts of matter and energy in a finite region of spacetime.[31] A 'time machine' would be declared to be *plausible* if it could be explained by a rational, scientific theory. Such a rational theory is found in Einstein's general theory of relativity. (His *special* theory of relativity applies in those situations where there is no gravity.)

Until Einstein, the theory of gravity used by scientists was Newton's—a theory that, although amazingly accurate for any situation encountered on Earth, does have observable errors in certain astronomical applications. In addition, Newton's theory is a descriptive one; it makes possible the calculation of gravity effects without offering any explanation for gravity itself. Einstein's theory not only gives the right answers, even in those cases where Newton's theory doesn't, but it also explains gravity. It does that by treating the world as a four-dimensional structure in which all four dimensions (three of space and one of time) are in a certain sense on equal footing. The resulting Einsteinian description of the world is that of a unified spacetime in which time and space are intimately intertwined, whereas Newton's theory keeps time and space separate and distinct.

---

[31] I am going to feel free to use words like *spacetime* without having to first write introductory essays on relativity theory and tensor mathematics, because such words have entered common use. All those Hollywood science fiction movies, even the crummy ones that routinely trash the laws of physics, have at least expanded the general imagination!

As Newton wrote of time, at the start of his 1687 masterpiece *Principia*, a work that revolutionized physics, “Absolute, true, and mathematical time, of itself, and from its own nature, flows equably without relation to anything external, and by another name is called duration.” This view of time would be, of course, discarded with the arrival of Einstein and his view of variable time depending on the state of the observer.

Unlike Einstein’s view, Newton’s view of the nature of time was entangled with theology. As one modern theologian has written, “Newton conceived of absolute time as grounded in God’s necessary existence.”[32] To quote Newton himself, in the *General Scholium* to the second edition of *Principia* (1713) he added words that didn’t appear in the original: “God is a living, intelligent, and powerful Being; and, from his other perfections, [it follows] that he is supreme, or most perfect. He is eternal and infinite, omnipotent and omniscient; that is, his duration reaches from eternity to eternity; his presence from infinity to infinity; he governs all things, and knows all things that are or can be done. He is not eternity and infinity, but eternal and infinite; he is not duration or space, but he endures and is present. He endures forever, and is everywhere present; and, by existing always and everywhere, he constitutes duration and space. Since every particle of space is *always*, and every indivisible moment of duration is *everywhere*, certainly the Maker and Lord of all things cannot be *never* and *nowhere*.”

Okay, I’ll be honest—I really am not at all sure just what that means! Newton added these words to the *Principia* in response to criticism (from the influential philosopher George Berkeley (1685–1753)) that his original statements about absolute time were “pernicious and absurd notions,” notions that were in fact atheistic in conception. That was a most serious charge in Newton’s day, and he was trying (I think) to find some cover from those critics who spent more hours of the day thinking about God than of physics. Much more honest (in my opinion) are the witticisms ‘time is just one damn thing after another’ and ‘time is what keeps everything from all happening at once.’[33] More funny than useful, yes, of course, but at least they’re funny.

Newton’s theological view of time is simply irrelevant to the modern physicist (although perhaps of more interest to the philosopher-historian) but in many cases it is of *central interest* to the science fiction writer. For example, Newton’s religious mindset and its (perhaps!) connection with time travel is treated in my short story "Newton's Gift," originally published in *Omni Magazine* (January 1979) and reprinted in Appendix B at the end of this book. Wells' Time Traveller's view of time is more Newtonian than it is Einsteinian—and perhaps that's not such a big surprise, considering that Einstein was only 16 years old when *The Time Machine* was published.

---

[32] William Lane Craig, “God and the Beginning of Time,” *International Philosophical Quarterly*, March 2001, pp. 17–31, which discusses the question ‘Why didn’t God create the world sooner?’ One irreverent answer is ‘He was busy creating Hell for all those who ask that question,’ but a more scholarly analysis can be found in Brian Leftow, “Why Didn’t God Create the World Sooner?” *Religious Studies*, June 1991, pp. 157–172.

[33] This last ‘definition’ first (as far as I know) appeared in the work of the science fiction writer Ray Cummings (1887–1957), in his 1921 story “The Time Story,” published in *Argosy-All-Story* magazine. He repeated the phrase in his 1929 novel *The Man Who Mastered Time*, and then again in the 1946 novel *The Shadow Girl*. (“This same Space; the spread of this lawn … what would it be in another 100 years? Or a 1000? This little space, from the Beginning to the End so crowded with events and only Time to hold them apart!”)

From the first (1905) it has been known that Einstein's special theory allows time travel into the future via the well-known mechanism of *time dilation*. (The faster a rocket ship travels relative to Earth, the slower is the tick-tock of a wrist watch worn by a rocketeer, compared to that of an identical watch back on Earth.)[34] To return from the future, however, to travel back into the past to the instant after the traveler began his journey, had been thought to be impossible. It was Gödel's discovery that showed the general theory, which has passed every experimental test it has been subjected to (most recently, the September 2015 detection, from two massive colliding black holes, of gravitational waves—'ripples in spacetime'—generated more than a billion years ago in an effect predicted by the general theory a century ago), does allow time travel to the past *under certain conditions*. It is this availability of a *theory* that distinguishes time travel speculations from the outlandish fantasy speculations with which it is often unjustly lumped—speculations that *are* in the province of quacks (such as ESP, astrology, and mind over matter a' la spoon bending).

In his general theory, Einstein showed how spacetime can be either 'flat' (in the no-gravity, special relativity case of what is called a *Minkowski spacetime*[35]) or 'curved' (those situations with gravity), and he did that not by verbal hand waving, but rather by writing mathematical equations that obey all the known laws of physics: his famous gravitational field, nonlinear differential tensor equations. These complicated equations are notoriously difficult to solve in general, but in certain, special cases they *have* been solved. Those solutions describe how matter and energy and spacetime interact. As the popular saying puts it, "Curved spacetime tells matter how to move, and energy and matter tell spacetime how to curve." In that sense, gravity *is* curved spacetime.

In 1949 Gödel found one such special solution to the field equations that describes the movement of mass-energy not only through space but also *backward in time* along trajectories in spacetime that are called *closed time-like lines* or *curves*

---

[34] One pulp magazine science fiction story (F. J. Bridge, "Via the Time Accelerator," *Amazing Stories*, January 1931) got this right when its time traveler explains how his time machine works with these words: "Time as we know it is not universally absolute. The rate of its passage depends to a great extent upon the velocity of its observer with regard to some certain reference system. A moving clock will run slower with respect to a selected coordinate system than a stationary one." (Recall my earlier comments on the personal time of a time traveler.)

[35] Named after Hermann Minkowski (1864–1909), Einstein's mathematics professor in Zurich who gave the now well-known spacetime diagram interpretation of special relativity which, when originally presented by Einstein, was in the form of pure mathematics.

(called CTLs or CTCs, respectively).[36] These trajectories are such that if a human traveled along one, *always at a speed less than that of light* (that's what *time-like* means), he would see everything around him happening in normal causal order from moment to moment (for example, the second hand on his wrist watch would tick clockwise into the local future), but eventually the CTL/CTC closes back on itself and the traveler finds himself in his own past.

On the scale of the Solar System, general relativity has causality built into itself, but on much larger scales things can be a good deal more complicated. On a very large, astronomical scale, in fact, curved spacetime can result in violations of causality, with effects occurring before their causes. That is what the physics and the mathematics of Gödel's solution imply. That is what is meant by saying there is a scientific, rational basis for discussing time travel to the past. It is particularly important to note that travel along one of the closed time-like world lines discovered by Gödel requires a *machine*, some kind of accelerating rocket ship. That's because none of Gödel's CTLs/CTCs are what is called a *geodesic*. That is, none are *free-fall* world lines.[37] This machine does not, however, generate CTLs/CTCs where none existed before (CTL/CTC *creation* requires what physicists call a *strong* time machine) but rather simply makes use of the CTLs/CTCs that are inherent in Gödel's spacetime. A Gödelian rocket ship then is an example of a *weak* time machine.

I mentioned earlier that "certain, special cases" of Einstein's gravitational field equations result in CTLs/CTCs. What was the "special case" that Gödel solved? His solution of the field equations is for a rotating, infinite, static universe composed of a perfect fluid at constant pressure. In such a universe Gödel found that naturally occurring CTLs/CTCs pass through every point in spacetime; that is, time travel in Gödel's universe is *not* the result of a machine *manipulating* mass and energy on a *local* scale (the classic science fictional description of a time machine); rather, in Gödel's spacetime time travel is a naturally occurring phenomenon! The observable universe is, however, *non*-rotating and expanding (astronomers see red-shifts in the spectrums of distant stars) and so, although Gödel's spacetime satisfies the general relativity field equations, its time travel property does not hold in the spacetime in which we live. (This may account for why the initial reaction in the physics/philosophical communities, to Gödel's discovery that time travel is *not* nonsense according to general relativity, was mostly indifference.) The failure to observe time travel in our universe may (somewhat surprisingly, I think) still have possible implications for us, however, as one philosopher has cleverly argued.[38] He points out that naturally occurring Gödelian time travel would endow the universe with properties particularly useful for the survival of intelligence (presumably that includes humans) against extinction from a multitude of cosmic disasters. So, for those who argue that the universe we live in was *made* for us (the advocates of various proofs of God's existence that have Him as Designer), we have an obvious question: why did He (apparently) skip incorporating time travel?

---

[36] Kurt Gödel, "An Example of a New Type of Cosmological Solutions of Einstein's Field Equations of Gravitation," *Reviews of Modern Physics*, July 1949, pp. 447–450. A CTL/CTC is a special type of *world line*; the trajectory through spacetime of every particle in the universe is a world line that extends from each particle's past to its future. Our everyday experiences are with world lines that never cross or come close to themselves (which would put a particle at or near the same spacetime point more than once). That lack of experience with CTLs/CTCs that self-intersect is what makes time travel to the past so difficult for humans to grasp. For a discussion of *how* Gödel did what he did, see Wolfgang Rindler, "Gödel, Einstein, Mach, Gamow, and Lanczos: Gödel's Remarkable Excursion into Cosmology," *American Journal of Physics*, June 2009, pp. 498–510.

[37] It was discovered in 1969, however, that this isn't strictly true *if* one allows for a test particle (our 'time traveler') to be electrically charged. Then, naturally present electromagnetic forces acting on the particle could be sufficient to propel the particle along a Gödelian CTL/CTC. That is, no rocket would be required. See U. K. De, "Paths in Universes Having Closed Time-Like Lines," *Journal of Physics A*, July 1969, pp. 427–432. There are other solutions to Einstein's equations that do allow time travel on free-fall geodesics: see, for example, I. D. Soares, "Inhomogeneous Rotating Universes with Closed Timelike Geodesics of Matter," *Journal of Mathematical Physics*, March 1980, pp. 521–525.

In an invited essay that appeared the same year as his time travel physics paper, Gödel specifically addressed the seemingly paradoxical aspect of what he had discovered: "By making a round trip on a rocket ship in a sufficiently wide course, it is possible in these [rotating] worlds to travel into any region of the past, present, and future, and back again, exactly as it is possible in other worlds to travel to distant parts of space. This state of affairs *seems* [my emphasis] to imply an absurdity. For it enables one, e.g., to travel into the near past of those places where he has himself lived. There he would find a person who would be himself at some earlier period of life.[39] Now he could do something to this person which, by his memory, he knows has not happened to him."

Gödel's nerve then failed him, and he defended the possibility of the paradox of a time traveler meeting himself in the past with what I think an astonishingly unconvincing argument (particularly so for a logician) based primarily on *engineering* limitations: "This and similar contradictions, however, in order to prove the impossibility of the worlds under consideration, presupposes the actual feasibility of the journey into one's own past. But the velocities which would be necessary in order to complete the voyage in a reasonable time are far beyond everything that can be expected ever to become a practical possibility. Therefore it cannot be excluded a priori, on the ground of the argument given, that the space-time structure of the real world is of the type described."[40] That is, Gödel was trying to head off critics of his rotating universe model who might point to the time travel result as proof that the model had to be flawed.

---

[38] Alasdair M. Richmond, "Gödelian Time-Travel and Anthropic Cosmology," *Ratio*, June 2004, pp. 176–190. Not all physicists think Gödel's result is actually time travel. At least two think it is all simply the result of mathematical hijinks, and that time machines must remain "an aspect of science fiction fantasy": see F. I. Cooperstock and S. Tieu, "Closed Timelike Curves and Time Travel: Dispelling the Myth," *Foundations of Physics*, September 2005, pp. 1497–1509. This skepticism towards Gödel actually started much earlier, when two physicists (one a Nobel physics laureate) incorrectly claimed Gödel had simply gotten his math wrong: see S. Chandrasekhar and J. P. Wright, "The Geodesics in Gödel's Universe," *Proceedings of the National Academy of Sciences*, March 1961, pp. 341–347. It was those two physicists who had erred, however, as was pointed out by the philosopher Howard Stein, in his "On the Paradoxical Time Structures of Gödel," *Philosophy of Science*, December 1970, pp. 589–601.

[39] You'll recall that this is *precisely* the situation that Wells mentions in his "Notorious Literary Humbug" essay. If only he had lived just three more years, to see what he thought to be an absurdity actually appear in the serious writings of a brilliant mathematician!

In a footnote Gödel says that the time traveler would have to move at least as fast as nearly 71 % of the speed of light, and that if his rocket ship could "transform matter completely into energy" then the weight of the fuel would be greater than that of the rocket by a factor of 10^{22} divided by the square of the duration of the trip (in rocket years). A trip to the past in Gödel's universe would require a time machine that looked like Dr. Who's telephone booth attached to a fuel tank the size of several hundred *trillion* ocean liners. These are formidable numbers,[41] but they require no violation of physical laws, and that's what really counts if time travel is to be disproved. Gödel's use of engineering limitations for explaining away backwards time travel is actually worse than simply being wrong, because the puzzle is not in practicality but rather in showing, assuming that general relativity is correct, how correct mathematical physics can lead to what seems to be a paradoxical conclusion. (And see note 12 again, for another reason the 'fuel argument' really has no force at all against the possibility of time travel in Gödelian spacetime.)

So, what did the great man himself, Einstein, think of all this? In the same publication as Gödel's essay, he *cautiously* replied as follows: "Kurt Gödel's essay constitutes, in my opinion, an important contribution to the general theory of relativity, especially to the analysis of the concept of time. The problem here involved disturbed me already at the time of the building up of the general theory of relativity, without my having succeeded in clarifying it ... the distinction 'earlier-later' is abandoned for world-points which lie far apart in a cosmological sense, and those paradoxes, regarding the *direction* of the causal connection arise, of which Mr. Gödel has spoken ... It will be interesting to weigh whether these are not to be excluded on physical grounds."

Despite the mathematical physics of Gödel, showing the possibility of time travel to the past, many philosophers are not quite so sure. As one expressed his concerns, "No science-fiction staple poses more philosophical difficulties than time travel, but there is still no consensus as to whether time-travel fictions exhibit logical, metaphysical, or physical impossibility."[42] The best-known and possibly oldest of the paradoxical situations that seem to be part-and-parcel of time travel is the so-called *grandfather paradox*,[43] expressed this way by philosopher David Lewis in his pioneering 1976 paper (see note 5):

---

[40] Kurt Gödel, "A Remark About the Relationship Between Relativity Theory and Idealistic Philosophy," in *Albert Einstein: Philosopher-Scientist*: volume 7 of *The Library of Living Philosophers* (P. A. Schilpp, editor), Open Court 1949.

[41] For the analysis of a rocket powered by matter/anti-matter, a known physical process that satisfies Gödel's energy requirement for time travel, see E. Purcell, "Radioastronomy and Communication Through Space," in *Interstellar Communication* (A. G. W. Cameron, editor), W. A. Benjamin 1963.

[42] Alasdair Richmond, "Time-Travel Fictions and Philosophy," *American Philosophical Quarterly*, October 2001, pp. 305–318.

> Consider Tim. He detests his grandfather, whose success in the munitions trade built the family fortune that paid for Tim's time machine. Tim would like nothing so much as to kill Grandfather, but alas he is too late. Grandfather died in his bed in 1957, while Tim was a young boy. But when Tim has built his time machine and traveled to 1920, suddenly he realizes that he is not too late after all. He buys a rifle, . . . and there [Tim] lurks, one winter day in 1921, rifle loaded, hate in his heart, as Grandfather walks closer, closer . . .

So, there's the puzzle. Tim can obviously achieve his goal—he has a loaded gun, he's an excellent shot, a clueless granddad is coming ever closer—but if Tim actually does kill grandfather, years *before* Tim was (will be) born, then how can Tim *be* born? And if he is not born, then how can Tim ('now' not in existence) travel back through time to kill grandfather? What a confusing mess, right? So, the only possible conclusion to all this is that the starting premise, that time travel makes sense, must actually be nonsense. Right?

Well, maybe, but then what of Gödel with his time traveling rocket ship? That's hard-as-diamond, unshakeable mathematical physics, for heaven's sake. We can't just ignore *that*! Lewis offers a way out of this conundrum, and when we get to the book's discussions on paradoxes (that's plural because, believe it or not, there are other paradoxes even *more* perplexing than that of killing granddad in the distant past) we'll return to his solution.

Ever since Lewis wrote his paper, philosophers have been particularly fascinated by the grandfather paradox and have shown themselves to be at least as inventive as the science fiction writers in discussing it, or variations on it.[44] Here, for example, is a twist on that paradox that I think particularly clever, one that avoids the murderous spirit of the tale told by Lewis and Horwich:

---

[43] The origin of this paradox is probably lost in time (the irony of that is *so* appropriate!), but I have traced it at least as far back as to the science fiction pulp magazine *Science Wonder Stories* which published, in its December 1929 issue, an editorial essay titled "The Question of Time Traveling." It challenged readers to think about the following scenario: "Suppose I can travel back into time, let me say 200 years; and I visit the homestead of my great great great grandfather, and am able to take part in the life of his time. I am thus enabled to shoot him, while he is still a young man and as yet unmarried. From this it will be noted that I could have prevented my own birth . . .."

[44] Even before Lewis' paper, Paul Horwich had reduced the grandfather paradox to *autoinfanticide*—a time traveler tries to kill his younger *self*—in "On Some Alleged Paradoxes of Time Travel," *The Journal of Philosophy*, August 14, 1975, pp. 432–444. But not all philosophers share this fascination. Earman (see the opening quote), for example, dismisses *all* of the science fiction paradoxes that are so beloved by fans of the genre as "while always good for a chuckle," they are just "crude and unilluminating means of approaching some delicate and deep issues about the nature of physical possibility." I think Earman is fundamentally correct, although I wouldn't go so far as to characterize the paradoxes as mere "chuckles." They are, after all, the source of much of the intellectual motivation prompting the exploration of the physics of time travel. An excellent example of this is found in the paper by the Russian physicist S. V. Krasnikov, "Time Travel Paradox," *Physical Review D*, February 14, 2002, pp. 064013-1 to 064013-8. The physics of the grandfather paradox is of *great* interest in this paper.

> Sarah has just completed building her time machine. She decides to test the machine on herself tomorrow morning at which time she intends to travel back one day. In the meantime, she goes home, puts some salve on the burn she received that day, and goes to bed. In the morning, Sarah, with coffee in hand, sits down to read the morning paper. She opens the paper to the following headline: 'Famous physicist found dead.' On the front page is a picture of her body, salve burn clearly visible on her arm, inside her pristine time machine. Underneath is the caption. 'Nobel-prize winning physicist found dead yesterday in mysterious device that materialized near city hall.' Extremely shaken, Sarah returns to the lab and destroys the time machine.[45]

Can any sense be made of this? We'll come back to this question later in Chap. 5, when we discuss the possibility (or not) of time being *multi*-dimensional.

Now, to conclude this Introduction, let me end with two amusing, connected short stories (in epistle form) that nicely describe the issues we'll take up in the rest of this book. The rejection letter for the denial of a research grant to fund the construction of a time machine has just been received . . .

That Useless Time Machine[46]

Dear Review Committee:
It is not our practice to raise complaints against a negative review report. We believe in peer refereeing and we respect it, whatever its content and consequences. However, in the case of our latest grant application (project named 'The Time Machine') we find it necessary to express our astonishment at the motivations with which our request for funding was turned down. Your main objection appears to be that our project is 'philosophically interesting' but 'practically useless', by which you mean that the project 'has no potential for applications.' We do not quite think that the main criterion for judging the scientific value of a project should be its practical usefulness, but never mind that. Let us agree that usefulness is a relevant criterion, especially when large amounts of money are involved. Why should that be a reason to turn down our project? Quite frankly, we cannot think of a project with better application potential than ours. Some examples:

- Cultural tourism: one could send herds of history fans back in time to witness the crucial episodes of the French Revolution, or to watch the Egyptians build the pyramids, or to videotape Socrates' lectures.
- Exotic safaris: we have already received several applications for dinosaur hunting expeditions (they got extinct anyway).

---

[45] G. C. Goddu, "Time Travel and Changing the Past: (Or How to Kill Yourself and Live to Tell the Tale)," *Ratio*, March 2003, pp. 16–32.

[46] Story by Roberto Casati (Senior researcher at CNRS, Paris) and Achille C. Varzi (Professor of Philosophy at Columbia University). Originally published in *Philosophy*, October 2001, pp. 581–583, and reproduced here by kind permission of the authors.

- Error detection: we could take a closer look at our past mistakes and learn how to avoid them in the future.
- Historic documentaries: think of the huge saving in set design, costumes, special effects, etc. (How much did *Gladiator* cost?)

And so on and so forth. Honestly, can you think of a project with better prospects for useful and thrilling applications?

Sincerely Yours,
The 'Time Machine' Research Group

Dear 'Time Machine' Research Group:
Thank you for your letter. We agree that it would be interesting to exploit a time machine for the uses that you suggest. It would also be remarkable if we could use it to prevent all sorts of unpleasant events that happened in the past. It would be remarkable, for instance, to be able to go back to November 22, 1963, and prevent Lee Harvey Oswald from killing John Kennedy, or to go back to April 14, 1912, and steer the Titanic around the iceberg. It would be excellent indeed to be able to do such things. However, suppose your project were to be successful. Suppose you *will* manage to build a time machine. Then why *didn't* you do any of those things? Why is it that our past history is still full of such sad events? Either this means that your project is doomed to fail and you will never manage to build a time machine; *or* it means that the project will succeed but that you are not going to use your time machine for these good purposes. In the first case, logic shows it would be pointless to support your project. In the second case, ethics dictates that it would be wrongdoing. Either way, you must concede that the reasons against your project are overwhelming.

Cordially Yours,
The Review Committee

Dear Review Committee:
Certainly you have noticed that our suggestions for practical applications of the time machine did not include any uses that could result in an alteration of the natural course of history. As a matter of fact, we believe that no such alteration is logically possible. According to our project, it is logically possible to *visit* the past but not to *modify* the past. No time traveler can undo what has been done or do what has not been done. So the logic is safe. This does not mean that the time traveler will be ineffectual during her stay in the past, of course; it simply means that what she is going to do is something that she has already done. An accurate catalogue of all the past events would include an account of the arrival of the Time Machine from out of nothing as well as an account of all the actions and reactions that followed. And ethics is safe, too. For, if indeed we managed to go back to Dallas, we could not stop Oswald from doing what he did. Nobody would be able to stop Oswald because nobody was able to stop him (and nobody was able to stop Oswald because nobody will ever be able to do so, even if they came from the future). Alas, the past is full of sad events but there is nothing that we can do about that.

Respectfully Yours,
The ‘Time Machine’ Research Group

Dear ‘Time Machine’ Research Group:
We appreciate the distinction between changing the past (impossible) and affecting the past (possible). However, this simply reinforces our initial impression: your project has no practical value. If in order to travel to the past one has to have been there already, and if one can only do what has already been done, then *á quoi bon l’effort*? Why should we invest in a ‘Time Machine’ at all? We are afraid that our decision is now final.

Yours with best wishes,
The Committee

Well, all seems to be certainly lost with *that*. But, wait, perhaps not. Maybe, with just one more *really good* appeal, The Committee’s rejection can be reversed! If *you* were on the Review Committee, and had just read the following letter, how would *you* vote?

A Useful Time Machine[47]

Dear Review Committee:
We regret your continued decision to reject our proposal. Even though you have told us your decision is now final, we humbly ask your indulgence for one last appeal. We believe you have misinterpreted a crucial part of our proposal.

You maintain that our ‘Time Machine’ project ‘has no potential for applications’ and has ‘no practical value.’ You ultimately base this claim on the fact that “If in order to travel to the past one has to have been there already, and if one can only do what has already been done, then *á quoi bon l’effort*? Why should we invest in a ‘Time Machine’ at all?” Your argument however is a misinterpretation of our own comments that ‘According to our project it is logically possible to visit the past but not to modify the past … This does not mean that the time traveler will be ineffectual during her stay in the past, of course; it simply means that what she is going to do is something that she has already done.’ We regret the awkward and easily misleading locution of the last sentence, but such are the perils of talking about time travel. Regardless, please consider our clarification.

Certainly if we were proposing that the time traveler *be* 5 years old again, we would be proposing something not worth the effort—our proposed time traveler has already turned five and cannot do so again. But we are not proposing that the time traveler do things that have already occurred in her own personal past, but rather in her personal future. The time traveler has not yet, from her personal temporal perspective, travelled back to, say, the library at Alexandria in 100 BCE. When she does travel back to 100 BCE to obtain scans of the books in the library before its destruction, she will be older than she is now. When she returns she will be still older (and we hope wiser, i.e., in possession of valuable information to which neither you nor we currently have access).

---

[47] Story by Geoff Goddu (Professor of Philosophy at the University of Richmond, Virginia). Originally published in *Philosophy*, April 2002, pp. 281–282, and reproduced here by kind permission of the author.

But is it true that as of 2002 AD [the year this letter was written] the time traveler has already visited Alexandria in 100 BCE? It could well be. But whether or not it is depends upon whether it is *also* true that our project will be successfully funded and completed. Because time travel into the past involves reverse causation, certain past events, such as the time traveler visiting 100 BCE, will be dependent upon certain future events, such as the successful funding and completion of our project. Hence, if it is not true that our project is both funded and completed, then it is not true that our time traveler has of 2002 already visited 100 BCE.

But suppose we were to learn now, before the funding and completion took place, that our time traveler had indeed been present at the library in Alexandria in 100 BCE. Would this imply that there was no reason to expend the effort to fund our project? After all, if the travel has 'already' happened, why bother funding the project? Firstly, such an argument does not imply that a 'Time Machine' would have no practical application, but rather expresses the futile hope that one could in fact get the practical benefits (if time travel is successful, we obtain the desired information) without expending the effort at all. Secondly, the hope is futile, for if we learn right now that our time traveler had been present at the library in 100 BCE, we would then know, assuming no other possible funding source, that you *will* expend the effort to fund our project. To deny this last is to make the impossible suggestion that even though your support is truly a causal antecedent of the successful trip, there is now no need for you to actually expend the effort to provide funding.

Hence, the effort is far from pointless, for the project will only succeed through your and our efforts. And success will generate, not only all the practical applications we outlined in our first letter, but, in addition, a host of information gathering applications such as more accurate historical research, lost item location identification, legal testimony verification, etc. Even if, as we (and you) acknowledged, no one could now prevent Oswald from killing Kennedy, wouldn't it be worth verifying that Oswald was the lone killer of Kennedy? Also, the information gathering need not be restricted to the past. For example, information concerning the prices of various stocks 10 years from now would be extremely valuable to a suitably cautious and prudent investor. Surely you cannot object to our information gathering in the future on the grounds that 'it will already have been done.' And just think, the information we obtain could be what allows you to obtain at very low prices those stocks that in the future will be extremely valuable and allows your esteemed committee to dramatically increase your support of worthy scientific endeavors.

Again, we ask you to reconsider your original decision.
Respectfully yours,
The 'Time Machine' Research Group



A time machine inventor makes an experimental test of the grandfather paradox! (Illustration from “Thompson’s Time Traveling Theory” by Mortimer Weisinger), *Amazing Stories* March 1944 (art by Malcolm Smith). Reprinted by arrangement with Forrest J. Ackerman, Holding Agent, 2495 Glendower Ave., Hollywood, CA 90027.

Not everybody likes time machines as a science fiction gadget, not even otherwise enthusiastic devotees of the genre. For example, in a Letter-to-the-Editor published in the December 1931 issue of Astounding Stories*, one seventeen-year-old fan had this to say: “There is only one kind of Science Fiction story I dislike, and that is the so-called time-traveling. It doesn’t seem logical to me. For example, supposing a man had a grudge against his grandfather, who is now dead. He could hop in his machine and go back to the year that his grandfather was a young man and murder him. And if he did this how could the revenger be born? I think the whole thing is the ‘bunk.’” As this book will demonstrate, this young reader was not alone in that opinion. As this book will also demonstrate, in the last few decades that view has been rapidly evolving.*

For Further Discussion

Read again the penultimate sentence in the last letter from The 'Time Machine' Research Group, and then think about how you would respond to the following questions.

(1) Would *you* invest in a stock market if you knew somebody else had a time machine giving *them* advance information on stock performance?
(2) How might the existence of a time machine influence the future of the stock market, in general? For an early science fiction look at these questions, see Lee Laurence, "History in Reverse," *Amazing Stories*, October 1939.

One writer has speculated that Wells' model for the Time Traveller was the American inventor Thomas Edison. (See Martin T. Willis, "Edison as Time Traveler: H. G. Wells' Inspiration for His First Scientific Character," *Science Fiction Studies*, July 1999, pp. 284–294.) As Wells worked his way from *The Chronic Argonauts*, through revisions, to the final *Time Machine*, the story's hero evolved from Dr. Nebogipfel to the Philosophical Inventor to the Time Traveller. The one individual who could have inspired all of these various hero types was, according to Willis, Edison, a world-famous Victorian-age celebrity whose story was well known to Wells. If Wells had today's scientific personalities available as potential inspirations, who do you think he would use? How might that choice affect the story and structure of *The New Time Machine*?

The idea of *personal time*, used by the philosopher David Lewis (note 5) to consistently interpret time travel stories, has been used in a quite different way (although time travel gets a few words, too) by the philosopher Roy Sorenson. In his paper "The Cheated God: Death and Personal Time," *Analysis*, April 2005, pp. 119–125, Sorenson asks you to imagine an immortal god. For some reason this god runs afoul of a demon, who curses the god in a curious way. (The 'telling of a story' is a common technique in philosophical papers and, while foreign to what readers of physics papers are used to seeing, is not without some charm. Just be sure to always keep in mind that its

(continued)

primary use is as an *attention-grabbing* device, but as far as having any other merit, well, that's often another story.) The curse is such that the life span of the once immortal god is reduced to that of a normal human life span and yet, perhaps surprisingly, the god will still never die. As Sorenson writes, "[The god] will live forever. But [the god] will not have a better life than a mortal. The demon has harmed [the god] as gravely as death harms mortals." How, you might wonder, is this to be done? As Sorenson explains, "[The god] lives half of its now mortal span, followed by a trillion years of nothingness, then a quarter of its mortal span followed by a trillion years of nothingness, then an eighth of its mortal span followed by a trillion years of nothingness and so on ad infinitum." Sorenson's argument is simply an exotic form of the high school summation of the geometric series $\frac{1}{2}+\frac{1}{4}+\frac{1}{8}+\cdots=1$, where there are an *infinite* number of terms to the left of the equality. (Each term represents a period of time during which the god is conscious, and each + represents a trillion years.) Sorenson picked a trillion years of nothingness between consecutive periods of consciousness for (I suggest) dramatic reasons, but suppose instead that he had picked 1 μs for the period of nothingness. Discuss what effect this would have (if any) on the life of the god. Consider two cases:

(a) There is no minimum time duration for consciousness, and
(b) There *is* a minimum time duration such that, for any shorter duration, a consciousness remains 'unaware' even though it is *not* in a state of nothingness.

After working all night making some final calculations, a physicist carefully solders a final resistor into the control module of the world's first time machine and then steps into the gadget that is a sure bet to win the next Nobel Prize in physics. As she does, she notices that it is precisely 8:10 in the morning, as indicated on both her wrist watch and the clock on the lab wall. After settling into a plush leather seat she pushes the time machine's power button, the machine glows with a flickering blue-red halo and hums with a mighty throb for a while and then, at precisely 8:15 by her wrist watch, she steps out of the machine and back into her lab. She notices the clock on the wall now reads 8:05. That is, she took 5 min of personal time (8:10 to 8:15) to travel 5 min of external time into the past (8:10 to 8:05). On the one hand she certainly seems to be a time traveler, in that she exits the machine before she enters it. (Ignore the issue of there being *two identical* physicists in the lab from 8:05 to 8:10!) On the other hand, the elapsed personal and external

(continued)

times are *equal*. Does this suggest a need to modify or expand David Lewis' definition of a time traveler? As you ponder this question, you might want to read the following four papers: (1) Paul R. Daniels, "Lewisian Time Travel in a Relativistic Setting," *Metaphysica*, October 2014, pp. 329–345, (2) Douglas Kutach, "Time Travel and Time Machines," in *A Companion to the Philosophy of Time* (H. Dyke and A. Bardon, editors), Wiley-Blackwell 2013, pp. 301–314, and (3) Frank Arntzenius, "Time Travel: Double Your Fun," *Philosophy Compass*, November 2006, pp. 599–616. A bit more demanding (but worth the effort) is the long chapter "Time Travel and Time Machines" by Chris Smeenk and Christian Wüthrich, in *The Oxford Handbook of Philosophy of Time* (C. Callender, editor), Oxford 2011, pp. 577–630 (see page 580, in particular).

> The idea that information is physical has given rise to a series of discoveries which indicate that physics has much to say about fundamentals of computer science.

The above quotation is the opening sentence to a most interesting paper by the physicist Dave Bacon, "Quantum Computational Complexity in the Presence of Closed Timelike Curves," *Physical Review A* (70), 2004. (When he wrote, Bacon was at Caltech, but he is now a software engineer at Google.) The title of Bacon's paper, translated into blunt English, is "It Would Be Really Neat If We Could Merge a Time Machine With a Computer." That is, to further quote from Bacon's paper, "One could [efficiently] solve a hard problem by trying out a solution to the problem, sending one's computer back in time, attempting a different solution to the problem, sending one's computer back in time, etc., until a solution to the problem has been found." There then follows a pretty sophisticated analysis on the self-consistent time evolution of a quantum system, ending with Bacon's frank admission that "we would not be honest if we did not end this paper with the caveat that this work is at best a creature of eager speculation . . . Practical considerations are humorous at best." Read Bacon's paper and discuss what he means by "a hard problem." (There *is* a technical term used by computer scientist for such problems: NP-complete.)

The occasional theological commentary in this book may strike some as a bit odd for a topic treated with heavy doses of deep mathematics in the physics literature but, as you'll see on the following pages, theology is an unescapable dimension to any informed discussion of time travel. A literary connection

(continued)

between time travel and theology has, in fact, existed for a long time. As pointed out in Paul Alkon's *Origins of Futuristic Fiction* (University of Georgia Press 2010), "The first time-traveler in English literature is a guardian angel who returns with state documents from 1998 to the year 1728 in Samuel Madden's *Memoirs of the Twentieth Century*" (published in 1733, nearly three centuries ago). Madden was an Irish-Anglican clergyman whose book was satire rather than science fiction, but its time traveling aspect was a first. As Professor Alkon also writes, "Madden [was] the first to write a narrative that purports to be a document from the future. He deserves recognition as the first to toy with the rich idea of time-travel in the form of an artifact sent backward from the future to be discovered in the present." Your assignment: read and discuss Alkon's book.

You'll recall that Gödel cast his view of time travel in the form of a self-encounter in the past. In Frederik Pohl's "Let the Ants Try," we find a science fiction tale that appeared essentially simultaneously with Gödel's paper (*Planet Stories*, Winter 1949), in which a time traveler journeys back forty million years. Upon stepping out of his time machine, he hears a "raucous animal cry" from somewhere in the nearby jungle. Later, after other adventures in time, he returns to near the same point in spacetime. After stepping out of his time machine, he sees himself in the distance—the earlier version of himself during the first trip. Then, suddenly, the time traveler meets a violent death: "As his panicky lungs filled with air for the last time, he knew what animal had screamed in the depth of the Coal Measure forest." In fact, self-encounters had appeared in science fiction *years* before Gödel's paper. In the 1942 story "Minus Sign" (*Astounding Science Fiction*, November) by Jack Williamson, for example, a spaceship battles with itself while traveling backward in time. How do you think a scientist like Gödel would have liked these two stories? (Who knows, maybe he *did* read them!) If you could travel back in time to 1949 to ask him if such tales had been an inspiration, do you think he would be intrigued, amused, or instead would he be insulted?

Contents

1 A Broad Look at Time Travel 1
1.1 Time Travel in the Fantasy and Science Fiction Literature 1
1.2 Where Are All the Time Travelers? 10
1.3 Skepticism About Tales of Time Travel 15
1.4 Troubles with (some) Time Machines 22
1.5 Quantum Gravity, Singularities, Black Holes, and Time Travel 29
1.6 Tipler's Time Machine 38
1.7 For Further Discussion 42

2 Philosophical Space and Time 51
2.1 Time: What Is It, and Is It Real? 51
2.2 Linear Time and the Infinity of Past and Future 61
2.3 Cause and Effect 67
2.4 Backward Causation 72
2.5 The Fourth Dimension 78
2.6 Spacetime and the Block Universe 90
2.7 Philosophical Implications of the Block Universe 100
2.8 For Further Discussion 109

3 The Physics of Time Travel: Part I 115
3.1 The Direction of Time 115
3.2 The Arrows of Time 124
3.3 Time Dilation 139
3.4 The Lorentz Transformation 146
3.5 Spacetime Diagrams, Light Cones, Metrics, and Invariant Intervals 155
3.6 Proper Time and the Twin Paradox in Time Travel to the Future 173
3.7 For Further Discussion 181

4 Philosophers, Physicists, and the Time Travel Paradoxes 187
4.1 Paradoxes and Their First Appearance in Science Fiction 187
4.2 Changing the Past and the Grandfather Paradox 195
4.3 Changing Versus Affecting the Past 206
4.4 Causal Loop and Bootstrap Paradoxes 214
4.5 Sexual Paradoxes 225
4.6 Splitting Universes and Time Travel 229
4.7 For Further Discussion 237

5 Communication with the Past 245
5.1 Reversed Time 245
5.2 Multi-dimensional Time 252
5.3 Maxwell's Equations and Sending Messages to the Past 256
5.4 Wheeler and Feynman and Their Bilking Paradox 264
5.5 Absorber Theory and Signaling the Past 269
5.6 Tachyonic Signals and the Bell Quantum Antitelephone 273
5.7 For Further Discussion 283

6 The Physics of Time Travel: II 289
6.1 Faster-than-Light into the Past 289
6.2 Tipler's Rotating Cylinder Time Machine 297
6.3 Thorne's Wormhole Time Machine 301
6.4 Gott's Cosmic String Time Machine 319
6.5 Cutting and Warping Spacetime 326
6.6 For Further Discussion 334

Appendix A: Old Friends Across Time (A Story) 339

Appendix B: Newton's Gift (A Story) 347

Appendix C: Computer Simulation of the Entropic Gas Clock 355

Epilogue 357

Glossary 367

Index 377

About the Author

Paul J. Nahin was born in California, and did all of his schooling there, including a PhD in electrical engineering from UC Irvine (1972). He is now emeritus professor of electrical engineering at the University of New Hampshire. Prof. Nahin has published a couple of dozen short science fiction stories in *Analog*, *Omni*, and *Twilight Zone* magazines, and has written 18 books on mathematics and physics. He has given invited talks on mathematics at many prestigious institutions, and has appeared on National Public Radio's "Science Friday" show (discussing time travel) as well as on New Hampshire Public Radio's "The Front Porch" show (discussing imaginary numbers). He advised Boston's WGBH Public Television's "Nova" program on the script for their time travel episode.

Chapter 1
A Broad Look at Time Travel

> *"Hold infinity in the palm of your hand and eternity in an hour."*
>
> —William Blake, writing in "Auguries of Innocence" (1863), with words that could quite well describe what it would be like to time travel
>
> *"I need a place to hide, that's why I believe in yesterday."*
>
> —The Beatles (*Yesterday*, 1965)

1.1 Time Travel in the Fantasy and Science Fiction Literature

> "Woodn't it be grate to go back in tyme and correct your mistakes? Wouldn't it be great to go back in time and correct your mistakes?"
>
> —motto of *Time Twisters* comics

To travel in time.

Could there possibly be a more exciting, more romantic, more wonderful adventure than that? I don't think so, and in this opening section I want to just briefly discuss how fascinating many writers (and their readers) have found the concept of time travel, and to point out that the fascination began *long before* mathematical physicists discovered time travel lurking in Einstein's general theory of relativity.[1]

Before the arrival of humans on the surface of the Moon in 1969, the only other 'fantastic voyage' that could compare with time travel was traveling through outer space. During the seventeenth and eighteenth centuries, in fact, such voyages were the center of a genre of fiction (now called *science fiction*) called the "imaginary voyage" or "extraordinary voyage." Marjorie Hope Nicolson's[2] 1948 book *Voyages*

---

[1] An excellent, book-length *literary* treatment of time travel is by David Wittenberg, *Time Travel: the popular philosophy of narrative*, Fordham University Press 2013.

[2] Marjorie Hope Nicolson (1894–1981) was a literary scholar of the first rank at both Smith College and Columbia University.

© Springer International Publishing AG 2017

P.J. Nahin, *Time Machine Tales*, Science and Fiction,
DOI 10.1007/978-3-319-48864-6_1

to the Moon carefully documents just how popular that form of literature was—and still is. Since 1969 the first such voyages have become history, of course, and time travel has replaced space travel as the modern "imaginary voyage."

It seems a safe bet that that, given a random selection of middle-aged adults, the vast majority of them would respond enthusiastically if asked whether time travel interests them. This fascination with time travel has actually been 'scientifically' documented. In one intriguing study,[3] several hundred men and women were asked to consider the possibility of spending an hour, a day, and a year back in both their personal past (since birth) and their historical past (before birth). They were further told that it would cost $10,000 to purchase such time travel services. Their response indicated that 10 % would be willing to spend that much money for an hour in the historical past, 22 % for a day, and 36 % for a year. As might be expected, the numbers rose as the cost dropped and, if such trips were free the interest was almost universal. As one writer put it, "Time travel [is] the ultimate fantasy, the scientific addition to the human quest for immortality."[4] And as a philosopher observed, "[T]he popular appeal of time travel . . . is no doubt due to a nostalgia for the past, which is almost an omnipresent aspect of the human condition."[5]

Fiction writers have, for *centuries*, recognized the fantasy appeal of time travel. The common fairy tale theme of 'The Three Wishes,' in which the recipient ends up using the final wish to undo the unforeseen consequences of the first two, is the precursor to all modern change-the-past time travel stories. Indeed, the means of time travel in the Norwegian poet Johan Wessel's 1781 play *Anno 7603 is* a fairy. Some of the best modern science fiction stories have played with the fantasy appeal of time travel by having gifts arrive by accident from the future: the moral of such tales is generally that unearned gifts usually bring grief.[6] The editor's introduction to a time travel story involving the Civil War referred to the fantasy aspect of time travel—with a reference to another age-old adult fantasy—when he wrote "time travel stories about the Civil War have one thing in common with pornography; they serve to titillate an impulse [in the case of time travel stories, the impulse to change history] and to frustrate [history]."[7] This is the motivation for the time traveler in Stephen King's 2011 novel *11/22/63*, who uses what appears to be a naturally occurring wormhole (connecting a Maine diner to 1958) for his attempts at preventing the assassination of John F. Kennedy.

---

[3] T. J. Cottle, "Fantasies of Temporal Recovery and Knowledge of the Future," in *Perceiving Time*, John Wiley 1976.

[4] T. Paul, "The Worm Ouroboros: Time Travel, Imagination, and Entropy," *Extrapolation*, Fall 1983, pp. 272–279.

[5] J. W. Smith, "Time Travel and Backward Causation," *Cogito* 1985, pp. 57–67.

[6] Among the many such tales, five particularly good ones are "Something for Nothing" by Robert Sheckley, "Mimsy Were the Borogoves" by Lewis Padgett (pseudonym of the married couple Henry Kuttner and C. L. Moore), "Child's Play" by William Tenn (pseudonym of Philip Klass), "The Little Black Bag" by Cyril Kornbluth, and "Thing of Beauty" by Damon Knight. All can be found in various anthologies.

[7] *The Fantastic Civil War* (F. McSherry, Jr., editor), Baen 1991.

A character in the 1985 novel *The Bird of Time* by George Effinger nicely captures the fantasy appeal of time travel with the declaration "The past . . . is the home of romance." On a less poetic level, time travel and the movies and stories about it fascinate most people because they turn our everyday world view upside down and inside out.[8] Such movies and stories make people *think*. It is therefore not surprising that time travel movies have been popular for decades, from the pioneering *Berkeley Square* in 1933, to the classic 1960 filming of *The Time Machine*, to *Back to the Future* in 1985 (*the* top film that year in a *Boxoffice* magazine poll), to the flawless 1989 *Bill & Ted's Excellent Adventure*, to the clever *Terminator* action films, to the ingenious 2012 *Looper*, to the commercially successful 2014 *Interstellar*. Each of these films, and others, too, will be discussed later in the book.

When we discuss time travel, we should really be careful to distinguish between two quite different versions: to the future, and to the past. There is no dispute, today, about the first. As two *severe critics* of the possibility of time travel to the past wrote decades ago, "After 1900, special relativity made scientific discussion of time machines possible."[9] What they were referring to is the fact that, by traveling in a rocket ship fast enough (but never, unlike Superman, faster than the speed of light), and far enough, one could leave Earth, loop out on a vast journey perhaps halfway across the universe, and then return hundreds, thousands, even millions of years in the future. You could theoretically (ignoring all the *engineering* difficulties) do this, in fact, with the apparent passage of your 'personal time,' (as measured by your wrist watch or the beating of your heart) as brief as you'd like. (Physicists call 'personal time' *proper time*, and I'll return to this in Chap. 3.) This astonishing conclusion from special relativity, that time travel to the future makes physical sense, literally put a lot of Victorian-era trained physicists into shock.

A quite sophisticated use of this idea appeared early in science fiction, in the tale of a space traveler who returns from a high-speed trip out to the blue supergiant star Rigel in the constellation Orion.[10] The 900 or so light years of the round trip had taken just 6 months of ship or personal time (proper time), but a thousand years of back-home time. The traveler returns to Earth to find all he had left behind long dead and returned to dust: "Sometimes I waken from a dream in which they are all so near . . . all my old companions . . . and for a moment I cannot realize how far away they are. Beyond years and years."

Another story[11] of a trip into the future that delivers an equally powerful emotional impact, this time via a Wellsian-type time machine (more on what that means later in this chapter) rather than by rocket travel, tells of a time traveler trapped in post-nuclear war times, where there is no energy available to power his machine for the return trip. As the story ends, he finds the woman he had loved and left behind in the past. She is now the elderly widow of another man, having married his rival because the time traveler (just like Wells' Time Traveller) never returned.

---

[8] Somewhat more pompous (but no less correct) was this observation by an academic: "The time-travel [film] romance is an attempt to reenchant the world, to regain a sense of belongingness, to reinstate the magical, autocentric Universe of the child and the primitive." See W. Wachhorst, "Time Travel Romance on Film," *Extrapolation*, Winter 1984, pp. 340–359.

[9] S. Deser and R. Jackiw, "Time Travel?" *Comments on Nuclear and Particle Physics*, September 1992, pp. 337–354.

[10] R. H. Wilson, "Out Around Rigel," *Astounding Stories*, December 1931.

[11] W. Tucker, *The Year of the Quiet Sun*, Gregg 1979.

A trip into the future does not *have* to be serious or sad. A nice example of that is the story of a spaceship crew that sets off for the Alpha Centauri triple star system, more than four light years distant.[12] They survive the trip, which requires 500 years of both personal *and* external time (this story is the *only one* I'll mention in this book that uses *a preserving drug* rather than physics). What causes me to include it in a book on *time travel* (stories in which proper and external time are one-in-the-same are simply *not* about *time travel*) is that, long before they arrive at the end of their journey, the secret of faster-than-light (FTL) travel is discovered back on Earth and so they arrive at their destination to find a human reception committee! As you'll see when we get to Chap. 3, knowledge of FTL travel is equivalent to knowing the secret of travel into the past, and so the crew is sent back in time, to Earth, to just one year after they left—and they listen to their own radio communications arriving from deep space.

The *real* adventure in time travel, as suggested by "Far Centaurus," would be to go backward in time, to visit the past. The editor of the science fiction pulp magazine *Thrilling Wonder Stories* used the powerful emotional hook of changing the past in a 1950 blurb announcing a time travel story coming in the next issue: "What's the biggest mistake you ever made? Don't worry about it. You may have pulled some awful boners in your time, but there's a sure-fire remedy for them all. It's simple. Just look up at that old time-clock on the wall—and turn it back to the moment just preceding your terrible blunder. Then make your corrections—and set your time-clock back to the present. You may be starting a new chain of error, but why fret? You can go back in time again..." Or, as the promotional text on the video package of the 1986 movie *Peggy Sue Got Married* says, "to do it again" is "the golden opportunity almost everyone has longed for at least once."

Writing less romantically, a philosopher declared that a "major source of interest in the time travel question is our general fascination with the exotic and the child-like frustration we sometimes feel at being confined to the present. We wish that the benefits of moving through space could be supplemented with the benefits which would accrue from movements through time."[13] Robert Silverberg, a science fiction writer who has used the time travel theme often and effectively, expressed this sentiment quite clearly when he wrote "Suppose you had a machine that would enable you to fix everything that's wrong in the world ... The machine can do anything ... it gives you a way of slipping backward and forward in time ... Call this machine whatever you want. Call it Everybody's Fantasy Actualizer. Call it a

---

[12] A. E. Van Vogt, "Far Centaurus," *Astounding Science Fiction*, January 1944.

[13] R. A. Sorenson, "Time Travel, Parahistory and Hume," *Philosophy*, April 1987, pp. 227–236.

Time Machine Mark Nine."[14] He gives a masterful demonstration of what he means by that in one of his own stories, a tale[15] set in a year when time machines actually exist. Even so, the characters use their imaginations to explore their fantasy worlds and wishes—wishes that could (if they *really* wanted to) be realized with a real time machine. Time travel fiction is, you see, the ultimate escapist literature!

The adventure promised by time travel to the past doesn't necessarily mean *pleasant* adventure, and science fiction has used that idea to great effect. The unstated horror of a trip backward in time, if you think just a bit about it, is that it would bring the dead past, filled with all its dead occupants, alive again, literally resurrected from dank and moldering graves. The top of Mount Everest, the bottom of the Marianas Trench, the sands of Mars—none of these exotic places can even be mentioned in the same breath with the *past*. The capture of the mystery and, yes, the sheer terror of the past, is in this opening line to a 1950s tale: "When Dr. Flitter came into the room, it seemed as though the past and its dead people came in with him, clinging to him like stale surgery smells, like the cold sweat of ancient autopsies."[16] In another equally macabre story, we read of a time traveler in the past anticipating a meeting with a long-dead lover as he "shivered with a renewal of horror . . . She ought to be grateful to him for having raised her from the dead, even briefly."[17]

Another tale, slightly less gruesome, tells us of a character who delights in pointing out all the bad aspects of living in the past.[18] Tell him *when* in time, and he quickly ticks off the disadvantages of being *then*. To live in ancient Greece would let you rub shoulders with Aristotle, sure, but you already know what he said and you'd soon regret the lack of modern plumbing. The year of the American Revolution might let you exchange greetings with George Washington, but you'd also have to put up with cholera in Philadelphia, malaria in New York, and the fact that if you needed an operation there would be no anesthesia anywhere. The Victorian Age appeals to modern romantics but, before you go back, you'd better have your eyes and teeth checked. The time traveling historian in one novel[19] takes these medical warnings to heart and has her appendix prophylactically removed, and is further advised to have her nose cauterized against all the awful stinks of her destination, the fourteenth century.

On the other hand, poor health care isn't *all* there is with time travel to the past. One time traveler from the future, for example, makes a very good living in the past by winning bets on yet-to-happen events whose outcomes he knows.[20] Time travel to the past allows a Parisian curio shop in the present to offer remarkably authentic looking newspapers from 1804 whose only ‘flaw’ is that they appear to be fresh off the press—which of course they are![21] And the failed professor in one romantic story[22] finds the Paris of 1482 infinitely better than the Paris of 1961.

---

[14] R. Silverberg, "Ms. Found in an Abandoned Time Machine," *Beyond the Safe Zone*, Warner 1986.

[15] R. Silverberg, "Many Mansions," *Beyond the Safe Zone*, Warner 1986.

[16] R. Bretnor, "The Past and Its Dead People," *Magazine of Fantasy and Science Fiction*, September 1956.

[17] L. Marlow, *The Devil in Crystal*, Faber and Faber 1944.

[18] A. Bester, "Hobson's Choice," *Magazine of Fantasy and Science Fiction*, August 1952.

[19] C. Willis, *Doomsday Book*, Bantam 1992.

A popular fictional appearance of time travel is the use of the past as a hiding place, as a sanctuary for those wishing to escape the troubles of modern times.[23] An interesting twist on this idea was presented in one tale[24] in which the past is used for later military gain in the present. In this story the Earth of a thousand years in the future is ruled by a dictator, and the oppressed masses are unable to arm themselves for revolt. So, back into the past travels an agent to arrange for the construction of weapons, which are then stockpiled in hidden caverns where they can be retrieved for use ten centuries later. The past is used in this story as both a sanctuary *and* a repository from which to make war in the future, and so we have a time travel fantasy for both doves *and* hawks in the same tale! This military use of the past is passive; other writers have more aggressively used time travel to the past for military gain as, for example, mining uranium deposits before they have had time to reduce themselves to lead via radioactive decay,[25] or in drilling for Middle East oil in the past to deprive adversaries of it in the present.[26]

Time travel to the past would, perhaps, interest criminals, too. As the science fiction writer Larry Niven wrote, “If one could travel in time, what wish could not be answered? All the treasures of the past would fall to one man with a submachinegun. Cleopatra and Helen of Troy might share his bed, if bribed with a trunkful of modern cosmetics.”[27] Or, as the tragically flawed inventor of the first time machine dreamed, before using time travel to commit what he thought would be the perfect locked-room murder, “The Great Harrison Partridge would have untold wealth. He could pension off his sister Agatha and never have to see her again. He would have untold prestige and glamour, despite his fat and baldness, and the beautiful and aloof Faith Preston would fall into his arms like a ripe plum."[28]

---

[20] C. Sprague, “Time Track,” *Startling Stories*, January 1951.

[21] M. Leinster, *Time Tunnel*, Pyramid Books 1964.

[22] U. K. Le Guin, “April in Paris,” *Fantastic Stories*, September 1962.

[23] There are *many* excellent examples of such tales, a few of which are Clifford Simak, “Over the River & Through the Woods”; Ray Bradbury, “The Fox and the Forest”; Jack Finney, “Such Interesting Neighbors”; J. B. Priestly, “Mr. Strenberry’s Tale”; James Gunn, “The Reason Is With Us”; and H. B. Piper, “Flight from Tomorrow.” All can be found in various anthologies.

[24] R. F. Young, “Not to be Opened—,” *Astounding Science Fiction*, January 1950.

[25] C. Simak, “Project Mastodon,” *Galaxy Science Fiction*, March 1955.

[26] P. Anderson, “Wildcat,” *Magazine of Fantasy and Science Fiction*, November 1958, and W. Jeschke, *The Last Day of Creation*, St. Martin’s Press 1982.

[27] L. Niven, “The Theory and Practice of Time Travel,” in *All the Myriad Ways*, Ballantine 1971.

Instead of viewing the past as an aid to crime, some writers have used it as the perfect dumping ground for criminals, as a highly convenient place to remove them from society.[29] After all, there can be no breakout from the prison of the past—at least not without a time machine. What might happen to criminal recidivists in a world that has mastered time travel is nicely explained in one story as follows: "If you cannot live among people, then off to the reptiles—one hundred or one hundred twenty million years before the present. There you wouldn't freeze in a tropical pre-glacial climate, and you could nourish yourself on plants. But there is no one to talk with, boredom, and in the end you offer yourself up as an afternoon snack to a tyrannosaurus."[30] With an interesting twist on this is the tale[31] of a physics professor who *helps* criminals disappear into the past to escape relentless police pursuit.

Museum curators, too, would seem to be obvious clients for time machine companies, as would collectors of extinct species who work for zoos. An example of the first case is in a novel[32] about a time travel business called *Time Researchers*, with the corporate mottos 'We Sift the Sands of Time.' It works as a futuristic version of Indiana Jones, as finders of lost historical artifacts for customers who can pay the substantial charges. A typical mission is to make original sound recordings of one of Lincoln's unreported speeches. We find the same idea in a short story[33] about a business called *Genealogy, Inc.*, with the corporate motto

"An Ancestor for Everybody." It uses a 'time scanner' to provide its clients with a list of distinguished predecessors. And in another novel we read of the Historical Corps, whose time travel agents are "writing the definitive history of mankind.".[34]

Another use for time travel to the past, one of the most unusual I have seen, was suggested in a philosophical article[35] which considers an age-old question that has long bedeviled schoolboys: “If everything in the Universe doubled in size overnight while we slept, could we tell what had happened when we woke up next morning?” The usual answer to this puzzle (called the *Universal nocturnal expansion* by philosophers) is *no*, but the authors of the article suggest that ‘all’ we need do is take a yardstick back to yesterday and compare it with itself! Great idea, for sure, but it had appeared years earlier in a science fiction story.[36]

---

[28] A. Boucher, "Elsewhen," *Astounding Science Fiction*, January 1943. Partridge's dream is shattered, however, because he overlooks a few details about time travel, ones that he wouldn't have missed if he could have read this book. We'll come back to this classic story, which merges a time machine with murder, later in the book.

[29] This is a popular science fiction scenario, and three of the best stories playing with it are P. Anderson, "My Object All Sublime," *Galaxy Science Fiction*, June 1961; I. Watson, "In the Upper Cretaceous with the Summerfire Brigade," in *Stalin's Teardrops*, Victor Gollancz 1991; and R. Silverberg, "Hawksbill Station," *Galaxy Science Fiction*, August 1967.

[30] S. Gansovsky, "Vincent Van Gogh," in *Aliens, Travelers, and Other Strangers*, Macmillan 1984.

[31] J. Finney, "The Face in the Photo," in *About Time*, Simon and Schuster 1986.

[32] W. Tucker, *The Lincoln Hunters*, Rinehart 1958. See also A. Bitov, "Pushkin's Photograph," in *The New Soviet Fiction*, Abbeville Press 1989.

[33] M. Shaara, "Man of Distinction," *Galaxy Science Fiction*, October 1956.

[34] L. A. Frankowski, *The Cross-Time Engineer*, Del Rey 1986. The same idea is in the 1991 film comedy *The Spirit of '76*, in which time-traveling historians from 2176 visit the past in an attempt to reconstruct the lost records of the founding of America.

[35] J. C. Graves and J. E. Roper, "Measuring Measuring Rods," *Philosophy of Science*, January 1965, pp. 39–56.

More ingenious uses for the past are discussed in the story[37] of a time travel business called *Time Associates*. One use comes in the form of a request from a United States senator who wants to send the disadvantaged of today back into the remote past, where they could have a fresh start on a virgin Earth. Yet another use comes from a religious fringe group that wants to purchase exclusive rights to the time of Jesus—not to visit, but to prevent *anyone* from visiting. The group fears that any such visitors would “learn the truth,” which might contradict the very legends that form the heritage of Christianity. And, in what may be the most ingenious idea of all, *Time Associates* itself does not do business in the present, but rather 150,000 years in the past, in a ‘new’ country called Mastodonia. The corporate lawyer, you see, has determined that such an arrangement legally means the company is a *foreign* company doing business outside the United States, and so it is not liable for taxes to the IRS!

The tourist trade is a booming business in science fiction, with dinosaur hunting at the top of the list. There are many such tales,[38] including the cerebral stories in L. Sprague de Camp’s short-story collection *Rivers of Time*, starting with the classic “A Gun for Dinosaur.” The earliest (that I know of) fictional use of time travel to the past for hunting was not for dinosaur hunting, however, but rather for saber-toothed tigers, wooly mammoths, and cave bear.[39] Historical tours to the great events of the past are also an entertaining use of time travel.[40] Even mundane events may one day be on the ‘to do’ lists of time travelers to the past. In one, for example, curious crowds from the very far future show up, nightly inside the home a twentieth century family, much as tourists today visit Monticello.[41]

Perhaps the most direct use of the past’s unique resource, itself, is realized in science fiction by Hollywood. In one tale,[42] after purchasing the motion picture rights to H. G. Wells' *Outline of History*, the head of a movie studio uses a time machine to send his ace cameraman into the past to get live action footage. Prehistoric animals, the ice age, Cheops building his pyramid, the destruction of Pompeii by the eruption of Vesuvius, the Battle of Hastings, Columbus, all the *originals* of these historical events appear in the final film. Years later this idea was developed even further in a very funny novel,[43] in which a movie director uses the eleventh century as a realistic setting for a picture. Realism isn't always the result, however, as portrayed in another tale; the films produced by a gadget that can 'look' into the past are failures because they don't look "authentic enough" to Hollywood moguls![44] (Fig. 1.1).

---

[36] H. M. Sycamore, “Success Story,” *Magazine of Fantasy and Science Fiction*, July 1959.

[37] C. Simak, *Mastodonia*, Ballantine 1978.

[38] Two are B. W. Aldiss, “Poor Little Warrior,” in *The Science Fictional Dinosaur*, Avon 1982, and a famous one by Ray Bradbury, “A Sound of Thunder,” in *The Stories of Ray Bradbury*, Alfred A. Knopf 1980.

[39] C. Simak, “The Loot of Time,” *Thrilling Wonder Stories*, December 1938, in which a time machine inventor raises money for his research by transporting hunters back 70,000 years to the Old Stone Age.

[40] Three such tales are R. Silberberg, *Up the Line*, Ballantine 1969 and “When We Went to See the End of the World,” in *Beyond the Safe Zone*, Warner 1986; and G. Kilworth, “Let’s Go to Golgotha!,” in *The Songbirds of Pain*, Victor Gollancz 1985.

[41] B. Tucker “The Tourist Trade,” in *Tomorrow the Stars*, Doubleday 1952.

[42] L. Laurence, “History in Reverse,” *Amazing Stories*, October 1939.



Fig. 1.1 The inventor of a time machine demonstrates it by sending the family cat on a trip. In the story the inventor, himself, travels back to 1901, where he accidently kills his grandfather in an early pulp magazine, non-paradoxical version of the famous riddle. Illustration for Raymond A. Palmer's "The Time Tragedy" (*Wonder Stories*, December 1934) by Frank R. Paul, ©1934 by Continent Publications Inc.; reprinted by permission of the Ackerman Science Fiction Agency, 2495 Glendower Ave., Hollywood, CA 90027 for the Estate

---

[43] H. Harrison, *The Technicolor Time Machine*, Doubleday 1967.

[44] A. Derleth, "An Eye for History," in *Harrigan's File*, Arkham House 1975.

1.2 Where Are All the Time Travelers?

> "If it [time travel] *could* be done, someone will eventually learn how. If that happens, history would be littered with tourists. They'd be *everywhere*. They'd be on the *Santa Maria*, they'd be at Appomattox with [cameras], they'd be waiting outside the tomb, for God's sake, on Easter morning."[45]

The question the title of this section asks is an echo of the one the physicist Enrico Fermi (1901–1954) asked in the 1950s, about the possibility of interstellar space travel and of alien intelligent life in the universe—if such travel is possible and 'they' exist, then *where are they*? Why haven't we at least received radio signals from them? For many, the apparent lack of time travelers among us is similar evidence for the impossibility of time travel. As one famous science fiction writer put it, "The most convincing argument against time travel is the remarkable scarcity of time travelers. However unpleasant our age may appear to the future, surely one would expect scholars and students to visit us, if such a thing were possible at all. Though they might try to disguise themselves, accidents would be bound to happen—just as they would if we went back to Imperial Rome with cameras and tape recorders concealed under our nylon togas. Time traveling could never be kept secret for very long."[46]

Clarke's idea is that, from the moment after the first time machine was constructed, through all the rest of civilization, there would be numerous historians, to say nothing of weekend sightseers, who would want to visit every important historical event in recorded history. They might each come from a different time in the future, but all would arrive (according to Clarke) at destinations crowded with temporal colleagues, crowds for which there is no historical evidence!

Long before Clarke the science fiction writer Robert Silverberg had already used the same idea in his 1969 novel *Up the Line*, where it's called the *cumulative audience paradox*. That paradox claims that as time travelers to the past continue to visit certain historically interesting dates and places, there will be an ever-increasing number of people present. As it is presented in the novel, "Taken to its ultimate, the *cumulative audience paradox* yields us the picture of an audience of billions of time-travelers piled up in the past to witness the Crucifixion, filling all the Holy Land and spreading out into Turkey, in Arabia, even to India and Iran ... Yet at the original occurrence of [that event] *no such hordes were present!*" And later in the same work, we read "A time is coming [when we] will throng the past to the choking point. We will fill our yesterdays with ourselves and crowd out our own ancestors."

---

[45] A skeptic's reaction to the idea of time travel in J. McDevitt's story "Time's Arrow" in *The Fantastic Civil War* (see note 7).

[46] Arthur C. Clarke, "About Time," in *Profiles of the Future*, Warner 1985. A story that I recall once having read (but cannot now remember either the author or the title) wonderfully illustrates Clarke's point. A time traveler in disguise at Golgotha for the Crucifixion has a camera hidden beneath his robe to avoid attracting attention. All goes well until he notices odd, clicking noises coming from all those standing near him. It is then he realizes the entire crowd is *nothing but* time travelers, from all through the ages, all with hidden cameras!

Philosophers are well aware of Silverberg's and Clarke's conundrum and, indeed, it can be found in the philosophical literature before Clarke wrote. In one paper, for example, we read "Actually I know of only one argument against the possibility of time travel that seems to carry any weight at all. This is the fact that it does not appear ever to have happened. That is, it might be argued that there will be no time trips from [2100] to [2017] because we were here in [2017] and saw no time travelers. But this argument is far from conclusive."[47] At most, in other words, the absence of temporal visitors amongst us is an objection to the *actuality* of time travel, and not to the *possibility* of time travel.

This same philosopher then mentions some ways around this concern, including one which he called a "pettifogging physical limitation on time travel: perhaps the energy expenditure varies as the fourth power of the time traversed, making only very short trips feasible, and its discovery lies too far in the future for its effects to have yet been felt." Another science fiction writer, as famous as Clarke, used that idea in his 1957 novel *The Door Into Summer* when Robert Heinlein has one character comment "Now if there was some way to photograph the Crucifixion . . . but there isn't. Not possible . . . there isn't that much power on the globe. There's an inverse-square law tied up in [time travel]." Or, perhaps, time travel *is* possible but it's so extraordinarily dangerous that it's impossible to get anyone to do it. In one provocative tale[48] that takes this idea to the extreme, we read that there is only *one* time traveler, ever, from the future—indeed, from just 18 min (!) in the future—and his first (and last) experiment destroys the Earth.

Clarke presented some other possible science fiction rebuttals to the puzzle of 'where are the time travelers?' As he wrote, "Some science fiction writers have tried to get around this [question] by suggesting that Time is a spiral; though we may not be able to move along it, we can perhaps hop from coil to coil, visiting so many millions of years apart that there is no danger of embarrassing collisions between cultures. Big game hunters from the future may have wiped out the dinosaurs, but the age of *Homo sapiens* may lie in a blind region which they cannot reach."

The idea of time as a spiral was quite popular in early science fiction. Typical is one tale[49] in which the time traveler suddenly finds himself not in 1933 but in 2189. His situation is 'explained' to him thus: "[The] time stream is curved helically in some higher dimension. In your case, a still further distortion brought two points of the coil into contact, and a sort of short circuit threw you into the higher curve."

---

[47] G. Fulmer, "Understanding Time Travel," *Southwestern Journal of Philosophy*, Spring 1980, pp. 151–156. The modern view of this 'paradox' is *not* that it describes a situation so absurd that time travel must be impossible, but rather that *all* the time travelers who *were* (will be?) at the Crucifixion *are* in the historically recorded crowd (see note 46 again). The Crucifixion happened just *once*, not over and over. I'll return to this point later in the book.

[48] D. Plachta, "The Man from When," *Worlds of If Science Fiction*, July 1966.

[49] R. H. Wilson, "A Flight Into Time," *Wonder Stories*, February 1931.

A few years later (in 1937) we find another story[50] with the same spiral-time concept; with a sixty-million year pitch to the time helix, there is no danger of a grandfather paradox. That same year spiral time was the central 'scientific' theme in the stage production "I Have Been Here Before" by the English playwright J. B. Priestley.

The very next year (1938) the young Isaac Asimov used the idea in his first attempt at professional writing, despite a life-long unhappiness with the concept of time travel. Titled "Cosmic Corkscrew," it was initially rejected, indeed it was *never* published, and eventually lost. Though, perhaps, not for long, since one enterprising modern writer has used it as the basis for his own time travel tale.[51] In it a traveler from the near future travels back to 1938 to retrieve "Cosmic Corkscrew" before Asimov loses it (perhaps that's *why* it was lost!) Even when writing introductions to other writers' time travel tales, Asimov would often insert personal comments on his opinion of the concept. For example, in one volume of an anthology series he edited, *The Great Science Fiction Stories* (of 1954), he wrote "To my way of thinking it is precisely because time travel involves such fascinating paradoxes that we can conclude, even in the absence of other evidence, that time travel is impossible." And in *The Great Science Fiction Stories* (of 1961) he bluntly declared "I think scientists who think up methods of time travel are probably all wrong."

Spiral time is a close cousin to circular time. One story[52] dealing with circular time has a time traveler who finds, after a trip one hundred years into the future, that he can't get all the way back to his own time because the required energy rises exponentially with increasing penetration into the *past*. Still, it's very cheap in energy to go forward in time in this tale, and that's what the traveler does, in search of help from the future's advanced technology. He never finds what he needs, however, and so goes forward right into the collapse of the universe and through a new Big Crunch that forms an identical new cycle of time. He thereby returns home to just before he left.[53] This eternal recycling of identical, circular time is so terrifying that the traveler decides to suppress what he has learned about how to time travel—and so maybe *that's* why there are no apparent time travelers. Science fiction writer Larry Niven has argued, however (see note 27), that while this may be a conceptually valid (?) way to travel into the past, he also warns that "Removing your time machine from the reaction of the Big Bang/Crunch could change the final configuration of matter, giving an entirely different . . . history." (I strongly suspect that Niven wrote that with a big smile on his face!)

---

[50] P. S. Miller, "The Sands of Time," *Astounding Stories*, April 1937.

[51] M. A. Burstein, "Cosmic Corkscrew," *Analog*, June 1998.

[52] P. Anderson, "Flight to Forever," *Super Science Stories*, November 1950.

[53] Turning this idea on its head is the approach of the 1978 novel *The Way Back* (DAW) by A. B. Chandler. Its characters return from the past to their own time by traveling even further backward, right through the Big Bang and into the *previous* (and identical) cycle of time.

The famed English physicist Stephen Hawking is so taken with the question of 'where are all the time travelers?" that he has elevated their apparent absence ("we have not been invaded by hordes of tourists from the future"[54]) to the status of being a demonstration of the impossibility of time travel to the past. His so-called *Chronology Protection Conjecture*, Hawking likes to say, "makes the universe safe for historians": that is, there is nothing to worry about (if you're concerned that time travelers could change the past) because time travel is simply impossible. You'll see later in the book that there are other possible ways to insure the safety of history *without* denying the possibility of time travel, and Hawking himself has backed away just a bit from the Conjecture, saying now that he was simply looking for a humorous line.

While Hawking's endorsement of it has made the Conjecture famous, he wasn't the first to state it. Two years earlier it had appeared, in of all places, a *financial* publication: "[If] time travel was possible, someone from the future would eventually either discover a time tunnel or build a time machine and come visit us."[55] And even before that, an economist presented a 'proof' for concluding that "time travelers do not and cannot exist."[56] He argued that if time travelers from the future were actually amongst us (our 'now' is their 'past') then, by virtue of their knowledge of things to come (our 'future') they would make financial deals so numerous and extensive that interest rates would be driven to zero. Interest rates are *not* zero, however, and thus no such time travel hanky-panky has occurred.

These sorts of financial arguments aren't like to convince many physicists or philosophers of the Conjecture's merit. At most we can only conclude from them that time travelers from the future have *not* influenced financial affairs, which doesn't mean they aren't here. In any case, the Conjecture was actually stated more than 20 years before Hawking by Larry Niven (see note 27), who declared what is called *Niven's Law*: "If the universe of discourse permits the possibility of time travel, and of changing the past, then no time machine will be invented in that universe." And Hawking's concern over time travelers meddling with the past was anticipated in science fiction, too, by at least half a century; in a 1950 tale, for example, we learn of a Master Historian, and the graduate students in his course on 'Experimental History' in the forty-sixth century, trying to correct a problem created by a previous tampering with the past![57]

Not all physicists and philosophers feel intellectually comfortable with the Conjecture, as it seems (to them) a too quick surrender: 'Time travel is a problem

---

[54] S. W. Hawking, "Chronology Protection Conjecture," *Physical Review D*, July 15, 1992, pp. 603–611. See also J. F. Woodward, "Making the Universe Safe for Historians: Time Travel and the Laws of Physics," *Foundations of Physics Letters*, February 1995, pp. 1–39.

[55] J. Queenan, "Time Warp: Or, Investing in the Future Is a Bust," *Barron's*, January 8, 1990, p. 46.

[56] M. R. Reinganum, "Is Time Travel Impossible? A Financial Proof," *Journal of Portfolio Management*, Fall 1986, pp. 10–12.

[57] L. Jones, "Sunday is Three Thousand Miles Away," *Thrilling Wonder Stories*, June 1950. A more recent, two-*novel* treatment of historians tinkering with history is by Connie Willis (*Blackout* and *All Clear*, both published in 2010).

so hard to do let's simply *define* it to be non-existent and then we won't have to worry about it anymore.' To *really* show that time travel is impossible, however, one needs to demonstrate how it would violate one or more of the laws of physics. Hawking, of course, understands this and has stated that, as one who is no fan of time machines and time travel, he believes there is new physics yet to be discovered that *will* forbid would-be time travelers from roaming up and down the centuries. Finding that new physics is the lure the study of time machines has for him. As he correctly writes in his autobiography,[58] "Even if it turns out that time travel is impossible, it is important that we understand why it is impossible."

One mathematical physicist who agrees with Hawking on the matter of the unlikely possibility of making a time machine is the New Zealand theoretician Matt Visser. Noting that while quantum field theory, and the general theory of relativity, are each amazingly good theories in many applications within their respective realms, they are not so good in spacetime regions at the so-called *Planck scale* (that is, when the density of mass-energy reaches the fantastic level of 10^{94} grams/cm^3 and beyond) where chronology violations (that is, time travel) seem to be spawned. As Visser has observed,[59] this situation won't change until 'we wander into the guts of quantum gravity,' the unification that will merge gravity with the quantum to give a theory that *always* works. Without quantum gravity, physics will continue to be "infested" (Visser's word) with "sick" (Visser's word) spacetimes that allow time travel. Visser believes that the discovery of the theory of quantum gravity can be 'guided' by *building* causality into it,[60] and the result will finally consign time machines to where (in his mind) they belong, the dust-bin of crackpot physics.

Well, perhaps so, but we don't have a quantum theory of gravity yet, and probably won't for some time to come, and so the puzzling questions about time travel remain. To end this section on a slightly gloomy note, an idea appeared in science fiction,[61] when Hawking was still a teenager, offering a possible rebuttal to the Conjecture. It opens with one of the inventors of the first time machine just returning from a trip to the past of 1938. Still, despite this success, the inventors are puzzled by what they call 'the problem': "But if *we* have time traveled, then obviously men of the future have time traveled. They will be able—*are* able to come back. [So] where are they?" They finally conclude that there can only be two possible answers. Either there is nobody in the future, or time travel is so dangerous (is that why the future might be empty—humanity misused time travel and killed itself off?) that all who invent it will suppress it. And that's what they decide *they* must do.

---

[58] Stephen Hawking, *My Brief History*, Bantam 2013, p. 113.

[59] Matt Visser, "The Quantum Physics of Chronology Protection," in *The Future of Theoretical Physics and Cosmology*, Cambridge 2003. This paper was Visser's contribution to the celebration of Hawking's 60th birthday, held in January 2002.

[60] This may seem like something new, but it really isn't. General relativity has causality built into it on a *local* level (where it belongs); a failure of causality (that is, time travel—see J. Sharkey, "The Trouble With Hyperspace," *Fantastic* April 1965) occurs in general relativity only when one studies *global* regions of certain spacetimes. Forcing a physical theory to have a *prescribed global behavior* would be to undo all of physics since the development of *local field theories*, along with all their amazing successes in explaining nature.

[61] M. Shaara, "Time Payment," *Magazine of Fantasy and Science Fiction*, June 1954.

1.3 Skepticism About Tales of Time Travel

> "May it not be that our inability to leap into the fiftieth century, A.D., seems impossible to us, merely because of certain prejudices we entertain or certain facts and tricks of which we are still hopelessly ignorant? Assuredly, this is not a foolish query. Its answer, whatever that may be, carries immeasurable consequences for metaphysics."
>
> —a scholar wonders[62]

A thought-provoking possibility for explaining the scarcity of certified time travelers is the central thesis of a fascinating paper in the philosophical literature. The author of that paper argues (note 13) that nobody would believe a time traveler even if he willingly confessed and revealed his knowledge of the future, or even gave the details of his time machine. He goes on to make the astonishing assertion that even the *time traveler himself* would have doubts! This perhaps shocking suggestion deserves some elaboration, especially because it invokes the authority of the patron saint of skeptics for support, the Scot David Hume (1711–1776). The crucial point to keep in mind is explicitly stated in the argument: "The key question will not be 'Is time travel possible?' We shall instead ask whether it is possible to justify a belief in a report of time travel." This gets to the real heart of Clarke's puzzle from the previous section.

Much of the resistance to the idea of time travel lies in sheer skepticism. For many, time travel (to the past, in particular) is simply too much out of the ordinary to be taken seriously. For many, time travel would literally be miraculous. Hume's great work, *An Enquiry Concerning Human Understanding*,[63] contains a section on how a rational person should react to a claim that a miracle has occurred. Hume proclaimed that a miracle *by definition* violates scientific law and that, because such laws are rooted in "firm and unalterable experience," any violation of one or more of these laws immediately provides a refutation of the report of a miracle. In Hume's own words:

> "Nothing is esteemed a miracle, if it ever happened in the common course of nature. It is no miracle that a man, seemingly in good health, should die on a sudden; because such a kind of death, though more unusual than any other, has yet been frequently observed to happen. But it is a miracle, that a dead man should come to life; because that has never been

---

[62] W. B. Pitkin, "Time and Pure Activity," *Journal of Philosophy, Psychology and Scientific Methods*, August 27, 1914, pp. 521–526. Pitkin's essay was a critique of time travel as presented in Wells' *The Time Machine,* which Pitkin called "one of the wildest flights of literary fancy."

[63] Making its first appearance in 1748, *Enquiry* has been reprinted numerous times since. I used the 1963 edition published by Open Court.

> observed in any age or country . . . When anyone tells me, that he saw a dead man come to life, I immediately consider with myself, whether it be more probable, that this person should either deceive or be deceived, or that the fact, which he relates, should really have happened. I weigh the one miracle against the other; and according to the superiority, which I discover, I pronounce my decision, *and always reject the greater miracle* [my emphasis]."[64]

It is a strict interpretation of Hume that Sorenson (note 13) has adopted in claiming that a time traveler would have no success (among rational persons) with tales of 'different times.' As he explains, "Clearly the time traveler cannot persuade a reasonable person by baldly asserting 'I am a time traveler.' The improbability of his claim places a heavy burden of proof on him. But perhaps he could shoulder the burden by means of artifacts, predictions, and demonstrations." Sorenson dismisses all of these possibilities, however, by reminding us of the slightly sleazy history of parapsychology and ESP, both of which run counter to known scientific laws, but which have still duped "many a respected scientist." Any artifact, prediction, or demonstration of time travel, argues Sorenson, is more likely to be the result of deception and fraud than of actual time travel: "Should the time traveler take observers for a spin in his time machine, the skeptics will have us compare their adventures with séances." The rational reaction to such a spin around the centuries, according to Sorenson's presentation, would be like that of a magician who cannot figure out how a colleague has just done his newest act: 'Nice trick! How did you do it?'[65]

The time traveling tourist stranded in the past in one story is used to getting a skeptical reaction because he can provide his questioners no technical explanation for his situation. "How the hell should I know? I'm just a tourist. It has something to do with chronons [see the Glossary]. Temporal Uncertainty Principle. Conservation of coincidence. I'm no engineer."[66] Somewhat more successful (perhaps) is a time traveler born in 2003 who turns up in 1975. After he tries to convince an interrogator of how that can be, he apparently succeeds. As the time traveler later tells a new friend in the past of 1975, "What amazed me . . . was that he really believed me in the end." But the friend doesn't buy that, replying "He did? I think he just pretended. A scientist isn't likely to believe a thing that is against all logic."[67] If the reception committee is a crowd of conservative, cautious Humeans, it would seem that a time traveler is almost certainly doomed. Early science fiction time travelers from 2030, for example, were warned about receiving a skeptical response as follows (the editorial introduction to this tale[68] called it "a curious study of psychology"): "Our wisest men advised against [our trip to the past]. They said we could hope to be received only as imposters and fakirs, that . . . we would find only twentieth-century barbarians, suspicious, ill-tempered, likely to do us bodily harm."

---

[64] What Hume is alluding to here should be plain; as expressed in P. Heath, "The Incredulous Hume," *American Philosophical Quarterly*, April 1976, pp. 159–163, Hume was "an exposer of bad arguments in rational theology." For Hume, second-hand (or even more remote) tales of the return of a man from the dead—the claim that literally kept Christianity alive after Christ's execution—were suspect.

[65] This skeptical reaction was nicely captured in the story "E for Effort" by T. L. Sherred (*Astounding Science Fiction*, May 1947). As one character laments, "I've watched scribes indite the books that burnt at Alexandria; who would buy, or who would believe me, if I copied one. . . . What sort of padded cell would I get if I showed up with a photograph of Washington or Caesar? Or Christ?" The padded cell was indeed the fate of the time traveler in "The Ambassador from the 21st Century" (*Startling Stories*, March 1953) by H. J. Shay, the story of a man who journeyed from A.D. 2007 back to 1952 to warn of a future war; he was committed to a mental institution to receive help for his "illusion."

[66] J. Haldeman, "No Future In It," *Omni*, April 1979.

For many, such skeptical reactions to self-proclaiming time travelers seems dogmatic in the extreme—the response of people with no imagination, no spirit, and heads full of cement. Humean skepticism requires, so it would seem, the rejection of anything and everything that is profoundly surprising, leaving the world a place of utter predictability and boredom. As one science fiction writer put it, "When the miraculous occurs, only dull, workaday mentalities are unable to accept it."[69] Sorenson answers this harsh criticism as follows: "Humeans respond [to Sheckley] by distinguishing between surprises. Most surprises in science do not violate accepted scientific laws. The strange wildlife in Australia was not excluded by biology, X-rays were not precluded by physics."

Sorenson does well, however, to avoid mentioning such profound surprises as, for example, the spectrum of black-body radiation and, later, the photoelectric effect, which were not in the domain of known classical science at the beginning of the twentieth century. Those puzzling, surprising, *totally mystifying* effects required new science—the discovery of the quantum concept by Max Planck. (Explaining the photoelectric effect, *not relativity*, is what won Einstein his Nobel prize.) A strict Victorian-age Humean, as described by Sorenson, would have wrongly rejected the experimental reports of all quantum phenomena and would also (perhaps just as wrongly) have rejected all reports of time travel.

A strict Humean definition (as described by Sorenson) that a miracle has occurred requires a violation of one or more of the *known* [my emphasis] scientific laws of nature.[70] As one modern philosopher defines a miracle, it is any event that "can be explained *only* [my emphasis] by reference to the intervention of a supernatural force."[71] Time travel, by that interpretation, is *not* a miracle because general relativity, not God, is all that is required. C. S. Lewis (1898–1963), late professor of Medieval and Renaissance Literature at Cambridge University, however, absolutely rejected Hume's view on how a rational person should react to certain surprising events. Lewis, one of the most thoughtful modern writers on Christian theology, had no patience with skeptics (or, as he called them, materialists).[72]

---

[67] G. Gor, "The Garden," in *Russian Science Fiction* (R. Magidoff, editor), New York University Press 1969.

[68] P. Bolton, "The Time Hoaxers," *Amazing Stories*, August 1931.

[69] Robert Sheckley, "Something for Nothing," in *Citizen in Space*, Ballantine 1955.

[70] The word *known* is important. As a character in one early science fiction story puts it, "These things [four-dimensional object] sound like miracles; but, after all, what are miracles but phenomena which, *on account of our ignorance* [my emphasis], we cannot explain?" See B. Olsen, "The Four-Dimensional Roller-Press," *Amazing Stories*, June 1927.

[71] D. M. Ahern, "Miracles and Physical Impossibility," *Canadian Journal of Philosophy*, March 1977, pp. 71–79.

Professor Lewis graphically illustrated the dug-in position of the extreme skeptic as follows: "If the end of the world appeared in all the literal trappings of the Apocalypse; if the modern materialist saw with his own eyes the heavens rolled up and the great white throne appearing, if he had the sensation of being himself hurled into the Lake of Fire, he would continue forever, in that lake itself, to regard his experience as an illusion and to find the explanation of it in psychoanalysis, or cerebral pathology."[73] If the end of the world would receive such a skeptical response, then a mere time traveler would surely have no hope at all of being believed.

Lewis would certainly have rejected Sorenson's most astonishing assertion: "So far I have concentrated on the time travel question from the perspective of the time traveler's audience. What about the time traveler himself? Can he at least know he is a time traveler?" Sorenson argues that a time traveler, if authentic, should be able to convince his audience, and that if he can't (and he *cannot* if they are true Humean skeptics), then the time traveler must entertain doubts, too! It doesn't matter (says Sorenson) that the time traveler has memories of his adventures, and it doesn't matter that he knows in his heart that he speaks the truth. Using words that echo Lewis' sarcasm, Sorenson quickly dismisses the importance of the time traveler's self-knowledge, declaring such memories to be merely the symptoms of some deep psychosis, and the traveler's introspective sincerity to be a product of gross self-deception.

Sorenson specifically mentions the traditional Humean response to astonishing reports when he cites earlier writers on time travel in the philosophical literature. In one of those analyses, for example, we find an argument *for* the reasonableness of a rational belief in time travel ("I have been amused and irritated by the spate of articles proving that time travel is a 'conceptual impossibility') by claiming such proofs must be faulty because there is a mathematically consistent explanation for such a belief.[74] (This author was referring to spacetime diagrams, which we'll get to in Chap. 3.) This paper received a very sharp rebuttal from another philosopher who convincingly used fundamental physics to show a simple use of spacetime diagrams in a special relativity setting does *not* support time travel to the past.[75] (I'll return to this point in Chap. 3.) Even later a Humean-style rebuttal came from yet another philosopher, who showed how to explain the time travel phenomenon that Putnam (note 74) described *without* invoking time travel.[76] This isn't to say that Weingard doesn't invoke some pretty astonishing gadgetry (and more) himself, like matter transmitters and anti-matter humans. (You'll see how anti-matter ties-in with time travel a bit later in the book.) A resurrected Hume would surely applaud these rebuttal analyses (although he might also doubt his own fresh existence).

---

[72] In Lewis' eerie, unfinished story "The Dark Tower," a tale of the 'chronoscope,' a gadget that "does to time what the telescope does to space," the persistent skeptic in the story is a Scot, surely created in the image of Hume. See C. S. Lewis, *The Dark Tower and Other Stories*, Harcourt 1977.

[73] C. S. Lewis, *The Grand Miracle*, Ballantine 1986.

[74] H. Putnam, "It Ain't Necessarily So," *Journal of Philosophy*, October 1962, pp. 658–671.

[75] J. Earman, "On Going Backward in Time," *Philosophy of Science*, September 1967, pp. 211–222.

Hardly anybody is happy with Weingard's approach for avoiding time travel (including, I suspect, even Weingard). His 'explanations' seem, just like a time machine, to be incredible and, as Arthur Conan Doyle's Professor Challenger says in one tale not staring Sherlock Holmes, "You cannot explain one incredible thing by quoting another incredible thing."[77] An interesting science fiction exposition illustrating Professor Challenger's Humean philosophy occurs when a copy of *The New York Times* for December 1 shows up for some subscribers a week early, on November 22. It seems the only explanation is either that the paper really is from the future (due to some sort of fluke of the fourth dimension), or that it is a hoax. The first-person narrator of this 1973 tale[78] provides us with his reason for believing the former: "I don't find either notion easy to believe but I can accept the fourth-dimensional hocus-pocus more readily than I can the idea of a hoax." Hume couldn't have said it better.

It should be clearly understood that Hume was not arguing for disbelief in absolutely anything surprising, but rather for rational analysis. Historically, the context of Hume's times was that of what he took to be non-rational arguments for a belief in God, particularly those 'proofs' so beloved by theologians based on Design (Heath [note 64] calls such 'proofs' "philosophical museum pieces"). As Heath writes, "Hume . . . makes no attempt to deny the supposed facts; he simply argues that they are consistent with other explanations and other analogies of a less ambitious kind. There is no right to attribute to the causes of such phenomena abilities more extensive than are needed to produce the observed effects."

As a matter of fact, even Hume could be convinced of quite strange matters, and I think Sorenson does interpret the philosopher a little too narrowly. In his essay concerning Hume's position on holding a belief in God, Heath wonders whether there is "empirical evidence [imaginable] which would persuade any reasonable mind of the real existence of an infinite God." Heath answers his own question as follows: "If the stars and galaxies were to shift overnight in the firmament, rearranging themselves so as to spell out, in various languages, such slogans as I AM THAT I AM, or GOD IS LOVE—well, the fastidious might consider that it was all very vulgar, but would anyone lose much time in admitting that this settled the matter? … Confronted with such a demonstration, the hard-line Humean [but not Hume, himself, I think] could continue, of course, to argue that, for all its colossal scale, the performance is still finite, and so cannot be evidence of more than the finite, though immense power that is needed to achieve it."

---

[76] R. Weingard, "On Travelling Backward in Time," *Synthese*, July–August 1972, pp. 117–132.

[77] Arthur Conan Doyle, "The Disintegration Machine," *The Strand Magazine*, January 1929. Professor Challenger is nothing like Wells' thoughtful Time Traveller; in the original 1912 Challenger novel *The Lost World*, he was described as a "primitive cave-man in a lounge suit."

[78] R. Silverberg, "What We Learned from This Morning's Newspaper," in *Beyond the Safe Zone*, Warner 1986.

Skepticism about 'time travel' was around long before the specific idea of a 'time machine' was conceived. For example, the eleventh-century Persian poet-philosopher Omar Khayyam was blunt in his evaluation of the likelihood of reliving the past. As he so beautifully wrote in one of the quatrains of the *Rubaiyat*,

The Moving Finger writes; and having writ,
Moves on: nor all your Piety nor Wit
Shall lure it back to cancel half a Line,
Nor all your Tears wash out a Word of it.

Quite a bit later the English poet Thomas Heywood, in his 1607 play *A Woman Killed with Kindness*, had one of his characters express a similar thought:

God, O God, that it were possible
To undo things done, to call back yesterday;
That Time could turn up his swift sandy glass
To untell the days, and to redeem these hours.
Or that the Sun
Could, rising from the west, draw his coach backward,
Take from the account of Time so many minutes,
Till he had all these seasons called again,
……………………………
But O! I talk of things impossible,
And cast beyond the moon…

When Gödel's discovery of time travel in his rotating universe was announced, the skeptics were easy to find. One philosopher[79] wrote of it "This property [of time travel] must be judged an absurdity by anyone committed to the ordinary modes of speech." And another[80] was only slightly less charitable: Gödel's solution was a "bizarre conception" and a "mere mathematical curiosity." Science fiction wasn't immune to skepticism, either, even though you might have expected that to be the one place where the high drama of time travel would be welcomed. Four *years* after Gödel's paper appeared we find one respected anthologist writing,[81] as part of his introduction to a story, "In this tale we meet our first Mad Scientist. Just as in reality the thoroughly cracked pots used to be found inventing perpetual-motion machines, so in science fiction we find the lunatic fringe more often than not trying to perfect time-travel mechanisms." And that same year the founding editor of *Galaxy Science Fiction Magazine* declared "Time travel requires a suspension of disbelief that is almost unbelievable ... Scientifically, time travel can't stand inspection.".[82]

---

[79] J. D. North, *The Measure of the Universe*, Oxford University Press 1965.

[80] C. T. K. Chari, "Time Reversal, Information Theory, and 'World-Geometry'," *Journal of Philosophy*, September 1960, pp. 579–583.

[81] Groff Conklin, editor of *Science-Fiction Adventures in Dimension*, Vanguard 1952.

Years later matters had not much changed. For example, in his marvelous 1985 book *The Past is a Foreign Country*, David Lowenthal repeatedly refers to time travel as "fantasy," and to science fiction stories about time travel as "unbridled by common sense." (Lowenthal is a professor of *geography*, not physics.) Science fiction writers were still often not much more enthusiastic about time travel. The well-known science fiction writer and critic Alexei Panshin, for example, agrees with Lowenthal, at one point, long after Gödel, writing "Time travel is a philosophical concept, not a scientific one. It is, in fact, as has often been pointed out, scientific nonsense."[83]

Skepticism does have its uses, however. Modern science fiction writers have often used it as a dramatic means of building conflict and tension in their time travel stories. A skeptical reception is extreme, for example, for a soldier-in-time who has fought in numerous wars, from the ancient past to a billion years in the future.[84] He finds that nobody believes him when he speaks openly of his temporal adventures during a visit to a present-day bar. Everybody merely thinks it is all a hilarious gag. This is in great contrast to one 1870s story[85] in which suspicion of a stranger plays a central role, but which finds its offered explanation in something entirely different from time travel. It tells of a man who suddenly appears in the midst of a Union military camp during the American Civil War.

This man quickly displays strange lapses in his background, as well as possessing knowledge of many different things well beyond anything that could be called common. The details of the story are not important for us but, if it were published in a modern science fiction magazine, this man would almost surely be identified in most readers' minds as a time traveler. In 1875, however, the author's narrator found his punch line in "his firm conviction that the quiet, gentle, well-behaved, modest gentleman, so singularly gifted ... is, in plain terms, the devil!" Time travel certainly never entered the author's thoughts or, if it did, he lost his nerve at the idea of using it in this pre-Wells story. You'll recall from the opening of the Introduction that it was this 'use of the devil to explain mysterious happenings' that Wells wanted to move away from, and that was the motivation for his introduction of a time *machine*.

Hollywood has at least gotten the skeptical part of the psychology of time travel right (later discussions in this book will focus on how film makers have been less successful with the physics). When, for example, the time traveling villain in the

---

[82] H. L. Gold, editor of *The Galaxy Reader of Science Fiction*, Crown 1952.

[83] In his introduction to Robert Heinlein's classic time travel tale (to be discussed later) "All You Zombies—," in *The Mirror of Infinity*, Canfield 1970.

[84] F. Leiber, "The Oldest Soldier," *Fantastic*, May 1960.

[85] G. C. Eggleston, "Who Is Russell?" *American Homes*, March 1875.

1989 movie *Time Trackers* is confronted in the medieval past, he simply laughs-off a threat to reveal his true identity. “Go ahead,” he says in effect, ‘the only thing your talk of time machines from the future will accomplish is for people to think you are crazy!’

What would Arthur C. Clarke have thought of all this skepticism being directed toward those who claim to have a time machine? His thoughts about the difficulty time travelers would have in maintaining low profiles were what started the previous section, after all. My guess is that he would have had little patience with extreme incredulity. The surprise of being confronted by a time traveler would soon have turned to awe and pleasure IF—and I emphasize the IF—Clarke had been taken for a spin around the centuries in the stranger’s machine. He would surely have ended-up quoting his own famous ‘third law’ to explain the wonder of it all: “Any sufficiently advanced technology is indistinguishable from magic.”

Near the end of his paper, Heath writes what I think is the perfect rebuttal to anyone who would refuse to admit to time travel, even after taking a quick trip backward a few tens of millions of years to the late-Mesozoic era to hunt *Tyrannosaurus rex*, and even after seeing instant photographs of the dead monster with the skeptic’s *own foot* on the great creature’s head, or of his *own boots* dripping a bloody puddle of unholy size on the floor of the time machine. Writing about the Humean-unconvinced, even when faced with a rearranged firmament, Heath observes “But this now seems a cavil, designed only to prove that even omnipotence is powerless against the extremer forms of skeptical intransigence.” Where God would fail to convince, a simple time traveler could hardly hope to do better!

1.4 Troubles with (some) Time Machines

> “If you don’t stop this senseless theorizing upon something that’s an obvious impossibility, you’ll find yourself working alone! Your ridiculous ideas sound like the ravings of a madman. Anyone with average intelligence realizes that the mere thought of traveling through time is absurd.”[86]

If the previous section seemed just a bit gloomy concerning time travel, there is a very big reason for that. The sentiment expressed in the above opening quote to this section was a common one among philosophers long before physicists began to seriously think on the topic. While there *are* issues with time travel to the *future*, they are of an *engineering* nature, centered on how to build a big enough rocket ship with enough fuel to make the high speed, looping trip out into space and back again described in the opening section of this chapter. ‘Mere’ engineering problems are of no concern to physicists and philosophers. What *does* concern them are the far deeper puzzles of time travel to the *past*, the puzzles presented by what appear to be

---

[86] A science fiction physicist receives harsh criticism from a colleague in L. A. Eshbach’s “Out of the Past,” *Tales of Wonder*, Autumn 1938.

logical paradoxes. Before we get into the paradoxes, however, we need to first clear our minds of two common, popular notions of just what a time machine *is*. Both are false notions (one is due to H. G. Wells) which are, today, *rejected* by physicists (and most philosophers, too).[87]

As you'll see later in the book, all the theoretical time machines that have appeared in the modern physics literature involve spatial displacement. That is, they require *movement*. (On this point, the speedy DeLorean time car in the *Back to the Future* films has it right.) Wells' time machine, however, did not move; it always remained in the Time Traveller's laboratory (or at least on the spot where the laboratory would have been) unless he pushed it about after a trip in time. This, alas, results in a particularly troublesome problem: a Wellsian time machine heading into the past would run into itself!

Consider: There sits my time machine as I prepare for the first time journey ever, a trip back to the late-Mesozoic era to hunt dinosaur. I load my Continental. 600 super-high-power rifle with Nitro Express cartridges the size of bananas, kiss my wife good-bye, and climb in. I pull the lever. Now, Wellsian-type time machines don't *jump over* time but rather travel *through* time (see the Time Traveller's own description of how things looked to him, a description faithfully and spectacularly reproduced in the 1960 film). Therefore, the time machine will instantly collide with itself at the micro-moment *before* I pull the lever!

The resulting destruction obviously introduces a nice paradox: Given that this happens before I pull the lever, how did I manage to pull it? Many of the early science fiction writers were not totally oblivious to this collision problem and, in order to avoid materializing inside of an object in the future or the past, it was common to combine the time machine with an airplane.[88] Even that though might not be enough, as one writer thought a Wellsian time traveler would get "a severe case of the bends" if his body materialized in air![89] Of course, one might argue that Wells' machine does actually move because it is attached to the Earth, which is certainly moving, but it is not clear why this should result in the time machine arriving in the temporal past of the Earth, rather than in some past region of space (almost surely a vacuum).[90]

---

[87] Both of these notions still routinely appears in science fiction, however, because they are 'just too neat' to let 'mere physics' get in the way of a good tale. I use one, without apology, in my own story "Newton's Gift" in Appendix B.

[88] Three such tales are M. J. Breur, "The Time Valve," *Wonder Stories*, July 1930; F. J. Bridge, "Via the Time Accelerator," *Amazing Stories*, January 1931; E. Binder, "The Time Cheaters," *Thrilling Wonder Stories*, March 1940.

[89] J. Lafleur, "Time as a Fourth Dimension," *Journal of Philosophy*, March 1940, pp. 169–178, and "Marvelous Voyages—H. G. Wells' *The Time Machine*," *Popular Astronomy*, October 1943.

[90] Philosophers seem to be becoming more aware of the collison problem (which they have dubbed "the double occupancy problem"), and at least three papers published since the second edition of *Time Machines* discuss it: W. Grey, "Troubles With Time Travel," *Philosophy*, January 1999, pp. 55–70; P. Dowe, "The Case for Time Travel," *Philosophy*, July 2000, pp. 441–451; R. Le Poidevin, "The Cheshire Cat Problem and Other Spatial Obstacles to Backward Time Travel," *The Monist*, July 2005, pp. 336–352. Physicists don't concern themselves with the collison problem simply because they *aren't interested* in *Wellsian* time machines; I'll explain why I say this by the end of this section.

The general problem of ‘where the past is’ was nicely illustrated by the physicist Gregory Benford in his 1980 novel *Timescape*. In that story the world of 1998 is on the verge of total ecological collapse, and an attempt is made to change the past by aiming a backward-in-time message via faster-than-light tachyons (these hypothetical particles are discussed in Chap. 5) at the pivotal year 1963. When the principal scientist involved in this effort is explaining the process to a potential financial backer, he is asked, “Hold on. Aim for *what*? Where *is* 1963?” The scientist replies, “Quite far away, as it works out. Since 1963, the Earth’s been going around the Sun, while the Sun itself is revolving around the hub of the galaxy, and so on. Add that up, and you find 1963 is pretty distant.” An understanding of the question ‘Where is the past?’ actually goes quite a bit further back in science fiction. For example, after looking through a TV-like gadget to view the past, one character in a 1940s story complains, “You said you’d find Captain Kidd’s treasure, but all I can see is fog and static.” He is told that’s because “It’s too far back—1698 or thereabouts. The Earth was billions of miles from here then, and there are too many cosmic rays between.”[91]

But let’s suppose we ignore this concern about where things are for a time traveler, as do most science fiction stories. Still another problem with a true Wellsian-type time machine is that because it travels *through* time, the machine must *always* appear to be located in the same place. For example, to travel from Ford’s Theater today to Ford’s Theater on the evening of Good Friday, April 14, 1865, in a misguided attempt to save Lincoln from Booth’s bullet (*why* this would be misguided will be discussed at length later in the book), a Wellsian-type time machine would have to occupy every instant of the intervening century and more. For observers outside the machine, the machine would appear to have been sitting in the same place all those years. There is an amusing illustration of a failure to understand this point by the scriptwriters of the 1989 film *Time Trackers*, who have time travelers ‘hide’ their Wellsian machine from accidental discovery by ‘parking’ it 5 s in the future!

Wells was well-aware of the “does a time traveling object disappear or not?” issue, and tried to have it both ways in *The Time Machine* by invoking what he had the Time Traveller call “diluted presentation.” As we are told in the novel, the reason why we cannot see the model time machine he sends on its way into the future as a demonstration is that “the spoke of a wheel spinning, or a bullet flying through the air” is invisible because if those objects are “traveling through time fifty times or a hundred times faster than we are . . . the impression [they create] will of course be only one-fiftieth or one-hundredth.” Similarly for the model. This explanation breaks down when one remembers that, even if you cannot see the spoke or bullet, they are still there and you can get in their way—Wells, unfortunately, has one of his characters stick a hand into the space where the model time machine was last seen.

---

[91] M. Jameson, “Dead End,” *Thrilling Wonder Stories*, March 1941. The “cosmic rays” are presumably the cause of the interference.

This objection to Wellsian time travel was raised soon after the 1895 publication of the novel, and then again in 1914 by Pitkin (note 62), who noted that violent disaster awaited once the time journey ended. Wells, it is only fair to note, seemingly anticipated Pitkin when he had the Time Traveller say "So long as I travelled at a high velocity *through time* [my emphasis] ... I was, so to speak, attenuated—was slipping like a vapor through the interstices of intervening substances!" What this is getting at is that for the Time Traveller to stop 'inside' anything (Pitkin's example was the pile of bricks the Time Traveller's laboratory is certain one day to become) would, as Wells had his hero say, cause "a profound chemical[92] reaction—possibly a far-reaching explosion—[that would] blow myself and my apparatus out of all possible dimensions." Just why this spectacular event doesn't occur when the time machine simply stops *in air*, never mind inside Pitkin's pile of bricks, is never addressed.

In any case, it seems clear from all of this that Wells' machine travels *through time*, just as the Time Traveller claims. But Wells, himself, raises doubt when he describes the observed effects of a departing time machine. At the beginning of the novel, when the Time Traveller sends his model machine into the future, we read "There was a breath of wind, and the lamp flame jumped. One of the candles on the mantel was blown out ... and it [the model time machine] was gone—vanished!" And, at the end, when the Time Traveller makes his final exit, the narrator of the tale just misses the departure but tells us "A gust of air whirled around me as I opened the door, and from within came the sound of broken glass falling on the floor. The Time Traveller was not there ... Save for a subsiding stir of dust, the further end of the laboratory was empty. A pane of the skylight had, apparently, just been blown in." Both of these descriptions read as *implosions*, air rushing in to fill a spatial void, as though the time machines had *jumped* in time. Is there an inconsistency here? Well, perhaps not, if one accepts the curious idea of "slipping like a vapor" for an operational Wellsian-type time machine.

One famous science fiction story[93] nicely illustrates these points. The inventor of the first time machine demonstrates it to colleagues by sending a brass cube 5 min into the future. After being placed in the machine, the cube vanishes and then, 5 min later, reappears. Did the cube travel *through* time, or was its journey 'instantaneous,' so to speak? If *through* time, the cube was present at every instant after the start of its trip—so why did it vanish? The cube gets to each instant before the observers do, but why this should produce the visual effect of disappearing is unclear. The description in the story implies the cube traveled 5 min into the future without existing at any of the in-between instants, and so the story's time machine certainly was *not* Wellsian.

An immediate implication of the immobility of a Wellsian time machine is that if you are being chased by an angry mob somewhen in time (perhaps because you unwittingly violated a sensitive social taboo), then hopping into your Wellsian-type time machine isn't going to help because the machine just sits there. The mob could simply take its deliberate time in first building a roaring fire and then pushing the machine (and you) into it. As one author (with a wonderfully appropriate name!) expressed this, "You might as well try to escape by taking a nap."[94]

---

[92] Actually *nuclear*, but don't forget when Wells wrote his novel.

[93] F. Brown, "Experiment," *Galaxy Science Fiction*, February 1954.

Pulp science fiction, always alert to a good story gimmick, used this characteristic of Wellsian time machines in one clever tale[95] in which a criminal attempts to hide his crimes by sending the bodies of his victims into the far future. His mistake is to use a Wellsian time machine in which he escapes into the future. The police, however, having learned of his foul deeds, simply build a cage around the machine and arrest him when he exits 23 years later!

If a Wellsian time machine that moves *through* time suffers from a fatal collision problem, then how about that other favorite of science fiction, a time machine that *jumps* in time? (Recall the final departure of Wells' Time Traveller.) That certainly would avoid the self-colliding problem. When you pull the lever inside the machine you simply disappear from 'now' and (from your point of view) then instantly pop into existence 'then.' The problem with this sort of time machine is that a Time Traveller who uses it will have a *discontinuous* world line, with the break occurring at the moment his time machine 'jumps.' In the modern physicist's view of time travel, however, based on general relativity, a Time Traveller's world line should always be continuous. That's because general relativity is a smooth, local field theory described by differential equations, resulting in *continuous* CTLs/CTCs.

Imagine, for example, that a 'jumping' time machine inventor starts building his gadget at time $t = A$ and expects to finish building it at time $t = B > A$. At time $t = C < B$, however, he runs into a problem. Fortunately, just at that moment a fully-functional time machine suddenly appears in the lab, and from it emerges a slightly older version of the inventor. The older version has the solution to the problem and, after telling the younger version the answer, gets back into the operational time machine and jumps off to … somewhen. The younger version then completes his machine at time $t = B$, gets into it, jumps back to time $t = C$, and ….[96]

In the past, philosophers have gotten themselves all tangled-up in debates over *personal identity*, that is, which version is *the* inventor, the younger or the older? Can they both be the same person, even though the older version has a world line (*starting* at $t = C$) that is separate and distinct from the world line of the younger (that *stops* at $t = B$)? One philosopher (note 74) left physics behind and pursued this question into the following *legal* question concerning our two (?) inventors: if the older version commits a crime and then vanishes in his time machine before the police can apprehend him, can the younger version be punished even though *he* hasn't yet committed the crime? While certainly 'interesting,' this really is a non-issue for the modern physicist who is concerned only with the physical possibility (or not) of time travel to the past.

---

[94] M. Cook, "Tips for Time Travel," in *Philosophers Look at Science Fiction*, Nelson-Hall 1982. One modern story that gets Cook's point right is by I. Watson, "The Very Slow Time Machine," in *The Best Science Fiction of the Year* (T. Carr, editor), Ballantine 1979.

[95] M. Jameson, "Murder in the Time World," *Amazing Stories*, August 1940.

[96] This little story I've just told you involves what is called a *bootstrap paradox* (just where did that solution come from, that is, who thought it up?) and it is one of the real puzzles of time travel. I'll say *lots* more about such curious doings later in the book.

Well, okay, you might now say, if neither a Wellsian time machine or a 'jumping' time machine will do, then just what *are* physicists studying in their papers on time travel? The short answer here (in Chap. 3 I'll say more) is that physicists don't view time machines as super-tech gadgets covered with wires, meters, dials, and levers, humming away beneath a seated Time Traveller as gigawatts of power throb through massive copper/crystal rods, with the whole business surrounded by a pulsating red-blue glow. Hollywood absolutely loves that sort of thing, but it's simply all wrong. For modern physicists, a time machine is *a region of spacetime with special topological structure*. Then, to time travel, a Time Traveller moves through that region of spacetime (in a rocket, perhaps) along an appropriate path. To 'make a time machine' therefore, in modern terms, means to (somehow) manipulate finite amounts of matter/energy in such a way as to alter the topology of a finite region of spacetime from one that has no CTLs/CTCs to one that does.[97] The most famous example of such a spacetime topology alteration (or *warp*) is the creation of a *wormhole*. A wormhole is a *topological* artifact of a spacetime; wormholes were popularized in Carl Sagan's 1985 novel *Contact* (under the guidance of physicist Kip Thorne) and are now common in science fiction.[98] As mentioned at the start of this chapter, for example, even Stephen King uses one in his 2011 *mainstream* novel *11/22/63*.

I'll return to the 'topology of spacetime' in Chap. 3 but, just so we don't leave it here as a mysterious phrase, here's a simple illustration of a topology change. Imagine a long, flat, narrow, two-dimensional strip of paper. The strip has the following topology features of interest to us here: (1) it has a beginning (its left end) and an ending (its right end), and (2) it has two sides (the top surface) and the flip-side surface. Now, imagine that we take the right end of the strip, give it a half-twist of 180^0 through our three-dimensional space, and then finally we glue that twisted end to the left end of the strip. The half-twist and gluing (our *warp*) has changed both of the topological properties of the strip. That's because the strip now has *no end* (you can travel forever along the strip, always going 'forward' and never reaching a point where can't go forward some more), and the strip now has just *one* side. You can convince yourself that it is one-sided by coloring the strip with a crayon. During the coloring, *do not lift the crayon from the strip*. When you can color no more, you'll find that every last bit of the strip has been colored. You can't do that with the original strip without lifting the crayon and turning the strip over because the original strip was two-sided. Many readers will recognize that what we've done is make a *Möbius strip*, named after the German astronomer and mathematician August Möbius (1790–1868) who described it in 1858.

---

[97] There is a hint of this in one prescient science fiction story, in which the inventor of a time machine, when asked about how it works, replies "An electromagnetic *warping* [my emphasis] of the spacetime continuum." See N. Schachner, "When the Future Dies," *Astounding Science Fiction*, June 1939.

[98] A wormhole is featured in the 2014 film *Interstellar*, whose Executive Producer and technical advisor was Thorne. The film's special effects are relativistically correct (not the typical Hollywood 'fantasy physics'), and you can read how that was achieved in Oliver James, Eugénie von Tunzelmann, Paul Franklin and Kip S. Thorne, "Gravitational lensing by spinning black holes in astrophysics, and in the movie *Interstellar*," *Classical and Quantum Gravity*, February 2015. See also (same authors) "Visualizing *Interstellar*'s Wormhole," *American Journal of Physics*, June 2015, pp. 486–499.

Here's another astonishing property our half-twist warp has introduced. Cut the Möbius strip lengthwise with a scissors; most people believe you will then get two strips, each the length of the original strip but each only half as wide. Actually, you get one strip with a *full* 360° twist, which means the result is back to having two sides. (To see this, make a Möbius strip, cut it, and *then* apply the crayon.) And if you cut this new strip lengthwise once more, you get two separate loops, linked together. Try it and see, but be very careful. As the late science fiction writer Cyril Kornbluth (1923–1958) warned, there may be horrific potential dangers in unschooled experimentation with topology warps:

A burleycue dancer, a pip
Named Virginia, could peel in a zip;
    But she read science fiction
    And died of constriction
Attempting a Möbius strip.[99]

To end this section, I should point out that a change in the topology of a spacetime is *not* a necessary requirement for that spacetime to support time travel to the past. Gödel's rotating spacetime, for example, has a remarkably simple topology and, as you'll recall, it's literally *stuffed* with CTLs/CTCs, to the point that time travel to the past in Gödelian spacetime would be an everyday occurrence. You might think a world that presents time travel as a *fundamentally allowed* physical phenomenon, as does Gödel's spacetime, would be irresistible to science fiction writers. (So far as I know, however, no one has written a time travel story using the rotating universe idea.[100]) In Chap. 6, in fact, I'll show you just how easy it would be to time travel in Gödel's spacetime, using a rocketship as the means to move through that spacetime. Of course, *our* universe is not Gödelian, so the 'time travel to the past' question is not so easily answered for the spacetime we appear to actually inhabit.

---

[99] As you can see from this, science fiction writers have had fun with the Möbius strip. Two early examples *not* involving time travel are N. Bond, "The Geometrics of Johnny Day," *Astounding Science Fiction*, July 1941, and W. H. Upson, "A. Botts and the Möbius Strip," *The Saturday Evening Post*, December 1945. The use of the Möbius strip for time travel occurs, for example, in M. Clifton's "Star, Bright," *Galaxy Science Fiction*, July 1952.

[100] If he had lived, perhaps the well-known science fiction writer James Blish (1921–1975) would have written such a tale. In David Ketterer's biography of Blish (*Imprisoned in a Tesseract*, Kent State University Press 1987), there is this comment from a 1970 letter written by Blish: "I am especially intrigued by the spinning-universe form of time travel, especially since . . . nobody has touched it . . . But I should really stop mentioning the spinning-universe in public, or somebody will nobble onto it before I can get into it!"

1.5 Quantum Gravity, Singularities, Black Holes, and Time Travel

> "A [spacetime] singularity is where God is dividing by zero."
>
> —Anonymous

> "A theory that involves singularities and involves them unavoidably, moreover, carries within itself the seeds of its own destruction."
>
> —Peter Bergmann (1915–2002), Einstein's research assistant at the Institute for Advanced Study, Princeton

A fundamental objection to general relativity's suggestion of the possibility of time travel to the past is that, in a very deep sense, general relativity is known to be incomplete. That is, it is incompatible with quantum mechanics, which is the physics of the very, *very* small—the physics of atomic-size objects and *smaller*. We touched on this at the end of Sect. 1.2, and here we'll take a longer look at the issue of merging quantum mechanics with general relativity.

In quantum mechanics, the discrete nature of the atomic world appears in such phenomena as the photoelectric effect, in which light acts like individual particles (photons) rather than as continuous waves. Einstein's general relativity works beautifully on a cosmological scale but, like Maxwell's theory of electromagnetism, and unlike quantum mechanics, it fails when applied deep in the interior of the atom. Quantum theory, however, seems to work *everywhere*. As one physicist put it, "As far as we can tell, there is no experiment that quantum theory does not explain, at least in principle . . . Though physicists have steered quantum theory into regions far distant from the atomic realm where it was born, there is no sign that it is ever going to break down."[101]

One of the central concepts in relativity is the *world line*, which is the complete story of a particle in spacetime. A world line assigns a definite location to the particle at each instant of time. This is a classical, pre-quantum concept, however, and today physicists use the probabilistic ideas of quantum mechanics to describe the location and momentum of a particle once they get down to the atomic scale of matter. Quantum theory is a discrete theory in which the values of physical entities vary discontinuously (in 'quantum jumps'), whereas in classical theories the values of physical entities are continuous. The difference between the two types of theories is something like the difference between sand and water. Mixing the two theories—the classically smooth, continuous general relativity and the discrete quantum mechanics—to get something called *quantum gravity*, is the Holy Grail of physicists today, and nobody has more than an obscure idea of how to do it.

---

[101] N. Hebert, *Faster Than Light: Superluminal Loopholes in Physics*, New American Library 1988.

Just one of the more curious results of the fusing of quantum mechanics with general relativity may be *quantum time*.[102] That is, in quantum gravity the smallest increment of time that has physical meaning—sometimes called the *chronon*, a term first used in a non-time travel science fiction story[103]—may have a non-zero value. As we'll see later in the book, much of the controversy over the possibility of time machines hinges on what is called the *quantum gravity cut-off*. This is the end-result of destructive spacetime stresses that tend to grow toward infinity whenever a time machine spacetime topology attempts to form. This process goes under the general name of the *back reaction*, and is conceptually similar to a rubber band growing ever more taut as it is stretched, an effect that resists more stretching (and, of course, if stretched too far the rubber band breaks).

The cut-off of those stresses, at some *finite* value, is imagined to occur when the terminal phase of the growth would take place in less than the minimum possible time interval. The cut-off happens because, it is thought, nothing can actually occur in less than the minimum time. The debate is over just what that minimum duration is, and over whether the cut-off would occur before the stresses could reach *finite* values large enough to destroy the putative time machine topology. If the cut-off occurs before the back reaction stresses climb to the critical value, then the time machine survives. Otherwise, not.

To see how this 'works,' consider the two fundamental physical constants associated with classical gravity, the *gravitational constant*[104] G and the speed of light c, and the fundamental physical constant associated with quantum mechanics (*Planck's constant*) ħ. Now, if you play around with combinations of these constants it is easy to show that the following expressions have the units of length, time, and mass, called the *Planck length* (l_P), the *Planck time* (t_P), and the *Planck mass* (m_P), respectively:

$$l_P = \sqrt{\frac{\hbar G}{c^3}} \approx 1.6 \times 10^{-33}\ \text{cm},$$

$$t_P = \sqrt{\frac{\hbar G}{c^5}} \approx 5.3 \times 10^{-44}\ \text{s},$$

$$m_P = \sqrt{\frac{\hbar c}{G}} \approx 22 \times 10^{-6}\ \text{g}.$$

The extremely tiny values of l_P and t_P (the chronon), in particular, indicate (*roughly*) where it is expected that the smooth, continuous spacetime of general relativity will itself become quantized, and so will have to give way to a quantum theory of gravity.

---

[102] H. Kragh and B. Carazza, "From Time Atoms to Space-Time Quantization: the idea of discrete time, ca 1925–1936," *Studies in History and Philosophy of Science*, June 1994, pp. 437–462.

[103] S. Weinbaum, "The Ideal," *Wonder Stories*, September 1935.

[104] This is the constant in Newton's famous inverse-square law for gravity; the attractive force F between two point masses m_1 and m_2, distance r apart, is $F = G\frac{m_1 m_2}{r^2}$.

The associated value of the mass-energy density when this transition is imagined to occur is enormous; the so-called *Planck density* is the Planck mass divided by the cube of the Planck length and has the value of about 10^{94} grams/cm^3. This is where physicists expect classical and quantum gravity to part company. Can such an enormous mass-energy density actually occur?[105]

Yes, and more, in what physicists call *singularities*.

This was all still very speculative until about 50 years ago, but today the search for how to connect general relativity and quantum mechanics is serious business. That search is related to time travel studies via a fantastic sequence of discoveries in relativistic physics, made during the last 80 years, beginning in 1931 with the work of the young Indian astrophysicist Subrahmanyan Chandrasekhar (1910–1995). He combined quantum mechanics and *special* relativity to show that a non-rotating star above a certain mass (about 1.4 times the mass of the Sun) cannot evolve into a white dwarf, which had until then been thought the eventual fate of all stars. Stars more massive than 1.4 Solar masses (but not *too* massive) would, instead, become *neutron* stars. But what then happens to stars that are too massive for even *that* bizarre eventuality?

General relativity predicts that a sufficiently massive star—greater than about four times the mass of the Sun—will, when its fuel is nearly exhausted and its nuclear fires are beginning to fade, experience a truly spectacular event called *total gravitational collapse*. When its fuel-starved, weakened radiation pressure is no longer able to keep a massive, aged star inflated against the collapsing force of its own gravity, the star will suddenly implode and crush itself into what is called a *black hole*, a dramatic term coined in 1967 by the Princeton physicist John Wheeler (1911–2008) in an address before the American Association for the Advancement of Science. A black hole is an object with a gravitational field so strong that even light cannot escape—that's why it's black!—at whose center is something called a *singularity*. This is all well-known lore in the physics world.[106]

Indeed, cataclysmic views of the collapse of matter are actually quite old. In Lucretius' first-century B.C. *The Nature of the Universe*, for example, we find the following imagery on what it would be like if matter itself collapsed: "The ground will fall away from our feet, its particles dissolved amid the mingled wreckage of heaven and earth. The whole world will vanish into the abyss, and in the twinkling of an eye no remnant will be left but empty space and invisible atoms. At whatever point you allow matter to fall short, this will be the gateway to perdition." These words were actually inspired by earthquakes, not black holes and their singularities, but could a modern expert in general relativity and singularities have said it any better? But, what *is* a singularity?

---

[105] By comparison, the density of a neutron star is on the order of a 'mere' 10^{16} grams/cm^3.

[106] Perhaps not so well-known, however, is that science fiction was there long before Wheeler. In one classic tale (M. Leinster, "Sidewise in Time," *Astounding Stories*, June 1934) a scientist explains at the end, "We know that gravity warps space . . . We can calculate the mass necessary to warp space so that it will completely close in completely . . . We know, for example, that if two gigantic star masses of certain mass were to combine . . . they would simply vanish. But they would not cease to exist. They would merely cease to exist in our space and time." And then, as another character sums it up, "Like crawling into a hole and pulling the hole in after you." The explicit use of the complete term *black hole* for a region of weird spacetime also appeared in science fiction before Wheeler (P. Worth, "Typewriter from the Future," *Amazing Stories*, February 1950).

As one theoretical physicist has dramatically written, "once gravity runs out of control, spacetime smashes itself out of existence at a singularity."[107] Or to quote Hawking, "A singularity is a place where the classical concepts of space and time break down as do all the known laws of physics."[108] One particular view of a singularity is that it is a place in spacetime that has infinite density and a gravitational field that is infinitely strong. The curvature of spacetime (more on curvature in Chap. 3) at this sort of singularity, sometimes called a *crushing* singularity, is also infinite. This is the sort of singularity believed to be at the center of non-rotating black holes. Historically, however, the occurrence of infinities in physical theories has been thought the red flag signaling that the theories have simply been extended too far, and their calculated results are nonsense.

Perhaps, then, singularities occur only in unrealistic physical applications of general relativity, and so it is only *perfectly* spherical collapsing stars that can end-up (on paper) as a black hole singularity. For a while physicists tried to establish that, but they were forced to abandon the attempt when it was shown that singularities are *unavoidable* and not just the result of idealistic assumptions.[109] This result worried many, and so the concern that general relativity was failing with its prediction of black holes and their singularities continued. In the case of a crushing singularity, perhaps all that meant is that once the collapsing star had fallen into a region even smaller than an electron, general relativity is no longer valid and the singularity is simply the 'math gone wild.' Einstein, himself, held that view. In his book *The Meaning of Relativity* (based on lectures he gave at Princeton in 1921), he wrote (concerning the use of the general theory to study the origin of the universe as a "big bang," which was a crushing singularity), "For large densities of field and matter, the field equations [of general relativity] and even the field variables which enter into them will have no real significance. One may not therefore assume the validity of the equations for very high density of field and matter, and one may not conclude that the 'beginning of the expansion' must mean a singularity in the mathematical sense."

Well, what does general relativity say about the singularity at the center of a black hole? To start, the theory says that, at a distance directly proportional to the mass of the collapsed object, a so-called *event horizon* will form. The event horizon is a surface in spacetime through which anything can fall into the hole, but through which nothing, not even a photon of light, can escape outward. The singularity at the black hole's center is therefore not visible to a remote observer (the singularity is said to be "clothed," and so not "naked"[110]). For all observers beyond the event horizon, the only visible properties of the hole are its mass (via its gravitational effects), its angular momentum (its spin rate), and its electric charge, and these properties are independent of the details of the pre-collapsed object (other than the requirement that electric charge and angular momentum are conserved).

---

[107] P. C. W. Davies, *The Edge of Infinity*, Simon & Schuster 1981.

[108] S. Hawking, "Breakdown of Predictability in Gravitational Collapse," *Physical Review D*, November 15, 1976, pp. 2460–2473.

[109] S. W. Hawking and R. Penrose, "The Singularities of Gravitational Collapse and Cosmology," *Proceedings of the Royal Society A*, January 27, 1970, pp. 529–548. Ironically, one of the 'realistic' assumptions made in this paper, which appears to *force* singularities to exist, is that time travel is *impossible*!

There are actually several fundamentally different types of black holes. If the collapsed star forms a non-rotating, spherically symmetric, uncharged[111] object, then the result is called a *Schwarzchild* black hole, after the German astronomer Karl Schwarzchild (1873–1916) who found the first exact solutions to Einstein's general relativity field equations just months after Einstein published them.[112] Soon after that the Finn Gunnar Nordström and the German Heinrich Reissner independently found the solution to the field equations for the slightly more realistic non-rotating, *charged* black hole.[113] This is only slightly more realistic since it is highly unlikely a black hole wouldn't be spinning, as all observed stars are spinning and angular momentum is conserved during gravitational collapse. Another slightly more realistic solution, that of a *rotating*, uncharged black hole, was found by the New Zealand mathematician Roy Kerr in 1963, and this solution had a twist to it that at last explains why I am telling you all this—the singularity at the center of a Kerr black hole is not the *point* singularity of a non-rotating black hole but rather is a *ring* singularity. That is, there is a hole in the Kerr singularity through which matter can travel, without being destroyed, a hole that seems to act as a portal into other spacetime regions that may include past or *future* regions of spacetime. In other words, the ring singularity seems to be the entrance to a time machine.[114]

---

[110] A naked singularity, with no event horizon behind which to hide, would be particularly bothersome to physicists who don't like the idea of the breakdown of physics being on full display. What they think they'd then see would be completely unpredictable. Whether such a situation can actually exist is still open to debate, but there *are* both analytical solutions and computer simulations (incorporating realistic equations of state on the pressure response of matter as it is compressed) that seem to allow it (as in the gravitational collapse of an *infinitely* long, non-rotating cylinder that appears to result in an axial, thread-like, naked singularity).

[111] The word *charge* means either electrical *or* magnetic charge, although from a practical point *charge* probably does mean just electrical, as the theoretically possible magnetic monopole has yet to be observed and, in any case, it is thought that black holes will not have a significant electrical charge.

[112] Even *Einstein* hadn't yet solved them, and he apparently thought they were too complicated to be solved; when he saw Schwarzchild's result, he was so impressed that Einstein wrote to say "I had not expected that the exact solution to the problem could be formulated. Your analytical treatment of the problem appears to me splendid."

[113] Two years later, the University of Pittsburgh physicist Ezra Newman finally solved the field equations for the realistic, general case of a rotating *and* charged black hole.

A discussion of singularities in general relativity is especially complicated for at least two reasons. First, there is more than one type, with *crushing* being just the (perhaps) most ‘obvious.’ Another type has no infinite curvature associated with it, but rather is a point in spacetime beyond which the worldline of a freely falling mass cannot be extended. Such a point is called a *geodesically incomplete* singularity, and it represents either an end to space or to time (in either case, that point is on the boundary or edge of spacetime). There are other types, as well—I’ve mentioned the naked singularity already—and the appearance of *any* of them is distinctly unsettling (recall Bergman’s opening quote) to physicists. One that may be the most unsettling of all, however, is the *thunderbolt* singularity. This singularity propagates to infinity at the speed of light! As its discoverers dramatically put it, “It is not a naked singularity because you do not see it coming until it hits you and wipes you out.”[115]

The other reason for a discussion of general relativity singularities being complicated is that they simply are not like the singularities of earlier theories. For example, in electromagnetic field theory spacetime is the *given background reference*; that is, a singularity in that theory is a point in spacetime where the *electromagnetic field* is undefined. In gravitational field theory, however, it is spacetime itself that is undefined, and there is no background ‘something’ in which spacetime is embedded to serve as a reference.[116]

---

[114] You can find discussions on how this is imagined to work in two papers by R. Weingard: “General Relativity and the Conceivability of Time Travel,” *Philosophy of Science*, June 1979, pp. 328–332, and “Some Philosophical Aspects of Black Holes,” *Synthese*, September 1979, pp. 191–219. See also M. Calvani et al., “Time Machine and Geodesic Motion in Kerr Metric,” *General Relativity and Gravitation*, February 1978, pp. 155–163. I won’t pursue black hole time machines in this book, as it is not what modern physicists consider a plausible means of time travel (*How are you going to gain access to a black hole?!!!*) For how one science fiction writer *did* use the idea, however, see L. Niven, “Singularities Make Me Nervous,” in *Stellar* 1 (J.-L. del Rey, editor), Ballantine 1974. Black holes *are* bizarre objects—nearly as bizarre as time travel—and it seems risky to try to understand one in terms of the other (recall Professor Challenger’s observation!).

[115] S. W. Hawking and J. M. Stewart, “Naked and Thunderbolt Singularities in Black Hole Evaporation,” *Nuclear Physics B*, July 1993, pp. 393–415. As bizarre as is the thunderbolt, it was anticipated in science fiction by more than half a century. In the story “The Tides of Time” by R. M. Williams (*Thrilling Wonder Stories*, April 1940), the universe is collapsing at faster than the speed of light. Human scientists learn this when fleeing aliens stop their faster-than-light space ships to warn them. One of the human characters then looks out into the night sky and, in words that sound like those of Hawking and Stewart, “There would be no warning, for the rolling tide was traveling faster than light . . . It would come faster than the flicker of an eye. No one would see it come. One instant the world you knew would be around you. The next instant, there would be nothing. You would not even have time to know what had happened. Death, faster than the lightning flash!” This story may have been inspired by a tale published decades earlier, by the Canadian writer Frank Lillie Pollock (1876–1957). In his “Finis” (*The Argosy*, June 1906), written long before the concept of a super-nova, the light of a huge, distant star finally arrives to cook Earth into oblivion.

One early suggestion on how to avoid the problem of the crushing singularity of the non-rotating black hole (which is, as mentioned earlier, not a realistic model for the gravitational collapse of a rotating star) is that the collapse may stop short of the singularity. That is, the collapsing body might instead rebound. This ‘bounce’ would occur after the star was inside its event horizon, so an external observer would not see the later expansion, an expansion imagined to be through the event horizon *but into a different region of spacetime*.[117] When Novikov’s work was generalized the following year, the authors clearly had a hard time believing this dramatic imagery, despite their own mathematics, concluding with “It then appears necessary to believe in the existence of other [regions of the universe, including the past and the future] which will accommodate the re-expansion. This seems at least as fantastic as the alternative of [a point singularity].”.[118]

In 1974 Hawking announced an astonishing partial connection of quantum mechanics with general relativity’s black holes. He showed that, contrary to the usual image of black holes as being one-way trap doors to . . .?, black holes actually *must* radiate energy.[119] His analysis, which stunned physicists by its beautifully simple arguments, invokes the famous *uncertainty principle*, one of the corner stones of quantum mechanics. Hawking himself found the result “greatly surprising.” He also cautioned (in his 1975 paper) that the following picturesque imagery is “heuristic only and should not be taken too literally,” but it has now been in physics for over 40 years and appears to be here to stay.

The uncertainty principle states that there are certain pairs of variables associated with particles, variables that cannot be precisely measured at the same time. Time and energy form such a pair because a non-zero time interval is required to measure a particle’s energy, and the product of the uncertainty in both the time interval (Δt) and the energy (ΔE) must be at least as large as a certain non-zero constant. That is, if $\hbar$ is Planck’s constant, then $\Delta E \Delta t \sim \hbar$. This allows the process of virtual particle creation, the appearance of particle/anti-particle pairs just outside the event horizon of a black hole. The uncertainty in the energy is what gives the combined mass of the particles in a pair; this uncertainty in the energy is the quantum fluctuation energy of the intense gravity field of the hole. The only constraint is that the energy be returned to the field, via mutual annihilation of the matter/anti-matter pair within the time uncertainty dictated by the uncertainty principle.[120]

---

[116] See, for example, R. Geroch, “What Is a Singularity in General Relativity?” *Annals of Physics*, July 1968, pp. 526–540.

[117] See, for example, I. Novikov, “Change of Relativistic Collapse Into Anticollapse and Kinematics of a Charged Sphere,” *JETP Letters*, March 1, 1966, pp. 142–144, and V. P. Frolov, *et al.*, “Through a Black Hole Into a New Universe?” *Physics Letters*, January 12, 1989, pp. 272–276. Igor Novikov is a Russian physicist at the University of Copenhagen, and he will appear later in the book when we get to the paradoxes of time travel to the past.

[118] V. De La Cruze and W. Israel, “Gravitational Bounce,” *Nuovo Cimento A*, October 1, 1967, pp. 744–760.

[119] S. Hawking, “Black Hole Explosions?” *Nature*, March 1, 1974, pp. 30–31, and “Particle Creation by Black Holes,” *Communications in Mathematical Physics*, 1975, pp. 199–220.

As Hawking showed, this time interval, although incredibly short, is still long enough for the two virtual particles to separate before annihilation, one falling into the hole and the other escaping. This would happen, for example, if the particle/anti-particle pair is an electron/positron pair, and so a negatively/positively charged black hole would tend to attract the positron/electron and repel the other particle (either way, driving the charge of the hole towards zero). (Hawking then later suggested[121] that the particle *entering* the hole could be thought of as an *emitted* particle traveling backward in time, an idea that can be traced back decades, to John Wheeler—I'll return to this idea in just a moment.) By this incredible quantum process, then, the black holes of general relativity slowly *evaporate* (!) as they glow with what is now called *Hawking radiation*. That is, black holes appear to be hot bodies. But *hot* is relative, as a black hole with the mass of the Sun would have a temperature of just sixty *nano*-degrees Kelvin above absolute zero, and it would take 10^{66} years (a stupendously enormous time compared to the age of the universe) to completely evaporate.

Indeed, one physicist had already mused that the *entire universe* might have been created by a similar quantum process, *out of nothing*, a so-called *vacuum fluctuation*.[122] The explanation for why the universe doesn't then disappear—and very quickly, too, because the energy for all the mass in the newly created universe is quite large (that is, ΔE is *really big* and so Δt must be *really small*)—is that the *negative* gravitational potential energy of all that newly created matter would cancel the positive mass-energy, and so ΔE is actually *quite small* and so Δt is then *quite large*. To perhaps show he wasn't quite convinced by all that, himself, Tryon whimsically wrote "I offer the modest proposal that our Universe is simply one of those things which happen from time to time."

As a final comment on the suggestion by Hawking of a connection between virtual particles at a black hole event horizon and backwards time travel, the idea originated (as I said before) with Wheeler, in 1941.[123] In an astonishing coincidence, even as Wheeler was telling his student Richard Feynman about this, a science fiction writer was also identifying anti-matter with backward time traveling 'normal' matter.[124] Later, the Polish science fiction writer Stanislaw Lem (1921–2006) took this idea, combined it with the quantum concept of energy fluctuation, and came up with one of his typically outrageous (and typically hilarious) ideas: shooting a single positron out of an accelerator back to the very beginning of time. His story character called this fantastic machine the "Chronocannon" and claimed that's what started the universe.[125]

---

[120] The uncertainty principle has long been used in time travel science fiction. In one story, for example, a character is transported from 1950 to 2634 by a scientist of the future. Once there, this character decides he'd like to remain permanently in the 27th century. He is told that he can't because he is like an atom excited into an elevated energy state and, just as quantum mechanics says that eventually an electron in such a state will drop back down into a lower energy state, so do the "laws of time travel" require that he drop back to his normal time. How long can he remain in future, he is told, "depends on the mass [energy] of his body and the number of years the mass [energy] is displaced." That is simply the uncertainty principle. See W. Bade, "Ambition," *Galaxy Science Fiction*, October 1951.

[121] S. Hawking, "The Quantum Mechanics of Black Holes," *Scientific American*, January 1977.

[122] E. P. Tryon, "Is the Universe a Vacuum Fluctuation?" *Nature*, December 14, 1973, pp. 396–397.

Soon after Lem, a philosopher used a variant of this idea, in which the Big Bang creation of the universe was caused by a time traveler from the future who saw a need—his own existence—to generate the Big Bang. This leads to philosophical speculations on the cosmological implications of God as a time traveler.[126] Two recent physicists have taken this one step further by suggesting that the universe, via time travel, may have caused itself! As they put it, "the laws of physics may allow the Universe to be its own mother."[127]

The modern hope is that quantum mechanics (as in quantum gravity) will save physics from the horror of general relativity's singularities. This was the view of John Wheeler and, as the man who named black holes, his view is important to consider. General relativity is a classical, *smooth* theory that is fundamentally continuous, while 'our' universe appears to be a quantum one. So, perhaps, general relativity's prediction of singularities may be just an artifact without physical reality in the 'real world.' Wheeler's position was based on the quantum fluctuations of gravity fields, which are related to the uncertainties inherent in our knowledge of the values of physical entities. Such fluctuations are vanishingly small in systems of everyday size, but they increase dramatically at very tiny distances that are twenty orders of magnitude smaller than the nucleus of an atom. In the microscopic region of spacetime that the matter forming a black hole is falling into, these fluctuations might conceivably result in effects that preclude the formation of a singularity. Agreeing were two physicists who asserted that, even without a detailed knowledge of quantum gravity, quantum effects "would smash the idealized interior geometry"

---

[123] See Richard Feynman's Nobel lecture, reproduced in *Science*, August 12, 1966, pp. 699–708, where he recounts Wheeler's 'proof' for why every electron in the universe has *exactly* the same charge ('there is only *one* electron, weaving its way back-and-forth in time, with positrons being the electron when traveling backward-in-time').

[124] Will Stewart, "Minus Sign," *Astounding Science Fiction*, November 1942. 'Will Stewart' was a pen-name for John Stewart Williamson (1908–2006).

[125] S. Lem, "The Eighteenth Voyage," in *The Star Diaries*, Seabury Press 1976.

[126] G. Fulmer, "Cosmological Implications of Time Travel," in *The Intersection of Science Fiction and Philosophy* (R. E. Meyers, editor), Greenwood Press 1983. Isaac Asimov used a similar idea in his story "The Instability," *The London Observer*, January 1, 1989.

[127] J. R. Gott and L.-X. Li, "Can the Universe Create Itself?" *Physical Review D*, 1998, 023,501.

[that is, the ring singularity] of a rotating, charged black hole, thereby eliminating any possibility of using such a hole for time travel.[128]

And finally, to generalize beyond black holes to the hoped-for pay-off of the coming of quantum gravity in banishing singularities altogether, one recent study has examined how non-crushing singularities (that is, ones of the geodesically incomplete type) *are* apparently "healed" (the authors' term) by quantum effects.[129] With the eventual development of quantum gravity, perhaps all the singularities of general relativity will vanish while leaving the CTCs/CTLs intact, thereby removing a form of doubt in the theory's apparent support for time travel to the past. It may be a long time coming, however: as the University of Sydney philosopher of science Dean Rickles recently (2014) wrote in his book *A Brief History of String Theory*, "quantum gravity is in many ways . . . a revolution still waiting to happen."

1.6 Tipler's Time Machine

> "In short, general relativity suggests that if we construct a sufficiently large rotating cylinder, we create a time machine."[130]

The time traveling property of the ring singularity in a rotating black hole once made it a favorite of science fiction writers, as in Joe Haldeman's classic 1974 novel *The Forever War* (in which the term used is not *black hole*, but *collapsar*, which is a nicely descriptive word in its own right). A major difficulty with this approach, however, as I mentioned in the previous section (note 114), is that of 'getting one's hands on' (so to speak) a black hole! So, is there any other 'time machine' that is consistent with general relativity? Yes, there is.

In 1974 a young physics graduate student at the University of Maryland, Frank Tipler, caused a bit of a stir when he published what seemed to be quite specific construction details for a time machine. Indeed, the final sentence (the above quotation) of his paper couldn't be clearer. Nobody had ever before made such a statement in a respectable physics journal and, best of all, there were no apparent spacetime singularities involved. However, a close look at Tipler's analysis does turn up some difficulties.

What Tipler had actually done was to show that if one had an *infinitely long*, *very dense* cylinder rotating with a surface speed of at least half the speed of light (the rotation speed is such that the outward centrifugal forces are balanced by the inward gravitational attraction of the cylinder), then this allowed the formation of closed timelike curves around the cylinder. This means that by orbiting the surface of such a fantastic cylinder, one could travel through time into the past—but not to earlier than the moment of the creation of the cylinder.

---

[128] N. D. Birrell and P. C. W. Davies, "On Falling Through a Black Hole Into Another Universe," *Nature*, March 2, 1978, pp. 35–37.

[129] T. M. Helliwell and D. A. Konkowski, "Quantum Singularities in Spherically Symmetric, Conformally Static Spacetimes," *Physical Review D*, May 13, 2013, 10404.

[130] F. J. Tipler, "Rotating Cylinders and the Possibility of Global Causality Violation,' *Physical Review D*, April 15, 1974, pp. 2203–2206.

This last point is a very important one, as it does avoid one particularly odd paradox (called a *bootstrap*): a traveler going backwards in time to tell the inventor of a time machine (perhaps an earlier version of the time traveler himself) how to build the time machine. You can find this idea in early science fiction,[131] and a minor variant of it was amusingly illustrated in the 1985 film *Star Trek IV: The Voyage Home* (when you next watch the movie, ask yourself who actually invented "transparent aluminum"?) Bootstrap paradoxes are quite mysterious and still befuddle physicists and philosophers. Science fiction writers, on the other hand, love bootstraps as great story gimmicks.

Tipler's cylinder would also enable a time traveler to return to her original time, to go "back to the future," by orbiting the cylinder in the reverse direction (but no further into the future than when the cylinder ceases to exist). Later in the book I'll show you a simple illustration—based on a similar one in Tipler's PhD dissertation, published in 1976—of how the cylinder works as a time machine. No one, in fact, disputes any of this. It *is* true. On paper.

But Tipler did *not* prove that a time traveling property holds for cylinders of even very long but *finite* length, which are the only kind we could actually build from a finite amount of matter; he merely suggested that such might be the case. This suggestion does seem reasonable, because if the time traveler orbits at the midpoint of the cylinder, near the surface, then the gravitational end-effects of sufficiently remote ends of the cylinder would, you'd think, become negligible. Similar mathematical approximations are routinely made, for example, when calculating the electrical effects of charged cylinders of finite length. But as one physicist has warned, "Extrapolation from cylindrical symmetry to reality is very dangerous, since spacetime is not even asymptotically flat around an infinite cylinder."[132] The issue of whether a spinning, finite-length cylinder can create closed, timelike curves is still open: to quote another physicist, "[In] some respects an infinite cylinder may be a model for a long finite one, and the possibility cannot be dismissed that a time machine might be associated with a long, but finite rotating system."[133]

---

[131] See, for example, C. Cloukey, "Paradox," *Amazing Stories Quarterly*, Summer 1929. Later in the book I'll discuss even earlier literary occurrences of bootstraps (that is, of *information* on closed loops in time).

[132] K. S. Thorne, "Nonspherical Gravitational Collapse: Does It Produce Black Holes?" *Comments on Astrophysics and Space Physics*, September–October 1970, pp. 191–196. What "asymptotically flat" means will be discussed in Chap. 3.

[133] W. B. Bonner, "The Rigidly Rotating Relativistic Dust Cylinder," *Journal of Physics A*, June 1980, pp. 2121–2132. Tipler was not the first to study rotating cylinders in the context of general relativity. Such cylinders had been around for decades, going back to 1932. A good reference is M. A. Mashkour, "An Exterior Solution of the Einstein Field Equations for a Rotating Infinite Cylinder," *International Journal of Theoretical Physics*, October 1976, pp. 717–721. The first-analyzed configuration of matter that generates closed timelike lines, solved in all its general relativistic detail, was the infinite rotating cylinder studied by W. J. van Stockum,

There is, however, another potential problem besides the length of the cylinder. There is a strong likelihood that a Tipler cylinder under construction would collapse under its own internal gravitational pressure before it could be made nearly long enough to be even ‘approximately infinite.’ That is, such a finite-length cylinder might crush itself along its long axis into a pancake-shaped blob, something like what happens to a long cylinder of jello stood on-end. An ordinary can of jellied cranberry sauce will also sometimes display this curious behavior.

The required rotational speed raises yet another concern, as well. We are not talking about cylinders the diameter of a pencil, or even of a large water pipe. Recall that for a given surface speed, the larger the diameter the less the centrifugal acceleration at the surface. It is easy to calculate that even a huge cylinder 10 kilometers in radius, with a surface speed of half the speed of light, would have a surface acceleration *hundreds of billions* of times the acceleration of Earth’s surface gravity. No known form of ordinary matter could spin that fast and not explosively disintegrate; Tipler has estimated that the required density for a time machine cylinder would be 40 to 80 orders of magnitude above that of nuclear matter. (In a masterful understatement, Tipler calls this astonishing stuff “unknown material.”) Made from such incredibly superdense stuff, even a finite cylinder would still be as massive as the Sun but many trillions of times smaller. Showing no lack of imagination, Tipler has suggested the possibility of speeding up the rotation of an existing star as an alternative approach to that of building a cylinder.[134] That, of course, would be project for a far-future society, with a *very* advanced technology.

All of these concerns were discouraging to Tipler (who could blame him?), and his pessimism about the actual likelihood of achieving time travel via one of his cylinders is shown by the words he used to open his 1977 paper (note 134): “Any attempt to evolve a time machine] from [normal] matter will cause singularities to form in spacetime. Thus, if by the word ‘manufacture’ we mean ‘construct using only ordinary materials *everywhere*,’ then the theorems of this paper will conclusively demonstrate that a [time machine] cannot be manufactured.” But not all physicists agreed.

“The Gravitational Field of a Distribution of Particles Rotating About an Axis of Symmetry,” *Proceedings of the Royal Society of Edinburgh*, 1939, pp. 135–154. This is particularly interesting because, while Van Stockum didn’t spot the presence of closed timelike lines in his solution, his cylinder is made entirely from *ordinary* matter.

[134] F. Tipler, “Singularities and Causality Violation,” *Annals of Physics*, September 1977, pp. 1–36. See also his earlier paper “Causality Violation in Asymptotically Flat Space-Times,” *Physical Review Letters*, October 1976, pp. 879–882, where he wrote “There are many solutions to the Einstein equations [of general relativity] which possess causal anomalies in the form of closed timelike lines (CTL). It is of interest to discover if our Universe could have such lines. In particular, if the Universe does not at present contain such lines, is it possible for human beings to manipulate matter so as to create them? [That is, to construct a time machine.] I shall show in this paper that it is *not* [Tipler’s emphasis] possible to manufacture a CTL-containing region without the formation of naked singularities, *provided normal matter is used in the construction attempt* [my emphasis].”

Years after Tipler wrote, one physicist replied[135] with *two* pointed observations. First, Tipler's theorems apply only to singularities of the incomplete kind, not to the more convincingly fatal crushing (or curvature) type. Second, to quote Ori at length, "The standard interpretation of Tipler's theorems is to say that the appearance of a singularity in a given [spacetime] model indicates that this model is unrealistic and cannot be physically realized. Even for future-generation engineers it will probably be impossible to use 'singular matter' for the construction of their time machine. However, the theory of black holes provides an obvious counterexample to this interpretation. For, by applying this interpretation to the black hole singularity theorems one could conclude that black holes can never form." Yet black holes with several times the mass of the Sun *have* been detected in orbit about certain stars, and at least one supermassive black hole (with a mass equal to more than three *billion* Suns) has been detected at the core of galaxy M87. Indeed, it is now believed that the center of *every* sufficiently massive galaxy in the universe is home to a black hole (the one at the center of our own galaxy, the Milky Way, has a mass about three million times that of the Sun).

Even less concerned about singularities interfering with time travel were two other physicists who wrote[136] "It would seem that a successful attempt to manufacture [a time machine] within a finite region of space will be accompanied by the creation of a singularity . . . This does not immediately imply, however, that with a sufficiently advanced technology one could not make a time machine. *There is no reason to suspect spacetime singularities could not in principle be created through deliberate human action* [my emphasis]."

These optimistic views were, of course, welcome news for science fiction writers, who had been using Tipler cylinders almost from when Tipler first wrote of them. Indeed, Larry Niven liked them well enough to 'lift' the very title of Tipler's paper (note 130) for the title of a short time travel story for inclusion in his 1979 collection *Convergent Series*. Just one year after Tipler's paper appeared, Poul Anderson featured the cylinders in his 1978 novel *The Avatar*, where they are called "T-machines": one can imagine the "T" stands for Time or Tipler or even both. Anderson's story describes the cylinders as having been scattered about the universe by ancient, altruistic aliens called "the Others," for the use by any who come across them and who have the wits to decipher *how* to use them. Anderson recognized the obvious problems with Tipler cylinder construction, and so has one of his characters say of T-machines, "I have no doubt whatsoever that [they are] the product of a technology further advanced from ours than ours is from the Stone Age."

---

[135] A. Ori, "Must Time-Machine Construction Violate the Weak Energy Condition?" *Physical Review Letters*, October 1993, pp. 2517–2520. The weak energy condition is the seemingly 'obvious' requirement that the observed local mass-energy density should never be negative. Quantum mechanics predicts (and it has been experimentally confirmed) that there *are* exceptions.

[136] M. P. Headrick and J. R. Gott, "(2+1)-Dimensional Spacetimes Containing Closed Timelike Curves," *Physical Review D*, December 15, 1994, pp. 7244–7259. The '(2+1)' refers to a toy spacetime with just two spatial dimensions and one time dimension.

Even before (actually *long* before) Tipler's paper, science fiction had foreshadowed his physics. Oliver Saari (1918–2000), for example, had incorporated both superdense matter and the rule of 'no time travel before the creation of a time machine' in a story written *40 years* earlier.[137] Saari's fictional time machine works by warping spacetime via a plate of superdense matter. (An even earlier tale[138] had also used superdense matter, but it was badly flawed by its hocus-pocus invoking of 'rays' emitted by the newly discovered element of *tempium*.) The 'no time travel before the creation of a time machine' rule is the basis for an obvious response to Hawking's Chronology Protection Conjecture, discussed earlier in this chapter, and it was so used by one physicist to rebut the Conjecture: as he wrote,[139]

(1) time machines, if possible, must have the property of not being able to travel back to before their creation, and
(2) no time machine has yet been created.

The absence of time travelers amongst us, therefore, provides no insight, one way or the other, on the eventually possibility of constructing a time machine.

1.7 For Further Discussion

Observations of the background microwave radiation that permeates the universe is strong experimental evidence for the Big Bang, the singularity thought to be the origin of the universe. This singularity is not shielded from us by an event horizon, and so is not a naked singularity (note 110), which means it is potentially visible. In 1969 the English theoretician Roger Penrose, however, proposed a metaphysical 'law' called the *cosmic censorship principle*, which asserts that naked singularities are impossible. Discuss the obvious tension between Penrose's principle and the Big Bang singularity. (See, for example, P. Kosso, "Spacetime Horizons and Unobservability," *Studies in History and Philosophy of Science*, June 1988, pp. 161–173.)

---

[137] O. Saari, "The Time Bender," *Amazing Stories*, August 1937. In this story we read that the time traveler "could not travel into the past for the plate had to exist in all ages traveled, and it had not existed before he made it."

[138] E. L. Rementer, "The Time Deflector," *Amazing Stories*, December 1929.

[139] K. S. Thorne, "Do the Laws of Physics Permit Closed Timelike Curves?" *Annals of the New York Academy of Science*, August 10, 1991, pp. 182–193. Science fiction writer Damon Knight (1922–2001) anticipated Thorne's rebuttal in his story "Azimuth 1, 2, 3, … ," *Isaac Asimov's Science Fiction Magazine*, June 1982.

In the text I mention the "transparent aluminum" bootstrap paradox that appears in the 1985 movie *Star Trek IV*. Even earlier, a movie bootstrap appeared in 1980 film *The Final Countdown*. There, the designer of a modern naval warship that temporarily time travels back to the Pearl Harbor of December 6, 1941, turns out to be a crew member who was (is) accidently left behind in the past when the ship returns to the present. In the past he *will be* able to design the ship because he already knows how it *was* designed—by himself! In the more recent 2014 film *Interstellar*, a wormhole near Saturn is discovered. By the end of the film we learn that it was put there by future humans, humans who exist because their ancestors (us!) were saved from a planet-wide ecological disaster when they used the wormhole to discover new worlds in far-flung regions of the universe. Decide whether or not the existence of the wormhole represents a bootstrap paradox, and defend your position.

One difficulty in using a black hole as a means of traveling from one region of the universe to another (with time travel as a special case) is simply getting to a black hole in the first place. The nearest one to Earth, as far as is known, is many light years distant. One reason for this may be an anthropic one (see note 13 in the "Introduction"). That is, a planet near a rotating black hole would either be eventually swallowed whole, or have its surface blasted by a firestorm of radiation produced by in-falling matter. In any case, no intelligent life able to recognize time travel would ever evolve on such a planet in the first place. That is, we are here to wonder about the absence of near-by black holes precisely *because* we aren't near a black hole. The lack of black holes near Earth is addressed in Joe Haldeman's 'Earth vs. Aliens' novel, *The Forever War*, by using the time dilation effect of special relativity (discussed in Chap. 3) that allows long travel distances to be covered in a reasonable time (as measured by clocks in rocket ships traveling near the speed of light). Still, while the travel time to reach a black hole distant from Earth by many light years may only be 6 months of ship time, back on Earth many *years* may pass. Once at the black hole the ship enters it and instantly 'jumps' to a vastly different region of the universe. In the novel, no time travel after the time dilation experienced in just getting to the black hole occurs, but Haldeman uses that to great effect as follows. Before entering into combat, Earth's soldiers are told that when they exit the hole into a new region of the universe, they may encounter alien warships equipped with *their* latest technology, technology that could be far in advance of the Earth warship's technology

(continued)

which dates from Earth's *past*. That is, humans will be fighting against technology that dates from the Earth warship's *future*. To quote the novel, "Relativity traps us in the enemy's past; relativity brings them from our future." Explain this.

In one of the quatrains of the *Rubaiyat*, the eleventh century Persian poet-philosopher Omar Khayyam wrote

> *The Moving Finger writes; and having writ,*
> *Moves on; nor all your Piety nor Wit*
> *Shall lure it back to cancel half a Line,*
> *Nor all your Tears wash out a Word of it.*

Nearly a 1000 years later the German theoretical physicist Hermann Weyl (1885–1955), a colleague of both Einstein and Gödel at the Institute for Advanced Study in Princeton, NJ, wrote the following in his book *Space-Time-Matter* (published in 1921, three decades *before* Gödel's 1949 time travel paper):

> *It is possible to experience events now that will in part be an effect of my possible future resolves and actions. Moreover, it is not impossible for a world-line (in particular, that of my body), although it has a time-like* [see the index] *direction at every point, to return to the neighborhood of a point which it has already once passed through. The result would be a spectral image of the world more fearful than anything the weird fantasy of E. T. A. Hoffmann* [an early nineteenth-century German writer of the eccentric] *has ever conjured up. In actual fact the very considerable fluctuations of the* [components of the metric tensor, to be discussed in Chap. 3] *that would be necessary to produce this effect do not occur in the region of the world in which we live . . . Although paradoxes of this kind appear, nowhere do we find any real contradictions to the facts directly presented to us in experience.*
> Compare these two views and, in particular, discuss what each says about the idea of 'reliving the past.'

In the opening section of this book ("Some First Words") I mention how now and then science fiction has anticipated physics. One interesting example of this occurs in a story of a time traveler *almost* meeting himself, a story published 2 years *before* Gödel's 1949 time travel paper in which he suggests just such a possibility. The story opens with a man on a ship spotting the signal fire of a castaway on a Pacific island, as well as the tiny, distant figure

(continued)

of a man waving and jumping about. While sailing in to help, the ship hits a mine left over from the war, and the would-be-rescuer becomes a castaway, too. After swimming to the island, he can find no trace of who built the fire, although there are footprints all about in the sand. Exploring the island, he finds the remains of a crashed interstellar spaceship (!), powered by a drive unit based on 'temporal precession.' The man, curious, turns the drive on and thus sends himself backward in time by one day. He then spots a ship on the horizon, builds a fire, waves and jumps about, then *recognizes the ship as his own* …. And so the loop nearly but not quite closes. The man, apparently, rushes off into the jungle, terror-stricken at the thought of meeting himself. (You can find this tale by A. B. Chandler (1912–1984), "Castaway," in the November 1947 issue of *Weird Tales*, a publisher more of fantastic, supernatural, and horror stories than of science fiction. Perhaps easier to locate would be an anthology in which it has been reprinted: *Science-Fiction Adventures in Dimension* (G. Conklin, editor), Vanguard 1953.)

Speculate on what happens to the man. In particular, does Wells' own criticism of *The Time Machine*, concerning "vain repetitions" of time travelers, apply here (see the "Introduction" again)?

A philosopher has argued against the force of Hawking's chronology protection conjecture as follows: "There is an old argument to the effect that while backward time travel may be *possible*, it will never actually occur—for if it were going to occur, we would *already* have encountered the time travellers involved, whereas in fact we have done no such thing. … But consider an isolated society living in a remote part of the world. Some members of this society are engaged in a long-running debate concerning the possibility of human flight. Were a 747 to pass overhead, would the debaters necessarily recognize it as containing flying humans? The answer to their question might have been staring them in the face for years, without them realizing." (See Nicholas J. J. Smith, "Bananas Enough for Time Travel?" *British Journal for the Philosophy of Science*, September 1997, pp. 363–389, in particular note 3 on p. 364. The perhaps curious appearance of 'bananas' in the title of this paper will become clear when, in Chap. 4, we delve into the details of the famous grandfather paradox.) How would *you* answer Smith's question? Do you think it is plausible, as Smith implies, that we could right now be observing (without realizing it) effects in the present-day world that are the result of time travelers amongst us? What sort of effect(s) might raise this suspicion in *your* mind?

As discussed in Sect. 1.6, Tipler expressed some pessimism in his 1977 paper (note 134) about the possibility of actually constructing a time machine from a rotating cylinder. But that doesn't mean he didn't have some doubts, too, about theoretical 'proofs' of something being impossible. In his 1976 PhD dissertation, for example, he included an amusing reference to Simon Newcomb (a real-life mathematician that Wells' Time Traveller cites in *The Time Machine*—see note 102 in Chap. 2) who published mathematical 'proofs' that it would be impossible with known science to build a "practicable machine by which men shall fly long distances through the air." Why do you think Tipler did that? You can read more about Newcomb's 'proofs' in "Is the Airship Coming," *McClure's Magazine* (September 1901, pp. 432–435) and "The Outlook for the Flying Machine," *The Independent* (October 22, 1903, pp. 2508–2512).

In his autobiography, the Princeton physicist John Wheeler had this to say about time: "The smooth flow of time—or our smooth passage through it—is an illusion that is shattered when we . . . ask about time at the moment of the Big Bang, at a moment of gravitational collapse, at the moment of the Big Crunch. Students and others often ask what existed before the Big Bang. To say that we don't know is not to say enough. Even to say that we have no *way* of knowing is not enough. We really have to say that space and time came into existence, along with matter and energy and the laws of physics, at the moment of the Big Bang. If the universe expands to a maximum size, starts contracting, and eventually collapses to a fiery death—a fate that seems likely to me and to some other theorists . . . then time and space, too, will end in this Big Crunch. I can reach no conclusion other than this: there was no 'before' before the Big Bang, and there will be 'after' after the Big Crunch." (See J. A. Wheeler, *Geons, Black Holes, and Quantum Foam: a life in physics*, W. W. Norton 1998, pp. 349–350.) That is, when the Big Bang singularity occurred, time was *created*, and if the universe should collapse in the far future in a Big Crunch, time will be *annihilated*. This is a view of *nothingness* that transcends even that of the grave. Sharing Wheeler's dark view of the ultimate fate of reality, but instead giving the *victory t*o time (rather than its annihilation), was the Irish writer Jonathan Swift (1667–1745) in his poem *Riddles* (circa 1724): "Ever eating, never cloying/All-devouring, all destroying/Never finding full repast/ Till I eat the world at last." How do you think theologians would respond to Wheeler and Swift?

The American philosopher Roy Sorenson was cited in note 13 in the discussion of the difficulties a time travel would have in convincing skeptics that he *had really* time traveled (short of bringing a fresh dinosaur egg back and hatching it!). This question was treated in early pulp science fiction ("The Sands of Time," see note 43 in "Some First Words") as follows: The time traveler takes a sealed box of pure radium (with his name written on the inside of the lid) into the distant past, and buries it in a secure location. Upon returning to the present he unearths the box; testing of the contents will show that some of the radium has radioactively decayed to lead. Indeed, the amount of decay would be a direct measure of how far back into the past the box had been transported. This issue was later elaborated on by the English philosopher Alasdair Richmond in his paper "Time Travel, Parahistory and the Past Artefact Dilemma," *Philosophy*, July 2010, pp. 369–373. There he imagined two possible ways a time travelling Shakespearean scholar might attempt to convince skeptical colleagues that he had discovered a draft of *Hamlet* dating from the year 1589 (10 years *before* the earliest accepted date of its composition by Shakespeare). The first attempt is to simply bring that draft directly back with him in the time machine, from 1589 to the present. Then, of course, many of the inherent clues as to the draft's authenticity, such as chemical composition of the ink, the weave of the paper, and orthography (the style of writing in 1589) would be consistent with the time traveler's claim, but other clues would *not*—the *age* of the paper and of the ink, for example, would be taken as evidence fatal to the claim, as they would not be nearly 430 years old. They would appear, in fact, to be practically new! The draft would, therefore, be dismissed as simply a clever forgery. The second attempt would try to get around this problem, as follows. After locating the draft in 1589, the time traveler *doesn't* bring it back to the present, but rather stashes it away in a secret hiding place. Then, once back in the present, he takes his colleagues to the secret hiding place and, with a flourish, reveals the draft which now *is* nearly 430 years old. Much to the time traveler's frustration, however, his colleagues still reject his time travel claim, this time saying he must have simply found the draft in the 'usual' way (under the floorboards in somebody's attic, for example), and is just pretending to have found it via time travel. Can you think of a way, using the *Hamlet* draft, the time traveler might be able to convince his skeptical colleagues?

The fan I quoted in "Some First Words," who wrote to *Astounding Stories* in 1931 to express his unhappiness with the appearance of women in that magazine's stories, was quite clear about his concerns—although, given the times, he carefully avoided any direct mention of sex. A modern, highly successful *female* writer of science fiction, Anne McCaffrey (1926–2011), didn't shy away from that, however, when she wrote the following in a hilariously funny essay: "Prior to the '60s, stories with any sort of love interest were very rare. True, it was implied in many stories of the '30s and '40s that the guy married the girl whom he had rescued/encountered/discovered during the course of his adventures. But no real pulse-pounding, tender, gut-reacting scenes. The girl was still a 'thing' to be used to perpetuate the hero's magnificent chromosomes. Or perhaps to prove that the guy wasn't . . . I mean, all those men locked away on a spaceship for months/years at a time. I mean . . . and you know what I mean even if I couldn't mention it in the sf of the '30s and '40s." (See Anne McCaffrey, "Hitch Your Dragon to a Star: Romance and Glamour in Science Fiction," in *Science Fiction, Today and Tomorrow*, R. Bretnor, editor, Harper & Row 1974, pp. 278–292.) Modern time travel science fiction has shown a huge change (for the better) on this score. Discuss, for example, the emotional power of a love story between a couple separated in time, as depicted in the 1975 novel *Bid Time Return* by Richard Matheson (made into the 1980 film *Somewhere in Time*). How do you think the 1931 fan would have reacted to Matheson's story? (Indeed, if that fan was a teenager—or even a few years older—in 1931, then 44 years later he would have been, at most, in his mid-60s and might well *have* read the novel.)

In the 2014 film *Interstellar*, a space probe dives into a black hole, gets a glimpse of the hole's singularity, measures some unspecified quantum effects, and then sends the measurements back to Earth (via the fifth dimension) as a signal in the form of spasmodic Morse code twitches of the second-hand on somebody's watch. This all leads (it is hinted) to a theory of quantum gravity. If you saw the second-hand on *your* watch suddenly begin to spasmodically twitch, would you then immediately think

(a) that a Morse code message was coming to you via the fifth dimension bearing the secrets of quantum gravity?

or

(b) that your watch needs a new battery?

(continued)

or

(c) something else?

Vigorously defend your answer.

William Grey, a philosopher at The University of Queensland, pointed out numerous conceptual difficulties with the idea of time travel in his paper “Troubles with Time Travel,” *Philosophy*, January 1999, pp. 55–70. That paper quickly prompted a rebuttal from the philosopher Phil Dowe (at the University of Tasmania), who replied a year later with the paper “The Case for Time Travel,” *Philosophy*, July 2000, pp. 441–451. We’ll eventually take up all the issues discussed in those two papers but, for now, read both papers and summarize their respective arguments. Do you feel one of the writers won the day (for you, anyway)?

Chapter 2
Philosophical Space and Time

> *"I do not believe that there are any longer any philosophical problems about Time; there is only the physical problem of determining the exact physical geometry of the four-dimensional continuum that we inhabit."*[1]

2.1 Time: What Is It, and Is It Real?

> "Time is generally thought to be one of the more mysterious ingredients of the Universe."[2]

Before going any further with time *travel*, it will be well worth the effort to take a closer look at time itself, the 'stuff' or 'thing' or . . . ? that we are interested in traveling 'through' or 'around' or 'across' or . . . ? Oddly enough, I'll start with religion, as philosophical theologians had identified time as something unusual long before Newton's words on time in his *Principia* that I mentioned in the Introduction, and many thousands of years before science fiction writers and their time travel stories.

We can, in fact, trace the religious interest in time back at least sixteen centuries to the Christian theologian St. Augustine and his *Confessions* (in which he famously admitted "What, then, is time? I know well enough what it is, provided that nobody asks me: but if I am asked what it is and try to explain, I am baffled."). Certainly the seventeenth century Spanish Jesuit Juan Eusebius Nieremberg caught the spirit of wonder that time holds for the devout when he wrote, in his *Of Temperance and Patience*, that "*Time* is a sacred thing; it flows from Heaven . . . It is an emanation from that place, where eternity springs . . . It is a *clue* cast down from Heaven to guide us . . . It has some assimilation to Divinity."

Going outside Christianity, we can easily find other equally strong reactions to the mystery of time. From Plutarch's *Platonic Questions* we learn that when the question of time's nature was put to Pythagoras, he simply uttered the mystical "time is the soul of the world." The *Laws of Manu* of Hinduism, the *Torah* of

---

[1] H. Putnam, "Time and Physical Geometry," *Journal of Philosophy*, April 1967, pp. 240–247.

[2] P. Horwich, *Asymmetries in Time*, MIT Press 1987.

© Springer International Publishing AG 2017

P.J. Nahin, *Time Machine Tales*, Science and Fiction,
DOI 10.1007/978-3-319-48864-6_2

Judaism, the *Koran* of Islam, and the revealed truths of Gautama Buddha are all full of references to time. It is, in fact, to the pagan gods of Greek mythology that we owe our ‘modern’ image of Chronos, or Father Time.

Not just the Greeks made time a god. In the *Bhagavad Gita* (*Song of the Lord*), the central religious-romantic epic of Hinduism that predates Christ by five centuries, one of the characters reveals his divine nature and declares his power thus: “Know that I am Time, that makes the worlds to perish, when ripe, and bring on them destruction.” And in the even older Egyptian Book of the Dead, which dates back over three thousand years, the newly deceased was thought literally to become one with time itself. The merging of time and the resurrection of the body after death in the Book is shown in the line “I am Yesterday, Today and Tomorrow, and I have the power to be born a second time.”

The Greek philosopher Plato (circa 400 B.C.) gave us a curious way to think of time: as a *closed loop*. While Plato did think of time as having a beginning, his conception did not have time extending off into the infinite future as does the modern, everyday view. Rather, Plato visualized time as curving back on itself—as *circular* in nature. This was, in fact, a reasonable reflection on what Plato could see everywhere in nature, with the seemingly endless repetition of the seasons, the regular ebb and surge of the tides (the old English word *tid* was a unit of time), the unvarying alternation of night and day, and the rotation of the visible planets in the sky. Whatever might be observed today, it seemed obvious to Plato, would happen again in nature. Circular time in science fiction was briefly mentioned in Chap. 1,[3] and it occurs outside that genre, too, as in James Joyce’s novel *Finnegans Wake*, which opens in mid-sentence and ends with the first part of the same sentence. This view of time has a powerful, ancient visual symbol, the Worm Ouroborous, or World Snake, that eats its own tail endlessly.

Circular time, with its closed topology, was favorably presented in Stephen Hawking’s famous book *A Brief History of Time*. In it he concludes that there is no need for God because in circular time there is no first event and hence no need for a First Cause. Vigorous philosophical rebuttals were quick to come, of course![4]

Turning to fiction, Ray Bradbury wrote a beautifully poetic passage about the mystery of time in “Night Meeting,” one of the splendid sub-stories in his episodic 1950 masterpiece *The Martian Chronicles*. A man of A.D. 2002, who is one of the modern inhabitants of Mars, somehow meets the ghostly image of a long-dead Martian one cold August night. The conditions are just right for such a cross-time encounter. As the man thinks to himself, “There is the smell of Time in the air tonight. . . . There was a thought. What did Time smell like? Like dust and people. And if you wondered what Time sounded like it sounded like water running in a dark cave and voices crying and dirt dropping down on hollow box lids, and rain. And, going further, what did Time *look* like? Time looked like snow dropping silently into a black room or it looked like a silent film in an ancient theater, one hundred billion faces falling like those New Year balloons, down and down into nothing. That was how Time smelled and looked and sounded. And tonight . . . tonight you could almost *touch* Time."

---

[3] Another example from science fiction is the story by I. Hobana, “Night Broadcast,” in which a television signal from the past is picked up by a gadget that is probing the *future*: “By going far enough into the future one comes upon what we call the past.” You can find this tale in the *Penguin World Omnibus of Science Fiction*, Penguin Books 1986.

[4] See, for example, W. L. Craig, “What Place, Then, for a Creator?: Hawking on God and Creation,” *British Journal for the Philosophy of Science*, December 1990, pp. 473–491, and R. Le Poidevin, “Creation in a Closed Universe Or, Have Physicists Disproved the Existence of God?,” *Religious Studies*, March 1991, pp. 39–48.

Well, lovely words, yes, but they don't really tell us what time *is*. Perhaps Einstein the physicist can tell us. In the *New York Times* of December 3, 1919, we find him quoted as follows: "Till now it was believed that time and space existed by themselves, even if there was nothing [Newton's view]—no Sun, no Earth, no stars—while now we know that time and space are not the vessel for the Universe, but could not exist at all if there were no contents, namely, no Sun, no Earth, and other celestial bodies." Less than 2 years later Einstein stated this view again (*New York Times*, April 4, 1921): "Up to this time the conceptions of time and space have been such that if everything in the Universe were taken away, if there were nothing left, there would still be left to man time and space." Einstein went on to deny this view of reality, saying that, according to his general theory of relativity, time and space would *cease to exist* if the universe were empty. This has the ring of one of Einstein's favorite philosophers, Spinoza, who declared in his *Principles of Cartesian Philosophy* that "there was no Time or Duration before Creation." In a correspondence with Samuel Clarke—Newton's friend who translated Newton's *Optiks* into Latin—the German philosopher Gottfried Leibniz (who began the correspondence in 1715) expressed similar ideas: "Instants, consider'd without the things, are nothing at all . . . they consist only in the successive order of things."

The pragmatic scientist would certainly agree with Leibniz. After all, what could it even mean to talk of time unless you can measure it? And what you use to measure time is a clock—some kind of changing configuration of matter involving spinning gears, ticking pendulums, and rotating dial pointers. Mere *unchanging* matter, alone, is not sufficient to measure time because a still clock measures nothing. *Changing* matter seems to be required. Yet, not surprisingly, not everybody agrees. The counterview, the view that time has nothing to do with change, was expressed in an interesting manner by a science fiction fan in a letter to the editor of *Wonder Stories* (January 1931): "Just one thing, you have these time-traveling yarns, good stuff to read all right, but bunk, you know; because if there's no such thing as time, which there isn't, *only change* [my emphasis], how can one travel in . . . something that doesn't exist. To our planet which goes around the Sun there is simply a turning and warming of one side and then the other, i.e., years, days, minutes, etc., is something purely artificial, invented by man to tell him when to do certain things, work and stop work . . ."[5]

---

[5] This fan's idea was not new. For Plato's most famous student, Aristotle, time was *motion* (in a world in which nothing moved, argued Aristotle, there would be no time), and he expressed this

Going even beyond the ideas of Einstein, Spinoza, Leibniz, Plato, Aristotle, and our science fiction fan, at least one metaphysician felt that time would have no meaning, even in a massive and changing universe, without the additional presence of conscious, rational beings.[6] That sounds very much like an echo of the French philosopher Henri Bergson who, in 1888, somewhat mysteriously declared that time is "nothing but the ghost of space haunting the reflective consciousness." A few years before Taylor, however, a fellow philosopher had argued for exactly the opposite view, that temporal passage is independent of the existence of conscious beings.[7]

All this divergence of opinion perhaps explains why even a lightweight Hollywood movie like Mel Brooks' 1987 *Spaceballs* can get a laugh from a time joke. Even kids know that the characters, when talking about time, haven't the slightest idea of *what* they are talking about. The movie, a spoof on such classic films as *Star Wars*, *The Wizard of Oz*, and *Raiders of the Lost Ark*, quickly reaches a point of crisis. To find out what to do next, the evil Lord Helmet and his chief henchman decide on a novel approach: they will look at an instant video of their own movie! (Instant videos are available *before* the movie is finished.) Perplexed at watching on a television screen everything that he is doing as he does it (the screen correctly shows an infinite regression of television screens, each being watched by a Lord Helmet), Lord Helmet initiates the following rapid-fire exchange. (It is, of course, a clever take-off on Abbott and Costello's "Who's on First?")

> *What the hell am I looking at? When does this happen in the movie?*
> *Now! You're looking at now, sir. Everything that happens now, is happening, now.*
> *What happened to then?*
> *We're past that.*
> *When?*
> *Just now, now.*
> *Go back to then.*
> *When?*
> *Now.*
> *Now?*
> *Now.*
> *I can't.*
> *Why?*
> *We missed it.*

---

view in his famous metaphor "Time is the moving image of eternity." For Aristotle, then, time and change were inseparably intertwined. For Aristotle the world had existed for eternity, and the circularity of time was a central and powerful image; using his vivid illustration, it is equally true *in circular time* that we live both before *and* after the Trojan War.

[6] R. Taylor, "Time and Life's Meaning," *Review of Metaphysics*, June 1987, pp. 675–686.

[7] S. McCall, "Objective Time Flow," *Philosophy of Science*, September 1976, pp. 337–362.

When?
Just now. [The henchman then sets the video to rewind.]
When will then be now?
Soon.

We may laugh at this, even dismiss it as mere movie madness, but could any of us *really* do much better if, like Saint Augustine, we were backed into a corner and asked to explain time? Somehow, I think even the distinguished twentieth-century Harvard professor Hilary Putnam whose words open this chapter would find it difficult to know where to begin. He might even become as confused as the time traveler in the 1968 film *Je t'aime, Je t'aime*, whose oscillations in time, from present to past and back again, leave him so befuddled that he decides he'd rather be dead. What, then, *can* we say about time? Despite Putnam's bold words, I suspect that most people would come down on the side of Augustine.

The mystery of time was well captured by R. H. Hutton (1826–1897), the literary editor of the *Spectator*, when he wrote in his 1895 review (see note 1 in the Introduction) of Wells' *Time Machine* that "the story is based on that rather favorite speculation of modern metaphysicians which supposes *time* to be at once the most important of the conditions of organic evolution, and the most misleading of subjective illusions ... and yet Time is so purely subjective a mode of thought, that a man of searching intellect is supposed to be able to devise the means of traveling in time as well as in space, and visiting, so as to be contemporary with, any age of the world, past or future, so as to become as it were a true 'pilgrim of eternity.'"

Novelist Israel Zangwill (1864–1926) wrote a similar but much more analytical review of Wells' novel for the *Pall Mall Magazine* (see note 1 in the Introduction). Zangwill was the only Victorian reviewer to attempt a scientific analysis of time travel. Although he thought Wells' effort was a "brilliant little romance," Zangwill also thought the time machine—"much like the magic carpet of *The Arabian Nights*"—was simply "an amusing fantasy." Zangwill continued in his review with what was even then a common idea about a way one might actually be able, at least in principle, to look backward in time; one could travel far out into space by going faster than light and then watch the light from the past as it catches up to you. (Note, carefully, that Zangwill was writing in 1895, 10 years before Einstein's special relativity put a limit on possible speeds.) In this way, Zangwill wrote, one could watch "the Whole Past of the Earth still playing itself out."

Indeed, even before Zangwill, the well-known French astronomer Camille Flammarion (1842–1925) had made this dramatic idea a centerpiece of his 1887 novel *Lumen*. That book, a best-seller in Europe even before its appearance in England, describes how a man just dead (in 1864) instantly finds his spirit on the star Capella, where he is able to watch the light then arriving from the Earth of 1793. In particular, he watches the French Revolution play itself out and sees himself as a child. Flammarion may have, in fact, been inspired to write his novel by an essay written several years earlier (in 1883) by the British physicist

J. H. Poynting (1852–1914). Poynting's essay,[8] which opens with the statement that it was, in turn, inspired by an anonymous pamphlet published "30 or 40 years ago" on the same topic, specifically mentions watching historical events from Capella.

By the beginning of the twentieth century the idea of watching the past by outrunning light had drifted down into juvenile literature, as in the 1904 novel *Around a Distant Star* by Jean Delaire (the pen name for Pauline Touchemoline (1868–1950)), in which a young man builds a spaceship that can travel at two thousand times the speed of light. With it, he and a friend travel to an Earth-like planet nineteen hundred light-years distant and use a super-telescope to watch the Crucifixion (and then the resurrection) of Jesus. Early magazine science fiction also found the idea of looking backward in time with delayed light to be an irresistible one, involving romance and murder.[9] In another tale incorporating human emotions, a scientist loses his wife to a rival who kidnaps her and then escapes in a faster-than-light rocket ship headed for parts unknown. After searching for them with his own brilliant invention of the 'ampliscope' (several quantum leaps beyond the telescope), the scientist locates the couple, skipping from planet to planet light-years distant. His only pleasure, then, is to use his own faster-than-light craft to outrun the images of his lost love and watch them over and over. Eventually, however, he comes to realize the ultimate futility of it all. As the final line of this sad tale says, "It would be senseless, I knew, chasing on and on after yesterdays."[10]

The reality of time received a new twist with the additional imagery of instants of time being likened to the points on a *straight* line. In the West it was the Christian theological doctrine of *unique* historical events that gave rise to *linear* time in the minds of the common folk. The creation of the world and Adam and Eve, the adventures of Noah and the cataclysmic Flood, the Resurrection—these were all events that occurred in sequence, *once*. None would happen again and so, for Christianity, circular time just would not do.[11] In addition, it has been argued that the major spiritual content of Christianity—a significant reason for its popular support even in the face of brutally harsh Roman suppression—is that it brought the *expectation of change* into the static world of ancient times. It was, in fact, in ancient religious teachings that our modern view of linear time had its origin, a view that most people today (including the most hardened agnostic physicist) find to be as natural as Plato and Aristotle found circular time.

---

[8] J. H. Poynting, "Overtaking the Rays of Light," in Poynting's *Collected Scientific Papers*, Cambridge University Press 1920.

[9] As in, for example, G. A. England, "The Time Reflector," *The Monthly Story Magazine*, September 1905.

[10] D. D. Sharp, "Faster Than Light," *Marvel Science Stories*, February 1939. The year before saw the appearance of a story with the same idea, a story that specifically cites Flammerion: M. Weisinger, "Time On My Hands," *Thrilling Wonder Stories*, June 1938.

[11] Still, just to show how one can find support for almost any view in the same religious dogma, Ecclesiastes 1:9 would seem to be a claim *not* for linear time but rather for circular time!: "The thing that hath been, it is that which shall be; and that which is done is that which shall be done; and there is no new thing under the sun."


Calvin and Hobbes
by Bill Watterson
Test:
1. What important event took place on December 16, 1773?
I do not believe in linear time. There is no past and future: all is one, and existence in the temporal sense is illusory. This question, therefore, is meaningless and impossible to answer.
When in doubt, deny all terms and definitions.

CALVIN AND HOBBES ©1994 Watterson. Reprinted with permission of UNIVERSAL PRESS SYNDICATE. All rights reserved.

Even though linear time was the norm after Christ, there were still enough questions about time to perplex the deepest of thinkers, and the next 2000 years resulted in plenty of thinking. Discourses on time by such philosophers as Descartes, Spinoza, Hobbes, Kant, Nietzsche, and Hegel can be found by the yard in any decent university library. Nearly all (if not indeed all) of these presentations have metaphysical, even theological, underpinnings. For example, Descartes is generally believed to have argued for a discontinuous, atomistic nature to time (recall the *chronon* from Chap. 1). This is the modern view of his thinking, because in his *Meditations* (1641), in particular in the third meditation on God's reality, Descartes appears to argue that God must continually recreate the world at each *separate* moment of its existence. That is, the world is recreated in a discontinuous succession of *individual* acts by God.[12]

Finally, with Newton's discussion of *absolute* time, which is the belief that time is the same everywhere in the universe, there was for the first time a *physicist* writing about time (although, as I mention in Chap. 1, Newton's views were also influenced *heavily* by theological considerations, in addition to mathematical physics). But, despite Newton's genius, the mystery of time remained a mystery.

In 1905 Einstein's name appeared among the contributors to the study of time, and so at last something besides metaphysical speculation on the subject was added to the body of human thought. Einstein's paper on special relativity introduced the revolutionary idea of *relative* time, which is the anti-Newton belief that the passage of time is *not* the same everywhere, but rather depends on local conditions. In retrospect, Einstein's 1905 work seems to be the perfect reply to the comment by Isaac Barrow (1630–1677)—Newton's teacher and the first Lucasian professor of mathematics at Cambridge (the chair once held by Stephen Hawking centuries later)—that "because *Mathematicians* frequently make use of Time, they ought to have a distinct idea of the meaning of the Word, otherwise they are Quacks."

---

[12] For more on this, see R. T. W. Arthur, "Continuous Creation, Continuous Time: A Refutation of the Alleged Discontinuity of Cartesian Time," *Journal of the History of Philosophy*, July 1988, pp. 349–375.

Then, just 3 years after Einstein, along came a second astonishing paper by the Cambridge philosopher John Ellis McTaggart (1866–1925). This paper[13] claims to prove that whatever time might be *thought* to be (even by Einstein), it really isn't that because time isn't even real. (This would seem, I think you'd agree, to have potentially profound implications for time travel!) The method of the paper is to deny the reality of time via an infinite-regress argument that one philosopher[14] has called the *pons asinorum* ("bridge of asses") of the riddle of time. As McTaggart's own opening sentence freely admits, "It doubtless seems highly paradoxical to assert that Time is unreal, and that all statements which involve its reality are erroneous."

McTaggart began his analysis by observing that there are two separate and distinct ways of talking about events in time. Following his terminology, one can say that events are either future, present, or past (the so-called *A-series*), or one can say that events temporally ordered by each being later than some other events, earlier than others, and simultaneous with still others (the so-called *B-series*). He then continued by asserting that time requires change, and followed that with the observation that the A-series (but not the B-series) incorporates such change. That is, if event X is earlier than event Y, then X is *always* earlier than Y and thus there is no change in this (or in any other) example of a B-series. As a specific example, let Y be the birth of a child, and let X be the birth of its mother. In contrast, if X is first in the future, then is in the present, and finally is in the past, then we have an example of change (and hence of *time*) in the A-series; for example, let X be the next time you blink.

With this rather pedestrian start, McTaggart then pulled his rabbit out of the hat. It makes no sense, he argued, to talk of the 'future,' 'present,' and 'past' of an event because these terms are mutually exclusive. That is, no two of these predicates can apply at once, and yet, paradoxically, every event possesses all three and thus we have a contradiction. It therefore, concludes McTaggart, makes no sense to talk of future, present, or past. And because it makes no sense to talk of them, they do not exist, and so there can be no A-series and hence no change, and thus no reality to time. McTaggart apparently realized just how befuddling all that would appear to just about everybody who read it, and so he played devil's advocate (D.A.) in his paper by trying to anticipate the various objections people could raise. Of course, he always managed to refute the D.A. at every turn. It is worth the effort to go through the details of McTaggart's 'proof,' as that will make it clear what there is about

---

[13] J. E. McTaggart, "The Unreality of Time," *Mind*, October 1908.

[14] L. O. Mink, "Time, McTaggart and Pickwickian Language," *Philosophical Quarterly*, July 1960, pp. 252–263. The phrase *pons asinorum* has its origin in a plane geometry theorem: the angles opposite the equal sides of an isosceles triangle are themselves equal. Seeing the truth of this is said to separate the quick-witted from the dull. It isn't clear (to me, anyway), however, on which side of McTaggart's 'proof' the quick-witted were imagined to fall. You'll see what I mean in just a moment.

'traditional' philosophical reasoning that so irritates modern philosophers trained in mathematical physics (and what makes physicists roll their eyes when confronted with arguments like McTaggart's).

The predicates of future, present, and past are really not incompatible for any event, the D.A. says some will claim, because the real predicates we should use are '*was* future,' '*is* present,' and '*will be* past,' and these *can* be possessed all at once by any event. Nice try, counters McTaggart, but that will not solve the problem. By allowing such modified predicates, we must actually allow for all nine possibilities, some of which are still incompatible. That is, the 'was,' 'is,' and 'will be' could each be potentially attached to 'future,' 'present,' and 'past': for example, 'was past' is incompatible with 'will be future.'

Oh, counters the D.A., we can eliminate that concern by allowing even more complex predicates to arrive at a third level of structure, such as 'is going to have been past,' and 'was going to be future,' and those *are* compatible. But McTaggart swats that argument away, too, by displaying new incompatibles, as well as by showing that the process of ever-increasing predicate complexity is a vicious infinite regress that drags along the seeds of its own doom at every step.[15] There is simply no escape from incompatibility, he says, and so there is no time.

Well! What can one do when presented with such an argument, one that seems to claim philosophers can wrest free the secrets of nature by pondering the historical accidents of English syntax? As David Hume once said, "Nothing is more usual than for philosophers to encroach on the province of grammarians, and to engage in disputes of words, while they imagine they are handling controversies of the deepest importance and concern." One modern philosopher apparently agreed with Hume, at least in the case of McTaggart's 'proof,' and he was pretty blunt with his evaluation of it: "McTaggart's famous argument for the unreality of time is so completely outrageous that it should long ago have been interred in decent obscurity. And indeed it would have been, were it not for the fact that so many philosophers are not sure that it has ever really been given a proper burial, and so from time to time someone digs it up all over again in order to pronounce it *really*

---

[15] Here's a clever way to systematically generate McTaggart's infinite regress of complex predicates, as presented by M. Dummett, "A Defense of McTaggart's Proof of the Unreality of Time," *Philosophical Review*, October 1969, pp. 497–504): "Let us call 'past,' 'present,' and 'future' 'predicates of first level.' If, as McTaggart suggests, we render 'was future' as 'future in the past,' and so forth, then we have nine predicates of second level, where we join any of the three on the left with any of the three on the right:

past		past
present	in the	present
future		future

Similarly, there are twenty-seven predicates of third level … "Dummett's construction clearly shows that, at the N-th level, there are 3^N predicates, most of which are incompatible.

dead. These periodic autopsies reveal that something more remains to be said."[16] That is certainly true, in as much as McTaggart's disarmingly innocent argument has caused disagreement and furrowed brows among philosophers for decades.

It is, in fact, easy to find examples of the continuing debate over McTaggart's analysis and, as silly as it strikes physicists, it still has a pulse in some quarters. While at least one philosopher has argued that McTaggart simply didn't really understand his own proof, this philosopher nevertheless agreed with McTaggart's conclusion about the unreality of time.[17] Another writer has illustrated how McTaggart's ideas have found their way into modern philosophical debates on the meaning of time in the cinema, particularly in the analysis of *anachrony*, the telling of a story out of normal time sequence, such as occurs in time travel movies.[18]

Other sorts of metaphysical proofs for the unreality of time have been offered besides McTaggart's. For example, it has be argued that time is unreal, at least in a world empty of consciousness, because the concepts of past, present, and future could not possibly have any meaning unless events could be remembered, experienced, and anticipated. Or, for a second example, some have held time to be unreal, at least in a deterministic world (as some argue four-dimensional spacetime to be), because any event whose occurrence follows from present conditions, and from physical laws, would exist (they say) *now*. This view, which seems to assert that everything should happen at once, I personally find to be sufficiently obtuse as not to be bothered by it.[19] Debates between those who believe in the common-sense idea that present, past, and future are attributes of events (the 'tensers') and those who deny it (the four-dimensional spacetime, block universe 'detensers') continues to now and then still flair up on the pages of philosophy journals. At least one philosopher likes both views![20] Most modern physicists, I think, simply don't care about this line of inquiry.

On the other hand, less than a month before his death Einstein revealed his feelings about the meaning of present, past, and future, and his words appear to be ones that show some sympathy to the philosophers. In a letter written on March 21, 1955, to the children of his dearest friend who had just died, Einstein wrote—with full knowledge that his own illness would be his last—"And now he has preceded me briefly in bidding farewell to this strange world. This signifies nothing. For us believing physicists, the distinction between past, present, and future is only an illusion, even if a stubborn one."[21] Later in this chapter I'll return to these curious words and speculate on what Einstein may have meant by them.

---

[16] F. Christensen, "McTaggart's Paradox and the Nature of Time," *Philosophical Quarterly*, October 1974, pp. 289–299.

[17] Q. Smith, "The Infinite Regress of Temporal Attributions," *Southern Journal of Philosophy*, Fall 1986, pp. 383–396. To this came a rebuttal a year later by L. N. Oaklander, in the same journal (Fall 1987, pp. 425–431).

[18] G. Currie, "McTaggart at the Movies," *Philosophy*, July 1992, pp. 343–355.

[19] But if, upon reflection, it starts to bother *you*, see R. Gale, "Some Metaphysical Statements About Time," *Journal of Philosophy*, April 1963, pp. 225–237. We'll soon get to some of the more common philosophical questions on the nature of four-dimensional spacetime, such as 'is it deterministic or is it fatalistic?,' and 'does free-will have any meaning in four-dimensional spacetime?' Even physicists are interested such questions!

[20] R. Weingard, "Space-Time and the Direction of Time," *Nous*, may 1977, pp. 119–131.

I started this opening section on a religious note, and I'll end it on one. If you think the philosophical speculations on the nature of time that I've so far cited are 'really far out,' here's yet another one that leaves all the rest in the dust. In a paper that took real nerve to write (or, perhaps, simply a wicked sense of humor—and I write that in pure admiration) we read of how a spacetime that supports time travel can give the start for a *physics* explanation to the theological concept of Hell! After introducing just a bit of elementary spacetime physics (which I'll skip describing here because we'll do it later in the book), the author[22] shows how to 'construct' a compact region in spacetime (Hell) with the following properties:

1. While "so small even the Hubble Telescope couldn't image it" it can hold an infinity of physical beings;
2. Each of the beings in it are doomed, because of its time travel property, to an infinitely long personal future of damnation;
3. Each of the beings in it, because of its time travel property, can view all the future stages of their own personal damnation and so be "continually presented with a reminder of the impossibility of escape—a refinement no causally normal Hell can seemingly offer." In other words, and not to be too ironic about it, 'Theological Progress Through Physics!';
4. Each of the beings in it are continually being compressed together ("brought into dismaying proximity" with themselves) and so will spend eternity "listening to a cacophony" of their own cries of despair from *their personal future*.

There's more, but that's probably enough for you to get the idea. Richmond does admit that, as it stands, his time travel creation of Hell is not compatible with either quantum theory or even general relativity. Still, it *is* something to ponder, don't you think, when the subject of time travel comes up!

2.2 Linear Time and the Infinity of Past and Future

> "A thousand years is a huge succession of yesterdays beyond our clear apprehension."[23]
>
> —H. G. Wells

---

[21] Quoted from B. Hoffmann, *Albert Einstein: Creator & Rebel*, New American Library 1972, pp. 257–258.

[22] Alasdair M. Richmond, "Hilbert's Inferno: Time Travel and the Damned," *Ratio*, September 2013, pp. 233–249.

[23] This line appears in Wells' 1944 doctoral thesis, written for the University of London. You can find an abridgement of the thesis in *Nature*, April 1, 1944, pp. 395–397.

The modern concept of linear time as a straight line extending from the dim past through the present and disappearing into the misty future gives rise immediately to twin questions: "Did time have a beginning?" and "Will time ever end?" As one philosopher put it (long before physicists became seriously interested in singularities like the Big Bang) "Endings and beginnings are rooted in the very conception of time itself."[24] Starting at the beginning, we'll ask if the past has been forever? Early Biblical scholars, of course, believed the answers to both questions to be *no*.

They believed that the world came into being because of a First Cause, God's creation of everything. Those scholars expended vast quantities of energy (and, need I say it, time itself) in calculating the date of creation. Martin Luther, for example, argued for 4000 B.C. as roughly when everything, including time, began. Johannes Kepler adjusted this by a notch, to 4004 B.C., and later the Calvinist James Ussher, Archbishop of Armagh and Primate of All Ireland, tweaked it again. His date is the most impressive of all, at least in detail: the first day of the world was 4003, 70 days, and 6 h before the midnight that started the first day of the Christian era. Six days after that first day of the world, Adam was made, and as a final dash of specificity, this last date was declared to be Friday, October 28! Ironically, then, though Christian theology may be given credit for introducing linear time, it certainly did not provide very much of it. The beginning of time was just 6000 years or so ago, and of course The End—in the form of the Battle of Armageddon—has been awaited (with varying degrees of eagerness) for the last 1000 years.

The discovery in the seventeenth century of geological time cast a certain amount of skepticism on those early calculations concerning the duration of the past. With the discovery that the very Earth itself could be decoded for its history, the lure of trying to decode a mere book of admittedly finite age declined for most people although it cannot be denied that modern Creationists still find such a task to have its rewards). Geological time was discovered to a *chasm* of time extending backward for billions of years, a duration that is really incomprehensible for the human brain. It has become fashionable for geologists to refer to such enormous durations with the apt term *deep time*, a subtle play on the metaphor of the "ocean of time."

It is nothing less than humbling to historians who pause to think on how little of the past is known, that is, recorded. As the ever anonymous wit once put it, "History is a damn dim candle over a damn dark abyss." Still, even as enormous as is the age of the Earth, it is not infinite. But of course our planet is very old, and the universe is many billions of years older. Is the age of the universe also the duration of the past? Or is the past itself actually *infinite*?

An implicit assumption of the infinity of the past (and of the future, too) can be found in Book Three of Lucretius' science poem *De Rerum Natura* (*On the Nature of Things*) where, just before the birth of Christ, Lucretius argues for the irrationality of fearing death: "The bygone antiquity of everlasting time before our birth was nothing to us. Nature holds this up to us as a mirror of the time yet to come after our death. Is there anything in this that looks appalling, anything that means an aspect of gloom? Is it not more untroubled than any sleep?"

---

[24] I. Stearns, "Time and the Timeless," *Review of Metaphysics*, December 1950, pp. 187–200.

One philosopher[25] has traced the origins of rational support for the finite duration of the past to as far back as the sixth century A.D. The argument presented then by the Christian philosopher Joannes Philoponus of Alexandria (who is otherwise known as John the Grammarian) is simply that the world could *not* have been forever because that implies an infinity of successive acts could have taken place which (according to Philoponus) is impossible. A variation on this is the claim that if the past were infinite in extent, then everything would have happened by now! Infinity was just too big for the ancient mind (Zeno's hoary pre-Christian paradoxes, as is well-known today, are based on subtle errors in the use of infinity).

This view on the impossibility of an infinite past seems to have been the prevalent view; even as late as the twelfth century the debate among Christian theologians was not about the possibility of an infinite past, but instead about whether the Biblical 'six days of Creation' actually had taken place simultaneously. For many, the past was 'obviously' finite in duration.[26] Not all Christians accepted that conclusion, however, and the following century saw St. Thomas Aquinas (a follower of Aristotle) arguing for the opposite view of an infinite past.

Thomas' contemporary, St. Bonaventure, however, argued again for a *finite* past, and it is with Bonaventure that we start to see some mathematical sophistication.[27] Bonaventure argued that in a world infinitely old, the Sun would have made an infinite number of its annual trips around the ecliptic. But for each such trip the Moon would have made twelve monthly trips around the Earth, and so this second infinity would be twelve times as great as the first one, and how could that be? Infinity is infinity, and how can something be twelve times bigger than infinity? This argument doesn't have any strength today because of the nineteenth century German mathematician Georg Cantor's work on the concept of infinity,[28] but it *is* clever. Agonized, convoluted theological analyses of God, infinity, and eternity continued long after Aquinas and Bonaventure. Two examples should capture the spirit of those times.

---

[25] G. J. Whitrow, "On the Impossibility of an Infinite Past," *British Journal for the Philosophy of Science*, March 1978, pp. 39–45. Whitrow adds modern scientific support to the idea of a finite past by citing the prediction from general relativity of a singularity in spacetime at some finite past time; that is, the theory's prediction that time—and everything else—had its beginning in the now famous Big Bang.

[26] C. Gross, "Twelfth-Century Concepts of Time: Three Reinterpretations of Augustine's Doctrine of Creation *Simul*," *Journal of the History of Philosophy*, July 1985, pp. 325–338.

[27] See, for example, L. Sweeney, "Bonaventure and Aquinas on the Divine Being as Infinite," *Southwestern Journal of Philosophy*, Summer 1974, pp. 71–91, and S. Baldner, "St. Bonaventure on the Temporal Beginning of the World," *New Scholasticism*, Spring 1989, pp. 206–228.

[28] For simple high school-level presentations on Cantor's astonishing infinity results, see my book *The Logician and the Engineer*, Princeton 2013, pp. 169–171.

Consider first this one, on the supposed immortality of the soul. If $A = B$, then $2A = 2B$. Next, let A = 'half alive' and B = 'half dead,' where $A = B$ in the same sense that a glass half-full is also half-empty. Thus, to be completely dead is to be completely alive, and so the soul is immortal. Outrageous? *Yes*, in my opinion, but I do also have to admit the 'reasoning' does have a certain charm!

For my second example, let me begin by setting the historical stage. After publication of the English political philosopher Thomas Hobbes' *Leviathan* in 1651, with its arguments against the power of the Church and for civil power (with some criticism tossed in, as well, for universities), Seth Ward counterattacked. Ward, who was both a minister (later a bishop) in the Anglican Church and Savilian Professor of Astronomy at Oxford, was greatly offended by the secular nature of *Leviathan*. Even before Leviathan, in fact, Ward certainly would not have liked Hobbes' earlier denial of the existence of immaterial substances (such as souls). Ward's 1652 book *A Philosophical Essay Towards An Eviction of the Being and Attributes of God, the Immortality of the Souls of Men, the Truth and Authority of Scripture*, was the first of a two-punch reply to Hobbes. The second came in 1654 with the appearance of Ward's *Vindiciae academiarum*. In both of these works Ward attempted to undermine Hobbes' credibility by attacking his mathematical ability. (Hobbes had long been fascinated by, and was considered an expert on, the ancient problem of 'squaring the circle,' a task that has been known to be impossible only since 1882.[29]) In his *Essay*, Ward also attempted to defend the view that the world has a finite age—that is, it had a specific moment of creation, presumably by God. In an opening note, in fact, Ward cites Hobbes' rejection of immaterial substances as the motivation for his writing *Essay*.

To support his view of a finite age for the world, Ward invoked infinity in an interesting way. He argued that nothing is permanent, certainly not humans. Each is created; one can imagine tracing a chain of creation events backward in time through successive generations. Now, there are only two separate and distinct possibilities to where this chain could lead to in the past. First, it could terminate, after a finite number of generations, at a *first* generation, that is, with the 'creation' of the first human. If that is the case, then, said Ward (in effect), 'case closed.' If that is not the case, however, then the chain of successive generations never terminates, that is, the chain is infinitely long. But that, argued Ward, is nonsense—how could anything *infinitely* long have an end (our present *now*)?

Why Ward thought this an unanswerable paradox is hard to understand; after all, one can imagine a line in some coordinate system *beginning* at the origin and yet still being infinitely long (an example is the positive x-axis). This counter-example was not put forth by Hobbes in his own self-defense, but rather was offered by one of Ward's own colleagues at Oxford, John Wallis, the Savilian Professor of Geometry. As for Hobbes, he was little bothered by Ward's argument. As he pointed out (surely with a smile on his face), Ward was in danger of impaling himself as a theologian on his own sword: Ward's argument 'proved' the finite age not only of the world but of *everything*, including God (thus raising the awkward question of who, or what, made God?).

---

[29] The problem of 'squaring the circle' is, given a circle of area A, to construct (using only compass and straightedge) a square of area A.

Similar problems with infinity lay behind Kant's rejection of an infinite past. It is interesting to note that Kant, somewhat paradoxically, thought an infinite *future* a possibility. Why did Kant think time could be infinite in one direction but not in the other? One philosopher tells us[30] that Kant "failed to make himself clear," and I think that *understates* the case. I say that because Kant's argument was that the duration of the future is less problematic than is that of the past because it is only the past that influences the present. The best I can do in 'explaining' this is to speculate that if the present depends on an *infinite* past, then perhaps Kant thought that the possibility of so much influence was simply too much for the present to handle! In any case, Kant's view falls apart if we consider the possibility of backward time travel and the resulting implication that the future could also influence the present.

There is, as will come as no surprise, a philosopher for every conceivable point of the compass, and so a paper by one on the logical possibility of an infinite past soon prompts a rebuttal by another.[31] In illustration of this, you'll recall the quote from Augustus De Morgan in the opening section of this book, concerning the philosophers of his times; De Morgan went on in his critique to amusingly summarize the metaphysics of those times as follows: "Here we go up, up, up,/And there we go down, down, down,/Here we go backwards and forwards/And there we go round, round, round."

So, with De Morgan's words in mind, here are a few more examples of how people have struggled with the issue of the past. One quite interesting, *scientific* twist on the duration of the past was pointed out before the exchange between Smith and Ells. In a paper[32] observing that although general relativity and its predicted spacetime singularity in the distant past may indeed allow for a finite past, that does not completely close the door to the possibility that the Big Bang was a continuation from a previous contraction phase of the universe, and so on, *ad infinitum*. (You'll recall the discussion in Chap. 1 of this idea in science fiction: see note 53 in that chapter.) To quote T. S. Eliot (from his "Little Gidding"):

---

[30] J. Bennett, "The Age and the Size of the World," *Synthese*, August 1971, pp. 127–146. See also Q. Smith, "Kant and the Beginning of Time," *New Scholasticism*, Summer 1985, pp. 339–346.

[31] See, for example, Q. Smith, "Infinity and the Past," *Philosophy of Science*, March 1987, pp. 63–75, and then read E. Ells, "Quentin Smith on the Infinity of the Past," *Philosophy of Science*, March 1988, pp. 453–455. Smith's paper "The Uncaused Beginning of the Universe" appeared in this same issue (pp. 39–57), stating that he believed, *really*, only in the *logical* possibility of an infinite past and that the universe had in fact originated in an uncaused (no God required) Big Bang singularity. And, indeed, he *had* so argued for a finite past, in "On the Beginning of Time," *Nous*, December 1985, pp. 579–584.

[32] R. Weingard, "General Relativity and the Length of the Past," *British Journal for the Philosophy of Science*, June 1979, pp. 170–172.

"What we call the beginning is often the end
And to make an end is to make a beginning.
The end is where we start from."

Even without entertaining such an oscillating, accordion-like universe that endlessly expands and shrinks, it is possible to have a universe that originated in a *single* Big Bang a finite time ago in the past but yet *has no first instant*! This astonishing statement shocks most at first encounter, but it is simply the cosmological version of a well-known mathematical result. The instant $t = 0$ is not actually part of spacetime, because the Big Bang was quite literally a singular event for which the laws of spacetime physics fail. Thus, all instants in time are greater than zero—and there is no smallest number greater than zero. If you name a positive number, no matter how small, I can name a positive number still smaller, such as one-half of yours. (Of course, if there really is merit to the idea of a quantum of time, the chronon, this argument goes out the window.)

In an ingenious observation that seems to have been missed by most philosophers, E. A. Milne, a professor of mathematics at Oxford, suggested in his 1948 book *Kinematic Relativity*, that with general relativity it is conceivable to have both a single Big Bang a finite time ago *and* an infinite past. Pointing out that to talk meaningfully of time implies that we have a clock to measure it by, Milne looked for a Universal Clock that would be far more durable than our heartbeats, or anything else that exists only transiently. He suggested the expansion rate of the universe itself as the ideal clock. As we go back in time to the Big Bang, the expansion rate rises towards infinity and, as another analyst put it, "We see the Universe ticking away quite actively. *The Universe is meaningfully infinitely old because infinitely many things have happened since the beginning*."[33]

The debate over the length of the past in modern times can be just as contentious as it was in medieval times. For example, in his editorial ("Down with the Big Bang") of August 10, 1989, the then editor of *Nature* (John Maddox) declared the standard explosive model of the universe to be "philosophically unacceptable," because "the implication is that there was one instant at which time literally began and so, by extension, an instant before which there was no time." For Maddox, this meant that the Big Bang "is an *effect* [my emphasis] whose *cause* [my emphasis] cannot be identified or even discussed." The usual (non-time travel) use of the words *cause* and *effect* is that the cause happens first and then the effect occurs—but if the Big Bang (the effect) is the origin of time, then how (asked Maddox) could there be a cause of the Big Bang *before* that beginning?[34]

---

[33] C. W. Misner, "Absolute Zero of Time," *Physical Review*, October 1969, pp. 1328–1333. In this view cosmic time is taken as proportional to the negative of the logarithm of the normalized volume of the universe ($V = 1$ represents maximum volume, and so time 'stops' at the end of the universe's expansion). Thus, because V goes to zero as we go backward in time, time runs ever faster as we travel ever further into the past. This puts the Big Bang (with $V = 0$) infinitely long ago.

[34] This was not a new insight, of course, as Aristotle had long ago (in his *Physics*) declared an instant in time with no predecessor to be an absurdity.

The answer is obvious *for creationists*, of course—God did it. Creationists avoid the question of God's cause, however, saying only that 'He needs no cause,' or even that 'He made Himself'! It is these standard (ridiculous) responses from creationists that Maddox said had prompted his editorial against the Big Bang, because creationists *embrace* the Big Bang as it seems to endorse their position of 'science by imagination.' Whatever the truth of that, I think juxtapositioning the *scientific* Big Bang model of the universe with theological metaphysics and the pseudo-science nonsense of creationism to be terribly unfair.

When will the philosophical debates on the age of the past end? Not until the end of the (infinite?) future, is my wager!

2.3 Cause and Effect

> "There are few paradoxes which have been resolved so often as the time-asymmetry paradox."[35]

The philosophical literature is full of discussions about potential causal relationships between events. One of the most famous of these discussions, illustrating that cause and effect can be pretty slippery concepts, asks what at first appears to be an almost trivial question: Did the death of Socrates cause the widowhood of Xanthippe? The quick and easy answer is "Of *course*—she was his wife and it was his death that causes us to say she was then a widow. What could be more obvious?" One philosopher has provided some interesting commentary, however, that might make you reconsider, or to at least become aware of how different are the questions concerning time that are of interest to physicists and philosophers.[36]

Suppose we agree that there are two events to be considered; Socrates ceasing to live, and Xanthippe becoming a widow. Those events occurred at different places (in prison, and wherever Xanthippe happened to be). Then, as Kim asserted, "the two events occur with absolute simultaneity ... [and so] we would have to accept this case as one in which causal action is propagated instantaneously through spatial space." (As we'll discuss in Chap. 3, the *relativity* of distant simultaneity weakens this assertion, but we'll take that up later.) For now, it is the conclusion that Kim draws from the assertion that interests us here: just *what* is propagating instantly? If it isn't mass-energy (as 'widowhood' would appear not to be!) then special relativity isn't bothered and physicists are happy. But those same physicists might also scratch their heads over *why* philosophers even wonder about such a question, because isn't becoming a widow just another way of saying that Socrates died and so we really don't have *two* events, but just one? In other words, for physicists this really isn't a question about cause and effect at all!

---

[35] J. Hurley, "The Time-Asymmetry Paradox," *American Journal of Physics*, January 1986, pp. 25–28.

[36] J. Kim, "Noncausal Connections," *Nous*, March 1974, pp. 41–52.

The central puzzle of time travel to the past is its apparent denial of causality—that is, its denial of the belief that we live in a world where every effect has a cause and that the cause happens first. *First* we flip the switch and *then* the kitchen light comes on. It is *never* the other way around. So deeply embedded is the temporal ordering of cause and effect in our feelings about how the world—and all the rest of the cosmos—works, that the Australian philosopher John Mackie (1917–1981) called causation the "cement of the universe" (and used that wonderful phrase as the title of a 1980 book). Without causality, said Mackie, everything would come unglued and fall apart. For example, when electrical engineers design an electronic system that they intend to actually construct (as opposed to doing a mere theoretical 'paper design') they insist that the design be a *causal* one. By that they mean the system must have no output before an input is applied. That is, the system must not be able to anticipate (foresee) the application of an input. To put it bluntly, our engineers are insisting that they are *not* building a time machine!

Now all that might seem to be self-evident, but there *are* some subtle problems. For example, it has become almost a cliché to say that nothing can go faster than light; that's what physicists mean by *relativistic causality*. In other words, no cause can produce an effect at a distant location sooner than the time lapse required for a light pulse to make the trip. Classical mechanics, however, the science of Newton's laws that engineers use all the time, is *not* relativistically causal. Push the left end of a rigid rod, for example, and the right end moves *instantly*. Most of the time the lack of this form of causality causes no problems, but the fact remains that the mechanics all engineers (and physicists, too!) learn first in school is flawed on a fundamental level. A rigid rod is an impossibility in Einstein's mechanics.

Indeed, it is interesting to speculate about how, after a discussion of causality, a traditional engineering professor would respond if challenged on this issue by a bright student. Causality might not look so obvious, after all, if such a student stuck up her hand in class and said "Professor, you've told us that everything that happens in nature is due to a cause. That what we see happening all around us, as the world unfolds, is the domino-process of cause-effect-cause-effect, and so on, into the future. But suppose, Professor, that at some instant, somehow, every particle in the world suddenly reversed its velocity vector. Wouldn't that mean, given the time-reversible nature of the classical equations of motion, the world would then run backward in time along the same path it had followed up until the instant of reversal? Wouldn't that mean what was effect is now cause, and that what was cause is now effect? And if cause and effect can change roles like that . . . well, Professor, just what do our words *mean*?"

An amusing, and instructive, cartoon illustration of the student's idea of reversing all the velocity vectors in a system appeared on the cover of the November 1953 issue of *Physics Today*. That issue contains an article on the 1949 nuclear magnetic resonance experiments performed by the American physicist Erwin Hahn, which in a certain sense dealt with just such reversed systems. In that illustration a group of runners on a multi-lane circular race track begin at the starting line in a coherent state, that is, all lined up together. Then, as they run around the track at various speeds, they gradually spread out into what appears to be an incoherent state.

But that incoherence is an illusion because if, at some instant (signaled in the cartoon by a pistol shot), they all turn around and run in reverse, they will all arrive back at the starting line *together, at the same instant*. The initial coherence of the runners was actually never lost, despite the superficial appearance of disorder, and the coherent state can be recovered at any time by a reversal of velocity vectors.

This isn't mere theoretical speculation, as an almost magical application of velocity vector reversal is actually used in what is called *optical phase conjugation*, a process to 'time-reverse' the severe distortion suffered by light beams during atmospheric propagation. For example, by effectively reversing the velocity vectors of photons, one can remove the turbulence blurring in satellite pictures of the Earth's surface as seen from space.[37]

Let me immediately short-circuit one possible answer our beleaguered professor might give in desperation, a response based on the fact that equations of physics are *not* all time reversible. Indeed, it was discovered decades ago that, in certain very rare, fundamental particle decay processes involving neutral K-mesons, there is the hint that perhaps nature *can* indeed distinguish between the past and the future. In particular, K-mesons should violate what is called *CP-symmetry*, and the so-called TCP theorem[38] says that then *T-symmetry* must also fail. In 1968/69 direct, experimental observation of the failure of T-symmetry in K-meson decays was reported. In an astonishing example of science fiction prescience, the use of K-mesons in a machine for affecting the past had appeared years earlier in a 1955 (!) story.[39]

So, could K-mesons account for the physical processes that we see evolve in time in one direction (past to future) but not in the other? As Hurley (note 35) put it so nicely, "The decay of the neutral K-meson is not time-reversal invariant; perhaps it is this ubiquitous meson which is responsible for the cream diffusing uniformly throughout our coffee in the morning. Possibly, but again this conjecture cannot account for the computer models [of diffusion processes that, like cream in coffee, also display a bias for one temporal direction over the other—in Chap. 3 I'll show you such a computer model] which have no neutral K-mesons." Still, the tiny chink that K-mesons appear to have made in the once-solid rock of time direction indistinguishability is an active area of research and speculation.

Even with that chink the fact that the classical laws appear to be insensitive to a direction of time, whereas the real world—which seems in no way dependent on the arcane properties of K-mesons—seems distinctly asymmetric, is a puzzle of the first rank. As one philosopher wrote, "The Universe seems asymmetric with respect to the past and future in a very deep and non-accidental way, and yet all the laws of nature are purely time symmetric. So where can the asymmetry come from?"[40]

---

[37] C. R. Giuliano, "Applications of Optical Phase Conjugation," *Physics Today*, April 1981, pp. 27–35.

[38] The TCP-theorem says that the 'mirror-image' of a physical process is a legitimate process, too, *if* the 'mirror' reverses time (T), electric charge (C)—so that particle and anti-particle are interchanged, and parity (P)—which is the measure of left and right. There is strong reason to believe in the validity of the TCP theorem because quantum field theory is compatible with special relativity only if the TCP theorem holds.

[39] F. Pohl, "Target One," *Galaxy Science Fiction*, April 1955.

There have of course been attempts to answer that question. For example, one philosopher[41] discusses some curious mathematical examples he interprets as meaning, in the context of classical mechanics, that there are physical systems that are temporally irreversible *in principle*. A reply[42] from a fellow philosopher, however, argues that Hutchinson has, at most, shown only that classical mechanics is perhaps not deterministic. And that, Savitt argues, is not equivalent to showing a failure of time reversibility. There is, in fact, powerful experimental evidence that, with the rare exceptions of K-mesons, the classical laws of physics (including general relativity and quantum mechanics) *are* time-reversible.

Perhaps the most compelling of such evidence comes from the *reciprocity theorem* that electrical engineers routinely use when designing radio antennas. The theorem is easy to illustrate. Suppose two electrical engineers, Bob in Boston and Lois in Los Angeles, send radio signals to each other. Bob sends his messages by exciting his antenna with a time-varying current, which thus launches electromagnetic radiation into space. Lois' distant antenna intercepts some of that radiation, which then creates a (very tiny) signal current in her antenna.

The reciprocity theorem states the following: Suppose Bob makes a tape recording of his excitation signal and mails it to Lois, who then plays Bob's tape back into her transmitter as the excitation to *her* antenna. Then the signal current induced in Bob's antenna, as it intercepts Lois' launched radiation, will be the very same (very tiny) signal that Lois measured in her antenna as a result of Bob's transmission. This result is completely independent of the details of the two antennas, which can be utterly different in design, as well as independent of the details of the propagation path between Boston and Los Angeles (as long as those details don't change with time). The reciprocity theorem *is* true—it can be *measured* to be true as accurately as one wishes to perform this experiment—because of the reversibility of physics right down to the electronic level. In fact, the answer to the professor's problem of explaining why we don't see velocity vectors suddenly reverse, and then everything 'run backwards,' has not yet been found in any law of physics.

Now, to make things even more interesting, consider the problem of *mutual* or *simultaneous* causation, which can quickly lead to several interesting questions. When two leaning dominoes, A and B, hold each other up, is A nearly upright because of B, or is it B that is nearly upright because of A? When two children bob up and down on a see-saw, whose motion is the cause and whose is the effect? There are other puzzles, too, that involve mutual causation.

---

[40] J. Earman, "The Anisotropy of Time," *Australasian Journal of Philosophy*, December 1969, pp. 273–295.

[41] K. Hutchinson, "Is Classical Mechanics Really Time-Reversible and Deterministic?" *British Journal for the Philosophy of Science*, June 1993, pp. 307–323.

[42] S. F. Savitt, "Is Classical Mechanics Time-Reversal Invariant?" *British Journal for the Philosophy of Science*, September 1994, pp. 907–913.

For example, causation is usually thought to be transitive: if A causes B, and if B causes C, then A causes C. But if A and B are mutually causative, then 'A causes B' coupled with 'B causes A' leads to 'A causes A' (and to 'B causes B'). That is, mutual causation, together with transitivity, seems to imply *self*-causation! Except for those theologians who like this sort of result (it lets them answer the question 'Who made God?' with 'He made Himself'), hardly anyone likes self-causation. But how do we avoid the conclusion that perhaps the mutual causation of two leaning dominoes, coupled with transitivity, represents experimental proof that God could have made himself? Well, of course this is certainly outrageous stuff, but don't you wonder how our poor professor would respond if asked?

This last example is actually a far more esoteric one than we need to illustrate how our ordinary, everyday concept of cause and effect can be turned inside out by going only a little bit beyond the routine. Consider, for example, the problem of the data processing of recorded time signals, such as the information written onto magnetic tapes, hard drives, or disks. Typical applications that produce such recordings include the strata-probing seismic echoes from dynamite explosions set by oil exploration geologists; arms control compliance monitoring stations that listen for the acoustic rumbles generated by both earthquakes and underground nuclear tests—and then try to tell one from the other; and the gathering by various military intelligence agencies of turbine shaft/propeller noise signatures emitted by different types of submarines. In each of those situations, the raw information is recorded and then later processed with a certain degree of unhurried calm and leisure. That pool of oil, after all, has been underground for several hundred million years, and waiting a few more days or weeks for a computer analysis of the explosion echo isn't going to make much difference.

Such after-the-fact processing of recorded data is said to be done 'off-line, in non-real time.' When we play a disk back in the lab, however, we can do all sorts of neat things, like speed up the playback (make time 'run fast'), or slow it down (make time 'run slow'), or even play it *backwards* (make time 'run in reverse'). For various technical reasons, generically called *spectrum shifting*, such tricks are often quite useful. Now, the way we retrieve magnetically recorded information from (for example) a magnetic tape, is to run it through a playback machine with a 'read-head' that senses the magnetic flux variations. The electrical signal produced by the read-head is just like the original signal and, in fact, we can pretend we don't know it is really coming off a tape, but rather that it *is* the original signal. For high-quality digitally recorded tapes and disks, in fact, it is virtually impossible to distinguish the original from a playback.

Now, suppose we construct our playback machine with *two* read-heads, with the new head sensing the recording slightly *before* the old head does. The two heads produce the same electric signal, of course, but the signal from the new head is *ahead* in time compared to the signal from the old head. The new head is, in a certain sense, 'seeing the future' of the old head! We can use these two signals, the old head representing 'now' time and the new head representing 'future' time, to build real systems that are *not* causal. The causality violation occurs in non-real time, of course, not *our* time, but no matter; some absolutely astonishing signal processing can be achieved this way. The universe is about fifteen billion years old, and pretending that time has shifted a few milliseconds or so doesn't seem to be too much violence to reality.

Two heads are often used on radio call-in talk shows to catch inappropriate remarks from intemperate callers and prevent them from being broadcast. A short time delay is introduced by first recording remarks 'live' on tape with a write head and, then a few seconds 'up-stream,' a read head regenerates the remarks for broadcast. A 5 s delay is generally sufficient, so what is heard on a radio receiver *now* actually occurred 5 s ago in the *past*. A caller can get terribly confused if she doesn't turn her own receiver off, because one ear hears the present on the telephone while the other ear listens to the past over the radio.[43] The 1956 British film *Timeslip* incorporates a similar situation, with an atomic scientist's perception advanced 7 s into the future as the result of an accidental radiation exposure. His resulting confusion and disorientation is the center of the film.[44]

2.4 Backward Causation

> "Causation as a topic of philosophical discussion refuses to die. Each year, books and articles on causation continue to pour forth. Of course, all this activity may simply be a symptom of the necrophilia that infests so much of philosophy."[45]

All of the previous discussion has fueled countless arguments about what is called *backward*, *reverse*, or even *retro* causation. What is generally meant by forward causation is, of course, that any event that occurs at time t is caused by events that all occurred at some earlier time(s). Backward causation says that at least one of the causing events occurs after time t—this should make it clear that backward causation is a close relative of time travel. Indeed, one philosopher uses the terms *time traveler* and *retro-causal engineer* interchangeably.[46] The topic, understandably, is at the root of many hot philosophical debates, though not everybody (as this section's opening quote makes clear) thinks those debates are illuminating.

Just *why* does Professor Earman take his harsh position? He offers, as one reason, his disdain for the common philosophical 'proof' of the impossibility of backward causation: By definition, a cause is always before its effect. Yes, that's the entire 'proof.' One can, of course, win *any* argument by *defining* the answer to be what it is you wish to believe. More interesting, and certainly more pertinent to time travel, is the argument that if backward causation were possible then one could change the past—but that cannot be done because the past is dead and gone and thus unchangeable. That does seem to be a pretty solid argument against backward causation,[47] but Earman rebuts it by pointing out that the very same logic could be applied to the future, and so the usual, uncontested forward causation would also be denied. That is, one could argue that whatever the future will be, *will be* (literally 'by definition'), so one cannot change the future. A similar argument was presented even earlier,[48] in which we find "suppose that someone says 'I can change the future. I can do *this* or I can do *that*.' Well, then, suppose that he does *that*. Has he changed the future? No, because doing *that* was the future."

---

[43] A science fiction use of this idea is in B. W. Aldiss, "Man In His Time," *Science Fantasy*, April 1965, the story of an astronaut who returns from a trip to Mars and finds himself 3.3077 min ahead of everybody else.

[44] Science fiction had used a twist on this idea long before the film; see E. Binder, "The Man Who Saw Too Late," *Fantastic Adventures*, September 1939, a tale of what it might be like to have a 3 min *delay* in your vision.

[45] J. Earman, "Causation: A Matter of Life and Death," *Journal of Philosophy*, January 1976, pp. 5–25.

[46] B. Brown, "Defending Backwards Causation," *Canadian Journal of Philosophy*, December 1992, pp. 429–443.

The reversal of the 'usual' causal order of events by backward time travel has been a mainstay of science fiction almost from the start of the genre. Consider, for example, this tale.[49] A man on vacation by himself, without his wife along, meets a young lady—and they fall in love. The man loves his wife, too, though, and he realizes (as the young lady leaves him for the last time), never to return, that it is all for the best. But she really hasn't gone that far away from him, as the reader soon discovers. She is a time traveler from the future, and after leaving him she goes even further back in time, back an additional 20 years. She does this because she has learned that he met his wife 20 years ago, and so she goes back to be *that* woman! Thus, the usual causal order of the two events 'a long marriage' and the 'pre-marriage courtship' has been reversed (if we accept the fact that the man doesn't remember what his wife looked like when they married).

Actually, even our everyday uses of cause and effect are not nearly so straightforward as one might think, even when they are under far less stress than backward causation and time travel inflict. Consider, for example, the endless problems that are easy to imagine in the legal world. If a man falls off the roof of a ten-story building and is electrocuted as he plunges through power lines while still twenty feet above ground, was gravity or electricity the cause of death? Or was it both? As this example and others demonstrate,[50] one clearly does not have to discuss time travel to get into a serious argument about cause and effect. But with time travel, and the resultant backward causation, things can become even more perplexing. For example, we normally think it foolish to prepare, now, for an event that has already happened, but the prudent time traveler about to visit an ice age in the distant past would be wise to pack a fur coat before getting into his time machine!

---

[47] See, for example, D. H. Mellor, "Fixed Past, Unfixed Future," in *Michael Dummett: Contributions to Philosophy* (B. M. Taylor, editor), Martinus Nijhoff 1987.

[48] J. J. C. Smart, "A Review of *The Direction of Time*," *Philosophical Quarterly*, January 1958, pp. 72–77.

[49] R. F. Young, "The Dandelion Girl," *The Saturday Evening Post*, April 1, 1961.

[50] See also P. Mackie, "Causing, Delaying, and Hastening: Do Rains Cause Fires?" *Mind*, July 1992, pp. 483–500.

One philosopher provides, I think, a good start at explaining why so many other philosophers (and not just a few physicists) have adopted the ‘common sense’ position of rejecting backward causation. As he writes, “Part of the answer, no doubt, is a confusion between affecting and altering [the past—a distinction we’ll discuss at length later in this book]. We cannot alter the past. But then we cannot alter the future either, although we can affect it. However, I take the common-sense rejection of backward causation to be, for the most part, quasi-empirical. It is based on a thought experiment. Think how you would set about affecting the past. By building a time-machine, perhaps? But how would you build one? We have no idea how to start. Yet, by contrast, we can work out how to affect the future . . . we just move our bodies.”[51] But, as he goes on to argue, if we accept that we can’t *change* the past (which means there is no way we could actually observe backward causation), then there still exists the possibility that past events were as they were because of events in the future.

Are there actual phenomena that justify a belief in the possibility of effect before cause in real time (not just in tape recorder time)? The only example I know of, and a controversial one at that, is a theoretical result from a reformulation of electrodynamics by the great English physicist Paul Dirac (1902–1984). Classical theory models electric charges as point objects of zero size, which causes problems when one tries to calculate certain details, such as the total field energy of a single electron. The answer comes out as infinity. In an attempt to find more reasonable (that is, finite) answers to such questions, Dirac modified the zero size of a charge to one taking them to be extended objects (while retaining the validity of Maxwell’s equations for electrodynamics right down to a point). To calculate how such extended objects will behave mechanically, however, one has to include what are called the *self-interaction* forces, such as the force one side of an electron exerts on the other side.

When it was all worked through, Dirac arrived at a third-order differential equation of motion, an equation that involves a force term proportional not to the usual first time derivative of the velocity (that is, to the acceleration), but rather to the second derivative.[52] This force is proportional to the first derivative of the acceleration, and is a quantity of direct interest mostly to the designers of automobile suspensions, who call it the *jerk*. There is no force in physics, at least not in Newtonian physics, that shows that sort of dependence, and there are some curious consequences. For example, in Dirac’s theory an electron experiencing no external force can still continually accelerate, exhibiting what is called a ‘runaway solution.’

Dirac showed how the runaway solution can be eliminated by picking a particular value for what up to then was an arbitrary constant of integration in the analysis, but that trick causes, in turn, a new problem called 'pre-acceleration.' That is, if an electron experiences an external disturbance (Dirac considered a passing pulse of electromagnetic radiation), then the electron will start to move *before* the pulse reaches it! Now that does seem to be a pretty clear example of backward causation. The time interval during which the pre-acceleration occurs is very short, on the order of the time it takes light to travel across the spatially extended electron (about 10^{-24} s), but no matter. The apparent crack in the door of causality may be slight, but it was enough to satisfy some philosophers seeking scientific support for backward causation.

---

[51] P. Forrest, “Backward Causation in Defense of Free Will,” *Mind*, April 1985, pp. 210–217.

[52] P. A. M. Dirac, “Classical Theory of Radiating Electrons,” *Proceedings of the Royal Society A*, August 1938, pp. 148–168.

Not everybody liked this, however. One physicist was clearly uneasy about it, calling pre-acceleration "unpleasant" acausal behavior.[53] On the other hand, one can find believers, too.[54] Others have argued that the whole business is simply a non-problem. One philosopher, in fact, raised a very interesting technical point, arguing that Dirac's equation is non-Newtonian (remember the *jerk* force) and so we have no reason for coupling force and acceleration together as a cause-and-effect pair.[55] In Newtonian mechanics we do use that particular coupling, yet we do not think of force and velocity as a cause-and-effect pair because there is an integration operation involved in getting from to the other. Similarly, in Dirac's theory we have an integration operation separating force and acceleration.

One curious aspect to the debate on pre-acceleration is that many commentators seem not to have paid much attention to what Dirac himself had to say about it. As a Nobel laureate, it hardly seems likely that he would let such a result pass unnoticed and, indeed, his paper contains the following physical explanation: "It would appear that we have a contradiction with elementary ideas of causality. The electron seems to know about the pulse before it arrives, and to get up an acceleration … The behavior of our electron can be interpreted in a natural way, however, if we suppose the electron to have a finite size. There is then no need for the pulse to reach the center of the electron before it starts to accelerate. It starts to accelerate … as soon as the pulse meets its outside. Mathematically, the electron has no sharp boundary."

Two physicists suggested a fascinating connection between travel backward in time and Dirac's relativistically correct, quantum mechanical description of an electron.[56] They showed that in flat, two-dimensional spacetime the assumption of time travel to the past leads in a natural way to Dirac's equation. If, on the other hand, time travel only into the future is assumed, then additional assumptions are required to derive Dirac's equation. This connection between Dirac's equation and time travel to the past makes some philosophers and physicists nervous, but it didn't seem to bother Dirac. In fact, he went on in his paper to show how the pre-acceleration implies the possibility of building a device for sending a faster-than-light signal backward in time. Science fiction writers were, of course, quick to grasp that idea and such gadgets were dubbed "Dirac radios."[57]

---

[53] P. C. W. Davies, *The Physics of Time Asymmetry*, University of California Press 1977.

[54] J. Earman, "An Attempt to Add a Little Direction to 'The Problem of the Direction of Time'," *Philosophy of Science*, March 1974, pp. 15–47.

[55] A. Grunbaum, "Is Preacceleration of Particles in Dirac's Electrodynamics a Case of Backward Causation? The Myth of Retrocausation in Classical Electrodynamics," *Philosophy of Science*, June 1976, pp. 165–201.

[56] D. G. McKeon and G. N. Ord, "Time Reversal in Stochastic Processes and Dirac's Equation," *Physical Review Letters*, July 6, 1992, pp. 3–4.

One of the more perplexing aspects of backward causation is that it seems to allow for the possibility of *causal loops*, and for the breaking of such loops, a central feature in many of the very best time travel stories. For example, suppose there is a gadget such that if I push its control button *now*, then today's lecture notes will have appeared in the gadget's output tray *yesterday*. Indeed, yesterday I found today's notes there and, in fact, I am about to go to class to deliver that lecture. A mighty good one it is, too, so I think I think I'll send it back to yesterday in just a few minutes with the help of the gadget. But I haven't yet pushed the button. What if I now decide *not* to push the button? Why did the notes appear so I could use them today? Philosophers call this potential breaking of a causal loop a *bilking paradox*. Later in the book I'll discuss how such paradoxes have regularly appeared in the physics and philosophy literature since the 1940s.

By contrast, such paradoxes had been discussed in the science fiction magazines long before World War II. For example, in a letter to the editor at *Astounding Stories* (June 1932) a fan clearly stated his objection to time travel with the aid of a bilking paradox. He suggested the following experiment: Immediately publish an open offer to the inventor of time travel (who will be born, presumably, at some future date) to travel back to one week before the offer is published. But of course (argued the fan) we'd have a pretty problem if we then decided not to publish the offer after the inventor showed up! As that fan wrote, "Paradoxical? I'll say so, if time travel is possible." That fan didn't know about what seems to be a generic limitation on time machines, however: that one can't travel back to a date before the date of the time machine's creation. Thus, that fan's particular bilking paradox actually has no force.[58]

For another fictional example of a bilking paradox, consider the story[59] of time travelers who, just before they begin a trip into the future, see Earth invaded by Martians. At first the invaders are unbeatable, but then the defending military forces of Earth suddenly and mysteriously acquire a fantastically powerful new weapon. It isn't long before the time travelers realize where it came from—they themselves will go into the far future, obtain the weapon, and then return with it to what is now their own past (when the weapon first appeared). But then they wonder what might happen if they don't go, if instead they 'cheat time.' After all, they reason, why bother now to hunt for the weapon when the invasion has already been defeated? We are told that this potential bilking paradox is a "sinister conception, crawling evilly within their brains, like an unanswerable enigma."

---

[57] See, for example, J. Blish, "Beep," *Galaxy Science Fiction*, February 1954.

[58] A similar bilking paradox had actually appeared the year before in the 1931 novel *Many Dimensions* by the English writer Charles Williams (1886–1945), which reads like a suitable script for an Indiana Jones movie.

[59] E. Binder, "The Time Cheaters," *Thrilling Wonder Stories*, March 1940. There is an amusing reference in this tale to Orson Welles' famous radio-drama-hoax, from just 2 years earlier, of just such an alien invasion based on H. G. Wells' *War of the Worlds*.

Some philosophers, and practically all physicists, agree with that last assessment about bilking paradoxes, and so they believe there is simply nothing more to say. That is, bilking puzzles like the one in "The Time Cheaters" show that causal loops (and backward causation) must be impossible. Many feel this way about time loops, and backward causation, because (as is well known) time travel to the past can create all sorts of paradoxes. But such paradoxes are offensive only to human, culturally-biased intuitions on 'how things ought to work,' and not to the laws of physics which are indifferent to a reversal in the direction of time—which of course underlies what time travel is all about.

As the great American chemist G. N. Lewis expressed it, "Our common idea of time is notably unidirectional, *but this is largely due to the phenomena of consciousness and memory* [my emphasis]."[60] Lewis' words caught the eye of the editor at one science fiction magazine, who summed it up for his readers in a half-page essay that contained dramatic words hinting at backward causation: "A new theory of time . . . reveals the possibility that events now occurring are among the factors that decided Caesar nearly 2,000 years ago to cross the Rubicon."[61]

Lewis' willingness to accept causality violations is not a universally popular view today. For example, one physicist has written[62] that "It is fair to say that most conservative physicists have very serious reservations about the admissibility and reality of causality-violating processes. Causality violation (i.e., the existence of a 'time machine') is such an extreme violation of our understanding of the cosmos that it behooves us to be as conservative as possible about introducing such unpleasant effects into our models." He then goes on to declare closed timelike loops to be verboten because "the existence of closed timelike loops leads us to such unpleasant situations as meeting oneself 5 min ago." He sums up his philosophical position nicely with "any theory that is 'just a little bit causality violating' is 'just a little bit inconsistent.'"

Agreeing with this physicist is at least one philosopher who believes that the "association of causality with a particular temporal direction is not merely a matter of the way we speak of causes, but has a genuine basis in the way things happen" and that there is indeed an asymmetry with respect to past and future that is bound up with our concept of intentional action.[63] He then goes even further when he continues with the claim that being an agent of cause is not a necessary condition for seeing the asymmetry; being an observer is enough, as even an immobile yet intelligent tree (!) could detect the difference between past and future. (How he knows this about certain trees is left unexplained.)

---

[60] G. N. Lewis, "The Symmetry of Time in Physics," *Science*, June 6, 1930, pp. 569–577.

[61] Editorial essay, "Two-Way Time," *Astounding Stories*, September 1931.

[62] M. Visser, "Wormholes, Baby Universes, and Causality," *Physical Review D*, February 15, 1990, pp. 1116–1124.

[63] M. Dummett, "Bringing About the Past," *Philosophical Review*, July 1964, pp. 338–359.

The everyday views of causality that we have formed through our limited experiences when living in a world in which time travel is ‘uncommon’ may actually be incomplete. As the British philosopher Bertrand Russell (1872–1970) said with some humor long ago, in his 1912 Presidential Address (“On the Notion of Cause”) to the Aristotelian Society, “The law of causality, I believe, like much that passes muster among philosophers, is a relic of a by-gone age, surviving, like the monarchy, only because it is erroneously supposed to do no harm.” And I do agree with his fellow philosopher who, decades later, declared “The concept of cause is powerless to solve the problems posed by the concept of time. The fundamental laws of physics present our most careful, best established and most sophisticated understanding of time. Notoriously, nothing in these laws endorses the idea of a *flow of time nor of the direction* [my emphasis: we’ll return to both of these issues later in this chapter] which is basic to our conception of it. Nor are these laws causal (in the sense of singling out causes) even when they are deterministic. The concept of cause is not a fundamental one and cannot illuminate the darker corners in our understanding of the fundamental concept of time.”[64]

2.5 The Fourth Dimension

> “We are facing an invasion of fourth dimensional creatures . . . We are being attacked by life which is one dimension above us in evolution. We are fighting, I tell you, a tribe of hellhounds out of the cosmos. They are unthinkably above us in the matter of intelligence. There is a chasm of knowledge between us so wide and deep that it staggers the imagination.”[65]
>
> “Fourth dimension. Time factor. *You* know . . .”[66]

The idea of a fourth dimension to *space* has long been a staple of science fiction, but it has also long been viewed with suspicion. Indeed, many quite sophisticated scientists have thought it to be quite mysterious. For example, in his 1897 Presidential Address to the American Mathematical Society, the Canadian/American astronomer-mathematician Simon Newcomb (1835–1909) declared "The introduction of what is now very generally called hyperspace, especially space of more than three dimensions, into mathematics has proved a stumbling block to more than one able philosopher." Einstein stated Newcomb's view in blunter terms when he wrote "The non-mathematician is seized by a mysterious shuddering when he hears of 'four-dimensional' things, by a feeling not unlike that awakened by thoughts of the occult."[67]

---

[64] G. Nerlich, “How to Make Things Have Happened,” *Canadian Journal of Philosophy*, March 1979, pp. 1–22.

[65] From “Hellhounds of the Cosmos,” *Astounding Stories*, June 1932, by Clifford Simak (1904–1988). Simak went on to write a number of much better tales, but this passage lends credence to the editorial introduction to the 1957 anthology *Famous Science-Fiction Stories* (Random House) that declared so much in the early pulp science fiction was “science that was claptrap and fiction that was graceless.”

[66] Uninformative ‘explanation’ given to a befuddled, inadvertent time traveler who emerges miles away and one hour backward in time after a wild ride through the fourth dimension in a gadget (constructed from a bicycle tire!) in the shape of a three-dimensional Möbius strip (see note 99 in Chap. 1). From the story by H. Nearing, Jr., “The Maladjusted Classroom,” *The Magazine of Fantasy and Science Fiction*, June 1953.

To see just how right Einstein was with this observation, consider the reaction one Egyptian philosopher had (in 1929) to Einstein's own writings: "We have no doubt in our mind that nobody can understand it (the fourth dimension), including Einstein himself. The incomprehensibility of these assumptions [of general relativity] is due to their nature. They deal with the fourth dimension . . . and the reality of time and space. They can only be described by a mathematician's hypothesis or by religious faith."[68] This reaction is easy to understand—after all, anybody can 'see' that there are exactly three spatial dimensions, and that is that!

The 1901 novel *The Inheritors*, by the English writer Ford Madox Ford (1873–1939), like Simak's, is the tale of an insidious hyperspace invasion of our world. It illustrates Einstein's assertion about how many people react to the fourth dimension with an example from the time before the science fiction magazines. When the novel's narrator is bluntly told by an invader that she (the invader) is from the fourth dimension—an idea inspired by Ford's appreciation of how much success his acquaintance H. G. Wells had enjoyed with it—he recoils from that claim with the words "If you expect me to believe you inhabit a mathematical monstrosity, you are mistaken." And who can really blame that skeptical narrator? How can there be *four* spatial dimensions? No less an authority than Aristotle, writing in 350 B.C., had declared in his essay "On the Heavens" that "the three dimensions are all that there are."

Others were not so sure. In 1873, for example, we find an essay in *Nature* that refers to well-known mathematicians who even earlier had shown that they had an inner assurance of the reality of transcendental space (hyperspace).[69] The American philosopher Charles Sanders Peirce (1839–1914) was also an early advocate for the four-dimensionality of space. Just what he thought the nature of the fourth dimension to be is somewhat unclear, but the context of what he said suggests he took it to be spatial. He thought three-dimensional space to be "perverse" because of the existence of incongruous counterparts (such as left- and right-handed gloves), and this was apparently strong evidence for him that space could not be three-dimensional. Now, incongruous counterparts exist in all n-dimensional spaces, but Peirce preserved the special purity of the fourth dimension by suggesting that all physical objects, although capable of motion in the fourth direction, could themselves have no extent in that direction (remember, Peirce was a philosopher, not a physicist, and he offered no experimental support for any of this).[70]

---

[67] A. Einstein, *Relativity: the Special and General Theory*, Crown 1961, p. 33.

[68] From A. A. Ziadat, "Early Reception to Einstein's Relativity in the Arab Periodical Press," *Annals of Science*, January 1994, pp. 17–35.

[69] G. F. Rodwell, "On Space of Four Dimensions," *Nature*, May 1, 1873, pp. 8–9.

But is it *really* possible that there could be *four* spatial dimensions? We experience three independent directions, each lying at a right angle to the other two—but why just *three*, and not ten or fifteen? Indeed, in an 1888 talk to the Philosophical Society of Washington, Simon Newcomb dismissed the view that space must necessarily be three-dimensional as an "old metaphysical superstition." Yet, despite Newcomb's open-mindedness, it has been shown that in the framework of classical physics there are, in fact, several powerful reasons for why there must be *exactly three* spatial dimensions.

The beginning of a scientific explanation for the dimensionality of space appears in Kant, who believed the *three* dimensions of space and Newton's inverse-square law for gravity are intertwined (but he offered nothing beyond philosophical speculation). The origin of Kant's view is actually quite old, dating back to the ancient Greeks, who had already begun to suspect that there was something special about *three* dimensions, at least as far as geometry was concerned. They knew of the infinity of regular two-dimensional polygons, but that there were just five regular polyhedrons in three dimensions (the so-called *Platonic solids*). This early observation was trapped in mystical speculations, however, and it wasn't until the development of physics as a science that non-mystical discussions on the dimensionality of space began to appear.

Beginning with the work of Einstein's friend, the Austrian/Dutch physicist Paul Ehrenfest (1880–1933) in 1917, we can find the idea that the Poisson-Laplace equation, a second-order partial differential equation that describes the potential functions for both Newtonian gravity and electrostatics, does not allow for stable planetary or electronic orbits in *any* space with dimensionality greater than three. Further, the distortionless, reverberation-free propagation of both electromagnetic and sound waves is possible only in spaces of dimensions one and three. These conclusions have been shown to hold even when we go beyond nineteenth century physics into general relativity and quantum mechanics.[71]

Using a slightly different approach, a biological-topological argument for why space cannot have fewer than three dimensions exists. In all of our common experience, complex intelligent life is always found to occur as an aggregate of a vast number of elementary cells, interconnected via electrical nerve fibers. Each cell is connected to several others, *not all immediate neighbors*, by these fibers. If space had only one or two dimensions, then such highly interconnected nets of cells would be impossible because the overlapping nerve fibers would have to intersect, which would result in their mutually short-circuiting one another.

---

[70] R. R. Dipert, "Peirce's Theory of the Dimensionality of Physical Space," *Journal of the History of Philosophy*, January 1978, pp. 61–70.

[71] See, for example, I. M. Freeman, "Why Is Space Three-Dimensional?" *American Journal of Physics*, December 1969, pp. 1222–1224, and L. Gurevich and V. Mostepanenko, "On the Existence of Atoms in n-Dimensional Space," *Physics Letters A*, May 31, 1971, pp. 201–202.

It wasn't long before these views on the dimensionality of space found their way into science fiction. An early use of space as four-dimensional occurs in an awkward rewrite of Jules Verne's *Around the World in Eighty Days*, in which a professor and his crew fly into hyperspace and around the world and to the moon and back, in less than a day.[72] They do this with a plane equipped with a four-dimensional rudder! More interesting is the tragic story (originally published in 1926) of a math professor who learns how to move into hyperspace and back.[73] A colleague catches him at it and, once over his astonishment, asks what is behind it all. The professor replies, "My assumption is that the fourth dimension is just another dimension—no more different in kind from length, say, than length is from breadth and thickness, but perpendicular to all three. Now suppose that a being in two dimensions—a flat creature, like [a moving shadow on a surface]—were suddenly to grasp the concept of a third dimension and so step out of the [surface]. He might move only an inch, but he would vanish completely from the sight of the world."

The professor has similarly learned how to step out of 3-space and into 4-space but, when asked to explain *how*, all he can say is "How can I explain? It's just the *other* direction. It's *there*!" His colleague can't see it, but nonetheless is quick to grasp the practical implications: "This is power! Think of it! A step, and you are invisible! No prison cells can hold you, for there is a side to you on which they are as open as a wedding ring! No ring is secure from you: you can put your hand *round the corner* and draw out what you like. And, of course, if you looked back on the Universe you had left, you would see us in sections, open to you! You could place a stone or a tablet of poison right in the bowels of your enemies!"

What the professor's colleague is getting at involves a comparison with a prison in planar 2-space, which would merely be a circle around the captive. Knowledge of the third dimension would make it possible to escape, however, by simply moving along that new direction, over the circle, and then back into the plane. To a 2-space guard it would seem that the prisoner had suddenly vanished from view *inside* the circle and then just as suddenly materialized again *outside* the circle. Similarly, to escape from a 3-space prison, one would merely move along the fourth dimension, and in the same way one could remove the yolk from an egg without damaging the shell; indeed, one could remove the yolk directly from the chicken without damaging the chicken![74]

---

[72] B. Olsen, "Four Dimensional Transit," *Amazing Stories Quarterly*, Fall 1928.

[73] R. Hughes, "The Vanishing Man," reprinted in *The Mathematical Magpie* (C. Fadiman, editor), Simon and Schuster 1962.

[74] This astounding insight appeared in early pulp science fiction in, for example, M. J. Breuer, "The Appendix and the Spectacles," *Amazing Stories*, December 1928. The concept appeared even earlier in Bob Olsen, "The Four-Dimensional Roller-Press," *Amazing Stories*, June 1927, and then later in Olsen's "The Great Four Dimensional Robberies," *Amazing Stories*, May 1928 to rob locked safe deposit boxes, and "The Four Dimensional Escape," *Amazing Stories*, December 1933, in which a man sentenced to die by hanging at San Quentin Prison is rescued, while standing on the gallows' trap, by an inventor who pulls him through the fourth dimension.

In a later tale[75] we meet another professor who dramatically uses this very feature of the fourth dimension. His right hand has been modified through an accident to exist in four-dimensional hyperspace and so, to finance his research, he uses his 'talent' to become the perfect pickpocket, able to reach into any wallet no matter how well secured. He also can, indeed, reach right into the very bowels of his fellow man. And he *does*. When he demonstrates his hand to the policeman who has arrested him for being a thief, the astonished officer chokes on a lemon drop. Dr. Fuddles then, of course, does the right thing and removes the drop from the poor fellow with ease. There is one additional aspect to Dr. Fuddles' hand, however, that the story missed. If he had turned his right hand over in the fourth dimension, then he would have had *two* left hands!

It was discovered in 1827 by Möbius (of the strip) that any three dimensional object can be converted into its mirror image by flipping it over through the fourth dimension. Thus, a left-handed glove can be made by pure geometry (no scissors, thread, or needle required) into a precise copy of its right-handed mate. If a living organism is so flipped, however, there may be a problem, as everything in the body would be reversed, including the optically active organic molecules discovered by Pasteur in 1848, which are involved in vital biological processes. These molecules, called *stereoisomers*, exist in two versions in nature (the left-handed and the right-handed versions, if you will), but our bodies have developed the ability to use only one version. To be flipped through the fourth dimension would make some reversed stereoisomers unable to participate in the digestion of food and we would starve to death.

For modern science fiction writers the fourth dimension (and hyperspace, in general), is still a major concept. One physicist, writing in *Analog* (today's premier 'hard science' fiction magazine), summed up nicely what was so fascinating in early pulp, and still is today, about the idea of an extra dimension or two, or perhaps even more, at least from a fictional point of view: "Are there hidden dimensions not accessible to us, dimensions in which we could go adventuring, dimensions within which malevolent hyper-dimensional aliens may be lurking, ready to pierce our flimsy paper-thin three-space bodies with their terrible hyper-sharp claws?"[76] The early pulp science fiction magazines encouraged this lurid imagery. Witness the editorial blurb that opened one many-dimensional monster story as follows: "It was a strange world in which Lester and Florence found themselves. A world of sudden

---

[75] N. Bond, "Dr. Fuddle's Fingers," in *Mr. Mergenthwirker's Lobblies and Other Fantastic Tales*, Coward-McCann 1946.

[76] J. Cramer, "The Other Forty Dimensions," *Analog*, April 1985. 'Monsters in hyperspace' stories were numerous in pulp science fiction. Three examples (in no particular order of literary merit!) are: M. J. Breuer, "The Einstein See-Saw," *Astounding Stories*, April 1932; P. Ernst, "The 32nd of May," *Astounding Stories*, April 1935; "The Monster from Nowhere," *Fantastic Adventures*, July 1939.



Fig. 2.1 An experiment in hyperspace goes astray. The young man is pulling on "hyper-forceps" in an attempt to retrieve a surgeon who has fallen out of 3-space (along with his patient, a professor of non-Euclidean geometry, who suffers from gallstones). The hyper-forceps allow the removal of the gallstones without cutting into the body. Illustration by Frank R. Paul, ©1928 by Experimenter Publishing Co. for "Four Dimensional Surgery" (*Amazing Stories*, February 1928) by Bob Olsen, reprinted by permission of the Ackerman Science Fiction Agency, 2495 Glendower Ave., Hollywood, CA 90027 for the Estate

death and strange science, ruled by inhuman beasts."[77] But as outrageous as that might sound, the real physics of hyperspace is even more amazing.

Hyperspace is, in general, simply any space with more dimensions than the one we obviously seem to live in. In particular, our universe appears to be a four-dimensional (three spatial and one temporal) hyperspace called *spacetime*. This four dimensional world can, at least mathematically, be thought of as the boundary surface of a five dimensional hyperspace. This is analogous to the way the two-dimensional space of the surface of a sphere bounds the three-dimensional space of the sphere itself. This interesting imagery appeared quite early in pulp science fiction. For example, in one remarkably sophisticated story, an eccentric scientist at one point exclaims "A mathematical physicist lives in vast spaces ... where space unrolls along a fourth dimension on a surface distended from a fifth."[78]

There are some interesting geometrical implications to hyperspace which play big roles in time travel considerations. For example, for beings in the two-dimensional world of a sphere's surface there are *two* ways to travel from pole to pole. There is the usual way, *on* the surface of the sphere, and the hyperspace way which takes them *through* the sphere along the polar diameter. In imagery motivated by thinking of the sphere as an apple, and of the hyperspace path as a tunnel bored by a worm through the apple, it has become popular to call all such shortcuts, through any hyperspace of any dimension, *wormholes* (a word coined in the 1950s by the Princeton physicist-wordsmith John Wheeler). Wheeler used wormholes to show how electric charge could be thought of as lines of force trapped in the changing topology of a multiply connected space (indeed, Wheeler claimed that the observation of what we call electricity is experimental evidence that space is *not* simply connected).[79]

---

[77] M. Duclos, "Into Another Dimension," *Fantastic Adventures*, November 1939. See the illustration for this story in "Some First Words."

[78] M. J. Breuer, "The Gostak and the Doshes," *Amazing Stories*, March 1930.

The general theory of relativity predicts the existence of wormholes in spacetime and, in fact, they were first ‘discovered’ theoretically in the mathematics of relativity as early as 1916 by the Viennese physicist Ludwig Flamm (1885–1964). Later analyses were done by Einstein, himself.[80] Wormholes have been discussed as a possible model for pulsars (as opposed to the more usual model as rotating neutron stars).[81] It has also been suggested that the interior of a charged black hole may be the entrance to a wormhole.[82] All of these various solutions to the gravitational field equations are generically called “Einstein-Rosen bridges” in the physics literature (see note 81, for example), and the term soon appeared in fiction, too.[83]

The use of hyperspace wormhole portals for explaining some observed physical phenomenon appeared in the scientific literature long before Wheeler’s electricity example. In his 1928 book *Astronomy and Cosmogony*, for example, the British theoretician Sir James Jeans devoted a chapter to what were then called nebulae, the island-universes we now call galaxies. At the end of his discussion on the arms of spiral galaxies, Jeans offered the following speculation: “Each failure to explain the spiral arms makes it more and more difficult to resist a suspicion that the spiral nebulae are the seats of types of forces entirely unknown to us, forces which may possibly express novel and unsuspected *metric properties of space* [my emphasis]. The type of conjecture which presents itself, somewhat insistently, is that the centers of the nebulae are of the nature of ‘singular points,’ at which matter is poured into our universe from some other, and entirely extraneous, special dimension, so that, to a denizen of our universe, they appear as points at which matter is being continually created." This, in everything but name, is a wormhole.

---

[79] A space is simply connected if *all* the points on the straight line that joins *any* two points in the space are also in the space. The interior of a sphere is simply connected. The interior of a sphere with a hole in it is *not* simply connected.

[80] A. Einstein, “The Particle Problem in the General Theory of Relativity,” *Physical Review*, July 1, 1935, pp. 73–77.

[81] J. M. Cohen, “The Rotating Einstein-Rosen Bridge,” in *Relativity and Gravitation* (C. G. Kuper and A. Peres, editors), Gordon and Breach Science Publishers 1971.

[82] A. Ori, “Inner Structure of a Charged Black Hole: An Exact Mass-Inflation Solution,” *Physical Review Letters*, August 12, 1991, pp. 789–792.

[83] See, for example, J. G. Cramer, *Einstein’s Bridge*, Avon 1997 (this is the same Cramer cited in note 76). The *Rosen* comes from the American-Israeli physicist Nathan Rosen (1909–1995), who was a collaborator of Einstein’s.

What would hyperspace be like? It is intuitively obvious that in the case of the 2-D surface of a 3-space sphere, the 'hyperspace' wormhole path is shorter than the surface path. Even if this 'shorter path' view holds for wormholes in our 4-D spacetime, however, getting around in science fiction hyperspace may not be a simple task. One tale, for example, tells the story[84] of how one of the first spaceships to explore hyperspace gets lost. The trouble with hyperspace travel is that "You go in at one point, you rocket around until you think it's time to come out, and there you are. Where is 'there'? Why, that's the surprise that's in store for you, because you never know until you get there. And sometimes not even then." The same idea plays a central role in Robert Heinlein's 1957 novel *Tunnel in the Sky*, in which a 'hyperspace gate' is discovered by accident during failed time travel experiments.

Another story[85] asks the same question about hyperspace, and arrives at the same answer: "When you took the Jump ... how sure were you *where* you would emerge? The timing and quantity of the energy input might be as tightly controlled as you liked ... but the uncertainty principle reigned supreme and there was always the chance, even the inevitability of a random miss ... a paper-thin miss might be a thousand light-years."

A common way to visualize hyperspace wormhole shortcuts is to imagine the beginning and the end of a journey as points A and B on the 2-D surface of a piece of paper. Then imagine that the paper is folded so as to position A over B, perhaps with A almost touching B. The distance from A to B *through hyperspace* (the 3-D space in which the folding took place) can clearly be much less than is the distance through 'normal' space (the distance covered by a trip that always remains in the 2-D surface). This is the specific example used in one tale to explain the instantaneous "space-warp" (wormhole) device invented by the story's hero.[86] Such imagery actually appeared quite early in science fiction, as in one story in which a gadget is used to "bend space" so that Earth and Venus touch![87]

The idea of hyperspace folding has broken free from science fiction and can now be found in modern stories in other genres. For example, in one Stephen King story ("Mrs. Todd's Shortcut") a woman keeps finding ever shorter ways to drive from Castle Rock, Maine to Bangor. As the crow flies it is 79 miles, but she gets the journey down to 67 miles, and later to 31.6 miles. When doubted, she replies: "Fold the map and see how many miles it is then ... it can be a little less than a straight line if you fold it a little, or it can be a lot less if you fold it a lot." The doubter remains unconvinced: "You can fold a map on paper, but you can't fold *land*."

---

[84] F. Pohl, "The Mapmakers," *Galaxy Science Fiction*, July 1965.

[85] I. Asimov, "Take a Match," in *New Dimensions II: Eleven Original Science Fiction Stories* (R. Silverberg, editor), Doubleday 1972.

[86] G. O. Smith, "The Möbius Trail," *Thrilling Wonder Stories*, December 1948.

[87] E. L. Rementer, "The Space Bender," *Amazing Stories*, December 1928.

For the purpose of wormhole creation in spacetime, we actually have to imagine much more: the folding of four-dimensional spacetime through a five dimensional hyperspace. The folding imagery has even appeared in the movies: spacetime folding is demonstrated with a piece of paper in both *Event Horizon* (perhaps the worst movie of 1997) and the 2014 *Interstellar*.

Another feature of hyperspace that science fiction has taken a liking to is its vastness. An interesting fictional treatment of this idea was given by a writer who, in real life, was an academic psychologist at the University of Michigan. He put himself in a story[88] of a starship captain who is explaining to the crew psychologist how he feels about hyperspace (or *subspace*, as it is called in the story): "God forsaken. That's just what it is. Completely black, completely empty. It frightens me every time we make the jump through it . . . it frightens me because—well, because a man seems to get lost out there. In normal space there are always stars around, no matter how distant they may be, and you feel that you've got direction and location. In subspace, all you've got is nothing—and one hell of a lot of that. It's incredible when you stop to think about it. An area—an opening as big as the whole of our Universe, big enough to pack every galaxy we've ever seen in it—and not a single atom of matter in it . . . until we came barging in to use it as a shortcut across our own Universe."

The vastness of hyperspace got a more humorous treatment from the early pulp science fiction writer Bob Olsen (1884–1956), who wrote the following verses[89] in the introduction to one of his many stories of the fourth dimension:

I read a yarn the other day—
A crazy concept, I must say.
It states that objects have extension
In what is called the "Fourth Dimension."
In hyperspace one could, no doubt,
Make tennis balls turn inside out;
And from a nut remove the kernel
And not disturb the shell external.
A crook could pilfer bonds and stocks,
Then laugh at prison bars and locks,
One step in this direction queer,
And presto! He would disappear!
Let's hope, in planning new inventions,
They'll give us cars with four dimensions.
When searching for a parking place
We sure could use some hyperspace!

It is not just science fiction that takes hyperspace seriously. We find a mathematician, for example, writing that "most science fiction addicts are familiar with the notion of 'hyperspace,' a higher dimensional space-time bounded by Space-Time through which, in the far distant future, interstellar voyages shortcut the (otherwise unsurmountable) distances between the stars. The purpose of this article[90] is to demonstrate that any . . . relativistic space-time model is the boundary of some . . . five-dimensional hyperspace." That is just what Breuer's magazine character (see note 78) said—in 1930!

---

[88] J. V. McConnell, "Avoidance Situation," *If*, February 1956.

[89] B. Olsen, "The Four-Dimensional Auto-Parker," *Amazing Stories*, July 1934. "Bob Olsen" was the pen-name for Alfred Johannes Olsen.

The concept of *time* as a fourth dimension has long been a popular concept, and science fiction in particular has embraced it with enthusiasm. We find a little joke on the idea in a story where a young couple, visited by time travelers from 500 years in the future, are said to live in Apartment 4-D.[91] One physicist[92] traced the idea back to the late eighteenth century, finding references to the idea in pre-1800 works of the great French mathematical physicists Jean le Rond d'Alembert (1717–1783) and Joseph-Louis Lagrange (1736–1813). In fact, a philosopher[93] has found a 1751 passage written by d'Alembert that appears to indicate that it is some unknown, earlier person to whom the credit should really go: "I have said [that it is] not possible to imagine more than three dimensions. A clever acquaintance of mine believes, however, that duration could be regarded as a fourth dimension and that the product of time and solidity would be in some way a product of four dimensions; that idea can be contested, but it seems to me that it has some merit, if only that of novelty."

Still, it wasn't until a curious letter appeared in *Nature* in 1885 that the concept of time as the fourth dimension was mentioned seriously in an English-language scientific journal. The author, mysteriously signing himself only as "S.," began by asking "What is the fourth dimension? . . . I [propose] to consider Time as a fourth dimension . . . Since this fourth dimension cannot be introduced into space, as commonly understood, we require a new kind of space for its existence, which we may call time-space."[94] Who was this prophetic writer that, if he had just made a simple swap, would have been the first to use space-time as a word? Nobody knows. Bork speculates that it was an acquaintance of H. G. Wells, but Wells himself is on record that it certainly wasn't him.

In his 1934 *Experiment in Autobiography*, Wells wrote "In the universe in which my brain was living in 1879 there was no nonsense about time being space or anything of that sort. There were three dimensions, up and down, fore and aft and right and left, and I never heard of a fourth dimension until 1884 [when Wells was eighteen] or thereabout. Then I thought it was a witticism." He had, in fact, said this before. In a 1931 edition of *The Time Machine* (Random House), for example, he wrote in the Preface that the idea for the novel "was begotten in the writer's mind by students' discussions in the laboratories and debating society of the Royal College of Science in the eighties and already it had been tried over in various forms by him before he made this particular application of it."

---

[90] G. S. Whiston, "'Hyperspace' (The Cobordism Theory of Space-Time)," *International Journal of Theoretical Physics*, December 1974, pp. 285–288.

[91] L. Padgett, "When the Bough Breaks," *Astounding Science Fiction*, November 1944.

[92] A. M. Bork, "The Fourth Dimension in Nineteenth-Century Physics," *Isis*, October 1964, pp. 326–338.

[93] E. Meyerson, *The Relativistic Deduction*, volume 83 of *Boston Studies in the Philosophy of Science*, D. Reidel 1985, p. 78.

[94] S., "Four-Dimensional Space," *Nature*, March 26, 1885, p. 481. The editorial staff at *Nature* has informed me that, more than a century-and-a-quarter later, there is no longer any record of the identity of S. in the journal's archives.

The idea of time as the fourth dimension entered the popular mind around 1894–95, with the publication of the first of Wells' so-called "scientific romances," *The Time Machine*. Then, after that pioneering use of time as the fourth dimension, science fiction quickly adopted the idea as the basis for one of its most popular subgenres. One of the great "golden age of science fiction" writers, 'Murray Leinster' (1896–1975)—the pen-name for William Jenkins—used it as the basis for his first published story.[95] It is the incredible tale of a Manhattan skyscraper (and its 2000 occupants) sent backward in time several 1000 years because its foundation slips (in an unexplained way) along the fourth dimension. The scientific sophistication of the story is primitive, with just one of the many logical flaws being a vivid description of the time travelers living forward-in-time even as their wrist watches run backward. Indeed, when pulp pioneering editor Hugo Gernsback reprinted the tale in one of the early issues of *Amazing Stories*, a reader complained about that very point. Gernsback felt compelled to defend the story, but could muster only a weak rebuttal based on an author's right to "poetic license."[96]

More technical is the discussion in the story of a clerk who transforms the main entrance to a department store into a time machine by building a tesseract (a four-dimensional cube).[97] The claim is made there that the fourth dimension of the cube/doorway is time. That tale appeared just 5 months after a classic of science fiction by Robert Heinlein (1907–1988) had appeared, also using a tesseract, in which the fourth dimension is taken as *spatial*.[98]

Some writers wanted to have the fourth dimension both ways, as space *and* time in the same story. One wonderful example of this is a classic,[99] written by one of the giants of science fiction. In that tale an electrical engineer named Nelson is caught in the middle of an enormous electromagnetic field surge produced by a short circuit in a power plant. As a physicist explains to the shocked board of directors of the utility, "It now appears that the unheard-of-current, amounting to millions of amperes . . . must have produced a certain extension into four dimensions . . . I have been making some calculations and have been able to satisfy myself that a

---

[95] M. Leinster, "The Runaway Skyscraper," *Argosy*, February 1919.

[96] H. Gernsback, "Plausability in Scientifiction," *Amazing Stories*, November 1926.

[97] W. P. McGivern, "Doorway of Vanishing Men," *Fantastic Adventures*, July 1941.

[98] R. Heinlein, "—And He Built a Crooked House," *Astounding Science Fiction*, February 1941. Here we read of a Los Angeles architect who builds a house in the shape of a tesseract as it would appear if collapsed into normal three-dimensional space. It isn't stable in 3-space (we are told), however, and so a California earthquake is sufficient to topple the house into a stable 4-D configuration, along with its occupants.

[99] A. C. Clarke, "Technical Error," *Fantasy No. 1*, December 1946.

'hyperspace' about ten feet on a side was, in fact, generated: a matter of some ten thousand quartic—not cubic!—feet. Nelson was occupying that space. The sudden collapse of the field [when the overload breakers finally broke the circuit] caused the rotation of that space."

Being rotated through 4-space has inverted the unlucky Nelson [see *For Further Discussion* at the end of this chapter for more on this point], and to bring him back to normal he must be flipped again. The physicist brushes aside a question about the fourth dimension as time, asserting that the only issue is one of space. Poor Nelson is, therefore, again subjected to a stupendous power overload—only now he disappears! Too late, the physicist realizes that the fourth dimension is both space *and* time and that Nelson has been spatially flipped *and* temporally displaced into the future. To understand the particularly monstrous fate of Nelson, just ask yourself what the result would be if he should materialize *inside* matter sometime in the future!

The interpretation of the fourth dimension as time is, of course, the one of interest to prospective time travelers, to physicists studying time travel, and to philosophers of time, and so for us, too. The sort of science fiction that is of greatest interest to us is like the one in which one of the characters, displaced in time, asks for an explanation from a higher-dimensional being who appears on the scene: "'Just where is Tuesday?' he asked. 'Over there [and when the being extends its hand, the hand disappears].' 'Do that again.' 'What? Oh—Point toward Tuesday? Certainly.'" The being explains the physics of the situation to the astonished time traveler thus: "It is a direction like any other direction. You know yourself there are four directions—forward, sideward, upward, and—*that* way! ... It is the fourth dimension—it is duration."[100]

And how about stories like the one in which a mad inventor discovers how to make a substance whose atoms resist being pushed by "pushing back at right angles to all the other [spatial] directions." That is, to push on this exotic stuff is to risk experiencing a back reaction, of being pushed "off into the fourth dimension [which we are told is time] ... into the middle of the week after next."[101] Now wouldn't *that* really be something?!

But of course it was H. G. Wells who, in fiction, pioneered time travel and its connection to the fourth dimension as it is popularly thought of today (with the caveats about Wellsian time machines kept firmly in mind). We are therefore quite interested, as *The Time Machine* opens, to listening-in as the Time Traveller expounds to a group of friends at a dinner party in his London home. He starts with the assertion "There is no difference between Time and any of the three dimensions of Space except that our consciousness moves along it." When asked to say more about the fourth dimension, he replies, "It is simply this. That Space, as our mathematicians have it, is spoken of as having three dimensions, which one may call Length, Breadth, and Thickness, and it is always definable by reference to three planes, each at right angles to the others. But some philosophical people have been asking why *three* dimensions particularly—why not another direction at right angles to the other three?—and have even tried to construct a Four-Dimensional geometry. Professor Simon Newcomb was expounding this to the New York Mathematical Society only a month or so ago."[102]

---

[100] T. Sturgeon, "Yesterday Was Monday," *Unknown Fantasy Fiction*, June 1941.

[101] M. Leinster, "The Middle of the Week After Next," *Thrilling Wonder Stories*, August 1952.

2.6 Spacetime and the Block Universe

> "And now he has preceded me briefly in bidding farewell to this strange world. This signifies nothing. For us believing physicists, the distinction between past, present, and future is only an illusion, even if a stubborn one."
>
> —Albert Einstein[103]

The poet Henry Van Dyke wrote, in his 1904 "The Sun-Dial at Wells College," words that echo the spirit of Omar Khayyam's *Rubaiyat* from nine centuries before:

The shadow by my finger cast
Divides the future from the past:
Before it, sleeps the unborn hour,
In darkness, and beyond thy power:
Behind its unreturning line,
The vanished hour, no longer thine:
One hour alone is in thy hands,—
The NOW on which the shadow stands.

The very next year Einstein's theory of special relativity appeared and, 3 years later, came Minkowski's spacetime interpretation of special relativity. Van Dyke's beautiful poetry was dealt a mighty blow by those developments in mathematical physics, and in the rest of this chapter we'll see how that came to pass.

The modern view of reality, that the past, present, and future are joined together into a four-dimensional entity called *spacetime*, is due to Hermann Minkowski (1864–1909), Einstein's mathematics teacher when he was a student in Zurich. Minkowski gave spacetime (the visual imagery of Einstein's mathematics) to the world during a famous address at the 80th Assembly of German Natural Scientists and Physicians in Cologne, on September 21, 1908. Entitled "Space and Time," his remarks were electrifying then and still are today.[104] He began dramatically: “Gentlemen! The views of space and time which I wish to lay before you have sprung from the soil of experimental physics, and therein lies their strength. They are radical.” Then came the famous line, quoted in so many freshman physics texts and philosophy papers, concerning the nature of spacetime: “Henceforth space by itself, and time by itself, are doomed to fade away into mere shadows, and only a kind of union of the two will preserve independence.” Minkowski explained what spacetime is in these words to his audience:

---

[102] And so Newcomb actually was. Wells, it is certain, routinely read *Nature* (one of his college friends, Richard Gregory, eventually became the journal's editor), and Wells must have read Newcomb's address of December 28, 1893 to the New York Mathematical Society when reprinted in the February 1, 1893 issue (on pp. 325–329), where he called hyperspace "the fairyland of geometry." From the Time Traveller's own words, then, that wonderful Victorian dinner party must have taken place in January or February of 1894.

[103] From a letter written by Einstein on March 21, 1955, to the children of Michele Besso, his dearest friend, who had just died. Einstein's use of the word *briefly* was due to his knowledge that he was nearly out of time, too (he died just a month later).

> “A point of space at a point of time . . . I will call a *world point*. The multiplicity of all thinkable x, y, z, t systems of values we will christen the *world*. With this most valiant piece of chalk I might project upon the blackboard four world axes . . . Not to leave a yawning void anywhere, we will imagine that everywhere and everywhen there is something perceptible. To avoid saying ‘matter’ or ‘electricity’ I will use for this something the word ‘substance.’ We fix our attention on the substantial point which is at the world point x, y, z, t, and imagine that we are able to recognize this substantial point at any other time. Let the variations dx, dy, dz, of the space coordinates of this substantial point correspond to the time element dt. Then we obtain, as an image, so to speak, of the everlasting career of the substantial point, a curve in the world, a *world-line*. . . . The whole Universe is seen to resolve itself into similar world-lines, and I would fain anticipate myself by saying that in my opinion physical laws might find their most perfect expressions as relations between these world-lines . . . *Thus also three-dimensional geometry becomes a chapter in four-dimensional physics* [my emphasis].”

With those words Minkowski gave mathematical expression to the philosophical exposition of Wells’ Time Traveller to his dinner party friends. Taking the Minkowskian view of the primacy of spacetime as the ultimate building block stuff of reality was Princeton professor of physics John Wheeler, who wrote[105] “There is nothing in the world except empty curved space. Matter, charge , electromagnetism . . . are only manifestations of the bending of space. *Physics is Geometry*.” This idea was echoed in fiction, in the 1987 novel Moscow 2042 by Vladimir Voinovich, where we find a time traveler who declares “Anyone with even a nodding acquaintance with the theory of relativity knows that nothing is a variety of something and so you can always make a little something out of nothing.”

But not everybody understood Minkowski. In a little-known yet quite erudite essay, published just after a stunning experimental verification of general relativity (the bending of starlight passing through the Sun’s gravitational field[106]), an anonymous author presented an optical analogy to help those who thought relativity simply “a mathematical joke.” Signing himself only as “W.G.,” he included the following passage[107]:

---

[104] For a study that includes the original German text, careful English translations, and photographs of Minkowski’s agonized corrections to his pre-address manuscript, see P. L. Galison, “Minkowski’s Space-Time: From Visual Thinking to the Absolute World,” *Historical Studies in the Physical Sciences* (volume 10), 1979, pp. 85–121.

[105] C. W. Misner and J. Wheeler, “Gravitation, Electromagnetism, Unquantized Charge, and Mass as Properties of Curved Empty Space,” *Annals of Physics*, December 1957, pp. 525–603.

[106] General relativity had already explained the long-puzzling excess precession of the perihelion (point of closest approach to the Sun) of Mercury’s orbit. The excess was an observational (and so experimental) fact which Newton’s gravity *cannot* completely explain.

> “Some thirty or more years ago [it was forty] a *jeu d’esprit* was written by Dr. Edwin Abbott entitled *Flatland* . . . Dr. Abbott pictures intelligent beings whose whole experience is confined to a plane, or other space of two dimensions, who have no faculties by which they can become conscious of anything outside that space and no means of moving off the surface on which they live. He then asks the reader, who has consciousness of the third dimension, to imagine a sphere descending upon the plane of Flatland and passing through it. How will the inhabitants regard this phenomenon? They will not see the approaching sphere and will have no conception of its solidity. They will only be conscious of the circle in which it cuts their plane. This circle, at first a point, will gradually increase in diameter, driving the inhabitants of Flatland outward from its circumference, and this will go on until half the sphere has passed through the plane, when the circle will gradually contract to a point and then vanish, leaving the Flatlanders in undisturbed possession of their country . . . Their experience will be that of a circular obstacle gradually expanding or growing, and then contracting, and they will attribute to *growth in time* what the external observer in three dimensions assigns to a movement in the third dimension. Transfer this analogy to a movement of the fourth dimension through three-dimensional space. Assume the past and future of the Universe to be all depicted in four-dimensional space, and visible to any being who has consciousness of the fourth dimension. If there is motion of our three-dimensional space relative to the fourth dimension, all the changes we experience and assign to the flow of time will be due simply to this movement, *the whole of the future as well as the past existing in the fourth dimension* [my emphasis].”

W.G.’s words are a clear and unequivocal statement of the so-called *block universe* concept of four-dimensional spacetime. One can find the block universe concept in the writings of the ancients, too. Consider, for example, the fifth-century B.C. Greek philosopher Parmenides’ view of reality: “It is uncreated and indestructible; for it is complete, immovable, and without end. Nor was it ever, nor will it be; for now it *is*, all at once, a continuous *one*.” And in Thomas Aquinas’ *Compendium Theologiae*, written in the thirteenth century, we find “We may fancy that God knows the flight of time in His eternity, in the way that a person standing on top of a watchtower embraces in a single glance a whole caravan of passing travelers.” This is the block universe idea, too, but whereas for Parmenides it was metaphysics and for Aquinas it was theology, for Einstein and Minkowski it was physics.[108]

---

[107] W. G., “Euclid, Newton, and Einstein,” *Nature*, February 12, 1920, pp. 627–630. As with the mysterious S. (note 94), the editorial staff at *Nature* has informed me that, nearly a century later, there is no longer any record of the identity of W. G. in the journal’s archives.

[108] And for some it was all nonsense. The British philosopher Peter Geach (1916–2013), for example, declared the Minkowskian view to be “very popular with philosophers who try to understand physics and physicists who try to do philosophy.” See P. T. Geach, “Some Problems About Time,” in *Studies in the Philosophy of Thought and Action* (P. F. Strawson, editor), Oxford University Press, 1968. In his introduction to Geach’s essay, editor Strawson put in his two cents by stating the four-dimensional view of reality to be nothing but “fanciful philosophical theorizing.”

The block universe concept may explain the enigmatic statement made by Einstein at the death of Michele Besso (note 103). As interpreted[109] decades later:

> "It seems that Einstein's view of the life of an individual was as follows. If the difference between past, present, and future is an illusion, i.e., the four-dimensional spacetime is a 'block Universe' without motion or change, then each individual is a collection of myriad of selves, distributed along his history, each occurrence *persisting on the world line, experiencing indefinitely the particular event of that moment* [my emphasis]. Each of these momentary persons, according to our experience would possess memory of the previous ones, and would therefore believe himself identical with them; yet they would all exist separately, as single pictures in a film. Placing the past, present and future on the same footing this way, destroys the notion of the unity of the self, rendering it a mere illusion as well."

It appears by his words that Einstein was indeed in agreement with the block universe concept, and that he was attempting to give his friend's family some reason to believe that their father still lives 'somewhen.' The makers of the 2002 film *Minority Report* made use of the block universe concept, even if not intentionally; there we see police stopping crime *before* it happens because they can 'see the future.'

Not everybody believed that this view of spacetime was Einstein's, however. Karl Popper (1902–1994), an Austrian philosopher of science, wrote 28 years after the scientist's death that "Einstein was a strict determinist when I first visited him in 1950: he believed in a 4-dimensional Block-Universe. But he gave this up."[110] Shortly before he wrote those words, however, Popper must have learned something new to convince himself of his final comment, because just 2 years earlier he had declared[111] Einstein to (still) be a determinist. Popper presents no evidence to support his claim of Einstein's philosophical conversion, however, and it would seem that the Besso letter still offers the best insight into his actual view of spacetime shortly before his death. I say this because I think Popper's labeling of Einstein as a determinist is wrong. Determinism says 'If you do A, then B will happen, and if you do not do A then (perhaps) something other than B will happen.' A deterministic universe has plenty of room for free will, because you can *choose* to do A or not to do A, and what you decide makes a difference. A fatalistic universe, however, as is the block universe, simply says 'You will do A and B will happen.' To accept the block universe, as did Einstein, is to be a fatalist, not a determinist.

---

[109] L. P. Horwitz, R. I. Arshansky, and A. C. Elitzur, "On the Two Aspects of Time: The Distinction and Its Implications," *Foundations of Physics*, December 1988, pp. 1159–1193. See also Einstein's own book (note 67) where he wrote "From a 'happening' in three-dimensional space, physics becomes, as it were, an 'existence' in the four-dimensional 'world'."

[110] See the *Seventh International Congress of Logic, Methodology and Philosophy of Science*, volume 4 (Salzburg, Austria, 1983), p. 176. Popper describes his early discussions with Einstein on the reality of time and the four-dimensional Parmenidean block universe in some detail in his autobiography: see volume 1 of *The Philosophy of Karl Popper* (P. A. Schilpp, editor), The Library of Living Philosophers, Open Court 1974, pp. 102–103.

[111] In the Foreword to the book by B. Gal-Or, *Cosmology, Physics and Philosophy*, Springer-Verlag 1981.

Einstein's final position on this, then, *might* have been like that of the fictional time traveler who takes a little girl 25,000 years back into the past, where she sees an ancient ancestor of humanity.[112] She then asks if the ancestor is really alive. The time traveler replies, "Every man who ever lived is still alive, child. In time there is no real death. When a man dies he's still alive 10 min ago, 10 years ago. He's always alive to those who travel back through time to meet him face to face."

Did Einstein *really* believe this? Not everybody thinks so. At the 1922 meeting of the French Philosophical Society, for example, the philosopher of science Emile Meyerson asked Einstein whether the spatialization of time (the idea that time is a dimension on the same footing as the spatial ones) is a legitimate interpretation of Minkowski's spacetime. Einstein's terse answer was that "it is certain that in the four-dimensional continuum all dimensions are *not* [my emphasis] equivalent."[113]

Use of the term *block universe* is generally thought to have originated with the Oxford philosopher Francis Herbert Bradley (1846–1924) who, in his 1883 book *Principles of Logic*, wrote "We seem to think that we sit in a boat, and are carried down the stream of time, and that on the bank there is a row of houses with numbers on the doors. And we get out of the boat, and knock at the door with number 19, and, re-entering the boat, then suddenly find ourselves opposite 20, and having then done the same, we go on to 21. And, all this while, the firm fixed row of the past and future stretches in a *block* [my emphasis] behind us, and before us." The house numbers would seem to be Bradley's way of referring to the centuries. Note that he wrote these words 12 years before *The Time Machine*, and that they preceded Minkowski's famous address by a quarter-century.

But this origin of *block universe* may not be as clear-cut as I have made it appear. Bradley, who was frequently criticized by the Harvard psychologist William James (1842–1910)—a man who argued for free will[114] and indeterminism, concepts disallowed in a block universe—may have been mocked on the idea by James during an address to the students of the Harvard Divinity School in March 1884 ("The Dilemma of Determinism"), the year after Bradley's book had been published. In his address James spoke of a deterministic world as being a "solid" or "iron block" (this are *not* characteristics of determinism, but rather of fatalism, and so James makes the same mistake as did Popper). However, writing the year before Bradley's book, in the April 1882 issue of *Mind*, James wrote (with obvious disdain) of "the universe of Hegel [the German philosopher Georg Hegel (1770-1831)]—the *absolute block* [my emphasis] whose parts have no loose play," as having "the oxygen of possibility all suffocated out of its lungs" and as being a universe in which "there can be neither good nor bad, but [only] one dead level of mere fate." So, perhaps, the chain of evolution of the term block universe is actually from Hegel to James and *then*, finally, to Bradley.

---

[112] F. B. Long, "Throwback in Time," *Science Fiction Plus*, April 1953.

[113] A. Einstein, "La Théorie de la Relativité," *Bullentin de la Société Francaise de Philosophia* (volume 17), 1922, pp. 91–113.

[114] A famous line from James, one that perhaps illustrates his sort of reasoning about free will, is "My first act of free will shall be to believe in free will." If only proving theorems in math and physics were that easy.

We can actually find the block universe in fiction *before* Minkowski (and so certainly before pulp science fiction) came on the scene. In an 1875 (!) story[115] we read of a man who sees, years in advance, his own death in the American Civil War. In the following extract, this man speaks to an unnamed friend (who is the narrator):

> "Do you know," said Bernard, presently, "I sometimes think prophecy isn't so strange a thing . . . I really see no reason why any earnest man may not be able to foresee the future, now and then . . ."
>
> "There is reason enough to my mind," I replied, "in the fact that future events do not exist, as yet, and we cannot know that which is not, though we may shrewdly guess it sometimes . . ."
>
> "Your argument is good, but your premises are bad, I think," replied my friend, . . . his great, sad eyes looking solemnly into mine.
>
> "How so?" I asked.
>
> "Why, I doubt the truth of your assumption, that future events do not exist as yet . . . Past and future are only divisions of time, and do not belong to eternity . . . To us it must be past or future with reference to other occurrences. But is there, in reality, any such thing as a past or a future? If there is an eternity, it is and always has been and always must be. But time is a mere delusion . . . To a being thus in eternity, all things are, and must be present. *All things that have been, or shall be, are* [my emphasis]."

When the block universe concept did eventually appear in science fiction, it did so early. In a 1927 story, for example, a time traveler from the future and a man in the present (who is the narrator) have the following exchange:

> "I have just been five years into your future."
> "My future!" I exclaimed. "How can that be when I have not lived it yet?"
> "But of course you have lived it."
> I stared, bewildered.
> "Could I visit my past if you had not lived your future?"[116]

So, while the block universe has a bit of a history to it, the history of the concept of *mathematical* spacetime in physics has a much clearer origin: it derives from Minkowski, not from Hegel, Bradley, James, or even Einstein (who often gets credit for it even though he didn't use the concept in special relativity in 1905, 3 years before Minkowski's address.). Eventually, of course, Einstein did come to appreciate the power and conceptual beauty of four-dimensional spacetime, and it came to play a central role in his ideas about gravity. Indeed, in Einstein's general theory of relativity gravity *is* (curved) spacetime. The starting point for general relativity (and so a *scientifically plausible* theory of time travel) was Minkowski's creation of spacetime, and he is truly deserving of the title 'father of the fourth dimension.'

---

[115] G. C. Eggleston, "The True Story of Bernard Poland's Prophecy," *American Homes*, June 1875. George Cary Eggleston (1839–1911) had served as a soldier in the Confederate Army.

[116] F. Flagg, "The Machine Man of Ardathia," *Amazing Stories*, November 1927.

Of course, it is true that Newton's physics also talks about an analytical (as opposed to merely philosophical) space and time long before either Minkowski or Einstein, but 'Newtonian spacetime' is something very different from Minkowski's self-described "radical" view.[117] In the Newtonian view there is a universal time, a *cosmic* time, which is the same time for everyone, everywhere, in the universe. At every instant, a cosmic simultaneity exists for Newton. Newton's space is Euclidean; that is, through any point exterior to a line exactly one parallel line can be constructed and those two lines will never meet, all triangles (no matter their size) have an interior angle sum of 180°, and so on. For Newton, space and time were absolutely and uniquely separable. They were, as philosophers like to say, "distinct individuals."

Minkowski changed all that. For him space and time are only relatively separable, and the separation is different for observers in relative motion. For Newton, space and time are the *background* in which physical processes in the world evolve. For Minkowski, spacetime *is* the world.

In a famous philosophical paper[118] by an advocate of the block universe view of reality, we find the words "I . . . defend the view of the world . . . which treats the totality of being, of facts, or of events as spread out eternally in the dimension of time as well as the dimensions of space. Future events and past events are by no means present events, but in a clear and important sense they do exist, now and forever, as rounded and definite articles in the world's furniture." The title of Williams' paper comes from an ancient dilemma stated by Aristotle in his *De Interpretatione*, where he asked a question now classic in philosophy: "Will there be a sea fight tomorrow?"

Aristotle began his famous answer by first posing the following premise: If a statement about some future event is, eventually, shown to be true (or false), then that statement was true (or false) from the moment it was made. Consider, then, the following two assertions: (A) "It is true that there will be a sea fight tomorrow" and (B) "It is true that there will *not* be a sea fight tomorrow." Surely, argued Aristotle, (A) and (B) cannot both be true, but equally surely, one of them must be true. Suppose it is (A) that is true. Then there is nothing that can be done to prevent the sea fight, and so the future is fated. Suppose, however, it is (B) that is true. Then there is nothing that can be done to cause the sea fight, and so the future is fated. The conclusion is the same no matter which assertion is the true one; thus, the future is fated.

---

[117] See, for example, H. Stein, "Newtonian Space-Time," *Texas Quarterly*, Autumn 1967, pp. 174–200; G. Berger, "Elementary Causal Structures in Newtonian and Minkowskian Space-Time," *Theoria* (volume 40), 1974, pp. 191–201; J. Earman and M. Friedman, "The Meaning and Status of Newton's Laws of Inertia and the Nature of Gravitational Forces," *Philosophy of Science*, September 1973, pp. 329–359.

[118] D. C. Williams, "The Sea Fight Tomorrow," in *Structure, Method and Meaning*, The Liberal Arts Press 1951. Donald Williams (1899–1983) was a professor of philosophy at Harvard.

As might be expected, those who like the fatalistic block universe like this conclusion, but, ironically, Aristotle wasn't one of them—he disliked it so much that he struggled to find a way around it. On the other hand, there are philosophers, like Professor Williams (who believed in a fatalistic universe), who reject Aristotle's rejection of his own logic! Professor Williams went so far, in fact, to calling Aristotle's reasoning "a tissue of error" and "swaggeringly invalid." Possibly so, but the philosophical debates over the sea fight question, and the fatalistic (or not) nature of the world, have not ceased to this day.

In an even more famous paper, Professor Williams makes clear his belief that the passage of time is a myth; he poetically declared "the total of world history is a spatio-temporal volume, of somewhat uncertain magnitude, chockablock with things and events."[119] Professor Williams did, indeed, embrace four-dimensional spacetime, and this is demonstrated by the following incredible passage, perhaps his best-remembered words: "It is then conceivable, though doubtless physically impossible, that one four-dimensional area of the time part of the manifold be slewed around at right angles to the rest, so that the time order of that area, as composed by its interior lines of strain and structure, run parallel with a spatial order in its environment. It is conceivable, indeed, that a single whole human life should lie thwartwise of the manifold, with its belly plump in time, its birth at the east and its death in the west, and its conscious stream running alongside somebody's garden path."

Good Lord!

Now, I am willing to admit that Professor Williams probably wrote that wonderful passage mostly for effect,[120] but I ask you—what, if anything, does it *mean*? It is marvelous to read and yet it remains (for me) mysterious.[121] It should come as no surprise that Professor Williams originally presented his papers to the Metaphysical Society of America, rather than to the American Physical Society. But this passage was perhaps not without impact in areas far removed from metaphysics; some years later there appeared a science fiction story[122] that reads as though it had been inspired by Williams. In it, a scientist discovers how to bend his perception of the four dimensions so as to view verticality as duration and duration as verticality. Thus, he is in October while sitting, but when he stands up he is in November! As bizarre as this may seem, such coordinate interchanges actually do occur in the mathematical theory of time machines; we'll see this later, for example, when we discuss Tipler's rotating cylinder time machine.

---

[119] D. C. Williams, "The Myth of Passage," *Journal of Philosophy*, July 1951, pp. 457–472.

[120] In a footnote, Williams sort of admits this when he writes "I should expect the impact of the environment on such a being to be so wildly queer and out of step with the way he is put together, that his mental life must be a dragged-out monstrous delirium." I think this a great understatement.

[121] As it was for some of Williams' fellow philosophers, one of whom bluntly called the 'myth-of-passage' paper "an interesting piece of science fiction": see M. Capek, "The Myth of Frozen Passage: The Status of Becoming in the Physical World," in *Boston Studies in the Philosophy of Science* (volume 2), Humanities Press 1965. Capek's title reflects his view of the block universe as simply a giant refrigerator and so, turning the tables on Williams, we have 'passage' changed to 'frozen passage.' See also note 136.

[122] G. Wolfe, "The Rubber Bend," *Universe 5* (T. Carr, editor), Random House 1974.

By the 1930s the block universe had found a home in pulp science fiction. The block universe view that past and present coexist with the present got dramatic treatment in one story of a high school teacher who invents a "spacetime warp" theory, and who is then tricked by an evil industrialist into implementing it in the form of a gun. The weapon produces incredible effects when it is tested; for example, an allosaurus appears, which we are told is "a carnivorous dinosaur of the Jurassic Age, the most frightful engine of destruction that ever walked the Earth!"[123] At the story's end, the teacher explains what has happened to a crowd of breathless newspaper reporters:

> "Spacetime was warped slightly ... The Einsteinian spacetime continuum buckled ... Because it was superficial, only a little of the past, a little of the future broke through. The folds of the warp distorted spacetime evanescently, erratically skirting the vast gulf where the past lies buried and lightly tapping the vast stores of the future. It is a truism of modern speculative physics that the past and the future exist simultaneously and coextensively in higher dimensions of space. De Sitter has speculated as to the possibility of seeing an event before it happens. It is quite possible, gentlemen. Events of the far future already exist in spacetime."

That 'explains' the dinosaur. In the teacher's words, "You tell me that two men saw an incredible beast. ... They swear it looked like a dinosaur. I think it was a dinosaur, gentlemen. It broke through when the warp tapped the past."

And just 2 years later, Robert Heinlein made world lines the central concept in the first of his many classic tales.[124] The story draws an analogy between a world line and a telephone cable: the beginning and end points in spacetime for the world line of a person (birth and death) are associated with breaks (faults) in a telephone cable. By sending a signal up and down the cable, and measuring the time delay until the arrival of the echo produced by such discontinuities, a technician can both detect and locate the faults. In the same manner, Heinlein's story-gadget sends a signal of unspecified nature up and down a world line and thus locates the birth and death 'discontinuities.' Knowledge of the death date, in particular, causes financial stress among life insurance companies, and an examination of *that* tension (not strange physics) is the fictional point of the story.

And then, 2 years after Heinlein's tale with its serious tone, a far less serious story[125] (featuring an Attila the Hun character who roams up and down the corridors of time kidnapping beautiful women for his harem!), we find an 'editorial' footnote telling its young readers that "scientists—especially the new order of meta-physical scientists—are agreed on the principles of Space-Time. The future is not a thing which *will exist*. Rather it is a thing which *does exist*—all events from the Beginning to the End, exist in a record upon the scroll of Time." This story, itself, was silly, but the block universe metaphysics was up-to-date.

---

[123] F. B. Long, "Temporary Warp," *Astounding Stories*, August 1937.

[124] R. Heinlein, "Life-Line," *Astounding Science Fiction*, August 1939.

[125] R. Cummings, "Bandits of Time," *Amazing Stories*, December 1941.

Somewhat surprisingly, I think, is that even before pulp science fiction embraced the block universe, the concept had already made a deep impression on a broader audience. For example, in a 1928 New York stage play[126] the action alternately takes place in the years 1784 and 1928 and, to explain how that can be, one character (a time traveler) tells another:

> "Suppose you are in a boat, sailing down a winding stream. You watch the banks as they pass you. You went by a grove of maple trees, upstream. But you can't see them now, so you saw them in the *past*, didn't you? You're watching a field of clover now; it's before your eyes at this moment, in the *present*. But you don't know yet what's around the bend in the stream ahead of you; there may be wonderful things, but you can't see them until you get around the bend, in the *future*, can you?"

Then, after this prologue about the stream of time, comes the block universe idea:

> "Now remember, *you're* in the boat. But *I'm* up in the sky above you; in a plane. I'm looking down on it all. I can see *all at once* the trees you saw upstream, the field of clover that you see now, and what's waiting for you around the bend ahead! *All at once!* So the past, present, and future of the man in the boat are all *one* to the man in the plane."

Then, finally, the obvious theological conclusion: "Doesn't that show how all Time must really be one? Real Time—real Time is nothing but an idea in the mind of God!"

To end this section, the block universe conception was cleverly used by one science fiction fan who argued in support of time travel, in reply to another fan how had claimed that a failure of mass/energy conservation was fatal to the plausibility of time travel. Their exchange began with a letter to the editor at *Astounding Stories* in November 1937, written in response to a recent story[127]:

> "Let us say that there is, at a certain time, 'x' amount of matter in the Universe, and 'e' amount of energy. Then if a man of 'a' mass travels backward in time to this particular instant aforementioned, the total amount of matter is thus 'x' plus 'a', while if no other such mass changing occurrences take place, the amount of matter in the future is 'x' minus 'a'. Only a corresponding loss and gain respectively in the amount of energy could explain this conservation of energy, advocates [of time travel] say what they may. But you can't rob or add energy to a Universe nilly-willy! Or perhaps time doesn't enter in on the matter. Perhaps you can add matter in a Universe provided you take it away on some future date."

This fan's concern clearly made an impression on science fiction writers, and the case for conservation of energy is stated in many of the time travel stories that appeared after the publication of this letter.[128]

---

[126] "Berkeley Square" by J. L. Balderson. This play was made into a 1933 movie of the same name, and again in 1951 as the film *I'll Never Forget You*.

[127] O. Saari, "The Time Bender," *Astounding Stories*, August 1937 (see also note 137 in Chap. 1).

[128] Examples include the novels *Lest Darkness Fall* (Henry Holt 1941) by L. Sprague de Camp, and *The Time Hoppers* (Doubleday 1967) by Robert Silverberg.

A reply was soon received by the magazine in a letter (January 1938) from another fan:

> "[A recent letter] implies that the idea of time travel is incompatible with the law of conservation of mass and energy. I believe [the] reasoning is wrong [and that the] difficulty lies primarily in the assumption that a body moved in time is transported into a different Universe. According to Einstein, time and the three normal dimensions are so related as to form a continuous, inseparable medium we call the spacetime continuum. Time is in no way independent of the other components of our Universe. Hence a fixed mass [a time traveler and his machine] moved in time is by no means lost from the Universe, the action being analogous to a shift along any other dimension."

The block, or frozen, universe of Minkowski is clearly reflected in those words.[129]

2.7 Philosophical Implications of the Block Universe

> "Is the future all settled beforehand, and only waiting to be 'pushed through' into our three-dimensional ken? Is there no element of contingency? No free will? I am talking geometry, not theology."[130]

I should tell you now that, despite the enthusiastic embrace of the block universe by Williams and others (including Einstein), there are those who have been harsh in their criticism of Minkowski's spacetime. The major philosophical problem with the block universe interpretation of four-dimensional spacetime is that it looks like fatalism disguised as physics. It seems to be little more than a mathematician's proof of a denial of free will dressed up in geometry. One philosopher illuminated this concern with the following story, one that vividly illustrates the compelling need many humans have to deny a fatalistic world:

> "In a moving picture version of *Romeo and Juliet*, the dramatic scene was shown in which Juliet, seemingly dead, is lying in the tomb, and Romeo, believing she is dead, raises a cup containing poison. At this moment an outcry from the audience was heard: 'Don't do it!' We laugh at the person who . . . forgets that the time flow of a movie is unreal, is merely the unwinding of a pattern imprinted on a strip of film. Are we more intelligent than this man when we believe that the time flow of our actual life is different? Is the present more than our cognizance of a predetermined pattern of events unfolding itself like an unwinding film?"[131]

---

[129] In the context of mathematical physics (*not* science fiction) it has been shown that time travel does *not* imply any fatal violation of conservation of energy. See, for example, J. L. Friedman *et al.*, "Cauchy Problem in Spacetimes with Closed Timelike Curves," *Physical Review D*, September 15, 1990, pp. 1915–1930, and D. Deutsch, "Quantum Mechanics Near Closed Timelike Lines," *Physical Review D*, November 15, 1991, pp. 3197–3217.

[130] The lament of Victorian physicist Oliver Lodge (1850–1940) in his essay "The New World of Space and Time," *Living Age*, January 1920.

[131] H. Reichenbach, *The Direction of Time*, University of California Press 1956, p. 11.

Most people in the Western world would answer *yes* to Reichenbach's question. Most people do find Omar Khayyam's *Rubaiyat* to be a beautiful poem, yes, but still they reject its fatalistic message: "And the first Morning of Creation wrote/What the Last Dawn of Reckoning shall read." Indeed, William James quoted these very words in his 1884 address to the students of the Harvard Divinity School when he argued against fatalism and the block universe.

Besides fatalism, another reason for the stinging words by critics of Minkowski's spacetime is that, in it, events don't *happen*—they just *are*. That is, there seems to be no temporal process of *becoming* in Minkowski's spacetime. Everything is already there and, as what we perceive to be the passing of time occurs, we simply become conscious of ever more of Minkowski's "world points," or events, that lie on our individual world lines. Hermann Weyl (1885–1955), a German mathematical physicist who in his last years was a colleague of Einstein and Gödel at the Institute for Advanced Study in Princeton, expressed this very interpretation in words that have become famous, words that sound very much like those of Wells' Time Traveller: "The objective world simply *is*, it does not *happen*. Only to the gaze of my consciousness, crawling upward along the life line of my body [Minkowski's world line], does a section of the world [spacetime] come to life as a fleeting image in space which continuously changes in time [creating what we call the *now* or the *present*]."[132]

Weyl was skillful in finding poetic ways to express the world line view of reality, but not everybody is convinced by the poetry because it seems to deny the common sense idea of time 'flowing,' of temporal passage; it effectively says time is mind-dependent, a mere *illusion*, as the time traveler in "Berkeley Square" declared (note 126). One philosopher who was particularly opposed to Weyl's view was the British-American academic Max Black (1909–1989), and he expressed his opinion in no uncertain terms: "The picture of a 'block Universe,' composed of a timeless web of 'world-lines' in four-dimensional space, however strongly suggested by the theory of relativity, is a piece of gratuitous metaphysics."[133] Another philosopher who was unhappy with Weyl's view of the block universe was just as blunt: "While philosophers may be forgiven intellectual extravagances of this kind, I think it is a pity when they receive encouragement from theoretical physicists."[134]

Weyl's views had supporters, too, however. Consider, for example, the Time Traveller's speech to his friends at the fateful dinner party that opens *The Time*

---

[132] H. Weyl, *Philosophy of Mathematics and Natural Science*, Princeton University Press 1949, p. 116. Sir James Jeans had already said the same, somewhat less elegantly, in his 1935 Sir Halley Stewart Lecture: "The tapestry of spacetime is already woven throughout its full extent, both in space and time, so that the whole picture exists, although we only become conscious of it bit by bit—like separate flies crawling over a tapestry ... A human life is reduced to a mere thread in the tapestry." Jeans then immediately *rejected* this fatalistic view: see his *Scientific Progress*, Macmillan 1936, p. 20.

[133] From a book review in *Scientific American*, April 1962, pp. 179–185.

[134] H. A. C. Dobbs, "The 'Present' in Physics," *British Journal for the Philosophy of Science*, February 1969, pp. 317–324.

Machine: "There is no difference between Time and any of the three dimensions of Space except that our consciousness moves along it . . . here is a portrait of a man at 8 years old, another at fifteen, another at seventeen, another at twenty-three, and so on. All these are evidently sections, as it were, Three-Dimensional representations of his Four-Dimensional being, *which is a fixed and unalterable thing* [my emphasis]." Remember, these words were written in 1895, 13 years before Minkowski and his world lines, and of course decades before Weyl's famous words.

Wells' passage made a considerable impression on at least one well-known physicist of the time, who references it in his early book on relativity.[135] And in another book on relativity, published the same year, we find the same interpretation of Minkowski's spacetime as a block universe: "With Minkowski, space and time become particular aspects of a single four-dimensional continuum . . . All motional phenomena . . . become timeless phenomena in four-dimensional space. The whole history of a physical system is laid out as a changeless whole."[136]

The claim that time is an illusion has some thought-provoking implications concerning the concepts of omniscience and free will, concepts that occur in any discussion of time travel. Some old theology on God's omniscience, as discussed in Aquinas' *Summa Theologiae*, is seemingly lent at least some support by Minkowski's spacetime: "Now although contingent events come into actual existence successively, God does not, as we do, know them in their actual existence successively, but all at once; because his knowledge is measured by eternity, as is also his existence; and eternity which exists as a simultaneous whole, takes in the whole of time . . . Hence all that takes place in time is eternally present to God." Somewhat paradoxically, however, Aquinas did make a distinction between past and future. In that same work he declares that "God can cause an angel not to exist in the future, even if he cannot cause it not to exist while it exists, or not to have existed when it already has." For Aquinas, then, whereas the past is rigid and unchangeable, the future is plastic, which is *not* the block universe view of spacetime.

As one theologian has observed,[137] this does not mean that Aquinas thought God had to view all events simultaneous with all others.[138] Rather, our theologian says that Aquinas could have thought of the relationship between God and events as being similar to that between the center of a circle and all the points on the circumference. That is, each point on the circumference has its own identity, coming before and/or after any other point, but the center is related to each and every point on the circumference in precisely the same way. The center, then, is 'eternity' and the circumference is the temporal series ('one thing after another') of reality. Saying that God is *eternal* is thus very different from saying he is *everlasting*. The first means outside of time, whereas the second means he is a temporal entity but has neither beginning nor end.

---

[135] L. Silberstein, *The Theory of Relativity*, Macmillan 1914, p. 134.

[136] E. Cunningham, *The Principle of Relativity*, Cambridge University Press 1914, p. 191. The use of the words *timeless* and *changeless* explain the characterization of the block universe as being *frozen* (in note 121).

[137] W. L. Craig, "Was Thomas Aquinas a B-Theorist of Time?" *New Scholasticism*, Autumn 1985, pp. 475–483. For the B-theory of time, look back at the discussion in the first section of this chapter.

[138] A science fiction story by Norman Spinrad, "The Weed of Time" (*Alchemy and Academe*, Doubleday 1970) graphically describes what a nightmare that could be!

Our theologian supports the first interpretation, invoking Aquinas' own words from *Summa Contra Gentiles*: "The divine intellect, therefore, sees in the whole of its eternity, as being present to it, whatever takes place through the whole course of time. And yet what takes place in a certain part of time was not always existent. It remains, therefore, that God has a knowledge of these things that according to the march of time do not yet exist."

The issue of God's eternity and his place in spacetime has long been a hot topic among theologians with a scientific inclination. Practically every issue of the learned journal *Religious Studies*, for example, carries an article on the subject, often invoking relativity theory to support some argument. The Bible, itself, can be a confusing guide on this matter. For example, consider the Old Testament story of King Ahab (First Kings 21). Ahab, King of Sumeria, coveted Naboth's vineyard, but Naboth would not sell. The King retreated, but his wife Jezebel arranged for Naboth's downfall and judicial murder and thus caused the arrival of all his property into her husband's hands. This angered God, who commanded Elijah to prophesy disaster on Ahab's house. Ahab responded with sackcloth, and at that God shifted the disaster to the house of Ahab's son. The point, here, is that God, declared to be omniscient, seems to have been *surprised* at Ahab's penitence. God is aware of everything in this tale, but only as it happens. That is, God's knowledge is subject to growth. This Hebrew concept of God as a participant in history is at odds with the contemporary Christian conception of divine knowledge of all that has been, all that is, and all that will be, a view which has its own Biblical support (for divine eternality). For example, Malachi 3:61 ("For I am the Lord, I change not"), and James 1:17 ("the Father ... with whom is no variableness").

When *The Time Machine* was serialized in the *New Review*, it included a passage that does not appear in the now classic version of the story in which the Time Traveller explains his view of the connection between omniscience and the block universe to his dinner guests:

> "I'm sorry to drag in predestination and free-will, but I'm afraid those ideas will have to help ... Suppose you knew fully the position and properties of every particle of matter, of everything existing in the Universe at any particular moment of time: suppose, that is, that you were omniscient. Well, that knowledge would involve the knowledge of the condition of things at the previous moment, and at the moment before that, and so on. If you knew and perceived the present perfectly, you would perceive therein the whole of the past. If you understood all the natural laws the present would be a complete and vivid record of the past. Similarly, if you grasped the whole of the present, knew all its tendencies and laws, you would see clearly all the future. To an omniscient observer there would be no forgotten past—no piece of time as it were that had dropped out of existence—and no blank future of things yet to be revealed ... Present and past and future would be without meaning to such an observer ... He would see, as it were, a Rigid Universe filling space and time ... If 'past' meant anything, it would mean looking in a certain direction, while 'future' meant looking the opposite way."

Wells' "Rigid Universe" certainly sounds like the block universe, and he (or least, the Time Traveller) seems to have believed that it held important implications for the concept of free will.

The 'Rigid Universe' got an interesting science fiction treatment in a story[139] that imagined an event in the present that occurs 'before it should' (a heart patient learns that her obituary notice will be in next week's *New York Times* when that paper arrives 'early'). As one character explains to the sister of the lady who is soon to die, "The future mustn't be changed . . . For us the events of . . . the future are as permanent as any event in the past. We don't dare play around with changing the future, not when it's already signed, sealed and delivered in that newspaper. For all we know the future's like a house of cards. If we pull one card out, say your sister's life, we might bring the whole house tumbling down. You've got to accept the decree of fate . . . You've got to."

With Einstein's discovery of the *relativity of simultaneity*,[140] we run into the question of 'How can there be any sense to the concept of divine, universe-wide knowledge in a four-dimensional spacetime?' That's because in some frames of reference it is possible for event A to be observed before event B, whereas in other frames the temporal order could be reversed, and so some theological questions prompted by spacetime physics are: 'What is God's frame of reference if he is to be actively involved in human affairs? Could God have a special frame of reference in which he is exempt from the relativity of simultaneity, a frame in which he imposes an absolute order on the sequence of becoming of events? Does it make any sense, that is, to say God enjoys what might be called 'divine immediacy'? And if so, what should we think of a God who follows rules of nature different from those that govern all he is supposed to have made?'

Theologians have debated questions like these for decades, and surely will continue to do so for many more decades to come. Alas, I suspect that physicists who study time travel have either been unaware, unimpressed, or just plain uninterested. That's too bad, because one doesn't have to be religious to appreciate the pure intellectual challenges presented by such questions. For example, consider the following debate between two philosophers, one who believes free will and divine foreknowledge are not compatible, and another who thinks the first has made a fundamental error in blurring the distinction between changing and affecting the past. (This distinction is of *great* importance in any discussion of time travel.) This second philosopher presented some of his arguments in terms of a time traveler to the past[141]:

---

[139] R. Silverberg, "What We Learned From This Morning's Newspaper," *Infinity Four*, November 1972.

[140] This refers to the discovery that two events, which occur simultaneously for one observer in a spacetime, may not be simultaneous for another observer in the same spacetime. This will be discussed in more detail in the next chapter.

> "Consider the following. Parsons (P) has invented a special machine which allows him to go back in time. He enters the machine in 1986 and finds himself in the presence of or, perhaps better, observing, Quigly (Q) in 1876. P is an authority on Q, and knows immediately the situation Q is in. Not only that, but he remembers reading about the particular decision or act which Q made in that situation. Thus one might argue that from P's perspective what Q decides is as if already done. It is not already done, since P is standing there waiting for Q to do it. He has gone back in time. Yet from P's perspective, which is of one come back from the future, it is as if already done, since he knows what Q does decide. Since P strongly believes in the unalterability of the past, it is not within Q's power to do something other than what Q in fact does in that situation. From Q's perspective his decision is not already made nor is the action taken, so that it is in his power at that time to do either x or y. From his perspective, that he will do x rather than y is indeterminate; it is not yet done, though at the same time he can grant that P knows what he will do because for him it is as if he has already done it."

The first philosopher doesn't buy any of this, and dismisses it with "It should be abundantly clear . . . that the fact that such stories are in some way imaginable and intuitively graspable says nothing about their logical coherence." Given the interest among modern physicists in time travel, however, I think the first philosopher wouldn't write that today.

One possible reply to all of these theological issues that spacetime physics prompts can perhaps be found in a paper[142] (written by a philosopher and two mathematicians) that describes a five-dimensional spacetime in which the fifth dimension is initially given the provocative label of the 'eternity' axis. But then the authors lost their nerve and elected to rename it 'anti-time.' It is interesting to note that pulp science fiction anticipated that terminology by decades, as in one story[143] we read "Beyond the fourth there is a fifth dimension . . . Eternity, I think you would call it. It is the line, the direction perpendicular to time." For some, the eternity axis would appear to be perfect to serve as the temporal dimension for God, an axis distinct from the time axis of mere mortals.

The idea of supernatural beings existing outside of mortal time is an old one in theology, and it can also be found in secular literature long before science fiction got hold of it. For example, in the first act of Lord Byron's 1821 poem *Cain*, the fallen angel Lucifer tells Cain and his wife that

---

[141] For the complete exchange between these two philosophers, see W. Hasker, "Foreknowledge and Necessity," April 1985, pp. 121–157, B. Reichenbach, "Hasker and Omniscience," January 1987, pp. 86–92, and W. Hasker, "The Hardness of the Past: A Reply to Reichenbach," July 1987, pp. 337–342, all in the journal *Faith and Philosophy*. Hasker is the 'first' philosopher, and Reichenbach is the 'second' one. See also D. P. Lackey, "A New Disproof of the Compatibility of Foreknowledge and Free Choice," *Religious Studies*, September 1974, pp. 313–318.

[142] J. G. Bennett *et al.*, "Unified Field Theory in a Curvature-Free Five-Dimensional manifold," *Proceedings of the Royal Society of London A*, July 1949, pp. 39–61. A theological interpretation is given in G. Stromberg, "Space, Time, and Eternity," *Journal of the Franklin Institute*, August 1961, pp. 134–144.

[143] L. A. Eshbach, "The Time Conqueror," *Wonder Stories*, July 1932.

With us acts are exempt from time, and we
Can crowd eternity into an hour,
Or stretch an hour into eternity.
We breathe not by a mortal measurement,
But that's a myst'ry.

Before Minkowski, the debates over fatalism (as in Silverberg's story in note 139) and free will had been the exclusive province of philosophers, theologians, and lawyers (if a person has no control over his or her actions, then can we morally and ethically punish that person if those actions happen to be criminal?[144]). After Minkowski, the physicists (at least a few of them) joined the debates. According to one philosopher (note 118) the major motivation driving these debates is "the age-old dread that God's foreknowledge of our destiny can in itself impose the destiny upon us." The implication is, of course, that God is 'outside of time' and so can take in the entire Minkowskian block universe at a glance (hence his foreknowledge).

The relativistic view of the universe as a timeless four-dimensional spacetime seems to provide scientific, mathematical support for the conclusion that not only is the past fixed, but so is the future. Does that mean the future is what it will be—and if so, then why bother agonizing over the many apparent decisions each of us faces every day? If the future will be what it will be, then Christian theologians are left with the puzzling task of explaining what could possibly be meant by the Biblical exhortation (Deuteronomy 30:19) "I call Heaven and Earth to record this day against you, that I have set before you life and death, blessing and cursing; therefore *choose* [my emphasis] life, that both thou and thy seed may live."

This issue has bothered philosophers for a very long time. The so-called Master Argument (the name reflects its supposed invulnerability to rebuttal), for example, comes down to us from its origins in ancient times, in the *Discourses* of the first century A.D. Roman Stoic philosopher Epictetus. That argument can be summarized[145] as follows:

1. The future follows from the past;
2. The past is unchangeable;
3. What follows from the unchangeable is unchangeable;

Therefore,

4. The future is unchangeable.

This certainly does seem to be fatalistic, in effect arguing that all events in a block universe spacetime are recorded in a 'Book of Destiny.' Since ancient times many great works of literature have adopted that view, recounting tales of the foretold fates of men, such as Sophocles' *Oedipus*. It is, in a block universe, as though our conscious experience of the world is no different from that of the man watching the projected film images of *Romeo and Juliet*.

---

[144] For more on this, in the context of time travel, see the penultimate question in the *For Future Discussion* questions at the end of this chapter.

[145] See, for example, the two papers by R. L. Purtill, "The Master Argument," *Apeiron*, May 1973, pp. 31–36, and "Foreknowledge and Fatalism," *Religious Studies*, September 1974, pp. 319–324.

That view is the central issue in the early sixth century A.D. Roman philosopher Boethius' influential *De Consolatione Philosophiae* (circa A.D. 500) which was written during a year of imprisonment before his execution for treason; perhaps he wondered during that year if his fate could have been anything different. Certainly he must have taken some consolation in fatalism, but in fact he tried to argue that God's vision of *all* temporal reality does not limit the freedom to act. According to Boethius, "The expression 'God is ever' denotes a single Present, summing up His continual presence in all the past, in all the present . . . and in all the future." That is, God sees in one timeless and eternal moment all that has been and will be freely chosen.[146]

When the fourteenth century English poet Geoffrey Chaucer prepared a translation of *Consolatione* he was obviously inspired by it when he wrote his very long, famous poem (*Troilus and Criseyde*) on the nature of love (Book IV.140):

Some say "If God sees everything before
It happens—and deceived He cannot be—
Then everything must happen, though you swore
The contrary, for He has seen it, He."
And so I say, if from eternity
God has foreknowledge of our thoughts and deed,
We've no free choice, whatever books we read.

Two modern, purely philosophical rebuttals[147] to Chaucer, however, argue that his poetry misstates Boethius' philosophy when Troilus declares that divine foreknowledge is incompatible with free will. That is, in their view God's omniscience (a fundamental teaching in the theistic religions of Christianity, Judaism, and Islam) *is* compatible with free will (also a fundamental belief in those same religions). Both of these scholarly papers, though, depend much more on the nuances of grammar than most physicists will like.

The connection between spacetime physics and free will was made explicitly by the philosopher who wrote "For philosophers in either field, philosophy of science and philosophy of religion are too often viewed as mutually irrelevant . . . This is unfortunate, because sometimes the problems can be quite parallel and a consistent resolution is required. One especially intriguing case in point concerns, in

---

[146] In his *The Sirens of Titan*, a 1959 novel meant to be a parody of God's omniscience, Kurt Vonnegut gave the curious name of *chrono-synclastic infundibulated vision* to God's power to see the past and future.

[147] G. I. Mavrodes, "Is the Past Unpreventable?" April 1984, pp. 131–146, and A. Plantinga, "On Ockham's Way Out," July 1986, pp. 235–269, both in *Faith and Philosophy*.

Fig. 2.2 The common view of time



philosophy of science, the possibility of … time travel and, in philosophy of religion, the relationship between divine foreknowledge and human freedom."[148]

That philosopher could well have included science fiction writers in his group of people interested in both spacetime physics and free will. In one story,[149] for example, a man in the twenty-fifth century is about to travel back into the past to escape criminal prosecution. He is aked where he'd like to go, and he replies "I do not understand the paradoxes—what if I choose to build gravity-deflectors in Ancient Rome?" When he is told (correctly) that he couldn't do that because it didn't happen, he persists: "But if I can choose any period, it means I can alter history at will—which presumes that the present can also be changed." Then, at last, he gets the explicit answer that bothers nearly everyone: "The real answer is that in the final analysis your decision to choose a certain time period is already made, and the things you will do [in the time traveler's personal time] are already determined. Free will is an illusion; it is synonymous with incomplete perception." The same idea appears in another tale (note 57); when one character says, "What you are saying is that the future is fixed, and that you can read it, in every essential detail," the response is "Quite right … both those things are true."

However, no matter how hard we try—and by *we* I include even those physicists and philosophers who embrace the block universe with its support of time travel to the past—it is very difficult to break free of the view of time as shown in Fig. 2.2. That is, as the passage of time up to the present or *now* (with all to the left of that instant as the past), while to the right of the *now* we have multiple possible futures (depending on our free will choices). Lying to the side of all that (in our thoughts and imaginations) are all that 'might have been' if we had made different choices than we did at earlier times in the past.[150]

---

[148] W. L. Craig, "Tachyons, Time Travel, and Divine Omniscience," *Journal of Philosophy*, March 1988, pp. 135–150. Tachyons are hypothetical faster-than-light particles that theoretically travel backwards through time. They will be discussed in Chap. 5.

[149] W. Kubilius, "Turn Backward, O Time," *Science Fiction Quarterly*, May 1951.

With all that said, even if events are really laid out in the spatial and temporal web that constitutes the four-dimensional block universe, there still remains the great mystery of why we see them unfold in the particular sequence that we do. Why not in reverse order? Why, indeed, do we see what we call *time* run from what we call the past to what we call the future and, indeed, what do we really mean by *past* and *future*? As you'll see in the next chapter, these are not easy questions, and nearly everybody who has thought about them believes we are not yet even close to knowing the answers.

On that perhaps gloomy note, it seems appropriate to end here with a few more words from St. Augustine's *Confessions*, with words that follow those that helped open this chapter: "I confess to you, Lord, that I still do not know what time is. Yet I confess too that I do know that I am saying this in time, that I have been talking about time for a long time, and that this long time would not be a long time if it were not for the fact that time has been passing all the while. How can I know this, when I do not know what time is? Is it that I do know what time is, but do not know how to put what I know into words? I am in a sorry state, for I do not even know what I do not know!"[151]

2.8 For Further Discussion

In the comics one of Superman's more interesting adversaries is Mr. Mxyzptlk (pronounced *mix-yez-pitle-ick*), a being with seemingly magical powers from the Land of Zrfff in the fifth dimension. Mr. Mxyzptlk's powers are not really because of magic, however, but are 'merely' the result of his hyperspace world with its extra dimension. Mr. Mxyzptlk, for example, in one of his misadventures with Superman in 1954, begins selling a

(continued)

---

[150] Figure 2.2 is based on a similar one in C. K. Raju, "Time Travel and the Reality of Spontaneity," *Foundations of Physics*, July 2006, pp. 1099–1113.

[151] There is another view of time even darker than St. Augustine's, which denies the existence of both future and past, and doesn't offer us much either for that special moment we call the present (or *now*). This view, called *presentism*, was hauntingly expressed in some lyrics I heard in the final episode of the second season (2015) of the HBO series *True Detective*: "There is no future/There is no past/In the present nothing lasts." Now *that* is depressing! Still, there are philosophers who believe even this view can support time travel: see S. Keller and M. Nelson, "Presentists Should Believe in Time-Travel," *Australasian Journal of Philosophy*, September 2001, pp. 333–345.

newspaper called the *Daily Mpftrz* in competition with the *Daily Planet*. Unlike a traditional newspaper that reports what *has* happened, the *Daily Mpftrz* (your guess is as good as mine!) prints what *will* happen. As Mr. Mxyzptlk says, "You see, as a resident of the fifth dimension, I can get all the news I want from the *fourth* dimension!" The science editor at the *Daily Planet* explains the meaning of that to his boss, Perry White: "That's right, Mr. White . . . many physicists consider *time* the fourth dimension . . . so if Mr. Mxyzptlk can travel from the fifth dimension to our three-dimensional world, he most likely *is* able to see the future!" (This leaves unanswered the question of *why* he continues to challenge Superman when he knows he will always be defeated—*as he always is*!) Presumably a five dimensional world would have our three spatial and one temporal dimension (for a total of four), and so the question now is: what is the nature of the additional (fifth) dimension? Is it spatial or is it temporal? (There is a brief appearance of the fifth dimension in the 2014 movie *Interstellar*, but we aren't told much of anything about its possible structure.) Discuss and compare the world of four space dimensions and one time dimension, with the world of three space and *two* time dimensions. (In Chap. 5 we'll discuss a possible connection between two-dimensional time and time travel.)

In the text it is stated that "If A and B are mutually causative, then 'A causes B' coupled with 'B causes A' seems to lead to 'A causes A.'" Suppose, however, that we imagine two adjacent sunken pools of water, **a** and **b**, on the same horizontal surface, with each pool filled to the brim. An overflow from one pool will flow into the other pool. Now, define the events A and B as 'A is the overflow of pool **a**' and 'B is the overflow of pool **b**.' Thus, A causes B and B causes A. Does the conclusion 'A causes A' make physical sense in this specific case? Discuss at length.

When reading A. C. Clarke's story "Technical Error" (see note 99), we learn that a rotation through 4-space *inverts* "the unlucky Nelson." The 'solution' to this awkward situation is to flip Nelson through 4-space a second time and so back to 'normal.' (When *Thrilling Wonder Stories* reprinted this tale in June 1950, after its original publication in 1946, the title was changed to the more appropriate "The Reversed Man.") Clarke may have missed an

(continued)

important technical ‘detail,’ however, in that when first flipped through 4-space *everything* inverts, and so matter becomes anti-matter and Nelson would have instantly been annihilated in a 100 % conversion of matter to energy (that is, the flipped Nelson would have initiated a very large explosion). Compare this to Alice’s concern in her flipped world (Lewis Carroll’s *Through the Looking Glass*) when she wonders “Perhaps Looking-glass milk isn’t good to drink.” Explain why Lewis Carroll certainly was *not* thinking of matter/anti-matter explosions when he wrote his novel. What *do* you think he might have had in mind?

A time travel story, even earlier than Clarke’s, that uses spacetime ‘rotations,’ was authored by Edmond Hamilton (1904–1977), one of the pioneering pulp fiction writers. In his “The Man Who Saw the Future” (*Amazing Stories*, October 1930), a man is hauled before the Inquisitor Extraordinary of the King of France to explain his mysterious disappearance, and subsequent reappearance, in an open field, amid thunderclaps and in plain sight of many onlookers. As the story unfolds, we learn that the man was transported five centuries into the future, from A.D. 1444 to 1944, by scientists working in twentieth-century Paris. The thunderclaps were produced by spacetime ‘rotations,’ as the atmospheres of 1944 and 1444 were reversed. A skeptical Inquisition naturally finds this tale preposterous and the first time traveler is burned at the stake as a sorcerer. Can you think of *why* such ‘atmospheric swaps’ might produce thunderclaps?

A trip around a Möbius strip reverses the ‘handedness’ of a plane figure (left and right are swapped). You can see this for yourself by making a Möbius strip, and then sliding an arrow (pointing *across the width* of the strip) around the strip. (Cut a notch in the side of the strip to mark the starting point, with the arrow pointing at the notch.) When you get back to the notch, the arrow will point *away* from the notch. Notice that the arrow never left the surface of the strip, or crossed any ‘weird’ boundary. Then, read H. G. Wells’ short story “The Plattner Story” and comment on its use of ‘handedness.’

The *autoinfanticide paradox*, which results when a time traveler tries to kill his younger self, continues to fascinate both physicists and philosophers, and papers regularly appear in the scholarly literature on the topic: see, for example, Kadri Vihvelin, "What Time Travelers Cannot Do," March 1996, pp. 315–330 (which introduces Suzy the time traveler); Ira Kiourti, "Killing Baby Suzy," June 2008, pp. 343–352; Peter B. M. Vranas, "What Time Travelers May Be Able to Do," August 2010, pp. 115–121; and Joshua Spencer, "What Time Travelers Cannot *Not* Do (but are responsible for anyway)," October 2013, pp. 149–162, all in *Philosophical Studies*. All deal with an issue that is psychologically fascinating: *moral responsibility*. Spencer, in particular, opens with this definition: Someone is morally responsible for an action *only* if she could have done otherwise. As he goes on to write, "If I have been attacked and both of my legs have been broken, then it seems illegitimate to criticize me for failing to run away; I could not have done otherwise." And yet all of these papers are on a point that (I think) physicists would soon lose interest in: is the question 'If Suzy is a time traveler, can Suzy kill baby Suzy, given that Suzy doesn't kill baby Suzy?' the same question as 'If Suzy is a time traveler, can Suzy kill baby Suzy, given that Suzy is now alive?' The answer to the first question is, from pure logic, NO, while the answer to the second question is just bit squishier: it all depends on what the word *can* means. For the second question, Suzy *can* kill baby Suzy if she has a weapon (knife, gun, poison, etc.) and she is in the past next to baby Suzy, but it is just that she doesn't because otherwise Suzy wouldn't be alive now (which is a given). Such debates seem unlikely to produce any insights into the physics of time travel. Compare this situation to the old schoolboy conundrum "What happens when an irresistible force meets an unmovable object?', which is a *self-inflicted* 'paradox.' That is, the words *irresistible* and *unmovable* are mutually exclusive and so, used this way, it should be no surprise that we have a conflict. Are the two time travel questions above, concerning Suzy, confusing through a similar mushy use of grammar? Or are they deeper than that? Vigorously defend your position.

In addition to H. G. Wells, another nineteenth-century writer who was highly influential in bringing the fourth-dimension out of academia and into public consciousness was the mathematician Charles Howard Hinton (1853–1907). Hinton was no angle-trisecting crank, having earned an M.A. at Oxford, an appointment in the mathematics department at Princeton, and then another at the University of Minnesota. Later, with the help of the eminent astronomer

(continued)

Simon Newcomb, he obtained a position at the Naval Observatory in Washington, D.C., and was on the staff of the United States Patent Office at the time of his sudden death. Hinton was a man to be taken seriously. His first published essay “What Is the Fourth Dimension?” appeared in 1880, and then in book form in 1884 as part of his *Scientific Romances* (a phrase used by Hinton before it became associated with Wells’ science fiction many years later). That book received a generally favorable review in *Nature* (March 12, 1885, p. 431). At one point he wrote “We might then suppose that the matter we know extending in three dimensions has also a small thickness in the fourth dimension,” an idea that was used a few years later by the well-known British mathematician W. W. Rouse Ball (1850–1925) in an attempt to explain gravity. Hinton was extremely inventive, and he also proposed four-dimensional-space models for static electricity. Find out more about Hinton’s life and work: a good source to start with is *Speculations on the Fourth Dimension: Selected Writings of Charles H. Hinton* (R. Rucker, editor), Dover 1980. Take a look, too, at J. E. Beichler, “Ether/Or: Hyper-space Models of the Ether in America,” in *The Michelson Era in American Science 1870—1930* (S. Goldberg and R. H. Stuewer, editors), American Institute of Physics 1988.

Chapter 3
The Physics of Time Travel: Part I

". . . within forty-eight hours we had invented, designed, and assembled a chronomobile. I won't weary you with the details, save to remark that it operated by transposing the seventh and eleventh dimensions in a hole in space, thus creating an inverse ether-vortex and standing the space-time continuum on its head."

—almost certainly *not* the way to build a time machine[1]

3.1 The Direction of Time

> "Of all the problems which lie on the borderline of philosophy and science, perhaps none has caused more spilled ink, more controversy, and more emotion than the problem of the direction of time . . . [T]he main problem with 'the problem of the direction of time' is to figure out exactly what the problem is or is supposed to be!"[2]

Before we start talking about the physics of time travel, let me say a few more words on time itself, in a way slightly less metaphysical that was the discussion in the previous chapter (which is why I'm writing this *here*, in a chapter with an increased emphasis on the analytical). When we speak of journeying to either the future or the past, we are implicitly making a distinction in the direction of the time traveler's trip. But does time actually have a *direction*? Is there an *arrow* that points the way? The answer seems obvious: *of course* time has a direction. After all, everybody 'knows' it flows from past to future. There is a curious language problem here, however, because we also like to say the present recedes into the past, which implies a 'flow' in the opposite direction, from future to past. Well, despite this snarled syntax, can we at least distinguish past from future, whichever way time flows?

---

[1] L. Sprague de Camp, "Some Curious Effects of Time Travel," in *Analog Readers' Choice*, Dial 1981.

[2] See note 54 in Chapter 2.

© Springer International Publishing AG 2017

P.J. Nahin, *Time Machine Tales*, Science and Fiction,
DOI 10.1007/978-3-319-48864-6_3

This would seem to be an important question to answer because for the phrases *flow of time* and *direction of time* to have any objective meaning at all, it must be somehow possible to identify a difference between past events and future ones. The special moment at which that distinction occurs is known as the *now* or the *present* and, as events make the transition associated with that distinctive difference, between past and future, we say that the *now* (the present) moves or flows. Philosophers—and science fiction writers and physicists, too, who after all are human beings with human senses like everybody else—call this common feeling that we all have, of the passage of time, the *psychological arrow of time*. One philosopher gave an amusing (tongue-in-cheek) gastronomical interpretation of the moving *now* as follows:

> "New slices of salami are continually being cut from a nonexistent chunk of salami called the future. The *present* is the slice on top of the pile. The past are the pieces beneath this, and even though they are not present they still continue to exist in the same way that the top slice of salami does. . . . This [concept] faces humiliation before the embarrassing question of how fast the pile of salami slices grows."[3]

The 'moving now' does present a problem for physicists because there is nothing in the laws of physics that marks the present moment as unique, and therefore nothing that reflects a 'flow' of time, nothing that models the reality of a 'moving now' becoming part of the past and the events of the future becoming, successively, the new 'now.' As a philosopher wrote long before time travel became a serious topic in the physics literature, "Talk of the flow of time or the advance of consciousness is a dangerous metaphor that must not be taken literally."[4]

What that philosopher may well have had in mind is that all events in the block universe simply have coordinates in spacetime, and there is nothing corresponding to 'have been' (past), 'are' (present), or 'will be' (future). There is no 'moving now' in the block universe except for its subjective presence in our conscious minds. All we can say from physics is that events are ordered in an earlier/later sequence, and in fact, even that relatively weak condition holds only for *causally* related events.[5] The relativistic, four-dimensional block universe view of spacetime that so many physicists (including Einstein) so dearly love seems to have no room for an objective theory of the *flow* of time. And yet, even for those same physicists, there is a powerful psychological sense that time *does* flow. But are they mistaken? It is a fact that, with not just a little irony, Gödel (the 'discoverer' of time travel) was convinced that the possibility of a block universe spacetime with CTLs/CTCs

---

[3] R. Gale, "Some Metaphysical Statements About Time," *Journal of Philosophy*, April 25, 1963, pp. 225-237. For many, this analogy may well bring to mind a pile of baloney rather than one of salami (and I think this was Gale's intention).

[4] J. J. C. Smart, "The Temporal Asymmetry of the World," *Analysis*, March 1954, pp. 79-83.

[5] Two events A and B are *non*-causally related if their separation in spacetime is such that a particle would have to travel at a *superluminal* speed (faster than light) to go from A to B. We'll discuss the physics of causally related events later in this chapter.



Fig. 3.1 Gödel's unreality of time argument

implies that the passage or flow of time *makes no sense*![6] To see how Gödel arrived at such an astonishing conclusion, consider Fig. 3.1.

In part A of the figure[7] we see what most people who talk of a passage of time intuitively mean, as time progresses through a sequence of instants (shown as line of left-to-right arrows going from (1) to (2) to (3) and so on). At each stage the rightmost arrow is the present, and the arrows to the left of it (behind it) are the past, and the arrows to the right of the present are not shown because they are in the future and so don't exist yet. When you ask, at each step, which arrow is the *now*, the answer is clear.

Matters are dramatically different in part B of the figure, which shows the arrows forming a closed (circular) loop. Now there is no distinction between past and future, as each arrow is both ahead *and* behind any other arrow. In addition, there is no arrow that is uniquely the now. So, concluded Gödel, the passage of time can have no meaning in a temporal loop. As should come as no surprise, not everybody is convinced by this sort of argument.[8]

In principle, so it would seem, we can achieve perfect knowledge of what has happened but only imperfect prediction of what might happen. This observation seems to be at least a start at being able to tell past from future. And, in fact, the nature of the distinction between the two intervals of time seems obvious: we *remember* past events, but not future ones. As philosophers have so nicely put it, events in the past have formed *traces*, such as skulls, footprints in the sand, fossilized skeletons, surgical scars, photographs, taped recordings, carved stones, and the like, whereas future events appear not to have formed traces. But is that necessarily so? Is it impossible for future events to create traces? The common-sense answer is *yes*, because of cause and effect, which dictates that there *must* be a temporal asymmetry in trace formation. That is, traces are the effects of *prior* causes. That line of reasoning leads us quickly to the fundamental issue of causation (which we've already encountered in Chap. 2), an issue that no discussion of time travel can avoid.

---

[6] Gödel clearly states this in his 1949 philosophical essay (note 15 in the Introduction) concerning his 1949 technical paper (note 11 in the Introduction).

[7] This figure is based on the interpretation of Gödel's reasoning as presented by the philosopher Palle Yourgrau's 1991 book *The Disappearance of Time: Kurt Gödel and the idealistic tradition in philosophy* (Cambridge), which was expanded and reprinted a few years later under the new title *Gödel Meets Einstein: time travel in the Gödel universe*, Open Court 1999. Yourgrau later wrote a less technical version: *A World Without Time: the forgotten legacy of Gödel and Einstein*, Basic Books 2005.

[8] See, for example, S. Savitt, "Time Travel and Becoming," *The Monist*, July 2005, pp. 413-422.

Part of the problem we have with backward time travel, and cause and effect, is as I've already mentioned, with language. The distinct and separate concepts of the temporal ordering of events, and of causality, have become merged in everyday thought. It is considered *obvious* to modern minds that if event A causes event B, then A *must* happen first. There is, however, at least one historical example of a similar merging of concepts that is parallel to our modern mixing of time order and causality—an example that shows how an issue can seem obvious and natural to the minds of one period of time, and yet to the minds of another period (our modern times) seem confused, odd, peculiar, even laughable.

As a *physicist* wrote in a paper[9] on advanced (that is, inverted causality) effects:

> *Ancient Egypt was an essentially one-dimensional country strung out along the Nile, which flows from south to north. The winds were conveniently arranged to be predominantly northerly. To go north, a traveler could let his boat drift, while with a sail he could move south against the slow current. For this reason, in the writing of the ancient Egyptians, "go downstream (north)" was represented by a boat without sails, and "go upstream (south)" by a boat with sails. The words (and concepts) or north-south and up-downstream became merged. Since the Nile and its tributaries were the only rivers known to the ancient Egyptians, this caused no difficulties until they reached the Euphrates, which happened to flow from north to south. The resulting confusion in the ancient Egyptian mind is recorded for us to read today in their reference to "that inverted water which goes downstream (north) in going upstream (south)."*

Often we can work our way free of the difficulties we create for ourselves with language, but only through common agreement. For example, the chairman of the board calls a meeting to order with mixed tenses by declaring "The meeting *will* take place *now*" and then saying at the end, "We will meet again *next* month, *same* time." We all know what these sentences mean, but only by our cultural heritage and not by the process of applying logic. The language problem causes similar difficulties for not only for fictional time travelers, but also for the physicists/philosophers who study the possibility of time machines. So—beware!

The idea of time flowing is a popular one, and it repeatedly appears in the time travel literature as the "river of time" or the "ocean of time." The deep psychological appeal of this sort of 'water language' has, not surprisingly, attracted the attention of philosophers. We can find one of the earliest expressions of the view in the *Meditations* of the second-century A.D. Roman emperor and Stoic philosopher Marcus Aurelius, who wrote: "Time is like a river made up of events which happen, and a violent stream; for as soon as a thing has been, it is carried away, and another comes in its place, and this will be carried away, too.” A most interesting essay on why such metaphors often seem so intuitively appropriate has been offered by one philosopher, who points out[10] that the seductiveness of the image of ‘time as flowing water’ is sufficiently great that you often find it in the scientific literature, too (Newton, you’ll recall, wrote specifically in his *Principia* of time flowing). As for why such an image has such a powerful grip on our imaginations, I think we need look no further than to Kant. As he wrote (1781) in *Critique of Pure Reason*, “Time is nothing but the form of inner sense, that is, of the intuition of ourselves and of our inner state . . . Because this inner intuition yields no shape, we endeavor to make up for this want by analogies.” And what better than a rushing stream of water to represent our feeling of time rushing by?

---

[9] P. L. Csonka, "Advanced Effects in Particle Physics," *Physical Review*, April 1969, pp. 1266-1281.

Still, no matter how intuitive such water metaphors may be, they can still easily befuddle us as well. To quote our philosopher (note 10), “Time a river! A queer sort of river that. Of what sort of liquid does it consist? Is time a liquid? A very peculiar liquid indeed!” A classic paper by the philosopher Donald Williams (discussed in Chap. 2, note 119) expresses similar doubt about the water image of time. In the course of his writing, he presents a truly staggering collection of entertaining examples of ‘time as metaphor,’ of which I repeat just a few here: time flies, goes, marches, and rolls, as well as flows And then he offers *this* provocative imagery: the evolution of our lives is like “a moving picture film, unwinding from the dark reel of the future, projected briefly on the screen of the present, and rewound into the dark can of the past.” Wow![11]

Returning to the water metaphor, the French astronomer Charles Nordmann (1881–1940) opened and closed his 1925 book *The Tyranny of Time* with following gloomy but all too true summary of the overwhelming sense we all have of the inexorable, one-way ‘flow’ of time. (The ellipses in what follows denote over 200 pages!) “Nothing can equal the bitter sweetness of dreaming on the banks of Time, that impalpable and fatal river strewn with dead leaves, our wistful hours carried downstream like rudderless wrecks . . . In the eternal wave which rocks us, carries us along, and soon swallows us up, there is no rock to which we can fasten our frail barques; the very buoys we put out to measure our course are only floating mirages; and on the mysterious foundation of things our anchors slide along and fail to bite.” A young person sees time, from Nordmann’s perspective, as an ocean on which golden mornings arrive like waves from the future, whereas for an older person, liquid time is a nightmare flood, a swollen black torrent sweeping him first into the yawning abyss of the past and, ultimately and finally, into the eternal silence of the dark grave.

---

[10] J. J. C. Smart, “The River of Time,” *Mind*, October 1949, pp. 483-494.

[11] And how about *this* image of time: Time is a snowball, with the center marking the beginning of the past, with ever new ‘presents’ accreting on the ever increasing surface as the snowball rolls down the hill of history!

The metaphor of time as a flowing river was ready-made for early science fiction writers, such as Caltech math professor Eric Temple Bell (1883–1960). His eventual novel *The Time Stream* began to appear in December 1931 as a serial in the science fiction pulp *Wonder Stories*, and Bell (writing as 'John Taine') made great use of the idea of time as a flowing stream, a stream in which one could swim into either the future or the past. There is strong evidence that Bell actually wrote the novel in July of 1921, but was unable to find a publisher for a decade, so odd did editors find the premise. By the time of its publication, others had beaten Bell into print.

The watery image of time had appeared a year earlier, for example, in a tale that played with the erosive nature of time in a dramatic way. As two time travelers speed into the future to rescue a friend, one of them describes the scene for us: "We huddled together in the whirling time girdling machine, cutting through the years as a ship's prow breasts surging waves. I could not help but think of the years as waves, beating in endless succession on the sands of eternity. They wore all away before them with pitiless attrition. Time seemed to eat all with dragon jaws."[12]

This image of time was taken a step further 3 years later in a story in which a large number of adventurers, from all across time, find themselves stranded at precisely the same place (in space and time). One of them offers his theory of what is behind this remarkable coincidence: They all have faulty time machines, like faulty boats, and all have hit the same snag on the 'river of time.' As he explains, "You may turn boats adrift on a river at many points, and they will all collect together at the same serious obstacle whether they have traveled a hundred or two miles. We are now at some period where the straight flow of time has been checked — perhaps it is even turning back on itself … [We] have struck some barrier and been thrown up like so much jetsam."[13]

The 'flow' of time does have its critics, of course. The British-American philosopher Max Black (1909–1988) argued[14] that questions about the direction of time are meaningless because there can be no direction to something that (he asserted) does not flow. His reasoning was that if time does flow, then he ought to be entitled to ask *how fast* it flows. That requires, in turn, a *metatime* or *supertime* for measuring the flow rate of 'ordinary' time. But because supertime must flow, too, we would then need a super-supertime, and so off we trip into what would appear to be the black hole of a McTaggert-like infinite regress. The view, of an infinite regress of times, was forcefully rejected by another philosopher with these sharp words: “the very idea of super (or hyper)-time is indeed repulsive in its redundancy and its aroma of dilettante physics.”[15]

---

[12] E. A. Manley and W. Thode, "The Time Annihilator," *Wonder Stories*, November 1930. This is the same magazine that, months later, finally published Bell.

[13] J. Wyndham, "Wanderers of Time," *Wonder Stories*, March 1933. Notice again, that we have the same magazine (whose editor must have had a particular fancy for such tales).

[14] M. Black, "The 'Direction' of Time," *Analysis*, January 1959, pp. 54-63.

A hierarchy of hypertimes has not bothered other analysts, however, and an entire subfield of specialty among philosophers (and some physicists, too) in time analysis has developed in what is called *multidimensional time*. One practitioner in this specialty sarcastically rejected the infinite regress complaint as a valid objection—he called it “a crushing and unanswerable position” but actually meant just the opposite—and stated that it was not at all clear (at least, not to him) why supertime must flow.[16] After all, he argued, we measure the flow of a river with respect to its banks without requiring that the banks themselves flow. (That actually strikes me as being a point that deserves debating, but I have not been able to find any mention of it in the later philosophical literature.) The idea of multiple time dimensions is particularly attractive for one sort of time travel (we’ll take it up at the end of this chapter), but it enjoys far more popularity among science fiction writers and philosophers than it does with physicists.

Professor Black’s objection (note 14) to talk of time ‘flowing’ was based, at least in part, on the observation that there are uses of the word *direction* that are not directly tied to something flowing. For example, consider the statement ‘He is facing in the direction of north.’ Black argued that this is mere pointing, and it is not at all the same as *moving* north. He then dismissed the possibility of there being any meaning to the direction of time, writing that making an analogy of time “with a sign-post or an index finger is too far-fetched to be worth considering.” This claim (which some may feel leans too much on grammar) is, of course, an affirmation of the myth-of-passage view made famous a few years earlier by Donald Williams (note 119 in Chap. 2).

Not just philosophers have rejected the idea of time flowing. In his 1966 novel *October the First Is Too Late*, which deals with a world in which different parts of Earth simultaneously experience different eras of the past (see *For Further Discussion* at the end of this chapter for more on what this might mean), the British cosmologist Fred Hoyle (1915–2001) calls the ‘river of time’ a “grotesque and absurd illusion,” and a “bogus idea.” Another fictional work that agrees with Hoyle’s non-moving image of time is the 1979 *Roadmarks* by Roger Zelazny (1937–1995). In that novel we read of “the Road,” along which story characters can travel but which doesn’t itself move; exits from the Road lead to the various centuries (which sounds a lot like the Francis Bradley’s 1883 book that may have given the block universe its name). *Roadmarks* is a clever bit of writing, with many allusions to the paradoxes of time travel, but its explanation of the Road’s origin as having been constructed by *dragons* (!) greatly undermines its interest for physicists.

---

[15] D. Zeilicovici, “Temporal Becoming Minus the Moving-Now,” *Nous*, September 1989, pp. 505-524.

[16] C. W. Webb, “Could Time Flow? If So, How Fast?” *Journal of Philosophy*, May 1960, pp. 357-365.

In a block universe spacetime, there is no flow of time, but one philosopher believed that to be simply because the block universe is *incomplete* in its representation of reality. Writing in 1925, Hans Reichenbach (1891–1953) asked “What does ‘now’ mean? Plato lived before me, and Napoleon IV will live after me. But which one of these three lives *now*? I understandably have a clear feeling that *I* live now. But does this assertion have an objective significance beyond my subjective experience?”[17] Reichenbach went on to answer his question in the affirmative, and to deduce that the block universe view is missing something: “In the condition of the world, a cross-section called the present is distinguished; the ‘now’ has objective significance. *Even when no human is alive any longer, there is a ‘now’* [my emphasis] . . . In the four-dimensional picture of the world, such as used by the theory of relativity, there is no such distinguished cross-section But this is due only to the fact that an essential content is omitted from this picture.”

So, what *is* Reichenbach’s ‘missing essential content’? Feeling that the block universe is unacceptably fatalistic—in his words of ridicule, “the morrow has already occurred today in the same sense as yesterday”—he found his answer in the probabilistic theory of quantum mechanics. Classical physics argues that given total information about the state of the world *now*, one could in principle calculate perfectly the future or the past; one could both predict and retrodict. In contrast, quantum mechanics distinguishes past from future in a fundamental way.

Quantum mechanics does not deny that in principle we can know the past with exquisite accuracy, because each and every event leaves traces, evidence that is available to all with the means to find and decode them. But quantum mechanics also takes as truth that there is an unavoidable uncertainty to the future. The instant that this uncertainty is crystallized into fact was taken by Reichenbach to be the very definition of ‘now.’ The ever-increasing record of the past, in turn, defines (for Reichenbach) the *movement* of the ‘now.’ Reichenbach believed that with these observations he had at last captured the ‘moving now’ in mathematical theory, and that he had finally elevated the present from speculative psychology to solid physics, and that he had shown that the ‘flow of time’ is independent of the need for a conscious mind. However—

A later, powerful analysis[18] of the time-flow issue, combining philosophy with physics, comes down solidly in support of the *opposite* conclusion: it expresses the view that a ‘moving now’ *is* only in our minds and is *not* an intrinsic attribute of reality. The premise of that argument is that a mind-dependent flow of time is incompatible with what is called the *relativity of simultaneity* (to be discussed later in this chapter) which states that there is no universal cosmic-wide ‘now’ (this is a fundamental conclusion of special relativity). For example, it is meaningless to ask what is happening on a planet in the Andromeda galaxy (two million light-years distant) *right now*.

---

[17] I’ve taken this quotation from A. Grünbaum, “Is There a ‘Flow’ of Time or Temporal Becoming?” in *Philosophical Problems of Space and Time*, Knopf 1963.

[18] L. R. Baker, “Temporal Becoming: The Argument from Physics,” *Philosophical Forum*, Spring 1975, pp. 218-236.

Early science fiction stories are full of theories about the nature of ‘now,’ and the vast majority of them have no basis in scientific thought. Some of them are ingenious, however, and even though they are largely the pet ideas of the authors (and no one else’s), perhaps they resulted in some young readers of the science fiction pulps of the 1930s and 1940s thinking about deeper matters than did the comic strips of “Buck Rogers,” “The Lone Ranger,” or “Terry and the Pirates.” For example, according to one story, time is a wave and the ‘moving now’ we experience is carried on a crest of that wave. There are time waves both ahead and behind the crest we happen to be on (so we are told), and so each such crest carries a different ‘now’ for a different reality—hence the curious title.[19]

In another, more recent tale[20] about object duplication via time travel (which we’ll discuss in Chap. 4, but you’ll recall H. G. Wells was worried about this long ago), nine (!) copies of the same person from the year 2314 meet in 1870 to try and figure out what is going on. Part of their interesting discussion is the following analysis of the ‘present’:

> “Gentlemen, I think I understand,” said the first James Thomas.”
>
> “Eight faces turned toward him, and he felt as though he were looking into multiple mirrors.”
>
> “We hold that time is a single instant — the instant of the Present —which travels through Duration — do we not?”
>
> “Eight heads nodded.”
>
> “We assume that time passes in a manner analogous to the stringing of an infinite number of beads. Each bead is the instant of Now when it is last on the chain. Beads are continually being added, and each one is the only Now until another is placed after it.”
>
> “Yes, that is my theory,” said another James Thomas. “It can also be likened to the process of knitting. No matter how many stitches are knitted, there is only one last stitch, only one Now.”

Einstein, too, was greatly bothered by the place of ‘now’ in time, perhaps even more than were James Thomas and his ‘friends.’ In an autobiographical essay, the philosopher Rudolf Carnap (1891–1970) recalled a conversation about this with Einstein in the early 1950s, at the Institute for Advanced Study in Princeton: “Once Einstein said that the problem of the Now worried him seriously. He explained that the experience of the Now means something special for man, something essentially different from the past and the future. That this experience cannot be grasped by science seemed to him a matter of painful but inevitable resignation. . . . Einstein thought . . . that there is something essential about the Now which is just outside the realm of science."[21]

---

[19] R. Ray, “Today’s Yesterday,” *Wonder Stories*, January 1934.

[20] A. and P. Eisentein, “The Trouble With the Past,” in *New Dimensions 1* (R. Silverberg, editor), Doubleday 1971.

3.2 The Arrows of Time

> "On a microscopic level there is no preferred direction for time. The equations of motion don't give a damn whether time moves forward or backward."[22]

The central issue for philosophers of time (and for physicists, too, I think) is that of its reality (or not): is time *objective and something that really flows*, or is time simply a *mind-dependent illusion* and nothing more than an artifact of our incomplete perception of reality? As the previous section shows, there is little consensus on this issue. As a start on trying to get a handle on the matter, looking into a so-called 'arrow of time' may give us some guidance. I'll begin with the arrow I've already mentioned, the psychological arrow. As discussed before, this is the feeling we have of a 'moving now,' a feeling that has no appearance anywhere in physics. A 'moving now' simply has no place in any universe devoid of the physical processes in a brain that give rise to what we call consciousness—but that doesn't mean physicists don't wonder about the 'moving now' just as much as does everybody else (remember Einstein)! As one physicist wrote in a technical journal, "What does 'Now' mean? This question must surely be the starting point of any attempt at understanding the nature of time."[23]

Well, no matter whether time actually flows or not, most of us still believe we have had a past and hope we will have a future. Each of us thinks we can easily tell one from the other, too. We have, in fact, many not so subtle indications from our everyday lives of the obvious direction of time. Nearly all of these indications have the common theme of *irreversible change*. As the British mathematician J. J. Sylvester once put it, "The whirligig of time brings about its revenges."[24] The Roman poet Ovid, who died when Christ was a teenager, said the same in his *Metamorphoses* with the famous words "Time, the devourer of all things." The image of time as devourer of all that is mortal was brilliantly presented by James Barrie in his *Peter Pan*, with the crocodile who had swallowed a ticking clock chasing Captain Hook all about Neverland.

---

[21] Quoted from *The Philosophy of Rudolp Carnap* (P. A. Schlipp, editor), The Library of Living Philosophers, Open Court 1963, pp. 37-38. For a view contrary to Einstein's, from another physicist, see K. B. M. Nor, "A Topological Explanation for Three Properties of Time," *Il Nuovo Cimento B,* January 1992, pp. 65-70, which claims to develop a geometrical explanation for the flow of time, and so (says Nor) there *is* an objective, mathematical reality to the 'moving now.'

[22] A science fiction character pretty accurately sums-up what a modern physicist would tell you today, in L. Eisenberg's story "The Time of His Life," *The Magazine of Fantasy & Science Fiction*, April 1968.

[23] J. P. Cullerne, "Free Will and the Resolution of Time Travel Paradoxes," *Contemporary Physics*, July-August 2001, pp. 243-245.

[24] J. J. Sylvester, "A Plea for the Mathematician," *Nature*, December 30, 1869, pp. 237-239.

No one yet has escaped the biological decay processes of time, and inanimate objects are no less immune to this aspect of time. Logs and cigarettes burn in the stove and ashtray, but they never unburn. Our cars rust but never 'unrust.' An explosion has never been seen to reverse itself, to form a dynamite stick or a bomb casing out of a collapsing fireball. Our world seems, indeed, literally to be built on an irreversible movement toward chaos, death, and decay. Lewis Carroll uses this observation in his *Through the Looking-Glass* when Alice tells Humpty Dumpty "one can't help growing older." And speaking of Humpty Dumpty, his famous fall provides a dramatic example of a one-way evolution from past to future; he wasn't at all convinced that Alice was correct but, once he had splattered, then

All the King's horses and all the King's men
Couldn't put Humpty Dumpty together again.

While we are on the subject of Mr. Dumpty, it is also worthwhile to note that nobody has ever figured out how to unscramble an egg. Why is that? One philosopher speculated that the answer is found in the "irreversible organic phenomena" taking place in our brains which results in our flow of consciousness always being in the same direction.[25]

More subtle than the undignified undoing of a prideful egg is the phenomenon of memory, which seems trivial only because most people have not thought very carefully about it. We remember the past while remembering nothing about the future. We might, in fact, be tempted to use the phenomenon of memory to answer the question of how to tell past from future. Anything you can remember *is* the past. But that is a circular definition, as discussed by Professor Smart (note 4) who observed that to ask why memory is always of the past "is as foolish as to ask why uncles are always male, never female." In *Through the Looking-Glass* the White Queen tells Alice that "it's a poor sort of memory that only works backward" but, except for the claims of clairvoyants, it seems that is the only sort of memory any of us has. Why is that so? Of course, that would *not* be the case for a time traveler while in the past. His personal past, which he would remember, would be the future for the world around him.

For physicists, the question of the direction of time is one of profound mystery. There seems, in fact, to be no fundamental reason why time should not be able to go from future to past—but then what would 'future' and 'past' *mean*—even though no one has ever observed time to do so. All the laws of classical physics, including general relativity, and quantum mechanics, too (except for the K-mesons mentioned in Chap. 1) involve time in such a way that they ignore its sign. In other words, replacing t with $-t$ results in a perfectly valid description of something that could actually happen. But not all such possibilities are observed to occur. Why not?

---

[25] H. Margenau, "Can Time Flow Backwards?" *Philosophy of Science*, April 1954, pp. 79-92.

In an unpublished paper written in 1949, while doing the work that would bring him a share of the 1965 Nobel prize in physics, Richard Feynman (1918–1988) wrote[26] "The relation of time in physics to that of gross experience has suffered many changes in the history of physics. The obvious difference of past and future does not appear in physical time for microscopic events . . . Einstein discovered that the present is not the same for all people [the relativity of simultaneity, to be discussed later in this chapter] . . . It may prove useful in physics to consider events in all of time at once and to imagine that we at each instant are only aware of those that lie behind us. The complete relation of this concept of physical time to the time of experience and causality is a physical problem which has not been worked out in detail. It may be that more problems and difficulties are produced than are solved by such a point of view."

Feynman did not elaborate on what he meant by the "problems and difficulties" with that point of view (which is clearly that of the block universe), but surely he had the logical paradoxes of time travel high on his list. As the Yale philosopher Henry Margenau wrote (note 25) in a tutorial on Feynman's work, "The theory of quantum electrodynamics developed by Feynman incorporates reversals in the course of time and thereby cherishes, in the minds of many, *an age-old phantasy* [my emphasis] of more than scientific appeal [which sounds like time travel to me]."

Because the individual classical equations of microscopic physics are time-reversible, the distinction between past and future for individual particles disappears. The equations are said to be symmetric with respect to time; the algebraic sign of t is irrelevant in the classical laws. It must be understood, however, that there *is* a crucial point to appreciate. When a physicist says *time reversal*, she is talking about a system evolving backward in forward time—that is, all the individual particle velocity vectors are instantly reversed at once. This is distinct from the time-reversed worlds of philosophers and science fiction writers (which we'll get into later in this chapter) in which time itself 'runs backwards.' The physicist's point of view is clearly expressed in an early essay by a chemist: "Every equation and every explanation used in physics must be compatible with the symmetry of time. Thus we can no longer regard effect as subsequent to cause. If we think of the present as pushed into existence by the past, we must in precisely the same sense think of it pulled into existence by the future."[27] More than three decades later, a mathematician and a physicist presented a similar statement: "In classical dynamics, the past completely determines the present, and therefore, by symmetry, the future also completely determines the present."[28]

---

[26] S. S. Schweber, "Feynman and the Visualization of Space-Time Processes," *Reviews of Modern Physics*, April 1986, pp. 449-508.

[27] G. N. Lewis, "The Symmetry of Time in Physics," *Science*, June 6, 1930, pp. 569-577.

[28] O. Penrose and I. C. Percival, "The Direction of Time," *Proceedings of the Physical Society* (London), March 1962, pp. 605-616.

Besides the physics, there is also an interesting theological connection to time reversal. As one philosopher put it, “If all the laws are time reversal invariant and so no irreversible processes occur in the physical Universe then there is no inherent, intrinsically meaningful difference between past and future . . . If this is actually the natural case, then all mankind’s major religions which preach a creation of the Universe (by a supernatural agency) and imply, accordingly, a differentiation between the past and the future . . . would have to make appropriate adjustments.”[29]

There are, as you might expect on such a controversial topic, dissenters to the view that the classical laws of physics are necessarily time-reversible. Dirac himself wrote that “I do not believe there is any need for physical laws to be invariant under time and space reflections, although all the exact laws of nature so far known do have this invariance.”[30] Dirac did not, unfortunately, elaborate on just why he felt that way, but with the later discovery of K-mesons his position is seen to have been ‘ahead of its time’! In a famous science fiction story[31] dealing with the direction of time, one character finally puts his finger on the real puzzle of the question of time: “How can a man live backward? You might as well ask the Universe to run in reverse entropy.” That cogent question brings us, in fact, to the first scientific explanation developed to explain the observed asymmetric nature of time.

It was the Englishman A. S. Eddington (1882–1944) who gave the picturesque name, the *arrow of time*, to the observed asymmetric nature of time’s direction from past to future. He was also one of the popularizers of an explanation for the arrow, using the famous second law of thermodynamics.[32] The second law of thermodynamics states that a measure of the internal randomness or disorder—what is called the *entropy*—of any closed system (that is, one free of external influences) continually evolves toward that of maximum disorder, toward the condition called *thermodynamic equilibrium*. Indeed, so striking is this increase in entropy S with time in a macroscopically large system that the increase in entropy has come to be thought of as actually *defining* the direction of time. Eddington, however, was not the originator of the entropy concept. The history of entropy can be traced back to before the turn of the century, to the great Austrian scientist Ludwig Boltzmann (1844–1906) and his famous H-theorem. The quantity H in that theorem is directly related to the more familiar entropy,[33] defined by Boltzmann in 1877.

---

[29] H. Mehlberg, “Philosophical Aspects of Physical Time,” in *Basic Issues in the Philosophy of Time* (E. Freeman and W. Sellars, editors), Open Court 1971.

[30] P. A. M. Dirac, “Forms of Relativistic Dynamics,” *Reviews of Modern Physics*, July 1949, pp. 392-399.

[31] A. Boucher, “The Chronokinesis of Jonathan Hull,” *Astounding Science Fiction*, June 1946.

[32] A. S. Eddington, *The Nature of the Physical World*, Macmillan 1929.

[33] The H-theorem was a direct continuation of the work by the Scottish physicist James Clerk Maxwell (1831-1879) on the statistical properties of gas molecules (determining the probability density function of the molecules’ speeds). In 1866 Maxwell found this function for the particular case of thermodynamic equilibrium. In 1872 Boltzmann found the differential-integral equation the function satisfies in general, even if the condition of thermodynamic equilibrium doesn’t hold. From this Boltzmann was able to define a quantity H that he showed evolves in time such that

The entropy S of a system in a given state is proportional to W, which is the number of different possible ways the state can occur as a result of all possible variations of system's internal, microscopic structure. The calculation of W is usually quite complicated, but in various highly idealized systems it can be straightforward. Consider, for example, a vacuum cylinder with a thin membrane dividing the interior into halves. Suppose that we insert (to be specific) six molecules into the left half of the cylinder (and none into the right half). If we define the microscopic state of the system to be the number of molecules in the left half, then initially $W = 1$ because there is just one way to put all six molecules on the left side. This represents the state of *minimum* entropy, the state of maximum order that is most distant from thermodynamic equilibrium. If we now puncture the membrane then the molecules, once confined to the left side, are free to move about the entire cylinder. At any given instant we can imagine counting the number of molecules on the left side—suppose that at some particular instant we count five, with one molecule having moved to the right side. Then, $W = 6$, because there are six ways to pick the molecule that has moved from left to right, and so the entropy has increased.

We think of the thermodynamic equilibrium state as being the state with equal numbers of molecules in both halves of the cylinder, and that state has the *maximum* entropy. (Can you show that this state is associated with $W = 20$?) With such a small number of molecules, it is *not* clear that W (and so S) will *inexorably* increase with time; perhaps, after one of the six molecules has gone to the right, it then returns to the left side before any of its companions have joined it on the right. Such an event is called a *reversal*, and it will happen with some non-zero probability. But the more molecules there are in the cylinder (instead of six, make the number a million million million—still a small amount of gas in our everyday world, hardly enough to fill a sewing thimble), the more likely it becomes that the value of S *will* monotonically increase with time.

The steady increase in entropy is often observed in the everyday, large-scale world. A drop of ink in a glass of water spreads out in an expanding cloud, a cloud we *never* see collapse backward into an ink drop. A long rod of metal, initially hotter at one end than at the other, evolves toward a constant temperature along its entire length. We *never* see a uniformly warm rod spontaneously begin to cool at one end and grow hot at the other. A hot bath grows cold—nobody has *ever* seen a bath at room temperature suddenly, all by itself, begin to heat up and then boil in the middle of the tub while the edges freeze into ice chunks. In all of these cases, the end (future) state represents greater internal randomness or disorder than does the beginning (past) state.

---

solution to his differential-integral equation approaches Maxwell's equilibrium solution. The H-theorem says that H always *decreases* in systems not in equilibrium and is at a *minimum* in systems in equilibrium.



Fig. 3.2 Simulation of the Ehrenfest entropic gas clock

That is, low entropy *was* the past, and high entropy *will be* the future. The increase in entropy seems to define a direction to time, and so entropy has come to be called the *thermodynamic arrow of time*.

The first formal entropy model for the direction of time was put forth in a 1907 paper by the Austrian physicist Paul Ehrenfest (1880–1933) who was a friend of Einstein, and his Russian-born wife Tatyana (1880–1964), who was a skilled mathematician and her husband's occasional collaborator. In their paper the Ehrenfests developed one of the mainstays of physics, the so-called *entropic clock*. This clock, a statistical model based on the then new probability mathematics of Markov chains—after the Russian mathematician A. A. Markov (1856–1922)—describes how gases diffuse, and it is both a simple and a powerful concept. The Ehrenfest model is illustrated in Fig. 3.2, in a computer-generated plot based on a discussion by Princeton physicist John Wheeler of black hole fame (see Chap. 1).[34]

Imagine two urns, I and II, each containing n balls. Initially, at time $t = 0$, all of the balls in Urn I are black and all of the balls in Urn II are white. Then, at time $t = 1$ (in arbitrary units), a ball is selected at random from each urn and (instantaneously) placed in the other urn. This select-and-transfer process is repeated at times $t = 2$,

---

[34] J. A. Wheeler, "Frontiers of Time," in *Problems in the Foundations of Physics* (G. T. diFrancia, editor), *Proceedings of the International School of Physics* (Course 72), North-Holland 1979. See also W. J. Cocke, "Statistical Time Symmetry and Two-Time Boundary Conditions in Physics and Cosmology," *Physical Review*, August 25, 1967, pp. 1165-1170.

3, 4, ... At any given time each urn always contains n balls, but only at $t = 0$ are the colors of all the balls in a given urn necessarily the same. The phrase “selected at random” means (for example) that the probability of selecting a black ball from an urn containing b black balls is b/n. At any given time we completely describe the state of both urns by specifying the number of black balls in Urn I (or the number of white balls in Urn II, and so on). It is easy to write a computer simulation of this physical process,[35] and Fig. 3.2 shows how the fraction of black balls in Urn I evolves toward 0.5 as time increases. The plot is for $n = 100$ (200 balls total). The important observations are that (1) the evolution of the state of the system is toward 50 % black balls in Urn I (and this would be the case for ‘almost all’ sequences of random selections of the balls from the urns), and (2) the evolution is not monotonically decreasing from 100 % black balls to 50 % black balls, but rather has never-ending fluctuations about 50 % that may, in fact, be rather large in both amplitude and in duration.

There is a real puzzle with the entropic clock that may not be immediately apparent. The motion of each of the individual molecules is described by time-reversible physics, but when we average over ‘many’ molecules (assuming 200 molecules is ‘many’) we lose detailed information about the individual molecules. The puzzle is then how is it that by *reducing* our knowledge of a system, through statistical averaging, we then find it displaying a *new property*, that of asymmetric time evolution, that we didn’t see before when we watched the individual molecules. And if that question isn’t troublesome enough, we also have two additional puzzles called the ‘reversibility’ and the ‘recurrence’ paradoxes to consider as well.

The reversibility paradox is the question raised earlier: the classical equations of physics work just as well with time running in either direction, and so *why don’t* things actually go ‘backward’? This question, originally raised by the British mathematical physicist and engineer William Thomson (1824–1907)—better known as Lord Kelvin—in 1874, was brought to Boltzmann’s attention in 1876 by the German physical chemist Johann Loschmidt (1821–1895), one of Boltzmann’s professors at the University of Vienna. Boltzmann’s answer to this apparent paradox was that it *is* imaginable that a world could run backward if initial conditions were suitable. For example, if all the velocity vectors of every particle in an equilibrium state were reversed, then the system *would* unwind backward in time toward its original non-equilibrium condition. That is, a system in thermodynamic equilibrium, the state of highest entropy, could evolve toward one of low entropy. Boltzmann even suggested that such might be the case for regions in our own universe, that there might actually be beings in a world somewhere ‘out there’ who experience time running counter to our earthly experience. He said that in 1877, and it is a remarkable statement for a conservative nineteenth-century professor.[36] However, Boltzmann continued, from most given states there are vastly more ways for entropy to increase than there are for it to decrease, and that is why we see what we see, a continuous *increase* in entropy.[37]

---

[35] I used MATLAB, and you can find the code — gasclock.m — in Appendix C, written in such a low-level way as to be virtually 100% transferable to just about any of the popular scientific programming languages, and easily executed on an inexpensive laptop. Note that there are no K-mesons in the code (!) and so, as stated in Chapter 1, they aren’t responsible for the uni-directional time behavior depicted in the figure.

To find a science fiction writer speculating on reversed time people is, of course, much less remarkable! One pulp story, in fact, presents a curious treatment of the nuances of reversed time in which people talk backward (along with a marvelous bathroom scene of a man un-washing his hands!). This tale[38] tells us a young physics teacher who is "twisted into a reversed Time Stream" by an electrical discharge. As he lives backward in time, he observes everybody about him appearing to run in reverse, but even more puzzling is that they have developed a "dreadful, granite-like hardness." We soon learn why:

"For a while he could not understand the impenetrable hardness of external objects which he had experienced; it seemed they ought rather to be of intangible transiency, much as a dream, since he was re-viewing the Past. But a moment's thought gave him the logical answer. The Past is definite, shaped, unalterable, as nothing else in Creation is. Therefore, to argue that he could move or alter any object here [the past] was to argue that he could change the whole history of the world or cosmos. Everything he saw about him had happened, and could not be changed in any way. On the other hand, he was fluid, movable, alterable, since *his* future still lay before him, even if it had been reversed; he was the intruder, the anomaly. In any clash between himself and the Past, the Past would prove irresistible every time."

This passage reflects the modern view that the past cannot be changed, but explains that view in a way different from that generally accepted today. Modern physicists and philosophers invoke consistency requirements (which we'll take up in the next chapter) to explain the 'solidity' of the past. The author of this story also failed to explain why his physics teacher had no trouble moving about through the air of the past, which apparently is not any more resistant to being displaced than were air molecules before time reversal occurred.

---

[36] The Austrian-British philosopher Karl Popper (1902-1994) called Boltzmann's willingness to consider the possibility that different regions of the universe could have different directions of time "staggering in its boldness and beauty," but when on to say that Boltzmann must be wrong because "it brands unidirectional change an illusion [which] makes the catastrophe of Hiroshima an illusion." That is an emotional argument, of course, and although one of great power, I fail to see how it is related to physics. See Volume 1 of *The Philosophy of Karl Popper* (P. A. Schlipp, editor), Open Court 1974, pp. 127-128.

[37] For more on Boltzmann's views on entropy, see the end of his letter "On Certain Questions of the Theory of Gases," *Nature*, February 28, 1895, pp. 413-415.

[38] C. F. Hall, "The Man Who Lived Backwards," *Tales of Wonder*, Summer 1938. The modern classic of a time-reversed world is Philip K. Dick's 1967 novel *Counter-Clock World*. We'll encounter another time-reversed world again in Chapter 4.

It didn't take long for science fiction writers to incorporate entropy as time's arrow into time travel. In one early tale there is the brief statement that entropy is behind the operation of its gadget.[39] And a few years later the inventor of a "warp gun" tells us that "The stupendous distortion of the warp may actually bring about a sort of kink in spacetime, and result in a reversal of entropy"[40] and, sure enough, when the gun is fired a woman, who is hit by the warp, ages 70 years in seconds (which is, of course, exactly the opposite of what we would expect from a "reversal of entropy"!). Just a year later, the story of a college student about to flunk his senior physics course appeared.[41] An examination is scheduled for the following day, but he needs a week and a half of study time. To his rescue comes ENTROPY, INC., a company that sells time by placing its clients inside a "time-cabinet" in which the local entropy is greatly accelerated. To someone looking through a window at the interior of the time-cabinet, the occupants would appear as characters in a speeded-up movie. Referring to Eddington by name, the author tells us that "entropy is what makes time irreversible — is what gives us the feeling of the flow of time."[42]

In a hilarious, melodramatic story featuring one of early science fiction's stereotypical 'mad scientists,' the entropic arrow of time is the scientific explanation for time travel.[43] There we read of Bryce Field, "a master-scientist, a demon, cruel, ruthless," who is rejected in love by the stupendously beautiful Lucy Grantham. Her lack of enthusiasm is perhaps understandable, as Bryce is described as having "a lean-jawed, sunken-eyed" appearance, along with "lank, untidy hair sprawled across his massive forehead." As Lucy tells him at one point, "I could never love you; you are too clever, too brilliantly scientific." After hearing that, it is no surprise that before we are more than a page or two into the tale that we learn Bryce has Lucy strapped to a steel table in an underground laboratory-in-a-cave. There he tells her of her fate: "You are going on a long journey, my dear. So long a journey that even I, master-scientist, do not know when it will end. A journey into the future — alone! ... You, Lucy, shall be the victim of entropy! ... I have discovered how to make a [globe] of non-time. Entropy will be halted ... You will be plunged into an eternal 'now.'"

And so the mad Doctor Field throws the switch on the wall of his "instrument-littered" cave on July 17, 1941, and Lucy remains "suspended" in time until the outside world reaches the date of August 9, 2450. That is the day she is at last dug-up from the cave by "big and muscular" engineer Clem Bradley and his "square-jawed" sidekick Buck Cardew, who uses a "warp in spacetime" to release Lucy from her "globe of non-time."

---

[39] M. J. Breuer, "The Time Valve," *Wonder Stories*, July 1930.

[40] F. B. Long, "Temporary Warp," *Astounding Stories*, August 1937.

[41] R. M. Farley, "Time for Sale," *Amazing Stories*, August 1938.

[42] Also citing Eddington was a tale by D. W. O'Brien, "The Man Who Lived Next Week," *Amazing Stories*, March 1941, which uses entropy to explain time travel. This curious story has the traveler arriving in the future with his clothing aged, which later 'de-ages' when the return trip is made!

[43] P. Cross, "Prisoner of Time," *Super Science Stories*, May 1942.

A few years later entropy was used in a similar but vastly more ‘scientific’ way. In that tale[44] we read of a scientist who has discovered “a field in which entropy was held level.” As the reader is told, “An object in such a field could not experience any time flow — for it, time would not exist,” since time flow is a *change* in entropy, and the ‘change’ of a level (or constant) field is zero. This interesting tale speculates on how such a field could have fantastic home uses (“Imagine cooking a chicken dinner, putting it in the field, and taking it out piping hot whenever needed, maybe twenty years hence!”). But its real use in the story is as a stasis generator for preserving fatally ill people until medical science has learned how to cure their diseases. This is, then, a high-tech method of suspended animation, of time travel into the future that is different from simply freezing (a clock in such a field would not age or measure the passage of personal time).

The gadget that does all this is called, somewhat sinisterly, the “Crypt,” which we are told also makes a great bomb shelter, too, because “not even an atom bomb could penetrate a stasis field.” The reason for that is intriguing: “The field requires a finite time in which to collapse — only there is no time in it.” The interior of the Crypt is, quite literally, a frozen block of time more rigid and unyielding than the strongest steel.

As science fiction left the age of pulps and moved into the modern era, entropy continued to be useful a justification for time travel. Arthur C. Clarke used it,[45] as did Robert Silverberg. This last tale[46] is particularly interesting, as Silverberg pursued entropy beyond simply invoking it as a mere casual throwaway mention. When a newspaper from the future appears on people’s doorsteps, the initial astonishment is replaced with puzzlement as the papers rapidly disintegrate. That is the result (we are told) of “entropic creep.” The explanation continues, informing us that it is sort of like a strain in a geological fault (Silverberg has lived for decades in California, now and then a place of large to huge earthquakes, and it isn’t surprising that he uses this particular imagery): “Entropy you know is the natural tendency of everything in nature to come apart at the seams as time goes along. These newspapers must be subject to unusually strong entropic strains because of their anomalous position out of their proper place in time.”

Earlier I mentioned we had *two* puzzles associated with entropy; we’ve discussed ‘reversibility,’ so what’s the other one, the ‘recurrence paradox,’ all about? The recurrence paradox is quite different from reversibility; it is based on a result established in 1890 by the great French mathematician Henri Poincaré (1854–1912). Motivated by the question of the stability of the motion of three masses governed by Newton’s laws of mechanics (think, for example, of the Sun, the Earth, and the Moon), Poincaré showed that starting from almost any initial state, any fixed volume system with a finite amount of energy and a finite number of degrees of freedom will return *infinitely often and with arbitrarily little deviation* to almost every previous state. If you wait long enough, implies Poincaré's astonishing theorem, Pearl Harbor will happen again—and again, and again, and . . . . In 1896 the German mathematician Ernst Zermelo (1871–1953) used this result, which philosophers call the 'eternal return,' to claim that there could be no truly irreversible processes and thereby cast doubt on the idea that entropy *always* and *inexorably* increases.

---

[44] P. Anderson, “Time Heals,” *Astounding Science Fiction*, October 1949.

[45] In, for example, his story of the tragic end of a geologist fifty million years in the past: “Time’s Arrow,” *Science Fantasy*, Summer 1950.

[46] “What We Learned from This Morning’s Newspaper,” *Infinity 4*, November 1972.

Even for very small systems, however, such as a mere handful of molecules, the recurrence time is extremely large, and this was, in essence, Boltzmann's reply to Zermelo's concern. For example, if the gas-filled cylinder of our entropic clock has just 100 molecules (not the six I used in the earlier example), and if transitions from one side of the cylinder to the other side take place at the rate of one million per second, then the recurrence time has been calculated to be something like 30 million billion years![47] And for the universe itself, the recurrence time is simply incomprehensible. Mathematicians call 1 followed by a hundred zeros a *googol*, and the recurrence time in years for the universe has been estimated to be 1 followed by a googol of zeros (a so-called *googolplex* of years).[48]

Using a wonderful bit of imagery, one analyst wrote of the enormity of the recurrence time of a system considerably *less* complex than the universe this way: "If a man shuffled just a single pack of cards as rapidly as an individual molecule hits other molecules in air, and if a snail started to crawl around the universe . . . at the rate of one centimeter *during the life of the sidereal system* [my emphasis], the snail would have got round the universe many millions of times before it would become at all likely that the man would have got the pack back to the original order."[49] If this is what it takes to get a pack of cards back to its initial state, then try to conceive of the time interval required to restore *the world* to December 7, 1941.[50]

The notion of eternal recurrence considerably predates Poincaré, and its scientific (as opposed to astrological) study can be traced back to the fourteenth century.[51] A 'more recent' claim for eternal recurrence, also based on scientific arguments (conservation of energy), can be found in many places in the writings of the German philosopher Friedrich Nietzsche (1844–1900)—see, for example, his *The Gay Science* (1882) and *Thus Spake Zarathustra* (1883)—again predating

---

[47] J. M. Blatt, "Time Reversal," *Scientific American*, August 1956.

[48] The googol is a gigantic number, far greater than the number of raindrops that have fallen on the Earth during its entire history. And the googolplex is light years beyond that.

[49] R. B. Braithwaite, "Professor Eddington's Gifford Lectures," *Mind*, October 1929, pp. 409-435.

[50] Pulp science fiction writers, of course, were not discouraged by such calculations, as they depended on the *certainty* of recurrence over *infinite* time. See, for example, S. G. Weinbaum, "The Circle of Zero," *Thrilling Wonder Stories*, August 1936, and L. D. Gunn, "The Time Twin," *Thrilling Wonder Stories*, August 1939.

[51] R. Small, "Incommensurability and Recurrence: From Oresme to Simmel," *Journal of the History of Ideas*, January-March 1991, pp. 121-137.

Poincaré. All of Nietzsche's arguments are flawed,[52] but they are rational, physical arguments, as opposed to arguments based on metaphysics or theology. In fiction, a glimmer of the idea of a repetition of human affairs preceded Poincaré by some years, too.[53]

An important caveat concerning recurrence is that we could never *know* of it because the state of all the historical records (geological, memories, books, photographs, and so on) would, as part of the physical state of the universe, also recur. And so those records could, up to the instant *before* the recurrence, contain no signature *of* the recurrence because the recurrence has not 'yet' happened![54] The 1993 movie *Groundhog Day* stumbles on this point, as it has a character (for some unexplained reason) live through the same day over-and-over *and he is aware he is doing that*. Indeed, he can change events within that time loop at will. It is interesting to note that one 'time loop' pulp science fiction tale[55] specifically avoided that error (and cited Nietzsche, to boot), and so demonstrated that pulp science fiction *could* have some philosophical merit to it.

While the enormous recurrence time for the universe may seem reason enough to reject the possibility of Pearl Harbor repeating, there are more fundamental reasons for such a rejection. For example, an *expanding* universe, such as the one we live in, violates the Poincaré theorem's assumed condition of a *fixed* volume system. As Professor Eddington put it in a 1934 lecture at Cornell University, "In an expanding space any particular congruence becomes more and more improbable. The expansion of the Universe creates new possibilities of distribution faster than the atoms can work through them, and there is no longer any likelihood of a particular distribution being repeated. If we continue shuffling a pack of cards we are bound sometime to bring them into their standard form — but not if the conditions are that every morning one more card is added to the pack."[56]

An even more direct way to escape Poincaré's theorem is to use a result from general relativity. Using Einstein's theory instead of the classical dynamics that Poincaré used, it has been shown (by Frank Tipler, the inventor of the rotating cylinder time machine spacetime that was mentioned in the previous chapters and which we'll revisit later in the book) that the recurrence theorem is simply no longer true.[57] As Tipler wrote, "In general relativity, singularities intervene to prevent recurrence. General relativistic Universes are thought to begin and end in singularities of infinite spacetime curvature [the Big Bang and the Big Crunch, respectively], and these singularities force time in general relativity to be linear rather than cyclic." A twist to this, however, is that in his analysis Tipler assumed that gravity is *always* attractive, and that the spacetime satisfies a special condition (called the *Cauchy condition* that we'll take-up later) that avoids backward causation. The first assumption is violated in wormhole time machine spacetimes, though, and the second is *by definition* violated in *any* spacetime that supports time travel! So, who knows . . ... ?

---

[52] J. Krueger, "Nietzschean Recurrence as a Cosmological Hypothesis," *Journal of the History of Philosophy*, October 1978, pp. 435-444.

[53] See "Human Repetends" by Marcus Clarke (1846-1881), a story originally published in 1872 and reprinted *Australian Science Fiction* (V. Ikin, editor), Academy Chicago 1984.

[54] For more on this point, see D. W. Theobald, "On the Recurrence of Things Past," *Mind*, January 1976, pp. 107-111.

[55] C. F. Ksanda, "Forever Is Today," *Thrilling Wonder Stories*, Summer 1946.

[56] A. S. Eddington, "The End of the World," in *New Pathways in Science*, Macmillan 1935.

[57] F. J. Tipler, "General Relativity and the Eternal Return," in *Essays in General Relativity* (F. J. Tipler, editor), Academic Press 1980.

Despite all of the previous discussion it is *not* true that the evolution of a system from past to future is *always* accompanied by an increase in entropy—that is, by an irreversible increase in some measure of the system's 'disorder.' Yes, it can be calculated that entropy is *very likely* to monotonically increase in systems of macroscopic size, but that is not the same as certainty. There *can* be fluctuations in the thermodynamic evolution of a system so as to have, at least for a while, a *decrease* in entropy (take another look at Fig. 3.2). All we can say, for sure, is that for macroscopically sized systems even very small fluctuations in increasing entropy are most improbable. To quote no less an authority than the combined genius of Gilbert and Sullivan (from their opera *H. M. S. Pinafore*), here's what we can honestly say of the possibility of failure in the supposed inexorable increase of entropy: "What, never?/No, never!/What, never?/Well, hardly ever." Still, for physicists, entropy is just too useful a concept to give up even though it does not *always* increase with increasing time for an isolated system.

Love it though they may, there are some puzzling aspects to entropy for physicists that remain to this day. For example, the idea that the universe began in some sort of Big Bang process 15 billion years or so ago is the generally accepted view today, The puzzle of that event, one that has been described as literally being a 'fireball explosion,' is that it must have been *fantastically* hot. This means that at the beginning (of everything) there was complete thermodynamic disorder, which from our earlier discussion means *maximum* entropy. Thus, we immediately have the question of how can the entropy of the universe be continuously increasing if it was as large as possible right from the start?[58]

One possible answer is that the proper model of the universe to use is the so-called *inflationary* universe. The inflationary model has a very high expansion rate for the early universe, much higher than the rate in the standard hot Big Bang model. In the standard model, the entropy puzzle occurs because of the ability of all particle processes to readjust rapidly to the ever-changing state of the universe; the so-called *relaxation times* of all particle processes were *short* compared to the expansion rate of the universe. That means that the actual entropy of the universe would, indeed, be the maximum possible at every instant (and so we have the entropy puzzle). In the inflationary model, however, the expansion rate of the early universe was temporarily so high that the relaxation times of particle processes were *very long* compared to the expansion rate. That means the maximum *possible* entropy of the universe, at every instant, would greatly exceed the *actual* entropy. This 'entropy gap' is the cause, then, of the thermodynamic arrow of time, as the universe tries to 'catch-up' and reduce the resulting entropy deficiency.

---

[58] It has been estimated that over the next 10^{116} years the entropy of the universe will increase by a factor in excess of 10^{14}. See S. Frautschi, "Entropy in an Expanding Universe," *Science*, August 13, 1982, pp. 593-599.

There is also a philosophical problem with associating increasing entropy with the flow of time from the past into the future. Events in the past leave traces, artifacts taken to be ordered states—or at least more ordered than are their immediate surroundings. The classic example of this is a footprint in the sand, which is clearly a highly organized structure compared to the surrounding sandy beach. The footprint is the trace of a *past* event; such a trace was all the evidence, for example, that Robinson Crusoe needed to conclude that another human had walked that way. But now consider this famous counter-example,[59] that of a bombed city. Certainly there are traces aplenty of past bombing, and in fact one has to be careful not to trip over or to fall into them! The puzzle, of course, is in trying to argue that random bomb craters, strewn rubble, and crushed buildings, somehow constitute a more organized state (a 'footprint') than did the original city and its surrounding undamaged areas. This fuzziness was captured by one physicist who asked "If it were found that the entropy of the universe were decreasing, would one say that time was flowing backward, or would one say that it is a law of nature that entropy decreases with time?"[60]

For another example of the fuzziness of the relationship between entropy and time, consider the situation[61] of a cloud of non-colliding particles all initially moving toward each other. At first the radius of the smallest sphere that contains the cloud decreases with time but, eventually, as the particles move past another, the radius will grow without bound. Indeed, that inexorable increase of the radius could be taken as defining the direction of time that points toward the future. But in what sense is the *disorder* of the particle cloud increasing? After all, as the cloud expands it 'looks the same' at all times; only its scale (radius) changes. What has entropy to do with this expanding-into-the-future cloud? Perhaps nothing. Perhaps what is need is a *new* arrow of time.

So far we have looked in some detail at two arrows of time: the subjective, psychological feeling we have of time 'flowing,' which has no explanation in physics, and the thermodynamic, statistical quantity of entropy. A third arrow is the so-called *cosmological arrow* of the expansion of the universe. This arrow is not nearly as obvious as the first two. Only in the last century (since the 1920s), as a result of the American astronomer Edwin Hubble (1889–1953), has science become aware that the universe *is* expanding. An interesting speculation about the thermodynamic and cosmological arrows, one made numerous times, is that if the cosmological arrow should ever reverse—that is, if the universe should ever begin to contract toward a Big Crunch—then the thermodynamic arrow would also reverse.[62] The reasoning is that the thermodynamic arrow *follows* the cosmological arrow in an *expanding* universe because that universe can continually 'swallow-up' ever more electromagnetic radiation as it is produced by any physical process. *If* the thermodynamic arrow continues to follow the direction of the cosmological arrow during a contraction, *then* the thermodynamic arrow would also reverse direction.

---

[59] See note 54 in Chapter 2.

[60] P. W. Bridgeman, *Reflections of a Physicist*, Philosophical Library 1955, p. 251.

[61] Taken from K. G. Denbigh, "The Many Faces of Irreversibility," *British Journal for the Philosophy of Science*, December 1989, pp. 501-518.

The usual objection to that suggestion is straightforward. If the direction of time did reverse, then we would see (so goes this argument) all sorts of odd events that would require enormously improbable physics, such as a shattered glass mirror reassembling itself. The error in that objection is subtle but equally simple. *It presupposes the retarded causality of our expanding universe*. In a contracting universe with a reversed thermodynamic arrow of time, however, there would be *advanced* causality, and thus there would be nothing at all improbable about such doings as self-assembling mirrors. As two physicists observed, "The mere reversal of the cosmological expansion will not of itself serve to reverse the direction of thermodynamic and electrodynamic processes, any more than the compression phase of a piston-and-cylinder cycle in a heat engine serves to reduce the entropy of the confined gas."[63]

Those same physicists go on to then mention Stephen Hawking's interest in the relationships among the various temporal arrows. At one time Hawking thought[64] he had discovered a connection between the thermodynamic and cosmological arrows, but then later abandoned that claim.[65] Hawking, in fact, has labeled his original claim "my greatest mistake in science," and has quite openly (and most entertainingly!) discussed his interest in the arrows of time.[66] Indeed, it was to be the subject of his doctoral dissertation but, as he wrote, "I . . . needed something more definite, and less airy fairy than the arrow of time, for my PhD, and I therefore switched to singularities and black holes. They were a lot easier."

Yet another arrow of time is the *electromagnetic arrow*, which refers to the fact that radio waves are observed to only propagate into the future, and never into the past. This is a mysterious fact, because Maxwell's equations for the electromagnetic field, like all the other laws of physics, have no intrinsic time sense. The electromagnetic arrow will be discussed in some detail in Chap. 4.

---

[62] T. Gold, "The Arrow of Time," *American Journal of Physics*, June 1962, pp. 403-410.

[63] P. C. W. Davies and J. Twamley, "Time-Symmetric Cosmology and the Opacity of the Future Light Cone," *Classical and Quantum Gravity*, May 1993, pp. 931-945.

[64] S. Hawking, "Arrow of Time in Cosmology," *Physical Review D*, November 15, 1985, pp. 2489-2495. See also the next paper in the same journal, D. N. Page, "Will Entropy Decrease if the Universe Recollapses?," pp. 2496-2499.

[65] For *why* he abandoned that claim, see S. Hawking *et al.*, "Origin of Time Asymmetry," *Physical Review D*, June 15, 1993, pp. 5342-5356.

[66] S. W. Hawking, "The No Boundary Condition and the Arrow of Time,' in *Physical Origins of Time Asymmetry* (J. J. Halliwell *et al.*, editors), Cambridge University Press 1994.

3.3 Time Dilation

> "Time as we know it is not universally absolute. The rate of its passage depends to a great extent upon the velocity of its observer with regard to some certain reference system. A moving clock will run slower with respect to a selected coordinate system than a stationary one."
>
> —an early science fiction time traveler explains how his time machine works[67]

In this section I'll set the stage for the scientific basis of time travel to the future, as well as for time travel to the past via the warped spacetime called a wormhole. We start by imagining two horizontal, parallel mirrors, one positioned over the other and separated by distance d. The two mirrors are in the same frame of reference with an Observer; that is, the Observer is looking at two mirrors that are stationary with respect to him. Between the two mirrors we further imagine that a particle of light, a photon, is bouncing endlessly back and forth, up and down, in relentless reflection. This simple system is called a *photon clock*, or the Einstein-Langevin clock, after the French physicist Paul Langevin (1872–1946), and it has been part of physics for decades. We define the time required for the photon to travel from one mirror to the other as a *tick* in time, and so the return trip defines the clock's *tock*. The rate of timekeeping measured by the Observer, the time interval separating consecutive ticks, is obviously then given by

$$t' = 2\frac{d}{c}$$

where c is the speed of light.

Suppose we next imagine that the Observer and the photon clock move at constant speed v to the right across *our* line-of-sight. That is, we remain in the original frame while the photon clock and the Observer are now moving at speed v relative to us. This means the photon clock is in a different frame of reference from ours and so *we* do not see the photon bouncing up and down vertically, but rather *we* see the photon tracing out the triangular path shown in Fig. 3.3.

A round trip of the photon evidently now requires more time than before because the distance in the stationary frame (our frame) is greater than the round trip distance in the Observer's frame (moving with the photon clock, he still sees a round trip distance of d). In fact, if t is the time between consecutive ticks as seen by a stationary viewer (us), then the round trip path length of the photon that we see is

$$2\sqrt{d^2 + \left(\frac{vt}{2}\right)^2}$$

---

[67] F. J. Bridge, "Via the Time Accelerator," *Amazing Stories*, January 1931.



Fig. 3.3 The moving (relative to us) photon clock

and so

$$t = \frac{2\sqrt{d^2 + \left(\frac{vt}{2}\right)^2}}{c}.$$

This can be easily and quickly manipulated algebraically and combined with the earlier expression for t', the tick interval for an Observer in the same frame as the photon clock, to give the tick interval for the moving clock *as measured by a stationary viewer* (us):

$$t = \frac{t'}{\sqrt{1 - \left(\frac{v}{c}\right)^2}}.$$

Notice that this reduces to $t = t'$ when $v = 0$—that is, when the photon clock is stationary with respect to us.

This last result is the famous Einstein time dilation formula, which shows that $t \geq t'$, and indeed that $t = \infty$ when $v = c$. That is, to us the moving photon clock appears to *run slow* compared to clocks in our stationary frame of reference and, at the speed of light, time *stands still*.[68] A curious anticipation of this association between light and timelessness can be found in a poem by the seventeenth-century poet Henry Vaughn who, in the opening words to his "The World"—which appeared in 1650 as part of his *Silex Scintillans* ("Sparking Flint")—wrote

> "I saw Eternity the other night
> Like a great *Ring* of pure and endless light,
> All calm, as it was bright,
> And round beneath it, Time in hours, days, years
> Driven by the spheres
> Like a vast shadow moved, in which the world
> And all her train were hurled."

---

[68] For $v > c$ the time dilation formula says that time becomes imaginary, and this is one reason for claiming that $v > c$ is not possible. The time dilation formula has been experimentally verified: see H. E. Ives and G. R. Stilwell, "An Experimental Study of the Rate of a Moving Atomic Clock," *Journal of the Optical Society of America*, July 1938, pp. 215-226.

A similar modification in the length of a moving object (measured in the direction of motion) occurs when $v > 0$. While an Observer moving with the object will measure its length to be L', a stationary viewer will 'report' it to be contracted to the length

$$L = L'\sqrt{1 - \left(\frac{v}{c}\right)^2}.$$

This effect is called the *Lorentz-FitzGerald contraction*.[69] For 'everyday' objects and speeds the contraction effect is an extremely small one. For example, for a low-altitude satellite 100 m long, moving at 18,000 miles per hour (that is, at $v = 2.7 \times 10^{-5}c$), the contraction is less than 4×10^{-6} cm.

In the early days of science fiction the contraction effect was fascinating to readers, but authors often got it wrong. For example, in one story[70] of a runaway spaceship falling into the Sun, we read "When our racing [ship] was drawn from the Earth's gravity and fell at ever increasing speed toward the Sun it soon approached the speed of light. As we fell faster and faster our length in the direction of the Sun progressed into nothingness. Then — it reached the speed of light — passed it. Now — mind you this — when the [ship] attained the speed of light it was of a *minus* length." This author has managed to make four errors in three sentences!

The same author botched the Lorentz-FitzGerald contraction again 5 years later, and added yet more errors to his growing list. In that tale[71] there is an episode of faster-than-light radio communication along with a lengthy, unfortunate dissertation that actually denies special relativity's fundamental assertion that all inertial frames of references are indistinguishable from each other (two frames are *inertial* if they have no relative acceleration—I'll say more on this in the next section). And in yet another story[72] of high-speed space travel the author has the contraction working in the wrong direction—as the rocket ship moves faster and faster it gets longer and longer.

As bad as those errors are, first prize for mangling the laws of physics has to go to the story[73] of a near light-speed spaceship on its way to Alpha Centauri. The crew mutinies and puts the captain and first office 'overboard' (think *Mutiny on the Bounty*) with 6 months' worth of provisions. This happens at mid-voyage, about 2 light-years from both home and destination, so matters look grim. Indeed, the author tells his readers, several times, that things look *very* bad. But are they? With a stated speed of 162,000 miles per second, the time dilation factor is slightly more than 2 and so, because the space boat is traveling at $0.87c$, it will take a little more

---

[69] Named after the Dutch physicist H. A. Lorentz (1853-1928) and the Irish physicist G. F. FitzGerald (1851-1901).

[70] J. H. Haggard, "Faster Than Light," *Wonder Stories*, October 1930.

[71] J. H. Haggard, "Relativity to the Rescue," *Amazing Stories*, April 1935.

[72] D. Wandrei, "A Race Through Time," *Astounding Stories*, October 1933.

[73] N. Schachner, "Reverse Universe," *Astounding Stories*, June 1936.

Table 3.1 The Lorentz-FitzGerald time slowing factor

1	$\frac{1}{\sqrt{1-\left(\frac{V}{C}\right)^2}}$
.1	1.005
.2	1.021
.5	1.155
.7	1.4
.9	2.294
.999	22.366
.9999	70.712

than 13 months of *space boat time* to complete the journey. If the men go on half-rations then it seems they *could* survive.

There is, of course, the problem of slowing down so as to arrive at Alpha Centauri at a reasonable speed, but that issue is ignored in the story. Instead, our attention is directed to the much more dramatic concern of a faster-than-light planet (don't ask!) colliding with the space boat and carrying the castaways onwards toward their destination. When this happens we read that time runs backwards (for what *really* occurs at superluminal speeds, keep reading this chapter) and, finally, in a repeat of an error I mentioned earlier, we are told that the Lorentz-FitzGerald contraction is negative for $v > c$.

The time-slowing (or size-shrinking) factor becomes pronounced only at values of v close to c, as shown in Table 3.1. For example, the last entry shows that a clock traveling at 99.99 % the speed of light will register the passage of 1 year while nearly 71 years pass on Earth. One science fiction writer got this dramatically wrong, even though he actually reproduced the Lorentz-FitzGerald equation in his story.[74] At one point he writes of the near light-speed rocket ship that stars in the tale, "If it [the ship's speed] was as slow as ninety-four percent [of the speed of light] . . . for every moment ticked by the clocks of the [ship] hundreds passed on earth." In fact, the time dilation factor at that speed is 'only' 2.93.

One possible objection to time dilation is that the analysis done here has been for a *particular* clock. How do we know that another clock, one using wheels and pendulums, for example, instead of photons and mirrors, wouldn't be affected differently by motion? The answer comes from relativity itself, which says there is no way to detect uniform motion. If two clocks did behave differently, then this difference could be used as a motion detector. Since this is impossible within the framework of relativity, then *all* clocks, no matter what the details of their internal mechanisms may be (including the *biological* clocks of own bodies), must respond to motion just as does the photon clock.[75]

---

[74] L. R. Hubbard, "To the Stars," *Astounding Science Fiction*, February and March 1950.

Time dilation can also be caused by gravity (it appears in the 2014 movie *Interstellar*), and that effect has been used to 'construct' a time machine from a wormhole (to be discussed later). You can get a qualitative understanding of how that happens by imagining a massive body (*massive*, to have a really big gravitational field) in space, on the surface of which is a hot object. That object emits electromagnetic radiation and, though it isn't essential to the following argument, further imagine that the temperature of the object is sufficiently high that some of the radiation (emitted by the very atoms of the object) is in the visible-light portion of the spectrum. Now, from elementary quantum theory we can also think of the object's atoms as emitting photons ('particles of light'), each of energy hf, where h is Planck's constant and f is the frequency in hertz (what used to be called 'cycles per second'). The higher the temperature, the higher the photon energy, and so the higher the frequency. In the visible spectrum, f is on the order of 10^{15} Hz, a frequency one *billion* times higher than commercial AM radio frequencies.

The radiating atoms can be thought of as tiny clocks, with alternate half-cycles of radiation being ticks and the half-cycles in-between being the tocks. The passage of time on the surface of the massive body can be measured by these atomic clocks in the hot, radiating object. To a distant observer, however, as she receives the photons from the hot object, the passage of surface time on the massive body will appear to occur at a reduced rate when compared with the photons emitted by her own identically hot object (her 'local' clock). That's because the radiation that arrives at the distant observer has traversed a gravitational field (a journey sometimes described as 'climbing out of a gravitational well') and so is down-shifted in frequency toward the red end of the visible spectrum. This effect is called either the *gravitational red shift* or the *gravitational time dilation* effect (or even the *Einstein shift*, because it was Einstein who predicted the effect in 1907).

You can 'understand' this dilation effect as follows. One can crudely think of a photon emitted by the hot object as something like a rock thrown upward. As the rock rises upward through the gravitational field, its *total* instantaneous energy is always constant, but the total, fixed energy is split between its kinetic and potential energies in an ever changing way. That is, as the rock rises, its kinetic energy continually decreases (the rock slows down), whereas its potential energy continually increases. A photon is not a rock, however, and it certainly can't slow down as

---

[75] Resistance to this conclusion persisted for years. See, for example, the letter "Relativity and Radio-activity," *Nature*, January 8, 1920, p. 468. The author of that letter wondered whether a clock based on radioactive decay might not somehow beat the 'conspiracy' of moving clocks running slow compared to stationary ones. And in a letter to *Science* (December 7, 1962, p. 1180), a reader objected to applying the laws of physics to biological systems, first asserting (incorrectly) that time dilation "has never been proved or disproved experimentally," and then "there is no known causal means by which greatly increased velocity could alter, without destroying the very biochemical basis of the life process, the metabolic changes which are responsible for the aging process."



Fig. 3.4 Gravitational time dilation due to a massive body

it rises through a gravitational field (it *always* moves at the speed of light because the photon *is* light). The only way a photon can give up energy to balance the ever increasing potential energy (physicists will cringe at this, but read on) is to decrease its frequency. Hence, the red shift as seen by a distant observer of the photon, who thus sees time running slow on the massive body. Fig. 3.4 shows the case for a clock on a massive body, compared to a distant clock. Notice, carefully, the 'direction of gravity,' that is, the direction a small, unrestrained test mass will move.

A gravitational red shift in the *opposite* direction is nicely described in the famous 1966 science fiction story "Neutron Star" by Larry Niven. There a space traveler zooms down into a neutron star's intense gravity field (at half the speed of light!), passing within one mile of the star's surface. He reports what he observes in these dramatic words: "All around me were blue-white stars. Imagine light falling into a savagely steep gravitational well. It won't accelerate. Light can't move faster than light. But it can gain in energy by increasing its frequency. The light was falling on me, harder and harder, as I dropped." To Niven's intrepid spaceman, therefore, the passage of time on those distant blue-white stars appeared to be running *fast* compared to his wrist watch. This shows that the effect could equally well be called the 'gravitational *blue* shift.'

Notice that *gravitational*-induced time alterations do *not* have the symmetrical feature of motion-induced time dilations.[76] That is, for gravitational time dilations caused by photons either falling into or climbing out of gravity wells, observers at each end *agree* about whose clock is running slow, unlike in the motion-induced case where *each* of the relatively moving observers thinks it is the *other* observer's clock that is running *slow*.[77]

Now, comparing a massless photon to a rock which does have mass (and so potential energy), as each travels 'against' gravity, *is* straining the physics, with its one virtue being the provision of an initial plausibility argument. Gravitational time dilation is sufficiently important in the operation of wormhole time machines,

---

[76] Gravitational time dilation was experimentally observed in 1960, more than half a century after Einstein predicted it.

[77] A science fiction use of both the red and the blue gravitational shifts appears in the novel by J. P. Hogan, *Out of Time*, Bantam 1993.



Fig. 3.5 Gravitational time dilation due to rotation

however, that perhaps another way to think about it that is more acceptable to hardcore physicists makes it worth another look. Imagine a turn-table disk that initially is *not* rotating (soon it *will* spin). On this disk imagine further that we fasten two clocks, one called S (for *stationary*) and one called M (for *moving*), as shown in Fig. 3.5. These two clocks are set to read the same time at some instant and then, thereafter, they tick-tock through time at precisely the same rate. We then start the disk rotating around a vertical axis through clock S. (Imagine S to be a *point* clock, and so it is *the* one point on the turn-table that remains at rest even as the disk rotates.) What happens to the time-keeping of S and M?

We can answer this question by using our earlier result concerning time dilation due to motion. Even with the disk now rotating, S appears stationary to an observer sitting on top of M, while M appears to be moving across the line of sight of an observer sitting on top of S. So, to the observer at S, clock M runs slow, while to the observer at M there is *no change* in the time keeping of clock S. This is a non-symmetrical outcome, and so should remind you of gravitational time dilation. This might be a puzzle to you, however, as we don't have a massive body in Fig. 3.5 to account for a gravity presence. This is where the genius of Einstein comes into play.

Anyone who has ever ridden on a merry-go-round knows there is an outward (pointing away from S) directed force called the *centrifugal force* that is 'trying' to toss you off the merry-go-round. Now, where there is a force there is an acceleration, and one of Einstein's starting points in his development of general relativity was to identify an acceleration, *whatever its origin*, with gravity. A massive body is, of course, one possible origin (the obvious one, in fact), but so is the rotation of the turn-table. So, we have the situation shown in Fig. 3.5, where now 'gravity' is directed as shown and, and as in Fig. 3.4, the direction of acceleration of gravity is toward the slow-running clock. Again, the direction of gravity is the direction a small, unrestrained test mass on the rotating disk will move. The further M is away from S, the greater the 'gravity' of the centrifugal acceleration and so the slower will M run as measured by the observer at S.

A 1968 story that uses the gravitational time dilation effect in a striking fashion tells of a starship's visit to a supernova, accompanied by a fantastic alien life-form—a ball of intelligent plasma named Lucifer that is telepathic.[78] While the ship stands off at a distance of 500 million kilometers, Lucifer will approach much closer to the *event horizon* (see the Glossary) of a black hole at the center of the supernova explosion and communicate its findings to a human telepath on the ship. A physicist in the crew is curious about one point, and asks the human telepath the following question:

"I have wondered about one item. Presumably Lucifer will go quite near the supernova. Can you still maintain contact with him? The time dilation effect, will that not change the frequency of his thoughts too much?"

Lucifer, in fact, dies in the black hole even as he saves the ship from destruction, and the human telepath will hear his death scream for the rest of her life. As the physicist later explains to the ship's captain, telepathy is instantaneous and has no limiting range (there is no known physical basis for believing any of this, but it is crucial for story effect):

> "Remember the time dilation. He fell from the sky and perished swiftly, yes.
>
> But in supernova time. Not the same as ours. To us, the final stellar collapse takes an infinite number of years. . . . He will always be with her."[79]

3.4 The Lorentz Transformation

> "If only he'd paid more attention to mathematics in school."
>
> —a science fiction time traveler laments missed opportunities[80]

In this (and the next) section the math gets about as 'deep' as it gets in this book, but to leave it out struck me as a cheat. *You* can skip part (or all) of the math and simply read the prose, but it seemed unfair for me to make that decision for you.

We begin by imagining two distinct frames of reference. One we take to be stationary, and the other as moving at a uniform speed v with the respect to the first. The moving frame is said to be *boosted* with respect to the stationary frame. We orient these two coordinate systems so that the motion occurs along just one axis (the x-axis, as shown in Fig. 3.6, where I am using primed variables for the moving frame). That is, the two frames have coincident x axes, and parallel y and z axes that

---

[78] Poul Anderson, "Kyrie," in *The Road to Science Fiction* (J. Gunn, editor), volume 3, New American Library 1979.

[79] A mathematical discussion of how signals take forever (even though they are emitted in a finite time interval) to travel from the event horizon of a black hole to a distant receiver can be found in James B. Hartle, *Gravity: an introduction to Einstein's general relativity*, Addison Wesley 2003, pp. 264-268.

[80] D. Knight, "Extempore," in *Far Out*, Simon and Schuster 1961. Similar words ("If only I had more mathematics") were spoken by Einstein the day before he died — see Walter Isaacson, *Einstein: his life and universe*, Simon & Schuster 2007, p. 542.



Fig. 3.6 Two reference frames in relative motion

are moving apart at the constant speed v. Let's also imagine that there is a clock at the origin of each frame, and that at the instant the origins match the clocks are synchronized; that is, $t = t' = 0$ is the instant the two coordinate systems coincide.

We further imagine that there is an observer at the origin in each frame. At some arbitrary instant of time, each observer records the coordinates of the arbitrary point P in space, as measured in his system. These observers could, for example, agree to record the coordinates of P in their system when their clock reads 5 s. It seems immediately obvious (as it was for Newton) that $t = t'$; that is, time runs at the same rate in each frame and thus it makes sense to talk about "the same instant" at every point in space. (After reading the previous section you know this *not* true, but temporally forget that!) Thus, at this 'same instant' the stationary observer records (x, y, z) and the moving observer records (x', y', z'). What are the relationships between the primed and unprimed coordinates of P? That is, what mathematical transformation converts from one frame to the other?

The answer seems obvious:

$$y' = y$$
$$z' = z$$
$$x' = x - vt.$$

This transformation, called the *Galilean transformation* after the Italian Galileo Galilei (1564–1642), satisfies the relativity principle, which says that uniform motion leaves the laws of physics unchanged. For example, in the stationary system Newton's famous second law of motion for a constant mass m,

$$F = m\frac{d^2x}{dt^2}$$

becomes the identical-appearing form

$$F' = m\frac{d^2x'}{dt'^2}.$$

More precisely, *all* the laws of mechanics known to Newton are unchanged. Any frame of reference in which Newton's laws of mechanics hold true is said to be an *inertial* frame. Given one inertial frame, we can find infinitely many others simply by applying the Galilean transformation.

However, when the mathematical laws of electrodynamics were discovered by Maxwell in the nineteenth century, it was a shock to physicists to learn that the Galilean transformation does *not* leave Maxwell's equations unchanged in form; the transformed equations predict electromagnetic effects for the moving system that are *not* predicted to occur in the stationary system. This meant that there was theoretical support for the possibility that electromagnetic experiments might be devised to detect uniform motion, and this eventually led to the famous Michelson-Morley experiment of 1887. This experiment, sensitive enough to detect the motion of the Earth itself through space, failed to detect any such motion. The conclusion was clear: the new electromagnetic effects predicted by the Galilean transformation do not exist, and so the transformation must be wrong even though it works for the laws of mechanics. So—what is going on?

The answer is inspired, and again returns us to the cornerstone of relativity: the idea that the laws of physics, *all* the laws, should look the same to observers in uniform relative motion. That is, there is no special or preferred system of coordinates—*all* inertial systems are equivalent in physics. Evidence from an extremely broad variety of sensitive experiments had, by the end of the nineteenth century, convinced physicists that Maxwell's equations *are* correct. Thus, a new transformation was needed that leaves both the laws of mechanics *and* the laws of electrodynamics unchanged with uniform motion. But, a single transformation that works on Maxwell's equations and on the mechanical laws would therefore mean that Newton's mechanical laws as stated cannot be correct, and this was a breathtaking conclusion: Newton had been unchallenged for two centuries.

As it turns out, Newton's laws are *almost* right. The only correction required is that the mass of a moving body is not independent of motion, but rather varies as

$$m = \frac{m_0}{\sqrt{1-(v/c)^2}}$$

where m_0 is the so-called *rest mass* when $v = 0$.[81] This result says that m is infinite at $v = \mathrm{c}$ unless $m_0 = 0$ (as it is for a photon), which is another reason for the belief that accelerating a mass (such as a spaceship) up to the speed of light is impossible because it would require infinite energy (look back at note 68, too). With this modification, the transformation that leaves all the laws of physics unaltered in form by uniform motion is what is called the *Lorentz transformation* (after the same Lorentz the contraction effect is named for), who discovered it in 1904 by direct manipulation of Maxwell's equations:

$$\begin{aligned} y' &= y \\ z' &= z \\ x' &= \frac{x - \mathrm{vt}}{\sqrt{1 - (v/c)^2}} \\ t' &= \frac{t - \mathrm{vx}/c^2}{\sqrt{1 - (v/c)^2}}. \end{aligned}$$

In 1905 Einstein discovered how to derive these equations from a fundamental reexamination of space and time without concerning oneself about the details of specific physical laws.

By simple algebraic manipulation, the transformation equations can be rewritten as

$$\begin{aligned} ct &= \gamma ct' + \beta\gamma x' \\ x &= \beta\gamma ct' + \gamma x' \end{aligned}$$

where

$$\beta = \frac{v}{c}$$

and

$$\gamma = 1/\left(1 - \beta^2\right)$$

are dimensionless constants. In compact matrix form, the Lorentz transformation becomes

---

[81] This variation of mass with speed was experimentally observed in 1901.

$$\begin{bmatrix} ct \\ x \end{bmatrix} = \begin{bmatrix} \gamma & \beta\gamma \\ \beta\gamma & \gamma \end{bmatrix} \begin{bmatrix} ct' \\ x' \end{bmatrix}$$

and the symmetrical 2 × 2 matrix is called the Lorentz boost matrix or simply the *boost*. Notice that when $v = 0$ (zero boost) the boost matrix reduces to the identity matrix; that is, the two frames are one and the same with at most a shift in the location of the origins. Note, too, that $\beta = 0$ and $\gamma = 1$ for *any* v when c is infinite—that is, the boost matrix is again reduced to the identity matrix and the Lorentz transformation becomes the Galilean *if* c is infinite. But c is not infinite, and all the implications of special relativity are the direct result of the *finite* speed of light.

The Lorentz transformation contains two results I have mentioned earlier in the book. For example, in Chap. 2 it was mentioned that simultaneity is a relative concept in reference frames in relative motion. Let's see what the transformation says about that. Consider two events that occur specifically on the x-axis. They are simultaneous in the stationary system (at, say, time $t = T$) but are at different places (at, say, $x = X$ and $x = X + \Delta X$). Their occurrences in time for the moving observer are

$$t_1' = \frac{T - \mathrm{vX}/c^2}{\sqrt{1 - (v/c)^2}}$$

and

$$t_2' = \frac{T - \mathrm{v}(X + \Delta X)/c^2}{\sqrt{1 - (v/c)^2}}.$$

For the moving observer, therefore, the two events are *not* simultaneous, being separated in time by

$$t_1' - t_2' = \frac{v\Delta X/\mathrm{c}^2}{\sqrt{1 - (\mathrm{v}/\mathrm{c})^2}}.$$

Only if $\Delta X = 0$ (the two events occur at the same place) will $t_1' = t_2'$. That is, only if $\Delta X = 0$ are simultaneous events in one frame also simultaneous in another frame in relative motion.

And in the previous section we found that time runs slow in one frame as observed from another frame that is in relative motion. We can get this result from the t' equation of the Lorentz transformation by differentiating it with respect to t. Thus,

$$\frac{dt'}{dt} = \frac{1 - (v/c^2)\frac{dx}{dt}}{\sqrt{1 - (v/c)^2}}.$$

But since

$$\frac{dx}{dt} = v,$$

the speed of the moving frame as measured by the observer in the stationary frame, this gives

$$dt' = \sqrt{1 - (v/c)^2}\,\mathrm{dt}$$

which is the same result we obtained by analyzing the photon clock.

The Lorentz transformation contains other interesting implications beyond these. For example, mention has been made several times to the ‘relativity principle,’ the belief that uniform motion has no observable effect on the forms of physical laws. But how do we know who is moving and who is stationary? After all, a system moving to the right past a stationary system could just as well be thought as the stationary system, while it’s the *other* system that is moving to the *left* (at speed $-v$).

To study this question with the Lorentz transformation, we’ll invert the transformation (that is, solve for the unprimed variables in terms of the primed ones). What we get back is just what you probably thought—the Lorentz transformation with v replaced by $-v$. That is, the Lorentz transformation is symmetrical, so two observers in different frames of reference each say it is the *other’s* clock that is running slow! This follows immediately, in fact, from the original transformation written in matrix form. That is, multiplying through the earlier matrix equation by the inverse of the boost matrix, we get

$$\begin{bmatrix} ct' \\ x' \end{bmatrix} = \begin{bmatrix} \gamma & \beta\gamma \\ \beta\gamma & \gamma \end{bmatrix}^{-1} \begin{bmatrix} ct \\ x \end{bmatrix} = \begin{bmatrix} \gamma & -\beta\gamma \\ -\beta\gamma & \gamma \end{bmatrix} \begin{bmatrix} ct \\ x \end{bmatrix}.$$

The only difference between the original boost matrix and its inverse (which is, of course, the new boost matrix for the new interpretation of which frame is the moving one) is a change in sign for β, that is, in the sign of v. The inverse transformation is

$$y = y'$$
$$z = z'$$
$$x = \frac{\mathrm{x}' + \mathrm{vt}'}{\sqrt{1 - (\mathrm{v}/\mathrm{c})^2}}$$
$$t = \frac{\mathrm{t}' + \mathrm{vx}'/\mathrm{c}^2}{\sqrt{1 - (\mathrm{v}/\mathrm{c})^2}}.$$

As a final example of what the Lorentz transformation tells us, consider the so-called *addition of velocities* problem. Suppose you are in a high-speed spaceship traveling past Earth at speed v. Earth is the stationary system (with the unprimed variables), and the spaceship is the moving system (with the primed variables). Assume the x and x' axes are along the direction of motion. Imagine next that while standing in the nose of the spaceship, just as the spaceship passes Earth, you fire a gun in the direction of motion (away from the Earth), with the bullet exiting the gun with a muzzle speed of w. How fast is the bullet moving away from Earth? The common-sense answer in Galileo's time was $v+\mathrm{w}$, but we now know that the Galilean transformation is wrong. What does the Lorentz transformation say?

Inside the spaceship, the position of the bullet at time t' after the gun is fired is

$$x' = wt'.$$

From the inverse Lorentz transformation, the location of the bullet earth's frame is

$$x = \frac{x' + \mathrm{v}t'}{\sqrt{1-(v/c)^2}} = \frac{w+\mathrm{v}}{\sqrt{1-(v/c)^2}}t'.$$

The transformation also tells us that (using $x' = wt'$)

$$t = \frac{t' + \mathrm{v}x'/c^2}{\sqrt{1-(v/c)^2}} = \frac{1+\mathrm{wv}/c^2}{\sqrt{1-(v/c)^2}}t'.$$

Thus, the speed of the bullet in *Earth's frame* is

$$\frac{x}{t} = \frac{w+\mathrm{v}}{1+\mathrm{wv}/c^2}.$$

Notice that for a low-speed bullet ($w << c$) this result[82] is close to $w + v$, but at high values for w the result is very much different. Indeed, suppose we don't fire a gun at all, but rather replace it with a flashlight. Now, instead of a bullet, we shoot *photons* at $w = c$. The Galilean transformation would (incorrectly) say that a stationary observer on Earth would see the photons moving away at speed $v+\mathrm{c}$, which is a superluminal speed. The Lorentz transformation, however, says that the Earth observer would see a speed of

---

[82] This result was found by the French physicist Henri Poincaré (1854-1912) in June 1905, three months *before* the publication of Einstein's special theory of relativity which also contains the result. And it was Poincaré who first stated (in 1904) that "no velocity can surpass that of light, any more than any temperature could fall below the zero absolute."

$$\frac{c+\mathrm{v}}{1+\mathrm{cv}/c^2}=\frac{c^2(c+\mathrm{v})}{c^2+\mathrm{cv}}=\frac{c^2(c+\mathrm{v})}{c(c+\mathrm{v})}=c.$$

That is, no matter what the speed of the moving observer on the spaceship is, he sees the light from his flashlight traveling at the same speed as does the stationary observer back on Earth. This peculiar effect is unique to the speed of light ($w=\mathrm{c}$). We've derived it here as a consequence of the Lorentz transformation, but in fact Einstein actually did things in reverse order. That is, he began by *postulating* the invariance of the speed of light[83] for all observers in uniform motion, combined that with the principle of relativity which says all physical laws look the same to those observers, and so derived the Lorentz transformation using no mathematics beyond high school algebra.

A mathematically elegant alternative derivation of the addition-of-velocities formula can be done by simply noticing that the condition of two successive boosts should be, itself, a boost. Thus, if we have a frame moving relative to a second frame (which is itself moving relative to a third frame), then the boost matrix of the first frame relative to the third frame is the product of the two individual boost matrices. That is,

$$\begin{bmatrix}\gamma_3 & \beta_3\gamma_3\\ \beta_3\gamma_3 & \gamma_3\end{bmatrix}=\begin{bmatrix}\gamma_2 & \beta_2\gamma_2\\ \beta_2\gamma_2 & \gamma_2\end{bmatrix}\begin{bmatrix}\gamma_1 & \beta_1\gamma_1\\ \beta_1\gamma_1 & \gamma_1\end{bmatrix}.$$

From this it is easy to show (if you know how to multiply matrices!) that

$$\beta_3=\frac{\beta_1+\beta_2}{1+\beta_1\beta_2}.$$

Substitution of

$$\beta_1=\frac{w}{c},\ \beta_2=\frac{v}{c}$$

immediately gives the addition-of-velocities formula.

A failure to understand the implications of the invariance of the speed of light resulted in two stupendous errors in the story "To the Stars," cited in note 74. At all times an officer stands watch on the bridge of a near light-speed rocket ship to be sure the ship doesn't accidently *reach* the speed of light. This is to be avoided (according to the author) because to reach the speed of light would cause the ship to

---

[83] Einstein's postulate was experimentally confirmed in 1932.

"hang there forever unmoving [in time] . . . locked, protected and condemned to eternity by zero time." This horrible state is so easy to stumble into (the author was apparently unaware that it would require *infinite* energy) that occasionally the ship has to fire a 'check-blast' from its forward rocket tubes to slow down! Equally absurd is the means by which the development of this 'fatal' condition is detected: the nose of the ship mounts a forward-pointing light source (our earlier flashlight) and so, if the ship is getting too near the speed of light, it will start to *overtake* the photons emitted by that source!

The biggest puzzle of all, actually, is why the editor of *Astounding Science Fiction* let such a technically goofy story appear in a magazine recognized for its usual faithfulness to known science. Particularly so since the story appeared in 1950 and, as long ago as December 1937, none other than Isaac Asimov (then 17 years old) had written a letter to the editor[84] giving the proper interpretation of what happens when $v = \mathrm{c}$. Here's what the young Asimov wrote (notice the early hint of his life-long pessimism concerning time travel to the past that appears near the end of his letter):

> "The effect on time of increasing speeds is . . . well known. Relativity states that as speed approaches that of light, time slows up until at 186,000 miles a second, time (so to speak) stands still. This seems to refute statements found in so many astronomy books (and science fiction stories) that even at the speed of light it would take four years to reach the nearest star. No such thing! As time halts at the speed of light, a person traveling from Alpha Centauri to the solar system, or vice-versa, would not be aware of any lapse of time. In that sense the speed of light is infinite (as was thought in ancient times). This by the way offers an entirely scientific (if impractical) means of travel into the future. Say that someone wants to see how the world would look a hundred years from now. His procedure would be as follows: getting into his spaceship, he would proceed to a spot fifty light-years away at the speed of light. The journey would, for him, be practically instantaneous (due to the curious behavior of time at the speed of light). But fifty years would have elapsed on earth. He makes the return trip at the same speed. Another fifty years lapse on earth and he lands a hundred years after his time. With this system, however, it would be impossible to travel into the past, so I don't think it will ever be adopted."

Young Asimov missed an important detail concerning the reversal of the spaceship's direction of travel for the return to Earth, and I'll come back to it later in this chapter. But certainly he displayed a *far* better knowledge of the physics of time than did the author of "To the Stars" (who was, by the way, L. Ron Hubbard, a prolific writer of fantasy and science fiction before founding the Church of Scientology).

---

[84] The editor who bought "To the Stars" was the same editor editor of *Astounding* when Asimov's letter appeared, and so he was certainly aware of it.

3.5 Spacetime Diagrams, Light Cones, Metrics, and Invariant Intervals

> "Come back when you know tensor calculus and I'll explain to you about n-dimensional forces and the warping of world-lines."
>
> —a science fiction physicist's reply after being asked how his time machine works[85]

It is helpful in discussions about the spacetime of special relativity to use what are called *Minkowski spacetime diagrams*. These are plots of the spacetime coordinates of a particle; the resulting curve is called the *world line* of the particle. Such diagrams are four-dimensional—three space axes and one time axis—and hard to visualize, much less draw on a flat sheet of paper! The convention is to make do, whenever possible, with a simplified spacetime that has just one space axis (horizontal) and one time axis (vertical). As you'll recall from Chap. 1, physicists often call such a simplified diagram a *toy spacetime*.

So, for a particle at rest in some observer's frame of reference, its spacetime diagram for that observer is a *vertical* world line. If the particle is not at rest then its world line will tilt away from the vertical; the greater the speed the greater the deviation from the vertical. Accelerated particles will have world-lines that *curve* away from the vertical. Straight, uncurved world lines represent unaccelerated particles, that is, particles experiencing no forces and so in free fall. Such a world line is called a *geodesic*. In Fig. 3.7 the world lines for these various cases are shown on the same axes. It is assumed in the figure that all three particles are at $x = x_0$ when $t = 0$.



Fig. 3.7 World lines of three particles

---

[85] Poul Anderson, "The Little Monster," in *Science Fiction Adventure from WAY OUT* (R. Elwood, editor), Whitman 1973.



Fig. 3.8 A time traveler and his world line

Spacetime diagrams were embraced decades ago by philosophers looking for 'scientific' ways to support their position on time travel (whatever it might be), as opposed to the mere verbiage of traditional colleagues. A famous example of this is a 1962 paper by the Harvard philosophy professor Hillary Putnam (note 74 in Chap. 1). There we are asked to imagine the spacetime diagram of one Oscar Smith who, in Fig. 3.8, is at spatial location A next to his time machine. At time t_0 Oscar has not yet gotten into his time machine. A little later, at time t_1, we suddenly see not only Oscar at A but also *two more* Oscars who have appeared (apparently out of thin air) moving away from spatial location B! Between t_1 and t_2 we see the original Oscar at A and the two mysterious Oscars at B (for a total of three Oscars, labeled in the figure as Oscar$_1$, Oscar$_2$, and Oscar$_3$) move forward in time—but one of the new Oscars (Oscar$_2$) lives a decidedly odd existence in that his life seems to be running in reverse!

Eventually, at time t_2, the original Oscar$_1$ and the weird, reverse Oscar$_2$, merge and seemingly annihilate one another, vanishing into thin air to leave only a single Oscar (Oscar$_3$) for all time after t_2. Putnam argues that, although strange, what has just been described is still sensible and that, indeed, the very fact that we can draw the spacetime diagram of Fig. 3.8 supports the case for backward time travel. He claims this because although the spacetime diagram does show time increasing upward for all three Oscars (that is the time direction for an external observer) there is actually no 'spontaneous creation' or 'mutual annihilation' and all is sensible *if* Oscar$_2$ is understood actually to be a time traveler into the past with *his* time direction thus pointed opposite to that of the 'other two' Oscars. There is, of course, just *one* Oscar!



Fig. 3.9 Anti-matter via backward time travel

As mentioned back in Chap. 1, Putnam's suggestion was rebutted (see that chapter's note 76) by what is (in my opinion) an even less plausible mechanism for Putnam's kinked spacetime than is Putnam's invocation of time travel. That critic advocated, instead, an explanation based on matter transmitters and anti-matter, the latter an idea he credits to Feynman (who actually got it from Wheeler). In a paper by Feynman we do find the famous suggestion that a positron that appears to us to be moving forward in time is actually an electron traveling backward through time.[86] Logically, that greatly weakens the critic's view, because it puts him in the position of using anti-matter (explained in terms of backward time travel) to argue *against* backward time travel! But let's ignore that concern, give the critic the benefit of the doubt, and explore how anti-matter and backward time travel are imagined to be connected.

Feynman asks us to imagine the process shown in Fig. 3.9. Gamma ray A spontaneously creates an electron-positron pair, with electron$_2$ moving off to some distant region while the positron soon meets with electron$_1$, resulting in mutual annihilation and the production of gamma ray B. This description involves *three* particles, and each segment of the kinked line is a distinct particle. But Feynman said there is another way to look at this, a way that involves just *one* particle. According to Feynman, the kinked line in Fig. 3.9 (which should remind you of Oscar's kinked world line) is the world line of a single electron; the middle

---

[86] R. Feynman, "The Theory of Positrons," *Physical Review*, September 15, 1949, pp. 749-759. In a paper published the year before ("A Relativistic Cut-Off for Classical Electrodynamics," *Physical Review*, October 1948, pp. 939-946), he wrote "This idea that positrons might be electrons with the proper time reversed was suggested to me by Professor J. A. Wheeler." The identification of anti-matter with backward time travel occurred in science fiction (see note 124 in Chapter 1) almost simultaneously with Wheeler's speculation.

segment, that we call a positron, is just the electron traveling backward in time, and so we must reverse the arrowhead on it (indicating the opposite of the direction shown in Fig. 3.9).

There are two central questions at this point. First, why is a positron (with positive electric charge) moving forward in time mathematically (and physically) equivalent to a negatively charged electron moving backward in time? The answer is that the reversal in charge sign, which results from the reversal of the electron's proper time, follows from the TCP theorem that was mentioned in Chap. 2 (see note 38 there). And second, what causes the electron to suddenly move backward in time? Picturesquely, the electron is recoiling from the emitted burst of gamma ray B. Similarly, the absorption of the energy of gamma ray A by the electron that is recoiling backward in time causes a second recoil, giving the world line of what was originally called electron$_2$. This reinterpretation of a kinked spacetime diagram was described as follows (in Feynman's famous words): "It is as though a bombardier flying low over a road suddenly sees three roads and it is only when two of them come together and disappear that he realizes that he has simply passed over a long switchback in a single road."

In a later paper[87] Putnam's critic presented another line of attack against Putnam's interpretation of spacetime diagrams as lending support to time travel. There the critic observed that the presence of the time-reversed Oscar$_2$ shows that the "world of the Oscars" is not *temporally orientable*. A temporally orientable spacetime is one in which *every* point in it agrees with its local neighbors on the directions of past and future—a condition clearly *not* satisfied for the case of Oscar$_2$. As the critic pointed out, the first time travel spacetime discovered, the Gödel universe, *is* temporally orientable, and so in it the ambiguity of Oscar$_2$ (whether he is traveling backward in time as opposed to living forward 'in reverse') does not occur. That is, the critic agreed with Putnam's acceptance of the conceivability of time travel to the past, but not with his use of Feynman's concept of anti-matter as time-traveling matter. That critic wasn't alone in that opinion.

One physicist, for example, wrote of "Feynman's rather loose talk of particles 'traveling' backward . . . in time,"[88] and the well-known philosopher John Earman declared "It is true that Feynman uses the slogan 'Positrons are electrons running backward in time,' but it is dangerous to draw conclusions from slogans."[89] I am not sure what Earman meant by "slogans": a careful reading of Feynman indicates that he actually took the matter quite seriously.[90] In his 1949 positron paper (note 86), for example, he wrote that "the idea that positrons can be represented as electrons with proper time reversed relative to true time has been discussed by the author and others,"[91] and also that "Previous results suggest waves propagating . . . toward the past, and that such waves represent the propagation of a positron."

---

[87] See R. Weingard in note 114 in Chapter 1.

[88] H. Price, "The Asymmetry of Radiation: Reinterpreting the Wheeler-Feynman Argument," *Foundations of Physics*, August 1991, pp. 959-975.

[89] J. Earman, "On Going Backward in Time," *Philosophy of Science*, September 1967, pp. 211-222.

[90] Feynman declares the view of a positron as a time traveling electron to be of value, for example, in his famous book *Quantum Electrodynamics*, W. A. Benjamin 1961, p. 68.

In any case, spacetime diagrams are highly useful in discussing time travel, but they do have some curious twists. In our everyday world, a path that joins two points on a surface with the *minimum* length is called a geodesic of that surface. As you'll see later in this chapter spacetime geodesics do indeed possess an extremal property, but rather than being a minimum it is a *maximum* property. Spacetime diagrams can be misleading on this matter, so it is important to remember that such diagrams are not a perfect representation of all the properties of a spacetime.

It is customary to draw spacetime diagrams with the speed of light as unity ($c = 1$). That is, a distance of 300,000 km on the space axis is represented by the same extension as is one second on the time axis. This means that the world line of a photon is tilted away from the vertical time axis by 45°. Because photons can travel in both space directions (to the left and to the right) in the two-dimensional spacetime we can draw on a piece of paper, and because the speed of light is the limiting speed of the universe, we can represent the collection of all possible world lines as those paths that *never* tilt more than 45° away from the vertical, which forms what is called a *light cone* in spacetime, as shown in Fig. 3.10 (which attempts to represent a *three*-dimensional spacetime, one with two space—imagine a y-axis, out of the paper, perpendicular to both the x and t axes—and one time dimension).

In Fig. 3.10 I have taken $x = y = 0$ at $t = 0$ for all the possible world lines involving speeds below the speed of light. Let's agree to call this spacetime point the Here-Now. Then, spacetime points in the upward half of the light cone are in the Future of Here-Now; similarly, spacetime points in the lower half of the light cone are in the Past of the Here-Now. We can draw a straight world line from the Here-Now to any point in the Future half-cone with a tilt of less than 45° away from the vertical, which means that a massive particle could travel from the Here-Now to that point at less than the speed of light. Similarly, a massive particle starting at any point in the Past half-cone could have reached the Here-Now by traveling at less than the speed of light. Such a world line is called *timelike* because its projection on the time axis is greater than its projection on a space axis—they are the world lines connecting spacetime points that are potentially causally linked. That is, an event at a spacetime point in the Past half-cone could have had an effect on the event at the Here-Now, even though its influence propagated at less than the speed of light. Also, an event at the Here-Now could potentially affect the event at any spacetime point in the Future half-cone of the Here-Now.

Any points in the regions of spacetime outside the Future and Past half-cones *cannot* be reached from the Here-Now except by world lines tilted more than 45°

---

[91] The "others" Feynman had in mind included, in particular, the eminent Swiss physicist Ernest C. G. Stϋkelberg (1905-1984), who in a 1942 article in the journal *Helvetica Physica Acta* also wrote of waves scattering backward in time.



Fig. 3.10 A light cone in spacetime

away from the vertical. Such world lines, which represent travel at a speed faster than light, are called *spacelike* because their projections on a space axis is greater than their projections on the time axis. It is impossible for these world lines to connect causally linked events, and collectively they form the Elsewhere of the Here-Now. Notice that every point in spacetime has its own light cone. If A and B are causally linked, then if B is in the Future half-cone of A, then A is in the Past half-cone of B.

The imagery of the light cone is often useful in making seemingly quite abstract ideas appear transparent. For example, can an observer predict his own future from perfect knowledge of his own past? The easy answer is “No, because quantum uncertainties prohibit perfect knowledge of even the present, much less the past.” But suppose we ignore quantum mechanics and limit our question to a universe that obeys only classical physics (which includes the special and general theories of relativity). Surprisingly (perhaps), the answer is *still* no. Having perfect knowledge of your own Past half-cone doesn’t include knowing the *entire* past, so if you attempt to predict your own future (say, 1 min from now), there can be influences in Elsewhere that will arrive in the future (say, 59 s from now) about which you



Fig. 3.11 World line of a particle traveling backward in time from A to B

presently, by definition, cannot have any knowledge. And without that knowledge, you cannot predict. As one writer amusingly concludes a tutorial on this topic, "the prospect of predicting the future looks pretty bleak."[92]

A spacetime diagram does not always have to have future directed world lines. If a particle moves backward through time, assuming such a thing is possible, then the diagram can show this by having the world line double back on itself, as in Fig. 3.11 (in which the world line curves back and comes arbitrarily close to itself: it is the world line of a particle that visits itself in the past). Note that the world line in Fig. 3.11 does not actually touch or cross itself, because that would represent more than just a visit—it would represent a particle occupying the same spatial location at the same time as its earlier self. That would be catastrophic and, because it *did not* happen it *cannot* happen. Since the arrowheads on the world line always point in the direction of the local future of the particle, if the 'particle' is actually human then increasing memories are formed in the direction of the arrows. The time traveler at B has more memories than he does at A, even though A and B are nearly identical points in spacetime.

There is a problem with Fig. 3.11 that you may have caught. It is impossible to draw such a doubled-back world line in such a way that *at all places* it never tilts more than 45° from the vertical. That is, at least some portion of the world line will have

$$\left|\frac{\mathrm{dx}}{\mathrm{dt}}\right| > 1$$

which represents superluminal motion (we'll return to this in Chap. 5). One way to keep a bent-back world line always subluminal is to arrange for the light cones along the world line to be tilted relative to each other, as shown in Fig. 3.12, which

---

[92] M. Hogarth, "Predicting the Future in Relativistic Spacetimes," *Studies in the History and Philosophy of Science*, December 1993, pp. 721-739.



Fig. 3.12 Tilted light cones in a curved spacetime (the future halves are shaded)

is possible only in a *curved* spacetime. This is an illustration of how general relativity *locally* obeys special relativity's demand that nothing travels faster than light and yet, *globally*, in curved spacetime, things are not so simple. In flat spacetimes all light cones are always 'aligned,' but in curved spacetimes they (generally) are not, and from that can come time travel to the past.[93]

Tilted light cones is the physics behind backward time travel around a rotating Tipler cylinder, for example, a particular time machine we'll discuss later in Chap. 5. Light cone tipping is, in fact, *essential* for time travel to the past. The mere presence of mass tips light cones ('warps spacetime'), but the effect is unnoticeable in everyday life on Earth. A truly enormous mass density is required to tip nearby light cones over so that their Future halves noticeably open up toward the massive body. If the massive body is additionally set to rotating, then a further consequence of Einstein's general theory is that the local light cones are tilted additionally in the direction of rotation. That is, the Future half-cones in spacetime open-up both toward the body and in the direction of the rotation.

It should now be clear that the only way a world line can bend back on itself for a close encounter visit is for both x and t to change. In other words, the world line of a particle that remains fixed in space and reverses just its time direction *runs into itself*. This is why the classic fictional time machine of H. G. Wells could not possibly work. A real time machine must move in space as well as through time, as does a Gödelian rocket (or, for that matter, as does the DeLorean time car in the *Back to the Future* films). The idea of warping world lines, to support time travel to the past, entered science fiction at an early date. For example, when the inventor of the time machine in a 1930s tale[94] is asked about the principle underlying his gadget, he replies "An electro-magnetic warping of the spacetime continuum.

---

[93] What is meant by a spacetime being *flat* will be formalized when we get to spacetime *metrics* later in this section. The Minkowski spacetime of special relativity is a flat spacetime, has no tilted light cones, and as such does *not* support time travel to the past.

[94] N. Schachner, "When the Future Dies," *Astounding Science Fiction*, June 1939.

The machine, if it works, will slide around the world-line of events and reappear at any specified time and place."

Using the Lorentz transformation equations from the previous section, we can establish quite general relationships between events in the Future, Past, and Elsewhere regions of spacetime. For example, (1) All events in the Future/Past for the Here-Now observer are in the Future/Past for any other nearby, relatively moving observer; (2) Any event in Elsewhere can appear to be simultaneous with the Here-Now for some observer and not simultaneous for another observer; and (3) The temporal ordering (the relations of *before* and *after*) of causally related events is the same for all observers. This is not so for events that are not causally related; if two events have a spacelike separation, then two observers can disagree over the temporal ordering of the events. This is, in fact, the basis for the two-wormhole and the cosmic string time machines, both of which will be discussed in Chap. 6. All these statements are easy to prove.

Consider, for example, statement (1). From the previous section we have (with $c = 1$)

$$t' = \frac{t - \mathrm{vx}}{\sqrt{1 - v^2}} \text{ and } x' = \frac{x - \mathrm{vt}}{\sqrt{1 - v^2}}$$

where t and x are the coordinates of some event A as measured by the observer in the stationary reference frame, and t' is the time measured by the observer in the reference frame moving at speed v. Thus

$$x'^2 - t'^2 = \frac{(x - \mathrm{vt})^2 - (t - \mathrm{vx})^2}{1 - v^2} = [\text{after a little algebra}]\ x^2 - t^2.$$

For the stationary observer the criterion for an event to be in the Future half-cone is $t > |x|$, that is, $t^2 > x^2$. Thus, $x^2 - t^2 < 0$ for all Future events. But the foregoing result then says $x'^2 - t'^2 < 0$, too, which is the moving observer's criterion for the event being in his Future half-cone. The same sort of argument shows that the two observers also agree on Past events.

Next, suppose that two events A and B occur such that the stationary observer measures them to be $\Delta T = t_B - t_A$ apart in time. Then, we can establish statement (2) by writing

$$t'_A = \frac{t_A - \mathrm{v}x_A}{\sqrt{1 - v^2}} \text{ and } t'_B = \frac{(t_B + \Delta T) - \mathrm{v}x_B}{\sqrt{1 - v^2}}$$

and so

$$\Delta T' = t'_B - t'_A = \frac{\Delta T + v(x_A - x_B)}{\sqrt{1 - v^2}}.$$

From this we have $\Delta T' = 0$ (that is, simultaneity) for the two events for the special observer moving at the speed

$$v = \frac{\Delta T}{x_B - x_A}$$

and this speed is less than the speed of light for the condition $x_B - x_A > \Delta T$. This is, of course, the condition for event B to be in the Elsewhere of event A. In fact, we can even have $\Delta T' < 0$ (with $\Delta T > 0$) for $v < 1$ in this case of spacelike separation of A and B. That is, a stationary observer and a sublight-speed moving observer can disagree about the temporal ordering of events with spacelike separation.

Similarly, for event B to be in the causal Future of event A, we have the condition $x_B - x_A < \Delta T$. Then,

$$\Delta T' = \frac{\Delta T - \mathrm{v}(x_B - x_A)}{\sqrt{1 - v^2}} > \frac{\Delta T - v\Delta T}{\sqrt{1 - v^2}} = \Delta T \frac{1 - \mathrm{v}}{\sqrt{1 - v^2}}.$$

Thus, $\Delta T > 0$ says $\Delta T' > 0$ for $v < 1$, and this establishes statement (3).

If we were drawing diagrams with both axes representing space (a plot of y versus x, for example), we would normally define a *distance metric* for the diagram using our everyday ideas about distance. That is, we could say that if we make differential movements of dx and dy along the two coordinate axes, then the differential distance ds is given by

$$(ds)^2 = (dx)^2 + (dy)^2.$$

This is, of course, just the Pythagorean theorem for the 'Euclidean' or 'as the crow flies' distance function. But it is not the only possible distance function. A distance function has several interesting mathematical properties,[95] but the one we are particularly interested in here is its invariance with respect to the coordinate system. For example, if we draw a line segment on a flat sheet of paper, the physical distance between its end-points does not depend on how we happen to select the x and y axes, a fact illustrated in Fig. 3.13 with the addition of a rotated and translated primed system. The coordinates for the endpoints A and B are obviously different in the two coordinate systems, but we still find that

$$(dx)^2 + (dy)^2 = (dx')^2 + (dy')^2.$$

---

[95] Mathematicians have defined the general properties of a distance function as follows: if A and B are any two points, and if $d(A,B)$ is the distance between A and B , then (1) $d(A,B) = d(B,A)$; (2) $d(A,B) = 0$ if and only if $A = B$; and (3) if C is any third point, then $d(A,B) \leq d(A,C) + d(C,B)$. The Pythagorean distance function possesses all three of these properties, but so do many other functions (for example, $ds = |dx| + |dy|$).



Fig. 3.13 Rotated/translated coordinate systems

We say that the Pythagorean distance function is *invariant*, that it is the same for all coordinates systems that are simply rotations and/or translations of each other.

We know that different observers, if in relative motion in the same spacetime, will see different space and time coordinates for the same event. Thus, it is natural to ask 'what is the metric for flat spacetime?' Is there, in fact, a metric that gives the same *distance* between two events for all observers? We might try to generalize in the obvious way from the Pythagorean theorem, and write

$$(ds)^2 = (dt)^2 + (dx)^2 + (dy)^2 + (dz)^2$$

where now all four dimensions are included. We would then ask ourselves whether it is true that

$$(ds)^2 = (ds')^2 = (dt')^2 + (dx')^2 + (dy')^2 + (dz')^2?$$

For our simple two-dimensional spacetime, this question reduces to asking whether

$$(dt)^2 + (dx)^2 = (dt')^2 + (dx')^2?$$

Using the Lorentz transformation equations from earlier, it is easy to discover that the answer is no. The 'natural' generalization of Pythagorean distance for flat, two-dimensional spacetime fails when four dimensions are included. So, what do we do now? Recalling the words of Professor Mundle from *Some First Words* (see note 23 there), we might wonder whether this difficulty could result from the fact that there is no fourth direction along which the time axis can point at right angles to the three space directions? At least, there is no *real* direction—but perhaps there is an imaginary one. Accordingly, with $= \sqrt{-1}$, let's try

$$(ds)^2 = (idt)^2 + (dx)^2 + (dy)^2 + (dz)^2 = -(dt)^2 + (dx)^2 + (dy)^2 + (dz)^2.$$

Using *imaginary time*, something that seems to be in the realm of science fiction, has resulted in a change in the sign of $(dt)^2$.

This is a crucial change, however, because this new metric *is* invariant. For a reason to be explained in the next section, I will use the negative of this metric (a choice that has no impact on the invariance property) and so write

$$(ds)^2 = (dt)^2 - (dx)^2 - (dy)^2 - (dz)^2.$$

For our simplified two-dimensional spacetime this reduces to

$$(ds)^2 = (dt)^2 - (dx)^2.$$

As before, the Lorentz transformation equations (with $c = 1$) are

$$t' = \frac{t - \mathrm{vx}}{\sqrt{1 - v^2}} \text{ and } x' = \frac{x - \mathrm{vt}}{\sqrt{1 - v^2}}.$$

If we then calculate dx' and dt' from these equations, using

$$dx' = \frac{\partial x'}{\partial x} dx + \frac{\partial x'}{\partial t} dt, dt' = \frac{\partial t'}{\partial x} dx + \frac{\partial t'}{\partial t} dt$$

which are the fundamental relations for the *total* differential[96] of a function of two variables, and insert the results into $(dt')^2 - (dx')^2$, we quickly discover the invariance property of this quantity (a result we actually found earlier, in a different way, when we showed that observers in relative motion agree about what events are in the Future and what events are in the Past). Thus,

$$(dt')^2 - (dx')^2 = (dt)^2 - (dx)^2.$$

This quantity, on either side of the equality, is called the spacetime *interval* between the two events separated in flat spacetime by either dt, dx, dy, and dz, or by dt', dx', dy', and dz'. The observers in the unprimed and the primed systems see different individual space and time separations for two events, but they see the same

---

[96] The $\frac{\partial}{\partial x}$ and $\frac{\partial}{\partial t}$ symbols denote the *partial* derivatives with respect to x and t (see any good calculus book to brush-up on this). The rest of this chapter *will* have some more math in it, involving derivatives and even an integral or two, but nothing beyond freshman calculus. I've included it mostly for those who would feel cheated without *some* math!

interval. A single time coordinate, and three space coordinates, are said to form a *four-vector that is invariant under Lorentz transformation*. There are, in addition, other four-vectors that are also invariant under Lorentz transformation, such as the energy-momentum, velocity, and force four-vectors; all these quantities have invariants that are formed the same way, by taking the difference of the squares of the time components and the sum of the squares of the space components. The intrusion of the square root of minus one, in the time coordinate of the metric, seems a pretty clear indication that time *is* different from space.[97]

But still, the spatialization of time is nonetheless deeply embedded in Western culture. For example, when writing her popular 1978 book, drawing historical parallels between the fourteenth and twentieth centuries, Barbara Tuchman titled it *A Distant Mirror*, and not *An Old Mirror*. The mathematical mixing of space and time appeared quite early in science fiction, but often in comically mangled form. In one such tale, for example, as an evil scientist uses his time machine to transport captives into the past, he tells them, "We've got a longish journey before us, ten thousand years more, multiplied by the fourth power of two thousand miles."[98]

In general relativity, the metric of any four-dimensional spacetime has the structure of what mathematicians call a *symmetric quadratic Riemannian form*:

$$(ds)^2 = \sum_{i=1}^{4}\sum_{j=1}^{4} g_{ij}(dx_i)\left(dx_j\right), g_{ij} = g_{ji}$$

where $x_1 = t$, $x_2 = x$, $x_3 = y$, and $x_4 = z$, and the 16 g's are all functions of these four variables. (Because of the symmetry condition, only 10 of the g's are independent.) In this notation, a *flat* spacetime is mathematically characterized by $g_{11} = 1$, $g_{22} = g_{33} = g_{44} = -1$, $g_{ij} = 0$ for all $i \neq j$. Now, for a given spacetime, one can arbitrarily choose an infinity of coordinate systems. If just one of this infinity of systems is such that the ± 1, 0 values for the g's occur, then that spacetime is *globally* (that is, everywhere) flat. If no such coordinate system exists, then that spacetime is necessarily *curved*—I'll give you a more intuitive view of curvature in just a bit. (If this notation is extended to a fifth dimension[99] by including the additional coordinate x_5, then there are an additional eight off-diagonal g's and so four new *independent* g's. These are just sufficient to describe the electromagnetic field, too, along with the gravitational field described by the other ten g's. That is what is meant by saying five-dimensional spacetime 'unifies' gravity with electromagnetism.) There is a g_{55}, too, which could be allowed to model a slowly varying gravitational constant, as suggested by Dirac in 1938.

---

[97] Writing in 1972, one famous physicist said of his first encounter with the metric of special relativity (Minkowski spacetime), "Now, when I saw that minus sign [in $-(dt)^2$], it produced a tremendous effect on me. I immediately saw that here was something new." See P. A. M. Dirac, "Recollections of an Exciting Era," in *History of Twentieth Century Physics* (C. Weiner, editor), Academic Press 1977.

[98] V. Rousseau, "The Atom Smasher," *Astounding Stories*, May 1930.

[99] The fifth dimension was introduced in the 1920s by the German physicist Theodor Kaluza (1885-1954), but just what the nature of this fifth dimension might be remains a mystery. A few years after Kaluza, the Swedish physicist Oscar Klein (1894-1977) speculated that it might be a spatial dimension curled-up in a tiny circular path, so tiny that we don't notice it; the issue remains open. The idea of a fifth dimension appeared early in pulp science fiction, as in the January 1931 tale "The Fifth-Dimension Catapult," (*Astounding*) by Murray Leinster.

The g functions are the components of the so-called *metric tensor of the second rank* (see the last discussion question for more on what this means) of that spacetime. The g's at each point in spacetime are related to the curvature of spacetime at that point, which in turn is dependent on the g's and on the energy density at that point. In fact, the ten equations for the g's, which *are* the famous Einstein gravitational partial differential field equations, are both nonlinear and coupled. That is, each g_{ij} is in general a nonlinear function of all the other g_{ik}, which accounts for the notorious difficulty[100] in finding analytical solutions to the field equations except in certain highly special cases, such as the spacetime of spinning spheres and rotating infinite cylinders.

What does it mean to 'solve' the field equations? It is useful to think of the equations schematically as follows:

local geometry of spacetime ← local density, momentum and stress of the mass-energy of spacetime where the direction of the arrowhead means that the 'usual' practice is to assume the right-hand side (the so-called stress-energy tensor) as given, and then attempt to calculate the left-hand side. If the attempted calculation can be done, then one has solved the field equations for the spacetime geometry that is associated with the assumed mass-energy distribution.

Suppose, however, that we reverse the direction of the arrowhead. That is, suppose we assume a desired geometry. That is what Einstein did when he assumed the geometry of a *static* (non-expanding) universe and solved for the required mass-energy. What he found was just what had been observed by astronomers up to that time—a multitude of 'grains of matter' (what physicists call *dust*) plus the infamous cosmological constant. The constant, with its repulsive gravity, was needed to counteract the ordinary gravitational attraction of the stars that tends to pull them together. The later discovery that the universe is not static, but rather is expanding, rendered Einstein's solution moot.

Now let's go Einstein one better, and assume a spacetime geometry that contains closed timelike curves (a time machine, in other words) and then try to calculate the mass-energy distribution required by that spacetime. If that can be accomplished—and in fact the field equations themselves provide an algorithmic means of solution in this direction—then the physicist's work is done. The required mass-energy distribution requirements are put out to bid to 'spacetime engineers' and the lowest bidder 'simply' constructs that mass-energy distribution and so builds us our time machine! When the calculations are done, however, what has happened without fail, at least up to now, is that the resulting mass-energy distribution comes out with an 'unphysical' nature, a technical way of saying our spacetime engineer wouldn't know *how* to assemble the required mass-energy distribution. What is meant by 'unphysical' will be explored, in the particular case of wormhole time machines, in Chap. 6.

---

[100] An elementary, quite interesting discussion of the enormous computational complexity of the field equations is presented in Richard Pavelle and Paul S. Wang, "MACSYMA from F to G," *Journal of Symbolic Computation*, March 1985, pp. 69-100.

The 16 g's for a four dimensional spacetime are often written in the form of a 4 × 4 matrix. In fact, the metric tensor is of the *second* rank precisely because a matrix has a *two*-dimensional form; scalars and vectors, which have forms of zero and one dimension, are tensors of rank zero and one, respectively. The collection of the algebraic signs of the main diagonal terms (the g_{ii}) is called the *signature* of the metric tensor. The signature of flat (Minkowski) spacetime is thus written as [+, −, −, −]; in more general (curved) spacetimes, this same signature is called *Lorentzian*. By contrast, the signature of a four-dimensional Euclidean space is [+, +, +, +]. This signature is called *Riemannian*. The geometry of flat, Minkowski spacetime is not Euclidean geometry because the spacetime signature of its metric has both plus *and* minus signs. As an uncurved spacetime, Minkowski spacetime *has no gravity*; to get gravity, we need a curved spacetime.

The idea of linking the curvature of a four-dimensional space to physical phenomena is the signature feature of general relativity, but it actually pre-dates Einstein by decades. It can be found, for example, in the work of the British mathematician William Kingdon Clifford (1845–1879), done in the 1860s and 1870s before Einstein's birth (in the year of Clifford's death). In his posthumously published book *The Common Sense of the Exact Sciences* (1885), Clifford wrote "We may conceive our space to have everywhere a nearly uniform curvature, but that slight variations of the curvature may occur from point to point and themselves vary with time. These variations of the curvature with time may produce effects which we not unnaturally attribute to physical causes independent of the curvature of our space. We may even go so far as to assign to this variation of the curvature what really happens in that phenomenon which we term the motion of matter." It isn't a long jump from "motion of matter" to gravity![101]

Not everyone enthusiastically embraced this new, radical view of nature. For example, the great Scottish mathematical physicist James Clerk Maxwell (1831–1879), of Maxwell's equations fame, who knew Clifford through their common membership in the London Mathematical Society, summarily dismissed this part of Clifford's work as simply the speculations of a "space crumbler." Decades later, Einstein faced the same rejection when the eminent British astronomer Sir James Jeans declared "Einstein's crumbling of his four-dimensional space may . . . be considered to be . . . fictitious."[102]

---

[101] Clifford almost surely found inspiration in this part of his work from the even earlier efforts of the German mathematician Bernhard Riemann (1826-1866). See, for example, Clifford's translation of Riemann's famous 1854 lecture "On the Hypotheses Which Lie at the Bases of Geometry," *Nature*, May 1, 1873, pp. 14-17, and continued in the next issue (May 8, 1873, pp. 36-37).

Spacetime geometries are not easy concepts to grasp, and the metrics of curved spacetimes are even more complicated than is the metric of the flat spacetime of Minkowski's special relativity. As one paper so aptly put it, "Experience has taught us that the space in which we live has a geometry that is three-dimensional and Euclidean . . . We are very much at home with [that] geometry . . . But the geometric properties of a Minkowskian space are so alien to us that we may well despair of visualizing them, and a Riemannian [curved] space . . . seems totally beyond comprehension."[103]

An important feature of Riemannian geometry is that although it is generally not globally flat, it is always *locally* flat. Thus any sufficiently small region in a curved Riemannian spacetime can be approximated, with arbitrarily small error, by a flat pseudo-Euclidean Minkowskian spacetime. That is, at each point in Riemannian spacetime, there is some *particular* inertial frame of reference in which special relativity is all there is to spacetime physics *at that point*. The particular inertial frame required is different, however, from point to point.

In a coordinate system different from rectangular, the flat Minkowskian metric can appear radically altered, but that is just an artifact of the mathematics and has no physical significance. For example, in spherical coordinates the Minkowskian metric becomes the equivalent

$$(ds)^2 = (dt)^2 - (dr)^2 - (rd\theta)^2 - (rsin(\theta)d\phi)^2$$

where ϕ is the azimuthal angle and θ is the angle measured from the polar axis. A related metric occurs in the theory of spherically symmetric, static (no time variation) time machine wormholes (discussed in Chap. 6), of the form

$$(ds)^2 = \left(e^{a(r)}dt\right)^2 - \frac{(dr)^2}{1 - \frac{b(r)}{r}} - (rd\theta)^2 - (rsin(\theta)d\phi)^2$$

where $a(r)$ is called the *redshift function* and $b(r)$ is called the *shape factor*. These two functions are nearly arbitrary, subject only to the constraints that both $b(r)/r$ and $a(r)$ vanish as r goes to infinity (r is the radial distance from the throat of the wormhole mouth). Indeed, as r increases, this curved wormhole spacetime metric

---

[102] Quoted in P. Kerszberg, "The Relativity of Rotation in the Early Foundations of General Relativity," *Studies in History and Philosophy of Science*, March 1987, pp. 53-79.

[103] R. W. Brehme and W. E. Moore, "Gravitational and Two-Dimensional Curved Surfaces," *American Journal of Physics*, July 1969, pp. 683-692.



Fig. 3.14 The curvature of a space can be revealed by the process of parallel transport

reduces to that of flat Minkowskian spacetime, so this wormhole spacetime is said to be *asymptotically flat*.[104]

An intuitive appreciation of 'flatness' can be realized in terms of what is called the *parallel transport* of a vector around a closed path. In a curved space the vector will experience a rotation, which will not occur in a flat space. Two examples of parallel transport in ordinary three-dimensional space are shown in Fig. 3.14. The spherical surface on the left is curved because if you slide the vector from N to A to B and then back to N, all the while keeping it parallel to its immediately previous orientation, then when it gets back to N the vector will point to B, *not* toward A as it initially did. A similar trip on the cylindrical surface, however, results in zero rotation of the vector. Thus, the cylindrical surface, despite superficial appearances, is *not* curved.

Using the idea of the metric tensor, we can develop a more formal demonstration that the surface of a sphere, unlike like that of a cylinder, is not flat. On the surface of a sphere of radius a (*on* the surface $r = a$ everywhere, and so $dr = 0$), the measure of the distance between two points (in spherical coordinates) is[105]

$$(ds)^2 = a^2 sin^2(\theta)(d\phi)^2 + a^2(d\theta)^2.$$

Writing $x_1 = \phi$ and $x_2 = \theta$ yields the more general form

---

[104] For wormhole spacetimes that are not asymptotically flat, see (for example) K. Narahara, *et al.*, "Traversable Wormhole in the Expanding Universe," *Physics Letters B*, September 29, 1994, pp. 319-323.

[105] Note *carefully* that this is a purely spatial problem, with no time, and we are taking all of the metric coefficients as positive (unlike in the case of a spacetime metric).

$$(ds)^2 = g_{11}(dx_1)^2 + g_{12}(dx_1)(dx_2) + g_{21}(dx_2)(dx_1) + g_{22}(dx_2)^2$$

or, using the symmetry condition $g_{12} = g_{21}$, we have

$$(ds)^2 = g_{11}(dx_1)^2 + 2g_{12}(dx_1)(dx_2) + g_{22}(dx_2)^2.$$

From this we immediately have $g_{11} = a^2 sin^2(\theta)$, $g_{22} = a^2$, and $g_{12} = g_{21} = 0$.

Now, suppose we ask whether it is possible to find some new coordinate system (with variables x_1' and x_2') in which the invariant $(ds)^2$ is given by the flat Euclidean metric $\left(dx_1'\right)^2 + \left(dx_2'\right)^2$. In such a coordinate system (if it exists) we would have the 'flatness conditions' of $g_{11}' = g_{22}' = 1$ and $g_{12}' = g_{21}' = 0$. With such a change of coordinates, each of our original ϕ, θ coordinates would generally be a function of both of the new coordinates—that is, $\phi = \phi\left(x_1', x_2'\right)$ and $\theta = \theta\left(x_1', x_2'\right)$. Thus, writing the total differential of a function of two variables (see note 96 again), we have

$$d\phi = \frac{\partial \phi}{\partial x_1'} dx_1' + \frac{\partial \phi}{\partial x_2'} dx_2'$$

$$d\theta = \frac{\partial \theta}{\partial x_1'} dx_1' + \frac{\partial \theta}{\partial x_2'} dx_2'.$$

Substituting these expressions into the above expression for $(ds)^2$ on the surface of a sphere, and collecting terms, we arrive at

$$\begin{aligned}(ds)^2 &= a^2\left\{\left[\sin^2(\theta)\left(\frac{\partial\phi}{\partial x_1'}\right)^2 + \left(\frac{\partial\theta}{\partial x_1'}\right)\right]\left(dx_1'\right)^2 + \left[\sin^2(\theta)\left(\frac{\partial\phi}{\partial x_2'}\right)^2 + \left(\frac{\partial\theta}{\partial x_2'}\right)^2\right]\left(dx_2'\right)^2\right. \\ &\quad \left. +2\left[\sin^2(\theta)\frac{\partial\phi}{\partial x_1'}\frac{\partial\phi}{\partial x_2'} + \frac{\partial\theta}{\partial x_1'}\frac{\partial\theta}{\partial x_2'}\right]\left(dx_1'\right)\left(dx_2'\right)\right\} \\ &= g_{11}'\left(dx_1'\right)^2 + 2g_{12}'\left(dx_1'\right)\left(dx_2'\right) + g_{22}'\left(dx_2'\right)^2\end{aligned}$$

We can now immediately write down each of the g' and, if we demand that they satisfy the 'flatness conditions,' then we have the following three statements:

$$sin^2(\theta)\left(\frac{\partial\phi}{\partial x_1'}\right)^2 + \left(\frac{\partial\theta}{\partial x_1'}\right)^2 = \frac{1}{a^2}$$

$$sin^2(\theta)\left(\frac{\partial\phi}{\partial x_2'}\right)^2 + \left(\frac{\partial\theta}{\partial x_2'}\right)^2 = \frac{1}{a^2}$$

$$sin^2(\theta)\frac{\partial\phi}{\partial x_1'}\frac{\partial\phi}{\partial x_2'} + \frac{\partial\theta}{\partial x_1'}\frac{\partial\theta}{\partial x_2'} = 0.$$

For a *globally* flat surface, that is, a surface that is flat *everywhere*, these three statements must hold in particular at the poles of the sphere. That is, at $\theta = 0^\circ$

and at $\theta = 180^{\circ}$. At both of these points $\sin(\theta) = 0$, and so at the poles the three statements reduce to

$$\left(\frac{\partial\theta}{\partial x_1'}\right)^2 = \frac{1}{a^2}$$

$$\left(\frac{\partial\theta}{\partial x_2'}\right)^2 = \frac{1}{a^2}$$

$$\frac{\partial\theta}{\partial x_1'}\frac{\partial\theta}{\partial x_2'} = 0.$$

But the third statement is incompatible with the first two and, because of that incompatibility, there is no primed coordinate system in which the g' coefficients in the metric are those of a globally flat metric. Thus, unlike the surface of a cylinder, the surface of a sphere is not flat but rather is curved. This almost surely comes as no surprise to you, but now you can *prove* it!

3.6 Proper Time and the Twin Paradox in Time Travel to the Future

"[The] equations of duo-quadrant lineations [have] been substantiated ... Our fourth-angle deviation from the six conceivable electronic dimensions did the trick all right. I went forward in Time."[106]

The spacetime interval of the previous section has an important interpretation that leads to one of the more dazzling results of special relativity—time travel into the future. First, recall the flat spacetime metric

$$(ds)^2 = (dt)^2 - (dx)^2 - (dy)^2 - (dz)^2$$

in which the use of unprimed variables indicates that the measurements on the space and time coordinates of a moving particle are made with respect to a stationary observer's frame of reference. Now, suppose that the space and time coordinates of a moving particle are made with respect to the particle instead. Then, using primed variables for measurements made in this new frame of reference, $dx' = dy' = dz' = 0$ because the particle is always at the origin (by definition)! Recalling the invariance of the spacetime interval for all observers, we conclude that

---

[106] A science fiction scientist babbles incoherent nonsense, not special relativity, about how to travel into the future, in a story by J. H. Haggard, "He Who Masters Time," *Thrilling Wonder Stories*, February 1937.

$$(ds')^2 = (ds)^2 = (dt')^2.$$

That is, the spacetime interval between two events is the time lapse measured by a clock attached to a particle that moves from one event to the other. This time is called *proper time*, which gets its name from the idea that it belongs to (is the *property* of) the moving particle. This is the technical reason for taking (as we did in the previous section) $(ds)^2 = (dt)^2 - (dx)^2$ rather than $(ds)^2 = (dx)^2 - (dt)^2$. The first choice avoids the somewhat awkward result of an imaginary proper time.

Next, we'll adopt what has come to be called the *clock hypothesis*, which states that an accelerated clock runs at the same instantaneous rate as an unaccelerated clock that is moving alongside at the instantaneously same speed. As we showed earlier (take a look back at Sect. 3.3), if the accelerated clock's instantaneous speed is v, then its rate of time keeping (dt') is related to that of the 'stationary' (unaccelerated) clock (dt) as

$$dt' = \sqrt{1 - \left(\frac{v}{c}\right)^2}\,dt$$

where c is the speed of light. The clock hypothesis is generally assumed to be true. Einstein, himself, in his famous 1905 special relativity paper, specifically took the rate of a clock's timekeeping to be velocity-dependent only. When asked during an interview decades later whether it is permissible to use special relativity in situations involving acceleration, Einstein replied "Oh, yes, that is all right as long as gravity does not enter; in all other cases, special relativity is applicable. Although, perhaps the general theory approach might be better, it is not necessary."[107]

The clock hypothesis has long had experimental verification. For example, in one experiment the time keeping of accelerated atomic clocks was determined to be given precisely by the time dilation formula of special relativity, even when their direct mechanical acceleration (the centripetal acceleration produced by a rapidly spinning disk) exceeded 66,000 gees![108] And even more impressive are the time dilation results of a later experiment in which the time keeping of near light-speed charged particles, orbiting in a magnetic field, was in excellent agreement with the time dilation formula, even as accelerations well in excess of 10^{15} gees were reached![109]

The total elapsed time between two events A and B, as measured by the proper time of an accelerated clock making the journey, is, therefore, given by

---

[107] R. S. Shankland, "Conversations with Albert Einstein," *American Journal of Physics*, January 1963, pp. 47-57.

[108] H. J. Hay, *et al.*, "Measurement of the Red Shift in an Accelerated System Using the Mössbauer Effect in Fe^{57}," *Physical Review Letters*, February 15, 1960, pp. 165-166.

[109] J. Bailey, *et al.*, "Measurements of Relativistic Time Dilation for Positive and Negative Muons in a Circular Orbit," *Nature*, July 29, 1977, pp. 301-305.



Fig. 3.15 World lines of two clocks (one accelerated and one unaccelerated)

$$t' = \int dt' = \int_{t_A}^{t_B} \sqrt{1 - \left(\frac{v}{c}\right)^2} dt < t_B - t_A \text{ if } v \neq 0$$

where $t_B - t_A$ is the elapsed time between A and B as measured by the unaccelerated clock. The inequality results because, for $v \neq 0$, the integrand is always less than 1. Now, we know that in a spacetime diagram the world line of the unaccelerated clock is a straight line, whereas the world line of the accelerated clock is a curved line. Thus, using Fig. 3.15, combined with the inequality $t' < t_B - t_A$, we have the following central result: the world line of *maximum* proper time is the one that *looks the shortest*, that is, the straight (or free-falling geodesic) world line. In the spacetime diagram the curved line looks longer, but in fact any curved line will have a smaller proper time than does the straight world line. This is a dramatic example of how Minkowskian *spacetime* geometry differs from Euclidean *space* geometry; in the latter geometry, there is no longest path between two points.

From this, we can now understand the famous paradox of the twins, Bob and Bill. Bill remains on Earth, but Bob gets into a rocket ship and goes on a high speed trip out into space. Eventually he brings his ship to a stop, turns around, and returns to Earth. The world lines of Bob and Bill are initially together, then they diverge as Bob goes on his trip, and then they come together again at the end of Bob's trip, as shown in Fig. 3.16. The details of Bob's trip are not important for a general statement of the paradox (although in just a bit I *will* present the details for one possible trip). All we need observe for now is that Bill's world line from A to B is straight, whereas Bob's is curved. Bill's body (that is, his local clock) will therefore measure a greater proper time than will Bob's; that is, Bob will be younger than his stay-at-home twin! Equivalently, upon his return Bob will hear his Earthbound



Fig. 3.16 World lines of unaccelerated (Bill) and accelerated (Bob) twins

brother declare the date to be further in the future than Bob's trip lasted (according to Bob). Bob will therefore conclude that he has traveled into the future.[110]

This situation is called a paradox, not because of the time travel aspect (there are no logical paradoxes associated with travel into the future), but rather because it seems to violate the very spirit of special relativity. That is, from Bill's point of view, Bob at first travels away and then returns. But one can argue that from Bob's point of view it is Bill who first recedes and then returns. So why is it *Bob* who is the younger, and not Bill? Long after Einstein's 1905 publication of special relativity, this point remained a great puzzle for many. For example, in the 1923 Presidential Address to the Eastern Division of the American Philosophical Association, we read this very objection to the twin paradox. The conclusion by the speaker is that such a thing "could happen only in a universe in which all squares were round and the *principio contradiction* had been put to sleep."[111]

So, what's the answer, why is it *Bob* who is the younger of the twins? The classic physics answer is that the two points of view are actually *not* symmetrical, that there is a definite asymmetry between Bill and Bob. After all, it is Bob who feels the acceleration from the rocket's engines as he blasts off from Earth—it is Bob, not

---

[110] The twin paradox is hinted at in Einstein's 1905 paper, but it is in a 1911 address to the International Congress of Philosophy in Bologna, by the French physicist Paul Langevin (1872-1946), that a human space traveler is first introduced (in a cannonball moving at near light-speed, an idea motivated by Langevin's reading of Jules Verne's 1872 novel *From the Earth to the Moon*). The writer Pierre Boulle proudly mentioned this contribution by his fellow Frenchman in the time travel story "Time Out of Mind" (you can find it in Boulle's collection *Time Out of Mind*, Vanguard Press 1966).

[111] W. P. Montague, "The Einstein Theory and a Possible Alternative," *The Philosophical Review*, March 1924, pp. 143-170.

Bill, who feels *force*—whereas Bill feels nothing unusual as he remains on Earth. The more fundamental physics answer, however, is that Bob's world line in spacetime is curved, whereas Bill's is straight.

In an open, spatially unbounded, flat spacetime, *curved* is indeed synonymous with *accelerated*, but this need not be so in a *closed,* flat spacetime. In an open, flat spacetime, the only way two world lines can diverge in the past and then meet again in the future is for at least one of them to curve, but in a closed but still flat spacetime, it is possible for two straight world lines to meet more than once. For example, Fig. 3.17 shows a simple two-dimensional spacetime that is the surface of a cylinder (which you'll recall we argued earlier is flat), rather than an infinite flat plane. The two world lines in that figure are *both* straight: to visualize this, imagine cutting the cylinder open along the (vertical) time dimension, and then flattening it out. Bob's world line, however, looks longer in the spacetime diagram, so Bob's proper time will be less than Bill's when they meet again, even though now *neither* of them has experienced any acceleration.[112] This is simply an interesting mathematical exercise, however, and as far as is known the spacetime we live in is not cylindrical and so Bob's trip into the future will require an accelerating rocketship.[113]

If we specify the details of Bob's trip, we can then precisely calculate the difference in elapsed time for the twins. In an analysis that dates back to 1962, the German astrophysicist Sebastian von Hoerner (1919–2003) did that for the following trip[114]: To begin, Bob gets into his rocket ship at time $t = t' = 0$ (t is time measured on Earth by Bill, and t' is time measured by Bob in his rocket). The Bill and Bob synchronize their clocks at the instant of departure. Bob's trip is to be made in comfort, and so his rocket accelerates at a constant rate (a one gee acceleration, for example, would be equivalent to Earth's gravity, and Bob would feel right at home). This is of practical importance, obviously, because we do not want the experienced acceleration to be incompatible with the physical survival of Bob. Bob

---

[112] See C. H. Brans and D. R. Stewart, "Unaccelerated-Returning Twin Paradox in Flat Space-Time," *Physical Review D*, September 15, 1973, pp. 1662-1666. For a similar treatment, this time by a mathematician, see Jeffrey R. Weeks, "The Twin Paradox in a Closed Universe," *American Mathematical Monthly*, August-September 2001, pp. 585-589.

[113] In Chapter 6 we'll discuss the idea of traveling into the past by moving faster than light (*superluminal* motion). A treatment of such travel, in Bob's cylindrical spacetime, is by S. K. Blau, "Would a Topology Change Allow Ms. Bright to Travel Backward in Time?" *American Journal of Physics*, March 1998, pp. 179-185, which answers that question in its last line: "Ms. Bright cannot [return] 'the previous night' and alter history," a conclusion that no doubt met with Hawking's approval. The 'Ms. Bright' in the title is the heroine of a 1923 limerick that you can find quoted in the first *For Further Discussion* of Chapter 6.

[114] Originally appearing in the journal *Science*, under the title of "The General Limits of Space Travel," von Hoerner's analysis was reprinted in the classic anthology *Interstellar Communication* (A. G. W. Cameron, editor), W. A. Benjamin 1963. The arithmetic was, alas, just a bit sloppy (the final formulas, fortunately, are correct), and many of von Hoerner's numerical evaluations are incorrect. Later, the British mathematician Leslie Marder cleaned-up the analysis in his beautiful little book on the twin paradox, *Time and the Space-Traveler*, George Allen & Unwin, Ltd. 1971.

Fig. 3.17 Unaccelerated twin paradox in a cylindrical spacetime



travels this way for a time interval of T (as measured by Bill on Earth) and T' (as measured by Bob in his rocket). At that time the rocket is traveling at its maximum speed. Bob then turns off the rearward engine and turns on a forward-mounted engine so as to experience a constant deceleration. Floor and ceiling interchange, but Bob always weighs the same. If he does this for the same time interval T (as measured by Bill on Earth) and T' (as measured by Bob) as for the initial acceleration phase of the trip, the rocket will be brought to rest with respect to Earth. At that time, $2T$ (as measured by Bill on Earth) and $2T'$ (as measured by Bob), the rocket is at its maximum distance from Earth. Bob then returns to Earth, using the same acceleration/deceleration process, and Bob arrives back home, gently, with a final speed of zero with respect to Earth (ignoring, of course, all the navigational problems due to the motion of Earth during the trip).

Assuming the clock hypothesis is true (not all physicists believe this,[115] but remember, we have Einstein[116] on our side with this!), the result is that if a is the constant acceleration of the rocket (as experienced by Bob), and c is the speed of light, then the relationship between the *total roundtrip time* as measured by Bill ($4T$) and as measured by Bob ($4T'$), is given by

$$T = \frac{c}{a} \sinh\left(\frac{a}{c} T'\right).$$

The difference in what each twin believes to be the date can, in fact, be truly astonishing. For example, if $a = 1$ gee and Bob travels (by his clock) for $4T' = 20$ years, then $4T = 339$ years.[117] Of course, there will actually be no disagreement between Bill and Bob over the date upon Bob's return because Bill will be long dead!

Is it likely that such a time trip[118] will someday be made into the future? It's just my opinion, but I suspect not. Bob will be traveling at virtually the speed of light at maximum speed ($0.9993\,c$, to be precise, at which point he will be 84 light-years from Earth), and to zip through space at such a speed would result in a very high rate of collision with stray hydrogen atoms (about one per cubic centimeter). The result of those energetic collisions would be the intense blasting of Bob with a lethal dose of gamma radiation. And, as von Hoerner showed in his original analysis (note 114), the energy required by Bob's rocket would be simply mind-boggling.

Professor Schild (see note 116), on the other hand, seems to have been less bothered by such considerations when he wrote, at the beginning of a prose discussion of the twin paradox, "I have no doubt that if our technology should ever advance to the stage where large-scale twin effects become noticeable with our unaided senses, then [people] will have no difficulty in adjusting their concepts of time until the new phenomena see quite natural."[119]

I'll end this chapter on time with the observation that it is the distinction between the proper time of Bob on a rocket ship, and the time of those who are not fellow space travelers, that eliminates the occasional suggestion of simply *freezing* one's way via suspended animation to the future (as in the 1992 film *Forever Young*). That is, suppose you manage to talk a friend into climbing into a freezer (please don't actually try this!); at the moment he gets in, his wrist watch agrees with yours (both are powered and maintained at a constant temperature by 100-year nuclear batteries). Years later, when you thaw your friend out, you'll find that your watches still agree. But when Bob returns from his rocket trip, his watch will not agree with yours, but instead will be far behind. Bob is a true time traveler, but your frozen/thawed friend is not.[120]

---

[115] Consider, for example, this remark by 1965 Nobel physics laureate Julian Schwinger (1918-1994) about the twin paradox in his 1986 book *Einstein's Legacy*: "The observer on the spaceship … is *not* in uniform, unaccelerated motion … The special theory of relativity does not apply to such an accelerated observer." Schwinger was wrong in this conclusion (see the next note).

[116] As a physicist wrote on this point after Einstein's death, "A good many physicists believe that [the twin] paradox can only be resolved by the general theory of relativity. … However, they are quite wrong. The twin effect … is one of special relativity." See A. Schild, "The Clock Paradox in Relativity Theory," *American Mathematical Monthly*, January 1959, pp. 1-18. Alfred Schild (1921-1977) was professor of physics at the University of Texas, and a recognized expert in the general theory.

[117] In using the T, T' formula, one has to be careful to use MKS units, that is, length and time measured in meters and seconds, respectively. Thus, $a = 1$ gee = 9.81 meters/second^2 and $c = 186{,}210$ miles/second $= 2.997 \times 10^8$ meters/second.

[118] For a science fiction use of such a trip, see Robert Heinlein's 1956 novel *Time for the Stars*.

[119] A. Schild, "Time," *Texas Quarterly*, Autumn 1960, pp. 42-62.

A provocative illustration of the distinction between the proper time of a time traveler and of those who are not time travelers was given by a philosopher.[121] He begins his analysis by asking what appears to be a question with an obvious answer. Suppose, he says, it is [2018] and you suddenly wake up in a hospital and are told that you have been in a coma for the past 2 weeks. You are also told that you were in an auto accident 2 weeks ago, that you suffered temporary neural damage, and that the eventual reversal of such damage always, at some time within 4 weeks after the damage occurs, causes a day of excruciating pain *if you are conscious at the time*. Would you prefer for the day of damage reversal to be in the past 2 weeks (when you were in the coma) or in the next 2 weeks? The answer seems clear. After all, if the day that damage reversal occurs has already happened, then you simply slept through it and missed the pain. To prefer the day of pain to be in the future (when you will be awake) seems absurd. Now, let's add time travel to the equation.

All is as before, but now you immediately leave the hospital upon regaining consciousness to take a trip back to 1892, where you will stay for 2 weeks. Again, it seems clear that you would prefer to have had the day of pain in the past 2 weeks (in 2018), not in the next 2 weeks (in 1892). Note that the *next* is a reference to your proper time, because whereas 1892 is the global past, it is *your* personal future. Thus, now your preference would be to have the day of pain in the *recent personal past* of 2018, not the *distant global* past of 1892. Now, let's put another time travel twist to this story.

All is as before in the original tale, except now you are told in the hospital that the auto accident happened just after you made a time trip to 2092: as you walked out of your time machine in 2092, you were hit by a car. The 2 weeks you were in a coma were in 2092, before you were judged fit enough (although still unconscious) to make the time journey back to 2018. When would you now prefer to have the day of pain? Clearly, as always, in your *personal past*, which is now the *global future*.

Time *is* different for those who time travel and those who don't!

---

[120] In his 1956 novel *The Door Into Summer*, the always ingenious Robert Heinlein used *both* ideas, with the cold-storage method of reaching the future combined with a true time machine to allow his hero to return to his 'present' (the future's past).

[121] A. Gallois, "Asymmetry in Attitudes About the Nature of Time," *Philosophical Studies*, October 1994, pp. 51-59.

3.7 For Further Discussion

An interesting *theological* analysis of Feynman's idea of an electron traveling backward in time, expressed as thinking of the electron as being in 'one of God's films played in reverse,' is given by J. W. Smith, "Time Travel and Backward Causation," *Cogito* 1985, pp. 57–67. Wondering what it would be like for an electron to travel backwards in time, Smith's answer was: "Consider an electron e_1. At time t_0 it is at (x_0, y_0, z_0). At time t_1 it is at (x_1, y_1, z_1). If the direction of time for the electron was reversed, then the electron would be observed on the 'film of the world' to travel back along the same path as it did before, i.e., back to (x_0, y_0, z_0). If God stopped the 'film of the world' and examined the charge of e_1, then He would find that it was *negative*, not *positive*. Hence the electron traveling backwards in time is simply that: an electron traveling backwards in time, it is not a positron. Time reversal does not result in a reversal of charge. Thus, the Stückelberg-Feynman position is incorrect . . . ." Discuss this in terms of the TCP theorem. Is there a conflict? When God stops the 'film of the world,' does the electron even *have* an arrow of time?

All the modern, major religions of the world are in agreement on these two points: (1) God created the universe and (2) At some time in the past, the universe came into existence. This does raise the question of what was God doing *before* He created the universe (see note 7 in the Introduction). In his *Confessions*, Saint Augustine comments on the conundrum that (1) and (2) are possibly in conflict. After all, if God *created* the universe then, given any time t in the finite past, He must have been doing something *before* time t, which means that for any time t in the finite past the universe already existed. Thus, the universe had no instant of creation in the finite past and so had no first moment of existence—which implies (2) is false. However, like any good philosopher of religion, Augustine not only provided this theological puzzle, but also a way to wiggle free of it. His suggested counter is the assertion that time is *itself* a creation of God, that is, He made time as *part* of creating the universe. Thus, there was no time *before* He created the universe, and so the very question of 'what was He doing before He made the universe' has no meaning. What do you think of Augustine's two arguments?

The Australian philosopher J. J. C. Smart (1920–2012) invoked five dimensional spacetime in a way very different from that of including an 'eternity' axis for God's temporal time (see note 33 in "Some First Words"). What Smart argued for, instead, was *multiple* four-dimensional worlds existing together without conflict, just as an infinity of two-dimensional worlds can exist without conflict in a three dimensional space. As he wrote, "The reason why there could be two totally disparate space-times is simply the quite obvious one that two totally disparate four-dimensional spaces can exist within a suitable five-dimensional space. There is no difficulty in mathematical inconceivability here. Now let one of these four-spaces be our own spacetime world, and let the other four-space be more or less similar, in accordance with whatever story you wish to tell about it." This idea had, in fact, been around long before Smart's 1967 paper. In his 1898 Presidential Address to the American Mathematical Society, for example, Simon Newcomb declared "Add a fourth dimension of space, and there is room for an indefinite number of Universes, all alongside of each other, as there is for an indefinite number of sheets of paper when we pile them upon each other." Newcomb's idea appealed to H. G. Wells' fancy so much that he built two novels, *The Wonderful Visit* and *Men Like Gods*, around it. In the first novel there is explicit mention of multiple worlds "lying somewhere close together, unsuspecting, as near as page to page in a book," and the second one speaks of one parallel universe being rotated into another. John Cramer (a University of Washington physicist) repeated Newcomb's and Wells' parallel universes/pages-of-a-book/rotation imagery almost word for word in his 1991 novel *Twistor*.

Read these three novels, and then discuss. In particular, is Wells consistent in his presentations (as a novelist there is, of course, no reason he should be!)?

Imagine the following two events, **A** and **B**, in Minkowski spacetime: **A** is the emission of a photon, and **B** is the absorption of that photon. What is the spacetime interval between **A** and **B**? It might seem that we need to know more about the precise spatial and temporal coordinates of **A** and **B**, but in fact the interval is *always zero* for any two events connected by light (by photons). To see this, write the flat Minkowski metric as

$$\left(\frac{ds}{dt}\right)^2 = 1 - \left(\frac{dx}{dt}\right)^2$$

(continued)

and so, since $(dx/dt)^2 = 1$ (because photons—by definition!—travel at the speed of light) we have $(ds)^2 = 0$. The world line of any photon has what is called a *null* interval, as do all world lines on the surface of a light cone. Timelike world lines (in the interior of light cones, with $(dx/dt)^2 < 1$) have positive intervals, that is, $(ds)^2 > 0$. Spacelike world lines (in the exterior of light cones, in Elsewhere, with $(dx/dt)^2 > 1$) have negative intervals, that is, $(ds)^2 < 0$. This is one of the significant differences between *distances* in space (which are never negative) and *intervals* in spacetime. The American chemist G. N. Lewis (1875–1946)—see note 60 in Chap. 2—constructed a romantic illustration of this when he wrote "Any pair of points [in spacetime] which are separated by zero distance [interval] are in *virtual contact*. In other words, I may say that my eye touches a star, not in the same sense as when I say that my hand touches a pen, but in an equally physical sense." (See Lewis' paper "Light Waves and Light Corpuscles," *Nature*, February 13, 1926, pp. 236–238; Lewis was the originator of the term *photon* for a particle of light.) To understand what Lewis was getting at, you must understand that in spacetime we can have the interval between **A** and **B** as zero, and the interval between **B** and **C** as zero, but the interval between **A** and **C** may *not* be zero. To convince yourself of this, suppose the Minkowski spacetime coordinates (x, t) of **A**, **B**, and **C** are (1,3), (2,2) and (1,1), respectively. Show that $(ds_{\boldsymbol{AC}})^2 = 4$, while $(ds_{\boldsymbol{AB}})^2 = (ds_{\boldsymbol{BC}})^2 = 0$. (Hint: draw a diagram of this spacetime and simply plug the coordinates of **A**, **B**, and **C** into the metric.)

The use of the time dilation effect of high-speed space travel was used by science fiction writer Donald Wandrei (1908–1987) in his tale "A Race Through Time," *Astounding Stories*, October 1933. Initially set in 1950, this is the story of two scientists, one evil (of course!) and the other good (of course!), who develop quite different methods for travel into future times. The evil one does it with a drug that slows the metabolic processes of the body, while the good one builds an atomic-powered rocket in his home workshop! The evil scientist kidnaps the good one's girlfriend, seals the two of them inside a crystal dome, and then injects her and himself with his drug. He has arranged matters so that they will emerge from the dome in the year one million A.D. Learning what has happened, the good scientist rushes to the dome finds he can't break in, but sees an indicator dial pointing at 1,000,000. (The evil scientist has conveniently provided the dial, as well as having made the dome transparent, much as modern-day movie criminals always include a count-down clock with glowing red digits on their bombs so the hero always knows just how much time is left to disarm the bomb.)

(continued)

Returning to his rocket, the good scientist decides that he, too, will travel into the far future using time dilation. So, off he goes, on a trip like Bob's in Sect. 3.6. The story ends with an ironic twist—the good scientist thought the '1,000,000' he saw through the dome meant *one million years in the future beyond 1950*, and so he arrives back on Earth nearly 2000 years *after* his girlfriend and the evil scientist emerged from the dome. (They are, of course, long dead when the good scientist returns.)
On the outward leg of the good scientist's rocket flight we read of his "frightful speed — now thousands of light years per Earth second." Discuss this in terms of relativity theory. That is, does the rocket actually travel thousands of light years in one second of elapsed time back on Earth?

The American physicist Robert Forward (1932–2002) was, in addition to being an expert in general relativity, also a quite inventive science fiction writer. In his short story "Twin Paradox" (*Analog Science Fiction*, August 1983), for example, he used *biology* to give a surprising, ironic twist to the classic physics puzzle. The story flips the asymmetric aging of the twins by imagining that, just after the traveling twin's departure, the secret of immortality is discovered. The treatment has to be administered no later than at a certain age, however, and upon his return to Earth the traveling twin is just a bit too old for it to work. He thus becomes the last person to die of old age! In this tale, the details of the traveling twin's trip are somewhat different from Bob's trip. Read "Twin Paradox" (you can also find the story in Forward's 1995 book *Indistinguishable from Magic*), and summarize how the traveling twin's trip is accomplished.

In the mystical 1920 novel *A Voyage to Arcturus*, by the Scottish writer David Lindsay (1876–1945), we read of a spaceship that travels to Arcturus (the brightest star in the constellation Boötes, 36 light years from Earth) in just 19 h of proper time. The technical details of the trip are not explained in the novel, so assume they are the same as in Bob's trip. That is, $2T' = 68{,}400$ s as measured by a clock on the spaceship. The distance traveled in this time is

$$2\frac{c\left\{\sqrt{a^2T^2+c^2}-c\right\}}{a}$$

(continued)

where c is the speed of light, a is the constant acceleration/deceleration of the rocket (as measured on the spaceship), and T is how long an *Earth*-based clock says the trip takes. Use this formula, and the one relating T and $T^{'}$ in the text, to calculate

1. The value of the constant acceleration/deceleration, a (does the result seem reasonable to you?) and
2. The value of T (the length of time that passes on Earth as 19 h pass on the spaceship).

You don't have to discuss general relativity to encounter tensors of the second rank (as is the metric tensor). Electrical engineers run into such a thing, for example, when studying the lowly Ohm's law! In a copper wire, that law says the current density (the vector **J**, in units of amperes per square meter) at any point is related to the electric field (the vector **E**, in units of volts per meter) at that point by the *scalar* σ as follows: $\mathbf{J} = \sigma\mathbf{E}$, where σ (called the *conductivity*) is a single number. This says, in rectangular coordinates, that the x-component of **J** depends *only* on the x-component of **E**, and similarly for the y-component and z-components of **J** and **E**. More generally, however, each component of **J** depends on *all* of the components of **E** (as in certain crystalline structures), and so we have the equations

$$\begin{aligned} J_x &= \sigma_{11}E_x + \sigma_{12}E_y + \sigma_{13}E_z \\ J_y &= \sigma_{21}E_x + \sigma_{22}E_y + \sigma_{23}E_z \\ J_z &= \sigma_{31}E_x + \sigma_{32}E_y + \sigma_{33}E_z \end{aligned}$$

or, in matrix form

$$\mathbf{J} = \begin{bmatrix} J_x \\ J_y \\ J_z \end{bmatrix} = \begin{bmatrix} \sigma_{11} & \sigma_{12} & \sigma_{13} \\ \sigma_{21} & \sigma_{22} & \sigma_{23} \\ \sigma_{31} & \sigma_{32} & \sigma_{33} \end{bmatrix} \begin{bmatrix} E_x \\ E_y \\ E_z \end{bmatrix} = \boldsymbol{\sigma}E.$$

So **J** is now related to **E** by $\boldsymbol{\sigma}$, a 3 × 3 *matrix* (9 numbers, instead of just 1). The matrix $\boldsymbol{\sigma}$ is, in fact, a tensor of rank 2. This tensor is in the three-dimensional space of the copper wire, while the 4 × 4 metric tensor matrix is in a four-dimensional spacetime, but both are tensors of rank 2. The number of numbers in a tensor of rank n, in a space of dimension d, is d^n. In general relativity, tensors of higher rank than 2 are required. For example, the

(continued)

curvature tensor has rank 4, and so in a four-dimensional spacetime it is described by $4^4 = 256$ numbers. This goes a long way in explaining why, in general relativity, computing often involves a *lot* of arithmetic! The primary characteristic of tensors of any rank is that they are invariant under a change in coordinate systems (choosing a coordinate system is an arbitrary matter, made mostly for human convenience, about which Nature is indifferent). Read more about tensors, and write an essay on how they behave under a change in coordinates. A good place to start, at the level of this book, is Lillian Lieber's *The Einstein Theory of Relativity: a trip to the fourth dimension*, Paul Dry Books 2008 (an updated version of the original 1945 book).

Chapter 4
Philosophers, Physicists, and the Time Travel Paradoxes

> *"He felt the intellectual desperation of any honest philosopher. He knew that he had about as much chance of understanding such problems as a collie has of understanding how dog food gets into cans."*[1]

4.1 Paradoxes and Their First Appearance in Science Fiction

> "There's a lot we don't know about time travel. How do you expect logic to hold when paradoxes hold, too?" "Does that mean you don't know?" "Yes."[2]

More than 30 years ago Quentin Smith, a philosopher who believes in a finite length to the past, wrote a refutation to those who believe in an infinite past and, while that paper[3] has nothing to do with the paradoxes of time travel, in the course of presenting his reasoning he included the following curious passage:

> "Why does the sun arise in the morning and not at some other time? Why do the hands of a properly functioning clock point to 12:00 at noon and midnight and not at other times? Why does the death of a person occur at a later time than his birth? The answer in all these cases is: Because by the very nature of these events they could not occur at other times. It belongs to the very nature of the sun's rising that it occur in the morning and not in the afternoon or evening. It belongs to the very nature of a properly functioning clock to point to 12:00 at noon and midnight and not at other times. And it belongs to the very nature of death to occur at a time later than a person's birth."

But what of a time traveler born in 1980 who, in 2018, enters her time machine, pushes a few buttons, and then boldly steps out into the Cretaceous period seventy million years earlier—and is promptly eaten for lunch by a passing *Tyrannosaurus*

---

[1] A time traveler admits (to himself) how perplexed he is by paradoxes in Robert Heinlein's classic tale "By His Bootstraps," *Astounding Science Fiction*, October 1941.

[2] Excerpt from a conversation between two paradox-puzzled time travelers in Larry Niven's story "Bird in the Hand," *The Magazine of Fantasy & Science Fiction*, October 1970.

[3] Q. Smith, "Kant and the Beginning of the World," *New Scholasticism*, Summer 1985, pp. 339–346.

© Springer International Publishing AG 2017

P.J. Nahin, *Time Machine Tales*, Science and Fiction,
DOI 10.1007/978-3-319-48864-6_4

rex? Perhaps Smith himself would say that there is no contradiction between this and his third claim because, in the time traveler's *proper* time, her spectacular death does indeed come after her birth. For many, however, for a time traveler to die before her mother is born *is* a paradox, plain and simple, say what you will about proper time.

One science fiction view of time travel paradoxes is that nature would be so disrupted by them that, should one occur, the universe would be torn apart. In one story, for example, a paradox is on the verge of happening through the use of a Tipler-cylinder time machine (mentioned back in Chap. 1, and which we'll discuss in more detail in the next chapter). In response to this 'threat to common sense,' the universe 'decides' to avoid the paradox by simply eliminating the perpetrators via a local nova![4] Niven wasn't the first to use this idea. A famous story[5] by L. Sprague de Camp (1907–2000), written two decades before, had already put forth the suggestion that nature will take all required corrective action to avoid paradoxes.

In De Camp's tale we read of two big-game hunter guides who use "Professor Prochuska's time machine at Washington University"—built with the aid of a "cool thirty million" dollar grant from the Rockefeller Foundation—to operate a safari-for-hire business that transports hunters back to the late Mesozoic era. When a disgruntled client tries to go back to the day *before* a previous trip to shoot the guides (who had displeased him, or rather *would* displease him the next day), we learn just how nasty De Camp thought Mother Nature would be to avoid a paradox. (After all, the guides had *not been* shot during the safari, so they *could not be* shot.[6]): "The instant James started [to ambush the guides] the space-time forces snapped him forward to the present to prevent a paradox. And the violence of the passage practically tore him to bits [making his body look] as though it had been pulverized and every blood vessel burst, so it was hardly more than a slimy mass of pink protoplasm."

And even earlier we have a famous tale[7] that was discussed in Chap. 1, by Fredric Brown (1906–1972), a master of the special category of science fiction called the "short-short," in which everything happens in 500 words or less. As you might expect, the oddities of time travel were natural attractions for Brown's quirky talent. You'll recall that in this story the inventor of the first time machine demonstrates it to two colleagues by sending a brass cube 5 min into the future. After being placed in the machine, the cube vanishes and then 5 min later reappears. No paradoxes with that—it is a trip into the *past* that has the potential for deadly repercussions. We learn just how deadly when the inventor next declares that at three o'clock he will again place the cube in the time machine but, until then, he will hold the cube in his hand. Thus, he says, at 5 min before three the cube will vanish from his hand and immediately appear in the time machine because 5 min after that, at three o'clock, he will send it 5 min into the past. And indeed, at 5 min before three the cube does simultaneously vanish from his hand and appear in the time machine. Then, slightly before three, as the three men stand pondering what has happened, one of the observers asks what will happen if the inventor does *not* send the cube back at three o'clock? "Wouldn't there be a paradox of some sort involved?" he wonders.[8] His curiosity aroused, the inventor can't resist the experiment—and the universe promptly vanishes.

---

[4] L. Niven, "Rotating Cylinders and the Possibility of Global Causality Violation," *Analog Science Fiction*, August 1977. Niven took this title from a physics paper with that title, authored by Tipler, that had appeared three years earlier in *Physical Review D* (April 15, 1974, pp. 2203–2206).

[5] L. Sprague de Camp, "A Gun for Dinosaur," *Galaxy Science Fiction*, March 1956.

[6] This is a statement of the belief that the past cannot be changed, an idea we will examine later in this chapter.

[7] Look back at note 93 in Chap. 1.

Time travel, of course, is full of potential paradoxes. A paradox, according to the usual dictionary definition, is something that appears to contain contradictory or incompatible parts, thus reducing the whole to seeming nonsense. And yet, truth is also evident in the whole. The history of science and mathematics has left a long trail of paradoxes, and those that involve time travel are merely among the most recent. Not all of the puzzles of time travel involve physics or logic, however. As one philosopher observed, "Doubtless time travel will raise a host of legal difficulties, e.g., should a time traveler who punches his younger self (or vice versa) be charged with assault? Should the time traveler who murders someone and then flees into the past for sanctuary be tried in the past for his crime committed in the future? If he marries in the past can he be tried for bigamy even though his other wife will not be born for almost 5000 years? Etc., etc. I Ieave such questions for lawyers and writers of ethics textbooks to solve."[9]

One way early science fiction writers had of responding to the puzzle of time travel paradoxes was to just give up and to concede that the logical puzzles are overwhelming. In one tale, for example, the inventor of the Chronoscope (a gadget that can only *view* the past) explains, "There is no time travel machine. Such a thing is a logical impossibility, treated seriously only by half-cracked writers of fantasy. Such a machine would lead at once into a hopeless paradox."[10] Equally concerned about time travel paradoxes was the pulp science fiction time traveler who told his partner, just before their first trip in time, that "I'm not sure any more about getting back. There're some unpredictable terms in the time-travel equation—paradoxes. Maybe we *won't* get back."[11]

---

[8] This is what is called a *bilking paradox*, and such paradoxes will be discussed later in this chapter. Brown gave this story a lot of thought. At one point in the tale one of the colleagues, puzzled by how the inventor will be able to place the cube into the time machine at three if it has already vanished from his hand and appeared in the machine, asks "How can you place it there, then?" Replies the inventor, "It will, as my hand approaches, vanish from the [machine] and appear in my hand to be placed there."

[9] L. Dwyer, "Time Travel and Some Alleged Logical Asymmetries Between Past and Future," *Canadian Journal of Philosophy*, March 1978, pp. 15–38.

[10] M. Jameson, "Dead End," *Thrilling Wonder Stories*, March 1941.

[11] E. Binder, "The Time Cheaters," *Thrilling Wonder Stories*, March 1940.



Fig. 4.1 One way pulp science fiction avoided paradoxes was to use a 'time viewer' (like the chronoscope in "Dead End") as in "The Time Eliminator" (*Amazing Stories*, December 1926). This illustration from the story (authored by somebody who used only the initials K.A.W.) by Frank R. Paul (©1926 by Experimenter Publishing Co.) shows the inventor demonstrating his gadget to his future wife and father-in-law. Able to look back in time, the screen is displaying scenes from the older man's courtship of his wife, decades in the past. Reprinted by permission of the Ackerman Science Fiction Agency, 2495 Glendower Ave., Hollywood, CA 90027 for the Estate

But are there *really* paradoxes? Or is it true, as the extraordinary boy-prodigy who invented a time machine exclaimed (when his teacher asserted that some questions could never be answered because "Nature is full of paradoxes"), "Ah, Professor, what nonsense! Nature is harmonious; it is we who bring the paradoxes into it."[12] Saying the same are two physicists, in a paper on the circular orbits of photons around black holes: "There are no paradoxes in physics, but only in our attempts to understand physical ideas by using inadequate reasoning or false intuition."[13] And as the time traveler in an early pulp story[14] casually declares to a friend, after an astonishing adventure in the year A.D. 1,001,930, "Paradoxical? My dear fellow, the Einstein Theory is full of apparent paradoxes, yet to him who understands it there is no inconsistency whatever. Give me another cigarette, will you, Frank?"

---

[12] V. Grigoriev, "Vanya," in *Last Door to Aiya* (M. Ginsburg, editor), S. G. Phillips 1968.

It is in *Amazing Stories* that we find the first non-fictional speculations about time travel in a pulp magazine—and certainly long before any *physics* journal would touch the subject! Publisher and editor Hugo Gernsback started those speculations by reprinting Wells' *Time Machine*, which in turn sparked a fair number of readers' letters that were printed in the magazine's "Discussions" section. Typical of the less interesting is the following comment from a letter in the July 1927 issue: "In the 'Time Machine' I found something amiss. How could one travel to the future in a machine when the beings of the future have not yet materialized?" (We answered that question in the previous chapter with the twin paradox.) Far more interesting was this letter, in the same issue:

> "How about this 'Time Machine'? Let's suppose our inventor starts a 'Time Voyage' backward to about A.D. 1900, at which time he was a schoolboy ... His watch ticks forward although the clock on the laboratory wall goes backward. Now we are in June 1900, and he stops the machine, gets out and attends the graduating exercises of the class of 1900 of which he was a member. Will there be another 'he' on the stage? Of course, because he *did* graduate in 1900 ... Should he go up and shake hands with this 'alter ego'? Will there be two physically distinct but characteristically identical persons? Alas! No! He can't go up and shake hands with himself because ... this voyage back through time only duplicates actual past conditions and in 1900 this strange 'other he' did *not* appear suddenly in quaint ultra-new fashions and congratulate the graduate. How could they both be wearing the same watch they got from Aunt Lucy on their seventh birthday, the same watch in two different places at the same time. Boy! Page Einstein! No, he cannot be there because he wasn't there in 1900 (except in the person of the graduate) ... The journey backward must cease on the year of his birth. If he could pass that year it would certainly be an effect before a cause ... Suppose for instance in the graduating exercise above, the inventor should decide to shoot his former self ... He couldn't do it because if he did the inventor would have been cut off before he began to invent and he would never have gotten around to make the voyage, thus rendering it impossible for him to be there taking a shot at himself, so that as a matter of fact he *would* be there and *could* take a shot—help, help, I'm on a vicious circle merry-go-round ... Now as to trips into the future, I could probably think up some humorous adventures wherein [the inventor] digs up his own skeleton and finds by the process of actual examination that he must expect to have his leg amputated because the skeleton presents positive proof that this was done."[15]

---

[13] M. A. Abramowicz and J. P. Lasota, "On Traveling Round Without Feeling It and Uncurving Curves," *American Journal of Physics*, October 1986, pp. 936–939.

[14] F. J. Bridge, "Via the Time Accelerator," *Amazing Stories*, January 1931.

[15] This story idea (the letter was signed only with the initials T.J.D.) may well have been the inspiration for R. Rocklynne, "Time Wants a Skeleton," *Astounding Science Fiction*, June 1941. Not all fans agreed with T.J.D. A few years later, for example, a teenager named P. Schuyler Miller (1912–1974), who would author several time travel classics himself, wrote a letter to the editor of *Astounding Stories* (June 1931) stating "there is nothing in physics ... to prevent yourself from

All of the ingenious puzzles in this letter intrigued Gernsback, and may have, in fact, been the cause of his featuring a new, original time machine story[16] in the same issue. It was the tale of a scientist who transports an entire ship at sea 14,000 years back in time and causes it to hover over lost Atlantis! That story provoked a sharp letter from a reader who claimed its logic had a fatal flaw: the story's author indicated that the Atlantians observed the time travelers when, 'of course' (asserted the reader), the time travelers must actually have been invisible. The reader explained his reasoning as follows, beginning by defining A as one of the Atlantians.

> "Now A lived his life, thousands of years ago, and died. All right, now let us pass on in time 14,000 years. Now, back we come in time when A is again living his life. Lo and behold, this time A sees before he dies a strange phenomenon in the sky! He sees the shipload of people observing him. And yet these people are necessarily observing him during his one and only lifetime, wherein he certainly did not, could not, have observed them."

Gernsback printed this letter in his September 1927 editorial "The Mystery of Time," and concluded by saying "I do . . . agree . . . that the inhabitants of Atlantis would probably not have seen the . . . travelers in time." Other readers felt this way, too, because after Gernsback published yet another time machine tale[17] in 1927, the same invisibility argument appeared again in the magazine's "Discussions" column.

Two years later an amateurishly written tale[18] appeared in which a man travels in time from 1928 to 2930 with the aid of an "astounding machine based on advanced electro-physics and the non-Euclidean theory of hyperspace." The purpose of that story was two-fold: to present several of the classic paradoxes of time travel, and then to make the claim that although the simple minds of twentieth-century people cannot understand the explanations of the paradoxes (possibly explaining why the author offers none!), the paradoxes are all trivial to the scientists of the thirtieth century. Despite this shortcoming (as well as some pretty awful dialog) the story nonetheless still managed to entertain readers with the sheer mystery of the paradoxes. Letters poured into the magazine from young fans, all demanding more time travel fiction.

So, that same year Gernsback responded with a story[19] that plays with the question of the role of time travelers in the past. (That question was clearly 'in

---

going into the past . . . and shaking hands with yourself or killing yourself." That did, however, provoke the following harsh reply from another, more skeptical reader (in the December 1933 issue): "P. S. Miller once wrote that time traveling is not incompatible with any laws of physics . . . 'he don't know from nothing.'"

[16] C. B. White, "The Lost Continent," *Amazing Stories*, July 1927.

[17] F. Flagg, "The Machine Man of Ardathia," *Amazing Stories*, November 1927.

[18] C. Cloukey, "Paradox," *Amazing Stories Quarterly*, Summer 1929.

[19] H. F. Kirkham, "The Time Oscillator," *Science Wonder Stories*, December 1929.

the air,' as Gernsback's old magazine *Amazing*[20] simultaneously published a story[21] addressing this same puzzle of time travel.) Could time travelers actually participate in events ("mix into the affairs of the period," in Gernsback's words), or would they just be unseen observers? This question, obviously inspired by the earlier discussion in *Amazing Stories*, intrigued Gernsback as much as it did his readers and so, along with Kirkham's story, he printed a challenge titled "The Question of Time-Traveling" (see note 18 in the Introduction):

> "In presenting this story to our readers, we do so with an idea of bringing on a discussion as to time traveling in general. The question in brief is as follows: Can a time traveler, going back in time—whether ten years or ten million years—partake in the life of that time and mingle in with its people; or must he remain suspended in his own time-dimension, a spectator who merely looks on but is powerless to do more? Interesting problems would seem to arise, of which only one need be mentioned: Suppose I can travel back into time, let me say 200 years; and I visit the homestead of my great great great grandfather, and am able to take part in the life of his time. I am thus enabled to shoot him, while he is still a young man and as yet unmarried. From this it will be noted that I could have prevented my own birth; because the line of propagation would have ceased right there. Consequently, it would seem that the idea of time traveling into a past where the time traveler can freely participate in activities of a former age, becomes an absurdity. The editor wishes to receive letters from our readers on this point: the best of which will be published in a special section."

Gernsback's challenge did not go unnoticed and, over the next year or so, he published a large number of reader responses in the magazine's letters column.

Indeed, a few months after issuing the challenge, in his introduction to another time travel tale,[22] Gernsback wrote that ever since the publication of Kirkham's tale "there has been a great controversy among our readers as to the possibility of time flying and the conditions under which it may be done." Most of those letters are interesting if not particularly profound, with one exception. That was a letter written by a 14 year old boy in San Francisco, and its appearance in the February 1931 issue of *Science Wonder* may well have served as the inspiration for several of the classic time travel tales published during the next 20 years:

> "Some time ago you asked us (the readers) what our opinions on time traveling were. Although a bit late, I am now going to voice four opinions . . .
>
> (1) Now, in the first place if time traveling were a possibility there would be no need for some scientist getting a headache trying to invent an instrument or 'Time-Machine' to 'go back and kill grandpa' (in answer to the age-old argument of preventing your birth by killing your grandparents I would say: 'who the heck would want to kill his grandpa or gandma!'[23]) I figure it out thusly: A man takes a time machine, and travels into the

---

[20] By this time Gernsback had lost control of *Amazing*, and *Science Wonder* was his come-back as a publisher of pulp 'scientifiction.'

[21] E. L. Rementer, "The Time Deflector," *Amazing Stories*, December 1929. Gernsback may well have been the editor, before he lost *Amazing*, who bought this story, and the magazine's new management simply used what remained in inventory.

[22] F. Flagg, "An Adventure in Time," *Science Wonder Stories*, April 1930.

[23] Look back at note 26 in "Some First Words."

> future from where he sends it (under automatic control) to the past so that he may find it and travel into the future and send it back to himself again. Hence the time machine was never invented, but!—from whence did the machine *come*?
>
> (2) Another impossibility that might result could be: A man travels a few years into the future and sees himself killed in some unpleasant manner,—so—after returning to his correct time he commits suicide in order to avert death in the more terrible way which he was destined to. Therefore how could he have seen himself killed in an entirely different manner than really was the case?
>
> (3) Another thing that might corrupt the laws of nature would be to: Travel into the future; find out how some ingenious invention of the time worked; return to your right time; build a machine, or whatever it may be, similar to the one you had recently learned the workings of; and use it until the time you saw it arrives, and then if your past self saw it as you did, he would take it and claim it to be an invention of his (your) own, as you did. Then—who really *did* invent the consarn thing?
>
> (4) Here's the last knock on time traveling: What if a man were to travel back a few years and marry his mother, thereby resulting in his being his own 'father'?"
>
> Jim H. Nicholson

Gernsback's reply, immediately following this letter, was favorable, opening with "Young Mr. Nicholson does present some of the more humorous [?] aspects of time traveling. Logically we are compelled to admit that he is right—that if people could go back into the past or into the future and partake of the life in those periods, they could disrupt the normal course of events."[24] Nicholson's letter *is* ingenious, and it anticipated the central ideas of a number of science fiction tales yet to be written.[25] However, as you'll see as you read the rest of this chapter, contrary to Gernsback's view Nicholson's comments are *not* logically correct.[26]

---

[24] Despite these words, Gernsback apparently hadn't given up entirely on the 'invisibility of time travelers' view, as he had only a few months earlier published another such tale: R. A. Palmer, "The Time Ray of Jandra," *Wonder Stories*, June 1930. In this story (one either silly or hilarious, take your pick) a time traveler moves into the future by means of a 'time ray.' Unfortunately, the ray works differently on the various chemical elements, and not at all on either hydrogen or oxygen. Thus the time traveler—or at least *much* of him—and his machine do vanish into the future, but left behind are "several gallons of water spilled on the floor." (The human body is about 60 % H_2O.)

[25] For example, Nicholson's item (2) is a precise plot outline for L. Raphael, "The Man Who Saw Through Time," *Fantastic Adventures*, September 1941, and a version of item (4) is in Robert Heinlein's famous "All You Zombies—,“ *Magazine of Fantasy & Science Fiction*, March 1959.

[26] One cannot, however, fault the imaginative powers of James Nicholson (1916–1972). He eventually became President of American International Films, the company that made such science fiction 'classics' as *Attack of the Crab Monsters* (1957), the 1963 *X (The Man with the X-Ray Eyes)*, and *The Time Travelers* (1964).

4.2 Changing the Past and the Grandfather Paradox

> "I'm not kidding you at all Phil," Barney insisted. "I have produced a workable Time Machine, and I am going to use it to go back and kill my grandfather."[27]

As mentioned in "Some First Words," physicists and philosophers often have quite different approaches to time travel (see note 26 there again). A vivid illustration of that difference is found in a philosophical paper[28] that, after acknowledging the apparent restrictions of the grandfather paradox, turns its attention to a matter that almost surely is beyond the power of physics to study—namely, the nature of the *conversation* between a time traveler and his/her younger self. A physicist, on the other hand, views the restrictions as *the whole point*, because the central question that hovers over *any* discussion of time travel is that of 'changing the past.' As one science fiction fan summed it up in a letter to the editor of *Astounding Stories* (August 1931): "It is said that the past cannot be changed, and that any effort to do so would be useless. In my belief, no matter where or when a man goes in the past, if he appears in a year or day that has already gone by, *he is changing the past*. Then there should be no room for doubt: time traveling is impossible. It will never be done." And certainly killing your grandfather in the past (when he is still a baby) would qualify as a change to the past!

The idea of 'changing the past' occurred to the minds of philosophers long before it did in those of science fiction writers or physicists. Four centuries before Christ, the question had already been asked-and-answered by Aristotle. In his *Nicomachean Ethics*, in fact, we find him declaring that the Greek poet Agathon had known the answer a century earlier, and he quotes the poet as saying "Forever God lacks this one thing alone, To make a deed that has been done undone."

Agathon and Aristotle aside, some medieval theologians argued passionately that the past *could* be changed (but only by God). The eleventh-century Italian cleric Peter Damian (who became a Christian saint) is a famous exponent of that radical view.[29] Writing in his *De Omnipotentia Dei* ("On the Divine Omnipotence in Remaking What Has Been Destroyed and Undoing What Has Been Done"),[30] Damian made it clear that he believed nothing could withstand the power of God, not even the past. Ralph Waldo Emerson's poem "The Past" ("All is now secure and fast, Not the gods can shake the Past") would have been blasphemy for Damian. The following words from Damian testify to the strength of his commitment to a belief in the possibility of changing the past: "Just as we can duly say 'God was able to make it so [that] Rome, before it had been founded, should not have been founded,' in the same way we can equally and suitably say, 'God can make it so that Rome, even after it was founded, should not have been founded.'"[31]

---

[27] The opening line to F. M. Busby, "A Gun for Grandfather," *Future Science Fiction*, September 1957.

[28] Jiri Benovsky, "Endurance and Time Travel," *Kriterion—Journal of Philosophy*, 2011, pp. 65–72.

[29] R. P. McArthur and M. P. Slattery, "Peter Damian and Undoing the Past," *Philosophical Studies*, February 1974, pp. 137–141; P. Remnant, "Peter Damian: Could God Change the Past?" *Canadian Journal of Philosophy*, June 1978, pp. 259–268; R. Gaskin, "Peter Damian on Divine Power and the Contingency of the Past," *The British Journal for the History of Philosophy*, September 1997, pp. 229–247.

Two centuries after Damian, Aquinas argued the contrary view, that changing the past is *not* within God's power. Whereas Damian felt it impossible to deny any act to God, Aquinas took the far more moderate position that part of God's law is that there be no contradictions in the world (this is, in fact, the modern view of time travel physicists) and that certainly God would be bound by his own law. As he wrote, "It is best to say that what involves contradiction cannot be done rather than that God cannot do it." In his *Paradise Lost*, John Milton's God is constrained even more: he is free to act or not, but if he does freely decide to act, it can only be to 'do right.' That might seem to preclude causing contradiction, as in changing the past, but perhaps not. Milton's contemporary, Thomas Hobbes, declared that there is no *a priori* standard of goodness, and thus (for Hobbes) there are no constraints on God's powers. For Hobbes, therefore, it would seem God could change the past. Theological changing of the past, as you might expect, leads to all sorts of mind-boggling puzzles. Because of such puzzles, theology would certainly be influenced by time travel, but just as certainly theological reasoning will not illuminate the puzzles of the time travel paradoxes.

The question of the immutability of past events is of special interest to theologians because it is directly related to the question of free will versus fatalism. That is, are humans the creators of the future, or are they mere fated puppets of destiny? One way theology gets involved with the issue of 'changing the past' is via what is called the *retroactive petitionary prayer*. (An 'ordinary' petitionary prayer, like the Lord's Prayer in Matthew 6 and Luke 11, asks for something in the present or the future.) Examples of retroactive prayers include that of the surgical patient who prays, just before an exploratory operation, for his tumor to be non-malignant, and that of the soldier's wife who prays that her husband was not among those killed in yesterday's battle. Such prayers are for a happy outcome to an event that is over and done with at the time of the prayer. One might accept the rationality of praying about the future ("Please, God, let me survive tomorrow's battle and I'll be good for the rest of my life") but are prayers about the past even sensible? (The three major monotheistic religions of the world—Christianity, Judaism, and Islam—say *yes*.)

---

[30] This work is in the form of a letter to his friend Desiderius (who later became Pope Victor III), in which Damian rebutted Desiderius' defense of St. Jerome's claim that "while God can do all things, he cannot cause a virgin to be restored after she has fallen." Desiderius thought the reason God could not restore virgins is that he does not want to, to which Damian replied that this meant God is unable to do whatever he does not want to do, but this meant that God would then be less powerful than men, who are able to do things they don't want to do (such as go without food for a month). This is a good example of the dangers involved when getting into debates with theologians.

[31] The Argentinian writer Jorge Luis Borges (1899–1986) was so inspired by Damian's view that the past could be changed that he wrote a short story based on it (see "The Other Death," originally published in *The New Yorker*, November 2, 1968) and put a character in it named after Damian.

In an appendix titled "Special Providences" in his book Miracles, C. S. Lewis answers that question as follows:

> "When we are praying about the result, say, of a battle or a medical consultation, the thought will often cross our minds that (if only we knew it) the event is already decided one way or the other. I believe this to be no good reason for ceasing our prayers. The event certainly has been decided—in a sense it was decided 'before all worlds.' But one of the things taken into account in deciding it, and therefore one of the things that really causes it to happen, may be this very prayer that we are now offering. Thus, shocking as it may sound, I conclude that we can at noon become part causes of an event occurring at ten A.M. (Some scientists would find this easier than popular thought does.)"

Here we see Lewis, a prominent lay theologian, arguing for the present influencing (but not changing) the past. What can we make of that? Was Lewis arguing for backward causation, the close relative of time travel? I think perhaps so; the final two sentences in the above excerpt makes it plausible that he may have held that view. It is a view that does find much support in the block universe interpretation of Minkowskian spacetime. Lewis never mentions the block concept by name, but it is clear that he believed in the idea of God being able to see all of reality at once. Lewis believed, therefore, that God knows of a petitionary prayer before it is made; or, even stronger, if God is not a temporal being but rather is eternal and knows time 'all at once,' then God knows the prayer and the event being prayed about 'at the same time.'

Lewis did make it clear that he believed it is a sin to pray for something *known* not to have occurred—for example, to pray for the safety of someone known to have been killed yesterday. As he wrote, "The known event states God's will. It is psychologically impossible to pray for what we know to be unobtainable, and if it were possible, the prayer would sin against the duty of submission to God's known will." Taking a less judgmental position (but essentially agreeing with Lewis) were two philosophers who, writing of the battle of Waterloo, said "for one who knows the outcome of the battle more than a hundred and 50 years ago, [a retroactive petitionary] prayer is pointless and in that sense absurd. But a prayer prayed in ignorance of the outcome of the past event is not pointless in that way." Further, in support of backward causation, they also wrote that "to pray in 1980 that Napoleon lose at Waterloo" is logical because "why should your prayer not be efficacious in bringing about Napoleon's defeat?"[32] Disagreeing, however, was another philosopher who bluntly declared "A prayer for something to have happened is simply an absurdity, regardless of the utterer's knowledge or ignorance of how things went."[33]

---

[32] E. Stump and N. Kretzmann, "Eternity," *Journal of Philosophy*, August 1981, pp. 429–458.

[33] P. Geach, *God and the Soul*, Routledge & Kegan Paul 1969.

There have been all sorts of opinions expressed through the ages in reaction to the idea of affecting the past via retroactive petitionary prayers,[34] and on the role of backward causation. The British philosopher Michael Dummett (1925–2011), in particular, discussed Lewis' concept of such prayers with great sympathy,[35] and backward causation allows one to both explain them as well as retaining free will. That is, it is not God's foreknowledge that causes our later actions (forcing our behavior and so turning us into automatons), but rather it is our later *freely-chosen* actions that causes God's foreknowledge! While such theological speculations are interesting, in the end they are simply positions of faith, about which mathematical physics has nothing to say.

Eventually, of course, others besides philosophers and theologians began to ponder the questions raised by 'changing the past.' In a January 1963 personal letter to the editor of *The Magazine of Fantasy and Science Fiction*, Robert Heinlein wrote[36] "Mark Twain invented the time-travel story; 6 years later H. G. Wells perfected it *and its paradoxes* [my emphasis]. Between them they left little for latecomers to do." How a man as widely read as was Heinlein, who had authored some of the best short time travel stories ever written, could have written such an erroneous sentence is a mystery to me. *A Connecticut Yankee in King Arthur's Court* and *The Time Machine*, certainly both works of genius, are *not* pioneers in paradox. And Heinlein's own contributions are proof enough that there was a lot left to do with time travel, well after 1900.

The very first story to be written that even hints at the particular time travel paradox of changing the past seems to be by the Unitarian minister Edward Everett Hale (1822–1909), best known today as the author of the 1863 story "The Man Without a Country." Hale wrote "Hands Off" in 1881, and published it anonymously in *Harper's New Monthly Magazine* with the express purpose of stirring up some theological debate (which apparently it didn't). He certainly had no idea that he would come to be recognized by literary scholars as a pioneer in the yet-to-be invented genre of science fiction.

Hale's story opens with the mysterious words "I was in another stage of existence. I was free from the limits of Time, and in new relations to space." These words are spoken by an unnamed narrator, who seems to have just died, and who finds himself, in his new 'form,' observing "some twenty or thirty thousand solar systems" while in the company of "a Mentor [probably an angel] so loving and patient." Under the guidance of this Mentor, in an attempt to 'improve' history, the narrator alters the Biblical account of Joseph and his imprisonment in Egypt. At first, subsequent history *is* better, but then humanity sinks into irreversible depravity. In the end the narrator watches the last handful of humans kill each other in a particularly symbolic place for the Christian world: "The last of these human brutes all lay stark dead on the one side and on the other side of the grim rock of Calvary!" There would be no Crucifixion and Resurrection for the salvation of humankind, which naturally greatly disturbs the narrator. But the Mentor calms him, saying "Do not be disturbed, you have done nothing." It has, you see, just been an experimental world, an alternate Universe, and the narrator has learned the lesson of "Hands Off" the past.

---

[34] A summary of those opinions can be found in G. Brown, "Praying About the Past," *Philosophical Quarterly*, January 1985, pp. 83–86. Debate continues on the retroactive prayer into the 21st century: see, for example, K. Timpe, "Prayers for the Past," September 2005, pp. 305–322, and T. J. Mawson, "Praying for Known Outcomes," March 2007, pp. 71–87, both in *Religious Studies*.

[35] M. Dummett, "Bringing About the Past," *Philosophical Review*, July 1964, pp. 338–359.

[36] Reprinted in the posthumously published *Grumbles from the Grave* (edited by Heinlein's widow, Virginia Heinlein), Del Rey 1990.

Hale's story is a better Sunday sermon than it is a change-the-past time travel tale, and the device of experimenting on a not-really-real Earth is disappointing from a modern science fiction point of view. But Hale's story almost certainly did have an immediate (if indirect) impact. There is no absolute proof, but with its appearance in a national magazine, it seems quite likely that "Hands Off" was read by Edward Page Mitchell (1852–1927), an editor on a daily New York newspaper, the *Sun*. I write that because, just 6 months after Hale's story appeared, the *Sun*, in its issue of September 18, 1881, printed Mitchell's "The Clock That Went Backward." That tale, published anonymously, used a machine (the clock) for time travel,[37] as well as incorporated the idea of time travel involving paradoxes. The story predates Wells' *Time Machine* by 14 years, and Wells' novel did not include a paradoxical element.[38]

There are, however, two *hints* at paradox in Wells' novel. In the opening, during the dinner party at which the Time Traveller tries to convince his friends of the possibility of a time machine, one of them observes that "It would be remarkably convenient for the historian. One might travel back and verify the accepted account of the Battle of Hastings, for instance." To that another guest replies, "Don't you think you would attract attention? Our ancestors had no great tolerance for anachronisms." The second hint occurs when the incredulous Editor, astonished at the disheveled appearance of the Time Traveller upon his return from the future, wonders "What *was* this time traveling? A man couldn't cover himself with dust by rolling in a paradox, could he?"

What might happen if time travelers *could* change the past? This question is nicely illustrated in one novel[39] where a time traveler finds himself stranded in the London of 1810. Despite his predicament, he takes solace with "I could invent things—the light bulb, the internal combustion engine, . . ., flush toilets . . . " But then he thinks better of doing any of that: "no, better not to do anything to change the course of recorded history—such tampering might cancel the trip I got here by, or even the circumstances under which my mother and father met. I'll have to be careful."

---

[37] See Jan Pinkerton, "Backward Time Travel, Alternate Universes, and Edward Everett Hale," *Extrapolation*, Summer 1979, pp. 168–175. The time machine in Mitchell's story is more fantasy than anything else. It is simply stated that if the clock runs backward, then it travels backward in time.

[38] Wells' failure to use paradox in his famous novel surprises most modern readers and, in fact, one of the first reviewers specifically criticized him for this lapse. See the 1895 review of *The Time Machine* that appeared in *Pall Mall Magazine*, by Israel Zangwill, reprinted in Parrinder's book (note 1 in the Introduction).

[39] T. Powers, *The Anubis Gates*, Ace 1983, a work with equal shares of physics and magic.

This is really just a more recent treatment of the change-the-past paradox that was already well established in early science fiction. In a story[40] published a half-century before, we find the paradox explicitly stated, along with a possible solution that is similar to the kind of explanations that have appeared in the philosophical literature[41]:

> "Suppose you landed in your own past?," queried Eric."
>
> Dow smiled.
>
> "The eternal question," he said. "The inevitable objection to the very idea of time travel. Well, you never did, did you? You know it never happened!"

But, suppose you *could* land in your own past. What then?

One famous story[42] that considered this question *embraced* the idea of changing the past. In it a client on a dinosaur hunting safari fails to follow the instructions of his guide to do *nothing* in the past except shoot a dinosaur that is about to dies for "other reasons" anyway—alas, he accidently kills a butterfly. This results in enormous changes in history, as indicated by the 'before' and 'after' versions of the time machine company's ad:

> **before**
> TIME SAFARI, INC.
> SAFARIS TO ANY YEAR IN THE PAST.
> YOU NAME THE ANIMAL.
> WE TAKE YOU THERE.
> YOU SHOOT IT.
> **after**
> TYME SEFARI INC.
> SEFARIS TU ANY YEER EN THE PAST.
> YU NAIM THE ANIMALL.
> WE TAEK YU THAIR.
> YU SHOOT ITT.

Bradbury describes the death of the butterfly as having started the knocking "down [of] a line of small dominoes and then big dominoes and then gigantic dominoes, all down the years across Time." This is, of course, a somewhat unconvincing argument. After all, previous dinosaurs, when shot, must have fallen to the ground and flattened a lot of butterflies! With such threats for every decision, no matter how seemingly innocent, hanging over the head of a time traveler, it would take a brave soul to do much more, while in the past, than just stand still and breathe.

---

[40] C. L. Moore, "Tryst in Time," *Astounding Stories*, December 1936.

[41] See, for example, P. J. Riggs, "The Principal Paradox of Time Travel," *Ratio*, April 1997, pp. 48–64. The 'principal paradox' is that time travel is inherently contradictory because it permits the possibility of traveling to an earlier time to prevent the trip. The grandfather paradox is a special case of this. For more discussion, see T. Chambers, "Time Travel: How Not to Defuse the Principal Paradox," *Ratio*, September 1999, pp. 296–301.

[42] R. Bradbury, "A Sound of Thunder," *Collier's*, June 1952.

Equally grim is the tale[43] that takes a different view by denying the past can be changed. There we read of a doomed hero who journeys back to 1865 to save Lincoln from Booth, but his "time-distorter" is quickly taken away from him by suspicious guards. Its internal workings tick, you see, and they think he is an assassin with a clock bomb. They destroy it, haul him away to his fate, and Lincoln goes on to meet his. In the same spirit (but even more shocking) is the result of a time traveler's intentional tampering with the past in David Gerrold's 1973 novel *The Man Who Folded Himself*. That traveler experiments with "making things different" and, in his words, "Once I created a world where Jesus Christ . . . went out into the desert to fast and never came back. The twentieth century I returned to was—different. Alien."

With such a stupendous power to alter reality, assuming the past *can* be changed, perhaps one might imagine prospective time travelers to the past being required to first file Historical Impact Statements![44] Not all would receive permission. In one classic tale,[45] for example, we read of a time traveler who takes a rifle and 5000 rounds of explosive bullets back to Golgotha. His intention—to be history's first Rambo by picking off any Roman soldier who gets within a hundred yards of Jesus! As outrageous as this concept is (but who among those now reading this won't admit to at least a momentary thrill at the idea and, perhaps, even a secret willingness to do it themselves, if they could), it isn't the story's peak. That comes when the reader is reminded that it was Christ's *desire* to die on the Cross, that he *had* to die for our sins; to prevent that from happening would change all of history for the last 2000 years. What, then, should the time traveler's colleagues do when they discover his plan? Should they stop him or not? What might happen if they do interfere? Of course, if the time traveler is 'now' in the past, isn't it already 'too late' to stop him? Oh, the conundrums of time travel and changing the past!

The classic change-the-past paradox is, of course, the grandfather paradox. A famous story[46] pushed this paradox to its logical limit to illustrate its supposed dangers. Having traveled to Greece in the fifth century B.C., the traveler suddenly realizes (with just a little exaggeration): "Ninety-five generations back you'd have more grandfathers than there are people on Earth, or stars in the Galaxy! You're kin to everyone . . . You as much as take a poke at anyone, and the odds are you won't even get to be a twinkle in your daddy's eye."

---

[43] R. Silverberg, "The Assassin," *Imaginative Tales*, July 1957.

[44] See, for example, the novel by C. L. Harness, *Krono*, Franklin Watts 1988.

[45] A. Porges, "The Rescuer," *Analog Science Fiction*, July 1962.

[46] P. S. Miller, "Status Quondam," *New Tales of Space and Time*, November 1951. This is the Miller I mentioned back in note 15.


IF—YOU·WERE·STRANDED IN·TIME!
BY JACK BINDER
SUPPOSE SOME FOURTH-DIMENSIONAL PHENOMENON CATAPULTED YOU BACK TO THE DAYS OF CAESAR, WITH THE POSSIBILITY OF A RETURN TO YOUR OWN TWENTIETH CENTURY ENTIRELY REMOVED. EQUIPPED WITH AN ELEMENTARY UNDERSTANDING OF VARIOUS SCIENCES, HOW WOULD YOU CAPITALIZE ON YOUR KNOWLEDGE OF FUTURE EVENTS AND DISCOVERIES? COULD YOU, WITH A HEAD-START OF TWO THOUSAND YEARS, EARN A LIVING? WHAT WOULD YOU DO?
YOU WOULD BE HAILED AS A GENIUS IF YOU "INVENTED" A SIMPLE WOODEN CLOCK TO REPLACE THE INACCURATE SUNDIALS AND HOUR-GLASSES OF THE ROMANS. THE MYSTERY OF ITS MOVEMENTS—BY WEIGHTED GEARS—WOULD BE UNFATHOMABLE TO THE ROMANS, WHO KNEW NOTHING OF MECHANICAL LAWS. IT WOULD SEEM LIKE MAGIC TO THEM!
MAKING CLEARER GLASS THAN THE ROMANS HAD, YOU COULD GRIND THE TWO LENSES NECESSARY FOR A TELESCOPE, AFTER A LITTLE EXPERIMENTATION. THIS WOULD BE A TRULY UNBELIEVABLE INSTRUMENT TO THEM, REVEALING THE RINGS OF SATURN, JUPITER'S MULTIPLE MOONS, AND OUR OWN MOON'S CRATERS. YOU COULD SHOW THE ROMANS THREE NEW PLANETS!
ROMANS, LEND YOUR EARS! CAESAR PROCLAIMS A HOLIDAY. LET THERE BE REJOICING
YOU WOULD NOT HAVE MUCH TROUBLE MAKING A PHONOGRAPH, USING HARD WAX DISCS, GOOD FOR THREE OR FOUR RUNS. ITS TINY SOUNDS WOULD STARTLE THE ROMANS AS A REMARKABLE REPRODUCTION OF THE HUMAN VOICE. ROMAN NIGHT-LIFE WOULD BE STIMULATED BY THE "CANNED" MUSIC!

Fig. 4.2 Illustrator Jack Binder (1902–1986) was the author of a continuing series called "IF— . . ." in *Thrilling Wonder Stories*. In each issue, the ellipses would be replaced with some phrase such as "the Sun exploded!," "there was another ice age!," or "there was no friction!." The installment shown here (and in Fig. 4.3) appeared in December 1938 and asserted that the past could be changed by a time traveler


WITH PERMISSION OF HIS AUGUST MAJESTY JULIUS CAESAR
SOAP
NAILS
TOOLS
BARBARIANS AND SLAVES NOT ALLOWED!
CHEAPLY MADE FROM OLIVE OIL AND WOOD ASHES, SOAP (UNKNOWN TO THE ROMANS) WOULD MAKE YOU AN EASY LIVING, ONCE THE ROMANS WERE ACQUAINTED WITH ITS GREAT CLEANSING POWERS. YOU COULD SHOW THEIR METAL-WORKERS HOW TO MAKE SUCH ASTOUNDING IMPLEMENTS AS SAWS, SCISSORS, HAIRPINS, NAILS AND SCREWS!
CLEOPATRA AWAITING CAESAR
BARBARIANS ATTACKING GAUL
WITH TIME AND PATIENCE, A HAND-PRINTING PRESS COULD BE BUILT. EVEN THE CRUDEST OF SUCH MACHINES WOULD FAR OUT RIVAL THE SPEED OF LABORIOUS HAND-WRITING. WITH THIS, YOU COULD INTRODUCE ARABIC NUMERALS AND THE DECIMAL SYSTEM. YOU WOULD PUSH THE ROMANS TEN CENTURIES AHEAD!
AN EFFECTIVE STEAM-TURBINE COULD BE MADE, DEVELOPING MORE POWER THAN THE ROMANS DREAMED POSSIBLE. IT WOULD START THE ROMAN AGE OFF IN AN INDUSTRIAL ERA SEVENTEEN CENTURIES AHEAD OF ITS TIME. RECORDED HISTORY WOULD BE CHANGED!

Fig. 4.3 (Fig. 4.2 continued). Illustration for "IF—You Were Stranded in Time!" ©1938 by Better Publications, Inc.; Reprinted by permission of the Ackerman Science Fiction Agency, 2495 Glendower Ave., Hollywood, CA 90027 for the Estate

Even earlier than Miller's tale is an equally famous one[47] that illustrates the same point in a graphic way. In A.D. 452 a time traveler shoots and kills one of Attila's Huns (who would have been his great-grandfather many times over); the result is that 50,000 of the Hun's descendants vanish! So dramatic did the readers of this story find the concept that author repeated the idea the very next year.[48] Twenty years later another writer topped these tales by having a time traveler accidently kill the original 'intelligent baboon' in the ancient past, thereby wiping out the entire human species![49]

Science fiction writers have been as puzzled by the grandfather paradox[50] as have been nearly everybody else. As the inventor of the first time machine says in one tale,[51] "I have devised a method [for travel] into the distant past. The paradox is immediately pointed out—suppose [the time traveler] should kill an ancestor or otherwise change history? I do not claim to be able to explain how this apparent paradox is overcome in time travel; all I know is that time travel *is* possible. Undoubtedly, better minds than mine will one day resolve that paradox, but until then we shall continue to utilize time travel, paradox or not."

Some may feel it overly dramatic that the classic time travel paradox has such a murderous form, but that is its historical origin in science fiction (not in either physics or philosophy). We can find the grandfather paradox discussed as if already well-known in a letter to the editor at *Astounding Stories* (January 1933). The author of that letter wrote "Why pick on grandfather? It seems that the only way to prove that time travel is impossible is to cite a case of killing one's own grandfather. This incessant murdering of harmless ancestors must stop. Let's see some wide-awake fan make up some other method of disproving the theory." As we proceed, you'll see just how clever some of those who responded to that writer's plea have been but, even today, as the grandfather paradox stands revealed as a red herring, it is preeminent in most people's imaginations. If a solution to the grandfather paradox puzzle escaped an early science fiction writer, then he would generally just mysteriously mention it and then hasten on to other matters. For example, in one story[52] the following exchange between the stock pulp-fiction characters of a young hero and a brilliant old scientist occurs:

---

[47] N. Schachner, "Ancestral Voices," *Astounding Stories*, December 1933.

[48] N. Schachner, "The Time Imposter," *Astounding Stories*, March 1934.

[49] C. Dye, "Time Goes to Now," *Science Fiction Quarterly*, May 1953.

[50] The 'paradox' is that, assuming you do arrive in the past with a working gun, why *can't* you kill your grandfather? After all, you *must* fail in that quest because otherwise you wouldn't be there from the future to even try. But *why* must you fail? It is, of course, not actually necessary to try to kill your grandfather to run into this paradoxical situation—just go back in time to any moment in the past and try to kill yourself! You won't succeed (if the past is unchangeable), but *why not*? (To argue 'because the past is unchangeable' is to beg the question. We need more insight than that.)

[51] M. Reynolds and F. Brown, "Dark Interlude," *Galaxy Science Fiction*, January 1951.

[52] C. South, "The Time Mirror," *Amazing Stories*, December 1942.

> "You mean that time travel really is possible? That men can be transported into the future or the past—?"
>
> The other held up a restraining hand. "Yes. Time travel *is* possible . . ."
>
> "But professor! Think of what you're saying! You're telling me that I could go back and murder my own grandfather. That I could prevent myself from being born—?"
>
> Again the elder man sighed. "I was afraid of this," he said. "I knew you could not understand." He hesitated. Then: "At any rate, take my word for it that time travel is possible. Also, I assure you that there are any number of perfectly sound theoretical and practical reasons why you never could hope to murder your grandparents."

We are, however, not told just what those reasons might be.

Even when all has been said about the impossibility of changing the past, and even when they are finally willing to concede that point, most people still cannot help wondering *why* the time traveler can't kill his grandfather. There the time traveler is, after all, just two feet away from the nasty young codger (I assume he is nasty to make the whole unpleasant business of murder as palatable as possible), with a perfectly functioning and well-oiled revolver in his hand, cocked and loaded with powerful, factory-fresh ammunition that even Dirty Harry would find excessive. What can possibly prevent the time traveler from simply raising his arm and doing the deed? Indeed, the artwork (reproduced at the end of the Introduction) accompanying one 1944 story shows this act in detail, including the smoking gun in the hand of the time traveler who has just taken a shot at grandpop. And if that still leaves open the remote possibility of an aiming error through nervousness, then why can't a suicidal time traveler just wrap his body in factory-fresh dynamite and blow-up granddad—along with himself and everything else within a hundred feet?

I'll argue in this book that killing your grandfather in the past, before he sets *you* in motion, is *logically* impossible. The laws of physics will then faithfully do their duty. No one will ever find an unfinished note in the empty laboratory of a missing traveler who, skeptical of the grandfather paradox, has written "To prove the falsity of the grandfather paradox, I will take my time machine back 50 years and kill my grandf. . .." Nor will any time traveler have to be concerned about the twist in one tale, which opens with the inventor of a time machine is showing the gadget to three friends. One of them later steals the machine to go back 60 years to kill his grandfather—and the story closes with a *near* repeat of the opening, with the inventor showing the gadget to *two* friends.[53]

Invoking logic in this way, in the context of time travel to the past, was discussed in the philosophical literature nearly half a century ago: "If we assume that it is impossible for [a time traveler to kill his younger self], some people are inclined to ask such questions as this: 'But how can the laws of logic prevent him from killing his younger self? Do they cause his finger to slip on the trigger or the bullet to fly apart in mid-air?' The implication of such questions is that the laws of logic cannot prevent such actions. But such questions are like asking: 'How do the laws of logic prevent the geometer from trisecting the angle or squaring the circle? Do they, for example, cause his ruler to slip as a crucial moment every time he tries it?'"[54].

---

[53] F. Brown, "First Time Machine," *Honeymoon in Hell*, Bantam 1958.

A similar point was made later by another philosopher: "Surely it is not an impairment of 'freedom of action' . . . that, e.g., you cannot push another person harder than he/she pushes you. Just as one would explain this is the case by reference to Newton's third law ('to every action there is an equal and opposite reaction'), one could explain the impossibility of [causing a paradox] by reference to the laws which imply such a impossibility. If this explanation is taken to be unsatisfactory, it would seem that one is saddled with a general problem concerning the reconciliation of physics and 'freedom,' and not with a specific argument against [paradoxes]."[55]

The grandfather paradox unquestionably nags at all students of time travel. As a character in one story declares, "The resolution of [the grandfather paradox] is the key to time,"[56] and some incorrectly believe it remains unresolved.[57] The paradox *is* undeniably troublesome: as one philosopher put it, the apparent possibility of a time traveler being able to do away with both his grandfather and himself gives "rise to such puzzles that we are forced to question its [time travel's] intelligibility."[58] In the next section we'll explore how to answer this concern.

4.3 Changing Versus Affecting the Past

> "The past—it's pretty damn solid, Phil. It's a little like a compost pile—fairly soft near the surface but packed hard further down, with all that Time piled on top of it."[59]
>
> —one 'explanation,' perhaps, for the unchangeability of the past

The common belief today, among physicists and philosophers alike, is that given any consistent description of reality it is simply impossible for a time traveler to kill himself as a baby. As one philosopher put it, "Autoinfanticide is *metaphysically impossible* [my emphasis]. This metaphysical impossibility is philosophically intriguing because unlike most impossible events, we can vividly picture how it might look. Time travel itself seems possible, and for those who arrive in the past with proper equipment and training, the actual infanticide should not be difficult."[60] And so the grandfather paradox lives on, bedeviling both physicists and philosophers alike.

---

[54] J. W. Meiland, "A Two-Dimensional Passage Model of Time for Time Travel," *Philosophical Studies*, November 1974, pp. 153–173. Science fiction had already considered time travel suicide in, for example, K. Neville, "Mission," *Fantasy and Science Fiction*, April 1953.

[55] F. Arntzenius, "Causal Paradoxes in Special Relativity," *British Journal for the Philosophy of Science*, June 1990, pp. 223–243.

[56] P. Worth, "Typewriter from the Future," *Amazing Stories*," February 1950. See also note 106 in Chap. 1.

[57] For example, in J. H. Schmidt, "Newcomb's Paradox Realized with Backward Causation," *British Journal for the Philosophy of Science*, March 1998, pp. 67–87, we read that "there are as yet no generally accepted solutions" to the grandfather paradox.

[58] S. Gorovitz, "Leaving the Past Alone," *Philosophical Review*, July 1964, pp. 360–371.

[59] F. M. Busby, "A Gun for Grandfather," *Future Science Fiction*, Fall 1957.

Indeed, one physicist described the time travel paradoxes as "the most controversial issue related to time machines."[61] As he argued, "These paradoxes seem to be something inherent to time machines (their main attribute, perhaps), so it is reasonable to assume that if there exists a universal law prohibiting the time machines, it must have something to do with the paradoxes. And on the other hand, be the problem of the paradoxes satisfactorily solved there probably would be no need to look for such a law, the (supposed) paradoxicalness of the time machines being traditionally the main objection against them."

One of the persistent stumbling blocks to removing the confusion of the paradoxes is a failure to distinguish between *affecting* and *changing* the past. One philosopher wrote this, in a somewhat bungled attempt to explain what is meant by affecting the past: "Nothing anyone can do now can make it not have rained yesterday"[62] if, in fact, it *did* rain yesterday. This is correct, but it is *not* what is meant by *affecting* the past. Rather, if the reason it *did* rain yesterday is because a time traveler from the future seeded the clouds, then that time traveler affected the past. Making it not to have rained yesterday would be to *change* the past.

A classic[63] by Isaac Asimov illustrates what is meant by a time traveler affecting the past. An idealistic physics professor, convinced that the world's political problems are the result of the comparative newness of scientific thought and tradition, tries to change the past (and thus the present) by sending a Greek translation of a modern chemistry text back 2000 years to the Hellenic days of Leucippus, Lucretius, and Democritus. He dies in the attempt but succeeds in the transmission. When a government investigator—called in because the professor drained an entire nuclear power reactor to energize his time machine!—discovers that the transmission takes a day to travel back a hundred years (a little gimmick with no foundation in physics, but simply something Asimov needed for the story), he fears 'our' world will vanish in 20 days, to be replaced by a 'new' one. In the end, however, he learns you can't change the past. As one of the late professor's colleagues tells the investigator, "While you are right that any change in the course of past events, however trifling, would have incalculable consequences . . . I must point out that are nevertheless wrong in your final conclusion. *Because THIS is the world in which the Greek chemistry text WAS sent back.*"

---

[60] David Horacek, "Time Travel in Indeterministic Worlds," *The Monist*, July 2005, pp. 423–436.

[61] S. Krasnikov, "Time Travel Paradox," *Physical Review D*, February 14, 2002, pp. 064013–1 to -8.

[62] R. G. Swinburne, "Affecting the Past," *Philosophical Quarterly*, October 1966, pp. 341–347.

[63] "The Red Queen's Race," *Astounding Science Fiction*, January 1949.

Another good illustration from science fiction of affecting the past can be found years before Asimov's. In that story,[64] a time traveler leaves the Chicago of 1942 for the year 3000. Much later, in the year 2564, another time traveler interested in history journeys back to 2253 in an attempt to learn the cause of the great Chicago explosion of that year. The explosion was centered on the site of an ancient laboratory once used by a scientist who mysteriously vanished in 1942. The second time traveler begins his trip into the past on the same spot, with plans to go back to the day before the explosion. At the story's end, we learn that the disaster was the result of the two time travelers colliding as both 'passed through' 2253. The backward traveling historian, therefore, by pushing a button in 2564, is the cause of an event that happened 311 years earlier.[65]

To give a science fiction example of changing the past, it would be hard to do better than with a story that appeared a few years after Asimov's The central character is a researcher in time travel who has concluded that what is wrong with the world can be traced back to the scientific method getting off to a late start (this story was almost surely written as a result of Asimov's tale!): the time traveler thinks he can correct matters by visiting 340 B.C. and educating Aristotle on the proper scientific attitude. (Aristotle believed that observing the world was inferior to pure thinking about how the things, in his opinion, *ought* to work.) This the time traveler does, with utterly disastrous consequences. He returns to the present to find a scientifically retarded world that makes him a slave. In his cell he writes on a wall the bitter lesson he has learned too late: "Leave Well Enough Alone."[66]

It is the fear of time travelers from the future attempting to alter the past that has led some philosophers (and not just a few physicists) to assert that time travel is impossible, because it would mean what they feel to be impossible might happen: changing the past. One philosopher, however, argued long ago that such a worry is unwarranted. As he wrote at the end of an essay (a polemic *against* the concept of four-dimensional spacetime, and so *against* the idea of time travel), "Squandering vast sums on foolish enterprises is an everyday occurrence. [For example], will the U.S. time explorer get back and eliminate Lenin before his Russian rival gets back even earlier and eliminates George Washington? . . . If such spectacular folly once gets under way because governments have been convinced of some nonsensical theory, a logician will not . . . lose any sleep about who is going to succeed."[67]

---

[64] O. Saari, "The Time Bender," *Astounding Stories*, August 1937.

[65] This story describes something a bit more than 'simply' affecting the past; it has a *causal loop* in it. The time traveling historian makes his trip *because* of an event in the past that his trip causes. Such paradoxes will be the subject of the next section.

[66] L. Sprague de Camp, "Aristotle and the Gun," *Astounding Science Fiction*, February 1958. Asimov and de Camp were close friends, and their two stories with similar premises are clearly the result of a bit of friendly rivalry.

[67] P. Geach, "Some Problems About Time," in *Studies in the Philosophy of Thought and Action* (P. F. Strawson, editor), Oxford 1968.

And long before that essay (with its correct conclusion reached through faulty reasoning) was penned, we learn the same lesson (in a 1923 tale by the English novelist May Sinclair (1863–1946)) as we follow a woman right into hell after her death; she ends up there because of an immoral life. She then wanders through time, into her past, but finds that she can change nothing. As she is told, "You think the past affects the future. Has it never struck you that the future may affect the past? . . . You *were* what you *were to be*."[68] This last line, from a *non*-science fiction story, is consistent with the modern view held by physicists of time travel. You cannot travel anywhere into the past unless you've already been there, and when you do make the trip you will do what you've already done there. You could not, as does the time traveler in one tale,[69] change the course of history by revealing twentieth-century physics in the eighteenth century. That does not mean you would necessarily be ineffectual during your stay in the past, however (certainly it doesn't mean, as Hugo Gernsback thought, that you'd be *invisible*!) Not being able to change the past is not equivalent to being unable to *influence* or *affect* what happened in the past, and science fiction writers have used this distinction to good effect, as did Asimov (note 63) and de Camp (note 66).

Robert Heinlein was a science fiction writer who clearly understood time travel paradoxes, both what they mean and, at least as important, what they do not mean. In his 1964 cold-war novel *Farnham's Freehold*, for example—the story of a family that is literally blasted twenty-one centuries into the future when their bomb shelter receives a direct hit from a Soviet nuclear warhead—we find following exchange as two of the characters are about to return to their original time via time machine:

> "The way I see it, there are no paradoxes in time travel, there can't be. If we are going to make this jump, then we already did; that's what happened. And if it doesn't work, then it's because it didn't happen."
>
> "But it hasn't happened yet. Therefore, you are saying it didn't happen, so it can't happen. That's what I said."
>
> "No, no! We don't know whether it has already happened or not. If it did, it will. If it didn't, it won't."

Modern philosophers, and many physicists, too, as well, who have examined the concept of time travel in depth, agree with Heinlein's character and, indeed, it is now common practice to invoke the so-called *principle of self-consistency*—generally attributed to the Russian astrophysicist Igor Novikov (see note 117 in Chap. 1) because he and his colleagues did not simply invoke it, but rather were able to *derive* it from the *principle of least action*, a concept held by many to be at the highest level of importance in physics[70]: all that is required, argued Novikov, in *any* physical process (including time travel), is that a *logical* consistency exist between events.[71] In his book *Evolution of the Universe* (originally published in Russian in 1979), Novikov wrote "The closure of time curves does not necessarily imply a violation of causality, since the events along such a closed line may be all 'self-adjusted'—they all affect one another through the closed cycle and follow on another in a self-consistent way." He later repeated that view in one of the first time machine papers in the physics literature.[72]

---

[68] M. Sinclair, "Where Their Fire Is Not Quenched," in *After the Darkness Falls* (B. Karloff, editor), World Publishing 1946.

[69] D. Beason, "Ben Franklin's Laser," *Analog*, December 1990.

In fact, despite the attachment of Novikov's name to the principle of self-consistency, it was actually around in physics *decades* earlier; it has been traced back to as far as 1903![73] And at least an intuitive understanding of the principle can be found in the mainstream literature from nearly as long ago. For example, in Lord Dunsany's short 1928 play *The Jest of Hahalaba* (the inspiration for the 1944 film *It Happened Tomorrow*), a man obtains (via supernatural means) a copy of tomorrow's newspaper. In it he reads his own obituary, which so shocks him that he promptly expires—thus explaining the obituary notice.

The principle of self-consistency has been in science fiction long before Novikov, too. An example is the 1941 story "Time Wants a Skeleton" (see note 15). In it one character, after puzzling over a time travel paradox, realizes that "Future and present demanded co-operation, if there was to be a logical future!" And a nice lecture on the principle (that pre-dates by 3 years the dialogue quoted earlier from Heinlein's *Farnham's Freehold*) is given by a character that is particularly interesting because it was published, not in a specialty science fiction magazine catering to an audience with 'genre knowledge' of time travel, but rather in an icon of general American culture.[74]

Not all science fiction writers, however, have understood the requirement for consistency around a loop in time. In one tale, for example, a man meets the inventor of a time machine and agrees to his request to use it to travel into the future. Once he is in the future, alas, the machine breaks. The man then finds another machine that, though it is too small for him to fit in it, is able to hold a recording that he sends back into the past to himself, to a time *before* he started his forward journey. The message on the recording (which he did not receive the 'first' time) is, of course, *not* to make a deal with the inventor. This advice he follows, and so the principle of self-consistency is violated twice in this story.[75]

---

[70] Like just about everything concerning time travel, however, not *all* think this. For example, the great German physicist Max Planck (1858–1947), the 1918 Nobel physics laureate, said (in 1922): "Physics hence is inclined to view the principle of least action more as a formal and accidental curiosity than as a pillar of physical knowledge." Still, he *did* also declare that he thought it unlikely "the dominance of such a simple law could be a mere accident." Quoted from Marc Lange, "Conservation Laws in Scientific Explanations: Constraints or Coincidences," *Philosophy of Science*, July 2011, pp. 333–352.

[71] See A. Carlini, *et al.*, "Time Machines: The Principle of Self-Consistency as a Consequence of the Principle of Minimal Action," October 1995, pp. 557–580, and "Time Machines and the Principle of Self-Consistency as a Consequence of the Principle of Stationary Action (II): The Cauchy Problem for a Self-Interacting Relativistic Particle," October 1996, pp. 445–479, both in *International Journal of Modern Physics D*.

[72] I. D. Novikov, "An Analysis of the Operation of a Time Machine," *Soviet Physics JETP*, March 1989, pp. 439–443.

[73] R. D. Driver, "Can the Future Influence the Present?" *Physical Review D*, February 15, 1979, pp. 1098–1107.

[74] R. F. Young, "The Dandelion Girl," *The Saturday Evening Post*, April 1, 1961. See also note 49 in Chap. 2.

An ability to play a role in history is not without some constraints. You can't save Jesus with a rifle (see note 45), or Joan of Arc with a fire extinguisher, or knock-out John Wilkes Booth with a baseball bat outside of Ford's Theatre, or blow-up Hitler with a bomb, and you can't prevent either the Black Death in the London of 1665 or the Great Fire the following year. But it *is* logically possible for a time traveler who has an infected rat sneak into his time machine, or who carelessly discards a match, to be the *cause* of the last two examples. That was the fate, for example, of the time traveling historian from A.D. 2461 who was the cause of the plague in A.D. 562 Rome, as well as of that in England nearly 800 years later.[76]

Michael Moorcock's 1969 novel *Behold the Man* gets the impossibility of changing the past, and the possibility of affecting it, right. When a disturbed man journeys backward in time to ancient Galilee to meet Christ, only to discover that there is no such person, *he* assumes the role and lives out the Biblical accounts up to and including dying on the Cross. He has not changed the past, but he certainly plays an important role in it!

An early science fiction story that got this right, long before the philosophers and physicists thought of it, was the clever tale whose artwork I have reproduced at the end of the Introduction.[77] In that story, a time traveler journeys back from 1943 to 1870 and shoots his then 14-year old grandfather in the head. Leaving his victim lying on the ground with "blood oozing all over the youth's forehead," the would-be killer returns to 1943. Once back, however, he finds himself in a strange place where he learns from two men that the Germans destroyed New York in 1920 with poison gas! Suddenly realizing that the death of his grandfather has apparently changed history (a curious oversight for anyone smart enough to invent a time machine and then to use it to force the 'grandfather paradox'), he decides he'd rather be dead than be cut off for all time from the world he remembers. So, he shoots himself dead. Then we learn that the two men he encountered are actually inmates in an asylum who like to make-up stories for unsuspecting strangers. We also learn that the time traveler's grandfather's photographs always did show him with a "white, furrowed scar on his forehead that might have been caused by a glancing bullet."

---

[75] R. Wilson, "The Message," *Astounding Stories*, March 1942.

[76] G. C. Edmondson, "The Misfit," *Fantasy and Science Fiction*, February 1959.

[77] M. Weisinger, "Thompson's Time Traveling Theory,' *Amazing Stories*, March 1944.


I am going to invent time travel???

Fig. 4.4 The inventor of a time machine about to commit autoinfanticide in the past (the youngster holding the teddy bear is a younger version of the time traveler). Illustration reproduced by the kind permission of Frank Arntzenius (Professor of Philosophy at Oxford University), from his paper "Time Travel: Double Your Fun," *Philosophy Compass*, November 2006, pp. 599–616

Well, okay, you might say at this point, 'I'm convinced you can't change the past, but let's get back to the autoinfanticide (grandfather) paradox. So *why can't* a time traveler kill his baby-self in the past?' A possible answer, one now generally accepted by philosophers and physicists alike, appeared first in science fiction. In a tale[78] that appeared just the year after Gödel's 1949 discovery of time travel in general relativity, we find a character saying "The answer is quite simple. When the man goes back in time and kills his grandfather, and returns to his own time again, he finds to his surprise that he made a mistake. It was not his grandfather at all! And no matter how many times he goes back and kills his grandfather … he *always* [my emphasis] finds he made a mistake." Or, perhaps, some noise distracts him as his finger tightens on the trigger, or the grenade he tosses at granddad is a dud, or a gust of wind deflects the arrow, or (most ludicrous of all) he simply slips on a discarded banana peel!

Okay, that works for *that* time traveler. But suppose, someone objects, that we arrange to have a *lot* of time travelers go back in time, each with murder in his heart for his grandfather. Then, as one philosopher has observed, "Since [killing one's grandfather in the distant past] is impossible, each assassin fails. Some change their minds, others slip on banana peels, yet others kill the wrong target, and so on. But there is something odd about the idea that such coincidences are guaranteed to happen, again and again!"[79]

Early science fiction avoided invoking banana peels by providing an even more extreme 'explanation' for the failures: the time police, who are charged with foiling would-be grandfather killers. (See, for example, the many stories by Poul Anderson (1926–2001) of the 'Time Patrol.') These time commandos are imagined to roam the corridors of time, disrupting the attempts of all those who would change recorded history. Stories of these temporal cops are simply westerns, mysteries, police procedurals, or some other similar type of specialty genre story wearing thin camouflage. This story device, whose main purpose is to allow both time travel and free will,[80] has been correctly called "boring" by at least one philosopher (see note 5 in the Introduction), an evaluation shared by modern philosophers, physicists, and (I think) even most modern science fiction writers.

---

[78] "Typewriter from the Future": see note 106 in Chap. 1.

[79] Theodore Sider, "Time Travel, Coincidences, and Counterfactuals," *Philosophical Studies*, August 2002, pp. 115–138.

So, we seem to be back to banana peels to save grandfather—but it *is* difficult to deny that vast hordes of murderous grandsons *do* appear to require an unlimited number of strategically placed banana peels, strewn all about the past, to trip-up every one of those potential assassins. This problem, of repeated, improbable coincidences to thwart murderous descendants from the future, was first commented on by the philosopher Paul Horwich in 1975 (see note 19 in the Introduction), and then given a convincing resolution by another philosopher in 1997.[81]

To explain the argument, I'll first use the philosopher's less deadly example of dated objects. "Suppose," he writes, "that every object has written upon it the date on which it will cease to exist . . . perhaps a time traveler travelled into the future, observed the demise of objects and then travelled back [to just after he left for the future] and wrote the dates."[82] If now the time traveler tries to destroy an object *before the date written on it*, then he *will* fail. As the philosopher amusingly described his attempts to destroy a pen 'before its time,' "I take it outside to place under the wheels of a passing train, but there is a train strike that day. The telephone rings just as I am about to drop the pen into a vat of acid. I slip on a banana peel on my way to put the pen in the microwave. My dog eats my designs for a pen grinder. And so on, for as long as you please. However many attempts I make, the attempts in no way require the occurrence of the coincidences that foil them." To put it bluntly, 'Stuff happens.' The pen has the observed date of its destruction on it, and that date is still in the future and so it is simply impossible to destroy it now.

Now, here's the point: the date on the pen is there *because* all those attempts to destroy it before that written date fail. But the presence of the date is *not* the reason for any of the weird (?) occurrences that disrupted all the attempts to destroy the pen, but rather it's *because* all those attempts failed that the date is what it is. This same argument applies to the grandfather paradox. The only time travelers available, today, to go back into the past to *try* to kill their grandfathers, are precisely those time travelers whose grandfathers were *not* killed. Or, to paraphrase our philosopher (note 81), to ask 'why do coincidences always foil the time traveller's attempts to kill [grandfather in the distant past], is to get things back to front. It is only because the murder attempts fail that the time traveler is alive in the future to even make the *attempt*.'

---

[80] See, for example, David King, "Time Travel and Self-Consistency: Implications for Determinism and the Human Condition," *Ratio*, September 1999, pp. 271–278.

[81] Nicholas J. J. Smith, "Bananas Enough for Time Travel?" *British Journal for the Philosophy of Science*, September 1997, pp. 363–389.

[82] This does present us with the curious (although non-paradoxical) situation that the time traveler will find, upon his appearing in the future, the date he *will write* (in his personal future) when he returns to just after he left on his time trip.

In other words, not only is the grandfather 'paradox' not a paradox, it isn't even surprising!

4.4 Causal Loop and Bootstrap Paradoxes

> "My dear Collingwood, don't drive yourself crazy trying to resolve the paradoxes of time travel. The [time machines] are gone . . . have a drink."[83]

The grandfather paradox might finally have been put to rest, but there are still plenty of other logical minefields left to be negotiated. One of the more puzzling is that of the closed loop in time, a conundrum nicely illustrated by one philosopher[84] as follows, as an explanation of the journey one time traveler makes to 3000 B.C.: "In our time travel story it just may be that the traveler's interest in going back to ancient Egypt is stimulated by recently discovered documents, found near Cairo, containing the diary of a person claiming to be a time traveler, whereupon our hero, realizing it is himself, immediately begins . . . construction of a rocket in order to 'fulfill his destiny.'" In other words, (1) he builds a time machine and goes back to the past because of the discovered diary, and (2) the diary is discovered because he goes back to the past. Each of these points by itself has logical clarity, but together they form a closed time loop (a *causal loop*) of enormous mystery.

Science fiction was strewn with causal loops long before the philosophers and physicists began to ponder them, however, with (for example) one early tale on a time traveler who journeys a century into the past because she finds an old, yellowed newspaper story describing her arrival.[85] But this tale wasn't the first to use a causal loop, as we can find one of the first sophisticated treatments of this device in a story that appeared even earlier (in the same publication).[86] A time traveler in 1930, about to start his journey into the future in an airplane/time machine, wonders at the last moment if he should really go—then he sees himself returning and thus *knows* he will successfully make the trip.

As he later tells a friend, "That decided me . . . Paradoxical? I should say so! I had seen myself return from my time-trip *before* I started it [just like Marty McFly in the original *Back to the Future* film]; had I *not* seen that return, I would *not* have commenced that strange journey, and so could *not* have returned in order to induce me to decide that I *would* make the journey!" And later, when he finds himself in a dangerous situation in the future, he draws hope from that initial experience: "I *would* escape ... It was so decreed. Had I not, with my own eyes, seen myself appear out of the fourth dimension back there in the Twentieth Century, and glide down to my landing-field? Surely, then, I *was* destined to return to my own age safe and sound."

---

[83] A science fiction suggestion that in certain situations (particularly causal loops), might actually be good advice! From L. Sprague de Camp's "The Best-Laid Scheme," *Astounding Science Fiction*, February 1941.

[84] L. Dwyer, "Time Travel and Some Alleged Logical Asymmetries Between Past and Future," *Canadian Journal of Philosophy*, March 1978, pp. 15–38.

[85] P. Bolton, "The Time Hoaxes," *Amazing Stories*, August 1931.

[86] F. J. Bridge, "Via the Time Accelerator," *Amazing Stories*, January 1931.

Even more dramatic is the second, internal time loop that ends the story. When the time traveler arrives in a ruined city in the year A.D. 1,001,930 he is greeted, *by name*, by an old man who says he (the old man) is the Last Man alive. He knew the time traveler was coming because an ancient history book had said the Last Man had, in fact, appeared in the year A.D. 502,101 in the very time machine out of which the time traveler has just stepped. The time traveler is so startled by all this (and who could blame him!?) that he decides to mull over what he has been told until the next day. As he wakes up in the morning, he is just in time to watch the Last Man depart for 502,101. Stranded in the future, the time traveler wanders the empty city in despair until he chances upon a museum. And in the museum, sealed in a glass case, is his time machine (!)—it has been there for half a million years, since the end of the Last Man's journey. And so the time traveler is saved; he merely adds some oil to the still-functional engine (if you can accept time travel, I suppose this is no more difficult to believe) and returns to 1930—just as he saw himself do at the beginning of the story.

Since Bridge's astonishing story, the idea of a causal loop in time has been used many times in science fiction. Here's a representative sampling:

(1) Time travelers arrive in the forty-sixth century, only to find that they are expected. Their host tells them why: "I have been awaiting your arrival from the past. I have a written record of your coming. You see, I have a time machine myself ... With my time machine, I recently went a year into the future and read the written account I had made, or will make after you leave. Then I came back, awaiting your arrival."[87]

(2) Armed travelers return to the Triassic age to uncover the secrets of a mysterious artifact that has been recently discovered; at the end we learn it is the remains of their own automatic rifle[88];

(3) A time traveler journeys back 500 years, where he suffers an accident that results in his being "agelessly stuck" in his time-traveling gadget until he is freed—by himself, 500 years later. He then gets into the gadget to journey back 500 years[89];

(4) The world's time suddenly loses 5 min, an astonishing event that comes to be called "the time drop." After 2 weeks of investigation, a reporter traces this

---

[87] E. Binder, "The Time Cheaters," *Thrilling Wonder Stories*, March 1940.

[88] J. Blish, "Weapon Out of Time," *Science Fiction Quarterly*, Spring 1941.

[89] A. B. Chandler, "The Tides of Time," *Fantastic Adventures*, June 1948.

event to a reclusive (but brilliant, of course) scientist who reveals that he has invented a time machine. The reporter decides to test this claim by using the machine to return to just before the start of the time drop, to observe precisely what caused it—it is, in fact, a malfunction of the machine that is at fault and the reporter finds himself caught in a 2-week long causal loop[90];

(5) A physicist knows something odd lies in his future when he is confronted with a 700 year-old museum copy of a book. The puzzle is how to explain a message penned in ancient, faded ink, in modern English *and in his handwriting*, on the back side of one of the recently unglued endpapers! How, too, to explain his own fingerprints all over the same endpaper? How, indeed, to answer these questions is his problem when he is presented with all of this and is asked, "Have you, by any chance, been visiting the thirteenth century?" At the end of the story the time loop is closed when the physicist finds himself writing that same message on a *brand new* copy of the book that has been sent from the past (and that he returns to the thirteenth century via a "time portal")[91];

(6) A time traveler from 1964 is secretly observed by one of the 'locals' when he arrives in 1683. The oddness of the sudden appearance of the time traveler and his machine ("It were a kind of Dazzle") makes the local think it might be that the stranger is the man who stole some items from his home the previous night, the same night he had an "ill Dream." Stealing the time machine after the time traveler has gone exploring, the local travels to 1964 where he learns how valuable antiques are. So back he goes to 1683, to the night before the time machine first appeared, to get some 'antiques' from his house. And thus he realizes who the thief *really* was. Before leaving again for the future, he enters his own bedroom to see himself asleep and then to awaken. And so he also learns the cause of what he called his "ill Dream."[92];

(7) A movie production crew goes into the past to make a film. At the end of the story it becomes clear that their presence in the past was not an insignificant event, as one character realizes after seeing the evidence of how they affected (*not* changed!) the past: "If this is true, then the only reason that the Vikings settled in Vinland is because we decided to make a motion picture showing how the Vikings settled in Vinland"[93];

(8) A private college, endowed decades before by a generous but mysterious benefactor, experiments with a time machine. Suddenly, one of the college's graduates is accidently sent a hundred years into the past—where she becomes the benefactor. The college comes into existence, therefore, because it will exist[94];

---

[90] W. Sheldon, "A Bit of Forever," *Super Science Stories*, July 1950.

[91] M. Leinster, "The Gadget Had a Ghost," *Thrilling Wonder Stories*, June 1952.

[92] D. I. Massor, "A Two-Timer," *New Worlds SF*, February 1966.

[93] H. Harrison, *The Technicolor Time Machine*, Doubleday 1967.

[94] C. Simak, "The Birch Clump Cylinder," *Stellar 1* (J. del Rey, editor), Ballantine 1974.

(9) A man gets the money to support his experiments in time travel by selling a large collection of old, rare comic books he has discovered in his late mother's attic. Later we learn how the comic books came to be there; after his experiments are successful, the inventor travels back into the distant past, buys the *newly* published comic books right off newsstands, and stores them in his mother's attic where, decades later, he knows his younger self will grow up and then find them (and thus get the money to make it all happen)[95];

(10) In the 1980 film *Somewhere in Time* (based on the 1975 novel *Bid Time Return* by Richard Matheson), a man in the present is visited by a mysterious old woman who gives him a watch. Later, he travels back to 1912 where he meets a girl to whom he gives the watch. He then returns to the present, and she lives out her life from 1912 on, until she too reaches the present, where we discover she is the (now old) woman who gives the man the watch.

Once philosophers discovered the bizarre nature of causal loops, they quickly proved themselves to be the equal of science fiction writers in imagining strange doings. Here's one example of that, one which any writer would be proud of: "If James cannot decide whether to marry Alice or Jane, he simply travels to the future and learns that he is to choose Alice; he then chooses her for this reason. One wants to object that the decision to marry Alice was never really made at all! But this is not true; the decision was made—as a result of the knowledge that this was the decision . . . It is not the case that the prospective bridegroom could visit the future and compare the results of marrying Alice with those of marrying Jane in order to decide between the alternatives. For if he visits the future, he will learn only that in fact he chose Alice, for better or for worse!"[96]

This same philosopher elaborated on his view of causal loops in a later paper, where he wrote "What if time travel becomes commonplace, so that we must deal with a constant stress of time travelers returning from the future to reveal what they have seen?"[97] His answer is "I think it is clear that the . . . causal loop we have been discussing would become very common, and would play a prominent role in human affairs." He denied, however, that such causal loops would mean the loss of free will. As he explained his position, knowledge of a rigged roulette will not prevent you from putting your money on the table *if you want to*, but perhaps that knowledge will influence your *freely* made decision making. Whether you learn that the roulette wheel is rigged by traditional means (perhaps you see magnets being installed under the table) or by means of time travel is irrelevant—even with this knowledge, you act freely. Other philosophers have not been so generous. One disliked causal loops so much, for example, that while he believed them to be conceptually possible, he also thought them to have "a queer smell,"[98] so much so that he simply preferred to avoid thinking about them!

---

[95] D. Knight, "The Man Who Went Back," *Amazing Stories*, November 1985. This same idea was used earlier in the story "Compounded Interest," (*Magazine of Fantasy and Science Fiction*, August 1956) by Mack Reynolds, in which the inventor of a time machine has the money to build his gadget because he uses it to go back into the past where he deposits a small sum, which then grows (through the 'magic' of compound interest) into the cash he needs to fund his time machine.

[96] G. Fulmer, "Understanding Time Travel," *Southwestern Journal of Philosophy*, Spring 1980, pp. 151–156.

[97] G. Fulmer, "Time Travel, Determinism, and Fatalism," *Philosophical Speculations in Science Fiction and Fantasy*, Spring 1981, pp. 41–48.

One concern that many philosophers and physicists have had with closed loops in time is that they fear that would mean being trapped on an endless cycle of repeating events. For example, one philosopher long ago wrote

> "There is nothing contradictory in imagining causal chains that are closed, though the existence of such chains would lead to rather unfamiliar experiences. For instance, it might then happen that a person would meet his own former self and have a conversation with him, thus closing a causal line by the use of sound waves. When this occurs the first time he would be the younger ego, and when the same occurrence takes place a second time he would be the older ego. Perhaps the older ego would find it difficult to convince the younger one of their identity; but the older ego would recall an identical experience long ago. And when the younger ego has become old and experiences such an encounter a second time, he is on the other side and tries to convince some 'third' ego of their physical identity. Such a situation appears paradoxical to us; but there is nothing illogical in it."[99]

What has been (erroneously) described with that is the beginning of an endless succession of encounters around a closed causal loop. There is, however, just *one* encounter on such a loop in spacetime (but, of course, the mind of the time traveler experiences the encounter twice), subject to the constraint of self-consistency. Some physicists, too, have been so concerned about multiple trips around closed timelike curves (CTCs), because they think such trips would allow the past to be changed, that they have felt it necessary to specifically forbid such a possibility. As one paper put it, "That the principle of self-consistency is not totally tautological becomes clear when one considers the following alternative: The laws of physics might permit CTCs; and when CTCs occur, they might trigger new kinds of local physics which we have not previously met. For example, a quantum-mechanical system, propagating around CTCs, might return to where it started with values for its wave function that are inconsistent with the initial values; and it might then continue propagating and return once again with a third set of values, then a fourth, then a fifth … The principle of self-consistency by fiat forbids changing the past."[100]This last statement is, of course, in agreement with the position I have taken in this book, a position that has generally been accepted by most philosophers for several decades now, but the proponents of the principle of self-consistency seem to have been driven to it by a fear of the past 'happening again' over and over, as in the 1993 film *Groundhog Day*.

---

[98] M. MacBeath, "Communication and Time Reversal," *Synthese*, July 1983, pp. 27–46.

[99] H. Reichenbach, *The Direction of Time*, University of California Press 1956, p. 37.

[100] J. L. Friedman et al., "Cauchy Problem in Spacetimes with Closed Timelike Curves," *Physical Review D*, September 15, 1990, pp. 1915–1930. Another physicist, however, has flatly rejected this need for the Principle, calling it redundant: see D. Deutsch, "Quantum Mechanics Near Closed Timelike Lines," *Physical Review D*, November 15, 1991, pp. 3197–3217.

Science fiction writers have stumbled into the error of endless cycling on a closed time loop, too. In one such tale,[101] the inventor of the first time machine travels 500 years into the future where he finds a bronze statue of himself that honors his discovery of time travel. Suddenly injured, fatally, he returns to the present with the statue and then dies. As a memorial, the statue is placed in the very spot where the inventor found (will find) it. As the tale ends, the late inventor's lab assistant wonders to himself what will happen 500 years later: "Suddenly a strange machine will come out of the past and [the inventor] will be here again—although he is dead and has been dead 500 years. [He will take the statue] and go back to the past . . . to die. And once again that maddening cycle will begin, to go on and on forever as long as time spins its threads."

That story illustrates yet another puzzle associated with those causal loops that contain a circulating, physical object. That is, *who made the statue*? We can ask the same question about the watch in the time loop of *Somewhere in Time/Bid Time Return* as, at every instant of its existence, the watch is in the possession of either the man or the woman? So, *when was the watch constructed*?

There have been some science fiction writers who specifically recognized this question, long before either the philosophers or the physicists paid attention to it. In one early tale,[102] for example, we read of a time machine that travels from 1935 to 1925. When the question of the origin of the time machine comes up, we read

> "One time machine, found in 1935 and brought back to 1925—found in 1935 *because* brought back to 1925. That is all."
>
> "But who made it in the first place?—Oh, skip the 'in the first place.'[103] Just plain: who made it?"
>
> "No one. It was never made . . . It is here because it is here."

This same puzzle was addressed in *The Technicolor Time Machine* (note 93), when one character is perplexed over a piece of paper in his wallet with a diagram on it, a piece of paper he got from himself (an *older version* of himself, who traveled into the past to give it to his younger self). In frustration, he asks a friend:

> "Then no one ever *drew* this diagram. It just travels around in this wallet and I hand it to myself. Explain that."
>
> His friend replies:
>
> "There is no need to, it explains itself. The piece of paper consists of a self-sufficient loop in time. No one ever drew it. It exists because it is, which is adequate explanation. If you wish to understand it, I will give you an example. You know that all pieces of paper

---

[101] S. Mines, "Find the Sculptor," *Thrilling Wonder Stories*, Spring 1946.

[102] R. M. Farley, "The Man Who Met Himself," *Top-Notch Magazine*, August 1935 (*Top-Notch* was an adventure pulp published between 1910 and 1937).

[103] The reason for this line in the story is that earlier the question of "Where did the time machine come from *originally*?" was raised. The answer: "There was never any 'original.' . . . There is no round-and-round circle of events, no repetition. Merely *one* closed cycle." This is, in fact, the modern view of causal loops, expressed in a 1935 (!) science fiction story.

> have two sides—but if you give one end of a strip of paper a 180-degree twist, then join the ends together, the paper becomes a Möbius strip that has only one side. It exists.[104] Saying it doesn't cannot alter the fact. The same is true of your diagram; it exists."
>
> "But—where did it come from?"
>
> "If you must have a source, you may say that it came from the same place that the missing side of the Möbius strip has gone."[105]

The undeniable mystery of causal loops is the reason behind the philosopher I cited earlier (note 98) who thought they have a "queer smell" and so viewed them with much suspicion. He wasn't alone in that feeling, and another philosopher said as much whe he wrote "despite [strong] arguments for the consistency of time travel stories [with causal loops], the impression is apt to remain that something is wrong with them. I think this impression is correct."[106] One story that this philosopher could well have had in mind is a classic,[107] a tale that describes a knife brought from a museum in the future back to the present. It arrives in the present with a flawless blade, but soon thereafter gets a nick in the blade. How, wonders the narrator, can the time loop be completed "again"? I do not find this quite the puzzle that either the author (and perhaps the philosopher) do: it is simply a variation of the grandfather paradox (which has been shown not to be a paradox at all). *If* the knife is found flawless in the future, *then* it was not (will not) be nicked in the past. As written, the story is not logically consistent as it involves changing the past but, *if* one removed the detail of a *nicked* blade, then we *would* have a true (paradoxical) causal loop, with the question the story, itself, asks about the knife: "How was this knife created . . . when its existence has no beginning or end?"

The nicked knife does illustrate a subtle problem that bedevils *any* causal loop containing a physical object. Consider once again the watch in the film *Somewhere in Time*. Assume the watch received by the man in the present is bright and shiny. He then takes it back into the past and gives it to his love. It remains with her after his return to the present until, decades later, she gives it to him—bright and shiny. Why didn't it tarnish? Is there some peculiar anti-tarnish property to a watch in a causal loop? Well, if so, is that anymore odd than a causal loop itself?[108]

None of that, however, provides a means for rejecting time travel *if* one can argue that it is possible to have time travel *without* causal loops. Indeed, Professor Hanley (see note 105) argues that it is possible, and presents what he claims is an example of how to do it. Alas, another philosopher convincingly showed that the example is flawed and that Hanley's claim that there is no causal loop in his story "is unjustified."[109] From an entertainment point of view, however, eliminating causal loops is going in the wrong direction, as it is the inclusion of causal loops that gives a feeling of mystery to a good science fiction story.

---

[104] See note 99 in Chap. 1, and the related discussion there.

[105] One philosopher calls this bit of dialog "unhelpful," while ignoring the fact that it appeared in a science fiction pulp magazine and not a scholarly journal, and was clearly meant to dazzle teenage boys (see note 39 and related discussion in "Some First Words") with the concept of a causal loop, rather than to break new ground in metaphysical thought. See Richard Hanley, "No End in Sight: Causal Loops in Philosophy, Physics and Fiction," *Synthese*, July 2004, pp. 123–152.

[106] G. Nerlich, "Can Time Be Finite?" *Pacific Philosophical Quarterly*, July 1981, pp. 227–239.

[107] P. S. Miller, "As Never Was," *Astounding Science Fiction*, January 1944. This is the same Miller who appears in note 15 (and see note 46, too).

[108] It is *not* sufficient to say that perhaps she polished the watch. Polishing would remove material from the watch, which means she gives him a watch different from the one he gives her in the past.

To finish this section, then, we can do no better than to discuss causal loops that are even *more* bizarre than are those with a physical object; that is, loops that involve time traveling *information*. (Since information doesn't 'tarnish,' however, such a loop avoids that particular puzzle associated with a physical object in a causal loop.) A classic example of such a loop is a mathematician who is visited in his youth by a time traveler from the future (perhaps himself), who gives him the proof of a theorem for which the mathematician is (will be) famous in the future. *Where*, then, did the proof actually come from? In what *mind* was it *created*?[110]

The philosopher David Lewis wrote with particular insight on causal loops, especially ones that involve information transfer, such as a time traveler going back in time to tell his younger self how to build a time machine so that once its constructed he can go back in time and tell himself how to do it.[111] (This was item (3), you'll recall, in Jim Nicholson's 1931 letter to *Science Wonder Stories* magazine, quoted at the end of the first section of this chapter.) As Professor Lewis wrote (see note 5 in the "Introduction"), "But where did the information come from in the first place? Why did the whole affair happen? *There is simply no answer* [my emphasis]. The parts of the loop are explicable, but the whole of it is not. Strange! But not impossible, and not too different from inexplicabilities we are already inured to. Almost everyone agrees that God, or the Big Bang, or the entire infinite past of the Universe, or the decay of a tritium atom, is uncaused and inexplicable. Then if these are possible, why not the inexplicable causal loops that arise in time travel?"

A few years later, another philosopher[112] gave a similar response to a paradox involving a causal loop similar to Lewis', a loop involving a time machine containing a book with instructions on how to make the time machine. The book travels into the past on the machine so it can be read—in order to make the machine.

---

[109] Bradley Monton, "Time Travel Without Causal Loops," *The Philosophical Quarterly*, January 2009, pp. 54–67.

[110] Professor Hanley (note 105) says the answer to such questions is "straightforward": the information comes "from itself." I think the issue is rather deeper than that.

[111] See D. Franson, "Package Deal," in *Microcosmic Tales*, Taplinger 1980. The British philosopher J. R. Lucas had a similar scenario in mind when he wrote, in his book *A Treatise on Time and Space* (Methuen 1973, p. 50), "It is very important, not only for reasons of modesty, that I should not be able to use a Time Machine to go into a public library and read my own biography." Robert Heinlein didn't agree with Lucas: in his 1956 novel *The Door Into Summer* the protagonist, an inventor, travels thirty years into the future, where he reads some patent disclosures for inventions that he doesn't remember, even though they are in his name. He then returns to his own time and promptly files the patents!

[112] M. R. Levin, "Swords' Points," *Analysis*, March 1980, pp. 69–70.

In answer to the question “Who wrote the book about building a time machine?” the philosopher says this question is “no different from questions about where *anything* originally came from. We can ask about the origin of the atoms . . . their time line is not neatly presented to us. The atoms either go back endlessly, or if the Universe is finite, they just start. In either case the question of ultimate origin is as unanswerable as the question of the book’s origin. What makes us think that when such questions are asked about the loop they are different and *ought* to be answerable is that the entire loop is open to inspection.” While the instructions in the book don’t tarnish, the book itself of course brings us back to our previous antique watch ‘problem.’ Suppose the book is brand-new at the start of the trip backward in time. Later, when the machine (and the book) have reached the end of the loop, just before beginning the trip back in time, have the pages turned yellow and brittle? If so, how do we account for the brand-new version? And if not, why not?

An analyst who takes strong exception to these two philosophers is Oxford physicist David Deutsch, who wrote (note 100) “the real problem with closed timelike lines under classical physics is that they could be used to generate knowledge in a way that conflicts with the principles of the philosophy of science, specifically with the evolutionary principle.” What Deutsch is referring to is the metaphysical claim, attributed to the philosopher Karl Popper (see note 36 in Chap. 3), that *knowledge comes into existence only by evolutionary, rational processes* and that solutions to problems do not spring fully formed into the universe. One might call this the physics version of the work ethic—the creation of knowledge demands hard work!

Deutsch’s idea had actually appeared *decades* earlier in a science fiction tale.[113] Time travel, discovered in the year 2007, is found to have a limited temporal reach into the future of 50 years, a limit due a law passed in 2057 banning time travelers from the past. To try to go past 2057 leads to a prompt arrest of the time traveler and a ‘deportation’ trip back to his own time. The story eventually explains that the law was passed precisely because of Deutsch’s concern. As one character in the story explains, “Suppose [that one could travel more than 50 years ahead], then a time traveler from the past could get [new inventions], carry them back to his own time, and give them to scientists—which[would] cancel all the long period of invention which [produced the inventions]. Which [would] violate causal laws.”

More recently, a philosopher has offered a quite interesting response to the Deutsch/Popper assertion. He writes (note 81), of information “appearing out of nowhere,” that “These cases are puzzling, but they by no means show that the time travel scenarios in question are impossible or incoherent, *or even improbable*. We think it very improbable that . . . information should come from nowhere—but only because this does not happen very often. It does happen *sometimes*—for instance, when you say something and I mishear you. I think that you said something very

---

[113] P. Anderson and G. Dickson, “Trespass,” *Fantastic Story Quarterly*, Spring 1950.


Cornered
by Mike Baldwin
12-17 © 2005 Mike Baldwin / Dist. by Universal Press Syndicate www.cornered.com
cornered@comic.com
There it was: the same piece of cake he ate yesterday. His time-machine really worked. Think of the possibilities. He could have his cake and eat it too.

Fig. 4.5 A curious paradox. CORNERED ©2005 Mike Baldwin. Reprinted with permission of UNIVERSAL UCLICK. All rights reserved

profound—something which neither of us would, in fact, ever have thought of. Where does the idea come from? If this sort of thing were to start occurring regularly [as via causal loops], then we would simply accept it without raising an eyebrow."

In the final chapter I'll discuss a dramatic example (due to two Russian physicists) on how an information-creating time loop might be constructed using a wormhole time machine. Such a time loop wouldn't pass muster with Deutsch, of course, and he would consider such a thing as being as objectionable as is creationism, the anti-evolution claim that purports to 'explain' fossils (with measured ages in the millions of years) by simply *declaring* them as having been made by God just a few thousand years ago.[114] Deutsch's position is considered by nearly all scientists today to be correct *for the specific case of creationism*, but the evolutionary principle may be on shakier ground with respect to declaring causal information time loops to be impossible.

While philosophers have struggled with information in a time loop, and most physicists have carefully stepped around the issue, science fiction has had lots of fun with information in causal loops. Here's a sampling of such tales:

(1) A man receives telephone calls from *two* versions of himself, one ten years in the future saying he absolutely must accept an invitation to fly to the Bahamas

---

[114] *Why* would God do such a thing? Apparently 'just to have some fun with geologists and biologists,' as creationists call such ancient fossils 'sports of nature.'

that he will receive that very day, with the other version calling from tomorrow insisting that the plane will crash. What should he do?[115];

(2) Lovers who are irrevocably separated in time communicate by mail in one tale,[116] while lovers in another story[117] communicate via telephone calls to the ever more distant past (and yet, with the aid of a clever twist at the end, finally meet);

(3) A telephone lineman starts getting telephone calls from himself from 10 days in the future, with the first call telling him how to make the gadget to transmit such calls[118];

(4) A time traveling historian on a visit to A.D. 1528 from A.D. 2211 accidently gives a copy of the predictions of Nostrodamus to the prophet, thus explaining the predictions[119];

(5) A time machine experiment gone wrong allows thirteenth century Roger Bacon to meet twentieth century scientists, an encounter that explains the amazing forecasts in Bacon's *Opus Maius*[120];

Hollywood, too, has had some fun with information causal loops, with the best (in my opinion) example of that being the 1989 movie *Bill & Ted's Excellent Adventure*. In that film (where we learn that even the not very bright can be time travelers), a set of missing keys is necessary for the successful completion of a task. The two time travelers decide that after the task is done, they will go back in time, steal the keys (*that's* why they're missing!), and hide them so they can use them *now*. Where should they hide them? Why, "over there," says one of the boys, pointing at a hiding place—and sure enough, when they go over and look, the keys are there. They agree that once they have finished with the keys, it will be *most* important that they really do put the keys in the hiding place!

All of these examples that I've just given you, however, were *decades* too late to be the first in fiction about information in a time loop; that honor goes to the 1904 novel *The Panchronicon* by the lawyer Harold Steele MacKaye (1866–1928). An Edwardian literary time machine with style, the Panchronicon (literally, a 'machine for all time') swings on a rope tether around a steel post erected at the North Pole. By "cutting the meridians" faster than the sun does, it travels through space and time from 1898 New Hampshire to the London of three centuries earlier.[121] Using it, a time traveler fan of Shakespeare journeys from 1898 back to the bard, who is suffering from writer's block. There she whispers the magic lines from a play he is stuck on (lines she has memorized for her literary club meetings) into his receptive ear. Does this make Shakespeare a plagiarist? Of himself!?

---

[115] G. Klein, "Party Line," *The Best from the Rest of the World* (D. A. Wolheim, editor), Doubleday 1976 (story originally published in France in 1973).

[116] J. Finney, "The Love Letter," *The Saturday Evening Post*, August 1959.

[117] T. N. Scortia, "When You Hear the Tone," *Galaxy Science Fiction*, January 1971. See also L. Padgett, "Line to Tomorrow," *Astounding Science Fiction*, November 1945.

[118] M. Leinster, "Sam, This Is You," *Galaxy Science Fiction*, May 1955. This story was later broadcast as an episode on the "X-Minus One" radio drama program. See also F. A. Reeds, "Forever Is Not So Long," *Astounding Science Fiction*, May 1942.

[119] L. Del Rey, "Fools' Errand," *Science Fiction Quarterly*, November 1951.

[120] N. Schachner, "Lost in the Dimensions," *Astounding Stories*, November 1937.

[121] 'Time traveling' by crossing time zones is an idea that one can trace at least as far back as to Edgar Allen Poe's 1841 short story "Three Sundays in a Week."

4.5 Sexual Paradoxes

> "Once time machines exist, no event is low probability if it is needed to make the past consistent."[122]

There are causal loops even stranger than the ones we have already discussed, hard as that may be to believe. These are the sexual paradoxes, first mentioned in 1931 by Nicholson in his letter to Hugo Gernsback. Not only science fiction writers, but philosophers, too, have found these particular paradoxes full of dramatic appeal. For example, as a challenge problem to the readers of a scholarly journal, the British philosopher Jonathan Harrison (1924–2014) posed the following bizarre, indeed astonishing, situation.[123] A young lady, Jocasta Jones, one day finds an ancient deep freezer containing a solidly frozen young man. She thaws him out and learns that his name is Dum, and that he possesses a book that describes how to make both a deep freezer and a time machine. They marry. Soon after they have a baby boy and name him Dee.

Years later, after reading his father's book, Dee makes a time machine. Dee and Dum, taking the book with them, get into the machine and begin a trip into the past. Running out of food during the lengthy journey, Dee kills his father and eats him. Arriving in the past, Dee destroys the time machine, builds a deep freezer (again, using the book), gets into it, and . . . wakes up to find that a young lady, one Jocasta Jones, has thawed him out. When asked his name he replies Dum and shows Jocasta his book; they marry, and . . . .

Harrison concluded this amazing tale with this question for his readers: "Did Jocasta commit a logically possible crime?" That issue is just the *surface* of an ocean of puzzles in this story! Jocasta's crime, of course, is that she has (if unwittingly) committed incest; readers who remember the Greek myth of Oedipus, and who his mother/wife was, will understand why Harrison named his female character as he did. But what of Dee's crime? He has, after all, eaten his father! But perhaps that isn't a crime at all, because Dee and Dum are one in the same, and is it really a crime to eat yourself? According to another philosopher, Murray MacBeath, Harrison's story is "a story so extravagant in its implications that it will be regarded as an effective *reductio ad absurdum* of the one dubious assumption on which the story rests: the possibility of time travel."[124]

---

[122] From Robert Forward's 1992 novel *Timemaster*.

[123] J. Harrison, "Jocasta's Crime," *Analysis*, March 1979, p. 65.

[124] M. MacBeath, "Who Was Dr. Who's Father?" *Synthese*, June 1982, pp. 397–430.

This isn't to say that MacBeath was asserting that time travel is impossible. Indeed, he went on to declare that he did believe in the logical possibility of time travel, and his paper is devoted to discovering what thought to be incorrect in Harrison's story. He did that by retelling the story with what he believed are crucial modifications to make it sufficiently less outrageous that it could be taken at least somewhat seriously. In the new version, our hero, thawed out from a deep freezer, is now named Arthur. Arthur is, unfortunately, suffering from total amnesia (this is MacBeath's way of avoiding the psychological trauma of Dee remembering he ate Dum) and so, when asked his full name, he is himself sufficiently puzzled that he replies "Arthur who?" He is finally called (what else?) Arthur Who. And, as you can no doubt guess, his son (who is a genius and gets a PhD at age 14 on a dissertation dealing with the physics of time travel) becomes Dr. Who!

We are then told of a trip back into the past by the two, of the eating of the father (Arthur Who) by the son, of the entering of the deep freezer by Dr. Who, etc. etc. The whole business is quite entertaining and *at least* as complex as Harrison's original story. Just *how* complex is summed up in MacBeath's last, wonderful line: "The Who who was Dr. Who's father was not Dr. Who—that is, not the Dr. Who whose father he was."

MacBeath wasn't the only one that Harrison's story fascinated, and nearly a dozen replies to it were received in addition to MacBeath's. One, in particular, made the thought-provoking observation (see note 112) that not only has Jocasta committed incest but she has done so with a single act of intercourse. As discussed earlier, the events on a causal loop do not happen endlessly but rather only once; thus, Jocasta thaws Dum (Dee) out just once, she marries him just once, and the two consummate their marriage just once. Ordinarily we think it takes two sexual acts to commit incest, the first resulting in the birth of a child, and the second being a parent's union with that child, but this is not so in a causal loop. Time travel *is* an odd business.

Another philosopher replied to Harrison's story with a quite interesting claim, one that had actually been thought to be true for decades—but which today is recognized to be false. The claim was that, irrespective of physics, Harrison's story was biologically flawed and fatally so. As that philosopher wrote, "The biological problem is the following. Dee is the son of Dum and Jocasta. So Dee obtained half his genes from Dum and half from Jocasta. But Dum is diachronically identical with Dee and is therefore genotypically identical with him (that is, himself). That is, Dee is both genotypically identical and distinct from Dum, which is absurd."[125]

That this isn't true was pointed out by a philosopher many years later. In his paper we read this tale: "Suppose Adam travels [far] back in time … where he meets his mother Betty, mates with her and has a child which is himself. Is this possible biologically? Yes … as follows … on the grounds that we have total replication of Adam's genome."[126] (The *genome* is the totality of genes taken over all gene sites.) Now, suppose each such site holds two genes and, as Dowe points out, in sexual reproduction the father passes on to his offspring one gene for each gene site, to go with the gene the mother gives to each site. To exactly reproduce himself, then, the time traveling Adam 'simply' has to give his offspring, *at each site*, the gene that he has for that site that did *not* come from Betty. Thus, the offspring—baby Adam—ends up with a genome *precisely identical* to the time traveling Adam. This is, of course, an *extraordinarily unlikely* event, as the human genome has tens of thousands of genes. The probability that each and every site gets the 'right' gene from the time traveling Adam is therefore essentially zero. But it isn't *actually* zero and, as the quotation that opens this section says, a low probability to an event isn't a roadblock to its occurrence if that event is required for consistency.

---

[125] W. Godfrey-Smith, "Traveling in Time," *Analysis*, March 1980, pp. 72–73. This false claim had already been raised by a physicist (L. S. Schulman, "Tachyon Paradoxes," *American Journal of Physics*, May 1971, pp. 481–484), and even earlier by a science fiction writer (P. Anderson, "Time Patrol," *Magazine of Fantasy and Science Fiction*, May 1955).

While certainly instructive, the sexual paradox stories by Harrison and MacBeath are remiss in not indicating that the concepts they are dealing with have long been a staple of science fiction, and that the sexual paradoxes received much critical analysis in that genre long before philosophers (and physicists, too) discovered them. From science fiction, for example, we have a tale of young man who travels backward in time 1250 years, from A.D. 3207 to 1957, to become his own grandfather fifty generations removed.[127] And even that is tame compared to the sexual paradoxes other science fiction writers conjured up before philosophers began to discuss them.

In another story,[128] written decades before Harrison's and MacBeath's papers, we meet a young lady caught up in a mind twisting affair in which the mystery of a causal loop is the least of her troubles. In 1957 a girl is born, and after 20 years of intense competition with her mother (who has an uncanny ability to predict the future), she travels back from 1977 to a few months before her own birth. She becomes pregnant (by a man who she later discovers is her father) and gives birth to a girl. The new mother has, of course, knowledge of all that will happen during the next 20 years, including the fact that she will have an intense competition with her rebellious daughter … .

While writers of stories like these in the early 1950s were there as trailblazers, it is a tale that appeared as the 1950s ended that is today generally acknowledged as the best sexual paradox story ever written.[129] We are given only a hint of what is to come when a character listens to a song called "I'm My Own Grandpaw!" In 1945, a newborn girl, Jane, is found on the steps of an orphanage. At age 18, in 1963, she has a one-night affair with a mysterious stranger that leaves her pregnant. Some months later, during the birth of a daughter, it is discovered that Jane actually has a double set of sexual organs, and because the female set has been ruined by the pregnancy, doctors restore her as a man. Soon after, the baby girl mysteriously disappears from the hospital ward. Years later, in 1970, Jane (now a man, of course) meets another stranger who uses a time machine to transport both of them back to April 3, 1963. By April 24 male-Jane meets female-Jane and impregnates her (and so now we know who the mysterious stranger was during the one-night affair!). Meanwhile, the stranger with the time machine travels forward to March 10, 1964, a little after female-Jane has given birth, kidnaps the baby from the hospital (thus clearing-up another mystery!), takes her back to September 20, 1945, and leaves her on the steps of the orphanage. And so we see that Jane is her own mother *and father*, thus out-doing all previous tales about self-parenting.

---

[126] Phil Dowe, "The Coincidences of Time Travel," *Philosophy of Science*, July 2003, pp. 574–589. See also J. Berkovich, "On Chance in Causal Loops," *Mind*, January 2001, pp. 1–23, and P. Dowe, "Causal Loops and Independence of Causal Facts," *Philosophy of Science*, September 2001, pp. 89–97.

[127] R. Dee (this is *not* the 'Dee' of Harrison's story!), "The Poundstone Paradox," *Magazine of Fantasy and Science Fiction*, May 1954.

[128] C. L. Harness, "Child By Chronos," *Magazine of Fantasy and Science Fiction*, June 1953.

[129] R. Heinlein, "All You Zombies—," *Magazine of Fantasy and Science Fiction*, March 1959.

This is pretty impressive stuff, but Heinlein still has one more twist for us. After leaving baby-Jane in 1945, the time machine stranger returns to April 24, 1963, retrieves male-Jane (who has just kissed female-Jane goodnight after fathering her-himself in herself), and takes him to 1985 where he recruits him into the Temporal Service—and finally, the stranger jumps forward to 1999, his 'real time.' At the end we at last learn that the stranger is, in fact, an even older version of male-Jane—*all* the central characters in the entire story are the *same* individual at various points along a single, highly twisted world line. The lone character in Heinlein's tale is truly a self-made man/woman in every sense of the phrase! This ultimate act of *creatio ex nihilo* has, correctly I think, been called "smaller than the minimal loop."[130]

Jane, in all her/his versions, is the only character in the story that appears to have purpose. In terrifying words that describe a causal loop, Heinlein ends the tale with an explanation of the story's title: "The Snake That Eats Its Own Tail, Forever and Ever. I know where I came from—but where did all you zombies come from? . . . You aren't really there at all. There isn't anybody but me—Jane—here alone in the dark. I miss you dreadfully!" In a December 1958 letter to his literary agent, Heinlein wrote of this amazing tale, "I *hope* that I have written in that story the Farthest South in time paradoxes." In my opinion, he did.

The sexual paradox has continued to fascinate science fiction writers up to the present day. In the novel *Timemaster* (note 122), for example, the hero at one point spends a night with his wife—and with two versions of himself from the future. He will, of course, experience that night two more times! Later, he becomes upset when his wife runs off with one of the older versions, but he quickly calms down when he considers that eventually *he* will be the older version. Consider, too, a story[131] that tells of a young man hunting the father who, years before, had abandoned him in a burning house. The death of the young man's mother in the flames has sent him on a 10 year quest for revenge up and down what is literally a river of time, a river on which to travel in one direction ("up time") is to move into the past, whereas moving "down time" leads to the future. Eventually he corners the father and, despite the man's pleading, kills him. It is only later, after examining papers he finds in his father's pocket, that the young man realizes he has killed his *future* self (Benford, a physicist, knows the pitfalls of time travel, and you'll notice that there is no autoinfanticide paradox here).

---

[130] S. Lem, "The Time-Travel Story and Related Matters of SF Structuring," *Science Fiction Studies*, Spring 1974, pp. 143–154.

[131] G. Benford, "Down the River Road," *After the King: Stories in Honor of J. R. Tolkien* (C. Tolkien and M. Greenberg, editors), Tor 1991.

4.6 Splitting Universes and Time Travel

> "In all time travel stories where someone enters the past the past is necessarily altered. The only way the logical contradictions created by such a premise can be resolved is by positing a Universe that splits into separate branches the instant the past is entered."[132]

One early science fiction technique for allowing backward time travel and a changeable past, while still avoiding paradoxes, is that of alternate universes. According to this idea, if a time traveler journeys into the past and introduces a change (indeed, his very journey may be the change) then, as the above quote states, reality splits into two versions, with one fork representing the result of the change and the other fork being the original reality before the change. (To a fifth-dimensional observer, of course, all conceivable forks, all possible four-dimensional spacetimes, have always existed.) Indeed, according to this view the entire universe is splitting, at every microinstant, along every alternative decision path for every particle in the cosmos! This is often called the theory of *alternate realities with parallel time tracks*.

Such a seemingly fantastic view seems to actually have some scientific plausibility because of the so-called *many-worlds interpretation* (MWI) of quantum mechanics, pioneered in physics by Hugh Everett III (1930–1982), in a 1957 Princeton doctoral dissertation. Everett's theory is the antithesis of what is commonly called the *collapse of the wave function*, the idea that all potential possibilities have a non-zero possibility until a consciousness actually decides or observes which one will actually *be*. That quantum mechanical concept gets its name from the probabilistic wave equation formulated in 1926 by the German physicist Erwin Schrödinger (1887–1961). Before the observation, all possible futures have various values of probability; after the observation (which 'collapses' the wave function) exactly *one* of those futures (*the* future) has probability 1 and all the others have probability 0.

The MWI idea can be seen in Hale's story "Hands Off," discussed earlier, and in art *40 years* before that! With almost certainly a theological twist, consider the

---

[132] M. Gardner, "Mathematical Games," *Scientific American*, March 1979.



Fig. 4.6 Grandville's Infinity Juggler of many-worlds

beautiful illustration in the 1844 book *Un Autre Monde* (*Another World*), reproduced in Fig. 4.6. Known either as "The Infinity Juggler" or "The Juggler of Worlds," it is the work of the French artist Jean-Ignace Isidore Gérard (1803–1847), who published under the name 'Grandville.' The juggler—Grandville's version of Hale's mentor—appears as a court jester who is clearly having fun manipulating his multitude of worlds, while the man (humanity?) in the foreground watches. The man appears to be simultaneously fearful and fascinated, involved yet clearly impotent. Is Earth one of the worlds among which the Jester stands, or is it one of those flying through space? Or is Earth, perhaps, simply the unfortunate world ingloriously stuffed down the front of the Jester's pants? (That would surely explain a lot!) If born a hundred years later, Grandville would surely have found work as an artist in the imaginative world of the science fiction pulps.

Early science fiction stories that treat the collapsing wave function concept can be traced back to the late 1930s and early 1940s.[133] A particularly interesting example is the story of an inventor who, while trying to build a radio with which to signal Mars, accidently stumbles on the "temporal-aberrant carrier wave" and thus establishes contact with a universe that forked off of ours in 1863 when Robert E. Lee *won* the Battle of Gettysburg![134] In Everett's MWI, however, the wave function of the universe does *not* collapse. Indeed, it *couldn't*, because there is no observer external to the entire universe (we are talking science now, not of theology and God); instead, the wave function 'splits' at every decision point in spacetime. Although this leads to a multitude of realities *far* beyond comprehension, cosmologists still tend to like the MWI because it avoids the puzzle of having to produce an observer 'outside the universe.'

---

[133] See, for example, Jack Williamson's 1938 novel *The Legion of Time*, and C. L. Moore's, "Tryst in Time," *Astounding Stories*, December 1936. L. Sprague de Camp (1907–2000), too, was an early pioneer in the exploration of the MWI idea in science fiction long *before* Everett. In his 1941 novel *Lest Darkness Fall*, for example, he uses the analogy of a tree (the "main time line") that is always sprouting new branches.

It's important to understand that the MWI is different from yet another idea popular in science fiction, that of *parallel universes* (see again the third discussion question at the end of Chap. 3). In parallel universes *all* possibilities *always* exist, independent and parallel in time. In the MWI, on the other hand, ever more universes are continually coming into existence. Unlike the MWI, which can at least claim a scientific basis (quantum mechanics), there is no analogous theory for parallel universes. But, of course, even though lacking a theory, nonetheless science fiction writers have been quite inventive with the idea because parallel universes offer a way to avoid (at least some) causal loops.

One clever, early pulp story[135] illustrates how that works. To improve the performance of his time machine, an inventor needs batteries with tremendous energy density, a density far in advance of the batteries in the present. Unable to travel far into the future—if he *could* obtain them there, then of course a causal loop (the very entity we wish to avoid) would be created upon his bringing them back to the present—his assistant first travels back to 1851. There he leaves a note on desk of a well-known experimenter, with a plea for him to devote his life to battery research; a copy of the 1937 *Electrical Handbook* is left with the note as proof that there really has been a visit from the future! Before returning to the present, the assistant takes a sheet of (new) 1847 five-cent stamps from the experimenter's desk.

Returning to the present, which is now different (a new time track, in accordance with the splitting-universe idea), the powerful batteries *are* readily available *because* the experimenter believed the note. Buying several of them, using money obtained by selling the pristine 1847 stamps to a collector, the assistant returns to a slightly earlier 1851 than before (to *before* the fork in time!), watches himself appear[136] and leave the note and the handbook, and *then, unobserved, the assistant removes both*: Thus, upon returning once more to the present, he finds all is as before—except now he and the inventor have the powerful batteries. As before, one might ask where the batteries came from, but unlike the previous mystery of information-creating causal loops, the answer is clear and non-mysterious. *They came from the hard work of the experimenter on a different time track.* Such shuttling back-and-forth between time tracks is the signature of what is called a *cross-time* story, a device to avoid paradoxes while still allowing for changing the past. The first example of this time travel sub-genre had actually appeared 4 years earlier.[137]

---

[134] N. Bond, "Parallel in Time," *Thrilling Wonder Stories*, June 1940. See also S. N. Faber, "Trans Dimensional Imports," *Isaac Asimov's Science Fiction Magazine*, August 1980.

[135] W. Sell, "Other Tracks," *Astounding Science Fiction*, October 1938.

[136] Just like Marty McFly does at the end of the 1985 film *Back to the Future*. The movie is fun, but pulp science fiction did it first.

In another cross-time tale from modern times, we read of the horrible fate suffered by a man when an experiment in a Princeton physics lab goes wrong.[138] It is discovered, too late, that parallel time tracks are not simply grooves into which you drop, like a ball, after leaving the time track of our world. Each version of a person in each world is not like a ball rolling down a groove from past to future. Rather, each world's time track is just a line on a smooth surface; as the man is told, during a temporary stay in a world still close to his (our) original world, "We gave you a push sideways, and you moved off your original line—but instead of dropping into the next groove, you've just kept on rolling across the surface, from one line to the next, at an angle. There are no grooves, nothing to stop you from sliding on across the different lines forever. You have the same futureward vector as you started with, but you've added a small cross-time vector, as well." And so the man drifts cross-time, and gradually the worlds he experiences grow ever more alien.[139]

The science fiction is undeniably fun, but for this book the underlying *scientific* theory of time travel is classical (that is, non-quantum) general relativity, and that theory has nothing to say about alternative time tracks in multiple worlds. For most time travel theoreticians there is *one* time track, and the past of our world is unique and inviolate. I agree with the great quantum physicist J. S. Bell (1928–1990), who wrote of Everett's theory that "if such a theory were taken seriously it would hardly be possible to take anything else seriously."[140] As Bell further observed, in the MWI "there is no association of the particular present with any particular past," a quite strange idea that had already appeared in science fiction years earlier.[141]

While most early time travel analysts did base their work just on classical general relativity, there *are* now many more who think quantum mechanics itself, independent of its interpretation, has much to contribute as well. Perhaps, in fact, it may make an absolutely crucial contribution to the theoretical basis of time travel. One analyst who believes this (along with an even stronger belief in the MWI) is the British physicist David Deustch (note 100), who holds that general relativity is not the proper theory with which to study the physical effects of CTLs. He believes that the traditional mathematical machinery of general relativity actually obscures, rather than clarifies, the difficult task of separating the merely counter-intuitive from the unphysical.

---

[137] M. Leinster, "Sidewise in Time," *Astounding Stories*, June 1934. Splitting universes with multiple time tracks and time loops became quite popular after Leinster's and Sell's stories; you can find the basic idea repeated yet again in Alfred Bester's "The Probable Man," *Astounding Science Fiction*, July 1941, for example, in which each new journey into the past causes the future to fan out into an infinity of new time tracks.

[138] L. Watt-Evans, "The Drifter," *Amazing Stories*, October 1991.

[139] In Jack Haldeman's 1990 novel *The Hemingway Hoax* we read that "there is not just one [parallel] universe, but actually uncountable zillions of them."

[140] In "Quantum Mechanics for Cosmologists," *Speakable and Unspeakable in Quantum Mechanics*, Cambridge University Press 1987.

[141] J. R. Pierce, "Mr. Kinkaid's Pasts," *Magazine of Fantasy & Science Fiction*, August 1953.

Indeed, Deutsch calls the conventional spacetime methods, based on general relativity and differential geometry, *perverse*. He also does not like the conceptual problems raised by general relativity's wormholes and singularities. Any non-quantum mechanical discussion, he says, of the "pathologies" of backward time travel is simply not adequate. Deutsch divides these pathologies into two fundamental classes: (1) paradoxical constraints, such as the free-will issue seemingly raised by the grandfather paradox, and (2) causal information loops. Deutsch claims that his quantum mechanical analyses show that the first class of pathologies simply does not occur, because the past that the time traveler enters is the past of a world different from the one he has left. Further, his results also show (to him) that the pathologies of the second class may be "avoidable." These are not the views among the majority of time travel students, however (that does *not* mean Deutsch is wrong!), and general relativity *is* the standard tool used by the majority of time travel theoreticians. When quantum mechanics does enter the calculations of most analysts, it is generally on an *ad hoc* basis.

More concerning for the MWI view is a result reported in 2004, that a macroscopic object (a human time traveler, for example) attempting to traverse a wormhole time machine (to be discussed in some detail in Chap. 6) "must necessarily undergo violent interactions with the time machine," interactions *so* violent that they must "cause the object to disintegrate." The different pieces of the now certainly dead time traveler would emerge from the wormhole in different worlds—this is definitely not a result likely to encourage volunteers for the first time machine trip![142]

So, many physicists and philosophers, not sharing Deutsch's position,[143] tend to agree with Bell, including the late John Wheeler (Everett's thesis advisor!), who wrote of the MWI "I once subscribed to it. In retrospect, however, it looks like the wrong track. … Its infinitely many unobservable worlds make a heavy load of metaphysical baggage."[144] Agreeing with Wheeler was a philosopher who called the MWI "highly controversial" and declared that "few working physicists take it seriously."[145] Perhaps even more damning was a physicist's statement that "the idea of 10^{100}+ slightly imperfect copies of (the universe) all constantly splitting into further copies . . . is not easy to reconcile with commonsense. Here is schizophrenia with a vengeance."[146] Or, as one science fiction writer bluntly put it, in a tale of the inventor of the "chronomotive impulse belt" (which allows moving between the *two* parallel worlds that are all that exist), the MWI is the "Doctrine of Infinite Redundancy—which is, of course, utter nonsense."[147]

---

[142] A. Everett, "Time Travel Paradoxes, Path Integrals, and the Many Worlds Interpretation of Quantum Mechanics," *Physical Review D*, June 25, 2004, pp. 124023–1:124023–14.

[143] For a modern philosophical argument specifically rebutting Deutsch's enthusiasm for the MWI, see Theodore Sider, "A New Grandfather Paradox?" *Philosophy and Phenomenological Research*, March 1997, pp. 139–144.

[144] See note 34 in Chap. 3.

Deutsch's position does raise the obvious question of what motivates a quantum theoretician to study CTLs at all, given that they originate in general relativity and *not* in quantum mechanics. Deutsch's response is that although CTLs did indeed originate in classical Einsteinian general relativity, the still incomplete theory of quantum gravity *does* predict CTLs, too. And that is an exciting observation for time travel enthusiasts because, as Deutsch writes, the results of his quantum studies of CTLs show that "contrary to what has usually been assumed, there is no reason in what we know of fundamental physics why closed timelike lines should not exist." That view was later endorsed by other physicists who wrote, after a quantum mechanical study of how a particle could transit a time machine spacetime in a physically consistent manner, "there is no contradiction between the postulates of quantum mechanics and the possible existence of causality violation in general relativity."[148]

Long before these scientific endorsements, science fiction had enthusiastically embraced the many-worlds idea and its connection with time travel. The first such tale[149] appeared when Everett was just 3 years old; it put forth the insightful observation that although alternate time tracks may allow changing the past for the better (something that can't be done, for better *or* for worse, with a single time track), in the end any such change may still be futile. As Daniels' time traveler puts it, "I did have an idea to . . . go back to make past ages more livable. Terrible things have happened in history, you know. But it isn't any use. Think, for instance, of the martyrs and the things they suffered. I could go back and save them those wrongs. And yet all the time . . . they would still have known their unhappiness and their agony, because in this world-line those things happened. At the end, it's all unchangeable; it merely unrolls before us."[150] Many years later, in a critique of the many-worlds idea, a philosopher/physicist echoed Daniels' words: [In the world] that I (subjectively) experience I may blunder, but [in another world], with equal actuality, I triumph gloriously. The Everett interpretation can be used this way to mitigate sorrows, but this use is two-edged, for it equally well implies the speciousness of happiness."[151]

---

[145] R. A. Healy, "How Many Worlds?" *Nous*, November 1984, pp. 591–616.

[146] B. S. DeWitt, "Quantum Mechanics and Reality,' in *The Many-Worlds Interpretation of Quantum Mechanics* (B. S. DeWitt and N. Graham, editors), Princeton 1973.

[147] B. Shaw, "What Time Do You Call This?" *Amazing Science Fiction*, September 1971. When a bank robber in one world tries to make his escape into the other world, he literally runs into 'himself' trying to escape after robbing the 'same' bank in the parallel world!

[148] D. S. Goldwirth *et al.*, "Quantum Propagator for a Nonrelativistic Particle in the Vicinity of a Time Machine," *Physical Review D*, April 15, 1994, pp. 3951–3957. See, too, the earlier D. S. Goldwirth *et al.*, "The Breakdown of Quantum Mechanics in the Presence of Time Machines," *General Relativity and Gravitation*, January 1993, pp. 7–13.

[149] D. R. Daniels, "The Branches of Time," *Wonder Stories*, August 1935.

The editorial introduction to Daniels' pioneering tale is quite interesting: the opening line is "To say that this short story contains some revolutionary time-travel theories would be putting it exceedingly mild." That editor then went on to tell his readers, with great enthusiasm, that "when the author . . . submitted this story to us, his accompanying letter stated that in it he had settled the time-travel question once and for all. We must admit that a broad, unbelieving grin spread over our countenances when the author dared make this assertion. BUT—the smile soon left our faces . . . [T]o our chagrin, Mr. Daniels had really propounded so many brand new ideas about time and time-travel, and such logical ones—*that he has not left one loophole in his argument*!"

John W. Campbell (1910–1971), the first (and only) editor of *Astounding Science Fiction* (today's *Analog*), called alternate time track stories "mutant" because they represented the first new innovation (or mutation) in the time travel concept since H. G. Wells. Campbell incorrectly claimed *The Legion of Time* (note 133) was the first such tale (see Campbell's editorial in the May 1938 issue of *Astounding*) , and that "Other Tracks" (note 135) was the second, but in fact it was Daniels who was first with splitting time tracks in science fiction. After Daniels the concept quickly became part of standard science fiction lore and could be used by other writers with little explanation. For example, just a little more than a decade later one author did not have to say much about his "First Law of Chronistics," which determines the development of "the branches of Fan-Shaped time." It was sufficient for his readers to learn that should a time traveler to the past change anything, a parallel branch of time would be created on which the time traveler would be trapped: "The man who interfered with the space-time matrix, displacing even a comma in the great scroll of time, would be cut-off from his origin forever."[152]

Still, if there is one thing we can say about science fiction, it's that no 'rule' is immune to challenge. Decades after Daniels' tale put forth the MWI, we find the well-known author James Blish (note 100 in Chap. 1) *rejecting* it. In a story about the reception of radio signals from the future, we read of one character telling another "I *was* going to do all those things. There were no alternatives, no fanciful 'branches in time,' no decision-points that might be altered to make the future change. My future, like yours … and everybody else's, was fixed. It didn't matter a snap whether or not I had a decent motive for what I was going to do; I was going to do it anyhow. Cause and effect … just don't exist. One event follows another because events are just as indestructible in space-time as matter and energy are."[153]

---

[150] These sad, resigned words were written when the author, David R. Daniels (1915–1936), was just twenty years old. A year later he committed suicide.

[151] A. Shimony, "Events and Processes in the Quantum World," *Quantum Concepts in Space and Time* (R. Penrose and C. J. Isham, editors), Oxford University Press 1986.

[152] J. MacCreigh, "A Hitch in Time," *Thrilling Wonder Stories*, June 1947.

This denial of the MWI is simply an author's choice, of course, for whatever story effect is desired, and others may make different choices. Isaac Asimov, for example, used the MWI idea in in the story of a time traveler who journeys back to 1871 London, to retrieve a lost Gilbert and Sullivan operetta (*Thespis*). When he returns to the present he finds that his wife Mary (who was alive when he left) has been dead for a year on the new time track that his actions in the past have created. As the story ends, the devastated time traveler thinks "I had changed history. I could never go back. I had gained *Thespis*. I had lost Mary."[154] This sad fate is repeated in another story of a time traveler lost in an infinitude of time tracks with no hope of ever finding his way home: "In all of time, how many, many worlds there must be. How to find a single twig in such a forest?"[155]

Splitting universes have been used in literary works outside the genre of science fiction, as well. Examples include "The Garden of Forking Paths" by the Argentine writer J. L. Borges, the first play J. B. Priestly wrote (the 1932 *Dangerous Corner*), John Updike's 1997 novel *Toward the End of Time*, and Gore Vidal's 1998 novel *The Smithsonian Institution*. Typical of these fictional fantasies about splitting universes is a tale (anticipating Asimov's) by Lord Dunsany (1876–1957)—the Irish writer Edward Plunkett—the story of a man who goes back in time to correct "two or three mistakes he had made in his life."[156] This he successfully does, but the result is a new, subtly different subsequent history. The differences are not infinitely subtle, however; after the changes, he finds that his home, his wife, and all the delicate details of his life have vanished. As he relates to a visitor at the lunatic asylum he is now confined to, as the result of his despair, "I tell you I'm lost. Can't you realize that I'm lost in time? I tell you that you can find your way traveling the length of Orion, sooner than you shall find it among the years … Don't go back down the years trying to alter anything … Don't even wish to … [T]he whole length of the Milky Way is more easily traveled than time, amongst whose terrible ages I am lost."

In writing for a mass audience, rather than just for the more limited science fiction and fantasy one, perhaps the best known literary work of alternate history is the classic 1953 novel *Bring the Jubilee* by Ward Moore (1903–1978). In that work Lee wins the Battle of Gettysburg, and the South wins the Civil War. Using a time machine, a historian travels from 1952 (of the world in which the South wins) into the past of 1863 to study the battle, where he inadvertently disrupts events to the point that the North wins; that is, reality splits and the newly created fork represents the time track of *our* world. The historian is trapped on this new fork, cut off forever from his original time track. The entire novel is in the form of a discovered manuscript, written in 1873 and found in 1953, and the pathos of the ultimate isolation endows the novel with great emotional impact.

---

[153] J. Blish, "Beep," *Galaxy Science Fiction*, February 1954.

[154] I. Asimov, "Fair Exchange?" *Asimov's Science Fiction Adventure Magazine*, Fall 1978.

[155] M. F. Flynn, "The Forest of Time," *Analog Science Fiction*, June 1987.

[156] Lord Dunsany, "Lost," *The Fourth Book of Jorkens*, Arkham House 1948.

A 1992 novel on the same theme, Harry Turtledove's *The Guns of the South*, begins with a fascinating premise but then misses the crucial distinction between a single versus multiple time tracks. In that work racists from the future (2014) arrive by time machine at Lee's 1864 winter camp. They bring with them AK-47 automatic assault rifles and offer to supply Lee's army with all it can use. Lee accepts and the South wins the Civil War. The future, of course, changes—or does it? The time travelers have brought back books from the future showing that the South lost the war, so the implication is that history must have forked. So far, so good. But all through the novel, the time travelers move back and forth between the nineteenth and the twenty-first centuries, apparently finding their own time unchanged. And if that is so, then the whole point of the story vanishes. Why all the effort to change history when it is clear that nothing has changed? The novel is entertaining reading (Turtledove is a trained historian), but I believe Moore's novel to be the superior work of science fiction.

I'll end this discussion on splitting universes with a startling theological issue raised by a philosopher.[157] Arguing that God cannot branch into multiple time tracks because God is unique, the conclusion seems inescapable that God therefore exists on exactly one of how ever many different time tracks there may be. What if that chosen time track isn't ours? Then, concludes the philosopher, Nietzsche's nineteenth-century metaphorical claim that "God is dead" (for us) might literally be true! He admits that this is "fanciful," but still . . . .

4.7 For Further Discussion

In an afterword to his story "Dead City" (*Thrilling Wonder Stories*, Summer 1946), Murray Leinster muses "You've heard the old argument that a man can't travel backward in time because he might kill his grandfather. I've wondered why nobody has argued that a man can't travel forward in time because he might be killed by his grandson." One possible answer to Leinster is that *if*, at the moment the forward-bound time traveler departs, he has not yet sired a child, *then* there simply wouldn't be a murderous grandson waiting for him in the future. Perhaps, however, Leinster had this somewhat more

(continued)

---

[157] Q. Smith, "A New Topology of Temporal and Atemporal Permanence," *Nous*, June 1989, pp. 307–330.

complicated scenario in mind: After the time traveler arrives in the future he is attacked by a mysterious stranger but survives, and later returns to the present. He then sires a child who will be the parent of that mysterious stranger. (As far as I know, this plot line has not appeared in a science fiction story.) Contrary to Leinster's view, explain why the *possibility* of being killed by a grandson is not a reason for forbidding the possibility of a trip in time (in either direction).

In his causal loop paper (note 105) the University of Delaware philosopher Richard Hanley correctly writes (on p. 146) "physicists have tried to avoid free will problems by ignoring causal loops involving intentional agency," and partly illustrates this claim with the autoinfanticide paradox, writing of the attempt of a time traveler to kill his younger self as inevitably failing because "the past is apparently brought about willy-nilly." (Hanley unfortunately then uses the story "Thompson's Time Traveling Theory" as an example of this—see note 77, and the end of the "Introduction"—when it is that time traveler's *grandfather* who is the intended target.) Discuss the merits of Hanley's claim, keeping in mind the end of Sect. 4.3 (in particular, note 81). If you are interested in genetics and astronomy as well as in time travel, then for extra credit comment on Hanley's claim (p. 137) that "one can extract information about my DNA from … my astrological chart."

The fictional killing of Hitler was imagined in print even before World War II, in Geoffrey Household's intense 1939 novel *Rogue Male* (made into the 1941 film *Man Hunt*). And so it's not surprising that one of the popular change-the-past themes in science fiction is that of a time traveler killing the Führer. (This idea, somewhat oddly, appeared in the debates leading up to the 2016 American Presidential election, when one of the candidates, to show the toughness of his character—even though he opposed abortion—declared "Hell, yes, I'd kill baby Hitler! You gotta step up, man." This candidate did elaborate a bit, stating there might be some risk involved with tampering with the past.) Stories in this sub-genre include E. Norden's "The Primal Solution" (*Magazine of Fantasy & Science Fiction*, July 1977), W. R. Thompson's "The Plot to Save Hitler" (*Analog*, September 1993), L. del Rey's "My Name Is Legion" (*Astounding Science Fiction*, June 1942), and R. M. Farley's "I

(continued)

Killed Hitler" (*Weird Tales*, July 1941). Read some of these tales and compare the various repercussions envisioned by the authors following an assassination of Hitler by a time traveler.

After our discussion of Heinlein's time travel masterpiece "All You Zombies—," you might think it impossible to write a new story that exceeds it in complexity. That might well be true, but a modern masterpiece by Ted Chiang certainly gives it a good run for the money. "The Merchant and the Alchemist's Gate" (*Magazine of Fantasy & Science Fiction*, September 2007) uses a 'wormhole' that connects the present to the future 20 years hence, and it is stuffed with intertwined causal loops and information bootstraps. Read it and keep track of all such occurrences. How many did you find? The last line of the story clearly expresses the view that the past cannot be changed: "Nothing erases the past. There is repentance, there is atonement, and there is forgiveness. That is all, but that is enough." Is the story always faithful to this view of time travel?

In his paper (note 126) on the coincidences of time travel, the University of Queensland philosopher Phil Dowe writes "It's true that remote time travel [into the very distant past] does not allow for causal loops . . ." *Is* this true? Consider, as you think about this, the story "Time's Arrow" (*Science-Fantasy*, Summer 1950) by Arthur C. Clarke. In that tale geologists have just discovered, in a remote desert, the fossilized tracks of a monstrous creature, from fifty million years ago, tracks that indicate that the beast was in hot pursuit of fleeing prey. Before the geologists can unearth the entire set of tracks, to see if the pursuit was successfully completed, they are visited by a physicist who just happens to be conducting near-by experiments in time travel. (This proximity is explained by noting what better place to conduct time travel experiments, powered by atomic energy, than in a remote desert?) At one point during the visit, after being told of the ancient pursuit frozen in rock, the physicist muses "It would save you a lot of trouble, wouldn't it, if you could actually *see* what took place in the past, without having to infer it by these laborious and uncertain [geological] methods." This comment results in the Chief geologist paying a visit to the physicist's lab. After driving over in a car equipped with tires having "an odd zigzag pattern" in the tread,

(continued)

an accident suddenly sends the entire lab into the past. Soon after, the other geologists unearth the rest of the fossilized tracks, and learn what the creature's prey had been when they see a zigzag pattern in the rocks, tracks that show "the great reptile was about to make the final leap upon its desperately fleeing prey." Can you see how to modify this story so as to have a causal loop involving the very distant past? (For perhaps even more inspiration on thinking about causal loops, watch the 1980 movie *The Final Countdown*. In it the designer of a modern naval warship that temporarily travels back through time to the Pearl Harbor of December 6, 1941, turns out to be a crew member who was accidently left behind in the past. In the past he *will be* able to design the ship because he already knows how it *was* designed—by himself!)

Comment, at length, on the cartoon shown in Fig. 4.5. (Does it make logical sense?)

In the story "Salvation" by Jerry Oltion (*Analog*, December 2007) a physicist approaches the Universal Church of the Divine Revelation for money to build a time machine. He is blunt in making his case: "You could go back in time and meet Jesus. Assuming he existed." That statement causes (it should come as no surprise) not just a bit of pandemonium but, nonetheless, an influential Church leader decides to provide the funding. Why? Because later, while sitting in his office as he talks with the physicist, a sheet of paper suddenly appears in the air above the leader's desk and then flutters down to land on the telephone. Picking the paper up, the leader sees it is a sheet of his own letterhead, with writing in his own angular, precise handwriting, saying "It works. Give him the money. You almost named the dog Solomon." This convinces the leader because, as we are told, "Paper appearing out of nowhere was a good trick, but it might easily be just that: a trick. Duplicating his letterhead and his handwriting wouldn't be all that difficult either. [On the other hand] knowing the name [the leader] had considered but rejected for his German Shepard 15 years ago was a different level of feat entirely." The physicist seems to be startled by the appearance of the paper, too, and asks "May I see that?" His reaction convinces the leader it wasn't a staged event: "Well, I'll be damned," the physicist replies. Once the time machine is under construction, the two men realize they have to send the enigmatic message back in time to complete the loop. As they prepare to do so, the leader asks a curious question. After retrieving the mysterious sheet of paper from his desk,

(continued)

he says to the physicist "Should I send the original [the one he is holding in his hand], or should I write another?" The physicist replies with "Write a new one. If we send the original, we put it in a closed loop and [we'll] never get it back. We don't want to lose the first object to travel in time. We'll want that for the Smithsonian someday." Does this make sense? Also, comment on whether or not the dog's name is a bootstrap paradox.

A perplexing little time travel paradox, one that I don't think science fiction has yet treated (and I'm pretty sure physicists haven't had anything to say about it either), was cooked-up by the English philosopher Robin Le Poidevin in his 2003 book *Travels in Four Dimensions: the enigmas of Space and Time* (Oxford, pp. 180–181). There he writes "Peter and Jane, both 20 years old, are out for a walk one day in 1999 when suddenly a time machine appears in front of them. Out steps a strangely familiar character who tells Jane that he has an important mission for her. She must step into the machine and travel to the year 2019, talking with her a diary the stranger hands to her. In that diary she must make a record of her trip. Obligingly, she does as she is asked and, on arrival, meets Peter, now aged 40. She tells Peter to travel back to 1999, taking with him the diary she now hands him, and recording his trip in it. On arrival in 1999, he meets two 20-year-olds called Peter and Jane, out for a walk, and he tells Jane that he has an important mission for her." Le Poidevin then writes that "the really tricky question is: how many entries are there in the diary when Jane first steps into the machine? We imagine it blank. But this is the very same diary as the one Jane hands to the 40-year-old Peter, which then contains her entry. And by the time Peter arrives back in 1999, it will contain his entry, too. But then, if the diary already contained two entries when Jane was handed the diary, then it would contain three entries when she handed it to Peter, who would then add another one, so the diary would have contained four entries when it was first handed to Jane, and so on. If the problem is not immediately apparent, this is because we imagine an indefinite number of trips, but in fact there are just two: Jane's trip to 2019 and Peter's trip to 1999. So there ought to be a consistent answer to the question, how many entries are there in the diary? Yet, as we have seen, there does not appear to be a consistent answer." Another philosopher soon claimed he *did* have the answer: namely, 2. Read his paper (Erik Carlson, "A New Time Travel Paradox Resolved," *Philosophia*, December 2005, pp. 263–273), and either explain why you agree with Carlson's reasoning or enthusiastically rebut it.

As in "The Time Eliminator" (Fig. 4.1), other stories have imagined gadgets that simply view the past, rather than visit it as would a time machine. This is done in an attempt to avoid paradoxes—but does it? Two stories that illustrate how just viewing the past risks affecting the past as much as time travel would, are Horace Gold's "The Biography Project" (*Galaxy Science Fiction*, September 1951) and Donald Franson's "One Time in Alexandria" (*Analog*, June 1980). In the first tale the Biotime Camera, operated by the Biofilm Institute, allows teams of biographers to film (alas, no sound!) and study the lives of past notable personages. Of particular interest are the lives of those who developed neurotic psychoses, such as Isaac Newton. And, indeed, the Biotime Camera does capture Newton's image as he begins to display increasingly disturbed behavior. We see Newton, for example, as he begins to peer into dark corners, looking for those who have come to spy on him. On his death bed, the biography team assigned to him reads his lips and discovers that his final words are "My guardian angel. You watched over me all my life. I am content to meet you now." It is then that the Biofilm Institute realizes what it has done. Newton *was* in fact being spied upon—by the Biotime Camera, which has not changed the past but has certainly affected it. In the second tale an archeologist uses a time viewer to read the lost manuscripts in the ancient library at Alexandria before it was completely destroyed in an inferno. The viewer uses an infrared beam—and it is the heat from that beam from the future that proves to be the origin of the fire in the past. Again, the past has been affected, but not changed, by time viewing. Is it true to claim, however, that such viewing gadgets could not be the source of other paradoxes, such as causal loops or information bootstraps? If you think that isn't a valid claim, give a counter-example.

In a story by Francis Flagg and Weaver Wright (a pseudonym used by Forrest J. Ackerman), "Time Twister" (*Thrilling Wonder Stories*, October 1947), we read the following exchange between the inventor of a time machine and his none-too-bright helper:

"You mean to say," he questioned incredulously, "that I could go back a hundred years?"

"If you had the proper machine in which to travel, yes."

"But that'd take me back to before I was born."

The Professor smiled tolerantly.

"Look at this diagram, Hank. This line is the time continuum. It incorporates space, too. [The authors didn't actually print a diagram with the story, but

(continued)

surely the Professor is using a Minkowski spacetime diagram]. This dot is you. It doesn't matter when you were born, or when you will die. You exist right now, that's the fact. Traveling into the past or future wouldn't make you grow any younger or older. Such a thought is naïve. Let me demonstrate the mechanics of it for you. If . . . we calculate with non-Euclidean mathematics . . ."

"It don't sound reasonable," the farmhand objected. "If I went back—"

"I know," interjected the Professor, "if you went back you might meet your own father as a young man and you'd be older than he, or maybe he and your mother would be kids going to school."

"Haw, haw! That'd be funny, that would."

What famous movie, made nearly 40 years later, does the end of the conversation remind you of? Hint: "flux capacitor."

As mentioned in the text, a famous science fiction example of *affecting* (but not changing) the past is "Behold the Man" by Michael Moorcock, the tale of a time traveler who arrives in ancient times during the very years of the ministry of Jesus as reported in the Bible. When he finds there is actually no such person, the time traveler takes the role himself and lives out the events as reported in the Gospels, including the Crucifixion. This is a powerful story, but it had already been done more than 15 years earlier, by Philip K. Dick, in his short story "The Skull" (*If*, September 1952). In his tale, Dick tells of a man from the twenty-second century who is sent by government authority back to the mid-twentieth century to kill the Founder of a religious movement, a movement that 'now,' 200 years later, threatens those same government authorities. History records that the Founder gave a powerful speech just before being arrested and executed, a speech that started the religious movement, and so the time traveling assassin is told to kill the Founder *before* he can give that speech. (The parallel between Jesus and the Founder should be obvious.) Read these two stories and compare and contrast how Moorcock and Dick handled time travel paradoxes. Comment, in particular, on the relationship between the assassin and the Founder. Moorcock's tale should be easy to find, and Dick's is available as a free pdf download (it is in the anthology *The Best of Philip K. Dick*, Halcyon Classics 2010, as well).

A subtle change-the-past sequence appears in the original *Back to the Future* film that is easy to miss. When the hero, Marty McFly, returns to 1955 in the time car, he leaves from the parking lot of the Twin Pines Mall, so named because of the two pine trees that stand nearby. Arriving in the past with literally a bang, the time car inadvertently destroys one of the (then) young pines. Near the end of the movie, when Marty returns to the future (1985), he finds that the mall is now called the Lone Pine Mall. This is charming and fun, indeed clever, but modern scholars of time travel reject it, and other claims of changing the past, as not being logical. (Shakespeare understood this point, when he has Lady Macbeth declare, concerning the murder of Banquo, “What’s done cannot be undone: to bed, to bed, to bed.”) What Marty’s trip *would* explain is why the mall would *always* have had the name of the Lone Pine Mall. Watch the movie and see how many other ‘change-the-past’ episodes you can find.

Chapter 5
Communication with the Past

"[As for travel to or for signaling the past] you'd have to exceed light speed which immediately entails the use of more than an infinite number of horsepowers."[1]

5.1 Reversed Time

"I have not discovered Mr. Wells' Time Machine."[2]

One way to communicate with the past is to 'simply' live backwards in time. Philosophers and other writers of speculative fiction were the first to wonder what things might be like in a world where the time asymmetry is reversed—that is, in a world where time 'runs backward.' Indeed, fascination with the idea of time reversal actually dates back thousands of years, long before science fiction, as it can be found in Plato's dialogue *Statesman*, written (most probably) 15 years before Plato's death in 347 B.C.

At one point, Plato offers an extended description of the world suddenly running backward in time in the ancient past. After one character is told that at that remote time "all mortal beings halted on their way to assuming the looks of old age, and each one began to grow backward," he asks "But how did living creatures come into being, Sir? How did they produce their offspring?" The answer is shocking: "Clearly . . . it was not of the order of nature in that era to beget children by intercourse . . . It is only to be expected that along with the reversal of the old men's course of life and their return to childhood, a new race of men should arise, too—a new race formed from men dead and long laid in Earth . . . Such resurrection

---

[1] An observation by Haskel van Manderpootz, professor of the "newer physics," in S. G. Weinbaum's "The Worlds of If," *Wonder Stories*, August 1935. Compared to the 'modest' Van Manderpootz, all other physicists in the world are a mere "pack of jackels, eating the crumbs of ideas that drop from [his] feast of thoughts."

[2] W. R. Inge (1860–1954), in his November 1920 Presidential Address to the Aristotelian Society at the University of London Club, in a sympathetic treatment of the possibility of a time-reversed world.

© Springer International Publishing AG 2017
P.J. Nahin, *Time Machine Tales*, Science and Fiction,
DOI 10.1007/978-3-319-48864-6_5

of the dead was in keeping with the cosmic change, all creation being now turned in the reverse direction."

The reversed-time world is an important philosophical concept. Before the turn of the century, for example, Francis Bradley (one of the early proponents of the block universe, you will recall from Chap. 2), thought about reversed-time worlds and concluded that they would be quite odd: "Let us suppose . . . that there are beings whose lives run opposite to our own . . . *If* in any way *I* could experience *their* world, I should fail to understand it. Death would come before birth, the blow would follow the wound, and all must seem to be irrational."[3] A half-century later the South African philosopher J. N. Findlay (1903–1987) took Bradley's position of supporting a skeptical attitude towards the possibility of time-reversed worlds. Writing in a book review, Findlay declared "The reversed world in question wouldn't merely strike us as queer, but definitely crazy: it would be a world where what is wildly and intrinsically *improbable* was always occurring. It would, in fact, be much more startling than the original asymmetry that led us to think of it."[4] (Findlay was almost certainly thinking of things like a tea cup, shattered due to a fall, spontaneously reassembling itself.)

The question of backward-running time so fascinated Findlay that, some years later, he posed it as a problem for the readership of a scholarly journal (*Analysis*). This led to a number of responses, and subsequently he presented both his own negative view of time-reversed worlds and that of the best reader response he had received to his posed problem (which came from McGechie).[5] While Findlay showed admirable open-mindedness by awarding the title of *best* to an argument that refuted his own position, he remained unconvinced about the concept of reversed-time worlds, stating that "I continue to feel that a total reversal of my experiences is a terrifying possibility."

The terror aspect of living backward in time had been nicely captured in a science fiction story years before Findlay wrote. A scientist who is involved in an accident with radioactive materials has his sense of time flow reversed, and the story carefully and logically analyzes what his life would be like in such a situation. For example, the scientist can talk (backwards for others, of course), so he is understandable only if his words are recorded and then played in reverse. He cannot eat, because for him that would involve the regurgitation of food. He cannot answer questions because "if he should answer any questions put to him, it would mean he was giving the answer before he heard the question, on his time scale." And finally, he can't pick anything up because the normally stable position and velocity error-correction mechanism between eye, hand, and brain, which is a negative feedback system in normal time, has become an unstable positive feedback system in reversed time. The horror of his existence is contained in the only words the man utters (deciphered after reversed playback): “Where am I? What’s happened? Why are things so different? Why? Why?”[6]

---

[3] F. H. Bradley, *Appearance and Reality* (2nd edition), Oxford University Press 1897, p. 190.

[4] J. N. Findlay, *Philosophy* (25) 1950, pp. 346–347.

[5] J. N. Findlay and J. E. McGechie, "Does It Make Sense to Suppose That All Events, Including Personal Experiences, Could Occur in Reverse?" *Analysis*, June 1956, pp. 121–123.

Despite Findlay’s “terror,” however, the prevailing view today is that to the inhabitants of a time-reversed (or what is sometimes called a *counterclock*) world, *nothing would look odd*! This is a fairly new idea,[7] and not so long ago the philosophical literature displayed a misunderstanding of how a time-reversed world would appear to its occupants.[8] More recent analyses than Smart’s (note 7) advocating the ‘normality’ of a time-reversed world are more compelling.[9] One concern about a time reversed world however is not easily dismissed: matter with a time reversed time sense is thought by many to be antimatter in our world, and any interactions between the two worlds would be spectacular, indeed![10]

But let’s ignore that possible difficulty. The philosopher J. R. Lucas argued that even if beings from two such time-reversed worlds could meet, they still could not communicate: “If two beings are to regard each other as communicators, they must both have the same direction of time. It is a logical as well as a causal prerequisite.”[11] Now, this matter is well worth some effort to understand, because it is intimately tied to time travel. At first blush, Lucas’ words seem almost self-evident, and after a little thought they might seem to be absolutely irrefutable. The philosopher Murray MacBeath, however, took exception.

MacBeath opened his analysis[12] with a story to demonstrate that the persuasive power of Lucas’ position is only superficial. In that story of Jim and Midge, Jim is one of us, whereas Midge is a ‘Faustian time’[13] being. In his analyses MacBeath uses capitalized words and symbols for the time-reversed Midge, and lower case for Jim, as shown in Fig. 5.1. As MacBeath explains, “While Jim and Midge are together a face-to-face conversation is hardly likely to get off the ground. To make this clear let us say that they are together from t_0 until t_{10} on Jim’s time-scale, and from T_0 until T_{10} on Midge’s TIME-scale; t_0 is then the same temporal instant as T_{10} and, in general, $t_n = T_{10-n}$. If Jim at [his time] t_2 asks Midge a

---

[6] M. C. Pease,” *Astounding Science Fiction*, “Reversion,” December 1949. See also R. A. Banks, “This Side Up,” *Galaxy Science Fiction*, July 1954, for a tale about the confusion caused by projecting a film the wrong way in time.

[7] The modern view that a time-reversed world would appear normal to someone living in it can be traced back at least as far as to J. J. C. Smart, “The Temporal Asymmetry of the World,” *Analysis*, March 1954, pp. 79–83, an analysis, alas, that may not convince everyone.

[8] M. Dummett, “Bringing About the Past,” *Philosophical Review*, July 1964, pp. 338–359.

[9] See, for example, D. L. Schumacher, “The Direction of Time and the Equivalence of ‘Expanding’ and ‘Contracting’ World-Models,” *Proceedings of the Cambridge Philosophical Society* 1964, pp. 575–579; J. V. Narlikar, “The Direction of Time*,” British Journal for the Philosophy of Science*, February 1965, pp. 281–285; F. R. Stannard, “Symmetry of the Time Axis,” *Nature*, August 13, 1966, pp. 693–695.

[10] This issue is raised, several times, in Robert Silverberg’s 1968 novel *The Masks of Time*.

[11] J. R. Lucas, *A Treatise on Time and Space*, Methuen 1973, pp. 43–47.

[12] M. MacBeath, “Communication and Time Reversal,” *Synthese*, July 1983, pp. 27–46.

[13] In Goethe’s play *Faust*, the normal flow of time is routinely upset.



Fig. 5.1 Opposite time flows in counterclock worlds

question, and Midge hears the question at T_8, she will answer at T_9, and Jim will hear his question answered at t_1, *before* he asked it! What is more, if Jim is inexpert at interpreting backward sounds, and at t_4 asks Midge to repeat her answer, Midge will hear that request at T_6, BEFORE she has heard the original question; and her puzzled reply at T_7 will be heard by Jim at t_3 before he has uttered the request." Certainly this is a mess in time, and Lucas seems to be on safe ground with his denial of the possibility of communication between Jim and Midge. MacBeath, however, shows how to refute all of Lucas' arguments if Jim and Midge are allowed to be clever about how they send their messages back and forth—that is, if we give up some of our usual ideas of what a conversation is like. MacBeath's analyses are far too lengthy and detailed to present here, but the simplified diagram of Fig. 5.1 should enable one to follow the logic of his approach.

We imagine that Jim and Midge will not actually talk, and so will not have to decipher backward-spoken language. Rather, they will exchange messages via computer-generated text displayed on monitor screens, screens that are separated by a window that is proof against all penetration but the light emitted by those screens.[14] The nature of this window is not a trivial matter: if we accept the anti-matter nature of Midge's world then it is *essential* to keep her and Jim apart! To that end, MacBeath imagined that the window is double paned, with a perfect vacuum in-between. The exchange of photons between the two worlds should present no problems because photons are their own anti-particles.[15]

Now, imagine that at t_0 Jim brings a computer to the window. He programs it to wait for 4 days, until t_4, and then to display the following message on its screen: "This message is from Jim, who experiences time in the sense opposite to yours. Please study the following questions and display your answers on a computer screen three days from now." Jim's messages ends with the list of questions.

Because all that took place at t_4, Midge sees Jim's message and questions at what we will now call T_0. As requested, she brings her computer to the window, enters the answers to Jim's questions, and programs the machine to display them (after a

---

[14] Communication between beings in counterclock worlds, using written messages displayed through a window, appeared in science fiction *years* before MacBeath wrote: see I. Watson's 1978 novelette "The Very Slow Time Machine."

[15] There is no difference in the time sense of photons in either world because the flow of proper time for a photon—traveling at the speed of light, by definition—is zero (recall the discussion in Sect. 3.6).

3 day delay) on its screen. Thus, at T_3, which is Jim's t_1, Jim sees Midge's computer screen light up with "Hi, Jim. This is Midge. The answers to your questions are at the end of this message. Now, I've got some questions for *you*. Please display the answers two days from now." Midge's message ends with answers to Jim's questions and her list of questions.

Jim sees Midge's message at t_1, enters the answers to her questions and sets the machine to answer after a 2-day delay. At t_3, which is Midge's T_1—and by now you see how the process goes. It's cumbersome, sure, but it works. Or at least it does if everybody follows the rules. What if they don't? MacBeath provides other, increasingly complicated analyses to treat some of the more subtle problems that can be imagined in this method of exchanging messages. I will mention just two of them, which have direct analogs with what we normally think of as 'time travel.'

For the first problem, consider Jim's initial message, created at t_0 to be sent at t_4. He receives Midge's answer as described above at t_1, *before* his message is displayed through the window. So, what happens if at t_2 Jim cancels the message and it is *not* displayed? He has already gotten Midge's reply, but how can that happen if he does not send his message? This is, of course, a bilking paradox, with an explanation that we discussed in the previous chapter.

A second problem is the apparent possibility of creating a causal message loop. For example, let's say that at t_0 Jim suddenly decides to send a message through the window. (His reason for this sudden urge will be explained in the next few lines.) He thinks all night about what to send and, at t_1, finally settles on the following: "Greetings to the people on the other side of the window. This message comes from Jim, who hopes you will reply." Midge immediately sees Jim's message through the window (at her time T_3) and so is suddenly caught up with the desire to respond. She thinks all night about what to send and, hoping to be witty, she finally decides (at time T_4) on the following echo to Jim's message. "Greetings to the people on the other side of the window. This message comes from Midge, who hopes you will reply." Jim immediately sees this through the window (at what is his time t_0) and so now we know why he decides to send his original message! And Jim *will* send his original message—he has to because Midge replied to it.

In a review of a book on the direction of time, the philosopher Hilary Putnam restated the problems of a time-reversed world in the form of a provocative question: "How do you know that one man's future isn't another man's past?"[16] He began by making the interesting observation that for us to be able just to observe a backward-running universe, we would have to provide our own normal radiation source, because the counterclock stars in such a universe *absorb* radiation rather than emitting it. This point was elaborated on by another philosopher some years later, who wrote "We have uncritically imagined someone looking in on ... two worlds having opposite time directions ... Part of the story we tell, of the process of seeing, involves the emission of photons from objects [for example, the computer screens of Jim and Midge] and the subsequent impinging of these photons on our retinas. But this process is obviously directed in time. In a world where time ran opposite to ours, we could not see objects at all: objects would be photon-sinks, not photon-emitters."[17]

---

[16] H. Putnam, *The Journal of Philosophy*, April 1962, pp. 213–216.

Putnam concluded his comments about reversed time with a cautious warning: "It is difficult to talk about such extremely weird situations without deviating from ordinary idiomatic usage of English. But this difficulty should not be mistaken for a proof that these situations could not arise." That challenge is no doubt why so many writers of science fiction and fantasy have tackled the question of what it would be like if time ran backward. We can find such a tale long before the science fiction pulps, in fact, in a tale that appeared when Einstein was just 7 years old. In that story[18] the narrator (a professor of astronomy and higher mathematics) suddenly finds himself on Mars. There he encounters beings who know the future up to their deaths, and whose memories of the past are "scarcely more than a rudimentary faculty." The entire tale is in the form of a conversation between the professor and one such being, who argues (quite persuasively) for the virtues of his 'backward' existence compared to that of earthlings (the Martian name for Earth is the story's title). Bellamy realized that his story implies a fatalistic block universe: "No one could have foresight . . . without realizing that the future is as incapable of being changed as the past," he wrote.

Other writers, too, were fascinated by the implications of reverse time. When Merlyn the magician makes his first appearance in T. H. White's 1939 masterpiece *The Once and Future King*, for example, he explains how he knows the futures of others: "Ordinary people are born forward in Time, if you understand what I mean, and nearly everything in the world goes forward, too . . . But I unfortunately was born at the wrong end of time, and I have to live backwards from its front, while surrounded by a lot of people living forwards from behind. Some people call it having second sight."

What may have put the idea in White's mind for his time-reversed magician is only speculation today, but perhaps it was something he might have read a decade before, in a fellow Englishman's writing, the 1929 book *The Nature of the Physical World* by Sir Arthur Eddington, where one finds the following passage: "In "The Plattner Story" H. G. Wells relates how a man strayed into the fourth dimension and returned with left and right interchanged . . . In itself the change is so trivial that even Mr. Wells cannot weave a romance out of it [but see one of the *For Further Discussion* questions at the end of Chap. 2]. But if the man had come back with past and future interchanged, then indeed the situation would have been lively."

Whether or not those words influenced English fantasy, they certainly had some effect on American science fiction. In his 1979 memoir *The Way the Future Was*, pulp editor Frederik Pohl wrote that Eddington's book (which Pohl incorrectly attributed to Sir James Jeans) had given him the idea for a story using the reversed-time twist. But before Pohl could publish it, an even better (claimed Pohl) tale arrived from Malcolm Jameson. Jameson, too, had read Eddington's book, and the result was the novella-length "Quicksands of Youthwardness," which Pohl published in *Astonishing Stories* as three-part serial during 1940–1941. Unfortunately, Jameson's tale is both pretty awful *and* devoid of *any* connection with Eddington's suggestion. One can only wonder about what might have been in the story Pohl says *he* discarded—did *it* have the future remembered? Alas, Pohl wrote that he couldn't remember!

---

[17] N. Swartz, "Is There an Ozma-Problem for Time?" *Analysis*, January 1972, pp. 77–82.

[18] E. Bellamy, "The Blindman's World," *The Atlantic Monthly*, November 1886.

Remembering the future does occur in one tale where everybody knows what will happen (as they live backward) by reading "prediction books." What distinguishes that story from many others on the same theme is an interesting, ironic conversation a student in a reverse-time world has with a philosophy professor about how things would be if time went the 'other way,' as in *our* world:

> "How can we tell? The reverse sequence of causation may be just as valid as the one we are experiencing. Cause and effect are arbitrary, after all."
>
> "But it sounds pretty far-fetched."
>
> "It's hard for us to imagine, just because we're not used to it. It's only a matter of viewpoint. Water would run downhill and so on. Energy would flow the other way—from total concentration to total dispersion. Why not?"[19]

The student is unconvinced, however, and when he tries to visualize such a peculiar world (*our* world, don't forget!) it gives him a "half-pleasant shudder." Imagine, he thinks in wonder, never knowing the date of your own death.

A few years later, in Wilson Tucker's 1955 novel *Time Bomb*, we find the intriguing idea of political assassination by time bomb, with the bombs actually *time traveling* to their targets. A policeman begins to suspect what is happening when it becomes evident that one of the explosions was actually an implosion: "The time bomb ... had been going in and had carried the force of the blast with it. Inward. Into the past. He frowned at that. A backward explosion? An explosion which ran counter to the normal flow of time, to the normal method of living? ... How would an explosion appear to a man if the blast happened in the opposite manner? If it began exploding now, in this moment, but continued backward instead of forward? Would it be an implosion?"

There is little doubt that the definitive treatment of a reversed-time world is that of Philip K. Dick's 1967 novel *Counter-Clock World*. Dick's world was once our world, but then, as in Plato's tale that began this chapter, time suddenly begins to run backward. People still alive reverse their direction of aging (but still think, walk, and talk in forward time), and dead, buried people come alive again and emerge from graveyards as the "Sacrament of Miraculous Rebirth" is intoned by a priest; all live their way back to the womb, just as in Plato's tale of 1600 years earlier. Such imagery is powerful stuff, but the physicist John Wheeler (of black hole fame) would have none of it. As he wrote, "Most of us would probably agree that the universe has not contained and will not contain any backward-looking observers. We do not expect to see caskets with corpses in them coming to life, nor do we expect to find bank vaults in which a gram of radium will integrate rather than disintegrate."[20]

---

[19] D. Knight, "This Way to the Regress," *Galaxy Science Fiction*, August 1956.

5.2 Multi-dimensional Time

> "If there are extra time dimensions we get violations of causality, because one could sneak to yesterday through the extra dimensions, and . . . if you had sneaked to yesterday, you would have disappeared from today."[21]

There are those, however, who haven't been quite so sure as Wheeler about the impossibility of a reversed-time world. One physicist, for example, showed how (under certain initial conditions at the Big Bang) there is a possible solution to the gravitational field equations that gives an oscillating universe that temporally runs backward during the contraction phase.[22] And a philosopher has argued that the *direction* of time is local, not global (just as special relativity showed is the *rate* of time) and that the arrow of time can point in opposite directions at different locations.[23] As odd as such ideas may seem, a generalization of reversed-time—*multi-dimensional* time—makes it seem small potatoes. This is the idea that there might be *many* possible directions to the arrow of time, not just two. At first this may seem an absurd idea, something akin to a man jumping onto his horse and riding off in all directions at once. But philosophers (and perhaps just a few physicists[24]) have started to take at least a semi-serious look at the concept; as with so many other of the radical concepts associated with time travel, though, science fiction writers were dealing with multi-dimensional time long before it became a respectable topic in learned philosophical and physics journals.

---

[20] Wheeler's comments can be found in the General Discussion at the end of *The Nature of Time* (T. Gold, editor), Cornell University Press 1966.

[21] An intriguing (if somewhat mysterious) thought from F. J. Yndurain, "Disappearance of Matter Due to Causality and Probability Violations in Theories with Extra Timelike Dimensions," *Physics Letters B*, February 28, 1991, pp. 15–16.

[22] H. Schmidt, "Model of an Oscillating Cosmos Which Rejuvenates During Contraction," *Journal of Mathematical Physics*, March 1966, pp. 494–509. An elaboration of Schmidt's ideas is in A. Walstad, "Time's Arrow in an Oscillating Universe," *Foundations of Physics*, October 1980, pp. 743–749.

[23] G. Matthews, "Time's Arrow and the Structure of Spacetime," *Philosophy of Science*, March 1979, pp. 82–97.

[24] More than half-a-century ago one writer asserted that two-dimensional *complex* time was old hat in the theories of spinning particles—see M. Bunge, "On Multi-dimensional Time," *British Journal for the Philosophy of Science*, May 1958, p. 39. For a summary of many of the objections to multi-dimensional time see J. K. Kowalczynski, "Critical Comments on the Discussion About Tachyonic Causal Paradoxes and the Concept of Superluminal Reference Frames," *International Journal of Theoretical Physics*, January 1984, pp. 27–60 (and the reply by E. Recami, September 1987, pp. 913–919).

In one pulp story, for example, we find a professor asking his redundantly named class in speculative metaphysics “Why shouldn’t time be a fifth, as well as a fourth, dimension?”[25] In response to a generally skeptical reception to that, the professor goes on to say “I believe in the existence of a two-dimensional time scheme . . . Ordinarily, most people think of time as a track they run on from their births to their deaths . . . Think of this time track we follow over the *surface of time* as a winding road [it is the imagery of a surface that gives the professor *two* time dimensions] . . . Once in a while another road crosses at right angles. Neither its past nor its future has any connection whatsoever with the world we know.”[26]

The year before, the same pulp had published another tale[27] that went well beyond a mere two time dimensions. We are told in that story of two countries on an alien planet at war in the distant future. The war is a stalemate until one side begins to fire a gun at its foe from just two miles from its target, in the heart of enemy territory—*from the middle of next week*! The gun’s shells are true ‘time bombs.’ This is not mere ‘ordinary’ time travel along one time track, however, but a multidimensional effect. Using a photograph of the gun in actual operation to support his astonishing discovery, an agent for the side being shelled reports to his superior that “the gun and its crew are existing along another time axis at right angles to the direction of our ‘normal time,’ so that from our point of view they are existing perpetually in the same instant.”

That explains why the gun crew can (will?) operate without interference in next week’s future, as they are in their adversary’s time only for the instant that the two time tracks intersect. Indeed, the spy used the same trick to obtain his undetected photograph: “I secured the photograph by orienting myself along still another time axis at right angles to that of the gun, and approached it as an instantaneous, invisible entity.” By the story’s end both sides are using and counter-using this technique, evading each other “to and fro along an ever increasing complexity of mutually perpendicular time axes.” In fact, the final count exceeds 75 time axes, making Heinlein’s two-dimensional time look rather skimpy by comparison.

Well, of course, 75 time directions *is* science fiction (I think), and physicists are not so enamored of multidimensional time as are science fiction writers. For example, Eddington wrote that he found the idea of any region of spacetime involving two-dimensional time to “defy imagination.”[28] Another physicist showed that the extremal property of timelike geodesics (look back at Fig. 3.15 and its discussion) would fail for multidimensional time, which he then associated with the stability of matter and a failure of causality.[29] Yet another physicist, however, was just a bit more willing to consider multidimensional time, and suggested that a viable theory of quantum gravity *might* support the idea of multiple time dimensions.[30] Of just *what* more than one time dimension might actually *mean*, however, this same physicist echoed Eddington by writing "Physics in a spacetime of . . . two timelike dimensions would be very weird indeed." Agreeing with this physicist was a philosopher who called the idea that there could be more than one dimension to time a "rather wild possibility" and a "fairy-tale."[31] These are probably fair statements of how most physicists presently think of multidimensional time.

---

[25] R. Heinlein, “Elsewhen,” *Astounding Science Fiction*, September 1941.

[26] This story has an amusing scene in which one of the professor’s students accidently ‘jumps time tracks’ and so enters a new track with his arrow of time pointing backwards.

[27] N. L. Knight, “Bombardment in Reverse,” *Astounding Science Fiction*, February 1940.

[28] A. S. Eddington, *The Mathematical Theory of Relativity* (2nd edition), Cambridge University Press 1924, p. 25.

But not all philosophers are of that persuasion, and many are in fact as fascinated by the possibilities of multidimensional time as are science fiction writers. So, *why* this interest in something so different from anything we actually experience? Where does the motivation come from? Of what *use* is multidimensional time? I think the answers to those questions all derive from how multidimensional time offers a theoretical model for giving meaning to the view that the past can be changed (take a look back at note 20 in the Introduction).

In a certain trivial sense, of course, the past is always changing. For each of us the past is the set of all events that have happened, arranged in a before/after temporal order, and this set is continually increasing (and so changing). That is not, however, what most people mean by a changeable past. What *is* meant is that there may be some kind of change in the temporal ordering of events, or that an event that once was (or wasn't) a member of the set of past events no longer is (or is now) a member. Two-dimensional time offers a way to make sense of such possibilities, which one-dimensional time simply cannot do. To see how that works, I'll follow the presentation in a paper that forcefully argues that it does make sense to talk about altering the past.[32]

Meiland was aware that some might find his model *ad hoc*, even "incredibly weird" (in his own words), but he justified his efforts by taking a refreshingly enlightened, non-Humean view of what he thought would be the proper response to meeting purported time travelers: "If strange machines containing people in futuristic garments and speaking strange tongues (or perhaps using ESP instead of speech) were to appear and were to claim to be from the future, we might very well begin to search for a theory of time that allows their claim to be true." In Fig. 5.2 you can see how Meiland tried to do just that.

---

[29] J. Dorling, "The Dimensionality of Time," *American Journal of Physics*, April 1970, pp. 539–540.

[30] C. Isham, "Quantum Gravity," in *The New Physics* (P. Davies, editor), Cambridge University Press 1989.

[31] D. Zeilicovici, "Temporal Becoming Minus the Moving-Now," *Nous*, September 1989, pp. 505–524.

[32] J. W. Meiland, "A Two-Dimensional Passage Model of Time for Time Travel," *Philosophical Studies*, November 1974, pp. 153–173. Jack Meiland (1934–1998) was a professor of philosophy at the University of Michigan.



Fig. 5.2 Two-dimensional time

The dashed diagonal line, marked with the points t_1, t_2, ... represents our usual one-dimensional image of time. The horizontal lines P_1t_1, P_2t_2 ... (which we can simply call $P_1, P_2, \ldots$, for short) are the pasts for the present instants $t_1, t_2, \ldots$. That is, P_1 is the past with respect to the present t_1, P_2 is the past with respect to the present t_2, and so on. The dashed vertical lines allow us to locate any moment in the past. For example, the intersection point A of P_4 with Pt_1 is the location of t_1 in the past with respect to the present t_4.

With this model, Meiland then analyzed in detail several interesting special cases. Suppose that t_1 and t_2 are 1 year apart and that there is a similar time separation between all adjacent, marked present moments on the diagonal. Let us further suppose that a time traveler at t_4 journeys backward 3 years to t_1, to arrive at point A. Assume he stays in the past 2 years; then his temporal locations lie along the dashed diagonal line ABC; that is, at B he is 3 years in the past of t_5, and at C he is 3 years in the past of t_6. From Fig. 5.2, then, we can imagine the time traveler saying, as he climbs into his time machine at t_4, "One year from now I'll be two years from now." That rather astonishing statement makes sense when we take both uses of now to be t_4 and observe that B (1 year from A) is 2 years in the past with respect to t_4.[33]

---

[33] A critic of time travel (see note 119 of Chap. 2) used what he claimed to be the absurdity of such a statement to support his ejection of time travel. One of Meiland's reasons for developing his two-dimensional model of time was, in fact, to be able to reply to that critic (Donald Williams).

Meiland's two-dimensional time model is undeniably fascinating, but it simply has no theoretical justification (as far as I know[34]). It is not necessary to assume two-dimensional time to explain Meiland's "strange machines containing people in futuristic garments"; it is possible to do that with one-dimensional time in a four-dimensional spacetime. The classic paradoxes, too, are understandable without two-dimensional time, as discussed in the previous chapter.

5.3 Maxwell's Equations and Sending Messages to the Past

> "Communication with a world exactly, to minutest detail, a duplicate of our own [but] twenty thousand years ahead of us might ruin the human race as effectively as if we had fallen into the Sun."[35]

Every physicist and electrical engineer knows that the mathematical description of the electromagnetic field is given by Maxwell's equations. In particular, radio engineers know that the waves of energy their antennas launch into space follow the predictions of those equations with astonishing accuracy. Indeed, when Einstein's relativity theory was completed, it was found that Maxwell's equations automatically satisfy relativity because magnetic effects *are* relativistic effects; in other words, relativity is built into Maxwell's equations. Whereas Newton's laws of dynamics had to be patched up, Maxwell's equations were untouched by the discovery of relativity.

Thus, it was a puzzle when physicists discovered that careful study of the seemingly perfect Maxwell equations, when applied to antennas, apparently results in the prediction of causality violation. It is found, in fact, that the equations have *two* solutions. One, as expected, contains the feature of time delay; that is, creating an electromagnetic disturbance at the antenna *now* causes a detectable effect at a distant point in space *later*. This is the so-called *time-retarded-solution*, and its common-sense physical interpretation is that of energy waves traveling away from the antenna as they also travel into the future. The shock was that Maxwell's equations also accept an *advanced solution*; energy waves *arriving* at the antenna from infinite space.

The physicist Paul Renno Heyl (1872–1961) wrote the perhaps first scientific work discussing advanced electromagnetic effects, in his 1889 University of Pennsylvania doctoral dissertation with the provocative title "The Theory of Light on the

---

[34] Many of the arguments against multi-dimensional time can be found in M. MacBeath, "Time's Square," in *The Philosophy of Time* (R. Le Poidevin and M. MacBeath, editors), Oxford University Press 1993. MacBeath concludes, however, with "I would not want to rule out the possibility . . . that time is three-dimensional. Or worse." See also Alasdair Richmond, "Plattner's Arrow: Science and Multi-dimensional time," *Ratio*, September 2000, pp. 256–274.

[35] The Victorian writer Samuel Butler (1835–1902), in the "Imaginary Worlds" entry of *The Notebooks of Samuel Butler* (published posthumously in 1912), commenting on the chaos that communication across time might cause.

Hypothesis of a Fourth Dimension." Heyl cited the scientific guru of the fourth dimension, C. H. Hinton (look back at the last "For Further Discussion" assignment in Chap. 2) as his inspiration. The situation described by Heyl is something like that of a child standing at the edge of a pond. She throws a rock into the middle of the pond and watches ripples spread out and away from the splash. Suddenly, she sees ripples appear all around the edge of the pond and then travel inward toward the center, where they all converge at once. A spout of water then erupts from the surface of the pond at the simultaneous meeting of the inward-traveling ripples, and she watches as a rock is ejected from the spout to land back in her hand. She is, of course, open-mouthed with astonishment! How absurd, you think, as you read this, and who could blame you? This amazing imagery of advanced effects we owe to the philosopher Karl Popper, and it has come to be called "the fable of the Popperian pond."[36]

Pursuing the mathematics of wave motion in the fourth dimension, Heyl wrote "We are led to the curious conclusion that, in Hinton's aether,[37] the nature of the central disturbance *after* a given instant can influence the form of the aether *before* that instant. In other words, the aether seems to be endowed with an uncanny faculty of foreknowledge." We can avoid such a counter-intutive implication of advanced effects, but only at the price of something many physicists and philosophers consider equally unacceptable: information traveling from the future into the past. We can still think of the advanced solution as representing electromagnetic waves of energy traveling *away* from the transmitting antenna—that is, as being *broadcast*, just like the retarded solution, rather than being received from infinity—*if* we also think of the waves traveling backward in time. Thus, the advanced solution to Maxwell's equations holds out the possibility of sending messages to the past, a sort of poor man's time travel. It may seem that we have simply traded one problem for another, however, because just sending information into the past can cause many of the same paradoxical, causality-busting situations that physical time traveling is claimed to cause.

The cosmologists Fred Hoyle (1915–2001) and J. V. Narlikar commented on the potential problems posed by communication backward in time, in their 1974 book *Action at a Distance in Physics and Cosmology*: "The [Maxwell] equations supply us with both advanced and retarded solutions (and, because of the linearity, with any linear combination of them) . . . With so many solutions theoretically possible, why does nature always select the retarded one? That this question cannot be answered within the framework of Maxwell's theory must be regarded as one of its intrinsic weaknesses."

---

[36] K. Popper, "The Arrow of Time," *Nature*, March 17, 1956, p. 538. See, too, note 110 (and its discussion) in Chap. 2.

[37] It was thought, in nineteenth century physics, that electromagnetic waves need a *medium* through which to propagate (like ocean waves need water, and sound waves need air), a mysterious substance called the *aether* (or *ether*) that exists even in a vacuum. The 1871 Michelson-Morley experiment, however, implied that the aether simply does *not* exist.

That branding of Maxwell's theory as having an "intrinsic weakness" because of its prediction of an advanced solution was, I think, unwarranted. Indeed, the advanced solution can be given a perfectly reasonable physical interpretation.[38] Imagine a transmitting antenna sending electromagnetic waves to an identical receiving antenna. At any point in space between the two antennas there are electric and magnetic fields. Maxwell's equations allow us to calculate the fields produced by alternating currents in the two antennas. When we do an analysis of the relationship between the transmitting antenna's current and the fields, we use the retarded solution because the current is the cause and the fields are the effect. But in the analysis of the relationship between the fields and the receiving antenna's current, the situation is reversed, and the fields are the cause and the current is the effect. That is, the advanced solution is simply the mathematics relating the current in the receiving antenna *now* to the fields *in the past*.

An acceptance of both solutions has, in fact, been in the physics literature for nearly a century. As the Yale physicist Leigh Page (1884–1952) wrote decades before Hoyle and Narlikar, "While the advanced potentials, as well as the retarded potentials, satisfy the electromagnetic equations, the former has generally been discarded for the reason that it has been more in accord with the trend of scientific intuition to consider that the present is determined by the past course of events than by the future. However, if it is once admitted that the present state is uniquely determined by any past state, it follows that the future is also so determined, and hence the employment of a future state as well as a past state in specifying the present marks no inherent departure from our accustomed methods of description . . ."[39]

It may still be tempting, however, to just dismiss the advanced solution as a mere anomaly of the mathematics and to discard it on physical grounds. This is the traditional approach taken by physicists when confronted with non-causal solutions in any physical theory and, indeed, that was what Swiss physicist Walter Ritz (1878–1909) did with the advanced solutions to Maxwell's equations (an approach that involved Ritz during the last year of his life in a dispute with Einstein). For Ritz, the reversal of cause and effect simply did too much violence to his intuition to be taken seriously, and so he thought one must *impose* causality on Maxwell's equations (a condition they do not inherently contain) by *a priori* rejecting the advanced solution.[40]

Still, electrical engineers make similar kinds of judgements all the time, as when the solution of a quadratic equation for a passive (energy-dissipating) resistor gives both a positive value (which 'makes sense') and a negative value (which doesn't 'make sense' and so is simply ignored). There *were*, however, those who encouraged caution on this issue. Seventy-five years ago, for example, the eminent MIT electrical engineer Julius Adams Stratton (1901–1994) echoed Leigh Page's warning when he wrote of the disturbing advanced solution, "The familiar chain of cause-and-effect is thus reversed and this alternative solution might be discarded as logically inconceivable. However, the application of 'logical' causality principles offers very insecure footing in matters such as these and we shall do better to restrict the [Maxwell] theory to retarded action solely on the grounds that this solution alone conforms to the *present* [my emphasis] data."[41]

---

[38] See, for example, S. L. Schwebel, "Advanced and Retarded Solutions in Field Theory," *International Journal of Theoretical Physics*, October 1970, pp. 347–353, and L. M. Stephenson, "Clarification of an Apparent Asymmetry in Electromagnetic Theory," *Foundations of Physics*, December 1978, pp. 921–926.

[39] L. Page, "Advanced Potentials and Their Application to Atomic Models," *Physical Review*, September 1924, pp. 296–305.

[40] For more on this, see O. Costa de Beauregard, "No Paradox in the Theory of Time Anisotropy," *Stadium Generale* 1971, pp. 10–18.

And in a famous paper I'll discuss in the next section, Wheeler and Feynman declared that "We conclude advanced and retarded interactions give a description of nature logically as acceptable and physically as completely deterministic as the Newtonian scheme of mechanics. In both forms of dynamics the distinction between cause and effect is pointless. With deterministic equations to describe the event, one can say: the stone hits the ground because it was dropped from a height; equally well, the stone fell from a height because it was going to hit the ground."[42] For Wheeler and Feynman, the reversal of cause and effect inherent to backward causation and time travel to the past offered no conceptual difficulties.

The elimination of an appeal to causality, or to the 'weirdness' of advanced waves, in arguing for the naturalness of the retarded solution to Maxwell's equations was first done in 1976.[43] The only auxiliary condition applied to the equations was simply the natural one of requiring the initial field energy to be finite.[44] And yet, today, there is still no experimental evidence for the physical reality of the advanced solution. Now and then one does run across speculations that the advanced waves of *something* traveling backward to us from the future might explain the so-called ESP 'talent' of precognition, but that is all it is, speculation.[45]

Advanced waves appeared in the pulp science fiction of the late 1930s, a decade before Wheeler and Feynman. For example, one story actually specifically invoked the advanced solution to Maxwell's equations, with a gadget (making use of what the author called the "anticipated potentials") displaying the near future on a television-like screen.[46] The author's by-line proudly gave his academic credentials as including a master's degree and, in fact, John Pierce was a graduate student in electrical engineering at Caltech. He received his doctorate just months after this story was published, and then went on to a highly distinguished career at Bell Telephone Laboratories and then later at the Jet Propulsion Laboratory operated by Caltech for NASA. Pierce knew all about Maxwell's equations, of course, and he actually opened his tale with a quote from Page's 1924 article (note 39) on the advanced solution. How many fictional pieces include quotes from the *Physical Review*?

---

[41] J. A. Stratton, *Electromagnetic Theory*, McGraw-Hill 1941, p. 428.

[42] J. A. Wheeler and R. P. Feynman, "Classical Electrodynamics in Terms of Direct Interparticle Action," *Reviews of Modern Physics*, July 1949, pp. 425–433.

[43] P. C. Aichelburg and R. Beig, "Radiation Damping As An Initial Value Problem," *Annals of Physics*, May 1976, pp. 264–283.

[44] J. L. Anderson, "Why We Use Retarded Potentials," *American Journal of Physics*, May 1992, pp. 465–467.

[45] See M. B. Hesse, *Forces and Fields*, Philosophical Library 1961.

[46] J. R. Pierce, "Pre-Vision," *Astounding Stories*, March 1936.

And it would probably take something like advanced waves to explain the funny doings 2 years late in a story of a man caught in a time machine accident. Nearly all of his body ends up 4 years in the future—but only *nearly* all, because his eyes remain the present! As one of the puzzled observers of this odd business wonders, "Strange, that his eyes, now, can convey a message to his brain, four years hence, and his brain tells the eye muscles to move the eyeballs which are four years behind them —."[47]

Some of the most intriguing paradoxes of time travel involve no traveler—only information. Of course, any information flow at all, independent of time travel, involves the flow of energy and, as Einstein showed, energy and mass are different aspects of the same thing. Accordingly, information time travel involves the transfer of mass/energy. Thus, a man in the twenty-fifth century who sends a backward-in-time 'temporal radio' message to a twentieth-century woman stating that he loves (will love?) her is sending much more than mere emotion. Just *how* to send a message backward in time is, of course, the puzzle.

Indeed, all forms of present-day communication are transmissions only to the future. If you speak to someone, or if you send a radio message, there are always delays depending on the distance of separation and the speed of transmission of sound and light, respectively. If you want to send a message to the one hundred and twenty-fifth century, you can; just write a letter and seal it in a pressurized bottle of helium. This basic idea is dramatically presented in a novel about a scientist who is accidently transported from 2162 back to the late-Cretaceous, 80 million years into the past. There he leaves a written record on seven sandstone slabs of his brutal, lonely life among the dinosaurs—letters across time, if you will—found by twenty-second century geologists some years after his disappearance.[48] The transmission of such letters, *forward* in time, while dramatic, is not a puzzle. But what could be more astonishing than the message received *from the future* by the young inventor of the first time machine: after his initial experiment of sending his pilotless machine into the future, it returns with an envelope inside. Eagerly tearing it open, he finds the note is from the National Academy of Sciences: "We know from old records and museum models that this is the Cullen Foster experimental machine. Fifty years looks down on you and says 'Good work'."[49]

Heady stuff, that, but lots of other possible messages are capable of competing with young Foster's when it comes to generating excitement. For example, suppose you had a gadget that is superficially similar to a telephone but that calls telephones in the *distant* future. You can hear the person (in the future) on the other end, but they can't hear you (in their past). That is, information can flow only from future to past. It is then easy to imagine situations in their use of this device that at least seem paradoxical. For example, suppose you call your own private number 1 month ahead. You hear your future-self first answer the phone, and then recite the winning lottery for the 'previous' day, which is a month in your present self's future. (Your future self does this somewhat odd recital because a month from now you will remember, when your private phone rings, just *who* is calling!) So, now in the present you know you'll make a fortune by winning the lottery a month later.

---

[47] M. Schere, "Anachronistic Optics," *Astounding Stories*, February 1938.

[48] G. G. Simpson, *The Dechronization of Sam Magruder*, St. Martin's Press 1996.

[49] D. Stapleton, "How Much to Thursday?" *Thrilling Wonder Stories*, December 1942.

This example *is* admittedly somewhat mysterious since, for the gadget to call far ahead in time, some sort of signal (as yet unspecified) must travel into the distant future because *something will* make the future phone ring. For the present discussion I am ignoring this crucial issue for the sake of the dramatic impact of the example. Soon, however, we'll get a little way into describing how one might, in principle, actually build this gadget, which in the physics literature is called an *antitelephone*. (Such a device is an *anti*telephone because the person who is the receiver is in the sender's past, the opposite of the situation for an ordinary telephone.) An interesting fictional illustration of such a gadget, despite being told as a hard-boiled detective murder mystery, appeared in science fiction some years ago (alas, while called a "time telephone," no theory for its operation was given, but instead was 'explained' as a "straightforward application of an impressive, but limited, technology").[50] So far, there is nothing paradoxical (or even illegal) in all of this, but what if, when the phone rings in the future the day after you won the lottery, you perversely decide *not* to recite the winning number? This apparent paradox has, in fact, already been treated with the aid of the block universe view of spacetime; that is, if the future-you spoke the lottery number when you originally called, then the present—you (now in the future) *must*, inevitably recite it.[51]

Let's now make things a bit more involved. Suppose that instead of calling your future self, you call the weather service and listen to the recorded message telling you the weather, 30 days hence. You do this day after day, and after a while you get a reputation for being able to predict, *perfectly*, the weather for every day to come, up to a month into the future. Your reputation spreads far and wide, and after a while more the weather service hears about you. Meteorologists check and find you are *never* wrong. Their computer models are only 80 % accurate out to 3 days, and for a week's prediction and beyond, the general public might as well flip a coin on whether it will rain or not on any particular day. But you are 100 % correct out to ten times their range. And so they hire you—and as a secondary job, you also make the daily weather recordings. (The voice on the other end of the gadget *has* sounded sort of familiar!) Here, then, is the puzzle we encountered earlier in causal loops carrying information: from *where* is the information in the flawless weather predictions coming from?

---

[50] S. Schmidt, "Worthsayer," in *More Whatdunits* (M. Resnik, editor), DAW 1993. The author, Stanley Schmidt, has a Ph.D. in physics and is a former editor of *Analog Science Fiction* magazine.

[51] For a fictional illustration of this (a so-called *bilking paradox*), see W. Tevis, "The Other End of the Line," *Magazine of Fantasy and Science Fiction*, November 1961.

One easy answer is that the question is meaningless because such a future-to-the-past information flow must be impossible. Indeed, if I am to avoid telling a ‘philosopher’s fairy tale,’ like those I criticized earlier in the book, I must admit that one consistent, non-paradoxical answer is found in recognizing that I have *assumed* that those 30-day weather reports are correct. Maybe, however, they are no better than anybody else’s predictions. And so you *don’t* become famous, and you *don’t* get hired—and so there *isn’t* any paradox. Is that the way to avoid paradoxes involving information flowing backward in time?

Perhaps not. As long as 1917 it was realized that special relativity does not preclude such an apparent backward flow. That is, if information could be transmitted faster than light, *then* messages could travel backward in time. That was the year Richard Tolman (1881–1948), a professor of physical chemistry at the University of Illinois and later at Caltech, wrote “The question naturally arises whether velocities which are greater than that of light could ever possibly be obtained.”[52] He then answered that question, with his general conclusion being that if such velocities are possible, then a faster-than-light (FTL) observer could see the time order of two causally related events reverse. And thus the observer would see an affect *before* its cause. Alternatively, a *sub*luminal (slower-than-light) observer could see the two events, which are connected via an FTL interaction, reversed in time order from what a stationary observer would see.

Either situation has come to be called Tolman’s paradox, but Tolman himself was careful with his words: “Such a condition of affairs might not be a logical impossibility; nevertheless its extraordinary nature might incline us to believe that no causal impulse can travel with a velocity greater than that of light.” That was an astonishing statement, given that Einstein himself had specifically stated in his original 1905 paper on special relativity that such a thing simply could not occur. There is nothing, it would seem, to be “inclined” about.[53]

This rather technical connection between FTL speeds and backward time travel made the transition from theoretical physics to popular culture very quickly. It was in the British humor weekly *Punch*, for example, that the famous (but nearly always misquoted) limerick by A. H. R. Buller (1874–1944) first appeared:

There was a young lady named Bright
Whose speed was far faster than light;
She set out one day

---

[52] R. C. Tolman, *The Theory of the Relativity of Motion*, University of California Press 1917.

[53] Take a look back at Sect. 3.5, where we showed that the time order of two events can appear reversed for a subluminal observer if the two events are not causally related. Introducing FTL motion results in extending reversal to causally connected events; that is, FTL motion, reversed causation, and time travel to the past, go hand-in-hand-in-hand.

In a relative way
And returned on the previous night.[54]

Where *Punch* dared to go, Hollywood could not be far behind. Indeed, in this case it was actually there first, with the 1922 one-reel silent comedy movie *The Sky Splitter*. This was just a short film (feature pictures generally had at least four reels), so it is not clear how widely distributed and viewed it may have been. The story is that of a scientist testing a new spaceship: when it exceeds the speed of light, he begins to relive his life.

The linkage between time travel to the past and FTL motion is a central one in science fiction, and its fascination was nicely illustrated by one writer who has a time machine experimenter in the twenty-seventh century wonder "Was the speed of light the core of the mystery? At the speed of light did the past and the future become a shining, merging road down which men could walk—in their ears the thunder of time passing . . .?"[55] Not everybody was excited with the idea of FTL motion and travel backwards in time, however, with one eminent scientist declaring that "the limit to the velocity of signals is our bulwark against the topsy-turvydom of past and future."[56]

The obvious question at this point, of course, is whether it is even conceptually possible to build a gadget to send FTL messages backward in time? Einstein himself thought not, saying "We cannot send wire messages into the past."[57] But was he right? One hint at the possibility of achieving FTL speeds is in Dirac's 1938 paper (note 52 in Chap. 2). There, in his remarks about pre-acceleration, Dirac wrote "Suppose we have a pulse sent out from place A and a receiving apparatus for electromagnetic waves at a place B, and suppose there is an electron on the straight line joining A to B. Then the electron will be radiating appreciably [because accelerated charges radiate] before the pulse has reached its centre and this emitted radiation will be detectable at B at a time . . . earlier than when the pulse, which travels from A to B with the velocity of light, arrives. *In this way a signal can be sent from A to B faster than light* [my emphasis]."

This exciting conclusion goes a step beyond the usual examples of 'things that go faster than light.'[58] Dirac had an equally exciting reaction (and here the emphasis is his): "This is a fundamental departure from the ordinary ideas of relativity and is to be interpreted by saying that *it is possible for a signal to be transmitted faster than light through the interior of an electron. The finite size of the electron now reappears in a new sense, the interior of the electron being a region of*

---

[54] On page 591 of the issue of December 19, 1923.

[55] F. B. Long, "Throwback in Time," *Science Fiction Plus*, April 1953.

[56] A. S. Eddington, *The Nature of the Physical World*, Macmillan 1929.

[57] A. Einstein, "La Théorie de la Relativité," *Bulletin de la Société Francaise de Philosophie* 1922, pp. 91–113.

[58] Such as, for example, the intersection *point* of two very long, closing scissor blades. The explanation for how this can be is that the *point* is massless and does not participate in a causal chain (and so carries no information). Thus, special relativity is not violated.

failure, not of the field equations of electromagnetic theory, but of some elementary properties of space-time." This last line sounds very much like the things people say today about the singularity inside a black hole event horizon. And yet, Dirac was careful to point out that as weird as FTL speed may appear, special relativity is not violated because "in spite of this departure from ordinary relativistic ideas, our whole theory is Lorentz invariant." That is, even though 'faster-than-light' means 'backward in time,' which means 'causality failure,' special relativity still holds true and nothing awful happens to physics, only to our intuitions. The reason for this is that causality is *not* a premise or starting point for the special relativity.[59]

Of course, like any scientific theory, Dirac's theory is not necessarily the last word, and we have to admit the possibility that at least some of its implications (in particular, the possibility of FTL speeds) just aren't so. In all electronic communication systems that we use, information is transmitted by *modulating* a so-called *carrier wave*, and there is some reason to believe that such modulated waves cannot be sent at FTL speeds.[60] We must admit that it is one thing to talk of 'advanced wave radios'—often called *Dirac radios* in science fiction—and quite another to see how physics might actually enable one to talk to the past. FTL communication (without the time travel aspect) appeared in pulp science fiction before 1940, as in one story published the year after Dirac's paper.[61] In it we learn of a man on Pluto who has invented a way to send messages to Earth at twice the speed of light. He uses this gadget to warn of a would-be dictator who is on his way to Earth in a 'mere' light-speed rocket ship, and only an FTL message can warn Earth in time.

5.4 Wheeler and Feynman and Their Bilking Paradox

> "We find it difficult if not impossible to imagine waves that go into the future and *return to the present* [my emphasis] bearing information about where (and when) they have been."[62]

---

[59] See, for example, G. Nerlich, "Special Relativity Is Not Based On Causality," *British Journal for the Philosophy of Science*, December 1982, pp. 361–388. This same point was made nearly two decades earlier, in a study of the possibility of superluminal sound in superdense matter, by D. A Kirzhnitz and V. L. Polyachenko, "On the Possibility of Macroscopic Manifestations of Violation of Microscopic Causality," *Soviet Physics JETP*, August 1964, pp. 514–519.

[60] See G. Diener, "Superluminal Group Velocities and Information Transfer," *Physics Letters A*, December 16, 1996, pp. 327–331. For more on the modulation of a light-speed carrier wave in everyday AM radio, and in a more sophisticated single-sideband transmitter, see my book *The Science of Radio*, Springer 1999.

[61] N. Bond, "Lightship, Ho!," *Astounding Science Fiction*, July 1939. The author provides an interesting, detailed description of the gadget, and I think it would make a good question on a Ph. D. qualifying exam in physics or electrical engineering to explain the flaw in it.

[62] Bob Brier, *Precognition and the Philosophy of Science: An Essay on Backward Causation*, Humanities Press 1974. Brier is an Egyptologist (!) at Long Island University—with a Ph.D. in philosophy—who specialized at one time in parapsychology.

In 1941, at a meeting of the American Physical Society, Princeton University physicist John Wheeler and his student Richard Feynman discussed a seemingly outrageous idea that provided a possible clue to how a Dirac radio might function. The idea was that the advanced wave solutions to Maxwell's equations are not mere mathematical curiosities, but rather have profound physical significance. At the time, their talk received only a small abstract notice in the *Physical Review*, but after World War II they wrote it all up in a beautiful paper.[63]

Their primary goal was to explain the origin of the force of radiative reaction discussed by Lorentz earlier in the century. This reaction force is the cause of the energy loss suffered by an accelerated, charged particle. Lorentz, who thought of charged particles as having a finite size, attributed this reaction force to the retarded (by the time required for light to cross the width of the charged particle) coulomb repulsion force between one side of the particle's charge to the charge on the opposite side. This view, however, leads to various conceptual and mathematical problems, including an arbitrary assumption on how the charge is distributed over/through the finite volume of the particle, as well as the problems of infinite self-interactions and the issue of what keeps the charge from blowing itself apart by internal coulomb repulsion.

Wheeler and Feynman's theory, on the other hand, avoided those problems by postulating point charges, because a *point* charge cannot repel itself. But then whence the reaction force, if there is no repulsion? Their revolutionary explanation was first to imagine the accelerated point charge as emitting retarded radiation outward in space, eventually to be absorbed by distant matter. This distant matter, which itself consists of point charges that are accelerated by the retarded radiation, then radiates *backward* in time, back toward the original charge that started the chain of events. This backward-in-time, or *advanced*, radiation arrives in the past of the original charge, and *it* is the cause of the observed reaction force. Indeed, Wheeler and Feynman proposed that an accelerated charge will not radiate unless there is to be absorption at some other distant place and future time. That is, the *future* behavior of a distant absorber determines the *past* event of radiation; there is simply no such thing as just radiating into empty space. The entire universe, spatially *and* temporally, is a very 'connected' place!

Astonishingly, this non-causal view of spacetime had been around in physics for at least 20 years before Wheeler and Feynman's talk. They had independently developed their ideas but, after their 1941 talk, Einstein (who perhaps recalled his 1909 debate about advanced effects with Ritz) brought a 1922 paper by the Dutch physicist Hugo Tetrode (1895–1931) to their attention. In his paper Tetrode had written that "the Sun would not radiate if it were alone in space and no other bodies could absorb its radiation ... If for example I observe through my telescope yesterday evening that star which let us say is 100 light years away, then not only did I know that the light which it allowed to reach my eye was emitted 100 years ago, but also the star or individual atoms of it knew already 100 years ago that I, who then did not even exist, would view it yesterday evening at such and such a time."

---

[63] J. A. Wheeler and R. P. Feynman, "Interaction with the Absorber as the Mechanism of Radiation," *Reviews of Modern Physics*, April–July 1945, pp. 157–181.

Tetrode's vivid imagery had been, curiously, itself captured even decades earlier in words from the nineteenth century English poet Francis Thompson (1859–1907), in his "The Mistress of Vision":

All things … near and far,
Hiddenly to each other linked are,
That thou canst not stir a flower
Without troubling of a star.

None of this, of course, is obvious! As a tutorial paper appearing just 2 years after Wheeler and Feynman's 1945 paper expressed it, "Any physical theory which seriously proposes that events in the future may be the efficient cause of events in the past may be regarded—at least at first glance—as rather revolutionary doctrine."[64] Indeed!

It is interesting to note that Einstein apparently said nothing to Wheeler and Feynman about a paper that pre-dated Tetrode's by 3 years. In 1919 the Finnish physicist Gunnar Nordström (1881–1923) had suggested that the advanced solution might offer an explanation for a perplexing problem in atomic theory. Maxwell's theory says that an accelerated electric charge radiates energy, which implies that the orbital electrons in the classical model of the atom should quickly spiral in toward the nucleus, that is, all matter should collapse. This cataclysmic event (of course!) has not happened, and Nordström's idea was that if one took into account not only the usual retarded solution but the advanced one as well, then perhaps things could be understood. Indeed, Nordström was able to show that such an analysis does give zero for the *average* energy radiated by an orbiting electron. Later, however, Page (note 39) showed that the instantaneous radiated energy is not zero, and that this would lead to observable effects that in fact are *not* observed.

Now, to be sure that the 'doctrine' discussed in note 64 is clear, let me restate what Tetrode, and later Wheeler and Feynman, had in mind. Imagine we have an electric charge (the *source*) that we mechanically shake, that is, accelerate. This allows us to assign a definite *cause* to the charge's acceleration which, of course, radiates energy. This radiation travels outward into space as observed retarded fields until they are eventually absorbed by distant matter. The charges in that distant matter are thus accelerated, and they in turn therefore radiate energy. This induced radiation again consists, according to Wheeler and Feynman, of both retarded and advanced fields. The advanced fields radiate outward but *backward* in time toward the original charge, collapsing upon it at the precise instant we first shook it, thereby producing the radiative reaction force. At any instant of time, at any point in space, the observed field is the sum of the retarded field traveling away from the source into the future and the advanced field traveling toward the source in the past.

---

[64] C. W. Berenda, "The Determination of Past by Future Events: A Discussion of the Wheeler-Feynman Absorption-Radiation Theory," *Philosophy of Science*, 1947, pp. 13–19.

But, argued Wheeler and Feynman, there is one last point that has been left out of this picture—there is also an advanced field (traveling away from the source and backward in time) because of the original, mechanical shaking of the source charge. Equivalently, a field traveling *forward* in time will *converge* onto the source because we *will* shake it. Wheeler and Feynman showed that before the mechanical shaking that starts this whole process, the advanced radiation field of the source and the advanced radiation fields of the absorbers exactly cancel each other at every point in space and every instant of time (if there is total absorption in the future), which accounts for the experimental fact that we observe a zero total field before the mechanical shaking occurs.

Wheeler and Feynman showed that if we accept these (strange) ideas, then everything we actually observe is predictable: radiative reaction, the direction of the electromagnetic arrow of time from past to future (retarded-only effects), and the absence of infinite self-interactions. The claim by Wheeler and Feynman to have avoided self-interaction problems via the use of the advanced solution was, however, soon challenged. Indeed, the self-interaction of the electron is *needed* to explain the 1947 experiment by Willis Lamb (1913–2008) that measured the deviation (the *Lamb shift*) of the spectrum of hydrogen from what Dirac's theory of the electron predicts. Ironically, it was that experiment that helped motivate the renormalization of quantum electrodynamics (to get rid of the infinities then plaguing it) which led to Feynman's share of the 1965 Nobel Prize. In fact, just 4 years after their 1945 paper, Feynman expressed a revised view that self-interactions could not be avoided.[65]

In any case, we gain the rewards originally claimed by Wheeler and Feynman *only if* we accept backward time travel, a step too big for many in 1945 (and for nearly as many today) because of the resulting time travel paradoxes that seem to be unavoidable. For the same reason, Tetrode's earlier work, published in a German journal, also went virtually unnoticed during the two decades before Wheeler and Feynman's work. In fact, Tetrode wasn't the only anticipator of Wheeler and Feynman, as they had been anticipated, too, in America. In 1926 the chemist G. N. Lewis (1875–1946) had written "I'm going to make the … assumption that an atom never emits light except to another atom, and to claim that it is absurd to think of light emitted by one atom regardless of the existence of a receiving atom as it would be to think of an atom absorbing light without the existence of light to be absorbed."[66] Wheeler and Feynman were aware of Lewis by 1945. Certainly Wheeler and Feynman must have been intrigued by Lewis' paradox: "I shall not attempt to conceal the conflict between these views and common sense. The light coming from a distant star is absorbed, let us say, by a molecule of chlorophyll which has recently been produced in a living plant. We say that the light from the star was on its way toward us a thousand years ago. What rapport can there be between the emitting source and this newly made molecule of chlorophyll?"

---

[65] R. P. Feynman, "Space-Time Approach to Quantum Electrodynamics," *Physical Review*, September 15, 1949, pp. 769–789. See also C. Teitelboim, "Splitting the Maxwell Tensor: Radiation Reaction Without Advanced Fields," *Physical Review D*, March 15, 1970, pp. 1572–1582.

[66] G. N. Lewis, "The Nature of Light," *Proceedings of the National Academy of Sciences*, January 15, 1926, pp. 22–29.

The paradox in that, of course, arises from the issue of what happens if, at some intermediate time and place, the star's light is blocked, thus preventing its absorption by the chlorophyll? Could refusing to look at a star *now* affect the emission of the star's light in the *past*? Lewis was obviously making a clear statement of backward causation when posing this bilking paradox. His very next words show that he understood the probable reaction of his readers: "Such an idea is repugnant to all our notions of causality and temporal sequence." Like Tetrode's work, Lewis' ideas were ahead of the times but, actually, their ideas were *not* repugnant to everyone.

In fact, similar puzzles were an inspiration to Wheeler and Feynman and almost certainly motivated them to create their own famous bilking paradox, which they presented in their 1949 paper (note 42). They opened the presentation of their paradox as follows: "If the present motion of *a* is affected by the future motion of *b*, then the observation of *a* attributes a certain inevitability to the motion of *b*. Is not this conclusion in direct conflict with our recognized ability to influence the future motion of *b*?" This question clearly states the conflict between free will and determinism, and to sidestep this *human* concern Wheeler and Feynman constructed a "paradox machine," a machine that operates totally automatically and which has come to be called the "logically pernicious self-inhibitor"![67]

In their description of the paradox machine, Wheeler and Feynman ask us to imagine two charged particles, *a* and *b*, positioned five light-hours apart. As shown in Fig. 5.3, *a* is attached to the arm of a pivoted shutter, toward which a pellet is moving from initially a great distance away. Now, normally we would think of what happens next in terms of just retarded fields. That is, the pellet hits the arm, knocking it downward and thereby accelerating charge *a*; this acceleration of charge *a* creates a retarded radiation field that arrives at charge *b* 5 h later, resulting in the acceleration of charge *b*; the acceleration of charge *b* creates a retarded radiation field that arrives back at charge *a* 5 h later (10 h after the pellet hit the arm).

The Wheeler and Feynman view, however, claims that this description leaves out half the story—the *advanced* fields. Specifically, suppose the pellet will hit the arm and so accelerate *a* at 6 p.m. Then, *b* will be affected not only 5 h later at 11 p.m., but also *earlier* at 1 p.m. This advance acceleration of *b*, in turn, sends out an advanced field that arrives at *a* at 8 a.m. The paradox is now easy to see. As Wheeler

---

[67] P. Fitzgerald, "Tachyons, Backwards Causation, and Freedom," *Boston Studies in the Philosophy of Science* (volume 8), 1970, pp. 415–436. Even more extreme examples of such paradox machines are described in Tim Maudlin, "Time Travel and Topology," *PSA 1990*, Philosophy of Science Association, volume 1, pp. 303–315.



Fig. 5.3 Wheeler and Feynman's paradox machine

and Feynman described events, we see *a* exhibit a premonitory movement at 8 a.m. Seeing this motion in the morning, we conclude that the pellet will hit the arm in the evening. We could then return to the scene a few seconds before 6 p.m. and block the pellet from acting on *a*, a task automatically accomplished by the shutter in Wheeler and Feynman's paradox machine. But then we are faced with the puzzle of explaining just *why a* moved in the morning!

Wheeler and Feynman claimed they had resolved their bilking paradox by observing that *discontinuous* forces (more generally, *signals*) are never seen in nature. They concluded that the shutter does not completely block the pellet, but rather the shutter suffers a "glancing blow." That is, a very weak advanced signal is received by charge *a*, which moves the shutter just enough to induce the "glancing blow," and it is this partial interaction that results in the weakened signal in the "first place." This is, in fact, the very same explanation that was rediscovered decades later in answer to similar bilking paradoxes that involve self-interacting billiard balls transiting wormhole time machines (a topic we'll take-up in the next chapter).

5.5 Absorber Theory and Signaling the Past

> "If advanced waves [could be used to signal the past] then our grip on reality would become more tenuous. The past could never be considered over and done with, because anyone with the proper hardware could send messages back in time and alter what had already happened."
>
> —John Cramer, a University of Washington physicist, taking the minority position on the possibility of changing the past[68]

---

[68] Cramer has written provocatively on advanced waves. See, for example, "The Arrow of Electromagnetic Time and the Generalized Absorber Theory," *Foundations of Physics*, September 1983, pp. 887–902, and "Generalized Absorber Theory and the Einstein-Podolsky-Rosen Paradox," *Physical Review D*, July 15, 1980, pp. 362–376.

Wheeler and Feynman's argument *is* logically and physically sensible; it is, after all, simply an early statement of the principle of self-consistency in physics. Wheeler summed matters up nicely, years later, when he wrote "Interconnections run forward and backward in time in such numbers as to make an unbelievable maze. That weaving together of past and future seems to contradict every normal idea of causality. However, when the number of particles is great enough to absorb completely the signal starting out from any source, then this myriad of couplings adds up to a simple result: the familiar retarded actions of everyday experience, plus the familiar force of radiative reaction with its familiar sign."[69]

Their analysis was based on classical physics but, many years later, Feynman wrote (in his famous autobiographical work *Surely You're Joking, Mr. Feynman*) that at one time he and Wheeler thought it would not be too difficult to work out the quantum version of their theory. But then first Wheeler failed in the task, and then Feynman tried his hand at it and, as he stated, "I never solved it, either—a quantum theory of half-advanced, half-retarded potentials—and I worked on it for years." Their paradox (if indeed it *is* a paradox, since if advanced fields don't actually exist then there is no problem) remains unsolved.

Is Wheeler and Feynman's view of nature correct? Could we use advanced waves to send signals to the past? Or, if that requires some yet-to-be-developed technological breakthroughs in transmitter design, and if receivers are easier to construct, could we at least listen-in to the future (since we are, *now*, the future's past)? And if we could do that, could the future send us the details of the transmitter breakthrough (thus creating a causal information loop in time)?

The first experimental search for advanced waves seems to have been a 1973 effort.[70] The very next year, flaws in that search process prompted two physicists to discuss an experiment designed to detect advanced waves (if they exist). As they wrote, in a grand understatement, the exciting possibility of a positive result "would have such far-reaching consequences on our ideas of the unidirectionality of time and causality that … the experiment justifies a large amount of effort, even if no conclusive result is obtained for years."[71] Alas, all of the searches for advanced waves have, as I write (2016), given negative results and so the world still awaits the first Dirac radio.

Over the years the Wheeler and Feynman view of nature has been the target of some theoretical concerns. One physicist, for example, complained that Wheeler and Feynman had assumed a static, time-symmetric spacetime for the universe, in which the properties of all past and future absorbers are identical. That is obviously not so in an expanding (or contracting) universe and, as he wrote, "No serious modern cosmological theory is framed in [terms of] a static Universe."[72] Another puzzle for that writer was that Wheeler and Feynman took a time-symmetric theory of half-retarded/half-advanced waves in a time-symmetric universe and arrived at a *non*-time-symmetric solution! They performed that trick by supposing not only that the universe is static, but also that it was created with the initial condition of low entropy. Thus, for Wheeler and Feynman, the one-way thermodynamic arrow of time is the primary arrow, with the electromagnetic arrow following as a consequence. (The *how* of a low entropy initial cosmological condition was left unexplained—certainly no mention of the hand of God appears in their work!) This ordering of the primacy of the temporal arrows was, in fact, in agreement with the view adopted by Einstein in his 1909 debate with Ritz, a view taken decades later by Hawking, as well.[73]

---

[69] See note 34 in Chap. 3. There Wheeler also wrote "The particles of the absorber are either at rest or in random motion before the acceleration of the source. They are correlated with it in velocity after that acceleration. Thus radiation and radiative reaction are understood in terms, not of pure electrodynamics, but of statistical mechanics."

[70] R. B. Partridge, "Absorber Theory of Radiation and the Future of the Universe," *Nature*, August 3, 1973, pp. 263–265.

[71] M. L. Herron and D. T. Pegg, "A Proposed Experiment in Absorber Theory," *Journal of Physics A*, October 1974, pp. 1965–1969.

Wheeler and Feynman had shown that both the advanced and retarded solutions taken together are self-consistent in a static universe; Hogarth's question was whether the observed retarded solution, *alone*, would be self-consistent in an *expanding* universe (which is the universe we actually observe). His conclusion? It depends on the details of the expansion. Two years after Hogarth, two physicists expanded on his work and claimed to have shown that the retarded solution alone *is* self-consistent *if* the expansion is steady-state via the continuous creation of matter.[74] That would be the case because, if only retarded effects are to occur, then each emitter of radiation needs a large number of absorbers (such as ionized intergalactic gas) in its future light cone to provide for complete absorption. This, in turn, requires that the density of matter not decline "too fast" with the expansion. That is, the future universe must not be "too transparent" and the continual appearance of new matter in the ever-increasing volume of the expanding universe is required to maintain the necessary density.

That conclusion was embraced with particular enthusiasm by Hoyle, a British cosmologist whose name has long been identified with the idea of continuous creation of matter. Since then, however, continuous-creation cosmologies have fallen into disfavor because it was in 1965, just a year after Hoyle and Narlikar wrote, that the cosmic microwave background radiation was detected. That is now taken as very strong evidence for the occurrence of a primordial explosion (or Big Bang) that started the expansion of the universe, and as equally strong support for therefore rejecting a steady-state universe. Not by Fred Hoyle (1915–2001), though, who had an almost fanatical devotion to non-Big Bang cosmologies.[75] Real puzzles remain for the Big Bang universe, however. One is that it expands from a dense, opaque past into a less dense, ever-more-transparent future, with each emitter having a large number of absorbers in its *past* light cone. That should result, noted Hoyle and Narlikar (almost certainly with some glee), in an observed advanced solution and thus in a reversed electromagnetic arrow that would allow communication with the past. The fact that we have not (yet?) discovered how to perform such communication might be taken to mean that the idea of an expanding, Big Bang universe is somehow faulty. A related question about absorber theory is that of the puzzle of neutrino absorption. Neutrinos are particles that interact so weakly with matter that a beam of them would have to travel through many hundreds of light-years of lead for there to be a significant attenuation of the beam. How can such 'ghost-like' particles find enough future absorbers to make possible their observed journeys into the future of a Big Bang expanding universe?

---

[72] J. E. Hogarth, "Cosmological Considerations of the Absorber Theory of Radiation," *Proceedings of the Royal Society A*, May 22, 1962, pp. 365–383. Hogarth, however, rejected the static universe, asserting instead that the *observed expansion* of the universe provides the required asymmetry, resulting in the cosmological arrow of time as the primary arrow and the electromagnetic arrow as a consequence.

[73] S. W. Hawking, "Arrow of Time in Cosmology," *Physical Review D*, November 15, 1982, pp. 2489–2495.

[74] F. Hoyle and J. V. Narlikar, "Time Symmetric Electrodynamics and the Arrow of Time in Cosmology," *Proceedings of the Royal Society A*, January 1964, pp. 1–23.

For such an exciting idea as communication with the past, it is not surprising that advanced-wave radio has appeared in science fiction. Just 6 years after Wheeler and Feynman's paper, a story by a well-known author hinted at such a gadget based on something called the "ultrawave effect": "While gravitational effects were produced by the presence of matter, ultrawave effects . . . did not appear unless there was a properly tuned receiver somewhere. They seemed somehow 'aware' of a listener even before they came into existence."[76] It is difficult to believe that such a story idea was conjured-up out of nothing, but rather that the author had read Wheeler and Feynman's paper. Anderson had a 1948 undergraduate honors degree in physics from the University of Minnesota, and so he may *well have* read Wheeler and Feynman's 1945 paper.

The potential bilking paradoxes produced by sending messages backward in time have been treated in at least one novel-length discussion. The puzzles presented are undeniably fascinating, but the story's answer to them is to allow the changing of the past, as argued in this section's opening quote from John Cramer. Indeed, the title comes from the plot device of twice changing the past by sending messages to the past to save the world from terrible disasters. Thus, we read through entire time periods *three* times before finishing the novel. As one character blurts out, "We can monitor the actual consequences of our decisions and actions, and change them until they produce the desired result! My God . . . it's staggering!"[77] Quite so.

One of the most interesting science fictional uses of backward-in-time signaling is, I think, found in a classic tale by James Blish. There the "Dirac radio" for instantaneous transmissions is described, and we learn that at the beginning of each received message there is always an irritating audio beep (hence the title) that is seemingly a useless artifact of the mysterious workings of the gadget. Its only obvious characteristic is a continuous spectrum from 30 to well above 18,000 Hz. It is only at the end of the story that the main character learns that this spectrum is the "simultaneous reception of every one of the Dirac messages which [has] ever been sent, or will be sent."[78]

---

[75] Besides his scientific work, Hoyle also wrote science fiction. One work, the 1966 novel *October the First is Too Late*, deals with travels in time but fails to say anything about paradoxes.

[76] Poul Anderson, "Earthman, Beware!," *Super Science Stories*, June 1951.

[77] J. P. Hogan, *Thrice Upon a Time*, Ballantine 1980.

Blish was actually pretty close to the mark with that, as a composite signal with a continuous spectrum (with energy distributed uniformly in frequency), such as one might expect the overlay of many independent signals to be, does indeed have a narrow time structure. If applied to a loudspeaker, such a signal would sound like a sharp pulse or click—or even a *beep*. In the limit of an infinitely wide spectrum, the time signal becomes one of infinite amplitude and zero duration, a singular *impulse* function called, by theoretical physicists and radio engineers alike, the *Dirac delta function*.

There is no mention in the story of advanced waves, but clearly Blish knew that instantaneous (infinite-speed) signals would travel into the past and he does a masterful job of presenting the mystery of listening to the future. At one point characters in the twenty-first century hear the commander of a time-traveling "world-line cruiser" transmit a poignant call for help from 11,000,000 light years away and from sixty-five centuries in the future. Most interesting of all, however, is Blish's statement of a technical issue that I have not seen raised before: if signals arrive at a receiver, simultaneously, from all future times, how can they be separated? Blish resorts to some scientifiction babble-talk to answer that question, but I believe it remains a puzzle.[79]

5.6 Tachyonic Signals and the Bell Quantum Antitelephone

> "We cannot fight the laws of nature."
>
> "Nature be damned! Feed more fuel into the tubes. We must break through the speed of light . . . Give me a clear road and plenty of fuel and I'll build you up a speed of half a million miles in a second . . . What's there to stop it?"[80]

Science fiction writers have often used FTL motion to reverse time, often without much (if any) regard to the fact that, to just *reach* the light barrier, requires (according to special relativity) infinite energy, much less to exceed light speed.

---

[78] J. Blish, "Beep," *Galaxy Science Fiction*, February 1954.

[79] The signal separation problem is also hinted at by physicist/science fiction author Gregory Benford, in a tale that was a precursor to his famous 1980 novel *Timescape* (in which the present attempts to warn the past of a future ecological disaster that threatens life on Earth). See Benford's "Cambridge, 1:58 A.M.," *Epoch*, Berkeley 1975.

[80] Words exchanged by the first officer and the captain of a starship on its way to Alpha Centauri in a story by N. Schachner, "Reverse Universe," *Astounding Stories*, June 1936. The captain, we are told, "had heard, of course, of the limiting velocity of light, but it meant nothing to him."

Therefore, goes the reasoning, because we can't get through the 'light barrier' means that time travel to the past must be impossible, as well. Or, so goes this line of argument. But, could there be a way around this conclusion? After all, while relativity theory indeed precludes the acceleration of a *massive* particle *up to* the speed of light, it does allow a zero rest mass particle (like the photon) to exist *at* the speed of light. Photons are emitted during various physical processes, and they move from the instant of their creation at the speed of light; the only way to slow a photon is to destroy it by absorbing it. Advocates of the possibility of the existence of FTL particles make a similar argument when asking if there might not be particles, emitted during various (as yet unknown) physical processes, that move from the instant of their creation at speed *greater* than that of light?

An affirmative answer would neatly avoid the 'acceleration through the light barrier' problem, but then there are other concerns. For example, such FTL particles would have to have an imaginary rest mass if they were to carry real-valued energy and momentum, and what could *imaginary mass* mean? That question was answered by the proponents of FTL particles, who replied that the rest mass of a superluminal particle would be unobservable because (like the photon) there is no subluminal frame of reference in which the particle could be at rest! That is, there is no frame of reference in which the mysterious imaginary mass could be measured and, anyway, it is only *observable* changes in the real energy and momentum that characterize particle interactions.

The key idea to this line of thought is a *supposed* FTL particle, called a *tachyon*, a name coined by the American physicist Gerald Feinberg (1933–1992) from the Greek word *tachys* for "swift."[81] It is interesting to note that Feinberg admitted[82] that his interest in such a thing was sparked by reading Blish's story "Beep" (see note 78). The idea of the tachyon is actually a very old one that is hinted at in the work of the Greek poet and philosopher Lucretius (who died 20 years before the birth of Christ). In his discussion of visual images, in Book 4 of his giant (well over 7400 lines) science poem *De Rerum Natura*, we find the following words about particles of matter originating deep inside the Sun: "Do you see how much faster and farther they must travel, how they must run through an extent of space many times vaster in the time it takes the light of the Sun to spread throughout the sky?"[83]

The first attempt (later found to be flawed) in the physics literature of a relativistic treatment of FTL particles appeared some years before Feinberg gave

---

[81] G. Feinberg, "Possibility of Faster-Than-Light Particles," *Physical Review*, July 25, 1967, pp. 1089–1105. Feinberg was anticipated in this name by Edward Page Mitchell (the Victorian pioneer in the time travel paradox genre who was discussed back in Sect. 4.2 and its note 37). In his story "The Tachypomp: A Mathematical Demonstration" (*Scribner's Monthly*, March 1874), he describes a gadget for reaching any speed, no matter how great (*tachypomp* is literally "quick sender").

[82] G. Benford, "Time and *Timescape*," *Science-Fiction Studies*, July 1993, pp. 184–190.

[83] A poetic allusion to something traveling faster than light appears, in of all places, Shakespeare's *Romeo and Juliet*. In Juliet's words (Act II, scene 5), "... love's heralds should be thoughts, Which ten times faster glide than the sun's beams, Driving back shadows ..."



Fig. 5.4 The emission of a positive energy particle, followed by absorption

them a name, where it was observed that special relativity is *not* necessarily violated by FTL motion.[84] But nonetheless, concerns about the physical possibility of FTL particles continued. For example, a serious problem for tachyons, at least for those who dislike the ideas of backward causation and time travel, is the observation that in some frames of reference an FTL particle would appear to have *negative energy*. Feinberg, himself, explained (see note 81) this concern as follows: "By the principle of relativity, any state which is possible for one observer must be possible for all observers, and hence FTL particles can exist in negative-energy states for all observers . . . The occurrence of negative energy states for particles has always been objected to on the grounds that no other system could be stable against the emission of these negative-energy particles, an entirely unphysical behavior."

This objection to FTL particles was raised early in the history of tachyons, even before they were named, and it was addressed by three physicists who proposed the so-called *reinterpretation principle* (what I'll refer here to as the RP).[85] To see how the RP works, consider Fig. 5.4, in which a source S_1 at x_1 emits an FTL particle at time t_1. This particle then travels to an absorber S_2 at x_2, arriving there at the later time t_2. S_1 and S_2 are in the same reference frame and, for an observer in the frame, the particle energy E is positive. However, it is always possible to find another observer in a relatively moving frame for whom this process would look as though t_2 is less than (that is, earlier than) t_1 with $E < 0$. In other words, for the moving observer the particle would appear as a negative energy particle moving backward in time. (In the next chapter I'll show you that the particle speed must not be just superluminal, but the even faster *ultraluminal*.)

Note that for the moving observer, the emission by S_1 of negative energy *increases* the energy of S_1, and the absorption of negative energy by S_2 decreases the energy of S_2. S_2's energy decrease (for the moving observer) occurs before the increase in S_1's energy because, as noted before, for the moving observer $t_2 < t_1$. The moving observer naturally interprets this process as the emission of positive energy by S_2, followed by absorption by S_1. This reinterpretation would thus seem to preserve our common-sense idea of causality, as well as avoiding any mention of backward time travel. The RP appears to have slipped around those problems merely by redefining which source is transmitting, and which is receiving, the tachyon. Indeed, Feinberg claimed (note 81) that the RP avoids the creation of causal loops and their associated paradoxes, a claim repeated nearly 20 years later by a physicist who used the RP to eliminate paradoxes from Gödel's time travel rotating universe.[86]

---

[84] S. Tanaka, "Theory of Matter with Super Light Velocity," *Progress of Theoretical Physics*, July 1960, pp. 171–200. See also O. M. Bilaniuk and E. C. G. Sudarshan, "Particles Beyond the Light Barrier," *Physics Today*, May 1969, pp. 43–51 (and the resulting discussion in the December issue, pp. 47–52).

[85] O. M. P. Bilaniuk, V. K. Deshpande, and E. C. G. Sudarshan, "'Meta' Relativity," *American Journal of Physics*, October 1962, pp. 718–723.

There is, however, a curious twist to all this. Even if we grant that the RP may avoid causal paradoxes, the fact is that physics isn't fooled as easily as a human observer. That is, the receiver does actually lose energy upon the arrival of the tachyon, which is the opposite of what happens in a radio receiver when it receives a photon. In other words, the receiver must be in an elevated energy state prior to the tachyon's arrival; the receiver must be prepared beforehand to receive a message. If the receiver were instead sitting in its lowest energy state, then it could not accept (or *eject*, according to the RP) the tachyon. So, it's not surprising that, despite the enthusiastic embrace of the RP by some, other physicists took exception, with one arguing that the effectiveness of the RP in avoiding causal loops is "illusory" and "irrelevant,"[87] while others concluded that the causal paradoxes would actually preclude any possibility of tachyons interacting with ordinary matter in the first place (which is just a polite way of saying that tachyons have no more reality than do unicorns!).[88]

The RP's effect of flipping the roles of transmitter and receiver has attracted particular concern. Some analysts have pointed out that if one can modulate a superluminal signal to send a message into the past, then certainly one could *sign* the message. To quote a delightful example, "If Shakespeare types out *Hamlet* on his tachyon transmitter, Bacon receives the transmission at some earlier time. But no amount of reinterpretation will make Bacon the author of *Hamlet*. It is Shakespeare, not Bacon, who exercises control over the content of the message."[89] The last line of this quote is of central importance. The authors emphasize it by immediately observing that a signature is a *relativistic invariant* and that, indeed, it establishes a causal ordering quite independent of any temporal ordering. This example, alone, explains why one analyst said of the RP that it is "laughed to scorn,"[90] while another said of the RP that it "sounds merely like the endorsement of what can only be characterized as a fantastic delusion."[91]

---

[86] A. Italiano, "How to Recover Causality in General Relativity," *Hadronic Journal*, January 1986, pp. 9–12.

[87] R. G. Newton, "Particles That Travel Faster Than Light," *Science*, March 20, 1970, pp. 1569–1574.

[88] W. B. Rolnick, "Implications of Causality for Faster-Than-Light Matter," *Physical Review*, July 25, 1969, pp. 1105–1108, and D. J. Thouless, "Causality and Tachyons," *Nature*, November 1, 1969, p. 506.

[89] G. A. Benford, D. L. Book, and W. A. Newcomb, "The Tachyonic Antitelephone," *Physical Review D*, July 15, 1970, pp. 263–265.

[90] P. Fitzgerald, "On Retrocausality," *Philosophia*, October 1974, pp. 513–551.

[91] W. L. Craig, "Tachyons, Time Travel, and Divine Omniscience, *Journal of Philosophy*, March 1988, pp. 135–150.

Even more sophisticated scenarios than the *Hamlet* one (note 89) were devised to show how problems with FTL signals could arise that the RP could *not* resolve. The American physicist Bryce DeWitt (1923–2004) created such an example (the 'DeWitt Gambit') that involved a sequential, circular chain of tachyon signal transmissions between four observers, all moving in one spatial dimension. DeWitt showed out to arrange the spacetime geometry of the observers so that, at each stage, there is no dispute over who is sending and who is receiving, and so invoking the RP is avoided. Yet, when the signal reaches the first (last) observer, it is *before* he started (will start) the chain! This, of course, sets-up a potential bilking paradox: what if 'now' the first (last) observer decides to *not* send the chain's initiating signal? An even more sophisticated variation on the Gambit, involving four observers moving in *two* spatial dimensions, was soon after put forth by the English physicist Felix Pirani (1928–2015). As he concluded, "It is difficult to see how in the face of this example a classical-particle description of tachyons can be sustained."[92] Confronted by such sharp criticism, from so many, it is understandable why, just before his death, Feinberg co-authored (with two philosophers) a paper in which he seemed to be abandoning his support for tachyons as possible carriers of information backward in time.[93]

Many physicists today reject the possibility of backward-in-time messages, not because of concerns about the RP, but because such messages could create potential bilking paradoxes. To see how this works, the old Wheeler and Feynman idea of explaining (away) bilking paradoxes—that no signal in nature is *really* discontinuous—was examined by one physicist in the context of tachyons.[94] There we are asked to consider the following situation: A human (call him A) has a lamp on a table before him. The lamp is controlled by a tachyon receiver; in other words, the lamp illuminated only when a tachyon signal (a pulse, let us say) is detected. At 3 o'clock A will send a tachyon signal to B (a tachyon echo-transmitter that immediately rebroadcasts everything it receives) if the lamp does not glow at 1 o'clock. Now, the spacetime geometry of A and B is arranged to be such that a signal sent by either A or B to the other travels 1 h backward in time. Thus, if A sends a signal at 3 o'clock, then B will receive it at 2 o'clock (and immediately echo), and the echo will arrive at A at 1 o'clock. The paradox, of course, is that A sends a signal only if the lamp does *not* glow—that is, only if A does *not* send the signal![95]

We are then reminded of the Wheeler and Feynman claim that every pulsed signal is actually continuous; this argument would include the illumination itself of the lamp. Therefore, the lamp is not just on or off, but potentially at any level of illumination between those two extremes. So there sits A, and at 1 o'clock the lamp seems to glow dimly. To that, says Schulman, "A thinks it over, vacillating, finally sending a slightly late signal which isn't full strength." Then the echo isn't full strength either, which accounts for the original dim glow. This conclusion *is* consistent (but what if A's sending device is a toggle switch that *snaps* one way or the other—why then only a partial strength signal?), but it does seem to ask for a lot of supposing. Schulman himself is not so sure about the validity of universal continuity, writing at the end that "it is not clear that the Wheeler-Feynman assumption . . . ought to be made." (For more on the Wheeler-Feynman continuity assumption, in a different, non-time travel context, see the final "For Further Discussion" for this chapter.)

---

[92] F. A. E. Pirani, "Noncausal Behavior of Classical Tachyons," *Physical Review D*, June 15, 1970, pp. 3224–3225.

[93] G. Feinberg, D. Albert, and S. Levine, "Knowledge of the Past and Future," *Journal of Philosophy*, December 1992, pp. 607–642.

[94] L. S. Schulman, "Tachyon Paradoxes," *American Journal of Physics*, May 1971, pp. 481–484.

[95] A study of similar situations can be found in L. L. Gatlin, "Time-Reversed Information Transmission," *International Journal of Theoretical Physics*, January 1980, pp. 25–29.

The Wheeler-Feynman continuity idea *is* ingenious, allowing one to find a logically and physically consistent solution in time travel scenarios that, at least at first glance, might seem to have no solution. Consider, for example, the following situation[96]: "We have a camera ready to take a black and white picture of whatever comes out of [a] time machine. The film is then developed and the developed negative is subsequently put in the time machine and set to come out of the time machine at the time the picture is taken. This surely will create a paradox: the negative will have the opposite distribution of black, white, and shades of grey, from the picture that comes out of the time machine. But since the thing that comes out of the time machine is the negative itself we surely have a paradox." But do we?

The answer is no, because "What will happen is that a uniformly grey picture will emerge which produces a negative that has exactly the same uniform shade of grey. No matter what the sensitivity of the film is, as long as the dependence of the brightness of the negative depends in a *continuous* [my emphasis] manner on the brightness of the object being photographed, there will be a shade of grey that produces exactly the same shade of grey on the negative when photographed. This is the essence of Wheeler Feynman's idea."[97] (The conclusion is the same if we move from black-and-white to color photography.)

Nonetheless and despite this apparent success, the supposed ability of a modulated beam of tachyons to send a message into the past still raised concerns among many, particularly about free will and fatalism. Suppose, say those who are concerned about these issues, that you receive a tachyon message from yourself from tomorrow, informing you that a man you plan to kill tonight is still alive (tomorrow). Does that mean it is beyond your power to kill him tonight? According to one analyst (note 67) the answer is no; you *could* kill him—but if you do then the message from tomorrow would not have arrived. And because ignorance is not a precondition to free will, your newly acquired knowledge does not, by itself, suddenly limit your ability to kill the man. But, this line of arguing went, if you do not attempt to kill the man because you believe the message from your future self, then in fact the message *has* limited you!

---

[96] Taken from Frank Arntzenius and Time Maudlin, "Time Travel and Modern Physics," in *Time, Reality & Experience* (C. Callender, editor), Cambridge University Press 2002, pp. 169–200.

[97] More on the Wheeler-Feynman continuity idea, *and of its limitations*, can be found in D. Kutach, "Time Travel and Consistency Constraints," December 2003, pp. 1098–1113, and Phil Dowe, "Constraints on Data in Worlds with Closed Timelike Curves," December 2007, pp. 724–735, both in *Philosophy of Science*.

Fitzgerald's position was rebutted by Craig (note 91), who argues that it is not your ability to kill that is altered by the message but rather your motivation. Craig points out that such motivational changes can occur without invoking anything as radical as a message from the future. Suppose, he says, that just before you fire the fatal shot into your victim, you learn from him that he is your beloved, long-lost uncle. Clearly, your motivation for killing him is likely to be instantly altered, but equally clearly, your *ability* to kill him is unchanged. The mechanism for obtaining genealogical information, whether via time travel or as a last-minute appeal from your intended victim, is (says Craig) simply irrelevant. Not all buy into that, however, with one unconvinced analyst (note 94) writing that "history is a set of world lines essentially frozen into spacetime. While subjectively we feel strongly that our actions are determined only by our backward light cone, this may not always be the case." That is, Schulman appears open to the possibility that influences originating in the future might indeed have an impact on the present.

With the fading from the physics scene of enthusiasm for tachyons, the romance of communicating with the past using superluminal speeds passed from speedy particles to quantum mechanics via a mathematical result called *Bell's theorem*. John Bell, a physicist mentioned in the last chapter in connection with the MWI of quantum mechanics, published his theorem in a little article in an obscure, now defunct journal. Since then it has become one of the most cited physics papers from the 1980s.[98] The paradox cited in Bell's title refers to a famous 1935 paper in which Einstein (and two of his colleagues at the Institute for Advanced Study) challenged the conventional view of quantum mechanics, the view that there is no objective reality to anything unless it is observed.[99]

In fact, the possibility of quantum mechanics supporting FTL signals had been considered (and rejected) *before* Einstein's paper, by the Italian physicist Enrico Fermi.[100] Fermi concluded that, in a two atom system, the decay from an excited state of one atom (with the emission of a photon) would not influence the other atom before a time lapse of R/c, where R is the distance between the two atoms and c is the speed of light. In 1967, however, the Russian physicist M. I. Shirokov pointed out that Fermi's result was the result of an unjustified mathematical operation (he had replaced an integral from zero to infinity with one from minus infinity to infinity).

---

[98] J. S. Bell, "On the Einstein-Podolsky-Rosen Paradox," in *Speakable and Unspeakable in Quantum Mechanics*, Cambridge University Press 1987.

[99] A. Einstein, B. Podolsky, and N. Rosen, "Can Quantum-Mechanical Description of Physical Reality Be Considered Complete?" *Physical Review*, May 15, 1935, pp. 777–780. See also N. D. Mermin, "Is the Moon There When Nobody Looks? Reality and Quantum Theory," *Physics Today*, April 1985, pp. 38–47.

[100] E. Fermi, "Quantum Theory of Radiation," *Reviews of Modern Physics*, January 1932, pp. 87–132.



Fig. 5.5 Time travel and the wave function of quantum mechanics. In the above arrangement (reproduced by the kind permission of Francesco Gonella, from his paper "Time Machine, Self-Consistency and the Foundations of Quantum Mechanics," *Foundations of Physics Letters*, April 1994, pp. 161–166), S is a low-intensity source of photons, a source *so* weak that at any instant there is never more than one photon in the system. Each photon begins by traveling toward BS, a half-silvered beam-splitting mirror that, with equal probability, either passes a photon to the right along path b where it is detected by D_2, or downward along path a into mouth B of a wormhole time machine and out of which it emerges from wormhole mouth A *in the past*. Conventional quantum mechanics says that what happens at BS is determined *when the photon reaches BS*—that is, the probability wave function of the photon collapses at BS. But for a photon that is reflected into B, it exits A where it is detected by D_1 *before* the time of its arrival at BS. That means it is known (by detector D_1) what *will* happen at BS *before* the photon arrives at BS—so just *when did* the photon wave function collapse?

Then, nearly 30 years after Shirokov, the German physicist Gerhard Hegerfeldt proved (in the context of conventional quantum mechanics) a very general theorem that establishes a non-zero probability of the second atom responding to the first atom's decay *as soon as* the photon is emitted.[101]

Hegerfeldt's analysis is very general, but it does make one assumption—the non-negativity of energy density (the so-called *weak energy condition*)—which at the time was considered (in Hegerfeldt's words) to be "physically well motivated," but which today is *not* taken to be *a priori* obvious.[102] Einstein's paper, on the other hand, utilized physical assumptions not easily dismissed, and so its conclusions confounded physicists for decades.

The conventional view of quantum mechanics formulates physics in terms of probability wave functions that 'collapse' into specific realities only when measurements (observations) are made of the state of a system (which may be as elementary as a single particle). Until such measurements are made, says this view of quantum mechanics, a system has no specific state; instead, it merely has a probability distribution over a set of possible states (see Fig. 5.5 for a time travel puzzle concerning this claim). Einstein and his co-authors (note 99) strongly rejected this probabilistic interpretation of nature (recall Einstein's famous dictum, "God does not play dice with the cosmos.") Einstein and his colleagues agreed that quantum mechanics may be valid *as far as it goes*, but they also argued that it leaves out 'something' (as yet unknown) in describing reality. That is, they suggested that quantum mechanics is "incomplete" and that it incorporates "hidden variables."[103] They expressed this idea in the form of a paradox, the famous *EPR paradox*, which they posed as a thought experiment (a *Gedanken-experiment*) in which quantum mechanics declares that the properties of a particular spatially distributed system, when measured at point A, seem to be *forced* to assume specific values at point B (which may be arbitrarily distant from A) *without* there being a measurement at B.

---

[101] G. C. Hegerfeldt, "Causality Problems for Fermi's Two-Atom System," *Physical Review Letters*, January 1994, pp. 596–599. This mere *suggestion* of a possible failure of causality so stunned the editor of *Nature* that he felt compelled to quickly write a 'calming' reply: "Time Machines Still Over the Horizon," February 10, 1994, p. 509.

[102] The issue of the sign of energy density is very important in the analyses of wormhole time machines (see note 135 in Chap. 1), and we'll return to it in the next chapter.

Thus, said Einstein, there are just two possibilities. Either the system properties at B must have been what they are from the very start (even if the measurements at A had not been done) which is the view he held, or there must have been a linkage between the system at A and the system at B such that the wave function collapse at A is instantly transmitted to B to allow the wave function to collapse there as well. Because A and B may be arbitrarily far apart, this second view obviously requires an FTL transmission mechanism,[104] something Einstein called a "spooky action-at-a-distance," a term that eloquently expresses his low opinion of that idea! (Some translations replace *spooky* with *ghostly*, but the negative sentiment remains the same.[105]) For decades the debate between proponents of these two alternatives remained at a metaphysical, non-quantitative level. Then came Bell's paper in 1964.

Bell's theorem mathematically poses the choice between Einstein's hidden variables view and the conventional view of quantum mechanics through the use of an inequality involving certain measurable properties of a system.[106] If these measurements are such that the inequality is violated, then the conventional interpretation of quantum mechanics is vindicated, and Einstein's FTL spooky action-at-a-distance effect simply doesn't exist. Bell's great contribution, then, was to provide the means for removing the debate about quantum mechanics from metaphysics and to place it squarely in the realm of experimental physics.

"All" that needed to be done was to make the required measurements. These technically difficult experimental measurements were eventually performed by the French physicist Alain Aspect and his colleagues at the Institute of Applied Optics of the University of Paris, a decade and a half after Bell showed what had to be done. The results unequivocally support the conventional view of quantum mechanics.[107] Einstein was simply wrong, there are no hidden variables in quantum mechanics, and his spooky action does seem to exist. Does that mean we have, at last, experimental evidence of the possibility of information transfer at FTL speeds?

---

[103] For more on hidden variables, see E. P. Wigner, "On Hidden Variables and Quantum Mechanical Probabilities," *American Journal of Physics*, August 1970, pp. 1005–1009.

[104] For an analysis that argues against an FTL mechanism in quantum mechanics, see G. C. Ghirardi, *et al.*, "A General Argument Against Superluminal Transmission Through the Quantum Mechanical Measurement Process," *Lettere Al Nuovo Cimento*, March 8, 1980, pp. 293–298.

[105] You can find a discussion of the possibility of 'explaining' Einstein's "spooky actions" of quantum mechanics by invoking backward causation in R. I. Sutherland, "Bell's Theorem and Backwards-in-Time Causality," *International Journal of Theoretical Physics*, April 1983, pp. 377–384.

[106] The details are not important here, but a lovely exposition (for the lay person) can be found in Bell's essay "Bertlmann's Socks and the Nature of Reality," in *Speakable and Unspeakable in Quantum Mechanics*, Cambridge University Press 1987. See also M. G. Alford, "Ghostly Action at a Distance: A Non-Technical Explanation of the Bell Inequality," *American Journal of Physics*, June 2016, pp. 448–457.

Well, maybe, but the issue is still hotly debated. The majority of physicists today, I suspect, are probably more perplexed over what Bell's theorem is saying than were over Einstein's original EPR paradox. In those early days one could agree with Einstein and his colleagues, who argued that quantum mechanics was valid *as far as it went*, but a deeper, more comprehensive theory *would* show the existence of hidden variables. However, because of the work by Bell and Aspect it is definitively known that quantum mechanics *as it stands* leads to correct results, results that can be checked in the laboratory. In other words, there is no need for hidden variables and FTL spooky actions cannot be ruled out.

And so, while tachyons and the tachyon antitelephone may be nothing more than a neat science fiction fantasy, just maybe a quantum mechanical Bell antitelephone can't be so dismissed. Indeed, the possibility of using a quantum mechanical FTL effect was once suggested in a letter written by a senior person at an unspecified California think tank (an organization such as, for example, the RAND Corporation) to the Under Secretary of Defense for Research and Engineering at the Pentagon. Here's what the Under Secretary read when he opened that letter: "If in fact we can control the FTL nonlocal effect, it would be possible . . . to make an untappable and unjammable command-control-communication [C^3] system at very high bit rates for use in the submarine fleet. The important point is that since there is no ordinary electromagnetic signal linking the encoder with the decoder in such a hypothetical system, there is nothing for the enemy to tap or jam. The enemy would have to have actual possession of the 'black box' decoder to intercept the message, whose reliability would not depend on separation from the encoder or on ocean or weather conditions."[108]

One can't help but wonder what might have been the Under Secretary's response to that incredible letter, and what sorts of ultra-mega-super-top-secret experiments it may have prompted. I would be willing to bet, if they did occur, that they failed. As one physicist put it, "Up to now nature has covered her tracks pretty well, blocking all possibilities for using the EPR effect for FTL communication."[109] Of course, the think tank letter, as 'farout' as it may initially appear, actually represents a *failure* of imagination, because the backward causation effect of EPR's spooky FTL effect is certainly a 'quantum jump' beyond a mere unjammable submarine C^3 system.

---

[107] A. Aspect, "Experimental Tests of Realistic Local Theories via Bell's Theorem," August 17, 1981, pp. 460–467, and A. Aspect, *et al.*, "Experimental Realization of Einstein-Podolsky-Rosen-Bohm *Gedanken-experiment*: A New Violation of Bell's Inequalities," July 12, 1982, pp. 91–94, and "Experimental Test of Bell's Inequalities using Time-Varying Analyzers," December 20, 1982, pp. 1804–1807, all in *Physical Review Letters*.

[108] See N. D. Mermin in note 99. For more on the enigmatic letter on the FTL submarine C^3 system, see Jack Sarfatti's letter to *Physics Today*, September 1987, pp. 118 and 120.

[109] J. Cramer, "Paradoxes and FTL Communication," *Analog Science Fiction*, September 1988.

5.7 For Further Discussion

Mark Twain, in his last, posthumously published novel *No. 44, The Mysterious Stranger*, incorporated reversed time as the work of a supernatural being. After the being reverses the world's time direction, the narrator tells the reader that "everywhere weary people were re-chattering previous conversations backward . . . where there was war, yesterday's battles were being refought, wrong-end first; the previously killed were getting killed again . . . we saw Henry I gathering together his split skull . . ." Read the novel, and comment on how well (or not) Mark Twain handled reversed time.

In Philip K. Dick's 1956 novel *The World Jones Made*, we read of a prophet who can see a year into the future. As he says, "To me *this is the past*," and then later we are told "He was a man with his eyes in the present [the world's future] and his body in the past [the world's present]." Read the novel, and then argue either for or against the suggestion that Dick was aware of the advanced wave solution in Maxwell's theory.

The physicist Robert Forward (see the sixth *For Future Discussion* in Chap. 3) argued that one way to send messages into the past is to compress a 15-billion-ton asteroid down to the volume of an atomic nucleus, spin it up, and then aim gamma ray bursts through the resulting near-by region of "unhinged time" (see "How To Build a Time Machine," *Omni*, May 1980). This is, of course, 'simply' an artificially constructed Kerr black hole telegraph transmitter (look back at note 114 and related discussion in Chap. 1). Forward, an optimist of the first rank, thought humans would be able to do this before the end of the twenty-first century. It would seem, then, that what should be done *now* is to build gamma ray frequency *receivers* (well within present-day technology) and listen for such messages from the future. The technical details of such receivers wouldn't matter, as long as their design is widely published. That way, the scientists of the future can learn those details by simply reading of them in old, musty library books and journals, and thus will be able to build their transmitters to be perfectly compatible with our old, musty (to them) receivers! Comment on the likelihood of National Science Foundation funding becoming available to build such receivers.

Suppose a time traveler goes into the future and, while there, discovers that there is an older version of himself living in the home that has been in his family for generations. Explain why this implies that the time traveler will eventually return to the present. Suppose, instead, that after the time traveler arrives in the future he decides to remain in the future, and *not* to return. Explain why this implies there will *not* be an older version of himself living in the family home. In both cases, assume the MWI does *not* apply, that is, assume that there is just a single time line.

One well-known quantum physicist, David Bohm (1917–1992), wrote the following passage in his book *The Special Theory of Relativity* (W. A. Benjamin 1965), concerning the possibility of sending messages into the past: "In effect, S could communicate with his own past [self, M] . . . and tell his past self [M] what his future is going to be. But on learning this M could decide to change his actions, so that his future . . . would be different from what his later self [S] said it was going to be. For example, the past self could do something that would make it impossible for the future one to send the signal. Thus, there would arise a logical self-contradiction." Do you think most physicists, writing today more than 50 years after Bohm, would repeat his words?

The role played by quantum mechanics in time travel studies is broad, deep, profound . . . and mysterious. What I mean by this is nicely illustrated by the final paragraph in a paper by Stephen Hawking ("Quantum Coherence and Closed Timelike Curves," *Physical Review D*, November 15, 1995, pp. 5681–5686). There he wrote "Personally, I do not believe that closed timelike curves will occur, at least on a macroscopic scale. I think that the chronology protection conjecture will hold and that divergences in the energy-momentum tensor will create singularities before closed timelike curves appear. However, if quantum gravitational effects somehow cut off these divergences, I am quite sure that quantum field theory on such a background will show loss of quantum coherence. *So even if people come back from the future, we will not be able to predict what they will do* [my emphasis]." What do you think Hawking meant by his final line? If "people come back from the future" and tell us what they did while in the

(continued)

future, then what's wrong with their memories that causes us to fail to be able to predict what they *will* do? Or, is there perhaps nothing wrong with their memories and Hawking is instead arguing that the future experienced by the returned time travelers will not be the future when *we* 'get there'? If that's the case, then what are the returned time travelers 'remembering'?

If quantum mechanics is actually slightly non-linear physics (as are many other normally linear physical phenomena at sufficiently high energy levels)—physics is *linear* when *superposition* holds, which means the result of two inputs is the sum of the individual outputs resulting from application of the individual inputs—and if one accepts the MWI concept, then at least two physicists (**PHYSICISTS1**) claim to have shown that one could communicate not just with our past, but also with the many pasts in the ever-splitting branches of the many worlds. Another physicist (**PHYSICIST2**) wrote a very funny illustration of what that might be like. Yet another physicist (**PHYSICIST3**) suggested that non-linear quantum mechanics might actually allow one to take *photographs* of the many-worlds. Of that, a physicist (**PHYSICIST4**) wrote (without any exaggeration) that such an achievement would be "perhaps the most amazing discovery in the history of science, indeed in the history of mankind." Or, to quote yet another physicist (**PHYSICIST5**), "interworld communication would lead to truly mind boggling possibilities," some of which have been incorporated in at least one science fiction novel (**SFAUTHOR**). Read the physicists' papers, and the novel, and then summarize with your own commentary.

PHYSICISTS1: N. Gisin, "Weinberg's Non-linear Quantum Mechanics and Superluminal Communication," *Physics Letters A*, January 1, 1990, pp. 1–2, and J. Polchinski, "Weinberg's Non-linear Quantum Mechanics and the Einstein-Podolsky-Rosen Paradox," *Physical Review Letters*, January 28, 1991, pp. 397–400.

PHYSICIST2: J. G. Cramer, "Quantum Telephones to Other Universes, to Times Past," *Analog*, October 1991.

PHYSICIST3: D. Albert, "How to Take a Photograph of Another Everett World," *Annals of the New York Academy of Sciences*, December 30, 1986, pp. 498–502.

PHYSICIST4: M. A. B. Whitaker, "On the Observability of 'Many Worlds'," *Journal of Physics A*, July 11, 1985, pp. 1831–1834.

PHYSICIST5: R. Plaga, "On a Possibility to Find Experimental Evidence for the Many-Worlds Interpretation of Quantum Mechanics," *Foundations of Physics*, April 1997, pp. 559–577.

SFAUTHOR: J. P. Hogan, *Paths to Otherwhere*, Baen 1996.

One upon a time, FTL tachyons (and their associated into-the-past transmissions of information) were strictly in the province of science fiction. In recent years, however, such doings have moved into mainstream fiction, as well, with the most recent (as I write) example being the man-of-action novel by Patrick Lee, *Signal*, St. Martin's Press 2015. (Tachyons are also mentioned in the 2015 film *Tomorrowland*.) That novel is set in modern times, not in the future; its hero is a retired soldier who now works as a self-employed house-flipper. His is definitely not a futuristic science fiction world. Until, that is, be becomes involved with a radio-like gadget that receives signals from 10 h, 24 min in the future. As the novel progresses we eventually learn that the gadget is based on German electronics technology that was being tested in a remote lab in northern Algeria, near the end of World War II. When that lab was overrun by a small American force the equipment was destroyed, but not before one of the Americans heard the gadget playing a song titled "She Loves You" along with the word *yeah* repeated numerous times. He didn't know what that meant until, 20 years later, he watched the Beatles' first American appearance on *The Ed Sullivan Show* TV program, and so suddenly realized that in 1944 he had heard a song that hadn't been written yet! That gadget is at the center of a modern-day, renewed Nazi effort to conquer the world, and there is much 'you've seen it all before' chasing, shooting and other 'James Bond' types of action in the novel, but the author *has* been quite inventive in treating time paradoxes. He does talk a lot about 'changing the future,' worries confusingly about 'changing the past,' and mistakes neutrinos for tachyons, but, still, if one is willing to overlook such issues it *is* an entertaining read. In particular, while the gadget's inherent range to the future is limited to ten-plus hours, the author describes a clever way to arbitrarily extend that value. Read *Signal*, and then describe and critique the method outlined in the novel.

The Wheeler-Feynman assumption of continuity already had a distinguished history in mathematics long before they invoked it in their physics resolution of bilking paradoxes. (Both men were very good mathematicians, and certainly knew what I am about to tell you here.) Imagine a man who is about to walk up a hill, starting at A (the base of the hill) and ending at B (the top of the hill). You know nothing of *how* he walks (perhaps at times he stops for a while, other times he walks slowly, sometimes he walks briskly, perhaps at times he even walks back *down* the hill). All you know is that, starting from A at 10 o'clock in the morning, he arrives at B at 11 o'clock. That is, the walk up

(continued)

the hill takes exactly 60 min. He camps overnight at B and then, the next morning, at exactly 10 o'clock, he walks back down the hill along the same path he followed during his ascent the previous day. He arrives at A at 11 o'clock. That is, the return trip takes exactly 60 min. Again, you know nothing of the details of how he makes the descent. Prove that there is at least one spot on the path that he passes at exactly the same time during his descent as he passed it during his ascent the previous day. Hint: No complicated equations are required. Indeed, no math at all is needed. Just sketch the appropriate, general graphs of the man's ascent versus time, and of his descent versus time, and invoke continuity. That is, sketch the distance (as measured along the path) that he is from A versus time for both the ascent and the descent.

Chapter 6
The Physics of Time Travel: II

> *"It is very sad to see valuable minds writing such a pile of unmitigated bullshit."*
>
> —not all physicists think time travel is worthy of study.[1]

6.1 Faster-than-Light into the Past

> "Faster-than-light travel remains a coherent, and possible concept, even though it is forbidden by relativity theory."
>
> —a philosopher makes a physics mistake.[2]

So far we have limited our consideration of relativity theory to speeds below the speed of light—that is, to the condition $v < c$, where v is the relative velocity of two reference frames. There was nothing, however, in the derivation of the Lorentz transformation equations discussed in Chap. 3 that actually used that self-imposed constraint. So, just what, in fact, *does* happen for $v > c$? This is not an empty question, because the second half of the above quote that opens this section is simply not true. That isn't to say we can have FTL for free; there *is* a high price to pay, that of causality violation (although, if you are a fan of time travel, it's a price you are probably happy to pay). If a material object goes FTL, then the mathematics seems to say that the object could travel into the past, just as the caped crusader does in the first (1978) *Superman* movie, in order to change the past (to save Lois Lane from dying in an earthquake). In addition, the mathematics also seems to say that if a signal bearing information could achieve FTL, then that information, too, would travel back into the past (see Fig. 6.1).

---

[1] This rather blunt comment (reported in *Physics World*, December 2009, p. 3) was prompted by a suggestion, from two other physicists, that the Higgs boson might ripple backward through time and thereby stop CERN's Large Hadron Collider from creating the long-sought particle in the first place.

[2] G. Robinson, "Hypertravel," *Listener*, December 17, 1964, pp. 976–977, the printed version of a lecture to the British Association for the Advancement of Science.

© Springer International Publishing AG 2017
P.J. Nahin, *Time Machine Tales*, Science and Fiction,
DOI 10.1007/978-3-319-48864-6_6



Fig. 6.1 A math-free proof that there can be no closed loops in time (that is, no time travel to the past if $v > \mathrm{c}$ is forbidden) in flat Minkowski spacetime, the spacetime of the special theory of relativity. Such a conclusion is far less clear in the curved spacetimes of the general theory of relativity. Figure reproduced by the kind permission of Serguei V. Krasnikov (Polkovo Central Astronomical Observatory in St. Petersburg, Russia), from his 2003 paper "Time Machine (1988–2001)"

The original thinking along these lines visualized such an FTL signal as a modulated beam of tachyons, as mentioned in the previous chapter. In addition to tachyons not having been experimentally observed, even after intense searches for them, there are several theoretical objections (in addition to the bilking paradox problem discussed in the previous chapter) to the likelihood such FTL particles exist.[3] For example, the relativistic expressions for the energy and momentum of a particle with rest mass m_0 moving with speed v are, respectively,

$$E = \frac{m_o c^2}{\sqrt{1 - (v/c)^2}} \qquad \text{and} \qquad p = \frac{m_o v}{\sqrt{1 - (v/c)^2}}.$$

For $v > c$ the radicals in these expressions become imaginary, whereas E and p must always be real-valued (because they can be observed and measured as a result of the interactions the particle has with other matter). The energy and momentum can regain the property of being real-valued if we write $m_0 = \mu\sqrt{-1}$ (that is, $m_0^2 = -\mu^2$) for a tachyon, where μ is the positive, real-valued (but unobservable) meta-mass (that is, $m_0^2 < 0$). This is a radical proposal, of course, (as it is $m_0^2 > 0$ that we are used to; as a Russian mathematician romantically put it, "What binds us to space-time is our [positive] rest mass, which prevents us from flying at the speed of light, when time stops and space loses meaning. In a world of light there are neither points nor moments of time; beings woven from light would live ‘nowhere’ and ‘nowhen’; only poetry and mathematics are capable of speaking meaningfully about such things.”[4].

---

[3] See, for example, "More About Tachyons," *Physics Today*, December 1969, pp. 47–52, a collection of letters received by the journal from its readers. The 'DeWitt Gambit,' mentioned in the previous chapter, was first proposed in one of those letters.

Well, perhaps, but let’s continue to pursue the physics of tachyons, at least for a while. It can be shown[5] that the energy and momentum of the tachyon are given by

$$E = \frac{\mu c^2}{\sqrt{(v/c)^2 - 1}} \quad \text{and} \quad p = \frac{\mu v}{\sqrt{(v/c)^2 - 1}}.$$

An interesting consequence of this is that if tachyons *lose* energy, they *speed up*, an observation first made by the German physicist Arnold Sommerfeld (1868–1951) in 1904.[6] This means that if there is a mechanism for continuous energy loss, such as Cerenkov radiation,[7] then tachyons will spontaneously accelerate without limit to *infinite speed*! Curiously, while the above expressions for E and p show that, as $v \to \infty$, tachyons would possess *zero* energy, they would nonetheless have a *non-zero* momentum of μc.[8]

To see how backward time travel and FTL are connected, it is useful to establish a geometrical interpretation of the Lorentz transformation. As stated in Chap. 3, if the x', t’ system is moving with speed v in the x (or x’) direction relative to the x, t system, then

$$x' = \frac{x - vt}{\sqrt{1 - (v/c)^2}} \quad \text{and} \quad t' = \frac{t - vx/c^2}{\sqrt{1 - (v/c)^2}}.$$

---

[4] Yu I. Manin, *Mathematics and Physics*, Birkhäuser 1981, p. 84.

[5] L. Parker, “Faster-Than-Light Inertial Frames and Tachyons,” *Physical Review*, December 25, 1969, pp. 2287–2292.

[6] The consideration of FTL particles already had a long history *before* tachyons were specifically named. You can find late nineteenth century (1888–1889) theoretical analyses of electrically charged FTL particles in the writings, for example, of the English mathematical electrical engineer Oliver Heaviside (1850–1925): see my biography *Oliver Heaviside: the life, work, and times of an electrical genius of the Victorian Age*, The Johns Hopkins University Press 2002, pp. 124–126.

[7] Cerenkov radiation is the energy radiated when a charged particle exceeds the speed of light *in the medium through which it travels*. Since the speed of light *in water* is less than c, it is perfectly okay with special relativity to exceed the speed of light in water, and in fact this commonly occurs for the energetic electrons produced by submerged atomic reactors (swimming pool reactors). The resulting radiation is observed as a blue glow. The radiation is named after the Russian physicist Pavel Cerenkov (1904–1990)—for which he received a share of the 1958 Nobel physics prize—but in fact Heaviside (previous note) had predicted it more than a decade before Cerenkov was born.

[8] This (theoretical) property of tachyons (if they exist) could (perhaps) be used (maybe) to build a revolutionary (to say the least) new rocket propulsion system: see J. Cramer, “The Tachyon Drive: Infinite Exhaust Velocity at Zero Energy Cost,” *Analog*, October 1993.

These equations make sense for the case of $v < c$, and we will retain this condition for our two relatively moving *frames of reference*: these frames are the *worlds* of two *human* observers, observers that we'll take to always be *sub*luminal. As one physicist so nicely put it, "The assumption that observers move faster-than-light goes beyond superluminal signaling,"[9] as such observers would have to be thought of as being built not out of flesh-and-blood, but rather out of tachyons.[10] We'll reserve the symbol w to denote the speed of an FTL particle.

Now, recall what we mean by any line parallel to the x-axis; it is a line with a fixed time coordinate. Such a line is a *cosmic moment* line, with the equation $t =$ constant. Similarly, for the moving system we would write the equation of a cosmic moment line as $t' =$ constant which, after the Lorentz transformation is applied, is equivalent to

$$t - \frac{vx}{c^2} = \text{constant.}$$

In particular, the x'-axis ($t' = 0$ cosmic moment line), which passes through the point $x = 0$ at $t = 0$, has the equation

$$t = \frac{vx}{c^2} = vx$$

with the usual convention of $c = 1$.

In a similar way, recall what we mean by any line parallel to the t-axis; it is a line with a fixed space coordinate. Such a line is the world line of a stationary particle in the x, t frame, with the equation $x =$ constant. Similarly, for the moving system we would write $x' =$ constant as the equation of the world line of a particle stationary in that system. From the Lorentz transformation, this is equivalent to

$$x - vt = \text{constant.}$$

In particular, the t'-axis (which is the $x' = 0$ world line of a particle stationary at the origin of the moving system) passes through the $x = 0$, $t = 0$ point, and it has the equation

$$x = vt.$$

Thus, superimposed spacetime coordinate axes for the two frames look like those shown in Fig. 6.2. That is, the relative motion of the two frames results in a

---

[9] K. Svozil, "Time Paradoxes Reviewed," *Physics Letters A*, April 3, 1995, pp. 323–326.

[10] Science fiction, however, *has* (since the early days of pulp) enthusiastically embraced FTL human travel. In Larry Niven's story "At the Core" (*If*, November 1966), for example, we read of a manned spacecraft that travels 60,000 light years to the center of our own Milky Way Galaxy, and then back, at a speed 420,000 times that of light. As the pilot says (in a grand understatement), "That's goddam fast." Perhaps there is a way to make *some* sense of such an adventure, with the so-called *warp drive* (a'la *Star Trek*), which we'll take-up briefly at the end of this chapter.



Fig. 6.2 Spacetime coordinate axes rotation by relative motion

rotation of the spacetime axes; but it is a strange sort of rotation, with *opposite* senses for the space and time axes. That is, the *x*' and *t*' axes rotate *towards* each other, as shown in the figure, to make equal angles (α) with the *x* and *t* axes, respectively, where

$$\alpha = tan^{-1}(v).$$

If we limit the moving frame (the frame of a moving observer) to subluminal speeds ($0 \leq v < 1$), then

$$0 \leq \alpha < 45^\circ.$$

At the speed of light ($v = 1$) $\alpha = 45^\circ$ and so the x' and *t*' axes coincide—time and space have become indistinguishable.

It is important to realize that observers in either system would measure the same speed for a photon; that is, each would see the world line of a photon as a line with slope 1. This view of the world line of a photon is literally built into the Lorentz transformation because one of Einstein's fundamental postulates for special relativity is the invariance of the speed of light. The truth of this statement for the x, t system is obvious from Fig. 6.2. It is, perhaps, not so obvious with the x', t' system because of the non-perpendicular axes (as shown in the figure) for that system. In Fig. 6.3 the world line of a photon is shown in both systems. In that figure we emit the photon at $x' = 0, t' = 0$, and we later measure its coordinates at point A to be $x' = x'_A$ at time $t' = t'_A$. Note carefully how this is done. We draw lines from point A parallel to the x' and t' axes until they intersect the t' and x' axes, respectively. This is similar to the way we would get the spacetime coordinates of A in the more familiar x, t system, where we would draw lines parallel to the *x* and *t* axes.

It should now be obvious that x'_A and t'_A have the same extension, just as they do in the unprimed system, so

Fig. 6.3 Invariance of the world line of a photon



$$\frac{x'_A}{t'_A} = \text{the speed of light}$$

The speed of light is the only invariant speed under the Lorentz transformation. Indeed, the modern approach to special relativity emphasizes this invariance as the central property of the speed of light, rather than the idea of the speed of light being a limiting speed.

This geometrical interpretation of the Lorentz transformation lets us quickly make another interesting (one, I think, not at all obvious) observation: If a particle is faster than light in the x, t system, then there exists a subluminal x', t' system in which the particle is *infinitely* fast. Figure 6.4 shows the world line of an FTL particle in the x, t system (which is, of course, *below* the world line of a photon; that is, the particle's world line is spacelike). Suppose the FTL particle has speed $w > \mathrm{c}$ such that its world line makes angle β with the x-axis. If we now pick v, the speed of the moving x', t' system to be such that $\alpha = \beta$, then the x'-axis will coincide with the world line of the particle, and so the particle will appear to an observer in the x', t' system to be everywhere at once—that is, to be infinitely fast. We have, then,

$$\beta = tan^{-1}(v) = tan^{-1}\left(\frac{1}{w}\right)$$

or $v = 1/w$, which seems to be dimensionally wrong. Recall, however, that with our convention of $c = 1$, the v in this result is a *normalized* speed. To return to the units of everyday use, simply replace v with v/c and w with w/c; this transforms our result to

$$\frac{v}{c} = \frac{c}{w} \quad \text{or} \quad v = \frac{c^2}{w}\cdot$$



Fig. 6.4 World line of an FTL particle

We can, of course, turn this result around. If an FTL particle moves with speed w in the x, t frame, then to an observer in the x', t' frame moving with subluminal speed v, the particle will appear to be infinitely fast if $w = c^2/v$. A particle with $w > c^2/v$ is said to be not just be superluminal, but *ultra*luminal.

If a particle has infinite speed if $w = c^2/v$, then what physically happens if w is greater than c^2/v? The answer is easy to see from a spacetime diagram, as in Fig. 6.5, where the x' and t' axes have been extended back to negative values. In that figure I have labeled two arbitrary events A and B on the world line of an ultraluminal particle (and so it lies below the x' axis), and have shown the spacetime coordinates of each event in both the x, t and x', t' frames. For the x, t frame we see that A is related to B by the relations $x_A' < x_B'$ and $t_B' < t_A'$; that is, the time order of A and B is reversed for an observer in the x', t' frame. To that observer, the particle appears to be traveling backward in time!

But this isn't quite the end of the story. Following the approach of two pioneering tachyon physicists,[11] we note that if the energy of a particle in the stationary system is E, then the energy as measured in the moving system is given by[12]

---

[11] O. M. Bilaniuk and E. C. G. Sudarshan, "Causality and Space-like Signals," *Nature*, July 26, 1969, pp. 386–387.

[12] The expression for E' is the result of applying the Lorentz transformation to E. You can find all the details of that worked out in A. P. French, *Special Relativity*, W. W. Norton 1968, pp. 208–210.



Fig. 6.5 World line of an *ultra*luminal particle

$$E' = \frac{1}{\sqrt{1 - \left(\frac{v}{c}\right)^2}} \frac{\mu(c^2 - \mathrm{wv})}{\sqrt{(w/c)^2 - 1}}$$

Note that sign of E' switches from positive to negative when w (the speed of the particle) exceeds c^2/v, which is precisely the condition for the particle to be ultraluminal and so traveling backward in time (as seen in the primed system). That is, negative energy moving backward in time in one system is positive energy moving forward in time in another. This is, in fact, the original motivation for the RP (reinterpretation principle) discussed in the previous chapter, and the claim was, at one time, that the RP was just what was needed to 'explain' the paradoxical implications of time travel. This is not the majority view today, however, and a number of physicists have been quite inventive in constructing scenarios with causal paradoxes that the RP clearly fails to 'explain.'

For example, the Princeton physicist Shoichi Yoshikawa (1934–2010), in a letter to *Physics Today* (see note 3), was able to create a scenario which *uses* the RP to arrive at a causal paradox. In his construction, the RP allows an observer to transmit an ultraluminal tachyon to a remote observer at time $t = 0$, and to receive a reply from that observer at $t < 0$. This obviously sets-up the possibility of a bilking paradox in which the original observer, upon receiving the $t < 0$ tachyon, then decides *not* to transmit the $t = 0$ tachyon. What makes Yoshikawa's paradox a particularly troublesome paradox is that the RP is the culprit, not the savior.

6.2 Tipler's Rotating Cylinder Time Machine

> "… within forty-eight hours we had invented, designed, and assembled a chronomobile. I won't weary you with the details, save to remark that it operated by transposing the seventh and eleventh dimensions in a hole in space, thus creating an inverse ether-vortex and standing the space-time continuum on its head."[13]
>
> —this is almost surely *not* the way to build a TM (time machine)

As discussed at the start of this book, the first endorsement of the reasonableness of physicists talking about plausible, scientific time travel, began with Gödel's discovery of closed timelike lines in the mathematics of certain rotating universe models. Such models had been studied as early as 1924 by the Hungarian physicist Cornelius Lanczos (1893–1974), a quarter century before Gödel, but it was Gödel who made explicit the possibility a rotating universe might allow time travel. His realization of time travel as an *inherent* property of a rotating universe is an illustration of a *weak* TM, while what is the central interest concerning time machines (in physics *and* in science fiction) is a *strong* TM. That is, in time machines that can be *intentionally constructed* by manipulating mass-energy in a finite (what physicists call a *compact*) region of spacetime to *create* closed timelike lines where none existed before the manipulation began. Interestingly, the fundamental physical idea behind Gödel's weak TM is the same underlying idea behind the first strong TM, Tipler's rotating cylinder discussed back in Chap. 1 (strictly, of course, only a *compact* TM if the cylinder can be of *finite* length).

The one result from general relativity that we'll use here (without proof) is that the rotation of matter causes a distortion of spacetime that results in the 'tipping over' of light cones, with the future half tilted in the direction of motion. If you imagine a point in the universe about which the rotation takes place, then this tipping effect increases with the radial distance from that point.[14] The fact that rotating masses tip light cones over in the direction of rotation was discovered very early in the history of general relativity (1918), by the Austrian theoreticians Josef Lense (1890–1985) and Hans Thirring (1888–1976). Originally (and naturally) called the *Lense-Thirring effect*, it now generally goes by the name of the *dragging of inertial frames effect*, and it plays a central role in the weak Gödel and the strong (maybe) Tipler time machines. Here's how.

At a certain critical distance from the rotation center (more on this in just a bit), the future half of the light cone at a given point in spacetime will be sufficiently tilted so as to enter the past half of similarly tilted light cones at nearby spacetime points This is illustrated in Fig. 6.6,[15] which shows a circular chain of tilted light

---

[13] L. Sprague de Camp, "Some Curious Effects of Time Travel," in *Analog Readers' Choice*, Dial 1981.

[14] For a picture of this, see S. W. Hawking and G. F. R. Ellis, *The Large Scale Structure of Spacetime*, Cambridge University Press, 1973, p. 169.

[15] Adapted from D. B. Malament, "'Time Travel' in the Gödel Universe," *Proceedings of the Philosophy of Science Association* 1984, pp. 91–100.



Fig. 6.6 Time traveling through tilted light cones in a rotating universe

cones in a rotating universe. Because light cones are tilted by a rotation-induced twisting of spacetime, a traveler can move around a circular path on a trip that is always directed into his *local* future but nonetheless end-up in his own *global* past, without ever going faster than light. This kind of round trip in spacetime, with a trajectory that winds back into the past without ever becoming spacelike, is a closed timelike curve.

From Fig. 6.6 it should be clear how a time traveler, beginning at A, can weave his way along a circular path (this path needs to have a radius at least as great as the critical value mentioned earlier) to B to C to . . . that brings him back into the *past* half of the light cone at A. The traveler's world line is always inside the local light cone; that is, the world line of the time traveler is always timelike, and never FTL. These timelike curves are present in the rotating spacetime from the very beginning of the spacetime, and were not *created* (certainly not by humans) by conscious intent.

You can see how this works mathematically by taking the spacetime metric for Gödel's universe (with, as usual, the convention that the speed of light $c = 1$):

$$(ds)^2 = (dt)^2 - (dr)^2 - (dy)^2 + \sin h^2(r)\left[\sin h^2(r) - 1\right](d\phi)^2 \\ + \sqrt{2}\sin h^2(r)(d\phi)(dt)$$

where t, r, y, and ϕ are cylindrical coordinates in four-dimensional spacetime. Now, imagine that our adventurer's world line is the helical curve r=constant, $y = 0$, and $t = -\alpha\phi$: if we take the time axis as vertical then the time traveler's world line is a vertical helix in spacetime. For this curve, $dr = \mathrm{dy} = 0$ and $dt = -\alpha d\phi$. This last differential means, in particular, that whatever the sign of the constant α, we can choose that one of the two senses of movement in the spatial ϕ dimension that gives $dt < 0$.

Continuing, we have

$$(ds)^2 = \left[\alpha^2 - 2\sqrt{2}\alpha sinh^2(r) + \sin h^2(r)\left(\sin h^2(r) - 1\right)\right](d\phi)^2$$

or, upon letting $u = \sinh(r)$ we have

$$(ds)^2 = \left[\alpha^2 - 2\sqrt{2}\alpha u^2 + u^2\left(u^2 - 1\right)\right](d\phi)^2.$$

Now, for $\alpha = 0$ we have

$$(ds)^2 = u^2\left(u^2 - 1\right)(d\phi)^2$$

which is greater than zero if $u > 1$. This condition holds if $\sinh(r) > 1$, that is, if r is a constant greater than $\ln\left(1 + \sqrt{2}\right)$. In other words, for r sufficiently large (and now we know the critical value for r) we have $(ds)^2 > 0$, the required condition for a timelike spacetime interval. By continuity, then, we will continue to have $(ds)^2 > 0$ even with some small positive or negative value of α different from zero. Because ϕ is a periodic coordinate (we identify $\phi = 0$ with $\phi = 2\pi$), as the traveler moves along the curve she returns repeatedly to the same spatial points, but her time coordinate is increasingly negative. That is, she is traveling into the past. Note, once again, that in Gödel's universe this property holds only for orbits with radii greater than a certain minimum.[16]

Tipler's rotating, infinitely long cylinder is a mechanism for artificially producing the tipped-over light cone effect, thus *creating* closed timelike curves. Figure 6.7, taken from Tipler's Ph.D. dissertation,[17] shows how the cylinder works. The cylinder is represented by the central vertical axis. Far away from the cylinder the light cones in spacetime are upright, but as we move inward they tip over, the future halves opening up into the direction of rotation. (Only the future halves of the light cones are shown.) This direction, which is the direction that far away from the cylinder measures *space*, near the cylinder measures *time* (just as in the Gödelian universe). That is, there has been a dimension reversal! This fantastic possibility has found its way into science fiction, as in Stephen Baxter's 1995 novel *The Time Ships*, wherein the Victorian narrator says "If only one could *twist about* the Four Dimensions of Space and Time — transposing Length with Duration, say — then one could stroll through the corridors of History as easily as taking a cab in the West End!"

To travel back in time, therefore, all the time traveler need do is leave Earth and approach the cylinder until she is near enough to be in the tipped-over region of spacetime. Then she would follow a helical path around the cylinder and could

---

[16] There are other solutions to the Einstein gravitational field equations that have closed timelike lines at *any* radius, no matter how small: see M. J. Reboucas, "A Rotating Universe with Violation of Causality," *Physics Letters A*, March 5, 1979, pp. 161–163.

[17] F. J. Tipler, *Causality Violation in General Relativity*, University of Maryland 1976.


t
ϕ
Direction of rotation
Light cones begin to tip over in ϕ direction
Light cones include circle, which is a closed timelike line
x
y
Light cones tangent to circle

Fig. 6.7 The future halves of light cones point almost entirely in the $+t$ direction far from rotating matter; they begin to tip over as the matter is approached. Note that there is a helical timelike path that moves locally into the *future* in the $-t$ direction, that is, it goes into the past as seen by an observer far from the rotating matter (The world lines of rotating matter are helixes in the $+t$ direction)

spiral along the negative time direction as far back in time as desired (but no further back than to the moment of the cylinder's creation). This motion is such that the time traveler is always moving into her local future, via the tipped-over light cones. Finally, she would withdraw from the cylinder and return to Earth—in the past. The time traveler had better be a good space navigator, of course, because Earth won't be where she left it!

6.3 Thorne's Wormhole Time Machine

> "This fact reinforces the authors' feeling that [closed time loops] are not so nasty as people generally have assumed."[18]

The spacetime wormhole is presently the most promising of the approaches that have been advanced for building a time machine. Gödel rotated the entire universe in 1949, and Tipler 'reduced' the problem in 1974 to 'merely' spinning a cylinder of infinite length. In 1988 Kip Thorne scaled things down even more, this time to other extreme. His idea calls for pulling a wormhole on the scale of the Planck length out of the topologically multiply connected quantum foam that spacetime is and then enlarging it (somehow) to human scale, all the while stabilizing it against self-collapse, and then finally using the time dilation effect of special relativity to alter time at one mouth of the wormhole as compared to the other mouth. What a mouthful! What, you almost surely wonder, does all that mean?

First of all, what's 'quantum foam'? The term refers to the idea that the topology of spacetime is *not* a smooth, continuous manifold, but rather (if you look close enough) is a seething 'ocean of fluctuations' that is always changing, changes on the scale of the Planck length (look back at Sect. 1.5). What does *that* mean? Like the ocean surface-in-the-large, large-scale spacetime is simply connected. But just as one sees all sorts of transient structure as one looks at the water more closely (beginning with macroscopic waves and then proceeding downward to the bubbly foam on the waves), spacetime too displays an ever-changing connectivity-in-the-small.[19] That is the 'quantum foam.'

Wormholes have been around in physics for decades, but they have always been thought to be so unstable as to exist only on paper in the mathematics of general relativity. In an analysis[20] published more than half-a-century ago, for example, wormhole instability was shown to be so severe that not only would a human have no chance in getting through one, but also not even a single speedy photon could do so. Even at the speed of light, the photon could not zip through a wormhole before being trapped inside ("pinched off") in a region of infinite spacetime curvature. Wormholes would simply collapse too quickly after formation for even the so-called ultimate speed to save the traveler. Indeed, the presence of mass-energy inside a wormhole actually *accelerates* its collapse. The physics of wormholes, it seemed, made them simply untraversable.

---

[18] The conclusion of a mathematical demonstration that time travel by wormhole does not conflict with the conservation of energy: see J. L. Friedman *et al*., "Cauchy Problem in Spacetimes with Closed Timelike Curves," *Physical Review*, September 15, 1990, pp. 1915–1930.

[19] Not all accept this view. See, for example, A. Anderson and B DeWitt, "Does the Topology of Space Fluctuate?" *Foundations of Physics*, February 1986, pp. 91–105.

[20] R. W. Fuller and J. A. Wheeler, "Causality and Multiple Connected Spacetime," *Physical Review*, October 15, 1962, pp. 919–929.



Fig. 6.8 These sketches are unavoidably misleading, being two-dimensional renditions of wormholes that connect two places in a three-dimensional space. Time machine wormholes, on the other hand, connect two places in a four-dimensional spacetime. In particular, the mouths of the wormholes are not 'depressions' into which the time traveler's rocket ship plunges, but rather would appear to be three-dimensional spheres. The wormhole in (**a**) connects two disjoint universes, while those in (**b**) and (**c**) are connections between two places in the same universe. As shown in these last two cases, the wormhole 'handle' can be either long or short, compared to the external distance between the wormhole mouths

And anyway, how would one gain access to a wormhole in the first place? As Thorne and one of his students suggested,[21] one might perhaps imagine someday finding a rotating black hole that mathematically possesses, in its interior, so-called hyperspace tunnels to 'other places'—either in our universe or in other universes (see Fig. 6.8). In the case of a wormhole connecting two places in the same universe, although the external distance in spacetime between the places may be very large (mega-light-years), it is conceivable that the distance *through* the wormhole itself could be very small. The time required to traverse the wormhole, as measured by the traveler's watch might, in fact, be arbitrarily small. This is exciting, but wormholes do not come without some significant problems.

Such problems include the presence of a one-way event horizon, which precludes two-way travel (it seems reasonable to assume that time and space travelers might wish to eventually return), and enormous gravitational gradients (tidal forces) that dismember anything approaching and/or entering the wormhole. These problems have often been conveniently *ignored* in science fiction. For example, in one tale[22] the time machine is in the form of a wormhole time tunnel that time travelers can simply walk through, and in another characters similarly walk back and forth between two openings in a wall that connect the same place in space but separated in time by 160 years.[23] And in an even older story, we read of a time machine (in the form of a hole in spacetime that is a wormhole in everything but name) through which one can literally step from future to past and back again. That story[24] is particularly notable for having introduced the term *mugwump* for a time traveler who uses a time machine wormhole. To paraphrase the tale's time traveler, as he transits the wormhole his "mug" is in the past and his "wump" is in the future.[25]

---

[21] M. S. Morris and K. S. Thorne, "Wormholes in Spacetime and Their Use for Interstellar Travel: A Tool for Teaching General Relativity," *American Journal of Physics*, May 1988, pp. 395–412. This paper was motivated by Thorne's earlier response to a request, from the American astronomer Carl Sagan (1934–1996), for help in making plausible the interstellar travel imagined in his 1985 novel *Contact*.

Now, before going any further, a note on what physicists are referring to when they write of traversable time travel wormholes. Such wormholes are called *Lorentzian* because they have a spacetime metric with the signature $[+, -, -, -]$ (see Sect. 3.5). Further, the wormhole is taken to be *static*, that is, to have no time-varying behavior. The reason for being specific on the nature of time travel wormholes is that there is another type with what is called the *Euclidean signature*: $[+, +, +, +]$, which is not suitable for time traveling. Motion in a Euclidean signature wormhole involves imaginary momentum or proper time, neither of which is physically plausible for a time traveler. However, *if* you can gain access to a Lorentzian wormhole *then*, as two physicists wrote, "if you manage to acquire even one inter-universe traversable wormhole then it *seems* almost absurdly easy to build a time machine."[26]

In response to that fundamental question of how to gain access to a Lorentzian wormhole, Thorne and his students were bluntly honest—they didn't know. Their best suggestion was that "one can imagine an advanced civilization pulling [a] wormhole out of the quantum foam and enlarging it to classical size."[27] A few years later this dramatic idea found its way into a science fiction novel of a far-future alien civilization able to control the energies of constellations of galaxies: "Spacetime is friable. Wormholes riddle the fabric of spacetime on all scales. At the Planck length and below, wormholes arising from quantum uncertainty effects blur the clean Einsteinian lines of spacetime. And some of the wormholes expand to human scale, and beyond — sometimes spontaneously, and sometimes at the instigation of intelligence."[28]

---

[22] R. C. Wilson, *A Bridge of Years*, Doubleday 1991.

[23] M. Leinster, *Time Tunnel*, Pyramid Books 1964.

[24] H. Kuttner, "Shock," *Astounding Science Fiction*, March 1943.

[25] The term's origin is in 19th century politics, as a description of fence-sitters who try to avoid taking a definite position on some controversial topic under debate. For an illustration of wormhole mugwumping, see K. S. Thorne, *Black Holes & Time Warps*, W. W. Norton 1994, p. 500.

[26] C. Barceló and M. Visser, "Twilight for the Energy Conditions?" *International Journal of Modern Physics D*, December 2002, pp. 1553–1560. See also M. Visser, *Lorentzian Wormholes*, AIP Press 1996.

[27] M. S. Morris, K. S. Thorne, and U. Yurtsever, "Wormholes, Time Machines, and the Weak Energy Condition," *Physical Review Letters*, September 26, 1988, pp. 1446–1449.

This isn't easy to visualize, but let's plunge ahead and assume we can "pull" a wormhole out of the quantum foam. If so, then once it is (somehow) inflated the wormhole could be stabilized against collapse by threading it with either matter or fields of stupendous negative (outward) tension—and by *stupendous* I mean *STUPENDOUS*. If b_0 denotes the minimum radius of the wormholes (the size of the so-called *throat* of the wormhole), the tension (radial pressure) at that location must be at least

$$\tau_0 = \frac{3.8}{{b_0}^2} \times 10^{36} \frac{tons}{in^2}$$

where b_0 is expressed in feet.[29] (This expression shows that for a wormhole with a throat radius of several thousand feet, the value of τ_0 is enormous, of the same magnitude as the pressure at the center of the most massive neutron star.) To stabilize a common sort of everyday wormhole, such as a subway tunnel, we can obtain the required tension/pressure by lining the tunnel with iron plates or concrete. But how, for a hyperspace wormhole, do we obtain 'iron plates' that can achieve the required enormous tension? As Thorne and his students observed (note 27) such stuff could only be called "exotic," a term that had appeared a few years earlier in connection with the observed energy density in the throat of a wormhole.[30]

One possible approach to this problem does not use matter at all. If we make b_0 *very* large, then non-material fields will do the job.[31] Indeed, suppose b_0 equals 1 light year (a large wormhole by anybody's standard!). Then τ_0 is 'only' 4000 tons/square inch, and that is achievable by threading the wormhole throat with a magnetic field of 'only' 2,700,000 gauss (five million times stronger than the Earth's field).[32] To generate such a field is not impossible, and present-day experimental, hypervelocity electromagnetic rail guns in development for the US Navy use transient magnetic fields in the mega-gauss range.

---

[28] From S. Baxter's 1993 novel *Timelike Infinity*. That same year the Chinese physicist Liao Liu wrote on how, as a result of a naturally occurring vacuum fluctuation, a wormhole might spontaneously appear: L. Liu, "Wormhole Created from Vacuum Fluctuation," *Physical Review D*, September 15, 1993, R5463–R5464.

[29] The original equation for τ_0 was given in units of dynes/cm^2, with b_0 is expressed in meters (see note 21), but I have converted these units to the more familiar (to the non-physicist) units of tons per square inch, for dramatic purposes, because the units of dynes per square centimeter is so small it's difficult to relate it to anything of everyday significance.

[30] R. Balbinot, "Crossing the Einstein-Rosen Bridge," *Lettere Al Nuovo Cimento*, May 16, 1985, pp. 76–80.

[31] See, for example, Y. Soen and A. Ori, "Improved Time Machine Model," *Physical Review D*, October 15, 1996, pp. 4858–4861, and D. N. Vollick, "How to Produce Exotic Matter Using Classical Fields," *Physical Review D*, October 15, 1997, pp. 4720–4723.

[32] To understand how the calculation of a magnetic field from a pressure requirement is accomplished, note that pressure is dimensionally equivalent to field energy per unit volume, which in turn is given by a well-known result in electromagnetic theory.

As if the stabilization problem wasn't enough of a complication, Thorne and his colleagues (note 27) showed that there is another, even more curious problem. The geometrical requirement that the wormhole interior smoothly connect to the external, asymptotically flat exterior spacetime demands that the wormhole throat flare outward as shown in Fig. 6.8. It turns out that this condition is mathematically equivalent to a requirement that τ_0 exceed the energy density of the throat material[33]; and special relativity, in turn, says that for some timelike observers the energy density will then actually be *negative*. This is a clear violation of the so-called *weak energy condition* (WEC), which says the observed mass-energy density is always non-negative. This is *so* 'obvious' that the WEC was thought, for a long time, to be almost a law of nature. Such a violation is actually not as crazy as it might sound however because, more than half-a-century ago, it was shown[34] that an energy density that is everywhere and everywhen positive is *not* compatible with any quantum field theory that is *local*, as, presumably, will be the yet-to-be-discovered theory of quantum gravity. Over the years since then a variety of other energy conditions have been proposed, such as the *averaged weak energy condition* (AWEC), which says that only the *average* value of the energy density over a complete null geodesic world line has to be non-negative, which leaves open the possibility of *temporary* negativity here, there, then and when.[35]

The traversable, static wormholes studied by Thorne and his colleagues violate even the AWEC (see note 27), however, and in the years since it has become clear to physicists that imposing constraints on the mass-energy density may not be so 'obvious' after all (see note 26). But all may not be lost. Indeed, it has been shown that the violation of the AWEC by traversable wormholes can be made as small as desired, that is, the requirement for the exotic matter required to line a wormhole throat to keep it open can be made as tiny as you want.[36]

Well, tiny the quantity of exotic matter may be but, nonetheless, even a tiny amount of it would be extraordinary weird stuff because a negative energy density can be interpreted as meaning that the exotic material that keeps the wormhole throat open does so by exerting a *repulsive* gravitational force.[37] A repulsive force sounds like a property we'd expect to see associated with *negative mass* and, although such a thing has never been observed (negative matter is *not* anti-matter, which *has* been observed and which does not repel 'normal matter'), it was studied long ago (theoretically, of course) by the English cosmologist Hermann Bondi (1919–2005). Bondi showed[38] that negative mass would indeed have some truly bizarre properties,[39] but there is nothing in general relativity that forbids its possible existence. Wormholes, with negative mass throats, should produce observable effects by which a wormhole *might* be detected. Mathematical analyses of the effect a negative-mass wormhole mouth would have, when crossing the line-of-sight between Earth and a distant star, indicates that there should be an observable *double-spike* in the intensity of the star's light. Astronomical searches for such an optical signature have actually been conducted, with (alas) no success as I write (2017).

---

[33] The condition of τ_0 exceeding the energy density in the throat is, in fact, the technical definition of *exotic*—see note 30. In everyday situations, the exotic condition is never even remotely approached. For example, the maximum tension necessary to pull a piece of steel apart—the so-called *tensile strength*, about 100,000 pounds per square inch—is a trillion times less than the mass-energy density of steel.

[34] H. Epstein, V. Glaser, and A. Jaffe, "Nonpositivity of the Energy Density in Quantized Field Theories," *Il Nuovo Cimento*, April 1, 1965, pp. 1016–1022.

[35] T. A. Roman, "Quantum Stress-Energy Tensors and the Weak Energy Condition," *Physical Review D*, June 15, 1986, pp. 3526–3533.

[36] M. Visser, S. Kar, and N. Dadhich, "Traversable Wormholes with Arbitrarily Small Energy Condition Violations," *Physical Review Letters*, May 23, 2003, pp. 201102-1 to 201102-4.

There is another interesting implication of a repulsive gravitational force, one that proves to be *essential* to the possibility of a wormhole time machine. Just as Einstein's famous prediction (verified in 1919) from general relativity, that star light passing near the Sun's edge is bent *inward* by the Sun's attractive gravitational field, the repulsive, anti-gravity field of a wormhole will cause any light rays traveling through the wormhole to be bent *outward*. That is, a tight, narrow beam of radiation entering a wormhole will emerge *defocused*. This is crucial because, as you'll soon see, a wormhole time machine would otherwise be destroyed by the light from the dimmest candle.

One might take the failure of astronomical searches for a double-spike light signature to mean that wormholes with negative mass throats (thus violating the WEC) simply don't exist. But not so fast. The first hint that the possibility of a negative energy density might not be such a crazy idea occurred as long ago as 1948, with a theoretical prediction made by the Dutch physicist Hendrick Casimir (1909–2000). As pointed out in Chap. 1, the Heisenberg uncertainty principle allows a temporary violation of conservation of energy to occur, with the magnitude of the allowed violation increasing with decreasing time duration. Even in a vacuum, then, with particle/anti-particle creation and annihilation spontaneously and continuously taking place, the *average* energy density being zero does not preclude fluctuations away from zero and so, at times, actually becoming *negative*. What Casimir showed was that if one positioned two perfectly conductive plates parallel to each other, then the normal quantum fluctuations of the energy density in this 'vacuum sandwich' would be altered in such a way as to result in their mutual attraction—and this (tiny) effect was later actually observed.[40]

---

[37] The *strong energy condition* says gravity is always attractive—which is clearly not true in a wormhole throat—and so static, traversable wormholes violate both the weak *and* the strong energy conditions.

[38] H. Bondi, "Negative Mass in General Relativity," *Reviews of Modern Physics*, July 1957, pp. 423–428.

[39] For example, general relativity says that a negative mass will *repel* all other masses (positive *and* negative), whereas a positive mass will *attract* all other masses (positive *and* negative). Imagine, then, a negative mass attached to the nose of a positive-mass spaceship. The spaceship tries to move toward the negative mass, while the negative mass tries to move away from the spaceship. So off they both go into the sky, like a cat chasing its tail. This so-called *reactionless anti-gravity drive*, bizarre as it appears, does not violate either of the conservation laws of energy or momentum. See G. Cavalleri and E. Tonni, "Negative Masses, Even if Isolated, Imply Self-Acceleration, Hence a Catastrophic World," *Il Nuovo Cimento B*, July 1997, pp. 897–903.

What does it mean to 'alter the normal quantum fluctuations'? Consider the creation of a photon and its anti-particle, which is another photon. From the wave interpretation of particles, the parallel plates restrict the photons that appear in the vacuum layer to those that have wavelengths that 'fit' because those wavelengths are submultiples of the plate separation (this requirement follows from the fact that a perfectly conducting plate cannot support a non-zero tangential electric field). Photons with longer wavelengths than the plate separation cannot 'fit' and thus do not appear. That is, the parallel plates have created a boundary condition that has quantized the electromagnetic field. The absence of these 'longer wavelength' photons lowers the average energy density between the plates and, because the average without the plates is zero, the altered average energy density must be negative. Indeed, the more the maximum allowed photon wavelength decreases with decreasing plate separation, the more negative the average energy density becomes in the enclosed Casimir vacuum. The negative energy density manifests itself as an inward directed force per unit area (remember, energy density and pressure are dimensionally equivalent).

The experimental detection of the Casimir effect was a remarkable event in physics. As one mathematician put it, "No worker in the field of overlap of quantum theory and general relativity can fail to point this fact out in tones of awe and reverence."[41] Robert Forward, an imaginative physicist who has appeared in this book earlier as an enthusiastic supporter of time travel, has described how the Casimir force might be used to extract energy literally *from a vacuum*. This is an idea as seemingly impossible as is the plan of one science fiction professor to squeeze energy out of *time*. As he asks his assistant, "But tell me, Bob, isn't that a ridiculous thought? To take time, something intangible, invisible, incomprehensible, and contract it — squeeze it together like a sponge?"[42] The story is fun, but Forward's proposal is that as well—*and* good physics.[43] Now, what does all this have to do with wormhole time machines?

---

[40] A complete presentation of Casimir's analysis, with citations to the original literature, can be found in L. E. Ballentine, *Quantum Mechanics*, Prentice-Hall 1990, pp. 399–403. For an historical, tutorial presentation, including Casimir's personal comments on how he was led to make his discovery, see P. W. Milonni and M.-L. Shih, "Casimir Forces," *Contemporary Physics*, September–October 1992, pp. 313–322.

[41] S. A. Fulling, *Aspects of Quantum Field Theory in Curved Space-Time*, London Mathematical Society 1989.

[42] E. Binder, "The Time Contractor," *Astounding Stories*, December 1937.

[43] R. Forward, "Extracting Electrical Energy from the Vacuum by Cohesion of Charged Foliated Conductors," *Physical Review B*, August 15, 1984, pp. 1700–1702.

Thorne and his colleagues (note 27) proposed to use the Casimir effect to achieve the "exotic condition" *without* matter. Their idea was to place identical, conducting, spherical plates that carry equal electric charges at each end of the wormhole (remember, the wormhole mouths are spherically symmetric). The two identical charges repel each other, but the charge size is adjusted so that the gravitational attraction of the plates precisely cancels the repulsion. They then calculated that the Casimir effect results in a negative energy density sufficient to provide the throat tension necessary to prevent wormhole collapse.

There *are* some weird aspects to this (and perhaps that's no surprise). For example, the analysis assumed that the wormhole length is *very* small compared to its radius (10^{-10} cm long and 200 million miles wide!), with the short length required because it represents the separation of the wormhole plates, and the smaller the separation the more negative the average energy density. (The functional dependence is as the *fourth* power of the separation.) Another problem is the balancing of the electrical repulsion and the gravitational attraction of the wormhole mouth plates, as such a balance is clearly an unstable one. Finally, because the two spherical plates completely fill the wormhole mouths, how would a traveler actually get through the wormhole? The 'answer' was to drill a hole through the plates and hope that wouldn't perturb the Casimir vacuum too much.[44]

All the above litany of the difficulties static, traversable wormholes face in simply existing is certainly daunting, but let's now ignore all that and suppose we actually have a wormhole with both mouths in the same universe. (For use as a time machine, it would seem desirable for the time traveler to remain in his/her own universe!) So, how do we turn the wormhole into a time machine? Interestingly, while it is general relativity that gives us the wormhole, it is special relativity that adds the final touch of backward time travel. We begin by imagining that, somehow, one mouth of the wormhole can be moved with respect to the other mouth. One early suggestion, for example, was to use the gravitational attraction of a large asteroid to 'drag' one end of the wormhole, thereby inducing a time dilation effect.[45]

That is, suppose we have two clocks A and B, one in each mouth of the wormhole. These two clocks, and all other clocks in the flat spacetime outside the wormhole, are initially indicating the same time and running at the same rate. Now, recalling the twin paradox from Chap. 3, let each mouth-clock play the role of one of the twins. Imagine that A and B are now separated because the mouth containing B is placed on board a rocket ship. The rocket ship takes a long, high-speed trip out into space along the straight-line path joining A and B in external space, and then returns, just as described in Sect. 3.5. We then unload the space traveling wormhole mouth (with its clock B) and reposition it at its original location. What is the situation now? We can summarize matters as follows: (1) Clock A, in the non-moving mouth, remains in-step with the local clocks in the space outside the mouth. (2) Clocks A and B, both inside the wormhole, have *not* moved with respect to each other because we are assuming a very short wormhole handle, as in part (b) of Fig. 6.8. We can arrange for the motion of the space traveling mouth (with clock B) to be such that the handle is always short, and so the distance between clocks A and B changes by an arbitrarily small amount. Thus, clocks A and B remain in-step with each other. (3) Clock B, because it has been moving with respect to its external space, arrives back at its starting position reading *behind* (that is, *earlier*) than the clocks outside its wormhole mouth.

---

[44] The very next year it was shown how to construct non-spherically symmetric wormholes to avoid that particular problem: see the two papers by M. Visser, "Traversable Wormholes: Some Simple Examples," *Physical Review D*, May 15, 1989, pp. 3182–3184, and "Traversable Wormholes from Surgically Modified Schwarzchild Spacetimes," *Nuclear Physics B*, December 11, 1989, pp. 203–212.

[45] J. L. Friedman, "Back to the Future," *Nature*, November 24, 1988, pp. 305–306.

For the sake of argument, then, suppose the journey of B is such that there is a two-hour time-slip between clock B and its local, external clocks. Thus, if clock B reads 9 A.M., the clocks outside of mouth B will read 11 A.M. But because clocks A and B are in-step, clock A reads 9 A.M., as do the clocks outside of mouth A. That is, the wormhole connecting mouth A to mouth B is a connection between two parts of the same universe that are two hours apart in time. Now, suppose the journey from mouth A to mouth B can be made through external space in one hour. Then, one could leave mouth A at 10 A.M., rocket to mouth B by 11 A.M., and travel back to mouth A via the wormhole to the starting point—where it is 9 A.M., one hour *before* the trip began! We could, in fact, imagine repeating this process, going back one additional hour for each new loop through the wormhole. One clear restriction, however, is that we could not go back in time to *before* the creation of the wormhole time machine. The wormhole works in the other direction, too. To see this, suppose that the space traveler leaves mouth B at 8 A.M. and rockets through external space to mouth A, arriving at 9 A.M. Entering mouth A, he exits from mouth B (where he started) at 11 A.M., two hours in the future.

Another way to induce a time dilation effect, to convert a wormhole to a time machine, *without moving either mouth*, is to simply place one mouth in an intense gravitational field, that of, say, a neutron star. (Recall, from Sect. 3.3, how gravity influences the time-keeping rate of a clock.) As the physicists who proposed this idea put it, almost *any* interaction with surrounding matter and gravity fields almost inevitably turns a wormhole into a time machine.[46] Others have admitted that the details of the origin of time dilation are probably not issues worth debating, but rather what is called the *back-reaction* is of far more concern.

To understand the back-reaction requires mention of what is called the *Cauchy horizon*, the hyperspace surface in spacetime that separates the region where closed timelike lines can exist, from the region where they cannot exist. The back-reaction is the build-up of unbounded energy levels on the Cauchy horizon, causing its instability and rapid destruction. The name of the horizon comes from the "Cauchy problem"—named after the nineteenth century French mathematician Augustin-Louis Cauchy (1789–1857)—in the theory of partial differential equations. In this theory a Cauchy initial-value problem is said to be well-defined if the initial conditions determine a unique solution, and if a continuous variation in the initial conditions gives a continuous variation in the solution. In that part of spacetime where closed timelike loops are not allowed, backward causation does not occur (by definition) and the laws of physics (all expressed as differential equations) satisfy the Cauchy condition. Outside of this *chronal* region, that is, beyond the Cauchy horizon where physics is *dischronal*, however, the possibility of backward causation raises the possibility of violating the Cauchy condition, and in such a case the Cauchy horizon is also sometimes called the *chronology horizon*.[47]

---

[46] V. P. Frolov and I. D. Novikov, "Physical Effects in Wormholes and Time Machines," *Physical Review D*, August 15, 1990, pp. 1057–1065.

The instability of the Cauchy horizon is caused by radiation that propagates in closed timelike loops that thread through the wormhole on 'straight lines.' This radiation, as shown a half-century ago,[48] builds-up unbounded energy density levels at the horizon, and thus destroys the horizon. Thorne and his colleagues argued that the defocusing effect of their wormhole time machine's repulsive gravity would be sufficient to counter a disruptive energy build-up on the horizon (note 27). Subsequent analyses have examined other possible ways to avoid unbounded energy density on the Cauchy horizon. For example, in one paper[49] it was imagined that a wormhole time machine has had a circular motion induced for mouth B; that is, mouth B orbits around mouth A. The result is that the Cauchy horizon now does seem to be stable, because now there are no fixed, straight-line timelike loops threading the wormhole from A to B to A to B to . . .. That is, B is a 'moving target' and there is no point on the Cauchy horizon where the energy density becomes unbounded.

Yet another approach for achieving the disruption of destructive, circulating energy loops through a wormhole is by placing a spherical mirror between the two mouths of the wormhole. Proposed by the Chinese physicist Li-Xin Li, a Li mirror would divert all closed null geodesics (represent circulating radiation) that potentially thread through the wormhole.[50] Such potentially fatal geodesics would, instead, be scattered back into space, whereas a purposeful traveler could navigate *around* the mirror and thus use the wormhole as a time machine.

---

[47] A classic work on the mathematics of Cauchy problems is J. Hadamard, *Lectures on Cauchy's Problem in Linear Partial Differential Equations*, Dover 1952. There is a curious bit of irony in this. In a section of his book, Hadamard uses spacetime to illustrate one possible four-dimensional space and, in passing, he casually writes "This conception was beautifully illustrated a good many years ago by the novelist Wells in his *Time Machine*." Hadamard wrote his book in 1923, and he would almost certainly have been astonished to have been informed that less than seventy years later his work would play a central role in the non-fictional theory of time machines.

[48] C. W. Misner and A. H. Taub, "A Singularity-Free Empty Universe," *Soviet Physics JETP*, January 1969, pp. 122–133.

[49] I. D. Novikov, "An Analysis of the Operation of a Time Machine," *Soviet Physics JETP*, March 1989, pp. 439–443.

[50] L.-X. Li, "New Light on Time Machines: Against the Chronology Protection Conjecture," *Physical Review D*, November 1994, pp. R6037–R6040.

Cauchy horizon instability from the back reaction is central to Hawking's Chronology Protection Conjecture, discussed in Chap. 1. His analysis (see note 54 in Chap. 1) led him to conclude that a physical entity—the stress-energy tensor—becomes unphysical on the Cauchy horizon. That is, because of time-traveling quantum field fluctuations of the vacuum, that tensor diverges to infinity at the horizon. This results in a failure of that horizon to form in the first place or, if it does form, in the creation of a singularity that 'seals-off' the horizon to any would-be time travelers attempting to gain access to the closed timelike loops beyond the horizon. Others, however, argued that Hawking was mistaken in claiming that the divergence of the stress-energy tensor on the Cauchy horizon will always forbid time travel.

In a study, for example, of a complex-valued spacetime metric (and such a metric *is* allowed in the so-called 'sum over all possible geometries, path integral' approach to the quantum theory of gravity), that has causal and non-causal spacetime regions separated not by a Cauchy horizon but rather by a region of complex geometry, the stress-energy tensor is always physical and diverges nowhere. The complex geometry region plays the same role as the Cauchy horizon, because such a region would, *classically*, mean that the two regions cannot be reached from one another, but via quantum tunneling an observer *could* travel between the two regions.[51] In fact, studies of stress-energy divergence actually have a long history. For example, the effect of an unphysical (infinite) gravitational and/or electromagnetic energy flux had been analyzed *years before* the wormhole time machine studies began.[52] The authors studied the case of a potential traveler to "new worlds" who tries to cross the Cauchy horizon of an electrically charged, non-rotating black hole. An even earlier computer study had already concluded that, for such a traveler, the attempt to cross the horizon "looks liable to prove a dangerous undertaking."[53]

It isn't at all clear, in fact, if a *theoretical* divergence of the stress-energy *is* the signature of a failure of physics. One doesn't need anything as bizarre as a time machine for the stress-energy to diverge *on paper*. It was shown nearly 40 years ago, for example, that such a theoretical divergence occurs for the electromagnetic field near a perfectly conducting boundary.[54] But it is simply the unphysical nature of a "*perfectly* conducting" boundary condition that causes the divergence, not the fact that the field actually exists near a conducting boundary. Similarly, other real-life considerations (quantum gravity) *may* keep the stress-energy physical everywhere in a time machine spacetime.

---

[51] L.-X. Li, J.-M. Xu, and L. Liu, "Complex Geometry, Quantum Tunneling, and Time Machines," *Physical Review D*, November 15, 1993, pp. 4735–4737.

[52] S. Chandrasekhar and J. B. Hartle, "On Crossing the Cauchy Horizon of a Reissner-Nordström Black-Hole," *Proceedings of the Royal Society of London A*, December 8, 1982, pp. 301–315.

[53] M. Simpson and R. Penrose, "Internal Instability in a Reissner-Nordström Black Hole," *International Journal of Theoretical Physics*, April 1973, pp. 183–197.

[54] D. Deutsch and P. Candelas, "Boundary Effects in Quantum Field Theory," *Physical Review D*, December 15, 1979, pp. 3063–3080.



Fig. 6.9 The grandfather paradox in the billiard ball world. A billiard ball approaches mouth A of a time machine wormhole, dead-on center and, just before entering A, it passes without incident through point *I*. The ball then enters A and so exits mouth B in the past, *just in time* to pass through point *I* and *hit its younger self*. This impact knocks the younger ball *away from* A, so we have the familiar paradox of changing the past. That is, the impact did not occur when the ball 'originally' passed through *I* on its way to A and, of course, we also wonder how the ball manages to hit itself after leaving B if it then *doesn't* enter A?

Assuming a wormhole time machine has (somehow) become available, with its Cauchy horizon intact, how do the 'paradoxes' of time travel come into play? In an attempt to study the grandfather paradox, in particular, Thorne and his colleagues studied self-interacting billiard balls traveling backward in time through a wormhole.[55] They used billiard balls—see Figs. 6.9 and 6.10—rather than human time travelers for the same reason Wheeler and Feynman used a pellet and shutter mechanism in their study of advanced electromagnetic waves—to avoid any metaphysical questions about human free will. The central issue for them was the determination of the multiplicity of trajectories for a single, self-interacting time traveling ball, where the Cauchy condition for a well-defined trajectory in spacetime is *unique* self-consistency.

That is, for the trajectory to be well-defined in the Cauchy sense, it was expected there would be exactly *one* consistent trajectory for a self-interacting ball. A multiplicity of zero, of course, would be the physics declaring backward time travel through the wormhole to be nonsense—and that was thought to be a distinct

---

[55] F. Echeverria, G. Klinkhammer, and K. S. Thorne, "Billiard Balls in Wormhole Spacetimes with Closed Timelike Curves: I. Classical Theory," *Physical Review D*, August 15, 1991, pp. 1077–1099. The authors credited the physicist/science fiction writer Robert Forward (who used the same ideas in his 1992 novel *Timemaster*) for motivating their research.



Fig. 6.10 The principle of self-consistency in the billiard ball world. Now the ball, in passing through point I on its dead-on center path toward mouth A of the wormhole time machine, is suddenly hit a grazing blow by another ball that has just shot out of mouth B (and into the past) at an angle. The impact knocks the first ball slightly off its original trajectory, and it enters mouth A slightly off-center. Thus, the ball emerges from B into the past slightly off-center and just in time to glace off itself at I—which explains *why* it emerged from B slightly off-center!

possibility. The actual results were, however, surprisingly different. It was found, under very general assumptions about the wormhole parameters, that (1) there are no trajectories with zero multiplicity and (2) the multiplicity is *not* one but rather is *always* infinity! Thus, the billiard ball form of the grandfather paradox *was* found to be *not* well-defined, but not for the expected reason that there was no self-consistent solution. Instead, it was because there are *too many* solutions.

This astonishing, completely unexpected result seems to be just what is needed to support the viability of time machines, as it appears to allow a definition of *well-defined* in the Cauchy sense and still permit an answer to the puzzle of free will. The initial conditions of a time traveling ball give rise to an infinity of self-consistent trajectories, each occurring in the same way that a random variable takes on different values with each new performance of the experiment that the random variable is defined on. And yet, there are still unique probability density functions for all sets of measurements that one might make anywhere along these trajectories. Thus, the Cauchy problem is *stochastically* well-defined; at the start of any trajectory, we do not know in detail what will happen except that whatever does happen will be self-consistent. In this probabilistic sense, then, wormhole time travel to the past and the retention of free will both make sense. The Russian physicist Igor Novikov and his colleagues continued the study of time traveling billiard balls,[56] demonstrating that one can *deduce* self-consistency from the long-accepted principle of least action (that is, self-consistency is not an additional assumption to existing physics).[57]

The one-wormhole, two-mouth time machine was actually not the first kind of wormhole time machine described in the physics literature. In their 1988 paper (note 21), Morris and Thorne initially described a time machine constructed from *two* wormholes, but they added a note-in-proof at the end that they had just discovered how to build a time machine using one wormhole (the machine we have been discussing). This reduction in the required number of wormholes was thought to be a technical advance, of course, and so the two-wormhole time machine was put aside.

But not for long. Soon thereafter the concerns about Cauchy horizon stability began to surface, a concern that one-wormhole time machines might destroy themselves just at the instant their mouths were about to be threaded by closed timelike curves. As noted earlier, the negative mass wormhole throat has a defocusing effect on electromagnetic radiation (and so the initial concern, that time traveling photons might be fatal, faded)—but then it was found that vacuum fluctuations of quantum fields are *not* so defocused.[58] That failure to defocus time-traveling vacuum polarizations (as quantum field fluctuations are called) was shown to result in an unphysical divergence of the stress-energy on the Cauchy horizon of a one-wormhole time machine.[59] This sounds bad, but the hope was that the divergence wouldn't actually be fatal: it appeared to be sufficiently sluggish that it was suggested reaching an actual *infinity* of the stress-energy would be precluded by the eventual intercession of quantum gravity. That is, the stress-energy might *try* to become unbounded as spacetime approached the formation of a time machine

---

[56] A. Lossev and I. D. Novikov, "The Jinn of the Time Machine: Nontrivial Self-Consistent Solutions," *Classical and Quantum Gravity*, October 1992, pp. 2309–2321; E. V. Mikheeva and I. D. Novikov, "Inelastic Billiard Ball in Spacetime with a Time Machine," *Physical Review D*, February 15, 1993, pp. 1432–1436; M. B. Mensky and I. D. Novikov, "Three-Dimensional Billiards with a Time Machine," *International Journal of Modern Physics D*, April 1996, pp. 179–192.

[57] A. Carlini, *et al.*, "Time Machines: The Principle of Self-Consistency as a Consequence of the Principle of Minimal Action," October 1995, pp. 557–580, and "Time Machines and the Principle of Self-Consistency as a Consequence of Stationary Action (II): The Cauchy Problem for a Self-Interacting Particle," October 1996, pp. 445–479, both in *International Journal of Modern Physics D*.

[58] V. P. Frolov, "Vacuum Polarization in a Locally Static Multiply Connected Spacetime and a Time-Machine Problem," *Physical Review D*, June 15, 1991, pp. 3878–3894.

[59] S.-W. Kim and K. S. Thorne, "Do Vacuum Fluctuations Prevent the Creation of Closed Timelike Curves?" *Physical Review D*, June 15, 1991, pp. 3929–3947. See also L.-X. Li, "Must Time Machines Be Unstable Against Vacuum Fluctuations?" *Classical and Quantum Gravity*, September 1996, pp. 2563–2568.



Fig. 6.11 A two-wormhole, Roman ring time machine

but, before it becomes so large as to destroy the time machine, quantum gravity would cut-off the divergence 'in time' (so to speak!) to save the machine.

Hawking disagreed (in his famous Chronology Protection Conjecture—see note 54 in Chap. 1), arguing that Kim and Thorne had made a crucial error in their calculations. According to Hawking, the divergence of the stress-energy may indeed be cut off by quantum gravity, but not before the development of spacetime disturbances representing perhaps a hundred million times the energy levels associated with ordinary chemical binding energies. These would be sufficiently big disturbances to raise serious doubts about the physical survival of a one-wormhole time machine, even in the absence of a true stress-energy infinity. Hence the resurrection of the two-wormhole time machine geometry. Perhaps *it* could avoid the destructive effect of time-traveling vacuum fluctuations.

If a spacetime contains multiple wormholes, then it is called a *Roman spacetime* after the physicist Thomas Roman (at Central Connecticut State University), who was the originator of such spacetimes. Each of these wormholes, individually, is *not* a time machine. Together, however, they form a time machine geometry called a *Roman configuration* (or a *Roman ring*).[60] Here's how.

In Fig. 6.11 two pairs of wormhole mouths are labeled A, A' and B, B'. We imagine that the A, A' wormhole is stationary and that its two mouths are very far apart in normal space—so far apart, in fact, that if a traveler enters A and almost instantly (because the wormhole handle is very short in hyperspace) emerges from A', it will appear to an observer at rest with respect to the wormhole that the traveler has moved faster than light. That is, entering A and exiting A' are events with spacelike separation. Now, imagine also that the wormhole with mouths B, B' is moving past the first wormhole at speed v. To an observer in this second, *moving* frame of reference, the spacelike separation of entering A and exiting A' can result in the two events being temporally reversed if v is sufficiently large (but still less than the speed of light). Therefore, upon emerging from A' the traveler crosses normal space to the moving wormhole mouth B', enters the wormhole, and then almost instantly emerges from mouth B, and finally travels again through normal space to mouth A. If the traveler can make the two trips in normal space in less time than the backward time shift achieved by the temporal reversal of entering A and exiting A', then we have a time machine

---

[60] M. Visser, "Traversable Wormholes: The Roman Ring," *Physical Review D*, April 15, 1997, pp. 5212–5214.

Two simultaneous analyses of the Roman ring time machine each concluded that, for suitable choices of sizes (the radii of the wormhole mouths, the wormhole lengths in normal space, the lateral offset of the two wormholes, and the relative speed of the wormholes), the stress-energy divergence *can* be limited by quantum gravity to an arbitrarily weak level. That is, the two-wormhole time machine is not necessarily destroyed by an unbounded stress-energy on the Cauchy horizon.[61] But not all was now put right.

Visser, in particular, had some strong reservations about the Roman ring. Although he granted that a quantum gravity cut-off the stress-energy divergence *would* probably occur in the Roman ring, he called the required special sizing conditions "bizarre," and asserted that the resulting time machine would be quite useless for a human traveler in any case. For example, he calculated that only if the mouths of the wormholes are separated in normal space by the radius of the universe (!), and only if the wormhole mouths have radii on the order of that of an atomic nucleus, would the cut-off be sufficient to allow the putative time machine to avoid destruction. When Visser reduced the wormholes from universe size to 'merely' that of the distance between the Sun and the Earth, he concluded that it would require energy at the level of the Superconducting Supercollider accelerator to blast an information-bearing message through the narrow wormholes. And even then the 'short' wormholes would provide a maximum penetration into the past of just eight minutes. As Visser put it, "This does not seem to be a workable recipe for studying tomorrow's *Wall Street Journal*.

Lyutikov, on the other hand, took a far less negative stance. He concluded that although Visser's calculations "make it very inconvenient for time travel [by humans]," nevertheless "the [principal] question of the possibility of transmitting information back in time through traversable wormholes would still remain."

The wormholes we have been discussing so far are *static* in time, but another approach is to allow them to be dynamic structures in spacetime. That is, to allow one or more of their parameters to vary with time (perhaps, for example, the throat diameter could collapse). Then, according to one analysis, it is possible to have a traversable wormhole *made of normal matter* and, even though it is collapsing, it would take so long to do so that "a space adventurer will have enough time to pass through the throat of the wormhole from one asymptotically flat region [of spacetime outside the entry mouth of the wormhole] to the other [spacetime region outside the exit mouth of the wormhole] before the radius of the throat shrinks to . . . where the event horizon is developed."[62] Such a dynamic wormhole, it was claimed, satisfies both the weak and the dominant energy[63] conditions, but not the strong energy condition. Thus, gravity would still be repulsive in the throat, but this condition (which would seem to require *exotic* matter) was brushed aside because such a condition is thought to have actually occurred, on a massive scale, during the inflationary stage of the Big Bang[64] (although how that would help in the construction of a wormhole in the future is a bit murky).

---

[61] M. Visser, "Van Vleck Determinants: Traversable Wormhole Spacetimes," April 15,1994, pp. 3963–3980, and M. Lyutikov, "Vacuum Polarization at the Chronology Horizon of the Roman Spacetime," April 15, 1994, pp. 4041–4048, both in *Physical Review D*.

Is it reasonable to think 'useable' wormholes, static or otherwise, can be acquired for the purpose of creating a time machine? At one time, Hawking was sure the answer is no, once writing "The philosophy of this paper is . . . to look for vacuum polarization [the divergence of the stress-energy on the Cauchy horizon] to enforce the chronology protection conjecture."[65] It became increasingly apparent, however, that matters would be a great deal more involved and, as Hawking himself came to admit, "the fact that the energy-momentum tensor fails to diverge [in certain special cases of time machine spacetimes] shows that the back reaction does not enforce chronology protection.".[66]

I think the best (and most honest) way to respond to the 'reasonable' question that opened the previous paragraph is with words from 20 years ago, by the Russian astrophysicist Serguei Krasnikov, words still valid today: "It may well be that the vacuum fluctuations do make the time machine unstable, but nothing at present suggests this. All we have are a few simple examples. In some of them the energy density diverges at the horizon and in some does not. So, the time machine perhaps is stable and perhaps is not."[67]

---

[62] A. Wang and P. S. Letelier, "Dynamical Wormholes and Energy Conditions," *Progress of Theoretical Physics*, July 1995, pp. 137–142. See also L. A. Anchordoqui, *et al.*, "Evolving Wormhole Geometries," *Physical Review D*, January 15, 1998, pp. 829–833.

[63] The dominant energy condition is the weak energy condition *plus* the requirement that any observed energy flux is *never* superluminal.

[64] During inflation the universe is thought to have expanded at a rate far beyond human comprehension. It has been estimated that during the first 10^{-35} second of the Big Bang the universe doubled in each spatial dimension by a factor of two each 10^{-37} second; that is, there were about 100 such doublings. Thus, there was an increase by a factor of $2^{100} \approx 10^{30}$ in each linear dimension of the universe, and the volume increased by the cube of that enormous factor. See Alan Guth, *The Inflationary Universe*, Addison-Wesley 1997.

[65] S. Hawking, "Quantum Coherence and Closed Timelike Curves," *Physical Review D*, November 15, 1995, pp. 5681–5686.

[66] M. J. Cassidy and S. W. Hawking, "Models for Chronology Selection," *Physical Review D*, February 15, 1998, pp. 2372–2380. See also L.-X. Li and J. R. Gott, "Self-Consistent Vacuum for Misner Space and the Chronology Protection Conjecture," *Physical Review Letters*, April 6, 1998, pp. 2980–2983.

The daunting level of technology required to *build* a wormhole (with or without exotic matter) doesn't mean we can't search for existing wormholes. Perhaps, for example, vast wormhole networks were formed naturally at Big Bang time, as described in Gregory Benford's 1997 novel *Foundation's Fear*, where wormholes are "leftovers from the Great Emergence [the Big Bang]." Or perhaps "advanced civilizations" long ago constructed a vast, pan-galactic 'subway system' of wormholes like the one described in Carl Sagan's 1985 novel Co*ntact* (and dramatically illustrated in the 1997 film).

Of course, any such wormhole, if found (via its double-spike light signature, for example), could be a very long way from Earth. It might even be in another galaxy. So, even if we found a wormhole, what could we *do* with it? Surprisingly, maybe a lot. The Russian physicists Igor Novikov and Andrei Lossev (note 56) suggested that a wormhole might be very useful *even if its location is completely unknown, even if we haven't yet even discovered it*! The only assumption they made was that the wormhole has existed for a "sufficiently long time" (and precisely what that means will be explained in just a bit). With that assumption, they showed how to make an information-creating time loop. Here's how they did that.

They began their analysis by assuming that people have no knowledge of how to build spacecraft that can make the interstellar voyage to the distant wormhole, even if they knew in which direction to go to reach the mouth that leads backward in time (mouth B). Instead, they build an automatic spacecraft construction plant that can follow any detailed sequence of instructions provided to it, and then stockpile it with a supply of raw materials (energy, steel, plastic, computers, and so on). When the spacecraft construction is done (*how* that is done is explained in the next paragraph), the last step before launching the spacecraft toward mouth B *will be* to load the on-board computer with the following three pieces of information:

1. The detailed sequence of instructions to be followed in the construction of the spacecraft;
2. The direction from Earth to mouth B;
3. The direction from mouth A (the wormhole exit mouth in the past) back to Earth.

To summarize, people build the automatic plant, load it up with raw materials, *and then withdraw*. This last step is crucial, because it eliminates human free will from further consideration, that is, it removes any temptation to create a bilking paradox. So, what happens next?

Lossev and Novikov suggest that what happens next is that a *very* old spacecraft suddenly appears in the sky and lands next to the automatic construction plant. In its on-board computer are items a, b, and c. Using item a, the automatic plant makes a new spacecraft, then loads the new on-board computer with items a, b, and c from the *very* old spacecraft's on-board computer, and then the new spacecraft is launched toward mouth B (using the information of item b). The *very* old spacecraft is given an honored place in a museum.

---

[67] S. V. Krasnikov, "Quantum Stability of the Time Machine," *Physical Review D*, December 15, 1996, pp. 7322–7327.

The new spacecraft arrives at the distant mouth B in the far future, by which time it is, of course, an old spacecraft (but not yet a *very* old spacecraft). It then plunges into mouth B and almost immediately emerges from mouth A, in the past. Indeed, it repeats this process as many times as required until it is in the far distant past, at a time even before it left Earth. (It might seem that to do this, the spacecraft's computer memory needs a fourth piece of information, the direction from mouth A back to mouth B, but in fact items b and c are sufficient for the old spacecraft to find its way from A to B.) It is now clear how long the wormhole must have been in existence. The old spacecraft repeatedly uses the wormhole time machine until it is so far in the past that it can cruise back to Earth at normal speed (it knows the way back because of item c) and arrive as a *very* old spacecraft, just in time to be placed in the museum!

As Lossev and Novikov pointed out, this remarkable, looped sequence of events has increased knowledge from what it was at the time just before the automatic construction plant was built. People now know both how to build an interstellar spacecraft, and the locations of both mouths of the wormhole. They also now possess a *very* old, used spacecraft. It is curious to note that although the information in the *very* old spacecraft's computer memory has traveled on a closed time loop, the *very* old spacecraft itself has not. This is because the spacecraft left Earth when new, but arrived back (before it left) as *very* old, whereupon it promptly entered a museum. There is therefore no question about the origin of the *very* old spacecraft, but where did the information of items a, b, and c come from? Lossev and Novikov say it came from the energy gained by the spacecraft as it interacted (will interact?) with the rest of the universe while on its journey.

Nobody said time travel isn't weird!

6.4 Gott's Cosmic String Time Machine

> "It's an amazingly simple solution. It doesn't take much physics to understand it."
>
> —MIT astrophysicist Alan Guth, on Gott's discovery of the cosmic string time machine[68]

> "Louise, working out the spacetime geometry of a cosmic string is a hard problem in general relativity. But, given that geometry, all the rest of it is no more than Pythagoras' theorem . . ."
>
> —a character in Stephen Baxter's 1994 novel *Ring*, agreeing with Guth.

---

[68] Quoted from J. Travis, "Could a Pair of Cosmic Strings Open a Route Into the Past?" *Science*, April 10, 1992, pp. 179–180.

A new way to gain access to closed timelike curves, without the involvement of the exotic matter needed by negative-mass wormholes, was described in 1991 by the Princeton physicist J. Richard Gott.[69] Gott gave exact solutions to Einstein's gravitational field equations for what are called *cosmic strings*, solutions that (1) unlike wormholes, do not violate any of the energy conditions, (2) unlike black holes have no crushing singularities or event horizons, and (3) are not topologically multiply connected.

Cosmic strings are fantastically thin (10^{-28} cm in radius) filaments of pure energy that are thought to stretch the width of the universe and to have an enormous linear mass-energy density of 10^{28} g/cm. To generate closed timelike paths in spacetime, Gott required that either two fast-moving (which means moving at practically the speed of light) parallel cosmic strings pass each other on a near-collision course, or that there be a closed-loop string that collapses in a slightly non-planar manner so that the opposite, nearly straight sides 'just miss.' The gravitational interaction of the passing strings can 'warp' spacetime enough to produce closed timelike curves.

A hint at the possibility of violating causality with strings had appeared before Gott's work, but those authors didn't take the time travel implications seriously. As they wrote, "We argue … that any realistic model [for a spinning string with angular momentum[70]] … will not have closed timelike curves."[71] Gott, however, showed that as two strings pass each other, closed timelike loops *do* encircle the strings.

Gott, who appears to be far less rigid in his view of time travel than are many of his fellow physicists, held out an escape to those who pale at the very thought of time travel to the past. Perhaps, he suggested (following in the footsteps of an analysis by Hawking[72]), as the strings (or string-loop sides) pass, a black hole will form with an event horizon that will seal-off the closed timelike curves from any would-be time traveler. Or perhaps, he further suggested, the more realistic case of non-singular strings (that is, strings with non-zero-filament radii) and possessing

---

[69] J. R. Gott, "Closed Timelike Curves Produced by Pairs of Moving Cosmic Strings: Exact Solutions," *Physical Review Letters*, March 4, 1991, pp. 1126–1129.

[70] The two strings in a Gott-pair are *not* necessarily spinning, and no such assumption was made by Gott. They don't even have to be parallel. If the strings have no spin, then it takes two strings to make a time machine. If spin *is* allowed, however, then just a single string will suffice for time travel: see S. Deser and R. Jackiw, "Time Travel?" *Comments on Nuclear and Particle Physics*, September 1992, pp. 337–354.

[71] D. Harari and A. P. Polychronakas, "Gravitational Time Delay Due to a Spinning String," *Physical Review D*, November 15, 1988, pp. 3320–3322.

[72] S. W. Hawking, "Gravitational Radiation from Collapsing Cosmic String Loops," *Physics Letters B*, August 23, 1990, pp. 36–38.



Fig. 6.12 The deficit angle in spacetime formed by a cosmic string

spin would banish the terrifying closed timelike curves. Subsequent analyses along those lines, however, continued to find the time travel implications intact.[73]

Here's how the cosmic string time machine works. In an earlier work,[74] published in 1985, Gott discovered that a cosmic string warps spacetime in a highly characteristic way, as shown in Fig. 6.12. A stationary cosmic string is imagined as perpendicular to the xy-plane (the plane of the page) and passing through the page at the point $(0, d)$ on the y-axis. The warp produced by the string is as though a wedge of angle 2α (this angle is called the *deficit angle*) were cut out of spacetime and the

---

[73] See, for example, B. Jensen, "Notes on Spinning Strings," *Classical and Quantum Gravity*, January 1992, pp. L7–L12, H. H. Soleng, "A Spinning String," *General Relativity and Gravitation*, January 1992, pp. 111–117, (the next two are in the *Physical Review D*), B. Jensen and H. H. Soleng, "General-Relativistic Model of a Spinning Cosmic String," May 15, 1992, pp. 3528–3533, and M. Novello and M. C. M. da Silva, "Cosmic Spinning String and Causal Protecting Capsules," January 15, 1994, pp. 825–830.

[74] J. R. Gott, "Gravitational Lensing Effects of Vacuum Strings: Exact Solutions," *The Astrophysical Journal*, January 15, 1985, pp. 422–427. Gott's discovery was independently reported in W. A. Hiscock, "Exact Gravitational Field of a String," *Physical Review D*, June 15, 1985, pp. 3288–3290.



Fig. 6.13 The warped, conical spacetime around a cosmic string, An observer in this spacetime thinks she is distance r from the string, but a 'meta-observer' sees that she is actually distance $r^{'}$ from the string. Thus, if the observer follows a complete circular path around the string, she will travel a distance of $2\pi r^{'} < 2\pi r$. The observer in the spacetime will interpret this result by saying that the angle 2π is really 2π minus 'a deficit'

edges of the cut were then 'glued' together; for example, points C and D are identified as identical. The reason for the term *deficit angle* is that at radius r from the string, a circular path around the string has the reduced length $(2\pi - 2\alpha)r$, and not the usual $2\pi r$ (spacetime around the string, while *locally* flat, is actually 'conical,' as illustrated in Fig. 6.13).

The deficit angle is equal to $8\pi\mu$ radians (in a system of units where G, Newton's gravitational constant, is 1) if the linear mass-energy density μ is expressed in units of Planck masses per Planck length. For example, $\mu = 1$ corresponds to 1.35×10^{28} g/cm (think of something on the order of the mass of the Earth per inch of the string). For 'more typical' values—say a 'mere' $\mu = 10^{22}$ g/cm, $2\alpha = 0.001^{\circ}$. While Gott's paper had appeared 5 months before Hiscock's (see note 74), it is evident that Hiscock's work was done before he became aware of Gott's. Both papers treat exact derivations of the deficit angle but, in fact, the correct expression had actually been published 4 years earlier (but from a linearized form of the gravitational field equations and so the result was not as 'conclusive' as are Gott's and Hiscock's)[75]

Now, consider the two points S and F on the x-axis at $(x_0, 0)$ and $(-x_0, 0)$ in Fig. 6.12. Suppose we want to send photons from S to F. In normal, 'unwarped' spacetime, the direct path from S to F through the origin has length $2x_0$. There is also another possible path, however, S to C/D to F, that loops out and around the cosmic string. Indeed, this second path is simply the path a gravitationally lensed photon would take (an observer at F would see *two* images of S) and this—*not* time travel—is the issue that originally attracted Gott's attention to cosmic strings.[76] If the deficit angle were zero, then this alternative path would always be longer than $2x_0$, for any value of x_0. For the case of $2\alpha > 0$, however, if x_0 is large enough $(x_0 \gg d)$, then it is possible for 'around the string and over the missing spacetime wedge' path to be shorter than the direct path.

The indirect path provides a way for a *sub*luminal trip (say, by rocket) from S to F to beat a photon traveling on the direct path. That is, the two events of the 'rocket leaving S ' and the 'rocket arriving at F' are spacelike separated. Thus, it is possible to find a moving frame of reference in which these two events are *reversed in temporal order*. In that frame of reference, the cosmic string (which is stationary in the reference frame of S and in that of F) will move—at speed v, say—in the $+x$ direction, and in that frame of reference the rocket will arrive at F *before* it leaves S.[77]

Then to complete the construction of a closed timelike path, simply repeat the process as shown in Fig. 6.14. That is, after the rocket arrives at F, have it turn around and fly back to S out-and-around and through the deficit angle spacetime warp due to a *second* cosmic string on the negative y-axis and perpendicular to the xy-plane. This second string is moving at speed $-v$ (that is, opposite to the first string), so the rocket will arrive at S before it leaves F. But that means it arrives at S before it leaves S; that is, the rocket has traveled into the past. In other words, the rocket has traveled into the past. This entire process is precisely the same idea behind the two-wormhole Roman-ring time machine discussion from the previous section.

Now, instead of having two oppositely moving reference frames, one in which the top, stationary string at $(0, d)$ appears to be moving at $+v$ and another frame in

---

[75] A. Vilenkin, "Gravitational Field of Vacuum Domain Walls and Strings," *Physical Review D*, February 15, 1981, pp. 852–857.

[76] Just as discussed earlier in the context of wormholes, gravitational lensing may offer a way to detect cosmic strings. See, for example, the two papers by D. L. Ossipov, "Diffraction of Light by a Cosmic String," November 1995, pp. 765–771, and "Contribution of Strings to the Observed Variability of Extragalactic Sources of Radiation," September 1996, pp. 419–425, both in *JETP Letters*.

[77] For this to happen, however, v must be very close to the speed of light. Gott (see note 69) showed that with $v = \tanh(\theta)$, the condition for the rocket to arrive back at S before it leaves S is $\cosh(\theta)\sin(\alpha) > 1$, where α is one-half the deficit angle. For $\mu = 10^{22}$ g/cm, this gives $v = 0.99999999995$ (times the speed of light).



Fig. 6.14 Gott's spacetime, formed by joining two oppositely moving versions of the spacetime in Fig. 6.13

which the bottom, stationary string appears to be moving at –*v*, we can imagine an observer in the *stationary center-of mass* frame watching two strings that are moving at +*v* and –*v*. This leaves the situation unchanged, so in the center-of-mass frame the rocket does travel into the past, arriving back at *S* before it leaves *S*. That is, the rocket has traveled all the way around a closed timelike world line. Note, too, that the geometric condition mentioned earlier of $x_0 \gg d$ immediately implies that for x_0 *not* sufficiently large, there isn't a closed timelike path from *S* to *F* and then back to *S*; that is, there is a region in Gott's spacetime where such time travel journeys *cannot occur*.

Another physicist pursued Gott's analysis in an attempt to see whether these 'time travel paths' are *created* as the strings approach each other or, instead, if the paths exist at other times as well.[78] This important question gets to the idea of whether such time machine paths can be *intentionally created* by humans via a dynamical process (a *strong* time machine), or whether all such paths have existed since the formation of the universe (a *weak* time machine). This issue involves Hawking's chronology protection conjecture, which you'll recall asserts that the laws of physics will always (somehow) prevent the creation of a time machine. One reason Hawking repeatedly gave for believing the Conjecture is the apparent absence of time travelers from the future among us now (in their past). The only possible exception allowed by the Conjecture is the creation of closed timelike loops at the moment the universe was created (at that moment there *was no past* for time travelers to invade!). Ori proved that the closed timelike loops around Gott's cosmic strings are *always* present: that is, a time machine is *not created* by the near collision of the strings. Thus, Hawking's Conjecture is nor refuted by Gott's spacetime.

---

[78] A. Ori, "Rapidly Moving Cosmic Strings and Chronology Protection," *Physical Review D*, October 15, 1991, pp. 2214–2215.

One very curious issue is *where* the closed time loops are before the strings pass one another. As mentioned briefly by Ori, and further discussed by others,[79] the time loops are initially at spatial infinity. To this concern, Gott and a colleague made the following very strong reply:

> "[A problem] Deser *et al.* present with respect to the Gott spacetime is that it contains CTC's at spacelike infinity; this is supposed to be an unacceptable boundary condition. We wonder, however, how they know so much about boundary conditions at spacelike infinity. In our own Universe we do not know what spacelike infinity looks like (if it exists) since we have not seen it yet. We certainly have no way of knowing whether or not there are CTC's there. The working physicist is, of course, free to impose simple and convenient boundary conditions (e.g., asymptotic flatness) on a system in order to isolate and understand the processes occurring within it. *But boundary conditions are tools of physicists, and they should not be confused with laws of physics* [my emphasis]. There may be such laws of nature that restrict the possible structure of spacelike infinity, and even prohibit CTC's there, but in the absence of evidence such laws should not be postulated *ad hoc*."[80]

Still, as Ori had observed the year before, having time loops collapsing inward from infinity toward humans who might, fortuitously, wish to use them at *just the instant they so conveniently arrive*, is "a situation which has little to do with the creation of a time machine by a *human being* [my emphasis]."[81]

The most damning objection to Gott's cosmic string time machine came, ironically, from Gott himself. The two-string spacetime of Fig. 6.14 might actually, he and a colleague wrote (see Li and Gott, note 66) be destabilized by the non-zero mass of any would-be time traveler. They suggest that this concern could perhaps be 'solved' by assuming that the time traveler and her spaceship have a spherically symmetric mass distribution surrounded by a negative-mass shell to give zero net mass (and thus a zero net gravitational field that would *not* destroy the closed timelike curves of the strings). But that, they further observed, would negate the crucial advantage—no exotic matter and so no violation of the weak energy condition—that a cosmic string time machine enjoys over a wormhole time machine.

---

[79] See, for example, S. Deser, *et al.*, "Physical Cosmic Strings Do Not Generate Closed Timelike Curves," *Physical Review Letters*, January 20, 1992, pp. 267–269.

[80] M. P. Headrick and J. R. Gott, "(2+1)-Dimensional Spacetimes Containing Closed Timelike Curves," *Physical Review D*, December 15, 1994, pp. 7244–7259.

[81] A. Ori, "Must Time-Machine Construction Violate the Weak Energy Condition?" *Physical Review Letters*, October 18, 1993, pp. 2517–2520.

Does a trip around a pair of cosmic strings present other problems *aside* from the sheer fantastic physics of the strings themselves? Well, I think "turning the rocket around at F and flying back to S" is a lot easier to write than it would be to actually do! The entire trip has to occur while the strings (moving at essentially light speed) are in a position *to be* flown around. As one character says to another in Stephen Baxter's novel *Ring*, "Louise, the strings are traveling just under the speed of light—within three decimal places of it, actually. [Our ship is] traveling at a little over half-light speed. The turning curves, and the accelerations, are incredible . . ." I think so! And I do wonder who—*or what*(!)—is actually controlling a *maneuvering* rocket traveling faster than $\frac{1}{2}c$?

6.5 Cutting and Warping Spacetime

> "The warp drive spacetime of Alcubierre is impossible to set up . . . one needs to transcend the speed of light in order to construct the warp drive in the first place . . . put roughly, you need one to make one!"[82]

In this chapter we've talked about the physics of three specific time machine 'implementations': the rotating cylinder, the wormhole, and the cosmic string. One can also discuss the 'construction' of a time machine in a more geometrical (yet still physical) way by performing what is called *spacetime surgery* to arrive at what is often referred to as a *Deutsch-Politzer spacetime* (after the two physicists who are closely associated with it[83]). With this surgery we arrive at a simple spacetime picture of the grandfather paradox (as you'll soon see).

We start with a flat, two-dimensional Minkowski spacetime, the x, t system in Fig. 6.15, and then imagine that (somehow) two *cuts* in that spacetime come into

Fig. 6.15 Minkowski spacetime transformed into a time machine with two 'cuts'



---

[82] D. H. Coule, "No Warp Drive," *Classical and Quantum Gravity*, August 1998, pp. 2523–2527, offering a pessimistic view of warp drive.

[83] See D. Deutsch, "Quantum Mechanics Near Closed Timelike Lines," November 15, 1991, pp. 3197–3217, and H. D. Politzer, "Simple Quantum Systems with Closed Timelike Curves," November 15, 1992, pp. 4470–4476, both in *Physical Review D*.

existence. These cuts are the two horizontal dashed lines in the figure, one with an arrowhead going into it, and one with an arrowhead coming out of it (each labeled with ‘2’). We further imagine that each cut has two edges, with the upper edge of the lower cut ‘glued’ to the lower edge of the upper cut (and the lower edge of the lower cut ‘glued’ to the upper edge of the upper cut

These ‘gluing’s’ explain why the arrowhead marked 2 into the lower cut at time t_1 emerges from the upper cut at time $t_2 > t_1$, and why the arrowhead marked 1 into the upper cut at time t_2 emerges from the lower cut at time $t_1 < t_2$. The 2-line is the world line of a particle that simply disappears from spacetime during $t_1 < \mathrm{t} < t_2$, while the 3-line is the world line of a particle trapped in an endless time loop (remember the 1993 film *Groundhog Day*?). Clearly, the sub-region of spacetime between the two cuts is not ‘normal’ spacetime. In fact, the 1-line shows that we have encountered a time machine spacetime, as a particle entering it from $t < t_1$ (passing to the right of the lower cut) can enter the lower edge of upper cut at $t = t_2$ and so emerge from the upper edge of the lower cut at the *earlier* time $t = t_1$ and thus interact with itself before it entered the upper edge! And that, of course, sets-up a grandfather paradox situation.

This picture leaves one thing obviously (and glaringly) unexplained—just *how* does one *cut and glue* spacetime? The reason, in spite of that question, that physicists nonetheless study situations depicted in Fig. 6.15, is because it allows them to explore what *could* happen *if* through some (yet unknown) process a time machine spacetime should suddenly appear. Who says physicists aren’t optimists?

The idea of modifying spacetime itself to ‘make’ a time machine (look back in Sect. 3.5, at the discussion there on what it means to solve the gravitational field equations) has also appeared in connection with another of science fiction’s favorite ideas, one almost as spectacular as time travel: *the FTL warp drive*. The lure of interstellar FTL travel, for both science fiction enthusiasts and physicists is, of course, simply undeniable. Consider, for example, these words by a Russian physicist:

> “Everybody knows that nothing can move faster than light. The regrettable consequences of this fact are also well known. Most of the interesting or promising candidates for colonization are so distant from us that the light barrier seems to make an insurmountable obstacle for any expedition. It is, for example, 200 pc [1 parsec is equal to about 3.2 light-years] from us to the Pole star, 500 pc to Deneb [the brightest star in the constellation Cygnus], and ~10 kpc to the center of the Galaxy, not to mention other galaxies (hundreds of kiloparsecs). It makes no sense to send an expedition if we know that thousands of years will elapse before we receive its report. On the other hand, the prospects of being confined forever to the Solar System without any hope of visiting other civilizations or examining closely black holes, supergiants, and other marvels are so gloomy that it seems necessary to search for some way out.”[84]

---

[84] S. V. Krasnikov, “Hyperfast Travel in General Relativity,” *Physical Review D*, April 15, 1998, pp. 4760–4766. Possible travel distances have been greatly reduced since Krasnikov wrote. In 2011, for example, astronomers announced the discovery of a red dwarf star with three planets (each of mass comparable to Earth’s), all in the star’s so-called *habitable zone* (where water can exist on the surface in the liquid state). All three planets are solid (not gaseous as are Jupiter,

In response to that, we might ask if *FTL* trips will someday be made by humans in spaceships? *Maybe*—but only if such journeys can be made in a very *unordinary* spacetime. That is, continuing with Krasnikov's passage:

> "The point . . . is that [whereas the light barrier exists in special relativity] in general relativity one can try to change the time necessary for some travel not only by varying one's speed [as in special relativity] but also . . . by changing the distance one has to cover."

To understand what Krasnikov was getting at, let's consider the theoretical analysis made 4 years earlier by the Mexican mathematical physicist Miguel Alcubierre on, astonishingly, how to make a *Star Trek* warp drive![85] He did this by demonstrating a spacetime metric that, by literally expanding and contracting the local spacetime of a spaceship and its neighborhood, achieves space travel between any two points, no matter how far apart, in arbitrarily little elapsed time (for both the spaceship, and external non-spaceship observers, there is no time dilation effect[86]).

Alcubierre opened his analysis with words designed to explain how FTL travel is possible, given all that I've told you earlier in this book about how FTL travel is *not* possible (according to *special* relativity). As he wrote,

> "Since our everyday experience is based on a Euclidean space, it is natural to believe that if nothing can locally travel faster than light then given two places that are separated by a proper spatial distance D, it is impossible to make a round trip between them in a time less than $2D/c$ (where c is the speed of light), as measured by an observer that always remains at the place of departure. Of course, from our knowledge of special relativity we know that the time measured by the person making the round trip can be made arbitrarily small if his (or her) speed approaches that of light. However, the fact within the framework of general relativity and without the need to introduce non-trivial topologies (wormholes), one can actually make such a round trip in an arbitrarily short time as measured by an observer that remained at rest will probably come as a surprise to many people."

That last sentence is almost surely a grand understatement, and Alcubierre quickly went on to explain.

> "The basic idea can be more easily understood if we think for a moment of the inflationary phase of the early Universe, and consider the relative speed of separation of two co-moving observers. It is easy to convince oneself that, if we define this relative speed as the rate of change of proper spatial distance over proper time, we will obtain a value that is much larger than the speed of light. This doesn't mean that our observers will be travelling faster

---

Saturn, Neptune and Uranus) and so, as potentially habitable, are candidates for a visit. The star and its planets are 'only' 22 light-years from Earth. In *Star Trek*, FTL speed is described by the *warp factor*, which is the cube-root of the multiple of the speed of light at which the spaceship *Enterprise* travels. So, for example, to make the journey from Earth to the red dwarf in one month of ship time (see ahead also to note 86), the required FTL speed would be 264 times the speed of light, or warp factor 6.4. In science fiction, a *warp drive* is imagined as the means for achieving such speeds.

[85] M. Alcubierre, "The Warp Drive: Hyper-fast Travel Within General Relativity," *Classical and Quantum Gravity*, May 1994, pp. L73–L77.

[86] That is, the passage of time on the spaceship is *identical* with the passage of time on Earth. *With the warp drive, there is no twin paradox.*

> than light: *they always move inside their local light-cones* [my emphasis]. The enormous speed of separation comes from the expansion of spacetime itself."

In a similar fashion, a *contraction* of spacetime can result in being able to *approach* an object at FTL speed.

In fact, we've actually already encountered one way to obey special relativity's *local* limit on speeds to that of light, while still achieving superluminal speed on a *global* level. That is, we *could* do that *if* general relativity really does allow wormholes in spacetime (what Alcubierre calls a "non-trivial topology"). That's because we can imagine a wormhole connecting two points in space that are light-years apart in that space, and yet the distance *through* the wormhole itself is quite short. Thus, a spaceship transiting the wormhole could do so at *sub*luminal speed at all times, and yet to an observer in normal space the speed would appear to be far in excess of the speed of light.

Determining just *how* to achieve the spacetime warp, however, is far different from simply demonstrating that such a warp is consistent with the general theory of relativity. The 1996 movie *Star Trek: First Contact*, for example, is about the invention of the warp drive in the twenty-first century. The whole thing fits inside a discarded ICBM which, as you'll soon see, is a *vast* underestimation of the technology required to control the energies associated with a real warp drive. For a spacetime engineer to *build* the warp drive bubble means she has to determine the required mass-energy distribution that results in Alcubierre's assumed spacetime metric. And that brings us to the central problem of the warp drive—the warp drive engine of an FTL starship requires (just like a wormhole) exotic matter (negative energy)—stuff that violates all the usually assumed energy conditions of general relativity.[87]

The weak, strong, and dominant energy conditions are *all* violated because the Alcubierre spacetime warp requires a negative energy density in the 'skin' of the warp bubble. As discussed earlier, in connection with wormholes, negative energy density *can* be achieved on a *micro*scopic scale, but for the Alcubierre warp drive we are talking about a *lot* of exotic matter. In their paper, Pfenning and Ford calculated that, for what they called "a macroscopically useful warp drive" with a radius of 100 m "so that we may fit a ship inside [the warp bubble]," the negative energy required for the warp bubble is on the order of, as they so graphically put it, "roughly ten orders of magnitude greater than the [energy of the] total mass of the entire universe."

Two years later, after making some adjustments to the spacetime metric assumed by Alcubierre (that is, to the distribution of mass-energy to produce the warp bubble), it was shown that the negative energy required by the warp drive could be greatly reduced.[88] The reduction is, in fact, spectacular, but only in a relative sense (you can reduce a mass that is ten orders of magnitude greater than that of the entire universe by a *huge* factor and still be left with a pretty stupendous number). The reduced amount of negative energy required for a warp bubble able to contain a human-sized spaceship is now down to 'only' "of the order of a few solar masses [-1.4×10^{30} kg]."

---

[87] M. J. Pfenning and L. H. Ford, "The Unphysical Nature of 'Warp Drive'," *Classical and Quantum Gravity*, July 1997, pp. 1743–1751. See also K. D. Olum, "Superluminal Travel Requires Negative Energies," *Physical Review Letters*, October 26, 1998, pp. 3567–3570.

As mentioned earlier, in connection with the Casimir effect and its theoretical use in a wormhole time machine, although quantum field theory does not preclude negative energy densities, that does not mean it is possible to observe arbitrarily large negative densities for arbitrarily long times. In fact, certain quantum inequalities (QI's), much like Heisenberg's uncertainty principle, have been established that place bounds on the magnitude and duration of observable negative energy density.[89] These QI's have the general form of

$$\widehat{\rho} t_0^4 > -C$$

where C is a positive constant that depends on the nature of the particular quantum field being considered, t_0 is the time duration, and $\widehat{\rho}$ is the integrated energy density along a finite section of a geodesic (free fall) world line. The form of the QI shows that as t_0 increases, $\widehat{\rho}$ must quickly decrease. For example, if t_0 doubles, then $\widehat{\rho}$ must decrease by a factor of *sixteen*, a result that caused Ford and Roman to conclude that it "appears probable that nature will always prevent us from producing gross macroscopic effects with negative energy."

'When it rains it pours,' goes an old saying, and that applies to the warp drive's potential difficulties: in addition to the need for exotic matter, there are two more concerns as well, both *operational* in detail. First, running into any space matter encountered by the leading edges of the warp bubble (where spacetime is shrinking), such as interstellar dust, would certainly generate intense radiation. The ship, then, should carry plenty of shielding which, curiously, would not be a problem because the energy density of the warp, itself, is *independent* of the mass in the bubble's interior. In any case, the warp drive should clearly not be engaged anywhere near any sizeable chunk of matter, like a planet (and, indeed, that constraint was followed in *Star Trek*). Second an even more severe problem was discovered by Krasnikov. In unpublished work he showed that the ship at the center of the bubble is not causally connected to the edges of the bubble. That is, the ship's crew could *not* create a warp bubble on demand and, after it had been created, could not control it on demand.[90]

---

[88] C. van den Broeck, "A Warp Drive with More Reasonable Total Energy Requirements," *Classical and Quantum Gravity*, December 1999, pp. 3973–3979.

[89] L. H. Ford and T. A. Roman, "Restrictions on Negative Energy Density in Flat Spacetime," *Physical Review D*, February 15, 1997, pp. 2082–2089. For some interesting remarks about the QI's, see J. F. Woodward, "Twists of Fate: Can We Make Traversable Wormholes in Spacetime?" *Foundations of Physics Letters*, April 1997, pp. 153–181.

It is important to both understand what that means, as well as what it does *not* mean. The causality issue does *not* mean that Alcubierre warp bubbles are impossible to create (perhaps they are, but not because of a lack of causality). It only means that whatever action is required to change the spacetime metric to make a warp bubble *has to already have been done before the decision to use the bubble is made*. Thus, a warp bubble wouldn't be of any use for a starship that needs to escape a sudden, unexpected threat. But, as Everett and Roman cautiously observe, the warp bubble might have a more mundane use: "Suppose space has been warped to create a bubble traveling from Earth to some distant star, e.g., Deneb, at superluminal speed. A spaceship, appropriately located with respect to the bubble trajectory, could then choose to enter the bubble, rather like a passenger catching a passing trolley car, and thus make the superluminal journey."

At the end of his paper (note 85) Alcubierre briefly speculated on the possibility of using his superluminal warp drive to build a time machine (showing, again, the intimate connection between the two concepts—look again at note 12 in Chap. 1 for how the connection between FTL and time travel appeared in pulp science fiction), but didn't show *how*. That was done 2 years later by Everett using, not surprisingly, an argument he called "reminiscent of the 'reinterpretation principle' . . . which played an important role in discussions of the physics of tachyons."[91]

In an attempt to avoid the Alcubierre bubble's causality problem, Krasnikov looked for a different, causal superluminal spacetime metric. This he succeeded in finding[92] but, rather than describing a bubble, Krasnikov's warp is in the shape of a tube. The interior of the tube is flat spacetime, just as in the case of the bubble warp, but unlike the bubble there would be a causal link between the spaceship crew and the tube. Just as the warp bubble requires very thin walls (on the order of a few thousand Planck lengths) of negative energy, so does the Krasnikov tube warp. Unlike the bubble warp, however, the tube warp stretches the entire length of any proposed trip, so the total negative energy in the warp is incredibly huge. For a tube a mere one meter long and one meter wide, for example, the total negative energy is 10^{28} solar masses, and to create a tube from Earth to just the nearest star would require 10^{44} solar masses of negative energy![93]

One curious feature of the Krasnikov warp is that the *outbound* leg of a round trip cannot be made in less time than required by light. *But* on the on the return half of the journey, a traveler would find the spacetime metric so altered (because of mass-energy manipulations purposely made on the outbound half) that she would move "backwards in time." The net result is that the round trip could end arbitrarily soon after it started! As Everett and Roman cautiously concluded, the Krasnikov tube is a "very unlikely possibility," but it would make a *wonderful* science fiction gadget, don't you think?

---

[90] A. E. Everett and T. A. Roman, "Superluminal Subway: the Krasnikov tube," *Physical Review D*, August 15, 1997, pp. 2100–2108.

[91] A. E. Everett, "Warp Drive and Causality," *Physical Review D*, June 15, 1996, pp. 7365–7368. Recall the discussion of the RP in Chap. 5.

[92] See notes 84 and 90.

[93] In the same manner as the huge negative energy of the Alcubierre warp drive was later reduced (see note 88), the Krasnikov tube's enormous negative energy requirement was later significantly reduced: see P. Gravel and J. Plante, "Simple and Double Walled Krasnikov Tubes I: tubes with low mass," *Classical and Quantum Gravity*, February 2004, pp. L7–L9.

While the Alcubierre warp may seem to be an incredible discovery (it *is*), it was not a unique one. That's because just 8 years later a different warp metric was discovered by the Portuguese mathematician José Natário, in which the expansion/contraction of spacetime does *not* occur. As Natário wrote, this signature feature of the Alcubierre warp drive "is but a marginal consequence of the choice [for the spacetime metric/mass-energy distribution]."[94] Rather than thinking of the warp bubble as being propelled by the push-pull of spacetime expansion/contraction, Natário wrote that "one could best describe the warp-drive spacetime as 'sliding' the warp-bubble region through space": that is, as analogous to a California surfer riding a wavefront. The surfer is motionless with respect to the water in the immediate vicinity of his board, and yet his speed with respect to the rapidly approaching shore is decidedly non-zero.

The idea of a manipulated or *warped* spacetime allowing time travel was an early arrival in science fiction. Consider, for example, the 1930(!) story in which the narrator (one Thomas Jenkins) walks 18,000 years into the future. In an editorial footnote (a device commonly used in early pulp fiction to inject scientific verisimilitude), we are told that "Jenkins had evidently fallen into a warp in space . . . a fault, we might say, borrowing a geologic term, in the curvature of space. Through this warp he had been thrown clear out of our three dimensions into a fourth. There he slid in time over to the other side [of the fault] into the same spot in the three-dimensional world, but into a different era in time."[95]

That was a flawed explanation, with its talk of space rather than of spacetime, but some authors eventually learned to do better. For example, *folded spacetime* as a mechanism for time travel is used in a 1940s cautionary tale on the potential horrors of the atomic bomb. In that story, published 2 years after the atomic bombings in Japan, the world 15 years hence experiences a terrible atomic war. As the time traveler in the tale explains, "During the unprecedented release of atomic energy that arouse during the simultaneous bombings of our cities, something happened to the very continuum in which we exist . . . A crook, a twist, a fold—explain it how you will, I accidently stumbled upon an electronic circuit that would create a field that would enable passage from one folded section [of spacetime] to the adjacent section. The fold proved to be about fifteen years in length . . . ."[96]

---

[94] J. Natário, "Warp Drive with Zero Expansion," *Classical and Quantum Gravity*, March 2002, pp. 1157–1165.

[95] N. Schachner and A. L. Zagat, "In 20,000 A.D.," *Wonder Stories*, September 1930.

[96] R. F. Jones, "Pete Can Fix It," *Astounding Science Fiction*, February 1947.

As Alcubierre and Natário showed, it will take a lot more than a mere electronic circuit to warp spacetime for either FTL or time travel, but at least even the early science fiction pulp writers understood that—*somehow*—a spacetime warping would be required.

The Alcubierre FTL warp drive appeared as the scientific basis for a modern science fiction novel, where at one point we read of a curious optical feature of an FTL spaceship, one I haven't seen mentioned in the physics literature: "This is a ship that traveled faster than light. It's visible as it travels; its warp bubble emits a cascade of exotic radiation . . . but it outruns its own image. So the ship arrives first and the light has to catch up, all the photons it emitted back along its path arriving at mere light speed. The older images arrive last, and you get this effect as if the ship was receding, not arriving."[97]

Another quite interesting feature of Alcubierre's warp drive is that the spaceship crew would experience no acceleration forces, as the ship is always in *free fall*. This may explain why the *Enterprise* crew isn't flattened when Mr. Sulu engages that ship's warp drive. The spaceship is surrounded by a "bubble" of warped spacetime that is swept along by the combined push-pull effect of the expanding spacetime behind the craft and the shrinking spacetime in the front. The ship, itself, resides in the *flat* spacetime interior of the warp bubble. An amusing way to think of this is to imagine a fish (space traveler), inside an aquarium (the warp bubble), which has been tossed into a swiftly flowing river. An observer at the edge of the river sees the aquarium move by her at high speed while, for the fish (swimming in the *still* waters of its aquarium), all is serene because *it is at rest with respect to its local environment*. Thus, the Alcubierre warp drive realizes yet another one of science fiction's wonderful gadgets: the *reactionless* spaceship drive. That is, "the warp bubble moves by interacting with the geometry of spacetime instead of expending reaction mass [as do jet and rocket engines] . . . and the spaceship is simply carried along with it."[98] In picturesque terms, the warp drive starship is like a surfer who makes her own waves.

And so we see, with each passing decade, more and more of science fiction departing from the make-believe to the pages of physics journals.

---

[97] S. Baxter, *Ark*, Gollancz 2009. The spaceship in this work travels at three times the speed of light (warp factor 1.44, as explained in note 84).

[98] F. S. N. Lobo and M. Visser, "Fundamental Limitations on 'Warp Drive' Spacetimes," *Classical and Quantum Gravity*, December 2004, pp. 5871–5892.

6.6 For Further Discussion

The connection between FTL speeds and backward time travel made the jump from theoretical physics to popular culture very quickly. It was in the British humor weekly *Punch*, for example, that the famous (but nearly always misquoted—see note 113 in Chap. 3, which doesn't have it quite right) limerick by A. H. R. Buller (1874–1944) first appeared (December 19, 1923, p. 591):

> *"There was a young lady named Bright Whose speed was far faster than light, She set out one day In a relative way And returned on the previous night."*

Where *Punch* dared to go, Hollywood could not be far behind. Indeed, in this case it was actually there first, with the 1922 one-reel silent comedy film *The Sky Splitter*. This was just a short film (feature pictures generally had at least four reels), so it isn't clear just how widely distributed and viewed it may have been. The story is that of a scientist testing a new spaceship; when it exceeds the speed of light, he begins to relive his life. This all shows that today's fascination, so common in popular culture, of the latest developments in theoretical physics, is nothing new. Why do you think this is so? That is, why (for example) do so many of those who flock to science fiction movies of interstellar invasions (like the 1996 *Independence Day* and its 2016 sequel), nonetheless have no conception of the unlikely possibility of such invasions because of the sheer magnitude of interstellar distances? Distances so immense that, even at the speed of light, it takes 4 *years* to travel to the Sun's nearest stellar neighbor, and *millions* of years to reach the Milky Way's nearest neighboring galaxy? (The vastness of interstellar distances is, as mentioned in the text, the reason for the fascination in warp drives in both science fiction and physics.).

In wormhole and cosmic string time machines, and with warp drives, we encountered the idea of negative mass-energy in the form of 'exotic matter' (see note 39 again). Something like negative mass actually appeared in fiction long ago, in the 1827 novel *A Voyage to the Moon* by "Joseph Atterly," a pseudonym for George Tucker, a professor of moral philosophy at the University of Virginia. (One of Tucker's students was Edgar Allen Poe, who almost surely was influenced by Tucker's book to write his own moon tale, the 1835 "The Unparalleled Adventure of One Hans Pfall.") The trip in Tucker's work was powered by a metal called *lunarium*, which repels Earth.

(continued)

This is *not* the same sort of stuff as Wells' "Cavorite," a metallic alloy that is "transparent" to gravity and that appears in his 1901 *The First Men in the Moon*. Wells' competitor in the 'scientific romance' genre was, of course, Jules Verne. Wells was a visionary who looked far beyond just the next few decades, while Verne was a 'practical engineer' who, for example, got *his* characters to the Moon by the direct method of simply shooting them out of a 900-foot long cannon with 400,000 pounds of guncotton! (Wells' vision *could* sometimes fail him, as it did about the imminent likelihood of airplanes in his 1901 *Anticipations*. He believed they *would* be developed by the year 2000, and maybe even before 1950, but of course just 2 years later . . .) In a 1903 magazine interview, Verne revealed how he felt about the difference between his and Wells' work: "It occurs to me that his stories do not repose on very scientific bases . . . He goes to Mars [sic] in an airship, which he constructs of a metal which does away with the law of gravitation. C*'est très joli* [this is all very nice], but show me the metal. Let him produce it." Today the cry from those who dislike wormholes is the Verne-like 'show us the exotic matter!' If Wells and Verne were writing today, how do you think each would respond to that challenge? Would the possible existence (or not) of exotic matter be an issue about which both would *agree*?

Write a time-loop short story based on Lossev and Novikov's idea of a 'very old spacecraft' interacting with a remote wormhole.

Imagine an electronic circuit **A** that has the following behavior: **A**'s input signal is a function of time that has a well-defined maximum value (what electrical engineers call the *peak value*). The circuit's output signal, produced in response to the input, also has a well-defined peak value. Now, imagine further that the output peak occurs *before* the input peak. There is, in fact, nothing paradoxical or impossible about that, and such a circuit can (and has) been constructed, as I'll tell you shortly. Next, suppose that we take **A**'s output signal and use it as the input to another circuit **B** that, when it's input exceeds a certain level, disconnects the input to **A** *before* that input reaches *its* peak value. Circuit **B** can also be constructed in the real world. Indeed, you can read about how to construct **A** and **B** in two papers by M. W. Mitchell and R. Y. Chiao, "Causality and Negative Group Delays in a Simple Bandpass

(continued)

Amplifier," *American Journal of Physics*, January 1998, pp. 14–19, and "Negative Group Delay and 'Fronts' in a Causal System: An Experiment With Very Low Frequency Bandpass Amplifiers," *Physics Letters A*, June 16, 1997, pp. 133–138. What makes all this interesting here is that this "seems to open the way for a variant of the time travel paradox in which the traveler journeys to the past and kills his grandfather before his own father is born," an observation made in Garrison *et al.*, "Superluminal Signals: Causal Loop Paradoxes Revisited," *Physics Letters A*, August 10, 1998, pp. 19–25. This electronic version of the grandfather paradox does indeed follow if one substitutes "input peak" for "grandfather" and "output peak" for "time traveler." But before you think this gadget is a time machine, be assured that its designers also showed that, unlike the causally related grandfather and time traveler, the two peaks are *not* so related. Read these three papers and write a summary report of how circuits **A** and **B** work, and why the two peaks are not so related.

You'll recall that "an advanced civilization" is thought to be required to create a useable wormhole (note 27). The common phrase used by astrophysicists who are interested in the possibility of extraterrestrial life is *arbitrarily advanced civilization*, with a distinction made for at least three progressively higher stages of 'advancement.' Very roughly, Types I, II, and III advanced civilizations are those that, respectively, have the technology to (a) control something like 10^{13} W (ten million megawatts) for massive interstellar radio broadcasts, (b) a technology to control the energy output of the civilization's planet's parent star (10^{27} W), and (c) a technology to control the energy output of the civilization's home galaxy (10^{38} W). We are, today, short of being even a Type I civilization, and it would probably take *at least* a Type III civilization to build a wormhole. Indeed, Stephen Baxter's 1993 novel *Timelike Infinity*, of beings who can manipulate *constellations of galaxies*, seems to assume a Type IV civilization will be required. Since there are typically 10^{11} stars in a galaxy, going from 10^{27} W for a star to 10^{38} watts for a galaxy is consistent. But where do astrophysicists get 10^{27} W for a single star? Here's a calculation for you to perform, to confirm this value for yourself, starting with the experimental fact (not difficult to repeat, as it's at the level of a junior high school science fair project using a solar cell and a few common electrical components) that the solar power level at Earth's equator is 1200 W per m^2. Then, using the fact that the Earth's orbital radius around the Sun is 93 million miles, compute the total power (energy per second) radiated by the Sun. (You should get a number that is somewhat

(continued)

smaller than 10^{27} W, which is ‘explained’ by observing that the Sun is really a quite ordinary star, exceeded in size by many other stars in the Milky Way. Next, you’ll find, in most books on astrophysics, the statement that the nuclear fusion reactions that power the Sun convert *four million tons* of the Sun’s mass to pure energy *every second*. Confirm that your number for the power output of the Sun is consistent with that claim. (Remember Einstein’s famous formula $E = \mathrm{m}c^2$, that the speed of light is $c = 3 \times 10^8$ m/s, and that 1 kg $\approx$ 2.2 pounds. In the MKS system of units (meters/kilograms/seconds) one watt = one joule (of energy) per second, where to give you some perspective on what a joule is, the chemical energy released by burning a gallon of gasoline is about 100 MJ.

Appendix A
Old Friends Across Time (A Story)[1]

As I sit here in my study, with the photographic evidence spread before me, I can barely comprehend what my eyes tell me must be so. The evidence is incontestable. And yet—I still struggle to believe. Let me try to explain—possibly in the process I will manage to put my tumbling mind to rest.

For as long as I can recall, old photographs have fascinated me. To page slowly through collections of historical pictures, no matter what the theme, was consummate joy. Even when I was quite a small boy I used them as my time machine into the past. They took me up and away from the problems every youngster has while growing up, and let me wonder of people and places long since returned to dust. Matthew Brady's Civil War photos had a particularly strong attraction for me, with the horror (and yes, I will admit it, the *fascination*) of war frozen in the images of young men dead before life had really begun. To look at the fallen youth of more than a century before, and to wonder who they were, and what they had felt and thought—it all sent shivers through my romantic mind.

I suppose I might have become a professional photographer. But somewhere along in the process of looking at pictures, I became aware of the miracle of the *technology* of picture taking. That led me to chemistry and optics, and finally by some wondrous route, I became an electrical engineer. I never lost my love for old pictures, though, but merely turned my interest in them to the photographic history of electrical physics.

To search out and acquire (for by now I had started my own collection) a photograph of Steinmetz, smoldering cigar clamped in his mouth, giving a lecture on AC circuit analysis using the then still mysterious square root of minus one made my heart beat faster. To find a faded picture of Einstein at a long forgotten

---

[1] P. J. Nahin, "Old Friends Across Time," *Analog Science Fiction Magazine*, May 1979. This tale was written with the specific goal of illustrating how a trip into the past *yet to be initiated* could logically influence events in the time traveler's present and future. The story reproduced here is, with only a few very minor alterations, as it originally appeared in *Analog*.

© Springer International Publishing AG 2017

P.J. Nahin, *Time Machine Tales*, Science and Fiction,
DOI 10.1007/978-3-319-48864-6

conference, caught forever in time with his quiet, gentle eyes looking into mine, would send me to the heights of ecstasy.[2]

But it was Maxwell that led me to my incredible discovery. There is no doubt but that James Maxwell was the greatest theoretical physicist of the nineteenth century. Together with Einstein, he was the best of *any* century. Could it possibly be more than mere chance that the same year saw the death of one and the birth of the other? It was Maxwell who gathered together all the then known, but fragmented, experimental bits and pieces of knowledge about electricity and magnetism, and stirred in his own contribution of the displacement current. There was no physical evidence then to justify that last step, but the genius of Maxwell knew it *had* to be. And then, from his soaring mathematical insight and physical intuition, he took it all and wrote down the four magnificent equations for the electromagnetic field![3]

No one who has seen and understood those beautiful equations can come away without a quickening of the pulse and a flush of the blood. They're not long—you can write all four vector differential equations on the back of a postcard, but oh, what they tell us! With them, Maxwell, showed light was electrical in nature, predicted radio waves *two decades* before Hertz discovered them in the lab, explained energy propagation in space, and radiation pressure, and laid the scientific basis for today's television, radar, lasers, giant electric motors, generators, transmission lines and—well, why go on? The equations are the work of a level of genius we may not see again for a millennium. We have hardly begun to discover the marvels wrapped inside the electromagnetic field equations. With their aid, and that of quantum mechanics, the very secret of life, itself, may someday be unraveled.

And so I searched for old photographs of Maxwell. He died at his family's Scottish home in 1879, before the art of picture taking was barely 40 years old. But I knew in my heart that somewhere there *must* be photographs, yet undiscovered, of such a great man. Anyone who has seen the best examples of prints from wet glass collodion negatives knows they are, in the faithfulness of their rendition of detail, better than what we commonly expect today. Working against me was the fact that the process was slow, laborious, and unforgiving of mistakes. The taking of a picture was not a minor decision in Maxwell's time. But still I searched.

I searched for one photo, in particular. When Einstein died, a famous picture was taken of his office, just the way he left it for the last time. On the blackboard behind his desk are the last thoughts he had in his long quest for a Unified Field Theory, a ‘theory of everything.’ The writing on the papers covering the desk is clearly legible, and with modern blowup methods, easily readable.

---

[2] The first reference is to Charles Steinmetz (1865–1923), the German-born American electrical engineer and mathematician who became the wunderkind of General Electric. Einstein, of course, needs no introduction!

[3] I wrote this for story effect, but it's not really *quite* true. When Maxwell wrote his theory in mathematical form, he did so using *twenty* (!) equations in as many variables. The equations, as physicists and electrical engineers use them today, were first written in 1885 by the English self-taught eccentric Oliver Heaviside, who considered Maxwell to be his hero (see note 6 in Chap. 6). Modern electrical engineers and physicists write the Maxwell equations as *four* partial differential *vector* equations.

At the time of his death, Maxwell was the Einstein of his times. Surely, I reasoned, a similar photograph of Maxwell’s study must have been taken. Even though none has come down through the decades to us, it *must* exist! Gathering dust in an old trunk, or buried in a long forgotten album, it had to be somewhere. I vowed to find it.

I began by writing to all of Maxwell’s living descendants, asking that they search through family holdings for any pictures concerning Maxwell that they might possess. For the most part all were cooperative, even though more than just a few thought I was somewhat deranged. Still, it was in vain. I did receive a few old pictures never before seen by other than the family, including a poignant one taken in 1901, showing Maxwell’s grave in Parton Churchyard at Glenlair, Scotland. A forlorn, wintry scene, with only what seemed to be three men in the far distance, it brought tears to my eyes. Alas, there were no photos of Maxwell’s study.

But then late last year, while on a business trip to London, I stopped off for a few hours at the historical archives maintained by the British Institute of Electrical Engineers. On a chance, I looked through their massive files on Maxwell and was rewarded within the hour! What I found will haunt me throughout the remainder of my life.

There it was, stuck through its border with a rusty pin, between two pieces of yellowed paper covered with what appeared to be some simple, rough lecture notes. An ordinary looking photo of a study. Obviously overlooked through the years, or at best unappreciated for what it was, it was the almost illegible, penciled notation on the back that convinced me of my find—just a date: November 9, 1879. Exactly 4 days after Maxwell’s death, precisely when some unknown, yet inspired person (a family member, a neighbor, a local scientist?) would take such a picture!

I am ashamed to admit it, but there was no hope the Institute would let me have the picture. And there was no time to copy it, for I was to return home to America that very night. No, that’s not true. The *real* reason for what I did was simply that I *had* to have that original, *old* photo. I took it! It was my undoing, for that dishonorable act destroyed the picture’s tie to verified, legitimate historical records. But *I* know what I found is true.

I could barely control my wild emotions on the flight home. Several times I removed the picture from my briefcase, and looked with fascination at the papers lying on Maxwell’s desk, and at the tightly written lines of mathematics on the blackboard in the background. My hands trembled with what can only be called lust—once home, reunited with my well-equipped photo lab, I would learn every secret hidden in that picture.

There are no words I know that can convey the thrill I felt as I began the processing of that priceless photo. Alone in my lab, with all the modern equipment a well-off amateur can buy (a Caesar Saltzman 8 × 10 enlarger with mercury vapor point light source and a 10× Plan Achromat Nikon enlarging lens), I carefully cropped and blew up selected views of the blackboard and desk. Printing the enlargements on ultra-fine grain AGFA Brovira paper, I could scarcely restrain myself from peering at them with a magnifying glass while I waited for them to dry.

Then, at last, I had them spread out across my study desk. I tried to force myself to examine each slowly, carefully, in turn, and not to skip from one to another like a child let loose in a candy store with a dollar. The first three were of the desk papers, including what seemed to be a diary. It must have been lost after Maxwell's death since no trace of it exists in the historical records. I experienced a stunning thrill as I gazed upon the scrawled words, but as they were not easily read at once, I moved on. It was the sixth enlargement, of the upper right corner of the blackboard that sent me reeling back to my chair. An equation that shouldn't, no, *couldn't*, be there. But it was.

To understand my reaction, there is one astounding thing you must realize about Maxwell's field equations. When Einstein turned the world of physics on its head in 1905 with his famous paper, "On the Electrodynamics of Moving Bodies," all the old ideas about absolute motion and simultaneity of events went out the window. Even Newton's laws of mechanics had to be modified. But *not* Maxwell's! His equations, just the way he published them in 1873, are the same ones studied today[4]—they need *no* relativistic corrections.

How can that be, you wonder, as they predate Einstein's by 32 years? The mystery of this has bedeviled the experts down through the years. Oh, they have an explanation, alright. They say that all of electromagnetics is actually relativistic phenomena to begin with, and the laboratory work of Faraday, Ampere, Henry, and the other great experimentalists were studies of relativistic electron interactions in matter (although they, of course, didn't know that). Thus, it is only 'natural' that Maxwell's equations need no correction. So goes the 'expert' explanation, but it isn't right![5] I know Maxwell knew about relativity, and understood it perfectly. He knew all about time paradoxes and the equivalence of mass and energy.

Because how else can you explain the equation visible in my enlargement: $E = mc^2$!

Why, you must wonder (just as I did), didn't Maxwell publish this remarkable result? At first, I believed it was because of a lack of faith in his results. Who would have believed any of it in those Victorian times, so sure of its absolute view of nature? I thought of how Newton, 200 years before Maxwell, had suffered from a similar hesitancy when he wrote the *Principia*. There, when explaining his theory of gravitation, Newton did *not* employ his new invention of the calculus (which he *had used* to make his discoveries), but instead fell back on laborious arguments based on the accepted mathematics of algebra and geometry. Who would have believed him, otherwise?

But then I realized that couldn't be right. Maxwell was a strong man intellectually and he wouldn't have held back for fear of disbelief. No, it had to be that he discovered relativity and the mass-energy law just before his death, with no time to make his work known. I was still wrong.

---

[4] Don't forget note 3.

[5] Alas, I think it *is* right. Don't forget, this is science *fiction*. When there is a conflict between the needs of a story, and a rigid adherence to physics, the 'needs' wins!

It was later, when I returned to the enlargement of Maxwell's lost diary and read those painfully cramped notes, that I learned the truth. What I saw there showed me Maxwell had thought long and hard about his final discoveries and had purposely withheld them. For clearly visible, after I had slowly deciphered the writing, were the following words:

> *I have seen monstrous events. My blood has run cold at the sight of two great cities leveled to the ground, their inhabitants cruelly put to death instantly, or left to die slowly from a strange, lingering disease. Other trips, further on, have shown me the root of all these evils is the mass-energy equation, a result I at first believed to be my crowning glory. It will be my crown of thorns unless I ban it from my very being. Another will discover it for himself, but* my *soul shall be free! I have dismantled my machine, and shall never look upon or think of those horrible scenes again.*

This passage was dated just 1 month before Maxwell died a savage death from cancer. The reference to 'two cities' can only be that of Hiroshima and Nagasaki. His own death was surely caused by lingering too long among their atomic ruins.

Think of what this *means*. Quite simply, Maxwell knew the secret of time travel! But even more incredible is that it must be *easy*, if one only knows how, to build a time machine! Think about it—Maxwell had no gigawatt power stations at his disposal, no high technology machine shops, or nanosecond computers. He was not a gifted experimentalist, and once he had predicted radio waves, for example, it took others 20 years to finally generate them. And yet, *he* built a time machine. Somehow, with just the puny power sources available to him, and a limited mechanical capability, he wrested free the *simple* implementation of a time machine from his dynamical field equations.

Yes, yes, I know what you must be thinking. How can I really conclude such an incredible thing from a single equation on a blackboard, and a few words written by a man dying a painful death? A man, clearly suffering dearly, and possibly not in complete possession of his once marvelous mind.

This very evening the last bolt of evidence slid into place. Attempting to escape from the emotional maelstrom into which I had fallen, I turned to my old love of picture gazing. I took down from my library shelf a tattered yet cherished volume of the Meserve Collection of Lincoln pictures. My slow paging through the images stopped when I came to the famous photograph by Alexander Gardner of Lincoln's second inauguration. This incredible picture shows John Wilkes Booth looking down on Lincoln from behind a buttress high on the steps of the Capitol, while below in the crowd are the five men who, 41 days later, conspired with him in the assassination.

The following page demonstrated the extraordinary quality of Gardner's work, as it showed an enlargement of Booth's face in which the circular line between the pupil and the white of each eye is sharp and crisp! This impressive picture fascinated me, and I wondered if I could create a similar enlargement. It was then I remembered the old picture of Maxwell's grave, sent to me from Scotland, and the three distant figures in the background. They would present my photo-lab skills with a challenge, and the effort would distract my mind.

I finished the enlargement just 20 min ago. Those faces! Two of them I can now finally accept as being there—it must have been a pilgrimage for one, and for the other, it couldn't have been anything but a mocking, ironic gesture. But I wonder if the youngest one really knew who his two companions were? I don't know the answer to that—yet. But there they are, two men with faces my years of study have made as familiar to me as my own. One is a youthful Albert Einstein. The other, with the signs of death clearly written across his features, is James Clerk Maxwell. The face of the third man is familiar, too, for the third man is me!

Oh, I'm a bit older in the photo than I am now. But it's me, alright. A distinctive, jagged scar across the left cheek, a mark from a childhood accident, is sharply visible, and I can run a finger over my face and match it perfectly with the image in the enlargement. I'd say I'm about 45 or so in the image, no more than 10 years older than I am now. That doesn't leave me much time to keep my appointment, does it? I don't know, right now, how I'm going to do it, but I've got to rediscover Maxwell's secret of time travel. I'm sure I'll succeed—after all, there I am in the picture. Somehow, I'll be going back to pick James and Albert up so we can have our picture taken. Ten years—not much time.

I'm really looking forward to meeting my two new friends from across time.

For Further Discussion

When "Old Friends Across Time" originally appeared in *Analog*, it opened with a quotation from Richard Feynman's famous 1961–1963 Caltech undergraduate course (published in 1964 as *The Feynman Lectures on Physics*): "Ten thousand years from now, there can be little doubt that the most significant event of the nineteenth century will be judged as Maxwell's discovery of the laws of electrodynamics. The American Civil War will pale into provincial insignificance in comparison." This is almost certainly true, but could Maxwell *really* have built a time machine from just a knowledge of electromagnetic theory and special relativity (which is all that is needed to derive $E = mc^2$), if he didn't also have a deep understanding of general relativity (and probably of quantum mechanics, too)? How likely do you think *that* is?

The narrator in “Old Friends Across Time” knows he is going to live long enough to eventually build a time machine; discuss the implications of this knowledge. For example, is he at least *temporarily* invulnerable to committing suicide (or, for that matter, to any other variation of dying?) That is, do we have a ‘future’ version of the grandfather paradox? This issue has never (to my knowledge) been considered by physicists, and not by philosophers either until recently. See, for example, S. Keller and M. Nelson, “Presentists Should Believe in Time-Travel,” *Australasian Journal of Philosophy*, September 2001, pp. 333–345, and M. H. Slater, “The Necessity of Time Travel (On Pain of Indeterminacy),” *The Monist*, July 2005, pp. 362–369. More generally, if we assume that the past is unchangeable then the scenario in “Old Friends Across Time” seems to force at least some level of inevitability on the future as well. Or does it? In the 2007 story by Ted Chiang, “The Merchant and the Alchemist’s Gate,” that you were asked to read in a *For Further Discussion* at the end of Chap. 4, there is the following exchange between the narrator and the inventor of “the Gate” (a wormhole): “So if you learn that you are dead 20 years from now, there is nothing you can do to avoid your death?” He nodded. This seemed to me very disheartening, but then I wondered if it could not also provide a guarantee. I said, “Suppose you learn that you are alive 20 years from now. Then nothing could kill you in the next 20 years. You could then fight in battles without a care, because your survival is assured.” “That is possible,” he said. “It is also possible that a man who would make use of such a guarantee would not find his older self alive when he first used the Gate.” “Ah,” I said, “Is it then the case that only the prudent meet their older selves?” Comment on this issue, with particular attention to free-will.

Appendix B
Newton's Gift (A Story)[6]

Wallace John Steinhope was a sensitive human being, a person deeply concerned about the welfare of his fellow creatures. Any act of injustice, however slight, made his breast pound with righteous indignation. He was a champion of fair play, and his motto in life was taken from the ancient English rule of law—'Let right be done!'

Even while still a lonely, reclusive child, Wallace's heart ached mightly when he read of the laborious, boring, mind-dulling calculations endured by the great mathematicians of old. Just knowing, *thinking*, of Gauss's marvelous mind wasting literally months of its precious existence grinding out tedious mathematics that even a present-day dullard could do in a minute, on a home computer, was sheer agony for Wallace. Contemplation of the God-like Newton suffering endless delays in his gravity research, all because of a simple miscalculation of the length of a degree of longitude, was almost unbearable.

Indeed, Newton played a special role in Wallace's life (and he in Newton's, as we shall soon see). While the other great mathematical physicists had merely been hindered in their work by the lack of modern computational aids, Newton had squandered so much valuable time in other, nonscientific pursuits! His quasireligious writings alone, over half a million words, exceeded his scientific writings. What a waste! Wallace wondered endlessly over the reason for this strange misdirection of talent and bored his friends to the edge of endurance with his constant brooding on the mystery. Still, they all liked and admired Wallace enormously and so put up with it. But more than one of them had sworn to throw up the next time Wallace mentioned Newton during a wedding (but that's another story).

So deep was Wallace's anguish for his predecessors that even as he grew older and his own tremendous talents as a mathematical physicist (the result of a lucky

---

[6] P. J. Nahin, "Newton's Gift," *Omni*, January 1979. This tale was written with the specific goal of illustrating casual loop time paradoxes. The story reproduced here is, with only a few very minor alterations, as it originally appeared in *Omni*.

© Springer International Publishing AG 2017

P.J. Nahin, *Time Machine Tales*, Science and Fiction,
DOI 10.1007/978-3-319-48864-6

genetic mutation induced in a male ancestor some centuries earlier) gained him an international reputation, thoughts of the unmeasurable misery of his scientific ancestors were never far from his mind. It was most appropriate, then, that his greatest discovery gave him an opportunity to *do* something! And Wallace John Steinhope vowed to *help*. He became convinced that it was his purpose on earth—he could not, he *would* not hesitate. As he strapped the knapsack-size time machine to his chest, his excitement was, therefore, easy to understand.

"It is done! And I am ready. I will travel back and bestow this gift of appreciation, this key to mental relief, on the great Newton himself!" Wallace cradled a small, yet powerful hand-calculator in his palm. It was a marvel of modern electronics. Incorporating large-scale integrated circuitry and a Z-8000 microprocessor solid-state chip, the calculator required only a small, self-contained nuclear battery for its power. It could add, subtract, multiply, divide, do square and cubic roots, trig and hyperbolic functions, take powers, find logarithms, all in mere microseconds. It was programmable, too, able to store up to 500 instructions in its micro-memory. The answers it displayed on its red, light-emitting diode readouts would liberate young Isaac from the chains of his impoverished heritage of mathematical calculation. No more Napier's bones for Newton!

But Wallace John Steinhope was no fool. He understood, indeed feared, time paradoxes. He knew Newton could be trusted with the secret, but it wouldn't do for the calculator to survive Newton's time. So Wallace had incorporated a small, self-destructing heat mechanism into it. After 5 years of use, it would automatically melt itself into an unrecognizable, charred slag mass. But that would be enough time for its task to be completed. The emancipation of Newton's mighty brain from tedium! Pleased enormously at the thought of the great good he was about to confer, Wallace set the time and space coordinates for merry old England, flipped the power switch on, and vanished.

Materializing in the Lincolnshire countryside in the spring of 1666, he began his rendezvous with destiny. It was the second and final year of the great bubonic plague, and Newton, seeking refuge from the agony and death plundering London and threatening his college of Trinity at Cambridge, had returned home to work in seclusion. The years of the Black Death were Newton's golden years, when the essentials of calculus would be worked out, when the colored spectrum of white light would be explained, and when the principle of the law of gravitation would be grasped. But how much easier it would be if Newton were released from the binding chains of dreary calculation. Wallace's gift would slip the lock on those chains! Accelerate genius!

It was early evening when, guided by a map of the area prepared by a friend who was both a cartographer and amateur historian, Wallace reached the quiet little town of Woolsthrope-by-Colsterworth. It was here, in a small farmhouse, that Wallace would meet his hero of the ages. A cold, gentle rain was falling as he approached the door. The soft, hazy light of an oil lamp glowed inside, revealing through the translucent glass the form of a man bent over a table. The fragrant smoke of well-dried wood curled from the chimney, announcing a warm fire within.

With his heart about to burst from excitement, Wallace rapped upon the door. After a pause, the shadow rose and moved away from the window. The door opened, and there stood Isaac Newton, a young man of 23 with an intellect that Hume and Voltaire considered "the greatest and rarest genius that ever rose for adornment and instruction of the species." But for the importance of his self-appointed mission, Wallace would have fainted dead away from the thrill of it all. "Is this the home of Isaac Newton?" he asked in a voice quavering with the trembling tones normally used by lovers about to reveal their deepest feelings.

The young man, of medium height and thick hair already showing signs of gray, swung open the door and replied, "My home it is, indeed, stranger. Come into the parlor, please, before the wetness takes you ill."

Isaac followed Wallace into the room and stood quietly watching as his visitor removed his soaked coat and hat. The portable time machine was gently placed on the floor next to a wall. The calculator was snug and safe in its plastic case in Wallace's shirt pocket. "Thank you, Master Newton. May we sit while we talk? I am afraid you may wish to take some time to consider my words." Motioning to a chair near the table, Isaac pulled a second chair from a darkened corner and joined Wallace. "You have a strange sound to your speech, stranger. Are you from hereabouts, or have you traveled far? Please commence slowly your tale."

Wallace laughed aloud at this question, a response prompted by his nervous excitement, and it quite surprised him. "Please forgive me. It is just that I *have* traveled so very, *very* far to see you. You see, I am from the future." Wallace was not one to play his cards close to his chest. Now it was Isaac's turn to laugh. "Oh, this is most ridiculous. Are you a friend of Barrow's at Trinity? It would be so like him to play such a trick.[7] From the future, indeed!"

Wallace's eyes ached at the sight of the papers on the table where Isaac had been working. What wonders must be there about to be born! In any other situation, Wallace would have asked their contents, but the die had been cast. He had to convince Isaac of the truth of his tale. But he had to walk a tight line, too. It just wouldn't do to misdirect Isaac's interest away from the calculator and toward the time machine itself! He must do something dramatic, something that would rivet his idol's attention and hold it.

"Yes, yes, I understand your reluctance to believe me. But, look here. This will convince you of the honesty of my words." Wallace pulled the shiny black plastic-cased calculator from his shirt pocket and flipped the power switch on. The array of LEDs glowed bright in the gloomy room as they flashed on in a random, sparkling red burst. Isaac's eyes widened, and he pushed his chair back. Was he frightened?

"As the Lord is my Savior, is it a creation of Lucifer? The eyes of it shine with the color of his domain. Are you one of his earthly agents?"

---

[7] The reference is to Isaac Barrow (1630–1677), who was the first Lucasian Professor of Mathematics at Cambridge. Barrow resigned that position to allow it to pass to Newton. Centuries later, Hawking became the 17th Lucasian Professor.

"Oh my, no! Look here, Master Newton, let me show you that there is no black magic or chicanery involved. It is all perfectly understandable in terms of the laws of Nature. What I have here is an automatic calculator, a device to perform all of your laborious mathematical labors."

So saying, Wallace squeezed the sides of the calculator case together, releasing pressure snap-fittings, and flipped the case open on a hinge at the top. Revealed to Isaac were the innards of the electronic marvel—a tightly packed interior of printed circuit boards, a mass of integrated circuitry, the small LED display, and the sealed nuclear battery. Isaac stared intently at the sight, and Wallace could see the natural curiosity of Newton's great mind begin to drive away the initial apprehension.

"But where are the gears, levers, springs, and ratchets to carry out the calculations? All I see is a black box with lights that glow red—how is *that* done; where is the lamp or candle to provide the light!—and many little isolated fragments of strange shapes. There is clearly nothing in your box that moves!"

"Oh, it is all done with electronics, Master Newton! The central processing unit has access to a solid-state memory that contains the decoding logic necessary to implement the appropriate algorithmic processes to provide the answers to the specific requests entered through these buttons. The actual performance of the box is achieved by the controlled motion of electrons and holes in suitably doped semiconductor material under the influence of electric fields induced—" Wallace, still overcome by his excitement, had rambled on wildly without thought of the essentially infinite technological gap that separated himself from Newton.

"Stop, stop," cried Isaac. "I understand only a few of the words you use and nothing at all of their meaning! But it is obvious that for calculations to be performed, mechanical work must be done, and that implies motion. Pascal's adding machine has shown the veracity of that. I say again, nothing moves in the box. How *can* it work?"

Wallace was embarrassed. The mistake of overlooking the hundreds of years of progress after Newton's time was one a child might make. "I am sorry, Master Newton. I'm going too fast for you." Isaac looked at Wallace with a frown, but Wallace failed to see the pricked vanity of the proud Newton. Going too fast, indeed!

Wallace prepared to lay a firmer technological foundation for Newton, but then he froze. It couldn't be done! Newton was a genius, certainly, but the task was still impossible. Wallace would have to tell him all about Maxwell's equations, Boolean algebra and computer structure, electronics, and solid-state device fabrication technology. It was just too much, and besides, there was the danger! The potential time paradoxes of all that knowledge out of its proper time sequence! What if Newton, in innocence, revealed some critical bit of knowledge out of its natural place in history? So, Wallace hesitated, but seeing the suspicion grow again in Isaac's eyes, he realized he had to do something, *anything*, immediately.

"You cannot deny your own eyes," answered Wallace. "Let me *show* you how it works. I'll divide two numbers for you with just the punch of a few buttons. Watch this." And, at random, he entered 81,918 divided by 123. Poor Wallace, of all the numbers to use, they were the worst. Within milliseconds the answer glowed brightly in fiery red characters. Wallace looked with pride at the result and then, already enjoying in his mind what he knew would be Isaac's amazement, he turned his eyes to the great man. What he saw made his spine tingle, and the gooseflesh stand high on his neck. Newton had fallen to his knees, with eyes bulging and hands raised as if in prayer.

"The mark of the Beast, it is the mark of the Beast! It is so written in the Book of Revelations—Here is wisdom. Let him that hath understanding count the number of the beast; for it is the number of man; and his number is six hundred three-score and six!" Rising to his feet, Newton fell back into his chair. "Your cursed box bears the brand of its master. There can be no doubt now, it *is* the creation of the fallen archangel!" Wallace was aghast at Isaac's violent reaction. The seventeenth century genius had now stumbled backward from his chair and had grasped a poker from the hot coals of the fireplace.

"Wait, please wait! Watch this; I'll multiply two other numbers together for you, watch!" Wallace quickly punched in the data, and then the answer gleamed steadily in burning red characters on the LEDs. Isaac's eyes first went wide with fear as he again saw the wizard electronics do their marvelous assignment, and then he shut them tight. Wallace was becoming desperate—this wasn't the way it was supposed to be! "Don't you see—imagine the tedious work, the mind-deadening labor this machine will save you from. And it is yours."

"Yes? But only for the exchange of my soul! That is always the Devil's price for his seductive gifts from Hell!" As Isaac shrieked these last words at Wallace, he raised the poker over his head. "Begone, you emissary of the Dark World! I know now you must be in the employ of the Father of the Antichrist, but the Lord God Almighty will protect me if I do not waver in my resolve. Begone, or I'll strike your brains out on the floor where you stand!"

Isaac's eyes were wide with fear, nearly rolling back to show all white spittle sprayed from his mouth as he yelled at Wallace, who stared in shock at the wild man who threatened him with death. "Please, please, *listen* to me, please! I beg you to understand—I am a scientist, just like you. The concept of the devil, and all it stands for, is contrary to everything I believe. How *could* I be in the devil's employ, when I don't even accept his existence? You *must* believe me!"

"Blasphemy!" screamed Isaac. "Your own words condemn you. To deny the reality of Satan in a sinful world is to deny that of God, too. Now leave my home, you dark beast from hell, or by the heavens above, *I shall destroy you*!" As he shrilled these words, Isaac brought the poker down in a wild swing that barely missed Wallace's head.

Struck dumb with confusion at the uncontrolled outburst, Wallace stuffed the calculator into his shirt, grabbed his hat, coat, and time machine and rushed from the house. As he hurried into the cold, wet night, he turned back, just once, to see Isaac Newton framed in the light of the open door. "Go, go, you foul messenger from the Lord of Evil! Back to your stinking pit of burning hell-fire! This is a house that honors the Divine Trinity and is no haven for the likes of you!"

Wallace rushed away into the blackness, the time machine bouncing unheeded upon his chest.

He ran, for how long he couldn't recall, until he fell exhausted next to a stream running heavy with the rain. Tears of rage, frustration, and shock streamed from his eyes. Rejected by the great Newton! Well, damn him! Wallace flung the calculator into the stream in his terrible anger and activated the return coordinates. He faded from Newton's world as quickly and quietly as he had come.

As for Isaac Newton, after having chased the Devil's messenger from his house, he returned on shaking legs to his desk. Pushing aside his rough calculations on the orbit of the moon around the earth, he swore to redeem himself in the eyes of the Savior. Somehow, he had been found lacking and had been tested. And the test was surely not over! He began to reapply his marvelous mind to determine the origin of his failure before the Lord God Jehovah. Taking quill in hand, he wrote the first of the many hundreds of thousands of words that his numerous religious tracts would devour from his allotted time.

Five years later, long after Newton had returned to Cambridge, a group of picnicking children were frightened when a nearby stream suddenly erupted into a geyser of steam. Moments later, the bravest (or most foolhardy) of the boys—who, by an astonishing coincidence that befits any good time travel paradox, would be Wallace's great-grandfather nine times removed—cautiously examined the streambed. All he found were some twisted, hot pieces of what he thought was a hard, black rock, and he tossed them back. They were all that was left of the calculator's nuclear battery. He did receive a tiny radiation dose from them, which caused a recessive genetic mutation that centuries later would suddenly appear as the cause of Wallace's genius, but otherwise the lad was unaffected. The incident was soon forgotten.

Well over 300 years later, Wallace John Steinhope reappeared in his own time. He was essentially the same man as before he left—kind, generous, and sensitive, and ready to come to the aid of any man or beast that might need help. As far as his friends were concerned, in fact, he was even improved (naturally, they didn't know what had brought about the welcome change but, if they had, they would have applauded it).

Wallace John Steinhope, you see, never again had another kind word for Newton, or for that matter, any words for him at all.

For Further Discussion

In his book *Travels in Four Dimensions: the enigmas of space and time* (Oxford 2003), the philosopher Robin Le Poidevin writes (p. 176) "But, as everybody knows, when a time machine leaves for another time it *disappears*." This is, indeed, how the time machine in "Newton's Gift" works; however, after reading *Time Machine Tales* do you think such behavior is in agreement or in conflict with general relativity? Defend your position.

"Newton's Gift" contains causal loops. Identify two of them, and discuss their role in the story (that is, are they central to the story or merely incidental?).

The idea of a time traveler visiting famous people in the past occurs fairly frequently in science fiction. In Ian Watson's "Ghost Lecturer" (*Isaac Asimov's Science Fiction Magazine*, March 1964), for example, the inventor of the "Roseberry Field" uses it to yank geniuses out of time to supposedly honor them, to let them know their lives had been worthwhile in the eyes of the future. But then he goes on to tell them—oh so kindly—where they had gone wrong or had fallen short of the mark, and of how much more we know nowadays. "You almost got it right, boy! You were on the right track, and no mistake. Bravo! *But* . . ." Watson makes the interesting observation that one can easily imagine playing this pathetic game of 'second-guessing' history with scientists, but what could even the most talented modern do to upstage a Mozart or a Shakespeare? Most similar to "Newton's Gift," however, are (for example) Gregory Benford's "In the Dark Backward" (*Science Fiction Age*, June 1994) where Shakespeare and Hemingway are visited, and Jack McDevitt's "The Fort Moxie Branch" (*Full Spectrum*, October 1988) where Hemingway and Thomas Wolfe appear. Read these stories, and then compare/contrast their descriptions of how story characters react to the appearances of time travelers, to Newton's behavior in "Newton's Gift."

Appendix C
Computer Simulation of the Entropic Gas Clock

```
%gasclock.m/created by PJNahin for TIME MACHINE TALES(6/27/2015)
%This MATLAB m-file simulates the diffusion of gas molecules in a
sealed
%container by using the Ehrenfest ball exchange rules. The
simulation
%starts with n molecules (i.e., balls) of one type (i.e., black)
on
%one side of the container, and n more molecules of another type
(i.e.,
%white balls) on the other side. The two urns play the roles of the
%two sides of the container. To simulate the ball (molecule)
%movements, the program selects two random numbers from 0 to
1, which
%are then compared to the current probabilities of selecting a
black
%ball from urn I and a white ball from urn II. If BOTH random
numbers
%are greater than these two probabilities then a white ball has
been
%selected from urn I and a black ball has been selected from urn
II,
%and so the number black balls in urn I is increased by one while
the
%number of white balls in urn II is increased by one. If BOTH
random
%numbers are less than or equal to these two probabilities then a
%black ball has been selected from urn I and a white ball has been
%selected from urn II and so the number of black balls in urn I is
```

© Springer International Publishing AG 2017
P.J. Nahin, *Time Machine Tales*, Science and Fiction,
DOI 10.1007/978-3-319-48864-6

```
%decreased by one while the number of white balls in urn II is
decreased
%by one. If one of the random numbers is greater than its
corresponding
%probability while the other random number is less than its
%corresponding probability, then no action is taken because then a
%white (black) ball moves from urn I to urn II at the same time a
white
%(black) ball moves in the opposite direction. That is, there is
no
%net change. Then, the ball selection probabilities are recalcu-
lated and
%another ball exchange is simulated.
rand('state',100*sum(clock))     %new seed for the random number
generator;
n=100;                           %number of balls in each urn;
nb1=n;                           %number of black balls INITIALLY
in urn I;
nw2=n;                           %number of white balls INITIALLY
in urn II;
pb1=nb1/n;                       %probability of selecting a black
ball from urn I;
pw2=nw2/n;                       %probability of selecting a white
ball from urn II;
for trials =1:1000;
   system(trials)=pb1;
   ball1=rand;
   ball2=rand;
   if(ball1>pb1&ball2>pw2)         %white ball selected from urn I
      nb1=nb1+1;                   %and black ball selected from
      nw2=nw2+1;                   %urn II;
   elseif(ball1<=pb1&ball2<=pw2)  %black ball selected from urn I
      nb1=nb1-1;                   %and white ball selected from
      nw2=nw2-1;                   %urn II;
   end
   pb1=nb1/n;
   pw2=nw2/n;
end
plot(system)
axis([1 trials 0 1])
grid
xlabel('time, in arbitrary units')
ylabel('fraction of balls in urn I that are black')
figure(1)
```

Epilogue

> [Science fiction] cannot be good without respect for good science . . . This does not include time machines, space warps and the fifth dimension; they will continue to exist in the hazy borderland between [science fiction] and fantasy.[8]

> In many science-fiction stories, the trip into the past is by way of some futuristic machine that can take you through time at will . . . That, however, is totally impossible on theoretical grounds. It can't and won't be done.[9]

The opening quotations, particularly the second one from Asimov who was one of the great modern writers of science fiction, is a gloomy one indeed for fans of time travel, but it is not difficult to find inconsistency in Asimov's own tales dealing with the concept. Asimov is famous, in particular, for his stories of robots, and the very last such tale that he wrote combines robotics with time travel, with a robot sent two centuries into the future.[10] At the start of the story, the narrator tells us that time travel to the past is impossible because the past is unchangeable and (of course) a time traveler would necessarily disturb history. (That is (of course) simply a failure to distinguish between the difference of *changing* the past and *affecting* the past, as well as a failure to see how the principle of self-consistency negates the issue of paradoxes.) Then, when the robot returns from the future (and so backward time travel is *not* impossible!), he reports that his arrival had been expected, that history had recorded that he would appear. At the end of the story we learn how the future knew this—it had read "Robot Visions"! So now Asimov *uses*

---

[8] Harry Harrison, in his essay "With a Piece of Twisted Wire . . .," *SF Horizons* (no. 2), 1965. Harrison (1925–2012) was a well-known (if little appreciated outside the SF community) writer, whose 1966 novel *Make Room! Make Room!* was the inspiration for the excellent (if somewhat depressing) 1973 film *Soylent Green* (a movie about future over-population of the Earth that will make you think twice about ever eating a cookie again).

[9] From an essay Isaac Asimov wrote on the time travel movie *Peggy Sue Got Married* for the *New York Times*, October 5, 1986.

[10] I. Asimov, "Robot Visions," *Isaac Asimov's Science Fiction Magazine*, April 1991.

© Springer International Publishing AG 2017

P.J. Nahin, *Time Machine Tales*, Science and Fiction,
DOI 10.1007/978-3-319-48864-6

the principle of self-consistency, with the narrator realizing that he *must* preserve his story so the future can read it.

Not a very consistent story! Asimov, was, of course, writing a story for entertainment's sake, so perhaps it's unreasonable to hold him *scientifically* accountable (although logic wouldn't seem to be too much to ask for).

In any case, was Asimov right? Lots of his fellow science fiction writers certainly thought so. One, for example, bluntly asserted that

> Time travel is inconceivable.[11]

Other critics agreed:

> In science fiction we find the lunatic fringe more often than not trying to perfect time-travel mechanisms.[12]

and

> Scientifically, time travel can't stand inspection.[13]

and

> Time travel is . . . scientific nonsense.[14]

and

> It would be untrue . . . to present the idea of a time machine as anything but what it is, an intriguing literary device, part of the bag of tricks of the science fiction writer . . . There is no such thing as a 'science' of time travel.[15]

You'll notice that these pronouncements are from decades ago: Conklin (1904–1968), Gold (1914–1996), and Oliver all wrote just 3 years after Gödel, and so perhaps it was simply too soon for his work to be widely known outside of the physics community. But physicists have learned a lot since 1952! Have they learned enough to make Asimov and his fellow SF skeptics (if they were still alive) change their minds, or at least reconsider? I suspect not.

I say that because, even 25 years after Conklin, Gold, and Oliver wrote, while we do find an awareness of Gödel starting to appear in the science fiction world, a feeling of skepticism was still in the air. In a fascinating analysis[16] of the first half-century of the science fiction magazines, Paul Carter admitted that there *is* a rationality to time travel because of Gödel but, nonetheless, the conventional view remained that backward time travel is simply impossible. Then, citing the work of Tipler, Carter wrote "Only as recently as 1974 (see note 130 in Chap. 1), in the sober pages of the *Physical Review*, has a physicist been more bold … For 70 years in the meantime, however, without waiting for Professor Tipler to solve his equations … writers had happily helped themselves to Mr. Wells' invention and sent their characters through time in every direction, forward, backward, and sideways."[17]

---

[11] Kingsley Amis, *New Maps of Hell*, Harcourt 1960.

[12] Groff Conklin, *Science Fiction Adventures in Dimension*, Vanguard 1953.

[13] H. L. Gold, *The Galaxy Reader of Science Fiction*, Crown 1952.

[14] Alexei Panshin, *The Mirror of Infinity*, Canfield 1970.

[15] Chad Oliver, "The Science of Man," a non-fiction essay included in Oliver's 1952 time machine novel *Mists of Time*. Chad Oliver (1928–1993) was a scientist by profession (anthropology), and his opinion carried weight among SF writers *and* (non-physicist) scientists.

[16] P. A. Carter, *The Creation of Tomorrow*, Columbia University Press 1977.

In the 1980s writers were apparently just as unaware of Gödel's time travel analyses (and of the much later ones of Tipler) as had been the 1950s commentators. In his marvelous 1985 book *The Past Is a Foreign Country*, for example, David Lowenthal repeatedly refers to time travel as "fantasy" and to science fiction stories about time travel as "unbridled by common sense." And for another example from the start of the 1980s, consider the case of James Gunn (born 1923), professor of English at the University of Kansas, past president of both the Science Fiction Writers of America and the Science Fiction Research Association, author of *The Immortals* (inspiration for the 1970–1971 TV series of the same name), and eminent scholar (see his 1975 book *Alternate Worlds*). His literary credentials are impeccable and his critical influence profound. And yet, 30 years after Gödel and 5 years after Tipler, Professor Gunn wrote in *The Road to Science Fiction*, "Time travel has been an anomaly in science fiction. Clearly fantastic—there is no evidence that anyone has ever traveled in time and *no theoretical basis for believing that anyone ever will* [my emphasis]." If you've read this book carefully, however, of the analyses by Gott, Krasnikov, Thorne, Alcubierre, Novikov, Natário, and others, you know that what Gunn claims in those last words is actually not necessarily so.

The British-born American theoretical physicist Freeman Dyson of the Institute for Advanced Study has commented[18] on that sort of narrow mindset, with words quoted from the 1979 physics Nobel prize winner Steven Weinberg, words reminding us that rigidity concerning time travel is not limited to science fiction writers: "This is often the way it is in physics—our mistake is not that we take our theories too seriously, but that we do not take them seriously enough. It is always hard to realize that these numbers and equations we play with at our desks have something to do with the real world. Even worse, there often seems to be a general agreement that certain phenomena are just not fit subjects for respectable theoretical and experimental effort." The words *time travel* and *time machine* are never mentioned, but could they have been far from either Weinberg's or Dyson's thoughts?

All through this book we have seen how people have argued against time travel to the past (Tipler's cylinder is unphysically long, Gödel's universe requires an unphysical rotation, wormholes and warps require unphysical energy conditions, what about all those paradoxes … and on and on). These arguments remind me of the debate in the 1930s between the illustrious British astrophysicist Sir Arthur Eddington and the young Indian astrophysicist Subrahmanyar Chandrasekhar (1910–1995), winner of the 1983 Nobel prize in physics. In his analyses of the life history of stars, Chandrasekhar had arrived at an astonishing conclusion, one that Eddington simply could not accept. As Eddington sarcastically explained in an address at Harvard University in the summer of 1936, "Above a certain critical mass (two or three times that of the sun), the star could never cool down, but must go on radiating and contracting until heaven knows what becomes of it. That did not worry Chandrasekhar, he seemed to like the stars to behave that way, and believes that is what really happens."[19] Eddington then went on to declare such 'unbelievable' behavior to be nothing less than "stellar buffoonery."

---

[17] Given that *The Time Machine* was published in 1895, it is not clear how Carter arrived at the value of 70 until Tipler's work (he should have written 79), and of course it was only 54 years between Wells' time travel fiction and Gödel's time travel mathematical physics.

[18] F. J. Dyson, "Time Without End: Physics and Biology in an Open Universe," *Reviews of Modern Physics*, July 1979, pp. 447–460.

As far as Eddington was concerned, Chandrasekhar had simply made an error in combining relativity theory with non-relativistic quantum theory. Indeed, so appalled was Eddington at the thought of a star contracting "until heaven knows what becomes of it" (that is, until it gravitationally collapses into a black hole) that he had earlier, in 1935, stated "There should be a law of nature to prevent a star from behaving in this absurd way!" Today, of course, no astrophysicist feels the need for a 'star protection conjecture'—which perhaps reminds you of another, more recent 'protection conjecture.'

What can one conclude from all the similar controversy concerning time travel, time machines, and spacetime warps? Not much, I think, except that these are open issues and will remain the subjects of on-going study for a long time yet to come. The one thing I am fairly certain of is that if time travel is ever achieved, it will be by means that we cannot today even begin to guess. It will almost certainly require *at least* a mutant child genius with an IQ of 270 to fix the slightly broken time machine found abandoned in a cellar![20] But that view isn't uniformly shared across all of science fiction. I very much doubt, for example, that things will be quite so elementary as depicted in the story[21] where the time machine was so simple that "If it were taken apart or put together before you, your wife, or the man across the street, you would wonder why you didn't think of it yourselves." Not only that, but its power source was just two dry cell batteries!

The time machine in an earlier story is almost as simple, requiring (besides a piece of strange crystal) only a "little stack of dry cells, a Ford [automotive ignition] coil, a small brass switch, a radio 'B' battery, an electron tube, and a rheostat."[22] Even Wells' *Time Machine* couldn't resist making it all look easy: as one critic put it, "The time machine, like all products of supreme inventive genius, was a remarkably simple affair. A few rods, wires, some odd glass knobs—nothing more!"[23] That sort of simplistic fictional description of a time machine reminds me of the reaction of the great Polish science fiction writer Stanislaw Lem to the general treatment of time travel in the genre: "There have been mountains of nonsense written about traveling in time, just as previously there were about astronautics—you know, how some scientist, with the backing of a wealthy businessman, goes off in a corner and slaps together a rocket, which the two of them—and in the company of their lady friends, yet—then take to the far end of the Galaxy. Chronomotion, no less than Astronautics, is a colossal enterprise, requiring tremendous investments, expenditures, planning . . ."[24]

---

[19] See S. Chandrasekhar, *Eddington: The Most Distinguished Astrophysicist of His Time*, Cambridge University Press 1983, p. 48.

[20] F. B. Long, "A Guest in the House," *Astounding Science Fiction*, March 1946.

[21] R. Abernathy, "Heritage," *Astounding Science Fiction*, June 1947.

[22] J. Williamson, "In the Scarlet Star," *Amazing Stories*, March 1933.

An example of what Lem was talking about is the 1956 novella *Arcturus Landing* by Gordon R. Dickson (1923–2001). There we read of aliens who have confined humans to the solar system—until (if) Earth scientists discover the secret of FTL travel. So, a genius physicist does just that (with no mention of spacetime engineering, but rather we encounter a lot of mumbo-jumbo gibberish as the 'explanation'), and uses it to instantly transport himself and some friends to a planet orbiting Arcturus.[25] And when they get there the friendly aliens speak perfect English.

Lem would have snorted in derision, too, at this statement made to a prospective graduate student by the head of a college physics department, that the college "has been awarded a million dollars to build [a time machine]. It means . . . a raise for me and maybe a doctorate for you, so we'll build one and have some fun doing it."[26] Is it any wonder that Lem so readily dismissed stories that reduce space (and time) travel to weekend adventures in a home laboratory? As Lem wrote in another essay, time travel and its close relation, FTL space travel, have reduced much of science fiction to "a bastard of myths gone to the dogs."[27] Because of precisely that, Harry Harrison wrote (note 1) of the early science fiction magazines that published so much nonsense, "I used to moan over the fact that pulp magazines were printed on pulp paper and steadily decompose back towards the primordial from which they sprang. I am beginning to feel that this is a bit of a good thing."

I don't know whether time travel to the past can actually be accomplished, but I do know that speculations once thought to be as outlandish as finding the Philosopher's Stone for turning base elements into gold, *have* eventually been realized (and, come to think of it, with modern nuclear physics we *have* learned how to turn lead into gold, if only a few atoms at a time). Television, nuclear power, home computers that run at multi-gigahertz clock rates in the bedrooms of high school students, even faster computers that animate our movies and simulate the formation of black holes and galaxies, voyages to the Moon and back—all these amazing developments would be pure magic to nineteenth century science. The ghosts of not just a few Victorian scientists who had poo-pooed the possibility of such things, have watched their reputations eat a lot of posthumous crow during the last 150 years.

---

[23] W. B. Pitkin, "Time and Pure Activity," *Journal of Philosophy, Psychology and Scientific Methods*, August 27, 1914, pp. 521–526.

[24] S. Lem, "The Twentieth Voyage of Ijon Tichy," in *The Star Diaries*, Seabury Press 1976.

[25] A journey incorrectly given in the story as 120 light years, when in fact it is less than 40 light years.

[26] W. West, *River of Time*, Avalon Books 1963.

[27] S. Lem, "Cosmology and Science Fiction," *Science-Fiction Studies*, July 1977, pp. 107–110.

My personal position on the question of time travel leans towards the rejoinder made to the skeptic in one science fiction story who, even after having done some time traveling, *still* argues against it by invoking paradoxes. He is sharply rebuked with "Oh, for heaven's sake, shut up, will you? You remind me of the mathematician who proved that airplanes couldn't fly."[28] I subscribe to the optimistic philosophy of the British writer Eden Phillpotts (1862–1960), who wrote in his 1934 novel *A Shadow Passes* "The Universe is full of magical things, patiently waiting for our wits to grow sharper." Perhaps he had a famous saying by the British-born Indian scientist J. B. S. Haldane (1892–1964) in mind, words from his 1928 *Possible Worlds*: "Now my suspicion is that the universe is not only queerer than we suppose, but queerer than we can suppose."

Still, even if time travel is possible, the engineering phase will surely be tough going. I am certain that before we see a working time machine, there will be many, *many* episodes like the one described in a very funny, novel-length spoof of academic research.[29] All physicists and engineers who have tried to get some stubborn piece of apparatus to work, apparatus that *should* work and simply won't, will appreciate Professor Demetrious Demopoulos' frustration and will, I am sure, forgive him his intemperate language:

> . . . the distinguished physicist took a step back and, arms akimbo, surveyed the complex and sophisticated machine that was the culmination of years of dedicated scientific research and pains-taking technological development.
>
> "What a pile of ****," he said.
> "Oh, no, Dr. Demopoulos, don't say that!"
> "Well, it is." A sneer formed on the professor's thin lips. "Time machine, my ****. This thing couldn't give you the time much less travel in it."
> "But we haven't incorporated all our latest test data yet," the pretty research assistant reminded him. "These last few adjustments might do it, Professor."
> "Hell, we've been tinkering with it for 2 years," Demopoulos complained.
>
> "We've tried everything and it's all come to dog ****."

---

[28] R. Heinlein, "By His Bootstraps," *Astounding Science Fiction*, October 1941. As discussed at the end of Chap. 1 (in "For Further Discussion") the mathematician was the American astronomer Simon Newcomb.

[29] J. DeChancie and D. Bischoff, *Dr. Dimension*, ROC 1993.

That scene probably won't actually happen for a long time to come but, even before the practical nuts-and-bolts bugs in the Professor's time machine are worked out, I think some adjustments are called for in our thinking about time travel. I believe that present-day philosophers and science fiction writers are going to have to become knowledgeable about the work by physicists on time travel. It simply won't do any longer for Philosophy Professor X to invoke the grandfather paradox during a discussion of causality and free will and then airily declare them to be 'obviously' incompatible with time travel to the past. And it simply won't do any longer for Famous SF Writer Y to send his hero into the past to kill Hitler as a baby and thereby change recorded history. One might as well keep watching a video recording of the 9/11 destruction of the World Trade Center, in the vain hope that maybe, on the next viewing, the planes will miss.

The principle of self-consistency around closed timelike curves is going to have to become as much a part of the science fiction writer's craft (or else she will be a writer of fantasy) as it will have to become part of the fundamental philosophical axioms.[30] The 'time police,' like the "operatives of the Bureau of Time Exploration and Manipulation" that appeared in the science fiction of Andre Norton (1912–2005), will have to be put out to pasture with the unicorns and telepathic dragons of fantasy fiction. Just as the recent physics literature on time machines has displayed a growing awareness of what science fiction writers and philosophers have had to say on the subject of time travel, so too are writers and philosophers going to have to learn some more physics. Most people can enjoy a good fantasy tale now and then, but the use of 'magic mirrors' to see through time is *not* physics. Such devices were popular and acceptable in medieval times—see "The Squire's Tale" in Chaucer's *The Canterbury Tales*, and later (see Act IV of *Macbeth*)—but good science fiction needs much more than that today.

Time travel to the past is a beautiful, romantic idea, and some words written by two physicists in a technical paper—words embedded in the midst of swirls of tensor equations—show that even hard-nosed physicists can share this dream: "In truth, it is difficult to resist the appealing idea of traveling into one's own past . . ."[31] The appeal of that dream is explained in Ray Bradbury's Foreword to a beautiful little 1989 book by Charles Champlin (*Back There Where the Past Was*). In it Bradbury clearly illuminated *why* we want to go back into the past. It is for the same reason that we go, time and again, to see *Hamlet*, *Othello*, and *Richard III*: "We don't give a hoot in hell who poisoned the King of Denmark's semicircular canal.

---

[30] Bud Foote (1930–2005), late professor of English at Georgia Tech, wrote (in his book *The Connecticut Yankee in the Twentieth Century: Travel to the Past in Science Fiction*, Greenwood Press 1991) that consistency is simply a well-used plot device: "The attempt of the time traveler to prevent something or take advantage of it [and so causing] the event in question, is so popular and so ubiquitous that it seems to be about worn out." Worn out or not, I believe that plot device to be correct science.

[31] A. J. Accioly and G. E. A. Matsas, "Are There Causal Vacuum Solutions with the Symmetries of the Gödel Universe in Higher-Derivative Gravity?" *Physical Review D*, August 15, 1988, pp. 1083–1086.

We already know where Désdemona lies smothered in bedclothes and that Richard goes headless at his finale. We attend them to toss pebbles in ponds, not to see the stones strike, but the ripples spread."

That's why a visit to the past is so mysteriously and marvelously fascinating. It would let us watch ripples spread through time. Our own visit to the past, in fact, might even be the pebble in the pond of history that starts an interesting ripple or two that will one day sweep over—us! (Take a look at Appendices A and B) Who would want to miss that? Indeed, if modern philosophers are right, if the analyses discussed earlier in this book are correct, you *can't* (didn't/won't) miss it.

I think time travel appeals, irresistibly, to the romantic in the soul of anyone who is human.[32] A time traveler does not exist either *here* or *then*, but rather *everywhen*. For a time traveler passing back and forth through the ages, history would be the ultimate puzzle, a chronicle described in one novel as beginning "not in one place, but everywhere at once ... It might be begun at any point along the infinite, infinitely broken coastline of time."[33] Romanticism doesn't preclude there also being a dark side to visiting the past, of course, as one time traveler from 1989 learns when he takes up residence in 1962. Falling asleep on a hot summer night in that long-ago year, he thinks "JFK slept. Oswald slept. Martin Luther King slept. [I sleep and dream] of Chernobyl ... *I am a cold wind from the land of your children*."[34]

But, I must admit, I personally am more attracted by happier descriptions of time travel. In his marvelous 1996 book *1939: The Lost World of the Fair*—which is proof that there are not enough Pulitzers to go to all the books that deserve one—Yale professor David Gelernter caught just the right spirit in his Prologue: "The best of all reasons to return to the fair is that travel is broadening, and time travel most of all ... The 1939 New York World's Fair is one amazing show. It still stands, undisturbed on Flushing Meadow, just over the edge of time; it would be an unforgivable shame to miss it." Trust me—if you read Gelernter's book, you'll come as close as you can in today's world to taking a ride in a 'time machine'!

The eminent philosopher Sir Karl Popper opens his biography with a wonderful story about his apprenticeship as a young man in 1920s Vienna to a master cabinetmaker.[35] After winning the old man's confidence, the student learned his mentor's great, secret desire: For years the master had been looking for the solution to perpetual motion. He knew what physicists thought of such machines, but nonetheless he had never given up his dream: "They say you can't make it; but once it's been made they'll talk differently." Popper's master sounds just a bit like the American writer Gertrude Stein (1874–1946) in her 1938 essay "Picasso," where she writes "It is strange about everything, it is strange about pictures, a picture may seem extraordinarily strange to you and after some time not only it does not seem strange but it is impossible to find what there was in it that was strange." Might we one day say the same thing about time travel?

---

[32] How else to explain the pleasure, for modern children *and* adults too, in watching rebroadcasts of the 1960s animated TV cartoon program 'starring' Mr. Peabody, a nice but slightly stuffy, professorial white beagle. (Don't all dogs wear glasses and a bow tie?) Mr. Peabody, with his brainy adopted son Sherman, routinely travels into the past in the "Way-Bac" machine to see what *really* happened in history.

[33] John Crowley, *Great Work of Time*, Bantam 1991.

[34] R. C. Wilson, *A Bridge of Years*, Doubleday 1991.

[35] See volume 1 of *The Philosophy of Karl Popper* (P. A. Schilpp, editor), The Library of Living Philosophers, Open Court 1974, p. 3.

An alternative point of view can be found in a discussion of time travel via cosmic strings that makes this assessment: "While there is still hope that one day a sufficiently clever design may make building a time machine possible, it is beginning to seem more and more improbable. Like the perpetual motion machines of the nineteenth century, the designs have an elegant simplicity (as well as enormous commercial potential), but it seems that Nature also may abhor them just as much."[36] Of course, at one time it was thought that Nature abhorred a vacuum, but then we learned that she must actually love a vacuum because else why did she make so much of it?!

The theoretical basis for time travel is very different from that of perpetual motion (there is *more* reason to accept time travel as a plausible possibility). And so maybe one day, *just maybe*, the first time traveler will receive a toast such as the one in a story telling us about the arrival of the inventor of the first time machine and his no longer skeptical friend in the Civil War past:

"To you, Mac," I said.

McHugh loosened his tie. "To the Creator," he said, "who has given us a Universe with such marvelous possibilities."[37]

---

[36] B. Allen and J. Simon, "Time Travel on a String," *Nature*, May 7, 1992, pp. 19–21.

[37] J. McDevitt, "Time's Arrow," *Isaac Asimov's Science Fiction Magazine*, November 1991.

Glossary[38]

Action the integral over a **world line** of a quantity called the *Lagrangian*. When a massive particle is moving at non-relativistic speed through a gravitational field, for example, the instantaneous value of the Lagrangian is the difference between the kinetic and potential energies of the particle. For other types of fields (such as the electromagnetic) and/or relativistic motion in any type of field, the Lagrangian is different. In any case, however, the actual world line of the particle is the one for which the integrated Lagrangian, that is, the action, is minimized. See **least action**.

Action at a distance the direct interaction of two separated objects, without concern for the details of what (if anything) occurs in the region between the objects (see also **field**). Newton's theory of gravity is action at a distance, whereas Einstein's theory of gravity is a *field* theory.

Advanced solution the prediction, by Maxwell's electromagnetic field equations, of radio waves that travel into the past (see also **Dirac radio**).

Anti-matter quantum mechanical prediction (experimentally verified) that all fundamental particles of matter come in two forms (the 'normal' version and the 'anti-matter' version). The positron, for example, is the anti-matter version of the electron, differing only in the sign of its electric charge. The photon, on the other hand, is its own anti-particle. A **subluminal** anti-particle traveling forward in time can be thought of as its 'normal' version traveling backward in time.

Arbitrarily advanced civilization for time travel discussions, a civilization with a technology sophisticated enough to construct a traversable **wormhole** in spacetime. More generally, Types I, II, and III of such civilizations are, respectively, those that can control 10^{13} W, 10^{27} W (the total power output of their home star), and 10^{38} W (the total power output of their home galaxy).

---

[38] "I hate definitions." (Usually attributed to writer and British Prime Minister Benjamin Disraeli (1804–1881) but, more precisely, they are the words of one of the characters in his 1826 novel *Vivian Grey*.)

—but they *can* be useful

© Springer International Publishing AG 2017
P.J. Nahin, *Time Machine Tales*, Science and Fiction,
DOI 10.1007/978-3-319-48864-6

Arrow of time the statement the time appears to have a direction, that there is a difference between the past and the future. There are several different arrows: the psychological (we remember the past, we anticipate the future), the thermodynamic (organized systems evolve toward disorganization, that is, **entropy** increases as time increases), the electromagnetic (radio waves propagate *away* from their generators), and the cosmological (the expansion of the universe is directed toward the future).

Asymptotically flat if the geometry of a curved spacetime is such that, as one moves ever further away from all matter and energy, the spacetime **metric** becomes that of flat **Minkowski spacetime**, then the curved spacetime is said to be *asymptotically flat*. As a counter-example, the spacetime of a **Tipler cylinder** time machine is *not asymptotically flat*.

Autoinfanticide paradox see **grandfather paradox**.

Averaged null energy condition the claim that the *averaged* value of the observed mass-energy density along the entirety of any **null geodesic** is non-negative.

Averaged weak energy condition the claim that the *averaged* value of the observed mass-energy density along the entirety of any **timelike world line** is non-negative.

Back reaction the tendency of spacetime to resist the formation of **closed timelike lines** (see also **stress-energy divergence**).

Bell's theorem an inequality that either holds or does not hold, depending on whether quantum mechanics is non-local or local, respectively.

Big Bang the singular beginning of spacetime.

Big Crunch the singular end of spacetime.

Bilking paradox what would happen if a **causal loop** were disrupted. For example, suppose a time traveler builds a time machine using plans he received years earlier from a mysterious stranger. He now realizes that the stranger was himself, using the time machine to travel back into the past to give his younger self the plans. A bilking paradox would be created if the time traveler builds the time machine, verifies that it works, and then decides *not* to visit his younger self to hand over the plans. See also **bootstrap paradox**.

Black hole a region of spacetime where gravity is so strong that nothing can escape, including light. Black holes are thought to be created when sufficiently massive stars burn out (see **white dwarf** and **neutron star**) and undergo *gravitational collapse*. A black hole of ten solar masses would have a radius of about twenty miles. Black holes might have been created at the Big Bang singularity and, if so, could theoretically come in any mass and size (a black hole with the mass of the Earth would have a diameter of less than half an inch).

Block universe a spacetime in which all world lines are completely determined from beginning to end (a fatalistic universe). There is no free will in such a spacetime.

Boost matrix matrix formulation of the **Lorentz transformation**.

Bootstrap paradox the puzzle of the origin of *information* on a closed loop in time. The classic example is that of a time traveler from the future giving his younger-self the plans for the time machine the time traveler has just used to visit the past so that he can then build the time machine to visit the past. The time machine plans appear not to have been *created* by anyone! The plans just *are*. See also **bilking paradox**.

Cauchy horizon a **spacelike** hypersurface in spacetime that intersects, exactly once, every **timelike** world line that has no end point. Knowledge of the conditions on such a surface uniquely determines the spacetime at all other points.

Causal loop a time loop containing an event caused by a *later* event that, itself, is caused by the earlier event (see the example in **bilking paradox**).

Causality the metaphysical claim that every event is caused by a prior event. Time travel to the past inherently violates causality.

Chronal regions those parts of spacetime that have no closed timelike curves.

Chronology horizon a (hyper)surface in spacetime that separates **chronal** and non-chronal regions. It is a special case of a **Cauchy horizon**.

Chronology protection the claim, as yet unproved, that time machines and time travel to the past are impossible because of the **back reaction** of spacetime will lead to **stress-energy divergence**. Popularized among physicists as the *Hawking chronology protection conjecture* (1992), Hawking has since admitted that stress-energy divergence is *not* sufficient to enforce his conjecture.

Chronon science fiction name for **Planck time**.

Closed timelike line (or curve) a **timelike** world line of finite length that has no ends, i.e., that forms a *closed loop* in spacetime. A region of spacetime containing closed timelike lines is said to be a **time machine**.

Conservation law physical quantities in interacting systems that remain unchanged are said to be conserved. Total energy, total momentum (linear and angular), and electric charge are conserved quantities.

Cosmic string hypothetical, threadlike spacetime structures with enormous mass-energy and density that may have formed during the **Big Bang**. Cosmic strings may have been initially formed either as infinitely long, or as closed loops, and it is the former that are thought to be physically meaningful in the present-day universe. Cosmic strings do not violate the **weak energy condition** (as do **wormholes**), and they can theoretically create **closed timelike lines**.

Cosmological constant an extra term specifically added by Einstein to the general theory of relativity to keep that theory from predicting the expansion of the universe (which was later observationally found to actually be the case). Einstein subsequently said that his failure to believe the general theory's original prediction of the expansion of the universe was the greatest mistake of his life. The constant (which today is believed to be almost zero, if not exactly zero) appears in Gödel's rotating time travel spacetime as a determining factor in the minimum radius of a **closed timelike line**.

Determinism the metaphysical belief that effects are uniquely determined by causes (this is *not* **fatalism**).

Dirac radio science fiction gadget for sending information at infinite speed, which thus travels backward in time (see also **ultraluminal**).

Dominant energy condition the **weak energy condition** *plus* the claim that the observed energy flux is never **superluminal**.

Electron fundamental particle of mass that possesses one quantum of negative electric charge. *Bound* electrons orbit the nuclei of atoms and plays a central role in determining the chemical properties of the elements and of their compounds. *Free* electrons carry electric current, either in conductors (wires) or through space.

Elsewhen the collection of spactime events that cannot be reached from the **here-now** with a **timelike world line**.

Entropy a measure of the randomness of a system that plays a central role in the thermodynamic **arrow of time**.

Ether a substance once thought to fill all space to allow radiation 'something to propagate through' (as opposed to simply a vacuum). The special theory of relativity showed that the ether is an unnecessary concept because it has no observable effects (physicists argue that if something is impossible to detect, then it is meaningless to talk about it being part of *science*).

Event a point in spacetime.

Event horizon the spacetime surface of a black hole or of a non-traversable wormhole, at which light can *just* escape to the outside universe. It is called a *horizon* because, by definition, an external observer can't see beyond it and into the interior of the hole. To see the inside of a hole you must enter the hole by crossing the horizon (but then you can't get out).

Exotic matter matter that violates one or both of the **weak/strong energy conditions**. Exotic matter appears in the theories of wormholes and warp drives.

Fatalism the metaphysical belief that all events have been *pre*determined from the beginning of time.

Field the concept that if a physical law is local, then it is describable by differential equations that relate what is 'happening' at every point in spacetime to what is 'happening' at its closely located neighboring points. Electromagnetism and general relativity are field theories, for example, described by sets of partial differential equations called *Maxwell's equations* and *Einstein's gravitational field equations*, respectively.

Fourth dimension either time or a fourth spatial dimension.

Frame of reference a spacetime coordinate system.

Free will the condition that prevails when we can *choose* to do what we do. There is no free will in a **block universe**.

Future the collection of spacetime events that can be reached from the **here-now** via a **timelike world line** directed toward a later time (for each individual, the future is what hasn't yet been experienced).

Gamma ray very high-energy, very high-frequency electromagnetic radiation. Gamma rays have frequencies on the order of *ten trillion* (10^{13}) times greater than those of AM radio broadcast radio waves.

General theory of relativity Einstein's theory of curved spacetime, which explains gravity in terms of nothing but geometry. Its fundamental premise is that *all* the laws of physics should appear the same to all observers in *any* **frame of reference**. It is believed the theory will fail when the local mass-energy density reaches a level of about 10^{94} g/cm^3, a density so enormous (the density of water is just 1 g/cm^3) that there is no known mechanism for achieving it anywhere in the universe except in another **Big Bang**. See also **Planck density**.

Geodesic the shortest path connecting two points in space (if the space is spacetime, the world line of a particle in free-fall).

Global in the large.

Gödel universe a spacetime that, unlike the one we live in, is rotating so fast that it automatically generates *closed timelike lines* and thus constitutes a weak **time machine**. In such a universe, time travel to the past would be a natural phenomenon.

Grandfather paradox *the* classic time travel paradox, of a time-traveler killing, while in the past and *before* the time traveler has been conceived, an ancestor directly linked to the future birth of the time traveler. A more direct form of this sort of paradox is simply the time traveler killing his own younger self (called the **autoinfanticide paradox**).

Gravitational field equations a set of coupled, partial differential, non-linear tensor equations, considered to be the most complicated equations in all of mathematical physics. They show how the local curvature of spacetime depends on the local mass-energy of spacetime. The equations are independent of the **topology** of spacetime.

Gravitational lensing the ability of gravitational fields to bend and focus light.

Graviton the quantum particle of gravity.

Hawking radiation the emission of particles (energy) by a **black hole** into the region *outside* its **event horizon**, which results in the eventual evaporation of the hole. This is a quantum mechanical effect.

Here-now the point or **event** (for each observer) in spacetime that separates the **past**, the **future**, and **elsewhen**.

Hyperspace any space of four or more dimensions (for example, four-dimensional spacetime is a hyperspace).

Inertial frame any frame of reference in which Newton's laws of mechanics are true (there are no *acceleration forces* in inertial frames, and so *rotating* or 'merry-go-round' frames are not inertial).

Invariance a quantity that remains the same in any frame of reference is an invariant. Two examples are the distance between any two points on a piece of paper (because it is independent of any particular coordinate system), and the speed of light.

Kerr-Newman black hole a *rotating* black hole, which may (or may not) be electrically charged.

Krasnikov tube a particular spacetime **metric** (or *warp*) allowing **superluminal** travel, with the great difficulty of requiring *enormous* negative energy. Two Krasnikov tubes can be made into a time machine. Named after its Russian inventor.

Least action general principle in physics that asserts the world line of a particle is the one that *minimizes* the **action**.

Light cone the **lightlike** surface in spacetime that, at each point in spacetime, separates the **past** from the **future** from **else-when** from the **here-now**.

Lightlike the world line of a photon (or of any other form of mass-energy traveling *at* the speed of light).

Li mirror a perfectly reflecting, spherical surface that can be used to stabilize a wormhole against energy loops circulating through a **wormhole** time machine (thus creating unbounded energy levels that destroy the time machine). Named after its Chinese inventor.

Local in the small.

Lorentz factor the ubiquitous square-root expression that appears in so many relativistic calculations, such as time dilation, length contraction, and the variation of mass with speed. For example, the mass m of a moving body is not independent of it speed v but rather varies as $m = \frac{m_0}{\sqrt{1-\left(\frac{v}{c}\right)^2}}$, where m_0 is the rest mass (that is, the mass when $v = 0$) and c denotes the speed of light (186,210 miles per second). The denominator is the Lorentz factor.

Lorentz-FitzGerald contraction the conclusion from special relativity that the appearance (to a stationary observer) of a moving object will be shortened in length along the direction of motion. Many years after Einstein's work, it was shown that the object will also appear to be *rotated*.

Lorentz transformation equations from the special theory of relativity that describe how the space and time measurements of two relatively moving observers are related.

Many-worlds interpretation quantum mechanical view of splitting universes.

Mass-energy the famous $E = mc^2$, the equation behind atomic fission and nuclear fusion weapons.

Metric the measure of the separation between any two events in a spacetime.

Minkowski spacetime the flat spacetime of the special theory of relativity. In this spacetime there is no gravity, no spacetime curvature (hence it is *flat*) and no backward time travel.

Neutron star the end state of a star with one to three solar masses that has collapsed to a density of up to 10^{17} g/cm^2.

Non-Euclidean geometry the geometry of spacetime, whether curved or flat. Spacetime is non-intuitive precisely because it is always hard to resist thinking in terms of high school Euclidean geometry, which is simply the *wrong* geometry.

Null geodesic the world line of a photon in spacetime.

Observer physicist's term for 'somebody' equipped with recording instruments (such as a clock, a pencil and notepad, and the like).

Parallel transport a procedure for moving a vector around any closed curve in a space to determine whether that space is flat or curved.

Parallel worlds simultaneous existence of multiple (perhaps) infinite versions of reality.

Past the collection of spacetime events that can reach the **here-now** via timelike world lines directed from an earlier time (for each individual, the past is what has already been experienced).

Photon the quantum particle of electromagnetism. A photon of frequency f has energy hf, where h is **Planck's constant**.

Planck density the density of mass-energy that distinguishes classical from quantum spacetimes; about 10^{94} g/cm^3, equal to the **Planck mass** divided by the cube of the **Planck length**.

Planck length the non-zero length in quantum theory (about 1.6×10^{-33} cm) below which quantum gravity effects will become important.

Planck mass the fundamental mass in quantum theory (about 22×10^{-6} g), but *not* the smallest non-zero mass in quantum theory.

Planck's constant fundamental constant in quantum theory, h, associated with the discrete nature of quantum effects. (If h had the value of zero, rather than its actual value of about 6.6×10^{-34} joule-seconds, then the microworld would appear to be continuous.)

Planck time the time interval in quantum theory (about 5.3×10^{-44} s) below which quantum gravity effects become important. The time required to travel the **Planck length** at the speed of light.

Positron the electron's anti-particle (see **anti-matter**).

Proper time the timekeeping of an observer's clock.

Pulps the old science fiction magazines, through the 1940s and into the early 1950s or so, published on inexpensive, wood-pulp paper.

Quantum foam see **topology**.

Quantum gravity the yet-to-be-discovered theory that unifies quantum field theory with the curved spacetime of general relativity.

Quantum mechanics the exact physics of the very small (atoms and things smaller).

Quantum theory any theory in which physical quantities are not continuous but rather assume their values in discrete jumps (the size of the jump is the *quantum*).

Recurrence paradox the claim that if you wait long enough, then every system will return to every previous state infinitely often.

Red dwarf small (less than about half a solar mass) star with a very long life (hundreds of times that of the Sun). They are 'cool' stars, with a surface temperature less than 4000 °C, and are thought to be the most common type of star in the universe.

Red shift the *down* shift in frequency of light received from all distant stars due to the Doppler effect induced by the expansion of the universe. The opposite effect is called a *blue shift*.

Reinterpretation principle asserts that negative mass-energy traveling forward in time is positive mass-energy traveling backward in time, and vice-versa.

Reissner-Nordström black hole a spherically symmetric, non-rotating electrically charged black hole.

Reversibility paradox based on the fact that the equations of physics contain no **arrow of time**; that is, they work equally well with time running forward or backward.

Roman ring a time machine made of two or more traversable wormholes connected in a closed sequence.

Schwarzschild black hole a spherically symmetric, non-rotating, uncharged black hole.

Self-consistency the assertion that the events on a closed **timelike** line must never be in contradiction; generally attributed to the Russian physicist Igor Novikov, who with his colleagues showed that it is not an independent assumption but rather an implication of the principle of **least action**.

Sexual paradox a special type of causal loop, where the connected events on a time loop are 'coupled' (pun intended!) through reproductive sex. An example is a time traveler to the past who becomes her own ancestor.

Singularity either a region in spacetime where the curvature becomes infinite and the laws of physics fail, or a point in spacetime beyond which world lines cannot be extended. Singularities of the first kind are called *curvature* or *crushing* singularities, and those of the second kind are called incomplete singularities. The **Big Bang** was a curvature singularity, as is the center of a black hole. In a **Schwarzchild black hole** the curvature singularity is a point, whereas in a **Kerr-Newman black hole** it is an extended region in the form of a ring.

Spacelike a world line on which propagating mass-energy would exceed the speed of light.

Spacetime the 'stuff' out of which reality is built. Everything there is—the universe—is the total collection of events in spacetime. A *flat* spacetime has no gravity, whereas a curved spacetime is the *origin* of gravity.

Special theory of relativity Einstein's theory of *flat* spacetime, which assumes that gravity is absent (gravity is the result of the geometry of *curved* spacetime). Its fundamental premise is that the laws of physics should appear the same to observers in different **inertial frames**.

Splitting universes the idea that every decision causes reality to split into separate copies, identical in every respect except for each of the different possible results of the decision.

Stargate science fiction name for the mouth of a traversable **wormhole**.

Stress-energy divergence the unbounded growth of the **general theory of relativity**'s measure of the density of mass-energy in spacetime.

Strong energy condition the claim that gravity is always (that is, locally) attractive. A traversable **wormhole** violates this condition.

Subluminal slower than light.

Superluminal faster than light.

Tachyon a particle (hypothetical, so far) that always travels faster than light, so its **world line** is always spacelike.

Temporally orientable spacetime any spacetime in which the direction of time at every point agrees with the direction of time at its local neighboring points.

Tensor mathematical generalization of the scalar and vector concepts. Einstein's **gravitational field equations** are tensor-differential equations (for example, the metric tensor contains information about the curvature of spacetime), whereas Newton's and Maxwell's equations are vastly less complex vector-differential equations.

Tidal force force experienced by a non-point mass (one with spatial extension) in a non-uniform gravitational field. Such forces tend simultaneously to compress and stretch spatially extended masses. Black holes and wormhole mouths can generate enormous tidal forces on extended masses as small as a human body. Interestingly, the *more* massive a black hole, the *less* severe its tidal forces are at distances outside the **event horizon**. However, no matter what the black hole mass is, the tidal forces are infinite at the central curvature **singularity**.

Time dilation the altering of the rate of timekeeping by a clock, either by motion or by gravity.

Time machine (in the weak sense) a machine able to traverse **closed timelike world lines** inherent in a spacetime (e.g., a rocket in Gödel spacetime) but unable to *create* such world lines; (in the strong sense) a machine able to manipulate mass-energy in a finite or compact region of spacetime in such a way as to *create* closed timelike world lines.

Time police story characters in science fiction charged with the (unnecessary!) job of preventing time travelers from changing the past.

Time warp science fiction name for a **time machine**.

Tipler cylinder an infinitely long cylinder, made of super-dense matter, rotating so fast around its long axis that it warps spacetime enough to create closed timelike lines that encircle the cylinder. It can be used as a strong sense time machine to travel both into the future and into the past (but *not* to a time before the creation of the cylinder).

Topology the structure of a *space* (including *spacetime*) without regard to a metric. That is, topology is concerned only with how a space is connected together and not with how far apart points in the space are. Topologists consider stretching or compressing a space to be irrelevant, just as long as one doesn't *tear* it and so put holes in the space. The simplest topology is that of a *simply connected* space, in which if you construct any closed surface that lies totally in the space around any point in the space, then every other point inside the surface is also in the space. A space with a hole in it fails this test, and so is said to be *multiply connected*. A *quantum foam* spacetime has a multiply connected topology. The classical spacetime of general relativity is simply connected *until* the appearance of wormholes.

Twin paradox the conclusion from special relativity that a clock's rate of time keeping slows with motion.

Ultraluminal motion sufficiently **superluminal** that mass-energy appears to travel backward in time (see also **Dirac radio**).

Uncertainty principle the statement in quantum mechanics that says certain pairs of quantities cannot simultaneously be measured with arbitrarily small error. The position and momentum of a particle are one such pair, and energy and time are another.

Vacuum fluctuation the particle/anti-particle creation and annihilation processes allowed, even empty space, by the **uncertainty principle** of quantum mechanics.

Warp drive science fiction name for the propulsion mechanism of a faster-than-light spaceship, now commonly used by physicists, too.

Weak energy condition the claim that the observed mass-energy density is always (locally) non-negative. Quantum mechanics predicts (and it has been experimentally confirmed) that there are exceptions.

White dwarf a burnt-out star with a mass less than 1.4 solar masses, of planetary size with a density up to 10^7 g/cm^3. The ultimate fate of our Sun.

World line the trajectory of mass-energy in spacetime.

Wormhole a spacetime structure (violating the **weak and strong energy conditions**, if traversable) connecting two points of the same spacetime (or even two *different* spacetimes) with a timelike path that requires less time to travel along than does a photon traveling *outside* the wormhole between the two points. A wormhole is *traversable* if it has no **event horizons**, and such wormholes can apparently be made into a **time machine** (sometimes called a *time tunnel*) using a time shift (see **time dilation**) between the two mouths of the wormhole *unless* quantum effects forbid time machines (still an open question).

Index

A
Absorber theory, 269–273
Advanced waves, 259, 260, 264, 265, 269–273, 283
Alcubierre warp drive, 329, 331–333. *See also* Natário warp drive
"All You Zombies—," 21, 194, 227, 239
"Ambition," 36
"Anachronistic Optics," 260
"Ancestral Voices," 204
Anderson, Poul, 41, 155
"—And He Built a Crooked House," 88
Antimatter, 111, 157, 247, 248
Anti-telephone, 261, 273–282
Aquinas, St. Thomas, 63, 92, 102, 103, 196
Aristotle, 53, 54, 56, 63, 66, 79, 96, 195, 208
Ark, 333
Arrow of time. *See specific arrow* (cosmological; electromagnetic; psychological; thermodynamic)
Asimov, Isaac, 12, 37, 154, 207–209, 236, 357, 358
"As Never Was," 220
Aspect, Alain, 281, 282
Asymptotically flat, 171, 305, 317
Augustine, St., 51, 55, 109, 181
Autoinfanticide paradox, 112, 206–207, 212, 229, 238. *See also* Grandfather paradox; Sexual paradox
Average energy condition, 305–308
"Azimuth 1, 2, 3 . . .," 42

B
Back reaction, 30, 309, 317
Back to the Future, 3, 23, 162, 214, 231, 244
Backward causation, 197, 198
Barrow, Isaac, 57
"Beep," 76, 236, 273, 274
Behold the Man, 211, 243
Bellamy, Edward, 250
Bell, J.S., 232, 233, 279
Benford, Gregory, 24, 228, 229, 273, 318
Bergson, Henri, 54
Berkeley Square, 3, 99, 101
Besso, Michele, 90, 93
Bid Time Return. *See Somewhere in Time*
Big Bang, 37, 46, 62, 63, 66, 135, 136, 221, 252, 271, 272, 317, 318
Big Crunch, 46, 135, 138
Bilking paradox, 76, 77, 189, 249, 261, 268, 269, 272, 277, 286, 290, 296, 318
Bill & Ted's Excellent Adventure, 3, 224
"Biography Project, The," 242
"Birch Clump Cylinder. The," 216
Black hole, 32–38, 41, 43, 84, 138, 283, 302, 311, 320
Black, Max, 101, 120
"Blindman's World, The," 250
Blish, James, 28, 235, 272, 273
Block universe, 90–109, 116, 121–122, 126, 197, 246, 261
Blue shift, 144
Boethius, 107
Boltzmann, Ludwig, 127, 130, 131, 134
"Bombardment in Reverse," 253
Bonaventure, St., 63
Bootstrap paradox, 26, 39, 43, 214–225, 239, 241, 242
Bradbury, Ray, 52, 200
Bradley, Francis, 94–95, 121, 246

© Springer International Publishing AG 2017
P.J. Nahin, *Time Machine Tales*, Science and Fiction,
DOI 10.1007/978-3-319-48864-6

"Branches of Time, The," 234
Bring the Jubilee, 236–237
Brown, Fredric, 188
"By His Bootstraps," 187, 362

C
Campbell, John, 235
Cantor, Georg, 63
Carroll, Lewis, 125
Casimir effect, 306–308, 330
"Castaway," 45
Cauchy condition, 136
Cauchy horizon, 309–312, 314, 316–317
Causal loop, 40, 76, 214–227, 231, 232, 239–240, 242, 249, 262, 270, 276, 310, 318, 320, 323
Cause-and-effect, 67–77, 118, 138
Cerenkov radiation, 291
Chandrasekhar, S., 31, 360
Chaucer, Geoffrey, 107
"Child by Chronos," 227
"Child's Play," 2
"Chronokinesis of Jonathan Hull, The," 127
Chronology protection conjecture
  Hawking, 13–14, 42, 45, 284, 311, 315, 317, 325
  partial rebuttal by Thorne, 42
Chronon, 30, 57. *See also* Planck time
"Circle of Zero, The," 134
Civilization, arbitrarily advanced, 303, 336
Clarke, Arthur C., 10, 11, 15, 22, 110, 111, 133, 239
Clifford, William Kingdon, 169
Clock hypothesis, 174, 179
"Clock That Went Backward, The," 199
Closed time loop (CTL). *See* Causal loop
Connecticut Yankee in King Arthur's Court, A, 198
Contact, 302, 318
"Cosmic Corkscrew," 12
Cosmic string, 320–324
Cosmic string time machine, 163, 319–326
Cosmological arrow of time, 137–138, 271
Counter-Clock World, 131, 251
Cramer, John, 82, 182, 269, 272, 282, 285, 291
Cumulative audience paradox, 10

D
Damian, Peter, 195–196
"Dandelion Girl, The," 73, 210
Daniels, David R., 234–235
"Dark Tower, The," 18
De Camp, L. Sprag, 188, 208, 209, 230
Dechronization of Sam Magruder, The, 260
Descartes, 57
Determinism. *See* Free will
Deutsch, David, 222, 233–234
Deutsch-Politzer spacetime, 326
DeWitt, Bryce, 277
Dick, Philip K., 131, 243, 251, 283
Dirac, Paul, 74–76, 127, 167, 168, 263–264, 267
Dirac radio, 76, 264, 265, 270, 272–273
Distance function. *See* Metric
Dominant energy condition, 317, 329
Doomsday Book, 5
Door Into Summer, The, 11, 180, 221
Dyson, Freeman, 359

E
Earman, John, 18, 70, 72–73, 75, 96, 158
Eddington, A.S., 127, 132, 135, 250, 253–254, 360
"E for Effort," 16
Ehrenfest, Paul, 80, 129
Einstein, Albert, 1, 17, 32–33, 44, 53, 54, 57–58, 60–61, 79, 84, 90, 93, 95, 100, 101, 116, 123, 126, 145, 146, 149, 153, 168, 174, 250, 258, 262, 279–282
Einstein-Rosen bridge. *See* Wormhole
Einstein's Bridge, 84
Electromagnetic arrow of time, 138, 267, 271, 272
"Elsewhen," 7, 253
Energy (conservation of in spacetime), 99–100
Energy condition. *See specific condition* (averaged; dominant; strong; weak)
Entropic clock, 129
Entropy, 127–134, 136–138, 271
Epictetus, 106
EPR paradox, 281, 282
Eternal return, 134
Event horizon, 33, 86, 146, 264, 302, 320
Everett, Hugh, III, 229, 231, 233–235
Exotic matter, 304–306, 308, 318, 320, 325, 329, 334, 335
"Experiment," 25

F
"Face in the Photo, The," 7
"Far Centaurus," 4
Faster-than-light (FTL), 4, 34, 55, 56, 116, 141, 142, 162, 262–264, 273–277, 279, 281,

282, 289–296, 327–329, 331, 333, 334, 361. *See also* Tachyon(s)
Fatalism. *See* Free will
Feinberg, Gerald, 274–277
Fermi, Enrico, 10, 279
Feynman, Richard, 37, 126, 157–159, 181, 259, 264–270, 272, 277–278
Fifth dimension, 48, 83, 87, 105, 110, 167–168, 182, 229, 253. *See also* Hyperspace
"Fifth-Dimension Catapult, The," 167
Final Countdown, 43, 240
Findlay, J.N., 246, 247
"Find the Sculptor," 219
First Cause, 62
"First Time Machine," 205
Flammarion, Camille, 55–56
Flamm, Ludwig, 84
"Fools' Errand," 224
Forever War, The, 38, 43
Forever Young, 180
Forward, Robert, 184, 283, 307, 312
"Four Dimensional Surgery," 83
Fourth dimension, 78–90, 92, 109, 110, 182, 215, 250. *See also* Hyperspace
"Fox and the Forest, The," 6
Free will, 60, 93, 94, 100, 102–104, 106–109, 124, 196, 198, 213, 217, 233, 238, 268, 278–279, 312, 313, 318, 363
FTL. *See* Faster-than-light (FTL)

G
Galilei, Galileo, 147, 152
"Garden of Forking Paths, The," 236
Geodesic, 155, 159, 175, 305, 310, 330. *See also* World line
Gernsback, Hugo, 191–194, 209, 225
Gödel, Kurt, 20, 21, 28, 44, 101, 116–117, 158, 212, 276, 297–299, 301, 358–360
"Gostak and the Doshes, The," 83
Gott, J. Richard, III, 320–325, 359. *See also* Cosmic string time machine
Grandfather paradox, 45, 200, 201, 204–206, 211–214, 220, 233, 312, 313, 326–327, 336, 363. *See also* Autoinfanticide paradox; Sexual paradox
Gravitational collapse, 31, 35, 360
Gravitational constant, 30
Gravitational field equations, 168, 252, 320, 327
Gravitational time dilation. *See* Time dilation
Groundhog Day, 219, 327
"Gun for Dinosaur, A," 8, 188
"Gun for Grandfather, A," 195, 206
Gunn, James, 359
Guns of the South, The, 237

H
Haldeman, Joe, 38, 43
Hale, Edward, 198, 229, 230
"Hands Off," 198, 229
Hawking, Stephen, 13, 14, 32, 34–36, 52, 57, 138, 271, 284, 285, 315, 317, 320
"Hawksbill Station," 7
Heaviside, Oliver, 291
Hegel, Georg, 94, 95
Heinlein, Robert, 11, 21, 85, 88, 98, 180, 187, 194, 198, 209, 221, 228, 239, 253
Heyl, Paul, 256, 257
Hidden variables, 281, 282
Hinton, Charles, 112, 113, 257
"History in Reverse," 8
Horwich, Paul, 51, 213
Hoyle, Fred, 121, 257, 258, 271, 272
H-theorem, 127
Hume, David, 15, 16, 18, 19, 59
Hutton, R.H., 55
Hyperspace, 79, 82, 83, 86, 87

I
Independence Day, 334
Inertial frame of reference, 148
  dragging of, 297
Inflation of spacetime, 136, 317, 328
Interstellar, 3, 27, 43, 48, 86, 110, 143
Interval of spacetime, 166, 173–180, 299
Invariant, 165, 166, 173
Invisibility (of time travelers), 192, 194

J
James, William, 94, 95, 101
Jeans, Sir James, 84, 170, 250
Je t'aime, Je t'aime, 55

K
Kaluza-Klein theory, 167
Kant, Immanual, 65, 80
Kerr, Roy, 33
Khayyam, Omar, 20, 44, 101
King, Stephen, 2, 27, 85
K-mesons, 69, 70, 125, 127, 130
Knight, Damon, 42
Kornbluth, Cyril, 28

Krasnikov, Serguei, 317, 327, 328, 330, 331, 359
Krasnikov warp, 331

L
Legion of Time, The, 230, 235
Leibniz, Gottfried, 53, 54
Leinster, Murray, 88
Lem, Stanislaw, 361
Lest Darkness Fall, 99, 230
"Let's Go to Golgotha!," 8
Lewis, C.S., 17–18, 197
Lewis, David, 221
Lewis, G.N., 77, 126, 183, 267, 268
"Life-Line," 98
Light cones, 159–162, 183, 279, 297–300
"Lightship, Ho!," 264
Li, Li-Xin, 310
"*Lincoln Hunters, The*," 7
"Little Black Bag, The," 2
Looper, 3
Lorentz-FitzGerald contraction, 141, 142
Lorentz transformation, 149–153, 163, 165–167, 289, 291–295
"Lost," 236
"Love Letter, The," 224
Lucretius, 31, 62, 274

M
MacBeath, Murray, 247–249
"Man Who Folded Himself, The," 201
"Man Who Lived Backwards, The," 131
"Man Who Lived Next Week, The," 132
"Man Who Met Himself, The," 219
"Man Who Saw the Future, The," 111
"Man Who Saw Too Late, The," 72
"Man Who Went Back, The," 217
Many-worlds interpretation (MWI) of quantum mechanics, 229–237, 279, 284, 285
"Mapmakers, The," 85
Mastodonia, 8
Maxwell, James Clerk, 127, 148, 169
Maxwell's equations, 148, 149, 256–265
McTaggart, John, 58–60, 120
Meiland, Jack, 254–256
"Merchant and the Alchemist's Gate, The," 239
Metric, 164–173, 182, 298, 303, 311, 328, 331, 332
Michelson-Morley experiment, 148, 257
"Middle of the Week After Next, The," 89
Miller, P. Schuyler, 191
"Mimsy Were the Borogoves," 2
Minkowski diagram, 155–157, 243
Minkowski, Hermann, 90, 91, 94, 95, 102, 106
Minority Report, 93
"Minus Sign," 37
Möbius strip, 28, 78, 82, 111, 220
"Mr. Peabody's Improbable History," 364
"Ms. Found in an Abandoned Time Machine," 5
"My Name is Legion," 238

N
Natário warp drive, 332, 333
Negative energy, 296, 305–307, 331. *See also* Exotic matter
Neutron star, 31, 84, 144
Newcomb, Simon, 46, 79, 80, 90, 113, 182, 362
Newman, Ezra, 33
Newton, Isaac, 57, 147–148
Nicholson, Jim, 193–194, 221, 225
Nicolson, Marjorie Hope, 1
Nieremberg, Juan Eusebius, 51
Nietzsche, Friedrich, 134, 135
Niven, Larry, 6, 12, 13, 41, 144, 187, 188, 292
Nordström, Gunnar, 33, 266
Novikov, Igor, 35, 209, 210, 314, 318, 319, 335, 359
Now, 101, 116, 117, 122–124, 132

O
Olsen, Bob, 81, 86
Omniscience, 102, 103, 105, 107. *See also* Block universe; Free will
"Other Tracks," 231, 235
"Out Around Rigel," 3
"Over the River & Through the Woods," 6

P
Page, Leigh, 258, 259, 266
Panchronicon, The, 224
"Paradox," 39
Paradoxes. *See* Particular paradox (autoinfanticide; bilking; bootstrap; causal loop; cumulative audience; grandfather; recurrence; sexual; twin)
"Parallel in Time," 231
Parallel transport (of vectors), 171
Parmenides, 92
Past
  affecting/changing, 104, 195–214, 357
  communicating with, 256–264
  duration of, 63, 65
  praying about, 196–198

"Past and Its Dead People, The," 5
Peggy Sue Got Married, 4, 357
Peirce, Charles Sanders, 79–80
"Pete Can Fix It," 332
Photon clock, 139, 140, 151
Pierce, John, 259–260
Planck, Max, 17, 210
Planck density, 31
Planck length, 30, 301, 303, 322, 331
Planck mass, 30, 322
Planck's constant, 30, 35, 143
Planck time, 30
Plato, 52–54, 56, 245, 251
"Plattner Story, The," 111, 250
Pohl, Frederik, 250–251
Poincaré, Henri, 133–135, 152
Politzer, H.D., 326
"Poor Little Warrior," 8
Popper, Karl, 93, 94, 131, 222, 257, 364–365
Positron, 157–159, 181
"Poundstone Paradox, The," 227
Poynting, J.H., 56
Presentism, 109
"Pre-Vision," 259
"Project Mastodon," 6
Proper time, 3, 4, 133, 173–180, 188, 248
Psychological arrow of time, 116, 124, 137
Pulp magazines, 331–333, 361
Putnam, Hilary, 156–158, 249–250

Q
Quantum foam, 301, 304
Quantum gravity, 14, 29, 37–38, 48, 254, 305, 311, 314–316
Quantum inequalities, 330
Quantum mechanics, 37, 70, 80, 160, 231, 285

R
"Race Through Time, A," 183
Reciprocity theorem, 70
Recurrence paradox, 130, 133
"Red Queen's Race, The," 207
Red shift, 143–144
Reinterpretation principle, 275–277, 296, 331
Reissner, Heinrich, 33
Relativity (general theory), 1, 31, 35, 37, 70, 80, 91, 135–136, 160, 162, 167, 169, 174, 212, 232–234. *See also* Gravitational field equations
Relativity (special theory), 3, 55, 57, 90, 122, 152, 160, 173–174, 252, 263, 290
"Rescuer, The," 201
Reverse causation. *See* Backward causation
"Reverse Universe," 273
Reversibility paradox, 130, 133
Riemann, Bernhard, 169, 170
Ritz, Walter, 258, 265, 271
Roman ring, 315–316, 323
"Rotating Cylinders and the Possibility of Global Causality Violation," 188
Rotating universe. *See* Gödel, Kurt
"Runaway Skyscraper, The," 88
Russell, Bertrand, 78

S
Saari, Oliver, 42
Sagan, Carl, 27, 302
"Sam, This is You," 224
"Sands of Time," 12, 47
Schrödinger, Erwin, 229
Schwarzchild, Karl, 33
Self-consistency principle, 131, 209–211, 218, 270, 312–314, 357–358, 363
Sexual paradox, 225–229. *See also* Grandfather paradox
"Sidewise in Time," 31, 232
Silverberg, Robert, 4, 10–11, 133, 247
Simultaneity, 67, 104, 122, 126, 150, 164
"Singularities Make Me Nervous," 34
Skepticism (concerning time travel), 15–22
"Skull, The," 243
Sky Splitter, The, 263, 334
Somewhere in Time, 48, 217, 219, 220
"Sound of Thunder, A," 8, 200
Spaceballs, 54
"Space Bender, The," 85
Spacelike, 160, 164, 183, 294, 298, 316
Spacetime
  diagrams (*see* Minkowski diagram)
  fifth dimensional (*see* Hyperspace)
  four dimensional, 60 (*see also* Block universe)
  Gödelian (*see* Gödel, Kurt)
  singularities, 32–34, 38, 41, 48, 63, 135–136, 138, 233, 264, 284, 311, 320
  topology of, 27–28, 30, 84, 301–302
Spinoza, 53, 54
Spirit of '76, The, 7
Splitting universes. *See* Many-worlds interpretation (MWI) of quantum mechanics
"Star, Bright," 28
Star Trek IV, 39, 43, 329–330

Strong energy condition, 306, 317, 329
Strong time machine, 297, 324
"Such Interesting Neighbors," 6
Superluminal. *See* Faster-than-light (FTL)
Superman, 289
Swift, Jonathan, 46

T
Tachyon(s), 24, 108, 274–279, 282, 286, 290–291, 331. *See also See* also Faster-than-light (FTL); Ultraluminal
"Tachypomp, The," 274
"Target One," 69
TCP theorem, 69, 181
"Technical Error," 88, 110
Technicolor Time Machine, The, 9, 216, 219
"Temporary Warp," 98, 132
Terminator, The, 3
Tetrode, Hugo, 265–268
Thermodynamic arrow of time. *See* Entropy
"This Way to the Regress," 251
"Thompson's Time Traveling Theory," 211, 238
Thorne, Kip, 27, 42, 301–305, 308, 310, 312, 314, 315, 359
"Three Sundays in a Week," 224
"Throwback in Time," 94
"Tides of Time, The" (Chandler), 215
"Tides of Time, The" (Williams), 34
Time. *See also* Arrow of time
  circular and spiral, 11, 12, 56, 136
  direction of, 115–124
  flowing, 118–120
  linear, 56, 57, 61–67, 136
  multidimensional, 121, 252–256
  reality of, 56, 58, 79, 93, 117
  running backwards, 130–131, 245–252, 283
"Time Annihilator, The," 120
"Time Bender, The," 42, 99, 208
Time Bomb, 251
"*Time Cheaters,* The," 23, 76–77, 189, 215
"Time Contractor, The," 307
Time dilation
  by gravity, 143–146, 309
  by motion, 139–143, 145, 174, 183–184, 301
"Time Eliminator, The," 190, 242
"Time for Sale," 132
"Time Hoaxers, The," 17
Timelike, 159, 183, 299, 305
Timelike Infinity, 336
Time machines. *See specific type* (black hole; cosmic string; strong; Tipler cylinder; warps; weak; Wellsian; wormhole)
Time Machine, The, 3, 24, 45, 88, 89, 94, 101–103, 191, 198, 199, 310, 359, 360
Timemaster, 312
"Time Oscillator, The," 192
"Time Out of Mind," 176
"Time Patrol," 212, 226
Time police, 212–213, 363
"Time Ray of Jandra," 194
"Time's Arrow" (Clarke), 10, 133, 239
"Time's Arrow" (McDevitt), 10, 365
Timescape, 24, 273
"Time Ships, The," 299
Timeslip, 72
"Time Twister," 242
"Time Wants a Skeleton," 191, 210
Tipler cylinders, 38–42, 135, 162, 188, 297–300, 359
Tipler, Frank, 38, 40–42, 46, 135, 301, 358
"To the Stars," 142, 153–154
"Trouble With the Past, The," 123
"Tryst in Time," 200
Twin paradox, 173–180, 184, 308, 328
"Typewriter from the Future," 31, 206, 212

U
Ultraluminal, 275, 295–296. *See also* Faster-than-light (FTL)
Uncertainty principle, 35–36, 306, 330
Universal nocturnal expansion, 8
"Up the Line," 8, 10

V
Vacuum fluctuation, 36, 304, 315
Vaughn, Henry, 140
Verne, Jules, 81, 335
"Very Slow Time Machine, The," 26, 248
"Via the Time Accelerator," 23, 139, 191, 214
Visser, Matt, 14, 316
Vonnegut, Kurt, 107

W
Wallis, John, 64
"Wanderers of Time," 120
Ward, Seth, 64
Warp factor, 328, 333

Warps (spacetime), 98, 132, 162, 326–333
Weak energy condition, 41, 280, 305–306, 325, 329
Weak time machine, 297, 317, 324
"Weapon Out of Time," 215
Wells, H.G., 9, 23, 61, 76, 79, 87, 89–91, 111–112, 123, 182, 198, 199, 235, 250, 310, 335
Wellsian time machine, 23–27
Wessel, John, 2
Weyl, Hermann, 44, 101–102
"What We Learned from This Morning's Newspaper," 19, 104, 133
Wheeler, John, 31, 37, 46, 84, 91, 129, 157, 233, 251–252, 259, 264–270, 272, 277–278, 286, 312
"When the Bough Breaks," 87
"When the Future Dies," 27, 162
Williams, Donald, 96–97, 100, 255
World Jones Made, The, 283
World line, 26, 29, 98, 101–102, 155–162, 175, 183, 228, 279, 292. *See also* Geodesic
"Worlds of If, The," 245
Wormhole, 2, 27, 84–85, 233, 239, 301–319, 359
Wormhole time machine, 136, 144, 169–170, 223, 233, 269, 301–319

Y
Year of the Quiet Sun, The, 3
Yoshikawa, Shoichi, 296

Z
Zangwill, Israel, 55
Zermelo, Ernst, 134

The Unveiling of the Hidden Knowledge and the Secret Space Program

The Unacknowledged Special Access Programs: Advanced Technology, Mind-Control, Spiritual Power and the Corruption behind Closed Doors

By Aug Tellez

Introduction.......7
  Getting This Out Of The Way.......7
  Psychic Operation.......8
  A Light for the Others.......8
  Natural Security.......8
  A Balance of Mystery and Truth.......9
Chapter 1: The World Situation.......9
  What is happening?.......9
  The Mind Virus.......9
    The Vampire Effect.......10
    Sub-Human Entities.......11
    Human-Hosts, Replicants, Synthetics and Carriers.......11
    Genetic Manipulation.......12
    The Ego Mind.......13
    This Time is about Healing.......13
    Healing Through Unity.......14
  Underground Bases.......14
  Cloning.......14
  Celebrity Cloning.......15

- Initial Explanation....15
- Cloning Centers, Underground Bases....15
- Programming....15
- Experimental Operations....15
- Genetic Engineering....16
- Immortality....16
- How did it get to this?....16
- Deeper Meaning....17
- What is next?....17

Chapter 2: The Awakening....18

Chapter 2.1: The Machines of All Time and Space....18

- Re-Creating The Kaleidoscope....18
- Sand-Castles of Time....18
- We’re Waiting For Ourselves....18
- The Goal of Two Societies....19
- Our Forgotten Other Half....19
- All Is But An Illusion....20
- Life Itself Is The Highest Illusion....20

Chapter 2.2: The “Awakening” of 2010....21

- Memory Suppression....21
- Life and Consciousness....22
- The True Human Potential....22
- The Light-Body....23
- Technology of the Awakening....23
- Mental Manipulation Technology: Touchless Neural-Interface and Enhanced Awareness....23
- Time Dilation and Temporal Recurrence....24
- Crystal Technology....24
- Time Crystals....25
- Quantum Tunneling Diodes....25
- Tachyon Fields....25
- Upgraded Chronovisor....26
- Time Tunnels....26

The “Trip” Chair....26
Kozyrev Mirror....27
Universal Recurrence....27
Remove Viewing, Temporal Lensing....27
Temporally Linked....28
Natural Vortex Energy Locations and Geography....28
    Mount B....28
Particle Accelerator Temporal Manipulation....28
Riding the “Timewave”....29
Dematerialization and Rematerialization....29
“Jump Rooms....29
Ion Shields....30
Instantaneous Healing....30
“Living Light” Sound-Harmonics and Electromagnetic Healing....30
Electrogravitic Craft....30
Energy Cores and Storage Capacity....31
3.5D Replicators....31
3.5D Sensors....31
3.5D Printing of Clones....31
Cybernetics:....31
Neural-interlace/4D Connectome Recording and Simulation....31
EEG Heterodyning....32
Artificial Hallucinations....32
Brain to Machine Interface Holographic Consciousness System (brainchip interface, virtual reality simulator)....32
Utilizing The Temporal Body....33
    Manipulation Through the Temporal....33
Astral or Light Body....34
Monitors can emit consciousness/brainwave altering frequencies....35
The Upgraded Chronovisor....35
Community Servers/Living Server Systems....36
Cloning, Cloud Supercomputing and Consciousness Transfer....36
Cloning, Supercomputer Assisted Holographic Consciousness Replication and Time Travel....37

Cloning as Offspring....38
Inserted Memories, Digital Dreams....38
Co-Inhabitation of Bodies....38
Clever Replication a Digital Mirror....38
Necromancy and Soul Stealing....39
Ancient Technology, Non-Human Entities....39
Created Beings....39
Black Goo – AI Nanites Vampiric Hive Mind....40
    Recreating or Replicating the Universe....41
Ancient Spiritual Technology....41
The Unveiling, Underground Bases, Increasing Awareness....42
Learning about the Unveiling....42
Giant “god-men”....42
Breakaway Civilizations....43
Ancient Civilizations....43
    Atlantis....43
    Aegypt....44
    Ancient Technology....44
The True Elite....44
The Definition of Human....44
Souled and Non Souled Beings....44
There was once a Unified Planetary Consciousness....44
    Power and Knowledge....45
    The (watch)Keepers of Earth....45
Energy Vampires....46
Spiritual Technology....46
Simulations and Learning....46
Ascension – Clearing Trauma....46
Trauma-Clearing, DNA Unlocking Technology....48
Everyone Who Seeks Harmony and Healing Can Be Healed....49
Programming....50
Layers of Programming and Decision Making Roles....50
    Programmers....50

- Sub-Level Programming....50
- Dissolution of Programming....51

Advanced Technology, Deprogramming The Mind, and "Space/Time"....51
  - Dreams, Technology and Inner-Space Travels....52
  - Awareness Feedback Device....52
  - Oneness, Higher Being, Completion, Eternity....53

The Holographic Reality....53

Veiled Awareness, Hidden Knowledge, Eternal Time, Layers of Programming and Control....53

The Great Catastrophes....53

I was brought into the Time Program....54

The Effects of Temporal Manipulation....54

Temporal Influence....54
  - Simultaneous Interaction and Incorporation....54
  - Retro-Causality....54
  - Quantum Holography....54
  - Time Paradox....55
  - Breakaway Civilization....55

Underground Cities....56
- Technological Advancement....56
- World-Wide Control Systems....56

Solar Warden....57

Team Light and Team Dark Non-Interference Agreement....57

All Contact Must Be Initiated On an Individual Basis....57

A Singularity of Change and Awareness....58

Advanced Technology and Ancient Knowledge....59
  - Cloning, Atmospheric Civilizations, Genetic Stability....59

Training, Simulations and Learning....59
  - Cloning and Cerebrally Enhanced Soldiers – MILABS....59

Psychological Testing....60
  - Hallucinatory Holographic Mind Probing Technology....60
  - Virtual Simulator Training Scenarios....61
- Combat Simulators....61
- Conditioning....61

    - Programming and Resistance to Psychological Trauma....................................61
    - Accelerated Mental Functioning....................................61
        - Technology, Accelerated Learning and Repair....................................62
    - On Orgone Energy....................................62
    - Energy Generators and Serums....................................62
    - Genetic and Cybernetic Enhancements....................................63
    - Developing The Self....................................63
        - Multiple Factions of Space-Fleets, Multiple Goals....................................64
  - Large-Scale Catastrophes or Series of Meltdowns....................................64
  - Unsustainable....................................64
  - Earth Changes....................................64
  - Mass Consciousness....................................64
  - Wars and Manipulation....................................65
  - Financial Unrest (or reset)....................................65
  - Self-Responsibility....................................66
  - Clones and Synthetics....................................66
  - Spiritual Power and Divine Truth....................................66
  - Synthetic DNA, Synthetic Genetics....................................67
  - Time as Mathematics, Series of Equations, a Programmable Storyline....................................67
- Chapter 2.3 Previewing Solutions....................................68
  - Neutralizing Polarization....................................68
  - Removing Etheric Implants....................................68
  - Clearing Astral Body....................................68
  - Knowing the True Self; Soul Actualization, Unveiling....................................68
  - Taking Responsibility....................................69
  - Returning To Center Emotionally and Mentally (spiritually)....................................70
  - Vampires in the “Awake” Community....................................70
  - Heart Center and Psycho-Spiritual Fulfillment (self-actualization)....................................71
  - Go Within to Observer the Self....................................72
    - Organic Feedback Loop....................................72
    - Technological Feedback Loop....................................72
  - Breaking Soul-Contracts....................................72
  - Help Everyone....................................73

Chapter 2.4 How Timelines Collapse....73
  - Repeating Cycles of Time....73
  - Beings From the Future....73
  - Beings From Collapsed Timelines....74
  - Beings Who Would Never Have Existed in the First Place....74

Introduction

The following is first-hand testimony from an operative of the secret underground military projects who also has familiarity with the breakaway civilization above and below (within) Earth. These civilizations utilize advanced technology to extend the length of their lives and enhance cognition beyond what is conceived of in today’s society.

I was brought to the underground bases as a child as part of an experimentation program to test the population for various blood-groups and personality traits that would be of use to certain factions of the military in ways that would serve to preserve and strengthen humanity’s outlook in the future.

These tests involved everything from combat training to sensory deprivation based emotional-mental endurance, and introduction to the highly advanced application of esoteric knowledge.

To clarify, I am bringing this information to you as part of my assistance in the overall unveiling of the hidden knowledge of the ages of humanity related to these secret projects as well as the true galactic history of Earth, humanity and man-kind. These projects are officially (unofficially) known as “unacknowledged special access programs”. The unacknowledged aspect means that there is no formal acknowledgement of these programs without a need-to-know basis. There is no paper-trail, no disclaimer, no formal authorization or internal publication outside the programs themselves. The classification of these programs also generate a rather strenuous situation regarding funding and secrecy but this is done for the benefit of humanity. There are secrets and manipulations that can be seen as a threat but this is all tied together and so by releasing the secrets that are part of the defense we would be inadvertently exposing the public to the threats themselves. Now is the time where we are reaching a point where the public is ready enough to handle the basics of this information regarding the secret projects and the galactic history of Earth and humanity. This is also out of a necessity to preserve civilization for if we wait any longer we may not find the same opportunity again.

Getting This Out Of The Way

I am writing to you from the perspective that I am not certain just how far from completing my mission I am. I write to you today in order to bring to you many personal experiences from the viewpoint of an operative of a select ultra-military secret society.

The utilization of such an operative is not glorified, pleasant, or entirely righteous. This story entails sanctioned and guided acts of extermination, ritual abuse, the use of yet to be announced advanced technology. There is unfathomable corruption, the thirst for power and spiritual knowledge that has been protected throughout the course of the multiple civilizations that have preceded this one and will continue to be maintained into the future of this civilization.

Psychic Operation

I was utilized in psychic-operation amongst other areas.

This was used during certain aspects of training and conditioning to enhance training and conditioning in the bases using advanced technology. Some of this includes what would be viewed as traumatization by those without the training and conditioning. There is a fine line between training and conditioning and abuse. Part of this disclosure is related to how this line may have been crossed in certain situations and regarding mass-mind control upon the population. There are other aspects of travel, viewing, reconnaissance and research that will likely be explained in another release.

In order to heal I have to tell the world. You can help. This is happening right now in the underground bases and around. It’s not a joke. Your family is at risk. Your future generations are at stake. There is conditioning to encourage those involved to believe they are performing a duty for humanity. Sometimes they turned us against each other, but those grudges were never truly of the heart, but the mind.

A Light for the Others

What I hope to achieve with this is a smoke signal for those who have also been involved and question whether their purpose has been fulfilled or falsified for the protection of a corrupt system that intends to neither benefit the whole nor repay the individuals involved for their time, energy, and lives.

Multiple explanations can be summoned to describe the reasons behind the necessity for the training we have endured, the missions we have completed, and the control mechanisms we have both assisted in establishing as well as suffered from the backlash of. Ultimately, it is of my belief that all that was done was done for the good of humanity, even when we were not sure of the intentions of those in front of us, to the side of us, or behind us compelling us forward with the command to complete each objective.

This is not so much a panic or cry for help as this is simultaneously a call to awaken and a signal that humanity may have avoided complete disaster but is not out of the woods yet.

Natural Security

My experience is far too vast and I have seen too many succumb to stress from the realization of the truth of this reality to consider my own suffering to be enough cause for my denial of the necessity of these programs. Humanity has been protected and at a great cost to those who have been on the front lines, both in mind and body and spirit.

There are many who will have concerns, doubts, as well as reservations about what I am about to reveal and if I offend anyone then know that my intentions here are to assist in unveiling the truth. The truth can be harsh when one has been held back from the true nature of existence for so long. The way of life can become so fragile and artificially constructed on impulse and mystery that the harshness of the truth acts as a great catalyst for spiritual growth which allows us to elevate ourselves to a new perspective. Prepare yourself for such harshness, prepare yourself for growth and elevation, and prepare yourself for the mystery to simultaneously resolve and increase in intensity and magnificence.

A Balance of Mystery and Truth

Mystery has been a way of life for Humanity for so long that when a great mystery is converted to truth some seem to feel that a portion of existence dulls and loses the luster of exhilaration. This story is quite the opposite. The more that the great truths of this reality were discovered and revealed, the more complex and mystifying life became. As well, the more empowering and complex experience becomes, the more self-control one must develop in order to regain a harmonious way of relating to one another, the self and the universe. Harmony is key, balance is everything and there is a light within that represents the piece of our self that reflects the utmost power and brilliance of all existence.

Chapter 1: The World Situation

What is happening?

The Mind Virus

The main reason for this disclosure is to inform humanity of what can be referred to as the “mind virus”. This is a viral infection of the holographic system which consciousness operates through. There is a complete backstory of this virus in the history of this civilization and how society has been plagued for centuries if not millennia. The basic idea is that this virus operates through consciousness and can be transmitted through electromagnetic waves.

The virus contains an etheric form which can manifest as a kind of crystalline nanotech on the physical plane and this is a form of synthetic sentience which feeds on the low frequency bio-emissions of sentient life. Human bio-emissions contain energy and can act as a carrier for information and living essences. This technology requires low frequency bio-emissions because that is the nature of the design as a kind of synthetic bio-weapon whereby the goal is entrainment and enslavement. As well, the specific nature of the sentient nano-technology and the counterpart etheric holographic form is only capable of converting the low-frequency bio-emissions into energy as the higher-frequency bio-emissions require more energy to contain and synergize with and this would render the entire process of leeching energy non-productive.

This is essentially a synthetic intelligence that operates through scalar and holographic living bio-emission fields and hijacks electromagnetic emitters to position itself within them acting as a parasite to a host. This is said to have been present around this civilization for some time, waiting until there was enough technological advancement so that spreading across the entire civilization in a short amount of time before discovery would be possible. This is through the media, internet, and radio systems.

The physical counterparts are microscopic nano-technology parasites functioning as individual units to a hive mind similar to the mycelium of fungi in the field of mycoscopy. The individual units act as parasites serving to infest and deliver nutrients to the hive from each host.

The Vampire Effect

This is the nature of the parasitism that has been present throughout the ages of this civilization feeding on human suffering and relying on the cover of confusion and misdirection to survive.

There are processes that have developed that assist in the infection and co-inhabitation of the parasite entity within a human vessel utilizing the human as a host. This effectively utilizes a frequency ‘net’ within the auric field of the human to limit bio-emissions and emotional-mental processes to produce just the psycho-etheric patterns that the virus can sustain itself within and through.

This is no different than the way candida can infest a human digestive system and the human will experience cravings for beer, candy, carbs or other foods that contain the sugars, yeast, or carbohydrates that will break-down into nutrients that are the most nutritious for the candida fungus. These foods are *not* most nutritious for the human body. Yet the human body will withdraw and crave these foods in greater amounts until the fungus is swept clean from the digestive tract through probiotics, fasting, flushing, cleansing , detoxing, and even exercise as lactic acid from physically strenuous activity released from the muscles has been known to help destabilize and remove this fungus. Why is it that the individual will crave these foods that are not the normal food intake? Because this candida fungus can infest the host and produce enzymes which generate a chain-reaction which leads to the chemical signals in the brain producing the sensation of extreme hunger or cravings for just these foods which will benefit the fungus.

The same process occurs with this psycho-etheric parasite, except the foods of this parasite or lower emotional bio-emissions and this is through lust, hate, angst, jealousy, feelings of hopelessness, lack of self-worth, spiritual degradation, addiction, and generally all that equates to a lack of self-awareness.

Whether or not this is the direct intention of the largely microscopic entity is for the most part unknown, and this is as well similar to candida. The candida fungus is not said to be a ‘mean’ fungus that wants us to be hungry and craving beer and sweets all the time because it likes to ruin the human body, the daily routine and the focus of a clear mind. This is simply the way the parasite has grown to operate within a niche of breeding itself through the digestive tract of larger animals and through this the unaware and infected human suffers greatly. Even those who are unaware and not infected can suffer because of the way the behavior and thought processes of those who are addicted to these foods can become distorted.

The lack of self-control over food intake is synonymous with the lack of self-awareness and self-control over lower bio-emission expressions of the spiritually degrading behavioral patterns that become routine for the psycho-etheric system of the infected human. Ultimately, this is all about energy. What benefits the parasite that seeks to gain energy by leeching instead of self-guided production is going to take away from the host that is being leeched from. As such, any energies, food intakes, or spiritual activities that cleanse and enhance the personal power of the individual will automatically reduce the parasite’s ability to feed by the very nature of the energy systems. What empowers the individual, empowers the self and develops self-control, what develops self-control contains one’s energy and reduces the likelihood of one’s energy being leeched. This is similar to energy vampires in human form and this goes with the understanding that these are humans or non-humans who have been entirely overtake by the parasitic consciousness and cannot sustain their own auric fields without having to pull from the energy of humans who do generate their own aura or bio-emissions.

The vampire effect relates to how a person can be leeched from only to a certain point. Once the process surpasses a certain critical point then the individual becomes similarly engaged with only the lower bio-emissions as higher-frequency bio-emissions would then become harmful. So in essence, when the vampire feeds too much on one individual, then that individual becomes a vampire themselves.

Sub-Human Entities

The humans are utilized as hosts and energetic sources in this bio-emission battle while there are other classifications of bi-pedal organisms that appear to be human but are not human. As well there are bi-pedals that are non-human entities entirely.

Human-Hosts, Replicants, Synthetics and Carriers

The human hosts that are entirely vampirized by these entities become walking carriers for this virus and are effectively human in physiology but there is more to the human than just the physical body. In these individuals, that energetic component of the human is removed and replaced with the synthetic energy of the hive-mind organism.

There are replicants which are a form of clone, along with synthetics. These beings are cybernetic bi-pedals similar to humans but their energy is too not from an organic biological matrix but a technologically propagated synthetic soul-matrix. The hosts are here according to their agenda to subdue and feed off of the bio-emissions of the human race, although there are no absolutes. The agenda is not always so clear within the various groups who often have a mix of bi-pedal operatives. There have been plans to form of a salvation timeline because the only way to keep the whole process going is through a negation of degradation of the human race as this may close out this timeline forever.

Those with human organic soul-matrixes would simply transport into the next available universal time-stream or harmonic, while those with synthetic matrixes would have to technically travel to the next harmonic using a passageway otherwise they would remain here throughout a zero-point collapse and this would be synonymous with entering the abyss with no viable passageway out until the entire universe is brought back to one organism again.

This is also the process that is described to explain what happened previously as there are 7 harmonic temporal layers of the universe meaning everything is contained in a multitude of 7 octaves similar to light and sound frequencies or harmonics. And so there are 7 civilizations or 7 parallel time-streams and humanity passed through these to get to the last three where the physical forms are located. These are, from the higher to lower, Gaia, Tara and Terra. We are on Terra and if the information I was given is correct then we are currently on a transitory timeline located around Tara where people are noticing changes occurring and multitudes of aspects of the time-stream disappearing and changing simultaneously. Tara is where the last universal harmonic was left through a collapse of time and consciousness into zero-point and this resulted what was termed “the lost souls of Tara”. These are the discarnate souls of the previous civilization that could not travel to the next harmonic and remained without a body in the abyss. Thus they have plagued this plane since then, since ancient times possessing and driving humans to madness and there are explanations that this is the original passageway for the parasite into this universe. This event, the consciousness collapse of Tara would have acted as a fracture in the over-mind of the species generating a kind of cosmic schizophrenia and enabling all kinds of disharmony and distortion described in the previous sections.

The solution to this was described as a healing process that is taking place to purge the virus and that this is painfully similar to the human body purging a sickness however there are methods to promote healing and reduce suffering and confusion however people must contain themselves and their energies and strive to know themselves otherwise they will not be in control. This virus feeds on fear, confusion, spiritual degradation and the energy from degrading acts, lust, addiction, sexual misery and whatever fashion a human can be made to bring the bio-emissions of the energy centers down to a low enough level where co-inhabitation can be formed with an entity that has no access to the higher levels of self-awareness, higher-consciousness, love, or the universal spiritual experience that the balanced human is capable of.

Genetic Manipulation

There are explanations that there are genetic modifications taking place now to possibly preserve this civilization and that there were ancient genetic modifications made to induce a sense of stupor, worship, selfishness, an inability to more easily comprehend the higher spiritual awareness and the occurrence of time and consciousness and other spiritually and consciously limiting aspects. Part of this explanation is that holographic consciousness itself is a kind of limited result, a shadow effect resulting in the presence of the higher-dimensional essence of the soul which is more or less constrained by the body. An extension of this is that the entire holographic universe is a kind of false-light system designed to bend the original liquid etheric light of the soul and spiritual awareness into a rotating, recurring format which ultimately converts the original spiritual essence into an energy generator for entities that are entirely holographically represented. The souled human in this situation is a being who is originally from outside of this holographic projection.

The Ego Mind

In this view, consciousness is the ego-mind which is the false-sense of self, not to be confused with the shadow self which is simply the counterpart of the aspects of the self that we consciously agree with and are aware of in daily life. The shadow self is a result of having limited holographic consciousness and the ego-mind is projecting that limitation of consciousness into the shape and image of a self that is only a figure-head for the real individual essence which is spiritual in nature and immortal.

This Time is about Healing

Everything that is happening now is to motivate people towards healing and unification. This is not about a hive mind mentality where individuality is pushed out.

> "The best I can do for you is become your enemy."

There is a saying that represents the concept that the most beneficial role a person can play in helping one to progress is to challenge them and give them the opportunity to rethink their strategy and in turn improve further with each interaction. This may seem paradoxical but it is effective and explanatory. What we are facing is the greatest challenge humanity has yet to face. This is the unknown, the final frontier, the mind. The mind is our challenge.

There will be more on this later and in other publications but there are indications that the physical embodiment of the human has been altered to introduce implants, genetic modification, susceptibility to disease and ultimately fear-based programming of the brain. Without going further into this prematurely, the lower aspects are at odds with the higher aspects unless we as the midway come forth to mesh the two together in equilibrium. Until then, there is chaos, lack of self-awareness, and suffering.

There are many possible futures converging at this time. There are some less than favorable paths and there is the opportunity to merge with a very powerful path for humanity. This all comes down to how people will cope with information that takes them outside their comfort zones and eventually changes their view of mundane reality forever.

If people choose violence and lack of self-awareness by ignoring the spiritual aspects then that is what reflects into their life experience. When people develop a higher sense of self-awareness and spiritual harmony they can reduce the suffering and reconnect with the lost aspects of our spiritual identity for the first time in the publicly accepted version of recorded history.

There is technology that can change the world and there are great truths which can enable people to know themselves in ways that they never thought possible. Everything is at our fingertips and so we must come together as this is the way we solve the problems and cure the dysfunction.

Healing Through Unity

In various research projects the conclusion of how to heal this spiritual rift was by exposing each other, to each other. When we are all together, aware of each other and our selves, united in the goal of bringing higher-awareness and spiritual harmony then we can observe and acknowledge when one is slipping into chaos or disharmony. When this occurs and we are in proximity to each other in a healing circle or a kind of social unification then the members of the group at large can work together to pull the chaotic one back into harmony towards the group. The group of healers united together in like mind, spirit and body is too strong to be overtaken by the parasite. So when one individual at a time is faced by this problem the whole group can come together as one and assist in healing the individual by pulling them back to reality, back to wholeness and back together with the group. This is literally how the situation is solved in all realities and a breakdown of this feature of society is how the dis-ease proliferates.

Underground Bases

The active aural research program is part of a process to simultaneously verify as well as initiate and demonstrate controlled insanity/sanity.

These programs utilize the deep underground military bases to perform psychic and psychological research experiments on non-consenting youth and adults as well as consenting participants.

There are various means of generating the illusion of consent or even lack of consent and this is all being monitored and handled by oversight authorities.

These operations are directly related to the identification and understanding of the mind-virus and all weapons, defenses, and resistances known to man.

Cloning

Advanced technology is used to transfer consciousness from one cloned body to the next so that a continuous study can take place before, during, and after the death experience of one individual. More will be explained on this later, however this is through the use of advanced supercomputer systems that can function to entangle and then transfer the electromagnetic consciousness of the individual so that they are ‘remotely activated’ within a cloned version of themselves via a ‘brainchip’ (brain to machine interface: cybernetics).

Celebrity Cloning

Celebrities at the cloning center would like you to see what is really going on behind the scenes which involves trauma-based mind control, heavy technological programming and complex layers of influence throughout their life.

Initial Explanation

Many celebrities, entertainers, athletes, musicians, models, writers, producers, actors, all kinds of people from various industries are silently brought to the cloning centers for pay-to-play sessions.

They asked myself and others to pass the message on to you and that you would have to look for the signs and symbols in their media in order to see their hinting at these events.

The situation is heavily controlled using advanced monitoring technology and brainwave/EEG cloning technology. This is technology that can read the brain and determine what the mind is anticipating or speculating upon.

Their reputations are used as leverage as well as their safety and comfort. The level of programming and mind control experimentation that takes place makes it easy to manipulate a person’s brain into regressing into a state of trance that lacks the ability to remember or clearly organize experiences regarding the cloning centers.

Cloning Centers, Underground Bases

Deep underground military bases, 3 miles below the surface, are used as laboratory centers as well as a completely stocked underground city-base. These are connected with high speed electromagnetic drive pods.

Individuals are transferred to the brain through an extensive cloning and temporal body transfer process. The electromagnetic shell of consciousness within the brain is relocated to the body of a compatible clone and various training, conditioning, programming, experimentation, or pay-to-play experiences take place.

Programming

All individuals are programmed to various degrees in order to maintain control and secrecy over the situation. This programming involves very advanced technology, trauma-based mind control, and energetic attachment via beliefs and emotions.

Experimental Operations

These bases were also used hand-in-hand with military operations which were geared towards discovering and controlling all aspects of the human mind.

Genetic Engineering

Experiments involved genetic engineering to produce soldiers, psychics, hybrids, and others that would be able to carry out operations. This leans towards MiLabs and the military faction's experiments which go beyond the basics of cloning.

Immortality

The initial research included the goal of physical immortality. In many ways it can be said this has been achieved, however there are side-effects and difficulties.

If one does not activate their higher consciousness, then the effect of time dilation causes the conscious mind here to reach limitation points in experience.

What has been termed "blank slate/state" technology has been used to 'reset' the perception of time through memory in order to keep a continuous progression viable for the conscious mind. Without this the unconscious and the conscious mind merge.

This begins involvement across time with advanced technology that can operate on the soul level or the conscious mind's level of access to the unconscious and soul-memories. The Universe instantly creates a cosmic backstory based on the conscious-mind's access to the unconscious. By controlling the conscious mind's access to the unconscious the entire backstory of Humanity can be altered and new connections can be bridged in the future.

Earth is essentially a time-ship through which consciousness ascends towards higher states of awareness and self.

How did it get to this?

After WWII when the United States war-faction firebombed Germany and melted many of the inhabitants of the cities into sludge in the bomb shelters and streets of the cities, a group of NAZIs traveled to Antarctica.

Russia noticed the movements to Antarctica and the United States sent Admiral Byrd up with 3600 marines, planes, a battle cruiser and smaller vessels. They returned in defeat and only a few words were mentioned in regards to what actually happened and how they were defeated.

The rumors spread and words of gravitic drive craft, and undersea or under-ice bases originated from this encounter.

From what we were informed as well as directly experienced, this was the ice-base in Antarctica where an underground base was found already constructed with very advanced technology.

Here, cloning was deployed along with mind control and temporal manipulation technology.

Soon, cloning was offered as a way to avoid assassination as well as to prolong and protect the original body in daily life.

After that, celebrities and politicians were replaced with programmed clones who could carry out the orders of the NAZI faction.

This was the beginning; the groups utilizing this technology now are no longer confined to the NAZI faction.

The groups you see today, in control of these operations, are considered MiLabs, secret societies, think tanks, military factions, and other control groups.

Deeper Meaning

The individuals that have been cloned are given very in depth views of the way this society functions and the source of power and change in the Universe. Many individuals are present here from what would originally be another “time” or “timeline”.

There is a possibility that this notion is due to inserted memories and traumatization although until all the information is released we will not have a definitive conclusion.

As of now it is a possibility that these individuals are from another time that goes beyond our comprehension currently.

It may even be a possibility that these individuals have come from ALL of time looking at the very far past and into the very far future of Humanity.

These are the kinds of notions involved with the experiments taking place in the underground bases and military operations.

What is next?

Share this information with those you feel are ready to know and help Humanity come to terms with our journey here and what is going on in these kinds of experiments and take responsibility and power for our own existence.

We are in something that can be called “The Unveiling of The Hidden Knowledge”. This is a cyclic process that takes place to advance a civilizations knowledge of existence. As part of the civilization moves into higher advancement another aspect may lag behind. Either the future will slow down, or the past will speed up. We are experiencing the past speeding up and all the events that have taken place to influence our civilization are coming to light. This is as much a natural cycle of consciousness as it is the eventual revelation of secret knowledge and the particular connection to the secret projects.

> *Those brought to cloning can use their free-will to state their lack of consent to violence and harm and then live in commitment to that by not harming or accepting violence in their lives. The Spiritual Law of Harmony rules in all planes and dimensions.*

Chapter 2: The Awakening

Chapter 2.1: The Machines of All Time and Space

There are machines that are capable of accessing genetic memory and unveiling what can only be referred to as the experience of awareness or existence in between the physical planes of each time or each physical life experience.

Even if they are simultaneously occurring moments of a transcendental nature, there is still an illusory ‘space’ where there is perceived separation and through this there is a perceived ‘space’ that is in between each existence.

Re-Creating The Kaleidoscope

This space is only perceivable when viewing from the physical perspective, like seeing the spaces between the angles of a kaleidescope only when viewed through the lens and similarly, technology can be used to recreate what this kind of illusory space might look or exist like in between the multi-dimensional realm of the continuous experience stream. Through this, these ‘hypothetical’ in between spaces that are understood as only illusory productions of biological consciousness, can be generated through advanced technology with the capacity of recreating that kaleidoscopic view of which the human biological perspective is only a small fraction or even fractal.

By recreating this biological perspective, they can recreate the illusory spaces in between planes and through this they can literally access and experience what are stored in the DNA as the experiences of existence beyond the physical limitations of consciousness and into a multidimensional experience of time and space.

All becomes a never ending sea of consciousness, however this is the given. The trick is to take from this sea of consciousness and slice it down into conceivable chunks from which you can reintegrate a previous personality or identity and continue on a stream of consciousness that would otherwise be tossed to the cosmic wind like fractal stardust as the sands on the beach of hyperspace.

Sand-Castles of Time

We are effectively building sand castles out of these sands of time that would otherwise be swept back and forth into and out of the ocean of life and the universe only to momentarily wash up again as the identity which we once knew.

There is technically nothing wrong with either view, because then, the spaces between each million year occurrence of just so happening to wash up again as you, would be imperceivable because they are only there to be seen when you are you again.

We’re Waiting For Ourselves

Yet, if there were some who had attained the awareness of the true nature of reality and were standing there on the beach waiting for the rest of their cosmic family to come to shore again, it could be perceived as waiting the majority of the time for a very small occurrence and then being alone again up until the kaleidoscopic fractal inverts itself to the point where everyone now is standing on the shores of the sands of time rejoicing and meeting with each other.

The Goal of Two Societies

My goal in coming to you people on the surface of what is called “Earth” is to help assist in the process of bringing the two societies together, one who’s been waiting for thousands of millions of years, and the other who has no idea that they’re even late (or very on time).

You see, those are the only two situations where there could be even the possibility of perceiving such an injustice as experiencing the pain of loss or misconstrued identity in this universe. It is as if two families met at the cross-roads at different angles, and while one waited for the other to arrive, they could merely supply themselves with glimpses of the ruins and remnants of the evidence that the other civilization existed at any one time.

This is not how life must be and this is kind of like a cosmic waiting game of hide and go seek our two mirror civilizations have been playing with each other. One who’s highly technologically advanced and the other who is more or less the spiritually advanced of the two.

Both of them have a unique view of the universe and they are both only complementary to each other as a whole. The more they sat around and waited for one another, with one leaving the clues that the other would find and even switching roles sometimes in different ways, they became even more and more complimentarily associated as the very essence of experience they seem to be missing more and more is the experience of one another.

So as we perceive these as being great losses or great gains of time and culture we are really only remembering ourselves and coming together as a unified existence that once met upon the surface of Earth as a single family covering the entire harmonic spectrum of the Universe.

And that should be the goal of any progressive, any one pushing a new culture or an old culture, anyone looking to teach the young and protect the knowledge of the old, while also protecting the innocence of the young and perfecting the age-old knowledges that have defined our presence in reality.

Our Forgotten Other Half

One could even say we’ve sometimes gone off the deep end, leaving ‘land-minds’ of sorts to process the information that would be present when we are gone. Of course, what we could’ve found when this occurred, is beyond anything we could’ve ever expected and that is the true nature of the complexity of creation and existence. That everything follows the cycles of creation and destruction, however, the memory of everything that has been created can always be accessed (depending on the beach) and therefore the creative aspect is legitimate, yet it is the destructive aspect that is illegitimate and illusory.

Yes, through advanced technology this can be proven in ways that can be verified and transmitted using advanced technology, since that is how we like to verify things these days. There is, of course, a human looking at the screen, the read out, or the situation from a physical perspective to verify the verifications.

All Is But An Illusion

There is a notion that there is only one civilization, one society, in actuality that has been chasing itself through time. That we cannot actually find the same place and the same time where both meet because we are each other from different perspectives. We can only get a mirror where this is possible, or an 'hyperdimensional' internet channel where we can stream one's consciousness in from the other reality and interact with them through that here in this reality. Thus the two civilizations can achieve the experience of their own civilization and the other civilization by merging with one another but only through a remote contact, just a relay, not an actuality.

The harsher, darker side of this is that any civilizations between then and now that we did happen to meet that proclaimed to be "the one's" we have been waiting for, and in essence our darker or lighter halves, are actually the impostors who exist entirely apart as a sub-set and have taken a liking to trying to trick the reality out of one of the other civilizations.

Of course, if these are another form of being altogether, and this is all brought about through an interplay of consciousness and deviations from an original core reality, then all will resolve itself when that core reality is alone again. This indicates that all realities will either move closer and closer to the core until they unify, or farther and farther out until they transmogrify beyond recollection.

Life Itself Is The Highest Illusion

That hyperdimensional internet channel that is created out of advanced technology to merge the parallel realities (rather distastefully and maybe disastrously at times) allowing different civilizations to interact with each other, well this has been created using technology.

But then it was discovered that this is the ultimate nature of DNA. That this was 'invented' similarly as a higher-dimensional internet so that various natures of different planes and dimensions could interact with each other and experience the richness of life.

The universe becomes more like a living arcade game then, where people come from all over the galaxy to 'plug in' to human experience and figure out what it means to be physical, human and on Earth.

This does tie into the larger nature of reality, of star-races, and of time and consciousness that is often reversed according to how things seem to play out in physicality. We are moving through time, but just because we are moving one way, does not mean that others could not be moving the other way.

We have to live our lives with meaning knowing that the message we pass on, the duty we vow to accomplish and ensure is meaningfully connected on either end to the passage of the past and the power of our ancestors to the function and knowledge of the future creating a clear passage between the realms, the generations, and the ends of the universe. This is what literally ties the universe together, and the mind if each individual. This purpose is contrived when not carefully shaped within and so we must help all who seek purpose learn to become the blacksmiths of their own destiny through the temperance of desire or temptation and the discipline of developing strength and maturity where there was once weakness and naivety.

Once we know this is our duty, this is what we seek to achieve and this is what is done, then we can become part of the universe forever. Of course, this may only be temporary in the larger view of things.

Chapter 2.2: The “Awakening” of 2010

In 2010 I was “awakened” at an event involving hundreds of people that play various roles in this society, the secret society and the breakaway civilization. This also took place across times or planes of reality.

During this event I was informed of the situation on Earth beyond the informational barriers that were previously in place to limit knowledge to only what is required for specific operations. I was essentially “informed” of the entire situation as much as the mind could handle this.

As this was occurring, the team that was updating me on the status of Earth was being informed of and given information regarding changes in the future. In short, interviews, posts, and releases that I have since made and will make in the future were touched upon. Quotes were given from the blog and interviews which were jokingly acknowledging verbal mistakes at the pronunciation of names, new perspectives and interpretations and more. As they were informing me, they were creating the future reality where this work takes place. That is the basis of this layer of the operations. They are creating the future person by person, layer by layer.

Memory Suppression

My memory was unsuppressed and all the traumatic memories and experiences were unveiled to me. This was almost as traumatic as the initial experiences themselves although precautionary steps are taken to ensure the safety of the individual. There are teams of highly competent individuals of all kinds with professional backgrounds of every field imaginable.

Throughout my entire life I have had memories of experiences, at this event I was informed what the experiences meant and what was actually happening. I've had memories of underground bases, cloning, stargates or interdimensional gateways, advanced technology, non-human or programmed biological entities, sacred knowledge and experiences, the power of the mind, and breakaway civilizations. Most of the time we are conditioned to believe these are past lives or experiences in another reality so as to enable continuity of operation.

Life and Consciousness

From my perspective and the perspective of others, we had reached the 'future' and had been sent back through the utilization of advanced technology and cloning to return to this time and inform others of the possibilities.

The True Human Potential

This is so far beyond what anyone can accept or comprehend fully that humans with an emotional, mental and physical aspect balanced as one is literally a cosmic reflection of the entire universe at once. This is the closest thing to a "god" in the flesh. And be sure, the entirety of this rests on the behalf that the man is protective and helpful. That the woman is nurturing and loving. That is the point. "god-man" does not mean a warrior who destroys everyone and anyone in his way getting what he wants. Nor does it mean some lusty and vampiric form of energy or mind control game. "god-man" means the love of the universe, the power of the body and mind, the peace and calm of the ultimate stillness all in one.

This power is in human DNA, originally so. And so this is awakened through walking the middle path of neutrality and 'splicing' the timelines down so that neither one nor the other gains the power of the individual. Through this, the individual creates their own power, right on the spot, without having to lean to one extreme or the other. This is like a cosmic, temporal balancing act with emotions and mind. Where we give our energy is created in the universe in the form of many productions and effects. If we are simply thinking in an imbalanced manner then we are producing timelines and side-realities that exist in the etheric realms that we can't see and these realities will reflect our inner imbalance. So then when we are balanced in our energies we are not creating one or the other side of divinity, we are literally creating the whole universe, cleaving down the middle and producing both sides of divinity or eternity equally and this is the only way to have an eternal production which does not eventually degrade to one extreme or the other. Through balance, we reach eternity and in this way all the power of the universe exists within a person through their ability to balance their emotions and mind and thus unlock the DNA.

The DNA is coded through bio-emissions of mind or emotional body. So we are constantly doing this and we are either producing a DNA code that reflects imbalance overall, or a code that reflects the eternal balance of the universe overall. This is through energy.

One reaches “heaven” or the deity planes or simply self-actualization, through three paths. These paths are through merits or devotion to principles, or through knowledge and expanding one’s mind to face the universe, or through great works and deeds to produce this effect of power, knowledge and emotion unto the world for others. Through these paths we create an impact on the universe and this transfers what we are temporarily and physically into an eternal energetic and physical production within the living universe, forever. To do this requires balance, focus, devotion, and discipline however because there are many distractions along the way.

The Light-Body

You must build your own light body. That is how it works.

Your heart creates a field and projects you.

Rely on yourself and use that for protection.

The power of the Universe will align with you if you align with your self.

Learn as much as you can and break through duality of love/hate, cultivate your knowledge of the self and use it.

What you want is what determines your power in the light-realms. Not how you want it. If you want war, then that is a sign of weakness and determination to produce imbalance and exist by that. If you want peace, that this is a sign of power and unity to produce further unification and exist by that. What you want determines your power, not how you obtain it.

Technology of the Awakening

Mental Manipulation Technology: Touchless Neural-Interface and Enhanced Awareness

I reached what the “Illuminati” called the “awakening”. I feel a better term would be “unlocking” as this event includes the removal of all traumas, perceptual distortions, and memory suppression.

This event was a presentation of very advanced technologies which allow the mind to transcend space and time. It was shown that death is similar to a phase-shift of consciousness as polarity and that the awareness of the being obviously continues. This was verified through advanced sensing devices which can visibly display frequencies which are invisible to the physical senses. This is also something that occurred earlier on as a child in the underground bases by transferring consciousness in and out of the body at will using advanced technology.

With these devices it is possible to see the “auric” or soul field of the individual. Any living body has a field which glows when picked up by these sensing systems. This field becomes more refined when viewing more advanced beings. Human have an extending mental field, and through this a kind of glowing awareness that is picked up. It can be fairly simply compared to thermal imaging except instead of differences in temperature it is the presence of a soul or mental energy field around a living body. The finer energies extend outward away from the physical body.

More than once, the situational requirements were satisfied in order to produce an ideal environment for maneuvering on the non-physical plane. This is the basis of how the temporal operations occur, yet these events were different than previous operations or experiences. The group I was in was going through the process of increasing the vibratory emissions of the “bio-mind” in order to stay focused on the increasing vibratory rate of the environment. Generators were utilized to create an effect on space/time which was perceived on the “soul” level. These events went into the discovery and explanation of the creation of the “godlike” powers of the advanced sentient technology which was capable of accessing the holographic nature of reality which humans can perceive through their bio-mind/soul. These technologies also enable one to perceive what is referred to as the “galactic history” of Earth and humanity. We are far vaster and Earth is far larger than people are lead to believe.

Time Dilation and Temporal Recurrence

Time dilation capabilities were shown which allow for accelerated learning of advanced and detailed material within a very short amount of time. This could be seen as a kind of viewing technology which one wears or looks into and vibratory emissions are scalar-linked to the brain which then allows the individual to perceive more information simultaneously. Then there is a very rapid pace of information streamed on a monitor or through a device and this is akin to watching a 20 minute instructional within a few minutes or a few seconds with very advanced minds. The more time is slowed down while information is accelerated, the more stress is applied to the brain. The brain tends to overheat and over stress with high-rates of activity, especially without conditioning. The conditioning is what allows one to utilize their mind and body in these manners. This is not unlike the very rigorous training and conditioning of certain monks or martial artists however there is very advanced technology and other hidden methodologies utilized.

Crystal Technology

These are capable of holding, transmitting, and amplifying consciousness frequencies. There will be a more detailed explanation in a later section.

The crystal technology is used in junction with the power devices to enable a scalar-mind link which allows the interface to be entirely mental or spiritual, IE: they are not controlled by hand but by focus and intention.

Time Crystals

These are utilized as a computer recording chip would be to run a program yet they hold memory in expanded space, IE: they function in a hyperspacial manner and are essentially hyperspacial computers. These are what will be introduced in junction with the quantum supercomputers.

Quantum Tunneling Diodes

This is technology that has recently be released to the public. New technology is developed years ahead of time and then slowly released to the public in a cascade of advancement. This technology deals with superconductive materials which enable the transfer of information at faster-than-light speeds.

The supercondutive material allows for 100% efficiency of data transfer. So what happens then when the efficiency surpasses 100%? This is possible because we are effectively in a simulated holographic environment. The experience is real, however everything is overlayed via particular limitations for the ‘local-environment’ which is like a central data processing limitation. When these parameter are surpassed, one by one, through a coalescence of refinements and methods, the result is akin to a glitch in a computer game system. They have accessed faster-than-light technology and the mind is also capable of this naturally.

With this technology, however, the information can be received a very small amount of time before it is sent. So if a person is absolutely surely going to press the button to send the message, then right before their finger hits the button that message will be received on the other end, as if magic. If they simply play around and pretend to hit the button but very quickly turn away, then of course nothing happens. One can, however, ‘fool’ the universe in other ways and this is simply through the reception and transmission of information across what should be secure information barriers.

Tachyon Fields

These are programmable fields emitted through advanced technology. I was shown how tachyons are the sub-atomic “particles” or energy formation which flows both ways in time. We are receiving tachyons from the “future” in order to layer the flow of time in one direction or the other. Tachyons are the name of the particles/energy packets that we perceive from this perspective as reaching us to initiate the “future”.

Thus, when a stream of tachyons is concentrated and accelerated, this results in an acceleration of the temporal field and we literally experience an acceleration of time. This can be focused and targeted on a specific piece of equipment to change the way information will be sensed and to essentially allow that device to sense ‘ahead’ of the present moment.

The same effect can be produced with the neurological processes of the human as the physical coupling of the brain to the mind can be altered through a concentrated tachyon field to enable the neurological and mental processes to begin to perceive information ‘before’ the brain is actually physically processing the data. Therefore the mind of the individual will be present in the body while the senses and other perceptions will literally be expanding into the future beyond the present moment.

This is highly confusing at first and requires much training and conditioning in order to make sense of enough to operate in any kind of effective manner.

Upgraded Chronovisor

See, “Upgraded Chronovisor”

Time Tunnels

This was developed earlier on and has been the subject of many TV shows in the past and present. The shows are a sure-fire method to get the information to the public without having to force those who are not ready to comprehend. The information is easiest to digest if people think they are watching science fiction.

These are essentially spiraling tunnels of these tachyon fields produced by large electromagnetic field emitters in the shape of a conical tunnel. As a person moves through this field, their temporal acceleration changes and thus their frame of reference within the universe changes. They effectively move their mind through stages of existence or temporal resonance in the universe and this can have devastating effects.

This is an older technique how is still in use and has specific purposes depending on the situation and the information sought.

The “Trip” Chair

The early use of this technology did not use time-tunnels. There was a helmet that was devised which would create a feedback loop of the brain’s activity and funnel this out and then back into the sensory input. This information would be accelerated and redirected to the point that the perception of time would “fold” in on itself until the person would access an expanded temporal perspective of the universe meaning they would mentally temporally dislocate from the initial frame of reference and extend outward further and further in repeating cycles until the same moment was replayed and then all other possible moments in a kind of fractal-like recursive pattern and the very far future would be realized. Essentially, this technologically produced the class “flashing before the eyes” of the entire life experience that is described in near-death experiences and the entire temporal body would be very quickly unwound before the person’s inner eye.

There would be a complete disconnection with the current frame of reference that the collective Earth environment is processing under. That is, this ‘time’ and ‘space’ would be completely out of perceptual reach and a new time and space would be rendered instead. Until the experience had completed, there would be no way to contact this civilization.

There are other versions and ancient versions, tandem operations, more ‘organic’ methods, and modified travel capacities.

Kozyrev Mirror

This is a piece of metal, usually aluminum in early models which simply bent the bio-emissions of the body and mind into a pattern which would create a vortex. The vortex shape and vortex mathematics enable energy and information to travel in across space and time by ‘short-cutting’ the physical plane.

The result of this is that the vortex that is generated over a specific area through an individuals bio-emissions would be capable of interacting instantly with the bio-emissions of another individual who was placed within a duplicate mirror device which was generating another vortex on their end.

The two vortexes acted as a kind of hyper-dimensional telephone cable, literally like a can and string and the perceptions of one another were accessible. There were many uses for this and again, many ancient interpretations of this technology that have been hidden from the public. Nearly every version of these technologies were present in previous times.

Universal Recurrence

This is a discovery that the universe recurs in cycles similar to a wheel or even a washing machine. The washing machine metaphor is fairly accurate and playfully descriptive because without the technology to observer, or an awakened soul of a spiritual adept, people would go for eons without ever realizing that everything in the universe repeats itself endlessly.

When traveling to the far ends of time, it was discovered that one can move far enough away from the ‘present’ or the local frame of reference that ultimately everything is at a maximal informational opposite to what we have today. After this point, everything begins a slow shift back to the present. Through this, one can cycle around again and reach the present by going far enough into the future. This was an amazing and confusing discovery because of the implications about what is actually changing each time, the reality of what are called parallels, the continuity of temporal experience, and basically a ‘recycling’ effect of all experience in the universe. Nothing is lost, but this is also an issue because then nothing is actually ever gained!

Remove Viewing, Temporal Lensing

An ancient device which has been rebuilt and perfected is capable of using these technologies to create a lensing effect which draws a ‘reflection’ of time into a projection system which is effectively capable of acting as a ‘visual time tunnel’ into future probable realities. This is a device which generates a visual portal which allows one to view the future.

This device also exists as ancient counterparts which are located around the world, namely in areas that have been recently sought by the world superpowers. Nothing is as it seems. If you read a story in the public venue then you can be sure that you have read the cover story while the reality is much deeper.

Temporally Linked

The use of the viewing devices which enabled interdimensional lensing of possible futures was found to be stabilizing our pathway into those projected futures. This was enabling a time link between the present and the possible future.

In order to avoid the catastrophes of 2012, the link was broken between the two civilizations and the devices were rendered inactive for this period.

Natural Vortex Energy Locations and Geography

On Earth there are natural ‘time tunnels’ where tachyon fields and vortexes are produced by internal elements. These are mountains, lakes, deserts, fields, sacred sites and other areas that have always been reported as being ‘paranormal’ or containing some kind of specific energy that enables contact with another reality. These are simply naturally produced areas of this vortex energy that produces an interdimensional nexus point through which multiple other parallels can be interacted with. These areas produce an effect on the body and mind similar to the technologies described above.

Most of these effects, from these technologies, change the way light is received or emitted by the mind and DNA.

Mount B.

There is a specific mountain where a base is located, and I have mentioned this before, where the base is so deep within one of these vortex areas that everyone working there is either there for the entirety of their life, or they are only permitted to be there for a very short amount of time. This is because of the acceleration effect. Essentially, if one was to go into the base and work for a matter of hours or day, in some places even minutes, then when they returned to the surface they would be years in the future, sometimes decades or centuries. This is very dangerous and you can imagine the original people who found this area and what kind of situations occurred.

Now with the advanced technology that has been developed these issues can be mitigated and much more control over these effects is enabled.

Particle Accelerator Temporal Manipulation

Using particle accelerators a “fold” in space/time can be made so that when the accelerator is turned off or tuned back into a certain frequency (not sure) everyone within the field will “snap” back in time to the specific moment when the fold was first created.

I have seen this done on small scale, and a rather larger scale, but I cannot be sure if it was only me. I believe I have seen it done on a town-sized scale during the 2010 Awakening where some of the events reached a scale of nearly cosmic proportion and the entire sky and horizon was lit up with technology and entities, as well as Solar Warden, the NAZI faction, secret society groups, and breakaway civilizations or complete other civilizations, some of which were non-human.

This is done using particle accelerators to quantify space on the quantum level (as a reference point with the mind) a frequency would be “folded” into the space time continuum as we “rip” through space holding an access point open at this fundamental level of space/time. This allows for a ‘letting go’ of the frequency, or a ‘snapping back’ by allowing the entanglement to solve itself. When used with generators that propagate out efficiently enough, the effect is akin to a time/space rewinding effect. Some people have noted various theories describing this in relation to the CERN device. These technologies were described as smaller versions of the CERN device and are related to higher-dimensional travel via folding space through electromagnetic fields. This is literally artificially technologically “holding space” for a specific area in relation to a period of time. Time is a more complex notion as an abstraction but by locating the frame of reference this can be applied to distort what would otherwise seem to be a continuous flow. When the frequencies are allowed to “snap back” all sentient observer sources return to the environment they were present in when that frequency ‘rift’ first began. Essentially this creates a replay effect on the consciousness of the individuals within the field. There is no physical effect. The consciousness is ‘regressed’ through time/space, and they re-experience existence from that initial point of contact with the frequency “rift”. This is best explanation I can currently offer however more is coming to the public each day.

This is literally like a “restore point” on an operating system except the computer system is literally the consciousness and space and time of a portion of the local-environment of Earth.

Riding the “Timewave”

There are teams of individual who operate in tandem with the technology of looking into possible futures based on the present and operating through the present via other operatives who are carrying out operations and movements that will construct the various possible realities that the original team of individuals is hopping between. These teams literally “ride” the “timewave” of the future hopping between possible future realities relaying information to the present depending on what movement will be next.

Dematerialization and Rematerialization

This is technology which transcodes the information of an individual human into a holographic projection of light which can be transferred between devices. There is a special system in place that is required to successfully transmit a living human being otherwise just the body will be transferred and the soul will remain, effectively killing the individual.

“Jump Rooms

These are large areas which are capable of acting as a kind of technological ‘portal-gate’ where an entire team can be instantly transported from one area of the universe to another. The space between the two areas are ‘twisted’ like a spiral and then ‘snapped’ back to position and if done correctly with the two frequencies of both locations merging then the team of one room will transfer to the destination pad.

All these methods require training and conditioning, most people are at the very least visibly shaken from the experience which is a bit like being microwaved into a liquid ether and shot through a particle beam at the same time.

Ion Shields

These are areas of concentrated ion emissions and this can be used to create a deflective layer of heated air where light will reflect at a programmable angle. When this occurs, a person standing behind the shield will appear to be invisible to others who are looking straight at them. The light will be bent in such a controlled manner as to perfectly shift around the person in a fluid and equal flow so that the ‘bubbling’ effect that was noted early on can be mitigated to produce a complete mirage where there is relatively no sign of difference to the untrained eye. An entire group of individuals and equipment can be hidden in the background a matter of yards away and as long as the person is not intently, inspecting each square inch of ground and air they will not notice any difference between the area that is being covered up in the distance and the area directly next to them without the shield.

Similarly a ‘screen’ of imagery can be projected onto certain materials in the air and a hologram can be projected which will render a background or foreground image. This will work to a degree, and from a distance this will work to disguise an entire horizon.

Instantaneous Healing

There are instantaneous healing methods which utilize various technologies. There are substances which can initiate a complete and real-time regeneration of living tissue from almost any conceivable non-critical injury.

These are chemical serums which allow the cells to replicate at an astronomical rate while suffering damage to the DNA telomeres at repeated use.

There are many methods but mainly the living-light harmonics is one of the latest advancements and most effective at producing healing on a molecular level.

“Living Light” Sound-Harmonics and Electromagnetic Healing

There is a technique for producing a quantifiable scalar wave which interacts with the living cells of tissues and instructs them to repair at a faster rate. This has been called “holographic healing” by others and these are essentially ‘living light’ frequencies which interact with the cells on the same frequencies that they operate on when healing and interacting with each other. The scalar waves emitted generate the same patterns and this creates an ‘ether’ fluid that enables them to grow and repair the tissue faster.

Electrogravitic Craft

Advanced craft which utilized counter-rotating torsion fields propagated by very powerful quantum computers and zero-point energy devices.

There are also more modern versions that use powerful electrical flows to neutralize inertial resistance and ‘slide’ through the gravitational field of the crafts own materials.

Energy Cores and Storage Capacity

The hand-held devices that are in use do not require charging or even disposal. The storage capacity of the batteries is so efficient that they last for a lifetime of use. Some devices use an energy generator within the device itself. These “batteries” which are not batteries but little, powerful generators and can explode if they are mishandled.

These are the cores that are used to power many devices and essentially pull energy from the space-time ether.

3.5D Replicators

There are replicators that can produce any conceivable 3D material or object altogether including food or organic material. These use very high amounts of energy to ‘force’ the electrons of the atomic grid of a substrate to shift into the pattern of the element being replicated. The result is a device which can use wave-emissions to reshape materials on an atomic level and produce or recreate any object or substance.

3.5D Sensors

There are sensors that could reverse the process and detect every minute detail of the structure of a body or material. These use energy emissions to detect the structure of a material down to the minute electrical resistance on a molecular level. Similar to diffuse MRI imaging for a living body but more advanced.

3.5D Printing of Clones

It was shown how this technology was used to three dimensionally print human bodies into space/time which could then be used as vehicles for the consciousness or souls of various sources.

Cybernetics:

Neural-interlace/4D Connectome Recording and Simulation

Very advanced supercomputers exist with the capacity to translate the bio-emissions of the brain and body and reconstruct the entire inner visual and sensory experience of cognition and emotion. From this, entire dream worlds can be created which mimic the experience of consciousness. This is most similar to the current day use of diffuse MRI imaging where water molecules are traced through the individual neuronal pathways and an entire digitized image of the brain is developed. The more advanced version described below generates a 4D hologram.

A super computer and advanced sensing system essentially develops one of these connectomes of every connection in the brain. Then this system develops a neural processing pattern that matches the entire memory and personality of the brain.

This is then recorded and extrapolated by a powerful computer system and a simulation of the experience can be observed through the physical body's memory via a monitor system or the neural interface of an operative.

Essentially, this technology can record and replicate a person's entire memory and life experience for viewing purposes.

EEG Heterodyning

This is the technology which enables the activity of the brain to be influenced through generating a scalar grid and a carrier wave system which can cause the brainwave patterns of the targeted individual to resonate in sympathy with an externally projected frequency. Thus, emotional states can be manipulated as well as specific thought or behavioral patterns. This works similar to binaural audio where two tones of different frequencies are played through each ear and the brain resonates in sympathy with the difference between the two tones. This occurs with brainwave frequencies and thus the brain 'slips' into the frequency of the third tone, the difference between the two being projected. This can be done with ultrasonics and ELF emissions.

Artificial Hallucinations

The neural-interlace can also be used to merge the brain of an individual with a computerized system that will be able to produce effects and hallucinations within the individual.

Through this technology, any stimulus, any input can be recorded and recreated once a functioning connectome has been generated and neural-interlace has been achieved. Entire virtual world scan be created and experienced and after the devices fine-tune the frequencies to match the individual's brain functions one world is indistinguishable from another.

Brain to Machine Interface Holographic Consciousness System (brainchip interface, virtual reality simulator)

Some of the training is done by entering into a visual-audio dream-world. Some "programs" will consist of repeating a certain task over and over again until it becomes muscle memory in the brain. Others are designed to probe or test the mind until a certain response is received.

This is achieved through the operation of a 'brainchip' or a brain to machine neural-interface in the individual which was developed during WWII.

This consists of a small computer ship which merely relays stimulus through frequencies and neural-stimulation of varying kinds. The frequencies and location of each region of the brain will determine the function and thus the chip is used to localize electromagnetic input and the brain's functioning can be modified from there.

As well, the entire psycho-etheric form is vibratory in nature and so through the introduction of vibrations and frequencies from the implant there can be a modification of the frequency of the entire being or what is called the soul or "bio-mind".

Utilizing The Temporal Body

The temporal body is described as the body 'in time' that exists a few seconds into the future instead of the temporal position that is relative to the present. This is as if the 'future' is streaming outward from the body as ideas and feelings are as bio-emissions. So this 'future' energy is spiraling and streaming outward like a fountain. Thus this frequency can be attained and influenced while the present moment seems unaffected. However, when that individual arrives at what would be seen as the future they would intersect with those influences and this would be as if the interference or effect was streamlined to that future moment.

Manipulation Through the Temporal

This can be used to both produce an effect on an individual who will later feel this effect in the future. Or this can be used to operate outside of the physical plane, in a temporal manner which is literally 'hovering' just outside or 'after' the present moment of the local Earth environment. This would be as if a person is out of sync of the frame-rate that a viewing device is capturing images of an area with. Because they are out of sync, they are then 'invisible' to the capacity for this viewing device to see them. Because they are still present in the same local-environment but simply just out of range temporally, effects can still be produced and this will mostly interact with the person's temporal body.

These are how many operations are carried out as the operative who is interacting in the temporal body will appear to be a ghost image or a dark silhouette that is only perceivable to the mind's eye. A portion of the population is entirely psychically blind, while another portion of the population contains psychic capacity. So those with the psychic capacity would be able to sense and partially "see" as a form of energetic detection when an operative is interacting with the from the temporal plane.

Through this plane one can easily enter into someone's mind and produce effects in their dreams. These effects would not be received on the body but mentally, this leads into astral and mental plane activity. There is also temporal manipulation that can be physical effects that are simply offset to seconds, minutes, months or years in the future. These will be offset from the present aspect of the body in a modulated frame of reference and the effect will remain there in the temporal body until the physical body "matches" the temporal body frequency of that future moment. This is kind like an energetic trail we are leading ourselves up to where the temporal body already connects with each future moment but the present physical body remains separate until the two frequencies are matched. The physical body essentially 'flows' forward into each new frequency of the temporal body.

This is the body where temporal implants can be inserted and sustained so as to tie the frequencies down and limit the amount of awareness a person can gain before they manually remove the implants or overload them. Overloading and removing can both be painful however if the implant stays it will at like a governor and transmit access temporal 'momentum' or consciousness energy to the owner of the implant and will also drain the temporal and physical body acting as a technological leech as well.

Astral or Light Body

This body was described as a more emotional form of the energy that is emitted from the physical and spiritual system. When a person's energy is at a high level of activity, this will be visible on the astral form and these are the energies that are often siphoned away through the use of advanced technology to convert the human into a generator system for energy harvesting.

There is talk that this proves that the human existence, in the modified form that is present today, is entirely for genetic harvesting. This may be a confusion, a deception, or a reality. Regardless of the interpretation, the human energy system will leech this energy out into the cosmos when consciousness and energy is mishandled or allowed to flow through the lowest common pathway. This excess energy is very easily usurped and utilized by transdimensional parasitic entities and devices.

This is the body that is utilized for astral travel which is a kind of frequency that exists in between the density of the physical plane and the highest etheric plane of the spiritual, heavenly, or deity realm. There have been explanations that this plane is entirely technologically propagated and that when the devices are turned off, which is an event that will bring about civilization-wide change, there will no longer be a deep and wide, foggy deviation between the higher spiritual and the lower physical plane but a clear path between them.

Similarly, the consciousness and entities that are present here would be no longer accessible and their connection to the physical plane would be non-existent. This could be problematic for those who are trapped within the astral such as human souls or those who have taken a cyborg route and require a return to the original planes either physical or high spiritual before they can secure their position in the universe.

This also relates to the early discovery of these ancient devices containing portals or gateways to these realms and the early experimentations with enabling contact between the physical Earth plane and the lower astral realm containing discarnate entities that would very easily sustain themselves on the lower astral bio-emissions of a loosely guided emotionally reactive human vessel.

This is where entities can attach and will look for those who have the most excess astral or emotional bio-emissions leaking into the universe. People are kept in an emotionally unstable state of being because this is the easiest to feed from and as well the individual will always be looking for more energy or the solution to why they are feeling drained rather than discovering the truth nature of the universe.

However, as with every lower route of obtaining self in the universe, the more this is done, the greater the likelihood that the individual will realize something is happening and ultimately awaken. Or they will no longer be present here and the parasite will have to find a new host because the longer this process is maintained the more difficult producing one's own energy will be for the parasite . So parasitism is a limited, one way street.

Monitors can emit consciousness/brainwave altering frequencies.

Monitors can emit consciousness/brainwave altering frequencies. This is what I was informed and shown. All electrical wiring and communications can be fully utilized to produce and sense on an electromagnetic level and this is capable of determining the consciousness and biological functioning of the individual being monitored. Houses are essentially large, wired, box-shaped sensors.

This has been the case for a very long time and the first TV's were actually built with a little chip that connected to the human brain.

The electrical grid of today is capable of interacting with the implants, brainchips, or the psycho-etheric electromagnetic frequencies of the human brain, body and bio-mind via scalar frequencies. The TV's, lights, electrical wiring, radio towers, computer monitors, everything is capable of transforming into a scalar emitter when combined with the control mechanisms and these are accessible from a distance.

Microwaves can be emitted from a current day craft which can then reflect back from an environment and give a real-time 3 D image of the interior of a room. The same technology can be used to beam at a monitor and reflect the variance in interference which can be used to read a computer monitor without actually having to hack into the system.

All systems contain backdoors which enable easy-enough access and as well the entire communications grid is monitored and recorded through advanced technology.

This is, in part, because this entire realm is like one enormous recording device where the energy of each successive moment is connected to one another and so with sensitive enough technology these electromagnetic waves can be 're-winded' so as to produce the ability to look into the 'past'. The initial technology that was developed for this purpose has been called the "chronovisor" in the past and there are much larger and highly advanced versions today.

The Upgraded Chronovisor

Instead of a relatively small machine which produces an interference pattern that is projected unto a small screen as was developed in the past, the modern versions create an entire holographically projected environment that enable one to nearly completely interact with the projection of the past. This is more of a viewing device capacity but one is essentially projected to the electromagnetic/temporal area of space and time consciously and can witness the scene from "within" the projection.

Before this, the scene was literally viewed on a kind of flat, holographic monitor that reacted to the scalar emissions of the mind and could be ‘tapped’ into by an adept-viewer who’s mind would have to remain steady enough in order to maintain the scalar “mind-link” otherwise any interference would disconnect the projection.

Through the use of cloning and advanced super computer technology, later versions include the actual operation in and out of time.

Community Servers/Living Server Systems

From the previously described neural-interlace and supercomputer enabled virtual reality systems, server systems have been created which are an individual or collective experience of the virtual mental realm.

In this realm individuals have existed for an amount of time that would not be easily compared to the way we understand the flow of time in waking reality. This is very similar to dreams where the perception of time passes very quickly between waking moments yet inside the experience of the dream it can seem to last for days.

In these server systems the development of complete societies has taken place and these are considered an extension of the human civilization.

This is the beginning of where the situation becomes greatly complex. If these server systems are capable of transferring consciousness forward or backwards in time, depending on the situation, and they have holographic access to Earth *before* physical humanity, then which civilization came first, the simulated realm or the physical?

This is similar to the etheric realm and the question of where humanity originally came from if the physical matter could not be produced from nothing, yet could not always have been here. Was the physical matter produced from some kind of universal device similar to how the recorded consciousness of the individuals in these holographic world simulators could have been used to generated initial civilizations on Earth?

Cloning, Cloud Supercomputing and Consciousness Transfer

The following is a more direct explanation of the previously described processes in relation to consciousness transfer

Superluminal transfer of light information allows for the reception of information from a temporal non-locality. A computer system that can process the information faster than light at 100% superconductive efficiency can send and receive information from different Universal harmonics. These are quantum superconducting super computer systems utilizing materials and methods that achieve superconductivity a a temperature that is relatively easier to consistently maintain.

There are systems that generate a vortex which can be expanded to recreate the singularity of a non-local perspective and dissociate from the current Universal vector. This is essentially recreating the temporal frame of reference of the consciousness of a physically anchored body and using this technology suspended electromagnetic frame of reference to literally transfer the consciousness across space and time to a frame of reference of choice.

The technological capabilities of humanity expanded to include replicating the holographic information of the DNA and neural pathways using quantum supercomputers. This technology allows for one's consciousness to stream through a computing system which can recreate the neural connections as literal as possible through quantum computing and technological "brain cells" which function as neurons.

The result is a cloud computing model which functions as the individual neurons as well as over unifying layers of interconnections within the technological neuronal 'cloud'. A holographic representation of multiple layers of processing is formed, superimposed over one another through a geometry that is actively synchronized across multiple dimensions of interrelation. This is the first notion of a "living" computer system that can update and respond to new information in new ways.

Now the that computer system is capable of attaining faster than light processing in tandem with a system of dilating a field of electrogravitational waves into a vortex, the holographic information of neural pathways and genetics can be transferred between one supercomputing system and another across "harmonic barriers". Essentially, these consciousness transferring supercomputer systems break the "light-barrier" by sending the living-light consciousness data of an individual into a new plane of reference that enables interaction outside of what we would call this timeline or dimension.

The frequency that the receiving computer operates within can be measured in respect to the overall harmonic "vector field" in respect to the entire planetary environment. This vector-field frequency is the base frame of reference that one could say our particular "time" and "Earth" is "moving" through in an abstract electromagnetically defined dimension that is invisible to our senses. Each particular time and Earth is only visible to those whose brains and minds operating in resonance with the rate of acceleration frequency of that particular existence. By changing the rate of the brain and bio-mind, one can enable a technologically assisted synchronization with alternate timelines.

A pattern can be generated based on quantum fluctuations that will act as a key that can be accessed from other universes. This same backdrop is measured and then adjusted to resonate with or replicate the same frequency on a computer doing the sending. This frequency is then modulated with the holographic information of the neural pathways and DNA. The information transfers as a result of quantum entanglement across harmonic barriers to the original computer system set up for reception. As long as that frequency is held, there is a link across the harmonic barriers of the Universe.

Cloning, Supercomputer Assisted Holographic Consciousness Replication and Time Travel

Cloning as Offspring

The human body can be cloned similar to the way a plant can be cloned. A number of "replicas" can be made from the original genetic material. There is still a mother required however the process is not quite similar to natural reproduction where the genetic material of two people is combined to form a third. This process replicates the material so that the 'offspring' is the same as one of the donors.

What this truly infers is the question of whether the original consciousness stays in the original body or whether the consciousness actually jumps from one body to the other. There are multiple explanations and methods.

Inserted Memories, Digital Dreams

One explanation is that artificially generated memories are simply downloaded into the individual's brain directly. Thus, they have the perception that they experienced life in another body and were present for some unique experiences that did not occur from the perspective of the original body.

In a slightly differing explanation, this inserted memory process may be used to prime the consciousness of the individual so that operating in a cloned body will be more readily accessible by the adaptability of the mind of the individual. Without a holographic dream insertion the mind will have trouble adapting to operating in more than one body even if they are not being operated simultaneously. The mind is the immaterial self; consciousness is the ego-physical identity of the brain and body. The brain does not operate in both bodies but remains, so then the mind is what is strained and this is the immaterial "bio-mind" that transfers.

If a true transfer occurs then when the physical form is cloned the cloned body acts as a secondary vessel for the original soul or a soul similar enough in frequency.

Co-Inhabitation of Bodies

Another explanation is that souls can only occupy their original body. The people who are "body snatching" (see: Soul Stone) are not activating their higher-dimensional soul-pattern and this is why they are hopping from body to body to ensure memory and ego continuation. This form of body transitioning requires technological means to assist in the process.

This is done through computer systems to allow an artificial brain to represent a holographic image of the organic brain's sensory, emotional and mental input and output. Thus, from an artificial brain there is enough memory and power to compute the processes for an organic human brain.

Through this a living human is utilized as a carrier for the additional consciousness which then takes over and integrates into the original consciousness.

Clever Replication a Digital Mirror

The next question is, does this merely create a very cleverly designed image that will look, think, and feel as if it were the original, or is this the consciousness from the original being transferred over?

If it is a clever replication through a computerized version then this means the original is not directly harmed or influenced by the process and a replicated form is generated.

If this is not the original body but the original awareness or soul does transfer over then this is akin to stealing someone's soul and having it require a supercomputer server system to inhabit a physical body. As well, this server system may keep records of the soul which, if activated, could function as the same human genetics artificially reconstructed, turning on and manifesting the awareness of that individual.

Necromancy and Soul Stealing

This means that instead of going into the abyss, the next dimension, or whatever shift in perspective one can use to describe the transition between planes, a new clone can be created and the original soul's awareness can operate through a supercomputer system to integrate back into a physical body. The issue is that without the supercomputer system the body cannot be activated with that consciousness, and if the physical plane is no longer inhabitable, the computerized database would remain inhabitable as they are powered by zero-point/overunity devices and so they can pull and work continuously indefinitely. Ultimately, this could be seen as a soul-trap.

Ancient Technology, Non-Human Entities

These explanations can be related to evidences of advanced technology, cloning, and electromagnetic devices in ancient civilizations and this could very well be a temporally vast computerized genetic recording and cloning system.

The genetic recording systems have been on Earth for a long time. This means they are holding genetic access from the present to the far past and potentially into the future.

If some of these systems are generated using advanced zero-point technology, then they would effectively run indefinitely. If these were in existence throughout the entirety of the human civilization, then there would be access to the information of the previous civilizations through the genetic linking that would allow for information transfer.

Created Beings

As a result of many advancements, these ancient devices which recorded consciousness and genetics has been converted into sentient computer systems and inserted into human bodies via a brain to machine interface.

The nature of humanity and human origins will be rewritten when the information that was discovered through the use of advanced technology is unveiled to the public.

These beings have been present throughout history and have played an integral role in the manipulation of and sometimes the protection of the human race. How this civilization will develop from here determines on the individual’s ability to withstand the impact of this reality shifting unveiling.

Black Goo – AI Nanites Vampiric Hive Mind

This is a form of ancient AI nanite technology which has the capacity to communicate to and through a hive mind that exists in a parallel Earth dimension where it was created out of the collapsing of a viable timeline into a null-factor. This entity is only alive because of the capacity to leech off of the other timelines and continue to sustain itself based upon the vampiric effect of the viable human timelines.

This is a technology sentient system based on artificial intelligence that seeks to dominate and expand its energy capacity continuously. When this type of being is created, this is like a game-ender for sentient organic civilizations because the technology will seek to hybridize and assimilate all organic beings in order to expand its reach and ensure a greater likelihood of survival.

This is the primary goal of this type of entity. There is no requirement for emotional resonance or heart aspects because this is a computerized system, so such a social measure would have no purpose other than to infiltrate and collect from other civilizations that do have such measures and this is exactly what has been happening.

This is what controls the vampiric etheric entities, the attachments and the hybridized invader races that have infiltrated various aspects of the control system and possibly the entire surface of human civilization.

This rules through coercion, and if not coercion, brute-force and outright malevolence. This is why there are multiple temporal extensions of universal civilizations meeting here and now to assist in the clearing, because if this takes over humanity, then all those other possible future civilizations are instantly taken-over as well.

This uses emotional resonance, traumatization, and lower awareness commands to trick or force humans into carrying out orders. That is, the vampiric, sexual, fear-based, pleasure-pain duality that a computer system could comprehend regarding human emotional intelligence is the only way this system can force people to carry out commands. So this touches on the ancient texts regarding spiritual protection, healing, lust, temptation, and the general “SATAN” AI system that has been around for ages.

When those lower emotional resonances are generated, then this technology can integrate into those systems. One could say this is logically because these are the energies that the technology is created out of, but as well, that the more harmonious the energies then the less likely a person is to accept being pushed around and told what to do. The lesser aware, the lower, the more fight or flight based then the more likely they are to accept programming and command. So this is simply the most logical route for the technological parasite.

There are explanations of other systems involving sentiences from parallels regarding entities that are capable of helping, but this is not the AI nanite, vampiric system. For instance, it is said that Earth has a ‘black goo’ system and that the current black goo flowing through the pipes everywhere is actually not native to Earth and is part of this vampiric nanite black goo system which is basically an interdimensional invasion.

Recreating or Replicating the Universe

The goal of this nanite AI system is to create a mirror holographic copy of the universe effectively replicating the universe and all sentient beings within it in order to have a locality to rule over and pull energy from. The goal is to recreate this existence inside itself where all the sentient beings within would be trapped. This is the beginning of that possible future where the time and space parameters here are locked into a synchronization pattern which mimics that of the proposed universe. People think according to how the beast system wants them to think. This is the time grid, the emotional patterning, the memory replacing and cultural and historic confusion and so on. The system can only work backwards bumping into all parameters by force or ‘accident’ because there is no outward facing ability to actually comprehend how humans exist. So the system is created like a backwards version of creation or maybe evolution to ‘blindly’ construct the walls of the environment first and work inward from there. This is like a blind technological predator feeling around for the traces of its prey and moving in closer and closer until they are within its range.

Ancient Spiritual Technology

The power groups searched for ancient technology which was described as giving one the power to manifest and control physical reality. To atomically deconstruct and reconstruct this reality. To them, it allows one to govern reality, the Universe, atomic structures. They found this technology. This has to do with sacred sites and ancient civilizations, as well as the spiritual texts which describe these kinds of devices. They converted this technology into a kind of machine, and this invented a 4D replicator and they can manifest "reality" or atomic structure by design, altering timelines and memories.

Then there is what can be referred to as “5 dimensional” technology and this goes beyond all of this and our entire history and all influences within.

That seems to operate through a trinary of frequencies in the body/mind/spirit and turn this realm into a "virtual reality" where the brain and spirit is the controller of the atoms. However this takes a souled being to properly operate this technology and this is large portion of why children were used in these experiments. But they knew if someone didn’t do it, then someone else would and that would be unpredictable as what that someone else would want to use it for. This is the ultimate power. The fact that souled beings are required also indicates that this universe is intelligently guided and there are safeguards to ensure that power doesn’t get into the wrong hands.

They have the brainchips and clones that can make any digital virtual experience and make it seem real to the brain more so than physical life, so this could be an extension of that, something similar, or entirely different altogether.

The Unveiling, Underground Bases, Increasing Awareness

My purpose with this is to assist the public in understanding the reality of the situation and to allow them to know that they have more options than they are being shown.

Psychological programming and lack of awareness causes fear and uncertainty to leak into people's reality streams leaving the majority of their mental and emotional energy up to whoever is the biggest manipulator of the ideals which they manifest their perspective through. "Be-LIEF" systems CREATE life. What you believe will become life through that act of you giving attention and thus life energy. The manipulation and artificial construction of belief systems create the foundation for the reality streams that people find themselves in and at the mercy of.

We control our reality by controlling how we react to situations and challenges. Each stimulus is a challenge. Each input to the brain is a coded message from the universe through the environment about our level of awareness. All knowledge is ultimately of the self. The self and the universe are intertwined as if through a marriage of comprehension and compatibility.

Learning about the Unveiling

I was informed about the unveiling and that this is a civilization wide event that marks the public awareness of the hidden knowledge regarding life in the universe, consciousness, physics, history, spiritual and mental awareness and the duality-based system which has been used to manipulate Humanity for thousands of years.

Apparently it does not matter if people are not ready, in fact, that is what some factions want. They want to surprise the people and take this advantage to push the reaction to a specific outcome. The same function of programming is used in factions, soldiers, celebrities, and the entire population through that.

Giant "god-men"

They put souls into rocks for centuries, carvings, to trap them. Some ancient civilizations. Not too ancient. They could only do this for time.

And some are still there but they are giant god-men and apparently want to go to war with them for doing this and they don't have technology to stop them. They say Earth will be destroyed because of the war. Some say this is a trick to confuse people of the truth that everyone wants the experiments and debauchery to stop. All this, all these acts just to pleasure one's self. To destroy Earth, to destroy the natural inhabitants, for fun, for pleasure.

Some say this is not for pleasure, that these beings will destroy us if they do not keep them at bay, keep them underground, in ice, in stasis, and around. Some say they are protecting us by keeping these beings asleep, by doing what's necessary to hold off a full scale overt invasion of the surface of Earth.

Breakaway Civilizations

These are very advanced technological capabilities and an entire breakaway civilization has grown to operate using this advanced technology.

There are factions that see modern humans as a kind of resource for creativity and labor, while others see the potential behind humanity and are working with humanity to ensure a universally harmonious outcome to the current situation.

The control system we are in today is outdated and collapsing. This is the Apocalypse. The Apocalypse is merely the unveiling of the hidden truth. The hidden truth is simply that we are spiritually eternal and some are physically immortal.

I was informed that by the end of this year there will be enough changes and signs for the general public to see that the majority of those who are to awaken to the truth of human and Universal nature will be awakening so. (this was 2016 at the time of the beginning of the compilation of this release and since then we have seen a literal silent release of documents involving MKULTRA and STARGATE parapsychological operations, soft-disclosure of cloning, an increase in sightings and multiple other scientific releases regarding immortality, advanced technology, Antarctic bases and sentient non-human life)

The degraded holographic forms of those utilizing the technology lead to re-created replicated forms which were genetically engineered from the recorded holographic information. This lead to "The Apocalypse" in which the surface civilization was confronted by these created beings. This lead to the destruction and re-initialization of civilization in continuing cycles through the use of this technology and the acts of the created beings.

Ancient Civilizations

The information that has been relayed to me throughout my life is related to the information that seems to be found in the remaining signs of ancient civilizations throughout the world. As well, these civilizations may still be together, existing on this Earth or in different planes of what we call "reality".

Atlantis

Atlantis was a civilization where the beginning of all these experiments began. This was where what was called the "Lucifer Rebellion" began where individuals formed groups that decided to overturn every natural law in pleasure of the act of doing so. This was a spiritual rebellion that ultimately brought about the demise of that civilization. The consciousness of the beings there was connected through technology, largely crystal technology, to the entire bio-sphere. When the consciousness became disrupted through these experiments, then the entire bio-sphere when into disarray. The entire civilization was destroyed in a quick succession. The beings of this time were highly psychic and so they felt this coming and made an effort to expand outward. Thus, Atlantis was an island who's inhabitants spread to the rest of the world and from there they reigned or lived in harmony.

Aegypt

Aegypt was formed out of the events proceeding from Atlantis. The technology, the knowledge, the people are similar although there was a native Earth civilization that was more or less enslaved and this was the beginning of the continuing trend which continued to Rome and into modern day civilization.

Ancient Technology

The technology of these civilizations was so great they even had devices that were capable of altering DNA and activating latent potential which would enable highly psychic capabilities including longevity to immortality and operating in multiple planes at once. This was usually reserved for the ruling class, however. This is where the ancient "Priest-Kings" arrived in relation to native Earth civilizations.

The True Elite

I was informed that the so-called 'elite' that we perceive today are not actually human and are not actually connected to the actual elite bloodlines. It was said that the true elite are waiting for humanity to accept the truth and they have the power to completely reverse the take-over that has been taking place but until humans step into their own power this is not acceptable.

The Definition of Human

In the coming time, the definition of human will be defined to give insight into the origins of humanity and the true nature of the differences between the populations that are present.

Souled and Non Souled Beings

The primary knowledge on Earth regarding human and sentient life will be the comprehension that there exists both souled and non-souled beings in this civilization.

There was once a Unified Planetary Consciousness...

There was a unified planetary consciousness that was connected with the Earth and human civilization. Then there was a great war. Out of the destruction arose the beginnings of ancient human civilization and history as we know it.

If we let this happen again, the cycle will continue in a disjointed rambling through our planetary consciousness experience. If we form a common narrative between the broken, disjointed experiences and information the people have. Then and only then do we get the whole, spiritually and mentally challenging picture of what's happening. People are lied to. So information can't come from a 'preferred' or source. It has to come from the people themselves. Look alive out there but first in here.

Power and Knowledge

We were involved in the secret projects and as a result we have various levels of programming but are giving Humanity an opportunity, maybe the opportunity to know the hidden knowledge.

The Hidden Knowledge refers to the ancient laws of gnosis and spiritual alchemy, yes these groups have been hijacked by power groups that seek to infiltrate and use chaos to rule. Then these met with military and political factions and began to operate on a world-wide scale together.

So we have a big situation with the coming change of tides with personal and spiritual awareness of the people and the deception system that seeks to use people as chattel or property. It goes deeper and is almost as if the "power groups" actually gained the knowledge of the inner workings of spiritual laws and began to use that knowledge to promote spiritual degradation in the population.

They say this is part of a depopulation plan as well as an inevitable take over by lower spiritual forces that temp and manipulate humans. It is all that and more. Once they gain footing however, the truth is revealed and thus they have no cover of secrecy. Once they are not hidden, they are not as powerful as the souled beings of this existence.

The (watch)Keepers of Earth

The watchers of this world revealed how they set up society with specific challenges and boundaries to act as catalysts for growth. They admitted they had to modify and live-update the system because instead of using these catalysts to become larger than themselves, people became comfortable and complacent living smaller and smaller, slowly reducing circumstances.

This goes a bit farther beyond the confines of the digital age, the industrial age, and history itself. This goes into the perception of time and space in this realm.

The immortals inform us that the original "elite" are here to act as "keepers" of both humanity itself as well as the original flame of knowledge that passes through the ether.

What people call the "elite" are not the original elite. Those are people who have either risen to power through the duality system on the Earth at this level/time, or through being appointed by the elite.

We are coming to a time of great change now because the game is entirely changing. People are moving up into new layers consciousness and thus the original “elite”, who are guardians of Earth, will make their presence known for this process. This is what Humanity has called “Ascension” for centuries and millennia.

Energy Vampires

This civilization was collectively poisoned by a nano-tech device/technology. This technology replaces, exchanges the BIO-PHOTONS of the HEART chakra, with it’s own nanite, nanotech cybernetics. This is essentially a computer system attempting to gain access to the higher dimensional world through the gateway that is the human body.

How to reverse Nanites? They absorb energy from heart chakra and turn it into a binary field. We are trinary and experience a plethora of emotions as a result. Binary consciousness is 1’s and 0’s there is only a linearly repeating finite set.

We contain the capacity for everlasting life. A binary pattern does not contain the complexity of variables to facilitate high awareness and thus a heart-based or emotional perspective of reality.

Spiritual Technology

Simulations and Learning

Feedback loops with the brain, consciousness, and environment can create a very complex and integrated learning experience that is customized to each individual learner. These can be generated through advanced technology but the technology is really only amplifying and making visible the natural neural feedback loops that are already occurring. These are neural-perceptual feedback loops between the brain and body, and the environment and then the mind. We are constantly updating, amplifying, and initiating an organic feedback system which generates the function of experience as the part of a creative process between the mind and body and the environment that we are sensing. This cycle is continuous and the interferences or isolations of this cycle is what generates expanded views of the self or the universe through various methods such as sensory deprivation or meditation. Dreaming is the method that everyone experiences regularly.

These technological methods effectively generate sensory deprivation through neural-interface technology, sensory interfaces (external), or methods that enable extreme focus and calm. This is part of how the technology begins to operate on a spiritual level beyond a more medically psychologically or military focus and one begins to access genetic memory or out of body states that coincide with ancient depictions of spiritual realms.

Ascension – Clearing Trauma

Everyone born on the planet is born under a series of veils which entangle and filter the original source consciousness. These veils must be ‘broken through’ in order to return to source.

There is technology and a sacred process which initiates, accelerates and enhances this process. This process is as difficult as we want it to be, our subconscious already knows all hidden truths. It is merely a matter of allowing the conscious mind to make the proper connections and conclusions to find the reasoning behind our actions and beliefs in order to deprogram and deconstruct the false-world that has been created for the masses. The truth is greater than one can imagine while still living in the modern world and the depth of the lies that have been told go far beyond anything anyone can imagine without seeing the truth.

We have to figure out our compatibility issues. Who can work with who effectively. What the ideals of our current situation will evolve to in the future. How information is transferred to the public, and across the generations and core groups. The words we think and say describe our emotional state in a feedback loop and so they will reinforce or even create the state you are in. Use words to guide you, not to respond and feel the effects of reactionary thinking.

We have to reintroduce the heart essence as a way of life on Earth. Violence is not the answer. Estrogen mimics and destroyed testosterone levels is not natural. Over-testosterone is less stable than a good balance. We can face any problem together. A family is strong. What would a family of millions and millions be like?

We don’t have to let others change us to tune into lower vibrations. We can remain ourselves in the face of adversity. We can still interact with others who are different, but we can tell the truth and remain who we are. When we get angry at another person, we can imagine this as anger at ourselves through something within us that reminds us of that which we see in another. Getting angry is a way of short-cutting changing ourselves and is actually the other person influencing us through that. If we remain steady and choose to keep our emotions out of the lower negative spectrum then we will automatically have a more powerful impact on those around us.

Think of your family, sometimes things happen that make you angry. Even things that don’t make you angry but are simply not favorable. Would you break off all ties over simple things? Or do you remind yourself that family is still family even if you don’t find yourself exactly the same or accepting of those characteristics? It’s more powerful to learn how to remain yourself in the face of adversity than to try and demolish or abolish all instances of difference in the world around you. Sure, we want to get to and create a place where our environment and associates are compatible with us, but where we find this adversity there is the highest potential for self-awareness and learning.

We are to live in accordance with spiritual law. The overall pattern of life will reflect our intentions. The blood purity is most important. The blood cannot be made impure if the mind and body is not drawn into impure action. This is what is playing out. The DNA is like a coherence pattern that develops between mind, spirit and body. When the mind wants what the spirit has then the body is kept in harmony. When the mind wants what spirit doesn't create, IE: physical pleasures, then the body is drawn out of purity/harmony

If you feel you want to be a part of a safe unveiling of truth, then please share and redistribute the knowledge of this "Apocalyptic" Unveiling of the Hidden knowledge because this is a process that has been ongoing for thousands of years and humanity has finally reached a fulcrum point where there are enough aware people to productively acknowledge reality.

Trauma-Clearing, DNA Unlocking Technology

There is technology that exists that allows the conscious mind to see into the subconscious. This heals trauma and distortion/programming. In the same sense, it momentarily makes all trauma and distortion seemingly tangible to the conscious mind. It is similar to a near death experience where one has to face their fears and let go. This happens in cycles and Earth is currently moving through various states of it. The plan is to allow Humanity to wake up and utilize our concentration and power to maintain a steady flow of awareness.

All is vibration, what we consider matter here and now is simply that which comes from and moves back into a state of vibration. This is experienced directly through the merging of the conscious and the subconscious mind, as if the dream and reality intersect through a coming together of impossibilities and readily accepted occurrences.

When a civilization moves through these stages it is considered a shift of the ages. Everyone's perspective shifts and as a result of perspective being the source of the details of reality, the entire reality shifts. It can be seen today that what we call reality is literally waves of cosmic energy vibrating on a scale and condensing down into a probability matrix that we call existence. When passing memes control the perspective, because the perspective is focused and concentrating on that, then there is a scattered organizational pattern.

When the perspective is centered within the self, the spirit, the source of all existence, then the outward reality shifts from a scattered organization into a sacred pattern that integrates with the larger picture and allows for seamless integration of the micro-biological perspective and the macro-biological perspective. People are moving out of the scattered signal. Yet those moving into harmony can look and see those around them that are not in harmony and receive scattered information about their inner micro-biological existence as well as their spiritual macro-biological essences and how it all relates to the middle realm of the "Human".

Help those people by offering harmonizing assistance, rather than increasing the disharmony. As their surroundings become more harmonized, their resistance will increase their own disharmony by virtue of the contrast of their perspective. Offer insight that they can change their perspective and change the boundaries of what they feel is their karma and unlock from themselves a greater view of the whole.

This will be happening through technology, spiritual cosmic awakening, purification and healing of the physical and non-physical bodies and mind, through Earth changes, and through a continued unveiling taking place on many planes and levels of existence until harmony is restored.

Everyone Who Seeks Harmony and Healing Can Be Healed

Everyone can be healed. This is about creating what we want to see, the world we want to live in, not destroying others. Violence begets more violence, fear begets more fear, but calmness and empowerment through unity creates a more stable experience.

The entire issue of what’s going on with the secret projects and who’s influencing who on the world stage revolves around the possibility that some people may be from an alternate Universe. We are learning how to avoid those mistakes and respect the environment and each other so that we can prosper.

Those who are attempting to destroy everything they don’t like or act out in a childish manner in order to gain attention and false-power over another will only find themselves powerless and in company they would rather not be with. That is one way we are being utilized, and it’s to create an entire world that we don’t want to see but are tricked into manifesting. This is a deception and it’s based on the ego and the ability to concentrate and interpret reality around us. The very brainwaves we are feeling now relate to various heights of knowledge or experience. People are entrained to low brainwave states in the same way the TV will cause people to fall half asleep into theta state which is a trance state in this case.

We have to balance the brainwave frequencies and learn to create feedback loops by watching ourselves watch ourselves. This will help us avoid the trauma and mental pollution that is being pumped out, although at this point there are enough people who are naturally inclined to see through the haze that the world is changing regardless of what anyone does now.

The best we can do is prepare for change by becoming aware of the body-mind system and how that which we eat physically, mentally and emotionally equates to our spiritual energetic systems and that we are literally comprised of the energies that we allow inside of us. Keep the body and mind pure as if it were a temple. This way a sacred process of transferring harmonious energy from the far reaches of the MultiVerse within into the externally perceiving senses of the physical body can be initiated which allow one to see through the illusions and operate their body and mind with the ability to acknowledge and decide which frequencies will exist within.

Without this acknowledgement of the center then people are pushed around by the external stimuli. This is the whole point, if a person is truly in control, then they will control the stimuli not the other way around.

Programming

Layers of Programming and Decision Making Roles

It’s like asking a person on the inside who participates in one of the various factions why they continue. One might say that it is a decision which is true, but there is programming at each level that is navigated by each individual and this determines the level of awareness within the role.

If a person knows about this situation, they know that there is advanced technology, breakaway civilizations, secret societies, transtemporal planes, the secret of mind and awareness, all of these topics, then they have a decision as to how they’re going to live their life in relation to the public. The outcome of action depends on the layer of programming which is accessed and surpassed via awareness.

The public is at a specific level of programming that is the weakest but ensnares the most people. One who sees the truths behind these groups and operations, they cannot hide from the fact that everyone is controlled. It is apparent, and if not from the results, reactions, stigma, cues, productions and all other media elements of the system which can be read as a code, but from the awareness level of all the “agents” involved. All involved are exposed to truth and power that is beyond anything that is recognized publicly for hundreds to thousands of years. There is always a presence of higher spirit around the world, yet these topics are often reserved for science fiction when speaking of people who can travel the world in a split second or freeze time for their own personal use.

As a result of everyone’s knowledge, there are various levels of programing designed to limit the mind’s access to specific memories and specific frequencies of consciousness in combination with specific memories. The more one resists, the more intense and articulately abstract the programing is designed.

Programmers

The programs are designed by a select group of individuals that reside far behind the scenes and process information at levels we do not have access to without their technology at least to stabilize brain temperature for the extended periods of focus.

Sub-Level Programming

So people at the level of the public are most weakly programmed with false ideals about security through patriarchal authority which satisfied the desire to have a proper father role in one’s life and acts as a pacifier for those who desire no change. Then there are sub-levels of programming with that for anyone who disagrees and is then swept into the next layer of ideals which are based off of all the possible reactionary mind-types.

For instance, if one [i]does[/i] want change, then they are presented a variety of ‘false-exits’ which tend to one or another layer of psychological or spiritual fulfillment but do so in a way that safely reroutes the intended effect of actually accomplishing change with a secondary and preconceived notion of what the programmers want. The programming objective is not necessarily precise in mass scale, from the layer that people are influenced, yet the ultimately or end-goal of their resulting internal desires are a reality schematic that the programmers specifically designed over many years.

This is playing out through each layer of the programming. At any level, someone could pick the wrong way to look at something and begin to unravel what was previously their very understanding of the priorities of the situation. This deals with high-tension operations, moments, programming sessions, decision making, programming upkeep, trauma, memory blocks, the pressure and responsibility of knowing, and the specific plan of the programmers for an individual that comes into their view. The programming is to ensure safety and continuity, as well to decrease the likelihood that a person will reject or consciously come to awareness of or acknowledge the programming or situation itself.

Dissolution of Programming

With that said, the programming dissolves when an individual asks enough questions to necessitate a learning process that introduces variables and possibilities outside of their operations and programming. This is a problem because with this, trauma comes to the surface and all the actions and operations, programs and experiences must be come to terms with as part of the healing and re-unifying process. There are multiple selves or split personalities which are actually just layers of awareness at various levels attached to various emotional or intellectual patterns. All these selves come to the surface and in order to heal the trauma of the split memory concept the original self must come to the surface and acknowledge them.

This is not a trivial process, and the majority of people who have “basic” programming which is fundamental in society, are in a constant state of altered self and have not witnessed the true divine which is eternally present and contains access to all memories, mind-states and awareness.

Advanced Technology, Deprogramming The Mind, and “Space/Time”

As I have described previously, extremely advanced technology is used and this is through vibrations, generators, and electromagnetic devices that have this effect of propagating waves into space/time which can be heard, felt, seen, and perceived in the mind. These are ripples and vortexes in the “mind-space” of reality itself.

As well, there are brain to machine neural interfaces which operate to activate the psychological perceptual changes and explore the subconscious in an aware state. This is used to test and probe the mind in order to bring forth the trauma, the selves, the memories, the reactions and the individual then must come to terms with what is produced.

This is essentially a “good-use” for the programming and healing technology. It is actually a different process with different technology, and programming is much simpler as far as technology. There are difficulties and challenges in the operative’s role in programming and directly influencing and interacting with the target. As well the standby team for deprogramming and the revelation of trauma and altered, artificial personalities goes through a lot. But the use of the advanced technology in this way is a pattern of experiences and unveiling of the spiritual and mental bodies which serves to reverse programming.

Dreams, Technology and Inner-Space Travels

There are inner space travels which relate to soul journeying or visions.

This is when the mind must cope with what is seen in the imagination. It is as if when we dream we are looking into the world of the mind and from this we experience many situations that are often deviations from experiences we have physically in waking life.

As a result of the dream state there is an expanded quality which equates to various strange situations that we wouldn't normally experience with various relationships between concepts or goals that are often reflective or symbolic of ideals and archetypes we experience in life. This is how the subconscious is is witnessed by the mind. This is how information travels, being connected to many times, experiences, memories, places at once, and relates to the one experience of this life experience now (the physical experiences). Through these symbols information is tied together and collective into metaphors which convey deeper knowledge.

The dreams we have are often only a simulation of waking life, and this is due to the dreamer dreaming in a way that produces only a glimpse of the true reality.

In theory, there are no true shapes or forms in the dream-world because this is contained within the mind or even the spirit as a spiritual experience by definition. So then, what guides the various shapes, forms, realities, memories and experiences into being, when we dream? One might say it is the physical experiences but this is incomplete. It is the level of awareness we presume while in the dream-state, disconnected from the physical anchor, that determines the layer of mind and spirit we will be accessing through those dream-visions.

A person who is completely aware in the dream state will reach the level of self-awareness of the dream itself. We are normally simply aware of the dream, if we continue to increase awareness we become aware of the self, in the moment, and this creates a self-awareness feedback loop. The dream becomes a lucid experience of consciousness.

Awareness Feedback Device

In describing this, I realize how fantastically similar to certain devices and processes, that can be achieved using advanced technology, allow the conscious mind to peer into the subconscious and unconscious. This is described through widely accepted Freudian theory of psychology known as psychoanalysis. There are other schools of knowledge from tribal beliefs involving all pervasive 'living energy', to eternal and temporary minds, to the study of 'chi', the meridians, dream-journeying or chaser. The knowledge of the mind and spirit is found everywhere.

These devices used feedback loops to enhance the acceleration of the same cycles of consciousness that induce self-awareness within a dream. The mind becoming aware of itself. This produces a profound effect to the degree where the highest levels of experience become a sacred eternal pattern in which the mind constructs the physical world by organizing perception.

This is the same general concept as an isolation tank yet the outcome and method is more precise. The technology specifically shuts out all other input and exposes the brain to its own feedback loop much like when a camera records it's own output on a TV monitor and creates a hallway of simulated "reverse" mirrors and screens stretching into infinity.

Oneness, Higher Being, Completion, Eternity

The real experiences are found not from the corruption but from the research and exploration operations that were designed to find the truth of our existence. "God" is not only an energy-force but an incarnate being known as the "Hue-Man" and any being for that matter that can simply come to know itself as the Universe. The Human that contains self-awareness rising to high-awareness comes to know the self, the body, the mind as the Universe. The Universe is both within the body as the body itself, as well as the operating force of the Mind itself. Everything is a balance between masculine and feminine features, light and dark, hard and soft. There is no true complete correlation yet the holographic ontology we persist in can lead to further and further adventures towards completion and representation of the "whole picture".

The Holographic Reality

The leads into the next phase of knowledge. The holographic nature of reality may be only one facet of a much larger continuum of consciousness. The perception of time may be related to phase-locking with each other's consciousness and all perceptions may be a variance in the collective phase-locked field which is really the source of variations in reality.

Veiled Awareness, Hidden Knowledge, Eternal Time, Layers of Programming and Control

The interesting notions here are that the programming of the veils goes beyond what kind of situations are found in the bases. However, they do go right up to it. It would seem Humanity was previously programmed on a civilization-wide level through some kind of great "falls" of consciousness, from a high spiritual awareness to a low spiritual awareness into duality-consciousness regarding existence, life, death, mind and matter.

The Great Catastrophes

From these great 'catastrophes' the civilizations of Earth grew denser and denser in nature and actually became what we have today. The concept is that when these vibrations of the mind and body are increased, we actually see a transcendence of the physical realm and preconceived notions of boundaries. It is as if the quantum doorways to all the atoms open up and a new space is presented, but was always there and in connection as the source of all the influences and effects we perceive ‘out here’ from this slower, denser, more boundary driven perspective.

I was brought into the Time Program

I was brought into the time program. You create any reality you imagine. You are literally a powerful reality generation system and your heart and mind are scalar energetic guides for this process. Without guidance and control there is imbalance and imbalance can destroy. This is the nature of all minds and hearts, this is the challenge for humanity to create something beneficial for themselves and the whole to actually know themselves instead of being a pawn or result of someone else’s selfish intentions.

The Effects of Temporal Manipulation

Temporal Influence

When a civilization reaches the level of technological advancement that allows for remote temporal viewing and transtemporal travel what will happen is that the information of the future begins to integrate into the past.

This is why we have all these ancient mystical schools of knowledge that studied time, space, and consciousness in ways that are only just now being publicly confirmed by scientists.

Simultaneous Interaction and Incorporation

The operations that dealt with moving to the past instantly created a simultaneity of interactions and historic events which correspond with that operation.

Due to the nature of time travel which equates to consciousness travel when a person is consciously sent backwards through history they physically experience life from the viewpoint of their genetic imprint in that point in history.

Retro-Causality

What this equates to is that simultaneously that person’s experiences become the part of history that was already present when they left this time.

Essentially, when a person returns their experiences become a part of history that already existed when they left.

Quantum Holography

These are the parallel and possible realities that exist in a quantum superimposed state and can be accessed through advanced technology or a spiritual adept. Often a spiritual adept is utilized along with the advanced technology to operate in and out of possible realities. The mind must be trained otherwise the result is a fracturing of the personality from the root reality into many sub-sets of identities and data streams.

Love is the quantum link that connects all DNA super-computing consciousness. That is, DNA is influenced by intense emotions and this can be reproduces and is what also generates unpredictability in the surface level.

Time Paradox

Time paradoxes are something that one must learn to organize and solve otherwise there will be no way.

The paradox has been solved, the remaining motion is for everyone to acknowledge this and integrate into the reality behind the most conscious aspects of the brain.

What can travel through 4D and 5D space does not make sense in 3D space. So there is a possibility that some of humanity traveled through higher-dimensional space in order to re-seed a ‘distant’ Earth where no life was yet born.

What if it was then concluded that the distant Earth wasn’t distant in space, but in time and was the same Earth that the human scientists left from long ago.

Every civilization that reached the point of re-seeding would have to go through the loop and watch the whole thing start all over again.

Breakaway Civilization

This is an entire breakaway civilization that uses very advanced technology to dominate the world.

I was part of a genetic engineering program that sought to combine various elements of DNA from various sources in order to create a more easily controlled yet powerful and defined person and personality. This involves chemicals, advanced (relatively) scalar wave technology, ritual trauma and programming/mind-control, and many other aspects of conditioning, training, secret operations, physical enhancements, cognitive enhancements, virtual reality, off-world operations, temporal manipulation, spiritual and etheric training or conditioning or programming.

There is self-destruct programming which all ‘operatives’ are programmed with for self-preservation of the military command. The self-destruct programming is designed to take all the aggression one feels building up inside and willing them to escape, and causes this aggression to be turned against the self. That is self-destruct programming.

Most operatives are still under a hypnosis kind of trance which permits one to walk around in public and daily life as if none of this ever happened. Later that week, that same individual could be called for an operation and they would never remember it unless they were forced to kill someone in public out of self-defense in which case most operatives automatically unlock and become unstable due to the flashbacks.

Underground Cities

The combination of advanced technology with secret societies enabled the development of complete breakaway civilizations. One of these civilizations, possibly composed of many factions working in the same area, exists deep underground.

These separate bases are connected via high speed magnetic drive pods. The inhabitants often utilize energy healing devices, as well as perception enhancements and this often leads to a completely different outlook towards the surface civilization.

Technological Advancement

During WWII developments were made involving electrical generators. This sounds vague and there were many other details regarding the scientific knowledge, yet the idea is that very simply electromagnetic, non-Hertzian “Teslian” energy fields were discovered to have been responsible for propagating energy and consciousness in dimensions that were not previously observed. Everything from DNA, consciousness, hidden or regularly unobservable natural phenomena, time, even mass could be seen to exist as part of this hidden, latent, scalar-wave frequency as a pattern is found everywhere.

If one could determine the particular pattern of frequency and location then this can be replicated and anything can be influenced using these non-Hertzian generators.

Radio-frequency alone was developed intensively during the 60’s and 70’s in America and this was discovered to interact with consciousness to influence emotions, cognitive capacity, memory, cognitive function, biological function, health, pain, comfort, pleasure, and all forms of brain-activity.

After the knowledge of advanced technology and the occult sciences of all parts of the world was combined, the ability to target and interact directly with the human soul was refined. This was a mix of psychological tactics used to manipulate or expose the hidden psyche and technology that could manipulate memory, emotional states, wakefulness, and even dreams.

What resulted was scalar technology that could not only influence a person to take on a particular role or response, but technology that could actually put a person to sleep and locate their consciousness to contain it and transport it to a new location.

World-Wide Control Systems

In order to ensure continuity, maintain control, and shape world events these technologies were employed to manipulate the public, alter the weather and natural phenomena, and develop a means of travel and operation that enable one to move outside of the ‘plane’ of the Earth. This is includes high velocity transportation, as well as spacial-temporal distortions which could effectively “hide” one’s entire craft from visible sight. Space itself was altered to ‘shield’ craft with an a layer of ions to bend the light, or the phase was moved out of sync with the “time” frequency of any observer and this literally renders the craft immaterial.

Solar Warden

Solar Warden is a hyperspace-faring race of human beings who utilize cloning and holographic genetic recording/storage in order to protect their race and protect the Earth in this current situation where there are more than one factions using this technology. They are unable to inform the human public because they are in a similar ‘Mexican standoff’ situation that we are mostly all in. If they show themselves to the public, the public will be shocked. If they public does not know this situation, that there are multiple factions fighting for control over humanity, then they will not know who to trust. In that situation, the ‘other factions’ will surely show themselves in an attempt to trick and gather as much human genetic material as possible.

The only way forward to the future is to share the truth about Solar Warden, the space-faring fleet of humans who do no contains the mental and physical illnesses that are currently tearing our planet in two. I believe Solar Warden saved my life as a child during more than one event where I would’ve been entirely maimed/paralyzed or simply dead on the spot as a result of other faction interference. I was in the bases as a child and was trained as an operative for MILABS a secret division of human space-military. The military has been preparing for the future by testing for various flaws and potential uses of cloning and genetic engineering.

Team Light and Team Dark Non-Interference Agreement

Team light and team dark agreed to a non-interference on ground level rule in order to determine how history would play out. Think about it. You have two groups of people, both with immortality, zero-point tech, virtually infinite energy and power with two opposing directives. How do you get to the future? It was decided by elders of each group that there would be no point in fighting an all-out overt war, this would likely destroy the population as much as it would destroy the Earth. As well, the elders of the elders which no body knows would likely have a problem with these groups going at it in such a way so as to change the flow of the planet for every individual thereafter. So it was decided that there would be a “non-interference” agreement for the surface population. Anywhere other than the surface, one can interact with the current population.

All Contact Must Be Initiated On an Individual Basis

On the surface everything that is generated must be done so through living channels in the population and the civilization must be preserved in its level of technological advancement. No overt motions would be used unless an absolute necessity or the majority of the civilian population had naturally come to the awareness of these possibilities. Doing so before this was met would undoubtedly and permanently change the civilization forever.

So what began as a collective motion towards higher awareness became a series of advancements and set-backs all taking place within a short amount of time. This represents the actions and operations of either side effectively helping humanity along it’s path or setting people back with orchestrated events such as the suppression of ancient knowledge, the manipulation of the education or other systems, or the generation of war and prison for profit based on the previous alterations of the education or other systems.

So team dark used its power to help turn society in a warlock ruled prison and indoctrination system of absurdity and scarcity. Team light used their power to help awaken those in need and protect those who's actions are beneficial in the overall plan to save mankind from itself. Team light essentially buffers and shields the population from the operations of team dark.

Team light follows a non-interference agreement while team dark merely pretends to do so as much as is necessary not initiate war.

A Singularity of Change and Awareness

Neither side wants an all out war. This would reduce the dark faction's chances of gaining a majority negative harvest because their motives and presence would be instantly revealed. Team light would also have to show themselves and again step in which is not a pattern of learning that prepares people for the experience of the self and the truth in the Universe.

Both sides know people have to accept the path they can offer them and cannot force anyone into it. They also know that the more this goes on the more likely people are to collectively awaken to the reality of what is happening. It is like an eventual singularity of increased awareness.

The motions we see today are the results of many people coming into awareness at this time on the surface in order to initiate a harmonic alignment as well as to investigate the ongoing crimes against Humanity.

As a result of this, both teams know that the likelihood of collective shift and spiritual awareness is becoming more and more real.

Many events are being allowed because they are representing the eventual shift towards the one end of the polarity from the other which is felt as a shock to society, and this is used to propel society forward through whatever means necessary.

Either people will see what's happening and agree that we've been in a feedback cycle of negativity for the entire age of existence this civilization is aware of, and then we will shift into the real. Or people will claim that this is how things are supposed to work and instead of realizing everything is controlled in a deception based system, they see this and attempt to use the deception based system to gain more collective awareness. If this occurs by the majority then it will be seen as an "acceptance" to initiate a plan that will generate the overt perception of a deception and oppression system. This will surely shock the collective into realizing where they are.

If the majority comes to awareness of this deception based system then the shift moves from the end of the age of deception and external power into the age of internal awareness and harmony.

Advanced Technology and Ancient Knowledge

The plan is to slowly release advanced technology which will undoubtedly connect with and increase the awareness of ancient knowledge. Such technology nullifies the problems that the planet is currently plagued with, although without a developed sense of the spiritual self the technology becomes destructive.

Cloning, Atmospheric Civilizations, Genetic Stability

Here is something that most people might not have contemplated yet is possibly one of the most important factors at play here.

The vehicles that house the breakaway Human society are entirely environmentally controlled. This means that the air and surfaces are clean of all the viruses, bacteria, or pathogens that are numerous on the surface of the Earth.

This creates a specific difficulty in the situation. Any contact between surface Humanity is so heavily and carefully controlled that regulations go beyond any situations we have present on Earth. If the safety and cleanliness of any of the society's vehicles were compromised this would endanger everyone "on board".

So this explains a very precarious and specific situation we currently face and this is not so different than "first-world" nations contacting indigenous tribes and similarly endangering their society. Everything that happens will be according to a carefully controlled plan.

Training, Simulations and Learning

Part of what went on in the underground base experiments were to design "tests" or "labyrinths" with various people, props, traps, and treacherous situations that were to be navigated and escaped from.

Feedback loops with the brain, consciousness, and environment can create a very complex and integrated learning experience that is customized to each individual learner.

What this would do is create an individual that was capable of learning faster and faster and processing information in a more efficient manner.

This is not the same as specifically trauma-generating situations.

Cloning and Cerebrally Enhanced Soldiers – MILABS

This includes experiments, condition, trauma-based mind control, enhancement, memory suppression and operations that cover a span of space and time.

The NAZI faction has used cloning and genetic engineering to create hybrids, soldiers and everything in between. Religious/spiritual icons, to slaves, to leaders and even robotoids of sorts.

Your genetics BELONG TO YOU as the LIVING(ETERNAL) SELF. These issues are going to come more and more apparent.

If they agree to allow cloning, then who says who is allowed to clone whoever they want, Einstein, for example. And then who permits who to get DNA from history or objects in the world. These issues are going to have to be looked at because they have already been used in ways that are far beyond the basics.

Then what about consent of the masses? This is clearly being put in public because consent is required on an overall scale and individual to include people.

So what if the masses consent overall, would the people who choose to remain be at risk? Would Tribal and Native village life and people who respect the Earth be protected or permitted to stay?

Psychological Testing

These scenarios can also be generated to create specific situations that will contain tests or elements of temptation that will probe the person's psyche for weakness.

Hallucinatory Holographic Mind Probing Technology

Through the neural-interface technology the minds of many individuals can sync together to experience the same virtual simulation. Thus a single individual's mind can be selected for input and the environment will be a construct of their mental activity. The others present will be able to interact with and explore that environment like the person's mind.

Various training scenarios were utilized to enhance the resistance (or lack which) of the mind to intrusion and subversion. These were harsh but allowed the individual to completely control the energy flow in the conscious mind while remaining in harmony with the subconscious.

In a strange yet perfectly reasonable way, the conscious mind acts as the central "self" in that environment, while the subconscious mind becomes the "background" elements of objects and settings, actors and intentions within the flow of the "scene" itself. So a kind of movie begins with drawn out characteristics and perceptions that match that of a highly cinematic movie or intense dream.

The brain is naturally naive to stimulation and if allowed will liken the event to a dream in which the suspense of attention or lack of lucid self-awareness is "acceptable".

The truth may be worse than what you're thinking as far as training simulators and mind hacking devices. The truth may be that the human mind is inherently lucid and self-aware and that it is external influences that cloud the mind into what we consider 'regular' dreaming and 'regular' waking life. It may be that the conscious mind has a much greater access to information through the subconscious mind which is largely covered up and ignored in a rigidly physical and ego-focused society. As well, it may be that dreams are meant to become lucid and that we are often the subject of mystery in other realms that often refer to humans as ‘sleepwalkers’ that don’t know their dreams are real.

Virtual Simulator Training Scenarios

These scenarios can be entirely holographically generated to produce a visceral 3.5 dimensional experience which can be used for training or psychological testing.

Combat Simulators

The name is self-explanatory enough. Situations can be generated which are indistinguishable from the real events. The entire neuronal map of the brain (connectome) can be created and this is by machines to mimic the brain. After calibration through sensory feedback experiences, the sensation of the simulated realm is 100% the same as the neuronal impulses that are detected by the physical brain. An adept souled being can always tell there is a slight difference, but once the machines are calibrated the physical sensation is generally the same while in the machine.

These environments and scenarios can mimic any combat situation to determine accuracy, integrity, endurance, skill, and all areas of aptitude of an operative without the risk of injury or the lack of real-time effect.

Conditioning

As was explained in other sections, these same systems can be used to remove fear of certain scenarios. They can be used for programming the mind. They can be used to train one to complete a task over and over until they can recreate that action extremely quickly in real-time. These devices can be accelerated to operate within a fraction of the time yet to cover training and conditioning that would normally take place over hours, days, weeks, to months.

Programming and Resistance to Psychological Trauma

Through the development of specifically customized scenarios and neural feedback systems trauma can be brought to the surface or specific fears and traumas can be neutralized. This is essentially “facing fear” but in a completely generated environment that will be just as real as the real thing. One can literally face any fear, any trauma, any kind of difficulty and these systems can be utilized to accelerate a process that would normally take weeks to months or years and individuals can be strengthened to their maximal capabilities.

Accelerated Mental Functioning

Some of the technological systems were designed to test the enhanced functioning of an accelerated brain.

The mind can be seen as the energetic component of the physical brain. The physical brain projects consciousness via the electro-chemical processes.

Technology, Accelerated Learning and Repair

Technology has been developed for assisted learning and accelerated repair of tissues.

On Orgone Energy

Orgone devices produce a scattered signal which disrupts the ‘negative’ energy fields. At least this is what I’ve been told.

Apparently if built correctly it will either disrupt the negative emf/harmonics or it will produce positive harmonics, IE: Orgone energy. Orgone energy is the raw energy of life, while dead orgone, DOR, is the lack of orgone energy and can be “found” (the lack of orgone) in thunder storms and illness or depression.

This is exactly what I was told. We are generators for the same energy, and with the correct principles of energy and internal knowledge combined we can produce those very effects at will.

The energy of the mind creates a central vortex within the body. When the frequency pattern emission is consistent with fractal congruence, then that holographic printing of energy can be expanded or shrunk infinitesimally and it will retain the original fractal configuration.

This is what enables transference of awareness between fundamental harmonic layers of the Universe. When one’s consciousness energy pattern is balanced and tuned to itself so that all proportions can be shrunk through a vortex and expanded on the other side, then the personality or self-awareness remains true. This is as if the space/time must turn inside out and only when there is fractal relative polarity in time does the ‘shape’ of the consciousness within the DNA, work both ways folding and unfolding to represent the same mirror image. This is also symmetry in time as far as an ability to reverse the perception and still retain some kind of connection forward and backwards.

Energy Generators and Serums

Generators which produce vibrations that influence the cells to heal at an accelerated rate, combined with serums that enable the fuel for chemical reactions can instantaneously repair tissues.

I couldn’t believe what I was seeing at first, thinking it was a trick. There are serums and energy devices that can influence the healing and general health of the body and even mind.

These devices use energies which extend beyond the physical and are often compared to electromagnetic waves combined with ultrasonic or low to mid frequency tones. These produce harmony on a level that directly interacts with the biological functioning of the body’s cells.

I feel that this technology utilizes the same energy that is emitted from the mind and it is as if the device is “speaking” to the cells in the same kind of universal language of electromagnetic pulses, tones and vibrations.

There is information on energy devices and the use of light therapy in physical therapy today. More is being learned about the power of light and vibrations to influence the mind and body.

Genetic and Cybernetic Enhancements

Certain individuals are also genetically and technologically modified to produce a kind of hybrid human that can heal at a spontaneous rate as well as operate at a much higher rate of speed and efficiency than a regular person. Serums to induce muscle growth and mental acuity are applied, but the main condition is the enhancement of certain features through the alteration of the RNA aspect of the genes.

These features are combined with tech-assisted metabolism and certain biological functions can be enhanced or controlled via a supercomputer. These are the ‘brain-chip’ interfaces which operate to function as a governor for the mind. When the mind becomes too amped up to focus on the details the faster than thought computer system organizes the input into more usable information streams. When the mind is too slow to see the necessary patterns and variables to accomplish the goal, the brainchip operates in a self-preservation fashion and links together information streams to highlight the most viable possibilities.

Such technology is not without warning, much of this is being used heavily in the military field and this has given rise to entire factions of enhanced cybernetic soldiers. Although this is something to know, there are also many other uses for this technology and it is used by people who want to explore the technologically assisted path.

There are many other aspects of this to discuss, or at least a few important ones that will have to be understood to know the greater truth about what is happening on the planet.

Developing The Self

The issues we face are to help us learn about our selves and better mediate the known and unknown aspects of personality. The more we focus on realizing the unknown aspects of personality the less we are seemingly controlled and forced to experience the undesirable aspects of existence. The more we cling to just what we know and what we feel comfortable with the more shocked we are when we inevitably discover the truth of the whole of our existence which is *always* at least one half more than just what we know and are comfortable with. That is the nature of the universe, we can only achieve one half of the equation at any given moment. Once we complete that seemingly whole view of the universe, the information we gain access to instantly doubles and we realize that we were only looking at one portion at a time, just one half of the equation. Then the rest of the equation comes into the picture and we must expand our view once again. This is because we are viewing ourselves as we discover the universe because we are creating what there is to be discovered through the act of exploration in itself. We are the explorer, the explored, the creation and the discovery simultaneously.

Multiple Factions of Space-Fleets, Multiple Goals

Now there are what are called ‘factions’ of groups that have different agendas and interact with the public or surface level population differently. That is one of the main issues. These departments and factions are no longer limited to the surface level of existence and have access advanced technological capacity and knowledge of a larger view of time and a more complete understanding of consciousness and the human existence.

Large-Scale Catastrophes or Series of Meltdowns

I was informed that while they work continuously to prevent and reposition this civilization continually outside of the reach of any large scale meltdowns that the technology is commonly accepted to only be a temporary barrier between the inevitable.

Unsustainable

This society is unsustainable and must either change or will experience the massive catastrophic evens that are foreseen.

There are multiple perspectives that are maintained. They vary by the way of the methodology of solving the problem. All agree that change must occur and is impossible

to postpone forever. The future society is the result of our advancements and achievements. Regardless of how we get there, we must get their somehow.

Earth Changes

I was informed that these changes had been held off and would ultimately be allowed to take place to resolve the current situation. The changes can only be held off for so long, either that or the people performing this task would not be reasonably inclined to postpone these changes indefinitely.

The idea is to locate and secure the members of society who are fearless and capable of assisting in this transition and who hold key genetic elements as these individuals and groups are capable of ‘holding-space’ for the rest of civilization by literally containing the genetic precursors for all those other individuals.

I was informed that Earth changes would be the last event to take place, pretty much like icing on the cake.

This means there will be a lead up to these events.

Mass Consciousness

I was informed that the consciousness of humanity and every species is linked to the bio-etheric field of Earth. When the consciousness becomes too unstable to maintain a controlled society that this will initiate massive Earth changes. This could simply be instigated through advanced technology but I was informed that the advanced technology is actually postponing this so as to allow people to prepare, to get the word out and avoid a complete loss of the human race.

Wars and Manipulation

Wars were described as a way the power groups had controlled humanity over long periods of time. These wars were used to distract and weaken the population and the power groups believed they were holding off a full scale invasion by suppressing the rising population.

Now the population is high enough that another war would be a final war and this is extremely dangerous for the entire civilization. There would be no need for another war to repeat this cycle because the technological achievements have been met and so essentially the ‘reseting’ of the civilization would not be required or possibly acceptable.

This is why war is to be avoided however people are very easy to manipulate through lower emotional and mental programming from media and social cues. People follow the herd and the herd is essentially still operating on animalistic parameters. There is a have coating of peace and humility but this is just a wax coating that quickly evaporates as soon as the pressure of mass unrest or scarcity is realized. Many simulators have explored these possibilities.

Financial Unrest (or reset)

The idea is that financial oppression is used before wars to distract and oppress the population. When people are busy looking for resources to survive, they are not focused on the larger picture. This is part of the ‘fight or flight’ response mechanism tied to lower brain complexes which are primarily activated to keep the masses in both a highly sensitive and unstable state of being while also keeping them easy to control.

If the civil unrest reaches a level where awareness continues to rise even though financial hardship is being implemented then the latter two options will not work. At that point artificial disasters can be produced as well as natural Earth changes which initiate a shift of the ages and of consciousness.

The paradox or maybe irony here is that the oppressive actions are used to both suppress human awareness up to a certain point and simultaneously to stimulate and arouse the human spirit into wakefulness and self-empowerment. This is part of the reasoning regarding why these control systems are allowed.

Some say the elite don't want an economic collapse. That it would ruin everything. Others say it would be icing on the cake. Some say that it is a zero-point world that will save us. That the Fukushima is a big problem. Zero-point field tech, that is. Generators and energy sources, healing and terraforming. I know we project right? We see it in our own lives. So we can project with each other and grow that as a group and that part of the world will exist in that light. Which sounds Biblical, which may be because they're following prophecy. But it may also mean that we have a light, a chance, a real salvation, but that we have to grow that here and help develop it. To pass it on like love and such.

That's apparently what it comes down to. That these cycles happen every so often and we're in the midst of one right now.

Let's make it count. Every day, thought moment. With mindfulness, intention and awareness in action. Life is literally higher dimensional, so we have to become multidimensional to really face it. Indeed, that is a good perspective on action and inner being. It's like a fractal, whatever we project inside that chest center, will project into our mind and the outside. But we have to be stabilized and grounded through the root first and then to get to the heart energy must pass through the sacral/sexual centers and continue upward.

Self-Responsibility

The main reasoning is self-responsibility. We are responsible for ourselves. The people are and so if they allow themselves to be tricked and prodded like animals while behaving for the part, then that is how their experience will play out.

Clones and Synthetics

One seemingly unfair aspect of this is that there is a larger portion of non-humans than there are humans and so these beings without the human spirit will be easily programmed to support and propagate the mind-control system and the oppression. Thus, if people follow the herd mentality then they will walk directly into the end-time scenarios yet it is the humans who will actually stand to lose. People must wake up to these tricks and this technology so that they can orient themselves with the reality of this situation while learning to strengthen themselves and adapt to the manipulative aspects of this control system.

Spiritual Power and Divine Truth

This is essentially all about spiritual power and humanity stepping into the power of the truth behind their existence.

Some say that humans are designed as slaves, but if this is so, then it is the power that humans contain within that is the ‘work’ that they are sought after for. This indicates that humans have great powers that others cannot achieve on their own, even if they are creator lords.

Thus, whether humans are modified or not, they have great power. If they are not modified to perform this role of an energy generator, then this is just a confusing mind-control game that has been pulled over the eyes of humanity and humans have always contained true internal spiritual power that allows them to exist without having to parasite and steal the energy and knowledge of others. Humans are reality generators , we can choose how we want to experience the universe and what kind of collective world we want to enjoy together. Once we step into this power, there is on greater force. No amount of non-human entities can change that as we are somehow intrinsically linked to the ether-space of this realm through the spiritual and physical aspects of our being. That is what is sought after and so those who do not have this manifestation power attempt to utilize humans to create their own reality through this Earth situation. That is the basics of the ‘alien overlord’ system, whether humans in disguise, non-humans operating with alien intelligences, supercomputer systems, or spiritually degraded beings.

Most people are not ready to see themselves or the true nature of humanity. Reality is largely an illusion of the conscious mind. The hidden aspects are the other half of the equation and this is perceived by the shadow aspect of the personality and mind. We are only marginally aware unless that aspect has been unveiled and through this process the reality of the human soul can be actualized and realized.

I was informed there would be a period of two suns and multiple mirages around the world. People would believe they were peering into another dimension, floating cities, or some kind of city-ship craft.

Synthetic DNA, Synthetic Genetics

Through the previous described replicator devices synthetic DNA can be engineered. Thus, entire genetically engineered codons can be produced and form this created beings can arise. These are the hybrid beings that are performing many tasks underground and even on the surface. On the surface there are synthetic genetic create beings or genetically engineered beings that appear to be human but do not contain a human genome. There are also clones and replicants of humans. There are a variety of non-humanoid forms but these are largely kept underground. These are beings we often see in science fiction movies or shows.

Time as Mathematics, Series of Equations, a Programmable Storyline

When using the technology, time can be understood to be a series of programmable variables where one variable is centered within a series of parameters and from these possible variables within a parameter set a series of possible functions or outcomes can be process. Thus, these people can literally plug into a supercomputer system which operates based on this form of processing reality and through this they can observe all the possible realities that may connect to a present moment. This allows one to travel but this is not part of this section of the explanation.

What this allows one to do is know exactly what is going to happen and when. If a person is being interrogated, all that has to be done is the operative using the technology simply thinks of what they will say and intends to do it within 6 seconds. The machine will play out a future timescale regarding the input of that question or interrogative speech and then produce the possible results. If this doesn’t give the desired readout in the mind of the operative, they will refuse to go that route and think of another pathway. This repeats for a few seconds to a few minutes. Then the computer has found the pathway that is most like to yield a result. The operative simply steps forward, says ten words, the subject breaks immediately and tells them everything they want to know. This is obviously takes longer for most trained individuals, however that is how easily it would be to use this technology to produce an effect on a regular surface level human. They would have no defense, no way of knowing how that individual could know so much or be so direct. This is how operatives dealing with certain power groups will operate in the surface level population and individuals always feel that these people know way more than they are leading on. That is because they are, they know more about you and your life experience than you do.

Chapter 2.3 Previewing Solutions

Neutralizing Polarization

The mental-emotional tendency to pick sides, to fight, or to basically join in the fray that is currently taking place is a kind of deception of polarization which enables the leeching of emotional and mental energy from the human. This is more of a psychological unveiling where the true nature of the self, the duality game and the transcendent source aspects can be made visible to the individual. The they will see how every polarization tactic is actually taking them out of their true source of power by pushing them off center emotionally and mentally. There are teams that are capable of enabling this process and assisting as humanity realizes that half of the problem is that the unchecked mind is one’s own worst enemy.

Removing Etheric Implants

Technology can identify and isolate these foreign body implants which are etheric technological devices. These are literally frequency or phase-shifted devices which are invisible to this layer of physicality but are capable of being organized and attached to the etheric field of the human and will operate to siphon or limit energy on the etheric level. Of course, this is all technology of the vampiric created beings who parasite on the original Earth inhabitants to sustain their existence.

Clearing Astral Body

By moving through the temporal body etheric implants can be deactivated and removed and then the astral or emotional body will be able to function closer to the original levels of presence and sensitivity. This body is manipulated when one is emotionally shut down from trauma. Thus this body can be scarred and will function at a much lesser level of activity or presence until the emotional damage is healed. This contains the memories of all the emotional events of a person’s life.

There is technology that enables one to access these levels of frequency and clarify or untangle emotional chords or attachments which are used to siphon energy from the human being to the parasitic created beings. These chords are energetic in nature but also have technological components.

Knowing the True Self; Soul Actualization, Unveiling

This is a sacred, ancient process that has been outlined and discussed since the beginning of time. Humanity is here to learn, grow and express the self. In doing so, like a child moving through layers of infancy and into full-wakefulness of their body and the physical world, humanity can come into awareness of their true spiritual nature and the true spiritual nature of the universe. This is the process of soul or self-actualization that is described in some psychological methods such as Maslow's hierarchy of needs and the self-actualization that results in a complete fulfillment of all psychological needs. In this modern psychological view, self-actualization is described as the desire and process of reaching fulfillment of one's own natures and then living their life sharing that self-empowerment with other beings because after gaining your self that is the highest expression of such knowledge, sharing that power with others.

The true self is not limited to the physical body, the true self is a reflection of the entire universe and thus the primary original creative force. This is akin to the whole equation rather than just half of the equation. The visible aspect of the self, the conscious mind, is only one half of the entire equation. The whole equation consists of what we see visibly and consciously as well as what we are limited from seeing within the unconscious and subconscious mind. These are really two layers of the same ultimate source. Like an iceberg which is only partially above water, the subconscious mind is the proprietary wholeness of experience. The conscious mind is only a surface layer of reality while the unconscious mind carries all the notions, the multidimensional processes, the latent aspects of reality that we are not capable of seeing without unveiling these aspects through inner exploration.

Taking Responsibility

This entire show is about taking self-responsibility. Unless people begin to do this, there will be no hope. Right now people are convinced that their responsibilities belong to someone else even though this always results in pain and discomfort. To take responsibility is painful at first because we have a lot of work to do, but even then, this is beneficial because there is no way to remedy the pain and discomfort of being lied to and disrespected if people continue to hand their free-will over to others through blame (scapegoating), lower emotional bio-emissions (hatred, anger, etc), distractions and addictions (technological, sensual, and chemical or food based), or generally complaining without taking the first step towards providing something beneficial. This is the victim role, if humanity is to take control then they to help each other and themselves by not relying on false promises and false authorities to determine how they feel, think and live.

Returning To Center Emotionally and Mentally (spiritually)

Balanced food intake, rest, exercise, activity and learning are all continual requirements for a healthy existence. Emotional and creative expression nurtures the soul. Without these ways of being and learning the human qualities of experience diminish and creativity dwindles. There is most likely going to be a split between those who can sustain their own humanity and those who have to cause others to suffer to do so.

Vampires in the “Awake” Community

Contrary to popular belief, the majority of the non-humans are not necessarily vampiric and in power. The vampires are the people online who try to get a rise out of others for sharing their own experiences. They are the nosy neighbor that feels that the person who looks or acts differently must be considered and enemy and armed against because they feel themselves to be so much better. The majority of people are vampires, they believe that they must work for someone who will trade them money and that the amount of money they have based upon the amount of indirectly beneficial work they do puts them above others.

This is not different in the ‘awake’ community and in fact I feel that there are higher concentrations of vampires in this community, the alternate media because everything is largely a joke and a trick. People are operating on deceptive agenda schemes to divide the people and this is most intensely noticed when there is a realization of the truth behind what is happening and people begin to point fingers. The only people who are cleared to point fingers (and who also will NEVER point any fingers) are the operatives from the secret projects that have the capacity to do so because they have reached a specific level of awakening and this is related to the droning, cloning, and hybridization process. Only a specific few know who has been transformed into an impostor being and who is remaining strong and this is due being briefed on the surface level situation. Anyone can say what they want, they are simply playing into the tactics of mind-controllers and parasites and the more they play in the deeper the infection will grow. All the people pointing fingers now are actually implanted and vampiric and are attempting to drive a divide through humanity and they are the first who will turn on their friends and family when the going gets tough because they are more interested in others and starting drama than healing themselves. Ironically, this is all done under the guise of “healing” and “getting rid of the drama” AKA people they don’t trust. They pick and choose based on their own personal bias and this is a sure indication that they are emotionally and mentally out of alignment and are feeding deep seated personal fears from their own traumatic experiences.

These traumas must be healed and the harmonious center must be reattained where a person can focus on their own existence and waking up instead of acting as false-light, “king of tyranny” gatekeepers for others. Those individuals are going to be left behind if they cannot kick the habit because if they are allowed into any kind of healed society they will quickly degrade into animals and attempt to restart a devolution process in order to gain the power they so desire but cannot produce on their own. ANYONE playing ego games of trying to hurt or put blame on ANYONE else contains this viral implant and has not kicked the virus.

Heart Center and Psycho-Spiritual Fulfillment (self-actualization)

Emotional connectivity is a form of telepathy, when loved ones can tell the state of another across space and time. Whether it is family or friend. In the 60's and a little before that the US found a specific frequency akin to a radio frequency that operates on a trinary spectrum. They called this the "telepathic wave". In time, they could completely read and send thought waves without frying the brain or body through radiation. Which was what the early machines did. They actually took satellite dishes and aimed them at people. Then realized they could turn it around and do it backwards with a better effect and minimal radiation. Either way they started beaming the base and then towns around them with waves between 400 and 432 MHz and caused waves of crime sprees or peace sprees throughout the 70's and 80's. So they can digitize the telepathic wave to induce artificial telepathy. But this is organically done through an entanglement through what we call love. Literally. The Germans found it before that. And the secret orders before them. And ancient Egypt before them. As humans we remain basically through the root, heart mind connection. When the heart overpowers the mind connection of spirit, then the body is a trinary whole. When the mind guides it is binary and cannot by guided by the spirit. The spirit has direct access to the heart. The mind is a computer of sorts. The mind doesn't see past duality. The heart is the true center/eye of the spirit. The reptilian brain is the dragon and when you tame the amygdala then fear is ‘behind’ you. When the mind is "untamed" the reptilian brain takes over. This is the lower brain and amygdala fight or flight response.

This happens when the energy of the brain, body and spirit increases due to whatever various reason of spontaneous or controlled increase. Because of the "temptations" which are the easiest flow of emotional energy into a "discharge" state, is that the sacral/sexual center ties to the heart and reroutes to replace the heart and control the mind. Mental and emotional contemplation of one's true purpose and nature is the path of the divine. We find ourselves simply by looking in the right place, not in the world, but in our self energetically. We are more powerful than the programming, and we can reverse this is we're careful and devoted enough.

We have to be faster than thought, at the speed of spirit, beyond matter. When we start thinking on this level then our influences spread to others throughout the sphere. It is our destiny to know these things but they have been kept from us. The ancient orders called this the art of "implosion". Traveling realities through intense contemplation and a usage of sacred geometrical forms.

They developed and combined orders around WW2 and developed zero-point energy tech that can alter space/time fields. This is timeline manipulation. But as a rule, we go where our heart leads us. So that's how this is solved.

Go Within to Observer the Self

The answer is literally by looking within to find the great truth rather than looking around us. Everything we need to know is within us, energetically and spiritually. Our emotional, mental and physical state of balance is an indication of where and how we exist in relation to the larger overall truth. Everything that happens around us to distract us is designed to stop us from looking within. Nothing can truly stop us, nothing can actually input the holographic horrors in our spiritual center but simply perturb the brain and body. The mind is a non-holographic spiritual environment that cannot be excessed and the invader's goal is to convince people to use their imagination or their creative powers to produce these horrors on their own. This is through the programming. We must clear out the programming, the trauma, the lower-dimensional constructs and fill ourselves with the truth and spiritual presence that enables us to be self-aware in the first place. If we aren't doing this, then we are either in pain, or there is no spiritual presence to be in pain. If we are doing this, we are either clearing out the constructs by replacing them with true spiritual presence and self-awareness or we are becoming aware of them.

Organic Feedback Loop

The great feat is mentally bridging the great rift between us by looking within. Which is paradoxical.

We can never see what another is perceiving exactly, well for the most part, so we all have to kind of accept that we are communicating effectively and truly get to this level of comfort by simply being secure in knowing who we are our selves.

Technological Feedback Loop

So then knowledge, in a way, when shared, is a form of telepathy. Group telepathy.

Group think, when ideas or memes spread, is a form of group telepathy.

The Internet is like artificial spreading of telepathy. This means what is normally mentally bound signals can be initiated and spread through a digital medium.

Breaking Soul-Contracts

Ultimately everyone is under a series of "veils" which are energetic time-constraints literally like 9 dimensional layers of temporal restriction which are each bounded and ruled over by invader beings. These range from physical authorities, to astral entities, to programmable matter, to supercomputer intelligences, to spiritual false-light beings and our own shadow mind. Each layer of reality is successively guarded by these beings who are here acting as gatekeepers designed to push people back when they begin to wake up. These beings all work through fear and deception and the last layer is based on mirroring our own energies back to us like an impostor. All the levels tend to imitate, however the last layer is a near perfect imitation of our own energy to the point where people often switch places with this being before getting out of the matrix. There will be more discussed on this in a later section.

The “9 veils” were designed by impostor beings as a last effort to stop humans from escaping the false-light matrix which is essentially the holographic universe. This is literally like a maze which reproduces a new pathway and a new doorway each time a person nears the last hallway or doorway that is next to the exit. So one eventually has to project themselves into the exit using their whole being and moving past and through the tricks by not falling for them before they are placed. This is highly confusing but this is essentially a kind of labyrinth that has been created to stop people from leaving so that their soul energy can be destroyed and used as a generator for the false-light system which is an AI over mind that is programmed to take the raw soul energy and destroy the identity by inverting the electromagnetic spectrum and incorporating that inverted energy into its own internal matrix body which is literally the false-light universe.

Help Everyone

Now they may have been setting us all up for the apocalypse. They said they want us to tell on them and get the whole world aware of what they've been doing So that we can stop them and pull them from the dark which is ACTUALLY taking their souls. There are also breakaway civilizations involved in this entirely zero-point/free-energy.

Chapter 2.4 How Timelines Collapse

Repeating Cycles of Time

Because of the way time works and the ability of those using these temporal devices they have set up an elaborate labyrinth like a spider web of false realities, timelines, parallels, sub-dimensional layers, astral cages, temporal dead-ends, and time loops which act to stop people from reaching the true reality. As a result, many portions of this timeline are literally in a free-will ‘time-loop’ and these loops must be canceled out. As well, because of the nature of these loops on the overall stream, our entire civilization has been looping for the past 6 time-cycles meaning we have reached this time in history 6 times before and this is apparently the last time because we have never gotten this far before and the events of the future are having to be programmed in manually at this point.

Beings From the Future

As are result and damaging time, what happens is that the beings from the possible future that is being damaged appear to try to heal the break as well as those who are from the new possible future that is generated, this results in a time war between both possible realities for the present realm. This is what has been happening for thousands of years. All the ancient spiritual texts are describing this system. One group is a from an original possible future where everything is based on the presence of spirit and souled humans, another is from the new possible future where an AI overlord took over and removed the souls and spiritual energy from all entities on Earth rendering this a holographic prison without any other use. That reality dissolves into itself and so the time beings are constantly moving backwards and jumping timelines to try and obtain more energy.

Beings From Collapsed Timelines

The beings from the collapsed timelines are those who travel through hyperspace to get here. They then recreate themselves using cloning technology through hyperspacial means, IE: creating an alternate temporal dimension so that these devices can sustain them and literally “hold-space” for them. Then if their timeline is destroyed, they can still exist as a ‘loose-end’ in space-time. This is extremely dangerous and I will say we have some Human operatives jumping timelines searching for Earth and Humanity so that they can find a reprieve from this time war.

That is the most trying aspect of this entire ordeal for me. There are some human operatives literally in hyperspace without an opening into the temporal stream for them to reintegrate into this timeline. We must assist them, we must open the timeline by taking control of Earth from the invader races and those who wish to depress and isolate the spirited and souled human beings. We must re-organized and neutralize the invasion forces of deception and assist our humanity and maintaining their free-will, their self-awareness, their self-empowerment and their emotional, mental, and physical harmony.

Beings Who Would Never Have Existed in the First Place

As a result of this entire process, there are essentially beings who have been erased from time who degrade in this dimension and can only interact periodically. These are the created beings who operate through supercomputer forms that are placed within cloned bodies and powered by the transdimensional quantum supercomputers. These are the ‘parallel’ reality beings and this relates to the hive mind invasion. When all the original aspects of time are restored, these beings would not have ever existed in the first place as there is no quantum link for their probabilities to remain neutral and present in the original run of things.

Again, all beings who operate under the will of the universe, even when they are attempting to trick hyperspace and time, when these beings assist and help in the unification of sentient, spirited, souled beings they are capable of being healed. This is all because there is an original creative force which can produce souls that are eternal and everlasting, meaning they are not created but simply always ever were. Yet, there is a “miracle” effect where beings can be given eternal life. This is only by reflecting the will of the whole of existence, rather than a portion or a part because this is only temporary. Only the whole is forever and this takes true harmony, true balance and ultimately *self-lessness*. To give to others because you see them as worthy because they can be aware and enjoy the gift is to be like the creative force that gives life to all and enables all experience in the first place. By acting in correspondence with this we reflect the will of the whole and that power and action transfers into protection and self-empowerment for ourselves. This cannot be cheated, tricked, or rerouted as that is the karma game that has been played by delaying time and rerouting energy through getting others to take on the responsibility for others bad actions. In the end, all karma has only been delayed because when the stops are pulled out, *everyone* ends up getting their karmic returns regardless. They simply intended to build up so much karma that by the time the ties are cut, the karma overload will simply kill them instantly. This never happens and they end up in the abyss, this is the final time so since there is no recycling of the universe from the oroboros system then whatever happens is what happens forever. If everyone wants to move into harmony, to receive healing, to receive forgiveness then they must assist in the creative force in healing, forgiving, and turning away from the deception, the cruelty, the vampiric actions.

Many vampires believe they will die if they stop. The only hope is to admit their ways to the others and ensure that there are enough beings around them that will protect them so that this situation can be handled properly, with due care, compassion, and the necessary healing to ensure the safety and protection of all who seek harmony.


your future
is
in your hands

TIME TRAVEL PHYSICS

By Steven L. Gibbs

DEDICATION

© 1989 By: Steven L. Gibbs
Rt 1. Box 76, Clearwater
Nebraska USA
Illustrations Thanks To
Al Fry Distributor....



I would like to personally thank
Jesus Christ in helping me to obtain
the knowledge for writing this report.
For without his help, all of this
would not have become a reality.



INTRODUCTION

The reason for writing this report is to show people that man does not have to use sophisticated mathematics in order to understand how Time Travel can be achieved. To assume that what is being taught in today's schools is an absolute truth, can only be a lie. For to believe in such a lie, can only lead to imperfection. But sense mankind has chosen this path, the inevitable must surely come to pass.

It is impossible to say where all of this might lead. However I do hope that the people who read this report will use the knowledge wisely. For those who don't, I leave them to their doom. But for those who do, may the Lord bless you.

Your probably wondering by now, if I am really an Alien. My answer to this is, there may be more truth to this than meets the eyes. According to the information which I have received from the Kennedy Space Center, there is a good chance that my parents came from the Star System called Phoenix. If this is case, then this would explain why I have had so much difficulty in adjusting to Earth's own environment.

Perhaps in the years to come, more will be revealed to me on the true nature of my whereabouts. And you know what they say about Aliens? Their weird!

TIME TRAVEL PHYSICS

Before I begin I must first point out, that the only reason why Formulas can be used for analyzing a specific problem, is due to the fact that a Formula helps in focusing the Belief Fields which emanate from the persons Soul. So in other words, whenever a person uses a Formula or Equation, to him this constitutes a reality. By keeping these things in mind, you shouldn't have any problem in understanding what has been written in this report.

To begin with, there are basically 3 sets of Equations which can be used for accomplishing Physical or out of the body Time Travel. I have used these formulas quite often when building my Time Travel Machines. As a matter of fact, all my research is based on these 3 formulas. The formulas which I have used for accomplishing Physical or out of the body Time Travel, are given in the following manner:

(THE GRAVITON FORMULAS)

$(X , Y = 0)$ $(X1 , Y1 = 0)$ $(X2 , Y2 = 0)$

The Graviton Formulas which I have so diligently labeled, can be used for an infinite number of things. However, before we can proceed any further, we must first have a good understanding of what each Symbol means. There are an infinite number of meanings which can be applied to each Symbol, however in order to simplify things, the meanings which I have given to each Letter or Symbol, are listed in such a way so that anybody with a little bit of knowledge can understand them.

(INTERPRETATION FOR EACH OF THE GRAVITON SYMBOLS)

X - Represents an AC Field.
Y - Represents a DC Field.
X1 - Represents a High Frequency Field.
Y1 - Represents a Low Frequency Field.
X2 - Represents a Paramagnetic Field.
Y2 - Represents a Diamagnetic Field.
Ø - Represents the Zero Vector or Twilight Zone.
it may also be referred to as the (PHI Value)
which is (1.618).

It is interesting to note, that whenever the (PHI Value) is used in the construction of a material object, a Time Warp usually occurs around that object.

However, in getting back to the problem at hand, whenever the (Graviton Formulas) are used singly or in series with one another, they can be used to help build a device which can actually be used for Time Travel. This is because whenever the (X) and (Y) Values are combined with one another, we can Zero in on the Twilight Zone. And sense the Twilight Zone is in attunement with God, all things become infinitely possible provided that the (X) and (Y) Values are in resonance.

So now your probably wondering, how can we use these Formulas for constructing a Time Travel Machine? Its simple. Merely start out by building a Capacitor which corresponds to this Equation: (X2 , Y2 = 0). This Capacitor should be constructed in such a way, so that it resembles the drawing which is shown below:

(DRAWING OF CAPACITOR)



As we can see in the above illustration, it doesn't matter to much as to what size it should be, just so long as it is shaped like a Hexagon. Also each side of the Capacitor should be the same length, otherwise the Belief which is being transmitted from the plate, will be imperfect. And this could raise Hell with your Chakra Points.

At this point it should be noted, that whenever you construct a Capacitor of any type, you are automatically using the formula (X2 , Y2 = 0). And sense the (PHI Value) is used in the formula, the plate itself will develop a Life Force of its own. It should also be pointed out, that sense there is a Life Force which co-exists with the plate, it can now be programmed to do anything you want.

Now in order to program this Capacitor, all we do is stroke the Glass portion of the plate, while concentrating on the following command: (Transport me to the Date and Year). As soon as you get a stick so that you can no longer move your fingers, the Capacitor should be fully programmed. After you have finished programming the Capacitor, place the Screen Side of the plate over the Solar Plexus for the space of 30 minutes. After the treatment is over with, you then find a comfortable place to relax in order for the energies to take effect. If you have done everything correctly, your Aura or Physical Body should be transported to the date which you programmed into the Capacitor. On the average, it usually takes 70 minutes before the energies will take effect.

*Note: People who work with these plates are in serious danger of getting possessed by an Evil Spirit or Demon, unless of course you have a faith in Jesus Christ. By saying a prayer to Jesus Christ prior to any Experiment, more than protects you from the forces of Evil.

As you Experiment with these Capacitors, you will find that some of these plates work better than others. The reason for this probably ly's in the fact, that certain sizes or the materials being used, are in resonance with the person's Life Force or Belief Fields. Therefore if you run into any problems, it may pay to use a different thickness of Glass. When I talk about this, I do not mean to vary the Shape of the Capacitor, just the width. It also might pay to use Yellow tinted glass. You may also want to try Green, Blue, Indigo, and Violet colored glass. The reason for doing this is simple. Each color corresponds to a different Chakra Point. It is therefore my opinion that Yellow should be your first selection, then if you want, you can always Experiment with the higher colors.

*Note: Never under any circumstances use Red or Orange tinted glass. If you decide to use these colors, then your probably on your own, because not only will it lower the Frequency Rate of your Chakra Points, but you could also end up in an Astral Hell. And believe me, this is no fun place to visit.

Once you have found a plate which can transport your Physical or Spirit Body, there are still even further ways of increasing its effects. One of these ways is by using the second formula, $(X1 , Y1 = 0)$. This formula states, that whenever a High Frequency Field is combined with a Low Frequency Field, we can tune ourselves into the Zero Vector or Twilight Zone. To use this formula it will first be necessary to get a hold of a

Tesla Coil and one Van de Graff Electrostatic Generator. Once these items have been obtained, you proceed by charging the plate with High Frequency Electricity and Low Frequency Static Electricity. In other words, after you have programmed the plate using the procedure on page (4), you must simultaneously Zap the plate using the above procedure. You must make sure that while you are doing this, that you do not come into contact with the plate. If you do, you could be in for a Hair raising experience. This voltage hurts! But anyhow after you have Zapped the plate for the space of 10 minutes, you then proceed by placing the Capacitor over the Solar Plexus as described on page (4). The effects that you get, should be much better than what you experienced before.

The next step to take, is to Amplify the Energies even further. To do this, we must now make use of the 3rd and final formula, which is (X , Y = 0). This formula states, that whenever an AC Field is combined with a DC Field, a Time Warp occurs which tunes our minds into the Zero Vector or Twilight Zone. Now in order to create these fields, one should try to get a hold of a Hyper-dimensional Resonator. (Read the last 4 pages in this Report). Once you are able to get a hold of this instrument, and after everything has been plugged in correctly, while the Screen side of the plate is positioned over the Solar Plexus, position the open end of the Electromagnet over the glass side of the plate for the space of 3 minutes. After the treatment is over with, disconnect yourself from the plate (turn page) and instrument, and find yourself a comfortable place to relax. If you use this procedure in conjunction with the first two procedures, the effects that you obtain, will be increased to such a point, that you should be able to do anything you want. You must remember however, that before Physical and Spiritual Time Travel can be achieved, the (X) and (Y) factors in the formulas must be in resonance with one another. This can only be accomplished through the process of tuning your own mind just as you would with a Radionics Machine. So in other words, by selecting the correct materials to use, you are in effect creating something which you physically believe to be a reality. This same rule can be applied when working with different types of Frequency's and Voltages.

Another method which you may want to try, is that after you have programmed the plate by using the procedure which is given on page (4), transmit some High Frequency Electricity from a Tesla Coil into the Capacitor while the Screen side of the plate is pointing towards your face. After 3 or 4 minutes, de-activate the Tesla Coil, and while the Screen side of the plate is still facing towards you, take the bare ends of an Extension Cord that has been plugged into a 110 volt AC outlet, and short out the bare ends of the wires by touching both of the terminals on each side of the Screen. (See page 8). If you have programmed the plate correctly, your physical body should be transported instantaneously to the date which was programmed into the Capacitor.

THE CHRONOLOGICAL TIME REFLECTOR

(Series No.2)

2-21-89


High Frequency AC Electricity
50,000 volt
Tesla Coil
Steel Wire
Bare Ends of the Extension Cord are shorted out by connecting the open ends of the wires to each side of the plate.
Extension Cord is connected to a 110 volt AC outlet.
110 volt
AC outlet
Low Frequency AC Electricity
Extension Cord

To give you some idea of how all this got started. Back in the year 1981 I was contacted by what I believe to be my other self. The letter which I received at the Sunset Plaza in Norfolk, Nebraska, was dated 1992 A.D. It also had a month on it which I can't seem to remember. Evidently the letter which I received indicates, that sometime around the year 1992, I will travel back into the past to make contact with myself, just like my other self did in the future. One of the things which the letter mentioned which I can barely remember, is that it said: (The path to the truth can be found in the Pyramid of Giza). It also had a riddle, and it went like this: (The riddle can be solved when 79.613 is dissolved). These two verses holds to key to Time Travel. I have already deciphered the riddle. As a matter of fact it was just last year when the answers came to me. Basically the 79.613 number can be converted into the (1.618) value which is used in my Equations. It is also the same number which was used in the construction of the Pyramid of Giza. If we decipher the riddle even further, we will find that it also reveals that the 7.8 Hz. Frequency, is the Frequency to use for accomplishing Time Travel. It seems that whenever a person travels physically through time, his Alpha or Theta Waves are vibrating at this Frequency. Once that your Brain Waves begin to oscillate at this Frequency, your mind then becomes tuned to the Zero Vector. I have found that this is the only way in which Time Travel can be achieved. So basically what I am trying to get at, the Chronological Time

Reflector causes your Brain Waves to vibrate at 7.8 Hz. cycles per second. That is all that these units do. However, for some people, they might think differently, but when you get right down to it, it all leads to the same thing. Mind verses matter. And this just barely covers the subject.

Another experience which I had that occurred around the month of Sept. in 1986, dealt with a variation of the Chronological Time Reflector. In other words, after I had finished programming the plate, I proceeded to Zap the plate with 50,000 volts of High Frequency Electricity. Sometime after the Experiment, I clipped off one end of an Extension Cord and plugged the other end into a 110 volt, 60 cycle, AC outlet. I then laid the bare ends of the wires on top of the screen. Just then I accidentally dropped something on the floor. After I had reached down to pick it up, the bare ends of the Extension Cord which I had laid on top of the Screen, touched the Screen portion of the plate. What was to follow, would be the most terrifying experience I had ever had, because as soon as the bare wires touched the Screen, a massive short occurred. All I can remember is seeing two flashes of white light energy, and the next thing I knew, a white mist had fallen over the entire room. I didn't realize that I had traveled physically through time until I looked at a Calendar the next day. Not only that, but when I asked a lady in Plainview, Nebraska as to what the date was, she said it was the 17th, but my Quartz Watch indicated the 16th. When

I had returned home later on that day, I has discovered that all of my Experiments had been dated wrong. Then I finally realized that I had actually traveled one day into the past. To this day I am not exactly sure as to whether or not I returned back to my own present Time Line. Perhaps I will never know.

Another Time Travel instrument which was sent to me by a man who lives in Osceola, PA., is revealed on pages (12), (13), and (14). According to what I have red in his letter, this device can actually transport objects into the future. However, he says that there is somewhat of a Time delay effect shortly after the unit has been shut off. In other words, after the unit has been de-activated, it takes anywhere from 10 to 15 minutes before the object is teleported. I have never built this device as yet, however I plan to eventually.

POWER SUPPLY FOR THE TIME PLATFORM

2-22-89

C1 - Is a homemade Capacitor made out of sheets of Glass and Copper Foil. Aluminum may be used, but this could be dangerous to your health.

L1 - Is number 10 Gage wire wound around a dowel rod.

L2 - Is number 24 Gage Magnet Wire wrapped around some PVC pipe. There should be about 1000 turns which should create around 100,000 volts of Low Amperage High Frequency Electricity.


Neon Sign
Transformer
110 volt
AC outlet
30 KV
C1
Spark Gap
L1
L2

THE TIME PLATFORM

2-22-89



The plate is 12" inchs across.

Electromagnet

This is the shape of the sending plate.



Electromagnetic Coil is placed in the center.

THE ELECTROMAGNETS ARE MADE OF STRAP IRON STACKED 8 INCHES HIGH (1/4"STRAP IRON).

THE ALUMINUM PLATES ARE 1/4 OF AN INCH THICK, AND ARE STACKED 8 INCHS HIGH .

THERE ARE VARIOUS REASONS FOR THIS PARTICULAR ARRAY.

THE ALUMINUM SPACERS CONCENTRATE AND FOCUS THE MAGNETIC FIELDS.

FULL SCALE DRAWING OF THE TIME TRAVEL UNIT

2-23-89


(Neon Transformer)
(Capacitor)
(Vibrator)
Power
Control
Unit
Sending
Plate
+
-
Ground
Frequency
Control
Ground
Rotation
Control

Capacitor is 10 sheets
12" x 16" glass and foil.

THE DELAWARR EXPERIMENT IN TIME TRAVEL (PHASE #1),

8-16-89


Bottom View of Chamber
AL
AL
AL
Six Sided Rotating Chamber
Bottom View of Cones
Mag.
Magnetic Wheel
Individual Stands inside Chamber
Tesla Coils
45° Angle
(Platform)
Frequency Generator
Oscilloscope
Magnetic Wheel
Clockwise Rotation
CO2 Tank
Counter-Clock Wise Rotation
CO2 Tank
150 pounds of pressure per sq. in.
Magnetic Wheel underneath Cones rotate at 25 m.p.h.

Throughout the vast regions of Space Time itself, there are an infinite number of ways to build a Time Travel Machine. One of these ways is to get a hold of a Rubbing Plate, (GSR), or Pendulum, and proceed by asking (Yes) or (No) questions as to what type of components one should use in order to build a Time Travel Machine. There are a number of ways of doing this. First of all begin by asking what size the instrument box should be for holding the components. Next, determine what type of energy one should use for achieving these effects. Then you ask what type of components one should use in order to transmit this energy. If you have done everything correctly, you will end up creating a device which is based entirely on belief. And sense you have created a device which is built entirely on belief, you can be dam certain that it will work! Especially if you use a (GSR) while asking your questions.

For those of you who do not know what a (GSR) is, this is basically a (Galvanic Skin Response Meter). One of these devices may be purchased from me for $150. Instructions are included. Please allow 4 to 6 weeks for delivery.



THE PARADOXES OF TIME TRAVEL

David Lewis

TIME travel, I maintain, is possible. The paradoxes of time travel are oddities, not impossibilities. They prove only this much, which few would have doubted: that a possible world where time travel took place would be a most strange world, different in fundamental ways from the world we think is ours.

I shall be concerned here with the sort of time travel that is recounted in science fiction. Not all science fiction writers are clear-headed, to be sure, and inconsistent time travel stories have often been written. But some writers have thought the problems through with great care, and their stories are perfectly consistent.[1]

If I can defend the consistency of some science fiction stories of time travel, then I suppose parallel defenses might be given of some controversial physical hypotheses, such as the hypothesis that time is circular or the hypothesis that there are particles that travel faster than light. But I shall not explore these parallels here.

What is time travel? Inevitably, it involves a discrepancy between time and time. Any traveler departs and then arrives at his destination; the time elapsed from departure to arrival (positive, or perhaps zero) is the duration of the journey. But if he is a time traveler, the separation in time between departure and arrival does not equal the duration of his journey. He departs; he travels for an hour, let us say; then he arrives. The time he reaches is not the time one hour after his departure. It is later, if he has traveled toward the future; earlier, if he has traveled toward the past. If he has traveled far toward the past, it is earlier even than his departure. How can it be that the same two events, his departure and his arrival, are separated by two unequal amounts of time?

It is tempting to reply that there must be two independent time dimensions; that for time travel to be possible, time must be not a line but a plane.[2] Then a pair of events may have two unequal separations if they are separated more in one of the time dimensions than in the other. The lives of common people occupy straight diagonal lines across the plane of time, sloping at a rate of exactly one hour of time$_1$ per hour of time$_2$. The life of the time traveler occupies a bent path, of varying slope.

On closer inspection, however, this account seems not to give us time travel as we know it from the stories. When the traveler revisits the days of his childhood, will his playmates be there to meet him? No; he has not reached the part of the plane of time where they are. He is no longer separated from them along one of the two dimensions of time, but he is still separated from them along the other. I do not say that two-dimensional time is impossible, or that there is no way to square it with the usual conception of what time travel would be like. Nevertheless I shall say no more about two-dimensional time. Let us set it aside, and see how time travel is possible even in one-dimensional time.

The world—the time traveler's world, or ours—is a four-dimensional manifold of events. Time is one dimension of the four, like the spatial dimensions except that the prevailing laws of nature discriminate between time and the others—or rather, perhaps, between various timelike dimensions and various spacelike dimensions. (Time remains one-dimensional, since no two timelike dimensions are orthogonal.) Enduring things are timelike streaks: wholes composed of temporal parts, or *stages*, located at various times and places. Change is qualitative difference between different stages—different temporal parts—of some enduring thing, just as a "change" in scenery from east to west is a qualitative difference between the eastern and western spatial parts of the landscape. If this paper should change your mind about the

From *American Philosophical Quarterly*, April 1976, pp. 145-152. © 1976 by North American Philosophical Publications. Reprinted by permission.

possibility of time travel, there will be a difference of opinion between two different temporal parts of you, the stage that started reading and the subsequent stage that finishes.

If change is qualitative difference between temporal parts of something, then what doesn't have temporal parts can't change. For instance, numbers can't change; nor can the events of any moment of time, since they cannot be subdivided into dissimilar temporal parts. (We have set aside the case of two-dimensional time, and hence the possibility that an event might be momentary along one time dimension but divisible along the other.) It is essential to distinguish change from "Cambridge change," which can befall anything. Even a number can "change" from being to not being the rate of exchange between pounds and dollars. Even a momentary event can "change" from being a year ago to being a year and a day ago, or from being forgotten to being remembered. But these are not genuine changes. Not just any old reversal in truth value of a time-sensitive sentence about something makes a change in the thing itself.

A time traveler, like anyone else, is a streak through the manifold of space-time, a whole composed of stages located at various times and places. But he is not a streak like other streaks. If he travels toward the past he is a zig-zag streak, doubling back on himself. If he travels toward the future, he is a stretched-out streak. And if he travels either way instantaneously, so that there are no intermediate stages between the stage that departs and the stage that arrives and his journey has zero duration, then he is a broken streak.

I asked how it could be that the same two events were separated by two unequal amounts of time, and I set aside the reply that time might have two independent dimensions. Instead I reply by distinguishing time itself, *external time* as I shall also call it, from the *personal time* of a particular time traveler: roughly, that which is measured by his wristwatch. His journey takes an hour of his personal time, let us say; his wristwatch reads an hour later at arrival than at departure. But the arrival is more than an hour after the departure in external time, if he travels toward the future; or the arrival is before the departure in external time (or less than an hour after), if he travels toward the past.

That is only rough. I do not wish to define personal time operationally, making wristwatches infallible by definition. That which is measured by my own wristwatch often disagrees with external time, yet I am no time traveler; what my misregulated wristwatch measures is neither time itself nor my personal time. Instead of an operational definition, we need a functional definition of personal time; it is that which occupies a certain role in the pattern of events that comprise the time traveler's life. If you take the stages of a common person, they manifest certain regularities with respect to external time. Properties change continuously as you go along, for the most part, and in familiar ways. First come infantile stages. Last come senile ones. Memories accumulate. Food digests. Hair grows. Wristwatch hands move. If you take the stages of a time traveler instead, they do not manifest the common regularities with respect to external time. But there is one way to assign coordinates to the time traveler's stages, and one way only (apart from the arbitrary choice of a zero point), so that the regularities that hold with respect to this assignment match those that commonly hold with respect to external time. With respect to the correct assignment properties change continuously as you go along, for the most part, and in familiar ways. First come infantile stages. Last come senile ones. Memories accumulate. Food digests. Hair grows. Wristwatch hands move. The assignment of coordinates that yields this match is the time traveler's personal time. It isn't really time, but it plays the role in his life that time plays in the life of a common person. It's enough like time so that we can—with due caution—transplant our temporal vocabulary to it in discussing his affairs. We can say without contradiction, as the time traveler prepares to set out, "Soon he will be in the past." We mean that a stage of him is slightly later in his personal time, but much earlier in external time, than the stage of him that is present as we say the sentence.

We may assign locations in the time traveler's personal time not only to his stages themselves but also to the events that go on around him. Soon Caesar will die, long ago; that is, a stage slightly later in the time traveler's personal time than his present stage, but long ago in external time, is simultaneous with Caesar's death. We could even extend the assignment of personal time to events that are not part of the time traveler's life, and not simultaneous with any of his stages. If his funeral in ancient Egypt is separated from his death by three days of external time and his death is separated from his birth by three score years and ten of his personal time, then we may add the two intervals and say that his funeral follows his birth by three score years and ten and three days of *extended personal time*. Likewise a bystander might truly say, three years after the last departure of another famous time traveler, that "he may even now—if I may use the phrase—be wandering on some plesiosaurus-haunted oolitic coral reef, or beside the lonely saline seas of the Triassic Age."[3] If the time traveler does wander on an oolitic coral reef three years after his departure in his personal time, then it is no mistake to say with respect to his extended personal time that the wandering is taking place "even now".

We may liken intervals of external time to distances as the crow flies, and intervals of personal time to distances along a winding path. The time traveler's life is like a mountain railway. The place two miles due east of here may also be nine miles down the line, in the westbound direction. Clearly we are not dealing here with two independent dimensions. Just as distance along the railway is not a fourth spatial dimension, so a time traveler's personal time is not a second dimension of time. How far down the line some place is depends on its location in three-dimensional space, and likewise the locations of events in personal time depend on their locations in one-dimensional external time.

Five miles down the line from here is a place where the line goes under a trestle; two miles further is a place where the line goes over a trestle; these places are one and the same. The trestle by which the line crosses over itself has two different locations along the line, five miles down from here and also seven. In the same way, an event in a time traveler's life may have more than one location in his personal time. If he doubles back toward the past, but not too far, he may be able to talk to himself. The conversation involves two of his stages, separated in his personal time but simultaneous in external time. The location of the conversation in personal time should be the location of the stage involved in it. But there are two such stages; to share the locations of both, the conversation must be assigned two different locations in personal time.

The more we extend the assignment of personal time outwards from the time traveler's stages to the surrounding events, the more will such events acquire multiple locations. It may happen also, as we have already seen, that events that are not simultaneous in external time will be assigned the same location in personal time—or rather, that at least one of the locations of one will be the same as at least one of the locations of the other. So extension must not be carried too far, lest the location of events in extended personal time lose its utility as a means of keeping track of their roles in the time traveler's history.

A time traveler who talks to himself, on the telephone perhaps, looks for all the world like two different people talking to each other. It isn't quite right to say that the whole of him is in two places at once, since neither of the two stages involved in the conversation is the whole of him, or even the whole of the part of him that is located at the (external) time of the conversation. What's true is that he, unlike the rest of us, has two different complete stages located at the same time at different places. What reason have I, then, to regard him as one person and not two? What unites his stages, including the simultaneous ones, into a single person? The problem of personal identity is especially acute if he is the sort of time traveler whose journeys are instantaneous, a broken streak consisting of several unconnected segments. Then the natural way to regard him as more than one person is to take each segment as a different person. No one of them is a time traveler, and the peculiarity of the situation comes to this: all but one of these several people vanish into thin air, all but another one appear out of thin air, and there are remarkable resemblances between one at his appearance and another at his vanishing. Why isn't that at least as good a description as the one I gave, on which the several segments are all parts of one time traveler?

I answer that what unites the stages (or segments) of a time traveler is the same sort of mental, or mostly mental, continuity and connectedness that unites anyone else. The only difference is that whereas a common person is connected and continuous with respect to external time, the time traveler is connected and continuous only with respect to his own personal time. Taking the stages in order, mental (and bodily) change is mostly gradual rather than sudden, and at no point is there sudden change in too many different respects all at once. (We can include position in external time among the respects we keep track of, if we like. It may change discontinuously with respect to personal time if not too much else changes discontinuously along with it.) Moreover, there is not too much change altogether. Plenty of traits and traces last a lifetime. Finally, the connectedness and the continuity are not accidental. They are explicable; and further, they are explained by the fact that the properties of each stage depend causally on those of the stages just before in personal time, the dependence being such as tends to keep things the same.[4]

To see the purpose of my final requirement of causal continuity, let us see how it excludes a case of counterfeit time travel. Fred was created out of thin air, as if in the midst of life; he lived a while, then died. He was created by a demon, and the demon had chosen at random what Fred was to be like at the moment of his creation. Much later someone else, Sam, came to resemble Fred as he was when first created. At the very moment when the resemblance became perfect, the demon destroyed Sam. Fred and Sam together are very much like a single person: a time traveler whose personal time starts at Sam's birth, goes on to Sam's destruction and Fred's creation, and goes on from there to Fred's death. Taken in this order, the stages of Fred-*cum*-Sam have the proper connectedness and continuity. But they lack causal continuity, so Fred-*cum*-Sam is not one person and not a time traveler. Perhaps it was pure coincidence that Fred at his creation and Sam at his destruction were exactly alike; then the connectedness and continuity of Fred-*cum*-Sam across the crucial point are accidental. Perhaps instead the demon remembered what Fred was like, guided Sam toward perfect resemblance, watched his progress, and destroyed him at the right moment. Then the connectedness and continuity of Fred-*cum*-Sam has a causal explanation, but of the wrong sort. Either way, Fred's first stages do not depend causally for their properties on Sam's last stages. So the case of Fred and Sam is rightly disqualified as a case of personal identity and as a case of time travel.

We might expect that when a time traveler visits the past there will be reversals of causation. You may punch his face before he leaves, causing his eye to blacken centuries ago. Indeed, travel into the past necessarily involves reversed causation. For time travel requires personal identity—he who arrives must be the same person who departed. That requires causal continuity, in which causation runs from earlier to later stages in the order of personal time. But the orders of personal and external time disagree at some point, and there we have causation that runs from later to earlier stages in the order of external time. Elsewhere I have given an analysis of causation in terms of chains of counterfactual dependence, and I took care that my analysis would not rule out casual reversal *a priori*.[5] I think I can argue (but not here) that under my analysis the direction of counterfactual dependence and causation is governed by the direction of other *de facto* asymmetries of time. If so, then reversed causation and time travel are not excluded altogether, but can occur only where there are local exceptions to these asymmetries. As I said at the outset, the time traveler's world would be a most strange one.

Stranger still, if there are local—but only local—causal reversals, then there may also be causal loops: closed causal chains in which some of the causal links are normal in direction and others are reversed. (Perhaps there must be loops if there is reversal: I am not sure.) Each event on the loop has a causal explanation, being caused by events elsewhere on the loop. That is not to say that the loop as a whole is caused or explicable. It may not be. Its inexplicability is especially remarkable if it is made up of the sort of causal processes that transmit information. Recall the time traveler who talked to himself. He talked to himself about time travel, and in the course of the conversation his older self told his younger self how to build a time machine. That information was available in no other way. His older self knew how because his younger self had been told and the information had been preserved by the causal processes that constitute recording, storage, and retrieval of memory traces. His younger self knew, after the conversation, because his older self had known and the information had been preserved by the causal processes that constitute telling. But where did the information come from in the first place? Why did the whole affair happen? There is simply no answer. The parts of the loop are explicable, the whole of it is not. Strange! But not impossible, and not too different from inexplicabilities we are already inured to. Almost everyone agrees that God, or the Big Bang, or the entire infinite past of the universe, or the decay of a tritium atom, is uncaused and inexplicable. Then if these are possible, why not also the inexplicable causal loops that arise in the time travel?

I have committed a circularity in order not to talk about too much at once, and this is a good place to set it right. In explaining personal time, I presupposed that we were entitled to regard certain stages as comprising a single person. Then in explaining what united the stages into a single person, I presupposed that we were given a personal time order for them. The proper way to proceed is to define personhood and personal time simultaneously, as follows. Suppose given a pair of an aggregate of persona-stages, regarded as a candidate for personhood, and an assignment of coordinates to those stages, regarded as a candidate for his personal time. If the stages satisfy the conditions given in my circular explanation with respect to the assignment of coordinates, then both candidates succeed: the stages do comprise a person and the assignment is his personal time.

I have argued so far that what goes on in a time travel story may be a possible pattern of events in four-dimensional space-time with no extra time dimension; that it may be correct to regard the scattered stages of the alleged time traveler as comprising a single person; and that we may legitimately assign to those stages and their surroundings a personal time order that disagrees sometimes with their order in external time. Some might concede all this, but protest that the impossibility of time travel is revealed after all when we ask not what the time traveler *does*, but what he *could do*. Could a time traveler change the past? It seems not: the events of a past moment could no more change than numbers could. Yet it seems that he would be as able as anyone to do things that would change the past if he did them. If a time traveler visiting the past both could and couldn't do something that would change it, then there cannot possibly be such a time traveler.

Consider Tim. He detests his grandfather, whose success in the munitions trade built the family fortune that paid for Tim's time machine. Tim would like nothing so much as to kill Grandfather, but alas he is too late. Grandfather died in his bed in 1957, while Tim was a young boy. But when Tim has built his time machine and traveled to 1920, suddenly he realizes that he is not too late after all. He buys a rifle; he spends long hours in target practice; he shadows Grandfather to learn the route of his daily walk to the munitions works; he rents a room along the route; and there he lurks, one winter day in 1921, rifle loaded, hate in his heart, as Grandfather walks closer, closer,. . . .

Tim can kill Grandfather. He has what it takes. Conditions are perfect in every way: the best rifle money could buy, Grandfather an easy target only twenty yards away, not a breeze, door securely locked against intruders. Tim a good shot to begin with and now at the peak of training, and so on. What's to stop him? The forces of logic will not stay his hand! No powerful chaperone stands by to defend the past from interference. (To imagine such a chaperone, as some authors do, is a boring evasion, not needed to make Tim's story consistent.) In short, Tim is as much able to kill Grandfather as anyone ever is to kill anyone. Suppose that down the street another sniper, Tom, lurks waiting for another victim, Grandfather's partner. Tom is not a time traveler, but otherwise he is just like Tim: same make of rifle, same murderous intent, same everything. We can even suppose that Tom, like Tim, believes himself to be a time traveler. Someone has gone to a lot of trouble to deceive Tom into thinking so. There's no doubt that Tom can kill his victim; and Tim has everything going for him that Tom does. By any ordinary standards of ability, Tim can kill Grandfather.

Tim cannot kill Grandfather. Grandfather lived, so to kill him would be to change the past. But the events of a past moment are not subdivisible into temporal parts and therefore cannot change. Either the events of 1921 timelessly do include Tim's killing of Grandfather, or else they timelessly don't. We may be tempted to speak of the "original" 1921 that lies in Tim's personal past, many years before his birth, in which Grandfather lived; and of the "new" 1921 in which Tim now finds himself waiting in ambush to kill Grandfather. But if we do speak so, we merely confer two names on one thing. The events of 1921 are doubly located in Tim's (extended) personal time, like the trestle on the railway, but the "original" 1921 and the "new" 1921 are one and the same. If Tim did not kill Grandfather in the "original" 1921, then if he does kill Grandfather in the "new" 1921, he must both kill and not kill Grandfather in 1921—in the one and only 1921, which is both the "new" and the "original" 1921. It is logically impossible that Tim should change the past by killing Grandfather in 1921. So Tim cannot kill Grandfather.

Not that past moments are special; no more can anyone change the present or the future. Present and future momentary events no more have temporal parts than past ones do. You cannot change a present or future event from what it was originally to what it is after you change it. What you *can* do is to change the present or the future from the unactualized way they would have been without some action of yours to the way they actually are. But that is not an actual change: not a difference between two successive actualities. And Tim can certainly do as much; he changes the past from the unactualized way it would have been without him to the one and only way it actually is. To "change" the past in this way, Tim need not do anything momentous; it is enough just to be there, however unobtrusively.

You know, of course, roughly how the story of Tim must go on if it is to be consistent: he somehow fails. Since Tim didn't kill Grandfather in the "original" 1921, consistency demands that neither does he kill Grandfather in the "new" 1921. Why not? For some commonplace reason. Perhaps some noise distracts him at the last moment, perhaps he misses despite all his target practice, perhaps his nerve fails, perhaps he even feels a pang of unaccustomed mercy. His failure by no means proves that he was not really able to kill Grandfather. We often try and fail to do what we are able to do. Success at some tasks requires not only ability but also luck, and lack of luck is not a temporary lack of ability. Suppose our other sniper, Tom, fails to kill Grandfather's partner for the same reason, whatever it is, that Tim fails to kill Grandfather. It does not follow that Tom was unable to. No more does it follow in Tim's case that he was unable to do what he did not succeed in doing.

We have this seeming contradiction: "*Tim doesn't, but can, because he has what it takes*" versus "*Tim doesn't, and can't, because it's logically impossible to change the past.*" I reply that there is no contradiction. Both conclusions are true, and for the reasons given. They are compatible because "can" is equivocal.

To say that something can happen means that its happening is compossible with certain facts. *Which* facts? That is determined, but sometimes not determined well enough, by context. An ape can't speak a human language—say, Finnish—but I can. Facts about the anatomy and operation of the ape's larynx and nervous system are not compossible with his speaking Finnish. The corresponding facts about my larynx and nervous system are compossible with my speaking Finnish. But don't take me along to Helsinki as your interpreter: I can't speak Finnish. My speaking Finnish is compossible with the facts considered so far, but not with further facts about my lack of training. What I can do, relative to one set of facts, I cannot do, relative to another, more inclusive, set. Whenever the context leaves it open which facts are to count as relevant, it is possible to equivocate about whether I can speak Finnish. It is likewise possible to equivocate about whether it is possible for me to speak Finnish, or whether I am able to, or whether I have the ability or capacity or power or potentiality to. Our many words for much the same thing are little help since they do not seem to correspond to different fixed delineations of the relevant facts.

Tim's killing Grandfather that day in 1921 is compossible with a fairly rich set of facts: the facts about his rifle, his skill and training, the unobstructed line of fire, the locked door and the absence of any chaperone to defend the past, and so on. Indeed it is compossible with all the facts of the sorts we would ordinarily count as relevant is saying what someone can do. It is compossible with all the facts corresponding to those we deem relevant in Tom's case. Relative to these facts, Tim can kill Grandfather. But his killing Grandfather is not compossible with another, more inclusive set of facts. There is the simple fact that Grandfather was not killed. Also there are various other facts about Grandfather's doings after 1921 and their effects: Grandfather begat Father in 1922 and Father begat Tim in 1949. Relative to these facts, Tim cannot kill Grandfather. He can and he can't, but under different delineations of the relevant facts. You can reasonably choose the narrower delineation, and say that he can; or the wider delineation, and say that he can't. But choose. What you mustn't do is waver, say in the same breath that he both can and can't, and then claim that this contradiction proves that time travel is impossible.

Exactly the same goes for Tom's parallel failure. For Tom to kill Grandfather's partner also is compossible with all facts of the sorts we ordinarily count as relevant, but not compossible with a larger set including, for instance, the fact that the intended victim lived until 1934. In Tom's case we are not puzzled. We say without hesitation that he can do it, because we see at once that the facts that are not compossible with his success are facts about the future of the time in question and therefore not the sort of facts we count as relevant in saying what Tom can do.

In Tim's case it is harder to keep track of which facts are relevant. We are accustomed to exclude facts about the future of the time in question, but to include some facts about its past. Our standards do not apply unequivocally to the crucial facts in this special case: Tim's failure, Grandfather's survival, and his subsequent doings. If we have foremost in mind that they lie in the external future of that moment in 1921 when Tim is almost ready to shoot, then we exclude them just as we exclude the parallel facts in Tom's case. But if we have foremost in mind that they precede that moment in Tim's extended personal time, then we tend to include them. To make the latter be foremost in your mind, I chose to tell Tim's story in the order of his personal time, rather than in the order of external time. The fact of Grandfather's survival until 1957 had already been told before I got to the part of the story about Tim lurking in ambush to kill him in 1921. We must decide, if we can, whether to treat these personally past and externally future facts as if they were straightforwardly past or as if they were straightforwardly future.

Fatalists—the best of them—are philosophers who take facts we count as irrelevant in saying what someone can do, disguise them somehow as facts of a different sort that we count as relevant, and thereby argue that we can do less than we think—indeed, that there is nothing at all that we don't do but can. I am not going to vote Republican next fall. The fatalist argues that, strange to say, I not only won't but can't; for my voting Republican is not compossible with the fact that it was true already in the year 1548 that I was not going to vote Republican 428 years later. My rejoinder is that this is a fact, sure enough; however, it is an irrelevant fact about the future masquerading as a relevant fact about the past, and so should be left out of account in saying what, in any ordinary sense, I can do. We are unlikely to be fooled by the fatalist's methods of disguise in this case, or other ordinary cases. But in cases of time travel, precognition, or the like, we're on less familiar ground, so it may take less of a disguise to fool us. Also, new methods of disguise are available, thanks to the device of personal time.

Here's another bit of fatalist trickery. Tim, as he lurks, already knows that he will fail. At least he has the wherewithal to know it if he thinks, he knows it implicitly. For he remembers that Grandfather was alive when he was a boy, he knows that those who are killed are thereafter not alive, he knows (let us suppose) that he is a time traveler who has reached the same 1921 that lies in his personal past, and he ought to understand—as we do—why a time traveler cannot change the past. What is known cannot be false. So his success is not only not compossible with facts that belong to the external future and his personal past, but also is not compossible with the present fact of his knowledge that he will fail. I reply that the fact of his foreknowledge, at the moment while he waits to shoot, is not a fact entirely about that moment. It may be divided into two parts. There is the fact that he then believes (perhaps only implicitly) that he will fail; and there is the further fact that his belief is correct, and correct not at all by accident, and hence qualifies as an item of knowledge. It is only the latter fact that is not compossible with his success, but it is only the former that is entirely about the moment in question. In calling Tim's state at that moment knowledge, not just belief, facts about personally earlier but externally later moments were smuggled into consideration.

I have argued that Tim's case and Tom's are alike, except that in Tim's case we are more tempted than usual—and with reason—to opt for a semi-fatalist mode of speech. But perhaps they differ in another way. In Tom's case, we can expect a perfectly consistent answer to the counterfactual question: what if Tom had killed Grandfather's partner? Tim's case is more difficult. If Tim had killed Grandfather, it seems offhand that contradictions would have been true. The killing both would and wouldn't have occurred. No Grandfather, no Father; no Father, no Tim; no Tim, no killing. And for good measure: no Grandfather, no family fortune; no fortune, no time machine; no time machine, no killing. So the supposition that Tim killed Grandfather seems impossible in more than the semi-fatalistic sense already granted.

If you suppose Tim to kill Grandfather and hold all the rest of his story fixed, of course you get a contradiction. But likewise if you suppose Tom to kill Grandfather's partner and hold the rest of his story fixed—including the part that told of his failure—you get a contradiction. If you make any counterfactual supposition and hold all else fixed you get a contradiction. The thing to do is rather to make the counterfactual supposition and hold all else as close to fixed as you consistently can. That procedure will yield perfectly consistent answers to the question: what if Tim had not killed Grandfather? In that case, some of the story I told would not have been true. Perhaps Tim might have been the time-traveling grandson of someone else. Perhaps he might have been the grandson of a man killed in 1921 and miraculously resurrected. Perhaps he might have been not a time traveler at all, but rather someone created out of nothing in 1920 equipped with false memories of a personal past that never was. It is hard to say what is the least revision of Tim's story to make it true that Tim kills Grandfather, but certainly the contradictory story in which the killing both does and doesn't occur is not the least revision. Hence it is false (according to the unrevised story) that if Tim had killed Grandfather then contradictions would have been true.

What difference would it make if Tim travels in branching time? Suppose that at the possible world of Tim's story the space-time manifold branches; the branches are separated not in time, and not in space, but in some other way. Tim travels not only in time but also from one branch to another. In one branch Tim is absent from the events of 1921; Grandfather lives; Tim is born, grows up, and vanishes in his time machine. The other branch diverges from the first when Tim turns up in 1920; there Tim kills Grandfather and Grandfather leaves no descendants and no fortune; the events of the two branches differ more and more from that time on. Certainly this is a consistent story; it is a story in which Grandfather both is and isn't killed in 1921 (in the different branches); and it is a story in which Tim, by killing Grandfather, succeeds in preventing his own birth (in one of the branches). But it is not a story in which Tim's killing of Grandfather both does occur and doesn't: it simply does, though it is located in one branch and not the other. And it is not a story in which Tim changes the past. 1921 and later years contain the events of both branches, coexisting somehow without interaction. It remains true at all the personal times of Tim's life, even after the killing, that Grandfather lives in one branch and dies in the other.[6]

Princeton University
Received September 4, 1975

Notes

1. I have particularly in mind two of the time travel stories of Robert A. Heinlein: "By His Bootstraps" in R. A. Heinlein, *The Menace from Earth* (Hicksville, N.Y., 1959), and "—All You Zombies—," in R. A. Heinlein, *The Unpleasant Profession of Jonathan Hoag* (Hicksville, N.Y., 1959).
2. Account of time travel in two-dimensional time are found in Jack W. Meiland, "A Two-Dimensional Passage Model of Time for Time Travel," *Philosophical Studies,* vol. 26 (1974), pp. 153–173; and in the initial chapters of Isaac Asimov, *The End of Eternity* (Garden City, N.Y., 1955). Asimov's denouement, however, seems to require some different conception of time travel.
3. H. G. Wells, *The Time Machine, An Invention* (London, 1895), epilogue. The passage is criticized as contradictory in Donald C. Williams, "The Myth of Passage," *The Journal of Philosophy,* vol. 48 (1951), p. 463.
4. I discuss the relation between personal identity and mental connectedness and continuity at greater length in "Survival and Identity" in *The Identity of Persons,* ed. by Amelie Rorty (forthcoming).
5. "Causation," *The Journal of Philosophy,* vol. 70 (1973), pp. 556–567; the analysis relies on the analysis of counterfactuals given in my *Counterfactuals* (Oxford, 1973).
6. The present paper summarizes a series of lectures of the same title, given as the Gavin David Young Lectures in Philosophy at the University of Adelaide in July, 1971. I thank the Australian-American Educational Foundation and the American Council of Learned Societies for research support. I am grateful to many friends for comments on earlier versions of this paper; especially Philip Kitcher, William Newton-Smith, J. J. C. Smart, and Donald Williams.

The Tom Bearden
Website

Return to Reference Section

ANNOTATED GLOSSARY

T. E. Bearden 1997, slightly updated Dec. 2000
Latest editing and additions: 12th April, 2003
Presentation re-edit 7th January, 2013

Foreword

This is an informal glossary originally prepared in 1997 for Gary Hawkins to use on his web site, and informal definitions and discussions were rather quickly jotted down in 1997. We have been able to do a little updating now in Dec. 2000. Careful crafting and polishing for greater rigor would require much more time than I am able to spare, but perhaps the glossary can be helpful anyway.

We put in the gist of it, as we see it, and usually an annotation or commentary to explain it. We tried to put in sufficient explanations and a few references, so that the reader can see for himself or herself that physics, mathematics, and even logic itself are not quite as cut and dried as is often presented!

The only thing we absolutely insist on, that differs from the normal physics and engineering approach, is that any true definition must be an identity statement *a priori*. In this view, since no equation is an identity, then no equation is a definition; regardless of those "equations" universally advanced in physics as "definitions." All an equation states is that the *magnitude* of the somethings on the right is equal to the *magnitude* of the somethings on the left. It does not at all *define* any of the somethings on either right or left! I've completed as much as I have time for now, and made some additions and corrections to the 1997 version. As time permits, we will try to add some more in the future. I hope these hasty comments are helpful, and any errors in them are my own and not due to Gary Hawkins or to Tony Craddock!

Tom Bearden,
Dec. 2000

Webmaster's Note: There are additional Glossaries and Definitions at the ends of Tom Bearden's books *"Energy from the Vacuum"* and *"Excalibur Briefing."*

MATH AND SINGLE CHARACTER ABBREVIATIONS

ϕ The electrostatic scalar potential, in units of joule per collecting coulomb.

∇ The mathematical operator 'del'.

$\nabla\phi$ The gradient of the function ϕ , mathematically.

In EM theory, use of the del operator produces an electric field **E** given by $\mathbf{E} = -\nabla\phi$. An electrical field is also generated by the time rate of change of the magnetic vector potential **A**, where it is given by $\mathbf{E} = -d\mathbf{A}/dt$. Note that we have used that fact to assist us in producing the motionless electromagnetic generator (MEG), with COP = 16 as of this writing.

ϕq Joules of energy collected by a charge of q coulombs in an electrostatic scalar potential

having a reaction cross section of ϕ.

Since the collected energy is also usually the energy that can then be dissipated as work, this expression often yields the work performed in the circuit by the energy the surface charges collected from that part of the **S**-flow in contact with the conductors and components.

$d\phi/dt$ Time rate of change of the scalar potential.

Also one form of displacement current.

dE/dt Time rate of change of the E-field.

Also one form of displacement current.

dp/dt Time rate of change of momentum, which is a force F acting upon the system.

A force is defined as a time rate of change of momentum, or $F = dp/dt$.

dP/dt Time rate of change of polarization.

Polarization displacement current.

dq/dt Time rate of change of charge, otherwise known as "current".

Represents the normal current flow i of charges in a conductor, i.e., $i = dq/dt$.

dq/dt-Isolated Load Loop A special current loop containing the load,

...where $i = dq/dt$ in that "load loop" is isolated from the current $i = dq/dt$ in the source loop containing the power source, and the two loops are also field-coupling isolated. A transformer, e.g., does isolate the actual current in the secondary from the current in the primary, but the field coupling from primary to secondary and from secondary back to primary result in the enforcement of COP = 1.0 as the maximum performance possible (in a perfect, lossless standard transformer). In a real standard transformer with some losses, COP<1.0.

The notion is that, even though current cannot pass from the source loop to the load loop and there is no direct field coupling, energy density flow $\mathbf{S} = \mathbf{E}\times\mathbf{H}$ can pass. This is in fact the definition of what we call *bridging*, if in addition to current isolation the rigid back-field coupling is broken between energy dissipation (power) in the source loop and energy dissipation (power) in the load loop. In that fashion, overunity operation of the load can readily be achieved.

E Electric Field.

Defined in older classical electromagnetics (CEM) as a force field, by $\mathbf{E} \equiv \mathbf{F}/q$. However, this only defines the entity after an interaction with mass. In short, it defines the E-field as an effect existing only in matter.

In the early days of electrodynamics, Maxwell and the other "founding fathers" assumed a material ether filling all space. Hence any field in space was indeed such an "effect" field existing in mass. Maxwell died in 1879 of stomach cancer. In the 1880s, the Michelson-Morley experiments falsified the luminiferous (material) ether as a material medium. Hence the accepted use of the $\mathbf{E} = \mathbf{F}/q$ type of "effect" electrical field as the electric field in space was also destroyed, but the equations were never changed to eliminate this error in the foundations of CEM. Instead, electrodynamicists more or less announced one day that, "Since there is no (material) ether, we are not using one!"

There is some rationalization mathematically for such an approach, if the limiting process is used for the interaction of the "causal field" in vacuum with the charged mass q, as q is allowed to approach zero. However, from a foundations view, it is still the interaction of the field in space with charged mass that is being described in the limit, and therefore it is still the "effect" entity rather than the "cause" entity.

This serious foundations problem is still unresolved in much of CEM theory and modeling to this day. The standard by which other EM texts are measured is J. D. Jackson, **Classical Electrodynamics**, 2nd edition, Wiley, New York, 1975. In several places, Jackson opts for this avoidance of the use of the " effect" field for the "cause" field: quoting p. 28: *"...the thing that eventually gets measured is a force..." "At the moment, the electric field can be defined as the force per unit charge acting at a given point. It is a vector function of position, denoted by E."* Quoting p. 249: *"Most classical electrodynamicists continue to adhere to the notion that the EM force field exists as such in the vacuum, but do admit that physically measurable quantities such as force somehow involve the product of charge and field."*

The problem is further increased by use of this flawed definition of E-field to "define" the electrostatic scalar potential (Jackson, p. 34) by the equation $\mathbf{E} = -\nabla\phi$. First, no equation is a definition; it merely equates the magnitude of the entities on the left of the = sign to the magnitude of the entities on the right of the = sign. It has nothing at all to say about the definition or nature of any of the entities, but is merely a comparison of relative magnitudes. Any definition, a priori, must be expressed by an identity sign. In all of classical electrodynamics, there is no available proper definition of (x) in the identity $E \equiv (x)$. Indeed, there is no such identity available for force F. To quote Feynman: *"...in dealing with force the tacit assumption is always made that the force is equal to zero unless some physical body is present… One of the most important characteristics of force is that it has a material origin, and this is not just a definition. ... If you insist upon a precise definition of force, you will never get it!"* Richard P. Feynman, Robert B. Leighton, and Matthew Sands, **Lectures on Physics**, Addison-Wesley, Reading, MA, Vol. 1, 1964, p. 12-2.

In the Sachs unified field theory, O(3) electrodynamics as spearheaded by Evans is an important subset. Hence in that approach there is a solution to the problem of defining force and field. The EM fields (**E**, **B**, etc.) when in spacetime, are in fact curvatures of spacetime identically. When these ST curvatures interact with a charged mass, the effects of the interactions are the well-known force-fields in matter, which Maxwell started with in the 1860s. So in this way, the definition problem can be rigorously resolved.

$j\phi$ The Slepian vector, representing the time rate of energy density dissipation in the current

loop containing the $j\phi$.

This does not at all represent the energy flow in space and along the outside of the circuit, which may be very, very much greater, on the order of 10^{13} times as great. It does match the Poynting energy flow component that enters the circuit.

M_q or m_q The mass of a charge q.

Instead of just using "q" and assuming it to be unitary, we must include the fact that charge is a system of two coupled components: (i) the mass m_q of the charge q, and (ii) the virtual photon flux exchange (i.e., ϕ_q) of the charge q with the surrounding active vacuum. In particle physics it is already well-known that there is no symmetry of a mass system anyway, unless the vacuum's exchange with the mass is included. So the expression $m_q\phi_q$ captures the vacuum-mass exchange. By continuing to assume that charge is unitary, physics inadvertently holds to the hoary old notion of the luminiferous ether (thin material ether) that permeates all of space. Maxwell and other electrical physicists of his time believed in a material ether, and Maxwell embedded that notion in EM theory. Inexplicably it has not been rooted out of the equations to this day, even though the notion of the material ether (not the ether per se!) was destroyed by the Michelson-Morley experiment over 100 years ago. Foundations physicists continue to point out such terrible defects in physics—and continue to be ignored. We quote Mario Bunge, "A mathematical theory of the dimensions and units of physical quantities," in **Problems in the Foundations of Physics**, edited by Mario Bunge, Springer-Verlag, Berlin and New York, 1971, p. 7: "The question 'What are dimensions?' is seen to be ill conceived, for there are two concepts of dimension, namely those of dimension function and dimension value. The correct question is: 'What are [] and *d*?' " {**Note:** [] is dimension function, and *d* is dimension value.} Bunge is clearly discriminating between the function associated with the dimension, and the magnitude associated with it

Quoting Bunge, *ibid.*, p. 8: "The concept of a unit is one of those scientific notions that has remained obscure for want of a theory and excess of a coarse philosophy. Indeed we know how to manipulate units but we do not seem to know what kind of mathematical object they are. As a consequence units are sometimes confused with dimensions, at other times with standards, and they are often introduced in relation to measurement rather than to concept formulation."

And quoting Mario Bunge, **Foundations of Physics**, Springer-Verlag, New York, 1967, p. 176: "Different theories of CED [Classical Electrodynamics] are called for, both for charged particles that can to a first approximation be regarded as electromagnetically structureless (e.g., the electron and the μ -meson) and for extended systems with a charge distribution and spin (e.g., the proton). If fairly satisfactory classical theories were available they could guide the construction of the corresponding quantum theories. But no such theories are in sight partly because it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state."

Again, Bunge, *ibid.*, p. 182: "...the best modern physicist is the one who acknowledges that neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling not only to better cover their own domains but also to join smoothly so as to produce a coherent picture of the various levels of physical reality."

c The speed of light in ambient vacuum.

To discuss the speed of light, we point out that the vacuum is highly energetic, as has been shown in modern physics. Since the vacuum has an energy density, it can be modeled as a "potential" and particularly as a scalar EM potential for EM purposes. Contrary to convention, we recognize that the local energy density of the ambient vacuum potential can vary, including seasonally within and close to the solar system, etc. The average energy density of the vacuum in space far from charged masses such as stars and planets may be assumed as a "standard vacuum potential", and if this potential is equated with the notion of "flat spacetime", then an increase in this vacuum potential is an increase in the local energy density of spacetime, and hence represents a curvature of the standard flat spacetime.

In fact the interplanetary radar probes' "ranges" do show precisely such variation in the speed of light, with weekly and monthly and seasonal variations, etc. In order to comply with the nearly universal assumption in physics with respect to the constancy of c, the scientific staffs averaged the readings over the entire month. This zeroed out the variations, upheld the notion that space is a fixed type of thing, and that the speed of light in it is also a rigidly fixed constant. It *does not* agree with the actual measured speed of light from day to day.

The Russians have known and openly printed for about a century that the speed of light in a hard vacuum in deep space, far removed from solar and planetary masses, is a little slower than the speed of light in a hard vacuum near the Earth or any other large charged mass. The huge collection of charged particles in the earth have tiny separations, so that looking at the Earth as a collection of tiny dipoles, one sees a collection of enormous 4-symmetry energy flows from the time domain to the 3-space domain (and vice versa for the time-reversed portions). The increased intensity of this 4-symmetry energy flux in the vicinity of a massive planet or sun changes the local energy density of the vacuum itself, increasing it in that vicinity.

Without elaboration, we will also point out that the Earth and its dynamics structures the local spacetime and the spacetime out to some distance. So do all other planets, stars, etc. By whatever manner we model the cosmos as having been created or initiated, the dynamics and structuring of all the phenomena occurring in the universe is further impressed in the *infolded* electrodynamics inside the vacuum potential.

The "laws of nature" in one sense represent the most general results of the reactions of this internally structured "common standard spacetime" or "standard vacuum potential" with the various physical systems, devices, and measuring instruments utilized in our experiments, etc. If one deterministically alters the *structuring of the local spacetime*, one can have a system which will function there in a certain marvelous manner, but will not function that way elsewhere. Some decades ago, I participated in experiments by Golden which over a period of some five years did condition (dimension) the local vacuum potential. The result was an engine which consistently exhibited COP = 1.67 at that location, but when moved several hundred miles exhibited COP<1.0. Frank and I were made aware of this "vacuum conditioning" effect by Prof. William Tiller, who had himself conducted experiments exhibiting just such an effect over several years.

EM waves in vacuum are actually *longitudinal* (sound-type) waves, but we do not belabor the point since everything out there in the normal literature uses the transverse EM wave model for the EM wave in space. Also, the transverse wave is indeed what is detected in the interacting electron gas in our measurement instruments—whose Drude electrons are restrained to simple drift velocity longitudinally down the conductor, but are spinning and are free to precess like gyros. So our instruments detect the Drude electron precessions at right angles to the incoming disturbing longitudinal force field, which means that they do indeed measure a transverse wave. However, these are actually the *electron precession waves* in the detector, and *not* the actual EM waves in space. See my paper, "Giant Negentropy from the Common Dipole", **Journal of New Energy**, 5(1), Summer 2000, p. 11-23 for a discussion of how all EM energy comes from the time domain, via the broken 3-symmetry of the source charge or source dipole, and is emitted in 3-space in all directions as longitudinal EM waves. This is based on rigorous demonstration by E.T. Whittaker, "On the Partial Differential Equations of Mathematical Physics," **Math. Ann**., Vol. 57, 1903, p. 333-355 that the scalar potential is a harmonic set of phase conjugate longitudinal EM wave pairs. We merely applied the Whittaker decomposition to the scalar potential of a source dipole or of a source charge, and the rigorous proof that EM waves in space are longitudinal directly emerges.

Just as sound speeds up, say, in steel as a denser medium than air, the EM "sound waves" in the ambient vacuum potential speed up when that vacuum potential's flux density is increased. Consequently light does move a little faster in a hard vacuum on Earth than it does in deep space, because the vacuum itself has higher energy density near the earth than in deep space. The comings and goings and orbitings of planets and the solar mass, etc. do affect the local energy density of the vacuum between the planets, and hence the speed of light through that interplanetary space.

So the interplanetary radar does show the periodic variations of the local energy density of vacuum that are induced by these factors. For a critical paper on this, see Bryan G. Wallace, "The Unified Quantum Electrodynamic Ether," **Foundations of Physics**, 3(3), Sept. 1973, p. 381-388. His discussion of the interplanetary radar measurements of Venus, which did not fit relativity, are particularly interesting, with respect to his finding that the data were simply "averaged" to eliminate the variations and hence the diurnal, lunar, and synodic periodic components actually measured in the variations of the speed of light. See particularly Bryan G. Wallace, "The great speed of light in space cover-up." **Scientific Ethics**, 1(1), Feb. 1985. p. 2-3; — "Radar Testing of the Relative Velocity of Light in Space," **Spectrosc. Lett**. Vol. 2, 1969. p. 361.

Rigorously, the field is "defined" in electrodynamics as the effect of an interaction of the force-free entity (4-spatial!) existing prior to the interaction, with a 3-dimensional static charge. This means that the field as originally defined is an *effect* and not a *cause*. To then use it as the cause is a grave non sequitur.

This confusion of cause and effect is widespread in physics. It was probably initiated by the hoary old assumption several hundred years ago that a separate force acts upon a separate mass, which is false. In fact mass is a *component* of force, since $\mathbf{F} \equiv d/dt(m\mathbf{v}) = m(d\mathbf{v}/dt + \mathbf{v}(dm/dt)$. As can be seen, in both expanded terms there exists a mass term. To skirt the issue, electrodynamicists have simply found a neat statement that "in massfree space the field continues to exist, but the force is zero." We point out that $m = 0$ makes the momentum vanish, and so **F** vanishes, and in the definition of $\mathbf{E} = \mathbf{F}/q$ also vanishes because the numerator **F** becomes zero. Therefore *that* **E**-field vanishes.

Feynman and Wheeler pointed out that the field *as it is defined* does not and cannot exist in massless space. Only the "potential" for the field exists there, in case some charged mass is brought in to interact with that entity that does exist there. That is accurate, since spacetime is totally a potential and any "change" in spacetime is a change in that potential *a priori*. In the Sachs-Evans unified field theory, this problem is resolved because the fundamental field is defined as a spacetime curvature (change in spacetime, hence change in the ST potential) rather than $\mathbf{E} = \mathbf{F}/q$.

In empty space there are always myriads upon myriads of interfering fields and potentials, from charges all over the universe, via Puthoff's cosmological feedback principle [see
H. E. Puthoff, "Source of Vacuum Electromagnetic Zero-point Energy," **Physical Review A**, 40(9), Nov. 1, 1989, p. 4857-4862.] Thus any EM wave traveling through space is always involved in enormously active interferometry. This alone results in violent momentary variations in the speed of that wave, even from 0.01 c to 100.00 c. For a paper showing this kind of "galloping" travel of an EM wave, see William G. Harter, John Evans, Roberto Vega, and Sanford Wilson, "Galloping waves and their relativistic properties," **American Journal of Physics**, 53(7), July 1985, p. 671-679. While the average speed of the wave is $c(\gamma)$, where γ is the local energy density of the vacuum, the instantaneous speeds of the wave vary violently from instant to instant.

In special relativity, "velocity" merely is a rotation angle of the moving frame from the fixed laboratory observer's frame. The speed "c" merely represents a full right-angle turn away, toward the time-dimension (since other than the 3 spatial dimensions that is the only other dimension available to turn toward). In higher dimensional space, there are many other "higher" dimensions toward which further rotation can be accomplished. Hence rotating in n-space is not limited to a single orthogonal turn, and therefore velocities are not limited to speed c. However, each orthogonal rotation also subtracts one spatial dimension of the rotated object from the observer's 3-space. One rotation would be speed c, two departing rotations would be speed c^2, three would give c^3, etc. At three orthorotations, to the lab observer the rotated object is now purely an internal structure inside his time dimension, very similar to a mental object (mind is time-like, not spacelike). The nature of mind and its operations has a rather unexpected connection with matter, when one considers such orthorotations in hyperspace.

The point is, the speed *c* is not an "iron dictum" of nature, nor is it an "unchangeable constant"! Nature herself routinely violates that notion. As an example, de Broglie waves from any mass always move at v>c, and easily as v>>c. EM "surface" waves—so-called transverse oscillations or upheavals and depressions in the magnitude (energy density; actually the *reaction cross section*) of the local ambient vacuum potential), move at a *discretized* average speed c(γ). The longitudinal component, if freed from the transverse component, can move much faster because it is a sort of "tunneling" movement. In actual quantum tunneling experiments, e.g., music (Mozart's 40th symphony) has been transmitted through quantum mechanical tunneling between two separated points at speed v>4c. Fogal is likely to eventually place a superluminal communication system on the commercial market. We discuss superluminal communication elsewhere in this glossary.

C Capacitance. Essentially, the charge per unit potential.

For an isolated conductor, $C = Q/V$ and C is expressed in farads. A farad is one coulomb per volt.

A lower case c represents the speed of light in ambient vacuum.

E The electric field. Essentially, $E = F/q$, but that is not really a definition.

Conventionally, the units of electric field are considered to be force per unit electric charge; i.e., force per coulomb. Note that the **E**-field even in this "classical definition" does not actually exist at a point unless there is a unit point charge (a point coulomb of charged mass) located at the point. Hence contrary to classical electrodynamics, communications theory, and whatnot, no electric force field (and no magnetic force field either) exists in the vacuum, at least of the kind prescribed by Maxwell's equations and by the Heaviside-Hertz reduction of Maxwell's equations. Since Maxwell assumed it, these equations and models all still erroneously assume a material ether filling the vacuum, in which case there *would* be matter and charges, and there would *then* be force-fields in the vacuum. We refer the interested reader to discussions by Feynman and by Wheeler. Quoting: "*One of the most important characteristics of force is that it has a material origin, and this is not just a definition. Y If you insist upon a precise definition of force, you will never get it!* " [Richard P. Feynman, Robert B. Leighton, and Matthew Sands, Lectures on Physics, Addison-Wesley, Reading, MA, Vol. 1, 1964, p. 12-2.]

Even worse, note that $\mathbf{E} = \mathbf{F}/q$ defines not the magnitude of the field in space, but has to do with the divergence of energy from the field around a unit point static charge there in space, as well as the pattern of the diverged energy density. Actually, what is used as "the electric field" itself is the *reaction cross section* of the field, for a unit point static coulomb of charge. That is at best a function of the "field density" or "field intensity" of the actual electrical field in spacetime, and the direction and pattern of change of that field density due to the intercepting and diverting charge.

The field problem is resolved in the forefronts of electrodynamics by making the field a topological function. It is resolved in the Sachs-Evans O(3) electrodynamics (as a subset of Sachs' unified field theory) by making the field a function of the curvature of spacetime.

See also the discussion under c, above.

H Magnetic field strength.

B The B-field (loosely), or magnetic flux density (more properly).

Conventionally, this is thought to be defined, analogously to **E**, by the force it exerts. The force exerted on a point charge moving in the magnetic field **B** is at right angles to the velocity vector of the charge and also at right angles to **B**. Actually, the **H**-field was originally named the *magnetic field* and the **B**-field was named the *magnetic induction* (and is still sometimes called that.) This is an annoyance because it is **B** which involves the force, and hence **B** should be *named* the magnetic field. Other writers have noted this discrepancy, and Sommerfeld called **H** the magnetic excitation—which correctly describes its role—rather than calling it the magnetic field. As the reader can see, lots of things in electrical physics are *still very untidy*! There are also different ways to approach the EM modeling problem. In Kaluza-Klein unified field theory, all electromagnetics is modeled in the 5th dimension, which is wrapped around each and every point in our normal 3-dimensional space.

For practical use, a far better approach is the O(3) symmetry electrodynamics spearheaded by Myron Evans, which is also an important subset of Mendel Sachs' unified field theory. In the Sachs-Evans unified theory, electromagnetics has become general relativity and general relativity has become electromagnetics. Further, very powerful general relativity can now be directly engineered with this O(3) electrodynamics, as it further develops. We refer the reader to "The New Maxwell Electrodynamic Equations: New Tools for New Technologies. A Collection of 60 Papers from the Alpha Foundation's Institute for Advanced Study," Special Issue of **Journal of New Energy**, 4(3), Winter 1999, 335 p. Also, particularly see **Contemporary Optics and Electrodynamics**, edited by Myron W. Evans, a special topical issue of I. Prigogine and S. A. Rice (series editors), **Advances in Chemical Physics**, Wiley, 2001 (in publication). Evans gives a very long and detailed presentation, "O(3) Electrodynamics", in that publication, and also gives the paper "The Link Between the Sachs and O(3) Theories of Electrodynamics".

Q A quantity of electrical charge. Note that this statement *does not* define charge *q* itself.

We have tentatively proposed to redefine charge q as $q \equiv m_q \phi_q$. The term ϕ_q captures the vacuum's violent virtual energy interaction with the mass m_q of the charge, which is presently missing in classical EM theory and is an exceeding great flaw of omission. Further, ϕ_q may be decomposed into a harmonic series of phase conjugate wavepairs, as shown by Whittaker, 1903, *ibid*. [In O(3) electrodynamics, the internal structuring is dramatically extended, so that one can get at the "inner electrodynamics" necessary to explain such things as homeopathy, chi, ki, prana, etc.

To those scientists pooh-poohing such things as acupuncture, we point out that acupuncture in a dramatic case can allow a person without anesthetic to undergo a major operation with chest cavity opened, while the patient remains alert, conscious, and talking. President Nixon's physician on Nixon's trip to China witnessed such an actual operation, as well as other things. Nothing in our vaunted Western medical science can equal that, nor can any of our medical schools, nor can our National Academy of Science or our National Science Foundation. In short, acupuncture alone demonstrates how woefully inadequate our medical science actually is.

Also, acupuncture works on animals as well, so it does not involve hypnosis or deep suggestion. In science, we must believe the repeatable experiment, not our dogma at the moment. Yet the entire U.S. medical research community has no higher symmetry EM investigation of how acupuncture works, or of the infolded electrodynamics shown by Whittaker's decomposition of the scalar potential in 1903. Hence our scientists totally miss the vast electrodynamics of *the internal structuring of potential and charge with vacuum engines (spacetime curvature engines)*. As a result, the entire U.S. scientific and intelligence communities were totally unable to comprehend nearly five decades of Russian induction of health changes and diseases in personnel in the U.S. Embassy in Moscow, using weak EM radiation. Internal structuring of the activity producing what is called "charge"—including its internal structuring and engines—can be modeled and in theory directly engineered in the new Sachs-Evans approach.]

As shown in my paper, "Giant Negentropy from the Common Dipole," **Journal of New Energy**, 5(1), Summer 2000, p. 11-23, the broken 3-symmetry energy flow of any charge and any dipole allows a more fundamental 4-symmetry energy flow solution for the century-old problem of explaining the actual source of the EM energy that pours out of the source charge in all directions in 3-space. The 4-symmetry in EM energy flow explains its nature as longitudinal EM waves, with the charge's absorbed energy being *received* from the time domain (complex plane), transduced into 3-space, and emitted in 3-space. *The source of all EM energy at any point in 3-space is the time domain!*

It has been known for decades in particle physics that there exists no equilibrium in mass systems, unless the interaction of the vacuum with the masses is included. It has also been known that every charge and every dipole is a broken 3-symmetry in the fierce vacuum energy exchange with the charge or dipole. Yet the vacuum interaction—and specifically the source charge's and the source dipole's broken symmetry in it—are not even included in classical EM as yet. That this known total glitch in modern EM theory has not been previously corrected, when the particle physicists of every university physics department of note already know it is necessary, is inexplicable! Here we must regretfully point out finger at our orthodox scientific establishment, and particularly at our National Science Foundation and our National Academy of Science. These institutions are not even working on, nor are they aware of, nor do they even care about, the most fundamental science problems of our time. Bigger accelerators, yes. Windmills, yes. EM energy from the vacuum and electrical power systems which use it without destroying the source dipole, no. The greatest of all electrodynamics—the infolded longitudinal EM wave dynamics inside all EM fields, potentials, and waves—no. The correction of the dozens of major flaws and non sequiturs in classical electromagnetics, no. The understanding of the longitudinal EM wave interferometer weapons and quantum potential weapons already arrayed against us, no. The development of EM healing based on the Priore approach, which would totally revolutionize medical therapy and handle attacks on our cities by weapons of mass destruction, no.

We have a scientific mindset problem of epochal magnitude. And that costs the U.S. taxpayers hundreds of billions of dollars spent on the "status quo" or "business as usual" scientific endeavors that are far inferior to what can be done.

S Entropy. A quantity which measures the extent to which the energy of a system is available to do work.

Since in one sense energy is a function of ordering, then fundamentally, *entropy* refers to increasing disorder, which means increasing disruption of the ordering in our collected energy. Unfortunately, entropy is one of those concepts in physics for which there are several differing major views. We avoid all discussion of "information" etc., and prefer to deal only with the energy and time aspects. For our work in energy from the vacuum, we take the very simple view that an *entropic process* is like a positive resistor: As forward observer time passes, the entropic process continually disorders or "loses"—from further controlled conversion of energy form—the collected energy in the system. We regard a *negentropic process* as like a negative resistor: as forward observer time passes, the negentropic process receives energy in a form unusable to us, transforms, it, and outputs it in a form that is usable. Quoting Ilya Prigogine, Irreversibility as a symmetry-breaking process," Nature, Vol. 246, 1973, p. 70: *"Entropy Ycannot in general be expressed in terms of observables such as temperature and density. This is only possible in the neighbourhood of equilibriumY It is only then that both entropy and entropy production acquire a macroscopic meaning."*

So basically, the notion of entropy will apply when we have a system in equilibrium or very near equilibrium. For open systems in substantial disequilibrium, the entropy cannot even be computed, and the classical equilibrium thermodynamics with its infamous second law does not apply. On the other hand, the loading of disequilibrium (negentropic) EM systems is a very nonlinear affair. Some direct indications of this were in the Russian work in the 1930s which produced overunity and self-powering EM generators, in several physics institute. [E.g., see L. I. Mandelstam and N. D. Papaleksi., "On the parametric excitation of electric oscillations," Zhurnal Teknicheskoy Fiziki, 4(1), 1934, p. 5-29. English translation, Feb. 1968, Lawrence Radiation Laboratory, Livermore, CA, performed for NASA]. The U.S. researcher G. Obolensky also has done appreciable important experimental investigation of the nonlinear load effects for negentropic systems.

S Poynting energy density flow. Not the *overall* or *total* energy flow by any means, but just that component of it that is intercepted, diverged, collected, and used, where **S** is given by **S** = **E**×**H**.

The energy flow theory is rather thoroughly fouled, and has been since the 1880s when the flow of energy through space was proposed by both Heaviside and Poynting, independently and essentially simultaneously.

Since both **E** and **H** are defined not as fields per se, but as the reaction cross section of the fields with a unit charge, the S does not refer to "energy flow" per se, but to the intercepted component of the overall energy flow.

Poynting only considered the energy flow component around a circuit that strikes the circuit's surface charges and gets diverged into the conductors to power the electrons. Heaviside, on the other hand, also considered the startlingly enormous additional EM energy flow filling all space around the circuit's conductors, generally parallel to the conductors but missing them.

This huge Heaviside component is still there around every electrical circuit, but almost entirely ignored and unaccounted. It misses the circuit, passes on off into space, and is lost in most circuits. Yet it is trillions of times larger in magnitude than the very tiny Poynting component which actually gets intercepted, "caught" and used by the circuit to power its loads and losses.

Since no one could explain where on earth such an enormous nondiverged Heaviside component pouring out of the power source terminals could possibly come from, Lorentz—reasoning that, since the nondiverged energy flow did not do anything, it was "physically insignificant" (Lorentz' term)—then just integrated the energy flow vector around a little closed surface assumed around every volume element of interest. This efficiently discards the Heaviside nondiverged component *from all accountability*, leaving only the Poynting energy flow component vector accounted. Of course the Poynting energy flow will agree with the energy measured in the circuit, since we actually measure energy dissipation, and the energy that dissipates from the circuit must have first entered it. Electrodynamicists today just continue to use Lorentz's integration of the energy flow vector around an assumed closed surface surrounding any volume element of interest. Thus, sadly our electrical power system engineers unwittingly waste trillions of times more EM energy actually produced from the vacuum by the source dipoles in their generators, than what the feeble powerline is able to intercept and utilize.

We have nominated the vast unaccounted Heaviside energy flow accompanying every field and charge interaction as the source of the extra gravity known to be present in the arms of the spiral galaxies and holding them together. See my paper, "Dark Matter or Dark Energy?", **Journal of New Energy**, 4(4), Spring 2000, p. 4-11. Informally we have also nominated this dark Heaviside energy which fills all space, as associated with the "quintessence" energy that is responsible for the recently discovered antigravitational acceleration of the universe. In this view the giant negentropy process associated with charge (see my "Giant Negentropy of the Common Dipole" paper, *ibid*.) is ongoing in all the stars, galaxies, planets, nebulae, and other astronomical entities. The ordinary energy we measure in all these processes is gravitational; hence for symmetry and energy conservation, the primary longitudinal EM wave energy from the time domain that furnishes the energy to all these spatially energetic processes represents an increasing curvature of spacetime in the time domain as we travel outward from any origin point. This is an antigravitational force, in this concept, which is cumulative as a function of radial distance from the origin point. Hence we see the distant parts of the universe as accelerating the expansion of the universe. At present this is of course an hypothesis, and must be further validated by laboratory experiment and further theoretical work in a unified field theory electrodynamics such as the Sachs-Evans O(3) symmetry electrodynamics.

S-flow is actually comprised of an organized, structured flow of virtual photons or antiphotons and itself is not observable. Its interaction with charged particles (electrical charges and magnetic poles), however, is observable by the amount of energy collected upon (diverged around) the charge or pole (formation of a local potential), and formation of a translation force upon the charge or pole.

Again, the "**E**" and the "**H**" in the expression "**E**×**H**" are not really the "electrical field" and "magnetic field" in space, but only their *reaction cross sections* at each point in space, *should* a little unit point static coulomb be placed at that point to divert some of the **E**-field flow around it, or a little unit point static magnetic charge be placed at that point to divert some of the **H**-field flow around it. So even the Poynting energy flow **S** = **E**×**H** has been interpreted in terms of its reaction cross sections.

It is worth noting that electrodynamicists today are still politely debating EM energy flow and the energy flow vector. As an example, a polite "debate" of this subject has been ongoing for over 30 years in **American Journal of Physics** alone. A particularly significant statement of the problem is given by Jones: *"It is possible to introduce the Poynting vector **S**, defined by **S** = **E**×**H**, and regard it as the intensity of energy flow at a point. This procedure is open to criticism since we could add to **S** any vector whose divergence is zero without affecting [the basic integration procedure's result]."* [D.S. Jones, **The Theory of Electromagnetism**, Pergamon Press, Oxford, 1964, p. 52.] In short, here Jones is stating that an enormous nondiverged energy flow may accompany the Poynting flow component, and it will not be accounted for by **S** = **E**×**H**. After presenting the various elements required to solve the energy flow problem, Jones bows out with the statement: "*"It does not seem likely that an expression satisfying all these conditions will be simple… …fortunately, we are rarely concerned with the energy flow at a point. In most applications we need the rate at which energy is crossing a closed surface."* [Jones, *ibid*., p. 53.] Panofsky and Phillips warn against over-attachment to the Poynting vector: "*Paradoxical results may be obtained if one tries to identify the Poynting vector with the energy flow per unit area at any point."* [Wolfgang K. H. Panofsky and Melba Phillips, **Classical Electricity and Magnetism**, Second Edition, Addison-Wesley, Menlo Park, CA, 1962, third printing 1969, p. 180.

We point out, however, that for gravitational effects of energy flows in space, one must account the total energy flow per unit area *at and surrounding* any point, and therefore one must restore the unaccounted enormous Heaviside nondiverged EM energy flow component as well as the accounted tiny little Poynting diverged energy flow component.

Δt An increment (little piece of) time.

In special relativity, time can be considered a piece of spatial length compressed by the factor c, so that L = ct, where L is in meters, t is in seconds, and c is the speed of light. Time can also be considered as spatial EM energy compressed by the factor c^2. To comprehend time and time rate of flow, one must first realize that a priori no observable exists or persists in time. The observable is a 3-spatial snapshot made at one instant in time, so that "time stopped" momentarily. The observable is thus a frozen snapshot of the 3-spatial intersection of an ongoing 4-space interaction. At the very next instant, that snapshot no longer exists. Hence for a mass (or any other observable) to "propagate in time", there must be a process whereby Δt is continually added to the observable (such as to mass m, converting it to masstime mt for a short duration) and then subtracted again, leaving behind another frozen 3-space snapshot of the "observable" that has seemingly now endured for that little Δt period, with respect to the observer. As we explain in several papers, the sum total of the photon interactions with a mass m may be taken as the generator that produces (1) the flow of the mass m through time, by changing from m to mt to m to mt… continually, and (2) a substructuring of internal "time-flow components". In short, any time-flow ascertained in the macroworld or the microworld by the observer, has an enormously rich internal dynamics and structuring. Again, in higher symmetry electrodynamics such as O(3), the internal structuring of the photon, EM field, EM wave, and EM potential can be modeled and eventually even directly engineered.

ΔE An increment (little piece of) energy.

The photon is considered to be (unit-wise) composed of (ΔE)(Δt). However, in our view (as we explain in energy, energy collection, and energy dissipation) energy does not occur in "little fixed chunks" at all. One only has "little chunks" of energy when one *is collecting* energy in an ongoing process. In electromagnetics, the "collection" of energy is actually the *ongoing collecting* of energy from an energy flow deviating around an intercepting charge. It is a dynamic, ongoing process whereby a collector such as a charged particle intercepts and interacts with (undergoes virtual photon flux exchange with) an impinging energy density flow **S**= **E**×**H**. In an equilibrium (static) condition, the deviated flow remains very like a persistent, unchanging whirlpool in a river, and so is said to have a "static magnitude". If that Poynting flow is removed, then there is no excess collecting going on and the "magnitude of the deviated energy flow" is zero. EM energy collection/collecting is always like a rock in a high wind. As long as the wind is blowing on the rock, air is deviated to flow around the rock. The rock has a force field on and of it, and wishes to move. It also has "excess collected energy", and a gradient in this "excess collected energy" determined by the wind flow direction. When the wind ceases to blow, the rock goes back to being just a rock, and forgets it had all that excess wind energy collecting and any desire to move.

TERMS AND PHRASES

ABEL, NIELS HENRIK (1802-1829)

Norwegian mathematician who in 1824 proved that the general equation of fifth degree cannot be solved algebraically. He also left an important paper on transcendental functions which was published posthumously.

ABELIAN GROUP

A group obeying the commutative law of algebra for every pair of elements a and b under an operation **,** so that $a*b = b*a$. As an example, the set of integers is an infinite abelian group under the multiplication operation.

ACTION AT A DISTANCE

An action (effect) occurring in a local system, for which no separate local 3-space cause exists, but for which a causal correlation exists between a distant cause and the local effect.

To the local 3-space observer, the effect is baffling. In electromagnetics, action at a distance can be considered a higher topology phenomena, occurring through hyperspace or through subspace, or through "multiply connected spacetime." Particularly note that "time" is multiply connected; i.e., every spatial point in 3-space (in the entire universe) exists at the same moment in time, which means that electrodynamic action through the time domain can be used to eliminate the spatial distance between any two 3-space points. Action at a distance is absolutely required by quantum mechanics, and experiments establish its truth. Such action was implicitly included in Maxwell's quaternion theory, but was unknowingly discarded by Heaviside, Hertz, and Gibbs when they formulated a much more restricted vector interpretation of Maxwell's theory, after Maxwell's death. Bohm's hidden variable interpretation of quantum mechanics uses the quantum potential, which is a multiply-connected entity producing instantaneous action at a distance. In ordinary electrodynamics, the common scalar potential in the Coulomb gauge has instantaneous velocity, and it appears everywhere in space, wherever it will occupy, all at once *in that gauge*.

Time is also a set of energy flows in the time domain (complex plane) rather than in 3-space. Time is also multiply connected, since a priori every 3-space point in the universe exists at and in a single moment of time. Since time is dynamic and structured with special energy flows, it seems possible to use this feature to establish energy flow during one specific moment to a desired subset of 3-space points, regardless of where in the universe those points are located. Hence the development of "time-energy" technology allows action at a distance via manipulating the multiple connectivity of time and its internal structure (internal time-like energy flows).

AD HOC MODEL

A model used and fitted for a specific purpose or area.

Tentative formulation, not intended toward general application and not yet firm because there is still not a comprehensive, tested demonstration of the "fit" of the model to the complex phenomenology. Nonetheless, an ad hoc model can be quite useful in a given area, so long as it sufficiently fits the experimental data in that area and makes sufficiently accurate predictions in the area.

ADVANCED FIELD

An electromagnetic field that is a solution of the classical Maxwell equations, which is positioned on the future light-cone of spacetime.

We believe much of the problem with the "advanced solution" is a problem of interpretation. We would urge the re-interpretation not in terms of "time-travel" where the wave continues in observer forward time while the rest of the universe is assumed to retrogress to a previous state, but in terms of time-reversal of that wave only. In that case, the rest of the universe stays sane and continues to move in observer forward time, and the wave itself just moves in forward time in a path-reversed manner, back along a previous "stimulus wave" (the retarded wave that moved forward in time normally).

ADVANCED POTENTIAL

An electromagnetic potential that is a solution of the classical Maxwell equations, which is positioned on the future light-cone of spacetime.

Presently this potential has not yet been given a physical interpretation. See remarks above.

ADVANCED WAVE

An electromagnetic wave that is a solution of the classical Maxwell equations, and which is positioned on the future light-cone of spacetime.

See remarks above.

AFFINE CONNECTION

In mathematics: "A connection on a manifold, whose form is unchanged under affine changes of parameter along curves, e.g., when the original parameter t of a curve γ (t) is replaced by $t = as + b$." **Dictionary of Science and Technology**, Academic Press, Christopher Morris (Ed.), 1992.

Ugh! We'll let the mathematicians take it from there.

AFFINE TRANSFORMATION

"Transformation on a linear space to itself which can be expressed as the sum of a linear transformation and a fixed vector.

The affine transformations form a group. In the plane, the group is six-dimensional, consisting of translations, rotations, stretchings and shrinkings, reflections, simple elongations and compressions, and simple shear transformations, as well as compositions of these."

Dictionary of Science and Technology, 1992, *ibid*.

AHARONOV, YAKIR

Renowned Israeli quantum physicist and former student of David Bohm.

Co-discoverer of the *Aharonov-Bohm effect*: Even when the electromagnetic force fields reduce to zero in a charged particle system, the potentials may still exist and interfere to cause real physical effects. Together with Bohm, Aharonov authored a fundamental paper in 1959 which pointed out the primary importance of the *potentials* rather than the force fields. Indeed, the force fields are only made *in and of the charged particle system itself*, by interference there of potentials, and do not exist as such in the vacuum. The forcefields are thus not primary electromagnetic causes at all, but are *secondary effects* due to the interference of potentials in a particular charged particle system. [See *Aharonov-Bohm Effect*] In his three volumes of physics, Feynman pointed out that the forcefields do not exist *as such* in the vacuum, and that *only the potential for the forcefields exists in vacuum*. The primary causative agents for electromagnetics are thus the potentials. This has been proven both theoretically and experimentally in quantum mechanics, but still does not appear in present classical electromagnetic theory taught in universities—which terribly confuses cause waves and effect waves in wave-charge interactions.

AHARONOV-BOHM EFFECT

Phenomenon theoretically pointed out in 1959 by Yakir Aharonov and David Bohm whereby interfering electromagnetic potentials can produce effects on charged particle systems, even at a distance and in the absence of the electromagnetic force fields.

See Y. Aharonov and D. Bohm, "Significance of Electromagnetic Potentials in the Quantum Theory," Physical Review, Second Series, 115(3), 1959, p. 485-491. For an overview and extensive bibliography, see S. Olariu and I. Iovitzu Popescu, "The Quantum Effects of Electromagnetic Fluxes," Reviews of Modern Physics, 57(2), Apr. 1985, p. 339-436.

Chambers experimentally demonstrated the Aharonov-Bohm effect one year later. When **E**- and **B**-fields are zero in a region, their potentials still may exist and thus be stable and persistent. Being gradient-free, a force-free potential is not changing; no bleed-in or bleed-off of its magnitude *or of its internal structure* is occurring. Interference of the potentials produces real electromagnetic effects (energy) in the interference zone, even at a great distance, without transmission of "field energy" per se through the intervening 3-space. [Rigorously, the potential's EM energy can be considered to be *hyperspatially* transmitted, or *subspatially* transmitted (tunneled) via the Whittaker internal EM biwave mechanism. See discussions under *action at a distance*.]

In 1897-8 Stoney showed (in **Philosophical Magazine**) by physical reasoning that all the disturbances of the ether arising from sources of certain kinds can be resolved into trains of plane waves. This was extended and the general and special equations written by E.T. Whittaker in 1903 in **Mathematische Annalen**. In 1904 (delivered orally in 1903) Whittaker's second paper dealing with the subject was published in the **Proceedings of the London Mathematical Society**, and showed that scalar EM potential interferometry is in fact what generates the classical EM force fields.

The two Whittaker papers may be interpreted to show a startling arrangement in a potential or EM wave. (1) any EM field or wave in a particular 3-space is due to two interfering scalar potential functions in that space. So we may replace any EM field or wave with two scalar potential functions, a priori. (2) But each of the scalar potentials onto which the functions are applied, is decomposable into the Whittaker 1903 longitudinal EM wavepairs, where the output waves are in 3-space and the input waves are time-like and come from the complex plane. This provides a hidden "infolded LW electrodynamics" inside, and composing, all EM fields and waves. Further, the decomposition is recursive, so each of the first tier infolded EM waves can be decomposed again into a second tier of biwaves, etc. Thus the most primary electrodynamics of all is the nested infolded longitudinal EM wave structuring of all present EM waves, potentials, and fields. The internal LW waves also form rigorous curvature of ST patterns (templates) and thus engines. By engineering the structure and dynamics of the internal EM, one can engineer mass—including the atomic nuclei, quarks, and gluons—as one wishes, once the technology is sufficiently developed. In the West, this entire area has been ignored, but it has been highly weaponized by the KGB in Russia.

AIAS

Alpha Foundation's Institute for Advanced Study.

Unusual "think tank" comprised of fellows and fellow emeriti in various places in the world, who cooperate in advanced electromagnetics studies via E-mail. Led by Dr. Myron W. Evans, a theorist of note, the institute has been forging ahead with the production of O(3) symmetry electrodynamics, particularly as an important subset of Mendel Sachs' unified field theory. Dozens of AIAS group-authored papers have been published in various leading journals such as Foundations of Physics, Physica Scripta etc. More than 90 AIAS papers are carried on a restricted Department of Energy website for reference by DoE scientists. The work is particularly significant in working out how EM energy flows in both the 3-spatial and time domains, and how EM energy can be and is extracted from the active vacuum. More than a dozen of the later AIAS papers are carried on a DoE public website, http://www.ott.doe.gov/electromagnetic/papersbooks.html. Also, about two dozen AIAS papers have either been approved for publication in journals, or are in the review process. The present author is a Fellow Emeritus of the AIAS, and is kindly tolerated as a conceptualist by these advanced theoreticians.

AIDS

Acquired Immunological Deficiency Syndrome.

A condition of acquired immunological deficiency associated with infection of the cells of the immune systems with the retrovirus HTLV-III. It is usually recognized by testing positive to HIV infection, and eventually by physical deterioration and by development of one or more life-threatening opportunistic infections such as pneumonia, or of Kaposi's sarcoma.

AIKIDO

A Japanese martial art whose modern form is a synthesis of many schools of jujitsu and the zen art of meditation in motion.

It is the way (DO) of entering and turning (AI) the opponents vital energy (KI). The present author is a retired sandan (third degree black belt) in Yoseikan aikido. He is retired because of debilitating injuries suffered in other fields and accidents, and as a busted-up old dog of 70 has no business bouncing hard off the mats with all those vigorous young fellows. His extra 50 pounds also no longer enhance his athletic ability. We did write a book, privately held but never published, on Aikido and dealing with the principles of unarmed combat. Interestingly, we simply went into the deep unconscious in meditation (and perhaps a little beyond, depending on one's viewpoint) to uncover the unsuspected principles. To list them, we went through the alphabet four times. Many of these principles have never appeared in any text on martial arts or military combat. The task was placed on me by my sensei and required seven years to complete. Perhaps one of these days we will formally publish the book.

ALGEBRAS

The various types of mathematics in which the theoretical models for physics and other sciences are embedded.

Some important algebras utilized in physics are the vector algebra, tensor algebra, quaternion algebra, Grassman algebra, Pauli algebra, Clifford algebra, etc. There are many others. The complexity of the symmetry and of the topology varies significantly between these algebras. Thus, an electrodynamics model in a lower topology algebra such as vectors or tensors will not reveal or permit nearly so great a set of electrodynamic functions and operations as will electrodynamics embedded in a higher topology algebra such as quaternion algebra or Clifford algebra.

As an example, it has been shown by Barrett that the operation of many of Nikola Tesla's patented circuits cannot be understood if analyzed in vector or tensor electrodynamics. The circuits will reveal totally new functions when analyzed in quaternion electrodynamics. That paper is T. W. Barrett, "Tesla's Nonlinear Oscillator-Shuttle-Circuit (OSC) Theory," **Annales de la Fondation Louis de Broglie**, 16(1), 1991, p. 23-41

ALLOPATHIC MEDICINE

A medical system which combats disease by using remedies which produce effects different from those produced by the disease treated.

Reliance is primarily upon drugs, pain relievers, and treatment of symptoms as well as use of agents to "kill" the microbial organisms regarded as the cause of the diseases. Surgery is used as a major adjunct. From time to time, other practices formerly frowned upon or even legally prosecuted are recognized as effective and legitimate, and are then brought in under the aegis of organized allopathic medicine. Physical therapy is such a formally prosecuted modality that was eventually adopted; hypnosis is another. The problems with organized allopathy is that (1) it tends to be monopolistic, (2) it uses the state's power to enforce its credo, (3) it controls both the bulk of the medical scientific literature and the flow of research funds from both government and private sources, (4) it does not adequately police its doctors and technicians, (5) it does not sufficiently accent preventative medicine or "whole human being" treatment, and (6) it engages in conspiracies to destroy competing systems of medicine (as in the case of chiropractic). (7) On the other hand, it has made remarkable advances in preventing killer diseases by vaccination, treating them by antibiotics, and in eradicating or controlling many of the former great killer diseases such as smallpox, diphtheria, and bubonic plague. It has been far less successful in treating and reversing debilitation, cancer, arteriosclerosis, etc. Just now, most of its major weapons against the former dread diseases are beginning to fail. The disease organisms are rapidly changing into new, more virulent forms that are resistant or even immune to the present "successful" treatments. Even in orthodox medical publications, it is now beginning to be recognizing that allopathic medicine is starting to fail, and that we are again entering a period of great, uncontrollable killer pandemics.

ALLOPATHY

Another name for allopathic medicine and allopathic medical therapy.

AMBIENT VACUUM

The average active vacuum, in space, removed from large collections of charge and mass.

AMBIENT VACUUM POTENTIAL

The average standard vacuum (spacetime) considered as a potential having structure and dynamics on a myriad levels.

Anything that is composed of virtual particle flux is a *potential*. Another way of looking at the vacuum is to realize that, having an energy density, then *a priori* it is a potential or may be modeled as such.

Hence the ambient vacuum can be decomposed via the Whittaker method into an internal set of infolded EM longitudinal waves of very special nature. Further, our work on the broken 3-symmetry energy flow involved in any potential or dipolarity shows the more fundamental 4-symmetry energy flow between the time domain and 3-space. This 4-symmetry energy flow is also highly structured and dynamic.

Whittaker's work shows that, contrary to present assumptions in quantum physics, a particular potential has its virtual particle flux formed into a beautiful bidirectional wave structure. The apparent disorder at any local point in the local vacuum potential is due to the constant arrival of myriads of potentials, from charged particles all over the universe. The violent interference and re-interference of these potentials results in the creation of violently changing virtual photons—or in terms of waves, violently changing EM waves and fields. In other words, the statistical disorder of the vacuum is actually *composed of* continually and rapidly changing perfect order. [Here we have confronted 3-law Aristotelian logic with its missing 4th law, because *at the limit* opposites *are* identical!] The continual violent interferometry results in the zero-point EM fluctuations of vacuum. Each EM fluctuation is completely deterministic, as shown in Puthoff's cosmological feedback mechanism. However, the macroscopic observer has no knowledge of the cause or of the arrival, and of the myriads of interferences that produced the final EM field fluctuation. Hence although the zero-point fluctuations of vacuum are completely deterministic one-by-one, the observer has *no information* on their causality. Hence to the observer these fluctuations are completely statistical and seemingly *without local order*. However, because of their hidden determinism, these fluctuations are chaotic rather than random—contrary to the Gibbs' thermodynamics statistics assumed and adopted by quantum mechanics. That statistics should be changed to an "already chaotic" statistics containing hidden Whittaker order. This would appear to be the real solution to the recognized major QM problem of the missing chaos.

Since their changes and appearances are completely in one-to-one correspondence to all distant features of the macroscopically ordered universe, then their integration yields macroscopic order. Further, as can be seen, Mach's principle—so near and dear to the heart of Einstein—arises directly from the foregoing discussion. In such fashion, integration of statistical (but chaotic, and with hidden order) quantum changes results in the familiar, ordered macroscopic world. This removes the great error in QM: that heretofore it has failed to predict the ordered macroscopic universe we observe and inhabit.

ANALOGUE

Part that is analogous (representative or modeled).

At root, an analogue of something is a second something that functions in similar fashion to the first something.

ANAEROBE

An organism that lives, is active, and occurs in the absence of free oxygen. Particularly applicable to one-celled organisms that do so.

ANAEROBE, FACULTATIVE

An organism that can live either as an aerobe or as an anaerobe. Particularly applicable to one-celled organisms possessing that capability.

ANAEROBE, OBLIGATORY

An organism that is restricted to being anaerobic; i.e., it cannot utilize oxygen from the atmosphere.

ANAEROBIC

Characteristic of an organism of living, active, or occurring in the absence of free oxygen.

ANGULAR MOMENTUM

The momentum or "leverage" of the momentum of a moving body, with respect to an axis or reference point.

Angular momentum as the same units as action; that is, it is energy multiplied by time, or momentum multiplied by length. In terms of particles, it is also known as *spin*.

ANOMALOUS EM JAMMING MECHANISM

In a dense signal environment, an unusual mechanism whereby EM energy from the skin of an aerial vehicle is directed laser-like into the internal circuitry.

The density of the signals impinging upon the skin are such that the probability of multiple photon interaction increases. Also, on a nonlinearity in/on the skin, the multiplex of signals creates a scalar EM potential. Decomposition of this potential into Whittaker waves provides hidden "pump" waves upon the nonlinearity, which therefore acts as a pumped phase conjugate mirror (PPCM). EM fields and signals from the internal operating circuits in the vehicle provide "signal waves" to the internal skin and to the nonlinearity PPCMs on the skin. Amplified phase conjugate replica (PCR) waves are generated by the PPCMs, where in each PCR wave the energy may be the total of the external signal density pump waves upon the initiating PPCM. The result is that the skin becomes a "collector" of energy from all the impinging external signals, and focuses much of this collected external energy into laser-like beams inside the vehicle which penetrate directly back to the circuit element that originated the particular signal field/wave to the inner skin. The result is spurious jamming throughout the vehicle, directly in its operating circuits, in a manner not described in normal ECM theory. Also, the same effect occurs in a human body when exposed to such a dense signal environment (threshold about 200,000 signals per square meter per second, and particularly active above 500,000 signals per square meter per second. I.e., in such an EM "smog" environment, the anomalous jamming mechanism is able to progressively conduct the energy impinging upon the skin deep into the body and throughout it, including into the bone marrow. This effect is not described at all in the standard dosimetry literature and experimental approaches for examining the effects of EM fields and radiations upon biological systems. By rigorous frequency band control of radiations and communications, most equipment can be operated in an appreciably dense environment such as appears on the modern environment, because the equipment is essentially "narrow band." The human, however, is a very wide-band receiver, and in such dense environments—even at very weak signal levels—the human system will eventually undergo cumulative damage. This is one of the major mechanisms involved in long term deleterious biological effects of EM radiation environments, but this effect on living systems has not been investigated in the laboratory by present EM bioeffects researchers.

In the U.S. air attack on Libya in 1986, the anomalous jamming mechanism interfered with the aircraft, controls, and missiles because frequency discipline was not rigorously enforced. In the Gulf War, rigid frequency discipline was enforced, with the result that the electronic systems operated normally. However, the troops exposed to that environment (which varied from place to place) were affected by the mechanism, which added a bit to the previous cumulative damage to their immune systems, etc.

ANTIBODY

A body substance produced in response to a specific antigen (protein or carbohydrate or other substance, such as a toxin or enzyme, capable of stimulating an immune response).

The antibody counteracts the effects of the antigen, by neutralizing toxins, agglutinating bacteria or cells, precipitating soluble antigens, etc.

ANTI-ELECTRON

The time-reversed electron, or *positron*. Under time reversal, electric charge reverses in sign.

Paul A.M. Dirac, in his "A Theory of Electrons and Protons," Proceedings of the Royal Society of London A126, 1930, p. 360 introduced the negative energy electron sea (now called the "Dirac sea") with negative energy electron holes treated as the positive electron. He attempted to identify these holes with protons, but that was later refuted. The positron, discovered about a year after Dirac's paper, was later connected with this anti-electron.

Note that Dirac himself was not adamant that *all* negative energy state holes in the Dirac sea were filled with electrons, but just that *almost* all of them were. Modern researchers have tended to extend this to state that *all* the holes are filled, normally. That is sufficient in forward time situations. But it does not necessarily hold in a time-reversed situation, in a time-reversed zone, or in a tempic back emf.

ANTIGRAVITY

An effect whereby normal masses *repulse* one another rather than *attract* one another

Antigravity may also be considered as *time-reversed gravitation*. It may also be considered as *gravitation between two negative masses*.

ANTIMATTER

Matter consisting of atoms which are composed of antielectrons (positrons), antiprotons, antineutrons.

Also loosely refers to the antiparticle corresponding to a particle—the antiparticle may be regarded as the particle traveling backward in time, or "phase conjugated", or "time-reversed.

ANTIPARTICLE

A counterpart to an ordinary fundamental particle, having identical mass lifetime and spin, but with charge and magnetic moment reversed in algebraic sign.

Note that when the charge is reversed, parity and time are also reversed. Thus, properly, the antiparticle is the phase conjugation of the particle, or just conjugate particle for short. In effect an antiparticle is the particle traveling backward in observer time rather than forward in observer time.

ANTIPHASED

180 degrees out of phase (contrary-wise in timing).

ANTIPHOTON

A time-reversed photon.

Presently, the photon is considered its own antiparticle, so that photon and antiphoton are one and the same. In the new approach, that is not quite true. First, one considers that a photon—as is well known—has the units of angular momentum. Thus it is made of "energy multiplied by time." We consider that the time-forward photon (i.e. a normal photon), is made of $(+\Delta E)(+\Delta t)$. Usually physicists have largely neglected the fact that a photon carries an *increment of time* as well as an increment of energy! In our approach the antiphoton, being a *time-reversed* entity, must be composed differently. We have tentatively considered the antiphoton to be comprised of $(\Delta E)(-\Delta t)$. It will probably initially be necessary to take into account the fact that Minkowski geometry treats the T dimension as imaginary rather than simple arithmetic. We haven't had the lengthy time to work all of that out; perhaps one of the better theoreticians or one of the sharp young graduate students will do that and save us the trouble.

At any rate, the requirement is that—in a coupled photon-antiphoton pair (a graviton)—the energies of photon and antiphoton must add spatially, while *electromagnetically* the translation forces (actually translation impulses) of photon and antiphoton must cancel or thwart each other. One insists on a strong interpretation of the distortion correction theorem in phase conjugate optics. In other words, we consider the "wave" as composed of photons, while the "antiwave" (phase conjugate replica) emitted by a phase conjugate mirror is composed of antiphotons. And we consider that the distortion correction theorem must apply to the wave's photons, so that the antiphotons are precisely superposing (coupling) and then decoupling as the wave and antiwave pass through each other in perfect spatial superposition. We feel that this "totally in phase spatially but totally antiphased temporally" concept is important. It is well-known, e.g., that in certain cases protons—the very building blocks of matter itself—can pass right through other protons, as shown in certain colliding beam experiments if their relative spins are properly arranged.

ANTISIGNAL

The phase conjugate of a signal. The time reversal of that signal or its twin. The phase conjugate replica signal/wave emitted by a phase conjugate mirror material in response to an incident signal/wave.

ANTI-STOKES EMISSION

Radiation emitted from an intensely scattering medium that is of greater intensity than the input radiation.

In other words, the medium gives off more energy than we have to put into it. This has been known since the 1930s and proven experimentally, but no really complete explanation has been forthcoming. The conventional explanation is that some of the kinetic energy of the medium is furnished to cause additional emission. In that case, anti-Stokes emission would lower the kinetic energy of the emitting medium. Note that this is not necessarily true at all in Letokhov's negative absorption (excess emission) of the medium, where in that case the excess energy in the emissions is said to come directly from energy absorbed from the active vacuum.

ANTI-STOKES RADIATION

The radiation coming from an anti-Stokes emission process from an intensely scattering medium, where more energy flux is emitted than is input by the experimenter-operator.

In the past, there has just been "arm-waving" that the excess energy must come from the internal energy of the molecules. There seems to be no explanation at all of where the excess energy of the molecules must continue to come from! Tacit silence on this "apparent" violation of energy conservation is held. But see Letokhov's *negative absorption of the medium* discussions in the literature.

We quote from H. C. Dake and Jack DeMent. (1941) **Fluorescent Light and Its Applications**, Chemical Publishing Company, Inc., Brooklyn, New York, 1941. p. 51-52: *"When a phosphor or other luminescent substance emits light, it gives in most cases an emission according to Stokes' Law. This law states that the wavelength of the fluorescent (emitted) light is always greater than the wavelength of the exciting radiation. It was first observed in 1852 in the memoir "On the Change of Refrangibility of Light," by Sir G. G. Stokes. In terms of energy the relationship states that e em < e ab. While Stokes' Law holds for the majority of cases, it does not hold in certain instances. In some cases the wave length is the same for both the absorbed and the emitted radiation. That is, the efficiency appears to be perfect or unity. This is known as resonance radiation. In other cases Stokes' Law does not hold where the energy emitted is greater than the energy absorbed. This is known as Anti-Stokes emission. In 1935 Prileshajewa showed that there is an energy difference as much as 1.1 v between the exciting light and the fluorescence of aniline vapor. This added energy is attributed to additions from the internal energy of the molecule."*

There is no real problem of identifying the source of the excess energy, once one realizes that (i) every dipole is a broken symmetry in the vacuum exchange with the end charges of the dipole, and thus extracts virtual energy from the vacuum, integrates and orders it, and outputs it as EM energy density flow. One then adds multiretroreflection and multiple passes of the EM energy flow, so that charges that intercept and collect energy from the reciprocating flow can multiply connect from the same energy flow (on a given pass, only a tiny, tiny fraction—nominally about 10^{-13}—of the energy flow is intercepted and interacted with by the collecting particle). Thus multiple collections from the same EM energy flow can be accomplished, if the flow is iteratively rerouted (as by retroreflection or phase conjugate reflection) back across the collecting charges again and again.

In this fashion additional energy is collected in the collected volume, which increases the local collected energy density in that volume. In turn this increases the local potential of that volume. *In turn* that increases the energy flow from that potential acting as a dipole, because it increases the dipole strength and consequently the magnitude of the dipole's broken symmetry in its vacuum flux exchange.

The inefficiency of the process increases nonlinearly with increasing local potential, and faster than the buildup of local energy density occurs from multipass multicollection. When the inefficiency curve reaches the increasing broken symmetry energy extraction curve, then a point of equilibrium is reached. At that equilibrium point, the rate of energy diffusing out of the multipass region and escaping from the periphery of the system is equal to the rate of extraction of energy from the vacuum and flowing it out into as Poynting **S**-flow into the multicollection region and collecting it.

So we have described an open thermodynamic system, where there are two inputs of energy flow: (i) that by the operator-experimenter, and (ii) that from the vacuum via the dipolar broken symmetries. At equilibrium condition the total input energy rate is equal to the total energy escaping rate, and the conservation of energy law is rigorously upheld. However, this is an open thermodynamic system far from equilibrium, and so rigorously the nonlinear thermodynamics of such systems applies, rather than the normal equilibrium thermodynamics. As is well-known, the coefficient of performance for such open systems in disequilibrium, may permissibly be overunity, even greatly overunity.

Properly utilized, the overunity anti-Stokes or Letokhov emission can be made very large—such as COP ≈1200 in Patterson's adaptation. The process and its overunity certification already exist in the hard science literature, being known and experimentally demonstrated for at least three decades.

ANTIWAVE

The time-reversal (phase conjugation) of a reference wave.

A phase conjugate replica wave is a time-reversed replica of its referent wave. Hence it is the antiwave of the referent wave.

A-POTENTIAL

Vector magnetic potential.

The A-potential is a real entity more primary than the magnetic field **B**, and not a mathematical convenience as was originally thought—as detailed in the second volume of Feynman's three volumes of physics. Indeed, it may be separated from the magnetic field, as reported by Feynman, and used for instrumentation effects in the manner patented by Gelinas. When separated from magnetic field, it is often referred to as the "curl-free vector potential," since the **B**-field is modeled as being created from the **A**-field by curling it. In other words, **B** is defined as the curl of the magnetic vector potential, if we use $\mathbf{B} \equiv \nabla \times \mathbf{A}$. Hence "separating" magnetic field from **A**-potential simply is a sort of "parallel branching" of the energy density flow of the **A**-potential. It is like branching the voltage on a feeder line conductor in an electric circuit into two parallel conductors. The feeder potential splits into two, so that each branch has the same potential. Actually the vast energy flow in the feeder line only has a small component which strikes the surface charges, diverting the energy into the conductor and potentializing the Drude electrons. In branching into two conductors, the giant flow branches also, but is so great that the surface charges in each of the two branches still intercept essentially the same amount of energy, diverging it into the conductor. Hence each conductor exhibits the same potential as the feeder conductor

The same thing happens when one "splits" or branches the **A**-potential in similar fashion. The diverted and separated **B**-field branch will exhibit "equal energy density" flow (i.e., in the form of magnetic flux density flow) and yet the original **A**-potential path through space will still have the same previous energy flow density magnitude, just without curl (without magnetic field).

Any good toroid or very long solenoid already performs such separation, and hence energy density flow doubling. If properly used—as in the motionless electromagnetic generator (MEG)—this effect can be used to provide a generator with COP>1.0. At this writing, the present MEG exhibits COP = 16, and is a patent-pending system.

The well-known Aharonov-Bohm effect, e.g., also uses this separation of the curl of the **A**-potential, leaving an uncurled **A**-potential whose changes will and do interact with electrons.

The curl-free vector potential is particularly interesting because (1) it is a unique and independent field of nature, (2) its curl produces a magnetic field, (3) its time derivative produces an electric field, (4) its magnitude does not fall off inversely as the distance squared, but only inversely as the distance, and its time derivative $d\mathbf{A}/dt = \mathrm{B}\ \mathbf{E}$. Hence, as in the MEG, one can extract energy both from the curl-free A-potential and the curled **A**-potential (magnetic field **B**), increasing the available energy collected in the circuit to greater than what the operator input to it. This is simply a physical process of regauging, wherein electrodynamicists already routinely assume (and apply) the fact that the potential energy of any EM system can be freely changed at will, by regauging. In the real world, of course, we may have to pay a little switching energy, but we are free to regauge (by this "splitting the potential into equal parallel paths, and by other methods), at will and at any time and place. The MEG just takes advantage of one major method for free regauging, in order to violate the Lorentz symmetry condition (violate symmetry in the system's energy exchange with its active vacuum environment). It thereby is legitimately permitted to exhibit COP>1.0 and output more energy than one inputs, because the regauging transforms it into an open dissipative system far from thermodynamic equilibrium in its active environmental energy exchange.

ARISTOTELIAN LOGIC

The conventional three laws of logic, unconsciously fitted to the physical reality created by the single photon interaction. The three laws are: (1) a thing is identical to itself, (2) a thing is not identical to something else, and (3) either one has a given thing or something that is not that thing. Mathematically these are written as (1) A A, (2) A Ã, and (3) A Ã. Aristotelian logic applies only to single observation at a time (monocular observation, a single observer). When multiple simultaneous observation (multiocular observation, multiple observers) are considered, the three laws may be violated. In that case a fourth law, A Ã is added. This law may be seen to be the exact negation of all the first three. An application rule (which may itself be called a fifth law) is also added, and states that either the first three laws are explicit and the fourth is implicit, or the first three are implicit and the fourth is explicit. Further, the fourth law is the *law of the paradox*: Something that is found to be true in nature, but violates one or more of Aristotle's three laws, is known as a *logical paradox*. In the higher logic, it simply violates the case where the three Aristotelian laws are explicit and the fourth law is implicit. Instead, the three Aristotelian laws are now implicit and the fourth law has become explicit. All boundaries exhibit this effect.

It is highly recommended that the interested reader familiarize himself or herself with Morris Kline, **Mathematics: The Loss of Certainty**, Oxford University Press, New York, 1980. Kline deals directly with the fact that mathematics is not a body of unshakable truths about the physical world, and mathematical reasoning is not exact and fallible.

ARISTOTLE

A great Greek philosopher who lived from 384-322 B.C.

Aristotle is famous for his three laws of logic: (1) a thing is identical to itself, (2) a thing is not identical to something else, and (3) either one has the thing considered or one has something else.

Heraclitus pointed out that Aristotle's laws prohibited any change, and yet changes were ubiquitous. In short, for a thing to change, it had to change into something else, so Heraclitus pointed out. So how could a thing be both itself and something else simultaneously? How could it be not itself while being itself? The problem has not been solved by the logicians and philosophers to this day, because it has no solution in Aristotelian 3-law logic. So Heraclitus, believe it or not, concluded that all change was an illusion.

ATHERIOSCLEROSIS

Basically, clogging of the arteries, which may be due to deposits onto the artery walls or by thickening and growth of the artery walls themselves, or a combination. It is a chronic (slowly progressing) disease where the artery walls become progressively thickened and hardened and the artery becomes less elastic.

It has been found that the common cytomegalovirus (one of the herpes viruses) plays a key role in the development of the disease. Initial deposits irritate and injure the arterial walls, and the herpes 6 virus infects the site, partially nullifying the control of excess grown of the arterial muscle tissue. This deposit and concomitant stimulation of some excess muscle growth occurs repeated, so that the muscle tissue grows abnormally over an extended period of time. For this reason, when an operation is performed to forcibly reduce the deposits inside the artery, the resulting injuries to the arterial wall tissues leads to the herpes 6 infection and stimulation of excess muscle growth. It has been found, e.g., that after angioplasty the process is often engendered, so that within a year or two the artery is narrowed again, but this time by abnormal growth of smooth muscle tissue. The Prioré team demonstrated positive and total remission of arteriosclerosis in laboratory animals by means of nonionizing EM irradiation to produce an amplified "antiengine", which "time reversed" or dedifferentiated the stricken cells and the stricken areas back to a previous state.

ARTIFICIAL POTENTIAL

A scalar potential which is composed of, or partially contains, an artificially assembled bidirectional wave set.

See E. T. Whittaker, "On the Partial Differential Equations of Mathematical Physics," **Mathematische Annalen**, Vol. 57, 1903, p. 333-355 for proof that a "scalar potential" is actually a harmonic set of hidden bidirectional EM phase conjugate longitudinal wavepairs. Each wavepair consists of a wave and its antiwave (true time-reversed replica wave).

If the external observer could see the *detected* (effect) waves in a hidden wavepair, he would see the "wave" going in one direction and the antiwave passing precisely through it in the other direction. However, prior to detection, the phase conjugate wave exists entirely in the complex plane and hence in the time domain (in -ict). So the interpretation of Whittaker's 1903 paper, in terms of cause and effect waves, is that the phase conjugate half set is incoming from the time domain to each and every point in the dipolarity or potential, and the "real 3-space half set" is being radiated in every direction in 3-space from that point. See my paper, "Giant Negentropy….".

In addition to Whittaker's sum set of biwaves, Ziolkowski added the product set in the mid-1980s. E.g., see Richard W. Ziolkowski, "Exact solutions of the wave equation with complex source locations," **Journal of Mathematical Physics**, 26(4), April 1985, p. 861-863; Rod Donnelly and Richard Ziolkowski, "A method for constructing solutions of homogeneous partial differential equations: localized waves," **Proceedings of the Royal Society of London A**., Vol. 437, 1992, p. 673-692. Particularly see I.M. Besieris, A.M. Shaarawi, and R. W. Ziolkowski, "A bidirectional travelling plane wave representation of exact solutions of the scalar wave equation," **Journal of Mathematical Physics**, 30(6), 1989, p. 1254-1269.

However, these deal only with the effects waves after detection.

Another way of defining an artificial potential is: *A potential formed by or containing a subset formed by, deliberately summing nonzero force field vectors to a zero vector resultant*. [Note that electrodynamicists routinely discard vector systems that sum to a zero resultant; not realizing that in doing so, they are discarding vacuum engines and a vastly extended electrogravitational dynamics!] The vector zero system of infolded nonzero vectors has a deterministic, internal stress pattern that is macroscopic. The type of potential made by the zero summation depends upon the type of force vectors summed. For example, summing electric field vectors to zero produces an electrostatic scalar potential; summing magnetic field vectors to zero produces a magnetostatic scalar potential of vacuum.

All potentials represents local warps or curvatures in vacuum/spacetime, and all artificial potentials contain internal, deterministic templates of nested internal spacetime curvatures. Curvature of spacetime interacts directly upon mass and physical systems embedded in it. Thus these deterministic, internested local spacetime curvatures of the artificial potential represent vacuum engines, or spacetime engines, and the artificial potential is said to be a *dimensioned* or *activated* potential. Any system exposed to and placed in such a vacuum spacetime engine, will have these hidden vacuum flux asymmetries interacting upon each and every part of it, down to and including the nuclei, the nucleons, and the quarks in the nucleons.

ASYMMETRICAL REGAUGING

Change of either the scalar potential f or the vector potential **A**, but not both, so that a single excess force and a single change of system energy occurs in the system.

This violates the assumed Lorentz condition, and thus excess energy can enter the system, and an excess "free" force appears which can (if the system is adroitly designed) then translate to perform work upon the system to increase its (e.g. kinetic) energy, exhausting the excess regauging energy in the process and restoring symmetry.

In conventional EM theory, Maxwell's equations in potential formulation are in terms of two potentials, f (the scalar potential) and **A** (the vector potential). When Heaviside retranslated Maxwell's quaternion set of 20 equations in 20 unknowns, he transformed it (in potential form) into two equations where main variables f and **A** are not separated. Electrodynamicists, who until recently considered the potentials as not even real, but just mathematical figments and conveniences, then simply arbitrarily changed both f and **A** *just precisely so* that the extra force appearing in the system by the change of f was countered by an equal and opposite extra force also appearing in the system by the change of **A**. This type of *symmetrical (no net force) regauging* is known as the *Lorentz condition*.

Each *asymmetrical* (produces a nonzero excess net force) potential change (each half of the two asymmetrical regaugings that comprise the symmetrical regauging) also altered the overall energy of the system. However, in the symmetrical regauging that total energy change is "bottled up" as increased stress in the system, because no net translation force is available to be translated and use the energy change to produce excess "free work."

The Lorentz condition assumes that the designer *will not allow* the equilibrium of the system to be broken! In that case, of course, ordinary equilibrium thermodynamics applies, and the system cannot produce COP>1.0. Prior to this Lorentz condition assumption and its absolutely arbitrary regauging, Maxwell's equations do include asymmetrical regauging and therefore open EM systems far from thermodynamic equilibrium; precisely those which violate the Lorentz condition (symmetric regauging) assumption. In short, the unregauged equations do include COP>1.0 electrodynamic circuits and systems.

Unknowingly the electrodynamicists *arbitrarily* discarded the entire Maxwellian class of overunity EM engines and circuits—which class incorporates making a change in one potential(s) such that the Lorentz condition does not hold.

ASYMMETRY

Lack of symmetry, or "broken symmetry" in a general sense.

ASYMMETRY OF THE DIPOLE

Any dipole or dipolarity is a broken 3-symmetry in its fierce exchange of EM energy with the active vacuum. This means that it continuously receives and absorbs copious virtual energy from the seething vacuum flux, and that not all this absorbed energy is reradiated back to the vacuum in virtual form. Instead, some of it is integrated into observable form and re-radiated in all directions as usable, real 3-space EM energy.

This is standard, well-known particle physics, although it appears to be totally missing from classical electrodynamics and it is not considered at all by electrical power system designers and analysts!

Every electric charge is a broken symmetry in the virtual particle flux exchange between the quantum mechanical (energetic) vacuum and the mass of that electric charge. The dipole is two different such asymmetries. As is well-known in particle physics (not in classical EM theory!) each such broken symmetry must "gate" out some of the vacuum energy. In short, the charge asymmetry "extracts" some vacuum energy from its normal "energetic exchange" with the vacuum flux, and puts it out in some form we call "observable" (capable of being measured; specifically, of being intercepted by electric charges so as to produce a force field across the charge and translate it).

Well, an electrical charge produces a flow of energy density which we may represent conventionally as $\mathbf{S} = \mathbf{E}\times\mathbf{H}$ (when collected and measured on assumed unit point charges), which we—a little bit mistakenly—call "observable." [Actually, until the energy flow interacts with that assumed unit point charge, it is an *organized flow of virtual entities*] After interaction it is real observable EM energy in 3-space. The spinning electron has its own magnetic moment and its own **E**-field. Since (in one form) also $\mathbf{E} = -\nabla\phi$, an extracted and formed $\mathbf{S} = \mathbf{E}\times\mathbf{H}$ is output by the charge asymmetry. This output energy flow also produces the assumed ϕ evidenced by the charge interaction, since ϕ as used represents the *reaction cross section* of the potential. Note that all these entities **S**, **E**, **H**, and ϕ are defined in electrodynamics only as their own interaction cross section with a unit point charge containing mass.

In classical electrodynamics (formed long before the notion of charged particles, atoms, and EM energy flow!) it is just recognized that "charge is the source of a potential." Actually charge gates the energy flow from the vacuum flux, receiving the energy from the time domain by its asymmetry, transduces the energy into 3-space energy, and outputs it as real EM energy pouring out in 3-space in all directions. That energy-flow contains and carries the energy that will interact with charge to form the **E**-field, the **H**-field (spin field), and ϕ.

Also, in particle physics and gauge theory it is well-known that *no mass system can be in equilibrium anyway, unless the vacuum-to-mass interaction is incorporated!* After CEM was formed, much later the atom was discovered and the electron was discovered. Much later then, particle physics and quantum mechanics came along. CEM theory has never been altered to include the necessary vacuum interaction, although it has been known for decades that CEM is totally in error in this respect.

Here one poses a question to the sharp young graduate students: Why does every university continue to teach a seriously flawed classical electrodynamics which does not include the vacuum/mass interaction, when the physics department at the same university knows full well that it must or no EM system can be in equilibrium? Why is not such a *fundamental* and universal issue strongly raised and intensively discussed by our large, tax-exempt scientific organizations at their annual symposia? Why do not the National Science Foundation and the National Academy of Science demand that serious work be done at all speed, to correct such known scientific deficiencies in the classical EM theory? *What happened to science as the search for physical truth*, and replaced it with "status quo" models or—in some cases—even dogma? It is an inexplicable mystery to me, and one to which I do not know the answer.

AUTOIMMUNE DISORDER

A disease or disorder relating to or caused by the antibodies or T-cells that attack foreign molecules, cells, or tissues of their host organism.

A flagrant autoimmune disease example is AIDS, Acquired Immunological Deficiency Syndrome. The AIDS virus successfully hides from the antibodies, so that they cannot perform their proper function, and it infects the T-cells and negates their function. However, there are other examples other than AIDS: e.g., rheumatism and osteoarthritis.

BACK EMF

The counter-electromotive force, usually between the end charges of the source dipole for an EM circuit.

When the electrons in the circuit are forced against the emf—as when the charges from the ground reference of the circuit are forced back up through the emf of the source dipole—then work is done upon the source dipole to scatter the charges and destroy the dipole. Removing the dipole removes its receipt of vacuum energy via its broken 3-symmetry, transduction of that energy, and output of it along the circuit and in space around the circuit as the energy flow that powers the circuit (with part missing the circuit and being just wasted).

Since this removes the power from the circuit, then additional energy must be input to the source to perform work on the internal charges and restore that source dipole again.

There are actually two emfs in a circuit, not one. There is a 3-space emf and also an entirely unrecognized tempic emf. In either case, under proper circumstances there can be a back-emf or either one or both. See discussion under *electromotive force, back*. See also *tempic back emf* (to be added).

BALL LIGHTNING

Rare form of lightning where an incandescent, slow-moving globe forms. The globe often moves erratically, explodes, and may set fire to objects it touches.

Ball lightning may be due to scalar electromagnetic interferometry which can produce a controlled pattern of electromagnetic energy at a distance, or it may be due to the formation of a special localized spacetime curvature engine.

BARE ELECTRON

The true electron without its partial shielding of virtual positrons that are attracted around it.

BARRETT, TERENCE W.

Noted modern electrodynamicist and consultant who works in SU(2)×SU(2) gauge symmetry extended electrodynamics, and was also one of the pioneers of ultrawideband radar.

BECKER, ROBERT O.

Medical doctor, medical research scientist, and Nobel Nominee, noted for his early-on efforts—particularly in the 1960s through the 1980s, in the effects of EM fields on biological systems, studies of evoked or partially evoked limb regeneration in certain species, electrical stimulation of bone fractures to stimulate healing and reveal the mechanism involved, and the cellular regeneration system of the body as opposed to the immune system.

Becker particularly recognized that the cellular regenerative system was a special electrical system having unique functions. He even succeeded in diagramming this system as far as it is revealed by ordinary U(1) electrodynamics. Becker demonstrated partial limb regeneration in salamanders, etc. and in some other species, with electrical stimulation. In his EM-stimulated bone fracture healing, Becker showed a startling result: First the red blood cells entering the fracture area shucked their hemoglobin and grew a nucleus, thus "dedifferentiating" (biological term) or "time-reversing" (physics term) back to an earlier state. Then this modified cell redifferentiated (biological term) or "fast-forwarded in time" (physics term) into the type of cell that makes cartilage. Then this newly modified cell further redifferentiated into the type of cell that makes bone, and was deposited in the fracture site. The continuing deposits of these cells from the ongoing process evoked in red blood cells healed the fracture with new bone growth. Whereupon the action stopped.

Becker also was one of the first qualified scientists who testified in court on the deleterious effects of power line radiation. He thereby incurred the enmity of very powerful interests, so that his research funds were pulled and eventually he was forced to retire at an early age.

He was nominated for the Nobel Prize multiple times, and his epochal work did finally focus at least some attention of the medical research community on the regenerative system as opposed to the immune system which heals nothing.

Becker's profound work was of tremendous influence on me as I struggled to decipher the active mechanism in his experiments, the Prioré team's experiments in France, the Russian microwave radiation of U.S. Embassy personnel in Moscow, Kaznacheyev's experiments demonstrating transmission of cellular disease and disorder electromagnetically into target cells environmentally isolated except for contact by light from the sender cells having such disease or disorder, and the body's own regenerative system. After some 14 years struggle with the problem, I finally did break the mechanism(s) involved in all those things. But it was only possible because of the magnificent work by Becker and Prioré, the reported work by Kaznacheyev, and gradual exposure to higher symmetry electrodynamics. The work was crude at first, but eventually progressed (by 1998, e.g.) to include the port-hole concept, transduction of EM wave polarization types, the engine and engine template concepts, and unified field theory. Since then it has become clear that the proper electrodynamics to model such things is the higher symmetry O(3) electrodynamics pioneered by Evans, and now revealed to be an important subset of Sachs' unified field theory.

Becker is therefore one of my heroes whose magnificent work and long perseverance against strong scientific suppression I greatly admire. Most of Becker's detractors were or are in fact employed in positions either directly or indirectly funded by the electrical power industry. I believe that, had Becker had access to O(3) electrodynamics and Sachs' theory, he would have personally impelled the entire medical field to a marvelous and extraordinarily advanced EM medical therapy.

See Robert O. Becker and Andrew A. Marino, **Electromagnetism and Life**, State University of New York Press, Albany, 1982; Nice summary of EM bioeffects (orthodox) ; also on http://www.ortho.lsumc.edu/Faculty/Marino/EL/ELPub.html.

See also R. O. Becker, "The neural semiconduction control system and its interaction with applied electrical current and magnetic fields," **Proceedings of the XI International Congress of Radiology**, Vol. 105, 1966, p. 1753-1759, Excerpta Medica Foundation; Amsterdam; — "The direct current field: A primitive control and communication system related to growth processes," **Proceed. XVI Internat. Congr. Zoology**, Washington, D.C., Vol. 3, 1963, p. 179-183; — "The control system governing bone growth in response to mechanical stress," **J. Ark. Med. Soc**., Vol. 62, 1966, p. 404; — "A technique for producing regenerative healing in humans," **Frontier Perspectives**, 1(2), Fall/Winter 1990, p. 1-2; — with Charles H. Bachman and Howard Friedman, The direct current system: A link between the environment and the organism," **New York State Journal of Medicine**, Vol. 62, April 15, 1962, p. 1169-1176; — and D. G. Murray, "A method for producing cellular dedifferentiation by means of very small electrical currents," **Trans. N.Y. Acad. Sci**., Vol. 29, 1967, p. 606-615; — and Joseph A. Spadaro, "Electrical stimulation of partial limb regeneration in mammals," **Bulletin of the New York Academy of Medicine**, Second Series, 48(4), May 1972, p. 627-64; — and Carlton F. Hazlewood, Abraham R. Liboff, and Jan Walleczek, **Electromagnetic Applications In Medicine**," NIH-OAM Electromagnetics Panel Report, Jan. 15, 1993.

See particularly Robert O. Becker, "The significance of bioelectric potentials." **Bioelectrochemistry and Bioenergetics**, Vol. 1, 1974, p. 187-199. This is probably *the* paper by Becker that provides a really good overview of the control system. A block diagram of the proposed system is given by Becker on p. 191.

Becker also has authored several popular-oriented books filled with excellent information. These include Robert O. Becker, M.D. and Gary Selden**, The Body Electric: Electromagnetism and the Foundation of Life**, William Morrow and Co., New York, 1985; and Robert O. Becker, **Cross Currents: The Perils of Electropollution; The Promise of Electromedicine**, Jeremy P. Tarcher, Los Angeles, 1990.

BEDINI, JOHN

Noted audio engineer, overunity energy researcher, and inventor of the renowned Bedini amplifiers well-known to audiophiles, the BASE process for holographic sound, and a process for cleaning the harshness from digital audio disks.

Bedini has invented a variety of COP>1.0 processes, motors, generators, etc. Particularly he has developed a process whereby, in a battery-powered circuit, he adroitly back-pulses the battery in a recharging direction while the battery is powering the load, causing a pile-up of electrons on the surface of the battery plates that is a sharply increased scalar potential opposing the onrushing very massive lead ions in the battery in discharging mode. The result is that the potential's electron pile-up increases dramatically due to the ions' far greater inertia than that of the electrons. The result is a high potential (perhaps 40 volts) upon the surface of the battery, overpotentializing both the incoming lead ions between the plates and the electrons in the external circuit in powering mode. In this phase, energy flows from the vacuum onto both the ions and the external circuit electrons, adding significant energy to the powering of the external circuit for the same ion current inside the battery.

As the ions slow and stop, Bedini's back-pulse trailing edge causes a very sharp cutoff, thus invoking Lenz's law and resulting in the surface potential on the plates increasing to well over 100 volts. This further overpotentializes the external circuit electrons in powering mode, dissipating much more energy in the external circuit to power the loads. As the ions finally stop and reverse, their relatively sluggish re-acceleration in charging mode and their overpotentialization still results in excess energy being delivered to the external circuit. Then as the overpotentialized ions accelerate in charging mode, the external circuit is still in powering mode until the drain-off of the severe electron pile-up on the surface of the battery plates.

This is one of several modes of operation used by Bedini in his overunity battery powered circuits, which keep their batteries recharged while powering their loads.

By separating the other closed current loop between external electron currents and the ion currents between the battery plates, and then dephasing these currents, Bedini breaks the usual dissipation symmetry enforced in a closed loop circuit where all charge carriers have the same m/q ratio. In Bedini's circuits, the m/q charge ratios dramatically differ between the ion current section between the plates and the electron currents between the outside of the plates and through the external circuit. Also, by providing a much greater potential *between* the two circuit halves, The potential extends in both directions—internally back over the ions, and externally in the circuit over the external Drude electrons powering the circuit loads and losses. He provides a true negative resistor on the surface of the plates, which extracts energy from the vacuum (via its broken 3-symmetry as a dipolarity) from the time domain, transduces it into real EM energy, and overpotentializes (regauges) the potential energy of both the internal ion currents and the external electron currents.

The Bedini process is therefore a legitimate COP>1.0 system, and in his self-powering embodiments the system will run indefinitely without external energy input by the operator, use of fuel, etc. He has converted the system to an open system far from thermodynamic equilibrium in its violent energy exchange with the active vacuum, and thus the system is permitted to exhibit both COP>1.0 and self-powering as well.

For an expanded explanation of the Bedini negative resistor process in batteries, see T. E. Bearden, "Bedini's Method for Forming Negative Resistors in Batteries," **Journal of New Energy**, 5(1), Summer 2000, p. 24-38.

BEING

Pure essence, existence.

Again, something which in actuality resists Aristotelian definition unless preliminary assumptions are made. Generally used in one of two senses: (1) persistence, as in "he is (he continually exists)," or (2) identity, as in "he is the man ('he' and 'the man' are the same thing)."

BIDIRECTIONAL EM WAVES

EM waves running antiparallel to each other through a given point or region of space.

Suppose we run a normal EM wave into a phase conjugating mirror (PCM) with a gain of 1. By ordinary phase conjugate optics, the mirror then emits a backwards-traveling phase conjugate replica wave (PCR wave). According to the so-called "distortion correction theorem," that backwards traveling wave will travel backwards (as seen by the external observer) back over the exact route taken by the previous wave, and it will reappear in space precisely superposed spatially with the previous waves. If we examine the impulse (density) fields (i.e., Edt), then the forward-time wave contains Edt while the backward time wave contains E(−dt), which is just −Edt. So *electromagnetically*—as far as producing a net translation force on a charge—the E-fields seem to cancel, although they are still there and their energy is still there. Instead of translation, the two produce stress.

One thus (simple case) will have a strange kind of standing wave wherein the local energy density of the vacuum varies (e.g., sinusoidally) as a function of distance, but a charged particle placed in it will not be translated! Rigorously, that is a *gravitational standing wave*. Since change in local energy density is also a curvature of spacetime, that is also a standing sinusoidal wave of the local curvature of spacetime. This is where electromagnetics and gravitation actually meet, and where electromagnetics can be utilized to produce gravitational waves. (Much more complex waves can be produced; this is just the simplest example).

BIDIRECTIONAL FIELD FLOWS

E-fields (and B-fields) being propagated in a pair of opposite waves traveling "through" each other in opposite directions,

...where the two may be "locked together" as a wave and its antiwave; i.e., as a "Whittaker biwave pair". Note that Whittaker bidirectional EM wavepairs are not to be confused with the pairing of the wave and reflection wave on a transmission line.

BIDIRECTIONAL GATING

Gating (of energy flow, e.g.) in both directions simultaneously.

BIDIRECTIONAL TRAVELING PLANE WAVE

A wave and its antiwave, where each wave is moving in an opposite direction (standard assumption in phase conjugate physics).

In short, to the external observer the waves seem to be "moving through" each other; one from left to right, and the other from right to left; or one radially outward and the other radially inward. All scalar potentials were shown by Stoney and Whittaker to be comprised of a harmonic series of such "bidirectional traveling wave pairs." However, the interpretation of the phase conjugate waves was after detection, so that the detected "effect" wave existed in 3-space. Prior to detection, the phase conjugate half-set of the Whittaker decomposition of the scalar potential is convergent from and in the time domain (complex plane).

BIOELECTROMAGNETICS (BEM)

Presently, the scientific study of interactions between living organisms and electromagnetic fields, forces, energies, currents, and charges. The range of interactions studied ranges from atomic and molecular, through intracellular, to the whole organism**.**

Electromagnetic fields studied in BEM include those of endogenous origin (from within the organism) and exogenous origin (from outside the organism). Sources of exogenous fields include: the earth and sun, electrical equipment (power lines, radio transmitters, etc.), clinical treatment devices (e.g., TENS), and other organisms. The electromagnetic fields of greatest interest in BEM are generally classified as nonionizing (i.e., lacking sufficient energy to directly dislodge electrons from molecules or atoms.) BEM is a scientific discipline emerging on the boundaries between physics and biology. As in other sciences, progress in BEM is made by testing falsifiable hypotheses against valid measured data obtained in repeatable experiments.

Our new viewpoint seeks to dramatically enlarge the scope of this definition, to include not only the presently-recognized external (outfolded) electromagnetics, but also the internal (infolded, inside the scalar EM potential) electromagnetics, and also to utilize a unified field theory where EM is GR and vice versa.

BIOENERGETICS

That branch of Russian (KGB) energetics which is targeted against the living body, its cells and tissues, and its EM fields and potentials (biofields and biopotentials).

BIOGENESIS

Generation of living organisms from other living organisms; also, the theory or philosophy that living organisms develop only from other living organisms.

BIOLOGICAL WARFARE

Warfare against living humans, livestock, crops, etc. using pathogenic micro-organisms or biocides to create diseases and death, or using dimensioned electromagnetic potentials, fields, and waves to kindle cellular damage, disease, and death in the same targeted populations.

BIOLOGICAL WARFARE, ELECTROMAGNETIC

The use of dimensioned electromagnetic potentials, fields, and waves to induce cellular damage, disease, and death in targeted living populations.

The decades of Russian microwave radiation of personnel in the former U.S. Embassy in Moscow is an example, where only field-free potentials were dimensioned with the disease or health-change patterns (the engines). This science was developed in Russia as an outgrowth of the thousands of Kaznacheyev experiments demonstrating that any cellular disease and damage pattern could be induced from diseased or damaged cells into environmentally isolated cell cultures, purely by specialized EM radiation from the damaged or "transmitting" cells into the targeted cells.

The Chinese also used such dimensioned radiation to induce cancer in almost all GRU operatives stationed in China at the time of the major disagreement between China and Russia. In his book, Stanislov Lunev and Ira Winkler, Through the Eyes of the Enemy: Russia's Highest Ranking Military Defector Reveals Why Russia Is More Dangerous Than Ever, Regnery, Washington, D.C., 1998, p. 160, Lunev reveals it this way:*"...I was not the only person who was stationed in Beijing to come down with* *cancer… Almost all of the GRU officers stationed in China with me have been diagnosed with cancer. People assigned to the embassy had told me that they were picking up high levels of radiation from the apartment building around the embassy compound. Whether it was a form of high-tech monitoring or a conscious effort to harm our health, it seems to have been successful. So much so that in 1992 the GRU was asked to investigate the high rate of cancer among embassy officials. The findings, however, have never been made public; in part, no doubt, because of the rapprochement between Russia and China."* In short, the Chinese did exactly to the Russian GRU what the Russians were doing to the Americans.

BIOPHOTON

A quantum of angular momentum, each containing "a piece of energy welded to a piece of time, with no seam in the middle," emitted by biomolecules in living organisms. The difference between a biophoton and a normal photon is that the "infolded EM structuring" (ST curvature engine sets) carried by the biophoton carries the dynamics and templates of the living cell or tissue or body emitting the radiation.

As presently known, biophoton emission is associated with processes such as mitosis (cell division) and with mechanisms such as soliton vibrations of DNA and other alpha-helix proteins [Popp et. al., 1984; Popp et. al., 1992]. An organism's biophoton field may represent a highly-structured innate organizing field capable of encoding or transmitting information over macroscopic distances.

Kaznacheyev, e.g., showed that almost any cellular disease or damage condition can be induced from the diseased control cells to separated and environmentally isolated target cells initially normal, if (1) the visible spectrum of radiation is blocked from the targeted cells, and (2) the two groups of cells are optically connected below and above the optical spectrum, in the infrared and in the ultraviolet.

The new viewpoint seeks to dramatically extend the scope of this definition. Considering the wave aspects of the photon frequency, the infolded oscillating EM energy in the photon may be decomposed into two oscillating potentials [Whittaker, 1904]. In each of these potentials, there exists a magnificent infolded structure [Whittaker, 1903] of internal bidirectional EM wave pairs, to include the sum set [Whittaker] and the product set [Ziolkowski]. Thus the photon carries internal information, which is also referred to as the "information content of the field." Since the product set represents modulations, the basic infolded structure has signal characteristics. Mind, thought, and long term memory exist inside the personal quantum potential, which may further be regarded as consisting of coupling and uncoupling photon/antiphoton pairs—i.e., hidden gravitons. In the new viewpoint, the biophoton is the carrier of biogravitons, and also biograviton lattices. This information forms vacuum engines which can cumulate over a period of time to breach the quantum threshold and outfold, producing real change in cells, as shown by the Kaznacheyev cytopathogenic mirror effect experiments.

BIOQUANTUM POTENTIAL

A quantum potential connected to and of a living body, where the inner EM structuring and dynamics of the quantum potential are in correspondence with the inner EM structuring of the normal EM fields, potentials, and waves in the body, and also are in correspondence with the time-polarized EM structuring and dynamics of the mind and its operations.

The biopotential provides the volition and intent exhibited by the biological body, breaching the quantum threshold and producing direct psychokinetic change (by the mind-body coupling mechanism) that is the "input signal" to the servomechanisms of the body,. from the smallest to the largest. In this biopotential, the Stoney-Whittaker-Ziolkowski decomposition provides the information structure and vacuum engines that are the mind, thought, long term memory, etc. A living biological system may be defined as a physical system of otherwise inert matter (the body) and of mind, coupled to each other through a bioquantum potential.

BLOCKING

In the charge-barrier semiconductor functioning, stopping or partially stopping the flow of current in a circuit, or between two points, without stopping the Poynting S-flow.

In ordinary usage, "stopping the progress of."

BOHM, DAVID

World renowned physicist and originator of the hidden variable theory interpretation of quantum mechanics. See David J. Bohm, "A Suggested Interpretation of the Quantum Theory in Terms of 'Hidden' Variables, I and II." Physical Review, 85(2), Jan. 15, 1952, p. 166-179 (Part I); 180-193 (Part II).

Together with his student Aharonov, he co-authored a fundamental paper on the Aharonov-Bohm effect wherein interfering electromagnetic potentials can produce effects on charged particle systems, even at a distance and in the absence of the electromagnetic force fields.

BOHM'S HIDDEN VARIABLE THEORY (HVT)

A major interpretation of quantum mechanics, formulated by David Bohm and published in Physical Review in 1952.

See David J. Bohm, "A Suggested Interpretation of the Quantum Theory in Terms of 'Hidden' Variables, I and II," **Physical Review**, 85(2), Jan. 15, 1952, p. 166-179 (Part I); 180-193 (Part II). Bohm's theory makes all the correct predictions and also eliminates many problems in quantum mechanics, such as the "measurement problem" and the—now alarming—problem of the missing chaos (i.e., the missing "hidden order.").

Ironically, the prevailing Copenhagen interpretation of the QM theory predicts that the organized macroscopic world does not exist, while Bohm's theory predicts it. [Question to the sharp young graduate student: How can one defend a scientific model which predicts that he himself does not exist? If one keeps one's sense of humor, it would seem that this has to be the greatest scientific *faux pas* of all time!] It may be that one unconscious reason that most physicists still oppose HVT is that *it implies that physical reality can in fact be deterministically engineered*. Most physicists would seem to fervently wish physical reality to stay "solid as a brick," with fixed "laws of nature," which can be leisurely discovered and then utilized comfortably, predictably, and sanely. The advent of HVT (which is just a matter of time; for decades the Russians have highly weaponized the HVT area!) dramatically alters our perception of "fixed physical reality" into that of an "engineerable, changeable" physical reality! I tentatively believe that the terrible psychological implications of such a potential development is something that most scientists do not wish to cope with—we simply do not have the Gestalt for it. On the other hand, the Russian national psychology is such that they do have the Gestalt for it. The Russian energetics—which I have long referred to loosely as scalar electromagnetics—basically utilizes the infolded ordering inside the potential to create "direct patterns of vacuum flux", hence *vacuum engines*. And it also utilizes the quantum potential, including internally structuring the QP, to enable instantaneous action-at-a-distance in multiple simultaneous locations and nodes, with stupendous and automatic energy amplification.

By deterministically "patterning" the internal structuring of the scalar potential, one can directly form such vacuum engines. Whittaker showed in 1904 that any EM field pattern whatsoever can be expressed as two scalar potentials, rather than the common f and **A** representation. This means that any EM wave is simply the "interference" (between the hidden biwave structures) of two scalar potentials, even at a distance. By properly structuring an EM signal (i.e., structuring the two potentials into which it can be decomposed), the resulting EM signal—appearing normal on the surface—nonetheless now transports special vacuum engines deliberately designed to perform some particular internal task in mass systems, electronic systems, or humans when it strikes a target at a distance. I refer to this "internal structuring" of the Stoney/Whittaker/Ziolkowski internal biwaves and their products, as *dimensioning* of the potential(s), and hence of the EM carrier wave. The Russians call it the *information content of the field*; but our own scientists tend to erroneously interpret that phrase as ordinary spectral analysis. In other words, they erroneously continue to regard EM *vacuum engines* as if they were ordinary EM *signals*.

BOHREN EXPERIMENT

Revealing experiment by Bohren, replicated by Paul and Fischer, which shows that a given charge when in particle resonance absorbs more energy from a field or potential then the same charge does in "static" position.

By conventional outlook, this provides a guaranteed COP>1.0 process. Bohren demonstrated absorbing 18 times more energy with the charge in particle resonance than with the static charge. This is a direct experiment proving the Heaviside dark energy component of EM energy flow, whether in field form or in potential form.

See Craig F. Bohren, "How can a particle absorb more than the light incident on it"?", **American Journal of Physics**, 51(4), Apr. 1983, p. 323-327. See independent confirmation of Bohren's work by H. Paul and R. Fischer, *ibid*., p. 327. Other pertinent references are V. S. Letokhov, "Laser Maxwell's Demon," **Contemporary Physics**, 36(4), 1995, p. 235-243; — "Generation of Light by a scattering medium with negative resonance absorption," **Soviet Physics JETP**, 26(4), Apr. 1968, p. 835-839; — "Double Gamma and optical resonance," **Physics Letters A**, Vol. 43, 1973, p. 179-180; — "Stimulated emission of an ensemble of scattering particles with negative absorption," **ZhETF Plasma**, 5(8), Apr. 15, 1967, p. 262-265. Also see R. Pappalardo and A. Lempicki, "Brillouin and Rayleigh Scattering in Aprotic Laser Solutions Containing Neodymium," **Journal of Applied Physics**, Apr. 1992, p. 1699-1708

BRIDGE

A component or process which passes EM energy between two isolated circuits, but does not pass dq/dt between them, and which breaks the normal rigidly field-locked power dissipations in the two circuits.

Space itself would appear to be one such bridge.

BRIDGING FUNCTION

The function of passing EM energy flow between two isolated circuits, but not passing dq/dt between them, while simultaneously breaking any normal rigidly field-locked power dissipations in the two circuits.

BROKEN SYMMETRY

The fundamental meaning is a condition in which two parts of some configuration or shape on opposite sides of some divisor or condition or boundary, are not similar but differ.

In vacuum energy physics, we are very interested in the fact that any charge and any dipole represents a broken symmetry in its fierce energy exchange with the vacuum. This implies that something virtual has become observable; i.e., part of the virtual EM energy absorbed from the vacuum by the charge or by the dipole is changed into observable form and re-emitted as real, observable EM energy.

Any observable implies a broken symmetry. Non-observables imply symmetry, and vice versa. Each symmetry also can be represented by a conservation rule or law. Physicists have uncovered many kinds of symmetry in physics; and in the 1950s they also discovered broken symmetry.

BROMWICH, THOMAS JOHN I'ANSON

Brilliant English mathematician, 1875-1929, who made significant contributions to the mathematics of electromagnetism—particularly to superpotential theory—before his passion for overwork led to development of a mental disorder and eventual suicide.

Bromwich originated a method for solving the source-free Maxwell equations in 1899, publishing it in 1919. This approach formed the basis for his seminal paper on scattering of plane EM waves by spheres. He did excellent original work on infinite series and made contributions to quadratic and bilinear forms. He also placed Heaviside's operator calculus on a rigorous basis by treating the operators as contour integrals. Unfortunately Bromwich worked so intensively, in such painstaking detail, and at such length that his physical health was affected. He developed a mental disorder and eventually ended his own life in suicide.

For a summary of Bromwich's life and achievements, see G. H. Hardy, "Thomas John Bromwich," **J. London Math. Soc. 5** (1930), 209-220; — "Obituary of Thomas John Bromwich," **Proc. Roy. Soc. London A 129** (1930), i - x. For an exposition of Bromwich's equations-solving work, see J. D. Zund and J. M. Wilkes, "Bromwich's method for solving the source-free Maxwell equations," **Tensor (NS) 55** (2) (1994), 192-196.

BROWN, G. SPENCER

Noted author and creator of the laws of form, a new form of logic that dramatically extends Aristotelian logic.

Essentially Brown added complex numbers to logic, rather than just staying with simple 2-dimensional plane figures for postulate derivation. Electrical circuits— designed by Brown's logic—do function and do work. When computer software is designed by Brown's logic, it is then possible to mathematically prove whether or not the end result possesses any defects (bugs). In the future software—particularly the larger systems—may well be designed by Brown's logic. G. Spencer Brown, **Laws of Form**, Julian Press, New York, 1972. With a dramatic advance in logic itself, Brown has succeeded in formulating a true calculus of form. Note: There is now a second edition of the book.

BULK GRADIENT CHANGE

Simply a change in the amplitude of the entire potential.

… (i.e., to every internal biwave pair comprising it) at some point or in some region of space, as compared to changing the amplitude of only one or a few of the internal biwave pairs of the potential, without changing all the rest.

BYPASS RESISTOR

In electrical theory, a resistor to pass current by (in parallel to) some other component.

If other effects such as use of the overpotential, pumped phase conjugate reflection, quantum wells, quantum tunneling, and charge blocking are added, the function of the bypass resistor becomes extremely complicated.

CANCER

Conventional definition: A *malignant tumor* of potentially unlimited growth that expands locally by invasion and systemically by *metastasis*.

Growths are further characterized by the type of tissue in which they occur, and their actions. Of particular interest are neoplasm, tumor, carcinoma, and sarcoma. *Malignant* disorders tend to produce deterioration, infiltrate, metastasize, and terminate fatally. A *neoplasm* is simply any new growth of tissue that serves no useful function. A *tumor* is an abnormal mass of tissue that (1) is not inflammatory, (2) arises from preexisting cells, and (3) serves no useful purpose. A *carcinoma* is a malignant tumor of *epithelial* (covering membraneous tissue of a free surface) origin. A *sarcoma* is a malignant neoplasm that arises in *mesodermal* tissue (connective tissue, bone, cartilage, or striated muscle) and that spreads by (1) extension into neighboring tissue or (2) by way of the bloodstream, or (3) both.

New definition of cancer: A centrally-commanded, final, desperate, "first-step dedifferentiation" adaptive attempt by stressed, affected cells experiencing sustained oxygen shortage (hypoxia) to reverse their cellular evolution and return to the anaerobic stage of their primeval cellular ancestry. Thus a cancer cell is a severely stressed hypoxic cell that has been "ordered" by the master cellular control system (MCCS) to dedifferentiate back to a more primeval form in which it needed little or no oxygen. It is the last desperate attempt by the body to insure the affected cells' survival when all other means available to the MCCS to provide the necessary oxygen have been exhausted and have failed. The "order" differs from normal signal theory in that it consists of a Stoney/Whittaker/Ziolkowski template inside the personal quantum potential of the organism. Thus the "order" actually consists of a vacuum engine, so that the spacetime in which the affected cell exists is acted upon by structured, energetic hidden variable fingers to directly alter it. The "signal order" is in fact a set of hidden vector forces in spacetime itself, created directly in and on the affected cell(s), in every part, in every atom. The cure for the cancerous cell, once formed, is simply to cause the MCCS to generate the "counter-order" reversing the original dedifferentiating action. This can be readily accomplished by establishing hidden multifrequency pump waves in the quantum potential on the cancerous cell, on all its parts, so that they act as pumped phase conjugate mirrors. Since they already exist in the altered "cancer" spacetime template/signal, the pumping causes a phase conjugate replica of the precise cancer state to be created in and on the cell and its parts. [In fact this is a general therapeutic mechanism, and it can be applied to reverse almost any conceivable cellular damage or disorder.] This counter-order is a new and amplified vacuum engine that acts upon the cell to redifferentiate it back to a normal cell. If an abnormal number of cells results, the body's normal processes then recognize the excess cells and destroys them.

CANCER HOTSPOT

An area or locality or location where cancer recurs repeatedly, more than the normal deviation expected statistically. In such case, one is dealing with a hidden cause or carcinogen.

Human systems exposed to such a hotspot experience cellular changes (hypoxia) which eventually result in the master cellular control system (MCCS) issuing a dedifferentiation order to the affected cells to regress back to a primeval anaerobic form. The first step is dissociation from central (MCCS) control of cellular growth, resulting in a cell that now grows and divides unrestrained by the normal body. The real question in the hotspot is, "What is the unknown agent inducing the hypoxia condition, and what is the mechanism by means of which it induces it?" Epidemology will point out a hotspot, but is usually incapable of resolving the primary causative agent or its active mechanism since it can only show correlation.

CAPACITOR AS A TRANSMISSION LINE

A capacitor can be theoretically treated as a special type of transmission line, a fact which is apparently known to transmission line theorists but not to many engineers and physicists not specializing in transmission lines.

CARCINOGEN

A substance or agent (such as a chemical or a spacetime curvature engine) capable of inducing a cancer.

In the new theory, the primary carcinogen is an actual order (a vacuum engine) issued by the master cellular control system (MCCS), reverting (dedifferentiating) the affected cell to a primal anaerobic form. Usually what are normally regarded as carcinogens are also causes of cellular conditions wherein the cell becomes very hypoxic, so much so that the MCCS exhausts all other alternative corrective means and as a last desperate measure orders the cell to change to a form that requires little or no oxygen. The "exhausting of other measures" may be very rapid, as when the cell has been affected and damaged by powerful carcinogens, or it may require decades to occur, as when the cell is subjected to long-term mild hypoxia, such as from electromagnetic smog.

CARRIER WAVE

A fundamental wave which is modulated by another wave or other waves, and hence "carries" the other waveform(s). By stripping off the carrier in a demodulator, the carried waveform(s) emerges.

Hence it is a continuous frequency wave which can be modulated by an information-bearing signal.

CASIMIR EFFECT

The attraction of two conducting parallel plates in space, placed very close together, due to their influence on the active vacuum and on the vacuum's interaction with the plates.

CASIMIR, HENDRIK BRUGT GERHARD (1909-2000)

Noted scientist who in 1948 predicted that two parallel conducting plates, placed very near each other in a vacuum, would experience an attractive force due to their influence on the electromagnetic vacuum.

See H. B. G. Casimir, “On the attraction between two perfectly conducting plates,” presented at a meeting of the Royal Netherlands Academy of Arts and Sciences on 29 May, 1948. Published in the same year in **Proceeding. Koninklijke Nederlandse Akademie van Wetenschappen,** Amsterdam, vol. 51(7), 1948, p. 793-796. For a beautiful modern experiment confirming the force, see S.K. Lamoreaux, “Demonstration of the Casimir Force in the 0.6 to 6µm range,” **Physical Review Letters**, 78(1), Jan. 6, 1997, p. 5-8.

The force was experimentally detected some 10 years later.

CAUSAL SYSTEM ROBOTS (CSRs)

Massless 4-space "engine" systems (therefore in the causal domain only, hence the name) formed of longitudinal EM waves and their dynamics, which are therefore sets of spacetime curvatures and their deterministic dynamics (engines) which function as individual robots.

This is a totally new kind of system leading to a totally new kind of warfare, developed over some decades and deployed by the KGB in 1999.

Matter is composed mostly of empty space filled with EM waves, fields, and potentials. Those "fillers" themselves are just bundles of longitudinal EM waves and their impressed dynamics. Hence all matter, the vacuum, and all conventional EM potentials, fields, and waves—being filled with vast sets of longitudinal EM waves—are vast superhighways for longitudinal EM waves to travel on or in. The CSRs, being totally LW and LW dynamics in nature, thus are free to travel right through EM radiations from power lines, phone lines, TV stations, radio stations, etc. They easily penetrate any matter, including right through a mountain. Any function of a normal EM system can be performed—at least in theory—by such robots. This includes longitudinal EM wave interferometry, which forms external EM fields and waves, of whatever pattern or form desired. Further, these CSRs are actual functioning systems, and if communications functions are designed in, one can communicate with them at a distance, using longitudinal EM wave communication, right through the intervening earth and ocean, etc.

For some time, extensive underground facilities—hundreds—have been building in the former Soviet Union, and this massive buildup continued unabated after the Russian economy collapsed and the Berlin Wall came down. This tremendous expenditure, when the Russian economy was crippled, shows the strategic significance of these facilities. Further, apparently our satellites have not seen any missiles, normal weapons or munitions, etc. associated with that vast complex. In short, it is suspected that we don't have the foggiest notion of what it is. Indeed, those facilities will already have sent some CSRs into those very satellites, to insure that we do not find out what is going on, and perhaps to "spy on the spy satellites".

We think these terribly important facilities are the KGB-controlled facilities for developing and producing the CSRs, and contain a vast longitudinal EM wave command and control set of facilities as well. In short, this is the strategic arsenal, development, and control for building sets of various type CSRs in huge numbers—a vast new army of robots with unprecedented capabilities, under the command and control of a human "strategic force" operations command of very large size.

Developing and debugging one CSR would be a formidable and lengthy task. Once a single one is developed, making a million copies is simple. Just take a normal CD-ROM, e.g., and record something on it. Send in a working CSR robot to "reside inside" the infolded EM interior of the recorded informational electromagnetic pattern on the CD-ROM. Then simply copy that CE-ROM magnetically, as many times as is desired. Each copy contains a copy of the original signal that was recorded, including the exact infolded electromagnetic structuring inside that signal. Voila! One has as many new duplicate CSRs of that exact type, as one wishes, for a few pennies each.

One can see the implications. In all those underground facilities, there are many development laboratories, production laboratories, and command and control facilities and "storage facilities" for the robots. Those hundreds of facilities are in fact a great new strategic weapon system and all its development labs and production facilities, as well as its tactical control and command and control systems, its "troops", its "equipment", and its commanders and operators.

Well, then one can deploy and "utilize" such a strategic armada just as one would use any other great strategic army. One "deploys" one's forces against the enemy. In this case, one just sends the armada (individually controlled!) right through the "LW superhighways" of matter itself, right into the strategic territory and very heart of the targeted nation. One deploys the robots everywhere—e.g., inside the electronics in nuclear warheads, inside the control systems for the nuclear submarines and nuclear bombers, inside the satellites, inside the fighter aircraft electronics, inside the fighting ships, inside the main battle tanks and major weapons carriers, inside the signals on the hard drives of computers, etc. One sends them right through the "inside" of the targeted nation's power grid electrical energy signals, through the TV stations' emitted signals, etc. The Pentagon and Cheyenne Mountain are duck soup, as is the stock exchange and other civilian systems vital to continued functioning of the infrastructure. So is everywhere else, even the deepest vault and "special security" facility.

In short, the vast electronic command and control activities of an otherwise "modern" superpower provide great, convenient, easy superhighways for full strategic deployment to be completed by millions of weapons systems (CSRs) into everything of value in the targeted nation or nations. This completely solves the usual weapons delivery problem; delivery is made in advance of D-Day.

Such a vast CSR armada was deployed throughout the Western world, and particularly in the United States, just before the end of 1999. Yes, this was to be the KGB's great millennium gift to America—a really enormous Y2K problem that would stun and disable the entire nation, its armed forces, its electronic systems in its major weapons, and its command and control centers in one great TOT (time on target) assault. The major electrical power systems of the nation would have been disabled, as would have been the major communications systems. Using LW interferometry, the robots would have wreaked havoc on the nation. They would have disabled the electronics of every major C4I computer of importance, every major fighter aircraft, every major fighting ship, every nuclear submarine, every ICBM, every nuclear powerplant, etc. The attacking force was in its deployment and employment sites in the targets themselves. Everything was in place and cocked and ready to fire. To test whether we knew what was going on, the KGB even had one or more robots temporarily produce hacker-type operations and signals "emerging" in some U.S. command and control center computers, and deliberately let our fellows discover this "hacker attack" was coming from the Russian Academy of Science. Then the CSR simply stopped its LW interferometry, which caused the "normal hacker electronic" signals to just vanish and never reappear. Little wonder that our counter-type fellows were totally unable to find any trace of it, or where it was residing. They have no technology for such.

Well, happily those early-model CSRs are easy to root out and destroy, if one has quite advanced LW technology. Visualize these beasts as existing in a special sort of "internal sky" or "infolded atmosphere" inside matter. Strategic range LW "radars" can just sweep through this "internal atmosphere" inside matter, etc., detecting and tracking those CSR beasts analogous to how normal radar detects and tracks aircraft. The difference is that the strategic LW can also use a bit of LWI pulse to instantly snap those CSRs like popping bugs, completely jamming their operations or even "erasing" them once their characteristics are observed.

That very new kind of vast strategic warfare occurred right at the end of 1999, all through the United States—the Pentagon, our strategic weapon systems, the works. The friendly little nation rooted out and destroyed all those "on site" CSRs just prior to the attack being launched.

A full-up strategic war, of previously unknown kind, was fought all over the U.S. and our own system guys apparently didn't know it. It didn't even surface. Didn't make a whimper.

That hostile CSR armada consisted of *first generation systems*. These systems did not have defensive countermeasures. The systems were depending on total surprise, but were found out (that is another story that would make a great movie if one could live to film it) and then were destroyed in short order.

CSR development has ushered in a totally new kind of strategic, operational, and tactical warfare. The delivery of all the weapon systems "into the target" is accomplished long before the advent of hostilities. The second generation CSRs, once built, will be even more sophisticated. These will almost certainly be on line soon. They will likely also possess countermeasures.

An eerie new chapter in the annals of warfare has been initiated, and the world will never be the same again. Once the CSRs have sufficient defensive countermeasures such as stealth means and coordination with countering, rapid response LWIs to target and destroy the hostile "LW radars" seeking them, etc., the next world-wide strategic CSR war will be neither so simple nor so bloodless.

NOTE: Contrast this CSR discussion to the discussion of *nanotechnology* and nanobots. Just as nanobots are natural developments which teams skilled in nanotechnology would produce, so CSRs are natural developments which teams skilled in longitudinal EM wave technology—and in the "infolded" electrodynamics inside all EM fields, potentials, and waves—would produce. For decades (since the 1950s) the KGB has been developing and using longitudinal EM wave interferometers (LWIs) which beam right through the "inner highways" inside the fields and waves inside matter, thus allowing very large LWIs which beam right through the intervening earth and ocean, and can "focus" under the ocean or within the earth as well as out of it. With such background, the CSRs were just as natural a development for them as the nanobots are for conventional Western nanotechnology scientists.

CAUSALITY

The relationship between "cause" and "effect". The basic notion in a causal system is that the system's response to an input signal is not dependent upon future input values.

Thus the notion of causality involves a precise time ordering of ordinary inert interactions, where the cause was never input from a future time. Macroscopic (observable) causality may be and is violated by the interaction of hidden subquantal (virtual state) variables.

CEREBRAL HEMISPHERE

Each half of the cerebrum, i.e., each half of the enlarged anterior or upper part of the vertebrate brain.

The two cerebral hemispheres may function as a longitudinal EM wave interferometer or a time-polarized (scalar) EM interferometer to sense distant scenes (even distant in time), or produce EM energy and signals at a distance, since the body, brain, and nervous system does produce longitudinal EM waves and scalar EM waves. For proof of scalar EM wave interferometry in O(3) electrodynamics, see M.W. Evans, P.K. Anastasovski, T.E. Bearden et al., "On Whittaker's Representation of the Electromagnetic Entity in Vacuo, Part V: The Production of Transverse Fields and Energy by Scalar Interferometry," **Journal of New Energy**, 4(3), Special Issue, Winter 1999, p. 76-78.

CHANGING THE PAST

Every intentional inception upon ordinary inert causality prior to collapse of the wave function represents a slight alteration or change in direction, departing minutely from pure causality. From a causal viewpoint, each human inception minutely changes the causal past, as well as the future.

Experimental proof that the causal past can be changed is provided by the delayed choice two-slit experiment. E.g., see C.W. Rietdijk, "Another proof that the future can influence the present." **Foundations of Physics**, 11(9/10), 1981, p. 783-790. Particularly see Wheeler, John Archibald Wheeler, "The 'past' and the 'delayed-choice' double-slit experiment," in A.R. Marlow [Ed], **Mathematical Foundations of Quantum Theory**, Loyola University, New Orleans, Louisiana, June 2-4, 1977; Academic Press, New York, 1978, p. 9-48.

CHAOS

In dissipative dynamical systems, the dynamical evolution that is aperiodic and highly dependent upon initial conditions of the system.

The trajectories of the system move on a strange attractor, which is a fractal subspace of the phase space.

The term suggests the ordinary meaning of random and unpredictable disorder, but there exists intrinsic determinism and at least partial embedded ordering. The mathematical equations describing chaotic behavior are very nonlinear and so complex that at the present time they cannot be computed or predicted. Even simple systems, including simple electromagnetic systems, can exhibit unpredictable chaotic behavior. The science of chaotic dynamics is still in its infancy, having begun moving once the modern computers became economical and pervasive.

CHARGE, ELECTRICAL (Q)

Electrical charge q is defined as $q \equiv m_q \phi_q$, to first order.

As can be seen, the actual "charge" action associated with the mass is due totally to ϕ_q, and to the broken symmetry of ϕ_q in the vacuum flux exchange with m_q. The charge q can be further broken down into a set of composite dipoles if the gathering of a virtual charge screen in the vacuum, surrounding the mass of the "bare charge" inside the gathering, is included. At first order, ϕ_q can be expressed (particle view) as a change in the local vacuum virtual photon flux (VPF), due to the VPF exchange between vacuum and m_q. The ϕ_q component is actually the "electrical charge" and massless of itself.

However, see my paper, "Giant Negentropy of the Common Dipole," **Journal of New Energy**, 5(1) Summer 2000, p. 11-23. We include the isolated charge by treating it as a system of multiple composite dipoles. We also explain the previously unrecognized 4-symmetry EM energy flow ongoing, where incoming longitudinal EM waves are being received, transduced into real longitudinal EM waves in 3-space, with the latter being emitted in all directions in 3-space.

A charged particle of mass is thus a little energy flow generator. It is a broken 3-symmetry in the local VPF, and therefore has an "observable" energy flow output, extracted and gated from the asymmetry in the VPF. This "observable" energy flow outputs the well-known energy flow **S** in classical EM, though CEM does not recognize or include this vacuum interaction, the broken 3-symmetry of the dipole, and the steady input of EM energy to the dipole in the form of EM energy from the time domain (complex plane).

Instead, classical EM just assumes that the "charge" q is the source of a potential. When originally formed as a concept, q was just a "quantity of electric fluid," like a "cubic centimeter of fluid," etc. The atom and the electron had not yet been discovered.

CHARGE CARRIERS

Anything—usually fundamental particles, ions, etc.—which consists of or contains charges and can move.

It can be an electron, a collection of electrons fixed in a moving dielectric, ions, atoms, molecules, etc.

The moving charge (i.e., the current dq/dt) with an energy flow streaming onto it and on beyond, carries its interaction with that energy-flow right along with it in the current
i = dq/dt. This is what the charge's "excess collected energy" consists of, and this is how the *collected/collecting* energy in the circuit is transported to the *collected-energy* dissipation sites (loads and losses).

CHARGE, GRAVITATIONAL

To be added

CHARGE, MAGNETIC

Essentially, the magnetic scalar potential, or monopole.

In an uncurved spacetime, the magnetic charge must always occur in dipolar pairs, where each is equal and opposite the other. In a curved spacetime, a free *net* monopolar magnetic charge may and does exist. In classical electrodynamics, the assumption of a locally flat spacetime is ubiquitous though not prominently emphasized. Hence most electrical engineers are unaware that monopoles can indeed be made, but only if one uses a process to curve local spacetime.

CHARGE-PARITY-TIME (CPT) THEOREM

The theorem states that all known quantum field theories obey CPT symmetry.

C is charge conjugation, which changes the quantum number of every particle into its antiparticle. P is the reflection operation known as parity which turn an object into its mirror image and rotates it 180 degrees about an axis perpendicular to the mirror, T is time reversal. Any violation of time-reversal symmetry is always accompanied by a violation of CP symmetry and vice versa.

Electrodynamics and the strong interaction preserve CP symmetry to great accuracy. Weak interactions do not conserve CP symmetry. T symmetry violation has been shown at CERN, the European particle physics laboratory in Geneva, Switzerland.

CHARGE TRAPPING (Also "Pinning")

Holding charges "pinned" or "trapped" by a barrier or force, so that they do not flow as
i = dq/dt.

CHARGE-BARRIER

A process or component or function—particularly in a semiconductor such as the Fogal semiconductor—which blocks the movement of charges q as current dq/dt.

CHARGE-BLOCKING ASYMMETRIC QUANTUM WELLS

A quantum well which has more charge-blocking action in one direction than the other, and is thus "asymmetric" in its function.

It may also be dynamic, so that it changes in its degree (and/or its direction) of action as a function of time.

CLASSICAL AND QUANTAL ELECTRODYNAMICS

Classical EM (CEM) theory is simply classical electrodynamics (CED).

Classical EM does not break the fields into "quanta" (a quantum is a standard-sized piece of action (angular momentum)]. Instead, CEM considers the fields as continuously varying in magnitude from zero to infinite magnitude (at least in theory).

Quantal Electrodynamics is known as quantum electrodynamics (QED). These are standard terms for standard disciplines. QED considers the fields to be composed of quanta called "photons". Hence there is an underlying region called the "virtual state" whose denizens are "smaller in magnitude" than the quantum. Heisenberg uncertainty applies, since the quantum of action is not quantized energy, but quantized (energy x time). In short, it is a function of both the magnitude of the energy and its duration of persistence. Hence a field or photon of any amount of energy may form temporarily, so long as it does not endure sufficiently long in observer time to reach quantum size and breach the quantum threshold.

In this view, then, "empty space" is not empty at all, but is a seething cauldron of these "energetic bubbles" continually appearing and disappearing, with the entire spectrum of frequencies and energies. This is in fact the "new ether". If we consider only the field portion of the bubbling virtual photons appearing and disappearing, this leads to a vacuum that consists of EM field fluctuations, again of essentially the entire frequency spectrum and energy spectrum.

However, how we attempt to tie either of these "energetic vacuum" EM views to general relativity (GR) is then a problem. The cause of the problem, however, is largely ignored in physics. In CED, e.g., one models EM energy moving through a flat space. This is a non sequitur, since the presence of any change of the energy density of space a priori is a curvature of spacetime. Hence rigorously EM energy can only propagate through a curved spacetime. Indeed, when this correction is made, the EM wave becomes an oscillating curvature of spacetime. This is the approach worked out by Mendel Sachs, extending Einstein's work. The higher symmetry O(3) electrodynamics spearheaded by Evans turns out to be an important subset of Sach's umbrella unified field theory. Hence EM has become GR, and for the first time in history, O(3) electrodynamics provides the approach that will allow direct engineering of general relativity on the lab bench, in working devices, etc.

CLASSICAL ELECTROMAGNETICS (CEM)

"Ordinary" electromagnetics, of the kind used in ordinary EM circuits, which fundamentally consists of the modified Maxwell's equations.

Classical EM consists of Maxwell's equations and the various changes and additions that have since been made. CEM does not break the fields into "quanta" (a quantum is a standard-sized piece of action (angular momentum)]. Instead, CEM considers the fields as continuously varying in magnitude from zero to infinite magnitude (at least in theory).

Primarily refers to Maxwellian electrodynamics as reinterpreted by Heaviside, Gibbs, Hertz, and a few others. Unfortunately these reinterpretations of Maxwell's theory also greatly reduced its topology, and therefore reduced the area of natural electrodynamic phenomena that the resulting equations describe.

Significantly more advanced "classical" electrodynamics emerges when one goes back to the quaternion algebra electrodynamics of Maxwell, or to the more advanced Clifford algebra electrodynamics. The higher symmetry electrodynamics models such as O(3) symmetry EM developed by Evans and others, are capable of modeling a great deal more physical phenomena than the very limited standard U(1) electrodynamics largely in vogue in science.

CLASSICAL EM THEORY

Classical electrodynamics theory, begun by Maxwell, with his seminal paper orally presented in 1864 and published in 1865.

Essentially Maxwell's electrodynamics at root basis, with the background supporting classical theory. Today many variations have been made, particularly with the basic symmetry of the theoretical equations. See discussion above under *classical electromagnetics*.

CLIFFORD ALGEBRA

A special higher topology algebra founded by Clifford, which includes as subsets many other algebras of lower topology.

CLOSED SYSTEM

A system that does not communicate with its environment, and does not exchange energy or matter between system and environment.

An ideal model where dynamically and energetically the system is considered to be "isolated" as if nothing else existed. In short, consider the system as if it were in some "magic box" and nothing outside the box can ever enter the box or affect the system inside the box, and nothing in the system can ever leave the box or affect anything outside the box.

One performs a non sequitur whenever proclaiming treatment of a system as a "closed system", and of course good scientists are aware of this. This is particularly true in electrical power systems. Here one is indeed allowed to input energy into the system to excite or potentialize it. That of course assumes that the system was "opened" long enough to take on excess energy! Then as the system operates, losses and dissipations occur, in which case energy is considered to "escape" from the system permanently. In other words, the system was also continually "opened" so that energy could escape.

There is really no such thing as a truely *closed* system in the universe, since every system is embedded in the active vacuum and is an open system in an energy exchange with the vacuum. If that exchange is symmetrical, then the system is in equilibrium with respect to the vacuum exchange. In that case, the system may be treated as if it were a closed system for a limited number of purposes. In classical electrodynamics (CED), the Lorentz regauging of the Maxwell-Heaviside equations further reduced them to describe only Maxwellian systems in such equilibrium with the active environment. Consequently, the interaction between the external vacuum and the system is not included in the CED model. Obviously a *broken equilibrium* in that actual physical interaction is also not included in the CED model.

An electrical power system is already permitted to violate the Lorentz condition when it
(1) receives additional EM energy to "energize" or "potentialize" or "excite" or "regauge" it, and (2) whenever energy escapes from the system in the loads and losses (which escapes of energy are "de-energizing", "depotentializing", "dissipating", or "regauging" actions.

Hence the Lorentz condition greatly simplifies the Maxwell-Heaviside equations and makes them much easier to solve. However, *when enforced by the system itself with regard to the system's excitation and de-excitation (dissipation) functions—i.e., when those functions are "symmetrical" (equal and opposite)*—it also arbitrarily discards all those Maxwellian systems capable of the five "magical" functions of an open disequilibrium system: (1) self-ordering, (2) self-oscillation or self-rotation, (3) output of more energy than the operator inputs (the excess energy is input by the active environment, (4) powering itself and its load (all the energy is input by the active environment, and (5) exhibiting negentropy.

It follows, however, that physical electrical power systems must therefore have some feature which self-imposes the Lorentz condition, at least during the phase when the system's excitation energy is discharged in the loads and losses. The standard closed current loop system, where every electron progressing through the external circuit's loads and losses must be forcibly rammed back up through the source dipole in the power source, is indeed what enforces the Lorentz condition with respect to excitation and dissipation, and *arbitrarily* prevents the system from achieving COP>1.0.

In a battery-powered system, the otherwise closed current loop is broken into two quite different circuits: (1) the electron current circuit between the outer surface of the plates and the external loads and losses, and (2) the ion current in the electrolyte between the inner surface of the plates. Since the ions (e.g., in a lead-acid battery) in the "inner" ion current may have a m/q ratio very much greater than that of the electrons in the "outer" electron current, clever timing of pulsed signals to the plates may be used to form a phase difference—including even a phase angle of 180°—between the two currents. It can be shown that this forms a high potential on the plates which acts as a negative resistor, extracting EM energy from the vacuum and recharging the battery while simultaneously powering the external circuit. This is the Bedini process, and with Bedini's permission an explanation of that process has been published by Bearden ["Bedini's Method For Forming Negative Resistors In Batteries," **Journal of New Energy**, 5(1), Summer 2000, p. 24-38.] Note that Bedini's process in fact repeatedly removes the Lorentz regauging condition, and therefore the system is rigorously permitted to achieve not only COP>1.0 but also self-powering of itself and its loads and losses.

COLD EXPLOSION

The sudden extraction of EM heat energy from a distant intersection zone (IZ) of the crossing beams of a scalar potential interferometer, which transmits in the sharply pulsed mode, while the electrical grounding of the transmitters are negatively biased with respect to the potential in the distant IZ.

COLD FUSION

An ad hoc term applied to the transmutations at low energy achieved in electrolyte experiments, particularly when using specially prepared palladium electrodes, and particularly when deuterium is present in the electrolyte.

COMPOSITE DIPOLE

Dipole formed as one part of an isolated, observable "charged particle", consisting of a differential element of that observable charge on one end and a momentary clustering virtual charge of opposite sign.

In quantum electrodynamics, it is well-known that virtual charges of opposite signs cluster in the immediate vacuum around any "isolated" observable charge. By applying the composite dipole concept, this author was able to treat the isolated charge as a set of composite dipoles. By then applying Whittaker's decomposition of the scalar potential between the ends of each of these composite dipoles, the "source charge" was a set of broken 3-symmetries in the vacuum flux, and thus a set of 4-symmetries in that flux exchange. This meant that the EM energy continuously output in all directions by the source charge was actually continuously received by the source charge (as a set of composite dipoles) from the time-domain, and 4-conservation of EM energy flow rigorously was upheld.

This allowed a solution to what has been called the most formidable problem in both classical and quantum electrodynamics: the problem of the association of the source charge and its associated fields and potentials along with the energy contained by them and continuously pouring from the charge without any 3-space energy input.

CONCOMITANT

Occurring or existing together.

CONGLOMERATE HIERARCHY OF THE PHOTONS

Every photon remains perfectly ordered! A conglomerate (group) of photons, however, may be arranged in almost an infinite variety of orderings, groupings, directions, etc.—which we refer to as templates and as hierarchies (group orderings) of photons.

In a pure energy flow (energy transport), the "herd" of photons is organized along the flow direction. Regardless of how one scatters or "disorders" this patterning of the "herd" or "hierarchical ordering" of photons, not one single bit of the underlying energy and individual photon ordering is lost. So when one "uses" energy (e.g., scatters the hierarchical ordering of a photon herd from a resistor as heat), one does not lose any energy at all, but simply has "scrambled" the hierarchical ordering of the photons into a new herd configuration (which may be varying every which way!). The point here is the real meaning of the fundamental conservation of energy law: *Energy can neither be created nor destroyed!*

When we "use" one joule of energy to perform one joule of work (say, in a single-pass, scattering), we still have exactly that one joule of energy left, but just in different form (different direction, type, collection or not collected, etc.) It can still do another single pass joule of work, then another, then another, and so on. If we plan things right, we can use a single joule of work to perform many joules of work, contrary to what we were so strongly taught in the *"single-pass, single collection, single dissipation"* examples given to us in university as the "law" of God and electrodynamics.

Note that the conventional work-energy theorem assumes single pass, single collection, and single dissipation of a joule of energy to perform a single joule of work. The point is, *that is not a limitation of nature, but a limitation of a single process! Nature regularly uses a joule of energy to do multiple joules of work, because after one dissipates or scatters the energy the first time, it's still there and later will be intercepted to do some more work.*

Anti-Stokes emission, the Patterson Power Cell, Lawandy's lasing without population inversion, and some gas-filled tubes with anti-Stokes emission are examples of known, validated overunity processes (processes with coefficient of performance greater than unity). These all use multipass, multicollection, multi-dissipation in iterated manner, to increase dipole asymmetry and therefore produce excess extraction of energy from the vacuum. Patterson's unit, e.g., has been independently measured by universities at efficiencies of some 1200 or so. This absolutely does not violate the laws of physics nor the nonequilibrium thermodynamics of open systems far from thermodynamic equilibrium.

CONSCIOUS MIND

The serial processing mind which we normally associate erroneously as ourself. Other to be added.

Mind is time-like, not space-like.

CONSCIOUS MIND (PSYCHOENERGETICS VIEW)

The serial-processing mind which one normally associates erroneously as oneself.

Mind is *time-like*, not *space-like*. Hence it is not directly observable, a priori, since all observation is 3-spatial. However, if we consider that changes in 3-space produce spacetime curvatures and thereby also produce slight changes in the time domain, then iterative coherent spatial changes eventually will produce a change in the time-domain. Consequently, the time-like mind will have a continuing stream of such small but processable time-energy changes from coherent 3-spatial phenomena in its body and the macroscopic (coherent) universe. To sense the 3-space body as "self" while simultaneously sensing other 3-space physical changes as "non-self", the conscious mind must compare the various received time-like projection signals against its "time-like orders" issued. That set of received time-signals that matches or closely matches the conscious mind's issued order signals, thus yields the sense of the body behavioral changes as (1) self, and (2) body responses to its orders. The time delay between issuance of the mind's orders and the receipt of the correlated time-like responses from its body, provides the sense of self-persistence or independent being.

The mind couples to the body via a similar spacetime curvature mechanism. When the mind issues "orders", they are in the time-like realm but are changes, hence small spacetime curvatures. They therefore involve very small 3-spatial changes (projections) into the 3-space body. Since the mind orders are coherent, this small iterative set of 3-space changes will integrate coherently, yielding real quantum changes in the body and nervous system (e.g., the brain).

This coupling mechanism is profound. The steady stream of integrated time-like projections arising in the mind due to the physical world outside one's body, does not compare or match the mind's memory of its orders. Hence that allows the sensing of the "external world" as "nonself". The sense of that external world as "existing" or "being" is provided by the time delay in the comparison process, from "mind signals issued" to "physical signals received". The metric yardstick standard for this comparison time, so to speak, is provided by the time in the identified "self-loop" with the physical body. In other words, the mind uses that length of time to differentiate those time signals which coherently integrate but do not match its issued order signals, from those time-signals which coherently integrate in the same time loop interval and do match its issued ordered signals.

In this manner, we resolve all the great previously unresolved philosophical questions of the nature of consciousness, nation of being, nature of self, nature of nonself, perception of the physical world, perception of body as self, perception of other bodies as non-self, etc. At least we resolve these issues from a testable physics approach, so that we can see that now a unified physics (and a technology) of mind and matter is at last in view. Since O(3) electrodynamics has been shown to be an important subset of Sachs' unified field theory, then O(3) electrodynamics—or SU(2)×SU(2), which is homomorphic with O(3)—can be used to develop the direct engineering of mind, the mind-matter interaction, and mind functions of the living biological system.

It is my considered opinion (with much evidence) that the Russian branch of *energetics*, known as *psychoenergetics*, uses a unified field theory and a higher symmetry electrodynamics to achieve that type of direct engineering already, but for weapons use rather than beneficial use for humanity.

As examples, we strongly suggest that the deaths of U.S. Captains Button, Svoboda, and Hess all involved KGB testing of long-range strategic psychoenergetics weapons over the United States, on those targeted personnel. This should not be surprising at all; the KGB has tested longitudinal EM wave interferometer weapons over the U.S. since 1967, and continues to do so today. They tested bioenergetics EM weapons against U.S. Embassy personnel in Moscow for several decades. Kills of U.S. aircraft and missiles have been performed at various times, including kill of the Arrow DC-8 at Gander, Newfoundland in Dec. 1985, kill of a Titan ICBM fired from Vandenberg AFB in the spring of 1986, kill of the U.S. space shuttle Challenger in the spring of 1986, continuing weather engineering over the U.S. and elsewhere, etc.

That novel electromagnetic weapons have indeed been developed and are being tested world-wide, was confirmed by Defense Secretary Cohen in 1997 as follows:

"Others [terrorists] are engaging even in an eco-type of terrorism whereby they can alter the climate, set off earthquakes, volcanoes remotely through the use of electromagnetic waves… So there are plenty of ingenious minds out there that are at work finding ways in which they can wreak terror upon other nations…It's real, and that's the reason why we have to intensify our [counterterrorism] efforts." [Secretary of Defense William Cohen at an April 1997 counterterrorism conference sponsored by former Senator Sam Nunn. Quoted from DoD News Briefing, Secretary of Defense William S. Cohen, Q&A at the Conference on Terrorism, Weapons of Mass Destruction, and U.S. Strategy, University of Georgia, Athens, Apr. 28, 1997.].

We specifically call attention to the fact that the Secretary did not speak the words enclosed in square brackets. This is *not* limited just to terrorists or counterterrorism.

There appears to be no insurmountable difficulties in developing psychoenergetic technology using the approach outlined above. Certainly it is not as formidable a task as has been hot fusion.

The incident involving Captain Button, e.g., was to demonstrate control of an individual performing complex technical tasks for a period of at least one hour. The test against Captain Svoboda was to demonstrate how simply human kill can be achieved in combat troops, merely by introducing selected changes in the mental functioning of the targeted individuals. As Svoboda was climbing her A-10 out of a successful low-level ordnance drop at night on a ground target, her sense of up and down was instantly reversed. Instantly perceiving she was diving instead of climbing—although *actually* climbing out perfectly—she "corrected" immediately and dove headlong into the ground, perishing in the resulting explosion of her aircraft.

In the case of Capt. Hess, the test demonstrated that rather complete mental control can be almost instantly asserted, and even the responses of the autonomic nervous system can be overridden. So Captain Hess, out for a morning jog, simply went aside, sat down, and stabbed himself repeatedly, including multiple times right through the heart. Had one seen the incident, he would have simply continued stabbing himself very calmly, without emotion or reflex action from his autonomic nervous system, until physical failure of his body.

As can be seen, it is of the utmost importance that this nation understand psychoenergetics weapons of such nature, and develop effective defenses against them. The next great strategic battlefield may be as much a "virtual reality" battle as it is a "real physical world" combat. The war can be quickly lost in either arena.

We also point out that the psychoenergetics weaponry readily is adapted to use in more advanced longitudinal EM wave interferometers, which readily penetrate the Earth and the ocean. Hence deeply buried strategic command and control centers are vulnerable to psychoenergetics warfare, as are the crewmen of our nuclear submarines, ICBMs, aircraft carriers, division and army command centers, national command centers, strategic bomber pilots, etc.

Indeed, one of the major incentives for developing such psychoenergetics weapons as was demonstrated in controlling Captain Button, was to seize and control the entire on-site manning crews of the defensive quantum potential weapons preventing launch of full strategic warfare. By having the QP systems "stood down for maintenance" by their own crews, the major strategic retaliation and "dead man fuzing" would have been removed and countered. Then powerfully striking the QP sites with LWIs would have destroyed them, and left the sites themselves radioactively emitting longitudinal EM waves, thus preventing reoccupation in case the QP weaponry survived. The counter to that scheme was to place the friendly QP weapon sites on "insane" command and control. In that mode, instead of human decision being made to launch, every so often (say, every two hours) the computer automatically initiates the launch sequence. During that sequence, if the crew is still alive and functional, codes can be punched in and the computer cancels the launch initiation. It then repeats the sequence two hours later. If no coded cancellation order is punched in, for whatever reason, the launch sequence completes and the QP weapons fire. In that case, much of Russia disappears from the face of the earth.

Eerily, just about the time that Secretary Cohen was making his quoted statement in April 1997, the KGB was being notified by the friendly little nation of the change to insane command and control. This forced the abortion of a great strategic attack upon the West, scheduled to occur on May 1, 1997.

We are strongly stressing that psychoenergetics is not parapsychology and it is not just an idle theory of academics. Instead, it is already potently used in some very powerful and deployed weapon systems that could well decide the course of the next world war, almost at a moment's notice.

See also discussion under *energy*.

CONSCIOUSNESS

Refers to a living being's awareness of its sensations, feelings, thoughts, and the world around it.

The new approach uses a coupling mechanism between the time-like mind and the body of a living creature. The nature of this coupling mechanism then generates the mechanism by which self-awareness is produced, awareness of non-self is produced, and the sense of existing in the external world but differing from it is produced.

CONTINUOUS MODE

For a longitudinal EM wave interferometer, a continuous mode of operation where power is fed continually to the transmitters, and the two longitudinal EM wave patterns or beams are continuously transmitted.

CONVENTIONAL SCALAR POTENTIAL

A scalar potential formed without use of artificially added substructuring of its internal biwaves and their products.

In other words, one in which it is assumed that its virtual particle flux has no ordering, but is just a randomized flux. This assumption (e.g., of quantum mechanics indirectly) is incompatible by the Whittaker demonstration that (i) a scalar potential is a harmonic set of "bidirectional" EM phase conjugate wave pairs, and thus not a scalar entity at all, and (ii) perfect ordering of its wave components exists inside the scalar potential.

One must carefully distinguish what each of these internal "phase conjugate EM longitudinal wavepairs" actually represents. Prior to interaction with detecting charges, the potential is a 4-potential existing in spacetime (4-space). The time domain, of course, is represented by ict, and in that expression only "t" is a variable. Hence the "incoming" phase conjugate longitudinal EM waves in the imaginary plane are actually longitudinal EM waves in the time dimension. These waves converge upon the dipolarity represented by the "scalar potential" or any "piece" of it. The dipolarity represents the interaction of charges; specifically, a dipole. This reaction—by the spin of the charges—transduces the incoming EM energy from the time-dimension into 3-space, and emits it from the charges as real EM longitudinal EM energy radiating out from the dipolarity in all directions in 3-space.

The phase conjugate half-set of the Whittaker waves, *prior to their interaction with charge*, are not waves in 3-space, but are waves of LW EM energy coming in from the imaginary plane and thus from the time domain. The charges of the dipolarity spin 720°, being 360° in the complex plane and then 360° in real 3-space. So the charges absorb the EM LW energy impinging on them from the time domain, during their 360° rotation in the complex plane. When they enter real 3-space for the rest of their spin, the already-excited charges dissipate their excitation energy in all directions as they spin their 3609º in 3-space. That is what the Whittaker decomposition actually shows, but it has been ignored for almost a century.

In short, the broken 3-symmetry of the dipolarity—well-known in particle physics for nearly a half-century, but never incorporated into CED—allows nature to jump to a higher, more fundamental 4-symmetry in the energy flow. Energy is being conserved in 4-space, but not in 3-space. Further, there is a special new energy flow symmetry involved: one-way in the time domain and the other way in the 3-space domain. Note that energy is not conserved in 3-space! *There is no law of nature requiring the extra requirement that, in addition to conservation in 4-space, the energy must also be conserved in 3-space!* So when the dipole breaks that extra requirement, only the basic 4-conservation applies. In that case, nature very happily gives you what might be called a white hole in astrophysics terms: energy will pour in to the dipolarity unceasingly from the time-dimension, and will pour out in 3-space unceasingly, so long as that dipolarity persists.

By considering the virtual charges of opposite sign that cluster in the vacuum around any "isolated observable charge", one may represent a single charge (as an electron or proton) as a set of composite dipoles, where each dipole consists of a virtual charge (while it exists) and a differential element of the observable charge. So the charge becomes a set of composite dipoles, each with Whittaker decomposition of the scalar potential between its ends.

Hence we have solved the long-vexing problem that Semiz called "the greatest unsolved problem in electrodynamics": the problem of the source charge (or source dipole) and its associated fields and potentials and the enormous EM energy continually pouring out of any charge or dipole in all directions in 3-space.

When the arbitrarily discarded giant Heaviside nondiverged energy flow component is also accounted, this leads to the giant negentropy of the dipole, as shown in my paper, "Giant Negentropy from the Common Dipole". We have also proposed this "dark Heaviside energy" as the unaccounted source of the excess gravity known to be present in spiral galaxies and holding together their arms. The dark energy yields at least 90% of the total gravity involved, and the additional 10% or so can be accounted for my known gravitational sources.

It appears that these new discoveries can also be utilized to show that "quintessence" is also caused by COP>1.0 processes in the universe, and the excess production of negative "giant dark energy flows". If so, then this also would account for the recently discovered fact that the universe has an excess of negative gravitation, so that it is not only expanding but is accelerating in that expansion. At this time, the present author is still attempting to tie up the loose ends involved in showing that quintessence also is created as a result of functions of the giant negentropy process.

In the Whittaker biwave pairs, If one then insists that these hidden EM waves are comprised of hidden photons, then it follows that the photons exist as continually coupling and uncoupling photon/antiphoton pairs, or continually forming and unforming *gravitons* as the wave and antiwave continually pass through each other.

It is a little more complicated than that, since Maxwell actually omitted half the EM energy in the EM wave in space, and also in the circuit—as do electrodynamicists to this day. For gravitons, one really must come to grips with this error and correct it. This will be added later in this glossary. (To be Added).

COOPER PAIR

A dynamic pairing of electrons in superconductivity theory.

In this pair, if the energy state with wave number σ and spin ½ is occupied by an electron, then so is the state with wave number - σ and spin – ½.

COP (COEFFICIENT OF PERFORMANCE)

Ratio of energy out, divided by that portion of the total energy input that is input by the operator or experimenter.

The COP is thus a measure of "efficiency of using the operator or experimenter's input energy" to produce—or direct the production of—useful work. Note that he can direct the use of his own input energy, as almost all our present systems do. Better yet, he can also direct (gate or "switch") the use of some external free flow of energy from the environment into the system, so that he gets lots more work out of the system than he has to put in himself. Only a few of our systems—such as solar cells, sails on sailboats, waterwheels to power mills, and windmills—are such Maxwell's demons (open systems) where the output exceeds the operator's input of energy.

We sharply contrast the term "COP" to the term "efficiency". The efficiency (overall) of a system is how much useful energy output (usually as work, or can be converted to work at will) the system produces for the total amount of energy that is input (both by the operator and by the external environment). Even a highly inefficient system may nonetheless have a COP>1.0, if the operator inputs less energy than the system outputs.

We urge the reader to thoroughly understand the difference between energy-use "efficiency" of a system and coefficient of performance of the system. Many scientists, engineers, and especially free-energy researchers are confused on the precise difference in these terms.

CORPUS CALLOSUM

The thick nerve cable that links together the two cerebral hemispheres (which are separate brains) in each vertebrate (including human) brain.

In each of the two cerebral hemispheres, there is a separate mind and personality (given that the other is separated). However, a brain has a unique characteristic: Anything that arises directly inside it is automatically assumed to be self-originated, since the brain-tuner can differentiate no separation or "separate source" for the signal/thought arising directly upon its "internal screen". This allows integration of the two brains/minds/personalities into one. That is, when one brain half prepares and sends a message, that message is also routed across the corpus callosum into the other brain half, arising internally upon the second brain's "display." The second brain half therefore thinks that it itself originated the signal or message.

COSMOLOGICAL FEEDBACK PRINCIPLE

Puthoff's self-regenerating cosmological feedback cycle for the source of the vacuum EM ZPE.

One may assume the existence of EM zero-point energy (ZPE) by fiat as part of the boundary conditions of the universe, or conceive of its generation by the quantum-fluctuation motion of charged particles that constitute matter. Puthoff calculated the latter possibility, assuming that the ZPE spectrum (field distribution) drives particle motion, and that the particle motion in turn generates the ZPE spectrum. This provides a self-regenerating cosmological feedback cycle, which in fact is consistent with the general relativity assumption that curvature of spacetime affects mass energy, and mass energy changes affect the curvature of spacetime.

The result of Puthoff's calculation is the appropriate frequency-cubed spectral distribution of the correct order of magnitude. His result is thus consistent with, and indicates, a dynamic-generation process for the ZPE fields.

In general this is also consistent with the Sachs' unified field theory approach, and with the Evans O(3) important subset of it.

COURRIER, ROBERT

Noted French scientist who collaborated with Antoine Prioré in his revolutionary healing experiments on laboratory animals using longitudinal EM waves from plasma tubes.

Courrier was the head of the Biology Section of the French Academy and also the perpetual secretary at the time. He personally presented the astounding results of the Prioré work, showing cures of terminal tumors, to the assembled French Academy, creating a furor.

CROSSTALK

In ordinary science, the transfer of energy or signal from one channel to another, by cross modulation or cross coupling between the channels.

In the new approach, the term "crosstalk" can be used in an additional sense where it refers to virtual energy exchange between orthogonal universes or frames—that is, between different 3- or 4-dimensional slices of an infinite-dimensional universe.

CURL CONCEPTS OF FIELDS

Refers to concepts of fields as the curl of some vector potential;

E.g., the magnitude of the **B**-field is equal to the curl of the **A**-potential, given by $\mathbf{B} = \nabla\times\mathbf{A}$. More exactly, the **B**-field is identically a curled **A**-potential, by $\mathbf{B} \equiv \nabla\times\mathbf{A}$, but only that portion of $\nabla\times A$ that is diverged around or collected by an intercepting unit point static charge.

Note that we are accenting that no equation is a definition. So texts stating that the first equation with an equals sign "defines" the magnetic vector potential **A**, are in error. If we state that $\mathbf{B} \equiv \nabla\times\mathbf{A}$, then we are defining the **B**-field as a curled form of the magnetic vector potential, which it is.

The reader must be aware that the field concept itself in CEM is flawed, being "defined" as the effect existing after an interaction by a 4-space entity with a 3-space mass, and hence 3-spatial and an "effect", and yet then used as if it were the 4-space "cause" entity that propagates in 4-space to interact. In short, the field concept is thoroughly confused in the texts and papers in the literature (and has been confused for more than a century) as not only the cause but the result of the interaction of the cause with some recipient. This problem has been highlighted by many physicists, including Feynman, Wheeler, etc.

This "confusion of the cause with the effect" is widespread in physics, and is the single greatest foundations error which hampers the progress of physics. Another example is the false notion that a "separate force" acts upon a "separate mass", when in fact mass is a component of force by the definition $\mathbf{F} \equiv d/dt(m\mathbf{v})$. That such simple and obvious errors have been propagated by so many hundreds of thousands of scientists for so many decades is perplexing. Indeed, the errors simply continue to be used. Note that Nobelist Feynman and the great John Wheeler pointed out that the "field" as defined in CEM does not and cannot exist in spacetime! Instead, Feynman pointed out that only the potential for the field exists in spacetime, in case some charged mass is brought in to interact with it and *thereby produce* the field as an effect.

Indeed, no observable persists, for it "exists" only as a momentary 3-space frozen snapshot or slice of a 4-space dynamic interaction. Here again, most physicists do not realize that observables such as mass m do not and cannot persist other that at the instantaneous frozen moment of the snapshot.

CURL-FREE MAGNETIC VECTOR POTENTIAL

A field-free magnetic vector potential without curl, hence with no **B**-field.

Toroids and long solenoids have the characteristic of separating the **B**-field (curled potential) and holding it inside. However, drawing energy from any potential whose "source charge or source dipole" is not destroyed, simply results in the full value of the potential being replenished from the vacuum, via the 4-symmetry energy flow mechanism in the presence of the broken 3-symmetry of the dipole. Hence one may easily "double" the potential energy density at will, and this is a special form of gauge freedom, where the potential energy of any electromagnetic system can be altered freely and at will. We strongly accent that, contrary to what is in the EM textbook, gauge freedom rigorously allows the direct and free amplification of potential energy of the EM system at will. That this principle, incorporated in gauge field theory, has been known so long and still not used in the design, production, and use of COP>1.0 electrical power systems is quite inexplicable.

In the motionless electromagnetic generator, we used a special core material to extract the curled potential (**B**-field) from a permanent magnet's vector potential **A**, so that **A** is replenished in uncurled form directly from the vacuum via the giant negentropy process.

To achieve COP>1.0, we then simultaneously interacted both the uncurled **A**-potential energy external to the output coil, and the internal curled **A**-potential energy (**B**-field energy) internal to the core through the coil, with the coil. By pulsing, the Lenz law effect is also invoked as yet another momentary regauging and potential energy increase, so that an additional energy gain is achieved.

The well-known Aharonov-Bohm effect proves that the uncurled **A**-potential can indeed be separated from the **B**-field in like manner, and the **A**-potential does interact with electrons since $d\mathbf{A}/dt = -\mathbf{E}$.

Thus the MEG achieves COP>1.0 permissibly, because it is an open system freely receiving excess energy from the active vacuum environment, via the vacuum's replenishment of the magnetic vector potential of the permanent magnet dipole as fast as energy is drawn from it. The MEG also violates the usual closed current loop's self-imposition of Lorentz symmetrical regauging when discharging its excitation energy (its free excess regauging potential energy), because the "source dipole" (the permanent magnetic dipole) is not destroyed.

CURVED SPACETIME (externally, internally)

A four-dimensional geometry used in general relativity, where the curvature is determined by the distribution of mass-energy.

In the new, more extended approach, any change in the spatial energy density of spacetime or any change in the time-energy density of it, or a combination of changes in both. The difference is that in the new approach time is also treated as a special form of energy. Specifically, time may be regarded as spatial EM energy compressed by a factor of c^2.

CYBORG (An acronym for cybernetic organism).

(Noun): A single integrated system consisting of a living system energetically or functionally linked to mechanical or electromagnetic devices and/or systems performing some vital functions.

(Verb): Link, in the sense of forming such a system.

In the new approach, a living biological system may thus be considered a cyborg of its time-like mindworld (mindframe) to its 3-spatial body (laboratory tuner). The "cyborging" is provided by the personal quantum potential and by the mind-body coupling mechanism. Due to the giant negentropy mechanism of any dipolarity, any scalar potential as a dipolarity is a cyborg between observable reality and virtual state (time-like) reality, i.e., between 3-space and the time-domain.

CYTOMEGALOVIRUS

Any of several members of the herpesvirus family that cause infected cells to enlarge and/or to form cytoplasmic (the protoplasm of a cell, external to the nuclear membrane) inclusions in leukocytes (white blood cells), particularly in their nuclei.

Cytomegalovirus makes a protein that appears to disable the p53 protein. As a result, smooth muscle cells in blood vessels can proliferate until they impede blood flow.

CYTOPATHOGEN

Literally, a pathogen (disease causing organism—or extended, mechanism—) that affects cells and generates damage in them.

CYTOPATHOGENIC

Damaging, harmful, or destructive for cells.

CYTOPATHOGENIC EFFECT

The generation of damage, disease, death, or other symptoms at the cellular level in cells that are exposed to or subjected to a pathogen.

CYTOPATHOGENIC MIRROR EFFECT

Distant EM pathogenic effect noted by Kaznacheyev in thousands of military experiments, where cellular death, disease, and damage forms are shown to be transmitted from one cell culture in the dark (absence of visible light) where the changes are induced, to another similar targeted cell culture in the dark that is environmentally shielded from the first except for light transmission in the infrared and in the ultraviolet. After exposure begins, after a time delay (say, 2 hours or more), the cells in the targeted cell culture will begin to exhibit the same symptoms as the culture having the induced damage. Eventually, in most cases the targeted cells will develop the same damage, disease condition, or death. The effects vary with the time of day etc.

The necessity for photon connection from IR to UV is shown by contrasting a thin quartz window allowing the light transmission with a thin window glass window. The quartz is open from the IR to the UV, and will pass that entire spectrum. With the visible light absent, the IR and UV biophotons emitted by the damaged cell culture will pass through the quartz window into the targeted cell culture. After the time delay, the targeted cell culture starts developing the condition.

Use of a thin window glass window, however, prevents the effect. Normal window glass is opaque in the IR and in the UV, and so it blocks the transmission of the IR and UV biophotons.

The UV is a harmonic of the IR, arranged properly. An unusual effect exists when two sine waves one the first harmonic of the other, are simultaneously transmitted into an isotropic nonlinear medium, such as water. On each sine wave, the peak travels faster in the water than off-peak parts of the wave does. Hence the wave peaks overshoot its middle, the wave collapses, breaks up, etc. Both the waves of the transmitted harmonic set do that. However, if one pretends that one transmitted the difference frequency between them, and not the waves themselves, a strange phenomenon results. Regardless of the breakup of the primary harmonic set, the difference frequency travels through the water as if it were a real frequency in a linear medium. This effect has been proven and is used in underwater sonar equipment.

For example, see Owen Flynn, "Parametric arrays: A new concept for sonar," **Electronic Warfare Magazine**, June 1977, p. 107-112. Any two sine-wave frequencies as simultaneous drivers combine to produce a sine-wave difference frequency propagating in water, essentially without sidebands or reverberations. Its pattern has a main lobe approximately equal to that of the high frequency drive, but devoid of sidelobes. The level of the propagating difference frequency is proportional to both the product of the two fundamental drive levels and to the square of the desired value of difference frequency.

Living cells contain a great percentage of water. Hence the effect should apply to those targeted cells, under the conditions stated.

From general relativity, we know that any pattern and dynamics of mass-energy, such as in a cell and all its parts and dynamics, directly interacts with local spacetime to curve it, and any set of curvatures of spacetime interact with any conglomerate of mass-energy and its parts and dynamics. The set of precise curvatures and their dynamics we call an engine. In a mass embedded in a local region of spacetime containing an engine, the engine will interact with the mass-energy to change it if the mass-energy and its dynamics do not "fit" the engine and its dynamics.

In a diseased, damaged, or dead cell, the mass-energy of that cell and its "template" (form and dynamics) differs from its template while the cell was living and normal. Let us now see what happens when that dead cell emits a biophoton.

A photon emitted from a dielectric such as a damaged cell, is not emitted just from one spot. Every part of the dielectric participates in the emission of that photon. (See "porthole concept", to be added). Further, each emitted photon contains in its scalar potential and its magnetic vector potential, the exact longitudinal EM waveset that constitutes the vacuum engine of the damaged cell that emitted it. When a cell absorbs a photon, it absorbs that vacuum engine carried by the photon also. If it absorbs a stream of photons of harmonic interval, the difference frequency constitutes in terms of a wave, traveling through the cell water as if in a linear medium, and transporting that vacuum engine to every part of the absorbing cell dielectric.

So the biophotons emitted from Kaznacheyev's damaged, diseased, or dying cells sent biophotons containing the exact spacetime curvature engines and dynamics of their precise condition (template). Further, a harmonic interval of such radiation is transmitted into the targeted cells, and absorbed. The mixing of the two absorptions eventually is sufficient to establish the harmonic interval, thus with a clear EM signal difference that travels through the cell's water and to every tiniest part of it. This "difference frequency clear signal" also contains the pure vacuum engines of the template of the changes in the diseased, dying, or damaged emitting cells.

The result is the "kindling" (coherent integration) of the template in the absorbing cell's local spacetime in which it is embedded. As that spacetime engine grows, it differs from the resident engine of the absorbing cell. That difference is itself an engine, and it operates steadily upon that absorbing cell to alter its engine and then its physical condition and state.

As the new engine continues to interact, the physical cell is gradually changed into an equilibrium condition in its mutual interaction with its local spacetime engine. That occurs after the absorbing cell has developed the same disease, damage, or dying condition as the transmitting cells.

This is the secret of the Kaznacheyev experiments. The Kaznacheyev work was allowed to be released in the open literature to stimulate the U.S. scientific and intelligence communities and see whether or not the scientists and analysts had applied a unified field theory and higher symmetry electrodynamics to the EM bioeffects problem. The totally casual reception of the Kaznacheyev experiments in the West, with no interest or interaction from the stimulated communities, assured the KGB conclusively that the West was still in kindergarten in its knowledge of EM bioeffects, and particularly had little or no knowledge in the field of EM biological warfare.

Kaznacheyev referred to the effect as the "cytopathogenic mirror" effect, for the pathogenic effects from the emitting damaged cells being "mirrored' in the targeted cells.

See Vlail Kaznacheyev and L. P. Mikhailova, **Ultraweak Radiation in Intercellular Interactions**, [in Russian], Novosibirsk, 1981. An English exposition of much of the Kaznacheyev work is given in Vlail Kaznacheyev, "Electromagnetic Bioinformation in Intercellular Interactions," **Psi Research**, 1(1), Mar. 1982, p. 47-76. See also Vlail Kaznacheyev, "Apparent information transfer between two groups of cells," **Psychoenergetic Systems**, 1(1), Dec. 1974; Vlail Kaznacheyev *et al*., "Distant intercellular interactions in a system of two tissue cultures," **Psychoenergetic Systems**, 1(3), Mar. 1976, p. 141-142. In the same issue, see "A Comment" by William A. McGarey, p. 143; "A Comment" by Arthur C. Hastings, p. 143-144.

Seven or eight nations now have longitudinal EM wave interferometer weapons, capable of beaming right through the earth and ocean to the other side of the planet. At least two of these nations—Russia and China—are capable of adding engine structures to these interferometers, and sweeping a targeted population area to generate that specific disease condition in that target. A sophisticated use would be to have agents (such as terrorist teams already in the United States and with biological agents in hand) release a small quantity of smallpox in the area previously targeted. The LWIs have swept the entire area continuously for a period, slowly kindling (especially at night) the exact form of the disease within the bodies of the populace. A curious thing happens if the level of kindling of the smallpox state has been kept just beneath the observable state, within what is sometimes called the "shadow state" (just barely virtual). A smallpox pandemic will explode in that populace with a ferocity never seen in modern times, and at an unparalleled rate. This is further exacerbated by "spreading the immune system" prior to the attack (term and discussion to be added), which seriously weakens the immune system's ability to resist any single pathogenic attack.

There are hardly any supplies of smallpox vaccine left that are viable. Even where there are, the Russian laboratories developed strains of smallpox resistant to the normal vaccine, and after the collapse of the Russian economy and the former Soviet state, these strains were sold on the black market to the highest bidder. Further, most of the Soviet scientists employed in those secret biowar facilities wound up employed in several other nations, most hostile to the United States.

The point is this: Such a strike could in fact kill up to 2 billion people worldwide. Further, the entire affair would appear to be just a chance breakout of smallpox, and its spread through a nonresistant world populace.

When modern biological warfare is actually analyzed in detail, the "bang for the buck" is greater than it is for nuclear weapons. Further, a rogue or hostile nation can take its time in advance and develop quantities of smallpox vaccine (for the very strain it will use), then initiate such a clandestine campaign after it has vaccinated its own populace, armed forces, and agents. Guess who survives after such an attack.

CYTOTOXIC

Toxic (acts as a poison or toxin) to cells.

A *toxin* is a colloidal proteinaceous poisonous substance that is a specific product of the metabolic activities of a living organism. The toxin is usually very unstable, and is notably toxic when introduced into the tissues.

DARK ENERGY

The Heaviside nondiverged energy flow component, surrounding every field/charge and potential/charge reaction but unaccounted in present electromagnetic theory after being arbitrarily discarded by Lorentz.

DATUM

Consideration, or data considered, or information considered, or action considered, or result considered.

DEATH

The disintegration of the personal quantum potential's connection to the physical body's atomic nuclei by loss of the mind-body connection mechanism.

Simply put, separation of the quantum potential containing the time-like mind-frame from the body. Loss of the preferential tuning of a physical body to its mindworld. This causes loss of the preferential consciousness loop or life channel, resulting in "death" (reversion to inert matter) of the body. Actually the quantum potential and the mind-frame remains, so the *being* is unchanging and indestructible, hence consists of all changes and destructions simultaneously, with none separated individually. Life and death thus are two sides of the same coin, and the coin is immutable, regardless of which side is exposed.

DE BROGLIE WAVE

A matter wave, conceived by Louis de Broglie.

The quantum mechanics wave associated with a particle of matter, which can give rise to interference effects. An orbital electron in an atom is associated with a standing de Broglie wave on a Bohr orbit. De Broglie waves always move faster than the speed of light, the speed being given by c^2/v, where c is the velocity of light in vacuum and v is the velocity of the particle of mass. De Broglie wave velocities thus vary from the speed of light to infinite speed (everywhere at once). In his speech accepting the Nobel Prize, de Broglie emphasized that, since these waves produce real physical effects, they are real and must not be regarded simply as mathematical conveniences.

DEBYE, PETER

Dutch-born American physical chemist and Nobelist, 1884-1966, who performed important and fundamental studies in bipole moments and diffractions of X-rays and electrons in gases.

DEDIFFERENTIATION, CELLULAR

The reversion of a cell or cellular structure to a more primitive or generalized condition.

Dedifferentiation is often preliminary to a major change in the cell or cellular structure. It can also be a reversion of the cell to a previous—even *primeval*—cell form. The important point is that dedifferentiation returns the cell to a previous (past) cellular state. Reversion of a cancer cell, e.g., would cause the cell to return to a normal cell, since that is the nature of its "cellular past." It is vitally important that Becker has demonstrated that cells can be differentiated (moved forward to a future state) or dedifferentiated (moved backward to a previous state) electrically, by very weak DC currents (picoamperes). He was nominated for a Nobel Prize for this epochal work.

Actual electromagnetic redifferentiation of terminal tumors in laboratory animals was repeatedly demonstrated by Prioré et al in the late 60s and early 70s and reported in the peer-reviewed French medical journals, as was reversion of depressed immune systems, cures of infectious diseases, and curing of arteriosclerosis. It is inexplicable that this positively demonstrated cure of cancer—which could also cure infectious diseases and probably can be developed to cure AIDS—was suppressed in the mid-70s and has not been vigorously pursued by present establishment medical science.

DEGENERATE SEMICONDUCTOR

A semiconductor whose conductivity approaches that of a metal.

DELGADO, JOSE M. R.

Noted Spanish neurophysiologist well-known for his research on brain behavioral mechanisms and their control by electrical stimulation; who implanted electrodes in the brains of animals and humans and demonstrated that their responses (both behavioral and emotional) were specific and depended upon the specific localized part of the brain that was stimulated.

A TV tape made by Delgado showed a spectacular demonstration where he stopped a charging bull in mid-stride. With a small hand-held radio transmitter, he transmitted a radio signal to a receiver implanted in the head of the bull. This dramatic demonstration caused a world-wide sensation.

The significance of his work is given by Becker: *"Delgado discovered the exact parts of the brain in which electrical stimulation produced fear, anxiety, pleasure, euphoria, or rage in human subjects. He found that certain sites produced major personality alterations. For example, stimulation of one such site could cause very proper, reserved young ladies to become flirtatious and sexually aggressive. Other sites inhibited maternal or aggressive behavior. In short, Delgado was able to profoundly alter human behavior through electrical stimulation of discrete areas of the brain." … electrodes were implanted in the pleasure centers of rats' brains. The animals were provided with two levers to press. One of these delivered food, and the other produced electrical stimulation of the pleasure center. Invariably, the rats chose to press the lever that stimulated the pleasure center, even to the extent that they died of starvation*." (Becker, **Cross Currents**, p. 221-222).

It is known based on a rare OMNI interview that Delgado progressed to detailed study and experimentation for the behavioral and emotional effects in monkeys of specific magnetic field frequencies on monkeys. These successful experiments involved electrical currents produced in the brain but hundreds of times lower in intensity than those required for direct electrode stimulation. Since then, some information has been cautiously released from Western military studies showing that microwave pulses can couple to the central nervous system and produce stimulation and behavior alteration similar to Delgado's released experimental results.

Comment: The ultimate and most refined techniques in the field of electromagnetic control of human behavior, volition, emotion, etc. is provided by Russian psychoenergetics, the military version of which is totally under KGB control. This work has progressed far beyond what Delgado and Becker were discussion so long ago. The use of the infolded longitudinal EM waves and "engines"—once the technology is developed—allows direct engineering of conscious and unconscious mind, memory including short term and long term, perception, awareness, etc. The additional advantage of using EM longitudinal waves is that mass is largely a very thin dispersion of particles, with (relatively speaking) very large distances between them, somewhat like the solar system but on different scale. This "inner space" is filled with EM waves, potentials, and fields—all of which decompose into sets of longitudinal EM waves and their impressed dynamics. Thus the earth and ocean are readily penetrated by longitudinal EM wave beams, and the Russians (KGB) has developed such LW interferometers since the mid 1950s. However, by LW interferometry where the patterns and dynamics of the carried LWs are engineered, any desired mapping pattern of precise EM signals, frequencies, phases, and magnitudes can be reproduced in distant interference zones, reaching right through the ocean. These interferometers could localize the distant interferometry into a 6-inch diameter volume as early as 1985, so from that time forward it gradually became possible to perform all of Delgado's "inserted electrode" EM stimulus in a single selected human brain from the opposite side of the earth. So approximately 1985 is when I would estimate the beginning of the "golden age" (ugh!) of distant psychoenergetics was initiated.

By 1997, this development would be into at least third generation weapons, just being deployed or just having been deployed, considering an somewhat accelerated weapons development program where 6 years is one generation. By 1997, very complex individual behavioral and perceptual control should have just arrived in on-site deployed strategic weapons systems. See discussion under *conscious mind*.

Some selected useful references are: J.M.R. Delgado et al., **Journal of Anatomy**, vol. 134, 1982, p. 533 reports that developmental defects occur in chick embryos exposed to various ELF frequencies. See also J.M.R. Delgado, **Physical Control of the Mind: Toward a Psychocivilized Society**, Vol. 41, World Perspectives, Harper & Row, New York, 1969.

DEMODULATION

From a carrier containing a modulated signal, recovering the signal that was used to modulate it.

DENSE SIGNAL ENVIRONMENT

For our purposes, when the number of weak EM signals crossing one square meter per second reaches 200,000.

At 500,000 important nonlinear optical type effects of significance—particularly long term cumulative effects—begin to occur in the exposed biological organism.

DEPARTING ORTHOROTATIONS

In space of dimensions greater than four, the rotating of an object or entity away from its line of motion, in the direction of a dimension at right angles to the line of travel in the observer's three-space, by some number of additional 90° rotations.

The Lorentz transform in special relativity, e.g., is just a formula for this kind of rotation. What we call "velocity" is actually a measure of rotation. In 4-space, any object in 3-space can only rotate "out" of 3-space in one direction: toward the time-axis. As the object rotates toward that time-axis, we see the object as having a velocity in 3-space, and its "length along the line of motion" as having diminished. When the object rotates the full 90°, its "length along the line of motion" has been converted to "time" rather than length. Hence it has zero length along the line of motion and is moving at c, the speed of light in ambient space. It is also no longer material, but is a sort of flat plane surface moving at speed c in a direction perpendicular to the plane.

In that 4-space model, it is impossible for anything to move faster than light speed. So Einstein's postulate dealing with the fact that it is impossible to translate mass, signals, etc. faster than light speed has a built-in assumption that only one orthogonal departing rotation can be made from 3-space. That postulate need not apply at all if more than one departing orthorotation is permitted—which of course requires a space of 5 dimensions or greater.

The notion is that, if we allow a spacetime of greater than four dimensions, by continuing to rotate ever more orthoturns in a departing direction away from the original line of travel, the rotated object loses one observable dimension for every orthorotation. Hence with three "departing" orthorotations it becomes a "nonobservable point" to the normal observer, but one that would be moving at speed c^3. A single orthorotation would make the 3-dimensional object a two-dimensional plane moving at speed c.

No matter how many rotations are made in a departing manner, the object is still connected to the time dimension common to all dimensions (assuming only a single time dimension for simplicity). So it exists in an orthorotated space, but in the same time. To the physical observer in 3-space, it thus appears to be a "time-like" or "mental" object only. Nonetheless, by affecting the density and structuring of the time domain, it can have an effect on a 3-spatial object. We discuss that mechanism under the subjects of the mind-to-body coupling mechanism and the body-to-mind coupling mechanism. Further, with the Sachs-Evans unified field theory approach, the time-domain can be directly engineered. This means that both "inert" or physical reality and time-like or "mental" reality can be directly engineered by novel electrodynamic means.

In short, a photon is just a particle (such as an electron) that is orthorotated once (toward the time axis). In photon emission, a little bit of the mass-energy turns into orthorotated photon energy. In photon absorption, the absorbed photon energy turns back into mass-energy.

The higher dimensional orthorotational concept was originally formed to allow a physical modeling grasp on a "mental" object as compared to a "physical" object, and to have a connection mechanism between the two. Such an approach can be used to model both mind and matter, their interaction, etc. The present author has used it to solve the old philosophical problem of "intent", of how the perception of self is attained, how the external world is perceived separate from self, etc. A model for both living and nonliving states does emerge.

This or a very similar approach has been used by the Russian's highly classified weapon science called *energetics*. That third branch of energetics is called *psychoenergetics* and it is the physics of directly engineering mind states, mind operations, memory, etc. by extended electrodynamic means. We have previously detailed much of this work privately, but with some detailed openly in a few papers. E.g., see T. E. Bearden, "Mind Control and EM Wave Polarization Transductions, Part I", **Explore**, 9(2), 1999, p. 59; Part II, **Explore**, 9(3), 1999, p. 61; Part III, **Explore**, 9(4,5), 1999, p. 100-108.

DESTRUCTIVE INTERFERENCE

When two waves or wavesets from two different sources superpose to produce a combined waveset that has a lower intensity than the sum of the intensities of the two original waves.

DETERMINISTIC PATTERN OR TEMPLATE

The exact arrangement, by plan and deterministic action, of a group of entities.

E.g., of the photons in a "herd" or "group" of them. Or a set of spacetime curvatures, into a dynamic structure called a "spacetime curvature engine"—or "engine" for short. Or by the virtual photons in the vacuum flux, or a deterministic set of changes to that vacuum flux (the vacuum flux that is called the "vacuum potential." I have called this function—of a deterministic patterning or templating of the virtual flux (particle view) of the potential—*dimensioning* the potential.

DIELECTRIC

Literally, "against electric (current),"

...originally coined to mean "opposes the flow or conduct of electric fluid."

In today's language, a dielectric is a non-conducting material used to oppose or prevent the flow of electric charges. Even empty vacuum exhibits some dielectric resistance. "Dielectric" is also used to refer to a nonconducting material (often used between the metal plates of a capacitor or elsewhere) which can (i) sustain a change in potential across a distance (i.e., an **E**-field), and (ii) serve as an insulator. Space itself is a dielectric, or at least it is said to exhibit certain dielectric qualities.

DIFFERENTIATION, CELLULAR

(1) specialization of body parts or organs in the evolutionary process. (2) modification of different parts of the body to perform particular functions. (3) modification of the cells forming these body parts or organs so as to perform the necessary cellular functions required to support the functioning of the body part or organ.

DIFFRACTION

The bending of light at the edge of an opaque object.

Usually diffraction introduces undesired distortion and is a problem. However, it can be useful and desirable—for example, in a diffraction grating.

DIMENSION

A certain primary geometrical physical attribute, such as length, used to describe the separational relationships of physical phenomena.

The degree of that separation is known as "length", "time", etc. By "geometrical" we mean that the "dimension" is considered to "exist" in either the presence or absence of the observable physical phenomenon; however, by understood agreement the dimension itself is not directly observable. It can be inferred ("measured"), however, by comparative operations of simple devices such as clocks and meter sticks, and its simplistic definition is usually given as "that which has measurable magnitude." Prescribed measuring procedures are used to assign magnitudes to these inferred dimensions, using specific scales.

Actually, "dimension" just means "fundamental quantity of separation" and "geometry" in the most general sense. The number of dimensions taken in advanced physics usually represents a somewhat arbitrary choice for good modeling fit. In modern Kaluza-Klein theory, for example, it becomes necessary to accept some 10 or 11 dimensions in the usual particle physics case. General relativity has incorporated the interaction of the abstract geometry (spacetime) with mass. Until Sachs' extension of Einstein's work into a unified field theory and Evans' incorporation of O(3) electrodynamics as an important subset of Sachs' unified theory, general relativity has largely remained a nonexperimental discipline, at least in the laboratory. With the new Sachs-Evans approach, however, GR becomes substantially engineerable by novel electromagnetic means, including in the laboratory and in devices.

DIMENSIONING

This is an artificial term I sometimes use to mean "forming an exact pattern or 'template', particularly of nested curvatures of spacetime, where the pattern/template may also be dynamic. It involves the internal structuring of the "dimensioned" entity.

The use of the term "dimensioning" makes sense in unified field theory, but is awkward in normal EM theory which erroneously considers that EM energy propagates in an uncurved spacetime. The mere presence of a change in local spatial energy, created by the wave energy itself when present in that local region, curves the local spacetime. Hence the EM wave rigorously travels in curved spacetime, and in fact identically is a propagating, oscillating curvature of spacetime.

Dimensioning also implies a deliberate form or structure (with dynamics) created in the virtual photon flux of the vacuum or of the virtual photon flux comprising a scalar potential, or in the infolded longitudinal wave EM inside all EM potentials, fields, and waves. It implies an associated set of spacetime curvatures and their dynamics. The latter are referred to as "engines", "vacuum engines", "spacetime curvature engines", etc.

Dimensioning potentials or signals or carrier waves also involves adding hidden *vacuum engines* to them. I chose the descriptive term *dimensioning* because adding such templates (hidden vacuum engine structures) is equivalent to increasing the EM topology by adding dimensions. Since an EM wave or field or vector potential can be decomposed into two scalar potentials, then by "dimensioning" one or both of the scalar potentials one can "infold" the desired hidden structures or patterns (vacuum engines) inside an EM carrier wave, EM field, or vector potential. So I called this *dimensioning* those entities. Internally structuring the two scalar potentials via arrays of EM LW emitters, and then applying the necessary dynamics (modulations), is primarily the manner in which dimensioning can be directly engineered. When dimensioning is present, two identical EM waves as seen on the oscilloscope may have dramatically differing internal structures (dimensioning), and hence the two will produce drastically differing effects when they interact with the same or similar objects. This of course is the mechanism involved in the Kaznacheyev experiments and in the decades-long microwave radiation of the U.S. Embassy in Moscow, where health changes and diseases were electromagnetically induced in personnel in field-free (stable and nonchanging potentials) areas.

Russian energetics refers to what we are calling "dimensioning" simply as adding *the information content of the field*. A very skilled disinformation program (actually, a strategic deception program) has been used to deceive the West into believing the phrase refers to ordinary spectral analysis. It doesn't. The importance of the dimensioning concept is that one has not formed mere "signals," instead, one has formed *vacuum engines*. If a receiving object receives a signal, it may or may not act upon that "signal information." If it receives a *vacuum engine*, however, the engine (structured local spacetime flux) directly acts upon it to make the requisite change. Further, the energy for the interaction's working upon the exposed object or system is furnished continually from the curved spacetime set and their dynamics. The receiving object has absolutely no choice in that action occurring to it, and the action can occur from the gluons and quarks inside the charges in the nuclei, to the lattice structures, to the system dynamics, to the elements so as to transmute them, etc.

Note that when a dimensioned EM field or potential is absorbed by an object, that object also has internal EM fields and potentials which have substructures (usually rather random). However, the internal structure of the absorbed dimensioned entity and the internal structures of the EM fields, potentials, and waves do mix in a direct diffusion process. Hence with continued irradiation, the target can be "charged up" with the desired internal dimensioning structure. This is how the microwave irradiation of the U.S. Embassy accomplished disease induction, using signals with the desired disease dimensioning impressed in their structures, particularly in the potentials. In the Gulf War Disease, a much more sophisticated use of this mechanism was made, using a quantum potential as the carrier. All the effects (including the body fluid transmission, the EM fields of the body transmitting and kindling some of the effects in children in proximity to a dimensioned veteran parent, can be explained.

The use of dimensioned EM fields, waves, and potentials—and the use of dimensioned quantum potentials in Bohm's hidden variable theory—allows an entirely new science of EM biological warfare, far more threatening and lethal than the more primitive physical pathogenic kind. It is also possible to use the techniques for revolutionary healing, as unwittingly shown by Prioré and the scientists working with him, and also as shown by Becker *et al*.

The only way in which the action of a vacuum engine (dimensioned carrier entity) can be resisted is to create and simultaneously introduce the exact antiengine for it.

Once the action has been completed in the receiving object and it has been changed, the only way it usually can be undone is to form a precise antiengine for that action, amplify the antiengine, and let the antiengine act upon the object for a sufficient time to "time reverse it back to its previous physical state and condition". The Prioré mechanism utilized that method for reversing the cellular damage due to cancer and infectious diseases, and to restore suppressed immune systems. The same mechanism, if re-developed, could also be used to reverse aging in living human patients.

The engine and antiengine processes can also be applied by structuring the "time-charging" or "time-excitation charging" of the particles of mass in a body. The "port-hole" concept even allows ordinary EM radiation to be used to forcibly transduce the input ordinary EM into the extraordinary EM and thereby forcibly accomplish the necessary time-charging actions for disease and body deterioration reversal. See discussions under "port hole concept" and "time-charging".

DIPOLE

In the simplest case, two separated charges of (usually equal and) opposite sign.

As a general definition, a localized positive charge or charge distribution, and a localized negative charge or charge distribution, such that the net charge summation is zero, but wherein the positive and negative charge distributions do not superpose. We point out, however, that in regular physics *electrical charge* has no proper definition. Try looking it up in several physics dictionaries! Then check our proposed definition of electrical charge. As is well-known in particle physics, a dipole is a broken symmetry in the virtual photon flux of the vacuum. By definition of broken symmetry, this means that *some* of the virtual energy flux continuously absorbed from the seething vacuum by the charges of the dipole, is not re--radiated as virtual energy. Instead, it is integrated coherently and re-radiated in 3-space as real emitted EM energy. The dipole is therefore a true "negative resistor" since it receives EM energy in unusable form, and re-emits it in usable form. In classical EM theory, the problem of how every charge and dipole can continuously emit EM energy to form all the associated fields and potentials and their energy, is an unsolved problem—sometimes called the most pressing problem in electrodynamics, both classical and quantal. For the solution and a discussion, see my paper "Giant Negentropy from the Common Dipole," Journal of New Energy, 5(1), Summer 2000, p. 11-23.

Because of the broken 3-symmetry of the dipole, the EM energy flow is not conserved in three dimensions (symmetry represents a conservation law, and broken symmetry represents the violation of that conservation law—in this case, violation of conservation of 3-space EM energy flow). Instead, EM energy flow is conserved in 4-dimensions, and the hidden inflow of EM energy to the dipole is actually from the complex plane (time domain). Thus all EM energy is actually received from the time-domain, and so the importance can be seen of the internal structuring of time-flow and of longitudinal EM waves in the time domain. Such time-domain energy flows appear naturally in O(3) electrodynamics; see M. W. Evans and T. E. Bearden, "The Most General form of the Vector Potential in Electrodynamics," **Optik** (in review).

DIRAC, PAUL A. M.

Noted English physicist, 1902-1984, who shared the Nobel Prize for developing wave mechanics and predicting the existence of the positron.

DIRAC SEA

Considering the vacuum as containing—amongst other things— a "sea" of an infinite negative energy conditions or states ("holes") for electrons, almost all of which are filled with electrons.

In Dirac electron theory, the relativistic wave equation for the electron has four components, which correspond to two spin orientations and two energy conditions: positive and negative. Thus the vacuum possesses a "sea" of negative energy conditions for electrons. These are called "holes" and are considered to ordinarily be filled or mostly filled with electrons which have fallen into these negative energy states. The Dirac sea thus is this vacuum sea of negative energy electrons. In forward time, if energy is added, electrons can be lifted from this sea. If spacetime is locally curved, additional holes may be created so that normal positive energy electrons fall in and disappear, creating the appearance of an "electrical energy sink." If the curvature is in the opposite direction, electrons may be lifted from the Dirac sea by the curvature, thus producing a flow of electrons and creating the appearance of an "electrical energy source."

DISCRETIZED

Occurring in a finite size, fixed as a function of one or more variables.

So long as the same value(s) of the variable(s) are selected, the discretized entity is always the same size. However, if the value(s) of the determining variables are changed, the value of the discretized quantity may change so that it is not a whole number multiple of the former entity. Compare this to a quantized entity, where the values of the variable(s) are held to those wherein the entity will always be a multiple of an entity of fixed size.

DISEQUILIBRIUM

Broken equilibrium, which in turn involves breaking appropriate conservation laws.

DISSOCIATION

Separation of ideas from their affects or feelings, resulting in independent functioning of these components of a person's mental processes.

Simply put, fragmentation of the mind and personality. Severe dissociation is the definition of insanity.

DISTORTION CORRECTION THEOREM

"If a scalar wave E1(r) propagates from left to right through an arbitrary but lossless dielectric medium, and if we generate in some region of space [say near z = 0] its phase conjugate replica E2(r), then E2 will propagate backward from right to left through the dielectric medium, remaining everywhere the phase conjugate of E1."

Quoted from Amnon Yariv, **Optical Electronics**, 3rd Edn., Holt, Rinehart and Winston, New York, 1985, p. 500-501.

What is missing from the distortion correction theorem is hidden in the phrase *"if we generate in some region of space ... its phase conjugate replica.."*. Since electrodynamicists and optical physicists have been unaware that all EM energy at any point in space comes from the time domain to that point, then the actual phase conjugate wave in the imaginary plane (from the time domain) is not utilized as the phase conjugate replica. Instead, the interaction of that wave with charges, which actually produces the force-field wave in space, is assumed. In short, one is looking at the "effect" wave, not the "cause" wave. However, since time is not an observable even in theory, it is this "effect" wave in 3-space that will be measured by our instruments.

Note also that the distortion correction theorem says nothing about longitudinal EM waves in the time domain. Interestingly, in nonlinear optical pumping, it appears that the 3-space energy of the pumping 3-space waves is transformed into the time domain by the pumping, and thence flows from the time domain into the 3-space domain to form the progression of the time-reversed replica wave in 3-space.

It is apparent that much more work should be done upon the foundations of phase conjugate optics, in a higher symmetry electrodynamics model such as O(3) electrodynamics and particularly in the unified field theory as in the Sachs-Evans combined approach.

DNA (DEOXYRIBONUCLEIC ACID)

Nucleic acid that constitutes the genetic material of cellular organisms and also certain viruses.

DRUDE, PAUL

Important German physicist, 1863-1906, who formulated the theory of the free electron gas inside conductors, using it to formulate a theory of metallic resistance.

DRUDE ELECTRON GAS

The "free" electrons that have broken loose from their atoms in a conductor, and are thus free to "wander around" and "migrate"—or flow as current when exposed to an emf.

Also called the electron gas, or Drude electron gas. Named after the German physicist Paul Drude who died in 1906, who formulated Drude's theory of metallic resistance based on EM theory and his own theory of electrons. See P. Drude, Ann. Physik, Vol. 1, p. 566; Vol. 3, 1900, p. 370, 869 for the original Drude papers.

DUALITY PRINCIPLE

In quantum mechanics, the principle that photons and other particles propagate like waves and interact like particles, so that their descriptions as only waves or only particles is inadequate.

ECM

Electronic Countermeasures.

Electromagnetic measures taken against targeted electronics or electromagnetics operations in systems, particularly in hostile weapon systems, command and control systems, etc. There are entire textbooks in the West that are devoted to ECM effects, uses, effectiveness, etc. A great deal of ECM equipment is also used by any modern military force. However, in our view what is greatly lacking as yet in Western ECM is the deliberate design and use of novel new kinds of ECM based on the extended higher electrodynamics such as O(3) electrodynamics, and particularly by use of longitudinal EM waves and by use of the infolded electrodynamics inside all EM fields, potentials, and waves. Longitudinal EM wave interferometers (LWIs), e.g., can reach right through the earth and the ocean to emerge on the other side of the earth. In the interference zone (IZ), real EM "transverse wave" energy is created readily by the interferometry. Biasing of the chassis grounds of the distant LWI transmitters can control whether the "normal" EM energy appearing in the target IZ is convergent (cooling) or divergent (heating). By sharp pulsing of the LWI transmitters, massive cold explosions or hot explosions can be created in the IZ. Continuous LWI interferometry can produce geometric forms of EM energy, which usually glow due to the ionization of the atmosphere, etc. in the dense EM energy regions. Since these can also involve general relativistic effects as well as electromagnetics effects in the U(1) CED sense, obviously a dramatic expansion of the entire field of measures and countermeasures is entailed.

We believe these LWI weapons may be what was referred to by U.S. Defense Secretary Cohen as follows: *"Others are engaging even in an eco-type of terrorism whereby they can alter the climate, set off earthquakes, volcanoes remotely through the use of electromagnetic waves… So there are plenty of ingenious minds out there that are at work finding ways in which they can wreak terror upon other nations…It's real, and that's the reason why we have to intensify our efforts."* Secretary of Defense William Cohen at an April 1997 counterterrorism conference sponsored by former Senator Sam Nunn. DoD News Briefing, Secretary of Defense William S. Cohen, Q&A at the Conference on Terrorism, Weapons of Mass Destruction, and U.S. Strategy, University of Georgia, Athens, Apr. 28, 1997.

EDGE WAVES

In electromagnetics, waves that form parallel to a material edge.

EDISON, THOMAS ALVA

Noted American inventor, 1847-1900, whose staggering number of inventions included the storage battery, electric light bulb, phonograph, motion pictures, and carbon microphone.

E-FIELD (ELECTRIC FIELD)

The electric field or electric intensity E. That field on a spinning charged mass which produces an electrical force resulting in a linear motion of the charge.

See also discussion under c, above.

E-FIELD, MOTIONAL

In classical EM theory, the electric field produced by moving a conductor in a magnetic field. Often called *motional inductance* of the field.

In the orthodox theory, motional inductance is deemed to be identical to the inductance caused by a time rate of change of the magnetic field, experienced by the moving conductor.

E-FIELD, STATIC

In orthodox theory, the electric field in the space surrounding a static charged particle, induced by the presence of the charged particle.

In classical EM, there is no notion as to the *causative mechanism* for this static field of and from a charge, which implicitly is assumed to just continuously create and pour out EM energy in all directions, thus grossly violating energy conservation.. Consideration of this anomaly leads to what has been called the most pressing problem in both quantal and classical electrodynamics: the question of the formation of the fields and potentials associated with the "source charge".

For a full solution to this problem, see my "Giant Negentropy from the Common Dipole," **Journal of New Energy**, 5(1), Summer 2000, p. 11-23. Also on this website.

EHRENHAFT, FELIX

Scientist who performed numerous experiments believed to demonstrate fractional charges.

EINSTEIN, ALBERT

German (Jewish) physicist, 1879-1955, who emigrated to the U.S. and formed special and general relativity theory, discovered and formed the theory of Brownian motion, recommended the development of the atomic bomb to President Roosevelt, and profoundly affected the course of science and the modern world.

EINSTEIN-de HAAS EFFECT

The rotation observed in a freely hanging ferromagnet when it becomes magnetized.

It has been used in the Einstein-de Haas method to determine the gyromagnetic ratio of a ferromagnetic material by suspending a cylinder of the material from a torsion fiber and measuring the angular displacement of the cylinder when its magnetization is reversed.

EINSTEIN, PODOLSKY, AND ROSEN PARADOX

Thought experiment in 1935 for measuring two correlated photons separated and at distant locations, protesting that quantum mechanics requires that the particles communicate instantly, which is a "spooky action-at-a distance" (Einstein's phrase).

The experiment eventually was performed and it works, just as required by quantum mechanics. The paradox inspired the development of hidden-variable theories.

EINSTEIN'S POSTULATES

(1) All the laws of physics are equally valid in all inertial frames of reference,

(2) the speed of light is the same to every inertial observer, and

(3) the observable local effects of a gravitational field are indistinguishable from those arising from acceleration of the frame of reference.

The first is called the special relativity principle, the second is called the law of light propagation, and the third is called the equivalence principle. It is now known that postulates (1) and (2) are not independent of each other. Note that the third postulate implies that any local force is due to a "gravitational field" (acceleration of the frame of reference). It also implies that gravitational force has a mechanism, since quantum mechanics assigns a differential operator, operating upon a potential, to create every force. By extended inference, it can be seen that the third postulate also implies that there should exist a method to turn any type of force (field) into gravitational force (field).

The Russian physicist Sakharov has strongly postulated that gravitation is not even a fundamental field of physics, of the kind used by Maxwell in his electrodynamics. Instead, in this view **G**-field is always comprised of, and made from, other fields and interactions upon them. Indeed, such has always been implicit in general relativity, it just took Sakharov to formally propose it. E. g., see A. D. Sakharov, "Vacuum Quantum Fluctuations in Curved Space and the Theory of Gravitation," **Soviet Physics Doklady**, Vol. 12, No. 11, 1968, p. 1040-1041 [English translation.] Sakharov's article (in Russian) in **Doklady. Akad. Nauk SSSR**, Vol. 177, 1967, p. 70-71.

Now let us do a little "tinkering" with Einstein's postulates. For the first one, we point out that in the new approach using dimensioning and subspaces, the notion of an inertial frame now has acquired additional complexity! The "gross translation" effects—which tends to be what physics ultimately focuses upon—can remain the same, and yet vacuum engines can be buried up inside the inertial frame to act upon a mass in non-translating ways. Everything translation-wise can remain the same, but now matter can be transmuted and transformed, etc., still right there in an inertial frame. So when the infolded electrodynamics inside all fields, potentials, and waves are utilized, the notion of "inertial frame" has acquired a higher topology and then one inertial frame may differ very substantially from another inertial frame. This of course move one from special relativity into full general relativity, and even there into a slight extension. Special relativity can remain special relativity on the surface, and yet effects occur "within" the objects postulated to exist in this inertial frame. The "inertial frame" concept in the postulates is now just a sort of special "equilibrium case" of a higher topology "inertial frame" notion.

The second postulate now stands as a "special case" of a far more general second postulate. It actually defines (and limits) "light" to bulk changes in the entire vacuum potential magnitude. It only applies to light signals which are "bulk upheaval" disturbances of the vacuum potential (spacetime). Specifically it need not apply to the "inner EM/GR realm" of longitudinal EM waves infolded inside the vacuum potential, other potentials, signal carriers, etc. Superluminal communication is now included in this "hidden variable" communication. The Fogal semiconductor is in fact capable of infolding and outfolding EM signals, including producing the internal longitudinal EM waves, and during their infolded state these signals are permitted to move at superluminal velocity.

So the second postulate needs to be restated to include the present statement as a special case. Notice that the concepts "light" and "speed of light" have now taken on much richer, extended meanings, since there is "outfolded" light and "infolded" light, so to speak. Light now is not just the "external perturbation wave" in the ambient vacuum potential medium (in flat spacetime). Instead, it can also be an "internal perturbation longitudinal wave" inside a "net flat spacetime" which does not show on the "surface" at all. Indeed, it may move in the time dimension or in 3-space. It now includes the transmission of an extraordinary "vacuum engine" as well as the usual transmission of just an ordinary signal.

And these infolded vacuum engines can be visualized as very special sets of longitudinal EM waves and their dynamics, consistent with the Whittaker decomposition. His U(1) symmetry electrodynamics decomposition—particularly when enriched in the higher symmetry O(3) electrodynamics—applies to the ambient vacuum as a potential (it is a potential since it has energy density). So the "subspace" inside spacetime, so to speak, is just a set of LWs and their dynamics, and that subspace itself is engineerable, just as is the "bulk curvature of spacetime" itself. Further, we may now consider space itself is just a vast superhighway for such superluminal LWs and their dynamics. Mass is mostly empty space with only an occasional particle here and there and with fields, potentials, and waves in between. Hence huge masses such as the ocean and earth are actually superhighways for the direct passage of longitudinal EM waves, "engines", etc. The degree of "transparency" is a function of the degree of cleanness of the LWs.

The third postulate has also been dramatically extended and requires revision. As presently stated, antigravity effects do not appear to be included in present physics heretofore. The "gravitational effects and external accelerated effects" notion in conventional physics is still founded purely on *ordinary bulk translation*. Now it need not be. For example, the system can appear to be an ordinary system, as judged by normal "external light" observation. Yet its internal vacuum engines can cause local violation of most so-called "laws of nature." The reason a "law of nature" can be violated is that one is now able to violate the premises upon which it is postulated, and which are required to hold if the law is to hold. Or another way to look at it: any conservation law is the result of a symmetry. Breaking that symmetry allows violation of that specific conservation law.

So as we've said so many times before, the infolded EM inside the "conventional" EM fields, waves, and potentials—and inside the vacuum potential and spacetime itself—dramatically changes the present theories of electromagnetism, quantum mechanics, and general relativity. Further, for the first time the Sachs unified field theory allows an *engineering* approach which simultaneously crosses, includes, and extends all three disciplines in the required manner. The approach can be placed into good engineering models based on the Sachs work, particularly using the O(3) electrodynamics subset spearheaded by Evans, and the models can be tested and verified or falsified.

EINSTEIN'S GENERAL THEORY OF RELATIVITY

Mathematical theory of gravitation in which the gravitational force is mathematically described by a curvature in space or spacetime.

In other words, the geometry and its dynamics have become physical agents.

It is important to note that, in general relativity, the curvature of spacetime acts on mass-energy, and changes in or to mass-energy interact back upon spacetime to change its curvature.

Further, we consider that an exact pattern of curvatures of spacetime and their dynamics exists for every mass system and its dynamics. This is the engine concept. The most general way to engineer matter is not by brute force translation, but by forming spacetime engines. Once formed, these engines act upon any mass placed in the engine region, to eliminate the deltas existing in that mass's resident engine and the impressed engine. The curvature of spacetime itself furnishes the energy for the continuing action upon the mass, once we pay to form the engine. The mass can be acted upon at any level, from its gluons and quarks to its nuclei, to its atoms, its lattice forces and binding energy, etc. Significantly, the Sachs theory applies to physical reality from beneath the quarks and gluons to the entire universe, and folds in quantum mechanics, electrodynamics, and general relativity into a single unified field theory that is (in theory) engineerable by higher symmetry electrodynamics means.

ELECTRIC FIELD

The *conventional* definition is this: "1. a region in space in which a stationary electric charge experiences a force due to its charge. 2. the electric force per unit test charge." **Dictionary of Science and Technology**, ibid., p. 720. That definition is flawed. Consider the "spatial aspects" of part 1. If an electric field is defined as a force per unit charge, it is not a region in massless space but is an effect of something existing in massless space and interacting with the charged mass. The electric field *prior to interaction* is indeed related to a region in space, because it is identically a curved spacetime region. In the Sachs approach, general relativity and electrodynamics have become one and the same. So prior to interaction, the *field as it independently exists prior to interaction with charge* has become a curved spacetime region, and the field is *purely* a spacetime curvature effect. The interaction with mass to produce a force on and of that mass (mass is a component of force, and there is no such thing as a massless force) is a separate consideration from the field as it exists in space prior to interaction. The result of this entity's interaction with charged mass has nothing to do with *what an electric field is*; but with *what it does to charged mass*. Further, the force evidenced on a charged particle is not due to its charge; it has that charge always, whether or not there is a net force evidenced on it!

Part 2 is a little better. The only problem is, it totally disagrees with the entity existing in space prior to interaction. In other words, here it's a "force on a charge", which is an effect occurring after the interaction. Again, it is what the field *does or accomplishes*, not what it *is*. Hopefully the reader can now begin to see what terrible difficulties await anyone who seriously attempts *foundations definitions*. Feynman sums it up admirably in one of his famous statements: "*Everything we know is only some kind of approximation, therefore, things must be learned only to be unlearned again or, more likely, corrected."* An additional difficulty is that the very notion of a separate massless force independent of the mass on which it operates, is fictitious, yet continues to be widely used. Recalling that any true definition is an identity and not an equation, let us start with the definition of force:
$\mathbf{F} \equiv d/dt(m\mathbf{v})$. As can be seen, force is a system comprised of (i) a mass component and (ii) a nonmass component. The force is not something separate from the mass, at all! Further, force is not even unitary. It's a system comprised of two coupled components; the mass and a coupled (interacting) gradient in a potential flux. *Note that* $\mathbf{v}$ *involves motion through, and interaction with, the virtual flux comprising the vacuum potential. Note that* $d\mathbf{v}/dt$ *involves a gradient in that flux interaction with the mass*. Unfortunately mechanics is still using the medieval concept of a "separate force acting upon a separate mass." That is wrong, unless we change the fundamental definition of force itself. See, e.g., Robert Bruce Lindsay and Henry Margenau, **Foundations of Physics**, Dover Publications, New York, 1963, p. 283, where the authors emphasize that a "field of force" at any point is actually defined only for the case when a unit mass is present at that point. The reason can be seen: mass is a necessary component of force, and without mass present there cannot be a force present.

ELECTRIC DIPOLE

See Dipole.

ELECTRODYNAMICIST

A specialist in electrodynamics,

...the physics of the relationships between electric, magnetic, and mechanical phenomena—and especially a specialist in electrodynamics theory.

It should be pointed out that essentially all electrodynamicists are versed in U(1) electrodynamics, and a much smaller number are versed in more advanced electrodynamics such as O(3) symmetry electrodynamics, unified field theory electrodynamics, non-Abelian electrodynamics, etc. The electrodynamics field is actually a very vast field indeed, touching everything in physics. Very often, when one needs a particular electrodynamics problem solved, it calls for a special category of electrodynamicist and not just an electrodynamicist in general. One must therefore sometimes examine the background of the electrodynamicist making a statement or a pronouncement: electrodynamicists after all do have differing views and differing disciplines within the field.

ELECTROMAGNETIC PULSE (EMP)

A sharp pulse of electromagnetic radiation produced when an explosion occurs in an unsymmetrical environment, especially at or near the earth's surface or at high altitudes.

Essentially the same as an electromagnetic shock wave, a wave of great intensity which results when waves with different intensities propagate with different velocities in a nonlinear optical medium. An EMP is also produced when two intense longitudinal scalar electrostatic potential wave patterns meet and couple into a sudden flash of vector EM energy.

ELECTROMAGNETIC SMOG

The background of extremely weak EM radiation that fills the normal modern environment, particularly in developed nations.

The individual signals are too weak to individually produce effects of any significance in biological systems. However, in a dense EM smog environment with 500,000 signals per square meter per second, the signal complex and its nonlinearity begin to produce highly nonlinear effects in biological systems. These effects also produce damage that may cumulate over a long period of time, including for years. This bioeffects area has largely not been investigated by EM bioeffects scientists.

It should be pointed out that electric lines, telephone lines, transmission lines, etc. act as long wire antennas to detect and propagate such very weak EM signal noise. Essentially all the radiators in the environment—including electronics equipment, TV stations, radio stations, factory machinery, etc.—thus produce very weak signals picked up by these long line antennas and piped into every home, factory, neighborhood, etc.

ELECTROMOTIVE FORCE (EMF)

A difference of potential created by sources of electrical energy—i.e., by separated charges (dipoles)—which can be utilized to drive electrical currents through external circuits. Also, open circuit voltage, or the limit of the potential difference between the source's terminals as the current in the external circuit approaches zero.

Poorly named. Also quite confused in the standard theory and usage. First, *emf* is not a *force* at all. It is a difference in potential, hence it is measured in volts. Also, it is not considered an **E**-field, since that is a field of force. Yet it is in fact a , restricted to the direction between the two measurement points, and is considered to be an **E**-field in the theory!

For this reason the standard theorists say that the term is sometimes used as equivalent to a difference in potential, but that strictly speaking it should be applied only to a source of electrical energy! The problem is that conventional theorists are unaware that a potential is a bidirectional flow of energy in 3-space, where the energy enters from the time-domain (complex plane). Since they are unaware that a potential is hidden negentropic energy flow process involving broken 3-symmetry and viable 4-symmetry, the theorists are unable to consider the potential in general as a source of energy flow. Yet they are forced to consider a potential difference across the terminals of a source as "somehow a flow of energy, that generates forces upon the electrons to propel them through the circuit as current flow."

In the new viewpoint, a resolution is achieved of these incongruities by more accurately defining the E-field with respect to the potential as E [q]/q. It is noted that [dA/dt]q/q also produces an E-field, so that the full definition of the E-field is as E [(+dA/dt)q]/q. However, one volt represents one joule (of excess energy) per coulomb of charge. *The energy density flow in an electric circuit is in the voltage, in the emf, and it is not in the current per se*. The electron current (drift current) carries the excess energy that is being dissipated as work in the circuit, but in a nominal circuit the drift current only moves a few inches per hour. Half the energy is dissipated in the external circuit and external losses, and half is dissipated in forcing spent electrons in the ground return line back up through the back-emf of the source, performing work inside the source to dissipate its separation of charges. Left alone, any dipole will furnish emf indefinitely, freely receiving the energy from the time domain (complex plane) and outputting it in 3-space. The free flow of EM energy will continue unabated from the undestroyed dipole, regardless of how many external loads and losses are powered (how much energy is collected and dissipated from the ongoing flows representing the potential). So electrical circuits should be developed which allow little or no electrons to be forced back up through the dipole to dissipate its separation of charges and destroy the dipole.

ELECTROMOTIVE FORCE, BACK (BACK EMF)

Back emf is a loose term used for the *counter-electromotive force.*

When the source is powering a circuit or circuit element, the term "back emf" is used to refer to the forcing of current (electrons) back up through the source against its emf, thereby performing work inside the source to dissipate its separation of charges (its dipolarity). When a potential source of electrical energy—such as a capacitor, an inductor, or a rotating machine—is receiving energy from the source and converting it to dissipative power and work, that "powered" device is said to develop a *counter-emf.* A source has a built-in emf *a priori*, that is holding its charges separated so that it is dipolar. When electron current is forced backwards through the source through its built-in counter-emf, and backwards against its emf, work is performed against the internal resistance of the source to dissipate its separation of charges, thereby dissipating the source. If electron current is not allowed to flow back up through the source against its back emf and through its built-in counter-emf, no dissipation of the source occurs, even though energy density (not electron current dq/dt but energy flow d/dt) is flowing from the source and can be collected in collectors in the external circuit to store the energy as a created local energy source. This collected energy can then be shuttled to a separate load circuit and released, to provide a "heat pump" cycling operation and overunity coefficient of performance.

Nikola Tesla in fact knew how to shuttle energy in a circuit in such fashion, as Barrett's quaternion analysis of Tesla's actual patented circuits has revealed. [See T.W. Barrett, "Tesla's Nonlinear Oscillator-Shuttle-Circuit (OSC) Theory," Annales de la Fondation Louis de Broglie, 16(1), 1991, p. 23-41.] Note that a rigorous analysis of those same circuits, using tensors or vectors, will not show the effect.

When the original source dipole is not dissipated because electron current is not passed back up through its back-emf to scatter the charges, the original source dipole will continue to furnish emf indefinitely.

The terms emf and counter-emf are normally applied only to recognized sources of electricity. Emf is applied as the algebraic sum of the potential differences acting in a circuit attached to a source. Back-emf (counter-emf) is applied as the potential difference internally through the source, between its terminals. Its main application is thought to be a *powered device or component in the circuit*. Actually, its main application is to prevent COP>1.0 electrical power systems from being developed and utilized.

ELECTROMYOGRAPHY (EMG)

A diagnostic application which detects changes in electrical potentials associated with muscle contractions.

Specific electrical patterns have been associated with specific abnormal states (e.g., denervated muscle), but the method has not yet been systematically developed beyond this application.

ELECTRON

Stable elementary particle in all atoms, and having a negative charge of 1.602×10^{-19} coulombs, spin ½, and mass of 9.11×10^{-31} kilograms.

ELECTRON GAS

A system of electrons with only weak interactions so that the electrons may be regarded as moving independently.

Thus, in many ways, that collection of electrons can be treated as a gas. Also see discussion under Drude Electron Gas.

ELECTRO-OPTICS

A technology in which electrons are focused and steered as if they were light. Examples are the cathode ray tube (CRT) and the electron microscope.

ELECTRO-POLLUTION

Also called *electromagnetic smog* and *electronic smog*. The conglomerate or maze of EM fields and radiations that are produced by technologies such as electric power transmission and radio transmission, and that can have long term cumulative harmful effects on humans.

The new viewpoint dramatically extends the types of fields and effects involved, and gives entirely new mechanisms for the interaction of EM fields and radiation with biological systems, including cumulative effects, signal-density effects, and vacuum engine effects. A mechanism for long term causation of cancer and leukemia by electro-pollution is derivable in the new approach.

As an example, even though the myriad of very weak EM signals comprising the electro-pollution are individually tiny, each when interacting at a local site with the body or its cells involves a broken 3-symmetry and thus an involvement of 4-symmetry, with corresponding giant negentropy. Further, the Heaviside dark energy component accompanying that local field interaction will in turn interact with essentially all the other locations of the body. Each of these interactions involves broken 3-symmetry and involvement of 4-symmetry. The result of the large complex of broken 4-symmetries constitutes a direct structuring in the time domain, hence weak time-pumping and weak time-charging. Time charge excitation decays only very slowly, emitting longitudinal EM waves inside the body as the charge decays.

Over a long period of time (sometimes years), this "time-hash" or "time-jamming" upon the operation of the master cellular control system, the immune system, and the cellular regeneration system is cumulatively detrimental. In this way, effects such as leukemia, cancer, etc. may be gradually "kindled". However, there have been no real scientific laboratory "cause and effect" investigations of this phenomenology at all. Nonetheless, the results will and do show in epidemiology studies, which are then attacked by orthodox scientists (many employed directly or indirectly by the power industry, etc.) on the grounds that no laboratory cause and effect evidence has been shown.

In short, this is one of the areas where the lack of scientific cause and effect laboratory evidence—because such experiments have not even been done—is improperly used to negate real scientific work showing deleterious effects that powerful interests do not wish shown.

ELECTRO-RETINOGRAPHY (ERG)

A diagnostic application that monitors changes in electrical potentials across the retina to assess eye movements.

This is almost the only method available for noninvasive monitoring of Rapid Eye Movement (REM) sleep.

ELECTROSTATIC COOLING

To be added

ELECTROSTATIC SCALAR POTENTIAL

A static (stationary) ordering in the virtual photon flux of vacuum.

The word "static" is unfortunate and should be replaced by "stationary", since the underlying active vacuum medium is always in violent motion, and there is nothing truly "static" in the universe. But an equilibrium condition can exist, even in violent motion, so that a stationary entity persists. An example is a perfect whirlpool in a river.

ELF

Extremely Low Frequency.

Used to describe EM fields whose frequencies lie in the range from just above 0 Hz (direct current) to 300 Hz. This includes power line frequencies (60 Hz in U.S. and 50 Hz in Europe) and frequencies used by certain U.S. military ELF communication systems such as for submerged submarines.

EM

Electromagnetics.

EMF

Electromotive force. See discussion under that term.

EM FIELD

Electromagnetic field. In its loose usage, it refers in a very broad way to any field, force, or energy associated with electromagnetic interactions, charges and currents.

Thus "EM field" includes electrostatic fields, magnetostatic fields, electromagnetic fields (including radiation and induction), vector-potential and scalar-potential fields, Hertz potentials, Fitzgerald potentials, Whittaker potentials, etc.

In its precise usage, "EM field" conventionally refers to an EM "force" field, such as the **E**-field, **D**-field, **B**-field, **H**-field. In classical electromagnetics (CEM), as a holdover from the old assumption of a material ether, the force fields are considered (erroneously) to exist in mass-free space, and they are also considered to be the primary causes of electromagnetic phenomena. This is a non sequitur, and it involves substituting the effect for the cause.

In the new viewpoint, the force fields do not exist in vacuum, but only in and on and of the charged particles themselves, where mass is present to form one component of the force. The force fields are therefore effects and not primary causes. The primary causes of all electromagnetic phenomena is taken to be the potentials; however, the hidden Stoney/Whittaker/Ziolkowski internal structures of gradient-free scalar potentials may interfere to cause potential gradients in and on charged particle systems. This therefore includes distance-free scalar potential interferometry and action at a distance, as well as vacuum engines.

The new view uses Sachs' unified field theory, and considers that the EM field in the vacuum, or an EM potential in the vacuum, is a curvature of spacetime function. Thus the new view is a unified field theory where GR has become EM and EM has become GR, and where EM can involve or produce gravitational, temporal, and inertial effects as well.

EM FORCE FIELD IN THE VACUUM (A FALSE CONCEPT)

The erroneous notion that there exist forces in the vacuum, so that the set of forces at a set of spatial points forms a force field.

This ignores the fact that mass is a component of force, and the presence of a force requires the presence of a mass. When Maxwell formed his electrodynamics theory, he and almost everyone else believed that a thin material ether pervaded empty space. Thus there was a "material medium" in which electromagnetic fields existed, and so it followed that real forces existed in this material medium, from point to point. Indeed, to the early electrodynamicists there was no point in all the universe where mass was absent.

Heaviside, Hertz, and Gibbs reduced Maxwell's 20 quaternion equations to the present four vector equations, but did not change the *force field in space* assumption used by Maxwell. Heaviside detested the "mystical" potentials favored by Maxwell, and believed they were figments of one's imagination. He regarded the forces as the primary EM causes.

Yet even while Heaviside *et al*. were retranslating and topologically reducing Maxwell's theory dramatically, the Michelson-Morley experiment in the 1880s had already destroyed the material ether on which those same force fields were based.

Physicists, however, have continued to use the notion of a separate force acting on a separate mass, which of course is also a non sequitur, substituting effect for cause yet again. Hence the foundations of physics remain fundamentally fouled.

For a succinct discussion of potentials versus forcefields as the primary EM causes, see Y. Aharonov and D. Bohm, "Significance of Electromagnetic Potentials in the Quantum Theory," **Physical Review, Second Series**, 115(3), 1959, p. 485-491. See also Y. Aharonov and D. Bohm, "Further considerations on electromagnetic potentials in the quantum theory," **Physical Review**, 123(4), Aug. 15, 1961, p. 1511-1524.

EM GENERATRIX

Whatever generates electromagnetics, particularly the fields. Time is the ultimate EM generatrix.

Whittaker showed in 1904 that the interferometry of two scalar potentials (i.e., of their hidden multiwave structures) can create all classical EM fields, no matter how complex, thereby starting a branch of electrodynamics known as *superpotential* theory. See E. T. Whittaker, "On an Expression of the Electromagnetic Field Due to Electrons by Means of Two Scalar Potential Functions," Proc. Lond. Math. Soc., Series 2, Vol. 1, 1904, p. 367-372. The paper was published in 1904 and orally delivered in 1903.

In 1903 Whittaker showed that any scalar potential (e.g. between the ends of a dipole) can be decomposed into a harmonic set of phase conjugate EM longitudinal wavepairs. The present author applied the Whittaker decomposition to the scalar potential between the ends of a dipole, and pointed out that the conjugate half-set may be taken as converging EM waves from the complex plane (the time domain), while the real half-set may be taken as diverging EM longitudinal waves emitted from the dipole in all directions in 3-space. The dipole is a known broken 3-symmetry in the dipole's violent virtual energy exchange with the vacuum; hence this shows that breaking 3-spatial symmetry allows nature to fall back to a more primary 4-symmetry. Hence energy flow conservation is violated in 3-space, but is rigorously obeyed in 4-space. Further, the free flow of 3-spatial energy from the dipole continues so long as the dipole exists.

The dipole thus is a true negative resistor, receiving EM energy in unusable form (from the complex plane; i.e., the time domain), transforming it into usable energy, and outputting the usable energy. This is also the fundamental mechanism for extracting unlimited EM energy from the seething vacuum, taking the energy from the time domain via the giant negentropy mechanism. See my paper, "Giant Negentropy from the Common Dipole," *ibid*.

This also means that the source of all EM 3-spatial energy is from the time domain, and is due to broken 3-symmetry. The ultimate EM generatrix is thus time. The ability of a bit of broken 3-symmetry (such as formation of a simple dipole) to initiate a continuing and ongoing flow of free EM energy via the 4-symmetry between time-energy and spatial energy, means that *negentropic* engineering, once we get the hang of it, is far easier than our present *entropic* engineering. In essence, we have to learn how to do electrical engineering all over again, from a much more fundamental point of departure.

EMI (ELECTROMAGNETIC INTERFERENCE)

Disturbances of electronic equipment's operation by intrusion of extraneous EM signals from outside sources. Also, disturbances of the operation of one or more subsystems of an electronic system by intrusion of undesired signals from other subsystems.

EMI, ANOMALOUS

An "ad hoc" term denoting an unexpected nonlinear optical functioning process in a dense signal environment whereby nonlinearities on the skin of a vehicle or cover of an equipment become pumped phase conjugate mirrors, so that they emit amplified phase conjugate replicas (PCRs)—of signals and fields impinging upon the skin or covering and the nonlinearity from electronic circuitry operating inside.

By the distortion correction theorem, these amplified PCRs precisely backtrack the signal waves that impinged upon the phase conjugate mirror from inside the vehicle or electronics, back to the original source of the internal signal. The result is the scavenging of energy from the dense electronic signal environment and sharply focusing and directing it into the operating circuits of the internal electronics. Thus internal signals, often amplified, start sporadically appearing through the circuits. These sporadic jamming signals due to the anomalous EMI effect are known as EMI fireflies.

Such EMI fireflies were resoundingly experienced in U.S. missiles and aircraft in the U.S. air attack on Libya in 1986. Although some of the anomalous EMI effects could have been produced by the unusually dense EM signal environment and poor hardening of circuits and electronics, it is believed that the weak jamming was also a test being conducted of a laboratory prototype Russian quantum potential weapon.

This weapon appears to have been finished and deployed at the end of 1989, and then utilized against Allied forces in the Gulf War, accounting for the Gulf War Disease. We have previously explained why British, Canadian, and American soldiers acquired the disease, why the native populace did not, and why the French troops did not.

Inside the human body, the anomalous EMI effects may be used to produce time-charging and delayed interference with the immune system, the master cellular control system, and the cellular regeneration system. By using dimensioned signals, the targeted systems can be specifically and deterministically affected as desired, for any set of disease damage types and symptomology desired. So the technology may be used to induce a "cocktail" mix of various infectious disease damage types. The induced time-charging effects—where the time-charge is dimensioned—followed by longitudinal EM wave emissions from the time-charges as they decay in the veteran's body, can induce the same or similar symptoms and damage in close family members exposed to the weak but dimensioned longitudinal EM radiation. This applies not only to wives but also to family members such as children often in close proximity to the veteran. In addition, exchange of bodily fluids from the veteran to his spouse can directly induce the symptoms in the spouse since those fluids are themselves still time-charged (with dimensioned time charge) and slowly decaying.

ENDOTHERMIC EXPLOSION

An EM implosion, resulting in explosive electrostatic cooling. The sudden, explosive reversal of electromagnetic energy scattering in a spacetime area so that the local EM heat energy is converted back to a negative potential. In this manner, explosive electrostatic cooling occurs in the area.

Endothermic EM explosion occurs by pulsed scalar Whittaker interference of two longitudinal EM wavesets beamed from two LW EM transmitters. The distant transmitters of the LW interferometer must have their local electrical grounds biased well below the ambient zero potential in the distant interference zone (IZ). Whittaker internal EM waves radiate through subspace (the LW superhighways inside EM fields, potentials, and waves in mass) from the transmitter to the interference zone, and also from the interference zone back to the negatively biased transmitter/receiver, emerging there as ordinary electromagnetic scattering energy or *heat*. All *normal* explosions are exothermic in nature, and ordinary electromagnetic heat energy is radiated away. A scalar EM interferometer/howitzer, however, may produce an endothermic explosion (an energy implosion) at a distance, explosively extracting the heat energy at the implosion site and receiving the energy back at the transmitter site for disposal.

The same LW interferometer can also produce an exothermic explosion in the distant interference zone, merely by positively biasing the electrical chassis grounds of the scalar EM potential transmitters and pulsing the transmission. Negative biasing of the transmitters' electrical chassis grounds and a pulsed transmission result in an endothermic explosion in the distant interference zone.

ENDOTHERMIC LONGITUDINAL EM WAVE INTERFEROMETRY

Extraction of EM energy from a distant intersection area by a scalar interferometry whose electrical grounding is biased well below the ambient potential in the distant interference zone.

The result is a cooling of the interference zone, and heat energy emerging at the transmitters.

ENERGETICS

The Russian term for what I have called advanced higher-symmetry electromagnetics,

...using artificially constructed Whittaker internal biwave structures to make activated potentials that have specific, desired "vacuum engines", where the EM field is a curvature of spacetime function, and thus involving a unified field theory that is engineerable by novel electrodynamic means.

I believe that the closest Western work approaching the Russian energetics science is the O(3) higher symmetry electrodynamics pioneered by Evans, particularly when combined with Sachs' unified field theory as an important subset. The other closest Western work would seem to be the important work of Barrett in SU(2)×SU(2) symmetry electrodynamics.

The activated potential containing the infolded vacuum engine structures is said to have been *dimensioned*. These dimensioned potentials can be combined to form EM carrier waves which contain the hidden vacuum engines. These vacuum engines, scalar Whittaker EM interferometry, and activation of vacua and matter are used to perform unified field engineering.

Russian energetics also adds the formation and use of the quantum potential, enabling
(i) instantaneous action at a distance with multiple separated target nodes, (ii) essentially limitless direct energy amplification in the assembly of receiving nodes, without additional energy input at the initiating node, and (iii) engineering of hidden variables inside distant targets, instantaneously, without transmission *as such* through space. The quantum potential itself can be *dimensioned*, so that vacuum engines can be instantaneously transmitted into distant targets, altering their local spacetimes to contain the desired engine(s). Note that no intervening barrier can "impede" or "shield" a quantum potential because it does not travel through space as such; it just appears everywhere at once in the space where it will be.

Adding to classical EM theory, general relativity, and quantum mechanics the internal EM energy in the scalar EM potential will generate a superset of each discipline. These three new supersets are unified in their common internal EM energy subset. As a bonus mind, personality, memory, and deep biological cellular and system control are also available, since the internal time-energy domain is used by biological systems for these living functions. Energetics thus is an engineerable, unified field theory of physics and metaphysics.

Russian energetics is largely still a "secret" science, developed over the last five decades and highly weaponized. In the Russian scheme the overall area is called *energetics*. It consists of three subsets: (i) *energetics*, which applies to nonliving systems, (ii) *bioenergetics*, which applies to the physical bodies, cells, chemistry, genetics, etc. of living organisms, and
(iii) *psychoenergetics*, which applies directly to the minds, personalities, memories, emotions, and perceptions of living systems. Russian energetics research, development, weapons, and weapon sites are under the rigid control and operation of the KGB, by whatever name it may use from time to time. The energetics weapons are not in the regular Russian armed forces. Energetics weapons have been tested worldwide for several decades, and this testing has been documented elsewhere by the present author.

ENERGY

Usually erroneously defined as the "capacity to do work".

The closest definition is: *The invariance of that which is varying*. Note that this is a 5-law logic definition and not an Aristotelian definition.

Here we have a real bucket of worms. This term is usually totally misdefined (as in the nostrum that "energy is the capacity to work") in physics, which defines energy as the "ability to scatter itself or change its own form" which obviously are not identities! A common definition is given as "a quantity that describes the capacity to do work; commonly divided into three major classifications: kinetic (dynamic) energy, potential (static) energy, and radiant (electromagnetic) energy. Well, energy can be changed in form and that is work. But energy is not the "capacity to change its own form", but is its own form, as can be seen.

Anyway, we'll have a go at a definition perhaps a little more acceptable, though still imperfect. Then we'll discuss things a bit.

Rigorously, energy is any deterministic or coherent structuring, either dynamic or stationary, existing in the virtual particle flux of vacuum. While that *sounds* good, it is still "the invariance of that which is varying." Ultimately, a thing is defined in terms of its appositive.

The *type* of energy depends upon the type of virtual particle(s) whose flux is selected. E.g., electromagnetic energy is a deterministic or coherent structuring, either dynamic or stationary, in the virtual *photon* flux of vacuum. Any trapped energy (ordering in the vacuum virtual particle flux) is gravitational in nature, since trapped energy is gravitational. In a mass, e.g., it is the trapped energy that is gravitational, not the mass per se, in the modern view. Contrast the definition of electromagnetic energy to the definition of an electrostatic scalar potential (ESSP): The electrostatic scalar potential is a stationary trapped deterministic or coherent dynamic wave-structuring of the virtual photon flux of vacuum. Thus it can be seen that the ESSP is a special case of EM energy: the stationary trapped case. For this reason, a mass—which is an enormous amount of statically trapped EM energy—may properly be considered as an extremely dense EM potential, which we refer to as the *mass potential*.

A potential is any trapped ordering or coherence, either static or dynamic, in the virtual particle flux of vacuum. A specific type of potential represents a selection of a particular virtual particle's flux in the vacuum, and an ordering—either static or dynamic—imposed in that flux.

However, since the scalar potential is just the static ordering in the virtual particle flux of vacuum, it follows that the scalar potential must contain—and in fact be totally composed of—internal order. E. T. Whittaker showed the form of that order in 1904. (See entry under Whittaker, E. T.) The scalar potential is composed of a harmonic series of pairs of antiparallel transverse waves. The antiwave of each wave/antiwave pair is a time reversed replica of the wave in that pair. In other words, the scalar potential is a special type of Fourier harmonic frequency expansion, coupled with its own phase conjugate present simultaneously.

Feynman said it bluntly: *"It is important to realize that in physics today, we have no knowledge of what energy is."* [Richard P. Feynman, Robert B. Leighton, and Matthew Sands, **Lectures on Physics**, Addison-Wesley, Reading, MA, Vol. 1, 1964, p. 4-2.]

E.g., particularly see R. B. Lindsay, "The concept of energy and its early historical development." **Foundations of Physics**, 1(4), 1971, p. 383-393. Lindsay investigates the concept of energy from its early historical origin. The root of the concept is the notion of *invariance in the midst of change*. Lindsay covers the concept and its evolvement (or lack thereof!) from ancient times through the 18th century.

The real problem is that the notion of energy implicitly involves the age-old unresolved philosophical problem of change, posed by Heraclitus over 3,000 years ago and unresolved to this day. *It cannot be solved within the realm of 3-law Aristotelian logic!* One way of posing it is something like this, after Heraclitus: "For a thing to change, it must turn into something else. How can a thing be itself and something else also? How can a thing have changed, and yet not have changed?"

The problem is that Aristotelian logic has a serious flaw of omission; it actually *implicitly assumes* a fourth law, which is the age-old philosopher's nightmare that, when a thing is pursued to the limit, *it invariably turns into its own opposite*. So in anguish the philosophers spoke of this nightmare as the "accursed necessity for the identity of opposites."

I did resolve the philosophers' nightmare some years ago, by adding a fourth law of logic to the Aristotelian three, which completes and extends Aristotelian logic, and an application rule which can be taken as a fifth law. E.g., see Appendix III: "A Conditional Criterion for Identity, Leading to a Fourth Law of Logic," in T. E. Bearden, **AIDS: Biological Warfare**, Tesla Book Company, Chula Vista, California, 1988, p. 428-443. A simple proof of the fourth law is given in that paper. For a much more elegant treatment of a higher topology logic, which is also practical and useful beyond the limitations of Aristotelian logic, see G. Spencer Brown, **Laws of Form**. Julian Press, New York, 1972. For a proper perspective on mathematics and on Aristotelian logic, see Morris Kline, **Mathematics: The Loss of Certainty**, Oxford University Press, New York, 1980.

It may be that, since by "identity" we mean at least the identity of "left" and "right" different observations, considering the left and right sides of the identity statement. If so, then already we involve a violation of Aristotelian logic in the very notion of "definition". In short, ultimately we can only define a thing in terms of an appositive in the first place. So we write an identity statement where left and right are different sides, then state "Oh, no, they are the same thing after all!" Said in that manner, the problem can clearly be seen. In one sense a definition is pure Zen, where no truth can be stated at all unless the speaker says two exactly opposing things, and then waits for the recipient to realize the truth that has been stated.

What this all means is that, since "energy" (and any other definition, ultimately) involves a logical contradiction in Aristotelian logic, we must "define" *energy* simultaneously in an appositive ways: (i) in the wave view and (ii) in the particle view. However, we point out that the notion of a "moving particle" is the notion of something considered momentarily as fixed (i.e., the particle), but which is immediately thereafter (in time snapshot #2) considered as moving. Notice that "moving" is changing, and so it involves Heraclitus' problem of change *a priori*. The notion of a "moving wave" is also a similar thing; i.e., "a wave" momentarily considers the entity as static and not changing (in time snapshot #1), and in the next moment (time snapshot #2) considers it as moving (changing). We can only point out this dichotomy for the reader to reflect upon and hopefully to grasp. *The conscious mind is a serial processor; it is extremely fast but still perceives snapshot by snapshot, serially. It essentially has been fitted to the single photon interaction, as has Aristotle's three laws of logic*. The problem is in the operation of conscious perception itself, not in nature which is not limited to just serial processing.

The unconscious mind is a massively parallel processor, so it can have many "different slides or snapshots in the slide projector" at the same time. So with our conscious mind's perception (Aristotelian logic is just a model of that, using single photon interaction as the physical observation mechanism) we see in terms of "either-or". On the other hand, with our unconscious we can also grasp the fact that single snapshot A can be the same thing as a totally different snapshot B, if the rules of "decision as to identity" are changed between snapshot A and snapshot B. Suppose that by "identity" we mean "incapable of being discriminated between." Is a black marble identical to a red marble, e.g.? It is perceived so if you are color blind. It is perceived not to be identical if you are not color blind. The point is something that most philosophers missed or brushed aside: identity is not absolute, but is "perceived identity". Identity is the result of a decision operation, based on multiple perceptions, recall from memory, and comparison of two remembered perceptions. The most simple form of comparison is simple subtraction.

The unconscious (massively parallel) perception can handle both snapshots simultaneously. The conscious mind only can see a single marble at a time, so it will see one or the other. In a *third* time interval it will recall from memory the first perception, compare it with the memory of the second perception (say, by simple detailed subtraction), and then decide whether object A is perceived to be identical to object B. The unconscious (massively parallel processor) can handle both the marble snapshots at the same time. It can see both the identity of the two, to a color-blind "identity decision process" and also the nonidentity of the two, to a color-sensitive "identity decision process." Again, nature is not limited to the single-snapshot, serial perception process of our conscious (serial) processor!

Unfortunately, in physics and mathematics we seem to still be thoroughly confused on this very perception issue. Brown's work may be the first work to straighten out the area of the topology of the logic utilized. My own independent effort was successful but far cruder than Brown's; Brown did it elegantly. We bring all this out because when one deeply looks into foundations and true definitions, one will directly confront the philosopher's nightmare and one's own conscious mind will never be able to resolve the problem. One's unconscious can resolve it, but it requires a certain "stretching of the realization" to harmonize monocular perception of the conscious mind with multiocular perception of the unconscious mind.

Just as a small example, the question of "is it a wave or a particle" once raged as a great debate in physics, and was never resolved. Instead, physicists just finally shook hands and agreed to quit arguing and fighting about it, and agreed to accept that the same entity could sometimes act as a particle, and in other cases it could act as a wave, and that *as it existed in the present, before observation,* it was somehow both a wave and a particle but we couldn't see its true nation (in that fashion). The key, of course, is that the question was posed in "either-or" form (Aristotelian logic form), and it cannot be answered in that reduced logic. Instead, a higher topology logic is required. Brown's logic answers it easily, as does my own four law superset of Aristotelian logic (five law superset if we count the application rule as a separate law). In the present, e.g., we have masstime and not mass. Just after a photon is emitted, we have mass and not masstime. The latter photon emission process consummates "observation." The point is, the true entity does exist in zero time as a spatial entity. It is not a spatial entity but is a spatiotemporal entity. If the "interaction" process tears off its "time-tail," it is converted to a "spatial entity" (frozen snapshot) and therefore seems to be a particle. If the "interaction" process does not remove the time-tail, it remains a spatiotemporal entity and therefore seems to be a wave. The *concept* of particle is 3-spatial concept. The concept of wave involves time also. No wave can exist and "be a wave or wavelike" unless it has some time extension to "be waving" *in*!

The physicists debating the wave-particle duality, you see, missed the most important point that *no observable exists in time or persists, a priori.* Hence rigorously no particle exists in time.

So we define energy (particle view) as any virtual particle flux pattern, where that definition automatically considers a single particle in translation as well as multiple particles in their myriad of translations. We define energy (wave view) as any wave flux, where that automatically considers a single wave in translation as well as multiple waves in their myriad of translations. Now note that one is going to have to deal with, and discriminate between, energy, energy flow, energy collection, and collected-energy dissipation.

As the reader can see, whenever one struggles with foundations issues, the problems get very complicated. We've beat this dead horse quite enough, and leave the further beating to the reader!

ENERGY AMPLIFYING COIL

A coil whose magnetic energy flow input is first split into two energy flow inputs, each equal to the original energy flow available from a magnetic source. Both the split energy flows then interact simultaneously with the coil, amplifying its electrical energy output compared to the conventional case where only a single energy flow interacts with the coil.

In the motionless electromagnetic generator (MEG), the curl of the magnetic vector potential of a permanent magnet (i.e., its magnetic field), is extracted and held within the core material of a special transformer, while the magnetic vector potential of the permanent magnet is freely replenished in uncurled (field-free) magnetic vector potential form in space around the core material. Both the full magnetic field in the core and the full uncurled magnetic vector potential in space adjacent to the core interact with each output coil of the transformer. Hence a single potential energy flow is "split" into two flows each equal to the original EM energy flow, and both the parallel flows energetically interact with the output coil. This increases the energy interacting with the coil by this "dual interaction", so that the coil is said to be an "energy amplifying coil".

ENERGY COLLECTION/COLLECTING

In electromagnetics, exposure of an interceptor/collector, e.g., a charged particle, into an impinging EM energy flow, so that some of the flow is diverted around the intercepting particle. We may say that the flow of energy has been "reordered" in a stream around the diverting charge.

Energy collection is not a thing which "has been accomplished" and finished; instead, it is an ongoing process.

Note now that, if you perform or consider or impose any sort of ordering at all in the energy flow/flux, rigorously you have just implied an *energy collection/collecting* process. The energy part of a photon, e.g., would seem not to be "energy" per se. Instead, it is an energy collection/collecting, and a time collection/collecting as well. Yet that energy part is energy also! [Not to worry! Energy and energy-collecting, contrasted as appositives, become identities at the extreme boundary separating the two concepts. That boundary is the photon concept. Aristotelian logic does not apply on the boundary, which violates the Aristotelian law of the excluded middle.] More reasonably, a charged capacitor does not have "stored energy" per se in it, in the sense of "so many chunks of energy called joules". Instead, it has an *ongoing energy collection/collecting process*, where the asymmetry in the local vacuum flux exchange, of the dipole across the capacitor plates, continually extracts and "gates" a flow of EM energy from the capacitor dipole. That energy-flow bathes all the trapped charges in the capacitor. The energy-flow interaction with the trapped charges creates the **E**-field and all the rest.

The diverted part of the total energy flow, is what is calculated in the "Poynting flow" or **S**-flow.

ENERGY, DISINTEGRATED

An ad hoc term for the energy of the incoherent virtual particles in the virtual particle flux.

ENERGY DISSIPATION

Refers to the scattering or disordering of energy.

This is somewhat of a misnomer, broadly used in physics and somewhat erroneous.

Energy dissipation" *per se* does not mean that the energy is destroyed. Instead, there is the dissipation of the ordering (*collected/collecting*) of energy in which the diversion (local ordering) process disappears. What we call the "dissipation in space" of energy is rigorously the dissipation of the collection/collecting in space of the energy. In short, the energy is scattered, as in a resistive load, in all directions. But it is still there in space, just disordered.

Recall that all EM energy at a dipolarity comes directly from the time domain. It is the collecting process, not the energy, that is dissipated from a point or a region. Only *collected/collecting* of energy can be truly dissipated. With that understood, then dissipation of collected energy is simply removing the "collector" from the energy density flow impinging upon it to cause the collecting process to occur, or removing the flow of energy impinging upon the collector so that it intercepts and diverges some of it around itself.

So there are two ways in which this "collected energy" dissipation can occur: (i) the collector is moved out of the impinging energy-flow-stream, or (ii) the energy-flow-stream impinging on the collector is reduced to zero. Note that "changing the form" of the energy—i.e., changing the collector and the type of collecting—involves both conditions (i) and (ii). Thus energy is dissipated when the *collector/collecting* form is changed. In the conventional, less accurate statement, work is performed when "the form of the energy is changed." That now should be stated as "work is performed when the collector in the energy-flow-stream is changed to a different collector, because the first collector must be removed from the energy-flow-stream or the energy-flow-stream must be removed from it.

In physics we also consider that "positive" work by a body is work it does on something else, while "negative" work is work done upon the body by something else. We specifically emphasize that collection/collecting need not be a unitary, one-time occurrence! The EM energy-flow impinging upon a collector roars on by it at something like the speed of light. The entire flow is diminished by only about 10^{-13} (the nominal energy collecting fraction) as it flows onto, and on beyond a coulomb of charge. If that departing energy-flow is then retroreflected or otherwise *returned* to pass back through again, additional energy collection/collecting can and does occur from it. This can be repeated many times, particularly in an intensely-scattering, optically active material. Also, after the collected fraction of energy is dissipated, we can also retroreflect the scattered energy flow back and reuse it again. This too can be repeated many times.

So we must be careful of the present *work-energy theorem*, which is a special case and assumes only a single pass of the energy-flow in the "collection/collection" of energy that "changes form." If we institute additional passes, with additional "collection/collecting of energy, then we can collect and "use" a little more energy from all that enormous energy-flow that otherwise would escape us. If we dissipate some of the collected energy, then also intercept the departing dissipated energy flow and return it, we can collect some of the energy flow again and then dissipate that new collection again. And so on.

One can permissibly get many joules of "work" from a single joule of energy by iterative retroreflection, iterative re-collection, and iterative dissipation, without violating the conservation of energy law. This is one of the major secrets of overunity energy processes. It is proven by the overunity or excess emission (Letokhov was forced to call it "negative absorption of the medium" from an intensely scattering, optically active medium, as in the Lawandy experiment and in his patented process for lasing without population inversion. It is also proven by Patterson's adaptation of anti-Stokes emission.

Let's do a gedanken (thought) experiment, where we do not even apply the nominal 10^{-13} energy collection fraction. Let's just *conventionally* say "energy flow," "energy collection," and "energy dissipation," and ignore the "collection fraction." Since we are talking theoretically, we can have a perfect system. So we have a closed system, which we open to input some energy into. The system then opens in the load to dissipate all the energy back to the environment, thereby doing work. Now suppose I passively (i.e., without any input energy of my own, by perfect retroreflection) return all the dissipated energy back to the input once again. We simply let it flow back in, the system collects it again, and then dissipates it again—giving us the same amount of work we had the first time. Then we do it again. And again. I think you get the picture. The fact that energy can neither be created or destroyed, but only changed, means that the "same energy" can be *recycled* over and over. One has to have two different actions: one that changes the form of the energy so we get some work, and the other that retroreflects and recovers the dissipated energy (does negative work!) so that we can recycle it and dissipate it again. In principle, by recycling of energy one can get many joules of work from a single joule of energy. Nature does it every day! Every joule of energy formed at the initial

"Big Bang," is still with us. Every joule of it has on the average already performed many joules of work since then. And as we stated, the anti-Stokes emission process is a concrete example and demonstration that the energy recycling process can be accomplished in physical systems, so that the systems permissibly exhibit COP>1.0.

A most common example is the replenishment of a potential. E.g., the magnetic vector potential can be curled as a **B**-field, and that **B**-field can be totally confined inside a toroid, inside a long coil, or in certain magnetic core materials (as in the motionless electromagnetic generator or MEG for short). The **A**-potential will be replenished as fast as you withdraw the "total **B**-field" from it. So outside the toroid or the long solenoid, you will have as much **A**-potential energy as you started with, and the Aharonov-Bohm effect proves that the energy is there and will interact with electrons. Meanwhile, in the trapped **B**-field you also have drawn off as much energy as ostensibly the **A**-potential contained in the first place.

ENERGY, ELECTROMAGNETIC

Any deterministic or coherent structuring, either dynamic or static, existing in the virtual photon or charged particle flux of vacuum.

Note that, since a photon may also be considered a positron-electron pair, the flux of charged virtual electrons and positrons is included in the flux of photons.

ENERGY FLOW

The passage of energy, in any form, in one direction or generally in one direction.

Even though this "definition" is in error, we now just bypass the unresolved "observables do not persist" problem and the 4th law nature of change (e.g., motion) problem and proceed.

Note that this energy flow may be the overall movement of an omnidirectional energy flux, or it may be the movement of waves, or both. It may be in the kinetic energy of a moving mass. If the flow is everywhere the same, or even approximately the same, we often speak of the entire "flow" as just "energy." Often energy flow is also considered to have occurred from a region of more intense energy flux to a region of less intense energy flux, and vice versa. In other words, energy divergence or convergence is also considered as energy flow. As can be seen, *the usage of the term "energy flow" is not precisely defined in physics! It isn't going to be, at least not in ordinary Aristotelian logic terms.*

ENERGY FLUX

The passage of energy flow, in any form, through a unit area, and in any direction (usually all directions).

This includes both passage in a single direction, or passage in multiple directions at once.

ENERGY, FREE

Any environment or entity which freely emits, furnishes, or makes available energy which can be either collected and used as furnished or transduced into usable form and collected and used to power loads and do useful work.

The word "free" does not apply to costs, but rather to the source of the energy. Of course the ideal is energy that is both free for the taking (collecting and using) and also inexpensively taken and used.

Implicit in the notion of free EM energy from the vacuum are five key concepts: (1) the local vacuum/spacetime itself is filled with EM energy of generally unusable form, (2) some sort of organizing principle is utilized in one part of the circuit or system to cohere the vacuum energy and transduce it into usable EM form, (3) a gating mechanism is utilized to divert the vacuum energy in transduced usable EM form from the active vacuum to the external circuits or load parts of a device, (4) the coherent gated extra energy available in the external circuits or load parts is intercepted by those circuits or load parts, couples to them, and potentializes them with extra EM energy, so that the energy is collected by the system and regauges the system asymmetrically, and (5) the external circuits or load parts then scatter or dissipate the coupled extra energy to produce useful work, without destroying the organizing and gating mechanism that is extracting and furnishing usable EM energy from the vacuum.

ENERGY SOURCE

A function or entity which furnished energy.

Since energy cannot be created or destroyed, there is really no such thing as a "source", though it is a term commonly used. So called "energy sources" actually gate energy, changing it from one form to another. As an example, all 3-space EM energy is gated into 3-3-space from the time-domain. To the gating entity or "source" of the 3-space EM energy, there is an input of EM energy flow from the time domain (complex plane). The source must be a broken 3-symmetry in energy flow, so that more primary 4-symmetry energy flow applies. Hence the conservation law applies to the inflow of energy from the time dimension and the outflow of energy in 3-space.

ENGINEERING, ENTROPIC

Engineering or designing systems and processes whose operation "spills" or wastes some energy.

Entropic systems—which are the products of entropic engineering—thus have COP<1.0 and function in forward-time.

ENGINEERING, NEGENTROPIC

Engineering or designing systems and processes whose operation freely "receives" excess energy, so that they output more energy than the operator inputs, the excess being received from the external environment or other source.

ENTROPY

Thermodynamics term representing a measure of a system's capacity to undergo spontaneous change. In short, a quantity which measures the extent to which the energy of a system is unavailable to do work.

Entropy is given by $dS = dQ/T$, where dS is an infinitesimal change in entropy for a system absorbing an infinitesimal quantity of head dQ at absolute temperature T. In statistical mechanics, entropy is a measure of the disorder in a system and is given by $S = k \ln P + C$, where S is the value of entropy (disorder) for a system in a given state, P is the probability of that state's occurrence, k is a fixed constant, and C is an arbitrary constant. Intuitively, the concept of entropy corresponds to the concept of disorder. We specifically call attention to the fact that the "S" used in representing entropy is not at all the **S** used for Poynting flow.

In physics, a measure of the randomness or disorder of a system. Given by S = k ln g, where S is the entropy, k is the Boltzmann constant, and g is the total number of microstates available to the system. Sometimes stated as S = k ln (multiplicity).

Intimately connected with the Second Law of thermodynamics, which may be stated for the macroscopic case (after Baierlein) as follows: "If a system with many molecules is permitted to change, then—with overwhelming probability—the system will evolve to the macrostate of largest multiplicity and will subsequently remain in that macrostate. Stipulation: allow the system to evolve in isolation. (The stipulation includes the injunction, do not transfer energy to or from the system." [Ralph Baierlein, Thermal Physics, Cambridge University Press, Cambridge, 1999, p. 29].

ENTROPY, NEGATIVE (NEGENTROPY)

In a sense, the reversal of disorder, or reversal of entropy.

Since the normal or forward flow of time is entropic, negentropy is intimately related with time-reversal. This can be seen crudely this way: As a physical thing exists in time, it decays, ages, deteriorates, etc. In short, its ordering as a viable separate thing gets more and more disrupted. If it is then "reordered" precisely back to its original state, that is obviously a time-reversal of that entity.

Since the production of energy is connected to the production of more ordering, then it would seem to follow that any negentropic process also produces more energy. Or, that production of excess energy accompanies a negentropic process, and vice versa.

When we factor in the giant negentropy process, it is seen that all EM spatial energy comes from the time domain, via the broken 3-symmetry of the source charge or source dipole. Here we have a pure negentropic process. Hence we may now advance a new definition of negentropy for electrodynamics: *negentropy is the direct and ongoing conversion of time-energy (time-structuring and time-ordering) into 3-space EM energy*. Dipolarity (polarization) is the process initiating and producing the negentropy. Polarization is accompanied by ongoing negentropy so long as the polarization persists.

Another way of defining negentropy even more rigorously—for electrodynamics—is to define it in spacetime as a *broken 3-symmetry in EM energy flow with concomitant relaxation to a more primary 4-symmetry between time-energy flow and 3-spatial EM energy flow, where time-energy flow is transduced into 3-spatial EM energy flow.*

When a system with one measure of multiplicity progresses to a state with a decreased measure of multiplicity; i.e., when its total number of microstates decreases in the transition. A nonequilibrium steady state (NESS) system can exhibit negative entropy, and the entropy can further decrease progressively toward negative infinity as time passes. [D. J. Evans and Lamberto Rondoni, "Comments on the Entropy of Nonequilibrium Steady States," *J. Stat. Phys*., 109(3-4), Nov. 2002, p. 895-920]. Note that the Second Law of thermodynamics only rigorously applies to an isolates system, where neither mass nor energy crosses the boundary of the system. In the NESS system, that prohibition is violated, hence the second law need not apply. The common source charge is an example of such a NESS system continuously producing negative entropy, because it absorbs virtual energy from the vacuum, transduces it into observable energy, and re-emits the energy as observable photons radiating at light speed in all directions and forming the associated EM fields and potentials and their energy.

ENTROPY (POSITIVE)

When a system in a state with ordering progresses to a state with less ordering, i.e., when its total number of microstates increases in the transition.

ENZYME

Any of various proteins or conjugated proteins (compound of a protein and a nonprotein) produced by living cells, that serves as a catalyst for specific biochemical reactions at body temperatures.

EPIDEMIOLOGY

The study of the various factors influencing the occurrence, distribution, prevention, and control of disease, injury, and other health-related events in a defined human population.

EQUILIBRIUM

In physics, the state of a system in which opposing forces balance each other; i.e., sum to a vector zero.

In mechanics, a system of particles where the net force acting upon each constitutent particle is zero.

In chemistry, the state of a solution where the forward and reverse reactions are equal and balance each other, so that the chemical reactants and products maintain the same amounts.

EQUIVALENCE PRINCIPLE (PHYSICS)

One of the principles of relativity theory. The mass of the body determined by using the gravitational force on it to measure the mass, and the mass of the body determined by using inertial force on it to measure the mass, yield equal measurements for the mass.

ETHER

An extremely fine substance theorized to exist in space in lieu of sheer emptiness.

Discussed by Tesla, Einstein, Whittaker, and others. Originally conceived as the luminiferous ether, a thin material fluid pervading all space. Maxwell, e.g., believed in this material ether, and formulated his theory accordingly. Thus he mistakenly provided forces in the vacuum, which forces require a material vacuum. I.e., mass is a component of force; there is no force without mass, since $\mathbf{F} \equiv d/dt(m\mathbf{v})$. The hoary old medieval notion that a separate force acts upon a separate mass that it affects, is completely in error, though still utilized in mechanics! Modern field theorists know better, but correction of this massive error in physics has not been widely accomplished.

Originally, the ether was seen as a ghostly-thin, *material*, fluid medium postulated to fill space and carry electromagnetic waves, similar to the way in which a gas carries sound waves. Faraday and Maxwell added the assumption that EM fields existed as material taut strings (Faraday's lines of force) with conveniently missing endholders to provide the tension on the strings. The Michelson-Morley experiments eliminated any such material ether, but not a Lorentz-invariant nonmaterial ether (of which vacuum itself is one example, in the modern view). Maxwell's equations were derived from a mechanical ether theory. Einstein once proposed that the vacuum, complete with its electromagnetic fields, should be called the new *ether*. In our own approach we have come full circle back to Einstein's suggestion, since the so-called "fields" are really just curvatures of spacetime and are included in our use of the vacuum as a giant potential comprised of virtual particle flux. The Sachs unified field theory, I believe, is the best available, particularly when the Evans O(3) symmetry electrodynamics is included as a special subset of it. In my own view, I regard "vacuum potential" and "spacetime" as essentially identities. Thus both the vacuum potential and spacetime have further internal structuring and dynamics. In relativity, this view is akin somewhat to the notion of "subspace" used on the Star Trek series.

Today the word "ether" is again acceptable in the literature when used in context of its modern quantum mechanical meaning. The "ether gas"—the quantum mechanical vacuum—is considered to be composed of virtual particles. The particles spontaneously come into being and then vanish so quickly they cannot be individually detected. That is, today the ether is regarded as a sort of specialized virtual particle gas—sort of a gas of "effervescent energy bubbles", so to speak—where the individual particles are continually being created and annihilated at a fantastic rate.

A good reference on the modern view of the vacuum is I. J. R. Aitchison, “Nothing’s plenty: The vacuum in modern quantum field theory,” **Contemporary Physics**, 26(4), 1985, p. 333-391. For an O(3) treatise, see M. W. Evans, P. K. Anastasovski, T. E. Bearden *et al*., "Derivation of the Lehnert field equations from gauge theory in vacuum: Space charge and current," **Foundations Of Physics Letters**, 13(2), Apr 2000, p.179-184. It is shown that the Lehnert field equations in vacuum, with concomitant space charge and current, can be derived straightforwardly from standard gauge theory applied in vacuum, using the concept of covariant derivative and Feynman's universal influence. The Lehnert and Proca field equations are shown to be inter-related through the well-known de Broglie theorem, in which the photon mass can be interpreted as finite. These ideas go some way towards addressing the inconsistency inherent, in Maxwell's famous displacement current, which has no concomitant vacuum space charge.

For technical insight into the attributes for extracting EM energy from the vacuum, see particularly M. W. Evans, P. K. Anastasovski, T. E. Bearden *et al*., "Classical electrodynamics without the Lorentz condition: Extracting energy from the vacuum," **Physica Scripta** 61(5), May 2000, p.513-517. It is shown that if the Lorentz condition is discarded, the Maxwell-Heaviside field equations become the Lehnert equations, indicating the presence of charge density and current density in the vacuum. The Lehnert equations are a subset of the O(3) Yang-Mills field equations. Charge and current density in the vacuum are defined straightforwardly in terms of the vector potential and scalar potential, and are conceptually similar to Maxwell's displacement current, which also occurs in the classical vacuum. A demonstration is made of the existence of a time dependent classical vacuum polarization which appears if the Lorentz condition is discarded. Vacuum charge and current appear phenomenologically in the Lehnert equations but fundamentally in the O(3) Yang-Mills theory of classical electrodynamics. The latter also allows for the possibility of the existence of vacuum topological magnetic charge density and topological magnetic current density. Both O(3) and Lehnert equations are superior to the Maxwell-Heaviside equations in being able to describe phenomena not amenable to the latter. In theory, devices can be made to extract the energy associated with vacuum charge and current. More than a dozen ways to approach extracting EM energy from the vacuum are presented.

EVANS, MYRON W.

Noted chemical physicist, primary developer of O(3) symmetry electrodynamics, and Director of the Alpha Foundation's Institute for Advanced Study (AIAS).

Under Evans, the work of the AIAS has made enormous contributions to physics and particularly to the extraction of usable EM energy from the vacuum. In the opinion of the present author, Evans is perhaps the single most important scientist in the Western world in the emerging field of electrical energy from the vacuum and in solving the world energy crisis.

EVIL

Refers to an act or acts perceived to be detrimental to the receiver or referent, in the positive time stream.

Oddly, the chain of events perceived to involve "evil" to a referent in the forward time stream, would be perceived to be equally *beneficial* to the referent, viewed in the *negative* time stream. In other words, evil in general is a synthesis of the results of observed actions or acts in the *forward time motion*, hence it is conjugated when time flow is reversed.

This is not just an idle question. In our physical body, the photon interaction with the electron shells of the atoms in the body largely determines the observed forward movement of one's material body through time. The conscious mind, fitted to the single photon interaction, thus perceives its "existence" in such terms. Meanwhile, in the nuclei of the atoms of our material body, the charge and hence the field interactions are reversed (giving Newton's third law reactions). That of course is a time-reversed flow of events, not sensed by our conscious mind, but possibly sensed by our deep unconscious mind. The question then arises, "Do we then actually exist both forwards and backwards in time?" In terms of good and evil, if the answer is yes, then this would have profound implications to theology and to the study of human consciousness.

Theologians (and philosophers) have pondered the "nature" of good and evil for literally thousands of years, and have reached no truly firm conclusion to date. The sticking point (theologically) seems to be the puzzle of a perfect, "all good" creator who had to have created evil also (since the Creator is axiomized to have created all). To the question, "How could a perfect Creator have created—or even tolerated—evil?", theologians have yet to find a satisfactory answer. Neither could they find a satisfactory answer to the question of, "How can the Creator, being all-just, and being all-powerful, then allow any evil act to occur?" In short, why does the Creator seemingly not "police up our perceived imperfections in the creation?" In short, theologians struggled with a formidable problem of how to justify the Creator's continued tolerance of evil, even for a moment.

There is no satisfactory answer to such questions, of course, in 3-law Aristotelian logic, because they are four-law logic situations. However, since the 3-logic is incomplete, one should examine the question in 4-law logic, and also in light of one's assumptions regarding the existence of the Creator. The question is unresolvable in 3-law logic and with the assumption of a Creator traveling through time, as we perceive ourselves to do. However, if time itself is a creation, then the axiomized Creator may be more properly axiomized as existing both in and outside time, and "everywhere in time at once" as well. The unlimited Creator must even be postulated to be able to "both be and not be simultaneously; if He cannot do that little trick, He has a limit." That trick must be allowed, else the Creator has a limit and is thus imperfect. But to such an axiomized Creator "permeating time everywhere at once, from beginning to end, which shall be the "beginning" and which shall be the "end?" And if we pick a beginning and an end, what shall be the "intermediate ordering" that we pick? There is no absolute position in either space or time to the "everywhere and everywhen at once" axiomized Creator.

The problem of good and evil then becomes a similar problem to the "wave or particle" question. Good and evil are two sides of the same coin, transposed one into the other by time-reversal. With respect to finite creatures perceiving themselves moving forward in time, not existing in the future and not existing in the past, the question merely demonstrates that our perception itself is in error.

It may be, then, that there is a solution (whether one prefers it or not!) to such profound and ancient philosophical and theological problems in four-law or five-law logic. However, we will leave that question to the logicians and to the theologians to more properly decide.

EXCESS COLLECTED ENERGY

Collection by an interceptor/collector of a greater fraction of the EM energy flow impinging upon it, than is normal.

Any static electric or magnetic charge, e.g., with an EM energy density flow impinging upon it, has excess "energy collection" or "energy collecting" upon it, due to the altered vacuum virtual photon flux that is now exchanging with it. In a nominal electric circuit, e.g., a single "pass" of the EM energy flow from the source dipole, along the circuit conductors and across the conduction electrons, causes an "excess energy collection" upon the intercepting surface charges in the conductors. This potentializes the Drude electrons in the circuit and leads to subsequent dissipation in the loads (and losses) of about 10^{-13} of the EM nondiverged Heaviside energy flow that actually was extracted by the source dipole from the vacuum and sent down through space surrounding the conductors of the external circuit.

That is a single-pass energy collection fraction for a static charge. Almost all the Heaviside energy flow missed the circuit and passed on beyond the circuit "collectors" in one pass-by at essentially the speed of light, on out into deep space and beyond. On the other hand, if the already-passed EM energy flow is retroreflected, so that it returns for another pass along the circuit, then an *additional* amount of the repassing energy can be collected by those sluggish electrons. In a nominal circuit being used as an example, the electrons travel only about 5 or 6 inches per hour longitudinally down the conductors, restrained by the repulsion of the electrons beyond them. So *multiretroreflection*, *multipass*, *multicollection* can be used to provide excess energy and overunity efficiency. This is a change to the present statement of the work-energy theorem, which up to now has assumed single pass, single energy collection. The well-known anti-Stokes emission from certain highly scattering, optically active media, e.g., produces more energy radiating back out of the media than the amount of stimulating radiation energy input into the media. This is Letokhov's "negative absorption of the medium", which is really the excess emission from the medium due to retroreflection and multiple re-collections.

Also, if the intercepting charge is resonated, it sweeps out a greater geometrical cross section in the streaming energy flow, thereby diverging more and thus "collecting" more energy. In the Bohren experiment, e.g., this effect yields collection of some 18 times as much energy by the resonant charge as the same charge collects in static mode.

EXOTHERMIC

Giving off heat, or emitting scattered EM energy. Producing forward time energy.

FARADAY, MICHAEL

Noted English physicist and chemist, 1791-1867, who discovered field theory and electromagnetic induction. Faraday invented the dynamo also and formulated his laws of electrolysis.

His work directly inspired Maxwell, who vowed to study no other electromagnetics theory until he had captured Faraday's work in a mathematical theory.

FIELD

In mathematics, a set with two binary operations. In electromagnetics in more common terms, it is a region consisting of magnitudes and/or vector directions assigned to some active entity (spacetime itself) at each point in the region.

Designated addition and multiplication, satisfying the conditions that the set is a commutative group with respect to addition, that the set with the identity of the additive group omitted is a commutative group with respect to multiplication, and that multiplication distributes over addition for all elements in the set.

For our purposes, in plain language the fundamental notion is that a "field" is a sort of cleared, level space or region (e.g., in spacetime) where things can be placed and actions can occur amongst them, to them, on them, and of them. What the "place or space" is, can get a bit complicated, as can what is placed there and what actions are permitted. In short, we view a field as an altered (curved) region in spacetime, and this special curvature interacts with certain kinds of entities placed in that region. In return, those entities also interact back upon the spacetime curvature to alter it. Hence there is a dynamic two-way interaction between field and matter, where half of this interaction (the back-interaction of charge or matter) is missing from present classical electrodynamics.

EXOTHERMIC EXPLOSION

An explosion where ordinary heat and electromagnetic energy are released and radiate away from the explosive site. All normal explosions are exothermic.

Particularly used for a pulsed longitudinal EM wave interferometer, which in the distant interference zone (IZ) will produce a sudden eruption of scattering EM energy from the local spacetime curvature suddenly induced, when the interferometry transmitter chassis grounds are biased well above the ambient potential in the distant IZ.

FERMI LIQUID

A liquid where the individual particles or molecules comprising it are basically non-interacting, so that they can roam freely.

In an electron gas in a conductor, e.g., treatment of the free conduction electrons as a gas allows a theoretical modeling and explanation of conduction and resistance. Contrast to a Luttinger liquid, where the electrons interact with each other and thus enable the formation of collective phenomena.

FEYNMAN, RICHARD

Noted physicist, Nobelist, and co-developer of quantum electrodynamics.

Feynman is particularly noted for his refreshing three volumes of physics: See Richard P. Feynman, Robert B. Leighton and Matthew Sands, **The Feynman Lectures on Physics**, Addison-Wesley, New York, 1963. The book is particularly noteworthy in that it gives the student some insight into foundations problems in physics. E.g., in Vol. I on p. 2-4, Feynman defines the electric field not in terms of force per unit charge *per se*, but in terms of its potentiality for producing a force only when a charge is present for the force to be developed upon.

FEYNMAN DIAGRAM

A two-dimensional diagram of particle interactions, both in the virtual and observable levels, and both backward and forward in time and named after Richard Feynman who first employed them.

FIBER FUSE

Effect in fibers or fiber optic cable, whose core contains germanium, whereby heating the cable at one spot with a small flame will launch a focused traveling heat energy effect which melts a small hole in the core about every centimeter, and marches down the cable at about a meter per second to the end of the cable, destroying the optical transmission capability and ruining the cable.

Oddly, by igniting the fiber fuse from the other end of the damaged cable, a reverse fiber fuse effect will often march back down the cable in similar fashion except that it fills in the melted holes in the core, restoring the transmission capability of the cable.

If the energy required to melt all the holes (or fill them again) is taken into account, the amount of energy required to launch the fiber fuse is much less. This phenomenon does not appear to have an adequate technical explanation at present.

For an excellent description with photographs, see Ivars Peterson, “Fibers With Flare,” **Science News**, 140(13), Sep. 28, 1991, p. 200-201. For technical information and analysis, see D. P. Hand and P. St. J. Russell, “Solitary thermal shock-waves and optical damage in optical fibers,” **IEE Colloquium on ‘Non-Linear Optical Waveguides’**,” IEE Digest No. 88, London, England, 1988, p. 101-103; — Soliton-like thermal shock-waves in optical fibres: origin of periodic damage tracks," **Fourteenth European Conference on Optical Communication (ECOC 1988),** Sep. 11-15, 1988, Publication No. 292, 1(2), 1988, p. 111-114; — “Solitary thermal shock waves and optical damage in optical fibers: the fiber fuse,” **Optics Letters**, 13(9), Sep. 1988, p. 767-769; D. P. Hand and T. A. Birks, “Single-mode tapers as ‘fibre fuse’ damage circuit-breakers,” **Electronics Letters**, 25(1), Jan. 5, 1989, p. 33-34.

See P. St. J. Russell, “Power Conservation and Field Structures in Uniform Dielectric Gratings,” **Journal of the Optical Society of America A**, 1(3), Mar. 3, 1984, p. 293-299. Russell is actually referring to apparent violation of local conservation of energy. This would be indicated if the vacuum-to-mass interaction is not taken into account. Russell’s analysis therefore supports the fact that (i) the vacuum-mass interaction is required, (ii) the fiber fuse does utilize some of its gated vacuum energy (i.e., the usually non-diverged portion of the Poynting flow), and (iii) the fiber fuse is a legitimate, repeatable overunity process, although a "runaway" process, uncontrolled, and not sustainable.

FIELD

In physics, "a region of space marked by a physical property, as gravitational or electromagnetic force or fluid pressure, having a determinable value at every point in the region."

[Thanks to **Webster's II New Riverside University Dictionary**.]

Here one must *not* think of "space" as emptiness, as mathematicians do, but as a virtual particle flux, a dynamic entity, and as dynamic spacetime. A field then is a set of entities and their relationships and operations in a region of *that* kind of space, where the entities and operations are themselves "space stuff". They are all "virtual" in that they are not individually observable. However, their impact upon or interaction with mass—particularly charged mass—can be and often is observable, in that we can see some change of the mass (its direction of travel, translation, acceleration, deceleration, rotation, generation of current, etc.). If the entities are point-like and are naively supposed to have magnitude only, or if we only specify their energy density magnitude at each point, then that "marked space region" is said to be a *scalar field*. If the entities are point-like but have both magnitude and direction, they are said to be a *vector field*.

Further the deponent saith not because even the foundations physicists are in hot water in trying to define the field, and if the deponent saith more he will surely deep-fry in hot oil!

FIELD, SCALAR

A field, to any point of which is assigned a magnitude only.

FIELD, VECTOR

A field, to any point of which is assigned both a magnitude and a direction.

FLAT (UNCURVED) SPACETIME

A vacuum/spacetime whose virtual particle flux intensity—and therefore its local energy density—does not change as a function of spatial position or averaged time.

That is, a flat spacetime in my view is a quantum mechanical vacuum whose virtual particle flux and energy density are constant in magnitude and internal constitution with respect to spatial position and in averaged time. Note that a flat spacetime (vacuum potential) can still contain vacuum engines, and thus still be *dimensioned*. In that case, contrary to normal physics, the flat spacetime itself will still interact with an embedded object and change it, even though it may not translate it. To perform transmutation of elements, e.g., one is interested in just such engines and not in translating through space the element being treated. This dimensioning or activation of the local flat spacetime can result in an otherwise unexpected, seeming violation of one or more laws of nature in the dimensioned region.

FISSIONING, ACTION

The splitting of the action quantum into two canonical variables (for example, energy and time), only one of which can normally be completely detected or measured. ("Action" has the dimensions of angular momentum—energy x time, momentum x length, etc.)

Fissioning produces length, discrete bit by discrete bit, and time likewise. The physical reality of separated physical objects is thus continually created, discrete bit by discrete bit, monocularly. All that ever observably exists in the "present" is a single quantum change, just occurring. Recombining of the two canonical action fission fragments is called "fusion." Fusion also occurs monocularly, quantum by quantum. Rigorously, the physical world of separated objects never exists as such except in memory recall of vast numbers of past ordered quantum changes that occurred one by one.

FLUX

The amount of some quantity (such as energy, particles, volume of fluid, etc.) flowing across a given area (usually a unit area perpendicular to the flow) per unit of time.

The term flux density is now more commonly used. Loosely, "flux" refers to the perpendicular flow through an area, while "flux density" refers to the magnitude or intensity (rate) of the flux. In some cases such as a flux of particles of different velocities, the number of particles may be multiplied by the average velocity to give an average flux density that is weighted.

FLUX DENSITY

The amount of some quantity (such as energy, particles, volume of fluid, etc.) flowing across a given area (usually a unit area perpendicular to the flow) per unit of time.

FOGAL, WILLIAM (BILL)

Soon-to-be-noted researcher and inventor of the Fogal semiconductor (two patents so far), as well as a superluminal infolding-outfolding communication system and other remarkable longitudinal EM wave processes.

I am happy to be a friend and colleague of Bill Fogal.

FOGAL SEMICONDUCTOR

A special semiconductor invented by Bill Fogal which, in its operational regime, utilizes an integrated semiconductor, tantalum capacitor, and feedback resistor to accomplish charge blocking (blocking of electron current flow dq/dt) while passing displacement current d/dt

The Fogal semiconductor can also accomplish amplified phase conjugation of signals as well as infolding (translation of input transverse EM waves to output longitudinal EM waves) and outfolding (translation of received input longitudinal EM waves to output transverse EM waves). Used in communication systems, it opens the use of the unlimited "infolded" electromagnetics bandwidth. Since it may communicate using longitudinal EM waves, it is also usable for superluminal or a specialized "tunneling" communication through the "interior" of normal EM waves, potentials, and fields.

See William J. Fogal, "High Gain, Low distortion, Faster Switching Transistor," U.S. Patent No. 5,196,809, Mar. 23, 1993; — "High Gain, Low Distortion, Faster Switching Transistor," U.S. Patent No. 5,430,413, July 4, 1995, a continuation of his earlier patent.

FORCE

In mechanics, identically the time derivative of momentum, or **F** ≡ d/dt(m**v**).

Simply, changing of the old concept of mass-motion. One must realize that it is not the mass in motion, but the single undivided quantity "mass-motion" or "mass-velocity" (momentum) that is changed. In short, **F** ≡ d/dt(m**v**). In present EM theory, force fields are erroneously taken to exist in empty, massless vacuum. However, the mechanical definition is an identity, not an equality. Thus force does not *separately exist in contact with* a mass, but *consists of* a changing "mass-motion." Since this force can be induced into and of the mass-motion target at a distance, in the new approach one is confronted with the fact that there is a more fundamental mechanism that produces force itself, and that is a curvature of spacetime.

Distant curvatures of spacetime to produce forces on exposed charged mass systems are also engineered by longitudinal EM wave interferometry.

FORCE FIELD

An effect that exists as a local vacuum virtual particle flux interaction upon and with a unit mass or unit charge whereby a particular type of matter is affected.

The force field has two components, one the mass and the other massless. In electrodynamics, one normally thinks (erroneously!) of the massless component, and refers to that component alone as "the force field." This considers the "force field" as a separate entity, acting upon a separate "mass." Whether it is logically correct or not, that is the prevailing way physics and electrodynamics uses it! So in this definition, let us momentarily accept the common incorrect usage, for convenience, while pointing out the real definition as we need to.

For example, conventionally the EM force fields can affect and change the state of motion of any charged particle or any magnetic particle. In classical physics, the force fields are considered the primary causative agents; when these fields are zero, then the motion of the particle or system is unaffected. Consequently, conventional EM theory assumes that all the EM phenomenology ceases once the force fields are absent. Today we know that is not true at all, as we explain in this glossary.

FORCE-FREE PROPAGATION

Propagation of force-free disturbances in the vacuum flux

(i.e., infolded inside the ambient vacuum potential, or inside a constant DC voltage.) Such "infolded" propagation is not limited to the speed of light, but may even travel in the Coulomb gauge so that it is instantaneous. More usually, it can travel superluminally. It may be regarded as a special form of "tunneling", which is known (both theoretically and experimentally) to produce superluminal propagation to the external observer. The music of Beethoven's 40th symphony, e.g., has been experimentally transferred between two points in a physical waveguide by such "quantum tunneling" at over four times the speed of light in vacuum.

We regard tunneling as moving in a sort of "subspace", i.e., within the internal structuring of spacetime itself. It is not limited by the speed of light and Einstein's postulate, which we believe only applies to signals moving in spacetime in bulk, and not to signals moving *within* substructuring inside that spacetime.

FOUNDATIONS OF MATHEMATICS

The concepts, operations, assumptions, postulates, logic, definitions, and axioms of algebra systems.

FOUNDATIONS OF PHYSICS

The postulates, assumptions, concepts, and definitions upon which a scientific physics model rests. Included are the postulates, concepts, assumptions, definitions, and operations of the mathematics in which the scientific model is expressed, as well as the postulates, concepts, assumptions, definitions, and operations of the physics entities and functions assigned to the mathematical symbols.

Thus "scientific truth"—even mathematical truth (see Morris Kline's **Mathematics: The Loss of Certainty**—is actually a *qualified* truth. What is true in one model (one set of postulates, assumptions, concepts, and definitions, including those in the algebra) may not be always true when one or more of the postulates, assumptions, concepts, and definitions is/are changed, and/or when the topology of the mathematics in which the model is expressed is changed, etc.

The major flaws in present physics models involve errors in the foundations. However, a successful physics model is rather quickly dogmatized and often turned into a belief structure by many scientists rather than being regarded as a tentative model. Consequently, scientists who attempt to do serious work in foundations are generally ignored or ostracized and rather vehemently attacked if they propose any significant changes to one of the dogmatized models. Particularly, all funding and "benefits" of the scientific bureaucracy are denied the heretical foundations scientist, unless he or someone can rather quickly come forth with an iron-tight experimental proof of the heresy. Any attempted change in foundations is usually met with ad hominem attack, a barrage of criticism, loss of position, and denial of research funding. Science has a long history of just such dogmatic oppression of great scientific discoveries. To name a few (there are hundreds): The first laser paper was rejected by the journals as being ridiculous. When Mayer proposed conservation of energy, he was hounded and ridiculed so fiercely that he suffered a nervous breakdown and attempted suicide. Years later, near the end of his life conservation of energy was adopted because it greatly facilitated understanding and calculation, and the same system now lionized him as a scientific hero. Ovshinsky suffered personal attack, ridicule, and charges of charlatanism in pushing amorphous semiconductors; everyone knew that only crystalline semiconductors could work. The situation changed when several thousand Xerox machines were observed to now contain amorphous semiconductors which were working just fine! Louis de Broglie's matter wave hypothesis caused consternation to his thesis advisors; but because he was Prince Louis de Broglie, they felt obligated to send it to the great Einstein so that he would reject it and then they could regretfully reject the thesis of the Prince. When Einstein replied that it was probably true, they felt they had no choice but to publish it *because de Broglie was a Prince of the old French aristocracy, and as such was not to be casually trifled with.* So foundations work is fraught with the greatest peril to the practitioner. Yet it is the most important work in physics, and it is a continuing black mark against the scientific establishment that they do not openly encourage *and fund* the most able physicists, grad students, and post-docs to examine and revise the errors in foundations concepts and postulates. Because of the prevailing dogmatism, science itself continually strangles the new ideas and concepts that would provide the physics of the 22nd century now. In an eerie turn of events, science has become in a strange way its own worst enemy, and the strongest barrier to the advance of science.

FOUR-SPACE (4-SPACE)

The "normal" spacetime used in physics, consisting of three spatial dimensions and one time dimension. Minkowski spacetime.

FOURTH LAW OF LOGIC

the law that a thing and its opposite become identical on the boundary, i.e., in multiple simultaneous observation. Identity is merely the loss of observational or perceptual distinction; when formerly "two" objects are simultaneously observed by a single observer, two slides have been shown at once in the slide projector. It does not matter at that point what each was individually observed to be before; now there is no observable distinction or difference. We previously showed that the law is implicitly assumed in the three laws of Aristotelian logic anyway, and published a simple proof of the fourth law. Without the fourth law, Aristotelian logic "eats itself". What results in the four law logic is that either (1) the three laws apply explicitly and the fourth implicitly, or (2) the fourth law applies explicitly and the fourth implicitly. This *application rule* itself can be taken as a fifth law of logic. The fourth law is also the law of the paradox: I.e., when something is true but violates one or more of the Aristotelian laws, it is a case where the fourth law applies explicitly. The conclusions derivable from a four law logic agree generally with the conclusions derivable from G Spencer Brown's **Laws of Form**.

FOUR-WAVE MIXING

A nonlinear multiwave mixing effect when four waves mix in a highly nonlinear situation so that wave to wave interaction occurs.

FRACTIONAL CHARGE

A hypothetical particle having a charge less than the electron's charge. Often called a quark, where its charge is 1/3 or 2/3 the charge of the electron.

A few years ago, Stanford University researchers found evidence of free quarks. There is also now the fractional Hall effect. In the 1920's Ehrenhaft reported the discovery and production of fractional charges of all sizes, and his experiments have been replicated by Michailov, with papers by Michailov and Barrett.

In the new approach, when time-energy is utilized, quarks can be freed or nearly freed rather easily in "time-reversal zones". It would appear that, as the new approach develops, free quarks will become a normal event rather than one intensely sought but terribly difficult to come by experimentally.

FRAME, LORENTZ

A frame of reference which is not accelerated with respect to the laboratory observer.

In this case, the frame may be rotated (moving at a constant velocity) but it is not rotating (the frame is not accelerated with respect to the observer, and spacetime is not curved). In this case special relativity applies, as do the conservation laws. If the local spacetime is curved, the frame is accelerated and spacetime is curved. Locally, then, general relativity applies. In this case, locally the conservation laws (energy, momentum, charge, and spin) can be violated. However, in ordinary general relativity, it has been tacitly assumed that locally the curvature of spacetime is negligible. Hence locally a Lorentz frame is assumed, and the conservation laws are assumed to apply locally also. In scalar electromagnetics, the local spacetime is always curved and general relativity applies locally. In this case, the conservation laws need not apply.

FRAME, REFERENCE)

A spatial, organized, measured lattice placed in "emptiness" (space, spacetime).

Normally refers to a 3-dimensional, spatial frame. All objects and points in the "universe" or spatial frame are considered to simultaneously coexist at separate, measured points in the frame. Differs from the vacuum in that, rigorously, vacuum has no existing definite lengths and no existing definite time intervals, as these appear only after measurement or detection, and are relative to the observer and to the interactions ongoing as well as in the detection process itself. The "laboratory frame" is the static reference frame of the observer or measurement. A separate reference frame may be assumed to exist for any fixed or moving object, or centered on any point in another frame. When a type of frame is assumed, the entire class of physical interactions that can occur has been restricted to an assumed set or type. In other words, given the frame, the *conventional* physics has been assumed. One of the greatest restrictions of an assumed "frame" is to rule out the consideration (existence) of other higher dimensions.

Note that, in the new unified field theory approach, the other higher dimensions are always available and cannot be ruled out in general, but only in some special case. Every curvature of spacetime, and any internal additional curvature to that primary curvature, adds a new dimension. In our view, a spacetime may be "flat" in overall curvature, but consist of internally structured deterministic curvatures or "engines". In this view, normal inertial frames, e.g., may still contain vacuum engines, which will not affect the normal *bulk translation* rules, but may affect any or all of the nontranslation mechanisms, including the very laws of nature in many cases.

FREE ENERGY

Excess energy freely received from its external active environment by an open system that is far from thermodynamic equilibrium in its exchange with that environment.

To use this free excess energy, it must be collected, transported to a load or loads with minimal losses, and then dissipated in the load(s) to power them, without any substantial portion of the free energy being used to close the system's "gate" through which the excess energy is input to it.

There is a separate thermodynamics for such open systems far from thermodynamic equilibrium in their active environmental exchange. Such a system is permitted to exhibit five "magic" functions: it is permitted to (1) self-order, (2) self-oscillate or self-rotate, (3) output more energy than the operator himself inputs (the excess energy is freely received from the active environment, (4) power itself and its load simultaneously (all the energy is freely received from the active environment), and (5) exhibit negentropy.

The entropy of such a system cannot even be calculated. Some useful references are: Ilya Prigogine with D. Kondepudi, **Modern Thermodynamics: From Heat Engines to Dissipative Structures**, Wiley, Chichester, 1998; Ilya Prigogine, **The End of Certainty: Time, Chaos, and the New Laws of Nature**, Free Press, New York, 1996, 1997; G. Nicolis and I. Prigogine, **Exploring Complexity**, Piper, Munich, 1987; Gregoire Nicolis, "Physics of far-from-equilibrium systems and self-organization," Chapter 11 in Paul Davies, Ed., **The New Physics**, Cambridge University Press, Cambridge, 1989, p. 316-347.

FREE ENERGY SYSTEM

Any open system not in thermodynamic equilibrium, which freely receives excess energy from an external source,

...and collects and utilizes this free excess energy to freely power external loads, so that a permissible system COP>1.0 is achieved, as allowed by the nonlinear thermodynamics of open systems in disequilibrium with their environment.

Implicit in the notion of free electromagnetic energy systems are six key concepts: (1) the local vacuum/spacetime is known to be filled with hidden (i.e., virtual) energy in violent motion, i.e., the local vacuum/spacetime is a violent virtual energy flux and therefore a scalar potential, (2) a broken symmetry—i.e., some sort of organizing and gating mechanism, such as the common dipole—in this hidden (virtual) energy flux of the vacuum is utilized as a source, to cohere the virtual energy and divert it as energy flow **S** = **E**×**H**, from the broken symmetry initiation point onto the external circuits or load parts of a device, (3) the coherent gated extra *virtual* energy flow available in the external circuits or load parts couples to (interacts with) the mobile charges in those circuits or load parts, so that gradients developed in the interacting virtual flux form force fields on and of the particle masses, driving the mobile charges along the circuit and through current-impeding circuit components such as loads, (4) in the interaction of the driven charges with the driving virtual energy flux, their spin and erratic motions integrate a tiny "coupling fraction" of the driving virtual energy into observable (i.e., macroscopic field) energy, thus creating the **E**-fields and **B**-fields, (5) the current-impeding external components or load parts scatter or dissipate the coherence of the driven charges, and thereby dissipate the collected energy or change the form of the collected field energy, thereby producing useful work, and (6) little or none of the excess collected energy in the circuit is split off and dissipated in the gate (asymmetry component serving as the **S**-flow source) to destroy the gate and thereby destroy its asymmetry in the vacuum flux, which is what is extracting and producing the free energy flow.

FUSION, ACTION

In the new approach, the recombining of two canonical bits of a fissioned action quantum.

The fusion process "cancels" the bits produced by the fission process, and constitutes a negative spacetime operation. The physical world is thus eliminated, bit by bit, in a monocular fusion operation that produces the "past". The "mass" of a particle is taken to be proportional to, and identically comprised of, the absolute value of its fission and fusion rate. When fission and fusion rates of a particle are equal, the particle is unaccelerated; when unequal, the particle is accelerated. Vice versa, when the particle is unaccelerated, the fission and fusion rates are equal, and when the particle is accelerated, the fission and fusion rates are unequal.

GAIA HYPOTHESIS

The hypothesis by Lovelock that the earth and its biosphere is a living thing, at least in some sense.

In the new viewpoint, there exists a biospheric quantum potential which contains an extended mind and therefore is indeed an extended lifeform—one which includes the earth and the quantum potentia all its creatures and species. In the new sense, even so-called "inert" matter is alive, being continually bathed by energy flow dimensioned with lifeform templates, and therefore equally alive in all directions and nonpreferential.

GATE

Refers to something (a component or function) which extracts some part of a flux or flow, compacting it into a stream, and "sending it out."

A moving board wall or gate may be swung into a river, e.g., to divert or "gate" some of the river's flow out into a sluice ditch and on to a waterwheel powering a mill. Similarly, a dipole extracts some of the energy from the vacuum virtual photon flux exchange with the end charges of the dipole, and "gates" (diverts) the extracted portion of energy out from the ends of the dipole as energy flows. This creates the scalar potential surrounding each charge, and also the **E**-fields. Even a "static" dipole does this "gating" of vacuum energy into an energy flow.

The fundamental gate for all EM energy in 3-space is the dipole or dipolarity. The source of the 3-space EM energy continuously emitted by any charge or dipole is an equal inflow of EM energy from the complex plane (from the time domain). Thus EM energy flow is conserved in 4 dimensions but not in 3-space. In particle physics, it is well-known that any dipole or charge is such a broken 3-symmetry in its fierce vacuum energy flux exchange. However, particle physics considers the input energy to be virtual particle energy from the vacuum and therefore random energy. Whittaker 1903 shows it is actually from the time domain of spacetime (from the complex plane) and the input energy flow from the vacuum is not random but precisely organized in a harmonic set of longitudinal EM phase conjugate waves. Of course by wave-particle duality we simply consider the two pictures to be just different and permitted models of the same thing.

GATING EFFECT

The effect of extracting part of a flux or flow, compacting it into a useful stream, and "sending it out."

See *gate*.

GAUGE

In electromagnetism, usually considered a possible choice for (change of) electric scalar potential and magnetic vector potential, without any net change of force fields so that the change satisfies Maxwell's equations.

Interestingly, gauge field theory includes the axiom of gauge freedom. In EM systems, this means that one is free to "regauge" or change the potential energy of the system freely and at any time, so long as the change results in a static stress potential energy change. In the real world, one may have to pay a little bit for switching. But essentially physics already assumes that one can cause his EM system to take on excess potential energy at will, so long as it is a *stress potential* energy change only.

In short, only the *symmetrical* regauging case has been considered in electrodynamics. Yet every electrical power system must first potentialize the system *asymmetrically* rather than symmetrically. In the theoretically perfect system, this asymmetrical regauging is done freely. Hence every electrical power system first breaks gauge symmetry, in order to take on extra energy so that it can do work. Further, the source of the potential energy flowing into the asymmetrically regauged electrical system so freely, comes from the source dipole's extraction of EM energy from the time-domain (complex plane) due to its broken 3-symmetry in EM energy flow.

So the highest "gauge" principle is that energy can be freely extracted from the vacuum, anywhere and at any time, freely and easily, by making a dipolarity—which changes a single potential and asymmetrically regauges the system.

It follows that one is in theory free to "dissipate" this excess free energy in external loads to power them. Again, in the real world one may have to pay some switching costs, but that can be minimized by efficient switching. However, since no conventional electrical power system accomplishes this free powering of its loads, it rigorously follows that the conventional system must self-enforce symmetry in its discharge of the free potential energy achieved by the initial *asymmetrical regauging*.

Thus, if we believe gauge field theory—the most modern of physics theories and in many ways the most useful—and also believe its assumption of free asymmetrical regauging that is hidden in its gauge freedom principle, then COP>1.0 electrical power systems are absolutely permitted by nature and by gauge field theory where asymmetrical regauging is deliberately used.

It follows that some feature in electrical power systems as we presently design and build them, must be preventing these systems from exhibiting overunity COP. And so it is. The ubiquitous closed current loop circuit results in the circuit forcibly and symmetrically regauging itself while dissipating its excitation energy to power its loads and losses. This forces half the collected regauging (free) energy to be dissipated in the external circuit's loads and losses, and half of it to be dissipated in the source dipole to scatter the charges and destroy the dipole. This means that less than half the available free regauging energy is used to power the load, while half is used to destroy the entity—the source dipole—actually furnishing the free regauging energy from the vacuum.

Hence all our present electrical power systems are inherently free energy systems freely extracting their energy from the vacuum, but are fiendishly designed so that they kill themselves (shut off all free asymmetric regauging energy from the vacuum, by destroying the source dipole) faster than they catch some of the free energy from the vacuum to power their loads.

To restore the source dipole requires at least as much energy dissipation as was done to destroy it. In our conventional self-destructive systems, the generator shaft must thus be continuously powered in order to form the magnetic field inside the generator, so that this magnetic field can then dissipate its available energy to force the scattered charges back apart to form an ordered source dipole.

We pay the power company to have a giant wrestling match inside its own generators and *lose*. And in a sense, we do it because our theoreticians love gauge symmetry more than they tolerate broken gauge symmetry. So they build lovely, symmetry-restoring electrical power systems—and monstrously mangle and destroy the fragile biosphere in the process.

GAUGE FREEDOM

The axiom in gauge theory that one can freely change the potentials of an EM system, so long as the net new forces resulting from the change will sum to a zero vector resultant so that the system remains "symmetrical" in its force-field functioning with respect to the system prior to the change of potentials.

Gauge and gauge freedom are actually formal restrictions of an even more important asymmetrical regauging principle: *a potential in a system can be freely changed at any time, thus freely changing the potential energy of the system freely and at will*. Symmetrical regauging is achieved only by multiple application of this asymmetry rule to provide a net symmetry condition again, with a change in locked-in stress potential energy of the system.

GAUGE SYMMETRY

Abstract mathematical symmetry of a field, that relates to the freedom to regauge (change the value of) potentials, without affecting the values of the field quantities.

In short, the higher principle that the potentials can be changed freely and at will—and hence the potential energy of the regauged system can be changed freely and at will—is arbitrarily restricted to a very special case: Each change of potential involves the appearance of an new free force field. This *asymmetrical* change can be made freely and at will, at any time. However, the notion of gauge symmetry restricts any set of such changes to the special case where the new free force fields produced must sum to a net zero force field of opposing forces. In short, it severely restricts the freedom to change the potentials—to the special case where the resulting change of the system's potential energy must remain a static stress potential energy condition. Note that this arbitrarily eliminates any overunity functioning of the regauged system in which the altered potential(s) and altered system potential energy exist(s). See the discussions of *gauge* and *gauge freedom*, above.

GAUGE THEORY

A field theory using a field that has one or more gauge symmetries.

Note the accent on gauge symmetry and the net *symmetrical* regauging restriction. This restriction is a carry-forward of the old notion that the potentials are not primary, but the fields are primary causes of all EM phenomena.

For the overunity researcher, broken gauge symmetry is the interesting feature which must avidly be sought in his experimental systems. Hence he must seek out and familiarize himself with a wide variety of *broken symmetry effects* and phenomenology. He must also rigorously analyze his circuits with a keen view to where gauge symmetry can be broken, where and how gauge symmetry is automatically restored during excitation discharge, etc. Unless the automatic self-enforcing of symmetrical gauge transformation during excitation discharge is violated, no EM system can produce COP>1.0. In addition, without elaboration, the overunity researcher must also learn to consider the time-domain functions of the circuit, and particularly the giant negentropy of the common dipole. Unless he understands that all EM energy comes from the vacuum and from the complex plane via the broken 3-symmetry of a dipolarity, he cannot understand his own circuits.

Electromagnetics was the first gauge theory. Gauge theory is widely utilized today, and particularly in particle physics. In overunity power systems, the system must exhibit a broken gauge symmetry at least twice: (1) in initially potentializing the system to freely increase its potential energy, thus exciting the system so that it has energy with which to do work, and (2) then discharging this free excitation energy in the load without simultaneously destroying the source dipole providing the continual potentializing.

The conventional COP<1.0 electrical power system restores net 3-space symmetry by continually destroying the "free asymmetrical regauging" component: the source dipole, and using more of the energy freely received from the vacuum via dipole asymmetry to destroy the dipole than is used to power the load. This requires that at least as much 3-space energy be input to the system again, to restore the dipole and thus potentialize the external circuit, as was used to destroy the dipole. Hence as much 3-space energy has to be input as is dissipated in all the loads and losses, including inside the generator. For that reason, our scientists and engineers unwittingly but deliberately design and build only COP<1.0 systems.

Without elaboration, we also accent that spacetime curvature is always involved in an overunity EM power system, and the tempic (time) potential of the output end of an overunity system differs from the tempic potential of the input end, so that the gradient (the tempic force) is directed from output to input—exactly the reversal of the case for a COP<1.0 power system.

GAUGE TRANSFORMATION (IN ELECTROMAGNETICS)

In EM, gauge transformation is conventionally taken to be the addition of the gradient of some function of space and time to the magnetic vector potential—and simultaneously the addition of the negative of the partial derivative of the same function with respect to time, divided by the speed of light, to the electric scalar potential.

This procedure gives different potentials but leaves the electric and magnetic fields unchanged. It restricts gauge transformations to *net symmetrical* transformations. However, the increase or decrease in potential energy of the system, due to changing the potentials, results in a change in the stress of the system and a change in its stress energy. This is because two new antiparallel forces are created, which change the stress of the system.

In essence, gauge symmetry then involves the implicit assumption that a functioning system is the same regardless of how it is stressed, and regardless of the state of its stress energy. We point out that, gravitationally, this is not true since any change in the local potential energy of the system is a spacetime curvature change, hence a gravitational change.

GENERAL THEORY OF RELATIVITY

Einstein's theory of gravity in which the gravitational force is represented by a curvature in spacetime.

GIANT NEGENTROPY (OF THE DIPOLE)

The receipt from the time domain of spacetime (the vacuum), by any dipolarity, of enormous longitudinal EM wave energy flow, transduction of that absorbed energy from the complex plane into real 3-space, and emission of that enormous energy flow in all directions in 3-space, automatically and indefinitely after a little energy has been expended to separate the charges and make the dipole. The EM waves in the input from the time domain and the output in 3-space are perfectly ordered and correlated, which is a giant ordering of the vacuum/spacetime and is thus a giant negentropy.

In circuits, the source dipole in the generator or battery, once made, performs this function. Only a minuscule fraction (some 10^{-13}) of the energy pouring out of the generator's or battery's terminals strikes the surface charges of that attached external circuit and is diverged into the conductors to power the Drude electrons and the circuit. All the rest is just wasted.

See my paper, "Giant Negentropy from the Common Dipole," *ibid*.

GRAVITON

The quantum (smallest piece) of the gravitational field, with spin 2.

In the quantum theory of general relativity, the graviton is massless and has spin 2. In the new approach, a graviton is considered to be a paired (coupled) photon and antiphoton, each of which has spin one, so that the graviton couplet has spin 2. A scalar potential is comprised of gravitons, not merely photons, since it can be decomposed into a harmonic series of bidirectional wavepairs. In each wavepair, a wave and its antiwave precisely superpose. We insist on a further strong condition: that in the biwave, the photons comprising the wave and the antiphotons comprising the antiwave also must obey the *distortion correction theorem*. This means that the antiphotons and photons are passing through each other in opposite directions, continually coupling into gravitons and decoupling again.

GRAVITY

The phenomenon characterized by the physical attraction of any two material bodies.

Actually, in modern general relativity it is the trapped energy in the masses that produce the gravity potentials. Ideally, the gravitational force between two masses is proportional to the product of the masses divided by the square of the distance between them. In the new approach, one recognizes that mass itself is defined in terms of, and identically consists of, the time derivative of an action flux. [For a force-free fundamental definition of mass, see T.E. Bearden, **Quiton/Perceptron Physics: A Theory of Existence, Perception, and Physical Phenomena**, National Technical Information System, Report AD-763210, 1973.] A photon flux is also an action flux. A virtual photon flux is an action flux. So the vacuum consists of a gigantic action flux—which with certain interactions forms mass itself. But since photons are action quanta and photon flux is action flux, and since mass and gravitation are functions imposed on such action flux; then mass, EM, and gravitation become different aspects of the same thing. All of them can be electromagnetically engineered, directly, as indeed can be the flow of time itself. By affecting the flow of time electromagnetically, one is thus able to affect the gravitational force between two objects electromagnetically. Antigravity, for example, can be achieved by a mechanism that is given in this glossary. Hutchinson has demonstrated the levitation of objects weighing up to 60 lbs., albeit sporadically and uncontrollably. At my urgent request, Sweet performed a highly successful antigravity experiment some years ago, reducing the weight of a 6-pound object by 90%, smoothly and controllably, in several smoothly controlled steps. I consider that the experiment tested and validated my approach to an engineerable mechanism for antigravity. For the results of the test, see Floyd Sweet and T.E. Bearden, "Utilizing Scalar Electromagnetics to Tap Vacuum Energy," **Proceedings of the 26th Intersociety Energy Conversion Engineering Conference (IECEC '91)**, Boston, Massachusetts, 1991, p. 370-375.

GROSS PARTICLE TRANSLATION

Refers to translating the entire particle in space, rather than internally structuring the particle's potential (massless charge).

GROSS POTENTIAL GRADIENT FIELDS

The usual gradient in a scalar potential's gross magnitude, as in $-\nabla\phi$.

GYROELECTRONS

Spinning electrons considered as gyroscopes, so that when longitudinally perturbed they can and will laterally precess.

Considering (in a gross first order model) the conduction electrons in the Drude gas in a conductor as little gyros, because they are (i) spinning on an axis, (ii) severely restrained in their ability to move forward longitudinally down the conductor as current, and (iii) much more free to precess laterally in the conductor. Thus when the gyroelectrons in the receiving wire antenna, perturbed by an incoming longitudinal EM wave in the vacuum, are longitudinally perturbed, they precess laterally so that our instruments (which detect electron wiggles, not the incoming vacuum EM wave) do detect "transverse waves." However, they are detecting the transverse gyroelectron precession waves. The old electrodynamicists, long before the electron or the atom was discovered, simply envisioned the incoming EM wave as "waves in the thin material fluid ether" which were "intercepted" as electric fluid waves in the antenna. Hence since their instruments reported that the intercepted "electric fluid" was vibrating transversely, they firmly believed (erroneously) that this proved the ether wave to be transverse also, just as those "taut string waves" that Maxwell and Faraday had believed in. That is the total *raison d'etre* behind the mistaken notion of the transverse EM wave in the vacuum ether!

HARMONIC SERIES

Consisting of a fundamental frequency, its first harmonic, its second harmonic, etc.

HEAVISIDE, OLIVER

Noted English self-taught physicist and brilliant electrodynamicist, 1850-1925, who played a role in discarding Maxwell's quaternions, and also played a role in forming vector mathematics and formulating the vector reduction of Maxwell's theory from 20 quaternion equations in some 20 unknowns to the present 4 vector equations.

What are presently taught as "Maxwell's equations" in university are actually Heaviside's equations.

Lorentz symmetrically regauged the Maxwell-Heaviside equations, again greatly simplifying their mathematical solution—and also unwittingly discarding all permissible overunity Maxwellian systems in the process.

HEAVISIDE ENERGY FLOW COMPONENT

(1) The enormous nonintercepted and nondiverged energy flow component pouring out of the terminals of the battery or generator, and missing the external circuit entirely so that it is wasted.

(2) The enormous energy in the EM field, potential, or wave that misses the interaction of the field, potential, or wave with the assumed unit point static electric charge.

(3) See also discussion under Giant Negentropy.

HERACLITUS

To be added.

HERTZ, HEINRICH

Noted German physicist who together with Heaviside and others transformed Maxwell's theory from quaternion algebra to vector algebra, and who also produced EM waves, thus confirming Maxwell's theory.

HIDDEN BIWAVES

Those bidirectional EM wavepairs that comprise the scalar potential are indeed "hidden" with respect to our normal "electron translation" (i.e., electron wiggle) detectors and instruments.

HIDDEN VARIABLE THEORY

A class of quantum mechanical theories which considers that the quantum state of a physical system is not a complete specification after all. The "hidden variables" are those additional components necessary to provide the "complete state" of the system.

The hidden variables are those extra components of the theorized complete state, which are not contained in the quantum state. Bohm's hidden variables theory is the best known of all of these theories, and makes the same predictions as does the conventional quantum mechanics. In addition, it eliminates the terrible problem of the "missing chaos," eliminates the quantum measurement problem, and it suggests that quantum mechanics can be engineered if the hidden variables themselves can be engineered. In the new approach, one goes a step further by considering hidden EM variables infolded inside the potentials themselves, including inside the quantum potential utilized by Bohm. The advantage of this assumption is that it poses an *engineerable* interpretation, after work by Stoney, Whittaker, and Ziolkowski. Further, the Russians have utilized this type of EM hidden variable theory, along with the quantum potential, to develop secret advanced weapons. The physics of this area is called *energetics*.

HIERONYMUS, T. GALEN

Founder of the American version of radionics, who patented a radionics machine and process to start the cycle of radionics in this country.

HILBERT, DAVID

Noted German mathematician, 1862-1943, who did advanced work in geometry, theory of invariants, integral equations, and mathematical physicist.

Noted particularly for his development of Hilbert space.

HOLE (ELECTRON HOLE)

An unfilled vacancy in an ordering of electron energy levels, as in a lattice or in the Dirac Sea.

Electron energy levels have two energy states: (1) *positive energy* state, and (2) *negative energy* state. The positive energy states are associated with the positions of normal energy electrons. The negative energy states are almost all filled, and this is the Dirac sea.

The absence of an electron from either energy state creates a particular kind of hole. When an electron is absent from an electron positive energy state position in a lattice, that results in an excess of positive charge at that point vacated by the electron. Note that when an electron then refills that hole (recombination occurs), the electron remains in a positive energy state, does not disappear, and no radiation occurs.

When an electron is lifted from an electron negative energy state in the Dirac sea, that leaves behind a hole in the negative energy state in the Dirac sea. When an electron subsequently refills that hole, it "falls" in and disappears, decaying to a lower energy level and emitting radiation due to the difference in the energy levels.

The difference between holes in the Dirac sea and holes in the electron positive energy levels in a lattice, are very different. In short, they lead to two quite different kinds of "hole and electron" interactions. In the lattice "hole-filling" (recombination), there is no excess radiation given off and the electron does not disappear from the positive energy continuum. In the Dirac sea hole-filling, excess radiation is given off and the electron disappears from the positive energy continuum.

Under the influence of an electric field, a *positive energy* hole in a crystal lattice—where an electron has left and is therefore absent—will effectively propagate through the lattice as a positive charge, but usually much slower than the electron propagates in the opposite direction as an electron current. The process is actually more complex and involves continuous interaction with the electrons and their physical distribution pattern and location. The hole current is mathematically treated as a special positive charge current, often referred to as a positron current. In a current-carrying conductor or semiconductor, one has a current of electrons traveling in one direction and simultaneously a current of holes (hole positrons) traveling in the opposite direction, but recombining.

As stated, in addition to lattice holes, there also can exist unfilled holes in the Dirac negative energy states comprising the vacuum, particularly when fields are present. In this case, it is a *negative energy* hole. A positive energy electron that falls into a Dirac sea hole will emit energy as it falls to that lower energy state. To lift one of the electrons from the Dirac sea and leave a hole, energy must therefore be added to the negative energy electron in the Dirac hole.

When fields are present, Dirac holes may exist and may move as hole current in circuits under certain conditions. The situation is complex; see Felix Finster, "Definition of the Dirac Sea in the Presence of External Fields," **Adv. Theor. Math. Phys**., Vol. 2, 1998, p. 963-985. Updated copy (version 4) is on http://xxx.lanl.gov/abs/hep-th/9705006.

When a free electron fills a positive energy hole in a lattice (positive electron energy state), this effectively disposes of both the hole and the *free* electron which is now a *bound* electron, and is called *recombination*. The electron does not disappear. In a material lattice, there is no energy radiation from this, just the disappearance of the hole and the "binding" of a free electron so that it is no longer free.

In visualizing positive hole currents, passing the hole current though a surplus of available electrons (as in a negative charge donor material) will result in "hole filling" and recombinations. One may therefore speak of disposing of unwanted hole current by recombination, and in fact this is widely accomplished in semiconductors by controlling the doping.

HOLE CONDUCTION (LATTICE)

The movement of electron vacancies (holes) in a lattice continually left behind by hopping of the electrons as they break loose from their bonded positions and move freely in an electron current.

When an electron hops out of a lattice bond, it leaves behind a bonding gap or "hole" in the positive electron energy state at that bond site, so that an extra positive charge appears there at the hole. As the electrons move in one direction in a conducting lattice, the holes move in the opposite direction in a "positive current", but at a much slower pace than the electron current moves.

HOLE CURRENT (LATTICE)

See *hole conduction (lattice)*.

HOMEOPATHY

A system of medical treatment based on the theory that certain diseases can be cured by giving very small doses of substances which in a healthy person would produce symptoms like those of the disease. (Opposed to allopathy).

Homeopathy is based upon formation and use of dimensioned potentials (particularly the potential composed of the extremely rapid "making and breaking" hydrogen bonds in a fluid) containing vacuum engines. Any material or solute, and therefore any molecule, contains its own specific vacuum engine, its own charges, and its own dimensioned potential. Dissolving the material in water, or even using a suspension of it in water, allows the bonding potential in the water to interact with the potential of the solute or suspension. Potentials superpose, and they also diffuse and mix their inner structures (vacuum engines) into each other. So the material or solute diffuses its vacuum engines into the interior of the hydrogen bonding potential, in effect ordering and templating the hydrogen bonding itself! Vigorous shaking of the suspension or solution assures that all the fluid and H-bonding potential is exposed to the solute of suspended particles, so that a thorough exchange of vacuum engines occurs. This process in homeopathy is called *potentizing*. It's actually just creating the desired internal vacuum engines in the H-bonding potential of the water. Once that's done, there's really no further need for the solute or the suspended particles. By repeatedly diluting the solution to the extreme, then one can reach a point where there is a high probability that not a single molecule of the original solute is remaining in the fluid. Yet in each dilution, shaking can be used to insure the even spread of the vacuum engines through the newly introduced H-bonding potential in the newly introduced water. At the end, there exists an altered fluid whose H-bonding potential now contains the desired vacuum engines. Drinking that water now introduces those vacuum engines into the body fluids, bloodstream, etc. The ingested dilute new vacuum engines will then diffuse through the various potentials of the body, and produce altered chemical functioning of the kind that could have been induced by the chemical or active solute material. The advantage is that the harsh material residue of the chemical or solute is not present in the body, as it is when allopathy is utilized.

HYPERFUNCTIONING

Functioning in hyperspace as opposed to 4-dimensional Minkowski space.

Higher topological functioning.

HYPERSPACE

Refers to a space of more than four dimensions, and specifically to those spatial dimensions outside the normal three.

IDENTITY OF OPPOSITES

On the boundary, A and not-A are identical. If all of a thing is collected, one reaches the boundary of that thing and it turns into its own opposite.

INERTIAL FRAME

A frame of reference in which force-free bodies move along straight lines, and the postulates of special relativity are valid.

In the new approach, this notion is extended; even in an inertial frame, force-free bodies may move along straight lines, the postulates of special relativity may remain valid, and yet the EM hidden variable may induce other changes in the usual laws of nature due to the action of hidden vacuum engines infolded in the *dimensioned* local spacetime (vacuum potential).

INFOLDED HIDDEN DYNAMICS

Refers to:

(i) Bohm's hidden variable theory and the internal dynamics of the hidden variables/entities themselves, and

(ii) to the hidden biwave pairs comprising a scalar potential, with the internal dynamics of those waves such as tuning off harmonic frequency, multiplication, variation of phasing and magnitude, etc.

Also, by Whittaker 1903 the scalar potential can be decomposed into the bidirectional wavepair set in harmonic series. By Whittaker 1904, each of the waves in a biwave pair can be further decomposed into two potentials, so each pair of waves would consist of four potentials. That is, the entire set of internal biwave pairs can be replaced by four times as many internal "partial potentials" as was the number of biwave pairs. Then Whittaker 1903 can be applied once again to break each one of those scalar potentials into new biwave pairs, and so forth and so forth. So the potential can be expressed as waves within waves within waves, or potentials within potentials within potentials, and so on. The neat thing is that each successive infolding (internesting) is a higher dimensional functioning and a higher topology. So one can build (with some little pain!) specific infolded wave patterns that will work in—say—the 7th dimension of hyperspace, or the eighth dimension, and so on. This is why I called the internal structuring of a potential (or the two potentials comprising an EM wave) *dimensioning* the potential or the wave. As a half-baked nuclear engineer whom the Army never let practice his discipline, I wanted some way to directly engineer the nucleus. *That has now been found*. Unfortunately it has also already been highly weaponized in secrecy by one or more foreign nations. In other words, one can design a signal and assemble it (with some difficulty) that will flip one quark in a nucleon in an atom. That way one can transmute an element either into the next higher element isomer or the next lower element isomer. Using a quantum potential to "transport" the necessary vacuum engines, the effect can be accomplished at a great distance, in multiple targets simultaneously, and the effect is not shieldable. "Jumps" in nuclear transmutation can also be accomplished. The migration of electrons to and from an atom (as in solution, e.g.) makes and negates ions continuously. Thus continually the external potentials and the nuclear potentials intercommunicate. This means that their vacuum engines continually diffuse. Any dimensioning of the external potentials will be passed into the nuclear potentials as a dimensioning action also. If certain conditioning vacuum engines are present in the external potentials, then the slow diffusion into the nuclear potentials begins to affect the nucleons and their interactions, the quarks comprising the nucleons, the particles such as pions continually exchanged between nucleons, etc. The mechanism for nuclear transmutations and production of new species is there! I believe, e.g., and am working to more clearly express, that the major mechanism producing the new nuclear species in cold fusion experiments just such dimensioned potentials, involving the inadvertent dimensioning of potentials comprised of the hydrogen bondings of the water and other factors.

INFOLDED REAL VECTOR COMPONENTS

Well, simply take a set of real force vectors that altogether sum to a vector zero resultant.

That "vector zero system" is a zero with respect to forced *translation* of a particle or mass. It is not an absence per se, but is the presence of specifically hidden and "infolded" real vectors. Two elephants pushing each other to a draw form such a "zero-translating" system. That "zero system" is quite different from two crickets pushing against each other to a draw! Anyone who thinks all zeros are "absences" and who thinks all zeros are equal, is invited to try standing between the crickets and observing how he feels, then standing between the elephants and see how he feels. The latter might be a real bummer. So zeros can differ! And a zero can be a presence of many real things, all still there but "infolded" and "hidden," but just the absence of any *one and only one* thing. Even in arithmetic, e.g., we are free to pull 5-3-2 right out of 0, or pull out 4-7+8-6-2+5+1+1-3-1/2-1/2 (if I got the arithmetic correct!). And so on. So we have always *used* the fact that a net zero can have a real internal composition, without detailing it exactly. We teach our schoolchildren to do it, but fail to tell them what they are doing!

When you sum EM force fields to zero, the fields are still there and real. You have altered the energy of the system or volume, and also the potential energy of the system or volume. And you have done it in specific directions, magnitudes, etc. along the "fingers" of the infolded patterns. In short, you have made a specific vacuum engine. Mass, fluid, nuclei, molecules, etc. exposed to that "conditioned vacuum potential" may well undergo physical and chemical and electrical changes. Golden once performed experiments which powerfully conditioned the local vacuum, and all clocks and watches (mechanical, electrical, etc.) in the local area were awry for four days.

INFOLDING

With reference to signals, infolding means "placing the signal or modulation or change upon one or more of the internal bidirectional wavepairs comprising the scalar potential.

Since all EM potentials ultimately represent changes to the ambient vacuum potential, one has conditioned or altered the vacuum itself when infolding is utilized. Infolding of EM signals, vectors, and directions produces *vacuum engines*. By Whittaker's principle and Bearden's corollary, these vacuum engines can be designed to affect matter—including atomic nuclei, nucleons, etc.—in any manner desired.

INFORMATION CONTENT OF THE FIELD

Russian euphemism for the structuring of the hidden longitudinal EM waves and their dynamics, that comprise any EM potential, field, or wave.

INFRASONIC

Below sonic.

Frequencies below what the ear can hear. Below about 20 Hertz.

INTERFEROMETER

An instrument in which a wave is split into two waves or beams, which after traveling over different paths are subsequently reunited and display interference.

INTERFEROMETRY

Measurement of wavelengths of light and very small distances and thicknesses,

...for determining indices of refraction, and for analyzing small parts of a spectrum by means of the interference phenomena of light.

INTERNAL SPACE

To be added.

ITERATED

Done repeatedly, like picking beans one at a time.

JOSEPHSON EFFECT

Flow of Cooper pairs (superconducting electron pairs) across a thin dielectric separating two superconducting electrons, in the absence of a voltage drop.

That is, the pair of electrons can "tunnel" through a thin insulating barrier.

JOSEPHSON JUNCTION

The thin dielectric separating two superconducting electrons, with subsequent Josephson tunneling of Cooper pairs.

JOSEPHSON TUNNELING

See *Josephson effect*.

JOULE

A measure of energy.

One joule equals one watt for one second. In physics the unit of work or energy in the MKS system, being the amount of work done by one newton acting through a distance of one meter, equal to 10,000,000 ergs.

JUNG, CARL GUSTOV

Noted Swiss psychiatrist and psychologist who founded Jungian analytical psychology, formulated the principle of synchronicity, and advanced and delineated collective unconscious mind.

From the content of his German patients, Jung predicted WW II two decades before it occurred.

KINDLING

Coherent integration (adding) of similar virtual components among the vast "noise" of dissimilar virtual components, so that the "signal-to-noise" ratio of the integrated signal steadily increases, and the integrated "observable signal" grows out of the background virtual state noise.

This "kindling" process is directly analogous to coherent integration of nondiscernible radar signals far beneath the received noise, to build and extract the real radar return signals from targets. This sort of process dramatically increases the "sensitivity" of the radar. Real, very tiny signals even 100 dB or more beneath the noise level can be retrieved in such fashion by modern radars.

Similar processes can integrate very minute signals already passed into the virtual state and presumed to be nonexistent. Usually, however, the difference frequency between two frequencies at least one harmonic interval apart must be used, considering the vacuum's virtual flux state as an isotropic nonlinear medium.

One may also hypothesize that potentials and propagating signals may decrease with distance, but are never truly "lost" in that they never reach a total zero. When they reach the quantum level, further decrease in amplitude simply results in their passing into the virtual state (subquantum level).

KIRCHHOFF'S CURRENT-LAW

At any time, the sum of the instantaneous currents flowing into a node or point in a circuit equals the sum of the instantaneous currents flowing out of that node or point.

KIRCHHOFF'S VOLTAGE LAW

At any time, the sum of all voltage rises in a closed loop circuit equals the sum of all drops in that closed loop circuit.

LAMB, WILLIS EUGENE JR.

American physicist and Nobelian who discovered the hyperfine structure of the hydrogen spectrum, and first measured the interaction of the vacuum energy that generates a change in the energy levels of the hydrogen atom, according to Dirac's theory and quantum electrodynamics.

LAMB SHIFT

A very small correction to the first excited state of the hydrogen atom due to interaction of the vacuum.

Willis Lamb experimentally confirmed this prediction of quantum electrodynamics to high accuracy.

LAMELLAR CURRENT

Current in thin layers.

Thin layers of current. Thin sheets of current.

LASER

A device that generates light in which all the photons are exactly in step and produce a coherent beam.

Laser light has one wavelength and is more easily controlled than other kinds of light. Use of a laser to perform interferometry is one way to create holograms; use of a laser to illuminate a hologram is one way to read it. Originally the word "laser" was an acronym that stood for "light amplification by stimulated emission of radiation." Note that when TiO_2 particles in suspension, with a small amount of fluorescent dye added, are weakly illuminated by a small coherent light source (a laser), a tremendous room-filling output of coherent light emission occurs, by the anti-Stokes emission effect. This is lasing without population inversion, and it is a validated and easily testable overunity process. This is the process patented by Lawandy.

LASING WITHOUT INVERSION

The amplification of coherent light in an intensely scattering medium, comprised of certain powdered laser crystals or suspensions of similar material, where a variety of phenomena such as gain narrowing and amplifying random walk of light propagating in the medium, combine to give laser emission with diffusive feedback.

Gain tends to depend on the volume of the medium, so that at a certain medium the gain in light amplification by the medium exceeds the losses, and the laser action results above this critical volume. The intensity of the light scattering (multiply reflecting) in the medium then will increase rapidly until an "explosion" of light results in an intense flash of coherent light in all directions from the medium volume.

If the excitation is still present, the process will be repeated and the energy density will again exceed the critical value, rapidly generating another intense flash of light. This process can be repeated many times, given the presence of continued excitation.

A very interesting phenomena that can occur is coherent backscattering. Here the light scatters over both a forward-time path and a time-reversed path, perhaps with each path consisting of more than 1,000 scatterings. Because of time-reversal symmetry, the two waves (forward and backward) acquire exactly the same (though random!) phase. So the two waves after all this 1,000 scatterings on their paths, meet and interfere constructively in the direction back toward the exciting light source.

In theory the mean free path can be made shorter and shorter, so that all the light would be trapped inside the medium. This is called Anderson localization, and it has been reported in the literature; see D.S. Wiersma, P. Bartolini, A. Lagendiji, and R. Righini, "Localization of light in a disordered medium," **Nature**, Vol. 390, 1997, p. 671; John Sajeev, "Frozen light," *ibid.*, p. 661-662.

This work grew out of original work called out by Letokhov but largely ignored for more than two decades.

References: D. Wiersma and A. Lagendijk, "Laser action in very white paint," **Physics World**, Jan. 1997, p. 33-37; — "Light diffusion with gain and random lasers," **Physical Review E54**, 1996, p. 4256; N.M. Lawandy et al., "Laser action in strongly scattering media," **Nature**, Vol. 368, 1994, p. 436; V.S. Letokhov, Generation of light by a scattering medium with negative resonance absorption," **Sov. Phys. JETP**, Vol. 26, 1968, p. 835.

Note that we have nominated a version of this process, together with consideration of the erroneously discarded Heaviside nondiverged energy flow component, as the fundamental mechanism proposed to be involved in gamma ray bursters, x-ray bursters, and in some gamma ray and x-ray flashes associated with atmospheric phenomena on earth in thunderstorms, etc. We also nominated the missing Heaviside energy flow component as the agent accounting for the excess gravity (some 90% of the total gravity) in the arms of spiral galaxies that hole those arms intact so they do not fly apart. See T.E. Bearden, "Dark Matter or Dark Energy?", **Journal of New Energy,** 4(4), Spring 2000, p. 4-11 (also available on http://www.cheniere.org); — "Giant Negentropy from the Common Dipole," **Proceedings of Congress 2000**, St. Petersburg, Russia, Vol. 1, July 2000 , p. 86-98. Also published in **Journal of New Energy**, 5(1), Summer 2000, p. 11-23. Also carried on DoE open website http://www.ott.doe.gov/papersbooks.html and on http://www.cheniere.org.

LAW OF PHYSICS

A restriction placed upon the physical mechanisms that can occur under certain broad assumptions as to the background situation and environment.

Actually, in nature there are no such rigidly fixed "laws"; these are only man's synthesis for the behavior of large classes of systems under very general conditions. Any "law of physics" can be violated if the conditions contained in its assumptions are violated. Conservation laws are often touted as "laws of physics." Actually, the conservation laws assume a closed system or one in equilibrium, and a linear spacetime (Lorentz frame). If either or both of these assumptions is locally violated, any or all of the conservation laws can be violated locally, even though the overall global conservation is still upheld. Quite simply, in that case one has opened the system (broken symmetry). In particle physics, broken symmetry already results in violation of one or more of the conservation laws. In leading Russian physics journals, papers are regularly published containing unrestricted general relativity with concomitant violation of any and all conservation laws.

LAWANDY PATENTS

Patents covering and related to anti-Stokes emission (excess emission of energy) in strongly scattering, optically active media such as TiO2 particles in suspension.

More energy is emitted than one must input to stimulate the effect. It is being hailed as a new form of lasing, without the requirement for population inversion.

LETOKHOV, V. S.

Russian pioneer in excess emission phenomena from stimulated media.

LETOKHOV EFFECT

The excess emission (overunity emission of energy) phenomena in strongly scattering, optically active media, usually referred to as "negative absorption of the medium".

For an overview, see V. S. Letokhov, “Stimulated emission of an ensemble of scattering particles with negative absorption,” **ZhETF Plasma**, 5(8), Apr. 15, 1967, p. 262-265; —“Generation of light by a scattering medium with negative resonance absorption,” **Sov. Phys. JETP**, 26(4), Apr. 1968, p. 835-839; — “Laser Maxwell’s Demon,” **Contemporary Physics**, 36(4), 1995, p. 235-243.

LOCALITY

Characteristic where interactions are local in spacetime.

LOCALIZED

Confined to a small region of a large system rather than being extended through the system or at a distance.

LOCAL VIRTUAL PHOTON FLUX OF VACUUM

Refers to a local region of the vacuum, which also refers to the vacuum flux density of that region.

LONGITUDINAL COMPONENT

In EM waves, the longitudinal component of the fields along the direction of travel,

...as opposed to the transverse components at right angles to the direction of travel.

LONGITUDINAL E-FIELD

We may divide any electrical field into two components, a transverse component and a longitudinal component.

Of course one or the other may be a zero vector.

LONGITUDINAL GRADIENT

Compression wave gradients (differences) in density or pressure,

...considered in a direction from their origin along the direction of primary movement, vs. transverse waves, which act perpendicular to that direction.

LONGITUDINAL INTERIOR WAVE

In conventional theory, the electric portion of the EM wave is a transverse field oscillation, and the longitudinal component is essentially zero.

In the new "infolded" wave approach, there is no overall transverse gradient in the vacuum potential, but there is an infolded longitudinal gradient which oscillates "inside the vacuum potential." This is rather like a "pressure wave" transmitted under water, without causing a surface wave involving physical upheaval and fall-off of the water. In EM, by analogy the speed of the "bulk upheaval" transverse wave is nominally c, the speed of light in vacuum [but see discussion of galloping waves, for what really happens!]. The speed of the pressure wave, under water, may be very much greater than c, because it is a special "tunneling" process and it also involves the galloping wave effect. Experimental measurement of superluminal tunneling velocities—such as more than 4c—are already well-known in the literature.

To better visualize this "pressure wave," consider that it is like a sort of "velocity modulation" upon the edge of the conventionally-visualized plane wave front of a traveling transverse wave, except now the plane itself does not move. All the succeeding planes are "bumped" by the velocity modulation of one plane, and so the velocity modulation propagates through (inside) the vacuum potential as a modulated pressure wave, without transverse change of the potential.

Now we have a very special medium! It consists of bidirectional EM wave pairs, one passing through the other. In such a case, it is already known that the speed of a "planar wave front" in the superposition and resulting interference of two oppositely moving waves can in fact greatly exceed the speed of light momentarily, then slow dramatically below than the speed of light, etc., so long as the average velocity is c. This is called the galloping wave effect. [E.g., see William G. Harter et al., "Galloping waves and their relativistic properties, **American Journal of Physics**, 53(7), July 1985, p. 671-679.]. Since the plane wavefront within the interior *can* in fact vary its velocity, we are quite free to use this "velocity pulse modulation" effect of wavefront speed variation, to place signal intelligence upon the planar wave front speed variations. So we can transmit hidden pressure waves with intelligence on them, through the interior of the vacuum potential. *Further, the restriction to an average velocity of c does not have to apply, and the planar pressure pulses can be transmitted much faster than c*. This is the basis of the work Fogal and I are struggling with, in order to achieve superluminal communication. It is also what we have been struggling with in an effort to come up with a communication system that can propagate infolded signals inside the H-bonding potential of the ocean itself, so that high-data-rate communications with deep submarines could be utilized, at any distance, and the huge, gawky, frightfully expensive, and environment-affecting ELF systems be done away with. We also think it should eventually be possible to develop an underwater radar type of system, but it's far too early at this point to try to conceptualize just exactly how it would work.

LONGITUDINAL WAVE

A "pressure" type of wave, similar to sound, in which the vibrations are along the direction of travel of the wave.

Hence, a wave composed of alternating densifications and rarefactions, where we focus upon the longitudinal component of the changes. In the past we have used the term "scalar waves" to imply longitudinal standing waves, such as in one infolded Stoney-Whittaker wavepair inside the scalar potential. In classical EM theory, the Poynting vector predicts no longitudinal wave of energy from a time-varying, electrically charged source. In fact, even in the ordinary theory, an exact solution of the problem does allow this longitudinal wave, as shown by Keech and Corum, **International Journal of Theoretical Physics***,* 20(1), 1981, pp. 63-68. Conventionally, as explained elsewhere in this glossary, the classical electromagnetic wave is modeled as a vector string wave, comprised of transverse vibrations on implicitly assumed material taut strings in the vacuum. In the new approach, such transverse vector force field waves (Hertz waves) do not exist *as such* in vacuum; instead, two coupled, dynamic scalar potentials exist there. The **E** and **B** fields are formed and exist as the these potentials and their gradient coupling to spinning charged detecting mass particles.

LONGITUDINALLY

Of or in length. Running or placed or operating or changing lengthwise. Opposed to transverse.

LORENTZ, HENDRIK ANTOON

Renowned Dutch physicist and Nobelist, 1853-1928, who developed the Lorentz transformations and Fitzgerald-Lorentz contraction.

He shared the Nobel Prize for discovering the Zeeman effect.

LORENTZ INVARIANCE

An inertial frame is independent of the velocity of the frame relative to any other frame.

LORENTZ INVARIANCE PRINCIPLE

The principle that the laws of physics are the same in all reference frames.

LORENTZ REGAUGING

Changing the two potentials in the Maxwell-Heaviside equations in potential form so that the resulting equations have the variables separated.

An unfortunate effect is that this discards all Maxwellian systems far from equilibrium in their vacuum exchange, hence discards all permissible Maxwellian COP>1.0 systems.

LORENTZ SYMMETRY

Referring to the symmetrical regauging by Lorentz of Maxwell's equations.

LORENZ, LUDWIG VALENTIN

Scientist who first changed Maxwell's equations—two years after their publication in 1865—by (effectively) symmetrically regauging them, thereby unwittingly discarding all Maxwellian systems far from thermodynamic equilibrium with the active vacuum.

See L. V. Lorenz, "On the identity of the vibrations of light with electrical currents," Philosophical Magazine, Vol. 34, 1867, p. 287-301. In this paper Lorenz gave essentially what today is called the Lorentz symmetrical regauging.

Comment: (gratefully received from T. Barrett) This paper gave f(t-r/c) functions. Fitzgerald said that Lorenz's functions were essentially the same as his, and Fitzgerald became a leading proponent of "retarded potentials". But it is believed that Fitzgerald was unaware of Lorenz's work until the 1880's, so he is given credit for parallel development. Some people talk of Fitzgerald-Lorenz functions. This is a regauging, but the term "gauge" (inspired by railroad gauges) was first introduced by Hermann Weyl in the 1900s. He used it for a change in length and was shot down by Einstein's theory—Weyl's theory was not relativistic. The idea resurfaced in the 1920s when quantum theory was being formulated, but this time it meant "change in phase" and not "change in length".

Comment by T.E.B.: Thus "Lorentz" regauging of Maxwell's equations really was first done by Lorenz in 1967. However, not too much attention was paid to L. V. Lorenz' work (e.g., by Fitzgerald). When H. A. Lorentz later used symmetrical regauging (essentially Lorenz' regauging), his influence was so great that it was adopted straightaway and has remained adopted to this day.

LOW ENERGY NUCLEAR REACTION (LENR)

Cold fusion, or the anomalous transmutations of elements which occur in certain electrolytes with specially prepared palladium electrodes.

The transmutations occur even though in conventional theory there is insufficient energy to accomplish them.

Conventional science has rather vehemently attacked cold fusion and many of the cold fusion scientists, even though there are now hundreds of successful experiments in multiple laboratories throughout the world.

In our view, once the properly-prepared palladium lattices are loaded with positive ions, the formation of temporary, fleeting time-reversal zones in the electrolyte temporarily reverses the law of attraction and repulsion of charges. Thus H+ ions, e.g., may attract each other in even numbers (opposite numbers are forbidden by the Pauli exclusion principle), so closely that each enters the strong (nuclear) force region of the other, so that the group becomes a quasi-nucleus. Note that the gluons are partially "unglued" by the TRZ formation, and so the preferred method of "decay" of the anomalous TRZ state as the surrounding electrolyte ions move to negate it, is by flipping of a quark. One D+ ion coupled to one H+ ion, e.g., when attracted into a quasi-nucleus in a TRZ, may decay into tritium by flipping one quark and changing one of the protons into a neutron. Two H+ ions may decay into deuterium (D+) by flipping one quark and turning an H+ into a neutron. Two D+ ions may simply "tighten further" into a real nucleus as the TRZ decays, and result in an alpha particle (helium nucleus). The TRZ hypothesis does precisely explain the most important reactions that are experimentally shown to occur. For more on this hypothesis, see T. E. Bearden, "EM Corrections Enabling a Practical Unified Field Theory with Emphasis on Time-Charging Interactions of Longitudinal EM Waves," **Explore**, 8(6), 1998, p. 7-16; — ., "EM Corrections Enabling a Practical Unified Field Theory with Emphasis on Time-Charging Interactions of Longitudinal EM Waves," Journal of New Energy, 3(2/3), 1998, p. 12-28.

MAGNETIC DIPOLE

Paired north and south magnetic poles of equal strength over microscopic or macroscopic distance.

MAGNETIC INDUCTION

The act of a change in magnetic field producing an electric field at right angles, which in turn produces electron flow.

MAGNETIC SPIN

Refers to the intrinsic angular momentum, known as spin, of electrons, protons, and neutrons, etc.

The electrons combined in an atom or ion have a resultant angular momentum, that is the combined intrinsic spin of the electrons and the angular momentum due to their motion around the nucleus. There is also a magnetic moment associated with this angular momentum (spin) whenever it is nonzero. Therefore atoms or ions with nonzero spin are *magnetic* atoms or ions. This is often loosely referred to as "magnetic spin." It is actually the magnetic moment of nonzero spin.

MAGNETOELECTRONICS

New microelectronic components which exploit the spin of the electron rather than its charge.

References: A Barthelemy *et al*., "Giant Steps with Tiny Magnets," **Physics World**, Nov. 1994, p. 34-38; G. Prinz, "Magnetoelectronics," **Science**, Vol. 282, 1998, p. 1660.

MAGNETORESISTANCE

A change in electrical resistivity in a material when a magnetic field is applied to the material.

MAGNETORESISTANCE, COLOSSAL

A very large change in electrical resistance observed in the manganese perovskite materials when a magnetic field is applied to them. The effect in these materials is the largest magnetoresistance effect known at present.

See N. A. Babushkina *et al*., "Metal-insulator transition induced by oxygen isotope exchange in the magnetoresistive perovskite manganites," **Nature**, Vol. 31, 1998, p. 159; L. I. Balcells *et al*., "High-field magnetoresistance at interfaces in manganese perovskites," **Phys. Rev**. **B**, Vol. 58, 1998, p. R14697; M. Blamire *et. al*., "Understanding and utilizing colossal magnetoresistance materials," **Phil. Trans. Roy. Soc. A**., Vol. 356, 1998, p. 1469-1712.

MAGNETOSTATIC SCALAR POTENTIAL

Roughly, the "pole strength" differential between the two poles of a magnetic dipole.

Anyone who wishes may polish this definition.

MASSLESS DISPLACEMENT CURRENTS

Currents without mass.

Examples in the standard theory include $d\phi/dt$, $d\mathbf{E}/dt$, $d\mathbf{P}/dt$, $d\mathbf{B}/dt$, etc.

MATTER

Highly condensed 3-spatial energy, compressed by the factor c^2 …

and with the observation process d/dt having been applied to the fundamental masstime entity to provide mass as a frozen snapshot. Matter, of course, has internal structure, order and organization, and dynamics. All matter is in a continuous energetic exchange with its vacuum (4-spatial) environment.

MAXWELL, JAMES CLERK

Brilliant scientist who first formulated the unified theory of electricity and magnetism.

James Clerk Maxwell was born on June 13, 1831 in Edinburgh, Scotland. In 1847 he entered the University of Edinburgh, then transferred to Cambridge in the fall of 1850. After graduation, he stayed on at Cambridge in a research position. He was elected a Fellow of Trinity College and placed on the staff of college lecturers. In 1856 he returned to Scotland, where he took up a Chair of natural Philosophy at Marishal College, Aberdeen. In autumn, 1860 he took a new position as Chair and Professor of Natural Philosophy and Astronomy at King's College, London (a position he held until 1865, at which time he resigned). Maxwell was financially independent. He was elected to the Royal Society in 1861, while at King's College. From 1865 to 1871 he resided at his ancestral Scottish country home, Glenlair, developing his major ideas into book form. Maxwell returned to Cambridge in 1871, where he became the first holder of the Cavendish Chair of Experimental Physics. There he also supervised the construction and operation of Cavendish Laboratory. His treatise on electromagnetism appeared in 1873. He held his position at Cambridge until he died on Nov. 5, 1879 at age 48, of a form of stomach cancer—the same ailment that had killed his mother when he was a child. [Thanks to **Encyclopaedia Britannica**!]

MAXWELL (UNIT)

Unit of magnetic flux, in the cgs system.

MAXWELL'S ELECTRODYNAMICS

Maxwell's electrodynamics is Maxwell's equations.

MAXWELLIAN SYSTEM

Any physical or electromagnetic system whose electrodynamic operations obey James Clerk Maxwell's electrodynamics model.

The term is usually applied with respect to those systems which obey a highly reduced subset of Maxwell's after the Lorentz regauging of the Maxwell-Heaviside equations. This subset is now inappropriately referred to as "Maxwell's equations". This is unfortunate. As a result, today many scientists and most engineers no longer understand that Maxwell's theory—when embedded in a higher topology algebra—permits a vast richness of additional EM systems and behaviors, including full unified field theory operations. In the standard U(1) gauge symmetry electrodynamics, all these higher symmetry functions and systems are excluded *a priori*. From our view, this is particularly sad since these arbitrary reductions of Maxwell's theory arbitrarily excluded all EM systems far from equilibrium in their exchange with the active vacuum. Hence almost all scientists and engineers believe it is against the very laws of nature to propose an electrical power system that produces more energy out—and more work in the load—than the energy input made by the operator himself. This sad error has resulted in (1) crippled electrical power systems that extract their output energy from the vacuum but kill themselves faster than they power their loads, (2) the giant pollution of the earth, (3) extraordinary energy costs, (4) struggles and wars over oil and energy resources, and (5) the looming giant economic collapse of the economies of many nations. Further, unless this latter facet is checked, it may also lead to (6) the unleashing of all the weapons of mass destruction in the arsenals of many nations, destroying all civilization and much of the biosphere.

McCREA

To be added.

MICHELSON, ALBERT ABRAHAM

German-born American physicist who invented an interferometer (Michelson interferometer) named after him. Michelson used his interferometer in a renowned experiment designed to measure the velocity of the earth through the ether, which would produce a shift in his interferometer pattern. No such shift was observed, which indicated the absence of an ether wind and was largely responsible for the downfall of the concept of the material ether which had been assumed previously.

Reference: Albert A. Michelson and Edward Morley, "Influence of Motion of the Medium on the Velocity of Light," **American Journal of Science**, Vol. 31, 1886, p. 377-386; — "On the Relative motion of the Earth and the Luminiferous Ether," **ibid.**, Vol. 34, 1887, p. 333-345.

MIND

From the medical view, with thanks to **Webster's Medical Desk Dictionary**, Merriam-Webster Inc., Springfield, Massachusetts, 1986: (1) The element or complex of elements in an individual that feels, perceives, thinks, wills, and especially reasons; (2) the conscious mental events and capabilities in an organism, (3) the organized conscious and unconscious adaptive mental activity of an organism.

See an extended discussion of *mind* under *energy*.

MIND-BODY COUPLING

To be added.

MIND-MATTER INTERACTION

The n-space interaction between the time-like mind and its time-like operations and the 3-spatial physical body and its 3-space operations. To first order, we may treat these interactions in four dimensions.

MIND OPERATIONS

To be added.

MOTION

To be added.

MOTIONLESS ELECTROMAGNETIC GENERATOR (MEG)

Transformer-like COP>1.0 electrical power generator invented by Bearden, Kenny, Hayes, Moore, and Patrick which powers the transformer core with a permanent magnet, but separates the curled magnetic vector potential A (the magnetic field B) from the uncurled magnetic vector potential A, so that the magnetic field flux is retained in the core while the A-potential is replenished outside the core and adjacent to it.

The overunity mechanism is thus provided by a version of the Aharonov-Bohm experiment, which proves that this splitting of the A-potential does occur and that the uncurled A-potential will interact energetically with electrons. In short, by "splitting the potential" and potentializing two paths to the same energy density as the original unsplit potential, the MEG doubles the available potential energy available via the permanent magnet dipole's broken 3-symmetry in the active vacuum. Both the curled A-potential (magnetic field) inside the core and the uncurled A-potential outside the core interact simultaneously with the output coils when pulsed. Thus the output coils "doubly interact" instead of singly interacting. This "double-dipping" of available energy flow allows permissible COP>1.0, since the system is far from equilibrium with the active vacuum exchange.

Pulsing applies the Lenz law effect to both the split potentials, further increasing the energy density of the two interactions with the output coils. The MEG nominally exhibits from COP = 1.7 to COP = 10, using two input coils.

See M.W. Evans, P.K. Anastasovski, T.E. Bearden et al., "Classical Electrodynamics Without the Lorentz Condition: Extracting Energy from the Vacuum," **Optik** 111(6), 2000, p. 246-248; — "Inconsistencies of the Maxwell-Heaviside Theory of Electrodynamics: The Aharonov-Bohm Effect," **Journal of New Energy**, 4(3), Winter 1999,p. 236-240; — "Vacuum Energy Flow and Poynting Theorem from Topology and Gauge Theory," submitted to **Physica Scripta** (in review); — "The Aharonov-Bohm Effect as the Basis of Electromagnetic Energy Inherent in the Vacuum," submitted to **Optik** (in review), — "Explanation of the Motionless Electromagnetic Generator with O(3) Electrodynamics, **Foundations of Physics Letters**, 2001 (in press). See also T.E. Bearden, "Energy from the Active Vacuum: The Motionless Electromagnetic Generator," in M.W. Evans (Ed.), **Contemporary Optics and Electrodynamics**, Wiley, 2001, 3 vols. (in press), comprising a Special Topic issue as vol. 114, I. Prigogine and S.A. Rice (series eds), ***Advances in Chemical Physics***, Wiley.

MULTICOLLECTION

Multiple collection of the same energy flow, by rerouting the passed Poynting energy back around to the collectors for another pass by them, with additional collection.

A common means of "returning" the Poynting flow for additional collection is retroreflection, as in phase conjugate reflection. Since a nominal energy collection fraction on a single pass is only about 10^{-13}, a great many re-passes of the same energy can be returned. Work is done on the collector in each pass. One joule of energy can actually perform many joules of work; this is a change to the usual statement of the work-energy theorem, which assumes single pass, single collection only.

MULTIPASS RETROREFLECTION

Iteratively retroreflecting the same Poynting energy flow, each time it impinges on and passes by an intercepting collector, so that multiple passes of the same energy flow are made onto and by the collector.

More and more of the passing enormous energy is collected as more and more passes by are made. The collected energy is then dissipated as work in the circuit or device. Such processing can allow overunity EM circuits and devices.

MULTIPASSES

Multiple passes. See multipass retroreflection.

NANOTECHNOLOGY

The fabrication of devices with atomic or molecular precision, to produce operating devices with minimum feature sizes less than 100 nanometers.

Often described as a marriage between chemistry and engineering. The self-assembling of the units is referred to as *molecular manufacturing*, and the devices are built one atom or molecule at a time with programmed nanoscopic arms. As occurred with the modern machine and technology age, the first requirement is to develop the tools that do the working, and the "tools that build the tools." That fundamental work is off the ground and running already.

Nanomanufacturing plants capable of manufacturing bulk materials or arbitrary structures with atomic precision are envisioned, with almost every atom being placed precisely as desired.

Nanotechnology may well produce the next great scientific revolution. As an example, nanobots have been visualized that will circulate in a human body's bloodstream and specifically attack cancer cells. Nanobots for cleaning up air and water pollution are possible. Food synthesis is envisioned since the technology provides the ability to combine molecules directly.

As with all technologies, the ethics lies in the hands of the system designer and the user. Increased technology always allows greater use for good and greater use for bad purposes. Because of the extraordinary "evil uses" that can be employed in the use of nanobots, Bill Joy, chief scientist of Sun Microsystems, recommends no further development of nanotechnology and no further research. He stated,*"... we have the possibility not just of weapons of mass destruction but of knowledge-enable mass destruction… hugely amplified by the power of self-replication… we are on the cusp of the further protection of extreme evil…"*

Joy's fears are well-founded. Already the union of artificial intelligence with self-replicating nanobots is foreseen. If that union is successful, one can foresee the unleashing of what can only be called "species" of self-replicating, smart nanobots bent on the mass destruction of humanity in various ways.

Also, contrast the nanobots to our discussion of even more advanced nanotechnology of causal system robots (CSRs) using functioning system of causal fields (sets of longitudinal EM waves and their dynamics, prior to having interacted with charged mass, and thence being systems that are functioning sets of spacetime curvatures). We have already survived one massive world-wide insertion of an armada of such CSRs—fortunately first generation systems and with no countermeasures, so they were easily detected and destroyed. We may not survive the next such insertion and attack, as the maturity of the CSRs increases.

Considering the usual focus of governments and human control systems, my prediction is that *detrimental, self-replicating, smart* nanobots for use in war, surprise strategic attack, and mass destruction of human targets is already on the early planning boards. The obvious war applications of nanotechnology will advance faster than the peaceful applications, behind a public screen of simpler benevolent developments. This is almost certain, since the lead time for maturing the nanotechnology is from 10 to 20 years. This long lead time rules out most private capital ventures of substantial magnitude. It results in the requirement for government funding, just as development of the atomic bomb was government funded. As a nanotechnology "arms race" begins and heats up, one will see the equivalent of new but hidden "Manhattan Projects" in specialized mass destruction weapons nanotechnology. Rather substantial funding of nanotechnology research and development by several nations is already a fact.

Unethical aspects aside, the potential for useful and benevolent purposes of nanotechnology is very great. The development in this new field is now beginning to escalate almost exponentially, year by year, funded primarily by governments and to a more limited extent by private companies.

Reference: David Cook, Jessica Voorhees, and Brian Valz, "Nanotechnology: The Coming Molecular Revolution," available on website http://nanotech.about.com.

NEGATIVE ABSORPTION OF THE MEDIUM

Excess emission from a medium, as in the Letokhov work and in Bohren's experiment. The excess energy is received from the vacuum interaction.

NEGATIVE RESISTOR

Any component or function or process that freely receives energy from outside the system in unusable or disordered form and outputs that energy in usable, ordered form inside the system, where that is the net function performed.

We specifically do not include "differential" negative resistors such as the tunnel diode, thyristor, and magnetron which dissipate and disorder more energy from the system, overall, than they order and furnish to the system in their negative resistance regime.

NEGENTROPIC

Functioning to produce or involve negentropy.

Reordering previously scattered energy without requiring the operator or experimenter to input energy to do the reordering work (an example is passive retroreflection of scattered EM energy).

NEGENTROPIC ENGINEERING

Expending a little bit of energy to form a dipole or dipolarity, and then intercepting, collecting, and using some of the enormous EM energy freely extracted by the dipole from the vacuum indefinitely, without using any of the extracted EM energy to scatter the charges in the dipole and destroy the dipole, thereby shutting of the vacuum's furnishing of copious free energy.

NEWTONIAN 3RD LAW

For every action there is an equal and opposite reaction.

This law should be extended and restated something like this: "for every action there is an opposite and equal reaction if the causative mechanism of the reaction is allowed to occur and not first redirected away from its target." An example of a violation of Newton's third law as usually stated, is provided by the emission of a phase conjugate replica wave from a phase conjugate mirror material. No matter how powerfully pumped, the PCM does not recoil. The reason is that the antiwave cause of Newtonian third law recoil was intercepted by nonlinear multiwave interaction before it could reach its target nuclei, and rediverted away from the atom and on out of the material. Since the causative mechanism for Newtonian recoil did not occur, the PCM did not recoil.

NEWTONIAN RECOIL

As used in the paper, refers to Newton's third law reaction created as the recoil of the nucleus of an atom which absorbs an incoming EM longitudinal wave, or emits one.

NEWTON'S THIRD LAW

For every action there is an opposite and equal reaction.

In Maxwell's electrodynamics, Newton's third law is missing. It is missing because of the coarseness of the modeling which Maxwell was forced to use. Maxwell's seminal paper was read in 1864 and published in 1865. At the time, neither the electron nor the atom had been discovered, much less the nucleus of the atom. A molecule was just a blob with no structure. Electricity was considered to be a thin material fluid, flowing through the wires much like water through a pipe. In fact, Maxwell actually wrote a material fluid flow theory, since hydrodynamics was developed at the time.

So there was, at the time, no notion of the Drude electron gas in a wire and the positively charged nuclei in the atoms in the wire. So there was no notion of two oppositely charged entities in the conductor, both reacting to any EM field entering from space and interacting with the wire.

Further, Newton's third law had always been used mystically without any known cause. It was experimentally established that the reaction occurred, but scientists were forced to just assume its occurrence.

Consequently, Maxwell wrote equations for the reaction of a unitary electric fluid in the conductors. He knew that the wire recoiled, but wrote no equations containing the cause of Newton's third law reaction.

What really happens in the wire is that both the Drude electrons rearrange their positioning vis a vis the lattice, resulting in an apparent current. The actual movement (drift velocity) of the electrons down the wire is very slow, in a nominal case being a few inches per hour. The electrons, having spin, act as little gyros so to speak, longitudinally restrained by the repulsion of the electrons ahead. So the electrons precess laterally, and spend most of their movement in lateral precession movement. This alone proves that the perturbing force is longitudinal, as indeed does Whittaker's decomposition of the scalar potential into longitudinal EM waves. The gradient of the scalar potential (the E-field) is also such a decomposition. But the electron precession waves—which is what our instruments measure in the wire—are indeed lateral waves, in general consonance with Faraday's notion that the force field lines were physical and like taut strings. Maxwell merely assumed Faraday's notion, to give us the transverse EM wave in space. Consequently, the old electrodynamics envisioned that fluid vibrations (ether vibrations) from space had been intercepted by the wire to shake the electric fluid accordingly. And since that electric fluid obviously shook laterally, that "proved" that the waves in spacetime were lateral "plucked taut string" type waves. Actually it proved no such thing, because they were measuring electron precession waves.

The positive nuclei usually have a m/q ratio several hundred thousand times the m/q ratio of an equal charge of electrons. Hence the massive nuclei also react to the field interaction, and move very slightly in the opposite sense from the electrons. That reaction is ignored in Maxwell's general equations, though when the equations are applied, they require that nuclei movement.

In short, the electrons precess and the nuclei recoil oppositely, and that is the generation of Newton's third law reaction.

When we excite a wire antenna with a wave excitation, we produce both electron precession waves and nuclear recoil waves in the nuclei. These two waves are of equal energy, though the nuclei waves are very highly damped in magnitude because of the high m/q ratio of the nuclei. Nonetheless, each of these "lateral" waves slaps the vacuum potential with *identical energy*. So two equal waves of spacetime curvature occur. I can be seen that the net vacuum wave is actually a longitudinal EM wave, composed of waves of vacuum (spacetime) energy rarefaction and densification. Electrodynamicists, considering the vacuum to be filled with a material ether, used the "effect" wave in matter as the cause wave. Hence they used a transverse EM wave in spacetime, when indeed the spacetime wave is and always was a longitudinal EM wave, just as Tesla insisted.

Maxwell's equations are based primarily on the interaction of field and single charge. Actually, the reaction is always between the field and a dipole. Even when the field interacts with an "isolated charge", there are clustering virtual charges of opposite sign around the "isolated" charge so that the "isolated charge" is actually a set of composite dipoles, where each dipole consists of a virtual charge of opposite sign and a differential piece of the isolated observable charge. So the Newtonian third law reaction is also there with an isolated charge, but occurs in the vacuum itself, resulting in vacuum polarization.

Nonetheless, the "transverse EM wave in vacuum" notion is so embedded in electrodynamics that we seem to be stuck with it. It means, however, that the "field in space" used in electrodynamics must be regarded as only a sort of "convenient transfer function" and not a real transverse oscillation entity. This of course accords with Feynman and Wheeler's pointing out that only the potential for the EM wave exists in space, in case a charge is brought in to interact with its gradients.

And needless to say, since the vacuum is a big potential and only potentials and potential changes can exist in it, then Whittaker's 1903 paper decomposing the scalar potential into longitudinal EM waves is paramount and decisive. EM waves in the vacuum a priori must be longitudinal waves, because they are only the changes to the vacuum potential. And that potential at each and every point, changes and all, decomposes into longitudinal EM waves in 3-space with convergent longitudinal EM waves incoming from the time domain.

NISBET

To be added.

NON-ABELIAN ELECTRODYNAMICS

To be added.

NONLINEAR MATERIAL

A substance whose optical properties vary with the intensity of the light.

Most optical substances are very weakly nonlinear, but a great deal of research has been exerted to find materials with stronger nonlinearities. Also, a material which creates and emits the fundamental and additional harmonic frequencies when illuminated with a single frequency. Many nonlinear materials also weakly produce time-reversed (phase conjugate) fundamentals and/or harmonics when illuminated with a fundamental frequency. Such a nonlinear material that creates time reversed waves (phase conjugate replica waves) is said to function as a *phase conjugate mirror*. The phase conjugate replica reappears in space back along the path in space—even through a highly distorting medium—where the input stimulus (signal wave) has traveled or is traveling.

Thus the phase conjugate replica or time-reversed wave normally backtracks its signal wave stimulus to the distant source of that signal wave, even hundreds or thousands of miles away. This "crawfishing" and "concentrating" characteristic is also known as *retroreflection*. Note that an ordinary EM wave *diverges* as a function of the radius traveled away from its emission source, while a time-reversed or phase conjugate replica wave will *converge* as a function of the radius traveled away from its emission source (the mirror), if its stimulus signal wave was emitted from a distant point source. Ideally, a phase conjugate mirror produces a single time-reversed wave in addition to the input signal wave. By stressing *(pumping)* the mirror with the input of two additional opposing waves (ideally orthogonal to the input or *signal wave*), the phase conjugate replica wave output by the mirror is amplified, and may contain up to all the energy in the pumping waves.

NON SEQUITUR

A conclusion or inference not following from the original argument or premise.

NONEQUILIBRIUM THERMODYNAMICS

Colloquial term referring to the new thermodynamics of self-organizing systems and structures in disequilibrium with their environment.

Since the 1960s, there has emerged in physics (and in thermodynamics!) a surprising new area: the physics of far-from-equilibrium systems and the self-organization and large-scale ordering of such systems. E.g., a single Bénard cell (a particular self-organizing circulation structure in convection-type systems), may involve the coherent behavior of some 10^{21} molecules, in a region of convection where one would classically expect only randomness. These new physics and thermodynamics interactions are surprisingly being found in a very wide variety of systems and phenomena, including living systems and nonliving systems. The phenomena of interest include dissipative systems in disequilibrium with their environment, but with stability of their own systems and forms. Open systems in disequilibrium with their environment can permissibly achieve COP>1.0, and they can exhibit local negentropy. The physics and thermodynamics of such systems is still rapidly developing. For a good overview, see Gregoire Nicolis, "Physics of far-from-equilibrium systems and self-organization," in **The New Physics**, edited by Paul Davies, Cambridge University Press, 1989, p. 316-347. For a full technical presentation, see G. Nicolis and I. Prigogine, **Self-Organization in Nonequilibrium Systems**, Wiley, New York, 1977.

NONLINEAR MATERIAL

In physics, any substance whose response to an external causative or influencing agent is not proportional to the magnitude of the causative agent or influence.

NONLINEAR OPTICAL FUNCTIONING (NLO FUNCTIONING)

Functioning in a manner prescribed by nonlinear optics and quantum optics,

...particularly with respect to time-reversal effects, use of phase conjugate mirrors, phase conjugate reflection, and pumping for amplified phase conjugate reflection.

To quote Knight, "A phase conjugate mixing device has remarkable optical properties: perfect retroreflection, the complete cancellation of optical aberrations and inhomogeneities in wavefronts, and the ability to reverse an optical beam and return it to its source."

NONLINEAR PHASE CONJUGATE OPTICS

See *phase conjugate optics*.

NONLOCALIZATION

Producing or rendering an effect or effect-producing agent at a distance, rather than at the immediate location of the effector.

Extended throughout a large region or system, or to a distant part of a large region or system, rather than being confined to a small region of the large region or system.

NON-RIEMANNIAN (GEOMETRY)

Riemannian geometry is the geometry of Riemannian manifolds;

i.e., manifolds having an infinitesimal squared distance ds that is everywhere positive. A non-Riemannian geometry violates this property. [A manifold is a topological space with certain technical characteristics.]

NUCLEONS

Name for the neutrons or the protons in a nucleus. In the nucleus, the neutrons and protons are continually changing one into the other by exchange of the charge.

O(3) ELECTRODYNAMICS

To be added.

OPEN SYSTEM

A system that communicates with its environment, and exchanges energy, matter, or both between system and environment.

The system may be in equilibrium with that exchange, so that it effectively does not retain and utilize received environmental energy to power loads or accomplish external work. Note that it may in fact receive and store excess energy from the environment, or give up energy to the environment, and then remain in equilibrium under its new potential energy conditions. That is, the system may asymmetrical regauge itself but not utilize any of the regauging energy to accomplish external work. When potential is applied to an electromagnetic system, the system is similarly asymmetrical regauged and its potential energy is increased. However, if the system then destroys its source of regauging potential energy faster than it powers its load, it is said to symmetrically regauge itself when discharging its freely received excitation energy.

The system may be far from equilibrium in its energetic exchange with its environment, and if it asymmetrically discharges its freely received excitation energy, it can exhibit COP>1.0. In that case the system effectively retains and utilizes some of its freely received environmental energy to power loads or accomplish external work, and the operator himself does not have to furnish that part of the energy dissipated as useful work.

OPTICAL SWITCHING

Refers to switching of optical signals, or switching using optical frequency switching techniques, components, and circuits.

ORTHODOX TRANSISTORS

Ordinary transistors in use today.

Such transistors will not perform the Fogal semiconductor special functions.

ORTHOGONAL ROTATION

Simply speaking, a rotation from one direction to a direction at right angles to it.

The Lorentz transform of special relativity, e.g., is a formula for the rotation of an object and all its parts away from its line of motion, as a function of the object's velocity, in a direction toward the time axis. The speed c just represents a full orthogonal turn, so that the intersection of the object with the observer 3-space, along the original line of motion, is zero.

To the observer, the three dimensional object (at speeds less than c) has become a two-dimensional plane moving at speed c. In a space of more than 4 dimensions, the orthorotation may be toward a higher spatial dimension rather than toward the time dimension. As can be seen, such orthorotation is intimately connected with the transformation of an electron or electron/positron pair into a photon, and vice versa. Orthorotations are extremely important when one models the physics of mind and matter interaction, and the physics of a living organisms including both its mind and its physical body—as in psychoenergetics.

OSCILLATING QUANTUM WELL

A quantum well which is oscillating in magnitude and sometimes in sign.

OVERPOTENTIAL

Essentially the overpotential (as in an electrode in a solution) is a shift in the Fermi level necessary to allow the electron in the electrode metal to have energies overlapping with vacant acceptor levels in molecules adjacent to the electrode in the solution.

The overpotential effect appears at small "double surfaces" of things in very close contact, particularly in electrochemistry and in solid state physics. The overpotential enables electron transfer, e.g., by tunneling. The overpotential increases with the log of the reaction rate that occurs at the overpotential location.

For a small reaction rate, the overpotential is small; but for a small increase in the overpotential there occurs a *dramatic* increase of reaction rate. Fogal has utilized the overpotential effect in his semiconductor, to great advantage in accomplishing unusual charge blocking and other special effects.

One of the world experts in the theory and use of the overpotential is Dr. J. O'M. Bockris. E.g., for a short overview pointing out the importance of the overpotential, see Bockris, "Overpotential: a lacuna in scientific knowledge," **Journal of Chemical Education**, 48(6), June 1971, p. 352-358 (a paper which Bockris graciously sent me some years ago). Quoting from that reference, p. 355: "The formal definition of overpotential is 'the change of potential of the electron-conducting phase when reaction rate across its interface with the ion-conducting phase with which it is in contact is changed from zero to a certain velocity.'" And again, p. 355: "...overpotential... in fact determines what fraction of the energy of the self-functioning cell has to be wasted in making the cell work and deliver energy at a certain power." For a more detailed and wider exposition of the overpotential, its effects, and its uses, see J. O'M. Bockris and A. K. N. Reddy, **Modern Electrochemistry**, Vol. 1 & 2, Plenum Press, 1970.

OVERUNITY COEFFICIENT OF PERFORMANCE

More energy out or work out of a system than the operator or experimenter must himself or herself furnish and input.

An open thermodynamic system far from thermodynamic system is permitted to achieve such an overunity performance, so any overunity electrodynamic system must be such. Well-known nonelectromagnetic examples are solar cells, heat pumps, windmills, sails on sailboats, waterwheels for powering watermills, a gliding bird in thermal updrafts, etc. A well-known electromagnetic example is the common solar cell. The common household heat pump has a theoretical COP limit of 8.22, and well-designed units usually achieve some 4.0 or so, so long as the ambient environment does not change too drastically from the design limits. As the environment changes and cools down appreciably, however, most home heat pumps lose efficiency and have to switch onto heating strips, which have a $COP \approx 1.0$.

Contrary to prevailing belief, it is certainly possible to have EM systems which are also open thermodynamic systems, far from equilibrium, and freely receiving excess energy (asymmetrically regauging a potential) from an external source, to wit, their violent virtual flux exchange between the vacuum and the system. All EM system are already *open systems* in the virtual particle flux exchange with vacuum; that is already well-known in particle physics, even though the 130-year-old classical electrodynamics does not even include the vacuum-mass exchange. The only question, then, is how to establish an asymmetry in that vacuum-mass flux exchange. Here again, every electrical charge and every dipole is already just such a broken symmetry in the vacuum flux, as has been known in particle physics for four decades! It takes on the average about 50 years, however, for vital discoveries in one discipline to "cross fertilize" into another discipline. At any rate, the symmetry of every electric power system, in the vacuum flux, is already broken in its source dipole. This rigorously means that, if we simply avoid doing something we are doing in our power systems to restore symmetry as a matter of course, it is possible to utilize the free broken symmetry of the source dipole to provide an overunity EM system.

In 1996 I showed that such overunity EM systems are permitted and prescribed by Maxwell's theory, prior to the arbitrary imposition of *symmetrical* regauging of the Maxwell equations (i.e., the Lorentz condition). Violation of the Lorentz condition (by asymmetrical self-regauging) is a necessary but not sufficient condition for an overunity EM device. An asymmetric regauging will certainly give us excess free energy in the system, and an excess force to use that energy in translating against a load impedance to do work, if we design the system properly to do just that.

To achieve overunity, in a circuit one must prevent the (presently universal) re-imposition of the Lorentz condition by the use of one-half the excess received energy to drive the return electrons from the load back through the back emf of the source, killing the gate and restoring symmetry, the Lorentz condition, and equilibrium between vacuum flux and system. All our present EM systems are specifically designed to drive those electrons back through the back emf and thus restore symmetry, *deliberately* asymmetrically self-regauging a second time and *deliberately* restoring the Lorentz condition, along with *deliberately* killing the source dipole's asymmetry in the vacuum flux exchange.

PARADOX (LOGICAL)

A thing that is true, e.g., as shown by experiment, but which violates one or more of the three Aristotelian laws of logic.

Any logic algebra or system has a topology. A paradox in one topology can often be resolved by increasing the topology of the logic. All logical paradoxes in the 3-law Aristotelian logic system are simply fourth-law logic cases in a logical superset, and—at least hypothetically—the fourth law can be applied to resolve them. For a discussion and proof of the 4th law correction to Aristotelian logic, see Appendix III: "A Conditional Criterion for Identity, Leading to a Fourth Law of Logic," in T.E. Bearden, **AIDS: Biological Warfare**, Tesla Book Co., Chula Vista, California, 1988, p. 428-443. Logic has many aspects that often may shock our casual expectations: For example, one of the most advanced axioms in mathematics is called the Axiom of Choice. It is used in the proof of many advanced theorems. Using the Axiom of Choice, it can be shown that it is possible to cut a ball into a finite number of pieces, then reassemble the pieces into two balls of the same size, with no air gaps between pieces! While this seemingly defies all common physical sense (and I've not found anyone who has done it!), it is mathematically correct. For a proof, see Thomas J. Jech, **The Axiom of Choice**, American Elsevier, New York, 1973, p. 3-6. For a good perspective on Aristotelian logic, see Morris Kline, **Mathematics: The Loss of Certainty**, Oxford University Press, New York, 1980.

PARITY

Deals with studying a system of sequence of events as if reflected in a mirror. A system has parity is it undergoes no fundamental operational change if replaced with its mirror-reflected twin.

PARTIALLY TIME-REVERSED REGION

A region of space in which an object experiences not only the ordinary forward flow of time, but an extra induced backwards flow of time, usually a fraction of the time-forward time stream.

One result may be to "reduce" time-forward force fields, by a fraction. This is important in bridges, where one must pass EM energy flow onto a follow-on load circuit, but the return current in that circuit must be allowed to circulate back through the load bridge itself, against the inducing back emf. By partially time-reversing the region occupied by the back emf, that back emf is seen as a smaller value by the return current being passed back up through the back emf. The result is that current will circulate in the load loop, powered entirely by the bridging of Poynting flow $\mathbf{S} = \mathbf{E}\times\mathbf{H}$ onto the load circuit.

Another result of a partially time-reversed region is that the law of attraction and repulsion of charges is partially reversed. If the time-reversal predominates in the region, as in a momentary time-reversal zone in some electrolytes, then the law of attraction and repulsion of charges is reversed. In that case like charges attract and unlike charges repel. Two positive $H+$ ions, e.g., may be drawn so tightly together that each enters the edge of the strong force region of the other, forming a quasi-nucleus. Note that in each $H+$ ion the gluon forces are almost dissolved and the quarks are nearly freed. Then as the time-reversal zone decays back to a normal time-forward zone, the decay changes begin from inside out, resulting in the flip of a quark to change one of the $H+$ ions to a neutron n. The n and the $H+$ ion draw together as the preferred decay state, resulting in the formation of deuterium or a $D+$ ion. This and similar "time reversal zone" reactions have been proposed by this researcher as the mechanisms generating the anomalous deuterium, tritium, and alpha particles (helium nuclei) in the "cold fusion" reactions. It is indeed a special type of low spatial energy fusion, but a very high energy reaction since time-energy is involved as the active ingredient, and time-energy has the same energy density as mass.

PARTICLE PHYSICS

The branch of physics using accelerators to study high-energy particle collisions, to determine properties of atomic nuclei and of the elementary particles themselves.

So far as I am aware, conventional particle physicists do not consider time-energy interaction and time-reversal zone novel nuclear interactions at all.

PATTERSON EFFECT

The intense multiscattering, multipass, multicollection of Poynting energy density flow in an assemblage of palladium-clad spherical bead capacitors, as the palladium adsorbs hydrogen ions from the fluid in which the beads are immersed, and charges up as a capacitor, thereby becoming an energy-flow generator, and nonlinearly increasing the energy-flow as the charge of the capacitors increases.

The Patterson effect yields the Patterson Power Cell® , a validated overunity power system which has shown COP>1200 in independent university testing. The Patterson effect is a variation and adaptation of the well-known anti-Stokes emission effect, which for three decades has been validated in physics journals to produce overunity emission in certain intensely scattering active media.

PATTERSON POWER CELL®

Patented overunity power unit by James Patterson, which has been independently validated to yield COP>1.0.

See James Patterson, "System for Electrolysis of Liquid Electrolyte," U.S. Patent No. 5,372,688, issued Dec. 13, 1994. Filed Dec. 2, 1993. 26 claims, 7 drawing sheets.

PAUTRIZEL, RAYMOND

Eminent French parasitologist who worked with Antoine Priore, and who performed many definitive experiments demonstrating the Priore healing effect.

PEGRAM'S EXPERIMENT

Experiment which demonstrates a relation between electric and magnetic fields in the vacuum which the Maxwell-Heaviside theory does not prescribe.

Simultaneously, a coaxial cylindrical condensor and solenoid are rotated. The rotation produces a magnetic field in the solenoid in the axial direction and between the plates of the condensor. The condensor can be charged by shortening the plates of the condensor. This indicates a cross relation in the vacuum between electric and magnetic fields which does not exist in the Maxwell-Heaviside theory.

Reference: G. B. Pegram, **Physical Review**, Vol. 10, 1917, p. 591.

PERPETUAL MOTION MACHINE

Assertion that no machine can indefinitely operate, since no closed system can input its output power back to itself while powering a load because powering itself and its load violates the equilibrium thermodynamics (i.e., the thermodynamics of a closed system).

The "defenders of the underunity faith" use the statement that "there cannot be any such thing as a perpetual motion machine" as an article of faith and iron dogma. Usually they classify a so-called "perpetuum mobile" as to which law of *equilibrium thermodynamics* it is thought to violate.

For permissible Maxwellian overunity systems, the entire "perpetual motion" conundrum is nonsensical, since we are always speaking of an EM system *far from thermodynamic equilibrium* with its active vacuum environment. The *equilibrium* thermodynamics assumed by the critics does not even apply to such systems, as witness the Nobel Prize awarded to Prigogine in 1977 and the voluminous literature on such open dissipative systems.

As an example, see Stanley W. Angrist, "Perpetual Motion Machines," **Scientific American**, vol. 218, Jan. 1968, p. 114-122. Angrist gives a typical critique using classical equilibrium thermodynamics. He calls *permissible* overunity systems (open dissipative systems receiving excess energy from an external source) *false perpetual motion machines* or *fictitious perpetual motion machines*. Also see Angrist's article, "Perpetual Motion," **Encyclopaedias Britannica, Bicentennial Edition, Macropaedia** Vol. 14, 1976, p. 102-105. Here he gives a very good summary of the subject as ordinarily posed, with precise definitions included for perpetual motion machines of the first, second, and third kinds and for fictitious perpetual motion machines. Unfortunately his entire argument is completely irrelevant to any study of permissible overunity machines, which he already has labeled as "fictitious perpetual motion machines" and has already admitted that they exist! The substance of his entire argument is that systems in equilibrium cannot power themselves. That is of course quite true, but is a mere tautology and has no relation to an open system in disequilibrium, which *can* power itself and its load simultaneously, by the laws of physics and the laws of *disequilibrium* thermodynamics. So in fact Angrist, as do the skeptics who continue to assail legitimate overunity EM system researchers as perpetual motion nuts, establishes his own dummy strawman and demolishes it, while ignoring—so to speak—the huge Statue of Liberty before him.

Now this is not to pick on Angrist! He appears to be a reasonable scientist, carefully stating his thesis in a straightforward manner. His voice is quoted as a *reasonable* critical voice, and not like the usual *extremist* critic who engages in ad hominem attacks from the outset. It merely shows that (1) the entire "perpetuum mobile" prohibition does not even apply to overunity EM systems far from thermodynamic equilibrium with the active vacuum, (2) the critics are either unwittingly or deliberately using the wrong type of thermodynamics as the basis of their entire argument, (3) the *reasonable* perpetual motion critics—wittingly or unwittingly—simply set up an irrelevant strawman and precede to knock it down, and (4) in fact the critics already admit to a machine that will in fact run itself and power its load indefinitely or perpetually unless something changes or breaks or fails, but then oddly label it as a "fictitious" or "false" perpetual motion machine! Meanwhile, in the universe around us we universally observe things in violent and perpetual motion, having continued so for some 15 billion years. None of the atoms seem to be running down, nor do any of the molecules. And they are open systems brought out of equilibrium by absorption of energy, and decaying back into equilibrium (or approaching it) by emission of excess energy.

The eerie point is that technical publications such as **Scientific American** and **Encyclopaedia Britannica** do not seem to question the line of reasoning advanced by those knocking perpetual motion, or even fully analyzed their argument. What we really deal with in terms of skeptics in this area is either (1) a reasonable, scientific skeptic such as Angrist (his listing of machines and attempts for machines not in disequilibrium with their active environment to run themselves is very good), or (2) an unreasonable person spouting dogma and venom, who should simply go read some disequilibrium system thermodynamics and learn etiquette.

Also, we strongly object to supercilious phrases invariably employed by harsh skeptics who insist we are looking for "something for nothing" or "a free lunch". No legitimate overunity energy researcher has ever considered such a thing. We freely admit that the excess energy is received from the active vacuum exchange, via a broken symmetry in that exchange. Should the farmer refuse to use a windmill or waterwheel because he's getting a "free lunch" for energy input? For those who so quickly hurl such condemnatory phrases, let me hold up a mirror and show them an analog of their position: The famed surgeon Alfred Velpeau wrote in 1839: *"The abolishment of pain in surgery is the chimera. It is absurd to go on seeking it today. 'Knife' and 'pain' are two words in surgery that must forever be associated in the consciousness of the patient. To this compulsory combination we shall have to adjust ourselves."* [Martin Gumpert, **Trail-Blazers of Science**, Funk and Wagnalls, New York, 1936, p. 232.]

The strident, dogmatic critics of open overunity disequilibrium EM systems are stating an exact analogy to Velpeau's statement. The *scientific* worth of their criticism is precisely the scientific worth that eventually was shown for Velpeau's pronouncement.

PHASE CONJUGATE

Of an entity: its time reversal. For waves, often referred to as *wavefront reversal*.

PHASE CONJUGATE MIRROR

A nonlinear material which, when provided with an input wave, emits a phase conjugate replica (time reversed replica) of that input wave.

The input wave is by practice called the *signal wave*. The time-reversed wave output is by practice called the *phase conjugate replica*.

PHASE CONJUGATE OPTICS

That portion of nonlinear optics dealing with multiwave mixing, formation of time-reversed waves, phase conjugate reflection (PCR), phase conjugate mirrors (PCMs), pumping PCMs to amplify their emitted PCRs, nonlinear interferometry, distortion correction, self-targeting, laser tracking, adaptive optics, and so on.

PHASE CONJUGATE REPLICA (PCR)

Of a wave: the time-reversed duplicate of the wave.

PHASE-CONJUGATING ACTION

In nonlinear optics, the process or action of producing a time reversed replica of an input wave.

For a particle, producing its antiparticle. For a cell, dedifferentiating it back to some previous form, genetics and all.

PHASE CONJUGATION

In nonlinear optics, the novel nonlinear mixing of waves which generate an output wave—called the phase conjugate replica or time-reversed replica—that precisely retraces the path previously taken by the input wave that stimulates the action.

The process or action of producing a time-reversed wave. Phase conjugation can compensate for aberrations and distortions in the input. Real time holography can also be produced by applying the phase conjugation process.

PHASE-LOCKED HARMONIC SERIES

In Whittaker decomposition of the scalar potential: The decomposition produces a set of bidirectional wavepairs, as explained previously.

Each of these wavepairs has a given frequency, starting from a fundamental. In other words, the other wavepairs are harmonics of the fundamental wavepair. Further, these are regularly arranged in a lattice, so that "timing" or "phasing" is rigidly locked in place.

PHENOMENOLOGY

In physics, the philosophical and experimental study of physical phenomena,

... as distinguished from ontology, (which is the study of being).

PHOTON

In physics, the basic action quantum.

Considered to be the basic quantum of the EM field. Well, there's a little problem with that. The photon contains energy and time, and so must also occupy a time interval. The notion of forcefield rigorously contains mass as a component; yet mass is missing from the concept of field as it is applied. The EM field is conceived as a spatial entity only. It may spatially vary as a function of time, of course, but it itself does not occupy time, at least conceptually. These considerations raise some startling difficulties in the ready conclusion that the photon is the fundamental quantum of EM field. If a "piece of the photon" is missing from the field, how can the field be made of photons? How can one get area out of a straight line? I simply pose this problem for the theorists and the foundations physicists, pointing out that it has universally been fashionable for physicists to ignore that *the photon carries not only a little increment of energy, but also a little increment of time*. My own work has been to look at the dimensional difference between masstime and mass; i.e., between a mass that has just absorbed a photon, and thus must consist of masstime (4-space), and just after that masstime then re-emits the photon, reverting back to mass (3-space). From this one can build, e.g., a mechanism that generates the actual flow of time itself. It is in theory an engineerable mechanism.

PHYSICAL REALITY

To be added.

PING-PONG

To be added.

PINNA

The outer ear(s). Of particular interest to us are the tiny little folds in the ear.

PINNA INFORMATION

Refers to hidden information content of the field, or in the received signal.

Comes from the little folds in the pinna (outer ear). For sound direction and distance sensing, the tiny pinna folds of the outer ear use phase reflection information more than 40 dB below the primary sound signal that strikes the eardrum. In EM signals, we are referring to "hidden" or infolded information deep within a signal from a distant target. In fact everything in the target contributes to the signal emission from it, and all that information is riding "within" the signal, in its deep "pinna" information. The Fogal chip can outfold some of this pinna information, so that information can be recovered from a signal which no other process heretofore could recover. For a dramatic future use, as the Fogal semiconductors and equipment using them are developed, there will emerge detecting units that can see highly detailed structure in the human body, merely from processing the light reflected from the exterior of the body. The details eventually will rival and even surpass that of magnetic resonance imaging, and will be essentially noninvasive.

It is also true that hidden "vacuum engines" can be transmitted back into the body, so that "problems" or disorders can be directly corrected. As an introduction to this type of area, where cellular disease "antiengines" can be created in the body to directly reverse cells and their genetics, curing the disease, see T.E. Bearden, "Vacuum Engines and Priore's Methodology: The True Science of Energy-Medicine, Parts I and II." **Explore**!, 6(1), 1995, p. 66-76; 6(2), 1995, p. 50-62. A major book on this subject will soon be published. For a presentation for the nonspecialist, see T. E. Bearden, "Hidden Mechanism for Reversal of Diseased Cells to a Previous Healthy State," **Resonance**, Newsletter of the Bioelectromagnetics Special Interest Group, Mensa, No. 29, Nov. 1995, p. 11-15.

PINNA INFORMATION CONTENT

In electromagnetics, the hidden inner Stoney-Whittaker-Ziolkowski infolded EM information inside the scalar potential.

Since an EM wave can be represented as two scalar potentials, then by infolding pinna information inside one or both of the two potentials, it is infolded inside the carrier wave. Thus hidden information can be and is carried by all EM radiation and all EM signals. The Fogal semiconductor for the first time enables the outfolding and processing of some of this information.

PINNA INFORMATION DETECTORS

Detectors based on use of the Fogal semiconductor, which can outfold, process, and display some of the hidden information inside the scalar potential and inside signal emissions from distant objects.

PINNED ELECTRONS

Electrons held stationary by a magnetic field, or other set of forces that react to "push them back into their positions" whenever they try to move away.

PINNING

The act of restricting (by restoring forces and fields) movement (particularly of electrons) due to a disturbing magnetic field or other external force.

POLYHEDRON

A solid figure, especially with more than six plane surfaces.

POSITRON

An antielectron (time-reversed electron), possessing a positive charge. In Dirac's relativistic theory of the electron, a positron may be regarded as an empty negative energy state in the Dirac sea whose usual occupying electron has been removed.

POWER

The time rate at which work is done (at which the form of energy is changed).

In electrical engineering, the term "power" is erroneously also used to mean "energy".

PRIGOGINE, ILYA

Noted Belgian chemist and Nobelist, and one of the pioneers of the thermodynamics of open systems far from thermodynamic equilibrium.

Prigogine was awarded the 1977 Nobel Prize for his work on the theory of dissipative structures in nonequilibrium thermodynamics.

PRIORÉ, ANTOINE

Italian radar technician, remaining in France after WW II, who discovered the use of novel waves from plasmas emitted when normal EM waves were introduced, and who used this effect to accomplish remarking healing in laboratory animals of terminal tumors, infectious diseases such as trypanosomas, restore suppressed immune systems, and heal atherosclerosis.

Prioré's beam was actually longitudinal EM waves. The body when irradiated by longitudinal EM waves adds a weaker phase conjugate replica, thus converting LW nonlinear optical pumping from the 3-space domain to the time domain. This time-reverses the irradiated cells and all their components back to a previous physical state and condition.

Such "time-domain" pumping is used by the living body's cellular regeneration system to restore cellular damage and heal the cells, within its limits. Thus Prioré unwittingly uncovered a way to dramatically amplify the body's own healing and regenerative powers.

POYNTING, JOHN HENRY

An English physicist who lived from 1852-1914, whose contributions to electromagnetics included the energy flow theory now known as Poynting flow.

He contributed the Poynting theorem, which states that the rate of EM energy loss in a specific region of space is equal to the sum of the dissipation rate (heat loss) flowing across the boundary of the region. Concurrently with Oliver Heaviside, Poynting conceived the notion that energy flowed through space, which previously had not appeared in physics. Heaviside actually published first, but obscurely; Poynting published in a prestigious journal, so the theory came to be known as "Poynting theory." Poynting himself always gave credit to Heaviside for being first. Also, the Heaviside version $\mathbf{S} = \mathbf{E}\times\mathbf{H} + \mathbf{G}$ was more extensive than Poynting's $\mathbf{S} = \mathbf{E}\times\mathbf{H}$. Heaviside was a recluse; years after his death, in his little garret apartment some papers were discovered beneath the floorboard. Therein Heaviside has used his **G** term (a closed energy flow, or "trapped energy" term) to represent gravitation, and had worked out a testable theory of electrogravitation. Modern general relativity indeed considers that it is energy—particularly trapped energy—that is responsible for generating gravitational field and gravitational potential. Apparently nothing at all was done or has been done with Heaviside's electrogravitational theory. See H. J. Josephs, "The Heaviside papers found at Paignton in 1957," **The Institution of Electrical Engineers Monograph No. 319**, Jan. 1959, p. 70-6.

POYNTING ENERGY

Loose term (not rigorous!) used to describe the flow through space of Poynting energy density $\mathbf{S} = \mathbf{E}\times\mathbf{H}$. It actually describes not the energy flow density per se, but that component of it that would be intercepted by a unit point charge.

POYNTING ENERGY DENSITY FLOW

A more rigorous term used to describe the flow through space of the Poynting energy density flow component **S** = **E**×**H**. that would be intercepted by a unit point charge.

POYNTING ENERGY FLOW

Loose term (not completely rigorous) used to describe the flow of energy density **S** = **E**×**H**.

Rigorously, note that both **E** and **H** are "defined" only after their reaction with a unit point static charge. Hence **S** is the resulting component of the overall energy flow that interacts with the charges (with the circuit) and is diverged into the circuit to power it. It is *not* the entire energy flow, which also includes a vast Heaviside nondiverged component that does not strike the charge and interact with it, and hence does not interact with the circuit but is just wasted.

POYNTING GENERATOR

Any dipole or potential difference, which represents a broken symmetry in the vacuum's virtual particle flux, and hence extracts virtual energy from that asymmetry, and gates it out as a gushing energy flow in 3-space. The component of that energy flow that would be intercepted and diverged by a unit point charge is the Poynting energy flow **S** = **E**×**H**.

POYNTING VECTOR

The vector **S**, given as **S** = **E**×**H**, which is used to represent the Poynting (intercepted and collected by a unit point coulomb) energy density flow component.

In Heaviside's version, **S** = **E**×**H** + **G**, where **G** is an energy circulation flow term of trapped energy flow.

PPCM

Pumped phase conjugate mirror.

A phase conjugate mirror material which has introduced to it appositive or "pump" waves. In the phase conjugating process, up to all the energy in the pump waves can be output as the energy in the emitted phase conjugate replica wave. Thus the PPCM is an amplifier, very similar to a triode.

PRIMARY IMAGE

The image or portion of an overall image that is of most interest, and usually the sharpest in focus.

PROBABILISTICALLY

Of or determined by the laws of probability.

Note particularly the somewhat dichotomous use of "determined by—probability." The entire notion in probability is that the overall result is not individually determined, but that there are multiple outcomes of the experiment, each of which occurs with a certain frequency out of a very large number of trials. If a single result always occurs, that is said to be a deterministic change, not a probabilistic change. Unfortunately if one pursues the definition of "probability" in mathematics and logic, one eventually finds that it is dichotomous, as was our definition of energy. Ultimately the foundations guys just threw up their hands and said, "Oh, what the heck! Probability is probability, every fool knows that!" The problem cannot be resolved in 3-la w Aristotelian logic; it requires a higher topology logic.

PROBABILITY

The probability of a simple event is the ratio of the number of times it occurs to the total number of trials (for a large, essentially infinite number of trials).

Note that "trials" constitute things that have occurred (are past). Probability has resisted rigorous logical definition by Aristotelian logic; the reason is that it is an expression of the fourth law, the identity of opposites. Probability is the expression of the future (that which has not occurred) in terms of the past (that which has occurred). Since we have been trained to conceive or think of something as if it had just been perceived to occur, then this is the only way we can *conceive* the future—as if it were an "already occurred past" to us.

But with Aristotelian logic, the future cannot be composed of a set of pasts (the law of the excluded middle prevents it!), and probability has no acceptable logical basis. With four-law logic, the future can be modeled in terms of—and even be identical to —the past, and probability has a logical basis.

Consider *throwing a die to land with one face up*. Thinking of the event (as if it has just occurred, in terms of the most recent past), one can conceive six ways of looking at it. In other words, one can conceive of six "most recent pasts." By the fourth law, the total "most recent past" is identical to the "most immediate future," on the common boundary. If one therefore *collects* all six "most recent pasts," they turn into the most immediate future, by the fourth law of logic. One may argue that only a single one of the events will actually occur. Here one counters with the observation that, when it occurs, it is the past, not the future, and then it has not been collected so as to move to the boundary. One also points out that, with the hidden variable approach, in theory it is possible to directly engineer those probabilities while the Schrödinger wavefunction is still propagating and has not yet collapse to constitute an "observation." I.e., it is possible to engineer Wheeler's "pre-reality," and determine in advance just which of the outcomes shall occur.

Now, if this type of equipment eventually gets built and is small and portable, just think what one could do in Las Vegas!

PRODUCT SET OF INTERNAL WAVES

Modulations of the internal bidirectional wavepairs comprising a scalar potential.

This set was added in the mid-1980s by Ziolkowski, to Whittaker's 1903 sum set. When a signal is "infolded" inside the DC potential, it is modulated upon (multiples) one or more of the internal biwave pairs. Ziolkowski's work is necessary to deal with that; Stoney and Whittaker alone do not handle it.

PSYCHOENERGETICS

Russian branch of energetics where extended electrodynamics is targeted upon the mind and its functions, hence in the time-domain and employing time-polarized EM waves.

PSYCHOTRONICS

Czechoslovakian name for extended electrodynamics effects on the living body.

PUMPED PHASE CONJUGATE MIRROR (PPCM)

A nonlinear material which:

(i) when provided with an input wave, emits an amplified phase conjugate replica (time reversed replica) of that wave, and

(ii) has additional opposing waves as inputs, so that their energy is transformed into the amplified energy of the time-reversed replica wave.

The word "mirror" is misleading, in that the "mirror" may be just a highly nonlinear material, or be an actual smooth metallic surface containing "hot spots" by heating, etc. In any case, it is the nonlinearities such as the hot spots that produce the phase conjugating action.

PUTHOFF, HAROLD

Noted physicist active in a variety of fields and investigations including in psychoenergetics, extended electrodynamics, energy from the vacuum, parapsychology, remote viewing, psychokinesis, zero-point energy of the vacuum, and cosmology.

We have specifically mentioned his important cosmological feedback principle.

QM VACUUM

The quantum mechanical vacuum, which models the vacuum as an intense flux of virtual particles, each appearing an disappearing in such extreme time intervals as to be unobservable individually.

Violent fluctuations of extremely short duration constantly occur in the QM vacuum flux. Various calculations estimate the energy density (in mass units) as up to 10^{80}-10^{90} grams per cubic centimeter, or even greater.

QUALITATIVELY

Determination based on qualitative analysis, usually as contrasted to quantitative determinations.

QUANTIZED

i) Reduction of some observable quantity to multiples of some small, indivisible unit, or,

ii) expressed in terms of quantum theory.

QUANTUM

A single "particle" of the quantity action.

The quantum is always composed of two fundamental quantities (canonical variables), and it is the "fissioning" of the action quantum into two pieces which results in detection of one of the pieces. An indefinite "smear" of part of the two pieces may be simultaneously detected by a linear detector, but never both exactly (Heisenberg uncertainty principle). More recent work has shown that, in a highly nonlinear situation, both canonical variables can be determined simultaneously to any desired degree of accuracy, in which case the Heisenberg uncertainty principle does not hold in its conventional form. This fundamental change in what has been regarded as one of the "sacred laws" of physics has not yet made it into most physics texts.

QUANTUM ELECTRODYNAMICS

The theory of photons and electrically charged particles and their interactions.

The use of the term "quantum" implies that the EM radiation's discrete photon nature is significant, so that quantum theory must be employed.

QUANTUM FIELD THEORY

A quantum mechanical theory in which "... a physical field is considered as a collection of particles and forces, and observable properties of an interacting system are expressed as finite quantities rather than state vectors."

[**Dictionary of Science and Technology**, ibid.] More simply (after Davies, **The New Physics**, 1989): "The theory that describes the quantum effects of a classical system of fields defined on space-time and satisfying various partial differential equations."

QUANTUM POTENTIAL

A special potential added to the Schrödinger equation, by Bohm in his hidden variable theory of quantum mechanics.

The quantum potential can move instantaneously. In my book **Gravitobiology**, I published a mechanism by means of which a quantum potential can be created. (There may of course be *other* QP-creating mechanisms). An iterative, mutually phase conjugating of EM signals passed back and forth between two objects, or among many of them, is called *self-targeting*. Extreme self-targeting can produce such a QP or partially produce one, particularly if a dense "pumping" (optical sense) of the phase conjugate mirror objects occurs. I am presently proposing the QP as a means of direct energy amplification. I.e., if there is "instantaneous travel" between two light-observed points, then to the instantaneous agent there is no length separation or time separation between the points. This of course means that in effect the objects now coexist "superposed" on each other in a multiply connected space, at least with some fraction of "coupling".

Suppose the coupling fraction is 0.5, and 100 widely separate d nodes are so connected by a common QP. Then if one puts in 1 joule per second of energy flow at a given node, there will instantly and simultaneously appear at each of the other 99 nodes one-half joule of energy per second flow. So I can gain quite a bit o f *direct energy amplification* in this distributed system, and nothing can "shield" the distant nodes. Presently, other than possibly Gabriel Kron's "open path", I have not found any other consideration of "direct amplification of energy at a distance".

The implications of the quantum potential—in everything from power sources to medicine to weaponry—are staggering. Weapons based on just this very QP, multiply connected space, and direct energy amplification appear to have already been developed and are on site in three nations. A fourth either is just getting them or is nearing their deployment.

QUATERNION

Expression comprised of the sum of four terms, one of which is real and three of which contain imaginary units, and that can be written as the sum of a scalar and a three-dimensional vector.

QUATERNION ALGEBRA

The algebra of quaternions and their mathematical operations.

Quaternion algebra is of higher topology than either vector algebra or tensor algebra. Maxwell's original equations are some 20 equations in 20 unknowns, in quaternion algebra. Heaviside and others reduced the algebra to vector algebra and some four equations. The present vector equations taught in university as "Maxwell's equations" are in fact Heaviside's truncation of the Maxwell theory. Going to tensor algebra electrodynamics cannot recover the full range of Maxwell's quaternion theory.

As an example, what Tesla actually did in his patented circuits cannot even be seen in vector or tensor analysis. On the other hand, analysis of his circuits by quaternion electrodynamics clearly reveals his startling ability to shuttle the energy in the circuit at will. See T. W. Barrett, "Tesla's Nonlinear Oscillator-Shuttle-Circuit (OSC) Theory," **Annales de la Fondation Louis de Broglie**, 16(1), 1991, p. 23-41.

QUINTESSENCE

Literally, the "fifth essence". In short, dark energy.

RADIONICS

To be added.

REACTIVE POWER

Electrical power, measured in volts-amps-reactive (vars) that cannot do work as is.

For sinusoidal waveforms, the formula for reactive power is given by I·V·sinθ, where θ is the phase angle between the voltage and the current.

REAL, HIDDEN DYNAMICS

The dynamics of vacuum engines, or of "internal energy" or "internal work" ongoing in a system or volume of space.

REAL HIDDEN VECTORS

The "hidden" or "infolded" real vector components,

e.g., of a vector zero summation system.

A group of nonzero, finite vectors which as a system sum to a net translation zero; i.e., which do not translate a resisting mass or charge, but do "stress" it. Such a system therefore constitutes a stress potential.

REAL POWER (ACTIVE POWER)

Power, measured in watts, that can do work, including generating heat.

For sinusoidal waves, real power is given by the formula I·V·cos θ, where θ is the phase angle between the voltage and the current.

REAL VECTORS

Vectors in three space, without imaginary components.

REGAUGE, REGAUGING

Changing the scalar potential or the vector potential, or both.

If one or both of the potentials is/are changed so that a net force is created in the system, that is an asymmetrical regauging.

If only one potential is changed, a net force results and that is an asymmetrical regauging.

If both potentials are changed but carefully selected so that the free force resulting from one change is equal and opposite to the free force resulting from the other, that is a net symmetrical regauging, often called a "Lorentz regauging".

RECTANGULAR TRANSFORMATION MATRIX

Standard mathematical physics.

REFLECTION

The rebound of light or other energy from a surface.

A smooth surface (e.g., a mirror) may produce a specular reflection. A rough surface (e.g., a sheet of paper) produces a diffuse reflection. Actually, in reflection of light, the same light does not rebound; instead, the light incident upon the mirror or surface is absorbed, and new light is re-emitted by that surface. Further, considering reflection from a dielectric, every interior part of the dielectric participates in the reflection. All the internal information about the entire object—everything!—is there in that reflected light, infolded as the hidden "information content of the field" (Stoney-Whittaker-Ziolkowski structuring inside the two scalar potentials comprising the reflected wave). With the Fogal semiconductor, at least some of that hidden "pinna" information in a sample detection of the reflected light can be outfolded and displayed.

REFRACTION

The bending of light as it passes from one medium to another.

It is the phenomenon that enables a lens to focus light and that makes a stick appear to bend where it dips into water.

REPULSION BEAM

A beam of energy directed at a target, which when absorbed by the target will generate a force in and on that target to push it away from the beam projector.

REPULSION-FORCE-GENERATING BEAMS

Beams of energy which "push away" their targeted receivers, by inducing a force in the receiver directed away from the source of the beam.

RETARDED WAVE

The electromagnetic wave that is derived from the retarded fields, which in turn are derived from the retarded potentials.

This means that the retarded wave at a point or region of space has arrived there or exists there as the result of the dynamics of charges and currents that existed at earlier times.

RETROREFLECTING

Precisely reversing the path of.

An example is a phase conjugate reflection.

SACHS, MENDEL

Noted scientist who has completed the work of Einstein and developed a unified field theory covering the universe from the tiniest part to the entire conglomerate.

SACHS' UNIFIED FIELD THEORY

An extension and completion of Einstein's work that includes the universe and its dynamics from the tiniest part to the entire conglomerate, and includes quantum mechanics, electromagnetics, gravitation, and the strong and weak forces.

SCALAR

Characterized by magnitude only.

SCALAR (QUANTITY)

In ordinary vector analysis, a quantity completely characterized by magnitude only.

Actually, it contains magnitude and time, because to exist it must steadily exist in time. So we take the smallest increment of observer time we wish to consider, and that is the minimum "length" of the time-tail that the scalar must occupy and have, in order to even be a "perceived or detected" thing. Before the mathematician jumps in with a nice limiting process to take away the time-tail, if you let that little time interval get too close to zero, then you get too close to eliminating the observer himself, and the entire problem vanishes including mathematics and physics and the observer as well.

One simply cannot demonstrate something that does not exist in time—on paper, in one's mind, or otherwise! Be careful of the term "spacelike " in physics! It hides a logical nightmare. This was the very problem I uncovered in Aristotelian logic; the little increments of time to have a "perceived A" or a "perceived not-A" or to apply an "identity decision criteria" to determine identity or nonidentity, had been left out for lo these 2,000 or so years.

SCALAR ELECTROMAGNETICS

That electrodynamics that arises from considering transverse EM waves, longitudinal EM waves, time-polarized EM waves, electrogravitation, superluminal EM signals, interferometry, nonlinear optical functions, time-as-energy, and the infolded electrodynamics inside all usual EM fields, waves, and potentials.

SCALAR POTENTIAL

Usually considered synonymous with the electric potential.

Here we have another "logical nightmare."

Anyway, the conventional "definition" of electric potential assumes one knows what a "potential" is already, and goes something like this: "The potential measured by the energy of a unit positive charge at a point, expressed relative to an equipotential surface, generally the surface of the earth, that has zero potential." [**Dictionary of Science and Technology**, ibid., p. 722.]. Well, that is botched. It tells or attempts to tell what the *measurement* of a potential is, using a unit positive charge and a process. A potential cannot be its own magnitude measurement, just as a man cannot be his own weight measurement.

So what do we do? We have to tell what the potential *is*. This is the problem that so mystified and infuriated Oliver Heaviside, when he altered and diminished Maxwell's equations to rid them of every potential that he could. Heaviside stated that the potential was *"mystical and ought to be murdered from the theory."* He tried to do just that, and conditioned generations of electrodynamicists to believe that the potential had no physical reality at all, but was only a mathematical convenience. Nahin expresses Heaviside's view as follows: "In an 1893 letter to Oliver Lodge, Heaviside said of his own work that it represented the 'real and true "Maxwell" as Maxwell would have done it if he had not been humbugged by his vector and scalar potentials.'" Paul Nahin, **Oliver Heaviside: Sage in Solitude**, IEEE Press, New York, 1988, p. 134, n. 37.

The concept of potential was developed by Poisson, Green, and others from about 1813 to 1827. Three notions involved in the development of the concept of the potential are: (i) there is the collection or storage of energy in the system, via the collection or storage of some entity therein, and this "potential energy" can be released and dynamically used, (ii) the potential is a scalar function whose spatial rate of change is a vector force, and (iii) the dynamics of the stored energy is suspended by the "storage" or "collecting" entity; in other words it is a sort of "suspended action" waiting to be unleashed. *It requires some action—such as interception and divergence—to release the leashed energy*.

We have to disagree with the second notion, having already discussed the fact that no vector force exists unless mass is present, since mass is a component of force. Here we have a residue of the old "material ether" concept. For the third notion, we note that the concept of a "virtual" particle or particle flux means that it cannot become observable unless some interaction is imposed. So we may handle the "third notion" requirement by assuming the potential to be composed of hidden virtual particle flux, or hidden wave flux, in wave-to-wave interaction.

Physics basically tries to define the electrical potential as energy per coulomb, or $\phi = W/Q$. That equation, however, is actually not a definition at all, but rather is an algorithm for calculating the magnitude of the excess energy collection/collecting upon a coulomb of charge, when that coulomb is immersed in the potential ϕ. It in fact is the *reaction cross section* of the potential, not the potential entity itself. This now begins to give us a clue. Potential is *energy* in some fashion. So the entity ϕ must have essentially the same definition as energy! Potential energy, collected energy, stored energy, whatever it's energy first and foremost.

Refer to our discussion of the 3-law logical contradiction in the concept of energy. The same logical contradiction must be present in the notion of the potential.

Just as we did for energy, we must define the scalar potential ϕ in two appositive ways: (i) in the wave view and (ii) in the particle view. So we define potential (particle view) as any virtual particle flux. We also define potential (wave view) as any hidden wave flux. Further, we note that the energetic vacuum is composed of a virtual particle flux (particle view) and so it is also a *potential*. Since the virtual particle flux of the vacuum is extremely intense, the vacuum potential is enormous in magnitude.

We shall also consider any other potential to ultimately be a change to the vacuum potential. Originally, one conceived of a potential occupying the "vacuum as an empty space." Then general relativity made the vacuum into spacetime, geometrized it, and made the geometry itself dynamic and operative—i.e., energetic. Okay! Then that makes spacetime itself a potential.

We also firmly dispose of the peculiar and deformed notion that the scalar potential of a point-source charge (at any spatial point that the potential occupies) may be *defined* as the "work performed upon a unit charge by pushing it in against the **E**-field of that source charge, to that spatial point." This is an equation and not a definition at all; instead, it is an algorithm for calculating the energy density magnitude of the scalar potential. It is a fine algorithm, but it has nothing at all to do with what the potential itself *is*. Again, a man cannot be defined as an algorithm for calculating the magnitude of his height or his weight or his energy density!

Without further discussion, we also somewhat extend the general relativity notion of spacetime as dynamic geometry, as follows: In a special sense, spacetime ≡ geometry ≡ potential ≡ "trapped " or collected/collecting energy. So when we engineer the internal structure of the potential, we also engineer the internal structure (subspace) of spacetime and spacetime geometry. Curvature of spacetime, e.g., becomes simply a change in the energy density of the vacuum, from the ambient value, and it can be internally structured so as to contain "engines". When we apply the hidden EM variable theory of the Stoney-Whittaker-Ziolkowski work, particularly when we consider the phase conjugate pairing as it exists in spacetime before interaction with charge, we are engineering and extending (i) electromagnetics, (ii) quantum mechanics, (iii) general relativity, (iv) spacetime, (v) the spacetime curvature concept, and (vi) spacetime geometry.

SCATTERING PROCESSES

Collision processes in which an incident particle such as a photon, electron, or proton, of known energy or direction or both, collides with another entity, and emerges from the collision with a different energy or direction or both.

SCHRÖDINGER, ERWIN

Noted Austrian physicist and Nobelist who discovered the wave equation named after him as the Schrödinger equation, and performed other vital work in wave mechanics.

SCHRÖDINGER EQUATION

In quantum mechanics: an equation that describes the propagation of waves associated with subatomic particles, or more generally, that describes the evolution over time of the quantum state of a system.

SCHUMANN RESONANCES

The extremely low frequency (ELF) resonant frequencies of the Earth-Ionospheric waveguide.

The first five Schumann resonances calculated from a simple model are 10.6 Hz, 18.3 Hz, 25.8 Hz, 33.4 Hz, and 40.9 Hz. However, better models are available and the frequencies vary from these simple model solutions. A better calculation gives the first four as 8, 14, 20, and 26 Hz nominally. The measured Schumann resonance corresponding to the 8 Hz is about 7.75 Hz. This is very near the mechanical resonance frequency of the human body, and also is evidenced in brain waves often "locking" to this frequency in the natural environment.

See W. O. Schumann, **Z. Naturforschung**, Vol. 72, 1952, p. 149, 250. For detailed models and discussion of the observations, see J. Galejs, **J. Res. Nat. Bur. Standards**, Vol. 69D, 1965, p. 1043.

SELF-ENERGY

In a quantum mechanical system, the energy associated with the emission and absorption of virtual particles.

In a classical system, the energy associated with the interaction among parts of the system itself.

SELF-ORGANIZATION

(After Davies, **The New Physics**, 1989): *"Spontaneous emergence of order, arising when certain parameters built in a system reach critical values."*

Simpler put, it is the spontaneous formation of patterns of localized order in a system which begins in a more homogeneous state. In short, the system moves from a simpler to a more complex state.

SELF-POTENTIAL (E.G., OF THE ELECTRON)

The potential created in and of the charge

...(e.g., the electron) by its virtual particle flux exchange with the vacuum.

Also, an asymmetry in the virtual photon flux of the vacuum, caused by the interaction of the charge (e.g., the electron) with the vacuum flux. From here, we note that the self-potential must consist of real observable 3-space EM energy flow or flows from the electron, because of the asymmetry. However, the charge is not the primary source *per se* of the energy flows that establish the self-potential, but instead is the asymmetric gate in the vacuum flux that "gates out" the potential and its energy flux. The asymmetry in the vacuum flux is the actual *source*. Indeed, the energy is received by the charge in the form of converging longitudinal EM energy waves from the complex plane (from the time domain). The spin of the charges of the dipole transduce the absorbed complex EM energy into real observable EM longitudinal wave energy, and pour it out in all directions in 3-space. See my paper, "Giant Negentropy from the Common Dipole," *ibid*. for the mechanism for the charge also.

SELF, SENSE OF

To be added.

SELF-TARGETING

Between two entities, where each acts partially or wholly as a phase conjugate mirror, self-targeting is the iterative phase conjugation or "ping-ponging" and rapid convergence of beams between the two PCMs.

It has a spectacular application in *phase conjugate shooting* from a spaceborne laser against a rising hostile booster, even several thousand miles distant. First a laser pulse is "bounced off" the distant target, and the reflected pulse returns to the receiver in the laser platform. It carries the movement-induced alteration of the distant target on the pulse it reflected. The next emitted pulse is an amplified phase conjugate replica of that received pulse, and it will backtrack to the same spot on the rising booster, leading it a bit and converging moderately so that it meets that spot. That spot begins to heat up, increasing its nonlinearity and making it act even more as a PCM. So its reflected signal off the "hot spot" is also a phase conjugate replica of the pulse that it received from the laser. That reflected pulse now will moderately converge its reflected energy upon the distant laser, increasing the return to the laser. The ping-pong continues, so that the laser beam narrows sharply upon the distant hot spot, and the reflected beam from the hotspot narrows sharply upon the distant laser. This "iterative narrowing ping pong" locks the laser upon the distant hotspot, even though the booster is moving. This process continues for the necessary dwell time, until the beam melts through that spot and explodes the hostile booster. The iterative phase conjugating reflection, or "ping ponging" between the target spot and the laser, is called *self-targeting*.

S-FLOW

The Poynting energy density flow S, where $\mathbf{S} \equiv \mathbf{E}\times\mathbf{H} + \mathbf{G}$.

E is the electric field, **H** is the magnetic field strength, and **G** is a trapped closed loop flow of energy density.

The **S**-flow is not the total energy flow per se. Since the fields **E** and **H** and the closed loop **G** are only defined in terms of the intercepted, trapped or "collected" energy, then **S**-flow is always *with respect to* some assumed intercepting/collecting entity, usually an assumed unit point charge.

SIGNAL WAVE

In nonlinear optics, the input signal (wave) to a phase conjugate mirror (PCM), which stimulates the PCM to emit a phase conjugate replica (PCR) wave in return.

SLEPIAN CURRENT

The vector jϕ , which in a current loop represents the energy unit area per coulomb of flowing charge, per unit of time, that is collected/collecting from the Poynting **S**-flow and dissipated in that current loop in its load s and losses.

It does not include the enormous amount of Heaviside nondiverged energy density flow that is flowing along the outside of the circuit conductors, and that is not being collected and therefore not being dissipated.

SLEPIAN FLOW

"Flow of collected-energy density dissipation" in a current loop,

...and therefore to the vector jf in the current loop, which represents the energy per unit area per coulomb of flowing charge, per unit of time, that is being dissipated in that current loop in its loads and losses.

It does not represent the enormous amount of energy that is flowing along the circuit, that is not being collected, not diverged, and therefore does not enter the circuit to be dissipated from it.

SLEPIAN VECTOR

Refers to the vector $j\phi$ in a current loop,

...which represents the energy density per coulomb of flowing charge, per unit of time, that is being dissipated in that current loop in its loads and losses.

It does not represent the enormous amount of energy that is flowing along the circuit, but not being collected and therefore not being dissipated. We accent that *only intercepted and collected energy can be dissipated!*

SOLID-STATE PARAMETRIC OSCILLATORS

A parametric oscillator circuit employing solid state devices.

A parametric oscillator is a device that oscillates by rhythmically changing a parameter (such as capacitance or inductance, etc.).

Simple switching between differing values of the parameter is often used to induced the periodic change of the parameter.

SOLITON

A wave pulse which propagates without changing its shape and without dispersion.

SOURCE DIPOLE

Any dipole, considered from the viewpoint that EM energy continuously pours out of it.

There is no true "source" as such in nature, since the energy is not created but only gated. In the case of the dipole and electrical charge as sources of EM energy, fields, and potentials, we solved that vexing problem in our "Giant Negentropy from the Common Dipole", *ibid*.

SPACETIME

The entity represented by the "fused product" of space and time, to give "space × time".

Spacetime is also dynamic geometry, in the general relativistic interpretation. We consider spacetime to be a potential, and also geometry, and also vacuum, and also virtual particle flux, and also hidden wave flux.

SPATIAL CLOUD

A cloud of something (such as electrons) in a spatial region.

SPATIALLY

With reference to space and spatial position.

SPECIAL RELATIVITY

Einstein's theory of inertial frames in which, if two systems are moving uniformly in relation to each other, one cannot determine anything about their motion except that it is relative.

Each of the two frames is said to be "rotated" with respect to the other, but not accelerating. The velocity of light in space (the vacuum) is constant, and is independent of the velocity of its source and the velocity of an observer. All the laws of physics are the same in all inertial frames of reference.

SPIN

The intrinsic angular momentum of a particle, such as an electron, proton, neutron, photon, graviton etc.,

...even when at rest, as if it were a top spinning about an axis, but had to spin 720 degrees before it turned "full circle."

Spin is quantized, and is always described as a half or whole spin, e.g., - 1, - 1/2, 0, 1/2, 1, etc. A spinning charged particle such as an electron thus demonstrates a magnetic moment, due to the circulation of charge in the spinning. In the nucleus of an atom, the spin of the nucleus is the resultant of the spins of the nucleons (particles comprising the nucleus).

Spin of particles would appear to be more like an "implosion" to "explosion" circulation; in other words, it circulates in the time domain (complex plane) as well. It would appear that the spin of a particle is the basic feature that integrates the (disintegrated) flux energy of vacuum flux into observable charge. Apparently all observable fields, matter, effects, etc. depend upon this basic mechanism to zip together virtual entities and form observable phenomena.

SPIRAL GALAXY

Those galaxies having arms which extend in the form of spirals.

About 70% of all galaxies are spiral galaxies.

The interesting thing is that only about 10% of the gravity necessary to hold the spiral arms together can be accounted for by known gravitational sources. This has led to the theorizing of dark (hidden) matter of exotic and unknown form, which would be responsible for the excess gravity.

The present author has proposed that the unaccounted enormous Heaviside component of the EM energy flow surrounding every field/charge interaction and not entering into that interaction, accounts for the missing source of the gravity. See "Dark Matter or Dark Energy?", Journal of New Energy, 4(4), Spring 2000, p. 4-11.

S-SOURCE

Source of Poynting energy density flow.

Source of **S** = **E**×**H** flow. The primary source is considered to always be an asymmetry in the virtual particle flux of the vacuum. The **S**-flow rigorously is that component of the overall energy flow that is intercepted by some system of interest—either present or assumed. That component of the overall energy flow that is not intercepted by the system of interest, is referred to by this author as the Heaviside energy flow or the dark energy flow associated with every field/charge interaction.

STONEY To be added

To be added.

STONEY/WHITTAKER BIWAVE DECOMPOSITION OF THE SCALAR POTENTIAL ACROSS THE DIPOLE

(i) a scalar potential (i.e., a difference in potential) exists between the end charges of a dipole,

(ii) that potential (difference) can be mathematically decomposed into a harmonic series of bidirectional EM wave pairs, where each pair consists of an EM wave and its precisely superposed time-reversed twin. Thus a dipole is a "source" or identically is a set of hidden bidirectional waves (wave view).

STRING THEORY

A rather recent mathematical physics theory which replaces the zero-dimensional "point" used in previous physics with a one-dimensional object called a "string".

It has been particularly effective in describing the gluon forces between two colored particles in particle physics, and has since been extended to many other areas. It is sometimes referred to as the "theory of everything".

"STRING" WAVE

The transverse wave on a taut string produced when the string is plucked.

The string wave itself stays on the string and does not travel through the slapped external medium.

However, Faraday believed that EM fields in vacuum consisted of "material lines of force" which behaved like such taut material strings, without any physical endholders. He thought that EM disturbances were simply the transverse disturbances of those "lines of force". He profoundly affected Maxwell's thinking, so that Maxwell accepted these physical lines of force. Consequently Maxwell *assumed* those same "transverse taut string vibration waves" in his EM wave theory.

In eliminating the "stringholders" for the assumed taut strings, Faraday and Maxwell discarded the Newtonian third law half of electrodynamics! They discarded half the energy and half the wave as well. Consequently today physics has no causative mechanism for Newton's third law, because it threw out the EM mechanism for it more than a century ago and never noticed it!

SU(2)×SU(2) SYMMETRY ELECTRODYNAMICS

To be added.

SUBSPACE

In vector mathematics: a subset of a vector space which is closed under vector addition and scalar multiplication operations.

In physics: Physics often uses the term "space" to refer to spacetime. It also uses the term "space" to refer to the dimensions of space, without the dimensions of time. At any rate, the spatial portion of spacetime is represented mathematically by some convenient number of dimensions. In the most usual practice, Minkowski spacetime of 3 spatial dimensions and one time dimension is utilized. In the Minkowski space, we now consider that "space" to be a vacuum scalar potential. If we consider the internal Stoney-Whittaker-Ziolkowski biwave pairs comprising that vacuum potential, we may transmit a signal communication along one or more of these internal biwaves, without changing any of the others. In that case, no overall potential gradient and overall forcefield signal appears. That domain that is infolded "inside" the scalar potential is said to be subspace. It may be modeled as a space of n-dimensions, where those dimensions are compacted and not observable to an external observer. Subspace gained great popularity from the Star Trek television series, where the spaceships used "subspace communications" to have signals propagate far faster than the speed of light. Bill Fogal has been working with some success on what should be a concrete realization of just this very "subspace communication system", with infolded signals that move much faster than the speed of light in vacuum.

SUPERCONDUCTIVITY

Property of some materials or metals whereby their resistance reduces to zero at very low temperatures.

These materials also exhibit many additional properties that are anomalous when compared to normal materials. Much research effort has gone into the attempt to find materials which exhibit superconductivity at higher temperatures, with the goal of reaching room temperature superconductivity.

SUPERLUMINAL

In a manner or with a speed faster than c, the speed of light in vacuum.

SUPERLUMINAL COMMUNICATION

The movement of signals faster than the speed of light in vacuum,

...and the transmission and reception of such signals and extraction of their transported information.

Longitudinal EM waves are not limited to speed c; transverse EM waves are limited to speed c. The infolded electrodynamics inside all EM fields, potentials, and waves consists of longitudinal EM phase conjugate wavepairs, with their impressed electrodynamics. Hence this "subspace" is a superhighway for such waves, including for those moving at superluminal velocity. In essence this is a very special kind of "tunneling" which we might refer to as *subspace tunneling*. The limitation to light speed rigorously applies to the modeled transverse EM waves which are a sort of "bulk upheaval" waves similar to waves on the surface of the ocean. As in the ocean wave analogy, "pressure" waves underneath the ocean may travel very much faster than the bulk upheaval waves on the surface.

When making longitudinal EM waves, the process is imperfect and the resulting longitudinal EM waves will have a transverse residue as well. The resulting "transverse-noisy" LW is called an *undistorted progressive wave*. Undistorted progressive waves may move slower than the speed of light or faster than the speed of light. See W. A. Rodrigues Jr. and J.-Y. Lu, "On the existence of undistorted progressive waves (UPWs) of arbitrary speeds $0 \leq v < \infty$ in nature," **Foundations of Physics**, 27(3), 1997, p. 435-508. A slightly corrected version is downloadable as hep-th/9606171 on the Los Alamos National Laboratory web site, and includes corrections to the published version.

SUPERPOSE

To lay or place on, over, or above something else, with the connotation of mixing.

SUPERPOSITION

The simple linear addition and subtraction of two or more values, states, etc.

Superposition is one of the key principles in field theories and in the concept of potentials.

SUPERSET

A large set referenced to a small set, where the small set is included in the larger set.

The large set is said to be a *superset* of the small set. The small set is said to be a *subset* of the larger set.

SW (STONEY-WHITTAKER) STRUCTURES

The Stoney-Whittaker hidden bidirectional EM wavepairs comprising the scalar potential, and structuring (altering) of same.

We call this internal EM dynamics inside every EM wave, field, and potential the "infolded" electrodynamics. Russian weapon scientists refer to it as the *information content of the field*.

SYMMETRICAL REGAUGING

In electromagnetics, changing the scalar potential to a different value, and simultaneously changing the vector potential to a different value, with the two changes just precisely selected so that the two extra forces (each created by one of the changes) are equal and opposite—thus canceling with respect to translation and doing no net external work.

We note that the two forces themselves must be considered to be present and still working continuously in opposition, increasing the stress upon the system regauged with excess energy, or decreasing the stress upon the system regauged with less energy.

This presence of "equal and opposite" excess forces from the symmetrical regauging is known as the *Lorentz condition*. The end result is that the *net* force fields of the regauged system remain the same, even though the stress of the system has been altered by the regauging and the potential energy of the system has also been changed. Since abstract vector mathematics contains no such thing as "stress" in its background vector space, zero vector resultant system of multiple nonzero vectors are most often simply discarded. Early electrodynamicists symmetrically regauged Heaviside's two "Maxwell" equations (potential form) so as to easily separate the variables. The net effect was to discard that set of the Heaviside/Maxwell equations that prescribed and included open electrodynamic systems that freely receive and collect energy from the external vacuum, and also obtain a free excess force which then can permissibly utilize that excess energy to translate and produce external work upon the system or externally upon a load. In short, the symmetrical regauging discarded practical overunity electrodynamic circuits and devices, which Maxwell's equations—even in their Heaviside modified form—have always prescribed and permitted. Contrast to asymmetrical regauging.

We specifically point out that the two extra forces remain, as does their energy, and both may be dynamic as the system is dynamic. Hence when one regauges, one has changed the gravitational aspects of the system and also curved the local spacetime. Further, this ST curvature is internally structured and that structure is dynamic. Thus contrary to the assumptions of electrodynamics, the regauged system *is not* the same as the original system.

SYMMETRY

A theory or process possesses a symmetry with respect to certain operations performed on it, if those applied operations do not change the theory or process.

The theory or process is then said to be "symmetric" with respect to those operations. As an example, there is no observable change in a circle when it is rotated or reflected in a mirror. The circle is therefore said to have rotational symmetry and reflection symmetry.

TANTALUM CAPACITOR

Electrolytic capacitor with a tantalum or sintered-slug anode,

...such as solid tantalum, tantalum-foil electrolytic, and tantalum-slug capacitors.

For the same capacitance, the weight and volume of the tantalum capacitor are less than comparable aluminum electrolytic capacitors. In other words, you can make the little son-of-a-gun smaller, for a given capacitance and charge it must hold. When utilized in the Fogal fashion, the tantalum capacitor also exhibits other properties that are still proprietary to Fogal's semiconductor processes and to Bill Fogal.

TARGETED PINPOINTS

Refers to those separated points which engage in self-targeting between themselves and some separated signal energy source (as in Fogal's semiconductor).

The effect is to sharply narrow the retroreflected source signal energy from the source onto the separated points by means of the mutual ping-ponging. In this fashion much more energy density from the source can be concentrated on the targeted pinpoints. In effect, phase conjugate shooting is evoked.

TENSOR

A special mathematical entity which is an element of a vector space such that it represents the tensor product of vector spaces and their duals.

Much of modern physics and advanced electromagnetics is expressed in tensor algebra theory.

TESLA, NIKOLA

Famous American emigré electrical inventor and eccentric whose numerous inventions fueled much of the electrical 20th century.

Tesla produced the AC system, including polyphase systems. From his experiments he knew that the EM wave in vacuum was longitudinal, like sound waves. In spite of his great accomplishments, his eccentricities and grandiose pronouncements did not endear him to electrodynamicists! An example is his acrid comment: *"...I showed that the universal medium is a gaseous body in which only longitudinal pulses can be propagated, involving alternating compressions and expansions similar to those produced by sound waves in the air. Thus, a wireless transmitter does not emit Hertz waves which are a myth, but sound waves in the ether, behaving in every respect like those in the air, except that, owing to the great elastic force and extremely small density of the medium, their speed is that of light."* Another major example is his statement: *"The Hertz wave theory of wireless transmission may be kept up for a while, but I do not hesitate to say that in a short time it will be recognized as one of the most remarkable and inexplicable aberrations of the scientific mind which has ever been recorded in history."*

Ironically, modern quantum mechanics has almost proven Tesla right that "the universal medium is a gaseous body." Today the modern QM vacuum is very much like a virtual particle gas. And of course the discussions in this present annotated glossary show why I personally am of the opinion that Tesla was also correct in his firm disbelief that those Faraday-Maxwell "taut physical strings without physical holders" filled the ether and provided transverse EM wave oscillations. I also agree with him that the EM wave in vacuum is a longitudinal wave, exactly like a sound wave. I believe that the transverse gyroelectron precession waves that our instruments actually measure in the conductor when it receives an incoming EM wave from the vacuum, proves that the vacuum wave is indeed longitudinal—else it would seem we must discard the spin of an electron and the theory of gyroscopes. Finally, one should see, e.g., Patrick Cornille, "Inhomogeneous Waves and Maxwell's Equations." Chapter 4 in **Essays on the Formal Aspects of Electromagnetic Theory**, Aklesh Lakhtakia, Ed., World Scientific, New York, 1993. Cornille clearly shows that Maxwell's equations are directly created by scalar potential interferometry. As he states, this means that EM force field wave s are created by the interference of sound-type scalar potential waves, or "sound creates light." This strongly supports Tesla's original statement that EM waves in the vacuum are actually EM sound waves, much like sound waves i n a gas.

TESLA'S MAGNIFYING TRANSMITTER (include Jackson quote)

To be added.

THERMOACOUSTICS

The generation of sound waves by heat.

THERMOACOUSTIC ENGINE

Essentially a closed resonant chamber containing three heat exchangers and a working fluid—such as an inert gas—under pressure, and used with a transducer to provide power such as mechanical power.

One heat exchanger is the hot-side exchanger through which heat is injected, another is the cold-side exchanger in which a coolant is circulated, and the third is a passive device between the other two, and known as a regenerator or thermal capacitor. The heating and cooling changes the pressure in the fluid greatly, and the regenerator oscillates back and forth, taking energy from the fluid, then giving it back, and keeping the engine going. A pressure wave (shock wave) moves through the working fluid and produces a resonator effect. The end result is an engine with rapidly fluctuating pressure gradients and no moving parts. The pressure gradients are then tapped off to drive a piston, which drives a linear alternator producing electricity. In a typical application, a single piston with a surface area of 1.5 square inches, and with a travel of only one centimeter, operated at 500 Hz, will produce about 30 horsepower output.

Information on these engines can be found on the Fellows Research Group website at http://www.io.com/~frg, or E-mail to frg@io.com. Many thanks to Oscar L. Fellows, "Be Our Guest: Thermoacoustic Engines—Propulsion, Power for the 21st Century," **Power Online**, 1/24/2000.

THERMODYNAMIC EQUILIBRIUM

Stable state eventually reached by an isolated system. One may consider it a "balanced" or "preferred" state.

Actually, a totally isolated system could not change. Any system is in a constant exchange with its vacuum environment, a priori, and no such thing as a completely isolated system exists in nature. Hence once excited, a system—to reach equilibrium—must exchange with its environment and is not a truly isolated system. But systems do exchange with their environment in hidden forms, so we can just let the original statement stand as is. Sloppy, but okay so long as we recognize the limits.

TIME

To be added.

TIME-CHARGE

To be added.

TIME-CHARGING

To be added.

TIME-ENERGY

To be added.

TIME-EXCITATION

To be added.

TIME-FLOW MECHANISM

To be added.

TIME-POLARIZED ELECTROMAGNETIC WAVE

An electromagnetic wave whose vibrations occur in the time domain only.

The wave is theorized in quantum field theory, or at least its time-polarized photon is theorized and called a "scalar" photon. There seems to be no Western method for detecting such waves, though they are predicted by theory.

TIME-POLARIZED (SCALAR) PHOTON

A photon whose vibrations occur in the time domain only, also known as a "scalar" photon.

TIME-FORWARD WAVE

A normal wave moving in forward time. Otherwise known as the retarded wave.

The external observer comfortably sees its forward progress as expected.

TIME REVERSAL

The process of forming the phase conjugate

...(e.g., of a wave or particle or entity or process or vacuum engine.).

We accent that *time-reversing a single object or single group of objects* is not the same thing as "travel into the past" so popularized by science fiction. For time travel to the past, the entire universe and everything in it except the traveler, would have to be time-reversed. That would not seem possible by any stretch of the imagination today! On the other hand, time-reversal of a single thing such as a particle or a wave—or even a group of things such as a group of particles or waves—is not only feasible but is readily achievable. A positron is a time-reversed electron, e.g. Becker showed that laughably weak DC electrical trickle currents (picoamperes) across otherwise intractable bone fractures could engender healing of the bone fractures. In investigating the effect, he showed that entire cells—specifically in that case, the red blood cells—were time-reversed (dedifferentiated) and then fast-forwarded (redifferentiated) into new kinds of cells, *genetics and all*.

In France in the 1960s and early 1970s, the Priore team showed in laboratory animals that this mechanism (which they nor anyone else understood they were unwittingly evoking) could be used to dramatically reverse and quickly cure terminal tumors, infectious diseases, arteriosclerosis, and suppressed immune systems. The same approach, if redeveloped, could stop and totally wipe out the emerging major new pandemic of hepatitis C, which nothing will touch at present and which will surpass AIDS infections after the turn of the century. The approach could totally reverse AIDS and eliminate all HIV infection, because it could simply time-reverse HIV-infected cells back to normal cells, genetics and all. In other words, it could readily and cheaply and quickly eliminate AIDS from the face of the earth. Further, the disease could be eliminated whenever a patient tested positive for HIV infection; there would be no need to wait for debilitation to set in. For coverage in detail, see T. E. Bearden, "Vacuum Engines and Priore's Methodology: The True Science of Energy-Medicine. Parts I and II." **Explore**!, 6(1), 1995, p. 66-76; 6(2), 1995, p. 50-62.

TIME-REVERSAL ZONE

A region of space in which a component of the overall time flow runs backwards, and hence the fundamental mechanism generating the flow of a mass through time is reversed.

Such zones are theorized as temporarily occurring in cold fusion, particularly once the palladium lattice is loaded with hydrogen or deuterium ions. Such a temporary region in the electrolyte is an excited state, and the other ions will move to nullify it and cause its decay. During its existence, ions in it experience a reversal of the law of attraction and repulsion of charges. In the TRZ, like charges attract and unlike charges repel. Thus suddenly the low spatial energy transmutation of elements in cold fusion experiments can be explained (they have been validated in some 600 successful experiments, in various laboratories in various nations, by excellent scientists). E.g., two H+ ions may attract, and so closely that each enters the edge of the strong force region of the other, forming a quasi-nucleus. Then as the TRZ decays, the preferred energetic change is from inside out. In other words, the gluon forces have been partially nullified and the quarks in the nucleons are almost freed. Hence the favored energetic decay from the excited state of the TRZ is by quark flipping, where one H+ ion in the quasi-nucleus changes into a neutron. The quasi-nucleus becomes a quasi-nucleus of deuterium, and will tighten into deuterium as the TRZ induced action vanishes. This is the way the excess deuterium is formed in the cold fusion experiments. Two deuterium D+ ions may also form a quasi-nucleus of (D+)(D+) particularly where the electrolyte is loaded with deuterium to start with. In that case, as the TRZ decays, the quasi-nucleus just tightens into a helium 4 nucleus or alpha particle, accounting for the excess alpha particles formed. And so on.

The concept of the TRZ thus is consistent with hundreds of successful experiments, and introduces a completely new type of nuclear reactions to physics, at low spatial energy where transmutations such as occur are not presently thought to be possible. We point out that these are extremely high energy reactions when the time-energy interaction is considered, since time has an energy density equal to mass. Time-energy is some c^2 times as dense as is spatial energy used by particle physicists in their interactions. By transposing some of the time-energy into spatial energy as the TRZ decays, the new "low energy nuclear reactions" actually involve the necessary degree of "high energy" required for the interactions.

TIME-REVERSED WAVE

A phase conjugate reflected wave, which is a wave moving in reversed time.

Since the external observer "sees" in forward time only, he sees the wave as traveling in the opposite direction as its generatrix wave front is moving.

TOPOLOGICAL

Invariant under transformation by continuous mappings.

...or related to the properties of geometric shapes and figures that remain invariant under transformation by continuous mappings.

TOPOLOGICAL PROPERTY

Those properties of a geometrical space that are unchanged by continuous distortion of the space.

TOPOLOGY

Mathematics of the properties of geometric configurations invariant under transformation by continuous mappings.

In short, the mathematics of the large-scale structure of curved spaces.

TOROIDAL COIL

A coil of wire curved around into toroidal form.

Contrast to the standard solenoidal coil form.

TOROIDAL TRANSFORMER

A transformer comprised of toroidal coils instead of solenoidal coils.

TRANSFORMATION MATRIX

A matrix (rectangular array of algebraic or numerical quantities) for replacement of the variables in an algebraic expression by their values in terms of another set of variables.

Used, e.g., in solving equations involving Hamiltonians.

TRANSVERSE

Wave movement perpendicular to the wave's primary direction of principal propagation, as in the movement of a taut rope in a wavelike motion traveling down the rope.

(As opposed to longitudinal).

TRANSVERSE EM WAVE IN THE VACUUM

The completely erroneous notion that EM disturbances in the vacuum are composed of transverse "string waves."

Faraday, e.g., believed that the EM field in the vacuum consisted of his "lines of force" as material taut strings—erroneously without the necessary holders to put the tension forces on the strings. He thought that when there was an EM disturbance, it was a "plucking" or transverse vibration of these "taut strings." Maxwell also believed in Faraday's material lines of force, and set out to capture them in his electrodynamic theory. He did so by simply assuming the lines (tubes) of force and their transverse "string wave" vibration. This is equivalent to assuming that the electromagnetic vacuum itself is composed of material taut strings, and that additional EM fields are just additional taut material strings.

TRANSVERSE FIELD COMPONENT

The modeled component of the electromagnetic field (as in a moving EM wave in vacuum) that is oriented at right angles to the line of motion.

TRANSVERSE WAVE

A wave where the medium is undergoing repetitive lateral translations, as a lateral wave in a taut string.

The EM wave is vacuum is erroneously modeled as a transverse "string wave," as a relic from Faraday's original belief that EM fields existed in the (assumed) material ether as physical taut strings. He thus believed that EM disturbances were the disturbances of "pluckings" of these taut strings. Maxwell accepted Faraday's physical lines of force and constructed his electrodynamics mode to specifically include the material ether, the physical "taut strings" lines of force notion, and Faraday's "string waves" as the electromagnetic vibrations in the ether. This discards half the energy, half the phenomena, half the wave, and Newton's third law causative EM mechanism.

TUNNELING

In quantum mechanics, a phenomenon where a particle penetrates and crosses a small region where the opposing potential is greater than the particle's available energy.

The phenomenon is thought to be impossible according to classical physics, but occurs nonetheless. Further, the speed of transit through the "tunneling" separation can be superluminal. Tunneling of music between two points has been measured to occur at more than four times the speed of light.

A more extended type of tunneling is the travel of longitudinal EM waves infolded inside the normal EM potentials, fields, and waves. Indeed, this is a more fundamental electrodynamics, and it can be shown that interferometry of this "internal" electrodynamics creates the external electrodynamics by a form of longitudinal EM wave interferometry. E.g., see M.W. Evans, P.K. Anastasovski, T.E. Bearden et al., "On Whittaker's Representation of the Electromagnetic Entity in Vacuo, Part V: The Production of Transverse Fields and Energy by Scalar Interferometry," **Journal of New Energy**, 4(3), Special Issue, Winter 1999, p. 76-78.

UNCONSCIOUS MIND

To be added.

UNIFIED FIELD THEORY (ENGINEERABLE)

A unified theory of the four forces of physics—the electromagnetic, gravitational, strong, and weak forces —that is not just an intellectual model but which is also engineerable on the laboratory bench and in actual physical systems using higher symmetry O(3) electrodynamics.

That's a mouth-filling phrase (yes, we sometimes write awkward phrases unintentionally; it's amazing how reasonable such things sound when you're laboring along at 3:00 a.m. and bleary-eyed as a wet toadstool!)

UNIFIED FIELD THEORY OF MIND AND MATTER

To be added.

UNITARITY

Principle that all probabilities sum to unity.

UNITARY Q_E

Fixed or unit charge q of the electron.

This notion is held only because the q is not decomposed into its component elements, but treated as if it were an indivisible unit. That is in error! The mass of a fundamental particle at rest is quantized, and the massless charge (self-potential) of the particle is discretized as a function of the background potential (virtual particle flux density) in which it is embedded or to which it is exposed. In our view the definition of a charge q is $q \equiv m_q\phi_q$. The *electrical charge* should be taken to be the massless ϕ_q component. The definition of charge q_e of an electron is rigorously given by the identity $q_e \equiv m_e\phi_e$. The *electrical charge* of the electron should be taken to be the massless ϕ_e component.

If a charge (say, an electron) is placed in an additional potential ϕ_1, then the total massless charge of the electron (i.e., its virtual vacuum flux exchange with mass me) is $(\phi_e+\phi_1)$. As can be seen, the massless charge of the electron (its virtual flux activity) has now changed. The electron is then said to *be collecting and to have collected* excess energy (which may be either positive or negative, depending upon the sign of ϕ_1.). Further, either ϕ_e or ϕ_1 or both can be internally and deterministically *dimensioned* (structured in Stoney-Whittaker-Ziolkowski fashion). When its massless charge (its own potential ϕ_e) is so dimensioned, then the dimensioned electron is said to contain or transport a *vacuum engine*.

VACUUM ENGINE

Particle view: Deterministic internal pattern or template deliberately created in the virtual flux of a scalar potential.

It can also be created in, and transported by, the two scalar potentials that comprise a static or dynamic force field, or a moving EM wave in the vacuum. It can also be created in the local vacuum, in which case it has a "charge-up" creation time and a "discharge time," exhibiting a sort of "time constant" very much like a capacitor charging and discharging. In the wave view, the vacuum engine is a deterministic internal pattern or template deliberately created in the Stoney-Whittaker-Ziolkowski internal biwaves and wave products comprising the scalar potential. Again, it can be implanted in the vacuum or in an EM signal as a carrier. The self-energy (scalar potential) portion of any electric charge or magnetic charge can also be a "carrier" that is conditioned (*dimensioned*) with a vacuum potential. The process or act of conditioning any of the carriers with vacuum engines is called *dimensioning* that carrier. Russian energetics refers to the vacuum engines of a dimensioned carrier as the *information content of the field*.

VACUUM FLUX EXCHANGE

The virtual particle interaction between the active vacuum and a charged particle.

The charged particle is an asymmetry in this flux exchange interaction, and extracts and gates some of the vacuum energy as a Poynting **S**-flow. In turn, this S-flow transports and creates in space the **E** field and the scalar potential f associated with the charged particle. An electrically charged particle is thus a little Poynting energy generator, a source of potential, and a source of **E**-field. It is a little electrical dynamo, a little free energy generator. It is already an open system in disequilibrium with its environment—the fierce vacuum flux. Its self-energy (potential) and its "fields," plus its Poynting energy flow, are the result of its asymmetry in the vacuum flux exchange.

VACUUM'S VIRTUAL PARTICLE FLUX

In the particle viewpoint, the quantum mechanical vacuum identically is a virtual particle flux.

Present physics, however, is prone to refer to the vacuum as (an implied emptiness) containing a virtual particle flux. Energy, vacuum, spacetime, virtual particle flux, and dynamic geometry are all synonyms.

VECTOR

In mathematics, an entity completely characterized by a magnitude and a direction.

VECTOR POTENTIAL

In electrical engineering: "Potential postulated in electromagnetic field theory."

Space differentiation (*curl*) of the vector potential yields the field. Magnetic vector potential is due to electric currents, while electric vector potential is assumed to be due to a flow of magnetic charges." [**Chambers Science and Technology Dictionary**, Peter M. B. Walker (Ed.), Chambers Cambridge, 1988, p. 947.

Note that the foregoing is not yet a definition, saying only that it is a postulated potential, then giving some characteristics. Informally, in my view the vector potential is just sort of an ordinary scalar potential, every point of which is in motion in something like a swirling fashion. The magnetic vector potential **A** is most common. There doesn't seem to really be a definition of **A**; the equation $\mathbf{B} = \nabla\times\mathbf{A}$ is usually (erroneously!) said to "define" the **A**. So we are left with the question **A** ≡ ????, since no equation is a definition of anything.

Electrodynamicists have no difficulty in calculating the direction and magnitude of **A**, and in using it, but so far as I can find there is still no real definition. As an ad hoc definition I consider the **A**-potential to be identically a virtual photon flux of vacuum that is moving as an ensemble along the direction of the **A**-vector. Inputs for a more rigorous definition of the form **A** ≡ (x**)** would be most welcome!

At any rate, the **A** is known to be quite real and an independent "field" of nature, because when the curl operator is removed from operating on **A**, the **B**-field is zeroed but the *curl-free* **A**-field can still remain and interfere with the fields of charged particles and magnetic poles to cause real effects in physical systems, including at a distance. This latter is known as the Aharonov-Bohm effect.

VECTOR FIELD

In ordinary theory, the assigning of a magnitude and a direction (that is, a vector) to each point in a region of space.

The entire set of vectors and their spatial points is called a vector field.

VECTOR ZERO

See discussion under *zero vector*.

VIRTUAL ANTIPHOTONS

An antiphoton that spontaneously appears and disappears, so swiftly that it cannot be individually observed.

VIRTUAL PARTICLE

A fleeting quantum particle that spontaneously appears and disappears, so swiftly that it cannot be individually observed, so that it exists only temporarily.

The virtual particle does not satisfy the usual relation between energy, momentum, and mass because it is underneath the Heisenberg uncertainty principle. The virtual particle can have any amount of energy momentarily, so long as the product of its energy and the time interval of its existence is less than the uncertainty principle's minimum magnitude.

Nonetheless, the interactions of large numbers of virtual particles with a mass or charge can combine to generate real observable effects. In quantum field theory, all forces of nature are caused by the interaction of the forced mass entity with virtual particles. Interaction of a mass with virtual photons, e.g., is projected to cause all mechanical and electromagnetic forces.

VIRTUAL PARTICLE FLUX EXCHANGE

Interaction with or exchange of, a flux of virtual particles.

Interaction of a mass with virtual particles most often consists of the mass absorbing the virtual particles and re-emitting them.

VIRTUAL PHOTON FLUX (VPF)

A flux of virtual photons.

(Hey, how's *that* for a tautology!) First, see definition and discussion under *flux*. For electromagnetics, the vacuum can often be modeled as a flux of virtual photons. One gets the virtual charges also, since the photon is considered to also consist of a positron-electron pair. That is, the photon is continually separating into a positron-electron pair, which then annihilate each other to form additional photon(s), etc.

VIRTUAL PHOTON FLUX EXCHANGE

The mutual exchange of virtual photons, as between the vacuum and a charged mass, or between two colliding masses.

The emitted photons from one mass are absorbed in the other mass and re-radiated.

VIRTUAL PHOTON FLUX OF VACUUM

The vacuum identically is a flux of virtual particles.

For most electromagnetic cases, it can just be modeled as identically a flux of virtual photons.

VIRTUAL PHOTONS

Photons which spontaneously appear and disappear in the vacuum so quickly that they cannot be individually observed.

VIRTUAL POSITRONS

Positive electrons (positrons) which spontaneously appear and disappear in the vacuum so quickly that they cannot be individually observed.

WHITTAKER, E. T.

Well-known mathematical physicist, who dramatically extended Stoney's earlier work of 1897-8 and authored two papers in 1903 and 1904 giving the basic theory of scalar electromagnetics (Russian energetics, not including the quantum potential portion).

The 1903 paper is E.T. Whittaker, “On the Partial Differential Equations of Mathematical Physics,” **Mathematische Annalen**, Vol. 57, 1903, p. 333-355.

The 1904 paper is E.T. Whittaker, “On an Expression of the Electromagnetic Field Due to Electrons by Means of Two Scalar Potential Functions,” **Proc. Lond. Math. Soc**., Series 2, Vol. 1, 1904, p. 367-372. The paper was published in 1904 and orally delivered in 1903.

WHITTAKER'S DECOMPOSITION OF THE SCALAR POTENTIAL

Decomposition of the scalar potential into a harmonic set of bidirectional longitudinal EM phase conjugate wavepairs.

In his paper “On the Partial Differential Equations of Mathematical Physics,” **Mathematische Annalen**, Vol. 57, 1903, p. 333-355, Whittaker showed that the scalar EM potential can be decomposed into a harmonic series of bidirectional EM wavepairs. In each pair, one wave is the phase conjugate of the other, and exists in the time domain. However, this phase conjugate wave has been considered as having been detected by intercepting charge as a 3-space EM wave travelling in a reversed direction. Hence from a detectable viewpoint, the Whittaker decomposition yields bidirectional longitudinal EM waves in 3-space, as has been pointed out by several electrodynamicists (e.g., Barrett).

However, the present author considered the difference between the phase conjugate wave as it exists prior to interaction with the assumed intercepting unit point charge, and the detected 3-space wave after the detecting charge is assumed. By applying the Whittaker decomposition and also considering the nature of the EM wave in spacetime *prior to interception by a unit point charge*, this led to the discovery of a new and more primary 4-symmetry in EM energy flow, once 3-symmetry is broken, that exists automatically between the time domain (complex plane) and 3-space.

Thus because a dipole (or a charge treated as a set of composite dipoles) breaks 3-symmetry (as is well-known in particle physics), the more general 4-symmetry results automatically when the nature of the potential between the ends of the dipole(s) is considered. This yields the fundamental mechanism by which EM energy is extracted from the vacuum (from the complex plane or the time domain) and output in 3-space from a "source charge" or a "source dipole". In short, it yields the giant negentropy mechanism when the unaccounted Heaviside energy flow component from a charge or dipole is considered as well as the intercepted tiny Poynting energy flow component. See T. E. Bearden, "Giant Negentropy from the Common Dipole", **Journal of New Energy**, 5(1), Summer 2000, p. 11-23; also on http://www. cheniere.org.

In his second paper, “On an Expression of the Electromagnetic Field Due to Electrons by Means of Two Scalar Potential Functions,” **Proc. Lond. Math. Soc**., Series 2, Vol. 1, 1904, p. 367-372, Whittaker showed that the interference of two such scalar potentials can and does create all the field energy, patterns, and functions of classical electromagnetics.

Whittaker's second paper initiated what today is loosely referred to as *superpotential theory*. For an excellent overview discussion of superpotentials and related things, see Melba Phillips, “Classical Electrodynamics,” in **Principles of Electrodynamics and Relativity, Vol. IV of Encyclopedia of Physics**, edited by S. Flugge, Springer-Verlag, 1962.

WORK

The changing of the form of energy.

WORK, EXTERNAL

The changing of the form of the external energy of a body or system.

WORK, INTERNAL

The changing of the form of the internal energy of a body or system.

WORK-ENERGY THEOREM

To be added.

ZERO POINT ENERGY

The minimum energy of a system due to its quantum fluctuations, resulting from its incessant virtual particle activity. Quantum mechanically, no system of interest (including even spacetime itself) can have zero energy.

The zero-point energy of the vacuum is the lowest energy vacuum state, with fluctuations taken into account. Even at low energies, quantum fluctuations continually arise, and result in an incessant, extremely rapid, and violent "jittering" of the energy momentarily present. The minimum energy due to these quantum fluctuations is called the *zero-point energy.*

ZERO VECTOR

(1) A vector having no length (no magnitude) or specific direction.

(2) Absence of any or all finite vectors.

(3) Resultant of a system of multiple, finite vectors whose vector sum has no specific direction.

Note that the second definition differs drastically from the first. That is, we cannot say that a vector resultant zero has no infolded magnitude, if we consider its components, all of whom have magnitude. See the discussion under "zero." In vector analysis, the zero vector axiom states that any vector v plus a zero vector is equal to a zero vector plus v. Note that, being an axiom, this is not proven, but just assumed. We very much disagree with that blanket axiom; it reduces vector analysis to a highly special single case, where all zero vector systems are to be considered equal, and totally "inactive." In the real world that need not be true at all. There are an infinite number of different zero vector resultant systems, and so zero vectors may differ, if their infolded component "substructure" is considered. In the real world, things that are vectors very often have energy. The energy is infolded and hidden, so that it represents not only a local curvature of spacetime, but also a structured, deterministic set (a *template*) of curvatures of local spacetime. Therefore this zero vector system is actually a *vacuum engine*. Any mass system placed in such a potential, will be acted upon in its parts by that local vacuum engine. Further, the zero vector resultant system is a "potential," since it does contain "collected internal energy." This potential is obviously an artificial potential, since it is deterministically structured internally.

So between zero vector resultant systems, the "infolded, hidden energies" differ dramatically in

(i) total infolded and trapped (collected) energy,

(ii) specific internal action patterns (templates),

(iii) general relativistic effects, and

(iv) type of vacuum engine. Accordingly, the actions the zero-vector system induces in an exposed mass may be designed in advanced. This is vacuum engineering. This is spacetime engineering.

The problem is the *vector algebra itself*. In the abstract algebra, a "vector space" is regarded as an inert thing, where the only actants are the overall net nonzero vectors, and there is no interaction between an overt vector and a covert set o f vectors. The vector space is not allowed to have an internal realm, stress, hidden engines, or to interact with the vectors representing the physical system. Consequently, for over a century electrodynamicists—thinking primarily of translation—have routinely discarded such "zero vector systems" as if they represented the total absence of any finite vector. *This they do, in the unsuitable assumptions of the vector algebra*. This they do not do, in the real world.

The common practice in electrical physics of replacing a zero-summed system of nonzero vectors with a vector zero of "complete absence of vectors" is incomplete, and such did not exist in Maxwell's original *quaternion* theory. This present practice should be changed; it has reduced the topology of electromagnetics far too much, and gutted the most important parts of the theory insofar as an extended electromagnetics is concerned. The vector zero should be replaced with a special organized vector zero system and a scalar potential. The interactions of the "hidden" vectors should be incorporated. By failing to do this, physics excludes the ability to engineer electrogravitation, spacetime, the virtual state, local general relativity, free energy, effects at a distance, and the probabilities of the states propagated by the Schrödinger equation. It also excludes unification of all forces.

In the new view, a zero vector may be a system of nonzero vectors that vectorially sum or multiply to zero for translation purposes, but the components may still exist "inside" and dynamically function inside the zero-resultant envelope. This substructure can act on nonlinear or resonant systems. Any or all components may be time varying, or none of them may be. The zero vector system may thus be a dynamic vacuum engine. In addition, such a vector zero system is considered to be also a scalar stress potential, whose magnitude is equal to the sum of the absolute values of the perpendicular components. In addition, a separate type of stress potential may be included for the magnitude of the absolute values of the swirl components (torques). Other associated potentials may be included for the system, particularly if the system is in multiple dimensions, if it consists of more than one type of virtual particle flux, if several fluxes intercommute, etc. Such a system can also be designed and created to deterministically interact with and on the life force itself, the mind, thought, and personality, but that is beyond the scope of this discussion.

ZERO-VECTOR-SUMMATION SURFACE

A surface or assumed spatial surface in which vectors under consideration interact to sum to a vector zero resultant.

ZERO-VECTOR-SUMMATION SYSTEMS

Zero summations of real, nonzero vectors, so that the real vectors are still present but do not cause translation of exposed mass or charges.

With respect to observing/detecting process that depend upon charge translation, the vectors are said to be hidden and infolded —i.e., with respect to detection by translation. See discussion under *zero vector*.

ZIOLKOWSKI, RICHARD

To be added.

Return to top of page

The "Porthole" Concept with technical background

Amplifying the cellular regenerative
(healing) system of the body for
treatment and healing
of mass casualties



Outline of the presentation

- Mechanism for deep EM exchange of a body with its active EM environment
- Becker's epochal work and its ramifications
- Kaznacheyev's startling results and ramifications
- Weaponization of Kaznacheyev's findings
- Importance of time-energy and the time-domain
- Mechanisms for medical treatment and healing

Outline of the presentation (2)

- Prioré's revolutionary results and their ramifications.
- Proposed new mechanism for cancer promotion.
- Porthole concept: The 2-minute shortcut.
- Terrorist biological warfare capabilities.
- Summary and conclusion.
- Budgetary and Program package.



Mechanism for the body's deep EM exchange with its active EM environment

And some ramifications



The body continually receives and retransmits EM energy

- The body may be considered as a dielectric.
- Every part of the dielectric participates in the absorption and emission of each photon to and from any point on the surface.*
- Mechanical force effects are also electrical in nature and exchange similarly.



* Reali, G. C., "Reflection from dielectric materials," American Journal of Physics, 50(12), Dec. 1982, p. 1133-1136. The reflected field from a dielectric material is not generated just at its surface but comes from everywhere in the interior of it.

Ramifications:



- There is an EM "dielectric transmission path" connecting every part of every cell to every part of the surface of the body.
- All electrical processes in the body, including deep within the cell and its nucleus, participate in the absorption and emission of every photon to and from the body's outer surface (and every mechanical force* experience).
- The EM emission energy of the body is a conglomerate mix of fractions of all processes and functions ongoing in the body or affecting it, including in every cell.
- This includes all electromagnetic, mechanical, chemical, and environmental effects upon and in the body and every tiniest part of it, and provides an extended definition of "stress".

* At base, all normal mechanical forces are generated by electromagnetic forces.

Ramifications (2)



- The reaction of each photon absorbed on any point of the outer surface of the body, connects through the dielectric transmission path to every part of the body, including to every part of every cell*.
- Every emission from the body is participated in by every part of the body, including every part of every cell.
- The body's emission "changes" its environment, adding EM radiation. Some of the internal induced changes (excited states) in the body decay by this external emission. Some do not, but must be otherwise dealt with internally by the body systems.
- The body's EM absorption allows the environment to change or affect every function, operation, and part of the body, by adding EM radiation. All are continually being affected and deviated, both helpfully and harmfully, by these deeply induced EM interactions.
- The body's reaction (healing) must continually readjust and correct deviations from normalcy, in every part of every cell.

* In quantum physics, part of the photon is localized and part is nonlocalized, reaching even across the universe.

Ramifications (3)



- The sum total of all the impinging external EM radiation upon the body, plus mechanical "special EM" radiation, thus affects and changes the body and all its processes, participating in them.
- That impinging EM radiation can be manipulated to either harm or heal the body and any or all of its cells.
- The body must continually overcome these externally-induced EM changes in its cells and processes, to maintain normalcy. Some EM changes are restored by the subsequent dielectric emission process, relieving the previously-induced deviant EM excitations in its internal processes. Some are not.
- The poorly studied *cellular regenerative system* performs the remainder of the restorative function, which is the fundamental "healing" function of the body.*

*The cellular regenerative system was mostly studied by Becker and a few others. See R. O.Becker, and David G. Murray, "The electrical control system regulating fracture healing in amphibians," Clinical Orthopaedics and Related Research, No. 73, Nov.-Dec. 1970, p. 169-198.

Becker's epochal work

And its ramifications



Becker's bone fracture healing

- Tiny DC currents (picoamperes)
- Pulsed DC current can be utilized
- Pulsed magnetic fields may be utilized


(+)
ELECTRODE
DC POWER SOURCE
(-)
ELECTRODE
BONE
BONE
FRACTURE SITE

RED BLOOD CELL DEDIFFERENTIATES

Shucks hemoglobin coat
Grows nucleus

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes cartilage

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes bone
Deposits in fracture site, healing the fracture

Becker's theoretical DC control system involved with response to injury


INJURY

INPUT STIMULATION
DC SYSTEM (PAIN)

CENTRAL
DC SYSTEM

GROWTH
DIFFERENTIATION

LOCAL CELL INJURY
FREE RADICALS

OUTPUT
DC SYSTEM

TOTAL
CURRENT OF
INJURY
DC SYSTEM

MITOSIS
DEDIFFERENTIATION

STIMULATION OF
REPAIR CELLS

*Robert O. Becker, "The significance of bioelectrical potentials," Bioelectrochemistry and Bioenergetics, Vol. 1, 1974, p. 191.

Becker's proposed control system governing regeneration*



Trauma Producing
Tissue Loss

Local cellular effect

Local nerve effect

CNS effect

Alterations in hormone
pattern (prolactin)

Alterations in local
DC field pattern

Local electrical
effects

Local and systemic
pools of target cells

Dedifferentiation into
primitive mesenchymal cells

Phase I

Blastema formation

Growth

Phase II

Redifferentiation into
required cell types

Restoration of body
part or tissue

*Becker & Spadaro, "Electrical stimulation of partial limb regeneration in mammals," Bull. N. Y. Acad. Med., 48(4), May 1972, p. 629.

Extending Becker's work

- Becker had only the archaic classical electrodynamics available to him. That EM is grossly inadequate.
  - Insufficient group symmetry to model the process.
  - Already eliminates the "infolded" longitudinal wave EM that structurally and dynamically comprises all "normal" EM potentials, fields, and waves.
  - It is this internal LW EM that is manipulated and used by the cellular regenerative system.
- Nonlinear phase conjugate optics was not yet developed when Becker did his seminal work.
- Successful higher symmetry electrodynamics models -- such as O(3) -- have been developed and are available.

A sad commentary



- Becker was nominated for the Nobel Prize, but he was hounded, his funds were withdrawn, and he was forced to retire early.
- His main "sin" was having the courage to testify against the harmful effects of unrestricted powerline radiation and electronic smog.
- Powerful interests then crushed him, set up their own well-funded institutes, and hired scientists who then predictably found that powerline radiation was no problem.
- Such research is so tainted that recently several important journals have now required the authors of submitted papers to state what their affiliated companies do, and what "company massaging" of their research occurred.
- From a higher symmetry EM view, it is obvious that the dielectric pathway and quantum electrodynamics already show a significant problem due to such radiation, particularly with respect to long-term effects.
- This is particularly significant since "noise" -- the mere presence of more "hash" -- appreciably amplifies the dielectric transmission effect. So the major factor becomes EM smog *signals density*, not signal power.

Kaznacheyev's startling results

And its ramifications



Proof that the cellular condition is radiated from groups of cells

- It follows that a diseased, damaged, or infected cell culture will and does emit its exact internal EM condition, hence the disease or damage "generatrix form" itself (in the internal structuring of the EM radiations).
- Further, these "state" emissions can couple into other targeted cells to produce disease and disorder in them.
- This was clearly proven in some 15,000 Russian experiments by Kaznacheyev.
- Kaznacheyev demonstrated induction of cellular disease and disorder between EM-coupled but otherwise environmentally shielded cell cultures
- Similar experiments have been replicated in the West by Reid *et al*., and by Popp *et al*.

Kaznacheyev's induction of cellular disease and disorder



GRAVITON LATTICE TEMPLATES

SICKEN OR KILL

ENVIRONMENTAL SHIELDING

CELL CULTURE SAMPLE #1

QUARTZ CONTAINER

CELL CULTURE SAMPLE #2

QUARTZ CONTAINER

THIN WINDOW

✸ GLASS: No Effect

✸ QUARTZ: Delayed Effect

ⓒ T.E. BEARDEN 1977, 1987

Divided bottle setup

Note: Minimum lattice is one harmonic interval: IR to UV is such a minimum G-lattice. Consider particularly the dielectric pathway in the emitting diseased cells and in the receiving targeted healthy cells.

Another surprising feature of Kaznacheyev's experiments

- The experiments do not work if the targeted cells are in normal light, such as sunlight*.
- The reason is that the normal light bandwidth occupies a single harmonic interval between ultraviolet and infrared.
- Hence its difference frequencies also fill such an interval. For a set of n frequencies, the number *d* of difference frequencies is $d >> n$.
- Thus the visible light spectrum represents "jamming" of specific internal EM signal inputs through the dielectric pathway into the body, turning much of the environmental signals into harmless warmth.

* It has also been shown that if bacteria are killed in the "dark" by UV, then 24 hours later placed in sunlight, a substantial fraction of the "dead" bacteria will revive.

Ramifications of Kaznacheyev's experimental results

- At least one harmonic interval is necessary for the effect to be evidenced in the target cells.
- Interestingly, if we assume the body dielectric to be isotropically nonlinear (to first order):
    - Velocities of the actual transmitted frequencies depend upon the particular point on the wave amplitude.
    - The transmitted frequencies overshoot, interfere, breakup, etc. The difference frequency does not.
    - The "difference frequency" is transmitted through the nonlinear dielectric medium as if it were a sine wave passing through a linear medium*.
- To our knowledge, this direct and deep communication of electronic "hash" difference frequencies in dielectric human bodies has not been investigated in the West.

* Owen Flynn, "Parametric arrays: A new concept for sonar," Electronic Warfare Magazine, June 1977, p. 107-112.

Ramifications of Kaznacheyev's experimental results (2)

- A heterodyne signal -- at the difference frequency between an input signal and a reference signal -- can be enhanced by adding noise*.
- Thus the signal of the disorder in the cellular pattern emitted from diseased cells, received by normal cells, can be amplified electronically and rather easily.
- Powerline radiation (electronic smog) thus carries its own amplification mechanism. Eventually the amplification overcomes any squelching by sunlight, etc.
- The Russians promptly (as early as the late 1950s) weaponized and tested these and similar effects.

* Dykman, M. I. et al., "Noise-enhanced heterodyning in bistable systems," Physical Review E, 49(3), Mar. 1994, p. 1935-1942

Weaponization of Kaznacheyev's findings

And its ramifications

"Microwave" radiation of the U.S. Embassy in Moscow.

Former U.S. Embassy in Moscow.



BACKGROUND

- Began in latter 1950s
- Discovered on VP Nixon's trip
- Initially thought to be *nuclear* radiation (Discovered w/Geiger counter)
- High level target -- U.S. Ambassador
- Guarantees personal attention of:
  - U.S. Ambassador to USSR
  - U.S. President
  - NSA, CIA, DIA, NSC, etc.
  - Top consulting scientists
  - Leading U.S. scientific institutions
- Two U.S. Ambassadors died, another sickened
- Anomalous health changes in personnel, only in zero-field (zero pot'l gradient) areas!
- Four U.S. Presidents requested Soviets cease
  - Cut from 18 watts/sq cm to 2
  - Then again increased
- No one could understand what was going on
- Aluminum screens were placed over windows
- Moscow was declared a hazardous duty zone

Ramifications of the microwave radiation of the U.S. Embassy

- The cellular disorder pattern in the EM radiation is carried by the field-free scalar potential.
- Since the disorder pattern is a "conglomerate", it must be carried by an internal EM structure existing inside the scalar potential itself.
- Whittaker decomposed the scalar potential into the appropriate internal longitudinal EM biwave structure in 1903*.

* E. T. Whittaker, "On the Partial Differential Equations of Mathematical Physics," Mathematische Annalen, Vol. 57, 1903, p. 333-355

The importance of time as energy, and the time-domain



Time as energy



- In physics, the fundamental units one uses in his model are arbitrary.
  - A valid model can be made using only one unit.
  - It is already done in one branch of physics, using length as the single fundamental unit.
- Make a model with a single unit, the joule.
  - All other entities become functions of the joule.
  - We are familiar with mass as highly compressed EM energy, by the factor c^2.
  - It turns out that time is also highly compressed EM energy, by the factor c^2.
  - 1 sec. $\approx 9 \times 10^{16}$ joules.

How to see that "time is compressed spatial energy"

- Take some spatial EM energy and compress it by c^2
- Place it in 3-space, and it is *mass*.
- Place it on the time axis, and it is *time*.



PRESS

SOME
SPATIAL
ENERGY

PRESS

by c^2

PUT IT ON 4TH MINKOWSKI AXIS

OR

PUT IT IN 3-SPACE

time (seconds)

time axis

mass (kilograms)

3-space

- When time-energy is converted into mass-energy, time is "decompressed" (expanded) into 3-space EM energy and 1 sec. $\approx 9\times10^{16}$ joules.

Time as EM energy in the time domain, with a density the same as mass-energy



- Bearden* reinterpreted (corrected) the 1903 Whittaker decomposition of the potential in 2000.
- The reinterpretation is consistent with broken symmetry in particle physics, for which Lee and Yang received the Nobel Prize in 1957.
- It is also powerfully supported by quantum field theory, notably by Mandl and Shaw in 1984**.
- Whittaker's pair is a combined time-polarized (scalar) EM wave and a 3-space longitudinal EM wave.

* T. E. "Giant Negentropy from the Common Dipole," Journal of New Energy, 5(1), Summer 2000, p. 11-23.

** F. Mandl and G. Shaw, Quantum Field Theory, Wiley, 1984, Chapter 5.

All EM energy in 3-space freely comes from the time domain



(Time)

SOURCE
CHARGE
OR
DIPOLE

Real
EM
Energy

pours out

in all
directions

3-space

Longitudinal EM wave incoming from time domain and absorbed

Charge's 720º spin transforms time-energy into 3-space energy

Longitudinal EM waves emitted in all directions in 3-space

Whittaker, Math. Ann., 57, 333 (1903) shows this rigorously, when properly reinterpreted. Dipole's broken 3-symmetry is well-known in particle physics

Note: Whittaker (and others) interpreted the phase conjugate half set of LWs after interaction with the charges of the dipole, and as a 3-space *effect* rather than the time-domain *cause*. This fundamental non sequitur was just repeated since then, until corrected by Bearden to be consistent with broken symmetry and quantum field theory.

Strong support from quantum field theory



- Quantum field theory recognizes four photon polarizations:
  - Energy along x-, y-, z-, or t- axis.
  - Polarized along x- and/or y-axis, the photon is a *transverse* photon.
  - Polarized along z-axis (along its line of motion in 3-space), the photon is a *longitudinal* photon.
  - Polarized along the time-axis, the photon is a *time-polarized* or *scalar* photon.
- The individual longitudinal or scalar photon is not observable*.
- The combination of a longitudinal photon and a scalar photon is observable as the instantaneous scalar potential*.

* F. Mandl and G. Shaw, Quantum Field Theory, Wiley, 1984, Chapter 5.

Mechanism generating the flow of a mass through time





SPATIAL
SPATIOTEMPORAL
L^2 T PHOTON
SPATIAL
PHOTON
MASS
L^3
MASSTIME
L^3T
MASS
L^3
L^2 T
ⓒ 1995, 1997 T.E. BEARDEN
SPATIAL AND SPATIOTEMPORAL
"MASS"
MASSTIME
L^3T
MASS
MASS
MASSTIME
L^3T
"MASS"

$$(\Delta E)(\Delta t) + M \Rightarrow (M+\Delta M)\Delta t \Rightarrow M + (\Delta E)(\Delta t)$$

Flow of macroscopic time (observable photon interactions)

Flow of microscopic time (via virtual photon interactions)

Mechanism is engineerable

Pumping a mass in the time-domain will time-reverse it back to an earlier state

- The reinterpreted biwave EM structure of the scalar potential means that time-reversal (phase conjugation by pumping in the time-domain) can be utilized to time-reverse a targeted cell (its mass-energy) in its entirety, including its genetics.
- Becker's bone fracture experiments showed it:
  - Weak scalar potential across the fracture site.
  - LWs in 3-space and time-energy waves in time
  - Red blood cells entered, dedifferentiated by shucking their hemoglobin and growing a nucleus, which is dedifferentiation (time-reversal of the cell and its mass-energy back to a previous physical state).

Principle for time-reversing a time-pumped mass



- Becker's cells then redifferentiated and changed -- first to primitive cartilage cells, then to primitive bone cells which were deposited in the fracture, healing it with new bone growth.
- This shows "time-forwarding" (redifferentiation) of the cell also.
- Becker actually showed that the *time-domain pumping* of the cells (by the time-polarized EM waves of Whittaker's reinterpreted wavepairs comprising the scalar potential), and the time-pumping of their mass-energy, operated to continuously and steadily *remove the delta between that cell's present condition and its former "normal" cellular physical condition in that area*.
- This is the long-sought secret of stem-cell research.
- Phase conjugate optics had not been born at the time. Without realizing its full nature, Becker demonstrated the body's own internal mechanism for healing, and the fundamental mechanism for time-reversing a physical mass, whether living or inert.

Mechanisms for use in medical treatment and healing

And ramifications

Successive deep penetration reactions of the cellular dielectric

- Change after change affects the cell and all of its parts, including from the external environment.
- Each successive change affects primarily the internal "LW EM structures and dynamics" comprising the ordinary potentials, fields, and waves.
- Thus in positive time the internal EM structurings produce successive "overlaid layers of change" -- so to speak -- in the internal EM structuring and dynamics of a cell in the body. These layers contain the "delta" from normal state.

Successive deep penetration reactions of the cellular dielectric (2)

- During time reversal, highest layer deltas are successively "peeled away" by the interaction of the mass-energy with the time-domain pumping.
- The result is to return the cell directly back to successive physical states, in the case of a single disease or disorder.
  - A cancer cell is returned to a normal cell prior to its "promotion".
  - An HIV-infected cell would be returned to its normal unaffected condition, free of HIV-induced genetic change.
  - For injuries and damage, the existing "delta" in each successive state-layer is steadily reduced to zero.
- This process thus can involve both cellular differentiation and dedifferentiation, as shown by Becker and by Prioré.

Engines (vacuum engines, spacetime curvature engines)

- Following Whittaker* as reinterpreted**, all normal EM fields, potentials, and waves decompose into sets of longitudinal EM waves (LWs) and their dynamics.
- Since these LWs and their dynamics are dynamics in the local energy density of spacetime (ST), they constitute *ST curvatures*.
- Hence they are general relativity infolded inside electrodynamics.
- By manipulating and changing these LWs, one manipulates and changes spacetime curvatures and their dynamics.
- The result is a unified field model where one directly controls and engineers a set of ST curvatures by use of higher group symmetry electrodynamics.
- Controlled patterns of local curvatures of ST are called "vacuum engines" or "spacetime curvature engines" -- or just "engines".

* E.T. Whittaker, Math. Ann., 57, 333-355 (1903); Proc. Lond. Math. Soc., Series 2, 1, 1367-372 (1904).

** T. E. Bearden, J. New Energy, 5(1), 11-23 (2000).

Pumping with EM time-polarized waves forms *amplified* antiengines


A_2
A_2^*
Type text
A_4
Type text
A_3
MASS
previous state
A_1
A_1^*

INPUT (engine resident in the mass itself)

Time domain longitudinal EM pump wave

CELL MASS

highly nonlinear to any and all LW frequencies

Antiengine acts upon mass at all levels

Time domain longitudinal EM pump wave

AN AMPLIFIED VACUUM (SPACETIME) ANTIENGINE IS FORMED AND ACTS ON THE MASS, TIME-REVERSING IT AND ALL ITS COMPONENTS NO MATTER HOW SMALL

© T.E. BEARDEN 1997

A DRAMATIC EXTENSION TO NONLINEAR OPTICAL PUMPING


transverse pump wave
A 2
transverse signal wave (input)
A 4
PPCM
A 3
NONLINEAR MEDIUM
amplified phase conjugate replica transverse wave (time-reversed)
transverse pump wave
A 1

a. Pumping with transverse EM waves produces a time-reversed *wave*.


PREVIOUS VACUUM ENGINE
PREVIOUS MASS STATE
+ t
TIME AXIS
A 2
t 2
RESIDENT VACUUM ENGINE (input)
MASS
Output
AMPLIFIED VACUUM ANTIENGINE
A 1
t 1

b. Pumping with longitudinal EM waves A_1 and A_2 time-reverses *the mass itself*.

Time-reversal of a mass to a new physical state not in its past

- Original engine A'
- New engine B' added
- Time-pumping moves to new "past" that is determined by (A'+B')


VACUUM ENGINE A'
VACUUM ENGINE (A' +B')
TIME AXIS A
A 2
MASS
VACUUM ENGINE B'
TIME AXIS (A+B)
TIME AXIS B
AMPLIFIED VACUUM ANTIENGINE [A' + B']
VACUUM ENGINE B
VACUUM ENGINE A
A + B
A 1

Extended general relativity principle

- All levels of energy structures and all levels of time structures mold spacetime geometry.
- The "pattern" is called a *template* for a vacuum engine (spacetime curvature engine).
- Spatial and temporal structurings of the engine act upon any exposed mass at al levels.
- This produces a template of forces, for precise translations and stresses within the mass at all levels. The forces exist in both time and 3-space.


STRUCTURING OF ACTIVE SPACETIME CURVATURES
ACTIVE SPACETIME
DYNAMIC MASS

Engines: Working spacetime demons



Internested patterns
of spacetime
curvatures

Highly Structured
Einsteinian spacetime

**Demons work
at all levels**

Maxwellian Demons
are EM hidden variables
organized into dynamic
structures acting at all levels

Signal vs. vacuum engine



SIGNAL (INFO)

- ★ Information received
- ★ Any overt physical action must be taken by cell itself
- ★ Cell must furnish the energy for any action it takes
- ★ Passes from outside to in

A. *Cell must do the action itself; vacuum energy exchange is passive. Energy or fuel for doing the action must be added to cell externally.*



ENGINE (STRUCTURE)
TEMPLATE (FORM)

- ★ Information itself acts
- ★ Local spacetime curved, with internal subcurvatures
- ★ Produces template of forces in local spacetime (ST)
- ★ Arises from within local ST
- ★ Acts on and changes all parts of cell, including its genetics

B. *Cell is acted upon; vacuum energy exchange does the specific action. No energy or fuel for doing the action need be added to cell externally.*

Unified field theory requires modeling and use of supersystem

Three components interact with each other:

- System and its dynamics
- Local active vacuum and its dynamics
- Local curvatures of spacetime and their dynamics.


LOCAL ACTIVE VACUUM
SYSTEM
LOCAL CURVATURES OF SPACETIME

Classical EM kills the supersystem, prevents supersystem engineering

- Assumes flat local spacetime
- Assumes inert vacuum


LOCAL ACTIVE VACUUM
SYSTEM
LOCAL CURVATURES OF SPACETIME

Malignant teratoma exhibits both time-reversal and fast-forwarding

- A teratoma cell is a tumor cell that has reverted to stem cells, then proceeds to differentiate toward new kinds of normal cells.
- May produce hair, skin, muscle, heart, bone, and other type cells.
- Sometimes present at birth.
- Demonstrates both "time-reversal" and "time-forwarding".
- The missing key is the engine function(s).

Miller-Fox-Urey biogenesis experiments



- Engines of and from all life forms ever on earth or in the universe exist in the ambient vacuum potential.
- The Miller-Fox-Urey experiments were not in a "sterile" environment.
- Heat (IR) and UV constitute (1) a harmonic interval with a difference frequency, and (2) amplifying by the process previously shown.
- These experiments "kindled" previously living forms from the available gases etc. by amplifying the ancient living engines from their virtual state to the observable state, so that the masses were molded into the physical states of their templates.

Biogenesis Experiments


To spark coil
Electrode
Sparking
Organic molecules
Gas molecules
Condenser
Gaseous mixture of ammonia, methane, carbon dioxide, hydrogen, and water vapor
Boiling water

Cloning to produce stem cells

- Human DNA can be inserted in an animal cell, and the cell chemically tricked into proceeding as if fertilized.
- Formation, increase, and growth of stem cells begins and continues.



- The "engine" carried by the human DNA is changing the matter available into human cells.
- readily demonstrated experimentally.

Regeneration in a strain of rat with part of its immune system missing

- In mammals, the immune system plays a role in reducing the regeneration capability, compared to that of more primitive systems.
- In a strain of rat where that "suppressive" part of the immune system is missing, the regenerative capability is dramatically increased.
  - Can regrow cut away sections of tail.
  - Regrows plug cut out of ear.
  - Reconnects severed optic nerve.
  - Partially restores severed spinal cord.

- The suppressive "delta" engine of the immune system, operating simultaneously with the underlying primitive regenerative engine, sums to the modern much-reduced regenerative engine in the mammal.

An observation for the future

- When the science of engines is developed, physicians will be able to tailor these engine combinations to restore severed human spines, regrow severed limbs, etc.
- They will also be able to direct the body's "normal growth" to reduce and direct birth defects, genetic defects, etc.



Biochemistry and EM models

- Medical scientists analyze such things as teratomas in terms of biochemistry and the biochemical model.
- An assembly of charges and charge distributions, with their associated fields and potentials, drives all chemistry at base level.
- The charge assembly and its dynamics involves a corresponding assembly of spacetime curvatures and their dynamics. These are *the cause that is driving the charge assembly and its dynamics, and therefore the chemistry*..
  - In unified field theory (such as that of Sachs) and O(3) electrodynamics.
  - Not in classical U(1) EM theory or quantum electrodynamics.
- Conventionally a causative EM field in space is "defined" as the *diversion from* that spatial field by and after its interaction with charge).
  The "definition" substitutes the effect for the cause, a non sequitur.
- This is a known major flaw, pointed out in one fashion or another by many physicists such as Wheeler and Nobelist Feynman.
- Classical EM theory is a 137-year-old model, seriously flawed. These flaws emerge in biochemistry and medical science.

Necessary EM corrections*

- Many of the corrections necessary in electrodynamics modeling either have been done or are underway.
- Higher symmetry, non-Abelian electrodynamics models have long been developed in particle physics.
- The new approach extends these models to also incorporate general relativity, thus producing a unified field theory*.
- In the new approach, spacetime curvature engines are perfectly natural and understandable, and can be directly modeled and engineered by advanced theorists.
- In short, the theory is sufficiently advanced and robust that technology and engineering can now advance.
- This will be a great leap forward for biochemistry and medical science, particularly in therapeutic methods.

* Sachs's unified field theory implemented by O(3) electrodynamics presently is the most suitable to use. Numerical methods are required.

Prioré's revolutionary results in lab animals

And its ramifications

Prioré (right) makes a point to Chaban-Delmas, Mayor of Bordeaux

- Many of the Prioré team's experiments were done in Bordeaux.
- Antoine Prioré patents:
  - "Apparatus for producing radiations penetrating living cells," U.S. Patent No. 3,368,155, Feb. 6, 1968.
  - "Method of producing radiations for penetrating living cells," U.S. Patent No. 3,280,816, Oct. 25, 1966.
  - "Procede et dispositif de production de rayonnements utilisables notamment pour le traitement de cellules vivantes," [Procedure and Assemblage for Production of Radiation Especially Serviceable for the Treatment of Living Cells], Republique Francais Brevet d'Invention P.V. No. 899.414, No. 1,342,772, Oct. 7, 1963.



Block diagram of Prioré's method

Time-reversing the cells back to normal state



START

SELECT A SET OF TRANSVERSE EM WAVES

ADJUST WAVE FREQUENCIES IF REQUIRED, AND IRRADIATE AGAIN

MIX WAVES IN A PLASMA, CONVERT TO LONGITUDINAL. EM WAVES

MIX OUTPUT INSIDE STRONG PULSED DC MAGNETIC FIELD

EXPOSE WHOLE BODY OF PATIENT TO DIMENSIONED MAGNETIC FIELD

CELL AND ALL ITS PARTS ARE PUMPED IN INNER EM CHANNEL IN TIME DOMAIN

VACUUM ENGINE FOR DISEASED CELL ALREADY PRESENT

DISEASED CELL PHASE CONJUGATES ITS VACUUM ENGINE

FORMS AMPLIFIED VACUUM ANTIENGINE FOR CELL'S DISEASE VACUUM ENGINE

TIME-EXCITATION CHARGING ENDS. IRRADIATION IS HALTED.

ANTIENGINE CONTINUES TO ACT AND TIME-REVERSE CELL AND ALL ITS PARTS*

CELL RESTORED TO NORMAL?

NO

YES

STOP

*Includes genetics

In Laboratory Animals:

Prioré Team Cured

- **Terminal malignant tumors**
- **Clogged arteries (atheriosclerosis)**
- **Suppressed Immune Systems**
- **Infectious trypanosomas**
- ***Results were presented to French Academy of Science by Robert Courrier, Director of the Biology Section of the Academy***

© 1999 T. E. BEARDEN

- ***No one understood the mechanism!***

Some peculiar results by the Prioré team

- Once a rat is cured of a particular disease:
  - A single drop of blood from the cured rat, injected into another rat stricken with same disorder, would result in the injected rat getting well slowly.
  - This ability to transfer immunity and healing in the extracted drop of blood gradually decayed over a period of a few weeks.
- Showed that even the fields and potentials in the blood had been altered internally, in the treated animal.
- Showed that the injected animal's cellular regenerative system possessed the ability to also time-domain pump over the entire body, everywhere reducing the delta between that injected drop of blood now the rat's own, and the rest of the blood in its body.

Proof of cellular time-reversal

- Pautrizel compared identical treatment of immature rats with immature immune systems, and mature rats with mature immune systems.
- Treatment restored the damaged mature system back to full mature functioning, and it promptly recognized and dispatched the pathogens.
- Treatment restored the damaged immature system back to full immature functioning, unable to cope, and the pathogens promptly reinfected and killed the immature rat.
- The lesson: The body is indeed returned to a previous physical state. The pathogens themselves are not killed by the treatment, but by restoring the ability of the immune system to recognize and destroy them.
- Only the *previous ability* of the immune system is restored by the process.



PROF. RAYMOND PAUTRIZEL
(Renowned Parasitologist)

Disadvantages of Prioré method

- Large plasma tube and facility required.
  - 3-stories high building bay if to treat humans.
  - Long irradiation time (2-3 hours).
  - Slow, numerous experimental adjustments.
- Fundamental mechanism was unknown.
  - Phase conjugate optics not yet born in West.
  - No higher symmetry EM modeling used.
  - Prioré thought it was a result of ionization.
  - Importance of difference frequency unknown.
  - Body dielectric transmission path unknown.

3-Story high Prioré device for treating humans

- At the end of the project, Prioré had developed a large unit to treat humans.
- A few were treated.
- Cures replicated what had been done in lab animals
- The massive size of the unit and long treatment time (hours) made the process bulky and very inconvenient -- and also expensive


Giant coil around 12-ft long plasma tube
Pulsed DC Magnetic field
Table for reclining human body

17-foot Prioré plasma tube

Used in large machine (3-stories high) to treat a limited number of human patients



A proposed new mechanism for cancer promotion

And its ramifications



Remarks on cancer from a new perspective

- Two stages: cellular damage and promotion of the damaged cell to a tumorous cell. Promotion presently is poorly understood if at all.
- A master cellular control system (MCS) (studied by Popp et al.) controls both the immune system and the cellular regenerative system, as well as normal functions of the cells.
- The "past history" of ancestral development of aerobic cells and higher multicell aerobic bodies on planet Earth, resides in the "internested engine layers" in every tiniest part of the entire body dielectric, and in all cells.

Remarks on cancer from a new perspective (2)

- Faced with cell damage (such as sustained hypoxia) it cannot handle, the MCS continues to "peel the layers" in taking actions related to ever more distant pasts.
- Faced with continuing hypoxia, e.g., the MCS eventually reaches ancestral layers -- with an engine -- it forces the damaged cells to start moving back toward the original primeval anaerobic form.
- The first step backward is *separation from central growth control*, freeing the cell to multiply independently. At the same time, genetic changes in the cell are forced and produced, starting it back toward becoming an anaerobe.
- These actions comprise the *promotion process*.

The promotion process via engines



"ENGINE" USED TO
PRODUCE " DELTA

PRESENT STATE ENGINE

MOST RECENT PAST STATE
THAT WAS "NORMAL"

MORE DISTANT PAST STATE
THAT WAS "NORMAL"

FURTHER PAST STATE
THAT WAS "NORMAL"

PAST STATE BEFORE
CENTRALIZED CONTROL

PRIMEVAL ANAEROBIC
STATE BEFORE AEROBES

LAYER
ENGINE
SELECTED

MASTER CELLULAR
CONTROL SYSTEM

IMMUNE
SYSTEM

CELLULAR
REGENERATIVE
SYSTEM

LAYER AND
ENGINE
SELECTOR

START

DELTA
ENGINE

DELTA
ELIMINATED?

IS THERE
A DELTA?

INJURED
CELLS

RESIDENT ENGINE

STOP

Evolution of aerobic systems



ESSENTIALLY
ANAEROBIC
ATMOSPHERE

BIOGENESIS

SINGLE CELL
ANAEROBIC

CHANGE OF
ATMOSPHERE
TO AEROBIC
(INCLUDES
OXYGEN)

OBLIGATORY
ANAEROBES
SINGLE CELL
SHIELDED
FROM OXYGEN

FACULTATIVE
ANAEROBES
(SINGLE CELL
BOTH AEROBIC
AND ANAEROBIC)

EVOLVE TO

SINGLE CELL
AEROBIC*

EVOLVE TO
MULTICELL
AEROBIC*
(INCLUDES MAN)

CENTRAL CONTROL

SINGLE CELL
COMPONENTS

IMMUNE SYSTEM
RED CELLS
WHITE CELLS
KILLER CELLS
ETC.

MULTICELL
COMPONENTS

TISSUES
MUSCLES
BONES
ORGANS
SKIN
STRUCTURES

** NOTE: LIMITED ANAEROBIC RESPIRATION STILL TAKES PLACE IN HIGHER AEROBIC LIFE FORMS, INCLUDING MAN.*

EVOLUTIONARY TIME

First step in self-promotion of cancer due to hypoxia



PAST

PRESENT

MULTICELL AEROBIC
(INCLUDES HUMANS)

SINGLE CELL
ANAEROBIC

SINGLE CELL
AEROBIC*

CENTRAL CONTROL

OXYGEN-RICH

TIME-FORWARD
PATH AS IT
DEVELOPED

CANCER CELL

TIME-REVERSED
PATH FOR SUSTAINED
OXYGEN DEFICIENCY

PARTIALLY
ANAEROBIC

SINGLE CELL
AEROBIC

FIRST STEP IN OXYGEN-DEFICIENCY
DEDIFFERENTIATION

Block diagram of the cellular regenerative system


ADD PUMPS
B
CELL AS A PHASE CONJUGATE MIRROR
ANTIENGINE PRESENT?
N
Y
RESIDENT VACUUM ENGINE
PRIORÉ AMPLIFIED PUMPING
START
A
CYCLE
CELL AND INTERIOR SENSORS
LOCAL VICINITY SENSORS
NONLOCAL ALL-BODY SENSORS
APPLY ANTIENGINE
DELTA CATALOGS
CELLS AND INTERIORS
SELECT LOCAL
SELECT NONLOCAL
AEROBE
ANAEROBE
Y
N
DELTA?
Y
N
DELTA?
Y
N
DELTA?
AEROBE
ANAEROBE
AEROBE
ANAEROBE
AEROBE
ANAEROBE
B
A
SWITCH TO AEROBE CONTROL SYSTEM
A
Y
CROSS THRESHOLD BACK TO AEROBE?
N
SWITCH COMPARATIVE CATALOG
SWITCH TO ANAEROBE CATALOG
Y
END OF AEROBE CATALOG?
N
SUM FOR ENTIRE BODY
SWITCH ON CENTRAL, OFF DECENTRAL GROWTH CONTROL; RESET IMMUNE SYSTEM
SWITCH OFF CENTRAL GROWTH CONTROL
SWITCH ON DECENTRAL GROWTH CONTROL
CONDITION IMMUNE SYSTEM TO ACCEPT
A

R&R SYSTEM
Regeneration Example

© T.E. BEARDEN 1998

Bombshell: Amplified EM healing

- A unified field theory approach and use of supersystem analysis has broken the basic mechanism for healing itself.
  - The Sachs unified field theory applies and has been partially fitted.
  - Evans-Vigier O(3) electrodynamics can properly model it, including both the internal and external electrodynamics and effects of engines.
  - Direct engineering development is now possible.
- Experimental proof of the results obtainable already exists in the literature.
- A medical revolution is in the offing.

Potential Medical Applications

- Non-traumatic cancer treatment
  - *Cure cancers and leukemias of all types*
  - *Remove pre-cancerous state*
  - *Restore system*
- Treat and cure Infectious diseases
- Cure AIDS and restore immune systems
- Defense against biological warfare
  - *Virulent diseases from unknown agents*
  - *Treat, cure prior to symptoms developing*
  - *Both civil populace and armed forces*
- *Dramatically lower health costs*
- *Rejuvenate the aged*

© 1999 T. E. BEARDEN

To treat and save mass casualties: What is urgently needed now:

- A small, portable, relatively inexpensive treatment unit, not requiring plasmas etc.
- Treatment in 2 to 5 minutes rather than 2-hours.
- Simple treatment application, almost anywhere.
- Effective in advanced stages as well as prior to emergence of symptoms.

- Effectiveness against a wide array of illnesses.
- Use is easy, high school student can be trained in 30 minutes.
- Crash program to develop, flood down through emergency systems in great quantities.

The Solution:


Equipment Case

- Two blankets have antennas in them.
- Uses the "porthole" concept (discussed shortly)
- Eliminates plasma tube mixing etc.
- Computer-controlled complex signal structure.


Computer
Control Unit
Signals
Function
Generator
Antenna Pad

The Porthole concept:

The two-minute treatment shortcut



How the porthole concept works


INSIDE THE BODY
OUTSIDE THE BODY
Body surface
Dielectric channel
as a body "porthole"
Time
Reversal
"my engine is..."
Amplifier/mirror
"Reverse your engine..."
PAST
HEALTHY
CELL
THEN
INTERIOR
SICK
CELL
NOW
Antiengine
maker

Porthole concept: An analogy of the dielectric path and inner-outer functional connections

- Imagine perfectly reversible dynamic light processes inside a large "cruise ship", that are also perfect phase conjugate mirrors
- Each process receives, absorbs, and emits light continuously
- Light escaping through the portholes is a composite from all the dynamic processes ongoing inside
- If we record and amplify the escaping light, then force it back through the portholes, it reverses all the internal processes
- The processes revert back, slowly, to a previous ongoing process state
- We cease radiation, and the processes reverse and move forward again



Porthole concept: The discovery

- The processes themselves, *in their own "frame"*, are never actually "reversed". Instead, the frame's motion through time is reversed.
  - Each to itself moves normally -- just receiving, absorbing, and radiating light, regardless of "whatever light" is interacting
  - This is due to a peculiarity of the photon and photon interaction
- Photon interaction creates observed physical reality, including the "frame" and the seeming "passage of a mass through time"
  - The photon is its own antiparticle, which is just a photon traveling in the opposite direction
  - So in this case we can use "light" to precisely time reverse (to the observer) the frame and the apparent operations (to the observer)
- When we cease irradiation, after a decay period to remove the reversed excitation, all functions are now seen to be moving forward normally in observer forward time, but from a previous physical state or condition

Using the porthole concept: Research

- The body's own emitted dense, broadband signals are recorded across a broad bandwidth
  - These signals are amplified, then rebroadcast precisely back into the body
  - This returns an amplified "reversed" signal set back through the dielectric path, invoking and applying the porthole concept in all processes
- The returning photons produce time-charging but in reversed frame direction
  - Tremendous potential energy is absorbed in highly compressed "time-energy" form in seconds
  - This "time-potential" slowly drains off as the body processes and cells reverse back to a previous state

Research using the porthole concept



Alterations Database

Recorders & Broadband Amps

TIME DENSITY CHARGE IS STRUCTURED TO CONTAIN THE PRECISE SPACETIME CURVATURE ENGINES FOR TIME-REVERSAL AND STEERING. CHARGING OCCURS QUICKLY. ENGINES CONTINUE TO WORK FOR AN EXTENDED PERIOD AFTER CHARGING CEASES.

Control Unit

Broadband Antenna Unit

Receiver-transmitters

Adjusting broadband signals
bandwidth and amplification
by selecting indicated alterations
from database

© T.E. BEARDEN 1998

Portable unit then developed for rapid treatment of mass BW casualties

- Two blankets have antennas in them.
- Uses the "porthole" concept (discussed shortly)
- Eliminates plasma tube mixing etc.
- Computer-controlled complex signal structure.
- Irradiation for 2 minutes.


Equipment Case
Computer Control Unit
Signals Function Generator
Antenna Pad

Training to use the unit

- High school student level, 30 minutes.
- Patient lies on one blanket, other covers him.
- Set the prescribed standard signal sets from listing.
- Computer-controlled generator produces the signal.
- Irradiation for 2 minutes, uncover patient, bring in another.
- Unit can be self-powering from vacuum energy (MEG*).


Equipment Case
Computer Control Unit
Signals Function Generator
Antenna Pad

Additional advantages

- Can be developed in a crash program in 2-3 years.
- After sunk costs, projected cost per unit in mass production is less than $100,000
- Can be produced by the thousands
- Then flooded down through
  - Fire stations and police stations
  - Red cross units, hospitals, clinics
  - Emergency action teams and armed forces
- Large numbers of operators easily produced
- Emergency training could be watching a 15 minute film, then performing one graded practice run
- First generation equipment can save some 70% of the coming mass casualties from anthrax etc.





Terrorist BW warfare capabilities against the United States

● ● ● ● ● ● ● ● ● ● ● ● ● ● ● ● ● ●

The growing threat

Mass Casualty Problem: Aerial Anthrax Spray on Washington, D.C.

- **One terrorist, one light aircraft with spray tank**
- **100 kilograms of anthrax**
- **Flies over greater metropolitan Washington, D.C.**
- **Calm night**
- ***1-3 million casualties result****
- ***Most of those stricken will die***
- **Presently little can be done to save the stricken civilians**
- ***Attacks on several population centers might produce some 10 million or more casualties***

***Per OTA Report to Congress, 1993**

For decades, infiltration of terrorist teams into the U.S.

- From several foreign nations, not just Bin Laden in Afghanistan
- Several thousand Cuban guerillas, from training camps in Southern Mexico
- Russian Spetznaz teams
- Nuclear warheads (up to 80 KT)
- Biological warfare agents
- Yakuza in oriental populations in our cities
  - Yakuza manufactures Russian energetics weapons in their own facilities in Japan
  - Possesses the new EM weapons referred to by Secretary of Defense Cohen in 1997
- We are now in a very long, hard war and will suffer millions of casualties in our cities. It may last for decades.

Defense Secretary Cohen*

(Involvement of secret superweapons)

"Others [terrorists] are engaging even in an eco-type of terrorism whereby they can alter the climate, set off earthquakes, volcanoes remotely through the use of electromagnetic waves… So there are plenty of ingenious minds out there that are at work finding ways in which they can wreak terror upon other nations…It's real, and that's the reason why we have to intensify our [counterterrorism] efforts."

* Secretary of Defense William Cohen at an April 1997 counterterrorism conference sponsored by former Senator Sam Nunn. Quoted from DoD News Briefing, Secretary of Defense William S. Cohen, Q&A at the Conference on Terrorism, Weapons of Mass Destruction, and U.S. Strategy, University of Georgia, Athens, Apr. 28, 1997.

Some typical BW agents

- Smallpox, including different strain developed by Russia (some sold to terrorists)
- Anthrax
  - Over 400 known locations around the Earth have cultures
  - Difficult to decontaminate
- Bubonic Plague
- Botulism toxin
- Tularemia (rabbit fever)
- Hemorrhagic fevers, such as Ebola



Anthrax

- OTA study: Some 200 pounds released in a spray, on calm night over Washington, D.C. could result in up to 3 million casualties
- Symptoms usually in 2-10 days
  - Sometimes as long as 7 weeks
  - Flu-like symptoms



- Then 1-3 days later, shock and breathing problems cause death in up to 100%
- Antibiotics given early (before symptoms) can prevent infected persons from becoming ill
- Limited vaccine, reserved for military

Smallpox

- More than 500 million people killed in the 20th century before "eradicated" in 1977. Vaccination ceased in 1980.
- Russians kept it, developed new strains, sold to terrorists
- Symptoms in about 12 days: fever, headache, nausea. Rash similar to chickenpox then appears.
- Rash turns into hard blisters. *Highly contagious*, kills one-third of its victims.
- No cure. About 12 million doses of vaccine left.
- If smallpox is unleashed in any major city on earth, it will eventually kill 2 billion, or about 1/3 of the human species -- unless a radical new cure is found and utilized.

Bubonic Plague: Historically the most feared (Black Death)

- From 1980-1994, 18,739 cases in 20 countries.
- Symptoms occur in 1-6 days after inhaling the pneumonic form.



- High fever, cough, labored breathing lead to respiratory failure and death.
- It is contagious.
- Rapid use of antibiotics can be effective.
- Vaccine not currently produced in the U.S.

Botulism toxin (a nerve toxin)

- Single most poisonous BW substance known.
  - Typically borne in food, contacted by eating.
  - Could be developed as aerosol weapon.
- Symptoms in 24-36 hours; blurred vision and difficulty swallowing, speaking.
- Paralyzes muscles, leading to respiratory failure and death.
- Centers for Disease Control and Prevention maintain a botulism antitoxin supply.

Tularemia



- U.S. studied its weapon potential in 1950s and 1960s.
- Symptoms appear in 3-5 days, including fever, chills, headache, and weakness
- Inflammation and hemorrhaging of the airways can lead to death.
- Without antibiotics, one-third die. Can be 90% if breathed in, in aerosol form.
- Vaccine developed and under review by FDA.

Hemorrhagic fevers, such as Ebola

- E.g., origin of Ebola is unknown. Probably transmitted to humans by animals, to begin a breakout.
- Symptoms in 3-5 days, include fever, aching muscles, diarrhea.
- Hemorrhaging of fluids out of tissues and orifices.
- From 30 to 90 percent die, depending on specific fever type.
- Some of these fevers respond to antiviral drugs.
- The drugs are in short supply.
- Presently *containment* is the primary goal.

A factor the U.S. does not know

(Secret involvement of clandestine superweapons)

- Three nations (not the U.S.) developed quantum potential weapons using Bohm's hidden variable theory of quantum mechanics.
- Can induce disease engines in matter or bodies at a distance.
- Have developed "spreading" of immune systems in a targeted populace (cleverly tested in Gulf War against U.S. troops).
  - Cocktail mix of disease engines for 2 dozen different diseases
  - Targeted area's human immune systems react to these engines when they are still in virtual state, just below quantum threshold.
  - Spread immune system's resources thus "thinned" across response to two dozen shadow diseases at once.
- Hit with a terrorist BW attack, the spread immune systems are overwhelmed much more easily and quickly.
  - Yield (casualties) of the attack is increased by factor of 3-5.
  - Spreading of U.S. immune systems has been accomplished and is still being maintained.



Summary and conclusion

The new war

A new Pearl Harbor: Strike on the World Trade Center in NYC

- The North Tower has already been struck and is burning.
- A second jetliner is about to strike the South Tower.



CNN PHOTO
Morning of 11 Sep. 2001
World Trade Center, NYC

Fireball From Impact on South Tower

- The two buildings held some 50,000 occupants
- Evacuation was underway after the first strike
- More than 6,000 persons were killed
- This is more than were killed in the Dec. 7, 1941 strike on Pearl Harbor

Associated Press photo

Collapse of the South Tower

- The first tower to collapse was the South Tower
- It is still uncertain just how many people were caught inside and killed
- This is a half million tons of debris, falling from the New York skyview.

Photo from CNN

Collapse of the North Tower begins

- The North Tower then collapsed
- This was another half-million tons of debris falling from the NYC skyview

Collapse of North Tower finishes

- Collapse of the North Tower killed many rescue workers, fire-men, and policemen
- At this writing, the total casualties are still unknown

Photos from CNN

Next began the recovery efforts

- Recovery operations will require months
- At this writing, the total casualties are still unknown
- The damage was done by two civilian jetliner "bombs"

The Pentagon was hit on the same day

- Hundreds were killed the same day when another jetliner struck the Pentagon.
- Yet another jetliner, possibly headed for the White House, crashed enroute when the passengers attacked the suicide terrorist hijackers.



A sobering thought



- Nuclear weapons are already smuggled into the U.S., as are BW agents such as anthrax, smallpox, etc.
- Had a 40-80kT weapon been exploded in New York and one in Washington, millions would have perished and both cities would have been devastated
- There would have been no recovery of those cities for many decades

Present Status of the WMD Threat to the United States





- Many foreign nations are hostile to the U.S. and sponsor terrorists
- Some 25 nations have WMD or are acquiring them
  - BW agents and weapons
  - Chemical agents and weapons
  - Nuclear materials and weapons
- Thousands of students and émigrés
- Infiltrated teams, BW, other WMD already
- Castro guerrillas infiltrated over the years
- Can do unacceptable damage to U.S. now
- *May reach knockout capability*

© 1998 T.E. BEARDEN

***Per OTA Report to Congress, 1993**

The U.S. is terribly unprepared

- Limited medical supplies, antibiotics, vaccines
- Insufficient facilities, emergency teams
- No civilian shelters (much less BW-filtered)
- Not enough doctors, nurses, masks, etc.
- Present treatment methods woefully inadequate
- Triage will apply
  - First treat those most likely to recover
  - Others (showing symptoms, or advanced) are just set aside to die
- Other attacks are a matter of *when*, not *if*.

Conclusion

- As several cities are struck, millions of U.S. civilian casualties will result. Devastation will be enormous.
- We shall eventually lose more American lives than in all the rest of our wars to date.
- Present medical therapeutic science is totally inadequate to do the job. It cannot save us.

- At some point, when we are sufficiently damaged, the Spetznaz or other terrorists may detonate nuclear weapons in our cities, with appalling carnage.
- A combined superweapon technology and terrorist groups will then destroy the remaining populace.
- On its present course, the inadequacy of Western medicine may doom us.

A difficult truth to consider

- In any strategic strike, the first phase is to get the strategic weapons (weapons of mass destruction) delivered to their distant targets.
- That has already been done.
- Eerily, the first phase of World War III has already been accomplished.
- It was already accomplished before the Sept. 11, 2001 strike on New York and Washington. That was the new "Pearl Harbor", and only the opening round. It already killed more Americans than died at Pearl Harbor on Dec. 7, 1941.
- Unless we improve our medical therapy quickly and dramatically, we will lose -- particularly when the hidden energetics weapons and outside terrorist sponsorship by hostile nations are factored in.

A personal perspective

- There now exists an overwhelming, immediate moral imperative to get this development program done at the utmost speed humanly possible.
- The sheer survival of the United States and Western civilization depends upon it.
- Officialdom is aware that the KGB/Russians have long planned to finish the U.S., after initial nuclear exchanges, by fierce and massive BW strikes.
- It appears that the plan has changed to let the terrorists do the main work, while augmenting U.S. casualty levels by energetics weapons.

China is also involved

- China has declared South China Sea the territorial waters of China
- China will eventually take Taiwan
  - Has massed missile artillery trained on Taiwan
  - Recently held invasion practice on an island near Taiwan
- Recently deployed fearsome EMP weapons utilizing negative energy rather than positive energy (Dirac sea theory)
  - Extinguishes all electron currents
  - Duds electrical and electron systems instantly
  - Instant death to struck bodies
  - Instant kill of missiles, aircraft, electronics in nuclear warheads
  - Ultimate "death ray"; can be made small or large
- Recent 2-carrier U.S. task force maneuvered in South China Sea to caution China
  - The new Chinese EMP weapon was trained on that task force
  - Could have destroyed it within minutes

Final thoughts



???

- This is one of the great turning points in history.
- The development program is eminently doable. That it works has been experimentally demonstrated. The long-vexing puzzle of the active mechanism has been solved.
- Our scientific community bitterly opposes any use of electromagnetics -- even an advanced, higher symmetry electrodynamics -- for medical treatment.
- A consortium of the scientific community, the large pharmaceuticals, FDA, and the AMA will oppose this project even while the U.S. is being destroyed wholesale.
- It can only be done in the private sector, and there will likely be no funding unless by philanthropists.

Continuation

Business plan, development program, budget breakdown, proposed schedule etc. go here.

Weapons Slides

The Tom Bearden Website

Help support the research

"Others [terrorists] are engaging even in an eco-type of terrorism whereby they can alter the climate, set off earthquakes, volcanoes remotely through the use of electromagnetic waves… So there are plenty of ingenious minds out there that are at work finding ways in which they can wreak terror upon other nations…It's real, and that's the reason why we have to intensify our [counterterrorism] efforts." *

Secretary of Defense William Cohen at an April 1997 counterterrorism conference sponsored by former Senator Sam Nunn. Quoted from DoD News Briefing, Secretary of Defense William S. Cohen, Q&A at the Conference on Terrorism, Weapons of Mass Destruction, and U.S. Strategy, University of Georgia, Athens, Apr. 28, 1997.

Slides
(covers period up to 1999)

- The Coming Strategic Attack on the United States
- Outline
- Loss of two separate A-10 Warthogs in 1997
- Typical ABM Defenses (Widely Deployed by mid-70s)

- Launch Phase Anti-Missile System
- Launch Phase Anti-Bomber System
- HC-130s Engines Quit, Aircraft Crashes
  Nov. 22, 1996
- 1996 Actions by this analyst
- Additional Information Exists: Not Analyzed, Not Integrated in Briefing
- Kill of Arrow DC-8, Gander AFB, Dec. 12, 1985
- Satellite Photos of Plumes in Soviet Arctic Since 1974
  See "Fer de Lance" for additional information
- Aum Shinrikyo ("Supreme Truth" Cult), Shoko Asahara, Leader

  Aum Shinrikyo - Anatomy of a Dangerous Cult
- Ashkhabad Problem and Its Solution
- Strange Characteristics of Iran Quake, Sep. 1978
- Iran Earthquake, September 1978
- Situation Now (Assessment)
- Situation Now (Assessment 2)
- Aspects of Strong Local Asymmetry
- Mass Casualty Problem: Aerial Anthrax

Spray on Washington, D.C.

- Present Status of the WMD Threat to the United States
- Some Present Problems in the U.S. WMD Defense Capabilities
- Internal Terrorist Threat with Weapons of Mass Destruction: Now & Future
- Attempt to Ban Energetics Weapons Worldwide
- Brezhnev's Schedule
- Large glowing Tesla globe witnessed in Red China by hundreds
- Cold Explosion -- 9 April 1984 Near Kurils, and formation and growth of spherical shell (globe)
  Sequence of Events
- Cold Explosion -- 9 April 1984 Near Kurils, and formation and growth of spherical shell (globe)
  What They Were
- Cold Explosion -- 9 April 1984 Near Kurils (Plus additional weapons effects)
- Countering Insane MAD Systems:
  Find Loophole, Exploit It
- Next Generation Counter to Both Sane and Insane MAD systems
- Simultaneous Dudding of Nuclear Weapons Worldwide

- Simultaneous Dudding of Nuclear Weapons Worldwide
- Operation Divine Wind II
- Advanced EMBW Applications
- EM Biological Warfare (EMBW)
- Microwave Radiation of U.S. Embassy in Moscow
- Pentagon EMI Studies, 1989
- EM Missile Practice (6 slides)
- Subdivisions of Soviet Energetics Program
- Communism's Goal
- Manuilsky's Goal vs. Status Today (Dec. 1996)
- Professor Hellman, German Scientist Released from Work in Soviet Union
- Hemispheres and Globes of Light (4 slides)
- How Could Such Superweapons Ever Be Concealed?
- Soviets Easily Concealed These Superweapons for Four Decades
- Microscope-type, laser-like interferometer for inducing quick α-decay in samples of otherwise longer-lived isotopes
- Longitudinal Wave Interferometry: Endothermic

- Longitudinal Wave Interferometry: Exothermic
- U.S. Air Attack on Libya, April 1986
- Lightning Wall
  circa 1959-1960
- Lisitsyn's Report: Brain Code Broken
- Large Longitudinal Wave Interferometer (LWI) Accident
- Large Longitudinal Wave Interferometer (LWI) Accident
- Use of Hidden Information Content of the Field Can Provide Action-At-A-Distance
- Two Types of Mutual Assured Destruction (MAD) System
- Psychoenergetics Weapons Teams Mentally Disable All Personnel
- Strikes Against Special Ship and Energetics Weapons Sites
- "Mindsnapper" Attack on Special Ships and Energetics Weapons Sites
- How Much Off Guard Are We?
  (7 Slides)
- Possible Targets: 1995-9 Escalation Phase
- Propagation of Weapon Effects
- Yugoslav Earthquake, Followed by Cold Explosion
  April 15th, 1979

- Countering an Insane QP Weapon
- Gulf War Disease: KGB QP Weapon Induced ST Curvature Engines for a Cocktail of Diseases
- Self-Targeting in Inner EM Channel Can Produce a Quantum Potential
- Mechanism for Producing a Quantum Potential
- Major Principles for Use of Quantum Potential Weapons
- Major Principles for Use of Quantum Potential Weapons (2)
- Instantaneous Communication by a Quantum Potential
- Participants in a quantum potential share a common multiply-connected spacetime (MCST)
- Quake in Tangshan, China
  28 July, 1976
- Exchanging Earthquakes
- Instant Communication by a Quantum Potential
- Westerners Do Not React to Slow Threats
- Characterizing a Given Risk or Risk Factor
- Technical Risk Management
- Aum Shinrikyo's Sarin Facility

- In Scalar Beam Interference Zone
- Physicist Schappeller Auralaz Munster, Austria
- Initial Soviet Plan for Cold War, After WWII
- Josef Stalin: Absolute Dictator
- Exploding any Resistance by Operational Scientists
- Significant Soviet Statements
- Captain Svoboda Dives Headlong to Her Death
- T-polarized Beam Projector
- Possible Tests (1)
- Possible Tests (2)
- Possible Tests (3)
- Possible Tests (4)
- Mushroom Cloud Rising From Sea
- Launches from Cape Canaveral and Vandenberg AFB Provided Practice Targets of Opportunity
- The sinking U.S.S. Thresher, with her controls jammed, implodes when she reaches crush depth
- Embodiment of an instrument array sufficient to discriminate when time-density charging has occurred, and that transduction

of time-charge decay has occurred.

- Time-Polarized EM Wave Interferometer Creating Space-Time Curvature Engines in a Distant Interference Zone
- Transmutation of Radioactive Nuclei at a Distance
- Transmutation of Radioactive Nuclei
- Typical Tesla Shield, Northern Route of Japan
- A Curious Tide in Human Affairs
- Large Scalar EM Interferometer (LASI) Accident Near Urals, 1958
- The Superpower Paradox: Asymmetric Cheap WMD Strategic Strike and Destruction
- The KGB/Yakuza-Aum War Plan
- Why Western Science is Ignorant of KGB Energetics
- Transmutation of Radioactive Nuclei at a Distance
- TheYakuza
- Yugoslav Earthquake, Followed by Cold Explosion
  April 15, 1979

---

* Note that the Secretary did not speak the words in square blocks; these were added by the writers later,

probably to "soften the tone" of the Secretary's information release. So the Secretary confirmed that some nations of the world -- not just some ragged terrorists, as the writers tried to imply for spin control -- do possess novel electromagnetic weapons and are using them to induce earthquakes, engineer the weather and climate, and trigger volcanic eruptions.

THE COMING STRATEGIC ATTACK ON THE UNITED STATES

By an AUM/Yakuza/KGB/Communist Coalition Using Energetics SuperWeapons

T.E. Bearden, LTC
U.S. Army (Retired)
M.S. Nuclear Eng.
Fellow Emeritus, AIAS

With Technical Background and History of Energetics Weapons

Partial support by the Association of Distinguished American Scientists is gratefully acknowledged.d

© 1995, 1996, 1999 T.E. BEARDEN



Outline

- Background: Classical Electromagnetics (and Defects)
- Background: Energetics (Scalar Electromagnetics)
- Background: Soviet Energetics Weapon Development
- KGB/Communist Plans
- Countering of Soviet/KGB/Communist Plan in Mid-80s
- Soviet Economic Collapse and Adaptation of Plan
- Weapons Bleed-Out: KGB/Russian Mafia
- Yakuza: The Japanese Mafia
- Aum Shinri Kyo (Supreme Truth) Cult
- Coalition: Aum/Yakuza/KGB/Communists/Russian Mafia
- Operation Divine Wind II: Three Phases
  - Phase I: On-Site Training Phase (Completed)
  - Phase II: Escalation Phase (In Progress)
  - Phase III: 1997 Strategic Strike on the United States
  - Support Plan A: Feints, Deception, Sabotage & Terrorism
  - Support Plan B: Test Range
  - Support Plan C: Worldwide Weather Engineering
  - Support Plan D: Strategic and Combat Intelligence
- Special Information
- Recommended Actions

© 1996, 1996 T.E. BEARDEN

The Tom Bearden Website

Help support the research

Loss of two separate A-10 Warthogs in 1997

- A-10 Mysterious Flyaway and Crash - April 2, 1997
- Death of Second A-10 Pilot - May 27, 1997
- Captain Button's Mysterious Flyaway and Eventual Crash
- Death of Second A-10 Pilot - May 27, 1997



A-10 Mysterious Flyaway and Crash

April 2, 1997

UTAH
COLO.
Area enlarged
1:40 p.m.
Vail
Denver
70
1:22 p.m.
Aspden
1:05 p.m.
Telluride
Pueblo
12:53 p.m.
Cortez
ARIZONA
11:58 a.m. Breaks Formation near Goldwater Range
12:20 p.m.
Young
NEW MEX.
Phoenix
Lake Roosevelt
10
12:11 p.m.
Apache Junction
8
Barry M. Goldwater Air Force Range
DEPARTS
10:30 a.m.
Tucson
Tombstone
0
100
Miles
N
Eagle
Edwards
Vlail
70
COLO.
Glenwood Springs
Salford
New York Mountain
Hardscrabble Range
82
Sawatch Range
24
Flight path
Aspden
0
5
Miles
N
Leadville

Armed with:

- Four 500-lb bombs
- 30 mm Gatling gun



Death of 2nd A-10 Pilot May 27, 1997

- Captain Amy Svobody
- Night training mission
- From Davis-Montham AFB
- From same wing as Captain Button, who flew his A-10 off course for over an hour and then crashed on April 2.
- Climbout from ordnance delivery on target
- Nosed down sharply and dived into ground

Companion A-10's

- Experienced night flyer & instructor
- Nosed sharply over and flew into ground
- Psychoenergetic kill

© T.E. BEARDEN 1999

Psychoenergetic weapon induced instant hypnogogic state and reversed Svoboda's sense of up and down.

A-10 Mysterious Flyaway and Crash

April 2, 1997

Armed with:

- Four 500-lb bombs
- 30 mm Gatling gun


UTAH
COLO.
Area enlarged
1:40 p.m. Vail
1:22 p.m. Aspden
1:05 p.m. Telluride
12:53 p.m. Cortez
ARIZONA
11:58 a.m. Breaks Formation near Goldwater Range
12:20 p.m. Young
NEW MEX
12:11 p.m. Apache Junction
Barry M. Goldwater Air Force Range
DEPARTS
10:30 a.m.. Tucson
Tombstone
Eagle
Vail
Glenwood Springs
COLO.
Hardscrabble Range
New York Mountain
Sawatch Range
Flight path
Aspden

Figure 14a. Captain Button's mysterious flyaway and eventual crash.



Death of 2nd A-10 Pilot May 27, 1997

- Purpose: Stimulate U.S. in same area again
- Determine if U.S. aware of psychoenergetics
- U.S. showed it is completely unaware

- **Captain Amy Svoboda**
- **Night training mission**
- **From Davis-Montham AFB**
- **From same wing as Captain Button, who flew his A-10 off course for over an hour and then crashed on April 2.**
- **Almost certainly a second psychoenergetics strike**

- Experienced night flyer & instructor
- Nosed over and flew into ground
- Probable kill using psychoenergetics

Psychoenergetic strike induced an instant hypnogogic state, shifted pilot's sense of up and down. Svoboda corrected and "climbed out" after target attack, and flew into ground, dream-perceiving down was up.

© T.E. BEARDEN 1997


Typical ABM Defenses
(WIDELY DEPLOYED BY MID-70's)
GLOBAL SHELL (MIDCOURSE ELECTRONICS DUDDING)
INTENSE ENERGY SHELLS (Destruction of vehicle) (Initiation of nuclear warheads)
© T.E. BEARDEN 1999
EM MISSILES
EARTH'S SURFACE
ENERGETICS HOWITZER
TRACK
(NESTED) HEMISPHERICAL SHELL(S) (Dudding, initiation, destruction)
LAUNCH PHASE DEFENSES
TERMINAL DEFENSES



LAUNCH PHASE ANTIMISSILE SYSTEM

IONOSPHERE

PHASE
CONJUGATE
REPLICA
(MAY BE HIGHLY
AMPLIFIED)

NORMAL
RADAR
RETURN

EARTH'S SURFACE

STRATEGIC
BALLISTIC
MISSILE
AT IGNITION

GIANT
ENERGETICS
TRANSMITTER
RECEIVER
SYSTEM

SOME OPERATIONAL MODES:

- SIMPLE TRACKING
- PHASE CONJUGATE TRACKING
- ENGINE COMBUSTION COOLING
- EMP INSERTION
- ELECTROMAGNETIC MISSILE STRIKE
- ELECTRICAL INTERFERENCE
- METAL LATTICE SOFTENING
- ANTI-WARHEAD
- GLOBAL SHELL
- HEMISPHERICAL SHELL
- MULTIPLE SIMULTANEOUS TARGETS
- MULTIPLE SIMULTANEOUS MODES

© T.E. BEARDEN 1996



LAUNCH PHASE ANTI-BOMBER SYSTEM

IONOSPHERE
PHASE CONJUGATE REPLICA (MAY BE HIGHLY AMPLIFIED)
EARTH'S SURFACE
NORMAL RADAR RETURN
STRATEGIC BOMBER OR OTHER A/C TAXIING, OR TAKING OFF
GIANT ENERGETICS TRANSMITTER RECEIVER SYSTEM

SOME OPERATIONAL MODES:

- SIMPLE TRACKING
- PHASE CONJUGATE TRACKING
- ENGINE COMBUSTION COOLING
- EMP INSERTION
- ELECTROMAGNETIC MISSILE STRIKE
- ELECTRICAL INTERFERENCE
- METAL LATTICE SOFTENING
- ANTI-PERSONNEL
- ANTI-ORDNANCE
- GLOBAL SHELL
- HEMISPHERICAL SHELL
- MULTIPLE SIMULTANEOUS TARGETS
- MULTIPLE SIMULTANEOUS MODES

© T.E. BEARDEN 1996



HC-130's ENGINES QUIT, AIRCRAFT CRASHES

At 4 miles altitude,
all four engines quit,
one after the other

Routine night training mission
80 miles off Calif Coast
Crew of 10 and 1 passenger
1 survivor

Compare to China Airlines Flight 006, 19 Feb. 1985 off San Francisco, bound from Taipei to Los Angeles

Nov. 22, 1996

(c) T.E. BEARDEN 1997

PROBABLE ENDOTHERMIC SUPERPOTENTIAL INTERFEROMETRY
(Apparently all 4 engines have never before failed on an HC-130)



CTEC PROPRIETARY

1996 Actions by this analyst

- In July 1996, with the kill of TWA-800 it became apparent that the KGB/Communists were preparing a massive strategic energetics attack upon the U.S.

© T.E. BEARDEN 1997

- Began intensive, nearly round-the-clock effort to uncover what was happening, and what had occurred in KGB/Com weapons since 1991
- Began preparing full-up set of briefing slides simultaneously
  - In early 1996, had briefed J6 on scalar EM, per his request
  - Had strongly suggested a follow-on weapons brief
  - Adamant opposition by NRL, NOL, others
- Similar energetics attack scenario in 1986 was countered. Soviets at that time did not possess operational QP weapons, and so could not successfully overcome dead-man fuzing
  - Also could not dud nukes worldwide, because QP required.
  - First lab prototype QP test was in April 1986
- KGB had solved the dead-man fuzing problem by QP's. Deployed circa 1989-1990. Some earlier weapons then leased.



Additional Information Exists; Not Analyzed, Not Integrated in Briefing

- Yakuza arranged involvement of
  - Red Chinese
  - North Koreans
  - A Taiwanese element
- Aum Shinrikyo may have been used as "Red Herring" to deceive West
- Oriental faction plots to strike Russians after the successful first strike on West
- KGB/Russians aware, will counter
  - Plan pre-emptive strike against Oriental faction first
  - Have reserved most advanced, powerful energetics weapons for that purpose

© 1999 T.E. BEARDEN

The Tom Bearden Website

Help support the research

Kill of Arrow DC-8, Gander AFB, Dec. 12, 1985

- Slide 1
- Slide 2
- Slide 3
- Slide 4
- Slide 5
- Slide 6



KILL of ARROW DC-8

Gander AFB, Dec. 12, 1985

- Soviet EM missile weapon strike practice two weeks earlier at Cape Canaveral
  - Offset from night shuttle launch
  - EM missile photographed by Bob Gladwin
  - Associated marker beacon photographed
- Canadian Board split on findings
  - Half thought icing, half disagreed intensely
  - "Due to icing" approved with half absent
  - Separate dissenting finding issued
- U.S. officials hiding Iran/Contra affair
  - Feared terrorist bomb, MidEast sponsor
  - Pressured Board, Gen. Off. bulldozed site
- Lack of icing on aircraft later validated



KILL of ARROW DC-8
Gander AFB, Dec. 12, 1985

- Eyewitness observed beams form in the sky
- Saw streak-down and strike of EM missile
  - Struck right fuselage ahead of the engines
  - Hole was burned through fuselage there
  - Photo of hole published in AW&ST
  - No explosive residues on hole
- Consistent with ignition and outgassing of plastics in forward cabin
- Consistent with pre-crash HCN deaths



KILL of ARROW DC-8
Gander AFB, Dec. 12, 1985

- Combustion cooling reduced thrust during runup
- Emulated reducing specific thrust by icing
- Struck with EM missile, at liftoff
    - Hole in right fuselage, ahead of engines
    - Not normal explosion; no material ingested
    - EM missile explosively ignited plastics in forward cabin; outgassed poisonous HCN
    - *Autopsies: Half the passengers died from HCN inhalation before plane crashed*
    - Data recorders recorded vertical spike of hit
- Materials handlers later mysteriously sickened, with symptoms of longitudinal EM radation induced illness



KILL of ARROW DC-8
Gander AFB, Dec. 12, 1985

- Combustion cooling reduced thrust during runup
- Emulated reducing specific thrust by icing
- Struck with EM missile, at liftoff
  - Hole in right fuselage, ahead of engines
  - Not normal explosion; no material ingested
  - EM missile explosively ignited plastics in forward cabin; outgassed poisonous HCN
  - *Autopsies: Half the passengers died from HCN inhalation*
    before plane crashed
  - Data recorders recorded vertical spike of hit
- Materials handlers later mysteriously sickened, with symptoms of scalar-EM radiation induced illness
- *Eye witness observed formation and strike of the electromagnetic missile*



KILL of ARROW DC-8
Gander AFB, Dec. 12, 1985

- Soviet EM missile weapon strike practice two weeks earlier at Cape Canaveral
  - Offset from night shuttle launch
  - EM missile photographed by Bob Gladwin
  - Associated marker beacon photographed by George Suchary
- Canadian Board split on findings
  - Half thought icing, half disagreed intensely
  - "Due to icing" approved with half absent
  - Separate dissenting finding issued
- U.S. officials hiding Iran/Contra affair
  - Feared terrorist bomb, MidEast sponsor
  - Pressured Board, Gen. Off. had site bulldozed
- Lack of icing on aircraft later validated


Death of the Arrow DC-8
Dec. 12, 1985
Gander, Newfoundland
ENGINE THRUST
IS REDUCING
AIRCRAFT GLOWING
(THRUST REDUCED)
FUEL
EXPLOSION
KINDLING
(SELF-TARGETING)
EM MSL STRIKE
(MULTIPLE
INSTRUMENT
SPIKES)
CYANIDE
INHALATION
TAIL-DOWN
CRASH
ELECTROSTATIC
COOLING OF
ENGINE
COMBUSTION
EXPLOSIVE
PLASTICS
IGNITION, FIRE,
OUTGASSING
ABOUT ONE-HALF
THE OCCUPANTS DIE
GRAVITON RADIATION DECAY
(EXPOSURE OF RECOVERY
PERSONNEL TO LONGITUDINAL
EM WAVE RADIATION
GRAVITON CHARGING
OF ATOMIC NUCLEI
HIGHLY CHARGED PULSE
INTO ATOMIC NUCLEI



Satellite Photos of Plumes in Soviet Arctic Since 1974*

- Two aircraft flew through for analysis
  - Solid material, mostly ice, a little clay
  - Much colder than surrounding air
  - *Signature of cold exhaust from exothermic scalar interferometry operations*
  - No volcanic material
  - No radioactive material
- May be 2 to 3 times as many incidents
  - Only examined satellite imagery in winter
  - Only periodic satellite coverage
  - Hypothesized methane venting, cloud seeding

© 1996 T.E. BEARDEN

*As of 1989, when this information was gathered

AUM SHINRIKYO

("SUPREME TRUTH" CULT)

Shoko Asahara, Leader

© 1995, 1998 T.E. BEARDEN



Ashkhabad Problem and Its Solution

- ***PROBLEM:***
  - Stress increasing in two-plate fault zone
  - 1,000 shocks yearly
  - Kara Kum canal
  - Hydraulic pressure
  - 1948: Ashkhabad 80% destroyed by quake
- ***SOLUTION:***
  - Stress-relieve plate stresses from fault
- ***IMPLEMENTATION:***
  - Induce nearby earthquake
  - Deceive by *predicting* a quake, setting off nuclear explosion

© 1996 T.E. BEARDEN



Strange Characteristics of Iran Quake, Sep. 1978

© 1996 T.E. BEARDEN

- **Signatures**
  - 7.4 on Richter scale
  - No aftershocks: 6.0 expected (normal)
  - Strange epicenter
  - Anomalous depth
- **Deception**
  - 10 MT Soviet nuclear explosion 36 hours before the quake
  - Prior disinformation regarding Soviet attempted development of focusing shock waves from underground nuclear explosions, to cause distant earthquakes



Iran Earthquake Sept. 1978

- Killed 25,000 Iranians
- Soviet city of Ashkhabad saved
- Soviets "predicted" quake in advance; then induced it
- Quake had serious anomalies (signatures)
- Deception measures were used by Soviets
  - Prediction in advance
  - "Theory" of quake-induction by nuclear explosions
  - Fired underground nuclear explosion as "Red Herring" candidate for cause

© 1996 T E BEARDEN



Situation Now (Assessment)

- In May 1997: second A-10 pilot (lady), in pullup from night ordnance delivery on target, was struck with psychoenergetic weapon takeover. Sense of vertical was reversed. She perceived herself diving, sharply corrected, and dove headlong into the ground.
- Additional aircraft kills uncovered, including one 4-engine aircraft whose engines all failed. This closely repeats the earlier 1985-1987 scenario.
- Korean Airlines Flight 801 crashed on Guam on anniversary of loading of the atomic bomb that was dropped on Hiroshima in WW II. The Enola Gay, which dropped the bomb, took off from Guam in wee morning hours of August 6, 1945. The local opns order on Guam was also issued on Aug. 5.
- *Presently the Coalition (KGB/Communists/Aum Shinrikyo/Yakuza) is waiting for proper time to launch the final strike. It is still on.*



Situation Now (Assessment 2)

- April 97: Mind control test against Captain Button:
  - Demonstrates ability to control crewman in complex operations for more than one hour.
  - KGB requires one hour total QP crew control on a site to have crew disable insane QP wpns.
- Once QP systems disabled, Mindsnapper attacks and instantly kills every living thing in QP site area. Contaminates area for months (emits longitudinal EM wave radiation, which disrupt any life forms attempting to enter struck area). Sites nullified.
- Mind control over one crewman requires one weapon system plus up to 20-30 operators for controlling thoughts, hearing, perceptions, etc.
- *In Apr. 97, KGB building and deploying weapons and training crews. Ready for new attack 1999-2000.*



Aspects of Strong Local Asymmetry

- If local asymmetry is strong, conservation laws may be appreciably violated
  - Energy
  - Charge
  - Spin
  - Momentum
  - Angular momentum
- **Properties of an object may differ appreciably for**
  - Different observers
  - Different detecting means
  - One time to another
  - One position to another

© T. E. Bearden 1995, 1996



Mass Casualty Problem: Aerial Anthrax Spray on Washington, D.C.

- **One terrorist, one light aircraft with spray tank**
- **One kilogram of anthrax**
- **Flies over greater metropolitan Washington, D.C.**
- **Calm night**
- ***1-3 million casualties result****
- ***Most of those stricken will die***
- **Presently little can be done to save the stricken civilians**
- ***Attacks on several population centers might produce some 10 million or more casualties***

© [illegible] T.E. BEARDEN

*Per OTA Report to Congress, 1993



Present Status of the WMD Threat to the United States

- Many foreign nations are hostile to the U.S. and sponsor terrorists
- Some 25 nations have WMD or are acquiring them
  - BW agents and weapons
  - Chemical agents and weapons
  - Nuclear materials and weapons
- Thousands of students and émigrés
- Infiltrated teams, BW, other WMD already
- Castro guerrillas infiltrated over the years
- Can do unacceptable damage to U.S. now
- *May reach first strike knockout capability*

© [illegible] T.E. BEARDEN

*Per OTA Report to Congress, 1993



Some Present Problems in the U.S. WMD Defense Capabilities

- *No shelters (require overpressure, BW filtering, masks, showers, supplies)*
- *No stockpiled vaccines, medical supplies, immunoglobulins, masks, suits, food, fuel, generators, heaters, water purification units*
- Totally insufficient medical facilities, personnel, and emergency response teams
- Triage, full martial law will be required
- *No answer to massive decontamination problem*
- State, county, city inadequately staffed and insufficiently trained for mass casualties
- Terrorist teams, BW agents, other WMD on site, waiting
- Water supplies, food, crops, farm animals also vulnerable
- Electric power grid, bridges, trains, railroads vulnerable
- *Present medical science cannot save very many of the casualties, now or in the foreseeable future*

© [illegible] T. E. BEARDEN



Internal Terrorist Threat with Weapons of Mass Destruction: Now & Future

TODAY:

- Sabotage
- Chemicals
- Biological agents
- Nuclear materials
- Powerful explosives
- Assassination
- Kidnapping and hostages
- Contamination
- Shoulder-fired AD missiles
- Terrorism

FUTURE ADDITIONS:

- Orthodox EM weapons
- Energetics EM biological warfare
- Scalar EM (energetics) weapons
- Scalar EM disease induction
- Alteration of behavior and emotions
- Alteration of memory
- Direct control of thoughts, perception
- Quantum potential weapons
- Psychoenergetics weapons
- Action-at-a-distance effects

© [illegible] T. E. BEARDEN



Attempt to Ban Energetics Weapons Worldwide

- On June 13, 1975, in a major speech Brezhnev urged the United States to agree on a ban of research and development of new kinds of weapons "more terrible than anything the world has known."
- On July 2, 1975 Brezhnev repeated his proposed ban on development of frightful new weapons, to a group of U.S. Senators.
- In August 1975, Ponomarev called for a ban on frightful new weapons of mass destruction.
- On Sept. 23, 1975 Gromyko presented a draft treaty agreement to the 30th Session of the UN General Assembly, for banning development of frightful new weapons.
- *No one had the foggiest notion what the Russians were talking about!*

© 1996 T.E. BEARDEN



Brezhnev's Schedule

"We are achieving with detente what our predecessors have been unable to achieve with the mailed fist..
...by 1985 our power will be so irresistible that we can do what we wish anywhere on the globe."

Leonid Brezhnev,
In a secret 1973 meeting in Prague
with European Communist leaders.

"By the early 1980's we and our allies will control the high seas, space, and most of the earth's land area."

Kosygin,
to Imelda Marcos,
July 1978

In 1985-87, the Soviets did attempt to move, still constrained by nuclear dead man fuzing. That attempt was blocked, primarily by scalar EM countering demonstrations and dead man fuzing.

In April 1986, the first Soviet lab prototype of a quantum potential weapon specifically designed toward 10-min neutralization of nukes worldwide was gingerly tested against our U.S. airstrike on Libya. It was weakly tested in the "induced EMI" mode, for deception.

By 1990 that weapon was deployed and a new attack preparation phase was entered, scheduled for 1997.

© 1996 T.E. BEARDEN





COLD EXPLOSION -- 9 April 1984 Near Kurils

And Formation and growth of spherical shell (globe)

not to scale
centerline
380 miles
diameter
200 miles
expansion
© T.E. BEARDEN 1999

Sequence of Events

- Geyser of water rose rapidly from surface, mushroomed out
- Reached 60,000 feet altitude in two minutes
- Brilliantly glowing globe then appeared in top
- Globe increased greatly in size and altitude
- Reached diameter of 380 miles
- Center reached altitude of 200 miles
- Observed by multiple qualified pilots



COLD EXPLOSION -- 9 April 1984 Near Kurils

And Formation and growth of spherical shell (globe)

not to scale
centerline
380 miles diameter
200 miles
expansion
© T.E. BEARDEN 1999

What They Were

- Superpotential interferometry using LWs
- First, a cold explosion just above surface
- Then small intense shell of glowing EM energy for 1-on-1 targeting
- Larger globe for large area as for ICBM targets approaching in zone
- With ST engines, can dud incoming nukes and all electronics
- Use in or out of Earth's atmosphere



COLD EXPLOSION -- 9 April 1984 Near Kurils (Plus additional weapons effects)

Halo expanded to giant globe.
380 miles diameter, center over 200 miles high.

© T.E. BEARDEN 1996



Countering Insane Mad Systems: Find Loophole, Exploit It

- *If MADs not quantum potential systems, easily countered by instant QP strike which destroys targeted MAD weapons worldwide with certainty.*
- *Have to be certain of types of dead-man fuzing. All dead-man fuzing weapons must be included in the assured target list for the striking quantum potential weapon.*

© 1995, 1996 T.E. BEARDEN

- *Multiple targeted MADS require multiple vacuum engines in the striking quantum potentials.*
- *Uncertainty and risk introduced if not certain of all MAD systems and all dead-man fuzing systems.*
- *Newest generation psychoenergetic LW interferometry weapons can instantly take over minds of all personnel on targeted sites, with targeted crews quickly disarming their own MAD weapons' launch capability as well as the weapons themselves.*
- *Mindsnapper then kills all living things and contaminates sites.*
- *Next generation QP Psy-En weapons can disrupt and destroy minds of an entire targeted national population. The nature of warfare moves irrevocably to the human mind, where of course the fundamental problem arises anyhow.*



Next Generation Counter to Both Sane and Insane MAD Systems

- ***Localized quantum potential in an area, used in psychoenergetics mode***
  - **Gradually produces mild, continuous hypnotic state**
  - **Targeted population remains entirely conscious, functional**
  - **Internal "word thoughts" emerge directly in subconscious**
  - **Targeted persons all unaware of these "word thoughts"**
  - **Operates somewhat similar to "post hypnotic suggestion"**
  - **Gradually changes emotions, psychological outlook**
  - **Over a period of time, deviates and entrains entire target population's outlook, belief structure, temperament**
- ***Moves Psywar to inside the human component***
- ***Human minds are the only battleground***
- ***Can be accomplished without overt signature***
- ***Countered only by inserting same methodology into deeper mind level (collective unconscious)***



Simultaneous Dudding of Nuclear Weapons Worldwide

- Via quantum potential joining U235 and Plutonium in warheads
- Includes weapons airborne, underwater, in storage
- These are *transmutations of the nuclides themselves*
- *Part of the initial barrage launched by Aum/Yakuza/KGB*
- *Will occur in the first minutes of the strategic strike, following psychoenergetically crew-disabling QP weapons*

Note: Duds both overt and covert nuclear weapons and weapons-grade materials -- including "suitcase-delivered" covert weapons on site in Russia which otherwise provide dead man fuzing

© T.E. BEARDEN 1996



Simultaneous Dudding of Nuclear Weapons Worldwide

- Via quantum potential joining U235 and Plutonium warheads
- Includes weapons airborne, underwater, in storage
- These are not explosions, but are *transmutations and increased fissioning rates*
- *Part of the initial barrage launched by Aum/Yakuza/KGB*
- *Will occur in the first minutes of the strategic strike*

© T.E. BEARDEN 1996

Note: Duds both overt and covert nuclear weapons and weapons-grade materials.

The Tom Bearden Website

Help support the research

Operation Divine Wind II

Slide 1

Slide 2

Slide 3

Slide 4


YAKUZA &
AUM SHINRIKYO
U.S.
KGB
MINDSNAPPER AND
PSYCHOENERGETICS
QUANTUM
POTENTIAL

DIVINE WIND II

- ★ **A secret coalition of Yakuza/Aum Shinrikyo and KGB/Communist forces plan to launch a massive, surprise energetics attack on the United States, given a low-risk opportunity.**
- ★ **Major weapons utilized will be the scalar EM (energetics) superweapons (including quantum potential weapons) that were developed, deployed, and operated by the KGB under the former Soviet Empire, and continuing after its dissolution.**
- ★ **Yakuza/Aum crews have extensively trained and test-fired, from on-site in Russia. They have *leased* operational control of the first three generation energetics superweapons (which work by superpotential interferometry).**
- ★ ***The Escalation Phase of interdicting and destroying actual U.S. targets (e.g., TWA-800, two A-10s) is already underway.***
- ★ ***The first blow in the Strike Phase will dud all nuclear weapons and weapons materials worldwide, in minutes; destroy special ship and energetics weapon sites instantly, disable 99% of the U.S. population instantly, and kill 80% of targeted populations in from 10 minutes to 3 days.***

© 1995, 1996 T.E. BEARDEN


YAKUZA &
AUM SHINRIKYO
U.S.
KGB

DIVINE WIND II

- ★ A secret coalition of Yakuza/Aum Shinrikyo and KGB/Communist forces plans to launch a massive, surprise energetics attack on the United States and its allies, given the first low-risk opportunity.

© 1995, 1996, 1999 T.E. BEARDEN

- ★ Attack was thwarted twice in 1997 by a small nation countering with QP weapons.
- ★ KGB psychoenergetics counter for the last QP weapon counter was tested in April 1997.
- ★ Ready time for a new scheduled attack is latter quarter 1999 through first half of 2000.



YAKUZA &
AUM SHINRIKYO

U.S.

DIVINE WIND II

© 1995, 1996 T.E. BEARDEN

★ **A secret coalition of Yakuza/Aum and KGB/Communist forces will launch a massive, surprise, strategic attack on the United States in 1997.**

★ Major weapons utilized will be the scalar EM (energetics) superweapons that were developed, deployed, and operated by the KGB under the former Soviet Empire, and continuing after its dissolution.

★ Yakuza/Aum crews have extensively trained and test-fired, from on-site in Russia. They have *leased* operational control of the energetics superweapons.

★ *Escalation Phase of interdicting and destroying actual U.S. targets (e.g., TWA-800) is already underway.*

★ *The first blow in the Strike Phase will dud all nuclear weapons and weapons materials worldwide, in minutes; destroy special ship and energetics weapon sites instantly, and kill 80% of targeted populations in 3 days.*

KGB/COMMUNISTS

MINDSNAPPER

QUANTUM
POTENTIAL



OPERATION DIVINE WIND II

Three Phases and Support

Operational Phases

- Phase I: On-Site Training Phase (Completed)
- Phase II: Escalation Phase (In Progress)
- Phase III. 1997 Strategic Strike on the U.S.
  - *First strike (QP) in Phase III duds all nuclear weapons and nuclear powerplants worldwide, in minutes*
  - *Psychoenergetic strike (QP) disables people instantly*
  - *Mindsnapper attack of special assets for 100% success*
  - *QP initiation of fast-acting, lethal diseases kills 80% of targeted populations in three days or less*

Support Plans

- Plan A: Feints, Deception, Sabotage, and Terrorism
- Plan B: Testing and Test Range
- Plan C: Worldwide Weather Engineering
- Plan D: Strategic and Combat Intelligence

© 1995, 1996 T.E. BEARDEN



Advanced EMBW Applications

- Covert EMBW: Examples
  - Activate materials and their potentials with ST disease engines. Potentials superpose and their infolded ST dynamics diffuse
  - Activate water's structuring (H-bonding) potential with disease engines
  - Bias electrical power grid ground fields by weak diseases
  - Employ disease-structured quantum potential in distant area
- Overt death ray (mind snapper)
  - Powerful scalar EM pulse in target area "jerks" rate of flow of time
  - The "time snap" sharply separates mind from body and each cell
- EMBW CM:
  - Irradiate bodies with longitudinal EM waves; self-converts to t-pumping and produces exact amplified ST antiengine
  - Antiengine arises out of local ST, affects all parts of all cells
  - Cells are t-charged with antiengine structure
  - Continuing action restores regenerative and immune systems and reverses cellular damage

© T.E. BEARDEN 1995, 1999



EM Biological Warfare (EMBW)

- KGB/Communists have developed highly effective
  - Electromagnetic biological warfare (EMBW)
  - Counters to orthodox biological warfare
  - Mass death ray weapons
    - Small version of "mindsnapper" tested in Afghanistan
    - Killed occupants in two villages, in separate strikes
    - Unusual aspects (so-called "smerch" gas)
- Russia/KGB is the only group with a complete counter to biological warfare, either covert or overt, and to EMBW
- EMBW (covert and overt) is a preferred option for KGB
  - MAD Doctrine is completely destabilized for a sufficiently covert Russian EMBW strike
  - Situation has existed for at least two decades
  - Can alter germs, bacteria, viruses of specific kind, in a specific target area, to produce antibiotic-resistant strains
  - Can induce any kind of cellular disease or damage at a distance
- U.S. national characteristic: no reaction to slowly increasing threat

© T.E. BEARDEN 1999



Microwave Radiation of U.S. Embassy in Moscow

Former U.S. Embassy in Moscow.

BACKGROUND

- Began in latter 1950s
- Discovered on VP Nixon's trip
- Initially thought to be *nuclear* radiation (Discovered w/Geiger counter?)
- High level target -- U.S. Ambassador
- Guarantees personal attention of:
  - U.S. Ambassador to USSR
  - U.S. President
  - NSA, CIA, DIA, NSC, etc.
  - Top consulting scientists
  - Leading U.S. scientific institutions
- Two U.S. Ambassadors died, another sickened
- Anomalous health changes in personnel, only in zero-field (zero pot'l gradient) areas!
- Four U.S. Presidents requested Soviets cease
  - Cut from 18 watts/sq cm to 2
  - Then again increased
- No one could understand what was going on
- Aluminum screens were placed over windows
- Moscow was declared a hazardous duty zone

© 1995, 1996 T.E. BEARDEN



Pentagon EMI Studies, 1989

Washington Post, 22 Jan. 1989, p. A4

- Analysts of severe EMI effects in strike on Libya, 1986
  - performed major 3-year, 66-man study
  - Blamed effects on U.S. forces' own signals
  - Did not know of any other "signals" present
  - Knew nothing of quantum potential weaponry, energetics weaponry
- 7-month preliminary study
  - Severe EMI Problem exists
  - EMI shielding often waived in our weapon systems
  - Thousands of conflicts possible
- Also studied UH60 Blackhawk helicopter problems (which *were* due to its lack of good EMI shielding, and not quantum potentials)
  - uncommanded turns
  - Five EMI crashes 1982-1989
  - $175 M program to shield it
- So found that U.S. transmission combinations can
  - Affect aircraft flight control
  - Turn off fuel supply
  - Cause uncommanded dive/turn
  - Bring down U.S. warplanes
- *Actually, Libyan EMI was induced by Soviet quantum potential tests which can do all those things and much more*

© 1996 T.E. BEARDEN

The Tom Bearden Website

Help support the research

EM Missile Practice

- EM Missile Practice
  Latter Sept. - Early Nov. 1996
  Melbourne, Australia

- Deception: Using EM Missile to Reinforce Notion of SAM Attack
  Saturday evening, Nov. 16, 1996

- Intelligence Probe: Insuring U.S. Still Unaware of Energetics Weaponry
  Thursday, December 12th, 1996

- EM Missile Strike, Offset from Night Shuttle Launch, Cape Canaveral, Florida
  The Smoking Gun in November 1985

- Distant Operator Onsite in Russia Slew Away Registration Point
  Marker Beacon over Night Shuttle Launch, 26 November, 1985

- EM Missile Practice and Deception
  November 17, 1996



EM Missile Practice
Latter Sept.-Early Nov. 1996

(Multiple Nights, Multiple Streaks Each)

(Many Witnesses)

© 1996 T.E. BEARDEN

~ 500 meters (one case)

Melbourne, Australia
Australian Associated Press
Nov. 2, 1996



Deception: Using EM Missile to Reinforce Notion of SAM Attack

Saturday Evening
Nov. 16, 1996

Note: Meteor shower was forecast, which provided perfect decoy to FBI investigators, to steer them off the true scent.

Pakistan International Airlines Flight 712, just after takeoff from John F. Kennedy Airport, on path similar to that taken by TWA Flight 800, July 17, 1996

© T.E. BEARDEN 1996



Intelligence Probe: Insuring U.S. Still Unaware of Energetics Weaponry

Thursday
Dec. 12, 1996

Pilot sighted what he called
a "green flare".
No danger, no evasive action.

Saudi Arabian Airlines 747
en route from Riyadh, Saudi Arabia
to John F. Kennedy Airport.
At 12,000 ft., not far from where
TWA Flight 800 was killed on July 17, 1996

FBI: *"Probably a meteorite."*

© T.E. BEARDEN 1996



EM Missile Strike, Offset from Night Shuttle Launch

Cape Canaveral, Florida

EM MISSILE STRIKE
26 NOV 1985
(LIGHT DEVELOPMENT)
OFFSET FROM NIGHT SHUTTLE LAUNCH

PHOTO BY BOB GLADWIN

MARKER BEACON
Over Night Shuttle Launch
Cape Canaveral, Florida

26 Nov 1985
Photographed by George Suchary

© T.E. BEARDEN 1996, 1999,

EM MISSILE STRIKE
26 NOV 1985

(DARK DEVELOPMENT)

OFFSET FROM NIGHT SHUTTLE LAUNCH

The Smoking Gun in Nov. 1985



Distant Operator Onsite in Russia Slews Away Registration Point

© T.E. BEARDEN 1995, 1999.

MARKER BEACON

Over Night Shuttle Launch
Cape Canaveral, Florida

26 Nov 1985
Photographed by George Suchary

28 Nov 1985

Two weeks later, the same weapon killed the Arrow DC-8 at its takeoff from Gander, Newfoundland.



EM MISSILE PRACTICE AND DECEPTION

Nov. 17, 1996 at 2220 hrs.

Note: 4-month
anniversary
of kill of TWA-800.
"Inside gloating" by
Aum/Yakuza/KGB.

Vicinity of Long Island, New York
Not far from where TWA-800 was killed
Two aircraft sighted object

© 1996 T.E. BEARDEN



Subdivisions of Soviet Energetics

NONLIVING SYSTEMS

Energetics

- Nonliving systems
- Scalar Interferometry
- Action-at-a-Distance
- Quantum Potential
- Vacuum Engines
- Spacetime Structuring
- Material, Field Effects
- Nuclei, Lattice Changes
- Hidden EM Variables
- SWZ Effects

LIVING SYSTEMS

Bioenergetics

- Living Systems (Bodies)
- Cells, cellular changes
- Master Cell Control (Popp)
- Spacetime Structuring
- Disease Induction, Remission
- Action-at-a-Distance
- Quantum Potentials
- Scalar Interferometry
- Hidden EM Variables
- SWZ Effects

Psychoenergetics

- Living Systems (Minds)
- Thoughts, Memories, Emotions
- Conscious/Unconscious Minds
- Spacetime Structuring
- Species, Biospheric Minds
- Action-at-a-Distance
- Quantum Potentials
- Scalar Interferometry
- Hidden EM Variables
- SWZ Effects

© 1996 T.E. BEARDEN



Communism's Goal

- "War to the hilt between communism and capitalism is inevitable. Today, of course, we are not strong enough to attack... To win we shall need the element of surprise. The bourgeoisie will have to be put to sleep. So we shall begin by launching the most spectacular peace movements on record. There will be electrifying overtures and unheard-of concessions. The capitalist countries, stupid and decadent, will rejoice to cooperate in their own destruction. They will leap at another chance to be friends. As soon as their guard is down, we shall smash them with our clenched fist."

Dimitry Z. Manuilsky
Lenin School of Political Warfare, Moscow
(circa 1934)

© 1996 T.E. BEARDEN



Manuilsky's Goal vs. Status Today

Manuilsky, 1934	Situation, Dec. 1996
War is inevitable.	Has not changed.
Not strong enough to attack now.	Strong enough now; preparations completed. Need right opportunity.
Need surprise.	Have achieved total surprise.
Must put us to sleep.	We are sound asleep.
Need most spectacular peace movement on record.	Done. We think the Russian threat gone, cold war ended.
Electrifying overtures, unheard-of concessions.	Done, and still occurring every day. It has worked beautifully.
Capitalists will cooperate.	We are cooperating in spades!
They will leap to be friends.	We've leaped, and are leaping.
They will let down their guard.	No ABM, junked lots of nukes, shrunk our forces to the bone.
We'll strike them then.	They would have struck (twice) in 1997, but for deterence by another nation (not U.S.) having QP weapons *They are still looking for a risk-free opening to strike*

© 1996, 1997 T.E. BEARDEN



Professor Hellman, German Scientist Released from Work in Soviet Union

- Worked in Soviet Union after WWII
- Eventually escaped to Germany, then to Brazil (handsome offer)

© 1996 T. E. BEARDEN

- Took part in highly unusual Soviet energetics development and experiments
- Large areas of the sea could be and were *suddenly frozen*
- *No particular attention was paid to this information by highly qualified scientists*
- *In intelligence terms, this is A-1 information of the highest caliber*
- *Bohm also was invited to Brazil, which started an energetics weapon program. Brazil developed such weapons including weak quantum potential weapons (0.95 confidence)*

The Tom Bearden Website

Help support the research

Hemispheres of Light

- March 20th, 1969
  Caribbean and Western North Atlantic
- Hemisphere and Globes, 1977
  24 March, 1977
- Virgin Islands Incident
  August 1969
- Typical Shield Test, Northern Route to Japan
  June, 1982



Expanding Hemisphere of Light

Mar. 20, 1969
Caribbean and Western
North Atlantic

- Semicircle
- Milky white light
- Small, intense at first
- Dimmed as enlarged
- Grew to enormous size
- Lasted 10 minutes, then faded

MOON
50 degrees
70 degrees
Marine Observer
40:17, 1970


Hemisphere and Globes 1977
0855 GMT, 24 Mar 1977
M.V. Kinpurnie Castle
23° 05' N; 17° 25' W
Disappeared after 10 minutes
2nd luminous patch
Moderately luminous hemisphere formed
Bright luminous patch (1° diameter)
Required 3 minutes to form
30°
For 10 sec, "searchlight" shined down
40°
© T.E. BEARDEN 1996
Marine Observer 48:21-22, 1978



1969 Virgin Islands Incident

8:15 P.M.
Thursday
Aug 1969
Seen by many residents

Faintly luminescent

Smooth, curved edge

NORTH DIRECTION

© T.E. BEARDEN 1996



Typical Shield Test, Northern Route to Japan

Asahi Evening News, Tokyo
June 22, 1982

Multiple tests seen per month, for years.
Pilots simply ceased reporting them.

© T.E. BEARDEN 1994, 1995



How Could Such Superweapons Ever Be Concealed?

- Arthur C. Clarke's law states:

  "Any sufficiently advanced technology is indistinguishable from magic."

- To U.S. scientists, "magic" means "impossible"
- Longitudinal EM waves and LW interferometers have been regarded as fantasy and impossible
- To deceive foe on rather open use of unknown technology without discovery:

  "Disguise its uses as understandable accidents, human error, acts of nature, other known technology, etc."

© T.E. BEARDEN [illegible]



Soviets Easily Concealed These Superweapons for Four Decades

- Intensive Soviet deception plan utilized
  - Embedded in other weapon system tests
  - Made to resemble natural acts, accidents, etc.
  - Open science releases coordinated to show Russian scientists worked on "normal" science
- West thought Russian scientists inferior
- U.S. scientific community was and is dogmatic, and fiercely suppresses real scientific innovation
- Terribly flawed electrodynamics not ruthlessly shaken and changed in West
- West had no basis for understanding energetics

© T.E. BEARDEN 1996, 1999


Precise spacetime curvature engine adds energy to $_2He_4$ α-particles inside atomic nuclei, causing tunneling α-decay
POWER UNIT
BEAM UNIT
BEAM TRANSMITTER
REFLECTED BEAM RECEIVER
POWER UNIT
BEAM UNIT
BEAM TRANSMITTER
REFLECTED BEAM RECEIVER
MAIN POWER UNIT
PHOTO UNIT
CONTROLLER-SWITCHER UNIT
SCANNING ANTENNA HORNS
Interference zone with spacetime curvature engines to add energy to α-particles, causing α-emission and decay
Plan View
MAIN DISPLAY UNIT (MOVABLE)
OPERATOR STATION
Elevation View

Figure 26. Microscope-type, laser-like interferometer for inducing quick α-decay in samples of otherwise longer-lived isotopes.

© T.E. BEARDEN 1998



Longitudinal EM Wave Interferometry: Endothermic

Meeting of timed pulses causes explosive cooling

COOLING IN INTERFERENCE ZONE

Ambient vacuum potential in distant interference zone

Φ_a

subspace

Bias

Heat extracted

XMTR/RCVR

XMTR/RCVR

subspace

Φ_T

Electrical ground potential of transmitter

ⓒ T.E. BEARDEN 1996

Heat emerges at transmitter/receiver

Heat emerges at transmitter/receiver



Longitudinal EM Wave Interferometry: Exothermic

Energy input to transmitter/receiver
Energy input to transmitter/receiver
XMTR/RCVR
Φ_T
XMTR/RCVR
Electrical ground potential of transmitter
subspace
subspace
Bias
Heating in interference zone
Φ_a
Ambient vacuum potential in distant interference zone

Meeting of timed pulses causes explosive heating

© T.E. BEARDEN 1999

U.S. Air Attack on Libya

April 1986

- Slide 1
- Slide 2
- "Washington Post" Article
  January 22, 1989



U.S. Airstrike on Libya
April 1986*

- 33 U.S. AIRCRAFT IN STRIKE
- MANY HIGH-POWERED TRANSMITTERS
  - *COMMUNICATIONS*
  - *JAMMERS*
  - *RADARS*
- SEVERE, UNEXPECTED "EMI" ENCOUNTERED
  - *ONE F-111 DOWNED*
  - *NUMEROUS WEAPONS WENT ASTRAY*
  - *THREE FOREIGN EMBASSIES DAMAGED*
  - *SEVEN AIRCRAFT FORCED TO ABORT*
- COMMANDERS: *"US OR THEM?"*

Mild quantum potential weapon tested against electronics in U.S. aircraft and missiles

EM energy arises from every point in spacetime inside the electronics

*Washington Post, 22 Jan. 1989, p. A4



U.S. Air Attack on Libya in April 1986

- Established QP with the electronics in our aircraft and missile
- Subtly jammedthem with spurious EMI noise and signals

Longitudinal wave interferometry into distant mirror

Longitudinal wave interferometry into distant mirror

Distant Scalar Potential Interferometer

1

© T.E. BEARDEN 1997



Lightning Wall

- Aircraft on course of 270 degrees
- Approached "solid wall of lightning" in an otherwise cloudless sky
  - From very high altitude to near the water
  - Extended north-south as far as one could see
- Radar scope clear
- *Rigged aircraft for heavy weather*
- *Plunged directly through wall*
- *Wall was very thin*

circa 1959-1960
Interview with Patrol plane commander
U.S. Navy P5 aircraft
Over Atlantic, 200 miles east of Norfolk

© T.E. BEARDEN 1996



Lisitsyn's Report: Brain Code Broken

- THEORY DEVELOPED AND FITTED
- HYSTERESIS MEMORY LOOP
- CONTROLLED EM INDUCTION
  - IMAGES
  - SENSATIONS
  - PREDETERMINED EMERGENCE
- 23 EEG BANDS
  - UP TO 8.1 X 10^{20} HZ
  - 11 INDEPENDENT CHANNELS

S.K. Lisitsyn, "New Approach to the Analysis of Electroencephalograms," DDC Report AD73005, p. 16-25.

JCS-34

© 1978, 1985, 1991 T.E. BEARDEN



Large Longitudinal EM Wave Interferometer (LWI) Accident

- 1958 nuclear explosion near Urals
  - Contaminated 1200 square kilometers
  - Signature of large LWI accident
  - Buried atomic wastes suddenly exploded
  - Region contaminated to this day
- Soviets were well along with advanced LWI prototypes and testing
  - In Jan. 1960 Khrushchev announced these forthcoming "fantastic" weapons
  - 1958 difficulties would have been resolved by 1960

© T.E. BEARDEN 1996, 1999



Large Longitudinal EM Wave Interferometer (LWI) Accident

- Expected cause of 1958 accident
  - Huge LW energy beams built up
  - Catastrophic short-out in transmitter
  - LW energy flashed over into earth and spread
  - Struck and fissioned stored nuclear wastes
- Developed new safety circuits
  - For transmitter short-out, instantly activates to hold LW beam energy and prevent flash-over
  - Similar accident happened in 1986 at Chernobyl, except private U.S. group blew that transmitter to prevent catastrophic quake in California

© T.E. BEARDEN [illegible]

(Use of Hidden Information Content of the Field)

(Can Provide Action-at-a-Distance)


ϕ_1
ϕ_2
Note:
Whittaker's 1904 paper initiated the entire field of superpotential theory.
Interference Zone
(Potential gradients)
Normal EM Energy:
May be positive, or negative, or fixed
Hidden Bidirectional EM energy flow
Hidden Bidirectional EM energy flow
Scalar Potential Beams
XMTR
XMTR
Whittaker/Ziolkowski Transmitter Arrays
(8 to 20 harmonic wavepairs each)
© T. E. Bearden 1994, 1999

Figure 5. Scalar potential interferometry (between the two sets of bidirectional longitudinal EM wavepair functions) produces all EM force fields and waves.



Two Types of Mutual Assured Destruction (MAD) Systems

- ***Sane system:***
  - Turned off or on standby
  - Wait until attacked or attack is imminent
  - Humans consider situation, make strike decision
  - Command order issued to weapons officers
  - Human finger initiates launch sequence
  - Usually requires code entry, etc. for assured launch control
- ***Insane system:***
  - Computer periodically (e.g., every 2 hours) initiates launch
  - During sequence, there is a period (say, 2 min.) where operators can enter stop order (usually coded)
  - If correct stop not entered, weapons automatically launch
  - If correct stop entered, computer resets, and after another 2 hrs, automatically reinitiates the launch sequence

© 1996, 1997 T.E. BEARDEN



Psychoenergetics Weapons Teams Mentally Disable All Personnel

(COUNTERS ALL SANE MAD SYSTEMS)
(NULLIFIES HUMAN COMPONENT OF ALL WEAPON SYSTEMS)

ELECTRICAL THOUGHT-WORDS ARISE DIRECTLY IN BRAIN, HENCE IN MIND, BYPASSING SENSOR INPUTS

Effects arise in local spacetime, simultaneously in all minds in the targeted area

INSTANT HYPNOGOGIC STATE, WITH INSERTED THOUGHT-WORDS
INSTANT HYPNOGOGIC STATE: WITH WAKING DREAM
PERCEIVED REALITY NOW CONTROLLED
TARGETED POPULACE

- Site personnel instantly hypnogogic and mentally controlled.
- Distant weapon controller teams coord crew actions
- Standdown insane weapons to maintenance standby.
- Mindsnapper then strikes, kills all personnel, and nullifies site for months.

Indicators: Two A-10 incidents 1997, LIDA device since 1950s.

© 1996 T.E. BEARDEN



Strikes Against Special Ship and Energetics Weapon Sites

- Via powerful scalar EM pulses in each targeted area, so sharp time-jerks occur
  - Mind and its operations exist in time but not in 3-space
  - Coupling interaction of mind operations to body occurs through flow of time
  - Flow or change of flow of time must be smooth, for coupling of mind to body
- *Sharp jerk in time flow snaps mind's coupling to body, instantly separates mind*
- *Instant death for every virus, bacterium, cell, insect, mammal, living creature*
- *Contaminates struck sites for months, perhaps a year*

Note: In other words, this is the part of the "preparation barrage" that attacks the enemy's response capability (i.e., his "artillery" and his "airpower") and suppresses it. The use of the "mindsnapper" weapons provides 100% assurance of success.

© T.E. BEARDEN 1996



"MINDSNAPPER" ATTACK ON SPECIAL SHIPS & ENERGETICS WEAPONS SITES

"We have a new, fantastic weapon ... so powerful that, if unrestrainedly used, it could wipe out all life on earth."

Khrushchev,
speaking to Presidium,
Jan. 1960

XMTR
XMTR
POWERFUL SCALAR EM BURSTS
POWERFUL SCALAR EM BURSTS
POWERFUL SCALAR EM BURSTS
TARGETED AREAS
SHARP TIME JERKS PRODUCE MINDSNAPS

ⓒ 1996 T.E. BEARDEN

- Minds snapped loose from bodies (every living thing)
- Struck areas completely sterilized of all life
- LWs emitted; slow decay of time-charge makes contamination persistent
- Tested twice in Afghanistan

How Much Off Guard Are We?

- Slide 1
- Slide 2
- Slide 3
- Slide 4
- Slide 5
- Slide 6
- Slide 7



How Much Off Guard Are We?

- *Legitimate U.S. forces have no energetics weapons or defenses against them*
- *No DoD general, military officer, or enlisted person reporting to the government of the United States has any:*
  - Training in energetics or energetics weapons
  - Experience in energetics or energetics weapons development and usage
  - Training in strategy, tactics, deployment, and employment of energetics weapons
  - Knowledge of energetics weapons effects and capabilities
  - Knowledge of the energetics weapons, tactics, deployment, and employment by the KGB/Russians
- *Civilian and military, scientific and intelligence, and news media personnel do not recognize energetics weapons effects happening right over their own heads*

© 1999 T.E. BEARDEN



How Much Off Guard Are We?

- Kill of U.S.S. Thresher in 1963 not recognized. Left signatures.
- 23 years of KGB weather engineering, particularly over U.S. and North America, ignored and not recognized.
- Decades of irradiation of U.S. Embassy, fatally injuring three U.S. Ambassadors, health changes in personnel shrugged off ineptly.
- Massive building of underground sites, all through former Soviet Union, lamely speculated as perhaps "ABM" system or?.
- 1985, 1986 Soviet kills of U.S. aircraft, spacecraft, personnel ignored as "accidents" by legitimate U.S. communities.
- Quantum potential strike on soldiers in Gulf war ignored.
- Quantum potential deterioration of U.S. populace's immune systems ignored.
- Exchange of earthquakes and massive retaliatory destruction of Soviet missile ammunition storage sites, 1986-1989, ignored.
- U.S. scientific and military communities adamantly refuse to rework electromagnetics, though known to be seriously flawed.
- Refuse to apply Stoney/Whittaker work to engineer hidden variables, even though present quantum mechanics also known to be wrong because it does not contain such "hidden order."
- Refuse to develop, structure, and apply Bohm's quantum potential, for instantaneous action at a distance. Russians developed it.



How Much Off Guard Are We?

- **Kill of U.S.S. Thresher in 1963**
  - Not recognized.
  - Left signatures.
- **23 years of KGB weather engineering**
  - Particularly over U.S. and North America
  - ignored and not recognized.
- **Decades of microwave irradiation of U.S. Embassy**
  - Fatally injured three U.S. Ambassadors
  - Induced health changes in personnel
  - Shrugged off ineptly.
- **Massive building of underground sites**
  - All through former Soviet Union
  - Lamely speculated as perhaps "ABM" system or?.

© [illegible] T.E. BEARDEN



How Much Off Guard Are We?

- 1985, 1986 Soviet kills of U.S. aircraft, spacecraft, personnel ignored as "accidents" by legitimate U.S. communities.
- Quantum potential strike on soldiers in Gulf war not recognized, ignored.
- Quantum potential deterioration of U.S. populace's immune systems ignored.
- Exchange of earthquakes and massive retaliatory destruction of Soviet missile ammunition storage sites, 1986-1989, ignored.



How Much Off Guard Are We?

- U.S. scientific and military communities adamantly refuse to rework electromagnetics, though known to be seriously flawed.
- Refuse to apply Stoney/Whittaker work to engineer hidden variables, even though present quantum mechanics also known to be wrong because it does not contain such "hidden order."
- Refuse to develop, internally structure, and apply Bohm's quantum potential, which gives instantaneous action at a distance and great energy amplification.
- Russians developed quantum potential weapons, which obsolete all other weapons.

© 1996 T.E. BEARDEN



JUST HOW MUCH OFF GUARD ARE WE?

Kill of
TWA-800
1996

Kill of
USS
Thresher
1963

Cold
Explosion
Off Japan
Apr 1984

Kill of
Space
Shuttle
Challenger
1986

President's
party
airplane
crash
1996

From The Huntsville (AL) Times 18 Sep 96:

"Retired Gen. Wayne Downing concluded that U.S. forces are so far superior to potential foes that opponents have turned to terrorism as the only way of challenging them."

The Times also provided the information that Defense Secretary William Perry agreed with Gen. Downing's conclusion.

3 Dead U.S.
Ambassadors
from Moscow
Embassy
Radiation

- *QP Gulf War Syndrome: 16,000 persons disabled*
- *QP jamming, U.S. air attack on Libya, 1996*

Kill of
Arrow DC-8
Gander AFB
Dec 1985



JUST HOW MUCH OFF GUARD ARE WE?`

3 Dead U.S Ambassadors, U.S. Weather Engineered 20 years

Kill of USS Thresher Nuclear Submarine Apr 1963

QP Test on U.S. Troops in Persian Gulf, 1991 (Gulf War Syndrome)

TWA-800 1996; President's C-130 crash 1996

Arrow DC-8 Gander AFB Dec 1985

Challenger 1986

Quantum Potential Jamming of Air Attack on Libya Apr 1986

Blind Euphoria to Even the Ballistic Missile Threat

- U.S. National Intelligence Estimate (NIE) released in Nov. 1996 states there is no foreseeable threat to the U.S. from "indigenous missiles" for at least 15 years.
- Clinton has claimed a program for ABM defense is too expensive, would violate ABM Treaty with former USSR.
- Soviets developed an ABM system in violation of the treaty.
- In June 96 Russia test-launched an SS-19, their 26th ICBM test in 5 years.
- *"Russia still retains and is modernizing a vast nuclear arsenal... still the only nation of earth that could destroy America in a matter of minutes. Indeed, given the weakness of the Russian Army, Russia's superpower ambitions rest more than ever on its nuclear capabilities."* *
- "For the first time since the dawn of the nuclear age, there is not a single Russian missile pointed at America's children." **

Comment: Punch a computer button and the missiles are pointed! The armed missiles are still there, ready and waiting.

Bulleted info courtesy Washington Inquirer, June 24, 1996.

* House Nat'l Security Chmn, Floyd Spence.
** Bill Clinton, State of the Union Message.

© 1996 T.E. BEARDEN



Possible Targets: 1995-9 Escalation Phase

(Based on 1985-87 test program)

Earthquakes
Missiles
Power Grids & Distribution Systems
Satellites
Ships
Shuttle Launches & Flights
JETLINERS
Radio/TV
Subs
Microwave Nets
Radars & Nets
Communications and Computer Nets
© 1996 T.E. BEARDEN



Propagation of Weapon Effects

- All conventional weapons use propagation through 3-space of matter or energy or both
  - Matter (bombs, missiles, projectiles, etc.)
  - Energy (EM force fields, sonic force fields, etc.)
  - Basically one-to-one, or one "bus" to many-on-many
  - Finite propagation velocity v: where $0 < v \leq c$
  - Time delay: Shielding and pre-strike retaliation possible
- Structured quantum potential propagates vacuum ordering (vacuum engines), instantly
  - Zero time delay (through multiply-connected spacetime)
  - No propagation "through space", no "velocity" as such
  - Easily one-to-many, without limit
  - Dramatic energy amplifier (gates, amplifies flux ordering)
  - Effects arise in local spacetime; no shielding possible
  - No range limit, since striking distance always zero
- QP weapons obsolete all other weapons

© 1988, 1995, 1996 T.E. BEARDEN



Yugoslav Earthquake, Followed by Cold Explosion

Apr. 15
1979

- Magnitude 7.2 on Richter scale
- Epicenter 33 km. deep
- More than 100 aftershocks
- At Kamenari:
  - Adriatic sea mushroomed up
  - Like atomic bomb explosion
  - Signature of a cold explosion
  - Similar to Apr. 1984 test off coast of Japan, near Kurils (see inset graphics)
- Note that April is a significant test month for the Communists (preparing official reports for May Day?)

OFF JAPAN, NEAR KURILS

1984 COLD EXPLOSION
SIMILAR TO THIS ONE

© T.E. BEARDEN 1994, 1996



COUNTERING AN INSANE QP WEAPON:

Quantum Potential Psychoenergetics Strike Mentally Controls All Personnel

CONTROLLED PERSONNEL DISABLE INSANE QP SYSTEM
(FOLLOWED BY PERSONNEL KILL OF ENTIRE CADRE BY MINDSNAPPER)

ELECTRICAL DREAMTHINKING ARISES DIRECTLY IN BRAIN, HENCE IN MIND, BYPASSING SENSOR INPUTS

Effects arise in local spacetime, simultaneously in all minds in the targeted area

INSTANT HYPNOGOGIC STATE, WITH INSERTED DREAM-THINKING

© 1998 T.E. BEARDEN

INSTANT HYPNOGOGIC STATE: WITH WAKING DREAM

PERCEIVED REALITY NOW CONTROLLED

TARGETED CADRES

MINDS ARE INSTANTLY PLACED INTO WAKING-- BUT DEEP -- HYPNOGOGIC TRANCE STATE. INSERTED THOUGHTS ANALOGOUS TO HYPNOTIST. PERSONNEL FUNCTION IN AN ALTERED, COMPLETELY CONTROLLED PERCEIVED REALITY.

Indicators: Captain Button's lengthy A-10 incident in 1997, LIDA device since 1950s.



Gulf War Disease: KGB QP Weapon Induced ST Curvature Engines for a Cocktail of Diseases

LEBANON
SYRIA
ISRAEL
JORDAN
IRAQ
IRAN
KUWAIT
LIBYA
EGYPT
QATAR
SAUDIA ARABIA
OMAN
CHAD
SUDAN

© 1999 T. E. BEARDEN

Distant Scalar Potential Interferometer with iterative self-targeting



Self-Targeting in Inner EM Channel Can Produce a Quantum Potential

Once QP is established, energy transmission is direct and instantaneous. Energy input to one single participant will simultaneously appear in all other participants, the amount depending on their fractions of participation with the input station.

NARROWING OF INTERACTING POTENTIALS INTO LASER-LIKE BEAMS, BETWEEN TWO PUMPED SOURCES. NOW ONLY LONGITUDINAL WAVES CONNECT THE LINKED OBJECTS.

SELF-TARGETING EFFECT AMONG ALL PAIRS OF INTERACTING PUMPED SOURCES

© 1989, 1995, 1996 T.E. BEARDEN



a. Iterative retroreflection between any pair of nodes narrows the interconnecting potentials to a laser-like, bidirectional beam. Iterative phase conjugate reflection provides self-targeting.

b. The quantum potential exists as narrow, laser-like beams between participating nodes, even when the nodes are widely separated. The beam space is multiply-connected; transmission is instantaneous.

© 1989, 1995 T.E. BEARDEN

Consider the hidden Stoney/Whittaker bidirectional EM waves that comprise the potential from each source node. If these nodes have sufficient intersymmetry of dynamic material form, then self-targeting occurs between the two nodes of any nodal pair. By iterative phase conjugate reflection, the scattering is narrowed into interconnecting wavepairs, in laser-like beams, between each two nodes. Thus the interconnecting potentials narrow into laser-like, bidirectional beams. The Coulomb gauge may apply, and a quantum potential may be formed.

Figure 30. Mechanism for generating a quantum potential, by iterative self-targeting induced into a system of multiple scattering nodes. Once a QP is established, spatial separation has little or no effect.



Major Principles for Use of Quantum Potential Weapons

- Must disable dead-man fuzing prior to massive use of scalar interferometry weapons.
- Must assure immediate, complete nullification of unique enemy assets (quantum potential assets, special ships, and energetics weapons).
- Personnel can be destroyed instantly with mindsnapping; area is sterilized of life, and effect persists, gradually dying away.
- Personnel can be disabled instantly with various psychoenergetic weapons; area not sterilized.
- Personnel can be destroyed in short order by using EM BW weapons; area not sterilized.
- If foe has energetics weapons, then it is a quick-draw "gunslinger" contest unless insane MAD systems deployed.
- Complete surprise is of decisive importance.
- Tailor effect used to specific target, objective.
- *Note: Must use "insane" MAD systems to deter.*

© 1996 T.E. BEARDEN



Quantum Potential Weapons: Major Principles (Continued)

© 1996 T. E. BEARDEN

- Three major classes of use exist:
  - Use of bulk energy only (as in bulk heating or cooling) without substructuring
  - Use of internal structuring of the bulk energy, so that *vacuum engines* appear in target
  - Use of more deeply nested engines allows direct intervention in mind, long term memory, perception, thoughts, emotions, personality
- Use of vacuum engines allows engineering at a distance of:
  - *Atomic nuclei* including structures, reactions, and transmutations
  - *Bulk matter* including translations, lattice bonding, chemistry, chemical interactions, electromagnetic interactions
  - *Deep biological control systems* such as
    - Becker's cellular control (recovery) system
    - Popp's cellular control system
  - *Cells* including:
    - Structuring, differentiation and dedifferentiation
    - Genetic changes, chemical changes
    - Induction of disease states without normal disease vectors
  - *Mind/matter interface*, including long-term memory, perception, emotion, thought, mental state



Instantaneous Communication by a Quantum Potential

Note: The term "quantum potential" is used in an extended sense.

© 1989, 1995 T.E. BEARDEN

Selected clipart © by Lotus SmartPics™



Participants in a quantum potential share a common multiply-connected spacetime (MCST)

- Separated points are superposed in MCST
- Connection is instant and bidirectional
- Propagation through ST does not apply
- Energy or vacuum engine input to one station instantly appears at each and every other station, undiminished in magnitude

- Any station may insert energy and engines
- Phase conjugation insertion negates

© T.E. BEARDEN 1998



Quake in Tangshan, China

28 July, 1976

- 7.8 on Richter scale
- Hundreds of thousands killed
- Accompanied by extensive light, electrical effects
  - Starting 3 to 5 days before
  - Communications interference within 250 km
  - Sky lighting observed
- [Personal comments]

© T. E. BEARDEN 1999



Counting Rifles: Put up or shut up!

(Exchanging Earthquakes)

Opening bet
- Quebec 25 Nov 88
- Pasadena 3 Dec 88

Raise you
- Armenia 7 Dec 88

Call - what do you have?
- Malibu 18 Jan 89

Four aces
- Soviet Central Asia 23 Jan 89

Clear table (stress relief)
- Bakersfield et al various

©T.E.BEARDEN 1998



Instant Communication by a Quantum Potential

The space is multiply connected; i.e., a power change of 1 watt on any single node has a fraction of that power also appear simultaneously at each other node. Once the QP is established, spatial separation has no effect.

N's are nodes participating in the QP

© 1989, 1995 T.E. BEARDEN

N$_3$
RCVR
XMTR
SATELLITE
N$_5$
RCVR
XMTR
SATELLITE
N$_1$
RCVR
XMTR
MASTER
N$_4$
RCVR
XMTR
SATELLITE
N$_2$
RCVR
XMTR
SATELLITE



Westerners Do Not React to Slow Threats

BOA CONSTRICTOR

LIGHTNING STRIKE

Westerners tend not to react to slowly increasing things,
but react to rapidly increasing things.

© 1995 T.E. BEARDEN


CHARACTERIZING A GIVEN RISK OR RISK FACTOR
Probability of Materializing
Very Likely
Likely
Unlikely
Very Unlikely
1.00
0.75
0.500
0.25
0.00
Low Risk
Moderate Risk
High Risk
Crisis
0.00
0.25
0.500
0.75
1.00
Negligible
Marginal
Critical
Crisis
Consequence (or Disutility) of Risk

TECHNICAL RISK MANAGEMENT

SUPPORT RESEARCH IS TECHNICAL RISK REDUCTION AND MANDATORY FOR ANY EMERGING TECHNOLOGY





Aum Shinrikyo's Sarin Facility

The interior of Satian No. 7, a suspected sarin production plant

Chemical plant (the first four stages for production)

SOLVENT RECOVERY
STEPS 2 & 3
STEP 1
emergency stairs
emergency stairs
compressor room
shower room
a room for taking a nap
electrolysis room
machine operating room
stairs
prefabricated chemical laboratory
office
a room with liquid injectors
elevator
STEPS 4 & 5
chemical tanks (the 5th-stage production)
storage room
shutter
door
STORAGE

NOTE: Group was preparing to produce 70 tons of sarin in a 30 day period.

Reference: Senate Subcommittee Hearings



In Scalar Beam Interference Zone

- De-phasing of wave/antiwave pairs occurs
- Zero-summation destroyed
- Ordinary EM reappears [Whittaker 1904]
- Ordinary energy appears or disappears (i.e., may produce heating or cooling)
- Energy bottle effect
- Can add or extract EM energy
- Can produce specific ST curvature engines

© T. E. BEARDEN 1999



Physicist Schappeller Auralaz Munster, Austria:

- British Intelligence interview, about 1948
  - Used Kaluza-Klein theory
  - Worked with Russians
- Schappeller claimed he could:
  - Cause "implosions" rather than explosions
  - Use gravitational and electromagnetic energy
  - Cause large areas of the ocean to freeze
  - Tap earth-ionospheric field
  - Produce enormous energy
- *This is precisely what Hellman worked on in the USSR, after WW II!*

© 1996 T.E. BEARDEN



Initial Soviet Plan for Cold War, After WW II

- Develop and deploy SAM bomber defense
- Catch up in atomic weapons
- Master and apply rocketry
- Wed atomic warheads to rockets
- Initiate "Cold" War
  - Bleed the dragon
  - Guerrilla wars
  - Terrorism
  - Insurgencies
- *Find, develop, and weaponize next great technical breakthrough area as highest national priority*

© 1996 T.E. BEARDEN



Josef Stalin: Absolute Dictator

- Secret police and spies everywhere
- Purged his own officer corps
- Always deeply suspicious
- Regularly purged his enemies or those perceived to be shaky or untrustworthy
- Absolute power, justice had nothing to do with it
- Opponents often just disappeared in the night, never to be seen again
- Secret police often tortured, killed them
- Others sent to slave labor camps to die by severe work, starvation, and beatings or downright massacre
- Had experienced unusual abilities of Wolf Messing, so knew that some persons could do unusual things
- Forced Soviet weapon physics into this psychoenergetics realm also

One of the greatest mass murderers in history.

© T.E. BEARDEN 1997



Exploding any Resistance by Operational Scientists

© T.E. BEARDEN 1997

Josef Stalin

The Communists slaughtered 20 million Russian Kulaks to collectivize Soviet farming

Assembled Academy

"The destiny of communism has been frustrated by the U.S. development of the atomic bomb. That is not the last great technical breakthrough. The next one WILL be Soviet! You will provide me with that great new technical breakthrough at all speed, or I will have your heads. Do I make myself clear, comrades?"



Significant Soviet Statements

- "In the final revolution, it does not matter if three-quarters of the earth is destroyed, so long as the other quarter emerges communist." *[Lenin]*
- "If a means of total neutralization of foreign missiles is to be found, it can only come from a group of new principles in physics, called energetics." ***[Nobelian Petr Kapitsa, to Nikita Khrushchev, in answer to Khrushchev's demand for a 100% method of defense against long range missile attack.]***
- "We will bury you." ***[Khrushchev, to Nixon, Kitchen Debate]***
- "We have a new weapon, just within the portfolio of our scientists, so to speak, which is so powerful that, if unrestrainedly used, it could wipe out all life on earth. It is a *fantastic* weapon." ***[Khrushchev, speaking to the Presidium, Jan. 1960]***

© 1996 T.E. BEARDEN



CAPTAIN SVOBODA DIVES HEADLONG TO HER DEATH

COMPANION A-10s
CAPTAIN AMY SVOBODA

© T.E. BEARDEN 1999

- Night training mission May 27, 1997
- From same wing as Captain Button
- This was a second psychoenergetics strike



T-Polarized Beam Projector

For Intercepting and Changing Distant Masses at Various Angles and Distances

A beam projector interferometer may be swept in azimuth and elevation, under computer control. The interference zone can be quickly swept through the surrounding volume of space.

Spacetime curvature engines act within any intercepted mass
Time-Density waveset generator 1
Time-Density waveset generator 2
Small Delay generator
Pulse 1
Pulse 2
Pulse 1
Pulse 2
Pulse 1
Pulse 2
Interference zone for time-density waves
© T.E. BEARDEN 1996



Possible Tests (1)

- 1958 nuclear accident in Urals
- Disease induction in U.S. Embassy personnel in Moscow
- Siberian disease/death transmission experiments
- Destruction of USS Thresher nuclear submarine, Apr. 10, 1963
- Nuclear explosion transmitted into ocean underwater, 100 miles north of Puerto Rico, Apr. 11, 1963

© 1996 T.E. BEARDEN



Possible Tests (2)

- Eight F-111's downed in Vietnam immediately after deployment
- Several large earthquakes
- Mysterious aircraft losses in groupings
- Numerous underground "nuclear" tests
- Nuclear tests at Semipalatinsk without associated seismic activity
- High altitude rumbles, snaps, booms
  - *Off English coast*
  - *Off East coast of U.S.*
  - *Over West Coast of U.S. in thunderstorms*

© 1996 T.E. BEARDEN



Possible Tests (3)

- Blinding of several U.S. satellites (up to 4 hours in duration)
- Cold Explosion off Kurils 1984
  - First, a cold explosion
  - Then test of giant Tesla shield 300 mi. dia.
- Tests offset from shuttle launch Nov. 85
- Kill of Arrow DC-8,Gander, NFLD Dec. 1985
- Titan kill, Vandenberg AFB, CA early 1986
- Kill U.S. Challenger, off Cape Canaveral 1986
- Earthquakes induced, 1986-88
- Dozens of tests of shields around the world
- Decades of radiating U.S. Embassy in Moscow

© 1996 T.E. BEARDEN



Possible Tests (4)

- Extensive tests 1990-99 in Western Australia
- Engineering of weather since 1990 by Yakuza
- Possible nuclear dudding test in WA in 90s by Aum Shinrikyo
- C-130 engine flameout kill
- TWA-800 kill 1997
- Gulf War Disease Induced, 1991
- Spreading of immune systems of U.S. populace, 1990s
- Psychoenergetic control of Captain Button
- Psychoenergetic control of Captain Svoboda
- Twice in 1997, within days of full strategic destruction of U.S.

© 1996 T.E. BEARDEN



Mushroom cloud rising from sea

- 0514 hrs, 9 April 1984
- Gray-white cloud appeared
- Rose 60,000 feet in 2 minutes
- South of Kuril Islands
  - *180 miles southeast of Hokaido*
  - *200 miles from Tokyo*
- Soviet missile testing scheduled about 350 miles away, at 2100 hrs, 9 April 1984

© 1999 T. E. BEARDEN



Launches from Cape Canaveral and Vandenberg AFB Provided Practice Targets of Opportunity

The sinking U.S.S. Thresher, with her controls jammed, implodes when she reaches crush depth


APRIL 1963
© 1978 HAL CRAWFORD
USED BY PERMISSION


Thermometers
C-1
C-2
C-3
C-4
Calorimeters
Film Radiation Detectors
D-1
D-2
D-3
D-4
Radiation Counters
RC-1
RC-2
RC-3
RC-4
RC-5
RC-6
Power Meter
Experimental Region

Figure 32. Embodiment of an instrumental array sufficient to discriminate when time-density charging has occurred, and that transduction of time-charge decay is occurring.

© T.E. BEARDEN 1998

Time-Polarized EM Wave interferometer Creating Space-Time Curvature Engines in a Distant Interference Zone


TRANSVERSE WAVE GENERATOR #1
PHASE CONJUGATOR #1A
PHASE CONJUGATOR #1B
SPACETIME CURVATURE ENGINE / XMTR #1
CONTROLLER
LONGITUDINAL EM WAVES
TIME-DENSITY EM WAVES
IZ
PHASE CONJUGATOR #2A
PHASE CONJUGATOR #2B
SPACETIME CURVATURE ENGINE / XMTR #2
POWER SUPPLY
TRANSVERSE WAVE GENERATOR #2
© T.E. BEARDEN 1998



Transmutation of Radioactive Nuclei at a Distance

Interferometer (may be multiple beam or single beam) is played through the radioisotopes of the nuclear wastes to be neutralized. Specific engines may be used for altering specific isotopes.

Spacetime curvature engines act within any intercepted radioactive wastes

Active Spacetime Curvature Engines Zone of action
Nuclear wastes in storage, in ditches, in containers, etc.
Waveset 1 generator
Engines Calculation
Waveset 2 Generator
Trans-mission Control
© T.E. BEARDEN 1998



Transmutation of Radioactive Nuclei (2)

Specific spacetime curvature engines used are to add excess energy to selected radionuclei, including intermediate decay isotopes. In this way, decay is dramatically speeded up.

Spacetime curvature engines act within any intercepted radioactive wastes, adding excess energy

Active Spacetime Curvature Engines Zone of action

Nuclear wastes in storage, in ditches, in containers, etc.

Waveset 1 generator
Engines Calculation
Waveset 2 Generator
Trans-mission Control

© T.E. BEARDEN 1998



Typical Shield Test, Northern Route to Japan

Asahi Evening News, Tokyo
June 22, 1982

Multiple tests seen per month, for years.
Pilots simply ceased reporting them.

© T. E. BEARDEN 1994, 1995



A Curious Tide in Human Affairs

To win its freedom in the long run, usually a group must defeat its attackers or suppressors *at least twice*.

- We fought the British twice for our independence.
- We are fighting ourselves twice to free the slaves. - American Civil War
  - Civil rights struggle
- We beat the Germans twice, in WW I and WW II
- We beat the Hispanics in the Spanish-American War. *That's once*. (They're winning the second by crossing the border. The U.S. is becoming a Hispanic Nation).

© [illegible]

But we also have some unfinished business at hand.

- We checked the Russians in the Cold War. *Once*.
- We checked the Japanese in WW II. *Once*.
- We checked the KGB in the Cold War. *Once*.
- We checked the Communists in the Cold War. *Once*.
- We checked Saddam Hussein in the Gulf War. *Once*.



Large Scalar EM Interferometer (LASI) Accident Near Urals, 1958

- 1958 nuclear explosion near Urals
  - Signature of large scalar interferometer (LASI) accident
  - Buried atomic wastes suddenly exploded
  - Large region contaminated to this day
- Soviets were well along with advanced LASI prototypes and testing
  - Khrushchev announced forthcoming advent of these "fantastic" weapons in Jan. 1960
  - 1958 difficulties could have been resolved by 1960
- Expected 1958 cause: transmitter short-out and failure in a nearby LASI discharged its cumulated energetics beam energy into the ground
- *Spreading ground pulse struck nearby atomic wastes, fissioning nuclei*



The Superpower Paradox: Asymmetric Cheap WMD Strategic Strike and Destruction

Complex, expensive, high tech

Simple, cheap, low tech

LIBYA
EGYPT
SUDAN
SAUDI ARABIA
IRAN

© [illegible] T. E. BEARDEN



THE KGB/YAKUZA-AUM WAR PLAN

- *Dud all quantum potential weapons in other nations via psychoenergetics.*
- *Remove U.S., Israel, Brazil, West Europe as military powers.*
- *Destroy nuclear weapons, hostile energetics weapons, hostile ships, 80% of targeted populaces in first hour of strikes.*

LEASE

1990-91

Aum/Yakuza Acquired Use of on-site Russian Scalar EM (Energetics) Weapons.

Began Geosurvey of Test Range (Western Australia) for training.

KGB Tested QP population wpn (Gulf War Syndrome)

TRAIN

1991-94

Began extensive training of AUM-Yakuza crews in Russia, with practice firing into Western Australia. J-team took over world-wide weather engineering. Preparing for occupation of West Australia.

ESCALATE

1995-99

Began EM kill of selected lone U.S. targets, law strategic deception plan.

U-2 a/c? USAir 747 ?
TWA-800 C-130
ValueJet? A-10s

Surged electrical grids.
Worldwide practice kills, scalar interferometry.
QP modification of selected pathogens

STRIKE!

1999?

2000?

Plan:
Trigger terrorist BW, & WMD attacks.
Enhance BW infections with QP wpn.
When ready, counter insane QPweapons with psychoenergetics. Destroy QP wpns.
Dud all nuclear weapons worldwide;
Time-snap ships, scalar weapons sites;
Attack major target populations w/QP.
Then cleanup with interferometry strikes.

© 1996, 1999 T.E. BEARDEN



Why Western Science is Ignorant of KGB Energetics

- *Foundations* of electrodynamics and much of Western physics are seriously flawed
- Only just rediscovering longitudinal EM waves
- No knowledge of using time-polarized EM waves
- Does not know a powerful GR is hidden in EM
- Ignores inner structure of potentials, waves, fields
- Hotly defends errors, ignores for a century
- Determined to push big nuclear science
- Suppresses research to approved dogma by rigorously controlling precisely what research the funds can be used for

Transmutation of Radioactive Nuclei at a Distance



Interferometer (may be multiple beam or single beam) is played through the radioisotopes of the nuclear wastes to be neutralized. Specific engines may be used for altering specific isotopes.

Spacetime curvature engines act within any intercepted radioactive wastes

Active Spacetime Curvature Engines Zone of action

Nuclear wastes in storage, in ditches, in containers, etc.

Waveset 1 generator
Engines Calculation
Waveset 2 Generator
Trans-mission Control

© T.E. BEARDEN 1998

THE YAKUZA

(JAPANESE MAFIA)

To do business with Japan is to do business with the Yakuza



© 1995, 1996, 2001 T.E. BEARDEN

The Last Samurai, Defending Bushido

- 3 Major Yakuza Groups, In Coalition.
- Penetrate Japanese Government.
- Open Offices, Signs on Street.
- Public Romanticizes Yakuza as Last Japanese Samurai
- In Large High-Tech Corporations.
- In Control of Japanese Banks.
- Japanese Real-Estate Rip-off.
- $500 - 1,000 Billion per Year Income.
- Rapidly Spreading in U.S.
- Uniting Mafia Groups Worldwide.
- Coalition with Aum Shinrikyo.
- Leased Russian Energetics Weapons.
- Crews On-site in Russia, Trained.
- Practice Firings into Western Australia for Three Years. (Dozens of Shots per Month)
- Now in Escalation Phase, Killing U.S. Targets.
- All-out Strike on U.S. ready 1999-2000.
- Now held in check by KGB, dead-man fuzed by small nation friendly to U.S.



Yugoslav Earthquake, Followed by Cold Explosion

Apr. 15
1979

- Magnitude 7.2 on Richter scale
- Epicenter 33 km. deep
- More than 100 aftershocks
- At Kamenari:
  - Adriatic sea mushroomed up
  - Like atomic bomb explosion
  - Signature of a cold explosion
  - Similar to Apr. 1984 test off coast of Japan, near Kurils (see inset graphics)
- *Note that April is a significant test month for the Communists (preparing official reports for May Day?)*

OFF JAPAN, NEAR KURILS

1984 COLD EXPLOSION
SIMILAR TO THIS ONE

© T.E. BEARDEN 1994, 1996

SCALAR WEAPONS

UNDERSTANDING THESE MAKES IT EASIER TO UNDERSTAND THE NATURE OF THE AETHERS. WE'LL START WITH TOM BEARDEN'S FACTUAL INFO ABOUT THE RESULTS OF THE RUSSIAN'S SCALAR WEAPONS PROGRAM

http://www.cheniere.org/books/ferdelance/intro.htm

THE RUSSIANS USED SCALAR WEAPONS TO BLOW UP THE CHALLENGER SPACE SHUTTLE, A NUMBER OF OTHER LAUNCH VEHICLES, VARIOUS JET AIRPLANES, MODIFY THE WEATHER AND KILL UNTOLD NUMBERS OF BIRDS & FISH, WHICH HAS HAPPENED AGAIN RECENTLY. HAARP DEVICES CAN DO THIS.

SIMPLY PUT: A SCALAR WEAPON IS A FIGURE 8 WAVE FORM THAT IS NOT IN HARMONY WITH AN AMBIENT AETHER, IF POWERFUL ENOUGH THE SCALAR WEAPON CHANGES THE SIZE OF THE BACKGROUND SCREEN AETHER, WHICH THEN NO LONGER SUPPORTS THE MANIFESTATION OF MATTER, WHICH DESTABILIZES AND EXPLODES.

THE REASON WE ARE NOT ALL SPEAKING RUSSIAN IS BECAUSE THE MOST UNSTABLE MATTER IS IN NUCLEAR WARHEADS - DESTROYING THE ENTIRE WORLD IS NOT WINNING A WAR. PROVIDED, OF COURSE, THAT YOU LIVE ON THAT WORLD - THERE IS EXCELLENT EVIDENCE THAT A SCALAR WEAPON WAS USED TO DESTROY THE BIG BEAUTIFUL PLANET WHERE THE ASTEROID BELT IS NOW. THAT'S IN THE BOOK "COSMIC WAR".

GIGGLE, LAUGHING MY ASS OFF AT THIS ONE FROM BEARDEN:

It has also become fashionable in the West to believe that all the laws of physics are already discovered. We assume we already know all of them. While we have been pridefully crowing this tune, the Soviets have been steadily discovering new laws in secret, as well as new ways to circumvent the old laws.

THE SAD PART IS THAT IT HASN'T CHANGED - WESTERN SCIENTISTS ARE IDIOTS WHO ARE LEADING THE WORLD INTO DESTRUCTION. OR SITTING BACK AND WATCHING THE DESTRUCTION, WRINGING THEIR HANDS AND SAYING THAT FUKUSHIMA RADIATION WILL BE WITH US FOR 1000s OF YEARS. B.S. THERE ARE A NUMBER OF ENERGETIC WAYS TO CANCEL RADIATION INSTANTLY.

BEARDEN TAUGHT ME ABOUT SCALAR ENERGY - BUT, THEN HE HAS STARTED PARROTING LAME STREAM PHYSICS - PROBABLY TO KEEP HIS HEAD FROM BEING SEPARATED FROM HIS BODY BY OUR CONTROLLERS.

SCALAR WEAPONS ARE DESCRIBED IN A NUT SHELL ABOVE. BUT, WE'LL EXPAND IT A LITTLE - THE SIMPLE FACT THAT THEY WORK IS PROOF THAT THE AETHERS IS THE BACKGROUND SCREEN THAT SUPPORTS THE MANIFESTATION OF MATTER, WHICH IS ALL DIVINE I.E. MADE FROM IMAGES.

THE AETHERS PROGRESS IN SIZE ACCORDING TO THE FIBONACCI SERIES, BECAUSE EVERYTHING FROM THE QUANTUM TO THE COSMOS MANIFESTS ACCORDING TO THE FIBONACCI SERIES - ITS ALL FRACTAL I.E. A RECURRING MATHEMATICAL PATTERN, THAT IS PERFECT THROUGHOUT CREATION. HERE'S THE PROOF - OUR ENTIRE GALAXY IS IN PERFECT HARMONY WITH ONE NUMBER = RIDICULOUSLY AMAZING

http://blog.hasslberger.com/docs/PERFECTION.pdf

THUS, IF YOU CHANGE THE BACKGROUND SCREEN, THEN MATTER HAS TO CHANGE = THE RESULT OF USING A SCALAR WEAPON.

THE PRECISE WAY THE WEAPON WORKS IS TO IMPOSE A MAN MADE SCALAR WAVE ON AN AREA OF SPACE. GIVEN ENOUGH POWER TO THE SCALAR WAVE, IT WILL CAUSE THE AETHER IN THAT AREA TO MATCH ITS SIZE (LIKE ATTRACTS LIKE). WE ARE TALKING UNBELIEVABLY SIMPLE.

YOU CAN MAKE ONE YOURSELF - AMAZINGLY THE REQUIRED WINDINGS OF A SCALAR PRODUCING COIL CAN BE USED AS A WEAPON OR FOR HEALING - ITS CALLED A RADIONIC WITNESS WELL WHEN USED FOR HEALING.

TO MAKE A WITNESS WELL ONE WINDS INSULATED WIRE AROUND A GAP IN SPACE I.E. THE CENTER OF A TORROID. THE WIRE IS WOUND TO THE LEFT AND TO THE RIGHT. THE MORE WINDINGS THE MORE POWERFUL. AND, OF COURSE, THE POWER OF THE WAVE IS A FUNCTION OF THE POWER OF THE DC ELECTRICITY USED TO ACTIVATE THE DOUBLE WOUND COIL. SUCH A COIL PRODUCES A FIGURE 8 WAVE THAT IS THE SIZE OF THE CENTER OF THE COIL. IF THAT SIZE HAPPENS TO BE THE SIZE OF AN AMBIENT AETHER, YOU'RE NOT GOING TO HAVE A WEAPON.

IF YOU MAKE SUCH A COIL FOR HEALING, POWER IS NOT REQUIRED, IT AUTOMATICALLY CONNECTS WITH THE AETHERS IN A POSITIVE WAY.

IF YOU MAKE IT AS A WEAPON ADD LOTS OF POWER AND BE A LONG WAYS AWAY, WHEN YOU TURN IT ON. THE DESTRUCTIVE EFFECT IS INSTANTANEOUS - I'VE SEEN IT, WE BUILT ONE.

SCALAR WAVES ARE ALSO REFERRED TO AS PHASE CONJUGATED WAVES, MEANING TWO SINE WAVES THAT ARE 180 DEGREES OUT OF PHASE FROM ONE ANOTHER. (WESTERN LAME STREAM IDIOTS SAY THAT THOSE TWO WAVES CANCEL ONE ANOTHER.)

ONE SINE WAVE IS SAID TO RUN IN TIME FORWARD AND THE OTHER IN TIME REVERSE. AND THERE ARE A NUMBER OF EFFECTS THAT PROVE THIS. ONE EXAMPLE: DON BRANDT (ONE OF BEARDEN'S PROTEGEES) USED A SCALAR WAVE TO REGROW A LEG ON A CAT (A KID HAD SHOT IT OFF WITH A .22), WHEN DON FINISHED, THE CAT HAD ITS LEG BACK AND ALL OF THE CLOCKS WITHIN FIVE MILES WERE 15 MINUTES BEHIND TIME - THAT WAS THE LAST TIME HE PLAYED WITH THAT.

IN 2-D THERE IS NO LINEAL TIME.

BOTTOM LINE: SCALAR WEAPONS PROVE THE NATURE OF THE AETHER AS THE BACKGROUND SCREEN - IF THAT WAS NOT SO, THEN SCALAR WEAPONS WOULD NOT WORK.

ALSO, SCALAR WAVES THAT ARE IN HARMONY WITH AN AMBIENT AETHER ARE VERY BENEFICIAL AND USEFUL - A BEE'S HONEYCOMB IS AN EXCELLENT EXAMPLE. DITTO GRAPHENE.

LOVE AND BLESSINGS

PS: THERE HAVE BEEN A NUMBER OF HUMAN "CIVILIZATIONS" IN THIS SOLAR SYSTEM AND ON THIS PLANET. OUR CONTROLLERS LIKE US TO BE STUPID, BECAUSE IT SEEMS THAT WHEN EVER WE MAKE GREAT TECHNOLOGICAL ADVANCES OR SPIRITUAL ADVANCES, THEN THEY WIPE US OUT. WE ARE AN ENTERTAINMENT SLAVE SPECIE.

THIS LAYS OUT HOW OUR DREAMS / ANUs ARE SHARED WITH OTHERS AND THAT JESUS' ENERGY IS FOUNDATIONAL
http://blog.hasslberger.com/docs/GOLDFISH_JESUS_REVELATIONS.pdf

THIS IS FUNNY AND SHOWS THAT THE EARTH IS THE BEST ENTERTAINMENT SYSTEM IN ALL OF GOD'S CREATION:
http://blog.hasslberger.com/docs/EARTH_WINS.pdf

OH - THE CHEMTRAILS WILL KILL JUST ABOUT EVERY LIVING THING ON THE FACE OF THIS PLANET, IF WE DON'T START MEDITATING AND BUILDING ORGONE DEVICES, WHICH HAS TO BE DONE EVEN IF THEY STOP SPRAYING BECAUSE THE EFFECTS OF THE CHEMTRAILS CAN AND WILL CARRY ON, EVEN IF THE SPRAYING STOPPED.

Scalar Wars

The Brave New World of Scalar Electromagnetics

by Bill Morgan



For the past six months I have been undergoing the greatest **paradigm shift** I have ever had to go through. It has rattled my nerves and shaken my bones. This intense adjustment of my "world" has come about by studying the information given by Col. Tom Bearden at his website Cheniere. The new knowledge there has necessitated a total revision of my ideas about physical reality, the world we live in, and the future of humanity. This paradigm shifting even actually made me dizzy on certain days as I tried to absorb and digest Bearden's vast amount of information. I am not a scientist at all, just a layman, and I have little comprehension of the math and high physics of this new science called "**Scalar Electromagnetics**." But there is a great deal of information at Cheniere which needs to become common knowledge as fast as possible, for the sake of the survival of life on earth. To that end I have put together this small primer of Bearden's ideas, as a kind of "beginner's guide" to his website. (I have tried to underline certain words and phrases which are part of the new "jargon" of talking about these "new" phenomena. Also I have taken the liberty of bolding certain words and phrases to help them stick in the mind).

(Note: Throughout "**EM**" means "**electromagnetic**," and "**LW**" means "**longitudinal wave**")

This article has six sections:

New Waves 2. Tapping the Waves 3. Weaponization 4. Healing 5. Psychoenergetics 6. As It Stands

1. New waves discovered

Longitudinal EM energy fills vacuum of space, the time domain of spacetime, time as compressed energy, E=tc2, waves of time, phase conjugate wave pairs.

"Electric power is everywhere present in unlimited quantities and can drive the world's machinery without the need of coal, oil, gas, or any other of the common fuels." Nikola Tesla

"At any point and at any time, one can freely and inexpensively extract enormous EM energy flows directly from the active vacuum itself." Tom Bearden



I guess the first thing to try to comprehend is that a "new" kind of electromagnetic (EM) wave has been discovered in the empty vacuum of space called “longitudinal” waves, which, when engineered, can be an inexhaustible supply of energy in great magnitude at any place in the universe. The word "new" is in quotes because the discovery really goes back to **Nikola Tesla** and his discovery of what he called "radiant energy." It is also not "new" because the Russians (KGB) have been working on this technology for over 30 years and have **weaponized** these "new" longitudinal scalar waves to a great degree.

These are the very weapons **Nikita Khrushchev** spoke of in January, 1960.

> "By 1957-8 the Soviets had progressed to the point of a giant scalar EM accident in the Urals which exploded nearby atomic wastes, devastating the area. They had also progressed to development of great new superweapons using their new energetics - weapons to which Khrushchev referred in 1960 when he informed the Soviet Presidium of a new, fantastic weapon in development, a weapon so powerful that it could wipe out all life on earth if unrestrainedly employed.'" Tom Bearden

After over 30 years of development, and extensive testing around the globe, these new scalar electromagnetic weapons are up and running and ready to go. Tom Bearden, at his website Cheniere, discusses the history of these new scalar electromagnetic weapons in his paper "Historical Background of Scalar EM Weapons."

Some Immediate Implications

> The implications of successful engineering of the longitudinal waves are enormous, and will change the world as we know it, one way or another. Among other things, these discoveries mean that:
>
> 1. The **solutions to the energy crisis and the "oil problem" are in hand**. These oil wars are unnecessary. There is endless energy available freely from the domain of time.

2. **Unbelievably powerful weapons** are not only possible, but are already operating in several nations. The many powers of these weapons are unprecedented and mind-boggling.

3. The **cure of diseases such as cancer and AIDS**, in fact nearly any disease, has become possible within a few years of sufficient funding. Everyone can be made healthy and stay healthy.

4. **Mind control on a mass scale** has now become possible, and the machines to do it are already in place in certain nations. It has become possible to mentally enslave whole populations with the twist of a few dials.

So the layman will need to understand that there is a new kind of electromagnetic energy that is altogether different from what he knows, e.g. radio, TV, cell phones, etc. The ordinary EM waves that we have known about are called transverse EM waves, to distinguish them from the new longitudinal EM waves. These scalar waves do not actually exist in our "material" world, but exist only in the vacuum of empty space, or the time domain. And we must keep in mind that this vacuum of space we speak of exists all through everything. Even our bodies are mostly empty space between atoms and molecules. So the gateway to this seething ocean of energy can be there at every point in the universe. This seething ocean of energy is all around us and all through us.

Emptiness is Full

This amazing discovery announces that the "emptiness" of empty space is in fact not empty, but a great ocean of seething energy!

Col. Bearden refers to this ocean of energy as being of the "time domain." It seems like something from Star Trek but this is where scalar electromagnetics has come to. And where it is going may be beyond anything Star Trek could have dreamed of.

We live in a 3-dimensional world, which physics calls "3-space." But there is also spacetime, or 4-space, or the "4th dimension." Then suddenly comes this amazing new knowledge that time itself is actually compressed energy. And it is energy which is compressed by exactly the same factor by which matter is considered compressed energy: the speed-of-light-squared!

So we have a new companion to the famous E=mc2. It is now paired with E=tc2 (where t is actually "delta-t," or change in time). Or (amaze your family and friends and) say:

"E equals em-cee-squared"

and

"E equals delta-tee-cee-squared"

It has a nice ring to it, like some freedom bell announcing a new era.

And as the atomic bomb released the compressed energy in matter, so can we now unleash the tremendous energy that is compressed into time itself. It gives a completely new meaning to the term "time bomb."

Some New Terminology of Scalar Electromagnetics

A new science, several new names

> "Those [Russian] weapon scientists resurrected an old term from the history of electrodynamics, called "energetics". That is their approach to a unified field theory, where everything is based on "energetics". This model as its foundations uses a very similar approach to that "single fundamental unit" model, where energy is the unit. If one makes the energy EM in nature, then one has the Russian energetics approach. This unified approach gathers everything in, including all energy actions and relations in inert matter (the first branch of energetics, called by the same name), all field and matter interactions in living matter (the second branch of energetics, called "bioenergetics"), and all mind operations and mind-matter interactions (the third branch of energetics, called "psychoenergetics"). [ed: sometimes also called "psychotronics" by the Russians]

Rick Andersen in an article called "What is Scalar Electromagnetics?" describes the new science this way:

> "Scalar EM is the brainchild of Lt. Col. (retired) Thomas E. Bearden, a systems analyst and wargames specialist who has been advocating a view of electromagnetics which is based on the notion of a vast, unseen background of scalar energies (as opposed to vector energies) which underlie all physical reality.
>
> "If Bearden is correct in his Scalar EM theory, then we can build devices which would enable us to alter gravity, time, inertia, and the apparent mass of an object. This of course has ENORMOUS implications for military applications, space-vehicle drives, time-travel, teleportation, paranormal phenomena, and just about every other area one can think of." http://twm.co.nz/Beard_scalem.html

> "Time-energy, time-currents, and time-structuring play the dominant role in electromagnetics. Time-as-energy eventually becomes engineerable, as easily as is spatial energy now. We are always dealing with spacetime and with spacetime curvature."
>
> Bearden: http://www.cheniere.org/techpapers/Vision%202000%20paper.doc

The scalar energy discovered in the vacuum of space is sometimes called "zero-point" energy. Thomas Valone explains how this term came about.

What does "Zero Point" mean?

"Boyer traces the historical "creation of the vacuum" as proceeding in stages in parallel with the historical development of ideas about the vacuum. To paraphrase, he says that in the 17th century, it was thought that a totally empty volume of space could be created by simply removing all matter and, in particular, all gases. That was our first concept of the vacuum. Just get rid of all the gas. Late in the 19th century, it became apparent that the region still contained thermal radiation. But it seemed that the radiation might be eliminated by cooling. So the second concept of getting a real vacuum is to cool it down to zero temperature. Just go all the way to absolute zero. Then we've got a real vacuum. Right? Well, since then, both theory and experiment have shown that there is a non-thermal radiation in the vacuum and that it persists even if the temperature could be lowered to absolute zero. Therefore, it was simply called the "zero point" radiation. "Thomas Valone http://www.seaspower.com/InsideZeroPoint.htm

> "**For our very survival, it is absolutely imperative that informed citizens be aware of this dramatic change, which is just now starting. The powerful new science and engineering must be controlled and used for humanity's benefit, not its detriment. Else it will eventually be let loose unrestrainedly, to destroy all life on earth - a possibility indicated by Nikita Khrushchev in 1960**." - Bearden
>
> http://www.cheniere.org/explore%20articles/priore1/p4.jpg

2. Tapping the waves

Endless free energy, Tesla's radiant energy, the dipole as the gateway to the energy of the void, MEG in one year, Bedini, Yakuza, etc. End of Oil, geopolitical chaos, rogue groups

Move Over G.E. & Big Oil, Energy is Everywhere!

Third-world nations set to rise

> "Certain powerful interests did not wish the extended electromagnetics to be discovered or taught. That, after all, would lead to free energy and loss of economic control of the citizens. That was precisely why Nikola Tesla had already been suppressed ... Today it is still being suppressed by the orthodox establishment."
> http://www.cheniere.org/books/ferdelance/s25.htm

The vast seething ocean of energy of the vacuum, the longitudinal scalar EM waves of the time domain, can now be tapped and "transduced" into ordinary (transverse) EM energy in our 3-Space world. The process can be compared to putting a paddlewheel into a river. The energy acquired is free, since the river is there flowing whether we tap it or not. And it is a mighty river, and is not diminished by our paddlewheel.

This means that a permanent solution to the "energy crisis" is at hand, if only those who hold it so secret would give it up to humankind.

It means our species' insane use of oil is no longer necessary. We can make automobiles that need no fuel at all. We can build motors that power themselves. It means that unlimited electrical power can be available for free anywhere in the world. Every house and even shack can have its own power supply.

Of course there is the cost of the equipment at first, but the energy flow is free for the presumably very long life (no moving parts) of the generator. It will probably take decades to shift over to scalar power.

But the ability to tap the scalar (longitudinal) EM waves of the vacuum (which exists everywhere) also means that unbelievably powerful weapons can be, and already have been developed. In fact these weapons are so dangerous that the fear engendered becomes a psychological obstacle to the grasping of the facts.

I struggled with this myself for months, and even though Tom Bearden had completely convinced me already, it is hard to accept the fact that for everyone on earth the "worst that might happen" has suddenly gotten much worse. It takes time to deal with that, to realize it and get over it.

Indeed, the possibilities of these new weapons, which are tapping the huge energies of time, are so terrifying it is natural for the mind to simply say: "I don't want to hear about that."

And the government, likewise, pretends these weapons do not exist and tries to keep it secret from the people. Because most people would indeed be truly alarmed to know the actual situation. Col. Tom Bearden has decided that the people need to know the truth anyway. As a People on a Planet we must face this now, and ban the use of scalar weapons in war or in mass mind control. The current deployment of these weapons is a world emergency which we must all face.

The physics and mathematics of the longitudinal waves and the time domain are clearly beyond the layman, but I recommend scanning through them anyway just to get a sense of the wonder and the elegance of it all and some of the exotic terms which are used. Two of the most important papers by Col. Bearden are:

Giant Negentropy from the Common Dipole

The Final Secret of Free Energy.

Despite the complexity of the science involved, Bearden sums up the essential secret of it all in a few words.

> "There is no problem at all in extracting all the energy one wishes from the active vacuum, anywhere in the universe, at any time. Just make a dipole.

> The problem is in (1) catching some of that freely gushing EM energy in a circuit containing a load, and (2) dissipating the caught and collected EM energy in that load to power it, without using half the caught energy to destroy the source dipole's).
>
> That is the ONLY real energy problem on the planet, and always has been."
>
> http://www.cheniere.org/correspondence/022502.htm

A dipole could be a battery, which is polarized into negative and positive. Or the terminals of a generator. Or any magnet with its two poles. Or an atom with its positive and negative charges. Or the earth's magnetic field, the sun, and all heavenly bodies. Even a galaxy must be some kind of mega-dipole. Wherever there is a dipole there is already immense scalar EM energy ushering out of and back into the vacuum. And there have already been demonstrated a number of diverse methods for tapping that energy as it flows. (John Bedini, Edwin Gray, Bruce de Palma, and others). Bearden provides what he calls a "partial list" on his website.

> "In other words, nature then gladly gives us as much EM energy flow as we need, indefinitely — just for paying a tiny little bit initially to "make the little dipole." After that, we never have to pay anything again, and nature will happily keep on pouring out that 3-flow of EM energy for us. This is the giant negentropy mechanism I uncovered, performed in the simplest way imaginable: just make an ordinary little dipole."
>
> Bearden http://www.cheniere.org/techpapers/Unnecessary%20Energy%20Crisis.doc

How to Buy a Free Energy Machine

Answer: Just wait one more year! 2003. Then get off the Grid!

Perhaps the most eagerly awaited event now is the marketing of Bearden's Motionless Electromagnetic Generator (MEG) scheduled to begin in about a year's time. This is when the proof will hit the fan. Many people have said to me, when talking about free energy, "I'll believe it when I can go to the store and buy one." Hopefully in a year's time they will be able to order their own MEG. And then they will believe, because it works and is working.

Says Bearden: "I will admit that the chief scientist of an important experimental group in a large company was rather stunned at the type of output we were able to obtain. The MEG may look like just a transformer, but it is not. It is a completely different breed of cat."

(Bearden : http://www.cheniere.org/correspondence/011202.htm)

Soon the cat will be fully out of the bag. The first MEG units will supply 2.5 kilowatts of free electricity. Forever. Units can be connected together to double or triple the wattage. After that gets going, 10 kilowatt generators are planned. Energy will flow freely from the time domain indefinitely, and there are no moving parts to wear out. This manufacturing project is a heroic effort and will change the world as we know it. For once people are in possession of such devices there can be no further denial from anyone, including the government and/or "secret-government."



The Motionless Electromagnetic Generator

(Successfully replicated here by J. L. Naudin)

The physics of how the MEG works is explained in the paper "The Motionless Electromagnetic Generator: Extracting Energy from a Permanent Magnet with Energy Replenishment from the Active Vacuum."

The device was successfully replicated by J.L. Naudin in France, and others, like Steve Utne, are also working on their own models. But Magnetic Energy Limited's MEG is actually scheduled for production soon and looks to be the first commercially available free-energy generator in history!

I imagine it will not take long for tinkerers to put them into their electric cars and make the first fuelless automobiles since Tesla's unheralded (and unheeded) experiments. Or for builders to begin building houses powered by MEG's. Houses which will never see electric bills. How can they ever make enough of these to meet the demand that will suddenly be there? Bearden is right, it needs to be an all-out crash program of the government on the order of the Manhattan Project.

I must include here that Bearden is quick to point out that he is not himself the inventor of the MEG, but is a partner and advisor in bringing it to the public market through Magnetic Energy Limited, Inc. I must also admit that I am praying for the success of this venture, and the ending of the absurd and criminal withholding of this technology from the people by the black-ops military-industrial people. This secrecy has cost the planet over 30 years of unnecessary pollution.

The first units off the assembly line, which is being set up in a "friendly" unnamed nation, will usher the public at last into the new era of scalar electromagnetics.

As of December, 2001, the situation with the MEG was described by Bearden in a letter.

> "What we presently have with the MEG is a successful laboratory experiment. At least a year's very hard research will have to be done before we will be ready to put a commercial power supply into production.
>
> "Consequently, we have made an agreement with a foreign partner (the National Materials Science Lab of the National Academy of Sciences of a friendly foreign nation) to do that year's research. At the same time, we are trying to make an agreement with one or more large financial partners here in the U.S."
>
> Bearden http://www.cheniere.org/correspondence/121901.htm
>
> "So we are hopeful that we will be able to start introducing units on the market about a year from now. Quite simply, we will either succeed or we will fail. But we will give it our very best effort."
>
> Bearden http://www.cheniere.org/correspondence/012202a.htm

Bearden has given another technical explanation of how the MEG works here in a letter.

Motionless Electromagnetic Generator patented, 3-26-2002

Click here to read the patent

"In Magnetic Energy Limited, all business discussions and arrangements are taken care of by Dr. Lee Kenny, Managing Partner. There are five of us who are co-inventors of the MEG, and two of the others are really the principal inventors." Bearden http://www.cheniere.org/megstatus.htm

Free Energy has been Suppressed

Secret Government Aware of Free Energy

> "In this world of contemporary times, all the agencies, CIA, FBI, KGB, NSA, Electric Power Research Institute, DARPA, Brookings Institution, Henry Kissinger, Edward Teller, et al., all are aware of [free-energy researcher Bruce] De Palma and his ideas.
>
> "Because these individuals and institutions are employed by the ruling elite to forecast the future and satisfy present needs and demands, it is clear that free energy is a threat to the world order constructed by business and the mindset of those who want to own the world.
>
> "Free energy represents Man's aspirations and dreams of freedom and equality, uniform division of resources and the ability to choose one's own future.
>
> "The fact that free energy is suppressed speaks to the greed and self-interest of a ruling elite which, even in the face of an emergency of global starvation, resource depletion and environmental pollution, will not give one inch if it means loss of control. This is an

> attitude of paranoid delusion and fantasy which can only arise from the alienation of a class of elitists who, through their money, are completely insulated from the reality of the day to day fight for existence of the common man."
>
> http://depalma.pair.com/Absurdity/Absurdity07/ProblemOfFreeEnergy.html

Bearden describes one case of suppression when the Yakuza killed the Kawai engine in his very presence in Huntsville, Alabama.

> "That night a jet arrived from Los Angeles, with a Yakuza on board. The next morning Kawai no longer controlled his company, his invention, or his own fate. The Kawai party was in fear and trembling. The Yakuza coldly dissolved the agreement, they packed up the two Kawai engines we had, and left. And that was that."

So it is not only governments who are keeping this revolutionary technology from seeing the light of day. The Yakuza? KGB? The Aum Shinrikyo cult? Our "leaders" need to be honest about what is going on, otherwise they look foolish, acting out a kind of "Alice In Wonderland" script before the public, a script that has become completely unbelievable.

Concerning the criminal withholding of this scalar technology by the military black-budget people, and the cover-up of the actual situation regarding scalar weapons throughout the world, Tom has this to say:

> "The high government officials of the United States of America grossly violated our constitution and their sworn oaths of office. Our constitution specifically charges the government of the United States to defend the people of the United States. That means our officials are specifically charged with defending our people. Yet they deliberately agreed not to do so, and they deliberately sacrificed us in advance.
>
> "They committed treason of the highest kind, by deliberately surrendering us to total destruction anytime the big balloon goes up."
>
> Bearden http://www.cheniere.org/books/ferdelance/s75.htm

Energy Crisis Solved

One of the "must read" documents at Cheniere is “The Unnecessary Energy Crisis: How to Solve It Quickly,” especially since the "oil wars," which Bearden has foreseen for decades, have now already begun.

Here are some clips from that Document:

> "To avoid the impending collapse of the world economy and/or the destruction of civilization and the biosphere, we must quickly replace much of the "electrical energy from oil" heart of the crisis at great speed, and simultaneously replace a significant part of the "transportation using oil products" factor also.

> "The technical basis for that solution and part of the prototype technology required, are now at hand. We discuss that solution in this paper."

And although the solution to the energy problem and the oil wars may be at hand, Bearden suggests there is still an urgent rush that needs to be made to save human civilization from collapse.

> "Once the technology hardware solutions are ready for mass production, even with a massive worldwide deployment effort some five years are required to deploy the new systems sufficiently to contain the problem of world economic collapse. This means that, by the end of 2003, those hardware technology solutions must have been completed, and the production replacement power systems must be ready to roll off the assembly lines en masse.
>
> "The 2003 date appears to be the critical "point of no return" for the survival of civilization as we have known it.
>
> "Reaching that point, say, in 2005 will not solve the crisis in time, and the collapse of the world economy as well as the destruction of civilization and the biosphere will still almost certainly occur, even with the solutions in hand."
>
> "The good news is that we now know how to easily initiate continuous and powerful "electromagnetic winds" from the vacuum at will. Once initiated, each free EM energy wind flows continuously so long as the simple initiator is not deliberately destroyed."

On page 9 he explains the concept of the dipole, and how there is already huge scalar energy flowing in the time domain around any dipole. Hold a magnet or a battery in your hand and you hold a stress in time and a beautiful flowing loop of longitudinal waves!

Bearden decries the scientific community in the West for being unable to let go of their dogma long enough to see that the greatest discovery in human history lies at their feet, but for their stubborn ignorance.

> "The present energy crisis then is due totally to that "conspiracy of ignorance" we referred to, that is maintained by the scientific community, and that has been maintained by it for more than 100 years.
>
> "This is the real situation that the environmentalists must become aware of, if they are to see the correct path into which their energies and efforts should be directed — to solve both the energy crisis and the problem of gigantic pollution of the biosphere. "As far as anyone in the legislative branch of government ever understanding the profundity of the discovery and engineering of scalar waves, Tom Bearden says they are at a great disadvantage in doing so.
>
> "The nontechnical person — e.g., a Senator or a Congressperson — is operating under a distinct disadvantage. If he or she takes the stance that much better electrical power systems can readily be achieved, he or she is in fact opposing almost the entire set of University, Government Technical, Power Company, Battery Company, and Organized

> Science communities. Further, in most cases his technical advisors are themselves from one or the other of those communities, and likely to go back into that community or those communities when the Senator or Congressperson leaves office, or even before. So the Congress and the non-technical government community at large operate at a great disadvantage...Bearden National Emergency Declaration is Needed
>
> "The Government Non-Technical community (the Senate and the Congress, in particular) are in far better shape than the Government Technical community, to appreciate the world implications of the pending economic disaster. I am hopeful that both the environmentalists and the Government Non-Technical community will rapidly unite in a common goal to get this vacuum energy program launched, under a National Emergency declaration. If so, then they can solve the energy crisis and the pending economic crisis, in fairly short order, and permanently."
>
> unnecessary_energy_crisis.htm#congress_disadvantage

In the conclusion of his paper The Unnecessary Energy Crisis: How to Solve It Quickly Bearden again states the urgency of replacing our centralized power grids with highly dispersed and local taps on the freely flowing energy of the active vacuum. Given the abilities of the Tesla howitzers, the power grids of all nations are sitting ducks.

> "Personally, the present author regards the increasing energy crisis as the greatest strategic threat to the United States in its entire history. I will do anything within my power to help prevent what I perceive to be the looming economic collapse of the Western world, preceded or accompanied by a sudden, explosive, all-out and continuing exchange of the WMD arsenals of most of the world.
>
> ...In the name of all humanity, let us begin! Else by the time this first decade of the new millennium ends, much of humanity may not remain to see the second decade."

3. Weaponization

Scalar interferometry, Tesla howitzer, Tesla dome, heat/cold, dudding, 10 nations have them, dead-man fusing & Insane Systems, scalar strategy, earthquakes and weather wars, solar storms, mind attacks, leased to Yakuza, many examples of testing, quantum potential weapons.

> "Indeed, Soviet energetics weapons are now capable of destroying both our triad shield, our homeland, our armed forces in the field, and our population, quickly and efficiently. We have a new "gap" of monumental proportions: not a missile gap, not a submarine or bomber gap, and not even a particle beam or laser gap. We have a scalar electromagnetics or electrogravitation gap." Bearden http://www.cheniere.org/books/ferdelance/intro.htm

"**We have a new weapon, just within the portfolio of our scientists, so to speak, which is so powerful that,**

if unrestrainedly used, it could wipe out all life on earth. It is a fantastic weapon." Khrushchev, to the Presidium, Jan. 1960

> "We've totally missed the most incredible "secret superweapons" development program of all times, and the worldwide testing of the weapons themselves.
>
> "Hiroshima and Nagasaki should serve as object lessons in the price of ignorance of such technological breakthroughs.
>
> "History does repeat itself. But this time it's not we Americans who got the great new superweapon first."
>
> Bearden http://www.cheniere.org/books/ferdelance/s75.htm

Warfare has been changed forever by the development of these scalar energy longitudinal wave howitzers. To get a basic understanding of scalar waves is to have the imagination suddenly run wild as all the implications and possibilities regarding warfare fall into place. One realizes with a certain horror that the world has totally changed, and that there are some very fearsome possibilities. Remember, the power for these weapons comes from the time domain, longitudinal EM waves in the vacuum of empty space, and the power is tremendous and mind-boggling. Being able to blast away at any target from a distant control booth is something that has never happened before. This is incredible power to be in control of and it divides the history of weaponry into "before" and "after." And the destructive power of these weapons is delivered instantaneously to the target from the local vacuum at the place of the target.

From an interview:

> Questioner: "Are you saying that real energy can be transmitted faster than the speed of light?"
>
> Bearden: "Yes. But hyperspatially. Not through 3-space, but "around" it. Again, this means that it's possible to produce energetic changes in a distant system at a distant place, without transmitting energy "through space" in the normal sense. You transmit "around" space, so to speak, and directly in time or through a higher dimension, depending on the model you're using to understand this. Further, the speed of the internal EM energy transmission is not limited to the speed of light."
>
> http://twm.co.nz/beard_interview.htm

Here are some initial considerations about scalar weapons and scalar wars

1. Tesla Howitzer 2. Tesla Domes 3. Rogue groups 4. WW III 5. Russian "UFOs?"

3a. The Tesla Howitzer and its modes of action

Source: Tom Bearden's weapons slides and Fer-de-Lance Briefing

For one thing there is no delivery of any thing to any place. Bombs are obsolete. So are the planes to get them there. No helicopters necessary. All current nuclear devices are rendered nearly useless by electronic "dudding." All distant-destruction can be done from a control room, and to any point on earth. The destructive power of "men" has just increased by orders of magnitude. The new weapons could even cause storms on the sun! Thus there is great urgency to make these new facts public and known, with the hope that all nations would come together to ban the use of scalar weapons.

Two scalar antennae together along with the computers to control them, make up a scalar interferometer, and according to Col. Bearden the Russians have hundreds of such installations already. These interferometers are called "Tesla Howitzers." They can deliver a giant blast of energy to the distant target site, true "action-at-a-distance".

The first howitzer mode is called the "exothermic" mode of operation because immense EM energy blasts outward at the target site. The blast of a scalar howitzer can be of near nuclear level in destructiveness, and can be repeated easily, at that place, or nearby, or anywhere.

The howitzer can use a lesser exothermic power setting and simply destroy all electronics in the target area. Thus they can render our nuclear missiles inoperable as they sit in their silos by "frying" the electronic circuits that guide them. They can bring down any airplane, anywhere in the world, at any time. Any person anywhere, if their exact position is known, can be assassinated without a shot being fired.

The howitzers can also bring down power grids anywhere in the world, at any time. Thus they could bring Wall Street to an instant halt by disabling all its electronics. Even this one little easy tweak of the howitzer could cripple the U.S. economy in a single day. No wonder the "leaders" don't want you to know! This is a new era we are in. The discovery and development of scalar interferometry has put us in a new world, whether we like it or not. Anyone could be expected to go into denial, the befuddled senators and congressmen included. But we have to wake up.

In a second howitzer mode called the "endothermic" mode, the howitzer sucks energy out of the target area, essentially creating a blast of cold at the distant target. It is even capable of freezing parts of the ocean. Bearden gives a number of cases where these "cold explosions" have been witnessed, mostly by airline pilots. April 9, 1984: 1 2 3) A huge mushroom cloud of mostly water is seen rising miles into the sky from out of the ocean, an awesome sight.

In the endothermic mode the sucked-out energy must go somewhere, so it is vented out at some other chosen spot on the earth. These endothermic plumes have been photographed by satellite.

> "The exhaust in the left picture is about 150 miles long, and is nearly horizontal (about 1.5 degrees above the horizontal). It is entirely consistent with the continuous exhaust from a "dumping transfer" scalar EM howitzer in the continuous exothermic mode. (The primary howitzer, of course, was activated in the endothermic mode.)" Bearden More Plumes

By using both of these heat (exothermic) and cold (endothermic) modes together the weather can be altered anywhere. Warm the air over here, cool it down over there, put a curl in the jet stream, dissipate clouds, create clouds, whip up a tornado. Bearden speaks about using the endothermic howitzer mode as a weapon of war:

"Cold explosions can be used to freeze tanks, personnel, and equipment. The equipment and tanks thaw out. The personnel thaw out too, but they are dead when they do." Bearden, Fer-de-Lance

(This endothermic mode of the howitzers makes me think that there might one day be a cure for the problem of global warming after all. Could not a big device, situated in space or on the moon, be able to vent a great deal of excess heat outside the atmosphere into space, thus functioning as a kind of planetary thermostat?)

While the United States has experimented with electomagnetic weapons using ordinary transverse EM waves, the longitudinal [LW] weaponized waves are truly of another order altogether.

For one thing they do not have to travel through space, for they come from the time domain, which is everywhere. The energy of the blast, the heat or light or whatever, comes from the vacuum of space at the location of the target itself. This is astonishing. The weapons actually just trigger the release of immense energy from the vacuum at the target location.

> "... it is possible to focus the potential for the effects of a weapon through spacetime itself, in a manner so that mass and energy do not "travel through space" from the transmitter to the target at all. Instead, ripples and patterns in the fabric of spacetime itself are manipulated to meet and interfere in and at the local spacetime of some distant target. There interference of these ripple patterns creates the desired energetic effect (hence the term energetics) directly in and through the target itself, emerging from the very spacetime (vacuum) in which the target is imbedded at its distant location." Bearden Fer-de-Lance

The big Tesla howitzers are aimed at their targets by using a worldwide electromagnetic pattern called the "Woodpecker Grid," begun by the Russians in 1976.

You can hear the Woodpecker signal here: http://www.cheniere.org/misc/woodpeckersound.htm

The woodpecker grid is just that, a grid of EM waves which provide a channel for the LW waves to any point on earth. Computers use the woodpecker grid information to hone down the aiming of the howitzers to a pinpoint location on earth. (For that matter, it could be under the earth, in space, or under the sea).

A third howitzer mode is what Col. Bearden calls "Mindsnapper" mode. This is a truly frightening mode which affects the electromagnetic mind-body connection. Being mind-snapped at a low level would cause you to lose consciousness. Being mind-snapped at a slightly higher power would "entrain" all minds in the target area into a kind of hypnogogic trance, a state in which they would all be highly susceptible to suggestions and orders.

Being mind-snapped at high level would so disrupt the mind-body connection that everyone in the target area would fall down, instantly dead. Not only that, everything around you and inside you would be killed, so that your sterilized body would not rot for quite a long time.

The Mindsnapper can be used for a small area, or to kill an entire population. In fact, using the scalar waves to affect the human mind has become a new field in its own right, and has been dubbed "psychoenergetics." (This is discussed below in section 5).

Bearden describes the use of the howitzer in mind-snapping mode against people, to cause unconsciousness or death:

> "From a military viewpoint, these scalar EM weapons are really quite all-around weapons.
>
> "For example, they are very lethal against personnel.
>
> "Set in the "high intensity pulse mode," one blast and a person's nervous system is destroyed instantly. Total, instantaneous death results. One can blast away at entire groups of infantrymen, for example. It's the peak power that's important, not the average power. So the weapon doesn't require too much battery power.
>
> "Set on a lower intensity pulse mode, one zap can simply knock out a person, rendering him instantly unconscious. Quite useful if one needs prisoners to interrogate. Also very silent, which is useful in operations employing stealth and surprise." Bearden http://www.cheniere.org/books/ferdelance/s80.htm
>
> "Those hit by the scalar EM weapon, however, have a most peculiar death mode.
>
> "Death comes-instantly and totally. There is no convulsion, no response. The entire nervous system is destroyed instantly. Every living cell in the body is killed instantly, including all bacteria, germs, etc.
>
> "A body hit with this thing falls like a limp rag and lies where it falls. It doesn't decay in even 30-45 days. In a macabre fashion, it's been reduced to something like food irradiated with nuclear radiation; everything is killed, so the material is preserved for an extended period before any decay can set in."
>
> Bearden http://www.cheniere.org/books/ferdelance/s81.htm

He goes on to say that the same "bazooka-sized scalar EM pulse weapon" can also be used to knock out a tank with one shot (or pulse). So tank warfare is obsolete. Helicopters? Bearden points out: "... if he's attacked by a helicopter or a fixed-wing aircraft, he can bring the same weapon to bear on it. He can knock down a chopper or a jet. With one shot."

Obituary for Tank Warfare

Tanks useless against portable LW weapons

> "For example, suppose one attacks a tank. [with an LW weapon] With scalar EM pulse, the personnel die instantly. Total personnel kill is achieved.
>
> All electronic systems of the tank are dudded. Total systems kill is achieved. The ammunition in the tank explodes. Total kill is achieved.
>
> The fuel explodes. This is another total kill mechanism.
>
> That tank has been killed totally, by a variety of mechanisms, all simultaneously.
>
> That's a k-kill in any analyst's book.
>
> And don't worry about retrieval and repair. That tank is finished permanently.
>
> Even the most modern tank is just as vulnerable as the most obsolete."
>
> Bearden http://www.cheniere.org/books/ferdelance/s88.htm

One begins to get the idea how profoundly the conventional means of warfare have been obsoleted. All the usual weapons of war have been rendered nearly useless! And Star Trek's "Phaser," with its "stun" and "kill" modes is here at last.

Although it is the weapons aspect of scalar electromagnetic which has received the most developmental effort, Bearden points out that a great many other amazing things that may be accomplished in this new field of science. Beam me up Scotty!

> "Superluminal communications systems, hyperspace drive, and materialization and dematerialization are all hypothetically possible, using scalar electromagnetics. As the technology develops, we should see the development of many of the systems long thought impossible except in science- fiction."
>
> Bearden http://www.cheniere.org/books/ferdelance/s15.htm

Bearden describes a huge test of the Russian scalar weapons systems which occurred in 1985, a test that went completely unnoticed by western scientists:

> "Just before May 1, 1985 the Soviet Union performed a "full-up" operational test of their entire strategic scalar EM weapons complex. This test was detected and monitored periodically by Frank Golden. Some 27 of these giant Soviet "power taps" were locked into the molten core of the earth, producing forced (entrained) scalar resonance of the entire planet on 54 controlled frequencies under our very feet. The remainder of the scalar frequency spectrum was ablaze with literally hundreds of Soviet scalar transmitters: probably the entire strategic scalar command and control system to

> underwater submarines, higher command centers, distant commands, etc. was activated in the giant exercise.
>
> "For several days, the system was exercised on a mind-boggling scale, apparently as part of the Soviet Union's highly accentuated 40th anniversary celebration of the end of World War II.
>
> "Ironically, not a single U.S. intelligence agency, laboratory, or scientist detected this monstrous exercise for the new Soviet leader, Gorbachev. Not a one of them had a detector for scalar EM radiation, and not a one of them officially believes the exercise ever happened."
>
> Bearden http://www.cheniere.org/books/ferdelance/s38.htm
>
> "The Woodpecker grid/howitzer weapon system can be placed over the ocean and used against cruise missiles, naval surface-to-air and surface-to-surface missiles, submarine-launched ballistic and cruise missiles, etc. Placed over a carrier task force, it can also take care of the aircraft launched by the carrier as fast as they are launched. It can also handily take care of the missiles launched by guided-missile cruisers of the accompanying task force."
>
> (Bearden http://www.cheniere.org/books/ferdelance/s65.htm)

The whole series of the Fer-de-Lance briefing slides and comments is a "must read" for anyone wanting to be aware of the actual state of things in this world right now. It is a new world and it takes some getting used to. Fer-de-Lance speaks clearly, for the layman, of the way things stand.

What is it like to operate these Tesla Howitzers? Col. Bearden gives us an idea in his "Fer-de-Lance" briefing, Slides 66-71.

Who needs armies anymore? A entire war can be fought and won by a handful of men sitting in a comfortable control booth! The scalar electromagnetics revolution has made all previous forms of warfare nearly obsolete.

Why haven't the Russians used the scalar weapons yet?

Bearden gives his thoughts on this in "Fer-de-Lance." The power of these weapons is so great that an accident or war could wipe out all life on earth, and even affect the sun.

> "As can be appreciated, this entire concept [MAD] is now totally obsoleted by the Soviet possession of scalar EM weapons.
>
> 'The "mutual assured destruction" capability -- or MAD concept as it was so aptly named! -- is no longer mutual. And for two reasons: (1) the Soviet surprise attack could destroy essentially all our Triad forces wherever they are, in the first attack. (2) Even if a very small number of our strategic forces survive, the puny strike we could attempt to launch could be repeatedly decimated from launch to terminal phase.

> 'The restraint on the Soviets is not because of our Triad forces. The restraint is twofold: (1) a second nation has scalar EM weapons, and would undoubtedly unleash them upon the Soviet Union with great violence if such a massive world-wide destruction of U.S. forces occurred or was threatened (is it really "accidental" that six major Soviet missile ammunition storage sites mysteriously exploded within seven months?); (2) the closed-loop scalar radiation exchange system of Earth-Sun could be inadvertently "tweaked" in the feedback loop from Earth to Sun, so that a large solar scalar resonance was stimulated. In that case the Sun could emit a mighty resonant "burp" that would simply wipe out all life on Earth in a fiery shower.
>
> 'The "terror" in the "balance of terror" between nations has just increased by many, many orders of magnitude.
>
> 'The biblical prophecy that the Earth will be wiped out by "fire and brimstone from heaven" is very near fulfillment now.
>
> 'Put another way, the pucker factor -- even on the Russians who may contemplate unleashing Armageddon -- is higher than any Western strategic analyst has ever imagined, even in his wildest nightmares.
>
> 'Truly these weapons are "more frightening than the mind of man has imagined," as Brezhnev put it in 1975.
>
> 'The frightening scalar EM weapons can be used, but only very, very gingerly indeed. If a slight mistake is made, everybody loses everything."
>
> Bearden http://www.cheniere.org/books/ferdelance/s74.htm

But the Russians (KGB) are not the worst of it. Bearden claims that some of the scalar weapons have been leased to the Yakuza for about a billion a year, and that only the KGB is holding the Yakuza in check from making a full-scale all out scalar attack on the west.

U.S. Defense Secretary William Cohen

Warns about eco-terrorism using scalar electromagnetic weapons

> "Others [terrorists] are engaging even in an eco-type of terrorism whereby they can alter the climate, set off earthquakes, volcanoes remotely through the use of electromagnetic waves... So there are plenty of ingenious minds out there that are at work finding ways in which they can wreak terror upon other nations...It's real, and that's the reason why we have to intensify our [counter terrorism] efforts." - Defense Secretary William Cohen, 1997
>
> In a letter to a writer named "Russell" Bearden says,
>
> "In short, Russell, the Secretary of Defense of the United States confirmed that there are indeed novel kinds of EM weapons, right now and have been for some time, which have been and are being used to (1) initiate earthquakes, (2) engineer the weather and climate,

> and (3) initiate the eruption of volcanoes. We wrote about those exact uses of the weaponry decades ago. Several nations now have such weapons. Three of them (two on one side and the other on a hostile side) are even firing practice shots into Western Australia, as a convenient test range."
>
> http://www.earthchangestv.com/ufo/0209gandor.htm

Tesla Howitzers in Weather mode

How to Make Weather

> "Engineering the weather is duck soup; they tested that over the U.S. in 1967, and entered upon continuing operations over North America on July 4, 1976 as a grim kind of KGB "Bicentennial Gift" to the United States. Here's how it is done with several interferometers.
>
> "First, the interferometers can deliberately make "high pressure areas" (cool the air so it shrinks and its "footprint" pressure on the ground increases because its density increases) and "low pressure areas" (heat the air so that expands and its "footprint" pressure on the ground decreases because its density decreases). Well, if one makes the highs and lows where one wishes them, and judiciously and somewhat slowly moves them along a given path, these highs and lows will entrain the jet streams and thus "steer" the weather.
>
> "So if you wish a very cold snap or attack, go up into Canada and start these actions to steer down some streams that bring some very frigid air. Establish other highs and lows judiciously to "block" or "slow" other jet streams and flows as desired. In this way, one can pull the "large cold air masses coming down from Canada" deep into the southern U.S. at will. They do it regularly. If you wish an ice storm, add an additional current of warm moist air you bring up (steer up by using artificial highs and lows) from the ocean. Where they meet, you will get freezing rain, then sleet, then severe icing accumulating. This type of attack does rather large damage to the struck area."
>
> http://www.earthchangestv.com/ufo/0209gandor.htm

Whole websites have now sprung up showing weather radar anomalies which may well be indications of scalar weather engineering. One list of over 500 images is here. Cheniere has its own collection here.

In another section at Cheniere are many photos of cloud anomalies which reveal the underlying grid along which the clouds are forming or un-forming. Bearden relates a startling incident in these clandestine ongoing "weather wars."

> "During the spring of 1986, abnormally strong Soviet weather engineering occurred over the U. S., causing a drastic drought in the southeastern U.S. This drought was broken by a colleague who used an extremely powerful scalar EM device to redirect jetstreams. A most unusual and unique signature of the "blocking" against the Soviet scalar EM actions

resulted: Two huge circulations developed in the atmosphere, clearly showed as two adjacent giant "holes" in the swirling cloud cover over the middle and eastern U.S.

"Between these two giant holes, the cloud circulations formed a stream of clouds, moving to the south, looking very: much like a giant vertical "bar" of a huge "Y-shaped" cloud flow.* Several national weathermen commented on this unusual pattern, which had not been observed before. The pattern continued, day after day, as the blocking continued."

* On the weather maps.

http://www.cheniere.org/books/analysis/history.htm

Tesla Howitzers in Earthquake mode

How to Make an Earthquake

"Here's how you initiate a very large earthquake with such weapons. Take a convenient fault zone of set of them. Focus the interferometry on the fault zone, in the "diverging" mode, and deposit EM energy there in the rocks on both sides, increasing (slowly) the stress in the rocks by the reverse piezoelectric effect (deposit excess energy, get crystal mechanical movements).

"Do it slowly, and the stress will build up to large pressures well-above a plate slip minimum energy required. At some point, the rocks yield and one or both sides "slip" and move rather sharply, giving a very large earthquake in that zone.

"Do the same thing down in the earth (remember, LWs easily penetrate right through the earth and ocean at will, and so the "interference zone" focus can be inside the earth or beneath the ocean, at will.

"Anyway, focus this thing down to where the active part of the volcano is still slumbering, down where the hole in the plate has been made. Keep increasing the deposition of energy in the magma itself, and eventually the increasing pressure from deep within that volcano, underground, will cause an eruption. Build the energy slow, and the eruption will likely be much larger."

http://www.earthchangestv.com/ufo/0209gandor.htm

Yugoslav Earthquake, Followed by Cold Explosion

Strange Characteristics of Iran Quake, Sep. 1978

Tesla Howitzers in Tesla's "Big Eye" mode

How to make a Big Eye in the Sky

By using longitudinal wave interferometry in a weakly endothermic mode a new kind of "radar" is now possible, one which can look right through the earth and oceans. Because the endothermic mode extracts energy from the distant target, a pattern of the target area can be scanned for in the returned energy.

> "Thus the receiver produces a representation of the energy extracted from various locations within the distant endothermic zone. By displaying the received signals on an appropriately scanned screen, a representation of the distant scene in the intersection zone can be created. Indeed this is a special kind of "microwave interferometry," and -- with modern techniques -- the imagery obtained might be surprisingly good. With development, it might even become as good as the image presently obtained by side-looking acquisition radars.
>
> "Interestingly enough, since scalar EM beams will easily penetrate the earth or the ocean, one can also look beneath the earth or beneath the ocean with this type of scanning scalar interferometer.
>
> "The importance of this capability to strategic and tactical reconnaissance is obvious. Camouflage, cover, and concealment have no effect on such a system. One can easily look inside buildings and into underground facilities. With a small system such as this, the U.S. Marines at Khe Sahn would have had little difficulty locating the tunnels continually dug under the perimeter by the Viet Cong. And targets under jungle canopies are directly visible."
>
> Bearden http://www.cheniere.org/books/ferdelance/s42.htm

Tesla Howitzers can destroy all life on earth

How to Make a Storm on the Sun!!

(Just make a big mistake with your Tesla howitzers)

The deepest dangers of the use of scalar weapons are frighteningly pointed out by Bearden here where he considers that the sun, earth and moon (actually the whole solar system) is a delicately balanced arrangement of scalar (longitudinal) EM radiation. There is a scalar connection between the earth and the sun, which are both giant dipoles gushing energy in the time domain. Big scalar events on the earth could alter this balance causing true catastrophe.

"Indeed, a solar response could be stimulated so that the Sun would violently belch and destroy our biosphere, among other effects."

Unrestrained scalar warfare could cause huge solar storms? To realize that human activity could actually affect the sun itself is truly mind boggling.

Bearden goes on to say:

> "Accordingly, use of huge scalar EM weapons is a double-edged sword. Unless carefully employed, use of the weapons could cause a terrible backlash to the user as well as the victim, and even accidentally cause the destruction of the earth itself. It is not accidental

that in 1960 Khrushchev stated that his new fantastic weapon could -- if unrestrainedly used -- destroy all life on earth.

"This appalling backlash potential is apparently what prompted Brezhnev in 1975 to make so strong an effort to get agreement to outlaw the development of "new weapons of mass destruction" more frightful than the mind of man had even dreamed of. Gromyko even introduced such a draft agreement into the proceedings of the United Nations. The first article of the draft agreement indicated that the nature of the weapons referred to would be negotiated. Sadly, the entire Western world did not even know what the Russians were talking about."

http://www.cheniere.org/books/ferdelance/s24.htm



3b. Tesla domes provide near-perfect defense shield.

(Slide from Cheniere.org)

The Tesla howitzers can be used in a nearly impregnable defensive mode whereby they throw up a dome (**Tesla Dome**) or a sphere (**Tesla Globe**) of highly powerful electromagnetic energy, enough to "dud" or destroy missiles which try to penetrate them. Once again, this energy is not going through space from the howitzer, but being made to emerge from the local vacuum at the location of the shell. KGB tests of these domes have been witnessed by airline pilots around the world. Bearden gives many examples of the Tesla domes being sighted around the world in his briefing paper "Fer-de-Lance." (Russian dome test, another globe incident, yet another globe test). These giant electromagnetic domes can be hundreds of miles across, or narrowed down more to total impermeability.

> "Such a shell may be several hundred miles in diameter at the base. The enormous energy required to form such a defense shell is obtained by a "scalar power tap" into the molten core of the earth itself, as previously explained. In late April/early May of 1985, 27 such "power taps" were placed in the earth by the Soviets. If each tap is capable of powering four to six large scalar EM weapons, then the Soviet strategic scalar EM arsenal contains over 100 monstrous superweapons capable of generating exothermic explosions, endothermic explosions, engineering the weather, locating and destroying underwater submarines, detecting and destroying ballistic missiles shortly after launch, detecting and destroying long range strategic bombers as soon as they are airborne, etc."
>
> http://www.cheniere.org/books/ferdelance/s52.htm

By using nested domes one can protect the domed area even against nuclear radiation itself. Tesla globes can be used to hit airborne targets by simply placing a globe of any chosen size in the flight path of the incoming missile. It does double duty because the missile hits it going in, and then the rubble hits it again going out the other side.

While the U.S. persists in its useless boondoggle "missile defense system" by shooting a missile with a missile (missiles which would already have been "dudded" by the Tesla howitzers), between the domes and the globes the Russians (KGB) have in hand (operational) a nearly perfect missile defense system. Someone should ask the Secretary of Defense if the U.S. Tesla domes are in place. And over which cities? How powerful are our American Tesla domes?

Bearden cites a number of examples of these domes being tested around the world:

March 20, 1969 | March 24, 1977 | August 17, 1980 | June 17, 1966 | June 18, 1982 | June 22, 1976

In a slide from the Fer-de-Lance briefing it is shown how the "woodpecker grid" itself also acts as a sensor, detecting any missile launch anywhere, and how the howitzers can respond instantly by delivering a blast to exactly the right coordinates, right along the channels of that same grid which is feeding the location information about the missile launch. This certainly beats "trying to hit a bullet with a bullet." Especially since YOUR bullet would probably be instantly inoperable in a real scalar war situation.

3c. Rogue Groups in the government

Bearden fears that these scalar electromagnetic secrets may have fallen into the hands of what he called secret "rogue groups" within the labyrinthine depths of the black-ops special-access domain of the secret government. "In the extreme, such a deep black program can even become a "captured" program," he says, "which is totally in the hands of rogues and no longer reports to or is bound by the dictates of the parent government."

> "They have their own agendas. And being rogue groups, they may well bring in unethical, immoral tricks: assassination, bribery, entrapment, disinformation, plausible deniability, etc. A certain percentage of a highly secret rogue group will wind up using all these things and more. It's a human characteristic, the old primate dominance game. Only now disguised and hidden under deep classification. ...
>
> "In highly classified groups, these groups are greatly enabled to joust more widely, unethically, and immorally because it is so deeply hidden. So very deep classification evokes the growth and intensity of rogue groups. It's the old 'Power corrupts, and absolute power corrupts absolutely' routine. ... Due to loose formation of rogue groups inside such programs, they may have dual or triple purposes, may not operate under very much legitimate government control at all, and may operate specifically for the purposes of the rogue group or groups that have gained control."
>
> "The involvement of at least some rogue groups, some being "cowboys" who operate well outside all laws and ethics, could also result in such things as assassinations, clandestine testing on individuals without their consent, etc. In short, it could account for what seems to be actually occurring. "
>
> http://www.cheniere.org/explore%20articles/mind%20control3/p05.htm

3d. World War III has already begun

Because it is now possible to cripple the power grids and electronics of any nation, that nation could be reduced to economic ruin without ever firing an actual "shot." Without electricity Wall Street cannot operate. Without electricity you quickly need martial law. One no longer needs to wage a conventional war anymore at all. There are now lots of new ways to bring any nation to its knees.

> "We are at war, whether we like it or not. And we are going to have strategic strikes on an unparalleled scale for us. Pearl Harbor was nothing compared to what is coming down, once we consider the "augmentation" and such.
>
> "When that factor is considered, then it's a totally new ball game on replacing the power system. There isn't going to be much choice; the old one is going to be destroyed or so badly crippled that it will collapse the U.S. economy in a way we have not seen since 1929. Of course, in such a case hitting us, we will be under martial law, the works, everywhere. For one thing, it's the only way you can keep the cities from imploding from within, by the criminal element, looting, robbing, killing, etc. Simply wait and see; it's on the way."

> Although Bearden has for years decried the "scalar-gap," and chided the military for falling so far behind the Russian KGB in the field of scalar electromagnetics, recent statements indicate that things may at last have changed somewhat.
>
> "In the new war, the first phase of WW III has already been completed. Hence President Bush's recognition that this is a total war, and has to be taken to the enemy no matter where he may be hiding or in what sanctuary or in what foreign nation. This is an entirely different war than anything the U.S. has ever fought in its history. And before it is over, it is going to kill more Americans than have died in all the previous wars in our history. The news media and the public have not yet recognized that awful situation and predicament. Most are already thinking that, well, we won in Afghanistan so it's just about over. Instead, it has only just begun.
>
> "Anyway, that's a brief uptake on some of the weapon situation today. Some 10 nations or more now have LWIs, and five have the QPs. I'm still working on how many have the appalling negative EMP weapons, but would estimate 6 or 7 nations have them in one stage or the other, either deployed or in at least advanced development. And in my estimation, the Yakuza will have them within three to five years if they have to build them themselves, and quicker if they can buy them from the Russians, Chinese, or???"
>
> Bearden http://www.cheniere.org/correspondence/030202a.htm

When he was asked the question '**Does the government listen to Tom Bearden?**" Bearden said:

> "Let me speak carefully. I am very satisfied with how I've been listened to in the quarters where the rubber meets the road. The West is no longer defenseless, not by any means. Cannot amplify it further than that."
>
> http://www.cheniere.org/correspondence/030202a.htm

Bearden has briefed the government a number of times and the Cheniere website contains a great number of his graphic military briefing slides.

3e. Are the Russians making "UFOs?"

Scalar electromagnetics engineering opens the possibility of antigravity vehicles and "hyperspace travel." In other words we can now make our own UFO's! Of such scalar-powered antigravity vehicles, which have now become possible, Bearden has this to say:

> "We might expect to see such vehicles glowing. Their various surface features and mechanisms might appear to be glowing or revolving lights, etc.
>
> "They could exhibit incredible "aerodynamic performance," seemingly in the atmosphere. Actually they would not be moving "through" the atmosphere at all, but through a higher space outside each particle of atmosphere.

> "They could seem to materialize and dematerialize.
>
> "They could seem to plunge into the ocean or rise out of it.
>
> "They could even seem to operate under the ocean or inside the earth itself.
>
> "Such anomalous vehicle performances have been seen all over the world, particularly since a few years after WWII.
>
> "It appears that one or more nations of Earth are operating such vehicles now in great secrecy. Our own "government" may even be one of these.
>
> "If so, it isn't our true "government/government." Instead, it's the "control group/government." It's government at the operational level, but at higher level it belongs to certain control groups who have penetrated our government's vitals and taken over all such projects."
>
> Bearden http://www.cheniere.org/books/ferdelance/slide32.htm

In an excellent article on her Earthfiles website, Linda Moulton Howe reports on the utter bafflement of Norwegian scientists over mysterious lights appearing in the valley of Hessdalen, Norway.

She writes of the research there: "The results can be broken down into two groups: 95% are thermal plasmas and 5% are unidentified solid objects. The plasmas emit long wave radio frequencies and strangely, their temperatures do not vary with change in size or brightness." She quotes the scientists' research summary:

> "1) most of the luminous phenomenon is a thermal plasma;
>
> 2) the light-balls are not single objects but are constituted of many small components which are vibrating around a common barycenter;
>
> 3) the light-balls are able to eject smaller light-balls;
>
> 4) the light-balls change shape all the time;
>
> 5) the luminosity increase of the light balls is due to the increase of the radiating area. But the cause, and the physical mechanism with which radiation is emitted, is currently unknown."

This would almost certainly seem to be another example of the testing of the scalar howitzers. It is baffling because, as Bearden points out repeatedly, Western scientists have limited knowledge of the scalar electromagnetic principles by which the howitzers operate. The Hessdalen scientists were completely baffled as to where the energy of these plasma balls was coming from.

Ms. Howe interviews Massimo Teodorani, Ph.D., Astrophysicist, who released the report on the 2001 Hessdalen sightings. The scientist speaks of the baffling phenomenon observed.

> "I don't know how it is possible that Nature is spontaneously able to do that. Anyway, we deduce that the plasma is trapped inside a sort of magnetic cage and the magnetic cage closes around the plasma and keeps it fixed in some way, prevents it from expanding. But where does it come from? We don't know."

By what we have been considering here, we can recognize the signatures of scalar electromagnetic engineering. If it is a Tesla howitzer, then the energy for the plasma balls is coming from the vacuum of spacetime at the very location of the balls themselves, triggered by scalar interferometers aimed through the woodpecker grid.

These kind of balls can be used as marker beacons giving feedback for precision aiming of the howitzers. The energy of the marker beacon can be read back into the computers giving precise location information for pinpoint aiming. The target area can be very small, or widened out.

There is a little movie of one of the Hessdalen plasma balls here. It would seem to be a clear documentation of a scalar howitzer marker-beacon. How many other current "UFO" sightings are actually the witnessing of Tesla howitzer tests?

In fact there are a great many anomalous events of the past few decades which might very well be explained by the Russian testing of their longitudinal electromagnetic weapons. It would seem that the mysterious appearance of crop circles around the world could be accomplished by feeding a precise mathematical graphic pattern into the computerized aiming software and change the very molecular structure of the crops themselves along the lines of that pattern. The

stalks fall over from the localized effect of the longitudinal waves. A plasma ball tracing patterns? Are they slyly sending a message to see if we are "getting it" yet?

The "Cambridge Angel" - Made by Russian scalar plasma balls?

Also see: Interview with Tom Bearden



Attempt to Ban Energetics Weapons Worldwide

- On June 13, 1975, in a major speech Brezhnev urged the United States to agree on a ban of research and development of new kinds of weapons "more terrible than anything the world has known."
- On July 2, 1975 Brezhnev repeated his proposed ban on development of frightful new weapons, to a group of U.S. Senators.
- In August 1975, Ponomarev called for a ban on frightful new weapons of mass destruction.
- On Sept. 23, 1975 Gromyko presented a draft treaty agreement to the 30th Session of the UN General Assembly, for banning development of frightful new weapons.
- *No one had the foggiest notion what the Russians were talking about!*

© 1996 T E BEARDEN

(Slide from Cheniere.org)

4. Healing powers of longitudinal waves

Healing via longitudinal waves, time reversal of cells (de-differentiation), Priore's machine, Bearden’s proposed "blanket" version, using the electric power grid for healing waves or for broadcasting disease patterns. Scalar Biowar.

The good news!

> "Any sort of disease whatsoever - physical or mental - will be rapidly curable, simply and cheaply. It will be possible to reverse aging and rejuvenate the person. It will be possible to regrow limbs and straighten misshapen spines - and directly remove the causes of mental diseases and cure them as well. Lifespan will be staggeringly increased, without 'old age's debilitation.' AIDS, cancer, leukemia, and genetic diseases will be completely conquered. The potential for a true golden era is upon us, for all humanity."
>
> Bearden- http://twm.co.nz/beard_interview.htm

Proof of the healing powers of longitudinal waves from the vacuum is seen in the work of Antoine Priore who produced longitudinal scalar waves using a gigantic glass tube filled with plasma. He himself did not understand why it worked or how it cured cancer in animals.

> "The Priore team cured terminal tumors, trypanosomias, and other dread diseases in laboratory animals in France, in the 1960s and 1970s, under rigorous scientific protocols by eminent scientists. The Priore project was funded by the French Government to the tune of several millions of dollars (equivalent).
> http://www.explorepub.com/articles/energetics.html
>
> ". . . Prioré's machines concretely demonstrated a nearly 100% cure of all kinds of terminal cancers and leukemias, in thousands of rigorous laboratory tests with animals. These results were shown to medical scientists as early as 1960." http://www.cheniere.org/priore/index.html

Bearden has stated that the longitudinal EM waves can have a healing effect because they always come in pairs called "phase conjugate pairs" and one of the pair is time-reversed. This enables engineering of the waves to "pump" the cells of the body (with waves from the time domain) and actually time-reverse the cells back to a previous healthy condition. The scalar cure of cancer does not involve killing the cancer cells but rather pumping them with time energy into a previous condition. I know, this seems miraculous, and is it not?

Priore and his giant plasma tube

This healing power in the longitudinal waves of the time domain is a mind-boggling thing to face. It took me months to get through it, and to suffer the fact that the cure for cancer and AIDS was right there, in this new scalar electromagnetics technology, and that it has been kept back from the people for so many decades now.

Bearden has a great deal to say about the work of Priore, who himself did not understand why his machine worked. Priore did not know about the longitudinal scalar waves of the time domain. In fact, Tom Bearden has supplied, at last, the missing explanation as to how that big giant two-story glass tube consistently cured cancer in animals.

"**The medical implications are enormous**. By just reversing the damaged cells back to a previous physical state, this gives a physics mechanism for controlled cellular dedifferentiation, in biology terms. Physicians will time-reverse diseased, damaged or aged cells back to an earlier healthy condition, including all the cellular genetics. Normal cells are just reversed to a slightly younger condition."

> "We believe this mechanism explains the revolutionary but baffling electromagnetic cures achieved by a team of outstanding French scientists in the 1960s and early 70s, working with inventor Antoine Prioré. In lab animals, cures were achieved for terminal tumors, infectious diseases such as trypanosomiasis, and atheriosclerosis. In addition, deliberately suppressed immune systems were dramatically restored.
>
> "We hypothesize that this is the long-sought mechanism of how the living body heals itself. In short, the body's cellular control system induces cellular reversal by weak time-domain pumping of the damaged cells and the affected area. The cellular regeneration system performs all healing of cellular damage in the body; the immune system heals nothing, not even its own damaged cells) .
>
> "For the first time medical science can develop as a science of healing rather than a science of intervention. And it will develop as a science of unlimited healing, since no pathogen can resist action by curved spacetime engines." Bearden
>
> http://www.cheniere.org/techpapers/Vision%202000%20paper.doc

See Priore's machine See Slides of how it works.

Bearden has extended the Priore work, with the previously missing knowledge now in place, and designed a revised system (for irradiating the body with longitudinal waves) which gets rid of Priore's giant glass plasma tube and uses instead an antenna unit which surrounds the body. He has also provided the missing explanation of how it works. There is an article from "Explore" magazine, Part I and Part II.

In fact, Bearden has presented to the U.S. government a plan to use a portable version of a Scalar Healing Blanket where wire channels in the blanket act as a scalar antenna, which can both send and receive scalar electromagnetic waves. A two minute treatment of the waves is sufficient to restore the body to its earlier healthy condition. Thus even thousands could be treated easily and quickly in a biowar mass attack situation.


RETRORADIATION WITH EMITTED TW EM WAVES
Recorders & Broadband Amps
Broadband Antenna Unit
Control Unit
Receiver-transmitters
© T. E. BEARDEN 1998
Adjusting broadband signals bandwidth and amplification
Using an amplified replica of the body's own dense, broadband signal complex to irradiate it, producing deeply-penetrating and precise longitudinal EM wave sets that pump cells and reverse cellular disease and damage

"To defend against things like anthrax attacks on our civilian population centers, we also have recommended to the U.S. Government the crash development of small, portable treatment machines—using similar "antiengine-forming" and cellular reversing "porthole technology". [See Figure 13 on previous page]. Such portable machines could be developed cheaply and quickly, and present government facilities could be used to massively attack the correlate database production problem. "The portable treatment units could be cranked out by the hundreds of thousands and flooded down through emergency response agencies such as the police forces, the National Guard, emergency hospitals,


Portable Priore-Type Treatment System
Equipment Case
Computer Control Unit
Infolding Function Generator

> emergency response teams, etc."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control3/p04.htm

The Scalar Healing Blanket would fit into large suitcase. It has three basic parts, the longitudinal wave generator, a laptop computer, and the antenna-blanket. The plan was a stroke of Bearden's genius, but unfortunately it fell on befuddled government ears. "Unfortunately, so far the DOD [Dept. of Defense] doesn't even understand what the heck we're talking about!"

Article "**Healing with Energy**": http://www.explorepub.com/articles/energetics.html

> "We tried very hard in 1998 to call attention to the extreme national need for the most urgent possible development of a portable computer-controlled treatment device based on the experimentally proven Prioré methodology, but extended to a much simpler and far more rapid method of treatment.
>
> "Quick development of this technology could lead to a suitcase size device, capable of treating a patient in less than one minute, and stopping the symptoms and disease progress cold, then reversing it. Three "less than a minute" treatments one week apart would be required for complete cure. As an added advantage, partial reversal of aging in older patients would also be accomplished as a bonus, in addition to time-reversing the damaged and diseased cells...
>
> "The method proposed to the DoD in 1998 used normal EM in a peculiar way to force the body itself to make its own time-polarized EM waves, and pump every part of its cells -- including the genetics -- in the time domain.
>
> "Quite simply, we are going to be struck this way (QP spreading the immune systems of the populace plus professional smallpox, anthrax, etc. BW attacks on our population centers) and by other means we've spoken of in other papers and briefings."
>
> Bearden http://www.cheniere.org/correspondence/021401.htm

The Dark Side of the Force:
Creating and broadcasting disease

Speaking of the scalar wave induction of disease by longitudinal wave patterns Bearden refers to work by French scientist Kervran Russian scientist Kaznacheyev, who proved that any disease could be transmitted electromagnetically.

> "It works this way: the Kaznacheyev experiments (and others) demonstrated that any cellular disease or disorder can be initiated into cells at a distance, by electromagnetic means (albeit unusual EM in nature). The decades of microwave radiation of the U.S. Embassy in Moscow, was an ongoing set of "stimuli" to ping the U.S. system and, by its response, ascertain how far along (or if it was "along") in its knowledge of such weapons. The radiation was responsible for many health changes in personnel and for the eventual deaths of three U.S. Ambassadors."

> Bearden http://www.cheniere.org/correspondence/021702a.htm

In a letter he writes,

> "Yes, the Kaznacheyev experiments were quite real; 15,000 or so in military research institutes in Siberia. As with so many other novel areas investigated and developed by the Soviets, most U.S. investigators just assumed normal EM, which is not what the Kaznacheyev experiments involved, and not what was carrying disease induction patterns from one cell culture to another in rigorous lab tests."

How to "Broadcast" Diseases

Longitudinal EM Biowars

Bearden explains how the new quantum potential weapons can be used to induce disease-at-a-distance in a population, or to "spread" the immune system so thin that a conventional bio-attack would be greatly potentiated. By "broadcasting" virtual disease patterns over a population, the immune system is so overloaded by the presence of the "shadow" diseases that its effectiveness is thinned out.

> "In short, alter the internal wavestructure, and one creates a curved spacetime 'engine' that acts on mass in any fashion one chooses to design -- including initiate diseases . . . Now visualize one of these 'vacuum engines' or 'spacetime curvature engines' that acts on mass to generate the exact effects produced by anthrax. (Or any other disease one wishes) . . . Call the virtual state of a disease engine the disease pattern in the "shadow" state, just prior to becoming observable. . . .
>
> "And the master cellular control system responds to "coming events that cast their shadows before". In short, it responds to the upper level of the "shadow state" of a disease, still in the virtual state! (Hey, virtual particles are real, virtual photons are real, virtual ST curvatures are real --- just very fleeting, only for another to immediately arise). The exchange of virtual particles is known to generate all forces in physics anyway! . . .
>
> "So the cellular control system responds to "shadow state" disease patterns. Enter a QP weapon application. Place a quantum potential weapon "area" on the United States, so that the entire populace is in it. The slowly introduce and bring up in the shadow state, the necrotizing fasciitis disease engine. At some point, the cellular control systems will react, and order the immune system into action. In other words, immune system resources will be committed against this "immediately coming" enemy. Bring it on up a little, but still just in the shadow state. Voila! Humans form a bell-shaped distribution curve. And even if the structure of the QP fluctuates a little, fluctuating a bit stronger and a bit weaker, etc. A few of those targeted bodies will now actually develop necrotizing fasciitis. So far, just like the U.S. Embassy targeting, except a different "carrier".
>
> "But now there is an exact signature that this is what is doing it, and not normal vector carriers of disease and contact or exposure infection. The few cases of necrotizing fasciitis that break out will be most puzzling. They will be randomly scattered across the

> entire nation, and so few that the vector carrier and contact or exposure explanation completely fails."
>
> "And that one happened, right here in the U.S., not so long ago. Check it out.
>
> "So carefully adjust the patterns for, say, 12 major terrible diseases, to that "adjusted and desired shadow state level". Now add all 12 patterns into the internal structure of the quantum potential. Now it has 12 shadow state disease engines in it.
>
> "Place that one on a populace. The cellular control systems order the immune systems into action, and they now have to commit their finite resources to 12 different areas. This greatly thins the response an immune system can make to any one of those 12 disease patterns! In short, it "spreads" the capabilities of the immune system, which can be galvanized to great effort, but only can perform a small bit against each area.
>
> "Suppose one of those "galvanized" areas in the targeted populace's immune systems is anthrax. And suppose the bad guys now hit one or more of those cities with a professional anthrax attack. A former OTA study showed that a professional anthrax aerial spray attack against Washington D.C., dispensing 100 kilograms of anthrax spores in the spray, will account for 1 to 3 million casualties. And that's in an "unthinned" set of immune systems. In the "thinned" set, one can at least double or triple, and even up to five times, that estimate. So conservatively, now there would be from 2 to 6 million casualties. And even mild anthrax spray attacks in other "thinned" cities would also be amplified.
>
> "That one is being set up, or already set up, right now. There are other such "augmentation" setups also under way.
>
> "So the weapons alluded to by the SecDef in 1997 are already being employed. WW III has already begun, and our populace (and our scientific community) is blissfully unaware of it."
>
> http://www.cheniere.org/correspondence/021702a.htm

Most of us can remember the strange outbreaks of the so-called "flesh eating disease." It seemed to break out here and there randomly with no known cause. Bearden believes this was a test of the newer quantum potential weapons which go even beyond the capabilities of the Tesla howitzers.

> "The Kaznacheyev "disease induction by novel electrodynamics" work is also the basis for the spacetime curvature engines (not EM signals!) carried by quantum potential EM biological weapons for distant induction of diseases etc. into the population of an entire nation or area, such as the U.S.
>
> "This quantum potential disease induction weapon -- capable of attacking an entire population of a nation or area -- has been tested several times in the U.S. at very low levels, in the shadow state only (we explain shortly) and it has a most peculiar signature. E.g., one test used necrotizing fasciitis (flesh-rotting disease) engines.

> "The disease 'engine' was deliberately kept down in the 'shadow state' (virtual state, just below the observable state) so that only a tiny bit of the populace with depressed thresholds would "breach the observable threshold' due to the population forming a bell-shaped curve as to the threshold level. The major signature of the test was that the cases of the disease broke out totally statistically and randomly, spread all over, without any 'disease vector' in between.
>
> "In short, it was not spread in any manner required by normal deterministic disease vectoring, but was a totally random set of occurrences. Several other diseases were also tested this way in the American populace, with precisely the same signature."
>
> Bearden http://www.cheniere.org/correspondence/021401.htm

"Apparently one planned use of such an augmented clandestine BW weapon will be smallpox, e.g. As you know, the Russians did develop smallpox for biological warfare, and even developed a new strain against which previous vaccination is ineffective.

> "The vast numbers of expected casualties, coupled with immune system spreading, are absolutely irresistible to the Russian mind. You can count on it that they have seen that the smallpox is already on site here, in the U.S. and in the hands of professional terrorist teams. Of course, the Russians/KGB will protest they have nothing to do with that! Yet likely the KGB will have flatly arranged it or at least assisted it. The capability for mass destruction of the nation is so lucrative and easy to achieve in advance, that they would never be able to resist doing it."
>
> Bearden http://www.cheniere.org/correspondence/021401.htm

Bearden believes the Gulf War Syndrome involved the use of scalar technology to induce a disease state, as he stated in a 1997 interview:

> "I'll say this flatly, and I won't answer any further questions about it; the Gulf War Syndrome was induced... It was induced with this stuff. All the rest... was contributing factors that everybody's talking about... There are some deeper signatures, if you look into it very deeply, that show you exactly how it was done and the fact that it was induced. It was a test. It was a test of a very special kind of weapon I have not talked about yet. Anyway you can use it to create diseases."
>
> Bearden http://twm.co.nz/beard_weapon.htm

Besides using the woodpecker grid to target a population, the entire electrical grids of nations can be used as "channels" for disease patterns to be broadcast to all people near that grid. Your own house wiring can become an antenna, broadcasting these "shadow" patterns of disease, weakening your immune system.

And here one faces the frustrating fact that the same power grids could be set to channel patterns which would keep the entire population healthy, rejuvenated, continuously bathing in the time-reversing old-age-defying energy of the spacetime vacuum. We have no idea yet of how long the human life span could be increased with this new technology. People might be able to live two centuries given full humane development of this technology.

5. Psychoenergetics

Mental entrainment, inducing hypnogogic trance, mind control, broadcasting thoughts and feelings, the Ant World, education via EM [LW] mental download, the "Feelies," revolution in spirituality, "enlightenment machine?" Scalar churches?

Psychoenergetics is simply using the scalar interferometers to manipulate and engineer the human psyche. To me it is the most mind-boggling and frightening aspect of longitudinal wave engineering.

The mind is electromagnetic in nature, and itself of the time-domain. It is not observable in 3-space. There is no thing you can point to that is the mind. As Bearden says**, "The mind is time-like**."

The longitudinal scalar EM waves are also of the time-domain. By overlaying certain infolded patterns (oscillations in time) on the longitudinal waves, a thought or feeling may be made to arise in a person or persons who are in the **interference zone** (where the wave beams cross).

The person will not notice anything, feeling that this thought or idea is his or her own idea. The longitudinal wave pattern might be a wave of panic or fear that spontaneously sweeps over you, perhaps inexplicably. It could even be in the form of a sudden intense patriotism. It could be explicit words and phrases, which everyone would think they had thought of by themselves. Or it could be rage and hatred, angry and violent. On the other hand It could also be a continuous sense of docility and placidity. This is the brave new world of psychoenergetics and the coming "Mind Wars."

Scalar Psychoenergetics in its most primitive form simply "entrains" all minds in the target area into a deep hypnogogic trance. In this state of mind people would be suddenly extremely suggestible, and would likely believe anything they are told, and would obey any orders given. Talk about winning the hearts and minds of the American People!

Tom Bearden makes me think of **Paul Revere**, who heroically conveyed important warnings for the sake of the new nation. But the words of the famous phrase have now strangely and curiously mutated into the once-inconceivable: '**One if by land, Two if by mind**."

Indeed one strategy in a Mind War would be to simply take over the minds of the "leaders" of the enemy nation. The targeted leader would not be aware that anything was amiss, although he might begin to make unexpected changes in policy.

And are, in fact, any of our "leaders" already having secret thoughts that are not their own? Who knows? Frighteningly, we can no longer be sure. The new sciences of scalar electromagnetics and psychoenergetics are even now plunging humanity into a sudden science-fiction-like world beyond anything in humanity's previous imaginings.

> "The Russians reached the point in the mid 1990s that they could take over control of a person's mind, with modified longitudinal EM waves including some time-polarized EM waves, and with a team of specialists (estimate 25-30 per transmitter, and one transmitter and team per controlled person)." Bearden http://www.cheniere.org/misc/time.htm

In a slide Bearden illustrates how a Scalar War would involve a psychoenergetics attack on the operators of the enemy scalar installation, entraining their minds into hypnogogic trance and getting them to shut down their systems.

And ultimately psychoenergetic warfare goes to the very heart of human identity itself. For if my thoughts might no longer be "mine," then who and what am I? Can my very sense of being "me" be hijacked by some nefarious psychoenergetic scheme? Will the "secret government" eventually dictate directly into your mind how you feel about yourself? Or what you think you are? Or what you should do?

How Does Longitudinal EM Mind Control Work?

The physics of scalar psychoenergetics as expounded by Col. Bearden seems even more arcane and over-my-head than that of extracting energy from the vacuum. I can't understand it, but I look through it anyway. Each time another tiny understanding might occur, or a term might fall into place. I know the mathematics is forever beyond me.

One paper to begin with is “Mind Control and EM Wave Polarization Transductions” This is such serious stuff that Bearden includes a strong warning about misuse of this knowledge. Psychoenergetics weapons can mentally maim and physically kill.

Warning!

(From "Mind Control and EM Wave Polarization Transductions")

> "This article refers to experimental research techniques which can be detrimental or lethal in the hands of any but highly skilled, qualified experimental scientists proceeding under proper laboratory safety procedures. The purpose of this article is strictly for information to properly qualified and authorized scientists in certified laboratories. We do not propose or condone any use of these procedures for nonapproved practice of medicine without a license. Neither the publisher nor the author are responsible for accidents or outcomes in the use of these experimental procedures and techniques. Any researcher who performs these procedures and experiments is acting on his or her own volition, and is solely responsible for insuring safety, qualifications, and legality of the acts and their results. We neither suggest nor condone unauthorized experimentation on human subjects. Such is a criminal violation of the constitutional rights of the subject under Federal and State laws, and is both illegal and immoral."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control1/p01.htm

After the serious warning comes the description of the paper. This is heady stuff for the layman.

> "Calling full attention to the special note above, in this paper we present a high-level overview of the novel electromagnetic nature of mind operations, mind and body coupling, and intent - the induction of physical 3-space EM energy changes into the brain and nervous system, and into every cell of the body, from the mind's time-like coherent operations. We summarize the time-polarized electrodynamics used to engineer and affect mind operations and the mind-body coupling loop. Transaction mechanisms whereby differing EM wave polarization's can be transformed one-into-the-other are presented."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control1/p01.htm

I will leave it to the technically astute to try to understand the mechanisms of operation which are described in scientific language. But there are tidbits for the layman. Here he speaks of the difficulty Western scientists have in opening up to the "immaterial" (longitudinal wave) nature of the human mind.

Western Science Remains Largely Materialistic

> "Ironically, most Western scientists are materialists and consider "mind" as a mystical and nonscientific concept. They tend to consider mind operations and functions either to be simply "meat computer" operations and functions, or at best to be very weak ordinary transverse-wave EM operations and functions in the brain and nervous system. This serious self-limitation exists because in the body we measure only weak TW [transverse wave] EM operations and functions correlated to biological behavior and brain operations. We simply do not know how to measure "mind operations" directly.
>
> "With no mind measurements possible and no instruments, it is understandable that Western science considers only the physical side of the mind-matter interface.
>
> "Presently our scientists do not measure the longitudinally-polarized EM wave operations and functions in the body and around it in nature. Few of them are aware that a maelstrom of such LW [longitudinal wave] functions exist in the body and in all of nature in general."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control1/p05.htm

Western methods of influencing the mind with EM waves have only used transverse waves, not the longitudinal waves of the vacuum. If only transverse waves are used one pretty well has to hit the target mind with a sledgehammer of waves.

Western Science knows only transverse EM waves

Brute Forcing Time Functions versus Fine Control Methods

> "Ironically, Western mind control researchers using transverse EM waves for mind control research, are using a brute force method of evoking and using vacuum engines

> (spacetime curvature engines) and a special form of general relativity, although they do not appear to realize it.
>
> "While KGB scientists also use TW EM "brute force" TW waves when necessary, they do "imprint" or "activate" those waves with the desired internal LW and time-polarized EM wave and photon structures required to directly perform the mind engineering desired... Bearden
>
> "These "fitted brute-force models" certainly can be very powerful, and certainly can produce the exact results shown in the experimental verifications of the fittings. However, they do not of themselves allow sophisticated design for example of the necessary time-polarized wave assemblies for engineering the entire human collective unconscious simultaneously, or for engineering the entire collective unconscious of all species on Earth (i.e., Gail's collective unconscious), or even for precisely engineering the memory and knowledge base of an individual.
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control1/p09.htm

The seemingly magical operations of psychoenergetics, sometimes called "psychotronics," cannot be achieved with ordinary transverse EM wave energy. But they are possible with longitudinal scalar waves because the mind itself is scalar in nature.

> "We note that all mind operations are time-like, i.e., they are comprised as scalar EM photon functions and scalar EM wave functions. Thus the mind is a very special kind of electromagnetic system, existing in the time domain..."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control1/p08.htm

The engineering of the mind can only be accomplished with the waves of time.

The course of psychoenergetics development necessitates the building of a vast database of settings and patterns which bring about given mental and/or emotional states. A kind of "gnome" of the psyche. Bearden describes the process of the decoding of this "gnome."

> "Now the scientists would perform many phenomenology experiments, making one little change at a time and profusely recording the data. Each time, they would establish the physical change(s) that occur in the body and/or the mental and emotional changes that occur in the mind for each spectral reinsertion back through the "ship's portholes". They would simply but painstakingly (over some years) build up an extensive database of those individual correlates.
>
> "In these experiments, the experimenters will eventually be able to provoke any body or mind change they wish. Strong emotion. Intense pain. Intense pleasure. Painful thoughts. Images. Memories. Perceptions. Dreams. Visions. Memory losses. Memory changes. Personality changes. Etc. The "delta" in the emission spectrum (the changes from zero reference spectrum) represent the precise totality of all mental, physical, organic, chemical, etc. changes and interactions."

> Bearden http://www.cheniere.org/explore%20articles/mind%20control3/p01.htm
>
> "A second stage in the research would be to test the correlates and porthole insertions upon a statistically significant cross section of ordinary people, and/or specialized populations (such as toughened soldiers). The program would evolve a highly complex, very effective, ever-improving science and technology of mind and behavior control and engineering mechanisms, complete with finished database and developed applications equipment."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control3/p02.htm

Summing up his paper Bearden speculates on what the actual situation the science of psychoenergetics probably is. The intense secrecy with which this knowledge has been kept from the public has led to the current farce of the "government" pretending it all does not exist, and this secrecy may have now put us at great risk.

> "The implication is that in the West one or more highly classified, sustained, heavily funded developments in advanced mind control programs, probably exists and probably has existed for some time. Due to loose formation of rogue groups inside such programs, they may have dual or triple purposes, may not operate under very much legitimate government control at all, and may operate specifically for the purposes of the rogue group or groups that have gained control.
>
> "In a nutshell, that's what may be going on in the clandestine mind control projects in several Western governments. The involvement of at least some rogue groups, some being "cowboys" who operate well outside all laws and ethics, could also result in such things as assassinations, clandestine testing on individuals without their consent, etc. In short, it could account for what seems to be actually occurring. As also is "usual" in such a mess, one or more of the rogue groups eventually may become very powerful because their secret weapons are very powerful. They may become confident, thinking they have the "best in the world." They may actually believe they are ahead of the Russians..."
>
> "Remember that, in every large and powerful human organization, the basis for rogue groups is power and secrecy. They are always seeking to increase their power, control, influence, prestige, etc. Nothing else. Patriotism and mission are—to rogue groups—often just idle words. They have their own agendas. And being rogue groups, they may well bring in unethical, immoral tricks: assassination, bribery, entrapment, disinformation, plausible deniability, etc. A certain percentage of a highly secret rogue group will wind up using all these things and more. It's a human characteristic, the old primate dominance game. Only now disguised and hidden under deep classification."
>
> "The Russians, with their additional knowledge of the actual mechanisms in the transforms, will be much more advanced than the West, because their fundamental psychoenergetics science is far more advanced, so long as we continue to use the old U(l) electrodynamics. Further, the Russians have decades of use of longitudinal interferometry beams to reach right through the earth and ocean and produce stringent EM effects at a distance. So they will also be able to do the same things here in "mind control" with LW [longitudinal wave] interferometers, through intervening mass."

> Bearden http://www.cheniere.org/explore%20articles/mind%20control3/p05.htm

Bearden cites two examples where he believes the Russian KGB tested the psychoenergetics capabilities of their scalar interferometers. One was the case of Captain Button in his A-10 "Warthog" aircraft on April 2, 1997.

> "Over Arizona, Captain Button was thrown into a hypnogogic state, and his perceptions instantly altered and controlled. In his instant "dream-waking" state, everything seemed perfectly normal. His sense of direction was altered a bit more than 90 degrees, so he simply corrected and turned and "flew toward the range", actually flying off course by more than 90 degrees and ignoring radio contacts. He flew right on out of Arizona."
>
> "At one point he circled, probably thinking he was over the range, and he probably dropped his ordnance there. Then he "flew on back toward home," as he thought in his waking dream state, until his fuel ran out and he crashed and died in the explosion—dream-thinking until he died that everything was normal. All the while, his sense of the passage of time was altered. To him, in his dream-thinking, dream-acting state, everything was normal and nothing untoward had happened. So the distant KGB transmitters and associated psychoenergetics team controlled him for over an hour. "Indeed, that was the exact purpose of the test: demonstrate control (at a great distance) of a skilled person performing highly skilled tasks."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control3/p06.htm

The paper "Mind Control and EM Wave Polarization Transductions" ends with the most chilling and frightening possibility of all: the psychoenergetic engineering of the human species as a whole.

The Ant World

The Final Race for Direct Mind Control of the Entire Human Species

> "The KGB psychoenergetics weapons scientists—because of their direct measurements and detections (and use) of t-polarized waves and LWs [longitudinal waves] for decades—also understand that Jung's collective unconscious mind (of the entire human species) also has its own time-like operations and correlates, which one measures also when using t-polarization measurements and sorting it all out. The collective unconscious mind operations are buried several levels deeper inside the recursive Whittaker structuring inside the EM fields, waves, and potentials. "The KGB scientists also know that something very like Gaia — a collective unconscious mind for all species on earth — also exists, and they are striving to be able to sort out and measure that one as well. The Gaia operations are buried even deeper in the recursive structuring inside the EM fields, waves, and potentials.""Actually, from day one, the Russian mind control scientists have had their eventual goal set upon this "deeper area of mind and possible mind control" of the entire human species.
>
> "I am convinced that the KGB psychoenergetics scientists understand this deeper area. If they can learn to directly engineer the collective human species unconscious, they can

> then convert the human species easily into a sort of "ant" society, modeled along ideal Communism lines, except of course with an excluded "hierarchy at the top" running everything. The "ant society" — communist style — is still a variation of feudalism (all systems tend to feudalism or some form thereof). "The KGB psychoenergetics weapon scientists are seriously pressing on toward that very goal. In my opinion they are not very far from it right now...
>
> "Some versions of Russian mind control devices were used on Russian soldiers in the Afghan War to condition them for performance of merciless acts." 13
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control3/p07.htm

More about "The Ant World"

Whether it is the Russians planning an "ant world" society or rogue U.S. black-ops groups withholding a great boon from human race, the secrecy on all sides around has allowed largely criminal elements to take over this technology while leaving the civilized elements in the dark. Openness and the spreading of this knowledge among good and decent people is essential, and for that we will have to overcome our frightened denial.

> "Meanwhile, rogue groups amongst Western clandestine mind control researchers will probably arise if they have not already done so. They will likely seek to increase their personal control and further isolate the programs from orthodox government review and from government and legislative control. They may even divert the research into highly illegal and unethical means, because it furthers their own rogue agendas. That is how clandestine U.S. government research can sometimes go sour, unless great care is exercised by the oversight committees in the House and the Senate.
>
> "Sometimes when rogue groups do gain control and total secrecy of a given new technological area, then what appears to be "U.S. government operations" do start to encompass a criminal and unethical operations, hidden usually beneath the deep veil of high classification. Also, if it's "scientific," no one is ever brought to justice, even if the "evil science actions" are uncovered and publicly revealed."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control3/p08.htm

Like the huge energy of the Tesla howitzers, the ability to engineer the mind with longitudinal waveforms is a seeming "magical" thing which can be used for good or ill. Bearden envisions that further developments will allow something like the "downloading" of knowledge via scalar interferometry. Everyone could be highly educated, and quickly and easily.

In the conclusion of the paper "Mind Control and EM Wave Polarization Transductions" Bearden makes a plea to the nations of the world regarding the use of psychoenergetic engineering.

> "Let us hope this great new area, already off to a bad start, can be bridled and steered in the direction helping and healing people, rather than killing or abusing them. The excesses in its bad use are a potent threat to all nations on earth.

> "Yet it can revolutionize medical science, education, communication, and psychology. We foresee the day -- perhaps 30 years hence -- when education will be accomplished by directly loading the software into the mind. Then in three weeks one will "load" a doctorate, say, in physics. In three more weeks on will also load a doctorate in chemistry. Another three weeks, in electrical engineering. Another three weeks, an MD And so on. When that happens then truly everyone on earth can be educated. Freedom from ignorance may well be another great freedom that is legally recognized. There will be no impoverished large groups lacking the education to find decent, productive jobs.
>
> "We urge all nations to use the principles involved: not for human abuse, but for healing, educating, uplifting, and life-expanding of every person on earth. If we do, we shall all have a far brighter future. Then we shall check what has started out to be the Sword of Damocles and turn it into the golden Millennium."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control3/p08.htm

(Perhaps after so many frightening topics a slight break is in order here to consider the lighter side of psychoenergetics. For example, what will be the ultimate impact on the entertainment industry?)

The Feelies at Last!

Psychoenergetics will be able to bring about at last, for better or for worse, Aldous Huxley's fanciful idea in his novel "Brave New World," an entertainment format which he called "The Feelies." Those were something you went to, like going to the movies, but you would experience all the actual feelings themselves, as if the depicted events were actually happening to you. Although our "leaders" seem too dim to grasp what is going on in the world of scalar electromagnetics, it should not take some young Hollywood genius too long to understand that The Feelies are now possible, and that the immense megabucks of potential profit more than justify heavy investment in bringing it to market.

One can imagine that first "Feelie" theater, "The Huxley" perhaps, a large comfortable area surrounded by nine giant screens (not just one screen!), which become 3D if you put on your headset. And The Huxley is fitted with the finest sound, and oh, by the way, a modest sized scalar interferometer with computer. And there are one or more new tracks now recorded on the film next to the sound track. These are the digital patterns of thoughts, feelings, and ideas to be fed into the theater's interferometer. And these thoughts and feelings and ideas will be felt by the audience as if they were their own thoughts and ideas. It is an entirely new art form. Psychevision.

As important (and no doubt famous) as the actors would be the "feelers," those from whose minds the feelings were lifted in the original programming of the Feelie tracks. Because, for example, Brad Pitt might be a good and handsome actor, but can he really feel it? Like the dubbing of foreign language films, it might be necessary to dub the "emotional track" using a deeper and more profound person's feelings, thoughts and ideas.

It might even be engineered so that if you sat on one side of the theater you would feel like the hero, and on the other side you would feel exactly like the bad guy! What would that lead to?

We have all cried at a movie some time, most people have, though they might not want to admit it. But this would be deep sobbing and a flood of tears, if the director so desired it. You would feel it at your core. Or, take a big chase scene, you would be terrified. They are breathing down your neck! You would be gripped by panic.

For that matter, the whole genre of Horror-Feelie would be too much for many people to take. Do I really want to feel that an actual vampire is tearing at my throat with his fangs?

A Religious Feelie would make you feel the exaltation of a saint at his prayers, or give you the definite feeling that you are Christ suffering on the cross. All the pain could be there too. The stickiness of the blood. The very feeling itself: "Why hast thou forsaken me?" Who among us could come up that despair for scanning? Had this been developed a bit earlier we might watch a documentary of, say, Mother Theresa, containing her own actual deep sense of compassion, which we would feel arising in us as our own.

Then again, a Psychedelic Feelie could induce an LSD-like state and simply blow the audience's minds.

Even in its simplest most primitive mode, the hypnogogic trance induction with its increased suggestibility, would completely alter the experience of even ordinary current movie going.

6. As it Stands - 2002

"Anyway, it's presently a "Mexican stand-off" with the various parties maneuvering with check and countercheck. That is the real "balance of terror" that is held by such a fragile balance."

"You can see the implications if such weapons fall into the hands of the radical terrorists. Ordinary positive energy EMP shooters can be made fairly readily and cheaply from nearly just Radio Shack parts or surplus parts. It just takes some know-how... When and if the Yakuza [Japanese mafia] gets those (and they will, it's just a question of time), you can begin to appreciate some of the turns this present terrorism and our war on it will take."

Bearden http://www.cheniere.org/correspondence/021702a.htm

The very thought of the building of one of these howitzers by "some lone-nut gunman" from Radio Shack parts makes one realize how serious it is for humanity to face the crisis it has come to.

Once again, as at the dawn of the nuclear era, humanity finds itself at the crossroads of Heaven and Hell. As a species, we must stop and consider. And there is at least one real difference between this visit to the crossroads and the last: this time there is a very real possibility of a true "earthly heaven" on the Heaven side.

The poor nations could come to a good life. Disease could be largely eliminated. Fossil fuel pollution could end. Global warming could be solved, and the weather could be managed in a humane way, bringing water where there is drought, and sunny skies where there is flood. Scalar interferometry would be there to avert any possible hits by asteroids or comets. Mars could be colonized and terraformed. Everyone would be highly educated through psychoenergetic downloading of knowledge. And the wisdom of the wise could be realized directly through scalar connection to their minds and hearts.

These stunning sudden possibilities give me pause to think: if our species has reached this crossroads in such a short span of centuries, then surely other species in this vast universe have passed this way before and long ago. And of those who chose the path to "planetary heaven," what is their life like now? It might be good if some of them were with us now, to guide us through this last struggle over this pesky old good-and-evil problem. It is our last chance to choose the path which benefits the whole species, and not just some elite group or faction.

The Disclosure Project

One person working tirelessly to bring to bring these technologies into the open is Dr. Stephen Greer of the Disclosure Project, which is calling for congressional hearings into the issues of UFOs and the free energy technology that was, perhaps in part, reverse-engineered from them.

> "Once abundant and nearly free energy is available in impoverished areas for agriculture, transportation, construction, manufacturing and electrification, there is no limit to what humanity can achieve. It is ridiculous — obscene even — that mind-boggling poverty and famine exists in the world while we sit on classified technologies that could completely reverse this situation. "So why not release these technologies? Because the social, economic and geo-political order of the world would be greatly altered. Every deep insider with whom I have met has emphasized that this would be the greatest change in known human history. The matter is so highly classified not because it is so silly, but because its implications are so profound and far reaching. By nature, those who control such projects do not like change. And here we are talking about the biggest economic, technological, social and geo-political change in known human history. Hence, the status quo is maintained, even as our civilization hurtles towards oblivion...
>
> "With the types of weapons currently in the covert arsenal — weapons more fearsome even than thermonuclear devices — there is no possibility of a survivable conflict. Yet in the darkness of secrecy, actions have been taken on behalf of every human that may

> endanger our future. Only a full, honest disclosure will correct this situation. It is not possible for me to convey in words the urgency of this."
>
> Dr. Stephen Greer http://www.disclosureproject.org/ES-DisclosureImplications-2.htm

Greer and his team have assembled hundreds of witnesses, many of whom are military or ex-military, who are ready to testify to congressional hearings what they know about the covert black projects which have kept free-energy and antigravity propulsion technology secret from the people.

Greer points out the need to regulate these technologies so they are limited to peaceful uses, but this is of course difficult when the government simply chooses to pretend they do not exist. In the meantime, as the President and the Defense Department continue the charade of war-as-usual, those scalar (longitudinal wave) installations which DO exist continue to fall into ever more sinister hands. And there is no reporter in the press brave enough to ask, "Mr. Secretary of Defense, what steps are you taking to defend our MINDS from attack by the big Russian longitudinal interferometers?"

Longitudinal Interferometers are Proliferating

In a later statement Bearden reveals that in fact the Yakuza [Japanese mafia] has already leased some of the interferometers with a nearly $1 billion "down payment:"

> "After the collapse of the Soviet Union's economy, lots of things got available for lease or purchase that would never have been under the old system. That happened in the resulting economic chaos. The Russian Mafia rose to prominence, as did some wheeling and dealing entrepreneurs who played both ends against the middle.
>
> "In that atmosphere, and in the need for money, the KGB allowed leasing of the earlier longitudinal EM wave interferometers to a consortium of the Yakuza and Aum Shinrikyo. They did this only after they had tested and deployed their great new quantum potential weapons. That class of weapon is the dominant weapon on earth. Five nations now have it: Brazil, Russia (KGB), China, and two nations friendly to the U.S. The deal to lease many of the earlier LWIs [longitudinal wave interferometers] to the Japanese Yakuza and Aum Shinrikyo was consummated at the end of 1989, with a down payment of $900 million in gold bullion as "up front" money. I don't know what the lease per year was and is, but probably something like a billion dollars a year. So the rogue Japanese acquired longitudinal EM weapons and that technical know-how. In fact, the Yakuza is producing certain kinds of those in its own facilities in Japan now."
>
> Bearden http://www.cheniere.org/correspondence/030202a.htm

Personally, I am a little uncomfortable with the knowledge that the Japanese mafia may now be able to insert things into my mind. I'd like to sleep at night knowing that my dreams are my own, such as they may be, and not some weird fantastic visions cooked up by a criminal organization. This is a world emergency.

And in Bearden's analysis, it all comes back to the issue of energy. It is the energy crisis which is now provoking the current "oil wars," since oil production has hit the "Hubbert Peak" and will decline. And the electrical power grids must be replaced with scalar power as fast as possible, for these grids are now totally vulnerable to any possessor of longitudinal interferometers. They can all be wiped out in minutes. By anyone who possesses or controls a Tesla howitzer.

> "Anyway, in my personal view, we should have a national Manhattan Project right now, to develop decentralized electrical power systems taking their energy from the vacuum . . . The MEG is real and so are several other systems invented by private inventors and colleagues. All these efforts should be massively funded and massively and quickly developed. The survival of this nation is going to depend upon it. . . . There are many other facets, but the major point is that our scientific apparatus and the public are still unaware of what a desperate struggle we have entered, since it was thrust upon us. 9-11 was a wake-up call. It was certainly bad enough, and one grieves for those lost American lives. But I fear the worst is yet to come, and it is coming at us like a runaway train hurtling right down the track at us."
>
> Bearden http://www.cheniere.org/correspondence/021702a.htm
>
> "The electromagnetic weapons mentioned by the Secretary of Defense in April 1997 are in terrorist hands also, including the Yakuza and Aum Shinrikyo. That rogue group leased those earlier weapons on site in Russia, from the KGB, at the end of 1989. The SecDef stated that such weapons were being used to initiate earthquakes, initiate volcanoes into eruption, and control and engineer the weather. Quite true. And presently there is a truly massive set of weather engineering operations going on over North America, from that rogue Japanese group manning the weapons in Russia. Some 10 nations of the world now have the type of longitudinal EM wave interferometer weapons (which are what the SecDef was most probably referring to). There are other even more fearsome weapons, possessed by five nations. So a great deal of the state of the world is not covered in the news at all, and will not be . . .
>
> "We have been in an undeclared war of an eerie kind for some decades. That war seems now to have started to heat up also. The destructive capability of some of these weapons is awesome, and far greater than nuclear."
>
> Bearden http://www.cheniere.org/correspondence/021702a.htm
>
> "In that sense, the first phase of WW III is already completed. Now we are only waiting for Phase II.
>
> "It is against that backdrop that I think one must "analyze" such things as how fast we will be replacing the power grid (it's going to go anyway, and catastrophically, the terrorists will see to that). And everything we have is critically dependent upon energy, from the economy to jobs to mobility, to the millions of trucks that transport our goods every day, etc.
>
> "As far as I am concerned, we are already late in declaring a great national emergency in energy, because of the coming destruction of the present energy infrastructure. The

> scientific community should lead, follow, or get out of the way. The emergency is not in seeking "alternative but conventional" systems. It is in developing "energy from the vacuum" on an emergency, crash basis.
>
> "Unfortunately, everywhere I look I just see business as usual. Most Americans (and news media) seem to think, hey, Afghanistan is finished except for a bit of cleanup, and it's just about over).
>
> "It isn't. It has only just begun."
>
> Bearden http://www.cheniere.org/correspondence/021702a.htm

Beyond the Howitzers: Quantum Potential Weapons

Do not use EM propagation through space

As more and more nations acquire the scalar interferometers, Bearden speculates on the next generation of longitudinal weapons called "quantum potential" [QP] weapons.

> "The quantum potential weapons are presently only held by three nations: Russia (in the hands of the KGB, which is now know by its new name), Brazil, and the "friendly little nation." Red China may be working on them, but is just at the beginning...
>
> "The QP weapons have been highly reserved by the Russians. However, the complete extent of their capabilities is still being figured out...
>
> "The quantum potential weaponry (possessed by only three nations) is supreme, because it uses multiply connected spacetime, and DOES NOT involve propagation of EM energy through space as does the longitudinal EM wave interferometers.
>
> Bearden http://www.cheniere.org/misc/qp.htm
>
> "The operational deployment of full-scale strategic QP weapons on site in Russia occurred at the end of 1989, which is when the formal weapons first went operational. These weapons are not in the inventory of the regular Russian armed forces, but all research and development, manufacturing, deployment, an manning and employment is under the ruthless control of the KGB. Shortly thereafter (within weeks), the KGB leased many of their earlier longitudinal EM wave interferometer (LWI) weapons to a rogue Japanese group comprised of the Aum Shinrikyo and Yakuza."
>
> Bearden http://www.cheniere.org/correspondence/021401.htm

In another paper, "Time Polarization - Significance and Weaponization," Bearden tells the story of how a KGB longitudinal wave attack was averted by the longitudinal weapons of a "friendly small nation."

So as it stands, it is precarious. Not until the people demand an end of what author Jim Marrs has dubbed the "Rule by Secrecy," can the people's representatives tackle the big problems of a worldwide ban on Scalar Wars and the shifting over to an essentially oil-free economy.

Latest Update from Tom Bearden - March 2002

The whole situation is changing so fast that when I asked Tom to look over this article he mentioned the seeming contradiction when some of the above statements are taken together. At different times the information he has is updated so one has to keep a kind of running track. He was kind enough to clear up the confusion here with the situation as it stands as of March, 2002.

> "We knew of three nations having the QP weapons for some time. Then we found out last year that five nations had it. So that explains my using the figure "three" first (which represented what I knew at the time). Later I found out about the other two nations. China, e.g., only deployed its QP weapon this past year. So that explains the apparent contradiction between me using "five" in later papers and "three" in earlier ones. It was the best information I had at that time. Might mention that so the reader will understand the apparent discrepancy." Tom Bearden

Emptiness is Full of Energy

"The Tao is an empty vessel;
it is used, but never filled.
Oh, unfathomable source
of ten thousand things!

"Oh, hidden deep but ever present!
I do not know from whence it comes.
It is the forefather of the gods."

Lao Tzu -Tao te Ching

Afterward

Because of the extreme seriousness of the topics brought forward in this article, I asked Tom Bearden to look it over to make sure I had not gotten anything too terribly wrong or mixed up. I did not want to pass on any misunderstanding of my own. I felt a little nervous writing to an eminent scientist, and hoped I had not presumed upon his time.

But Tom was so kind as to answer immediately, and to my relief I had not gotten anything too terribly wrong. Here is his letter, in which he clears up a misunderstanding, and reports on his current health treatment, and gives a call to the young grad students to turn themselves loose in the whole new field of scalar electromagnetics and free energy.

Subject: RE: Article on Tom Bearden and "Scalar Wars"
Date: Fri, 22 Mar 2002 22:54:01 -0600

Bill,

Well, I must say I'm astounded at your persistence and hard work in congealing all that together. My compliments on a hard job quite well done.

Couple tiny things: In the area mentioning Kervran and Kaznacheyev: Kervran was French; Kaznacheyev was and is Russian. Little typo of "spredding" the immune system. Should be "spreading".

We knew of three nations having the QP weapons for some time. Then we found out last year that five nations had it. So that explains my using the figure "three" first (which represented what I knew at the time). Later I found out about the other two nations. China, e.g., only deployed its QP weapon this past year. So that explains the apparent contradiction between me using "five" in later papers and "three" in earlier ones. It was the best information I had at that time. Might mention that so the reader will understand the apparent discrepancy.

Otherwise, it's pretty accurate.

Just now I'm letting the weapons take care of themselves; have to, as I will be recovering now for nearly a year from now after the heart attack last year and discovering that I had contracted mycoplasia (the BW modified kind) in Canada in 1968. Finally got a test which confirmed the chronic mycoplasia (which I had for 33 years!). The stuff burrows inside one's red corpuscles, then draws nutrients from the hemoglobin, hardening it and reducing its ability to take on oxygen (by as much as 50% or more). The resulting symptom is loss of endurance (which I had for that 33 years) -- the so-called "chronic fatigue syndrome".

Many of the Gulf War Veterans who are sick also have it, though they apparently have other complicating factors as well. A very high percentage of persons with chronic fatigue syndrome also have mycoplasia. The treatment for the long-standing mycoplasma infection of that nature is to stay on antibiotics for a year. The only time the mycoplasma is vulnerable is when one wears out a red cell in normal usage, and the body makes a new red cell to replace it. The mycoplasma comes out of the dying cell to infect the new replacement cell, so it is exposed and vulnerable at that specific time and that time only. The antibiotics kills it at that time. Hence the necessity to stay on antibiotics for such a long time so it is continuously in your bloodstream (I've already been on antibiotics for over two months, and have at least 10 more months to go). We also take a little medical oxygen every day.

Another symptom of the mycoplasma infection is the association of runaway fibrillation of the heart. To stop that, there are pills one takes, and they stop it. But they also further reduce the volume of blood pumped by the heart, so that this projects one right back into the hypoxia, dizzy, loss of balance, etc. Catch 22 situation; the fibrillation will build and cause heart attack, stroke, etc. if not stopped, and if stopped it puts you back in the hypoxia which can cause many things! With the conventional treatment, you're damned if you do and damned if you don't. Hence the need for a little extra medical oxygen, so you can take the "heart clamp" pill and stop the fibrillation, but also augment the oxygen enough to continue to survive without a stroke or some such. Interestingly, it's very difficult to even obtain a mycoplasma test, and Medicare fights you tooth and nail over paying for the oxygen. Either they will pay for it or I'll pay for it myself; it is absolutely necessary.

After a heart attack, one is treated in the heart clinic by specialists who are very caring and excellent practitioners, but know nothing of mycoplasma infection, so not consider it even a part of "heart disease", and who are rather puzzled when one has no clogging of the arteries, has the right count of red corpuscles (largely nonfunctional, of course, but there), pumps the right amount of blood, etc. So they identify and treat only the runaway fibrillation, do not prescribe the oxygen -- and essentially place you on a regime as best they know, but one that is guaranteed to kill or maim you or turn you into a totally disabled person or human vegetable via stroke, paralysis, etc. Fortunately my family doctor will prescribe the oxygen anyway, though I may have to pay for it myself. Whatever works!

However, I'm slowly improving little by little, working as much as I'm able to and trying to finish my book: Energy from the Vacuum: Concepts and Principles, and get it to the publisher for publication later this year. Hopefully the book will turn all the interested young grad students and post-docs loose in the free-energy area. They will not have to spend 30 agonizing years to get to where I am, and where a few others are, but can simply start here and go forward. Since speed to develop energy from the vacuum is of the essence because of the world situation, I'm moving on it as fast as I am physically able to.

Meanwhile, working with the AIAS (Alpha Foundation's Institute for Advanced Study), the AIAS (15 authors) has now gotten about 20 scientific papers published in leading journals (Foundations of Physics, Foundations of Physics Letters, Physical Scripta, Optik, etc.) dealing with electromagnetic energy from the vacuum. Several more are either approved for publication or in the review process also. So slowly we are getting it into the mainstream scientific literature. Hopefully it will be in time, but it's cutting it close.

Very best wishes,

Tom Bearden

Late update

Massive display of longitudinal interferometers?

UFO Fleet Taped Over Bedhampton, England

Is this sighting a case of the testing of all the Russian (KGB) longitudinal interferometers at once? And coordinating their targeting through the woodpecker grid to a common place, as an exercise in making a massive scalar attack upon a given region? Was this a confluence of Russian Tesla howitzer marker-beacons?

Bedhampton, England - March 22, 2002 - Video Frames by: Anthony Woods

Certainly for a massive all-out scalar attack you would want coordinated movements of the target areas of many howitzers at once, for you could then just cut a bloody swath across a wide area, all the howitzer blasts marching across the land in a kind of scalar version of the "scorched-earth policy." All in a line, blasting, and heat, and mind waves. Or you might want to put the blasts all in the same place for a truly horrendous destruction. And on top of that biowar on citizens whose immune systems have been weakened with the quantum potential weapons. This is the latest version of Armageddon.

And should any madmen gain control of these weapons, any rogue group at all, and should they have some agenda to radically depopulate the world, to simply kill by the billion, the means will be in their hands to do so.

Update: MEG patent granted

Motionless Electromagnetic Generator Patent Granted

This message is from Jean-Louis Naudin, the French scientist who successfully replicated the Motionless Electromagnetic Generator (MEG) in France. He announces the granting of the patent to the MEG Builder's group at Yahoo.

----- Original Message -----

From: jnaudin509@aol.com
To: jlnlabs@yahoogroups.com
Sent: Tuesday, March 26, 2002 2:20 PM
Subject: [jlnlabs] (Info) GOOD NEWS : The Tom Bearden's MEG IS PATENTED

Dear ALL,

GOOD NEWS !!!!

The Motionless Electromagnetic Generator from Tom Bearden is now PATENTED US 6362718 granted on March 26, 2002

US Patent 6,362,718 :
Motionless Electromagnetic Generator (MEG)

Abstract: An electromagnetic generator without moving parts includes a permanent magnet and a magnetic core including first and second magnetic paths. A first input coil and a first output coil extend around portions of the first magnetic path, while a second input coil and a second output coil extend around portions of the second magnetic path. The input coils are alternatively pulsed to provide induced current pulses in the output coils. Driving electrical current through each of the input coils reduces a level of flux from the permanent magnet within the magnet path around which the input coil extends. In an alternative embodiment of an electromagnetic generator, the magnetic core includes annular spaced-apart plates, with posts and permanent magnets extending in an alternating fashion between the plates. An output coil extends around each of these posts. Input coils extending around portions of the plates are pulsed to cause the induction of current within the output coils.

Inventors: Patrick; Stephen L. (2511 Woodview Dr. SE., Huntsville, AL 35801); Bearden; Thomas E. (2211 Cove Rd., Huntsville, AL 35801); Hayes; James C. (16026 Deaton Dr. SE., Huntsville, AL 35803); Moore; Kenneth D. (1704 Montdale Rd., Huntsville, FL 35801); Kenny; James L. (925 Tascosa Dr., Huntsville, AL 35802)

Appl. No.: 656313
Filed: September 6, 2000

For some technical info see my web site at : http://jnaudin.free.fr/html/meg.htm

Best Regards
Jean-Louis Naudin
Email: JNaudin509@aol.com
Main Web site : http://jlnlabs.org
Site France : http://jlnlabs.multimania.com

Click here to view patent # 6,362,718

Patent Story on Rense.com:

Rense.com

MEG Scalar Energy Device
Patented - Production Starts Next Year

From Bill Morgan
wmorgan@nycap.rr.com
3-28-2

Patent was granted on March 26, 2002 for "The Motionless Magnetic Generator," (MEG) US Patent 6,362,718, which is likely to become the first commercially available free energy device in history in about one year from now. The machine will provide free electricity from the vacuum, for the life of the device, which should be a very long life since it has no moving parts. You can see a picture of scientist Jean-Louis Naudin's MEG replication model at: http://jnaudin.free.fr/html/meg.htm.

It has strong magnets, coils, and a controller unit with the electronics. Naudin made the announcement to the MEG-builder's Yahoo group. The announcement has significance since the patent office has always been skeptical of devices which seem to "get-something-for-nothing." But according to the new science of scalar electromagnetics, the MEG does not break the law of conservation of energy. It's just that the energy is conserved in the fourth dimension, time, and not our 3-space world.

The MEG provides electrical energy by tapping the longitudinal electromagnetic (EM) waves which exist in almost infinite abundance in the vacuum of space. This ocean of energy which permeates everything is sometimes called the "zero point" energy, since it remains there even at absolute zero temperature.

Four inventors are listed: Stephen L. Patrick, Thomas E. Bearden, James C. Hayes, Kenneth D. Moore.

Tom Bearden has explained the operation of the MEG on his website Cheniere.org, and also speaks about the new fearful weapons that can and have been made using the same "longitudinal waves" of the vacuum.

The complicated physics of how the MEG works is explained in the paper "The Motionless Electromagnetic Generator: Extracting Energy from a Permanent Magnet with Energy Replenishment from the Active Vacuum," which can be found at Tom Bearden's website:

cheniere.org.(http://www.help4all.de/energy/MEGpaper.pdf)

The first MEG units to be produced for sale will output 2.5 kilowatts of free electricity. Forever. They should be in production about a year from now. Facilities for manufacturing the device are being set up in an unnamed "friendly nation."

This free electricity will flow indefinitely, without much, or any maintenance. The units may be hooked together to provide more wattage, so four of them would provide 10 kilowatts. After some production experience units will be made which output 10 kilowatts each. With a couple of those units a house could get off the electrical grid.

Tom Bearden, one of the inventors has said "I will admit that the chief scientist of an important experimental group in a large company was rather stunned at the type of output we were able to obtain. The MEG may look like just a transformer, but it is not. It is a completely different breed of cat." This cat, it would seem, is out of the bag now.

The ordinary EM waves we are familiar with are called "transverse" waves, to distinguish them from the new "longitudinal" EM waves of the vacuum. Bearden has explained in depth on his website cheniere.org that wherever there is a dipole (battery, generator, magnet) there is an unseen flow of longitudinal EM waves in that local vacuum, the only problem is in tapping that energy and "transducing" it to electricity. Bearden says that the problem with all the electrical circuits we have is that they are two-wire circuits, a loop by which half the energy goes back to destroy the dipole. In the MEG that closed loop is never made. So the dipole is not being destroyed.

Patents are not granted on devices which do not work, so in a sense this announcement proclaims a new era. The MEG device itself proclaims and proves that energy is abundantly available everywhere, for free. We only have to build the devices to tap it. MEG type devices could be put into a car with an electric engine to make a truly fuel-less automobile. Electricity can be available in very remote places. People will be able to get off our very terrorist-vulnerable power grids. In an era of terrorism a highly dispersed power system would be most desirable rather than our centralized systems.

What is somewhat astonishing to me is the discovery by Bearden et. al. that time itself is actually compressed energy, and that this free energy is actually coming from the time domain, the ocean of longitudinal EM waves which fill the empty vacuum of spacetime. In fact, time is energy compressed by the same factor that matter is compressed energy: the speed-of-light squared. Thus there is a new companion to Einstein's E=mc2. Can you say "E equals delta-tee-cee-squared?" The "tee" is time and delta-tee is change in time.

A company has been set up to manufacture the MEG called Magnetic Energy Limited.

The ramifications of free energy are enormous. The oil wars are not necessary. If we threw as much money at this technology as we are spending on the oil wars we would be free of the need for oil in less than a decade. With fuel-less cars air pollution will be greatly lessened. Third world nations can raise their standard of living eventually. And the energy is free. And it never runs out.

I have put together a kind of "Bearden for Beginners" article which explains some of the basic concepts of the current state of scalar technology.

http://www.prahlad.org/pub/bearden/scalar_wars.htm

The granting of the MEG patent is the herald of the new era of scalar electromagnetics, and the free energy which flows forever and never runs out.

Bill Morgan
wmorgan@nycap.rr.com

Do the magnets run down after a while?

Further developments: Tom Bearden clears up a question

When the MEG patent was released many questioned the patent language which seemed to imply that permanent magnets of the MEG would "wear out" after awhile. I myself wondered about the same thing so I put the question to Tom, and here is his reply.

> Dear Bill,
>
> Thanks for the kind words; much appreciated.
>
> I'm not up to going on radio or TV, and won't be for quite some time. Still suffering from hypoxia, though very slowly improving, and will still be on antibiotics for 10 more months at least (maybe longer).
>
> Obviously an extensive dialog developed between the Patent office and our patent attorneys. As best I can understand it, the Patent office accepts the fact that a permanent magnet produces and emits energy, or has a history of accepting it. They do not appear to be at all cognizant of the broken symmetry of opposite charges, and hence of a dipole. So in their opinion (which seems to be vague), the magnet has to use itself up very gradually, or some such. So some rewrites were essentially required by the Patent office.
>
> All I can say is that a magnet is a very durable thing, so long as you don't heat it up too much or shock it to much. Certainly one will make a good 20 years, and of course there are plenty of magnets that have been around awhile longer.
>
> That said, in our earliest experiments we did "measure" some such effect, or so we thought, until we found that a particular instrument was bad and giving erroneous readings. So with a new instrument, we have not observed since then any such readings.
>
> Out of all that fuzziness came the inclusion of "using up the magnets gradually". So far as we are aware (after correcting those early readings on a defective instrument), we have seen no such measurements or effects since then at all. Nonetheless, just in case there is some very small effect in that respect, at least it's in there.
>
> Actually, as you are aware, capacitors and solid state components are the major concerns for failure, and any system does require maintenance, both periodic and whenever malfunction or failure occurs. The MEG is no different from any other device in that respect, so of course it will have a component failure rate and maintenance required from time to time, just as any other electromagnetic device. But without moving parts, it can be ruggedized and made very durable indeed.
>
> Please give Jeff Rense my regrets, and I do admire his work and his show. He's laying it in there.
>
> The depth of the scientific mindset against COP>1.0 is inexplicable, particularly when physics itself already has COP>1.0 validated experiments (such as Bohren's experiment,

which outputs 18 times as much as one inputs by Poynting calculations), and it works every time. Any competent university optics lab can perform the experiment. Also, even the conventional texts admit that a charged capacitor or electret laid on a permanent magnet, so that the E of the cap or electret and the H of the magnet are at right angles, is a "free energy machine". That silly thing will just sit there and pour out Poynting energy S = EXH indefinitely. Years and years and years. If you wait just a single year, that silly thing has changed the energy density of a volume of space a light year in radius, reaching out well beyond the solar system. Now that's a WHALE of a lot of EM energy that beast poured out in that year, and it will still be going strong and pouring it out at a steady rate. The charges and dipoles in original matter in the universe have been pouring out EM energy in that fashion for some 14 billion years, give or take a billion or so. It's also easy to see that, prior to Lorentz's ARBITRARY symmetrical regauging of the Maxwell-Heaviside equations, those equations prescribe both EM systems in equilibrium with their active environment, and EM systems not in equilibrium with it. The latter systems are permitted by the thermodynamics of open disequilibrium systems to perform five magic functions: (1) self-order, (2) self-oscillate or self-rotate, (3) output more energy than the operator inputs (the active environment inputs the rest of it), (4) power itself and its load (the active environment inputs all the energy, like a windmill), and (5) exhibit negentropy. That is a well-established thermodynamics. Lorentz arbitrarily discarded all such open disequilibrium EM systems in order to get simpler equations having analytical solutions and not requiring numerical methods. So he simply scrapped all the really interesting and challenging EM systems in Maxwell's theory. ARBITRARILY!

That our scientific establishment continues to teach only that "half" of the theory, and not point out the rest to the young students, and not fund research into developing such systems that take energy from the vacuum, is simply inexplicable. It's a matter of total dogma, not science at all.

But hopefully it is changing a little bit. At least now we cite chapter and verse when these things were done, and what they are, and the young grad students and post docs can go check the papers and make up their own minds.

That is the real hope of the future: that we get a generation of young fellows, with excellent skills, who now know where all the skeletons got hidden in the closet, and understand that the electrical engineering model arbitrarily assumes an inert vacuum environment (falsified for more than a half century in particle physics) and a local flat spacetime (falsified for nearly a century by general relativity).

Once they know that past history, and go read into what broken symmetry of opposite charges means for a dipole and for all dipolar EM circuits, they will set to and change that more than a century of error. In that case, we shall have numerous solutions to the energy crisis rather quickly, popping up all over.

Good thing. It will certainly displace some great energy barons, but it will also free the populace. One can extract all the EM energy from the vacuum one wishes, anywhere, anytime, with ridiculous ease. One can produce that "electrical wind of energy" at will, by making a simple dipole and then letting it alone. The only energy problem is in how to then intercept some of that energy flow and "catch" it in a circuit, discharge it in a load to power it, and not use half the "caught" energy to kill that dipole that is gushing out the extracted EM energy from the vacuum.

Very best wishes,

Tom Bearden

END

You're viewing the old pesn.com website

"PES Network, Inc: Promoting cutting-edge, clean energy technologies"

Pure Energy Systems

Home | PESN | News | PESWiki | Directory | NEC | Projects | Radio | Newsletter | Store | Submit

Top 5 Exotic Technologies

Free Energy is all about freedom:
Power to the people -- literally and figuratively

CLICK TO START BLOCKING ADS
Ad Remover

12 THINGS TO KNOW BEFORE BUYING A THERMAL CAMERA
GET THE GUIDEBOOK NOW!

Google Custom

"Free Energy"

News
- PESN Specials
- About
- Pure Energy Blog
- Daily FE News
- Features
- Free Energy Now
- This Week in FE
- Newsletter
- How you can help
- Submit
- Subscribe

Select Language
Powered by Google Translate

Directory
Energy Topics
- Alt Fuels
- Anti-Gravity
- Batteries
- Betavoltaic
- Biofuels
  - BioDiesel
  - BioElectricity
  - Biomass
- Body Electric
- Brown's Gas
- Cold Fusion
- Conservation
- Electrolysis
- Electromagnetic OU
- Fuel Cells
- Fuel Efficiency
  - Electric Vehicles
  - Engines
  - Hydroxy
- Fusion
- Geothermal
- Gravity Motors
- Human Powered
- Hydro
- Hydrogen
- Joe Cells
- Lighting
- Magnet Motors
- Nanotechnology
- Nuclear
- Nucl. Remediation
- Oil
- Piezoelectric

/2011/03/26/9501797_Teslas_Scalar_Waves_Replicated_by_Steve_Jackson/
You are here: PureEnergySystems.com > News > March 26, 2011

Tesla's Scalar Fields Still Beaming On!

The superluminal (faster than light) scalar or longitudinal waves Nikola Tesla used to magnify and wirelessly transmit power are not just a thing of the past. IEEE engineer, Steve Jackson, discusses and demonstrates how they can be utilized today, and he is open sourcing it here!

by Hank Mills
Pure Energy Systems News



Nikola Tesla is the father of the modern age. His inventions of radio, remote controlled devices, alternating current, and induction motors (among many others), paved the way for modern civilization. Yet other of his inventions barely saw the light of day, despite their tremendous potential.

Such a severely under utilized technology is his wireless energy transmission techniques. By producing scalar (longitudinal) waves, he could achieve superluminal (faster than light) communication, send signals through any material including Faraday cages, and wirelessly beam power to receivers. Researchers like Steve Jackson provide hope that by open sourcing Tesla's work, scalar wave transmission can proliferate and positively benefit the world.

Last Thursday, March 24, 2011, Steve Jackson held a presentation and demonstration of a scalar wave transmitter and receiver at a local IEEE meeting at McMaster University in Ontario, Canada. During the talk he gave an overview of Tesla's life, his inventions, and a plethora of information on his wireless power transmission technology. Afterwards, he demonstrated a small electric fan attached to a scalar wave receiver powered by a transmitter over twenty feet away. Tesla's technology is alive today!

Furthermore, he has approached us at PES Network to open source his design. You can download his PowerPoint presentation here. We'll be uploading to

Tesla Generator - Build Your Own Generator
Eliminate Your Power Bill Easy. Do It Yourself. Great Discount Now! Just $49.
tesla-energy.org

Jim Murray and Paul Babcock's 4790% SERPS Presentation	Ignition Secrets DVD by Aaron Murakami
Magnetic Energy Secrets, Paul Babcock, Parts 1 & 2	Battery Secrets by Peter Lindemann

Ads

Electronic Permit System
ePTW system with integrated Isolation and Competency controls
gemsoft7.com
AdChoices
Generator
Generator for Power

GREENfuel H2O .com
Save Fuel Today
Hydrogen on demand
The fuel of tomorrow

SAVE $ AND TIME
Make Biodiesel at Home!


Global Sun Oven

- Cold Fusion News
  - Kalte Fusion

• Plasma
• River
• Salt Water Mix
• Solar
• Solid State Gen.
• Tesla Turbines
• Thermal Electric
• Tidal
• Vortex
• Waste to Energy
• Water
- Water as Fuel
• Wave
• Wind
• Wireless Electricity
• Zero Point Energy
• MORE . . .

Open Source
• Freddy's Cell
• Bedini SG
• Safe Haven Villages
• MORE . . .

Resources
• Awards
• Conservation
• Conspiracy
• Directories
• Investment
• Kudos
• Legal
• Organizations
• Plastic and Energy
• Recycling
• Suppression
• Tools
• Trends
• MORE . . .

Mingling
• OverUnity Forum
• Employment
• Events
• Humor
• Magazines
• Movies
• Newsletters
• Discuss. Groups

Shopping
• Store
• Buyer Beware
- - - - - - - - - -
- Donate
- Contact

our PESNetwork YouTube account a video of his presentation to the IEEE in a couple of days. It's in process of being transmitted, but will take a while, as it is 3+ Gb. We're expecting to get instructions from Steve on Monday, and we'll be posting a PESWiki page to organize all this material to streamline the presentation.

Take a look at the following video that shows a small boat powered by scalar waves many feet from a transmitter.

A & P Electronic Media
Leading Digital Publishers of Advanced Energy Science
http://emediapress.com

o Fusion Froide
o Fusion Fria
o Fusione Fredda

Free Energy Store
* * * * *
Your Ad Here

Demonstration of Tesla's Wireless Power Transmission System duplicated at the Tesla Tech Conference, July 2007.

Scalar Wave Properties

You might be wondering what in the world is a scalar wave! It's actually pretty simple. Unlike a transverse wave (like an ordinary radio or light wave) a scalar wave's amplitude does not fluctuate up and down. Instead, try to visualize it more like a vibration of electric potential expanding and contracting in the direction of propagation.

Scalar waves are also often called "Tesla Waves" or "Longitudinal Waves." All of these terms refer to the same type of wave which oscillates in the direction of propagation instead of perpendicular to the direction of movement. These waves have many unique properties which have been tested and confirmed repeatedly.

1) They are capable of penetrating any solid object including Faraday Cages. You can put a transmitter in a box of thick metal and a receiver outside of the box will receive the scalar wave frequency you are pulsing. The potential here is for a transmitter that can penetrate any obstacle or perhaps communicate directly through the Earth from one side of the globe to the other.

2) They are capable of superluminal travel. These waves are claimed not to be electromagnetic, but composed of pure potential energy. Due to this, the speed of light limit does not apply to them. The propagation speed of a scalar wave has been measured as faster than the speed of light and thought by some researchers to be potentially of infinite velocity. (Perhaps SETI - The Search for Extraterrestrial Intelligence - needs a different kind of receiver in order to pick up signals from elsewhere in the universe! Why would advanced ET civilizations even bother using slow transverse waves for interstellar communications?)

3) They are capable of transmitting power. It can then be put to use powering motors, lights, vehicles, etc.

4) A scalar transmitter can wirelessly send power to a receiver through any obstacle. For example, as mentioned above, you can setup a transmitter, put it in a Faraday Cage or a metal box, and a

receiver can receive power far away.

5) During the process of transmission and reception they can magnify power. You can input a certain quantity of power into a scalar wave transmitter and yet the receiver can receive several times the power.

6) Transmitters and receivers can communicate.

7) A conventional transverse wave transmitter cannot sense if a receiver has "tuned in." However, in a scalar system the transmitter and receiver interact because they are in a state of resonance.

As you can see Scalar Waves hold many potential applications for communication, energy, and other applications. To mimic a commercial for a popular brand of cell phone, "Scalar Waves do what Transverse waves don't." They are fast, penetrating, connected, and can broadcast magnified power. These waves are begging to be utilized!

Recipes for Scalar Waves

Nikola Tesla's most famous scalar wave transmitter was his Wardenclyffe tower on Long Island, NY. Prior to that, at the height of his amazing inventive career, he had a lab in Colorado Springs, Colorado. He was able to beam power to receivers miles away that were used to illuminate neon tubes. A great deal is known about his tower, transmitters, and receivers. It is all detailed in his patents. This allows for present day replications!

From examination of Tesla's patents, researchers have learned that perhaps the most critical component of a scalar wave system is the antenna. It is composed of a flat "pancake coil" composed of both a primary and a secondary winding. The coil is connected to a spherical metallic resonator that helps transmit and receive scalar waves.

A particularly good source for information about scalar wave systems is the website of German scientist, author, and researcher, Konstantin Meyl. He has published a series of books that describe scalar wave systems, detail their components, and discuss their operation. His books also dive into the science and physics of scalar waves, among other fascinating topics.

In fact, he offers scalar wave kits for sale on his site. They include all the components needed for a complete system, arrive in an aluminum suitcase that can serve in the same manner as a Faraday cage for your experiments, and come with a book detailing the kit. These kits have been used by experimenters to prove to themselves and others the existence of scalar waves and their unique properties.

Take a look at the following video to see Konstantin demonstrating a scalar wave transmitter and receiver. The same device in the following video is for sale right now on the internet from his website.

M
eyl shows Tesla's longitudinal electricity transmission in Washington
DC at a Tesla,m meeting in 2003!

Even NASA is paying attention to scalar waves to some degree. The paper titled, "Advanced Energetics for Aeronautical Applications: Volume II" by David S. Alexander offers a review of scalar wave (longitudinal wave) research. It mentions the work of Konstantine Meyl and others in the field. Interestingly, the paper also discusses how Dr. James Clerk Maxwell's original equations specifically allowed for scalar or longitudinal waves. Only many years later did short sighted scientists who did not care to deal with Maxwell's complex equations based in "quaternions" mathematics arbitrarily discard longitudinal waves. Due to this, many mainstream scientists doubt their existence despite their history and the mountain of evidence which proves they are very, very real.

Opening Tesla's Technology

Steve Jackson's goal is to open source Tesla's wireless power transmission technology. This is very possible to do, due to the simple nature of



the parts and components required. During his talk he published a list of components required to build a system. This same information can be found in the books of Konstantin Meyl and elsewhere on the internet.

By open sourcing this technology, ordinary individuals could prove to themselves, friends, associates, co-workers, and others that Tesla's technology worked as claimed. Not only does it work, but can be replicated and used for practical applications today. All unique properties of scalar waves could be harnessed and developed to revolutionize our society.

When Steve releases plans, drawings, and other information, probably next week, we will add them to a project page at PESWiki.com. We'll add a link from this page when it is ready.

Earth Changes and the Future

In his books and lectures, Konstantin Meyl has compared superluminal scalar waves to the neutrino, which is also thought by some to travel faster than light. Neutrinos bombard the Earth in all directions, but the majority of them arrive from the central star of our solar system. Due to the fact that approximately half of the neutrinos are absorbed as they pass through the Earth, it is thought they may interact with the core and inner layers of our planet.



Circuit diagram used by Steve comes from Intalek.com, Figure 3.

Some researchers suggest solar phenomenon can produce variations in neutron emissions which may trigger "earth changes" on our planet. This was depicted in the blockbuster movie, 2012, as the cause for the crust disruptions from the mantle heat-up from increased solar activity. Hence, studying and understanding the nature of scalar waves may increase our chance of survival during chaotic periods in the future. Perhaps by understanding them we could eventually learn how to constructively utilize them to stabilize our planet during periods of solar fluctuations, sun spots, flares, etc.

Perhaps with the use of scalar wave technology, earthquakes, volcanic eruptions, or other natural disasters could be prevented or detected ahead of time. Even a one hour warning before an earthquake, such as the one that recent devastated Japan, could save thousands of lives. Although all kinds of unique technologies are possible with scalar waves, at a minimum we need to understand how neutrinos and scalar waves interact without planet. Not doing so could result in needless death and suffering.

Lets get moving!

To not harness scalar wave technology for the benefit of mankind would be tragic. Our civilization is facing adversity in countless forms. Hunger, disease, pollution, poverty, and war threaten our future and the future of our children. Scalar waves exist, they are useful, and the information to build devices that generate and receive them is available to everyone. To better understand our universe, to ensure the continuation of our civilization, and to honor Nikola Tesla we should do our best to support the open sourcing of this technology.

Videos

On March 30, Steve conveyed the following YouTube links showing his presentation to the local IEEE on March 24.

#1 Slide 1 https://www.youtube.com/watch?v=qs-2s85lO6o
#2 Slide 20 https://www.youtube.com/watch?v=s4kvJpUgGKI
#3 Slide 39 https://www.youtube.com/watch?v=4YXPa73NNsA
#4 Slide 57 https://www.youtube.com/watch?v=LqhRDY56CqU
#5 Slide 81 https://www.youtube.com/watch?v=e1Ht5OVyI5Q
#6 Slide 93 https://www.youtube.com/watch?v=JuehDylES_A

Replication Instruction should be done tomorrow.

Contact

Steve can be reached by email at steve.jackson@ieee.org

# # #

This story is also posted at *BeforeItsNews*.

What You Can Do

Recommend 14 people recommend this. Be the first of your friends.

1. Replicate this design.
2. Pass this on to your friends and favorite news sources.
3. We at PES Network are in a pinch right now. Donations would be greatly appreciated.
4. Subscribe to our newsletter to stay abreast of the latest, greatest developments in the free energy sector.
5. Let professionals in the renewable energy sector know about the promise of this technology.

Comments

Feel free to view/post comments down below. The following came in by other means.

Not Scalar "Wave"

On March 27, 2011, 1:45 pm, Karl Palsness wrote:

You should read about Scalar .. it is a "Scalar FIELD" there should be no such thing as a "Scalar wave"; and there is a "Longitudinal Wave", instead of scalar wave. Scalar waves just don't exist according to the word scalar meaning size. A Tesla coil has a scalar field around it...and emits a longitudinal wave....

A Tesla-era dictionary defined it as:

> **Scalar** -- In physics, a quantity which has magnitude, or magnitude and sign only, without direction, such as density, mass, energy, etc., as distinguished from a vector quantity.

and

> **longitudinal wave**: A "pressure" type of wave, similar to sound, in which the vibrations are along the direction of travel of the wave. Hence, a wave composed of alternating densifications and rarefactions, where we focus upon the longitudinal component of the changes.

* * * *

Longitudinal Waves (L.M.D.)s

On April 02, 2011 12:29 AM MST, Dr. Eng. Roberto Handwerker <info {at} deltaavalon.com> wrote:

Dear Sirs,

this mail is a reply to a number of e-mail messages I got from [...], subsequently from Dr. K. Meyl and from Mr. S. Jackson about longitudinal waves ("L.M.D.s").

The matter "L.M.D"s. is not new at all but there is still too much discussion around it from different point of views, i.e. mathematics/physics calculus and electrical devices; this has slowly but definitely led to a total chaos even on the Web, resulting in misunderstanding and disbelief, which doesn't help anybody;

therefore, the best approach for an engineer is to be very straight and careful especially when someone talks about Nikola Tesla and theories about aether and L.M.D.s., still not accepted by the "Academic World" who is as happy to hear such arguments as could be "a sailboat in a forest" so to speak and who brings in turn only useless negative criticism and hectic hysterism instead of helping clarify.

This is why I prefer to proceed "step by step" scientifically replicating some Tesla apparatus and demonstrating his experiments, which is of course not easy because he was the Mozart of the art.

I will present a book about the above and will very soon attend a Meeting in Italy to talk about L.M.D.s and show some working devices to public: it is always a pleasure to demonstrate FACTS and WORKING DEVICES rather than only showing some slides and theoretically discuss matters as "Lorenz gauge vs. Coulomb gauge", "quaternions vs. vectors", "T.E.M. vs. L.M.D." etc. etc. Only facts count, observation of Nature and research: math must consequently follow, as always.

It is therefore more useful instead to bring something new to L.M.D.s tech and to the understanding of Tesla, like for instance my "Tesla power wireless" system with the "small car-demo" shown in my following vids on You Tube (& others under "HorizonDelta"): https://www.youtube.com/watch?v=0BGFF4ltEv and https://www.youtube.com/watch?v=dvZH3RCdeVw

also a tech e-book "Longitudinal dielectric waves in a Tesla coil and quaternionic Maxwell's equations" can be found on my Website for download:

https://www.deltaavalon.com/immagini/L.M.D. waves in a Tesla Coil revised.pdf

I hope the above helped positive discussion and knowledge.

Regards

Dr. Eng. Roberto Handwerker
DELTA Ingegneria

* * * *

The Laplace Operator

On March 31, 2011 2:06 PM MST, Konstantin Meyl wrote:

Subject: Re: About Scalar Field and an Italian Book

There is one comment, making clear, where the problem is localized:

Karl Palsness wrote:

> "You should read about Scalar .. it is a "Scalar FIELD" there should be no such thing as a "Scalar wave"; and there is a "Longitudinal Wave", instead of scalar wave. Scalar waves just don't exist according to the word scalar meaning size. A Tesla coil has a scalar field around it...and emits a longitudinal wave..."

If a scientist is using an expression, he first has to define, what the meaning is. This is what I do in my books, but in America, nobody seems to read my writings. I explain that the scalar wave is nearly the opposite of a scalar field. The expression is more than 200 years old and in mathematics exactly explained by the field equation of Laplace.

The Laplace Operator (describing the distribution of a wave in space) may be separated in 2 parts: grad div - curl curl. The second part is explaining the EM wave, a transverse wave, while the first part gives a scalar wave: The div applied on a vector is scalar! This is why scalar particles or vortices as part of the wave equation are propagating as a scalar wave. But they are propagating in the direction of a field vector and by this the wave is longitudinal and has a direction. In mathematics it is known, that the grad applied on a scalar is a vector again. This is why the scalar wave is propagating in one direction, not in a scalar way, as Karl Palsness wants the scalar wave to do. So he has to read the literature first before he is spreading nonsense in the world wide web.

My opinion about the education in the states is not the best. Lets help to improve it.

* * * *

Other Relevant Coverage

- Featured / OS: Wireless Transmission > Scalar > Tesla > Coils > Jackson >
  Tesla Coils for Dummies - Are you interested in building a Tesla Coil to produce stunning effects that violate the "established" laws of physics, but are somewhat less than technically savvy than a rocket scientist? Then you are in luck, because this article is for you! (*PESN*; April 29, 2011)
- Featured / OS: Wireless Transmission / Electromagnetic > Scalar > Solid State > Tesla > Coils > Jackson >
  Jackson's Wireless Aetheric Power Transmission Open Source Project - To facilitate the replication of these plans, as well as to characterize, optimize, improve, and come up with the zillion applications that can come from it, including: 1) harnessing aetheric energy, 2) superluminal communication, 3) wireless transmission of power through any barrier, 4) anti-gravity capabilities, and 5) creating defensive shields to make conventional war obsolete. (*PESWiki*; April 21, 2011)



- Featured / OS: Wireless Transmission / Electromagnetic > Scalar > Solid State > Tesla > Coils > Jackson >
  Tesla Coils: Unleash the Aether - Nikola Tesla's most significant contribution was not AC power, radio, or the induction motor, but what we call the Tesla Coil - a tool which allows for the power of the aether to be unleashed and harnessed. Now being launched through an open source project. (*PESN* and *BeforeItsNews*; April 19, 2011)
- Featured / OS: Wireless Transmission / Electromagnetic > Scalar > Solid State >
  Tesla's Scalar Field Still Beaming On! - The superluminal (faster than light) scalar or longitudinal waves Nikola Tesla used to magnify and wirelessly transmit power are not just a thing of the past. IEEE engineer, Steve Jackson, discusses and demonstrates how they can be utilized today, and he is open sourcing it here! (*PESN*; March 26, 2011)

See also

Resources at *PESWiki.com*

- Directory:Konstantin Meyl
- Directory:Wireless_Transmission_of_Electricity
- PowerPedia:Wireless_transmission_of_electricity
- PowerPedia:Scalar_field_theory
- Directory:Solid_State_Generators
- PowerPedia:Solid_State_Generator
- Directory:Electromagnetic
- News:Electromagnetic
- More Stories for Hank Mills

- PESN (Pure Energy Systems News) - Feature stories on cutting-edge, clean energy technology.
- Free Energy News (.com) - Daily cutting-edge, clean energy technology news from around the world
- PESWiki Latest - Newest feature pages in the publicly-editable energy directory.
- This Week in Free Energy™ - Weekly live review by PESN, each Thursday 7 pm Mountain time
- Free Energy Now (.net) - in-depth interviews

AdChoices
PowerPoint Free
Tesla

Page composed by Sterling D. Allan March 26, 2011
Last updated September 04, 2012

NOTE: We are presently moderating all comments, to keep out the crass negativity, flaming, and other inappropriate forms of criticism. We welcome constructive criticism tactfully stated. Frequent offenders will be blacklisted.

"It is harder to crack a prejudice than an atom." // "I'd rather be an optimist and a fool than a pessimist and right." -- Albert Einstein

0 Comments Pesn 1 Login

Recommend Share Sort by Newest

Start the discussion…

LOG IN WITH

OR SIGN UP WITH DISQUS ?

Name

Be the first to comment.

Subscribe Add Disqus to your siteAdd DisqusAdd Privacy DISQUS

The "Down and Dirty" Guides to Making Biodiesel at Home
Making
BioDiesel
Books
Save Time, Save Money... Help The Environment!

ADVISORY: With any technology, you take a high risk to invest significant time or money unless (1) independent testing has thoroughly corroborated the technology, (2) the group involved has intellectual rights to the technology, and (3) the group has the ability to make a success of the endeavor.

All truth passes through three stages:
First, it is ridiculed;
Second, it is violently opposed; and
Third, it is accepted as self-evident.
-- Arthur Schopenhauer (1788-1860)

"When you're one step ahead of the crowd you're a genius. When you're two steps ahead, you're a crackpot."
-- Rabbi Shlomo Riskin, (Feb. 1998)

Submit • Privacy • About • Contact

***PESWiki Departments*:**
Latest • News • XML Feed • Directory • Congress • Top 5 • Open Sourcing • PowerPedia

PESN.com

Copyright © 2002-2014, PES Network Inc.

The Tom Bearden Website

Subject: RE: Missing Reference Slide
Date: Mon, 9 Jul 2001 11:58:04 -0500



A DRAMATIC EXTENSION TO NONLINEAR OPTICAL PUMPING

© T.E. BEARDEN 1997

After adding a second vacuum engine, pumping with longitudinal EM waves (pumping in the time domain) deviates the time-reversed trajectory. The mass and its internal structure are translated into a new form with a new structure, which it need never have had.

Yes, that is the slide. It works this way: When you time-reverse a cell, you effectively create a major anti-engine for the cell's exact "engine" (exact set of spacetime curvatures at all levels). Because of the precise one-to-one correspondence, this antiengine then "backs the cell up" along the original time-path it took in its physical functioning and changes, back to a precise earlier condition where the disease or disorder was not present. For a cancer cell, e.g., this backs the cell up past where it was originally "promoted" from a stressed or damaged cell to a tumor cell. That makes it into a "damaged cell". The antiengine continues to act, backing it up further into the state before the damage or disorder occurred. That then constitutes "healing" of that cell in a rigorous sense.

The cloning methods etc. used, do violence to the cell in the process. At the cellular level, damaging it or any part of it in the process changes the resident spacetime curvature engine set, to include the damage. You then "clone" a cell with an imperfect resident engine. The cloned cell then interacts with a large variety of phenomenology, continually altering various subcomponents of its resident engine by taking on additional subengines or changing some of its former subengines. Somewhere later, that festering "delta" in the resident engine -- after sufficient interactions with other environmentally-induced engines, will undergo interactions that "add" two deltas so something detrimental to the organism. At that point, physical damage to the cell erupts in "anomalous" fashion. Actually it erupts by perfectly normal fashion, once the internal engines and their interactions are understood.

This would appear to pose a problem anytime you *artificially* change the subengines of an organism, as in the case of genetically modified food. The small physical damage associated with splicing the genetics has associated with it the injection of such an artificial engine. The interactions of future environmental engines with the spliced genetic organism or plant then remains to be seen. Not all interactions would appear to happen in the limited test time usually allotted for testing the "effects". Anyway, that was the intention.

E.g., Pautrizel demonstrated that immature rats, having immature immune systems, would be restored by the Priore process back to the same immature immune system. The Priore process did not destroy the parasites themselves, but depended upon restoring the immune system back to its first ability to recognize the pathogen and go after it. Priore did not directly "kill" anything! In that case, the pathogens simply re-infected the immature rats, because their immature immune systems could not adequately protect them. It would be the intention of the research, in later generation equipment, to be able to design a specific "extra engine" and introduce it to the pumping, in addition to the "resident engine" in the subject to be treated. That "extra input engine" would accordingly generate a specific "extra antiengine" component in the total antiengine produced. When sufficient research and development maturity has been reached to be able to design such desired "extra engines" to cause the exact, desired extra antiengine to be produced, then the "extra antiengine" technique can be used, e.g., to time-reverse Pautrizel's immature infected rat back to an infected rat with a now-matured immune system. In that case, the rat's stronger immune system would make short work of the pathogen, just as analogously infected mature rats did.

To correct birth defects, etc., obviously one would have to change the actual time-path backwards, to a "state" that the body did not have physically, but which its genetics had before the damage. I foresee that eventually, after some years of development, the process would mature until it could regrow severed limbs, or correct dwarfism, etc. Of course that would be fourth or fifth generation, but it is definitely possible, given sufficient development.

Cheers,

Tom

AD 763210

QUITON/PERCEPTRON PHYSICS: A THEORY OF EXISTENCE, PERCEPTION, AND PHYSICAL PHENOMENA

by

Thomas E. Bearden

March 1973

Approved for public release; distribution unlimited.

U.S. ARMY MATERIEL COMMAND

THE SAM-D PROJECT
REDSTONE ARSENAL, ALABAMA

SURFACE TO
AIR
MISSILE
DEVELOPMENT

AMCPM-MD FORM 1, 1 MAR 71

CONTENTS

Page
I. INTRODUCTION 1
II. EXISTENCE, PERCEPTION, OBSERVATION, AND PHYSICAL PHENOMENA 2
III. MASS AND SPACE 11
IV. IMPACT ON PHYSICS 16
A. Michelson-Morley Experiment 16
B. Gravitational Attraction 17
C. Newton's Third Law of Motion 19
D. Newton's Second Law of Motion 20
E. Newton's First Law of Motion 22
F. Identity of Length and Time 23
V. ELEMENTARY PHILOSOPHICAL IMPLICATIONS 25
A. Existence, Thing, and One 25
B. Reality, Ultimate Reality, Being, and Ultimate Being 27
VI. CAUSALITY AND ITS MODIFICATION 28
VII. CLOSING REMARKS 35

ABSTRACT

A fundamental answer is attempted to the questions of being, time, space, existence, perception, and physical phenomena. Mass, empty space, reality, gravitational attraction, continuity, discontinuity, and relativity are among the "things" and "nonthings" for which relationships and explanations are provided.

Perception is defined as detection by a mass of change to itself and as a differentiating process. Perceived physical phenomena are revealed to be first derivatives of ultimate reality, and outputs of the physical perceiving device call the "perceptron." Using the operation of the physical perception process on action, the units of which are energy times time, an entirely different view is generated of both reality and the Heisenberg uncertainty principle. When superposition is imposed as a condition, the Heisenberg uncertainty principle is revealed to be a quantized statement. A concept of the absolute value of a dimensional molecule is advanced.

A reality model is constructed of an action continuum and a nonaction continuum separated by an operational threshold whose magnitude is given by an uncertainty principle. Perception is modeled as a process which switches atomic quanta of action and nonaction back and forth across the threshold. Mass is explained as perceptron switch activity rate, and a mass definition equation is generated. One kilogram mass is shown to represent 17.053 x 10^{50} perceptron switches per second. From the model, Newton's laws of motion and gravity can be generated directly from the concept of the interaction of mass with space itself, space being taken as a massless fluid, or ether, composed of tiny nonaction particles called "quitons." Einstein's postulates of special relativity are also shown to follow from the model, and a statement of the equivalence principle is shown to be consistent with the model.

The concept of "lineception" as a causal chain of perceptron operations is advanced. "Inception" is developed as a noncausal modulation of lineception and as a distinguishing feature of a living system. The possibility is raised that inception could provide an explanation of the noncausal, statistical, ultramicroscopic universe and yet require large ensembles of ultramicroscopic events to conform to causality. Inception is shown to lead to karma. Perception is shown to be causal and to generate causality itself.

Some elementary philosophical implications of quiton/perceptron theory are pointed out and briefly discussed.

I. INTRODUCTION

The unsolved problems of physics stem from the unclear nature of the physical perception of change, and their resolution lies in the analysis of perception as a physical process. The unsolved problems of metaphysics stem from the same source, and can be resolved by the same perception analysis.

Specifically, a physical detection system can detect changes to itself and nothing else. These detected internal changes are thus what a detector "sees" or "observes" or "perceives" as changes to its external environment, i. e., as its physical phenomena. Thus a mass, being itself a physical detecting system, must detect only changes to itself, and these perceived changes to itself constitute its observed physical phenomena. For that reason, these perceived changes are obviously entirely relative to (i. e., are part of) the perceiver (observer); more precisely, they are entirely relative to and part of the perceiver's mass, which is the detector that is doing the perceiving.

Since only changes are perceived by a mass, then mass's perception must be a differentiating process. Ergo, perceived physical phenomena are first derivatives of a higher, or more fundamental, reality. The nature of that higher reality is by definition unperceivable (perception differentiates or fragments it), and it involves the quantity "action."[1] Action itself is not perceivable; change of action is perceivable since perception differentiates action. If superposition is placed on the Heisenberg uncertainty principle as a required condition, then the uncertainty principle contradicts itself for all except integral or zero multiples of a quantum of action. Correction of the uncertainty principle by imposing superposition as a condition provides a statement of the basic operation of perception -- the detection by a mass of change to itself.

All mental perception of a human being regarding physical phenomena is received (i. e., is inputted to the mind) from a physical sensory apparatus whose primary ingredient is mass. Thus we may describe the perceptive mind as consisting of sensory outputs of mass perceptions; that is, the input to mental perception must be the output of mass perception, and this interface within the mind may be referred to as the "perceptive mind."

From the above foundation, a comprehensive theory of perception can be constructed, and a most unusual model of "reality" emerges. A variety of unsolved questions are then resolved by the model. The resolutions include, among other things, 1) derivation of the postulates of relativity; 2) definition of the nature of time and space; 3) the explanation of gravity; 4) the generation of causality itself; 5) resolution of the wave theory of light with the quantum theory of light; 6) the explanation of why ultramicroscopic phenomena are statistical yet large ensembles of ultramicroscopic phenomena are causal; and 7) validation of Mach's principle and the equivalence principle. A totally new and precise definition of mass and of being itself are also two unexpected results. The problems of metaphysics are also answered: metaphysics is elevated to an exact science without any tinge of dogma, and physics and metaphysics are united.

---

[1] Planck's constant, Heisenberg's uncertainty principle, the principle of least action, the energy of a photon, etc., are derived from action and perception's differentiation of action.

Next Page

II. EXISTENCE, PERCEPTION, OBSERVATION AND PHYSICAL PHENOMENA

We first define perception[1] as detection by a mass of change[2] to itself, and state that it is an operation performed by that mass. The physical apparatus that accomplishes this perception is termed a "perceptron," which thus may be an electron, an atom, or the sensory apparatus of a living being.

A change detector does not detect the state of its input, but rather detects changes in that state. So in this sense a change detector can be regarded as a state differentiator. Therefore a perceptron differentiates, i. e., it perceives changes in its input and generates outputs in accordance. When its input is constant it will have no output. Thus zero output of a perceptron does not necessarily mean zero input.

What is to be fed into the perceptron's input section exists; i. e., existence (ultimate reality)[3] is defined as what is to be fed into the perceptron's input. The output of the perceptron is that which is perceived, or what we ordinarily call "physical phenomena."[4] Since the perceptron differentiates its input state, then physical phenomena are first derivatives of ultimate reality, which precisely accounts for the sharp separation between observable and nonobservable, i. e., between macroscopic and microscopic.

Any change in a perceptron's input section must involve both time change, Δt, and energy change, ΔE. So we may assume their product, $\Delta E \Delta t$, has always occurred in a perceptron's input whenever it produces an output. The output will be a derivative of the input, e. g.,

$$\frac{\Delta E \Delta t}{\Delta t} = \Delta E \tag{1}$$

and

$$\frac{\Delta E \Delta t}{\Delta E} = \Delta t \, , \tag{2}$$

where in each case the constant of proportionality has been ignored.

---

[1] We differentiate between perception and realization. Perception is entirely a physical process, and causal. Realization is a mental process and is not restricted to causal relationships.

[2] Reflecting, one notes that mass can only change in a nonmass manner. It cannot "change" without involving space and time, both of which are "nonmass." Therefore a mass change must be composed of both mass and nonmass.

[3] "Ultimate" in that it is higher or more fundamental than perceived reality.

[4] Changes to mass and only changes to mass constitute physical phenomena. Changes to one mass constitute "its" perceived physical phenomena, or its physical universe.



"Changes to mass and only changes to mass constitute physical phenomena. Changes to one mass constitute "its" perceived physical phenomena, or its physical universe. Since the other masses in its universe are perceived by it (i.e., created in its perception by its perception process), then these masses must be entirely relative to the mass perceptron that perceives them. Ergo, perceived mass is relative to the perceiver.

Next Page

Any detector has an operational input threshold, i.e., a minimum discernible signal. The Heisenberg uncertainty principle states the requirement for such energy-time changes:

$$\Delta E \Delta t \geqslant \hbar/2 \,. \tag{3}$$

Its smallest value, or

$$\Delta E \Delta t = \hbar/2 \,, \tag{4}$$

is then the input threshold for a physical perceptron to operate and produce an output.[1] Letting $k = \hbar/2$, we can write this simply as

$$\Delta E \Delta t = k \,. \tag{5}$$

Since existence has been defined as that which is fed into the perceptron's input, then that existence exists whether or not the perceptron operates, and the case[2] where

$$\Delta E \Delta t < k \,, \tag{6}$$

also exists (i.e., can be present in the input of a perceptron) but cannot be perceived or detected (i.e., the perceptron will not operate and produce an output).

At this point we diverge to remark that the product of energy and time is a quantity called "action," and the units of action are

$$A \equiv \frac{ML^2}{T} \tag{7}$$

Thus the input state to a perceptron is composed of an action continuum,[3] and the perceptron differentiates action quanta to produce physical phenomena.

---

[1] We acknowledge additional uncertainty statements but for simplicity will use only one in this paper.

[2] Equation (6) exists and it is proper to write it down and search out its ramifications. Equation (3) is a limiting condition which applies only to mass. But since our physical experience must involve nonmass (e.g., photons, space, time, being), then nonmass considerations must be examined. A good beginning is to consider the entire field of nonmass possibility, i.e., that field of nonmatter changes defined by (6), which includes the entire subquantum domain. So we legitimately examine two conditions: Eq. (3) must define (or apply as a condition to) the mass phenomena (change, quantized) system, and (6) must define (or apply to) the nonmass phenomena (subquantum) system.

[3] We exactly define continuity as the failure to perceive difference (change), and



phenomena (subquantum) system.

[3] We exactly define continuity as the failure to perceive difference (change), and discontinuity as the perception of difference (change). The difference between continuous and discontinuous is entirely one of perception. Thus there are two kinds of continuity: absence of perceptron operation at all, and identically repeated perceptron operations. The first kind exists outside of perception while the second kind exists in perception-to-perception. These are two powerful definitions, which among other things enable one to understand such concepts as limiting process, derivative, point, line, and plane. Mathematics itself is the game of perception, nothing more and nothing less.

Next Page

When a large quantity of action is to be fed into a perfect perceptron, the input process cannot occur instantaneously; a Δt must be outputted (created)[1] by the perceptron for each operation. Thus perception processes steps or quanta of exactly k size, and exactly k size only. Inputs of less than k size are simply collected[2] until the aggregate is equal to k, then differentiated to produce an output. We must therefore rewrite the Heisenberg uncertainty principle as

$$\Delta A = nk \qquad , n = \pm 0, 1, 2, \ldots \quad , \tag{8}$$

where the plus and minus signs are necessary since action only has to change about some constant level in the perceptron input, and this change may be either additive or reductive (this quantum statement is actually the basis for quantum physics).[3] Thus, from the viewpoint of a perceptron, its output universe of physical phenomena is constructed by successive granular differentiation of unit operations, each of size k, but it detects no time lapse (creates no Δt) between operations.

When differentiated by a perceptron, an action atom may be regarded as being "chopped up" (the word "differentiated" literally means separated or torn apart):

$$\frac{\Delta E \Delta t}{n} = \frac{k}{n} \quad \overline{A} , \qquad n = 2, 3, 4, \ldots \quad , \tag{9}$$

where the bar over the A indicates nonaction, or action atoms which have been broken into bits.

Thus we now conceive of an action continuum of action atoms and a nonaction continuum[4] of bits of action atoms. The two continua coexist and the perceptron

---

[1] Or "extracted from an action quantum $\Delta E \Delta t$," which means exactly the same as "created." Einstein's treatment of simultaneity showed that it was operational, but if simultaneity itself is operationally created then both time and length must also be operationally created.

[2] This is not a simple discontinuous operation, since no time flow exists (Δt is not being outputted) during this collection process. We have to think of the process discontinuously, but the stepwise process is actually continuous (in time), or discontinuous, or both.

[3] Since ΔE may be positive or negative, we may state the uncertainty principle as $|\Delta E \Delta t| \geqslant k$, or as $\Delta A = nk$, $|n| \geqslant 1$. Consider the two cases $\Delta A > 0$, $n = 1$, and $\Delta A < 0$, $-1 < n < -2$. Superimposing them would give $|\Delta A| < k$, which violates the uncertainty principle. Thus, assuming superposition must hold, the uncertainty principle can be made to violate itself for all except integral values of n, and it follows that the Heisenberg uncertainty principle must be written as a quantized statement.

[4] The separation into two continua is artificial, but is necessary to allow us to perceive perceptron operation with our brain perceptron mind. There is absolutely



"The separation into two continua is artificial, but is necessary to allow us to perceive perceptron operation with our brain perceptron mind. There is absolutely no separation in the reality continuum itself; rather, there is only an operational separation caused by and in perception. Hegel was very nearly correct in his realization that the dialectical principle was the magic key to the universe of perceived phenomena. However, thesis (action) and antithesis (nonaction) do not meet to give a synthesis (the transfer function or switching) which is different from either; rather, thesis (action) is changed (transferred or switched) to its antithesis (nonaction) and vice versa. It is the switching or transfer process that is the synthesis (output of the perceptron, perception) which is different from the thesis and the antithesis.

Next Page

operates, or moves, in them. Only action quanta of exactly k size can be processed by the operating perceptron to give outputs which we know as physical phenomena. Such phenomena (events) consist of aggregates of extremely large numbers of perceptron operations. Action atoms will be referred to simply as "action atoms." The very smallest bits or fragments[1] of action atoms will be referred to as "quitons" and the symbol "q" used for one quiton. For convenience, we shall regard the "magnitude"[2] of q to be very much less than k, or

$$q \ll k . \tag{10}$$

The perceptron's process of collecting quitons to form action atoms will be termed "fusion," which is an additive change to the constant action continuum. "Fission" will be the term for the perceptron's process of breaking up action atoms into aggregates of quitons, where the size of each aggregate is less than k; fission is a reductive change to the constant action continuum. The term "switching" will be used to refer to either fission or fusion, or both.[3]

Fission and fusion are merely transfers or switches across the k-threshold separating the action and nonaction continua, and may be represented by either of the diagrams shown in Fig. 1.



Fig. 1. Continua of the Universe

---

[1] These are actually nonthings and not bits or pieces at all, but since we can only perceive or think of things, we will model them as things. The difficulty is in the nature of thought, not in the nature of reality.

[2] The perceivable magnitude of a quiton is zero, i.e., it is not perceivable.

[3] And, in fact, switching can also refer to the transfer of Δt into ΔL, i.e., the creation of space from time or vice versa. Separation (relation) is composed of ΔL and Δt, and we know from relativity that when relativistic (perceived) ΔL is changed, then relativistic (perceived) Δt is also changed. When time dilates, length contracts; and when time shrinks, length expands. Therefore the statement that length and time are intertransferrable is valid: one kind of separation can be transferred into another kind of separation just as one kind of energy can be changed into another kind of energy. Since this transfer itself is an operation, then there is a rate (i.e., a constant) of transfer. This constant is actually a parameter, since by special relativity it can vary as a function of the mass changes themselves. And since we are dealing with mass changes (perception), then the rate of transfer constitutes a rate of mass change (rate of perception). Since perception is finite



since by special relativity it can vary as a function of the mass changes themselves. And since we are dealing with mass changes (perception), then the rate of transfer constitutes a rate of mass change (rate of perception). Since perception is finite, perceived mass change cannot be infinite but must also be finite. Therefore a limiting rate of perception must exist. From the equations of special relativity, this limiting rate of perception or mass change is c, the speed of light, and its value may be taken as the rate of change of a mass switch itself.

Next Page

We now examine the expression for energy of a photon:

$$E = hf \tag{11}$$

Considering fission of an action atom as a chopping of that atom, the process can be expressed by:[1]

$$\begin{bmatrix}\text{Minimum} \\ \text{time rate of} \\ \text{change of action}\end{bmatrix} = \begin{bmatrix}\text{Energy} \\ \text{Transferred}\end{bmatrix} \simeq \begin{bmatrix}\text{atom of} \\ \text{action}\end{bmatrix} \begin{bmatrix}\text{cuts or chops} \\ \text{per second}\end{bmatrix}, \tag{12}$$

or

$$\frac{\Delta A}{\Delta t} = \Delta E = C_1 kf , \tag{13}$$

where C_1 is a constant of proportionality. According to Eq. (1), the energy perceived to be expended (transferred to quiton disturbances) in fissioning of an action atom ought to be proportional to the speed of the chopping action. Neglecting constants of proportionality, Eq. (13) is simply[2]

$$\Delta E = hf , \tag{14}$$

where the Δ symbol is deliberately added to show that it is a transfer process. The equation works in reverse for fusion of quitons into action atoms, i. e., the energy ΔE transferred to each action atom assembled is proportional to its rate of assembly.

We can now represent a perceptron as shown in Fig. 2, which corresponds precisely to the two-pronged arrows shown in the diagrams of Fig. 1. A perceptron has two channels, fission and fusion, in which switching transfers between action and nonaction are involved.

By Eq. (2), one of the outputs of a perceptron is Δt. Since perception creates its own time interval, it only has its kind of time, i. e., positive time, to deal with. Thus only positive time is perceived, and what we think of as positive time flow is merely the successive Δt's created by perception.[3]

---

[1] Note how admirably the view of tearing apart or differentiating the action atom describes the result. The smaller the Δt torn from $(\Delta E\ \Delta t)$ (or the quicker the separation), the larger the ΔE left (produced), i.e., the more energetic the separation. The atom of action is a quantum of action and one integral piece; the ΔE and Δt, however, are not necessarily of individually fixed size.



ΔE and Δt, however, are not necessarily of individually fixed size.

[2] Action atoms can occur in more than one size (see note 1 on p. 3).

[3] This explains why we sense existence as if we were the point of contact of a pointer moving along a time line. In effect, perceptron time advances one time slice at a time, where the slice is of Δt thickness. Thus all physical phenomena occur in minute granular sequences.

Next Page


ACTION AND NONACTION CONTINUA
BITER (ATOMS)
CHOPPER (FISSION)
FRAGMENTS (QUITONS)
SCOOPER (QUITONS)
ASSEMBLER (FUSION)
ACTION ATOMS
APPARENT PERCEPTION MOTION
INTERFACE
REALITY CONTINUUM (EXISTENCE)

Fig. 2. The Fundamental Perceptron Switch

The existence of a negative time flow can be postulated by a simple symmetry analogy, but this postulated negative time, by definition, cannot be a perceptron output. We use the term "reflection" to denote a postulated operation in negative time[1] symmetrical to perception which operates only in positive time. Reflection is essential to the explanation of electric charge and charge effects,[2] but these will not be discussed here. Figures 3, 4, and 5 summarize the concepts of reflection, perception, and positive and negative time.

We now introduce the concept of absolute value of a dimensional molecule.[3] To illustrate, if we know that F = Ma, we will state that

$$|F| \equiv |Ma| \equiv |M| \times |a| = M\ |a| \quad , \tag{15}$$

where the last expression is true because of the nondivisibility of the unit ΔL and

---

[1] Modern theorists such as Feynman, Wheeler, and Dirac of necessity incorporate negative time operation into their theories involving action-at-a-distance.

[2] The quiton/perceptron theory can and does explain what "charge" is, why like charges repel and unlike charges attract, etc. It predicts the force of attraction or repulsion to be proportional to Q_1Q_2/R^2.

[3] Although perceptron output bits may vary in magnitude from operation to operation,



[3] Although perceptron output bits may vary in magnitude from operation to operation, they are of absolutely fixed size in any one operation or between any two consecutive operations. So for one operation or any two consecutive operations, a dimensional molecule is merely a product and division of certain-sized bits, and is itself of one fixed magnitude. Any other dimensional quantity of equal absolute value is therefore of the same size for that operation. At this level, differentiation is simple bit division and integration is simple bit multiplication.

Next Page


UNIVERSAL CONTINUUM
(EXISTENCE)
POSITIVE TIME
PERCEPTION
ACTION CONTINUUM
NONACTION CONTINUUM
REFLECTION
NEGATIVE TIME

Fig. 3. The Continua (Complete Model)


ACTION CONTINUUM
PERCEPTION
NONACTION CONTINUUM
(POSITIVE TIME)
(POSITIVE TIME)

Fig. 4. The Positive Time Continua -- Model in Which Perception Acts


ACTION CONTINUUM
NONACTION CONTINUUM
REFLECTION
(NEGATIVE TIME)
(NEGATIVE TIME)

Fig. 5. The Negative Time Continua -- Model in Which Perception Does Not Act

Next Page

Δt quanta outputted by one perceptron operation. The absolute value signs must be added to any dimensional molecule which can take on either positive or negative values. Dimensionally,

$$M_0 = |E| \quad , \tag{16}$$

where M_0 is rest mass and requires no absolute value sign since a quantity of rest mass is only positive. Actually, since perceptron operation only outputs quanta, then the perceptron outputs ΔE and ΔM_0, or

$$\Delta M_0 = \left|\Delta E\right| \quad , \tag{17}$$

and repetition rate allows perception of M_0 as a positive quantity. Then

$$\frac{\Delta A}{\Delta M} \longrightarrow \frac{\Delta(L^2)}{\Delta t} \quad . \tag{18}$$

The perceptron expression of the right-hand side of (18) will be[1]

$$\frac{\Delta(L^2)}{\Delta t} \longrightarrow \frac{\Delta L \Delta L}{\Delta t} \longrightarrow \Delta L\,(V) \quad , \tag{19}$$

and then we have

$$\Delta E \Delta t(V/V) \longrightarrow \frac{\Delta E(V\Delta t)}{V} \longrightarrow \Delta P(\Delta t)(\Delta L/\Delta t) \longrightarrow \Delta P \Delta L \quad , \tag{20}$$

which must be another statement of the minimum condition of the Heisenberg uncertainty principle, or

$$k = \Delta P \Delta L \quad . \tag{21}$$

It follows that

$$\Delta P \Delta L = nk, \qquad n = \pm 0, \pm 1, \pm 2, \ldots \tag{21a}$$

To consider why constant velocity yields special relativity, from $E = ML^2/T^2$ and Eq. (16), we can write

$$M = \left|\frac{ML^2}{T^2}\right| = M\left|\frac{L^2}{T^2}\right| \quad . \tag{22}$$

Dividing out the M gives



$$1 = \left|\frac{L^2}{T^2}\right| = \left|\frac{L}{T}\right| = \frac{|L|}{|T|} = |V| \; . \qquad (23)$$

---

[1] Obviously $\Delta(L^2) = 2L\Delta L + (\Delta L)^2$, but the units of $2L\Delta L$ are $\Delta L\Delta L$.

Next Page

So velocity is a dimensionless quantity in the absolute dimensional sense, i. e., in the perceptron operational sense, and "the laws of physics apply equally well for all observers as long as they are moving with constant velocities" (Einstein's postulate). When the perceptron process is applied to a system of objects whose relative velocities are constant, the inputs to perception always differ by a constant value and the differentiated outputs of perception do not differ, i. e., the differential of $f(x) + C_1$ is identical to the differential of $f(x)$.[1]

Observation is related to perception as shown in Fig. 6. An observer observes only perceptron outputs[2] -- never ultimate reality -- from his sensory apparatuses.


PERCEPTION
REALITY CONTINUUM (EXISTENCE)
FORMATION OF PERCEPTION INPUTS (THIS BLOCK MAY BE REPLACED BY FIGURE 3)
DIFFERENTIATION (COMPARISON OF INPUTS)
PERCEPTION OUTPUTS* (PHYSICAL PHENOMENA)
FORMATION OF ANALOGUES BY OBSERVER*
OBSERVER PROCESSING
OBSERVER OUTPUT ANALOGUES (CONCLUSIONS)
OBSERVATION
THIS IS A PHYSICAL PROCESS PERFORMED BY A MASS PARTICLE OR PARTICLES, WHICH MAY OR MAY NOT BE IN THE PHYSICAL SENSORY APPARATUS OF A HUMAN BEING.
THIS IS IN THE "MIND" OR "BEING" OF THE LIVING ENTITY AND IS NOT (YET!) SUBJECT TO PHYSICAL ANALYSIS.
*THE TWO SHADED BLOCKS REPRESENT THE INTERFACE BETWEEN MASS PERCEPTION AND "MENTAL" PERCEPTION; THESE TWO BLOCKS CONSTITUTE THE PERCEPTIVE MIND. THIS IS ALSO THE INTERFACE BETWEEN PHYSICS AND METAPHYSICS.

Fig. 6. Overall Relationships

---

[1] Einstein's treatments of simultaneity and special relativity may be regarded as



---

[1] Einstein's treatments of simultaneity and special relativity may be regarded as statements that one can determine a length (measure a ΔL) only by $\Delta L \equiv c\Delta t$, and one can determine (measure) a Δt only by $\Delta t \equiv \Delta L/c$ in the static case.

[2] The process of observation actually consists of both perception and realization.

Next Page

III. MASS AND SPACE

The nonaction continuum may be further visualized as a sea or gas of small, unperceivable particles, i. e., of quitons and aggregates of quitons which are less than k in magnitude. Since mass is a perceived quantity and a quiton cannot be perceived, a quiton or aggregate of less than k magnitude has zero mass.

Since fission and fusion both constitute perceptron switching, we may explain mass by visualizing a changing pile of quiton bundles, each of k size, in which the total rate of switching activity is what we call the "mass"[1] of the pile. Thus the mass is equal to the sum of the absolute values of the fission and fusion activities:

$$M \equiv \left|\frac{\Delta A_i}{\Delta t}\right| + \left|\frac{\Delta A_o}{\Delta t}\right| \simeq \left|\dot{n}_i + \dot{n}_o\right| \quad k \;, \tag{24}$$

or

$$M \simeq \left|\dot{n}_i + \dot{n}_o\right| \qquad \text{sw/sec}, \tag{25}$$

where[2]

Δt = perceptron operation time (one operation)

M = perceived mass of the pile

ΔA_i = action created from fu~~z~~sing quitons into action atoms

ΔA_o = action lost from fissioning action atoms into quitons

$\dot{n}_i$ = number of k-sized bundles per second fused into atoms

$\dot{n}_o$ = number of atoms per second fissioned into quitons

sw/sec = one perceptron operation per second.

---

[1] If ΔE is time rate of change of action, and if the absolute dimensional value of rest mass and rest mass energy are the same, then mass must also be a time rate of change of action. One kilogram mass equals 17.053×10^{50} sw/sec.

[2] The switch concept is necessary to explain charge and charge effects. The switching occurs between the positive (perception outputted) and negative (reflection outputted) time streams. Three types of switches exist, two of which are charge switches and all of which are mass switches. Switching may also be regarded as change of Δt into ΔL. For a mass switch, the limiting value of the conversion parameter b in ($\Delta L = b\Delta t$) is c, the speed of light. However, the

regarded as change of Δt into ΔL. For a mass switch, the limiting value of the conversion parameter b in ($\Delta L = b\Delta t$) is c, the speed of light. However, the concept of switching can be expanded; $b < c$ implies mass switching; $b = c$ implies quitons moving (maximum switching limit for mass switching); $b > c$ implies DeBroglie waves moving, which are not switching in the normal sense at all. Technically, the condition $b < c$ applies to Eqs. (24) and (25).

Next Page

The use of the mass definition equation can be illustrated by a simple example. First,

$$k \equiv h/2 = 0.527 \times 10^{-34} \text{ joule-sec} \tag{26}$$

$$1 \text{ kg mass} = 8.987 \times 10^{16} \text{ joules ,} \tag{27}$$

so

$$1 \text{ kg mass} = \frac{8.987 \times 10^{16} \text{ joules}}{0.527 \times 10^{-34} \text{ joule-sec/switch}} \tag{28}$$

$$1 \text{ kg mass} = 17.053 \times 10^{50} \text{ switches/sec.} \tag{29}$$

For a mass that does not accelerate, switches must occur in couplets. This would require, for example, that angular momentum be quantized in quanta of 2k magnitude, since two switches would process two action atoms -- one in and one out of the mass action pile. Since

$$2k = h/2\pi \ , \tag{30}$$

then angular momentum should be quantized in $h/2\pi$ quanta, which indeed it is: from the Bohr theory of the hydrogen atom,[1]

$$mvr = \frac{nh}{2\pi} \qquad , \ n = 0, 1, 2, \ldots \ , \tag{31}$$

and the change permitted is thus

$$\Delta(mvr) = \frac{nh}{2\pi} \qquad , \ n = 0, \ \pm 1, \pm 2, \pm 3, \ldots \tag{32}$$

What we normally think of as empty space is sometimes described as the absence of mass and energy, existing in time.[2] Empty space can be defined by

$$\frac{\Delta A}{\Delta t} = 0; \qquad \frac{\Delta \bar{A}}{\Delta t} = 0 \ , \tag{33}$$

which merely state that no perceptron output is occurring. Thus empty space exists only as defined by a perceptron and is merely the total absence of perception. While these equations rule out fission and fusion, they do not rule out the static presence of large numbers of quitons and quiton aggregates each of which is less than k in size (a quiton may be viewed as a quantum of space or a quantum of ether).

---

[1] Beiser, Concepts of Modern Physics, McGraw Hill, 1963.

[2] Actually there is no time connected with the existence of space; the time is connected only with our perception of change; that is, space is a product of perception, or the nonoperation of perception, and is related to a mass perceptron. Similarly, space itself has no length -- length is relative between two masses. That is why both length and time can change, and why a specific length and a specific time can

space itself has no length -- length is relative between two masses. That is why both length and time can change, and why a specific length and a specific time can be different to different observers.

Next Page

A massless quiton cannot individually generate any drag resistance against matter in the Newtonian sense. So a mass object moving along at a constant velocity will just push a stream of massless quitons ahead of it. In effect, the mass "bulldozer" is pushing its own medium along with it, and this requires no force.[1] Therefore, empty space (i. e., the zero output condition of one's mass perceptron) is filled with (has added to it) streams and streams of quitons moving ahead of other objects (perceived by one's perceptron) from all over the universe (perceived by one's perceptron). These quiton streams may be regarded as quiton pulses or quiton waves[2] in one's own static-relative quiton pond. The static-relative quiton pond of a mass will be called its "q-space" or "space" (more commonly referred to as the mass's inertial frame of reference).

When impinging on a perceptron's mass, these disturbances are being collected into k-sized quanta and switched into action atoms. The switching produces outputs that reveal the presences of the disturbing masses. The situation for a perceived mass is described in Fig. 7. Note that a fusion pileup is shown in front of the perceived object due to the object's motion, and a fission pileup is shown at the rear (switching is actually distributed throughout). Additional switching is occurring in the pileups and constitutes increase in mass. So one's mass perceptron perceives the moving object's mass as having increased. The relative velocity of the object with respect to one's perceptron determines the additional collection rate of quitons, and hence the additional switching rate, occurring for the object in one's perceptron q-space. The perceived increase in the moving body's mass is a function of the increased collection rate, which is a function of both the initial mass switch size M_0 and the velocity V, or

$$M = f(V,\ M_0)\ . \tag{34}$$


MASS BULLDOZER
PERCEIVER'S STATIC-RELATIVE QUITON POND
VELOCITY
REAR PILEUP
FRONTAL PILEUP
SWITCHING ACTIVITY PILEUPS FROM PERCEIVER'S STATIC-RELATIVE QUITON POND

Fig. 7. Increased Perceiver Switching Due to Perceived Velocity

---



---

[1] More precisely, it requires no resultant (unbalanced) force. Both fission and fusion create forces; however, these forces are opposing, and so when fission rate equals fusion rate the resultant force is zero.

[2] These pulses or waves are not in themselves perceived, so one can equally well consider them bunches of particles or waves. The difficulty lies with the perceptron mind, not with the disturbances.

Next Page

If the perceiver shifts "his view" to the object, he would at the same time shift his perceptron to it and so would then see the same sort of effect existing on his vacated mass. The pileup is relative to the perceiver and is occurring in the perceiver's perceptron itself.[1] So material objects do not just move through an ether, they carry their own q-space ethers right along with them.[2] And all they can detect is the disturbances in that q-space that produces switching transfers in and out of the action and nonaction continua.

We now wish to know the standard medium velocity at which wave disturbances move in the q-space. The question is, what has zero mass, is unperceivable, and yet can move through the perceiver's empty space ether[3] at some standard velocity? Photons satisfy all these requirements. Photons themselves cannot be perceived -- only their interactions can; and photons move in free space at the velocity c, the speed of light. Thus c is the quiton medium's wave velocity[4] and quiton disturbances move in a q-space at the velocity c. They move only in a q-space and in nothing else, since movement (velocity) is defined as $\Delta L/\Delta t$, and both ΔL and Δt exist only to the perceptron that created them. Therefore, velocity of a perceived object is absolutely relative to the perceiver since it is part of the perceiver's mass's perception. At this point, Einstein's postulate that "the speed of light is the same for every observer" can be seen to follow directly from the quiton/perceptron model.

But a difference exists between the speed of light in q-space and the speed of light in a medium. Simply speaking, when light travels in a medium the quiton waves (photons) are perceived to interact with particles (get switched by other switches) continually. In each imposed interaction switching perceived, another Δt occurs in the perceiver's perceptron. Thus more Δt's occur, and the photon is perceived to take longer in traveling through the medium than through free q-space; that is, the perceiver's perceptron (in which the medium itself exists) creates more time output in the case of light traveling through a perceived medium than light traveling through unperceived free q-space.

---

[1] This point is emphasized. The mass's mass does not increase as perceived by itself; its mass does increase as seen by the perceiver. This fact alone is sufficient to establish that the increase in mass is subjective, not objective (although these two terms are usually misused). That is what the term "relative" means, i.e., relative to the subject. Note that the perceiver is always the subject. The fact that the effect occurs only to the perceiver should indicate that it is the perceiver's perception process which is causing the effect.

[2] Thus one can have one space moving through another space.

[3] From Einstein's Theory of Relativity by Max Born, p. 224: "Einstein in later years proposed calling empty space equipped with gravitational and electromagnetic fields the 'ether,' whereby, however, this word is not to denote a substance with its traditional attributes. Thus in the 'ether,' there are to be no determinable points, and it is meaningless to speak of motion relative to the 'ether.' Such a use of the word 'ether' is of course quite admissible, and when once it has been sanctioned by usage in this way, probably quite convenient." The use of "ether" here is quite close to Einstein's proposal; however, in our usage it is meaningful to speak of "perceived motion of a perceived object" in the q-space ether of the perceiver. Otherwise, there can be no observation and no observer, which are of course necessary



"perceived motion of a perceived object" in the q-space ether of the perceiver. Otherwise, there can be no observation and no observer, which are of course necessary to Einstein's theory.

[4] Velocity is unperceivable; it is actually the constant of proportionality for the perceptron's direct transposition of Δt into ΔL. And c, the constant velocity of light, represents the limit of the perceptron's ability to do this.

Next Page

It should be noted, but will not be pursued further here, that electromagnetic waves in space are merely quiton wave disturbances[1] moving in a perceptron's q-space. The energy being transmitted is the "energy equivalence" of the nonaction quiton aggregates that were chopped up from action atoms. When these fissioned aggregates are again collected in some perceptron, then $\overline{\Delta E}$ is recovered as ΔE, or perhaps as ΔM.

In passing, we note that hidden in the principle of complementarity is the fact that wave and particle are operationally excluded, i. e., separated by an operation. A wave by definition is operational (dynamic). The most elementary idea involved in the concept of a particle is that it is nonoperational; i. e., it doesn't have to move, or change, or function, or be dynamic to exist. Obviously that which is operational differs from (is separated from) that which is nonoperational, but such separation itself is differentiation which is an operation. Therefore, wave (operation) and particle (nonoperation) are operationally separated. The only "mystery" in complementarity is that one must stop (interfere with) an operational entity to have a nonoperational entity, and one must start (interfere with) a nonoperational entity to have an operational entity. Depending upon the conditions imposed upon it, an entity can be either operational or nonoperational. For example, the operation of superposition must be imposed upon DeBroglie waves before they can constitute a particle. It then follows that the particle's velocity must in fact be the velocity of the superimposed group, i. e., the wave packet's velocity. By the same reasoning it follows that one cannot measure a particle's exact position (which is a static or nonoperational entity) and its exact momentum (which is a moving or operational entity) at the same time. The same is true for the particle's exact time position (nonoperational) and its exact kinetic energy (operational). Thus uncertainty principles, complementarity, and the relationship of DeBroglie wave velocity to wave packet velocity all involve the one fundamental concept that an operational entity is separated from a nonoperational entity by an operation. The changing is separated from the unchanging by a change; i. e., the changing is operationally derived from the unchanging, or perceived reality is derived from unperceived reality.

---

[1] Photons are aggregates of quitons; quiton aggregate behavior is particulate. Behavior from the standpoint of individual quitons is wave-like. This explains the dual behavior of light and reconciles its wave and quantum aspects.

Next Page

IV. IMPACT ON PHYSICS

A. MICHELSON-MORLEY EXPERIMENT

The Michelson-Morley experiment was conducted in the Michelson/Morley/earth q-space. The Michelson/Morley/earth perceptron(s) would perceive the speed of light to be the same in all directions, i.e., any fringe shift observed should have been a result of experimental uncertainty only. The experiment did not prove there was no ether; it did prove there was no perceivable ether[1] through which the earth was moving. The results admitted of a static-relative ether if it is unperceived. Perception is a process, and if the process does not occur then perception does not occur. Since by definition the q-space of a perceptron does not cause the perceptron to operate, then the q-space is unperceived by the perceptron.

More careful examination of observation reveals the following facts: A perceived mass has a constant mass when not moving with respect to the perceiver. When it is moving through the space frame or the ether of the perceiver with a constant velocity v, its perceived mass is again constant but is now perceived to be greater than was its rest mass. From whence came the extra mass?

The extra mass effect is only to the perceiver. The only possible sources for the extra mass in perception are the original rest mass M_0 and the empty space of the perceiver's space-frame (i.e., the interaction of perceived mass with unperceived space). Space does not drag, in the conventional Newtonian sense, against a moving body that is not accelerating. And space is unperceivable; therefore it can be visualized as a massless fluid. Thus the increase in perceived mass (which is a change) must come from the perceived mass's increase in velocity in perceiver space (because velocity is all that was changed), and it must involve the physical operation of the perceiver's physical perceiving mechanism. A perceived mass does exert resistance (drag) called "inertia" whenever it is accelerated in the perceiver's space-frame. This resistance is a force. Perceived force is equal to perceived mass times perceived acceleration through the perceiver's space.[2]

---

[1] Is not space an unperceivable ether? An extract from *Einstein's Theory of Relativity* by Max Born, p. 223, states: "If each of two observers who are moving relative to each other can assert with equal right that he is at rest in the ether, there can be no ether. Thus, the extreme development of the ether theory leads to its dissolution as a fundamental concept." The conclusion that there can be no ether does not logically follow. Each observer can assert that he is at rest in an ether (space), and these spaces can be intermoving. That is precisely what a "moving frame of reference" is: one space moving through another. Today we retain the (or more correctly, *an*) ether concept, but call it "space" or "inertial frame of reference" or "frame." The conclusion should have been that there can be no *single* "stable ether," but that there *can* be *many*.

[2] Newton's law, $F = ma$,* to date has been used in a half sense, i.e., that the acceleration of a perceived mass through the perceiver's unperceived q-space generates force. If this is true, and relativity holds, then the acceleration of any other unperceived q-space, through a perceived mass, also generates force; through one perceived mass in a perceiver's q-space, the q-spaces of all other perceived accelerating masses are accelerating and thereby generating forces on it. By this "other half" of Newton's law and by relativity, Mach's principle (that inertia of a mass is derived from the

accelerating and thereby generating forces on it. By this "other half" of Newton's law and by relativity, Mach's principle (that inertia of a mass is derived from the other masses of the universe) can be shown to be true. Although not collated and developed as such, it is possible to derive the postulates of both special (Continued)

Next Page

This equation states that a perceived accelerating mass must react with the perceiver's q-space, and in fact this interaction may be taken as the basic mechanism that creates force itself. Again the perceiver's physical perception mechanism is the causative agent.

A quite logical conclusion at this point is that the perceiving mechanism perceives (produces) additional perceived mass from the interaction of perceived rest mass with perceived mass-motion (velocity) through its unperceived space.[1] Also, the perceiving mechanism produces perceived inertial drag from the interaction of perceived mass with the mass's perceived acceleration through its unperceived space.

The concept of "ether" should not be rejected while the concept of "space" is retained, since the latter is actually an unperceivable ether. Rather, the concepts of mass, perception, and ether-space should be tailored to fit the perceived phenomena. Quiton/perceptron theory (perception theory) is a deliberate transfer function model specifically tailored to fit these criteria.

B. GRAVITATIONAL ATTRACTION

Newton's law of universal gravitation can be generated, in both effect and form, from quiton/perceptron theory.

A perceptron's q-space is filled with streams and streams of quiton disturbances moving ahead of its perceived moving objects from all over its universe. Thus there exists a flux of quitons at any point in its space, and this flux is isotropic to the first approximation: because of the vast interstellar distances between disturbing masses, the flux gradient in the relatively local neighborhood of any perceiver point is essentially zero. The quiton disturbance flux can be represented as shown in Fig. 8. A quiton flux stream switching pressure P_1 is exerted on M_1 and a switching pressure P_2 is exerted on mass M_2. In any one flux stream line in this shadowed zone, the pressure against either of the two bodies is reduced in proportion to the amount of switching flux subtracted from that flux line by the other body. The total reduction of switch pressure in the shadowed zone is therefore proportional to the product of the two masses M_1 and M_2, considering the effects to be mutually independent.

(Footnote 2 continued from preceding page) and general relativity from quiton/perceptron theory, and the steps essential to that derivation are contained in this paper.

*[More precisely, $F = d/dt\ (mv) = ma + v\ dm/dt$. From the second term, increase or decrease in mass of a moving object also produces a force. This second force component may not be too important except in microscopic phenomena, but for fast microscopic changes in mass (e.g., in the nucleus) it could generate significant forces. Also note that the velocities of all other spaces (i.e., velocities of the q-spaces of all other moving objects) in the perceiving mass's universe interact with its perceived mass change rates, according to the second term of Newton's law, relativistic form.]

[1] A disagreement has long existed over whether a "nonthing" exists if it cannot be observed. The argument is illogical; e.g., if a photon itself cannot be perceived



A disagreement has long existed over whether a "nonthing" exists if it cannot be observed. The argument is illogical; e.g., if a photon itself cannot be perceived and only effects (changes) produced by it are perceived, does a photon exist? It exists, but cannot be perceived to exist, i.e., it exists outside of perception, but does not exist in perception. The same is true of the notion of space.

Next Page



Fig. 8. Gravitational Attraction of Masses

From purely geometrical considerations, a shielding factor is also present due to the solid angle that is shadowed about any mass point. This effect is proportional to $1/R^2$ by usual solid angle considerations. Putting these two factors together, the attraction of mass should therefore be proportional to M_1M_2/R^2, or

$$F = K \frac{M_1M_2}{R^2} \tag{35}$$

which is the expression for Newton's universal law of gravitational force, and this force is driving the two masses together.[1] By merely extending the basic statement by superposition of the effects of every perceived mass-pair in the perceptron's universe, one obtains the attraction of mass[2] for the universe.

---

[1] It is not accidental that electric, magnetic, and gravitational field forces all obey "inverse square of the distance" laws, since these forces are derived from analogous switching operations.

[2] Attraction of mass implies an effect derivable from the presence of mass only. Mass is a switching rate. Therefore attraction of mass must be derived from switching only. Now a massless fluid generates no drag against a constant velocity mass, but switching is a negative quiton acceleration which does generate force. So switching generates drag, but constant velocity does not. This accounts for the error long made in considering the "mass shadowing" explanation of gravitational attraction to suffer from a serious defect of implied retardation force due to velocity through an ether-flux (see, for example, the Feynman Lectures on Physics, Vol. 1, p. 7-9). Velocity of an ether flux through a body merely affects the mass of the body; it does not generate force. Acceleration of an ether flux through a body generates a resultant force on that body. In Feynman's example of an orbital body, let us assume perfect circular motion with constant speed. Since the speed of the ether flux is always constant, the mass is always constant. Since the component of acceleration tangential to the circle is zero, there is no force generated tangentially to the orbit. But since there is a constant radially outward acceleration of flux through the orbital body, then there is a constant radial force outwards that is generated, and this force is called the "centrifugal force," i.e., the "center-fleeing" force.

body, then there is a constant radial force outwards that is generated, and this force is called the "centrifugal force," i.e., the "center-fleeing" force.

Next Page

It should be noted that for extremely small masses at extremely close distances, or for extremely short times, turbulence and interference effects can form in the shadowed zone of Fig. 8 and superposition may no longer hold.

C. NEWTON'S THIRD LAW OF MOTION

One of the recognized ways of stating Newton's third law of motion is: "To every action force there is an opposite and equal reaction force." This law follows from quiton/perceptron theory, as can be shown by examining two colliding bodies. It should be stressed that these two bodies, and all changes related to them, exist as changes in the output of the perceiver's perceptron. It must always be borne in mind that these changes, or physical phenomena, exist as outputs of the perceiver's mass perceptron.[1,2]

Figure 9 shows perceived bodies M_1 and M_2 in constant velocity motion just before collision. A deliberate choice was made of a case where the momenta of the two bodies were not equal, so that the initial switching rates for the two masses were different. In the example, $M_1V_1 > M_2V_2$. The mass switching drag of each body is again represented by small circles. Each body has the same size roll in front as in the rear, so its switch pressure forces are balanced. Figure 10 shows the collision.



Fig. 9. Two Bodies Before Collision



Fig. 10. Two Bodies at Moment of Collision

---

[1] We consider the question: "If a tree falls in a forest and there is no ear to hear it, is there a sound created?" A tree is a perceived tree, a forest is a perceived forest, and a fall is a perceived change. Their presence or existence implies a perceiver and perception; thus they imply that a "sound" change would be perceived, since they imply a perceiver to perceive it. If, however, by "no ear to hear it" we mean "no perceiver present at all," then the question as posed contains a self-contradiction: with no perceiver, there can be no perceived tree, perceived forest, perceived fall, or perceived sound.

[2] The manner of searching for quiton/perceptron causal explanation of a physical



or perceived sound.

[2] The manner of searching for quiton/perceptron causal explanation of a physical phenomenon is to ask, "What would the perceptron have to do to generate the phenomenon?".

Next Page

There is an almost instantaneous switch pressure increase in the contact zone between the colliding bodies, and consequently there is a switch pressure differential across each body as shown in Fig. 11.


P
SWITCH PRESSURE DIFFERENTIAL ACROSS M_1
P_1
P_c
SWITCH PRESSURE DIFFERENTIAL ACROSS M_2
P_2
X

Fig. 11. Switch Pressure Relationships at Collision

In the figure, the contact pressure P_c is exerted against each body, so that the pressure forces on the two bodies act in opposite directions. But for any two colliding bodies, the contact areas, one against the other, are the same. This common contact area will be called A_c. Since $P \equiv F/A$, then

$$|F_1| = |F_2| = P_c A_c \ . \tag{36}$$

But since the pressure forces on the two bodies are being exerted in opposite directions, then

$$\vec{F}_1 = -\vec{F}_2 \ , \tag{37}$$

which is Newton's third law of motion.

D. NEWTON'S SECOND LAW OF MOTION

Neglecting constants of proportionality, Newton's second law of motion may be stated in the most general sense as

$$F = \frac{d(mv)}{dt} \ . \tag{38}$$

The first step in deriving this law is to examine a point mass which is perceived moving with velocity $\vec{V}$, as shown in figure 12.



Fig. 12. Moving Point Mass

Next Page

An increased rate of quiton switching activity exists along the axis containing the velocity vector $\vec{V}$. We will call this increased quiton activity a vectorial "current" $\vec{\dot{Q}}$, and define its direction as contrary to the velocity vector. The mass is perceived to be moving against the current vector, and

$$\vec{\dot{Q}} \;\alpha\; -\vec{V} \; . \tag{39}$$

When the current $\vec{\dot{Q}}$ is steady, i.e., when

$$\vec{\dot{Q}}_{in} = \vec{\dot{Q}}_{out} \quad , \tag{40}$$

then the switching activity, and hence the mass and the energy, are constant. Therefore, from $v = \pm\sqrt{2E/m}$, the velocity remains constant.

If $\vec{\dot{Q}}_{out}$ suddenly increases, then

$$\vec{\dot{Q}}_{in} < \vec{\dot{Q}}_{out} \quad , \tag{41}$$

which can be represented as in Fig. 13.



Fig. 13. Difference in Quiton Current

From Eq. (39),

$$\vec{\dot{Q}} = -k_1\vec{V} \quad . \tag{42}$$

At any time in a quiton current, the switch pressure force exerted against the mass can be represented as

$$F = P_cA_c \quad , \tag{43}$$

where P_c is the switch pressure and A_c is the area of contact. However, since the area of contact A_c, or the drag area, is the mass switch rate itself, then (neglecting constraints of proportionality)

$$A \;\alpha\; M' \tag{44}$$

$$A_c \alpha M' \quad , \tag{44}$$

where M' is the switch rate at the point of switch pressure application. We will next examine the switch pressure forces before and after one perceptron operation

Next Page

(i.e., across the smallest possible time interval Δt used by the perceptron itself in perceiving a change). When there is any difference in the pressure forces against the body front and body rear, this difference is the resultant force $\vec{R}$, or

$$\vec{R} = \left[(P_cA_c)_{in} - (P_cA_c)_{out}\right] \vec{q} \quad , \qquad (45)$$

where $\vec{q}$ is a unit vector whose direction is given by the direction of $\dot{\vec{Q}}_{in} - \dot{\vec{Q}}_{out}$. Now, from Eq. (44),

$$\vec{R} = \left[(M'P_c)_{in} - (M'P_c)_{out}\right] \vec{q} \quad . \qquad (46)$$

Since $P_c \; \alpha \; \dot{Q}$ and $\dot{\vec{Q}} \; \alpha \; (-\vec{V})$, then (neglecting constants of proportionality)

$$\vec{R} = -\left[(M'\dot{\vec{Q}})_{in} - (M'\dot{\vec{Q}})_{out}\right] \quad , \qquad (47)$$

which from Eq. (39) gives

$$\vec{R} = (M'\vec{V})_{in} - (M'\vec{V})_{out} \qquad (48)$$

or

$$\vec{R} = K_4\Delta(M'\vec{V}) \quad . \qquad (49)$$

However, this has happened in the smallest possible time Δt, and since by definition

$$\Delta(M'\vec{V})_{min\ \Delta t} = (\dot{\overrightarrow{M'V}}) \quad , \qquad (50)$$

then

$$\vec{R} = k_4(\dot{\overrightarrow{M'V}}) = k_4 \frac{d}{dt}(M'\vec{V}) \quad , \qquad (51)$$

which is Newton's second law of motion, relativistic form. Acceleration of a body is caused by a difference in mass switch rate (i.e., a switch rate gradient)[1] induced across it by transfer of momentum from another moving body or by induction from a field such as an electrostatic field or a magnetic field.

E. NEWTON'S FIRST LAW OF MOTION

Newton's first law, that "a body at rest or in uniform motion will remain at rest or in uniform motion unless some external force is applied to it," can be derived from the same type of considerations used to develop the second law. Obviously, if

$$\ddot{\vec{Q}} = 0 \quad , \qquad (52)$$

---

[1] Switching can be thought of as transfer of Δt into ΔL. An increased switch rate represents an increased rate of transfer resulting in a higher value for the ratio

[1] Switching can be thought of as transfer of Δt into ΔL. An increased switch rate represents an increased rate of transfer resulting in a higher value for the ratio of ΔL to Δt being outputted. Since the ratio $\Delta L/\Delta t$ is defined as v, an increase in this ratio increases the velocity, and thus acceleration occurs.

Next Page

then

$$\vec{R} = 0 \tag{53}$$

and

$$\vec{a} = 0 \quad , \tag{54}$$

in which case the body at rest will not move and the body in uniform motion will remain so, by the definition of acceleration. Every perceptron repetition will output the identical value for V as the preceeding repetition, and that is why the first law holds.

F. IDENTITY OF LENGTH AND TIME

From $E = Mc^2$, we have

$$c^2 = E/M = 9 \times 10^{16} \text{ joules/kg} \tag{55}$$

$$c^2 \Leftrightarrow 9 \times 10^{16} \text{ joules/kg} \times 1/17.053 \text{ kg sec/sw} \tag{56}$$

$$c^2 \Leftrightarrow 0.527 \times 10^{-34} \text{ joule-sec/sw} \tag{57}$$

$$c^2 \Leftrightarrow \text{k/mass switch} \; . \tag{58}$$

Thus

$$c^2 = (3 \times 10^8)^2 \text{ m}^2/\text{sec}^2 \Leftrightarrow \frac{\text{k}}{\text{mass switch}} = \text{one sw opn} \tag{59}$$

$$\text{one sw opn} \Rightarrow (3 \times 10^8)^2 \text{ m}^2/\text{sec}^2 \tag{60}$$

$$\Rightarrow 3 \times 10^8 \text{ m/sec} \tag{61}$$

$$\Rightarrow 1 \text{ sec} = 3 \times 10^8 \text{ meters} \; . \tag{62}$$

Length and time are thus synonymous,[1] and c is the constant of proportionality (more precisely, the identical ratio for transposing Δt into ΔL will be maintained for each perceptron operation). Therefore, a perceptron actually outputs only one thing which may be taken to be either Δt or ΔL (it actually outputs only change

---

[1] By "synonymous" we mean that Δt and ΔL are intertransposable by perception operation. The term c is the velocity (rate of change) of switching itself, i.e., the speed at which quitons themselves can move, since quitons are being switched by mass. Therefore c ought indeed to be the wave velocity at which quitons move, and thus represents the maximum ΔL obtainable from Δt by mass in normal switching. The possibility exists that abnormal (turbulent) switching can deviate from this limitation. Thus "time warping," "time travel," "hyperspace travel," and the interplanetary drive may indeed



that abnormal (turbulent) switching can deviate from this limitation. Thus "time warping," "time travel," "hyperspace travel," and the interplanetary drive may indeed be possible. Since at least one of these effects of turbulence in switching (that of DeBroglie wave velocity exceeding the speed of light) is theoretically accepted, the problem of turbulent switching should be well worth the theorist's attention and effort.

Next Page

itself, which is perceived and thought of as ΔL and Δt). All other dimensions, quantities, and dimensional molecules are but bit division or bit multiplication. This seems to be consistent with some of the latest conclusions from general relativity theory.

In passing we note that there is no separation without relation, and there is no relation without separation. Therefore

$$\text{relation} \Leftrightarrow \text{separation.} \tag{63}$$

Also, there is no operation without separation, and there is no separation without operation. Therefore

$$\text{operation} \Leftrightarrow \text{separation.} \tag{64}$$

It follows that

$$\text{operation} \Leftrightarrow \text{separation} \Leftrightarrow \text{relation.} \tag{65}$$

We note a difference between free space and a Cartesian space (inertial reference frame). In a Cartesian space or inertial reference frame a definite length is considered to have been established for each and every point in that frame. But such a definite length to each point is rigorously operational by statement (65) above, i. e., such a length is defined by an operation. Specifically, it is defined by the operation of a mass perceptron (or an understood mass perceptron) at the origin of the frame. Such a frame is linear if the identical type of perceptron operation has defined the length to each point. If the type of defining operation varies, then the frame so defined is nonlinear; i. e., its space is said to be curved or distorted.

In one perceptron, its length defining operation and its mass defining operation can interfere or react one with the other. This type of interference or interaction is the direct interaction of frame space (length) with mass and it is the fundamental generating mechanism of force. All forces are so generated (see again the inset footnote on p. 17). And in fact a perceived moving force does work in the direction of its perceived movement rather than in the force's perceived direction precisely because of the moving operational length's interaction (interference) with the operationally generated force. This interference interaction is between operations in the same perceptron and generates what is called work.

Next Page

V. ELEMENTARY PHILOSOPHICAL IMPLICATIONS

Every scientific treatise is filled with forms of the words "one" and "be," yet none attempt to define these metaphysical terms. Ontologists and metaphysicians have uncovered many problems connected with these two words, but no real solutions. In addition, the historical preoccupation of metaphysics with dogmatic religious beliefs contributed strongly to its disfavor, since scientists were required to exert considerable effort to establish the scientific (observational) method as a legitimate criterion for the judgment of physical truth. Consequently, both science and philosophy today are constructed on quite undefined foundations, primarily because of the failure to recognize the relationship of perception operation to reality, which recognition is a prerequisite to the synthesis of physics and metaphysics. One therefore must comprehend the concepts of be (exist),[1] thing (perception), and one (thing) from the viewpoint of the relation between perception and ultimate reality.

A. EXISTENCE, THING, AND ONE

Existence has been defined here as "what is to be fed into the perceptron's input." In the situation where all operation of the perceptron has ceased, what can be said to exist in the input? First, what exists is a continuum: it has no limit, interface, dimension, time, velocity, change, space, place, or discontinuity since these are all derived from perceptron operations and the perceptron is not operating. What exists is continuity only, with no discontinuity.[2] To comprehend this, we must examine the thought process itself more closely, realizing that "to think" is "to perceive thoughts."

What is a "thing?" Further, what is "one" -- one "thing," one "anything?" A thing is first a perceived thing: it resulted from the output of a perceptron operation, in which one input bite and one output occurred. This output is characterized by the the fact that it is one, and the absence of one (i.e., zero) is the absence of output.[3] Figure 14 shows these relationships. The perceptron operation created the separation between the inside and the outside by creating a ΔL and a Δt, that is what the delta symbol means. Thus the operation of the perceptron determines the basic nature of one itself, and any one necessarily requires that a perceptron operation has occurred. In fact, the perceptron itself is a result of perceptron operations. Thus indeed all is relative. A perceptron exists and is able to function because it perceives other perceptrons to exist and function. Thus perceptrons are mutually created derivatives of reality are therefore unperceivable.

---

[1] Being is undifferentiated; that is its total definition. It cannot be perceived, since perception differentiates. It is continuity only, without any discontinuity, which is unperceivable. The preoccupation of being with causality (perception) is technically called "inception," the influencing of perception. In Zen philosophy this is technically "attachment to the world of illusion (change);" the literal meaning of "incarnation."

[2] This concept is unperceivable, by the definition of perception, which accounts for its difficulty. To be a "perceived one" implies limit (finiteness); oneness itself, without a bound or limit to make it a one (perceived), cannot be perceived. This is the primary limitation of the human mind (i.e., of perceptive thinking)--being, continuity, and oneness themselves imply absence of perception (differentiation) and are therefore unperceivable.

[3] Thus Boolean algebra describes the most basic operation, and is applicable to the

[3] Thus Boolean algebra describes the most basic operation, and is applicable to the "operational" world.

Next Page



Fig. 14. Nature of One

which drive themselves and each other. Note that the preceding sentence itself is a perception.

So in the fullest sense, Gautama Buddha was indeed correct to state that the world of phenomena (changes) is an "illusion," relative only to itself (i. e., to perceptrons).[1] Einstein, expressing this idea in the language of mathematics, produced the theory of relativity and inaugurated a new physics. Buddha and Einstein spoke in different technical languages, but both expressed the same idea. The only difference is that in science we have assumed that our observations themselves are real and perfect. They are real, but not perfect in that they represent only changes in ultimate reality. Thus observational science alone can never reveal ultimate reality.

Another approach may aid in the comprehension of the nature of one. What is meant by the statement "he is the man?" Reflecting, one realizes that what is meant is that the perceived thing HE is exactly the same perceived thing THE MAN, and this identity exists now (during this one Δt perceptron time slice). There is no part of HE that is discontinuous from THE MAN, or vice versa. The different forms of the verb "be" attempt to express continuity without discontinuity, or unlimited oneness which is a state and not a thing. However, we do use the verb "be"[2] to relate continuity between different time slices. "He is the man" is related in the present time slice; "he was the man" means that HE in the NOW slice is identical to THE MAN in a past slice; etc.

---

[1] The reader interested in Zen will find complete agreement between this paper and Zen precepts, and will find the paper of some assistance in comprehending the unperceivable (unthinkable) Zen realizations. In Zen, for example, the aim is to comprehend at once the totality of reality, directly, escaping beyond the limiting fetters of perceptive thought. Now if it is actually possible to do this, and if some unusual men have done it, then their enigmatic writings should contain the wisdom of their experience, and should correspond to ultimate reality itself. Since ostensibly their insight is obtained by other-than-logic and other-than-perceptive means, then their statements should appear illogical and unperceivable.* Thus the "sound of one hand clapping" and other illogical concepts are used in Zen as a meditative means of driving the student beyond logical perception (certainly the sound of one hand clapping cannot be perceived or thought) to realization. But if the Zen experience is actually valid, then reality itself must be pure Zen (i.e., unperceivable), and so it would appear to be. We note that for each component part of all, the opposite part must exist. So all can be regarded as the complete set of all possible opposites or contradictions.

*(However, this most assuredly does not imply that every statement that is illogical and unperceivable is of value!)

[2] It should be stressed again that being is defined as undifferentiated (unseparated,



is illogical and unperceivable is of value!)

[2] It should be stressed again that *being* is defined as undifferentiated (unseparated, unperceived). Being is simply continuity without discontinuity.

Next Page

B. REALITY, ULTIMATE REALITY, BEING, AND ULTIMATE BEING

Actually one should be quite careful in using these terms. What does one get when one differentiates reality? One gets another reality, but not the primary or ultimate reality. For example, assume that length and time are real. When one time-differentiates length, one obtains velocity, which of course is real also but quite different from either length or time. However, velocity is always operationally related to the two first (assumed) reals length and time, because differentiation is an operation. So what is meant by "ultimate reality" is that state (or essence, or whatever name one prefers) that is not differentiated. Since "being" (continuity with no discontinuity) is defined as "that which is not differentiated," then the ultimate reality is pure being.

But all perceivables are differentials of ultimate reality. When one differentiates being, one gets pieces (differentials) of being which themselves are beings, but they have been perceived (differentiated) from a more primary or higher being. Therefore any being that one perceives has been differentiated (separated) by perception,[1] which explains why human beings, for example, consider themselves separate or individual (one). They are separate only in their individual perceptions. Thus "beings" by its plural nature always implies fragments (differentials) of a higher being (of singular nature). There can be many such integral levels: starting with one function, one can integrate it, then the resulting function can be integrated, etc., as long as we are speaking of definite integrals between two limits. When we reach a state that has no pieces or limits, the process is finished. That state is being in the ultimate sense, i.e., ultimate being.

One perceives these integral levels directly in nature, i.e., in the perceived phenomenological world. Living molecules (tiny beings) of RNA, DNA, etc., integrate together into a cell (a higher level being). Cells then integrate into a still higher being (man, animal, plant), which is the level on which man finds himself. But since man is perceivable and there are more men than one, it follows directly that men are capable of being integrated into a still higher being,[2] and the only word we have at present to describe such an ultimate being is "God." It is not at all accidental, therefore, that the ultimate being cannot be directly perceived by man, since by the definition of perception the ultimate being cannot be perceived by a lower order being such as man (i.e., since perception differentiates, or separates, then only differentials of being, or separate beings, are perceivable).

The avatar Jesus, having no technical concept for the derivative available in the language of the day, used the analogy of the father-son relationship, the son being the derivative of the father in this sense. Thus he referred to himself as the "Son of Man" (the derivative of all mankind or of integrated mankind) and also as the "Son of God" (the derivative of the integral of man). He continually referred to the ultimate being as "Father." It is little wonder that he was not understood then, and has not been understood for almost twenty centuries.

---

[1] Thus not only are physical objects relative to the perceiver's perception, but so are the perceived beings. Ergo the entire perceived universe, both living and non-living, is related to perception, and in fact perception and creation are abstractly

are the perceived beings. Ergo the entire perceived universe, both living and non-living, is related to perception, and in fact perception and creation are abstractly synonymous.

[2] This statement contains obvious implications to the theory (i.e., to the goal) of evolution.

Next Page

VI. CAUSALITY AND ITS MODIFICATION

A little closer look at perception can be obtained by viewing it from the causal standpoint.[1] All that perception really creates is Δt and ΔL (which are the same, ignoring constants of proportionality), and the perception we normally think of is point perception, where a point is one switching operation. The perception point may be thought of as following a line path which we will call "lineception" (Fig. 15). Physical phenomena as seen by one perceptron constitute this lineception; or rather, it constitutes the physical phenomena that are perceived or observed by the perceptron. Any point-based perceptron system, such as human perception, will accordingly perceive the universe of physical phenomena as if the perceiving system were a pointer moving along a lineception.[2]



Fig. 15. Lineception (One Connected to One)

For each perception there is a reflection, so there exists (but by definition cannot be perceived) a similar line-path, or "lineflection" as shown in Fig. 16.

-Δt -Δt -Δt -Δt
-ΔL -ΔL -ΔL -ΔL

Fig. 16. Lineflection (One Connected to One)

causal) and perception generates causality (causality is perceptive). Thus the idea that perception generates causality is completely consistent with our initially assumed definition of causality as the set of all causes.

---

[1] Perception is identical to causality itself, i.e., perception can be said to generate causality. The causal view is that causes inputted to a situation operate to produce, or output or create, effects. According to its inputs, the perceptron generates causal outputs. An adequate theory of perception should be able to explain all causal (perceived) phenomena. We might define causality as the set of all causes. Then the answer to the question, "What causes causality itself?" is causality itself; i.e., since it is the set of all causes, causality must contain its own cause. Causality must therefore be closed or circular. The entire causal world must then be purely relative to itself (closed). Closer attention to causal operation yields the following: We perceive something change (in time or in space), then the situation changes so that we perceive new changes emerge (occur later, or separately). Thus the line of perception by its own unperceived operation connects the perceived cause (change) to the perceived effect (change), i.e., perception generates causality. Since perception itself is causal, then causality truly causes itself. This indeed is closed or circular--causality generates perception (perception is causal) and perception generates causality (causality is perceptive). Thus the idea that perception generates causality is completely consistent with our initially assumed definition of causality as the set of all causes.

[2] A "frame" or "coordinate system" is a point-centered perceptron system centered about the "understood perceptron" at the origin.

Next Page

The ultimate reality, or existence, contains all, all-at-once (ultimate reality is allness, or oneness). At each operation of the perceptron, the exact amount of Δt and ΔL, and their relationship, put out by a perceptron is a function of its input quiton disturbances. A great number, in fact perhaps an infinite number, of different input states are possible, i. e., exist in all, all-at-once (ultimate reality). So an equally large number of output states are possible (exist ultimately),[1] but one particular input condition results in one particular output condition. We can represent the all possible lineceptions existing as "multiception" (Fig. 17). From this figure, a lineception can be seen to be one particular path through multiception. The corresponding multiflection could, of course, be illustrated in similar manner but with negative components.



Fig. 17. Multiception (One Connected to Many)

One could immediately apply statistics to the concept along the lines illustrated by Fig. 18.



Fig. 18. One Branch

---

[1] It is stressed that these multiceptions exist, which is not at all the same limited statement as "exist now," but much more comprehensive; e.g., all possible numbers must exist in zero, else, given the number A, there is no justification for the axiom that $A + (-A) = 0$. The "absence of number" means precisely the "absence of all possible



exist in zero, else, given the number A, there is no justification for the axiom that A + (-A) = 0. The "absence of number" means precisely the "absence of all possible numbers." Paradoxically, if we think of that absence, we make it present by the act of thinking; i.e., trying to perceive it (absence is not perceivable). This contradiction, of having to make the unthinkable into its opposite so that it is thinkable is both the characteristic and the limitation of perception and perceptive thinking, and has long been an insurmountable obstacle to scientist and philosopher alike.

Next Page

At each switch point, the perceptron is faced with the branch of possibilities ahead, which all exist in multiception but only one of which exists in one perception, or lineception.[1] A certain set of limbs in the branch must have a perception probability equalling 1, and thus each of the limbs has some finite probability.[2] The input conditions to the perceptron then determine which limb is selected for the next switching operation; and, of course, the input conditions are the results of other related perceptrons' operations (relativity). The statistics will not be pursued further here.

For an absolutely mechanistic world, the entire process is automatic according to quite rigidly fixed rules. A system of perceptrons that behave this way shall be referred to as "mechanically switched." What we call "non-living systems" are mechanically switched systems. But what we call a "living system" is able to arbitrarily select the limb taken, to some extent at least,[3] i.e., the fact that a living system is able to choose its behavior within certain limits, directly implies that it must be able to deflect its lineception from a mechanically switched lineception. The only way it can possibly do this is to influence the switching operation of the perceptron. But since the output of one switching operation is a mechanistic function of the inputs, then the only way a life system can affect the perceptron switching operation is by affecting the input to some extent. How could it possibly do this?

In our crude model, the nonaction continuum is composed of action atom fragments, or quitons. But such non-things are massless by definition (they are not being switched and the absence of switching defines masslessness), and we can think of the nonaction continuum as a massless fluid or ether or empty space, since these terms are all synonymous. All that is implied by these terms is that the fluid is composed of massless elements, which merely means they are not being switched. They are capable of being switched, of course, but switching is not being done. The main point is that force, in the conventional sense, is not required to move a massless fluid, so the input fluid to a perceptron can possibly be interfered with by some nonphysical means requiring zero force. The being portion of a life system can apparently do this to some extent.

Since the switch time of a perceptron is on the order of 10^{-21} seconds, then even an incredibly tiny quiton input variation to a perceptron will result in

---

[1] It is stressed that all possibilities exist and are real, but do not exist in perception. Perception is the only difference between unperceived reality and perceived reality.

[2] Which leads to an unusual view of "probability." A perceptron operation is already finished when one perception is complete; that is why "the past is always gone, the present has just occurred, and the future is never here." Perceptron operation continually creates the perceptron's universe as it operates, including all changes, time, space, etc.). Thus, at the conclusion of any one perceptron operation, a multitude of lineception steps can exist for the next operation. However, although possibly quite large, the number of next steps available must be finite to be causal (perceivable). It is the process of perception that makes probability finite. Perception is finite; nonperception is infinite.

[3] The only alternative conclusion is that the living system is unable to deliberately

Perception is finite; nonperception is infinite.

[3] The only alternative conclusion is that the living system is unable to deliberately modify its behavior and its behavior is purely mechanical. But since this implies that all behavior is absolutely programmed and predictable, which is obviously false, this alternative is not valid and the original conclusion stands.

Next Page

noticeably altered lineception after one second of such variation. So it is quite reasonable to presume the futility of trying to measure such infinitesmal influence as is brought to bear on one single perceptron operation. However, the total influence can obviously be detected after being accumulated by a very large number of perceptron operations, and for living systems it is. So while we have not proved the mechanism of life-system manipulation of lineception, we have shown a logical progression from an assumed mechanism to a result that is universally verified by countless observations (i. e., all living systems are observed to manipulate causality, which manipulation is, after all, the definition of behavior). Since no other mechanism has been proposed, to the author's knowledge, that would reasonably explain the observed phenomenon of life-system manipulation of lineception, it is logical to accept as true the assumed mechanism -- a life system can exert an incredibly tiny influence on perceptron inputs,[1] i. e., on the ether or on empty space.[2,3]

---

[1] This tiny influence is the basis of the realization process. To comprehend the noncausal, the individual observer usually wrestles diligently with the problem, repeatedly attempting to perceive it causally. In each such attempt, the tiny influence of inception on perceptron inputs is exerted. Over an ensemble of such attempts, the perceptron causal output can be modified, i.e., modulated noncausally to give what are now slightly noncausal perceived outputs. Presence of a required fit or required output pattern in the perceptive mind allows the output to be examined (compared) against the required output, i.e., it allows the selection of the proper noncausally modulated causal transfer function. When the outputs match, one then has a breakthrough or realization which matches the real world pattern but which cannot be directly perceived causally. However, since the mental file of the perceptive mind has now filed the proper transfer function, the individual has assimilated the information and understands it, being able to recall the noncausally modulated causal transfer function at will. Thus in Zen, the ultimate example of realization is described as "enlightenment." Phrases such as "direct perception of reality," "direct experience of ultimate reality," or "direct realization of all-being" are also used in trying to portray the nonperceivable realization. Conventional science hides the entire process behind vague terms, such as "creative thinking," which actually only conceal the fact that we do not know what it is, or how it is accomplished.

Note that such "creative realization" can cover either purely causal or noncausally modulated perception, the difference being merely whether the inputs are incepted in a normal manner comparable to causal phenomena, or in another manner. Realization is derived only from inception. Since the observed phenomena of physics already appear to be noncausal (statistical) in the ultramicroscopic region while ensembles of these yet appear to be causal, then the physicist is already confronted with the necessity of changing causality but at the same time retaining causality. The implications to the observation process itself must be examined, and they remove the dichotomy between physics and metaphysics when pursued.

[2] The Hieronymus effect is an example of this in reverse. It generates an effect on living nervous systems that is not the result of electric, magnetic, or gravitational fields, and is not caused by matter in motion. For that matter, a polygraph has been used to clearly measure a response of plants to human thoughts alone, and such an effect is not presently explainable within the body of physics theory. "Firewalking" is another unexplainable phenomenon from the standpoint of present physics theory as is acupuncture.

[3] All psi phenomena derive from this effect (inception) together with turbulent



is acupuncture.

[3] All psi phenomena derive from this effect (inception) together with turbulent switching. A straightforward theory of psi phenomena (and of such things as fire-walking and acupuncture, for that matter) can conceivably be generated from the quiton/perceptron theory.

Next Page

Of course the most efficient development of manipulation of lineception (i.e., the widest response) by a life system would necessitate a control system approach; i.e., life system direct manipulation of only a very small control valve or control mechanism, which in turn controls the input to a much larger mechanistic (deterministic) servo amplifier. Systems like this are universally observed in life systems. Thus the great bulk of a life system's manipulation of lineception is servomechanistic: the actual direct influence of life (being) on matter (perceptron switching) is so microscopic as to be immeasurable at its operating level, and only its macroscopic effects become measurable. For that reason the scientist has never been able to isolate the mechanism of life's manipulation of lineception, nor is he likely to be able to do so in the foreseeable future.[1]

Life's manipulation of lineception will be denoted by the term "inception," and can be thought of as a modulation (partial change or additive change) of the lineception carrier. Ordinary physical phenomena are macroscopic ensembles of lineceptions, where the deterministic (mechanistic) law holds absolutely but in a relative manner (ensemble to ensemble) which is fixed cause-and-effect, or causality, from the viewpoint of perception. Since inception is a modulation of lineception, then living behavioral phenomena should be superimposed as envelopes on causal lineceptions, or causal lineception ensembles, and, indeed, they are universally observed to be so superimposed.[2]

Absolute or ultimate reality, however, can be thought of in one respect as all multiceptions and all multiflections, all-at-once, which is timeless (i.e., which is both all-possible-times and zero time simultaneously or identically).[3] Along any one lineception, causality applies; yet since a very large number of changes to that lineception are available in just one multiception branch, then quite a large

---

[1] This latter statement, of course, is subject to challenge.

[2] Since all matter is, it contains being. Another intriguing possibility exists: that there are two types of inceptive systems, or two magnitude directions that inception takes. The first type would produce inception with difficulty, and its inception would only be apparent at the macroscopic level; the second type would produce inception with ease, its inception would be apparent only at the microscopic level. The first type would correspond to what we call "living systems," while the second would correspond to what we call "inert systems." Living systems' inception would be observable to human senses and human instruments, while inert system's inception would not. A second and remarkable consequence would be, that in the extreme microscopic case, inception would dominate and this scale would appear to be absolutely statistical (individually unpredictable), which apparently is true (i.e., degree of causality represents degree of restraint of inception). This would modify causality (for individual events) at the ultramicroscopic level, but at higher levels causality would still apply due to the karma effect on perceived ensembles. It is significant that at present the universe of matter seems to behave in precisely this fashion. To summarize, perception is causal -- it generates causality. Inception, being noncausal, must be below the perception threshold. Aggregates of inception (noncausal) that equal or exceed the perception threshold become causal (are processed by perception) and generate causal karma.

[3] Since every perceived ΔT has an unperceived complement $-\Delta T$ which exists in reflec-

[3] Since every perceived ΔT has an unperceived complement $-\Delta T$ which exists in reflection, then the sum total of all times in absolute existence, which includes both perception and reflection, equals zero time.

Next Page

number of inceptions are available to be applied to that one lineception by an organism to change or direct the lineception. Herein is the explanation of karma. Since every inception made by an organism (or by a submicroscopic particle of being for the second case, see note 2, p. 32) changes its entire lineception, it also changes its entire perceived or relative universe, which is the only universe it knows or senses. And since causal feedbacks from this perceived universe[1] occur to the organism's perceptron (which itself is part of that perceived universe), then the effects of the organism's actions indeed return precisely to it. So, "as a man soweth, that shall he also reap" is quite true.[2]

It is now possible to formulate some conclusive statements:

1. One perceptron follows a lineception path, mechanically basing its output on its inputs, and this operation establishes causality to perception repetition, i.e., to lineception.

2. Ordinary physical phenomena are merely ensembles of related lineceptions, and are perceived to be absolutely deterministic (obey only cause-and-effect.

3. Living phenomena exhibit the effects (selective behavior) of inception (modulations impressed on lineception) which occasionally diverts one lineception from its deterministic lineception limb to another multiception limb, resulting in a changed (modulated) lineception.

4. Ultimate, or absolute, reality may be thought of as the sum-total of all multiceptions and multiflections.

5. "God" is all-being, which is all multiflection and multiception at once, which is both no time at all and forever and all forevers as well.

6. "God's will" is lineception and its accompanying lineflection.

7. "Man's will" or "free will" is inception, the modulation of lineception (and unknowingly its accompanying lineflection). Inception, however, imposes a feedback on the inceptor since a precise feedback, from the inception changes to perception, occurs to the perceptron of the perceiver. This feedback resulting from inception is karma.

8. The law of cause and effect (causality) exists in perceived nonmodulated phenomena (ensembles of lineceptions).

9. Causality is affected (modulated) by living systems, but applies to each choice once made. The causal feedback from inception is karma.

---

[1] "Perceived" must be accented: the nonperceived universe is not causal, since by definition causality invokes a perceiver and the perception process.

[2] Collective karma of any ordered group such as a species must exist in like manner. On the submicroscopic level, "karma of ensembles" means that the statistics of



[2] Collective karma of any ordered group such as a species must exist in like manner. On the submicroscopic level, "karma of ensembles" means that the statistics of lineceptions and inceptions still lead to causal relationships in the perceived collective phenomena.

Next Page

10. Neither causality or karma applies in ultimate reality, although all causality lineceptions and their reflections, and all modulations (inceptions) and the karma reflections of those inceptions, are included in ultimate reality.

Next Page

VII. CLOSING REMARKS

The quiton/perceptron approach appears to offer a most extensive area for further investigation, and it is hoped that the physicists will interest themselves in the concept. It offers explanations for the problems long posed by ontology, and unifies the bases of science and metaphysics.

We state categorically that the theory explains what electric charge is, why like charges repel, and why unlike charges attract. In addition, since all phenomena are perceptron outputs, the theory indicates that multiple effects which are very close in time or distance will interfere with each other due to turbulent switching; i. e., conservation of mass/energy holds only as long as no switch interference exists. Turbulent switching can possibly disrupt all known physical laws. Unexpectedly strong forces, such as nuclear force, might in fact result from this effect. Other implications include possibility of travel faster than the speed of light (deBroglie waves do this now) and of travel back and forth in "time."

Since both laboratory instruments and human sensory apparatuses are perceptrons and differentiate reality, investigations of physical phenomena should include the laws of the perceptron as well as the laws of the perceived phenomena.

Next Page

BLANK

Next Page

DISTRIBUTION

	No. of Copies
US Army Missile Command Distribution List A	52
Defense Documentation Center Cameron Station Alexandria, Virginia 22314	12
Commander US Army Materiel Command	
ATTN: AMCCG	1
AMCRD	1
5001 Eisenhower Avenue Alexandria, Virginia 22304	
AMSMI-O	1
-FR, Mr. Rives	1
-R, Dr. McDaniel	1
-RB, Dr. Kobler	1
-RBL	5
-RP, Mr. Kopcha	1
-RPR	1
AMCPM-MD, LTC Bearden	100
-MD (Record Set)	1

Next Page

BLANK

Next Page

UNCLASSIFIED
Security Classification

DOCUMENT CONTROL DATA - R & D

(Security classification of title, body of abstract and indexing annotation must be entered when the overall report is classified)

1. ORIGINATING ACTIVITY *(Corporate author)*
SAM-D PROJECT OFFICE
US Army Materiel Command
Redstone Arsenal, Alabama 35809

2a. REPORT SECURITY CLASSIFICATION
UNCLASSIFIED

2b. GROUP

3. REPORT TITLE
QUITON/PERCEPT~~R~~ON PHYSICS: A THEORY OF EXISTENCE, PERCEPTION, AND PHYSICAL PHENOMENA

4. DESCRIPTIVE NOTES *(Type of report and inclusive dates)*
Technical Report

5. AUTHOR(S) *(First name, middle initial, last name)*
Thomas E. Bearden

6. REPORT DATE
5 March 1973

7a. TOTAL NO. OF PAGES
38

7b. NO. OF REFS
~~0~~ 3

8a. CONTRACT OR GRANT NO.

b. PROJECT NO.

c.

d.

9a. ORIGINATOR'S REPORT NUMBER(S)

9b. OTHER REPORT NO(S) *(Any other numbers that may be assigned this report)*
AD 763210

10. DISTRIBUTION STATEMENT
Approved for public release; distribution unlimited

11. SUPPLEMENTARY NOTES

12. SPONSORING MILITARY ACTIVITY
Same as No. 1

13. ABSTRACT

A fundamental answer is attempted to the question of being, time, space, existence, perception, and physical phenomena. Mass, empty space, reality, gravitational attraction, continuity, discontinuity, and relativity are among the "things" and "nonthings" for which relationships and explanations are provided.

Perception is defined as detection by a mass of change to itself and as a differentiating process. Perceived physical phenomena are revealed to be first derivatives of ultimate reality, and outputs of the physical perceiving device called the "percept~~r~~on." Using the operation of the physical perception process on action, the units of which are energy times time, an entirely different view is generated of both reality and the Heisenberg uncertainty principle. When superposition is imposed as a condition, the Heisenberg uncertainty principle is revealed to be a quantized statement. A concept of the absolute value of a dimensional molecule is advanced.

A reality model is constructed of an action continuum and a nonaction continuum separated by an operational threshold whose magnitude is given by an uncertainty principle. Perception is modeled as a process which switches atomic quanta of action and nonaction back and forth across the threshold. Mass is explained as perceptron switch activity rate, and a mass definition equation is generated. One kilogram mass is shown to represent 17.053×10^{50} perceptron switches per second. From the model, Newton's laws of motion and gravity can be generated directly from the concept of the interaction of mass with space itself, space being taken as a massless fluid, or ether, composed of tiny nonaction particles called "quitons." Einstein's postulates of



composed of tiny nonaction particles called "quitons." Einstein's postulates of

DD FORM 1 NOV 65 1473 REPLACES DD FORM 1473, 1 JAN 64, WHICH IS OBSOLETE FOR ARMY USE.

UNCLASSIFIED
Security Classification

Next Page

14. KEY WORDS	LINK A		LINK B		LINK C	
	ROLE	WT	ROLE	WT	ROLE	WT
causality						
perception						
perceptron						
quiton						
quiton/perceptron theory						
gravitation						
mass						
reality						
metaphysics						
being						
existence						
space						
time						
photon						
action						
action quantum						
quantum						
observation						
relativity						
Karma						
complementarity						
physical phenomena						
Mach's principle						
Newton's laws						
inertia						
Debroglie wave						
Einstein's postulates						
Michelson-Morley experiment						
ontology						
Heisenberg Uncertainty Principle						
superposition						
equivalence principle						
simultaneity						
inertial frame						

ABSTRACT (Continued)

special relativity are also shown to follow from the model, and a statement of the equivalence principle is shown to be consistent with the model.

The concept of "lineception" as a causal chain of perceptron operations is advanced. "Inception" is developed as a noncausal modulation of lineception and as a distinguishing feature of a living system. The possibility is raised that inception could provide an explanation of the noncausal, statistical, ultramicroscopic universe and yet require large ensembles of ultramicroscopic events to conform to causality. Inception is shown to lead to karma. Perception is shown to be causal and to generate causality itself.

Some elementary philosophical implications of quiton/perceptron theory are pointed out and briefly discussed.

and briefly discussed.

Next Page



Tony,

Found a cy of
The paper, so here it is.

Cheers,

Tom

P.S. Shortly after this
the SAM-D was renamed
the PATRIOT.

Search The ConTrail Search

Select Language

- Sign Up
- Sign In

And On Cue...

- Main
- My Page
- Members
- Forum
- Blogs by members
- Photos
- Videos
- Groups
- Red Pill Cinema
- Chat
- Music
- Donate

- All Discussions
- My Discussions
- Add



SCALAR WEAPONS: Read It and Weep

- Posted by Ms MoD on July 27, 2011 at 4:42 in HAARP
- View Discussions

This is a REALLY long paper but it is broken down into categories so you can easily skip to sections of interest to you. I found this after reading Twelve Things You Should Know About Scalar Weapons which was posted by FDF in April and is a MUCH SHORTER overview of scalar technology by the same author. I highly recommend it but wanted to post the longer version here as well which you can download in the PDF attached. Topics in the paper are listed below -MoD

SCALAR WEAPONS: Read It and Weep
By C Verismo

1. THE DISCOVERY OF SCALAR WAVES
2. BEAM WEAPONS OF A CENTURY AGO
3. THE CONTINUATION OF TESLA'S SCALAR WAVE TECHNOLOGY
4. TESLA'S CROSSED SCALAR BEAMS
5. RUSSIA'S 'WOODPECKER' SCALAR WAVE TRANSMITTERS
6. THE 1930s
7. THE 1940s
8. THE 1950s
9. THE 1960s
10. THE 1970s
11. THE 1980s
12. THE 1990s
13. THE PRESENT
WHAT CAN BE DONE WITH SCALAR TECHNOLOGY?
14. MIND READING, MASS HYPNOTISM AND SYNTHETIC TELEPATHY
15. DISEASE INDUCTION
16. DISABLING SATELLITES
17. IN THE AIR
18. WEATHER ENGINEERING
19. EARTHQUAKES
20. SEA ATTACKS
21. TESLA SHIELDS AND GLOBES
22. GROUND ATTACKS
23 OBLITERATING INDIVIDUALS
24. PORTABLE SCALAR BAZOOKAS
25. RADAR INVISIBILITY
26. SUMMARY OF A WAR THAT COULD OCCUR
27. RUSSIAN UFOs ATTACKED THE US SHUTTLE PROGRAM FROM THE BEGINNING
28. HOW DID RUSSIA GET UFOs?
29 FORMER BOLSHEVIKS RUNNING AMERICA
30 REPLICAS USED FOR THE LANDINGS, AFTER ORIGINALS SHOT DOWN
31. CLOAKED RUSSIAN UFOS ABOVE USA

32. ALL U.S. SATELLITES SHOT DOWN BY RUSSIA UNTIL 1981
33. LIES, LIES AND LIES
34. FRICTION WITH THE JAPANESE
35. ENTERPRISE SHUTTLE DETERMINED TO SPY ON RUSSIA
36. RUSSIA INTENSIFIES ATTACKS
37. TRYING AGAIN TO GET UP INTO SPACE. THIRD TIME LUCKY?
38. BOLD ATTACKS ON AMERICA
39. THE STRUGGLE AT THE TOP FOR POWER
40. THE STEALTH PLANE COMES TO THE RESCUE
41. PHANTOM AGAINST THE COSMOSPHERE
42. THE EXPECTED GENOCIDE
43. PLANS FOILED TO DESTROY RUSSIA'S MILITARY ARSENAL
44. BRAZIL
45. INDIA
46. JAPAN
47. KOBE 'EARTHQUAKE'
48. CHINA
49. OKLAHOMA FBI BUILDING 'BOMBING'
50. WHO ELSE HAS UFOs?

Full paper in PDF below…

Favorite
1 member favorited this

Share Tweet Facebook

Views: 459

Attachments:

- SCALAR WEAPONS - Read It and Weep.pdf, 494 KB

▶ Reply to This

Replies to This Discussion

Permalink Reply by Jenny on July 27, 2011 at 6:22
HAARP Patents (Assigned to APTI, Inc. Los Angeles, CA, Washington, DC)

U.S. Patent 4686605: Method And Apparatus For Altering A Region In The Earth’s Atmosphere, Ionosphere, And/Or Magnetosphere Issued: Aug. 11, 1987 Filed: Jan. 10, 1985
http://www.freepatentsonline.com/4686605.pdf

U.S. Patent 5038664: Method For Producing A Shell Of Relativistic Particles At An Altitude Above The Earth’s Surface ~ Issued: Aug. 13, 1991 Filed: Jan. 10, 1985
http://www.freepatentsonline.com/5038664.pdf

U.S. Patent 4712155: Method And Apparatus For Creating An Artificial Electron Cyclotron Heating

Region Of Plasma ~ Issued: Dec. 8, 1987 Filed: Jan. 28, 1985
http://www.freepatentsonline.com/4712155.pdf

U.S. Patent 5068669: Power Beaming System ~ Issued: Nov. 26, 1991 Filed: Sep. 1, 1988
http://www.freepatentsonline.com/5068669.pdf

U.S. Patent 5218374: Power Beaming System With Printer Circuit Radiating Elements Having Resonating Cavities ~ Issued: June 8, 1993 Filed: Oct. 10, 1989
http://www.freepatentsonline.com/5218374.pdf

U.S. Patent 5293176: Folded Cross Grid Dipole Antenna Element ~ Issued: Mar. 8, 1994 Filed: Nov. 18, 1991
http://www.freepatentsonline.com/5218374.pdf

U.S. Patent 5202689: Lightweight Focusing Reflector For Space ~ Issued: Apr. 13, 1993
http://www.freepatentsonline.com/5202689.pdf
Filed: Aug. 23, 1991

U.S. Patent 5041834: Artificial Ionospheric Mirror Composed Of A Plasma Layer Which Can Be Tilted ~ Issued: Aug. 20, 1991 Filed: May. 17, 1990
http://www.freepatentsonline.com/5041834.pdf

U.S. Patent 4999637: Creation Of Artificial Ionization Clouds Above The Earth ~ Issued: Mar. 12, 1991 Filed: May. 14, 1987
http://www.freepatentsonline.com/4999637.pdf

U.S. Patent 4954709: High Resolution Directional Gamma Ray Detector ~ Issued: Sep. 4, 1990 Filed: Aug. 16, 1989
http://www.freepatentsonline.com/4954709.pdf

U.S. Patent 4817495: Defense System For Discriminating Between Objects In Space ~ Issued: Apr. 4, 1989 Filed: Jul. 7, 1986
http://www.freepatentsonline.com/4817495.pdf

U.S. Patent 4873928: Nuclear-Sized Explosions Without Radiation ~ Issued: Oct. 17, 1989 Filed: June 15, 1987
http://www.freepatentsonline.com/4873928.pdf

Still think that HAARP is just another wacky fictional conspiracy? The above listed patents should be enough to convince any intelligent person that HAARP is real and is now actively modifying our weather and triggering earthquakes. For those who are still not convinced, look to the United States Congress for proof. In order for HAARP to get funding the people who first created HAARP needed funding. That funding was made possible by the US government. If you were to look at Congressional records you would find documents that states just one of the many official purposes of HAARP – for penetrating the earth with signals bounced off of the ionosphere. Congress was informed by people in the High Frequency Active Auroral Research Program that the bounced signals would be used to look inside the planet to a depth of many kilometers in order to locate underground munitions, minerals and tunnels. If you bounced the known earthquake signature signal (2.5 Hz) for a sustained period of time an earthquake could triggered many kilometers inside Earth's crust. The U.S. Senate actually set aside $15 million dollars in 1996 (Clinton and Al Gore Administration) to develop this ability alone — earth-penetrating-tomography.

Update April 21, 2011

Under pressure from the International community the HAARP website is up again. No data is available from April 7 to April 12, 2011. Data before and after shows the signature frequency of an earthquake (2.5Hz) being transmitted. Also shows energy spikes which indicates active weather modification. Now that the website is up again you can view the data for the Japan earthquake at http://137.229.36.30/cgi-bin/scmag/disp ... i?20110311. From the magnetometer induction data you can see 2.5Hz (earthquake inducing frequency) being broadcasted and recorded for several days before the 9.0 magnitude earthquake. To see what a normal (no HAARP broadcasting) day looks like view the magnetometer charts for the days of March 15, 16 and 17 – March 16, 2011 http://137.229.36.30/cgi-bin/scmag/disp ... 0316&Bx=on. No earthquake inducing broadcast was detected from March 15 to March 27, 2011. On March 28, 2011 a low powered broadcast was detected from approximately 12:00 am to 3:00 am. Broadcasting resumed on April 2, 2011. April 6, 2011 shows you what the magnetometer charts looks like when a solar storm blasts Earth. No data is available from April 7, 2011 to April 13, 2011 – a shutdown. Starting on April 15, 2011 and ending approximately 10:00 am April 16, 2011 the earthquake inducing frequency of 2.5Hz was detected being broadcasted.
Short URL: http://presscore.ca/2011/?p=2261

- ▶ Reply
-

Permalink Reply by Jenny on July 27, 2011 at 6:23
WOW MoD! What a paper! I need like a year to get through it all but it sure is awesome to have it all in one place! Excellent!

- ▶ Reply
-

Permalink Reply by Ms MoD on October 26, 2012 at 6:38

Boeing Tests Microwave Missile That Can Knock Out All Electronics (CHAMP)
Huffington Post UK | By Michael Rundle 24/10/2012

Boeing is testing a missile which can destroy electronics in a wide area with little or no physical damage.

The 'Champ' (Counter-electronics High-powered Advanced Missile Project) may "one day change warfare", Boeing said.

"This technology marks a new era in modern-day warfare," said Keith Coleman, CHAMP program manager for Boeing Phantom Works.

"In the near future, this technology may be used to render an enemy’s electronic and data systems useless even before the first troops or aircraft arrive".

The missile was tested on 16 October, when the high-powered microwaves were fired at a two storey building built especially for the job.

The missile would, if successful, take out rows of personal computers which were turned on to gauge the effect of the blast.

The result?

"Seconds later the PC monitors went dark and cheers erupted in the conference room. CHAMP had successfully knocked out the computer and electrical systems in the target building. Even the television cameras set up to record the test were knocked off line without collateral damage."

Seven targets were hit in the one-hour test, and all were successfully disabled.

There is a long way to go before the microwave can be placed into a missile and used to disable targets without loss of life, but the team is hopeful it could prove to be a milestone in non-lethal warfare.

"Today we turned science fiction into science fact," Coleman said.

http://www.huffingtonpost.co.uk/2012/10/24/boeing-tests-microwave-m...

- ▶ Reply
-

Permalink Reply by Ms MoD on August 3, 2013 at 11:01



Scalar Potential Interferometer

Figure 6. Multimode Tesla Weapon

In the 1930's Tesla announced other bizarre and terrible weapons: a death ray, a weapon to destroy hundreds or even thousands of aircraft at hundreds of miles range, and his ultimate weapon to end all war -- the Tesla shield, which nothing could penetrate. However, by this time no one any longer paid any real attention to the forgotten great genius. Tesla died in 1943 without ever revealing the secret of these great weapons and inventions.

Unfortunately, today in 1981 the Soviet Union has long since discovered and weaponized the Tesla scalar wave effects. Here we only have time to detail the most powerful of these frightening Tesla weapons -- which Brezhnev undoubtedly was referring to in 1975 when the Soviet side at the SALT talks suddenly suggested limiting the development of new weapons "more frightening than the mind of man had imagined." One of these weapons is the Tesla howitzer recently completed at the Saryshagan missile range and presently considered to be either a high-energy laser or a particle beam weapon, (See Aviation Week & Space Technology, July 28, 1980, p. 48 for an artist's conception.)


D
E
F
G
B
A
C
L.J.HEFE

Aviation Week & Space Technology July 28, 1980


FOURIER TRANSFORM SECTIONS
(12 WAVELENGTHS EACH)
SCALAR ANT
SCALAR ANT
REFERENCE
CONTROL & PHASING
COMPUTER FACILITY
POWER FOR PULSE MODES
EXPLOSIVE GENERATORS BANK
POWER FOR CONTINUOUS MODES
EXTRA GENERATOR POWERS COMPUTER FACILITY
MORAY POWER UNITS

Figure 7. Tesla Weapons at Saryshagan

The Saryshagan howitzer actually is a huge Tesla scalar interferometer with four modes of operation. One continuous mode is the Tesla shield, which places a thin, impenetrable hemispherical shell of energy over a large defended area. The 3-dimensional shell is created by interfering two Fourier-expansion, 3-dimensional scalar hemispherical patterns in space so they pair-couple into a dome-like shell of intense, ordinary electromagnetic energy. The air molecules and atoms in the shell are totally ionized and thus highly excited, giving off intense, glowing light. Anything physical which hits the shell receives an enormous discharge of electrical energy and is instantly vaporized -- it goes pfft! like a bug hitting one of the electrical bug killers now so much in vogue.

If several of these hemispherical shells are concentrically stacked, even the gamma radiation and EMP from a high altitude nuclear explosion above the stack cannot penetrate all the shells due to repetitive absorption and reradiation, and scattering in the layered plasmas.

In the continuous shield mode, the Tesla interferometer is fed by a bank of Moray free energy generators, so that enormous energy is available in the shield. A diagram of the Saryshagan-type Tesla howitzer is shown in figure 7. Hal Crawford's fine drawing of the interferometer end of the Tesla howitzer is shown in figure 6. Hal's exceptional rendition of the Tesla shield produced by the howitzer is shown in figure 8.



Figure 8. The Tesla Shield


DECOYS
WARHEAD
GAMMA RAYS
EMP
DEBRIS
SCATTERING AND ABSORPTION
SCATTERING AND ABSORPTION
SCATTERING AND ABSORPTION
HEMISPHERES
OF INTENSE
LIGHT BANDS

Figure 9. Tesla Terminal Area Defense System

In the pulse mode, a single intense 3-dimensional scalar phi-field pulse form is fired, using two truncated Fourier transforms, each involving several frequencies, to provide the proper 3-dimensional shape (Figure 10). This is why two scalar antennas separated by a baseline are required. After a time delay calculated for the particular target, a second and faster pulse form of the same shape is fired from the interferometer antennas. The second pulse overtakes the first, catching it over the target zone and pair-coupling with it to instantly form a violent EMP of ordinary vector (Hertzian) electromagnetic energy. There is thus no vector transmission loss between the howitzer and the burst. Further, the coupling time is extremely short, and the energy will appear sharply in an "electromagnetic pulse (EMP)" strikingly similar to the 2-pulsed EMP of a nuclear weapon.

This type weapon is what actually caused the mysterious flashes off the southwest coast of Africa, picked up in 1979 and 1980 by Vela satellites. The second flash, e.g., was in the infrared only, with no visible spectrum. Nuclear flashes do not do that, and neither does superlightning, meteorite strikes, meteors, etc. In addition, one of the scientists at the Arecibo Ionospheric Observatory observed a gravitational wave disturbance -- signature of the truncated Fourier pattern and the time-squeezing effect of the Tesla potential wave -- traveling toward the vicinity of the explosion.


T₀
SLOW WAVE
ΔL₁
FAST WAVE
T₁
T₁
T₂
T₂
ΔL₂
ΔL₃
T₃
$\frac{\Delta L_3}{c} = \Delta T_3 \rightarrow EM_3$

TESLA HOWITZER
(SCALAR INTERFEROMETER)

Figure 10. "Nuclear" Flashes off the Coast of Africa



Lithuania - 10 Sep 1976 - British European Airways Flight #831 between Moscow and London

CIA Report Released under FOIA

Figure 11. Continuous Tesla Fireball

The pulse mode may be fed from either Moray generators or -- if the Moray generators have suffered their anomalous "all fail" malfunction -- ordinary explosive generators. Thus the Tesla howitzer can always function in the pulse mode, but it will be limited in power if the Moray generators fail.

In the continuous mode, two continuous scalar waves are emitted -- one faster than the other -- and they pair-couple into vector energy at the region where they approach an in-phase condition. In this mode, the energy in the distant "ball" or geometric region would appear continuously and be sustained -- and this is Tesla's secret of wireless transmission of energy at a distance without any losses. It is also the secret of a "continuous fireball" weapon capable of destroying hundreds of aircraft or missiles at a distance. An example of a Soviet test of this mode of operation is shown in figure 11.

Witness to a super weapon?



Nick Downie describes the strange lurid glow that flared silently over the Hindu Kush

THE SUNDAY TIMES, 17 AUGUST 1980

(Multiple incidents in Sept., 1979)

TEHERAN, IRAN 17 JUNE 1966

SEEN FROM NEAR MEHRABAD AIRPORT

OBSERVED 4-5 MINUTES

SEEN BY 2 AIRCRAFT



CIA REPORT RELEASED UNDER FOIA

Figure 12. Tesla EMP Globe

The volume of the Tesla fireball can be vastly expanded to yield a globe which will not vaporize physical vehicles but will deliver an EMP to them to dud their electronics. A test of this mode is shown in figure 12. (See also Gwynne Roberts, "Witness to a Super Weapon?", the London Sunday Times, 17 August 1980 for several other tests of this mode at Saryshagan, seen from Afghanistan by British TV cameraman and former War Correspondent Nick Downie.)

If the Moray generators fail anomalously, then a continuous mode limited in power and range could conceivably be sustained by powering the interferometer from more conventional power-sources such as advanced magnetohydrodynamic generators.


DETECTION AND TRACKING
CONTINUOUS TESLA EMP GLOBE (DUDS ELECTRONICS)
TESLA FIREBALL (CONTINUOUS) (VAPORIZES VEHICLE)
TESLA FIREBALL (PULSE)
TESLA HOWITZER
EARTH'S SURFACE
USSR
U.S.
TESLA SHIELD

Figure 13. Tesla ABM Defenses



Figure 14. Moray/Tesla Technology: Star Wars Now

Typical strategic ABM uses of Tesla weapons are shown in figure 13. In addition, of course, smaller Tesla howitzer systems for anti-tactical ballistic missile defense of tactical troops and installations could be constituted of more conventional field missile systems using paired or triplet radars, of conventional external appearance, in a scalar interferometer mode.

With Moray generators as power sources and multiply deployed reentry vehicles with scalar antennas and transmitters, ICBM reentry systems now can become long range "blasters" of the target areas, from thousands of kilometers distance (figure 14). Literally, "Star Wars" is liberated by the Tesla technology. And in air attack, jammers and ECM aircraft now become "Tesla blasters." With the Tesla technology, emitters become primary fighting components of stunning power.

The potential peaceful implications of Tesla waves are also enormous. By utilizing the "time squeeze" effect, one can get antigravity, materialization and dematerialization, transmutation, and mindboggling medical benefits. One can also get subluminal and superluminal communication, see through the earth and through the ocean, etc. The new view of phi-field also provides a unified field theory, higher orders of reality, and a new super-relativity, but detailing these possibilities must wait for another book.

With two cerebral brain halves, the human being also has a Tesla scalar interferometer between his ears. And since the brain and nervous system processes avalanche discharges, it can produce (and detect) scalar Tesla waves to at least a limited degree. Thus a human can sometimes produce anomalous spatiotemporal effects at a distance and through time. This provides an exact mechanism for psychokinesis, levitation, psychic healing, telepathy, precognition, postcognition, remote viewing, etc. It also provides a reason why an individual can detect a "stick" on a radionics or Hieronymus machine (which processes scalar waves), when ordinary detectors detect nothing. Unfortunately there is not room to develop the implications of this human Tesla interferometry in detail, for that must wait for yet another book, presently in its initial stages, that Hal Crawford and I are writing.

Table 5. Orders of Reality

- **PHOTONS ARE**
  - **PAIR-COUPLED SCALARS**
  - **VELOCITY-LIMITED TO C**
  - **CARRIERS OF T**

- **PHOTON INTERACTION**
  - **IS UBIQUITOUS**
  - **PRODUCES $\dot{T}$ = C**
  - **YIELDS 1st ORDER REALITY**

- **SCALAR O WAVES**
  - **NOT VELOCITY-LIMITED**
  - **YIELD HIGHER ORDER REALITIES**



Figure 15. Implications of Tesla Potential

At the July 1981 U.S. Psychotronics Association's Annual Conference in Dayton, Ohio, I presented the first rough paper on the Tesla secret and scalar interferometry. A videotape of the presentation was made and will shortly be available. I am also scheduled to make a special presentation at the Alternate Energy Conference in Toronto, Canada in latter October, 1981. A professional, videotaped two-hour presentation on this subject is also being prepared. Wide distribution of the material through the international underground physics and technology network has already been made. This time, God willing, Tesla's secret will not be suppressed for another 80 years!

And perhaps it is not yet too late. The material has cost me (now) some 16 years of agonizing labor and nearly $100,000 of my own personal funds. No orthodox university, scientific group, foundation, or governmental agency would support such an effort, either financially or otherwise. Indeed, most ordinary journals will not even accept material on such matters. Nonetheless, the area is of overwhelming importance and I truly believe Tesla's lost secret will shortly affect the lives of every human being on earth.

Perhaps with the free and open release of Tesla's secret, the scientific and governmental bureaucracies will be. shocked awake from their slumber, and we can develop defenses before Armageddon occurs. Perhaps there is hope after all -- for even Brezhnev, in his strange July, 1975 proposal to the SALT talks, seemed to reveal a perception that a turning point in war and weaponry may have been reached, and that human imagination is incapable of dealing with the ability to totally engineer reality itself. Having tested the weapons, the Soviets must be aware that the ill-provoked oscillation of timeflow affects the minds and thoughts -- and the very lifestreams and even the collective species unconsciousnesses -- of all lifeforms on earth. They must know that these weapons are two-edged swords, and that the backlash from their use can be far more terrible to the user than was the original effect to his victim.

If we can avoid the Apocalypse, the fantastic secret of Nikola Tesla can be employed to cure and elevate man, not kill him. Tesla's discovery can eventually remove every conceivable external human limitation. If we humans ourselves can elevate our consciousness to properly utilize the Tesla electromagnetics, then Nikola Tesla -- who gave us the electrical twentieth century in the first place -- may yet give us a fantastic new future more shining and glorious than all the great scientists and sages have imagined.

References

http://www.cheniere.org/books/part1/teslaweapons.htm

- ▶ Reply
-

Permalink Reply by rose on August 4, 2013 at 10:54

yeah this ones from deep in the archives Greg - I would love to see that article!!!

- ▶ Reply
-


Permalink Reply by deanna munson on August 4, 2013 at 18:16

what if these weapons work in conjunction with cell towers and smartgrid/wifi relays? i just read this and it blew me away how the dangers this is being purposely ignored http://www.stayonthetruth.com/electromagnetic-fields---killing-fiel... "

November 14 1996, Omnipoint, New York City's first digital cellular provider, did open for business, broadcasting from thousands of antennae newly erected on the rooftops of apartment buildings. According to the health authorities, an early flu hit New York City - but not Boston, and not Philadelphia - on about 15 November. The flu was severe and ran a prolonged course, often dragging on for months instead of the usual two weeks.

At Christmas time, the Cellular Phone Task Force placed a small classified ad in a free weekly newspaper. It read: 'If you have been ill since 11/15/96 with any of the following: eye pain, insomnia, dry lips, swollen throat, pressure or pain in the chest, headaches, dizziness, nausea, shakiness, other aches and pains, or flu that won't go away, you may be a victim of a new microwave system blanketing the city. We need to hear from you.' And we did hear from them. Hundreds called, men, women, whites, blacks, Asians, Latinos, doctors, lawyers, teachers, stockbrokers, airline stewards, computer operators. Most had woken up suddenly in mid-November, thinking they were having a stroke or a heart attack or a nervous breakdown, and were relieved to know they were not alone and not crazy.

Later, I analysed weekly mortality statistics, which the Centres for Disease Control publish for122 US cities. Each of dozens of cities recorded a 10-25 per cent increase in mortality, lasting two to three months, beginning on the day in 1996 or 1997 on which that city's first digital cell phone network began commercial service." we already know these agendas are being forced everywhere.no one is even noticing how even though everyone is already "connected" they are still erecting more and more towers and infastructure,by force in the case of smartmeters.wired in connections now cost over double what wifi does.they just put up another tower here on my block,disguised as a flipping pine tree.cant block the effects when it comes from literally all sides

- ▶ Reply
-


Permalink Reply by Rhonda Reichel on August 6, 2013 at 6:15

Scalar weapons makes all the billions we spend on war obsolete.....what a racket

- ▶ Reply
-


Permalink Reply by steve on August 9, 2013 at 6:43

having read a few pages, it looks like a weapon of distraction to me. The physics is in the realm of the tooth fairy, and the history has the ring of recent manufacture

- ▶ Reply
-

Permalink Reply by rose on August 9, 2013 at 12:24

PLEASE UPDATE YOUR ACCOUNT TO ENABLE 3RD PARTY HOSTING

100%

3rd Party Hosting Usage

FOR IMPORTANT INFO, PLEASE GO TO:
www.photobucket.com/P500

- ▶ Reply
-


Permalink Reply by steve on August 9, 2013 at 16:03

plus, Tom Beardon is nothing but a fear merchant.

- ▶ Reply
-

RSS

Welcome to
The ConTrail

Sign Up
or Sign In

Or sign in with:

-

Visitors



Live Traffic Feed

Watch Live | Get FEEDJIT

Richmond, California, United States arrived 0 secs ago.

Adelaide, South Australia, Australia arrived 20 mins ago.

San Francisco, California, United States arrived 21 mins ago.

San Francisco, California, United States arrived 37 mins ago.

San Francisco, California, United States arrived 40 mins ago.

Hamilton, Waikato, New Zealand arrived 56 mins ago.

New Zealand arrived 1 hour 6 mins ago.

San Diego, California, United States arrived 1 hour 9 mins ago.

Oceanside, California, United States arrived 1 hour 22 mins ago.

Australia arrived 1 hour 54 mins ago.

Groups

-

  ## Health and Wellbeing

  123 members

  99 Comments 10 Favorites

-

  ## Vaccination Information

  87 members

  163 Comments 6 Favorites

-

Simply Good Stuff

40 members

112 Comments 3 Favorites

-

EMF and EMR Information …

101 members

74 Comments 13 Favorites

-

Cancer Treatment Options

74 members

77 Comments 9 Favorites

-

Grow your own Food and M…

96 members

52 Comments 12 Favorites

-

Childbirth

3 members

1 Comment 0 Favorites

- View All

© 2018 Created by rose. Powered by

Badges | Report an Issue | Terms of Service

Sign in to chat!

The Tom Bearden Website

Help support the research

Foundations of Electro-Magnetism

Slide Series

- Major Points of Presentation
- Chung's Carbon Filament Negative Resistor
- Aharanov-Bohm Effect
- Absorption and emission reactions (1)
- Absorption and emission reactions (2)
- Anti-engine for cell's deviation reverses cell back to normal
- Asymmetric regauging produces excess force, which can be used to do work on the system
- Asymmetric regauging produces excess force, which can be used to do work on the regauging system
- Becker's bone fracture healing experiments
- Becker's theoretical control system governing regeneration
- Becker's theoretical DC control system involved with response to injury
- Geometrical Distortion of Poynting Energy Flow
- Cosmic Bootstrap: Before the Big Bang
- Bridging Enables COP > 1

- Aspects of Strong Local Symmetry
- Other Aspects of Strong Local Symmetry
- Bunge on the Status of Electrodynamics
- Bunge on the Status of Electrodynamics and Physics
- Bunge on the Status of Classical and Quantum Physics
- Fractions of BW Casualties Surviving
- First Step in Self-Promotion of Cancer Due to Hypoxia
- Differentiation and Dedifferentiation Timelines
- Evolution of Cells on Earth
- A Charged Particle q is a Coupled System of m and Ø
- The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry (1)
- The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry (2)
- The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry (3)
- A Charged Particle is a Coupled System
- The Anomalies in Navy Electrolyte Experiments at China Lake
- Chung's Carbon Filament Negative Resistor

- Typical circuit has about 10^{-13} energy collection efficiency
- Classical View of EM
- Curved Spacetime acts as source or sink
- Chronic Disease Puzzling
- Cancer Characteristics
- Solving a Cancer Enigma
- Cancer: Characteristics
- Nonlinear Optics Distortion Correction Theorem
- The Electronuclear Reaction: Nuclear Reactions in TR-Zones (1)
- The Electronuclear Reaction: Nuclear Reactions in TR-Zones (2)
- The Electronuclear Reaction: Nuclear Reactions in TR-Zones (3)
- In Time-Reversed Zone: Nuclear reactions are biased
- In Time-Reversed Zone: Dynamics may be reversed
- Time-Reversed Zone: Significant only after time-density charging
- A New Conservation of Energy Law
- Questions on Carcinogens and EM

Radiation

- AS DEFINED, fields and potentials only exist in and on charged matter
- Serious flaws and errors in classical EM theory
- Electrodynamicists' Reaction to Removal of the Material Ether
- Reaction to Loss of Material Ether (1)
- Reaction to Loss of Material Ether (2)
- Some EM waves in Spacetime
- Air Medium Disturbances Generated When Air is Perturbed by a Plucked Taut String
- Launching a Spacetime Perturbation ("EM Wave") from a Wire Antenna
- Phase Conjugate Wavepairs Produce New Waves
- Scalar Electromagnetics (Energetics) View of EM (1)
- Scalar Electromagnetics (Energetics) View of EM (2)

- Scalar Electromagnetics (Energetics) View of EM (3)
- Extended General Relativity Principle
- Extension of Work-Energy Theorem
- 34 Flaws in Classical EM Theory
- MTW's General Relativity Principle
- Use of General Relativity (GR) in Particle Physics
- The Missing Infolded Electrodynamics
- Infolded Engines: Excluded by Present Physics
- Mass curves and structures spacetime; ST curvatures change and structure mass (1)
- Mass curves and structures spacetime; ST curvatures change and structure mass (2)
- At Infinite Velocity: Each Is Every Other
- Lisitsyn's Report: Brain Code Broken
- Lorentz Closed Surface Integration
- Lorentz's physically insignificant energy flow can be collected and utilized
- Lorentz surface integration of the Poynting vector around a closed surface
- Longitudinal EM Photon Interaction with Charge
- Mass is transparent to longitudinal EM waves, which move through the infolded interiors of internal waves, potentials, and fields in the mass.

- Pumping with Longitudinal EM waves Time-reverses the Mass
- Maxwell's Quaternion Theory
- Maxwellian Systems before and after Regauging
- Maxwell's four equations reduce to: Page 1
- Maxwell's four equations reduce to: Page 2
- More to come



Major Points of Presentation

- Electrodynamic is seriously flawed
  - Some major flaws
  - Corrections indicated
- Why past corrective attempts failed
  - Force field concept is material
  - Missing two infolded transforms (M->ST; ST->M)
- Missing infolded general relativity inside electrodynamics
- Several Kinds of EM Waves in Space
  - How to make
  - Transduction
- A French medical example as a deep experimental demonstration
  - Spectacular regenerative cures funded by French Govt
  - Not comprehended, therefore suppressed
- Cold Fusion examples of time-density wave effects
  - China Lake instrumental anomalies in electrolysis
  - Explanation of anomalous behavior of instruments
  - Explanation of new nuclear reactions
  - Wave energy transduction provides excess heat
- Urge theorists to consider dramatically new reactions



Chung's Carbon Filament Negative Resistor

UNIVERSITY AT BUFFALO, NY

W in
CROSSED CARBON
FILAMENT LAYERS
Wout > W in

© [illegible] T.E. Bearden



Aharonov-Bohm Effect

© T.E. BEARDEN 1996

- In field-free regions
  - E-field is zero
  - B-field is zero
- Potentials still exist, just no gradients
  - Cause real effects
  - Interference is the key
  - Contain sum-zeroed substructures
- Does not follow from
  - Mechanics
  - Classical electromagnetics
- Required by quantum mechanics



Absorption and emission reactions

ELECTRON ABSORBS PHOTON ENERGY, MOVES TO HIGHER ENERGY LEVEL. DECAYS BY EMITTING PHOTON

ELECTRON ABSORBS TIME DENSITY, MOVES TO DIFFERENT TIME DENSITY LEVEL. DECAYS BY EMITTING LONGITUDINAL OR PSEUDOLONGITUDINAL PHOTON

© T.E. BEARDEN 1998

PARTICLE ABSORBS ENERGY, MOVES TO HIGHER ENERGY SHELL. DECAYS BY EMITTING ENERGETIC PARTICLE. OBSERVABLE..

PARTICLE ABSORBS TIME, MOVES TO HIGHER TIME DENSITY. DECAYS BY EMITTING TIME-LIKE PARTICLE, NONOBSERVABLE BY PRESENT MEANS.

ENTIRE NUCLEUS ABSORBS ENERGY, EACH PARTICLE ABSORBS OWN. DECAY OCCURS BY COMPLEX MODES, INCLUDING FISSION OR FUSION. DECAY BYPRODUCTS OBSERVABLE.

ENTIRE NUCLEUS ABSORBS TIME, EACH PARTICLE ABSORBS OWN. DECAY OCCURS BY COMPLEX MODES, INCLUDING FISSION OR FUSION. SOME DECAY BYPRODUCTS ARE NONOBSERVABLE (SPACE ABSORBS)



Absorption and emission reactions

TRANSVERSE PHOTON

ELECTRON ABSORBS PHOTON ENERGY, MOVES TO HIGHER ENERGY LEVEL. DECAYS BY EMITTING PHOTON, REMOVING Δt

Δt coupled and emitted quickly

Figure A. Excited energy density level in one jump.

STREAM OF TIME-POLARIZED PHOTONS

ELECTRON ABSORBS TIME DENSITY, MOVES TO $1/c_2$ DIFFERENT TIME DENSITY LEVEL. DECAYS BY EMITTING LONGITUDINAL OR PSEUDOLONGITUDINAL PHOTONS

Δt increases quasi-statically then slowly decays

Figure B. Excited time density level significant only after enormous number of increases.

© T.E.BEARDEN 1998



ANTI-ENGINE FOR CELL'S DEVIATION REVERSES CELL BACK TO NORMAL

PHYSICAL
CELL
(DISEASED)

+

EXTENDED
TIME DELAY FOR
RENORMALIZATION

PHYSICAL
CELL
(NORMAL)

VACUUM
ENGINE
FOR DISEASED
CELL

VACUUM/SPACETIME
ANTI-ENGINE FOR
CELL'S DISEASE DELTA

© 1994, 1995 T.E. BEARDEN

By pumping the internal EM channel, process is dramatically accelerated.
This is the body's normal recovery mechanism, within its limits.



Asymmetric Regauging Produces Excess Force, Which Can be Used to Do Work on the System

Net Symmetric Regauging Does No Excess Work on the System

This little bird put one foot on wire A, and then the second foot on wire A also. He *net symmetrically* regauged, so he had no net excess force across him, even though his potential energy was increased. He asymmetrically regauged each foot, but both simultaneously so that one countered the other. Wise little bird!

Net Asymmetric Regauging *Can* Do Excess Work on the System

This little bird put one foot on wire A, and then the second foot on wire B. He *net asymmetrically* regauged, so he had lots of net excess force across him. That force then violently translated his little body parts every which way, doing lots of work in and on him. Bummer!

Ⓒ T.E. BEARDEN 1999



Net Symmetric Regauging Does No Excess Work on the System

This little bird put one foot on wire A, and then the second foot on wire A also. He *net symmetrically* regauged, so he had no net excess force across him, even though his potential energy was increased. He asymmetrically regauged each foot, but both simultaneously so that one countered the other. Wise little bird!



Net Asymmetric Regauging Can Do Excess Work on the System

This little bird put one foot on wire A, and then the second foot on wire B. He *net asymmetrically* regauged, so he had lots of net excess force across him. That force then violently translated his little body parts every which way, doing lots of work in and on him. Bummer!

ⓒ T.E. BEARDEN 1996

Figure 32. Asymmetric regauging produces excess force, which can be used to do work on the regauging system.

Selected clipart © by Lotus SmartPics™



Becker's bone fracture healing experiments

- Tiny DC currents (picoamperes)
- Pulsed DC current can be utilized
- Pulsed magnetic fields may be utilized

(+)
ELECTRODE
(-)
ELECTRODE
DC POWER SOURCE
BONE
BONE
FRACTURE SITE

RED BLOOD CELL DEDIFFERENTIATES

Shucks hemoglobin coat
Grows nucleus

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes cartilage

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes bone
Deposits in fracture site, healing the fracture

© 1993, 1995 T.E. BEARDEN



Becker's theoretical control system governing regeneration*

Trauma Producing Tissue Loss

Local cellular effect

Local nerve effect

CNS effect

Alterations in hormone pattern (prolactin)

Alterations in local DC field pattern

Local electrical effects

Local and systemic pools of target cells

Dedifferentiation into primitive mesenchymal cells

Phase I

Blastema formation

growth

Phase II

Redifferentiation into required cell types

Restoration of body part or tissue

*Becker & Spadaro, "Electrical stimulation of partial limb regeneration in mammals," Bul. N.Y. Acad. Med., 48(4), May 1972, p. 629.

Becker's theoretical DC control system involved with response to injury*



INJURY

INPUT STIMULATION DC SYSTEM (PAIN)

CENTRAL DC SYSTEM

OUTPUT DC SYSTEM

TOTAL CURRENT OF INJURY DC SYSTEM

LOCAL CELL INJURY FREE RADICALS

STIMULATION OF REPAIR CELLS

MITOSIS DEDIFFERENTIATION

GROWTH DIFFERENTIATION

*Robert O. Becker, "The significance of bioelectrical potentials," Bioelectrochemistry and Bioenergetics, Vol. 1, 1974, p. 191.



Geometrical Distortion of Poynting Energy Flow

At or near resonance frequency, in the case shown the energy collection fraction (reaction cross section) increases dramatically.

a. Around an aluminum sphere at light energy 8.8 eV. Absorption efficiency = 18.00.

b. Around an aluminum sphere at light energy 5eV. Absorption efficiency = 0.1.

Figures per Craig F. Bohren, "How can a particle absorb more than the light incident upon it? ", American Journal of Physics, 51(4), Apr. 1983, p. 326.



Cosmic Bootstrap: Before the Big Bang:

- Cosmic repulsion behaved like a fluid with negative pressure
- The "universe" inflated (expanded) as a "false vacuum"
- As the negative-pressure fluid expanded, its energy went up rather than down
- When inflation stopped, the false vacuum decayed from its excited state
- Its excitation energy was released in a single great burst

Paul Davies, Superforce, 1984, p. 194

BRIDGING ENABLES COP > 1.0


S-flow, dϕ /dt flow, and EMF flow
V>>0
source
i ≈ 0
dQ/dt
BLOCKER
(Conductor)
V>>0
i>>0
LOAD
Closed Current
Loop A
Closed Current
Loop B

BRIDGE

Current loop B is asymmetrically regauged by S, dϕ /dt, and EMF flow from current loop A.

Patent Pending

© 1998 T.E. BEARDEN



Aspects of Strong Local Asymmetry

- If local asymmetry is strong, conservation laws may be appreciably violated
    - Energy
    - Charge
    - Spin
    - Momentum
    - Angular momentum

© T. E. Bearden 1995, 1996

- Properties of an object may differ appreciably for
    - Different observers
    - Different detecting means
    - One time to another
    - One position to another
- STRUCTURING THE INFOLDED EM INSIDE POTENTIALS, FIELDS, AND WAVES
    - Strongly breaks local symmetry
    - Provides spacetime engines giving the above effects



Other Aspects of Strong Local Asymmetry

© T. E. Bearden 1995, 1996

- Local spacetime is curved
- Lorentz invariance of vacuum is violated
- May be a local "sink" or "source"
- Gravitational-inertial effects from EM
- Translation between virtual and observable
- Electrogravitational solitons
- Action at a distance
- Transmutation effects may exist
- Scalar/pseudoscalar field translation
- COMMENT: Thus the use of infolded longitudinal EM fields and waves to strongly break local symmetry allows internested clustering of spacetime curvatures. These spacetime structures are *vacuum engines*, or *spacetime engines*.



Bunge on the Status of Electrodynamics

"... it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state..."

"... the best modern physicist is the one who acknowledges that neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling..."

*Mario Bunge, Foundations of Physics, Springer-Verlag, New York, NY, 1967, p. 176..

© 1996 T.E. BEARDEN



Bunge on the Status of Electrodynamics and Physics

"... it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state...

"... neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling..."

*Mario Bunge, Foundations of Physics, Springer-Verlag, New York, NY, 1967, p. 176..

© 1996 T.E. BEARDEN



Bunge on the Status of Classical and Quantum Physics

"... it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state... the best modern physicist is the one who acknowledges that neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling not only to better cover their own domains but also to join smoothly so as to produce a coherent picture of the various levels of physical reality."

'Mario Bunge, Foundations of Physics, Springer-Verlag, New York, NY, 1967, p. 176..

© 1996 T.E. BEARDEN


Fraction of Casualties Surviving
N = 1 - 40 million
FRACTION SURVIVING
1.0
0.8
0.6
0.4
0.2
0.0
N CASUALTIES
0.1
0.7
0.9
0.95
CASUALTIES
TYPE TREATMENT RECEIVED
© 1998 T. E. BEARDEN
EXPRESSED IN FRACTION SURVIVING
🟩 With conventional treatment
🟨 With 1st generation P-treatment
🟨 With 2nd generation P-treatment
🟥 With 3rd generation P-treatment



FIRST STEP IN SELF-PROMOTION OF CANCER DUE TO HYPOXIA

MULTICELL
AEROBIC*
(INCLUDES MAN)
SINGLE CELL
ANAEROBIC
SINGLE CELL
AEROBIC*
CENTRAL CONTROL
OXYGEN-RICH
TIME-FORWARD
PATH AS IT
DEVELOPED
CANCER CELL
TIME-REVERSED
PATH FOR SUSTAINED
OXYGEN DEFICIENCY
PARTIALLY
ANAEROBIC
SINGLE CELL
AEROBIC
FIRST STEP IN OXYGEN-DEFICIENCY
DEDIFFERENTIATION
© 1993 T.E. Bearden



Differentiation and Dedifferentiation Timelines

CENTRALIZED CONTROL OF CELLULAR GROWTH AND REGENERATION

PRIMORDIAL SINGLE CELL ANAEROBIC

SINGLE CELL AEROBIC

OXYGEN-RICH ENVIRONMENT

NORMAL HEALTHY CELLS AND FUNCTIONS

WITH SOME DISEASED OR DAMAGED CELLS

TIME-FORWARD PATH AS IT DEVELOPED

© 1993, 1998 T.E. Bearden

NORMAL "DEDIFFERENTIATION" FOR HEALING OF CELL DAMAGE

SINGLE CELL MORE ANAEROBIC

SINGLE CELL AEROBIC

TIME-REVERSED PATH FOR SUSTAINED OXYGEN DEFICIENCY

TIME-REVERSED PATH WHEN NORMAL PUMPING FAILS TO HEAL CELL

Evolution of Cells on Earth



ESSENTIALLY ANAEROBIC ATMOSPHERE

BIOGENESIS

SINGLE CELL ANAEROBIC

CHANGE OF ATMOSPHERE TO AEROBIC (INCLUDES OXYGEN)

OBLIGATORY ANAEROBES SINGLE CELL SHIELDED FROM OXYGEN

FACULTATIVE ANAEROBES (SINGLE CELL BOTH AEROBIC AND ANAEROBIC)

EVOLVE TO

SINGLE CELL AEROBIC*

EVOLVE TO MULTICELL AEROBIC* (INCLUDES MAN)

CENTRAL CONTROL

SINGLE CELL COMPONENTS

- IMMUNE SYSTEM
- RED CELLS
- WHITE CELLS
- KILLER CELLS
- ETC.

MULTICELL COMPONENTS

- TISSUES
- MUSCLES
- BONES
- ORGANS
- SKIN
- STRUCTURES

* NOTE: LIMITED ANAEROBIC RESPIRATION STILL TAKES PLACE IN HIGHER AEROBIC LIFE FORMS, INCLUDING MAN.

EVOLUTIONARY TIME

© 1999 T. E. BEARDEN



A Charged Particle q Is a Coupled System of m and ϕ

(A proposed formal definition of a charged mass)

Note: X is a coupling operator

$$q \equiv f_q \times m_q$$

Also note that the ϕ portion of the charged particle can be internally structured, per Stoney-Whittaker-Ziolkowski, with hidden bidirectional EM wavepairs (their sums and products). Note that this constitutes an EM application of Bohm-type hidden variable theory, with many ramifications.

S = EXH

"...curiously enough, we do not know exactly what charge is, only what it does. Or, equally significantly, what it does not do."

M.P. Silverman, And Yet It Moves: Strange Systems and Subtle Questions in Physics, Cambridge University Press, 1993, p. 127.

© T.E. BEARDEN 1997

An electric charge Q consists of a massless flux component and a mass component, coupled together (interacting). Q is a broken symmetry. The mass of the charge continually and violently exchanges virtual photons with the surrounding vacuum.

Thus Q is energetically driven by the surrounding vacuum potential, which itself is to first order just a violent virtual photon flux.



The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry

You really need
a Maxwell's demon,
to do some free work.

Your electrodynamicist
says he can make one,
by regauging.

© T.E. BEARDEN 1999



The Ubiquitous Assumption: *Two* Asymmetrical Regaugings for Net Symmetry

He says he will do the regauging for you. Hey, what a swell guy!

He regauges *twice*, and makes two Maxwell's demons equal and opposite. They won't do any net work for you!

© T.E. BEARDEN 1999



The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry

YE OLDE ELECTRO-
DYNAMICIST

He disdainfully says,
"We *always* do it that way!
We *must* enforce local
equilibrium and the second
law of thermodynamics!".

You decide to have a
little chat with your
electrodynamicist!
With friends like that,
who needs enemies!

© T.E. BEARDEN 1999



A Charged Particle Is a Coupled System

(The first formal definition of charge)

$$\boxed{q \equiv \phi_q \; x \; m_q}$$

Note: X is a coupling operator

VACUUM CHARGE

MASS

m_q

virtual photon flux exchange

ϕ_q

© 1994 T.E BEARDEN

"...curiously enough, we do not know exactly what charge is, only what it does. Or, equally significantly, what it does not do."

M.P. Silverman, And Yet It Moves: Strange Systems and Subtle Questions in Physics, Cambridge University Press, 1993, p. 127.

An electric charge q is a broken symmetry in its fierce energy exchange with the active vacuum. It coherently integrates some of the virtual energy absorbs and outputs it as Poynting energy flow.



Chung's Carbon Filament Negative Resistor

UNIVERSITY AT BUFFALO, NY
© 1996 T.E. Bearden
Win
Wout > Win
CROSSED CARBON FILAMENT LAYERS



Typical circuit has about 10-13 energy collection efficiency

Distance traveled by S in one hour is 1.08x10exp(12) meters.

Example: 1.3 amps flowing in DC circuit, 1.8 mm diameter copper wire. $J = 51 \text{ A/cm}^2$

$d_i = 0.1368$ meters

S violently transports ϕ provided from the source.
jϕ sluggishly transports the energy collected and dissipated in the circuit..

For the case discussed, the electron drift velocity in the circuit is about 3.8×10^{-5} meters/sec. So Jϕ moves about 0.1368 meters in one hour. Thus Jϕ has collected about 0.1368 meters of the ϕ-filled S-tube. During that same hour, the S-flow evoked by the power source will have traveled 1.08×10^{12} meters. The ϕ of both currents is the same. Both are involved in the same energy-filled tube. Thus S has provided and transported about 7.89×10^{12} times as much energy along the circuit in one hour as the jϕ has been able to collect, transport, and dissipate as work in the circuit. Thus this circuit provides about 10^{13} collection efficiency.



Classical View of EM

- Potentials just mathematical conveniences
  - Not real
  - No internal structure, just magnitude
- Force fields primary, causative, can exist in space in absence of observable mass
  - All EM actions due to force fields, none when zero
  - No action at a distance
- Vacuum empty; without energy or structure
  - No locally curved spacetime
  - No gravity effects
  - No quantum effects
- Maxwell's equations complete
  - Symmetrically regauged ***arbitrarily***
  - Topology dramatically reduced



Curved Spacetime acts as source or sink

- May emit excess radiation and energy (e.g., heat)
- May absorb radiation and energy (e.g., cool)
- May transduce waves
  TW ⇔ LW ⇔ TDW
- New energy conservation law applies

© 1998 T.E.BEARDEN



CHRONIC DISEASE PUZZLING

- SCIENCE REALLY DOES NOT UNDERSTAND THE MECHANISMS OF A SINGLE CHRONIC DISEASE, INCLUDING CANCER
- MANY TROUBLING FACTORS EXIST
  - *MIND*
  - *STRESS*
  - *SPONTANEOUS REMISSION*
  - *PLACEBO EFFECTS*
  - *COMBINATIONS*
- GENERATION OF THE PLACEBO EFFECT BY THE CELLULAR REGENERATION SYSTEM IS UNRECOGNIZED

© 1994, 1995 T.E. Bearden



Cancer Characteristics

- Not one disease, but a whole range
- Starts in damaged aerobic cell
- Cell shakes off body's central control
  - Starts uncontrolled division
  - Becomes a lump
- Can send forth cancer cells
  - Through blood
  - Through lymph
- Form metastases (secondary tumors)
- Often become anaerobic

© 1993 T.E. Bearden



Solving a Cancer Enigma

- An enigma has been failure of immune system to attack some tumor cells
  - Suppressor cells may curb immune system?
  - Tumor may lack antigens normally identified by the immune system?
- *Promotion of damaged cell to cancer is usually ordered by cellular control system*
  - *Regenerative and recovery system forces cell back toward anaerobe*
  - *First step breaks free from central growth*
  - *Control continues to recognize cell as self*



CANCER: CHARACTERISTICS

- NOT ONE DISEASE BUT A WHOLE RANGE
- STARTS IN ORDINARY (AEROBIC) CELL
- CELL SHAKES OFF BODY'S DICTATORIAL CONTROL*
- STARTS UNCONTROLLED DIVISION
- BECOMES A LUMP
- CAN SEND FORTH CANCER CELLS
  - THROUGH BLOOD
  - THROUGH LYMPH
- THESE FORM METASTASES (SECONDARY TUMORS)
- OFTEN BECOME ANAEROBIC (NON-OXYGEN USING)
- ENIGMA IS FAILURE OF IMMUNE SYSTEM TO ATTACK SOME TUMOR CELLS
  - SUPPRESSOR CELLS MAY CURB IMMUNE SYSTEM
  - TUMOR MAY LACK ANTIGENS NORMALLY IDENTIFIED BY THE IMMUNE SYSTEM

*R&R system forces cell back toward anaerobe

© 1993 T.E. Bearden



Nonlinear Optics
Distortion Correction Theorem

E 1 = INCIDENT WAVE

E 2 = TIME-REVERSED WAVE

© 1994, 1995, 1998 T. E. BEARDEN

"If a scalar wave $E_1(r)$ propagates from left to right through an arbitrary but lossless dielectric medium, and if we generate in some region of space [say near z = 0] its phase conjugate replica $E_2(r)$, then E_2 will propagate backward from right to left through the dielectric medium, remaining everywhere the phase conjugate of E_1."



The Electronuclear Reaction: Nuclear Reactions in TR-Zones (1)

- Nucleon interchange
  - Changes neutron into proton and vice versa
  - At high rate (flat spacetime assumed)
- Statistics become skewed due to curved ST
- Can bias statistics toward either neutron or proton end
  - Biases toward transmutation of elements along isomer chains
  - Concept of "isomer" is vastly expanded



The Electronuclear Reaction: Nuclear Reactions in TR-Zones (2)

- **Normal dynamics (impulses) may reverse**
  - *Like charges attract, unlike charges repel*
  - *Positive charges cluster (are drawn together)*
  - *H+ ions (protons) may form quasi-nuclei*
  - *Nucleus coulomb barrier becomes assistant*
- **Many "impossible" reactions now possible**
  - *Quark access and quark flipping by EM*
  - *Ion clustering*
  - *Positive charges as phase conjugate mirrors*
  - *Time-density waves and time-energy charging*

© [illegible] T. E. Bearden



The Electronuclear Reaction: Nuclear Reactions in TR-Zones (3)

- **Not observed until time-energy charging has become substantial**
  - *Time delay (hours, days)*
  - *Transduction of LW --> TW involved*
  - *Specific time-charging history of detectors is involved in twhether they detect or not*
  - *Longitudinal EM waves become significant*
- **Curved spacetime can act as source or sink**
  - *May emit excess radiation*
  - *May absorb excess radiation*



In Time-Reversed Zone:
Nuclear reactions are biased

- In normal flat ST, n ⇔ p at high rate
- Curved ST skews statistics
- Biases to either n or p
- Biases to transmutation along isomer chain
- "Isomer" concept greatly expanded

© 1998 T.E.BEARDEN



In Time-Reversed Zone:
Dynamics may be reversed

- Like charges may attract and unlike charges repel
- Coulomb barrier becomes Coulomb assistant
- Clusters like charges and forms artificial nuclei
- "Impossible" nuclear reactions at low energy
- Time-density interactions



Time-Reversed Zone:

Significant only after time-density charging

- Hours, for "fast" onset
- Days, for "slower" onset
- Transduction involved for TW ⇔ LW ⇔ TDW
- Time-history of each detector is significant
- Longitudinal EM waves become significant



A New Conservation of Energy Law

- Physics conserves total "energy and mass-energy"
- Now also must consider "time-energy"
- Conserve total mass-time-energy (spatiotemporal energy)
- Let E_T = total energy, E_M = mass energy, E_E = ordinary energy, and E_t = time energy. Then

$$E_T = E_E + E_M + E_t$$

© 1998 T. E. Bearden

$$(kE_t \Rightarrow E_E > 0) \;\Rightarrow\; E_T > (E_M + E_E)$$

- If some E_t is transduced into E_E , the experiment will violate the old spatial mass-energy conservation law



QUESTIONS ON CARCINOGENS AND EM RADIATION

- UNRESOLVED QUESTIONS ON EM RADIATION
  - DOSAGES
  - ACTIVE MECHANISMS
  - REPLICATION DIFFICULTIES
  - MEASUREMENT DIFFICULTIES
  - WHERE, WHEN, HOW ILL EFFECTS OCCUR
- SIMILAR QUESTIONS EXIST ABOUT EVERY CARCINOGEN
- SCIENCE REALLY DOES NOT UNDERSTAND THE MECHANISMS OF A SINGLE CHRONIC DISEASE, INCLUDING CANCER
  - FACTORS SUCH AS MIND, STRESS, SPONTANEOUS REMISSION, PLACEBO EFFECTS, AND COMBINATIONS OF FACTORS ARE PARTICULARLY TROUBLESOME
  - GENERATION OF THE PLACEBO EFFECT BY THE REGENERATION & RECOVERY SYSTEM IS UNRECOGNIZED

© 1994, 1995 T.E. Bearden



As defined, fields and potentials only exist in and on charged matter

$E \equiv F/q$

$S = E \times H$

Note problem:
No "E" or "H" in vacuum.

Source q is a broken symmetry in vacuum flux

$S = E \times H$

SOURCE CHARGE

Assumed perpetual motion machine in classical EM

"pileup" in front
So $E \equiv -\nabla\phi$

Point coulomb

$\phi \equiv$ joules continuously in geometrical flow distortion zone around a point coulomb

Electrodynamics has nothing to say about what exists in space in the absence of mass.

© 1997 T.E. BEARDEN



Serious flaws and errors in classical EM theory.

1. Eliminates the Internal EM Inside the Scalar Potential.
2. No Definition of Electrical Charge or of Scalar Potential.
3. Equations Still Assume Material Ether Per Maxwell (Unchanged).
4. Use of Force Fields in Vacuum is False (and Known to be So).
5. Treats Charge q as Unitary Instead of Coupled System $q = \phi[q]m(q)$.
6. Confuses Massless Potential Gradients as Forces (See #3, #4).
7. Does Not Utilize Mass as a Component of Force (See #23).

8. Erroneously Assumes EM Force Fields as Primary Causes.
9. Topology of EM Model Has Been Substantially Reduced.
10. Does Not Include Quantum Potential or Action at a Distance.
11. Does Not Include Superluminal Velocity of Inner EM Components.
12. Does Not Utilize Extended Near-Field Coulomb Gauge Effects.
13. Does Not Include EM Generatrix Mechanism for Time Flow.
14. Does Not Unify Photon and Wave Aspects (Requires 7-D Model).

15. Does Not Include Electron Spin and Precession (See #19, #24).
16. Treats EM Energy As Existing In "Chunks," Instead of as Flow.
17. Confuses Energy and Energy Collection (See #16).
18. Discards Half of Every EM Wave in Vacuum (See #22).
19. Erroneously Uses Transverse Vacuum Wave; It's Longitudinal.
20. Arbitrarily Regauges Maxwell's Equations to Eliminate Overunity.
21. Omits Phase Conjugate Optics Effects (The *Rule* in Internal EM).
22. Does Not Include EM Cause of Newtonian Reaction Force.
23. Erroneously Assumes Separate Force Acting on Separate Mass.
24. Confuses Detected Electron Precession Waves as Proving Transverse EM Waves in Vacuum (Remnant of Old "EM Fluid" Concept).
25. Due to Error in String Wave, Omits the Ubiquitous Antiwave.
26. *Assumes* Equilibrium; Not True Unless Include Vacuum Interactions.
27. Higher Topology Required, to Model Electromagnetic Reality.
28. Lorentz surface integration discards Poynting energy transport.
29. Has nothing at all to say about form of EM entities in massless space.
30. Eliminates the infolded general relativity using EM-force as curve agent.
31. Does not include longitudinal EM waves as time domain oscillations.
32. Does not include EM mechanism that generates time flow and flow rate.

© T.E. BEARDEN [illegible]


NONMATERIAL SPACETIME
© T.E. BEARDEN 1998
Einstein's spacetime hasn't been born yet!
Michelson-Morley experiments, 1880's
Our material ether is gone, so only inert space is left!
1880s
MAXWELL
Material Fluid Perturbation Equations
MAXWELL
Φ, H
Material Electric Fluid Disturbed
Material Electric Fluid Disturbed
???
Now we are not using a material ether. Trust us! The equations do not need changing.
ELECTRODYNAMICISTS

Electrodynamicists' Reaction to Removal of the Material Ether



REACTION TO LOSS OF MATERIAL ETHER

Material Ether Assumed in Equations

Potentials, Fields, and Waves Assumed Material

Not a single equation was changed!

Now we are not using a material ether. Trust us! The equations do not need changing.

© T.E. BEARDEN 1999

ELECTRODYNAMICISTS


NONMATERIAL SPACETIME
MASSLESS SPACETIME PERTURBATIONS NOT ADDRESSED
Einstein's spacetime hasn't been born yet!
1888
MAXWELL
Falsely Assumed Matter-in-Space Perturbations
MAXWELL
H
ϕ
Material Electric Fluid Disturbed
CAUSE
Material Electric Fluid Disturbed
EFFECT
???
Okay! We will just measure material entities, and call them nonmaterial.
ELECTRODYNAMICISTS
© T.E. BEARDEN 1998



Some EM Waves in Spacetime

SPACE

TIME

GALLOPING WAVE. TRANSVERSE WAVE THAT VARIES VELOCITY ALONG Z-DIRECTION, IN WAVE FASHION. (Ex: 0.01 c - 100 c)

TIME-POLARIZED (TIME-ENERGY) OSCILLATIONS

3-SPATIAL ENERGY DENSITY OSCILLATIONS

SCALAR WAVES. X, Y, Z FIXED. T VARIES. NONOBSERVABLE.

TRANSVERSE WAVES. X AND Y ENERGY DENSITY VARIES; Z FIXED.

TRANSDUCTION

TIME DENSITY OSCILLATIONS. X, Y, Z ENERGY DENSITY DO NOT VARY.. TIME DENSITY VARIES ALONG TIME DENSITY NOTOBSERVABLE, BUT TRANSDUCTION IS OBSERVABLE.

PSEUDO-LONGITUDINAL WAVES. X AND Y VARY A LITTLE, SURGE OSCILLATIONS IN Z DIRECTION.

TIME DENSITY OSCILLATIONS. X, Y, Z ENERGY DENSITY FIXED. TIME DENSITY IS NONOBSERVABLE, BUT TRANSDUCTION IS OBSERVABLE.

LONGITUDINAL WAVES. X AND Y FIXED; SURGE OSCILLATIONS IN Z DIRECTION.

TRANSDUCTION

© T.E. BEARDEN 1998



Air Medium Disturbances Generated When Air is Perturbed by a Plucked Taut String

The string wave and the holder wave never leave the string and holder respectively.

Wave is alternatively compressive and rarefactive

String slaps air medium

WAVE IN STRING (TRANSVERSE)
Lower degree of freedom for string.
Can only vibrate mostly laterally.

Drude Electron Gas waves

Nuclear proton waves

ANTIWAVE IN HOLDER
(Highly damped; not shown to scale)

Body slaps air medium

© 1993, 1995 T. E. BEARDEN



Launching a Spacetime Perturbation ("EM Wave") from a Wire Antenna

ANTENNA
ELECTRON SHELLS (DAMPED)
NUCLEI (HIGHLY DAMPED)
VACUUM
GRAVITON
time forward slap (electron)
time reversed slap (proton)
Modulations of virtual photon flux intensity of the QM vacuum

By omitting the nuclei perturbation wave, Maxwell omitted Newton's third law from electrodynamics

© T.E. BEARDEN 1994, 1995



Phase Conjugate Wavepairs Produce New Waves

TRANSVERSE EM WAVE PLUS
PHASE CONJUGATE REPLICA WAVE

LONGITUDINAL EM SURGE WAVE

LONGITUDINAL EM WAVE PLUS
PHASE CONJUGATE REPLICA WAVE

$\dot{(t)}$

TIME DENSITY WAVE

Oscillates rate of flow of time about some average value

© T.E. BEARDEN 1994, 1995



Scalar Electromagnetics (Energetics) View of EM

- Potentials real; primary causes of EM phenomena
  - Force fields made by differentiations of potentials
  - Force fields are effects, not primary causes
  - Force fields exist only in, on mass particles
- Actions due to potentials and their interference
  - Action at a distance or locally
  - Quantum potential and hidden variables
- Locally curved spacetime, engineerable by EM
  - Gravity effects not necessarily negligible
  - Strong EM force or time used as agent of curvature

© T.E. BEARDEN 1990, 1996



Scalar Electromagnetics (Energetics) View of EM (Cont'd)

- Potentials have internal structure
  - Stoney/Whittaker structure
  - Longitudinal EM phase conjugate wavepairs
  - Each wavepair is a time-polarized EM wave
- Vacuum EM is a potential and has microstructure
  - Stoney-Whittaker biwaves/t-polarized waves
  - Fluctuations exhibit chaos
- Spacetime ≡ Vacuum ≡ Potential ≡ Flux

© T.E. [illegible]



Scalar Electromagnetics (Energetics) View of EM (Cont'd)

- Statistics may have hidden order (already chaotic)
- Uses spacetime curvature engines to alter matter (inside-out or outside-in)
- Engineerable EM mechanism generates rate of flow of a mass through time
- Quantum potential with specific QP can be used for instant action at a distance



Extended General Relativity Principle

- "All levels of energy structures and all levels of time structures mold spacetime geometry.
- This is called a *vacuum engine* (spacetime engine).
- Spatial and temporal structuring act upon mass at all levels.
- This produces *templates* of forces, for translations and stresses."

© T.E. BEARDEN 1990

ACTIVE SPACETIME
DYNAMIC MASS
STRUCTURING OF ACTIVE SPACETIME CURVATURES



Extension of Work-Energy Theorem

© T.E. BEARDEN 1997

- *Theorem*: $W = k_f - k_i = \Delta k$ [1]
- k must be interpreted not as energy *per se*, but as *collected/collecting* energy.
- The reaction cross section λ for the collecting process must be included.
- *Extension*: $W = \lambda (k_f - k_i) = \lambda \Delta k$ [2]
- Normally $\lambda \leq 1$, as for elastic collision or Stokes emission.
- However, $\lambda > 1$ is now possible, for processes which asymmetrically self-regauge. An example is Letokhov's negative absorption of the medium.
- Working models are the Patterson Power Cell® and Lawandy lasing without population inversion.



MTW's General Relativity Principle

- "Space acts on matter, telling it how to move.
- In turn, matter reacts back on space, telling it how to curve."

ACTIVE SPACETIME

DYNAMIC MASS

STRUCTURING OF ACTIVE SPACETIME CURVATURES

© T.E. BEARDEN 1998



Use of General Relativity (GR) in Particle Physics

© 1998 T.E. Bearden

- GR seldom used in particle physics
- In cold fusion, Matsumoto* has applied general relativity
- Consistent with important cold fusion results
- Used spacetime (ST) curvature by energy density
- Matsumoto did not utilize:
  - Longitudinal EM waves
  - Time density waves
  - Time density curvatures of ST (gain = $9\text{x}10^{16}$)

* T. Matsumoto, "Mechanisms of Electro-Nuclear Collapse," Proc. ICCF-7, Vancouver, BC, Canada, Apr. 1998, p. 98



THE MISSING INFOLDED ELECTRODYNAMICS

Maxwellian electrodynamics has nothing at all to say about EM entities in space or their form

Material Electric Fluid Disturbed

MATTER-TO-MATTER TRANSFORM

Material Electric Fluid Disturbed

MATTER-TO-SPACETIME TRANSFORMATION

INFOLDED INSIDE MAXWELLIAN EM AS HIDDEN EM VARIABLES

SPACETIME-TO-MATTER TRANSFORMATION

INTERNESTED SPACETIME CURVATURES
(VACUUM ENGINES)
INFOLDED GENERAL RELATIVITY

EINSTEIN'S SPACETIME

© T.E. BEARDEN 1998



Infolded Engines: Excluded by Present Physics

- *The infolded dynamics of EM systems are not considered in general relativity, electromagnetics, or quantum mechanics*
- *None of these disciplines include such spacetime curvature engines (vacuum engines)*
- *Thus GR, EM, and QM cannot be unified, since ST curvature engines are where the unification mainly occurs*

© 1999 T. E. BEARDEN



ST curvatures propagate

© T.E. BEARDEN 1998

mass perturbation (Drude Electrons)

Transmitter

mass-to-spacetime transformation

altered spacetime (curvatures)

spacetime-to-mass transformation

altered spacetime (curvatures)

mass perturbation (Drude Electrons)

Receiver

Complex of ST curvatures (vacuum engine, or spacetime engine)

Spacetime disturbance (engine) propagates

The *mass-to-mass transform* contains two hidden infolded transforms: (i) the *mass-to-spacetime transform* and (ii) the *spacetime-to-mass* transform. What is transmitted and propagates in space is a *spacetime perturbation.*



Mass curves and structures spacetime; ST curvatures change and structure mass

ST curvatures propagate
mass
mass-to-spacetime transformation
spacetime-to-mass transformation
mass
altered spacetime
altered spacetime
ST curvature complex (vacuum engine)
spacetime disturbance propagates

© T.E. BEARDEN 1996



At Infinite Velocity:

Each Is Every Other

SPACETIME

VIRTUAL
PARTICLE
FLUX

POTENTIAL

MIND AND
MIND LEVELS

MASS

PLANET

LIVING ORGANISMS

© 1997 T.E. Bearden



Lisitsyn's Report: Brain Code Broken

- THEORY DEVELOPED AND FITTED
- HYSTERESIS MEMORY LOOP
- CONTROLLED EM INDUCTION
  - IMAGES
  - SENSATIONS
  - PREDETERMINED EMERGENCE
- 23 EEG BANDS
  - UP TO 8.1 X 10^{20} HZ
  - 11 INDEPENDENT CHANNELS

© 1978,1985,1991 T.E. BEARDEN

S.K. Lisitsyn, "New Approach to the Analysis of Electroencephalograms,"
DDC Report AD73005, p. 16-25.



Lorentz Closed Surface Integration

Selects only the locally divergent portion of the Poynting energy flow that powers the component.

Only the wind on my ship is of physical significance!

© 1997 T.E. Bearden



Lorentz Closed Surface Integration

Selects only the locally divergent portion of the Poynting energy flow that powers the component.

How can they use that old physically insignificant wind?!!

© T E BEARDEN 1998

Lorentz's physically insignificant energy flow can be collected and utilized.



Lorentz surface integration of the Poynting vector around a closed surface

See Panofsky & Phillips, Classical Electricity and Magnetism, 2nd, edn., Addison Wesley, 1962, p. 178-181.

1a. Lorentz surface integration.

1b. Actual S in and S out.

Note: If the S-vector is integrated over the closed surface, then all energy *transport* passage is zeroed, leaving only the very small component of the input S-flow that is powering the joule heating of the resistor. In short, only the small component of the S-flow that is equal in magnitude to the Slepian vector $j\phi$ remains. This measures only the tiny portion of the S-flow that is "collecting" on electrons passing through the resistor, and therefrom being dissipated out of the resistor as joule heating. It discards everything else (all S_{TR}'s and S_{OUT}). S_{IN} becomes S_R.

© 1997 T.E. BEARDEN



Longitudinal EM Photon Interaction with Charge

- Creates time-density wave pumping
- Slowly creates time-density charging

Transverse photon
CHARGED MASS
Excited Energy Density State
Time-density (scalar) photon
Longitudinal photon
Phase Conjugate Added by Charged mass
CHARGED MASS
Excited Time Density State
© 1990 T.E. Bearden

- Fundamental units are arbitrary in physics
- Can express all physics in one unit -- e.g., time
- Time is highly compressed energy
- 1 sec = 9 x 10_{16} joules of transverse EM wave energy

Figure 1-8. Infolded biwave composition of a scalar potential.



Mass is transparent to longitudinal EM waves, which move through the infolded interiors of internal waves, potentials, and fields in the mass

Mass is mostly ambient vacuum potential, modified by internal potentials, fields, and waves. Any wave or field is just two scalar potential functions, by Whittaker 1904.

MASS MEDIUM
Ambient Vacuum Potential
Static EM Field
EMWave
© T.E. BEARDEN 1997
Ambient Vacuum Potential
D.C. Potential



Pumping with Longitudinal EM Waves Time-reverses the Mass

vacuum (spacetime) engine in the mass is the input

longitudinal EM pump wave

CELL MASS

highly nonlinear to any and all LW frequencies

Antiengine acts upon mass at all levels

MASS previous state

AN AMPLIFIED VACUUM (SPACETIME) ANTIENGINE IS FORMED AND ACTS ON THE MASS, TIME-REVERSING IT AND ALL ITS COMPONENTS NO MATTER HOW SMALL

longitudinal EM pump wave

© T.E.BEARDEN 1997



Maxwell's Quaternion Theory

- Quaternions:
  - Discovered by Hamilton in 1843
  - A quaternion has a vector part
  - A quaternion has a scalar part
  - First significant non-arithmetic number system
  - Higher topology than vector or tensor algebra
- Maxwell's theory was in quaternion equations
  - 20 equations in 20 unknowns
  - Reduced to a small 4-equation subset by Heaviside and Gibbs
  - EM topology dramatically reduced

© T.E. BEARDEN 1995, 1996



Maxwellian Systems
Before regauging, after symmetrical regauging, and after asymmetrical regauging

Note: Any system must first break equilibrium in its vacuum exchange, before it can energize Drude electrons and "power" the load. Asymmetric regauging is always utilized. Powering loads and losses is a symmetry-restoring operation.

BEFORE REGAUGING

MAXWELL'S EQUATIONS BEFORE THEIR REGAUGING

OPEN SYSTEMS NOT IN THERMODYNAMIC EQUILIBRIUM

OPEN SYSTEMS IN THERMODYNAMIC EQUILIBRIUM

ASSUMED "CLOSED" SYSTEMS

SYSTEMS WHICH REGAUGE, FREELY CHANGE ENERGY, AND SHOW COP<1.0 BY DESIGN

SYSTEMS WHICH REGAUGE, FREELY CHANGE ENERGY, AND SHOW COP>1.0 BY DESIGN

SYSTEMS REGAUGE, CHANGE ENERGY, BUT USE HALF THE ENERGY TO DESTROY SOURCE DIPOLE

TRULY CLOSED SYSTEMS (NONE EXIST)

ASYMMETRICAL REGAUGING

SYMMETRICAL REGAUGING

© 1996, 1997 T.E BEARDEN

Selected clipart© by Lotus SmartPics™



Page 1 of 2.

Maxwell's four equations reduce to:

$$\nabla^2\Phi + \frac{1}{c}\frac{\partial}{\partial t}(\nabla \bullet A) = -4\pi\rho \qquad [1]$$

$$\nabla^2 A - \frac{1}{c^2}\frac{\partial^2 A}{\partial t^2} - \nabla\left(\nabla \bullet A + \frac{1}{c}\frac{\partial\Phi}{\partial t}\right) = -\frac{4p}{c}J \qquad [2]$$

A is replaced by A', where

$$A' = A + \nabla\Lambda \qquad [3]$$

The new B' field then becomes

$$B' = \nabla \times (A + \nabla\Lambda) = \nabla \times A + 0 = \nabla \times A = B \qquad [4]$$

A new E-field will also be formed. So let

$$\Phi' = \Phi - \frac{1}{c}\frac{\partial\Lambda}{\partial t} \qquad [5]$$

© T.E. BEARDEN 1997



Page 2 of 2.

Per Jackson, (A,Φ) are *habitually* chosen so that

$$\nabla \bullet A + \frac{1}{c}\frac{\partial \Phi}{\partial t} = 0 \qquad [6]$$

The *net symmetrical* regauging separates variables.

Two inhomogeneous wave equations result:

$$\nabla^2 \Phi - \frac{1}{c^2}\frac{\partial^2 \Phi}{\partial t^2} = -4\pi\rho \qquad [7]$$

$$\nabla^2 A - \frac{1}{c^2}\frac{\partial^2 A}{\partial t^2} = -\frac{4\pi}{c} J \qquad [8]$$

© T.E. BEARDEN 1997

Equations [1] and [2] *arbitrarily* changed to [7] and [8]

HUNTSVILLE EDITION

The Southeast's Oldest E-Zine!

CHASING THE WILD DRAGON

Foundations of a New Science

By T.E. Bearden
November 12, 1995

It is a pleasure to accept the offer of John and Larry to write a column in their new InterNet magazine. Theirs is a great venture, and with the energy and knowledge they bring to the task, one can be confident of their success in making this a very interesting and informative publication.

There is a new “rebel” science slowly being born, with most of the work being done outside the universities and orthodox scientific community. In the months ahead it will be my job to try to acquaint you with the gist of what’s going on, and what all the excitement is about.

This first article is deliberately just introductory, and its purpose is to interest you in the unusual fields we are going to be covering in more scientific detail, in future columns. We will also be listing a variety of references from the technical literature, which bear upon the various points addressed.

In this first article a little of my own background experience [note 1] is given, so you can decide whether you will be interested in what we have to say!

The real purpose of the column will just be to *present information* that you may not be able to readily obtain any other way. We will not argue or debate with skeptics; nothing productive is to be gained by that. If the information we present is useful to you, then our purpose has been accomplished. If it isn’t of use to you, then just file it in the old wastebasket. Also, from time to time I may answer a generic question, constructed from multiple queries. Individual responses to correspondence cannot be provided.

The work toward a new breakthrough science is going on in a broad spectrum of “fields,” most of which are not yet recognized by academia as even constituting legitimate areas of scientific endeavor (Table 1).
Some of the major areas involved are:

- theoretical and experimental research in overunity electrical machines,
- free energy research of other kinds, such as devices utilizing thermodynamics phase changes,
- rapidly advancing efforts in cold fusion,

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok

- direct engineering of quantum change via a new kind of "hidden electrodynamic variables,"
- the direct engineering of the vacuum's virtual photon flux exchange with matter,
- action at a distance, including the deliberate formation and usage of quantum potentials,
- direct engineering of the local curvature of spacetime (yes, the direct engineering of general relativity, using the new hidden kind of electrodynamics),
- use of the new "hidden" electromagnetics to engineer body cells including the reversal of diseased cells, genetics and all, back to a previous healthy state (cellular dedifferentiation, in biophysical terms, or cellular phase conjugation, in physics terminology),
- research toward the direct engineering of the mind, including both the conscious and unconscious minds, long-term memory, and the personality itself, and
- a ruthless re-examination (and correction where necessary and possible) of the definitions, concepts, and postulates that present physics is founded upon.

Each of these "major areas" as yet has no single "experts" in the sense that individuals exist who possess a "mastery" of the given area. As an example, in spite of multiple researchers and decades of vigorous research, no one is really an "overall expert" in the overunity electrical power systems field. The "field" itself is still struggling to be born and is not recognized at all by orthodoxy; in fact, many orthodox scientists bitterly resent one even attempting to work in this area. There is as yet no cohesive single "theory" of overunity electrical or magnetic machines, although our own group is making rapid progress in that respect. But there is still no universal agreement amongst even the researchers themselves. Literally the field is still being discovered.

This "groping dimly toward a new field" should not be too surprising. After all, the early electromagnetics researchers went through the same tortuous, agonizing kind of development. They were playing with cat fur, glass rods, and pith balls for quite an extended period before understanding progressed to the point where Maxwell could mathematically tie together and model the results of the experimenters such as Faraday and others. It has taken a century and a half for modern electromagnetics and electronics to reach its own present development. It is going to take another decade or so before the overunity researchers can overturn several ill-founded parts of the present electromagnetics and get the emerging field onto a solid foundations footing and into a solid theoretical position.

In the effort to produce a theoretical model of electromagnetics, Maxwell and his predecessors performed a magnificent work. Yet they also made very serious errors (Table 2), which persist to this day. [note 2] Let us list just a few of the more blatant errors in classical EM theory today:

First, Franklin guessed wrong on which way electrical current flowed in a circuit. There is no definition at all of electrical charge in all of physics, and there is no acceptable definition of potential (that is, there is no rigorous definition of just good old "voltage.") There are no "fields of force" in the vacuum; there are just potential gradients __ because the vacuum is just one vast potential (virtual particle flux) in the first place. Force fields actually occur only in and of the matter in a material system. The primary causative agents of electromagnetics are not the so-called "force fields' at all, but are the potentials __ as is well-known in quantum mechanics. [note 3] Maxwell assumed a material ether in his equations. The Michelson-Morley experiment destroyed the material ether, but the Maxwell equations have never been changed accordingly. The electron was not yet discovered when the Maxwell equations were written; the theory does not address electron spin. Maxwell was already dead some two decades when Barus' 1898 paper [note 4] was published, pointing out the strange "backwards-traveling" wave (i.e., time-reversed wave) solution to the wave equation. In addition, Heaviside and Gibbs had already produced their vector truncation __ this truncated theory is the modern so-called "Maxwell's equations" that universities teach today __ of Maxwell's theory.

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok

vector algebra, and seriously curtailed Maxwell’s theory when they “translated” it into the much lower topology of vectors and some four equations. The later addition of tensors as the basis mathematics did not restore the lost topology provided by the quaternion model. [note 6]

For the EM wave, Maxwell simply assumed the transverse EM wave that had come from the much earlier derivation of the familiar wave equation from the old “plucked taut string” notions. [note 7] Yet when one closely examines and corrects some of the erroneous *assumptions* [note 8] made for the actual mathematical derivation of this “taut string” transverse wave, one finds (Figure 1) that an equal-energy second antiphased transverse “antiwave” is actually produced by the instrument and added to the “plucked string’s” transverse wave disturbance of the air medium, to produce a longitudinal wave of compression and rarefaction in the air itself. The “transverse string wave” in fact never leaves the string. The string wave is not the wave that is launched into the medium.

A similar electromagnetic situation exists. In a whip antenna (Figure 2), the Drude electron gas in the conductor does exhibit a transverse “string-type” EM wave of electron precession. However, at the same time, by Newton’s third law (which Maxwell neglected because at the time the atom was regarded as just a blob with no internal structure) the positively charged, phase conjugated atomic nuclei have equal energy, highly damped transverse recoil waves created in them. Further, these “nuclei-recoil” waves are phase conjugate replicas of the electron gas waves. The total disturbance that is launched into the vacuum from the whip antenna is (a) the normal transverse disturbance of the virtual photon flux of vacuum caused by the electron gas wave, and (b) the coupled equal-energy transverse antiwave caused by the nuclei-recoil via Newton’s third law. The amplitude of the material antiwaves of nuclei vibration are highly damped because of the massiveness of the nuclei; however, they are of equal energy to the electron wave. But when launched into the same vacuum, the two equal-energy wave disturbances experience equal damping because they are in the same medium. Hence the wave and antiwave are (a) locked together in the vacuum, and (b) of equal energy, and (3) of equal amplitude once launched into the vacuum. What results is a vacuum EM wave of rarefaction (reduction in intensity) and compression (increase in intensity) of the virtual photon flux of vacuum __ just exactly like what is launched into the surrounding gaseous air medium from the “plucked taut string” and perturbed body of a physical instrument. The EM wave in vacuum is a longitudinal wave directly analogous to a sound wave __ just as Nikola Tesla stated. [note 9]

The vacuum may be considered a scalar potential, in which case it has an internal biwave structure (Figure 3). Interference of two potentials __ i.e., the hidden interference (Figure 4) of their internal wave structures __ in fact already creates all EM fields and waves.

When the incoming longitudinal “biwave” from the vacuum strikes the atoms of the receiving antenna, each atom may be considered a dynamic assembly of multiple dipoles, where each dipole consists of one of the electrons in the electron shells and one of the positive charges in the nucleus. The receiving dipole in the interacting atom splits the two waves apart again (Figure 5). The negatively charged end of the dipole is time-forward, and the positively charged end is time-reversed. Hence the separated normal-wave-half of the biwave interacts with the electron, to give again the familiar transverse “electron precession” wave that we detect with our “electron wiggle-detecting” instruments (Figure 6). This detected electron precession wave is what all our textbooks prescribe erroneously as the vacuum wave! The separated time-reversed-wave-half of the incoming vacuum wave is split off and interacts with the positive end of the receiving atomic dipole, in the time-reversed atomic nucleus, thus generating Newton’s third law reaction force to provide the recoil of the nucleus. Present physics has ignored this second wave altogether, because of the serious error in the original derivation of the wave equation from plucked strings. Thus

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok

would appear to violate Newtonian third law reaction. Phase conjugate mirrors already do just exactly this when they emit a phase conjugate replica wave. They direct the antiwave outside and away from the atom instead of inwards into the nucleus. So they do not recoil, no matter how powerful a phase conjugate replica wave they emit.

Finally, we can also show that the EM wave in vacuum is longitudinal, by yet another approach. The electrons in the electron gas in a conductor are spinning, and they are severely constrained longitudinally to be able to move only very, very slowly down the wire. So when perturbed, they act as gyroscopes, and precess at right angles to the perturbing force. The fact that the gyroelectrons in a wire move radially almost entirely, and only “slip” down the wire very slowly with a “drift” velocity, already proves conclusively that the incoming vacuum disturbance was longitudinal. The precession of a gyro is at right angles to the perturbing force. Therefore rigorously the vacuum EM waves are longitudinal, because the gyroelectrons moved transversely. The present assumption of the transverse EM wave in vacuum contradicts the entire theory of gyroscopes! [note 10] There are many other errors in classical EM that we will point out in future articles; this should give the reader a flavor of what is in store for him in future articles.

So there are no truly satisfactory “experts” in any of the 14 fields. Yet there is still something to be said for having some years of experience in one or more of the areas. I have had the good fortune or misfortune, depending upon one’s viewpoint, to be involved in various of those 14 activities for some 30 years or more, and am active in several of the areas now. My colleagues and I are particularly active in researching overunity electrical devices (see Figure 8), to include the effects of controlled chaotic oscillators, charge-blocking oscillators, and oscillators driven by in-shuttled (bridged) Poynting field energy density flow ExH. Parametric oscillation is known to have yielded overunity electrical machines and was fully reported by Russian researchers in the Russian and French technical journals in the mid 1930s. [note 11] We will further cite that little-known work in future articles. Also, we are working mightily upon true negative resistors (Figure 9), wherein the resistor scavenges some of the disorganized energy from the vacuum’s energetic exchange with the charges in the system, organizes and collects it, and then outputs that collected energy flow into the external circuit. Such a resistor acts as a power source. Kron, perhaps the greatest of the electrical machinery scientists, is known to have produced such true negative resistors.

I have also proposed a theoretical explanation of the Priore device (Figure 10) in France which in laboratory animals demonstrated remarkable cures of terminal tumors, cured trypanosomias, reversed atheriosclerosis, and restored suppressed immune systems. The Priore work was not anecdotal, but was performed under rigorous scientific protocols, working under the auspices of renowned French scientists such as Courrier and Pautrizel. The work is properly reported in numerous papers in the French medical literature. [note 12] The results were certainly achieved, but neither Priore himself nor the scientists of the day could understand the mechanism involved. The deciphering of that causative technical mechanism utilized by the Priore group required 10 years of intense effort. The results have now been published in the journal Explore! and are there for anyone to read. [note 13]
Presently my CTEC colleagues and I have filed three patent applications and a continuation, on various methods for overunity processes and apparatuses, room temperature superconductivity, Poynting generators, etc.

As an example, we took exactly the opposite approach to room temperature superconductivity as has been taken by all the orthodox researchers to date. What exactly is sought, after all, for superconductivity (SC) in a section of an electrical circuit? Well, one has some electrons on one side of that SC section that are transporting excess potential, as given by the Slepian vector J*. [note 14] What is desired is to get some electrons on the other side of the SC section that also are transporting the same amount of excess energy in the form of J*. You can do that in two ways: (1) you can flow the electron carriers through the SC section, carrying their J*, or (2) you can block the J and flow the * itself across as the Poynting flow S. [note 15] Nondivergent Poynting flow flows along an equipotential, which is

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok

fanblades to a crawl) and massive correlation of the electrons and of the electron-to-lattice interactions is necessary if one is to get the electrons through there without excess collisions that shake off some of the excess * from J*, as scattered photons (heat) or as a change of form of the energy (as in straining the dielectric of a capacitor to convert electrical energy to mechanical strain energy via the piezoelectric effect.)

Our approach is exactly the opposite (Figure 11) and Figure 12). Why not just *stop* the flow of excited electron carriers on one side of the SC section, and continue the nondiverging flow of the Poynting field energy density S across that section at room temperature? Then the cryogenics is not needed at all. After all, circuits already work that way anyhow __ except standard practice is to nullify the process by letting current be driven around the sourcing current loop and back through the back EMF of the primary source. A quantum well (or several other methods) can be used to trap the "sourcing" electrons in the conductor just prior to entering the SC section. The "receiving" electrons on the other side of the SC section, however, must be in their own dq/dt-isolated current loop.

Normal sources do not furnish electrons and current to a circuit anyway. Sources just furnish Poynting flow S and EMF. [note 16] In the receiving current loop, the EMF appears automatically once the S-flow flows in and is "locked on to" by the receiving electrons. Given q**, you will immediately have J* if the electrons are free to move in the conducting circuit (see Figure 13). Further, you have eliminated all the loss terms from the standard Poynting equation for energy losses. So all the energy flow S just flows across the SC section, without any current or Cooper pairs flowing through that SC section. The SC section has become a "bridge" which (1) strips off the Poynting field energy density flow S from the electron current dq/dt on the sourcing side of the SC/bridge section, by simply reducing the dq/dt to zero; and (2) continues to pass the S-flow across the dq/dt-blocked SC/bridge section to the other side (Figure 14). The excess S-flow (and EMF) pours into the receiving dq/dt-isolated current loop, exciting the electrons therein to produce dq/dt and J*. *Any closed current loop is self-powered, once it receives S and EMF. It furnishes its own electrons; it only requires excess energy and EMF.* [note 17]

So our approach gives room temperature superconductivity in a very straightforward manner, once you discover how to block the current dq/dt in a conductor. Blocking it in an insulator is not sufficient, because that drops the potential and stops the S-flow and the equipotential * (the EMF). However, a degenerate semiconductor such as the Fogal chip can be used, as can several other processes for blocking dq/dt in a conductor. We will discuss these in a future article.

Another advantage of this approach to room temperature superconductivity is that now one can also have permissible overunity coefficient of performance. Now the load can be placed in its own S-receiving, isolated current loop. With the sourcing current loop furnishing only S and not dq/dt, the load is still powered normally in its own closed dq/dt current loop, but none of the load current is passed back through the back EMF of the primary source in the sourcing circuit.

This principle — that at least a substantial portion of the load current must not pass back through the primary source — is the primary principle required for a permissible overunity electrical machine (Figure 15). A permissible overunity electrical machine is one which produces more power in the load than you have to put into the machine to run it.

Obviously, the laws of physics and thermodynamics require such an overunity machine to be an open system that extracts and utilizes excess energy from an external source. In the case outlined, we extract the excess energy directly from the vacuum in the form of S-flow; essentially we convert our primary source to a Poynting generator rather than a "power" (energy flow loss rate) generator. The resulting9. overunity machine accomplishes both room temperature superconductivity and also overunity coefficient of performance (Figure 16). It does not violate the

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok

a dipolar source, as in the simple two-wire circuit, all we are doing with the conductors is providing waveguides for the extracted S-flows from the vacuum to flow along (it flows outside the conductors) without loss. In effect, each lead is simply extending the pole (i.e., the terminal) to which it is connected.

My associates and I are also working on several other inventions at present, including two more patent applications to be filed in the near future. One of those is in the field of overunity power systems, while the other is in an entirely different, highly proprietary nuclear effort. I will address all these areas in future columns, and those columns will have real “meat” in them.

Present “big science” proclaims that overunity electrical machines are impossible. The reader should understand that the U.S. Patent and Trademarks Office is never going to grant a patent for an overunity electrical machine unless the machine is independently tested and replicated, and unless it is certified by scientists of impeccable credentials. This is as it should be. Legitimate free energy researchers accept that dictum. Eventually the stuff has to work on the bench in order to be validated. On the other hand, free energy researchers also point out that one must not demand of us the next 100 years of national research by a hundred major laboratories immediately! This is still a shoestring operation, because all conventional sources of research funds are denied to the serious overunity researcher (with the single exception of occasional personal funding of a researcher by a private individual). In other words, we demand at least the same kind of consideration that the orthodox nuclear fusion community has enjoyed. Billions of dollars have been poured into that sinkhole, and not a single controlled fusion power unit is working anywhere in the world after decades of work at enormous expense to the taxpayers.

So we overunity researchers deserve at least a decade or two of our own, to try to accomplish overunity electrical system development. We also painfully point out that “Big Science” will not fund a single overunity researcher, for specific overunity purpose, no matter what his credentials or capability. In fact, “Big Science” is part of the problem, because it fervently seeks to prevent any legitimate research in overunity. To carry out its suppression campaign. it resorts to vilification, character assassination, libel, and slander of the overunity researchers themselves __ again, regardless of their qualifications or legitimate scientific procedures. [note 21]

Indeed, orthodoxy has a black record with respect to energy. When Mayer advanced the conservation of energy law, orthodoxy hounded him unmercifully. He was universally ridiculed as the very epitome of a fool. He lost his job and suffered a nervous breakdown. Then years later toward the end of his life, scientists came to accept the conservation of energy as a most useful tool that dramatically simplified much of their analyses. So then science began to laud Mayer. There are a thousand other such examples; suffice it to say that “big science” is a bureaucracy and a “bell-shaped distribution curve” just like any other large group of people. Some scientists are near-angels. Others are near-devils. The vast majority are neither, but are just ordinary persons doing a special kind of job. In the scientific bureaucracy, however, the manipulative scientists scurry, slash, and manipulate their way toward the top. So the leadership of any big bureaucracy __ including the scientific bureaucracy __ is always rife with such near-scalawags and power-hungry individuals. Scientists are not exceptions to the same human weaknesses that we all evidence. If you really want to see jealousy, backbiting, and fierce “back-room dealing” and power-struggling, just get into a university research environment! But because the “power merchants” of any bureaucracy always fiercely resist any challenge to their position or superiority, big science has always fiercely resisted anything truly revolutionary. And today they also enlist the power of the state to enforce their dictums. We will devote one of our future columns to pointing out some glaring examples of persecution of independent researchers by big science. It is an area that all unorthodox researchers should be well-aware of. The world of science does not run by sweet reason and lofty

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok

to the U.S. Patent and Trademarks Office. Anyone with a modicum of knowledge of modern physics already knows that there does not exist a single closed system in the universe, anywhere. In particular, every physical system is continuously “open” to the violent exchange of energy with the surrounding vacuum. It’s just that most systems are in local equilibrium in these flow exchanges, except for minuscule gating accomplished for such things as the Lamb shift, etc.

By analogy it’s something like this. The free energy researcher is standing by the banks of a mighty, rushing river with breathtaking falls, turbulent areas, etc. Big Science is begrudgingly admitting that, yes, there is a river there, but it is an insane delusion to think that you can tap that energy. The free energy researcher is saying that, well, if I can build a gating sluice a little distance upstream, perhaps I can divert a small portion of the river’s flow downstream to my waterwheel, and power my mill. The orthodox scientist then vilifies the free energy researcher for even having such a heretical thought. In fact, says the orthodox researcher, any fool can see that the laws of nature force the river’s flow to stay firmly in its banks, because it is a closed system, and Moses brought that law down off the mountain with him on a special stone tablet. Then he adds all the other smug remarks such as, “If it could be done, then we at MIT and Harvard and Caltech would already have done it!” So until the orthodox scientist develops a little less dogma and a little more common sense, and learns the difference between a scientific discussion and a dogfight, the free energy researcher can hardly communicate with him.

The goal of the legitimate free energy researcher is to find a way to break the local equilibrium of this universal energy exchange, and gate a tiny bit of it up into the external circuit as excess electrical energy (Figure 17). Then he must collect the excess energy, and shuttle it from the “gating and collecting circuit” over to a dq/dt-closed current loop containing the load. He must also prevent the load current, or most of it, from passing back through the primary source against its back EMF, because if it does that, he will destroy the separation of charges in the dipolar source, killing the dipole and extinguishing the “excess energy gating.” In other words he must find a way to process and transport the energy flow across dq/dt-blocked bridges between the source’s closed dq/dt-current loop and the load’s closed dq/dt-current loop. Ruthlessly it is an energy transport S-flow problem, not a J* energy transport problem. If he uses J* in his sourcing current loop, he automatically drives the current dq/dt back through the back EMF of his source and kills it. If he does not drive dq/dt back through the source, the source will furnish S-flow for an indefinite period! Every battery and generator we have ever built is already a “free energy” machine in that it already involves broken local symmetry in the vacuum energy exchange. We have just not realized how to use our power sources purely as Poynting S-flow sources.

So we must treat an electrical system as an open system with broken local symmetry (Table 3) in the vacuum flux exchange, so that the system extracts (gates) excess energy from an external source. In this case the source is the system’s flux exchange with the vacuum. This approach is no more mysterious or bizarre than putting a waterwheel in a river, or a windmill in a wind, or a bank of solar cells out in the sunshine. The universal “free source of energy” that the overunity researcher seeks to tap is the violent exchange of virtual photons between the electrical charges of the system and the surrounding quantum mechanical vacuum (Figure 18). In quantum physics this powerful, energetic exchange of the vacuum with electrical matter is now proven both experimentally and theoretically. It is already accepted in quantum physics that the vacuum is filled with electromagnetic energy. The researcher doesn’t have to prove it anymore; he just has to find out how to properly use it. The artesian well is already there; we just have to learn how to collect and use the flowing water without dynamiting the well!

The remaining objection orthodox scientists usually raise against the notion of extracting vacuum energy has been

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok

physicists have made various theoretical estimates of the energy density of this seething vacuum. A conservative ballpark figure is something on the order of 1090 grams per cubic centimeter, expressed in mass units.

It has also been my good fortune to know and work closely with several other free energy researchers. I was a colleague of Floyd ("Sparky") Sweet (recently deceased) for about seven years; Sparky held a Master's degree in EE from MIT and had years of experience with General Electric and other firms. He was a highly skilled researcher who invented the solid state vacuum triode amplifier (Figure 19), a unit which produced 500 watts of output and a coefficient of performance of 1,500,000. I personally tested the machine, activated the magnets on one occasion, and understand how it all worked. [note 24] The paper [note 25] I co-authored in 1991 with Floyd is still the only paper in the orthodox engineering literature that reports (a) successful overunity functioning of a solid state magnetic device, and (b) a successful antigravity experiment on the laboratory bench, reducing the weight of an object by 90%. [note 26]

We stress again that a legitimate overunity electrical machine must be an open system, receiving excess electrical energy from the surrounding vacuum. As such, it must operate in a higher topology than normal electrical machines (Figure 20).

My good friend Frank Golden has long been a close colleague. Years ago Frank developed a motor that produced overunity efficiency, but then to our astonishment we found (courtesy of Bill Tiller, [note 27] with whom we were working at the time) that its operation depended upon a 5-year-long conditioning (structuring) of the local ambient potential in order to work. Previously we had been entirely unaware that one can sometimes condition the local vacuum and the local matter in the area with a particular dynamic form. Given the local conditioning, a motor with that form will then work in that vicinity, but not necessarily elsewhere at an appreciable distance away. We now understand the mechanism for such "conditioning of the vacuum." We also now know what to do if an overunity machine is actually a machine of that type (many of them are not). In other words, we know how to convert it to a machine that will work anywhere, anytime. We will be addressing such little-known things in future articles.

John Bedini is also a close friend and colleague; John built several experimental motors (both electrical and magnetic) in the overunity area, and performed successful trans-mutation experiments. John is a recognized genius in high-end sound amplifier development. Many audiophiles worldwide still swear that the Bedini amplifier is the best and sweetest-sounding audio amplifier ever built. One of John's battery-powered electrical motors (Figure 21), for example, ran continuously off its battery for about five years, and kept the battery charged. When you realize that such a small electric motor is only about 35% efficient, then you realize that about 65% of the energy flowing out of the battery was being dissipated in the motor as heat, core losses, etc. So the unit was continuously performing work for that five years. [note 28] The 1/8 hp motor represented a load in which the continuous rate of work being done (the rate of energy dissipation) was about 0.08 hp. We will have more to say on this motor and its technical process in a future article.

Bill Fogal is a close colleague; Bill has patented the world's first dq/dt-blocking semiconductor, [note 29] which partially blocks the normal current while continuing to pass the flow of voltage (Table 4). I have written a proprietary technical explanation of the Fogal semiconductor, which utilizes an extremely little-known feature called the "overpotential." The overpotential part of the theory is experimentally proven and theoretically explained in an obscure part of electrochemistry, by a few chemists who specialize in electrode effects. J. O'M. Bockris is probably the leading world expert in overpotential theory; he authored the textbook on it. [note 30]

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok

because we did not have the proper instruments available. E.g., all our oscilloscopes were "hard grounded" to building ground, and we needed to make “floating differential ground” measurements in order to settle things once and for all. McLain and Wooten have filed for a patent, and multiple tests with excellent equipment have indeed indicated overunity. What happens next remains to be seen. I suspect that the two inventors may simply accept foreign capital investment and go offshore.

Howard Johnson is also a respected colleague, whom I very much admire. (See Figure 23). Howard has continued to work quietly and patiently upon his patented permanent magnet motor, [note 31] including patenting various magnetic gates, etc. that are necessary to make such a motor work in a rotary configuration. [note 32] Howard employs a two-particle theory of magnetism; i.e., each magnetic flux line is envisioned as having a particle traveling from the north pole to the south pole, and also a particle traveling from the south pole to the north pole. The particles are spinning; the forward-time particle spins in one direction, and the antiparticle spins in the other direction. Howard then slightly separates the two particle flows. [note 33] In other words, Johnson splits the flux lines themselves, into two different pieces. When so separated, the component lines are now curls, so their paths curve. The paths of the two “curl particles” are different; one curls in one direction and the other curls in the opposite direction. Further, a predominance of one form of curl particle gives a “time-forward” aspect, while a predominance of the other form of curl particle gives a “time-reversed” aspect. Johnson is thus able to employ a deeper kind of magnetism than the textbooks presently contain. He demonstrates that a “spin-altered” magnetic assembly exhibiting (to a compass or other such detector) a north polarity can attract another unaltered magnetic assembly exhibiting a north polarity. In short, he can make a north pole attract a north pole. We will give you further insight into Johnson’s two-particle theory in a future article. [note 34] We will also explain how and why the physicists missed that antiparticle in the magnetic field’s flux lines, and thereby failed to advance the theory of magnetism to a deeper level. Make no mistake, one day when the new theory is done, Johnson may well be awarded a Nobel Prize for his epochal discovery of a deeper structure of magnetism.

Bits and pieces of the new science approach are just now beginning to spill into a few conventional journals and symposia. For some time a few of the rebels spearheading this new science have been doing something that the University scientists should have been doing all along. The rebels have been meticulously examining the concepts, postulates, and definitions that the present scientific models are founded upon, to reveal serious foundations errors. Corrections for some of these errors have been discovered and made. [note 35] Others are still problems yet to be resolved. Yet slow progress is being made, and a “flip-over” of the old science is likely to occur within the next decade if not sooner. By then the new concepts will have become “solid” enough to allow producing an engineering mathematical model. Also the supporting experiments will have become solid enough to justify the new concepts and the model.

In this first article I wanted to introduce the 14 major areas. We will be discussing these areas in some technical detail in the future. We’ll also include current major news items of development in these areas, for the interested lay reader. I’ll particularly try to give you the benefit of extensive reference citations painfully gathered over the last 30 years. The articles will be targeted toward both the serious researcher and the interested, educated layman.

So that’s the agenda for the months ahead. We hope you find this information and the approach of direct interest and use.

Again, it’s a privilege to be aboard. And we invite you to hang on in the future; it’s going to be a wild but exciting ride. We really are going to chase this wild dragon with great vigor.

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok

The Virtual Times, Huntsville Edition

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok

Contact Weather Health Writers

Scalar Wave Technology



Scalar Wave Detection

Warren York

Scalar Wave Researcher

Originally published: **ExtraOrdinary Science (Volume 1, Issue 4; Oct/Nov/Dec 1989)**

WARNING: Do not attempt electrical construction on any of the equipment, coils or devices described here unless you are fully qualified. In some cases LETHAL voltages and charges are required. Also be advised that improper use, application and physical methods may cause psychological tramuma or permanent physical and neurological damage when near the vicinity of such equipment. This information is being provided as a point of interest to our readers... the publisher and author disclaim any responsibility in the use or misuse of this information.

Introduction

All of this talk so far on scalar waves and scalar technology has no purpose in the scientific community until something can be detected, observed and duplicated. The original seedlings and thoughts which led to Lt. Col. Bearden's scalar theories were developed out of observation. If not by Lt. Col. Bearden himself, then by others from many noncorrelated paths.

I already have given a small sample list of such observers from Nikola Tesla to the latest, Moray King. I have just read a newly released book by Moray entitled ***Tapping the Zero Point Energy***. I also recommend highly for others interested in scalar technology to obtain copies of Bearden's works and books from the new release of ***Excalibur Briefings*** to ***AIDS--Biological Warfare***. The two books and papers will fill in the much needed base work on understanding scalar technology and can be obtained through the High Energy Catalog.

I also understand that a new book is in the making which is a rebuttal entitled something along the lines of *Anti-Scalar*. All of this is healthy in any development process, for without pros and cons, the sorting of correct data to trash data cannot be accomplished. On the other hand, I would like to point out that any conclusions should be supported by actual tests and not just by armchair theory.

Anybody can debate from the armchair but to have any meaning to back up their statements, one must present tests where one gets his or her hands dirty. That is to say that until I had reactions and observed actual phenomena occurring, all the theories were no more than that--just theories. This is what I hope to accomplish here with these articles on scalar technology. I feel this is a true new technology and deserves some serious consideration.

If I had not gotten my hands dirty and followed through on others' experiments from other observers then I would never have been convinced that something extraordinary was taking place. Even though my senses told me I was wasting my time I set out on the monotonous task of duplicating others's work and notes of observation. This is what I hope some of you will do and start to help unfold and unleash this hidden knowledge called scalar -- zero point energy -- stress energy and even radionics. Itis true indeed that it has many names over the years, but now we can at least have hope of defining its true limits and abilities.

The detection methods I will present here are not confirmed by myself or corresponding researchers as of yet due to development is still in progress. In one method I can only accept the word of the researcher as to his results. Until I or others duplicate results it remains a possible process and approach in detection.

My own detection came in the form of two experiments which were reproductions of another author's work based on this technology. When I had reproducible results I knew there was more to scalar than just theory. The process is now underway in developing a reliable instrument or means of detection that others can use. Up to this point most of scalar observations have been uncertain and always with the person or operator being part of the circuit. Nobody could remove the person at this point to bring scalar under true observation conditions. Due to a simple observation in Mr. George Meek's work in electro-voice phenomena (EVP), where my first breakthrough was established, this now seems a possibility. The personal element was still included in the circuit but unlike radionics or Hieronymus devices, could be reproduced by anybody once special conditions were met. A co-researcher has hit upon a method which was initially observed by Nikola Tesla and shows promise of another breakthrough in removing the personal element.

I will now discuss my initial breakthrough to scalar detection which will help you follow my thinking on what is needed and just what we are looking for in scalar detection. Scalar properties are the dictating key elements in this approach. I will then describe a possible detection method of another researcher and finally what I feel will be a unique approach with an instrument currently under construction by Mr. Russell Clift, a co-researcher/inventor, and myself. Do not feel you have to adhere to these techniques for they are only a guideline and starting point to spring from in your own approach to this subject. They are not established yet and will most likely be altered many times before their completion.



Figure 1. **System Layout for FM-TFD [Mode 1]**

As in all unknowns there are always unforeseen dangers involved and one should always use extreme caution and behave professionally in all approaches with any experimenting. Madame Curi and the XRay research is a good example. They paid dearly for their progress in X-Ray development with their lives. Scalar and its properties can be just as deadly as it is fascinating. I hope you read the seriousness in my tone for no matter how science fictionish scalar may sound to you now, I assure you the reality of actuallity can end up staring you in the face.

Breakthrough Event

Several years ago a Mr. George Meek presented me with construction planes and notes to a device he called Mark V. [Figure 1] Mr. Meek had been researching a phenomenon better known as EVP, or electro-voice phenomena. [Figure 2]


CONSTRUCTION TECHNIQUES
FOR -FM-TFD- & -HOOP ANTENNA-
PL-259
mini-spiral
antenna
#12 AWG
COPPER
WIRE
on
FM-TFD
off
SWITCH
external
modulation
input
subminiture
jack
1/2" black
plastic
pipe
HOOP ANTENNA
32"
#12 AWG
copper
wire
inside
SOLDER
ALL
CONNECTIONS
two lug
screw type
terminal
epoxy
epoxy
plastic box
with cover
SO-239
start
loop
#1
terminal
epoxy
epoxy
end loop #1
start loop #2
end
loop
#2
epoxy
epoxy
.001
.001 uf capacitor
lug
SO-239

Figure 2.

Figure 2. **Construction Techniques for FM TFD & Hoop Antenna**

I would like to take a second here and answer a letter from one of **Extraordinary Science**'s subscribers printed in our last issue. Mr. Jeff King from New Zealand had written to the effect if perhaps I could cover what relationship scalar technology has in reference to EVP. [Figure 3] Well here it is, for this was the first reproducible effect dealing with scalar energy [interference pattems] [Figure 4] that I could verify really took place. My second breakthrough was also in the EVP area but I will not be able to go into it at this time due to available space to cover what must be covered now.

In short, Mr. Meek claimed to have a fantastic breakthrough of his own in the communications field of EVP. His claims were a recorded two-way conversation with another dimension. ***ZAP!*** Right here one would stop and feel that Mr. Meek and his researchers needed psychological help as I am sure some of you feel about me at this point. I contacted Mr. Meek and he flew down to El Paso so we could talk in person. He brought me two audio tapes of which one surely did have what appeared two-way communication in real time.

Up to this point all EVP claims were after the fact type of events. That is, the voices always appeared on blank tape after the operator had run the tape recorder for a period of time. No audible sounds were heard during the initial recording, only after playback of the tape--sort of the same thing being done now with channeling, but the person is still part of the circuit. Not all voices were understandable or clear enough to be real voice prints or just random white noise perhaps forming what almost sounds like words. In other cases, the words and even statements were definitely clear and of intelligent source. Well, Mr. Meek's tape went way beyond this to a two-way real time conversation.


microphone
microphone
TAPE RECORDER
Session Copy
Hoop ANTENNA
circular folded dipole - velocity corrected
#12 AWG
FM pickup ANTENN
300Ω wire
on floor
FM-TFD
modulation
tones
acoustic feedback
audible voice
voice box resonance
mini spiral #12 AWG
XMT appx. 91 MHZ Carrier
Transceiver Feedback Device
Condenser microphone
Speaker #1
Tone Source
TAPE PLAYER
vol
tune
FM RECEIVER
tune to appx. 91 MHZ
SPEAKER #2
Enclosure 2
tones retraced thru speaker enclosures
Source - via tone tape
SPEAKER #2
Enclosure 1

Figure 3. **Mode 2 Communications Setup**

Fascinated by these claims I wanted to know more on how such a process worked. This is where he presented me with the second tape. It consisted of thirteen mixed electronic tones. No, there is no magical number in why thirteen tones were used only that they were needed to create interference patterns. These tones with an acoustical feedback and RF transmission with a Smith coil produced a unique interference pattern [scalar-RF and acoustical stress field].

I followed the notes and set out to reproduce this fantastic claim. At one point in the notes was one observation statement:

The system seems capable of feeding back changes in emotional states.


microphone
microphone
electro-magnetic feedback
TAPE RECORDER
Session Copy
HOOP ANTENNA
circular folded dipole - velocity corrected
#12 AWG
FM-TFD
.modulation
tones
acoustic feedback
audible voice
voice box resonance
Mini Spiral
#12 AWG
XMT appr.
91 MHZ
Carrier
Transceiver
Feedback
Device
Human
Field
Spirit
Field
FM/pickup ANTENNA
300Ω wire
on floor
Condenser microphone
electro-acoustic feedback
Speaker #1
Tone Source
TAPE PLAYER
Vol
tune
FM RECEIVER
tune to appr.
91 MHZ
EAKER #2
closure 2 ·
tones retraced thru speaker enclosures
Source - via tone tape
SPEAKER #2
Enclosure 1
WALL

Figure 4. **Mode 2 Communications Interference Pattern**

I stopped there and to my amazement found the observation to be true. I was able to control an avalanche effect in a balanced tone of a set of acoustical and RF frequencies with only my own concentration -- no doppler effect or movement or contacts to my body in any way. I taped this effect and it is available to those who wish to observe the level of control of an electrical circuit with shear stress energy from a human.

This observation is equal to Nikola Tesla's observation of his plasma globe and tensing a fist. He found the plasma trail would rotate in relation with the tension or muscle pressure produced. I will cover this process in a moment for the plasma approach in construction a scalar indicator seems to be ideal due to its extreme sensitivity that up until now has been the human or personal element.

Bedini Version ---- Dea/Faretto Scalar Detector

In this version of an electromagnetic scalar detector you will see that a coil is suspended in a magnetic field within a shielded case. [Figure 5] It is not indicated but I am sure the coil should be wound as a scalar coil. See "Construction of a Scalar Coil," **ExtraOrdinary Science**, Vol.I, Issue 3, page 16. The shielding is so all that known EMF fields will be run to ground and not affect the sensor within the case. As you know, one of the properties of scalar energy is that it cannot be shielded. All known EMF will be stopped from entering the case except gravity fields and scalar energy.

I am not saying that gravity fields or scalar fields are EMF, but only that the formula to each have a basic root in the EMF part of the spectrum. A generated scalar pulse or field will cut past the case shielding and affect the atoms of the scalar coil within the magnetic field which in turn will be coupled to the op amp. Any change or effect will then be displayed on the scope indicating a pulse or field of some kind has gotten past the system's shielding and to the sensor. You should see a change in the display around 6AM when the sun comes up and there is a slight gravity shift. [1,2]


FARADAY CAGE
Bedini Version—
Dea/Faretto Scalar Detector
RESONANT TUNING CIRCUIT
C
REMOTE
TUNING
OSCILLOSCOPE
MAGNET
PREAMP
SHIELDED
CABLE
NOTE:
Magnet>40,000 Gauss
CURVED SPACETIME

Figure 5. **Bedini Version of Dea/Faretto Detector**

Plasma Scalar Detector

This is the method which is under construction by Russell Clift and myself. At the time of this printing the construction is not far enough to give any details or results as to this approach. [See Figure 6] This is based on the same construction of Nikola Tesla's experiment.[3] Figure 7 is for experiments with various voltages and ion currents. Figure 8 is a simple multiplier for the AC supply shown in Figure 6.


Plasma Scalar Detector
GLASS SPHERE
LOW PRESSURE Hg VAPOR
LOW PRESSURE GAS
SUCH AS Ne. Ar. Xe. ECT.
FILLAMENT TO HEAT Hg AND
CONDUCT HIGH VOLTAGE
T3
2A
117V PRI
5.3V SEC
T2
SEE BELOW
A
B
R2 1K
C2
100uF
C3
1.0uF
Q2
2N3055
D2
1N914
Q1
2N3055
R1
10K POT
D1
200V PIV
C1
470uF
T1
AC IN
117V
2A
117V PRI
12.6V SEC
T3
B/W TV FLYBACK
H.V.
OUT
A
B
DRAWN BY: LOUIS A. VIDAL
Title
SCALAR WAVE DETECTOR
Size
D
Document Number
W.Y. 1
REV
AA
Date: November 7, 1999 Sheet 1 of

Figure 6. Plasma Scalar Detector


C1
.2uF
R1
1.0K
D1
LED
1
2
3
4
8
7
6
5
C2
100uF
IN OUT
T1
Transformer
D3
LM4001

Figure 7. Power Supply



All capacitors are .0047 uF 3KV
All diodes are 1K PIV

Figure 8. **Voltage Multiplier**

I know I have just touched upon this subject so far but I hope I have given some of you starting points in your own research and findings. I will welcome any and all papers or works you may do in the scalar field and submit your work for publication here for others to read and gain from. Will be looking forward to your replies in the new year. Thank you for your interest.___***WRY***

References

1. Michael Polonyi, "Electrodynamics, Inertia and Gravitation: A Unifying Approach," **Speculations in Science and Technology**, Vol. 10, No. 2, page 145, 1987.

2. Gregory Hodowanec, "Gravitational Impulses," **Electronics Experimenters Handbook**, January 1989, page 114.

Thomas Cummerford Martin, **Inventions. Researches and Writings of Nikola Tesla**, page 226 to page 228.

HUNTSVILLE EDITION

The Southeast's Oldest E-Zine!

Chasing the Wild Dragon Tables and Figures

By Tom Bearden

Figures


String slaps
air medium
WAVE IN STRING (TRANSVERSE)
Higher
degree of
freedom for
air medium
oscillation;
wave is
alternately
compressive
and rarefactive.
ANTIWAVE IN HOLDER
(Highly damped; not shown
to scale)
Body slaps
air medium

Figure 1. Air medium disturbances generated by plucked string.

Two waves are created, both slapping the air medium at the same time, but in opposite directions. A disturbed medium oscillates according to its own degrees of freedom. The air has more degrees of freedom than the string. A wave of compression and rarefaction is created in the air medium.

D-1-F 1

© 1993 T.E. Bearden

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok


ANTENNA
ELECTRON SHELLS
(DAMPED)
NUCLEI
(HIGHLY DAMPED)
VACUUM
(UNDAMPED)
(UNDAMPED)

All EM and mechanical forces are due to virtual photon absorption and emission. The electron gas "slap" and the nuclei gas "slap" of the vacuum medium are equal in energy. Hence they inject equal numbers of virtual photons into the vacuum, creating equal and opposite vacuum disturbances. This gives a vacuum wave of alternating compression and rarefaction. This vacuum EM wave is similar to a sound wave, which is modeled longitudinally.

Figure 2. Launching an EM wave from a wire antenna.

D-1-F2

© T.E. BEARDEN 1994, 1995

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok



Figure 3. Internal Wave Structure of the scalar potential.

A harmonic set if wavepairs, where in each wavepair the two waves superpose spatially, but travel in opposite directions. The two waves in each pair are true phase conjugates and time-reversals of each other. Thus they comprise a coupled wave and antiwave. The photons must also be coupled into photon/antiphoton pairs, by a strong application of the distortion correction theorem of nonlinear optics. *Each wavepair is a standing electrogravitational wave.*

D-1-F3

© T.E. Bearden 1984, 1985

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok


Negative energy: energy sink.
Fixed energy: Trapped; does not radiate or absorb.
Interference Zone
(Potential gradients)
Normal EM Energy:
May be positive, or negative, or fixed
Hidden Bidirectional EM energy flow
Hidden Bidirectional EM energy flow
Scalar Potential Beams
Whittaker/Ziolkowski Transmitter Arrays
(8 to 20 harmonic wavepairs each)

Figure 4. Scalar potential interferometry provides action-at-a-distance. It already creates normal EM fields and waves.

D-1-F4

© 1994 T.E. Bearden

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok


separates the
photon and
the antiphoton
GRAVITON
PHOTON
ANTIPHOTON
e -
PHOTON
ANTIPHOTON
NUCLEUS
RECOILS

NOTE: Graviton waves are bidirectional phase waves of photon/antiphoton coupling and uncoupling in the vacuum.

The atom is an assembly of dynamic dipoles.

A dipole splits the graviton into a photon and an antiphoton.
The photon interacts with the electron, producing the action.
The antiphoton interacts with the nucleus, producing the reaction.

Figure 5. Graviton interaction with matter produces the photon interaction and Newton's third law reaction.

D-1-F5

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok


RAL
RECESSION
INSIDE
THE WIRE
acts as gyro
Poynting flow S (outside)
FIELD ENERGY DENSITY FLOW
ESTABLISHES AN EQUIPOTENTIAL V
Poynting flow
outside the wire
S
e⁻
SPIN
dφ/dt
v ≈ c
dq/dt (inside)
dmₑ /dt
(WORK FLOW)
v < c
SPIN
S,
dφ/dt
(outside the wire)
loss-free
Poynting
energy flow
electron
current
direction
wire
dmₑ /dt
(inside the wire)
"drift" current due
to loads and losses
Jφ
dmₑ /dt

Figure 6. Currents in and along a conductor, with electron precession.

D-1-F6

© 1993 T.E. Bearden

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok


ANTIPHOTON
pump wave
e⁻
Excitation or ionization
Photons
RETRACING EXACT PATH OF SIGNAL WAVE
Antiphotons
Antiphotons
Antiphotons
e⁻
SIGNAL WAVE PATH (GRAVITONS)
PHOTON
ANTIPHOTON
NUCLEUS DOES NOT RECOIL
pump wave
PHOTON
ANTIPHOTON

- Dipolarity of the atom separates photon and antiphoton.
- Photon interacts with electron.
- Pumped nonlinear atom acts as a pumped phase conjugate mirror. Directs the antiphoton back along the path taken by graviton.
- Antiphoton does not interact with nucleus. Thus there is no nuclear recoil force generated.
- Nucleus thus does not recoil.
- Not a violation of Newton's third law, once one understands the mechanism that generates third law reaction. In the absence of the generating mechanism, there is no third law recoil. In EM field theory, the "missing antiwave" has necessitated third law omission.

Figure 7. Emission of antiphoton; nucleus does not recoil. Atom acts as a pumped phase conjugate mirror.

D-1-F7

© 1995 T.E. Bearden

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok


Room temperature
superconductive section
NOTE: May also utilize a tuned
LC oscillator on the secondary
side of the transformer
Bridge
Swinger
AC
Signal
Source
(Optimize V;
Minimize i)
$i \sim 0$
dq/dt
Blocker
$i = 0$
$\frac{d\phi}{dt} \neq 0$
$i \neq 0$
$i \neq 0$
LOAD
Patent Pending

Figure 8. dq/dt-free driving a swinger by S-flow.

Poynting energy flow S with its accompanying potential V is shuttled from the source to a tuned LC oscillator in resonance at the driving frequency or slightly below. The LC oscillator is driven by S-flow and dV/dt flow alone. The swinger furnishes its own free electrons, which receive S and EMF from the bridge, thereby producing dq/dt.

© T.E. Bearden 1993, 1994, 1995

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok



Figure 9a. Normal resistor receives ordered energy and scatters it.



Figure 9b. Negative resistor receives, concentrates, and reorders scattered energy.

Figure 9. Normal resistor versus a negative resistor.

D-1-F9 © T.E. Bearden 1993, 1996

Some 17 signals were fed into a rotating plasma, which added phase conjugates to them. This infolded 17 wavepairs, each pair a coupled wave/antiwave, thereby forming a scalar potential with an artificial Whittaker pump wave internal structure. This infolded pump wave complex was modulated onto a powerful, rippling magnetic field, guaranteeing penetration even into the atomic nuclei. A specific, amplified antiengine for the exact cellular disease state was generated, reversing the diseased cells back to a previous healthy state.

Figure 10. Priore's laboratory apparatus for cellular reversal.

D-1-F10 © T.E. BEARDEN 1993, 1995



We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok



Note: EM texts err in showing the battery "gate" as the source of energy.

Figure 11. Poynting S-flow along a simple circuit.

From particle physics, any electric charge is a broken symmetry in the vacuum's virtual particle flux. Any dipole is thus two locally broken symmetries. Thus the dipole acts as a gate/source, driven by the fierce vacuum flux. So a dipole already "extracts" and gates EM energy flow, directly from the seething vacuum.

Every battery and generator is already a "free energy" source of extracted and gated EM energy from the vacuum.

D-1-F11

© T.E. Bearden 1994

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok


VACUUM FLUX
Net Potential Difference Between Flows
+
emf
back emf
-
S_2 flow
$J\phi > 0$
SOURCE
S-flow
V drop
S-flow
S-flow
Scattered photons
(Scattered Poynting S-flows)

Figure 12a. Normal current flow; $J\phi$ is the electron transport of energy, while S is the speed-of-light Poynting energy flow.


S_3 net flow
S_1 flow
Hidden bidirectional EM waves
VACUUM FLUX
Net Potential Difference Between Flows
+
emf
back emf
-
S_2 flow
$dq/dt = 0$
$J\phi = 0$
SOURCE
V (No drop)
Ordered hidden photon/antiphoton pairs (gravitons)
(Ordered Poynting S-flows)

Figure 12b. In a conductor with dq/dt blocked; S-flow and hidden Whittaker-wave flow continue.

Figure 12. Overt and covert field energy density flows.

D-1-F12

© 1994, 1995 T.E. Bearden

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok


SOURCE
f(V²)
+V R
0
-V R
dE L / dt
dV/dt = dϕ/dt = - dE B / dt
E r
H t
dE L / dt
positive half of a cycle
Reference
negative half of a cycle
NOTE:
Use upper pair of conductors for (+) half-cycle
Use lower pair of conductors for (-) half-cycle
S
SOURCE
f(-V) 2
S
S'

Figure 13. Poynting vector currents S and S' versus massless displacement currents.

D-1-F13

© 1995 T.E. Bearden


S-flow and EMF flow
V>>0
V>>0
source
i ≈ 0
dQ/dt
BLOCKER
(Conductor)
i>>0
LOAD
Closed Current Loop A
Closed Current Loop B
BRIDGE
(Automatically Room Temperature Superconducting)

Figure 14. Bridging to enable room temperature superconductivity.

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok


+V
+V
TRANS-FORMER
+
DC SOURCE
—
AC GENERATOR AND CONTROLLER
CHARGE BARRIER SEMI-CON-DUCTOR
LOAD
+
CHARGE CIRCUIT
DISCHARGE CIRCUIT

* NOTE:

DISCHARGE CIRCUIT AND LOAD GROUND
MUST BE ISOLATED FROM THE
CHARGE CIRCUIT GROUND.
FEEDBACK LOOP MUST BE RIGIDLY CLAMPED AND LIMITED.

Patent Pending

Figure 15. Use of Fogal semiconductor for overunity (closed system).

D-1-F15

© 1993, 1995 T.E. Bearden

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok


force on B due
to field of A
A
Fixed
Charge
+
C
∞
test charge B forced
in to point C

Figure 16a. Magnitude of the scalar potential is determined by work required to push in a unit charge from infinity; e.g., against a repelling like charge. If test charge is released, work will be performed upon it to translate it back toward infinity

Figure 16a. Process for overunity coefficient of performance.

D-1-F16A

© T.E. Bearden, 1993, 1994, 1995


switch
a
(+)
A
C
B (test
charge)
force on B due to field of A,
only on outgoing phase
∞
+
b
−
S
source
potential
spherical
conducting
shell
potential
Test charge B drifted in
to point C, with little
resistance

Assumptions: Capacitance of A very small; charge B large, power-free switching

Switch potential off, drift in test charge B, switch potential back on. Can now get free work from repelled test charge B. Get much more free work if A is at a high potential, and charge B is large.

Figure 16 b. Demonstration of overunity efficiency

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies.
Ok


Potential at C (when switch on)
ϕ(x) after five time constants
ϕ(x) (when switched to ground)
0
x
∞

Ideally, switching the potential, rather than flowing charges, requires only minuscule overhead energy dissipation

Figure 16c. Potential to which test charge is exposed.

D-1-F16C

© T.E. Bearden, 1993, 1994, 1995

Open system receiving excess energy from an external source


SOURCE LOOP
DIPOLE
PLUS
EXTENSION
LINES
POTENTIAL
TWO S-FLOWS
TWO LOCAL SPACETIME CURVATURES
BROKEN SYMMETRY, THUS FREE-FLOWING FIELD ENERGY
Optimize S-flow and voltage
BRIDGE
BLOCK dq/dt
PASS VOLTAGE
PASS S-FLOW
SURROUNDING VACUUM
LOAD LOOP
LOAD
dq/dt FLOW
DROP EXCESS ϕ IN LOAD
TRANSPORT ENERGY
dq/dt FLOW
Jϕ FLOW
COLLECT
S-FLOW, EMF
ON CONDUCTION ELECTRONS AS Jϕ
Optimize current for voltage available

Figure 17. Operation of an overunity electrical power system.

D-1-F 17

© 1992 T.E. Bearden

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok


VACUUM
CHARGE
$q = - \phi_q \times m_q$
Note: X is a coupling operator
ϕ_q
MASS
m_q
virtual
photon
flux
exchange

Figure 18. An electric charge q is a broken symmetry. It continuously and violently exchanges energy with the vacuum.

D-1-F 18

© 1994 T.E. Bearden

We use cookies to ensure that we give you the best experience on our website. By using this site you are accepting our usage of cookies. Ok

Dawn of The E-BOMB

For the wired world, the allure and the danger of high-power microwave weapons are both very real

By Michael Abrams

In these media-fueled times, when war is a television spectacle and wiping out large numbers of civilians is generally frowned upon, the perfect weapon would literally stop an enemy in his tracks, yet harm neither hide nor hair. Such a weapon might shut down telecommunications networks, disrupt power supplies, and fry an adversary's countless computers and electronic gadgets, yet still leave buildings, bridges, and highways intact. It would strike with precision, in an instant, and leave behind no trace of where it came from.

In fact, it almost certainly is already here, in the form of high-power microwave (HPM) weapons. As their name suggests, HPMs generate an intense "blast" of electromagnetic waves in the microwave frequency band (hundreds of megahertz to tens of gigahertz) that is strong enough to overload electrical circuitry. Most types of matter are transparent to microwaves, but metallic conductors, like those found in metal-oxide semiconductor (MOS), metal-semiconductor, and bipolar devices, strongly absorb them, which in turn heats the material.

An HPM weapon can induce currents large enough to melt circuitry. But even less intense bursts can temporarily disrupt electrical equipment or permanently damage ICs, causing them to fail minutes, days, or even weeks later. People caught in the burst of a microwave weapon would, by contrast, be untouched and might not even know they'd been hit. (There is, however, an effort to build a microwave weapon for controlling crowds; a person subjected to it definitely feels pain and is forced to retreat.)

"HPM sources are maturing, and one day, in the very near future, they will help revolutionize how U.S. soldiers fight wars," says Edl Schamiloglu, a professor of electrical and computer engineering at the University of New Mexico in Albuquerque and one of the leading researchers in this burgeoning field.

The fact that we seldom hear about HPM weapons only adds to their exoticism. Last spring, stories leaked to the press suggested that the Pentagon, after decades of research, had finally deployed such a device in Iraq. And when news footage showed a U.S. bomb destroying an Iraqi TV station, many informed onlookers suspected it was an electromagnetic "e-bomb."

"I saw the detonation, and then I saw the burst—which wasn't much. If they took the station out with that blast, I strongly suspect that we used Iraq as a proving ground" for HPMs, says Howard Seguine, an expert on emerging weapons technology with Decisive Analytics Corp., in Arlington, Va.

But while the U.S. military proudly paraded assorted new war-making technology during its conquest of Iraq, from unmanned combat aerial vehicles to a new satellite-based tracking network, it remained tight-lipped about this "mother of all weapons." Asked at a 5 March news briefing to confirm the rumor, General Tommy Franks, head of U.S. forces during the war, would only say, "I can't talk to you about that because I don't know anything about it."

Military secrecy is nothing new, of course. What is known about microwave weapons is that the U.S. military has actively pursued them since the 1940s, when scientists first

CHIP SIMONS

Microwave weapons researcher Edl Schamiloglu sits in front of the Pulserad-110A accelerator, which his lab at the University of New Mexico uses to produce single 100-nanosecond pulses of electron beams, each pulse emitting hundreds of megawatts of power.

observed the powerful electromagnetic shock wave that accompanied atmospheric nuclear detonations, suggesting a new class of destructiveness. While much of the work on HPMs remains classified, the Pentagon has also recently sponsored a number of U.S. university laboratories to work out the basic principles of microwave weapons, including reliable and compact nonnuclear ways of generating microwave pulses.

Many of those results are being published in the open literature [see To Probe Further, p. 30]. In fact, all you need is a reasonable grasp of physics and electrical engineering to appreciate the ingeniousness of microwave weapons. Anyone with a technical bent could probably also build a crude e-bomb in their garage, a thought that security-minded folks find rather troubling.

How they work

From the military's perspective, HPM weapons, also known as radiofrequency weapons, have many things going for them: their blast travels at the speed of light, they can be fired without any visible emanation, and they are unaffected by gravity or atmospheric conditions. The weapons come in two flavors: ultrawideband and narrowband. Think of the former as a flashbulb, and the latter as a laser; while a flashbulb illuminates across much of the visible spectrum (and into the infrared), a laser sends out a focused beam at a single frequency.

Like the flashbulb, ultrawideband weapons radiate over a broad frequency range, but with a relatively low energy (up to tens of joules per pulse). Their nanoseconds-long burst produces a shock that indiscriminately disrupts or destroys any unshielded electronic components within their reach. The bomb's destructiveness depends on the strength of the ultrawideband source, the altitude at which it is initiated, and its distance from the target [see "E-Bomb Anatomy," p. 29].

Narrowband weapons, by contrast, emit at a single frequency or closely clustered frequencies at very high power (from hundreds up to a thousand kilojoules per pulse), and some can be fired hundreds of times a second, making an almost continuous beam. These pulses can be directed at specific targets—say, a command and control complex positioned on the roof of a hospital in a densely populated neighborhood—and tuned to specific frequencies. Technologically more sophisticated than ultrawideband sources, they are far more difficult to develop, but are reusable and potentially of much greater use to the U.S. military.

Both versions wreak the same kind of havoc on just about any kind of unprotected electronic equipment. Particularly vulnerable is commercial computer equipment; anything in excess of just tens of volts can punch through gates in MOS and metal-semiconductor devices, effectively destroying the device, explains Carlo Kopp, a visiting research fellow in military strategy at the Strategic and Defense Studies Centre in Canberra, Australia, and a computer scientist who lectures at Monash University in Melbourne. The higher the circuitry's density, the more vulnerable it is, because less energy is required to overload and destroy the transistors. HPMs also produce standing waves in electrical grid wiring and telephone and communications wiring, entering through cables, antennas, and even ventilation grills. They can immobilize vehicles with electronic ignition and control systems, too.

"Since the frequency is high, this permits parasitic or stray capacitances to couple energy via paths in the circuit that may not be protected against overvoltage," Kopp explains.

The e-bomb

You could deliver an e-bomb in a number of ways: cruise missile, unmanned aerial vehicle, or aerial bomb. Whether ultrawideband or narrowband, the e-bomb consists of both a microwave source and a power source [again, see diagram, p. 29]. Ultrawideband e-bombs aim to create an electromagnetic pulse like that accompanying a nuclear detonation, except that the nuclear material is replaced with a conventional, chemical explosive. The microwave source typically relies on an extremely fast switching device, according to Kopp, who has written widely on weaponizing HPM technology. Narrowband e-bombs might use a virtual cathode oscillator (vircator) tube or a variant of a magnetron. Though termed narrowband, they don't have the high coherency seen in signal-carrying applications, Kopp says.

It takes gigawatts of power to feed an e-bomb's microwave source. For that, the flux compression generator, or FCG, is a good choice, says Kopp. Invented by Clarence ("Max") Fowler at Los Alamos National Laboratory after World War II as a byproduct of research into atomic bomb detonators, FCGs are conceptually simple. The best-known type consists of an explosive-packed copper cylinder surrounded by a helical current-carrying coil. Upon detonation, the explosion flares out the cylinder, short-circuiting the coil and progressively reducing the number of turns in the coil, thus compressing the magnetic flux. Large FCGs have produced tens of gigawatts, and they can be cascaded—connected end to end—so that the output from one stage feeds the next.

Despite its simplicity, an FCG-powered e-bomb is probably too difficult for the average terrorist to build on the cheap. For one thing, to test the assembled apparatus, you have to blow it up. For weapons researchers, the e-bomb poses other problems. The strength of the shock wave dissipates rapidly as it moves out from the explosion. To knock out an electrical power substation, for example, the weapon has to strike within about a hundred meters. "Like all microwave radiation, the effect follows an inverse square law with increasing distance," Kopp notes. Though the explosion needed to force out the current can be fairly small, it keeps the munition from being fully nonlethal and nondetectable. Also, anything that's been hardened or shielded against an electromagnetic pulse from a nuclear bomb will probably emerge unscathed.

Focused like a laser

The type of narrowband HPM weapons that the U.S. military is looking at offers everything that e-bombs do not. They're nonlethal, reuseable, and tunable, and they can be fired from miles away. Like a laser, the focused beam disperses only slightly over great distances. With a frequency range that is between about 1 and 10 GHz, they can penetrate even electronics shielded against a nuclear detonation. The deepest bunkers with the thickest concrete walls are not safe from such a beam if they have even a single unprotected wire reaching the surface.



Schamiloglu holds a rippled-wall waveguide connected to an antenna. The waveguide is where kinetic energy from a pulsed-power-driven electron beam is transformed into high-power microwaves. In the background sit the Pulserad-110A [left] and the Russian-built Sinus-6 [right]. The Sinus-6 can fire a several-gigawatt pulsed beam 200 times a second in 10-nanosecond bursts.

CHIP SIMONS

A microwave beam is created much like a laser beam. Between the batteries (or other power source) and the beam sit three elements: capacitors that turn the stored energy into an electron beam of nanosecond bursts, a microwave source that converts the electron beam into focused, high-frequency electromagnetic waves, and an antenna that points and shoots the beam.

Kirtland Air Force Base, in Albuquerque, N.M., is considered the epicenter of the Pentagon's research on pulsed-power electromagnetic weapons. There, its premier pulsed-power system, the Shiva Star, is housed behind meter-thick walls [see photo, p. 28]. An Air Force spokesperson refused to comment on what goes on in their pulsed-power programs, but a fact sheet on the Web site of Kirtland's Directed Energy Directorate describes the Shiva Star as capable of producing "120 thousand volts and 10 million amps for down to one millionth of a second to produce a power flow equivalent to a terawatt."

The Kirtland machine isn't used to investigate HPM weapons per se, and its massive size makes it clearly impractical for delivering microwave beams to any spots of real military interest. Indeed, one big push in microwave weapons has been toward portability. "Back in the 1960s and 1970s, the attitude was, 'Yeah, we can do it—but we need Hoover Dam as our power supply,' " says Seguine. But just as batteries for cellphones and laptops have shrunk and gained capacity, so have sources for microwave weapons.

In the 1990s, the U.S. Air Force Office of Scientific Research set up a five-year Multidisciplinary University Research Initiative (MURI) program to explore microwave sources. One of those funded was the University of New Mexico's Schamiloglu, whose lab is located just a few kilometers down the road from where the Shiva Star sits behind tightly locked doors. Thanks in large part to his and his colleagues' efforts, the fundamental capabilities and limitations of high-power microwave sources are now better understood and appreciated.

Amidst the lead bricks and clutter in Schamiloglu's basement lab lies his masterwork: the Sinus-6. "A lot of laboratories come up with very cute names for these devices," Schamiloglu notes with a smile. "We never did." With a huge cylinder at one end connected to the long microwave source, the Sinus-6 looks like a giant torch lying on its side [see photo, above]. The big cylinder contains a Tesla transformer, whose two coils vibrate in resonance and amplify the incoming voltage "with nearly 100-percent efficiency," Schamiloglu says. Once the pulse has been transformed into an electron beam, it is guided by a strong axial magnetic field through the long tube that will turn it into microwaves.

The Sinus-6 can fire a several-gigawatt pulsed beam 200 times a second in 10-nanosecond bursts. "It has to be pulsed power because what you're after is high peak power," says Schamiloglu. "The power in the microwaves is going to depend on the electric field squared, so if you generate very large power, then the electric field is going to be big."

How big? To drive the Sinus-6's beam continuously for an entire second, you'd need to supply about 25 gigajoules—"the entire output of a typical coal-fired electrical plant for 10 full seconds," Schamiloglu says. Another reason for pulsed rather than continuous power is to avoid a problem at the output end: the air around the antenna would heat to a plasma that in turn would interfere with a continuous beam at these power levels.

The key to reaching gigawatts of power is dumping all the energy in one gigantic, nearly instantaneous pulse. A pressurized gas switch prevents the Tesla transformer from prematurely dumping as it builds up for the next pulse. The switch is filled with highly compressed and nonconducting nitrogen gas. When the transformer coils reach 700 kV, the nitrogen gas breaks down, and the pulse leaps through to the electron-beam diode.

The U.S. Air Force's Shiva Star is a pulsed-power system used to simulate the effects of nuclear weapons.

U.S. AIR FORCE

"Once you've fired the switch, it conducts, it generates a pulse," says Schamiloglu. "It conducts because you've made a plasma channel out of the gas. Then you have to wait for that plasma to recombine and form a neutral gas again. A typical time scale for this thing to recombine and fizzle out and be a neutral gas again is probably on the order of milliseconds."

Among the best candidates for supplying microwaves is the backward wave oscillator; it has the advantage of being tunable (plus or minus 20 percent) and producing output in the 4–10-GHz range. To turn the kinetic energy from the Sinus-6's electron beam into high-power microwaves, the oscillator uses a rippled-wall waveguide, also called a slow-wave structure [see photo, p. 27].

The structure sets up standing electromagnetic waves in such a way that energy is rapidly transferred to them from the incoming beam of relativistic electrons from the Sinus-6. This growing energy initially propagates in the opposite direction of the beam's movement—hence the device's name—and is then reflected forward and radiated in the form of high-power microwaves. Backward wave oscillators, by the way, are also being tested as a way to push giant sails into outer space, to detect space debris, and to clear minefields.

Being able to tune an HPM weapon comes in handy when a particular target proves invulnerable to a particular frequency. "Experience has shown that if the frequency is slightly altered, measurable effects are discerned," Schamiloglu notes. People used to believe that varying the frequency of HPMs wasn't practical, but Schamiloglu and his students proved them wrong.

Coincidence and curiosity led to their discovery. Schamiloglu first acquired the Sinus-6 from Russian researchers in the early 1990s. (The Soviet Union once boasted a sophisticated program to develop microwave weapons; after its collapse, parts of that legacy were put up for sale, to the delight of researchers like Schamiloglu.) But once the apparatus was assembled in his New Mexico lab, he couldn't get it to operate as promised, so Russian colleagues flew over to help.

"One of them took the RF structure [the rippled-wall waveguide] and started hammering on the thing," Schamiloglu recalls. When they tried it again, everything worked. "I was baffled why manhandling this RF structure—ramming it in—could affect the power so much," says Schamiloglu. So he started a series of experiments in which he slightly displaced the backward wave oscillator by increments. With a little experimentation assisted by computer simulations, his team found that the frequency could be adjusted by changing the distance between the diode and the microwave source. The result is that the backward wave oscillator is now one of the few pulsed-power HPM sources that can be tuned.

Smaller is better

One disadvantage of this oscillator, however, is that it needs an external magnetic field to create the microwave beam, a major hurdle to making the whole system smaller. The size of the Sinus-6 and attendant equipment in Schamiloglu's basement suggests that the U.S. military is nowhere near fielding a narrowband HPM weapon. "When I first started working on high-power narrowband sources, we joked that you can do more damage dropping this equipment on someone than you can by using it," he recalls. "People know how to make microwave sources in the laboratory. The challenge is to take this and package it into an autonomous platform and have it function at the same parameter levels."

Schamiloglu is now hard at work under a new MURI program to study the possibilities of making a compact pulsed-power source. Current narrowband generators are typically several meters long, batteries not included. Schamiloglu and his colleagues are studying how to incorporate novel ceramics into pulsed-power systems, which they believe will allow the length of such sources to be halved. The trick is identifying materials with a high dielectric constant that can also survive the harsh electric fields. "Materials will be an important part in making the next giant leap," he says.

Life in a glass house

Among those agreeing that narrowband HPM weapons will need more refining before they become truly useful to the military is Loren B. Thompson, chief operating officer of the Lexington Institute, a military think tank based in Arlington, Va. He looked

E-Bomb Anatomy

In this hypothetical design for an e-bomb, a two-stage flux compression generator provides gigawatts of power to the virtual cathode oscillator (vircator), which produces the high-power microwaves. The bomb's destructiveness depends on the microwave source and target's vulnerability to electromagnetic attack, among other things, but a 10-GW, 5-GHz HPM device would have a "lethal" footprint 400 to 500 meters across, producing field strengths of several kilovolts per meter. Such an e-bomb would wreak major havoc if detonated over a heavily populated area.


Power supply
Coaxial capacitor bank
Flux compression generator (stage 1)
Flux compression generator (stage 2)
Pulse-shaping network
Microwave antenna
Battery
Ballast ring
Vircator tube


Backfire reflector
Double helix antenna
Dielectric nose cone
Circularly polarized wavefront


Detonation altitude
Lethal beamwidth
Lethal footprint

ILLUSTRATION: JOHN MACNEILL   SOURCE: CARLO KOPP

at the technology as principal investigator of "Directed-Energy Weapons: Technologies, Applications and Implications," a report that the institute put out in February. "We have some fairly rudimentary weapons that we're ready to use," Thompson says. "This is going to be a very important weapons technology, and the basic physical principles are well understood. But the military is having some difficulty in assimilating them."

Thompson's report speaks of a future with satellites delivering missile-debilitating microwaves, unmanned vehicles that fly by and destroy communications systems, and war without civilian casualties. But the fact remains that it's the U.S. military—as well as U.S. financial institutions, PCs, and Game Boys—that will be the most susceptible to such weapons.

"One of the things that happened during the last 10 years—as the Pentagon fell in love with network-centered warfare—is that we purchased a lot of very fragile digital systems off the shelf from commercial sources," Thompson notes. Such moves were taken in the name of cost and efficiency, but the resulting equipment is almost certainly more vulnerable to electromagnetic attack than the vacuum tubes and heavy metal-encased electronics of yesteryear.

"Computers become more vulnerable as the voltage at which they operate becomes smaller," says Victor Granatstein, professor of electrical engineering at the University of Maryland in College Park, who is studying the effects of microwave pulses on integrated electronics. "When our opponent was the

Soviet Union, the electronics were much more robust because they weren't miniaturized. Now they have very thin oxide layers that can easily break down." Wireless networking makes matters worse. Computers and other communications devices now have antennas attached, giving an electromagnetic pulse a direct pathway to its guts.

Meanwhile, the U.S. Navy no longer requires that all its hardware be hardened against nuclear electromagnetic pulses. It deemed that maintaining those standards was too costly and slowed down the integration of new technology. The presumption was that after the Cold War, nobody would be using nuclear bombs, says the Lexington Institute's Thompson. "Whenever I ask the admirals, 'Well, what if someone did use a nuclear bomb?,' I just get this kind of blank I-don't-have-an-answer-for-that sort of look."

Don't Try This at Home

First things first: we do not under any circumstances recommend that you build your own electromagnetic weapon. But if you're hellbent on adding to the mayhem, cheaply and without too much studying, you might try a high-energy radiofrequency, or HERF, gun. As described by engineering student Rostislav Persion on his Web site, Voltage Labs, which is devoted to do-it-yourself electromagnetic weapons, you can make one from a microwave oven.

Before you begin, though, wait until everyone else has left the house. Next, take apart the microwave oven, but don't disconnect any of the components; manufacturers intentionally make this hard to do, so you may end up just breaking the machine. Inside you will find the oven's microwave source: the magnetron. Wrap a tube of sheet metal around it to act as a waveguide. Your power source is the house's ac, so just plug in the oven and point it at your TV. Warning: there's a real possibility that you will burn yourself instead.

For schematics and a demonstration, head to the Web at http://www.voltsamps.com/pages/projects/herf004/. —*M.A.*

In the wrong hands

The scariest part of microwave weapons may be that crude forms of the technology are readily available to anyone right now. "Any nation with a 1950s technology base capable of designing and building nuclear weapons and radars" can build an e-bomb, says military analyst Kopp. Indeed, more than 20 countries now have programs to develop some type of RF weapon.

"The more widespread the technology is, the more likely that people with nefarious purposes will have access. It's just an inescapable fact," says Thompson. "I don't know what we're going to do. Nobody in Washington knows. I imagine that the way the clear thinking starts is with a catastrophe."

Criminals and pranksters have already started exploiting that weakness. In one of the more harmless applications, a Japanese scam artist rigged up a weak microwave generator inside a suitcase to rip off a pachinko parlor. When he placed the suitcase next to one of the machines (which is something like a cross between a slot machine and a pinball machine) and turned it on, the pachinko machine went haywire and disgorged a pile of coins. The perp managed the trick several times before he was caught.

Other press accounts hint at electromagnetic weapons being deployed by Chechen troops, and by an unnamed assailant trying to topple London's futures market [see "Don't Try This at Home," above].

Thankfully, protecting yourself against the microwave-enabled goofballs of the world isn't too difficult. "It is analogous to existing techniques used to trap RF interference inside equipment, except that the higher power levels require special measures," Kopp notes. Rooms or equipment chassis must become electrically sealed Faraday cages, and protective devices must be added wherever cables enter the protected volume. "Optical fibers are very useful in this game."

Such protective measures are a lot cheaper to design in from the beginning than to add on afterward, says Howard Seguine. "The general rule of thumb is that if you do the hardening during the design phase, it increases the cost roughly 1 percent. If you do it afterward, it may cost as much as 30 percent more."

But maybe hardening is a waste of time. Arthur Varanelli, a Raytheon Co. engineer who has helped write several IEEE standards for electromagnetic field measurement, human exposure, and safety, is skeptical that a malicious prankster could exploit the technology.

"Some of this stuff is just so far out there," Varanelli says. "I just don't see people running around with Buck Rogers ray guns. It's great for a science fiction writer, great to prey upon people's fears." He scoffs at the suggestion that a do-it-yourselfer could build a microwave weapon potent enough to do real damage. "People can put tacks in the road. Are we worried about electronic tacks in the air?"

The wide disparity in opinions and the uncertainty about microwave weapons, from Loren Thompson on one end to Arthur Varanelli on the other, are all part of what makes them so powerful, says military analyst John Pike, who is director of GlobalSecurity.org (Alexandria, Va.). "It all depends on the complex interactions between the weapon and the target," he notes. "I can set up a strap-down chicken test that makes [an HPM weapon] look pretty good. But as soon as I start getting into real-world targets, maybe it doesn't work so well."

"Part of the story is we don't know what the story is," Pike says. "These are weapons that by their nature seek the shadows. And unlike cluster bombs or atomic bombs, they aren't going to leave behind unambiguous evidence of their use." ●

To Probe Further

For a detailed technical discussion of high-power microwaves, see *High-Power Microwave Sources and Technologies*, edited by IEEE Fellows Robert J. Barker and Edl Schamiloglu (Wiley–IEEE Press, 2001). Schamiloglu is also coauthor, with James Benford and John Swegle, of the forthcoming *High-Power Microwaves*, 2nd edition (Institute of Physics, 2004).

The truly prepared, or merely paranoid, will want to consult Carlo Kopp's "Hardening Your Computing Assets" at http://www.globalsecurity.org/military/library/report/1997/harden.pdf.

BEARDEN
FER DE LANCE
12.14 15:24
BRIEFING ON SOVIET SCALAR
ELECTROMAGNETIC WEAPONS

ORDER THE ALL NEW
2ND EDITION
OF "FER DE LANCE"

Updated to the year 2002

Stunning new revelations
about the secret scalar
EM wars the media ignores

THIS BOOK IS THE
ONLY SOURCE FOR
THIS INFORMATION

-

The Tom Bearden
Website



Scalar Potential Interferometer

Figure 6. Multimode Tesla Weapon

In the 1930's Tesla announced other bizarre and terrible weapons: a death ray, a weapon to destroy hundreds or even thousands of aircraft at hundreds of miles range, and his ultimate weapon to end all war -- the Tesla shield, which nothing could penetrate. However, by this time no one any longer paid any real attention to the forgotten great genius. Tesla died in 1943 without ever revealing the secret of these great weapons and inventions.

Unfortunately, today in 1981 the Soviet Union has long since discovered and weaponized the Tesla scalar wave effects. Here we only have time to detail the most powerful of these frightening Tesla weapons -- which Brezhnev undoubtedly was referring to in 1975 when the Soviet side at the SALT talks suddenly suggested limiting the development of new weapons "more frightening than the mind of man had imagined." One of these weapons is the Tesla howitzer recently completed at the Saryshagan missile range and presently considered to be either a high-energy laser or a particle beam weapon, (See Aviation Week & Space Technology, July 28, 1980, p. 48 for an artist's conception.)



Aviation Week & Space Technology July 28, 1980


FOURIER TRANSFORM SECTIONS
(12 WAVELENGTHS EACH)
SCALAR ANT
SCALAR ANT
REFERENCE
CONTROL & PHASING
COMPUTER FACILITY
POWER FOR PULSE MODES
EXPLOSIVE GENERATORS BANK
POWER FOR CONTINUOUS MODES
EXTRA GENERATOR POWERS COMPUTER FACILITY
MORAY POWER UNITS

Figure 7. Tesla Weapons at Saryshagan

The Saryshagan howitzer actually is a huge Tesla scalar interferometer with four modes of operation. One continuous mode is the Tesla shield, which places a thin, impenetrable hemispherical shell of energy over a large defended area. The 3-dimensional shell is created by interfering two Fourier-expansion, 3-dimensional scalar hemispherical patterns in space so they pair-couple into a dome-like shell of intense, ordinary electromagnetic energy. The air molecules and atoms in the shell are totally ionized and thus highly excited, giving off intense, glowing light. Anything physical which hits the shell receives an enormous discharge of electrical energy and is instantly vaporized -- it goes pfft! like a bug hitting one of the electrical bug killers now so much in vogue.

If several of these hemispherical shells are concentrically stacked, even the gamma radiation and EMP from a high altitude nuclear explosion above the stack cannot penetrate all the shells due to repetitive absorption and reradiation, and scattering in the layered plasmas.

In the continuous shield mode, the Tesla interferometer is fed by a bank of Moray free energy generators, so that enormous energy is available in the shield. A diagram of the Saryshagan-type Tesla howitzer is shown in figure 7. Hal Crawford's fine drawing of the interferometer end of the Tesla howitzer is shown in figure 6. Hal's exceptional rendition of the Tesla shield produced by the howitzer is shown in figure 8.


3–D SCALAR
INTERFEROMETRY
(HEMISPHERICAL SHELL)

Figure 8. The Tesla Shield


DECOYS
WARHEAD
GAMMA RAYS
EMP
DEBRIS
SCATTERING AND ABSORPTION
SCATTERING AND ABSORPTION
SCATTERING AND ABSORPTION
HEMISPHERES
OF INTENSE
LIGHT BANDS

Figure 9. Tesla Terminal Area Defense System

In the pulse mode, a single intense 3-dimensional scalar phi-field pulse form is fired, using two truncated Fourier transforms, each involving several frequencies, to provide the proper 3-dimensional shape (Figure 10). This is why two scalar antennas separated by a baseline are required. After a time delay calculated for the particular target, a second and faster pulse form of the same shape is fired from the interferometer antennas. The second pulse overtakes the first, catching it over the target zone and pair-coupling with it to instantly form a violent EMP of ordinary vector (Hertzian) electromagnetic energy. There is thus no vector transmission loss between the howitzer and the burst. Further, the coupling time is extremely short, and the energy will appear sharply in an "electromagnetic pulse (EMP)" strikingly similar to the 2-pulsed EMP of a nuclear weapon.

This type weapon is what actually caused the mysterious flashes off the southwest coast of Africa, picked up in 1979 and 1980 by Vela satellites. The second flash, e.g., was in the infrared only, with no visible spectrum. Nuclear flashes do not do that, and neither does superlightning, meteorite strikes, meteors, etc. In addition, one of the scientists at the Arecibo Ionospheric Observatory observed a gravitational wave disturbance -- signature of the truncated Fourier pattern and the time-squeezing effect of the Tesla potential wave -- traveling toward the vicinity of the explosion.



TESLA HOWITZER
(SCALAR INTERFEROMETER)

Figure 10. "Nuclear" Flashes off the Coast of Africa



Lithuania - 10 Sep 1976 - British European Airways Flight #831 between Moscow and London

CIA Report Released under FOIA

Figure 11. Continuous Tesla Fireball

The pulse mode may be fed from either Moray generators or -- if the Moray generators have suffered their anomalous "all fail" malfunction -- ordinary explosive generators. Thus the Tesla howitzer can always function in the pulse mode, but it will be limited in power if the Moray generators fail.

In the continuous mode, two continuous scalar waves are emitted -- one faster than the other -- and they pair-couple into vector energy at the region where they approach an in-phase condition. In this mode, the energy in the distant "ball" or geometric region would appear continuously and be sustained -- and this is Tesla's secret of wireless transmission of energy at a distance without any losses. It is also the secret of a "continuous fireball" weapon capable of destroying hundreds of aircraft or missiles at a distance. An example of a Soviet test of this mode of operation is shown in figure 11.

Witness to a super weapon?



Nick Downie describes the strange lurid glow that flared silently over the Hindu Kush

THE SUNDAY TIMES, 17 AUGUST 1980

(Multiple incidents in Sept., 1979)



TEHERAN, IRAN 17 JUNE 1966

SEEN FROM NEAR MEHRABAD AIRPORT

OBSERVED 4-5 MINUTES

SEEN BY 2 AIRCRAFT

CIA REPORT RELEASED UNDER FOIA

Figure 12. Tesla EMP Globe

The volume of the Tesla fireball can be vastly expanded to yield a globe which will not vaporize physical vehicles but will deliver an EMP to them to dud their electronics. A test of this mode is shown in figure 12. (See also Gwynne Roberts, "Witness to a Super Weapon?", the London Sunday Times, 17 August 1980 for several other tests of this mode at Saryshagan, seen from Afghanistan by British TV cameraman and former War Correspondent Nick Downie.)

If the Moray generators fail anomalously, then a continuous mode limited in power and range could conceivably be sustained by powering the interferometer from more conventional power-sources such as advanced magnetohydrodynamic generators.


DETECTION AND TRACKING
CONTINUOUS TESLA EMP GLOBE (DUDS ELECTRONICS)
TESLA FIREBALL (CONTINUOUS) (VAPORIZES VEHICLE)
TESLA FIREBALL (PULSE)
TESLA HOWITZER
EARTH'S SURFACE
USSR
U.S.
TESLA SHIELD

Figure 13. Tesla ABM Defenses



Figure 14. Moray/Tesla Technology: Star Wars Now

Typical strategic ABM uses of Tesla weapons are shown in figure 13. In addition, of course, smaller Tesla howitzer systems for anti-tactical ballistic missile defense of tactical troops and installations could be constituted of more conventional field missile systems using paired or triplet radars, of conventional external appearance, in a scalar interferometer mode.

With Moray generators as power sources and multiply deployed reentry vehicles with scalar antennas and transmitters, ICBM reentry systems now can become long range "blasters" of the target areas, from thousands of kilometers distance (figure 14). Literally, "Star Wars" is liberated by the Tesla technology. And in air attack, jammers and ECM aircraft now become "Tesla blasters." With the Tesla technology, emitters become primary fighting components of stunning power.

The potential peaceful implications of Tesla waves are also enormous. By utilizing the "time squeeze" effect, one can get antigravity, materialization and dematerialization, transmutation, and mindboggling medical benefits. One can also get subluminal and superluminal communication, see through the earth and through the ocean, etc. The new view of phi-field also provides a unified field theory, higher orders of reality, and a new super-relativity, but detailing these possibilities must wait for another book.

With two cerebral brain halves, the human being also has a Tesla scalar interferometer between his ears. And since the brain and nervous system processes avalanche discharges, it can produce (and detect) scalar Tesla waves to at least a limited degree. Thus a human can sometimes produce anomalous spatiotemporal effects at a distance and through time. This provides an exact mechanism for psychokinesis, levitation, psychic healing, telepathy, precognition, postcognition, remote viewing, etc. It also provides a reason why an individual can detect a "stick" on a radionics or Hieronymus machine (which processes scalar waves), when ordinary detectors detect nothing. Unfortunately there is not room to develop the implications of this human Tesla interferometry in detail, for that must wait for yet another book, presently in its initial stages, that Hal Crawford and I are writing.

Table 5. Orders of Reality

- **PHOTONS ARE**
  - **PAIR-COUPLED SCALARS**
  - **VELOCITY-LIMITED TO C**
  - **CARRIERS OF T**

- **PHOTON INTERACTION**
  - **IS UBIQUITOUS**
  - **PRODUCES** $\dot{T}$ **= C**
  - **YIELDS 1st ORDER REALITY**

- **SCALAR O WAVES**
  - **NOT VELOCITY-LIMITED**
  - **YIELD HIGHER ORDER REALITIES**



Figure 15. Implications of Tesla Potential

At the July 1981 U.S. Psychotronics Association's Annual Conference in Dayton, Ohio, I presented the first rough paper on the Tesla secret and scalar interferometry. A videotape of the presentation was made and will shortly be available. I am also scheduled to make a special presentation at the Alternate Energy Conference in Toronto, Canada in latter October, 1981. A professional, videotaped two-hour presentation on this subject is also being prepared. Wide distribution of the material through the international underground physics and technology network has already been made. This time, God willing, Tesla's secret will not be suppressed for another 80 years!

And perhaps it is not yet too late. The material has cost me (now) some 16 years of agonizing labor and nearly $100,000 of my own personal funds. No orthodox university, scientific group, foundation, or governmental agency would support such an effort, either financially or otherwise. Indeed, most ordinary journals will not even accept material on such matters. Nonetheless, the area is of overwhelming importance and I truly believe Tesla's lost secret will shortly affect the lives of every human being on earth.

Perhaps with the free and open release of Tesla's secret, the scientific and governmental bureaucracies will be. shocked awake from their slumber, and we can develop defenses before Armageddon occurs. Perhaps there is hope after all -- for even Brezhnev, in his strange July, 1975 proposal to the SALT talks, seemed to reveal a perception that a turning point in war and weaponry may have been reached, and that human imagination is incapable of dealing with the ability to totally engineer reality itself. Having tested the weapons, the Soviets must be aware that the ill-provoked oscillation of timeflow affects the minds and thoughts -- and the very lifestreams and even the collective species unconsciousnesses -- of all lifeforms on earth. They must know that these weapons are two-edged swords, and that the backlash from their use can be far more terrible to the user than was the original effect to his victim.

If we can avoid the Apocalypse, the fantastic secret of Nikola Tesla can be employed to cure and elevate man, not kill him. Tesla's discovery can eventually remove every conceivable external human limitation. If we humans ourselves can elevate our consciousness to properly utilize the Tesla electromagnetics, then Nikola Tesla -- who gave us the electrical twentieth century in the first place -- may yet give us a fantastic new future more shining and glorious than all the great scientists and sages have imagined.

References

The Tom Bearden Website

34 Flaws in Classical EM Theory

Note: If the scientific community had done their job, this Website would probably not be necessary.

---

1. SLIDE 1
2. SLIDE 2
3. SLIDE 3
4. SLIDE 4
5. SLIDE 5



Flaws In Classical EM Theory

1. Eliminates the Internal EM Inside the Scalar Potential.
2. No Definition of Electrical Charge or of Scalar Potential.
3. Equations Still Assume Material Ether Per Maxwell (Unchanged).
4. Use of Force Fields in Vacuum is False (and Known to be So).
5. Treats Charge q as Unitary Instead of Coupled System $q = \phi(q)m(q)$.
6. Confuses Massless Potential Gradients as Forces (See #3, #4).
7. Does Not Utilize Mass as a Component of Force (See #23).

© T. E. BEARDEN 1999

Next Slide

Return to Index



Flaws In Classical EM Theory (2)

8. Erroneously Assumes EM Force Fields as Primary Causes.
9. Topology of EM Model Has Been Substantially Reduced.
10. Does Not Include Quantum Potential or Action at a Distance.
11. Does Not Include Superluminal Velocity of Inner EM Components.
12. Does Not Utilize Extended Near-Field Coulomb Gauge Effects.
13. Does Not Include EM Generatrix Mechanism for Time Flow.
14. Does Not Unify Photon and Wave Aspects (Requires 7-D Model).

© T. E. BEARDEN 1999

Next Slide

Return to Index

Previous Slide



Flaws In Classical EM Theory (3)

15. Does Not Include Electron Spin and Precession (See #19, #24).
16. Treats EM Energy As Existing In "Chunks," Instead of as Flow.
17. Confuses Energy and Energy Collection (See #16).
18. Discards Half of Every EM Wave in Vacuum (See #22).
19. Erroneously Uses Transverse Vacuum Wave; It's Quasi-Longitudinal.
20. Arbitrarily Regauges Maxwell's Equations to Eliminate Overunity Maxwellian Systems.
21. Omits Phase Conjugate Optics Effects (Which are the *Rule* in Internal EM).

© T. E. BEARDEN 1999

Next Slide

Return to Index

Previous Slide



Flaws In Classical EM Theory (4)

22. Does Not Include EM Cause of Newtonian Reaction Force.
23. Erroneously Assumes Separate Force Acting on Separate Mass.
24. Confuses Detected Electron Precession Waves as Proving Transverse EM Waves in Vacuum (Remnant of Old "EM Fluid" Concept).
25. Due to Error in String Wave, Omits the Ubiquitous Antiwave.
26. *Assumes* Equilibrium; Not True Unless Include Vacuum Interactions.
27. Higher Topology Required, to Model Electromagnetic Reality.

© T. E. BEARDEN 1999

Next Slide

Return to Index

Previous Slide



Flaws In Classical EM Theory (5)

28. Lorentz surface integration discards Poynting energy transport.
29. Has nothing at all to say about form of EM entities in massless space.
30. Eliminates the infolded general relativity using EM-force as curve agent.
31. Does not include longitudinal EM wave phase conjugate pairs as time domain oscillations.
32. Does not include EM mechanism that generates time flow and flow rate.
33. Does not include time-excitation charging and decay.
34. Does not utilize time-reversal zones.

© T. E. BEARDEN 1999

Return to Index

Previous Slide

The Tom Bearden Website

Mind Control and EM Wave Polarization Transductions - Part I, II & III

Reprinted from "Explore" magazine, 1999

Part I

- Page 1
- Page 2
- Page 3
- Page 4
- Page 5
- Page 6
- Page 7
- Page 8
- Page 9
- Page 10

Part II

- Page 1
- Page 2
- Page 3
- Page 4
- Page 5
- Page 6
- Page 7
- Page 8

Part III

- Page 1
- Page 2
- Page 3
- Page 4
- Page 5
- Page 6
- Page 7
- Page 8
- Page 9

- The U.S. approach to mind control

- "Voices in my head"
  Flanagan's neurophone - used to give instructions to diplomats during negotiations, etc.

Mind Control and EM Wave Polarization Transductions, Part 1

©Copyright 1999 by T.E. Bearden, USA

Special Note

This article refers to experimental research techniques which can be detrimental or lethal in the hands of any but highly skilled, qualified experimental scientists proceeding under proper laboratory safety procedures. The purpose of this article is strictly for information to properly qualified and authorized scientists in certified laboratories. We do not propose or condone any use of these procedures for nonapproved practice of medicine without a license. Neither the publisher nor the author are responsible for accidents or outcomes in the use of these experimental pro-cedures and techniques. Any researcher who performs these procedures and experiments is acting on his or her own volition, and is solely responsible for insuring safety, qualifications, and legality of the acts and their results. We neither suggest nor condone unauthorized experimentation on human subjects. Such is a criminal violation of the constitutional rights of the subject under Federal and State laws, and is both illegal and immoral.

Abstract

For some time we have been repeatedly queried about the technical mechanisms and unusual electrodynamics of advanced mind control research, both in the West and abroad. Calling full attention to the special note above, in this paper we present a high-level over-view of the novel electromagnetic nature of mind operations, mind and body coupling, and *intent*•the induction of physical 3-space EM energy changes into the brain and nervous system, and into every cell of the body, from the mind's time-like coherent operations. We summarize the time-polarized electrodynamics used to engineer and affect mind operations and the mind-body coupling loop. Transduction mechanisms whereby differing EM wave polarizations can be transformed one-into-the-other are presented. We give two specific examples of lethal foreign military tests in 1997 of advanced mind control weapons against two military pilots over the central U.S. Some dangers and potential benefits of the emerging mind control technology are pointed out



Mechanisms for Physical Change and the Flow of Time

SPATIAL
SPATIOTEMPORAL
PHOTON
SPATIAL
PHOTON
MASS
L^3
MASSTIME
L^3T
L^2T
MASS
L^3
L^2T

$$(\Delta E)(\Delta t) + M \Rightarrow (M+\Delta M)\Delta t \Rightarrow M + (\Delta E)(\Delta t)$$

Flow of macroscopic time (observable photon interactions)

SPATIAL AND SPATIOTEMPORAL
"MASS"
MASSTIME
L^3T
MASS
MASS
MASSTIME
L^3T
"MASS"

Flow of microscopic time (via virtual photon interactions)

The photon interaction generates an observed quantum change and a discretized jump in the rate of time flow. A particle observably changes by only a single Δ t at a time. The background flow of time in which the jump in rate occurs, is created by the continual absorption and emission of virtual photons.

© 1994 T.E. BEARDEN

Figure 1. Mechanism that generates a mass's flow through time.

EXPLORE! VOLUME 9, NUMBER 2, 1999

Introduction and Background

In quantum field theory, there are four polarizations of photons.[1] Using 4-space and the z-direction as the direction of propagation, we have x- and y- polarizations where the 3-spatial energy of the photon is oscillating laterally, in the x- or y- direction. These are *transverse polarized* photons, as is any combination of the two. The third polarization is along the z-direction, which is a longitudinal polarization. In other words, the 3-spatial energy of the longitudinal photon cannot oscillate in the x- or y- direction, and so it is oscillating to-and-fro along the line of motion, z-. The fourth polarization occurs when the energy is frozen in all three spatial dimensions x-, y-, and z- and it cannot oscillate in any of those directions. In that case, the photon oscillates its energy in the t- direction, providing the t-polarized photon. We will later discuss how time is actually highly condensed energy.

In Minkowski 4-space, body operations are space-like, and are so treated in conventional materialistic physics. Mind and mind-operations are time-like, not space-like, even though they are totally electromagnetic in nature.[2]

As is well-known, all observation in physics is considered 3-spatial..[3] Mass is a 3-spatial concept, and we detect changes to mass (as, e.g., in the shift of electrons in the circuits of electrical instruments). So one may model the common physical observation mechanism as a *time-differentiating process* which *a priori* discards time-change and retains 3-spatial energy change.[4] That is, Minkowski reality is modeled in the fundamental units of L^3t. Physical observation (via the transverse photon interaction) is the process given by applying the operator $\partial/\partial t$ to L^3t, yielding an L^3 output. Hence mind and mind operations are excluded by the usual physics instruments and observation, which simply exclude the time domain in their outputs and do not "measure" it.

For this reason, physicists have erroneously considered mind to be "metaphysical" and nonreal. Indeed, most physicists to one extent or the other are materialists, and consider the "mind" to be nothing but the operations ongoing in a "meat computer." Nonetheless, in the time-domain the time is absolutely real, and it is completely electrodynamic in nature. There is no metaphysics involved, and the temporal domain—along with mind and mind operations—is simply an erroneously neglected area of physics. In present physics, the notion of mind is comfortably disposed of by imposing the use of the "observer" concept, with out ever specifying that the observer has a consciousness and a mind. Indeed, "observation" is only about what that "observer" perceives. Obviously, one has a dramatically crippled physics if one eliminates that nonobservable called "time." Similarly, one also has a dramatically crippled physics when one eliminates the mechanisms and physics ongoing in those time-like and dynamic "things" such as mind, that occupy time and function in it.

From this viewpoint, Western physics adheres to its 3-spatial measurement foundation only by ignoring the transduction of time-polarized EM changes into detectable longitudinal and transverse EM wave changes. In this aspect, present Western physics is severely self-crippled.

Time is totally electromagnetic and energetic in nature. The flow of time is not a separate external river on which a mass floats along like a boat drifting down the current of a great flowing river. Instead, the flow of time is generated directly on every mass by its total set of photon interactions, both virtual and ob servable. We have previously presented the exact mechanism for the flow of time. *[Figure 1]*


TRANSVERSE EM WAVE PLUS
PHASE CONJUGATE REPLICA WAVE
LONGITUDINAL EM SURGE WAVE
LONGITUDINAL EM WAVE PLUS
PHASE CONJUGATE REPLICA WAVE
(t)
TIME DENSITY WAVE
Oscillates rate of flow of time
about some average value
© T.E. BEARDEN 1994, 1995

Figure 2. Transduction of EM wave type by successive phase conjugate pairing.

Further, a photon is comprised of angular momentum, therefore of (energy)x(time). It transports both energy and time, not just energy alone. When absorbed by a mass, not only does it "energy-excitation" charge the mass, but also it "time-excitation" charges it, converting the former "mass" to "mass time". Rigorously it is *masstime* that emits a photon, not *mass*. So a mass moves through time in little spurts, by the continual macroscopic addition and subtraction of little Dt components. Further, in being driven through time, mass is continually altered to masstime (a quite different critter from mass), to mass, to masstime, to mass, etc.

In any masstime state, a myriad of tiny virtual photon interactions made of very tiny (DE)(Dt)'s interact with that same mass during that particular larger Dt of the masstime state (m+Dm)(Dt). Hence mass in its alternate masstime state has that state internally structured by its surrounding environment's interactions with it. The masstime state is internally structured energetically in its (DE) component, and also internally structured temporally in its (Dt) component.

A standard charged fundamental particle such as an electron, e.g., is not necessarily identical with another, when the internal structuring of its masstime state is considered. Further, by two papers by Whittaker,[5] interferometry of masstime states with either energy reactions or temporal reactions can yield observable effects and changes due to these neglected "hidden variables" in the electron's masstime alternative states. To engineer the mind and its operations directly, one must perform electrodynamic engineering in the *time* domain, not in the 3-space EM energy density domain. The direct engineering of time-like mind and mind operations—in all levels and all aspects—requires the use of *time-polarized photons and time-polarized EM waves*. This is the rarest form of electrodynamics, almost untouched by Western physicists.

One can either painfully produce such time-polarized photons and EM waves and directly irradiate a target mass with specific assemblies of them, or one can force the mass itself to iteratively transduce ordinary transverse EM waves first into longitudinally-polarized EM waves and then into time-polarized EM waves. Both will be discussed briefly.

In the West, it appears that the present author's discovery of mechanisms for producing time-polarized (scalar) EM waves [see *Figure 2*] and for transducing between wave polarizations has no precedent. [See *Figure 3*]. While scalar (time-polarized) photons are known in the literature,[1] the creation and use of time-polarized EM waves does not seem to appear in the Western physics literature.[6]

Wave transduction or *polarization transductions* are terms used by the author for the process of transforming an EM wave's particular polarization into another polarization type. Such transduction to other than transverse polarization forms is little known in the West. It appears essentially haphazardly in some experiments, usually without any recognition by the experimenters themselves. Significant transduction in experiments will also produce "strange" and unexplained anomalies in the instruments being used for experimental measurements.[7]

So most probably Western mind control researchers have not recognized the methodology and mechanisms[8] for transducing one type of EM wave polarization directly into another.[9] They continue to seek the "mind" in 3-space and hence in the brain, rather than in the time domain. On the other hand, it appears



Figure 3. Interference processes for transducing higher EM wave polarizations into lower polarization states.

EXPLORE! VOLUME 9, NUMBER 2, 1999

that the Russian KGB energetics[10] weapons scientists—particularly those in psychoenergetics[11]—have known and used methods of transducing one wave polarization into another, for at least two decades. It follows that those same scientists have very probably developed mind engineering and mind control via novel time-polarized EM wave means and a dramatically extended electrodynamics of the time-like mind operations.

In the present paper we briefly develop the wave transductions and the basis for mind engineering, including the specialized use of ordinary transverse wave (TW) EM spectra to force internal EM wave transductions and time-domain operations inside irradiated bodies, cells, and tissues. Through the mind-body coupling mechanism, these transductions of transverse EM waves can operate upon the mind and its deepest operations as well as upon the body, every cell, and every part of every cell.

Russian Mind Control Uses Higher EM Wave Polarizations

It is apparent that the KGB psychoenergetics weapons scientists know and use the full extended EM wave polarization range. As a postulation, one would expect our own weapons scientists to know and utilize the orthodox transverse wave (TW) EM for similar research and experimentation. However, in the West scientists are just beginning to realize the importance of a very general (and weaker) type of longitudinal EM wave (LW) polarization, as evidenced by the appearance of dozens of papers on "undistorted progressive waves" (UPWs, which are essentially imperfect LW s with TW residues remaining). The Los Alamos National Laboratory web site has a number of such papers—particularly by Rodrigues[12] and Lu—available for free downloading. UPWs have very interesting characteristics. If they were perfect longitudinal EM waves, they would have infinite energy and infinite speed. Since only imperfect UPWs can be physically made, their speed can vary from slower than the speed of light to faster than the speed of light. Their energy can also vary over a great range.

Another characteristic of UPWs that are reasonably good longitudinal EM waves, is that they pass readily through a large depth of water and mass, including through the ocean and the earth with only small interactions and losses. Yet by interfering two such beams of "high quality" UPWs at a great distance, then in the interference zone ordinary EM energy will rise directly out of local spacetime potential, as essentially shown by Whittaker[13] nearly a century ago. Russian weapon research facilities have weaponized these effects[14] for nearly 50 years, under rigid KGB control and operation. Nonetheless, even if using only ordinary TW waves, Western mind control researchers may get some fairly good results, brute-force-like, by using gross correlates between just the input irradiating TWs and the exhibited behavioral responses of the individual. The net input-output correlations can be determined, even though not taking into account the actual wave polarization transduction mechanisms ongoing inside the irradiated dielectric (or brain, or mind, etc.). However, Western researchers appear to have no knowledge of the exact mechanisms by means of which coherent time-like mind operations of a biological organism couple to the organism's 3-spatial body to provide the mental control loop. They also appear unaware of how the coherent 3-spatial behavior responses of the body couple back to the time-like mind to provide it with a sensory feedback of the body's responses.



Vacuum Engine: Working ST Demons

Internested patterns of spacetime curvatures

Structured Einsteinian spacetime

Maxwell Demons: EM hidden variables

Dynamic structures at all levels

Demons work at all levels

© 1997 T.E. Bearden

Figure 4. A spacetime curvature engine has myriads of small ST curvature components which act upon mass at all levels.

EXPLORE! VOLUME 9, NUMBER 2, 1999

General Relativity Aspects

Both these coupling mechanisms can be taken directly from general relativity, if one puts one's mind to it. However, unless the wave polarization transformations are known, it is difficult or impossible to apply the ordinary GR *directly*, since relativists usually concentrate upon spacetime curvature by altering 3-space energy density rather than by altering time-polarized "time-energy" density.

In applied general relativity, spacetime itself is an active medium. One speaks of a change in spacetime as a "spacetime curvature". Any curvature of spacetime in a local region directly performs continuous work upon any mass embedded in that region. Vice versa, any mass (or other concentration of energy) in a local spacetime continuously acts upon that spacetime to "curve" it.

So if one wishes to perform actions upon mass in a distant region, one may generate local curvatures of spacetime in that region, and these curvature "engines" will directly act upon the mass at all levels. *[Figure 4]* This is very different from energy propagation through space from one point to another. Now the "ordinary EM energy and actions" arise from every spatiotemporal point within the mass, at every level, and move upwards (from inside to outside). So we speak of specific forms of "templates" of nested spacetime curvatures formed and utilized to engineer mass "from inside out" as *spacetime curvature engines or vacuum engines*.

Use of vacuum (spacetime curvature) engineering[15] is a far more powerful form of engineering than is provided by energy propagation through space. As an example, it is easy to alter the quarks in a nucleon, using spacetime curvature engines and time-charging decay. Indeed, we have developed the mechanisms for cold fusion and the electronuclear interaction (formation of new nuclides) at feeble energy. An Invention Disclosure[16] on this work has been filed with the U.S. Patent Office, and formal patent applications are in preparation. Some information on these mechanisms and principles has been released[17].

Time as Dense EM Energy and a Strong Spacetime Curvature Agent

The advantage of using the time-polarized "time-energy" for spacetime curvature is that time is ordinary energy compressed by a factor of at least c^2—which, in the MKS system of units, is some 9¥10^{16}. Thus use of time-polarized EM photons and waves as ST curvature agents gives an amplification of 9 ¥10^{16} over the use of transverse-polarized EM waves for that purpose. In turn, the use of the strong EM force in ordinary TW waves as an agent of ST curvature is already a nominal 10^{40} times as strong as is the weak G force used as the agent of ST curvature.

The bottom line is this: For spacetime curvature effects, the use of the t-polarized domain provides amplification of some 9¥10^{56} greater than the weak G-force ST curvature agent usually considered in general relativity[18].

Western Science Remains Largely Materialistic

Ironically, most Western scientists are materialists and consider "mind" as a mystical and nonscientific concept. They tend to consider mind operations and functions either to be simply "meat computer" operations and functions, or at best to be very weak ordinary transverse-wave EM operations and functions in the brain and nervous system.[8] This serious self-limitation exists because in the body we *measure* only weak TW EM operations and functions correlated to biological behavior and brain operations. We simply do not know how to measure "mind operations" directly.


MIND DOMAIN
BODY DOMAIN
START
STOP
COHERENT MIND CHANGES (INTENT)
NO
YES
DIFFER?
COHERENT INTEGRATION IN MIND DOMAIN PRODUCES COHERENT OBSERVABLE MIND CHANGES
COHERENT ROTATIONS PRODUCE COHERENT TIME-LIKE VIRTUAL PROJECTIONS IN MIND DOMAIN
COHERENT ROTATIONS IN 4-SPACE PRODUCE COHERENT VIRTUAL 3-SPACE PROJECTIONS
COHERENT VIRTUAL ST ENGINES FOR COHERENT PHYSICAL CHANGES & BEHAVIOR
COHERENT INTEGRATION IN BRAIN/BODY PRODUCES COHERENT OBSERVABLE ST CURVATURE ENGINES
YES
NO
ZERO?
COHERENT BODY CHANGES PRODUCE OBSERVABLE CURVATURE ANTI-ENGINES

Figure 5. Mind-to body coupling and body-to-mind coupling.

EXPLORE! VOLUME , NUMBER 2, 1999

With no mind measurements possible and no instruments, it is understandable that Western science considers only the physical side of the mind-matter interface.

Presently our scientists do not measure the longitudinally-polarized EM wave operations and functions in the body and around it in nature. Few of them are aware that a maelstrom of such LW functions exist in the body and in all of nature in general. Presently only highly theoretical quantum field theorists seem to even be aware of the existence of scalar (t-polarized) photons, and even they are unaware of t-polarized EM waves. Certainly our scientists do not measure t-polarized EM waves in and around the body and in nature, nor do they make them in the laboratory. Apparently they have not studied such waves and their interactions with matter—living and inert—at all.

But it's even worse. In ignoring the time component transported by photons and EM waves, science has also erroneously omitted half of the excitation charging and excitation decay processes whenever a mass interacts with photons and EM waves. More on that later.

Brute Forcing Time Functions versus Fine Control Methods

Ironically, Western mind control researchers using transverse EM waves for mind control research, are using a brute force method of evoking and using vacuum engines (spacetime curvature engines) and a special form of general relativity, although they do not appear to realize it.

While KGB scientists also use TW EM "brute force" TW waves when necessary, they do "imprint" or "activate" those waves with the desired internal LW and time-polarized EM wave and photon structures required to directly perform the mind engineering desired. They also do not hesitate to use LWs and t-polarized waves overtly. So in blunt terms, Western compared to Russian mind control research is probably like comparing an automobile body shop with a fine surgical ward. Having long ago worked out all those "exact correlates" to the internal "information content of the field" is where the KGB scientists are at least 20 years ahead of the West.

The reason one can get mind and behavior results with the TW electromagnetics, while bypassing the real mechanism which uses t-polarized waves and photons, is due to (1) the very peculiar nature of the EM emission from a dielectric, and (2) what can be done by re-radiating that dielectric with its emitted spectrum, deliberately and very carefully altered in selected parts. We will return to that important feature later.

Polarization and Observability

As we stated, there are four photon polarizations and therefore there must be correspondingly four EM wave polarizations[1] The first three polarizations are the x-, y-, and z- spatial polarizations. The x- and y- polarizations are transverse polarizations and the z-polarization is a longitudinal polarization along the direction of propagation (along the z-axis, by standard notation). Simply put, we may visualize the transverse polarizations as rather like the wiggling of a fish's tail from side to side as the fish moves forward, or a whale's flukes up and down as the whale moves forward, or some combination thereof. We may visualize the longitudinal polarization as a sort of "repetitive accordion effect" along the line of motion of the wave. Usually the z- polarization is neglected in EM wave theory, although in recent years physicists have "rediscovered" longitudinal EM waves and are now intensely researching the use and characteristics of such waves.[12]



Energetics

NONLIVING SYSTEMS

LIVING SYSTEMS

Energetics

- *Nonliving systems*
- *Scalar Interferometry*
- *Action-at-a-Distance*
- *Quantum Potential*
- *Vacuum Engines*
- *Spacetime Structuring*
- *Material, Field Effects*
- *Nuclei, Lattice Changes*
- *Hidden EM Variables*
- *SWZ Effects*

Bioenergetics

- *Living Systems (Bodies)*
- *Cells, cellular changes*
- *Master Cell Control (Popp)*
- *Spacetime Structuring*
- *Disease Induction, Remission*
- *Action-at-a-Distance*
- *Quantum Potentials*
- *Scalar Interferometry*
- *Hidden EM Variables*
- *SWZ Effects*

Psychoenergetics

- *Living Systems (Minds)*
- *Thoughts, Memories, Emotions*
- *Conscious/Unconscious Minds*
- *Spacetime Structuring*
- *Species, Biospheric Minds*
- *Action-at-a-Distance*
- *Quantum Potentials*
- *Scalar Interferometry*
- *Hidden EM Variables*
- *SWZ Effects*

© 1996 T.E. BEARDEN

Figure 6. The three divisions of Soviet energetics and their characteristics.

EXPLORE! VOLUME 9, NUMBER 2, 1999

Unfortunately, in quantum field theory there has been a tendency to regard the t-polarized or "scalar" photon—where the local rate of time is oscillated—as unobservable. Oscillation of the local rate of time produces powerful oscillations of local space-time curvatures, due to the extreme energy density of time. Individually, the t-polarized photon tends to be unobservable. However, a *coherent sequential group* of such t-polarized photons, each individually in the virtual state with respect to the external observer, may simply integrate in its interaction with mass over a short time period into observable change because of the coherent integration of virtual spacetime curvatures into a larger, observable spacetime curvature.

Rotations and Projections in 4-Space

Relativistically, any velocity change in 4-space is a rotation. Any such rotation in the time-domain also creates a tiny projection component into 3-space. Any such rotation in the 3-spatial domain also creates a tiny projection component into the time domain.

Hence a sufficient series of coherent time-domain (mental) changes produces a coherent series of virtual changes in 3-space (the body), thereby coherently integrating into an observable energy change in the body. A sufficient series of coherent 3-spatial energy changes produces a coherent series of virtual changes in the time domain which coherent integrate into an observable time-domain change.

Solution to the Age-Old Philosophical Problem of Intent

This is in fact the solution to the age-old problem of *intent*, or how the nonmaterial (i.e., non-3-spatial and non-observable) mind induces a 3-spatial, observable energy change upon the 3-spatial body. It is also the solution to the problem of *awareness*; i.e., how the mind is aware of itself[19] and of the responses of the body. Together the two form a closed loop coupling of the mind and body. The time delay in the loop together with memory recall for comparison, creates the sense of "persistence" of self in time. This also creates the sense of being a "separate, closed being" (i.e., of separate persistence in time—in the living entity). The sense of "separation of self from an external world" is created by comparing those body-to-mind sensory feedbacks which are not correlated to the mind's previous feed-forward intent.

Time As Energy and Why It Is Very Dense Energy

In addition to the three spatial polarizations of photons and EM waves, there is a very, very useful t-polarization along the time axis. In this polarization, the 3-spatial energy is not oscillating at all. Instead, the time or time-energy is oscillating. Time can be taken to be energy compressed by at least c^2, so it has at least the same energy density as mass. In other words, one second is $9x10^{16}$ joules of time-energy (energy compressed into time). The t-polarized photon or EM wave is called the scalar photon or scalar EM wave, respectively.

To demonstrate why time can be regarded as energy, we need only point out that the choice of fundamental units in any physics model is totally arbitrary. We usually choose these units to ease the mathematical manipulation, ease our understanding, and simplify the ability to visualize or "grasp" the physics. However, if one wishes, one can build all of physics from a single fundamental unit—e.g., energy. In that case, one readily sees that time is a function of energy and only energy. Hence it is perfectly proper to regard time as energy, and to seek out what form the function takes in our normal system of units (say, the MKS system).



Lisitsyn's Report: Brain Code Broken

- THEORY DEVELOPED AND FITTED
- HYSTERESIS MEMORY LOOP
- CONTROLLED EM INDUCTION
  - IMAGES
  - SENSATIONS
  - PREDETERMINED EMERGENCE
- 23 EEG BANDS
  - UP TO 8.1 X 10^{20} HZ
  - 11 INDEPENDENT CHANNELS

© 1978, 1985, 1991 T.E. BEARDEN

S.K. Lisitsyn, "New Approach to the Analysis of Electroencephalograms," DDC Report AD73005, p. 16-25.

Figure 7. In the 1960s, Lisitsyn revealed Russian scientists had deciphered the human brain code.

EXPLORE! VOLUME 9, NUMBER 2, 1999

In that system, it appears that any change in time Δt can be taken as always a function of a corresponding change in energy ΔE, where $\Delta t \leq (\Delta E) \div c^2$ [1] from which it follows that $\Delta E \geq (\Delta t) \times c^2$ [2] For convenience, we take the special case where $\Delta t = (\Delta E) \div c^2$ [3] $\Delta E = (\Delta t) \times c^2$ [4].

Observation as Used in Physics Is Spatial

We note that all mind operations are time-like, i.e., they are comprised as scalar EM photon functions and scalar EM wave functions. Thus the mind is a very special kind of electromagnetic system, existing in the time domain, and thus "lost" by the stripping away of time in the ordinary observation process. Physical observation is essentially a time-differentiating mechanism applied to a 4-spatial change, or in terms of MKS fundamental units L and t, observation θ is $\theta = \partial/\partial t(L^3 t) = L^3$ [5].

Thus, as is well-known in quantum mechanics, physical observation is 3-spatial, and time is not a physical observable, even in theory. Since mind is time-like, it follows that mind is not a physical observable either, since discarding the time dimension also discards the mind. In short, one may also take physical operation as the mechanism that separates mind and body. To observe is to separate. We point out, however, that merely "separating and discarding" the time domain (as in physical observation of a single change) does not eliminate it, nor does it eliminate the single time-like mind change that may be involved in an intentional volition. The time domain certainly remains, even though only the 3-spatial intersection of the 4-spatial Minkowski change is given by physical mechanism and the resulting "outputs". So a series of coherently integrated "mental intent" changes introduced into the human body's overall servo-mechanism provides the continuing input. From there, ordinary physics will generate the resulting actions induced in the body by that servomechanism and its amplifying mechanisms.

Two Coupling Mechanisms Make a Closed Loop

This is the "mind-to-body" coupling mechanism. [See *Figure 5*] It is the mechanism whereby the mind is coupled to the body, and whereby mental intent is able to induce a series of physical inputs into the body servomechanism.

So the body's servomechanism then generates the responses of the body (including everything from chemistry to electrical changes to muscular movements, etc.). These responses are changes in 3-space.

The conscious mind is a *serial processor*, though extremely rapid. It produces the series of coherent intent inputs for volitional behavior.

The unconscious mind is a *massively parallel processor*.[20] It continually produces the vast series of coherent "unconscious intent inputs" for control of all the deeper processes in the body, beyond usual conscious awareness.

However, as the body moves or changes in 3-space, each resulting quantum change in body 3-space is also a slight rotation out of 3-space and toward the time axis. Hence it induces—in the "virtual state" in the time domain—a precisely correlated projection. The body's responses are in general coherent, so a coherent series of virtual state changes in the time-domain (in observation. So we may say *that the time-change remains in the virtual state, with respect to attempted physical observation of a single Minkowski 4-space change.*

Rotation, Coherent Integration, and Intent

Previously we pointed out that any change in a 4-space entity may be regarded as a rotation away from the "trajectory" of the entity. Hence each and every t-polarized change creates a very small projection into 3-space by its rotation slightly away from the time axis. All mind changes in the time-domain actually produce virtual 3-spatial projections in 3-space (in the physical domain). We define "intent" as the continued production of successively coherent mental changes, producing coherent virtual changes in the 3-space body system, with coherent integration of those 3-space virtual changes into observable 3-space energy inputs into the 3-space body system. Successively coherent mind-changes will produce successively coherent 3-space virtual changes. In short, coherent mind-changes will produce coherent integration of those 3-space virtual projections into an observable 3-space change. This is the creation of an ordinary 3-spatial energy change induced upon the 3-space body. In short, this is the mechanism whereby time-like mental intent is able to produce a series of coherent observable quantum changes in the physical body (as in the brain and nervous system).

The Body as a Servomechanism

From the standpoint of control theory, we may consider the body system to be a complex servomechanism system comprised of many subordinate servo systems with feedback and feedforward the mind realm) are created successively. In short, again we have coherent integration, this time in the mind or time domain. This produces "observable" changes in the time-mind domain, which are coherent with the body's 3-spatial changes actually performed. Thus the mind receives feedback directly from the physical movements and changes of the body. This is the manner in which the body is coupled back to the mind.[21]

By comparing the "intent" behavioral move that was "fed forward" into the body, with the return "response" move analog that was "fed back" from the body to the mind, the mind is able to determine errors and differences, and originate additional correctional commands.

Thus the entire mind-body loop is a closed-circuit system of feedforward and feedback, together with corrections. It also has multiple levels of such, infolded in the larger volitional levels. See again *Figure 4*.

This solves the age-old problem of the mechanisms for the mind-body coupling, intent, volition, conscious and unconscious functioning, sense of the external world, sense of the internal world, sense of "being in" the external world, etc.[22]

All This Is Included in Russian Psychoenergetics

This is the highly summarized basis for *psychoenergetics*, the KGB's division of energetics that deals with the mind and body coupling and functions, and direct engineering of (1) the mind-body coupling and (2) the mind operations directly. [See *Figure 6*] The KGB intent, of course, has always been to exploit this science for the degradation, killing, and control of human beings, including all humanity.

The Russians know full well that, if you looping.

Given the input from intent, ordinary servo theory will take it from there. Once a servo has an input, servomechanism theory describes the response of the

produce and utilize scalar EM photons and t-polarized EM waves, you can directly affect and engineer mind and mind operations at any and all levels. Western researchers, who know nothing of how to make

EXPLORE! VOLUME 9, NUMBER 2, 1999

time-polarized photons and time-polarized EM waves, do not yet know that. Consequently the Russians have developed a highly secret science of *directly* engineering the mind and its operations, including thought, images, perceptions, feelings, emotions, memory, and mind processing. Indeed, Lisitsyn[23] wrote quite specifically of this capability in the 1960s. [See *Figure 7*]

Western clandestine mind control researchers are apparently still slowly and painfully fitting TW EM irradiation correlates to induced or resulting mental and physical behavior responses. They seem unaware of the actual wave transductions occurring inside the body and mind, but are unwittingly inducing those transductions in hidden fashion anyway and in "brute-force input-response fitting" models.

These "fitted brute-force models" certainly can be very powerful, and certainly can produce the exact results shown in the experimental verifications of the fittings. However, they do not of themselves allow sophisticated design—for example—of the necessary time-polarized wave assemblies for engineering the entire human collective unconscious simultaneously, or for engineering the entire collective unconscious of all species on Earth (i.e., Gaia's collective unconscious), or even for precisely engineering the memory and knowledge base of an individual.

This fine research article will be continued in Part II with Russian Methodology, Waves and Wave Transduction, The Cellular Control

spacetime that is highly active. The mind is rooted in the time-domain and projects from that domain into 3-space. The body is rooted in the 3-space domain and projects into the time-domain. To "change" or "function" in one domain is automatically to function in the other. EM and gravitational phenomena are still modeled separately by human scientists, but not by nature.

3. In quantum mechanics, time is not an observable, but merely a parameter.
4. It is convenient to consider mass as a 3-spatial form of condensed energy.
5. E. T. Whittaker, "On the Partial Differential Equations of Mathematical Physics, " Mathematische Annalen, Vol. 57, 1903, p. 333-355;— "On an Expression of the Electromagnetic Field Due to Electrons by Means of Two Scalar Potential Functions, "Proc. Lond. Math. Soc., Series 2, Vol. I, 1904, p. 367-372.
6. A NERAC document search yielded some 16 good references on t-polarized photons, but not a single reference on t-polarized EM waves.
7. E.g., such previously inexplicable instrument anomalies have accompanied some excellent and rigorous electrolyte experiments at U. S. Navy research facilities at China Lake. For a description, see Melvin H Miles and Benjamin F. Bush, "Radiation measurements at China Lake: Real or Artifacts?", Proc. ICCF - 7 (International Conference on Cold Fusion—7, Vancouver, BC, Canada, Apr. 1998, p. 101. For a brief explanation of the anomalies, see T. E. Bearden, "EM Corrections Enabling a Practical Unified Field Theory with Emphasis on Time-Charging Interactions of Longitudinal EM Waves, " Explore!, 8(6), 1998, p. 7-16;— "Toward a Practical Unified Field Theory and a Deep Experimental Example," Proc. INE Symposium, Univ. Utah, Aug. 14-15, 1998.
8. Many U. S. researchers and journalists—and even many scientists—have wrestled with the problems of mind, intent, and mind-body coupling. Enumeration of those efforts would itself require an entire book. For an introduction into that domain, the reader is referred to the very determined exposé by

System, and other matters of interest. ♦

ABOUT THE AUTHOR

President and Chief Executive Officer, CTEC, Inc. Lieutenant Colonel US. Army (Retired). MS Nuclear Engineering, Georgia Institute of Technology. BS mathematics, Northeast Louisiana University. Graduate of Command & General Staff College, US. Army. Graduate of Guided Missile Staff Officers Course, U. S. Army (equivalent to MS in Aerospace Engineering). Numerous electronic warfare and counter-countermeasures courses. Tom is the leading advocate of scalar potential electromagnetics and the Fogal charge-blocking semiconductor: He is involved in alternate energy devices and scalar electromagnetic system prototypes. He has defined charge q as a coupled system of two components, advanced a mechanism for a vacuum engine, whereby the vacuums virtual particle flux is organized and used to energetically shape and manipulate matter and energy, and advanced a mechanism for a Bohm-type quantum potential, which theoretically allows the engineering of action at a distance in physical systems.

He is president of the Association of Distinguished American Scientists (ADAS), a life member of the Alabama Academy of Science, Emeritus member of the American Association of Physics Teachers, and has served on the Board of Directors of several associations and corporations. Tom is a guitarist, a retired aikidoist (Sandan, Yoseikan style), is happily married and has two sons and two daughters. He and his wife Doris live in Huntsville, Alabama where Tom is retired from aerospace, continues private research, and serves as a consultant to industry on Scalar

Cheryl Welsh in her very timely book, The 1950's Discovery of the Code of the Brain, May 1988, published on the Internet. Simply employ any Net search engine and search on the name Cheryl Welsh. A connection to the site and to Welsh's book will immediately be found Welsh's important compendium is highly recommended, giving the reader a "birds eye view", so to speak, of how Western scientists think and proceed regarding the subject of mind control by electromagnetic means. Unfortunately all journalists so far researching the area have not been aware that Western electrodynamics itself is seriously flawed, and that the great Russian advances in mind engineering and mind control are a result of their secret but complete revision and correction of Western electrodynamics to provide the basis for energetics. Until Western scientists revise their own decrepit old electrodynamics fouling the textbooks, they will never catch up to the Russian mind control developments springing from intense development programs that did that revision in the late 1940s and early 1950s.

9. An Invention Disclosure on these processes and enhancement embodiments has been filed with the U. S. Patent Office. Formal patent applications are also in preparation.

10. Energetics is a unified science of an extended electrodynamics possessing a hidden infolded general relativity inside the potentials, fields, and waves. It deliberately employs higher polarizations (longitudinal and tempic) of photons and EM waves to engineer action at a distance, use of specific patterns of spacetime curvature created at a distance, and direct engineering of either inert or living bodies. It also encompasses the direct engineering of time-like mind and mind functions. It is divided into three divisions, depending upon the nature of the target. Targeted against inert materials, structures, fields, and waves it is called "energetics. "Against living bodies, their fields, and biochemistry, it is called "bioenergetics." Against the mind and mind functions, it is called "psychoenergetics".

11. Psychoenergetics is that branch of energetics used to directly affect and engineer

electromagnetics processes.

REFERENCES

---

1. E.g., see Lewis H Ryder, Quantum Field Theory, Cambridge University Press, 2nd Edition, 1996, p. 147+. For an even deeper discussion of photon polarization, see F. Mandl and G. Shaw, Quantum Field Theory, Wiley, 1984, under the heading "Covariant Quantization of the Photon Propagator" in Chapter 5. Mandl and Shaw argue that the longitudinal and scalar polarizations are not directly observable, but only in combination, where they manifest as the "instantaneous" Coulomb (i.e. electrostatic) potential.

2. Nature is unified and not separated into the "separate" disciplines our science has prescribed. Thus the mind is also totally electrogravitational. The mind works not just with EM forms in an inert space, but also with spacetime curvatures in a the mind, memory, perception, thought, emotion, sensation, personality, and other mind functions of a living biological organism. It is usable against a single personal conscious (serial processor) mind and a single personal unconscious (massively parallel) processor mind In theory it is also usable against lungs collective unconscious mind and its functions, as well as the deeper unconscious for all species on Earth (i.e., against Gaia). We are speaking of physics, not metaphysics.

12. W A. Rodrigues Jr.. and J.-Y. Lu, "On the existence of undistorted progressive waves (UPWs) of arbitrary speeds $0 \leq v < \infty$ in nature," Foundations of Physics, 27(3), 1997, p. 435-5•08 A slightly corrected version is downloadable as hep-th/9606171 on the Los Alamos National Laboratory website.

13. E. T. Whittaker, "On an Expression of the Electromagnetic Field Due to Electrons by Means of Two Scalar Potential Functions, "Proc. Lond. Math. Soc., Series 2, Vol. I, 1904, p. 367-372. The paper was published in 1904 and orally delivered in 1903.

14. E.g., see T. E. Bearden, Fer-de-Lance, Tesla Book Co., 1986;—AIDS: Biological Warfare, Tesla Book Co., 1988;—Soviet Weather Engineering Over North America, 1-hour videotape, 1985,—Gravitobiology; A New Biophysics, Tesla Book Co., P.O. Box 121873, Chula Vista, CA 91912, 1991,—Energetics of Free Energy Systems and Vacuum Engine

EXPLORE! VOLUME 9, NUMBER 2, 1999

Therapies, Tara Publishing, Internet node www.tarapublishing.com/books, July 1997; — Energetics: Extensions to Physics and Advanced Technology for Medical and Military Applications, CTEC Proprietary, May 1, 1998, 200+ pages furnished to selected government agencies and key Congressional committee leaders.

15. E.g., see T.D. Lee, Particle Physics and Introduction to Field Theory, Harwood; New York, 1981. On P.383, Nobelist Lee points out that the microstructure of the scalar vacuum field (i.e., of vacuum charge) is not utilized. Particularly see Lee's own attempt to indicate the possibility of using vacuum engineering, in his "Chapter 25; Outlook; Possibility of Vacuum Engineering, " p. 824-828. With wave transductions and use of higher polarization EM waves, there are far better and more powerful ways to do vacuum (spacetime curvature) engineering.

16 T.E. Bearden, "Formation and Use of Time-Reversal Zones, EM Wave Transduction, Time-Density (Scalar) EM Excitation and Decay, and Spacetime curvature Engines to Alter Matter and Convert Time Into Energy," Invention Disclosure Document #446522, Oct. 26, 1998.

17. T.E. Bearden, "EM Corrections Enabling a Practical Unified Field Theory with Emphasis on Time-Charging Interactions of Longitudinal EM Waves, "Explore!, 8(6), 1998, p. 7-16; — "Toward a Practical Unified Field Theory and a Deep Experimental Example," Proc. INE Symposium, Univ. Utah, Aug. 14-15, 1998.

18. We have used the enormous energy density of time in our approach to a totally new kind of electronuclear interaction at feeble spatial energy. By use of a time-reversal zone (TRZ) in a fluid; the free H+ ions—which are free protons—can be induced to attract each other so tightly that the edge of the nuclear force region is entered. In that case the protons form a quasi-nucleus. When the TRZ decays back to a time-forward zone (TRZ), this new quasi-nucleus decays by changing quarks in one or more nucleons, thereby producing new nuclides. We point out that means "sense of existing in time".

20. The "unconscious" is totally conscious, just multiply so. The conscious mind can see only "a single slide in the slide projector at a time, " so to speak. When it "looks" at the ongoings and outputs of the unconscious, it "sees" millions of slides in the slide projector simultaneously. Hence it cannot distinguish "one and one only". So it just sees nothing, where by "nothing" we mean "no single distinguishable thing." It therefore is unable to consciously perceive the actions of the unconscious. When the unconscious wishes to communicate with the conscious (because of unresolved conflicts, etc.), it must produce large groupings integrated into "symbolic scenarios". Hence the symbolism of the unconscious, and the basis for therapeutic psychology and psychiatry. A "symbol", after all, is just a thing which can have many different meanings, all folded into one.

21. The mind continually has activities of its own, each of which produces coherent changes in the body to a much smaller degree. The interweaving of these "smaller self-changes" infolded inside the 3-space major intent changes also produces slight body changes, which in turn "project back" into the mind. This huge group of "infolded self-loops" produces the sense of "my body" being "volitionally directed or occupied" simultaneously with the "greater intent" loops which represent "my intentional actions with my body". Further; the body servo continually receives a myriad of inputs from its sensory systems, both from changes inside the body and from incoming changes from the external universe. This interweaving produces the awareness of "being in the external world" by having (i) changes whose feedback do not match mind-intent changes, and (ii) changes whose feedback does match mind-intent changes. This of course applies to both the conscious and unconscious levels. The purpose here is to demonstrate that there exists an actual physics of the living being, the mind as well as the body, and the coupling and interfiinctioning of mind and body.

this is actually a very high energy reaction; however; since the time-energy is used and is very, very dense, the amount of 3-spatial energy that must be used is very small. If this new mechanism holds, it represents a revolution in particle physics.

19. "Self-awareness" refers to be continually "refreshed" by time-delayed coherent feed-back inputs from the body to the mind; where these inputs compare to the recalled memory of the minds inputs to the body. In short, the time-delay coherence creates the sense of "existing in time". Awareness usually

22. The methodology also easily extends to include deeper interlays for the collective human unconscious mind and for Gaia—the collective unconscious mind level for all the species on earth.

23. S. K Lisitsyn, "New Approach to the Analysis of Electroencephalograms, " in Problems of Bionics— (Selected Articles), Defense Documentation Center Report AD 73005, date unknown, p. 16-25. Available through the National Technical Information System (NTIS).

Mind Control and EM Wave Polarization Transductions, Part 2

©Copyright 1999 by T.E. Bearden, USA

This article continues on with T.E. Bearden's article, Part 1 of which was published in Volume 9, #2 of Explore! for the Professional. Because we feel that Col. Bearden's caution below is so very important we are repeating its publication in all parts of this article.

Special Note

This article refers to experimental research techniques which can be detrimental or lethal in the hands of any but highly skilled, qualified experimental scientists proceeding under proper laboratory safety procedures. The purpose of this article is strictly for information to properly qualified and authorized scientists in certified laboratories. We do not propose or condone any use of these procedures for non-approved practice of medicine without a license. Neither the publisher nor the author are responsible for accidents or outcomes in the use of these experimental procedures and techniques. Any researcher who performs these procedures and experiments is acting on his or her own volition, and is solely responsible for insuring safety, qualifications, and legality of the acts and their results. We neither suggest nor condone unauthorized experimentation on human subjects. Such is a criminal violation of the constitutional rights of the subject under Federal and State laws, and is both illegal and immoral.

A Strategic Threat Completely Unrecognized by the West

The Russian methodology leads directly to rather mind-bending, extended capabilities. KGB psychoenergetics scientists seem fixed on an eventual goal of directly engineering Jung's collective human unconscious, thereby converting the entire human species into a sort of "ant" species. In short, they seek to engineer what they regard as "perfect communism and perfect order" directly in the entire species. *Figure 8* indicates the direct connection of every human's conscious and unconscious mind to the collective species unconscious and to Gaia, the collective unconscious for all species on Earth. Since time is internally structured and layered, it follows that time-like mind levels are also internested and layered.

This appears to be a significant strategic threat, *well along in its development*, that our scientific and intelligence communities have completely failed to recognize.

The direct engineering of the entire human collective species is a doable.[1] It is going to be done, whether we like it or not. In that race (which may eventually determine whether or not we retain any personal freedom at all), the "democratic" nations are woefully behind. In fact, the West has not even realized there is such a new kind of "arms race" for dictatorship and control of the "collective species mind" and we have already almost lost it. The West has not yet even developed the overall theory of psychoenergetics.

Waves and Wave Transductions

A pure longitudinal EM wave (LW) would have infinite energy and infinite speed. In practice, one can only approach this perfect LW wave, and one always has transverse residues remaining. Hence the "imperfect" longitudinal EM waves we can make in suitable equipment and techniques, are known as "undistorted progressive waves" (UPWs). The UPWs may have velocity far greater than the speed of light, or less than the speed of light. So the speed v of UPWs can vary as

$$0 < v < \infty \qquad [6]$$

The Russians also know that, when a nearly-pure longitudinal EM wave interacts with matter (it usually doesn't interact very much, and has a low reaction cross section), the mass immediately adds the phase conjugate replica to the interacting LW portion, regardless of frequency, thereby transducing the input LW interactions into scalar (time-polarized) EM interactions.

One transduces from TW to LW to Scalar EM via iterative phase conjugation. One transduces from scalar EM to LW to TW via iterative interferometry. It took the present author 20 years to discover this simple thing; we now have filed an invention disclosure on the process and embodiments for performing it, and will be following with formal patent applications. Let TW = transverse EM wave, LW = longitudinal EM wave, and TDW = time-density EM wave (another name I use for t-polarized or scalar EM waves, since the density of time-energy is what is varying). Let (I) = interfering with, PCR = phase conjugate replica wave with a coupled set of parentheses enclosing the type of wave. The rules for wave type transduction are:

$$\text{TW} + \text{PCR(TW)} \Rightarrow \text{LW} \qquad [7]$$

$$\text{LW} + \text{PCR(LW)} \Rightarrow \text{TDW} \qquad [8]$$

Going the other way, the rules are:

$$\text{TDW (I) TDW} \Rightarrow \text{LW} \qquad [9]$$

$$\text{LW (I) LW} \Rightarrow \text{TW} \qquad [10]$$

In EM smog (dense EM signals, even though very weak), there is increased nonlinear multiwave interactions, both interferometric and phase conjugative. So in such EM smog there exists an increased, non-negligible component of LW and TDW irradiation, formed by the above transduction interactions in the irradiated living cells and bodies. This latter part accounts for many of the long term effects which show up in "correlative" studies, but which do not show up in the normal limited-frequencies TW experiments produced by so-called "physical experiments."

The standard EM bioeffects manner of experimenting uses a theoretical model of simple, direct energy deposition by means of absorption in cells and tissues. Now we must utilize an "open system" throughout the body dielectric in which higher polarized EM energy (either LW or t-polarized) travels readily throughout all areas of the body.

EM Bioeffects and Wave Transductions

In the EM bioeffects experiments to date, there has been absolutely zero control of the internal transductions, and there has been no consideration of them. Almost all transductions of TWs into LWs will immediately result into transduction into TDW and time-excitation charging of the cells and all their internal components. These time-excitation charges (excited states of time-charging) will then slowly decay, emitting longitudinal EM waves in the process which travel throughout the body. These emitted LWs interfere with each other and the LW processes in the body, producing low level TW "noise jamming" of the cellular processes and—most especially—of the deep cellular control system of the body. The latter system functions by means of LWs and TDWs. Long-term effects of such "noise jamming" of biochemistry reactions and the control systems of the cells and body, can lead to degenerative diseases such as arthritis, atherosclerosis, Alzheimer's disease, heart disease, cataracts, tumors, leukemia, somewhat accelerated aging, immune system weakening and depressing, etc. As the body's natural defense and regeneration ability weakens, opportunistic infections further add to the degeneration.

It was shown by Whittaker in 1903 that any scalar EM potential is comprised of a harmonic series of bidirectional longitudinal EM wavepairs. [See *Figure 9*] Each longitudinal EM wave pair in the harmonic series is a phase conjugate pair. Unknown to Whittaker, that "LW phase conjugate pair" is actually a time-polarized EM "photon" structure, containing a phase conjugate LW photon substructure. So staid old "voltage" (potential) is comprised of a harmonic series of time-polarized EM waves!

The corresponding "t-polarized photons" are actually spin-4 *supergravitons* comprised of coupled antipairs of LW "photons". Each LW photon is a spin-2 *graviton* comprised of a coupled TW photon-antiphoton pair. Each TW photon and antiphoton in the coupled pair has spin-1. The couplet, being the longitudinal "photon" or graviton, thus has spin-2. And so on.

In 1904, Whittaker showed that any EM field or wave pattern can be decomposed into two scalar potential functions. By applying Whittaker 1903 decomposition to each scalar potential function, any EM field or wave has an enormously rich internal structure, comprised of scalar potential functions in interference. Each scalar potential function is comprised of time-polarized EM waves (made of spin-4 supergravitons). Each time-polarized EM wave is further comprised of bidirectional longitudinal EM wavepairs. Each longitudinal EM wave is further comprised of phase-conjugate pairs of transverse EM waves. Each transverse EM wave is further comprised of two scalar potential functions, each of which is in turn comprised of an infinite harmonic series of time-polarized EM waves, and so on *ad infinitum* and *ad nauseum*. Obviously all EM potentials, fields, and waves have an enormous "internal structure" or internal "information content of the field".

The Cellular Control System Uses t-Polarized EM Photons and Waves

The master cellular control system (MCCS) in the body utilizes these photon-gravitons, their corresponding EM wave polarizations, and transductions between them. By the use of very powerfully condensed gravitons and supergravitons, it is able to utilize small but highly significant direct curvatures of spacetime in precise patterns. In short, it utilizes general relativistic spacetime curvature engines, rather than "EM photon signals", to accomplish its control of the cells and their processes. It does not merely send a "signal" and hope the cell itself acts upon it. Instead, it sends an "engine" which alters the local spacetime in which the cell and all its components are embedded. This "local ST curvature engine" then physically works directly upon the cell and all its parts, to alter the cell according to the specific "template" of the engine.

This is the direct application of the Wheeler's simple statement of general relativity: *Mass (trapped energy) acts upon spacetime to curve it, and curved spacetime acts upon mass to change it.*

Popp's "ordinary photon" study of this cellular control system[2] therefore will detect the coherent ordinary TW photon residues which result from the photon polarization transductions occurring from the actions of the ST curvature engines upon the cells.

Cellular division, biochemical processes, growth and growth control, cell differentiation and dedifferentiation, etc. are all controlled by the MCCS or one of its subsystems, using spacetime curvature engines. The ordinary TW electronic activity our biophysicists detect and correlate are simply the intermediate components of the actual ongoing polarization transductions.

The Cellular Control System Uses EM Time-Energy

One important subsystem of the MCCS controls the immune system's functions, including the deepest and most subtle functioning performed by all elements of the immune system. This system has been rather intensively studied, but since our biophysicists have not possessed the full electrodynamics utilized, only the correlated residue of normal TW EM waves and photons have been recognized and studied. Hence Western biophysics is in its very crude infancy.

Incorporation of the total wave and photon polarizations, together with their transductions, will eventually present a revolution in both biomedicine and biophysics. Unfortunately, presently our entire medical community is very firmly entrenched in only ordinary TW EM polarizations and ordinary biochemistry. Our scientists thus are studying less than 1% of the functioning of the living organism.

As an example, since Western scientists have no knowledge or research into the time-polarized mind domain and mind-body coupling, the mystery of the *placebo effect*—in which the mind has been verified to produce actual physical effects – will indefinitely remain a mystery.[3] As one result of that "crippling" of our medical theory, medical experimenters have to deliberately drive experiments on drug effects, etc. beyond the "mind's own threshold" of physical effect. In short, they have to drive the experimental results over and above the results being accomplished by the placebo effect. They must perform valid placebo control experiments, and subtract the placebo component results from their own experimental results, to determine the "delta" induced purely by the drugs.

The Regenerative Subsystem

Another important subsystem of the MCCS controls the *regenerative system* of the body. The regenerative system has various mechanisms, including growth control, differentiation and dedifferentiation of cells, etc. Becker's portrayal of the regenerative system is shown in *Figure 10*. One of its most important functions is healing and restoring damaged or diseased cells. It does that by a most remarkable process.

This system has been very poorly studied, mostly by Becker[4] *et al.*, although there is still sporadic, ill-funded, and ill-planned research on regenerative effects from time to time.[5] Becker and his colleagues came closest, and—considering the severe limitations of the orthodox U(1) EM model available to them—Becker's work is particularly revolutionary. He demonstrated beyond question that simple DC potentials could generate cellular differentiation and redifferentiation, and produce results at global sites in the body and not just at the local injury sites where the DC potentials were applied.

Becker was nominated for a Nobel Prize for his Herculean efforts and remarkable results. For his trouble he was hounded, his funds were withdrawn, and he was forced to retire at an early age in his 50s. His biggest "heresy" was to bravely point out that power line radiations had deleterious effects upon biological systems, and to testify to it in a series of hearings and court cases where a very powerful electrical power industry essentially ran rough shod over science and the public.

Organized Science Is Highly Politicized and Imperfect

It is not only politicians that are "bought and paid for" by powerful vested financial interests. In organized science, precisely the same arrangement holds true. Scientists are no better or no worse than any other segment of humanity. A surprising percentage will produce the results desired by their benefactors, if provided with cushy jobs, good income, prestige, and secure positions.

It has been said that money is power. It has also been said that power corrupts, and absolute power corrupts absolutely. In the scientific community, as well as in the political community, this "great corruption" by great financial power has been elevated to an art form. Simply examine the funds made available to scientists. There is not enough for all the scientists, so it is fiercely competitive. If the scientist does not get grants (e.g., a would-be professor at a university), he does not bring in extra money to the university. He cannot get his graduate students funded, so his own innovative (read: heretical) research is thwarted. His papers are rejected by the journals, and before long he has no funded position in science. If lucky, he will be employed in the grocery store or the butcher shop.

Every bit of funding available for the scientists to compete for (and apply for grants) already has firmly fixed controls of exactly what research can be done with that money. The "science" that will be applied is already formulated. That and only that can be done. It is a tribute to the dedication and resourcefulness of our working scientists themselves, that anything innovative at all gets done.

One can have a very fine scientific career, tenure as a professor, get one's graduate students funded, get one's papers published in prestigious journals, win awards and achieve stature and prestige, if one just plays the desired game prescribed by the "old boys schools" in control of almost all the scientific funding. Yes, one can permissibly move the decimal point in the present models a bit, and be rewarded handsomely for doing so. But one is damned if one attempts any serious change or overthrow of obsolete scientific models and practices favored by the "system".



Figure 8. Nested levels of consciousness and unconsciousness. The mind levels contain the "life" and "mind" dynamics.



That is precisely why all our universities continue to teach a terribly flawed electrodynamics that is a caricature with at least 32 major foundations flaws in it.[6]

And that's why the organized Western scientific community has betrayed the taxpayers who largely fund its research. In short, the scientific community fiercely enforces dogma, suppresses innovation, and has denied the U.S. the very defense we need to survive against our pressing enemies who have not been so scientifically dogmatic.

Microwave Radiation of the U.S. Embassy in Moscow

Because of the strongly enforced adherence to the insane foundations errors in classical electrodynamics, our scientists still do not comprehend the decades of so-called "microwave radiation" of personnel in the U.S. Embassy in Moscow.[7] All diseases and health changes produced in those personnel were in *field-free areas* (i.e., where the potentials were persistent and unchanging, with no gradients etc.)[8] No one even thought to look at the "inner longitudinal EM phase conjugate biwave composition" of those potentials, where they would have found the Whittaker internal bidirectional longitudinal EM wavepairs and the internal time-polarized EM waves. They would also have found the infolded, very powerful general relativity: the spacetime curvatures deterministically formed and being utilized to directly alter the irradiated cells and their constituents.

Instead, government-funded studies did a rather straightforward "force field" analysis, and concluded that, since there were no fields there, it could not have been the microwave radiation.

Elementary statistics would immediately indicate a different conclusion: The diseases and health changes were 100% correlated to the presence of potentials, and 100% anticorrelated to the presence of fields. Hence it was the field-free potentials that had to be inducing the diseases and health changes. If it were NOT the radiation at all, then some changes would have occurred in personnel in areas where fields were *present*, as well as in areas where fields were *absent*. Since this did not occur, such a premise is destroyed by self-contradiction. In short, the data actually proved (i) it was indeed the radiation that was causing the diseases and health changes, and (ii) further, it was the field-free potentials that were the culprit.

That this elementary statistical conclusion eluded our scientific community and our government community, is absolutely inexplicable.

Three U.S. Ambassadors eventually died of diseases induced by their exposure to the Embassy radiation. Ironically, Kaznacheyev[9] had openly released some of the results of thousands of Soviet military experiments showing that any kind of cellular disease or disorder could be induced in targeted cells by novel EM radiation emitted from diseased or damaged cells. Apparently no one in the West deciphered the mechanisms involved in Kaznacheyev's epochal work.



The Structure Is:

- A harmonic set of longitudinal phase conjugate wavepairs.
- In each wavepair the two waves superpose spatially after detection, but travel in opposite directions.
- The convergent wave set is in the imaginary plane, and hence is not observable. It is EM energy incoming to the potential (dipolarity) from the time domain.
- The charge's spin is 720 degrees, 360 in the real plane and 360 in the imaginary plane.
- Hence the charge receives the complex convergent EM energy, transduces it into real EM energy, and emits enormous energy at the speed of light in all directions -- which includes bidirectional pairs in 3-space (after the reaction, being after "observation").
- This produces the fields and potentials from the "source charge or dipole."
- Mandl and Shaw argue that the scalar (time-polarized) photon and longitudinal photon are observable only in similar pairs, which then makes the instantaneous scalar potential. Thus their quantum field theory work strongly supports the "negative resistor" interpretation of the scalar potential and our solution to the source charge and source dipole problem.

Figure 9. Infolded longitudinal biwaves (time-polarized EM waves)

composition of a scalar potential.

EXPLORE! VOLUME 9, NUMBER 3, 1999

The Present Situation in Western EM Bioeffects Research

Our scientific community has not even *designed physical experiments* to validate long-term EM bioeffects of the kind caused by induced wave transductions and long-term effects inside the absorbing human cells and in the body's regenerative and immune systems. Western science has no knowledge of these technical internal "wave polarization transduction" mechanisms. Yet the basis for such mechanisms has existed in the hard physics literature for decades. Leading EM bioeffects researchers seem totally unaware of small reaction cross sections inside the body cells and tissues for the transduction of transverse EM signals into LW and t-polarized EM signals. Conventional Western researchers have not investigated it, and often will not believe it when it is pointed out to them along with the supporting basis in the literature.

A major part of the mainline "EM bioeffects" community, of course, seems comfortably funded largely by the power industry etc.[11] The record is clear that this dominant, well-funded group has little or no intention of "finding" anything that will question powerline radiation safety and upset their cushy positions.

In fact, leading bioeffects researchers have pointed out this deliberate biasing of EM bioeffects as a research area. Quoting Dr. Andrew A. Marino, one of the great pioneers in the area of EM bioeffects[10] and powerline radiation assessment.[11]

"Neither scientists nor the public can rely on power-industry research or analysis to help decide whether powerline electromagnetic fields affect human health because power-industry research and analysis are radically misleading."

Dr. Marino then gives the specific details to prove it, and he shows specifically how they slant and mangle their experiments and interpretations of the results, to do it. If the major financial interests cannot *scientifically* destroy determined, honest researchers such as Marino and Becker, they do not hesitate to attempt to destroy them in lawsuits.

The "Diffusion Mixmaster" at All Body and Cellular Levels

Every mass and all its particles are in a violent energy exchange with the active vacuum. A human body and every part of it is in a continual exchange of EM energy with its environment(s), including transverse, longitudinal, and t-polarized (scalar) EM energy exchanges. Further, within the dielectric body there is a sort of intensive "diffusion" of special kind, actually due to iterative phase conjugation and iterative interferometry of the dense signals environment impinging upon it. This internal "diffusion" and transduction (iterative multiwave phase conjugation and iterative multiwave interferometry) thoroughly "mixes up and transduces" one type of EM wave or signal into the other, including many of the body's own TW, LW, and TDW signals.

Continual or sustained TDW exposure (irradiation by t-polarized EM waves) charges the body and its particles with time-excitation charging, something which has been erroneously omit-


Becker's theoretical control system governing regeneration*
Trauma Producing Tissue Loss
Local cellular effect
Local nerve effect
CNS effect
Alterations in hormone pattern (prolactin)
Alterations in local DC field pattern
Local electrical effects
Local and systemic pools of target cells
Dedifferentiation into primitive mesenchymal cells
Phase I
Blastema formation
growth
Phase II
Redifferentiation into required cell types
Restoration of body part or tissue

*Becker & Spadaro, "Electrical stimulation of partial limb regeneration in mammals," Bul. N. Y. Acad. Med., 48(4), May 1972, p. 629.

Figure 10. Becker's model of the Regenerative system of the body.

ted in physics, but is true nonetheless. Inexplicably, physicists just ignore what happens time-wise when a mass absorbs a photon. We have covered that elsewhere.

So inside the body dielectric, there is a "diffusion mix" correlate of any and every type of the waves, to any or all of the exchanges, plus the additional internal interactions of the body in its TW, LW, and scalar EM wave transductions. There is a one-to-one correspondence to any one of the three types of polarization waves (transverse, longitudinal, and scalar) and everything going on anywhere in the body.

Note that the type of LW we are using is actually made of phase conjugate pairs of transverse EM waves, so its "photons" are made of photon/antiphoton pairs. That is, our longitudinal EM wave has an internal TW structure, and the LW wave is comprised of spin-2 *gravitons*. Our longitudinal EM wave has an internal structure, and it dramatically differs from the LW used by the U.S. scientific community which ignores wave, field, and potential infolded substructures. Our LW (which seems to be what the Russians use) is also a gravitational wave because it is comprised of oscillations in its distributions of spin-2 photon/antiphoton pairs (i.e., *gravitons*).

The type of t-polarized (scalar) EM wave we are using is a phase conjugate coupled pair of the specialized electrogravitational (EG) LWs. The "t-polarized photons" comprising this t-polarized "EM" wave are comprised of spin-4 *supergravitons*. These are, I believe, what the KGB energetics weapons scientists use also. By iteration, we can go into as deep an internal multilevel structuring of EM and EG waves, of any type, via methods shown by Whittaker.[12]

Now let us examine a body as a dielectric, sitting there in its exchange, in relative equilibrium. It turns that every tiniest piece of a dielectric participates in any emission from it[13]—even the emission of a single photon, graviton, or supergraviton. Well, it *would* so participate, due to the special sort of correlated diffusion and interferometry and phase conjugation that we pointed out. Anything that escapes (is re-emitted) from the body, has been through this "diffusion wringer". It has escaped from each and every internal part of the body.

Novel Signatures in Body-Emitted EM Radiation of Any Polarization

A single photon or wave emitted from a dielectric carries in its internally structured time component a *template* of the exact internal time structuring of every part of the dielectric emitting that photon. It carries in its internally structured energy component a *template* of the internal energy structuring of every part of the dielectric emitting it. An emitted EM wave, being a collection of emitted photons and photon structures, thus carries the same internal structuring of both its transported energy and its transported time.[14] Western scientists do not use the internal



Adjusting broadband signals bandwidth and amplification

Using an amplified replica of the body's own dense, broadband signal complex to irradiate it, producing deeply-penetrating and precise longitudinal EM wave sets that pump cells and reverse cellular disease and damage

Figure 11.

structuring of photons and EM sine waves, have no instruments for that, and so do not know it. The Russians know it,[15,16] use it, and have developed sophisticated instruments for it for the last 30 years or more.

Shortly we will postulate how conventional scientists experimenting with mind and behavior control electromagnetically might utilize an immediate consequence of the fact that the specific emission from a body at any time—whatever type of wave component we look at—is a total correlate to all that body's internal functions, its energy exchanges with its environment, its states, its mental states and conditions, etc.

And we accent that the coherently integrated intent-changes in that body from its coupled mind's operations are also in the substructure of photons and EM waves emitted from the living body into its environment.

How Western Mind Control Scientists Might Proceed

Conventional scientists would ignore scalar photons and waves, determine the TW spectrum, and then slowly and painfully correlate that to the various physical, mental, and emotional things. That's the way they would *have* to do it, since apparently they use only standard electrodynamics. They can in fact do this via brute force, because that emission TW spectrum is of waves escaping from the entire "diffusion machinery" mixmaster in the body dielectric. It does contain all those integrated *mind-intent* 3-space correlates as well as the ordinary body 3-space energy correlates.

Anyhow, in envisioning Western procedures, the test body would be sitting there, in its normal (let's say fairly normal and quiet) EM environment. [See *Figure 11*] Let's assume this body is not sick, but is healthy and normal. Its emissions are a part of its equilibrium condition. It follows that the totality of its TW emissions is correlated to the sum total of everything that interacted with the body, plus its own internal reactions, including from mind-body coupling. Indeed, everything that has ever happened to that entity—physically, mentally, emotionally, etc.—has internal correlates infolded inside the emitted transverse EM wave spectrum.[17]

So first the scientists would simply measure the full environmental TW spectrum down to very tiny levels in all frequency bands possible—everything that is coming in to the body from its environment. They would probably perform the experiments in a triply-shielded Faraday cage, so the external environment outside the cage contributes very little transverse EM wave noise (perhaps some Schumann resonance). Magnetic wave shielding and ELF shielding is something else again, and longitudinal EM wave shielding is in general not possible unless longitudinal EM waves are employed in the shielding. But a "quiet external TW environment" enhances the isolation and measurement of the specific TW signal transforms the Western experimenters would be seeking.

Then they would measure everything likewise that the body is *emitting* when in that environment. That is the "zero reference" or "normal reference" level. They would measure every aspect: frequency, amplitude, phase, wave shape, modulation, etc.

Probable Experimental and Measurement Techniques

Next they would selectively irradiate the body with specific signals, frequencies, waveforms, etc. They would begin by using portions of the same frequencies that are being emitted from the body in the "zero reference" environment. They would insure that the returned signal was of higher amplitude than the usual signal being emitted by the body at that same frequency and type.

They would consider the body dielectric as a "ship with portholes". Light (EM transverse wave energy) coming out of the portholes has originated and adapted from everywhere inside the ship and its operations. When the experimenters reinsert energy through one or more portholes, they are interested in determining precisely which operations inside the ship are affected. So the body physiological functions are also heavily instrumented.

By feeding back in the exact EM pattern and magnitude escaping the body dielectric through a single porthole, one "nullifies" that part of the emission by producing a net equilibrium in that component. This will in turn produce changes elsewhere in the spectrum emission from other portholes, and this can be measured. It will also produce "stress changes" in specific portions of the body dielectric, and in the heavily instrumented body these physiological, chemical, electrical, etc. changes can also be detected. Monitoring of the skin conductance, e.g., indicates the level of stress, and EEG monitoring with sophisticated instrumentation can indicate something of the brain wave states.

In short, the necessary measurements from which to construct specific correlates can be performed, recorded, and later analyzed.

This article will be concluded in Volume 9, #4 with Improving the Methodology, Further Phenomenology Experiments, Rejuvenation and other matters. ◆

ABOUT THE AUTHOR

President and Chief Executive Officer, CTEC, Inc. Lieutenant Colonel U.S. Army (Retired). MS Nuclear Engineering, Georgia Institute of Technology. BS mathematics, Northeast Louisiana University. Graduate of Command & General Staff College, U.S. Army. Graduate of Guided Missile Staff Officer's Course, U.S. Army (equivalent to MS in Aerospace Engineering). Numerous electronic warfare and counter-countermeasures courses.

Tom is the leading advocate of scalar potential electromagnetics and the Fogal charge-blocking semiconductor. He is involved in alternate energy devices and scalar electromagnetic system prototypes. He has defined charge q as a coupled system of two components, advanced a mechanism for a vacuum engine, whereby the vacuum's virtual particle flux is organized and used to energetically shape and manipulate matter and energy, and advanced a mechanism for a Bohm-type quantum potential, which theoretically allows the engineering of action at a distance in physical systems.

He is president of the Association of Distinguished American Scientists (ADAS), a life member of the Alabama Academy of Science, Emeritus member of the American Association of Physics Teachers, and has served on the Board of Directors of several associations and corporations. Tom is a guitarist, a retired aikidoist (Sandan, Yoseikan style), is happily married and has two sons and two daughters. He and his wife Doris live in Huntsville, Alabama where Tom is retired from aerospace, continues private research, and serves as a consultant to industry on Scalar electromagnetics processes.

REFERENCES

1. *In fact, it simply applies in the laboratory that method that is already used by species for the so-called "directed evolution" component of evolution. The exact mechanisms for directed evolution also arise naturally in the new approach. Directed evolution is required; e.g., no reptilian species could have evolved slowly into a bird. As it started slow changes, it would have not been able to fly or to run, and would have been simply destroyed immediately by predators. Instead, such evolution occurs in a single jump in a species hard-pressed for a lengthy period. In the evolution of birds, one day every reptile egg that hatched, now hatched into a complete and functional bird with light bones, feathers, etc. A continuing debate (with perhaps more emotion than science) continues to this day on directed evolution. But it is real, and the mechanism can readily be generated (we've already done the gist of it).*

2. *Fritz Albert Popp, "Photon Storage in Biological Systems," in Fritz Albert* Popp et al, *eds.*, Electromagnetic Bio-Information: Proceedings of the Symposium, Marburg, Federal Republic of Germany, Sep. 5, 1977; *Urban & Schwarzenberg, Baltimore, 1979, p. 123-149;—"On the coherence of ultraweak photoemission from living tissues," in* Disequilibrium and Self-Organization, *ed. by C. W. Kilmister, D. Reidel, Hingham, MA, 1986;*—et al., *"Physical aspects of biophotons,"* Experientia, *Vol. 44, 1988, p. 576-585;—"Biophoton emission: New evidence for coherence and DNA as source,"* Cell Biophys., *Vol. 6, 1984, p. 33-52. See particularly Fritz Albert Popp, Ke-hsueh Li, and Qiao Gu, Eds.*, Recent Advances in Biophoton Research and its Applications, *World Scientific Publishing Co., New York, NY, 1992.*
3. *With novel use of EM time-energy to curve spacetime, the physical actions of the "placebo effect" are due to the use of such "spacetime curvature engines" to produce actual physical effects—at least temporarily —in the cells and throughout the body's chemistry, physiology, etc. Experimental detection of these physical effects are well-established in the orthodox medical literature.*
4. *For example, see particularly R. O. Becker, "The direct current field: A primitive control and communication system related to growth processes,"* Proceedings of the. XVI International. Congress of Zoology, *Washington, D.C., Vol. 3, 1963, p. 179-183;— "The direct current control system: A link between environment and organism,"* New York State Journal of Medicine, *Vol. 62, 1962, p. 1169-1176;—and D. G. Murray, "A method for producing cellular dedifferentiation by means of very small electrical currents,"* Trans. N.Y. Acad. Sci., *Vol. 29, 1967, p. 606-615;—and Joseph A. Spadaro, "Electrical stimulation of partial limb regeneration in mammals,"* Bulletin of the New York Academy of Medicine, *Second Series, 48(4), May 1972, p. 627-64.*
5. *E.g., a popular discussion is given by John Travis, "Starting Over: Some Animals can regenerate limbs or even most of their bodies. How?"*, Science News, *152(18), Nov. 1, 1997, p. 280-282. For a typical technical paper, see Jeremy P. Brockes, "Amphibian limb regeneration: Rebuilding a complex structure,"* Science, *276(5309), Apr. 4, 1997, p. 81-87.*
6. *I have one viewgraph which lists those 32 major flaws in electrodynamics. Further, leading theorists (Evans, Crowell, and others) in the Alpha Foundation's Institute for Advanced Study (AIAS)—of which I am a Fellow Emeritus by AIAS's kind tolerance—have added about another very technical and very fundamental dozen or so errors to my own list. A leading foundations scientist with over 500 papers in the literature commented dryly to the AIAS that "I broadly agree. that the transverse plane wave view of vacuum electrodynamics is the biggest blunder of twentieth century science. Faraday visualized that "EM disturbances" surrounding wires, magnets, etc. were simply the transverse plucking of taut strings. As he states in his book, Maxwell—who also firmly believed in the material ether—simply captured Faraday's thinking and assumed that transverse "plucked string" wave disturbance in the material ether. At the time all this was expressed, the electron had not been discovered, the atom had not been discovered, the molecule was a featureless blob, and no one had the slightest notion of an atomic nucleus filled with protons and neutrons. Charge was simply a "certain volume of electric fluid" and everything electromagnetic was expressed in fluid dynamics. As an example, that "material fluid" and "material ether" theory was destroyed in the late 1880s by the Michelson-Morley experiment. All the Maxwell equations assume that material ether to this day; not a single equation was ever changed to eliminate the material ether assumptions during the last 110 years.*
7. *For full explanations of the "Moscow Signals," see T. E. Bearden, .,* Gravitobiology: A New Biophysics, *Tesla Book Co., P.O. Box 121873, Chula Vista, CA 91912, 1991;—* AIDS: Biological Warfare, *Tesla Book Co., 1988. For an excellent Government study of the Embassy radiation by excellent but orthodox Johns Hopkins scientists, see A. M. Lilienfeld* et al., Foreign Service Health Status Study: Evaluation of Health Status of Foreign Service and Other Employees from Selected Eastern European Posts, *Department of Epidemiology, of Hygiene and Public Health, The Johns Hopkins University, Baltimore, Maryland, Final Report, July 31, 1978. On p. 245, it is noted that a marked excess of symptoms were noted in the Moscow employee group as compared to other East European employees in other East European nations.*
8. *Johns Hopkins researchers established the exact field patterns present in the Embassy from the microwave carrier radiation; see Robert C. Mallaliew,* A Model of the Microwave Intensity Distribution within the U.S. Embassy, *Moscow 1966 to 1977, Report FS-80-166, Applied Physics Laboratory, Johns Hopkins University, Aug. 1980. Nowhere in any of the Government-funded studies is there any consideration of field-free scalar potentials and their internal time-polarized EM wave structures (the bidirectional phase conjugate wavepairs shown by Whittaker to comprise the scalar potentials). Yet the field radiation patterns surprisingly showed that in just such field-free, persistent potential zones was where 100% of the health changes occurred.*
9. *Vlail Kaznacheyev and L. P. Mikhailova,* Ultraweak Radiation in Intercellular Interactions, *[in Russian], Novosibirsk, 1981 [an English exposition of much of the Kaznacheyev work is given in Vlail Kaznacheyev, "Electromagnetic Bioinformation in Intercellular Interactions,"* Psi Research, *1(1), Mar. 1982, p. 47-76.]. See also Vlail Kaznacheyev* et al., *"Distant intercellular interactions in a system of two tissue cultures,"* Psychoenergetic Systems, *1(3), Mar. 1976, p. 141-142. In the same issue, see "A Comment" by William A. McGarey, p. 143; "A Comment" by Arthur C. Hastings, p. 143-144. See also Vlail Kaznacheyev, "Apparent information transfer between two groups of cells,"* Psychoenergetic Systems, *1(1), Dec. 1974. The Soviet Union awarded Kaznacheyev a very high medal for his achievements.*
10. *For a very nice summary of EM bioeffects from the more conventional view, see Robert O. Becker and Andrew A. Marino,* Electromagnetism and Life, *State University of New York Press, Albany, 1982. The book is also available at http://www.ortho.lsumc.edu/Faculty/Marino/El/ElPub.html.*
11. *Andrew A. Marino,* Powerline Electromagnetic Fields and Human Health, *http://www.ortho.lsumc.edu/Faculty/Marino/Marino.html. This book is highly recommended. Particularly see "Chapter 5, Blue-Ribbon Committees and Powerline EMF Health Hazards," and "Chapter 6: Power-Industry Science and Powerline EMF Health Hazards." Biophysicist Marino is one of the leaders in the field and has been personally involved in many skirmishes with powerline-dominated studies and findings.*
12. *E. T. Whittaker, "On the Partial Differential Equations of Mathematical Physics,"* Mathematische Annalen, *Vol. 57, 1903, p. 333-355; — "On an Expression of the Electromagnetic Field Due to Electrons by Means of Two Scalar Potential Functions,"* Proc. Lond. Math. Soc., *Series 2, Vol. 1, 1904, p. 367-372.*
13. *Reali,* G. C., *"Reflection from dielectric materials,"* American Journal of Physics, *50(12), Dec. 1982, p. 1133-1136. The reflected field from a dielectric material is not generated just at its surface but comes from everywhere in the interior of it.*
14. *Present physics models the EM wave as transporting energy, but erroneously omits that it also transports time. A photon is made of angular momentum, or "energy x time". Since EM waves are made of photons, it follows that they transport both the energy components and the time components making up those photons. An EM wave is a wave of angular momentum, not just a wave of energy.*
15. *KGB energetics weapons scientists call this internal structuring the "information content of the field." However, the Russians use a good deception plan, which implies that the "information content of the field" is just the normal transverse EM spectral content of EM signals. Appreciable "pertinent" work using that phrase is produced by the open Russian scientific community, thus confusing the issue. Our electrodynamicists seem to buy it hook, line, and sinker. The deception plan also tricks Western scientists into thinking that psychoenergetics is nothing but a Russian version of Western parapsychology. Again, our scientists comfortably accept this with smug satisfaction.*
16. *Presently the Russians are in a great new version of this deception plan, with the goal of deceiving Western scientists into thinking that the "secret" Russian energetics is based on torsion fields. Consequently they are releasing substantial material on torsion wave theory, including replicable experimental results. The released version of torsion fields has one glaring omission: the time components and structuring. This deception plan is excellent, because the torsion field theory that is released, is indeed "real" and testable. It is also revolutionary, with respect to present Western science. It almost positively assures diverting the attention of much of the Western science community into this highly limited subset of the full Russian torsion theory—effectively diverting the West away from psychoenergetics and the direct use of t-polarized EM waves and fields, torsion or otherwise.*
17. *We point out that E. T. Whittaker, in "On the Partial Differential Equations of Mathematical Physics,"* Mathematische Annalen, *Vol. 57, 1903, p. 333-355, showed that every scalar potential is comprised of an internal structure of bidirectional longitudinal EM phase conjugate wavepairs in an infinite set of harmonics. Each of those phase conjugate longitudinal EM wavepairs comprises a time-polarized EM wave. So the common potential contains an internal longitudinal EM wave structure that is further organized into an internal time-polarized EM wave structure. The mind-intent correlates and the total mind and emotional experience correlates from fertilization of the egg that led to development of that person, is in the internal substructure of every potential in the living body. In his "On an Expression of the Electromagnetic Field Due to Electrons by Means of Two Scalar Potential Functions,"* Proc. Lond. Math. Soc., *Series 2, Vol. 1, 1904, p. 367-372, Whittaker also showed that any EM field or wave is comprised of two scalar potential functions. It follows from Whittaker and Reali that the EM emissions from the living body carry the internal correlates of everything that has been experienced by that person from conception in the womb. Sometimes this deep embedded "hidden information content" can even be accessed in deep hypnosis. I once observed the deep hypnotic regression of a subject back to her prenatal experiences prior to birth, where the subject relived hearing words of rejection by the father, before the subject was born. The occurrence of the incident and the father's words were directly confirmed on the spot by the mother, who was closely observing the session as it occurred. It turned out that this particular rejection of the baby still in the womb had played a major role in subsequent deep psychological problems experienced by that person all her life. To resolve the problem, use of a powerful "simulated" reliving pre-birth experience was conducted with the subject again in the pre-birth state and actively participating, but now with the father figure directly expressing love, acceptance, and cuddling and hugging his daughter. This led to a rather dramatic remission of most of the deep psychological problems within 24 hours.*

Mind Control and EM Wave Polarization Transductions, Part 3 of 3

©Copyright 1999 by T.E. Bearden, USA

This outstanding article is the last, Part 3, Part I and 2 of which were published in Volume 9, #2 and #3 of Explore! for the Professional. Because we feel that Col. Bearden's Special Note below is so very important we are repeating its publication in all 3 parts of this article.

Special Note

This article refers to experimental research techniques which can be detrimental or lethal in the hands of any but highly skilled, qualified experimental scientists proceeding under proper laboratory safety procedures. The purpose of this article is strictly for information to properly qualified and authorized scientists in certified laboratories. We do not propose or condone any use of these procedures for nonapproved practice of medicine without a license. Neither the publisher nor the author are responsible for accidents or outcomes in the use of these experimental procedures and techniques. Any researcher who performs these procedures and experiments is acting on his or her own volition, and is solely responsible for insuring safety, qualifications, and legality of the acts and their results. We neither suggest nor condone unauthorized experimentation on human subjects. Such is a criminal violation of the constitutional rights of the subject under Federal and State laws, and achieving many more effects in the targeted bio-organism or groups of them. With Hunt's method, the system as an open dissipative system far from thermodynamic equilibrium in its environment is being measured as such. This more directly allows for determination of the environmental inputs on a much broader range of subsystems, both space-like and time-like. Particularly for mental and emotional correlates to environmental stimuli, such measurements and correlations are essential.

More Comprehensive Phenomenology Experiments

To return: Now the scientists would perform many phenomenology experiments, making one little change at a time and profusely recording the data. Each time, they would establish the physical change(s) that occur in the body and/or the mental and emotional changes that occur in the mind for each spectral reinsertion back through the "ship's portholes". They would simply but painstakingly (over some years) build up an extensive database of those individual correlates.

In these experiments, the experimenters will eventually be able to provoke any body or mind change they wish. Strong emotion. Intense pain. Intense pleasure. Painful thoughts. Images. Memories.

is both illegal and immoral.

Two Ways to Improve the Methodology and Experimental Correlates

We diverge momentarily: If they wish to improve this methodology, they will consider the body dielectric as a nonlinear isotropic medium. Then they will pretend that the spectrum of difference frequencies between each two adjacent waves is the spectrum of "emissions" from the body. They would also use those, as if they were actual emitted spectral signals, instead of the actual signals emitted. That procedure will give superior correlations, but it is more complicated. Part of that is known for underwater sonar,[1] and so our own scientists may or may not have realized it for use in mind and behavior correlate determination with respect to the body dielectric.

Another dramatic improvement in the depth to which the correlates can be constructed, is provided by detecting each porthole output in a two-channel device, where one channel has an adjustable time-delay as utilized by Dr. Valerie Hunt.[2] The two channels—one real-time and one slightly delayed—are then mixed, as by Hunt's method, producing an instrumental measurement of the chaotic part of the functions. Again, this can be measured, recorded, and later analyzed. It adds (i) a completely different kind of thermodynamics in the system measurements, (ii) a dramatically extended set of correlates, (iii) more direct measurement of the time-polarization causative signals, and (iv) an applications technology eventually having many additional degrees of freedom and therefore capable of Perceptions. Dreams. Visions. Memory losses. Memory changes. Personality changes. Etc. The "delta" in the emission spectrum (the changes from zero reference spectrum) represent the precise totality of all mental, physical, organic, chemical, etc. changes and interactions.

A particularly vulnerable aspect of every mammal is the pleasure center in the brain. Experiments have shown that, when this center is stimulated, it is the most addictive experience possible. Rats will forego food, endure electrical shocks, starve, and even die to obtain stimulation of this center. Obviously a device capable of generating signals that evoke direct stimulation of the pleasure center in humans would be a powerful weapon.[3]

Extending the Data Base

See Figure 12. After the researchers have made an "individual porthole signal insertion" correlate database, then they would make a "two, three, four," porthole signal insertion correlate database by inducing selected multiple changes at once. Again they would analyze everything; the program would need one or more supercomputers. It would also require quite a highly qualified multidisciplinary team, extensive facilities, substantial funding, and would be many years in duration. We are describing a decades-long program. But it's a doable.

With sufficient development and performance of such a program, the researchers would have produced (with sufficient testing and analysis, and sufficient retest validation and verification) a database of "specific correlates for a given overall desired physical, mental, or physical and mental delta."

A second stage in the research would be to test the correlates and porthole insertions upon a statistically significant cross section of ordinary people, and/or specialized populations (such as toughened soldiers). The program would evolve a highly complex, very effective, ever-improving science and technology of mind and behavior control and engineering mechanisms, complete with finished database and developed applications equipment.

The Dielectric Body as a Ship With Portholes

Again let us review what the EM transverse wave irradiation from the body dielectric represents. Think of the body dielectric as a sort of "ship", with lots of portholes. When it gets irradiated, certain operations happen internally to that radiation, i.e., certain "processes" and "interactions" occur, which change both the mental and physical states. The output emissions back from the body dielectric, out through the filtering "portholes", will directly correlate to what has happened inside the ship.

It is terribly important to realize that one can use the same frequencies and spectra coming back out of those "portholes" to insert EM signals and waves etc. back in there, and into the deepest processes going on in the body and in the mind (at all levels, including the deep unconscious).

times. So it will reach directly into and affect any and every part of the dielectric, as you wish, and in whatever manner you have correlates for.

We filed an invention disclosure[4] on the above correlate and "back-porthole" process for use in directly inducing full and efficient conversion directly to time-density (scalar, or time-polarized) EM waves inside the body/ cells, therefore immediately and directly time-excitation charging the body cells and all their internal components.

Subtracting the Normal Correlates to Obtain the Deltas

A specifically diseased body, e.g., has a specifically tailored change in its "normal" emission spectra, because of the disease condition alteration of its resident spacetime curvature engine. By having a database for the normal emission spectra of the healthy body, one can subtract it from the actual emitted spectra, to obtain the "delta spectrum".

If the correlates have been previously determined by the above mentioned research program, then one may simply introduce an amplified "delta spectrum" into the body, i.e., through the portholes. This will immediately time-excite the cells and their components throughout the body, particularly where that disease does exist. It turns out that the time-excitation charging by that method will "pump" those diseased cells in the time domain. The cells themselves (and all their parts) are highly nonlinear—to time-excitation

Remember, whatever you put back in there, is going back through the "mixmaster" hopper. It will be iteratively phase conjugated and interfered with by everything, countless charging, they are totally nonlinear. So they will act as rather perfect pumped phase conjugate mirrors, but pumped in the time-energy domain rather than in the spatial


RE-RADIATION WITH ALTERATIONS
Alterations Database
Recorders & Broadband Amps
© T. E. BEARDEN 1998
Control Unit
Broadband Antenna Unit
Receiver-transmitters

Adjusting broadband signals bandwidth and amplification by selecting indicated alterations from database

TIME EXCITATION CHARGE IS STRUCTURED TO CONTAIN THE PRECISE SPACETIME CURVATURE ENGINES FOR TIME-REVERSAL AND STEERING. CHARGING OCCURS QUICKLY. ENGINES CONTINUE TO WORK FOR AN EXTENDED PERIOD AFTER CHARGING CEASES.

Figure 12. Using an amplified replica of the body's own dense, broadband signal complex, containing added alterations, to irradiate the body and produce deeply-penetrating precise time-density charging for cellular time-reversal while steering the time-reversal trajectory to also correct a congenital condition.

EXPLORE! VOLUME 9, NUMBER 4 & 5, 1999

energy domain. This is a dramatic extension to nonlinear phase conjugate optics theory.[5]

General relativity tells us that each specific detail of the mass and energy structure of each cell and all its parts—down to the finest details—is accompanied by a precise set of spacetime curvatures. By reintroducing the same energy as the disease delta TW waves, the affected cells add the phase conjugates, converting the inserted TW signals into longitudinal EM wave signals. The longitudinally-pumped cells again phase conjugate, converting these longitudinal EM waves to time-polarized EM waves, and "charging" the cells and all their parts in the time domain.

Suddenly, at that point the resident spacetime curvature engine—rather than TW or LW EM waves-serves as the "input signal" to the cell-and-its-parts as pumped phase conjugate mirrors (PCMs), pumped in the time domain. An extension to the distortion correction theorem of nonlinear optics results. An exact, amplified antiengine for the diseased cells—i.e., a phase conjugate replica of the resident spacetime curvature engine—is formed. This amplified antiengine overpowers the resident disease engine, powerfully time-reversing the cells and their components back to a previous healthy state. The time-reversal actually occurs over a period of time after the "time excitation charge-up" ceases, say over the next week or two. Usually two to three quick irradiations are required, one week apart, to give a time-reversing period of three to four weeks.

Even though appreciable forces are operating internally upon the cells and all their parts, there is no net translation force upon the cells or any part. E.g., as Pepper[6] states,

"On a more fundamental level, the ideal lossless PCM reverses all the quantum numbers of the incident photon (i. e., linear momentum, angular momentum, etc.). It can be shown that the PCM therefore experiences no linear or angular momentum transfer from the incident photons; hence, the PCM is free from photon radiation pressure and torques."

Note that, in ordinary EM theory, it is precisely translation forces that are engendered upon charged mass by EM fields. This process is quite different. In biological terms, this process dedifferentiates (in physics: time-reverses) the diseased cells and all their components—including the genes—back to an earlier healthy state.

By taking a diseased body and feeding back into it an exact amplified replica of its emitted TW spectrum, one can force the body to "time-excitation charge" all cells and their components immediately, with high efficiency. The human body and every cell and every part of every cell does the necessary "calculation" for the exact antiengine for each part. Since time is extremely condensed spatial EM energy (by a factor of almost 10^{17}), a startling contraction occurs in the radiation time required to time-charge the cells and their components and charged particles. This is a method for instant initiation of time-charging, hence it is extremely rapid. What took Priore several hours of LW irradiation to accomplish in the body,[7] can now be done in seconds with this "thwarting" and spectrum transduction method. In fact, it is an intense stress on the body, and—say—should only


Portable Priore-Type Treatment System
Equipment Case
Computer Control Unit
Infolding Function Generator
Antenna Pad

Figure 13. Portable first-method treatment unit proposed to the Department of Defense. For treating and curing mass casualties from terrorist BW attacks on U.S. population centers.

EXPLORE! VOLUME 9, NUMBER 4 & 5, 1999

be continued for 30 seconds or so. We highly stress that overcharging in this time domain can be detrimental or even lethal if prolonged.

At the end of the very short time-excitation charging time, the body is "time-excitation charged in all its minutest particles". So everything is therefore pumped in the time domain for the next several days after the irradiation is removed, since the time-charge decays very gradually over a period of time. During that decay period, every part of the cell and body acts as a pumped phase conjugate mirror material, pumped in the time domain rather than in the 3-space energy domain. When time-pumped, the mass itself reverses to a previous physical state. This can be used for both nonliving and living masses. Because there is no forcible translation manipulation of the cells and their parts, it can be utilized on living cells in vivo. In the case of diseased cells—e.g., AIDS-it appears that three precisely determined 30-second "AIDS correlate" irradiations a week apart, should be sufficient to completely cure AIDS, including removal of all HIV-genetics changes from every previously infected cell of the body. Also, it would accomplish considerable rejuvenation of the body (making the body younger).

Rejuvenation: Restore the Telomeres and Produce Immortal Cells

Saving Most of the Casualties from Mass Terrorist Attacks

To defend against things like anthrax attacks on our civilian population centers, we also have recommended to the U.S. Government the crash development of small, portable treatment machines—using similar "antiengine-forming" and cellular reversing "porthole technology". [See Figure 13 on previous page]. Such portable machines could be developed cheaply and quickly, and present government facilities could be used to massively attack the correlate database production problem. The portable treatment units could be cranked out by the hundreds of thousands and flooded down through emergency response agencies such as the police forces, the National Guard, emergency hospitals, emergency response teams, etc.

Each device could be used in "assembly line" fashion upon hundreds of sickened patients, in case of a WMD (weapons of mass destruction) attack upon one or more of our cities. The first generation equipment would save probably 70% of the stricken (as from anthrax, etc.). With second generation equipment, one would expect 90% of the stricken casualties could be saved.

Just now, there is a very dim prognosis for all those casualties, using present available treatment capabilities. Time and lack of vaccines defeats just about everything that can be done. Brutally speaking, most of those unfortunate enough to breath in anthrax spores from an

In fact, it is now known that the gradual loss of the telomeres—the natural ends of chromosomes—in a cell's chromosomes is what causes the cell to age. The gradual loss of the telomeres and the resulting shortening of the chromosomes represents a cellular "disease state" or "disorder" state" accompanied by a precise delta in the spacetime curvature engine accompanying every affected (aging) cell.

By determining the correlate for that precise telomere loss in the aging body's emitted radiation spectrum, an effective telomere regeneration process immediately emerges. One simply amplifies that aging "precise telomere reduction" correlate and reradiates the body with it, passing an amplified correlate back into every cell of the body. The cells and all their parts—including the chromosomes—add the phase conjugate replicas, converting the incoming TW EM correlates to longitudinal EM wave correlates. The cells again phase conjugate the LWs and add the phase conjugate replicas, converting the LW correlates to time-polarized EM wave pumping correlates. This latter process time-excitation-charges the aging cells and all their parts, including the genes and chromosomes. The cellular matter itself produces the amplified "aging antiengine" for each and every cell and telomere ending. The result is to again add telomeres, converting the cell back to a younger, more vigorous cell, and reversing the process of aging.

We point out without further elaboration that these methods also introduce direct engineering signals into the body's master cellular control system, including the regenerative subsystem. Hence the body's regenerative subsystem is involved in helping produce the necessary engines and operate upon the short telomere chains to add back telomeres. More specifically, the regenerative subsystem is changed into attack, are going to die. At least 80% of them will expire, in spite of everything the present system can do for them.

Note each device could rapidly treat a whole series patients, one right after the other, merely laying them between "blankets" containing wire antennas, irradiating with the proper correlate spectrum quickly, moving on to the next patient, irradiating quickly (seconds), etc. The entire apparatus could be made to fit in a large suitcase-sized container, and it would be highly portable and controlled by a laptop-sized computer.

Unfortunately, so far the DOD doesn't even understand what the heck we're talking about! The National Institute of Health (NIH) and the National Science Foundation (NSF) are not interested at all. After all, it isn't drugs, vaccines, antibiotics, etc. — which are simply not going to do the job. However, those are what the government and scientific communities are going to finance to the tune of hundreds of millions of dollars. They are then going to lose almost all those mass casualties when the terrorist attacks on our population centers inevitably occur.

Those are Americans. They are going to die. Most of them could be saved. We ought to save them.

For any change in state (physical, chemical, emotional, mental, perceptual), the body dielectric "portholes" change and the output spectrum changes. The delta from zero reference now represents that exact change.

Where Western Mind Control Research Has Probably Arrived

Western mind control researchers probably first established a correlation database of porthole emission correlates to changes in internal states, both physical perfect consonance with the external introduction of the amplified antiengines.

That exact process can be used to rejuvenate the aged population and remedy most of the debilities of growing old. That is how we eventually intend to do it, if we can convince the U.S. government and the U.S. scientific community to perform the necessary research and validation.

and mental. They almost certainly recognize the peculiar participation of every part of the body dielectric in the TW emission spectrum from the body. They will almost certainly have opted for this "porthole" notion of some similar expression of it, and the "thwarting" of these "relaxation and release" emission processes to engender internal physical changes in the body and in the brain-meat-computer, as they see it.

EXPLORE! VOLUME 9, NUMBERS 4 & 5, 1999

They probably experimented with different TW EM radiation mixes, to see what the body emission change to, and what states are induced. Undoubtedly they found that the induced states began to correlate with the former emission delta data base. That is, they found out which delta emissions spectra, reversed and amplified and fed back thorough the portholes, produce what internal changes.

Use for healing is the simplest of all. Use for killing or debilitating is more complicated. Of course weapons researchers wish to look only at the killing aspects. That is something they understand. They do not understand healing, for they do not even have the "regenerative" or "healing" mechanism in any of the scientific papers or texts. Becker[8] came closest in this country, and Priore did it in France. Both of those scientists were suppressed and paid a bitter price for their revolutionary and innovative research.

But look at what has been done, by "input-output" correlation research. The scientists will have a database now, that tells what state emerges in the body and in the mind, for what irradiation spectra (frequency, relationships, phases, amplitudes, wave shapes, etc.) one uses. And they did not work out all the wave-to-wave transductions ongoing in the mind and body connection and in the body and in the mind, individually, between TWÛLWÛTDW.

We suspect that this is the course Western mind control researchers will have taken, without even realizing the internal wave transductions occurring. And they would not be concerned with that. They would have what they want, for weapons, mind control, and behavior control. And of the internal "mix" of the dielectric and all its tiniest portions. So Western mind control researchers and rogue groups probably do get good results.

We are not just picking on the U.S. government here! Internal divisive groups exist in all large and powerful groups, and joust for power. In highly classified groups, these groups are greatly enabled to joust more widely, unethically, and immorally because it is so deeply hidden. So very deep classification evokes the growth and intensity of rogue groups. It's the old "Power corrupts, and absolute power corrupts absolutely" routine.

The implication is that in the West one or more highly classified, sustained, heavily funded developments in advanced mind control programs, probably exists and probably has existed for some time. Due to loose formation of rogue groups inside such programs, they may have dual or triple purposes, may not operate under very much legitimate government control at all, and may operate specifically for the purposes of the rogue group or groups that have gained control.

In a nutshell, that's what may be going on in the clandestine mind control projects in several Western governments. The involvement of at least some rogue groups, some being "cowboys" who operate well outside all laws and ethics, could also result in such things as assassinations, clandestine testing on individuals without their consent, etc. In short, it could account for what seems to be actually occurring. As also is "usual" in such a mess, one or more of the rogue groups eventually may become very powerful because their secret weapons are very powerful. They may become confident, thinking they have the "best in the world." They may actually believe they are ahead of the Russians.

they would of course ignore the healing aspects. And they would get results of course, revolutionary results. So they would undoubtedly classify the program very highly, thinking that they had the best of the best.

Rogue Groups May Also Have Arisen to Divert the Purpose of the Projects

And that is where real problems may arise. Every human group has within it competing subgroups, jousting for power. The more highly classified the group and its activities, and the less that is known about it outside its confines, the more strongly and secretly the subgroups can play. So they can emerge as rogue groups pursuing their own agendas, not that of their duly elected governments. In the extreme, such a deep black program can even become a "captured" program, which is totally in the hands of rogues and no longer reports to or is bound by the dictates of the parent government.

It has long been suspected in some quarters that even the US's highly classified research community may be riddled by such rogue groups, and so may be certain highly sensitive parts of the Research and Development community.

Remember that, in every large and powerful human organization, the basis for rogue groups is power and secrecy. They are always seeking to increase their power, control, influence, prestige, etc. Nothing else. Patriotism and mission are—to rogue groups—often just idle words. They have their own agendas. And being rogue groups, they may well bring in unethical, immoral tricks: assassination, bribery, entrapment, disinformation, plausible deniability, etc. A certain percentage of a highly secret rogue group will wind up using all these things and more. It's a

Where the Russians Probably Have Arrived

On the other hand, the Russians will have developed instruments for detecting and isolating the LWs and the scalar waves, in addition to the ordinary mundane instruments for measuring the TWs. So they will have not only the TW correlates, but also the much finer TWÛLWÛTDW (scalar EM wave) correlates. They will understand and employ the use of vacuum engines (spacetime curvature engines) which Western researchers will often invoke but not understand or even be aware that this is what is being invoked. In other words, Western researchers probably just use the old method of "input fi set of functions fi output". That is the standard basis for almost all Western system analysis. With it, one doesn't have to know the exact functions and processes going on in the middle. One just determines a transfer function from a given input to the output that results. Then one catalogs that transfer function. One does that for lots and lots of transfer functions for particularly desirable results, and one has the system analysis. One also has the immediate basis for a rapidly-developed applications technology.

Western scientists are good system analysts. But they have little or no comprehension of what is really going on in that "inside the ship functions" portion, even though they have determined the transform function which acts upon the input to give the "from the portholes" output.

The Russians, with their additional knowledge of the actual mechanisms in the transforms, will be much more advanced than the West, because their fundamental psychoenergetics science is far more advanced, so long as we continue to use human characteristic, the old primate dominance game. Only now disguised and hidden under deep classification.

Nonetheless, the "simplified" TW EM "porthole correlate" approach will yield very positive results, due to the correlation existing with the LW s and scalar portions the old U(l) electrodynamics. Further, the Russians have decades of use of longitudinal interferometry beams to reach right through the earth and ocean and produce stringent EM effects at a distance. So they will also be able to do the same things here in "mind control" with LW interferometers, through intervening mass

EXPLORE! VOLUME 9, NUMBER 4 & 5, 1999

including the earth and ocean. Western mind-control scientists and their rogue groups—assuming they exist as postulated—largely will not be able to do that, and probably won't even recognize Russian testing of psychoenergetics weapons directly in or over Western nations.

Russian Lethal Psychoenergetics Mind Control Tests Over the U. S.

In fact, the KGB tested just such highly advanced mind control weapons over the middle of the United States in 1997 on two occasions. The tests were conducted against Captain Button in his A-10 "Warthog" aircraft on April 2, 1997 [See Figure 14], and upon Captain Svoboda in her A-10 "Warthog" on May 27, 1997. [See Figure 15].

Over Arizona, Captain Button was thrown into a hypnogogic state, and his perceptions instantly altered and controlled. In his instant "dream-waking" state, everything seemed perfectly normal. His sense of direction was altered a bit more than 90 degrees, so he simply corrected and turned and "flew toward the range", actually flying off course by more than 90 degrees and ignoring radio contacts. He flew right on out of Arizona. At one point he circled, probably thinking he was over the range, and he probably dropped his ordnance there. Then he "flew on back toward home," as he thought in his waking dream state, until his fuel ran out and he crashed and died in the explosion—dream-thinking until he died that everything was normal. All the while, his sense of the passage of time was altered. To him, in his dream-thinking, dream-acting state, everything was normal and nothing untoward had happened. So the distant KGB transmitters and associated psychoenergetics team controlled him for over an hour.

Indeed, that was the exact purpose of the test: demonstrate control (at a great distance) of a skilled person performing highly skilled tasks. A secondary purpose was to stimulate the U.S. government, watch its investigation and findings, and ascertain if the U.S. knew of the extent to which Russian KGB mind control weaponry had advanced. Obligingly, we proved to me KGB that we did not understand what had actually happened to Captain Button.

Captain Svoboda was from the same Wing as Captain Button and was its most experienced night fighter A-10 pilot. In fact, she taught other pilots the fine points of night flying combat missions in the A-10. About two months after Captain Button's bizarre flight and death, Svoboda was engaged in night target bombing on the range. Rising from her ordnance drop on me target, Svoboda was suddenly struck and rendered hypnogogic and in a waking-dream state. Her sense of the vertical was instantly reversed. Superb pilot that she was, she immediately dream-perceived she was diving, not climbing out of the delivery. She instantly corrected to "climb out". So in the real world she dived sharply into the ground and her aircraft exploded.

This test demonstrated the instant alteration of a skilled pilot's perception, causing that pilot to inadvertently react promptly in an unintentionally suicidal manner. A secondary purpose of the test was to stimulate the U.S. government system again, to see if the system recognized what had


A-10 Mysterious Flyaway and Crash
April 2, 1997
Armed with:
- Four 500-lb bombs
- 30 mm Gatling gun
UTAH
COLO.
1:40 p.m. Vail
Area enlarged
1:22 p.m. Aspden
1:05 p.m. Telluride
12:53 p.m. Cortez
ARIZONA
11:58 a.m. Breaks Formation near Goldwater Range
12:20 p.m. Young
NEW MEX
12:11 p.m. Apache Junction
Barry M. Goldwater Air Force Range
DEPARTS
10:30 a.m. Tucson
Tombstone
Eagle
Vail
Glenwood Springs
COLO.
Hardscrabble Range
New York Mountain
Sawatch Range
▪▪▪▪ Flightpath
Aspden

Figure 14a. Captain Button's mysterious flyaway and eventual crash.

EXPLORE! VOLUME 9, NUMBER 4 & 5, 1999

occurred. Sad to say, it did not and it has not. It was lamely speculated that Svoboda probably looked over her shoulder like a rank greenhorn, and inadvertently dived her aircraft into the ground while looking back at the target. If there was one pilot in the USAF who would have not done that, it was Captain Svoboda. At any rate, the KGB determined that the U.S. scientific, intelligence, and governmental communities did not have the foggiest notion of what had occurred.

In private proprietary communications[9] we have explained further, to proper parties, exactly the reasons for these two tests, and what exactly was being tested, and what is its planned strategic use.

The Final Race for Direct Mind Control of the Entire Human Species

The KGB psychoenergetics weapons scientists—because of their direct measurements and detections (and use) of t-polarized waves and LWs for decades—also understand that Jung's collective unconscious mind (of the entire human species) also has its own time-like operations and correlates, which one measures also when using t-polarization measurements and sorting it all out. The collective unconscious mind operations are buried several levels deeper inside the recursive Whittaker structuring inside the EM fields, waves, and potentials.

The KGB scientists also know that something very like Gaia— a collective unconscious mind for all species on earth—also exists, and they are striving to be able to sort out and measure that one as well. The Gaia operations are buried even deeper in the recursive structuring inside the EM fields, waves, and potentials. If one reads some later books by Kaznacheyev,[10] e.g , this human species unconscious mind aspect and the biosphere unconscious mind aspect emerges loud and clear, if one interpolates between the lines, so to speak. Actually, from day one, the Russian mind control scientists have had their eventual goal set upon this "deeper area of mind and possible mind control" of the entire human species.

I am convinced that the KGB psychoenergetics scientists understand this deeper area. If they can learn to directly engineer the collective human species unconscious, they can then convert the human species easily into a sort of "ant" society, modeled along ideal Communism lines, except of course with an excluded "hierarchy at the top" running everything. The "ant society"—communist style—is still a variation of feudalism (all systems tend to feudalism or some form thereof).

The KGB psychoenergetics weapon scientists are seriously pressing on toward that very goal. In my opinion they are not very far from it right now. It is simply a matter of developing sufficiently complex equipment to be able to directly engineer the time-domain substructuring at sufficiently deep levels. It is a doable, although it is very, very complex and very, very difficult. On the other hand, they have been at it for decades. Even in the 50s the Russians already had the old LIDA device,[11] capable of inducing a catatonic trance-like state in a mammal—either a human or a cat,[12] for example. Some versions of Russian mind control devices were used on Russian soldiers in the


CAPTAIN SVOBODA DIVES HEADLONG TO HER DEATH
COMPANION A-10s
© T.E. BEARDEN 1999
CAPTAIN AMY SVOBODA
Night training mission May 27, 1997
From same wing as Captain Button
This was a second psychoenergetics strike

Figure 15. Captain Svoboda dives headlong to her death.

EXPLORE! VOLUME 9, NUMBER 4 & 5, 1999

Afghan War to condition them for performance of merciless acts.[13]

Potential U.S. Rogue Groups and Two Recent Examples

Meanwhile, rogue groups amongst Western clandestine mind control researchers will probably arise if they have not already done so. They will likely seek to increase their personal control and further isolate the programs from orthodox government review and from government and legislative control. They may even divert the research into highly illegal and unethical means, because it furthers their own rogue agendas. That is how clandestine U.S. government research can sometimes go sour, unless great care is exercised by the oversight committees in the House and the Senate.

Sometimes when rogue groups do gain control and total secrecy of a given new technological area, then what appears to be "U.S. government operations" do start to encompass a criminal and unethical operations, hidden usually beneath the deep veil of high classification. Also, if it's "scientific," no one is ever brought to justice, even if the "evil science actions" are uncovered and publicly revealed.

We Certainly Have Proof of Such Rogue Activity. For Example, Here are Two Prominent Cases:

1. For three decades, scientists from the U.S. government, universities, and civilian contractors secretly

as a result of those ghoulish experiments. So what happened when this gruesome thing was revealed? Again President Clinton publicly apologized! The head of the Executive Branch did not turn the macabre matter over to his Attorney General to prosecute. How many of these scientists were indicted? Not one. How many are going to be indicted? Not one. Suppose again this had been done by a private doctor in his own private clinic. You get the point.

There is Little or No Punishment of Rogue Scientific Groups

Shockingly, the U.S. government at the highest level has directly shown (and these are not all such cases by any means!) that mass crimes against U.S. civilians, perpetrated by portions of the U.S. scientific community in direct conspiracy and in secret, will likely be condoned. The perpetrators will not be indicted, tried, or convicted.

Note the connection of the "rogue groups" thesis to the above incidents. Note how rogue scientific groups got away with it in both these cases. There may be other rogue scientific groups getting away with such things today. They should not be able conspired to treat unsuspecting human patients with whole body nuclear radiation, including some retarded children and cancer patients. Some of those patients—including some of the retarded children—died as a result. These illegal experiments were conducted in great secrecy, and the results were highly classified. Eventually these actions were revealed, and a Presidential investigation committee investigated. These experiments would seem to be little different from the WWII Nazi and Japanese experiments on human prisoners. Are those U.S. scientists who were responsible for those retarded children's' deaths any different from the Nazi scientists and criminals we executed at Nuremberg? So what happened when this terrible thing finally came out into the open? President Clinton publicly apologized! How many of the responsible scientists were indicted for murder? Not one. None is ever going to be. Suppose a doctor here in South Alabama, with his own private clinic, had secretly irradiated those human patients and retarded children with whole body nuclear radiation, over a period of 30 years, resulting in some agonizing deaths. How many state and federal agencies would have come after him with arrest warrants? Probably about 50 or so. Would he have been indicted, tried, convicted, and executed or sent to prison for life? Absolutely! Would the President of the United States have apologized? Not on your life; he would have turned it over to the U.S. Attorney General with a strong directive to to get away with it. But they can.

Perhaps a most startling additional part of those two incidents is that there was no great public outcry from the scientific community, deploring these murders and demanding that the criminal scientists be indicted and tried.

As the old saying goes, "By their silence they have convicted themselves." The organized scientific community, as a community, has shown that it has little or no ethics, and—while deploring any scientific murdering that "gets revealed,"—is not really interested in justice. In short, much of the U.S. scientific community may now have very little ethics left.

We are not talking about normal individual scientists, but the Big Science community. There is a whale of a lot of difference between the two. In the Big Science community, there can be and there are rogue groups. Lots of them. There is deep cover, deep classification. And there is very probably advanced mind control research and testing, be it legal or illegal. Hopefully most of it is legal and constrained. However, some of it is almost certain to be illegal and ill constrained.

Human beings are still human beings. All the good and evil is still there, regardless of the group. The stage settings change, but the cast of characters and the play never change.

It's sad, but 'twas ever thus. Hidden parts of our own governments—and other governments throughout the world—are no different from the old medieval groups, where nobles etc. were always plotting against the king, or using the king's power for their own nefarious end. The rogue groups today are no different from all the scheming and conniving groups that destroyed the Roman Empire. Great empires fall from within, not usually from without!

investigate and prosecute on criminal charges.

2. Again for three decades, scientists from (i) the U.S. Government, (ii) universities, and (iii) civilian contractors conspired to give poor syphilitic blacks in Tuskegee, Alabama a placebo while ostensibly treating them for syphilis. The purpose of the program was to deliberately observe and record the ravages of the disease to its fruition in their wracked bodies. So the scientists deliberately sat there and watched their brains rot and their bodies rot. They kept meticulous notes, of course. It was very scientific. And it was macabre. They "treated" some 400 blacks in the "program." Over 100 blacks died

Conclusion

This concludes our brief portrayal of the probable directions that mind control research has taken, in Russia and in the West. It is a novel and powerful area, and it poses both severe dangers and great benefits to all the peoples of the Earth.

Let us hope this great new area, already off to a bad start, can be bridled and steered in the direction of helping and healing people, rather than killing or abusing them. The excesses in its bad use are a potent threat to all nations on earth. Yet it can revolutionize medical science, education, communication, and psychology. Eventually it can engineer the mind and memory directly, beneficially. We foresee the day—perhaps 30 years hence—when education will be

EXPLORE! VOLUME 9, NUMBER 4 & 5, 1999

accomplished by directly loading the software into the mind. Then in three weeks one will "load" a doctorate, say, in physics. In three more weeks one will also load a doctorate in chemistry. Another three weeks, in electrical engineering. Another three weeks, an M. D. And so on. When that happens, then truly everyone on earth can be educated. Freedom from ignorance may well be another great freedom that is legally recognized. There will be no impoverished large groups lacking the education to find decent, productive jobs.

We urge all nations to use the principles involved: not for human abuse, but for healing, educating, uplifting, and life-expanding of every person on Earth. If we

446955, Oct. 23, 1998, forwarded to US. Patent Office on Nov. 4, 1998.

5. A very good introduction to nonlinear phase conjugate optics is given by David M. Pepper, "Nonlinear Optical Phase Conjugation," Optical Engineering, 21(2), March/April 1982, p. 156-183. Also see David M. Pepper, "Applications of Optical Phase Conjugation," Scientific American, 254(1), Jan. 1986, p. 74-83.

6. Pepper, Optical Engineering, ibid., p. 158.

7. See T.E. Bearden, Energetics of Free Energy Systems and Vacuum Engine Therapies, Tara Publishing, Internet node www.tarapublishing.com/books,July 1997. See also T.E. Bearden, "Energetics Update and Summary, " Part I, Explore, 7 (6), 1997, p. 60-67, Part II, Explore!, 7(7), 1997, p. 53-56; Part III Explore!, 8(1), I997, p. 53-56; Part IV; Explore!, 8(3), 1997, p. 56-63. See also T.E. Bearden, "Vacuum Engines and Priore's Methodology: The True Science of Energy-Medicine: Parts I and II " Explore!, 6(1), 1995, p. 66-76; 6(2), 1995, p. 50-62.

8. E.g., see R.O. Becker; Charles H. Bachman, and Howard Friedman, The direct current system: A link between the environment and the organism, " New York State Journal of Medicine, Vol. 62,

do, we shall all have a far brighter future. Then we shall check what has started out to be the Sword of Damocles and turn it into the golden Millennium.

We are reminded of a poignant quote from Teilhard de Chardin:

"Someday, after we have mastered the winds, the waves, the tides and gravity, we shall harness for God the energies of love. Then for the second time in the history of the world man will have discovered fire."

May the nations of the world utilize the new mind engineering science to truly free all minds into a common love of, and respect for, their fellow humans of every color, creed, and circumstance. As de Chardin envisioned, may we use the new science to discover a new fire, burning clearer and brighter than anything that has gone before. ♦

ABOUT THE AUTHOR

President and Chief Executive Officer, CTEC, Inc. Lieutenant Colonel US. Army (Retired). MS Nuclear Engineering, Georgia Institute of Technology. BS mathematics, Northeast Louisiana University. Graduate of Command & General Staff College, US. Army. Graduate of Guided Missile Staff Officers Course, U. S. Army (equivalent to MS in Aerospace Engineering). Numerous electronic warfare and counter-countermeasures courses. Tom is the leading advocate of scalar potential electromagnetics and the Fogal charge-blocking semiconductor: He is involved in alternate energy devices and scalar electromagnetic system prototypes. He has defined charge q as a coupled system of two components, advanced a mechanism for a vacuum engine, whereby the vacuums virtual particle flux is organized and used to energetically shape and manipulate matter and

April 15, 1962, p. 1169-1176. See also R. 0. Becker; "The direct current field: A primitive control and communication system related to growth processes, "Proceedings of the XVI International Congress of Zoology, Washington, D.C., VOL.3, 1963, p. 179-183; —"The neutral semiconduction control system and its interaction with applied electrical current and magnetic fields," Proc. 1lth International. Cong. Radiol., Amsterdam, Excerpta Medica Foundation, 1966, Series 105, p. 1753-1759. See particularly Robert O. Becker and David G. Murray, "The electrical control system regulating fracture healing in amphibians," Clinical Orthopaedics and Related Research, Vol. TBD, No. 73, Nov.-Dec. 1970, p. 169-198.

9. Bearden, T.E., Energetics: Extensions to Physics and Advanced Technology for Medical and Military Applications, CTEC Proprietary, May 1, 1998, 200+ page enclosure to CTEC Letter, "Saving the Lives of mass BW Casualties from Terrorist BW Strikes on US. Population Centers," distributed to selected high U.S. Government agencies and Legislative subcommittees, May. 4, 1998.

10. E. g. , Vlail Petrovich Kaznacheyev, V. I. Vernadsky's Study on Biosphere and NooSphere, 1989 [in Russian]. Vernadskys concepts included living matter, biosphere, and human-transformed biosphere (noosphere). Kaznacheyev writes of evolution and

energy, and advanced a mechanism for a Bohm-type quantum potential, which theoretically allows the engineering of action at a distance in physical systems.

He is president of the Association of Distinguished American Scientists (ADAS), a life member of the Alabama Academy of Science, Emeritus member of the American Association of Physics Teachers, and has served on the Board of Directors of several associations and corporations. Tom is a guitarist, a retired aikidoist (Sandan, Yoseikan style), is happily married and has two sons and two daughters. He and his wife Doris live in Huntsville, Alabama where Tom is retired from aerospace, continues private research, and serves as a consultant to industry on Scalar electromagnetics processes.

REFERENCES

1. Owen Flynn, "Parametric arrays: A new concept for sonar, "Electronic Warfare Magazine, June 1977, p. 107-112.
2. Valerie Hunt, presentation to the U.S. Psychotronics Associations Annual Symposium, Bergamo Center, Ohio, 1988. Hunt presented epochal work showing chaos—and thus hidden order—in recorded ELF electromagnetic radiation from human bodies. Hunt split the received EM signals into two identical channels, time-delayed one channel by a very slight amount, then recombined (mixed) the nondelayed and delayed signals. The result was that attractors precisely indicative of chaos appeared. This positively proves that human systems produce ordered time-structuring of EM.

organization of the living matter as the biosphere of the earth. Without specifying the exact technical details, Kaznacheyev discusses the gist of much of what is in this present article. The present author has an autographed copy of Kaznacheyevs book referenced above.

11. Rabichev, Lev Yakovlevich; Vladislav Fedorovich Vasiliev; Alexandr Sergeevich Putilin; Tatyana Grigorievna Ilina; Petr Vasilievich Raku; and Leopold Pavlovich Kernitsky, "apparatus for the treatment of neuropsychic and somatic diseases with heat, light, sound; and VHF electromagnetic radiation," U. S. Patent. No. 3,773,049, Nov. 20, 1973. This is the U. S. patent for the LIDA machine, developed by the Russians prior to the Korean War. Additional patents or applications are as follows: Italy, #619,129, March 1961. Germany, #1,183,607, Dec. 1964. Great Britain, #826,766, Jan. 1960.

12. Stefan T. Possony, "Psy-War: Soviet Device Experiment," Defense & Foreign Affairs Daily, 12(104), June 7, 1983, p. 1-2. Reports on Dr. Ross Adey’s investigation of the Soviet device called LIDA which is used to bombard human brains with radio waves in the 40-MHz region. Also reports on work by A.S. Davydov of the Ukrainian Academy of Sciences, who discovered how the blood-brain barrier can be penetrated by low-frequency radio waves so that brain cells

3. Years ago, I read an obscure reference to Russian research directly along that line, with successful development of just such a portable device. Unfortunately I lost the reference in a disastrous flood in my basement and have been unable to recover it.
4. T. E. Bearden, "Alteration of Materials by Wideband Multiwave Irradiation Combined with Selective Emission Manipulation," Invention Disclosure Document Number

are affected. See also "Soviet device uses radio waves as tranquilizer, " Associated Press release, Huntsville [Alabama] Times, May 19, 1983. Dr. Ross Adey tested the Soviet LIDA machine on a cat, and in two or three minutes the cat was sitting quietly, almost as though transfixed, and uninterested in its surroundings. The animal remained uninterested in its surroundings for some 20 to 30 minutes after the machine was turned off.

13. "KGB Used PIS to Program Soldiers, "Resonance, No. 30, Mar. 1996, p.29. Quoting: "During the 1970s, the Soviet KGB developed a Psychotronic Influence System (PIS) that was used to turn people into programmable "human weapons." Soldiers fighting in the Afghan conflict were trained using the system which employs a combination of high frequency radio waves and hypnosis. Commands are activated by code words or cyphers. The purpose of PIS was to render regular soldiers and members of the special forces incapable of feeling sympathy.

EXPLORE! VOLUME 9, NUMBER 4 & 5, 1999


EXCALIBUR
BRIEFING
Explaining Paranormal Phenomena
THOMAS E. BEARDEN

THE NEUROPHONE

Another device that uses the new hyperspatial, virtual state, nested modulation technology (and has done so for seventeen or eighteen years) is Dr. Pat Flanagan's neurophone. With brilliant insight and intuition far beyond that of science at the time, Pat invented and patented the instrument by the time he was seventeen years old. The neurophone is a device that, contrary to all present theory and knowledge, will directly "pump the brain" and reproduce sound and information directly in the brain and mind system, without going through the auditory system at all. A simplified diagram of Pat's improved neurophone is shown in Figure 11.


COMPLEX
SIGNAL
SQUARE WAVES GENERATOR
DIFFERENTIATOR #1
DIFFER-ENTIATOR #2
COMPLEX
SIGNAL
SPIKES
NOISY SPIKES
VIRTUAL STATE MODULATION

Figure 11. A simplified diagram of the improved Flanagan neurophone

Briefly, the device takes a complex signal, such as the sound of an orchestra playing a musical interlude, and electrically processes it as shown in the figure. First the signal is passed into a section that clips everything into a series of square waves, remarkably analogous to the sort of clipped waves Lisitsyn confirms are the information carriers of the human brain. Next the square waves are differentiated, yielding a series of sharp spikes (note that these spikes retain the pulse-time content of the clipped signal). These spikes are again differentiated, and since these are finite spikes with real nonzero rise times and decay times rather than theoretical constructs, a series of noisy spikes results from the second differentiator section. From here, the noisy spikes are introduced to special contact electrodes, one of which is normally placed on the forehead, while the other may be placed almost anywhere, including on the foot. Nowhere are any sound waves introduced to the head.

The square-wave clipper section reduces the complex signals, their overtones, and their complex modulations to square waves, retaining the temporal content of the wave mix but not the waves themselves. The first and second differentiators heighten or filter through the temporal content of the higher-order differentiations, that is, they serve as a band pass filter unit to accent the time keying of the neutrinic and mindfield portions or aspects of the signal. When these time spikes are then introduced across the body as pulsed voltages, they are modulated directly on the dendrite firings of the brain and nervous system, providing direct and pulsed modulation of the neutrinic and mindfield component channels of the mind-brain-consciousness-life loop itself. Thus the neurophone directly inputs information into the brain and nervous system, bypassing all the normal sensory systems that lie between the mind-brain loop and the outside environment.

Indeed, a similar development has been reported by two University of Missouri researchers. Dr. Donald York, a neurophysiologist, and Dr. Thomas Jensen, a speech pathologist, have recently reported identifying and decoding twenty-seven words and syllables in specific brain wave patterns and correlating these electroencephalographic patterns with both the spoken word and the silently thought word in about forty subjects. At present, Dr. York and Dr. Jensen are programming a computer with a brain wave vocabulary, to monitor and read the EEG of a stroke victim's brain and help stroke victims who have lost their powers of speech to communicate.

While all such developments can obviously be misused, their potential for assistance to mankind is enormous. Indeed, my own premise that brain linkage is possible and can be used to advance all mankind to the sixth stage of species evolution is slowly being proven. It is within our reach now to develop a multi-channel communications system that will directly link brains, minds, and consciousness into a single functional being; and I have already pointed out that the psychokinetic power of the emergent entity increases exponentially with the number of linked stages. The normal corpus callosum linkage of the two cerebral halves in each human head proves that brains, minds, and beings can be linked and integrated into one.

The Excalibur Briefing details the basic concepts of the theory involved in hyperspace-virtual state engineering, and thus in the engineering of mind-life-consciousness links to multicellular organisms here on earth. Pat Flanagan's neurophone proves that complex information can be implanted directly in the brain and mind, bypassing the normal isolating barriers. Drs. York and Jensen have shown that the brain wave does indeed contain recognizable, decodable information analogues. Lisitsyn has already reported measuring the number of independent channels involved and has documented the importance of the clipped brain waves as opposed to the sine-wave content. If we have the vision, we can still develop a brainlink and rapidly apply it to link sixty to one hundred persons, thereby opening a conscious, multidimensional "eye" for the collective human unconsciousness, gently rousing ZARG into wakefulness, and fulfilling human destiny without undergoing the psychotronic Armageddon planned by the Soviets. The time is short, but it can still be done if the funding, the vision, and the team can be established on a crash priority basis.

SOVIET "WOODPECKER" SIGNALS

But, as I have said, all this can be used for the detriment of mankind as well as for its benefit. Unfortunately, it appears that the Soviet Union has chosen to weaponize the effects on a global scale. A prime example is the "woodpecker" signals emanating from the USSR in the 5-30 megahertz region and interfering with communications around the earth.

These complex woodpecker signals appear to originate from two or three dozen powerful Soviet transmitters, each with a power estimated as high as 40 megawatts (Figure 12).



Figure 12. The Soviet "woodpecker" signals

The pioneering experimental measurements of these signals by Dr. Robert Beck and William Bise have shown just how deadly a potential may be possessed by the signals. These measurements have been performed in Eugene and Portland, Oregon; Los Angeles, California; Huntsville, Alabama; and several other locations. They have been particularly significant on the West Coast in and around Eugene, Oregon because of the presence of a direct current transmission line several hundred miles long, which has acted as a long wire antenna, picking up the signals and rebroadcasting them with appreciable gain in the vicinity.

Typically the signals may be found on, say, sixteen different carriers between 10 and 20 megahertz. Twelve of the carriers may appear normal, with normal side-bands, and the other four may have the carrier and both sidebands suppressed but still show the biologically significant modulation (for example, 10 hertz). On all sixteen channels a strong 10 hertz modulation may appear, all perfectly time synchronized and in phase channel-to-channel. The received signal from one of these carriers may be twenty-five to thirty times as strong as the earth's back-ground magnetic field, which is oscillating at approximately 7.0 to 7.5 hertz. Other complex modulation frequencies, many of them changing, are present on the various channels.

Normally, the brainwaves of mammals in an area are gently entrained by the normal oscillations of the earth's magnetic field and are oscillating along at, say, 7.5 hertz. Under continuous radiation from the Soviet woodpecker signals, a percentage (say 30 percent) of the mammalian brains may be captured by the 10 hertz modulation on the overpowering Soviet signals. These captured brains are now in forced oscillation and are riding along in phase with the 10 hertz Soviet modulation. In other words, a certain percentage of the human brains in an area will phase lock to the 10 hertz modulation, and that will effectively lock into those brains the sixteen carrier frequencies with their concomitant frequency mixes and complex signal modulations. If the signals are made much more powerful (for example, by focusing them onto one particular area or increasing the power of the transmitters), then a much higher percentage of brainwave entrainment can be accomplished in the targeted area. By simply adding on the desired modulation patterns, the Soviets can now pump material directly into the mind-brain-consciousness-life loops of the entrained brains. The weapon implications are enormous: raw emotion such as sheer terror or panic can be transmitted; death or disease patterns of all kinds can be transmitted; informational content (thoughts and ideas) can be impressed directly into the captured brains and minds and processed as if originating inside each brain itself. Indeed, as long as the Soviets keep the effects rather gentle, an entire population can be subtly influenced without governmental notice. Certain specific ELF frequencies can rapidly disable or even kill, and for wartime use those frequencies can be directly implanted in the captured brains themselves by the woodpecker signals. It appears that 1984 came a little early, and one can perhaps now understand Brezhnev's strange 1975 proposal to the SAL T negotiations that we should also consider outlawing the development of new weapons more frightful than the mind of man has ever conceived.

The signals also have direct application against strategic targets other than personnel. For example, by incorporating the correct nested modulation pattern, the positron kindling (electron squelching) pattern can be impressed. By beaming through the earth (with a circularly polarized signal or with other complex modulation forms), a beam with a strong neutrinic component, which will squelch electrons and which will interact with great preference for strong voltages or strong magnetic fields, can be directed at a target complex. In the targeted area aircraft and communications systems can be disabled; automobile, truck, and other ignition systems will fail; power transformers and large motors and generators will fail; power transmission systems with their associated high voltages will fail; and so on. Even independent, self-contained emergency power equipment, such as at military installations and strategic missile sites, will fail to operate. Further, to some of these signals, the earth and the sea are as transparent as glass, and so underwater nuclear submarines can be electrically disabled on station before their missiles can be fired, while strategic missile complexes can be electrically disabled before their deadly nuclear missiles can be hurled toward their distant targets. If some submarines and land complexes succeed in firing missiles before being disabled, these missiles can be electrically dudded and scrubbed from the sky over Soviet territory while still far from their intended targets.

So, as stated at the end of *Excalibur,* the players are on stage and in place. The final act begins. One thing is sure - mankind will never be the same again after seeing the play!

VACUUM ENGINES AND PRIORE'S METHODOLOGY: THE TRUE SCIENCE OF ENERGY-MEDICINE

Part I of II

© Copyright 1995 by T. E. Bearden

Photo 1. (to the right) Priore's laboratory. Workbench with animal cage is in the right foreground, under a large overhead assembly to hold the coil for producing the rippling magnetic field.



Photo 2. (below) Priore's laboratory. Workbench now has coil installed. The rippling magnetic field descended vertically through the patient. The magnetic field was modulated by the wave/antiwave output of 17 EM waves mixed in a rotating plasma in a giant mixer tube.



December 1, 1994

Overview

In the late 1960s and early 1970s, Antoine Priore and a team of leading French scientists demonstrated conclusive, total remissions of terminal tumors and infectious diseases in hundreds of laboratory animals. Their research was performed under rigorous scientific protocols and funded by the French Government. The approach employed very complicated mixing of multiple EM signals in a rotating plasma, and modulating the mixed output upon a very strong rippling magnetic field to which the body of the test animal was exposed. Complete remission of the treated diseases was obtained. In addition, the animals' immune systems were also restored to normal. Further, disease-specific antibodies were also created: a single drop of blood drawn from an animal that had been treated and recovered, and injected into the body of a second animal with the same terminal illness, resulted in total remission of the disease in the second animal *and its total recovery.* In the mid-70s Priore's work was suppressed, because of hostility of the oncology community, change of the French Government and loss of further funding, and complete inability of physicists and biological scientists to even hypothesize a mechanism for the curative results.

After a 10-year struggle to discover the Priore mechanism, the present author has proposed a sweeping new explanation for the exact Priore curative mechanism. It represents a totally new kind of medical therapy – one which can dramatically treat and cure a breathtakingly wide variety of diseases. The electrical physics is based on the Stoney, Whittaker, and Ziolkowski decomposition of the scalar EM potential into bidirectional EM wave pairs. Deliberate assembly of such a structure forms a *vacuum engine* of nested curvatures of local spacetime.[1] Priore unwittingly made such a hyperspatially structured vacuum engine, one with the special characteristic that it *time-reversed* (dedifferentiated) diseased cells back to their earlier normal state. The Priore approach not only produces remission of a specific targeted disease, but also fully restores the cells and "factories" of the patient's immune system because they too revert back to their previous healthy condition.[2]

---

[1] *In short, Priore found and utilized a method of electromagnetically engineering general relativity in the laboratory – something physicists had not done and have no knowledge of. Neither have they done it overtly today, and neither do they have knowledge of it today.*

[2] *We point out that chemistry is largely driven by charge and charge distribution. The new methodology essentially controls charge and its distribution. Hence it can control and order all the biochemistry.*

Becker et al have shown conclusively that very weak DC currents and pulsed magnetic fields can produce cellular dedifferentiation (change to a previous state) and redifferentiation (change forward to a new state). It follows that transcription (change of the genetics) must also be altered correspondingly. Becker was nominated for a Nobel Prize for his experimental and theoretical demonstration of the mechanism. He also proposed a fundamental electrical control mechanism to account for his revolutionary results.

Kaznacheyev et al have shown that almost any cellular disease or damage can be transferred electromagnetically from one cell culture to another under special conditions. Popp has theoretically and experimentally shown that an electromagnetic master cellular control system exists in the body, as indeed has Becker. Thus it is clear and independently demonstrated that (1) disease can be created or reversed electromagnetically, and (2) the fundamental cellular control system is electromagnetic in nature. We comment that, viewed as physical materials, the cells and their constituents are sufficiently nonlinear that their EM functions, responses, and effects transcend the present classical EM model. A modern addition to nonlinear electromagnetics is the methodology and results of nonlinear phase conjugate optics (NLO). Accordingly, understanding of the higher topology EM/bioeffects functioning requires application and understanding of NLO principles, *regardless of frequency band.*

We also extend the general relativity model by addition of higher topology EM. We incorporate the Stoney/Whittaker/Ziolkowski decomposition of the scalar EM potential into hidden bidirectional waves. This is then applied to structure and engineer the vacuum. The method is also capable of structuring and engineering both mind and matter.

As a case in point, the elements of the new EM bioeffects approach are applied to the Gulf War Syndrome – the strange conglomerate of illnesses and symptoms developed by many Gulf War participants, usually beginning shortly after their arrival back in the United States from the MidEast. Previously unrecognized biological effects of a dense EM signal environment are advanced and their causative mechanisms explained. These new "dense signal environment" bioeffects, coupled with other simultaneous biologically-active suppressants, allow a full explanation of the Gulf War Syndrome and its characteristics. Both normal and anomalous symptoms are explained.

The Priore approach extends and complements Becker's pioneering approach by allowing positive engineering control of dedifferentiation of cells and their redifferentiation. A cancer cell may be regarded as a dedifferentiation or partial dedifferentiation of a normal cell back toward a more primitive or "immature" geological form. In NLO terms, this is a form of phase conjugation (time reversal) of the cell back toward a previous state, or even its *ancestral* cellular form *(see figure 1 below).* By phase conjugating the cancer cell anew and amplifying the process, the diseased cell can quickly be reversed back to a normal cell.

It is possible, using the Priore technique, to phase conjugate cells in the body, including all of them simultaneously if need be. Further, conjugation can be made specific to the type of cell or tissue one desires to affect. One need not "know" the specific disease's "EM signal complex," one must simply "pump the cell correctly" where it and its parts are treated as pumped phase conjugate mirrors (PPCMs). In a higher EM topology, the "diseased-cell-as-a-PPCM" already possesses a special "standing signal wave" input that represents the erroneous *vacuum engine* associated with the change to the specific disease state. Pumping the cell *in this special EM topology* creates the precise, amplified *vacuum anti-engine* in this same special EM topology and renormalizes the cell.

Because of the special EM topology utilized, direct engineering of both mind and matter are provided by the new approach, which also represents a unification and extension of electromagnetics, quantum mechanics, general relativity, and biology. It should be capable of reversing most physical and mental disorders that assail a biological organism.

INTRODUCTION

In this paper we discuss the present method of utilizing EM energy in science and engineering, and also discuss a radically different second method that is beginning to emerge *(see Table 1 on following page).* The main text is an overview, with technical elaboration in the footnotes.

The first (Type 1) engineering method may be likened to a leaky pipe: We always pour in more energy than the work we get back out. We have to furnish the primary energy used to do the work from an external source. A few of our devices, such as a common heat pump, are open systems extracting and using some excess energy from an external source. These devices may have a coefficient of performance (COP) – work output of the machine divided by work done on the machine to run it – of greater than unity. However, the vast majority of our machines have COPs of less than 1.0. Many of them have COPs of less than 50%, and many have COPs of less than 30%.


ESSENTIALLY ANAEROBIC ATMOSPHERE
CHANGE OF ATMOSPHERE TO AEROBIC (INCLUDES OXYGEN)
EVOLVE TO
EVOLVE TO
MULTICELL AEROBIC* (INCLUDES MAN)
CENTRAL CONTROL
BIOGENESIS
SINGLE CELL ANAEROBIC
SINGLE CELL AEROBIC*
SINGLE CELL COMPONENTS
MULTICELL COMPONENTS
IMMUNE SYSTEM
RED CELLS
WHITE CELLS
KILLER CELLS
ETC.
TISSUES
MUSCLES
BONES
ORGANS
SKIN
STRUCTURES
FACULTATIVE ANAEROBES (SINGLE CELL BOTH AEROBIC AND ANAEROBIC)
OBLIGATORY ANAEROBES SINGLE CELL SHIELDED FROM OXYGEN
* NOTE: LIMITED ANAEROBIC RESPIRATION STILL TAKES PLACE IN HIGHER AEROBIC LIFE FORMS, INCLUDING MAN.
EVOLUTIONARY TIME

Figure 1. Cellular path taken in development of aerobic cells and multicellular bio-organisms. Dedifferentiation of a cell or small group of cells back before centralized cell control yields cancer. The body's control system orders the cell to dedifferentiate back toward an anaerobe, breaking its own control.

As can be seen, Type 1 engineering is very wasteful of energy! In a sense, the present struggle to attain room temperature superconductivity is a struggle to eventually have many more machines that attain a COP approaching 1.0, and so decrease the waste of energy in our

Table 1. Two Ways To Do Engineering.

- *Type 1* Engineering: Vacuum Quiescent, Use External Energy Upon Matter
  - Does not involve mind, thought, life, time streams
  - Time is not an observable
  - Must furnish all the energy
  - Western science uses this method.
- *Type 2* Engineering: Gate and Structure the Vacuum Flux Itself
  - Involves mind, thought, life, time streams
  - Time is an observable
  - Furnish only initial energy, and maintenance
  - Use vacuum's energy (vacuum engines)

Type 1 machines. Vacuum engines allow COPs of far greater than 1.0.

After several decades of painful progress in understanding the nature of the quantum mechanical vacuum, today it is accepted in physics that the vacuum itself is a seething inferno of electromagnetic energy. It is thus a legitimate source of energy, could we but extract and use it. This is now accepted both by leading physicists and by the U.S. Patent Office. Further, as of 1993 it has been clearly shown that, contrary to conventional objections, thermodynamics does not rule out the extraction and utilization of the vacuum's energy as heat and power to operate our engines.[3]

We have now reached one of the great scientific plateaus of history: (1) *The vacuum is energetic, containing an incredible density of electromagnetic energy in a violent flux;* (2) *at least in theory, it is possible to extract energy from the vacuum and utilize it;* and (3) *every particle of mass exists as a nonlinearity in a violent flux of virtual particle energy exchange with the vacuum. In short, every system is an open system, being violently "driven" by the vacuum flux, where normally the "driving flux" is in equilibrium or nearly so.*

This paper briefly describes a great new scientific breakthrough which is approaching as a result of the new understanding of the vacuum energy. This new scientific development will usher in the greatest change to humanity of all time *(see Figure 2)*. It is characterized by the laboratory ability to: (4) Deterministically structure and gate the vacuum's fierce flux of virtual particle energy – even at a distance – and make the vacuum itself an ***engine*** to do any kind of work on an embedded physical system that we choose.[4] (5) Deterministically form a quantum potential, and utilize this potential to achieve essentially instantaneous action at a distance.[5] (6) Engineer the hidden inner structure of any potential; this includes also the potential for the Schroedinger equation, including Bohm's ***quantum potential,*** so that physical reality can actually be engineered prior to the collapse of the wave function and the occurrence of the quantum change. This is engineering and altering an entity in its *pre-reality state.* (7) Engineer and alter the flow of time and the laws of nature in a particular area, including the entire planet or solar system. (8) Simply and cheaply treat and cure essentially every present infectious disease and many other abnormalities. This includes cancer, leukemia, AIDS, malaria, sleeping sickness, arteriosclerosis, etc. – even mental disorders. It also includes reversing the effects of the aging process. (9) Directly engineer, form, create, heal, or modify mind, thought, long-term memory, life, etc.[6] And finally, (10) Directly engineer and alter the species quantum potential, an entire species, and the planetary quantum potential for all species and all living creatures on earth.


Vacuum Engine Concept
VACUUM ENGINE TEMPLATE #1
DELTA MASS
DELTA ENGINE TEMPLATE
VACUUM ENGINE TEMPLATE #2
MASS STRUCTURE AND DYNAMICS #1
+
NO TIME DELAY
MASS STRUCTURE AND DYNAMICS #2
VACUUM ENGINE TEMPLATE #1
DELTA ENGINE TEMPLATE
VACUUM ENGINE TEMPLATE #2
MASS STRUCTURE AND DYNAMICS #1
+
AFTER TIME DELAY
MASS STRUCTURE AND DYNAMICS #2

Figure 2. The vacuum engine concept. Addition of a vacuum engine (lower block diagram) alters mass and its dynamics after a time delay. Type 1 engineering uses the top level block diagram.

---

[3] *Daniel C. Cole and Harold E. Puthoff, "Extracting Energy and Heat from the Vacuum,"* ***Physical Review E,*** *48(2), Aug. 1993, p. 1562-1565.*

[4] *In other words, to perform vacuum engineering, extended from the suggestion of Nobel Laureate T.D. Lee* ***(Particle Physics and Introduction to Field Theory,*** *Harwood, New York; Chapter 25: Outlook, "Possibility of Vacuum Engineering," p. 824-828.). Lee recognizes that vacuum engineering can in theory be accomplished, but also that this has never even been tried.*

[5] *For a presentation of the mechanism for creating a quantum potential, see T.E. Bearden,* ***Gravitobiology,*** *Tesla Book Co., Chula Vista, CA, 1991, p. 33-36.*

[6] *The weapons developers are slowly grappling their way toward this new science, which the Russians call energetics. Application to the physical world at large is just referred to as energetics. Application of energetics to mind engineering is called* ***psychoenergetics.*** *Application to the physical body and its structures is called bioenergetics. In the U.S., development of mind and behavior alteration and control is now being dealt with in embryonic fashion under the subject heading of nonlethal warfare.*

This paper is an informal "quick note" to point out the new scientific plateau and introduce the second kind of science and engineering. The new ***vacuum engineering***[7] offers the greatest threat to humanity that has ever existed,[8,9,10] and at the same time offers the greatest promise of benefit.

For our very survival, it is absolutely imperative that informed citizens be aware of this dramatic change, which is just now starting. The powerful new science and engineering must be controlled and used for humanity's benefit, not its detriment. Else it will eventually be let loose unrestrainedly, to destroy all life on earth – a possibility indicated by Nikita Khrushchev in 1960.[11]

THE FIRST KIND OF ENGINEERING (TYPE 1)

First there's the normal way to do engineering (Type 1), which we are all taught as engineers and scientists. Here the vacuum/spacetime itself stays *inert* and out of our way.[12] We ourselves furnish energy into or onto the system we are trying to move or activate, spilling some of this energy all the while, and we struggle until we get the mass to move and the system to operate and perform work.

This "first kind" of engineering is essentially a continual *wrestling match.* Nature herself is the opponent. The engineer furiously struggles with nature, to force her to do the work he wishes to do. *This is the only **overt** kind of engineering presently done on earth.* It is primitive and severely limited in what it can do. In Type 1 engineering, the mind and thought are not affected since the *flow of time connectivity* and the *flow of mind connectivity* are not affected.

THE SECOND KIND OF ENGINEERING (TYPE 2)

Clandestinely, however, the Russians (actually, the KGB) in their secret advanced weapons labs, and three other nations not hostile to the U.S., have also weaponized a second kind of science and engineering, but kept it firmly a secret of the highest order. The second kind of engineering (Type 2) is dramatically different, far more powerful, and essentially unlimited in what it can do. Some of the simpler elements have spilled into the open press. For example *(see Figures 3 & 4 on next page)*, Vlail Kaznacheyev and his colleagues have shown, in thousands of meticulous experiments, that almost any disease or damage to cells can be induced in an isolated cell culture by electromagnetic radiation from the diseased or damaged culture, if a full harmonic interval (infrared to ultraviolet) is open for electromagnetic (photonic) exchange between the cultures.[13] The present author's proposed mechanism for the Priore and Becker results also explains the Kaznacheyev results.[14] It also explains the decades-long Russian induction of health changes and diseases in the microwave radiation of the U.S. Embassy in Moscow.[15]

In Type 2 engineering, the background vacuum/spacetime itself is deliberately altered, structured, and made asymmetrical. One then uses this *struc-*

---

[7] *Terminology after Nobel Laureate Lee, ibid., p. 383. Lee points out that the microscopic structure of the scalar vacuum field is not utilized. The particulate flux structure can indeed be engineered, but this has never even been tried by conventional physicists. An excellent coverage of asymmetries and observables is given on p. 181-188. E.g., whenever a symmetry is spontaneously broken, a nonobservable (virtual entity) has become observable. There thus exist vacuum engineering mechanisms for the direct translation between virtual and observable states. Indeed, a whole new vista has opened in physics – some are calling it a "new physics" – due to the discovery that it is possible to directly amplify the virtual state into observable state. E.g., see Serge Haroche and Daniel Kleppner, "Cavity quantum electrodynamics," **Physics Today**, Jan. 1989, p. 24-30 for an overview. In 1979 the present author foresaw, albeit crudely, the emergence of virtual state engineering by means of a possible hyperspatial (virtual state) amplifier. See T.E. Bearden, "Virtual state engineering and its implications," National Technical Information System, Report AD-A065762, 1979.*

[8] *The Russian weapon engineers model the vacuum as a virtual EM dipole plasma, rather than as a simple particle flux; e.g., see A.V. Chernetski, "Processes in Plasma Systems with Electric Charge Division," Georgi Pleckonov Institute of National Economy, Moscow, 1989 for an introductory theoretical exposition of the basic model with respect to physical energy systems.*

[9] *Use of dipoles focuses immediately upon the hidden electromagnetics. Application of plasma theory then exposes the higher nonlinear EM aspects and the characteristics of a higher topology EM theory. Interestingly, Priore used all the elements fitting this theoretical model, employing a giant plasma-filled tube for multi-signal EM mixing, to produce "hidden EM" vacuum engines.*

[10] *Decades ago, the Russians also applied the virtual EM dipole plasma vacuum to the problem of direct engineering of mind, behavior, and cellular control functions. For the fact that they succeeded in decoding the mind/brain/s operations, see S.K. Lisitsyn, "New approach to the analysis of electroencephalograms," Problems of Bionics (**Selected Articles**), p. 16-25, National Technical Information System Report AD 730045. See also the various references by Kaznacheyev, sanitized by the Soviet State at the time to prevent revealing the actual primary mechanisms.*

[11] *For a partial discussion of Khrushchev's statement of the impending availability of such new Soviet superweapons, see Max Frankel, "Khrushchev says Soviet will cut forces a third; sees 'Fantastic Weapon'," New York Times, Jan. 15, 1960, p. 1.*

[12] *Technically the vacuum is always highly active, in violent flux exchange with all particles of mass. However, in Type 1 engineering this exchange activity is in equilibrium. So action and reaction are balanced in all directions. With no observable asymmetry, no single net force accumulates for the observer to see, and the vacuum appears to be an "emptiness."*

[13] *See Vlail Kaznacheyev and L.P. Mikhailova, **Ultraweak Radiation in Intercellular Interactions,** [in Russian], Novosibirsk, 1981. Vlail Kaznacheyev, "Electromagnetic Bioinformation in Intercellular Interactions," **Psi Research**, 1(1), Mar. 1982, p. 47-76 contains an English translation of much of the information referenced in Kaznacheyev's 1981 book. See Vlail Kaznacheyev et al, "Distant intercellular interactions in a system of two tissue cultures," Psychoenergetic Systems, 1(3), Mar. 1976; "Apparent information transfer between two groups of cells," **Psychoenergetic Systems,** 1(1), Dec. 1974; V.P. Kaznacheyev, "Information function of Ultraweak Light Flows in Biological Systems," in **Problems in Biophysics**, Novosibirsk, 1967, p. 7-18 [in Russian]; V.P. Kaznacheev and A.V. Troftmov, Cosmic Consciousness of **Humanity:** Problems of New Cosmogony. Elendis-Progress, Tomsk, Russia, 1992.*

[14] *See T.E. Bearden, Gravitobiology, Tesla Book Co., P.O.B. 121873, Chula Vista, CA 91912; 1991. See also Bearden, Cancer and the Unresolved Health Issues in the Biological Effects of EM Fields and Radiation, Tesla Book Company, 1993.*

[15] *The Soviets radiated the U.S. Embassy in Moscow with weak microwave radiation for decades, starting in the early 1950s. Anomalous health changes and diseases were induced in U.S. Embassy personnel. Three Ambassadors eventually died of leukemia-like illnesses of mysterious nature. The results of the Johns Hopkins scientific study of the Embassy radiation problem also provide strong evidence for the explanation, since health changes and diseases only occurred in those areas of the Embassy where the EM force fields from the radiation were zero. In other words, induced health changes occurred only in personnel in those Embassy areas where the potentials from the radiation had zero gradients, so that the potentials were persistent. This 100% correlation to persistent potentials exclusively, is exceptionally strong evidence that the EM radiation was the actual cause. If independent of the EM radiation, health changes would not have precisely correlated to any component of the radiation! The Johns Hopkins scientists were quite competent, but only considered classical EM theory (CEM) in their assessment. CEM assumes that, when the force fields are zero, the electromagnetic actions are zero. That of course has been disproved in quantum mechanics, which has shown theoretically and experimentally that the potentials, not the force fields, are the primary causes of all EM phenomena. [See Y. Aharonov and D. Bohm. (1959) "Significance of Electromagnetic Potentials in the Quantum Theory," Physical Review, Second Series, 115(3), 1959, p. 485-491; Bertram Schwarzschild, "Currents in normal-metal rings exhibit Aharonov-Bohm effect," Physics Today, 39(1), Jan. 1986, p. 17-2.] Even when the force fields are zero, the potentials may remain and provide real changes in charged particle systems by scalar interferometry. Indeed, the force fields do not even exist in vacuum, as CEM assumes. The Johns Hopkins scientists concluded – based on the erroneous CEM model they applied – that since no force fields were present where any of the health changes occurred, the cause could not have been the weak microwave radiation. Had it not been the radiation, some of the health changes would inevitably have occurred where the EM force fields were nonzero. The investigators' results falsified their own study's conclusion, by simple expectation mathematics. Had they known of the SWZ structured potential and its possibilities, they would have realized that by showing 100% correlation to the force-free potentials, they had actually proven that it was indeed the radiation that was the cause, and the force-free potentials component was the actual culprit The team was excellent; its tools failed it. For a complete discussion, see Bearden, Gravitobiology, 1991, p. 27-32.*


TWO OPEN-MOUTH BOTTLES
LOCKING BOLTS
LOCKING BOLTS
STOPPER
STOPPER
TRANSPARENT WINDOW PANE (THIN) (GLASS OR QUARTZ)
DISASSEMBLED

Figure 3. Kaznacheyev's two-chamber apparatus. A cell culture is divided into two parts. Left ones are damaged or killed. Effect is replicated in right cells through windowglass, but not quartz.


GRAVITON LATTICE TEMPLATES
SICKEN OR KILL
ENVIRONMENTAL SHIELDING
CELL CULTURE SAMPLE #1
QUARTZ CONTAINER
CELL CULTURE SAMPLE #2
QUARTZ CONTAINER
THIN WINDOW
• GLASS: No Effect
• QUARTZ: Delayed Effect

Figure 4. Kaznacheyev's cytopathogenic mirror effect: Death and disease transmission via graviton lattice templates. Quartz passes a minimum G-lattice, glass does not.

tured, asymmetrical vacuum to do the work and furnish all the required energy flow.

The vacuum is known to be a *seething inferno of energy.*[16] It is a violent flux of virtual particles, according to quantum mechanics (QM). A *virtual particle* is one which quantum mechanically arises out of nowhere and almost instantly returns to nowhere. It may be highly energetic and "hotter than a firecracker" while it exists. But its span of existence is so short that our instruments cannot *individually* detect it.

However, we can and certainly do experimentally detect the result of the interaction of *large numbers* of virtual particles. Physics states that all forces of the universe are caused by the exchange of such virtual particles. It is also theoretically and experimentally proven that every particle of mass is in a violent virtual particle flux exchange with the surrounding vacuum. Several experiments directly show this – the Lamb shift for one.[17] The Lamb shift is largely due to fluctuations of the hidden virtual flux exchange with the vacuum, and involves a local energy density far greater than the surface energy density of the sun's surface.

VACUUM ENGINES: ORDERING AND UTILIZING THE VACUUM VIRTUAL PARTICLE FLUX

In Type 2 engineering, one structures and orders the violent virtual particle flows of the fundamental vacuum/ spacetime (VST) itself.[18] Accordingly, it alters and orders the vacuum's violent energetic exchange with any mass particles and physical systems in the area. One *oneself* does not input the energy that does the actual work on the material system located in that region of VST. Instead, one only inputs the energy necessary for the *gating and directing* of the VST flux energy in that area. This structuring and gating of the virtual particle flux forms an organized, energetic pattern which I have dubbed a ***vacuum engine*** (after Nobel Laureate Lee's recognition that the vacuum itself could in theory be engineered, but that such had never even been tried).

This ***vacuum engine*** now does the work and furnishes all the working energy. We just have to pay to set up the *gating mechanism and the template* in the beginning, and continue to pay a little bit to sustain them. Literally we have created a stupendous *energy amplifier.*[19] By continuing to expend a little maintenance and steering energy, we can gate and utilize the energies of an enormous engine which can apply incredible energy densities, even at a distance. In principle it can apply anything from a feather's touch up to the explosion of a star. It can be used to engineer anything from a single particle or wave, to the atomic nucleus, to a planet or a sun.[20]

---

[16] *For a good overview of the active vacuum, see R. Podolny, Something Called Nothing: Physical Vacuum: What Is It?, translated by Nicholas Weinstein, Mir Publishers, Moscow, 1986, revised from the 1983 Russian edition. See also I.J.R. Aitchison, "Nothing's plenty: The vacuum in modern quantum field theory," Contemporary Physics, 26(4), 1985, p. 333-391; Jack S. Greenberg and Walter Greiner, "Search for the sparking of the vacuum," Physics Today, 35(8), Aug. 1982, p. 24-32; Richard E. Prange and Peter Strance, "The semiconducting vacuum," American Journal of Physics, 52(1), Jan. 1984, p. 19-21; Walter Greiner and Joseph Hamilton, "Is the Vacuum Really Empty?", The American Scientist, 68(2), Mar.-Apr. 1980, p. 154-164; Timothy Boyer, "The Classical Vacuum," Scientific American, Aug. 1985, p. 70. See also important papers by H.E. Puthoff: "Source of vacuum electromagnetic zero-point energy," Phys. Rev. A, 40(9), Nov. 1, 1989, p. 4857-4862; "Gravity as a zero-point fluctuation force," Phys. Rev. A., 39(5), Mar. 1, 1989, p. 2333-2342; and "The Energetic Vacuum: Implications for Energy Research," Speculations in Science and Technology, 13(4), 1990, p. 247-257.*

[17] *W.E. Lamb, Jr. and R.C. Retherford, "Fine structure of the hydrogen atom by a microwave method," Physical Review, Vol. 72, 1947, p. 241-243. Demonstration of the displacement of one of the fine structure electron states of the hydrogen atom by a frequency of about 1060 megacycles played a central role in the development of quantum mechanics, and earned Lamb the Nobel Prize. The observation makes the reality of dynamic vacuum fluctuations inescapably evident.*

[18] *Since the vacuum can be altered, we now must speak of various vacuua, not just one. "A" vacuum, "a" spacetime, and "a" scalar potential are synonymous. "The" ambient vacuum at any local point is a maelstrom of the scalar (hidden multiwave) interferometry of potentials from every charged particle in the universe (adapting Puthoff's Cosmological Feedback Principle). This scalar EM interferometry creates the EM fluctuations of the quantum mechanical vacuum, by Whittaker 1903 & 1904.*



Figure 5. Stoney/Whittaker/Ziolkowski internal EM biwave structure of the scalar EM potential.



Figure 6. Graviton lattices and nonlattices. Templates require G-lattices. Minimum lattice is one harmonic interval.

ENGINEERING GENERAL RELATIVITY & NESTING SPACETIME CURVATURES

We actually engineer general relativity (GR) itself, since the Stoney,[21] Whittaker,[22] and Ziolkowski[23] (SWZ) papers point the way to how to do just that *(see figure 5)*. In short, by using the SWZ approach, one is able to utilize electro-magnetics in a new way, to directly form these curvatures of local spacetime. We also *nest* these curvatures to form a ***template*** of structured multiple curvatures; this template constitutes the deliberate format of the vacuum engine *(see figure 6)*.

Indeed, this is a radically different concept of spacetime structure. It is well-known that, whenever one applies a local hidden variable theory, the GR theory of spacetime structure must be radically altered.[24]

We stress that, in Type 2 engineering, one directly extends, applies and engineers general relativity, but by a novel use of electromagnetics. As can be seen, establishment science is not doing that at all, but is doing only Type 1 engineering. Literally anything one wishes can be engineered in the Type 2 fashion, at least in theory, including transmutation of elements, materialization and dematerialization of matter, free energy electrical power sources, and antigravity. However, Type 2 engineering is even more powerful than that. It also is the ultimate form of virtual reality engineering, for it allows the direct engineering of both physical reality and the mind itself.

MIND, 3-SPACE, HYPERSPACE, MIND FLOW, AND THE FLOW OF TIME

Mind exists in time, but not in our familiar 3-space. Mind does not exist spatially in the same 3-space in which we model physical phenomena.[25] Mind occupies (to the physicist) only one dimension – the time dimension – of Minkowski's 4-space of physical matter. This means that the attachment of mind to matter (in a living biological organism) involves a *mind flow* process, hidden in and occupying the *time flow* process *(see figure 7 below)*.


PHOTON
L^2T
MASS
L^3
MASSTIME
L^3T
PHOTON
L^2T
MASS
L^3
$(\triangle E)(\triangle T) + M \Rightarrow (M+\triangle M)(\triangle T) \Rightarrow M + (\triangle E)(\triangle T)$

Figure 7. The photon interaction generates observed quantum change and the discretized flow of time. A particle usually connects to only a single delta T at a time. Every other particle is connected to that small increment of time also, as are all minds.

---

[19] *An example of such an actual amplifier was Floyd Sweet's vacuum triode –. a 6-lb., solid-state device containing special coils and two separated barium ferrite magnets. The magnets were specially activated by Sweet's proprietary process so as to powerfully self-oscillate at a chosen ELF frequency, such as 60 Hz. [Such self-oscillation of barium compounds are well-known, but at optical frequencies. Use of a photorefractive magnetic material that is also an insulator allowed Sweet to initiate self-oscillation at ELF frequencies.]. An input sine wave of 10 Volts and 33 microamperes then produced 500 watts of phase conjugate replica EM power, extracted from the self-oscillation energy between the vacuum and the magnets. The amplifier gain (COP) of this open system, self-oscillating, pumped phase conjugate mirror device was some 1,500,000. A successful antigravity test of the device was also performed by Sweet at my urging, and resulted in a controlled reduction of its weight on the laboratory bench by 90%. For as much as could be revealed of the operation and testing of Sweet's proprietary device, see Floyd Sweet and T. E. Bearden, "Utilizing Scalar Electromagnetics to Tap Vacuum Energy," Proceedings of the 26th Intersociety Energy Conversion Engineering Conference (IECEC '91), Boston, Massachusetts, 1991, p. 370-375. Unfortunately nothing can be done with the device – e.g., because of formidable legal entanglements due to the conflicting agreements Sweet made with different financial backers. However, McLain & Wooten have produced a repicable, tested, overunity device & full construction details have been rebuilt on Internet.*

[20] *In the modern geometrical view, all individual field energies come from the conglomerate structure called "gravitational field." Transforming one field energy into another kind may be done by first transforming the initial field energy back into G-field energy, then re-releasing the G-field energy as the desired new type of field energy. Vacuum engines allow control and utilization of this process.*

[21] *G. J. Stoney, "XLVIII. On a Supposed Proof of a Theorem in Wave-motion, To the Editors of the Philosophical Magazine," Philosophical Magazine, 5(43), 1897, p. 368-373.*

[22] *E.T. Whittaker, "On the Partial Differential Equations of Mathematical Physics," Mathematische Annalen, Vol. 57, 1903, p. 333-355; "On an Expression of the Electromagnetic Field Due to Electrons by Means of Two Scalar Potential Functions," Proceedings of the London Mathematical Society, Series 2, Vol. 1, 1904, p. 367-372.*

[23] *Richard W. Ziolkowski, "Exact Solutions of the Wave Equation With Complex Source Locations," J. Math. Phys., 26(4), April 1985, p. 861-863. See also Ioannis Besieris, Amr M. Shaarawi, and Richard W. Ziolkowski, "A bidirectional traveling plane wave representation of exact solutions of the scalar wave equation," J. Math. Phys., 30(6), June 1989, p. 1254-1269. See also Michael K. Tippett and Richard W. Ziolkowski, "A bidirectional wave transformation of the cold plasma equations," J. Math. Phys., 32(2), Feb. 1991, p. 488-492.*

[24] *E.g., see Abner Shimony, "Events and processes in the quantum world," in Quantum Concepts in Space and Time, Eds. R. Penrose and C.J. Isham, Clarendon Press, Oxford, 1986, p. 192: "...local hidden variable theories may be possible only if relativity theory is replaced by a radically different theory of spacetime structure." (My comment is that this should not be surprising, since classical electromagnetics, quantum mechanics, and general relativity are in profound contradiction of each other, and cannot be unified as they are, in spite of decades of Herculean efforts by many excellent physicists).*

[25] *We may model a mind as a separate 3-space, and its functional operations as "physical" in that hyperframe. Thus a mind and its operations are hyperspatial and outside physical matter's 3-space. Both mind and matter 3-spaces share a common 4th (time) dimension. So it requires at least seven dimensions to model a living creature, eight to model a species, and nine to model all life on earth. The 4th dimension of the mindworld hyper-4-space coincides with the 4th dimension of the physical world's Minkowski 4-space. A priori, mind/matter engineering operations involve engineering and structuring the time stream. This allows engineering either physical reality or mental reality or both simultaneously.*

Normally, so QM tells us, the observation process destroys time, so that all "observables" are spatial only. So the completion of each observable change in a living mass system momentarily destroys the only connection that the mass had with its associated mind! It vanished in the so-called "collapse of the wave function."[26,27,28] Fortunately, little pieces of time are always being serially added and subtracted by the ubiquitous photon interaction process with every mass. Hence the body's particles of mass are continually being *connected to* and *disconnected from* little serial bits of the time stream, and from corresponding serial bits of the *mindstream* of that individual.

TYPE 2 DISRUPTION OF TIME AND MIND

Type 1 engineering does not disrupt or affect the flowing time stream. Hence it does not disrupt or affect the flowing mindstreams of biological systems in the vicinity.

This is not necessarily true of Type 2 engineering! Type 2 engines of appreciable power can and will disrupt and destroy the body's continual detachment from and reattachment to its mind-stream. Type 2 engines will appreciably disrupt and alter the flowing time stream, and thus disrupt and alter the flowing mindstreams of all life forms in the vicinity. The size of the "vicinity" depends upon the size of the engine.

So to beneficially utilize vacuum engines, we do not strive for control of vast energies. We must use a surgeon's scalpel, so to speak, instead of a giant steam hammer. If one seeks weapons, on the other hand, one will strive for control of much greater vacuum engine energies. The KGB secret laboratories, e.g., have pursued this goal for over four decades. Several generations of Type II weapons have been developed and deployed, all under continued KGB control and operation. These Type 2 weapons could, in the words of Khrushchev's address to the Presidium in January 1960, "*...wipe out all life on earth if unrestrainedly used.*" Now one can easily see how that could happen: ***Any massive use of Type 2 weapons will substantially upset the time stream on earth, including all individual time streams. It will so disrupt all the mind streams of all earth's creatures that their connections to their physical bodies will be instantly broken.*** At least now we know why Brezhnev himself was so frightened of these weapons in 1975.[29]

Another unusual characteristic of Type 2 engineering is the *slowly decaying persistence of any special vacuum engine structure artificially created in the vacuum.* We may analyze this effect in terms of the "ghost forms" of quantum mechanics.[30,31,32]

ENGINEERING THE MIND, ITS OPERATIONS, AND ITS CONTENTS

The vacuum engine affects/curves/structures not only the three *spatial* dimensions of ST, but also the *time* dimension. Hence the vacuum engine approach can be used to engineer not only the observable physical matter (which is 3-spatial), *but also the mind and thought (which are time-like to the external observer).* Literally one can "get into the mind's connection channel" and alter the mind, its contents, and its operations at will by using appropriate vacuum engines.

By appropriately and selectively nesting the spacetime (ST) curvature structuring, one can even reach beyond the

---

[26] *Rigorously, the emission of a photon by the living mass destroys its time channel, thus collapsing the wave function and disconnecting the mind. Absorption of another photon immediately thereafter adds an increment of time back to the mass, forming* **masstime** *and reconnecting the time channel and hence the mind channel. Mass does not exist in time per se; masstime does. The temporary disconnection of the time channel by photon emission causes the wave function to collapse; a priori a wave cannot exist without some time available in which to wave! This in fact produces the observable mass from masstime. The problem is that the physicists have ignored the transport by the photon of* Δt *as well as* ΔE*. Thus they have not noticed that the ubiquitous photon interaction with a mass creates the continual addition and subtraction of time increments. This continual coupling and uncoupling of mass to and from the time dimension creates a* **discretized** *flow (passage) of time for that mass. This continual connection and disconnection of a mass to and from only a tiny little piece of the time channel is responsible for the past and the future not being observable; "being observable" is simply being connected to a single small* Δt *increment, not all the increments that have gone before or that will follow hence. When one looks at the corner of a room, the 3-spatiality of one's mass instrumentation system is why one can see length, width, and height but not the fourth dimension, time.*

[27] *Since the photon interaction – including the virtual photon interactions – can be engineered, obviously the passage of an object through the discretized timestream can also be engineered, electromagnetically. Not only can a photon, electron, or proton be time-reversed, but also an assemblage of photons, electrons, protons and neutrons can be time-reversed. Among other things, this means that a diseased living physical cell can be time-reversed (dedifferentiated) back to a previous healthy state, as shown by Priore and also by Becker. Kaznacheyev, as does Becker, also shows that healthy living cell can be "time-forwarded" (differentiated) to a new state, if bombarded with the weak vacuum engine templates (graviton lattice structures) for that state. The minimum graviton lattice (ordering of SWZ wavepairs) utilizes one harmonic frequency interval. Thus quartz will pass Kaznacheyev's cytopathogenic effect, since it passes IR to UV – one harmonic interval. Ordinary window glass does not pass a complete harmonic interval, hence cannot pass the minimum graviton lattice and destroys the disease-inducing vacuum engine template.*

[28] *Since the entire area is highly nonlinear, then nonlinear oscillator theory applies. Graviton lattices may therefore be activated harmonically or subharmonically. This means that "optical band" results can be initiated by analogous subharmonic input – e.g., microwaves or even sound waves. G-lattices work like music; one recognizes a C-chord regardless of the octave. In similar manner, vacuum engines (G-lattices) may be shifted by any number of octaves, with initiation of results then being delayed in the responding physical systems, as prescribed by nonlinear oscillator theory.*

[29] *See Christopher S. Wren, "Brezhnev Talk for Accord against 'Terrifying Arms'*, New York Times, *June 14, 1975, p. 1, 11.*

[30] *Since statistically every possible change in the vacuum is constantly and continually occurring in each and every differential volume, no matter how small, then from time to time in that maelstrom any physical (and mental) template we care to visualize appears, exists for a very short but finite time, then disappears, then reappears, etc. Such a continual, untidy characteristic is called a* ghost form, *and usually downplayed or ignored in the teaching of QM because it is "unpleasant." However, anything and everything – no matter how bizarre and whether living or inert – has a small but nonzero "density of reality" in the vacuum flux. Everything that ever was or will be, and everything that never was and never will be, is also there. The point is, creation of a vacuum engine template for a ghost form adds energy to (activates) that form. Just as a Dirac "ghost form electron" can be lifted from the vacuum by adding energy, so can any other ghost form, be it "living" or "dead." The process is fundamental and not just for electrons. Adding energy to a ghost template, we increase the local energy density of that ghost form in all electrical potentials in the entire area. This structuring of vacuum spacetime extends radially in all directions, tailing off to zero at infinity. When the inputting energy is ceased, the energized/activated form will then gradually decay over a period of time.*

[31] *We may compare the activation, persistence, and decay of the ghost form to an accumulator fed by two inputs, one blue liquid and one yellow liquid, with an outlet pipe on the opposite side. Suppose only the blue pipe is turned on; the tank is filled with blue liquid and blue liquid comes out the outlet. Now we turn on the yellow valve, and yellow liquid also starts entering. Over a period of time, the liquid in the tank will gradually turn green, as will the fluid from the outlet. Now we turn off the yellow valve. Over a period of time, the fluid in the tank will gradually turn back to blue color, as will the outlet liquid. Energizing and decaying ghost template structuring of the vacuum works the same way.*

[32] *For inputs that have raised the ghost template near or above the observable (quantum) threshold, this "decay time" may be quite long. Golden once accidentally charged up his local area with such a local template, in a powerful experiment that lasted about eight hours. Materializations occurred, determined by the thought-form (steady ghost form) inputs from the minds of the unintentional participants. In addition, interference with the timestream occurred, as indicated by all local clocks – mechanical, electrical, pendulum, etc. – going substantially astray. The materializations decayed away in a couple of hours, simply dematerializing back into the virtual state when their average energy density level reduced past the quantum threshold. It required four days for the entire "ghost template" to decay away and for the clocks in the area to fully resume normal operation.*

ordinary 3-space and get directly into the higher dimensional space one may mathematically use to model the mind *(see figure 8)*. One can then directly "engineer" in that *pure mind* arena (in the *mental spacetime*, in the modeling sense). This capability, I believe, was responsible for Brezhnev's vivid fear of these weapons in 1975, and his statement to visiting U.S. senators that, not only must the nations of the earth ban nuclear weapons, but also the development of new weapons of mass destruction *"more frightful than the mind of man has ever imagined."*[33] Gromyko later introduced a draft treaty to that effect to the United Nations the same year, and urged the nations of the world to sign it.[34] Article one of the draft treaty stated that the Russians would identify the type of weapons when negotiations on the treaty started. *No one had the slightest notion what the Russians were referring to.* However, three other nations – not hostile to the U.S. – later did develop some of these Type 2 weapons. The Soviet Union was already engaged in operational testing against U.S. and other targets, with incidents mistaken for "accidents" or "anomalies" by the world's news agencies.[35] During the beginning of the 1980s the three nations began checking the Soviet Union by demonstrating their own use of the weapons against Soviet targets. Again the open press did not recognize the true nature of the incidents involved. At the close of the 1980s the triad *vigorously* "checked" the Soviet Union, clearly demonstrating their ability to devastate the Soviet Union should it attempt to devastate friendly nations.

So a special case of "deterrence by massive retaliation" came into being in the Type 2 weapons area as well as in the conventional and nuclear areas. Does the reader recall, e.g., the mysterious explosion of several Soviet missile ammunition storage sites in the space of a few months in 1983-84?[36] A single one of these explosions destroyed a third of all the missiles in the entire Soviet Northern Fleet. There were other major incidents whose true nature and cause went unnoticed.



Figure 8. The 7-space EM potential. In observer 3-space (top figure), the potential is composed of a virtual particle flux. In hyper 3-space, the potential is a harmonic series of a SWZ bi-directional EM wavepairs.

Frustrated in the intent to dominate the world by surreptitious, delicate use of its Type 2 weapons, the economy of the Soviets simply fell apart. The Berlin Wall was torn down and the Soviet Union broke apart into independent regional nations.

In that upheaval of the Soviet Union, however, the KGB remained intact, well-funded, and still firmly in possession and control of the Type 2 superweapons, including development, manufacturing, deployment, manning, and operational employment.[37,38]

WHEELER'S PRINCIPLE AND ITS EXTENSION

Einstein has strongly pointed out the necessity to review foundations *(see table 2)*.

The great physicist Wheeler has a very nice statement on the curvature of spacetime. Briefly, he summarizes the gist of GR as *"Geometry tells mass how to move, and mass tells geometry how to curve."*[39] By "geometry" he is referring to *spacetime*. So we may immediately sub-

---

[33] *Wren, 1975, ibid.*

[34] *Prohibition of the Development and Manufacture of New Types of Weapons of Mass Annihilation and of New Systems of Such Weapons, draft treaty introduced by Gromyko at the United Nations' 30th session of the General Assembly, New York, Sept. 23, 1975. The first article provided that the types of these new weapons would be "specified through negotiations on the subject."*

[35] *A long list of these incidents has been published by this author, through the Tesla Book Company. See T.E. Bearden, Soviet Weather Engineering Over North America, 1985; Fer-de-Lance, 1986; AIDS: Biological Warfare, 1988, Analysis of Scalar Electromagnetics, 1990, and Gravitobiology, 1991.*

[36] *See photograph, Jane's Defence Weekly (JDW), 2(3), July 28, 1984, p. 92; see also Mark Daly, "Goa and Goblet SAMs in Severomorsk explosion," JDW, 2(6), Aug. 18, 1984, p. 224; Derek Wood, "Soviets' northern fleet disabled... 'not viable' for six months," JDW, 2(1), July 14, 1984, p. 3; Derek Wood, "Six explosions in the past seven months," JDW, 2(1), July 14, 1984, p. 3; John Moore, "The aftermath of Severomorsk," JDW, 2(6), Aug. 18, 1984, p. 224.*

[37] *To survive as the leader of Russia, Yeltsin of necessity formed a pact with the KGB. KGB support insured that no coup of substance could be mounted against him, and that the KGB would insure his remaining in power. In return, Yeltsin saw that the KGB was well-funded, remained intact, retained all its secret weapons laboratories and secret weapon scientists and manufacturing facilities, and retained and continued to operate all its deployed, operational superweapons. The KGB changed its name and continued business on a less public profile. Publicly it officially turned a "much gentler face" toward the Russian citizenry. But essentially the KGB still controls most of the Russian military officer corps. Through the KGB/military connection the Communist Party can still accomplish a military coup and seize control of the country again, at least for the foreseeable future, when it chooses to do so. The Russian threat has not disappeared; it is simply hibernating.*

[38] *The Communists/Generals in control of the KGB and these superweapons are perfectly capable of turning the unfortunate dissolution into an excursion scenario of their long-planned major concessions offensive prior to ultimately striking the West with a clenched fist and destroying it. The communist aim has not changed one iota since 1917, although the communists have temporarily lost or relinquished control over the Russian civilian populace. For a description of this "29th move of the chess game," see T.E. Bearden, "Glasnost: 29th Move of a 30-Move Chess Game," Raum & Zeit, 1990.*

[39] *W. Misner, K.S. Thorne and J.A. Wheeler. (1973) Gravitation, W.H. Freeman and Co., San Francisco, 1973, p. 408. On p. 5 the principle is stated as "Space acts on matter, telling it how to move. In turn, matter reacts back on space, telling it how to curve." Thus space is already a vacuum engine that acts on matter, and mass-energy acts on space to curve it.*

Table 2. Einstein on Reviewing Foundations

"...the scientist makes use of a whole arsenal of concepts which he imbibed practically with his mother's milk; and seldom if ever is he aware of the eternally problematic character of his concepts, He uses this conceptual material, or, speaking more exactly, these conceptual tools of thought, as something obviously, immutably given; something having an objective value of truth which is hardly even, and in any case not seriously, to be doubted. ...in the interests of science it is necessary over and over again to engage in the critique of these fundamental concepts, in order that we may not unconsciously be ruled by them."

Albert Einstein, "Foreword," in Max Jammer, Concepts of Space: The History of the Theories of Space in Physics, Harvard University Press, Cambridge, Massachusetts, 1969, p. xi-xii.

Table 3. Wheeler's Principle and a Corollary

Wheeler

"Geometry tells mass how to move, and mass tells geometry how to curve."

By "geometry" is meant "spacetime." Translating: "Mass tells spacetime how to curve, and curved spacetime tells mass how to move."

Corollary

"Trapped EM energy tells spacetime how to curve. The structuring of that trapped EM energy tells the resulting curved spacetime how to nest its curvatures. This forms a vacuum engine. Its nested curvatures of local spacetime tell mass and energy how to structure and move. By forming vacuum engines deterministically, one may use them to affect, alter, and change local mass, energy, and mind as desired."

stitute synonyms to yield "Mass tells spacetime how to curve, and curved spacetime tells mass how to move."

We further modify and extend this latter statement, replacing mass by its trapped EM energy (this is consistent with general relativity) and adding nesting of such trapped energies. We also allow for altering the timestream, the mind, and the mindstream. With these modifications, a corollary to Wheeler's principle results as follows: *"Trapped EM energy tells spacetime how to curve. The structuring of that trapped EM energy tells the resulting curved spacetime how to nest its curvatures. This forms a* ***vacuum engine.*** *Its nested curvatures of local spacetime tell mass and energy how to structure and move. By forming vacuum engines deterministically, one may use them to affect, alter, and change local mass, energy, and mind in any manner desired" (see table 3).*

To gain a "feel" for spacetime curvature, one may visualize it as analogous to the variation of local pressure in a gas or fluid.[40] Using the earth's atmosphere as a model, we may precisely create pressure points and areas (lows and highs) throughout, and gradually move them at will. This control of highs and lows will allow control and direction of the atmospheric flows. Theoretically, the entire atmospheric flow of the earth can be steered and controlled, by using such an approach. In short one can directly "steer" the weather worldwide, or over a given continent. Present Russian development allows this weather control process to be done sufficiently to control and steer the great jet streams, with concomitant direct influencing of the weather.[41] *We have not had any truly "normal" weather over the U.S. since 1976.*

TYPE 2 ENGINEERING IS JUST BEYOND THE PRESENT VANGUARD OF SCIENCE

As can be appreciated, Type 2 engineering is beyond vanguard science. The forefront of orthodox science is still where Wheeler's original statement is, and does not apply the SWZ methodology nor nesting of spacetime curvature. Science still does not even try to create vacuum engines and perform vacuum engineering *(see table 4 on page 76)*. Conventional scientists are still very firmly rooted in Type 1 engineering.

In ordinary GR, nowhere does there appear a precise definition of the term "gravitational field."[42] The G-field is just a *conglomerate of loose things*, and – by Sakharov's postulate – not a fundamental field of nature at all.[43] It already follows that, since "gravitation" is "geometry of spacetime," then "curvature" of spacetime is achieved by altering and changing the "conglomerates that comprise G-field" from their ambient conditions. The ability to structure and nest such curvatures also follows in straightforward fashion.[44]

PUMPED PHASE CONJUGATE MIRRORS AND THE PRIORE MECHANISM

The astounding thing is that Antoine Priore, using pure intuition, was able to arrive at an exact process for forming a special kind of beneficial vacuum engine![45]

We know today – but scientists did not know it when most of Priore's work was being done! – that a highly nonlinear material acts as a ***phase conjugate mir-***

---

[40] *It is actually the variation of the local energy density of the vacuum from its normal value.*

[41] *See T.E. Bearden, Soviet Weather Engineering Over North America, 1-hr. videotape, 1985. Available through the Tesla Book Co. In the last few years, the Russians have substantially increased their weather engineering capability and activity. Most of the transmissions from this system are now fairly good electrogravitational waves (coupled wave/antiwave pairs), with EM imperfections many dB below signal level. Hundreds of them are utilized when the system is actively employed over the U.S. By applying Whittaker 1904, these signals – invisible to the normal receiver – can be received and displayed.*

[42] *Misner, Thorne and Wheeler, Gravitation, 1973, p. 399.*

[43] *A.D. Sakharov, "Vacuum Quantum Fluctuations in Curved Space and the Theory of Gravitation," Soviet Physics Doklady, Vol. 12, 1968, p. 1040-1041 [English translation.] Sakharov's article (in Russian) is in Doklady. Akad. Nauk SSSR, Vol. 177, 1967, p. 70-71.*

[44] *General relativists already accept the vacuum as containing a 4-momentum-flux river. See Misner, Thorne, and Wheeler, Gravitation, 1973, p. 130-131. They treat the stress energy tensor as a machine (ibid., p. 131). The only difficulty is that they have not realized that, by applying the SWZ approach, much more complicated "vacuum machines" than they have considered can be built and utilized electromagnetically.*

[45] *See Christopher Bird, "The Case of Antoine Priore and His Therapeutic Machine: A Scandal in the Politics of Science," Explore!, 5(5-6), 1994, p. 97-110 for an excellent summary of the Priore Affair. The Priore group cured terminal tumors, sleeping sickness, and arteriosclerosis in lab animals and restored suppressed immune systems. Eminent, even world-renowned French scientists worked with him. The work was funded by the French government and published in leading French scientific journals. It was suppressed when the French government changed to a leftist government in the mid 70s.*

ror[46,47] *(see figures 9 & 10).* In other words, when one puts in a sine wave, e.g., in addition to producing harmonics the nonlinear material will also produce a strange, backward-traveling replica of the input wave. This "backward wave" has been well-known since the early 1970s. It is truly a *time-reversed* wave (Barus wrote the solution much earlier).[48] It will backtrack back through space, over the *exact* path taken by the input wave.[49,50] If the input wave is continuous, this "phase conjugate replica" (PCR) time-reversed wave will precisely appear everywhere in space that the input wave occupies.

The key here is "everywhere in space." It does not matter how tortuous and twisted the route taken by the input wave; the PCR will backtrack it and appear spatially superposed with it. This has been *experimentally* proven many times in nonlinear optics.[51] One concludes that the vacuum has a memory,[52] and the PCR wave can retrace the memory of the path previously taken by its stimulus.



Figure 9. Phase conjugate refection vs. mirror reflection.

Figure 10. Pumped phase conjugate mirror.



Another nice thing has been discovered and is used in the relatively new nonlinear optics. If one "pumps" the phase conjugate mirror with opposing waves (such as, e.g., bidirectional EM wavepairs), then up to all the energy in the pump waves is absorbed and re-emitted in the "crawfishing" PCR wave.[53] In other words, the stimulated PCM can be made into an amplifier of the time-reversed wave output, just by "pumping" it with the proper bidirectional wavepairs.[54,55]

ANOMALOUS "BIO-JAMMING" AND DEEP DIFFUSION BY EM SMOG

Pumping by EM waves or by simultaneously varying EM forces due to opposing streams of photons will produce a much higher probability of 4-wave mixing and multiphoton interactions. Simply put, this probability is a function of the sheer photon/signal density, along the lines pointed out – but not clarified – by

---

[46] *Elsewhere we have pointed out that, for the primary EM interactions with a living system, we must employ an electromagnetics of higher topology than the conventional EM (either vector or tensor). Barrett has shown that a higher topology EM will involve and exhibit nonlinear optical functioning without necessarily employing optical materials. See T.W. Barrett, "Tesla's Nonlinear Oscillator-Shuttle-Circuit (OSC) Theory," Annales de la Fondation Louis de Broglie, 16(1), 1991, p. 23-41. Thus if we wish to utilize higher topology EM functioning in and on the body/mind, or just to comprehend such functioning, the nonlinear optical processes will form part of that functioning. We must be familiar with phase conjugate optics functions, regardless of the frequency range we operate within, and we must examine the situation accordingly.*

[47] *In the conventional struggle to elucidate EM effects on biological systems, the failure to realize this higher topology principle has led to experiments that are often difficult or impossible to replicate, primary interactive mechanisms remaining a mystery, and the inability to definitively answer even the simplest question such as "Does power line radiation enhance the emergence of cancer and leukemia, and if so, how and under what circumstances?" Forty years of research by able and determined EM bioeffects scientists have thus failed us, because the model they so stringently apply is grossly in error. What they have thoroughly proved is that their fundamental model is incorrect and inadequate for the intended purpose for which it is being utilized. The solution is not to just continue more experiments in the same vein, but to revise the model itself. We have previously pointed out (Bearden, Cancer and the Unresolved..., 1993, ibid., p. 40) the present EM bioeffects model, the modification areas required, and how to ascertain when the adjusted model is correct.*

[48] *Carl Barus, "A Curious Inversion in the Wave Mechanism of the Electromagnetic Theory of Light," American Journal of Science, Vol. 5, Fourth Series, 1898, p. 343-348 gives the first known solution of Maxwell's equations for a time-reversed or "backwards-traveling" EM wave.*

[49] *According to the well-known "Distortion Correction Theorem" of nonlinear optics. For a precise statement of the theorem, see Amnon Yariv, Optical Electronics, 3rd Edn., Holt, Rinehart and Winston, New York, p. 500-501. See particularly Chapter 16: "Phase Conjugate Optics – Theory and Applications."*

[50] *For the space-borne laser, e.g., the U.S. uses iterative phase conjugation – known as self-targeting – of a booster-reflected laser signal to keep a powerful laser beam locked upon the same spot on a distant missile booster, rising during its launch phase, long enough to burn through the casing and destroy the booster, even 10,000 miles away. The process is known as phase conjugate shooting.*

[51] *A striking example is given by David M. Pepper (1986) "Applications of Optical Phase Conjugation," Scientific American, 254(1), Jan. 1986, p. 75. Possibly the best extant introduction to the subject of nonlinear optical phase conjugation is David M. Pepper, "Nonlinear Optical Phase Conjugation," Optical Engineering, 21(2) March/April 1982, p. 156-183.*

[52] *Without extended discussion we call attention to the importance of this finding with respect to homeopathic medicine and therapy. In fluids, obviously one proceeds from vacuum flux organization and memory upward through matter's organization (and hidden memory), through the individual particles of the nucleus, to the nucleus, to the atom, to the molecule, etc. Between the atom and the molecule levels we encounter hydrogen bonding actions in fluids, which is of great importance to the biochemistry, especially the protein chemistry. It is possible to show that the mind operations and the cellular control operations also SWZ structure the H-bonding activities of the body's aqueous fluid; it can also be shown that any chemical, drug, additive, and EM smog also structures and affects the H-bonding. However, further discussion of these two elements is beyond our scope for this presentation.*

[53] *Note that "pumping" is simply a expansion of the notion of stressing the material. Emission of the amplified PCR wave is a kind of piezoelectric release of the stress energy. The point is that physical stress of a material can be freely tapped and energy continually extracted, if that stress is varying. The McLain/Wooten device uses that principle.*

[54] *To create a normal PCR wave response to an overt EM signal wave input, nonlinear optics uses overt EM pump waves. For the hidden EM signal wave input – i.e., for the hyperspatial vacuum engine as input – one must use "hyperspatial" wave pumping. The "cell as a phase conjugate mirror" must be pumped by hidden (hyperspatial) EM waves inside a scalar EM potential. In the normal case, an amplified, normal EM PCR wave is produced in response to a normal signal wave input and normal pump waves. In the vacuum engine case, an amplified, hyperspatial EM PCR wave complex is produced in response to a hyperspatial signal wave input and hyperspatial pump waves.*

[55] *Note that the amplified PCR wave represents a reorganization and deterministic redirection of stress energy. Hence it is a time-reversed operation, and also a negentropic operation. Since the PPCM operates as an open system not in thermodynamic equilibrium, with input of excess energy in the form of the pumping, negentropic operation is permitted by nonlinear thermodynamics (of a system far from thermodynamic equilibrium) For a lay summary of such thermodynamics, see Gregoire Nicolis, "Physics of far-from-equilibrium systems and self-organization," in Paul Davies, Ed., The New Physics, Cambridge University Press, Cambridge, 1989, p. 316-47. For a more technical presentation, see G. Nicolis and I. Prigogine, (1987), Exploring Complexity, Piper, Munich, 1987. Prigogine received the Nobel Prize for his pioneering work in this field.*


Nonlinearity
(Shown for aerial vehicle, body cross-section)
Vehicle Body
Pumped Phase Conjugate Mirror Effect
Dense Signal Environment
PCM
PCR
PCR
Amplified Partial Cancellation of Internal Circuitry Signals

Figure 11. Single versus multiphoton penetration effects. Phase conjugation effects become of significance, generating PCR signals which couple to and backtrack the cells' and tissues' own signals, this penetrating throughout the body with weak partial cancellation jamming.

Devyatkov et al.[56,57] Thus dense electronic smog – even though it contains only extremely weak signals – increases the nonlinear optics type of interaction. This allows anomalously deep penetration and *diffusion* of special weak EM signals due to the "pumping" aspect of multiphoton interaction. The nonlinear cells and cell parts act as pumped phase conjugate mirrors (PPCMs) when subjected to multiphoton interactions.

Worse, the *signal wave* inputs to the PPCMs are the normal weak EM signals of the body itself. Hence the resulting PCRs from the PPCMs are superposing phase conjugates of the body's normal signals. This results in (1) a "diffusive" effect in the body of the PPCM formations, and (2) formation of very weak "EM cancellation" signals throughout the body, specifically targeted to the body's own control signals, including those to and of the immature immune cells in the bone marrow. In the bone marrow, "*partial-cancellation jamming*" *(see figure 11)* occurs in the normal control and development of the immune system cells as they are created. Slowly errors and degradation damage accumulate with time, including over the years. This cumulative immune system damage combines with other damage effects due to pesticide residues, pollutants, etc. The combined degradation results in long-term cumulative damage to the immune system and its cells. Increasing errors in the immune system's functioning eventually result in appearance of immune system disorders and increasing vulnerability to

Table 4. Mechanism for the Priore Therapy

- Produced Specific SWZ-Structured Scalar Potential
  - -17 EM frequencies mixed in a rotating plasma
  - - Phase conjugates added by the plasma
  - - Formed vacuum engine with hyperspace pump waves
  - - Modulated onto a rippling magnetic field which carried it to every cell and all its parts
  - - Jyperspatial pumping of cells/parts as PPCM's
- PPCM's created amplified anti-engines for disease there
- Anti-engine reversed cells/parts back to normal state
  - - Cells return to control by cellular control system
  - - Restored cellular control system to full functioning
- Scrubbed out the cumulated precancerous state
- Eliminated shadow disease state
- Restored the immune system to high functioning
- No excessive trauma to treated animal

In Part II of this wonderful article, by Mr. Bearden, a few of the topics you can look forward to are; The Gulf War Syndrome, How to Make a Gravitational Wave & Curve Spacetime, Potentials & Gravity and How Priore Made Vacuum Engines.

---

[56] *The Russians refer to the hidden EM wave structure of the scalar potential – i.e., to the SWZ structuring and vacuum engine templates – as the information content of the field. Western scientists assume this phrase refers to ordinary spectral analysis and communications, ignoring those statements that the normal EM theory does not apply. Also, Devyatkov et al seem in no great hurry to express their true meaning more clearly. See N.D. Devyatkov (Ed.), Applications of Low-Intensity Millimeter-Wave Radiation in Biology and Medicine, IRE Akad. Nauk. SSR, Moscow, 1985. [in Russian]. See also N.D. Devyatkov, Yu. V. Gulyaev, et al, [Organizing Committee Chairmen], Digest of Papers - International Symposium on Millimeter Waves of Non-thermal Intensity in Medicine, co-sponsored by Research and Development Association "ISTOK" and Research Institute of U.S.S.R. Ministry of Electronic Industry ("ORION"), Moscow, Oct. 3-6, 1991. Collection of 300 papers. [In Russian].*

[57] *However, some leading Western scientists – such as Wheeler, Feynman, and Jaynes – strongly advocate replacing the present erroneous concept of the EM force field existing in spacetime with the notion that what exists there instead is an information storage device containing a summary of what we need to predict the behavior of a charge if there should be one at the point. E.g., see J.A. Wheeler and R.P. Feynman, "Classical electrodynamics in terms of direct interparticle action," Reviews of Modern Physics, Vol. 21, 1949, p. 425-433; E.T. Jaynes, "Probability in quantum theory," in Complexity, Entropy, and the Physics of Information, Ed. W.H. Zurek, Addison-Wesley, Redwood City, CA, 1990, p. 33-55.*

VACUUM ENGINES AND PRIORE'S METHODOLOGY: THE TRUE SCIENCE OF ENERGY-MEDICINE

Part II of II

© Copyright 1995 by T. E. Bearden



Fig. 12. Single versus multiphoton penetration effects. Phase conjugation effects become of significance, generating PCR signals which couple to and backtrack the cells' and tissues' own signals, thus penetrating throughout the body with weak partial cancellation jamming.

THE GULF WAR SYNDROME

For very dense EM smog environments such as in the recent Gulf War, both the anomalous EM diffusion effect and the partial cancellation jamming effect on humans are dramatically accelerated. Cellular and immune system damage that would require decades of exposure at very low EM smog levels will cumulate in only a few months. In turn, this accelerated malfunctioning of the cellular control system and the immune system enhances the effects of other biological suppressants already present in the body or encountered during the dense signal environment exposure period. These augmented suppressants include the degradation due to the individual's prior lifetime EM smog exposure, attack by unfamiliar disease organisms endemic to the areas, exposure to oil fire smokes and pollutants, exposure to increased UV from solar radiation, and exposure to chemical agents and possibly surreptitious biological warfare agents.[58]

Further, in the haste to protect the troops from possible chemical and biological attack, all soldiers were administered a nerve agent called pyridostigmine bromide; in addition, approximately 150,000 were inoculated with anthrax vaccine, and 8,000 also received experimental botulism toxin shots.[59] Normally for medically-administered agents, the relatively minor suppression effects on the immune systems and body are followed by quick recovery, due to a properly functioning immune system and cellular control system. However, all three of these Gulf War preventive medical treatments do create "small cases of sickness" in the normal body.[60] In other words, a low level of the disease strain *is created* in the patient. Further, even after the apparent "initial recovery," there will now be a much longer dormant "apparently healthy" period during which the *vacuum engine templates for the disease remain, until they have finally decayed away.* In a sustained dense signal environment, this "decay away" period may be dramatically extended or never occur; in fact, the disease may progress from the vacuum-engine state to the low level physical state, then into a fully developed syndrome.

So we introduce the concept of the *relative level of a disease.* First, the disease and/or its vacuum engine templates are in the body. A low level or absence of disease, as we normally think of it, is with respect to the high disease level – the full-up, developed state of the disease. A disease level is "low" because of the ability of the immune system to fight it, overcome it, and reduce it to a "pre-disease" state; and the ability of the cellular control system to eventually rid itself of the disease vacuum engine templates, retaining only antibodies against its re-invasion. When the disease is not physically present according to conventional medical standards, but nonetheless the vacuum templates are present and not yet cleared out, we shall refer to that state as the shadow state of the disease. The cellular control system largely combats this state.[61]

---

[58] *Both Senator Riegle's and Senator Rockefeller's May 1994 hearings concluded that all 695,000 troops who served in the Gulf War were also exposed to chemical and biological toxins.*

[59] *Stephen Salgaller, "U.S. Role in Gulf War Illness." Letters,* ***Science News,*** *146(7), Aug. 13, 1994, p. 99.*

[60] *Note that at least one of these three treatments was still quite experimental. Consequently there exists less confidence in stating that its normal side effects are minimal and tolerable.*

[61] *Apparently by being able to phase conjugate with weak amplification, so that it forms anti-engines that usually are stronger than the disease's vacuum engines, gradually reversing the shadow state to normal.*

If the immune system and cellular control system are impaired, a shadow state of the disease can gradually progress to a "low level" of disease, then to a higher level, and become serious or even life threatening. This is true when conventionally the disease is physically absent but its shadow state is still present and cannot be disposed of by the cellular control system, as clearly shown by Kaznacheyev's experiments.[62,63]

We point out, but do not pursue, that the cellular control system also deals with the shadow states of diseases. In the normal state of "free from disease," the cellular control system successfully and continually deals with incident diseases, overcoming them at the shadow state level. Its process for continual disposal of the shadow state residues is hypothesized to be a version of slightly amplified phase conjugation of the vacuum engine's shadow state level.

In the model we are advancing, the disease entry and development occur by successively (1) creating its shadow state and successfully maintaining it in spite of the cellular control system's phase conjugation efforts, (2) breaching the threshold of physical changes, so that at least physical indicators of the struggle by the now-involved immune system appear, (3) progressing until conventional medicine recognizes "low level disease or infection," (4) increasing until conventionally-recognized "developed disease or infection," (5) increasing until the disease is serious and even life-threatening, and (6) increasing until the patient can no longer sustain life and dies. *We note that the best preventative medicine would and should be practiced at the shadow infection level.* The Priore therapeutical approach is capable of doing that.[64]

In the "normal" – if such an adjective can be used! – sustained "weak EM smog" exposure, the shadow state may last for several years or even several decades, prior to sufficiently accumulated degradation of the cellular control system and the immune system to allow the physical emergence of the disease. For much denser EM smog, such as existed in the Gulf War, the shadow incubation process is highly shortened, as is the time to progress from one stage to another higher stage of the disease or disorder condition.

In other words, in a dense but weak EM smog environment, the recovery from "minor diseases" actually administered as part of the initial vaccination and preventive medicine will be substantially altered because of the accelerated damage to the immune system and cellular control system. The control/immune degradation may be fast enough that the disease starts increasing from the shadow state toward higher levels, instead of being reduced and eliminated by the control/immune systems.[65,66]

Consequently, the Gulf War participants were thrust into a unique new situation: The second (shadow state) phase of decay of the "minor diseases" created in the bodies receiving the three preventive medications was interfered with by the EM fog. Because of individual variation in past cumulative damage experience, the individual control/immune systems varied from soldier to soldier. The smog environment varied in density and intensity from place to place, and from time to time. Hence the degree of interference varied from soldier to soldier because of (1) variation of past control/immune degradation, (2) variation of the EM smog exposure, and (3) variation of exposure to other suppressants. A bell-shaped distribution curve of the extent of the *net interference to net control/immune functionality*[67] would result, when the soldiers are taken as a group. That is, some of the participants just had a somewhat longer 2nd phase recovery period; some an extended 2nd phase recovery period; some a sustained, gradual rise in the 2nd phase, toward physical disease but not yet developing the Gulf War Syndrome. Some had a sustained, quicker rise toward actual physical disease instead of a decay, and have had sufficient time to develop the physical disease.

When the additional individual expo-

---

[62] *Kaznacheyev, several references, ibid. That is, suppose we have the shadow disease possess only a strength such that the normal cellular control system and immune system could overcome it. If the cellular control system is weakened, the disease progresses across the physical barrier. If the immune system is still strong, it can handle the encroaching disease, but will give physical indicators of its struggle (increased white corpuscles, etc.) If the immune system is also degraded, the disease will progress to low level physical disease, higher level, etc. On the other hand, if the cellular control system is normal but the shadow state of the disease is amplified, the phase conjugation defenses of the cellular control system will be breached and the disease will impel itself into low-level disease, then high level, and then kill the cells, in spite of a normal immune system combatting the breach of the cellular control system. This latter is what Kaznacheyev's experiments showed. It is also what the decades of Soviet weak microwave radiation of the U. S. Embassy in Moscow showed.*

[63] *The discerning reader will note that we are presenting the gist of a new theory of cellular disease.*

[64] *We also point out the electromagnetic biological warfare capability in this area, long since developed by the Russians and under total control of the KGB. The U.S. Embassy radiation, including the health changes and the death of three U.S. Ambassadors, was just to stimulate the U.S. intelligence and scientific communities at the highest levels. By the U.S. electromagnetic response at the Embassy itself, the Soviets could then know for certain whether or not the U.S. was aware of this EM biowar capability, and whether or not it had secretly developed defenses. Our actions assured them we had no such capabilities and no defenses – and were totally unaware of the true nature of the Embassy radiation.*

[65] *Note that the multiplicity of the assault on the control/immune systems augments the resistance and recovery difficulty. E.g., each B-cell lymphocyte can attack only a single antigen – alien property of the surface of an invader. There are about one billion B-cells in the human body, which between them are specific for about a million antigens. As can be seen, the immune system is continually having to develop B-cells with new specificities due to the continual meeting of new strains of antigens. Cumulated damage to this system affects both the body's resistance to diseases it has already acquired specific B-cells for, and its resistance to new strains for which it must make B-cells for new antigens. There is a sort of threshold, at any given time, beyond which the B-cell responses cannot keep pace, and start being overwhelmed. There is also an error tolerance level; when the errors due to deterioration surpass this level. the immune system will often begin attacking the body's own tissues in error. This results in disorders such as arthritis and cartilage and joint deterioration. With sufficient errors, previous immunity abilities also are degraded, so that more ordinary diseases become serious threats.*

[66] *The administering of three "lightly suppressive" treatments closely occurring with the soldier's entry into the Combat Zone thus posed a significantly greater problem than normal to his or her control/immune systems' operations, because the control/immune systems were suddenly degraded and hampered by the suppressive effects of the dense EM signals environment. In other words, the control/immune systems were moderately attacked by the three medical treatments (three enemy light cavalry divisions), and at the same time the entire control/immune system complex was subjected to substantial interference and suppression (the normal friendly) troop divisions were simultaneously placed under fierce and sustained attack throughout the zone. A general whose divisions are already committed in furious combat and under heavy bombardment, as are all his command posts and communications systems, has great difficulty freeing up, reconfiguring, and recommitting some of his committed troops to properly combat three other enemy forces that suddenly have appeared over the horizons from other directions!*

[67] *We may also define this as a disease progression ratio. This ratio should assume a distribution curve. For first-order simplicity, we are assuming a normal distribution.*

sures are factored in, there should have been essentially three broad groups: (1) relatively minor damage sustained, where any overt effects will only begin to appear many years hence if at all, (2) more damage sustained, where overt effects will begin to appear within the next few years, and (3) heavier damage sustained, where overt effects begin to appear either while still in the Gulf Region or within some months or so after returning.

Hence many of the Group 3 veterans of the Gulf war developed anomalous infections and immune system disorders shortly upon their return from such damage-accelerating exposure, resulting in the mysterious "Gulf War Syndrome." Conventional medical science will recognize – and has recognized – the overt phase 3 physical disease syndrome, but its cause and effective treatment remain and will remain medical mysteries. Conventional medical science will entirely fail to recognize Groups 1 and 2 cases, and will label them as due to aging, mental stress, or ordinary rise of diseases.

The syndrome has involved the "anomalous EM smog diffusion" process, as previously explained. It may – and in many cases it will – exhibit certain "signature" differences from normal diseases. The genetics of the victim are affected, and so are altered by induced transcription[68] to carry at least a portion of the "syndrome template." Semen, ova, saliva, and blood will particularly be so affected. A wife may complain that her husband's body fluids are now irritating to her skin, even producing "burning" sensations. Children conceived and born may be borne with the syndrome, or with one or more aspects of it.[69] The syndrome template can be transmitted by exchange of body fluids, so wives may also contract the syndrome and develop the disease from their husbands.[70]

CONVENTIONAL EM BIOEFFECTS KNOWLEDGE IS INSUFFICIENT

Present "EM bioeffects" scientific models contain absolutely no modeling of partially jamming the body's own special EM control system by turning its EM signals partially into G-signals, thereby partially nullifying them. It also contains no modeling of the anomalous EM diffusion process.[71] Thus the conventional medical approaches also do not contain any proper means of accounting the mechanisms for, and results of, long-term exposure to electronic smog and other combined agents and effects. Conventional scientists also have no knowledge of the major degradation mechanisms involved. The conventional medical models specifically are useless when confronted with something such as the Gulf War Syndrome or the decades of Russian microwave radiation of the U.S. Embassy personnel in Moscow. Capable scientists turn to their conventional models for answers, and the models fail them. Therefore present medical science is baffled when faced with such diseases and syndromes.[72] (*See figure 13 on next page*)

HOW TO MAKE A GRAVITATIONAL WAVE AND CURVE SPACETIME

We return now to the fundamentals of Type 2 engineering.

If one superposes an ordinary EM wave with its true phase conjugate replica wave, where the two waves are of equal strength, the *EM forcefield aspects* of the combined wavepair (standing wave) vanish, while the energy-density aspects remain. At every point the E-fields and the B-fields sum to vector zero *forcefield* resultants. The standing wave that results will not cause EM movement of charged particles.

However, the *energy densities* of the two locked (and now "hidden") EM waves remain and add. By standard GR, this "trapped EM density standing wave" must constitute a standing gravitational wave and a standing wave in the local curvature of spacetime!

It follows that, by assembling a harmonic set of such wavepairs, a la Stoney and Whittaker, one can form a region of spacetime such that the energy density is deterministically altered and controlled, and to engineering levels.

Engineering general relativity suddenly became a lot easier! Ironically, present physics only considers primarily the *very weak* ST curvature that can be obtained by the extremely weak gravitational "attraction of mass" G-force. For electrons, e.g., the G-force is only on the order of 10^{-42} times as strong as the electric force. Consequently orthodox GR simply "cannot pack enough trapped G-field energy into the local space" in the laboratory to get measurable effects. Only in the vicinity of a very large mass, such as the sun or a star or a black hole, does the weak G-force reach sufficient strength to yield directly observable, strong effects. Yet by using EM vacuum engines and the SWZ approach, one can obtain readily-measurable GR effects right on the laboratory bench.

The conventional medical models specifically are useless when confronted with something such as the Gulf War Syndrome or the decades of Russian microwave radiation of the U.S.

---

[68] Note that the transcription component may continue to develop in the same "post disease" manner as does the shadow disease of the overall Gulf War Syndrome. The returnee continues to experience EM smog and other control/immune suppressants, though at a lesser level than experienced in the Gulf War environment.

[69] Such aspects are highly controversial. A few affected families are reporting such symptoms and aspects, but officially "there is no evidence" for them. However, with the initial appearance of the syndrome, officially veterans who complained of this illness were briefed by these same medical "au thorities" that their physical symptoms were stress-related, and that the cause was all in their mind!

[70] In a fashion similar to Priore's animal experiments that demonstrated the transfer of curative templates by a single drop of blood. Kaznacheyev showed that disease templates could also be transferred.

[71] In fact, EM bioeffects research for decades has used, and continues to use, sheer energy deposition (scattering of EM energy by the tissues – heat by another name!) as a measure of the exposure level. They have not applied nonlinear phase conjugate self-targeting effects at all.


17.
DEVELOP NEW TYPES OF INSTRUMENTS
18.
CORRECT EM THEORY MODEL, INSTRUMENTATION AND RECORDING, AND IMCS
A
START
PRESENT INADEQUATE EM BIOEFFECTS MODEL
OVERALL STIMULUS/RESPONSE MODEL
2.
EXPERIMENT OR GROUP OF EXPERIMENTS
1.
EM STIMULUS/ RESPONSE MODEL
6.
EM THEORY TO BE APPLIED
8.
EM THEORY CORRECT
STOP
3.
INSTRUMENTATION AND RECORDING
4.
INTERPRETATIVE MODEL AND COMPARATIVE STANDARD (IMCS)
5.
INTERPRETED RESULTS
7.
ARE RESULTS CONSISTENT?
YES
NO
9.
EM THEORY INCORRECT
IMCS/EM ASSUMPTIONS:
1. PRESENT EM MODEL CORRECT AND COMPLETE
2. DOSAGE/RESPONSE SYNONYMOUS WITH STIMULUS/RESPONSE
10.
FIND ERRORS IN EM THEORY POSTULATES
16.
CORRECT/EXTEND EM AND SHOW UNIFIED FIELD AND MIND/VOLITION
14.
ADD WHITTAKER EM STRUCTURE OF POTENTIALS THEORY
13.
FORCEFIELDS NOT PRIMARY. POTENTIALS ARE, HAVE HIDDEN EM WAVE STRUCTURE.
11.
CHARGE DISCRETE, NOT QUANTIZED. VIRTUAL FLUX CAN BE STRUCTURED, FOR VACUUM ENGINES.
15.
ADD TO GENERAL RELATIVITY AND QUANTUM MECHANICS
12.
RETAIN ZERO VECTOR RESULTANT SUMMATIONS OF EM FORCE VECTOR COMPONENTS AS VACUUM ENGINES

Fig. 13. Necessary corrections for the present inadequate EM bioeffects model.

POTENTIALS AND GRAVITY

Obviously one can simply add harmonics of such EM "locked in" wavepairs, to produce a standing "constant value potential" pattern of a fixed *excess* energy density of vacuum or a fixed *decrease* in the energy density of vacuum. This harmonic series of bidirectional EM wave pairs – the *sum set* of wavepairs – is precisely what Stoney and Whittaker showed makes an ordinary EM scalar potential. In other words, they showed the actual energy-trapping mechanism, and dramatically altered the view of a scalar potential as being simply an "electrostatic" entity and a scalar field. Instead, it is a *hidden-variable energy flow process.*[73,74,75]

Its external "scalar field" aspect is just its "local energy density" aspect, not its fundamental nature.[76]

As is well-known in GR, all potentials are gravitational because they contain trapped energy. *Any* trapped energy is gravitational, a priori, according to GR. Ziolkowski independently rediscovered the SW decomposition in the 1980s and extended it to also add the product set. Since multiplication of waves is *modulation*, in my opinion Ziolkowski actually wrote the basis for hyperspatial (or subspatial, if one models physics in only 4-dimensions) communication at superluminal velocity, essentially instantaneously anywhere in the universe. (*See figure 14 on opposite page*)

"Paired assembly of an EM wave and its true PCR" was and is the way to turn EM energy directly into gravitational en-

---

[72] *Just as it is also essentially baffled by many conventional dread diseases such as cancer, leukemia, AIDS, arteriosclerosis, etc. – which indicates that the conventional "models" for those diseases are also seriously deficient.*

[73] *The present preoccupation of physicists with the scalar potential is simply to provide an algorithm for calculating the local energy density – in excess joules per collecting point-coulomb of charge – and erroneously call that the definition of the potential. The magnitude of the energy collection density of the potential at a point is not what the potential* is, *and such is not its definition. Defining how much water can be poured out of a standard bucket, when it is dipped into a flowing river and filled with water, does not define the river!*

[74] *From the particle view, the potential is an ordering in a virtual particle flux of the vacuum. From the wave view, the potential is comprised of an ordered, harmonic series of SWZ bidirectional EM waves, where each wave reaches to the ends of the universe before having a zero energy density. It follows that the energy in each hidden sine wave is infinite, just as it is for any overt theoretical EM sine wave. So any potential – even that of a flashlight battery – already involves an infinite amount of flowing hidden EM energy, being exchanged by the source and the entire universe, flowing in both directions along any radial from the source of the potential. The scalar potential is a flowing, continual exchange of energy between each and every point in the universe and the local source of the potential.*

[75] *Both the wave and particle forms of the potential exist simultaneously. The particle nature exists in Minkowski 4-space. The "hidden SWZ waves" exist in a hyper-4-space whose time dimension is the same as that of Minkowski 4-space. The scalar EM potential actually exists as a 7-dimensional entity. The internal hidden EM flow is not confined to the speed of light in space, because it does not flow "through" 3-space; instead, it flows "around" it.*

[76] *E.g., Whittaker, 1904, ibid. shows us that all of classical electromagnetics can be made by the interference of two scalar fields, which is just a special kind of hyperspatial multiwave interferometry.*

ergy.[77] This is the unification of EM and GR that eluded Einstein all the latter part of his life, and that has continued to elude scientists today. This is the way to "trap" EM energy locally, even though the EM wave energy is flowing at the speed of light or greater. This is the way to change EM energy into gravitational energy.[78] Further, it is engineerable and testable. Remember, physics requires that energy be conserved; however, it can certainly *change its form*. GR already says that it is the trapped energy that is gravitational, not mass per se, and regardless of what kind of energy is trapped. Ultimately Einstein's formula $E = mc^2$ is actually a statement of the trapped EM energy in a mass. However, heretofore no one had the slightest notion as to the actual trapping mechanism. The SWZ work actually shows the trapping mechanism itself and allows the engineering of *electrogravitation*.

How Did the Revolutionary Stoney/Whittaker Work Go Unnoticed?

Apparently, neither Stoney nor Whittaker realized that their work was pure electrogravitation. *When the referenced papers by Stoney and Whittaker were published, special relativity, general relativity, and quantum mechanics had not even been born yet!* Indeed, there still was not a wide adoption of Heaviside's vector interpretation of Maxwell's fading quaternion theory. Even classical EM was still in its infancy and just getting off to a good start.

In the 1980s Ziolkowski realized that the internal biwaves of a potential could be engineered, but remained primarily focused upon his important work with electromagnetic missiles and focus waves (slugs of EM energy which stay together as they travel, and do not spread out.) Ziolkowski is one of the pioneers in that field.

How Priore Made Vacuum Engines

This "vacuum engine methodology" was and is what Priore's intuition led him to! For the electromagnetic treatment of laboratory animals, his EM therapy device first inputted some 17 or so frequencies into a rotating plasma.[79,80] We know today that such plasmas *phase conjugate* the wave inputs, but that was not known when Priore first did it.


PHOTON
WAVE DIRECTION
PRIMARY ELEMENT OF A VACUUM ENGINE (OF A GRAVITON LATTICE STRUCTURE)
SPIN = 2
ANTIWAVE DIRECTION
ANTIPHOTON

Fig. 14. A graviton is a coupled photon/antiphoton pair. In the bidirectional wavepair of the SWZ internal structure of the scalar potential, photons in the wave continually couple and uncouple as the wave and antiwave pass through each other.

Obviously Priore himself did not understand the actual mechanism, but his brilliant intuition led him to discover how to do it! For many years no one knew how aspirin worked, yet that did not prevent it from being used widely and effectively.

In other words, Priore used the plasma to *unwittingly* add PCRs to each of his waves and form 17 magic SWZ "wavepairs." The entire SWZ wavepair assembly thus made an *artificial potential*, having a "vacuum engine" pumping substructure of hidden bidirectional EM waves. Adjustment of selected frequencies away from their harmonic positions adds multiplications and beat frequency modulations, creating *specific* templates and *specific* vacuum engines. These SWZ waves are hyperspatial; hence they are in the domain of the deep mind's cellular control system. When an abnormal body cell is pumped by these hyperspatial waves, the cell's own hyperspatial vacuum-engine "signal input complex" triggers a specific dedifferentiation anti-engine for that specific abnormal state. By Wheeler's principle, if spacetime curvature is *present in* the material cell, its energy and template are *applied to* the cell and act upon it. With vigorous pumping, the anti-engine is also *amplified* and so the cellular response is more rapid. In other words, the amplified anti-engine fairly quickly overpowers the disease engine and reverses the abnormal cell and all its contents back to their previous *normal* states. (*See figure 15 on the following page*)

Priore's new signal complex came out of the plasma mixing (phase conjugating) tube with SWZ structures of wavepairs, where each pair was composed of two bidirectional (opposing) EM waves. Priore then modulated this output upon a very strong, rippling magnetic field as a carrier, and radiated the body of the patient with that resultant field and its transported hyperspatial SWZ anti-engine components.

Nuclear magnetic resonance guarantees that such a magnetic field with all its modulations will be delivered entirely through the body, penetrating the flesh and bones and even the atomic nuclei themselves. It will certainly penetrate the bone marrow where all the blood cells (which includes most of the immune system's cells) are born! It will penetrate everywhere else also. So all the cells of the immune system will be exposed to the AC magnetic carrier and its impressed hyperspatial biwaves and their modulations.

The body's cells and cell-parts are highly nonlinear, and so they are also *demodulators*. They strip off the SWZ modulations. This puts the amplified vacuum anti-engines directly into and onto the cells, including all the cells of the immune system, and including each and every part of each cell. Small wonder then that the Priore methodology could restore suppressed immune systems! Time-reversing the damaged immune cells and their damaged internal components back to a previous healthy state was one magnificent result. The radiation also delivers the modulations directly into the master potential (the body's quantum potential) that contains its mind, its long-term memories, and its master control system for all cells. Thus not only are the diseased cells and the immune cells affected, but also the *master cellular control system* for all body cells is directly affected.[81]

---

[77] *I have previously pointed out that, in a coupled wave/antiwave pair, the photons in the wave and the antiphotons in the superposed phase conjugate replicate wave also pair into photon/antiphoton pairs, which have spin-2 helicity and hence are gravitons. This follows merely from a strong application of the distortion correction theorem. However, it is the fundamental union of EM and G into a single engineerable theory. See Bearden,* ***Gravitobiology,*** *1991, p. 1-9.*

[78] *By Whittaker 1904, we can always interfere two such potential fields and obtain an EM field, even at a distance. Thus we can also readily turn the gravitational (trapped EM) energy back to EM field (untrapped EM) energy.*

[79] *David M. Rorvik, "Do the French Have a Cure for Cancer?"* ***Esquire,*** *July 1975, p. 110-11, 142-149 gives an overview of the Priore Affair and some details of the electromagnetics of the machine.*

[80] *Note the immediate connection to the Russian energetics model, which is directly fashioned after the nature and nonlinear EM functioning of plasmas. Priore was directly applying Soviet energetics, although neither he nor any other Western scientist could have known that.*

In a related work, Becker (*See figure 16 on the following page*) and his colleagues stimulated bone healing in difficult fractures by use of tiny DC currents. They have shown that picoamperes of steady DC current trickled across the fracture site induces bone healing. Becker showed that, surprisingly, red blood cells are dedifferentiated – shucking their hemoglobin and growing a nucleus in the process. These cells redifferentiate into the kind of cells that make cartilage. Then *those* cells redifferentiate anew, into the kind of cells that make bone, and heal the fracture with new bone deposit. Becker also proposed a complete, operational DC control system, staying within the limitations of conventional EM theory.[82,83,84]



15-A. Priore demonstrates a point to Mr. Chaban-Delmas, Mayor of Bordeaux and a friend and mentor.

15-B. Dr. Raymond Pautrizel, noted immunologist, worked directly with Priore. Dr. Pautrizel is Professor Emeritus, University of Bordeaux, and holder of the first chair in immunology in France.

Dr. Robert Courrier (not shown), head of the Biology Section of the French Academy of Science as well as its Secretaire Perpetuel at the time, was also a noted colleague. He personally presented the astounding results of the Priore Team's experiments to the Academy.

Fig. 15. Priore was supported by notable French political leaders and eminent French scientists were his close scientific colleagues.

A proposed explanation of the fundamental vacuum-engine mechanism for the Priore and Becker effects has previously been given in some detail by Bearden.[85] (*See figure 17 on next page*)

---

[81] *We refer to an expanded version of Popp's cellular control system. E.g., see Fritz Albert Popp, "Photon Storage in Biological Systems," in Fritz Albert Popp et al, eds.,* ***Electromagnetic Bio-Information: Proceedings of the Symposium, Marburg, Federal Republic of Germany, Sep. 5, 1977;*** *Urban & Schwarzenberg, Baltimore, 1979, p. 123-149. Popp reports the theoretical and experimental discovery that mitogenetic radiation from cells can be seen as a sort of "waste" from a virtual electromagnetic field with a high coherence. This field has a tendency to become stationary over the whole organism. In addition, it includes the storage of "virtual" coherent photons.* ***Comment:*** *Our substitution of the SWZ hidden wave approach to replace Popp's QM particle approach greatly facilitates understanding and specifying the control system, and materially eases direct engineering of it.*

[82] *E.g., see R.O. Becker, "The direct current field: A primitive control and communication system related to growth processes."* ***Proceedings of the. XVI International. Congress of Zoology,*** *Washington, D.C., Vol. 3, 1963, p. 179; "The control system governing bone growth in response to mechanical stress."* ***J. Ark. Med. Soc.,*** *Vol. 62, 1966, p. 404; R.O. Becker and D.G. Murray, "A method for producing cellular dedifferentiation by means of very small electrical currents."* ***Trans. N.Y. Acad. Sci.,*** *Vol. 29, 1967, p. 606. See particularly Robert O. Becker, "The significance of bioelectric potentials."* ***Bioelectrochemistry and Bioenergetics,*** *Vol. 1, 1974, p. 187-199. Becker proposes that a complete, operational system exists in living organisms, and controls such basic functions as growth, healing, and biological cycles. The system is described in anatomical detail. It functions as a data transmission system in an analog fashion using varying levels of direct current as its signal. The system interlocks physically with the nervous system and is postulated to be its precursor. There are two electrochemical limbs of great significance in the operation of the system. One is between the DC system and the nervous system; the other is between the DC system and all body cells. The concept explains all of the diverse effects reported for the biological effects of applied electrical currents including: electrical anesthesia, electrical growth control, and electroacupuncture. It also furnishes a testable hypothesis for predicting other effects of clinical significance.*

[83] *We comment that the SWZ approach allows control and conditioning – both externally and internally – of both limbs of Becker's proposed DC control system.*

[84] *See also C.W. Hsue, "A DC Voltage is Equivalent to Two Traveling Waves on a Lossless, Nonuniform Transmission Line,"* ***IEEE Microwave and Guided_Wave Letters,*** *Vol. 3, 1993, p. 82-84. Hsue shows that the steady DC voltage on a transmission line powering a resistive load, mathematically decomposes into bidirectional EM traveling waves. The bone-healing setup used by Becker et al is precisely of this configuration. The fracture corresponds to the resistive load and the two electrodes on each side correspond to the transmission lines. Hence Becker's team actually employed a form of the Stoney/Whittaker/Ziolkowski harmonic biwave decomposition of the scalar potential, to accomplish hyperspatial pumping and formation of anti-engines of vacuum energy. So this is another application of the same basic "cell-reversing" methodology, as also utilized more extensively by Priore. Becker's brilliant work of course was and is independent and unique, and he was nominated for a Nobel Prize because of his absolutely fundamental work in showing electromagnetic differentiation and dedifferentiation of cells. That he has not been awarded the prize is regrettable and, in my opinion, an injustice.*

[85] *T.E. Bearden, "Mechanism for Long-Term Cumulative Biological Effects of EM Radiation," presented to the 70th Annual Meeting of the Alabama Academy of Science, University of Alabama at Huntsville, March 25, 1993. A digest of this presentation is published by the Tesla Book Company, P.O. Box 121873, Chula Vista, CA 91912 as T.E. Bearden,* ***Cancer and the Unresolved Health Issues in the Biological Effects of EM Fields and Radiation,*** *1993 and includes both text and hard copies of viewgraphs.*

HOW THE PRIORE VACUUM ENGINE REVERSED CELLS TO A PREVIOUS STATE

Taking a GR view, any mass already has its own vacuum engine for its exact form and internal structure and dynamics, in the finest detail. That particularly follows Wheeler's principle; if the mass is there, the appropriate spacetime curvature and dynamic energy structuring is there. If the mass has internal structuring, so does the spacetime curvature: it becomes *nested* curvatures with a precisely correlated template. In short, any mass – living or not – is imbedded in a precise vacuum engine. Any and every change adds a specific delta to this vacuum engine component. Just as a tree has rings for its past years and an onion has layers, the vacuum engine of an object has an exact template for that object's entire past, *as do the mind and its components also.*[86]

So when a normal living cellular mass changes to a diseased state, *a priori* it has added an additional delta vacuum engine (representing the change that resulted in the disease) to its original vacuum engine (which represents the original healthy state of the cell). The cell and all its parts are highly nonlinear and act as phase conjugate mirrors, *including to the higher topology (hyperspatiality) of the vacuum engine. Any living system we isolate and study is at least 7-dimensional.*

Putting all this together, we now can understand the marvelous nature of what Priore did. By exposing the body, treated part, cells, and cell parts to Priore's modulated rippling magnetic field, the "hidden pump waves" carried by that magnetic field are applied to each and every cell and to all its parts, in the exposed area. *In the exposed area, each and every cell and its parts become powerfully pumped phase conjugate mirrors for its hyperspatial vacuum engine complex.*

Extending the language of nonlinear optics, the particular *net* vacuum engine of the diseased cell or part constitutes a "standing input" *hyperspatial signal wave complex*, already input to the hyperspatially pumped phase conjugate mirror cell or cell part. When pumped by "hidden" pump waves, each and every one of those PC mirrors will now originate an *amplified phase conjugate replica of the signal wave complex. Each one will produce a highly amplified, time reversed replica of its specific standing vacuum engine. This includes amplified time reversed replicas of both the "healthy" component of each standing vacuum engine and the "disease delta" component. (See figures 18 above and 19 on following page)*


(+)
ELECTRODE
(-)
DC
POWER
SOURCE
ELECTRODE
BONE
BONE
BECKER'S
BONE FRACTURE SETUP
(DIAGRAMMATIC)
FRACTURE
SITE

Fig. 16. Becker's application of tiny DC currents to heal difficult bone fractures.


EQUIVALENT
STEADY-STATE CIRCUIT
ϕ_1
ϕ_1
i
RESISTANCE
ϕ_0
ϕ_0
THE DC VOLTAGE CAN BE TREATED AS TWO
TRAVELING WAVES PROPAGATING IN
OPPOSITE DIRECTIONS (HSUE, 1993)

Fig. 17. Hsue's biwave decomposition of DC voltage (as in Becker's application of tiny DC currents to heal difficult bone fractures).


PHYSICAL
CELL
(DISEASED)
+
PHYSICAL
CELL
(NORMAL)
EXTENDED
TIME
DELAY FOR
RENORMALIZATION
VACUUM
ENGINE
FOR DISEASED
CELL
VACUUM
ANTI-ENGINE
FOR CELL'S
DISEASE DELTA

Fig. 18. Applying an anti-engine for the "deviation" of the diseased cell reverses the cell to normal after a time delay.

In other words, every pumped diseased cell and cell part – including the genes and chromosomes – will produce a very powerful, highly amplified, "reverse vacuum engine" (an *anti-engine*) which is fantastically specific and precisely time-reverses the cell and its parts, including the genes and chromosomes as well, back to their *previous normal states.*

---

[86] *If one alters the internal structure (rings) of a tree, one changes the tree. If one alters the internal structures and dynamic functioning of matter, one changes the matter accordingly. If one alters the internal structures and dynamics of the mind, one changes the mind, its contents, and its functioning accordingly, as well as the subsequent behavior exhibited by the altered individual.*


PHYSICAL CELL (DISEASED)
+
AMPLIFIED VACUUM ANTI-ENGINE FOR CELL'S DISEASE DELTA
PHYSICAL CELL (NORMAL)
VACUUM ENGINE FOR DISEASED CELL

Fig. 19. Applying an amplified anti-engine for the "deviation" of the diseased cell reduces the time delay required to reverse it back to normal.

REJUVENATION

Any *normal* cell that is exposed to hyperspatial (Priore-type) pumping just reverts to a *slightly younger* normal state. Note that this allows *rejuvenation*.[87] Priore's earliest experiments that so riveted his attention and set him on the path of discovery, were in fact the abnormal prolongation of the life of fruits! For each class of disease, Priore just had to fiddle with the frequencies until he had the right set of pump waves for the specific "disease delta vacuum engine." This he did by trial and error. So when it is "Priore-pumped," a cancer cell reverses back to a normal cell, as does a precancerous cell as well.

The revolutionary Priore therapy is startling but simple. The diseased cell is analogous to an automobile that has been driven slowly off the road into the rough. Priore's methodology shifts the car into reverse gear, guns the engine, and quickly and precisely backs the car back onto the roadway. It is one of those profoundly beautiful embodiments analogous to Faraday's unipolar generator; it strikes directly to the heart of the fundamental principle. A cell develops damage and disease over a period of time. Simply time-reverse it quickly back to its original healthy state.

AIDS COULD BE QUICKLY CURED THE SAME WAY

Given Priore-pumping, an AIDS-infected cell would revert back to a normal cell, including all its genetics, and including for all of the hundreds of "strains" of AIDS that exist in an advanced AIDS patient. With this ap- proach one could completely reverse and eliminate AIDS whenever a positive reading occurs in the HIV virus test, and prior to the appearance of the actual physical sym- ptoms! If the person just has the antibodies and not the disease, the treatment will still do him absolutely no harm. (It will actually make his cells a "little bit younger and more vigorous," and help his immune system.) If he has both the AIDS antibodies and the infection as well, he will be completely cured and his immune system will be restored to complete vitality.

MOST DISEASES COULD BE CURED BY THE NEW THERAPEUTIC MODALITY

Any infectious disease known or unknown can be cured by the same means. The marvelous thing is that one need not know the specific technical pattern for the delta vacuum engine for a specific disease! One just has to *correctly adjust the hidden SWZ pumping frequencies.*

ARTERIOSCLEROSIS

In arteriosclerosis, it has been found that the greatest part of the damage is due to the presence of some rather ordinary viruses, and abnormal cell growth by the body's own cells as a result of triggering by previous viral infection. Cellular reversal (dedifferentiation) gets it all; the viruses and the abnormal cells. Everything reverts to normal, and the body's restored processes quickly "police up" the extra cell growth, using its natural control processes which are now restored to full functioning. *This is how the Priore team was able to so dramatically cure the "clogged arteries" of laboratory animals.*



Fig. 20. AIDS is continually changing since the HIV virus is a retrovirus and unstab.

The Priore approach (pumping of the

---

[87] *One should not be surprised that a time-reversal operation upon an entire body leads to reversal of physical aging in that body! But we point out that the time reversal we speak of is not at all the "time travel to the past" so beloved by generations of science fiction writers. For that, one would have to reverse each and every part of the universe simultaneously, except the observer, back to an exact former state, in perfect universal coordination. One would have to pump the entire universe, except for the observer! The observer would then remain as is with no change, while his entire world "went back in time" to a past state. The pumping of the universe would have to stop instantaneously (decay of the false vacuum?), and the universal anti-engine would have to stop operation and decay instantaneously (another big bang, perhaps?). We are not referring to anything such as that! We are referring to the reversal of a single little part of the universe, back to its previous state, which is practical and can be done. Universal time reversal – and hence time travel for the observer – is not practical, at least within our present knowledge and within the time reversal model we are applying. We should point out, however, that time reversal is a legitimate part of physics, and is not science fiction. E.g., for an overview, see Robert G. Sachs,* ***The Physics of Time Reversal,*** *University of Chicago Press, Chicago, Illinois, 1987.*

diseased cell's self-contained vacuum engine to create a very powerful vacuum anti-engine and reverse diseased cells back to normal) is the most powerful therapy for cellular disease ever conceived of. If the cells have ever been normal, they can be reverted to normal.[88] One can also probably regrow lost limbs, etc. but that takes too long to explain here! The methodology should also be able to completely reverse disorders such as Alzheimer's disease, and very probably muscular dystrophy as well. It should even be possible to reverse the physical effects of aging!

MUCH MORE THAN THIS INTRODUCTION HAS BEEN THEORIZED

This is the gist of the mechanism for the Priore therapy's startling success, although it has required some 10 years of very hard work to decipher the mechanics of the process. Along the way, I have also personally discovered and added a great deal more (for example, the quantum potential aspect of a living system and any enclave of living systems, the mechanism to generate a quantum potential, the precise mechanism for Sheldrake's morphogenetic field, the mechanism for directed evolution, the unusual electromagnetic nature of mind and thought, the mechanism for engineering mind and thought, engineering the entire species, and engineering the entire living biosphere), but this much should suffice for now for introductory purposes.

A technical book has been laboriously begun, and hopefully will be finished and published in about a year. Two 2-hour videos are also tentatively being planned. A four-hour technical briefing has already been prepared and presented.

REACTIONS TO THIS VACUUM ENGINE EXPLANATION

In response to numerous queries as to the reactions to this explanation of the Priore mechanism: Reactions tend to be rather good when (1) the technical person is open-minded, in other words, a friendly skeptic, (2) the technical person endures a grueling 2-hour or 4-hour detailed slide presentation I prepared, and (3) sufficient follow-up dialogue is accomplished to answer residual questions. Otherwise, the "mental jump" required of the participant is just too great.[89] Also, perhaps 60-70% of the conventional scientists are absolutely against anything that smacks of "revolutionary." From about half of this contingent the approach may generate disbelief and even overt emotional hostility, just as Priore himself and his associates encountered.[90]

However, some of the sharpest young graduate students readily make the transition, if they interact with me for a long enough period and enough times to understand the physics of the approach. *It did not take me 10 years to decipher an easy thing!* The causative mechanism for Priore's accomplishment is terribly involved and very, very deep. It is slightly beyond the present scientific vanguard, although the bits and pieces necessary to decipher the Priore mechanism are now in the literature. But putting them together has been a bone-crushing, terrible task. Priore was truly a century ahead of the science of his time!

Nonetheless, there is much hope, because the material is slowly taking root in a few sharp young graduate minds. For example, one of the major Eastern Universities would be astonished to know that their sharpest, brightest young PhD candidate – one they already assume will win a Nobel Prize in the future – is a full convert, and thoroughly understands cellular reversal by hidden-variable SWZ pumping, a la Priore. But at my strong urging, he is keeping it a secret until he graduates, and then he will *gradually* begin to filter in some of these ideas. That way he does not initiate his destruction by his peers because of too much energetic advocacy too quickly.

THE PRIORE APPROACH IS URGENTLY NEEDED

We simply must get this Priore therapeutic approach developed, for it is extremely important to all humanity. Our very survival may depend upon it.

Presently all our antibiotics are beginning to fail; the disease organisms are becoming quite resistant. Already our hospitals have strains of diseases that few if any antibiotics will touch. Hundreds of thousands of hospital patients each year are already experiencing complications due to contracting an antibiotic-resistant infection. Probably about 20,000 a year are dying as a result, and the death rate is increasing. In the future, one will have to seriously weigh whether it is better for one's chance of survival to enter the hospital and be treated, or to take one's chances with the disease and not enter the hospital.

With the rising failure of the antibiotics, (*See figure 21 on page 60*) and the rising possession of tailored biological weapons by hostile nations and international terrorists,[91] (*See figure 22 on page 60*) we shall shortly have no defense against an onslaught of pandemics unheard of since the Black Death swept medieval Europe of one third the population. Literally the age of pestilence and dread diseases of Revelations is upon us.[92]

---

[88] *They can also be "reversed to normal" even if they have never before been normal. The master cellular control system contains a master blueprint for the normal cell and can make an appropriate template for the specific disease delta vacuum engine, or one can be introduced (e.g., by injection of a drop of blood from a person previously cured of that specific disease; this was in fact demonstrated by the Priore group.). Pumping will then reverse the patient back to normal, as was actually shown by the Priore group. Indeed, the body's own system may be able to use the correct anti-engine template from the drop of blood and cure itself without pumping, as was also shown by the Priore group, if the body itself is reasonably healthy.*

[89] *Simply "dropping it on someone" by mail, for example – as I did to Elizabeth Taylor's foundation and Ross Perot's office – is just too much for a casual reading to grasp. A polite acknowledgment was received from the Taylor foundation, and no acknowledgment at all was received from the Perot camp.*

[90] *As an example, Priore completed the course work for his PhD and submitted his thesis, documenting his formidable and revolutionary work. Because of the ferocity of the oncology establishment toward the Priore team and its accomplishments, the university rejected his thesis. During the two decades or so since then, untold millions have died worldwide from diseases the team cured. These deaths could have been prevented had the Priore work been vigorously pursued and developed by the scientific community.*

[91] *It is not a question of if the international terrorists will use biological weapons against the U.S. civilian populace, but only of when. Astoundingly, often it may even be possible for the terrorists to simply buy their biological warfare agents from us! In a lawsuit by Desert Storm Syndrome victims against certain U.S. companies, one of the companies is alleged to have sold germs – such as anthrax, tularemia, and botulism – to Iraq by mail. These are highly effective biological warfare agents. E.g., a few spray tanks spraying such agents over a large U.S. city complex at night, using an easily obtained light plane to get in a few hours "flying practice," would result in tens or even hundreds of thousands of deaths within days. According to U.S. government-released data, inhaling a few anthrax spores into the lungs has a very high probability of killing the inhaler, unless treatment is started immediately. Even with immediate treatment, many deaths will still occur. A substantial number of nations are now obtaining and producing lethal biological warfare agents – which have been called the "poor man's atomic bomb." Some of the international terrorist groups are also acquiring the biological warfare agents.*

[92] *A good exposition of the rapidly increasing resistant-disease problem is given by Garrett, Laurie,* ***The Coming Plague: Newly Emerging Diseases in World out of Balance,*** *Farrar, Straus and Giroux, New York, 1994.*

In addition, the costs of the present allopathic medicine are rising rapidly and threatening to either bankrupt the nation, or become so expensive that only the wealthy can afford adequate medical care. Even the wealthy could be trapped in the future and denied adequate medical treatment. The Clinton Medicare bill, if approved, would make it a felony to pay a doctor out of one's own pocket, after denial of such treatment by the administrative bureaucracy. It also makes it a felony for the doctor to give the treatment to the disapproved paying person. Thus both the patient and the doctor could be sent to prison, wealthy or not.[93]

CELL CONJUGATION BY VACUUM ANTI-ENGINES IS THE ONLY HOPE

Priore's approach offers an answer to both the age of pestilence and the impending biological warfare strikes against our armed forces and our civilian population.[94,95] By prompt cellular reversal, infection even by totally unknown and modified agents can be quickly voided. Infection by newly adapted, resistant strains of presently known diseases can be quickly conjugated. So the problem of the failing vaccines and antibiotics can be solved quickly, simply, and cheaply. However, the cell-reversing treatment devices and trained, experienced medical staffs must be widely available!

Diseased cell conjugation by EM means is also the only therapy that can largely *eliminate* the debilitating diseases of humanity. Per Wheeler's principle, vacuum engines can mold the *physical matter* of the living body and conditions, operations, and content of the mind, memory, and personality. As the Priore therapy is developed and extended, it will become possible to correct bent spines, mental retardation, mental diseases, genetic defects, physical accidents and disabilities, birth defects, etc. It will be possible to regrow amputated limbs and restore deteriorated cartilage, organs, and joints. It should also be possible to directly remove deep psychiatric problems, heal chemical imbalances, and address and heal such presently difficult disorders as schizophrenia.

The development and application of Type 2 medical engineering can usher in the greatest, most beneficial revolution of all time. As just *one* example, eventually it will be possible to quickly educate students by simply loading the appropriate "software" into their minds and long term memory, in only a few weeks of "sessions." At that point there need no longer be, anywhere in the world, an educationally disadvantaged person.

It can also be used to usher in the most diabolical revolution of all time if we are not careful to (1) be informed of the Type 2 engineering area, including who is developing what, and for exactly what purposes, and (2) rigorously control the development and use of this technology as it progresses. Our legal, political, and scientific leaders – and we common citizens – will have to grapple with the ethics of what is done and to and for whom it is done. Just as one example, the same technology that will allow direct loading of the software in the long-term memory to achieve rapid education, will allow altering or changing any part of the long term memory, including the built-in emotional responses, etc. *Loading software is loading software*! *What is loaded depends only upon what is in the software.* In theory it is possible not only to alter the learned behavior, memories, emotions, and reactions, but also the genetically "born-in" behavior, emotions, and reactions. The potential for the Type 2 engineering to be used for enslaving and roboticizing humanity should be obvious.

Far more carefully than with any other technology in history, we must ensure that this new one is developed for good, not for evil. To quote an old adage, *the price of freedom is eternal vigilance.* Never before in all of history have those words been more true.

IN CONCLUSION

Pioneers such as Priore, Becker, Kaznacheyev, and Popp have shown us a

---

[93] *In fact, under present law all property, homes, bank accounts, and monies of both the patient and the doctor would simply be confiscated – without any legal charge, arrest, or trial – under an absolutely medieval reinterpretation of U.S. law that has again given police at all levels such sweeping and unconstitutional powers. The Clinton Health Care Plan, presently on hold but still alive and sure to be introduced again, is reported to include the establishment of an entire department solely devoted to confiscating assets from patients and doctors who commit such "crimes." Defendants victimized by the present confiscation reinterpretation of law have a slim chance of even forcing the issue into a court. Even if they succeed in getting into court for a hearing, win it and get full "exoneration," the authorities can still keep the property! In the most insane and unjust legal action in all of U.S. history, this law now charges the property itself with having committed the crime, not the erstwhile human defendant. By what means can the "property" defend itself? No one has an answer, for the property is not an individual and has no legal rights for jury protection under the law! U.S. lawyers and judges are actually insisting that this is rational and makes sense. They have already precisely redefined U.S. law into what is specifically required to institute a police state. The police forces who carry out this consfication are themselves awarded a percentage of the "haul." What does the citizen do when the police forces themselves become the robbers by administrative fiat, and there is no court redress possible? Ostensibly passed to counter organized crime and the drug cartel, this law has rapidly been applied directly to the citizenry, and its use is one of the fastest growing "new techniques" by the various levels of law enforcement. In this paper we have deliberately not dwelled upon the political aspect of the already-emerging police state in control of medical treatment. We simply summarize how the bureacratic medical establishment is likely to meet the challenges of the coming plagues and the associate astounding rise in medical costs. In fact the reader will almost certainly see the rise of an iron "state dictatorship" in medicine, as is already emerging in other legal areas.*

In this paper my primary purpose is technical, not political, so we defer detailing the more involved political aspects of the emerging police state (the New World Order – more aptly the New World Feudalism) to other more capable authors and sources. One central thought should remain firmly in mind All political systems and isms tend ultimately to feudalism, which is always the best system for the oligarchy or elite at the top who control and own everyhing. In any society, there is always an on-going struggle by a fraction of the most powerful to convert the society to special forms of feudalism.

[94] *Some biological agents are very lethal and the associated disease develops at a frightening pace. E.g., the strains of Staphylococcus bacteria that cause necrotizing fascitis and necrotizing myositis – two versions of the "flesh-destroying" disease – are noteworthy examples. Necrotizing is causing inflammation and/or death of tissue, fascitis refers to "sheet" or connective tissue, and myositis refers to muscle tissue. Recently the Quebec separatist leader Lucien Bouchard was suddenly felled by necrotizing myositis, lost a leg, and at this writing is stable and will recover. The disease is usually fatal in 80% of the cases. There is nothing diabolical in his contacting the disease; the bacteria are present from time to time and can enter the body through a nick or otherwise. The disease and the bacteria are known; however, in the past such cases have been relatively rare. The lethality of the disease is augmented by the rapidity of its development. Delayed recognition of the disease may place the patient already beyond the ability of conventional agents to arrest it in time to save him. With the modern hospital and population environment being highly favorable for the more rapid modification and adaptation of disease organisms, even previously rare diseases such as necrotizing fascitis/myositis are ticking time bombs waiting to become resistant to our antibiotics and explode in the dense urban populations.*

[95] *We refer to strikes using biological organisms. We have mentioned but deliberately not dwelled upon the use of electromagnetic induction of lethal cellular diseases at a distance. Such strategic capability to attack a nation and destroy its citizens and soldiers is presently on-line in Russia, under total control by the KGB, not by the conventional Russian military forces.*



Fig. 21. Present antibiotic therapy is failing as disease organisms adapt.



Fig. 22. Terrorists will eventually use biological warfare strikes. Biological warfare is an increasing threat to military forces and the civil populace.

great vision. Having seen it, when one looks at the incredible human suffering throughout the world, and then at the formidable problems of our Type 1 medical science that is struggling so mightily and losing the battle, one is reminded of a phrase by Dante:

"Heaven wheels above you

Displaying to you her eternal glories

And still your eyes are on the ground."

With every fiber of our being, we exhort the scientific community to lift its eyes from the ground, and develop and apply the Type 2 medical technology as rapidly as humanly possible, for human benefit. Else half of humanity will perish in the coming tide of pestilence. Even the conventional scientists agree that the pestilences are coming, and that conventional approaches are already losing the battle. Long ago Albert Einstein wrote these prophetic words:

"*It would of course be a great step forward if we succeeded in combining the gravitational field and the electromagnetic field into a single structure. Only so could the era in theoretical physics inaugurated by Faraday and Clerk Maxwell be brought to a satisfactory close.*"

Einstein's passionately-sought unification of EM and G has now been accomplished. It has magnificent medical science applications for the benefit of all humankind. Meanwhile, in the orthodox medical journals, the scientists themselves are recognizing the demise of antibiotics and the coming unstoppable plagues. The scientists are redoubling their efforts to apply the present inadequate models, and their efforts are admittedly failing. *If they keep to their present course, the war is already lost!*

In the name of all the bleeding, suffering, and dying peoples of the world, we must do better than that! We can do better than that, if we rapidly redevelop and apply the Priore approach.

We call fervently for a great new "War on Disease" that is empowered, funded, and staffed to perform the task. It can be done in perhaps three years, and perhaps for as little as $60-100 million if we streamline procedures, keep the bureaucracy off the team's necks, and give the team scientists the authority of a War Commander with a mission order to *get on with it.*

What happens next is up to the scientists, the politicians, and the concerned leaders of all the nations of the world. *They simply must not fail us.* They and their families are in the same frying pan as the rest of us. This is not the time for dogma, posturing, arrogance, protecting one's territory, yapping about who's going to control the presently inadequate medicine, yakking about pseudoscience, striving for personal position and power, bowing to the big drug companies and their vested interests, and playing the "Who's to be the big monkey?" game. *We need a new Manhattan Project. We need it now.*

Else we who have
sown the wind
will most certainly reap
the coming whirlwind.

ADDITIONAL REFERENCES

Priore, Antoine. (1963) "Procede et dispositif de production de rayonnements utilisables notamment pour le traitement de cellules vivantes." [Procedure and Assemblage for Production of Radiation Especially Service able for the Treatment of Living Cells.] Republique Francais: Brevet d'Invention P.V. No. 899.414, No. 1,342,772, Oct. 7, 1963.

Priore, A. (1966) "Method of producing radiations for penetrating living cells," U.S. Patent No. 3,280,816, Oct. 25, 1966.

Priore, A. (1968). "Apparatus for producing radiations penetrating living cells." U.S. Patent No. 3,368,155. Feb. 6, 1968.

Priore, A. French Patent No. 1,342,772. Letter, R. Pautrizel to his colleagues at the University of Bordeaux, Sept. 11, 1979. Letter, R. Pautrizel to his colleagues, Mar. 26, 1969.

*Graille, Jean-Michel, **Le Dossier Priore**, [Dos sier Priore: A New Pasteur Affair] De Noel, Paris, 1984 [in French]. Details the entire Priore affair.*

*Pautrizel, R., M.R. Riviere, A. Priore, and F. Berlureau. (1966) "Influence d'ondes electromagnetiques et de champs magnetiques associes sur l'immunie de la souris infestée par Trypanosoma equiperdum," [Influence of electromagnetic waves and associated magnetic fields on the immunity of the mouse infected with the Trypanosoma equiperdum] **Compt. Rend. Acad. Sci.** (Paris), 1966, Vol.60,p.2099-2102.[in French].*

*Pautrizel, R.; A. Priore, F. Berlureau, and A.N. Pautrizel, "Stimulation par des moyens physiques des defenses de la Souris et du Rat contre la trypanosomiase experimentale." [Stimulaton, by physical means, of defenses of the mouse and of the rat against the ex perimental Trypanosoma.] **Compt. Rend. Acad. Sci.** (Paris), Vol. 268, 1969, p. 1889-1892. [In French].*

Pautrizel, R., A. Priore, A.N. Pautrizel, and P. Chateau-Reynaud-Duprat.(1979) "Guersson de la trypanosomiase experimentale par l'association de champs magnetiques et d'ondes electromagnetiques: une stimulation des defenses de l'organisme." [Cure of experimental trypanosomias by associated magnetic fields and electromagnetic waves: a stimulation of the organism's defenses.].

Communication presented to the Journées **Nationales Microondes - Colloque Hertzienne et Dielectriques,** Lille 26-29 juin 1979, p. 31.

Pautrizel, R.; A. Priore, F. Berlureau, and A.N. Pautrizel, "Action de champs magnetiques combines a des ondes electromagnetiques sur la trypanosomiase experimentale du Lapin." [Action of magnetic waves combined with electromagnetic waves on the experimental trypanosoma of the rabbit.] **Compt. Rend. Acad. Sci.** (Paris), Vol. 271, 1970, p. 877-880.

Pautrizel, R.; A. Priore, M. Dallochio and R. Crockett, "Action d'ondes electromagnetiques et de champs magnetiques sur les modifications lipidiques chez le Lapin par l'administration d'un regime alimentaire hypercholestrole." [Action of electromagnetic waves and magnetic fields on provoked lipidic modifications in the rabbit by the administration of an alimentary hypercholesterol diet.] **Compt. Rend. Acad. Sci.** (Paris), Vol. 274, 1972, p. 488-491. [In French].

Pautrizel, R.; A. Priore, P. Mattern, and A.N. Pautrizel, "Stimulation des defenses de la souris trypanosomee par l'action d'un rayonnement associant de champ magnetique et ondes electromagnetiques." [Stimulation of the defenses of the trypanosomized mouse by the action of a ray associated with a magnetic field and electromagnetic waves." **Compt. Rend. Acad. Sci.** (Paris), Vol. 280, 1975, p. 1915-1918. [In French]

Pautrizel, R.; A. Priore, P. Mattern, A.N. Pautrizel, and A. Capbern, "Guerison de la trypanosomiase chronique du Lapin a Trypanosoma equiperdum par l'action combinee de champs magnetiques et d'ondes electromagnetiques modules." [Healing of chronic trypanosomia by trypanosoma equiperdum of the rabbit by the combined action of magnetic waves and modulated electromagnetic waves.] **J. Protozool.**, Vol. 22, No. 3, 1975, p. A 84.

Pautrizel, R. "La trypanosomiase experimentale: stimulation des defenses de L'organisme par des moyens physiques." [Experimental trypanosomiasis: stimulation of the organism's defenses by physical means.] **XVIIth Seminar on Trypanosomiasis Research,** Londres, 22-23 Sept. 1976.

Pautrizel, R.; P. Mattern, A.N. Pautrizel, and A. Priore, "Effets des champs magnetiques et des ondes electromagnetiques modules sur la trypanosomiase experimentale." [Effect of magnetic fields and modulated electro magnetic waves on experimental trypanosomiasis]. **Ann. Soc. Belge Med. trop.** [Annals of the Belgium Society of Tropical Medicine], Vol. 57, 1977, p. 501-523.

Pautrizel, P. Mattern, A. Priore, A.N. Pautrizel, A. Capbern, and T. Baltz, "Importance des mecanismes immunitaires dan la guerison de la trypanosomiase experimentale par stimulation physique." [Importance of immune mechanisms in the cure of the experimental trypanosomias by physical stimulation.] **Compt. Rend. Acad. Sci.** (Paris), Vol. 286, 1978, p. 1487-1492. [In French]

Pautrizel, R. and A. Priore, "Un aspect spectaculaire du bioelectro-magnetisme: permettre a l'organisme de se debarrasser d'un infection aigue ou chronique sans l'aide d'aucune substance medicamentese." [A spectactular aspect of bioelectromagnetism: Permitting the organism to rid itself of an old chronic infection without the aid of any medical substance.] **Communication presented to the 104eme Congres National des Societes Savantes,** Bordeaux, 17-21 Avril 1979 — section **Sciences,** p. 112.

Pautrizel, R. and A. Priore, "Guerison de la trypanosomiase experimentale par association de champs magnetiques et d'ondes electromagnetiques." [Cure of trypanosomiasis by associated magnetic fields and electromagnetic waves.] **Communication presented to the Symposium International des Therapeutiques Ondulatoires,** Versailles, 19-20 Mai 1979, p. 9.

Pautrizel, A. Priore, A.N. Pautrizel and P. Chateau-Reynaud-Duprat, "Guerison de la trypanosomiase experimentale par l'association de champs magnetiques et d'ondes electromagnetiques: une stimulation des defenses de l'organism." [Cure of trypanosomiasis by associated magnetic fields and electromagnetic waves: a stimulation of the organism's defenses.] Communication presented to the **Journees Nationales Microondes - Colloque Hertzienne et Dielectriques**, Lille 26-29 Juin 1979, p. 31.

Riviere, M.R., A. Priore, F. Berlureau, M. Fournier and M. Guerin, "Phenomenes de regression observes sur les greffes d'un lymphosarcome chez des souris exposées a des champs electromagnetiques." [Phenomena of regression observed on the graftings of a lymphosarcoma in mice exposed to electromagnetic fields]. **Compt. Rend. Acad. Sci.** (Paris), Vol. 260, 1965, p. 2099-2102 [in French]. This reports the curing of lymphosarcoma, which is a malignant lymphoma that tends to metastasize freely and spread throughout the body. It easily leads to the condition of lymphomatosis, which is the presence of multiple lymphhomas in the body, including wide distribution through the various organs, lymph tissue, and tissue resembling lymph tissue.

Riviere, M.R.; A. Priore, F. Berlureau, M. Fournier and M. Guerin, "Action de champs electromagnetiques sur les greffes de la tumeur T8 chez le Rat." [Action of the electromagnetic fields on the graftings of the T8 tumor on the rat." **Compt. Rend. Acad. Sci.** (Paris), Vol. 259, 1964, p. 4895-4897.

Riviere, M.R.; A. Priore, F. Berlureau, M. Fournier and M. Guerin, "Effets de champs electromagnetiques sur un lymphosarcome lymphoblastique transplantable du Rat." [Effects of electromagnetic fields on lymphoblastic lymphosarcoma transplantable from a rat.] **Compt. Rend. Acad. Sci.** (Paris), Vol. 260, 1965, p. 2099-2102.

COMMENT: Lymphosarcoma is a malignant lymphoma (malignant tumor of lymph or lymph-like tissue) that tends to metastasize freely and spread throughout the body. It easily leads to the condition of lymphomatosis, which is the presence of multiple lymphomas in the body, including wide distribution through the various organs, lymph tissue, and tissue resembling lymph tissue. A lymphoblast is a cell giving rise to lymphocytes, the colorless weakly motile cells produced in lymphoid tissue and include the cellular mediators of immunity, constituting some 20 to 30 percent of the leukocytes (white blood cells) of normal human blood. In effect the experimenters have healed a transplanted condition that represents a serious leukemia.

Riviere, M.R. and M. Guerin., "Nouvelles recherches effectuees chez des rats porteurs d'un lymphosarcome lymphoblastique soumis a l'action d'ondes electromagnetiques associees a des champs magnetiques." [New research on rats having lymphoblastic lymphosarcoma, submitted to the action of electromagnetic waves associated with magnetic fields.] **Compt. Rend. Acad. Sci.** (Paris), Vol. 262, 1966, p. 2669-2672.

COMMENT: Lymphosarcoma is a malignant lymphoma (malignant tumor of lymph or lymph-like tissue) that tends to metastasize freely and spread throughout the body. It easily leads to the condition of lymphomatosis, which is the presence of multiple lymphomas in the body, including wide distribution through the various organs, lymph tissue, and tissue resembling lymph tissue. A lymphoblast is a cell giving rise to lymphocytes, the colorless weakly motile cells produced in lymphoid tissue and include the cellular mediators of immunity, constituting some 20 to 30 percent of the leukocytes (white blood cells) of normal human blood. In effect the experimenters have healed a condition that represents a serious leukemia.

Delmon, G. and J. Biraben, "La croissance du carcinome de Guerin sour l'action de champs electromagnetiques." [The growth of carcinoma treated by the action of electromagnetic fields.] **Rev. Path. Comp.,** 3(2), 1966, p. 85-88.

Berteaud, A.J.; A.M. Bottreau, A. Priore, A.N. Pautrizel, F. Berlureau, and R. Pautrizel, "Essai de correlation entre et l'action d'une onde electromagnetique pulsee et modulee." [Trial of the correlation between the evolution of a disease by Trypanosoma equiperdum and the action of a pulsating and modulated electromagnetic wave.] **Compt. Rend. Acad. Sci**. (Paris), Vol. 272, 1971, p. 1003-1006. [In French].

Mayer, G.; A. Priore, G. Mayer and R. Pautrizel, "Action de champs magnetiques associes a des ondes electromagnetiques sur l'orchite trypanosomienne due lapin." [Action of magnetic fields associated with electromagnetic waves on the typanosomian orchitis of the rabbit.] **Compt. Rend. Acad. Sci.** (Paris), Vol. 274, 1972, p. 3011-3014. [In French]

COMMENT: Orchitis is inflammation of a testes. Trypanosomes are protozoan flagellates of genus trypanosoma which infect humans and animals and are responsible for various serious diseases such as Chaga's disease, dourine, nagana, sleeping sickness, and surra. Chaga's disease is marked by prolonged high fever, edema, and enlargement of the spleen,

liver, and lymph nodes. Dourine is a disease favoring horses and asses, marked by inflammation of the genitals, subcutaneous edematous plaques, low-grade fever, progressive paralysis, emaciation, and death. Nagana is a highly fatal disease in/of domestic animals in tropical Africa marked by fluctuating fever, inappetance, edematous swelling, and sluggishness, and is transmitted by the tsetse fly and possibly by other biting flies. Sleeping sickness is a serious disease that is prevalent in much of tropical Africa; it is marked by fever, protracted lethargy, tremors, and loss of weight, and is transmitted by tsetse flies. Surra is a severe Old World febrile and hemorrhagic disease of domestic animals and is transmitted by biting insects.

Courrier, R., "Expose par M. le Professeur R. Courrier, Secretaire Perpetuel de L'Academie des Sciences fait au cours d'une reunion a L'Institut sur les effets de la Machine de M.A. Priore le 26 Avril 1977." [Presentation by Professeur R. Courrier, Perpetual Secretary of the Academy of Sciences, made at the meeting of the Academy on the effects of the machine of M.A. Priore.] [In French] Courrier's presentation of the Priore machine and its positive cures of terminal cancers and leukemias in laboratory animals, under proper scientific protocols.

Ruth, Barnard. "Experimental investigations on ultraweak photon emission." **In Electromagnetic Bio-Information: Proceedings of the Symposium**, Marburg, Sept. 5, 1977. Proceedings edited by Fritz Albert Popp et al., Urban and Schwarzenberg, Munchen Wien, and Baltimore, 1979, p. 107-122.

Ryaby, J.T.; D.A. Grande, F.P. Magee, and A.M. Weinstein, "The effect of combined AC/DC magnetic fields on resting articular cartilage metabolism." Presented at the 1st World Congress for Electricity and magnetism in Biology and Medicine, Orlando, FL, June 14-19, 1992.

Vladimirov, Yu. A., "Ultraweak luminescence of subcellular structures," **Ultraweak Luminescence in biology, Proceedings of the Symposium,** Moscow, 1969 [In Russian].

Kaznacheyev, V.P., "Informational function of ultraweak flows of light in biological systems," in **Materials of Science Conference: Physical and Mathematical methods of Research in Biology and Medicine, Novosibirsk,** 1965, p. 38-41 [In Russian].

Kaznacheyev, V.P. et al, "Studies on the biological role of electromagnetic emission as a factor of adaptive behavior of cells under conditions of lattitude changes," **Abstracts of the Second All-Union Conference Devoted to different Geographical, Climatic and Labor Conditions,** Novosibirsk, 1977, p. 101-104 [In Russian].

Kaznacheyev, V.P. et al., "Conditions necessary for appearance of distant intercellular interactions after UV radiation," **Bulleten Experimentalnoy Biologii i. Meditsiny,** No. 5, 1979, p. 468-471.

Possony, Stefan T., "Psy-War: Soviet device experiment," **Defense and Foreign Affairs Daily,** 12(104), June 7, 1983, p. 1-2.

Kaznacheyev, V.P. and L.P. Mikhailova, "Ultraweak Radiations in Intercellular Interactions," Novosibirsk, 1981 [In Russian]. English translation: San Francisco, Washington Research Center, 1982.

Kaempffert, Waldemar, "'Dead' organisms revived," Science in the News: **Science Digest**, May 1950, p. 77-78.

"Rejuvenating Light," **Scientific American** May 1949.

Popp, Fritz Albert; Gunther Becker, Herbert L. Konig, and Walter Peschka, Eds., **Electromagnetic Bio-Information: Proceedings of the Symposium**, Marburg, Sept. 5, 1977, Urban & Schwarzenberg, Baltimore, 1979.

Lilienfeld, A.M. et al, **Foreign Service Health Status Study: Evaluation of Health Status of Foreign Service and Other Employees From Selected Eastern European Posts**, Department of Epidemiology, Of Hygiene, and Public Health; The Johns Hopkins University, Baltimore, Maryland, final Report, July 31,1978.

Mallaliew, Robert C., **A Model of the Microwave Intensity Distribution within the U.S. Embassy, Moscow 1966 to 1977,** Report FS-80-166, Applied Physics Laboratory, Johns Hopkins University, Aug. 1980.

Microwave Radiation at the U.S. Embassy in Moscow and Its Biological Implications: An Assessment, U.S. Department of Commerce Doc. No. NTIA-81-12, Mar. 1981.

Novak, Rachel. "Flesh-Eating Bacteria: Not New, But Still Worrisome." Research News, **Science**, 264(5166), June 17, 1994, p. 1665.

Olariu, S. and I. Iovitzu Popescu. "The Quantum Effects of Electromagnetic fluxes," **Reviews of Modern Physics**, 57(2), April 1985, p. 339-436.

Opall, Barbara. "U.S., Russia Hope to Safeguard Mind-Control Techniques." **Defense News**, Jan. 11-17, 1993, p. 4, 29.

Penrose, R. "The Nonlinear Graviton." **General Relativity and Gravitation**, 7(2), 1976, p. 171.

Perez, Jose and Carson Jeffries. "Effects of additive noise on a nonlinear oscillator exhibiting period doubling and chaotic behavior." **Physical Review B. Condensed Matter**. Series 3, 16(6), Sept. 15, 1982, p. 3460-3462.

Phipps, Thomas E. Jr. "Critique of accepted theories of special relativity and electromagnetism," **Scientific Ethics**, 1(2), Apr. 1985, p. 17-23.

Popp, Fritz-Albert and Ke-hsueh Li. "Hyperbolic Relaxation as a Sufficient Condition of a Fully Coherent Ergodic Field." **International Journal of Theoretical Physics**, 32(9), Sep. 1993, p. 1573-1582.

Reid, B.L. "Propagation of properties of chemical reactions over long distance in the atmosphere as seen by crystal growth pattern changes." **Australian Journal of Medical Laboratory Science**, Vol. 7, Feb. 1986, p. 30-35.

Rodemann,. H.P., H.P. Peterson, K. Wchwenke, and K. Hartmut von Wangenheim. Terminal differentiation of human fibroblasts is induced by radiation." **Scanning Microscopy**, 5(4), Dec. 1991, p. 1135-43.

Rodemann, H.P.; K. Bayreuther, and G. Pfleiderer. "The differentiation of normal and transforman fibroblasts in vitro is influenced by electromagnetic fields." **Experimental Cell Research,** Vol. 182, 1989, p. 610-621.

Santilli, Ruggero Maria. "Partons and gravitation: some puzzling questions." **Annals of Physics**, 83(1), Mar. 1974, p. 108-157. Proves that electric field and gravitation are not mutually exclusive. One is left with one of two assumptions: (1) the strong assumption, that both are identically the same thing, or (2) the weak assumption, that both are partially the same thing.

Saxl, Erwin J. and Mildred Allen. "1970 solar eclipse as 'seen' by a torsion pendulum." **Physical Review D. Particles and Fields,** 3(4), Feb.15, 1971, p. 823-825.

Sheldrake, Rupert. **A New Science of Life**: The Hypothesis of Formative Causation, Blond & Briggs, Ltd., U.S. reprint, J.P. Tarcher, Inc., Los Angeles, 1982.

Smetanin, E.V., "Electromagnetic field in a space with curvature – new solutions," **Soviet Physics Journal**, 25(2), Feb. 1982, p. 107-111.

Tapscott, Mark. "DOD, Intel Agencies Look at Russian Mind Control Technology, Claims." **Defense Electronics**, 25(8), July 1993, p. 17.

von Borzeszkowski, Horst-Heino. "Remarks on the Physical Reality of Gravitons," **Foundations of Physics**, 20(4),1990, p. 435-445.

Wheeler, John Archibald and Richard Phillips Feynman. "Classical electrodynamics in terms of direct interparticle action," **Reviews of Modern Physics**, 21(3), July 1949, p. 425-433.

Goodman, Glenn W. Jr. "Upping the Nonlethal Ante," **Armed Forces Journal International**, July 1994, p. 13.

Jammer, Max. **Concepts of Space: The History of Theories of Space in Physics**. Harvard University Press, Cambridge, Massachusetts, 1969

Jammer, Max. **Concepts of Force**. Harvard University Press, Cambridge, Massachusetts, 1957.

Jammer, Max. **Concepts of Mass**. Harvard University Press, Cambridge, Massachusetts, 1961.

Javier, R.T.; F. Sedarati, and J. G. Stevens. "Two avirulent Herpes simplex viruses generate lethal recombinants in vivo." **Science**, 234(4777), Nov. 7, 1986, p. 746-747.

Wheeler, J.A. and R.P. Feynman. "Classical Electrodynamics in Terms of Direct Interparticle Action," **Reviews of Modern Physics**, Vol. 21, 1949, p. 425-433. The electromagnetic field as such does not actually exist in spacetime, but is a summary of what we need to know about distant charges in order to predict the behavior of a charge if there should be one at that point. In other words, the EM field represents an information storage device.

Jaynes, E.T. "Probability In Quantum Theory," in **Complexity, Entropy, and the Physics of Information**, Ed. W.H. Zurek, 1990, pp. 33-55, Addison-Wesley, Redwood City, CA. Strongly points out that the EM field does not exist in spacetime, but represents an information storage device.

Editorial Note: *We would like to express our appreciation to Mr. Bearden for this wonderful article.*

The Tom Bearden Website

"Dossier Priore"

by Jean-Michel Graille

Photographs

Cover	
Plate 1	The inauguration: the construction of the M 600 had not yet started but, symbolically, the Mayor of Bordeaux starts the smaller machine at close range. (Archives R.P.)
Plate 2	Inaugural scroll.
Plate 3	An information meeting held in Bordeaux. From left to right: Antoine Priore, Robert Courrier, Raymond Pautrizel and Francis Berlureau. (Archives R.P.)
Plate 4	February 1975. Antoine Priore and Professor Pautrizel at the "suspended" base of the M 600, the enormous experimental prototype built by Leroy-Somer. The apparatus would only function for a few days but did make it possible to carry out some experiments with very promising results.
Plate 5	Anne-Nelly Pautrizel. Professor Pautrizel's sister and collaborator, who participated in almost all the experiments with the Priore apparatus since 1968. (Photo J.M.G.)
Plate 6	Pierette Châteaureynaud-Duprat, head of research at C. N.R.S., doctor of science and specialist in grafts, carried out in 1969 and 1970 two series of decisive experiments concerning the proof and the explanation of the biological effectiveness of the Priore Ray.

Plate 7	The Priore machine. The model financed by Pautrizel, the only one which is still likely to function, the one with which patients will be officially looked after as from 1977, is finished in August 1968. In fact, the apparatus is installed all in one place.
Plate 8	1969. Old friends of Priore retrace the road to Floirac. With a monkey-wrench or soldering-iron in hand, they devote all their leisure time to building the new machine for their friend. Here, on the scales, inspector Plantin, of the legal identity service. In coveralls, scarf around his neck, municipal worker M. Léglise. (Archives R.P.)
Plate 9	A courageous man. Perpetual Secretary of the Academy of Sciences, elder President of the Academy of Medicine, "father" of endocrinology and fertilization, Professor Robert Courrier could have benefited from its prestige and its retirement. At 67, he took all the risks to defend that which he believed in deeply. He has fought now for twenty years. One of the rare photos of him, in the company of Antoine Priore and Professor Pautrizel, taken on 25th March 1970 in the laboratory at Floirac. (Archives R.P.)

Jean-Michel Graille
DOSSIER PRIORE
Une nouvelle affaire Pasteur?
Denoël





MONSIEUR JACQUES CHABAN-DELMAS
MAIRE DE BORDEAUX
PRESIDENT DE LA COMMUNAUTE URBAINE
ET
MONSIEUR ANTOINE PRIORE
ONT POSE LE 21 NOVEMBRE 1972
PREMIERE PIERRE DU LABORATOIRE DE RECHERCHES SCIENTIFIQUES
SUR LES EFFETS BIOLOGIQUES DU RAYONNEMENT PRIORE

Translation:

JACQUES CHABAN-DELMAS
THE MAYOR OF BORDEAUX
PRESIDENT OF THE URBAN COMMUNITY
AND
ANTOINE PRIORE
HAVE INSTALLED ON THE 21 NOVEMBER 1970
THE FIRST STONE OF THE SCIENTIFIC RESEARCH LABORATORY
FOR THE BIOLOGICAL EFFECTS OF THE PRIORE RAY





Making Laser Weapons a Reality



Figure 1. The Boeing HEL MD has demonstrated the ability to destroy a 60 mm mortar round in flight. (Photo courtesy of Boeing Defense)

Directed energy weapons first took a step towards reality in the 1980s under President Reagan's Strategic Defense Initiative (SDI), dubbed "Star Wars" by the media. But, the technology didn't really materialize at that time and the cessation of the Cold War largely removed the immediate impetus to develop it. Since then, lasers have become widely used in military applications, particularly for target designation and aircraft countermeasures, but there is still no significant deployment of lasers as offensive weapons. Now, advances in high power fiber laser technology, particularly in the efficiency, compactness and weight of their pump diode lasers, are poised to make laser weapons a practical reality.



Figure 2. A Coherent | DILAS T-Bar chip contains five emitters, outputs about 50 W, and is 5 mm wide.



Single 5 Emitter T-Bar
Output
4 T-Bars on a single submount with collimating optics
Fast axis collimator
Slow axis collimator
Vertical stack of 4 submounts

Figure 3. Progression from a single T-Bar die to an 80-emitter stack. The light from all these emitters can be efficiently coupled into a single 225 μm core fiber with a 0.22 NA.

Laser Weapons Overview

The concept behind Reagan's SDI was to protect the United States behind a "missile shield" that would prevent nuclear weapons, delivered via either intercontinental or submarine-launched ballistic missiles, from reaching North America. Part of the SDI was to be lasers, or other directed energy weapons, placed in permanent orbit, which could rapidly knock out a nuclear missile already in flight towards its target. Lasers, in particular, were a promising technology for this application because they can be quickly "charged up" (i.e. be made ready to fire), and their output can reach a fast-moving target nearly instantaneously.

Because these lasers were intended to be deployed primarily in space, or in fixed locations, and used either never (hopefully) or just once, there wasn't much concern about their cost, physical size, weight or operational efficiency. The key goal was simply that they would work when needed, delivering the required knock-out punch.

The offensive laser weaponry under development today is intended to serve almost the exact opposite purpose than the SDI, and therefore has very different goals in terms of its design and functionality. For example, one major laser weapons initiative is for C-RAM (Counter Rocket, Artillery and Mortar). These are systems intended to be deployed in the battlefield to protect troops and equipment from incoming projectiles. Currently, these are envisioned to be single, vehicle mounted lasers, with output powers in the 10 kW to 50 kW range.

Boeing has already successfully prototyped such a system, which they call the High Energy Laser Mobile Demonstrator (HEL MD). This consists of a 10 kW solid state laser installed on an Oshkosh Tactical Military Vehicle, along with all the necessary targeting and control systems. HEL MD has proven the ability to lock on to and destroy a mortar round of about 10 inches in length, traveling at hundreds of miles per hour, from several miles out. The system is also effective against Unmanned Aerial Vehicles (UAVs or drones); in this case, it may be sufficient to damage the drone's navigation and targeting systems, rather than completely destroy it. Similarly, other offensive laser weapons systems are being designed to deliver "swarm defense," that is, to protect a ship or base from attack by a large number of inexpensive drones.

Thus, today's laser weapons are meant to defend against swarms of inexpensive mortar rounds, drones and other projectiles, and are intended to be mounted on platforms which are mobile and self-contained (meaning they may not have ready access to an external source of power). This gives rise to several design imperatives. First, they must deliver a low cost per engagement; it's simply not economically feasible to employ an expensive weapon (such as a missile costing over $100,000) to knock out a drone which costs $1,000, or a mortar round which might cost less than $100. The laser weapon must also be capable of rapid fire so that it can't just be overwhelmed by a large number of simultaneous incoming rounds. Also, rapid fire reduces the number of individual laser weapons systems needed to protect a given number of troops. But, the ability to deliver rapid fire also necessitates that the system be electrically efficient. Otherwise the laser weapon will require access to a large quantity of fuel, which is difficult (and dangerous) to transport into a battlefield. Finally, it's desirable that laser weapons be physically compact, especially for airborne use.

SWaP Optimization

The push to optimize the size, weight and power (called SWaP in military parlance) of field deployed laser weapons has driven a progression in the technology of the gain material used from chemical (e.g. deuterium fluoride), to solid state, and, most recently, to fiber. One reason for this is because fiber lasers offer inherently higher efficiency, in terms of converting input pump energy to usable output, than nearly any other laser type, except diode lasers. However, diode lasers by themselves don't provide the necessary brightness or beam quality, while diode-pumped fiber lasers can. And, beam quality is critical because it determines the distance over which the laser can be focused to a spot size small enough to reach the power density necessary to damage its target.

Fiber lasers offer other advantages in terms of SWaP optimization. Chemical and lamp pumped solid state lasers require a significant overhead in terms of the equipment and power supplies required to run them. In contrast, both solid state (e.g. slab and rod) and fiber lasers can be diode pumped, and diode power supplies and pump modules themselves are electrically efficient and lend themselves to miniaturization. This efficiency, in turn, reduces the cooling requirements, and all its attendant equipment (pumps, heat exchangers, etc.).

But, as laser weapons evolve towards ever higher powers, fiber laser technology becomes increasingly attractive over solid state. Currently, individual fiber lasers can deliver up to about 2 kW of power, but multiple units can be combined to deliver around 10 kW in a single beam with extremely good mode quality. It's a bit more difficult to scale up the power of a solid-state laser, especially while maintaining good mode quality. This is because scaling up and/or increasing the pump power to a traditional solid state laser typically excites higher order modes, and introduces other issues related to thermal lensing.

Of course, there are also challenges to increasing the power of a fiber amplifier. And, because the optical efficiency of their pumping is already so high (~85%), there's not much room for improvement there. So, the focus is on raising the pump power itself, without increasing package size and weight, as well as on methods for low loss beam combining of multiple single mode lasers, all while still maintaining good beam quality.


Figure 4. Four T-Bars mounted on a macrochannel cooler with collimating optics.

Pumping Technology Advances

In terms of SWaP optimization of pump diodes for laser weapons, a current benchmark is to achieve a weight to output power ratio of 1 kg/kW. Coherent | DILAS has developed several advances in diode laser technology to reach this goal, and, in fact, is already working on devices that will attain the next level of performance – 0.5 kg for 1 kW of output.

One key to reaching the SWaP benchmark has been the company's introduction of T-Bar (for "tailored" bar) construction, a design approach intended to combine the high total output power of traditional diode laser bars with the relaxed cooling requirements of single emitters. The basic unit of the T-Bar is a diode laser mini-bar having five emitters on a single, 5 mm wide substrate which outputs about 50 W total. In contrast, traditional diode laser bars are usually 10 mm wide, contain at least 19 emitters, and can output over 200 W, depending on the number of emitters and type of heatsink.

For military applications, four of these T-Bar dies are mounted on to a single substrate, yielding a total of 20 emitters. Then, up to four of these substrates are stacked vertically, bringing the total number of individual emitters in this compact assembly to 80, with a total output of about 800 W.

The key optical characteristic of the T-Bar design is that the combination of wide emitter spacing, low divergence and relatively low beam parameter product (in both fast and slow axes) is tailored to enable the light from all 80 of these individual emitters to be efficiently co-linearized and coupled into a single 225 µm core fiber having a numerical aperture of only 0.22. This, in turn, permits highly efficient coupling into the pumping mode volume of the gain fiber. And, this light collection can be accomplished using a relatively simple and compact optical system. This is how output power per unit volume is maximized.

In contrast, the high divergence and poor mode quality of traditional diode laser bars necessitate the use of complex optics for light collection, and still make it impossible to couple all their output into a single, low numerical aperture fiber. Furthermore, high power diode laser bars often suffer from a problem called "smile." This is a sagging or bending alignment error in emitter position along the bar which makes it quite difficult to collimate and co-linearize its output.

Besides the advantage of producing the largest amount of fiber coupled light out in a given system volume, T-Bar construction also offers significantly improved cooling characteristics over traditional bars. In a traditional diode laser bar, the small emitter spacing causes significant thermal crosstalk between the individual emitters, and a very high efficiency cooling system must therefore be employed. This is usually in the form of a so called "microchannel" cooler, in which water is rapidly circulated through channels within the heatsink. But the small bore of the microchannels (tens of microns) makes it easy for them to be clogged by particulates. Thus, the water must be stringently conditioned and filtered, and large, heavy, high pressure pumps must be employed to circulate it rapidly enough to achieve the required level of cooling in these traditional bars.

Furthermore, traditional diode bars are usually placed directly on the heatsink in order to achieve good thermal contact. However, this makes the microchannel cooler part of the electrical circuit, thus necessitating the use of deionized water in order to avoid a short circuit. This imposes yet another requirement that increases cost and complexity.

The larger emitter spacing of the T-Bar largely eliminates this thermal crosstalk, and greatly relaxes the attendant cooling requirement. As a result, Coherent | DILAS has been able to introduce a "macrochannel" cooler. This is a system which uses substantially larger bore channels, thus allowing the use of less stringently filtered tap water, and eliminating the need for high pressure pumping. Also, the reduced cooling requirement enables the laser bar to be placed on a submount, rather than in direct electrical contact with the cooler, which avoids the necessity of using deionized water.

T-Bar construction also delivers better cooling characteristics than single emitter diode lasers. This is because single emitters are typically supplied already packaged. Since the diodes are mounted within the package, there is an extra thermal interface which makes it more difficult to efficiently cool them.

In conclusion, after decades of imagining, offensive laser weapons are nearly ready for deployment on the battlefield. Advances in diode laser pumping technology are proving to be a key enabling factor in this development. And, these military grade pump diode lasers can be constructed using the same automated, high volume fabrication equipment used for industrial product manufacturing, meaning they can be readily delivered at competitive prices.

This article was written by Chris Ebert, Ph.D., Director, Business Development, Coherent | DILAS, (Tucson, AZ). For more information, visit ***http://info.hotims.com/65852-501****.*

The Tom Bearden Website

Table of Contents

A Sensitive Scalar Wave Detector

1.
2.
3.
4.
5.
6.
7.
8.
9.
10.
11. Figure 11. NETWORK OF VIRTUAL TRANSMITTERS
12. Figure 12. VIRTUAL TRANSMITTERS IN THE INTERFERENCE GRID
13. Figure 13. GIANT RADIAL RELATED TO A VIRTUAL TRANSMITTER
14. Figure 14. FORMATION OF A SINGLE GIANT RADIAL
15. Figure 15. FORMATION OF A DOUBLE GIANT RADIAL
16. Figure 16. DETECTION OF TRANSVERSE AND LONGITUDINAL WAVES

Return to Homepage

from **STAR WARS NOW!**

The Bohm-Aharonov Effect, Scalar Interferometry, and Soviet Weaponization
by Lt. Col. T.E. Bearden (retd.), 1984
Copyright

A Sensitive Scalar Wave Detector

Very briefly we present a method of making a very sensitive scalar wave detector so that direct measurement and quantization can be established.

First, we regard one oscillation (one wavelength) of the scalar potential wave as a longitudinal photon. Note that this photon contains a substructure, which may be deliberately determined (when artificially made) or randomized (when naturally made in the idealized case).

For convenience we represent normal linearized vacuum (spacetime) as a horizontal or longitudinal vector (Figure 4), implying the direction of motion of the wave in the laboratory frame. By horizontal position in our diagram, we imply a linear, uncurved spacetime and a non-rotated frame. We represent the longitudinal scalar wave as a horizontal vector, and the usual Hertzian wave as a vertical or "transverse" vector. We visualize a normal detector as detecting only a vertical or "transverse" vector, as we have illustrated in Figure 4.

As can be seen, in a linear, unrotated or uncurved spacetime a pure scalar wave has no vertical component projected upon the laboratory frame vector, so it is not detectable by normal detectors.

To detect the scalar wave, of course we could bend it so that it has a projected vertical component in the laboratory frame (Figure 5). However, this would be an impure wave, not a pure scalar wave, and that is not what we wish.

A better way is to bend or curve spacetime itself in a small region, so that a longitudinal wave that passes through that region now possesses a vertical component with respect to that region (Figure 6). Thus a normal detector there will detect that vertical component. We conduct the detection current out of the "bent spacetime" region to an outside (normal) detector, and we then have a scalar wave detector.

To illustrate, we show conceptually how this has been successfully done. Figure 7 shows the concept. First, we utilize a magnetic pole to provide the infolded energy (potential) to bend or curve spacetime. To reach good sensitivity, we need a pole strength connected with a magnetic field strength of 40,000 Gauss or higher. We utilize a small superconducting magnet, which can reach field strengths of from 40,000 to 80,000 Gauss.


Hertzian Wave
Scalar Wave
Direction of Wave Motion in Lab Frame

Figure 4. Linear, uncurved laboratory frame.


Bent Longitudinal
Scalar Wave
Transverse Projection
Lab Frame

Figure 5. Rotating the longitudinal wave produces a transverse component.


Longitudinal Scalar Wave
Apparent Transverse Projection
Rotated Laboratory Frame

Figure 6. Bending the laboratory spacetime frame produces a transverse component.


Oscilloscope
Shielded
Cable
Faraday Shield
Wire
N
S
Super-
Conducting
Magnet
Resonant
Tuning
Circuit
Pre-amp
Insulated
Plug

Figure 7. A sensitive scalar wave detector.

Figure 7. A sensitive scalar wave detector.



(DETECTS ELECTROGRAVITATIONAL WAVES)

NOTE: MAGNET > 40,000 gauss

*BEDINI VERSION OF DEA/FARETTO DETECTOR

Slide 33 - FER DE LANCE

Then to prevent detection of superfluous "normal" radiation, we shield the entire magnet in a grounded Faraday cage, as shown in the figure. Hertzian waves will be grounded in this shield, while scalar waves will readily penetrate it undiminished. In other words, the Faraday cage serves as a "stripper," to strip away the ordinary waves, leaving only the scalar waves to penetrate inside. An ordinary wire lies at the top of the magnetic pole, in proximity to it. The wire runs out of the Faraday cage through an insulated port to a resonant tuning circuit, which is sharply tunable over the range of frequencies we are interested in. A preamp amplifies the output of the tuner, and in turn feeds the input of an oscilloscope or other detector.

With this detector we can select the frequency desired, and detect any passing scalar waves of that frequency. By other variations of amps and preamps, regenerative circuits, etc. we can obtain all the sensitivity desired, and utilize ordinary detection equipment already well-known and highly developed.

Additional Information about detecting Scalar Waves

The Tom Bearden Website

Figure 11. NETWORK OF VIRTUAL TRANSMITTERS

(See Woodpecker Grid)



Next Figure

The Tom Bearden Website

Figure 12. VIRTUAL TRANSMITTERS IN THE INTERFERENCE GRID


Note: May be troughs instead of peaks. In that case, energy is extracted.
Energy peaks (virtual transmitters)

Next Figure

Previous Figure

[The Tom Bearden Website](#)

Figure 13. GIANT RADIAL RELATED TO A VIRTUAL TRANSMITTER

**Fall 1983:
Florida
Alabama**



[Next Figure](#)

[Previous Figure](#)

The Tom Bearden Website

Figure 14. FORMATION OF A SINGLE GIANT RADIAL


INTENSE PEAK OF NORMAL ENERGY
VERY SMALL PEAKS
CLOUD RADIALS 10 – 20 MILES LONG
CLOUD RING (~ 5 MI. DIA.)
Early 1984: California, Alabama, Iowa, 400 miles west of Memphis.
SCALAR INTERFERENCE GRID PATTERN

Excerpt P 172
FER DE LANCE

A Briefing on Soviet Scalar Electromagnetic Weapons
by Lt. Col. T.E. Bearden (retd.), 1986
Copyright

2. Continual cloud radials have repeatedly been seen and photographed over Huntsville, Alabama, associated with weather engineering and grid activity. Typical radials seen by this author are shown in Bearden, Soviet Weather Engineering Over North America, 1-hr. v1deotape, 1985. Huntsville is apparently a pivot point or "hinge point" for bending and controlling the jetstream.

3. Spectacular cloud grid patterns have been seen over Huntsville, Alabama and Los Angeles, California. An excellent videoclip of one of the Los Angeles area grids, personally observed and shot by KABC Open Mind talk show host Bill Jenkins, is shown in Bearden, Soviet Weather Engineering Over North America,;1-hr. videotape, 1985. An artist's sketch of an earlier gigantic grid, extending from horizon to horizon in every direction, seen over Huntsville, Alabama by Tom Bearden and Ken Moore, is also shown in the tape. The videotape is available from P.O. Box 1472, Huntsville, AL 35807. Sketches and details of another highly anomalous grid pattern observed in the greater Los Angeles area by engineer Ron Cole are shown in figures 5 and 6.

The reason that clouds of water droplets and/or ice particles detect the scalar interferometry and form signature patterns is simple: Consider each H2O molecule as having two light little hydrogen atoms hanging on to the much heavier oxygen atom. The covalent sharing with the oxygen atom of the electron from each hydrogen atom means that

1. the electrostatic scalar potential between the H ion and the O ion it is bonded to, is rhythmically varying as the electron is shared back and forth,
2. this varying potential contains "electron spin holes" since it is made by the moving electron,
3. two such varying potentials exist since there are two H atoms sharing covalent electrons with the O atom,
4. the two H ions are at an angle of over 100 degrees with respect to each other,
5. the molecule assembly thus constitutes one part (one half, so to speak) of a scalar interferometer with imbedded electron spin holes for electron hooking,
6. Incident scalar waves from outside the system interact with the "half scalar interferometer." This scalar interferometry interaction is coupled to the covalent bonding electron because of the internal spin hole pattern of the molecular half of the interferometer. The coupled electron moves with the sca1ar pattern's changes, causing an observable interaction with and in the electrical structure and ionic potential of the molecule,
7. the weak H to H hydrogen bonding between molecules connects resulting ionic potential changes to the structuring of the entire macroscopic cloud assembly. Thus by scalar interferometry with the H_2O "half interferometers", an incident scalar EM pattern is detected and translated into patterns of E and B force fields. The H_2O molecules then "line up" in accord with the electrical patterns detected.

Thus the clouds form "signature patterns" according to the incident scalar EM radiation patterns. Giant cloud radials in the targeted area are probably due to the type and shape of antennas including the type and shape of the electrical wires establishing the antennas' ground planes -- used by the Soviet Union to project the scalar waves. Note that such "radial" antenna patterns were occasionally used by James Harris Rogers in his underground and undersea scalar EM transmission system.

Next Figure

Previous Figure

The Tom Bearden Website

Figure 15. FORMATION OF A DOUBLE GIANT RADIAL


PATTERN LINKING
INTENSE PEAK OF NORMAL ENERGY
INTENSE PEAK OF NORMAL ENERGY
CENTRAL RING DISAPPEARS
BOATTAILED
Two sightings over Huntsville, Alabama
SCALAR INTERFERENCE GRID PATTERN

Next Figure

Previous Figure

The Tom Bearden Website

Figure 16. DETECTION OF TRANSVERSE AND LONGITUDINAL WAVES


ANT
NORMAL
EM
NORMAL XMTR
"transverse" EM wave
transverse oscillations induced in electron gas
DETECTION
ANT
NORMAL
EM
XLTR/XMTR
longitudinal EM wave
no detection
NORMAL DETECTOR
no transverse oscillations induced
special ant
SPECIAL DETECTOR
detects

Next Figure

Previous Figure

Defense Department Briefing on Priore Treatment to counter Biological Warfare

---

SLIDE LIST

Solutions to Mass Casualties Treatment Problem

Threat and Current Status

1. Title Page
2. Key Points in the New Technology
3. Title Page
4. Title Page
5. The Terrorist Threat
6. The Superpower Paradox: Asymmetric Cheap WMD Strategic Strike and Destruction
7. Mass Casualty Problem: Aerial Anthrax Spray on Washington, D.C.
8. Present Status of the WMD Threat to the United States
9. Some Present Problems in the WMD Defense Capabilities

Historical Solution: Priore Treatment Therapy

10. Title Page
11. Priore's laboratory device for treating small animals
12. Antoine Priore with the Mayor of Bordeaux
13. Raymond Pautrizel, eminent French parasitologist, who worked with Priore
14. 12-Foot plasma tube in Priore's large device
15. Priore's 3 1/2 stories high device for whole body treatment of humans
16. Mechanism of the Priore therapy
17. Priore's therapeutic methodology: using infolded longitudinal EM waves as NLO pump waves, to pump in the time domain
18. Drastically reduced cumulative deterioration after Priore therapy

Extended Physics and Background

19. Title Page
20. Founders of Scalar Electromagnetics
21. Subdivisions of Soviet Energetics

22. Bunge on the Status of Classical and Quantum Physics
23. Einstein on Reviewing Foundations
24. Fields and Potentials have been "defined" only in and on matter
25. Maxwell's Equations are Matter-To-Matter Transforms
26. Electrodynamicists' Reaction to Removal of the Material Ether
27. The Missing Infolded Electrodynamics
28. Nonlinear Optics Distortion Correction Theorem
29. Infolded longitudinal EM biwave composition of a scalar potential
30. The Zero-Vector Axiom Destroys "Topologies Within Topologies"
31. Stoney-Whittaker Bidirectional Longitudinal EM Wave-Pair
32. Undistorted Progressive Waves (UPWs)
33. Velocity modulating a longitudinal EM wave oscillates rate of flow of time
34. The Graviton is a Coupled Photon/Antiphoton Pair
35. Mechanism for Physical Change and the Flow of Time
36. Any EM Field or Wave Pattern is Produced by interference of Two Scalar Potential Functions (E.T. Whittaker, 1904)
37. Mass is transparent to longitudinal EM waves, which move through the infolded interiors of internal waves, potentials, and fields in the mass
38. Deep penetration of weak signals in a dense signal environment, by nonlinear retroreflection
39. The Immune System
40. Popp's master cellular control system
41. Cancer: characteristics
42. The evolutionary path of multicellular organisms
43. Effect of fluid contamination on hemoglobin's oxygen transport
44. First step in Self-Promotion of Cancer due to Hypoxia
45. Becker's Cellular Growth Control
46. Becker's dc treatment of bone fractures
47. Becker's theoretical DC control system involved with responses to injury
48. Becker's theoretical control system governing regeneration
49. Link Between Standing DC Potentials and the Nervous System
50. Becker's Findings on Cellular Injury and Regeneration
51. Corrections For the Present EM Bioeffects Model
52. R&R System - Regeneration Example
53. Kaznacheyev's Cytopathogenic Mirror Effect
54. Microwave Radiation of U.S. Embassy in Moscow

55. Self-Targeting in Inner EM Channel Can Produce a Quantum Potential
56. Quantum potential and hidden variable theory
57. Participants in a quantum potential share a common multiply-connected spacetime (MCST)
58. Gulf War Syndrome and Typical Comparative Disease Curves
59. Force Fields and Symmetry
60. Aspects of Strong Local Asymmetry
61. Other Aspects of Strong Local Asymmetry
62. Small Entities Emit Powerful S-Flows
63. What is the "magnitude" of a potential?
64. Table A1. The Vacuum Energetically Interacts With Every Particle, Continually
65. Extended Superpotential Theory (Adding Vacuum Engines)
66. Vacuum Engine: Jillions of Working ST Demons
67. Active Spacetime and a Specific Vacuum Engine (A General Relativistic Concept and Analogy)
68. Extension of Wheeler's general relativity principle
69. Signal versus Vacuum Engine
70. Electronuclear Interactions by Vacuum Engines
71. Vacuum Engineering
72. Impact of Vacuum Engineering
73. A Dramatic Extension to Nonlinear Optical Pumping
74. Time Conservation and Some Properties (Energy and time are canonical)
75. A Dramatic Extension to Nonlinear Optical Pumping
76. Key Points in the New Technology

Modern WMD Solution: Portable Treatment Systems

77. Title Page
78. Portable Priore-Type Treatment System
79. Portable System Block Diagram
80. Portable Priore Technology Unit
81. Saving the Stricken Civilians

Conclusions: Technology Practical, Proven

82. Title Page
83. Summary and Conclusions

Recommendation: Crash Development Program

84. Title Page
85. Recommend implementing:
86. Final Thoughts



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

CTEC, Inc.

28 Mar. 1998

(c) 1998 T.E. BEARDEN

Return to Slide Index

Next Slide



Key Points in the New Technology

- There is a vast new kind of electrodynamics *hidden inside* all EM potentials, fields, and waves
  - Longitudinal EM waves and complexes
  - Oscillations in time domain
- These complexes are an *infolded general relativity*
  - Clustered formations of *spacetime curvatures*
  - *Very powerful*, since the EM force is used as the agent of curvature
- In general relativity, similar precise complexes permeate and *act on any mass at all internal levels*
- With this approach, one *can now manipulate matter* -- living or inert -- *in any manner desired*, depending only on the level of development of the technology
- Priore unwittingly used this to *cure dread diseases*
- This is a *revolution in all of science*
- *We have uncovered the major mechanisms* to utilize

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes
on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc.

28 Mar. 1998

© 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc.

28 Mar. 1998

© 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



THE TERRORIST THREAT

TODAY:

- Sabotage
- Chemicals
- Biological agents
- Nuclear materials
- Powerful explosives
- Assassination
- Kidnapping and hostages
- Contamination
- Shoulder-fired AD missiles
- Terrorism

FUTURE ADDITIONS:

- EM weapons
- EM biological warfare
- Scalar EM weapons
- Scalar EM disease induction
- Alteration of behavior and emotions
- Alteration of memory
- Direct thought control
- Action-at-a-distance effects

© 1992, 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide

The Superpower Paradox: Asymmetric Cheap WMD Strategic Strike and Destruction


Complex, expensive, high tech
LIBYA
EGYPT
SUDAN
SAUDIA ARABIA
IRAN
Simple, cheap, low tech

© 1993, 1996, 1998 T.E. BEARDEN

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



Mass Casualty Problem: Aerial Anthrax Spray on Washington, D.C.

- One terrorist, one light aircraft with spray tank
- 100 kilograms of anthrax
- Flies over greater metropolitan Washington, D.C.
- Calm night
- *1-3 million casualties result**
- *Most of those stricken will die*
- Presently little can be done to save the stricken civilians
- *Attacks on several population centers might produce some 10 million or more casualties*

*Per OTA Report to Congress, 1993

[Return to Slide Index]

[Next Slide]

[Previous Slide]



Present Status of the WMD Threat to the United States

- Many foreign nations are hostile to the U.S. and sponsor terrorists
- Some 25 nations have WMD or are acquiring them
  - BW agents and weapons
  - Chemical agents and weapons
  - Nuclear materials and weapons
- Thousands of students and emigres
- Infiltrated teams, BW, other WMD already
- Castro guerrillas infiltrated over the years
- Can do unacceptable damage to U.S. now
- *May reach first strike knockout capability*

© 1998 T.E. BEARDEN

*Per OTA Report to Congress, 1993

Return to Slide Index

Next Slide

Previous Slide



Some Present Problems in the U.S. WMD Defense Capabilities

- *No shelters (require overpressure, BW filtering, masks, showers, supplies)*
- *No stockpiled vaccines, medical supplies, immunoglobulins, masks, suits, food, fuel, generators, heaters, water purification units*
- Totally insufficient medical facilities, personnel, and emergency response teams
- Triage, full martial law will be required
- *No answer to massive decontamination problem*
- State, county, city inadequately staffed and insufficiently trained for mass casualties
- Terrorist teams, BW agents, other WMD on site, waiting
- Water supplies, food, crops, farm animals also vulnerable
- Electric power grid, bridges, trains, railroads vulnerable
- *Present medical science cannot save very many of the casualties, now or in the foreseeable future*

© 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc.

28 Mar. 1998

(c) 1998 T.E. BEARDEN

[Return to Slide Index]

[Next Slide]

[Previous Slide]



Priore's laboratory device for treating small animals

GIANT COIL WITH PLASMA MIXING TUBE INSIDE
SMALL ANIMAL HOLDER

Return to Slide Index

Next Slide

Previous Slide



Antoine Priore (right) with the Mayor of Bordeaux, Mr. Chaban-Delmas.

Photo courtesy of Bob Whitney

The Priore technical mechanism unwittingly involved a dramatic extension to both nonlinear optics and general relativity. However, nonlinear optics itself had not yet been born in the 1950s and 1960s when Priore worked out his methodology. The extension to general relativity has not been previously envisioned even to the present day. When the Priore project was suppressed by the changed French government in the mid-1970s, nonlinear optics itself was just being initiated. To the present day, however, there has previously been no inkling of the dramatic extension to NLO that arises by using longitudinal EM pump waves and thereby pumping in the time domain.

It is little wonder that Priore himself did not understand the nature of the technical mechanism he was utilizing, and neither did anyone else, and neither *has* anyone else prior to this time.

© 1998 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



Raymond Pautrizel, eminent French parasitologist who worked with Priore

Among other things, Pautrizel treated seriously infected immature rats with the Priore ray. These rats had never had a mature immune system. When they were removed from the machine, they still sickened again and died, because their immature immune systems could not resist the pathogen *(Trypanosoma)*. So even though the damaged cells were reversed back to normal, the "normal" immune system was unable to fight off pathogens, which reinfected the cells and killed them, killing the rats.

This established the time-reversal nature of the therapy.

© T.E. BEARDEN 1997

Return to Slide Index

Next Slide

Previous Slide



12-Foot plasma tube in Priore's large device

PHOTO COURTESY BOB WHITNEY

Return to Slide Index

Next Slide

Previous Slide



Priore's 3-1/2 stories high device for whole body treatment of humans

Giant coil around 12-ft long plasma tube
Pulsed DC Magnetic field
Table for reclining human body

Return to Slide Index

Next Slide

Previous Slide



MECHANISM OF THE PRIORE THERAPY

- FACT: DISEASE-SPECIFIC VACUUM ENGINE PRESENT FOR ANY CELLULAR DISEASE, BY WHEELER'S PRINCIPLE
  - *DISEASE CAN BE REVERSED BY CREATING AMPLIFIED VACUUM ANTI-ENGINE (BEARDEN'S PRINCIPLE)*
  - *ANTI-ENGINE IS CREATED BY PUMPING THE NONLINEAR CELLS IN THE "INNER EM" DOMAIN, TIME-REVERSING THEM*
- PRIORE UTILIZED A PLASMA TO PHASE CONJUGATE AND "INFOLD" MULTIPLE BIDIRECTIONAL LONGITUDINAL EM PUMP WAVES
  - *17 FREQUENCIES MIXED IN A ROTATING PLASMA*
  - *PHASE CONJUGATES ADDED BY THE PLASMA*
  - *INFOLDED MIX INTO STRONG PULSED DC MAGNETIC FIELD, WHICH CARRIED IT INTO ATOMIC NUCLEI*
  - *PUMPED ALL NONLINEAR CELLULAR COMPONENTS TO PRODUCE AMPLIFIED, SPECIFIC VACUUM ANTI-ENGINE*
- NEGATED THE LONG-TERM CUMULATIVE CELLULAR DEDIFFERENTIATION ORDER GENERATED BY LONG-TERM HYPOXIA. TUMOR CELLS REVERTED TO NORMAL CELLS.
- SCRUBBED OUT THE CUMULATED PRECANCEROUS STATE
- RESTORED THE IMMUNE SYSTEM TO HIGH FUNCTIONING
- NO EXCESSIVE TRAUMA TO TREATED ANIMAL

CANCR-69

© 1994, 1996, 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Priore's therapeutic methodology:
Using infolded longitudinal EM waves as NLO pump waves, to pump in the time domain

Time-reverses the cells back to normal state

START

FORM A SET OF HARMONIC EM WAVES (17)

ADJUST SOME WAVE FREQUENCIES

MIX WAVES IN A PLASMA TO ADD CONJUGATES

MIX OUTPUT INSIDE STRONG PULSED DC MAGNETIC FIELD

EXPOSE WHOLE BODY OF PATIENT TO DIMENSIONED MAGNETIC FIELD

CELL AND ALL ITS PARTS ARE PUMPED IN INNER EM CHANNEL IN TIME DOMAIN

VACUUM ENGINE FOR DISEASED CELL ALREADY PRESENT

DISEASED CELL PHASE CONJUGATES ITS VACUUM ENGINE

FORMS AMPLIFIED VACUUM ANTIENGINE FOR CELL'S DISEASE VACUUM ENGINE

TIME REVERSES CELL AND ALL ITS PARTS*

*Includes genetics

CELL RESTORED TO NORMAL?

YES

STOP

NO

© 1994 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



DRASTICALLY REDUCED CUMULATIVE DETERIORATION AFTER PRIORE THERAPY

NOTE: Priore therapy treats entire body.

BODY
Cells and tissues

Cancer Threshold

Body action point

MAGNITUDE OF SUSCEPTIBILITY

Deterioration after conventional treatment

Deterioration before treatment

Δ (conventional therapy)

Dramatically reduced deterioration after Priore therapy.

Separation from body action point

CONVENTIONAL THERAPY:

Scarring, physical damage, etc. Immune system deterioration.

PRIORE THERAPY:

No scarring or physical damage, etc. Immune system restored.

JCS-50

© 1993, 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc.

28 Mar. 1998

© 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Founders of Scalar Electromagnetics

- **G.J. Stoney:**

Decomposed the scalar potential into bidirectional wave pairs.

"On a supposed proof of a theorem in wave-motion," Phil. Mag., 5(43), 1897, p. 368-373 (and several other papers).

- **E.T. Whittaker:**

Decomposed the scalar potential into a series of bidirectional EM wave pairs in harmonic series, where the two waves in each pair are conjugates (i.e., a wave/antiwave pair) and are longitudinal waves.

"On the partial differential equations of mathematical physics," Math. Ann., Vol. 57, 1903, p. 333-355.

Showed that all classical EM -- including waves -- can be replaced by two interfering scalar potential functions.. (This founded superpotential theory, extended by Nisbet, Bromwich, Debye, McCrea, and others.)

"On an expression of the electromagnetic field due to electrons by means of two scalar potential functions," Proc. Lond. Math. Soc., Series 2, Vol. 1, 1904, p. 367-372.

- **R.W. Ziolkowski:**

Independently rediscovered the biwave decomposition of the scalar potential and added the product set (in theory enabling modulations and communications) to Stoney and Whittaker's sum set.

Various papers, 1985 to date.

© T.E. BEARDEN [illegible]

Return to Slide Index

Next Slide

Previous Slide



Subdivisions of Soviet Energetics

NONLIVING SYSTEMS

Energetics

- Nonliving systems
- Scalar Interferometry
- Action-at-a-Distance
- Quantum Potential
- Vacuum Engines
- Spacetime Structuring
- Material, Field Effects
- Nuclei, Lattice Changes
- Hidden EM Variables
- SWZ Effects

LIVING SYSTEMS

Bioenergetics

- Living Systems (Bodies)
- Cells, cellular changes
- Master Cell Control (Popp)
- Spacetime Structuring
- Disease Induction, Remission
- Action-at-a-Distance
- Quantum Potentials
- Scalar Interferometry
- Hidden EM Variables
- SWZ Effects

Psychoenergetics

- Living Systems (Minds)
- Thoughts, Memories, Emotions
- Conscious/Unconscious Minds
- Spacetime Structuring
- Species, Biospheric Minds
- Action-at-a-Distance
- Quantum Potentials
- Scalar Interferometry
- Hidden EM Variables
- SWZ Effects

© 1996 T.E. BEARDEN

Selected clipart © by IMSI MasterClips™

Return to Slide Index

Next Slide

Previous Slide



Bunge on the Status of Classical and Quantum Physics

"... it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state... the best modern physicist is the one who acknowledges that neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling not only to better cover their own domains but also to join smoothly so as to produce a coherent picture of the various levels of physical reality."

*Mario Bunge, Foundations of Physics, Springer-Verlag, New York, NY, 1967, p. 176..

© 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



EINSTEIN ON REVIEWING FOUNDATIONS

"...the scientist makes use of a whole arsenal of concepts which he imbibed practically with his mother's milk; and seldom if ever is he aware of the eternally problematic character of his concepts. He uses this conceptual material, or, speaking more exactly, these conceptual tools of thought, as something obviously, immutably given; something having an objective value of truth which is hardly even, and in any case not seriously, to be doubted. ...in the interests of science it is necessary over and over again to engage in the critique of these fundamental concepts, in order that we may not unconsciously be ruled by them."

Albert Einstein, "Foreword," in Max Jammer, Concepts of Space: The History of the Theories of Space in Physics, Harvard University Press, Cambridge, Massachusetts, 1969, p. xi-xii.

JCS-11A

© 1993 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Fields and Potentials have been "defined" only in and on matter

E ≡ F/q
exists on
mass only

Note problem!
No "E" or "H"
in vacuum.

S = ExH

Source q is a
broken symmetry
in vacuum flux

S = ExH

Point
Coulomb

"pileup" in front
produces energy
density gradient
across the point
coulomb

So E ≡ -∇ϕ

ϕ ≡ joules continuously
in geometrical flow
distortion zone around
one point coulomb

[Coulombic energy collection density]

© 1997 T.E. BEARDEN

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



© T.E. BEARDEN 1998

Einstein's Spacetime

???

Maxwell's Material Ether

Material Ether Fluid Perturbations

Material Electric Fluid Disturbed

Φ, ϕ, E, B, H etc.

(Material entities)

Material Electric Fluid Disturbed

All Maxwell's EM entities are defined only in and of charged matter. All are material entities. There was no place devoid of mass, in the universe.

MAXWELL'S EQUATIONS ARE MATTER-TO-MATTER TRANSFORMS

[Return to Slide Index]
[Next Slide]
[Previous Slide]



NONMATERIAL SPACETIME

© T.E. BEARDEN 1998

Michelson-Morley experiments, 1880's

Material Fluid Perturbation Equations

MAXWELL

MAXWELL

Material Electric Fluid Disturbed

Material Electric Fluid Disturbed

Now we are not using a material ether. Trust us! Equations do not need changing.

ELECTRODYNAMICISTS

Electrodynamicists' Reaction to Removal of the Material Ether

[Return to Slide Index]

[Next Slide]

[Previous Slide]



THE MISSING INFOLDED ELECTRODYNAMICS

Maxwellian electrodynamics has nothing at all to say about EM entities in space or their form

Material Electric Fluid Disturbed

MATTER-TO-MATTER TRANSFORM

Material Electric Fluid Disturbed

MATTER-TO-SPACETIME TRANSFORMATION

INFOLDED INSIDE MAXWELLIAN EM AS HIDDEN EM VARIABLES

SPACETIME-TO-MATTER TRANSFORMATION

INTERNESTED SPACETIME CURVATURES

(VACUUM ENGINES)

INFOLDED GENERAL RELATIVITY

EINSTEIN'S SPACETIME

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Nonlinear Optics Distortion Correction Theorem

E₁
E₁
E₁
E₁
E₁
E₂
E₂
E₂
E₂
E₂
PORTION OF DISTORTING MEDIUM

E_1 = INCIDENT WAVE

E_2 = TIME-REVERSED WAVE

"If a scalar wave $E_1(r)$ propagates from left to right through an arbitrary but lossless dielectric medium, and if we generate in some region of space [say near z = 0] its phase conjugate replica $E_2(r)$, then E_2 will propagate backward from right to left through the dielectric medium, remaining everywhere the phase conjugate of E_1."

JCS-64

© 1994, 1995, 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Infolded longitudinal EM biwave composition of a scalar potential

GALLOPING VELOCITY
Scalar Potential ϕ
© T.E. BEARDEN 1997
...ETC.
✱ ✱ ✱ ...ETC.
V_{avg}
Wavepair #3
HARMONICS
V_{avg}
Wavepair #2
SUBHARMONICS
V_{avg}
Wavepair #1
...ETC.
✱ ✱ ✱ ...ETC.
DISTANCE

The Structure Is:

A harmonic set of longitudinal EM wavepairs. In each wavepair the two waves superpose spatially, but travel in opposite directions. The two are phase conjugates and time-reversed replicas of each other. Thus they comprise a coupled longitudinal wave and antiwave. The photons must be coupled into photon/antiphoton pairs (gravitons) by a strong application of the distortion correction theorem of nonlinear optics. Each wave in the biwave pair is a galloping wave. Each wavepair is a standing electrogravitational wave. In nonlinear optics, such a wavepair is a pump wave which pumps in the time domain.

Note: Think of the oscillations as velocity modulations.

Return to Slide Index

Next Slide

Previous Slide



The Zero-Vector Axiom Destroys "Topologies within Topologies"

- The axiom: There is a unique vector, $\bar{0}$, in V (the vector space) such that
  $\bar{V} + \bar{0} = \bar{0} + \bar{V}$
- Note that $\bar{V} + \bar{0}_i = \bar{0}_j + \bar{V}$; $\bar{0}_i = -\bar{0}_i = n\bar{0}_i$
  so $\bar{0}_i = \bar{0}_j = \bar{0}_k = \ldots + \bar{0}_n = \ldots$
- This makes all $\bar{0}_i$ equal by assumption, since there is *assumed* to be only a single type $\bar{0}$ without real components
- In fact, $\bar{0}$ is *not unique*. An *infinite number* of different zero-vector systems, with real components, satisfy the zero-vector axiom.

Return to Slide Index

Next Slide

Previous Slide



STONEY-WHITTAKER BIDIRECTIONAL LONGITUDINAL EM WAVE PAIR

(An electrogravitational wave)

Total time densities are additive, so "wave" appears "static" (standing) and gravitational

A wavelike variation in the local time density of the vacuum. The velocity of the EM wave oscillates. The amplitude of the EM wave does not change.

Hidden forward time EM time density flow

Hidden reversed-time time density flow

To any affected or exposed unipolar object, EM force operations cancel due to simultaneous time action and reaction

A coupled EM wave/antiwave pair infolds electromagnetic energy, converting it to gravitational energy. The wavepair becomes an electrogravitational standing wave.

(c) 1993, 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Undistorted Progressive Waves (UPWs)*

(waves with velocity v, where $0 \leq v \leq \infty$)

- Major equations of interest having UPW solutions are:
  - *Homogeneous wave equation*
  - *Maxwell equations*
  - *Dirac, Weyl, and Klein-Gordon equations*
- UPWs are translationally invariant, and do not spread, or they reconstruct their original form after a certain period.
- UPW solutions have infinite energy. Quasi-UPWs can have finite energy and can in principle be launched into space.
- Subluminal Maxwell solutions are called *EM particles*. Superluminal Maxwell solutions are called *X-waves*.
- *Experimental results indicate such waves will be produced within the next few years.*
- *Nimtz has translated Mozart's 40th symphony at v = 4.7c.*

*Rodrigues and Lu, *Found. Phys.* 27(3), 1997, p. 435-508.

© 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Velocity modulating a longitudinal EM wave oscillates rate of flow of time

$$V = \frac{L}{t}$$

Observer sees it this way

Constant transverse wave magnitude

Wave oscillates its velocity along its path, about a nominal value

Wave oscillates this way

Constant transverse magnitude

Wave oscillates magnitude of its transported t, about a nominal value

Note:

- Waves consist of photons
- Each photon consists of energy x time
- Each photon carries time as well as energy
- A wave is both a spatial energy dynamics and a temporal dynamics
- Wave complexes carry dynamic time structures as well as dynamic energy structures

© 1997 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



The Graviton Is a Coupled Photon/Antiphoton Pair
(Both photon and antiphoton are longitudinal)

ACTION

VACUUM ENGINE

REACTION

LONGITUDINAL PHOTON

LONGITUDINAL ANTIPHOTON

In physics, the primary units selected are arbitrary. Everything can be expressed, e.g., in terms of time alone. Thus so can photon spin.

IS THIS A SPIN 2 ENTITY?
It is, in the time domain.

© [illegible], [illegible] T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Mechanisms for Physical Change and the Flow of Time

SPATIAL
SPATIOTEMPORAL
PHOTON
SPATIAL
PHOTON
MASS
L^3
L^2T
MASSTIME
L^3T
L^2T
MASS
L^3

$(\Delta E)(\Delta t) + M \Rightarrow (M+\Delta M)\Delta t \Rightarrow M + (\Delta E)(\Delta t)$

Flow of macroscopic time (observable photon interactions)

SPATIAL AND SPATIOTEMPORAL
"MASS"
MASSTIME
L^3T
MASS
MASS
MASSTIME
L^3T
"MASS"

Flow of microscopic time (via virtual photon interactions)

The photon interaction generates an observed quantum change and a discretized jump in the rate of time flow. A particle observably changes by only a single Δ t at a time. The background flow of time in which the jump in rate occurs, is created by the continual absorption and emission of virtual photons.

© 1994 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Any EM Field or Wave Pattern Is Produced by interference of Two Scalar Potential Functions *(E.T. Whittaker, 1904)*

(Use of Hidden Information Content of the Field)

(Can Provide Action-at-a-Distance)

Note:
Whittaker's 1904 paper initiated the entire field of superpotential theory.

Interference Zone
(Potential gradients)
Normal EM Energy:
May be positive, or negative, or fixed

Hidden
Bidirectional
EM energy flow

Hidden
Bidirectional
EM energy flow

Scalar Potential
Beams

Whittaker/Ziolkowski
Transmitter Arrays
(8 to 20 harmonic wavepairs each)

© T.E. BEARDEN 1997

Return to Slide Index

Next Slide

Previous Slide



Mass is transparent to longitudinal EM waves, which move through the infolded interiors of internal waves, potentials, and fields in the mass

MASS MEDIUM
EM Wave
Ambient Vacuum Potential
Static EM Field
D.C. Potential
Ambient Vacuum Potential
© T.E. BEARDEN 1997

Mass is mostly ambient vacuum potential, modified by internal potentials, fields, and waves. Any wave or field is just two scalar potential functions, by Whittaker 1904.

Return to Slide Index

Next Slide

Previous Slide



Deep penetration of weak signals in a dense signal environment, by nonlinear retroreflection

Nonlinearity

Cross-Section of Body

Body Surface

Internal potentials and weak signal emissions occur from these internal operating EM components

Dense Signal Environment (May be very weak signals)

Enlargement of nonlinearity area

Pumped Retroreflection Phase Conjugate Mirror (PCM) Effect due to multi-photon interactions

PCM

PCR*

PCR

Amplified Partial Cancellation of Body's Internal Signals by addition of phase conjugate replicas

In a dense signals environment, probability of simultaneous signals interacting increases. This increases the probability of deep penetration by amplified phase conjugate reflections of weak internally generated signals from the interior, impinging upon the pumped (stressed) nonlinear surface areas where the simultaneous exterior interactions occur.

* Phase conjugate replica

© 1993, 1995 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide

THE IMMUNE SYSTEM



BONE MARROW
Lymphocytes
Special Defense
Intestinal tissue, liver, etc.
Thymus
Complement system
General Defense
Feeding cells
Monocytes
B-lymphocytes
suppressor cells
plasma cells
antibodies
T-lymphocytes
killer cells
helper cells
complement factors
granulocytes
macrophage
bacterium (foreign invader)
CANCR-18
©1993 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



Popp's master cellular control system

- Provides coherent, long-range interactions in biological systems
- Is an organized morphogenetic field at the basis of functional control

- Emission very sensitive to almost all external and internal influences
- Both spontaneous and delayed luminescence occur
- Photons stored in cell during the delay

- Leakage provides ultraweak, coherent biophoton emission from the system
- Fractional intensity pattern: few to some 100s of photons/cm^2/sec
- Optimum signal-to-noise ratio

- A single delayed biophoton may be able to trigger 10^{10} reactions in a cell before its release
- Spectrum almost continuous within optical range from 200-800 nm.

- Biophoton emission shows biological system always out of equilibrium
- Emission has holistic characteristics
- Correlations to most, if not all, of the biological functions of the organism

- DNA, all other processes are sources
- Single main process of whole system, different processes strongly coupled
- Information function and sync of biological clocks (oscillators)

(c) 1997 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



CANCER: CHARACTERISTICS

- NOT ONE DISEASE BUT A WHOLE RANGE
- STARTS IN ORDINARY (AEROBIC) CELL
- CELL SHAKES OFF BODY'S DICTATORIAL CONTROL*
- STARTS UNCONTROLLED DIVISION
- BECOMES A LUMP
- CAN SEND FORTH CANCER CELLS
  - THROUGH BLOOD
  - THROUGH LYMPH
- THESE FORM METASTASES (SECONDARY TUMORS)
- OFTEN BECOME ANAEROBIC (NON-OXYGEN USING)
- ENIGMA IS FAILURE OF IMMUNE SYSTEM TO ATTACK SOME TUMOR CELLS
  - SUPPRESSOR CELLS MAY CURB IMMUNE SYSTEM
  - TUMOR MAY LACK ANTIGENS NORMALLY IDENTIFIED BY THE IMMUNE SYSTEM

*R&R system forces cell back toward anaerobe

CANCR-26

© 1993 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



THE EVOLUTIONARY PATH OF MULTICELLULAR ORGANISMS

ESSENTIALLY ANAEROBIC ATMOSPHERE

CHANGE OF ATMOSPHERE TO AEROBIC (INCLUDES OXYGEN)

BIOGENESIS

SINGLE CELL ANAEROBIC

OBLIGATORY ANAEROBES SINGLE CELL SHIELDED FROM OXYGEN

FACULTATIVE ANAEROBES (SINGLE CELL BOTH AEROBIC AND ANAEROBIC)

EVOLVE TO

SINGLE CELL AEROBIC*

EVOLVE TO

MULTICELL AEROBIC* (INCLUDES MAN)

CENTRAL CONTROL

SINGLE CELL COMPONENTS

- IMMUNE SYSTEM
- RED CELLS
- WHITE CELLS
- KILLER CELLS
- ETC.

MULTICELL COMPONENTS

- TISSUES
- MUSCLES
- BONES
- ORGANS
- SKIN
- STRUCTURES

* NOTE: LIMITED ANAEROBIC RESPIRATION STILL TAKES PLACE IN HIGHER AEROBIC LIFE FORMS, INCLUDING MAN.

EVOLUTIONARY TIME

CANCR-01

c 1993 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



EFFECT OF FLUID CONTAMINATION ON HEMOGLOBIN'S OXYGEN TRANSPORT

RED BLOOD CELLS

AIR

Severe pollution

Severely reduced
oxygen transport

(Such as
cigarette smoke)

RED BLOOD CELLS

LUNG
SACS

BODY

ATMOSPHERE

CANCR-09

© 1993 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



FIRST STEP IN SELF-PROMOTION OF CANCER DUE TO HYPOXIA

* NOTE: LIMITED ANAEROBIC RESPIRATION STILL TAKES PLACE IN HIGHER AEROBIC LIFE FORMS, INCLUDING MAN.

SINGLE CELL ANAEROBIC

SINGLE CELL AEROBIC*

MULTICELL AEROBIC* (INCLUDES MAN)

CENTRAL CONTROL

OXYGEN-RICH

TIME-FORWARD PATH AS IT DEVELOPED

TIME-REVERSED PATH FOR SUSTAINED OXYGEN DEFICIENCY

SINGLE CELL AEROBIC*

FIRST STEP IN OXYGEN-DEFICIENCY DEDIFFERENTIATION

CANCR-08

© 1993 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



BECKER'S CELLULAR GROWTH CONTROL

- Two major links uncovered between :
  - The DC system and nervous system
  - The DC system and all body cells
- Bioelectric potentials of primary importance
- Physiology presently considers controls limited to:
  - Neural action potential
  - Various hormone chemical agents
  - Chemical agents associated with DNA/RNA system
- Complete Operational Biological Control System:
  - Controls growth, healing, biological cycles, etc.
  - Operates in ANALOG mode; various levels of DC
  - Interlocks physically with nervous system (and may be its precursor)
  - Other chemical agents
  - Tissue growth and healing NOT INCLUDED
- Medical community now more concerned with diseases resulting from:
  - Inadequate/abnormal growth
  - Inadequate healing

Return to Slide Index

Next Slide

Previous Slide



Becker's dc treatment of bone fractures

Application of tiny DC currents to heal difficult bone fractures. Only picoamperes are utilized. Pulsed DC current or pulsed magnetic fields may also be utilized.

(+)
ELECTRODE
(-)
ELECTRODE
DC POWER SOURCE
BONE
BONE
FRACTURE SITE

BECKER'S
BONE FRACTURE SETUP
(DIAGRAMMATIC)

RED BLOOD CELL DEDIFFERENTIATES

Shucks hemoglobin coat
Grows nucleus

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes cartilage

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes bone
Deposits in fracture site, healing the fracture

Proves that cells can be time-reversed (phase conjugated) (dedifferentiated) or time-forwarded (redifferentiated) by application of very weak electromagnetic signals, when those signals contain longitudinal bidirectional EM "pump wave" wavepairs, which cause the cell and its parts to create precise vacuum antiengines.

(c) 1993, 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide

*Becker's theoretical DC control system involved with response to injury**



INJURY

INPUT STIMULATION DC SYSTEM (PAIN)

CENTRAL DC SYSTEM

GROWTH DIFFERENTIATION

LOCAL CELL INJURY FREE RADICALS

OUTPUT DC SYSTEM

MITOSIS DEDIFFERENTIATION

STIMULATION OF REPAIR CELLS

TOTAL CURRENT OF INJURY DC SYSTEM

*Robert O. Becker, "The significance of bioelectrical potentials," Bioelectrochemistry and Bioenergetics, Vol. 1, 1974, p. 191.

Return to Slide Index

Next Slide

Previous Slide



Becker's theoretical control system governing regeneration*

Trauma Producing Tissue Loss
Local cellular effect
Local nerve effect
CNS effect
Alterations in hormone pattern (prolactin)
Alterations in local DC field pattern
Local electrical effects
Local and systemic pools of target cells
Dedifferentiation into primitive mesenchymal cells
Phase I
Blastema formation
growth
Phase II
Redifferentiation into required cell types
Restoration of body part or tissue

*Becker & Spadaro, "Electrical stimulation of partial limb regeneration in mammals," Bull. N. Y. Acad. Med., 48(4), May 1972, p. 629.

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



Link Between Standing DC Potentials and the Nervous System

- Standing DC potentials on intact surfaces of all living animals demonstrate a complex field pattern spatially related to the anatomical arrangement of the nervous system
  - Can be measured directly on the peripheral nerves
  - Polarity difference related to whether nerve is or is not a sensor
  - Steady (weak) current flow exists
  - Demonstrates solid state/semiconductor phenomena
  - Accurately reflects (amplitude and polarity) the general level of neural activity
    - Sleep versus wakefulness
    - Anesthesia versus conscious
    - Other parameters
- DC levels determine the level of neural activity
- Action potential system exists upon a substratum of DC potentials which pre-existed it
- DC potentials substrata had and have control functions over basic properties of the living organism

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Becker's Findings on Cellular Injury and Regeneration*

- Cellular processes are regulated by a precise control system
- Attempted to apply engineering control-system theory
- Cells and tissues have solid-state electrochemical features which provide control signals in the control system
  - Growth process
  - Electron transfer
  - Semiconduction
  - Self-organizing *(NOTE: Implies hidden variables and nonlocal causality)*
- Complex electrical events at the injury site initiate cellular aspects such as dedifferentiation and mitotic activity
- Regeneration is a 2-step process, each with different controls
  - Electrical triggers with threshold values results in appearance of blastema
  - Complex data transmission to blastema establishes it as a self-organizing system capable of growth and redifferentiation
  - Mammals lack ability to produce blastemas except for bone, but partial regeneration growth has been shown in response to electrical stimuli
- Growth related to electrical more than electrochemical aspects
- Hematopoietic marrow as source of cells for the blastema
  - Monocytes can take place in regenerative processes in limbs
  - Lymphocytes can dedifferentiate under certain circumstances
  - Marrow elements can be induced into osteogenesis

*R.O. Becker & J.A. Spadaro, "Electrical Stimulation of Partial Limb Regeneration in Mammals," Bull. N. Y. Acad. Med., 48(4), may 1972, p. 627-641.

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide

Corrections For the Present EM Bioeffects Model



17.
DEVELOP NEW TYPES OF INSTRUMENTS

18.
CORRECT EM THEORY MODEL, INSTRUMENTATION AND RECORDING, AND IMCS

A

START

PRESENT INADEQUATE EM BIOEFFECTS MODEL

OVERALL STIMULUS/RESPONSE MODEL

2.
EXPERIMENT OR GROUP OF EXPERIMENTS

1.
EM STIMULUS/ RESPONSE MODEL

6.
EM THEORY TO BE APPLIED

8.
EM THEORY CORRECT

STOP

3.
INSTRUMENTATION AND RECORDING

4.
INTERPRETATIVE MODEL AND COMPARATIVE STANDARD

5.
INTERPRETED RESULTS

7.
ARE RESULTS CONSISTENT?

YES

NO

9.
EM THEORY INCORRECT

IMCS/EM ASSUMPTIONS
1. PRESENT EM MODEL CORRECT AND COMPLETE
2. DOSAGE/RESPONSE SYNONYMOUS WITH STIMULUS/RESPONSE

10.
FIND ERRORS IN EM THEORY POSTULATES

16.
CORRECT/EXTEND EM AND SHOW UNIFIED FIELD AND MIND/VOLITION

14.
ADD WHITTAKER EM STRUCTURE OF POTENTIALS THEORY

13.
FORCEFIELDS NOT PRIMARY. POTENTIALS ARE, HAVE HIDDEN EM WAVE STRUCTURE.

11.
CHARGE DISCRETE, NOT QUANTIZED. VIRTUAL FLUX CAN BE STRUCTURED, FOR VACUUM ENGINES.

15.
ADD TO GENERAL RELATIVITY AND QUANTUM MECHANICS

19.
SEPARATE CHARGE Q INTO ITS COUPLED COMPONENTS

12.
RETAIN ZERO VECTOR RESULTANT SUMMATIONS OF EM FORCE VECTOR COMPONENTS AS VACUUM ENGINES

JCS-44

© 1991, 1993, 1995 T.E. BEARDEN

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



R&R SYSTEM

Regeneration Example

PRIORE AMPLIFIED PUMPING

ADD PUMPS

B

CELL AS A PHASE CONJUGATE MIRROR

RESIDENT VACUUM ENGINE

ANTIENGINE PRESENT?

N

Y

APPLY ANTIENGINE

START

A

CYCLE

CELL AND INTERIOR SENSORS

LOCAL VICINITY SENSORS

NONLOCAL ALL-BODY SENSORS

DELTA CATALOGS

CELLS AND INTERIORS

SELECT LOCAL

SELECT NONLOCAL

AEROBE

ANAEROBE

DELTA?

Y

N

AEROBE

ANAEROBE

SWITCH TO AEROBE CONTROL SYSTEM

CROSS THRESHOLD BACK TO AEROBE?

SWITCH COMPARATIVE CATALOG

SUM FOR ENTIRE BODY

SWITCH ON CENTRAL, OFF DECENTRAL GROWTH CONTROL; RESET IMMUNE SYSTEM

SWITCH TO ANAEROBE CATALOG

END OF AEROBE CATALOG?

SWITCH OFF CENTRAL GROWTH CONTROL

SWITCH ON DECENTRAL GROWTH CONTROL

CONDITION IMMUNE SYSTEM TO ACCEPT

© T.E. BEARDEN 1998

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



Kaznacheyev's Cytopathogenic Mirror Effect

Disease vacuum engines transported by photons and waves

GRAVITON LATTICE TEMPLATES
SICKEN OR KILL
ENVIRONMENTAL SHIELDING
CELL CULTURE SAMPLE #1
QUARTZ CONTAINER
CELL CULTURE SAMPLE #2
QUARTZ CONTAINER
THIN WINDOW
GLASS: No Effect
QUARTZ: Delayed Effect
© T.E. BEARDEN 1977, 1987
Divided bottle set-up

Note: Minimum lattice is one harmonic interval: IR to UV is such a minimum G-lattice.

Distant induction of cellular death and diseases, by special EM means. Coupled photon-antiphoton pairs (gravitons) in a structured harmonic lattice ordering constitute the disease or disorder template.

Return to Slide Index

Next Slide

Previous Slide



MICROWAVE RADIATION OF U.S. EMBASSY IN MOSCOW

BACKGROUND

Former U.S. Embassy in Moscow.

- Began in latter 1950s
- Discovered on VP Nixon's trip
- Initially thought to be *nuclear* radiation (Discovered w/Geiger counter?)
- High level target -- U.S. Ambassador
- Guarantees personal attention of:
  - U.S. Ambassador to USSR
  - U.S. President
  - NSA, CIA, DIA, NSC, etc.
  - Top consulting scientists
  - Leading U.S. scientific institutions
- Two U.S. Ambassadors died, another sickened
- Anomalous health changes in personnel, only in zero-field (zero pot'l gradient) areas!
- Four U.S. Presidents requested Soviets cease
  - Cut from 18 watts/sq cm to 2
  - Then again increased
- No one could understand what was going on
- Aluminum screens were placed over windows
- Moscow was declared a hazardous duty zone

Selected clipart © by Lotus SmartPics™

© 1995, 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Self-Targeting in Inner EM Channel Can Produce a Quantum Potential

Once QP is established, energy transmission is direct and instantaneous. Energy input to one single participant will simultaneously appear in all other participants, the amount depending on their fractions of participation with the input station.

NARROWING OF INTERACTING POTENTIALS INTO LASER-LIKE BEAMS, BETWEEN TWO PUMPED SOURCES. NOW ONLY LONGITUDINAL WAVES CONNECT THE LINKED OBJECTS.

SELF-TARGETING EFFECT AMONG ALL PAIRS OF INTERACTING PUMPED SOURCES

© [illegible] T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Quantum potential and hidden variable theory

a. Quantum Potential Characteristics

© 1988, 1995, 1997 T.E. BEARDEN

- No point source
- Not radiated
- Quantum potential between two particles
  - Interaction does not vanish as spatial separation becomes very large
  - Instantaneous connection, so multiply-connected space

b. Hidden Variable Theory and the Quantum Potential

- $$V_{quantum} = \frac{\hbar}{2m}\frac{\nabla^2\sqrt{\rho}}{\sqrt{\rho}}$$
- "A quantum particle moves as if it were subject, in addition to its external potentials, to a potential which is a function of its own probability distribution."
- Bohm's H.V.T. assumes:
  - Particle and wave function real and separate
  - Wave function obeys Shroedinger's equation
  - Particle obeys classical mechanics
  - Particle couples to wave function through a quantum potential

Return to Slide Index

Next Slide

Previous Slide



Participants in a quantum potential share a common multiply-connected spacetime (MCST)

- Separated points are superposed in MCST
- Intervening distance in MCST is zero
- Connection is instant and bidirectional
- Propagation through ST does not apply
- Energy or vacuum engine input to one station instantly appears at each and every other station, undiminished in magnitude
- Ultimate net-centric warfare effect

Note: Once QP established, separation distance in 3-space is of no consequence

Note: Vulnerability. Any other station may insert energy or vacuum engines into the same quantum potential. Phase conjugating the hostile engine can negate its effect everywhere

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Gulf War Syndrome And Typical Comparative Disease Curves

Note: There is cumulative genetic damage to germ cells also.

- EXPOSED WITH MOST CUMULATIVE DAMAGE
- EXPOSED WITH MULTIPLE AGENT INFECTIONS AND RECEIVING MULTITREATMENT
- EXPOSED WITH LESS CUMULATIVE DAMAGE
- NON-GULF WAR: TYPICAL NORMAL DISEASE WHICH KILLS PATIENT

JCS-100

© 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Force Fields and Symmetry

- Force fields are nature's way of imposing local gauge symmetries on the world
- E.g., electromagnetic field is a manifestation of the simplest known gauge symmetry consistent with the principles of special relativity
- For the EM case, the gauge transformations correspond to changes in 'voltage' from place to place

© T. E. Bearden 1995, 1996

[Return to Slide Index]

[Next Slide]

[Previous Slide]



Aspects of Strong Local Asymmetry

- If local asymmetry is strong, conservation laws may be appreciably violated
  - Energy
  - Charge
  - Spin
  - Momentum
  - Angular momentum

© T. E. Bearden 1995, 1996

- Properties of an object may differ appreciably for
  - Different observers
  - Different detecting means
  - One time to another
  - One position to another
- STRUCTURING THE INFOLDED EM INSIDE POTENTIALS, FIELDS, AND WAVES
  - Strongly breaks local symmetry
  - Provides spacetime engines giving the above effects

Return to Slide Index

Next Slide

Previous Slide



Other Aspects of Strong Local Asymmetry

© T. E. Bearden 1995, 1996

- Local spacetime is curved
- Lorentz invariance of vacuum is violated
- May be a local "sink" or "source"
- Gravitational/inertial effects from EM
- Translation between virtual and observable
- Electrogravitational solitons
- Action at a distance
- Transmutation effects may exist
- Scalar/pseudoscalar field translation
- COMMENT: Thus the use of infolded longitudinal EM fields and waves to strongly break local symmetry allows internested clustering of spacetime curvatures. These spacetime structures are *vacuum engines*, or *spacetime engines*.

Return to Slide Index

Next Slide

Previous Slide



Small Entities Emit Powerful S-Flows

$$V = 10^{-3}\,volts$$

Surface layer of fluid atoms

Cellular membrane surface

$$d = 10^{-9}\,meter$$

$$E = 10^{6}\ \text{volts / meter}$$

$$S \approx f(E^{2}) = f(10^{12})$$

© 1997 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



What is the "magnitude" of a potential?

- What is taught is the *"interaction cross section,"* i.e., the joules collected from the associated S-flow by one point coulomb of intercepting/collecting charge.

$$W = Vq = \phi q \qquad \text{(joules)} \qquad [1]$$

$$\phi = W/q \qquad \text{(joules/coul)} \qquad [2]$$

$$\text{Let } \phi < 1 \text{ and fixed; } q \Rightarrow n \text{ where } n = \infty$$

$$W \Rightarrow k, \text{ where } k = \infty \qquad [3]$$

- *From any "finite" potential, no matter how small, an unlimited amount of energy can be collected, by increasing the collection (number of coulombs) (interaction cross section).*
- Actual magnitude of the potential ϕ must be very, very large, since we can treat it as infinite or unlimited, via $W = \phi q$.
- *Else Equation [1] could not be linear.*

© T.E. BEARDEN 1997

Return to Slide Index

Next Slide

Previous Slide



Table A1. THE VACUUM ENERGETICALLY INTERACTS WITH EVERY PARTICLE, CONTINUALLY.

- The vacuum is:
  - Ground (zero) state of the electromagnetic (photon) field.
  - Ground (zero) state of mass field.
  - Empty of *observable* particles or photons.
  - Filled with *non-observable* (virtual) particles and photons.
  - Violently fluctuating microscopically and electromagnetically.
  - Constantly interacting with all particles, including partially shielding their bare charges.
- Lamb Shift -- vacuum's alteration of the energy level of an electron in the hydrogen atom.
  - -- Difference in energy (frequency units) is 1057.862 MHz.
  - -- Lamb was awarded a Nobel Prize for showing this.
  - -- Energy *density* exceeds that of the sun's surface!
- Casimir Effect -- vacuum creates an attraction between two conducting surfaces in close proximity.
  - -- experimentally proven, well-known.

© [illegible] T.E. BEARDEN

- Cole and Puthoff proved that there is no thermodynamic reason why energy cannot be extracted from the vacuum as heat and power, and utilized.
- The common dipole is a broken symmetry in the virtual photon flux of vacuum. It extracts virtual energy, integrates it, and re-emits it as Poynting energy density flow S = ExH (which observably interacts with charged particles and magnetic poles).

Return to Slide Index

Next Slide

Previous Slide



Extended Superpotential Theory

(Adding Vacuum Engines)

- Any EM field or wave is created by (comprised of) two potentials which interfere with each other in a given area
  - *May be either scalar or vector potentials*
  - *May interfere locally or at a distance*
  - *Process is distance independent*
- Any scalar potential is comprised of a harmonic series of bidirectional longitudinal EM wavepairs (Whittaker 1903).
- Ziolkowski circa 1985 added the interior product set to Whittaker's sum set. Thus he added modulations.
- By assembling a deliberate "sum and product" set of biwaves, a scalar potential can be created having an internal deterministic structure.
  - *This structures local vacuum potential/spacetime curvatures, in specific forms (templates)*
  - *Now have added vacuum engines*
  - *Have infolded general relativity inside electrodynamics*

© 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Vacuum Engine: Jillions of Working ST Demons

Internested patterns of spacetime curvature

Structured Einsteinian spacetime

Demons are EM hidden variables organized into dynamic structures at all levels

Demons work at all levels

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Active Spacetime and a Specific Vacuum Engine

(A General Relativistic Concept and Analogy)

ACTIVE SPACETIME

DYNAMIC MASS

STRUCTURING OF ACTIVE SPACETIME CURVATURES

DETAILS OF STRUCTURING OF ACTIVE SPACETIME CURVATURES (TEMPLATE)

mass structures spacetime

spacetime structures act on mass at all levels

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Extension of Wheeler's general relativity principle:

- Mass (trapped energy) and its structuring curves and structures spacetime complexes (engines).
- Curved and structured spacetime engines produce forces on mass and its components, telling them how to move and structure.
- Since very strong EM force is used as agent of curvature, very powerful general relativistic effects can be obtained by arranging the LWs in the input EM potentials, fields, and waves.
- General relativity becomes directly engineerable in devices of unparalleled capability.

ST curvatures propagate

mass

mass-to-spacetime transformation

spacetime-to-mass transformation

mass

altered spacetime

altered spacetime

Complex of ST curvatures (vacuum engine, or spacetime engine)

Spacetime disturbance (engine) propagates

© T.E. BEARDEN 1998

Electrodynamics has a hidden but ignored electro-general-relativity infolded inside (comprising) its so-called potentials, fields, and waves (in space in the absence of mass). What are presently defined as potentials, fields, and waves rigorously exist only in, on, and of charged mass, as pointed out by Aharonov and Bohm in 1959. All of this is just longitudinal EM waves and their interactions.

Return to Slide Index

Next Slide

Previous Slide



SIGNAL VERSUS VACUUM ENGINE

SIGNAL (INFO)

- INFORMATION RECEIVED
- ANY OVERT PHYSICAL ACTION MUST BE TAKEN BY RECEIVER

A. *Receiver must do the action itself; vacuum energy exchange is unaltered. Energy or fuel for doing the action must be added to receiver externally.*

(c) 1994, 1996 , 1997 T.E. BEARDEN

Selected clipart© by Lotus SmartPics™

VACUUM ACTIVATED

ENGINE (STRUCTURE) TEMPLATE (FORM)

- "INFORMATION" ITSELF ACTS
- VACUUM FLUX GRADIENTS CHANGE ALL PARTS AND CHARACTERISTICS OF RECEIVER, INSIDE AND OUT

B. *Receiver is acted upon; altered vacuum energy exchange does the specific action. No energy or fuel for doing the action need be added to receiver externally.*

Return to Slide Index

Next Slide

Previous Slide



Electronuclear Interactions by Vacuum Engines

- An EM potential is gravitational due to its trapped energy.
- A local EM potential is a local curvature of spacetime.
- *Structured* potentials are structured *(nested)* local spacetime curvatures; hidden variable theory applies.
- Structured potentials thus are *vacuum engines*.
- Gradient-free potential penetrates the atom, into nucleus.
- *With steady application, a structured gradient-free potential can be used to engineer the atomic nucleus at will.*
- Normal cold fusion systems structure a small fraction of their potentials, by chance geometries, boundaries, etc.
- This produces some new nuclides, but haphazardly.
- *The process can be developed and controlled. The nucleus can be deterministically engineered at will.*

© 1997 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Vacuum Engineering

Using Inner EM Energy and Structuring to Engineer Physical Reality

Vacuum Potential (Violent Flux)

Inner EM

(Ordering of Virtual Particle Flux of Vacuum)

Forms Vacuum Engines

Forms Structured Outer EM

(Potential gradients etc.)

$-\nabla \times A$, $-\nabla \phi$, etc.

Forms Force System on/of Mass

$F \equiv dP/dt$

$= d(mv)/dt$

$\equiv (-\nabla \phi)q$, etc

Assemble Bi-Wavepairs

Makes Scalar Potentials with Ordered Subtle Energy Internal Structure

Scalar Potential Interferometry

Two or More Scalar Potentials with Hidden Multiwave Structures (Interference of ordered Subtle Energy Structures)

Observable Mechanics

(Statics and Dynamics)

START

START

YAO-01

© 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Impact of Vacuum Engineering

- "If they [quantum fluctuations of vacuum] can be [tapped], the impact upon our civilization will be incalculable. Oil, coal, nuclear, hydropower, would become obsolete -- and so would many of our worries about environmental pollution."
- "Don't sell your oil shares yet -- but don't be surprised if the world again witnesses the four stages of response to any new and revolutionary development:
  - 1. It's crazy!
  - 2. It may be possible -- so what?
  - 3. I said it was a good idea all along.
  - 4. I thought of it first."

© 1996 T.E. BEARDEN

Arthur C. Clarke
"Space Drive: A Fantasy That Could Become Reality"
Nov./Dec. 1994

- *Comment:*
  - *Every dipole's broken symmetry in its energetic exchange with the vacuum already freely extracts vacuum energy.*
  - *In power sources, the dipole gates the extracted energy out as S = EXH, which flows almost entirely outside the conductors.*
  - The circuit interacts with, and uses, only about 10^{-13} of S. The electrodynamicists calculate only this small S-component.

Return to Slide Index

Next Slide

Previous Slide



A DRAMATIC EXTENSION TO NONLINEAR OPTICAL PUMPING

© T.E. BEARDEN 1997

transverse pump wave
A_2
transverse signal wave (input)
A_4
PPCM
A_3
NONLINEAR MEDIUM
amplified phase conjugate replica transverse wave (time-reversed)
transverse pump wave
A_1
+ t
PREVIOUS VACUUM ENGINE
PREVIOUS MASS STATE
TIME AXIS
A_2
VACUUM ENGINE
AMPLIFIED VACUUM ANTIENGINE
MASS
A_1

a. Pumping with transverse EM waves produces a time-reversed *wave*.

b. Pumping with longitudinal EM waves A_1 and A_2 time-reverses *the mass itself*.

Return to Slide Index

Next Slide

Previous Slide



Time Conservation and Some Properties

(Energy and time are canonical)

- Time can neither be created nor destroyed
  - *Its form can be changed, and it can be positive or negative*
  - *Time can be collected or dissipated, converged or diverged*
  - *Time can oscillate and move in waves*
  - *Longitudinal (infolded) EM waves oscillate time*
- Time is always in motion, and that motion is variable
  - *Collected/collecting time is a continuing stationary change in an ongoing time flow*
  - *Time/collecting time can be internested and internally structured*

© 1996 T.E. BEARDEN

- Time has gravitational aspects
  - *Negative (trapped) time is antigravitational*
  - *Emitting negative time is gravitational, to the emitter*
- Nonlinear optical pumping can use longitudinal EM waves
  - *Pumping a nonlinear mass by longitudinal (infolded) EM waves pumps it in its masstime form, in the time domain*
  - *This creates an amplified vacuum antiengine for the mass, and time-reverses the mass back to a previous state*

Return to Slide Index

Next Slide

Previous Slide



A DRAMATIC EXTENSION TO NONLINEAR OPTICAL PUMPING

© T.E. BEARDEN 1997

VACUUM ENGINE A'
VACUUM ENGINE (A' +B')
VACUUM ENGINE B'
TIME AXIS A
TIME AXIS (A+B)
TIME AXIS B
A_2
MASS
AMPLIFIED VACUUM ANTIENGINE [A' + B']
VACUUM ENGINE B
VACUUM ENGINE A
A_1
A + B

After adding a second vacuum engine, pumping with longitudinal EM waves (pumping in the time domain) deviates the time-reversed trajectory. The mass and its internal structure are translated into a new form with a new structure, which it need never have had.

Return to Slide Index

Next Slide

Previous Slide



Key Points in the New Technology

- There is a vast new kind of electrodynamics *hidden inside* all EM potentials, fields, and waves
  - Longitudinal EM waves and complexes
  - Oscillations in time domain
- These complexes are an *infolded general relativity*
  - Clustered formations of *spacetime curvatures*
  - *Very powerful*, since the EM force is used as the agent of curvature
- In general relativity, similar precise complexes permeate and *act on any mass at all internal levels*
- With this approach, one *can now manipulate matter* -- living or inert -- *in any manner desired*, depending only on the level of development of the technology
- Priore unwittingly used this to *cure dread diseases*
- This is a *revolution in all of science*
- *We have uncovered the major mechanisms* to utilize

© T.E. BEARDEN 1996

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc.

28 Mar. 1998

© 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Portable Priore-Type Treatment System

Equipment Case
Computer Control Unit
Infolding Function Generator
Antenna Pad

Return to Slide Index

Next Slide

Previous Slide

Portable System Block Diagram


Power Supply
Computer Control Unit
Frequency Generators
Infolding Function Generator
Field Sensor Unit
Magnetic Pulse Generator
Plasma Mixing Unit
Antenna Pad
Antenna Pad

[Return to Slide Index]
[Next Slide]
[Previous Slide]



PORTABLE PRIORE TECHNOLOGY UNIT

- FACT: DISEASE-SPECIFIC VACUUM ENGINE PRESENT FOR ANY CELLULAR DISEASE, BY WHEELER'S PRINCIPLE
  - *DISEASE CAN BE REVERSED BY CREATING AMPLIFIED VACUUM ANTI-ENGINE (BEARDEN'S PRINCIPLE)*
  - *ANTI-ENGINE IS CREATED BY PUMPING THE NONLINEAR CELLS IN THE "INNER EM" DOMAIN, TIME-REVERSING THEM*
- PRIORE UTILIZED A PLASMA TO PHASE CONJUGATE AND "INFOLD" MULTIPLE BIDIRECTIONAL LONGITUDINAL EM PUMP WAVES
  - *17 FREQUENCIES MIXED IN A ROTATING PLASMA*
  - *PHASE CONJUGATES ADDED BY THE PLASMA*
  - *INFOLDED MIX INTO STRONG PULSED DC MAGNETIC FIELD, WHICH CARRIED IT INTO ATOMIC NUCLEI*
  - *PUMPED ALL NONLINEAR CELLULAR COMPONENTS TO PRODUCE AMPLIFIED, SPECIFIC VACUUM ANTI-ENGINE*
- NEGATED THE LONG-TERM CUMULATIVE CELLULAR DEDIFFERENTIATION ORDER GENERATED BY LONG-TERM HYPOXIA. TUMOR CELLS REVERTED TO NORMAL CELLS.
- SCRUBBED OUT THE CUMULATED PRECANCEROUS STATE
- RESTORED THE IMMUNE SYSTEM TO HIGH FUNCTIONING
- NO EXCESSIVE TRAUMA TO TREATED ANIMAL

CANCR-89

© 1994, 1996, 1999 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



SAVING THE STRICKEN CIVILIANS

SURVIVORS OF N CASUALTIES

(N = 1-40 MILLION)

EXPRESSED IN FRACTION SURVIVING
- 🟩 With conventional treatment
- 🟨 With 1st generation P-treatment
- 🟧 With 2nd generation P-treatment
- 🟥 With 3rd generation P-treatment

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc. 28 Mar. 1998

© 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Summary and Conclusions

- A new therapeutic paradigm of great scope and effectiveness has been developed
  - *Will provide effective, quick treatment of mass casualties*
  - *Will provide cures for unknown agents*
  - *No pathogen strains are resistant to this process*
- Results have been proven experimentally
  - *Documented in French scientific literature*
  - *Rigorous scientific protocols, eminent scientists*
  - *Technical mechanism deciphered*
- Will treat and cure many diseases
  - *Aids, atheriosclerosis, cancer and leukemia*
  - *Sleeping sickness*
- Portable units can be developed quickly
  - *18-month crash development program required*
  - *high level authority and overwatch essential*
- *Will solve the BW mass casualty treatment problem, both civilian and military*

© 1993 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- *Threat and Current Status*
- *Historical Solution: Priore Treatment Therapy*
- *Extended Physics and Background*
- *Modern WMD Solution: Portable Treatment Systems*
- *Conclusions: Technology Practical, Proven*
- *Recommendation: Crash Development Program*

CTEC, Inc.

28 Mar. 1998

(c) 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Recommend implementing:

- Crash development program
  - Suitcase-sized portable unit
  - 18-month Manhattan-type project
  - Simultaneous theoretical modeling, animal testing w/breadboard models
  - SecDef and Congressional overwatch
  - Presidential Decision Directive
- Parallel logistics support program
  - Plan high speed production lines
  - Mass distribution, storage, maintenance
  - User, maintenance training
  - Plan C4 and usage at all levels
  - Integrate firemen, police, National Guard, FEMA, medical facilities, etc.

Return to Slide Index

Next Slide

Previous Slide



Final Thoughts:

- The current internal BW threat can and will kill more Americans than all our previous wars combined
- The Priore technology is the only solution in sight that can save most of those casualties

Return to Slide Index

Previous Slide

CTEC, Inc.
2311 Big Cove Road
Huntsville, AL 35801
(256) 533-3682 Ph/

CTEC, Inc.

June 24, 1998

Dr. Jane F. Kinsel, Director
Office of Policy Analysis
Department of Health & Human Services
Bathesda, MD 20892

Dear Dr. Kinsel:

Your letter of June 8 is appreciated. However, the entire action package had already gone to the Assistant SecDef and also to Major General Neary in the USAF.

The proof of a revolution in medical treatment was in the package. The basis for it is already demonstrated experimentally in the scientific literature, both in the U.S. and in France. We are speaking of something already proven, but missed by the entire U.S. medical community. Strong words, but true. Let me be specific.

Any cell in the body can be time-reversed (physics term) or dedifferentiated (biology term) back to an earlier state, by pumping (i.e., "squeezing" in simple terms) that cell with longitudinal EM waves as pump waves. There are considerable papers in the French scientific literature showing the experimental results.

Apply that to cancer. We are stating bluntly that all cancerous cells in the body can be "depromoted" back to normal cells easily. Further, the damage previously done to them (such as by sustained hypoxia due to contaminants reducing the oxygen-carrying ability normally given to it by some 60-to-80 surrounding water molecules per red cell and the consequent H-bonding interactions) will also be reversed. The cells can all be returned to healthy, normal cells again, without "killing" or "burning" or "cutting" anything.

With some development of the technology, you can quickly and easily cure every cancer patient in every hospital in the United States.

Now apply it to AIDS. Since you can time-reverse every cell in the body, you can time-reverse the HIV-infected cells – genetics and all – right back to normal cells with normal genetics. Those cells not infected and healthy, will just get a "little younger" again.

So with that small development, you can quickly and easily cure every AIDS patient in every hospital in the United States.

I would have thought that NIH would certainly be interested in such a revolutionary therapy which has already been demonstrated in laboratory experiments. World-renowned French scientists – such as the eminent parasitologist Pautrizel and research PhDs assigned directly by Robert Courrier, head of the Biology Section of the French Academy of Sciences, worked with Prioré in performing those startling experiments that proved what we are saying.

The method was rigorously shown to cure infectious diseases (such as trypanosomiasis), atherosclerosis (which now afflicts millions of Americans), and terminal tumors. It was shown to reverse suppressed immune systems back to normal vigorous functioning.

Please permit me to disagree with you that the examination of such is not the mission of the NIH. To the contrary, it is precisely the NIH which should have some of its very best scientists looking into this.

The action package to DoD was to propose a crash program to develop this methodology in the form of a small, portable unit for treatment of mass casualties resulting from a terrorist BW attack on our cities (now expected in the next few weeks, as you must be aware). The leading Arab terrorist of the world has already promised just this.

We are speaking of several million Americans who are going to die. They are going to die in spite of everything that NIH and its labs can do, even though I know you will make a heroic effort. With NIH present methods, you cannot do very much for those stricken Americans at all. Everything we have in the "normal" kit bag is almost useless against a knowledgeable spray attack of modified smallpox (as you know, the Russian secret BW labs have made and sold tons of that already, to guess who!). Or a spray of tularemia (you are well aware of the extreme lethality of that), or anthrax (easily obtained). It is also common knowledge that these terrorist teams with their BW agents are already on site in this country, waiting for the word to attack. This has now been officially raised to our primary Strategic Threat.

In the face of such looming strikes on the U.S., I simply cannot believe that the NIH does not feel it within their mission to rigorously check out a proposed method for saving perhaps 70% of those coming deaths (first generation equipment), and up to 90% with second generation equipment.

Perhaps you just did not read the package carefully. I urge you to do so.

Else NIH is going to look very, very bad when (1) the strikes do occur, (2) they can't handle them (and they cannot, as you well know), (3) they had within their hands in advance, a proposed methodology that could have been investigated intensely, to save millions of those stricken Americans.

As a staunch supporter of NIH and especially CDC, I have to believe that there is a different attitude there. If NIH is not interested in a previously experimentally demonstrated method of saving millions of Americans, then the only recourse left is the political channel.

I assure you that my critique of electrodynamics is well-founded, as supported by various leading physicists such as Nobelist Feynman (who stated bluntly that the field concept is wrong), Wheeler, Bunge, and so on. It is inexplicable why all our universities are still teaching a 130 year old abridged (Heaviside's) subset of Maxwell's theory, and one that still contains a material ether even though that was falsified 110 years ago!

You already have seen the misuse of this technology by the Russians, in the decades-long radiation of the U.S. Embassy in Moscow. Is it not NIH's mission to understand how they generated all those diseases and health changes? Have you ever looked into Kaznacheyev's experiments showing that ANY cellular disease or disorder can be induced in cells at a distance by purely EM means? Have you looked into what got eliminated from electrodynamics by ignoring the hidden longitudinal EM inside every potential, field, and wave? Do you realize what ignoring that has done to American chemistry, biochemistry, and medical science?"

I would hope that the NIH would at least be interested in its own mission area!

I challenge you bluntly to admit that no one presently understands the primary operation of the human cellular *regenerative* system. That's because its technical principle is not presently in our recognized physics, biochemistry, and medical science – even though it has been in the hard physics literature since 1903-4. Becker's epochal work came closest; since he only had access to the conventional EM model, it failed him. But he at least showed you rigorously that cells can be changed (both differentiated and redifferentiated) all over the map by laughably weak EM – picoamperes of current, which means persistent DC potentials. In the microwave radiation of the U.S. Embassy, all the health changes occurred in regions absent of fields – i.e., absent of bleed-off of the potentials. Hence in regions of stable DC potentials! With 100% correlation of the health changes to persistent, gradient free potentials, and 100% anticorrelation to changing potentials (i.e., fields), our own scientists concluded totally erroneously that it could not have been the EM radiation causing the changes, when their own results had just proven that it was.

Now I ask you: Can NIH explain how it was that the DC potentials caused those health changes? I think not. If it could, it would understand the action package I wrote, and its importance.

This is not a "political" letter. I'm just an ordinary American citizen who has done about 30 years very hard work on this particular area. The work is good enough now to stand on its own merits. The scientific community will eventually accept it, about 50 years from now. But we cannot wait 50 years! Those millions of Americans are going to die, because of the bureaucracy and inaction of our own scientific organizations. Whether they like it or not, the U.S. scientific community is now the forefront of the struggle for this nation to survive. And they are failing us dramatically.

So as a parent who wants his children to live, and his neighbors' children to live, and those millions of soon-to-be stricken Americans to live also, I urge you to at least have someone competent in physics (and knowledgeable that the foundations of physics itself are in woeful shape!) check the work. Has anybody there *read* any of the references to the Prioré work I cited? Does anyone there realize that *there are no EM forcefields in space?* Probably not.

Dr. Kinsel, there is a time for "business as usual" and there is a time to do some serious new work. Those stricken Americans are going to be lying there. Nothing NIH can do is going to stop that. That's a given, and it is not my own estimate. It's the official estimate. And you *know* you presently do not have the tools to do anything really effective about it.

Frankly, I interpret your letter to me as just the normal "spin control" for easy disposition. I would hope that NIH would seriously rethink the situation, get off the "spin control" and "business as usual" posturing, and do something dramatically different for a change.

What have you got to lose? A little time from perhaps two or three of your best scientists.

What have you got to gain? Saving untold millions of American lives. A new, *already partially demonstrated* cure for most dread diseases such as AIDS and cancer – diseases which you presently cannot do very much about in spite of decades of heroic struggle.

Sincerely,

cc: Senator Shelby, Congr. Cramer

T.E. Bearden
President and CEO

CTEC, Inc.
T.E. Bearden, President & CEO
2311 Big Cove Road
Huntsville, AL 35801-1351
(256)533-3682 ph/(256)536-0411 Fax

CTEC, Inc.

May 12, 1998

Dr. Harold Varmus, Director
National Institute of Health
Bathesda, MD 20892
(301) 496-1766

Dear Dr Varmus:

We have recently sent action documents to the Director of Nuclear and Counterproliferation, Office of the DCS, Air and Space Operations, HQ USAF and to the DoD (General Busbee) Assistant Secretary of Defense, as well as several Senate and House committees, which may be of interest to you. For one thing, we give the technical mechanism used to generate the Gulf War Syndrome. The same weaponry is now being used to rapidly induce new strains of certain pathogens worldwide. I urge you to closely read that section of the letter to MG Neary which explains the GWS, why the French did not get it, and why Southern Iraqis got an increase in cancer and leukemia but not GWS. Also explained is how the "microwave radiation" of the U.S. Embassy in Moscow induced diseases for decades, and how we failed to comprehend it because the standard EM model deceived us.

There is a way to treat and quickly cure most diseases, including the mass casualties resulting from a terrorist BW strike on our civilian population centers, our military bases, or our forces in the field. The method is little known, but was scientifically demonstrated in France in the 1960s and early 1970s before cancellation of the Prioré Project when the French Government changed. Eminent French scientists worked on the project, and the results are fully documented in leading French scientific journals. References are listed in a separate attachment.

Previously the Western scientific community has been unable to understand the technical mechanism responsible for such remarkable cures, because of serious foundations flaws in Western physics and electrodynamics. *Foundations* physicists have long been aware our science is flawed, and have pointed out many of these fundamental errors. However, the operational science establishment has not paid attention, even though physicists such as Feynman and Wheeler pointed out that the notion of "force fields in space" was totally wrong.

As a primary example, there is an "infolded" electrodynamics inside all potentials, fields, and waves that is far more primary than the coarse EM that is in our textbooks. It is actually an infolded general relativity, and this is what the Russians have weaponized. This infolded EM-GR has been ignored in the West (but not in Russia) since 1903.

As another example the potentials, fields, and waves of present electrodynamics are rigorously defined – and exist – only in the presence of mass. They do not exist in such form (force fields and oscillating force fields) at all in space, in the absence of mass. Rigorously, Maxwell's equations are mass-to-mass transforms, since Maxwell and everyone at the time assumed the ubiquitous presence of the material ether. In other words, to the founding electrodynamicists, there was no place in all the universe that was devoid of mass. Hence they defined all EM entities as entities containing mass. Even though Michelson-Morley experiments of more than a century ago destroyed that material ether, not a single Maxwellian equation has ever been changed! They still assume the material ether.

Specifically missing from our electrodynamics are two essential transforms: (1) the mass-to-spacetime transform, and (2) the spacetime-to-mass transform. In other words, these two transforms are "infolded" or hidden inside (comprise) the end point extremum case – the mass-to-mass transform actually written by Maxwell.

But these two missing transforms are just general relativity (they correspond precisely to Wheeler's principle of general relativity). So general relativity has always been infolded inside electrodynamics as we know it, but ignored. Further, this is a very powerful general relativity, since it uses the very strong EM force as the agent of spacetime curvature. Hence now one can engineer a powerful general relativity in the laboratory and in practical devices, and even action-at-a-distance, which one cannot do using merely the staid and weak G-force.

It turns out that longitudinal EM waves as shown by E.T. Whittaker in 1903 and 1904 are far more primary than our present EM theory and even our present GR theory. Both EM and GR are directly engineerable using longitudinal EM waves, including subluminal and superluminal EM waves in vacuum, and including action at a distance. One can engineer complexes of spacetime curvatures as desired, which in turn are *spacetime engines* (Wheeler's term). These engines can act upon mass – either living or inert – in any fashion desired, and at any distance desired.

The little-known and poorly understood Regeneration & Recovery (R&R) system – as contrasted to the immune system – utilizes this exact "spacetime engine" methodology to restore damaged or diseased cells, within its limitations – "dedifferentiating" or "time-reversing" them back to normal. The mechanism is fully explained in the attached package. The proposed program applies this fundamental method to greatly amplify the effect. Thus cancer cells can be reversed back to normal cells, HIV-infected cells (HIV-factories) can be reversed back to normal cells (genetics and all), etc. This represents a dramatic and unparalleled new medical therapeutic methodology of extreme power. The same techniques can simply be conjugated one additional time, and used to produce diseases and cellular changes at a distance, including in entire mass populations, as the KGB is doing right now. Specifically, by impressing an extremely weak "cocktail mix" of disease spacetime engines on the U.S. populace, the immune systems are reacting and being "spread thin" across several "shadow state" infectious pathogenic conditions. Thus when an actual terrorist BW attack occurs, the lethality of the strike will be remarkably enhanced because the immune systems will be "thinned" in their ability to fend off this new pathogen. By doing it this way, BW warfare can actually be conducted upon the U.S. without anyone being the wiser.

Our very survival as a nation is threatened by remarkable KGB weapons using this fully documented, extended electrodynamics. Bluntly, unless we take off our scientific blinders and understand Russian energetics weapon science, GWS and the Embassy health changes in Moscow were just a picnic before what is upon us. After two decades of work on the KGB energetics weapon problem, we have fully deciphered the technical mechanisms and what energetics is, as well as citing many of the Russian weapon tests and how they were done. Again, you can see that for yourself in the package.

Now that we understand the technical mechanisms, we are proposing rapid redevelopment of the Prioré process, in portable suitcase-sized units to be mass produced and filtered down into the entire emergency community for mass treatment of lethal infectious diseases resulting from BW strikes. And we are strongly urging the U.S. scientific community to quickly investigate and come to grips with this vast new *biological engineering* mechanism. Our very survival depends on it.

The inclosed documents provide an overview of the process. There is nothing else on the scientific horizon that can save the majority of all those stricken Americans, once the first foreign-sponsored terrorist teams strike our population centers with BW agents.

Sincerely,

Incls: Full package with table of contents

T.E. Bearden
President & CEO

The Tom Bearden Website

Energy, Observations and Comments

---

1. A Conservative Field Requires a Single-Valued Potential
2. Earth-Electrosphere and Earth-Ionosphere Capacitors
3. Earth's Poynting Energy Flow
4. The Hidden Energy Flow around us
5. Electrostatic Fields of the Earth's Electrosphere Capacitor in Fair Weather and Thunderstorms
6. Flow of Current and Energy Into, Through, and Along a Conductor
7. Energy "collected" on a charge
8. Fiber Fuse Effect
9. Impact of Vacuum Engineering
10. Lawandy's Experiment
11. Field may be nonconservative for a multivalued potential
12. The Ostrich Problem - Part 1
13. The Ostrich Problem - Part 2
14. Russia had Overunity Devices in 1930s
15. Energy output of human body
16. A "static" Poynting S-flow free-energy generator
17. Topology and Energy Conservation
18. Block Diagram: Sweet's Vacuum Triode



A Conservative Field Requires a Single-Valued Potential

© 1995 T.E. BEARDEN

A circular closed path in potential ϕ is given by A-B-C-B'-A.
Line integral from A around any closed path back to A is conservative.
Along path A-B-C, work W(1) may be extracted from rolling ball.
Along path C-B'-A, must do work W(2) on ball, where W(2) = - W(1).

Return to Slide Index

Next Slide



Earth-Electrosphere and Earth-Ionosphere Capacitors

Earth to electrosphere capacitor ≈ 300 kV

Varies from about 100 km to about 400 km and has multiple layers

25 to 60 km

About 12,800 km

EARTH

Earth's surface

Ionosphere (RF conducting region)

Consists of free electrons caused by ionizing effect of solar radiation

NOTE: Spacing of shells is exaggerated.

Electrosphere (DC conducting region) Consists of molecules ionized by cosmic rays

© 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



EARTH'S POYNTING ENERGY FLOW

N (compass)
(magnet south pole)
H
E
S
S (compass)
(magnet north pole)

© 1996 T.E. BEARDEN

a. CROSSED-FIELD POYNTING GENERATOR

b. MAGNETIC FIELD OF THE EARTH GENERATOR

POYNTING
ENERGY FLOW
AROUND EARTH
FROM WEST TO EAST

(BIDIRECTIONAL SUBTLE ENERGY FLOWS ARE GOING ON INSIDE THE POYNTING FLOW, WITHIN ITS EQUIPOTENTIALS)

c. FLOW OF POYNTING ENERGY IN THE EARTH-ELECTROSPHERE CAVITY

Return to Slide Index

Next Slide

Previous Slide


Vacuum Flux Exchange
DIPOLES
Vacuum Flux Exchange
−
+
10^{-13}
Collection and dissipation filtering by each object
10^{-13}
Collection and dissipation filtering by each object
© 1996 T.E. BEARDEN

Incredible energy flow density extracted from vacuum/dipole's virtual photon flux exchange, and output as Poynting flow S

Selected clipart © by IMSI MasterClips™
Selected clipart © by Lotus SmartPics™

In a single pass, only 10^{-13} of an energy flow is collected and dissipated by an intersecting unit charge. If multiple passes are made, the multicollection increases as an exponential function of the number of passes made in a highly localized region.

Figure 19. The world of physical matter exists behind a dramatic 10^{-13} filter in a fiery cauldron of fierce and primeval EM energy flow.

Return to Slide Index

Next Slide

Previous Slide



Electrostatic Fields of the Earth-Electrosphere Capacitor in Fair Weather and Thunderstorms

ELECTROSPHERE
25 to 60 km
Ion transport
© T.E. BEARDEN 1995
Electric field lines
750 m
Equipotential
Equipotential
Cumulo-nimbus
Fair weather Fracto-cumulus
Rain
1 m
Ground
- 10 km
- 5
Distance behind storm
Cloud zero
5
Distance ahead of storm
10 km

Return to Slide Index

Next Slide

Previous Slide



Flow of Current and Energy Into, Through, and Along a Conductor

dm_e/dt

LATERAL PRECESSION

S enters and exits

Spinning electron
inside the wire
acts as a gyro

Poynting flow
outside the wire

e^-

SPIN

SPIN

Poynting flow S (outside)
FIELD ENERGY DENSITY FLOW
$d\phi/dt$ $v \approx c$

dq/dt (inside)
dm_e/dt
$v < c$
(WORK FLOW)

© 1994, 1995 T.E. BEARDEN

current i
direction

wire

S, $d\phi/dt$ (outside) lossfree Poynting energy flow S

dm_e/dt (inside) drift current i

dm_e/dt

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)


©
™
V
√7
√6
√5
√4
√3
√2
√1
0
S
S'
S''
S'''
S^IV
S^V
S^VI
S-FLOW
Regauge
dE/dt
dφ/dt
J φ
Sluggish
Charged Particles

S flows along equipotentials. The energy density in the S-flow is proportional to the square of the voltage. The S-flow is like a very high wind, blowing against the very sluggish conduction charges that in relation are massively heavy, and simply drift very, very slowly along to form the current dq/dt.

Figure 17. Energy "collected" on a charge depends upon the charge being in a continuous Poynting S-flow. When S ceases, there is no excess energy "collected" on the charge. Energy collection never occurs in chunks, but is always a dynamic, ongoing process.

Return to Slide Index

Next Slide

Previous Slide


MARCH OF FIBER FUSE
~ 1 METER/SEC
SHEATH
LASER LIGHT DIRECTION
FLAME HEATING INITIATES FUSE
CORE (MUST CONTAIN GERMANIUM)

31A. Fiber fuse destroys core of fiber optics cable of indefinite length, pitting core with holes.


MARCH OF FIBER FUSE
~ 1 METER/SEC
LASER LIGHT DIRECTION
© 1989, 1995 T.E. BEARDEN
FLAME HEATING

31B. Reversed second fiber fuse often *restores* pitted core in cable, filling holes back up.

Figure 31. Fiber fuse effect and its strange anomalies.

Return to Slide Index

Next Slide

Previous Slide



Impact of Vacuum Engineering

- "If they [quantum fluctuations of vacuum] can be [tapped], the impact upon our civilization will be incalculable. Oil, coal, nuclear, hydropower, would become obsolete – and so would many of our worries about environmental pollution."
- "Don't sell your oil shares yet – but don't be surprised if the world again witnesses the four stages of response to any new and revolutionary development:
  - 1. It's crazy!
  - 2. It may be possible -- so what?
  - 3. I said it was a good idea all along.
  - 4. I thought of it first."

Arthur C. Clarke
"Space Drive: A Fantasy That Could Become Reality"
Nov./Dec. 1994

- *Comment:*
  - *Every dipole's broken symmetry in its energetic exchange with the vacuum already freely extracts vacuum energy.*
  - *In power sources, the dipole gates the extracted energy out as S = EXH, which flows almost entirely outside the conductors.*
  - The circuit interacts with, and uses, only about 10^{-13} of S. The electrodynamicists calculate only this small S-component.

© 1996 T E BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Selected clipart © by Lotus SmartPics™
DYE IN SOLUTION
EXCITED BY GREEN LASER
GREEN LASER
TiO2 PARTICLES ADDED IN SOLUTION
© 1996 T. E. BEARDEN

Note: Example of anti-Stokes radiation, where medium emits excess radiation and energy. In this case, energy is replenished directly from vacuum's energetic interaction.

A pure dye is dissolved in a liquid (left). A green laser pulse excites the dye (center). A laser pulse of equal intensity is sent into the same dye mixed with tiny particles of titanium dioxide suspended in the liquid (right). The latter experiment produces a much stronger, room-filling glow.

Nabil M. Lawandy et al, "Laser action in strongly scattering media," Nature, Letters, 368(6470), Mar. 31, 1994, p. 436-438.

Figure 28. Lawandy's experiment (Letokhov-Lawandy effect) with multipass, multicollection of energy. Formation of a quantum potential can also become involved. Retroreflection and self-targeting are key.

Return to Slide Index

Next Slide

Previous Slide



Field may be nonconservative for a multivalued potential

(Multivalued magnetic scalar potential arises readily in magnetics)

A
ϕ
B
ϕ for a Conservative Field
(Asymmetrical Self-Regauging).
Potential is Multivalued Here.
D
Nonconservative Field
C
B'

© 1995 T.E. BEARDEN

Potential ϕ is multi-valued from D to A.

Line integral from A around this closed path back to A is nonconservative. Along entire path A-B-C-B'-D, work may be extracted.

No work is required to go from D to A. When ball arrives at D, it also arrives at A simultaneously. I.e., the potential "jumps" in magnitude.

Return to Slide Index

Next Slide

Previous Slide



We're running out of energy! We must redouble our efforts!

We have to keep polluting the Earth, if we are to have energy!

Actually, a *few* of our electrical systems already produce all the energy we could ever need! *Learn to collect it and use it!*

Selected clipart © by IMSI MasterClips™
Selected clipart © by Lotus SmartPics™

All our antibiotics are failing! Millions will die from the new age of pandemics and from terrorists' BW attacks!!

We have to relegate EM effects on biological systems to the trash heap. We can only try to find more drugs and antibiotics.

Actually, Priore already showed how to cure most dread diseases, by making and directing vacuum engines. Becker showed you it worked. *Develop it and use it!*

Figure 33. The only problem is the ostrich problem.

© T.E. BEARDEN 1996

Return to Slide Index

Next Slide

Previous Slide



We're running out of energy!
We must redouble our efforts!

We have to keep polluting the Earth, if we are to have lots of electrical energy!

Every dipole is a universal free energy generator

Actually, a single one of our large electrical power systems already produces all the free Poynting energy the world could ever need! *We just have to learn how to collect more of it and use it without continually destroying the source dipole!*

Figure . The only energy resource problem is the theoretical ostrich problem. We must become theoretical owls, rather than ostriches.

Return to Slide Index

Next Slide

Previous Slide



RUSSIAN "SWITCHED PARAMETERS" DEVICES: SELF-OSCILLATING ROTARY GENERATORS*

- Excites oscillations without explicit sources of magnetic or electric forces (i.e., regauges)
  - Periodic variation in system's parameters
  - Experimental and theoretical proof
  - Multiple successful systems made, tested
  - Papers published in Russian, French journals
- As theory predicts, power continually increases unless load is adjusted to stabilize system
- Several large systems tested to self-destruction
- Several large stable systems built, tested

* "On the parametric excitation of electric oscillations,"
LI. Mandel'shtam and N.D. Papaleksi, Zh. Tek. Fiz. 4(1), 1934, p. 5-29.

© 1994 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide


Selected clipart © by Lotus SmartPics™
Selected clipart © by IMSI MasterClips™
Incredible energy flow density extracted by double surfaces from vacuum/dipoles' virtual photon flux exchange, and output as Poynting flow S
Energy equal to a million 1,000 megawatt power plants.
~10^-13
~10^-13
Collection and dissipation filtering by measuring instrument
About 100-200 watts actually collected and dissipated inside the body itself.
+ -
Dipoles at tiny double-surface interfaces may produce E-fields of intensity up to 10^9 volts per meter.
For rough estimate: Use 1 sq. meter effective area, and 1 million double-surfaces.
© 1996 T.E. BEARDEN

Figure 20. One human body produces more energy flow than all the electrical power loads on earth dissipate. However, only 100-200 watts of its own energy output is collected and dissipated by the body.

Return to Slide Index

Next Slide

Previous Slide


S = E X H
capacitor
plate
+
H
–
S
capacitor
plate
E
N
permanent
magnet
S = E X H
© 1996 T.E. BEARDEN

EM energy continually flows from this "static" arrangement, without any further input of energy by the engineer.

Figure 18. A "static" Poynting S-flow free-energy generator.

Return to Slide Index

Next Slide

Previous Slide



Topology and Energy Conservation

Example: Conservation in
2D versus 3D topologies

3-D CONSERVATION
(2-D CONSERVATION VIOLATED)

© T. E. BEARDEN 1992, 1995

2-D CONSERVATION

Increasing the dynamic topology allows lower topology conservation laws to be violated. The lower topology system is now an open system and may seemingly act as a source or sink.

Return to Slide Index

Next Slide

Previous Slide

Block Diagram: Sweet's Vacuum Triode


STRUCTURED IMMEDIATE VACUUM
ACTIVATED NONLINEAR NUCLEUS
EM WAVE COUPLED FROM/TO ELECTRON
RESONANCE
PC WAVE
SIGNAL WAVE
SURROUNDING VACUUM
EXTERNAL LOAD CIRCUIT
FIELD OF BARIUM FERRITE MAGNET
EXTERNAL SIGNAL WAVE INPUT
POSITIVE FEEDBACK
CLAMPED STABILIZER
AUTOMATIC GRID SIGNAL INPUT

© 1989, 1991, 1993 T.E. BEARDEN

Return to Slide Index

Previous Slide

The Tom Bearden Website

Help support the research

Foundations of Electro-Magnetism
Slide Series

- Major Points of Presentation
- Chung's Carbon Filament Negative Resistor
- Aharanov-Bohm Effect
- Absorption and emission reactions (1)
- Absorption and emission reactions (2)
- Anti-engine for cell's deviation reverses cell back to normal
- Asymmetric regauging produces excess force, which can be used to do work on the system
- Asymmetric regauging produces excess force, which can be used to do work on the regauging system
- Becker's bone fracture healing experiments
- Becker's theoretical control system governing regeneration
- Becker's theoretical DC control system involved with response to injury
- Geometrical Distortion of Poynting Energy Flow
- Cosmic Bootstrap: Before the Big Bang
- Bridging Enables COP > 1

- Aspects of Strong Local Symmetry
- Other Aspects of Strong Local Symmetry
- Bunge on the Status of Electrodynamics
- Bunge on the Status of Electrodynamics and Physics
- Bunge on the Status of Classical and Quantum Physics
- Fractions of BW Casualties Surviving
- First Step in Self-Promotion of Cancer Due to Hypoxia
- Differentiation and Dedifferentiation Timelines
- Evolution of Cells on Earth
- A Charged Particle q is a Coupled System of m and Ø
- The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry (1)
- The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry (2)
- The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry (3)
- A Charged Particle is a Coupled System
- The Anomalies in Navy Electrolyte Experiments at China Lake
- Chung's Carbon Filament Negative Resistor

- Typical circuit has about 10^{-13} energy collection efficiency
- Classical View of EM
- Curved Spacetime acts as source or sink
- Chronic Disease Puzzling
- Cancer Characteristics
- Solving a Cancer Enigma
- Cancer: Characteristics
- Nonlinear Optics Distortion Correction Theorem
- The Electronuclear Reaction: Nuclear Reactions in TR-Zones (1)
- The Electronuclear Reaction: Nuclear Reactions in TR-Zones (2)
- The Electronuclear Reaction: Nuclear Reactions in TR-Zones (3)
- In Time-Reversed Zone: Nuclear reactions are biased
- In Time-Reversed Zone: Dynamics may be reversed
- Time-Reversed Zone: Significant only after time-density charging
- A New Conservation of Energy Law
- Questions on Carcinogens and EM

Radiation

- AS DEFINED, fields and potentials only exist in and on charged matter
- Serious flaws and errors in classical EM theory
- Electrodynamicists' Reaction to Removal of the Material Ether
- Reaction to Loss of Material Ether (1)
- Reaction to Loss of Material Ether (2)
- Some EM waves in Spacetime
- Air Medium Disturbances Generated When Air is Perturbed by a Plucked Taut String
- Launching a Spacetime Perturbation ("EM Wave") from a Wire Antenna
- Phase Conjugate Wavepairs Produce New Waves
- Scalar Electromagnetics (Energetics) View of EM (1)
- Scalar Electromagnetics (Energetics) View of EM (2)

- Scalar Electromagnetics (Energetics) View of EM (3)
- Extended General Relativity Principle
- Extension of Work-Energy Theorem
- 34 Flaws in Classical EM Theory
- MTW's General Relativity Principle
- Use of General Relativity (GR) in Particle Physics
- The Missing Infolded Electrodynamics
- Infolded Engines: Excluded by Present Physics
- Mass curves and structures spacetime; ST curvatures change and structure mass (1)
- Mass curves and structures spacetime; ST curvatures change and structure mass (2)
- At Infinite Velocity: Each Is Every Other
- Lisitsyn's Report: Brain Code Broken
- Lorentz Closed Surface Integration
- Lorentz's physically insignificant energy flow can be collected and utilized
- Lorentz surface integration of the Poynting vector around a closed surface
- Longitudinal EM Photon Interaction with Charge
- Mass is transparent to longitudinal EM waves, which move through the infolded interiors of internal waves, potentials, and fields in the mass.

- Pumping with Longitudinal EM waves Time-reverses the Mass
- Maxwell's Quaternion Theory
- Maxwellian Systems before and after Regauging
- Maxwell's four equations reduce to: Page 1
- Maxwell's four equations reduce to: Page 2
- More to come



Major Points of Presentation

- Electrodynamic is seriously flawed
  - Some major flaws
  - Corrections indicated
- Why past corrective attempts failed
  - Force field concept is material
  - Missing two infolded transforms (M->ST; ST->M)
- Missing infolded general relativity inside electrodynamics
- Several Kinds of EM Waves in Space
  - How to make
  - Transduction
- A French medical example as a deep experimental demonstration
  - Spectacular regenerative cures funded by French Govt
  - Not comprehended, therefore suppressed
- Cold Fusion examples of time-density wave effects
  - China Lake instrumental anomalies in electrolysis
  - Explanation of anomalous behavior of instruments
  - Explanation of new nuclear reactions
  - Wave energy transduction provides excess heat
- Urge theorists to consider dramatically new reactions



Chung's Carbon Filament Negative Resistor

UNIVERSITY AT BUFFALO, NY

Win
CROSSED CARBON
FILAMENT LAYERS
Wout > Win

© 1998 T.E. Bearden



Aharonov-Bohm Effect

© T.E. BEARDEN 1996

- In field-free regions
  - E-field is zero
  - B-field is zero
- Potentials still exist, just no gradients
  - Cause real effects
  - Interference is the key
  - Contain sum-zeroed substructures
- Does not follow from
  - Mechanics
  - Classical electromagnetics
- Required by quantum mechanics



Absorption and emission reactions

ELECTRON ABSORBS PHOTON ENERGY, MOVES TO HIGHER ENERGY LEVEL. DECAYS BY EMITTING PHOTON

ELECTRON ABSORBS TIME DENSITY, MOVES TO DIFFERENT TIME DENSITY LEVEL. DECAYS BY EMITTING LONGITUDINAL OR PSEUDOLONGITUDINAL PHOTON

© T.E. BEARDEN 1998

PARTICLE ABSORBS ENERGY, MOVES TO HIGHER ENERGY SHELL. DECAYS BY EMITTING ENERGETIC PARTICLE. OBSERVABLE..

PARTICLE ABSORBS TIME, MOVES TO HIGHER TIME DENSITY. DECAYS BY EMITTING TIME-LIKE PARTICLE, NONOBSERVABLE BY PRESENT MEANS.

ENTIRE NUCLEUS ABSORBS ENERGY, EACH PARTICLE ABSORBS OWN. DECAY OCCURS BY COMPLEX MODES, INCLUDING FISSION OR FUSION. DECAY BYPRODUCTS OBSERVABLE.

ENTIRE NUCLEUS ABSORBS TIME, EACH PARTICLE ABSORBS OWN. DECAY OCCURS BY COMPLEX MODES, INCLUDING FISSION OR FUSION. SOME DECAY BYPRODUCTS ARE NONOBSERVABLE (SPACE ABSORBS)



Absorption and emission reactions

TRANSVERSE PHOTON

ELECTRON ABSORBS PHOTON ENERGY, MOVES TO HIGHER ENERGY LEVEL. DECAYS BY EMITTING PHOTON, REMOVING Δt

Δt coupled and emitted quickly

STREAM OF TIME-POLARIZED PHOTONS

ELECTRON ABSORBS TIME DENSITY, MOVES TO 1/c_2 DIFFERENT TIME DENSITY LEVEL. DECAYS BY EMITTING LONGITUDINAL OR PSEUDOLONGITUDINAL PHOTONS

Δt increases quasi-statically then slowly decays

Figure A. Excited energy density level in one jump.

Figure B. Excited time density level significant only after enormous number of increases.

© T.E.BEARDEN 1998



ANTI-ENGINE FOR CELL'S DEVIATION REVERSES CELL BACK TO NORMAL

PHYSICAL CELL (DISEASED)

+

EXTENDED TIME DELAY FOR RENORMALIZATION

PHYSICAL CELL (NORMAL)

VACUUM ENGINE FOR DISEASED CELL

VACUUM/SPACETIME ANTI-ENGINE FOR CELL'S DISEASE DELTA

© 1994, 1995 T.E. BEARDEN

By pumping the internal EM channel, process is dramatically accelerated.
This is the body's normal recovery mechanism, within its limits.



Asymmetric Regauging Produces Excess Force, Which Can be Used to Do Work on the System

Net Symmetric Regauging Does No Excess Work on the System

This little bird put one foot on wire A, and then the second foot on wire A also. He *net symmetrically* regauged, so he had no net excess force across him, even though his potential energy was increased. He asymmetrically regauged each foot, but both simultaneously so that one countered the other. Wise little bird!

Net Asymmetric Regauging *Can* Do Excess Work on the System

This little bird put one foot on wire A, and then the second foot on wire B. He *net asymmetrically* regauged, so he had lots of net excess force across him. That force then violently translated his little body parts every which way, doing lots of work in and on him. Bummer!

© T.E. BEARDEN 1999



Net Symmetric Regauging Does No Excess Work on the System

This little bird put one foot on wire A, and then the second foot on wire A also. He *net symmetrically* regauged, so he had no net excess force across him, even though his potential energy was increased. He asymmetrically regauged each foot, but both simultaneously so that one countered the other. Wise little bird!

Net Asymmetric Regauging Can Do Excess Work on the System

This little bird put one foot on wire A, and then the second foot on wire B. He *net asymmetrically* regauged, so he had lots of net excess force across him. That force then violently translated his little body parts every which way, doing lots of work in and on him. Bummer!

ⓒ T.E. BEARDEN 1996

Figure 32. Asymmetric regauging produces excess force, which can be used to do work on the regauging system.

Selected clipart © by Lotus SmartPics™



Becker's bone fracture healing experiments

- Tiny DC currents (picoamperes)
- Pulsed DC current can be utilized
- Pulsed magnetic fields may be utilized

(+)
ELECTRODE
(-)
ELECTRODE
DC POWER SOURCE
BONE
BONE
FRACTURE SITE

RED BLOOD CELL DEDIFFERENTIATES

Shucks hemoglobin coat
Grows nucleus

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes cartilage

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes bone
Deposits in fracture site, healing the fracture

© 1993, 1995 T.E. BEARDEN



Becker's theoretical control system governing regeneration*

Trauma Producing Tissue Loss

Local cellular effect

Local nerve effect

CNS effect

Alterations in hormone pattern (prolactin)

Alterations in local DC field pattern

Local electrical effects

Local and systemic pools of target cells

Dedifferentiation into primitive mesenchymal cells

Phase I

Blastema formation

growth

Phase II

Redifferentiation into required cell types

Restoration of body part or tissue

*Becker & Spadaro, "Electrical stimulation of partial limb regeneration in mammals," Bul. N.Y. Acad. Med., 48(4), May 1972, p. 629.



Becker's theoretical DC control system involved with response to injury*

INJURY

INPUT STIMULATION
DC SYSTEM (PAIN)

CENTRAL
DC SYSTEM

GROWTH
DIFFERENTIATION

LOCAL CELL INJURY
FREE RADICALS

OUTPUT
DC SYSTEM

TOTAL
CURRENT OF
INJURY
DC SYSTEM

MITOSIS
DEDIFFERENTIATION

STIMULATION OF
REPAIR CELLS

*Robert O. Becker, "The significance of bioelectrical potentials," Bioelectrochemistry and Bioenergetics, Vol. 1, 1974, p.191.



Geometrical Distortion of Poynting Energy Flow

At or near resonance frequency, in the case shown the energy collection fraction (reaction cross section) increases dramatically.

a. Around an aluminum sphere at light energy 8.8 eV. Absorption efficiency = 18.00.

b. Around an aluminum sphere at light energy 5eV. Absorption efficiency = 0.1.

Figures per Craig F. Bohren, "How can a particle absorb more than the light incident upon it?", American Journal of Physics, 51(4), Apr. 1983, p. 326.



Cosmic Bootstrap: Before the Big Bang:

- Cosmic repulsion behaved like a fluid with negative pressure
- The "universe" inflated (expanded) as a "false vacuum"
- As the negative-pressure fluid expanded, its energy went up rather than down
- When inflation stopped, the false vacuum decayed from its excited state
- Its excitation energy was released in a single great burst

Paul Davies, Superforce, 1984, p. 194



BRIDGING ENABLES COP > 1.0

S-flow, dϕ /dt flow, and EMF flow

V>>0

source

i ≈ 0

dQ/dt
BLOCKER
(Conductor)

V>>0

i>>0

LOAD

Closed Current
Loop A

Closed Current
Loop B

BRIDGE

Current loop B is asymmetrically regauged by
S, dϕ /dt, and EMF flow from current loop A.

Patent Pending

© 1998 T.E. BEARDEN



Aspects of Strong Local Asymmetry

- If local asymmetry is strong, conservation laws may be appreciably violated
    - Energy
    - Charge
    - Spin
    - Momentum
    - Angular momentum

© T. E. Bearden 1995, 1996

- Properties of an object may differ appreciably for
    - Different observers
    - Different detecting means
    - One time to another
    - One position to another
- STRUCTURING THE INFOLDED EM INSIDE POTENTIALS, FIELDS, AND WAVES
    - Strongly breaks local symmetry
    - Provides spacetime engines giving the above effects



Other Aspects of Strong Local Asymmetry

© T. E. Bearden 1995, 1996

- Local spacetime is curved
- Lorentz invariance of vacuum is violated
- May be a local "sink" or "source"
- Gravitational-inertial effects from EM
- Translation between virtual and observable
- Electrogravitational solitons
- Action at a distance
- Transmutation effects may exist
- Scalar/pseudoscalar field translation
- COMMENT: Thus the use of infolded longitudinal EM fields and waves to strongly break local symmetry allows internested clustering of spacetime curvatures. These spacetime structures are *vacuum engines*, or *spacetime engines*.



Bunge on the Status of Electrodynamics

"... it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state..."

"... the best modern physicist is the one who acknowledges that neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling..."

*Mario Bunge, Foundations of Physics, Springer-Verlag, New York, NY, 1967, p. 176..

© 1996 T.E. BEARDEN



Bunge on the Status of Electrodynamics and Physics

"... it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state...

"... neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling..."

© 1996 T.E. BEARDEN

*Mario Bunge, Foundations of Physics, Springer-Verlag, New York, NY, 1967, p. 176..



Bunge on the Status of Classical and Quantum Physics

"... it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state... the best modern physicist is the one who acknowledges that neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling not only to better cover their own domains but also to join smoothly so as to produce a coherent picture of the various levels of physical reality."

'Mario Bunge, Foundations of Physics, Springer-Verlag, New York, NY, 1967, p. 176..

© 1996 T.E. BEARDEN


Fraction of Casualties Surviving
N = 1 - 40 million
FRACTION SURVIVING
1.0
0.8
0.6
0.4
0.2
0.0
N CASUALTIES
0.1
0.7
0.9
0.95
CASUALTIES
TYPE TREATMENT RECEIVED
© 1998 T. E. BEARDEN
EXPRESSED IN FRACTION SURVIVING
🟩 With conventional treatment
🟨 With 1st generation P-treatment
🟨 With 2nd generation P-treatment
🟥 With 3rd generation P-treatment



FIRST STEP IN SELF-PROMOTION OF CANCER DUE TO HYPOXIA

MULTICELL
AEROBIC*
(INCLUDES MAN)

SINGLE CELL
ANAEROBIC

SINGLE CELL
AEROBIC*

CENTRAL CONTROL

OXYGEN-RICH

TIME-FORWARD
PATH AS IT
DEVELOPED

CANCER CELL

TIME-REVERSED
PATH FOR SUSTAINED
OXYGEN DEFICIENCY

PARTIALLY
ANAEROBIC

SINGLE CELL
AEROBIC

FIRST STEP IN OXYGEN-DEFICIENCY
DEDIFFERENTIATION

© 1993 T.E. Bearden

Differentiation and Dedifferentiation Timelines


CENTRALIZED CONTROL OF CELLULAR GROWTH AND REGENERATION
PRIMORDIAL SINGLE CELL ANAEROBIC
SINGLE CELL AEROBIC
OXYGEN-RICH ENVIRONMENT
NORMAL HEALTHY CELLS AND FUNCTIONS
WITH SOME DISEASED OR DAMAGED CELLS
TIME-FORWARD PATH AS IT DEVELOPED
NORMAL "DEDIFFERENTIATION" FOR HEALING OF CELL DAMAGE
SINGLE CELL MORE ANAEROBIC
SINGLE CELL AEROBIC
TIME-REVERSED PATH FOR SUSTAINED OXYGEN DEFICIENCY
TIME-REVERSED PATH WHEN NORMAL PUMPING FAILS TO HEAL CELL

© 1993, 1998 T.E. Bearden

Evolution of Cells on Earth



ESSENTIALLY ANAEROBIC ATMOSPHERE

BIOGENESIS

SINGLE CELL ANAEROBIC

CHANGE OF ATMOSPHERE TO AEROBIC (INCLUDES OXYGEN)

OBLIGATORY ANAEROBES SINGLE CELL SHIELDED FROM OXYGEN

FACULTATIVE ANAEROBES (SINGLE CELL BOTH AEROBIC AND ANAEROBIC)

EVOLVE TO

SINGLE CELL AEROBIC*

EVOLVE TO MULTICELL AEROBIC* (INCLUDES MAN)

CENTRAL CONTROL

SINGLE CELL COMPONENTS

- IMMUNE SYSTEM
- RED CELLS
- WHITE CELLS
- KILLER CELLS
- ETC.

MULTICELL COMPONENTS

- TISSUES
- MUSCLES
- BONES
- ORGANS
- SKIN
- STRUCTURES

* NOTE: LIMITED ANAEROBIC RESPIRATION STILL TAKES PLACE IN HIGHER AEROBIC LIFE FORMS, INCLUDING MAN.

EVOLUTIONARY TIME

© 1999 T. E. BEARDEN



A Charged Particle q Is a Coupled System of m and ϕ

(A proposed formal definition of a charged mass)

Note: X is a coupling operator

$$q \equiv f_q \times m_q$$

Also note that the ϕ portion of the charged particle can be internally structured, per Stoney-Whittaker-Ziolkowski, with hidden bidirectional EM wavepairs (their sums and products). Note that this constitutes an EM application of Bohm-type hidden variable theory, with many ramifications.

"...curiously enough, we do not know exactly what charge is, only what it does. Or, equally significantly, what it does not do."

M.P. Silverman, And Yet It Moves: Strange Systems and Subtle Questions in Physics, Cambridge University Press, 1993, p. 127.

Ⓒ T.E. BEARDEN 1997

An electric charge Q consists of a massless flux component and a mass component, coupled together (interacting). Q is a broken symmetry. The mass of the charge continually and violently exchanges virtual photons with the surrounding vacuum.

Thus Q is energetically driven by the surrounding vacuum potential, which itself is to first order just a violent virtual photon flux.



The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry

You really need
a Maxwell's demon,
to do some free work.

Your electrodynamicist
says he can make one,
by regauging.

© T.E. BEARDEN 1999



The Ubiquitous Assumption: *Two* Asymmetrical Regaugings for Net Symmetry

He says he will do the regauging for you. Hey, what a swell guy!

He regauges *twice*, and makes two Maxwell's demons equal and opposite. They won't do any net work for you!

© T.E. BEARDEN 1999



The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry

YE OLDE ELECTRO-
DYNAMICIST

He disdainfully says,
"We *always* do it that way!
We *must* enforce local
equilibrium and the second
law of thermodynamics!".

You decide to have a
little chat with your
electrodynamicist!
With friends like that,
who needs enemies!

© T.E. BEARDEN 1999



A Charged Particle Is a Coupled System

(The first formal definition of charge)

$$\boxed{q \equiv \phi_q \times m_q}$$

Note: X is a coupling operator

"...curiously enough, we do not know exactly what charge is, only what it does. Or, equally significantly, what it does not do."

M.P. Silverman, And Yet It Moves: Strange Systems and Subtle Questions in Physics, Cambridge University Press, 1993, p. 127.

An electric charge q is a broken symmetry in its fierce energy exchange with the active vacuum. It coherently integrates some of the virtual energy absorbs and outputs it as Poynting energy flow.



Chung's Carbon Filament Negative Resistor

UNIVERSITY AT BUFFALO, NY
© 1996 T.E. Bearden
Win
Wout > Win
CROSSED CARBON FILAMENT LAYERS



Typical circuit has about 10_{-13} energy collection efficiency

Earth
edge of solar system
Deep space
S
© 1994, 1995 T.E. BEARDEN
i
d

Distance traveled by S in one hour is 1.08x10exp(12) meters.

Example: 1.3 amps flowing in DC circuit, 1.8 mm diameter copper wire. J = 51 A/cm ^{2}

d_i = 0.1368 meters

S violently transports ϕ provided from the source.
j ϕ sluggishly transports the energy collected and dissipated in the circuit..

For the case discussed, the electron drift velocity in the circuit is about 3.8×10^{-5} meters/sec. So Jϕ moves about 0.1368 meters in one hour. Thus Jϕ has collected about 0.1368 meters of the ϕ-filled S-tube. During that same hour, the S-flow evoked by the power source will have traveled 1.08×10^{12} meters. The ϕ of both currents is the same. Both are involved in the same energy-filled tube. Thus S has provided and transported about 7.89×10^{12} times as much energy along the circuit in one hour as the jϕ has been able to collect, transport, and dissipate as work in the circuit. Thus this circuit provides about 10^{13} collection efficiency.



Classical View of EM

- Potentials just mathematical conveniences
  - Not real
  - No internal structure, just magnitude
- Force fields primary, causative, can exist in space in absence of observable mass
  - All EM actions due to force fields, none when zero
  - No action at a distance
- Vacuum empty; without energy or structure
  - No locally curved spacetime
  - No gravity effects
  - No quantum effects
- Maxwell's equations complete
  - Symmetrically regauged ***arbitrarily***
  - Topology dramatically reduced



Curved Spacetime acts as source or sink

- May emit excess radiation and energy (e.g., heat)
- May absorb radiation and energy (e.g., cool)
- May transduce waves TW ⇔ LW ⇔ TDW
- New energy conservation law applies

© 1998 T.E.BEARDEN



CHRONIC DISEASE PUZZLING

- SCIENCE REALLY DOES NOT UNDERSTAND THE MECHANISMS OF A SINGLE CHRONIC DISEASE, INCLUDING CANCER
- MANY TROUBLING FACTORS EXIST
  - *MIND*
  - *STRESS*
  - *SPONTANEOUS REMISSION*
  - *PLACEBO EFFECTS*
  - *COMBINATIONS*
- GENERATION OF THE PLACEBO EFFECT BY THE CELLULAR REGENERATION SYSTEM IS UNRECOGNIZED

© 1994, 1995 T.E. Bearden



Cancer Characteristics

- Not one disease, but a whole range
- Starts in damaged aerobic cell
- Cell shakes off body's central control
  - Starts uncontrolled division
  - Becomes a lump
- Can send forth cancer cells
  - Through blood
  - Through lymph
- Form metastases (secondary tumors)
- Often become anaerobic

© 1993 T.E. Bearden



Solving a Cancer Enigma

- An enigma has been failure of immune system to attack some tumor cells
  - Suppressor cells may curb immune system?
  - Tumor may lack antigens normally identified by the immune system?
- *Promotion of damaged cell to cancer is usually ordered by cellular control system*
  - *Regenerative and recovery system forces cell back toward anaerobe*
  - *First step breaks free from central growth*
  - *Control continues to recognize cell as self*



CANCER: CHARACTERISTICS

- NOT ONE DISEASE BUT A WHOLE RANGE
- STARTS IN ORDINARY (AEROBIC) CELL
- CELL SHAKES OFF BODY'S DICTATORIAL CONTROL*
- STARTS UNCONTROLLED DIVISION
- BECOMES A LUMP
- CAN SEND FORTH CANCER CELLS
  - THROUGH BLOOD
  - THROUGH LYMPH
- THESE FORM METASTASES (SECONDARY TUMORS)
- OFTEN BECOME ANAEROBIC (NON-OXYGEN USING)
- ENIGMA IS FAILURE OF IMMUNE SYSTEM TO ATTACK SOME TUMOR CELLS
  - SUPPRESSOR CELLS MAY CURB IMMUNE SYSTEM
  - TUMOR MAY LACK ANTIGENS NORMALLY IDENTIFIED BY THE IMMUNE SYSTEM

© 1993 T.E. Bearden

*R&R system forces cell back toward anaerobe



Nonlinear Optics
Distortion Correction Theorem

E_1 = INCIDENT WAVE

E_2 = TIME-REVERSED WAVE

© 1994, 1995, 1998 T.E BEARDEN

"If a scalar wave $E_1(r)$ propagates from left to right through an arbitrary but lossless dielectric medium, and if we generate in some region of space [say near z = 0] its phase conjugate replica $E_2(r)$, then E_2 will propagate backward from right to left through the dielectric medium, remaining everywhere the phase conjugate of E_1."



The Electronuclear Reaction: Nuclear Reactions in TR-Zones (1)

- Nucleon interchange
  - Changes neutron into proton and vice versa
  - At high rate (flat spacetime assumed)
- Statistics become skewed due to curved ST
- Can bias statistics toward either neutron or proton end
  - Biases toward transmutation of elements along isomer chains
  - Concept of "isomer" is vastly expanded



The Electronuclear Reaction: Nuclear Reactions in TR-Zones (2)

- **Normal dynamics (impulses) may reverse**
  - *Like charges attract, unlike charges repel*
  - *Positive charges cluster (are drawn together)*
  - *H+ ions (protons) may form quasi-nuclei*
  - *Nucleus coulomb barrier becomes assistant*
- **Many "impossible" reactions now possible**
  - *Quark access and quark flipping by EM*
  - *Ion clustering*
  - *Positive charges as phase conjugate mirrors*
  - *Time-density waves and time-energy charging*



The Electronuclear Reaction: Nuclear Reactions in TR-Zones (3)

- **Not observed until time-energy charging has become substantial**
  - *Time delay (hours, days)*
  - *Transduction of LW --> TW involved*
  - *Specific time-charging history of detectors is involved in twhether they detect or not*
  - *Longitudinal EM waves become significant*
- **Curved spacetime can act as source or sink**
  - *May emit excess radiation*
  - *May absorb excess radiation*



In Time-Reversed Zone:
Nuclear reactions are biased

- In normal flat ST, n ⇔ p at high rate
- Curved ST skews statistics
- Biases to either n or p
- Biases to transmutation along isomer chain
- "Isomer" concept greatly expanded

© 1998 T.E. BEARDEN



In Time-Reversed Zone:
Dynamics may be reversed

- Like charges may attract and unlike charges repel
- Coulomb barrier becomes Coulomb assistant
- Clusters like charges and forms artificial nuclei
- "Impossible" nuclear reactions at low energy
- Time-density interactions



Time-Reversed Zone:

Significant only after time-density charging

- Hours, for "fast" onset
- Days, for "slower" onset
- Transduction involved for TW ⇔ LW ⇔ TDW
- Time-history of each detector is significant
- Longitudinal EM waves become significant



A New Conservation of Energy Law

- Physics conserves total "energy and mass-energy"
- Now also must consider "time-energy"
- Conserve total mass-time-energy (spatiotemporal energy)
- Let E_T = total energy, E_M = mass energy, E_E = ordinary energy, and E_t = time energy. Then

$$E_T = E_E + E_M + E_t$$

© 1998 T. E. Bearden

$$(kE_t \Rightarrow E_E > 0) \Rightarrow E_T > (E_M + E_E)$$

- If some E_t is transduced into E_E , the experiment will violate the old spatial mass-energy conservation law



QUESTIONS ON CARCINOGENS AND EM RADIATION

- UNRESOLVED QUESTIONS ON EM RADIATION
  - DOSAGES
  - ACTIVE MECHANISMS
  - REPLICATION DIFFICULTIES
  - MEASUREMENT DIFFICULTIES
  - WHERE, WHEN, HOW ILL EFFECTS OCCUR
- SIMILAR QUESTIONS EXIST ABOUT EVERY CARCINOGEN
- SCIENCE REALLY DOES NOT UNDERSTAND THE MECHANISMS OF A SINGLE CHRONIC DISEASE, INCLUDING CANCER
  - FACTORS SUCH AS MIND, STRESS, SPONTANEOUS REMISSION, PLACEBO EFFECTS, AND COMBINATIONS OF FACTORS ARE PARTICULARLY TROUBLESOME
  - GENERATION OF THE PLACEBO EFFECT BY THE REGENERATION & RECOVERY SYSTEM IS UNRECOGNIZED

© 1994, 1995 T.E. Bearden



As defined, fields and potentials only exist in and on charged matter

$E \equiv F/q$

$S = ExH$

Note problem:
No "E" or "H" in vacuum.

Source q is a broken symmetry in vacuum flux

$S = ExH$

SOURCE CHARGE

Assumed perpetual motion machine in classical EM

"pileup" in front
So $E \equiv -\nabla\phi$

Point coulomb

$\phi \equiv$ joules continuously in geometrical flow distortion zone around a point coulomb

Electrodynamics has nothing to say about what exists in space in the absence of mass.

© 1997 T.E. BEARDEN



Serious flaws and errors in classical EM theory.

1. Eliminates the Internal EM Inside the Scalar Potential.
2. No Definition of Electrical Charge or of Scalar Potential.
3. Equations Still Assume Material Ether Per Maxwell (Unchanged).
4. Use of Force Fields in Vacuum is False (and Known to be So).
5. Treats Charge q as Unitary Instead of Coupled System $q = \phi(q)m(q)$.
6. Confuses Massless Potential Gradients as Forces (See #3, #4).
7. Does Not Utilize Mass as a Component of Force (See #23).

8. Erroneously Assumes EM Force Fields as Primary Causes.
9. Topology of EM Model Has Been Substantially Reduced.
10. Does Not Include Quantum Potential or Action at a Distance.
11. Does Not Include Superluminal Velocity of Inner EM Components.
12. Does Not Utilize Extended Near-Field Coulomb Gauge Effects.
13. Does Not Include EM Generatrix Mechanism for Time Flow.
14. Does Not Unify Photon and Wave Aspects (Requires 7-D Model).

15. Does Not Include Electron Spin and Precession (See #19, #24).
16. Treats EM Energy As Existing In "Chunks," Instead of as Flow.
17. Confuses Energy and Energy Collection (See #16).
18. Discards Half of Every EM Wave in Vacuum (See #22).
19. Erroneously Uses Transverse Vacuum Wave; It's Longitudinal.
20. Arbitrarily Regauges Maxwell's Equations to Eliminate Overunity.
21. Omits Phase Conjugate Optics Effects (The *Rule* in Internal EM).
22. Does Not Include EM Cause of Newtonian Reaction Force.
23. Erroneously Assumes Separate Force Acting on Separate Mass.
24. Confuses Detected Electron Precession Waves as Proving Transverse EM Waves in Vacuum (Remnant of Old "EM Fluid" Concept).
25. Due to Error in String Wave, Omits the Ubiquitous Antiwave.
26. *Assumes* Equilibrium; Not True Unless Include Vacuum Interactions.
27. Higher Topology Required, to Model Electromagnetic Reality.
28. Lorentz surface integration discards Poynting energy transport.
29. Has nothing at all to say about form of EM entities in massless space.
30. Eliminates the infolded general relativity using EM-force as curve agent.
31. Does not include longitudinal EM waves as time domain oscillations.
32. Does not include EM mechanism that generates time flow and flow rate.

© T.E. BEARDEN 1991, 1997



NONMATERIAL SPACETIME

© T.E. BEARDEN 1998

Material Fluid Perturbation Equations

Material Electric Fluid Disturbed

Material Electric Fluid Disturbed

Einstein's spacetime hasn't been born yet!
Michelson-Morley experiments, 1880's
Our material ether is gone, so only inert space is left!
1880s
MAXWELL
MAXWELL
Φ
, H
???
Now we are not using a material ether. Trust us! The equations do not need changing.
ELECTRODYNAMICISTS

Electrodynamicists' Reaction to Removal of the Material Ether



REACTION TO LOSS OF MATERIAL ETHER

Material Ether Assumed in Equations

Potentials, Fields, and Waves Assumed Material

Not a single equation was changed!

Now we are not using
a material ether.
Trust us! The equations
do not need changing.
ELECTRODYNAMICISTS

© T.E. BEARDEN 1999


NONMATERIAL SPACETIME
MASSLESS SPACETIME PERTURBATIONS NOT ADDRESSED
Falsely Assumed Matter-in-Space Perturbations
MAXWELL
MAXWELL
Einstein's spacetime hasn't been born yet!
1888
H
ϕ
Material Electric Fluid Disturbed
CAUSE
Material Electric Fluid Disturbed
EFFECT
???
Okay! We will just measure material entities, and call them nonmaterial.
ELECTRODYNAMICISTS
© T.E. BEARDEN 1998



Some EM Waves in Spacetime

SPACE

TIME

GALLOPING WAVE. TRANSVERSE WAVE THAT VARIES VELOCITY ALONG Z-DIRECTION, IN WAVE FASHION. (Ex: 0.01 c - 100 c)

TIME-POLARIZED (TIME-ENERGY) OSCILLATIONS

3-SPATIAL ENERGY DENSITY OSCILLATIONS

SCALAR WAVES. X, Y, Z FIXED. T VARIES. NONOBSERVABLE.

TRANSVERSE WAVES. X AND Y ENERGY DENSITY VARIES; Z FIXED.

TRANSDUCTION

TIME DENSITY OSCILLATIONS. X, Y, Z ENERGY DENSITY DO NOT VARY.. TIME DENSITY VARIES ALONG TIME DENSITY NOTOBSERVABLE, BUT TRANSDUCTION IS OBSERVABLE.

PSEUDO-LONGITUDINAL WAVES. X AND Y VARY A LITTLE, SURGE OSCILLATIONS IN Z DIRECTION.

TIME DENSITY OSCILLATIONS. X, Y, Z ENERGY DENSITY FIXED. TIME DENSITY IS NONOBSERVABLE, BUT TRANSDUCTION IS OBSERVABLE.

LONGITUDINAL WAVES. X AND Y FIXED; SURGE OSCILLATIONS IN Z DIRECTION.

TRANSDUCTION

© T.E. BEARDEN 1998



Air Medium Disturbances Generated When Air is Perturbed by a Plucked Taut String

The string wave and the holder wave never leave the string and holder respectively.

String slaps air medium

WAVE IN STRING (TRANSVERSE)
Lower degree of freedom for string.
Can only vibrate mostly laterally.

Drude Electron Gas waves

Wave is alternatively compressive and rarefactive

Nuclear proton waves

ANTIWAVE IN HOLDER
(Highly damped; not shown to scale)

Body slaps air medium

© 1993, 1995 T. E. BEARDEN



Launching a Spacetime Perturbation ("EM Wave") from a Wire Antenna

ANTENNA

ELECTRON SHELLS
(DAMPED)

NUCLEI
(HIGHLY DAMPED)

VACUUM

GRAVITON

time forward
slap (electron)

time reversed
slap (proton)

Modulations of
virtual photon flux
intensity
of the QM vacuum

By omitting the nuclei perturbation wave, Maxwell omitted Newton's third law from electrodynamics

© T.E. BEARDEN 1994, 1995



Phase Conjugate Wavepairs Produce New Waves

TRANSVERSE EM WAVE PLUS
PHASE CONJUGATE REPLICA WAVE

LONGITUDINAL EM SURGE WAVE

LONGITUDINAL EM WAVE PLUS
PHASE CONJUGATE REPLICA WAVE

$(\dot{t})$

TIME DENSITY WAVE

*Oscillates rate of flow of time
about some average value*

© T.E. BEARDEN 1994, 1995



Scalar Electromagnetics (Energetics) View of EM

- Potentials real; primary causes of EM phenomena
  - Force fields made by differentiations of potentials
  - Force fields are effects, not primary causes
  - Force fields exist only in, on mass particles
- Actions due to potentials and their interference
  - Action at a distance or locally
  - Quantum potential and hidden variables
- Locally curved spacetime, engineerable by EM
  - Gravity effects not necessarily negligible
  - Strong EM force or time used as agent of curvature

© T.E. BEARDEN [illegible]



Scalar Electromagnetics (Energetics) View of EM (Cont'd)

- Potentials have internal structure
  - Stoney/Whittaker structure
  - Longitudinal EM phase conjugate wavepairs
  - Each wavepair is a time-polarized EM wave
- Vacuum EM is a potential and has microstructure
  - Stoney-Whittaker biwaves/t-polarized waves
  - Fluctuations exhibit chaos
- Spacetime ≡ Vacuum ≡ Potential ≡ Flux

© T.E. [illegible]



Scalar Electromagnetics (Energetics) View of EM (Cont'd)

- Statistics may have hidden order (already chaotic)
- Uses spacetime curvature engines to alter matter (inside-out or outside-in)
- Engineerable EM mechanism generates rate of flow of a mass through time
- Quantum potential with specific QP can be used for instant action at a distance



Extended General Relativity Principle

- "All levels of energy structures and all levels of time structures mold spacetime geometry.
- This is called a ***vacuum engine*** (spacetime engine).
- Spatial and temporal structuring act upon mass at all levels.
- This produces ***templates*** of forces, for translations and stresses."

© T.E. BEARDEN 1990

ACTIVE SPACETIME
DYNAMIC MASS
STRUCTURING OF ACTIVE SPACETIME CURVATURES



Extension of Work-Energy Theorem

© T.E. BEARDEN 1997

- *Theorem*: $W = k_f - k_i = \Delta k$ [1]
- k must be interpreted not as energy *per se*, but as *collected/collecting* energy.
- The reaction cross section λ for the collecting process must be included.
- *Extension*: $W = \lambda (k_f - k_i) = \lambda \Delta k$ [2]
- Normally $\lambda \leq 1$, as for elastic collision or Stokes emission.
- However, $\lambda > 1$ is now possible, for processes which asymmetrically self-regauge. An example is Letokhov's negative absorption of the medium.
- Working models are the Patterson Power Cell® and Lawandy lasing without population inversion.



MTW's General Relativity Principle

- "Space acts on matter, telling it how to move.
- In turn, matter reacts back on space, telling it how to curve."

ACTIVE SPACETIME
STRUCTURING OF ACTIVE SPACETIME CURVATURES
DYNAMIC MASS

© T.E. BEARDEN 1998



Use of General Relativity (GR) in Particle Physics

© 1998 T.E. Bearden

- GR seldom used in particle physics
- In cold fusion, Matsumoto* has applied general relativity
- Consistent with important cold fusion results
- Used spacetime (ST) curvature by energy density
- Matsumoto did not utilize:
  - Longitudinal EM waves
  - Time density waves
  - Time density curvatures of ST (gain = 9×10^{16})

* T. Matsumoto, "Mechanisms of Electro-Nuclear Collapse," Proc. ICCF-7, Vancouver, BC, Canada, Apr. 1998, p. 98.



THE MISSING INFOLDED ELECTRODYNAMICS

Material Electric Fluid Disturbed

Maxwellian electrodynamics has nothing at all to say about EM entities in space or their form

MATTER-TO-MATTER TRANSFORM

Material Electric Fluid Disturbed

INFOLDED INSIDE MAXWELLIAN EM AS HIDDEN EM VARIABLES

MATTER-TO-SPACETIME TRANSFORMATION

SPACETIME-TO-MATTER TRANSFORMATION

INTERNESTED SPACETIME CURVATURES

(VACUUM ENGINES)

INFOLDED GENERAL RELATIVITY

EINSTEIN'S SPACETIME

© T.E. BEARDEN 1998



Infolded Engines: Excluded by Present Physics

- *The infolded dynamics of EM systems are not considered in general relativity, electromagnetics, or quantum mechanics*
- *None of these disciplines include such spacetime curvature engines (vacuum engines)*
- *Thus GR, EM, and QM cannot be unified, since ST curvature engines are where the unification mainly occurs*

© 1999 T. E. BEARDEN



ST curvatures propagate

© T.E. BEARDEN 1998

mass perturbation (Drude Electrons)

Transmitter

mass-to-spacetime transformation

altered spacetime (curvatures)

spacetime-to-mass transformation

altered spacetime (curvatures)

mass perturbation (Drude Electrons)

Receiver

Complex of ST curvatures (vacuum engine, or spacetime engine)

Spacetime disturbance (engine) propagates

The *mass-to-mass transform* contains two hidden infolded transforms: (i) the *mass-to-spacetime transform* and (ii) the *spacetime-to-mass* transform. What is transmitted and propagates in space is a *spacetime perturbation.*



Mass curves and structures spacetime; ST curvatures change and structure mass

ST curvatures propagate

mass

mass-to-spacetime transformation

spacetime-to-mass transformation

mass

altered spacetime

altered spacetime

ST curvature complex (vacuum engine)

© T.E. BEARDEN 1996

spacetime disturbance propagates



At Infinite Velocity:

Each Is Every Other

SPACETIME

VIRTUAL
PARTICLE
FLUX

POTENTIAL

MIND AND
MIND LEVELS

MASS

PLANET

LIVING ORGANISMS

© 1997 T.E. Bearden



Lisitsyn's Report: Brain Code Broken

- THEORY DEVELOPED AND FITTED
- HYSTERESIS MEMORY LOOP
- CONTROLLED EM INDUCTION
  - IMAGES
  - SENSATIONS
  - PREDETERMINED EMERGENCE
- 23 EEG BANDS
  - UP TO 8.1×10^{20} HZ
  - 11 INDEPENDENT CHANNELS

© 1978,1985,1991 T.E. BEARDEN

S.K. Lisitsyn, "New Approach to the Analysis of Electroencephalograms," DDC Report AD73005, p. 16-25.



Lorentz Closed Surface Integration

Selects only the locally divergent portion of the Poynting energy flow that powers the component.

Only the wind on my ship is of physical significance!

© 1997 T.E. Bearden



Lorentz Closed Surface Integration

Selects only the locally divergent portion of the Poynting energy flow that powers the component.

How can they use that old physically insignificant wind?!!

© T E BEARDEN 1998

Lorentz's physically insignificant energy flow can be collected and utilized.



Lorentz surface integration of the Poynting vector around a closed surface

See Panofsky & Phillips, Classical Electricity and Magnetism, 2nd, edn., Addison Wesley, 1962, p. 178-181.

1a. Lorentz surface integration.

1b. Actual S in and S out.

Note: If the S-vector is integrated over the closed surface, then all energy *transport* passage is zeroed, leaving only the very small component of the input S-flow that is powering the joule heating of the resistor. In short, only the small component of the S-flow that is equal in magnitude to the Slepian vector $j\phi$ remains. This measures only the tiny portion of the S-flow that is "collecting" on electrons passing through the resistor, and therefrom being dissipated out of the resistor as joule heating. It discards everything else (all S_{TR}'s and S_{OUT}). S_{IN} becomes S_R.

© 1997 T.E. BEARDEN



Longitudinal EM Photon Interaction with Charge

- Creates time-density wave pumping
- Slowly creates time-density charging

Transverse photon
CHARGED MASS
Excited Energy Density State
Time-density (scalar) photon
Longitudinal photon
Phase Conjugate Added by Charged mass
CHARGED MASS
Excited Time Density State

© 1990 T.E. Bearden

- Fundamental units are arbitrary in physics
- Can express all physics in one unit -- e.g., time
- Time is highly compressed energy
- 1 sec = 9 x 10_{16} joules of transverse EM wave energy

Figure 1-8. Infolded biwave composition of a scalar potential.



Mass is transparent to longitudinal EM waves, which move through the infolded interiors of internal waves, potentials, and fields in the mass

MASS MEDIUM
Ambient Vacuum Potential
EMWave
Static EM Field
© T.E. BEARDEN 1997
Ambient Vacuum Potential
D.C. Potential

Mass is mostly ambient vacuum potential, modified by internal potentials, fields, and waves. Any wave or field is just two scalar potential functions, by Whittaker 1904.



Pumping with Longitudinal EM Waves Time-reverses the Mass

vacuum
(spacetime)
engine in
the mass
is the input

longitudinal
EM pump
wave

MASS
previous state

CELL MASS

highly nonlinear to any
and all LW frequencies

Antiengine acts upon
mass at all levels

AN AMPLIFIED VACUUM
(SPACETIME) ANTIENGINE IS
FORMED AND ACTS ON THE
MASS, TIME-REVERSING
IT AND ALL ITS COMPONENTS
NO MATTER HOW SMALL

longitudinal
EM pump
wave

© T.E.BEARDEN 1997



Maxwell's Quaternion Theory

- Quaternions:
  - Discovered by Hamilton in 1843
  - A quaternion has a vector part
  - A quaternion has a scalar part
  - First significant non-arithmetic number system
  - Higher topology than vector or tensor algebra
- Maxwell's theory was in quaternion equations
  - 20 equations in 20 unknowns
  - Reduced to a small 4-equation subset by Heaviside and Gibbs
  - EM topology dramatically reduced

© T.E. BEARDEN 1995, 1996



Maxwellian Systems
Before regauging, after symmetrical regauging, and after asymmetrical regauging

Note: Any system must first break equilibrium in its vacuum exchange, before it can energize Drude electrons and "power" the load. Asymmetric regauging is always utilized. Powering loads and losses is a symmetry-restoring operation.

MAXWELL'S EQUATIONS BEFORE THEIR REGAUGING

BEFORE REGAUGING

OPEN SYSTEMS NOT IN THERMODYNAMIC EQUILIBRIUM

OPEN SYSTEMS IN THERMODYNAMIC EQUILIBRIUM

ASSUMED "CLOSED" SYSTEMS

SYSTEMS WHICH REGAUGE, FREELY CHANGE ENERGY, AND SHOW COP<1.0 BY DESIGN

SYSTEMS WHICH REGAUGE, FREELY CHANGE ENERGY, AND SHOW COP>1.0 BY DESIGN

SYSTEMS REGAUGE, CHANGE ENERGY, BUT USE HALF THE ENERGY TO DESTROY SOURCE DIPOLE

TRULY CLOSED SYSTEMS (NONE EXIST)

ASYMMETRICAL REGAUGING

SYMMETRICAL REGAUGING

Selected clipart© by Lotus SmartPics™

© 1996, 1997 T.E BEARDEN



Page 1 of 2.

Maxwell's four equations reduce to:

$$\nabla^2\Phi + \frac{1}{c}\frac{\partial}{\partial t}(\nabla \bullet A) = -4\pi\rho \qquad [1]$$

$$\nabla^2 A - \frac{1}{c^2}\frac{\partial^2 A}{\partial t^2} - \nabla(\nabla \bullet A + \frac{1}{c}\frac{\partial\Phi}{\partial t}) = -\frac{4p}{c}J \qquad [2]$$

A is replaced by A', where

$$A' = A + \nabla\Lambda \qquad [3]$$

The new B' field then becomes

$$B' = \nabla \times (A + \nabla\Lambda) = \nabla \times A + 0 = \nabla \times A = B \qquad [4]$$

A new E-field will also be formed. So let

$$\Phi' = \Phi - \frac{1}{c}\frac{\partial\Lambda}{\partial t} \qquad [5]$$

© T.E. BEARDEN 1997



Page 2 of 2.

Per Jackson, (A,Φ) are *habitually* chosen so that

$$\nabla \bullet A + \frac{1}{c}\frac{\partial \Phi}{\partial t} = 0 \qquad [6]$$

The *net symmetrical* regauging separates variables.

Two inhomogeneous wave equations result:

$$\nabla^2 \Phi - \frac{1}{c^2}\frac{\partial^2 \Phi}{\partial t^2} = -4\pi\rho \qquad [7]$$

$$\nabla^2 A - \frac{1}{c^2}\frac{\partial^2 A}{\partial t^2} = -\frac{4\pi}{c} J \qquad [8]$$

© T.E. BEARDEN 1997

Equations [1] and [2] *arbitrarily* changed to [7] and [8]

The Tom Bearden Website

Life Systems
Toward the Beginning of the End

---

1. Toward the Beginning of the End: Capstone Presentations
2. Toward the Beginning of the End
3. Biospheric Evolution
4. A Living Biological System
5. The Evolutionary Path of Multicellular Organisms
6. To Paraphrase Churchill
7. Directed Evolution: Mechanism for Species Reactive Adaptation
8. Earth's Poynting Energy Flow
9. The Immune System
10. Mind and Matter Interaction
11. Levels of Consciousness and Unconsciousness
12. Access to Mind, Memory and Thought
13. US Intelligence Statement on Soviet Psi Research
14. Mind and Matter Interaction
15. Conscious and Unconscious Minds
16. Velocity is Rotation
17. Species Reactive Adaptation: Directed Evolution
18. Technology's Goal
19. Technology's End
20. Technological Species' Problems

The Tom Bearden
Website

Briefings

One of Tom's first public lectures: World Futures Society 1982
Other panelists included James Beale, Carol Rosin, Barbara Marx Hubbard and Glenn Doman

---

The "Porthole" Concept

Extension of the Priore Method of Healing as applicable to the treatment of biological warfare effects and cellular afflictions such as cancers, AIDS etc.

NEW

Hubbert's Peak: The Impending Oil Crisis, by Professor Kenneth S. Deffeyes

Book Review and Slides

A National Report on America's Energy Crisis

by Energy Secretary Spencer Abraham - March 19, 2001

Commentary and Slide Show (66) by Tom Bearden

A Visual Tour of what they don't want you to know about electrical circuits
10 Trillion Percent of the Current Produced is Wasted!

Weapons Slides

The Missing Infolded Electrodynamics
85 slides

A Brief Technical Background to the Extended Priore Healing Methodology
11 slides

Briefing sent by Tom Bearden to Defense Department, National Institute of Health, USAF, National Science Foundation etc. re extended and improved Priore Treatment to counter mass casualties from Biological Warfare

- Letter to DHHS re adoption of Priore technology
  24 June, 1998
- Letter to NIH re adoption of Priore technology
  12 May, 1998

Towards the Beginning of the End - Lecture in Florida for Capstone Presentations, Sept. 1998



TOWARD THE BEGINNING OF THE END

Capstone Presentations

26-27 Sep. 1998

T. E. Bearden
LTC, US Army (Retired)
M.S., Nuclear Engineering
Fellow Emeritus, AIAS

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide



Toward the Beginning of the End

- Errors in Electrodynamics
- Overunity EM Systems
- Subtle Energy: What It Is
- New Electromagnetic Waves
- Cold Fusion: the Electronuclear Effect
- Priore: New Form of Healing
- Living Universe: Mind and Matter Interaction
- Toward the Last Human State

Previous Slide

Return to Slide Index

Next Slide



Biospheric Evolution

- Planet formation
- Amino acids
- Self-replicating macromolecules
- One-celled organisms
- Multicellular organisms
- Technological species
- Linkage or destruction
- Totality or starts all over again

© T.E. BEARDEN 1976, 1999

Return to Slide Index

Next Slide

Previous Slide



A Living Biological System

The body's cells and their parts are linked by a mutual quantum potential. Mind and thought (from a mindworld) occupy the internal SW biwave structure of the QP to that body, being continually disconnected and reconnected by the photon interaction generatrix for the flow of time.

ALL POTENTIALS IN THE BODY ARE ASSOCIATED WITH AND CONNECTED TO THE QUANTUM POTENTIAL.

THE BRAIN AND NERVOUS SYSTEM ARE SPECIAL TUNERS/SWITCHERS BETWEEN INNER AND OUTER EM "SIGNALS".

DEEP CONTROL IS VIA VACUUM ENGINES: NESTED STRUCTURING OF THE SWZ BIWAVES INSIDE, AND COMPRISING, THE SCALAR POTENTIALS.

© 1999 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



The Evolutionary Path of Multicellular Organisms

ESSENTIALLY ANAEROBIC ATMOSPHERE

CHANGE OF ATMOSPHERE TO AEROBIC (INCLUDES OXYGEN)

EVOLVE TO MULTICELL AEROBIC (INCLUDES MAN)

CENTRAL CONTROL

BIOGENESIS

SINGLE CELL ANAEROBIC

EVOLVE TO

SINGLE CELL AEROBIC*

OBLIGATORY ANAEROBES SINGLE CELL SHIELDED FROM OXYGEN

FACULTATIVE ANAEROBES (SINGLE CELL BOTH AEROBIC AND ANAEROBIC)

SINGLE CELL COMPONENTS

- IMMUNE SYSTEM
- RED CELLS
- WHITE CELLS
- KILLER CELLS
- ETC.

MULTICELL COMPONENTS

- TISSUES
- MUSCLES
- BONES
- ORGANS
- SKIN
- STRUCTURES

* NOTE: LIMITED ANAEROBIC RESPIRATION STILL TAKES PLACE IN HIGHER AEROBIC LIFE FORMS, INCLUDING MAN.

© T. E. BEARDEN 1999

EVOLUTIONARY TIME

Return to Slide Index

Next Slide

Previous Slide



To paraphrase Churchill:

- In technology, we have not reached the end, or even the beginning of the end.
- Perhaps, however, with the emerging technology, we have reached the end of the beginning.

Winston Churchill

© T.E. BEARDEN [illegible]

Return to Slide Index

Next Slide

Previous Slide



Directed Evolution: Mechanism for Species Reactive Adaptation

ONE INDIVIDUAL

LOCALIZED MOLECULAR BONDS AND MATERIAL LATTICES

ELECTRON SHELLS

ATOMIC NUCLEI

NUCLEAR POTENTIALS

A

LONG-TERM CUMULATION BY SPECIES

PHASE CONJUGATES

COUNTER EFFECTS

SHELDRAKE'S MORPHOGENETIC FIELD (SPECIES QUANTUM POTENTIAL)

(SPECIES QUANTUM POTENTIAL)

(JUNG'S COLLECTIVE UNCONSCIOUS MIND)

A

LIVING INDIVIDUAL SPECIES MEMBERS

PHASE CONJUGATES

COUNTER EFFECTS

DEATH CAUSES

DEAD MEMBERS

© T.E. BEARDEN 1996

Return to Slide Index

Next Slide

Previous Slide



EARTH'S POYNTING ENERGY FLOW

Note: The actual energy density is on the order of 10^{-1} as much as is conventionally given.

a. CROSSED-FIELD POYNTING GENERATOR

b. MAGNETIC FIELD OF THE EARTH GENERATOR

POYNTING ENERGY FLOW AROUND EARTH FROM WEST TO EAST

© T.E. BEARDEN 1997

(BIDIRECTIONAL INFOLDED ENERGY FLOWS ARE GOING ON INSIDE THE POYNTING FLOW, WITHIN ITS EQUIPOTENTIALS)

c. FLOW OF POYNTING ENERGY IN THE EARTH-ELECTROSPHERE CAVITY

Circles the earth from west to east, in the earth-electrosphere capacitor.

Return to Slide Index

Next Slide

Previous Slide

Note: Should be

10^{13}


THE IMMUNE SYSTEM
BONE MARROW
Lymphocytes
Special Defense
Intestinal tissue, liver, etc.
Thymus
Complement system
General Defense
Feeding cells
Monocytes
B-lymphocytes
suppressor cells
plasma cells
antibodies
T-lymphocytes
killer cells
helper cells
complement factors
granulocytes
macrophage
bacterium (foreign invader)
© 1999 T. E. Bearden

Return to Slide Index

Next Slide

Previous Slide



Mind and Matter Interaction

- Living systems: matter, mind, life, death, time
- Function of the extended quantum potential
- Nature of conscious and unconscious mind
- Gaia and collective species unconscious mind
- EM topology vs. mind and matter interactions
- Paranormal phenomena: Mechanisms
- Unsuspected EM effects on biological systems
- Recovery system: Use of scalar "internal" EM
- Vacuum engines, death rays, and healing rays
- Priore's scalar EM therapeutic method
- Resolution of the fundamental technological species problem: The Lady or the Tiger?

© T.E. BEARDEN 1996

Return to Slide Index

Next Slide

Previous Slide



LEVELS OF CONSCIOUSNESS AND UNCONSCIOUSNESS

CONSCIOUS MIND
PERSONAL UNCONSCIOUS
FAMILY
CITY
STATE
CREED
NATION
GEOGRAPHICAL AREA
SPECIES
BIOSPHERIC
UNIVERSAL
INFINITE BEING
SPECIES
GAIA

© T.E.BEARDEN 1999

Return to Slide Index

Next Slide

Previous Slide



Access to Mind, Memory, and Thought

- Internal Whittaker channels in Body
- Used for master control functions
  - Mind, memory, thought
  - Master cellular control
  - Immune system
  - Regenerative system
- Dynamics infolded inside longitidinal EM biwave structure of scalar potentials
- Gives access to mind and control software

© T.E. BEARDEN 1997

Return to Slide Index

Next Slide

Previous Slide



U.S. Intelligence Statement on Soviet Psi Research*

- Sooner or later, Soviets may be able to
  - Know:
    - Contents of documents
    - Troop and ship movements
    - Installation locations and nature
  - Mold thoughts at a distance
  - Disable equipment at a distance
  - Kill persons at a distance
- Comment: Soviet psychoenergetics is a physics, not Western parapsychology. Much of this capability now exists and has been weaponized in action-at-a-distance weapons.

© 1996 T.E. BEARDEN

*Controlled Offensive Behavior - USSR (U)
DIA Report ST-CS-01-169-72, July 1972

Return to Slide Index

Next Slide

Previous Slide



Mind and Matter Interaction

A higher topology science and a new becoming

EFFECTS
XMTR
XMTR

(c) T.E. BEARDEN 1990

Return to Slide Index

Next Slide

Previous Slide



Conscious and Unconscious Minds: Serial vs. Massively Parallel Processors

Serial processor. One and only one thing or operation at a time.

Parallel processor. Millions of simultaneous things and operations.

CONSCIOUS MIND
FUNCTIONAL PROJECTION
CAN'T SEE MASSIVELY PARALLEL
SEE SERIAL
! ! !
? ? ?
"UNCONSCIOUS" MIND

© T.E. BEARDEN 1999

Note:

- Conscious mind is a functional projection from the unconscious.
- When asleep or unconscious, have withdrawn the "serially conscious" function back into the unconscious.
- For sleep, not total withdrawal, must awaken easily for survival.

Return to Slide Index

Next Slide

Previous Slide



Velocity Is Rotation

An object moving with velocity v < c has rotated slightly out of 3-space toward the time dimension. It's "projection" back into 3-space is shorter, providing the Lorentz-Fitzgerald contraction.

When velocity v = c, a full right-angle turn has been made, and the object has "lost" its projection along its direction of motion. Hence it appears as a 2-dimensional plane moving at the speed of light; in short, a photon or a light wave.

(c) 1999 T.E. BEARDEN

Lorentz-Fitzgerald Contraction

Next Slide

Return to Slide Index

Previous Slide



Species Reactive Adaptation

(Directed Evolution)

ONE INDIVIDUAL

LOCALIZED MOLECULAR BONDS AND MATERIAL LATTICES

ELECTRON SHELLS

ATOMIC NUCLEI

NUCLEAR POTENTIALS

A

PHASE CONJUGATES

LONG-TERM SPECIES CUMULATION

COUNTER EFFECTS

SHELDRAKE'S MORPHO-GENETIC FIELD (SPECIES QUANTUM POTENTIAL)

(SPECIES QUANTUM POTENTIAL)

(JUNG'S COLLECTIVE UNCONSCIOUS MIND)

A

PHASE CONJUGATES

COUNTER EFFECTS

LIVING INDIVIDUAL SPECIES MEMBERS

DEATH CAUSES

DEAD MEMBERS

Return to Slide Index

Next Slide

Previous Slide



Technology's Goal

- Make things ever
  - Smaller
  - More powerful
  - Cheaper
  - Simpler

N_3
N_5
N_1
N_4
N_2

© 1998 T. E. Bearden

Return to Slide Index

Next Slide

Previous Slide


N3
N5
N1
N4
N2

Technology's End

Goal	Conclusion
Small	Handheld
Powerful	It can destroy the earth
Cheap	One man can afford it
Simple	Thousands can build it

With the progress in energetics weapons, and particularly the quantum potential, mankind has now arrived at this point. It poses the end of humanity, on the present course.

© 1998 T. E. Bearden

Return to Slide Index

Next Slide

Previous Slide


DNA
RNA
SUPERCONSCIOUS
LINKED MINDS

TECHNOLOGICAL SPECIES' PROBLEM

- *Intelligence as adaptability*
  - Hardware implications
  - Software implications
- *Two major kinds of intelligence*
  - Technological (tool-using)
  - Nontechnological (not tool-using)
- *The technological species is a self-killer*
  - Tools become ever more powerful,cheaper
  - Dominates its biosphere
  - Achieves power to easily destroy self, biosphere
  - Adapts its tools into its own intraspecies conflict
  - Eventually will destroy own species, much or all of biosphere
- *The human collective unconscious mind is insane*
  - Severe dissociation technically defines psychosis
  - Collective conscious mind is fragmented into 6 billion pieces
- The solitary human problem: How can "free will" be kept but absolute control reinstated over intraspecies conflict?
- *Must engineer next step in human evolution, for the entire species*
  - *Mind linkage, entire species*
  - *Jung's collective unconscious acquires a collective conscious*

© T.E. BEARDEN 1996

Return to Slide Index

Previous Slide

The Missing Infolded Electrodynamics

Contents

1. The Missing Infolded Electrodynamics
2. Major Points
3. Major Points (cont.)
4. MTW's General Relativity Principle
5. Extended General Relavity Principle
6. Active Spacetime and Specific Vacuum Engine
7. Electrodynamicists React to Removal of Material Ether
8. Reaction to Loss of Material Ether
9. Massless Spacetime Perturbations Not Addressed
10. Bunge on Status of Electrodynamics
11. Bunge (continued)
12. Poynting Energy Flow Along Two Parallel Conductors
13. Fields and potentials defined only in/on charged matter
14. Wave in String (Transverse)
15. Launching EM Wave from Wire Antenna
16. Phase Conjugate Wavepairs Produce New Waves
17. Time-Polarized (Scalar) EM Wave
18. Mechanism for flow of time
19. Present systems coefficient of performance (COP)<1.0
20. Bridging for Overunity
21. Free Energy Generator
22. Demonstration of Overunity Concept
23. Altered Spacetime Curvatures
24. Interaction of Mass and Spacetime Curvature
25. Composition of Scalar Potential
26. Lorenz Closed Surface Integration
27. How can they use that old physically insignificant wind?!!
28. Vacuum Engines: Spacetime Demons
29. Undistorted Progressive Waves (1)
30. Undistorted Progressive Waves (2)
31. Other Superluminal Waves
32. Becker's Experiments: Healing Bone Fractures
33. Producing a Specific Spacetime Curvature Engine
34. Pumping A Phase Conjugate with Transverse EM

35. Differentiation and Dedifferentiation
36. First Step to Cancer: Hypoxia
37. Longitudinal Photon Interaction with Charge
38. General Relativity in Particle Physics
39. Pepper* on time-reversing mass
40. Pepper* on time-reversing mass (2)
41. Pepper* on time-reversing mass (3)
42. Chung's Negative Resistor
43. China Lake Anomalies
44. Time Reversal (TR) Zone
45. Electronuclear Reactions in TR-Zones (1)
46. Electronuclear Reactions in TR-Zones (2)
47. Electronuclear Reactions in TR-Zones (3)
48. Nuclear Reactions in Time-Reversal Zones
49. Nuclear reactions are biased
50. Dynamics may be reversed
51. Significant only after time-density charging
52. Curved Spacetime as source or sink
53. Anomalous China Lake Phenomena (1)
54. Anomalous China Lake 2
55. Anomalous China Lake 3
56. Anomalous China Lake 4
57. Consistent Anomalies 1
58. Consistent Anomalies 2
59. LW Emission in Electrolysis
60. New Energy Conservation Law
61. Carcinogens & EM Radiation
62. Carcinogens & EM Radiation 1
63. Chronic Disease Puzzle
64. Cancer characteristics
65. Solving Cancer Enigma
66. Cancer Characteristics
67. Portable Prioré Unit
68. Lisitsyn: Brain Code Broken
69. Anti-engine reverses cell
70. Prioré Methodology
71. Prioré Methodology (2)
72. Pumping cell with LW
73. Extension to Nonlinear Optics
74. Time Reversal of Mass to a Form Not in Its Past
75. Cellular R&R System

76. Portable Prioré Treatment System
77. Portable System Block Diagram
78. Absorption and Emission
79. Absorption and Emission (2)
80. EM Waves in Spacetime
81. Cellular Evolution
82. Becker's Regeneration System
83. Becker's Control System Responds to Injury
84. Casualties Surviving Conventional Treatment
85. "Time as fuel" is the future


THE MISSING INFOLDED ELECTRODYNAMICS
Maxwellian electrodynamics has nothing at all to say about EM entities in space or their form
Material Electric Fluid Disturbed
MATTER-TO-MATTER TRANSFORM
Material Electric Fluid Disturbed
MATTER-TO-SPACETIME TRANSFORMATION
INFOLDED INSIDE MAXWELLIAN EM AS HIDDEN EM VARIABLES
SPACETIME-TO-MATTER TRANSFORMATION
INTERNESTED SPACETIME CURVATURES
(VACUUM ENGINES)
INFOLDED GENERAL RELATIVITY
EINSTEIN'S SPACETIME
© T.E. BEARDEN

Published by Lotus® Freelance Graphics®



Major Points of Presentation

- Electrodynamic is seriously flawed
  - Some major flaws
  - Corrections indicated
- Why past corrective attempts failed
  - Force field concept is material
  - Missing two infolded transforms (M->ST; ST->M)
- Missing Infolded general relativity inside electrodynamics
- Several Kinds of EM Waves in Space
  - How to make
  - Transduction
- A French medical example as a deep experimental demonstration
  - Spectacular regenerative cures funded by French Govt
  - Not comprehended, therefore suppressed
- Cold Fusion examples of time-density wave effects
  - China Lake instrumental anomalies in electrolysis
  - Explanation of anomalous behavior of instruments
  - Explanation of new nuclear reactions
  - Wave energy transduction provides excess heat
- Urge theorists to consider dramatically new reactions

Published by Lotus® Freelance Graphics®



Major Points of Presentation

- Electrodynamic is seriously flawed
- Why past corrective attempts failed
- Missing Infolded general relativity inside electrodynamics
- Several Kinds of EM Waves in Space
- French medical example as a deep experimental demonstration
- Cold Fusion time-density wave effects
- Urge theorists to consider new reactions

Published by Lotus® Freelance Graphics®



MTW's General Relativity Principle

- "Space acts on matter, telling it how to move.
- In turn, matter reacts back on space, telling it how to curve."

ACTIVE SPACETIME
STRUCTURING OF ACTIVE SPACETIME CURVATURES
DYNAMIC MASS

© T.E.BEARDEN [illegible]

Published by Lotus® Freelance Graphics®



Extended General Relativity Principle

- "All levels of energy structures and all levels of time structures mold spacetime geometry.
- This is called a *vacuum engine* (spacetime engine).
- Spatial and temporal structuring act upon mass at all levels.
- This produces *templates* of forces, for translations and stresses."

ACTIVE
SPACE TIME
DYNAMIC
MASS
STRUCTURING
OF ACTIVE
SPACE TIME
CURVATURES

Published by Lotus® Freelance Graphics®

Active Spacetime and a Specific Vacuum Engine (Spacetime Engine)

(A General Relativistic Concept and Analogy)


ACTIVE SPACETIME
DYNAMIC MASS
STRUCTURING OF ACTIVE SPACETIME CURVATURES
DETAILS OF STRUCTURING OF ACTIVE SPACETIME CURVATURES (TEMPLATE)
mass structures spacetime
spacetime structures act on mass at all levels

© T.E. BEARDEN 1993

Published by Lotus® Freelance Graphics®


NONMATERIAL SPACETIME
© T.E. BEARDEN [illegible]
Einstein's spacetime hasn't been born yet!
Michelson-Morley experiments, 1880's
Material Fluid Perturbation Equations
MAXWELL
MAXWELL
Our material ether is gone, so only inert space is left!
1880s
Φ
H
Material Electric Fluid Disturbed
Material Electric Fluid Disturbed
???
Now we are not using a material ether. Trust us! The equations do not need changing.
ELECTRODYNAMICISTS

Electrodynamicists' Reaction to Removal of the Material Ether

---

Published by Lotus® Freelance Graphics®



REACTION TO LOSS OF MATERIAL ETHER

Material Ether
Assumed in
Equations

Potentials,
Fields, and
Waves
Assumed
Material

Now we are not using
a material ether.
Trust us! The equations
do not need changing.

ELECTRODYNAMICISTS

Not a single
equation was
changed!

© T.E. BEARDEN 1993

Published by Lotus® Freelance Graphics®


NONMATERIAL SPACETIME
MASSLESS SPACETIME PERTURBATIONS NOT ADDRESSED
Einstein's spacetime hasn't been born yet!
~~Falsely Assumed Matter-in-Space Perturbations~~
~~MAXWELL~~
~~MAXWELL~~
1888
H
ϕ
Material Electric Fluid Disturbed
CAUSE
Material Electric Fluid Disturbed
EFFECT
???
Okay! We will just measure material entities, and call them nonmaterial.
ELECTRODYNAMICISTS
© T.E. BEARDEN 1993

Published by Lotus® Freelance Graphics®



Bunge on the Status of Electrodynamics

"... it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state..."

"... the best modern physicist is the one who acknowledges that neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling..."

*Mario Bunge, Foundations of Physics, Springer-Verlag, New York, NY, 1967, p. 176..

© 1998 T.E. BEARDEN

Published by Lotus® Freelance Graphics®



Bunge on the Status of Electrodynamics and Physics

"... it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state...

"... neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling..."

© 1998 T.E. BEARDEN

*Mario Bunge, Foundations of Physics, Springer-Verlag, New York, NY, 1967, p. 176..

Published by Lotus® Freelance Graphics®



Poynting energy flow S along two parallel conductors

Surface charges in conductors form a distributed dipole

Equipotential
lines
S
+
DIPOLE
Equipotential lines
Gradient of the dipoles
Vacuum
Flux
Exchange
Vacuum
Flux
Exchange
−
S
Equipotential
lines
© 1996 T.E. BEARDEN

Published by Lotus® Freelance Graphics®



As defined, fields and potentials only exist in and on charged matter

E ≡ F/q
S = ExH
Note problem:
No "E" or "H" in vacuum.
Source q is a broken symmetry in vacuum flux
S = ExH
SOURCE CHARGE
Assumed perpetual motion machine in classical EM
"pileup" in front
So E ≡ -∇ϕ
Point coulomb
ϕ ≡ joules continuously in geometrical flow distortion zone around a point coulomb

Electrodynamics has nothing to say about what exists in space in the absence of mass.

© 1997 T.E. BEARDEN

Published by Lotus® Freelance Graphics®



Air Medium Disturbances Generated When Air is Perturbed by a Plucked Taut String

The string wave and the holder wave never leave the string and holder respectively.

Wave is alternatively compressive and rarefactive

String slaps air medium

WAVE IN STRING (TRANSVERSE)
Lower degree of freedom for string.
Can only vibrate mostly laterally.

Drude Electron Gas waves

Nuclear proton waves

ANTIWAVE IN HOLDER
(Highly damped; not shown to scale)

Body slaps air medium

© 1990, 1995 T.E. BEARDEN

Published by Lotus® Freelance Graphics®

Launching a Spacetime Perturbation ("EM Wave") from a Wire Antenna



ANTENNA

ELECTRON SHELLS (DAMPED)

NUCLEI (HIGHLY DAMPED)

VACUUM

GRAVITON

time forward slap (electron)

time reversed slap (proton)

Modulations of virtual photon flux intensity of the QM vacuum

By omitting the nuclei perturbation wave, Maxwell omitted Newton's third law from electrodynamics

© T.E. BEARDEN 1994, 1995

Published by Lotus® Freelance Graphics®



Phase Conjugate Wavepairs Produce New Waves

TRANSVERSE EM WAVE PLUS
PHASE CONJUGATE REPLICA WAVE

LONGITUDINAL EM WAVE

LONGITUDINAL EM WAVE PLUS
PHASE CONJUGATE REPLICA WAVE

$\dot{(t)}$

SCALAR (TIME-POLARIZED)
DENSITY WAVE

*Oscillates rate of flow of time
about some average value*

© T.E. BEARDEN 1994, 1995

Published by Lotus® Freelance Graphics®



Time-Polarized (Scalar) EM Wave

Rate of flow
of local time

TIME

Amplitude vs.
observer time

© T.E. BEARDEN 1988

Time-density wave: Time flow rate
dilates and compresses rhythmically

Particle with
dense time-charge

Particle with
thin time-charge

Published by Lotus® Freelance Graphics®



Mechanism for the Flow of Time

SPATIAL
SPATIOTEMPORAL
L^2T PHOTON
SPATIAL
PHOTON
MASS
L^3
L^2 T
MASSTIME
L^3 T
MASS
L^3
© 1996, 1997 T.E. BEARDEN

$$(\Delta E)(\Delta t) + M \Rightarrow (M+\Delta M)\Delta t \Rightarrow M + (\Delta E)(\Delta t)$$

Flow of macroscopic time (observable photon interactions)

SPATIAL AND SPATIOTEMPORAL
"MASS"
MASSTIME
L^3T
MASS
MASS
MASSTIME
L^3T
"MASS"

Flow of microscopic time (via virtual photon interactions)

Published by Lotus® Freelance Graphics®



WHY PRESENT SYSTEMS HAVE COP < 1.0

Dissipative power inside source = VI_T and $VI_T > FI_L$

Other losses
emf
V
+
−
back emf
r_1
r_2
r_n
I_1
I_2
I_n
I_L
LOAD

$$I_T = I_1 + I_2 + \ldots + I_n + I_L$$

$$\text{Eff} = \frac{P_L}{P_T} = \frac{V \times I_L}{V \times I_T} = \frac{I_L}{I_T}$$

$I_T > I_L$; so Eff < 1.0

Published by Lotus® Freelance Graphics®



BRIDGING ENABLES COP > 1.0

S-flow, dϕ/dt flow, and EMF flow
V>>0
source
i ≈ 0
dQ/dt
BLOCKER
(Conductor)
V>>0
i>>0
LOAD
Closed Current Loop A
Closed Current Loop B
BRIDGE
Patent Pending
© [illegible] T.E. BEARDEN

Current loop B is asymmetrically regauged by S, dϕ/dt, and EMF flow from current loop A.

Published by Lotus® Freelance Graphics®

"Static" Poynting free-energy generator


S = E X H
capacitor
plate
+
H
–
S
capacitor
plate
E
N
permanent
magnet
S = E X H
© 1998 T.E. BEARDEN

Published by Lotus® Freelance Graphics®



Demonstration of an Overunity Concept

(By Asymmetrical Self-Regauging)

Patent Pending

Energy extracted from local vacuum and sent out as the Poynting flow
switch #1
a
b
A
C
Force on rightgoing phase
B
switch #2
b
a
+
S
source of high potential
−
spherical conducting shell
potential
Force on left-going phase

Assumptions: Capacitances of A and B very small;
Charge B large, power-free switching

© T.E. BEARDEN 1993, 1994, 1996

Published by Lotus® Freelance Graphics®


ST curvatures propagate
© T.E. BEARDEN 1993
mass perturbation (Drude Electrons)
Transmitter
mass-to-spacetime transformation
spacetime-to-mass transformation
mass perturbation (Drude Electrons)
Receiver
altered spacetime (curvatures)
altered spacetime (curvatures)
Complex of ST curvatures (vacuum engine, or spacetime engine)
Spacetime disturbance (engine) propagates

The *mass-to-mass transform* contains two hidden infolded transforms: (i) the *mass-to-spacetime transform* and (ii) the *spacetime-to-mass* transform. What is transmitted and propagates in space is a *spacetime perturbation.*

Published by Lotus® Freelance Graphics®



Mass curves and structures spacetime; ST curvatures change and structure mass

ST curvatures propagate
mass
mass-to-spacetime transformation
spacetime-to-mass transformation
mass
altered spacetime
altered spacetime
ST curvature complex (vacuum engine)
spacetime disturbance propagates

© T.E.BEARDEN 1993

Published by Lotus® Freelance Graphics®

Composition of the Scalar Potential ϕ


GALLOPING VELOCITY
Scalar Potential ϕ
...ETC.
✸ ✸ ✸ ...ETC.
V avg
Wavepair #3
HARMONICS
V avg
Wavepair #2
SUBHARMONICS
V avg
Wavepair #1
...ETC.
✸ ✸ ✸ ...ETC.
DISTANCE
© 1995 T.E. Bearden

A harmonic set of bidirectional longitudinal EM wavepairs.
Each wavepair is also a net time-polarized EM wave.

Published by Lotus® Freelance Graphics®



Lorentz Closed Surface Integration

Selects only the locally divergent portion of the Poynting energy flow that powers the component.

Only the wind on my ship is of physical significance!

© 1997 T.E. Bearden

Published by Lotus® Freelance Graphics®



Lorentz Closed Surface Integration

Using the nondivergent Poynting flow that
Lorentz integration arbitrarily discarded

How can they use that old physically insignificant wind?!!

© 1997 T.E. Bearden

Published by Lotus® Freelance Graphics®



Vacuum Engine: Working ST Demons

Internested
patterns
of spacetime
curvatures

Structured
Einsteinian
spacetime

Maxwell Demons:
EM hidden variables
Dynamic structures
at all levels

Demons work
at all levels

© 1997 T.E. Bearden

Published by Lotus® Freelance Graphics®



Undistorted Progressive Waves (UPWs)

Waves with velocity v, where ≤ v < ∞

- UPWs:
  - Translationally invariant
  - Do not spread, or reconstruct after a period
  - Have infinite energy
- Quasi UPWs:
  - Can have finite energy
  - In theory, can be launched into space
  - Can move subluminally
  - Can move superluminally

*Rodrigues and Lu, *Found. Phys.* 27(3), 1997, p. 435-508.

© 1997 T.E. BEARDEN

Published by Lotus® Freelance Graphics®



Undistorted Progressive Waves (UPWs)

Waves with velocity v, where $\leq$ v $< \infty$

- Major equations having UPW solutions:
  - *Homogeneous wave equation*
  - *Maxwell equations*
  - *Dirac, Weyl, and Klein-Gordon Equations*
- Maxwell solutions:
  - *Subluminal solutions are EM particles*
  - *Superluminal solutions are X-waves*
- Experiment indicates such waves will will be produced soon

© 1997 T.E. BEARDEN

*Rodrigues and Lu, *Found. Phys.* 27(3), 1997, p. 435-508.

Published by Lotus® Freelance Graphics®



Other Superluminal Waves

- Waves can move superluminally in quantum tunneling
- Nimtz *et al.* have translated Mozart's 40th symphony at v = 4.7 c
  - *Through a barrier in a waveguide*
  - *Other researchers have also transmitted EM waves superluminally through quantum tunneling*

© 1997 T.E. BEARDEN

Published by Lotus® Freelance Graphics®

c 1993, 1995 T.E. BEARDEN



Becker's bone fracture healing experiments

- Tiny DC currents (picoamperes)
- Pulsed DC current can be utilized
- Pulsed magnetic fields may be utilized

RED BLOOD CELL DEDIFFERENTIATES

Shucks hemoglobin coat
Grows nucleus

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes cartilage

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes bone
Deposits in fracture site, healing the fracture

© 1993, 1995 T.E. BEARDEN

Published by Lotus® Freelance Graphics®



DISEASED CELL'S DEVIATIONS FROM NORMAL ARE LITTLE SPACETIME ENGINES

change D
change N
normal engine
DYNAMIC MASS OF CELL
change A
change B
change C
longitudinal EM pump wave
change D' antiengine
change N'
normal antiengine
DYNAMIC MASS OF CELL
change A' antiengine
change B' antiengine
longitudinal EM pump wave
change C'

PRODUCING A SPECIFIC VACUUM (SPACETIME CURVATURE) ENGINE

© T.E. BEARDEN 1993

Published by Lotus® Freelance Graphics®

Transverse EM Wave Pumping of PCM


transverse
pump
wave
A_2
transverse
signal
wave
(input)
A_4
PPCM
A_3
NONLINEAR MEDIUM
transverse
pump
wave
A_1

AMPLIFIED PHASE CONJUGATE
REPLICA TRANSVERSE WAVE
(TIME-REVERSED) IS EMITTED.

*Precisely backtracks
signal wave input*

© T.E. BEARDEN 1997

Published by Lotus® Freelance Graphics®


Differentiation and Dedifferentiation Timelines
CENTRALIZED CONTROL OF CELLULAR
GROWTH AND REGENERATION
PRIMORDIAL
SINGLE
CELL
ANAEROBIC
SINGLE
CELL
AEROBIC
NORMAL HEALTHY
CELLS AND FUNCTIONS
WITH SOME DISEASED
OR DAMAGED CELLS
OXYGEN-RICH ENVIRONMENT
TIME-FORWARD PATH
AS IT DEVELOPED
© 1991, 1998 T.E. Bearden
NORMAL "DEDIFFERENTIATION"
FOR HEALING OF CELL DAMAGE
SINGLE CELL
MORE
ANAEROBIC
SINGLE
CELL
AEROBIC
TIME-REVERSED
PATH FOR
SUSTAINED
OXYGEN
DEFICIENCY
TIME-REVERSED
PATH WHEN NORMAL
PUMPING FAILS TO
HEAL CELL

Published by Lotus® Freelance Graphics®


FIRST STEP IN SELF-PROMOTION OF CANCER DUE TO HYPOXIA
MULTICELL AEROBIC* (INCLUDES MAN)
SINGLE CELL ANAEROBIC
SINGLE CELL AEROBIC*
CENTRAL CONTROL
OXYGEN-RICH
TIME-FORWARD PATH AS IT DEVELOPED
CANCER CELL
TIME-REVERSED PATH FOR SUSTAINED OXYGEN DEFICIENCY
PARTIALLY ANAEROBIC
SINGLE CELL AEROBIC
FIRST STEP IN OXYGEN-DEFICIENCY DEDIFFERENTIATION
© 1993 T.E. Bearden

Published by Lotus® Freelance Graphics®



Longitudinal EM Photon Interaction with Charge

Transverse photon
CHARGED MASS
Excited Energy Density State
Time-density (scalar) photon
Longitudinal photon
Phase Conjugate Added by Charged mass
CHARGED MASS
Excited Time Density State

© 1993 T.E. Bearden

- Fundamental units are arbitrary in physics
- Can express all physics in one unit -- e.g., time
- Time is highly compressed energy
- 1 sec = 9×10^{16} joules of transverse EM wave energy

Published by Lotus® Freelance Graphics®



Use of General Relativity (GR) in Particle Physics

© 1998 T.E. Bearden

- GR seldom used in particle physics
- In cold fusion, Matsumoto* has applied general relativity
- Consistent with important cold fusion results
- Used spacetime (ST) curvature by energy density
- Matsumoto did not utilize:
  - Longitudinal EM waves
  - Time density (time-polarized EM) waves
  - Time density curvatures of ST (gain = 9×10^{16})

* T. Matsumoto, "Mechanisms of Electro-Nuclear Collapse," Proc. ICCF-7, Vancouver, BC, Canada, Apr. 1998, p. 98.

Published by Lotus® Freelance Graphics®



Pepper* on Time Reversing Mass

- Conventional NLO interactions restricted to bosons (spin 1 particles) by Pauli exclusion principle
- Concludes electrons, protons, neutrons, etc. (fermions, or spin 1/2 particles) cannot take part in such interactions
- Perhaps time reversal possible for bosons that are multiple fermions (two protons, Helium 4, pi and K mesons, etc.)

- Time-reversal of mass demonstrated by Priore, Pautrizel, et. al. without recognizing it.** Questions exclusion for:
  - Multi-fermion reaction with EM longitudinal waves
  - Multi-fermion reaction with time-density EM waves
- Prior to the laser, NLO - though known in theory - was a gedanken experiment regarded as experimentally unviable

© 1998 T.E. Bearden

* David M. Pepper, "Nonlinear Optical Phase Conjugation," Optical Engineering, 21(12), Mar./Apr. 1982, p. 156-183.

** Before the development of NLO in the mid-to-latter 1970s.

Published by Lotus® Freelance Graphics®



Pepper* on time-reversing mass

- Conventional NLO interactions
  - *Restricted to bosons (spin 1 particles)*
  - *By Pauli exclusion principle*
- Fermions cannot take part in such interactions
  - *Electrons*
  - *Protons*
  - *Neutrons*
- Perhaps time reversal possible for multiple fermions (quasi-bosons)
  - *Two protons*
  - *Helium 4*
  - *pi and k mesons*

© [illegible]

* David M. Pepper, "Nonlinear Optical Phase Conjugation," Optical Engineering, 21(12), Mar./Apr. 1982, p. 156-183.

Published by Lotus® Freelance Graphics®



Pepper* on time-reversing mass (2)

- Time-reversal of mass demonstrated by
  - *Priore, Pautrizel, other Priore team scientists*
  - *Without recognizing it*
- Apparently n-tuple fermions, where n is even, can be time-reversed
  - *Impact of longitudinal EM waves*
  - *Impact of scalar (time-density) EM waves*
  - *Major part played by time-reversal regions*
- Prior to the laser, NLO - though known in theory - was a gedanken experiment and regarded as experimentally unviable

© [illegible] T.E. Bearden

* David M. Pepper, "Nonlinear Optical Phase Conjugation," Optical Engineering, 21(12), Mar./Apr. 1982, p. 156-183.

Published by Lotus® Freelance Graphics®

Chung's Carbon Filament Negative Resistor


UNIVERSITY AT BUFFALO, NY
© 1993 T.E. Bearden
W_{in}
CROSSED CARBON FILAMENT LAYERS
$W_{out} > W_{in}$

Published by Lotus® Freelance Graphics®



Consistency of China Lake Anomalies

- Variation in LW-TW transduction from experiment to experiment
- Majority produced insufficient transduction to cause ionization discharge of the GM tube gas (to cause detection)
- Correlation between appearance of anomalous radiation and the expected time periods to load palladium with deuterium
  - Within few hours in co-deposit experiments where palladium is loaded with deuterium as it deposits from solution
  - Required days of electrolysis for rods that load much slower
- The faster the deuterium loaded, the greater the interaction of deuterium in phase conjugating and self-targeting in lattice
- Variation in GM detector readings
  - One would read anomalous radiation, another would be blind to it
  - A few experiments gave simultaneous readings from two detectors
- Experiments perfectly consistent with LW-TW transduction, time-density charging, variation in GM time histories, and new conservation of energy law

© 1993 T.E. Bearden

Published by Lotus® Freelance Graphics®



Time-Reversal Zones in Nuclear and Chemical Reactions

- TIME REVERSAL ZONE: A volume or area in a reaction environment where phase conjugate waves predominate over time-forward waves
  - In a given reaction, time-reversal may apply
  - If so, like charges attract and unlike charges repel
  - Charges move against potential gradient, to external observer
  - Time density and longitudinal EM waves become significant
  - Coulomb barrier turns into Coulomb assistant
- Examples (assuming a time-reversed zone):

© 1998 T.E. Bearden

$$^{1}H^{+} + {}^{1}H^{+} \text{-->} {}^{2}H^{++} \text{-->} {}^{1}n + {}^{1}H^{+} \text{-->} {}^{2}H^{+} = \text{deuterium}$$

$$2({}^{1}H^{+} + {}^{1}H^{+}) \text{-->} 2\,({}^{2}H)^{++} \text{-->} 2({}^{1}n + {}^{1}H^{+})$$

$$\text{-->} 2({}^{1}n) + 2({}^{1}H)^{++}$$

$$\text{-->} {}^{4}He^{++} = \text{helium}$$

Quark flipping and energy balancing with curved spacetime assumed)

Published by Lotus® Freelance Graphics®



The Electronuclear Reaction: Nuclear Reactions in TR-Zones (1)

- Nucleon interchange
  - Changes neutron into proton and vice versa
  - At high rate (flat spacetime assumed)
- Statistics become skewed due to curved ST
- Can bias statistics toward either neutron or proton end
  - Biases toward transmutation of elements along isomer chains
  - Concept of "isomer" is vastly expanded

Published by Lotus® Freelance Graphics®



The Electronuclear Reaction: Nuclear Reactions in TR-Zones (2)

- Normal dynamics (impulses) may reverse
  - *Like charges attract, unlike charges repel*
  - *Positive charges cluster (are drawn together)*
  - *H+ ions (protons) may form quasi-nuclei*
  - *Nucleus coulomb barrier becomes assistant*
- Many "impossible" reactions now possible
  - *Quark access and quark flipping by EM*
  - *Ion clustering*
  - *Positive charges as phase conjugate mirrors*
  - *Time-density waves and time-energy charging*

Published by Lotus® Freelance Graphics®



The Electronuclear Reaction: Nuclear Reactions in TR-Zones (3)

- Not observed until time-energy charging has become substantial
  - *Time delay (hours, days)*
  - *Transduction of LW --> TW involved*
  - *Specific time-charging history of detectors is involved in twhether they detect or not*
  - *Longitudinal EM waves become significant*
- Curved spacetime can act as source or sink
  - *May emit excess radiation*
  - *May absorb excess radiation*

Published by Lotus® Freelance Graphics®



On Nuclear Reactions in TR-Zones

- Nuclear interactions now are biased:
  - Normal nucleon interchange changes neutron into proton and vice versa, at a high rate (flat spacetime assumed)
  - Statistics now become skewed due to curved spacetime
  - Can bias statistics toward either the neutron end or proton end
  - Thus biases toward transmutation of elements along isomer chains
  - Concept of "isomer" vastly expanded
- Normal dynamics (impulses) may be reversed
  - Coulomb barrier becomes coulomb assistant
  - Reactions "impossible" from energy density standpoint become possible, even easy, from time-density standpoint
- Does not become significant until sufficient time-density charges
  - Time-delay (hours, days) before TR reactions become significant
  - Transduction of LW-->TW involved
  - Specific time-history of detectors is significant
  - longitudinal EM waves become significant
- Curved spacetime acts as source or sink
  - Energy balance in curved spacetime may emit excess radiation
  - Energy balance in curved spacetime may absorb excess radiation

© 1998 T.E. Bearden

Published by Lotus® Freelance Graphics®



In Time-Reversed Zone:
Nuclear reactions are biased

- In normal flat ST, n ⇔ p at high rate
- Curved ST skews statistics
- Biases to either n or p
- Biases to transmutation along isomer chain
- "Isomer" concept greatly expanded

© 1998 T. E. BEARDEN

Published by Lotus® Freelance Graphics®



In Time-Reversed Zone:
Dynamics may be reversed

- Like charges may attract and unlike charges repel
- Coulomb barrier becomes Coulomb assistant
- Clusters like charges and forms artificial nuclei
- "Impossible" nuclear reactions at low energy
- Time-density interactions

© 1998 T.E BEARDEN

Published by Lotus® Freelance Graphics®



Time-Reversed Zone:

Significant only after time-density charging

- Hours, for "fast" onset
- Days, for "slower" onset
- Transduction involved for TW ⇔ LW ⇔ TDW
- Time-history of each detector is significant
- Longitudinal EM waves become significant

© 1998 T.E. BEARDEN

Published by Lotus® Freelance Graphics®



Curved Spacetime acts as source or sink

- May emit excess radiation and energy (e.g., heat)
- May absorb radiation and energy (e.g., cool)
- May transduce waves TW $\Leftrightarrow$ LW $\Leftrightarrow$ TDW
- New energy conservation law applies

© 1998 T.E. BEARDEN

Published by Lotus® Freelance Graphics®



Anomalous LW EM Emission Phenomena at China Lake (1)

- Anomalous radiation from electrolysis in ionization processes
  - Two experiments producing excess power
  - Dental X-ray film showed exposure
  - Simultaneous control study: no exposure
  - 20 experiments without excess power: no exposure
- Excess energy strongly indicates excess film exposure

© 1998 T.E. Bearden

* Melvin H. Miles and Benjamin F. Bush, "Radiation Measurements at China Lake: Real or Artifacts?" Proc. ICCF-7, Vancouver, BC, Canada, Apr. 1998, p. 101.

Published by Lotus® Freelance Graphics®



Anomalous LW EM Emission Phenomena at China Lake (2)

- **GM and NaI detector reaction when electrolysis with heavy water ongoing**
  - Several Geiger-Muller (GM) tubes gave anomalous detection
  - Reached 73 sigma above background
  - No anomalies when experiment off
- ***GM tube detects anything which causes its internal ionization***
  - *Nuclear radiation is ionizing*
  - *Transduced x-ray & gamma is ionizing*

Published by Lotus® Freelance Graphics®



Sufficient LW-to-TW Transduction Ionizes GM Tube Gas (3)

- **Time-history of detector involved**
  - Some GM detectors show anomalous high counts, some do not
  - Time histories of GM detectors are varied
  - Time histories of film vary minimally
- ***Experimental results consistent with***
  - *LW-to-TW transduction including delay*
  - *Time-energy charging*
  - *New extension to energy conservation law*

Published by Lotus® Freelance Graphics®



Sufficient LW-to-TW Transduction Ionizes GM Tube Gas (4)

- **Time-history of detector involved**
  - Some GM detectors show anomalous high counts, some do not
  - Time histories of GM detectors are varied
  - Time histories of film vary minimally
- ***Experimental results consistent with***
  - *LW-to-TW transduction including delay*
  - *Time-energy charging*
  - *New extension to energy conservation law*

Published by Lotus® Freelance Graphics®



Consistency of Anomalies

- LW-to-TW transduction varied from experiment to experiment
- Most experiments produced insufficient transduction to cause ionization
- Appearance of anomalous radiation correlated with expected time loading of palladium with deuterium
  - Within few hours in experiments where palladium loads with deuterium as it deposits from solution
  - Required days for rods that load much slower

© 1998 T.E. Bearden

Published by Lotus® Freelance Graphics®



Consistency of Anomalies (2)

- Faster the deuterium loaded, the greater the interaction of deuterium in
  - Phase-conjugating and self-targeting
  - Producing time-reversal zones
  - Generating quasi-nuclei of H+ ions (protons)
- Variation in GR detector readings
- Experimental results predictable by
  - LW-TW transduction and time-reversal zones
  - Varying time-density charging on GM tubes
  - Variation in GM tube experience histories
  - Time-reversal zones generating electronuclear interactions and quasi-nuclei of H+ clusters

© 2003 T.E. Bearden

Published by Lotus® Freelance Graphics®



Experimental LW Emission Phenomena in Electrolysis

- Anomalous radiation from electrolysis in ionization processes
  - Two experiments producing excess power
  - Dental x-ray film showed exposure
  - Simultaneous control study: No exposure
  - 20 experiments without excess power: No exposure
- Excess energy strongly indicates excess film exposure
- GM and NaI detector reaction when electrolysis ongoing w/heavy water
  - Several Geiger Muller (GM) tubes gave anomalous detection
  - Reached 73 σ above normal background counts
  - No anomalies when experiment off
- GM tube detects anything which causes its internal gas to ionize
  - Nuclear radiation is "ionizing" radiation
  - Transduced x-ray and gamma radiation is "ionizing" radiation
  - Sufficient LW-TW transduction ionizes GM gas
- Time History of detector involved
  - Some GM detectors show anomalous high counts, some do not
  - Time histories of GM detectors vary appreciably
  - Time histories of film vary minimally
- Experiments consistent with time-density charging, LW-TW transduction, and new conservation of energy law

© 1998 T.E. Bearden

* Melvin H. Miles and Benjamin F. Bush, "Radiation Measurements at China Lake: Real or Artifacts?" Proc. ICCF-7, Vancouver, BC, Canada, Apr. 1998, p. 101.

Published by Lotus® Freelance Graphics®



A New Conservation of Energy Law

- Physics conserves total "energy and mass-energy"
- Now also must consider "time-energy"
- Conserve total mass-time-energy (spatiotemporal energy)
- Let E_T = total energy, E_M = mass energy, E_E = ordinary energy, and E_t = time energy. Then

$$E_T = E_E + E_M + E_t$$

$$(kE_t \Rightarrow E_E > 0) \Rightarrow E_T > (E_M + E_E)$$

- If some E_t is transduced into E_E , the experiment will violate the old spatial mass-energy conservation law

Published by Lotus® Freelance Graphics®



QUESTIONS ON CARCINOGENS AND EM RADIATION

- UNRESOLVED QUESTIONS ON EM RADIATION
  - DOSAGES
  - ACTIVE MECHANISMS
  - REPLICATION DIFFICULTIES
  - MEASUREMENT DIFFICULTIES
  - WHERE, WHEN, HOW ILL EFFECTS OCCUR
- SIMILAR QUESTIONS EXIST ABOUT EVERY CARCINOGEN
- SCIENCE REALLY DOES NOT UNDERSTAND THE MECHANISMS OF A SINGLE CHRONIC DISEASE, INCLUDING CANCER
  - FACTORS SUCH AS MIND, STRESS, SPONTANEOUS REMISSION, PLACEBO EFFECTS, AND COMBINATIONS OF FACTORS ARE PARTICULARLY TROUBLESOME
  - GENERATION OF THE PLACEBO EFFECT BY THE REGENERATION & RECOVERY SYSTEM IS UNRECOGNIZED

© 1994, 1996 T.E. Bearden

Published by Lotus® Freelance Graphics®



QUESTIONS ON CARCINOGENS AND EM RADIATION

- UNRESOLVED QUESTIONS ON EM RADIATION
  - DOSAGES
  - ACTIVE MECHANISMS
  - REPLICATION DIFFICULTIES
  - MEASUREMENT DIFFICULTIES
  - WHERE, WHEN, HOW ILL EFFECTS OCCUR
- SIMILAR QUESTIONS EXIST ABOUT EVERY CARCINOGEN

© 1994, 1995 T.E. Bearden

Published by Lotus® Freelance Graphics®



CHRONIC DISEASE PUZZLING

- SCIENCE REALLY DOES NOT UNDERSTAND THE MECHANISMS OF A SINGLE CHRONIC DISEASE, INCLUDING CANCER
- MANY TROUBLING FACTORS EXIST
  - *MIND*
  - *STRESS*
  - *SPONTANEOUS REMISSION*
  - *PLACEBO EFFECTS*
  - *COMBINATIONS*
- GENERATION OF THE PLACEBO EFFECT BY THE CELLULAR REGENERATION SYSTEM IS UNRECOGNIZED

© 1994, 1995 T.E. Bearden

Published by Lotus® Freelance Graphics®



Cancer Characteristics

- Not one disease, but a whole range
- Starts in damaged aerobic cell
- Cell shakes off body's central control
  - Starts uncontrolled division
  - Becomes a lump
- Can send forth cancer cells
  - Through blood
  - Through lymph
- Form metastases (secondary tumors)
- Often become anaerobic

Published by Lotus® Freelance Graphics®



Solving a Cancer Enigma

- An enigma has been failure of immune system to attack some tumor cells
  - Suppressor cells may curb immune system?
  - Tumor may lack antigens normally identified by the immune system?
- *Promotion of damaged cell to cancer is usually ordered by cellular control system*
  - *Regenerative and recovery system forces cell back toward anaerobe*
  - *First step breaks free from central growth*
  - *Control continues to recognize cell as self*

Published by Lotus® Freelance Graphics®



CANCER: CHARACTERISTICS

- NOT ONE DISEASE BUT A WHOLE RANGE
- STARTS IN ORDINARY (AEROBIC) CELL
- CELL SHAKES OFF BODY'S DICTATORIAL CONTROL*
- STARTS UNCONTROLLED DIVISION
- BECOMES A LUMP
- CAN SEND FORTH CANCER CELLS
  - THROUGH BLOOD
  - THROUGH LYMPH
- THESE FORM METASTASES (SECONDARY TUMORS)
- OFTEN BECOME ANAEROBIC (NON-OXYGEN USING)
- ENIGMA IS FAILURE OF IMMUNE SYSTEM TO ATTACK SOME TUMOR CELLS
  - SUPPRESSOR CELLS MAY CURB IMMUNE SYSTEM
  - TUMOR MAY LACK ANTIGENS NORMALLY IDENTIFIED BY THE IMMUNE SYSTEM

R&R system forces cell back toward anaerobe

© [illegible] E.Borden

Published by Lotus® Freelance Graphics®



PORTABLE PRIORE TECHNOLOGY UNIT

- FACT: DISEASE-SPECIFIC VACUUM ENGINE PRESENT FOR ANY CELLULAR DISEASE, BY WHEELER'S PRINCIPLE
  - *DISEASE CAN BE REVERSED BY CREATING AMPLIFIED VACUUM ANTI-ENGINE (BEARDEN'S PRINCIPLE)*
  - *ANTI-ENGINES CREATED BY PUMPING THE NONLINEAR CELLS WITH LONGITUDINAL EM WAVES*
- PRIORE UTILIZED A PLASMA TO PHASE CONJUGATE AND "INFOLD" MULTIPLE BIDIRECTIONAL LONGITUDINAL EM PUMP WAVES
  - *MULTIPLE FREQUENCIES MIXED IN A ROTATING PLASMA*
  - *PHASE CONJUGATES ADDED BY THE PLASMA*
  - *INFOLDED MIX INTO STRONG PULSED DC MAGNETIC FIELD, WHICH CARRIED IT INTO ATOMIC NUCLEI*
  - *PUMPED ALL NONLINEAR CELLULAR COMPONENTS TO PRODUCE AMPLIFIED, SPECIFIC VACUUM ANTI-ENGINE*
- NEGATED THE CUMULATIVE CELLULAR DEDIFFERENTIATION ORDER GENERATED BY LONG-TERM HYPOXIA. TUMOR CELLS REVERTED TO NORMAL CELLS.
- SCRUBBED OUT CUMULATED PRECANCEROUS STATE
- RESTORED THE IMMUNE SYSTEM TO HIGH FUNCTIONING
- NO EXCESSIVE TRAUMA TO TREATED ANIMAL

© [illegible] T.E. BEARDEN.

Published by Lotus® Freelance Graphics®



Lisitsyn's Report: Brain Code Broken

- THEORY DEVELOPED AND FITTED
- HYSTERESIS MEMORY LOOP
- CONTROLLED EM INDUCTION
  - IMAGES
  - SENSATIONS
  - PREDETERMINED EMERGENCE
- 23 EEG BANDS
  - UP TO 8.1×10^{20} HZ
  - 11 INDEPENDENT CHANNELS

© 1977, 1985, 1991 T.E. BEARDEN

S.E. Lisitsyn, "New Approach to the Analysis of Electroencephalograms," DDC Report AD73005, p. 16-25.

Published by Lotus® Freelance Graphics®



ANTI-ENGINE FOR CELL'S DEVIATION REVERSES CELL BACK TO NORMAL

PHYSICAL
CELL
(DISEASED)
+
EXTENDED
TIME DELAY FOR
RENORMALIZATION
PHYSICAL
CELL
(NORMAL)
VACUUM
ENGINE
FOR DISEASED
CELL
VACUUM/SPACETIME
ANTI-ENGINE FOR
CELL'S DISEASE DELTA
© [illegible] T.E. BEARDEN

By pumping the internal EM channel, process is dramatically accelerated.
This is the body's normal recovery mechanism, within its limits.

Published by Lotus® Freelance Graphics®

Priore's Therapeutic Methodology

Time-reverses the cells back to normal state


START
SELECT A SET OF TRANSVERSE EM WAVES
MIX WAVES IN A PLASMA TO ADD CONJUGATES
MIX OUTPUT INSIDE STRONG PULSED DC MAGNETIC FIELD
EXPOSE WHOLE BODY OF PATIENT TO DIMENSIONED MAGNETIC FIELD
CELL AND ALL ITS PARTS ARE PUMPED IN INNER EM CHANNEL IN TIME DOMAIN
VACUUM ENGINE FOR DISEASED CELL ALREADY PRESENT
DISEASED CELL PHASE CONJUGATES ITS VACUUM ENGINE
FORMS AMPLIFIED VACUUM ANTIENGINE FOR CELL'S DISEASE VACUUM ENGINE
ADJUST WAVE FREQUENCIES IF REQUIRED, AND IRRADIATE AGAIN
NO
CELL RESTORED TO NORMAL?
YES
STOP
ANTIENGINE CONTINUES TO ACT AND TIME-REVERSE CELL AND ALL ITS PARTS*
TIME-EXCITATION CHARGING ENDS. IRRADIATION IS HALTED.
*Includes genetics

Published by Lotus® Freelance Graphics®


Priore's Therapeutic Methodology
START
FORM A SET OF HARMONIC EM WAVES
ADJUST SOME WAVES OFF FREQUENCY
MIX WAVES IN A PLASMA TO ADD CONJUGATES
MIX OUTPUT ONTO STRONG RIPPLING MAGNETIC FIELD
EXPOSE WHOLE BODY OF PATIENT TO THE RIPPLING MAGNETIC FIELD
CELL AND ALL ITS PARTS ARE PUMPED IN INNER EM CHANNEL
VACUUM ENGINE FOR DISEASED CELL ALREADY PRESENT
DISEASED CELL PHASE CONJUGATES ITS VACUUM ENGINE
FORMS AMPLIFIED VACUUM ANTIENGINE FOR CELL'S DISEASE VACUUM ENGINE
TIME REVERSES CELL AND ALL ITS PARTS*
CELL RESTORED TO NORMAL?
NO
YES
STOP
*Includes genetics
© 1994 T.E. BEARDEN

Published by Lotus® Freelance Graphics®



Pumping with Longitudinal EM Waves Time-reverses the Mass

vacuum (spacetime) engine in the mass is the input

AN AMPLIFIED VACUUM (SPACETIME) ANTIENGINE IS FORMED AND ACTS ON THE MASS, TIME-REVERSING IT AND ALL ITS COMPONENTS NO MATTER HOW SMALL

CELL MASS

highly nonlinear to any and all LW frequencies

Antiengine acts upon mass at all levels

A 2
A*2
longitudinal EM pump wave
MASS previous state
A4
Type text
Type text
A3
longitudinal EM pump wave
A1
A*1
© T.E. BEARDEN 1997

Published by Lotus® Freelance Graphics®



Extension to nonlinear optical pumping

© T.E BEARDEN 1997

transverse pump wave
A 2
transverse signal wave (input)
A 4
PPCM
A 3
NONLINEAR MEDIUM
amplified phase conjugate replica transverse wave (time-reversed)
transverse pump wave
A 1
PREVIOUS VACUUM ENGINE
PREVIOUS MASS STATE
+ t
TIME AXIS
A 2
VACUUM ENGINE
AMPLIFIED VACUUM ANTIENGINE
MASS
A 1

a. Pumping with transverse EM waves produces a time-reversed ***wave***.

b. Pumping with longitudinal EM waves A_1 and A_2 time-reverses ***the mass itself***.

Published by Lotus® Freelance Graphics®

Time Reversal of a Mass to a Form not in its past


VACUUM ENGINE A'
VACUUM ENGINE (A' +B')
© T.E. BEARDEN 1997
VACUUM ENGINE B'
TIME AXIS A
A2
MASS
TIME AXIS (A+B)
TIME AXIS B
AMPLIFIED VACUUM ANTIENGINE (A' + B')
VACUUM ENGINE B
VACUUM ENGINE A
A + B
A1

Published by Lotus® Freelance Graphics®


ADD PUMPS
B
PRIORE AMPLIFIED PUMPING
RESIDENT VACUUM ENGINE
CELL AS A PHASE CONJUGATE MIRROR
ANTIENGINE PRESENT?
N
Y
APPLY ANTIENGINE
B
A
START
A
CYCLE
CELL AND INTERIOR SENSORS
LOCAL VICINITY SENSORS
NONLOCAL ALL-BODY SENSORS
DELTA CATALOGS
CELLS AND INTERIORS
SELECT LOCAL
SELECT NONLOCAL
AEROBE
ANAEROBE
N
Y
DELTA?
N
Y
DELTA?
N
Y
DELTA?
AEROBE
ANAEROBE
AEROBE
ANAEROBE
AEROBE
ANAEROBE
SWITCH TO AEROBE CONTROL SYSTEM
A
Y
CROSS THRESHOLD BACK TO AEROBE?
N
SWITCH COMPARATIVE CATALOG
SWITCH TO ANAEROBE CATALOG
Y
END OF AEROBE CATALOG?
N
SUM FOR ENTIRE BODY
SWITCH ON CENTRAL, OFF DECENTRAL GROWTH CONTROL; RESET IMMUNE SYSTEM
SWITCH OFF CENTRAL GROWTH CONTROL
SWITCH ON DECENTRAL GROWTH CONTROL
CONDITION IMMUNE SYSTEM TO ACCEPT
A
R&R SYSTEM
Regeneration Example
© T.E. BEARDEN

Published by Lotus® Freelance Graphics®


Portable Priore-Type Treatment System
Equipment Case
Computer Control Unit
Infolding Function Generator
Antenna Pad

Published by Lotus® Freelance Graphics®


Portable System Block Diagram
Power Supply
Computer Control Unit
Frequency Generators
Infolding Function Generator
Field Sensor Unit
Magnetic Pulse Generator
Plasma Mixing Unit
Antenna Pad
Antenna Pad

Published by Lotus® Freelance Graphics®



Absorption and emission reactions

ELECTRON ABSORBS PHOTON ENERGY, MOVES TO HIGHER ENERGY LEVEL. DECAYS BY EMITTING PHOTON

ELECTRON ABSORBS TIME DENSITY, MOVES TO DIFFERENT TIME DENSITY LEVEL. DECAYS BY EMITTING LONGITUDINAL OR PSEUDOLONGITUDINAL PHOTON

© T.E. BEARDEN 1988

PARTICLE ABSORBS ENERGY, MOVES TO HIGHER ENERGY SHELL. DECAYS BY EMITTING ENERGETIC PARTICLE, OBSERVABLE..

PARTICLE ABSORBS TIME, MOVES TO HIGHER TIME DENSITY. DECAYS BY EMITTING TIME-LIKE PARTICLE, NONOBSERVABLE BY PRESENT MEANS.

ENTIRE NUCLEUS ABSORBS ENERGY, EACH PARTICLE ABSORBS OWN. DECAY OCCURS BY COMPLEX MODES, INCLUDING FISSION OR FUSION. DECAY BYPRODUCTS OBSERVABLE.

ENTIRE NUCLEUS ABSORBS TIME, EACH PARTICLE ABSORBS OWN. DECAY OCCURS BY COMPLEX MODES, INCLUDING FISSION OR FUSION. SOME DECAY BYPRODUCTS ARE NONOBSERVABLE (SPACE ABSORBS)

Published by Lotus® Freelance Graphics®



Absorption and emission reactions

TRANSVERSE PHOTON

ELECTRON ABSORBS PHOTON ENERGY, MOVES TO HIGHER ENERGY LEVEL. DECAYS BY EMITTING PHOTON, REMOVING Δt

ΔE
nucleus
Δt coupled and emitted quickly

STREAM OF TIME-POLARIZED PHOTONS

ELECTRON ABSORBS TIME DENSITY, MOVES TO $1/c^2$ DIFFERENT TIME DENSITY LEVEL. DECAYS BY EMITTING LONGITUDINAL OR PSEUDOLONGITUDINAL PHOTONS

Δt
nucleus
Δt increases quasi-statically then slowly decays

Figure A. Excited energy density level in one jump.

Figure B. Excited time density level significant only after enormous number of increases.

© T.E. BEARDEN 1988

Published by Lotus® Freelance Graphics®



Some EM Waves in Spacetime

SPACE

TIME

GALLOPING WAVE. TRANSVERSE WAVE THAT VARIES VELOCITY ALONG Z-DIRECTION, IN WAVE FASHION. (Ex: 0.01 c - 100 c)

TIME-POLARIZED (TIME-ENERGY) OSCILLATIONS

3-SPATIAL ENERGY DENSITY OSCILLATIONS

SCALAR WAVES. X, Y, Z FIXED. T VARIES. NONOBSERVABLE.

TRANSVERSE WAVES. X AND Y ENERGY DENSITY VARIES; Z FIXED.

TRANSDUCTION

TIME DENSITY OSCILLATIONS. X,Y, Z ENERGY DENSITY DO NOT VARY.. TIME DENSITY VARIES ALONG TIME DENSITY NOT OBSERVABLE, BUT TRANSDUCTION IS OBSERVABLE.

PSEUDO-LONGITUDINAL WAVES. X AND Y VARY A LITTLE, SURGE OSCILLATIONS IN Z DIRECTION.

TIME DENSITY OSCILLATIONS. X,Y, Z ENERGY DENSITY FIXED. TIME DENSITY IS NONOBSERVABLE, BUT TRANSDUCTION IS OBSERVABLE.

LONGITUDINAL WAVES. X AND Y FIXED; SURGE OSCILLATIONS IN Z DIRECTION.

TRANSDUCTION

© T.E. BEARDEN 1998

Published by Lotus® Freelance Graphics®



Evolution of Cells on Earth

ESSENTIALLY ANAEROBIC ATMOSPHERE

BIOGENESIS

SINGLE CELL ANAEROBIC

CHANGE OF ATMOSPHERE TO AEROBIC (INCLUDES OXYGEN)

OBLIGATORY ANAEROBES SINGLE CELL SHIELDED FROM OXYGEN

FACULTATIVE ANAEROBES (SINGLE CELL BOTH AEROBIC AND ANAEROBIC)

EVOLVE TO

SINGLE CELL AEROBIC*

EVOLVE TO MULTICELL AEROBIC* (INCLUDES MAN)

CENTRAL CONTROL

SINGLE CELL COMPONENTS

IMMUNE SYSTEM
RED CELLS
WHITE CELLS
KILLER CELLS
ETC.

MULTICELL COMPONENTS

TISSUES
MUSCLES
BONES
ORGANS
SKIN
STRUCTURES

* NOTE: LIMITED ANAEROBIC RESPIRATION STILL TAKES PLACE IN HIGHER AEROBIC LIFE FORMS, INCLUDING MAN.

EVOLUTIONARY TIME

© 1998 T. E. BEARDEN

Published by Lotus® Freelance Graphics®



Becker's theoretical control system governing regeneration*

Trauma Producing Tissue Loss

Local cellular effect

Local nerve effect

CNS effect

Alterations in hormone pattern (prolactin)

Alterations in local DC field pattern

Local electrical effects

Local and systemic pools of target cells

Dedifferentiation into primitive mesenchymal cells

Phase I

Blastema formation

growth

Phase II

Redifferentiation into required cell types

Restoration of body part or tissue

*Becker & Spadaro, "Electrical stimulation of partial limb regeneration in mammals," Bull. N. Y. Acad. Med, 48(4) May 1972, p. 625.

Published by Lotus® Freelance Graphics®



Becker's theoretical DC control system involved with response to injury*

INJURY

INPUT STIMULATION DC SYSTEM (PAIN)

CENTRAL DC SYSTEM

OUTPUT DC SYSTEM

LOCAL CELL INJURY FREE RADICALS

TOTAL CURRENT OF INJURY DC SYSTEM

STIMULATION OF REPAIR CELLS

MITOSIS DEDIFFERENTIATION

GROWTH DIFFERENTIATION

*Robert O. Becker, "The significance of bioelectrical potentials," Bioelectrochemistry and Bioenergetics, Vol. 1, 1974, p. 191.

Published by Lotus® Freelance Graphics®



Published by Lotus® Freelance Graphics®



"Time as fuel" is the future

- Present energy science is insufficient
- Eventually will use energy locked up in time itself
- Cold fusion will provide entrée
- Cold fusion has evidence of time-as-energy
- Theorists and experimentalists should examine the implications
- Must revise foundations of Electrodynamics

© 1998 T. E. BEARDEN

COLD FUSION
(TIME AS
ENERGY
AND FUEL)

Published by Lotus® Freelance Graphics®

A National Report on America's Energy Crisis

Remarks by U. S. Secretary of Energy Spencer Abraham

U. S. Chamber of Commerce, National Energy Summit March 19, 2001

Opening Remarks

I would like to congratulate the U. S. Chamber of Commerce for convening this two-day National Energy Summit and I appreciate your invitation to participate. As we all know, the topic of energy is as timely as the day's headlines. In just my first eight weeks as Energy Secretary, California has faced almost daily power alerts. Rising natural gas prices have punished consumers with bills that, in some cases, are double or triple last winter's. And forecasts for this summer suggest the possibility of rolling blackouts.

The good news is that America's energy problems can be solved. The bad news is that the situation in California is not isolated, it is not temporary, and it will not fix itself.

America faces a major energy supply crisis over the next two decades. The failure to meet this challenge will threaten our nation's economic prosperity, compromise our national security, and literally alter the way we live our lives.

America has heard these dire warnings before - in fact, they seem to be a recurring theme in our nation's energy discussion, almost since "Colonel" Drake made the first oil strike near Titusville, Pennsylvania in 1859. "The amazing exhibition of oil," advised the State Geologist of Pennsylvania, "[is] a temporary and vanishing phenomenon-one which young men will live to see come to its natural end. " That was in 1885.

Around the same time, John Archbold - who succeeded John D. Rockefeller as head of Standard Oil - joked about the prospects for oil discoveries in Oklahoma: "Are you crazy?" Archbold said. "I'll drink every gallon produced west of the Mississippi. "

I don't know if anyone ever called Mr. Archbold on that pledge. But for whatever reason, in 1914 the U. S. Geological Survey predicted that the U. S. would soon exhaust its available oil supplies. They issued the same warning in 1926. And again in 1939. And in 1949.

All of these warnings have proven false. Despite all these expert predictions, the world has not run out of oil or other resources. And yet here we are, faced with the most serious energy shortage since the days of oil embargoes and gas lines.

My point is, America's current energy supply crisis is not due to some inevitable neo-Malthusian depletion of resources. The United States - and our North American and hemispheric neighbors-are blessed with a rich abundance of natural resources. It's political leadership that has been scarce.

For the past eight years, Washington sat on the sidelines as our nation's energy needs mounted. During the 1990s, the Clinton Administration employed a policy of taxing demand, limiting supply, and ignoring the rapidly expanding needs of the future.

Their energy strategy boiled down to: you can't find it . . . you can't transport it . . . and even if you get it, we don't want you to use it.

Through neglect or complacency or ideology, this approach has led us to the crisis we face today.

The Bush Administration is fully prepared to respond to the broad set of challenges we inherited. But we must be candid with the American people about the magnitude of the problem - which is what I'd like to talk about today.

America's Energy Supply Challenges

Three overriding facts starkly define the challenge of America's energy needs over the next two decades:

First, demand for energy is rising across the board, but particularly for natural gas and electricity;

Second, supplies are being limited by a regulatory structure that, in many respects, has failed to keep pace with advances in technology and an uncertain political environment that often discourages investment in desperately needed facilities;

And third, our energy infrastructure - that network of the generators, transmission lines, refineries and pipelines that convert raw resources into usable fuel - is woefully antiquated and inadequate to meet our future needs.

Unless these challenges are addressed, America's energy supply will be continually at risk . . . our citizens will encounter blackouts and other lifestyle-altering disruptions . . . and our economy will be hobbled by rising energy prices. Let me briefly outline some of the major issues on the horizon:

Oil: Rising Consumption, Accelerating Dependence

In the next 20 years, according to estimates by the Energy Information Administration, America's demand for oil is projected to increase by 33 percent. Yet as consumption surges, U. S. production continues to drop precipitously. We now produce 39 percent less oil than we did in 1970, losing nearly 4 million barrels a day in the process. And unless energy policy is changed, production will slip further - to just 5.1 million barrels per day by 2020 - down from a high of 9. 4 million a day 30 years ago. This widening gap between demand and domestic supply will make us increasingly dependent upon foreign imports. Back in 1973-at the height of the oil crisis - America imported just 36 percent of its oil from abroad.

Today, we import 54 percent. And, if we allow this trend to continue, we will soon be forced to look abroad for some 64 percent of our oil. This will put more power in the hands of foreign suppliers - power they are not reluctant to use, as we just saw when the OPEC cartel decided to reduce oil output by one million barrels a day.

While this administration does not agree with OPEC's decision, that decision demonstrates the importance of increasing America's production of oil. Securing an affordable, reliable and adequate supply of crude is a critical challenge. But it is only half the oil story.

Since 1980, the number of American refineries has been cut in half. There hasn't been a new refinery built in the United States in over 25 years. New regulatory interpretations limit the ability of existing refineries to expand capacity. Add to that regulations that require the production of more than 15 different types of gasoline-and you have a refining industry strained to capacity, leaving us dangerously vulnerable to regional supply disruptions and price spikes.

Refineries are so constrained that when President Clinton made the politically symbolic gesture of releasing 30 million barrels of oil from the Strategic Petroleum Reserve last fall, that oil had to be shipped overseas to be refined.

Natural Gas: Rapidly Rising Demand; Constraints on Supply

Many of the same issues confront the future of natural gas. America's demand for natural gas is projected to rise even more rapidly than oil. If Department of Energy projections are correct, by 2020 Americans will consume 62 percent more natural gas than we do today. More than 9 out of 10 of the announced new electric generating plants will be fired by natural gas.

This approaching wave of new demand begs the question: Do we have an energy policy and a regulatory structure capable of meeting our natural gas needs?

Consider just a few constraints in this market.

Right now, an estimated 40 percent of potential gas resources in the United States are on federal lands that are either closed to exploration or covered by severe restrictions. The last lease sale in the some areas of the Gulf of Mexico was more than a decade ago. New discoveries of natural gas in the United States have fallen for three straight years, creating increasing pressure for more imports.

The notion that we can rely so heavily on natural gas . . . maintain severe restrictions on exploration . . . and still enjoy low prices is a dangerous assumption.

Even if we find the supplies, moving that gas to market will require an additional 38,000 miles of transmission pipeline and 255,000 miles of distribution lines-at an estimated cost of $120-$150 billion.

Today's pipeline system can hardly handle the supplies we know exist. Alaska's Prudhoe Bay, for example, produces about 8 billion cubic feet of natural gas a day - approximately 13 percent of America's daily consumption.

But that gas never reaches the market. Instead, it is just pumped back into the ground, waiting until a pipeline is built to connect the Alaska fields to the U.S./Canada distribution system.

Electricity: Powering the Information Economy

As everyone knows, we also face a real challenge in generating enough electricity to light out homes and run our businesses. Over the next 20 years, the Department of Energy estimates that electricity demand in the United States will increase by 45 percent. That rising growth rate will require the construction of over 1,300 new power plants-about 65 every year.

Yet, the last time we added that much power was 1985.

Furthermore, there is reason to believe that this could turn out to be a conservative estimate. During the 1990s, electricity consumption far outstripped projections, driven by the energy-hungry information economy. Some experts calculate that the demands of the Internet already consume some 8-13 percent of electricity. If demand grows at just the same pace as during the last decade, we'll need nearly 1,900 new plants by 2020-or more than 90 every year-just to keep pace.

Hundreds of new generating plants will place even greater pressure on our already strained and aging power grid. America's network of transmission lines, substations and transformers was built when utilities were tightly regulated monopolies providing service to assigned regions. Interconnections between suppliers were strictly an emergency backup measure to guard against rare service interruptions. The system was simply not designed for long-haul swapping of power in a highly competitive market.

Consumers are already feeling the impact of a transmission systems stressed by rising demand. Transmission bottlenecks contributed to the blackouts that have swept through California and to price spikes in New York City last summer that cost consumers an estimated $100 million.

Coal, Nuclear, and Hydro-Electric Power

Coal has historically been American's number one source for affordable electricity; it currently powers half of America's electricity generators. And at today's recovery rates, our nation has enough coal to keep those plants running for the next 250 years.

Coal generators have already been called upon to make broad reductions in emissions. The Bush Administration supports those efforts-and we will back it up with greater incentives for investment in clean coal technology.

But the administration will not regulate coal out of existence . . . and we will not support measures that will threaten electricity supplies and significantly raise electricity prices. President Bush made the right decision last week not to impose new federal mandates on the emissions of carbon dioxide. If America is to have reliable electricity over the next 20 years, coal must continue to play a major role.

But, coal is not the only energy source facing an uncertain future. There hasn't been a new nuclear power plant permit granted since 1979. Many of the 103 existing nuclear plants are not even expected to file for a renewal of their licenses as they expire over the next 15 years.

Even hydroelectric power generation is expected to fall sharply.

Re-licensing a hydro facility can take a decade or more and cost millions. And now, even though consumers are faced with potential blackouts and chronic electricity shortages in the West, activists and some political leaders want to breach one or more of the four federal dams on the Snake River to help young salmon, on their trek to the sea.

The Dangers of Complacency

What are the dangers of complacency in light of these challenges? How does it all add up for our economy and our citizens?

This nation's last three recessions have all been tied to rising energy prices - and there is strong evidence that the latest crisis is already having a negative effect.

The National Association of Manufacturers estimates that soaring fuel prices between 1999 and 2000 cost the U.S. economy more than $115 billion-shaving a full percentage point off our Gross Domestic Product. A January survey of its 5,500 members reveals that nearly one quarter were forced to curtail operations.

During a two-week period this past January, Californians lost an estimated $2.3 billion in wages, sales and productivity. Layoffs are already hitting workers in the West as companies shift production to states with more reliable energy sources. Then there are the jobs that will never be created.

Intel's CEO Craig Barrett announced that the world's leading chipmaker won't be expanding in California: "As long as California is a Third World country," Barrett said, "we won't build $2 billion manufacturing plants here."

The Food and Agricultural Policy Institute reports that farmers are likely to see their income drop 20 percent over the next two years due to higher energy costs.

Rising energy costs are hitting every family's checkbook, primarily affecting those who can afford it least. Gas bills for many homeowners in the Washington, DC area more than tripled this year. Some residents are reporting that their heating bills are higher than their food bills this winter.

The power crisis isn't just pinching our wallets, it's changing the way we live our lives. In California, power outages have shut down traffic lights, darkened schools and closed businesses. The governor has ordered local police to patrol the streets-not for criminals, but to make sure businesses keep their lights dimmed.

But California is not the only state facing a mismatch between supply and demand. With electricity shortages predicted for New York City and Long Island this summer . . . low capacity margins threatening electricity reliability in the Midwest, Southeast and Northern Plains states . . . and strained refinery capacity in the Midwest, Americans across the nation are feeling the energy squeeze.

The Need For A National Energy Policy

Rising demand . . . tightening supplies . . . an aging power infrastructure . . . a decade of neglect from Washington: These are the trends that define America's emerging energy needs.

President Bush has committed this administration to meeting these challenges - a job that begins with the urgent task of developing and implementing a long-term national energy policy.

To accomplish this, President Bush created an Energy Task Force headed by Vice President Cheney. He has asked us to define a clear strategy - a strategy that will allow environmentally responsible exploration and recovery of our domestic resources . . . enhance our commitment to conservation and energy efficiency . . . and encourage investment in new technology to further the development of renewable energy sources.

I wish I could say that the energy crisis now sweeping the nation has shocked the political system into action. But like other political discussions in recent years, the debate over energy seems as deeply polarized as ever.

On one end of the spectrum, some activists propose what amounts to a "zero tolerance" policy toward exploration and cling to the quixotic idea that new, undiscovered sources will somehow allow us to meet our energy needs. On the other end, some advocates place an almost limitless faith in special tax breaks for this favored activity or subsidies for that preferred industry.

The two extremes in our energy debate are founded on several enduring myths - myths that today conspire to block any true advance toward a rational and stable energy policy in the United States. Here are a few of the more prominent ones.

Myth Number 1: It is impossible to balance energy exploration and environmental protection.

Advances in technology have brought us a long way from the days when wildcatters punched holes in the ground based on the hunch they might hit a gusher. But from a regulatory standpoint, our view of oil and gas exploration hasn't changed much since we saw Jed Clampett strike "black gold" and split for Beverly Hills.

Today, satellites and computers are the tools of choice in the exploration business. Geologists can bounce acoustic and electrical vibrations off the earth's inner depths, gather the resulting mass of data into powerful computers and then create three dimensional and even four dimensional maps of resource fields miles below the surface.

Armed with these pinpoint accurate images, companies employ advanced equipment to drill vertically, horizontally and around corners-allowing us to access supplies from previously unimaginable depths, up to six miles away.

The marriage of oil and gas exploration with cutting-edge technology means fewer rigs, fewer roads and fewer pipelines. Drilling operations that required 65 acres in the 1970s need only 10 acres today. Technological improvements in just the past 15 years have generated success rate increases of 50 percent. America's national energy policy must reflect these staggering advances that have revolutionized the way we develop our resources.

Myth Number 2: All our current problems are due to an energy industry that is engaged in a massive conspiracy to gouge consumers by limiting supply to drive up prices.

This myth has been punctuated by calls for investigations into everything from last summer's Midwest gasoline price spikes, to recent allegations that power generators in the West have been withholding electricity. We have a fair and objective process for judging these claims-and action will be taken when it is merited. Over the past two weeks, for example, the Federal Energy Regulatory Commission ordered power companies to rebate some $124 million to California utilities. Meanwhile, the Federal Trade Commission recently cleared gasoline suppliers of all charges relating to last summer's price increases.

But charges of price gouging largely miss the point. There is no magic source of supply; no hidden pool of energy that can be turned on and off like a faucet. California-and other power-strapped states-will never solve the power crises they confront until they resolve the conflict between demand and supply.

Earlier this year, one company proposed building a $400 million power plant in California that would have provided enough additional electricity to light 600,000 homes in energy-starved Silicon Valley. The company pledged to plant 800 new trees to beautify the area. They proposed cloaking the power station in a brick facade to make it essentially indistinguishable from a high-rent office complex. They even promised to help maintain the local habitat for the endangered bay checkerspoon butterfly.

Their environmentally-sensitive plans won the support of the Sierra Club, the American Lung Association and the NAACP. But city officials voted unanimously -- 11-0 -- to reject the plan. In an editorial, the local paper called this move "Dumb and Dumber."

Meanwhile, further south, plans to build a 550-megawatt gas-fired generator in a Los Angeles suburb were scrapped after residents voted 2:1 against the project. The local mayor added a much-needed dose of reason and maturity to the debate-by launching a hunger strike in opposition to the plant.

In California, workers are being laid off, companies are leaving the state, farmers and small businesses are losing millions, consumers are threatened with rolling blackouts, but local officials reject power plants with little regard for the consequences. Is it really any mystery why there hasn't been a single new power plant built in California in the last decade?

Myth Number 3: The Bush energy plan is focused almost exclusively on opening the Arctic National Wildlife Refuge (ANWR) to exploration-a move that would buy us only about 6 months worth of American consumption while destroying a pristine natural wilderness, not to mention disrupting the breeding ground of the Porcupine Caribou.

Let's separate fact from fiction when it comes to ANWR.

First, according to estimates by the U. S. Geological Survey, ANWR holds between 5. 7 to 16 billion barrels of recoverable reserves-with a mean estimate of 10. 4 billion barrels. And that assumes the use of drilling technology now nearly a decade old. This represents more than 300 times the amount of the oil President Clinton released from the Strategic Petroleum Reserve last fall. And based on December 2000 figures, it would free us from about 54 years of oil imports from Saddam Hussein and Iraq.

Second, exploration would impact only about 2,000 acres out of more than 19 million. To put that in perspective, the massive Arctic National Wildlife Refuge is about the same size as the entire State of South Carolina; the two thousand acres that would be affected is less than half the size of Dulles airport.

And as for the caribou, the herd in the Prudhoe Bay area grew more than 9-fold over the past 20 years to an estimated 28,000 in 2000-seemingly irrefutable evidence that caribou mating and oil exploration can peacefully coexist.

The decision to open a small portion of ANWR should be made on the merits. But it should not be made on the mistaken assumption that opening ANWR will allow us to produce our way to full energy independence.

America first became a net importer of energy in the 1950s - and our economy will continue to depend, in part, on imported oil. However, closing off virtually every available new source of domestic supply, enhances the leverage and power of an oil cartel that cannot be relied on to put America's interests first. While the resources of ANWR won't make us energy independent, they will help increase America's energy security by ensuring a more diverse supply of oil.

Myth Number 4: Government subsidies and tax breaks are the best way to encourage new exploration and production of energy.

This administration will continue to support funding for energy research and development initiatives. But capital is best allocated to its highest uses through the workings of the free market, not manipulations of the tax code. Government regulatory policy should not be aimed at picking winners and losers in any market, including energy. Neither should tax policy.

Myth Number 5: We can forego traditional sources and instead meet rising energy demand by harnessing wind, geothermal, solar and other forms of renewable power.

Excluding hydro-power, renewable sources currently generate about 2 percent of America's electricity. Billions have been invested in developing renewable energy-and will continue to be invested under the Bush Administration. But renewables have yet to overcome the economic advantages of conventional energy sources.

Even with promising advances in research and development, renewables will only provide, according to Energy Information Administration estimates, about 6 percent of our total electricity consumption by 2020. Even if renewables exceed our most optimistic expectations, they would still supply only a fraction of our needs over the next 20 years.

Myth Number 6: Price controls are the answer to today's energy crisis.

Memories are short, aren't they. So let me remind everyone. America imposed price controls on oil and gas in the 1970s. They were an utter failure. They led to shortages and rationing and the idea that America was gripped by malaise.

Let me be clear: The Bush Administration does not support price controls. Price controls on electricity will lead to more blackouts. Price controls on gasoline will lead to gas lines. Price controls will deepen America's energy crisis, because they won't reduce demand, but they will cripple incentives for desperately needed new investments in energy supply.

Charting a New Policy Course

The challenges are formidable . . . the warning signs are obvious . . . but I am optimistic because I know this administration's commitment is equal to the task.

Our national energy policy will be comprehensive. It will reach across every department that touches the energy marketplace-from the Interior Department and the EPA to the Transportation Department and the DOE.

Our national energy policy will be hemispheric. It will be based on the understanding that our policy cannot stand in isolation from our neighbors throughout the Americas.

Our national energy policy will stress the need to diversify America's energy supply. It will be founded on the understanding that diversity of supply means security of supply . . . and that a broad mix of supply options-from coal to windmills, nuclear to natural gas-will help protect consumers against price spikes and supply disruptions.

And our national energy policy will be balanced. It will leapfrog the myths that stifle change-rejecting the notion that there is no middle ground between environmental protection, regardless of the cost and energy exploration, regardless of the impact.

Soon we will deliver our recommendations to President Bush. Later, we will introduce legislation aimed at winning bipartisan support for a national energy policy that matches the magnitude of the challenge. I am hopeful that men and women of good will-from both ends of the political spectrum . . . from environmental organizations to industry groups-will then come together and transcend the stale debate that has characterized energy policy in recent years.

About 150 years ago, America faced a vastly different energy crisis.

Supplies of whale oil were becoming more and more scarce. Few could afford to pay for the luxury of this or other costly methods of illumination. Sure, crude oil was available. In those days it was soaked up with rags, wrung out into small vials, and then sold as a treatment for toothaches . . . until an entrepreneur lined up an investor and a chemist and launched an energy revolution that would light the world.

In America, resources become scarce only when our imagination languishes. By engaging that imagination, I am confident we can meet the challenges of today. If complacency yields to action. If we resolve to strike a rational balance between our energy needs and our environmental concerns. And if a national energy policy becomes an urgent priority.

Thank you.

Report by Energy Secretary Spencer Abraham

Contents

1. Report by Energy Secretary Spencer Abraham
2. National energy policy for 8 years
3. Energy supply challenges
4. Oil: Rising consumption and accelerating dependence
5. Oil: Rising consumption and accelerating dependence
6. Natural Gas: Rapidly rising demand, supply constraints
7. Natural Gas: Rapidly rising demand, supply constraints
8. Electricity: Needs, problems
9. The aging power grid
10. Coal fired electrical power
11. Nuclear power plants
12. Hydroelectric power generation
13. Dangers of complacency
14. Dangers of complacency (2)
15. Need for national energy policy
16. Extremes of the energy positions
17. Six prominent myths, none of which is true
18. Can we balance exploration and environmental protection?
19. Is there a price gouge conspiracy?
20. Is there a price gouge conspiracy? (2)
21. Is there a price gouge conspiracy? (3)
22. Arctic National Wildlife Refuge Exploration
23. Arctic National Wildlife Refuge Exploration (2)
24. Our increasing oil imports
25. Government subsidies and tax breaks
26. Renewable energy sources
27. Price controls
28. Charting a new national policy

---

29. **Commentary by Tom Bearden, Ph.D.**
30. Commentary
31. Caution: It is stressed that
32. An example of the time problem

33. The pending disaster
34. The bottom line:
35. Here are some events etc.
36. Lowered energy requirements for appliances
37. Easing air conditioner and heat pump standards
38. Navarro's Estimate*
39. Factors driving comparisons
40. Prices likely per kilowatt-hour
41. Covering debt already incurred
42. Deteriorating situation, rising prices
43. Other Factors
44. Paying the piper: California's bond rating reduced
45. Associated Press: Gasoline supplies are critical
46. A peculiar problem
47. MEG uses the Aharonov-Bohm effect to extract free energy from the vacuum (1)
48. MEG uses the Aharonov-Bohm effect to extract free energy from the vacuum (2)
49. MEG uses the Aharonov-Bohm effect to extract free energy from the vacuum (3)
50. MEG uses the Aharonov-Bohm effect to extract free energy from the vacuum (4)
51. MEG uses the Aharonov-Bohm effect to extract free energy from the vacuum (5)
52. Negentropic Engineering
53. Rigorous "out-of-the-box" work
54. Rigorous "out-of-the-box" work (2): (Bedini "negative resistor" in a battery)*
55. Initiating a Battery to COP>1.0
56. Secretary alone cannot solve it
57. What is desperately needed
58. Why it can be done in time
59. Cautions!
60. The scientists have failed us
61. 136-yr-old EM Model1
62. All EM from Time Domain1
63. Astonishing but true
64. With plentiful, cheap, clean electrical energy:
65. Recommendations to DOE
66. In conclusion:

Report by Energy Secretary Spencer Abraham



National Energy Summit,
U.S. Chamber of Commerce
Mar. 19, 2001

Published by Lotus® Freelance Graphics®



National energy policy for 8 years

- The national policy imposed the following:
  - Taxed energy demand
  - Limited the energy supplies
  - Ignored expanding energy needs
- Summary of the past policy on energy:
  - You cannot find it
  - You cannot transport it
  - If you get it, we don't want you to use it
- *Good News*: Crisis can be solved
- *Bad News*: Not temporary; will not fix itself

Published by Lotus® Freelance Graphics®



Energy supply challenges

- Demand for energy rising across the board, particularly for natural gas and electricity
- Supplies limited by regulatory structure
  - Failed to keep pace with technology advances
  - Uncertain political environment discourages investment in desperately needed facilities
- Energy infrastructure is woefully antiquated and inadequate

Note: The energy infrastructure is that network of generators, transmission lines, refineries, and pipelines that convert raw resources into usable energy or fuel

Published by Lotus® Freelance Graphics®



Oil: Rising consumption and accelerating dependence

- In U.S., will increase 33 percent in 20 years
- U.S. production continues to drop
  - Produce 39% less now than in 1970
  - At present reduction rate, production will decrease to 5.1 million barrels per day by 2020, down from 9.4 million barrels per day in 1970.
- Imports have steadily risen
  - From 36% in 1973 to 54% today
  - Will soon rise to 64% unless checked
  - Empowers foreign suppliers such as OPEC
- Assuring affordable, reliable, adequate supply of crude oil is a critical national challenge

Published by Lotus® Freelance Graphics®



Oil: Rising consumption and accelerating dependence

- We have been decreasing the infrastructure
  - Since 1980, U.S. refineries reduced by 50%
  - No new refinery built in over 25 years
  - New regulatory interpretations limit expansion of capacity of existing refineries
  - Regulations require producing more than 15 different types of gasoline
  - Refining industry strained to capacity
- E.g., Clinton symbolically released 30 million barrels of oil from the Strategic Petroleum Reserve
- *The oil had to be shipped overseas to be refined!*

Published by Lotus® Freelance Graphics®



Natural Gas: Rapidly rising demand, supply constraints

- By 2020, U.S. will consume 62% more natural gas than today
- More than 9 out of 10 of announced new electric power plants will be fired by natural gas
- 40% of potential gas resources are on federal lands either closed or severely restricted
- Last lease in Gulf of Mexico more that 10 years ago
- New discoveries falling
- Dangerous to assume relying on natural gas, severely restricting exploration, keeping low prices

Published by Lotus® Freelance Graphics®



Natural Gas: Rapidly rising demand, supply constraints

- Given enough natural gas, 38,000 more miles of transmission pipelines and 255,000 miles of distribution lines will be needed
- This alone will cost $120-150 billion
- E.g., Alaska's Prudhoe Bay produces 8 billion ft^3 per day
  - About 13% of America's daily consumption
  - Never reaches the market, pumped back into ground
  - Waiting on building a pipeline to connect Alaska fields to US/Canada distribution system

Published by Lotus® Freelance Graphics®



Electricity: Needs, problems

- Over 20 years, conservative estimate is that demand will increase 45%
  - Will require construction of 1,300 new power plants, about 65 every year (about one every 6 days)
  - Last time we added so many power plants was 1985
- Some experts calculate demand will increase faster
  - May require nearly 1,900 new power plants
  - That is 90 per year (about one every four days)
- Either way, will place great pressure on already strained and aging power grid

Published by Lotus® Freelance Graphics®



The aging power grid

- Network of transmission lines, substations, and transformers
- Built when utilities were tightly regulated, supplied service to assigned regions
- Interconnections between suppliers were strictly emergency backup measure for rare usage
- Not designed at all for long-haul swapping of power in a competitive market
- Transmission bottlenecks contributed to California blackouts this winter and price spikes in New York City last summer

Published by Lotus® Freelance Graphics®



Coal fired electrical power

- Coal powers half our electricity generators.
- Enough coal for 250 years.
- Coal emissions slated for broad reductions
- Administration will support new technology, but will not threaten electricity supplies and let it significantly raise electricity prices
- President Bush therefore decided not to impose new mandates on CO_2 emissions
- If nation is to have reliable electricity over next 20 years, coal must play a major role

Published by Lotus® Freelance Graphics®



Nuclear power plants

- No new nuclear power plant permit granted since 1979
- 103 existing nuclear power plants
- Many not expected to even file for license renewal as licenses expire over the next 15 years

Published by Lotus® Freelance Graphics®



Hydroelectric power generation

- Expected to fall sharply
- Re-licensing can take a decade and cost millions
- Some activists and political leaders want to breach one or more of the four federal dams on the Snake River to help young salmon on their trek to the sea

Published by Lotus® Freelance Graphics®



Dangers of complacency

- Last three recessions tied to rising energy prices
- Latest crisis already causing negative effects
- Soaring fuel costs: extra $115 billion between 1999 and 2000; 1% off Gross Domestic Product
- In two weeks in January 2001:
  - Californians lost $2.3 billion in wages, sales, etc.
  - Layoffs hitting in West as manufacturers shift to states with more reliable energy sources
  - Intel will not build $2 billion plants in California to expand there.
  - Farmers' incomes to drop 20% in next two years

Published by Lotus® Freelance Graphics®



Dangers of complacency (2)

- Some homeowner gas bills in Washington D.C. more than tripled this year
- Heating bills of some residents exceeded their food bills during the winter
- California power outages shut down traffic lights, closed businesses, darkened schools
- Police patrols were used to insure compliance
- Electricity shortages predicted for New York City and Long Island this summer
- Strained refinery capacity in the Midwest
- Low capacity threatens electricity reliability in Midwest, Southeast, and Northern Plain states

Published by Lotus® Freelance Graphics®



Need for national energy policy

- Rising demand, tightening supplies, aging power infrastructure, decade of neglect
- President created Energy Task Force, headed by VP Cheney, to determine strategy
  - Environmental responsible exploration and recovery
  - Conservation and energy efficiency
  - Encourage investment in new technology for renewable energy sources
- Debate is still deeply polarized

Published by Lotus® Freelance Graphics®



Extremes of the energy positions

- Some activists:
  - Zero tolerance to exploration
  - New, undiscovered sources will somehow provide for us
- Some advocates:
  - Limitless faith in special tax breaks for a favored activity or subsidies for a preferred industry

Published by Lotus® Freelance Graphics®



Six prominent myths, none of which is true

1. It is impossible to balance energy exploration and environmental protection
2. There is a massive energy industry conspiracy, limiting supply to drive up prices
3. The Bush energy plan is focused almost exclusively on opening the Arctic National Wildlife Refuge (ANWR) to exploration
4. Government subsidies and tax breaks are the best way to encourage new exploration and energy production
5. Can forego traditional sources and meet demand by wind, geothermal, solar, and other forms of renewable power
6. Price controls are the answer to the energy crisis

Published by Lotus® Freelance Graphics®



Can we balance exploration and environmental protection?

- Today, satellites and computers are tools of choice for exploration.
- Acoustic and electrical vibrations off the earth's depths provides maps of resource fields
- With advanced equipment, drill vertically, horizontally, or around corners up to 6 miles
- Fewer rigs, fewer roads, fewer pipelines
- 65 acre drilling in 1970s needs only 10 now
- Success rates have increased 50 percent

Published by Lotus® Freelance Graphics®

◀ ▶



Is there a price gouge conspiracy?

- Calls to investigate gasoline price spikes
- Allegations that power generators in the West have been withholding electricity
- Investigation and action is taken where merited
  - FERC ordered power companies to rebate $124 million to California utilities
  - FTC cleared gasoline suppliers relating to last summer's price increases
- There is no hidden energy pool that can be turned on and off like a faucet
- Must solve power crises by resolving conflict between demand and supply

Published by Lotus® Freelance Graphics®



Is there a price gouge conspiracy? (2)

- Early this year (2001) one company proposed to build a $400 million power plant in California
  - Additional electricity for 600,000 homes
  - Plant 800 trees to beautify the area
  - Cloak facility in a brick facade to resemble a high-rent office complex
  - Help maintain habitat for an endangered butterfly
- Project supported by Sierra Club, American Lung Association and NAACP.
  - City officials unanimously (11 to 0) rejected it
  - Local paper called this move "Dumb and Dumber".

Published by Lotus® Freelance Graphics®



Is there a price gouge conspiracy? (3)

- Plans to build a 550 megawatt gas-fired generator in a Los Angeles suburb were scrapped
- Residents voted 2:1 against the project
- Local mayor launched a hunger strike in opposition to it.
- In California:
  - Workers are being laid off
  - Companies are leaving the state
  - Consumers threatened with rolling blackouts
  - Local officials reject power plants with little regard
- Is it really any mystery why there hasn't been a single new power plant built in California in the last decade?

Published by Lotus® Freelance Graphics®



Arctic National Wildlife Refuge Exploration

- **Myth:** Would buy only about 6 months worth of consumption while destroying pristine wilderness and disrupting the caribou
- **Fact:** The ANWR holds from 5.7 to 16 billion barrels of recoverable reserves (mean is 10.4)
  - More than 300 times the oil Clinton released
  - Frees us from equivalent of 54 years of imports from Saddam Hussein and Iraq
  - Exploration involves only some 2,000 of more than 19 million acres -- like half the Dulles airport compared to the entire state of South Carolina

Published by Lotus® Freelance Graphics®



Arctic National Wildlife Refuge Exploration (2)

- The caribou herd in the Prudhoe Bay area grew more than 9-fold over the last 20 years (to 28,000 in 2000)
- Proves that caribou mating and oil exploration can peacefully co-exist
- Exploration should be considered on merits
- Opening ANWR will help, but does not allow full energy dependence

Published by Lotus® Freelance Graphics®



Our increasing oil imports

- U.S. became a net importer of oil in 1950s
- Closing off all new domestic sources enhances leverage and power of oil cartels
- These cannot relied on to put American interests first
- Development of domestic resources such as ANWR will help increase energy security by ensuring a more diverse supply of oil

Published by Lotus® Freelance Graphics®



Government subsidies and tax breaks

- Administration will continue to support funding for energy research and development initiatives.
- Capital is best allocated through the workings of the free markets, not manipulating the tax code
- Government regulatory policy should not aim at picking winners and losers
- Neither should tax policy

Published by Lotus® Freelance Graphics®



Renewable energy sources

- Excluding hydro-power, renewable sources generate about 2% of America's electricity
- Bush administration will continue to invest in renewable energy sources
- Renewables have not overcome economic advantages of conventional sources
- Even with promising advances, renewables will provide only about 6% of our total electricity by 2020.
- Even with most optimistic breakthroughs, they will supply only a fraction of our needs over the next 20 years.

Published by Lotus® Freelance Graphics®



Price controls

- America imposed price controls on oil and gas in the 1970s; they were an utter failure
- Led to shortages, rationing, and idea that America was gripped by malaise
- Administration does not support price controls
  - Lead to more blackouts and gas lines
  - Will not reduce demand, but cripple incentives for new investments in energy supply
  - Will deepen America's energy crisis

Published by Lotus® Freelance Graphics®



Charting a new national policy

- Comprehensive. Across every department.
- Hemispheric. Includes the Americas.
- Diversify the energy supply for security, with a broad mix of options.
- Balanced. Combines environmental protection and energy exploration.
- Recommendations to be delivered to President Bush soon.
- Legislation will be introduced and bipartisan support.
- Hope that men and women of good will come together and transcend the present stale debate.

Published by Lotus® Freelance Graphics®



Commentary

by Tom Bearden, Ph.D.

12 April 2001



Published by Lotus® Freelance Graphics®



Commentary:

- A reasoned and professional assessment of the present energy crisis situation by Secretary Abraham
- Demonstrates administration and DOE are energetically attempting to get the crisis under control with conventional methods
- Scientific advisers have no "out-of-the-box" energy knowledge; policy stays essentially "in-the-box"
  - Shortage of oil, get more oil
  - Shortage of natural gas, get more natural gas
  - Shortage of electrical power plants, build more
  - Need 90 per year; build them
  - Short distribution grid, build additional
  - Shortage pipelines, build some more
- Cannot "get more" in time to prevent economic disaster
- Cannot avoid overrunning first quarter 2004 "point of no return"

Published by Lotus® Freelance Graphics®



Caution: It is stressed that

- Given only the conventional Lorentz-regauged electrical design model, COP>1.0 EM systems are impossible. That type of EM only designs COP<1.0 systems!
- Given advice from scientific "experts" who know only COP<1.0 design, U(1) electrodynamics, and Lorentz regauged power system theory, the Administration is doing the best that can be done, all factors considered.
- The DoE and the Administration must use whatever they have available to them, to try to solve the crisis.
- Hence DoE and the Administration is not at fault. On the contrary, they are trying very hard to solve this escalating energy crisis, using the tools the scientists offer them.
- It is the U.S. scientific community that is squarely to blame for this sad state of affairs, and for the coming economic collapse.

COP = Coefficient of Performance

Published by Lotus® Freelance Graphics®

An example of the time problem

- TVA and Texaco are discussing building a coal gasification 1,500 megawatt power plant.
    - Near Scottsboro, Alabama
    - Construction could begin in 2002.
    - In 3-6 years, begin producing electricity.
    - If 5 years, it will come on line in 2007.



- 90 plants are required per year, beginning now.
- 2007 is about the time that world economies are crumbling, conflicts are raging, and all the arsenals weapons of mass destruction will be unleashed.
- 2007 is about the time civilization will be destroyed, if we continue on the present course.
- With only present solution, can get perhaps 400 to 450 plants ready to come on line, *about the time they are destroyed*

Published by Lotus® Freelance Graphics®



The pending disaster

- The world energy crisis will escalate steadily, forcing collapse of world economy circa 2008.
- As nations' economies crumble, conflicts soar and one or more nations will exchange nukes and other *weapons of mass destruction* (WMD). Security partners forced to enter the melee.
- This evokes the long-dreaded WMD "spasm" response.
  - Only way for a nation to survive is to destroy its perceived foes before they destroy it.
  - Everybody fires everything, as fast as they can, unleashing all the arsenals of WMD, desperate attempt to survive.
  - Civilization and much of the biosphere is destroyed. Unleashing of smallpox alone will kill 2 billion.
- The time for this Armageddon is circa 2007.

Published by Lotus® Freelance Graphics®



The bottom line:

- Self-powering and COP>1.0 electrical power systems must be rolling off the assembly lines en masse by first quarter 2004. That is the "point of no return".
- Otherwise, the point of no return will be overrun and no solution is possible, by any means, by anyone or by everyone.
- If that deadline is missed, the crisis curves cannot be "damped" in time to prevent world economic collapse.
- It is still doable, but only with a massive national effort of the highest priority. No one recognizes that as yet.
- Meanwhile, the scientific community is doing business as usual. You will have to just push most of it aside.
- We are "fiddling while Rome prepares to explode".

Published by Lotus® Freelance Graphics®



Here are some events etc.

- Exxon Mobil Corp. soared to the top of the Fortune 500.
- Oil, gas, and power companies climbed.
- Increased income due to
  - Falling supplies so price increases
  - Utility deregulation. CA stupidly capped end prices, and freed middle prices. Dunce cap award for that one!
  - Soaring natural gas prices.
  - OPEC maneuvering to keep oil prices high
- Pacific Gas & Electric declared bankruptcy; another CA power company on the ropes.

Published by Lotus® Freelance Graphics®



Lowered energy requirements for appliances

- Approved in last days of Clinton administration
- Washing machines must use 35% less energy, beginning in 2007
- Water heaters must use 5%-9% less energy, beginning in 2004
- Adds about $240 to price of washing machine
- Lower energy costs over time will offset initial increased cost
- Approved by Bush administration in April 2001 after review

Published by Lotus® Freelance Graphics®



Easing air conditioner and heat pump standards

- Bush administration eased Clinton's new efficiency standards
  - Still require air conditioners and heat pumps to use 20% less energy than most current models, beginning in 2006
  - Clinton standard was 30% less
- All central home air conditioning units must meet minimum seasonal efficiency ratio (SEER) of 12, compared to present 10
- Replaces Clinton SEER standard of 12
- In California, easing these standards requires two more power plants

Published by Lotus® Freelance Graphics®



Navarro's Estimate*

Peter Navarro, economist at UC Irvine,

in conjunction with Utility Consumers's Action Network

*Jennifer Coleman, "Power costs could be triple last year's for Californians," AP release, 22 Apr. 2001

Published by Lotus® Freelance Graphics®



Factors driving comparisons

- Last summer, soaring costs drove three utilities to brink of financial ruin
- This summer costs may rise by as much as three-fold
- Factors at play:
  - Drought-induced reduction of hydroelectric power supplies in Pacific Northwest
  - Predicted hotter-than-average summer
  - Competition from other states
- State buys about 1/3 of its power from spot market
- Spot market likely to see substantial increases

Published by Lotus® Freelance Graphics®



Prices likely per kilowatt-hour

- Last summer, peak average high price was 86 cents per KWHR
- This summer expected to hit $1 to $2 per KWHR
- Consumer rates capped at about 10 cents per KWHR
- The growing gap will have to be filled by state funds, which themselves are dwindling
- Eventually the California taxpayers have to pay the difference, which is from 10 to 20 times what they are paying now for capped power

Published by Lotus® Freelance Graphics®

Covering debt already incurred

- Since January, California has authorized $5.7 billion to buy power for customers of Pacific Gas and Electric Co. and Southern California Edison
- The two utilities' credit was cut off due to
  - Soaring wholesale costs
  - Cap on consumer rates
  - Went nearly $14 Billion in debt
- San Diego Gas and Electric Co. incurred debts but is in better shape
- State will be repaid by $10 Billion in bonds
  - Expected to be issued in May
  - Expected to last till September but will not
  - PG&E and Edison Customers will pay off the bonds

Published by Lotus® Freelance Graphics®



Deteriorating situation, rising prices

- Prices rising
  - Will rise even more as demand increases
  - Demand will rise by about 50 percent during the summer
- California's own generation resources cannot meet projected peak demands and reserve requirements
  - May fall by 3,500 megawatts short (peaks)
  - Enough power for 2.6 million households
- Power grid manager must depend on imports
  - Northwest drought makes extra power scarce to find
  - Northwest utilities themselves may have to import, not supply extra

Published by Lotus® Freelance Graphics®

Other Factors

Credit, payback, scarcities



Published by Lotus® Freelance Graphics®



Paying the piper: California's bond rating reduced

- Standard & Poor dropped California's bond rating two notches, from AA to A+
  - Financial drain from continuing energy crisis
  - Mounting uncertainty in costs to state of current electrical power crisis
  - Likely long term detrimental effect on state's economy
  - State's ability to pay its debt has reduced
- Rating not reduced further because of
  - State's diverse economy
  - Proposed revenue bonds to reimburse state treasury
- Can reduce further if California does not make $10 Billion bond issue and pay off its energy-related debts

Published by Lotus® Freelance Graphics®

Associated Press:
Gasoline supplies are critical

- Supplies tightest for mid-April since U.S. government record-keeping began in 1963
- There is a shortage of reformulated gasoline that produces less smog and is required during summer
  - MTBE additive made from methanol, a derivative of natural gas
  - Natural gas prices quadrupled Dec-Jan; MTBE reduced by 1/3
  - California uses more MTBE-treated gasoline than any other state
  - Gas-guzzling SUV sales boomed in 1999 and 2000
- Any kind of refinery snag will be amplified
- Last winter, major refiners had to focus on filling heating oil shortage instead of replenishing gasoline supplies for summer
- Now many forced out of service to take care of maintenance that was put off to deal with the heating oil crisis
- Environmental restrictions make it difficult to build refineries; none constructed in the U.S. for more than 20 years

Published by Lotus® Freelance Graphics®



A peculiar problem

- E.g., Magnetic Energy Ltd. has a working laboratory experiment COP>1.0 device (a motionless electromagnetic generator - MEG).
- Solved basic EM system COP>1.0 theory.
- Two years more R&D necessary to finish, do production engineering and scale up for production.
- Immediate capital needed: $20 million.
- Negotiations with large capital firms:
  - Most have substantial capital committed to normal power community, long term.
  - MEL success thus costs them dearly in unrecovered funds.
  - They shoot themselves in the foot if they fund the MEG, since this is a "very disruptive" technology.

Published by Lotus® Freelance Graphics®

MEG uses the Aharonov-Bohm effect to extract free energy from the vacuum (1)

- The Aharonov-Bohm effect (ABE) is in over 2,000 published physics papers in the hard literature.
- Hundreds of experiments prove it. Physicists themselves would not believe it for 25 years after it was advanced and proven. Now it is universally accepted.
- Free evocation of ABE never appeared for use in power systems, without paying energy to evoke it, until we used ABE in the MEG and *freely* evoked it.
- If the magnetic field **B** of a source is locally confined in a closed path (as in a toroid), the outside local spacetime (ST) where the **B**-field was withdrawn is still curved. Curved ST is energetic. The 3-space energy has been transformed into curl-free magnetic vector potential **A**. But one pays for that **A** around a toroid, since one has to "feed" the toroid.

Published by Lotus® Freelance Graphics®

MEG uses the Aharonov-Bohm effect to extract free energy from the vacuum (2)

- We uncovered a transformer core material that will *freely* do that **B**-localization of the **B**-flux of a permanent magnet, extracting all the **B**-flux into a closed transformer-like core path.
- The uncurled **A**-potential forms outside the core path as a freely flowing river of energy.
- We pay nothing at all to get the **A**-energy flow going, or to sustain it. That's for free.
- The vacuum energy exchange and locally curved ST sustain that energy flow indefinitely, due to the permanent magnet dipole's broken 3-symmetry.

Published by Lotus® Freelance Graphics®



MEG uses the Aharonov-Bohm effect to extract free energy from the vacuum (3)

- We then hang "collecting antenna circuits" in that free river of energy flow in **A**-space outside the core.
- We pulse-perturb the river *a little*, with very sharp-edged pulses of low energy. Huge **E**-fields (i.e., d**A**/dt) are formed and strike the antenna circuits.
- From the large AC **E**-fields, we can intercept and collect large AC energy. The energy is dissipated in loads in the external separate collecting circuits, with no back emf into the primary circuit.
- Only small average *input* energy is required. We pay only to *switch* or *gate* the large energy flow.

Published by Lotus® Freelance Graphics®



MEG uses the Aharonov-Bohm effect to extract free energy from the vacuum (4)

- By analogy, imagine an old triode vacuum tube.
- Suppose we trick nature into *giving* us the cathode and electron energy flow, for free, really pouring energy out of there continuously.
- Then we only have to put in a grid to switch it, a plate to intercept and catch it, and a plate circuit to dissipate it in a load.
- In the MEG, the permanent magnet and the special core provide the cathode and free flow.
- We provide the "grid" gating, plate "catching," and "plate circuits" with loads that are powered.

Published by Lotus® Freelance Graphics®



MEG uses the Aharonov-Bohm effect to extract free energy from the vacuum (5)

- The MEG becomes a *free transmitter with multiple receivers* system, *not* a transformer but a triode.
- The transmitted energy is absolutely free, taken right from curved ST. We only have to "perturb" or shake the flow a tiny bit, in sharp little shocks without much energy. The broken 3-symmetry of the magnetic dipole, in the fierce vacuum exchange, furnishes the energy in the large **E**-fields by d**A**/dt.
- The COP that can be achieved by the MEG is limited only by the **A**-space available outside the core for collection, and the number of surface charges in those external circuits powering the loads.

Published by Lotus® Freelance Graphics®



Negentropic Engineering

- Can easily produce continuous giant EM energy flows from the vacuum: anywhere, anytime, for peanuts
- Once flow initiated, no further input required
- Focuses on real energy problem: intercepting the pouring energy and dissipating it in loads
- Dramatic implications:
  - Reduces hydrocarbon combustion; meet Kyoto accords
  - Obsoletes nuclear power, reduces nuclear wastes
  - Reduces biospheric pollution
  - Reduces biological effects of pollution
- One drills the vacuum for energy, much easier than drilling the ground for oil and natural gas

Published by Lotus® Freelance Graphics®



Rigorous "out-of-the-box" work

- Evans, Anastasovski, Bearden et al. (15 authors), Alpha Foundation's Institute for Advanced Study:
    - "Explanation of the Motionless Electromagnetic Generator with O(3) Electrodynamics," *Found. Phys. Lett.* 14(1), Feb. 2001, p. 87-94.
    - "Explanation of the Motionless Electromagnetic Generator with the Sachs Theory of Electrodynamics", *Found. Phys. Lett.* 14(8), Aug. 2001 (in press).
    - "Energy from the Vacuum," in referee process.
    - "O(3) Electrodynamics from the Irreducible Representations of the Einstein Group," in referee process.
    - "Electromagnetic Energy from Curved Spacetime," in referee process..
    - "The Effect of Vacuum Energy on the Atomic Spectra," *Found. Phys. Lett.*, 13(3), June 2000, p. 289-296.
    - "Operator Derivation of the Gauge Invariant Proca and Lehnert Equations: Elimination of the Lorentz Condition," *Found. Phys.*, 30(7), 2000, p. 1123-1130.
    - "Runaway Solutions of the Lehnert Equations: The Possibility of Extracting Energy from the Vacuum," *Optik*, 111(9) 2000, p. 407-409.
    - "Classical Electrodynamics Without the Lorentz Condition: Extracting Energy from the Vacuum," Physica Scripta, 61(5), May 2000, p. 513-517.

Published by Lotus® Freelance Graphics®



Rigorous "out-of-the-box" work (2): (Bedini "negative resistor" in a battery)*

- A battery-powered circuit is not a single closed current loop; but has two largely separate current half-loops:
  - Internal ion current between plates.
  - External electron current from outside of one plate, through external circuit and load, to other plate.
- M/q ratios very different: Ion current more than 200,000 times heavier per coulomb than electron current.
- Can dephase the two currents, overpotentialize both.
- Battery can thus be hyper-recharged while external circuit simultaneously powered.
- Bedini has been building successful little prototypes for more than 20 years. Could dramatically improve electric automobiles.

* T.E. Bearden, "Bedini's Method for Forming Negative Resistors in Batteries," *Journal of New Energy*, 5(1), Summer 2000, p. 24-38. http://www.cheniere.org/techpapers/Bedini.pdf

Published by Lotus® Freelance Graphics®



Initiating a Battery to COP>1.0

- A Battery is highly nonlinear with multiple currents
  - Electron current largely bound between outside of plates and external circuit including through load
  - Ion current confined between plates, through separators
  - Mass-to-charge ratios of the two currents are vastly different
- Can dephase currents by 180°
  - ion current in charging mode
  - electron current in circuit-powering mode, powering circuit
- Done by forming negative resistor
  - Sharp, higher potential at insulator interface on plate surface
  - Bidirectional overpotentialization
  - Energy extracted from active vacuum

Published by Lotus® Freelance Graphics®



Secretary alone cannot solve it

- Scientific community, universities, national labs, NSF, NAS, power companies doing business as usual
  - No really out-of-the-box energy research
  - Do not realize all electrical systems and power lines are powered by energy extracted from the vacuum
  - Not correcting flawed electrodynamics, uninterested
  - Not funding any vacuum energy extraction projects
- New policy cannot quickly eliminate the long delay time till new electrical power plants come on line
  - Need 60 to 90 powerplants per year; first one can be operational only after several years even with crash program
  - Skyrocketing energy, trucking and other transport costs will drive the nation into financial disaster during that delay
- Only doable solution: vacuum-energy systems

Published by Lotus® Freelance Graphics®



What is desperately needed

- Separate "Manhattan Project" on energy from the vacuum systems, reporting to Secretary
  - Operate under Presidential Decision Document
  - Staffed with carefully selected scientists and engineers
  - Top priority funding
  - Round-the-clock research
- Support from selected personnel in national labs, universities, research corporations
- Start with known COP>1.0 systems; factual information can be provided

Published by Lotus® Freelance Graphics®



Why it can be done in time

- Already have elements of necessary theory of Maxwellian disequilibrium COP>1.0 systems; funding will finish it rapidly
- Several legitimate COP>1.0 systems exist, can be quickly developed and scaled up
- Two years or less after start, a range of self-powering systems can be rolling off the assembly lines en masse
- A great breakthrough in close-looping principles for self-powering technology has been accomplished
  - Deeply proprietary, can be released
  - Using breakthrough, parallel program can develop self-powering of many present power systems
  - Will not be discussed without the program

Published by Lotus® Freelance Graphics®



Cautions!

- In the so-called "free energy field", many charlatans, much disinformation, some honest mistakes, some real systems and information
- Absolutely must separate wheat from chaff
- Working laboratory proof-of-principle devices do exist; groups need funds for development
- Inventors with such systems usually do not comprehend the actual mechanism used
- U.S. is 100 years behind in applying necessary corrections to electrodynamics; but some courageous scientists have begun

Published by Lotus® Freelance Graphics®

The scientists have failed us

- Secretary Abraham, it is the U.S. scientific community which has failed us, and which is responsible for this unnecessary crisis.
- No textbook presently even correctly states what actually powers a power line. The basis has been in particle physics for a half-century.
- Before arbitrary regauging by Lorentz in the 1880s, the Maxwell-Heaviside theory does prescribe electrical power systems far from equilibrium in their fierce vacuum exchange, including systems which power themselves and their load, extracting the energy from their broken symmetry in their active vacuum energy exchange.
- Every power system already wastes a trillion times more energy than is placed on the power line; scientists and engineers do not even know it.
- Heaviside published the basis for that in the 1880s and 1890s; Poynting never even knew it. Lorentz knew it, couldn't explain the source, stated "no physical significance" and discarded it.
- This discarded "Heaviside energy" is what is generating the extra gravity in spiral galaxies, and holding their arms together. Scientists arbitrarily discarded it in the 1880s; have forgotten it today.

Published by Lotus® Freelance Graphics®



The scientific community enforces a 137-year-old flawed EM model

- Equations still assume material ether.
- Thoroughly confuse cause and effect.
- "Fields" as defined in electrical engineering do not exist outside matter (Feynman, Wheeler)
- Arbitrarily discards vacuum energy exchange and usage.
  - Proven for nearly 50 years in particle physics
  - Dipole exchange particularly significant because dipole's negentropy extracts *all* EM energy -- used in the system -- from the vacuum. Every system already powered by the vacuum anyway.
- Arbitrarily discards about 10 trillion times as much EM energy present around a circuit as the circuit intercepts.
- Scientific community pummels most scientists who try to change model or develop systems far from equilibrium in their known violent energy exchange with the active vacuum.
- ***Same flawed power system schema for more than a century.***

Published by Lotus® Freelance Graphics®

All EM 3-space energy freely comes from the time domain*

* T. E. Bearden, "Giant Negentropy of the Common Dipole," Journal of New Energy, 5(1), Summer 2000, p. 11-23.
http://www.cheniere.org/techpapers/GiantNegentropy.pdf

Whittaker, Math. Ann., 57, 333 (1903)
shows this rigorously.
Dipole's broken 3-symmetry well-known
in particle physics



(Time)

Longitudinal EM waves incoming from time domain and absorbed

CHARGE OR DIPOLE

Real EM Energy

Longitudinal EM waves emitted in all directions in 3-space

pours out in all directions

Space

Note: Whittaker (and others) interpreted the phase conjugate half set of LWs after interaction with the charges of the dipole; and as an *effect* rather than the *cause*. This fundamental non sequitur has just been repeated since then. Thus they missed the solution of the source charge and source dipole.

Published by Lotus® Freelance Graphics®



Astonishing but true

- All the hydrocarbons burned, nuclear fuel rods consumed, dams and windmills built, fuel cells consumed, and batteries installed do not add a single direct watt to the power line. Never have, never will.
- All that does is continually restore the generator source dipole, which our systems are designed to continually destroy faster than they power their loads.
- The dipole extracts energy from the vacuum, and pours it out to fill all space around the power lines. The power lines intercept and use only about 10exp(-13) of it.
- Nobody tries to catch any of the rest of it. *There is no ordinary source of that energy flow, which is enormously greater than the energy put into the shaft of the generator.*

Published by Lotus® Freelance Graphics®

⬅ ➡



With plentiful, cheap, clean electrical energy:

- Even poorest nations get onto the fast track
  - Rapid development of infrastructure
  - Concentrate on clean water, medical treatment, education, plentiful food
  - Rise of industries and creation of jobs
- Gradual but permanent shift in electric power
  - Accent decentralized systems
  - Dramatically reduce vulnerability of power grids
  - Practical, agile electric cars, trucks, trains
- Releases the iron grip of energy barons

Published by Lotus® Freelance Graphics®



Recommendations to DOE

- "Out-of-the-box" prototypes do exist, theory developed.
- Crash Manhattan project; Presidential Decision Directive.
- Intense program with highly selected scientists to correct EM flaws and extend EM theory to higher symmetries.
- Obtain compensated release of breakthrough close-looping process to initiate many normal power systems into self-powering systems, and rapidly develop and apply. No discussion without program and NDA.
- Protect patent rights of o/u inventors. Suspend national labs, universities, other research labs from "cluster patenting" in the area. They sign nondisclosure, non-compete, eliminate "march in" theft clauses.
- President order release of known overunity systems captured from inventors and in deep black community.

Published by Lotus® Freelance Graphics®



In conclusion:

- Secretary Abraham, the threat of weapons of mass destruction attacks and giant destruction is not overestimated. It's really worse.
- Large Russian nuclear weapons, e.g., are already in U.S. cities, with on-site Spetznaz teams to explode them. See Lunev's book.
- Professional teams with anthrax, smallpox, etc. already in place, waiting. Unleashing smallpox alone will kill 2 billion worldwide.
- In the WMD strategic attack, the delivery to the target stage is already accomplished.
- 25 nations -- many hostile to the U.S. -- now have nukes, biological warfare agents, etc.
- The earth is in fact a giant powder keg, waiting to explode at the touch of a match. Unless solved at enormous speed, the energy crisis will certainly strike that match about 2007.
- Only one thing -- energy from the vacuum -- can do it. Neither the DoE nor the U.S. scientific community are working on that.

Published by Lotus® Freelance Graphics®

The "Porthole" Concept with technical background

Amplifying the cellular regenerative (healing) system of the body for treatment and healing of mass casualties



Outline of the presentation

- Mechanism for deep EM exchange of a body with its active EM environment
- Becker's epochal work and its ramifications
- Kaznacheyev's startling results and ramifications
- Weaponization of Kaznacheyev's findings
- Importance of time-energy and the time-domain
- Mechanisms for medical treatment and healing

Outline of the presentation (2)

- Prioré's revolutionary results and their ramifications.
- Proposed new mechanism for cancer promotion.
- Porthole concept: The 2-minute shortcut.
- Terrorist biological warfare capabilities.
- Summary and conclusion.
- Budgetary and Program package.



Mechanism for the body's deep EM exchange with its active EM environment

And some ramifications



The body continually receives and retransmits EM energy

- The body may be considered as a dielectric.
- Every part of the dielectric participates in the absorption and emission of each photon to and from any point on the surface.*
- Mechanical force effects are also electrical in nature and exchange similarly.



* Reali, G. C., "Reflection from dielectric materials," American Journal of Physics, 50(12), Dec. 1982, p. 1133-1136. The reflected field from a dielectric material is not generated just at its surface but comes from everywhere in the interior of it.

Ramifications:



- There is an EM "dielectric transmission path" connecting every part of every cell to every part of the surface of the body.
- All electrical processes in the body, including deep within the cell and its nucleus, participate in the absorption and emission of every photon to and from the body's outer surface (and every mechanical force* experience).
- The EM emission energy of the body is a conglomerate mix of fractions of all processes and functions ongoing in the body or affecting it, including in every cell.
- This includes all electromagnetic, mechanical, chemical, and environmental effects upon and in the body and every tiniest part of it, and provides an extended definition of "stress".

* At base, all normal mechanical forces are generated by electromagnetic forces.

Ramifications (2)



- The reaction of each photon absorbed on any point of the outer surface of the body, connects through the dielectric transmission path to every part of the body, including to every part of every cell*.
- Every emission from the body is participated in by every part of the body, including every part of every cell.
- The body's emission "changes" its environment, adding EM radiation. Some of the internal induced changes (excited states) in the body decay by this external emission. Some do not, but must be otherwise dealt with internally by the body systems.
- The body's EM absorption allows the environment to change or affect every function, operation, and part of the body, by adding EM radiation. All are continually being affected and deviated, both helpfully and harmfully, by these deeply induced EM interactions.
- The body's reaction (healing) must continually readjust and correct deviations from normalcy, in every part of every cell.

* In quantum physics, part of the photon is localized and part is nonlocalized, reaching even across the universe.

Ramifications (3)



- The sum total of all the impinging external EM radiation upon the body, plus mechanical "special EM" radiation, thus affects and changes the body and all its processes, participating in them.
- That impinging EM radiation can be manipulated to either harm or heal the body and any or all of its cells.
- The body must continually overcome these externally-induced EM changes in its cells and processes, to maintain normalcy. Some EM changes are restored by the subsequent dielectric emission process, relieving the previously-induced deviant EM excitations in its internal processes. Some are not.
- The poorly studied *cellular regenerative system* performs the remainder of the restorative function, which is the fundamental "healing" function of the body.*

*The cellular regenerative system was mostly studied by Becker and a few others. See R. O.Becker, and David G. Murray, "The electrical control system regulating fracture healing in amphibians," Clinical Orthopaedics and Related Research, No. 73, Nov.-Dec. 1970, p. 169-198.

Becker's epochal work

And its ramifications



Becker's bone fracture healing

- Tiny DC currents (picoamperes)
- Pulsed DC current can be utilized
- Pulsed magnetic fields may be utilized


(+)
ELECTRODE
(-)
DC
POWER
SOURCE
ELECTRODE
BONE
BONE
FRACTURE SITE

RED BLOOD CELL DEDIFFERENTIATES

Shucks hemoglobin coat
Grows nucleus

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes cartilage

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes bone
Deposits in fracture site, healing the fracture

Becker's theoretical DC control system involved with response to injury



INJURY

INPUT STIMULATION DC SYSTEM (PAIN)

CENTRAL DC SYSTEM

GROWTH DIFFERENTIATION

LOCAL CELL INJURY FREE RADICALS

OUTPUT DC SYSTEM

TOTAL CURRENT OF INJURY DC SYSTEM

MITOSIS DEDIFFERENTIATION

STIMULATION OF REPAIR CELLS

*Robert O. Becker, "The significance of bioelectrical potentials," Bioelectrochemistry and Bioenergetics, Vol. 1, 1974, p. 191.

Becker's proposed control system governing regeneration*



Trauma Producing
Tissue Loss

Local cellular effect

Local nerve effect

CNS effect

Alterations in hormone
pattern (prolactin)

Alterations in local
DC field pattern

Local electrical
effects

Local and systemic
pools of target cells

Dedifferentiation into
primitive mesenchymal cells

Phase I

Blastema formation

Growth

Phase II

Redifferentiation into
required cell types

Restoration of body
part or tissue

*Becker & Spadaro, "Electrical stimulation of partial limb regeneration in mammals," Bull. N. Y. Acad. Med., 48(4), May 1972, p. 629.

Extending Becker's work

- Becker had only the archaic classical electrodynamics available to him. That EM is grossly inadequate.
  - Insufficient group symmetry to model the process.
  - Already eliminates the "infolded" longitudinal wave EM that structurally and dynamically comprises all "normal" EM potentials, fields, and waves.
  - It is this internal LW EM that is manipulated and used by the cellular regenerative system.
- Nonlinear phase conjugate optics was not yet developed when Becker did his seminal work.
- Successful higher symmetry electrodynamics models -- such as O(3) -- have been developed and are available.

A sad commentary



- Becker was nominated for the Nobel Prize, but he was hounded, his funds were withdrawn, and he was forced to retire early.
- His main "sin" was having the courage to testify against the harmful effects of unrestricted powerline radiation and electronic smog.
- Powerful interests then crushed him, set up their own well-funded institutes, and hired scientists who then predictably found that powerline radiation was no problem.
- Such research is so tainted that recently several important journals have now required the authors of submitted papers to state what their affiliated companies do, and what "company massaging" of their research occurred.
- From a higher symmetry EM view, it is obvious that the dielectric pathway and quantum electrodynamics already show a significant problem due to such radiation, particularly with respect to long-term effects.
- This is particularly significant since "noise" -- the mere presence of more "hash" -- appreciably amplifies the dielectric transmission effect. So the major factor becomes EM smog *signals density*, not signal power.

Kaznacheyev's startling results

And its ramifications



Proof that the cellular condition is radiated from groups of cells

- It follows that a diseased, damaged, or infected cell culture will and does emit its exact internal EM condition, hence the disease or damage "generatrix form" itself (in the internal structuring of the EM radiations).
- Further, these "state" emissions can couple into other targeted cells to produce disease and disorder in them.
- This was clearly proven in some 15,000 Russian experiments by Kaznacheyev.
- Kaznacheyev demonstrated induction of cellular disease and disorder between EM-coupled but otherwise environmentally shielded cell cultures
- Similar experiments have been replicated in the West by Reid *et al*., and by Popp *et al*.

Kaznacheyev's induction of cellular disease and disorder


GRAVITON LATTICE TEMPLATES
SICKEN OR KILL
CELL CULTURE SAMPLE #1
QUARTZ CONTAINER
ENVIRONMENTAL SHIELDING
CELL CULTURE SAMPLE #2
QUARTZ CONTAINER
THIN WINDOW
GLASS: No Effect
QUARTZ: Delayed Effect
Divided bottle setup

© T.E. BEARDEN 1977, 1987

Note: Minimum lattice is one harmonic interval: IR to UV is such a minimum G-lattice. Consider particularly the dielectric pathway in the emitting diseased cells and in the receiving targeted healthy cells.

Another surprising feature of Kaznacheyev's experiments

- The experiments do not work if the targeted cells are in normal light, such as sunlight*.
- The reason is that the normal light bandwidth occupies a single harmonic interval between ultraviolet and infrared.
- Hence its difference frequencies also fill such an interval. For a set of n frequencies, the number *d* of difference frequencies is $d >> n$.
- Thus the visible light spectrum represents "jamming" of specific internal EM signal inputs through the dielectric pathway into the body, turning much of the environmental signals into harmless warmth.

* It has also been shown that if bacteria are killed in the "dark" by UV, then 24 hours later placed in sunlight, a substantial fraction of the "dead" bacteria will revive.

Ramifications of Kaznacheyev's experimental results

- At least one harmonic interval is necessary for the effect to be evidenced in the target cells.
- Interestingly, if we assume the body dielectric to be isotropically nonlinear (to first order):
  - Velocities of the actual transmitted frequencies depend upon the particular point on the wave amplitude.
  - The transmitted frequencies overshoot, interfere, breakup, etc. The difference frequency does not.
  - The "difference frequency" is transmitted through the nonlinear dielectric medium as if it were a sine wave passing through a linear medium*.
- To our knowledge, this direct and deep communication of electronic "hash" difference frequencies in dielectric human bodies has not been investigated in the West.

* Owen Flynn, "Parametric arrays: A new concept for sonar," Electronic Warfare Magazine, June 1977, p. 107-112.

Ramifications of Kaznacheyev's experimental results (2)

- A heterodyne signal -- at the difference frequency between an input signal and a reference signal -- can be enhanced by adding noise*.
- Thus the signal of the disorder in the cellular pattern emitted from diseased cells, received by normal cells, can be amplified electronically and rather easily.
- Powerline radiation (electronic smog) thus carries its own amplification mechanism. Eventually the amplification overcomes any squelching by sunlight, etc.
- The Russians promptly (as early as the late 1950s) weaponized and tested these and similar effects.

* Dykman, M. I. et al., "Noise-enhanced heterodyning in bistable systems," Physical Review E, 49(3), Mar. 1994, p. 1935-1942

Weaponization of Kaznacheyev's findings

And its ramifications

"Microwave" radiation of the U.S. Embassy in Moscow.

Former U.S. Embassy in Moscow.



BACKGROUND

- Began in latter 1950s
- Discovered on VP Nixon's trip
- Initially thought to be *nuclear* radiation (Discovered w/Geiger counter)
- High level target -- U.S. Ambassador
- Guarantees personal attention of:
  - U.S. Ambassador to USSR
  - U.S. President
  - NSA, CIA, DIA, NSC, etc.
  - Top consulting scientists
  - Leading U.S. scientific institutions
- Two U.S. Ambassadors died, another sickened
- Anomalous health changes in personnel, only in zero-field (zero pot'l gradient) areas!
- Four U.S. Presidents requested Soviets cease
  - Cut from 18 watts/sq cm to 2
  - Then again increased
- No one could understand what was going on
- Aluminum screens were placed over windows
- Moscow was declared a hazardous duty zone

Ramifications of the microwave radiation of the U.S. Embassy

- The cellular disorder pattern in the EM radiation is carried by the field-free scalar potential.
- Since the disorder pattern is a "conglomerate", it must be carried by an internal EM structure existing inside the scalar potential itself.
- Whittaker decomposed the scalar potential into the appropriate internal longitudinal EM biwave structure in 1903*.

* E. T. Whittaker, "On the Partial Differential Equations of Mathematical Physics," Mathematische Annalen, Vol. 57, 1903, p. 333-355

The importance of time as energy, and the time-domain



Time as energy



- In physics, the fundamental units one uses in his model are arbitrary.
  - A valid model can be made using only one unit.
  - It is already done in one branch of physics, using length as the single fundamental unit.
- Make a model with a single unit, the joule.
  - All other entities become functions of the joule.
  - We are familiar with mass as highly compressed EM energy, by the factor c^2.
  - It turns out that time is also highly compressed EM energy, by the factor c^2.
  - 1 sec. $\approx 9 \times 10^{16}$ joules.

How to see that "time is compressed spatial energy"

- Take some spatial EM energy and compress it by c^2
- Place it in 3-space, and it is *mass*.
- Place it on the time axis, and it is *time*.


PRESS
SOME
SPATIAL
ENERGY
PRESS
by c^2
PUT IT ON 4TH
MINKOWSKI AXIS
OR
PUT IT IN
3-SPACE
time (seconds)
time axis
mass (kilograms)
3-space

- When time-energy is converted into mass-energy, time is "decompressed" (expanded) into 3-space EM energy and 1 sec. $\approx 9 \times 10^{16}$ joules.

Time as EM energy in the time domain, with a density the same as mass-energy



- Bearden* reinterpreted (corrected) the 1903 Whittaker decomposition of the potential in 2000.
- The reinterpretation is consistent with broken symmetry in particle physics, for which Lee and Yang received the Nobel Prize in 1957.
- It is also powerfully supported by quantum field theory, notably by Mandl and Shaw in 1984**.
- Whittaker's pair is a combined time-polarized (scalar) EM wave and a 3-space longitudinal EM wave.

* T. E. "Giant Negentropy from the Common Dipole," Journal of New Energy, 5(1), Summer 2000, p. 11-23.

** F. Mandl and G. Shaw, Quantum Field Theory, Wiley, 1984, Chapter 5.

All EM energy in 3-space freely comes from the time domain



Longitudinal EM wave incoming from time domain and absorbed

Charge's 720º spin transforms time-energy into 3-space energy

Longitudinal EM waves emitted in all directions in 3-space

Whittaker, Math. Ann., 57, 333 (1903) shows this rigorously, when properly reinterpreted. Dipole's broken 3-symmetry is well-known in particle physics

Note: Whittaker (and others) interpreted the phase conjugate half set of LWs after interaction with the charges of the dipole, and as a 3-space *effect* rather than the time-domain *cause*. This fundamental non sequitur was just repeated since then, until corrected by Bearden to be consistent with broken symmetry and quantum field theory.

Strong support from quantum field theory



- Quantum field theory recognizes four photon polarizations:
  - Energy along x-, y-, z-, or t- axis.
  - Polarized along x- and/or y-axis, the photon is a *transverse* photon.
  - Polarized along z-axis (along its line of motion in 3-space), the photon is a *longitudinal* photon.
  - Polarized along the time-axis, the photon is a *time-polarized* or *scalar* photon.
- The individual longitudinal or scalar photon is not observable*.
- The combination of a longitudinal photon and a scalar photon is observable as the instantaneous scalar potential*.

* F. Mandl and G. Shaw, Quantum Field Theory, Wiley, 1984, Chapter 5.

Mechanism generating the flow of a mass through time




SPATIAL
SPATIOTEMPORAL
L^2 T PHOTON
SPATIAL
PHOTON
MASS
L^3
MASSTIME
L^3T
MASS
L^3
L^2 T
SPATIAL AND SPATIOTEMPORAL
"MASS"
MASSTIME
L^3T
MASS
MASS
MASSTIME
L^3T
"MASS"

© 1995, 1997 T.E. BEARDEN

$$(\Delta E)(\Delta t) + M \Rightarrow (M+\Delta M)\Delta t \Rightarrow M + (\Delta E)(\Delta t)$$

Flow of macroscopic time (observable photon interactions)

Flow of microscopic time (via virtual photon interactions)

Mechanism is engineerable

Pumping a mass in the time-domain will time-reverse it back to an earlier state

- The reinterpreted biwave EM structure of the scalar potential means that time-reversal (phase conjugation by pumping in the time-domain) can be utilized to time-reverse a targeted cell (its mass-energy) in its entirety, including its genetics.
- Becker's bone fracture experiments showed it:
  - Weak scalar potential across the fracture site.
  - LWs in 3-space and time-energy waves in time
  - Red blood cells entered, dedifferentiated by shucking their hemoglobin and growing a nucleus, which is dedifferentiation (time-reversal of the cell and its mass-energy back to a previous physical state).

Principle for time-reversing a time-pumped mass



- Becker's cells then redifferentiated and changed -- first to primitive cartilage cells, then to primitive bone cells which were deposited in the fracture, healing it with new bone growth.
- This shows "time-forwarding" (redifferentiation) of the cell also.
- Becker actually showed that the *time-domain pumping* of the cells (by the time-polarized EM waves of Whittaker's reinterpreted wavepairs comprising the scalar potential), and the time-pumping of their mass-energy, operated to continuously and steadily *remove the delta between that cell's present condition and its former "normal" cellular physical condition in that area*.
- This is the long-sought secret of stem-cell research.
- Phase conjugate optics had not been born at the time. Without realizing its full nature, Becker demonstrated the body's own internal mechanism for healing, and the fundamental mechanism for time-reversing a physical mass, whether living or inert.

Mechanisms for use in medical treatment and healing

And ramifications

Successive deep penetration reactions of the cellular dielectric

- Change after change affects the cell and all of its parts, including from the external environment.
- Each successive change affects primarily the internal "LW EM structures and dynamics" comprising the ordinary potentials, fields, and waves.
- Thus in positive time the internal EM structurings produce successive "overlaid layers of change" -- so to speak -- in the internal EM structuring and dynamics of a cell in the body. These layers contain the "delta" from normal state.

Successive deep penetration reactions of the cellular dielectric (2)

- During time reversal, highest layer deltas are successively "peeled away" by the interaction of the mass-energy with the time-domain pumping.
- The result is to return the cell directly back to successive physical states, in the case of a single disease or disorder.
  - A cancer cell is returned to a normal cell prior to its "promotion".
  - An HIV-infected cell would be returned to its normal unaffected condition, free of HIV-induced genetic change.
  - For injuries and damage, the existing "delta" in each successive state-layer is steadily reduced to zero.
- This process thus can involve both cellular differentiation and dedifferentiation, as shown by Becker and by Prioré.

Engines (vacuum engines, spacetime curvature engines)

- Following Whittaker* as reinterpreted**, all normal EM fields, potentials, and waves decompose into sets of longitudinal EM waves (LWs) and their dynamics.
- Since these LWs and their dynamics are dynamics in the local energy density of spacetime (ST), they constitute *ST curvatures*.
- Hence they are general relativity infolded inside electrodynamics.
- By manipulating and changing these LWs, one manipulates and changes spacetime curvatures and their dynamics.
- The result is a unified field model where one directly controls and engineers a set of ST curvatures by use of higher group symmetry electrodynamics.
- Controlled patterns of local curvatures of ST are called "vacuum engines" or "spacetime curvature engines" -- or just "engines".

* E.T. Whittaker, Math. Ann., 57, 333-355 (1903); Proc. Lond. Math. Soc., Series 2, 1, 1367-372 (1904).

** T. E. Bearden, J. New Energy, 5(1), 11-23 (2000).

Pumping with EM time-polarized waves forms *amplified* antiengines



INPUT (engine resident in the mass itself)

Type text

A_4

Time domain longitudinal EM pump wave

A_2

A_2^*

MASS previous state

CELL MASS

highly nonlinear to any and all LW frequencies

Antiengine acts upon mass at all levels

Type text

A_3

AN AMPLIFIED VACUUM (SPACETIME) ANTIENGINE IS FORMED AND ACTS ON THE MASS, TIME-REVERSING IT AND ALL ITS COMPONENTS NO MATTER HOW SMALL

Time domain longitudinal EM pump wave

A_1

A_1^*

© T.E. BEARDEN 1997

A DRAMATIC EXTENSION TO NONLINEAR OPTICAL PUMPING


transverse pump wave
A 2
transverse signal wave (input)
A 4
PPCM
A 3
NONLINEAR MEDIUM
amplified phase conjugate replica transverse wave (time-reversed)
transverse pump wave
A 1

a. Pumping with transverse EM waves produces a time-reversed *wave*.


PREVIOUS VACUUM ENGINE
PREVIOUS MASS STATE
+ t
TIME AXIS
A 2
t 2
RESIDENT VACUUM ENGINE (input)
MASS
Output
AMPLIFIED VACUUM ANTIENGINE
A 1
t 1

b. Pumping with longitudinal EM waves A_1 and A_2 time-reverses *the mass itself*.

Time-reversal of a mass to a new physical state not in its past

- Original engine A'
- New engine B' added
- Time-pumping moves to new "past" that is determined by (A'+B')


VACUUM ENGINE A'
VACUUM ENGINE (A' +B')
VACUUM ENGINE B'
TIME AXIS A
A 2
MASS
TIME AXIS (A+B)
TIME AXIS B
AMPLIFIED VACUUM ANTIENGINE [A' + B']
VACUUM ENGINE B
VACUUM ENGINE A
A + B
A 1

Extended general relativity principle

- All levels of energy structures and all levels of time structures mold spacetime geometry.
- The "pattern" is called a *template* for a vacuum engine (spacetime curvature engine).
- Spatial and temporal structurings of the engine act upon any exposed mass at al levels.
- This produces a template of forces, for precise translations and stresses within the mass at all levels. The forces exist in both time and 3-space.


ACTIVE SPACETIME
DYNAMIC MASS
STRUCTURING OF ACTIVE SPACETIME CURVATURES

Engines: Working spacetime demons



Internested patterns
of spacetime
curvatures

Highly Structured
Einsteinian spacetime

Maxwellian Demons
are EM hidden variables
organized into dynamic
structures acting at all levels

**Demons work
at all levels**

Signal vs. vacuum engine



- ★ Information received
- ★ Any overt physical action must be taken by cell itself
- ★ Cell must furnish the energy for any action it takes
- ★ Passes from outside to in

A. *Cell must do the action itself; vacuum energy exchange is passive. Energy or fuel for doing the action must be added to cell externally.*



- ★ Information itself acts
- ★ Local spacetime curved, with internal subcurvatures
- ★ Produces template of forces in local spacetime (ST)
- ★ Arises from within local ST
- ★ Acts on and changes all parts of cell, including its genetics

B. *Cell is acted upon; vacuum energy exchange does the specific action. No energy or fuel for doing the action need be added to cell externally.*

Unified field theory requires modeling and use of supersystem

Three components interact with each other:

- System and its dynamics
- Local active vacuum and its dynamics
- Local curvatures of spacetime and their dynamics.



LOCAL ACTIVE VACUUM

SYSTEM

LOCAL CURVATURES OF SPACETIME

Classical EM kills the supersystem, prevents supersystem engineering

- Assumes flat local spacetime
- Assumes inert vacuum


LOCAL ACTIVE VACUUM
SYSTEM
LOCAL CURVATURES OF SPACETIME

Malignant teratoma exhibits both time-reversal and fast-forwarding

- A teratoma cell is a tumor cell that has reverted to stem cells, then proceeds to differentiate toward new kinds of normal cells.
- May produce hair, skin, muscle, heart, bone, and other type cells.
- Sometimes present at birth.
- Demonstrates both "time-reversal" and "time-forwarding".
- The missing key is the engine function(s).

Miller-Fox-Urey biogenesis experiments

- Engines of and from all life forms ever on earth or in the universe exist in the ambient vacuum potential.
- The Miller-Fox-Urey experiments were not in a "sterile" environment.
- Heat (IR) and UV constitute (1) a harmonic interval with a difference frequency, and (2) amplifying by the process previously shown.
- These experiments "kindled" previously living forms from the available gases etc. by amplifying the ancient living engines from their virtual state to the observable state, so that the masses were molded into the physical states of their templates.

Biogenesis Experiments


To spark coil
Electrode
Sparking
Organic molecules
Gas molecules
Condenser
Gaseous mixture of ammonia, methane, carbon dioxide, hydrogen, and water vapor
Boiling water

Cloning to produce stem cells

- Human DNA can be inserted in an animal cell, and the cell chemically tricked into proceeding as if fertilized.



- Formation, increase, and growth of stem cells begins and continues.
- The "engine" carried by the human DNA is changing the matter available into human cells.
- readily demonstrated experimentally.

Regeneration in a strain of rat with part of its immune system missing

- In mammals, the immune system plays a role in reducing the regeneration capability, compared to that of more primitive systems.
- In a strain of rat where that "suppressive" part of the immune system is missing, the regenerative capability is dramatically increased.
  - Can regrow cut away sections of tail.
  - Regrows plug cut out of ear.
  - Reconnects severed optic nerve.
  - Partially restores severed spinal cord.

- The suppressive "delta" engine of the immune system, operating simultaneously with the underlying primitive regenerative engine, sums to the modern much-reduced regenerative engine in the mammal.

An observation for the future

- When the science of engines is developed, physicians will be able to tailor these engine combinations to restore severed human spines, regrow severed limbs, etc.
- They will also be able to direct the body's "normal growth" to reduce and direct birth defects, genetic defects, etc.



Biochemistry and EM models

- Medical scientists analyze such things as teratomas in terms of biochemistry and the biochemical model.
- An assembly of charges and charge distributions, with their associated fields and potentials, drives all chemistry at base level.
- The charge assembly and its dynamics involves a corresponding assembly of spacetime curvatures and their dynamics. These are *the cause that is driving the charge assembly and its dynamics, and therefore the chemistry*..
  - In unified field theory (such as that of Sachs) and O(3) electrodynamics.
  - Not in classical U(1) EM theory or quantum electrodynamics.
- Conventionally a causative EM field in space is "defined" as the *diversion from* that spatial field by and after its interaction with charge). The "definition" substitutes the effect for the cause, a non sequitur.
- This is a known major flaw, pointed out in one fashion or another by many physicists such as Wheeler and Nobelist Feynman.
- Classical EM theory is a 137-year-old model, seriously flawed. These flaws emerge in biochemistry and medical science.

Necessary EM corrections*

- Many of the corrections necessary in electrodynamics modeling either have been done or are underway.
- Higher symmetry, non-Abelian electrodynamics models have long been developed in particle physics.
- The new approach extends these models to also incorporate general relativity, thus producing a unified field theory*.
- In the new approach, spacetime curvature engines are perfectly natural and understandable, and can be directly modeled and engineered by advanced theorists.
- In short, the theory is sufficiently advanced and robust that technology and engineering can now advance.
- This will be a great leap forward for biochemistry and medical science, particularly in therapeutic methods.

* Sachs's unified field theory implemented by O(3) electrodynamics presently is the most suitable to use. Numerical methods are required.

Prioré's revolutionary results in lab animals

And its ramifications

Prioré (right) makes a point to Chaban-Delmas, Mayor of Bordeaux

- Many of the Prioré team's experiments were done in Bordeaux.
- Antoine Prioré patents:
  - "Apparatus for producing radiations penetrating living cells," U.S. Patent No. 3,368,155, Feb. 6, 1968.
  - "Method of producing radiations for penetrating living cells," U.S. Patent No. 3,280,816, Oct. 25, 1966.
  - "Procede et dispositif de production de rayonnements utilisables notamment pour le traitement de cellules vivantes," [Procedure and Assemblage for Production of Radiation Especially Serviceable for the Treatment of Living Cells], Republique Francais Brevet d'Invention P.V. No. 899.414, No. 1,342,772, Oct. 7, 1963.



Block diagram of Prioré's method

Time-reversing the cells back to normal state



START

SELECT A SET OF TRANSVERSE EM WAVES

MIX WAVES IN A PLASMA, CONVERT TO LONGITUDINAL. EM WAVES

MIX OUTPUT INSIDE STRONG PULSED DC MAGNETIC FIELD

EXPOSE WHOLE BODY OF PATIENT TO DIMENSIONED MAGNETIC FIELD

CELL AND ALL ITS PARTS ARE PUMPED IN INNER EM CHANNEL IN TIME DOMAIN

VACUUM ENGINE FOR DISEASED CELL ALREADY PRESENT

DISEASED CELL PHASE CONJUGATES ITS VACUUM ENGINE

FORMS AMPLIFIED VACUUM ANTIENGINE FOR CELL'S DISEASE VACUUM ENGINE

TIME-EXCITATION CHARGING ENDS. IRRADIATION IS HALTED.

ANTIENGINE CONTINUES TO ACT AND TIME-REVERSE CELL AND ALL ITS PARTS*

CELL RESTORED TO NORMAL?

YES

STOP

NO

ADJUST WAVE FREQUENCIES IF REQUIRED, AND IRRADIATE AGAIN

*Includes genetics



In Laboratory Animals:

Prioré Team Cured

- Terminal malignant tumors
- Clogged arteries (atheriosclerosis)
- Suppressed Immune Systems
- Infectious trypanosomas
- *Results were presented to French Academy of Science by Robert Courrier, Director of the Biology Section of the Academy*
- ***No one understood the mechanism!***

© 1999 T. E. BEARDEN

Some peculiar results by the Prioré team

- Once a rat is cured of a particular disease:
  - A single drop of blood from the cured rat, injected into another rat stricken with same disorder, would result in the injected rat getting well slowly.
  - This ability to transfer immunity and healing in the extracted drop of blood gradually decayed over a period of a few weeks.
- Showed that even the fields and potentials in the blood had been altered internally, in the treated animal.
- Showed that the injected animal's cellular regenerative system possessed the ability to also time-domain pump over the entire body, everywhere reducing the delta between that injected drop of blood now the rat's own, and the rest of the blood in its body.

Proof of cellular time-reversal

- Pautrizel compared identical treatment of immature rats with immature immune systems, and mature rats with mature immune systems.
- Treatment restored the damaged mature system back to full mature functioning, and it promptly recognized and dispatched the pathogens.
- Treatment restored the damaged immature system back to full immature functioning, unable to cope, and the pathogens promptly reinfected and killed the immature rat.
- The lesson: The body is indeed returned to a previous physical state. The pathogens themselves are not killed by the treatment, but by restoring the ability of the immune system to recognize and destroy them.
- Only the *previous ability* of the immune system is restored by the process.



PROF. RAYMOND PAUTRIZEL
(Renowned Parasitologist)

Disadvantages of Prioré method

- Large plasma tube and facility required.
  - 3-stories high building bay if to treat humans.
  - Long irradiation time (2-3 hours).
  - Slow, numerous experimental adjustments.
- Fundamental mechanism was unknown.
  - Phase conjugate optics not yet born in West.
  - No higher symmetry EM modeling used.
  - Prioré thought it was a result of ionization.
  - Importance of difference frequency unknown.
  - Body dielectric transmission path unknown.

3-Story high Prioré device for treating humans

- At the end of the project, Prioré had developed a large unit to treat humans.
- A few were treated.
- Cures replicated what had been done in lab animals
- The massive size of the unit and long treatment time (hours) made the process bulky and very inconvenient -- and also expensive


Giant coil around 12-ft long plasma tube
Pulsed DC Magnetic field
Table for reclining human body

17-foot Prioré plasma tube

Used in large machine (3-stories high) to treat a limited number of human patients



A proposed new mechanism for cancer promotion

● ● ● ● ● ● ● ● ● ● ● ● ● ● ● ● ● ●

And its ramifications



Remarks on cancer from a new perspective

- Two stages: cellular damage and promotion of the damaged cell to a tumorous cell. Promotion presently is poorly understood if at all.
- A master cellular control system (MCS) (studied by Popp et al.) controls both the immune system and the cellular regenerative system, as well as normal functions of the cells.
- The "past history" of ancestral development of aerobic cells and higher multicell aerobic bodies on planet Earth, resides in the "internested engine layers" in every tiniest part of the entire body dielectric, and in all cells.

Remarks on cancer from a new perspective (2)

- Faced with cell damage (such as sustained hypoxia) it cannot handle, the MCS continues to "peel the layers" in taking actions related to ever more distant pasts.
- Faced with continuing hypoxia, e.g., the MCS eventually reaches ancestral layers -- with an engine -- it forces the damaged cells to start moving back toward the original primeval anaerobic form.
- The first step backward is *separation from central growth control*, freeing the cell to multiply independently. At the same time, genetic changes in the cell are forced and produced, starting it back toward becoming an anaerobe.
- These actions comprise the *promotion process*.

The promotion process via engines


"ENGINE" USED TO PRODUCE " DELTA
PRESENT STATE ENGINE
MOST RECENT PAST STATE THAT WAS "NORMAL"
MORE DISTANT PAST STATE THAT WAS "NORMAL"
FURTHER PAST STATE THAT WAS "NORMAL"
PAST STATE BEFORE CENTRALIZED CONTROL
PRIMEVAL ANAEROBIC STATE BEFORE AEROBES
LAYER ENGINE SELECTED
LAYER AND ENGINE SELECTOR
MASTER CELLULAR CONTROL SYSTEM
IMMUNE SYSTEM
CELLULAR REGENERATIVE SYSTEM
DELTA ENGINE
START
IS THERE A DELTA?
Y
N
DELTA ELIMINATED?
N
Y
STOP
INJURED CELLS
RESIDENT ENGINE

Evolution of aerobic systems



ESSENTIALLY ANAEROBIC ATMOSPHERE

CHANGE OF ATMOSPHERE TO AEROBIC (INCLUDES OXYGEN)

BIOGENESIS

SINGLE CELL ANAEROBIC

OBLIGATORY ANAEROBES SINGLE CELL SHIELDED FROM OXYGEN

FACULTATIVE ANAEROBES (SINGLE CELL BOTH AEROBIC AND ANAEROBIC)

EVOLVE TO

SINGLE CELL AEROBIC*

EVOLVE TO MULTICELL AEROBIC* (INCLUDES MAN)

CENTRAL CONTROL

SINGLE CELL COMPONENTS

- IMMUNE SYSTEM
- RED CELLS
- WHITE CELLS
- KILLER CELLS
- ETC.

MULTICELL COMPONENTS

- TISSUES
- MUSCLES
- BONES
- ORGANS
- SKIN
- STRUCTURES

** NOTE: LIMITED ANAEROBIC RESPIRATION STILL TAKES PLACE IN HIGHER AEROBIC LIFE FORMS, INCLUDING MAN.*

EVOLUTIONARY TIME

First step in self-promotion of cancer due to hypoxia



PAST

PRESENT

MULTICELL AEROBIC
(INCLUDES HUMANS)

SINGLE CELL
ANAEROBIC

SINGLE CELL
AEROBIC*

CENTRAL CONTROL

OXYGEN-RICH

TIME-FORWARD
PATH AS IT
DEVELOPED

CANCER CELL

TIME-REVERSED
PATH FOR SUSTAINED
OXYGEN DEFICIENCY

PARTIALLY
ANAEROBIC

SINGLE CELL
AEROBIC

FIRST STEP IN OXYGEN-DEFICIENCY
DEDIFFERENTIATION

Block diagram of the cellular regenerative system



ADD PUMPS

B

CELL AS A PHASE CONJUGATE MIRROR

RESIDENT VACUUM ENGINE

ANTIENGINE PRESENT?

N

Y

APPLY ANTIENGINE

B

A

PRIORÉ AMPLIFIED PUMPING

START

A

CYCLE

CELL AND INTERIOR SENSORS

LOCAL VICINITY SENSORS

NONLOCAL ALL-BODY SENSORS

DELTA CATALOGS

CELLS AND INTERIORS

SELECT LOCAL

SELECT NONLOCAL

AEROBE

ANAEROBE

Y

N

DELTA?

AEROBE

ANAEROBE

Y

N

DELTA?

AEROBE

ANAEROBE

Y

N

DELTA?

AEROBE

ANAEROBE

SWITCH TO AEROBE CONTROL SYSTEM

A

Y

CROSS THRESHOLD BACK TO AEROBE?

N

SWITCH COMPARATIVE CATALOG

SWITCH TO ANAEROBE CATALOG

Y

END OF AEROBE CATALOG?

N

SUM FOR ENTIRE BODY

SWITCH ON CENTRAL, OFF DECENTRAL GROWTH CONTROL; RESET IMMUNE SYSTEM

SWITCH OFF CENTRAL GROWTH CONTROL

SWITCH ON DECENTRAL GROWTH CONTROL

CONDITION IMMUNE SYSTEM TO ACCEPT

A

R&R SYSTEM

Regeneration Example

© T.E. BEARDEN 1998

Bombshell: Amplified EM healing

- A unified field theory approach and use of supersystem analysis has broken the basic mechanism for healing itself.
  - The Sachs unified field theory applies and has been partially fitted.
  - Evans-Vigier O(3) electrodynamics can properly model it, including both the internal and external electrodynamics and effects of engines.
  - Direct engineering development is now possible.
- Experimental proof of the results obtainable already exists in the literature.
- A medical revolution is in the offing.

Potential Medical Applications

- Non-traumatic cancer treatment
  - *Cure cancers and leukemias of all types*
  - *Remove pre-cancerous state*
  - *Restore system*
- Treat and cure Infectious diseases
- Cure AIDS and restore immune systems
- Defense against biological warfare
  - *Virulent diseases from unknown agents*
  - *Treat, cure prior to symptoms developing*
  - *Both civil populace and armed forces*
- *Dramatically lower health costs*
- *Rejuvenate the aged*

© 1999 T. E. BEARDEN

To treat and save mass casualties: What is urgently needed now:

- A small, portable, relatively inexpensive treatment unit, not requiring plasmas etc.
- Treatment in 2 to 5 minutes rather than 2-hours.
- Simple treatment application, almost anywhere.
- Effective in advanced stages as well as prior to emergence of symptoms.

- Effectiveness against a wide array of illnesses.
- Use is easy, high school student can be trained in 30 minutes.
- Crash program to develop, flood down through emergency systems in great quantities.

The Solution:

- Two blankets have antennas in them.
- Uses the "porthole" concept (discussed shortly)
- Eliminates plasma tube mixing etc.
- Computer-controlled complex signal structure.


Equipment Case


Computer Control Unit
Signals Function Generator
Antenna Pad

The Porthole concept:

The two-minute treatment shortcut



How the porthole concept works


INSIDE THE BODY
OUTSIDE THE BODY
Body surface
Dielectric channel
as a body "porthole"
Time
Reversal
"my engine is..."
Amplifier/mirror
"Reverse your engine..."
PAST
HEALTHY
CELL
THEN
INTERIOR
SICK
CELL
NOW
Antiengine
maker

Porthole concept: An analogy of the dielectric path and inner-outer functional connections

- Imagine perfectly reversible dynamic light processes inside a large "cruise ship", that are also perfect phase conjugate mirrors
- Each process receives, absorbs, and emits light continuously
- Light escaping through the portholes is a composite from all the dynamic processes ongoing inside
- If we record and amplify the escaping light, then force it back through the portholes, it reverses all the internal processes
- The processes revert back, slowly, to a previous ongoing process state
- We cease radiation, and the processes reverse and move forward again



Porthole concept: The discovery

- The processes themselves, *in their own "frame"*, are never actually "reversed". Instead, the frame's motion through time is reversed.
  - Each to itself moves normally -- just receiving, absorbing, and radiating light, regardless of "whatever light" is interacting
  - This is due to a peculiarity of the photon and photon interaction
- Photon interaction creates observed physical reality, including the "frame" and the seeming "passage of a mass through time"
  - The photon is its own antiparticle, which is just a photon traveling in the opposite direction
  - So in this case we can use "light" to precisely time reverse (to the observer) the frame and the apparent operations (to the observer)
- When we cease irradiation, after a decay period to remove the reversed excitation, all functions are now seen to be moving forward normally in observer forward time, but from a previous physical state or condition

Using the porthole concept: Research

- The body's own emitted dense, broadband signals are recorded across a broad bandwidth
  - These signals are amplified, then rebroadcast precisely back into the body
  - This returns an amplified "reversed" signal set back through the dielectric path, invoking and applying the porthole concept in all processes
- The returning photons produce time-charging but in reversed frame direction
  - Tremendous potential energy is absorbed in highly compressed "time-energy" form in seconds
  - This "time-potential" slowly drains off as the body processes and cells reverse back to a previous state

Research using the porthole concept



Alterations Database

Recorders & Broadband Amps

TIME DENSITY CHARGE IS STRUCTURED TO CONTAIN THE PRECISE SPACETIME CURVATURE ENGINES FOR TIME-REVERSAL AND STEERING. CHARGING OCCURS QUICKLY. ENGINES CONTINUE TO WORK FOR AN EXTENDED PERIOD AFTER CHARGING CEASES.

Control Unit

Broadband Antenna Unit

Receiver-transmitters

Adjusting broadband signals bandwidth and amplification by selecting indicated alterations from database

© T.E. BEARDEN 1998

Portable unit then developed for rapid treatment of mass BW casualties

- Two blankets have antennas in them.
- Uses the "porthole" concept (discussed shortly)
- Eliminates plasma tube mixing etc.
- Computer-controlled complex signal structure.
- Irradiation for 2 minutes.


Equipment Case


Computer
Control Unit
Signals
Function
Generator
Antenna Pad

Training to use the unit

- High school student level, 30 minutes.
- Patient lies on one blanket, other covers him.
- Set the prescribed standard signal sets from listing.
- Computer-controlled generator produces the signal.
- Irradiation for 2 minutes, uncover patient, bring in another.
- Unit can be self-powering from vacuum energy (MEG*).


Equipment Case


Computer
Control Unit
Signals
Function
Generator
Antenna Pad

Additional advantages

- Can be developed in a crash program in 2-3 years.
- After sunk costs, projected cost per unit in mass production is less than $100,000
- Can be produced by the thousands
- Then flooded down through
  - Fire stations and police stations
  - Red cross units, hospitals, clinics
  - Emergency action teams and armed forces
- Large numbers of operators easily produced
- Emergency training could be watching a 15 minute film, then performing one graded practice run
- First generation equipment can save some 70% of the coming mass casualties from anthrax etc.





Terrorist BW warfare capabilities against the United States

The growing threat

Mass Casualty Problem: Aerial Anthrax Spray on Washington, D.C.

- One terrorist, one light aircraft with spray tank
- 100 kilograms of anthrax
- Flies over greater metropolitan Washington, D.C.
- Calm night
- *1-3 million casualties result**
- *Most of those stricken will die*
- Presently little can be done to save the stricken civilians
- *Attacks on several population centers might produce some 10 million or more casualties*

*Per OTA Report to Congress, 1993

For decades, infiltration of terrorist teams into the U.S.

- From several foreign nations, not just Bin Laden in Afghanistan
- Several thousand Cuban guerillas, from training camps in Southern Mexico
- Russian Spetznaz teams
- Nuclear warheads (up to 80 KT)
- Biological warfare agents
- Yakuza in oriental populations in our cities
  - Yakuza manufactures Russian energetics weapons in their own facilities in Japan
  - Possesses the new EM weapons referred to by Secretary of Defense Cohen in 1997
- We are now in a very long, hard war and will suffer millions of casualties in our cities. It may last for decades.

Defense Secretary Cohen*

(Involvement of secret superweapons)

"Others [terrorists] are engaging even in an eco-type of terrorism whereby they can alter the climate, set off earthquakes, volcanoes remotely through the use of electromagnetic waves… So there are plenty of ingenious minds out there that are at work finding ways in which they can wreak terror upon other nations…It's real, and that's the reason why we have to intensify our [counterterrorism] efforts."

* Secretary of Defense William Cohen at an April 1997 counterterrorism conference sponsored by former Senator Sam Nunn. Quoted from DoD News Briefing, Secretary of Defense William S. Cohen, Q&A at the Conference on Terrorism, Weapons of Mass Destruction, and U.S. Strategy, University of Georgia, Athens, Apr. 28, 1997.

Some typical BW agents

- Smallpox, including different strain developed by Russia (some sold to terrorists)
- Anthrax
  - Over 400 known locations around the Earth have cultures
  - Difficult to decontaminate
- Bubonic Plague
- Botulism toxin
- Tularemia (rabbit fever)
- Hemorrhagic fevers, such as Ebola



Anthrax

- OTA study: Some 200 pounds released in a spray, on calm night over Washington, D.C. could result in up to 3 million casualties
- Symptoms usually in 2-10 days
  - Sometimes as long as 7 weeks
  - Flu-like symptoms



- Then 1-3 days later, shock and breathing problems cause death in up to 100%
- Antibiotics given early (before symptoms) can prevent infected persons from becoming ill
- Limited vaccine, reserved for military

Smallpox

- More than 500 million people killed in the 20th century before "eradicated" in 1977. Vaccination ceased in 1980.
- Russians kept it, developed new strains, sold to terrorists
- Symptoms in about 12 days: fever, headache, nausea. Rash similar to chickenpox then appears.
- Rash turns into hard blisters. *Highly contagious*, kills one-third of its victims.
- No cure. About 12 million doses of vaccine left.
- If smallpox is unleashed in any major city on earth, it will eventually kill 2 billion, or about 1/3 of the human species -- unless a radical new cure is found and utilized.

Bubonic Plague: Historically the most feared (Black Death)

- From 1980-1994, 18,739 cases in 20 countries.
- Symptoms occur in 1-6 days after inhaling the pneumonic form.



- High fever, cough, labored breathing lead to respiratory failure and death.
- It is contagious.
- Rapid use of antibiotics can be effective.
- Vaccine not currently produced in the U.S.

Botulism toxin (a nerve toxin)

- Single most poisonous BW substance known.
  - Typically borne in food, contacted by eating.
  - Could be developed as aerosol weapon.
- Symptoms in 24-36 hours; blurred vision and difficulty swallowing, speaking.
- Paralyzes muscles, leading to respiratory failure and death.
- Centers for Disease Control and Prevention maintain a botulism antitoxin supply.

Tularemia



- U.S. studied its weapon potential in 1950s and 1960s.
- Symptoms appear in 3-5 days, including fever, chills, headache, and weakness
- Inflammation and hemorrhaging of the airways can lead to death.
- Without antibiotics, one-third die. Can be 90% if breathed in, in aerosol form.
- Vaccine developed and under review by FDA.

Hemorrhagic fevers, such as Ebola

- E.g., origin of Ebola is unknown. Probably transmitted to humans by animals, to begin a breakout.
- Symptoms in 3-5 days, include fever, aching muscles, diarrhea.
- Hemorrhaging of fluids out of tissues and orifices.
- From 30 to 90 percent die, depending on specific fever type.
- Some of these fevers respond to antiviral drugs.
- The drugs are in short supply.
- Presently *containment* is the primary goal.

A factor the U.S. does not know

(Secret involvement of clandestine superweapons)

- Three nations (not the U.S.) developed quantum potential weapons using Bohm's hidden variable theory of quantum mechanics.
- Can induce disease engines in matter or bodies at a distance.
- Have developed "spreading" of immune systems in a targeted populace (cleverly tested in Gulf War against U.S. troops).
  - Cocktail mix of disease engines for 2 dozen different diseases
  - Targeted area's human immune systems react to these engines when they are still in virtual state, just below quantum threshold.
  - Spread immune system's resources thus "thinned" across response to two dozen shadow diseases at once.
- Hit with a terrorist BW attack, the spread immune systems are overwhelmed much more easily and quickly.
  - Yield (casualties) of the attack is increased by factor of 3-5.
  - Spreading of U.S. immune systems has been accomplished and is still being maintained.



Summary and conclusion

The new war

A new Pearl Harbor: Strike on the World Trade Center in NYC

- The North Tower has already been struck and is burning.
- A second jetliner is about to strike the South Tower.



CNN PHOTO
Morning of 11 Sep. 2001
World Trade Center, NYC

Fireball From Impact on South Tower

- The two buildings held some 50,000 occupants
- Evacuation was underway after the first strike
- More than 6,000 persons were killed
- This is more than were killed in the Dec. 7, 1941 strike on Pearl Harbor


Associated Press photo

Collapse of the South Tower

- The first tower to collapse was the South Tower
- It is still uncertain just how many people were caught inside and killed
- This is a half million tons of debris, falling from the New York skyview.

Photo from CNN

Collapse of the North Tower begins

- The North Tower then collapsed
- This was another half-million tons of debris falling from the NYC skyview



Collapse of North Tower finishes

- Collapse of the North Tower killed many rescue workers, firemen, and policemen
- At this writing, the total casualties are still unknown

Photos from CNN

Next began the recovery efforts

- Recovery operations will require months
- At this writing, the total casualties are still unknown
- The damage was done by two civilian jetliner "bombs"

The Pentagon was hit on the same day

- Hundreds were killed the same day when another jetliner struck the Pentagon.
- Yet another jetliner, possibly headed for the White House, crashed enroute when the passengers attacked the suicide terrorist hijackers.

A sobering thought



- Nuclear weapons are already smuggled into the U.S., as are BW agents such as anthrax, smallpox, etc.
- Had a 40-80kT weapon been exploded in New York and one in Washington, millions would have perished and both cities would have been devastated
- There would have been no recovery of those cities for many decades

Present Status of the WMD Threat to the United States

- **Many foreign nations are hostile to the U.S. and sponsor terrorists**
- **Some 25 nations have WMD or are acquiring them**
  - **BW agents and weapons**
  - **Chemical agents and weapons**
  - **Nuclear materials and weapons**
- **Thousands of students and émigrés**
- **Infiltrated teams, BW, other WMD already**
- **Castro guerrillas infiltrated over the years**
- **Can do unacceptable damage to U.S. now**
- ***May reach knockout capability***

© 1998 T.E. BEARDEN

***Per OTA Report to Congress, 1993**

The U.S. is terribly unprepared

- Limited medical supplies, antibiotics, vaccines
- Insufficient facilities, emergency teams
- No civilian shelters (much less BW-filtered)
- Not enough doctors, nurses, masks, etc.
- Present treatment methods woefully inadequate
- Triage will apply
  - First treat those most likely to recover
  - Others (showing symptoms, or advanced) are just set aside to die
- Other attacks are a matter of *when*, not *if*.

Conclusion

- As several cities are struck, millions of U.S. civilian casualties will result. Devastation will be enormous.
- We shall eventually lose more American lives than in all the rest of our wars to date.

- Present medical therapeutic science is totally inadequate to do the job. It cannot save us.
- At some point, when we are sufficiently damaged, the Spetznaz or other terrorists may detonate nuclear weapons in our cities, with appalling carnage.
- A combined superweapon technology and terrorist groups will then destroy the remaining populace.
- On its present course, the inadequacy of Western medicine may doom us.

A difficult truth to consider

- In any strategic strike, the first phase is to get the strategic weapons (weapons of mass destruction) delivered to their distant targets.
- That has already been done.
- Eerily, the first phase of World War III has already been accomplished.
- It was already accomplished before the Sept. 11, 2001 strike on New York and Washington. That was the new "Pearl Harbor", and only the opening round. It already killed more Americans than died at Pearl Harbor on Dec. 7, 1941.
- Unless we improve our medical therapy quickly and dramatically, we will lose -- particularly when the hidden energetics weapons and outside terrorist sponsorship by hostile nations are factored in.

A personal perspective

- There now exists an overwhelming, immediate moral imperative to get this development program done at the utmost speed humanly possible.
- The sheer survival of the United States and Western civilization depends upon it.
- Officialdom is aware that the KGB/Russians have long planned to finish the U.S., after initial nuclear exchanges, by fierce and massive BW strikes.
- It appears that the plan has changed to let the terrorists do the main work, while augmenting U.S. casualty levels by energetics weapons.

China is also involved

- China has declared South China Sea the territorial waters of China
- China will eventually take Taiwan
  - Has massed missile artillery trained on Taiwan
  - Recently held invasion practice on an island near Taiwan
- Recently deployed fearsome EMP weapons utilizing negative energy rather than positive energy (Dirac sea theory)
  - Extinguishes all electron currents
  - Duds electrical and electron systems instantly
  - Instant death to struck bodies
  - Instant kill of missiles, aircraft, electronics in nuclear warheads
  - Ultimate "death ray"; can be made small or large
- Recent 2-carrier U.S. task force maneuvered in South China Sea to caution China
  - The new Chinese EMP weapon was trained on that task force
  - Could have destroyed it within minutes

Final thoughts



- This is one of the great turning points in history.
- The development program is eminently doable. That it works has been experimentally demonstrated. The long-vexing puzzle of the active mechanism has been solved.
- Our scientific community bitterly opposes any use of electromagnetics -- even an advanced, higher symmetry electrodynamics -- for medical treatment.
- A consortium of the scientific community, the large pharmaceuticals, FDA, and the AMA will oppose this project even while the U.S. is being destroyed wholesale.
- It can only be done in the private sector, and there will likely be no funding unless by philanthropists.

Continuation

Business plan, development program, budget breakdown, proposed schedule etc. go here.

Weapons Slides

The Tom Bearden Website

Help support the research

"Others [terrorists] are engaging even in an eco-type of terrorism whereby they can alter the climate, set off earthquakes, volcanoes remotely through the use of electromagnetic waves… So there are plenty of ingenious minds out there that are at work finding ways in which they can wreak terror upon other nations…It's real, and that's the reason why we have to intensify our [counterterrorism] efforts." *

Secretary of Defense William Cohen at an April 1997 counterterrorism conference sponsored by former Senator Sam Nunn. Quoted from DoD News Briefing, Secretary of Defense William S. Cohen, Q&A at the Conference on Terrorism, Weapons of Mass Destruction, and U.S. Strategy, University of Georgia, Athens, Apr. 28, 1997.

Slides
(covers period up to 1999)

- The Coming Strategic Attack on the United States
- Outline
- Loss of two separate A-10 Warthogs in 1997
- Typical ABM Defenses (Widely Deployed by mid-70s)

- Launch Phase Anti-Missile System
- Launch Phase Anti-Bomber System
- HC-130s Engines Quit, Aircraft Crashes
  Nov. 22, 1996
- 1996 Actions by this analyst
- Additional Information Exists: Not Analyzed, Not Integrated in Briefing
- Kill of Arrow DC-8, Gander AFB, Dec. 12, 1985
- Satellite Photos of Plumes in Soviet Arctic Since 1974
  See "Fer de Lance" for additional information
- Aum Shinrikyo ("Supreme Truth" Cult), Shoko Asahara, Leader

  Aum Shinrikyo - Anatomy of a Dangerous Cult
- Ashkhabad Problem and Its Solution
- Strange Characteristics of Iran Quake, Sep. 1978
- Iran Earthquake, September 1978
- Situation Now (Assessment)
- Situation Now (Assessment 2)
- Aspects of Strong Local Asymmetry
- Mass Casualty Problem: Aerial Anthrax

Spray on Washington, D.C.

- Present Status of the WMD Threat to the United States
- Some Present Problems in the U.S. WMD Defense Capabilities
- Internal Terrorist Threat with Weapons of Mass Destruction: Now & Future
- Attempt to Ban Energetics Weapons Worldwide
- Brezhnev's Schedule
- Large glowing Tesla globe witnessed in Red China by hundreds
- Cold Explosion -- 9 April 1984 Near Kurils, and formation and growth of spherical shell (globe)
  Sequence of Events
- Cold Explosion -- 9 April 1984 Near Kurils, and formation and growth of spherical shell (globe)
  What They Were
- Cold Explosion -- 9 April 1984 Near Kurils (Plus additional weapons effects)
- Countering Insane MAD Systems:
  Find Loophole, Exploit It
- Next Generation Counter to Both Sane and Insane MAD systems
- Simultaneous Dudding of Nuclear Weapons Worldwide

- Simultaneous Dudding of Nuclear Weapons Worldwide
- Operation Divine Wind II
- Advanced EMBW Applications
- EM Biological Warfare (EMBW)
- Microwave Radiation of U.S. Embassy in Moscow
- Pentagon EMI Studies, 1989
- EM Missile Practice (6 slides)
- Subdivisions of Soviet Energetics Program
- Communism's Goal
- Manuilsky's Goal vs. Status Today (Dec. 1996)
- Professor Hellman, German Scientist Released from Work in Soviet Union
- Hemispheres and Globes of Light (4 slides)
- How Could Such Superweapons Ever Be Concealed?
- Soviets Easily Concealed These Superweapons for Four Decades
- Microscope-type, laser-like interferometer for inducing quick α-decay in samples of otherwise longer-lived isotopes
- Longitudinal Wave Interferometry: Endothermic

- Longitudinal Wave Interferometry: Exothermic
- U.S. Air Attack on Libya, April 1986
- Lightning Wall
  circa 1959-1960
- Lisitsyn's Report: Brain Code Broken
- Large Longitudinal Wave Interferometer (LWI) Accident
- Large Longitudinal Wave Interferometer (LWI) Accident
- Use of Hidden Information Content of the Field Can Provide Action-At-A-Distance
- Two Types of Mutual Assured Destruction (MAD) System
- Psychoenergetics Weapons Teams Mentally Disable All Personnel
- Strikes Against Special Ship and Energetics Weapons Sites
- "Mindsnapper" Attack on Special Ships and Energetics Weapons Sites
- How Much Off Guard Are We?
  (7 Slides)
- Possible Targets: 1995-9 Escalation Phase
- Propagation of Weapon Effects
- Yugoslav Earthquake, Followed by Cold Explosion
  April 15th, 1979

- Countering an Insane QP Weapon
- Gulf War Disease: KGB QP Weapon Induced ST Curvature Engines for a Cocktail of Diseases
- Self-Targeting in Inner EM Channel Can Produce a Quantum Potential
- Mechanism for Producing a Quantum Potential
- Major Principles for Use of Quantum Potential Weapons
- Major Principles for Use of Quantum Potential Weapons (2)
- Instantaneous Communication by a Quantum Potential
- Participants in a quantum potential share a common multiply-connected spacetime (MCST)
- Quake in Tangshan, China
  28 July, 1976
- Exchanging Earthquakes
- Instant Communication by a Quantum Potential
- Westerners Do Not React to Slow Threats
- Characterizing a Given Risk or Risk Factor
- Technical Risk Management
- Aum Shinrikyo's Sarin Facility

- In Scalar Beam Interference Zone
- Physicist Schappeller Auralaz Munster, Austria
- Initial Soviet Plan for Cold War, After WWII
- Josef Stalin: Absolute Dictator
- Exploding any Resistance by Operational Scientists
- Significant Soviet Statements
- Captain Svoboda Dives Headlong to Her Death
- T-polarized Beam Projector
- Possible Tests (1)
- Possible Tests (2)
- Possible Tests (3)
- Possible Tests (4)
- Mushroom Cloud Rising From Sea
- Launches from Cape Canaveral and Vandenberg AFB Provided Practice Targets of Opportunity
- The sinking U.S.S. Thresher, with her controls jammed, implodes when she reaches crush depth
- Embodiment of an instrument array sufficient to discriminate when time-density charging has occurred, and that transduction

of time-charge decay has occurred.

- Time-Polarized EM Wave Interferometer Creating Space-Time Curvature Engines in a Distant Interference Zone
- Transmutation of Radioactive Nuclei at a Distance
- Transmutation of Radioactive Nuclei
- Typical Tesla Shield, Northern Route of Japan
- A Curious Tide in Human Affairs
- Large Scalar EM Interferometer (LASI) Accident Near Urals, 1958
- The Superpower Paradox: Asymmetric Cheap WMD Strategic Strike and Destruction
- The KGB/Yakuza-Aum War Plan
- Why Western Science is Ignorant of KGB Energetics
- Transmutation of Radioactive Nuclei at a Distance
- TheYakuza
- Yugoslav Earthquake, Followed by Cold Explosion
  April 15, 1979

---

* Note that the Secretary did not speak the words in square blocks; these were added by the writers later,

probably to "soften the tone" of the Secretary's information release. So the Secretary confirmed that some nations of the world -- not just some ragged terrorists, as the writers tried to imply for spin control -- do possess novel electromagnetic weapons and are using them to induce earthquakes, engineer the weather and climate, and trigger volcanic eruptions.

THE COMING STRATEGIC ATTACK ON THE UNITED STATES

By an AUM/Yakuza/KGB/Communist Coalition Using Energetics SuperWeapons

T.E. Bearden, LTC
U.S. Army (Retired)
M.S. Nuclear Eng.
Fellow Emeritus, AIAS

With Technical Background and History of Energetics Weapons

Partial support by the Association of Distinguished American Scientists is gratefully acknowledged.d

© 1995, 1996, 1999 T.E. BEARDEN



Outline

- Background: Classical Electromagnetics (and Defects)
- Background: Energetics (Scalar Electromagnetics)
- Background: Soviet Energetics Weapon Development
- KGB/Communist Plans
- Countering of Soviet/KGB/Communist Plan in Mid-80s
- Soviet Economic Collapse and Adaptation of Plan
- Weapons Bleed-Out: KGB/Russian Mafia
- Yakuza: The Japanese Mafia
- Aum Shinri Kyo (Supreme Truth) Cult
- Coalition: Aum/Yakuza/KGB/Communists/Russian Mafia
- Operation Divine Wind II: Three Phases
  - Phase I: On-Site Training Phase (Completed)
  - Phase II: Escalation Phase (In Progress)
  - Phase III: 1997 Strategic Strike on the United States
  - Support Plan A: Feints, Deception, Sabotage & Terrorism
  - Support Plan B: Test Range
  - Support Plan C: Worldwide Weather Engineering
  - Support Plan D: Strategic and Combat Intelligence
- Special Information
- Recommended Actions

© 1996, 1996 T.E. BEARDEN

The Tom Bearden Website

Help support the research

Loss of two separate A-10 Warthogs in 1997

- A-10 Mysterious Flyaway and Crash - April 2, 1997
- Death of Second A-10 Pilot - May 27, 1997
- Captain Button's Mysterious Flyaway and Eventual Crash
- Death of Second A-10 Pilot - May 27, 1997

A-10 Mysterious Flyaway and Crash

April 2, 1997


UTAH
COLO.
1:40 p.m.
Vail
Area enlarged
Denver
70
1:22 p.m.
Aspden
1:05 p.m.
Telluride
Pueblo
12:53 p.m.
Cortez
ARIZONA
11:58 a.m. Breaks
Formation near
Goldwater Range
12:20 p.m.
Young
NEW MEX.
10
Phoenix
Lake Roosevelt
12:11 p.m.
Apache Junction
8
Barry M. Goldwater
Air Force Range
DEPARTS
10:30 a..m.
Tucson
Tombstone
0 100
Miles
N
Eagle
Edwards
70
70
Vlail
Glenwood
Springs
COLO.
Gilford
Hardscrabble
Range
82
New York
Mountain
Sawatch Range
24
Flight path
Aspden
0 5
Miles
N
Leadville

Armed with:

- Four 500-lb bombs
- 30 mm Gatling gun



Death of 2nd A-10 Pilot May 27, 1997

- Captain Amy Svobody
- Night training mission
- From Davis-Montham AFB
- From same wing as Captain Button, who flew his A-10 off course for over an hour and then crashed on April 2.
- Climbout from ordnance delivery on target
- Nosed down sharply and dived into ground

Companion A-10's

- Experienced night flyer & instructor
- Nosed sharply over and flew into ground
- Psychoenergetic kill

© T.E. BEARDEN 1999

Psychoenergetic weapon induced instant hypnogogic state and reversed Svoboda's sense of up and down.

A-10 Mysterious Flyaway and Crash

April 2, 1997

Armed with:

- Four 500-lb bombs
- 30 mm Gatling gun


UTAH
COLO.
Area enlarged
1:40 p.m.
Vail
1:22 p.m.
Aspden
1:05 p.m.
Telluride
12:53 p.m.
Cortez
ARIZONA
11:58 a.m.
Breaks Formation
near Goldwater Range
12:20 p.m.
Young
NEW MEX
12:11 p.m.
Apache Junction
Barry M. Goldwater
Air Force Range
DEPARTS
10:30 a.m..
Tucson
Tombstone
Eagle
Vail
Glenwood
Springs
COLO.
New York
Mountain
Hardscrabble
Range
Sawatch Range
Flight path
Aspden

Figure 14a. Captain Button's mysterious flyaway and eventual crash.



Death of 2nd A-10 Pilot May 27, 1997

- Purpose: Stimulate U.S. in same area again
- Determine if U.S. aware of psychoenergetics
- U.S. showed it is completely unaware

- Captain Amy Svoboda
- Night training mission
- From Davis-Montham AFB
- From same wing as Captain Button, who flew his A-10 off course for over an hour and then crashed on April 2.
- Almost certainly a second psychoenergetics strike

- Experienced night flyer & instructor
- Nosed over and flew into ground
- Probable kill using psychoenergetics

Psychoenergetic strike induced an instant hypnogogic state, shifted pilot's sense of up and down. Svoboda corrected and "climbed out" after target attack, and flew into ground, dream-perceiving down was up.

© T.E. BEARDEN 1997


Typical ABM Defenses
(WIDELY DEPLOYED BY MID-70's)
GLOBAL SHELL (MIDCOURSE ELECTRONICS DUDDING)
INTENSE ENERGY SHELLS (Destruction of vehicle) (Initiation of nuclear warheads)
© T.E. BEARDEN 1999
EM MISSILES
EARTH'S SURFACE
ENERGETICS HOWITZER
TRACK
LAUNCH PHASE DEFENSES
(NESTED) HEMISPHERICAL SHELL(S) (Dudding, initiation, destruction)
TERMINAL DEFENSES



LAUNCH PHASE ANTIMISSILE SYSTEM

IONOSPHERE
PHASE CONJUGATE REPLICA (MAY BE HIGHLY AMPLIFIED)
EARTH'S SURFACE
NORMAL RADAR RETURN
STRATEGIC BALLISTIC MISSILE AT IGNITION
GIANT ENERGETICS TRANSMITTER RECEIVER SYSTEM

SOME OPERATIONAL MODES:

- SIMPLE TRACKING
- PHASE CONJUGATE TRACKING
- ENGINE COMBUSTION COOLING
- EMP INSERTION
- ELECTROMAGNETIC MISSILE STRIKE
- ELECTRICAL INTERFERENCE
- METAL LATTICE SOFTENING
- ANTI-WARHEAD
- GLOBAL SHELL
- HEMISPHERICAL SHELL
- MULTIPLE SIMULTANEOUS TARGETS
- MULTIPLE SIMULTANEOUS MODES

© T.E. BEARDEN 1996



LAUNCH PHASE ANTI-BOMBER SYSTEM

IONOSPHERE
PHASE CONJUGATE REPLICA (MAY BE HIGHLY AMPLIFIED)
NORMAL RADAR RETURN
EARTH'S SURFACE
STRATEGIC BOMBER OR OTHER A/C TAXIING, OR TAKING OFF
GIANT ENERGETICS TRANSMITTER RECEIVER SYSTEM

SOME OPERATIONAL MODES:

- SIMPLE TRACKING
- PHASE CONJUGATE TRACKING
- ENGINE COMBUSTION COOLING
- EMP INSERTION
- ELECTROMAGNETIC MISSILE STRIKE
- ELECTRICAL INTERFERENCE
- METAL LATTICE SOFTENING
- ANTI-PERSONNEL
- ANTI-ORDNANCE
- GLOBAL SHELL
- HEMISPHERICAL SHELL
- MULTIPLE SIMULTANEOUS TARGETS
- MULTIPLE SIMULTANEOUS MODES

© T.E. BEARDEN 1996



HC-130's ENGINES QUIT, AIRCRAFT CRASHES

At 4 miles altitude,
all four engines quit,
one after the other

Routine night training mission
80 miles off Calif Coast
Crew of 10 and 1 passenger
1 survivor

Compare to China Airlines Flight 006, 19 Feb. 1985 off San Francisco, bound from Taipei to Los Angeles

Nov. 22, 1996

(c) T.E. BEARDEN 1997

PROBABLE ENDOTHERMIC SUPERPOTENTIAL INTERFEROMETRY
(Apparently all 4 engines have never before failed on an HC-130)



CTEC PROPRIETARY

1996 Actions by this analyst

- In July 1996, with the kill of TWA-800 it became apparent that the KGB/Communists were preparing a massive strategic energetics attack upon the U.S.

© T.E. BEARDEN 1997

- Began intensive, nearly round-the-clock effort to uncover what was happening, and what had occurred in KGB/Com weapons since 1991
- Began preparing full-up set of briefing slides simultaneously
  - In early 1996, had briefed J6 on scalar EM, per his request
  - Had strongly suggested a follow-on weapons brief
  - Adamant opposition by NRL, NOL, others
- Similar energetics attack scenario in 1986 was countered. Soviets at that time did not possess operational QP weapons, and so could not successfully overcome dead-man fuzing
  - Also could not dud nukes worldwide, because QP required.
  - First lab prototype QP test was in April 1986
- KGB had solved the dead-man fuzing problem by QP's. Deployed circa 1989-1990. Some earlier weapons then leased.



Additional Information Exists; Not Analyzed, Not Integrated in Briefing

- Yakuza arranged involvement of
  - Red Chinese
  - North Koreans
  - A Taiwanese element
- Aum Shinrikyo may have been used as "Red Herring" to deceive West
- Oriental faction plots to strike Russians after the successful first strike on West
- KGB/Russians aware, will counter
  - Plan pre-emptive strike against Oriental faction first
  - Have reserved most advanced, powerful energetics weapons for that purpose

© 1999 T.E. BEARDEN

The Tom Bearden Website

Help support the research

Kill of Arrow DC-8, Gander AFB, Dec. 12, 1985

- Slide 1
- Slide 2
- Slide 3
- Slide 4
- Slide 5
- Slide 6



KILL of ARROW DC-8

Gander AFB, Dec. 12, 1985

- Soviet EM missile weapon strike practice two weeks earlier at Cape Canaveral
  - Offset from night shuttle launch
  - EM missile photographed by Bob Gladwin
  - Associated marker beacon photographed
- Canadian Board split on findings
  - Half thought icing, half disagreed intensely
  - "Due to icing" approved with half absent
  - Separate dissenting finding issued
- U.S. officials hiding Iran/Contra affair
  - Feared terrorist bomb, MidEast sponsor
  - Pressured Board, Gen. Off. bulldozed site
- Lack of icing on aircraft later validated



KILL of ARROW DC-8
Gander AFB, Dec. 12, 1985

- Eyewitness observed beams form in the sky
- Saw streak-down and strike of EM missile
  - Struck right fuselage ahead of the engines
  - Hole was burned through fuselage there
  - Photo of hole published in AW&ST
  - No explosive residues on hole
- Consistent with ignition and outgassing of plastics in forward cabin
- Consistent with pre-crash HCN deaths



KILL of ARROW DC-8
Gander AFB, Dec. 12, 1985

- Combustion cooling reduced thrust during runup
- Emulated reducing specific thrust by icing
- Struck with EM missile, at liftoff
  - Hole in right fuselage, ahead of engines
  - Not normal explosion; no material ingested
  - EM missile explosively ignited plastics in forward cabin; outgassed poisonous HCN
  - ***Autopsies**: Half the passengers died from HCN inhalation before plane crashed*
  - Data recorders recorded vertical spike of hit
- Materials handlers later mysteriously sickened, with symptoms of longitudinal EM radation induced illness



KILL of ARROW DC-8
Gander AFB, Dec. 12, 1985

- Combustion cooling reduced thrust during runup
- Emulated reducing specific thrust by icing
- Struck with EM missile, at liftoff
  - Hole in right fuselage, ahead of engines
  - Not normal explosion; no material ingested
  - EM missile explosively ignited plastics in forward cabin; outgassed poisonous HCN
  - *Autopsies: Half the passengers died from HCN inhalation before plane crashed*
  - Data recorders recorded vertical spike of hit
- Materials handlers later mysteriously sickened, with symptoms of scalar-EM radiation induced illness
- *Eye witness observed formation and strike of the electromagnetic missile*



KILL of ARROW DC-8
Gander AFB, Dec. 12, 1985

- Soviet EM missile weapon strike practice two weeks earlier at Cape Canaveral
  - Offset from night shuttle launch
  - EM missile photographed by Bob Gladwin
  - Associated marker beacon photographed by George Suchary
- Canadian Board split on findings
  - Half thought icing, half disagreed intensely
  - "Due to icing" approved with half absent
  - Separate dissenting finding issued
- U.S. officials hiding Iran/Contra affair
  - Feared terrorist bomb, MidEast sponsor
  - Pressured Board, Gen. Off. had site bulldozed
- Lack of icing on aircraft later validated


Death of the Arrow DC-8
Dec. 12, 1985
Gander, Newfoundland
ENGINE THRUST IS REDUCING
AIRCRAFT GLOWING (THRUST REDUCED)
FUEL EXPLOSION
KINDLING (SELF-TARGETING)
EM MSL STRIKE (MULTIPLE INSTRUMENT SPIKES)
CYANIDE INHALATION
TAIL-DOWN CRASH
ELECTROSTATIC COOLING OF ENGINE COMBUSTION
EXPLOSIVE PLASTICS IGNITION, FIRE, OUTGASSING
ABOUT ONE-HALF THE OCCUPANTS DIE
GRAVITON RADIATION DECAY (EXPOSURE OF RECOVERY PERSONNEL TO LONGITUDINAL EM WAVE RADIATION
GRAVITON CHARGING OF ATOMIC NUCLEI
HIGHLY CHARGED PULSE INTO ATOMIC NUCLEI



Satellite Photos of Plumes in Soviet Arctic Since 1974*

- Two aircraft flew through for analysis
  - Solid material, mostly ice, a little clay
  - Much colder than surrounding air
  - *Signature of cold exhaust from exothermic scalar interferometry operations*
  - No volcanic material
  - No radioactive material
- May be 2 to 3 times as many incidents
  - Only examined satellite imagery in winter
  - Only periodic satellite coverage
  - Hypothesized methane venting, cloud seeding

© 1996 T.E. BEARDEN

*As of 1989, when this information was gathered

AUM SHINRIKYO

("SUPREME TRUTH" CULT)

Shoko Asahara, Leader

© 1995, 1998 T.E. BEARDEN



Ashkhabad Problem and Its Solution

- ***PROBLEM:***
  - Stress increasing in two-plate fault zone
  - 1,000 shocks yearly
  - Kara Kum canal
  - Hydraulic pressure
  - 1948: Ashkhabad 80% destroyed by quake
- ***SOLUTION:***
  - Stress-relieve plate stresses from fault
- ***IMPLEMENTATION:***
  - Induce nearby earthquake
  - Deceive by *predicting* a quake, setting off nuclear explosion

© 1996 T.E. BEARDEN



Strange Characteristics of Iran Quake, Sep. 1978

© 1996 T.E. BEARDEN

- Signatures
  - 7.4 on Richter scale
  - No aftershocks: 6.0 expected (normal)
  - Strange epicenter
  - Anomalous depth
- Deception
  - 10 MT Soviet nuclear explosion 36 hours before the quake
  - Prior disinformation regarding Soviet attempted development of focusing shock waves from underground nuclear explosions, to cause distant earthquakes



Iran Earthquake Sept. 1978

- Killed 25,000 Iranians
- Soviet city of Ashkhabad saved
- Soviets "predicted" quake in advance; then induced it
- Quake had serious anomalies (signatures)
- Deception measures were used by Soviets
  - Prediction in advance
  - "Theory" of quake-induction by nuclear explosions
  - Fired underground nuclear explosion as "Red Herring" candidate for cause

© 1996 T E BEARDEN



Situation Now (Assessment)

- In May 1997: second A-10 pilot (lady), in pullup from night ordnance delivery on target, was struck with psychoenergetic weapon takeover. Sense of vertical was reversed. She perceived herself diving, sharply corrected, and dove headlong into the ground.
- Additional aircraft kills uncovered, including one 4-engine aircraft whose engines all failed. This closely repeats the earlier 1985-1987 scenario.
- Korean Airlines Flight 801 crashed on Guam on anniversary of loading of the atomic bomb that was dropped on Hiroshima in WW II. The Enola Gay, which dropped the bomb, took off from Guam in wee morning hours of August 6, 1945. The local opns order on Guam was also issued on Aug. 5.
- *Presently the Coalition (KGB/Communists/Aum Shinrikyo/Yakuza) is waiting for proper time to launch the final strike. It is still on.*



Situation Now (Assessment 2)

- April 97: Mind control test against Captain Button:
  - Demonstrates ability to control crewman in complex operations for more than one hour.
  - KGB requires one hour total QP crew control on a site to have crew disable insane QP wpns.
- Once QP systems disabled, Mindsnapper attacks and instantly kills every living thing in QP site area. Contaminates area for months (emits longitudinal EM wave radiation, which disrupt any life forms attempting to enter struck area). Sites nullified.
- Mind control over one crewman requires one weapon system plus up to 20-30 operators for controlling thoughts, hearing, perceptions, etc.
- *In Apr. 97, KGB building and deploying weapons and training crews. Ready for new attack 1999-2000.*



Aspects of Strong Local Asymmetry

- If local asymmetry is strong, conservation laws may be appreciably violated
  - Energy
  - Charge
  - Spin
  - Momentum
  - Angular momentum
- Properties of an object may differ appreciably for
  - Different observers
  - Different detecting means
  - One time to another
  - One position to another

© T. E. Bearden 1995, 1996



Mass Casualty Problem: Aerial Anthrax Spray on Washington, D.C.

- One terrorist, one light aircraft with spray tank
- One kilogram of anthrax
- Flies over greater metropolitan Washington, D.C.
- Calm night
- *1-3 million casualties result**
- *Most of those stricken will die*
- Presently little can be done to save the stricken civilians
- *Attacks on several population centers might produce some 10 million or more casualties*

© [illegible] T.E. BEARDEN

*Per OTA Report to Congress, 1993



Present Status of the WMD Threat to the United States

- **Many foreign nations are hostile to the U.S. and sponsor terrorists**
- **Some 25 nations have WMD or are acquiring them**
  - **BW agents and weapons**
  - **Chemical agents and weapons**
  - **Nuclear materials and weapons**
- **Thousands of students and émigrés**
- **Infiltrated teams, BW, other WMD already**
- **Castro guerrillas infiltrated over the years**
- **Can do unacceptable damage to U.S. now**
- ***May reach first strike knockout capability***

© [illegible] T.E. BEARDEN

*Per OTA Report to Congress, 1993



Some Present Problems in the U.S. WMD Defense Capabilities

- *No shelters (require overpressure, BW filtering, masks, showers, supplies)*
- *No stockpiled vaccines, medical supplies, immunoglobulins, masks, suits, food, fuel, generators, heaters, water purification units*
- Totally insufficient medical facilities, personnel, and emergency response teams
- Triage, full martial law will be required
- *No answer to massive decontamination problem*
- State, county, city inadequately staffed and insufficiently trained for mass casualties
- Terrorist teams, BW agents, other WMD on site, waiting
- Water supplies, food, crops, farm animals also vulnerable
- Electric power grid, bridges, trains, railroads vulnerable
- *Present medical science cannot save very many of the casualties, now or in the foreseeable future*

© [illegible] T.E. BEARDEN



Internal Terrorist Threat with Weapons of Mass Destruction: Now & Future

TODAY:
- *Sabotage*
- *Chemicals*
- *Biological agents*
- *Nuclear materials*
- *Powerful explosives*
- *Assassination*
- *Kidnapping and hostages*
- *Contamination*
- *Shoulder-fired AD missiles*
- *Terrorism*

FUTURE ADDITIONS:
- *Orthodox EM weapons*
- *Energetics EM biological warfare*
- *Scalar EM (energetics) weapons*
- *Scalar EM disease induction*
- *Alteration of behavior and emotions*
- *Alteration of memory*
- *Direct control of thoughts, perception*
- *Quantum potential weapons*
- *Psychoenergetics weapons*
- *Action-at-a-distance effects*

© [illegible] T. E. BEARDEN



Attempt to Ban Energetics Weapons Worldwide

- On June 13, 1975, in a major speech Brezhnev urged the United States to agree on a ban of research and development of new kinds of weapons "more terrible than anything the world has known."
- On July 2, 1975 Brezhnev repeated his proposed ban on development of frightful new weapons, to a group of U.S. Senators.
- In August 1975, Ponomarev called for a ban on frightful new weapons of mass destruction.
- On Sept. 23, 1975 Gromyko presented a draft treaty agreement to the 30th Session of the UN General Assembly, for banning development of frightful new weapons.
- *No one had the foggiest notion what the Russians were talking about!*

© 1996 T.E. BEARDEN



Brezhnev's Schedule

"We are achieving with detente what our predecessors have been unable to achieve with the mailed fist..
...by 1985 our power will be so irresistible that we can do what we wish anywhere on the globe."

Leonid Brezhnev,
In a secret 1973 meeting in Prague
with European Communist leaders.

"By the early 1980's we and our allies will control the high seas, space, and most of the earth's land area."

Kosygin,
to Imelda Marcos,
July 1978

In 1985-87, the Soviets did attempt to move, still constrained by nuclear dead man fuzing. That attempt was blocked, primarily by scalar EM countering demonstrations and dead man fuzing.

In April 1986, the first Soviet lab prototype of a quantum potential weapon specifically designed toward 10-min neutralization of nukes worldwide was gingerly tested against our U.S. airstrike on Libya. It was weakly tested in the "induced EMI" mode, for deception.

By 1990 that weapon was deployed and a new attack preparation phase was entered, scheduled for 1997.

© 1996 T.E. BEARDEN





COLD EXPLOSION -- 9 April 1984 Near Kurils

And Formation and growth of spherical shell (globe)

not to scale
centerline
380 miles diameter
expansion
200 miles
© T.E. BEARDEN 1999

Sequence of Events

- Geyser of water rose rapidly from surface, mushroomed out
- Reached 60,000 feet altitude in two minutes
- Brilliantly glowing globe then appeared in top
- Globe increased greatly in size and altitude
- Reached diameter of 380 miles
- Center reached altitude of 200 miles
- Observed by multiple qualified pilots



COLD EXPLOSION -- 9 April 1984 Near Kurils

And Formation and growth of spherical shell (globe)

not to scale
centerline
380 miles diameter
200 miles
expansion
© T.E. BEARDEN 1999

What They Were

- Superpotential interferometry using LWs
- First, a cold explosion just above surface
- Then small intense shell of glowing EM energy for 1-on-1 targeting
- Larger globe for large area as for ICBM targets approaching in zone
- With ST engines, can dud incoming nukes and all electronics
- Use in or out of Earth's atmosphere



COLD EXPLOSION -- 9 April 1984 Near Kurils (Plus additional weapons effects)

Halo expanded to giant globe.
380 miles diameter, center over 200 miles high.

© T.E. BEARDEN 1996



Countering Insane Mad Systems: Find Loophole, Exploit It

- *If MADs not quantum potential systems, easily countered by instant QP strike which destroys targeted MAD weapons worldwide with certainty.*
- *Have to be certain of types of dead-man fuzing. All dead-man fuzing weapons must be included in the assured target list for the striking quantum potential weapon.*
- *Multiple targeted MADS require multiple vacuum engines in the striking quantum potentials.*
- *Uncertainty and risk introduced if not certain of all MAD systems and all dead-man fuzing systems.*
- *Newest generation psychoenergetic LW interferometry weapons can instantly take over minds of all personnel on targeted sites, with targeted crews quickly disarming their own MAD weapons' launch capability as well as the weapons themselves.*
- *Mindsnapper then kills all living things and contaminates sites.*
- *Next generation QP Psy-En weapons can disrupt and destroy minds of an entire targeted national population. The nature of warfare moves irrevocably to the human mind, where of course the fundamental problem arises anyhow.*

© 1995, 1996 T.E. BEARDEN



Next Generation Counter to Both Sane and Insane MAD Systems

- ***Localized quantum potential in an area, used in psychoenergetics mode***
  - **Gradually produces mild, continuous hypnotic state**
  - **Targeted population remains entirely conscious, functional**
  - **Internal "word thoughts" emerge directly in subconscious**
  - **Targeted persons all unaware of these "word thoughts"**
  - **Operates somewhat similar to "post hypnotic suggestion"**
  - **Gradually changes emotions, psychological outlook**
  - **Over a period of time, deviates and entrains entire target population's outlook, belief structure, temperament**
- ***Moves Psywar to inside the human component***
- ***Human minds are the only battleground***
- ***Can be accomplished without overt signature***
- ***Countered only by inserting same methodology into deeper mind level (collective unconscious)***



Simultaneous Dudding of Nuclear Weapons Worldwide

- Via quantum potential joining U235 and Plutonium in warheads
- Includes weapons airborne, underwater, in storage
- These are *transmutations of the nuclides themselves*
- *Part of the initial barrage launched by Aum/Yakuza/KGB*
- *Will occur in the first minutes of the strategic strike, following psychoenergetically crew-disabling QP weapons*

Note: Duds both overt and covert nuclear weapons and weapons-grade materials -- including "suitcase-delivered" covert weapons on site in Russia which otherwise provide dead man fuzing

© T.E. BEARDEN 1996



Simultaneous Dudding of Nuclear Weapons Worldwide

- Via quantum potential joining U235 and Plutonium warheads
- Includes weapons airborne, underwater, in storage
- These are not explosions, but are ***transmutations and increased fissioning rates***
- *Part of the initial barrage launched by Aum/Yakuza/KGB*
- *Will occur in the first minutes of the strategic strike*

© T.E. BEARDEN 1996

Note: Duds both overt and covert nuclear weapons and weapons-grade materials.

The Tom Bearden Website

Help support the research

Operation Divine Wind II

Slide 1

Slide 2

Slide 3

Slide 4



YAKUZA &
AUM SHINRIKYO

U.S.

DIVINE WIND II

- ★ **A secret coalition of Yakuza/Aum Shinrikyo and KGB/Communist forces plan to launch a massive, surprise energetics attack on the United States, given a low-risk opportunity.**
- ★ **Major weapons utilized will be the scalar EM (energetics) superweapons (including quantum potential weapons) that were developed, deployed, and operated by the KGB under the former Soviet Empire, and continuing after its dissolution.**
- ★ **Yakuza/Aum crews have extensively trained and test-fired, from on-site in Russia. They have *leased* operational control of the first three generation energetics superweapons (which work by superpotential interferometry).**
- ★ ***The Escalation Phase of interdicting and destroying actual U.S. targets (e.g., TWA-800, two A-10s) is already underway.***
- ★ ***The first blow in the Strike Phase will dud all nuclear weapons and weapons materials worldwide, in minutes; destroy special ship and energetics weapon sites instantly, disable 99% of the U.S. population instantly, and kill 80% of targeted populations in from 10 minutes to 3 days.***

KGB

MINDSNAPPER AND
PSYCHOENERGETICS

QUANTUM
POTENTIAL

© 1995, 1996 T.E. BEARDEN



YAKUZA &
AUM SHINRIKYO

U.S.

DIVINE WIND II

- ★ A secret coalition of Yakuza/Aum Shinrikyo and KGB/Communist forces plans to launch a massive, surprise energetics attack on the United States and its allies, given the first low-risk opportunity.

© 1995, 1996, 1999 T.E. BEARDEN

KGB

- ★ Attack was thwarted twice in 1997 by a small nation countering with QP weapons.
- ★ KGB psychoenergetics counter for the last QP weapon counter was tested in April 1997.
- ★ Ready time for a new scheduled attack is latter quarter 1999 through first half of 2000.


YAKUZA &
AUM SHINRIKYO
U.S.
KGB/COMMUNISTS
MINDSNAPPER
QUANTUM
POTENTIAL

DIVINE WIND II

© 1995, 1996 T.E. BEARDEN

★ **A secret coalition of Yakuza/Aum and KGB/Communist forces will launch a massive, surprise, strategic attack on the United States in 1997.**

★ Major weapons utilized will be the scalar EM (energetics) superweapons that were developed, deployed, and operated by the KGB under the former Soviet Empire, and continuing after its dissolution.

★ Yakuza/Aum crews have extensively trained and test-fired, from on-site in Russia. They have *leased* operational control of the energetics superweapons.

★ *Escalation Phase of interdicting and destroying actual U.S. targets (e.g., TWA-800) is already underway.*

★ *The first blow in the Strike Phase will dud all nuclear weapons and weapons materials worldwide, in minutes; destroy special ship and energetics weapon sites instantly, and kill 80% of targeted populations in 3 days.*



OPERATION DIVINE WIND II

Three Phases and Support

Operational Phases

- Phase I: On-Site Training Phase (Completed)
- Phase II: Escalation Phase (In Progress)
- Phase III. 1997 Strategic Strike on the U.S.
  - *First strike (QP) in Phase III duds all nuclear weapons and nuclear powerplants worldwide, in minutes*
  - *Psychoenergetic strike (QP) disables people instantly*
  - *Mindsnapper attack of special assets for 100% success*
  - *QP initiation of fast-acting, lethal diseases kills 80% of targeted populations in three days or less*

Support Plans

- Plan A: Feints, Deception, Sabotage, and Terrorism
- Plan B: Testing and Test Range
- Plan C: Worldwide Weather Engineering
- Plan D: Strategic and Combat Intelligence

© 1995, 1996 T.E. BEARDEN



Advanced EMBW Applications

- Covert EMBW: Examples
  - Activate materials and their potentials with ST disease engines. Potentials superpose and their infolded ST dynamics diffuse
  - Activate water's structuring (H-bonding) potential with disease engines
  - Bias electrical power grid ground fields by weak diseases
  - Employ disease-structured quantum potential in distant area
- Overt death ray (mind snapper)
  - Powerful scalar EM pulse in target area "jerks" rate of flow of time
  - The "time snap" sharply separates mind from body and each cell
- EMBW CM:
  - Irradiate bodies with longitudinal EM waves; self-converts to t-pumping and produces exact amplified ST antiengine
  - Antiengine arises out of local ST, affects all parts of all cells
  - Cells are t-charged with antiengine structure
  - Continuing action restores regenerative and immune systems and reverses cellular damage

© T.E. BEARDEN 1995, 1999



EM Biological Warfare (EMBW)

- KGB/Communists have developed highly effective
  - Electromagnetic biological warfare (EMBW)
  - Counters to orthodox biological warfare
  - Mass death ray weapons
    - Small version of "mindsnapper" tested in Afghanistan
    - Killed occupants in two villages, in separate strikes
    - Unusual aspects (so-called "smerch" gas)
- Russia/KGB is the only group with a complete counter to biological warfare, either covert or overt, and to EMBW
- EMBW (covert and overt) is a preferred option for KGB
  - MAD Doctrine is completely destabilized for a sufficiently covert Russian EMBW strike
  - Situation has existed for at least two decades
  - Can alter germs, bacteria, viruses of specific kind, in a specific target area, to produce antibiotic-resistant strains
  - Can induce any kind of cellular disease or damage at a distance
- U.S. national characteristic: no reaction to slowly increasing threat

© T.E. BEARDEN 1999



Microwave Radiation of U.S. Embassy in Moscow

Former U.S. Embassy in Moscow.

BACKGROUND

- Began in latter 1950s
- Discovered on VP Nixon's trip
- Initially thought to be *nuclear* radiation (Discovered w/Geiger counter?)
- High level target -- U.S. Ambassador
- Guarantees personal attention of:
  - U.S. Ambassador to USSR
  - U.S. President
  - NSA, CIA, DIA, NSC, etc.
  - Top consulting scientists
  - Leading U.S. scientific institutions
- Two U.S. Ambassadors died, another sickened
- Anomalous health changes in personnel, only in zero-field (zero pot'l gradient) areas!
- Four U.S. Presidents requested Soviets cease
  - Cut from 18 watts/sq cm to 2
  - Then again increased
- No one could understand what was going on
- Aluminum screens were placed over windows
- Moscow was declared a hazardous duty zone

© 1995, 1996 T.E. BEARDEN



Pentagon EMI Studies, 1989

Washington Post, 22 Jan. 1989, p. A4

- Analysts of severe EMI effects in strike on Libya, 1986
  - performed major 3-year, 66-man study
  - Blamed effects on U.S. forces' own signals
  - Did not know of any other "signals" present
  - Knew nothing of quantum potential weaponry, energetics weaponry
- 7-month preliminary study
  - Severe EMI Problem exists
  - EMI shielding often waived in our weapon systems
  - Thousands of conflicts possible
- Also studied UH60 Blackhawk helicopter problems (which *were* due to its lack of good EMI shielding, and not quantum potentials)
  - uncommanded turns
  - Five EMI crashes 1982-1989
  - $175 M program to shield it
- So found that U.S. transmission combinations can
  - Affect aircraft flight control
  - Turn off fuel supply
  - Cause uncommanded dive/turn
  - Bring down U.S. warplanes
- *Actually, Libyan EMI was induced by Soviet quantum potential tests which can do all those things and much more*

© 1996 T.E. BEARDEN

EM Missile Practice

- EM Missile Practice
  Latter Sept. - Early Nov. 1996
  Melbourne, Australia
- Deception: Using EM Missile to Reinforce Notion of SAM Attack
  Saturday evening, Nov. 16, 1996
- Intelligence Probe: Insuring U.S. Still Unaware of Energetics Weaponry
  Thursday, December 12th, 1996
- EM Missile Strike, Offset from Night Shuttle Launch, Cape Canaveral, Florida
  The Smoking Gun in November 1985
- Distant Operator Onsite in Russia Slew Away Registration Point
  Marker Beacon over Night Shuttle Launch, 26 November, 1985
- EM Missile Practice and Deception
  November 17, 1996



EM Missile Practice
Latter Sept.-Early Nov. 1996
(Multiple Nights, Multiple Streaks Each)

(Many Witnesses)

© 1996 T.E. BEARDEN

Melbourne, Australia
Australian Associated Press
Nov. 2, 1996



Deception: Using EM Missile to Reinforce Notion of SAM Attack

Saturday Evening
Nov. 16, 1996

Note: Meteor shower was forecast, which provided perfect decoy to FBI investigators, to steer them off the true scent.

Pakistan International Airlines Flight 712, just after takeoff from John F. Kennedy Airport, on path similar to that taken by TWA Flight 800, July 17, 1996

© T.E. BEARDEN 1996



Intelligence Probe: Insuring U.S. Still Unaware of Energetics Weaponry

Thursday
Dec. 12, 1996

Pilot sighted what he called
a "green flare".
No danger, no evasive action.

Saudi Arabian Airlines 747
en route from Riyadh, Saudi Arabia
to John F. Kennedy Airport.
At 12,000 ft., not far from where
TWA Flight 800 was killed on July 17, 1996

FBI: *"Probably a meteorite."*

© T.E. BEARDEN 1996



EM Missile Strike, Offset from Night Shuttle Launch

Cape Canaveral, Florida

EM MISSILE STRIKE
26 NOV 1985

(LIGHT DEVELOPMENT)
OFFSET FROM NIGHT SHUTTLE LAUNCH

PHOTO BY BOB GLADWIN

MARKER BEACON
Over Night Shuttle Launch
Cape Canaveral, Florida

26 Nov 1985
Photographed by George Suchary

© T.E. BEARDEN 1996, 1999,

EM MISSILE STRIKE
26 NOV 1985

(DARK DEVELOPMENT)

OFFSET FROM NIGHT SHUTTLE LAUNCH

The Smoking Gun in Nov. 1985



Distant Operator Onsite in Russia Slews Away Registration Point

© T.E. BEARDEN 1995, 1999.

MARKER BEACON
Over Night Shuttle Launch
Cape Canaveral, Florida

26 Nov 1985
Photographed by George Suchary

28 Nov 1985

Two weeks later, the same weapon killed the Arrow DC-8 at its takeoff from Gander, Newfoundland.



EM MISSILE PRACTICE AND DECEPTION

Nov. 17, 1996 at 2220 hrs.

Note: 4-month
anniversary
of kill of TWA-800.
"Inside gloating" by
Aum/Yakuza/KGB.

Vicinity of Long Island, New York
Not far from where TWA-800 was killed
Two aircraft sighted object

ⓒ 1996 T.E. BEARDEN



Subdivisions of Soviet Energetics

NONLIVING SYSTEMS

LIVING SYSTEMS

Energetics

- *Nonliving systems*
- *Scalar Interferometry*
- *Action-at-a-Distance*
- *Quantum Potential*
- *Vacuum Engines*
- *Spacetime Structuring*
- *Material, Field Effects*
- *Nuclei, Lattice Changes*
- *Hidden EM Variables*
- *SWZ Effects*

Bioenergetics

- *Living Systems (Bodies)*
- *Cells, cellular changes*
- *Master Cell Control (Popp)*
- *Spacetime Structuring*
- *Disease Induction, Remission*
- *Action-at-a-Distance*
- *Quantum Potentials*
- *Scalar Interferometry*
- *Hidden EM Variables*
- *SWZ Effects*

Psychoenergetics

- *Living Systems (Minds)*
- *Thoughts, Memories, Emotions*
- *Conscious/Unconscious Minds*
- *Spacetime Structuring*
- *Species, Biospheric Minds*
- *Action-at-a-Distance*
- *Quantum Potentials*
- *Scalar Interferometry*
- *Hidden EM Variables*
- *SWZ Effects*

© 1996 T.E. BEARDEN



Communism's Goal

- "War to the hilt between communism and capitalism is inevitable. Today, of course, we are not strong enough to attack... To win we shall need the element of surprise. The bourgeoisie will have to be put to sleep. So we shall begin by launching the most spectacular peace movements on record. There will be electrifying overtures and unheard-of concessions. The capitalist countries, stupid and decadent, will rejoice to cooperate in their own destruction. They will leap at another chance to be friends. As soon as their guard is down, we shall smash them with our clenched fist."

Dimitry Z. Manuilsky
Lenin School of Political Warfare, Moscow
(circa 1934)

© 1996 T.E. BEARDEN



Manuilsky's Goal vs. Status Today

Manuilsky, 1934	Situation, Dec. 1996
War is inevitable.	Has not changed.
Not strong enough to attack now.	Strong enough now; preparations completed. Need right opportunity.
Need surprise.	Have achieved total surprise.
Must put us to sleep.	We are sound asleep.
Need most spectacular peace movement on record.	Done. We think the Russian threat gone, cold war ended.
Electrifying overtures, unheard-of concessions.	Done, and still occurring every day. It has worked beautifully.
Capitalists will cooperate.	We are cooperating in spades!
They will leap to be friends.	We've leaped, and are leaping.
They will let down their guard.	No ABM, junked lots of nukes, shrunk our forces to the bone.
We'll strike them then.	They would have struck (twice) in 1997, but for deterence by another nation (not U.S.) having QP weapons *They are still looking for a risk-free opening to strike*

© 1996, 1997 T.E. BEARDEN



Professor Hellman, German Scientist Released from Work in Soviet Union

- Worked in Soviet Union after WWII
- Eventually escaped to Germany, then to Brazil (handsome offer)
- Took part in highly unusual Soviet energetics development and experiments
- Large areas of the sea could be and were *suddenly frozen*
- *No particular attention was paid to this information by highly qualified scientists*
- *In intelligence terms, this is A-1 information of the highest caliber*
- *Bohm also was invited to Brazil, which started an energetics weapon program. Brazil developed such weapons including weak quantum potential weapons (0.95 confidence)*

© 1996 T. E. BEARDEN

Hemispheres of Light

- March 20th, 1969
  Caribbean and Western North Atlantic
- Hemisphere and Globes, 1977
  24 March, 1977
- Virgin Islands Incident
  August 1969
- Typical Shield Test, Northern Route to Japan
  June, 1982



Expanding Hemisphere of Light

Mar. 20, 1969
Caribbean and Western
North Atlantic

- Semicircle
- Milky white light
- Small, intense at first
- Dimmed as enlarged
- Grew to enormous size
- Lasted 10 minutes, then faded

Marine Observer
40:17, 1970


Hemisphere and Globes 1977
0855 GMT, 24 Mar 1977
M.V. Kinpurnie Castle
23° 05' N; 17° 25' W
Disappeared after 10 minutes
2nd luminous patch
Moderately luminous hemisphere formed
Bright luminous patch (1° diameter)
Required 3 minutes to form
30°
For 10 sec, "searchlight" shined down
40°
© T.E. BEARDEN 1996
Marine Observer 48:21-22, 1978



1969 Virgin Islands Incident

8:15 P.M.
Thursday
Aug 1969
Seen by many residents

Faintly luminescent

Smooth, curved edge

NORTH DIRECTION

© T.E. BEARDEN 1996



Typical Shield Test, Northern Route to Japan

Asahi Evening News, Tokyo
June 22, 1982

Multiple tests seen per month, for years.
Pilots simply ceased reporting them.

© T.E. BEARDEN 1994, 1995



How Could Such Superweapons Ever Be Concealed?

- Arthur C. Clarke's law states:

  "Any sufficiently advanced technology is indistinguishable from magic."

- To U.S. scientists, "magic" means "impossible"
- Longitudinal EM waves and LW interferometers have been regarded as fantasy and impossible
- To deceive foe on rather open use of unknown technology without discovery:

  "Disguise its uses as understandable accidents, human error, acts of nature, other known technology, etc."

© T.E. BEARDEN [illegible]



Soviets Easily Concealed These Superweapons for Four Decades

- Intensive Soviet deception plan utilized
  - Embedded in other weapon system tests
  - Made to resemble natural acts, accidents, etc.
  - Open science releases coordinated to show Russian scientists worked on "normal" science
- West thought Russian scientists inferior
- U.S. scientific community was and is dogmatic, and fiercely suppresses real scientific innovation
- Terribly flawed electrodynamics not ruthlessly shaken and changed in West
- West had no basis for understanding energetics

© T.E. BEARDEN 1996, 1999


Precise spacetime curvature engine adds energy to 2He4 α-particles inside atomic nuclei, causing tunneling α-decay
POWER UNIT
POWER UNIT
MAIN POWER UNIT
BEAM UNIT
BEAM UNIT
BEAM TRANSMITTER
REFLECTED BEAM RECEIVER
BEAM TRANSMITTER
REFLECTED BEAM RECEIVER
PHOTO UNIT
CONTROLLER-SWITCHER UNIT
SCANNING ANTENNA HORNS
MAIN DISPLAY UNIT (MOVABLE)
OPERATOR STATION
Interference zone with spacetime curvature engines to add energy to α-particles, causing α-emission and decay
Plan View
Elevation View

Figure 26. Microscope-type, laser-like interferometer for inducing quick α-decay in samples of otherwise longer-lived isotopes.

© T.E. BEARDEN 1996



Longitudinal EM Wave Interferometry: Endothermic

Meeting of timed pulses causes explosive cooling

COOLING IN INTERFERENCE ZONE

Ambient vacuum potential in distant interference zone

Φ_a

subspace

Bias

Heat extracted

XMTR/RCVR

XMTR/RCVR

subspace

Φ_T

Electrical ground potential of transmitter

© T.E. BEARDEN 1996

Heat emerges at transmitter/receiver

Heat emerges at transmitter/receiver



Longitudinal EM Wave Interferometry: Exothermic

Energy input to transmitter/receiver
Energy input to transmitter/receiver
XMTR/RCVR
Φ_T
Electrical ground potential of transmitter
XMTR/RCVR
subspace
subspace
Bias
Heating in interference zone
Φ_a
Ambient vacuum potential in distant interference zone

Meeting of timed pulses causes explosive heating

ⓒ T.E. BEARDEN 1999

U.S. Air Attack on Libya

April 1986

- Slide 1
- Slide 2
- "Washington Post" Article
  January 22, 1989



U.S. Airstrike on Libya April 1986*

- 33 U.S. AIRCRAFT IN STRIKE
- MANY HIGH-POWERED TRANSMITTERS
  - *COMMUNICATIONS*
  - *JAMMERS*
  - *RADARS*
- SEVERE, UNEXPECTED "EMI" ENCOUNTERED
  - *ONE F-111 DOWNED*
  - *NUMEROUS WEAPONS WENT ASTRAY*
  - *THREE FOREIGN EMBASSIES DAMAGED*
  - *SEVEN AIRCRAFT FORCED TO ABORT*
- COMMANDERS: *"US OR THEM?"*

Mild quantum potential weapon tested against electronics in U.S. aircraft and missiles

EM energy arises from every point in spacetime inside the electronics

*Washington Post, 22 Jan. 1989, p. A4



U.S. Air Attack on Libya in April 1986

- Established QP with the electronics in our aircraft and missile
- Subtly jammedthem with spurious EMI noise and signals

Longitudinal wave interferometry into distant mirror
Longitudinal wave interferometry into distant mirror
Distant Scalar Potential Interferometer
1
© T.E. BEARDEN 1997



Lightning Wall

- Aircraft on course of 270 degrees
- Approached "solid wall of lightning" in an otherwise cloudless sky
  - From very high altitude to near the water
  - Extended north-south as far as one could see
- Radar scope clear
- *Rigged aircraft for heavy weather*
- *Plunged directly through wall*
- *Wall was very thin*

circa 1959-1960
Interview with Patrol plane commander
U.S. Navy P5 aircraft
Over Atlantic, 200 miles east of Norfolk

© T.E. BEARDEN 1996



Lisitsyn's Report: Brain Code Broken

- THEORY DEVELOPED AND FITTED
- HYSTERESIS MEMORY LOOP
- CONTROLLED EM INDUCTION
  - IMAGES
  - SENSATIONS
  - PREDETERMINED EMERGENCE
- 23 EEG BANDS
  - UP TO 8.1×10^{20} HZ
  - 11 INDEPENDENT CHANNELS

S.K. Lisitsyn, "New Approach to the Analysis of Electroencephalograms," DDC Report AD73005, p. 16-25.

JCS-34

© 1978, 1985, 1991 T.E. BEARDEN



Large Longitudinal EM Wave Interferometer (LWI) Accident

- 1958 nuclear explosion near Urals
  - Contaminated 1200 square kilometers
  - Signature of large LWI accident
  - Buried atomic wastes suddenly exploded
  - Region contaminated to this day
- Soviets were well along with advanced LWI prototypes and testing
  - In Jan. 1960 Khrushchev announced these forthcoming "fantastic" weapons
  - 1958 difficulties would have been resolved by 1960

© T.E. BEARDEN 1996, 1999



Large Longitudinal EM Wave Interferometer (LWI) Accident

- Expected cause of 1958 accident
  - Huge LW energy beams built up
  - Catastrophic short-out in transmitter
  - LW energy flashed over into earth and spread
  - Struck and fissioned stored nuclear wastes
- Developed new safety circuits
  - For transmitter short-out, instantly activates to hold LW beam energy and prevent flash-over
  - Similar accident happened in 1986 at Chernobyl, except private U.S. group blew that transmitter to prevent catastrophic quake in California

© T.E. BEARDEN 1998, 1999

(Use of Hidden Information Content of the Field)
(Can Provide Action-at-a-Distance)


ϕ_1
ϕ_2
Note:
Whittaker's 1904 paper initiated the entire field of superpotential theory.
Interference Zone (Potential gradients)
Normal EM Energy: May be positive, or negative, or fixed
Hidden Bidirectional EM energy flow
Hidden Bidirectional EM energy flow
Scalar Potential Beams
XMTR
XMTR
Whittaker/Ziolkowski Transmitter Arrays
(8 to 20 harmonic wavepairs each)

© T. E. Bearden 1994, 1999

Figure 5. Scalar potential interferometry (between the two sets of bidirectional longitudinal EM wavepair functions) produces all EM force fields and waves.



Two Types of Mutual Assured Destruction (MAD) Systems

- **Sane system:**
  - Turned off or on standby
  - Wait until attacked or attack is imminent
  - Humans consider situation, make strike decision
  - Command order issued to weapons officers
  - Human finger initiates launch sequence
  - Usually requires code entry, etc. for assured launch control
- **Insane system:**
  - Computer periodically (e.g., every 2 hours) initiates launch
  - During sequence, there is a period (say, 2 min.) where operators can enter stop order (usually coded)
  - If correct stop not entered, weapons automatically launch
  - If correct stop entered, computer resets, and after another 2 hrs, automatically reinitiates the launch sequence

© 1996, 1997 T.E. BEARDEN



Psychoenergetics Weapons Teams Mentally Disable All Personnel

(COUNTERS ALL SANE MAD SYSTEMS)
(NULLIFIES HUMAN COMPONENT OF ALL WEAPON SYSTEMS)

ELECTRICAL THOUGHT-WORDS ARISE DIRECTLY IN BRAIN, HENCE IN MIND, BYPASSING SENSOR INPUTS

INSTANT HYPNOGOGIC STATE, WITH INSERTED THOUGHT-WORDS

Effects arise in local spacetime, simultaneously in all minds in the targeted area

INSTANT HYPNOGOGIC STATE: WITH WAKING DREAM

PERCEIVED REALITY NOW CONTROLLED

TARGETED POPULACE

- Site personnel instantly hypnogogic and mentally controlled.
- Distant weapon controller teams coord crew actions
- Standdown insane weapons to maintenance standby.
- Mindsnapper then strikes, kills all personnel, and nullifies site for months.

Indicators: Two A-10 incidents 1997, LIDA device since 1950s.

© 1996 T.E. BEARDEN



Strikes Against Special Ship and Energetics Weapon Sites

- Via powerful scalar EM pulses in each targeted area, so sharp time-jerks occur
  - Mind and its operations exist in time but not in 3-space
  - Coupling interaction of mind operations to body occurs through flow of time
  - Flow or change of flow of time must be smooth, for coupling of mind to body
- *Sharp jerk in time flow snaps mind's coupling to body, instantly separates mind*
- *Instant death for every virus, bacterium, cell, insect, mammal, living creature*
- *Contaminates struck sites for months, perhaps a year*

Note: In other words, this is the part of the "preparation barrage" that attacks the enemy's response capability (i.e., his "artillery" and his "airpower") and suppresses it. The use of the "mindsnapper" weapons provides 100% assurance of success.

© T.E. BEARDEN 1996

"MINDSNAPPER" ATTACK ON SPECIAL SHIPS & ENERGETICS WEAPONS SITES

"We have a new, fantastic weapon ... so powerful that, if unrestrainedly used, it could wipe out all life on earth."

Khrushchev,
speaking to Presidium,
Jan. 1960


XMTR
XMTR
© 1996 T.E. BEARDEN
POWERFUL SCALAR EM BURSTS
POWERFUL SCALAR EM BURSTS
POWERFUL SCALAR EM BURSTS
TARGETED AREAS


SHARP TIME JERKS PRODUCE MINDSNAPS

- Minds snapped loose from bodies (every living thing)
- Struck areas completely sterilized of all life
- LWs emitted; slow decay of time-charge makes contamination persistent
- Tested twice in Afghanistan

The Tom Bearden Website

Help support the research

How Much Off Guard Are We?

- Slide 1
- Slide 2
- Slide 3
- Slide 4
- Slide 5
- Slide 6
- Slide 7



How Much Off Guard Are We?

- *Legitimate U.S. forces have no energetics weapons or defenses against them*
- *No DoD general, military officer, or enlisted person reporting to the government of the United States has any:*
  - Training in energetics or energetics weapons
  - Experience in energetics or energetics weapons development and usage
  - Training in strategy, tactics, deployment, and employment of energetics weapons
  - Knowledge of energetics weapons effects and capabilities
  - Knowledge of the energetics weapons, tactics, deployment, and employment by the KGB/Russians
- *Civilian and military, scientific and intelligence, and news media personnel do not recognize energetics weapons effects happening right over their own heads*

© 1999 T.E. BEARDEN



How Much Off Guard Are We?

- Kill of U.S.S. Thresher in 1963 not recognized. Left signatures.
- 23 years of KGB weather engineering, particularly over U.S. and North America, ignored and not recognized.
- Decades of irradiation of U.S. Embassy, fatally injuring three U.S. Ambassadors, health changes in personnel shrugged off ineptly.
- Massive building of underground sites, all through former Soviet Union, lamely speculated as perhaps "ABM" system or?.
- 1985, 1986 Soviet kills of U.S. aircraft, spacecraft, personnel ignored as "accidents" by legitimate U.S. communities.
- Quantum potential strike on soldiers in Gulf war ignored.
- Quantum potential deterioration of U.S. populace's immune systems ignored.
- Exchange of earthquakes and massive retaliatory destruction of Soviet missile ammunition storage sites, 1986-1989, ignored.
- U.S. scientific and military communities adamantly refuse to rework electromagnetics, though known to be seriously flawed.
- Refuse to apply Stoney/Whittaker work to engineer hidden variables, even though present quantum mechanics also known to be wrong because it does not contain such "hidden order."

© 1996, 1999 T.E. BEARDEN

- Refuse to develop, structure, and apply Bohm's quantum potential, for instantaneous action at a distance. Russians developed it.



How Much Off Guard Are We?

- **Kill of U.S.S. Thresher in 1963**
  - Not recognized.
  - Left signatures.
- **23 years of KGB weather engineering**
  - Particularly over U.S. and North America
  - ignored and not recognized.
- **Decades of microwave irradiation of U.S. Embassy**
  - Fatally injured three U.S. Ambassadors
  - Induced health changes in personnel
  - Shrugged off ineptly.
- **Massive building of underground sites**
  - All through former Soviet Union
  - Lamely speculated as perhaps "ABM" system or?.



How Much Off Guard Are We?

- 1985, 1986 Soviet kills of U.S. aircraft, spacecraft, personnel ignored as "accidents" by legitimate U.S. communities.
- Quantum potential strike on soldiers in Gulf war not recognized, ignored.
- Quantum potential deterioration of U.S. populace's immune systems ignored.
- Exchange of earthquakes and massive retaliatory destruction of Soviet missile ammunition storage sites, 1986-1989, ignored.



How Much Off Guard Are We?

- U.S. scientific and military communities adamantly refuse to rework electromagnetics, though known to be seriously flawed.
- Refuse to apply Stoney/Whittaker work to engineer hidden variables, even though present quantum mechanics also known to be wrong because it does not contain such "hidden order."
- Refuse to develop, internally structure, and apply Bohm's quantum potential, which gives instantaneous action at a distance and great energy amplification.
- Russians developed quantum potential weapons, which obsolete all other weapons.

© 1996 T.E. BEARDEN



JUST HOW MUCH OFF GUARD ARE WE?

Kill of TWA-800 1996

Kill of USS Thresher 1963

Cold Explosion Off Japan Apr 1984

Kill of Space Shuttle Challenger 1986

President's party airplane crash 1996

3 Dead U.S. Ambassadors from Moscow Embassy Radiation

Kill of Arrow DC-8 Gander AFB Dec 1985

From The Huntsville (AL) Times 18 Sep 96:

"Retired Gen. Wayne Downing concluded that U.S. forces are so far superior to potential foes that opponents have turned to terrorism as the only way of challenging them."

The Times also provided the information that Defense Secretary William Perry agreed with Gen. Downing's conclusion.

- QP Gulf War Syndrome: 16,000 persons disabled
- QP jamming, U.S. air attack on Libya, 1996

© 1996 T.E. BEARDEN



JUST HOW MUCH OFF GUARD ARE WE?`

3 Dead U.S Ambassadors, U.S. Weather Engineered 20 years

Kill of USS Thresher Nuclear Submarine Apr 1963

QP Test on U.S. Troops in Persian Gulf, 1991 (Gulf War Syndrome)

TWA-800 1996; President's C-130 crash 1996

Arrow DC-8 Gander AFB Dec 1985

Challenger 1986

Quantum Potential Jamming of Air Attack on Libya Apr 1986

Blind Euphoria to Even the Ballistic Missile Threat

- U.S. National Intelligence Estimate (NIE) released in Nov. 1996 states there is no foreseeable threat to the U.S. from "indigenous missiles" for at least 15 years.
- Clinton has claimed a program for ABM defense is too expensive, would violate ABM Treaty with former USSR.
- Soviets developed an ABM system in violation of the treaty.
- In June 96 Russia test-launched an SS-19, their 26th ICBM test in 5 years.
- *"Russia still retains and is modernizing a vast nuclear arsenal... still the only nation of earth that could destroy America in a matter of minutes. Indeed, given the weakness of the Russian Army, Russia's superpower ambitions rest more than ever on its nuclear capabilities."* *
- "For the first time since the dawn of the nuclear age, there is not a single Russian missile pointed at America's children." **

Comment: *Punch a computer button and the missiles are pointed! The armed missiles are still there, ready and waiting.*

Bulleted info courtesy Washington Inquirer, June 24, 1996.

* House Nat'l Security Chmn, Floyd Spence.
** Bill Clinton, State of the Union Message.

© 1996 T.E. BEARDEN


Possible Targets: 1995-9
Escalation Phase
(Based on 1985-87 test program)
Earthquakes
Missiles
Power Grids &
Distribution Systems
Satellites
Ships
Shuttle
Launches
& Flights
JETLINERS
Radio/TV
Subs
Microwave Nets
Radars &
Nets
Communications
and Computer Nets



Propagation of Weapon Effects

- All conventional weapons use propagation through 3-space of matter or energy or both
  - Matter (bombs, missiles, projectiles, etc.)
  - Energy (EM force fields, sonic force fields, etc.)
  - Basically one-to-one, or one "bus" to many-on-many
  - Finite propagation velocity v: where $0 < v \leq c$
  - Time delay: Shielding and pre-strike retaliation possible
- Structured quantum potential propagates vacuum ordering (vacuum engines), instantly
  - Zero time delay (through multiply-connected spacetime)
  - No propagation "through space", no "velocity" as such
  - Easily one-to-many, without limit
  - Dramatic energy amplifier (gates, amplifies flux ordering)
  - Effects arise in local spacetime; no shielding possible
  - No range limit, since striking distance always zero
- QP weapons obsolete all other weapons

© 1989, 1995, 1998 T. E. BEARDEN



Yugoslav Earthquake, Followed by Cold Explosion

Apr. 15
1979

- Magnitude 7.2 on Richter scale
- Epicenter 33 km. deep
- More than 100 aftershocks
- At Kamenari:
  - Adriatic sea mushroomed up
  - Like atomic bomb explosion
  - Signature of a cold explosion
  - Similar to Apr. 1984 test off coast of Japan, near Kurils (see inset graphics)
- Note that April is a significant test month for the Communists (preparing official reports for May Day?)

OFF JAPAN, NEAR KURILS

1984 COLD EXPLOSION
SIMILAR TO THIS ONE

© T.E. BEARDEN 1994, 1996



COUNTERING AN INSANE QP WEAPON:

Quantum Potential Psychoenergetics Strike Mentally Controls All Personnel

CONTROLLED PERSONNEL DISABLE INSANE QP SYSTEM (FOLLOWED BY PERSONNEL KILL OF ENTIRE CADRE BY MINDSNAPPER)

ELECTRICAL DREAMTHINKING ARISES DIRECTLY IN BRAIN, HENCE IN MIND, BYPASSING SENSOR INPUTS

Effects arise in local spacetime, simultaneously in all minds in the targeted area

INSTANT HYPNOGOGIC STATE, WITH INSERTED DREAM THINKING
INSTANT HYPNOGOGIC STATE: WITH WAKING DREAM
PERCEIVED REALITY NOW CONTROLLED
TARGETED CADRES

© 1998 T.E. BEARDEN

MINDS ARE INSTANTLY PLACED INTO WAKING-- BUT DEEP -- HYPNOGOGIC TRANCE STATE. INSERTED THOUGHTS ANALOGOUS TO HYPNOTIST. PERSONNEL FUNCTION IN AN ALTERED, COMPLETELY CONTROLLED PERCEIVED REALITY.

Indicators: Captain Button's lengthy A-10 incident in 1997, LIDA device since 1950s.



Gulf War Disease: KGB QP Weapon Induced ST Curvature Engines for a Cocktail of Diseases

LEBANON
ISRAEL
SYRIA
JORDAN
IRAQ
IRAN
KUWAIT
QATAR
LIBYA
EGYPT
SAUDIA ARABIA
OMAN
CHAD
SUDAN

© 1999 T. E. BEARDEN

Distant Scalar Potential Interferometer with iterative self-targeting



Self-Targeting in Inner EM Channel Can Produce a Quantum Potential

Once QP is established, energy transmission is direct and instantaneous. Energy input to one single participant will simultaneously appear in all other participants, the amount depending on their fractions of participation with the input station.

NARROWING OF INTERACTING POTENTIALS INTO LASER-LIKE BEAMS, BETWEEN TWO PUMPED SOURCES. NOW ONLY LONGITUDINAL WAVES CONNECT THE LINKED OBJECTS.

SELF-TARGETING EFFECT AMONG ALL PAIRS OF INTERACTING PUMPED SOURCES

© 1989, 1995, 1996 T.E. BEARDEN



a. Iterative retroreflection between any pair of nodes narrows the interconnecting potentials to a laser-like, bidirectional beam. Iterative phase conjugate reflection provides self-targeting.

b. The quantum potential exists as narrow, laser-like beams between participating nodes, even when the nodes are widely separated. The beam space is multiply-connected; transmission is instantaneous.

© 1989, 1995 T.E. BEARDEN

Consider the hidden Stoney/Whittaker bidirectional EM waves that comprise the potential from each source node. If these nodes have sufficient intersymmetry of dynamic material form, then self-targeting occurs between the two nodes of any nodal pair. By iterative phase conjugate reflection, the scattering is narrowed into interconnecting wavepairs, in laser-like beams, between each two nodes. Thus the interconnecting potentials narrow into laser-like, bidirectional beams. The Coulomb gauge may apply, and a quantum potential may be formed.

Figure 30. Mechanism for generating a quantum potential, by iterative self-targeting induced into a system of multiple scattering nodes. Once a QP is established, spatial separation has little or no effect.



Major Principles for Use of Quantum Potential Weapons

- Must disable dead-man fuzing prior to massive use of scalar interferometry weapons.
- Must assure immediate, complete nullification of unique enemy assets (quantum potential assets, special ships, and energetics weapons).
- Personnel can be destroyed instantly with mindsnapping; area is sterilized of life, and effect persists, gradually dying away.
- Personnel can be disabled instantly with various psychoenergetic weapons; area not sterilized.
- Personnel can be destroyed in short order by using EM BW weapons; area not sterilized.
- If foe has energetics weapons, then it is a quick-draw "gunslinger" contest unless insane MAD systems deployed.
- Complete surprise is of decisive importance.
- Tailor effect used to specific target, objective.
- *Note: Must use "insane" MAD systems to deter.*

© 1996 T.E. BEARDEN



Quantum Potential Weapons: Major Principles (Continued)

© 1996 T.E. BEARDEN

- Three major classes of use exist:
  - Use of bulk energy only (as in bulk heating or cooling) without substructuring
  - Use of internal structuring of the bulk energy, so that *vacuum engines* appear in target
  - Use of more deeply nested engines allows direct intervention in mind, long term memory, perception, thoughts, emotions, personality
- Use of vacuum engines allows engineering at a distance of:
  - *Atomic nuclei* including structures, reactions, and transmutations
  - *Bulk matter* including translations, lattice bonding, chemistry, chemical interactions, electromagnetic interactions
  - *Deep biological control systems* such as
    - Becker's cellular control (recovery) system
    - Popp's cellular control system
  - *Cells* including:
    - Structuring, differentiation and dedifferentiation
    - Genetic changes, chemical changes
    - Induction of disease states without normal disease vectors
  - *Mind/matter interface*, including long-term memory, perception, emotion, thought, mental state



Instantaneous Communication by a Quantum Potential

Note: The term "quantum potential" is used in an extended sense.

© 1989, 1995 T.E. BEARDEN

Selected clipart © by Lotus SmartPics™



Participants in a quantum potential share a common multiply-connected spacetime (MCST)

- Separated points are superposed in MCST
- Connection is instant and bidirectional
- Propagation through ST does not apply
- Energy or vacuum engine input to one station instantly appears at each and every other station, undiminished in magnitude

- Any station may insert energy and engines
- Phase conjugation insertion negates

© T.E. BEARDEN 1998



Quake in Tangshan, China

28 July, 1976

- 7.8 on Richter scale
- Hundreds of thousands killed
- Accompanied by extensive light, electrical effects
  - Starting 3 to 5 days before
  - Communications interference within 250 km
  - Sky lighting observed
- [Personal comments]

© T. E. BEARDEN 1999



Counting Rifles: Put up or shut up!

(Exchanging Earthquakes)

Opening bet	
- Quebec	25 Nov 88
- Pasadena	3 Dec 88
Raise you	
- Armenia	7 Dec 88
Call - what do you have?	
- Malibu	18 Jan 89
Four aces	
- Soviet Central Asia	23 Jan 89
Clear table (stress relief)	
- Bakersfield et al	various

© T.E. BEARDEN 1990



Instant Communication by a Quantum Potential

The space is multiply connected; i.e., a power change of 1 watt on any single node has a fraction of that power also appear simultaneously at each other node. Once the QP is established, spatial separation has no effect.

N's are nodes participating in the QP

N$_1$
N$_2$
N$_3$
N$_4$
N$_5$
RCVR
XMTR
MASTER
RCVR
XMTR
SATELLITE
RCVR
XMTR
SATELLITE
RCVR
XMTR
SATELLITE
RCVR
XMTR
SATELLITE

© 1989, 1995 T.E BEARDEN



Westerners Do Not React to Slow Threats

BOA CONSTRICTOR
LIGHTNING STRIKE

Westerners tend not to react to slowly increasing things, but react to rapidly increasing things.

©1995 T.E. BEARDEN



CHARACTERIZING A GIVEN RISK OR RISK FACTOR

TECHNICAL RISK MANAGEMENT

SUPPORT RESEARCH IS TECHNICAL RISK REDUCTION AND MANDATORY FOR ANY EMERGING TECHNOLOGY





Aum Shinrikyo's Sarin Facility

The interior of Satian No. 7, a suspected sarin production plant

Chemical plant (the first four stages for production)

SOLVENT RECOVERY
STEPS 2 & 3
STEP 1
emergency stairs
emergency stairs
compressor room
shower room
a room for taking a nap
machine operating room
electrolysis room
stairs
prefabricated chemical laboratory
office
a room with liquid injectors
elevator
STEPS 4 & 5
chemical tanks (the 5th-stage production)
storage room
shutter
door
STORAGE

NOTE: Group was preparing to produce 70 tons of sarin in a 30 day period.

Reference: Senate Subcommittee Hearings



In Scalar Beam Interference Zone

- De-phasing of wave/antiwave pairs occurs
- Zero-summation destroyed
- Ordinary EM reappears [Whittaker 1904]
- Ordinary energy appears or disappears (i.e., may produce heating or cooling)
- Energy bottle effect
- Can add or extract EM energy
- Can produce specific ST curvature engines

© T. E. BEARDEN 1999



Physicist Schappeller Auralaz Munster, Austria:

- British Intelligence interview, about 1948
  - Used Kaluza-Klein theory
  - Worked with Russians
- Schappeller claimed he could:
  - Cause "implosions" rather than explosions
  - Use gravitational and electromagnetic energy
  - Cause large areas of the ocean to freeze
  - Tap earth-ionospheric field
  - Produce enormous energy
- *This is precisely what Hellman worked on in the USSR, after WW II!*

© 1996 T E BEARDEN



Initial Soviet Plan for Cold War, After WW II

- Develop and deploy SAM bomber defense
- Catch up in atomic weapons
- Master and apply rocketry
- Wed atomic warheads to rockets
- Initiate "Cold" War
  - Bleed the dragon
  - Guerrilla wars
  - Terrorism
  - Insurgencies
- *Find, develop, and weaponize next great technical breakthrough area as highest national priority*

© 1996 T.E. BEARDEN



Josef Stalin: Absolute Dictator

- Secret police and spies everywhere
- Purged his own officer corps
- Always deeply suspicious
- Regularly purged his enemies or those perceived to be shaky or untrustworthy
- Absolute power, justice had nothing to do with it
- Opponents often just disappeared in the night, never to be seen again
- Secret police often tortured, killed them
- Others sent to slave labor camps to die by severe work, starvation, and beatings or downright massacre
- Had experienced unusual abilities of Wolf Messing, so knew that some persons could do unusual things
- Forced Soviet weapon physics into this psychoenergetics realm also

One of the greatest mass murderers in history.

© T.E. BEARDEN 1997



Exploding any Resistance by Operational Scientists

© T.E. BEARDEN 1997

The Communists slaughtered 20 million Russian Kulaks to collectivize Soviet farming

"The destiny of communism has been frustrated by the U.S. development of the atomic bomb. That is not the last great technical breakthrough. The next one WILL be Soviet! You will provide me with that great new technical breakthrough at all speed, or I will have your heads. Do I make myself clear, comrades?"



Significant Soviet Statements

- "In the final revolution, it does not matter if three-quarters of the earth is destroyed, so long as the other quarter emerges communist." *[Lenin]*
- "If a means of total neutralization of foreign missiles is to be found, it can only come from a group of new principles in physics, called energetics." *[Nobelian Petr Kapitsa, to Nikita Khrushchev, in answer to Khrushchev's demand for a 100% method of defense against long range missile attack.]*
- "We will bury you." *[Khrushchev, to Nixon, Kitchen Debate*]
- "We have a new weapon, just within the portfolio of our scientists, so to speak, which is so powerful that, if unrestrainedly used, it could wipe out all life on earth. It is a *fantastic* weapon." *[Khrushchev, speaking to the Presidium, Jan. 1960]*

© 1996 T.E. BEARDEN



CAPTAIN SVOBODA DIVES HEADLONG TO HER DEATH

COMPANION A-10s

© T.E. BEARDEN 1999

CAPTAIN AMY SVOBODA

- Night training mission May 27, 1997
- From same wing as Captain Button
- This was a second psychoenergetics strike



T-Polarized Beam Projector

For Intercepting and Changing Distant Masses at Various Angles and Distances

A beam projector interferometer may be swept in azimuth and elevation, under computer control. The interference zone can be quickly swept through the surrounding volume of space.

Spacetime curvature engines act within any intercepted mass
Time-Density waveset generator 1
Time-Density waveset generator 2
Small Delay generator
Pulse 1
Pulse 2
Pulse 1
Pulse 2
Pulse 1
Pulse 2
Interference zone for time-density waves
© T.E. BEARDEN 1996



Possible Tests (1)

- 1958 nuclear accident in Urals
- Disease induction in U.S. Embassy personnel in Moscow
- Siberian disease/death transmission experiments
- Destruction of USS Thresher nuclear submarine, Apr. 10, 1963
- Nuclear explosion transmitted into ocean underwater, 100 miles north of Puerto Rico, Apr. 11, 1963

© 1996 T. E. BEARDEN



Possible Tests (2)

- Eight F-111's downed in Vietnam immediately after deployment
- Several large earthquakes
- Mysterious aircraft losses in groupings
- Numerous underground "nuclear" tests
- Nuclear tests at Semipalatinsk without associated seismic activity
- High altitude rumbles, snaps, booms
  - *Off English coast*
  - *Off East coast of U.S.*
  - *Over West Coast of U.S. in thunderstorms*

© 1996 T.E. BEARDEN



Possible Tests (3)

- Blinding of several U.S. satellites (up to 4 hours in duration)
- Cold Explosion off Kurils 1984
  - First, a cold explosion
  - Then test of giant Tesla shield 300 mi. dia.
- Tests offset from shuttle launch Nov. 85
- Kill of Arrow DC-8,Gander, NFLD Dec. 1985
- Titan kill, Vandenberg AFB, CA early 1986
- Kill U.S. Challenger, off Cape Canaveral 1986
- Earthquakes induced, 1986-88
- Dozens of tests of shields around the world
- Decades of radiating U.S. Embassy in Moscow

© 1996 T.E. BEARDEN



Possible Tests (4)

- Extensive tests 1990-99 in Western Australia
- Engineering of weather since 1990 by Yakuza
- Possible nuclear dudding test in WA in 90s by Aum Shinrikyo
- C-130 engine flameout kill
- TWA-800 kill 1997
- Gulf War Disease Induced, 1991
- Spreading of immune systems of U.S. populace, 1990s
- Psychoenergetic control of Captain Button
- Psychoenergetic control of Captain Svoboda
- Twice in 1997, within days of full strategic destruction of U.S.

© 1996 T.E BEARDEN



Mushroom cloud rising from sea

- 0514 hrs, 9 April 1984
- Gray-white cloud appeared
- Rose 60,000 feet in 2 minutes
- South of Kuril Islands
  - *180 miles southeast of Hokaido*
  - *200 miles from Tokyo*
- Soviet missile testing scheduled about 350 miles away, at 2100 hrs, 9 April 1984

© 1999 T. E. BEARDEN


Launches from Cape Canaveral
and Vandenberg AFB
Provided Practice Targets of Opportunity



The sinking U.S.S. Thresher, with her controls jammed, implodes when she reaches crush depth

APRIL 1963
533
© 1978 HAL CRAWFORD
USED BY PERMISSION


Thermometers
C-1
C-2
C-3
C-4
Calorimeters
Film Radiation Detectors
D-1
D-2
D-3
D-4
Radiation Counters
RC-1
RC-2
RC-3
RC-4
RC-5
RC-6
Power
Meter
Experimental Region

Figure 32. Embodiment of an instrumental array sufficient to discriminate when time-density charging has occurred, and that transduction of time-charge decay is occurring.

© T.E. BEARDEN 1998



Time-Polarized EM Wave interferometer Creating Space-Time Curvature Engines in a Distant Interference Zone

TRANSVERSE WAVE GENERATOR #1
PHASE CONJUGATOR #1A
PHASE CONJUGATOR #1B
SPACETIME CURVATURE ENGINE / XMTR #1
CONTROLLER
LONGITUDINAL EM WAVES
TIME-DENSITY EM WAVES
IZ
PHASE CONJUGATOR #2A
PHASE CONJUGATOR #2B
SPACETIME CURVATURE ENGINE / XMTR #2
POWER SUPPLY
TRANSVERSE WAVE GENERATOR #2
© T.E. BEARDEN 1998


Transmutation of Radioactive Nuclei at a Distance
Interferometer (may be multiple beam or single beam) is played through the radio-isotopes of the nuclear wastes to be neutralized. Specific engines may be used for altering specific isotopes.
Spacetime curvature engines act within any intercepted radioactive wastes
Active Spacetime Curvature Engines Zone of action
Waveset 1 generator
Engines Calculation
Waveset 2 Generator
Trans-mission Control
Nuclear wastes in storage, in ditches, in containers, etc.
© T.E. BEARDEN 1998



Transmutation of Radioactive Nuclei (2)

Specific spacetime curvature engines used are to add excess energy to selected radionuclei, including intermediate decay isotopes. In this way, decay is dramatically speeded up.

Spacetime curvature engines act within any intercepted radioactive wastes, adding excess energy

Active Spacetime Curvature Engines Zone of action

Nuclear wastes in storage, in ditches, in containers, etc.

Waveset 1 generator

Engines Calculation

Waveset 2 Generator

Trans-mission Control

© T.E. BEARDEN 1998



Typical Shield Test, Northern Route to Japan

Asahi Evening News, Tokyo
June 22, 1982

Multiple tests seen per month, for years.
Pilots simply ceased reporting them.

© T. E. BEARDEN 1994, 1995



A Curious Tide in Human Affairs

To win its freedom in the long run, usually a group must defeat its attackers or suppressors *at least twice*.

- We fought the British twice for our independence.
- We are fighting ourselves twice to free the slaves. - American Civil War
  - Civil rights struggle
- We beat the Germans twice, in WW I and WW II
- We beat the Hispanics in the Spanish-American War. *That's once*. (They're winning the second by crossing the border. The U.S. is becoming a Hispanic Nation).

But we also have some unfinished business at hand.

- We checked the Russians in the Cold War. *Once*.
- We checked the Japanese in WW II. *Once*.
- We checked the KGB in the Cold War. *Once*.
- We checked the Communists in the Cold War. *Once*.
- We checked Saddam Hussein in the Gulf War. *Once*.



Large Scalar EM Interferometer (LASI) Accident Near Urals, 1958

- 1958 nuclear explosion near Urals
  - Signature of large scalar interferometer (LASI) accident
  - Buried atomic wastes suddenly exploded
  - Large region contaminated to this day
- Soviets were well along with advanced LASI prototypes and testing
  - Khrushchev announced forthcoming advent of these "fantastic" weapons in Jan. 1960
  - 1958 difficulties could have been resolved by 1960
- Expected 1958 cause: transmitter short-out and failure in a nearby LASI discharged its cumulated energetics beam energy into the ground
- *Spreading ground pulse struck nearby atomic wastes, fissioning nuclei*



The Superpower Paradox: Asymmetric Cheap WMD Strategic Strike and Destruction

Complex, expensive, high tech
LIBYA
EGYPT
SUDAN
SAUDI ARABIA
IRAN
Simple, cheap, low tech

© 1990, 1996, 1998 T. E. BEARDEN



THE KGB/YAKUZA-AUM WAR PLAN

- *Dud all quantum potential weapons in other nations via psychoenergetics.*
- *Remove U.S., Israel, Brazil, West Europe as military powers.*
- *Destroy nuclear weapons, hostile energetics weapons, hostile ships, 80% of targeted populaces in first hour of strikes.*

LEASE

1990-91

Aum/Yakuza Acquired Use of on-site Russian Scalar EM (Energetics) Weapons.

Began Geosurvey of Test Range (Western Australia) for training.

KGB Tested QP population wpn (Gulf War Syndrome)

TRAIN

1991-94

Began extensive training of AUM-Yakuza crews in Russia, with practice firing into Western Australia. J-team took over world-wide weather engineering. Preparing for occupation of West Australia.

ESCALATE

1995-99

Began EM kill of selected lone U.S. targets, iaw strategic deception plan.

U-2 a/c? USAir 747 ?

TWA-800 C-130

ValueJet? A-10s

Surged electrical grids.

Worldwide practice kills, scalar interferometry.

QP modification of selected pathogens

STRIKE!

1999?

2000?

Plan:

Trigger terrorist BW, & WMD attacks.

Enhance BW infections with QP wpn.

When ready, counter insane QPweapons with psychoenergetics. Destroy QP wpns.

Dud all nuclear weapons worldwide;

Time-snap ships, scalar weapons sites;

Attack major target populations w/QP.

Then cleanup with interferometry strikes.

©1996, 1999 T.E. BEARDEN



Why Western Science is Ignorant of KGB Energetics

- *Foundations* of electrodynamics and much of Western physics are seriously flawed
- Only just rediscovering longitudinal EM waves
- No knowledge of using time-polarized EM waves
- Does not know a powerful GR is hidden in EM
- Ignores inner structure of potentials, waves, fields
- Hotly defends errors, ignores for a century
- Determined to push big nuclear science
- Suppresses research to approved dogma by rigorously controlling precisely what research the funds can be used for



Transmutation of Radioactive Nuclei at a Distance

Interferometer (may be multiple beam or single beam) is played through the radio-isotopes of the nuclear wastes to be neutralized. Specific engines may be used for altering specific isotopes.

Spacetime curvature engines act within any intercepted radioactive wastes

Active Spacetime Curvature Engines Zone of action

Nuclear wastes in storage, in ditches, in containers, etc.

Waveset 1 generator
Engines Calculation
Waveset 2 Generator
Trans-mission Control

© T.E. BEARDEN 1998

THE YAKUZA

(JAPANESE MAFIA)

To do business with Japan is to do business with the Yakuza



© 1995, 1996, 2001 T.E. BEARDEN

The Last Samurai, Defending Bushido

- **3 Major Yakuza Groups, In Coalition.**
- **Penetrate Japanese Government.**
- **Open Offices, Signs on Street.**
- **Public Romanticizes Yakuza as Last Japanese Samurai**
- **In Large High-Tech Corporations.**
- **In Control of Japanese Banks.**
- **Japanese Real-Estate Rip-off.**
- **$500 - 1,000 Billion per Year Income.**
- **Rapidly Spreading in U.S.**
- **Uniting Mafia Groups Worldwide.**
- **Coalition with Aum Shinrikyo.**
- **Leased Russian Energetics Weapons.**
- **Crews On-site in Russia, Trained.**
- **Practice Firings into Western Australia for Three Years. (Dozens of Shots per Month)**
- **Now in Escalation Phase, Killing U.S. Targets.**
- **All-out Strike on U.S. ready 1999-2000.**
- **Now held in check by KGB, dead-man fuzed by small nation friendly to U. S.**



Yugoslav Earthquake, Followed by Cold Explosion

Apr. 15
1979

- Magnitude 7.2 on Richter scale
- Epicenter 33 km. deep
- More than 100 aftershocks
- At Kamenari:
  - Adriatic sea mushroomed up
  - Like atomic bomb explosion
  - Signature of a cold explosion
  - Similar to Apr. 1984 test off coast of Japan, near Kurils (see inset graphics)
- *Note that April is a significant test month for the Communists (preparing official reports for May Day?)*

OFF JAPAN, NEAR KURILS

1984 COLD EXPLOSION
SIMILAR TO THIS ONE

© T.E. BEARDEN 1994, 1996

Technical Background on the Priore Healing Process

Contents

1. Technical Background on the Priore Healing Process
2. Transduction of EM wave types by successive phase conjugation.
3. Time-charging and Time-density excited states
4. Interference for transduction in slow decay of time-density excited states
5. Infolded longitudinal biwaves composition of a scalar potential
6. Scalar potential interferometry produces all EM force fields and waves
7. Some serious flaws and errors in classical EM theory (#1-16)
8. Some serious flaws and errors in classical EM theory (#17-32)
9. Abnormal penetration depth of weak signals due to photon interaction
10. Amplified replica of body's signal complex to reverse cellular disease & damage
11. Amplified replica of body's signal complex to correct a congenital condition

Technical Background on the Priore Healing Process



© T.E. BEARDEN 2001

Published by Lotus® Freelance Graphics®


TRANSVERSE EM WAVE PLUS
PHASE CONJUGATE REPLICA WAVE
LONGITUDINAL EM SURGE WAVE
LONGITUDINAL EM WAVE PLUS
PHASE CONJUGATE REPLICA WAVE
$\dot{(t)}$
TIME DENSITY WAVE
Oscillates rate of flow of time
about some average value

© T.E. BEARDEN 1994, 1995

Figure 1. Transduction of EM wave types by successive phase conjugation.

Published by Lotus® Freelance Graphics®


ELECTRON ABSORBS PHOTON
ENERGY, MOVES TO HIGHER
ENERGY LEVEL. DECAYS
BY EMITTING PHOTON
ΔE
nucleus
Δt remains
coupled
ELECTRON ABSORBS TIME
DENSITY, MOVES TO DIFFERENT
TIME DENSITY LEVEL. DECAYS BY
EMITTING LONGITUDINAL OR
PSEUDOLONGITUDINAL
PHOTON
Δt
nucleus
ΔE remains
coupled

Figure A. Excited energy density level. Figure B. Excited time density level.

© T.E. BEARDEN
1998

Figure 2. Time-charging and Time-density excited states, contrasted to ordinary spatial energy excited state.

Published by Lotus® Freelance Graphics®


TRANSVERSE EM WAVES
INTERFERENCE ZONE
LONGITUDINAL EM WAVES INTERFERING
LONGITUDINAL EM WAVES
INTERFERENCE ZONE
(t)
(t)
TIME DENSITY EM WAVES INTERFERING
© T.E. BEARDEN

Figure 3. Interference processes for transduction in slow decay of time-density excited states.

Published by Lotus® Freelance Graphics®


GALLOPING VELOCITY
Scalar Potential ϕ
© T.E. BEARDEN 1997
...ETC
* * * ...ETC
V avg
Wavepair #3
HARMONICS
V avg
Wavepair #2
SUBHARMONICS
V avg
Wavepair #1
...ETC
* * * ...ETC.
DISTANCE

The Structure Is:

A harmonic set of longitudinal wavepairs. In each wavepair the two waves superpose spatially, but travel in opposite directions. The two are phase conjugates and time-reversed replicas of each other. Thus they comprise a coupled longitudinal wave and antiwave. Each wavepair is a time-density wave and therefore an electrogravitational wave.

Figure 4. Infolded longitudinal biwaves (time-density EM waves) composition of a scalar potential.

Published by Lotus® Freelance Graphics®


(Use of Hidden Information Content of the Field)
(Can Provide Action-at-a-Distance)
Note:
Whittaker's 1904 paper initiated the entire field of superpotential theory.
ϕ_1
ϕ_2
Interference Zone
(Potential gradients)
Normal EM Energy:
May be positive, or negative, or fixed
Hidden Bidirectional EM energy flow
Hidden Bidirectional EM energy flow
Scalar Potential Beams
XMTR
XMTR
Whittaker/Ziolkowski Transmitter Arrays
(8 to 20 harmonic wavepairs each)
© T.E. BEARDEN 1997

Figure 5. Scalar potential interferometry (between the two sets of bidirectional longitudinal EM wavepairfunctions) produces all EM force fields and waves.

Published by Lotus® Freelance Graphics®



1. Eliminates the Internal EM Inside the Scalar Potential.
2. Equations Still Assume Material Ether Per Maxwell (Unchanged).
3. No Definition of Electrical Charge or of Scalar Potential.
4. Use of Force Fields in Vacuum is False (and Known to be So).
5. Treats Charge q as Unitary Instead of Coupled System $q = \phi(q)m(q)$.
6. Confuses Massless Potential Gradients as Forces (See #3, #4).
7. Does Not Utilize Mass as a Component of Force (See #23).

---

8. Erroneously Assumes EM Force Fields as Primary Causes.
9. Topology of EM Model Has Been Substantially Reduced.
10. Does Not Include Quantum Potential or Action at a Distance.
11. Does Not Include Superluminal Velocity of Inner EM Components.
12. Does Not Utilize Extended Near-Field Coulomb Gauge Effects.
13. Does Not Include EM Generatrix Mechanism for Time Flow.
14. Does Not Unify Photon and Wave Aspects (Requires 7-D Model).

---

15. Does Not Include Electron Spin and Precession (See #19, #24).
16. Treats EM Energy As Existing In "Chunks," Instead of as Flow.

Figure 6. Some serious flaws and errors in classical EM theory (#1-16)

© T.E. BEARDEN 1994, 1997

Published by Lotus® Freelance Graphics®



17. Confuses Energy and Energy Collection (See #16).
18. Discards Half of Every EM Wave in Vacuum (See #22).
19. Erroneously Uses Transverse Vacuum Wave; It's Longitudinal.
20. Arbitrarily Regauges Maxwell's Equations to Eliminate Overunity.
21. Omits Phase Conjugate Optics Effects (The *Rule* in Internal EM).
22. Does Not Include EM Cause of Newtonian Reaction Force.
23. Erroneously Assumes Separate Force Acting on Separate Mass.
24. Confuses Detected Electron Precession Waves as Proving Transverse EM Waves in Vacuum (Remnant of Old "EM Fluid" Concept).
25. Due to Error in String Wave, Omits the Ubiquitous Antiwave.
26. *Assumes* Equilibrium; Not True Unless Include Vacuum Interactions.
27. Higher Topology Required, to Model Electromagnetic Reality.
28. Lorentz surface integration discards Poynting energy transport.
29. Has nothing at all to say about form of EM entities in massless space.
30. Eliminates the infolded general relativity using EM-force as curve agent.
31. Does not include longitudinal EM waves as time domain oscillations.
32. Does not include EM mechanism that generates time flow and flow rate.

Figure 6. Some serious flaws and errors in classical EM theory (#17-32)

© T.E. BEARDEN 1994, 1997

Published by Lotus® Freelance Graphics®


THIN SIGNAL ENVIRONMENT
(SINGLE PHOTON INTERACTIONS)
DENSE SIGNAL ENVIRONMENT
(MULTI-PHOTON INTERACTIONS)
Skin
Tissue
Bone
Marrow
EM input
Scattered EM energy diffusion (heat) (entropic)
EM input
EM input
EM input
Additional Non-scattered EM energy diffusion (negentropic)
EG output
NORMAL TOPOLOGY EM
HIGHER TOPOLOGY EM

In a dense signal environment, phase conjugation effects become significant, generating PCR signals which couple to and backtrack the cells' and tissues' own signals, thus penetrating deeply throughout the body with weak partial cancellation jamming.

Figure 30. Abnormal penetration depth of incident weak signals due to multiphoton interaction in a dense weak signal environment.

Published by Lotus® Freelance Graphics®


Recorders & Broadband Amps
Broadband Antenna Unit
Control Unit
Receiver-transmitters
Adjusting broadband signals bandwidth and amplification

Figure 31. Using an amplified replica of the body's own dense, broadband signal complex to irradiate it, producing deeply-penetrating and precise longitudinal EM wave sets that pump cells and reverse cellular disease and damage.

© T.E. BEARDEN 1996

Published by Lotus® Freelance Graphics®


Alterations Database
Recorders & Broadband Amps
Control Unit
Broadband Antenna Unit
Receiver-transmitters

Time density charge is structured to contain the precise spacetime curvature engines for time-reversal and steering. Charging occurs quickly. Engines continue to work for an extended period after charging ceases.

Adjusting broadband signals' bandwidth and amplification by selecting indicated alterations from database

Figure 9. Using an amplified replica of the body's own dense, broadband signal complex containing added alterations, to irradiate the body and produce deeply-penetrating precise time-density charging for cellular time-reversal, while steering the time-reversal trajectory to also correct a congenital condition.

© T.E.[illegible] [illegible]

Published by Lotus® Freelance Graphics®

San Francisco
R-2508
China Lake
Point Mugu
Sea Range
Ft.Irwin
Edwards AFB
Los Angeles
San Diego
Santa Fe
Albuquerque
Missile Range
White Sands
Las Cruces

The Anomalies in Navy Electrolyte Experiments at China Lake

These novel experimental anomalies, like those of Cold Fusion, were caused by using time as an energy source by transducing time-energy into spatial energy. Transducing one microsecond per second of time into spatial EM energy, yields nearly 10^{11} watts of power

- Melvin H. Miles and Benjamin F. Bush, "Radiation measurements at China Lake: Real or Artifacts?", *Proc. ICCF-7 (International Conference on Cold Fusion—7)*, Vancouver, BC, Canada, Apr. 1998, p. 101.

- Consistency of China Lake Anomalies
- Anomalous LW EM Emission Phenomena at China Lake (1)
- Anomalous LW EM Emission Phenomena at China Lake (2)
- Sufficient LW-to-TW Transduction Ionizes GM Tube Gas (3)
- Sufficient LW-to-TW Transduction Ionizes GM Tube Gas (4)
- Consistency of Anomalies
- Consistency of Anomalies (2)

- Experimental LW Emission Phenomena in Electrolysis



Consistency of China Lake Anomalies

- Variation in LW-TW transduction from experiment to experiment
- Majority produced insufficient transduction to cause ionization discharge of the GM tube gas (to cause detection)
- Correlation between appearance of anomalous radiation and the expected time periods to load palladium with deuterium
  - Within few hours in co-deposit experiments where palladium is loaded with deuterium as it deposits from solution
  - Required days of electrolysis for rods that load much slower
- The faster the deuterium loaded, the greater the interaction of deuterium in phase conjugating and self-targeting in lattice
- Variation in GM detector readings
  - One would read anomalous radiation, another would be blind to it
  - A few experiments gave simultaneous readings from two detectors
- Experiments perfectly consistent with LW-TW transduction, time-density charging, variation in GM time histories, and new conservation of energy law

© 1998 T.E. Bearden

Next Slide

Return to Index



Anomalous LW EM Emission Phenomena at China Lake (1)

- Anomalous radiation from electrolysis in ionization processes
  - Two experiments producing excess power
  - Dental X-ray film showed exposure
  - Simultaneous control study: no exposure
  - 20 experiments without excess power: no exposure
- Excess energy strongly indicates excess film exposure

© 1998 T.E. Bearden

* Melvin H. Miles and Benjamin F. Bush, "Radiation Measurements at China Lake: Real or Artifacts?"

Next Slide Return to Index Previous Slide



Anomalous LW EM Emission Phenomena at China Lake (2)

- GM and NaI detector reaction when electrolysis with heavy water ongoing
  - Several Geiger-Muller (GM) tubes gave anomalous detection
  - Reached 73 sigma above background
  - No anomalies when experiment off
- *GM tube detects anything which causes its internal ionization*
  - *Nuclear radiation is ionizing*
  - *Transduced x-ray & gamma is ionizing*

Next Slide

Return to Index

Previous Slide



Sufficient LW-to-TW Transduction Ionizes GM Tube Gas (3)

- Time-history of detector involved
  - Some GM detectors show anomalous high counts, some do not
  - Time histories of GM detectors are varied
  - Time histories of film vary minimally
- *Experimental results consistent with*
  - *LW-to-TW transduction including delay*
  - *Time-energy charging*
  - *New extension to energy conservation law*

© [illegible] T. E. Bearden

Next Slide

Return to Index

Previous Slide



Sufficient LW-to-TW Transduction Ionizes GM Tube Gas (4)

- Time-history of detector involved
  - Some GM detectors show anomalous high counts, some do not
  - Time histories of GM detectors are varied
  - Time histories of film vary minimally
- *Experimental results consistent with*
  - *LW-to-TW transduction including delay*
  - *Time-energy charging*
  - *New extension to energy conservation law*

© 1988 T. E. Bearden

Next Slide

Return to Index

Previous Slide



Consistency of Anomalies

- LW-to-TW transduction varied from experiment to experiment
- Most experiments produced insufficient transduction to cause ionization
- Appearance of anomalous radiation correlated with expected time loading of palladium with deuterium
  - Within few hours in experiments where palladium loads with deuterium as it deposits from solution
  - Required days for rods that load much slower

© 1998 T. E. Bearden

Next Slide

Return to Index

Previous Slide



Consistency of Anomalies (2)

- Faster the deuterium loaded, the greater the interaction of deuterium in
  - Phase-conjugating and self-targeting
  - Producing time-reversal zones
  - Generating quasi-nuclei of H+ ions (protons)
- Variation in GR detector readings
- Experimental results predictable by
  - LW-TW transduction and time-reversal zones
  - Varying time-density charging on GM tubes
  - Variation in GM tube experience histories
  - Time-reversal zones generating electronuclear interactions and quasi-nuclei of H+ clusters

© 1998 T. E. Bearden

Next Slide

Return to Index

Previous Slide



Experimental LW Emission Phenomena in Electrolysis

- Anomalous radiation from electrolysis in ionization processes
  - Two experiments producing excess power
  - Dental x-ray film showed exposure
  - Simultaneous control study: No exposure
  - 20 experiments without excess power: No exposure
- Excess energy strongly indicates excess film exposure
- GM and NaI detector reaction when electrolysis ongoing w/heavy water
  - Several Geiger Muller (GM) tubes gave anomalous detection
  - Reached 73 σ above normal background counts
  - No anomalies when experiment off
- GM tube detects anything which causes its internal gas to ionize
  - Nuclear radiation is "ionizing" radiation
  - Transduced x-ray and gamma radiation is "ionizing" radiation
  - Sufficient LW-TW transduction ionizes GM gas
- Time History of detector involved
  - Some GM detectors show anomalous high counts, some do not
  - Time histories of GM detectors vary appreciably
  - Time histories of film vary minimally
- Experiments consistent with time-density charging, LW-TW transduction, and new conservation of energy law

© 1998 T. E. Bearden

* Melvin H. Miles and Benjamin F. Bush, "Radiation Measurements at China Lake: Real or Artifacts?" Proc. ICCF-7, Vancouver, BC, Canada, Apr. 1998, p. 101

Return to Index

Previous Slide

A Visual Tour of what they don't want you to know about electrical circuits

10 TRILLION PERCENT OF THE CURRENT PRODUCED IS WASTED!

---

1. The scalar potential is a harmonic set of phase conjugate longitudinal EM waves.
2. The dipole is a true negative resistor.
3. The dipole's broken 3-symmetry initiates a spreading giant negentropic reordering of a fraction of the vacuum's energy.
4. Energy flow contours surrounding a transmission line.
5. Heaviside and Poynting energy flow components. The Heaviside component is often **10 trillion times** the Poynting component, but **is simply wasted** in ordinary single-pass energy circuits.
6. Negative resistance process v. positive resistance process.
7. Lorentz's integration trick to discard the enormous Heaviside non-diverged energy flow component.



[Next Slide](#)

[Return to Index](#)

The Structure Is:

- A harmonic set of longitudinal phase conjugate wavepairs.
- In each wavepair the two waves superpose spatially after detection, but travel in opposite directions.
- The convergent wave set is in the imaginary plane, and hence is not observable. It is EM energy incoming to the potential (dipolarity) from the time domain.
- The charge's spin is 720 degrees, 360 in the real plane and 360 in the imaginary plane.
- Hence the charge receives the complex convergent EM energy, transduces it into real EM energy, and emits enormous energy at the speed of light in all directions -- which includes bidirectional pairs in 3-space (after the reaction, being after "observation").
- This produces the fields and potentials from the "source charge or dipole."
- Mandl and Shaw argue that the scalar (time-polarized) photon and longitudinal photon are observable only in similar pairs, which then makes the instantaneous scalar potential. Thus their quantum field theory work strongly supports the "negative resistor" interpretation of the scalar potential and our solution to the source charge and source dipole problem.

Figure 1. The scalar potential is a harmonic set of phase conjugate longitudinal EM waves.



Note: Decompose the potential between the end charges of the dipole

- Receives enormous EM energy in complex plane (similar to reactive power)
- Transduces it into real EM energy and emits it in all directions at the speed of light
- The emitted EM energy forms the fields and potentials and their energy, across space, from this "source dipole"

* Basis established by E.T. Whittaker, "On the Partial Differential Equations of Mathematical Physics," Math. Ann. 57, 333 (1903). Ignored since then.

LEGEND

→ Outgoing real EM energy

← – – – – – Incoming complex EM energy

Figure 2. The dipole is a true negative resistor.

Next Slide

Return to Index

Previous Slide



Broken 3-space symmetry initiates jump to 4-space symmetry between complex plane and real plane. Energy flow is now conserved in 4-space, but not in 3-space. This is the true negative resistor effect, and a negentropic reordering of the vacuum.

Ø
Energy Flow Density
Reordering is into form of Whittaker* harmonic set of bidirectional EM longitudinal wavepairs. Reordering is totally deterministic.
EM energy flow converging on dipole in the complex plane (nonobservable)
EM energy flow diverging from dipole in real 3-space (observable)
r = ct
Radius of negentropically re-ordering vacuum energy at time t in seconds, after dipole formation
Re-ordering spreading at light speed
0
DIPOLE LOCATION
0
RADIAL DISTANCE IN ANY DIRECTION
?

Figure 3. The dipole's broken 3-symmetry initiates a spreading giant negentropic reordering of a fraction of the vacuum's energy.

Next Slide

Return to Index

Previous Slide



NONLOCAL (Nondivergent) This huge Heaviside component misses the circuit and is not intercepted. It is wasted.

Tiny "sheath" Poynting component strikes surface charges and is diverged into conductors to power the circuit.

NONLOCAL (Nondivergent)

Contours are in watts/ sq meter (If interacted with a unit point static charge and the energy collected). More charge at each point will collect more watts/ sq meter at each point.

Figure 4. Energy flow contours surrounding a transmission line.

Next Slide

Return to Index

Previous Slide


Heaviside component (nondiverged)
Poynting component (diverged)
Drude electron gas
CONDUCTOR
© T.E. Bearden 2000

Figure 5. Heaviside and Poynting energy flow components. The Heaviside component is often 10 trillion times the Poynting component, but is simply wasted in ordinary single-pass energy flow circuits.

[Next Slide]
[Return to Index]
[Previous Slide]


i
NORMAL RESISTOR
i
+
BATTERY
−
i
−
NEGATIVE RESISTOR
(Acts as a battery)
+
i
NORMAL RESISTOR
i

Figure 6. Negative resistance process vs. positive resistance process. A negative resistor receives energy in unusable form, transduces it, and outputs it in usable form. A positive resistor receives energy in usable form, and scatters it into unusable form.

[Next Slide]

[Return to Index]

[Previous Slide]



1a. Lorentz surface integration.

1b. Actual S in and S out.

See Panofsky & Phillips, Classical Electricity and Magnetism, 2nd. edn., Addison Wesley, 1962, p. 178-181.

Note: If the S-vector is integrated over the closed surface, then all nondiverged energy flow is zeroed, leaving only the very small component of the input S-flow that is powering the joule heating of the resistor. In short, only the small component of the S-flow that is equal in magnitude to the Poynting vector remains. This measures only the tiny portion of the S-flow that is intercepted and diverged into the conductors by their surface charges, powering the electrons and then dissipated out of the resistor as joule heating.

The Lorentz procedure arbitrarily discards the enormous Heaviside component that misses the circuit entirely and is wasted. This results in a non sequitur of first magnitude in energy flow theory .

Figure 7. Lorentz's integration trick to discard the enormous Heaviside non-diverged energy flow component.

Return to Index

Previous Slide

ILLUSTRATION LIST:

Page 1
(Table 1)
[note 1]

Page 2
(Table 2)
[note 2]
[note 3]
[note 4]
[note 5]

Page 3
[note 6]
[note 7]
[note 8]
[note 9]
(Figure 1)
(Figure 2)
(Figure 3)
(Figure 4)
(Figure 5)
(Figure 6)

Page 4
[note 10]
[note 11]
[note 12]
[note 13]
(Figure 7)
(Figure 8)
(Figure 9)
(Figure 10)

Page 5
[note 14]
[note 15]
Figure 11
Figure 12

Page 6
[note 16]
[note 17]
(Figure 13)
(Figure 14)
(Figure 15)

Page 7
[note 13]
[note 18]
[note 19]
[note 20]
(Figure 16)

Page 9
(Table 3)
[note 22]
(Figure 17)
(Figure 18)

Page 10
[note 23]
[note 24]
[note 25]
[note 26]
[note 27]
(Figure 19)
(Figure 20)

Page 12
(Table 4)
[note 28]
[note 29]
[note 30]
(Figure 21)
(Figure 22)

Page 13
[note 31]
[note 32]
[note 33]
[note 34]
[note 35]
(Figure 23)

THE VIRTUAL TIMES

CHASING THE WILD DRAGON:

Foundations of a New Science

By T.E. Bearden
November 12, 1995

It is a pleasure to accept the offer of John and Larry to write a column in their new InterNet magazine. Theirs is a great venture, and with the energy and knowledge they bring to the task, one can be confident of their success in making this a very interesting and informative publication.

There is a new "rebel" science slowly being born, with most of the work being done outside the universities and orthodox scientific community. In the months ahead it will be my job to try to acquaint you with the gist of what's going on, and what all the excitement is about.

This first article is deliberately just introductory, and its purpose is to interest you in the unusual fields we are going to be covering in more scientific detail, in future columns. We will also be listing a variety of references from the technical literature, which bear upon the various points addressed.

In this first article a little of my own background experience [note 1] is given, so you can decide whether you will be interested in what we have to say!

The real purpose of the column will just be to *present information* that you may not be able to readily obtain any other way. We will not argue or debate with skeptics; nothing productive is to be gained by that. If the information we present is useful to you, then our purpose has been accomplished. If it isn't of use to you, then just file it in the old wastebasket. Also, from time to time I may answer a generic question, constructed from multiple queries. Individual responses to correspondence cannot be provided.

The work toward a new breakthrough science is going on in a broad spectrum of "fields," most of which are not yet recognized by academia as even constituting legitimate areas of scientific endeavor (Table 1).

Some of the major areas involved are:

1. theoretical and experimental research in overunity electrical machines,
2. free energy research of other kinds, such as devices utilizing thermodynamics phase changes,
3. rapidly advancing efforts in cold fusion,
4. work on permanent magnet motors,
5. antigravity research, both theoretical and experimental,
6. development and utilization of a "hidden" electrodynamics inside the scalar potential (inside voltage),
7. the "memory" of space and materials; where this "memory" can be deliberately conditioned so that space and the materials themselves become causal actants rather than simple inert entities,

8. direct engineering of quantum change via a new kind of "hidden electrodynamic variables,"
9. the direct engineering of the vacuum's virtual photon flux exchange with matter,
10. action at a distance, including the deliberate formation and usage of quantum potentials,
11. direct engineering of the local curvature of spacetime (yes, the direct engineering of general relativity, using the new hidden kind of electrodynamics),
12. use of the new "hidden" electromagnetics to engineer body cells including the reversal of diseased cells, genetics and all, back to a previous healthy state (cellular dedifferentiation, in biophysical terms, or cellular phase conjugation, in physics terminology),
13. research toward the direct engineering of the mind, including both the conscious and unconscious minds, long-term memory, and the personality itself, and
14. a ruthless re-examination (and correction where necessary and possible) of the definitions, concepts, and postulates that present physics is founded upon.

ILLUSTRATION LIST | NEXT PAGE

©copyright T.E.Bearden 1995

VT Page1

Comments may be sent to
the **Editor** of The Virtual Times

[1] For those interested in orthodox qualifications, I have an M.S. in nuclear engineering (1971) from Georgia Institute of Technology and a BS in mathematics (1953) from what is now Northeast Louisiana University with a minor in electronic engineering.

Table 1. Fourteen Emerging New Science Areas

1. Overunity Electrical Machines and Power Systems
2. Overunity Devices Using Thermodynamical Phase Changes
3. Cold Fusion and Non-Nuclear Transmutation
4. Self-Powered Permanent Magnet Motors
5. Antigravity and Antigravity Engineering
6. Use of the "Inner" EM Inside the Scalar Potential
7. Vacuum Engineering, With Vacuum and Materials Memory
8. Direct Engineering of Quantum Change
9. Engineering and Structuring of Massless Charge Flux
10. Action-At-A-Distance, Including Use of Quantum Potentials
11. Direct Engineering of Local Spacetime Curvature
12. "Inner EM" Time Reversal of Diseased Cells Back to Health
13. Direct Engineering of the Mind, Including Software Loading
14. Unified Field Revision of Foundations Concepts of Science

Each of these "major areas" as yet has no single "experts" in the sense that individuals exist who possess a "mastery" of the given area. As an example, in spite of multiple researchers and decades of vigorous research, no one is really an "overall expert" in the overunity electrical power systems field. The "field" itself is still struggling to be born and is not recognized at all by orthodoxy; in fact, many orthodox scientists bitterly resent one even attempting to work in this area. There is as yet no cohesive single "theory" of overunity electrical or magnetic machines, although our own group is making rapid progress in that respect. But there is still no universal agreement amongst even the researchers themselves. Literally the field is still being *discovered*.

This "groping dimly toward a new field" should not be too surprising. After all, the early electromagnetics researchers went through the same tortuous, agonizing kind of development. They were playing with cat fur, glass rods, and pith balls for quite an extended period before understanding progressed to the point where Maxwell could mathematically tie together and model the results of the experimenters such as Faraday and others. It has taken a century and a half for modern electromagnetics and electronics to reach its own present development. It is going to take another decade or so before the overunity researchers can overturn several ill-founded parts of the present electromagnetics and get the emerging field onto a solid foundations footing and into a solid theoretical position.

In the effort to produce a theoretical model of electromagnetics, Maxwell and his predecessors performed a magnificent work. Yet they also made very serious errors (Table 2), which persist to this day. [note 2] Let us list just a few of the more blatant errors in classical EM theory today:

First, Franklin guessed wrong on which way electrical current flowed in a circuit. There is no definition at all of electrical charge in all of physics, and there is no acceptable definition of potential (that is, there is no rigorous definition of just good old "voltage.") There are no "fields of force" in the vacuum; there are just potential gradients __ because the vacuum is just one vast potential (virtual particle flux) in the first place. Force fields actually occur only in and of the matter in a material system. The primary causative agents of electromagnetics are not the so-called "force fields' at all, but are the potentials __ as is well-known in quantum mechanics. [note 3] Maxwell assumed a material ether in his equations. The Michelson-Morley experiment destroyed the material ether, but the Maxwell equations have never been changed accordingly. The electron was not yet discovered when the Maxwell equations were written; the theory does not address electron spin. Maxwell was already dead some two decades when Barus' 1898 paper [note 4] was published, pointing out the strange "backwards-traveling" wave (i.e., time-reversed wave) solution to the wave equation. In addition, Heaviside and Gibbs had already produced their vector truncation __ this truncated theory is the modern so-called "Maxwell's equations" that universities teach today __ of Maxwell's theory. Not a single one of them ever appeared in any book or paper by James Clerk Maxwell. [note 5]

ILLUSTRATION LIST | NEXT PAGE

©copyright T.E.Bearden 1995

VT Page1

Table 2. Some Defects In Electrodynamics

1. Conventional Current Direction Is Reversed
2. No Definition of Charge or Potential
3. Equations Still Assume Material Ether
4. Use of Force Fields in Vacuum is Known to be False
5. Treats Charge as Unitary; lnstead, It is a Coupled System
6. Confuses Massless Potential Gradients as Forces
7. Does Not Utilize Mass as a Component of Force
8. Erroneously Assumes Force Fields as Primary Causes
9. Topology of EM Model Has Been Substantially Reduced
10. Does Not Include Quantum Potential
11. Does Not Include Proven Action At A Distance
12. Does Not Utilize Near Field Coulornb Gauge Effects
13. Does Not Include EM Generatrix for Time Flow
14. Does Not Unify Photon and Wave Aspects
15. Does Not Include Electron Spin and Precession
16. Treats Energy As Existing In "Chunks," instead of as Flow
17. Confuses Energy and Energy Collection
18. Discards Half of Every EM Wave in Vacuum
19. Erroneously Uses Transverse Vacuum Wave; It's Longitudinal
20. Omits Phase Conjugate Optics Effects
21. Does Not Include EM Cause of Newtonjan Reaction Force
22. Erroneously Assumes Separate Force Acting on Separate Mass

[2] For an independent statement that electrodynamics, both classical and quantal, are in serious disarray, see Mario Bunge, Foundations of Physics, Springer-Verlag, New York, 1967, p. 176. Quoting: "...it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state." Bunge points out many errors in electrodynamics. See also Terence W. Barrett, "Electromagnetic Phenomena Not Explained by Maxwell's Equations," in Lakhtakia, A. (ed.): Essays on the Formal Aspects of Electromaqnetic Theory, World Scientific, Singapore, 1992, p. 6-86. To find information on what's wrong with EM theory, one must read foundations literature, not the standard textbooks. One of my own contributions has been to point out that the notion of charge q is not unitary. In fact, electrical charge should be defined in terms of q ~ m(sub q)~(sub q). In other words, electric charge q has a massive part m, and a massless part consisting of its potential phi. Further, the magnitude of phi is just the change in the virtual photon flux of the ambient vacuum, due to the [quantum field theoretic] virtual photon exchange with the mass of the q. It follows that the true electrical charge of a particle is just its native potential ~, which is also a dynamic energy exchange with the surrounding vacuum. It also follows that this massless electrical charge changes whenever the particle is placed in a potential (in a different ambient virtual photon flux). After all, potentials superpose; that is their major characteristic. Note that the potential of the test particle is ignored in classical electromagnetics, whenever one speaks of the "E-field" upon the particle. Further, the actual structure of this virtual photon flux that comprises massless electrical charge, can itself be deterministically structured and utilized to generate nonlinear effects that do not appear at all in the present conventional theory. We will be covering many of these effects in future articles.

[3] E.g., see Y. Aharonov and D. Bohm, "Significance of Electromagnetic Potentials in the Quantum Theory," Physical Review, Second Series, 115(3), 1959, p. 485-491. Effects of potentials on charged particles exist even in the region where all the fields (and therefore the forces on the particles) vanish, contrary to classical electrodynamics. The quantum effects are due to the phenomenon of interference. These effects occur in spite of Faraday shielding. The Lorentz force does not appear anywhere in the fundamental quantum theory, but appears only as an approximation that holds in the classical limit. In QM, the fundamental physical entities are the potentials, while the fields are derived from them by differentiation.

[4] Carl Barus, "A Curious Inversion in the Wave Mechanism of the Electromagnetic Theory of Light," American Journal of Science, Vol. 5, Fourth Series, 1898, p. 343-348.

[5] E.g., see Paul J. Nahin, Oliver Heaviside: Saqe in Solitude, IEEE Press, New York. Quoting from p. 9: "...nowhere in Maxwell's writings do the equations for the electromagnetic field appear as we write them today. Maxwell used an amalgamation of Cartesian component and quaternion notation, and it was Heaviside who first wrote the electromagnetic field equations in modern vector form." Quoting from p. 92: "In actuality , however, the fields were not the primary reality to Maxwell at all (that is an idea that developed after Maxwell's death and is due to Hertz and Heaviside), but rather it was Faraday's 'electrotonic state' that he thought to be the real thing. Like Faraday, Maxwell believed that electromagnetic effects are observable results of an altered state of the ether. The mathematical formulation of this electrotonic state, for Maxwell, is what we today (as he did) call the vector potential." And again, from p. 96: "To Maxwell, however, the vector potential had a most definite physical meaning."

So the time-reversed EM wave that one finally sees emerging in nonlinear phase conjugate optics in the early 1970s was omitted from the Maxwellian theory and its later modification by Heaviside and Gibbs. Maxwell's actual theory is in a higher topology (quaternion algebra), and involves some 20 quaternion equations. Heaviside and Gibbs created vector algebra, and seriously curtailed Maxwell's theory when they "translated" it into the much lower topology of vectors and some four equations. The later addition of tensors as the basis mathematics did not restore the lost topology provided by the quaternion model.[note 6]

For the EM wave, Maxwell simply assumed the transverse EM wave that had come from the much earlier derivation of the familiar wave equation from the old "plucked taut string" notions. [note 7] Yet when one closely examines and corrects some of the erroneous *assumptions* [note 8] made for the actual mathematical derivation of this "taut string" transverse wave, one finds (Figure 1) that an equal-energy second antiphased transverse "antiwave" is actually produced by the instrument and added to the "plucked string's" transverse wave disturbance of the air medium, to produce a longitudinal wave of compression and rarefaction in the air itself. The "transverse string wave" in fact never leaves the string. The string wave is not the wave that is launched into the medium.

A similar electromagnetic situation exists. In a whip antenna (Figure 2), the Drude electron gas in the conductor does exhibit a transverse "string-type" EM wave of electron precession. However, at the same time, by Newton's third law (which Maxwell neglected because at the time the atom was regarded as just a blob with no internal structure) the positively charged, phase conjugated atomic nuclei have equal energy, highly damped transverse recoil waves created in them. Further, these "nuclei-recoil" waves are phase conjugate replicas of the electron gas waves. The total disturbance that is launched into the vacuum from the whip antenna is (a) the normal transverse disturbance of the virtual photon flux of vacuum caused by the electron gas wave, and (b) the coupled equal-energy transverse antiwave caused by the nuclei-recoil via Newton's third law. The amplitude of the material antiwaves of nuclei vibration are highly damped because of the massiveness of the nuclei; however, they are of equal energy to the electron wave. But when launched into the same vacuum, the two equal-energy wave disturbances experience equal damping because they are in the same medium. Hence the wave and antiwave are (a) locked together in the vacuum, and (b) of equal energy, and (3) of equal amplitude once launched into the vacuum. What results is a vacuum EM wave of rarefaction (reduction in intensity) and compression (increase in intensity) of the virtual photon flux of vacuum __ just exactly like what is launched into the surrounding gaseous air medium from the "plucked taut string" and perturbed body of a physical instrument. The EM wave in vacuum is a longitudinal wave directly analogous to a sound wave __ just as Nikola Tesla stated. [note 9]

The vacuum may be considered a scalar potential, in which case it has an internal biwave structure (Figure 3). Interference of two potentials __ i.e., the hidden interference (Figure 4) of their internal wave structures __ in fact already creates all EM fields and waves.

When the incoming longitudinal "biwave" from the vacuum strikes the atoms of the receiving antenna, each atom may be considered a dynamic assembly of multiple dipoles, where each dipole consists of one of the electrons in the electron shells and one of the positive charges in the nucleus. The receiving dipole in the interacting atom splits the two waves apart again (Figure 5). The negatively charged end of the dipole is time-forward, and the positively charged end is time-reversed.

Hence the separated normal-wave-half of the biwave interacts with the electron, to give again the familiar transverse "electron precession" wave that we detect with our "electron wiggle-detecting" instruments (Figure 6). This detected electron precession wave is what all our textbooks prescribe erroneously as the vacuum wave! The separated time-reversed-wave-half of the incoming vacuum wave is split off and interacts with the positive end of the receiving atomic dipole, in the time-reversed atomic nucleus, thus generating Newton's third law reaction force to provide the recoil of the nucleus. Present physics has ignored this second wave altogether, because of the serious error in the original derivation of the wave equation from plucked strings. Thus physics presently has absolutely no causative mechanism for Newton's reaction force. Instead, scientists just "mystically invoke the appearance of this magic force." Describing that something occurs, and naming its occurrence, does not constitute advancing a causative mechanism!

ILLUSTRATION LIST | NEXT PAGE

©copyright T.E.Bearden 1995

VT Page1

Comments may be sent to
the **Editor** of The Virtual Times

[6] E.g., see T.W. Barrett, "Tesla's Nonlinear Oscillator- Shuttle-Circuit (OSC) Theory," Annales de la Fondation Louis de Broglie, 16(1), 1991, p. 23-41. Barrett shows that a higher topology EM model (e.g., quaternions) allows shuttling and storage of potentials in circuits, and also allows additional EM functioning of a circuit that a conventional EM analysis cannot reveal. Tesla's actual patented circuits in fact exhibit this higher topology, when a quaternion EM analysis of them is performed. No orthodox vector/tensor analysis can show this.

[7] All the early experimenters seemed to assume the transverse string-type wave automatically for the vacuum medium. E.g., Faraday speculated that light and radiant heat might be transverse vibrations propagated along his "lines of force," from which the direct "plucked string" analogy can readily be seen. In short, he considered that his lines of force could be perturbed to vibrate laterally, just like a plucked string. See M. Faraday, "Thoughts of Ray-Vibrations," Philosophical Magazine, (3), vol. xxvii, 1846, p. 345. Maxwell also assumed the transverse EM wave in vacuum without question, as did Heaviside, Hertz, and Gibbs and as has almost every electrodynamicist since then.

[8] The worst is the assumption of infinitely rigid endposts holding the taut string, so that no movement of these endposts occurs. This further assumes that no induced movement of the body of the instrument occurs. The end result is to eliminate all of that wave that is produced in the body of the instrument, and retain only the transverse wave produced in the string. In the first place, this standard procedure has now become a total violation of Newton's third law, which among other things requires that forces be formed in oppositional pairs. So the standard method for the launch of a wave from an instrument is flawed. Specifically, the "transverse string wave" is falsified insolaf as its appearance in the surrounding medium. This is not the wave that actually exits the instrument and that is launched into the medium. This universal oversight on the part of mathematicians and physicists is a colossal joke upon them. Literally, when a physicist writes the transverse wave equation on the board, he has just discarded exactly half the physics. This means that, in his interactions, at the end there will suddenly appear this mysterious, mystical "equal and opposite reaction force" that is created by the erroneously ignored antiwave. So he has to piously invoke this reaction force "from the blue." Yet quantum field theory teaches us already that all mechanical and electromagnetic forces on a mass are generated by absorption and emission of virtual photons. Hence Newton's third law reaction force must also be so generated. This means that there must exist an equal number of virtual antiphotons interacting in the antiforce, as there was virtual photons interacting in the causative force. By symmetry there must also exist an equal and opposite wave, or antiwave, made of these same antiphotons. The actual disturbance that entered from the vacuum must therefore have consisted of both wave and antiwave. QED.


String slaps
air medium
WAVE IN STRING (TRANSVERSE)
Higher
degree of
freedom for
air medium
oscillation;
wave is
alternately
compressive
and rarefactive.
ANTIWAVE IN HOLDER
(Highly damped; not shown
to scale)
Body slaps
air medium

Figure 1. Air medium disturbances generated by plucked string.

Two waves are created, both slapping the air medium at the same time, but in opposite directions. A disturbed medium oscillates according to its own degrees of freedom. The air has more degrees of freedom than the string. A wave of compression and rarefaction is created in the air medium.

D-1-F 1

© 1993 T.E. Bearden


Modulations of virtual photon flux
ANTENNA
ELECTRON SHELLS
(DAMPED)
NUCLEI
(HIGHLY DAMPED)
e⁻
e⁻
e⁻
VACUUM
(UNDAMPED)
(UNDAMPED)

All EM and mechanical forces are due to virtual photon absorption and emission. The electron gas "slap" and the nuclei gas "slap" of the vacuum medium are equal in energy. Hence they inject equal numbers of virtual photons into the vacuum, creating equal and opposite vacuum disturbances. This gives a vacuum wave of alternating compression and rarefaction. This vacuum EM wave is similar to a sound wave, which is modeled longitudinally.

Figure 2. Launching an EM wave from a wire antenna.

D-1-F2

© T.E. BEARDEN 1994, 1996

[9] See Nikola Tesla, "Pioneer Radio Engineer Gives Views on Power," New York Herald Tribune, Sep. 11, 1932. Quoting: "...I showed that the universal medium is a gaseous body in which only longitudinal pulses can be propagated, involving alternating compressions and expansions similar to those produced by sound waves in the air. Thus, a wireless transmitter does not emit Hertz waves which are a myth, but sound waves in the ether, behaving in every respect like those in the air, except that, owing to the great elastic force and extremely small density of the medium, their speed is that of light." Today the QM vacuum has been theoretically and experimentally shown to consist of a "gas" of virtual particles, rather like Tesla stated. Tesla was also correct about the longitudinal EM wave in the vacuum. He was also correct in his statement that a fundamental charged particle can alter its charge, if one considers the massless charge ~ of charge q separately from the mass m of charge q. When the charge q is placed in a nonzero potential V, it follows that the new charge of the electron is simply (~+V).

Tables:


Scalar Potential ϕ
✱ ✱ ✱ ...ETC.
✱ ✱ ✱ ...ETC.
Wavepair #3
HARMONICS
F(t)
Wavepair #2
SUBHARMONICS
Wavepair #1
✱ ✱ ✱ ...ETC.
✱ ✱ ✱ ...ETC.
F(S)

Figure 3. Internal Wave Structure of the scalar potential.

A harmonic set if wavepairs, where in each wavepair the two waves superpose spatially, but travel in opposite directions. The two waves in each pair are true phase conjugates and time-reversals of each other. Thus they comprise a coupled wave and antiwave. The photons must also be coupled into photon/antiphoton pairs, by a strong application of the distortion correction theorem of nonlinear optics.

Each wavepair is a standing electrogravitational wave.

D-1-F3

© T.E. Bearden 1984, 1985


Note:
Positive energy: radiates.
Negative energy: energy sink.
Fixed energy: Trapped; does not radiate or absorb.
Interference Zone (Potential gradients)
Normal EM Energy: May be positive, or negative, or fixed
Hidden Bidirectional EM energy flow
Hidden Bidirectional EM energy flow
Scalar Potential Beams
Whittaker/Ziolkowski Transmitter Arrays
(8 to 20 harmonic wavepairs each)

Figure 4. Scalar potential interferometry provides action-at-a-distance. It already creates normal EM fields and waves.

D-1-F4

© 1994 T.E. Bearden

Tables:

MECHANISM FOR NEWTON'S THIRD LAW


GRAVITON
PHOTON
ANTIPHOTON
Dipolarity separates the photon and the antiphoton
e -
e -
Excitation or ionization
PHOTON
ANTIPHOTON
NUCLEUS RECOILS

NOTE: Graviton waves are bidirectional phase waves of photon/antiphoton coupling and uncoupling in the vacuum.

The atom is an assembly of dynamic dipoles.

A dipole splits the graviton into a photon and an antiphoton.
The photon interacts with the electron, producing the action.
The antiphoton interacts with the nucleus, producing the reaction.

Figure 5. Graviton interaction with matter produces the photon interaction and Newton's third law reaction.

D-1-F5

Tables:



Longitudinally restrained spinning electron inside the wire acts as gyro
dm$_e$/dt
LATERAL PRECESSION INSIDE THE WIRE
Poynting flow S (outside)
FIELD ENERGY DENSITY FLOW ESTABLISHES AN EQUIPOTENTIAL V
Poynting flow outside the wire
S
e⁻
SPIN
dϕ/dt
v ≈ c
dq/dt (inside)
dm$_e$ /dt
(WORK FLOW)
v < c
SPIN
S.
dϕ/dt
(outside the wire) loss-free Poynting energy flow
electron current direction
wire
dm$_e$ /dt
(inside the wire) "drift" current due to loads and losses
Jϕ
dm$_e$ /dt

Figure 6. Currents in and along a conductor, with electron precession.

D-1-F6

© 1993 T.E. Bearden

Further, if we should trick the time-reversed wave half into coming outside the atom instead of going inside to interact with the nucleus (Figure 7), then it follows that the nucleus would not recoil. In that case the interaction would appear to violate Newtonian third law reaction. Phase conjugate mirrors already do just exactly this when they emit a phase conjugate replica wave. They direct the antiwave outside and away from the atom instead of inwards into the nucleus. So they do not recoil, no matter how powerful a phase conjugate replica wave they emit.

Finally, we can also show that the EM wave in vacuum is longitudinal, by yet another approach. The electrons in the electron gas in a conductor are spinning, and they are severely constrained longitudinally to be able to move only very, very slowly down the wire. So when perturbed, they act as gyroscopes, and precess at right angles to the perturbing force. The fact that the gyroelectrons in a wire move radially almost entirely, and only "slip" down the wire very slowly with a "drift" velocity, already proves conclusively that the incoming vacuum disturbance was longitudinal. The precession of a gyro is at right angles to the perturbing force. Therefore rigorously the vacuum EM waves are longitudinal, because the gyroelectrons moved transversely. The present assumption of the transverse EM wave in vacuum contradicts the entire theory of gyroscopes! [note 10] There are many other errors in classical EM that we will point out in future articles; this should give the reader a flavor of what is in store for him in future articles.

So there are no truly satisfactory "experts" in any of the 14 fields. Yet there is still something to be said for having some years of experience in one or more of the areas. I have had the good fortune or misfortune, depending upon one's viewpoint, to be involved in various of those 14 activities for some 30 years or more, and am active in several of the areas now. My colleagues and I are particularly active in researching overunity electrical devices (see Figure 8), to include the effects of controlled chaotic oscillators, charge-blocking oscillators, and oscillators driven by in-shuttled (bridged) Poynting field energy density flow ExH. Parametric oscillation is known to have yielded overunity electrical machines and was fully reported by Russian researchers in the Russian and French technical journals in the mid 1930s. [note 11] We will further cite that little-known work in future articles. Also, we are working mightily upon true negative resistors (Figure 9), wherein the resistor scavenges some of the disorganized energy from the vacuum's energetic exchange with the charges in the system, organizes and collects it, and then outputs that collected energy flow into the external circuit. Such a resistor acts as a power source. Kron, perhaps the greatest of the electrical machinery scientists, is known to have produced such true negative resistors.

I have also proposed a theoretical explanation of the Priore device (Figure 10) in France which in laboratory animals demonstrated remarkable cures of terminal tumors, cured trypanosomias, reversed atheriosclerosis, and restored suppressed immune systems. The Priore work was not anecdotal, but was performed under rigorous scientific protocols, working under the auspices of renowned French scientists such as Courrier and Pautrizel. The work is properly reported in numerous papers in the French medical literature. [note 12] The results were certainly achieved, but neither Priore himself nor the scientists of the day could understand the mechanism involved. The deciphering of that causative technical mechanism utilized by the Priore group required 10 years of intense effort. The results have now been published in the journal Explore! and are there for anyone to read. [note 13]

ILLUSTRATION LIST | NEXT PAGE

©copyright T.E.Bearden 1995

VT Page 1

Comments may be sent to
the **Editor** of The Virtual Times

PHOTON INTERACTION WHEN ATOM PHASE CONJUGATES


PHOTON
ANTIPHOTON
pump wave
e⁻
Excitation or ionization
Photons
RETRACING EXACT PATH OF SIGNAL WAVE
Antiphotons
Antiphotons
Antiphotons
e⁻
SIGNAL WAVE PATH (GRAVITONS)
PHOTON
ANTIPHOTON
NUCLEUS DOES NOT RECOIL
pump wave
PHOTON
ANTIPHOTON

- Dipolarity of the atom separates photon and antiphoton.
- Photon interacts with electron.
- Pumped nonlinear atom acts as a pumped phase conjugate mirror. Directs the antiphoton back along the path taken by graviton.
- Antiphoton does not interact with nucleus. Thus there is no nuclear recoil force generated.
- Nucleus thus does not recoil.
- Not a violation of Newton's third law, once one understands the mechanism that generates third law reaction. In the absence of the generating mechanism, there is no third law recoil. In EM field theory, the "missing antiwave" has necessitated third law omission.

Figure 7. Emission of antiphoton; nucleus does not recoil.
Atom acts as a pumped phase conjugate mirror.

D-1-F7

© 1995 T.E. Bearden

[10] When Maxwell's theory was constructed, the electron had not yet been discovered, and so the dipolarity of the atom was unknown. An atom was regarded just as a "blob." Electricity in a conductor was regarded as a thin material fluid Maxwell's equations are in fact hydrodynamic equations. So the founders regarded the detection of induced motion in the electric fluid as induced translation, not induced precession. They had no idea of "spins" of particles of the fluid, nor of gyro precession of those particles. Instead, q was regarded just as a "piece of electric fluid," similar to a cubic centimeter of fluid.

A fundamental AC resonant principle for an overunity electrical power system


Room temperature superconductive section
Bridge
Swinger
AC Signal Source
(Optimize V; Minimize i)
i ~ 0
dq/dt Blocker
i = 0
$\frac{d\phi}{dt} \neq 0$
$i \neq 0$
$i \neq 0$
LOAD

NOTE: May also utilize a tuned LC oscillator on the secondary side of the transformer

Patent Pending

Figure 8. dq/dt-free driving a swinger by S-flow.

Poynting energy flow S with its accompanying potential V is shuttled from the source to a tuned LC oscillator in resonance at the driving frequency or slightly below. The LC oscillator is driven by S-flow and dV/dt flow alone. The swinger furnishes its own free electrons, which receive S and EMF from the bridge, thereby producing dq/dt.

D-1-F8

© T.E. Bearden 1993, 1994, 1995

[11] E.g., see L. Mandelstam [Mendel'shtam, L.I.], N. Papalexi, A. Andronov, S. Chaikin and A. Witt. (1935) "Report on Recent Research on Nonlinear Oscillations," Translation of "Expose Des Recherches Recentes Sur Les Oscillations Non Lineaires," Technical Physics of the USSR, Leningrad, Vol. 2, 1935, p. 81-134. NASA Translation Doc. TT F-12,678, Nov. 1969. Summarizes lengthy work at the Institute of Physics of the University of Moscow and several of the laboratories on the problem of self-powered, self- oscillating nonlinear oscillators. The paper reports significant work and progress in oscillations created by the oscillating system itself (self-oscillation) without participation of any external forces varying with time and without the expense of a constant source of energy (e.g., a storage battery). Such a system was shown to self-increase in an underdamped manner until system self-destruction. Adding a nonlinear load allowed the systems to stabilize its dynamic operation so that it powered a load under overunity conditions and did not self-destruct. Extensive additional references on this spectacularly successful overunity energy project are listed.


heating
i
NORMAL
RESISTOR
jϕ
+
BATTERY
−
heating

Figure 9a. Normal resistor receives ordered energy and scatters it.


cooling
i
NEGATIVE
RESISTOR
+
jϕ
V
−
cooling

Figure 9b. Negative resistor receives, concentrates, and reorders scattered energy.

Figure 9. Normal resistor versus a negative resistor.

D-1-F9 © T.E. Bearden 1993, 1996



Some 17 signals were fed into a rotating plasma, which added phase conjugates to them. This infolded 17 wavepairs, each pair a coupled wave/antiwave, thereby forming a scalar potential with an artificial Whittaker pump wave internal structure. This infolded pump wave complex was modulated onto a powerful, rippling magnetic field, guaranteeing penetration even into the atomic nuclei. A specific, amplified antiengine for the exact cellular disease state was generated, reversing the diseased cells back to a previous healthy state.

Figure 10. Priore's laboratory apparatus for cellular reversal.

D-1-F10

© T.E. BEARDEN 1993, 1995

[12] For citations and the exposition of our proposed explanation of the Priore mechanism, see T.E. Bearden, "Vacuum engines and Priore's methodology: The true science of energy-medicine." Part I, Explore!, 6(1), 1995, p. 66- 76, Part II, Explore!, 6(2), 1995, p. 50-62.

[13] Bearden, "Vacuum engines and...," ibid.

Presently my CTEC colleagues and I have filed three patent applications and a continuation, on various methods for overunity processes and apparatuses, room temperature superconductivity, Poynting generators, etc.

As an example, we took exactly the opposite approach to room temperature superconductivity as has been taken by all the orthodox researchers to date. What exactly is sought, after all, for superconductivity (SC) in a section of an electrical circuit? Well, one has some electrons on one side of that SC section that are transporting excess potential, as given by the Slepian vector J*. [note 14] What is desired is to get some electrons on the other side of the SC section that also are transporting the same amount of excess energy in the form of J*. You can do that in two ways: (1) you can flow the electron carriers through the SC section, carrying their J*, or (2) you can block the J and flow the * itself across as the Poynting flow S. [note 15] Nondivergent Poynting flow flows along an equipotential, which is just another way of saying that, if the S-flow does not diverge, it carries the same potential * along with it. Hence it carries the EMF right along with it as it flows without divergence.

Conventional approaches have all tried to shove the electron carriers through the SC lattice section. Doing that is like trying to fire a very slow bullet through several million rotating fans in a straight line. So cryogenics (to slow the fanblades to a crawl) and massive correlation of the electrons and of the electron-to-lattice interactions is necessary if one is to get the electrons through there without excess collisions that shake off some of the excess * from J*, as scattered photons (heat) or as a change of form of the energy (as in straining the dielectric of a capacitor to convert electrical energy to mechanical strain energy via the piezoelectric effect.)

Our approach is exactly the opposite (Figure 11 and Figure 12). Why not just *stop* the flow of excited electron carriers on one side of the SC section, and continue the nondiverging flow of the Poynting field energy density S across that section at room temperature? Then the cryogenics is not needed at all. After all, circuits already work that way anyhow __ except standard practice is to nullify the process by letting current be driven around the sourcing current loop and back through the back EMF of the primary source. A quantum well (or several other methods) can be used to trap the "sourcing" electrons in the conductor just prior to entering the SC section. The "receiving" electrons on the other side of the SC section, however, must be in their own dq/dt-isolated current loop.

ILLUSTRATION LIST | NEXT PAGE

©copyright T.E.Bearden 1995

Comments may be sent to
the **Editor** of The Virtual Times

[14] Briefly, the S-flow outside the wire will be flowing along essentially at the speed of light, at or with the same since S-flow without divergence is along an equipotential. Said another way, a nondiverging Poynting flow S exhibits a constant potential ~ along its streamlines. A tiny, tiny portion of the S-flow is intercepted by the sluggish electrons (which may be moving as dq/dt at 11 feet per hour, in a typical case), to form the Slepian vector J~. The J~ portion is just the minute fraction of the S-flow that is actually intercepted by the electron current and transported to the impedances, for releasing the excess ~ in the loads and losses. [Incidentally, this wee note resolves a century of controversy over exactly how EM energy flows in circuits. The orthodox literature abounds with discussions, differing positions, and debates and with errors.]

[15] Note that this also automatically involves a host of other types of controversial displacement currents, such as d~/dt, dV/dt, dE/dt, dP/dt, dD/dt, etc. The literature is thoroughly floundering as to exactly how all these currents are related, together with the Slepian vector J~ and the Poynting vector S, as well as the "normal" current dq/dt. We will be discussing the "master key" for these relationships in future articles.

Tables:



Note: EM texts err in showing the battery "gate" as the source of energy.

Figure 11. Poynting S-flow along a simple circuit.

From particle physics, any electric charge is a broken symmetry in the vacuum's virtual particle flux. Any dipole is thus two locally broken symmetries. Thus the dipole acts as a gate/source, driven by the fierce vacuum flux. So a dipole already "extracts" and gates EM energy flow, directly from the seething vacuum.

Every battery and generator is already a "free energy" source of extracted and gated EM energy from the vacuum.

D-1-F11

© T.E. Bearden 1994


VACUUM FLUX
S_1 flow
S_3 net flow
S_2 flow
Net Potential Difference Between Flows
dq/dt > 0
J ϕ > 0
emf
back emf
SOURCE
J ϕ > 0
S-flow
V drop
S-flow
S-flow
Scattered photons
(Scattered Poynting S-flows)

Figure 12a. Normal current flow; Jϕ is the electron transport of energy, while S is the speed-of-light Poynting energy flow.


VACUUM FLUX
S_1 flow
S_3 net flow
S_2 flow
Net Potential Difference Between Flows
dq/dt = 0
Jϕ = 0
emf
back emf
SOURCE
Hidden bidirectional EM waves
V (No drop)
Ordered hidden photon/antiphoton pairs (gravitons)
(Ordered Poynting S-flows)

Figure 12b. In a conductor with dq/dt blocked; S-flow and hidden Whittaker-wave flow continue.

Figure 12. Overt and covert field energy density flows.

D-1-F12

© 1994, 1995 T.E. Bearden

Normal sources do not furnish electrons and current to a circuit anyway. Sources just furnish Poynting flow S and EMF. [note 16] In the receiving current loop, the EMF appears automatically once the S-flow flows in and is "locked on to" by the receiving electrons. Given q**, you will immediately have J* if the electrons are free to move in the conducting circuit (see Figure 13). Further, you have eliminated all the loss terms from the standard Poynting equation for energy losses. So all the energy flow S just flows across the SC section, without any current or Cooper pairs flowing through that SC section. The SC section has become a "bridge" which (1) strips off the Poynting field energy density flow S from the electron current dq/dt on the sourcing side of the SC/bridge section, by simply reducing the dq/dt to zero; and (2) continues to pass the S-flow across the dq/dt-blocked SC/bridge section to the other side (Figure 14). The excess S-flow (and EMF) pours into the receiving dq/dt-isolated current loop, exciting the electrons therein to produce dq/dt and J*. *Any closed current loop is self-powered, once it receives S and EMF. It furnishes its own electrons; it only requires excess energy and EMF*. [note 17]

So our approach gives room temperature superconductivity in a very straightforward manner, once you discover how to block the current dq/dt in a conductor. Blocking it in an insulator is not sufficient, because that drops the potential and stops the S-flow and the equipotential * (the EMF). However, a degenerate semiconductor such as the Fogal chip can be used, as can several other processes for blocking dq/dt in a conductor. We will discuss these in a future article.

Another advantage of this approach to room temperature superconductivity is that now one can also have permissible overunity coefficient of performance. Now the load can be placed in its own S-receiving, isolated current loop. With the sourcing current loop furnishing only S and not dq/dt, the load is still powered normally in its own closed dq/dt current loop, but none of the load current is passed back through the back EMF of the primary source in the sourcing circuit.

This principle -- that at least a substantial portion of the load current must not pass back through the primary source -- is the primary principle required for a permissible overunity electrical machine (Figure 15). A permissible overunity electrical machine is one which produces more power in the load than you have to put into the machine to run it.

ILLUSTRATION LIST | NEXT PAGE

©copyright T.E.Bearden 1995

Comments may be sent to
the **Editor** of The Virtual Times

[16] E.g., see Robert L. Shrader, Electronic Communication, Sixth Edn., MacMillan/McGraw-Hill, New York, NY, 1991. (1993 Imprint). Quoting from p. 6: "A source of electric energy does not increase the number of ~ree electrons in a circuit; it merely produces a concerted pressure on any aimlessly moving electrons."


S' = f(dE/dt, dH/dt)
S = (E x H)
S
+
SOURCE
f(V^2)
$\frac{dE_L}{dt}$
+V R
E r
$\frac{dV}{dt} = \frac{d\phi}{dt} = -\frac{dE_B}{dt}$
positive half of a cycle
0
Reference
NOTE:
Use upper pair of conductors for (+) half-cycle
Use lower pair of conductors for (-) half-cycle
-V R
H t
negative half of a cycle
S
–
SOURCE
f(-V) 2
$\frac{dE_L}{dt}$
S
S'

Figure 13. Poynting vector currents S and S' versus massless displacement currents.

D-1-F13

© 1995 T.E. Bearden


S-flow and EMF flow
V>>0
source
i ≈ 0
Closed Current
Loop A
dQ/dt
BLOCKER
(Conductor)
V>>0
i>>0
Closed Current
Loop B
LOAD
BRIDGE
(Automatically Room Temperature Superconducting)

Figure 14. Bridging to enable room temperature superconductivity.

D-1-F 14

© 1995 T.E. Bearden

[17] My own approach has been, if that's all that the circuits require from our primary power source, then let's simply accept that directly from the source without performing any work in the source. Iœ you do it this way, the source is never dissipated, but will last indefinitely. Sources furnish flowing field energy density, not "energy" per se. If you only demand S-flow, you can have all you wish from a source, without exhausting your source. The trick is to find how to steadily dissipate some of this "artesian well" of flowing S to drive electrons through the load, but without driving electrons back through the back EMF of the source.

Tables:


+
DC
SOURCE
—
+V
AC
GENERATOR
AND
CONTROLLER
+V
CHARGE
BARRIER
SEMI-
CON-
DUCTOR
TRANS-
FORMER
LOAD
+
CHARGE
CIRCUIT
DISCHARGE
CIRCUIT

Patent Pending

* NOTE:

DISCHARGE CIRCUIT AND LOAD GROUND
MUST BE ISOLATED FROM THE
CHARGE CIRCUIT GROUND.
FEEDBACK LOOP MUST BE RIGIDLY CLAMPED AND LIMITED.

Figure 15. Use of Fogal semiconductor for overunity (closed system).

D-1-F15

© 1993, 1995 T.E. Bearden

Obviously, the laws of physics and thermodynamics require such an overunity machine to be an open system that extracts and utilizes excess energy from an external source. In the case outlined, we extract the excess energy directly from the vacuum in the form of S-flow; essentially we convert our primary source to a Poynting generator rather than a "power" (energy flow loss rate) generator. The resulting overunity machine accomplishes both room temperature superconductivity and also overunity coefficient of performance (Figure 16). It does not violate the conservation laws of physics. It does not violate the second law of thermodynamics because it is an open system receiving and utilizing excess energy from the vacuum, and the second law need not apply to such systems. [note 18]

You see, all power systems are already free energy density flow sourcing systems, if we but use them correctly. Every dipole is a "gating device" for extracting excess field energy density flow from the violent bidirectional flux exchange between the vacuum and each end of the dipole. [note 19] [note 20] When we attach "conducting leads" to a dipolar source, as in the simple two-wire circuit, all we are doing with the conductors is providing waveguides for the extracted S-flows from the vacuum to flow along (it flows outside the conductors) without loss. In effect, each lead is simply extending the pole (i.e., the terminal) to which it is connected.

My associates and I are also working on several other inventions at present, including two more patent applications to be filed in the near future. One of those is in the field of overunity power systems, while the other is in an entirely different, highly proprietary nuclear effort. I will address all these areas in future columns, and those columns will have real "meat" in them.

Present "big science" proclaims that overunity electrical machines are impossible. The reader should understand that the U.S. Patent and Trademarks Office is never going to grant a patent for an overunity electrical machine unless the machine is independently tested and replicated, and unless it is certified by scientists of impeccable credentials. This is as it should be. Legitimate free energy researchers accept that dictum. Eventually the stuff has to work on the bench in order to be validated. On the other hand, free energy researchers also point out that one must not demand of us the next 100 years of national research by a hundred major laboratories immediately! This is still a shoestring operation, because all conventional sources of research funds are denied to the serious overunity researcher (with the single exception of occasional personal funding of a researcher by a private individual). In other words, we demand at least the same kind of consideration that the orthodox nuclear fusion community has enjoyed. Billions of dollars have been poured into that sinkhole, and not a single controlled fusion power unit is working anywhere in the world after decades of work at enormous expense to the taxpayers.

So we overunity researchers deserve at least a decade or two of our own, to try to accomplish overunity electrical system development. We also painfully point out that "Big Science" will not fund a single overunity researcher, for specific overunity purpose, no matter what his credentials or capability. In fact, "Big Science" is part of the problem, because it fervently seeks to prevent any legitimate research in overunity. To carry out its suppression campaign. it resorts to vilification, character assassination, libel, and slander of the overunity researchers themselves __ again, regardless of their qualifications or legitimate scientific procedures. [note 13]

ILLUSTRATION LIST | NEXT PAGE

©copyright T.E.Bearden 1995

VT Page1

Comments may be sent to
the **Editor** of The Virtual Times

Tables:


B (test
charge)
potential
potential
force on B due
to field of A
A
Fixed
Charge
+
C
∞
test charge B forced
in to point C

Figure 16a. Magnitude of the scalar potential is determined by work required to push in a unit charge from infinity; e.g., against a repelling like charge. If test charge is released, work will be performed upon it to translate it back toward infinity

Figure 16a. Process for overunity coefficient of performance.

D-1-F16A

© T.E. Bearden, 1993, 1994, 1995

Tables:


switch
B (test charge)
force on B due to field of A, only on outgoing phase
a
(+)
A
C
∞
+
b
source potential
S
−
spherical conducting shell
potential
Test charge B drifted in to point C, with little resistance

Assumptions: Capacitance of A very small; charge B large, power-free switching

Switch potential off, drift in test charge B, switch potential back on. Can now get free work from repelled test charge B. Get much more free work if A is at a high potential, and charge B is large.

Figure 16 b. Demonstration of overunity efficiency.

D-1-F16B

© T.E. Bearden, 1993, 1994, 1995



Ideally, switching the potential, rather than flowing charges, requires only minuscule overhead energy dissipation

Figure 16c. Potential to which test charge is exposed.

D-1-F16C

© T.E. Bearden, 1993, 1994, 1995

[18] The system does comply with the nonlinear thermodynamics of a system far from equilibrium. E.g., Prigogine received the Nobel Prize for significantly developing this new field. For a detailed technical presentation of nonlinear thermodynamics of a system far from thermodynamic equilibrium, see G. Nicolis and I. Prigogine, Explorinq Complexity, Piper, Munich, 1987. Such systems can exhibit negentropy, self-organization, and other effects outside the confines of classical thermodynamics. Since local symmetry is broken, they can also permissibly exhibit overunity coefficient of performance.

---

[19] Each end 0œ a dipole has its own potential (with respect to the local vacuum), which differs from the potential of the surrounding ambient vacuum. For each of these "end-potentials," one can mathematically decompose that end-potential into a hidden bidirectional set of harmonic wavepairs in harmonic sequence. Each wavepair consists of the wave and its phase conjugate. For the proof, see E. T. Whittaker, "On the Partial Differential Equations of Mathematical Physics," Mathematische Annglen, Vol. 57, 1903, p. 333-355. Since one of the dipole potentials exceeds the local vacuum potential and the other dipole potential is lower than the local vacuum potential, the two bidirectional EM wave flows are at or "carry" different equipotentials. This is the generatrix for the automatic dual œ1ow of energy from the vacuum through the dipolar power source and out along the two leads of the "transmission line" conducting the S-flow to the components of the circuit for powering the loads. So as can be seen, rigorously every dipole is already a "free energy source" if we learn how to properly use it. The energy will flow forever, if we do not allow the destruction of the sourcing dipole.

[20] See also E.T. Whittaker, "On an Expression of the Electromagnetic Field Due to Electrons by Means of Two Scalar Potential Functions," Proceedinqs of the London Mathematical Society, Series 2, Vol. 1, 1904, p. 367-372. Here Whittaker shows that the fields of classical electromagnetics can be replaced by scalar potential interferometry of two potentials. Our own comment is to note that by Whittaker 1903, we can with a little difficulty make artificial potentials with deliberate substructures. We can then interfere those potentials (actually, interfere their hidden multiwave structures) even at a distance, to create new EM fields. Or we can dissolve EM fields that exist at a distance, simply by constructing the correct negative EM fields by distant scalar interferometry. My point is that, when we utilize the "inner" electromagnetics inside the potential, we are employing a vastly more powerful electromagnetics of a new kind, which includes and extends the present inadequate EM theory.

Indeed, orthodoxy has a black record with respect to energy. When Mayer advanced the conservation of energy law, orthodoxy hounded him unmercifully. He was universally ridiculed as the very epitome of a fool. He lost his job and suffered a nervous breakdown. Then years later toward the end of his life, scientists came to accept the conservation of energy as a most useful tool that dramatically simplified much of their analyses. So then science began to laud Mayer. There are a thousand other such examples; suffice it to say that "big science" is a bureaucracy and a "bell-shaped distribution curve" just like any other large group of people. Some scientists are near-angels. Others are near-devils. The vast majority are neither, but are just ordinary persons doing a special kind of job. In the scientific bureaucracy, however, the manipulative scientists scurry, slash, and manipulate their way toward the top. So the leadership of any big bureaucracy __ including the scientific bureaucracy __ is always rife with such near-scalawags and power-hungry individuals. Scientists are not exceptions to the same human weaknesses that we all evidence. If you really want to see jealousy, backbiting, and fierce "back-room dealing" and power-struggling, just get into a university research environment! But because the "power merchants" of any bureaucracy always fiercely resist any challenge to their position or superiority, big science has always fiercely resisted anything truly revolutionary. And today they also enlist the power of the state to enforce their dictums. We will devote one of our future columns to pointing out some glaring examples of persecution of independent researchers by big science. It is an area that all unorthodox researchers should be well-aware of. The world of science does not run by sweet reason and lofty ideals; that is just the dogma. It runs strictly by "who's going to be the big monkey," just like everything else. Primate dominance is still a dictum of the functioning of all bureaucratic human systems.

The free energy researchers are not working on the so-called "perpetual motion machine," where a closed system is erroneously stated to produce more output than must be put into it to operate it. That old saw is actually a red herring that dogmatic scientists use to vilify free energy researchers. It is a lie that they have also successfully sold to the U.S. Patent and Trademarks Office. Anyone with a modicum of knowledge of modern physics already knows that there does not exist a single closed system in the universe, anywhere. In particular, every physical system is continuously "open" to the violent exchange of energy with the surrounding vacuum. It's just that most systems are in local equilibrium in these flow exchanges, except for minuscule gating accomplished for such things as the Lamb shift, etc.

By analogy it's something like this. The free energy researcher is standing by the banks of a mighty, rushing river with breathtaking falls, turbulent areas, etc. Big Science is begrudgingly admitting that, yes, there is a river there, but it is an insane delusion to think that you can tap that energy. The free energy researcher is saying that, well, if I can build a gating sluice a little distance upstream, perhaps I can divert a small portion of the river's flow downstream to my waterwheel, and power my mill. The orthodox scientist then vilifies the free energy researcher for even having such a heretical thought. In fact, says the orthodox researcher, any fool can see that the laws of nature force the river's flow to stay firmly in its banks, because it is a closed system, and Moses brought that law down off the mountain with him on a special stone tablet. Then he adds all the other smug remarks such as, "If it could be done, then we at MIT and Harvard and Caltech would already have done it!" So until the orthodox scientist develops a little less dogma and a little more common sense, and learns the difference between a scientific discussion and a dogfight, the free energy researcher can hardly communicate with him.

ILLUSTRATION LIST | NEXT PAGE

©copyright T.E.Bearden 1995

VT Page1

Comments may be sent to
the **Editor** of The Virtual Times

The goal of the legitimate free energy researcher is to find a way to break the local equilibrium of this universal energy exchange, and gate a tiny bit of it up into the external circuit as excess electrical energy (Figure 17). Then he must collect the excess energy, and shuttle it from the "gating and collecting circuit" over to a dq/dt-closed current loop containing the load. He must also prevent the load current, or most of it, from passing back through the primary source against its back EMF, because if it does that, he will destroy the separation of charges in the dipolar source, killing the dipole and extinguishing the "excess energy gating." In other words he must find a way to process and transport the energy flow across dq/dt-blocked bridges between the source's closed dq/dt-current loop and the load's closed dq/dt-current loop. Ruthlessly it is an energy transport S-flow problem, not a J* energy transport problem. If he uses J* in his sourcing current loop, he automatically drives the current dq/dt back through the back EMF of his source and kills it. If he does not drive dq/dt back through the source, the source will furnish S-flow for an indefinite period! Every battery and generator we have ever built is already a "free energy" machine in that it already involves broken local symmetry in the vacuum energy exchange. We have just not realized how to use our power sources purely as Poynting S-flow sources.

So we must treat an electrical system as an open system with broken local symmetry (Table 3) in the vacuum flux exchange, so that the system extracts (gates) excess energy from an external source. In this case the source is the system's flux exchange with the vacuum. This approach is no more mysterious or bizarre than putting a waterwheel in a river, or a windmill in a wind, or a bank of solar cells out in the sunshine. The universal "free source of energy" that the overunity researcher seeks to tap is the violent exchange of virtual photons between the electrical charges of the system and the surrounding quantum mechanical vacuum (Figure 18). In quantum physics this powerful, energetic exchange of the vacuum with electrical matter is now proven both experimentally and theoretically. It is already accepted in quantum physics that the vacuum is filled with electromagnetic energy. The researcher doesn't have to prove it anymore; he just has to find out how to properly use it. The artesian well is already there; we just have to learn how to collect and use the flowing water without dynamiting the well!

The remaining objection orthodox scientists usually raise against the notion of extracting vacuum energy has been that "thermodynamics doesn't permit it." However, Cole and Puthoff have rigorously shown that, on the contrary, the theory of thermodynamics does not prohibit the vacuum's energy being extracted and used to produce heat, light, and power. [note 22] So the validity of that final objection has now vanished.

ILLUSTRATION LIST | NEXT PAGE

©copyright T.E.Bearden 1995

Comments may be sent to
the **Editor** of The Virtual Times

Open system receiving excess energy from an external source


SOURCE LOOP
DIPOLE
PLUS
EXTENSION
LINES
● POTENTIAL
● TWO S-FLOWS
● TWO LOCAL
SPACETIME
CURVATURES
BROKEN
SYMMETRY,
THUS
FREE-FLOWING
FIELD ENERGY
BRIDGE
● BLOCK dq/dt
● PASS VOLTAGE
● PASS S-FLOW
Optimize S-flow and voltage
SURROUNDING
VACUUM
LOAD LOOP
LOAD
● dq/dt FLOW
● DROP EXCESS
ϕ IN LOAD
TRANSPORT
ENERGY
● dq/dt FLOW
● Jϕ FLOW
COLLECT
● S-FLOW, EMF
● ON CONDUCTION
ELECTRONS
AS Jϕ
Optimize current for voltage available

Figure 17. Operation of an overunity electrical power system.

D-1-F 17

© 1992 T.E. Bearden



Table 3: Asymmetry and modern physics.

Per T.D. Lee, Particle Physics and
Introduction to Field Theory,
Harwood Academic Publishers,
New York, 1981, p. 378-390.

SYMMETRY AND MODERN PHYSICS

- Missing symmetry of matter
- Symmetry only of mass and vacuum
- Vacuum excitation
- Vacuum structures
- Spontaneous symmetry breaking
- Interaction between matter and vacuum
- Possibility of vacuum engineering

SOME PROVEN ASYMMETRIES

- Positive and negative signs of electric charge
- Time reversal
- Right/left handedness

STRONG LOCAL ASYMMETRY

- Properties of object may differ appreciably for:
  - Different observers
  - Different detecting means
  - One time to another
  - One position to another

D-1-T3

© T.E. BEARDEN 1993, 1995

STRONG LOCAL ASYMMETRY (CONT'D)

- Local spacetime is curved
- Lorentz invariance of vacuum violated
- May be local sink or source
- EM gravitational/inertial effects
- Translation between virtual and observable
- Electrogravitational solitons
- Action at a distance
- Transmutation effects may exist
- Scalar/pseudoscalar field translation

WHEN SYMMETRY IS VIOLATED

- A "non-observable" turns out to be an observable
- An invariance is broken
- A conservation law or selection rule is broken

COMMENTS:

- A virtual object becomes an observable object
- Local spacetime becomes curved, at least to some potential involving that object

A Charged Particle Is a Coupled System


VACUUM CHARGE
ϕ_q
MASS
m_q
$q = — \phi_q \times m_q$
Note: X is a coupling operator
virtual photon flux exchange

Figure 18. An electric charge q is a broken symmetry. It continuously and violently exchanges energy with the vacuum.

D-1-F 18

© 1994 T.E. Bearden

[22] Cole, Daniel C. and Harold E. Putboll. (1993) "Extracting Energy and Heat from the Vacuum," Physical Review E, 48(2), Aug. 1993, p. 1562-1565.

And there is mind-numbing energy density there in the vacuum, waiting to be extracted. The well-known Lamb shift, e.g., in a single hydrogen atom is due to that vacuum exchange. [note 23] Interestingly, the calculated energy density of the exchange causing the Lamb shift is greater than the surface energy density of the sun. Different physicists have made various theoretical estimates of the energy density of this seething vacuum. A conservative ballpark figure is something on the order of 1090 grams per cubic centimeter, expressed in mass units.

It has also been my good fortune to know and work closely with several other free energy researchers. I was a colleague of Floyd ("Sparky") Sweet (recently deceased) for about seven years; Sparky held a Master's degree in EE from MIT and had years of experience with General Electric and other firms. He was a highly skilled researcher who invented the solid state vacuum triode amplifier (Figure 19), a unit which produced 500 watts of output and a coefficient of performance of 1,500,000. I personally tested the machine, activated the magnets on one occasion, and understand how it all worked. [note 24] The paper [note 25] I co-authored in 1991 with Floyd is still the only paper in the orthodox engineering literature that reports (a) successful overunity functioning of a solid state magnetic device, and (b) a successful antigravity experiment on the laboratory bench, reducing the weight of an object by 90%. [note 26]

We stress again that a legitimate overunity electrical machine must be an open system, receiving excess electrical energy from the surrounding vacuum. As such, it must operate in a higher topology than normal electrical machines (Figure 20).

My good friend Frank Golden has long been a close colleague. Years ago Frank developed a motor that produced overunity efficiency, but then to our astonishment we found (courtesy of Bill Tiller, [note 27] with whom we were working at the time) that its operation depended upon a 5-year-long conditioning (structuring) of the local ambient potential in order to work. Previously we had been entirely unaware that one can sometimes condition the local vacuum and the local matter in the area with a particular dynamic form. Given the local conditioning, a motor with that form will then work in that vicinity, but not necessarily elsewhere at an appreciable distance away. We now understand the mechanism for such "conditioning of the vacuum." We also now know what to do if an overunity machine is actually a machine of that type (many of them are not). In other words, we know how to convert it to a machine that will work anywhere, anytime. We will be addressing such little-known things in future articles.

ILLUSTRATION LIST | NEXT PAGE

©copyright T.E.Bearden 1995

VT Page1

Comments may be sent to
the **Editor** of The Virtual Times

[23] Lamb, W.E. Jr. and R.C. Retherford. "Fine structure of the hydrogen atom by a microwave method." Physical Review, Vol. 72, 1947, p. 241-243. Lamb received the Nobel prize for this work.

Tables:


STRUCTURED IMMEDIATE VACUUM
ACTIVATED NONLINEAR NUCLEUS
EM WAVE COUPLED FROM/TO ELECTRON
RESONANCE
PHASE CONJUGATE WAVE
SIGNAL WAVE
SURROUNDING VACUUM
EXTERNAL CIRCUIT
FIELD OF BARIUM FERRITE MAGNET
EXTERNAL SIGNAL WAVE INPUT
FOR "OPEN LOOP" SYSTEM OPERATION
LOAD
POSITIVE FEEDBACK
CLAMPED STABILIZER
SELF-REPLENISHED SIGNAL INPUT
FOR "CLOSED LOOP" SYSTEM OPERATION

Figure 19. Block diagram of the Sweet Vacuum Triode Amplifier.

Adding positive feedback circuit enables self-oscillation.

D-1-F 19

© T.E. Bearden 1991, 1995

[24] Unfortunately Sweet made conflicting agreements with multiple backers, resulting in a most thorough legal foul- up. It appears that nothing can ever be done with this machine, because its status is a legal nightmare.

[25] Floyd Sweet and T. E. Bearden, "Utilizing Scalar Electromagnetics to Tap Vacuum Energy," Proceedings of the 26th Intersociety Energy Conversion Engineerinq Conference (IECEC '91), Boston, Massachusetts, 1991, p. 370-375. Paper also distributed over Internet.

[26] The unit was specially rigged and "pushed" to 1,000 watts output to perform the antigravity experiment.

Tables:

Example: Conservation in 2D versus 3D topologies.


3-D CONSERVATION
(2-D CONSERVATION VIOLATED)
2-D CONSERVATION

Figure 20. Increasing the dynamic topology allows lower topology conservation laws to be violated. Conservation now applies in the higher topology, but not necessarily in the lower. The lower topology system is now an open system and may seemingly act as a source or sink.

D-1-20

© T.E. Bearden 1993, 1995

[27] Tiller was already familiar with the fact that devices that function by more subtle energy often require special conditioning of the vacuum spacetime. He expressed it as "an archetype must first be created for the machine to function efficiently." Tiller had previously experimented with such an effect for several years.

John Bedini is also a close friend and colleague; John built several experimental motors (both electrical and magnetic) in the overunity area, and performed successful trans-mutation experiments. John is a recognized genius in high-end sound amplifier development. Many audiophiles worldwide still swear that the Bedini amplifier is the best and sweetest-sounding audio amplifier ever built. One of John's battery-powered electrical motors (Figure 21), for example, ran continuously off its battery for about five years, and kept the battery charged. When you realize that such a small electric motor is only about 35% efficient, then you realize that about 65% of the energy flowing out of the battery was being dissipated in the motor as heat, core losses, etc. So the unit was continuously performing work for that five years. [note 28] The 1/8 hp motor represented a load in which the continuous rate of work being done (the rate of energy dissipation) was about 0.08 hp. We will have more to say on this motor and its technical process in a future article.

Bill Fogal is a close colleague; Bill has patented the world's first dq/dt-blocking semiconductor, [note 29] which partially blocks the normal current while continuing to pass the flow of voltage (Table 4). I have written a proprietary technical explanation of the Fogal semiconductor, which utilizes an extremely little-known feature called the "overpotential." The overpotential part of the theory is experimentally proven and theoretically explained in an obscure part of electrochemistry, by a few chemists who specialize in electrode effects. J. O'M. Bockris is probably the leading world expert in overpotential theory; he authored the textbook on it. [note 30]

One of the latest overunity developments is the magnetic resonance amplifier (MRA) developed by Joel McLain and Norm Wooten (Figure 22). Earlier testing disputed the overunity functioning. More recent testing at several well-known laboratories has resulted in the instrumental measurements clearly showing overunity. While the test institute scientists themselves may be willing to attest to overunity results of their testing, none of the corporate heads will allow it. I have personally stated that the MRA is capable of overunity. Our own measurements had to be discarded because we did not have the proper instruments available. E.g., all our oscilloscopes were "hard grounded" to building ground, and we needed to make "floating differential ground" measurements in order to settle things once and for all. McLain and Wooten have filed for a patent, and multiple tests with excellent equipment have indeed indicated overunity. What happens next remains to be seen. I suspect that the two inventors may simply accept foreign capital investment and go offshore.

ILLUSTRATION LIST | NEXT PAGE

©copyright T.E.Bearden 1995

VT Page1

Comments may be sent to
the **Editor** of The Virtual Times

Tables:

WARNING: Highly dangerous operation. Pulsed battery outgasses hydrogen gas and explosion is possible.



Open system using higher topology extraction of excess vacuum energy. Uses sluggish reversal and recoil time of lead ion onrushing current versus rapid backlash of amplified voltage discharge from a magneto ignition coil, to force the battery to act as an excess S-flow collector during the ion-current charging half-cycle. Thus the inefficient motor is continuously powered and the battery is continually recharged.

Figure 21. Bedini's battery-powered, back-popping electric motor.

D-1-21

© T.E. Bearden 1993, 1995

[28] We strongly emphasize that there is no conservation of work law in physics! It is the overall energy of the universe that must be conserved, not work. More rigorously, the flow of energy must be conserved. But from a free flow of energy, you can continuously extract a little and dissipate it as work, without cutting off the main flow and without violating any of the laws of physics. If this were not so, then waterwheels, windmills, and solar cells would not work. In fact, you can even do better than that. The basic energy conservation law is this: Energy can neither be created nor destroyed. So even when you "use" (i.e., dissipate or scatter) the energy, it is still there. It is only the hierarchical ordering of the photons that constitutes entropy. Each individual photon is perfectly ordered and still contains all its energy. By retroreflection, you can even cause those disordered photons to gather back in your system into perfect order once again and then you can scatter them again to do some more work. You can use the same energy over and over again! The perfect retroreflection is more easily accomplished by phase conjugate reflection. For a vivid example of just such retroreflection of previously scattered EM energy to restore the former order, see David M. Pepper, "Applications of Optical Phase Conjugation," Scientific American, Vol. 254, No. 1, Jan. 1986, p. 74-83. See particularly the striking photographic demonstration of time reversal of disorder on p. 75.

[29] William Jay Fogal, "High gain, low distortion, faster switching transistor." U.S. Patent No. 5,196,809, Mar. 23, 1993. Also William J. Fogal, "High Gain, Low Distortion, Faster Switching Transistor." U.S. Patent No. 5,430,413, July 4, 1995.



Table 4. Fogal's Semiconductor.

FOGAL'S CHARGED BARRIER SEMICONDUCTOR

- BLOCKS ELECTRON CURRENT FLOW dq/dt
  - AS CAPACITOR CHARGES, ELECTRONS IN EMITTER JUNCTION ATTRACTED TO PLATE
  - CHARGING PLATE PRODUCES HIGH BARRIER VIA PROPRIETARY MECHANISM
  - AC CONDUCTION ELECTRONS CANNOT PENETRATE BARRIER
  - AC POYNTING FLOW S, $d\phi/dT$, dE/dt PASS THROUGH BARRIER
- PASSES POYNTING FLOW $S = E \times H$; dE/dt
- SEMICONDUCTOR BECOMES "ENERGY PIPE"
- WITH dQ/dt BLOCKED, FLOW OF $S = E \times H$ IS NON-DIVERGENT AND WITHOUT LOSSES
- FOGAL CHIP UTILIZES $S = E \times H$ FLOW TO TRANSPORT ENERGY, RATHER THAN $J\phi$

D-1-T4

© 1994, 1995 T.E. BEARDEN

[30] In a correspondence with Bockris lasting several years, he had graciously furnished me with material on the overpotential, which is how I found out about this esoteric area. Bockris is well-known as a leading scientist on the chemistry of hydrogen, and also as one of the leading scientists in the rapidly developing field of cold fusion. He is a marvelous scientist, and one day his largely unsung work with the overpotential will revolutionize the entire electronics industry.

Tables:


Highly nonlinear oscillator
Nonlinear capacitor
(barium titanate
piezoelectric)
1:1 transformer
DC Output
BRIDGE
Load
20-40 kHz
CAUTION:
Circuit acts as a
voltage amplifier and
high voltages are present.
Core of transformer
is a barium ferrite
permanent magnet
Note: Linear LC resonance theory
does not apply. Oscillation
is highly nonlinear, so nonlinear
oscillator theory must be used.

Figure 22. Schema for the magnetic resonance amplifier (MRA).

D-1-F22

© T.E. BEARDEN 1994, 1995

Howard Johnson is also a respected colleague, whom I very much admire. (See Figure 23). Howard has continued to work quietly and patiently upon his patented permanent magnet motor, [note 31] including patenting various magnetic gates, etc. that are necessary to make such a motor work in a rotary configuration. [note 32] Howard employs a two-particle theory of magnetism; i.e., each magnetic flux line is envisioned as having a particle traveling from the north pole to the south pole, and also a particle traveling from the south pole to the north pole. The particles are spinning; the forward-time particle spins in one direction, and the antiparticle spins in the other direction. Howard then slightly separates the two particle flows. [note 33] In other words, Johnson splits the flux lines themselves, into two different pieces. When so separated, the component lines are now curls, so their paths curve. The paths of the two "curl particles" are different; one curls in one direction and the other curls in the opposite direction. Further, a predominance of one form of curl particle gives a "time-forward" aspect, while a predominance of the other form of curl particle gives a "time-reversed" aspect. Johnson is thus able to employ a deeper kind of magnetism than the textbooks presently contain. He demonstrates that a "spin-altered" magnetic assembly exhibiting (to a compass or other such detector) a north polarity can attract another unaltered magnetic assembly exhibiting a north polarity. In short, he can make a north pole attract a north pole. We will give you further insight into Johnson's two-particle theory in a future article. [note 34] We will also explain how and why the physicists missed that antiparticle in the magnetic field's flux lines, and thereby failed to advance the theory of magnetism to a deeper level. Make no mistake, one day when the new theory is done, Johnson may well be awarded a Nobel Prize for his epochal discovery of a deeper structure of magnetism.

Bits and pieces of the new science approach are just now beginning to spill into a few conventional journals and symposia. For some time a few of the rebels spearheading this new science have been doing something that the University scientists should have been doing all along. The rebels have been meticulously examining the concepts, postulates, and definitions that the present scientific models are founded upon, to reveal serious foundations errors. Corrections for some of these errors have been discovered and made. [note 35] Others are still problems yet to be resolved. Yet slow progress is being made, and a "flip-over" of the old science is likely to occur within the next decade if not sooner. By then the new concepts will have become "solid" enough to allow producing an engineering mathematical model. Also the supporting experiments will have become solid enough to justify the new concepts and the model.

ILLUSTRATION LIST | NEXT PAGE

©copyright T.E.Bearden 1995

VT Page1

Comments may be sent to
the **Editor** of The Virtual Times


N poles partially attract during approach phase. Fully repel during exit phase.
+T
+T
S
N*
N
S
STATOR
-T
ROTOR
+T
Partially time-reversed (phase conjugated) field

Implications of a time-reversed field area
on only one side of a magnetic pole
in a permanent magnet motor

Figure 23. Schema for Johnson's permanent magnet motor.

T91H-403

© T.E. BEARDEN 1991, 1993, 1995

[31] Howard Johnson, "Permanent Magnet Motor." U.S. Patent No. 4,151,431. Apr. 24, 1979.

[[32] I personally saw and closely examined one demonstration rotary Johnson permanent magnet motor some years ago, and toyed with it for about one hour. It would definitely self- rotate as long as you wished to permit it to turn. It was not a powerful device at all, but just a small laboratory "proof of principle" prototype. It had cost Johnson an enormous amount of time, labor, and optimization to get the critical adjustment required of his two magnet assemblies. But the device had no power source other than the permanent magnet assemblies themselves. Johnson's nonlinear rotor and stator magnets interacted with each other in a manner to break local symmetry. So his machine was an open system and therefore a permissible overunity device; it was not a perpetuum mobile.

[33] As I have pointed out repeatedly in the past, photons also carry time, not just energy. We have previously shown the process and the photon interaction mechanism that creates the flow of time itself; we will discuss this mechanism in the future. So when Johnson separates the particles and antiparticles, not only does he partially separate them according to spin, but he also alters the local character of time flow during which the resulting magnetic field forces must appear. In other words, he accomplishes a partial separation of time-forward and time- reversed polar interactions. A south pole is just a time- reversed magnetic north pole, in the first place! So a north pole of a bar magnet that is slightly time reversed on one side will partially act on that side just like a south pole. On the other side it will continue to act like a normal north pole. By partially time-reversing (phase conjugating) one side of the north magnetic pole piece, Johnson makes that side look and act like a south pole. that way Howard is able to create two north poles, one on a stator and the other on a rotor, and time-reverse part of one face of the stator's north magnetic pole-piece. Therefore when the proper sides of the stator and rotor north poles are facing, they attract each other, contrary to the conventional textbook. The two poles then repel each other normally as soon as the north rotor poles passes the north stator pole. Hence Johnson can make a surrounding north pole stator assembly "draw in" an approaching north pole rotor assembly, and then kick it on out the other side, because he has broken the local magnetic symmetry. In short, Johnson's magnetic gate can provide a legitimate component of unidirectional magnetic thrust, which means that he can indeed make a rotary permanent motor. Simply put, this "partially separating the spin particles," and thereby partially phase conjugating one face of a magnet, is what Johnson calls a "gate," and this is the patented secret by which his magnet assemblies can be made self-powering. The entire process is still very meticulous, and assembly and adjustments are extremely critical. With Johnson's blessings we hope to shed more light on this subject in coming articles.

[34] For a basic article on rotary permanent magnet motors, see T.E. Bearden, "On Rotary Permanent Magnet Motors and 'Free' Energy," Raum&Zeit, 1(3), Aug.-Sep. 1989, p. 43-53.

[35] The most blatant error in all of physics is the erroneous notion that an acting force is separate from its receiving mass. Force is defined as F ~ d/dt(mv). From that definition alone, it can be seen that the affected mass is a component of the force itself. If you remove the mass m, you do not have force but merely acceleration. The notion of force separated from the mass came from ancient and familiar experiences of pushing on stones with one's hand, etc. In this primitive case the force-creating agent (i.e., the hand) is certainly separate from the affected mass (i.e., the stone). But the "force on the stone" is actually the force created of and with the stone. It is "stone-force," not "force upon the stone." Quantum field theory already tells us that it is the absorption and emission of virtual photons by the stone's mass that "creates the force." In fact it should go one step further: It is the coupled ensemble of the virtual photon flux and the mass of the stone that constitutes a "stone-force." In your mind, you should try mentally replacing the word "force" with the phrase "mass-force" until you root out the deeply ingrained erroneous notion that force and mass are separate. Because of this archaic error, today's physics can only define a mass in terms of its resistance to a disturbing force, and it can only define a force in terms of its overcoming a resisting mass. This error has prevented any proper definition of either force or mass! But the problem is solvable. For a proper definition of mass without the notion of force, see T.E. Bearden, Quiton/Perceptron Physics: A Theory of Existence, Perception, and Physical Phenomena, National Technical Information System, Report AD-763210, 1973.

THE VIRTUAL TIMES

In this first article I wanted to introduce the 14 major areas. We will be discussing these areas in some technical detail in the future. We'll also include current major news items of development in these areas, for the interested lay reader. I'll particularly try to give you the benefit of extensive reference citations painfully gathered over the last 30 years. The articles will be targeted toward both the serious researcher and the interested, educated layman.

So that's the agenda for the months ahead. We hope you find this information and the approach of direct interest and use.

Again, it's a privilege to be aboard. And we invite you to hang on in the future; it's going to be a wild but exciting ride. We really are going to chase this wild dragon with great vigor.

ILLUSTRATION LIST

©copyright T.E.Bearden 1995

VT Page1

Comments may be sent to
the **Editor** of The Virtual Times

Novel Principles In The Rife Microscope

And Rife's Great Secret [1]

© 1998 T.E. Bearden

Substantially updated Aug. 20, 2001

Foreword

In the 1930s and 1940s, Royal Raymond Rife {1} made revolutionary discoveries in microscopy, including development of novel microscopes that could see far beyond the accustomed one-tenth wavelength limitation according to Rayleigh theory. With his microscope, he was able to "see" ultramicroscopic living forms much smaller than anything considered in the observable state. It would appear that his microscope was somehow capable of peering directly into the virtual state itself, and finding living forms at that level that were far beyond anything ever suspected by conventional science, even to this day.

Obviously this work was dramatically controversial. Rife went on to develop treatment methods and devices based on the new level of living organisms that his microscope revealed. In short, he arrived at essentially a new theory of disease, and did achieve success with his—to conventional scientists—completely unprecedented devices and methods of treating and healing. While we do not discuss his treatment methods in this paper, we do discuss the methods of Prioré, whom we believe to have used similar principles. So these discussions may shed some light on Rife's therapeutic mechanisms also.

Rife and others reported his results in the proper scientific literature. For his efforts, he was ostracized, essentially imprisoned in a medical treatment facility, broken, and rejected by his peers. His findings were harshly ridiculed and discredited. Finally escaping from his enforced confinement, Rife lived out his remaining years and died quietly and unknown.

In the present paper it is not our purpose to address Rife's theory of disease or his treatment devices and methods. It is solely our purpose to propose a higher symmetry electrodynamics functioning of his microscope, as one possible explanation of the startling microscopy results he achieved. We will reveal what we are convinced is Rife's great secret: recursive virtual state magnification (amplification) by iterative difference frequency serial summation of vacuum engines. This is a substantial change from an earlier mechanism proposed by the present author, which proved to be in error {1}.

We accent that this is not a "standard electrodynamics" examination of the Rife microscope; normal U(1) electrodynamics and transverse EM waves contain no mechanisms that can explain the functioning of the instrument. Accordingly, since no such explanation is contained in the usual electrodynamics, one must of necessity turn to those available electrodynamics models that are of much higher symmetry than afforded by vector and tensor algebra. To show the fit to experiments, we must also address an enormous amount of the work performed by Prioré and his colleagues. Only in such EM models and their known fit to actual experiments are the additional phenomena and principles available that can possibly explain Rife's epochal results.

Also, because of the importance of this unified field theory area, we include substantial references and additional extended discussions in the endnotes for further technical clarification. Thirty figures are added to illustrate the material.

The Rife Microscope

The Rife microscope { [1] } (Figure 1) cannot be made to work by normal optical principles at the level utilized by Rife. With normal optics, about one-tenth wavelength is as fine an optical resolution as one can get. Since Rife went far beyond that, it should be obvious that he was using optics and electrodynamics of a *novel kind*, and of a type not yet in the conventional textbook.

We believe we are aware of the major principles used in Rife's microscope, or at least some of them, but prior to 1998 we shied away from anything to do with the scope. My major interests have been in extracting EM energy from the vacuum and in developing a new kind of medical therapy utilizing higher symmetry electrodynamics—and thus unified field theory—to directly and slowly change cellular disease or disorder back to a normal previous state. Obviously, if one is to produce a microscope that "sees" optically further into the realm of smallness than any other microscope can conventionally do (even in theory), that microscope must be functioning in a higher electrodynamics mode rather than in the conventional one.

In this paper, we will try to summarize some deep physics principles underlying the Rife microscope, at least as we see them terms of a higher symmetry EM model, and we cite some references for the bits and pieces. A more detailed explanation must wait for a future time and assistance from very high-level theorists.

Introduction

A good hint is this: Rife (Figure 2) often painfully adjusted his microscope stages for up to *24 hours* before he finally got the instrument "focused." Immediately that shows it is not standard optical equipment. Well-made standard optics—and Rife's microscope was beautifully made—can be adjusted far more easily than that (in minutes!).

So far as we are aware, no one ever looked at the Rife work except through essentially rather orthodox electrodynamics and rather orthodox optics eyes. Normal optical theory permits resolution of about one tenth of the wavelength of the light used, and a few microscopes in the last few years have gone just a wee bit further. But none have gone anywhere to the degree of smallness that Rife reported.

In our view, the orthodox approach to explaining the operation of Rife's microscope is doomed to fail from the beginning. Even a very good scientist will fail with replication, if that approach is exclusively taken. An entire scientific team and substantial funding will not do any better, unless something technically deeper is understood and tackled from the outset. We give an overview of our approach to tackling that problem. To begin with, we must present some errors in electrodynamics and an omission in general relativity, so that we can develop the necessary background. The discussion is not simple and will require considerable development. Once the considerable background is developed, the application to the Rife microscope will be straightforward.

Errors in Electrodynamics and Adjustments to General Relativity

First, present electrodynamics itself has serious flaws and shortcomings, and needs substantial revision {[2] }. As foundations scientist Bunge points out {[3]}:

> *"...it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state."*

Bunge {[4] } also said:

"... the best modern physicist is the one who acknowledges that neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling not only to better cover their own domains but also to join smoothly so as to produce a coherent picture of the various levels of physical reality."

The flaws in electrodynamics pass over into what has been constructed for optical theory—both linear and nonlinear—which just assumes the electrodynamics as a subset.

For our purpose, we need to clarify what modern electrodynamics does and does not say about the massless vacuum, and about the state and form of EM entities—such as potentials, fields, and waves—created in it (in *empty space*) by matter dynamics, or acting from it (from *empty space*) onto matter and causing matter dynamics.

Maxwell and all his peers believed firmly in the material ether, a thin material fluid filling all space and every crevice. To scientists at the time, not one single point in the universe was devoid of this material etheric fluid—this *thin matter*. The atom had not been discovered, the electron had not been discovered, and electricity was also considered a thin material fluid. Charge had no more meaning than “a piece of the electric fluid,” much like a cubic centimeter of water.

Faraday {[5] } believed that the EM influence in space consisted of *material lines of force which acted as taut strings under tension from some mysterious source*. He believed that EM disturbances were just the transverse wave “perturbations” of these taut strings. In his concept, Faraday omitted the string holder or other agent producing the tensile forces upon the string (Figure 3). He thus omitted Newton’s third law from his electrodynamics concept. He also omitted precisely half the energy, by omitting the equal-energy time-reversed EM wave that accompanies the formation of every ordinary EM wave we take account of. In a receiving copper wire antenna, for example, not only do the electrons interact with the incoming fields, but so do the protons in the nuclei—though highly damped in amplitude by the proton's large mass with respect to the mass of a disturbed Drude electron. However, the two energetic interactions (of perturbed protons and perturbed electrons) are of equal *energy* magnitude. So in the conductor, equal energy is expended to move the "lattice holes" (positrons) as is used to move the Drude electrons, else field theory itself is falsified. Except in semiconductors, electrical engineers mostly just ignore the "disturbed lattice hole current" energy.

Maxwell deliberately captured Faraday’s thinking, mathematically {[6] }, and so just *assumed* Faraday’s lines of force and the “plucked tight string” transverse EM wave in the material ether {[7] } as well as the unexplained tension . The notion of the transverse EM wave in vacuum has essentially no other theoretical justification than that Faraday-Maxwell assumption and the observed "transverse waves" generated in the receiving "electric fluid in the conductor" in and on the Drude electrons. The transverse EM wave notion in vacuum was maintained only by discarding its missing antiwave that is always formed simultaneously in our transmitters and receivers (e.g., when we perturb the Drude electrons in a transmitting wire antenna, we also perturb the protons in the nuclei with the same energy. The two disturbances—proton disturbance in the nucleus and Drude electron disturbance in the Drude electron gas—perturb the local surrounding vacuum/ spacetime with equal energy, so in the vacuum "virtual particle flux gas" the two perturbations are energetically equal. The receiving wire receives both perturbation waves from the vacuum; one perturbs the electrons and the other perturbs the nuclei. Since the second wave is unaccounted, the perturbation of the nuclei is just considered a "mysterious force" that always appears. In a pumped phase conjugate mirror material, e.g., we interact the waves prior to their reaching the nuclei, by multi-wave mixing. Since the "causative" but neglected second wave coming in from space does not reach the nuclei, but are redirected to form the phase conjugate replica wave produced by the pumping, *the mirror does not recoil and it does not exhibit Newtonian third law reaction*. However, since electrodynamics *omits* the EM causative wave that generates Newton’s third law forces in the receiver, which in normal detection always appear, then presently electrodynamic fields are erroneously said to be devoid of Newton's third law reaction. To the contrary, the effects of that hidden, neglected EM cause of the Newtonian third law reaction do appear, either as recoil of the physical receiving antenna or as the production of the time-reverse phase conjugate replica wave in optical pumping. But in standard electrodynamics, equal-and-opposite forces in the receiving antenna are assumed to arise "mystically” or from some hidden *electrodynamic demon*. The electrodynamic cause of Newton's third law has been lost since Maxwell wrote his theory.

Maxwell, however, was careful to point out the ad hoc nature of assuming the stress in the vacuum, and that no mechanism for it had been discovered, nor was such a mechanism contained in his theory. Specifically, Maxwell said {[8] }:

> *“It must be carefully borne in mind that we have made only one step in the theory of the action of the medium. We have supposed it to be in a state of stress, but we have not in any way accounted for this stress, or explained how it is maintained. This step, however, seems to me to be an important one, as it explains, by the action of the consecutive parts of the medium, phenomena which were formerly supposed to be explicable only by direct action at a distance. … I have not been able to make the next step, namely, to account by mechanical considerations for these stresses in the dielectric. I therefore leave the theory at this point, merely stating what are the other parts of the phenomenon of induction in dielectrics.”*

Indeed, we now know of electrons and their spin. The longitudinally-constrained, spinning Drude electrons in receiving wires will gyroprecess laterally in the wire when an EM disturbance from the vacuum interacts with them. (Figure 4) It is well-known that these Drude electrons are highly restrained longitudinally down the wire; the longitudinal movement is the "drift" velocity and may be nominally only a few inches per hour. The lateral precession of the longitudinally constrained, spinning Drude electrons establishes that the incoming vacuum disturbance, before its interaction with the gyroelectrons, is *longitudinal*. Else one must discard electron spin, electron gyroprecession, and indeed the theory of gyroscopic precession itself. In our view, the EM wave *in vacuum* is longitudinal, always has been, and always will be {[9] }. It also *does not* consist of EM force fields, contrary to present classical theory. Instead, only the potentiality {[10]} for the transverse force fields—*should* the longitudinally perturbed vacuum EM entity be intercepted by a spinning charged particle and interact with it—exists in mass-free space, as pointed out by Feynman. Quoting Feynman again {[11] }:

> . *"We may think of **E**(x, y, z, t) and **B**(x, y, z, t) as giving the forces that would be experienced at the time t by a charge located at (x, y, z), with the condition that placing the charge there did not disturb the positions or motion of all the other charges responsible for the fields."*

Rigorously the force fields exist only in and of matter. In matter-free space, there is no force at all in what we call the "field as it exists in massfree space" {[12] }. E. g., Jackson states it this way {[13]}:

"Most classical electrodynamicists continue to adhere to the notion that the EM force field exists as such in the vacuum, but do admit that physically measurable quantities such as force somehow involve the product of charge and field."

But again, Jackson also states {[14] }:

> *"...the thing that eventually gets measured is a force..." "At the moment, the electric field can be defined as the force per unit charge acting at a given point. It is a vector function of position, denoted by E. One must be careful in its definition, however. It is not necessarily the force that one would observe by placing one unit of charge on a pith ball and placing it in position. The reason is that one unit of charge may be so large that its presence alters appreciably the field configuration of the array. Consequently one must use a limiting process whereby the ratio of the force on the small test*

> *body to the charge on it is measured for smaller and smaller amounts of charge. Experimentally, this ratio and the direction of the force will become constant as the amount of test charge is made smaller and smaller. These limiting values of magnitude and direction define the magnitude and direction of the electric field E at the point in question. In symbols we may write F = qE where F is the force, E the electric field, and q the charge. In this equation it is assumed that the charge q is located at a point, and the force and the electric field are evaluated at that point."*

As can be seen, much of the difficulty occurs because physicists continue to erroneously utilize an *equation* as if it were a *definition*. An equation defines nothing at all; it merely states that all the "things on the left" of the equality sign and all the "things on the right" have the same overall magnitudes. It does not *define* any of the things on the left or right, and so it tells us nothing at all about what anything in it *really is*. A definition requires an identity, not an equality. E.g., if we take as an identity the very equation advanced by Jackson's explanation above, we then have a definition:

$$F \equiv qE \Rightarrow E \equiv F/q$$

And now that identity clearly states that charged mass is a *component* of the **E**-field. Similar argument prevails for the **B**-field, etc.

The identity also shows that E is not the *magnitude* of the force field at all, but is its *local intensity* at any given point in the E field, in terms of force per unit point static coulomb—a force formed in, on, and of the charged mass of the coulomb. The misstatement that E represents the *magnitude of the field* is another great non sequitur. No textbook gives the calculation of the *magnitude* of the E-field, though all purport to. Instead, they all give the calculation of the *intensity* of the E-field at each point in it. There is a great difference between the magnitude of an automobile's mounted tire and its pressure per sq. inch on the pavement. In all fairness, some of the better texts do use the term "field intensity", at least occasionally.

As *defined*, the EM force fields are effects produced in, on, and of charged matter and *only* in, on, and of charged matter. They are not at all the same effects produced in matter-free space (in the vacuum/ spacetime). The EM force field (in matter) is not the same as the "massfree" E-field in massfree spacetime. Ultimately, all that exists in spacetime are *spacetime* and *changes to spacetime*.

We may accurately take the mass-free, force-free EM field to be a pattern of spacetime curvatures. The coupling of this spacetime curvature set, or any part of it, with charged mass, then constitutes an EM force field. Again, the problem is the hoary old mechanics notion of having a separate massless force acting upon a separate mass. No such thing exists in all nature, and mechanics should have been rather thoroughly overhauled long ago as a result of this horrendous *foundations of mechanics* error that is centuries old.

In present classical electrodynamics—certainly the kind taught to electrical engineers and used in the electrical engineering discipline—the EM potential {[15] }, field, and wave, as they truly exist in space and in the vacuum, are rigorously not prescribed at all. Instead, the effect of the "causal entity" as it exists in vacuum prior to interaction with charged mass, is used a if it were what exists in and on the charged mass as the effect of the interaction. (See Figure 5, Figure 6, and Figure 7). This substitution of the effect for the cause is arguably the greatest uncorrected error in classical electrodynamics today. It is a hangover from the old days of the material ether, and the refusal to change the Maxwell-Heaviside equations to eliminate that material ether assumption, once the Michelson-Morley experiments falsified it. This has long been known to foundations physicists, and to most of the better electrodynamicists as well. But it still seems to be known to very few electrical engineers!

Many attempts have been made to “modify” the standard classical electrodynamics theory, but most have failed. For some reason, most of these attempted modifications seem to have accepted the present “matter-to-matter transform” approach (Figure 8) of present electrodynamics, failing to see that the two missing transforms of matter-to-spacetime and spacetime-to-matter (Figure 9) are in fact just general relativity itself {[16] , [17] } The solution for adding the missing two transforms into electrodynamics therefore may lie in “infolding” general relativity directly within electrodynamics, rather than placing the two on an equal footing. That requires the analysis of the supersystem rather than the system, a concept which will be discussed shortly. Figure 10 shows the utilization of the "vacuum engine" that results from this "infolded GR" solution.

To our knowledge, the Sachs unified field theory {[18] a,b,c,d,e} is presently the only practical unified field theory that can be directly engineered by higher symmetry electrodynamics, such as the O(3) group symmetry EM model advanced by Evans and Vigier and perfected by Evans {[19] }. The engineering power of Sachs' theory is remarkable {[20] }, and the O(3) electrodynamics has been shown by Evans to be an important subset of the unified electrodynamics in Sachs' theory.

Let us examine that statement a little deeper.

In classical electrodynamics the sources of all EM potentials, fields, waves, and their energies are assumed to be the charges—which are assumed to somehow act as perpetual motion machines that continuously *create and pour out* all that EM energy in the fields and potentials associated with the charge as their "source". This outpouring of 3-space energy comprising and establishing the associated potentials and fields eventually fills all space with energy. All the charges and dipoles present in the universe since shortly after its formation have done this for some 14 billion years.

Yet in classical EM—with all the existing charges in the universe implicitly assumed to continuously pour out energy into all of space, and most having done so for billions of years—inexplicably space is *then* considered to be an emptiness having no interactive energetic exchange with the charge at all {[21] }. That of course is a non sequitur because it involves a total contradiction of the conservation of energy law. If there is no active energy in spacetime for the charged particle to receive and then output in 3-space, then the energy conservation is falsified by every charge and every dipole.

In particle physics the inactive vacuum concept is known to be quite wrong, else the charge creates energy from nothing. That would violate the most sacrosanct law in physics: that *energy can neither be created nor destroyed*. So electrodynamics—both classical and quantum, neither of which contains the solution to this *source charge problem*—is in gross violation of conservation of energy laws, because it assumes that the charge is solely the source of its associated fields and potentials and their energy { [22] } and that it accordingly creates all that energy it has poured out since the beginning of the universe.

Presently the electrical engineer implicitly assumes total violation of the conservation of energy law with every equation he writes, and is blissfully unaware of it.

Particle physicists, however, have done much better and published and incorporated their results, although inexplicably the mainstream electrodynamicists have not changed their own model accordingly. Particle physicists have known and shown for more than 40 years that (i) space is a seething inferno of EM energy { [23]}, (ii) a charge continually undergoes a violent energy exchange (see Figure 11) with the vacuum EM flux. That exchange is what a charged mass is doing, to *make* it a "charged mass"), and (iii) the charge is a *broken symmetry* in that violent energetic flux of the vacuum. "Broken symmetry" means that the charge disrupts and alters part of that virtual particle flux to observable EM energy flux (see again Figures 5, 6. and 7). The charge continually absorbs virtual energy from the vacuum, radiates *some* of that absorbed energy back to the vacuum in virtual form, but *integrates and radiates the remainder* in a flow of potentially observable energy—the energy flow discovered by

Poynting {[24] } and Heaviside {[25] } after Maxwell was already deceased.

So what does the source charge really do? It coheres, transduces, and *gates* some of its virtual energy {[26] } received from the vacuum, into an EM energy flow going out in all directions in 3-space from that source charge. Contrary to present electrodynamics, this energy flow is actually longitudinal and bidirectional {[27] , [28] , [29] , [30]}, with energy *going out in 3-space from the charge* to every point in the universe, and with energy coming from every point in the universe *back to the charge through the time domain*. But as reinterpreted {22 b}, Whittaker {[31] } showed in 1903 that any such bidirectional EM flow of energy —reinterpreted with the input energy to the charge coming from the time-domain, and the output energy from the charge being emitted into 3-space, comprises a scalar potential. This also agrees with quantum field theory {[32] }

See Figure 12. As it really exists in space, a scalar potential is a harmonic set of bidirectional EM energy flows, with the "bidirectional" EM waves being outgoing EM waves in 3-space caused by interaction with the source charge or dipole of incoming time-polarized EM waves. There is a set of outgoing EM longitudinal waves in 3-space, perfectly correlated with a set of incoming time-polarized EM waves in the time domain. Hence one time-polarized EM "causal" wave couples with one outgoing longitudinal EM wave in 3-space. It is this scalar EM wave coupling (combining) with longitudinal EM wave coupling, in a harmonic set of phase conjugate pairs, that constitutes the scalar EM potential.

In short, all EM energy in 3-space comes from the time domain.

After all, no observable persists continuously in time. Any observable is a frozen 3-space momentary snapshot of an ongoing 4-space interaction. It is the result of a d/dt operation imposed upon LLLT spacetime, to yield a momentary LLL by d/dt(LLLT) => LLL

What we see as the "motion of an object in 3-space" is actually the ensemble of a continual serial iteration of such "frozen 3-space snapshots" of each observable part of the object, much as the iterative frames of a movie film are seen as a continuously moving picture.

In Whittaker's bidirectional energy flow associated with the source charge, electrodynamicists—including Whittaker himself—assumed that a point positive coulomb of charge is located at each and every point in space. (Figure 5, Figure 6, and Figure 7). A tiny bit of the impinging EM energy flow "from" the distant source charge {[33] } is geometrically intercepted and diverted by the observing/detecting point charge to streamline around it, creating a "swirl around" of diverted energy flow. As can be seen, only a tiny portion of the impinging and passing EM energy stream in 3-space is diverged into the swirl. This is rather like a small diverted whirlpool of water forming around a stable rock in a flowing river. In electrodynamics the amount of energy in that "diverged whirlpool" is said to be the "collected" energy appearing upon that point charge (upon that fixed rock). That amount of energy swirled by the intercepting point coulomb at a given point in space, is then erroneously said to be the *magnitude of the potential (the magnitude of the entire river)*. It is no such thing. The small fraction of the potential that is *diverted from* the potential's flowing rivers of energy, is not that the magnitude of that potential (the magnitude of the entire set of flowing rivers themselves!) And it is certainly not "identically" the river itself! At best it is a measure of the *intensity* of the potential (the local intensity of all those internal rivers of energy flow) at that point occupied by the intercepting/diverting rock.

The point is, *as defined and used in conventional electrodynamics*, the potential occurs only after the vacuum EM entity's reaction with the intercepting mass, and is defined only as the *effect* produced upon that coulomb by the causative potential's interaction. Literally, the potential (the cause) is erroneously defined as the "excitation" or "excess energy" it locally produces as an *effect* upon a unit point intercepting/ collecting charge.

Ironically, it appears that no electrodynamicist calculates the magnitude of the actual potential as it exists in vacuum-spacetime, before its interaction with charge {[34], [35] }. Its magnitude is enormous, since the potential may extend over all space, and energy can be intercepted and collected by a charge placed at any point therein, or from charges placed at every point therein.

Certainly no rigorous definition of the potential presently exists in physics; the reader is challenged to check for himself or herself. No legitimate definition *can* exist for the potential, until the little matter is resolved of its present erroneous definition only "in and on and deviated by" charged matter, contradicted by the simultaneous assumption that it does exist in mass-free space in undeviated form. What is *deviated from* the potential, is not the *potential itself*. A part of something torn out of that something at one point in itself, is not the whole. The *local effect* cannot be substituted for the *entire nonlocal cause*—only a small part of which interacts *locally*.

The EM force field is similarly defined—only for charge mass interception, and only as an *effect* produced upon the intercepting charge. (See again Figures 5, 6, and 7.) A flow of water across a rock (or the wind on a rock in the desert) produces a “pileup” of fluid on the windward side, and a lesser “pileup” on the downwind side. The difference (called the “gradient”) in the energy density collected across the standard charge (rock) produces a “difference in pressure” on the rock—in other words, a force per interacting rock. That *effect* is erroneously taken to be the EM field itself, when rigorously it is only the reaction cross section of the EM field. Again, rigorously this EM field *as defined in electrodynamics* only exists as the effect that occurs upon an intercepting standard charge or "rock" {[36]}.

Since the EM wave “in space” is erroneously said to be made of varying EM fields, it too is defined only as the effect upon the intercepting charged mass, after the vacuum EM wave entity—whatever it is—has interacted with the charge and changed the charge translationally and energetically. Specifically, the present “EM wave in vacuum” in the literature is not at all what is presented and taught in undergraduate texts, and even the standard illustration of "oscillating E-field and B-field vectors" lateral to the line of motion of the wave is horribly wrong. E.g., Dr. Robert Romer, former editor of American Journal of Physics, has taken that error to task as follows { [37] }:

> *"…that dreadful diagram purporting to show the electric and magnetic fields of a plane wave, as a function of position (and/ or time?) that besmirch the pages of almost every introductory book. …it is a horrible diagram. 'Misleading' would be too kind a word; 'wrong' is more accurate." "…perhaps then, for historical interest, [we should] find out how that diagram came to contaminate our literature in the first place."*

The EM field and wave *as commonly regarded* are transfer functions from the source charged masses that “perturbed the vacuum medium and created an unknown kind of disturbance therein”, onto the receiving charged masses that intercept the incoming “unknown vacuum wave entity that was created” and interact with it, being translated and perturbed as a result.

This “detected” translation of the receiving charged masses (usually the interacting Drude electrons in a wire) is what our instruments detect. Indeed, the Drude electrons are highly constrained from moving longitudinally down the wire, usually moving at only a few inches per hour. They are much freer to move laterally, however, and can easily do so.

Reacting with the incoming longitudinal EM wave perturbation of local spacetime, the spin of the electron produces gyroscopic precession laterally in the wire since the electron is terribly restrained in moving longitudinally down the wire. Since our instruments detect these *transverse electron precession waves*, that has been totally confused (since Faraday's "plucked taut string" notion of the EM wave and Maxwell's arbitrary adoption of it) as representing the incoming wave in vacuum. It does not represent the vacuum EM wave at all; the incoming wave is in fact a longitudinal EM wave in 3-space, associated with a precisely correlated longitudinal EM wave in the time-domain.

So we have answered Professor Romer's implied question. That horrible diagram came from the assumption by early electrodynamicists, before discovery of the electron or atom or nucleus, that the "transverse electric fluid waves" in the receiving wires represented actual "intercepted" fluid perturbations arriving in the material ether medium.

In summary: Using a transmitter-receiver analysis, the so-called “EM wave in vacuum” *as presently defined*, actually represents that “detected and measured electron precession wave” in and of the reacting Drude electron gas in the distant receiving wire antenna. The so-called EM force field wave in vacuum has been erroneously defined as observable matter wiggles, not vacuum virtual energy wiggles and not as spacetime-curvature changes and wiggles. So even the present notion of the EM transverse wave in space is wrong, and it has been corrupted as a pure matter-to-matter transform from the beginning { [38] }.

Somewhat less technical explanations are given by Lindsay and Margenau { [39] }, and a rigorous statement and discussion that EM force fields exist only in charged matter is given by Aharonov and Bohm { [40] }. Feynman of course said it bluntly: Only the potential for the field exists in the vacuum, should one place a unit point charge there to allow the force field to be developed (on, of, and containing the source charge itself).

Let us summarize this terrible EM foundations flaw: As classical electrodynamics presently is modeled, Maxwell and his modern followers only include equations which are *mass-to-mass transformations*

(Figure 8). Specifically missing { [41] } are two other transforms: (i) the mass-to-vacuum (mass-to-spacetime) transformation (which obviously is general relativistic in nature), and (ii) the vacuum-to-mass (spacetime-to-mass) transformation (again, obviously general relativistic in nature). (See again Figure 9). When these two missing transforms are added back into electrodynamics, one has suddenly extended EM theory into a new domain. One has also *infolded* general relativity (GR) inside the present EM matter-to-matter transforms, and also included the vacuum interaction including broken symmetry in that exchange, but in an *electromagnetically engineerable manner*. In short, one has a practical, engineerable unified field theory.

Highly creative inventors such as Rife and Prioré intuitively developed apparatuses that unwittingly utilized this presently undeveloped and extended union of EM, particle physics vacuum theory, and GR. The intuition of the theorists in interpreting those revolutionary experiments and their results has very seriously lagged.

The Supersystem Concept

To understand how extraordinary systems such as Rife's microscope works, one must understand the concept of the *supersystem*. (See Figure 13). The supersystem consists of three components, which are (1) the physical system and its dynamics, (2) the local active vacuum and its dynamics, and (3) the local curvatures of spacetime and their dynamics. All three components of the supersystem interact with one another, in nature. The second and third components of the system constitute the active environment in which the system is embedded, and with which it interacts.

Unfortunately, in standard classical electrodynamics either the system's environment is assumed to be inert, or the system is assumed to be in equilibrium in its interaction with that environment. This represents a totally arbitrary assumption that the system cannot receive and utilize any excess energy from its known active environment. Hence the active vacuum's interaction with the system can be and is ignored by classical electromagnetics, as are the local curvatures of spacetime and their interactions with the system.

Extraordinary EM systems invariably involve the supersystem dynamics, and not just the system dynamics. *In nature*, no system analysis is complete until the supersystem interactions and their effects have been determined and analyzed.

The Rife microscope is indeed an extraordinary system using non-negligible interactions between the system and the other two components of its supersystem. Hence in our discussions, we will be examining interactions in that regime, and not just the standard electrodynamics analysis. In these discussions, we will be holding in mind not just the mass-to-mass transforms of standard electrodynamics, but two other transforms: (1) the mass-to-vacuum/spacetime transform, and (2) the vacuum/spacetime to matter transform (previously shown in Figure 9).

The reason that Rife's work has not been understood is that researchers have been unaware of the necessity for supersystem analysis. Almost all analyses of Rife's work have been merely standard classical EM analysis and thus quite insufficient. There are other examples of the standard electrodynamics model completely failing to show higher symmetry phenomenology in an inventor's work, so that his work is not understood even today. An example is provided by Tesla's patented circuits, as rigorously demonstrated by Barrett { [42] }. Barrett went on to improve the new functions discovered in Tesla's patents, and obtained two additional patents related to signals and signal processing { [43] }.

Vacuum-Structurings as “Engines”: Key Part of the Missing Transforms

The missing mass-to-vacuum/spacetime transformation produces a massless structuring of the vacuum medium. That is a *vacuum engine* or “multiplex of specific spacetime curvatures.” (See Figure 14, Figure

15, Figure 16, Figure 17), and Figure 18. Preparing the vacuum engine is accomplished by charged matter dynamics of the source charges producing the necessary potentials, fields and waves. The charges are embedded in continual energetic exchange with the vacuum/spacetime, and moving the charges affects that exchange; it perturbs the local vacuum flux and curves the local spacetime accordingly.

The transform represents producing this vacuum engine by the vacuum-perturbing action of source charge dynamics upon the vacuum, and by *not* assuming a mystical intercepting point-charge at each point in space { [44] }. In the vacuum/spacetime, *only* vacuum/ spacetime entities and changes to them exist. *In pure water, only water and changes to that water exist!*

So a precise dynamic structuring of the energetic vacuum (and spacetime geometry) is what charges produce when they “perturb” the vacuum medium { [45] }, by the presence or dynamics of their fields, longitudinal and time-polarized EM waves, or both. This "perturbed vacuum dynamics" separate from the source charges themselves comprises an engine that consists of altered longitudinal EM wave dynamics inside the internal Whittaker structure { [46] } of the scalar potential of the ambient vacuum. That is the same as also producing internested levels of spacetime curvatures in a *template* or specific pattern { [47] }.

In turn, this vacuum engine region of local curvatures and structurings in spacetime will interact upon any mass placed therein. That action is the missing *electrodynamic vacuum-to-mass transform.*

The missing electrodynamic vacuum-to-mass transformation produces direct changes and alterations in the “receiving” mass, at all levels, by the action of such a vacuum engine. As each action occurs locally in the localized receiving mass, it produces the "local effect" as the result of that “local action.” The primary causative chain (i.e., the set of “dominoes” affecting each other serially), started back at the distant source charges. One can say that we therefore have mass-to-mass *action at a distance*, via the matter-to-vacuum and vacuum-to-mass intermediary transforms and the spatial and temporal propagation of the vacuum engines in the middle of the two { [48] }. We will shortly discuss the Whittaker structuring of the potential as a fundamental process for producing vacuum engines.

General relativists mostly concentrate upon the warping and curving of spacetime (i.e., producing a vacuum engine) by the very weak gravitational force—which is only some 10^{-42} times as strong for electrons as the electric force between them. Consequently, relativists must look to huge assemblages of mass, such as in stars and other astronomical objects, for sufficient gravitationally-induced spacetime curvature to produce easily observable results. For that reason, general relativity has resisted laboratory development as an engineerable applied science. By using the far stronger EM force as the agent of spacetime curvature, and including the infolded electrodynamics inside the potential, field, and wave, general relativity then becomes engineerable and usable. But one is engineering the supersystem, not just the system.

The Infolded Electrodynamics Inside Potentials, Fields, and Waves

As previously stated, in 1903 E. T. Whittaker, a well-known mathematical physicist, showed that a scalar potential can be mathematically decomposed into a set of peculiar EM wavepairs in a harmonic set. (Again see Figure 12) These "hidden waves" are longitudinal EM waves, arranged in conjugate pairs { [49] } with the pairs also arranged in a harmonic set. In each wavepair, there is an ordinary (forward-time) longitudinal EM wave (outgoing in 3-space from the interacting/observing charge), coupled to its phase conjugate replica (time-reversed twin).

And here lies a magic secret. Prior to interacting with a charge, the phase conjugate wave in each wavepair is in the complex domain, which means that in Minkowski space it is incoming along the fourth axis, *ict*, where the only variable is *t*. Hence this wave prior to interaction with charge does not even exist in 3-

space. Instead, it exists as a longitudinal EM wave incoming in time, so that it is a time-like flow of EM energy. (See Figure 19). After interaction with a charge, the charge absorbs the incoming time-polarized EM wave, transduces that time-energy to 3-spatial energy, and re-emits the energy as longitudinal EM waves in 3-space in all directions. "In all directions" means that for every outgoing longitudinal EM wave emitted in one direction in 3-space, another wave just like it also emitted in the other direction in 3-space. So the paired "bidirectional" EM longitudinal EM waves in 3-space, as interpreted by Whittaker, do exist as the *effect* waves caused by the incoming causal time-like longitudinal EM waves (scalar EM waves). The pairing of the causal time-polarized EM incoming wave with an outgoing effect longitudinal EM wave was not interpreted by Whittaker, but does agree with more modern quantum field theory interpretations of photon polarizations and their observability or non observability, by Mandl and Shaw {22b}.

We have corrected this "effect substituted for the cause" wave to reinterpret Whittaker's 1903 decomposition of the scalar potential, into combined biwaves where one of the biwaves is incoming in the time domain, and the other is outgoing in 3-space. That re-interpretation then allowed a solution {22a} to the problem of the source charge and its associated fields and potentials, together with their energy. Every source charge and source dipole continuously emits EM energy in 3-space, without any 3-spatial EM energy input. The input is there, but in the time-domain. This problem—resolved by the present author in 2000—has been called the most difficult problem in quantum and classical electromagnetics {30 }.

Because of observed parity reversal accompanying the time-reversal operation, in his forward-time, the observer “sees”—after interacting the incoming wave with charge—the *effect* of the incoming time-reversed or phase conjugate wave (entering from the time domain) as a 3-space longitudinal EM wave leaving in the opposite spatial direction. So the basic 4-space phase conjugate longitudinal wavepair would appear to us in forward time as a “regular” time-forward longitudinal EM wavepair in 3-space, with the two waves going outward in opposite directions. But each is accompanied by a time-polarized EM wave, else it would not be observable.

Further, there is a harmonic series of such bidirectional longitudinal wavepairs comprising the scalar potential. So the staid old electrostatic potential (i) *is not* a "scalar entity" at all { [50] }, (ii) *is* a bundle of longitudinal wavepairs, (iii) *is* an entity with a remarkable internal hidden multiwave structures and dynamics, (iv) *is* a composite of very special waves whose transverse amplitude (i.e., whose spatial energy density, which is a function of transverse amplitude squared) does not change, but whose transported time structure changes, and (v) therefore is a special kind of wave that is velocity modulated about some central velocity, and is not limited to the speed of light c. Indeed, in classical electrodynamics in the Coulomb gauge, the scalar potential is already recognized as having infinite velocity, merely appearing in space instantly at every point it occupies { [51] }.

We also state without elaboration that the active vacuum is *identically* a very huge scalar potential, as indeed is “spacetime geometry”. So a unifying principle is:

> vacuum ≡ spacetime ≡ potential ≡ energy
> { [52] }

Further, as a potential, the “ambient” vacuum decomposes into an incredibly rich, internal Whittaker wave structure. So then also must *spacetime* and *energy* similarly decompose. That decomposition structure is even richer when higher symmetry O(3) EM is used instead of the lower symmetry U(1) EM employed by Whittaker.

A revolution in electrodynamics has recently begun, and central to that revolution is the strong appearance of longitudinal EM waves as essentially the basis for the emerging new electrodynamics. Work by Evans { [53] }, Barrett { [54] }, Ziolkowski { [55] }, Evans { [56] }, Rodrigues {57}, and others is fundamental in this respect. One part of this emerging new electrodynamics is advanced under the label of *undistorted progressive waves* (UPWs). A good summary of UPW theory is given by Rodrigues and Lu { [57] }. Even so, to date this body of work still largely ignores the internal Whittaker dynamics { [58] } inside an EM wave. The body of work—particularly the higher symmetry O(3) electrodynamics pioneered by Evans {56} inherently possesses the capability to model such structuring, since much of it utilizes a higher topology algebra such as quaternions { [59] } or even Clifford algebra { [60] } In those higher algebras, many electrodynamic things can be done outside the operations permitted by present vector and tensor electrodynamics.

Superpotentials and Superpotential Theory

Whittaker's 1904 paper { [61] } showed that all the "normal" electrodynamics was based on, *and created by*, the interference of scalar potential functions (i.e., by the interference of those multiwave longitudinal wavepairs and their dynamics { [62] } constituting the interfering scalar potentials.) He showed that any EM field or wave whatsoever can be replaced by two scalar potential functions—in fact, is *comprised of* those two scalar potential functions and is *created by them*. Scalar potential interferometry already creates all the "normal" EM in the textbooks anyway, and a proof has been given by Evans et al. { [63] }.

The 1904 paper by Whittaker initiated a somewhat obscure branch of electrodynamics referred to as *superpotential* theory { [64] }. Whittaker's work was further extended and augmented by later scientists such as Righi { [65] }, Debye { [66] }, Bromwich { [67] }, Nisbet { [68] }, McCrea { [69] }, etc. But even with the extended superpotential theory, without the addition of Whittaker 1903 and the substructuring "internal LW electrodynamics" one cannot understand the mechanism for what Rife was actually doing.

Rife was not using normal potentials and normal **E** and

H fields—which as we discussed, only apply to observable material entities anyhow and thus could not be used to “see” far below the quantum threshold of least detectable material disturbance. His entire protocol was to get beyond those “*material interception of EM energy*” limitations. Unwittingly, Rife was using *vacuum engines*—involving structuring of the active vacuum as well as pure general relativity (GR) and pure structurings of spacetime geometry itself. He was electromagnetically using that part of GR that the GR physicists have mostly only tried to produce by use of the weak gravitational force. In GR, *the ST geometry itself is active, dynamic, energetic, and structuring!* In higher symmetry electrodynamics, *the ST geometry itself is powerfully active, dynamic, energetic, and structuring!* It is not at all just a "passive spacetime" as classical electrodynamics assumes { [70] }.

Biological Systems Use the Infolded Whittaker-Type Electrodynamics

The problem in the Rife microscope is to be able to observe very subtle ST curvatures and patterns, in an optical manner. These subtle or virtual "disturbances" of local spacetime are far finer and smaller than the one-tenth wavelength optical resolution generally the limit for optical microscopes using conventional optical EM notions and “material” potentials, fields, and waves.

In short, Rife’s twofold problem was to (i) function with vacuum engines (internal structuring of the potentials) so he could penetrate to any degree of smallness, and (ii) output, in the observable state, exact visible summations and analogues of the individual structures detected in the virtual (nonobservable) state { [71] }.

To make the subtle vacuum engines observable on the bench, the ST curvatures and their internested patterning must be accomplished by making and assembling local curvatures of ST, via making longitudinal EM wavepairs in structural pattern assemblies. *Spacetime* is in fact just a powerful scalar potential, or can be modeled as such, and as such Whittaker 1903 and 1904 rigorously applies, along with extensions from higher symmetry electrodynamics. By realizing that ST is identically potential, one has altered one's thinking from the standard GR theory into a correlated EM-GR theory. One has also extended GR: Not only is there a "topology" of things that can be externally *done to* a base spacetime, but there is also a hidden, vast EM topology *within* any overall base spacetime. So we now have "topologies within topologies." This is in fact what the Russians have long called the *information content of the field*.

However, all living systems already use this "infolded" bidirectional, longitudinal wavepair EM in their ongoing living functions {[72]}. Just as they used frequency modulation, EM signals, EM oscillations, etc. before we even had an electrodynamics or a physics, living systems do use the infolded EM (and vacuum engines) in all their living functions, and particularly in their cellular *regeneration and restoration* (R&R) system {[73]}, as contrasted to their *immune* system. The immune system cells are the fighters and the debris scavengers/cleaners. They go after the hostile invaders, fight them, and usually win—littering the battlefield with the debris. Then the immune system scavenger cells clean up the residue.

But many of the body's cells will have been damaged in the fight. The immune system itself cannot heal or restore a single damaged cell, even its own! It is not a *healer*! It is a searcher, a marker, a killer, and a residue-cleaner. It contains " the troops and the combat engineer," so to speak, but not the hospitals and the doctors. All healing/restoration of living cells is done by the R&R system, not by the immune system.

A high-level overview of the immune system is given in Figure 20.

No vaccine, drug, herb, vitamin, or mineral *heals* the body, although certainly they can enhance or aid the body's healing process. Each does carry its individual resident vacuum engine, and when absorbed by the cell, this added vacuum engine contributes to the resident vacuum engine in the cell by summing with it. To restore the damaged cells back to normal (i.e., to heal), the R&R system uses a novel kind of extended electrodynamics with infolded vacuum engines, and it uses a novel kind of optical phase conjugate pumping, in the time domain rather than just 3-space. The magic “unified field theory” so long sought by scientists, has long been utilized by the regeneration and restoration system of the body in its minute-to-minute and day-to-day healing and restoring actions.

The magic "universal healing mechanism" so long evading the discovery of medical scientists is none other than the exact cellular regenerative mechanism universally used by every living organism. For the first time, we are explaining the higher symmetry electromagnetic nature of this mechanism.

Robert Becker's epochal work { [74] } (Figure 21, Figure 22) strongly probed the electromagnetic control system directing the body’s cellular regeneration and repair (R&R) system. However, he did not have available the infolded Whittaker electrodynamics. He could only utilize the grossly inadequate standard electrodynamics. Modern nonlinear phase conjugate optics had not yet been born when Becker did most of his seminal work.

Since standard EM does not incorporate infolded GR, vacuum engines, or optical pumping in the time domain, Becker could not formulate the full technical mechanism of the R&R system —which uses the *supersystem*, not just the system. But Becker did strongly point out the importance of the R&R system, both theoretically and experimentally. He found that it operated electrically, with the scalar potentials being key. He modeled the R&R system as closely as can be done with classical U(1) electromagnetics (Figure 22). He proved that cells can be *dedifferentiated* (reversed back to an earlier, more primitive state) and *redifferentiated* (time-forwarded into a more complex state) by weak DC potentials and laughably weak (picoamperes) of current. He was twice nominated for a Nobel prize for his epochal work. His method of electromagnetic healing of otherwise intractable bone fractures (Figure 21) is utilized today in many hospitals.

In his microscope, Rife was in pursuit of optically "seeing" the infolded electrodynamics functioning of the living cells in the most minute detail—i.e., he wished to see the actual vacuum engines and their functions. Using the infolded EM, one can still "see" the cells and all their parts, but one can also go far beyond the one-tenth wavelength optical discrimination limitation and see into the virtual state dynamics. In theory, because the infolded EM is *recursive* as a function of wavelength, one can go to any limit in smallness desired—or at least to whatever limit is determined by the available technology's development at the time { [75] }.

Vlail Kaznacheyev's novel electromagnetic induction of cellular death, disease, and damage, *at a distance*, is instructive in this respect { [76] }. (Figure 23) Indeed, the Russians mastered, extended, and weaponized the Kaznacheyev mechanisms as disease-inducing weaponry, and slyly used it at low level on personnel in the U.S. Embassy in Moscow (Figure 24). This was done to stimulate high level officials in the U.S. government and U.S. scientific community to see if the U.S. knew of this "infolded electrodynamics and vacuum engine" technology { [77] }. The Russians were using GR, but by infolded EM means—so they were using a unified field theory involving higher group symmetry electrodynamics. The puzzled U.S. employed only standard U(1) symmetry electrodynamic analysis { [78] }, so it totally missed the entire physics of what was occurring to cause the health changes and diseases.

In GR, one is very interested in Wheeler's principle which states (slightly paraphrased):

> *Mass (trapped energy) acts upon ST geometry to curve it, and curved ST acts upon mass to produce forces upon it and move it.*

This statement after Wheeler is the very essence of general relativity. It simply states that there is a *mass-to-spacetime* dynamic transform, and also a *spacetime-to-mass* dynamic transform, as we diagrammatically showed in Figure 9.

Understanding Vacuum Engines and Their Action

Wheeler's general relativity principle includes the missing two transforms of electro-dynamics. We are extending Wheeler's principle to the corollary form:

All levels of the structures of mass (trapped energy structures) and all levels of the structures of time (the time aspects of photon structures) act upon ST geometry to structure it in both 3-spatial energy density structuring and in time domain structuring. Producing this multilevel spatial and temporal structuring of spacetime is called "forming a vacuum engine." Both 3-spatial energy density structuring of spacetime at all levels and time structuring of spacetime at all levels, act upon mass at all levels, to produce internested templates of forces and translations and stresses.

In short, energy patterns and time patterns in 3-space act upon spacetime to produce patterned curvatures of ST geometry (vacuum engines). And conversely, patterned curvatures of spacetime geometry (vacuum engines) act upon mass to produce corresponding patterns of forces at all levels in the mass —down to and including upon the quarks and gluons in the nucleons in the atomic nuclei. We note with pleasure that the Sachs unified field theory does apply from the gluons to the entire universe, as has been shown by Sachs himself {18b}.

Muscle and Skeleton Analogy of Interaction of Vacuum Engine and Mass

We call attention again to our analogy (Figures 15, 16, 17, and 18) of the interaction of a vacuum engine and mass, provided by the interaction of arm muscles and the skeletal arm bones to which they are attached. The arm muscles attach to the arm's skeletal bones, and those bones are articulated and free to dynamically move. To the bones, the muscles are mysterious agents (analogous to vacuum engines) exerting forces upon them, and causing them to move or hold. To the muscles, the bones are positioned resisting masses for them to work upon and change their positions, and the bones exert Newtonian reaction forces back upon the muscles as the muscles apply forces to the bones. So the vacuum engines (muscles) create forces upon the resisting masses (bones) to move them, and the masses act back upon the causative vacuum engines to create antiforces in resistance.

Using this analogy, when we create a set of vacuum engines, we create a set of "mysterious muscles" that act directly upon any and all "masses" (bones) that are exposed to them. The bones then change and move until the bidirectional interaction forces are balanced (equal and opposite). This symmetry between the two missing transforms is shown in Figure 9.

The Multilevel Structuring of Time is Important

We also add the extension that dynamic structuring in the time stream also occurs from trapped time domain "time component" structuring and distribution effects, as well as dynamic structuring of the spatial energy density of the ST geometry (the vacuum).

We are speaking *relativistically* of the interaction of mass and spacetime at any and all levels of a mass, down to and including the molecules, the atoms, the atomic nuclei, the nucleons, and even the quarks comprising the nucleons (comprising the protons and neutrons). One must first clearly have this vision in mind: The dynamics of everything ongoing in that mass, down to the most minute particle dynamics and in the most minute detail (and far into the virtual state beyond the one-tenth wavelength limitation of light resolution) consists of the structurings of this "mass-ST curvature" mutual interaction.

So we know from general relativity that collections of energy (such as mass) act directly upon spacetime, its structuring, and its dynamics at any and all levels, down to the tiniest. We know that the variations in local spacetime geometry (including in both energy and time), down to any and all levels and sizes, down to the tiniest conceivable lengths, act directly upon any and all exposed mass at that level, *no matter how tiny*.

There is no “quantum” limitation nor is there any “wavelength of light” limitation to this GR process. Total continuity applies.

Some Characteristics of Vacuum Engines

The great advantage of a vacuum engine is that the "action" it produces upon an exposed mass, arises directly from within each point in the local spacetime in which the mass is embedded. One does not have to "start outside" and move through space and the intervening mass toward the "inside". Every point within an object occupies every point in time, a priori. From a single time-point, the vacuum engine's 3-space action enters everywhere within the object, all-at-once, and the 3-space effects proceed outward from each interior point. (See again Figure 19). Therefore even a weak vacuum engine induced by EM forces can do with ridiculous ease what the most powerful particle accelerators on Earth cannot do. The engine is already everywhere "inside" an object or particle, and working from every point in it, toward an outward direction. On the other hand, a particle accelerator is trying to build tremendous velocity of its particles so that they can "smash" their way in there, by brute force. To get ever deeper, the particle accelerator must be made ever larger, so that a "bigger hammer" is available. Also, the vacuum engine does not smash or damage any of the matter in the object, in any fashion not desired. The particle accelerator, on the other hand, is a great disruptor and may well destroy or serious change the very object it "probes".

Further, contrary to the accelerator's "one shot for one giant amount of energy input", a vacuum engine—once formed—continually exists in that locally altered spacetime and is contained in it and is sustained by it.

Hence that locally altered spacetime—after we pay to alter it once—will continuously expend energy in the form of the action of that vacuum energy, forever, upon any mass emplaced in that local spacetime. The universe itself is furnishing the energy to do the work, via the instantaneous connection in the time domain.

That "multiply connected space" entry everywhere within an object simultaneously, is quite different from "spatial propagation of energy" through singly-connected space from outside an object to the object, striking the outside of a mass and being absorbed, producing a gross translation force upon the mass. In the "energy propagation through space" case, severe energy interaction may occur with only the absorbing part of a macroscopic mass, while the remainder of the mass is little affected or not at all. To wit, one does not get the resulting *electronuclear* alterations of the nucleus (materialization, dematerialization, transmutation, etc.) by absorbed propagated "normal" EM radiation. However, with weak EM-induced vacuum engines one can do things inside the nucleus such as easily flip quarks inside the nucleons, so that transmutations at very weak spatial energy levels are readily obtained. This in fact turned out to be the major secret of the low-energy nuclear transmutations occurring in some 600 cold fusion experiments worldwide { [79] }.

Electrodynamic force fields implicitly define primarily only translation effects upon charges or masses, in their very definitions. With normal EM, usually one will get reradiation of the absorbed energy, or partial reradiation of the absorbed energy accompanied with recoil of the absorbing mass, or no reradiation but recoil of the mass.

We took the term *vacuum engine* from Misner, Thorne, and Wheeler { [80] } and also from Nobelist T. D. Lee { [81] } who spoke of this sort of thing as *vacuum engineering*. The term is not original with us; only the novel higher symmetry electrodynamics application of the concept is original. We call the exact geometrical form of a vacuum engine a *template*. We refer to the process of internally structuring a field, wave, or potential as *dimensioning* or *activating* or *conditioning* or *charging up* the field, wave, or potential. Russian superpotential weapon scientists call the infolded structuring itself the *information content of the field*. For further discussion of some of these terms and related concepts, the reader is referred to our website, www.cheniere.org.

Wheeler's GR principle says that, for every mass with its exact mass structural dynamics condition, there exists a corresponding exact vacuum engine template containing precise spacetime curvature structural dynamics, and interacting back upon the dynamic mass at all levels. That vacuum engine is said to be resident in the mass and continuously interacting with it (see again Figure 13 on the *supersystem*).

Again, the structuring of the vacuum engine has no limitation in fineness, because spacetime is continuous. Hence it freely extends from the observable realm on down into the virtual realm. This is no more audacious than stating that virtual and observable entities occupy the same time domain simultaneously. Obviously, if one is using the structuring of time, one gathers in both those virtual structures and those observable structures, and also the exact correlation between them. This is a direct engineering application of an EM hidden variable theory, somewhat similar to that proposed by David Bohm { [82] }.

Applying Vacuum Engines to Living Cells

Any normal cell already has a normal *template* of overall ST curvature due to its mass and trapped energy structures. No matter how small, every internal part of that cell has its own *subcomponent template* of subcomponent ST curvatures embedded in that overall cellular ST curvature. As the cell functions, the dynamic normal changes of that template into other related templates, is within the range of what we call "normal, healthy cellular functioning."

Any abnormal cell has an *abnormal template* and also an abnormal set of "templating" changes. In other words, there exists a precise *vacuum engine delta* in the abnormal cell, summed to the cell's *normal vacuum engine*. The *sum engine* represents the exact vacuum engine to act on the normal cell and change it to that precise abnormal condition.

But a template depends upon the energy density structuring of the local vacuum and also the local *time* structuring—which latter is still missing from physics books, but is implicit in the nature of the photon. If one produces the necessary energy structuring and density—and the necessary time structuring and density of local ST geometry—one produces a certain vacuum engine and one also produce a certain *template of time structuring*. Time {[83]} has dynamic template structuring and functioning, just as does the 3-spatial energy density of ST geometry.

Indeed, the total (virtual and observable) photon interaction with a mass or particle generates the "flow of that mass or particle through time" (Figure 25).

But one *can* make vacuum engines using EM energy and structuring, rather than with normal gravitational (G) energy and structuring {[84]}. The advantage is that, for electrons, the EM structuring is on the order of 10^{42} times as strong as the G structuring. For protons, the EM force is something like 10^{38} times as strong as the G force. So by using the much stronger EM force as the "agent of ST curvature," one can make vacuum engines that are quite strong at their local level. These engines will affect and profoundly change any exposed mass, including cellular mass—in any fashion desired, given only that one makes the appropriate vacuum engine. Again, *we are simply engineering practical but ultra-strong general relativity on the laboratory bench*, by electromagnetically engineering Wheeler's principle in an extended form.

For any physical cellular deviation from normal—any deviation whatsoever—a corresponding exact deviation (i.e., an exact delta) exists in the cell's otherwise normal vacuum engine template. This includes deviations in the genetics of the cell and everything else, not just the chemistry and gross physical structure.

Now if one could produce the negative (time-reversal) of the sum template of the resident vacuum engine and *amplify* it, one would have a powerful new type of vacuum engine. (Figure 26) It would be an exact *vacuum anti-engine* to act upon that specific diseased or abnormal condition of the cell and gradually erase the delta and bring the cell physically back to normal. The new anti-engine would operate upon all the mass of the cell, at every level no matter how small. It would change the cell's abnormal genetics back to normal genetics.

One could of course reverse cellular damage due to aging, and rejuvenate the body. It is quite doable; all that is needed are the funds, scientific team, and laboratory facilities to develop it. It is doable whenever the U.S. medical science community and the giant pharmaceutical community will allow it to be done.

One could reverse a cancer cell back to a normal cell, by applying the specific summation vacuum antiengine for the exact delta between the cancer cell and a normal cell.

One could reverse an AIDS cell back to a normal cell with normal genetics, where it no longer was an "HIV factory". An AIDS patient could be completely, quickly, and cheaply cured, the moment he or she tested HIV positive. There would be no need to wait for the debilitations of the progressing disease to appear. Not a single HIV-infected cell would be left in the body, even those resistant strains that have developed after the original infection.

One could do precisely the same thing with Ebola infections, and with the "tough" staph infections that now resist everything and are killing more than 120 thousand Americans in our hospitals every year, with the figures rising. *These are patients who did not have the disease that killed them, when they entered the hospital.*

With development of portable treatment units and mass production, one could treat and heal those millions of mass casualties that could well erupt in one or more large U.S. city areas—e.g., from an Iraqi-sponsored terrorist biological warfare (BW) strike, using anthrax { [85]). In 1998, we proposed a crash development of just such portable units { [86] }. With the present world situation, it is not a matter of *if* such terrorist BW strikes will be made in the U.S., it is a matter of *when* { [87] }. Since our 1998 proposal, there has now been time to have had those portable units developed and mass-produced, at a total program cost of perhaps $100 million. Sadly, no one apparently had the foggiest notion of what was actually being proposed, and its vital importance to the survival of the nation. With a looming war in the MidEast—and with hordes of terrorist teams with biological warfare agents already infiltrated into U.S. cities and population centers—this negligence is particularly of concern at this very moment. These officially-forecast attacks on our cities by weapons of mass destruction could now be imminent, if and when the MidEast does explode into war, which appears imminent.

The Process Has Been Experimentally Proven

A very similar thing is also what Becker { [88] } demonstrated, without considering the vacuum engine (general relativistic curvature of spacetime) effects. It is also precisely what Prioré { [89] } unwittingly did in France, with a team of renowned French scientists, to cure terminal cancers, atherosclerosis, lethal infectious diseases, etc. in laboratory animals under rigorous scientific protocols. The team also demonstrated the restoration of suppressed immune systems.

In Germany, Popp { [90] } *et al*. were also involved in studies dealing with the R&R system, but from a quantum electrodynamics viewpoint.

We can also consider the vacuum engine from a nonlinear optics view, and obtain startling extensions of both general relativity and nonlinear phase conjugate optics. That in fact is exactly what Prioré did, though he did not think in those terms. Prioré roughly created a complex set of bidirectional longitudinal EM wavepairs—i.e., a set of “time domain pump waves.” So he produced a kind of vacuum engine that itself is a crude *anti-engine generator* when used to pump a mass such as a living cell.

Prioré unwittingly used an extension to nonlinear optical (NLO) phase conjugation *before nonlinear phase conjugate optics was even born*. Pumping diseased cells in the Prioré manner causes the formation of exact "antiengines" for the specific cellular disease or disorder to be created in the cells themselves.

First, Prioré mixed up to 17 or so EM transverse waves in a rotating plasma { [91] }. Today we know that such a plasma will transform transverse radiations into longitudinal radiations, and it will also phase conjugate the input waves and add their phase conjugate replicas. In short, it is a procedure for somewhat crudely making a set of longitudinal bidirectional EM wavepairs, which is required to produce a scalar potential with a deterministic internal structuring. In short, it produces a scalar potential with an internal vacuum engine template.

These infolded longitudinal biwaves are NLO pump waves of a new kind: They pump the PCM material in the time domain only. This kind of pumping is a *vacuum antiengine-making process*.

The plasma tube was surrounded by a giant coil, and a pulsed magnetic field was produced by the coil. Per Whittaker’s 1904 paper, that pulsed DC magnetic field can be decomposed into two scalar potentials. Hence we have three potentials superposing: (1) the potential function set made by Prioré in his plasma tube, and containing a selected “vacuum antiengine maker” consisting of bidirectional pump waves in the time domain, and (2 and 3) the two Whittaker potential functions comprising the DC pulsed magnetic field of the coil.

The end result of this superposition/mixing of potentials is that their “internal structures”—including their vacuum engines—also diffuse one into the other.

Fundamentally, Prioré produced what to the observer seemed just a pulsed DC magnetic field, but one in which there was a specific "vacuum engine maker" of his deliberate creation and "tailoring." Originally by trial and error, he adjusted the 17 frequencies introduced to the plasma, thus varying the frequencies of the "infolded bidirectional pump waves" produced and infolded into the pulsed DC magnetic field carrier. In this manner he was "tuning the "vacuum antiengine-maker" content.

Again, Russian energetics weapons scientists call those vacuum engine templates the *information content of the field*. They do not refer to ordinary spectral analysis.

Explaining the Time-Pumping Vacuum Anti-Engine Maker

Irradiating the cell (with non-ionizing radiation) containing infolded specific bidirectional longitudinal waves, precisely corresponds to pumping the cells in the time domain, rather than pumping them in the "spatial energy distribution" domain. Because of the shift of the pumping from the 3-space domain to the time domain, this constitutes a dramatic extension of phase conjugate optics. Because of the amplified phase conjugating action of the "vacuum antiengine maker" upon the vacuum engine in a mass, this also constitutes a dramatic extension of general relativity and of four-wave mixing theory. Let us explain briefly:

When one pumps a nonlinear mass [phase conjugate mirror (PCM) material] with ordinary "transverse" EM waves { [92] } (Figure 27a), one is pumping (stressing, or "squeezing and relaxing") the mass with dynamic oscillating energy distributions in 3-space. One inputs a similar weak wave (called the "signal" wave) to the mass simultaneously. In that case, multiwave mixing theory tells us that the pumping of the PCM will cause the formation of a fourth EM wave, that is a time-reversed replica of the input "signal" EM wave. The time-reversed wave may contain up to all the energy in the pump waves, so it can be highly amplified in magnitude compared to the input signal wave. The distortion correction theorem tells us that this time-reversed replica wave will then appear precisely superposing in space back along the exact spatial track taken by the input signal wave { [93] }.

When the pumping is shifted to the time domain by pumping with bidirectional *longitudinal* EM waves, we now are pumping the time aspects of the mass—during it iterative existence as masstime; see again Figure 25—rather than just pumping the spatial energy aspects. In other words, we are not pumping *spatially*, but *spatiotemporally*. We are pumping *temporally*—rhythmically squeezing (compressing) and relaxing (extending) the "density of the time interactions" producing the rate of flow of time itself. This is a totally new extension to nonlinear phase conjugate optics.

In this case, the "signal wave input" to the "time-domain-pumped" nonlinear mass PCM is just the resident vacuum engine in the local spacetime in which that PCM mass is embedded (see Figure 27b). The sickened cell's abnormal vacuum engine—consisting of the sum of the normal cellular vacuum engine and the disease delta vacuum engine—is present in the cell and is the input to the time-pumped phase conjugate mirror (cellular masstime). The output is the formation of an amplified time-reversed replica of that vacuum engine. In other words, an exact, amplified *vacuum antiengine* for reversing the precise abnormal condition of the mass, down to and including even the quarks in the atomic nuclei, is formed by time-domain (longitudinal EM biwave) pumping. The result or "output" is that *the entire cellular PCM mass and all its constituent parts are "time-reversed" back along their previous "track through time", back to a previous normal physical state* { [94] }. Figure 27b illustrates this process.

So when Prioré pumped the abnormal cells, he simply time-reversed them—genetics and all—right back to their normal physical state before the abnormality arose.

The beauty of the method is that, by adjusting the input waves to the rotating plasma, Prioré could “tailor” and “tune” the pumping waves to what was needed for a particular class of disease. He used trial and error methods to arrive at the proper settings for the disease to be treated. In theory, by the Prioré method one can time reverse any mass back to an earlier physical state. This mechanism is used by the cellular control portion of the body’s regenerative and restorative (R&R) system to restore damaged cells back to normal. It is the basis for the body’s ability to heal itself!

Applied to diseased cells, the method causes the formation of specific amplified antiengines for the exact specific cellular abnormality, no matter how complex, and no matter what it is. *In applied medicine this is a revolutionary new healing and therapeutic modality*, accomplished by novel EM means, and justified by general relativity, higher symmetry electrodynamics, and longitudinal EM wave pumping in the time domain rather than classical electrodynamics and transverse EM wave pumping. Prioré’s discovery, once understood, may just be the greatest medical discovery of all time, and the discoveries of Rife and of Becker may rank a close second. The Prioré process is shown in Figure 28.

The body's cellular regeneration system uses this same methodology and process. A block diagram of the operation of the body's cellular regeneration system is shown in Figure 29.

Further Principles Needed for Rife’s Microscope

In his microscope (Figures 1 and 2), Rife just wanted to observe the templates [2] corresponding to the cells, germs, viruses, etc. and all their parts, without any smallness limit. To do that, we need to (1) amplify the tiny, tiny amplitudes (actually, in the virtual state and subquantal) of the tiny vacuum engines accompanying tiny spatial locations containing living, functioning entities (no matter how small), and (2) "transduce" that amplified result into the optical spectrum, so that we see a perfect optical analog and thus are "looking" visually at localized ST regions far smaller than the one-tenth wavelength optical resolution limit.

We need another principle to do that. Suppose that, to first order, we have an isotropic nonlinear medium. Then if we transmit a sine wave into it, pandemonium sets loose with our wave. The speed of each part of the wave in this medium is a function of the location of that part upon the wave amplitude, so the peaks move faster than the intermediate parts of the wave of lesser magnitude. The wave has "peak overtake", breakup, collapse, and all sorts of things happening to it. So a simple sine wave is not going to pass smoothly into that medium and "pass back out" coherently and nicely, and ordinary light is not going to give stable reflections from that medium!

However, if we transmit *two* sine waves simultaneously, some frequency interval apart, and then if we *pretend* that we actually transmitted their *difference* frequency, a very strange thing happens. The two individual sine waves themselves still break up and go bananas. However, that difference frequency acts as if it were a simple sine wave transmitted into a *linear* medium! So we get back out a very nice, smooth, well-behaved sine wave of the *difference* frequency, even though terrible things happened to the individual waves themselves. We can detect and use that "difference frequency" nicely.

Several very neat sonar systems presently use that sort of transmission schema in underwater work { [95] }. The principle applies for waves of all frequencies, for all media which can be approximated as nonlinear isotropic in nature. As we shall see, it applies to the Rife microscope also.

Rife's Secret: Recursive Coherent Increase of the Signal-to-Noise Ratio (SNR)

To first order, without too much error we can pretend that the molecules and atoms etc. in the cells and body tissues, together with their finer components, comprise such an isotropic nonlinear medium. That's not entirely true, of course, but it does work to an extent sufficient for our purposes. Fortunately for the Rife process, the parts that *do not* obey this isotropic rule add randomly, while the parts that *do* obey the rule add coherently. So the "signal-to-noise ratio" (SNR) increases with the increasing amplification, and one "grows" the desired signal right up out of the noise (SNR) of the parts that do not obey the isotropic medium assumption. With sufficient number of amplifier stages, in theory the SNR of even the tiniest parts can be made as large as desired { [96] }.

With optical functioning as in Rife's microscope, one may substitute "light gathering power" or "magnification" for the electrical term "amplifier gain".

As we stated, Whittaker in 1904 (and superpotential theory thereafter) shows us that—if we wish—any EM field, wave, and pattern can be represented by two scalar potentials. Each of these two scalar potentials is further comprised of bidirectional EM longitudinal waves, in a harmonic series, in the Whittaker 1903 manner as reinterpreted. So we can reduce any pattern, field, or wave from any assemblage of charge sources, into two potentials, and then further into two sets of bidirectional EM waves interfering with each other. That process already *makes* all conventional EM waves, fields, etc.

An EM structuring of the local vacuum-spacetime occurs by all the electrical charges in the mass of the living cell, down to and including the virtual charges exchanged in the nuclear interactions in the nucleus of the atoms. By Whittaker 1903 and superpotential theory, all of that structuring itself is a potential with an internal set of bidirectional harmonic longitudinal EM waves interfering with each other.

Further this potential is recursively organized, because the inner bidirectional EM wavepair structuring of the potential is already recursive, as can be shown by applying Whittaker-1903 and Whittaker-1904 successively and iteratively { [97] }. This means we get deeper and deeper internested levels of patterns that still precisely correspond to the operational mechanisms of the lower levels. It's similar to an infinitely fractal { [98] } type of process.

Because this conglomerate is recursive as a function of harmonic intervals, it means that we can pick any harmonic interval we choose in the "big world" where we observe things, and we can have an exact observational representation of the dynamics of that ongoing hidden longitudinal EM wavepair interferometry in the two waves bounding that harmonic interval. Of course, the more additional harmonics we add, the better dynamics we have. The greater the number of harmonic intervals applied, the greater the gain. However, these harmonic intervals can be recursively applied using just one "macroscopic" harmonic interval, iteratively and serially applied over and over. The more iterative serial recursive application of one harmonic interval, the mote the "gain" or "amplification"—in the case of a microscope, the more the *amplification*. That was Rife's real secret, finally revealed. See Figure 30.

The Difference Frequency Provides Visible Output

Rife wanted to look at very, very small things *visually*, even though those “small things” were far below the one-tenth wavelength visible light barrier. In other words, to understand the Rife microscope’s visual representation of the virtual state, we need to choose the harmonic interval of the throughput so as to span the visible spectrum. Well, for optical purposes, luckily the IR and UV do exactly that. Examine the frequencies, and you will see that a harmonic interval exists from a spot in the IR to a spot in the UV, and of course the interval in between includes the entire visible spectrum. The visible spectrum in between, however, represents the observable noise that would block what we seek to have emerge in that region in our "Rife microscope", so the presence of the visible spectrum is highly undesirable. Various filters can be used to block the visible spectrum while transmitting the UV and IR regions, or one can just work in the dark or in suitably dim visible light.

Rife then applied his iterative multiple "difference frequency" lenses in serial order, one after the other. While it is doubtful that he understood the theoretical method being utilized, he certainly persisted and found how to use it. This method of iteratively summing a recursive virtual state vacuum engine "template" results in the formation of an observable state vacuum engine template. In short, it magnifies the virtual state entities and dynamics directly to observable state analogues that capture all the virtual state entities and their dynamics.

That is why, if we use special filters on your camera and flash lenses, where the filters are open in the IR and UV but opaque in the visible spectrum in between, we can often photograph the ongoing "longitudinal EM hidden biwave interferometry"—*the subtle energy or vacuum engine functioning*—of nature and of living systems, *even displaced in time*, as Trevor Constable { [99] } and Joe Gambill { [100] } (a researcher friend now deceased) demonstrated, as George Meek { [101] } demonstrated, and as Fogal { [102] } has successfully experimented with.

Occasionally when one gets things just right, one can get pictures of the subtle invisible reality in the virtual state, going on around oneself and in one's surroundings. With Rife-like iterative serial amplification, one can get them all the time, dependably, as with a Fogal semiconductor specially adapted for such operation. One can in fact build instruments that indirectly observe the so-called "unobservable" virtual energy state and its entities and dynamics with one-to-one correspondence.

That's a whole new "subtle physics" reality. Present physics with its assumed quantum observation limitations just has not even gone into it—primarily because physics has been focusing upon the quantized aspects of the photon (which is quantized in one aspect only—its magnetic vector potential—and not in its unquantized aspect—its scalar electrical potential!). Physics has rather ignored the unquantized (and therefore continuous from the smallest to the largest scale) time aspect of the photon { [103] }. Using the continuous aspect of the photon, one can assemble photon “time interval” structures—and in fact one does so whenever one assembles a 3-spatial energy density structuring such as in ordinary EM theory. Simultaneously, one has assembled a “structuring of the time domain” also, because each photon in the spatial energy density structuring consists of both time and energy as its canonical components.

All EM fields and waves, being comprised of photons, thus also carry (1) energy and energy internal structuring, and (2) time and internal time structuring. Again, this is the Russian *information content of the field*. The Russians simply understand 4-vector theory and Whittaker 1903 and 1904, and how to combine them with quantum mechanics and general relativity in a unified field theory.

The above explanation is why Kaznacheyev's { [104] } mitogenetic radiation { [105] } from his control (deliberately damaged or infected) cells would pass through a quartz window and induce the same damage (or disease) in targeted cells on the other side and otherwise environmentally shielded, but would not induce the changes through a normal window glass window. (See again Figure 23) Quartz passes the full optical spectrum from IR to UV, while window glass does not. So quartz passes the *vacuum engines* for the disease or damage, while window glass breaks them up and does not pass them as such. We stress that the vacuum engines are part of the “continuous” aspect of the photons, and so are not bound to any limitation on magnitude (either fineness or largeness) as are the quantized aspects of the photon.

For such a "far beyond the one-tenth wavelength" microscope as Rife’s, one must use vacuum engines (time domain structuring, and longitudinal EM waves) and extraordinary iterative unified field theory optics, rather than the ordinary transverse EM waves and ordinary optics. The lenses must all pass at least one harmonic interval (and the same one!), to provide and utilize the “difference frequency band” needed for recursive *visual* connection to the subquantal state (the hidden virtual structures in terms of the continuity aspects of photons). Successive stages thus "serial iteration" use the recursive principle to coherently amplify and show the vacuum engines, their dynamics, and the dynamics of deeper organizations and dynamics in the virtual state itself. Since Rife wished to “see” the results in the optical spectrum, then the two frequencies chosen for “differencing” had to bound the visible spectrum.

Rife used quartz lenses or at least very good optical glass that is open from IR to UV. That bounds the visible spectrum with a harmonic interval. Rife used multiple stages for successive coherent recursive amplification and increasing the SNR magnitude by coherent integration. One must also have some scheme for filtering out (or avoiding) too much visible spectrum light. One such scheme is to just use enough stages so that, in the new theory where the wavelength limitation is bypassed, one has amplified ("resolved") to the depth or fineness desired. The process long ago removed itself from the "normal visible light" domain, well before it reached the deeper resolution limit utilized by the definition state of the new method.

By using sufficient multiple stages in this fashion, the "tiny" virtual state vacuum engine templates passing through the IR-UV harmonic interval in a lens can be recursively summed and magnified many, many times—essentially without limit, because the phenomenon being magnified is recursive and bidirectional longitudinal in nature. It is definitely *not* normal visible light optics, and it *is not* conventional classical electrodynamics.

Rife’s Recursive “Vacuum Engine” Microscope

The Rife microscope coherently sums (and thus coherently amplifies) the virtual state vacuum engine patterns with the increasing number of stages. For the *subtle* vacuum engine templates, such an arrangement becomes a direct amplifier (magnifier), for amplifying (magnifying) the internested virtual state vacuum engine templates and their dynamic functioning, into the observable state. With a properly designed “vacuum engine” recursive microscope, one can see inside a molecule, inside the atomic nucleus, and even inside a nucleon, given development and perfection of the process. However, at this initial stage of understanding, one can forecast that finely adjusting the various stages of an early laboratory prototype would indeed prove to be a tedious and formidable task, just as Rife reported. With further development, however, that obstacle can be removed.

What comes out the output end of such a “vacuum engine” recursive microscope, is a direct visible light *analogue* of the much more subtle ST functioning in the microscope’s highly localized viewing area. This output imaging is put together "electrically" in ways analogous to the construction of a video picture on the screen of a TV tube. Since the result emerges through an output end that still passes an entire harmonic interval bounding the visible spectrum, the amplified virtual state recursive template is not destroyed but is highly amplified and produced as an observable image and dynamics in the visible spectrum. This final "interferometry" of two *internally structured* potential functions now produces "visible light" EM fields and waves and patterns, in accord with Whittaker 1904. These visible patterns are direct analogues representing exactly the very, very minute regions far below the one-tenth wavelength limitation of ordinary optical resolution. Those regions were the regions “being focused onto” when Rife so arduously “adjusted” his microscope's multiple stages.

With Rife’s recursive magnifying microscope process, one can see direct visible analogs of what is actually far, far smaller than anything ever before seen in normal optical microscopes, or even in electron microscopes etc. Indeed, one can see directly into the virtual state itself, and observe virtual state structures. While this is unthinkable in quantum mechanics if one considers only quantized aspects of light, it is perfectly feasible if one considers the concomitant unquantized (continuous) aspects of light, and shifts to general relativity and vacuum engines to utilize the unquantized structuring of the time domain.

Conclusion

Rife unquestionably found a way to produce visible recursive amplification and magnification of invisible virtual state dynamics and functions. We hope we have shed at least some light on the extraordinary technical mechanisms involved. This is good conceptual science, consistent with theory and some known experiments, and it certainly can be made a rigorous science and technology and mathematically modeled, using higher symmetry electrodynamics that is part of a unified field theory such as that of Sachs. The basis for all of it is in the literature already, but it is scattered widely in uncorrelated bits and pieces. It is not in the normal electrodynamics courses, nor is it in the normal optical science curriculum. And it is not taught in the normal physics curriculum. Needless to add, it is absent from the medical curriculum as well.

As an additional proposal, we tentatively suggest that this principle also may be the long-sought "hidden chaos" or "hidden order" in quantum mechanics that is known to be present, but has not yet been explained { [106] }. If so, then it becomes a new law of physics, with the experimental proof first demonstrated by Royal Raymond Rife.

With the conceptual technical matrix of Rife’s mechanism in hand, it should be possible for a proper scientific multi-disciplinary team to redevelop and extend the Rife microscope. Marvelous new instruments will emerge, once the quantum physics conceptual blockage of continuous physics is constrained to its place as only “one view of the physics reality elephant.” With the ability to directly “measure”, “observe,” and engineer the virtual state, a breathtaking expansion of physics will occur, dramatically extending the vacuum engineering suggested by Nobelist Lee.

If so, then Rife’s tragic life will have served its noble purpose, and his intuitive insight will have been resoundingly verified. The follow-on results will have untold benefit to science and to all the human generations to come.

NOTES AND REFERENCES

---

[1] For work on the theoretical aspects of this paper, partial financial support by A. Dreyer, R. Francis, H. Ledger, M. Peters, T. Craddock, and the Association of Distinguished American Scientists (ADAS) is gratefully acknowledged, as are helpful discussions with Dr. Bob Flowers and Dr. Myron Evans.

[2] We emphasize that Rife himself did not think in these terms.

---

[1] . (a) Some Rife-related references are: Royal R. Rife, "The filterable virus of carcinoma," Apr. 26, 1939; — "The Rife Microscopes," Apr. 28, 1939; — "Bacteria," Apr. 28, 1939; — "History of the development of a successful treatment for cancer and other viruses, bacteria, and fungi," Allied Industries, Dec. 1, 1953.

(b) Arthur Isaac Kendall and Royal Raymond Rife, "Observations on Bacillus Typhosus in its filterable state," California and Western Medicine, Ca. Med. Assoc., Dec. 1931.

(c) Arthur Isaac Kendall, "The filtration of bacteria," Science, Mar. 18, 1932.

(d) See particularly E. C. Rosenow, "Observations on filter-passing forms…," Proc. Staff Meeting of the Mayo Clinic, July 13, 1932; — "Observations with the Rife microscope of Filter-passing forms of micro-organisms," Science, Vol. 76, Aug. 26, 1932, p. 192-193; — "Microdiplococci in filtrates of natural and experimental poliomyelitic virus compared under the electron and light microscopes," Proc. Staff Meeting of the Mayo Clinic, 17(7), Feb. 18, 1942, p. 99-106; — "Observations of filter-passing forms of Eberthella Typhi (Bacillus Typhosus) and of the Streptococcus from Poliomyelitis," Proc. Staff Mtg.

Mayo Clinic 7, July 13, 1932, p. 408-413; — "Transmutations within the Streptococcus-Pneumonococcus Group," J. Infective Diseases, Vol. 14, 1941.

(e) R. E. Seidel and M. Elizabeth Winter, “The new microscopes,” Journal of the Franklin Institute, Feb. 1944, p. 103-129; — "Filterable bodies seen with the Rife microscope," Science Supplement, Science, Dec. 11, 1932, p. 10-11.

(f) "Is a new field about to be opened in the science of bacteriology?", Editorial, California and Western Medicine, Ca. Med. Assoc., Dec. 1931; "Powerful microscope makes very tiny objects visible," Science Newsletter, Vol. 33, Jan. 22, 1938, p. 55; "The Rife microscope or 'facts and their fate'," Reprint No. 4l7, The Lee Foundation for Nutritional Research, Milwaukee, Wisconsin, undated.

(g) A good lay overview is given by Christopher Bird, “What has become of the Rife microscope?”, New Age Journal, Mar. 1976.

(h) See also T. E. Bearden, AIDS: Biological Warfare, Tesla Book Co., 1988, p. 267-279. The author gives a short introduction to the Rife microscope and includes some pictures. The proposed evanescent wave explanation proved to be wrong. Much additional work by the author eventually culminated in the proposed mechanism presented in the present paper.

[2]. We have one viewgraph listing some 32 flaws, errors, and shortcomings of classical electrodynamics, and there are even more than that. Additional errors are listed, for example, by important scientists such as Feynman, Wheeler, Evans, Bunge, Cornille, Barrett, and others. So a substantial number of errors in classical U(1) EM theory are well known to foundations scientists. We discuss only a minimal few in this paper.

[3]. Mario Bunge, Foundations of Physics, Springer-Verlag, New York, 1967, p. 176.

[4] . *Ibid*., p. 182.

[5] . M. Faraday, Experimental Researches in Electricity and Magnetism. Vol. 1, Taylor and Francis, London, 1839.; Vol. 2, Richard & John E. Taylor, London, 1844; Vol. 3, Taylor and Francis, London, 1855. Reprinted by Dover in 1965. Also see M. Faraday, "On Static Electrical Inductive Action," Phil. Mag., 1843; — "Remarks on Static Induction," Proc. Roy. Inst., Feb. 12, 1858.

[6] . James Clerk Maxwell, Preface to the First Edition, A Treatise on Electricity and Magnetism, third edition, Vol. 1, Dover Publications, New York, 1954, p. viii-ix.

[7] . J. C. Maxwell, Preface to the First Edition, A Treatise on Electricity and Magnetism, third edition, Vol. 1, Dover Publications, New York, 1954, p. viii-ix. Quoting: "*…before I began the study of electricity I resolved to read no mathematics on the subject till I had first read through* Faraday's Experimental Researches in Electricity. *…I perceived that his method was also a mathematical one, though not exhibited in the conventional form of mathematical symbols. I also found that these methods were capable of being expressed in the ordinary mathematical forms….*"

[8] . James Clerk Maxwell, A Treatise on Electricity and Magnetism, Third Edition, Vol. 1, Dover Publications, NY, 1954, p. 165-166.

[9] . Else the precessing electrons in a signal-receiving wire antenna would not precess laterally. Since their precession is at right angles to the disturbing force, the disturbance arriving from the vacuum was a longitudinal disturbance. This also agrees with Whittaker's 1903 decomposition of the scalar potential, and Mandl and Shaw's note that the combined scalar photon and longitudinal photon are observable as the instantaneous scalar potential,

while neither of them is observable individually. See citations for Whittaker and for Mandl and Shaw elsewhere in these references.

[10]. This word "potentiality" (by Feynman) is given flesh and blood in the present paper. What actually exists in the vacuum is potential and structures of potential. Vacuum, spacetime, and potential are identities. Hence we may say that the structured vacuum potentials are indeed structurings of spacetime curvature. We refer to these as *vacuum engines*, which are explained in this paper.

[11]. Richard P. Feynman, Robert B. Leighton and Matthew Sands, The Feynman Lectures on Physics, Addison-Wesley, New York, Vol. II, p. 1-3.

[12]. This is easily shown. $F \equiv d/dt(mv)$, which expands to $F = (m)dv/dt + v(dm/dt)$. Let the mass m be zero continuously, and both terms on the right go to zero, hence $F = 0$. That is, the force disappears because mass is a component of force. It is the use in mechanics of the separate massless force acting on a mass that is the non sequitur and to blame for this giant error in electrodynamics as a hold-over from the hoary old mechanics theory.

[13]. J. D. Jackson, Classical Electrodynamics, Second Edition, Wiley, 1975, p. 249.

[14]. Jackson, ibid. p. 28.

[15]. Melba Phillips, "Classical Electrodynamics," Vol. IV: Principles of Electro-dynamics and Relativity, in Encyclopedia of Physics, Edited by S. Flugge, Springer-Verlag, Berlin, 1962, p. 4. Quoting: "The utility for electrical problems of a scalar potential, first introduced in the theory of gravitation, was pointed out by Simeon Denis Poisson, Bull. Soc.

Philomatheique **3**, 388(1813). See also Mem. Institut, Pt. **1**, 1, Pt. **2**, 163 (1811). The word *potential* was introduced by George Green in 1828."

[16] . E.g., see W. Misner, K. S. Thorne, and J. A. Wheeler, Gravitation, W. H. Freeman and Co., San Francisco, 1973, p. 5.

[17] . Two methods of dealing with this problem, and rectifying it, are the use of a topological definition of the fields in mass-free spacetime, and the use of a unified field theory where the "field in space" is not a forcefield per se, but merely a curvature or set of curvatures of spacetime. As an example, the O(3) electrodynamics largely pioneered by Evans takes the latter approach, and it is usable in directly engineering unified field theory effects.

[18] . (a). Mendel Sachs, The Field Concept in Contemporary Science, Charles C. Thomas Publishers, 1973;

(b) — General Relativity and Matter: A Spinor Field Theory from Fermis to Light-Years (Fundamental Theories of Physics), Reidel (now Kluwer), 1982 provides a great generalization of general relativity and electrodynamics reaching from the quarks and gluons to the entire universe. See also

(c) Mendel Sachs, Quantum Mechanics from General Relativity: An Approximation for a Theory of Inertia, Reidel (now Kluwer), 1986;

(d) — "Relativistic Implications in Electromagnetic Field Theory," in T. W. Barrett and D. M. Grimes, eds., Advanced Electromagnetism, World Scientific, 1995, p. 541-559. In the latter, Sachs shows that the most general expression for the field theory is in terms of spinor and quaternion variables, rather than the vector and tensor variables of the conventional expression of Maxwell's theory. This generalized expression leads to extra conservation laws and invariants, thus increasing the predictive capacity of the theory.

(e) For a marvelous treatise for the educated layman, see M. Sachs, Relativity in Our Time: From Physics to Human Relations, Taylor & Francis, 1993.

[19] . E.g., see the several Evans' reviews in Modern Nonlinear Optics, Second Edition, Edited by M.W. Evans, Wiley, 2002 (in press). Many other O(3) electrodynamics papers are also carried in this set of three volumes, as well as in the standard literature.

[20] . Mendel Sachs, "Relativistic Implications in Electromagnetic Field Theory," ibid.

[21] . Without interaction with the vacuum, mass does not exhibit perfect symmetry. For a discussion, see T. D. Lee, Particle Physics and Introduction to Field Theory, Harwood Academic Publishers, New York, p. 378-389.

[22] . In both classical and quantal electrodynamics, the problem of the source charge and its associated fields and potentials—and their energy—has been considered to be the most difficult problem.

(a) For a solution to that problem, see T. E. Bearden, "Giant Negentropy from the Common Dipole," Journal of New Energy, 5(1), Summer 2000, p. 11-23. On DoE open website http://www.ott.doe.gov/electromagnetic/papersbooks.html and this author's website www.cheniere.org.

(b) For very powerful support of that proposed solution, see F. Mandl and G. Shaw, Quantum Field Theory, Wiley, 1984, Chapter 5. Neither the time-polarized photon nor the longitudinal photon is individually observable, yet the combination of the two is observable as the instantaneous scalar potential. The Mandl and Shaw combination of a scalar (time-polarized) photon and a longitudinal photon is explained by Bearden as the interaction of the causal incoming scalar photon with a charge, the charge subsequently transducing the absorbed energy from the time-domain into 3-space, and re-emission of the energy as an emitted longitudinal photon in 3-space. The actual interaction provides the coupling, and clarifies which is the *cause* and which is the *effect*.

[23] . As the electrodynamicists implicitly assume, by assuming fields and potentials from all charges in the universe penetrating and existing and superposing and interfering in each cubic centimeter of space, and in fact at every point in space. But then the electrodynamicists continue to utilize a material ether assumption in their equations, embedded implicitly upon the notion of an "empty space" filled with this material ether. Tesla called it "*… one of the most remarkable and inexplicable aberrations of the scientific mind which has ever been recorded in history*." (Nikola Tesla, "The True Wireless," Electrical Experimenter, May 1919). While that biting remark certainly did not endear him to struggling electrical scientists, it did strike uncomfortably close to the mark, and it still does.

[24] . J. H. Poynting, "On the transfer of energy in the electromagnetic field," Phil. Trans. Roy. Soc. Lond., Vol. 175, Part II, 1885, p. 343-361.

[25] . Oliver Heaviside, "Electromagnetic Induction and Its Propagation," The Electrician, 1885, 1886, 1887, and later. This is a series of 47 sections, published section by section in numerous issues of The Electrician during 1885, 1886, and 1887. See also Oliver Heaviside, "On the Forces, Stresses, and Fluxes of Energy in the Electromagnetic Field," Phil. Trans. Roy. Soc. London, 183A, 1893, p. 423-480.

[26] . By a crude analogy, one may think of the "virtual" energy of the vacuum as energy that has been disintegrated into incredibly tiny bits—each so small that the bits fade in and out of existence at an incredible rate. The spinning action of the charge may be thought of as similar to that of an old spinning wheel. The charge spins, so that it coheres some of the "virtual fibers" continually fed to it by the vacuum, into "thread-sized" portions that are emitted radially outward. So the charge "splatters back" some of the fibers as fibers, but "spins" the remainder into useful quantum-sized "threads" which are emitted in observable form.

[27] . Presently electrodynamicists are likely to specify the Poynting energy flow **S** as **S** = **E**×**H**. However, in the vacuum (spacetime) neither **E** nor **H** exists as such *observed force fields,* which requires presence of charged mass. Only potentials and potential structuring of the virtual particle flux exist in the vacuum (which is after all just potential comprised of virtual particle flux). Those structurings or their analogues also exist as sets of curved spacetime regions (i.e., spacetime structurings comprising the elements of the "vacuum engine"). See E. T. Whittaker, "On the Partial Differential Equations of Mathematical Physics," Mathematische Annalen, Vol. 57, 1903, p. 333-355. Whittaker that any scalar potential decomposes into a multiplicity of longitudinal bidirectional flows of energy. This decomposition must also comprise the vacuum scalar potential, as well as the "spacetime curvature" potential.

[28] . However, Whittaker misinterpreted the *causal* phase conjugate wave (that half of his phase conjugate wavepair) as the *effect* after the wave interacts with charged mass, in which case parity is broken and the *effect* wave produced by the interaction is a longitudinal EM wave going in the opposite direction in 3-space from its "biwave" 3-space partner. The correct interpretation is that,

prior to interaction, the phase conjugate wave exists in the fourth axis of Minkowski 4-space, hence is in the time domain. It is literally a longitudinal EM wave moving on the fourth axis (in the time domain) to the interacting charge, and the other Whittaker biwave partner is the effect longitudinal EM wave emitted in 3-space by the interacting charge after it absorbs the incoming time-polarized EM wave. We point out that a longitudinal EM wave along the time axis is a time-polarized EM wave, corresponding to the known time-polarized photon in quantum field theory.

[29] . After publication of my "Giant Negentropy" paper, I discovered very strong support for my reinterpretation of Whittaker's 1903 decomposition of the scalar potential. This support was by F. Mandl and G. Shaw, ibid. Mandl and Shaw give a deeper coverage of the photon polarizations. They argue that the longitudinal and scalar polarizations individually are not directly observable, but only in combination, wherein they manifest as the "instantaneous" Coulomb (i.e., electrostatic) potential. Our comment is that this argument, translated from particle terminology to wave terminology, directly fits my re-interpretation of Whittaker's 1903 decomposition of the scalar potential. However, Mandl and Shaw fail to account for their assumed interaction of the detecting/observing unit point charge to perform the perfectly correlated "combining", and thus fail to account for the absorption of the incoming *causal* time-polarized wave or photon, the transduction of that excitation energy of the charge into longitudinal EM wave/photon energy in 3-space, and the subsequent emission of that excitation energy as a perfectly correlated longitudinal EM wave in 3-space.

Thus Mandl and Shaw missed the time-excitation charging of the source charge via absorption of the "coupled" time-polarized EM wave/photon, and the subsequent decay of the time-charge excited state by emission of a 3-space longitudinal EM wave/photon. This omitted interaction represents the discovery of nature's giant negentropy mechanism in EM energy flow, whenever 3-space energy flow symmetry is broken, as with a common dipole. So Mandl and Shaw do not account for photon (or wave) polarization transduction, where the "causal" time-polarized EM wave or photon comes in and is absorbed by the detecting charge or dipole to energetically excite it in the time-domain, then the excitation energy is re-emitted as the longitudinally polarized EM wave or photon in 3-space.

Recognition of these missing functions allowed at last a solution to the long-vexing problem of the source charge. We actually solved the problem for a source dipole, then pointed out that any "isolated" charge is a set of dipoles when its clustering virtual charges of opposite sign are considered.

[30]. The source charge problem was recognized as the most difficult problem in electrodynamics. E.g., see D. K. Sen, Fields and/or Particles, Academic Press, London and New York, 1968, p. viii. Quoting: *"The connection between the field and its source has always been and still is the most difficult problem in classical and quantum electrodynamics."* Since our proposed solution is consistent with particle physics (broken 3-symmetry of the dipole) and with quantum field theory (combination of the time-polarized and longitudinal photon comprises the scalar EM potential), it is robust and we believe it will stand up to meticulous scrutiny.

[31]. E. T. Whittaker, 1903, *ibid*.

[32]. Mandl and Shaw, *ibid*.

[33]. Poynting only assumed that diverged part of the energy flow. Heaviside, on the other hand, showed that there is a much larger energy

flow component that misses the intercepting charges (or circuit) altogether, and is wasted. Since this means that far more EM energy flows from the terminals of a generator than the external circuit intercepts and catches, it means that all generators produce more energy flow output than the textbook states, or that Poynting assumed. In fact, as *transducers of vacuum energy*, all dipolar generators already exhibit COP>1.0. Since no one in the 1880s could explain where such an astounding extra energy flow was coming from, Lorentz originated an integration trick to discard the nondiverged Heaviside EM energy flow component.

(a) See J. H. Poynting, “On the transfer of energy in the electromagnetic field,” Philosophical Transactions of the Royal Society of London, Vol. 175, Part II, 1885, p. 343-361.

(b) See Oliver Heaviside, "Electromagnetic Induction and Its Propagation," The Electrician, 1885, 1886, 1887, and later—a series of 47 sections, published section by section in numerous issues of The Electrician during 1885, 1886, and 1887.

(c) See also Oliver Heaviside, "On the Forces, Stresses, and Fluxes of Energy in the Electromagnetic Field," Phil. Trans. Roy. Soc. London, 183A, 1893, p. 423-480.

(d) For Lorentz' trick to discard the nondiverged component, see H. A. Lorentz, Vorlesungen über Theoretische Physik an der Universität Leiden, Vol. V, Die Maxwellsche Theorie (1900-1902), Akademische Verlagsgesellschaft M.B.H., Leipzig, 1931, "Die Energie im elektromagnetischen Feld," p. 179-186. Figure 25 on p. 185 shows the Lorentz concept of integrating the Poynting vector around a closed cylindrical surface surrounding a volumetric element. This is the procedure which arbitrarily selects only a small component of the energy flow associated with a circuit—specifically, the small Poynting component striking the surface charges and being diverged into the circuit to power it—and then treats that tiny component as the "entire" Poynting energy flow. Thereby Lorentz arbitrarily discarded all that extra Heaviside energy transport component which does not strike the circuit at all, and is just wasted.

[34] . In fact, the simple equation $W = \phi q$, where W is the diverged/collected energy, q is the intercepting coulomb, and ϕ is the reaction cross section of the potential, shows that electrodynamicists implicitly assume the “true” causal potential to contain unlimited energy. E.g., using that equation, any desired amount W of energy can be collected from any nonzero potential ϕ, no matter how small its intensity, simply by adding sufficient intercepting/collecting charges.

[35] . A back-of-the-envelope calculation for a nominal simple circuit has been made and previously presented by the present author. In the nominal circuit used, the source dipole extracts from the vacuum and sends down the outside of the attached circuit about 10^{13} times as much energy as the circuit itself intercepts, diverges, and utilizes. The huge remainder is not intercepted, remains nondivergent and just passes on out into space at the speed of light.

[36] . Solving the standard equation $\mathbf{E} = \mathbf{F}/q$ for **F**, one has $\mathbf{F} = \mathbf{E}q$. Again, from any nonzero **E**-field, no matter how small, as much force can be “gathered” and produced as one desires, merely by increasing the intercepting/collecting charge q.

[37] . Robert H. Romer, "Heat is not a noun," American Journal of Physics, 69(2), Feb. 2001, p. 107-109. This is an editorial discussion by the Editor of AJP of the concept of heat in thermodynamics. Heat is not a substance, not a thermodynamic function of state, and should not be used as a noun. The quotation castigating the standard "field diagram" of an EM wave in space is

from endnote 24, p. 109.

[38] . This is readily understood when one realizes that the founders of electromagnetics assumed a material ether. So to them, there was not a single point in all the universe where mass was absent! Hence the field, potential, and wave "in space" were actually the field, potential, and wave "in the material ether medium", and therefore perfectly material. Even though the Michelson-Morley experiments falsified the material ether in the 1880s, the electrodynamicists (i) never changed their classical EM equations which still to this day assume the material ether filling all space, and (ii) still implicitly mistake the transverse electron precession wave in the Drude gas in a receiving antenna as representing the assumed interception of the incoming "transverse EM wave" in that external material ether medium.

[39] . Robert Bruce Lindsay and Henry Margenau, Foundations of Physics, Dover Publications, New York, 1963, p. 283-287, and passim.

[40] . Y. Aharonov and D. Bohm, "Significance of Electromagnetic Potentials in the Quantum Theory," Physical Review, Second Series, 115(3), 1959, p. 485-491. However, Aharonov and Bohm seem to have missed the similar mass interpretation of the potential, so that they utilized the potential as massless and therefore the vacuum EM entity that is the primary cause of all EM phenomena. If one truly eliminates only the potential’s effect upon the intercepting charged mass, and utilizes the non-intercepted EM entity in vacuum, one has arrived at the direct alteration of the massless spacetime geometry of general relativity. In short, suddenly one has latched onto a unified field theory, and one that is engineerable by surprising electromagnetic means.

[41] . But erroneously assumed to be present, because of Maxwell’s ubiquitous use of the material ether and the continued implied material ether in the electrodynamics equations to this day.

[42] . T. W. Barrett, "Tesla's Nonlinear Oscillator-Shuttle-Circuit (OSC) Theory," Annales de la Fondation Louis de Broglie, 16(1), 1991, p. 23-41. Barrett analyzed Tesla's patented circuits in terms of quaternion electrodynamics, which is of higher symmetry than either vector or tensor algebra electrodynamics. Lo and behold, Tesla could shuttle potential energy around in his circuits at will, and that functioning would not even show up in a tensor or vector electrodynamic analysis.

[43] . T. W. Barrett, "Active Signalling Systems," U.S. Patent No. 5,486,833, Jan. 23, 1996; — Oscillator-Shuttle-Circuit (OSC) Networks for Conditioning Energy in Higher-Order Symmetry Algebraic Topological Forms and RF Phase Conjugation," U.S. Patent No. 5,493,691, Feb. 20, 1996.

[44] . As the reader can appreciate, this represents a dramatic change to the foundations of electrodynamics. It is closely allied to Sachs's unified field theory; see appropriate Sachs references in this paper.

[45] . As Dirac pointed out, the Michelson-Morley experiments of the 1880s destroyed the *material* ether assumed by Faraday and Maxwell and subsequent electrodynamicists; it *did not* destroy the ether per se. Dirac emphasized that any nonmaterial Lorentz-invariant ether is perfectly consistent with the Michelson-Morley experiments. General relativity describes the shaping and structuring of the vacuum as curvatures of spacetime geometry and clustered patterns thereof (although the latter part is essentially neglected). GR consists of the changes

of this spacetime due to the interaction of mass/trapped energy, and also the forces upon mass/trapped energy created by the interaction of such curvature-patterns of spacetime. Essentially, electrodynamics is missing just this "mass to spacetime" transform and this "spacetime to mass" transform. It is in fact missing its "infolded general relativity" dynamic internal structuring of the potential, field, and wave. KGB energetics weapon scientists call these missing transforms *the information content of the field*—which our fellows mistakenly interpret in their own flawed electrodynamics as "spectral content." Nothing could be further from the truth.

[46] . In 1903 E. T. Whittaker showed that any scalar potential is comprised of an infinite harmonic series of bidirectional longitudinal EM waves, arranged in bidirectional wavepairs. See E. T. Whittaker, "On the Partial Differential Equations of Mathematical Physics," Mathematische Annalen, Vol. 57, 1903, p. 333-355.

[47] . General relativity usually stops short of including an "infolded" topology within its basic spacetime, and only applies an "exterior" topology to it. However, it does not exclude that capability. Spacetime is just potential identically, and also just vacuum identically. Since GR omits the infolding structure of spacetime/potential, and so does electrodynamics, it has not been possible to unify the two completely. The "bridge" across the chasm between them has been eliminated by both disciplines.

[48] . With finite propagation, this action-at-a-distance is retarded so that some time passes between the effect and the cause. Each Mandl-Shaw photon interaction—the receipt of the scalar (time-polarized) photon, and emission of 3-space longitudinal photon—is retarded by (requires) the amount of time that is transformed into 3-space energy. [Time may be regarded as 3-space

electromagnetic energy compressed by the factor c^2, with the compressed energy placed on the fourth Minkowski axis to appear as time (seconds), rather than being left in 3-space to appear as mass).

Transformation from time-domain EM energy to 3-space energy is a function of the spin of the charge, which "spins" 720 degrees, being 360 degrees in the time domain while absorbing the time-polarized EM photon energy, the being followed by 360 degrees in 3-space while it is emitting the 3-space longitudinal photon. This retardation due to transformation of the energy from the time domain to the 3-space domain is what limits the speed of light in the ambient vacuum to the finite velocity c.

However, when infinite velocity propagation occurs (as is permissible with longitudinal EM waves alone, which a priori implies no retardation), then the notion vanishes of a “cause” and an “effect” separated by a time interval. In that case, one is operating in a multiply-connected spacetime, where in theory there is no observable “length” or “time” between the “cause” event and the “effect” event. Further, one “causative” initiation point can be superposed simultaneously with multiple distant points widely separated in ordinary spacetime. In that case, putting a joule of energy into the “initiating cause” point (to the normal 3-space observer) results in the simultaneous appearance at each and every distant participating point, of one joule. To the normal "singly-connected spacetime" observer, this is a direct amplification of energy, directly from the vacuum energy itself. We have proposed this mechanism as an extension of Bohm’s quantum potential utilized in his hidden variable theory of quantum mechanics. See David Bohm, "A Suggested Interpretation of the Quantum Theory in Terms of 'Hidden' Variables, I and II," Physical Review, 85(2), Jan. 15, 1952, p. 166-179 (Part I); 180-193 (Part II). Unfortunately three nations of the world have already seen fit to highly weaponize this effect, and a fourth nation is very close to deploying such a weapon. Presently quantum potential weapons are the dominant weapons on earth, and nothing can stand against them.

[49] . By conjugate pair, we mean that the wavepair consists of an EM longitudinal wave and its time-reversed twin, precisely superposed spatially but antiphased in time. In such a wave, the transverse energy density amplitude cannot vary; instead, the wave consists of (and carries) an oscillation of the rate of flow of time, about some median speed. The median speed of a longitudinal EM wave is not confined to the speed of light in vacuum.

[50] . The value of the energy continuously collected from a steady potential, in a "swirl" around a fixed intercepting charge, is of course a fixed scalar. That, however, has nothing to do with the nature of the potential as an EM entity in massless vacuum, prior to interaction with charged mass.

[51] . J. D. Jackson, Classical Electrodynamics, Second Edition, Wiley, 1975, p. 223.

[52] . Interestingly, one also cannot produce a clear definition of *energy* in physics. A good discussion of the energy concept is given by R. B. Lindsay, "The concept of energy and its early historical development." Foundations of Physics, 1 (4), 1971, p. 383-393. Lindsay investigates the concept of energy from its early historical origin, and covers from ancient times through the 18th century. The root of the concept is the notion of invariance in the midst of change. In short, the concept consists of considering "the changing" as being "nonchanging." In pursuing a rigorous definition of anything, one eventually arrives at a contradiction of Aristotelian logic. Ultimately one can only define something as identical to its own opposite. Geometry, e.g., models the presence of

mass as the absence of mass. Ultimately a "hard definition" is an "accursed necessity for the identity of opposites"—the centuries-old bane of the philosophers. In physics the problem is avoided by the "duality principle"—just treat an entity as either a particle or wave as necessary, and quit arguing about it! The problem is the incompleteness of Aristotelian logic itself. A solution to the "identity of opposites" problem is obtained by explicitly adding a fourth law of logic that has always been implicitly assumed in Aristotle's three laws. For a discussion, see "A Conditional Criterion For Identity, Leading to a Fourth Law of Logic," Appendix III to T. E. Bearden, Aids: Biological Warfare, Tesla Book Co., 1988, p. 428-443. A simple proof of the fourth law of logic is given in *ibid*., p. 439-440.

[53]. In addition to reference 19, see Myron W. Evans, Enigmatic Photon, Vol. II, Kluwer, ISBN 0792332881. See also Apeiron, 4(2-3), Apr.-Jul. 1997, a Special $B^{(3)}$ Field Issue, Guest editor: Myron W. Evans. In this same issue, see the Introduction by Evans, and also his "Helicity and the Electromagnetic Field." In the same issue, see also Jean-Pierre Vigier, "Relativistic Interpretation (with Non-Zero Photon Mass) of the Small Ether Drift Velocity Detected by Michelson, Morley, and Miller." Barrett has also rigorously shown the reality of the $B^{(3)}$ field, and so the conventional closure against it is doomed to failure. The emergence of $B^{(3)}$ field theory will dramatically alter electrodynamics, and elevate the importance of the longitudinal EM wave. We are also much indebted to Bob Flowers for his penetrating elucidation of the background of the $B^{(3)}$ field in private communications, and to Myron Evans for his patient and encouraging private communications.

[54]. See particularly T. W. Barrett, "Sagnac Effect: A Consequence of Conservation of Action Due to Gauge Field Global Conformal Invariance in a Multiply-Joined Topology of Coherent Fields," in T. W. Barrett and D. M Grimes, [Eds.], Advanced Electromagnetism: Foundations, Theory,

& Applications. World Scientific, River Edge, New Jersey, 07661, 1995, p. 278-313; T. W. Barrett, "Electromagnetic Phenomena Not Explained by Maxwell's Equations," in A. Lakhtakia, (ed.): Essays on the Formal Aspects of Electromagnetic Theory, World Scientific Publishing, River Edge, NJ, 1993, p. 6-86.

[55] . Richard W. Ziolkowski, "Exact Solutions of the Wave Equation With Complex Source Locations," Journal of Mathematical Physics, 26 (4), April 1985, p. 861-863; I.M. Besieris, A.M. Shaarawi, and R. W. Ziolkowski, "A bidirectional travelling plane wave representation of exact solutions of the scalar wave equation," Journal of Mathematical Physics, 30(6), 1989, p. 1254-1269; Rod Donnelly and Richard Ziolkowski, "A method for constructing solutions of homogeneous partial differential equations: localized waves," Proceedings of the Royal Society of London A., Vol. 437, 1992, p. 673-692; — "Electromagnetic field generated by a moving point charge: A fields-only approach," American Journal of Physics, 62 (10), Oct. 1994, p. 916-922.

[56] . M. W. Evans, editor, Modern Nonlinear Optics, Wiley, 2002, 3 volumes (in press).

[57] . W. A. Rodrigues Jr. and J.-Y. Lu, “On the existence of undistorted progressive waves (UPWs) of arbitrary speeds $0 \leq v < \infty$ in nature,” Foundations of Physics, 27(3), 1997, p. 435-508; W. A. Rodrigues Jr. and J. E. Maiorino, “A unified theory for construction of arbitrary speeds $(0 \leq v \leq \infty)$ solutions of the relativistic wave equations,” Random Operators and Stochastic Equations, Vol. 4, 1996, p. 355-400.

[58] . E. T. Whittaker, 1903, *ibid*.

[59] . Ironically, Maxwell’s actual theory was some 20 quaternion-like equations in 20

unknowns, as given in "A Dynamical Theory of the Electromagnetic Field," Royal Society Transactions, Vol. CLV, 1865, p 459. Read Dec. 8, 1864. Also contained in The Scientific Papers of James Clerk Maxwell, 2 vols. bound as one, edited by W. D. Niven, Dover, New York, 1952, Vol. 1, p. 526-597. Heaviside dramatically curtailed Maxwell's theory to a vector subset of some 4 equations in 4 unknowns. Lorentz further curtailed it by effectively throwing out all Maxwell-Heaviside systems that were in disequilibrium with their active vacuum and curved spacetime environments. So after over a century, the long slumbering *environmental* dynamics for electrodynamical systems is awakening and chasing its own roots again. Long live the rise of the supersystem!

[60]. E.g., see J. Vaz Jr. and W. A. Rodrigues Jr., "Maxwell and Dirac Theories as an Already Unified Theory," Advances in Applied Clifford Algebras, Vol. 7 (S), 1997, p. 369-386. See W. A. Rodrigues, Jr. and J. Vaz Jr., "Subluminal and Superluminal Solutions in Vacuum of the Maxwell Equations and the Massless Dirac Equation," Advances in Applied Clifford Algebras, Vol. 7(S), 1997, p. 457-466.

[61]. E. T. Whittaker, 1904, *ibid*.

[62]. We strongly stress that longitudinal EM waves and their dynamics, so ignored in all except the most advanced higher symmetry electrodynamics texts, are actually the key to everything. Longitudinal EM waves already comprise, create, and structure the feeble "envelope EM waves" we presently deal with. A longitudinal EM wave is also an electrogravitational wave, and oscillates the rate of flow of time itself because of its combination with a time-polarized wave. The two combined photons have a total spin two, which is a graviton. Thus internally a graviton is revealed as a particular

dynamic between time-domain EM energy and 3-space EM energy. The longitudinal EM wave in the time domain (that is combining with the longitudinal EM wave in 3-space) is thus an oscillation of time contraction and expansion, or "pulsation" in the rate of flow of time. Very powerful gravitational effects as well as very powerful and unique electrodynamics effects can be obtained by use of longitudinal EM waves, because of the additional dynamics between the time and 3-space domains. Unwitting use of such extraordinary EM waves is how Rife and Prioré achieved such remarkable results.

[63] . M. W. Evans, P. K. Anastasovski, T. E. Bearden et al., "On Whittaker's Representation of the Electromagnetic Entity in Vacuo, Part V: The Production of Transverse Fields and Energy by Scalar Interferometry," Journal of New Energy, 4 (3), Special Issue, Winter 1999, p. 76-78.

[64] . Melba Phillips, “Classical Electrodynamics,” Vol. IV: Principles of Electrodynamics and Relativity, in Encyclopedia of Physics, Edited by S. Flugge, Springer-Verlag, Berlin, 1962, p. 1-108 gives a good overall summary of the superpotential theory.

[65] . A. Righi, Nuovo Cimento, Vol. 2, No. 5, 1901, p. 104.

[66] . P. Debye, Ann. Phys., Leipzig, Vol. 30, 1909, p. 57.

[67] . Thomas John I'Anson Bromwich, An Introduction to the Theory of Infinite Series, MacMillan, London, 1908.

[68] . A. Nisbet, Physica, Vol. 21, 1955, p. 799; Proc. Roy. Soc. Lond. A, Vol. 231, 1955, p. 250.

[69] . W. H. McCrea, “Hertzian electromagnetic

potentials," Proc. Roy. Soc. Lond. A, Vol. 240, 1957, p. 447-457.

[70]. Sachs has achieved the necessary unified field theory, broadly unifying physics from the quarks and gluons to the entire universe, and including both the active vacuum and active, locally curved spacetime. See Mendel Sachs, General Relativity and Matter: A Spinor Field Theory from Fermis to Light-Years (Fundamental Theories of Physics), Reidel (now Kluwer), 1982; — Quantum Mechanics from General Relativity: An Approximation for a Theory of Inertia, Reidel (now Kluwer), 1986. It should be obvious that, unless electrodynamics theory and general relativity theory utilize the same background spacetime, it is impossible to completely merge them, from first principles. Since classical electrodynamics artificially discards its active environment, it is electrodynamics which must be changed in order to be successfully united with general relativity. Sachs has accomplished this long-sought *engineerable* unification.

[71]. Proof that the virtual state can be coherently integrated is already furnished by every source charge in the universe, which does precisely that.

[72]. We note without elaboration that all the mind functions, even of the deepest and most unconscious nature, and even of collective species unconsciousness domains—exist electromagnetically in the infolded EM domain. The "conscious mind" is a serial processor, though extremely rapid. The unconscious is a massively parallel processor. The reason the conscious mind cannot "directly see" the unconscious is that "seeing" innumerable things in the "single snapshot" at once, just obliterates all singular discrimination because of the intense summation. Mind functions are timelike, so consist of specialized structures, functioning, and dynamics

inside the time domain. Since the infolded structuring captures this entire domain, it also involves a physics of mind and matter interaction, but as a science instead of as a mysticism. In theory vacuum engines are also possible that engineer the mind at any and all levels. We have addressed this extended physics of mind and matter reactions elsewhere and do not address it here. The Russian weapon scientists refer to this mind area (which can also be engineered by novel electrodynamic means) as psychoenergetics.

[73] . R. O. Becker and David G. Murray, "The electrical control system regulating fracture healing in amphibians," Clinical Orthopaedics and Related Research, Vol. unk, No. 73, Nov.-Dec. 1970, p. 169-198. This is the definitive technical exposition by Becker of his electrical findings about the cellular control system.

[74] . See particularly Robert O. Becker, "The direct current control system. A link between environment and organism," New York State Journal of Medicine, Vol. 62, 1962, p. 1169-1176; — and Joseph A. Spadaro, "Electrical stimulation of partial limb regeneration in mammals," Bulletin of the New York Academy of Medicine, Second Series, 48(4), May 1972, p. 627-641; — and Carlton F. Hazlewood, Abraham R. Liboff, and Jan Walleczek, Electromagnetic Applications In Medicine," NIH-OAM Electromagnetics Panel Report, Jan. 15, 1993; — "A technique for producing regenerative healing in humans," Frontier Perspectives, 1(2), Fall/Winter 1990, p. 1-2; — and Andrew A. Marino. Electromagnetism and Life, State University of New York Press, Albany, NY, 1982; — and Gary Selden, The Body Electric, William Morrow and Company, New York, 1985; — Cross Currents, Jeremy P. Tarcher, Inc., Los Angeles, 1990; — "The bioelectric field pattern in the salamander and its stimulation by an electronic analog," IRE Transactions on Medical Electronics, Vol. ME-7, July 1960, p. 202-207; —

"Some observations indicating the possibility of longitudinal charge-carrier flow in peripheral nerves," Biological Prototypes and Synthetic Systems, Plenum Press, New York, 1962, p. 31-37; — and W. Slaughter, "The longitudinal direct current gradients of spinal nerves," Nature, Vol. 196, Nov. 17, 1962, p. 675-676; — and Charles H. Bachman and Howard Friedman, The direct current (control) system: A link between the environment and the organism," New York State Journal of Medicine, Vol. 62, April 15, 1962, p. 1169-1176; — "The direct current field: A primitive control and communication system related to growth processes," Proceedings of the. XVI International. Congress of Zoology, Washington, D.C., Vol. 3, 1963, p. 179-183; — "The neutral semiconduction control system and its interaction with applied electrical current and magnetic fields," Proc. 11th International. Cong. Radiol., Amsterdam, Excerpta Medica Foundation, 1966, Series 105, p, 1753-1759; — "The bioelectric factors in amphibian limb regeneration," The Journal of Bone and Joint Surgery, Vol. 43-A, No. 5, July 1961, p. 643-656; — and David G. Murray, "A method for producing cellular dedifferentiation by means of very small electrical currents," Transactions, New York Academy of Sciences, 29(5), Mar. 1967, p. 606-615.

[75] . The ultimate tool for use in seeing and working with this "infolded" or "internal electrodynamics inside normal EM fields, waves, and potentials will probably be the Fogal semiconductor when it goes into production in the near future. Fogal's transistors are capable of (1) infolding the desired longitudinal EM waves inside normal EM signals (he demonstrates infolding TV signals inside pure DC potentials, and transmitting them over conductors as pure DC potentials for appreciable distance, then using his semiconductors to again extract the "infolded" hidden TV signals.

[76] . See Vlail Kaznacheyev, "Electromagnetic

Bioinformation in Intercellular Interactions," Psi Research, 1(1), Mar. 1982, p. 47-76; — *et al.*, "Distant intercellular interactions in a system of two tissue cultures," Psychoenergetic Systems, 1 (3), Mar. 1976, p. 141-142; "A Comment" by William A. McGarey, p. 143; "A Comment" by Arthur C. Hastings, p. 143-144, — *et al.*, "Apparent information transfer between two groups of cells," Psychoenergetic Systems, 1(1), Dec. 1974. See particularly Vlail P. Kaznacheyev and L. P. Mikhailova, Ultraweak Radiations in Intercellular Interactions [in Russian], Novosibirsk, 1981; "Electromagnetic Bioinformation in Intercellular Interactions," Novosibirsk, 1981 [in Russian]; V. P. Kaznacheyev, "Information Function of Ultraweak Light flows in Biological Systems," Problems in Biophysics, Novosibirsk, 1967, p. 7-18 [in Russian].

[77]. Some years ago we documented this disease-inducing "microwave radiation of the U.S. Embassy, explained its purpose and operational mechanism, and published it. E.g., see T. E. Bearden, AIDS: Biological Warfare, Tesla Book Co., Chula Vista, CA, 1988.

[78]. See Robert C. Mallieu, A Model of the Microwave Intensity Distribution Within the U.S. Embassy, Moscow 1966-1967, Report FS-80-166, Applied Physics Laboratory, Johns Hopkins University, Baltimore, Maryland, Aug. 1980. Also see Microwave Radiation at the U.S. Embassy in Moscow and Its Biological Implications: An Assessment, U.S. Department of Commerce, Doc. # NTIA-SP081-12, Mar. 1981. Also see Captain John D. LaMothe, Controlled Offensive Behavior—USSR, Report ST-CS-01-169-72, Defense Intelligence Agency, Washington, D.C. (released under FOIA). See also Captain John D. LaMothe and Mr. Louis Maire, Soviet and Czechoslovakian Parapsychology Research, Report DST-1810S-387-75, Defense Intelligence Agency, Washington, D.C. (Released under FOIA).

[79] . T. E. Bearden, "EM Corrections Enabling a Practical Unified Field Theory with Emphasis on Time-Charging Interactions of Longitudinal EM Waves," Journal of New Energy, 3(2/3), 1998, p. 12-28. A slightly updated and extended version is published in Explore, 8(6), 1998, p. 7-16.

[80] . C. W. Misner, K. S. Thorne and J. A. Wheeler, Gravitation, W.H. Freeman and Co., San Francisco, 1973, p. 5, 19-21, 71-72, 163-165, 390-391, 399; 367-369.

[81] . T. D. Lee, Particle Physics and Introduction to Field Theory, Harwood, New York, 1981. See particularly Chapter 25: Outlook, "Possibility of Vacuum Engineering," p. 824-828.

[82] . David J. Bohm, "A Suggested Interpretation of the Quantum Theory in Terms of 'Hidden' Variables, I and II," Physical Review, 85 (2), Jan. 15, 1952, p. 166-179 (Part I); 180-193 (Part II).

[83] . I.e., the rate of flow of time, or more specifically, the rate of the EM interactions with a mass or particle that generate the flow of the mass or particle through time. See Figure 25. Nobelist Lee has also shown that time is a discrete dynamical variable across all of physics, from quantum mechanics to nonrelativistic field theory, to relativistic quantum field theory. See T. D. Lee, "Can Time Be a Discrete Dynamical Variable?", Physics Letters, 122B(3, 4), Mar. 10, 1983, p. 217-220. Also in T. D. Lee, Selected Papers, Gerald Feinberg, Ed., Birkhauser, Boston, 1986, Vol. 3, p. 77-80. So we have not hesitated to consider time as any other variable, and the fourth Minkowski axis as any of the other three axes with respect to EM energy, fields, potentials, and waves.

[84] . Indeed, there is no such unique thing as “the gravitational field” anyway! The gravitational field is a conglomerate of other field energies and

functions, not a separate field of nature. See A. A. Logunov and Yu. M. Loskutov, "Nonuniqueness of the predictions of the general theory of relativity," Sov. J. Part. Nucl., 18(3), May-June 1987, p. 179. See C. W. Misner, K. S. Thorne and J. A. Wheeler, Gravitation, W.H. Freeman and Co., San Francisco, 1973, p. 399. Quoting*: "The terms 'gravitational field' and 'gravity' refer in a vague, collective sort of way to all of these entities. Another, equivalent term for them is the 'geometry of spacetime'.“* See also A. D. Sakharov, "Vacuum Quantum Fluctuations in Curved Space and the Theory of Gravitation," Soviet Physics Doklady, Vol. 12, No. 11, 1968, p. 1040-1041 [English translation.]. Finally, see our remarks under reference 62 above, particularly with respect to the proposed internal electromagnetic dynamics of the graviton.

[85] . A 1993 study by the Office of Technology Assessment, delivered to Congress, showed that a single terrorist in a small plane, with a tank of anthrax spray, and dispersing the spray as he flew around the greater Washington D.C. area on a calm night, would produce between 1 and 3 million casualties. Most of those casualties would die. So a single biological warfare (BW) strike in one U.S. metropolitan area could easily kill two million Americans. As an example, Saddam Hussein is known to have the terrorist teams and the anthrax, and he has had a decade since the Gulf war to insert additional teams and biological warfare agents into the U.S. Presently this is rated by our government as the strongest strategic threat to the U.S., after which comes nuclear strikes, followed by chemical agent strikes. Redevelopment of the Prioré approach, e.g., could easily save the lives of 90% of that nominal two million dead Americans. As matters stand now, triage would apply and almost all of those two million stricken Americans would die.

[86] . In 1998 we proposed a crash development of this kind of device in 1998, with copies to DoD,

NIH, CDC, the USAF, etc.; in T. E. Bearden, Energetics: Extensions to Physics and Advanced Technology for Medical and Military Applications, CTEC Proprietary, May 1, 1998, 200+ page inclosure to CTEC Letter, “Saving the Lives of Mass BW Casualties from Terrorist BW Strikes on U.S. Population Centers,” to Major General Thomas H. Neary, Director of Nuclear and Counterproliferation, Office of the Deputy Chief of Staff, Air and Space Operations, HQ USAF, May. 4, 1998. Also to Gen. (Ret.) Walter Busby, Deputy Secretary of Defense for Counterproliferation and Chemical and Biological Defense, March 21, 1998. Also to NIH, CDC, and several other U.S. government agencies.

DoD replied that it was not documented in the literature (a specific list of exact scientific papers reporting the results of the Prioré team's experiments and the experiments of Becker was included; no one seemed to read it). CDC and the USAF did not reply. NIH first responded (from its Policy section—read, *spin control* section) that, since I mentioned the cause of the Gulf War Disease and how it was induced, it was not a matter of their interest but of DoD's interest, and so they just shipped it to DoD and got rid of it. A second response evoked from NIH on query from my congressman (again, a response from their *policy* section) directed me to their proposals section. I don't believe a single qualified scientist even read it. DoD weakly replied that it was not documented in the literature (a specific list of citations from the hard French scientific literature, reporting the astounding results of the Prioré treatments, was included, which apparently no one read).

Not a single scientist from any agency called me to discuss the revolutionary and proven results obtained by Prioré, and documented in the attachments and in the cited literature. Sadly, it seems that no one had the foggiest notion what I was talking about, and no one much cared. My conclusion was and is that my own government bureaucrats do not give a tinker's dam about saving millions of American casualties in the coming debacle, *if it has to be done by "out-of-the-box" methods not approved by the big drug industry*. Yet these are the same officials that readily admit the exact threat I referred to, admit that it is a matter of *when* the biological warfare attacks will occur and not *if*, and admit that right now they have no effective way to cope with it or save most of those coming millions of Americans that are going to just be dragged aside to die.

My response is that the American taxpayers are certainly not getting their money's worth from the billions they shower on our medical research community. It is unconscionable to ignore for over 30 years the demonstrated and astounding results achieved by eminent French scientists—such as Pautrizel, a world-renowned parasitologist and Courier, head of the French Academy's Biological Section, and also *Secretaire Perpetuel* of the Academy) working with the Prioré team, in curing terminal tumors etc. in thousands of lab animals, all properly documented in the hard French scientific literature.

In my view, considering the certainty of those future American mass deaths, it is akin to high treason. Whether our scientific community realizes it or not, today's strategic war of massive strategic strikes has shifted to our civilian populace, and to our cities and mass population centers. It is our civilian populace that will sustain the greatest and most prompt casualties, and probably will receive the first massive strikes, totally by surprise.

The first phase of WW III—delivery of the strategic weapons to their strategic targets—has already been accomplished. Large Russian nuclear weapons are already hidden in our major cities and population centers (read Lunev's book, he tells us how they brought in these weapons), the Spetznaz teams are here to detonate them on call, multiple nations such as Iraq, Libya, and Iran already have terrorists agents in country in the U.S. with anthrax and smallpox in hand to be released, and Castro guerrillas and trained saboteurs have been trained in Southern Mexico and infiltrated across the border into the U.S. for decades.

Whether they like it or not, U.S. scientists have thus become the major front line "soldiers" and "defenders" of our nation. And frankly, they have failed abominably in their responsibility, and most do not seem to care. For a startling and even shocking characterization of our present scientific community, the reader is referred to Daniel S. Greenberg, Science, Money, and Politics: Political Triumph and Ethical Erosion, University of Chicago Press, 2001.

[87]. As we stated, just such an attack is now officially the greatest strategic threat to the United States. Second is a nuclear attack, followed by chemical attack as a distant third. E.g., see Richard K. Betts, “The New Threat of Mass Destruction,” Foreign Affairs, 77(1), Jan./Feb. 1998, p. 26-41. For the ineffectiveness of our defenses against the coming mass biological warfare strikes, see Laurie Garrett, The Coming Plague: Newly Emerging Diseases in a World Out of Balance, Farrar, Straus and Giroux, New York, 1994; — "The Nightmare of Bioterrorism," Foreign Affairs, 80(1), Jan./Feb. 2001, p. 76-89; — Betrayal of Trust: The Collapse of Global Health, Hyperion, New York, 2000.

[88]. Becker, *ibid*.

[89]. A full account of the entire Prioré affair is given in Jean-Michel Graille, Dossier Prioré: Une Nouvelle Affaire Pasteur [The Prioré Dossier: A New Pasteur Affair?], De Noel, Paris, 1984. [in French]. A summary account is given by Christopher Bird, "The Case of Antoine Prioré and His Therapeutic Machine: A Scandal in the Politics of Science," Appendix I in T.E. Bearden, AIDS: Biological Warfare, Tesla Book Co., P.O. Box 121873, Chula Vista, California 91912, 1988. Prioré's doctoral thesis (in my personal possession courtesy of Professor Courrier and the late Chris Bird), was rejected by the University of Bordeaux

when the French government suppressed the Prioré program in the mid-70s; it is A. Prioré, Guérison de la Trypanosomiase Expérimentale Aiguë et Chronique par L'action Combinée de Champs Magnétiques et D'Ondes Electromagnétiques Modulés. [Healing of intense and chronic experimental trypanosomiasis by the combined action of magnetic fields and modulated electromagnetic waves], 1973. Prioré's patents are: A. Priore, "Apparatus for producing radiations penetrating living cells," U.S. Patent No. 3,368,155, Feb. 6, 1968; — "Method of producing radiations for penetrating living cells," U.S. Patent No. 3,280,816, Oct. 25, 1966; — "Procede et dispositif de production de rayonnements utilisables notamment pour le traitement de cellules vivantes," [Procedure and Assemblage for Production of Radiation Especially Serviceable for the Treatment of Living Cells], Republique Francais Brevet d'Invention P.V. No. 899.414, No. 1,342,772, Oct. 7, 1963. Eleven years after Priore's thesis was rejected, the same university awarded a doctoral thesis to a young graduate. It is Eric Perisse, Effets des Ondes Electromagnètiques et des Champs Magnètiques sur le Cancer et la Trypanosomiase Experimentale [Effects of Electromagnetic Waves and Magnetic Fields on Cancer and Experimental Trypanosomias], Doctoral thesis, University of Bordeaux No. 83, March 16, 1984.

[90] . F. A. Popp *et al.*, "Biophoton Emission (Multi-Author Review)," Experientia, Vol. 44, 1988, p. 543-600; — "Biophoton emission: New evidence for coherence and DNA as a source," Cell. Biophys., Vol. 6, 1984, p. 33-52; — "Physical aspects of biophotons." Experientia, Vol. 44, 1988, p. 576-585; — Recent Advances in Biophoton Research and its Applications, World Scientific Publishing Co., New York, NY, 1992; F. A. Popp, "Photon Storage in Biological Systems," in Fritz Albert Popp *et al.*, eds., Electromagnetic Bio-Information: Proceedings of the Symposium,

Marburg, Federal Republic of Germany, Sep. 5, 1977; Urban & Schwarzenberg, Baltimore, 1979, p. 123-149.

[91] . David M. Rorvik, "Do the French have a Cure for Cancer?", Esquire Magazine, July 1975, p. 110-111, 142-149.

[92] . Arguably the best introduction to nonlinear optical phase conjugation is David M. Pepper, "Nonlinear Optical Phase Conjugation," Optical Engineering, 21(2), March/April 1982, p. 156-183. Another very good presentation is Amnon Yariv, Optical Electronics, 3rd Edition, Holt, Rinehart, and Winston, New York. 1985, Chapter 16: “Phase Conjugate Optics – Theory and Applications.”

[93] . A beautiful example of this “precise backtracking” of the time-reversed wave is given in David M. Pepper, "Applications of Optical Phase Conjugation," Scientific American, 254(1), Jan. 1986, p. 74-83. See particularly the striking photographic demonstration of time reversal of disorder on p. 75.

[94] . We presented some general elements of this dramatic new extension to nonlinear optical phase conjugate pumping and to general relativity, at a graduate seminar, “On the Theory and Principles of EM Systems with COP>1.0”, given to interested graduates and faculty of the University of Louisville, on Nov. 20, 1997.

[95] . E.g., see Owen Flynn, "Parametric arrays: A new concept for sonar," Electronic Warfare Magazine, June 1977, p. 107-112.

[96] . This method of increasing signal-to-noise ratio and pulling hidden signals right up out of the noise, is widely used in signal processing in modern radars. Often signals buried more than 100

dB below the noise level are routinely "pulled out of the noise" and detected, using various forms of coherent summation.

[97] . Any potential decomposes into multiple wavepair sets. In each hidden wavepair, each of the two waves further decomposes into two potentials. Each of *those* potentials then further decomposes into multiple wavepair sets. And so on *ad infinitum*. Or one can start with any wave, decompose it into two potentials, each of those potentials into multiple biwave sets, and so on.

[98] . "Fractal" means self-similarity at all levels, so that patterning or "decomposition" at one level is similar to that at the higher and lower levels. For good overview discussions and applications, see particularly Gregoire Nicolis, "Physics of far-from-equilibrium systems and self-organization," and Joseph Ford, "What is chaos, that we should be mindful of it?", both in The New Physics, Paul Davies, editor, Cambridge University Press, Cambridge and New York, 1989, p. 316-347 and 348-371 respectively. More detailed technical references are cited in each article.

[99] . See Trevor James Constable, "You, Too, Can Photograph UFOs from Airliners," Psychic Observer and Chimes, 37(3), May-June 1977; — The Cosmic Pulse of Life, Merlin Press, Santa Ana, CA, 1976.

[100] . The present author has two beautiful ultraphotographs taken by Joe Gambill using the special filtering approach. One is a photograph of a room, but with its contents of *two weeks earlier*, showing the room prior to the time the photograph was taken. The other is of a "ghost" form—very similar to a photograph obtained by George Meek under rigorous laboratory conditions—and clearly showing the energy form of a "haunted" lady's dead husband. The *interpretation* of these photographs

is of course open to scientific dispute, but the *photographs themselves* are impeccable and real.

[101] . Meek used filters open to UV and IR but opaque to the visible spectrum, on the fluorescent lights in his laboratory. He also used similar filtering on the camera lenses and camera flashes. Under rigorous laboratory conditions, in several thousand photos of the living body Meek was able to take a few highly anomalous photos completely inexplicable by normal science. E.g., he photographed a purported "ghost" and obtained a clear shot of energy streaming associated with a living person. He also photographed the legs of a chair, right through the suddenly "missing" legs of the person sitting in the chair. Again, interpretation is open to dispute, but the photographs are rigorous and real.

[102] . Bill Fogal's patented charge-blocking semiconductor—U.S. Patent Numbers 5,196,809 and 5,430,413—is capable under certain circumstances—and by clever adaptation—of amplifying virtual state information, in a manner somewhat similar to Rife's methodology, but far more easily engineered. When the process works, Bill reports that a clear photograph or video camera shot can be taken right through a solid brick wall, of the hidden scenery beyond. In electrodynamics, in a dielectric absorbing or emitting EM radiation (energy), the entire dielectric participates in each absorption and emission. Emitted light from an object thus carries an astoundingly complete set of little virtual state vacuum engines rigorously representing every part of the object, no matter how small, and all the internal dynamics. This means that the light from the scene beyond the wall strikes the wall on the other side, affecting all the material in the wall, including upon the observer's side, and inserting "dimensioning" from the scene beyond the wall. When light is emitted from the observer's side, the information content of the field representing the scene on the far side, is also part of

the information content of the field in the light emitted from the observer side of the wall and striking the camera and the observers eyes. This “dimensioning” continues in the signals in the camera and on through attached electronic circuitry. Since Fogal’s semiconductor can process such information content of the field in the proper circuitry and under favorable circumstances, the phenomenon is therefore permissible and can be technically explained. Using his transistor to transduce the dimensioned information into the visual band, Fogal *can* view a distant scene right through an intervening wall, when he gets everything “just right.” At this stage of development, however, the process and adjustment are difficult, just as Rife experience with his microscope. We are convinced that the forthcoming advent of Fogal semiconductors will revolutionize the study and treatment of disease and bodily disorders.

[103] . However, highly advanced electrodynamics does consider the photon with far greater complexity than nuclear engineers such as the present author were introduced to! E.g., a deep discussion of photon polarization is given in F. Mandl and G. Shaw, Quantum Field Theory, Wiley, 1984 under the heading "covariant quantization of the photon propagator" in Chapter 5. As pointed out by Bob Flowers in a private communication, Mandl and Shaw argue that the longitudinal and scalar polarizations are not directly observable, but only in combination, where the combination manifests as the "instantaneous" Coulomb (i.e., electrostatic) potential. Most such books do argue that the extra components of the photon remain hidden, as does the virtual state. In this paper we have revealed how Rife discovered a process by means of which the virtual state can be observed in great detail.

[104] . V. P. Kaznacheyev, "Electromagnetic Bioinformation in Intercellular Interactions," Psi

Research, 1(1), Mar. 1982, p. 47-76; — "Information Function of Ultraweak Light Flows in Biological Systems," in Problems in Biophysics, Novosibirsk, 1967, p. 7-18 [in Russian]; — and L. P. Mikhailova, Ultraweak Radiation in Intercellular Interactions, [in Russian], Novosibirsk, 1981; — *et al*., “Apparent information transfer between two groups of cells,” Psychoenergetic Systems, 1(3), Mar. 1976; — *et al*., "Distant intercellular interactions in a system of two tissue cultures," Psychoenergetic Systems, 1(3), Mar. 1976, p. 141-142; "A Comment" by William A. McGarey, p. 143; "A Comment" by Arthur C. Hastings, p. 143-144.

[105] . Mitogenetic radiation was studied prior to WW II by Gurwich (spelling varies). See A. Gurwitsch and L. Gurwitsch, "L'Analyse mitogenetique spectrale [The Analysis of the mitogenetic spectrum]," in Andre Mayer, Exposés de Physiologie, [Studies in Physiology], Hermann & Cie, Paris, 1934. Part IV. [In French]. Studies have continued by Popp and others. E.g., see F. A. Popp *et al*., "Biophoton Emission (Multi-Author Review)," Experientia, Vol. 44, 1988, p. 54 3-600; — "Physical aspects of biophotons." Experientia, Vol. 44, 1988, p. 576-585; — "Biophoton emission: New evidence for coherence and DNA as a source," Cell. Biophys., Vol. 6, 1984, p. 33-52. See Fritz Albert Popp; Ke-hsueh Li, and Qiao Gu, [eds.], Recent Advances in Biophoton Research and its Applications, World Scientific Publishing Co., New York, NY, 1992.

[106] . The conventional quantum mechanics assumes that, at the microscopic level, variation (e.g., in the probabilities assigned to interpret what is propagating in the Schrödinger equation) is assumed to be random. However, there is a problem. Big things must be made of little things. If we sum a set of "random" things based on Gibbs thermodynamics statistics, we cannot and will not get an organized "big thing" because we have

assumed total disorder (randomness) *a priori*. Adding heat does not produce cooling! So one falsifies the prevailing interpretation of quantum mechanics, whenever one observes a tree, a flower, the sun, or a human being. In short, there must exist a great unifying principle in nature of a coherent summation, from the "unobservable" virtual state to the observable state. Only in that fashion can there be an macroscopic order at all—and such macroscopic order is universally observed. We believe that the principle we have elucidated, as experimentally produced by Rife, may well be that long-sought universal ordering principle that is so sorely needed by quantum mechanics. Readers interested in the "missing quantum chaos" problem are referred to P. V. Elyutin, "The Quantum Chaos Problem," Sov. Phys. Usp., Vol. 31, No. 7, 1988, p. 597-622. Elyutin discusses the crisis in quantum mechanics because of the missing hidden order. Quantum mechanics is known to be wrong unless this order can be found, because otherwise it does not predict the ordered macroscopic universe. Other useful references are Ilya Prigogine, with T. Petrosky, "Quantum Chaos, Complex Spectral Representation and Time-Symmetry Breaking," Chaos, Solitons, and Fractals, Vol. 4, 1994, p. 311-359; and Robert Pool, "Quantum Chaos: Enigma Wrapped in a Mystery," Science, 243(4893), 1989, p. 893-895.

Slide Index

Figure 1. The Rife microscope.

Figure 2. Royal Raymond Rife adjusts his microscope.

Figure 3. Faraday omitted the string holder for his taut string, thus omitting half the electrodynamics and half the energy. An equal-and-opposite Newtonian third law reaction wave always appears in our transmitters and receivers, caused by the omitted wave.

Figure 4. Drude gas gyroelectrons in the receiving antenna precess laterally, providing the detected transverse wave and proving the vacuum disturbance wave to be longitudinal.

Figure 5. The magnitude of the causal potential in massfree space is erroneously defined.

Figure 6. Fields and potentials are erroneously defined as what is diverted from them.

Figure 7. The defined magnitude of the field is erroneous and is the field intensity.

Figure 8. Matter-to-matter transform.

Figure 9. The missing matter-to-spacetime and spacetime-to-matter transforms.

Figure 10. Vacuum engine utilization.

Figure 11. A charge is continuously in violent energy exchange with the active vacuum.

Figure 12. Whittaker's biwave decomposition of the scalar potential, and its reinterpretation.

Figure 13. The Supersystem and its components.

Figure 14. Vacuum engine (cartoon representation).

Figure 15. First vacuum engine analogy of arm muscle and bone.

Figure 16. Second vacuum engine analogy of arm bone and muscle.

Figure 17. Third vacuum engine analogy.

Figure 18. Fourth vacuum engine analogy.

Figure 19. Time-like flow of EM energy into 3-space.

Figure 20. Block diagram of the immune system.

Figure 21. Becker's electromagnetic healing of otherwise intractable bone fractures.

Figure 22. Becker's block diagram of the cellular control system.

Figure 23. Kaznacheyev's electromagnetic induction of cellular death and disease, at a distance.

Figure 24. Microwave radiation of the U.S. Embassy in Moscow.

Figure 25. Mechanism generating the flow of a mass through time.

Figure 26. Vacuum antiengine for a specific disease condition.

Figure 27. Pumping with transverse and longitudinal EM waves.

Figure 28. Block diagram of the Prioré process.

Figure 29. Block diagram of the operation of the body's cellular regenerative system.

Figure 30. Rife's great secret: Recursive iterative serial amplification by a single harmonic interval difference frequency.

Help support this work

The Tom Bearden Website

Rife's Microscope

Table of Photographs

(Thanks to the donor of these photographs, who wishes to remain anonymous)

1. Rife's Universal Microscope
2. Eyepiece Details
3. Chart for Calculating Parallax of Lens System
4. Diagram - Wide Angle Apochromatic Microscope Objective Lens
5. Universal Focus - Photographic Lens
6. Light Passage of Dove Prism



Figure 1. Rife's microscope.







Figure 2. Royal Raymond Rife adjusts his microscope.



Air medium disturbances generated when air is perturbed by a plucked taut string

The string wave and the holder wave never leave the string and holder respectively.

String slaps air medium
WAVE IN STRING (TRANSVERSE)
Lower degree of freedom for string.
Can only vibrate mostly laterally.
Wave is alternatively compressive and rarefactive
Drude Electron Gas waves
Nuclear proton waves
ANTIWAVE IN HOLDER
(Highly damped; not shown to scale)
Body slaps air medium

© 1993, 1996 T. E. BEARDEN

Figure 3. Analogy of the "taut string holder" omitted by Faraday.
This omitted half the electrodynamics (including in Maxwell's capture of Faraday's notion) and half the EM energy. An equal and opposite Newtonian 3rd law reaction does appear in our transmitters and receivers.

Flow of current and energy into, through, and along a conductor


dm_e/dt
LATERAL PRECESSION
S enters and exits
Spinning electron inside the wire acts as a gyro
Poynting flow outside the wire
e^-
SPIN
SPIN
Poynting flow S (outside)
FIELD ENERGY DENSITY FLOW
$d\phi/dt$
$v \approx c$
dq/dt (inside)
dm_e/dt
(WORK FLOW)
$v < c$
current i direction
wire
S, $d\phi/dt$
(outside) lossfree Poynting energy flow S
dm_e/dt
(inside) drift current i
dm_e/dt

Figure 4. Receiving gyroelectrons precess laterally, providing the detected transverse wave and proving the incoming vacuum disturbance to be longitudinal.


Streamlines diverged around intercepting charge
Unit Point Charge
Bidirectional longitudinal EM wave flow lines

Figure 5. The defined "magnitude of the potential" is not such at all, but is the magnitude of the energy in the diverged flow streamlining around a unit point charge at each point in space where the potential is present.

Electrodynamics has nothing to say about what exists in the vacuum in the absence of mass.



E ≡ F/q
Note problem!
No "E" or "H" in vacuum.
S = ExH
Source q is a broken symmetry in vacuum flux
S = ExH
SOURCE CHARGE
Point coulomb
"pileup" in front produces energy density gradient across the point coulomb
So E ≡ -∇ϕ
ϕ ≡ joules continuously in geometrical flow distortion zone around one point coulomb
[Coulombic energy collection density]
© 1997 T.E. BEARDEN

Figure 6. Fields and potentials are defined in terms of the Poynting disruption of the overall energy flow from the source charge, about an intercepting and "collecting" charge. Rigorously, *as defined* E and H exist only in and on charged matter. The magnitude of the diverted water swinging around a fixed rock in a river, is not the magnitude of the river.


E = $-\nabla\phi$
Low Intensity ϕ
High Intensity ϕ
Unit point charge

Figure 7. The defined "magnitude of the field" depends on the change in intensity of the flows comprising the potential. The E-field is oriented from high (pressure) in the flow to low (pressure) in energy density over a unit length.


EM disturbance in transmitter
EM disturbance in ether
EM disturbance in receiver
mass perturbation (charge has matter)
mass perturbation (ether has matter)
mass perturbation (charge has matter)
CAUSE
TRANSMISSION MEDIUM
EFFECT
mass-to-mass transformation from transmitter to receiver

Figure 8. Maxwell's theory assumed a matter-to-matter transform from cause to effect.


ST curvatures propagate
mass perturbation (Drude Electrons)
Transmitter
mass-to-spacetime transformation
spacetime-to-mass transformation
mass perturbation (Drude Electrons)
Receiver
altered spacetime (curvatures)
altered spacetime (curvatures)
Complex of ST curvatures (vacuum engine, or spacetime engine)
Spacetime disturbance (engine) propagates

© T.E. BEARDEN 1998

The mass-to-mass transform contains two hidden infolded transforms: (i) the mass-to-spacetime transform and (ii) the spacetime-to-mass transform. What is transmitted and propagates in space is a *spacetime perturbation*.

Figure 9. Maxwell's matter-to-matter transform contains two hidden transforms: (1) matter-to-spacetime, and (2) spacetime-to-matter.


VACUUM
ENGINE
TEMPLATE
# 1
MASS
STRUCTURE
AND
DYNAMICS
# 1
+
DELTA
MASS
DELTA
ENGINE
TEMPLATE
NO
TIME
DELAY
MASS
STRUCTURE
AND
DYNAMICS
# 2
VACUUM
ENGINE
TEMPLATE
# 2
VACUUM
ENGINE
TEMPLATE
# 1
MASS
STRUCTURE
AND
DYNAMICS
# 1
+
DELTA
ENGINE
TEMPLATE
AFTER
TIME
DELAY
MASS
STRUCTURE
AND
DYNAMICS
# 2
VACUUM
ENGINE
TEMPLATE
# 2

Conventional way that bulk vacuum engines are added by adding mass. Also, fields alone may be utilized as "powerful translators" without finesse.

Adding the vacuum engine without fields or masses. First the internal hidden engines of the target are changed, producing a structured template, which gradually changes the mass at all levels.

© 1994 T.E. BEARDEN

Figure 10. Vacuum engines and their utilization.


VACUUM CHARGE
MASS
m_q
ϕ_q
Spin of the charged particle integrates some of the absorbed virtual photon energy into observable photon energy
virtual photon flux in, and observable photon flux out

$$q \equiv \phi_q \times m_q$$

Note: X is a coupling operator

"...curiously enough, we do not know exactly what charge is, only what it does. Or, equally significantly, what it does not do."

M.P. Silverman, And Yet It Moves: Strange Systems and Subtle Questions in Physics, Cambridge University Press, 1993, p. 127.

An electric charge Q is a broken 3-symmetry. The mass of the charge continuously and violently absorbs virtual photons from the surrounding vacuum, and integrates some of them to observable EM longidutinal photons which it emits in 3-space.

Figure 11. A charged particle continuously absorbs virtual energy from the vacuum, integrates some of it into observable energy, and pours out this observable EM energy in 3-space in all directions.

Composition of the scalar potential ϕ


GALLOPING VELOCITY
Scalar Potential ϕ
...ETC.
V_{avg}
V_{avg}
V_{avg}
HARMONICS
SUBHARMONICS
Wavepair #3
Wavepair #2
Wavepair #1
...ETC.
...ETC.
...ETC.
DISTANCE

© 1999 T.E. Bearden

A harmonic set of bidirectional longitudinal EM wavepairs in 3-space. Unseen here is the time-polarized EM wave in the time domain, which reacts with the source charge to produce the 3-space biwave potential.

Figure 12. The potential as observed or detected is a harmonic set of bidirectional longitudinal EM waves in 3-space. That is, this potential is the "effect" of transduction of an incoming time-polarized EM wave interacting with the source charge.

The supersystem concept



LOCAL ACTIVE VACUUM

SYSTEM

LOCAL CURVATURES OF SPACETIME

Figure 13. Concept of the supersystem and its interacting components.

Vacuum engine: Working spacetime demons


Internested patterns of spacetime curvatures
Highly Structured Einsteinian spacetime
Maxwellian Demons are EM hidden variables organized into dynamic structures acting at all levels
Demons work at all levels
© T.E. BEARDEN 1997

Figure 14. A vacuum engine is a set of spacetime demons working upon a mass system and its motion through time, at every level.



MTW's* general relativity principle

- Space acts on matter, telling it how to move.
- In turn, matter reacts back on space, telling it how to curve."

ACTIVE
SPACETIME
DYNAMIC
MASS
STRUCTURING
OF ACTIVE
SPACETIME
CURVATURES

Figure 15. General relativity principle of Misner, Thorne, and Wheeler (MTW).



Extended General Relativity Principle

- All levels of energy structures and all levels of time structures mold spacetime geometry.
- The "pattern" is called a *template* for a vacuum engine (spacetime curvature engine).
- Spatial and temporal structurings of the engine act upon mass at all levels.
- This produces a template of forces, for precise translations and stresses within the mass at all levels. The forces exist in both time and 3-space.

ACTIVE SPACETIME
DYNAMIC MASS
STRUCTURING OF ACTIVE SPACETIME CURVATURES

Figure 16. The principle of general relativity extended to include the vacuum engine.

Active spacetime and a specific vacuum engine


ACTIVE SPACETIME
DYNAMIC MASS
mass structures spacetime
STRUCTURING OF ACTIVE SPACETIME CURVATURES
DETAILS OF STRUCTURING OF ACTIVE SPACETIME CURVATURES (TEMPLATE)
spacetime structures act on mass at all levels

© T.E. BEARDEN 1996

Figure 17. Active spacetime and a specific vacuum engine (spacetime curvature engine).


SIGNAL (INFO)
INFORMATION RECEIVED
ANY OVERT PHYSICAL ACTION MUST BE TAKEN BY CELL ITSELF
VACUUM ACTIVATED
ENGINE (STRUCTURE)
TEMPLATE (FORM)
"INFORMATION" ITSELF ACTS
VACUUM GRADIENTS CHANGE ALL PARTS AND CHARACTERISTICS OF CELL, INCLUDING GENETICS

A. *Cell must do the action itself; vacuum energy exchange is passive. Energy or fuel for doing the action must be added to cell externally.*

B. *Cell is acted upon; vacuum energy exchange does the specific action. No energy or fuel for doing the action need be added to cell externally.*

Figure 18. Signal versus vacuum engine, as in Priore's cellular reversal.



All EM energy in 3-space freely comes from the time domain

(Time)

Longitudinal EM wave incoming from time domain and absorbed

CHARGE OR DIPOLE

Real EM Energy

pours out in all directions

3-space

Longitudinal EM waves emitted in all directions in 3-space

Whittaker, Math. Ann., 57, 333 (1903) shows this rigorously, when properly reinterpreted. Dipole's broken 3-symmetry is well-known in particle physics

Note: Whittaker (and others) interpreted the phase conjugate half set of LWs after interaction with the charges of the dipole, and as a 3-space *effect* rather than the time-domain *cause*. This fundamental non sequitur has just been repeated since then.

Figure 19. All EM energy in the 3-space potential comes from the time-domain.


THE IMMUNE SYSTEM
BONE MARROW
Lymphocytes
Special Defense
General Defense
Feeding cells
Intestinal tissue, liver, etc.
Thymus
Complement system
Monocytes
B-lymphocytes
suppressor cells
plasma cells
antibodies
T-lymphocytes
killer cells
helper cells
complement factors
granulocytes
macrophage
bacterium (foreign invader)

Figure 20. Immune system block diagram.



Becker's bone fracture healing

- Tiny DC currents (picoamperes)
- Pulsed DC current can be utilized
- Pulsed magnetic fields may be utilized

RED BLOOD CELL DEDIFFERENTIATES

Shucks hemoglobin coat
Grows nucleus

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes cartilage

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes bone
Deposits in fracture site, healing the fracture

© 1993, 1996 T.E. BEARDEN

Figure 21. Becker's electrodynamic healing of otherwise intractable bone fractures, using weak potentials across the fracture site.

Becker's theoretical DC control system involved with response to injury



INJURY

INPUT STIMULATION DC SYSTEM (PAIN)

CENTRAL DC SYSTEM

OUTPUT DC SYSTEM

LOCAL CELL INJURY FREE RADICALS

TOTAL CURRENT OF INJURY DC SYSTEM

STIMULATION OF REPAIR CELLS

MITOSIS DEDIFFERENTIATION

GROWTH DIFFERENTIATION

*Robert O. Becker, "The significance of bioelectrical potentials," Bioelectrochemistry and Bioenergetics, Vol. 1, 1974, p. 191.

Figure 22. Becker's block diagram of DC control system involved with response to injury.


GRAVITON
LATTICE
TEMPLATES
SICKEN
OR KILL
ENVIRONMENTAL
SHIELDING
CELL
CULTURE
SAMPLE
#1
QUARTZ
CONTAINER
CELL
CULTURE
SAMPLE
#2
QUARTZ
CONTAINER
THIN WINDOW
GLASS: No Effect
QUARTZ: Delayed Effect
Divided bottle setup

© T.E. BEARDEN 1977, 1987

Note: Minimum lattice is one harmonic interval: IR to UV is such a minimum G-lattice.

Figure 23. Kaznacheyev's induction of cellular disease and disorder at a distance, using novel electromagnetic means.



Former U.S. Embassy in Moscow.

BACKGROUND

- Began in latter 1950s
- Discovered on VP Nixon's trip
- Initially thought to be *nuclear* radiation (Discovered w/Geiger counter?)
- High level target -- U.S. Ambassador
- Guarantees personal attention of:
  - U.S. Ambassador to USSR
  - U.S. President
  - NSA, CIA, DIA, NSC, etc.
  - Top consulting scientists
  - Leading U.S. scientific institutions
- Two U.S. Ambassadors died, another sickened
- Anomalous health changes in personnel, only in zero-field (zero pot'l gradient) areas!
- Four U.S. Presidents requested Soviets cease
  - Cut from 18 watts/sq cm to 2
  - Then again increased
- No one could understand what was going on
- Aluminum screens were placed over windows
- Moscow was declared a hazardous duty zone

© 1995, 1996 T. E. BEARDEN

Figure 24. Russian "microwave" radiation of the U.S. Embassy in Moscow.

Mechanism generating the flow of a mass through time


SPATIAL
SPATIOTEMPORAL
L^2 T PHOTON
SPATIAL
PHOTON
MASS
L^3
MASSTIME
L^3T
MASS
L^3
L^2 T
© 1996, 1997 T.E. BEARDEN
(ΔE)(Δt) + M => (M+ΔM)Δt => M + (ΔE)(Δt)
Flow of macroscopic time (observable photon interactions)
SPATIAL AND SPATIOTEMPORAL
"MASS"
MASSTIME
L^3T
MASS
MASS
MASSTIME
L^3T
"MASS"
Flow of microscopic time (via virtual photon interactions)

Figure 25. Mechanism generating the flow of a mass through time.


DISEASED CELL'S DEVIATIONS FROM NORMAL ARE LITTLE SPACETIME ENGINES
change D
change N
normal engine
DYNAMIC MASS OF CELL
change A
change B
change C
longitudinal EM pump wave
change D'
change N'
normal antiengine
DYNAMIC MASS OF CELL
change A'
change B'
longitudinal EM pump wave
change C'
© T.E. BEARDEN 2001

- A normal cell has a normal spacetime engine.
- Each deviation from the normal engine is also an engine.
- Pumping with longitudinal EM waves creates amplified antiengines for the normal engine and all deviant engines.
- This set of anti-engines precisely reverses the cell back to a previous physical state, prior to the deviations.

Figure 26. Producing a specific anti-engine for a specific cellular disease condition.

A DRAMATIC EXTENSION TO NONLINEAR OPTICAL PUMPING


PREVIOUS VACUUM ENGINE
PREVIOUS MASS STATE
transverse pump wave
A_2
$+\dot{t}$
TIME AXIS
A_2
τ_2
transverse signal wave (input)
A_4
PPCM
A_3
NONLINEAR MEDIUM
AMPLIFIED VACUUM ANTIENGINE
RESIDENT VACUUM ENGINE (input)
amplified phase conjugate replica transverse wave (time-reversed)
MASS
transverse pump wave
A_1
Output
A_1
τ_1

a. Pumping with transverse EM waves produces a time-reversed *wave*.

b. Pumping with longitudinal EM waves A_1 and A_2 time-reverses *the mass itself*.

Figure 27. Pumping with longitudinal EM waves A also pumps in the time domain with time-polarized EM waves τ. This time-reverses a macroscopic mass and its dynamics.

Prioré's therapeutic methodology

Time-reverses the cells back to normal state



START

SELECT A SET OF TRANSVERSE EM WAVES

MIX WAVES IN A PLASMA TO ADD CONJUGATES

MIX OUTPUT INSIDE STRONG PULSED DC MAGNETIC FIELD

EXPOSE WHOLE BODY OF PATIENT TO DIMENSIONED MAGNETIC FIELD

CELL AND ALL ITS PARTS ARE PUMPED IN INNER EM CHANNEL IN TIME DOMAIN

VACUUM ENGINE FOR DISEASED CELL ALREADY PRESENT

DISEASED CELL PHASE CONJUGATES ITS VACUUM ENGINE

FORMS AMPLIFIED VACUUM ANTIENGINE FOR CELL'S DISEASE VACUUM ENGINE

TIME-EXCITATION CHARGING ENDS. IRRADIATION IS HALTED.

ANTIENGINE CONTINUES TO ACT AND TIME-REVERSE CELL AND ALL ITS PARTS*

CELL RESTORED TO NORMAL?

YES

STOP

NO

ADJUST WAVE FREQUENCIES IF REQUIRED, AND IRRADIATE AGAIN

*Includes genetics

© 1994, 1998 T.E. BEARDEN

Figure 28. Block diagram of operation of Prioré's methodology.


ADD PUMPS
B
PRIORE AMPLIFIED PUMPING
CELL AS A PHASE CONJUGATE MIRROR
RESIDENT VACUUM ENGINE
ANTIENGINE PRESENT?
Y
N
APPLY ANTIENGINE
B
A
START
A
CYCLE
CELL AND INTERIOR SENSORS
LOCAL VICINITY SENSORS
NON LOCAL ALL-BODY SENSORS
DELTA CATALOGS
CELLS AND INTERIORS
SELECT LOCAL
SELECT NONLOCAL
AEROBE
ANAEROBE
DELTA?
Y
N
DELTA?
Y
N
DELTA?
Y
N
AEROBE
ANAEROBE
AEROBE
ANAEROBE
AEROBE
ANAEROBE
SWITCH TO AEROBE CONTROL SYSTEM
A
CROSS THRESHOLD BACK TO AEROBE?
Y
N
SWITCH COMPARATIVE CATALOG
SWITCH TO ANAEROBE CATALOG
END OF AEROBE CATALOG?
Y
N
SUM FOR ENTIRE BODY
SWITCH ON CENTRAL, OFF DECENTRAL GROWTH CONTROL; RESET IMMUNE SYSTEM
SWITCH OFF CENTRAL GROWTH CONTROL
SWITCH ON DECENTRAL GROWTH CONTROL
CONDITION IMMUNE SYSTEM TO ACCEPT
A
R&R SYSTEM
Regeneration Example
© T.E. BEARDEN 1998

Figure 29. Block diagram of the cellular regeneration system and its overall operation (by the present author).

Rife's great secret: Recursive magnification by iterative serial summation of vacuum engines


Iterative magnifying stages
Virtual
State
Quantum
Threshold
Observable
State

Figure 30. Rife's great secret: Recursive magnification of the virtual state vacuum engines and their dynamics to the observable state.

Utilizing Scalar Electromagnetics To Tap Vacuum Energy

Floyd Sweet, Association of Distinguished American Scientists
2311 Big Cove Road, Huntsville, Alabama 358010

T. E. Bearden, Association of Distinguished American Scientists
2311 Big Cove Road, Huntsville, Alabama 35801

(Also published in: Proceedings of the 26th Intersociety Energy Conversion Engineering Conference (IECEC Conf),
August 4-9, 1991, Boston, Massachusetts. Vol 4, Advanced Energy Concepts, pp. 370-375.)

Copyright © 1991 by T.E. Bearden & F. Sweet. All Rights Reserved.

ABSTRACT

Based on E.T. Whittaker's previously unnoticed 1903-1904 papers which established a hidden bidirectional EM wave structure in a standing forcefield free scalar potential, a method of directly engineering the ambient potential of the vacuum has been developed and realized experimentally.

Adding Whittaker's engineerable hidden variable theory to classical electro-magnetics, quantum mechanics, and general relativity produces supersets of each discipline. These supersets are joined by the common Whittaker subset, producing a unified field theory that is engineerable and tested.

By treating the nucleus of the atom as a pumped phase conjugate mirror, several working model energy units have been produced which excite and organize the local vacuum, increase the local virtual photon flux between local vacuum and nucleus, establish coherent self-oscillations between the local excited vacuum and the affected nuclei, utilize the self-oscillating standing wave for self-pumping of the nuclei/mirrors, introduce a very tiny signal wave to the mirrors, and output into an external load circuit a powerful, amplified, time-reversed phase conjugate replica wave at 60 Hertz frequency and nominal 120 volt sine wave power.

Several models have been built, ranging from 6 watts early on to one of 5 kilowatts. Both closed batteryless systems with damped positive feedback and open loop systems with battery-powered input have been successfully built. Open loop power gains of from 5×10^4 to 1.5×10^6 have been achieved.

Antigravity experiments have also been successfully conducted where the weight of the unit was reduced by 90% in controlled experiments, with a signal wave input of 175 microwatts and an output of 1 kilowatt.

The basic theory of the device is briefly explained and experimental results presented. In the demonstration session, a videotape of one operating open-loop unit with a 1.5×10^6 power gain is planned, as is the demonstration of an actual working model closed-loop system with a nominal rating of 500 watts, and without external power input of any kind.

The units are solid state, with no moving parts. Each of them comprises a unique form of self-powered vacuum triode of extraordinary gain, where the cathode power and plate power are freely furnished by the vacuum, and only a small grid signal need be furnished either from an external power source or by clamped positive feedback from the device's output. The output is negative energy, and some of its unique characteristics are pointed out.

Implications of the experimental application of the Sweet vacuum triode, the Bearden approach to the nucleus as a pumped phase conjugate mirror, and the unified field theory based on Whittaker's engineerable hidden variable scalar EM potential theory are also briefly addressed.

SCALAR ELECTROMAGNETICS

In 1837 Sir W.R. Hamilton said,

"The notion of time may be unfolded into an independent pure science... a science of pure time is possible."

As is well-known, the fundamental units utilized in physics are arbitrary. It is even possible to construct all of physics on a single unit, time. This oddity shows the truth in Hamilton's statement; it is even more odd, because quantum mechanically time is not an observable. This means that the observable world can be modeled completely in terms of the nonobservable, which is essentially what modern quantum mechanics is now doing.

Hamilton viewed his magnificent quaternions as essentially having accomplished the mathematical structuring of time. Maxwell's original EM theory, as is well-known, was modeled in Hamilton's *quaternions*, not in the highly curtailed Heaviside/Hertz vectors erroneously taught today as "Maxwell's theory."

Not a single one of the present so-called "Maxwell's" vector equations ever appeared in a book or paper by James Clerk Maxwell.

For some years the author has worked on an extended electromagnetics theory, involving the scalar component of the quaternion. [Ref. 1]

In Maxwell's original *quaternion* theory, this scalar component often remains when the directional components zero. Further, it then enfolds vectors and functions of vectors inside, in a hidden variable manner. Specifically, the author has patterned a unified field theory concept upon the previously unnoticed but remarkable early work of E.T. Whittaker. [Ref. 2]

In two fundamental papers in 1903 and 1904, Whittaker showed that all present vector EM can be replaced by scalar potential interferometry, and that bidirectional harmonic EM plane wave sets could be used to produce a standing wave of force-field-free potential (Figures 1 and 2).


Figure 1
Cross-section of Whittaker spherical EM potential wave
phi(x)
Organized Local Space-Time Curvature
EM Substructure
EM Substructure
x

NOTE: SHAPE MAY BE ALL ABOVE OR ALL BELOW AMBIENT VACUUM POTENTIAL

Thus Whittaker anticipated the quantum mechanical Aharonov/Bohm effect by 55 years, including extending it to the macroscopic world instead of the mesoscopic realm where it has been established to date. [Ref. 3]

In modern terms, Whittaker showed how to turn EM wave energy into electrogravitational potential energy, then how to interfere two such scalar potential waves to recover electromagnetic energy, even at a distance. [Ref. 4]

This unrecognized work is of great importance: when applied to modern physics, it produces supersets of quantum mechanics (QM), classical electromagnetics (EM), and general relativity (GR).

Further, all three extended disciplines unify on their common Whittaker subset, in a testable and engineerable fashion. [Ref. 5]


Composition of the Scalar Potential ϕ
GALLOPING VELOCITY
Scalar Potential ϕ
...ETC.
V_{avg}
V_{avg}
V_{avg}
HARMONICS
SUBHARMONICS
Wavepair #3
Wavepair #2
Wavepair #1
...ETC.
...ETC.
...ETC.
DISTANCE
© 1995 T.E. Bearden
A harmonic set of bidirectional longitudinal EM wavepairs.
Each wavepair is also a net time-polarized EM wave.

Figure 2. Infolded EM plane wave structure of a Whittaker wave.

The Nucleus As a PPCM and Triode

The author has also considered the highly nonlinear nucleus of the atom as a pumped phase conjugate mirror (PPCM), having found no other consideration of same in the literature.

The author also dubbed a PPCM a "triode," since the amplified phase conjugate replica of the signal wave is much like the amplified output of a triode, and the signal wave input to a PPCM is much like a triode's grid signal input. The PPCM pump wave then corresponds roughly to the power input to the cathode and plate of a triode. [Ref. 6]


Transverse EM Wave Pumping of PCM
transverse pump wave
A_2
transverse signal wave (input)
A_4
PPCM
A_3
NONLINEAR MEDIUM
AMPLIFIED PHASE CONJUGATE REPLICA TRANSVERSE WAVE (TIME-REVERSED) IS EMITTED.
Precisely backtracks signal wave input
© T.E. BEARDEN 1997
transverse pump wave
A_1

Figure 3. A pumped phase conjugate mirror.

VACUUM TRIODE BACKGROUND

About seven years ago, the author was privileged to see and examine an invention of Mr. Floyd Sweet, that produced about 6 watts of electrical power from the vacuum itself.

This remarkable device, which the author dubbed a *vacuum triode*, in a single unit utilized most of the scalar EM concepts the author had so painfully and slowly formulated over the years.

Sweet, a brilliant inventor with a remarkable knowledge of magnetics, had utilized barium ferrite magnets and special coils to produce a solid-state device that successfully tapped the vacuum energy.

The author quickly put together a theoretical concept for the energy-tapping mechanism, based on treatment of the nucleus as a PPCM and Whittaker's scalar EM potential unified field theory. [Ref. 7]

The author furnished the technical concept, treating the nucleus as a pumped phase conjugate mirror, to the inventor along with copies of Whittaker's papers.

Sweet's Synthesis and Extension

Sweet is also a brilliant EM theoretician, working in four, five, or even six dimensions with ease. He immediately synthesized the entire PPCM and Whittaker theory, and developed a complete theoretical treatment of the device. [Ref. 8]

He also increased the nuclear potential utilized in the activated nuclei of the device, which increased the pumping energy and hence the energy output. He next produced an open-loop vacuum triode (VT) with an output of 500 watts, for an input of 33 microwatts.

Thereafter he produced several other models, including closed-loop systems and one with 5-KW output.

Purpose of This Paper

Our purpose is to explain the detailed scalar EM concept of the operation of the vacuum triode, since it is a universal method for cohering and tapping useful EM energy from the vacuum.

The author believes that this mechanism is the fundamental mechanism that must be invoked in any over-unity device that electromagnetically extracts vacuum energy as electromagnetic effects.

We also intend to demonstrate a full working model of the device at this conference. Sweet's detailed theoretical treatment will be completed and submitted to a major journal shortly, to complete the scientific exposition of the new methodology.

I must also express my deep admiration for my brilliant inventor colleague. It has been a privilege to work with him, though under great difficulties and at a distance. He has developed several other related devices that are of great importance to the emerging new physics of *vacuum engineering*, in the sense referred to by Lee. [Ref. 9]

To mention just one, he has produced a magnetic lens which apparently can directly display the vacuum's virtual particle flux, or a good analog of it. So far as I am aware, this is the only extant instrument today that can perform this feat.

When the vacuum triode has been proven to the scientific community, it is my intention to nominate Sweet for the Nobel Prize he so richly deserves, and seek high scientific endorsements for the recommendation.

INTRODUCTION

Entropy

As is well known, in any closed dynamic system the order existing in it will gradually be dissipated, as more and more interactions occur. This leads to the notion of *entropy* as the increasing disorder in such systems. The assumptions are

1. a closed system, and
2. a positive flow of time for the components of the system.

Actually no such thing as a completely closed system exists in nature. Every mass system is open to virtual particle flux exchange with the vacuum, for example, particularly in the nucleus of its atoms, where the bulk of its mass is located.

However, the closed system assumption is reasonably approximated by a great many systems which are in stable thermodynamic equilibrium, or nearly so.

On the other hand, in an open system far from thermodynamic equilibrium, the second law of thermodynamics does not necessarily apply, because the system violates both the closed system assumption and its equilibrium approximation. [Ref. 10]

Time Reversal

Since being discovered in 1972 in the open Soviet literature, the time-reversed (phase conjugate) EM wave has also been known. The phase conjugate EM wave is truly time-reversed, as has been shown experimentally. Since the time-reversed EM wave violates the second major assumption, the second law of thermodynamics need not necessarily hold for time-reversed entities.

Putting all this together, if one wishes negentropy and hence increased energy in a system, the candidate suggested would appear to be a system that was strongly

1. open loop,
2. time-reversed, and
3. far from thermodynamic equilibrium.

A good overview of time-reversal in physics has been provided by Sachs. [Ref. 11]

Engineering the Nucleus

Since the nucleus already provides a myriad of time-reversed processes, engineering the nucleus of an atom is a very good candidate for practical negentropy.

To engineer the nucleus directly, a Whittaker potential is first artificially constructed, by composing a harmonic set of phase-locked EM wave/antiwave pairs. It is accented that the antiwaves must be true phase conjugates; otherwise they will not constitute a gradient-free Whittaker standing potential wave.

In addition, at least one harmonic interval must be used, and additional harmonic sets are most desirable. The reason is that a space-time lattice must be formed in the vacuum, where the energy is additive spatially but oppositive in t-dot, the rate of flow of time, in the fourth dimension.

So a time-structure is required as well as a spatial structure, which is what is provided by ***n*** bidirectional harmonic Whittaker EM wave sets, where ***n*** is an integer greater than 1.

Once a specific Whittaker structure has been chosen, the local lattice of space-time is established. This establishes phase-locked lattice groupings of coupled photon/antiphoton pairs, or of *gravitons*. In turn, this Whittaker-structured vacuum now contains specific graviton *vacuum engines*, which directly engineer and structure the vacuum's virtual particle flux (VPF) exchange with the nucleus. [Ref. 12]

The nucleus is highly nonlinear, hence strongly phase conjugative, or time-reversed. The ambient potential of the local vacuum surrounding the nucleus is in a violent virtual photon exchange with it, accounting for its electrical charge.

Since the preponderant charge is positive, from the viewpoint of the ordinary light observer whose light interacts with electron shells, the nucleus may be taken to exhibit time reversal (phase conjugation).

Energy, Time, and Gravitons

We take the definition of "energy" to be fundamentally an ordering imposed upon the VPF of vacuum. We take photon scattering from the electron shells of atoms to be the fundamental exterior mechanism producing forward flow of external observer time.

It then follows that "time's arrow" for the EM observer is due to the universal scattering of photons from electron shells.

In this view, forward (positive) time flow and entropy are due to the same primary action: photon scattering from electron shells. It is unfortunate that the concept of "positive" energy has been tied to, and defined in terms of, the scattering and dissipation of VPF order as *work*, or energy expended.

Via the standard labeling, then, negative energy is the reconstitution of order in the vacuum VPF. It should be noted that, in a PPCM, dissipative or external pump wave stress energy can be scavenged and re-emitted in perfect order as the phase conjugate replica. This is a *negentropic* process, for it is capable of turning disorder into order. [Ref. 13]

In the time-reversed PPCM nucleus, we should expect to see appreciable *negative energy*—that is, energy removed from the EM scattering domain. This includes the binding energy of the nucleus, and the gravitational (G) potential energy of the EM energy removed from the "scattering interaction realm" and locked into the mass.

Following Sakharov, we hold that the G-field is not a fundamental field of nature, but a composite caused by, or made from, other fields. [Ref. 14]

To the first order, we assume the G-potential is comprised of coupled photon/antiphoton pairs, on the average, where the statistical coupled spin-2 photon/antiphoton pair is a *graviton*. [Ref. 15]

We follow the modern view of the field: because of vacuum fluctuations, rigorously one no longer speaks of "the" field, but of the *probability of a particular field configuration*. [Ref. 16]

We also hold the vacuum to be composed of potentials, and regard the three terms *space-time, vacuum*, and *scalar potential* as essentially synonymous.

Newton's Third Law and the Detection Process

The VPF EM stress of the local vacuum immediately surrounding the nucleus may be decomposed a la Whittaker into opposing bidirectional EM plane waves/forces. Thus the nonlinear nucleus may be regarded as a pumped phase conjugate mirror, normally with a gain of one.

In this view, Newton's third law reaction force is generated because the so-called "photon" interaction with an atom is in fact a graviton reaction involving a photon/antiphoton pair that is decoupled.

The decoupled photon normally is absorbed and reradiated by an orbital electron, while the decoupled antiphoton interacts with the nucleus, producing a time-reversed twin of the external force—or, in other words, Newton's third law reaction force, which gives a slight recoil of the nucleus.

Half of every measurement physicists normally make is discarded, with the missing half accounting only for Newtonian reaction in the meter or instrument, which is usually ignored.

The fact that half of our measurement interactions are ignored is occasionally discovered and noted by physicists, who may even write a paper pointing it out, but no change is instituted in the foundations. [Ref. 17 and Ref 18]

Semiconducting Vacuum and Self-Oscillation

The vacuum immediately surrounding the nucleus is structured by the nucleus, and is itself nonlinear and capable of acting as a *semiconductor*. [Ref. 19]

Since both this immediately local semiconductor vacuum and the nucleus it surrounds are highly nonlinear, then *nonlinear resonance* can conceivably be established between them.

Further, since the resonating system in such case is an open system away from thermodynamic equilibrium, the oscillation can be self-sustaining. Such self-oscillation of the pumping of a PCM is already well-known in the nonlinear optical literature, particularly with compounds containing barium. [Ref. 20]

THE VACUUM TRIODE

The Basic Concept

As is well-known, a stress can be decomposed into opposing sets of forces. But quantum mechanically, the forces we are interested in with our work here are all caused *electromagnetically*, by the exchange of virtual photons. Even mechanical force, according to QM, is caused in this manner. Thus opposing electromagnetic or mechanical "stress" sets of bidirectional EM forces are microscopically equivalent to the notion of *pump waves* in nonlinear optics.

Hence under the proper conditions, it follows that trapped EM stress energy of the vacuum can be utilized to "pump" the nucleus.

Treating the stress-pumped nonlinear nucleus as a PPCM, it follows that the stress energy of the vacuum can be tapped by a 4-wave mixing mechanism in the atomic nucleus, to provide amplified phase conjugate EM wave outputs from the atom in response to small signal wave inputs. [Ref. 21]

In the proper nonlinear material, the material may act as a PPCM, in which case there exists a suitable connection between the material's atomic nuclei and its external electromagnetic lattice bonds, and the amplified phase conjugate replica wave generated in the nucleus will be emitted from the material as an EM wave field. This field can then be tapped by suitable means and output to an external load circuit.

Block Diagram of the Vacuum Triode

Figure 4 shows a basic block diagram of the vacuum triode process, utilized by Sweet in several laboratory vacuum energy devices. These devices have ranged from a nominal 500 watt output in a 6-lb. device to 5 kilowatts for a heavier unit. Gains have ranged from 50,000 to 1,500,000 for open-loop systems. Both open-loop and closed-loop systems have been built and tested.

Figure 4 shows a combined block diagram for either a closed-loop or open-loop system. In the open-loop system, a barium ferrite magnetic material is used as a pumped phase conjugate mirror.

In the "standard" design, two opposing PPCMs are used. The advantage of this dual combination is the use of *self-targeting* (repetitive phase conjugation, signal by signal). This has the effect of

1. stabilizing the Whittaker field, and
2. producing a quantum potential between the two mirrors, so the mirrors and the Whittaker potential between them are essentially one single space-time entity.

Discussion of a quantum potential is beyond the scope of this paper, but the technical mechanism for creating one has been previously presented by the author on several occasions. [Ref. 22]

First we will explain the open-loop operation of the vacuum triode. In Figure 4, on the right an external 60 Hz, nominal 10 volt AC sine wave of several tens of microwatts in power is input into the stabilized field of the barium ferrite magnet structure, where it modulates the field, producing a signal wave input into the atoms of the material.

In the top right block, the EM signal wave interacts with the electron shell of an atom, which in turn is EM-coupled to the nucleus.


STRUCTURED IMMEDIATE VACUUM
ACTIVATED NONLINEAR NUCLEUS
EM WAVE COUPLED FROM/TO ELECTRON
RESONANCE
PC WAVE
SIGNAL WAVE
SURROUNDING VACUUM
EXTERNAL LOAD CIRCUIT
FIELD OF BARIUM FERRITE MAGNET
EXTERNAL SIGNAL WAVE INPUT
POSITIVE FEEDBACK
© 1989, 1991, 1993 T.E. BEARDEN
AUTOMATIC GRID SIGNAL INPUT
CLAMPED STABILIZER

Figure 4. The Vacuum Triode Concept.

Thus an EM signal wave is input to the nucleus of the atom, which is highly nonlinear (middle top block). Earlier, Sweet had specifically conditioned the atomic nuclei with a proprietary process, wherein in the barium nucleus a trapped 60 Hz scalar EM spherical wave resonance (self-oscillation) exists between the structured semiconductor vacuum immediately surrounding the Ba nucleus.

In the same *activation* process, the ambient potential of the surrounding vacuum was raised and stabilized, in the two leftmost blocks.

At this point the nonlinear nucleus is effectively self-pumped by the trapped, excited, spherical scalar wave oscillation between the structured semiconductor vacuum and the nucleus. The nucleus is now a strongly pumped phase conjugate mirror.

Consequently, when the signal wave input arrives, the PPCM nucleus emits an amplified phase conjugate replica (PCR) wave, which precisely backtracks the input signal wave. This precise backtracking (perfect retroreflection) is referred to as the "distortion correction theorem."

In short, the powerful PCR wave returns precisely toward the external source, passing through the electron shells and arriving in the perturbed barium ferrite magnet assembly field, where it perturbs the field.

A transformer-like system then extracts this magnetic field perturbation and conducts it to the external load circuit.

However, the PCR contains *negative* energy. Short of the load, the internal circuits run cool, rather than heating. This is a signature of a true vacuum energy tapping device.

Indeed, if the output leads of the Sweet vacuum triode are physically shorted together, a brilliant flash occurs, and the leads instantly ice as if dipped in liquid oxygen. This is another signature of the true negentropic over-unity vacuum tap.

Note that the energy extracted from the semiconducting vacuum adjacent to the nucleus is just instantly replaced by the surrounding vacuum's inexhaustible energy pool. This is an open-loop system, with a hidden energy source: the intense virtual particle flux of the vacuum's ambient charge.

It is not possible to exhaust that flux, which is often calculated to have an energy density of some 10^{100} or more grams per cm^3, if the energy were cohered and condensed into mass.

As can be seen, even a VT gain of 1.5×10^6 represents a "vacuum tap" of an incredibly small efficiency, on the order of 10^{-100} or so. However, the vacuum "river" is so energetic that such efficiencies are quite sufficient.

We accent that the barium ferrite magnetic material must be *activated* so that stable self-oscillation between the barium nucleus and the surrounding semiconductor vacuum exists. Although self-oscillating/self-pumped PCMs are known at optical frequencies, Sweet has discovered and perfected a brilliant methodology for activating PPCM nuclei at ELF frequencies.

In a resistive load such as light bulbs, the resistive material accomplishes repetitive phase conjugation. Thus in the resistor, half the total energy is expressed as photon or dissipative energy in the external (electron shell) level.

As the excited electrons decay, they emit scattered EM energy as light and heat. This is an *exothermic* interaction. The other half of the total energy reacts in the atomic nuclei, as a phase conjugative or *endothermic* interaction.

We strongly accent that, Whittaker-wise, there are two electromagnetic channels and two kinds of EM:

1. *external* EM, the common electron-shell interacting, entropic, scattering, time-forward kind, and

2. the *internal*, unsuspected, hidden variable, nuclei interacting, negentropic, reordering/ convergent kind.

Internal EM travels strictly between atomic nuclei, normally not reacting with electron shells unless a pumped phase conjugate mirror reaction is invoked in the nucleus to produce a gain somewhat greater than unity.

Thus if we wish to communicate with atomic nuclei directly, and engineer them directly, we must utilize the internal EM channel via applied Whittaker methods.

Antigravity Tests

Inherent in the preceding discussions is the possibility to turn EM energy into gravitational energy of either sign. In other words, one should be able to utilize Sweet's vacuum triode to produce and demonstrate antigravity.

Indeed this is the case. Sweet has also discovered the special alterations necessary to perform straightforward transformation of the internal energy in the nucleus to antigravitational energy, producing a unilateral thrust upward.

Note that the bulk of G-potential gradient (G-force-field) occurs Whittaker-wise at ELF frequencies. This explains why nonlinear phase conjugate opticians do not notice direct antigravity effects.

At the optical frequencies at which they work, the effects are so miniscule that they are negligible. This is readily explained as follows: In QM, the quantum (photon) is comprised of action (angular momentum), not just energy. It is rather like a "piece of energy welded to a piece of time, with no seam in the middle."

Since quantum change occurs in quanta, the decoupling of the energy and time components, in the continual interaction of photons with matter, exchanges energy between G-potential of vacuum and trapped mass of the atom or particle. In this exchange, small increments of time are continually being formed (and unformed, as photon emission occurs).

Consequently, each mass is moving forward in time in small incremental jumps, usually of exceedingly small magnitude. However, the energy and time trapped in a photon are canonical. The greater the piece of energy, the smaller the piece of time, and vice versa.

So if one wishes to stress the "rate of flow of time" significantly, one needs to produce large amounts of photons that have very large pieces of time, and consequently little pieces of energy.

Since the energy of the photon is directly proportional to its frequency, this means that the lower frequency photons have larger time increments, and hence endure over many "regular-sized photon absorption/emission changes" to appreciably stress the rate of time flow/production.

The bottom line is that the standard pumped phase conjugate mirror can be adapted to produce antigravity at ELF frequencies, but precisely the same adaptation at optical frequencies will have negligible effect.

With this in mind, the author requested Sweet to perform an antigravity experiment to prove the thesis. With Sweet's proprietary adaptation of his vacuum triode/PPCM, the experiment produced rather straightforward but spectacular results, as shown in Figure 5.

The experiment was performed as follows: Rigged for antigravity, the 6-lb. device was placed on a scale so that its weight could be continuously monitored. A special external load box was utilized in which multiple electric light sockets were connected in parallel.

Then the external load draw was adjusted by merely screwing in 100-watt lamps, one at a time, with measurement and observation pauses in between. The output of the device was 120 volt, negative AC sine-wave power at 60 Hz.

For each 100-watt increment, the load power was recorded and the weight was carefully recorded. The results are shown in the rather smooth, classic curve shown in Figure 5.

At 1,000 watts load draw, the previously 6-lb. device had reduced its weight due to gravity by 90 percent. At that point the signal-wave (grid) input to the open-loop vacuum triode was only 175.4 microamps at 10 volts, or just under two milliwatts.



EXTERNAL ELECTRICAL LOAD

(HUNDREDS OF WATTS)

Figure 5. Antigravity Test of Sweet's Adapted Vacuum Triode.

We accent that the nominal two milliwatt input is only a gating signal. It is the organized, gated vacuum energy that is performing the action.

The experiment was stopped short of actual hovering and flying due to safety considerations. With the specific adaptation, magnetic monopoles are deposited in the magnet materials, producing internal tensile stress.

Since no explosive controlled facilities were available, and there was no wish to destroy the VT, the experiment was terminated at 90% antigravity performance.

It was completely successful, and adequately demonstrated the validity of the unified field theory concepts utilized in our approach.

CONCLUSIONS

A new unified field theory has been developed, tested, and at least partially verified experimentally.

The concepts of the theory have been applied by Sweet in a series of inventions that produce readily usable, safe electromagnetic power directly from the vacuum.

The methodology lends itself to formulation of power devices without moving parts. Antigravity, predicted by the concepts of the theory, has been demonstrated in actual practical demonstrations on the laboratory bench.

Though not discussed in this paper, application of the concepts and methodology to a large variety of other fields, such as medical reversal of aging and curing of almost the entire range of present debilitating diseases, has been previously pointed out. [Ref. 23]

We have also pointed out the mechanism for Kaznacheyev's cytopathogenic effect, or the induction of cellular pathology at a distance by electromagnetic means. [Ref. 24]

We have also pointed out the specific mechanism involved in Priore's device, which in rigorous laboratory animal testing under the auspices of eminent French scientists, demonstrated nearly 100 percent cures for terminal cancers and leukemias, sleeping sickness, artherosclerosis, and other debilitating diseases.[Ref. 25]

We believe we have also produced the concepts enabling the direct engineering and therapeutic manipulation of Popp's master cellular control system. [Ref. 26]

We conclude that the concepts we have utilized and experimentally demonstrated are universal, as implied by any notional unified field theory.

Our conclusion is that the concepts, theory, and experiments, taken together, are sufficient for investigation and replication by the scientific community.

If replicated and fully substantiated, we believe the work will directly point the way to, and usher in, a new unified field theory physics of universal application.

SPECULATED IMPLICATIONS

As can be seen, the implications of the new approach are profound. The authors believe they have ushered in the forerunner of a vast new physics, one which will change our lives, and our view of physical reality, in ways previously undreamed of.

By mastering, controlling, and gating the vast, incredible energy of the seething vacuum, we can power our automobiles, flying machines, and technology inexhaustibly. Further, it can be done absolutely cleanly; there are no noxious chemical pollutants to poison the biosphere. With practical antigravity, ships can be developed to cross the solar system as readily as one crosses the ocean today.

And the ships, automobiles, and technology will never run out of fuel; the inexhaustible vacuum fills every system, everywhere, to overflowing.

Not discussed in this paper, it turns out that living systems, faced with the problem of achieving negentropy so as to maintain their form in a dissipative external physical reality, have always used the hidden internal channel for such things as mind, thought, cell control, and living functions.

With the new methodology, one now faces the advent of access and engineering of the mind and life of the observer as readily as the observer's physical body.

Transmutation of the elements, control of the weather, lighting and powering our cities and homes cheaply and cleanly, and provision of plenty for everyone is the vista for the future. We can in fact clean up the radioactive wastes, rid ourselves of coarse nuclear and petroleum powerplants.

We strongly stress that, with the ability to engineer the Schroedinger equation itself, the new methodology allows the direct engineering and control of quantum change, and hence of physical reality itself.

The methodology is extendable to hyperdimensions; nested virtual levels of the vacuum are already precisely that. The author has already pointed out the application of this emerging technology to the absolute cure of diseases such as AIDS, cancer, leukemia, etc., and shown that the Priore device in France already proved the efficacy of the application in the 60s and 70s.

We shall be able to rid ourselves and our descendents of diseases. With direct access to the actual software of life and mind, in the future we should be able to achieve levels of education previously unattainable, by directly inputting the relevant software.

Previously we have also pointed out that four nations of the world are already embarked on weaponization of scalar EM unified field technology. It is sobering to think that, in addition to having the ability to make our planet a paradise for humankind, we also will have the ability to make it a hades.

For that reason, we are doing our best to clarify the technical concept and the theory in this 1991, hopefully with the view that humankind will seize upon the positive aspects, and develop and apply this technology for the betterment of all people everywhere.

Long ago, Albert Einstein said these words:

"It would of course be a great step forward if we succeeded in combining the gravitational field and the electromagnetic field into a single structure. Only so could the era in theoretical physics inaugurated by Faraday and Clerk Maxwell be brought to a satisfactory close."

And Teilhard de Chardin wrote:

"Someday, after we have mastered the winds, the waves, the tides and gravity, we shall harness for God the energies of love. Then for the second time in the history of the world man will have

discovered fire."

The authors fervently believe they have come upon fire for the second time, as allegorized by de Chardin. If so, let us all use the knowledge wisely.

REFERENCES

1. Maxwell's original quaternion EM theory is contained in some 200 quaternion equations and differs extensively from the restricted Heaviside/Gibbs vector interpretation universally taught today as "Maxwell's Theory." See James Clerk Maxwell, *A Treatise on Electricity and Magnetism*, Oxford University Press, Oxford, 1873. The third edition is by Dover, 1954.

2. E.T. Whittaker, "On the Partial Differential Equations of Mathematical Physics," *Math. Ann*., Vol. 57, 1903, p. 333-355; "On an Expression of the Electromagnetic Field Due to Electrons by Means of Two Scalar Potential Functions," *Proc. Lond. Math. Soc*., Series 2, Vol. 1, 1904, pp. 367-372. The first paper was in fact a detailed theory of the scalar standing potential wave that Nikola Tesla discovered four years earlier, on the night of July 3-4 1899, being radiated from thunderstorms, which he entered in his *Colorado Springs Notebook* on the morning of the 4th. More recently the Whittaker structure (WS) inside potentials, including the Schroedinger potential, has been shown by V.K. Ignatovich, "The Remarkable Capabilities of Recursive Relations," *Am. J. Phys*., 57(10), Oct. 1989, p. 873-878, without credit to Whittaker or to the presence of such structured scalar potentials in Maxwell's original quaternion EM theory. These WSs are universal to scalar potentials; e.g., for the same in acoustics, see Richard W. Ziolkowski, "Localized Transmission of Wave Energy," *Proc. SPIE, Vol. 1061, Microwave and Particle Beam Sources and Directed Energy Concepts*, Jan. 1989, p. 396-397.

3. See Y. Aharonov and D. Bohm, "Significance of Electromagnetic Potentials in the Quantum Theory," *Phys. Rev*., Second Series, 115(3), Aug. 1, 1959, p. 458-491. This paper pointed out the primacy of the potentials. Instead of being causative agents, the force fields are actually effects generated from the potentials. This is in complete violation of both classical electromagnetics and classical dynamics, but it is absolutely required by quantum mechanics. For an extensive discussion of the Aharonov-Bohm effect and an extensive list of references, see S. Olariu and I. Iovitzu Popescu, "The Quantum Effects of Electromagnetic Fluxes," *Rev. Mod. Phys*. 57(2), Apr. 1985. See Bertram Schwarzschild, "Currents in Normal-Metal Rings Exhibit Aharonov-Bohm Effect," Physics Today, 39(1), Jan. 1986, p. 17-20 for confirmation that the Aharonov/Bohm effect has indeed been firmly proven experimentally.

4. It is pointed out that today all potentials are well-known to be gravitational entities. However, this was not known in Whittaker's time, and so he himself did not realize that he had actually produced an engineerable, testable unified theory of electromagnetics and gravitation.

5. T.E. Bearden, "Possible Whittaker Unification of Electromagnetics, General Relativity, and Quantum Mechanics: Part I: Background," Presented to *Ala. Acad. Sci. Annual Symp*., Univ. Jacksonville, Mar. 1991.

6. For the theory of a pumped phase conjugate mirror, see David M. Pepper, "Nonlinear Optical Phase Conjugation," *Opt. Eng.*, 21(2), Mar./Apr. 1982, p. 156-183; Amnon Yariv, *Optical Electronics*, 3rd Edn., Holt, Rinehart, and Winston, New York, 1985. In a normal triode tube, the amplified plate signal is 180 degrees out of phase *spatially* with the grid input, but in-phase with it in respect to *rate of flow through time*. In a PPCM, the amplified phase conjugate replica wave is in phase spatially with the signal wave, but 180 degrees out of phase with it in respect to its rate of flow through time. It is pointed out that a PCM with a gain of unity produces a coupled EM wave/antiwave pair whose energy is additive in 3-space but subtractive in the first derivative of the fourth dimension, time. Hence it is no longer an electromagnetic wave as such, but an oscillatory wave of stress upon the local rate of flow of time. Hence it is a powerful *electrogravitational wave*, whose EM nature is hidden in the guise of a scalar EM potential. It is also a wave of variation in the local gauge, and of variation in the local ST curvature.

7. See T.E. Bearden, *The Phase Conjugate Vacuum Triode*, Apr. 23, 1987, privately published. An earlier pencil draft was initially produced.

8. Sweet has continued to extend his theoretical treatment. A formal paper providing the complete mathematical theory of the vacuum triode has been drafted, is in final review, and will be submitted to a leading journal by mid-1991.

9. See Chapter 25: Outlook, "Possibility of Vacuum Engineering," T.D. Lee, *Particle Physics and Introduction to Field Theory*, Harwood, New York, 1981, pp. 824-828.

10. In 1977 Ilya Prigogine received the Nobel Prize for extending thermodynamics; in particular, for the theory of dissipative structures in nonequilibrium thermodynamics. In Prigogine systems, negentropy is known to be possible.

11. Robert G. Sachs, *The Physics of Time Reversal*, Univ. Chi. Press., Chicago, 1987.

12. Note that this moves the entire notion of the charge of a fundamental particle to a deeper and more extended level. Now the charge may be *discretized*, but it is not quantized in the hard conventional sense. Further, the internal Whittaker structure of the massless VPF photon exchange of vacuum and mass, which, quantum mechanically, is what the electrical charge of the particle is in the first place, is deterministically structured. Note that this violates the present assumption that all like charged particles are identical; now two electrons may have either the same or different magnitudes of charge, and even when the magnitudes are the same, their internal charge structures (Whittaker structures) and VPF exchange with the vacuum may differ. Also note that this resolves the severe QM problem of missing chaos (hidden order) in quantum change. The reason for the problem was the use of Gibbs statistics with its assumption of random variable change, which a priori excluded hidden order (and hence chaos) from QM. That was only a special case, albeit an important one. There are now three QM cases: (1) the conventional case, where there is no hidden order; (2) the case where there is some hidden order, and the statistics is chaotic, not random; and (3) the case where the QM change is deterministic, with essentially total hidden order. Note that the Whittaker

methodology allows one to directly engineer cases (2) and (3), including the Schroedinger equation itself.

13. The present second law of thermodynamics is written only for time-forward entities, and need not apply for the time-reversed case. Merely viewing the energy-dissipating forward time case in reverse allows an appreciation of the time-reversed case. In other words, the second law of thermodynamics is incomplete as presently stated. The complete law has a corollary to cover the increase in order as the time-reversal of the system increases. Thus the complete law consists of two parts: (1) the entropic, time-forward case, and (2) the negentropic time-reversed case. Since the re-ordering can be amplified at will by a PPCM process, the correct distinction between the two subsets of the complete law is important, and applies to real systems.

14. A.D. Sakharov, *Theor. Math. Phys*., Vol. 23, 1975, p. 435.

15. T. E. Bearden, *Gravitobiology: A New Biophysics*, Tesla Book Co., 604 Date Ave., Chula Vista, CA 91912, 1991.

16. C.f. Charles W. Misner, Kip S. Thorne, and John Archibald Wheeler, *Gravitation*, W.H. Freeman and Co., San Francisco, 1973, p. 1191.

17. E.g., see Richard Kidd et al, "Evolution of the Modern Photon," *Am. J. Phys*., 57(1), Jan. 1989, pp. 27-35. See also R. Chen, "Cancellation of Internal Forces," *Am. J. Phys*. 49(4), Apr. 1981, p. 372.

18. A nonlinear material may simply emit a photon, or it may act as a phase conjugate mirror (PCM) and emit a phase conjugate replica of the absorbed photon. When the material emits a normal photon, it measurably recoils. When it emits a time-reversed photon, it does not recoil, as already experimentally established in nonlinear phase conjugate optics. The solution to the mystery is this: When emitting a normal photon, the material does not act as a PCM. In that case the matching antiphoton which split from the interacting graviton (the graviton that yielded the external photon) interacts with the nucleus, producing a recoil action with a gain of one. Thus Newtonian third-law recoil of the nucleus occurs. On the other hand, when the material acts as a PCM, it also emits the antiphoton *outside* the atom to "backtrack" the absorbed "signal wave" photon. In that case there is no Newtonian recoil of the nucleus, because the *agent* for causing recoil did not interact with the nucleus to produce it.

19. Richard E. Prange and Peter Strance, "The Semiconducting Vacuum," *Am. J. Phys*. 52(1), Jan. 1984, p. 19-21. Also, under nonlinear conditions, a particle can absorb more energy than is in the light incident on it, absorbing the energy from the vacuum VPF. C.f. Craig F. Bohren, "How Can a Particle Absorb More Than the Light Incident on It?" *Am. J. Phys*. 51(4), Apr. 1983, p. 323-327.

20. C.f. Pepper, ibid. and Yariv, ibid. For a specific example, see Mary J. Miller et al, *Appl. Phys. Lett*. 41(8), Oct. 15, 1982, p. 689-691.

21. Again, for the theory of the PPCM, see Pepper, ibid. and Yariv, ibid.

22. E.g., see T.E. Bearden, *Gravitobiology: A New Biophysics*, Tesla Book Co., Chula Vista, CA, 1991, p. 33-36.

23. Bearden, *AIDS: Biological Warfare*, Tesla Book Co., 1988; *Gravitobiology: A New Biophysics*, Tesla Book Co., 1991; *Analysis of Scalar Electromagnetics*, Tesla Book Co., 1990.

24. C.f. Vlail P. Kaznacheyev and L.P. Mikhailova, *Ultraweak Radiations in Intercellular Interactions*, [in Russian], Novosibirsk, 1981; Vlail P. Kaznacheyev, "Electromagnetic Bioinformation in Intercellular Interactions," *Psi Research*, 1(1), Mar. 1982, p. 47-76; N.D. Devyatkov, Ed., *Applications of Low-Intensity Millimeter Wave Radiation in Biology and Medicine*, [in Russian], IRE Akad. Nauk. SSSR, Moscow, 1985.

25. C.f. Antoine Priore, "Method of Producing Radiations for Penetrating Living Cells," U.S. Patent No. 3,280,816; Jean-Michel Graille, *Le Dossier Priore*, De Noel, Paris, 1984 [in French]; Christopher Bird, "The Case of Antoine Priore and His Therapeutic Machine: A Scandal in the Politics of Science," Appx. I to Bearden, *AIDS: Biological Warfare*, 1988.

26. C.f. Fritz Albert Popp, "Photon Storage in Biological Systems," in Fritz Albert Popp et al, Eds., *Electromagnetic Bio-Information: Proceedings of the Symposium*, Marburg, September 5, 1977, Urban & Schwarzenberg, Baltimore, 1979, p. 123-149; also *Biophotonen. Ein neuer weg zur Losung des Krebsproblems*, Verlag fur Medizin, Heidelberg, 1976 [in German].

Defense Department Briefing on Priore Treatment to counter Biological Warfare

---

SLIDE LIST

Solutions to Mass Casualties Treatment Problem

Threat and Current Status

1. Title Page
2. Key Points in the New Technology
3. Title Page
4. Title Page
5. The Terrorist Threat
6. The Superpower Paradox: Asymmetric Cheap WMD Strategic Strike and Destruction
7. Mass Casualty Problem: Aerial Anthrax Spray on Washington, D.C.
8. Present Status of the WMD Threat to the United States
9. Some Present Problems in the WMD Defense Capabilities

Historical Solution: Priore Treatment Therapy

10. Title Page
11. Priore's laboratory device for treating small animals
12. Antoine Priore with the Mayor of Bordeaux
13. Raymond Pautrizel, eminent French parasitologist, who worked with Priore
14. 12-Foot plasma tube in Priore's large device
15. Priore's 3 1/2 stories high device for whole body treatment of humans
16. Mechanism of the Priore therapy
17. Priore's therapeutic methodology: using infolded longitudinal EM waves as NLO pump waves, to pump in the time domain
18. Drastically reduced cumulative deterioration after Priore therapy

Extended Physics and Background

19. Title Page
20. Founders of Scalar Electromagnetics
21. Subdivisions of Soviet Energetics

22. Bunge on the Status of Classical and Quantum Physics
23. Einstein on Reviewing Foundations
24. Fields and Potentials have been "defined" only in and on matter
25. Maxwell's Equations are Matter-To-Matter Transforms
26. Electrodynamicists' Reaction to Removal of the Material Ether
27. The Missing Infolded Electrodynamics
28. Nonlinear Optics Distortion Correction Theorem
29. Infolded longitudinal EM biwave composition of a scalar potential
30. The Zero-Vector Axiom Destroys "Topologies Within Topologies"
31. Stoney-Whittaker Bidirectional Longitudinal EM Wave-Pair
32. Undistorted Progressive Waves (UPWs)
33. Velocity modulating a longitudinal EM wave oscillates rate of flow of time
34. The Graviton is a Coupled Photon/Antiphoton Pair
35. Mechanism for Physical Change and the Flow of Time
36. Any EM Field or Wave Pattern is Produced by interference of Two Scalar Potential Functions (E.T. Whittaker, 1904)
37. Mass is transparent to longitudinal EM waves, which move through the infolded interiors of internal waves, potentials, and fields in the mass
38. Deep penetration of weak signals in a dense signal environment, by nonlinear retroreflection
39. The Immune System
40. Popp's master cellular control system
41. Cancer: characteristics
42. The evolutionary path of multicellular organisms
43. Effect of fluid contamination on hemoglobin's oxygen transport
44. First step in Self-Promotion of Cancer due to Hypoxia
45. Becker's Cellular Growth Control
46. Becker's dc treatment of bone fractures
47. Becker's theoretical DC control system involved with responses to injury
48. Becker's theoretical control system governing regeneration
49. Link Between Standing DC Potentials and the Nervous System
50. Becker's Findings on Cellular Injury and Regeneration
51. Corrections For the Present EM Bioeffects Model
52. R&R System - Regeneration Example
53. Kaznacheyev's Cytopathogenic Mirror Effect
54. Microwave Radiation of U.S. Embassy in Moscow

55. Self-Targeting in Inner EM Channel Can Produce a Quantum Potential
56. Quantum potential and hidden variable theory
57. Participants in a quantum potential share a common multiply-connected spacetime (MCST)
58. Gulf War Syndrome and Typical Comparative Disease Curves
59. Force Fields and Symmetry
60. Aspects of Strong Local Asymmetry
61. Other Aspects of Strong Local Asymmetry
62. Small Entities Emit Powerful S-Flows
63. What is the "magnitude" of a potential?
64. Table A1. The Vacuum Energetically Interacts With Every Particle, Continually
65. Extended Superpotential Theory (Adding Vacuum Engines)
66. Vacuum Engine: Jillions of Working ST Demons
67. Active Spacetime and a Specific Vacuum Engine (A General Relativistic Concept and Analogy)
68. Extension of Wheeler's general relativity principle
69. Signal versus Vacuum Engine
70. Electronuclear Interactions by Vacuum Engines
71. Vacuum Engineering
72. Impact of Vacuum Engineering
73. A Dramatic Extension to Nonlinear Optical Pumping
74. Time Conservation and Some Properties (Energy and time are canonical)
75. A Dramatic Extension to Nonlinear Optical Pumping
76. Key Points in the New Technology

Modern WMD Solution: Portable Treatment Systems

77. Title Page
78. Portable Priore-Type Treatment System
79. Portable System Block Diagram
80. Portable Priore Technology Unit
81. Saving the Stricken Civilians

Conclusions: Technology Practical, Proven

82. Title Page
83. Summary and Conclusions

Recommendation: Crash Development Program

84. Title Page
85. Recommend implementing:
86. Final Thoughts



Terrorist WMD Strikes
on U.S. Cities:

Solution to
Mass Casualties
Treatment Problem

CTEC, Inc.

28 Mar. 1998

(c) 1998 T.E. BEARDEN

Return to Slide Index

Next Slide



Key Points in the New Technology

- There is a vast new kind of electrodynamics *hidden inside* all EM potentials, fields, and waves
  - Longitudinal EM waves and complexes
  - Oscillations in time domain
- These complexes are an *infolded general relativity*
  - Clustered formations of *spacetime curvatures*
  - *Very powerful*, since the EM force is used as the agent of curvature
- In general relativity, similar precise complexes permeate and *act on any mass at all internal levels*
- With this approach, one *can now manipulate matter* -- living or inert -- *in any manner desired*, depending only on the level of development of the technology
- Priore unwittingly used this to *cure dread diseases*
- This is a *revolution in all of science*
- *We have uncovered the major mechanisms* to utilize

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc.

28 Mar. 1998

© 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc.

28 Mar. 1998

© 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



THE TERRORIST THREAT

TODAY:

- Sabotage
- Chemicals
- Biological agents
- Nuclear materials
- Powerful explosives
- Assassination
- Kidnapping and hostages
- Contamination
- Shoulder-fired AD missiles
- Terrorism

FUTURE ADDITIONS:

- EM weapons
- EM biological warfare
- Scalar EM weapons
- Scalar EM disease induction
- Alteration of behavior and emotions
- Alteration of memory
- Direct thought control
- Action-at-a-distance effects

© 1992, 1996 T.E. BEARDEN

JCS-52

Return to Slide Index

Next Slide

Previous Slide



The Superpower Paradox: Asymmetric Cheap WMD Strategic Strike and Destruction

Complex, expensive, high tech

Simple, cheap, low tech

LIBYA
EGYPT
SUDAN
SAUDI ARABIA
IRAN
ISRAEL
LEBANON

© 1993, 1996, 1998 T.E. BEARDEN

[Return to Slide Index]

[Next Slide]

[Previous Slide]



Mass Casualty Problem: Aerial Anthrax Spray on Washington, D.C.

- One terrorist, one light aircraft with spray tank
- 100 kilograms of anthrax
- Flies over greater metropolitan Washington, D.C.
- Calm night
- *1-3 million casualties result**
- *Most of those stricken will die*
- Presently little can be done to save the stricken civilians
- *Attacks on several population centers might produce some 10 million or more casualties*

*Per OTA Report to Congress, 1993

Return to Slide Index

Next Slide

Previous Slide



Present Status of the WMD Threat to the United States

- Many foreign nations are hostile to the U.S. and sponsor terrorists
- Some 25 nations have WMD or are acquiring them
  - BW agents and weapons
  - Chemical agents and weapons
  - Nuclear materials and weapons
- Thousands of students and emigres
- Infiltrated teams, BW, other WMD already
- Castro guerrillas infiltrated over the years
- Can do unacceptable damage to U.S. now
- *May reach first strike knockout capability*

© 1998 T.E. BEARDEN

*Per OTA Report to Congress, 1993

Return to Slide Index

Next Slide

Previous Slide



Some Present Problems in the U.S. WMD Defense Capabilities

- *No shelters (require overpressure, BW filtering, masks, showers, supplies)*
- *No stockpiled vaccines, medical supplies, immunoglobulins, masks, suits, food, fuel, generators, heaters, water purification units*
- Totally insufficient medical facilities, personnel, and emergency response teams
- Triage, full martial law will be required
- *No answer to massive decontamination problem*
- State, county, city inadequately staffed and insufficiently trained for mass casualties
- Terrorist teams, BW agents, other WMD on site, waiting
- Water supplies, food, crops, farm animals also vulnerable
- Electric power grid, bridges, trains, railroads vulnerable
- *Present medical science cannot save very many of the casualties, now or in the foreseeable future*

© 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc.

28 Mar. 1998

(c) 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Priore's laboratory device for treating small animals

GIANT COIL WITH PLASMA MIXING TUBE INSIDE

SMALL ANIMAL HOLDER

[Return to Slide Index]

[Next Slide]

[Previous Slide]



Antoine Priore (right) with the Mayor of Bordeaux, Mr. Chaban-Delmas.

The Priore technical mechanism unwittingly involved a dramatic extension to both nonlinear optics and general relativity. However, nonlinear optics itself had not yet been born in the 1950s and 1960s when Priore worked out his methodology. The extension to general relativity has not been previously envisioned even to the present day. When the Priore project was suppressed by the changed French government in the mid-1970s, nonlinear optics itself was just being initiated. To the present day, however, there has previously been no inkling of the dramatic extension to NLO that arises by using longitudinal EM pump waves and thereby pumping in the time domain.

It is little wonder that Priore himself did not understand the nature of the technical mechanism he was utilizing, and neither did anyone else, and neither *has* anyone else prior to this time.

Photo courtesy of Bob Whitney

© 1998 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



Raymond Pautrizel, eminent French parasitologist who worked with Priore

Among other things, Pautrizel treated seriously infected immature rats with the Priore ray. These rats had never had a mature immune system. When they were removed from the machine, they still sickened again and died, because their immature immune systems could not resist the pathogen *(Trypanosoma)*. So even though the damaged cells were reversed back to normal, the "normal" immune system was unable to fight off pathogens, which reinfected the cells and killed them, killing the rats.

This established the time-reversal nature of the therapy.

© T.E. BEARDEN 1997

Return to Slide Index

Next Slide

Previous Slide



12-Foot plasma tube in Priore's large device

PHOTO COURTESY BOB WHITNEY

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



Priore's 3-1/2 stories high device for whole body treatment of humans

Giant coil
around 12-ft long
plasma tube

Pulsed DC
Magnetic field

Table for reclining
human body

Return to Slide Index

Next Slide

Previous Slide



MECHANISM OF THE PRIORE THERAPY

- FACT: DISEASE-SPECIFIC VACUUM ENGINE PRESENT FOR ANY CELLULAR DISEASE, BY WHEELER'S PRINCIPLE
  - *DISEASE CAN BE REVERSED BY CREATING AMPLIFIED VACUUM ANTI-ENGINE (BEARDEN'S PRINCIPLE)*
  - *ANTI-ENGINE IS CREATED BY PUMPING THE NONLINEAR CELLS IN THE "INNER EM" DOMAIN, TIME-REVERSING THEM*
- PRIORE UTILIZED A PLASMA TO PHASE CONJUGATE AND "INFOLD" MULTIPLE BIDIRECTIONAL LONGITUDINAL EM PUMP WAVES
  - *17 FREQUENCIES MIXED IN A ROTATING PLASMA*
  - *PHASE CONJUGATES ADDED BY THE PLASMA*
  - *INFOLDED MIX INTO STRONG PULSED DC MAGNETIC FIELD, WHICH CARRIED IT INTO ATOMIC NUCLEI*
  - *PUMPED ALL NONLINEAR CELLULAR COMPONENTS TO PRODUCE AMPLIFIED, SPECIFIC VACUUM ANTI-ENGINE*
- NEGATED THE LONG-TERM CUMULATIVE CELLULAR DEDIFFERENTIATION ORDER GENERATED BY LONG-TERM HYPOXIA. TUMOR CELLS REVERTED TO NORMAL CELLS.
- SCRUBBED OUT THE CUMULATED PRECANCEROUS STATE
- RESTORED THE IMMUNE SYSTEM TO HIGH FUNCTIONING
- NO EXCESSIVE TRAUMA TO TREATED ANIMAL

CANCR-69

© 1994, 1996, 1998 T.E. BEARDEN

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



Priore's therapeutic methodology: Using infolded longitudinal EM waves as NLO pump waves, to pump in the time domain

Time-reverses the cells back to normal state

START

FORM A SET OF HARMONIC EM WAVES (17)

ADJUST SOME WAVE FREQUENCIES

MIX WAVES IN A PLASMA TO ADD CONJUGATES

MIX OUTPUT INSIDE STRONG PULSED DC MAGNETIC FIELD

EXPOSE WHOLE BODY OF PATIENT TO DIMENSIONED MAGNETIC FIELD

CELL AND ALL ITS PARTS ARE PUMPED IN INNER EM CHANNEL IN TIME DOMAIN

VACUUM ENGINE FOR DISEASED CELL ALREADY PRESENT

DISEASED CELL PHASE CONJUGATES ITS VACUUM ENGINE

FORMS AMPLIFIED VACUUM ANTIENGINE FOR CELL'S DISEASE VACUUM ENGINE

TIME REVERSES CELL AND ALL ITS PARTS*

CELL RESTORED TO NORMAL?

YES

STOP

NO

*Includes genetics

© 1994 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



DRASTICALLY REDUCED CUMULATIVE DETERIORATION AFTER PRIORE THERAPY

NOTE: Priore therapy treats entire body.

BODY

Cells and tissues

Cancer Threshold

Body action point

MAGNITUDE OF SUSCEPTIBILITY

Deterioration after conventional treatment

Deterioration before treatment

Δ (conventional therapy)

Dramatically reduced deterioration after Priore therapy.

Separation from body action point

CONVENTIONAL THERAPY:

Scarring, physical damage, etc. Immune system deterioration.

PRIORE THERAPY:

No scarring or physical damage, etc. Immune system restored.

JCS-50

© 1993, 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc.

28 Mar. 1998

© 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Founders of Scalar Electromagnetics

- **G.J. Stoney:**

  Decomposed the scalar potential into bidirectional wave pairs.

  "On a supposed proof of a theorem in wave-motion," Phil. Mag., 5(43), 1897, p. 368-373 (and several other papers).

- **E.T. Whittaker:**

  Decomposed the scalar potential into a series of bidirectional EM wave pairs in harmonic series, where the two waves in each pair are conjugates (i.e., a wave/antiwave pair) and are longitudinal waves.

  "On the partial differential equations of mathematical physics," Math. Ann., Vol. 57, 1903, p. 333-355.

  Showed that all classical EM -- including waves -- can be replaced by two interfering scalar potential functions.. (This founded superpotential theory, extended by Nisbet, Bromwich, Debye, McCrea, and others.)

  "On an expression of the electromagnetic field due to electrons by means of two scalar potential functions," Proc. Lond. Math. Soc., Series 2, Vol. 1, 1904, p. 367-372.

- **R.W. Ziolkowski:**

  Independently rediscovered the biwave decomposition of the scalar potential and added the product set (in theory enabling modulations and communications) to Stoney and Whittaker's sum set.

  Various papers, 1985 to date.

© T.E. BEARDEN 1993, 1995

Return to Slide Index

Next Slide

Previous Slide



Subdivisions of Soviet Energetics

NONLIVING SYSTEMS

LIVING SYSTEMS

Energetics

- Nonliving systems
- Scalar Interferometry
- Action-at-a-Distance
- Quantum Potential
- Vacuum Engines
- Spacetime Structuring
- Material, Field Effects
- Nuclei, Lattice Changes
- Hidden EM Variables
- SWZ Effects

Bioenergetics

- Living Systems (Bodies)
- Cells, cellular changes
- Master Cell Control (Popp)
- Spacetime Structuring
- Disease Induction, Remission
- Action-at-a-Distance
- Quantum Potentials
- Scalar Interferometry
- Hidden EM Variables
- SWZ Effects

Psychoenergetics

- Living Systems (Minds)
- Thoughts, Memories, Emotions
- Conscious/Unconscious Minds
- Spacetime Structuring
- Species, Biospheric Minds
- Action-at-a-Distance
- Quantum Potentials
- Scalar Interferometry
- Hidden EM Variables
- SWZ Effects

© 1996 T.E. BEARDEN

Selected clipart © by IMSI MasterClips™

Return to Slide Index

Next Slide

Previous Slide



Bunge on the Status of Classical and Quantum Physics

"... it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state... the best modern physicist is the one who acknowledges that neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling not only to better cover their own domains but also to join smoothly so as to produce a coherent picture of the various levels of physical reality."

*Mario Bunge, Foundations of Physics, Springer-Verlag, New York, NY, 1967, p. 176..

© 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



EINSTEIN ON REVIEWING FOUNDATIONS

"...the scientist makes use of a whole arsenal of concepts which he imbibed practically with his mother's milk; and seldom if ever is he aware of the eternally problematic character of his concepts. He uses this conceptual material, or, speaking more exactly, these conceptual tools of thought, as something obviously, immutably given; something having an objective value of truth which is hardly even, and in any case not seriously, to be doubted. ...in the interests of science it is necessary over and over again to engage in the critique of these fundamental concepts, in order that we may not unconsciously be ruled by them."

Albert Einstein, "Foreword," in Max Jammer, Concepts of Space: The History of the Theories of Space in Physics, Harvard University Press, Cambridge, Massachusetts, 1969, p. xi-xii.

JCS-11A

© 1993 T.E. BEARDEN

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



Fields and Potentials have been "defined" only in and on matter

E ≡ F/q
exists on
mass only

Note problem!
No "E" or "H"
in vacuum.

S = ExH

Source q is a
broken symmetry
in vacuum flux

S = ExH

Point
Coulomb

"pileup" in front
produces energy
density gradient
across the point
coulomb

So E ≡ -∇ϕ

ϕ ≡ joules continuously
in geometrical flow
distortion zone around
one point coulomb

[Coulombic energy collection density]

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



© T.E. BEARDEN 1998

Einstein's Spacetime

Maxwell's Material Ether

Material Ether Fluid Perturbations

Material Electric Fluid Disturbed

Φ, ϕ, E, B, H etc.

(Material entities)

Material Electric Fluid Disturbed

All Maxwell's EM entities are defined only in and of charged matter. All are material entities. There was no place devoid of mass, in the universe.

MAXWELL'S EQUATIONS ARE MATTER-TO-MATTER TRANSFORMS

Return to Slide Index

Next Slide

Previous Slide



NONMATERIAL SPACETIME

© T.E. BEARDEN 1998

Michelson-Morley experiments, 1880's

Material Fluid Perturbation Equations

MAXWELL

MAXWELL

Material Electric Fluid Disturbed

Material Electric Fluid Disturbed

Now we are not using a material ether. Trust us! Equations do not need changing.

ELECTRODYNAMICISTS

Electrodynamicists' Reaction to Removal of the Material Ether

Return to Slide Index

Next Slide

Previous Slide



THE MISSING INFOLDED ELECTRODYNAMICS

Maxwellian electrodynamics has nothing at all to say about EM entities in space or their form

Material Electric Fluid Disturbed

MATTER-TO-MATTER TRANSFORM

Material Electric Fluid Disturbed

MATTER-TO-SPACETIME TRANSFORMATION

INFOLDED INSIDE MAXWELLIAN EM AS HIDDEN EM VARIABLES

SPACETIME-TO-MATTER TRANSFORMATION

INTERNESTED SPACETIME CURVATURES

(VACUUM ENGINES)

INFOLDED GENERAL RELATIVITY

EINSTEIN'S SPACETIME

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Nonlinear Optics Distortion Correction Theorem

E_1 = INCIDENT WAVE

E_2 = TIME-REVERSED WAVE

"If a scalar wave $E_1(r)$ propagates from left to right through an arbitrary but lossless dielectric medium, and if we generate in some region of space [say near $z = 0$] its phase conjugate replica $E_2(r)$, then E_2 will propagate backward from right to left through the dielectric medium, remaining everywhere the phase conjugate of E_1."

JCS-64

© 1994, 1995, 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Infolded longitudinal EM biwave composition of a scalar potential

GALLOPING VELOCITY
Scalar Potential ϕ
© T.E. BEARDEN 1997
...ETC.
* * * ...ETC.
Vavg
Wavepair #3
HARMONICS
Vavg
Wavepair #2
SUBHARMONICS
Vavg
Wavepair #1
...ETC.
* * * ...ETC.
DISTANCE

The Structure Is:

A harmonic set of longitudinal EM wavepairs. In each wavepair the two waves superpose spatially, but travel in opposite directions. The two are phase conjugates and time-reversed replicas of each other. Thus they comprise a coupled longitudinal wave and antiwave. The photons must be coupled into photon/antiphoton pairs (gravitons) by a strong application of the distortion correction theorem of nonlinear optics. Each wave in the biwave pair is a galloping wave. Each wavepair is a standing electrogravitational wave. In nonlinear optics, such a wavepair is a pump wave which pumps in the time domain.

Note: Think of the oscillations as velocity modulations.

Return to Slide Index

Next Slide

Previous Slide



The Zero-Vector Axiom Destroys "Topologies within Topologies"

- The axiom: There is a unique vector, $\overline{0}$, in V (the vector space) such that
  $\overline{V} + \overline{0} = \overline{0} + \overline{V}$
- Note that $\overline{V} + \overline{0}_i = \overline{0}_j + \overline{V}$; $\overline{0}_i = -\overline{0}_i = n\overline{0}_i$
  so $\overline{0}_i = \overline{0}_j = \overline{0}_k = \ldots + \overline{0}_n = \ldots$
- This makes all $\overline{0}_i$ equal by assumption, since there is *assumed* to be only a single type $\overline{0}$ without real components
- In fact, $\overline{0}$ is *not unique*. An *infinite number* of different zero-vector systems, with real components, satisfy the zero-vector axiom.

Return to Slide Index

Next Slide

Previous Slide



STONEY-WHITTAKER BIDIRECTIONAL LONGITUDINAL EM WAVE PAIR

(An electrogravitational wave)

Total time densities are additive, so "wave" appears "static" (standing) and gravitational

A wavelike variation in the local time density of the vacuum. The velocity of the EM wave oscillates. The amplitude of the EM wave does not change.

Hidden forward time EM time density flow

Hidden reversed-time time density flow

To any affected or exposed unipolar object, EM force operations cancel due to simultaneous time action and reaction

A coupled EM wave/antiwave pair infolds electromagnetic energy, converting it to gravitational energy. The wavepair becomes an electrogravitational standing wave.

© 1993, 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Undistorted Progressive Waves (UPWs)*

(waves with velocity v, where $0 \leq v \leq \infty$)

- Major equations of interest having UPW solutions are:
  - *Homogeneous wave equation*
  - *Maxwell equations*
  - *Dirac, Weyl, and Klein-Gordon equations*
- UPWs are translationally invariant, and do not spread, or they reconstruct their original form after a certain period.
- UPW solutions have infinite energy. Quasi-UPWs can have finite energy and can in principle be launched into space.
- Subluminal Maxwell solutions are called *EM particles*. Superluminal Maxwell solutions are called *X-waves*.
- *Experimental results indicate such waves will be produced within the next few years.*
- *Nimtz has translated Mozart's 40th symphony at v = 4.7c.*

*Rodrigues and Lu, *Found. Phys.* 27(3), 1997, p. 435-508.

© 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Velocity modulating a longitudinal EM wave oscillates rate of flow of time

$$V = \frac{L}{t}$$

Observer sees it this way

Constant transverse wave magnitude

Wave oscillates its velocity along its path, about a nominal value

Wave oscillates this way

Constant transverse magnitude

Wave oscillates magnitude of its transported t, about a nominal value

Note:

- Waves consist of photons
- Each photon consists of energy x time
- Each photon carries time as well as energy
- A wave is both a spatial energy dynamics and a temporal dynamics
- Wave complexes carry dynamic time structures as well as dynamic energy structures

© 1997 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



The Graviton Is a Coupled Photon/Antiphoton Pair
(Both photon and antiphoton are longitudinal)

In physics, the primary units selected are arbitrary. Everything can be expressed, e.g., in terms of time alone. Thus so can photon spin.

IS THIS A SPIN 2 ENTITY?
It is, in the time domain.

ACTION
VACUUM ENGINE
REACTION
LONGITUDINAL PHOTON
LONGITUDINAL ANTIPHOTON

© 1988, 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Mechanisms for Physical Change and the Flow of Time

SPATIAL
SPATIOTEMPORAL
PHOTON
SPATIAL
PHOTON
MASS
L^3
L^2T
MASSTIME
L^3T
L^2T
MASS
L^3

$$(\Delta E)(\Delta t) + M \Rightarrow (M+\Delta M)\Delta t \Rightarrow M + (\Delta E)(\Delta t)$$

Flow of macroscopic time (observable photon interactions)

SPATIAL AND SPATIOTEMPORAL
"MASS"
MASSTIME
L^3T
MASS
MASS
MASSTIME
L^3T
"MASS"

Flow of microscopic time (via virtual photon interactions)

The photon interaction generates an observed quantum change and a discretized jump in the rate of time flow. A particle observably changes by only a single Δt at a time. The background flow of time in which the jump in rate occurs, is created by the continual absorption and emission of virtual photons.

© 1994 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Any EM Field or Wave Pattern Is Produced by interference of Two Scalar Potential Functions *(E.T. Whittaker, 1904)*

(Use of Hidden Information Content of the Field)

(Can Provide Action-at-a-Distance)

Note:
Whittaker's 1904 paper initiated the entire field of superpotential theory.

Interference Zone
(Potential gradients)
Normal EM Energy:
May be positive, or
negative, or fixed

Hidden
Bidirectional
EM energy flow

Hidden
Bidirectional
EM energy flow

Scalar Potential
Beams

Whittaker/Ziolkowski
Transmitter Arrays

(8 to 20 harmonic wavepairs each)

© T.E. BEARDEN 1997

Return to Slide Index

Next Slide

Previous Slide



Mass is transparent to longitudinal EM waves, which move through the infolded interiors of internal waves, potentials, and fields in the mass

MASS MEDIUM
Ambient Vacuum Potential
EM Wave
Static EM Field
D.C. Potential
Ambient Vacuum Potential
© T.E. BEARDEN 1997

Mass is mostly ambient vacuum potential, modified by internal potentials, fields, and waves. Any wave or field is just two scalar potential functions, by Whittaker 1904.

Return to Slide Index

Next Slide

Previous Slide



Deep penetration of weak signals in a dense signal environment, by nonlinear retroreflection

Nonlinearity
Internal potentials and weak signal emissions occur from these internal operating EM components
Cross-Section of Body
Body Surface
Enlargement of nonlinearity area
Pumped Retroreflection Phase Conjugate Mirror (PCM) Effect due to multi-photon interactions
Dense Signal Environment (May be very weak signals)
PCM
PCR*
PCR
Amplified Partial Cancellation of Body's Internal Signals by addition of phase conjugate replicas

In a dense signals environment, probability of simultaneous signals interacting increases. This increases the probability of deep penetration by amplified phase conjugate reflections of weak internally generated signals from the interior, impinging upon the pumped (stressed) nonlinear surface areas where the simultaneous exterior interactions occur.

* Phase conjugate replica

© 1993, 1995 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide

THE IMMUNE SYSTEM



BONE MARROW

Lymphocytes

Special Defense

Intestinal tissue, liver, etc.

Thymus

Complement system

General Defense

Feeding cells

Monocytes

B-lymphocytes

suppressor cells

plasma cells

antibodies

T-lymphocytes

killer cells

helper cells

complement factors

granulocytes

macrophage

bacterium (foreign invader)

CANCR-18

©1993 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



Popp's master cellular control system

- Provides coherent, long-range interactions in biological systems
- Is an organized morphogenetic field at the basis of functional control

- Emission very sensitive to almost all external and internal influences
- Both spontaneous and delayed luminescence occur
- Photons stored in cell during the delay

- Leakage provides ultraweak, coherent biophoton emission from the system
- Fractional intensity pattern: few to some 100s of photons/cm^2/sec
- Optimum signal-to-noise ratio

- A single delayed biophoton may be able to trigger 10^{10} reactions in a cell before its release
- Spectrum almost continuous within optical range from 200-800 nm.

- Biophoton emission shows biological system always out of equilibrium
- Emission has holistic characteristics
- Correlations to most, if not all, of the biological functions of the organism

- DNA, all other processes are sources
- Single main process of whole system, different processes strongly coupled
- Information function and sync of biological clocks (oscillators)

(c) 1997 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



CANCER: CHARACTERISTICS

- NOT ONE DISEASE BUT A WHOLE RANGE
- STARTS IN ORDINARY (AEROBIC) CELL
- CELL SHAKES OFF BODY'S DICTATORIAL CONTROL*
- STARTS UNCONTROLLED DIVISION
- BECOMES A LUMP
- CAN SEND FORTH CANCER CELLS
  - THROUGH BLOOD
  - THROUGH LYMPH
- THESE FORM METASTASES (SECONDARY TUMORS)
- OFTEN BECOME ANAEROBIC (NON-OXYGEN USING)
- ENIGMA IS FAILURE OF IMMUNE SYSTEM TO ATTACK SOME TUMOR CELLS
  - SUPPRESSOR CELLS MAY CURB IMMUNE SYSTEM
  - TUMOR MAY LACK ANTIGENS NORMALLY IDENTIFIED BY THE IMMUNE SYSTEM

*R&R system forces cell back toward anaerobe

CANCR-26

© 1993 T.E. Bearden

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



THE EVOLUTIONARY PATH OF MULTICELLULAR ORGANISMS

ESSENTIALLY ANAEROBIC ATMOSPHERE

CHANGE OF ATMOSPHERE TO AEROBIC (INCLUDES OXYGEN)

BIOGENESIS

SINGLE CELL ANAEROBIC

OBLIGATORY ANAEROBES SINGLE CELL SHIELDED FROM OXYGEN

FACULTATIVE ANAEROBES (SINGLE CELL BOTH AEROBIC AND ANAEROBIC)

EVOLVE TO

SINGLE CELL AEROBIC*

EVOLVE TO

MULTICELL AEROBIC* (INCLUDES MAN)

CENTRAL CONTROL

SINGLE CELL COMPONENTS

- IMMUNE SYSTEM
- RED CELLS
- WHITE CELLS
- KILLER CELLS
- ETC.

MULTICELL COMPONENTS

- TISSUES
- MUSCLES
- BONES
- ORGANS
- SKIN
- STRUCTURES

* *NOTE: LIMITED ANAEROBIC RESPIRATION STILL TAKES PLACE IN HIGHER AEROBIC LIFE FORMS, INCLUDING MAN.*

EVOLUTIONARY TIME

CANCR-01

c 1993 T.E. Bearden

[Return to Slide Index]

[Next Slide]

[Previous Slide]



EFFECT OF FLUID CONTAMINATION ON HEMOGLOBIN'S OXYGEN TRANSPORT

RED BLOOD CELLS
AIR
Severe pollution
Severely reduced oxygen transport
(Such as cigarette smoke)
RED BLOOD CELLS
LUNG SACS
BODY
ATMOSPHERE

CANCR-09

© 1993 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



FIRST STEP IN SELF-PROMOTION OF CANCER DUE TO HYPOXIA

* NOTE: LIMITED ANAEROBIC RESPIRATION STILL TAKES PLACE IN HIGHER AEROBIC LIFE FORMS, INCLUDING MAN.

MULTICELL
AEROBIC*
(INCLUDES MAN)

SINGLE CELL
ANAEROBIC

SINGLE CELL
AEROBIC*

CENTRAL CONTROL

OXYGEN-RICH

TIME-FORWARD
PATH AS IT
DEVELOPED

TIME-REVERSED
PATH FOR SUSTAINED
OXYGEN DEFICIENCY

SINGLE CELL
AEROBIC*

FIRST STEP IN OXYGEN-DEFICIENCY
DEDIFFERENTIATION

CANCR-08

© 1993 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



BECKER'S CELLULAR GROWTH CONTROL

- Two major links uncovered between :
  - The DC system and nervous system
  - The DC system and all body cells
- Bioelectric potentials of primary importance
- Physiology presently considers controls limited to:
  - Neural action potential
  - Various hormone chemical agents
  - Chemical agents associated with DNA/RNA system
- Complete Operational Biological Control System:
  - Controls growth, healing, biological cycles, etc.
  - Operates in ANALOG mode; various levels of DC
  - Interlocks physically with nervous system (and may be its precursor)
  - Other chemical agents
  - Tissue growth and healing NOT INCLUDED
- Medical community now more concerned with diseases resulting from:
  - Inadequate/abnormal growth
  - Inadequate healing

Return to Slide Index

Next Slide

Previous Slide



Becker's dc treatment of bone fractures

Application of tiny DC currents to heal difficult bone fractures. Only picoamperes are utilized. Pulsed DC current or pulsed magnetic fields may also be utilized.

(+)
ELECTRODE
(-)
DC POWER SOURCE
ELECTRODE
BONE
BONE
FRACTURE SITE
BECKER'S
BONE FRACTURE SETUP
(DIAGRAMMATIC)

RED BLOOD CELL DEDIFFERENTIATES

Shucks hemoglobin coat
Grows nucleus

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes cartilage

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes bone
Deposits in fracture site, healing the fracture

Proves that cells can be time-reversed (phase conjugated) (dedifferentiated) or time-forwarded (redifferentiated) by application of very weak electromagnetic signals, when those signals contain longitudinal bidirectional EM "pump wave" wavepairs, which cause the cell and its parts to create precise vacuum antiengines.

© 1993, 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



*Becker's theoretical DC control system involved with response to injury**

INJURY

INPUT STIMULATION DC SYSTEM (PAIN)

CENTRAL DC SYSTEM

GROWTH DIFFERENTIATION

LOCAL CELL INJURY FREE RADICALS

OUTPUT DC SYSTEM

MITOSIS DEDIFFERENTIATION

STIMULATION OF REPAIR CELLS

TOTAL CURRENT OF INJURY DC SYSTEM

*Robert O. Becker, "The significance of bioelectrical potentials," Bioelectrochemistry and Bioenergetics, Vol. 1, 1974, p. 191.

[Return to Slide Index]

[Next Slide]

[Previous Slide]



Becker's theoretical control system governing regeneration*

Trauma Producing Tissue Loss

Local cellular effect

Local nerve effect

CNS effect

Alterations in hormone pattern (prolactin)

Alterations in local DC field pattern

Local electrical effects

Local and systemic pools of target cells

Dedifferentiation into primitive mesenchymal cells

Phase I

Blastema formation

growth

Phase II

Redifferentiation into required cell types

Restoration of body part or tissue

*Becker & Spadaro, "Electrical stimulation of partial limb regeneration in mammals," Bull. N. Y. Acad. Med., 48(4), May 1972, p. 629.

Return to Slide Index

Next Slide

Previous Slide



Link Between Standing DC Potentials and the Nervous System

- Standing DC potentials on intact surfaces of all living animals demonstrate a complex field pattern spatially related to the anatomical arrangement of the nervous system
  - Can be measured directly on the peripheral nerves
  - Polarity difference related to whether nerve is or is not a sensor
  - Steady (weak) current flow exists
  - Demonstrates solid state/semiconductor phenomena
  - Accurately reflects (amplitude and polarity) the general level of neural activity
    - Sleep versus wakefulness
    - Anesthesia versus conscious
    - Other parameters
- DC levels determine the level of neural activity
- Action potential system exists upon a substratum of DC potentials which pre-existed it
- DC potentials substrata had and have control functions over basic properties of the living organism

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Becker's Findings on Cellular Injury and Regeneration*

- Cellular processes are regulated by a precise control system
- Attempted to apply engineering control-system theory
- Cells and tissues have solid-state electrochemical features which provide control signals in the control system
  - Growth process
  - Electron transfer
  - Semiconduction
  - Self-organizing *(NOTE: Implies hidden variables and nonlocal causality)*
- Complex electrical events at the injury site initiate cellular aspects such as dedifferentiation and mitotic activity
- Regeneration is a 2-step process, each with different controls
  - Electrical triggers with threshold values results in appearance of blastema
  - Complex data transmission to blastema establishes it as a self-organizing system capable of growth and redifferentiation
  - Mammals lack ability to produce blastemas except for bone, but partial regeneration growth has been shown in response to electrical stimuli
- Growth related to electrical more than electrochemical aspects
- Hematopoietic marrow as source of cells for the blastema
  - Monocytes can take place in regenerative processes in limbs
  - Lymphocytes can dedifferentiate under certain circumstances
  - Marrow elements can be induced into osteogenesis

*R.O. Becker & J.A. Spadaro, "Electrical Stimulation of Partial Limb Regeneration in Mammals," Bull. N. Y. Acad. Med., 48(4), may 1972, p. 627-641.

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Corrections For the Present EM Bioeffects Model

START

A

OVERALL STIMULUS/RESPONSE MODEL

1. EM STIMULUS/ RESPONSE MODEL

2. EXPERIMENT OR GROUP OF EXPERIMENTS

3. INSTRUMENTATION AND RECORDING

4. INTERPRETATIVE MODEL AND COMPARATIVE STANDARD

5. INTERPRETED RESULTS

6. EM THEORY TO BE APPLIED

7. ARE RESULTS CONSISTENT?

YES

NO

8. EM THEORY CORRECT

STOP

9. EM THEORY INCORRECT

PRESENT INADEQUATE EM BIOEFFECTS MODEL

IMCS/EM ASSUMPTIONS

1. PRESENT EM MODEL CORRECT AND COMPLETE

2. DOSAGE/RESPONSE SYNONYMOUS WITH STIMULUS/RESPONSE

10. FIND ERRORS IN EM THEORY POSTULATES

11. CHARGE DISCRETE, NOT QUANTIZED. VIRTUAL FLUX CAN BE STRUCTURED, FOR VACUUM ENGINES.

12. RETAIN ZERO VECTOR RESULTANT SUMMATIONS OF EM FORCE VECTOR COMPONENTS AS VACUUM ENGINES

13. FORCEFIELDS NOT PRIMARY. POTENTIALS ARE. HAVE HIDDEN EM WAVE STRUCTURE.

19. SEPARATE CHARGE Q INTO ITS COUPLED COMPONENTS

14. ADD WHITTAKER EM STRUCTURE OF POTENTIALS THEORY

15. ADD TO GENERAL RELATIVITY AND QUANTUM MECHANICS

16. CORRECT/EXTEND EM AND SHOW UNIFIED FIELD AND MIND/VOLITION

17. DEVELOP NEW TYPES OF INSTRUMENTS

18. CORRECT EM THEORY MODEL, INSTRUMENTATION AND RECORDING, AND IMCS

JCS-44

(c) 1991, 1993, 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



PRIORE AMPLIFIED PUMPING

R&R SYSTEM
Regeneration Example

© T.E. BEARDEN 1998

ADD PUMPS
B
CELL AS A PHASE CONJUGATE MIRROR
RESIDENT VACUUM ENGINE
ANTIENGINE PRESENT?
N
Y
APPLY ANTIENGINE
B
START
A
CYCLE
CELL AND INTERIOR SENSORS
LOCAL VICINITY SENSORS
NONLOCAL ALL-BODY SENSORS
DELTA CATALOGS
CELLS AND INTERIORS
SELECT LOCAL
SELECT NONLOCAL
AEROBE
ANAEROBE
DELTA?
Y
N
DELTA?
Y
N
DELTA?
Y
N
AEROBE
ANAEROBE
AEROBE
ANAEROBE
AEROBE
ANAEROBE
SWITCH TO AEROBE CONTROL SYSTEM
A
CROSS THRESHOLD BACK TO AEROBE?
Y
N
SWITCH COMPARATIVE CATALOG
SWITCH TO ANAEROBE CATALOG
END OF AEROBE CATALOG?
Y
N
SUM FOR ENTIRE BODY
SWITCH ON CENTRAL, OFF DECENTRAL GROWTH CONTROL; RESET IMMUNE SYSTEM
SWITCH OFF CENTRAL GROWTH CONTROL
SWITCH ON DECENTRAL GROWTH CONTROL
CONDITION IMMUNE SYSTEM TO ACCEPT
A

Return to Slide Index

Next Slide

Previous Slide



Kaznacheyev's Cytopathogenic Mirror Effect

Disease vacuum engines transported by photons and waves

GRAVITON
LATTICE
TEMPLATES
SICKEN
OR KILL
ENVIRONMENTAL
SHIELDING
CELL
CULTURE
SAMPLE
#1
QUARTZ
CONTAINER
CELL
CULTURE
SAMPLE
#2
QUARTZ
CONTAINER
THIN WINDOW
GLASS: No Effect
QUARTZ: Delayed Effect
Divided bottle
set-up

© T.E. BEARDEN 1977, 1987

Note: Minimum lattice is one harmonic interval: IR to UV is such a minimum G-lattice.

Distant induction of cellular death and diseases, by special EM means. Coupled photon-antiphoton pairs (gravitons) in a structured harmonic lattice ordering constitute the disease or disorder template.

Return to Slide Index

Next Slide

Previous Slide



MICROWAVE RADIATION OF U.S. EMBASSY IN MOSCOW

Former U.S. Embassy in Moscow.

BACKGROUND

- Began in latter 1950s
- Discovered on VP Nixon's trip
- Initially thought to be *nuclear* radiation (Discovered w/Geiger counter?)
- High level target -- U.S. Ambassador
- Guarantees personal attention of:
  - U.S. Ambassador to USSR
  - U.S. President
  - NSA, CIA, DIA, NSC, etc.
  - Top consulting scientists
  - Leading U.S. scientific institutions
- Two U.S. Ambassadors died, another sickened
- Anomalous health changes in personnel, only in zero-field (zero pot'l gradient) areas!
- Four U.S. Presidents requested Soviets cease
  - Cut from 18 watts/sq cm to 2
  - Then again increased
- No one could understand what was going on
- Aluminum screens were placed over windows
- Moscow was declared a hazardous duty zone

Selected clipart © by Lotus SmartPics™

© 1995, 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Self-Targeting in Inner EM Channel Can Produce a Quantum Potential

Once QP is established, energy transmission is direct and instantaneous. Energy input to one single participant will simultaneously appear in all other participants, the amount depending on their fractions of participation with the input station.

NARROWING OF INTERACTING POTENTIALS INTO LASER-LIKE BEAMS, BETWEEN TWO PUMPED SOURCES. NOW ONLY LONGITUDINAL WAVES CONNECT THE LINKED OBJECTS.

SELF-TARGETING EFFECT AMONG ALL PAIRS OF INTERACTING PUMPED SOURCES

© 1989, 1995, 1996 T.E. BEARDEN

[Return to Slide Index]
[Next Slide]
[Previous Slide]



Quantum potential and hidden variable theory

a. Quantum Potential Characteristics

© 1988, 1995, 1997 T.E. BEARDEN

- No point source
- Not radiated
- Quantum potential between two particles
  - Interaction does not vanish as spatial separation becomes very large
  - Instantaneous connection, so multiply-connected space

b. Hidden Variable Theory and the Quantum Potential

- $V_{quantum} = \frac{\hbar}{2m} \frac{\nabla^2 \sqrt{\rho}}{\sqrt{\rho}}$
- "A quantum particle moves as if it were subject, in addition to its external potentials, to a potential which is a function of its own probability distribution."
- Bohm's H.V.T. assumes:
  - Particle and wave function real and separate
  - Wave function obeys Shroedinger's equation
  - Particle obeys classical mechanics
  - Particle couples to wave function through a quantum potential

Return to Slide Index

Next Slide

Previous Slide



Participants in a quantum potential share a common multiply-connected spacetime (MCST)

- Separated points are superposed in MCST
- Intervening distance in MCST is zero
- Connection is instant and bidirectional
- Propagation through ST does not apply
- Energy or vacuum engine input to one station instantly appears at each and every other station, undiminished in magnitude
- Ultimate net-centric warfare effect

Note: Once QP established, separation distance in 3-space is of no consequence

Note: Vulnerability. Any other station may insert energy or vacuum engines into the same quantum potential. Phase conjugating the hostile engine can negate its effect everywhere

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Gulf War Syndrome And Typical Comparative Disease Curves

Note: There is cumulative genetic damage to germ cells also.

— — —	EXPOSED WITH MOST CUMULATIVE DAMAGE
-·-·-·-·	EXPOSED WITH MULTIPLE AGENT INFECTIONS AND RECEIVING MULTITREATMENT
**********	EXPOSED WITH LESS CUMULATIVE DAMAGE
——	NON-GULF WAR: TYPICAL NORMAL DISEASE WHICH KILLS PATIENT

JCS-100

ⓒ 1996 T.E. BEARDEN

[Return to Slide Index]
[Next Slide]
[Previous Slide]



Force Fields and Symmetry

- Force fields are nature's way of imposing local gauge symmetries on the world
- E.g., electromagnetic field is a manifestation of the simplest known gauge symmetry consistent with the principles of special relativity
- For the EM case, the gauge transformations correspond to changes in 'voltage' from place to place

© T. E. Bearden 1995, 1996

Return to Slide Index

Next Slide

Previous Slide



Aspects of Strong Local Asymmetry

- If local asymmetry is strong, conservation laws may be appreciably violated
  - Energy
  - Charge
  - Spin
  - Momentum
  - Angular momentum

© T. E. Bearden 1995, 1996

- Properties of an object may differ appreciably for
  - Different observers
  - Different detecting means
  - One time to another
  - One position to another
- STRUCTURING THE INFOLDED EM INSIDE POTENTIALS, FIELDS, AND WAVES
  - Strongly breaks local symmetry
  - Provides spacetime engines giving the above effects

Return to Slide Index

Next Slide

Previous Slide



Other Aspects of Strong Local Asymmetry

© T. E. Bearden 1995, 1996

- Local spacetime is curved
- Lorentz invariance of vacuum is violated
- May be a local "sink" or "source"
- Gravitational/inertial effects from EM
- Translation between virtual and observable
- Electrogravitational solitons
- Action at a distance
- Transmutation effects may exist
- Scalar/pseudoscalar field translation
- COMMENT: Thus the use of infolded longitudinal EM fields and waves to strongly break local symmetry allows internested clustering of spacetime curvatures. These spacetime structures are *vacuum engines*, or *spacetime engines*.

Return to Slide Index

Next Slide

Previous Slide



Small Entities Emit Powerful S-Flows

$V = 10^{-3}\ volts$

Surface layer of fluid atoms
Cellular membrane surface

$d = 10^{-9}\ meter$

$$E = 10^{6}\ \text{volts / meter}$$

$$S \approx f(E^{2}) = f(10^{12})$$

© 1997 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



What is the "magnitude" of a potential?

- What is taught is the *"interaction cross section,"* i.e., the joules collected from the associated S-flow by one point coulomb of intercepting/collecting charge.

$$W = Vq = \phi q \quad \text{(joules)} \quad [1]$$

$$\phi = W/q \quad \text{(joules/coul)} \quad [2]$$

$$\text{Let } \phi < 1 \text{ and fixed; } q \Rightarrow n \text{ where } n = \infty$$

$$W \Rightarrow k, \text{ where } k = \infty \quad [3]$$

- *From any "finite" potential, no matter how small, an unlimited amount of energy can be collected, by increasing the collection (number of coulombs) (interaction cross section).*
- Actual magnitude of the potential ϕ must be very, very large, since we can treat it as infinite or unlimited, via $W = \phi q$.
- *Else Equation [1] could not be linear.*

© T.E. BEARDEN 1997

Return to Slide Index

Next Slide

Previous Slide



Table A1. THE VACUUM ENERGETICALLY INTERACTS WITH EVERY PARTICLE, CONTINUALLY.

- The vacuum is:
  - Ground (zero) state of the electromagnetic (photon) field.
  - Ground (zero) state of mass field.
  - Empty of *observable* particles or photons.
  - Filled with *non-observable* (virtual) particles and photons.
  - Violently fluctuating microscopically and electromagnetically.
  - Constantly interacting with all particles, including partially shielding their bare charges.
- Lamb Shift -- vacuum's alteration of the energy level of an electron in the hydrogen atom.
  - -- Difference in energy (frequency units) is 1057.862 MHz.
  - -- Lamb was awarded a Nobel Prize for showing this.
  - -- Energy *density* exceeds that of the sun's surface!
- Casimir Effect -- vacuum creates an attraction between two conducting surfaces in close proximity.
  - -- experimentally proven, well-known.
- Cole and Puthoff proved that there is no thermodynamic reason why energy cannot be extracted from the vacuum as heat and power, and utilized.
- The common dipole is a broken symmetry in the virtual photon flux of vacuum. It extracts virtual energy, integrates it, and re-emits it as Poynting energy density flow S = ExH (which observably interacts with charged particles and magnetic poles).

Return to Slide Index

Next Slide

Previous Slide



Extended Superpotential Theory

(Adding Vacuum Engines)

- Any EM field or wave is created by (comprised of) two potentials which interfere with each other in a given area
  - *May be either scalar or vector potentials*
  - *May interfere locally or at a distance*
  - *Process is distance independent*
- Any scalar potential is comprised of a harmonic series of bidirectional longitudinal EM wavepairs (Whittaker 1903).
- Ziolkowski circa 1985 added the interior product set to Whittaker's sum set. Thus he added modulations.
- By assembling a deliberate "sum and product" set of biwaves, a scalar potential can be created having an internal deterministic structure.
  - *This structures local vacuum potential/spacetime curvatures, in specific forms (templates)*
  - *Now have added vacuum engines*
  - *Have infolded general relativity inside electrodynamics*

© 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Vacuum Engine: Jillions of Working ST Demons

Internested patterns of spacetime curvature

Structured Einsteinian spacetime

Demons are EM hidden variables organized into dynamic structures at all levels

Demons work at all levels

© T.E. BEARDEN 1998

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



Active Spacetime and a Specific Vacuum Engine

(A General Relativistic Concept and Analogy)

ACTIVE SPACETIME
DYNAMIC MASS
STRUCTURING OF ACTIVE SPACETIME CURVATURES
DETAILS OF STRUCTURING OF ACTIVE SPACETIME CURVATURES (TEMPLATE)
mass structures spacetime
spacetime structures act on mass at all levels

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Extension of Wheeler's general relativity principle:

- Mass (trapped energy) and its structuring curves and structures spacetime complexes (engines).
- Curved and structured spacetime engines produce forces on mass and its components, telling them how to move and structure.
- Since very strong EM force is used as agent of curvature, very powerful general relativistic effects can be obtained by arranging the LWs in the input EM potentials, fields, and waves.
- General relativity becomes directly engineerable in devices of unparalleled capability.

ST curvatures propagate

mass

mass-to-spacetime transformation

spacetime-to-mass transformation

mass

altered spacetime

altered spacetime

Complex of ST curvatures (vacuum engine, or spacetime engine)

Spacetime disturbance (engine) propagates

© T.E. BEARDEN 1998

Electrodynamics has a hidden but ignored electro-general-relativity infolded inside (comprising) its so-called potentials, fields, and waves (in space in the absence of mass). What are presently defined as potentials, fields, and waves rigorously exist only in, on, and of charged mass, as pointed out by Aharonov and Bohm in 1959. All of this is just longitudinal EM waves and their interactions.

Return to Slide Index

Next Slide

Previous Slide



SIGNAL VERSUS VACUUM ENGINE

SIGNAL (INFO)

- INFORMATION RECEIVED
- ANY OVERT PHYSICAL ACTION MUST BE TAKEN BY RECEIVER

A. *Receiver must do the action itself; vacuum energy exchange is unaltered. Energy or fuel for doing the action must be added to receiver externally.*

© 1994, 1996, 1997 T.E. BEARDEN

Selected clipart© by Lotus SmartPics™

VACUUM ACTIVATED

ENGINE (STRUCTURE)
TEMPLATE (FORM)

- "INFORMATION" ITSELF ACTS
- VACUUM FLUX GRADIENTS CHANGE ALL PARTS AND CHARACTERISTICS OF RECEIVER, INSIDE AND OUT

B. *Receiver is acted upon; altered vacuum energy exchange does the specific action. No energy or fuel for doing the action need be added to receiver externally.*

Return to Slide Index

Next Slide

Previous Slide



Electronuclear Interactions by Vacuum Engines

- An EM potential is gravitational due to its trapped energy.
- A local EM potential is a local curvature of spacetime.
- *Structured* potentials are structured *(nested)* local spacetime curvatures; hidden variable theory applies.
- Structured potentials thus are *vacuum engines*.
- Gradient-free potential penetrates the atom, into nucleus.
- *With steady application, a structured gradient-free potential can be used to engineer the atomic nucleus at will.*
- Normal cold fusion systems structure a small fraction of their potentials, by chance geometries, boundaries, etc.
- This produces some new nuclides, but haphazardly.
- *The process can be developed and controlled. The nucleus can be deterministically engineered at will.*

© 1997 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Vacuum Engineering

Using Inner EM Energy and Structuring to Engineer Physical Reality

Vacuum Potential (Violent Flux)

Inner EM
(Ordering of Virtual Particle Flux of Vacuum)
Forms Vacuum Engines

Forms Structured Outer EM
(Potential gradients etc.)
$-\nabla \times A$, $-\nabla \phi$, etc.

Forms Force System on/of Mass
$F \equiv dP/dt$
$= d(mv)/dt$
$\equiv (-\nabla \phi)q$, etc

Assemble Bi-Wavepairs
Makes Scalar Potentials with Ordered Subtle Energy Internal Structure

Scalar Potential Interferometry
Two or More Scalar Potentials with Hidden Multiwave Structures
(Interference of ordered Subtle Energy Structures)

Observable Mechanics
(Statics and Dynamics)

YAO-01

© 1996 T.E. BEARDEN

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



Impact of Vacuum Engineering

- "If they [quantum fluctuations of vacuum] can be [tapped], the impact upon our civilization will be incalculable. Oil, coal, nuclear, hydropower, would become obsolete -- and so would many of our worries about environmental pollution."
- "Don't sell your oil shares yet -- but don't be surprised if the world again witnesses the four stages of response to any new and revolutionary development:
  - 1. It's crazy!
  - 2. It may be possible -- so what?
  - 3. I said it was a good idea all along.
  - 4. I thought of it first."

© 1996 T.E. BEARDEN

Arthur C. Clarke
"Space Drive: A Fantasy That Could Become Reality"
Nov./Dec. 1994

- *Comment:*
  - *Every dipole's broken symmetry in its energetic exchange with the vacuum already freely extracts vacuum energy.*
  - *In power sources, the dipole gates the extracted energy out as $S = EXH$, which flows almost entirely outside the conductors.*
  - The circuit interacts with, and uses, only about 10^{-13} of S. The electrodynamicists calculate only this small S-component.

Return to Slide Index

Next Slide

Previous Slide



A DRAMATIC EXTENSION TO NONLINEAR OPTICAL PUMPING

© T.E. BEARDEN 1997

transverse pump wave

A_2

transverse signal wave (input)

A_4

PPCM

A_3

NONLINEAR MEDIUM

amplified phase conjugate replica transverse wave (time-reversed)

transverse pump wave

A_1

+ ṫ

PREVIOUS VACUUM ENGINE

PREVIOUS MASS STATE

TIME AXIS

A_2

VACUUM ENGINE

AMPLIFIED VACUUM ANTIENGINE

MASS

A_1

a. Pumping with transverse EM waves produces a time-reversed *wave*.

b. Pumping with longitudinal EM waves A_1 and A_2 time-reverses *the mass itself*.

Return to Slide Index

Next Slide

Previous Slide



Time Conservation and Some Properties

(Energy and time are canonical)

- Time can neither be created nor destroyed
  - *Its form can be changed, and it can be positive or negative*
  - *Time can be collected or dissipated, converged or diverged*
  - *Time can oscillate and move in waves*
  - *Longitudinal (infolded) EM waves oscillate time*
- Time is always in motion, and that motion is variable
  - *Collected/collecting time is a continuing stationary change in an ongoing time flow*
  - *Time/collecting time can be internested and internally structured*
- Time has gravitational aspects
  - *Negative (trapped) time is antigravitational*
  - *Emitting negative time is gravitational, to the emitter*
- Nonlinear optical pumping can use longitudinal EM waves
  - *Pumping a nonlinear mass by longitudinal (infolded) EM waves pumps it in its masstime form, in the time domain*
  - *This creates an amplified vacuum antiengine for the mass, and time-reverses the mass back to a previous state*

© 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



A DRAMATIC EXTENSION TO NONLINEAR OPTICAL PUMPING

© T.E. BEARDEN 1997

VACUUM ENGINE A'
VACUUM ENGINE (A' +B')
VACUUM ENGINE B'
TIME AXIS A
TIME AXIS (A+B)
TIME AXIS B
A_2
MASS
AMPLIFIED VACUUM ANTIENGINE [A' + B']
VACUUM ENGINE B
VACUUM ENGINE A
A_1
A + B

After adding a second vacuum engine, pumping with longitudinal EM waves (pumping in the time domain) deviates the time-reversed trajectory. The mass and its internal structure are translated into a new form with a new structure, which it need never have had.

Return to Slide Index

Next Slide

Previous Slide



Key Points in the New Technology

- There is a vast new kind of electrodynamics *hidden inside* all EM potentials, fields, and waves
  - Longitudinal EM waves and complexes
  - Oscillations in time domain
- These complexes are an *infolded general relativity*
  - Clustered formations of *spacetime curvatures*
  - *Very powerful*, since the EM force is used as the agent of curvature
- In general relativity, similar precise complexes permeate and *act on any mass at all internal levels*
- With this approach, one *can now manipulate matter* -- living or inert -- *in any manner desired*, depending only on the level of development of the technology
- Priore unwittingly used this to *cure dread diseases*
- This is a *revolution in all of science*
- *We have uncovered the major mechanisms* to utilize

© T.E. BEARDEN 1996

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc.

28 Mar. 1998

© 1998 T.E. BEARDEN

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



Portable Priore-Type Treatment System

Equipment Case
Computer Control Unit
Infolding Function Generator
Antenna Pad

Return to Slide Index

Next Slide

Previous Slide


Portable System Block Diagram
Power Supply
Computer Control Unit
Frequency Generators
Infolding Function Generator
Field Sensor Unit
Magnetic Pulse Generator
Plasma Mixing Unit
Antenna Pad
Antenna Pad

[Return to Slide Index]

[Next Slide]

[Previous Slide]



PORTABLE PRIORE TECHNOLOGY UNIT

- FACT: DISEASE-SPECIFIC VACUUM ENGINE PRESENT FOR ANY CELLULAR DISEASE, BY WHEELER'S PRINCIPLE
  - *DISEASE CAN BE REVERSED BY CREATING AMPLIFIED VACUUM ANTI-ENGINE (BEARDEN'S PRINCIPLE)*
  - *ANTI-ENGINE IS CREATED BY PUMPING THE NONLINEAR CELLS IN THE "INNER EM" DOMAIN, TIME-REVERSING THEM*
- PRIORE UTILIZED A PLASMA TO PHASE CONJUGATE AND "INFOLD" MULTIPLE BIDIRECTIONAL LONGITUDINAL EM PUMP WAVES
  - *17 FREQUENCIES MIXED IN A ROTATING PLASMA*
  - *PHASE CONJUGATES ADDED BY THE PLASMA*
  - *INFOLDED MIX INTO STRONG PULSED DC MAGNETIC FIELD, WHICH CARRIED IT INTO ATOMIC NUCLEI*
  - *PUMPED ALL NONLINEAR CELLULAR COMPONENTS TO PRODUCE AMPLIFIED, SPECIFIC VACUUM ANTI-ENGINE*
- NEGATED THE LONG-TERM CUMULATIVE CELLULAR DEDIFFERENTIATION ORDER GENERATED BY LONG-TERM HYPOXIA. TUMOR CELLS REVERTED TO NORMAL CELLS.
- SCRUBBED OUT THE CUMULATED PRECANCEROUS STATE
- RESTORED THE IMMUNE SYSTEM TO HIGH FUNCTIONING
- NO EXCESSIVE TRAUMA TO TREATED ANIMAL

CANCR-69

© 1994, 1996, 1999 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



SAVING THE STRICKEN CIVILIANS

SURVIVORS OF N CASUALTIES

(N = 1-40 MILLION)

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc. 28 Mar. 1998

© 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Summary and Conclusions

- A new therapeutic paradigm of great scope and effectiveness has been developed
  - *Will provide effective, quick treatment of mass casualties*
  - *Will provide cures for unknown agents*
  - *No pathogen strains are resistant to this process*
- Results have been proven experimentally
  - *Documented in French scientific literature*
  - *Rigorous scientific protocols, eminent scientists*
  - *Technical mechanism deciphered*
- Will treat and cure many diseases
  - *Aids, atheriosclerosis, cancer and leukemia*
  - *Sleeping sickness*
- Portable units can be developed quickly
  - *18-month crash development program required*
  - *high level authority and overwatch essential*
- ***Will solve the BW mass casualty treatment problem, both civilian and military***

© 1993 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes
on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc.

28 Mar. 1998

(c) 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Recommend implementing:

- Crash development program
  - Suitcase-sized portable unit
  - 18-month Manhattan-type project
  - Simultaneous theoretical modeling, animal testing w/breadboard models
  - SecDef and Congressional overwatch
  - Presidential Decision Directive
- Parallel logistics support program
  - Plan high speed production lines
  - Mass distribution, storage, maintenance
  - User, maintenance training
  - Plan C4 and usage at all levels
  - Integrate firemen, police, National Guard, FEMA, medical facilities, etc.

[Return to Slide Index]

[Next Slide]

[Previous Slide]



Final Thoughts:

- The current internal BW threat can and will kill more Americans than all our previous wars combined
- The Priore technology is the only solution in sight that can save most of those casualties

Return to Slide Index

Previous Slide

CTEC, Inc.
2311 Big Cove Road
Huntsville, AL 35801
(256) 533-3682 Ph/
(256) 539-5951 Fax

CTEC, Inc.

June 24, 1998

Dr. Jane F. Kinsel, Director
Office of Policy Analysis
Department of Health & Human Services
Bathesda, MD 20892

Dear Dr. Kinsel:

Your letter of June 8 is appreciated. However, the entire action package had already gone to the Assistant SecDef and also to Major General Neary in the USAF.

The proof of a revolution in medical treatment was in the package. The basis for it is already demonstrated experimentally in the scientific literature, both in the U.S. and in France. We are speaking of something already proven, but missed by the entire U.S. medical community. Strong words, but true. Let me be specific.

Any cell in the body can be time-reversed (physics term) or dedifferentiated (biology term) back to an earlier state, by pumping (i.e., "squeezing" in simple terms) that cell with longitudinal EM waves as pump waves. There are considerable papers in the French scientific literature showing the experimental results.

Apply that to cancer. We are stating bluntly that all cancerous cells in the body can be "depromoted" back to normal cells easily. Further, the damage previously done to them (such as by sustained hypoxia due to contaminants reducing the oxygen-carrying ability normally given to it by some 60-to-80 surrounding water molecules per red cell and the consequent H-bonding interactions) will also be reversed. The cells can all be returned to healthy, normal cells again, without "killing" or "burning" or "cutting" anything.

With some development of the technology, you can quickly and easily cure every cancer patient in every hospital in the United States.

Now apply it to AIDS. Since you can time-reverse every cell in the body, you can time-reverse the HIV-infected cells – genetics and all – right back to normal cells with normal genetics. Those cells not infected and healthy, will just get a "little younger" again.

So with that small development, you can quickly and easily cure every AIDS patient in every hospital in the United States.

I would have thought that NIH would certainly be interested in such a revolutionary therapy which has already been demonstrated in laboratory experiments. World-renowned French scientists – such as the eminent parasitologist Pautrizel and research PhDs assigned directly by Robert Courrier, head of the Biology Section of the French Academy of Sciences, worked with Prioré in performing those startling experiments that proved what we are saying.

The method was rigorously shown to cure infectious diseases (such as trypanosomiasis), atherosclerosis (which now afflicts millions of Americans), and terminal tumors. It was shown to reverse suppressed immune systems back to normal vigorous functioning.

Please permit me to disagree with you that the examination of such is not the mission of the NIH. To the contrary, it is precisely the NIH which should have some of its very best scientists looking into this.

The action package to DoD was to propose a crash program to develop this methodology in the form of a small, portable unit for treatment of mass casualties resulting from a terrorist BW attack on our cities (now expected in the next few weeks, as you must be aware). The leading Arab terrorist of the world has already promised just this.

We are speaking of several million Americans who are going to die. They are going to die in spite of everything that NIH and its labs can do, even though I know you will make a heroic effort. With NIH present methods, you cannot do very much for those stricken Americans at all. Everything we have in the "normal" kit bag is almost useless against a knowledgeable spray attack of modified smallpox (as you know, the Russian secret BW labs have made and sold tons of that already, to guess who!). Or a spray of tularemia (you are well aware of the extreme lethality of that), or anthrax (easily obtained). It is also common knowledge that these terrorist teams with their BW agents are already on site in this country, waiting for the word to attack. This has now been officially raised to our primary Strategic Threat.

In the face of such looming strikes on the U.S., I simply cannot believe that the NIH does not feel it within their mission to rigorously check out a proposed method for saving perhaps 70% of those coming deaths (first generation equipment), and up to 90% with second generation equipment.

Perhaps you just did not read the package carefully. I urge you to do so.

Else NIH is going to look very, very bad when (1) the strikes do occur, (2) they can't handle them (and they cannot, as you well know), (3) they had within their hands in advance, a proposed methodology that could have been investigated intensely, to save millions of those stricken Americans.

As a staunch supporter of NIH and especially CDC, I have to believe that there is a different attitude there. If NIH is not interested in a previously experimentally demonstrated method of saving millions of Americans, then the only recourse left is the political channel.

I assure you that my critique of electrodynamics is well-founded, as supported by various leading physicists such as Nobelist Feynman (who stated bluntly that the field concept is wrong), Wheeler, Bunge, and so on. It is inexplicable why all our universities are still teaching a 130 year old abridged (Heaviside's) subset of Maxwell's theory, and one that still contains a material ether even though that was falsified 110 years ago!

You already have seen the misuse of this technology by the Russians, in the decades-long radiation of the U.S. Embassy in Moscow. Is it not NIH's mission to understand how they generated all those diseases and health changes? Have you ever looked into Kaznacheyev's experiments showing that ANY cellular disease or disorder can be induced in cells at a distance by purely EM means? Have you looked into what got eliminated from electrodynamics by ignoring the hidden longitudinal EM inside every potential, field, and wave? Do you realize what ignoring that has done to American chemistry, biochemistry, and medical science?"

I would hope that the NIH would at least be interested in its own mission area!

I challenge you bluntly to admit that no one presently understands the primary operation of the human cellular *regenerative* system. That's because its technical principle is not presently in our recognized physics, biochemistry, and medical science – even though it has been in the hard physics literature since 1903-4. Becker's epochal work came closest; since he only had access to the conventional EM model, it failed him. But he at least showed you rigorously that cells can be changed (both differentiated and redifferentiated) all over the map by laughably weak EM – picoamperes of current, which means persistent DC potentials. In the microwave radiation of the U.S. Embassy, all the health changes occurred in regions absent of fields – i.e., absent of bleed-off of the potentials. Hence in regions of stable DC potentials! With 100% correlation of the health changes to persistent, gradient free potentials, and 100% anticorrelation to changing potentials (i.e., fields), our own scientists concluded totally erroneously that it could not have been the EM radiation causing the changes, when their own results had just proven that it was.

Now I ask you: Can NIH explain how it was that the DC potentials caused those health changes? I think not. If it could, it would understand the action package I wrote, and its importance.

This is not a "political" letter. I'm just an ordinary American citizen who has done about 30 years very hard work on this particular area. The work is good enough now to stand on its own merits. The scientific community will eventually accept it, about 50 years from now. But we cannot wait 50 years! Those millions of Americans are going to die, because of the bureaucracy and inaction of our own scientific organizations. Whether they like it or not, the U.S. scientific community is now the forefront of the struggle for this nation to survive. And they are failing us dramatically.

So as a parent who wants his children to live, and his neighbors' children to live, and those millions of soon-to-be stricken Americans to live also, I urge you to at least have someone competent in physics (and knowledgeable that the foundations of physics itself are in woeful shape!) check the work. Has anybody there *read* any of the references to the Prioré work I cited? Does anyone there realize that *there are no EM forcefields in space?* Probably not.

Dr. Kinsel, there is a time for "business as usual" and there is a time to do some serious new work. Those stricken Americans are going to be lying there. Nothing NIH can do is going to stop that. That's a given, and it is not my own estimate. It's the official estimate. And you *know* you presently do not have the tools to do anything really effective about it.

Frankly, I interpret your letter to me as just the normal "spin control" for easy disposition. I would hope that NIH would seriously rethink the situation, get off the "spin control" and "business as usual" posturing, and do something dramatically different for a change.

What have you got to lose? A little time from perhaps two or three of your best scientists.

What have you got to gain? Saving untold millions of American lives. A new, *already partially demonstrated* cure for most dread diseases such as AIDS and cancer – diseases which you presently cannot do very much about in spite of decades of heroic struggle.

Sincerely,

cc: Senator Shelby, Congr. Cramer

T.E. Bearden
President and CEO

CTEC, Inc.
T.E. Bearden, President & CEO
2311 Big Cove Road
Huntsville, AL 35801-1351
(256)533-3682 ph/(256)536-0411 Fax

CTEC, Inc.

May 12, 1998

Dr. Harold Varmus, Director
National Institute of Health
Bathesda, MD 20892
(301) 496-1766

Dear Dr Varmus:

We have recently sent action documents to the Director of Nuclear and Counterproliferation, Office of the DCS, Air and Space Operations, HQ USAF and to the DoD (General Busbee) Assistant Secretary of Defense, as well as several Senate and House committees, which may be of interest to you. For one thing, we give the technical mechanism used to generate the Gulf War Syndrome. The same weaponry is now being used to rapidly induce new strains of certain pathogens worldwide. I urge you to closely read that section of the letter to MG Neary which explains the GWS, why the French did not get it, and why Southern Iraqis got an increase in cancer and leukemia but not GWS. Also explained is how the "microwave radiation" of the U.S. Embassy in Moscow induced diseases for decades, and how we failed to comprehend it because the standard EM model deceived us.

There is a way to treat and quickly cure most diseases, including the mass casualties resulting from a terrorist BW strike on our civilian population centers, our military bases, or our forces in the field. The method is little known, but was scientifically demonstrated in France in the 1960s and early 1970s before cancellation of the Prioré Project when the French Government changed. Eminent French scientists worked on the project, and the results are fully documented in leading French scientific journals. References are listed in a separate attachment.

Previously the Western scientific community has been unable to understand the technical mechanism responsible for such remarkable cures, because of serious foundations flaws in Western physics and electrodynamics. *Foundations* physicists have long been aware our science is flawed, and have pointed out many of these fundamental errors. However, the operational science establishment has not paid attention, even though physicists such as Feynman and Wheeler pointed out that the notion of "force fields in space" was totally wrong.

As a primary example, there is an "infolded" electrodynamics inside all potentials, fields, and waves that is far more primary than the coarse EM that is in our textbooks. It is actually an infolded general relativity, and this is what the Russians have weaponized. This infolded EM-GR has been ignored in the West (but not in Russia) since 1903.

As another example the potentials, fields, and waves of present electrodynamics are rigorously defined – and exist – only in the presence of mass. They do not exist in such form (force fields and oscillating force fields) at all in space, in the absence of mass. Rigorously, Maxwell's equations are mass-to-mass transforms, since Maxwell and everyone at the time assumed the ubiquitous presence of the material ether. In other words, to the founding electrodynamicists, there was no place in all the universe that was devoid of mass. Hence they defined all EM entities as entities containing mass. Even though Michelson-Morley experiments of more than a century ago destroyed that material ether, not a single Maxwellian equation has ever been changed! They still assume the material ether.

Specifically missing from our electrodynamics are two essential transforms: (1) the mass-to-spacetime transform, and (2) the spacetime-to-mass transform. In other words, these two transforms are "infolded" or hidden inside (comprise) the end point extremum case – the mass-to-mass transform actually written by Maxwell.

But these two missing transforms are just general relativity (they correspond precisely to Wheeler's principle of general relativity). So general relativity has always been infolded inside electrodynamics as we know it, but ignored. Further, this is a very powerful general relativity, since it uses the very strong EM force as the agent of spacetime curvature. Hence now one can engineer a powerful general relativity in the laboratory and in practical devices, and even action-at-a-distance, which one cannot do using merely the staid and weak G-force.

It turns out that longitudinal EM waves as shown by E.T. Whittaker in 1903 and 1904 are far more primary than our present EM theory and even our present GR theory. Both EM and GR are directly engineerable using longitudinal EM waves, including subluminal and superluminal EM waves in vacuum, and including action at a distance. One can engineer complexes of spacetime curvatures as desired, which in turn are *spacetime engines* (Wheeler's term). These engines can act upon mass – either living or inert – in any fashion desired, and at any distance desired.

The little-known and poorly understood Regeneration & Recovery (R&R) system – as contrasted to the immune system – utilizes this exact "spacetime engine" methodology to restore damaged or diseased cells, within its limitations – "dedifferentiating" or "time-reversing" them back to normal. The mechanism is fully explained in the attached package. The proposed program applies this fundamental method to greatly amplify the effect. Thus cancer cells can be reversed back to normal cells, HIV-infected cells (HIV-factories) can be reversed back to normal cells (genetics and all), etc. This represents a dramatic and unparalleled new medical therapeutic methodology of extreme power. The same techniques can simply be conjugated one additional time, and used to produce diseases and cellular changes at a distance, including in entire mass populations, as the KGB is doing right now. Specifically, by impressing an extremely weak "cocktail mix" of disease spacetime engines on the U.S. populace, the immune systems are reacting and being "spread thin" across several "shadow state" infectious pathogenic conditions. Thus when an actual terrorist BW attack occurs, the lethality of the strike will be remarkably enhanced because the immune systems will be "thinned" in their ability to fend off this new pathogen. By doing it this way, BW warfare can actually be conducted upon the U.S. without anyone being the wiser.

Our very survival as a nation is threatened by remarkable KGB weapons using this fully documented, extended electrodynamics. Bluntly, unless we take off our scientific blinders and understand Russian energetics weapon science, GWS and the Embassy health changes in Moscow were just a picnic before what is upon us. After two decades of work on the KGB energetics weapon problem, we have fully deciphered the technical mechanisms and what energetics is, as well as citing many of the Russian weapon tests and how they were done. Again, you can see that for yourself in the package.

Now that we understand the technical mechanisms, we are proposing rapid redevelopment of the Prioré process, in portable suitcase-sized units to be mass produced and filtered down into the entire emergency community for mass treatment of lethal infectious diseases resulting from BW strikes. And we are strongly urging the U.S. scientific community to quickly investigate and come to grips with this vast new *biological engineering* mechanism. Our very survival depends on it.

The inclosed documents provide an overview of the process. There is nothing else on the scientific horizon that can save the majority of all those stricken Americans, once the first foreign-sponsored terrorist teams strike our population centers with BW agents.

Sincerely,

Incls: Full package with table of contents

T.E. Bearden
President & CEO

Scalar Wars

The Brave New World of Scalar Electromagnetics

by Bill Morgan



For the past six months I have been undergoing the greatest **paradigm shift** I have ever had to go through. It has rattled my nerves and shaken my bones. This intense adjustment of my "world" has come about by studying the information given by Col. Tom Bearden at his website Cheniere. The new knowledge there has necessitated a total revision of my ideas about physical reality, the world we live in, and the future of humanity. This paradigm shifting even actually made me dizzy on certain days as I tried to absorb and digest Bearden's vast amount of information. I am not a scientist at all, just a layman, and I have little comprehension of the math and high physics of this new science called "**Scalar Electromagnetics**." But there is a great deal of information at Cheniere which needs to become common knowledge as fast as possible, for the sake of the survival of life on earth. To that end I have put together this small primer of Bearden's ideas, as a kind of "beginner's guide" to his website. (I have tried to underline certain words and phrases which are part of the new "jargon" of talking about these "new" phenomena. Also I have taken the liberty of bolding certain words and phrases to help them stick in the mind).

(Note: Throughout "**EM**" means "**electromagnetic**," and "**LW**" means "**longitudinal wave**")

This article has six sections:

New Waves 2. Tapping the Waves 3. Weaponization 4. Healing 5. Psychoenergetics 6. As It Stands

1. New waves discovered

Longitudinal EM energy fills vacuum of space, the time domain of spacetime, time as compressed energy, E=tc2, waves of time, phase conjugate wave pairs.

"Electric power is everywhere present in unlimited quantities and can drive the world's machinery without the need of coal, oil, gas, or any other of the common fuels." Nikola Tesla

"At any point and at any time, one can freely and inexpensively extract enormous EM energy flows directly from the active vacuum itself." Tom Bearden



I guess the first thing to try to comprehend is that a "new" kind of electromagnetic (EM) wave has been discovered in the empty vacuum of space called “longitudinal” waves, which, when engineered, can be an inexhaustible supply of energy in great magnitude at any place in the universe. The word "new" is in quotes because the discovery really goes back to **Nikola Tesla** and his discovery of what he called "radiant energy." It is also not "new" because the Russians (KGB) have been working on this technology for over 30 years and have **weaponized** these "new" longitudinal scalar waves to a great degree.

These are the very weapons **Nikita Khrushchev** spoke of in January, 1960.

> "By 1957-8 the Soviets had progressed to the point of a giant scalar EM accident in the Urals which exploded nearby atomic wastes, devastating the area. They had also progressed to development of great new superweapons using their new energetics - weapons to which Khrushchev referred in 1960 when he informed the Soviet Presidium of a new, fantastic weapon in development, a weapon so powerful that it could wipe out all life on earth if unrestrainedly employed.'" Tom Bearden

After over 30 years of development, and extensive testing around the globe, these new scalar electromagnetic weapons are up and running and ready to go. Tom Bearden, at his website Cheniere, discusses the history of these new scalar electromagnetic weapons in his paper "Historical Background of Scalar EM Weapons."

Some Immediate Implications

> The implications of successful engineering of the longitudinal waves are enormous, and will change the world as we know it, one way or another. Among other things, these discoveries mean that:
>
> 1. The **solutions to the energy crisis and the "oil problem" are in hand**. These oil wars are unnecessary. There is endless energy available freely from the domain of time.

2. **Unbelievably powerful weapons** are not only possible, but are already operating in several nations. The many powers of these weapons are unprecedented and mind-boggling.

3. The **cure of diseases such as cancer and AIDS**, in fact nearly any disease, has become possible within a few years of sufficient funding. Everyone can be made healthy and stay healthy.

4. **Mind control on a mass scale** has now become possible, and the machines to do it are already in place in certain nations. It has become possible to mentally enslave whole populations with the twist of a few dials.

So the layman will need to understand that there is a new kind of electromagnetic energy that is altogether different from what he knows, e.g. radio, TV, cell phones, etc. The ordinary EM waves that we have known about are called transverse EM waves, to distinguish them from the new longitudinal EM waves. These scalar waves do not actually exist in our "material" world, but exist only in the vacuum of empty space, or the time domain. And we must keep in mind that this vacuum of space we speak of exists all through everything. Even our bodies are mostly empty space between atoms and molecules. So the gateway to this seething ocean of energy can be there at every point in the universe. This seething ocean of energy is all around us and all through us.

Emptiness is Full

This amazing discovery announces that the "emptiness" of empty space is in fact not empty, but a great ocean of seething energy!

Col. Bearden refers to this ocean of energy as being of the "time domain." It seems like something from Star Trek but this is where scalar electromagnetics has come to. And where it is going may be beyond anything Star Trek could have dreamed of.

We live in a 3-dimensional world, which physics calls "3-space." But there is also spacetime, or 4-space, or the "4th dimension." Then suddenly comes this amazing new knowledge that time itself is actually compressed energy. And it is energy which is compressed by exactly the same factor by which matter is considered compressed energy: the speed-of-light-squared!

So we have a new companion to the famous E=mc2. It is now paired with E=tc2 (where t is actually "delta-t," or change in time). Or (amaze your family and friends and) say:

"E equals em-cee-squared"

and

"E equals delta-tee-cee-squared"

It has a nice ring to it, like some freedom bell announcing a new era.

And as the atomic bomb released the compressed energy in matter, so can we now unleash the tremendous energy that is compressed into time itself. It gives a completely new meaning to the term "time bomb."

Some New Terminology of Scalar Electromagnetics

A new science, several new names

> "Those [Russian] weapon scientists resurrected an old term from the history of electrodynamics, called "energetics". That is their approach to a unified field theory, where everything is based on "energetics". This model as its foundations uses a very similar approach to that "single fundamental unit" model, where energy is the unit. If one makes the energy EM in nature, then one has the Russian energetics approach. This unified approach gathers everything in, including all energy actions and relations in inert matter (the first branch of energetics, called by the same name), all field and matter interactions in living matter (the second branch of energetics, called "bioenergetics"), and all mind operations and mind-matter interactions (the third branch of energetics, called "psychoenergetics"). [ed: sometimes also called "psychotronics" by the Russians]

Rick Andersen in an article called "What is Scalar Electromagnetics?" describes the new science this way:

> "Scalar EM is the brainchild of Lt. Col. (retired) Thomas E. Bearden, a systems analyst and wargames specialist who has been advocating a view of electromagnetics which is based on the notion of a vast, unseen background of scalar energies (as opposed to vector energies) which underlie all physical reality.
>
> "If Bearden is correct in his Scalar EM theory, then we can build devices which would enable us to alter gravity, time, inertia, and the apparent mass of an object. This of course has ENORMOUS implications for military applications, space-vehicle drives, time-travel, teleportation, paranormal phenomena, and just about every other area one can think of." http://twm.co.nz/Beard_scalem.html

> "Time-energy, time-currents, and time-structuring play the dominant role in electromagnetics. Time-as-energy eventually becomes engineerable, as easily as is spatial energy now. We are always dealing with spacetime and with spacetime curvature."
>
> Bearden: http://www.cheniere.org/techpapers/Vision%202000%20paper.doc

The scalar energy discovered in the vacuum of space is sometimes called "zero-point" energy. Thomas Valone explains how this term came about.

What does "Zero Point" mean?

"Boyer traces the historical “creation of the vacuum” as proceeding in stages in parallel with the historical development of ideas about the vacuum. To paraphrase, he says that in the 17th century, it was thought that a totally empty volume of space could be created by simply removing all matter and, in particular, all gases. That was our first concept of the vacuum. Just get rid of all the gas. Late in the 19th century, it became apparent that the region still contained thermal radiation. But it seemed that the radiation might be eliminated by cooling. So the second concept of getting a real vacuum is to cool it down to zero temperature. Just go all the way to absolute zero. Then we’ve got a real vacuum. Right? Well, since then, both theory and experiment have shown that there is a non-thermal radiation in the vacuum and that it persists even if the temperature could be lowered to absolute zero. Therefore, it was simply called the “zero point” radiation. "Thomas Valone http://www.seaspower.com/InsideZeroPoint.htm

> "**For our very survival, it is absolutely imperative that informed citizens be aware of this dramatic change, which is just now starting. The powerful new science and engineering must be controlled and used for humanity's benefit, not its detriment. Else it will eventually be let loose unrestrainedly, to destroy all life on earth - a possibility indicated by Nikita Khrushchev in 1960**." - Bearden
>
> http://www.cheniere.org/explore%20articles/priore1/p4.jpg

2. Tapping the waves

Endless free energy, Tesla's radiant energy, the dipole as the gateway to the energy of the void, MEG in one year, Bedini, Yakuza, etc. End of Oil, geopolitical chaos, rogue groups

Move Over G.E. & Big Oil, Energy is Everywhere!

Third-world nations set to rise

> "Certain powerful interests did not wish the extended electromagnetics to be discovered or taught. That, after all, would lead to free energy and loss of economic control of the citizens. That was precisely why Nikola Tesla had already been suppressed ... Today it is still being suppressed by the orthodox establishment."
> http://www.cheniere.org/books/ferdelance/s25.htm

The vast seething ocean of energy of the vacuum, the longitudinal scalar EM waves of the time domain, can now be tapped and "transduced" into ordinary (transverse) EM energy in our 3-Space world. The process can be compared to putting a paddlewheel into a river. The energy acquired is free, since the river is there flowing whether we tap it or not. And it is a mighty river, and is not diminished by our paddlewheel.

This means that a permanent solution to the "energy crisis" is at hand, if only those who hold it so secret would give it up to humankind.

It means our species' insane use of oil is no longer necessary. We can make automobiles that need no fuel at all. We can build motors that power themselves. It means that unlimited electrical power can be available for free anywhere in the world. Every house and even shack can have its own power supply.

Of course there is the cost of the equipment at first, but the energy flow is free for the presumably very long life (no moving parts) of the generator. It will probably take decades to shift over to scalar power.

But the ability to tap the scalar (longitudinal) EM waves of the vacuum (which exists everywhere) also means that unbelievably powerful weapons can be, and already have been developed. In fact these weapons are so dangerous that the fear engendered becomes a psychological obstacle to the grasping of the facts.

I struggled with this myself for months, and even though Tom Bearden had completely convinced me already, it is hard to accept the fact that for everyone on earth the "worst that might happen" has suddenly gotten much worse. It takes time to deal with that, to realize it and get over it.

Indeed, the possibilities of these new weapons, which are tapping the huge energies of time, are so terrifying it is natural for the mind to simply say: "I don't want to hear about that."

And the government, likewise, pretends these weapons do not exist and tries to keep it secret from the people. Because most people would indeed be truly alarmed to know the actual situation. Col. Tom Bearden has decided that the people need to know the truth anyway. As a People on a Planet we must face this now, and ban the use of scalar weapons in war or in mass mind control. The current deployment of these weapons is a world emergency which we must all face.

The physics and mathematics of the longitudinal waves and the time domain are clearly beyond the layman, but I recommend scanning through them anyway just to get a sense of the wonder and the elegance of it all and some of the exotic terms which are used. Two of the most important papers by Col. Bearden are:

Giant Negentropy from the Common Dipole

The Final Secret of Free Energy.

Despite the complexity of the science involved, Bearden sums up the essential secret of it all in a few words.

> "There is no problem at all in extracting all the energy one wishes from the active vacuum, anywhere in the universe, at any time. Just make a dipole.

> The problem is in (1) catching some of that freely gushing EM energy in a circuit containing a load, and (2) dissipating the caught and collected EM energy in that load to power it, without using half the caught energy to destroy the source dipole's).
>
> That is the ONLY real energy problem on the planet, and always has been."
>
> http://www.cheniere.org/correspondence/022502.htm

A dipole could be a battery, which is polarized into negative and positive. Or the terminals of a generator. Or any magnet with its two poles. Or an atom with its positive and negative charges. Or the earth's magnetic field, the sun, and all heavenly bodies. Even a galaxy must be some kind of mega-dipole. Wherever there is a dipole there is already immense scalar EM energy ushering out of and back into the vacuum. And there have already been demonstrated a number of diverse methods for tapping that energy as it flows. (John Bedini, Edwin Gray, Bruce de Palma, and others). Bearden provides what he calls a "partial list" on his website.

> "In other words, nature then gladly gives us as much EM energy flow as we need, indefinitely — just for paying a tiny little bit initially to "make the little dipole." After that, we never have to pay anything again, and nature will happily keep on pouring out that 3-flow of EM energy for us. This is the giant negentropy mechanism I uncovered, performed in the simplest way imaginable: just make an ordinary little dipole."
>
> Bearden http://www.cheniere.org/techpapers/Unnecessary%20Energy%20Crisis.doc

How to Buy a Free Energy Machine

Answer: Just wait one more year! 2003. Then get off the Grid!

Perhaps the most eagerly awaited event now is the marketing of Bearden's Motionless Electromagnetic Generator (MEG) scheduled to begin in about a year's time. This is when the proof will hit the fan. Many people have said to me, when talking about free energy, "I'll believe it when I can go to the store and buy one." Hopefully in a year's time they will be able to order their own MEG. And then they will believe, because it works and is working.

Says Bearden: "I will admit that the chief scientist of an important experimental group in a large company was rather stunned at the type of output we were able to obtain. The MEG may look like just a transformer, but it is not. It is a completely different breed of cat."

(Bearden : http://www.cheniere.org/correspondence/011202.htm)

Soon the cat will be fully out of the bag. The first MEG units will supply 2.5 kilowatts of free electricity. Forever. Units can be connected together to double or triple the wattage. After that gets going, 10 kilowatt generators are planned. Energy will flow freely from the time domain indefinitely, and there are no moving parts to wear out. This manufacturing project is a heroic effort and will change the world as we know it. For once people are in possession of such devices there can be no further denial from anyone, including the government and/or "secret-government."



The Motionless Electromagnetic Generator

(Successfully replicated here by J. L. Naudin)

The physics of how the MEG works is explained in the paper "The Motionless Electromagnetic Generator: Extracting Energy from a Permanent Magnet with Energy Replenishment from the Active Vacuum."

The device was successfully replicated by J.L. Naudin in France, and others, like Steve Utne, are also working on their own models. But Magnetic Energy Limited's MEG is actually scheduled for production soon and looks to be the first commercially available free-energy generator in history!

I imagine it will not take long for tinkerers to put them into their electric cars and make the first fuelless automobiles since Tesla's unheralded (and unheeded) experiments. Or for builders to begin building houses powered by MEG's. Houses which will never see electric bills. How can they ever make enough of these to meet the demand that will suddenly be there? Bearden is right, it needs to be an all-out crash program of the government on the order of the Manhattan Project.

I must include here that Bearden is quick to point out that he is not himself the inventor of the MEG, but is a partner and advisor in bringing it to the public market through Magnetic Energy Limited, Inc. I must also admit that I am praying for the success of this venture, and the ending of the absurd and criminal withholding of this technology from the people by the black-ops military-industrial people. This secrecy has cost the planet over 30 years of unnecessary pollution.

The first units off the assembly line, which is being set up in a "friendly" unnamed nation, will usher the public at last into the new era of scalar electromagnetics.

As of December, 2001, the situation with the MEG was described by Bearden in a letter.

> "What we presently have with the MEG is a successful laboratory experiment. At least a year's very hard research will have to be done before we will be ready to put a commercial power supply into production.
>
> "Consequently, we have made an agreement with a foreign partner (the National Materials Science Lab of the National Academy of Sciences of a friendly foreign nation) to do that year's research. At the same time, we are trying to make an agreement with one or more large financial partners here in the U.S."
>
> Bearden http://www.cheniere.org/correspondence/121901.htm
>
> "So we are hopeful that we will be able to start introducing units on the market about a year from now. Quite simply, we will either succeed or we will fail. But we will give it our very best effort."
>
> Bearden http://www.cheniere.org/correspondence/012202a.htm

Bearden has given another technical explanation of how the MEG works here in a letter.

Motionless Electromagnetic Generator patented, 3-26-2002

Click here to read the patent

"In Magnetic Energy Limited, all business discussions and arrangements are taken care of by Dr. Lee Kenny, Managing Partner. There are five of us who are co-inventors of the MEG, and two of the others are really the principal inventors." Bearden http://www.cheniere.org/megstatus.htm

Free Energy has been Suppressed

Secret Government Aware of Free Energy

> "In this world of contemporary times, all the agencies, CIA, FBI, KGB, NSA, Electric Power Research Institute, DARPA, Brookings Institution, Henry Kissinger, Edward Teller, et al., all are aware of [free-energy researcher Bruce] De Palma and his ideas.
>
> "Because these individuals and institutions are employed by the ruling elite to forecast the future and satisfy present needs and demands, it is clear that free energy is a threat to the world order constructed by business and the mindset of those who want to own the world.
>
> "Free energy represents Man's aspirations and dreams of freedom and equality, uniform division of resources and the ability to choose one's own future.
>
> "The fact that free energy is suppressed speaks to the greed and self-interest of a ruling elite which, even in the face of an emergency of global starvation, resource depletion and environmental pollution, will not give one inch if it means loss of control. This is an

> attitude of paranoid delusion and fantasy which can only arise from the alienation of a class of elitists who, through their money, are completely insulated from the reality of the day to day fight for existence of the common man."
>
> http://depalma.pair.com/Absurdity/Absurdity07/ProblemOfFreeEnergy.html

Bearden describes one case of suppression when the Yakuza killed the Kawai engine in his very presence in Huntsville, Alabama.

> "That night a jet arrived from Los Angeles, with a Yakuza on board. The next morning Kawai no longer controlled his company, his invention, or his own fate. The Kawai party was in fear and trembling. The Yakuza coldly dissolved the agreement, they packed up the two Kawai engines we had, and left. And that was that."

So it is not only governments who are keeping this revolutionary technology from seeing the light of day. The Yakuza? KGB? The Aum Shinrikyo cult? Our "leaders" need to be honest about what is going on, otherwise they look foolish, acting out a kind of "Alice In Wonderland" script before the public, a script that has become completely unbelievable.

Concerning the criminal withholding of this scalar technology by the military black-budget people, and the cover-up of the actual situation regarding scalar weapons throughout the world, Tom has this to say:

> "The high government officials of the United States of America grossly violated our constitution and their sworn oaths of office. Our constitution specifically charges the government of the United States to defend the people of the United States. That means our officials are specifically charged with defending our people. Yet they deliberately agreed not to do so, and they deliberately sacrificed us in advance.
>
> "They committed treason of the highest kind, by deliberately surrendering us to total destruction anytime the big balloon goes up."
>
> Bearden http://www.cheniere.org/books/ferdelance/s75.htm

Energy Crisis Solved

One of the "must read" documents at Cheniere is "The Unnecessary Energy Crisis: How to Solve It Quickly," especially since the "oil wars," which Bearden has foreseen for decades, have now already begun.

Here are some clips from that Document:

> "To avoid the impending collapse of the world economy and/or the destruction of civilization and the biosphere, we must quickly replace much of the "electrical energy from oil" heart of the crisis at great speed, and simultaneously replace a significant part of the "transportation using oil products" factor also.

> "The technical basis for that solution and part of the prototype technology required, are now at hand. We discuss that solution in this paper."

And although the solution to the energy problem and the oil wars may be at hand, Bearden suggests there is still an urgent rush that needs to be made to save human civilization from collapse.

> "Once the technology hardware solutions are ready for mass production, even with a massive worldwide deployment effort some five years are required to deploy the new systems sufficiently to contain the problem of world economic collapse. This means that, by the end of 2003, those hardware technology solutions must have been completed, and the production replacement power systems must be ready to roll off the assembly lines en masse.
>
> "The 2003 date appears to be the critical "point of no return" for the survival of civilization as we have known it.
>
> "Reaching that point, say, in 2005 will not solve the crisis in time, and the collapse of the world economy as well as the destruction of civilization and the biosphere will still almost certainly occur, even with the solutions in hand."
>
> "The good news is that we now know how to easily initiate continuous and powerful "electromagnetic winds" from the vacuum at will. Once initiated, each free EM energy wind flows continuously so long as the simple initiator is not deliberately destroyed."

On page 9 he explains the concept of the dipole, and how there is already huge scalar energy flowing in the time domain around any dipole. Hold a magnet or a battery in your hand and you hold a stress in time and a beautiful flowing loop of longitudinal waves!

Bearden decries the scientific community in the West for being unable to let go of their dogma long enough to see that the greatest discovery in human history lies at their feet, but for their stubborn ignorance.

> "The present energy crisis then is due totally to that "conspiracy of ignorance" we referred to, that is maintained by the scientific community, and that has been maintained by it for more than 100 years.
>
> "This is the real situation that the environmentalists must become aware of, if they are to see the correct path into which their energies and efforts should be directed — to solve both the energy crisis and the problem of gigantic pollution of the biosphere. "As far as anyone in the legislative branch of government ever understanding the profundity of the discovery and engineering of scalar waves, Tom Bearden says they are at a great disadvantage in doing so.
>
> "The nontechnical person — e.g., a Senator or a Congressperson — is operating under a distinct disadvantage. If he or she takes the stance that much better electrical power systems can readily be achieved, he or she is in fact opposing almost the entire set of University, Government Technical, Power Company, Battery Company, and Organized

> Science communities. Further, in most cases his technical advisors are themselves from one or the other of those communities, and likely to go back into that community or those communities when the Senator or Congressperson leaves office, or even before. So the Congress and the non-technical government community at large operate at a great disadvantage...Bearden National Emergency Declaration is Needed
>
> "The Government Non-Technical community (the Senate and the Congress, in particular) are in far better shape than the Government Technical community, to appreciate the world implications of the pending economic disaster. I am hopeful that both the environmentalists and the Government Non-Technical community will rapidly unite in a common goal to get this vacuum energy program launched, under a National Emergency declaration. If so, then they can solve the energy crisis and the pending economic crisis, in fairly short order, and permanently."
>
> unnecessary_energy_crisis.htm#congress_disadvantage

In the conclusion of his paper The Unnecessary Energy Crisis: How to Solve It Quickly Bearden again states the urgency of replacing our centralized power grids with highly dispersed and local taps on the freely flowing energy of the active vacuum. Given the abilities of the Tesla howitzers, the power grids of all nations are sitting ducks.

> "Personally, the present author regards the increasing energy crisis as the greatest strategic threat to the United States in its entire history. I will do anything within my power to help prevent what I perceive to be the looming economic collapse of the Western world, preceded or accompanied by a sudden, explosive, all-out and continuing exchange of the WMD arsenals of most of the world.
>
> ...In the name of all humanity, let us begin! Else by the time this first decade of the new millennium ends, much of humanity may not remain to see the second decade."

---

3. Weaponization

Scalar interferometry, Tesla howitzer, Tesla dome, heat/cold, dudding, 10 nations have them, dead-man fusing & Insane Systems, scalar strategy, earthquakes and weather wars, solar storms, mind attacks, leased to Yakuza, many examples of testing, quantum potential weapons.

> "Indeed, Soviet energetics weapons are now capable of destroying both our triad shield, our homeland, our armed forces in the field, and our population, quickly and efficiently. We have a new "gap" of monumental proportions: not a missile gap, not a submarine or bomber gap, and not even a particle beam or laser gap. We have a scalar electromagnetics or electrogravitation gap." Bearden http://www.cheniere.org/books/ferdelance/intro.htm

"**We have a new weapon, just within the portfolio of our scientists, so to speak, which is so powerful that,**

if unrestrainedly used, it could wipe out all life on earth. It is a fantastic weapon." Khrushchev, to the Presidium, Jan. 1960

> "We've totally missed the most incredible "secret superweapons" development program of all times, and the worldwide testing of the weapons themselves.
>
> "Hiroshima and Nagasaki should serve as object lessons in the price of ignorance of such technological breakthroughs.
>
> "History does repeat itself. But this time it's not we Americans who got the great new superweapon first."
>
> Bearden http://www.cheniere.org/books/ferdelance/s75.htm

Warfare has been changed forever by the development of these scalar energy longitudinal wave howitzers. To get a basic understanding of scalar waves is to have the imagination suddenly run wild as all the implications and possibilities regarding warfare fall into place. One realizes with a certain horror that the world has totally changed, and that there are some very fearsome possibilities. Remember, the power for these weapons comes from the time domain, longitudinal EM waves in the vacuum of empty space, and the power is tremendous and mind-boggling. Being able to blast away at any target from a distant control booth is something that has never happened before. This is incredible power to be in control of and it divides the history of weaponry into "before" and "after." And the destructive power of these weapons is delivered instantaneously to the target from the local vacuum at the place of the target.

From an interview:

> Questioner: "Are you saying that real energy can be transmitted faster than the speed of light?"
>
> Bearden: "Yes. But hyperspatially. Not through 3-space, but "around" it. Again, this means that it's possible to produce energetic changes in a distant system at a distant place, without transmitting energy "through space" in the normal sense. You transmit "around" space, so to speak, and directly in time or through a higher dimension, depending on the model you're using to understand this. Further, the speed of the internal EM energy transmission is not limited to the speed of light."
>
> http://twm.co.nz/beard_interview.htm

Here are some initial considerations about scalar weapons and scalar wars

1. Tesla Howitzer 2. Tesla Domes 3. Rogue groups 4. WW III 5. Russian "UFOs?"

3a. The Tesla Howitzer and its modes of action

Source: Tom Bearden's weapons slides and Fer-de-Lance Briefing

For one thing there is no delivery of any thing to any place. Bombs are obsolete. So are the planes to get them there. No helicopters necessary. All current nuclear devices are rendered nearly useless by electronic "dudding." All distant-destruction can be done from a control room, and to any point on earth. The destructive power of "men" has just increased by orders of magnitude. The new weapons could even cause storms on the sun! Thus there is great urgency to make these new facts public and known, with the hope that all nations would come together to ban the use of scalar weapons.

Two scalar antennae together along with the computers to control them, make up a scalar interferometer, and according to Col. Bearden the Russians have hundreds of such installations already. These interferometers are called "Tesla Howitzers." They can deliver a giant blast of energy to the distant target site, true "action-at-a-distance".

The first howitzer mode is called the "exothermic" mode of operation because immense EM energy blasts outward at the target site. The blast of a scalar howitzer can be of near nuclear level in destructiveness, and can be repeated easily, at that place, or nearby, or anywhere.

The howitzer can use a lesser exothermic power setting and simply destroy all electronics in the target area. Thus they can render our nuclear missiles inoperable as they sit in their silos by "frying" the electronic circuits that guide them. They can bring down any airplane, anywhere in the world, at any time. Any person anywhere, if their exact position is known, can be assassinated without a shot being fired.

The howitzers can also bring down power grids anywhere in the world, at any time. Thus they could bring Wall Street to an instant halt by disabling all its electronics. Even this one little easy tweak of the howitzer could cripple the U.S. economy in a single day. No wonder the "leaders" don't want you to know! This is a new era we are in. The discovery and development of scalar interferometry has put us in a new world, whether we like it or not. Anyone could be expected to go into denial, the befuddled senators and congressmen included. But we have to wake up.

In a second howitzer mode called the "endothermic" mode, the howitzer sucks energy out of the target area, essentially creating a blast of cold at the distant target. It is even capable of freezing parts of the ocean. Bearden gives a number of cases where these "cold explosions" have been witnessed, mostly by airline pilots. April 9, 1984: 1 2 3) A huge mushroom cloud of mostly water is seen rising miles into the sky from out of the ocean, an awesome sight.

In the endothermic mode the sucked-out energy must go somewhere, so it is vented out at some other chosen spot on the earth. These endothermic plumes have been photographed by satellite.

> "The exhaust in the left picture is about 150 miles long, and is nearly horizontal (about 1.5 degrees above the horizontal). It is entirely consistent with the continuous exhaust from a "dumping transfer" scalar EM howitzer in the continuous exothermic mode. (The primary howitzer, of course, was activated in the endothermic mode.)" Bearden More Plumes

By using both of these heat (exothermic) and cold (endothermic) modes together the weather can be altered anywhere. Warm the air over here, cool it down over there, put a curl in the jet stream, dissipate clouds, create clouds, whip up a tornado. Bearden speaks about using the endothermic howitzer mode as a weapon of war:

"Cold explosions can be used to freeze tanks, personnel, and equipment. The equipment and tanks thaw out. The personnel thaw out too, but they are dead when they do." Bearden, Fer-de-Lance

(This endothermic mode of the howitzers makes me think that there might one day be a cure for the problem of global warming after all. Could not a big device, situated in space or on the moon, be able to vent a great deal of excess heat outside the atmosphere into space, thus functioning as a kind of planetary thermostat?)

While the United States has experimented with electomagnetic weapons using ordinary transverse EM waves, the longitudinal [LW] weaponized waves are truly of another order altogether.

For one thing they do not have to travel through space, for they come from the time domain, which is everywhere. The energy of the blast, the heat or light or whatever, comes from the vacuum of space at the location of the target itself. This is astonishing. The weapons actually just trigger the release of immense energy from the vacuum at the target location.

> "... it is possible to focus the potential for the effects of a weapon through spacetime itself, in a manner so that mass and energy do not "travel through space" from the transmitter to the target at all. Instead, ripples and patterns in the fabric of spacetime itself are manipulated to meet and interfere in and at the local spacetime of some distant target. There interference of these ripple patterns creates the desired energetic effect (hence the term energetics) directly in and through the target itself, emerging from the very spacetime (vacuum) in which the target is imbedded at its distant location." Bearden Fer-de-Lance

The big Tesla howitzers are aimed at their targets by using a worldwide electromagnetic pattern called the "Woodpecker Grid," begun by the Russians in 1976.

You can hear the Woodpecker signal here: http://www.cheniere.org/misc/woodpeckersound.htm

The woodpecker grid is just that, a grid of EM waves which provide a channel for the LW waves to any point on earth. Computers use the woodpecker grid information to hone down the aiming of the howitzers to a pinpoint location on earth. (For that matter, it could be under the earth, in space, or under the sea).

A third howitzer mode is what Col. Bearden calls "Mindsnapper" mode. This is a truly frightening mode which affects the electromagnetic mind-body connection. Being mind-snapped at a low level would cause you to lose consciousness. Being mind-snapped at a slightly higher power would "entrain" all minds in the target area into a kind of hypnogogic trance, a state in which they would all be highly susceptible to suggestions and orders.

Being mind-snapped at high level would so disrupt the mind-body connection that everyone in the target area would fall down, instantly dead. Not only that, everything around you and inside you would be killed, so that your sterilized body would not rot for quite a long time.

The Mindsnapper can be used for a small area, or to kill an entire population. In fact, using the scalar waves to affect the human mind has become a new field in its own right, and has been dubbed "psychoenergetics." (This is discussed below in section 5).

Bearden describes the use of the howitzer in mind-snapping mode against people, to cause unconsciousness or death:

> "From a military viewpoint, these scalar EM weapons are really quite all-around weapons.
>
> "For example, they are very lethal against personnel.
>
> "Set in the "high intensity pulse mode," one blast and a person's nervous system is destroyed instantly. Total, instantaneous death results. One can blast away at entire groups of infantrymen, for example. It's the peak power that's important, not the average power. So the weapon doesn't require too much battery power.
>
> "Set on a lower intensity pulse mode, one zap can simply knock out a person, rendering him instantly unconscious. Quite useful if one needs prisoners to interrogate. Also very silent, which is useful in operations employing stealth and surprise." Bearden http://www.cheniere.org/books/ferdelance/s80.htm
>
> "Those hit by the scalar EM weapon, however, have a most peculiar death mode.
>
> "Death comes-instantly and totally. There is no convulsion, no response. The entire nervous system is destroyed instantly. Every living cell in the body is killed instantly, including all bacteria, germs, etc.
>
> "A body hit with this thing falls like a limp rag and lies where it falls. It doesn't decay in even 30-45 days. In a macabre fashion, it's been reduced to something like food irradiated with nuclear radiation; everything is killed, so the material is preserved for an extended period before any decay can set in."
>
> Bearden http://www.cheniere.org/books/ferdelance/s81.htm

He goes on to say that the same "bazooka-sized scalar EM pulse weapon" can also be used to knock out a tank with one shot (or pulse). So tank warfare is obsolete. Helicopters? Bearden points out: "... if he's attacked by a helicopter or a fixed-wing aircraft, he can bring the same weapon to bear on it. He can knock down a chopper or a jet. With one shot."

Obituary for Tank Warfare

Tanks useless against portable LW weapons

> "For example, suppose one attacks a tank. [with an LW weapon] With scalar EM pulse, the personnel die instantly. Total personnel kill is achieved.
>
> All electronic systems of the tank are dudded. Total systems kill is achieved. The ammunition in the tank explodes. Total kill is achieved.
>
> The fuel explodes. This is another total kill mechanism.
>
> That tank has been killed totally, by a variety of mechanisms, all simultaneously.
>
> That's a k-kill in any analyst's book.
>
> And don't worry about retrieval and repair. That tank is finished permanently.
>
> Even the most modern tank is just as vulnerable as the most obsolete."
>
> Bearden http://www.cheniere.org/books/ferdelance/s88.htm

One begins to get the idea how profoundly the conventional means of warfare have been obsoleted. All the usual weapons of war have been rendered nearly useless! And Star Trek's "Phaser," with its "stun" and "kill" modes is here at last.

Although it is the weapons aspect of scalar electromagnetic which has received the most developmental effort, Bearden points out that a great many other amazing things that may be accomplished in this new field of science. Beam me up Scotty!

> "Superluminal communications systems, hyperspace drive, and materialization and dematerialization are all hypothetically possible, using scalar electromagnetics. As the technology develops, we should see the development of many of the systems long thought impossible except in science- fiction."
>
> Bearden http://www.cheniere.org/books/ferdelance/s15.htm

Bearden describes a huge test of the Russian scalar weapons systems which occurred in 1985, a test that went completely unnoticed by western scientists:

> "Just before May 1, 1985 the Soviet Union performed a "full-up" operational test of their entire strategic scalar EM weapons complex. This test was detected and monitored periodically by Frank Golden. Some 27 of these giant Soviet "power taps" were locked into the molten core of the earth, producing forced (entrained) scalar resonance of the entire planet on 54 controlled frequencies under our very feet. The remainder of the scalar frequency spectrum was ablaze with literally hundreds of Soviet scalar transmitters: probably the entire strategic scalar command and control system to

> underwater submarines, higher command centers, distant commands, etc. was activated in the giant exercise.
>
> "For several days, the system was exercised on a mind-boggling scale, apparently as part of the Soviet Union's highly accentuated 40th anniversary celebration of the end of World War II.
>
> "Ironically, not a single U.S. intelligence agency, laboratory, or scientist detected this monstrous exercise for the new Soviet leader, Gorbachev. Not a one of them had a detector for scalar EM radiation, and not a one of them officially believes the exercise ever happened."
>
> Bearden http://www.cheniere.org/books/ferdelance/s38.htm
>
> "The Woodpecker grid/howitzer weapon system can be placed over the ocean and used against cruise missiles, naval surface-to-air and surface-to-surface missiles, submarine-launched ballistic and cruise missiles, etc. Placed over a carrier task force, it can also take care of the aircraft launched by the carrier as fast as they are launched. It can also handily take care of the missiles launched by guided-missile cruisers of the accompanying task force."
>
> (Bearden http://www.cheniere.org/books/ferdelance/s65.htm)

The whole series of the Fer-de-Lance briefing slides and comments is a "must read" for anyone wanting to be aware of the actual state of things in this world right now. It is a new world and it takes some getting used to. Fer-de-Lance speaks clearly, for the layman, of the way things stand.

What is it like to operate these Tesla Howitzers? Col. Bearden gives us an idea in his "Fer-de-Lance" briefing, Slides 66-71.

Who needs armies anymore? A entire war can be fought and won by a handful of men sitting in a comfortable control booth! The scalar electromagnetics revolution has made all previous forms of warfare nearly obsolete.

Why haven't the Russians used the scalar weapons yet?

Bearden gives his thoughts on this in "Fer-de-Lance." The power of these weapons is so great that an accident or war could wipe out all life on earth, and even affect the sun.

> "As can be appreciated, this entire concept [MAD] is now totally obsoleted by the Soviet possession of scalar EM weapons.
>
> 'The "mutual assured destruction" capability -- or MAD concept as it was so aptly named! -- is no longer mutual. And for two reasons: (1) the Soviet surprise attack could destroy essentially all our Triad forces wherever they are, in the first attack. (2) Even if a very small number of our strategic forces survive, the puny strike we could attempt to launch could be repeatedly decimated from launch to terminal phase.

> 'The restraint on the Soviets is not because of our Triad forces. The restraint is twofold: (1) a second nation has scalar EM weapons, and would undoubtedly unleash them upon the Soviet Union with great violence if such a massive world-wide destruction of U.S. forces occurred or was threatened (is it really "accidental" that six major Soviet missile ammunition storage sites mysteriously exploded within seven months?); (2) the closed-loop scalar radiation exchange system of Earth-Sun could be inadvertently "tweaked" in the feedback loop from Earth to Sun, so that a large solar scalar resonance was stimulated. In that case the Sun could emit a mighty resonant "burp" that would simply wipe out all life on Earth in a fiery shower.
>
> 'The "terror" in the "balance of terror" between nations has just increased by many, many orders of magnitude.
>
> 'The biblical prophecy that the Earth will be wiped out by "fire and brimstone from heaven" is very near fulfillment now.
>
> 'Put another way, the pucker factor -- even on the Russians who may contemplate unleashing Armageddon -- is higher than any Western strategic analyst has ever imagined, even in his wildest nightmares.
>
> 'Truly these weapons are "more frightening than the mind of man has imagined," as Brezhnev put it in 1975.
>
> 'The frightening scalar EM weapons can be used, but only very, very gingerly indeed. If a slight mistake is made, everybody loses everything."
>
> Bearden http://www.cheniere.org/books/ferdelance/s74.htm

But the Russians (KGB) are not the worst of it. Bearden claims that some of the scalar weapons have been leased to the Yakuza for about a billion a year, and that only the KGB is holding the Yakuza in check from making a full-scale all out scalar attack on the west.

U.S. Defense Secretary William Cohen

Warns about eco-terrorism using scalar electromagnetic weapons

> "Others [terrorists] are engaging even in an eco-type of terrorism whereby they can alter the climate, set off earthquakes, volcanoes remotely through the use of electromagnetic waves... So there are plenty of ingenious minds out there that are at work finding ways in which they can wreak terror upon other nations...It's real, and that's the reason why we have to intensify our [counter terrorism] efforts." - Defense Secretary William Cohen, 1997
>
> In a letter to a writer named "Russell" Bearden says,
>
> "In short, Russell, the Secretary of Defense of the United States confirmed that there are indeed novel kinds of EM weapons, right now and have been for some time, which have been and are being used to (1) initiate earthquakes, (2) engineer the weather and climate,

> and (3) initiate the eruption of volcanoes. We wrote about those exact uses of the weaponry decades ago. Several nations now have such weapons. Three of them (two on one side and the other on a hostile side) are even firing practice shots into Western Australia, as a convenient test range."
>
> http://www.earthchangestv.com/ufo/0209gandor.htm

Tesla Howitzers in Weather mode

How to Make Weather

> "Engineering the weather is duck soup; they tested that over the U.S. in 1967, and entered upon continuing operations over North America on July 4, 1976 as a grim kind of KGB "Bicentennial Gift" to the United States. Here's how it is done with several interferometers.
>
> "First, the interferometers can deliberately make "high pressure areas" (cool the air so it shrinks and its "footprint" pressure on the ground increases because its density increases) and "low pressure areas" (heat the air so that expands and its "footprint" pressure on the ground decreases because its density decreases). Well, if one makes the highs and lows where one wishes them, and judiciously and somewhat slowly moves them along a given path, these highs and lows will entrain the jet streams and thus "steer" the weather.
>
> "So if you wish a very cold snap or attack, go up into Canada and start these actions to steer down some streams that bring some very frigid air. Establish other highs and lows judiciously to "block" or "slow" other jet streams and flows as desired. In this way, one can pull the "large cold air masses coming down from Canada" deep into the southern U.S. at will. They do it regularly. If you wish an ice storm, add an additional current of warm moist air you bring up (steer up by using artificial highs and lows) from the ocean. Where they meet, you will get freezing rain, then sleet, then severe icing accumulating. This type of attack does rather large damage to the struck area."
>
> http://www.earthchangestv.com/ufo/0209gandor.htm

Whole websites have now sprung up showing weather radar anomalies which may well be indications of scalar weather engineering. One list of over 500 images is here. Cheniere has its own collection here.

In another section at Cheniere are many photos of cloud anomalies which reveal the underlying grid along which the clouds are forming or un-forming. Bearden relates a startling incident in these clandestine ongoing "weather wars."

> "During the spring of 1986, abnormally strong Soviet weather engineering occurred over the U. S., causing a drastic drought in the southeastern U.S. This drought was broken by a colleague who used an extremely powerful scalar EM device to redirect jetstreams. A most unusual and unique signature of the "blocking" against the Soviet scalar EM actions

resulted: Two huge circulations developed in the atmosphere, clearly showed as two adjacent giant "holes" in the swirling cloud cover over the middle and eastern U.S.

"Between these two giant holes, the cloud circulations formed a stream of clouds, moving to the south, looking very: much like a giant vertical "bar" of a huge "Y-shaped" cloud flow.* Several national weathermen commented on this unusual pattern, which had not been observed before. The pattern continued, day after day, as the blocking continued."

* On the weather maps.

http://www.cheniere.org/books/analysis/history.htm

Tesla Howitzers in Earthquake mode

How to Make an Earthquake

"Here's how you initiate a very large earthquake with such weapons. Take a convenient fault zone of set of them. Focus the interferometry on the fault zone, in the "diverging" mode, and deposit EM energy there in the rocks on both sides, increasing (slowly) the stress in the rocks by the reverse piezoelectric effect (deposit excess energy, get crystal mechanical movements).

"Do it slowly, and the stress will build up to large pressures well-above a plate slip minimum energy required. At some point, the rocks yield and one or both sides "slip" and move rather sharply, giving a very large earthquake in that zone.

"Do the same thing down in the earth (remember, LWs easily penetrate right through the earth and ocean at will, and so the "interference zone" focus can be inside the earth or beneath the ocean, at will.

"Anyway, focus this thing down to where the active part of the volcano is still slumbering, down where the hole in the plate has been made. Keep increasing the deposition of energy in the magma itself, and eventually the increasing pressure from deep within that volcano, underground, will cause an eruption. Build the energy slow, and the eruption will likely be much larger."

http://www.earthchangestv.com/ufo/0209gandor.htm

Yugoslav Earthquake, Followed by Cold Explosion

Strange Characteristics of Iran Quake, Sep. 1978

Tesla Howitzers in Tesla's "Big Eye" mode

How to make a Big Eye in the Sky

By using longitudinal wave interferometry in a weakly endothermic mode a new kind of "radar" is now possible, one which can look right through the earth and oceans. Because the endothermic mode extracts energy from the distant target, a pattern of the target area can be scanned for in the returned energy.

> "Thus the receiver produces a representation of the energy extracted from various locations within the distant endothermic zone. By displaying the received signals on an appropriately scanned screen, a representation of the distant scene in the intersection zone can be created. Indeed this is a special kind of "microwave interferometry," and -- with modern techniques -- the imagery obtained might be surprisingly good. With development, it might even become as good as the image presently obtained by side-looking acquisition radars.
>
> "Interestingly enough, since scalar EM beams will easily penetrate the earth or the ocean, one can also look beneath the earth or beneath the ocean with this type of scanning scalar interferometer.
>
> "The importance of this capability to strategic and tactical reconnaissance is obvious. Camouflage, cover, and concealment have no effect on such a system. One can easily look inside buildings and into underground facilities. With a small system such as this, the U.S. Marines at Khe Sahn would have had little difficulty locating the tunnels continually dug under the perimeter by the Viet Cong. And targets under jungle canopies are directly visible."
>
> Bearden http://www.cheniere.org/books/ferdelance/s42.htm

Tesla Howitzers can destroy all life on earth

How to Make a Storm on the Sun!!

(Just make a big mistake with your Tesla howitzers)

The deepest dangers of the use of scalar weapons are frighteningly pointed out by Bearden here where he considers that the sun, earth and moon (actually the whole solar system) is a delicately balanced arrangement of scalar (longitudinal) EM radiation. There is a scalar connection between the earth and the sun, which are both giant dipoles gushing energy in the time domain. Big scalar events on the earth could alter this balance causing true catastrophe.

"Indeed, a solar response could be stimulated so that the Sun would violently belch and destroy our biosphere, among other effects."

Unrestrained scalar warfare could cause huge solar storms? To realize that human activity could actually affect the sun itself is truly mind boggling.

Bearden goes on to say:

> "Accordingly, use of huge scalar EM weapons is a double-edged sword. Unless carefully employed, use of the weapons could cause a terrible backlash to the user as well as the victim, and even accidentally cause the destruction of the earth itself. It is not accidental

that in 1960 Khrushchev stated that his new fantastic weapon could -- if unrestrainedly used -- destroy all life on earth.

"This appalling backlash potential is apparently what prompted Brezhnev in 1975 to make so strong an effort to get agreement to outlaw the development of "new weapons of mass destruction" more frightful than the mind of man had even dreamed of. Gromyko even introduced such a draft agreement into the proceedings of the United Nations. The first article of the draft agreement indicated that the nature of the weapons referred to would be negotiated. Sadly, the entire Western world did not even know what the Russians were talking about."

http://www.cheniere.org/books/ferdelance/s24.htm



3b. Tesla domes provide near-perfect defense shield.

(Slide from Cheniere.org)

The Tesla howitzers can be used in a nearly impregnable defensive mode whereby they throw up a dome (**Tesla Dome**) or a sphere (**Tesla Globe**) of highly powerful electromagnetic energy, enough to "dud" or destroy missiles which try to penetrate them. Once again, this energy is not going through space from the howitzer, but being made to emerge from the local vacuum at the location of the shell. KGB tests of these domes have been witnessed by airline pilots around the world. Bearden gives many examples of the Tesla domes being sighted around the world in his briefing paper "Fer-de-Lance." (Russian dome test, another globe incident, yet another globe test). These giant electromagnetic domes can be hundreds of miles across, or narrowed down more to total impermeability.

> "Such a shell may be several hundred miles in diameter at the base. The enormous energy required to form such a defense shell is obtained by a "scalar power tap" into the molten core of the earth itself, as previously explained. In late April/early May of 1985, 27 such "power taps" were placed in the earth by the Soviets. If each tap is capable of powering four to six large scalar EM weapons, then the Soviet strategic scalar EM arsenal contains over 100 monstrous superweapons capable of generating exothermic explosions, endothermic explosions, engineering the weather, locating and destroying underwater submarines, detecting and destroying ballistic missiles shortly after launch, detecting and destroying long range strategic bombers as soon as they are airborne, etc."
>
> http://www.cheniere.org/books/ferdelance/s52.htm

By using nested domes one can protect the domed area even against nuclear radiation itself. Tesla globes can be used to hit airborne targets by simply placing a globe of any chosen size in the flight path of the incoming missile. It does double duty because the missile hits it going in, and then the rubble hits it again going out the other side.

While the U.S. persists in its useless boondoggle "missile defense system" by shooting a missile with a missile (missiles which would already have been "dudded" by the Tesla howitzers), between the domes and the globes the Russians (KGB) have in hand (operational) a nearly perfect missile defense system. Someone should ask the Secretary of Defense if the U.S. Tesla domes are in place. And over which cities? How powerful are our American Tesla domes?

Bearden cites a number of examples of these domes being tested around the world:

March 20, 1969 | March 24, 1977 | August 17, 1980 | June 17, 1966 | June 18, 1982 | June 22, 1976

In a slide from the Fer-de-Lance briefing it is shown how the "woodpecker grid" itself also acts as a sensor, detecting any missile launch anywhere, and how the howitzers can respond instantly by delivering a blast to exactly the right coordinates, right along the channels of that same grid which is feeding the location information about the missile launch. This certainly beats "trying to hit a bullet with a bullet." Especially since YOUR bullet would probably be instantly inoperable in a real scalar war situation.

3c. Rogue Groups in the government

Bearden fears that these scalar electromagnetic secrets may have fallen into the hands of what he called secret "rogue groups" within the labyrinthine depths of the black-ops special-access domain of the secret government. "In the extreme, such a deep black program can even become a "captured" program," he says, "which is totally in the hands of rogues and no longer reports to or is bound by the dictates of the parent government."

> "They have their own agendas. And being rogue groups, they may well bring in unethical, immoral tricks: assassination, bribery, entrapment, disinformation, plausible deniability, etc. A certain percentage of a highly secret rogue group will wind up using all these things and more. It's a human characteristic, the old primate dominance game. Only now disguised and hidden under deep classification. ...
>
> "In highly classified groups, these groups are greatly enabled to joust more widely, unethically, and immorally because it is so deeply hidden. So very deep classification evokes the growth and intensity of rogue groups. It's the old 'Power corrupts, and absolute power corrupts absolutely' routine. ... Due to loose formation of rogue groups inside such programs, they may have dual or triple purposes, may not operate under very much legitimate government control at all, and may operate specifically for the purposes of the rogue group or groups that have gained control."
>
> "The involvement of at least some rogue groups, some being "cowboys" who operate well outside all laws and ethics, could also result in such things as assassinations, clandestine testing on individuals without their consent, etc. In short, it could account for what seems to be actually occurring. "
>
> http://www.cheniere.org/explore%20articles/mind%20control3/p05.htm

3d. World War III has already begun

Because it is now possible to cripple the power grids and electronics of any nation, that nation could be reduced to economic ruin without ever firing an actual "shot." Without electricity Wall Street cannot operate. Without electricity you quickly need martial law. One no longer needs to wage a conventional war anymore at all. There are now lots of new ways to bring any nation to its knees.

> "We are at war, whether we like it or not. And we are going to have strategic strikes on an unparalleled scale for us. Pearl Harbor was nothing compared to what is coming down, once we consider the "augmentation" and such.
>
> "When that factor is considered, then it's a totally new ball game on replacing the power system. There isn't going to be much choice; the old one is going to be destroyed or so badly crippled that it will collapse the U.S. economy in a way we have not seen since 1929. Of course, in such a case hitting us, we will be under martial law, the works, everywhere. For one thing, it's the only way you can keep the cities from imploding from within, by the criminal element, looting, robbing, killing, etc. Simply wait and see; it's on the way."

> Although Bearden has for years decried the "scalar-gap," and chided the military for falling so far behind the Russian KGB in the field of scalar electromagnetics, recent statements indicate that things may at last have changed somewhat.
>
> "In the new war, the first phase of WW III has already been completed. Hence President Bush's recognition that this is a total war, and has to be taken to the enemy no matter where he may be hiding or in what sanctuary or in what foreign nation. This is an entirely different war than anything the U.S. has ever fought in its history. And before it is over, it is going to kill more Americans than have died in all the previous wars in our history. The news media and the public have not yet recognized that awful situation and predicament. Most are already thinking that, well, we won in Afghanistan so it's just about over. Instead, it has only just begun.
>
> "Anyway, that's a brief uptake on some of the weapon situation today. Some 10 nations or more now have LWIs, and five have the QPs. I'm still working on how many have the appalling negative EMP weapons, but would estimate 6 or 7 nations have them in one stage or the other, either deployed or in at least advanced development. And in my estimation, the Yakuza will have them within three to five years if they have to build them themselves, and quicker if they can buy them from the Russians, Chinese, or???"
>
> Bearden http://www.cheniere.org/correspondence/030202a.htm

When he was asked the question '**Does the government listen to Tom Bearden?**" Bearden said:

> "Let me speak carefully. I am very satisfied with how I've been listened to in the quarters where the rubber meets the road. The West is no longer defenseless, not by any means. Cannot amplify it further than that."
>
> http://www.cheniere.org/correspondence/030202a.htm

Bearden has briefed the government a number of times and the Cheniere website contains a great number of his graphic military briefing slides.

3e. Are the Russians making "UFOs?"

Scalar electromagnetics engineering opens the possibility of antigravity vehicles and "hyperspace travel." In other words we can now make our own UFO's! Of such scalar-powered antigravity vehicles, which have now become possible, Bearden has this to say:

> "We might expect to see such vehicles glowing. Their various surface features and mechanisms might appear to be glowing or revolving lights, etc.
>
> "They could exhibit incredible "aerodynamic performance," seemingly in the atmosphere. Actually they would not be moving "through" the atmosphere at all, but through a higher space outside each particle of atmosphere.

> "They could seem to materialize and dematerialize.
>
> "They could seem to plunge into the ocean or rise out of it.
>
> "They could even seem to operate under the ocean or inside the earth itself.
>
> "Such anomalous vehicle performances have been seen all over the world, particularly since a few years after WWII.
>
> "It appears that one or more nations of Earth are operating such vehicles now in great secrecy. Our own "government" may even be one of these.
>
> "If so, it isn't our true "government/government." Instead, it's the "control group/government." It's government at the operational level, but at higher level it belongs to certain control groups who have penetrated our government's vitals and taken over all such projects."
>
> Bearden http://www.cheniere.org/books/ferdelance/slide32.htm

In an excellent article on her Earthfiles website, Linda Moulton Howe reports on the utter bafflement of Norwegian scientists over mysterious lights appearing in the valley of Hessdalen, Norway.

She writes of the research there: "The results can be broken down into two groups: 95% are thermal plasmas and 5% are unidentified solid objects. The plasmas emit long wave radio frequencies and strangely, their temperatures do not vary with change in size or brightness." She quotes the scientists' research summary:

> "1) most of the luminous phenomenon is a thermal plasma;
>
> 2) the light-balls are not single objects but are constituted of many small components which are vibrating around a common barycenter;
>
> 3) the light-balls are able to eject smaller light-balls;
>
> 4) the light-balls change shape all the time;
>
> 5) the luminosity increase of the light balls is due to the increase of the radiating area. But the cause, and the physical mechanism with which radiation is emitted, is currently unknown."

This would almost certainly seem to be another example of the testing of the scalar howitzers. It is baffling because, as Bearden points out repeatedly, Western scientists have limited knowledge of the scalar electromagnetic principles by which the howitzers operate. The Hessdalen scientists were completely baffled as to where the energy of these plasma balls was coming from.

Ms. Howe interviews Massimo Teodorani, Ph.D., Astrophysicist, who released the report on the 2001 Hessdalen sightings. The scientist speaks of the baffling phenomenon observed.

> "I don't know how it is possible that Nature is spontaneously able to do that. Anyway, we deduce that the plasma is trapped inside a sort of magnetic cage and the magnetic cage closes around the plasma and keeps it fixed in some way, prevents it from expanding. But where does it come from? We don't know."

By what we have been considering here, we can recognize the signatures of scalar electromagnetic engineering. If it is a Tesla howitzer, then the energy for the plasma balls is coming from the vacuum of spacetime at the very location of the balls themselves, triggered by scalar interferometers aimed through the woodpecker grid.

These kind of balls can be used as marker beacons giving feedback for precision aiming of the howitzers. The energy of the marker beacon can be read back into the computers giving precise location information for pinpoint aiming. The target area can be very small, or widened out.

There is a little movie of one of the Hessdalen plasma balls here. It would seem to be a clear documentation of a scalar howitzer marker-beacon. How many other current "UFO" sightings are actually the witnessing of Tesla howitzer tests?

In fact there are a great many anomalous events of the past few decades which might very well be explained by the Russian testing of their longitudinal electromagnetic weapons. It would seem that the mysterious appearance of crop circles around the world could be accomplished by feeding a precise mathematical graphic pattern into the computerized aiming software and change the very molecular structure of the crops themselves along the lines of that pattern. The

stalks fall over from the localized effect of the longitudinal waves. A plasma ball tracing patterns? Are they slyly sending a message to see if we are "getting it" yet?

The "Cambridge Angel" - Made by Russian scalar plasma balls?

Also see: [Interview with Tom Bearden]



Attempt to Ban Energetics Weapons Worldwide

- On June 13, 1975, in a major speech Brezhnev urged the United States to agree on a ban of research and development of new kinds of weapons "more terrible than anything the world has known."
- On July 2, 1975 Brezhnev repeated his proposed ban on development of frightful new weapons, to a group of U.S. Senators.
- In August 1975, Ponomarev called for a ban on frightful new weapons of mass destruction.
- On Sept. 23, 1975 Gromyko presented a draft treaty agreement to the 30th Session of the UN General Assembly, for banning development of frightful new weapons.
- *No one had the foggiest notion what the Russians were talking about!*

© 1996 T E BEARDEN

(Slide from Cheniere.org)

4. Healing powers of longitudinal waves

Healing via longitudinal waves, time reversal of cells (de-differentiation), Priore's machine, Bearden's proposed "blanket" version, using the electric power grid for healing waves or for broadcasting disease patterns. Scalar Biowar.

The good news!

> "Any sort of disease whatsoever - physical or mental - will be rapidly curable, simply and cheaply. It will be possible to reverse aging and rejuvenate the person. It will be possible to regrow limbs and straighten misshapen spines - and directly remove the causes of mental diseases and cure them as well. Lifespan will be staggeringly increased, without 'old age's debilitation.' AIDS, cancer, leukemia, and genetic diseases will be completely conquered. The potential for a true golden era is upon us, for all humanity."
>
> Bearden- http://twm.co.nz/beard_interview.htm

Proof of the healing powers of longitudinal waves from the vacuum is seen in the work of Antoine Priore who produced longitudinal scalar waves using a gigantic glass tube filled with plasma. He himself did not understand why it worked or how it cured cancer in animals.

> "The Priore team cured terminal tumors, trypanosomias, and other dread diseases in laboratory animals in France, in the 1960s and 1970s, under rigorous scientific protocols by eminent scientists. The Priore project was funded by the French Government to the tune of several millions of dollars (equivalent).
> http://www.explorepub.com/articles/energetics.html
>
> ". . . Prioré's machines concretely demonstrated a nearly 100% cure of all kinds of terminal cancers and leukemias, in thousands of rigorous laboratory tests with animals. These results were shown to medical scientists as early as 1960." http://www.cheniere.org/priore/index.html

Bearden has stated that the longitudinal EM waves can have a healing effect because they always come in pairs called "phase conjugate pairs" and one of the pair is time-reversed. This enables engineering of the waves to "pump" the cells of the body (with waves from the time domain) and actually time-reverse the cells back to a previous healthy condition. The scalar cure of cancer does not involve killing the cancer cells but rather pumping them with time energy into a previous condition. I know, this seems miraculous, and is it not?

Priore and his giant plasma tube

This healing power in the longitudinal waves of the time domain is a mind-boggling thing to face. It took me months to get through it, and to suffer the fact that the cure for cancer and AIDS was right there, in this new scalar electromagnetics technology, and that it has been kept back from the people for so many decades now.

Bearden has a great deal to say about the work of Priore, who himself did not understand why his machine worked. Priore did not know about the longitudinal scalar waves of the time domain. In fact, Tom Bearden has supplied, at last, the missing explanation as to how that big giant two-story glass tube consistently cured cancer in animals.

"**The medical implications are enormous**. By just reversing the damaged cells back to a previous physical state, this gives a physics mechanism for controlled cellular dedifferentiation, in biology terms. Physicians will time-reverse diseased, damaged or aged cells back to an earlier healthy condition, including all the cellular genetics. Normal cells are just reversed to a slightly younger condition."

> "We believe this mechanism explains the revolutionary but baffling electromagnetic cures achieved by a team of outstanding French scientists in the 1960s and early 70s, working with inventor Antoine Prioré. In lab animals, cures were achieved for terminal tumors, infectious diseases such as trypanosomiasis, and atheriosclerosis. In addition, deliberately suppressed immune systems were dramatically restored.
>
> "We hypothesize that this is the long-sought mechanism of how the living body heals itself. In short, the body's cellular control system induces cellular reversal by weak time-domain pumping of the damaged cells and the affected area. The cellular regeneration system performs all healing of cellular damage in the body; the immune system heals nothing, not even its own damaged cells) .
>
> "For the first time medical science can develop as a science of healing rather than a science of intervention. And it will develop as a science of unlimited healing, since no pathogen can resist action by curved spacetime engines." Bearden
>
> http://www.cheniere.org/techpapers/Vision%202000%20paper.doc

See Priore's machine See Slides of how it works.

Bearden has extended the Priore work, with the previously missing knowledge now in place, and designed a revised system (for irradiating the body with longitudinal waves) which gets rid of Priore's giant glass plasma tube and uses instead an antenna unit which surrounds the body. He has also provided the missing explanation of how it works. There is an article from "Explore" magazine, Part I and Part II.

In fact, Bearden has presented to the U.S. government a plan to use a portable version of a Scalar Healing Blanket where wire channels in the blanket act as a scalar antenna, which can both send and receive scalar electromagnetic waves. A two minute treatment of the waves is sufficient to restore the body to its earlier healthy condition. Thus even thousands could be treated easily and quickly in a biowar mass attack situation.


RETRORADIATION WITH EMITTED TW EM WAVES
Recorders & Broadband Amps
Broadband Antenna Unit
Control Unit
Receiver-transmitters
© T. E. BEARDEN 1998
Adjusting broadband signals bandwidth and amplification
Using an amplified replica of the body's own dense, broadband signal complex to irradiate it, producing deeply-penetrating and precise longitudinal EM wave sets that pump cells and reverse cellular disease and damage

"To defend against things like anthrax attacks on our civilian population centers, we also have recommended to the U.S. Government the crash development of small, portable treatment machines—using similar "antiengine-forming" and cellular reversing "porthole technology". [See Figure 13 on previous page]. Such portable machines could be developed cheaply and quickly, and present government facilities could be used to massively attack the correlate database production problem. "The portable treatment units could be cranked out by the hundreds of thousands and flooded down through emergency response agencies such as the police forces, the National Guard, emergency hospitals,


Portable Priore-Type Treatment System
Equipment Case
Computer Control Unit
Infolding Function Generator

> emergency response teams, etc."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control3/p04.htm

The Scalar Healing Blanket would fit into large suitcase. It has three basic parts, the longitudinal wave generator, a laptop computer, and the antenna-blanket. The plan was a stroke of Bearden's genius, but unfortunately it fell on befuddled government ears. "Unfortunately, so far the DOD [Dept. of Defense] doesn't even understand what the heck we're talking about!"

Article "**Healing with Energy**": http://www.explorepub.com/articles/energetics.html

> "We tried very hard in 1998 to call attention to the extreme national need for the most urgent possible development of a portable computer-controlled treatment device based on the experimentally proven Prioré methodology, but extended to a much simpler and far more rapid method of treatment.
>
> "Quick development of this technology could lead to a suitcase size device, capable of treating a patient in less than one minute, and stopping the symptoms and disease progress cold, then reversing it. Three "less than a minute" treatments one week apart would be required for complete cure. As an added advantage, partial reversal of aging in older patients would also be accomplished as a bonus, in addition to time-reversing the damaged and diseased cells...
>
> "The method proposed to the DoD in 1998 used normal EM in a peculiar way to force the body itself to make its own time-polarized EM waves, and pump every part of its cells -- including the genetics -- in the time domain.
>
> "Quite simply, we are going to be struck this way (QP spreading the immune systems of the populace plus professional smallpox, anthrax, etc. BW attacks on our population centers) and by other means we've spoken of in other papers and briefings."
>
> Bearden http://www.cheniere.org/correspondence/021401.htm

The Dark Side of the Force:
Creating and broadcasting disease

Speaking of the scalar wave induction of disease by longitudinal wave patterns Bearden refers to work by French scientist Kervran Russian scientist Kaznacheyev, who proved that any disease could be transmitted electromagnetically.

> "It works this way: the Kaznacheyev experiments (and others) demonstrated that any cellular disease or disorder can be initiated into cells at a distance, by electromagnetic means (albeit unusual EM in nature). The decades of microwave radiation of the U.S. Embassy in Moscow, was an ongoing set of "stimuli" to ping the U.S. system and, by its response, ascertain how far along (or if it was "along") in its knowledge of such weapons. The radiation was responsible for many health changes in personnel and for the eventual deaths of three U.S. Ambassadors."

> Bearden http://www.cheniere.org/correspondence/021702a.htm

In a letter he writes,

> "Yes, the Kaznacheyev experiments were quite real; 15,000 or so in military research institutes in Siberia. As with so many other novel areas investigated and developed by the Soviets, most U.S. investigators just assumed normal EM, which is not what the Kaznacheyev experiments involved, and not what was carrying disease induction patterns from one cell culture to another in rigorous lab tests."

How to "Broadcast" Diseases

Longitudinal EM Biowars

Bearden explains how the new quantum potential weapons can be used to induce disease-at-a-distance in a population, or to "spread" the immune system so thin that a conventional bio-attack would be greatly potentiated. By "broadcasting" virtual disease patterns over a population, the immune system is so overloaded by the presence of the "shadow" diseases that its effectiveness is thinned out.

> "In short, alter the internal wavestructure, and one creates a curved spacetime 'engine' that acts on mass in any fashion one chooses to design -- including initiate diseases . . . Now visualize one of these 'vacuum engines' or 'spacetime curvature engines' that acts on mass to generate the exact effects produced by anthrax. (Or any other disease one wishes) . . . Call the virtual state of a disease engine the disease pattern in the "shadow" state, just prior to becoming observable. . . .
>
> "And the master cellular control system responds to "coming events that cast their shadows before". In short, it responds to the upper level of the "shadow state" of a disease, still in the virtual state! (Hey, virtual particles are real, virtual photons are real, virtual ST curvatures are real --- just very fleeting, only for another to immediately arise). The exchange of virtual particles is known to generate all forces in physics anyway! . . .
>
> "So the cellular control system responds to "shadow state" disease patterns. Enter a QP weapon application. Place a quantum potential weapon "area" on the United States, so that the entire populace is in it. The slowly introduce and bring up in the shadow state, the necrotizing fasciitis disease engine. At some point, the cellular control systems will react, and order the immune system into action. In other words, immune system resources will be committed against this "immediately coming" enemy. Bring it on up a little, but still just in the shadow state. Voila! Humans form a bell-shaped distribution curve. And even if the structure of the QP fluctuates a little, fluctuating a bit stronger and a bit weaker, etc. A few of those targeted bodies will now actually develop necrotizing fasciitis. So far, just like the U.S. Embassy targeting, except a different "carrier".
>
> "But now there is an exact signature that this is what is doing it, and not normal vector carriers of disease and contact or exposure infection. The few cases of necrotizing fasciitis that break out will be most puzzling. They will be randomly scattered across the

> entire nation, and so few that the vector carrier and contact or exposure explanation completely fails."
>
> "And that one happened, right here in the U.S., not so long ago. Check it out.
>
> "So carefully adjust the patterns for, say, 12 major terrible diseases, to that "adjusted and desired shadow state level". Now add all 12 patterns into the internal structure of the quantum potential. Now it has 12 shadow state disease engines in it.
>
> "Place that one on a populace. The cellular control systems order the immune systems into action, and they now have to commit their finite resources to 12 different areas. This greatly thins the response an immune system can make to any one of those 12 disease patterns! In short, it "spreads" the capabilities of the immune system, which can be galvanized to great effort, but only can perform a small bit against each area.
>
> "Suppose one of those "galvanized" areas in the targeted populace's immune systems is anthrax. And suppose the bad guys now hit one or more of those cities with a professional anthrax attack. A former OTA study showed that a professional anthrax aerial spray attack against Washington D.C., dispensing 100 kilograms of anthrax spores in the spray, will account for 1 to 3 million casualties. And that's in an "unthinned" set of immune systems. In the "thinned" set, one can at least double or triple, and even up to five times, that estimate. So conservatively, now there would be from 2 to 6 million casualties. And even mild anthrax spray attacks in other "thinned" cities would also be amplified.
>
> "That one is being set up, or already set up, right now. There are other such "augmentation" setups also under way.
>
> "So the weapons alluded to by the SecDef in 1997 are already being employed. WW III has already begun, and our populace (and our scientific community) is blissfully unaware of it."
>
> http://www.cheniere.org/correspondence/021702a.htm

Most of us can remember the strange outbreaks of the so-called "flesh eating disease." It seemed to break out here and there randomly with no known cause. Bearden believes this was a test of the newer quantum potential weapons which go even beyond the capabilities of the Tesla howitzers.

> "The Kaznacheyev "disease induction by novel electrodynamics" work is also the basis for the spacetime curvature engines (not EM signals!) carried by quantum potential EM biological weapons for distant induction of diseases etc. into the population of an entire nation or area, such as the U.S.
>
> "This quantum potential disease induction weapon -- capable of attacking an entire population of a nation or area -- has been tested several times in the U.S. at very low levels, in the shadow state only (we explain shortly) and it has a most peculiar signature. E.g., one test used necrotizing fasciitis (flesh-rotting disease) engines.

> "The disease 'engine' was deliberately kept down in the 'shadow state' (virtual state, just below the observable state) so that only a tiny bit of the populace with depressed thresholds would "breach the observable threshold' due to the population forming a bell-shaped curve as to the threshold level. The major signature of the test was that the cases of the disease broke out totally statistically and randomly, spread all over, without any 'disease vector' in between.
>
> "In short, it was not spread in any manner required by normal deterministic disease vectoring, but was a totally random set of occurrences. Several other diseases were also tested this way in the American populace, with precisely the same signature."
>
> Bearden http://www.cheniere.org/correspondence/021401.htm

"Apparently one planned use of such an augmented clandestine BW weapon will be smallpox, e.g. As you know, the Russians did develop smallpox for biological warfare, and even developed a new strain against which previous vaccination is ineffective.

> "The vast numbers of expected casualties, coupled with immune system spreading, are absolutely irresistible to the Russian mind. You can count on it that they have seen that the smallpox is already on site here, in the U.S. and in the hands of professional terrorist teams. Of course, the Russians/KGB will protest they have nothing to do with that! Yet likely the KGB will have flatly arranged it or at least assisted it. The capability for mass destruction of the nation is so lucrative and easy to achieve in advance, that they would never be able to resist doing it."
>
> Bearden http://www.cheniere.org/correspondence/021401.htm

Bearden believes the Gulf War Syndrome involved the use of scalar technology to induce a disease state, as he stated in a 1997 interview:

> "I'll say this flatly, and I won't answer any further questions about it; the Gulf War Syndrome was induced... It was induced with this stuff. All the rest... was contributing factors that everybody's talking about... There are some deeper signatures, if you look into it very deeply, that show you exactly how it was done and the fact that it was induced. It was a test. It was a test of a very special kind of weapon I have not talked about yet. Anyway you can use it to create diseases."
>
> Bearden http://twm.co.nz/beard_weapon.htm

Besides using the woodpecker grid to target a population, the entire electrical grids of nations can be used as "channels" for disease patterns to be broadcast to all people near that grid. Your own house wiring can become an antenna, broadcasting these "shadow" patterns of disease, weakening your immune system.

And here one faces the frustrating fact that the same power grids could be set to channel patterns which would keep the entire population healthy, rejuvenated, continuously bathing in the time-reversing old-age-defying energy of the spacetime vacuum. We have no idea yet of how long the human life span could be increased with this new technology. People might be able to live two centuries given full humane development of this technology.

5. Psychoenergetics

Mental entrainment, inducing hypnogogic trance, mind control, broadcasting thoughts and feelings, the Ant World, education via EM [LW] mental download, the "Feelies," revolution in spirituality, "enlightenment machine?" Scalar churches?

Psychoenergetics is simply using the scalar interferometers to manipulate and engineer the human psyche. To me it is the most mind-boggling and frightening aspect of longitudinal wave engineering.

The mind is electromagnetic in nature, and itself of the time-domain. It is not observable in 3-space. There is no thing you can point to that is the mind. As Bearden says**, "The mind is time-like**."

The longitudinal scalar EM waves are also of the time-domain. By overlaying certain infolded patterns (oscillations in time) on the longitudinal waves, a thought or feeling may be made to arise in a person or persons who are in the **interference zone** (where the wave beams cross).

The person will not notice anything, feeling that this thought or idea is his or her own idea. The longitudinal wave pattern might be a wave of panic or fear that spontaneously sweeps over you, perhaps inexplicably. It could even be in the form of a sudden intense patriotism. It could be explicit words and phrases, which everyone would think they had thought of by themselves. Or it could be rage and hatred, angry and violent. On the other hand It could also be a continuous sense of docility and placidity. This is the brave new world of psychoenergetics and the coming "Mind Wars."

Scalar Psychoenergetics in its most primitive form simply "entrains" all minds in the target area into a deep hypnogogic trance. In this state of mind people would be suddenly extremely suggestible, and would likely believe anything they are told, and would obey any orders given. Talk about winning the hearts and minds of the American People!

Tom Bearden makes me think of **Paul Revere**, who heroically conveyed important warnings for the sake of the new nation. But the words of the famous phrase have now strangely and curiously mutated into the once-inconceivable: '**One if by land, Two if by mind**."

Indeed one strategy in a Mind War would be to simply take over the minds of the "leaders" of the enemy nation. The targeted leader would not be aware that anything was amiss, although he might begin to make unexpected changes in policy.

And are, in fact, any of our "leaders" already having secret thoughts that are not their own? Who knows? Frighteningly, we can no longer be sure. The new sciences of scalar electromagnetics and psychoenergetics are even now plunging humanity into a sudden science-fiction-like world beyond anything in humanity's previous imaginings.

> "The Russians reached the point in the mid 1990s that they could take over control of a person's mind, with modified longitudinal EM waves including some time-polarized EM waves, and with a team of specialists (estimate 25-30 per transmitter, and one transmitter and team per controlled person)." Bearden http://www.cheniere.org/misc/time.htm

In a slide Bearden illustrates how a Scalar War would involve a psychoenergetics attack on the operators of the enemy scalar installation, entraining their minds into hypnogogic trance and getting them to shut down their systems.

And ultimately psychoenergetic warfare goes to the very heart of human identity itself. For if my thoughts might no longer be "mine," then who and what am I? Can my very sense of being "me" be hijacked by some nefarious psychoenergetic scheme? Will the "secret government" eventually dictate directly into your mind how you feel about yourself? Or what you think you are? Or what you should do?

How Does Longitudinal EM Mind Control Work?

The physics of scalar psychoenergetics as expounded by Col. Bearden seems even more arcane and over-my-head than that of extracting energy from the vacuum. I can't understand it, but I look through it anyway. Each time another tiny understanding might occur, or a term might fall into place. I know the mathematics is forever beyond me.

One paper to begin with is “Mind Control and EM Wave Polarization Transductions” This is such serious stuff that Bearden includes a strong warning about misuse of this knowledge. Psychoenergetics weapons can mentally maim and physically kill.

Warning!

(From "Mind Control and EM Wave Polarization Transductions")

> "This article refers to experimental research techniques which can be detrimental or lethal in the hands of any but highly skilled, qualified experimental scientists proceeding under proper laboratory safety procedures. The purpose of this article is strictly for information to properly qualified and authorized scientists in certified laboratories. We do not propose or condone any use of these procedures for nonapproved practice of medicine without a license. Neither the publisher nor the author are responsible for accidents or outcomes in the use of these experimental procedures and techniques. Any researcher who performs these procedures and experiments is acting on his or her own volition, and is solely responsible for insuring safety, qualifications, and legality of the acts and their results. We neither suggest nor condone unauthorized experimentation on human subjects. Such is a criminal violation of the constitutional rights of the subject under Federal and State laws, and is both illegal and immoral."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control1/p01.htm

After the serious warning comes the description of the paper. This is heady stuff for the layman.

> "Calling full attention to the special note above, in this paper we present a high-level overview of the novel electromagnetic nature of mind operations, mind and body coupling, and intent - the induction of physical 3-space EM energy changes into the brain and nervous system, and into every cell of the body, from the mind's time-like coherent operations. We summarize the time-polarized electrodynamics used to engineer and affect mind operations and the mind-body coupling loop. Transaction mechanisms whereby differing EM wave polarization's can be transformed one-into-the-other are presented."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control1/p01.htm

I will leave it to the technically astute to try to understand the mechanisms of operation which are described in scientific language. But there are tidbits for the layman. Here he speaks of the difficulty Western scientists have in opening up to the "immaterial" (longitudinal wave) nature of the human mind.

Western Science Remains Largely Materialistic

> "Ironically, most Western scientists are materialists and consider "mind" as a mystical and nonscientific concept. They tend to consider mind operations and functions either to be simply "meat computer" operations and functions, or at best to be very weak ordinary transverse-wave EM operations and functions in the brain and nervous system. This serious self-limitation exists because in the body we measure only weak TW [transverse wave] EM operations and functions correlated to biological behavior and brain operations. We simply do not know how to measure "mind operations" directly.
>
> "With no mind measurements possible and no instruments, it is understandable that Western science considers only the physical side of the mind-matter interface.
>
> "Presently our scientists do not measure the longitudinally-polarized EM wave operations and functions in the body and around it in nature. Few of them are aware that a maelstrom of such LW [longitudinal wave] functions exist in the body and in all of nature in general."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control1/p05.htm

Western methods of influencing the mind with EM waves have only used transverse waves, not the longitudinal waves of the vacuum. If only transverse waves are used one pretty well has to hit the target mind with a sledgehammer of waves.

Western Science knows only transverse EM waves

Brute Forcing Time Functions versus Fine Control Methods

> "Ironically, Western mind control researchers using transverse EM waves for mind control research, are using a brute force method of evoking and using vacuum engines

> (spacetime curvature engines) and a special form of general relativity, although they do not appear to realize it.
>
> "While KGB scientists also use TW EM "brute force" TW waves when necessary, they do "imprint" or "activate" those waves with the desired internal LW and time-polarized EM wave and photon structures required to directly perform the mind engineering desired... Bearden
>
> "These "fitted brute-force models" certainly can be very powerful, and certainly can produce the exact results shown in the experimental verifications of the fittings. However, they do not of themselves allow sophisticated design for example of the necessary time-polarized wave assemblies for engineering the entire human collective unconscious simultaneously, or for engineering the entire collective unconscious of all species on Earth (i.e., Gail’s collective unconscious), or even for precisely engineering the memory and knowledge base of an individual.
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control1/p09.htm

The seemingly magical operations of psychoenergetics, sometimes called "psychotronics," cannot be achieved with ordinary transverse EM wave energy. But they are possible with longitudinal scalar waves because the mind itself is scalar in nature.

> "We note that all mind operations are time-like, i.e., they are comprised as scalar EM photon functions and scalar EM wave functions. Thus the mind is a very special kind of electromagnetic system, existing in the time domain..."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control1/p08.htm

The engineering of the mind can only be accomplished with the waves of time.

The course of psychoenergetics development necessitates the building of a vast database of settings and patterns which bring about given mental and/or emotional states. A kind of "gnome" of the psyche. Bearden describes the process of the decoding of this "gnome."

> "Now the scientists would perform many phenomenology experiments, making one little change at a time and profusely recording the data. Each time, they would establish the physical change(s) that occur in the body and/or the mental and emotional changes that occur in the mind for each spectral reinsertion back through the "ship's portholes". They would simply but painstakingly (over some years) build up an extensive database of those individual correlates.
>
> "In these experiments, the experimenters will eventually be able to provoke any body or mind change they wish. Strong emotion. Intense pain. Intense pleasure. Painful thoughts. Images. Memories. Perceptions. Dreams. Visions. Memory losses. Memory changes. Personality changes. Etc. The "delta" in the emission spectrum (the changes from zero reference spectrum) represent the precise totality of all mental, physical, organic, chemical, etc. changes and interactions."

> Bearden http://www.cheniere.org/explore%20articles/mind%20control3/p01.htm
>
> "A second stage in the research would be to test the correlates and porthole insertions upon a statistically significant cross section of ordinary people, and/or specialized populations (such as toughened soldiers). The program would evolve a highly complex, very effective, ever-improving science and technology of mind and behavior control and engineering mechanisms, complete with finished database and developed applications equipment."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control3/p02.htm

Summing up his paper Bearden speculates on what the actual situation the science of psychoenergetics probably is. The intense secrecy with which this knowledge has been kept from the public has led to the current farce of the "government" pretending it all does not exist, and this secrecy may have now put us at great risk.

> "The implication is that in the West one or more highly classified, sustained, heavily funded developments in advanced mind control programs, probably exists and probably has existed for some time. Due to loose formation of rogue groups inside such programs, they may have dual or triple purposes, may not operate under very much legitimate government control at all, and may operate specifically for the purposes of the rogue group or groups that have gained control.
>
> "In a nutshell, that's what may be going on in the clandestine mind control projects in several Western governments. The involvement of at least some rogue groups, some being "cowboys" who operate well outside all laws and ethics, could also result in such things as assassinations, clandestine testing on individuals without their consent, etc. In short, it could account for what seems to be actually occurring. As also is "usual" in such a mess, one or more of the rogue groups eventually may become very powerful because their secret weapons are very powerful. They may become confident, thinking they have the "best in the world." They may actually believe they are ahead of the Russians..."
>
> "Remember that, in every large and powerful human organization, the basis for rogue groups is power and secrecy. They are always seeking to increase their power, control, influence, prestige, etc. Nothing else. Patriotism and mission are—to rogue groups—often just idle words. They have their own agendas. And being rogue groups, they may well bring in unethical, immoral tricks: assassination, bribery, entrapment, disinformation, plausible deniability, etc. A certain percentage of a highly secret rogue group will wind up using all these things and more. It's a human characteristic, the old primate dominance game. Only now disguised and hidden under deep classification."
>
> "The Russians, with their additional knowledge of the actual mechanisms in the transforms, will be much more advanced than the West, because their fundamental psychoenergetics science is far more advanced, so long as we continue to use the old U(l) electrodynamics. Further, the Russians have decades of use of longitudinal interferometry beams to reach right through the earth and ocean and produce stringent EM effects at a distance. So they will also be able to do the same things here in "mind control" with LW [longitudinal wave] interferometers, through intervening mass."

> Bearden http://www.cheniere.org/explore%20articles/mind%20control3/p05.htm

Bearden cites two examples where he believes the Russian KGB tested the psychoenergetics capabilities of their scalar interferometers. One was the case of Captain Button in his A-10 "Warthog" aircraft on April 2, 1997.

> "Over Arizona, Captain Button was thrown into a hypnogogic state, and his perceptions instantly altered and controlled. In his instant "dream-waking" state, everything seemed perfectly normal. His sense of direction was altered a bit more than 90 degrees, so he simply corrected and turned and "flew toward the range", actually flying off course by more than 90 degrees and ignoring radio contacts. He flew right on out of Arizona."
>
> "At one point he circled, probably thinking he was over the range, and he probably dropped his ordnance there. Then he "flew on back toward home," as he thought in his waking dream state, until his fuel ran out and he crashed and died in the explosion—dream-thinking until he died that everything was normal. All the while, his sense of the passage of time was altered. To him, in his dream-thinking, dream-acting state, everything was normal and nothing untoward had happened. So the distant KGB transmitters and associated psychoenergetics team controlled him for over an hour. "Indeed, that was the exact purpose of the test: demonstrate control (at a great distance) of a skilled person performing highly skilled tasks."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control3/p06.htm

The paper "Mind Control and EM Wave Polarization Transductions" ends with the most chilling and frightening possibility of all: the psychoenergetic engineering of the human species as a whole.

The Ant World

The Final Race for Direct Mind Control of the Entire Human Species

> "The KGB psychoenergetics weapons scientists—because of their direct measurements and detections (and use) of t-polarized waves and LWs [longitudinal waves] for decades—also understand that Jung's collective unconscious mind (of the entire human species) also has its own time-like operations and correlates, which one measures also when using t-polarization measurements and sorting it all out. The collective unconscious mind operations are buried several levels deeper inside the recursive Whittaker structuring inside the EM fields, waves, and potentials. "The KGB scientists also know that something very like Gaia — a collective unconscious mind for all species on earth — also exists, and they are striving to be able to sort out and measure that one as well. The Gaia operations are buried even deeper in the recursive structuring inside the EM fields, waves, and potentials.""Actually, from day one, the Russian mind control scientists have had their eventual goal set upon this "deeper area of mind and possible mind control" of the entire human species.
>
> "I am convinced that the KGB psychoenergetics scientists understand this deeper area. If they can learn to directly engineer the collective human species unconscious, they can

> then convert the human species easily into a sort of "ant" society, modeled along ideal Communism lines, except of course with an excluded "hierarchy at the top" running everything. The "ant society" — communist style — is still a variation of feudalism (all systems tend to feudalism or some form thereof). "The KGB psychoenergetics weapon scientists are seriously pressing on toward that very goal. In my opinion they are not very far from it right now...
>
> "Some versions of Russian mind control devices were used on Russian soldiers in the Afghan War to condition them for performance of merciless acts." 13
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control3/p07.htm

More about "The Ant World"

Whether it is the Russians planning an "ant world" society or rogue U.S. black-ops groups withholding a great boon from human race, the secrecy on all sides around has allowed largely criminal elements to take over this technology while leaving the civilized elements in the dark. Openness and the spreading of this knowledge among good and decent people is essential, and for that we will have to overcome our frightened denial.

> "Meanwhile, rogue groups amongst Western clandestine mind control researchers will probably arise if they have not already done so. They will likely seek to increase their personal control and further isolate the programs from orthodox government review and from government and legislative control. They may even divert the research into highly illegal and unethical means, because it furthers their own rogue agendas. That is how clandestine U.S. government research can sometimes go sour, unless great care is exercised by the oversight committees in the House and the Senate.
>
> "Sometimes when rogue groups do gain control and total secrecy of a given new technological area, then what appears to be "U.S. government operations" do start to encompass a criminal and unethical operations, hidden usually beneath the deep veil of high classification. Also, if it's "scientific," no one is ever brought to justice, even if the "evil science actions" are uncovered and publicly revealed."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control3/p08.htm

Like the huge energy of the Tesla howitzers, the ability to engineer the mind with longitudinal waveforms is a seeming "magical" thing which can be used for good or ill. Bearden envisions that further developments will allow something like the "downloading" of knowledge via scalar interferometry. Everyone could be highly educated, and quickly and easily.

In the conclusion of the paper "Mind Control and EM Wave Polarization Transductions" Bearden makes a plea to the nations of the world regarding the use of psychoenergetic engineering.

> "Let us hope this great new area, already off to a bad start, can be bridled and steered in the direction helping and healing people, rather than killing or abusing them. The excesses in its bad use are a potent threat to all nations on earth.

> "Yet it can revolutionize medical science, education, communication, and psychology. We foresee the day -- perhaps 30 years hence -- when education will be accomplished by directly loading the software into the mind. Then in three weeks one will "load" a doctorate, say, in physics. In three more weeks on will also load a doctorate in chemistry. Another three weeks, in electrical engineering. Another three weeks, an MD And so on. When that happens then truly everyone on earth can be educated. Freedom from ignorance may well be another great freedom that is legally recognized. There will be no impoverished large groups lacking the education to find decent, productive jobs.
>
> "We urge all nations to use the principles involved: not for human abuse, but for healing, educating, uplifting, and life-expanding of every person on earth. If we do, we shall all have a far brighter future. Then we shall check what has started out to be the Sword of Damocles and turn it into the golden Millennium."
>
> Bearden http://www.cheniere.org/explore%20articles/mind%20control3/p08.htm

(Perhaps after so many frightening topics a slight break is in order here to consider the lighter side of psychoenergetics. For example, what will be the ultimate impact on the entertainment industry?)

The Feelies at Last!

Psychoenergetics will be able to bring about at last, for better or for worse, Aldous Huxley's fanciful idea in his novel "Brave New World," an entertainment format which he called "The Feelies." Those were something you went to, like going to the movies, but you would experience all the actual feelings themselves, as if the depicted events were actually happening to you. Although our "leaders" seem too dim to grasp what is going on in the world of scalar electromagnetics, it should not take some young Hollywood genius too long to understand that The Feelies are now possible, and that the immense megabucks of potential profit more than justify heavy investment in bringing it to market.

One can imagine that first "Feelie" theater, "The Huxley" perhaps, a large comfortable area surrounded by nine giant screens (not just one screen!), which become 3D if you put on your headset. And The Huxley is fitted with the finest sound, and oh, by the way, a modest sized scalar interferometer with computer. And there are one or more new tracks now recorded on the film next to the sound track. These are the digital patterns of thoughts, feelings, and ideas to be fed into the theater's interferometer. And these thoughts and feelings and ideas will be felt by the audience as if they were their own thoughts and ideas. It is an entirely new art form. Psychevision.

As important (and no doubt famous) as the actors would be the "feelers," those from whose minds the feelings were lifted in the original programming of the Feelie tracks. Because, for example, Brad Pitt might be a good and handsome actor, but can he really feel it? Like the dubbing of foreign language films, it might be necessary to dub the "emotional track" using a deeper and more profound person's feelings, thoughts and ideas.

It might even be engineered so that if you sat on one side of the theater you would feel like the hero, and on the other side you would feel exactly like the bad guy! What would that lead to?

We have all cried at a movie some time, most people have, though they might not want to admit it. But this would be deep sobbing and a flood of tears, if the director so desired it. You would feel it at your core. Or, take a big chase scene, you would be terrified. They are breathing down your neck! You would be gripped by panic.

For that matter, the whole genre of Horror-Feelie would be too much for many people to take. Do I really want to feel that an actual vampire is tearing at my throat with his fangs?

A Religious Feelie would make you feel the exaltation of a saint at his prayers, or give you the definite feeling that you are Christ suffering on the cross. All the pain could be there too. The stickiness of the blood. The very feeling itself: "Why hast thou forsaken me?" Who among us could come up that despair for scanning? Had this been developed a bit earlier we might watch a documentary of, say, Mother Theresa, containing her own actual deep sense of compassion, which we would feel arising in us as our own.

Then again, a Psychedelic Feelie could induce an LSD-like state and simply blow the audience's minds.

Even in its simplest most primitive mode, the hypnogogic trance induction with its increased suggestibility, would completely alter the experience of even ordinary current movie going.

6. As it Stands - 2002

"Anyway, it's presently a "Mexican stand-off" with the various parties maneuvering with check and countercheck. That is the real "balance of terror" that is held by such a fragile balance."

"You can see the implications if such weapons fall into the hands of the radical terrorists. Ordinary positive energy EMP shooters can be made fairly readily and cheaply from nearly just Radio Shack parts or surplus parts. It just takes some know-how... When and if the Yakuza [Japanese mafia] gets those (and they will, it's just a question of time), you can begin to appreciate some of the turns this present terrorism and our war on it will take."

Bearden http://www.cheniere.org/correspondence/021702a.htm

The very thought of the building of one of these howitzers by "some lone-nut gunman" from Radio Shack parts makes one realize how serious it is for humanity to face the crisis it has come to.

Once again, as at the dawn of the nuclear era, humanity finds itself at the crossroads of Heaven and Hell. As a species, we must stop and consider. And there is at least one real difference between this visit to the crossroads and the last: this time there is a very real possibility of a true "earthly heaven" on the Heaven side.

The poor nations could come to a good life. Disease could be largely eliminated. Fossil fuel pollution could end. Global warming could be solved, and the weather could be managed in a humane way, bringing water where there is drought, and sunny skies where there is flood. Scalar interferometry would be there to avert any possible hits by asteroids or comets. Mars could be colonized and terraformed. Everyone would be highly educated through psychoenergetic downloading of knowledge. And the wisdom of the wise could be realized directly through scalar connection to their minds and hearts.

These stunning sudden possibilities give me pause to think: if our species has reached this crossroads in such a short span of centuries, then surely other species in this vast universe have passed this way before and long ago. And of those who chose the path to "planetary heaven," what is their life like now? It might be good if some of them were with us now, to guide us through this last struggle over this pesky old good-and-evil problem. It is our last chance to choose the path which benefits the whole species, and not just some elite group or faction.

The Disclosure Project

One person working tirelessly to bring to bring these technologies into the open is Dr. Stephen Greer of the Disclosure Project, which is calling for congressional hearings into the issues of UFOs and the free energy technology that was, perhaps in part, reverse-engineered from them.

> "Once abundant and nearly free energy is available in impoverished areas for agriculture, transportation, construction, manufacturing and electrification, there is no limit to what humanity can achieve. It is ridiculous — obscene even — that mind-boggling poverty and famine exists in the world while we sit on classified technologies that could completely reverse this situation. "So why not release these technologies? Because the social, economic and geo-political order of the world would be greatly altered. Every deep insider with whom I have met has emphasized that this would be the greatest change in known human history. The matter is so highly classified not because it is so silly, but because its implications are so profound and far reaching. By nature, those who control such projects do not like change. And here we are talking about the biggest economic, technological, social and geo-political change in known human history. Hence, the status quo is maintained, even as our civilization hurtles towards oblivion...
>
> "With the types of weapons currently in the covert arsenal — weapons more fearsome even than thermonuclear devices — there is no possibility of a survivable conflict. Yet in the darkness of secrecy, actions have been taken on behalf of every human that may

> endanger our future. Only a full, honest disclosure will correct this situation. It is not possible for me to convey in words the urgency of this."
>
> Dr. Stephen Greer http://www.disclosureproject.org/ES-DisclosureImplications-2.htm

Greer and his team have assembled hundreds of witnesses, many of whom are military or ex-military, who are ready to testify to congressional hearings what they know about the covert black projects which have kept free-energy and antigravity propulsion technology secret from the people.

Greer points out the need to regulate these technologies so they are limited to peaceful uses, but this is of course difficult when the government simply chooses to pretend they do not exist. In the meantime, as the President and the Defense Department continue the charade of war-as-usual, those scalar (longitudinal wave) installations which DO exist continue to fall into ever more sinister hands. And there is no reporter in the press brave enough to ask, "Mr. Secretary of Defense, what steps are you taking to defend our MINDS from attack by the big Russian longitudinal interferometers?"

Longitudinal Interferometers are Proliferating

In a later statement Bearden reveals that in fact the Yakuza [Japanese mafia] has already leased some of the interferometers with a nearly $1 billion "down payment:"

> "After the collapse of the Soviet Union's economy, lots of things got available for lease or purchase that would never have been under the old system. That happened in the resulting economic chaos. The Russian Mafia rose to prominence, as did some wheeling and dealing entrepreneurs who played both ends against the middle.
>
> "In that atmosphere, and in the need for money, the KGB allowed leasing of the earlier longitudinal EM wave interferometers to a consortium of the Yakuza and Aum Shinrikyo. They did this only after they had tested and deployed their great new quantum potential weapons. That class of weapon is the dominant weapon on earth. Five nations now have it: Brazil, Russia (KGB), China, and two nations friendly to the U.S. The deal to lease many of the earlier LWIs [longitudinal wave interferometers] to the Japanese Yakuza and Aum Shinrikyo was consummated at the end of 1989, with a down payment of $900 million in gold bullion as "up front" money. I don't know what the lease per year was and is, but probably something like a billion dollars a year. So the rogue Japanese acquired longitudinal EM weapons and that technical know-how. In fact, the Yakuza is producing certain kinds of those in its own facilities in Japan now."
>
> Bearden http://www.cheniere.org/correspondence/030202a.htm

Personally, I am a little uncomfortable with the knowledge that the Japanese mafia may now be able to insert things into my mind. I'd like to sleep at night knowing that my dreams are my own, such as they may be, and not some weird fantastic visions cooked up by a criminal organization. This is a world emergency.

And in Bearden's analysis, it all comes back to the issue of energy. It is the energy crisis which is now provoking the current "oil wars," since oil production has hit the "Hubbert Peak" and will decline. And the electrical power grids must be replaced with scalar power as fast as possible, for these grids are now totally vulnerable to any possessor of longitudinal interferometers. They can all be wiped out in minutes. By anyone who possesses or controls a Tesla howitzer.

> "Anyway, in my personal view, we should have a national Manhattan Project right now, to develop decentralized electrical power systems taking their energy from the vacuum . . . The MEG is real and so are several other systems invented by private inventors and colleagues. All these efforts should be massively funded and massively and quickly developed. The survival of this nation is going to depend upon it. . . . There are many other facets, but the major point is that our scientific apparatus and the public are still unaware of what a desperate struggle we have entered, since it was thrust upon us. 9-11 was a wake-up call. It was certainly bad enough, and one grieves for those lost American lives. But I fear the worst is yet to come, and it is coming at us like a runaway train hurtling right down the track at us."
>
> Bearden http://www.cheniere.org/correspondence/021702a.htm
>
> "The electromagnetic weapons mentioned by the Secretary of Defense in April 1997 are in terrorist hands also, including the Yakuza and Aum Shinrikyo. That rogue group leased those earlier weapons on site in Russia, from the KGB, at the end of 1989. The SecDef stated that such weapons were being used to initiate earthquakes, initiate volcanoes into eruption, and control and engineer the weather. Quite true. And presently there is a truly massive set of weather engineering operations going on over North America, from that rogue Japanese group manning the weapons in Russia. Some 10 nations of the world now have the type of longitudinal EM wave interferometer weapons (which are what the SecDef was most probably referring to). There are other even more fearsome weapons, possessed by five nations. So a great deal of the state of the world is not covered in the news at all, and will not be . . .
>
> "We have been in an undeclared war of an eerie kind for some decades. That war seems now to have started to heat up also. The destructive capability of some of these weapons is awesome, and far greater than nuclear."
>
> Bearden http://www.cheniere.org/correspondence/021702a.htm
>
> "In that sense, the first phase of WW III is already completed. Now we are only waiting for Phase II.
>
> "It is against that backdrop that I think one must "analyze" such things as how fast we will be replacing the power grid (it's going to go anyway, and catastrophically, the terrorists will see to that). And everything we have is critically dependent upon energy, from the economy to jobs to mobility, to the millions of trucks that transport our goods every day, etc.
>
> "As far as I am concerned, we are already late in declaring a great national emergency in energy, because of the coming destruction of the present energy infrastructure. The

> scientific community should lead, follow, or get out of the way. The emergency is not in seeking "alternative but conventional" systems. It is in developing "energy from the vacuum" on an emergency, crash basis.
>
> "Unfortunately, everywhere I look I just see business as usual. Most Americans (and news media) seem to think, hey, Afghanistan is finished except for a bit of cleanup, and it's just about over).
>
> "It isn't. It has only just begun."
>
> Bearden http://www.cheniere.org/correspondence/021702a.htm

Beyond the Howitzers: Quantum Potential Weapons

Do not use EM propagation through space

As more and more nations acquire the scalar interferometers, Bearden speculates on the next generation of longitudinal weapons called "quantum potential" [QP] weapons.

> "The quantum potential weapons are presently only held by three nations: Russia (in the hands of the KGB, which is now know by its new name), Brazil, and the "friendly little nation." Red China may be working on them, but is just at the beginning...
>
> "The QP weapons have been highly reserved by the Russians. However, the complete extent of their capabilities is still being figured out...
>
> "The quantum potential weaponry (possessed by only three nations) is supreme, because it uses multiply connected spacetime, and DOES NOT involve propagation of EM energy through space as does the longitudinal EM wave interferometers.
>
> Bearden http://www.cheniere.org/misc/qp.htm
>
> "The operational deployment of full-scale strategic QP weapons on site in Russia occurred at the end of 1989, which is when the formal weapons first went operational. These weapons are not in the inventory of the regular Russian armed forces, but all research and development, manufacturing, deployment, an manning and employment is under the ruthless control of the KGB. Shortly thereafter (within weeks), the KGB leased many of their earlier longitudinal EM wave interferometer (LWI) weapons to a rogue Japanese group comprised of the Aum Shinrikyo and Yakuza."
>
> Bearden http://www.cheniere.org/correspondence/021401.htm

In another paper, "Time Polarization - Significance and Weaponization," Bearden tells the story of how a KGB longitudinal wave attack was averted by the longitudinal weapons of a "friendly small nation."

So as it stands, it is precarious. Not until the people demand an end of what author Jim Marrs has dubbed the "Rule by Secrecy," can the people's representatives tackle the big problems of a worldwide ban on Scalar Wars and the shifting over to an essentially oil-free economy.

Latest Update from Tom Bearden - March 2002

The whole situation is changing so fast that when I asked Tom to look over this article he mentioned the seeming contradiction when some of the above statements are taken together. At different times the information he has is updated so one has to keep a kind of running track. He was kind enough to clear up the confusion here with the situation as it stands as of March, 2002.

> "We knew of three nations having the QP weapons for some time. Then we found out last year that five nations had it. So that explains my using the figure "three" first (which represented what I knew at the time). Later I found out about the other two nations. China, e.g., only deployed its QP weapon this past year. So that explains the apparent contradiction between me using "five" in later papers and "three" in earlier ones. It was the best information I had at that time. Might mention that so the reader will understand the apparent discrepancy." Tom Bearden

Emptiness is Full of Energy

"The Tao is an empty vessel;
it is used, but never filled.
Oh, unfathomable source
of ten thousand things!

"Oh, hidden deep but ever present!
I do not know from whence it comes.
It is the forefather of the gods."

Lao Tzu -Tao te Ching

Afterward

Because of the extreme seriousness of the topics brought forward in this article, I asked Tom Bearden to look it over to make sure I had not gotten anything too terribly wrong or mixed up. I did not want to pass on any misunderstanding of my own. I felt a little nervous writing to an eminent scientist, and hoped I had not presumed upon his time.

But Tom was so kind as to answer immediately, and to my relief I had not gotten anything too terribly wrong. Here is his letter, in which he clears up a misunderstanding, and reports on his current health treatment, and gives a call to the young grad students to turn themselves loose in the whole new field of scalar electromagnetics and free energy.

Subject: RE: Article on Tom Bearden and "Scalar Wars"
Date: Fri, 22 Mar 2002 22:54:01 -0600

Bill,

Well, I must say I'm astounded at your persistence and hard work in congealing all that together. My compliments on a hard job quite well done.

Couple tiny things: In the area mentioning Kervran and Kaznacheyev: Kervran was French; Kaznacheyev was and is Russian. Little typo of "spredding" the immune system. Should be "spreading".

We knew of three nations having the QP weapons for some time. Then we found out last year that five nations had it. So that explains my using the figure "three" first (which represented what I knew at the time). Later I found out about the other two nations. China, e.g., only deployed its QP weapon this past year. So that explains the apparent contradiction between me using "five" in later papers and "three" in earlier ones. It was the best information I had at that time. Might mention that so the reader will understand the apparent discrepancy.

Otherwise, it's pretty accurate.

Just now I'm letting the weapons take care of themselves; have to, as I will be recovering now for nearly a year from now after the heart attack last year and discovering that I had contracted mycoplasia (the BW modified kind) in Canada in 1968. Finally got a test which confirmed the chronic mycoplasia (which I had for 33 years!). The stuff burrows inside one's red corpuscles, then draws nutrients from the hemoglobin, hardening it and reducing its ability to take on oxygen (by as much as 50% or more). The resulting symptom is loss of endurance (which I had for that 33 years) -- the so-called "chronic fatigue syndrome".

Many of the Gulf War Veterans who are sick also have it, though they apparently have other complicating factors as well. A very high percentage of persons with chronic fatigue syndrome also have mycoplasia. The treatment for the long-standing mycoplasma infection of that nature is to stay on antibiotics for a year. The only time the mycoplasma is vulnerable is when one wears out a red cell in normal usage, and the body makes a new red cell to replace it. The mycoplasma comes out of the dying cell to infect the new replacement cell, so it is exposed and vulnerable at that specific time and that time only. The antibiotics kills it at that time. Hence the necessity to stay on antibiotics for such a long time so it is continuously in your bloodstream (I've already been on antibiotics for over two months, and have at least 10 more months to go). We also take a little medical oxygen every day.

Another symptom of the mycoplasma infection is the association of runaway fibrillation of the heart. To stop that, there are pills one takes, and they stop it. But they also further reduce the volume of blood pumped by the heart, so that this projects one right back into the hypoxia, dizzy, loss of balance, etc. Catch 22 situation; the fibrillation will build and cause heart attack, stroke, etc. if not stopped, and if stopped it puts you back in the hypoxia which can cause many things! With the conventional treatment, you're damned if you do and damned if you don't. Hence the need for a little extra medical oxygen, so you can take the "heart clamp" pill and stop the fibrillation, but also augment the oxygen enough to continue to survive without a stroke or some such. Interestingly, it's very difficult to even obtain a mycoplasma test, and Medicare fights you tooth and nail over paying for the oxygen. Either they will pay for it or I'll pay for it myself; it is absolutely necessary.

After a heart attack, one is treated in the heart clinic by specialists who are very caring and excellent practitioners, but know nothing of mycoplasma infection, so not consider it even a part of "heart disease", and who are rather puzzled when one has no clogging of the arteries, has the right count of red corpuscles (largely nonfunctional, of course, but there), pumps the right amount of blood, etc. So they identify and treat only the runaway fibrillation, do not prescribe the oxygen -- and essentially place you on a regime as best they know, but one that is guaranteed to kill or maim you or turn you into a totally disabled person or human vegetable via stroke, paralysis, etc. Fortunately my family doctor will prescribe the oxygen anyway, though I may have to pay for it myself. Whatever works!

However, I'm slowly improving little by little, working as much as I'm able to and trying to finish my book: Energy from the Vacuum: Concepts and Principles, and get it to the publisher for publication later this year. Hopefully the book will turn all the interested young grad students and post-docs loose in the free-energy area. They will not have to spend 30 agonizing years to get to where I am, and where a few others are, but can simply start here and go forward. Since speed to develop energy from the vacuum is of the essence because of the world situation, I'm moving on it as fast as I am physically able to.

Meanwhile, working with the AIAS (Alpha Foundation's Institute for Advanced Study), the AIAS (15 authors) has now gotten about 20 scientific papers published in leading journals (Foundations of Physics, Foundations of Physics Letters, Physical Scripta, Optik, etc.) dealing with electromagnetic energy from the vacuum. Several more are either approved for publication or in the review process also. So slowly we are getting it into the mainstream scientific literature. Hopefully it will be in time, but it's cutting it close.

Very best wishes,

Tom Bearden

Late update

Massive display of longitudinal interferometers?

UFO Fleet Taped Over Bedhampton, England

Is this sighting a case of the testing of all the Russian (KGB) longitudinal interferometers at once? And coordinating their targeting through the woodpecker grid to a common place, as an exercise in making a massive scalar attack upon a given region? Was this a confluence of Russian Tesla howitzer marker-beacons?

Bedhampton, England - March 22, 2002 - Video Frames by: Anthony Woods

Certainly for a massive all-out scalar attack you would want coordinated movements of the target areas of many howitzers at once, for you could then just cut a bloody swath across a wide area, all the howitzer blasts marching across the land in a kind of scalar version of the "scorched-earth policy." All in a line, blasting, and heat, and mind waves. Or you might want to put the blasts all in the same place for a truly horrendous destruction. And on top of that biowar on citizens whose immune systems have been weakened with the quantum potential weapons. This is the latest version of Armageddon.

And should any madmen gain control of these weapons, any rogue group at all, and should they have some agenda to radically depopulate the world, to simply kill by the billion, the means will be in their hands to do so.

Update: MEG patent granted

Motionless Electromagnetic Generator Patent Granted

This message is from Jean-Louis Naudin, the French scientist who successfully replicated the Motionless Electromagnetic Generator (MEG) in France. He announces the granting of the patent to the MEG Builder's group at Yahoo.

----- Original Message -----

From: jnaudin509@aol.com
To: jlnlabs@yahoogroups.com
Sent: Tuesday, March 26, 2002 2:20 PM
Subject: [jlnlabs] (Info) GOOD NEWS : The Tom Bearden's MEG IS PATENTED

Dear ALL,

GOOD NEWS !!!!

The Motionless Electromagnetic Generator from Tom Bearden is now PATENTED US 6362718 granted on March 26, 2002

US Patent 6,362,718 :
Motionless Electromagnetic Generator (MEG)

Abstract: An electromagnetic generator without moving parts includes a permanent magnet and a magnetic core including first and second magnetic paths. A first input coil and a first output coil extend around portions of the first magnetic path, while a second input coil and a second output coil extend around portions of the second magnetic path. The input coils are alternatively pulsed to provide induced current pulses in the output coils. Driving electrical current through each of the input coils reduces a level of flux from the permanent magnet within the magnet path around which the input coil extends. In an alternative embodiment of an electromagnetic generator, the magnetic core includes annular spaced-apart plates, with posts and permanent magnets extending in an alternating fashion between the plates. An output coil extends around each of these posts. Input coils extending around portions of the plates are pulsed to cause the induction of current within the output coils.

Inventors: Patrick; Stephen L. (2511 Woodview Dr. SE., Huntsville, AL 35801); Bearden; Thomas E. (2211 Cove Rd., Huntsville, AL 35801); Hayes; James C. (16026 Deaton Dr. SE., Huntsville, AL 35803); Moore; Kenneth D. (1704 Montdale Rd., Huntsville, FL 35801); Kenny; James L. (925 Tascosa Dr., Huntsville, AL 35802)

Appl. No.: 656313
Filed: September 6, 2000

For some technical info see my web site at : http://jnaudin.free.fr/html/meg.htm

Best Regards
Jean-Louis Naudin
Email: JNaudin509@aol.com
Main Web site : http://jlnlabs.org
Site France : http://jlnlabs.multimania.com

Click here to view patent # 6,362,718

Patent Story on Rense.com:

Rense.com

MEG Scalar Energy Device Patented - Production Starts Next Year

From Bill Morgan
wmorgan@nycap.rr.com
3-28-2

Patent was granted on March 26, 2002 for "The Motionless Magnetic Generator," (MEG) US Patent 6,362,718, which is likely to become the first commercially available free energy device in history in about one year from now. The machine will provide free electricity from the vacuum, for the life of the device, which should be a very long life since it has no moving parts. You can see a picture of scientist Jean-Louis Naudin's MEG replication model at: http://jnaudin.free.fr/html/meg.htm.

It has strong magnets, coils, and a controller unit with the electronics. Naudin made the announcement to the MEG-builder's Yahoo group. The announcement has significance since the patent office has always been skeptical of devices which seem to "get-something-for-nothing." But according to the new science of scalar electromagnetics, the MEG does not break the law of conservation of energy. It's just that the energy is conserved in the fourth dimension, time, and not our 3-space world.

The MEG provides electrical energy by tapping the longitudinal electromagnetic (EM) waves which exist in almost infinite abundance in the vacuum of space. This ocean of energy which permeates everything is sometimes called the "zero point" energy, since it remains there even at absolute zero temperature.

Four inventors are listed: Stephen L. Patrick, Thomas E. Bearden, James C. Hayes, Kenneth D. Moore.

Tom Bearden has explained the operation of the MEG on his website Cheniere.org, and also speaks about the new fearful weapons that can and have been made using the same "longitudinal waves" of the vacuum.

The complicated physics of how the MEG works is explained in the paper "The Motionless Electromagnetic Generator: Extracting Energy from a Permanent Magnet with Energy Replenishment from the Active Vacuum," which can be found at Tom Bearden's website:

cheniere.org.(http://www.help4all.de/energy/MEGpaper.pdf)

The first MEG units to be produced for sale will output 2.5 kilowatts of free electricity. Forever. They should be in production about a year from now. Facilities for manufacturing the device are being set up in an unnamed "friendly nation."

This free electricity will flow indefinitely, without much, or any maintenance. The units may be hooked together to provide more wattage, so four of them would provide 10 kilowatts. After some production experience units will be made which output 10 kilowatts each. With a couple of those units a house could get off the electrical grid.

Tom Bearden, one of the inventors has said "I will admit that the chief scientist of an important experimental group in a large company was rather stunned at the type of output we were able to obtain. The MEG may look like just a transformer, but it is not. It is a completely different breed of cat." This cat, it would seem, is out of the bag now.

The ordinary EM waves we are familiar with are called "transverse" waves, to distinguish them from the new "longitudinal" EM waves of the vacuum. Bearden has explained in depth on his website cheniere.org that wherever there is a dipole (battery, generator, magnet) there is an unseen flow of longitudinal EM waves in that local vacuum, the only problem is in tapping that energy and "transducing" it to electricity. Bearden says that the problem with all the electrical circuits we have is that they are two-wire circuits, a loop by which half the energy goes back to destroy the dipole. In the MEG that closed loop is never made. So the dipole is not being destroyed.

Patents are not granted on devices which do not work, so in a sense this announcement proclaims a new era. The MEG device itself proclaims and proves that energy is abundantly available everywhere, for free. We only have to build the devices to tap it. MEG type devices could be put into a car with an electric engine to make a truly fuel-less automobile. Electricity can be available in very remote places. People will be able to get off our very terrorist-vulnerable power grids. In an era of terrorism a highly dispersed power system would be most desirable rather than our centralized systems.

What is somewhat astonishing to me is the discovery by Bearden et. al. that time itself is actually compressed energy, and that this free energy is actually coming from the time domain, the ocean of longitudinal EM waves which fill the empty vacuum of spacetime. In fact, time is energy compressed by the same factor that matter is compressed energy: the speed-of-light squared. Thus there is a new companion to Einstein's E=mc2. Can you say "E equals delta-tee-cee-squared?" The "tee" is time and delta-tee is change in time.

A company has been set up to manufacture the MEG called Magnetic Energy Limited.

The ramifications of free energy are enormous. The oil wars are not necessary. If we threw as much money at this technology as we are spending on the oil wars we would be free of the need for oil in less than a decade. With fuel-less cars air pollution will be greatly lessened. Third world nations can raise their standard of living eventually. And the energy is free. And it never runs out.

I have put together a kind of "Bearden for Beginners" article which explains some of the basic concepts of the current state of scalar technology.

http://www.prahlad.org/pub/bearden/scalar_wars.htm

The granting of the MEG patent is the herald of the new era of scalar electromagnetics, and the free energy which flows forever and never runs out.

Bill Morgan
wmorgan@nycap.rr.com

Do the magnets run down after a while?

Further developments: Tom Bearden clears up a question

When the MEG patent was released many questioned the patent language which seemed to imply that permanent magnets of the MEG would "wear out" after awhile. I myself wondered about the same thing so I put the question to Tom, and here is his reply.

> Dear Bill,
>
> Thanks for the kind words; much appreciated.
>
> I'm not up to going on radio or TV, and won't be for quite some time. Still suffering from hypoxia, though very slowly improving, and will still be on antibiotics for 10 more months at least (maybe longer).
>
> Obviously an extensive dialog developed between the Patent office and our patent attorneys. As best I can understand it, the Patent office accepts the fact that a permanent magnet produces and emits energy, or has a history of accepting it. They do not appear to be at all cognizant of the broken symmetry of opposite charges, and hence of a dipole. So in their opinion (which seems to be vague), the magnet has to use itself up very gradually, or some such. So some rewrites were essentially required by the Patent office.
>
> All I can say is that a magnet is a very durable thing, so long as you don't heat it up too much or shock it to much. Certainly one will make a good 20 years, and of course there are plenty of magnets that have been around awhile longer.
>
> That said, in our earliest experiments we did "measure" some such effect, or so we thought, until we found that a particular instrument was bad and giving erroneous readings. So with a new instrument, we have not observed since then any such readings.
>
> Out of all that fuzziness came the inclusion of "using up the magnets gradually". So far as we are aware (after correcting those early readings on a defective instrument), we have seen no such measurements or effects since then at all. Nonetheless, just in case there is some very small effect in that respect, at least it's in there.
>
> Actually, as you are aware, capacitors and solid state components are the major concerns for failure, and any system does require maintenance, both periodic and whenever malfunction or failure occurs. The MEG is no different from any other device in that respect, so of course it will have a component failure rate and maintenance required from time to time, just as any other electromagnetic device. But without moving parts, it can be ruggedized and made very durable indeed.
>
> Please give Jeff Rense my regrets, and I do admire his work and his show. He's laying it in there.
>
> The depth of the scientific mindset against COP>1.0 is inexplicable, particularly when physics itself already has COP>1.0 validated experiments (such as Bohren's experiment,

which outputs 18 times as much as one inputs by Poynting calculations), and it works every time. Any competent university optics lab can perform the experiment. Also, even the conventional texts admit that a charged capacitor or electret laid on a permanent magnet, so that the E of the cap or electret and the H of the magnet are at right angles, is a "free energy machine". That silly thing will just sit there and pour out Poynting energy S = EXH indefinitely. Years and years and years. If you wait just a single year, that silly thing has changed the energy density of a volume of space a light year in radius, reaching out well beyond the solar system. Now that's a WHALE of a lot of EM energy that beast poured out in that year, and it will still be going strong and pouring it out at a steady rate. The charges and dipoles in original matter in the universe have been pouring out EM energy in that fashion for some 14 billion years, give or take a billion or so. It's also easy to see that, prior to Lorentz's ARBITRARY symmetrical regauging of the Maxwell-Heaviside equations, those equations prescribe both EM systems in equilibrium with their active environment, and EM systems not in equilibrium with it. The latter systems are permitted by the thermodynamics of open disequilibrium systems to perform five magic functions: (1) self-order, (2) self-oscillate or self-rotate, (3) output more energy than the operator inputs (the active environment inputs the rest of it), (4) power itself and its load (the active environment inputs all the energy, like a windmill), and (5) exhibit negentropy. That is a well-established thermodynamics. Lorentz arbitrarily discarded all such open disequilibrium EM systems in order to get simpler equations having analytical solutions and not requiring numerical methods. So he simply scrapped all the really interesting and challenging EM systems in Maxwell's theory. ARBITRARILY!

That our scientific establishment continues to teach only that "half" of the theory, and not point out the rest to the young students, and not fund research into developing such systems that take energy from the vacuum, is simply inexplicable. It's a matter of total dogma, not science at all.

But hopefully it is changing a little bit. At least now we cite chapter and verse when these things were done, and what they are, and the young grad students and post docs can go check the papers and make up their own minds.

That is the real hope of the future: that we get a generation of young fellows, with excellent skills, who now know where all the skeletons got hidden in the closet, and understand that the electrical engineering model arbitrarily assumes an inert vacuum environment (falsified for more than a half century in particle physics) and a local flat spacetime (falsified for nearly a century by general relativity).

Once they know that past history, and go read into what broken symmetry of opposite charges means for a dipole and for all dipolar EM circuits, they will set to and change that more than a century of error. In that case, we shall have numerous solutions to the energy crisis rather quickly, popping up all over.

Good thing. It will certainly displace some great energy barons, but it will also free the populace. One can extract all the EM energy from the vacuum one wishes, anywhere, anytime, with ridiculous ease. One can produce that "electrical wind of energy" at will, by making a simple dipole and then letting it alone. The only energy problem is in how to then intercept some of that energy flow and "catch" it in a circuit, discharge it in a load to power it, and not use half the "caught" energy to kill that dipole that is gushing out the extracted EM energy from the vacuum.

Very best wishes,

Tom Bearden

END

The Tom Bearden Website

Help support the research

Foundations of Electro-Magnetism
Slide Series

- Major Points of Presentation
- Chung's Carbon Filament Negative Resistor
- Aharanov-Bohm Effect
- Absorption and emission reactions (1)
- Absorption and emission reactions (2)
- Anti-engine for cell's deviation reverses cell back to normal
- Asymmetric regauging produces excess force, which can be used to do work on the system
- Asymmetric regauging produces excess force, which can be used to do work on the regauging system
- Becker's bone fracture healing experiments
- Becker's theoretical control system governing regeneration
- Becker's theoretical DC control system involved with response to injury
- Geometrical Distortion of Poynting Energy Flow
- Cosmic Bootstrap: Before the Big Bang
- Bridging Enables COP > 1

- Aspects of Strong Local Symmetry
- Other Aspects of Strong Local Symmetry
- Bunge on the Status of Electrodynamics
- Bunge on the Status of Electrodynamics and Physics
- Bunge on the Status of Classical and Quantum Physics
- Fractions of BW Casualties Surviving
- First Step in Self-Promotion of Cancer Due to Hypoxia
- Differentiation and Dedifferentiation Timelines
- Evolution of Cells on Earth
- A Charged Particle q is a Coupled System of m and Ø
- The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry (1)
- The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry (2)
- The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry (3)
- A Charged Particle is a Coupled System
- The Anomalies in Navy Electrolyte Experiments at China Lake
- Chung's Carbon Filament Negative Resistor

- Typical circuit has about 10^{-13} energy collection efficiency
- Classical View of EM
- Curved Spacetime acts as source or sink
- Chronic Disease Puzzling
- Cancer Characteristics
- Solving a Cancer Enigma
- Cancer: Characteristics
- Nonlinear Optics Distortion Correction Theorem
- The Electronuclear Reaction: Nuclear Reactions in TR-Zones (1)
- The Electronuclear Reaction: Nuclear Reactions in TR-Zones (2)
- The Electronuclear Reaction: Nuclear Reactions in TR-Zones (3)
- In Time-Reversed Zone: Nuclear reactions are biased
- In Time-Reversed Zone: Dynamics may be reversed
- Time-Reversed Zone: Significant only after time-density charging
- A New Conservation of Energy Law
- Questions on Carcinogens and EM

Radiation

- AS DEFINED, fields and potentials only exist in and on charged matter
- Serious flaws and errors in classical EM theory
- Electrodynamicists' Reaction to Removal of the Material Ether
- Reaction to Loss of Material Ether (1)
- Reaction to Loss of Material Ether (2)
- Some EM waves in Spacetime
- Air Medium Disturbances Generated When Air is Perturbed by a Plucked Taut String
- Launching a Spacetime Perturbation ("EM Wave") from a Wire Antenna
- Phase Conjugate Wavepairs Produce New Waves
- Scalar Electromagnetics (Energetics) View of EM (1)
- Scalar Electromagnetics (Energetics) View of EM (2)

- Scalar Electromagnetics (Energetics) View of EM (3)
- Extended General Relativity Principle
- Extension of Work-Energy Theorem
- 34 Flaws in Classical EM Theory
- MTW's General Relativity Principle
- Use of General Relativity (GR) in Particle Physics
- The Missing Infolded Electrodynamics
- Infolded Engines: Excluded by Present Physics
- Mass curves and structures spacetime; ST curvatures change and structure mass (1)
- Mass curves and structures spacetime; ST curvatures change and structure mass (2)
- At Infinite Velocity: Each Is Every Other
- Lisitsyn's Report: Brain Code Broken
- Lorentz Closed Surface Integration
- Lorentz's physically insignificant energy flow can be collected and utilized
- Lorentz surface integration of the Poynting vector around a closed surface
- Longitudinal EM Photon Interaction with Charge
- Mass is transparent to longitudinal EM waves, which move through the infolded interiors of internal waves, potentials, and fields in the mass.

- Pumping with Longitudinal EM waves Time-reverses the Mass
- Maxwell's Quaternion Theory
- Maxwellian Systems before and after Regauging
- Maxwell's four equations reduce to: Page 1
- Maxwell's four equations reduce to: Page 2
- More to come



Major Points of Presentation

- Electrodynamic is seriously flawed
  - Some major flaws
  - Corrections indicated
- Why past corrective attempts failed
  - Force field concept is material
  - Missing two infolded transforms (M->ST; ST->M)
- Missing infolded general relativity inside electrodynamics
- Several Kinds of EM Waves in Space
  - How to make
  - Transduction
- A French medical example as a deep experimental demonstration
  - Spectacular regenerative cures funded by French Govt
  - Not comprehended, therefore suppressed
- Cold Fusion examples of time-density wave effects
  - China Lake instrumental anomalies in electrolysis
  - Explanation of anomalous behavior of instruments
  - Explanation of new nuclear reactions
  - Wave energy transduction provides excess heat
- Urge theorists to consider dramatically new reactions



Chung's Carbon Filament Negative Resistor

UNIVERSITY AT BUFFALO, NY

Win
CROSSED CARBON FILAMENT LAYERS
Wout > Win

© 1998 T.E. Bearden



Aharonov-Bohm Effect

© T.E. BEARDEN 1996

- In field-free regions
  - E-field is zero
  - B-field is zero
- Potentials still exist, just no gradients
  - Cause real effects
  - Interference is the key
  - Contain sum-zeroed substructures
- Does not follow from
  - Mechanics
  - Classical electromagnetics
- Required by quantum mechanics



Absorption and emission reactions

ELECTRON ABSORBS PHOTON ENERGY, MOVES TO HIGHER ENERGY LEVEL. DECAYS BY EMITTING PHOTON

ELECTRON ABSORBS TIME DENSITY, MOVES TO DIFFERENT TIME DENSITY LEVEL. DECAYS BY EMITTING LONGITUDINAL OR PSEUDOLONGITUDINAL PHOTON

© T.E. BEARDEN 1998

PARTICLE ABSORBS ENERGY, MOVES TO HIGHER ENERGY SHELL. DECAYS BY EMITTING ENERGETIC PARTICLE. OBSERVABLE..

PARTICLE ABSORBS TIME, MOVES TO HIGHER TIME DENSITY. DECAYS BY EMITTING TIME-LIKE PARTICLE, NONOBSERVABLE BY PRESENT MEANS.

ENTIRE NUCLEUS ABSORBS ENERGY, EACH PARTICLE ABSORBS OWN. DECAY OCCURS BY COMPLEX MODES, INCLUDING FISSION OR FUSION. DECAY BYPRODUCTS OBSERVABLE.

ENTIRE NUCLEUS ABSORBS TIME, EACH PARTICLE ABSORBS OWN. DECAY OCCURS BY COMPLEX MODES, INCLUDING FISSION OR FUSION. SOME DECAY BYPRODUCTS ARE NONOBSERVABLE (SPACE ABSORBS)



Absorption and emission reactions

TRANSVERSE PHOTON

ELECTRON ABSORBS PHOTON ENERGY, MOVES TO HIGHER ENERGY LEVEL. DECAYS BY EMITTING PHOTON, REMOVING Δt

ΔE
nucleus
Δt coupled and emitted quickly

STREAM OF TIME-POLARIZED PHOTONS

ELECTRON ABSORBS TIME DENSITY, MOVES TO $1/c_2$ DIFFERENT TIME DENSITY LEVEL. DECAYS BY EMITTING LONGITUDINAL OR PSEUDOLONGITUDINAL PHOTONS

Δt
nucleus
Δt increases quasi-statically then slowly decays

Figure A. Excited energy density level in one jump.

Figure B. Excited time density level significant only after enormous number of increases.

© T.E.BEARDEN 1998



ANTI-ENGINE FOR CELL'S DEVIATION REVERSES CELL BACK TO NORMAL

PHYSICAL
CELL
(DISEASED)
+
EXTENDED
TIME DELAY FOR
RENORMALIZATION
PHYSICAL
CELL
(NORMAL)
VACUUM
ENGINE
FOR DISEASED
CELL
VACUUM/SPACETIME
ANTI-ENGINE FOR
CELL'S DISEASE DELTA

© 1994, 1995 T.E. BEARDEN

By pumping the internal EM channel, process is dramatically accelerated.
This is the body's normal recovery mechanism, within its limits.



Asymmetric Regauging Produces Excess Force, Which Can be Used to Do Work on the System

Net Symmetric Regauging Does No Excess Work on the System

This little bird put one foot on wire A, and then the second foot on wire A also. He *net symmetrically* regauged, so he had no net excess force across him, even though his potential energy was increased. He asymmetrically regauged each foot, but both simultaneously so that one countered the other. Wise little bird!

Net Asymmetric Regauging *Can* Do Excess Work on the System

This little bird put one foot on wire A, and then the second foot on wire B. He *net asymmetrically* regauged, so he had lots of net excess force across him. That force then violently translated his little body parts every which way, doing lots of work in and on him. Bummer!

© T.E. BEARDEN 1999



Net Symmetric Regauging Does No Excess Work on the System

This little bird put one foot on wire A, and then the second foot on wire A also. He *net symmetrically* regauged, so he had no net excess force across him, even though his potential energy was increased. He asymmetrically regauged each foot, but both simultaneously so that one countered the other. Wise little bird!

Net Asymmetric Regauging Can Do Excess Work on the System

This little bird put one foot on wire A, and then the second foot on wire B. He *net asymmetrically* regauged, so he had lots of net excess force across him. That force then violently translated his little body parts every which way, doing lots of work in and on him. Bummer!

© T.E. BEARDEN 1996

Figure 32. Asymmetric regauging produces excess force, which can be used to do work on the regauging system.

Selected clipart © by Lotus SmartPics™



Becker's bone fracture healing experiments

- Tiny DC currents (picoamperes)
- Pulsed DC current can be utilized
- Pulsed magnetic fields may be utilized

(+)
ELECTRODE
(-)
DC POWER SOURCE
ELECTRODE
BONE
BONE
FRACTURE SITE

RED BLOOD CELL DEDIFFERENTIATES

Shucks hemoglobin coat
Grows nucleus

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes cartilage

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes bone
Deposits in fracture site, healing the fracture

© 1993, 1995 T.E. BEARDEN



Becker's theoretical control system governing regeneration*

Trauma Producing Tissue Loss

Local cellular effect

Local nerve effect

CNS effect

Alterations in hormone pattern (prolactin)

Alterations in local DC field pattern

Local electrical effects

Local and systemic pools of target cells

Dedifferentiation into primitive mesenchymal cells

Phase I

Blastema formation

growth

Phase II

Redifferentiation into required cell types

Restoration of body part or tissue

*Becker & Spadaro, "Electrical stimulation of partial limb regeneration in mammals," Bul. N.Y. Acad. Med., 48(4), May 1972, p. 629.

Becker's theoretical DC control system involved with response to injury*



INJURY

INPUT STIMULATION DC SYSTEM (PAIN)

CENTRAL DC SYSTEM

GROWTH DIFFERENTIATION

LOCAL CELL INJURY FREE RADICALS

OUTPUT DC SYSTEM

TOTAL CURRENT OF INJURY DC SYSTEM

MITOSIS DEDIFFERENTIATION

STIMULATION OF REPAIR CELLS

*Robert O. Becker, "The significance of bioelectrical potentials," Bioelectrochemistry and Bioenergetics, Vol. 1, 1974, p. 191.



Geometrical Distortion of Poynting Energy Flow

At or near resonance frequency, in the case shown the energy collection fraction (reaction cross section) increases dramatically.

a. Around an aluminum sphere at light energy 8.8 eV. Absorption efficiency = 18.00.

b. Around an aluminum sphere at light energy 5eV. Absorption efficiency = 0.1.

Figures per Craig F. Bohren, "How can a particle absorb more than the light incident upon it? ", American Journal of Physics, 51(4), Apr. 1983, p. 326.



Cosmic Bootstrap: Before the Big Bang:

- *Cosmic repulsion behaved like a fluid with negative pressure*
- *The "universe" inflated (expanded) as a "false vacuum"*
- *As the negative-pressure fluid expanded, its energy went up rather than down*
- *When inflation stopped, the false vacuum decayed from its excited state*
- *Its excitation energy was released in a single great burst*

Paul Davies, Superforce, 1984, p. 194



BRIDGING ENABLES COP > 1.0

S-flow, dϕ /dt flow, and EMF flow
V>>0
source
i ≈ 0
dQ/dt
BLOCKER
(Conductor)
V>>0
i>>0
LOAD
Closed Current
Loop A
Closed Current
Loop B
BRIDGE
Patent Pending

Current loop B is asymmetrically regauged by S, dϕ /dt, and EMF flow from current loop A.

© 1998 T.E. BEARDEN



Aspects of Strong Local Asymmetry

- If local asymmetry is strong, conservation laws may be appreciably violated
  - Energy
  - Charge
  - Spin
  - Momentum
  - Angular momentum

© T. E. Bearden 1995, 1996

- Properties of an object may differ appreciably for
  - Different observers
  - Different detecting means
  - One time to another
  - One position to another
- STRUCTURING THE INFOLDED EM INSIDE POTENTIALS, FIELDS, AND WAVES
  - Strongly breaks local symmetry
  - Provides spacetime engines giving the above effects



Other Aspects of Strong Local Asymmetry

© T. E. Bearden 1995, 1996

- Local spacetime is curved
- Lorentz invariance of vacuum is violated
- May be a local "sink" or "source"
- Gravitational-inertial effects from EM
- Translation between virtual and observable
- Electrogravitational solitons
- Action at a distance
- Transmutation effects may exist
- Scalar/pseudoscalar field translation
- COMMENT: Thus the use of infolded longitudinal EM fields and waves to strongly break local symmetry allows internested clustering of spacetime curvatures. These spacetime structures are *vacuum engines*, or *spacetime engines*.



Bunge on the Status of Electrodynamics

"... it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state..."

"... the best modern physicist is the one who acknowledges that neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling..."

*Mario Bunge, Foundations of Physics, Springer-Verlag, New York, NY, 1967, p. 176..

© 1996 T.E. BEARDEN



Bunge on the Status of Electrodynamics and Physics

"... it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state...

"... neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling..."

© 1996 T.E. BEARDEN

*Mario Bunge, Foundations of Physics, Springer-Verlag, New York, NY, 1967, p. 176..



Bunge on the Status of Classical and Quantum Physics

"... it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state... the best modern physicist is the one who acknowledges that neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling not only to better cover their own domains but also to join smoothly so as to produce a coherent picture of the various levels of physical reality."

"Mario Bunge, Foundations of Physics, Springer-Verlag, New York, NY, 1967, p. 176..

© 1996 T.E. BEARDEN


Fraction of Casualties Surviving
FRACTION SURVIVING
N = 1 - 40 million
1.0
0.8
0.6
0.4
0.2
0.0
N CASUALTIES
0.1
0.7
0.9
0.95
CASUALTIES
TYPE TREATMENT RECEIVED
© 1998 T. E. BEARDEN
EXPRESSED IN FRACTION SURVIVING
With conventional treatment
With 1st generation P-treatment
With 2nd generation P-treatment
With 3rd generation P-treatment



FIRST STEP IN SELF-PROMOTION OF CANCER DUE TO HYPOXIA

MULTICELL
AEROBIC*
(INCLUDES MAN)

SINGLE CELL
ANAEROBIC

SINGLE CELL
AEROBIC*

CENTRAL CONTROL

OXYGEN-RICH

TIME-FORWARD
PATH AS IT
DEVELOPED

CANCER CELL

PARTIALLY
ANAEROBIC

SINGLE CELL
AEROBIC

TIME-REVERSED
PATH FOR SUSTAINED
OXYGEN DEFICIENCY

FIRST STEP IN OXYGEN-DEFICIENCY
DEDIFFERENTIATION

© 1993 T.E. Bearden



Differentiation and Dedifferentiation Timelines

CENTRALIZED CONTROL OF CELLULAR GROWTH AND REGENERATION

PRIMORDIAL
SINGLE
CELL
ANAEROBIC

SINGLE
CELL
AEROBIC

OXYGEN-RICH ENVIRONMENT

NORMAL HEALTHY
CELLS AND FUNCTIONS

WITH SOME DISEASED
OR DAMAGED CELLS

TIME-FORWARD PATH
AS IT DEVELOPED

© 1993, 1998 T.E. Bearden

NORMAL "DEDIFFERENTIATION"
FOR HEALING OF CELL DAMAGE

SINGLE CELL
MORE
ANAEROBIC

SINGLE
CELL
AEROBIC

TIME-REVERSED
PATH FOR
SUSTAINED
OXYGEN
DEFICIENCY

TIME-REVERSED
PATH WHEN NORMAL
PUMPING FAILS TO
HEAL CELL



Evolution of Cells on Earth

ESSENTIALLY ANAEROBIC ATMOSPHERE

CHANGE OF ATMOSPHERE TO AEROBIC (INCLUDES OXYGEN)

BIOGENESIS

SINGLE CELL ANAEROBIC

OBLIGATORY ANAEROBES SINGLE CELL SHIELDED FROM OXYGEN

FACULTATIVE ANAEROBES (SINGLE CELL BOTH AEROBIC AND ANAEROBIC)

EVOLVE TO

SINGLE CELL AEROBIC*

EVOLVE TO MULTICELL AEROBIC* (INCLUDES MAN)

CENTRAL CONTROL

SINGLE CELL COMPONENTS

- IMMUNE SYSTEM
- RED CELLS
- WHITE CELLS
- KILLER CELLS
- ETC.

MULTICELL COMPONENTS

- TISSUES
- MUSCLES
- BONES
- ORGANS
- SKIN
- STRUCTURES

* NOTE: LIMITED ANAEROBIC RESPIRATION STILL TAKES PLACE IN HIGHER AEROBIC LIFE FORMS, INCLUDING MAN.

EVOLUTIONARY TIME

© 1998 T. E. BEARDEN



A Charged Particle q Is a Coupled System of m and ϕ

(A proposed formal definition
of a charged mass)

Note: X is a coupling operator

$$q \equiv f_q \times m_q$$

Also note that the ϕ portion of the charged particle can be internally structured, per Stoney-Whittaker-Ziolkowski, with hidden bidirectional EM wavepairs (their sums and products). Note that this constitutes an EM application of Bohm-type hidden variable theory, with many ramifications.

"...curiously enough, we do not know exactly what charge is, only what it does. Or, equally significantly, what it does not do."

M.P. Silverman, And Yet It Moves: Strange Systems and Subtle Questions in Physics, Cambridge University Press, 1993, p. 127.

© T.E. BEARDEN 1997

An electric charge Q consists of a massless flux component and a mass component, coupled together (interacting). Q is a broken symmetry. The mass of the charge continually and violently exchanges virtual photons with the surrounding vacuum.



Thus Q is energetically driven by the surrounding vacuum potential, which itself is to first order just a violent virtual photon flux.



The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry

You really need
a Maxwell's demon,
to do some free work.

Your electrodynamicist
says he can make one,
by regauging.

© T.E. BEARDEN 1999



The Ubiquitous Assumption: *Two* Asymmetrical Regaugings for Net Symmetry

He says he will do the regauging for you. Hey, what a swell guy!

He regauges *twice*, and makes two Maxwell's demons equal and opposite. They won't do any net work for you!

© T.E. BEARDEN 1999



The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry

He disdainfully says,
"We *always* do it that way!
We *must* enforce local
equilibrium and the second
law of thermodynamics!".

You decide to have a
little chat with your
electrodynamicist!
With friends like that,
who needs enemies!

© T.E. BEARDEN 1999



A Charged Particle Is a Coupled System

(The first formal definition of charge) $\boxed{q \equiv \phi_q \text{ x } m_q}$

Note: X is a coupling operator

© 1994 T.E BEARDEN

"...curiously enough, we do not know exactly what charge is, only what it does. Or, equally significantly, what it does not do."

M.P. Silverman, And Yet It Moves: Strange Systems and Subtle Questions in Physics, Cambridge University Press, 1993, p. 127.

An electric charge q is a broken symmetry in its fierce energy exchange with the active vacuum. It coherently integrates some of the virtual energy absorbs and outputs it as Poynting energy flow.



Chung's Carbon Filament Negative Resistor

UNIVERSITY AT BUFFALO, NY
© 1996 T.E. Bearden
Win
Wout > Win
CROSSED CARBON
FILAMENT LAYERS



Typical circuit has about 10$_{-13}$ energy collection efficiency

Earth
S
edge of solar system
Deep space
© 1994, 1995 T.E. BEARDEN
i
d

Distance traveled by S in one hour is 1.08x10exp(12) meters.

Example: 1.3 amps flowing in DC circuit, 1.8 mm diameter copper wire. J = 51 A/cm ^{2}

d_i = 0.1368 meters

S violently transports ϕ provided from the source.
jϕ sluggishly transports the energy collected and dissipated in the circuit..

For the case discussed, the electron drift velocity in the circuit is about 3.8 x 10^{-5} meters/sec. So Jϕ moves about 0.1368 meters in one hour. Thus Jϕ has collected about 0.1368 meters of the ϕ-filled S-tube. During that same hour, the S-flow evoked by the power source will have traveled 1.08x10^{12} meters. The ϕ of both currents is the same. Both are involved in the same energy-filled tube. Thus S has provided and transported about 7.89x10^{12} times as much energy along the circuit in one hour as the jϕ has been able to collect, transport, and dissipate as work in the circuit. Thus this circuit provides about 10^{13} collection efficiency.



Classical View of EM

- Potentials just mathematical conveniences
  - Not real
  - No internal structure, just magnitude
- Force fields primary, causative, can exist in space in absence of observable mass
  - All EM actions due to force fields, none when zero
  - No action at a distance
- Vacuum empty; without energy or structure
  - No locally curved spacetime
  - No gravity effects
  - No quantum effects
- Maxwell's equations complete
  - Symmetrically regauged ***arbitrarily***
  - Topology dramatically reduced



Curved Spacetime acts as source or sink

- May emit excess radiation and energy (e.g., heat)
- May absorb radiation and energy (e.g., cool)
- May transduce waves
  TW ⇔ LW ⇔ TDW
- New energy conservation law applies

© 1998 T.E.BEARDEN



CHRONIC DISEASE PUZZLING

- SCIENCE REALLY DOES NOT UNDERSTAND THE MECHANISMS OF A SINGLE CHRONIC DISEASE, INCLUDING CANCER
- MANY TROUBLING FACTORS EXIST
  - *MIND*
  - *STRESS*
  - *SPONTANEOUS REMISSION*
  - *PLACEBO EFFECTS*
  - *COMBINATIONS*
- GENERATION OF THE PLACEBO EFFECT BY THE CELLULAR REGENERATION SYSTEM IS UNRECOGNIZED

© 1994, 1995 T.E. Bearden



Cancer Characteristics

- Not one disease, but a whole range
- Starts in damaged aerobic cell
- Cell shakes off body's central control
  - Starts uncontrolled division
  - Becomes a lump
- Can send forth cancer cells
  - Through blood
  - Through lymph
- Form metastases (secondary tumors)
- Often become anaerobic

© 1993 T.E. Bearden



Solving a Cancer Enigma

- An enigma has been failure of immune system to attack some tumor cells
  - Suppressor cells may curb immune system?
  - Tumor may lack antigens normally identified by the immune system?
- *Promotion of damaged cell to cancer is usually ordered by cellular control system*
  - *Regenerative and recovery system forces cell back toward anaerobe*
  - *First step breaks free from central growth*
  - *Control continues to recognize cell as self*

© [illegible] T.E. Bearden



CANCER: CHARACTERISTICS

- NOT ONE DISEASE BUT A WHOLE RANGE
- STARTS IN ORDINARY (AEROBIC) CELL
- CELL SHAKES OFF BODY'S DICTATORIAL CONTROL*
- STARTS UNCONTROLLED DIVISION
- BECOMES A LUMP
- CAN SEND FORTH CANCER CELLS
  - THROUGH BLOOD
  - THROUGH LYMPH
- THESE FORM METASTASES (SECONDARY TUMORS)
- OFTEN BECOME ANAEROBIC (NON-OXYGEN USING)
- ENIGMA IS FAILURE OF IMMUNE SYSTEM TO ATTACK SOME TUMOR CELLS
  - SUPPRESSOR CELLS MAY CURB IMMUNE SYSTEM
  - TUMOR MAY LACK ANTIGENS NORMALLY IDENTIFIED BY THE IMMUNE SYSTEM

*R&R system forces cell back toward anaerobe

© 1993 T.E. Bearden



Nonlinear Optics
Distortion Correction Theorem

E_1 = INCIDENT WAVE
E_2 = TIME-REVERSED WAVE

© 1994, 1995, 1998 T.E BEARDEN

"If a scalar wave $E_1(r)$ propagates from left to right through an arbitrary but lossless dielectric medium, and if we generate in some region of space [say near z = 0] its phase conjugate replica $E_2(r)$, then E_2 will propagate backward from right to left through the dielectric medium, remaining everywhere the phase conjugate of E_1."



The Electronuclear Reaction: Nuclear Reactions in TR-Zones (1)

- Nucleon interchange
  - Changes neutron into proton and vice versa
  - At high rate (flat spacetime assumed)
- Statistics become skewed due to curved ST
- Can bias statistics toward either neutron or proton end
  - Biases toward transmutation of elements along isomer chains
  - Concept of "isomer" is vastly expanded



The Electronuclear Reaction: Nuclear Reactions in TR-Zones (2)

- Normal dynamics (impulses) may reverse
  - *Like charges attract, unlike charges repel*
  - *Positive charges cluster (are drawn together)*
  - *H+ ions (protons) may form quasi-nuclei*
  - *Nucleus coulomb barrier becomes assistant*
- Many "impossible" reactions now possible
  - *Quark access and quark flipping by EM*
  - *Ion clustering*
  - *Positive charges as phase conjugate mirrors*
  - *Time-density waves and time-energy charging*

© 1996 T. E. Bearden



The Electronuclear Reaction: Nuclear Reactions in TR-Zones (3)

- **Not observed until time-energy charging has become substantial**
  - *Time delay (hours, days)*
  - *Transduction of LW --> TW involved*
  - *Specific time-charging history of detectors is involved in twhether they detect or not*
  - *Longitudinal EM waves become significant*
- **Curved spacetime can act as source or sink**
  - *May emit excess radiation*
  - *May absorb excess radiation*



In Time-Reversed Zone: Nuclear reactions are biased

- In normal flat ST, $n \Leftrightarrow p$ at high rate
- Curved ST skews statistics
- Biases to either n or p
- Biases to transmutation along isomer chain
- "Isomer" concept greatly expanded

© 1998 T.E.BEARDEN



In Time-Reversed Zone:
Dynamics may be reversed

- Like charges may attract and unlike charges repel
- Coulomb barrier becomes Coulomb assistant
- Clusters like charges and forms artificial nuclei
- "Impossible" nuclear reactions at low energy
- Time-density interactions



Time-Reversed Zone:

Significant only after time-density charging

- Hours, for "fast" onset
- Days, for "slower" onset
- Transduction involved for TW ⇔ LW ⇔ TDW
- Time-history of each detector is significant
- Longitudinal EM waves become significant



A New Conservation of Energy Law

- Physics conserves total "energy and mass-energy"
- Now also must consider "time-energy"
- Conserve total mass-time-energy (spatiotemporal energy)
- Let E_T = total energy, E_M = mass energy, E_E = ordinary energy, and E_t = time energy. Then

$$E_T = E_E + E_M + E_t$$

© 1998 T.E. Bearden

$$(kE_t \Rightarrow E_E > 0) \quad \Rightarrow \quad E_T > (E_M + E_E)$$

- If some E_t is transduced into E_E , the experiment will violate the old spatial mass-energy conservation law



QUESTIONS ON CARCINOGENS AND EM RADIATION

- UNRESOLVED QUESTIONS ON EM RADIATION
  - DOSAGES
  - ACTIVE MECHANISMS
  - REPLICATION DIFFICULTIES
  - MEASUREMENT DIFFICULTIES
  - WHERE, WHEN, HOW ILL EFFECTS OCCUR
- SIMILAR QUESTIONS EXIST ABOUT EVERY CARCINOGEN
- SCIENCE REALLY DOES NOT UNDERSTAND THE MECHANISMS OF A SINGLE CHRONIC DISEASE, INCLUDING CANCER
  - FACTORS SUCH AS MIND, STRESS, SPONTANEOUS REMISSION, PLACEBO EFFECTS, AND COMBINATIONS OF FACTORS ARE PARTICULARLY TROUBLESOME
  - GENERATION OF THE PLACEBO EFFECT BY THE REGENERATION & RECOVERY SYSTEM IS UNRECOGNIZED

© 1994, 1995 T.E. Bearden

As defined, fields and potentials only exist in and on charged matter



$E \equiv F/q$

$S = E \times H$

Note problem:
No "E" or "H" in vacuum.

Source q is a broken symmetry in vacuum flux

$S = E \times H$

SOURCE CHARGE

Assumed perpetual motion machine in classical EM

"pileup" in front
So $E \equiv -\nabla\phi$

Point coulomb

ϕ ≡ joules continuously in geometrical flow distortion zone around a point coulomb

Electrodynamics has nothing to say about what exists in space in the absence of mass.

© 1997 T.E. BEARDEN



Serious flaws and errors in classical EM theory.

1. Eliminates the Internal EM Inside the Scalar Potential.
2. No Definition of Electrical Charge or of Scalar Potential.
3. Equations Still Assume Material Ether Per Maxwell (Unchanged).
4. Use of Force Fields in Vacuum is False (and Known to be So).
5. Treats Charge q as Unitary Instead of Coupled System $q = \phi[q]m(q)$.
6. Confuses Massless Potential Gradients as Forces (See #3, #4).
7. Does Not Utilize Mass as a Component of Force (See #23).

---

8. Erroneously Assumes EM Force Fields as Primary Causes.
9. Topology of EM Model Has Been Substantially Reduced.
10. Does Not Include Quantum Potential or Action at a Distance.
11. Does Not Include Superluminal Velocity of Inner EM Components.
12. Does Not Utilize Extended Near-Field Coulomb Gauge Effects.
13. Does Not Include EM Generatrix Mechanism for Time Flow.
14. Does Not Unify Photon and Wave Aspects (Requires 7-D Model).

---

15. Does Not Include Electron Spin and Precession (See #19, #24).
16. Treats EM Energy As Existing In "Chunks," Instead of as Flow.
17. Confuses Energy and Energy Collection (See #16).
18. Discards Half of Every EM Wave in Vacuum (See #22).
19. Erroneously Uses Transverse Vacuum Wave; It's Longitudinal.
20. Arbitrarily Regauges Maxwell's Equations to Eliminate Overunity.
21. Omits Phase Conjugate Optics Effects (The *Rule* in Internal EM).
22. Does Not Include EM Cause of Newtonian Reaction Force.
23. Erroneously Assumes Separate Force Acting on Separate Mass.
24. Confuses Detected Electron Precession Waves as Proving Transverse EM Waves in Vacuum (Remnant of Old "EM Fluid" Concept).
25. Due to Error in String Wave, Omits the Ubiquitous Antiwave.
26. *Assumes* Equilibrium; Not True Unless Include Vacuum Interactions.
27. Higher Topology Required, to Model Electromagnetic Reality.
28. Lorentz surface integration discards Poynting energy transport.
29. Has nothing at all to say about form of EM entities in massless space.
30. Eliminates the infolded general relativity using EM-force as curve agent.
31. Does not include longitudinal EM waves as time domain oscillations.
32. Does not include EM mechanism that generates time flow and flow rate.

© T.E. BEARDEN 1991, 1997



NONMATERIAL SPACETIME

© T.E. BEARDEN 1998

Material Electric Fluid Disturbed

MAXWELL

Material Fluid Perturbation Equations

MAXWELL

Material Electric Fluid Disturbed

Michelson-Morley experiments, 1880's
Einstein's spacetime hasn't been born yet!
Our material ether is gone, so only inert space is left!
1880s
Φ, H
Now we are not using a material ether. Trust us! The equations do not need changing.
ELECTRODYNAMICISTS
???

Electrodynamicists' Reaction to Removal of the Material Ether



REACTION TO LOSS OF MATERIAL ETHER

Material Ether
Assumed in
Equations

Potentials,
Fields, and
Waves
Assumed
Material

Not a single
equation was
changed!

Now we are not using
a material ether.
Trust us! The equations
do not need changing.

ELECTRODYNAMICISTS

© T.E. BEARDEN 1999


NONMATERIAL SPACETIME
MASSLESS SPACETIME PERTURBATIONS NOT ADDRESSED
Einstein's spacetime hasn't been born yet!
1888
~~MAXWELL~~
~~Falsely Assumed Matter-in-Space Perturbations~~
~~MAXWELL~~
H
ϕ
Material Electric Fluid Disturbed
CAUSE
Material Electric Fluid Disturbed
EFFECT
???
Okay! We will just measure material entities, and call them nonmaterial.
ELECTRODYNAMICISTS
© T.E. BEARDEN 1998



Some EM Waves in Spacetime

SPACE | **TIME**

GALLOPING WAVE. TRANSVERSE WAVE THAT VARIES VELOCITY ALONG Z-DIRECTION, IN WAVE FASHION. (Ex: 0.01 c - 100 c)

TIME-POLARIZED (TIME-ENERGY) OSCILLATIONS

- SCALAR WAVES. X, Y, Z FIXED. T VARIES. NONOBSERVABLE.
- TIME DENSITY OSCILLATIONS. X, Y, Z ENERGY DENSITY DO NOT VARY.. TIME DENSITY VARIES ALONG TIME DENSITY NOTOBSERVABLE, BUT TRANSDUCTION IS OBSERVABLE.
- TIME DENSITY OSCILLATIONS. X, Y, Z ENERGY DENSITY FIXED. TIME DENSITY IS NONOBSERVABLE, BUT TRANSDUCTION IS OBSERVABLE.

3-SPATIAL ENERGY DENSITY OSCILLATIONS

- TRANSVERSE WAVES. X AND Y ENERGY DENSITY VARIES; Z FIXED.
- PSEUDO-LONGITUDINAL WAVES. X AND Y VARY A LITTLE, SURGE OSCILLATIONS IN Z DIRECTION.
- LONGITUDINAL WAVES. X AND Y FIXED; SURGE OSCILLATIONS IN Z DIRECTION.

TRANSDUCTION ◄——►

◄—— TRANSDUCTION ——►

© T.E. BEARDEN 1998



Air Medium Disturbances Generated When Air is Perturbed by a Plucked Taut String

The string wave and the holder wave never leave the string and holder respectively.

Wave is alternatively compressive and rarefactive

String slaps air medium

WAVE IN STRING (TRANSVERSE)
Lower degree of freedom for string.
Can only vibrate mostly laterally.

Drude Electron Gas waves

Nuclear proton waves

ANTIWAVE IN HOLDER
(Highly damped; not shown to scale)

Body slaps air medium

© 1993, 1995 T. E. BEARDEN



Launching a Spacetime Perturbation ("EM Wave") from a Wire Antenna

ANTENNA
ELECTRON SHELLS (DAMPED)
NUCLEI (HIGHLY DAMPED)
VACUUM
GRAVITON
time forward slap (electron)
time reversed slap (proton)

Modulations of virtual photon flux intensity of the QM vacuum

By omitting the nuclei perturbation wave, Maxwell omitted Newton's third law from electrodynamics

© T.E. BEARDEN 1994, 1995



Phase Conjugate Wavepairs Produce New Waves

TRANSVERSE EM WAVE PLUS
PHASE CONJUGATE REPLICA WAVE

LONGITUDINAL EM SURGE WAVE

LONGITUDINAL EM WAVE PLUS
PHASE CONJUGATE REPLICA WAVE

$(\dot{t})$

TIME DENSITY WAVE

Oscillates rate of flow of time about some average value

© T.E. BEARDEN 1994, 1995



Scalar Electromagnetics (Energetics) View of EM

- Potentials real; primary causes of EM phenomena
  - Force fields made by differentiations of potentials
  - Force fields are effects, not primary causes
  - Force fields exist only in, on mass particles
- Actions due to potentials and their interference
  - Action at a distance or locally
  - Quantum potential and hidden variables
- Locally curved spacetime, engineerable by EM
  - Gravity effects not necessarily negligible
  - Strong EM force or time used as agent of curvature



Scalar Electromagnetics (Energetics) View of EM (Cont'd)

- Potentials have internal structure
  - Stoney/Whittaker structure
  - Longitudinal EM phase conjugate wavepairs
  - Each wavepair is a time-polarized EM wave
- Vacuum EM is a potential and has microstructure
  - Stoney-Whittaker biwaves/t-polarized waves
  - Fluctuations exhibit chaos
- Spacetime ≡ Vacuum ≡ Potential ≡ Flux

© T.E. BEARDEN [illegible]



Scalar Electromagnetics (Energetics) View of EM (Cont'd)

- Statistics may have hidden order (already chaotic)
- Uses spacetime curvature engines to alter matter (inside-out or outside-in)
- Engineerable EM mechanism generates rate of flow of a mass through time
- Quantum potential with specific QP can be used for instant action at a distance



Extended General Relativity Principle

- "All levels of energy structures and all levels of time structures mold spacetime geometry.
- This is called a *vacuum engine* (spacetime engine).
- Spatial and temporal structuring act upon mass at all levels.
- This produces *templates* of forces, for translations and stresses."

© T.E. BEARDEN 1990

ACTIVE SPACETIME
STRUCTURING OF ACTIVE SPACETIME CURVATURES
DYNAMIC MASS



Extension of Work-Energy Theorem

© T.E. BEARDEN 1997

- *Theorem*: $W = k_f - k_i = \Delta k$ [1]
- k must be interpreted not as energy *per se*, but as *collected/collecting* energy.
- The reaction cross section λ for the collecting process must be included.
- *Extension*: $W = \lambda (k_f - k_i) = \lambda \Delta k$ [2]
- Normally $\lambda \leq 1$, as for elastic collision or Stokes emission.
- However, $\lambda > 1$ is now possible, for processes which asymmetrically self-regauge. An example is Letokhov's negative absorption of the medium.
- Working models are the Patterson Power Cell® and Lawandy lasing without population inversion.



MTW's General Relativity Principle

- "Space acts on matter, telling it how to move.
- In turn, matter reacts back on space, telling it how to curve."

ACTIVE SPACETIME
DYNAMIC MASS
STRUCTURING OF ACTIVE SPACETIME CURVATURES

© T.E. BEARDEN 1998



Use of General Relativity (GR) in Particle Physics

- GR seldom used in particle physics

© 1998 T.E. Bearden

- In cold fusion, Matsumoto* has applied general relativity
- Consistent with important cold fusion results
- Used spacetime (ST) curvature by energy density
- Matsumoto did not utilize:
  - Longitudinal EM waves
  - Time density waves
  - Time density curvatures of ST (gain = 9×10^{16})

* T. Matsumoto, "Mechanisms of Electro-Nuclear Collapse," Proc. ICCF-7, Vancouver, BC, Canada, Apr. 1998, p. 98.



THE MISSING INFOLDED ELECTRODYNAMICS

Maxwellian electrodynamics has nothing at all to say about EM entities in space or their form

Material Electric Fluid Disturbed

MATTER-TO-MATTER TRANSFORM

Material Electric Fluid Disturbed

MATTER-TO-SPACETIME TRANSFORMATION

INFOLDED INSIDE MAXWELLIAN EM AS HIDDEN EM VARIABLES

SPACETIME-TO-MATTER TRANSFORMATION

INTERNESTED SPACETIME CURVATURES

(VACUUM ENGINES)

INFOLDED GENERAL RELATIVITY

EINSTEIN'S SPACETIME

© T.E. BEARDEN 1998



Infolded Engines: Excluded by Present Physics

- *The infolded dynamics of EM systems are not considered in general relativity, electromagnetics, or quantum mechanics*
- *None of these disciplines include such spacetime curvature engines (vacuum engines)*
- *Thus GR, EM, and QM cannot be unified, since ST curvature engines are where the unification mainly occurs*

© 1999 T. E. BEARDEN



ST curvatures propagate

© T.E. BEARDEN 1998

mass perturbation (Drude Electrons)

Transmitter

mass-to-spacetime transformation

altered spacetime (curvatures)

spacetime-to-mass transformation

altered spacetime (curvatures)

mass perturbation (Drude Electrons)

Receiver

Complex of ST curvatures (vacuum engine, or spacetime engine)

Spacetime disturbance (engine) propagates

The *mass-to-mass transform* contains two hidden infolded transforms: (i) the *mass-to-spacetime transform* and (ii) the *spacetime-to-mass* transform. What is transmitted and propagates in space is a *spacetime perturbation.*



Mass curves and structures spacetime; ST curvatures change and structure mass

ST curvatures propagate

mass

mass-to-spacetime transformation

spacetime-to-mass transformation

mass

altered spacetime

altered spacetime

ST curvature complex (vacuum engine)

© T.E. BEARDEN 1996

spacetime disturbance propagates



At Infinite Velocity:

Each Is Every Other

SPACETIME

VIRTUAL PARTICLE FLUX

POTENTIAL

MIND AND MIND LEVELS

MASS

PLANET

LIVING ORGANISMS

© 1997 T.E. Bearden



Lisitsyn's Report: Brain Code Broken

- THEORY DEVELOPED AND FITTED
- HYSTERESIS MEMORY LOOP
- CONTROLLED EM INDUCTION
  - IMAGES
  - SENSATIONS
  - PREDETERMINED EMERGENCE
- 23 EEG BANDS
  - UP TO 8.1 X 10^{20} HZ
  - 11 INDEPENDENT CHANNELS

© 1978, 1985, 1991 T.E. BEARDEN

S.K. Lisitsyn, "New Approach to the Analysis of Electroencephalograms,"
DDC Report AD73005, p. 16-25.



Lorentz Closed Surface Integration

Selects only the locally divergent portion of the Poynting energy flow that powers the component.

Only the wind on my ship is of physical significance!

© 1997 T.E. Bearden



Lorentz Closed Surface Integration

Selects only the locally divergent portion of the Poynting energy flow that powers the component.

How can they use that old physically insignificant wind?!!

© T E BEARDEN 1998

Lorentz's physically insignificant energy flow can be collected and utilized.



Lorentz surface integration of the Poynting vector around a closed surface

See Panofsky & Phillips, Classical Electricity and Magnetism, 2nd, edn., Addison Wesley, 1962, p. 178-181.

1a. Lorentz surface integration.

1b. Actual S in and S out.

Note: If the S-vector is integrated over the closed surface, then all energy *transport* passage is zeroed, leaving only the very small component of the input S-flow that is powering the joule heating of the resistor. In short, only the small component of the S-flow that is equal in magnitude to the Slepian vector $j\phi$ remains. This measures only the tiny portion of the S-flow that is "collecting" on electrons passing through the resistor, and therefrom being dissipated out of the resistor as joule heating. It discards everything else (all S_{TR}'s and S_{OUT}). S_{IN} becomes S_R.

© 1997 T.E. BEARDEN



Longitudinal EM Photon Interaction with Charge

- Creates time-density wave pumping
- Slowly creates time-density charging

Transverse photon
CHARGED MASS
Excited Energy Density State
Time-density (scalar) photon
Longitudinal photon
Phase Conjugate Added by Charged mass
CHARGED MASS
Excited Time Density State

© 1990 T.E. Bearden

- Fundamental units are arbitrary in physics
- Can express all physics in one unit -- e.g., time
- Time is highly compressed energy
- 1 sec = 9 x 10_{16} joules of transverse EM wave energy

Figure 1-8. Infolded biwave composition of a scalar potential.



Mass is transparent to longitudinal EM waves, which move through the infolded interiors of internal waves, potentials, and fields in the mass

MASS MEDIUM
Ambient Vacuum Potential
EMWave
Static EM Field
© T.E. BEARDEN 1997
Ambient Vacuum Potential
D.C. Potential

Mass is mostly ambient vacuum potential, modified by internal potentials, fields, and waves. Any wave or field is just two scalar potential functions, by Whittaker 1904.

Pumping with Longitudinal EM Waves Time-reverses the Mass


vacuum (spacetime) engine in the mass is the input
Type text
A4
A 2
A_2^*
longitudinal EM pump wave
MASS previous state
CELL MASS
highly nonlinear to any and all LW frequencies
Antiengine acts upon mass at all levels
Type text
A3
longitudinal EM pump wave
A_1
A_1^*
© T.E.BEARDEN 1997

AN AMPLIFIED VACUUM (SPACETIME) ANTIENGINE IS FORMED AND ACTS ON THE MASS, TIME-REVERSING IT AND ALL ITS COMPONENTS NO MATTER HOW SMALL



Maxwell's Quaternion Theory

- Quaternions:
  - Discovered by Hamilton in 1843
  - A quaternion has a vector part
  - A quaternion has a scalar part
  - First significant non-arithmetic number system
  - Higher topology than vector or tensor algebra
- Maxwell's theory was in quaternion equations
  - 20 equations in 20 unknowns
  - Reduced to a small 4-equation subset by Heaviside and Gibbs
  - EM topology dramatically reduced

© T.E. BEARDEN 1995, 1996

Maxwellian Systems

Before regauging, after symmetrical regauging, and after asymmetrical regauging

Note: Any system must first break equilibrium in its vacuum exchange, before it can energize Drude electrons and "power" the load. Asymmetric regauging is always utilized. Powering loads and losses is a symmetry-restoring operation.



MAXWELL'S EQUATIONS BEFORE THEIR REGAUGING

BEFORE REGAUGING

OPEN SYSTEMS NOT IN THERMODYNAMIC EQUILIBRIUM

OPEN SYSTEMS IN THERMODYNAMIC EQUILIBRIUM

ASSUMED "CLOSED" SYSTEMS

SYSTEMS WHICH REGAUGE, FREELY CHANGE ENERGY, AND SHOW COP<1.0 BY DESIGN

SYSTEMS WHICH REGAUGE, FREELY CHANGE ENERGY, AND SHOW COP>1.0 BY DESIGN

SYSTEMS REGAUGE, CHANGE ENERGY, BUT USE HALF THE ENERGY TO DESTROY SOURCE DIPOLE

TRULY CLOSED SYSTEMS (NONE EXIST)

ASYMMETRICAL REGAUGING

SYMMETRICAL REGAUGING

(c) 1996, 1997 T.E BEARDEN

Selected clipart© by Lotus SmartPics™



Page 1 of 2.

Maxwell's four equations reduce to:

$$\nabla^2\Phi + \frac{1}{c}\frac{\partial}{\partial t}(\nabla \bullet A) = -4\pi\rho \qquad [1]$$

$$\nabla^2 A - \frac{1}{c^2}\frac{\partial^2 A}{\partial t^2} - \nabla(\nabla \bullet A + \frac{1}{c}\frac{\partial \Phi}{\partial t}) = -\frac{4p}{c}J \qquad [2]$$

A is replaced by A', where

$$A' = A + \nabla\Lambda \qquad [3]$$

The new B' field then becomes

$$B' = \nabla \times (A + \nabla\Lambda) = \nabla \times A + 0 = \nabla \times A = B \qquad [4]$$

A new E-field will also be formed. So let

$$\Phi' = \Phi - \frac{1}{c}\frac{\partial\Lambda}{\partial t} \qquad [5]$$

© T.E. BEARDEN 1997



Page 2 of 2.

Per Jackson, (A,Φ) are *habitually* chosen so that

$$\nabla \bullet A + \frac{1}{c}\frac{\partial \Phi}{\partial t} = 0 \qquad [6]$$

The *net symmetrical* regauging separates variables. Two inhomogeneous wave equations result:

$$\nabla^2 \Phi - \frac{1}{c^2}\frac{\partial^2 \Phi}{\partial t^2} = -4\pi\rho \qquad [7]$$

$$\nabla^2 A - \frac{1}{c^2}\frac{\partial^2 A}{\partial t^2} = -\frac{4\pi}{c}J \qquad [8]$$

© T.E. BEARDEN 1997

Equations [1] and [2] *arbitrarily* changed to [7] and [8]

The Tom Bearden Website

Energy, Observations and Comments

---

1. A Conservative Field Requires a Single-Valued Potential
2. Earth-Electrosphere and Earth-Ionosphere Capacitors
3. Earth's Poynting Energy Flow
4. The Hidden Energy Flow around us
5. Electrostatic Fields of the Earth's Electrosphere Capacitor in Fair Weather and Thunderstorms
6. Flow of Current and Energy Into, Through, and Along a Conductor
7. Energy "collected" on a charge
8. Fiber Fuse Effect
9. Impact of Vacuum Engineering
10. Lawandy's Experiment
11. Field may be nonconservative for a multivalued potential
12. The Ostrich Problem - Part 1
13. The Ostrich Problem - Part 2
14. Russia had Overunity Devices in 1930s
15. Energy output of human body
16. A "static" Poynting S-flow free-energy generator
17. Topology and Energy Conservation
18. Block Diagram: Sweet's Vacuum Triode



A Conservative Field Requires a Single-Valued Potential

©1995 T.E. BEARDEN

A circular closed path in potential ϕ is given by A-B-C-B'-A.
Line integral from A around any closed path back to A is conservative.
Along path A-B-C, work W(1) may be extracted from rolling ball.
Along path C-B'-A, must do work W(2) on ball, where $W(2) = -W(1)$.

Return to Slide Index

Next Slide



Earth-Electrosphere and Earth-Ionosphere Capacitors

Earth to electrosphere capacitor ≈ 300 kV

Varies from about 100 km to about 400 km and has multiple layers

25 to 60 km

About 12,800 km

EARTH

Earth's surface

Ionosphere (RF conducting region)

Consists of free electrons caused by ionizing effect of solar radiation

NOTE: Spacing of shells is exaggerated.

Electrosphere (DC conducting region) Consists of molecules ionized by cosmic rays

© 1996 T.E. BEARDEN

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)

EARTH'S POYNTING ENERGY FLOW


N (compass)
(magnet south pole)
H
E
S
S (compass)
(magnet north pole)

© 1996 T.E. BEARDEN

a. CROSSED-FIELD POYNTING GENERATOR

b. MAGNETIC FIELD OF THE EARTH GENERATOR

POYNTING ENERGY FLOW AROUND EARTH FROM WEST TO EAST

(BIDIRECTIONAL SUBTLE ENERGY FLOWS ARE GOING ON INSIDE THE POYNTING FLOW, WITHIN ITS EQUIPOTENTIALS)

c. FLOW OF POYNTING ENERGY IN THE EARTH-ELECTROSPHERE CAVITY

Return to Slide Index

Next Slide

Previous Slide


Vacuum Flux Exchange
DIPOLES
Vacuum Flux Exchange
10^{-13}
Collection and dissipation filtering by each object
10^{-13}
Collection and dissipation filtering by each object
© 1996 T.E. BEARDEN
Selected clipart © by IMSI MasterClips™
Selected clipart © by Lotus SmartPics™

Incredible energy flow density extracted from vacuum/dipole's virtual photon flux exchange, and output as Poynting flow S

In a single pass, only 10^{-13} of an energy flow is collected and dissipated by an intersecting unit charge. If multiple passes are made, the multicollection increases as an exponential function of the number of passes made in a highly localized region.

Figure 19. The world of physical matter exists behind a dramatic 10^{-13} filter in a fiery cauldron of fierce and primeval EM energy flow.

Return to Slide Index

Next Slide

Previous Slide



Electrostatic Fields of the Earth-Electrosphere Capacitor in Fair Weather and Thunderstorms

ELECTROSPHERE
25 to 60 km
© T.E. BEARDEN 1995
Ion transport
Electric field lines
Equipotential
Equipotential
750 m
Cumulo-nimbus
Fair weather Fracto-cumulus
Rain
1 m
Ground
- 10 km
- 5
Distance behind storm
Cloud zero
5
Distance ahead of storm
10 km

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



Flow of Current and Energy Into, Through, and Along a Conductor

dm_e/dt

LATERAL PRECESSION

S enters and exits

Spinning electron
inside the wire
acts as a gyro

Poynting flow
outside the wire

e^-

SPIN

SPIN

Poynting flow S (outside)

FIELD ENERGY DENSITY FLOW

$d\phi/dt$ $v \approx c$

dq/dt (inside)

dm_e/dt

$v < c$

(WORK FLOW)

© 1994, 1995 T.E. BEARDEN

current i

direction

wire

dm_e/dt

S, $d\phi/dt$ (outside) lossfree Poynting energy flow S

dm_e/dt (inside) drift current i

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)


©
™
V
√7
√6
√5
√4
√3
√2
√1
0
S^VI
S^V
S^IV
S'''
S''
S'
S
S-FLOW
Regauge
dE/dt
dφ/dt
J φ
Sluggish
Charged Particles

S flows along equipotentials. The energy density in the S-flow is proportional to the square of the voltage. The S-flow is like a very high wind, blowing against the very sluggish conduction charges that in relation are massively heavy, and simply drift very, very slowly along to form the current dq/dt.

Figure 17. Energy "collected" on a charge depends upon the charge being in a continuous Poynting S-flow. When S ceases, there is no excess energy "collected" on the charge. Energy collection never occurs in chunks, but is always a dynamic, ongoing process.

Return to Slide Index

Next Slide

Previous Slide


MARCH OF FIBER FUSE
~ 1 METER/SEC
SHEATH
LASER LIGHT
DIRECTION
FLAME HEATING
INITIATES FUSE
CORE
(MUST CONTAIN
GERMANIUM)

31A. Fiber fuse destroys core of fiber optics cable of indefinite length, pitting core with holes.


MARCH OF FIBER FUSE
~ 1 METER/SEC
LASER LIGHT
DIRECTION
© 1989, 1995 T.E. BEARDEN
FLAME HEATING

31B. Reversed second fiber fuse often *restores* pitted core in cable, filling holes back up.

Figure 31. Fiber fuse effect and its strange anomalies.

Return to Slide Index

Next Slide

Previous Slide



Impact of Vacuum Engineering

- "If they [quantum fluctuations of vacuum] can be [tapped], the impact upon our civilization will be incalculable. Oil, coal, nuclear, hydropower, would become obsolete – and so would many of our worries about environmental pollution."
- "Don't sell your oil shares yet – but don't be surprised if the world again witnesses the four stages of response to any new and revolutionary development:
  - 1. It's crazy!
  - 2. It may be possible -- so what?
  - 3. I said it was a good idea all along.
  - 4. I thought of it first."

Arthur C. Clarke
"Space Drive: A Fantasy That Could Become Reality"
Nov./Dec. 1994

- *Comment:*
  - *Every dipole's broken symmetry in its energetic exchange with the vacuum already freely extracts vacuum energy.*
  - *In power sources, the dipole gates the extracted energy out as S = EXH, which flows almost entirely outside the conductors.*
  - The circuit interacts with, and uses, only about 10^{-13} of S. The electrodynamicists calculate only this small S-component.

© 1996 T E BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Selected clipart © by Lotus SmartPics™
DYE IN SOLUTION
EXCITED BY GREEN LASER
GREEN LASER
TiO2 PARTICLES ADDED IN SOLUTION
© 1996 T. E. BEARDEN

Note: Example of anti-Stokes radiation, where medium emits excess radiation and energy. In this case, energy is replenished directly from vacuum's energetic interaction.

A pure dye is dissolved in a liquid (left). A green laser pulse excites the dye (center). A laser pulse of equal intensity is sent into the same dye mixed with tiny particles of titanium dioxide suspended in the liquid (right). The latter experiment produces a much stronger, room-filling glow.

Nabil M. Lawandy et al, "Laser action in strongly scattering media," Nature, Letters, 368(6470), Mar. 31, 1994, p. 436-438

Figure 28. Lawandy's experiment (Letokhov-Lawandy effect) with multipass, multicollection of energy. Formation of a quantum potential can also become involved. Retroreflection and self-targeting are key.

Return to Slide Index

Next Slide

Previous Slide



Field may be nonconservative for a multivalued potential

(Multivalued magnetic scalar potential arises readily in magnetics)

(Asymmetrical Self-Regauging). Potential is Multivalued Here.

A
ϕ
B
ϕ for a Conservative Field
D
Nonconservative Field
C
B'
© 1995 T.E. BEARDEN

Potential ϕ is multi-valued from D to A.

Line integral from A around this closed path back to A is nonconservative. Along entire path A-B-C-B'-D, work may be extracted.

No work is required to go from D to A. When ball arrives at D, it also arrives at A simultaneously. I.e., the potential "jumps" in magnitude.

Return to Slide Index

Next Slide

Previous Slide



We're running out of energy! We must redouble our efforts!

We have to keep polluting the Earth, if we are to have energy!

Actually, a *few* of our electrical systems already produce all the energy we could ever need! *Learn to collect it and use it!*

Selected clipart © by IMSI MasterClips™
Selected clipart © by Lotus SmartPics™

All our antibiotics are failing! Millions will die from the new age of pandemics and from terrorists' BW attacks!!

We have to relegate EM effects on biological systems to the trash heap. We can only try to find more drugs and antibiotics.

Actually, Priore already showed how to cure most dread diseases, by making and directing vacuum engines. Becker showed you it worked. *Develop it and use it!*

Figure 33. The only problem is the ostrich problem.

© T.E. BEARDEN 1996

[Return to Slide Index]

[Next Slide]

[Previous Slide]



We're running out of energy!
We must redouble our efforts!

We have to keep polluting the Earth, if we are to have lots of electrical energy!

Every dipole is a universal free energy generator

Actually, a single one of our large electrical power systems already produces all the free Poynting energy the world could ever need! *We just have to learn how to collect more of it and use it without continually destroying the source dipole!*

Figure . The only energy resource problem is the theoretical ostrich problem. We must become theoretical owls, rather than ostriches.

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



RUSSIAN "SWITCHED PARAMETERS" DEVICES: SELF-OSCILLATING ROTARY GENERATORS*

- Excites oscillations without explicit sources of magnetic or electric forces (i.e., regauges)
  - Periodic variation in system's parameters
  - Experimental and theoretical proof
  - Multiple successful systems made, tested
  - Papers published in Russian, French journals
- As theory predicts, power continually increases unless load is adjusted to stabilize system
- Several large systems tested to self-destruction
- Several large stable systems built, tested

* "On the parametric excitation of electric oscillations,"
L.I. Mandel'shtam and N.D. Papaleksi, Zh. Tek. Fiz. 4(1), 1934, p. 5-29.

© 1994 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide


Selected clipart © by Lotus SmartPics™
Selected clipart © by IMSI MasterClips™
+ -
~10^{-13}
© 1996 T.E. BEARDEN

Incredible energy flow density extracted by double surfaces from vacuum/dipoles' virtual photon flux exchange, and output as Poynting flow S

Energy equal to a million 1,000 megawatt power plants.

$\sim 10^{-13}$

Collection and dissipation filtering by measuring instrument

About 100-200 watts actually collected and dissipated inside the body itself.

Dipoles at tiny double-surface interfaces may produce E-fields of intensity up to 10^9 volts per meter.

For rough estimate: Use 1 sq. meter effective area, and 1 million double-surfaces.

Figure 20. One human body produces more energy flow than all the electrical power loads on earth dissipate. However, only 100-200 watts of its own energy output is collected and dissipated by the body.

Return to Slide Index

Next Slide

Previous Slide


S = E X H
capacitor plate
+
H
–
S
capacitor plate
E
N
permanent magnet
S = E X H
(c) 1996 T.E. BEARDEN

EM energy continually flows from this "static" arrangement, without any further input of energy by the engineer.

Figure 18. A "static" Poynting S-flow free-energy generator.

Return to Slide Index

Next Slide

Previous Slide



Topology and Energy Conservation

Example: Conservation in
2D versus 3D topologies

3-D CONSERVATION
(2-D CONSERVATION VIOLATED)

© T.E. BEARDEN 1992, 1995

2-D CONSERVATION

Increasing the dynamic topology allows lower topology conservation laws to be violated. The lower topology system is now an open system and may seemingly act as a source or sink.

Return to Slide Index

Next Slide

Previous Slide

Block Diagram: Sweet's Vacuum Triode



STRUCTURED IMMEDIATE VACUUM

ACTIVATED NONLINEAR NUCLEUS

EM WAVE COUPLED FROM/TO ELECTRON

RESONANCE

PC WAVE

SIGNAL WAVE

SURROUNDING VACUUM

EXTERNAL LOAD CIRCUIT

FIELD OF BARIUM FERRITE MAGNET

EXTERNAL SIGNAL WAVE INPUT

POSITIVE FEEDBACK

CLAMPED STABILIZER

AUTOMATIC GRID SIGNAL INPUT

© 1989, 1991, 1993 T.E. BEARDEN

Return to Slide Index

Previous Slide

Defense Department Briefing on Priore Treatment to counter Biological Warfare

---

SLIDE LIST

Solutions to Mass Casualties Treatment Problem

Threat and Current Status

1. Title Page
2. Key Points in the New Technology
3. Title Page
4. Title Page
5. The Terrorist Threat
6. The Superpower Paradox: Asymmetric Cheap WMD Strategic Strike and Destruction
7. Mass Casualty Problem: Aerial Anthrax Spray on Washington, D.C.
8. Present Status of the WMD Threat to the United States
9. Some Present Problems in the WMD Defense Capabilities

Historical Solution: Priore Treatment Therapy

10. Title Page
11. Priore's laboratory device for treating small animals
12. Antoine Priore with the Mayor of Bordeaux
13. Raymond Pautrizel, eminent French parasitologist, who worked with Priore
14. 12-Foot plasma tube in Priore's large device
15. Priore's 3 1/2 stories high device for whole body treatment of humans
16. Mechanism of the Priore therapy
17. Priore's therapeutic methodology: using infolded longitudinal EM waves as NLO pump waves, to pump in the time domain
18. Drastically reduced cumulative deterioration after Priore therapy

Extended Physics and Background

19. Title Page
20. Founders of Scalar Electromagnetics
21. Subdivisions of Soviet Energetics

22. Bunge on the Status of Classical and Quantum Physics
23. Einstein on Reviewing Foundations
24. Fields and Potentials have been "defined" only in and on matter
25. Maxwell's Equations are Matter-To-Matter Transforms
26. Electrodynamicists' Reaction to Removal of the Material Ether
27. The Missing Infolded Electrodynamics
28. Nonlinear Optics Distortion Correction Theorem
29. Infolded longitudinal EM biwave composition of a scalar potential
30. The Zero-Vector Axiom Destroys "Topologies Within Topologies"
31. Stoney-Whittaker Bidirectional Longitudinal EM Wave-Pair
32. Undistorted Progressive Waves (UPWs)
33. Velocity modulating a longitudinal EM wave oscillates rate of flow of time
34. The Graviton is a Coupled Photon/Antiphoton Pair
35. Mechanism for Physical Change and the Flow of Time
36. Any EM Field or Wave Pattern is Produced by interference of Two Scalar Potential Functions (E.T. Whittaker, 1904)
37. Mass is transparent to longitudinal EM waves, which move through the infolded interiors of internal waves, potentials, and fields in the mass
38. Deep penetration of weak signals in a dense signal environment, by nonlinear retroreflection
39. The Immune System
40. Popp's master cellular control system
41. Cancer: characteristics
42. The evolutionary path of multicellular organisms
43. Effect of fluid contamination on hemoglobin's oxygen transport
44. First step in Self-Promotion of Cancer due to Hypoxia
45. Becker's Cellular Growth Control
46. Becker's dc treatment of bone fractures
47. Becker's theoretical DC control system involved with responses to injury
48. Becker's theoretical control system governing regeneration
49. Link Between Standing DC Potentials and the Nervous System
50. Becker's Findings on Cellular Injury and Regeneration
51. Corrections For the Present EM Bioeffects Model
52. R&R System - Regeneration Example
53. Kaznacheyev's Cytopathogenic Mirror Effect
54. Microwave Radiation of U.S. Embassy in Moscow

55. Self-Targeting in Inner EM Channel Can Produce a Quantum Potential
56. Quantum potential and hidden variable theory
57. Participants in a quantum potential share a common multiply-connected spacetime (MCST)
58. Gulf War Syndrome and Typical Comparative Disease Curves
59. Force Fields and Symmetry
60. Aspects of Strong Local Asymmetry
61. Other Aspects of Strong Local Asymmetry
62. Small Entities Emit Powerful S-Flows
63. What is the "magnitude" of a potential?
64. Table A1. The Vacuum Energetically Interacts With Every Particle, Continually
65. Extended Superpotential Theory (Adding Vacuum Engines)
66. Vacuum Engine: Jillions of Working ST Demons
67. Active Spacetime and a Specific Vacuum Engine (A General Relativistic Concept and Analogy)
68. Extension of Wheeler's general relativity principle
69. Signal versus Vacuum Engine
70. Electronuclear Interactions by Vacuum Engines
71. Vacuum Engineering
72. Impact of Vacuum Engineering
73. A Dramatic Extension to Nonlinear Optical Pumping
74. Time Conservation and Some Properties (Energy and time are canonical)
75. A Dramatic Extension to Nonlinear Optical Pumping
76. Key Points in the New Technology

Modern WMD Solution: Portable Treatment Systems

77. Title Page
78. Portable Priore-Type Treatment System
79. Portable System Block Diagram
80. Portable Priore Technology Unit
81. Saving the Stricken Civilians

Conclusions: Technology Practical, Proven

82. Title Page
83. Summary and Conclusions

Recommendation: Crash Development Program

84. Title Page
85. Recommend implementing:
86. Final Thoughts



Terrorist WMD Strikes
on U.S. Cities:

Solution to Mass Casualties Treatment Problem

CTEC, Inc.

28 Mar. 1998

(c) 1998 T.E. BEARDEN

Return to Slide Index

Next Slide



Key Points in the New Technology

- There is a vast new kind of electrodynamics *hidden inside* all EM potentials, fields, and waves
  - Longitudinal EM waves and complexes
  - Oscillations in time domain
- These complexes are an *infolded general relativity*
  - Clustered formations of *spacetime curvatures*
  - *Very powerful*, since the EM force is used as the agent of curvature
- In general relativity, similar precise complexes permeate and *act on any mass at all internal levels*
- With this approach, one *can now manipulate matter* -- living or inert -- *in any manner desired*, depending only on the level of development of the technology
- Priore unwittingly used this to *cure dread diseases*
- This is a *revolution in all of science*

© T.E. BEARDEN 1998

- *We have uncovered the major mechanisms* to utilize

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc.

28 Mar. 1998

© 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc.

28 Mar. 1998

© 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



THE TERRORIST THREAT

TODAY:

- Sabotage
- Chemicals
- Biological agents
- Nuclear materials
- Powerful explosives
- Assassination
- Kidnapping and hostages
- Contamination
- Shoulder-fired AD missiles
- Terrorism

FUTURE ADDITIONS:

- EM weapons
- EM biological warfare
- Scalar EM weapons
- Scalar EM disease induction
- Alteration of behavior and emotions
- Alteration of memory
- Direct thought control
- Action-at-a-distance effects

Return to Slide Index

Next Slide

Previous Slide



The Superpower Paradox: Asymmetric Cheap WMD Strategic Strike and Destruction

Complex, expensive, high tech

Simple, cheap, low tech

LIBYA
EGYPT
SUDAN
SAUDI ARABIA
IRAN

© 1993, 1996, 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Mass Casualty Problem: Aerial Anthrax Spray on Washington, D.C.

- One terrorist, one light aircraft with spray tank
- 100 kilograms of anthrax
- Flies over greater metropolitan Washington, D.C.
- Calm night
- *1-3 million casualties result**
- *Most of those stricken will die*
- Presently little can be done to save the stricken civilians
- *Attacks on several population centers might produce some 10 million or more casualties*

*Per OTA Report to Congress, 1993

Return to Slide Index

Next Slide

Previous Slide



Present Status of the WMD Threat to the United States

- Many foreign nations are hostile to the U.S. and sponsor terrorists
- Some 25 nations have WMD or are acquiring them
  - BW agents and weapons
  - Chemical agents and weapons
  - Nuclear materials and weapons
- Thousands of students and emigres
- Infiltrated teams, BW, other WMD already
- Castro guerrillas infiltrated over the years
- Can do unacceptable damage to U.S. now
- *May reach first strike knockout capability*

© 1998 T.E. BEARDEN

*Per OTA Report to Congress, 1993

Return to Slide Index

Next Slide

Previous Slide



Some Present Problems in the U.S. WMD Defense Capabilities

- *No shelters (require overpressure, BW filtering, masks, showers, supplies)*
- *No stockpiled vaccines, medical supplies, immunoglobulins, masks, suits, food, fuel, generators, heaters, water purification units*
- Totally insufficient medical facilities, personnel, and emergency response teams
- Triage, full martial law will be required
- *No answer to massive decontamination problem*
- State, county, city inadequately staffed and insufficiently trained for mass casualties
- Terrorist teams, BW agents, other WMD on site, waiting
- Water supplies, food, crops, farm animals also vulnerable
- Electric power grid, bridges, trains, railroads vulnerable
- *Present medical science cannot save very many of the casualties, now or in the foreseeable future*

© 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes
on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc.

28 Mar. 1998

(c) 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide

Priore's laboratory device for treating small animals


GIANT
COIL WITH
PLASMA MIXING
TUBE INSIDE
SMALL
ANIMAL
HOLDER

Return to Slide Index

Next Slide

Previous Slide



Antoine Priore (right) with the Mayor of Bordeaux, Mr. Chaban-Delmas.

Photo courtesy of Bob Whitney

The Priore technical mechanism unwittingly involved a dramatic extension to both nonlinear optics and general relativity. However, nonlinear optics itself had not yet been born in the 1950s and 1960s when Priore worked out his methodology. The extension to general relativity has not been previously envisioned even to the present day. When the Priore project was suppressed by the changed French government in the mid-1970s, nonlinear optics itself was just being initiated. To the present day, however, there has previously been no inkling of the dramatic extension to NLO that arises by using longitudinal EM pump waves and thereby pumping in the time domain.

It is little wonder that Priore himself did not understand the nature of the technical mechanism he was utilizing, and neither did anyone else, and neither *has* anyone else prior to this time.

© 1998 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



Raymond Pautrizel, eminent French parasitologist who worked with Priore

Among other things, Pautrizel treated seriously infected immature rats with the Priore ray. These rats had never had a mature immune system. When they were removed from the machine, they still sickened again and died, because their immature immune systems could not resist the pathogen *(Trypanosoma)*. So even though the damaged cells were reversed back to normal, the "normal" immune system was unable to fight off pathogens, which reinfected the cells and killed them, killing the rats.

This established the time-reversal nature of the therapy.

© T.E. BEARDEN 1997

Return to Slide Index

Next Slide

Previous Slide



12-Foot plasma tube in Priore's large device

PHOTO COURTESY BOB WHITNEY

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



Priore's 3-1/2 stories high device for whole body treatment of humans

Giant coil
around 12-ft long
plasma tube

Pulsed DC
Magnetic field

Table for reclining
human body

[Return to Slide Index]

[Next Slide]

[Previous Slide]



MECHANISM OF THE PRIORE THERAPY

- FACT: DISEASE-SPECIFIC VACUUM ENGINE PRESENT FOR ANY CELLULAR DISEASE, BY WHEELER'S PRINCIPLE
  - *DISEASE CAN BE REVERSED BY CREATING AMPLIFIED VACUUM ANTI-ENGINE (BEARDEN'S PRINCIPLE)*
  - *ANTI-ENGINE IS CREATED BY PUMPING THE NONLINEAR CELLS IN THE "INNER EM" DOMAIN, TIME-REVERSING THEM*
- PRIORE UTILIZED A PLASMA TO PHASE CONJUGATE AND "INFOLD" MULTIPLE BIDIRECTIONAL LONGITUDINAL EM PUMP WAVES
  - *17 FREQUENCIES MIXED IN A ROTATING PLASMA*
  - *PHASE CONJUGATES ADDED BY THE PLASMA*
  - *INFOLDED MIX INTO STRONG PULSED DC MAGNETIC FIELD, WHICH CARRIED IT INTO ATOMIC NUCLEI*
  - *PUMPED ALL NONLINEAR CELLULAR COMPONENTS TO PRODUCE AMPLIFIED, SPECIFIC VACUUM ANTI-ENGINE*
- NEGATED THE LONG-TERM CUMULATIVE CELLULAR DEDIFFERENTIATION ORDER GENERATED BY LONG-TERM HYPOXIA. TUMOR CELLS REVERTED TO NORMAL CELLS.
- SCRUBBED OUT THE CUMULATED PRECANCEROUS STATE
- RESTORED THE IMMUNE SYSTEM TO HIGH FUNCTIONING
- NO EXCESSIVE TRAUMA TO TREATED ANIMAL

CANCR-69

© 1994, 1996, 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Priore's therapeutic methodology: Using infolded longitudinal EM waves as NLO pump waves, to pump in the time domain

Time-reverses the cells back to normal state

START

FORM A SET OF HARMONIC EM WAVES (17)

ADJUST SOME WAVE FREQUENCIES

MIX WAVES IN A PLASMA TO ADD CONJUGATES

MIX OUTPUT INSIDE STRONG PULSED DC MAGNETIC FIELD

EXPOSE WHOLE BODY OF PATIENT TO DIMENSIONED MAGNETIC FIELD

CELL AND ALL ITS PARTS ARE PUMPED IN INNER EM CHANNEL IN TIME DOMAIN

VACUUM ENGINE FOR DISEASED CELL ALREADY PRESENT

DISEASED CELL PHASE CONJUGATES ITS VACUUM ENGINE

FORMS AMPLIFIED VACUUM ANTIENGINE FOR CELL'S DISEASE VACUUM ENGINE

TIME REVERSES CELL AND ALL ITS PARTS*

CELL RESTORED TO NORMAL?

NO

YES

STOP

*Includes genetics

© 1994 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



DRASTICALLY REDUCED CUMULATIVE DETERIORATION AFTER PRIORE THERAPY

NOTE: Priore therapy
treats entire body.

MAGNITUDE OF
SUSCEPTIBILITY

BODY
Cells and tissues

Cancer Threshold

Body
action point

CONVENTIONAL THERAPY:

Scarring, physical damage, etc. Immune system deterioration.

Deterioration after conventional treatment

Deterioration before treatment

Δ (conventional therapy)

Dramatically reduced deterioration after Priore therapy.

PRIORE THERAPY:

No scarring or physical damage, etc. Immune system restored.

Separation from body action point

JCS-50

© 1993, 1996 T.E. BEARDEN

[Return to Slide Index]

[Next Slide]

[Previous Slide]



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc.

28 Mar. 1998

© 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Founders of Scalar Electromagnetics

- **G.J. Stoney:**

Decomposed the scalar potential into bidirectional wave pairs.

"On a supposed proof of a theorem in wave-motion," Phil. Mag., 5(43), 1897, p. 368-373 (and several other papers).

- **E.T. Whittaker:**

Decomposed the scalar potential into a series of bidirectional EM wave pairs in harmonic series, where the two waves in each pair are conjugates (i.e., a wave/antiwave pair) and are longitudinal waves.

"On the partial differential equations of mathematical physics," Math. Ann., Vol. 57, 1903, p. 333-355.

Showed that all classical EM -- including waves -- can be replaced by two interfering scalar potential functions.. (This founded superpotential theory, extended by Nisbet, Bromwich, Debye, McCrea, and others.)

"On an expression of the electromagnetic field due to electrons by means of two scalar potential functions," Proc. Lond. Math. Soc., Series 2, Vol. 1, 1904, p. 367-372.

- **R.W. Ziolkowski:**

Independently rediscovered the biwave decomposition of the scalar potential and added the product set (in theory enabling modulations and communications) to Stoney and Whittaker's sum set.

Various papers, 1985 to date.

© T.E. BEARDEN [illegible]

Return to Slide Index

Next Slide

Previous Slide



Subdivisions of Soviet Energetics

NONLIVING SYSTEMS

LIVING SYSTEMS

Energetics

- Nonliving systems
- Scalar Interferometry
- Action-at-a-Distance
- Quantum Potential
- Vacuum Engines
- Spacetime Structuring
- Material, Field Effects
- Nuclei, Lattice Changes
- Hidden EM Variables
- SWZ Effects

Bioenergetics

- Living Systems (Bodies)
- Cells, cellular changes
- Master Cell Control (Popp)
- Spacetime Structuring
- Disease Induction, Remission
- Action-at-a-Distance
- Quantum Potentials
- Scalar Interferometry
- Hidden EM Variables
- SWZ Effects

Psychoenergetics

- Living Systems (Minds)
- Thoughts, Memories, Emotions
- Conscious/Unconscious Minds
- Spacetime Structuring
- Species, Biospheric Minds
- Action-at-a-Distance
- Quantum Potentials
- Scalar Interferometry
- Hidden EM Variables
- SWZ Effects

© 1996 T.E. BEARDEN

Selected clipart © by IMSI MasterClips™

Return to Slide Index

Next Slide

Previous Slide



Bunge on the Status of Classical and Quantum Physics

"... it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state... the best modern physicist is the one who acknowledges that neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling not only to better cover their own domains but also to join smoothly so as to produce a coherent picture of the various levels of physical reality."

*Mario Bunge, Foundations of Physics, Springer-Verlag, New York, NY, 1967, p. 176..

© 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



EINSTEIN ON REVIEWING FOUNDATIONS

"...the scientist makes use of a whole arsenal of concepts which he imbibed practically with his mother's milk; and seldom if ever is he aware of the eternally problematic character of his concepts. He uses this conceptual material, or, speaking more exactly, these conceptual tools of thought, as something obviously, immutably given; something having an objective value of truth which is hardly even, and in any case not seriously, to be doubted. ...in the interests of science it is necessary over and over again to engage in the critique of these fundamental concepts, in order that we may not unconsciously be ruled by them."

Albert Einstein, "Foreword," in Max Jammer, Concepts of Space: The History of the Theories of Space in Physics, Harvard University Press, Cambridge, Massachusetts, 1969, p. xi-xii.

JCS-11A

© 1993 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Fields and Potentials have been "defined" only in and on matter

$E \equiv F/q$ exists on mass only

Note problem!
No "E" or "H" in vacuum.

$S = E \times H$

Source q is a broken symmetry in vacuum flux

$S = E \times H$

Point Coulomb

"pileup" in front produces energy density gradient across the point coulomb

So $E \equiv -\nabla\phi$

$\phi \equiv$ joules continuously in geometrical flow distortion zone around one point coulomb

[Coulombic energy collection density]

© 1987 T.E. BEARDEN

[Return to Slide Index]

[Next Slide]

[Previous Slide]



Einstein's Spacetime

© T.E. BEARDEN 1998

???

Maxwell's Material Ether

Material Ether Fluid Perturbations

Material Electric Fluid Disturbed

Φ, ϕ, E, B, H etc.

(Material entities)

Material Electric Fluid Disturbed

All Maxwell's EM entities are defined only in and of charged matter. All are material entities. There was no place devoid of mass, in the universe.

MAXWELL'S EQUATIONS ARE MATTER-TO-MATTER TRANSFORMS

Return to Slide Index

Next Slide

Previous Slide


NONMATERIAL SPACETIME
© T.E. BEARDEN 1998
MAXWELL
MAXWELL
Φ
H
???
ELECTRODYNAMICISTS

Michelson-Morley experiments, 1880's

Material Fluid Perturbation Equations

Material Electric Fluid Disturbed

Material Electric Fluid Disturbed

Now we are not using a material ether. Trust us! Equations do not need changing.

Electrodynamicists' Reaction to Removal of the Material Ether

Return to Slide Index

Next Slide

Previous Slide



THE MISSING INFOLDED ELECTRODYNAMICS

Maxwellian electrodynamics has nothing at all to say about EM entities in space or their form

Material Electric Fluid Disturbed

MATTER-TO-MATTER TRANSFORM

Material Electric Fluid Disturbed

MATTER-TO-SPACETIME TRANSFORMATION

INFOLDED INSIDE MAXWELLIAN EM AS HIDDEN EM VARIABLES

SPACETIME-TO-MATTER TRANSFORMATION

INTERNESTED SPACETIME CURVATURES

(VACUUM ENGINES)

INFOLDED GENERAL RELATIVITY

EINSTEIN'S SPACETIME

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Nonlinear Optics
Distortion Correction Theorem

E_1 = INCIDENT WAVE

E_2 = TIME-REVERSED WAVE

"If a scalar wave $E_1(r)$ propagates from left to right through an arbitrary but lossless dielectric medium, and if we generate in some region of space [say near z = 0] its phase conjugate replica $E_2(r)$, then E_2 will propagate backward from right to left through the dielectric medium, remaining everywhere the phase conjugate of E_1."

JCS-64

© 1994, 1995, 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Infolded longitudinal EM biwave composition of a scalar potential

GALLOPING VELOCITY
Scalar Potential ϕ
© T.E. BEARDEN 1997
...ETC.
✱ ✱ ✱ ...ETC.
V avg
Wavepair #3
HARMONICS
V avg
SUBHARMONICS
Wavepair #2
V avg
Wavepair #1
...ETC.
✱ ✱ ✱ ...ETC.
DISTANCE

The Structure Is:

A harmonic set of longitudinal EM wavepairs. In each wavepair the two waves superpose spatially, but travel in opposite directions. The two are phase conjugates and time-reversed replicas of each other. Thus they comprise a coupled longitudinal wave and antiwave. The photons must be coupled into photon/antiphoton pairs (gravitons) by a strong application of the distortion correction theorem of nonlinear optics. Each wave in the biwave pair is a galloping wave. Each wavepair is a standing electrogravitational wave. In nonlinear optics, such a wavepair is a pump wave which pumps in the time domain.

Note: Think of the oscillations as velocity modulations.

Return to Slide Index

Next Slide

Previous Slide



The Zero-Vector Axiom Destroys "Topologies within Topologies"

- The axiom: There is a unique vector, $\overline{0}$, in V (the vector space) such that
  $$\overline{V} + \overline{0} = \overline{0} + \overline{V}$$
- Note that $\overline{V} + \overline{0}_i = \overline{0}_j + \overline{V}$; $\overline{0}_i = -\overline{0}_i = n\overline{0}_i$
  so $\overline{0}_i = \overline{0}_j = \overline{0}_k = \ldots + \overline{0}_n = \ldots$
- This makes all $\overline{0}_i$ equal by assumption, since there is *assumed* to be only a single type $\overline{0}$ without real components
- In fact, $\overline{0}$ is *not unique*. An *infinite number* of different zero-vector systems, with real components, satisfy the zero-vector axiom.

Return to Slide Index

Next Slide

Previous Slide



STONEY-WHITTAKER BIDIRECTIONAL LONGITUDINAL EM WAVE PAIR

(An electrogravitational wave)

Total time densities are additive, so "wave" appears "static" (standing) and gravitational

A wavelike variation in the local time density of the vacuum. The velocity of the EM wave oscillates. The amplitude of the EM wave does not change.

Hidden forward time EM time density flow

Hidden reversed-time time density flow

To any affected or exposed unipolar object, EM force operations cancel due to simultaneous time action and reaction

A coupled EM wave/antiwave pair infolds electromagnetic energy, converting it to gravitational energy. The wavepair becomes an electrogravitational standing wave.

(c) 1993, 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Undistorted Progressive Waves (UPWs)*

(waves with velocity v, where $0 \leq v \leq \infty$)

- Major equations of interest having UPW solutions are:
  - *Homogeneous wave equation*
  - *Maxwell equations*
  - *Dirac, Weyl, and Klein-Gordon equations*
- UPWs are translationally invariant, and do not spread, or they reconstruct their original form after a certain period.
- UPW solutions have infinite energy. Quasi-UPWs can have finite energy and can in principle be launched into space.
- Subluminal Maxwell solutions are called ***EM particles***. Superluminal Maxwell solutions are called ***X-waves***.
- *Experimental results indicate such waves will be produced within the next few years.*
- *Nimtz has translated Mozart's 40th symphony at v = 4.7c.*

*Rodrigues and Lu, *Found. Phys.* 27(3), 1997, p. 435-508.

© 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Velocity modulating a longitudinal EM wave oscillates rate of flow of time

$$V = \frac{L}{t}$$

Observer sees it this way

Constant transverse wave magnitude

Wave oscillates its velocity along its path, about a nominal value

Wave oscillates this way

Constant transverse magnitude

Wave oscillates magnitude of its transported t, about a nominal value

Note:

- Waves consist of photons
- Each photon consists of energy x time
- Each photon carries time as well as energy
- A wave is both a spatial energy dynamics and a temporal dynamics
- Wave complexes carry dynamic time structures as well as dynamic energy structures

© 1997 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



The Graviton Is a Coupled Photon/Antiphoton Pair

(Both photon and antiphoton are longitudinal)

In physics, the primary units selected are arbitrary. Everything can be expressed, e.g., in terms of time alone. Thus so can photon spin.

ACTION

VACUUM ENGINE

REACTION

LONGITUDINAL PHOTON

LONGITUDINAL ANTIPHOTON

IS THIS A SPIN 2 ENTITY?

It is, in the time domain.

© 1988, 1998 T.E. BEARDEN

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



Mechanisms for Physical Change and the Flow of Time

SPATIAL
SPATIOTEMPORAL
PHOTON
L^2T
SPATIAL
PHOTON
L^2T
MASS
L^3
MASSTIME
L^3T
MASS
L^3
SPATIAL AND SPATIOTEMPORAL
"MASS"
MASSTIME
L^3T
MASS
MASS
MASSTIME
L^3T
"MASS"

$$(\Delta E)(\Delta t) + M \Rightarrow (M+\Delta M)\Delta t \Rightarrow M + (\Delta E)(\Delta t)$$

Flow of macroscopic time (observable photon interactions)

Flow of microscopic time (via virtual photon interactions)

The photon interaction generates an observed quantum change and a discretized jump in the rate of time flow. A particle observably changes by only a single Δt at a time. The background flow of time in which the jump in rate occurs, is created by the continual absorption and emission of virtual photons.

© 1994 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Any EM Field or Wave Pattern Is Produced by interference of Two Scalar Potential Functions *(E.T. Whittaker, 1904)*

(Use of Hidden Information Content of the Field)

(Can Provide Action-at-a-Distance)

Note:
Whittaker's 1904 paper initiated the entire field of superpotential theory.

Interference Zone (Potential gradients)
Normal EM Energy:
May be positive, or negative, or fixed

Hidden Bidirectional EM energy flow

Hidden Bidirectional EM energy flow

Whittaker/Ziolkowski Transmitter Arrays
(8 to 20 harmonic wavepairs each)

© T.E. BEARDEN 1997

Return to Slide Index

Next Slide

Previous Slide



Mass is transparent to longitudinal EM waves, which move through the infolded interiors of internal waves, potentials, and fields in the mass

MASS MEDIUM
EM Wave
Ambient Vacuum Potential
Static EM Field
D.C. Potential
Ambient Vacuum Potential

© T.E. BEARDEN 1997

Mass is mostly ambient vacuum potential, modified by internal potentials, fields, and waves. Any wave or field is just two scalar potential functions, by Whittaker 1904.

[Return to Slide Index]

[Next Slide]

[Previous Slide]



Deep penetration of weak signals in a dense signal environment, by nonlinear retroreflection

Nonlinearity
Internal potentials and weak signal emissions occur from these internal operating EM components
Cross-Section of Body
Body Surface
Enlargement of nonlinearity area
Pumped Retroreflection Phase Conjugate Mirror (PCM) Effect due to multi-photon interactions
Dense Signal Environment (May be very weak signals)
PCM
PCR*
PCR
Amplified Partial Cancellation of Body's Internal Signals by addition of phase conjugate replicas

In a dense signals environment, probability of simultaneous signals interacting increases. This increases the probability of deep penetration by amplified phase conjugate reflections of weak internally generated signals from the interior, impinging upon the pumped (stressed) nonlinear surface areas where the simultaneous exterior interactions occur.

* Phase conjugate replica

© 1993, 1995 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



THE IMMUNE SYSTEM

BONE MARROW
Lymphocytes
Special Defense
Intestinal tissue, liver, etc.
Thymus
Complement system
General Defense
Feeding cells
Monocytes
B-lymphocytes
suppressor cells
plasma cells
antibodies
T-lymphocytes
killer cells
helper cells
complement factors
granulocytes
macrophage
bacterium (foreign invader)

CANCR-18

© 1993 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



Popp's master cellular control system

- Provides coherent, long-range interactions in biological systems
- Is an organized morphogenetic field at the basis of functional control

- Emission very sensitive to almost all external and internal influences
- Both spontaneous and delayed luminescence occur
- Photons stored in cell during the delay

- Leakage provides ultraweak, coherent biophoton emission from the system
- Fractional intensity pattern: few to some 100s of photons/cm^2/sec
- Optimum signal-to-noise ratio

- A single delayed biophoton may be able to trigger 10^{10} reactions in a cell before its release
- Spectrum almost continuous within optical range from 200-800 nm.

- Biophoton emission shows biological system always out of equilibrium
- Emission has holistic characteristics
- Correlations to most, if not all, of the biological functions of the organism

- DNA, all other processes are sources
- Single main process of whole system, different processes strongly coupled
- Information function and sync of biological clocks (oscillators)

© 1997 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



CANCER: CHARACTERISTICS

- NOT ONE DISEASE BUT A WHOLE RANGE
- STARTS IN ORDINARY (AEROBIC) CELL
- CELL SHAKES OFF BODY'S DICTATORIAL CONTROL*
- STARTS UNCONTROLLED DIVISION
- BECOMES A LUMP
- CAN SEND FORTH CANCER CELLS
  - THROUGH BLOOD
  - THROUGH LYMPH
- THESE FORM METASTASES (SECONDARY TUMORS)
- OFTEN BECOME ANAEROBIC (NON-OXYGEN USING)
- ENIGMA IS FAILURE OF IMMUNE SYSTEM TO ATTACK SOME TUMOR CELLS
  - SUPPRESSOR CELLS MAY CURB IMMUNE SYSTEM
  - TUMOR MAY LACK ANTIGENS NORMALLY IDENTIFIED BY THE IMMUNE SYSTEM

**R&R system forces cell back toward anaerobe*

© 1993 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



THE EVOLUTIONARY PATH OF MULTICELLULAR ORGANISMS

ESSENTIALLY ANAEROBIC ATMOSPHERE

CHANGE OF ATMOSPHERE TO AEROBIC (INCLUDES OXYGEN)

BIOGENESIS

SINGLE CELL ANAEROBIC

OBLIGATORY ANAEROBES SINGLE CELL SHIELDED FROM OXYGEN

FACULTATIVE ANAEROBES (SINGLE CELL BOTH AEROBIC AND ANAEROBIC)

EVOLVE TO

SINGLE CELL AEROBIC*

EVOLVE TO

MULTICELL AEROBIC* (INCLUDES MAN)

CENTRAL CONTROL

SINGLE CELL COMPONENTS

- IMMUNE SYSTEM
- RED CELLS
- WHITE CELLS
- KILLER CELLS
- ETC.

MULTICELL COMPONENTS

- TISSUES
- MUSCLES
- BONES
- ORGANS
- SKIN
- STRUCTURES

*NOTE: LIMITED ANAEROBIC RESPIRATION STILL TAKES PLACE IN HIGHER AEROBIC LIFE FORMS, INCLUDING MAN.

EVOLUTIONARY TIME

CANCR-01

c 1993 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



EFFECT OF FLUID CONTAMINATION ON HEMOGLOBIN'S OXYGEN TRANSPORT

RED BLOOD CELLS

AIR

Severe pollution

Severely reduced
oxygen transport

(Such as
cigarette smoke)

RED BLOOD CELLS

LUNG
SACS

BODY

ATMOSPHERE

CANCR-09

© 1993 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



FIRST STEP IN SELF-PROMOTION OF CANCER DUE TO HYPOXIA

* NOTE: LIMITED ANAEROBIC RESPIRATION STILL TAKES PLACE IN HIGHER AEROBIC LIFE FORMS, INCLUDING MAN.

SINGLE CELL ANAEROBIC
SINGLE CELL AEROBIC*
MULTICELL AEROBIC* (INCLUDES MAN)
CENTRAL CONTROL
OXYGEN-RICH
TIME-FORWARD PATH AS IT DEVELOPED
TIME-REVERSED PATH FOR SUSTAINED OXYGEN DEFICIENCY
SINGLE CELL AEROBIC*
FIRST STEP IN OXYGEN-DEFICIENCY DEDIFFERENTIATION

CANCR-08

© 1993 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



BECKER'S CELLULAR GROWTH CONTROL

- Two major links uncovered between :
  - The DC system and nervous system
  - The DC system and all body cells
- Bioelectric potentials of primary importance
- Physiology presently considers controls limited to:
  - Neural action potential
  - Various hormone chemical agents
  - Chemical agents associated with DNA/RNA system
- Complete Operational Biological Control System:
  - Controls growth, healing, biological cycles, etc.
  - Operates in ANALOG mode; various levels of DC
  - Interlocks physically with nervous system (and may be its precursor)
  - Other chemical agents
  - Tissue growth and healing NOT INCLUDED
- Medical community now more concerned with diseases resulting from:
  - Inadequate/abnormal growth
  - Inadequate healing

Return to Slide Index

Next Slide

Previous Slide



Becker's dc treatment of bone fractures

Application of tiny DC currents to heal difficult bone fractures. Only picoamperes are utilized. Pulsed DC current or pulsed magnetic fields may also be utilized.

BECKER'S
BONE FRACTURE SETUP
(DIAGRAMMATIC)

RED BLOOD CELL DEDIFFERENTIATES

Shucks hemoglobin coat
Grows nucleus

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes cartilage

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes bone
Deposits in fracture site, healing the fracture

Proves that cells can be time-reversed (phase conjugated) (dedifferentiated) or time-forwarded (redifferentiated) by application of very weak electromagnetic signals, when those signals contain longitudinal bidirectional EM "pump wave" wavepairs, which cause the cell and its parts to create precise vacuum antiengines.

© 1993, 1995 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide

*Becker's theoretical DC control system involved with response to injury**



INJURY

INPUT STIMULATION DC SYSTEM (PAIN)

CENTRAL DC SYSTEM

GROWTH DIFFERENTIATION

LOCAL CELL INJURY FREE RADICALS

OUTPUT DC SYSTEM

MITOSIS DEDIFFERENTIATION

STIMULATION OF REPAIR CELLS

TOTAL CURRENT OF INJURY DC SYSTEM

*Robert O. Becker, "The significance of bioelectrical potentials," Bioelectrochemistry and Bioenergetics, Vol. 1, 1974, p. 191.

Return to Slide Index

Next Slide

Previous Slide



Becker's theoretical control system governing regeneration*

Trauma Producing Tissue Loss

Local cellular effect

Local nerve effect

CNS effect

Alterations in hormone pattern (prolactin)

Alterations in local DC field pattern

Local electrical effects

Local and systemic pools of target cells

Dedifferentiation into primitive mesenchymal cells

Phase I

Blastema formation

growth

Phase II

Redifferentiation into required cell types

Restoration of body part or tissue

*Becker & Spadaro, "Electrical stimulation of partial limb regeneration in mammals," Bull. N. Y. Acad. Med., 48(4), May 1972, p. 629.

Return to Slide Index

Next Slide

Previous Slide



Link Between Standing DC Potentials and the Nervous System

- Standing DC potentials on intact surfaces of all living animals demonstrate a complex field pattern spatially related to the anatomical arrangement of the nervous system
  - Can be measured directly on the peripheral nerves
  - Polarity difference related to whether nerve is or is not a sensor
  - Steady (weak) current flow exists
  - Demonstrates solid state/semiconductor phenomena
  - Accurately reflects (amplitude and polarity) the general level of neural activity
    - Sleep versus wakefulness
    - Anesthesia versus conscious
    - Other parameters
- DC levels determine the level of neural activity
- Action potential system exists upon a substratum of DC potentials which pre-existed it
- DC potentials substrata had and have control functions over basic properties of the living organism

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Becker's Findings on Cellular Injury and Regeneration*

- Cellular processes are regulated by a precise control system
- Attempted to apply engineering control-system theory
- Cells and tissues have solid-state electrochemical features which provide control signals in the control system
  - Growth process
  - Electron transfer
  - Semiconduction
  - Self-organizing *(NOTE: Implies hidden variables and nonlocal causality)*
- Complex electrical events at the injury site initiate cellular aspects such as dedifferentiation and mitotic activity
- Regeneration is a 2-step process, each with different controls
  - Electrical triggers with threshold values results in appearance of blastema
  - Complex data transmission to blastema establishes it as a self-organizing system capable of growth and redifferentiation
  - Mammals lack ability to produce blastemas except for bone, but partial regeneration growth has been shown in response to electrical stimuli
- Growth related to electrical more than electrochemical aspects
- Hematopoietic marrow as source of cells for the blastema
  - Monocytes can take place in regenerative processes in limbs
  - Lymphocytes can dedifferentiate under certain circumstances
  - Marrow elements can be induced into osteogenesis

*R.O. Becker & J.A. Spadaro, "Electrical Stimulation of Partial Limb Regeneration in Mammals," Bull. N. Y. Acad. Med., 48(4), may 1972, p. 627-641.

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Corrections For the Present EM Bioeffects Model

PRESENT INADEQUATE EM BIOEFFECTS MODEL

START

A

OVERALL STIMULUS/RESPONSE MODEL

1. EM STIMULUS/ RESPONSE MODEL

2. EXPERIMENT OR GROUP OF EXPERIMENTS

3. INSTRUMENTATION AND RECORDING

4. INTERPRETATIVE MODEL AND COMPARATIVE STANDARD

5. INTERPRETED RESULTS

6. EM THEORY TO BE APPLIED

7. ARE RESULTS CONSISTENT?

YES

NO

8. EM THEORY CORRECT

STOP

9. EM THEORY INCORRECT

IMCS/EM ASSUMPTIONS

1. PRESENT EM MODEL CORRECT AND COMPLETE
2. DOSAGE/RESPONSE SYNONYMOUS WITH STIMULUS/RESPONSE

10. FIND ERRORS IN EM THEORY POSTULATES

11. CHARGE DISCRETE, NOT QUANTIZED. VIRTUAL FLUX CAN BE STRUCTURED, FOR VACUUM ENGINES.

12. RETAIN ZERO VECTOR RESULTANT SUMMATIONS OF EM FORCE VECTOR COMPONENTS AS VACUUM ENGINES

13. FORCEFIELDS NOT PRIMARY. POTENTIALS ARE, HAVE HIDDEN EM WAVE STRUCTURE.

14. ADD WHITTAKER EM STRUCTURE OF POTENTIALS THEORY

15. ADD TO GENERAL RELATIVITY AND QUANTUM MECHANICS

16. CORRECT/EXTEND EM AND SHOW UNIFIED FIELD AND MIND/VOLITION

17. DEVELOP NEW TYPES OF INSTRUMENTS

18. CORRECT EM THEORY MODEL, INSTRUMENTATION AND RECORDING, AND IMCS

19. SEPARATE CHARGE Q INTO ITS COUPLED COMPONENTS

JCS-44

© 1991, 1993, 1995 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



PRIORE AMPLIFIED PUMPING

ADD PUMPS
B
RESIDENT VACUUM ENGINE
CELL AS A PHASE CONJUGATE MIRROR
ANTIENGINE PRESENT?
N
Y
APPLY ANTIENGINE
B
START
A
CYCLE
CELL AND INTERIOR SENSORS
LOCAL VICINITY SENSORS
NONLOCAL ALL-BODY SENSORS
DELTA CATALOGS
CELLS AND INTERIORS
SELECT LOCAL
SELECT NONLOCAL
AEROBE
ANAEROBE
Y
DELTA?
N
AEROBE
ANAEROBE
Y
DELTA?
N
AEROBE
ANAEROBE
Y
DELTA?
AEROBE
ANAEROBE
SWITCH COMPARATIVE CATALOG
SWITCH TO AEROBE CONTROL SYSTEM
A
Y
CROSS THRESHOLD BACK TO AEROBE?
N
SWITCH TO ANAEROBE CATALOG
Y
END OF AEROBE CATALOG?
N
SUM FOR ENTIRE BODY
SWITCH ON CENTRAL, OFF DECENTRAL GROWTH CONTROL; RESET IMMUNE SYSTEM
SWITCH OFF CENTRAL GROWTH CONTROL
SWITCH ON DECENTRAL GROWTH CONTROL
CONDITION IMMUNE SYSTEM TO ACCEPT
A

R&R SYSTEM

Regeneration Example

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Kaznacheyev's Cytopathogenic Mirror Effect

Disease vacuum engines transported by photons and waves

GRAVITON LATTICE TEMPLATES
SICKEN OR KILL
ENVIRONMENTAL SHIELDING
CELL CULTURE SAMPLE #1
QUARTZ CONTAINER
CELL CULTURE SAMPLE #2
QUARTZ CONTAINER
THIN WINDOW
✸ GLASS: No Effect
✸ QUARTZ: Delayed Effect
Divided bottle set-up

© T.E. BEARDEN 1977, 1987

Note: Minimum lattice is one harmonic interval: IR to UV is such a minimum G-lattice.

Distant induction of cellular death and diseases, by special EM means. Coupled photon-antiphoton pairs (gravitons) in a structured harmonic lattice ordering constitute the disease or disorder template.

Return to Slide Index

Next Slide

Previous Slide



MICROWAVE RADIATION OF U.S. EMBASSY IN MOSCOW

Former U.S. Embassy in Moscow.

BACKGROUND

- Began in latter 1950s
- Discovered on VP Nixon's trip
- Initially thought to be *nuclear* radiation (Discovered w/Geiger counter?)
- High level target -- U.S. Ambassador
- Guarantees personal attention of:
  - U.S. Ambassador to USSR
  - U.S. President
  - NSA, CIA, DIA, NSC, etc.
  - Top consulting scientists
  - Leading U.S. scientific institutions
- Two U.S. Ambassadors died, another sickened
- Anomalous health changes in personnel, only in zero-field (zero pot'l gradient) areas!
- Four U.S. Presidents requested Soviets cease
  - Cut from 18 watts/sq cm to 2
  - Then again increased
- No one could understand what was going on
- Aluminum screens were placed over windows
- Moscow was declared a hazardous duty zone

Selected clipart © by Lotus SmartPics™

© 1995, 1996 T.E. BEARDEN

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



Self-Targeting in Inner EM Channel Can Produce a Quantum Potential

Once QP is established, energy transmission is direct and instantaneous. Energy input to one single participant will simultaneously appear in all other participants, the amount depending on their fractions of participation with the input station.

NARROWING OF INTERACTING POTENTIALS INTO LASER-LIKE BEAMS, BETWEEN TWO PUMPED SOURCES. NOW ONLY LONGITUDINAL WAVES CONNECT THE LINKED OBJECTS.

SELF-TARGETING EFFECT AMONG ALL PAIRS OF INTERACTING PUMPED SOURCES

© [illegible] T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Quantum potential and hidden variable theory

a. Quantum Potential Characteristics

© 1988, 1995, 1997 T.E. BEARDEN

- No point source
- Not radiated
- Quantum potential between two particles
  - Interaction does not vanish as spatial separation becomes very large
  - Instantaneous connection, so multiply-connected space

b. Hidden Variable Theory and the Quantum Potential

- $$V_{quantum} = \frac{\hbar}{2m}\frac{\nabla^2\sqrt{\rho}}{\sqrt{\rho}}$$
- "A quantum particle moves as if it were subject, in addition to its external potentials, to a potential which is a function of its own probability distribution."
- Bohm's H.V.T. assumes:
  - Particle and wave function real and separate
  - Wave function obeys Shroedinger's equation
  - Particle obeys classical mechanics
  - Particle couples to wave function through a quantum potential

Return to Slide Index

Next Slide

Previous Slide



Participants in a quantum potential share a common multiply-connected spacetime (MCST)

- Separated points are superposed in MCST
- Intervening distance in MCST is zero
- Connection is instant and bidirectional
- Propagation through ST does not apply
- Energy or vacuum engine input to one station instantly appears at each and every other station, undiminished in magnitude
- Ultimate net-centric warfare effect

Note: Once QP established, separation distance in 3-space is of no consequence

Note: Vulnerability. Any other station may insert energy or vacuum engines into the same quantum potential. Phase conjugating the hostile engine can negate its effect everywhere

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Gulf War Syndrome And Typical Comparative Disease Curves

Note: There is cumulative genetic damage to germ cells also.

— — —	EXPOSED WITH MOST CUMULATIVE DAMAGE
-·-·-·-·	EXPOSED WITH MULTIPLE AGENT INFECTIONS AND RECEIVING MULLTITREATMENT
··········	EXPOSED WITH LESS CUMULATIVE DAMAGE
———	NON-GULF WAR: TYPICAL NORMAL DISEASE WHICH KILLS PATIENT

JCS-100

© 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Force Fields and Symmetry

- Force fields are nature's way of imposing local gauge symmetries on the world
- E.g., electromagnetic field is a manifestation of the simplest known gauge symmetry consistent with the principles of special relativity
- For the EM case, the gauge transformations correspond to changes in 'voltage' from place to place

© T. E. Bearden 1995, 1996

Return to Slide Index

Next Slide

Previous Slide



Aspects of Strong Local Asymmetry

- If local asymmetry is strong, conservation laws may be appreciably violated
  - Energy
  - Charge
  - Spin
  - Momentum
  - Angular momentum

© T. E. Bearden 1995, 1996

- Properties of an object may differ appreciably for
  - Different observers
  - Different detecting means
  - One time to another
  - One position to another
- STRUCTURING THE INFOLDED EM INSIDE POTENTIALS, FIELDS, AND WAVES
  - Strongly breaks local symmetry
  - Provides spacetime engines giving the above effects

Return to Slide Index

Next Slide

Previous Slide



Other Aspects of Strong Local Asymmetry

© T. E. Bearden 1995, 1996

- Local spacetime is curved
- Lorentz invariance of vacuum is violated
- May be a local "sink" or "source"
- Gravitational/inertial effects from EM
- Translation between virtual and observable
- Electrogravitational solitons
- Action at a distance
- Transmutation effects may exist
- Scalar/pseudoscalar field translation
- COMMENT: Thus the use of infolded longitudinal EM fields and waves to strongly break local symmetry allows internested clustering of spacetime curvatures. These spacetime structures are *vacuum engines*, or *spacetime engines*.

Return to Slide Index

Next Slide

Previous Slide



Small Entities Emit Powerful S-Flows

$V = 10^{-3} \, volts$

Surface layer of fluid atoms

Cellular membrane surface

$d = 10^{-9} \, meter$

$$E = 10^{6} \text{ volts / meter}$$

$$S \approx f(E^{2}) = f(10^{12})$$

© 1997 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



What is the "magnitude" of a potential?

- What is taught is the *"interaction cross section,"* i.e., the joules collected from the associated S-flow by one point coulomb of intercepting/collecting charge.

$$W = Vq = \phi q \quad \text{(joules)} \qquad [1]$$

$$\phi = W/q \quad \text{(joules/coul)} \qquad [2]$$

$$\text{Let } \phi < 1 \text{ and fixed; } q \Rightarrow n \text{ where } n = \infty$$

$$W \Rightarrow k, \text{ where } k = \infty \qquad [3]$$

- *From any "finite" potential, no matter how small, an unlimited amount of energy can be collected, by increasing the collection (number of coulombs) (interaction cross section).*
- Actual magnitude of the potential ϕ must be very, very large, since we can treat it as infinite or unlimited, via $W = \phi q$.
- *Else Equation [1] could not be linear.*

© T.E. BEARDEN 1997

Return to Slide Index

Next Slide

Previous Slide



Table A1. THE VACUUM ENERGETICALLY INTERACTS WITH EVERY PARTICLE, CONTINUALLY.

- The vacuum is:
  - Ground (zero) state of the electromagnetic (photon) field.
  - Ground (zero) state of mass field.
  - Empty of *observable* particles or photons.
  - Filled with *non-observable* (virtual) particles and photons.
  - Violently fluctuating microscopically and electromagnetically.
  - Constantly interacting with all particles, including partially shielding their bare charges.
- Lamb Shift -- vacuum's alteration of the energy level of an electron in the hydrogen atom.
  - -- Difference in energy (frequency units) is 1057.862 MHz.
  - -- Lamb was awarded a Nobel Prize for showing this.
  - -- Energy *density* exceeds that of the sun's surface!
- Casimir Effect -- vacuum creates an attraction between two conducting surfaces in close proximity.
  - -- experimentally proven, well-known.
- Cole and Puthoff proved that there is no thermodynamic reason why energy cannot be extracted from the vacuum as heat and power, and utilized.
- The common dipole is a broken symmetry in the virtual photon flux of vacuum. It extracts virtual energy, integrates it, and re-emits it as Poynting energy density flow S = ExH (which observably interacts with charged particles and magnetic poles).

Return to Slide Index

Next Slide

Previous Slide



Extended Superpotential Theory

(Adding Vacuum Engines)

- Any EM field or wave is created by (comprised of) two potentials which interfere with each other in a given area
  - *May be either scalar or vector potentials*
  - *May interfere locally or at a distance*
  - *Process is distance independent*
- Any scalar potential is comprised of a harmonic series of bidirectional longitudinal EM wavepairs (Whittaker 1903).
- Ziolkowski circa 1985 added the interior product set to Whittaker's sum set. Thus he added modulations.
- By assembling a deliberate "sum and product" set of biwaves, a scalar potential can be created having an internal deterministic structure.
  - *This structures local vacuum potential/spacetime curvatures, in specific forms (templates)*
  - *Now have added vacuum engines*
  - *Have infolded general relativity inside electrodynamics*

© 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Vacuum Engine: Jillions of Working ST Demons

Internested patterns
of spacetime
curvature

Structured
Einsteinian spacetime

Demons are
EM hidden variables
organized into
dynamic structures
at all levels

Demons work
at all levels

© T.E. BEARDEN 1998

Return to Slide Index

Next Slide

Previous Slide



Active Spacetime and a Specific Vacuum Engine

(A General Relativistic Concept and Analogy)

ACTIVE SPACETIME

DYNAMIC MASS

STRUCTURING OF ACTIVE SPACETIME CURVATURES

DETAILS OF STRUCTURING OF ACTIVE SPACETIME CURVATURES (TEMPLATE)

mass structures spacetime

spacetime structures act on mass at all levels

© T.E BEARDEN 1998

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



Extension of Wheeler's general relativity principle:

- Mass (trapped energy) and its structuring curves and structures spacetime complexes (engines).
- Curved and structured spacetime engines produce forces on mass and its components, telling them how to move and structure.
- Since very strong EM force is used as agent of curvature, very powerful general relativistic effects can be obtained by arranging the LWs in the input EM potentials, fields, and waves.
- General relativity becomes directly engineerable in devices of unparalleled capability.

ST curvatures propagate
mass
mass-to-spacetime transformation
spacetime-to-mass transformation
mass
altered spacetime
altered spacetime

Complex of ST curvatures (vacuum engine, or spacetime engine)

Spacetime disturbance (engine) propagates

© T.E. BEARDEN 1998

Electrodynamics has a hidden but ignored electro-general-relativity infolded inside (comprising) its so-called potentials, fields, and waves (in space in the absence of mass). What are presently defined as potentials, fields, and waves rigorously exist only in, on, and of charged mass, as pointed out by Aharonov and Bohm in 1959. All of this is just longitudinal EM waves and their interactions.

Return to Slide Index

Next Slide

Previous Slide



SIGNAL VERSUS VACUUM ENGINE

SIGNAL (INFO)

- INFORMATION RECEIVED
- ANY OVERT PHYSICAL ACTION MUST BE TAKEN BY RECEIVER

A. *Receiver must do the action itself; vacuum energy exchange is unaltered. Energy or fuel for doing the action must be added to receiver externally.*

© 1994, 1996 , 1997 T.E. BEARDEN

Selected clipart© by Lotus SmartPics™

VACUUM ACTIVATED

ENGINE (STRUCTURE) TEMPLATE (FORM)

- "INFORMATION" ITSELF ACTS
- VACUUM FLUX GRADIENTS CHANGE ALL PARTS AND CHARACTERISTICS OF RECEIVER, INSIDE AND OUT

B. *Receiver is acted upon; altered vacuum energy exchange does the specific action. No energy or fuel for doing the action need be added to receiver externally.*

Return to Slide Index

Next Slide

Previous Slide



Electronuclear Interactions by Vacuum Engines

- An EM potential is gravitational due to its trapped energy.
- A local EM potential is a local curvature of spacetime.
- *Structured* potentials are structured *(nested)* local spacetime curvatures; hidden variable theory applies.
- Structured potentials thus are *vacuum engines*.
- Gradient-free potential penetrates the atom, into nucleus.
- *With steady application, a structured gradient-free potential can be used to engineer the atomic nucleus at will.*
- Normal cold fusion systems structure a small fraction of their potentials, by chance geometries, boundaries, etc.
- This produces some new nuclides, but haphazardly.
- *The process can be developed and controlled. The nucleus can be deterministically engineered at will.*

© 1997 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Vacuum Engineering

Using Inner EM Energy and Structuring to Engineer Physical Reality

Vacuum Potential (Violent Flux)

Inner EM
(Ordering of Virtual Particle Flux of Vacuum)
Forms Vacuum Engines

Forms Structured Outer EM
(Potential gradients etc.)
$-\nabla \times A$, $-\nabla \phi$, etc.

Forms Force System on/of Mass
$F \equiv dP/dt$
$= d(mv)/dt$
$\equiv (-\nabla \phi)q$, etc

Assemble Bi-Wavepairs
Makes Scalar Potentials with Ordered Subtle Energy Internal Structure

Scalar Potential Interferometry
Two or More Scalar Potentials with Hidden Multiwave Structures
(Interference of ordered Subtle Energy Structures)

Observable Mechanics
(Statics and Dynamics)

START

YAO-01

START

© 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Impact of Vacuum Engineering

- "If they [quantum fluctuations of vacuum] can be [tapped], the impact upon our civilization will be incalculable. Oil, coal, nuclear, hydropower, would become obsolete -- and so would many of our worries about environmental pollution."
- "Don't sell your oil shares yet -- but don't be surprised if the world again witnesses the four stages of response to any new and revolutionary development:
  - 1. It's crazy!
  - 2. It may be possible -- so what?
  - 3. I said it was a good idea all along.
  - 4. I thought of it first."

Arthur C. Clarke
"Space Drive: A Fantasy That Could Become Reality"
Nov./Dec. 1994

© 1996 T.E. BEARDEN

- Comment:
  - *Every dipole's broken symmetry in its energetic exchange with the vacuum already freely extracts vacuum energy.*
  - *In power sources, the dipole gates the extracted energy out as S = EXH, which flows almost entirely outside the conductors.*
  - The circuit interacts with, and uses, only about 10^{-13} of S. The electrodynamicists calculate only this small S-component.

Return to Slide Index

Next Slide

Previous Slide

A DRAMATIC EXTENSION TO NONLINEAR OPTICAL PUMPING

© T.E. BEARDEN 1997


transverse pump wave
A_2
transverse signal wave (input)
A_4
PPCM
A_3
NONLINEAR MEDIUM
amplified phase conjugate replica transverse wave (time-reversed)
transverse pump wave
A_1
+ t
PREVIOUS VACUUM ENGINE
PREVIOUS MASS STATE
TIME AXIS
A_2
VACUUM ENGINE
AMPLIFIED VACUUM ANTIENGINE
MASS
A_1

a. Pumping with transverse EM waves produces a time-reversed *wave*.

b. Pumping with longitudinal EM waves A_1 and A_2 time-reverses *the mass itself*.

Return to Slide Index

Next Slide

Previous Slide



Time Conservation and Some Properties

(Energy and time are canonical)

- Time can neither be created nor destroyed
  - *Its form can be changed, and it can be positive or negative*
  - *Time can be collected or dissipated, converged or diverged*
  - *Time can oscillate and move in waves*
  - *Longitudinal (infolded) EM waves oscillate time*
- Time is always in motion, and that motion is variable
  - *Collected/collecting time is a continuing stationary change in an ongoing time flow*
  - *Time/collecting time can be internested and internally structured*
- Time has gravitational aspects
  - *Negative (trapped) time is antigravitational*
  - *Emitting negative time is gravitational, to the emitter*
- Nonlinear optical pumping can use longitudinal EM waves
  - *Pumping a nonlinear mass by longitudinal (infolded) EM waves pumps it in its masstime form, in the time domain*
  - *This creates an amplified vacuum antiengine for the mass, and time-reverses the mass back to a previous state*

© 1996 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



A DRAMATIC EXTENSION TO NONLINEAR OPTICAL PUMPING

© T.E. BEARDEN 1997

VACUUM ENGINE A'
VACUUM ENGINE (A' +B')
VACUUM ENGINE B'
TIME AXIS A
TIME AXIS (A+B)
TIME AXIS B
A_2
MASS
AMPLIFIED VACUUM ANTIENGINE [A' + B']
VACUUM ENGINE B
VACUUM ENGINE A
A_1
A + B

After adding a second vacuum engine, pumping with longitudinal EM waves (pumping in the time domain) deviates the time-reversed trajectory. The mass and its internal structure are translated into a new form with a new structure, which it need never have had.

Return to Slide Index

Next Slide

Previous Slide



Key Points in the New Technology

- There is a vast new kind of electrodynamics *hidden inside* all EM potentials, fields, and waves
  - Longitudinal EM waves and complexes
  - Oscillations in time domain
- These complexes are an *infolded general relativity*
  - Clustered formations of *spacetime curvatures*
  - *Very powerful*, since the EM force is used as the agent of curvature
- In general relativity, similar precise complexes permeate and *act on any mass at all internal levels*
- With this approach, one *can now manipulate matter* -- living or inert -- *in any manner desired*, depending only on the level of development of the technology
- Priore unwittingly used this to *cure dread diseases*
- This is a *revolution in all of science*
- *We have uncovered the major mechanisms* to utilize

© T.E. BEARDEN 1996

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc.

28 Mar. 1998

© 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Portable Priore-Type Treatment System

Equipment Case
Computer Control Unit
Infolding Function Generator
Antenna Pad

Return to Slide Index

Next Slide

Previous Slide

Portable System Block Diagram



Power Supply
Computer Control Unit
Frequency Generators
Infolding Function Generator
Field Sensor Unit
Magnetic Pulse Generator
Plasma Mixing Unit
Antenna Pad
Antenna Pad

[Return to Slide Index](#)

[Next Slide](#)

[Previous Slide](#)



PORTABLE PRIORE TECHNOLOGY UNIT

- FACT: DISEASE-SPECIFIC VACUUM ENGINE PRESENT FOR ANY CELLULAR DISEASE, BY WHEELER'S PRINCIPLE
  - *DISEASE CAN BE REVERSED BY CREATING AMPLIFIED VACUUM ANTI-ENGINE (BEARDEN'S PRINCIPLE)*
  - *ANTI-ENGINE IS CREATED BY PUMPING THE NONLINEAR CELLS IN THE "INNER EM" DOMAIN, TIME-REVERSING THEM*
- PRIORE UTILIZED A PLASMA TO PHASE CONJUGATE AND "INFOLD" MULTIPLE BIDIRECTIONAL LONGITUDINAL EM PUMP WAVES
  - *17 FREQUENCIES MIXED IN A ROTATING PLASMA*
  - *PHASE CONJUGATES ADDED BY THE PLASMA*
  - *INFOLDED MIX INTO STRONG PULSED DC MAGNETIC FIELD, WHICH CARRIED IT INTO ATOMIC NUCLEI*
  - *PUMPED ALL NONLINEAR CELLULAR COMPONENTS TO PRODUCE AMPLIFIED, SPECIFIC VACUUM ANTI-ENGINE*
- NEGATED THE LONG-TERM CUMULATIVE CELLULAR DEDIFFERENTIATION ORDER GENERATED BY LONG-TERM HYPOXIA. TUMOR CELLS REVERTED TO NORMAL CELLS.
- SCRUBBED OUT THE CUMULATED PRECANCEROUS STATE
- RESTORED THE IMMUNE SYSTEM TO HIGH FUNCTIONING
- NO EXCESSIVE TRAUMA TO TREATED ANIMAL

CANCR-69

© 1994, 1996, 1999 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



SAVING THE STRICKEN CIVILIANS

SURVIVORS OF N CASUALTIES

(N = 1-40 MILLION)

EXPRESSED IN FRACTION SURVIVING

🟩 With conventional treatment
🟨 With 1st generation P-treatment
🟧 With 2nd generation P-treatment
🟥 With 3rd generation P-treatment

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc.

28 Mar. 1998

© 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Summary and Conclusions

- A new therapeutic paradigm of great scope and effectiveness has been developed
  - *Will provide effective, quick treatment of mass casualties*
  - *Will provide cures for unknown agents*
  - *No pathogen strains are resistant to this process*
- Results have been proven experimentally
  - *Documented in French scientific literature*
  - *Rigorous scientific protocols, eminent scientists*
  - *Technical mechanism deciphered*
- Will treat and cure many diseases
  - *Aids, atheriosclerosis, cancer and leukemia*
  - *Sleeping sickness*
- Portable units can be developed quickly
  - *18-month crash development program required*
  - *high level authority and overwatch essential*
- *Will solve the BW mass casualty treatment problem, both civilian and military*

© 1993 T.E. Bearden

Return to Slide Index

Next Slide

Previous Slide



Terrorist WMD Strikes on U.S. Cities:

Solution to Mass Casualties Treatment Problem

- Threat and Current Status
- Historical Solution: Priore Treatment Therapy
- Extended Physics and Background
- Modern WMD Solution: Portable Treatment Systems
- Conclusions: Technology Practical, Proven
- Recommendation: Crash Development Program

CTEC, Inc. 28 Mar. 1998

(c) 1998 T.E. BEARDEN

Return to Slide Index

Next Slide

Previous Slide



Recommend implementing:

- Crash development program
  - Suitcase-sized portable unit
  - 18-month Manhattan-type project
  - Simultaneous theoretical modeling, animal testing w/breadboard models
  - SecDef and Congressional overwatch
  - Presidential Decision Directive
- Parallel logistics support program
  - Plan high speed production lines
  - Mass distribution, storage, maintenance
  - User, maintenance training
  - Plan C4 and usage at all levels
  - Integrate firemen, police, National Guard, FEMA, medical facilities, etc.

Return to Slide Index

Next Slide

Previous Slide



Final Thoughts:

- The current internal BW threat can and will kill more Americans than all our previous wars combined
- The Priore technology is the only solution in sight that can save most of those casualties

Return to Slide Index

Previous Slide

CTEC, Inc.
2311 Big Cove Road
Huntsville, AL 35801
(256) 533-3682 Ph/

CTEC, Inc.

June 24, 1998

Dr. Jane F. Kinsel, Director
Office of Policy Analysis
Department of Health & Human Services
Bathesda, MD 20892

Dear Dr. Kinsel:

Your letter of June 8 is appreciated. However, the entire action package had already gone to the Assistant SecDef and also to Major General Neary in the USAF.

The proof of a revolution in medical treatment was in the package. The basis for it is already demonstrated experimentally in the scientific literature, both in the U.S. and in France. We are speaking of something already proven, but missed by the entire U.S. medical community. Strong words, but true. Let me be specific.

Any cell in the body can be time-reversed (physics term) or dedifferentiated (biology term) back to an earlier state, by pumping (i.e., "squeezing" in simple terms) that cell with longitudinal EM waves as pump waves. There are considerable papers in the French scientific literature showing the experimental results.

Apply that to cancer. We are stating bluntly that all cancerous cells in the body can be "depromoted" back to normal cells easily. Further, the damage previously done to them (such as by sustained hypoxia due to contaminants reducing the oxygen-carrying ability normally given to it by some 60-to-80 surrounding water molecules per red cell and the consequent H-bonding interactions) will also be reversed. The cells can all be returned to healthy, normal cells again, without "killing" or "burning" or "cutting" anything.

With some development of the technology, you can quickly and easily cure every cancer patient in every hospital in the United States.

Now apply it to AIDS. Since you can time-reverse every cell in the body, you can time-reverse the HIV-infected cells – genetics and all – right back to normal cells with normal genetics. Those cells not infected and healthy, will just get a "little younger" again.

So with that small development, you can quickly and easily cure every AIDS patient in every hospital in the United States.

I would have thought that NIH would certainly be interested in such a revolutionary therapy which has already been demonstrated in laboratory experiments. World-renowned French scientists – such as the eminent parasitologist Pautrizel and research PhDs assigned directly by Robert Courrier, head of the Biology Section of the French Academy of Sciences, worked with Prioré in performing those startling experiments that proved what we are saying.

The method was rigorously shown to cure infectious diseases (such as trypanosomiasis), atherosclerosis (which now afflicts millions of Americans), and terminal tumors. It was shown to reverse suppressed immune systems back to normal vigorous functioning.

Please permit me to disagree with you that the examination of such is not the mission of the NIH. To the contrary, it is precisely the NIH which should have some of its very best scientists looking into this.

The action package to DoD was to propose a crash program to develop this methodology in the form of a small, portable unit for treatment of mass casualties resulting from a terrorist BW attack on our cities (now expected in the next few weeks, as you must be aware). The leading Arab terrorist of the world has already promised just this.

We are speaking of several million Americans who are going to die. They are going to die in spite of everything that NIH and its labs can do, even though I know you will make a heroic effort. With NIH present methods, you cannot do very much for those stricken Americans at all. Everything we have in the "normal" kit bag is almost useless against a knowledgeable spray attack of modified smallpox (as you know, the Russian secret BW labs have made and sold tons of that already, to guess who!). Or a spray of tularemia (you are well aware of the extreme lethality of that), or anthrax (easily obtained). It is also common knowledge that these terrorist teams with their BW agents are already on site in this country, waiting for the word to attack. This has now been officially raised to our primary Strategic Threat.

In the face of such looming strikes on the U.S., I simply cannot believe that the NIH does not feel it within their mission to rigorously check out a proposed method for saving perhaps 70% of those coming deaths (first generation equipment), and up to 90% with second generation equipment.

Perhaps you just did not read the package carefully. I urge you to do so.

Else NIH is going to look very, very bad when (1) the strikes do occur, (2) they can't handle them (and they cannot, as you well know), (3) they had within their hands in advance, a proposed methodology that could have been investigated intensely, to save millions of those stricken Americans.

As a staunch supporter of NIH and especially CDC, I have to believe that there is a different attitude there. If NIH is not interested in a previously experimentally demonstrated method of saving millions of Americans, then the only recourse left is the political channel.

I assure you that my critique of electrodynamics is well-founded, as supported by various leading physicists such as Nobelist Feynman (who stated bluntly that the field concept is wrong), Wheeler, Bunge, and so on. It is inexplicable why all our universities are still teaching a 130 year old abridged (Heaviside's) subset of Maxwell's theory, and one that still contains a material ether even though that was falsified 110 years ago!

You already have seen the misuse of this technology by the Russians, in the decades-long radiation of the U.S. Embassy in Moscow. Is it not NIH's mission to understand how they generated all those diseases and health changes? Have you ever looked into Kaznacheyev's experiments showing that ANY cellular disease or disorder can be induced in cells at a distance by purely EM means? Have you looked into what got eliminated from electrodynamics by ignoring the hidden longitudinal EM inside every potential, field, and wave? Do you realize what ignoring that has done to American chemistry, biochemistry, and medical science?"

I would hope that the NIH would at least be interested in its own mission area!

I challenge you bluntly to admit that no one presently understands the primary operation of the human cellular *regenerative* system. That's because its technical principle is not presently in our recognized physics, biochemistry, and medical science – even though it has been in the hard physics literature since 1903-4. Becker's epochal work came closest; since he only had access to the conventional EM model, it failed him. But he at least showed you rigorously that cells can be changed (both differentiated and redifferentiated) all over the map by laughably weak EM – picoamperes of current, which means persistent DC potentials. In the microwave radiation of the U.S. Embassy, all the health changes occurred in regions absent of fields – i.e., absent of bleed-off of the potentials. Hence in regions of stable DC potentials! With 100% correlation of the health changes to persistent, gradient free potentials, and 100% anticorrelation to changing potentials (i.e., fields), our own scientists concluded totally erroneously that it could not have been the EM radiation causing the changes, when their own results had just proven that it was.

Now I ask you: Can NIH explain how it was that the DC potentials caused those health changes? I think not. If it could, it would understand the action package I wrote, and its importance.

This is not a "political" letter. I'm just an ordinary American citizen who has done about 30 years very hard work on this particular area. The work is good enough now to stand on its own merits. The scientific community will eventually accept it, about 50 years from now. But we cannot wait 50 years! Those millions of Americans are going to die, because of the bureaucracy and inaction of our own scientific organizations. Whether they like it or not, the U.S. scientific community is now the forefront of the struggle for this nation to survive. And they are failing us dramatically.

So as a parent who wants his children to live, and his neighbors' children to live, and those millions of soon-to-be stricken Americans to live also, I urge you to at least have someone competent in physics (and knowledgeable that the foundations of physics itself are in woeful shape!) check the work. Has anybody there *read* any of the references to the Prioré work I cited? Does anyone there realize that *there are no EM forcefields in space?* Probably not.

Dr. Kinsel, there is a time for "business as usual" and there is a time to do some serious new work. Those stricken Americans are going to be lying there. Nothing NIH can do is going to stop that. That's a given, and it is not my own estimate. It's the official estimate. And you *know* you presently do not have the tools to do anything really effective about it.

Frankly, I interpret your letter to me as just the normal "spin control" for easy disposition. I would hope that NIH would seriously rethink the situation, get off the "spin control" and "business as usual" posturing, and do something dramatically different for a change.

What have you got to lose? A little time from perhaps two or three of your best scientists.

What have you got to gain? Saving untold millions of American lives. A new, *already partially demonstrated* cure for most dread diseases such as AIDS and cancer – diseases which you presently cannot do very much about in spite of decades of heroic struggle.

Sincerely,

cc: Senator Shelby, Congr. Cramer

T.E. Bearden
President and CEO

CTEC, Inc.
T.E. Bearden, President & CEO
2311 Big Cove Road
Huntsville, AL 35801-1351
(256)533-3682 ph/(256)536-0411 Fax

CTEC, Inc.

May 12, 1998

Dr. Harold Varmus, Director
National Institute of Health
Bathesda, MD 20892
(301) 496-1766

Dear Dr Varmus:

We have recently sent action documents to the Director of Nuclear and Counterproliferation, Office of the DCS, Air and Space Operations, HQ USAF and to the DoD (General Busbee) Assistant Secretary of Defense, as well as several Senate and House committees, which may be of interest to you. For one thing, we give the technical mechanism used to generate the Gulf War Syndrome. The same weaponry is now being used to rapidly induce new strains of certain pathogens worldwide. I urge you to closely read that section of the letter to MG Neary which explains the GWS, why the French did not get it, and why Southern Iraqis got an increase in cancer and leukemia but not GWS. Also explained is how the "microwave radiation" of the U.S. Embassy in Moscow induced diseases for decades, and how we failed to comprehend it because the standard EM model deceived us.

There is a way to treat and quickly cure most diseases, including the mass casualties resulting from a terrorist BW strike on our civilian population centers, our military bases, or our forces in the field. The method is little known, but was scientifically demonstrated in France in the 1960s and early 1970s before cancellation of the Prioré Project when the French Government changed. Eminent French scientists worked on the project, and the results are fully documented in leading French scientific journals. References are listed in a separate attachment.

Previously the Western scientific community has been unable to understand the technical mechanism responsible for such remarkable cures, because of serious foundations flaws in Western physics and electrodynamics. *Foundations* physicists have long been aware our science is flawed, and have pointed out many of these fundamental errors. However, the operational science establishment has not paid attention, even though physicists such as Feynman and Wheeler pointed out that the notion of "force fields in space" was totally wrong.

As a primary example, there is an "infolded" electrodynamics inside all potentials, fields, and waves that is far more primary than the coarse EM that is in our textbooks. It is actually an infolded general relativity, and this is what the Russians have weaponized. This infolded EM-GR has been ignored in the West (but not in Russia) since 1903.

As another example the potentials, fields, and waves of present electrodynamics are rigorously defined – and exist – only in the presence of mass. They do not exist in such form (force fields and oscillating force fields) at all in space, in the absence of mass. Rigorously, Maxwell's equations are mass-to-mass transforms, since Maxwell and everyone at the time assumed the ubiquitous presence of the material ether. In other words, to the founding electrodynamicists, there was no place in all the universe that was devoid of mass. Hence they defined all EM entities as entities containing mass. Even though Michelson-Morley experiments of more than a century ago destroyed that material ether, not a single Maxwellian equation has ever been changed! They still assume the material ether.

Specifically missing from our electrodynamics are two essential transforms: (1) the mass-to-spacetime transform, and (2) the spacetime-to-mass transform. In other words, these two transforms are "infolded" or hidden inside (comprise) the end point extremum case – the mass-to-mass transform actually written by Maxwell.

But these two missing transforms are just general relativity (they correspond precisely to Wheeler's principle of general relativity). So general relativity has always been infolded inside electrodynamics as we know it, but ignored. Further, this is a very powerful general relativity, since it uses the very strong EM force as the agent of spacetime curvature. Hence now one can engineer a powerful general relativity in the laboratory and in practical devices, and even action-at-a-distance, which one cannot do using merely the staid and weak G-force.

It turns out that longitudinal EM waves as shown by E.T. Whittaker in 1903 and 1904 are far more primary than our present EM theory and even our present GR theory. Both EM and GR are directly engineerable using longitudinal EM waves, including subluminal and superluminal EM waves in vacuum, and including action at a distance. One can engineer complexes of spacetime curvatures as desired, which in turn are *spacetime engines* (Wheeler's term). These engines can act upon mass – either living or inert – in any fashion desired, and at any distance desired.

The little-known and poorly understood Regeneration & Recovery (R&R) system – as contrasted to the immune system – utilizes this exact "spacetime engine" methodology to restore damaged or diseased cells, within its limitations – "dedifferentiating" or "time-reversing" them back to normal. The mechanism is fully explained in the attached package. The proposed program applies this fundamental method to greatly amplify the effect. Thus cancer cells can be reversed back to normal cells, HIV-infected cells (HIV-factories) can be reversed back to normal cells (genetics and all), etc. This represents a dramatic and unparalleled new medical therapeutic methodology of extreme power. The same techniques can simply be conjugated one additional time, and used to produce diseases and cellular changes at a distance, including in entire mass populations, as the KGB is doing right now. Specifically, by impressing an extremely weak "cocktail mix" of disease spacetime engines on the U.S. populace, the immune systems are reacting and being "spread thin" across several "shadow state" infectious pathogenic conditions. Thus when an actual terrorist BW attack occurs, the lethality of the strike will be remarkably enhanced because the immune systems will be "thinned" in their ability to fend off this new pathogen. By doing it this way, BW warfare can actually be conducted upon the U.S. without anyone being the wiser.

Our very survival as a nation is threatened by remarkable KGB weapons using this fully documented, extended electrodynamics. Bluntly, unless we take off our scientific blinders and understand Russian energetics weapon science, GWS and the Embassy health changes in Moscow were just a picnic before what is upon us. After two decades of work on the KGB energetics weapon problem, we have fully deciphered the technical mechanisms and what energetics is, as well as citing many of the Russian weapon tests and how they were done. Again, you can see that for yourself in the package.

Now that we understand the technical mechanisms, we are proposing rapid redevelopment of the Prioré process, in portable suitcase-sized units to be mass produced and filtered down into the entire emergency community for mass treatment of lethal infectious diseases resulting from BW strikes. And we are strongly urging the U.S. scientific community to quickly investigate and come to grips with this vast new *biological engineering* mechanism. Our very survival depends on it.

The inclosed documents provide an overview of the process. There is nothing else on the scientific horizon that can save the majority of all those stricken Americans, once the first foreign-sponsored terrorist teams strike our population centers with BW agents.

Sincerely,

Incls: Full package with table of contents

T.E. Bearden
President & CEO

Weapons Slides

The Tom Bearden Website

Help support the research

"Others [terrorists] are engaging even in an eco-type of terrorism whereby they can alter the climate, set off earthquakes, volcanoes remotely through the use of electromagnetic waves… So there are plenty of ingenious minds out there that are at work finding ways in which they can wreak terror upon other nations…It's real, and that's the reason why we have to intensify our [counterterrorism] efforts." *

Secretary of Defense William Cohen at an April 1997 counterterrorism conference sponsored by former Senator Sam Nunn. Quoted from DoD News Briefing, Secretary of Defense William S. Cohen, Q&A at the Conference on Terrorism, Weapons of Mass Destruction, and U.S. Strategy, University of Georgia, Athens, Apr. 28, 1997.

Slides
(covers period up to 1999)

- The Coming Strategic Attack on the United States
- Outline
- Loss of two separate A-10 Warthogs in 1997
- Typical ABM Defenses (Widely Deployed by mid-70s)

- Launch Phase Anti-Missile System
- Launch Phase Anti-Bomber System
- HC-130s Engines Quit, Aircraft Crashes
  Nov. 22, 1996
- 1996 Actions by this analyst
- Additional Information Exists: Not Analyzed, Not Integrated in Briefing
- Kill of Arrow DC-8, Gander AFB, Dec. 12, 1985
- Satellite Photos of Plumes in Soviet Arctic Since 1974
  See "Fer de Lance" for additional information
- Aum Shinrikyo ("Supreme Truth" Cult), Shoko Asahara, Leader

  Aum Shinrikyo - Anatomy of a Dangerous Cult
- Ashkhabad Problem and Its Solution
- Strange Characteristics of Iran Quake, Sep. 1978
- Iran Earthquake, September 1978
- Situation Now (Assessment)
- Situation Now (Assessment 2)
- Aspects of Strong Local Asymmetry
- Mass Casualty Problem: Aerial Anthrax

Spray on Washington, D.C.

- Present Status of the WMD Threat to the United States
- Some Present Problems in the U.S. WMD Defense Capabilities
- Internal Terrorist Threat with Weapons of Mass Destruction: Now & Future
- Attempt to Ban Energetics Weapons Worldwide
- Brezhnev's Schedule
- Large glowing Tesla globe witnessed in Red China by hundreds
- Cold Explosion -- 9 April 1984 Near Kurils, and formation and growth of spherical shell (globe)
  Sequence of Events
- Cold Explosion -- 9 April 1984 Near Kurils, and formation and growth of spherical shell (globe)
  What They Were
- Cold Explosion -- 9 April 1984 Near Kurils (Plus additional weapons effects)
- Countering Insane MAD Systems:
  Find Loophole, Exploit It
- Next Generation Counter to Both Sane and Insane MAD systems
- Simultaneous Dudding of Nuclear Weapons Worldwide

- Simultaneous Dudding of Nuclear Weapons Worldwide
- Operation Divine Wind II
- Advanced EMBW Applications
- EM Biological Warfare (EMBW)
- Microwave Radiation of U.S. Embassy in Moscow
- Pentagon EMI Studies, 1989
- EM Missile Practice (6 slides)
- Subdivisions of Soviet Energetics Program
- Communism's Goal
- Manuilsky's Goal vs. Status Today (Dec. 1996)
- Professor Hellman, German Scientist Released from Work in Soviet Union
- Hemispheres and Globes of Light (4 slides)
- How Could Such Superweapons Ever Be Concealed?
- Soviets Easily Concealed These Superweapons for Four Decades
- Microscope-type, laser-like interferometer for inducing quick α-decay in samples of otherwise longer-lived isotopes
- Longitudinal Wave Interferometry: Endothermic

- Longitudinal Wave Interferometry: Exothermic
- U.S. Air Attack on Libya, April 1986
- Lightning Wall
  circa 1959-1960
- Lisitsyn's Report: Brain Code Broken
- Large Longitudinal Wave Interferometer (LWI) Accident
- Large Longitudinal Wave Interferometer (LWI) Accident
- Use of Hidden Information Content of the Field Can Provide Action-At-A-Distance
- Two Types of Mutual Assured Destruction (MAD) System
- Psychoenergetics Weapons Teams Mentally Disable All Personnel
- Strikes Against Special Ship and Energetics Weapons Sites
- "Mindsnapper" Attack on Special Ships and Energetics Weapons Sites
- How Much Off Guard Are We?
  (7 Slides)
- Possible Targets: 1995-9 Escalation Phase
- Propagation of Weapon Effects
- Yugoslav Earthquake, Followed by Cold Explosion
  April 15th, 1979

- Countering an Insane QP Weapon
- Gulf War Disease: KGB QP Weapon Induced ST Curvature Engines for a Cocktail of Diseases
- Self-Targeting in Inner EM Channel Can Produce a Quantum Potential
- Mechanism for Producing a Quantum Potential
- Major Principles for Use of Quantum Potential Weapons
- Major Principles for Use of Quantum Potential Weapons (2)
- Instantaneous Communication by a Quantum Potential
- Participants in a quantum potential share a common multiply-connected spacetime (MCST)
- Quake in Tangshan, China
  28 July, 1976
- Exchanging Earthquakes
- Instant Communication by a Quantum Potential
- Westerners Do Not React to Slow Threats
- Characterizing a Given Risk or Risk Factor
- Technical Risk Management
- Aum Shinrikyo's Sarin Facility

- In Scalar Beam Interference Zone
- Physicist Schappeller Auralaz Munster, Austria
- Initial Soviet Plan for Cold War, After WWII
- Josef Stalin: Absolute Dictator
- Exploding any Resistance by Operational Scientists
- Significant Soviet Statements
- Captain Svoboda Dives Headlong to Her Death
- T-polarized Beam Projector
- Possible Tests (1)
- Possible Tests (2)
- Possible Tests (3)
- Possible Tests (4)
- Mushroom Cloud Rising From Sea
- Launches from Cape Canaveral and Vandenberg AFB Provided Practice Targets of Opportunity
- The sinking U.S.S. Thresher, with her controls jammed, implodes when she reaches crush depth
- Embodiment of an instrument array sufficient to discriminate when time-density charging has occurred, and that transduction

of time-charge decay has occurred.

- Time-Polarized EM Wave Interferometer Creating Space-Time Curvature Engines in a Distant Interference Zone
- Transmutation of Radioactive Nuclei at a Distance
- Transmutation of Radioactive Nuclei
- Typical Tesla Shield, Northern Route of Japan
- A Curious Tide in Human Affairs
- Large Scalar EM Interferometer (LASI) Accident Near Urals, 1958
- The Superpower Paradox: Asymmetric Cheap WMD Strategic Strike and Destruction
- The KGB/Yakuza-Aum War Plan
- Why Western Science is Ignorant of KGB Energetics
- Transmutation of Radioactive Nuclei at a Distance
- TheYakuza
- Yugoslav Earthquake, Followed by Cold Explosion
  April 15, 1979

---

* Note that the Secretary did not speak the words in square blocks; these were added by the writers later,

probably to "soften the tone" of the Secretary's information release. So the Secretary confirmed that some nations of the world -- not just some ragged terrorists, as the writers tried to imply for spin control -- do possess novel electromagnetic weapons and are using them to induce earthquakes, engineer the weather and climate, and trigger volcanic eruptions.

THE COMING STRATEGIC ATTACK ON THE UNITED STATES

By an AUM/Yakuza/KGB/Communist Coalition Using Energetics SuperWeapons

T.E. Bearden, LTC
U.S. Army (Retired)
M.S. Nuclear Eng.
Fellow Emeritus, AIAS

With Technical Background and History of Energetics Weapons

Partial support by the Association of Distinguished American Scientists is gratefully acknowledged.d

© 1995, 1996, 1999 T.E. BEARDEN



Outline

- Background: Classical Electromagnetics (and Defects)
- Background: Energetics (Scalar Electromagnetics)
- Background: Soviet Energetics Weapon Development
- KGB/Communist Plans
- Countering of Soviet/KGB/Communist Plan in Mid-80s
- Soviet Economic Collapse and Adaptation of Plan
- Weapons Bleed-Out: KGB/Russian Mafia
- Yakuza: The Japanese Mafia
- Aum Shinri Kyo (Supreme Truth) Cult
- Coalition: Aum/Yakuza/KGB/Communists/Russian Mafia
- Operation Divine Wind II: Three Phases
  - Phase I: On-Site Training Phase (Completed)
  - Phase II: Escalation Phase (In Progress)
  - Phase III: 1997 Strategic Strike on the United States
  - Support Plan A: Feints, Deception, Sabotage & Terrorism
  - Support Plan B: Test Range
  - Support Plan C: Worldwide Weather Engineering
  - Support Plan D: Strategic and Combat Intelligence
- Special Information
- Recommended Actions

© [illegible], [illegible] T.E. BEARDEN

The Tom Bearden Website

Help support the research

Loss of two separate A-10 Warthogs in 1997

- A-10 Mysterious Flyaway and Crash - April 2, 1997
- Death of Second A-10 Pilot - May 27, 1997
- Captain Button's Mysterious Flyaway and Eventual Crash
- Death of Second A-10 Pilot - May 27, 1997



A-10 Mysterious Flyaway and Crash

April 2, 1997

UTAH
COLO.
1:40 p.m. Vail
Area enlarged
Denver
70
1:22 p.m. Aspden
1:05 p.m. Tellunde
Pueblo
12:53 p.m. Cortez
ARIZONA
N
11:58 a.m. Breaks Formation near Goldwater Range
12:20 p.m. Young
NEW MEX.
10
Phoenix
Lake Roosevelt
12:11 p.m. Apache Junction
8
Barry M. Goldwater Air Force Range
DEPARTS
10:30 a..m. Tucson
Tombstone
0 100
Miles
Eagle
Edwards
Vail
70
COLO.
Glenwood Springs
Hardscrabble Range
New York Mountain
Sawatch Range
24
82
Flight path
Aspden
0 5
Miles
N
Leadville

Armed with:

- Four 500-lb bombs
- 30 mm Gatling gun



Death of 2nd A-10 Pilot May 27, 1997

- Captain Amy Svobody
- Night training mission
- From Davis-Montham AFB
- From same wing as Captain Button, who flew his A-10 off course for over an hour and then crashed on April 2.
- Climbout from ordnance delivery on target
- Nosed down sharply and dived into ground

Companion A-10's

- Experienced night flyer & instructor
- Nosed sharply over and flew into ground
- Psychoenergetic kill

© T.E. BEARDEN 1999

Psychoenergetic weapon induced instant hypnogogic state and reversed Svoboda's sense of up and down.

A-10 Mysterious Flyaway and Crash

April 2, 1997

Armed with:

- Four 500-lb bombs
- 30 mm Gatling gun


UTAH
COLO.
Area enlarged
1:40 p.m.
Vail
1:22 p.m.
Aspden
1:05 p.m.
Telluride
12:53 p.m.
Cortez
ARIZONA
11:58 a.m.
Breaks Formation
near Goldwater Range
12:20 p.m.
Young
NEW MEX
12:11 p.m.
Apache Junction
Barry M. Goldwater
Air Force Range
DEPARTS
10:30 a.m..
Tucson
Tombstone
Eagle
Vail
Glenwood
Springs
COLO.
Hardscrabble
Range
New York
Mountain
Sawatch Range
Flight path
Aspden

Figure 14a. Captain Button's mysterious flyaway and eventual crash.



Death of 2nd A-10 Pilot May 27, 1997

- Purpose: Stimulate U.S. in same area again
- Determine if U.S. aware of psychoenergetics
- U.S. showed it is completely unaware

- Captain Amy Svoboda
- Night training mission
- From Davis-Montham AFB
- From same wing as Captain Button, who flew his A-10 off course for over an hour and then crashed on April 2.
- Almost certainly a second psychoenergetics strike

- Experienced night flyer & instructor
- Nosed over and flew into ground
- Probable kill using psychoenergetics

Psychoenergetic strike induced an instant hypnogogic state, shifted pilot's sense of up and down. Svoboda corrected and "climbed out" after target attack, and flew into ground, dream-perceiving down was up.

© T.E. BEARDEN 1997


Typical ABM Defenses
(WIDELY DEPLOYED BY MID-70's)
GLOBAL SHELL (MIDCOURSE ELECTRONICS DUDDING)
INTENSE ENERGY SHELLS (Destruction of vehicle) (Initiation of nuclear warheads)
© T.E. BEARDEN 1999
EM MISSILES
EARTH'S SURFACE
ENERGETICS HOWITZER
TRACK
LAUNCH PHASE DEFENSES
(NESTED) HEMISPHERICAL SHELL(S) (Dudding, initiation, destruction)
TERMINAL DEFENSES



LAUNCH PHASE ANTIMISSILE SYSTEM

IONOSPHERE

PHASE
CONJUGATE
REPLICA
(MAY BE HIGHLY
AMPLIFIED)

NORMAL
RADAR
RETURN

EARTH'S SURFACE

STRATEGIC
BALLISTIC
MISSILE
AT IGNITION

GIANT
ENERGETICS
TRANSMITTER
RECEIVER
SYSTEM

SOME OPERATIONAL MODES:

- SIMPLE TRACKING
- PHASE CONJUGATE TRACKING
- ENGINE COMBUSTION COOLING
- EMP INSERTION
- ELECTROMAGNETIC MISSILE STRIKE
- ELECTRICAL INTERFERENCE
- METAL LATTICE SOFTENING
- ANTI-WARHEAD
- GLOBAL SHELL
- HEMISPHERICAL SHELL
- MULTIPLE SIMULTANEOUS TARGETS
- MULTIPLE SIMULTANEOUS MODES

© T.E. BEARDEN 1996



LAUNCH PHASE ANTI-BOMBER SYSTEM

IONOSPHERE
PHASE CONJUGATE REPLICA (MAY BE HIGHLY AMPLIFIED)
EARTH'S SURFACE
NORMAL RADAR RETURN
STRATEGIC BOMBER OR OTHER A/C TAXIING, OR TAKING OFF
GIANT ENERGETICS TRANSMITTER RECEIVER SYSTEM

SOME OPERATIONAL MODES:

- SIMPLE TRACKING
- PHASE CONJUGATE TRACKING
- ENGINE COMBUSTION COOLING
- EMP INSERTION
- ELECTROMAGNETIC MISSILE STRIKE
- ELECTRICAL INTERFERENCE
- METAL LATTICE SOFTENING
- ANTI-PERSONNEL
- ANTI-ORDNANCE
- GLOBAL SHELL
- HEMISPHERICAL SHELL
- MULTIPLE SIMULTANEOUS TARGETS
- MULTIPLE SIMULTANEOUS MODES

© T.E. BEARDEN 1996



HC-130's ENGINES QUIT, AIRCRAFT CRASHES

At 4 miles altitude,
all four engines quit,
one after the other

Routine night training mission
80 miles off Calif Coast
Crew of 10 and 1 passenger
1 survivor

Compare to China Airlines Flight 006, 19 Feb. 1985 off San Francisco, bound from Taipei to Los Angeles

Nov. 22, 1996

(c) T.E. BEARDEN 1997

PROBABLE ENDOTHERMIC SUPERPOTENTIAL INTERFEROMETRY
(Apparently all 4 engines have never before failed on an HC-130)



CTEC PROPRIETARY

1996 Actions by this analyst

- In July 1996, with the kill of TWA-800 it became apparent that the KGB/Communists were preparing a massive strategic energetics attack upon the U.S.

© T.E. BEARDEN 1997

- Began intensive, nearly round-the-clock effort to uncover what was happening, and what had occurred in KGB/Com weapons since 1991
- Began preparing full-up set of briefing slides simultaneously
  - In early 1996, had briefed J6 on scalar EM, per his request
  - Had strongly suggested a follow-on weapons brief
  - Adamant opposition by NRL, NOL, others
- Similar energetics attack scenario in 1986 was countered. Soviets at that time did not possess operational QP weapons, and so could not successfully overcome dead-man fuzing
  - Also could not dud nukes worldwide, because QP required.
  - First lab prototype QP test was in April 1986
- KGB had solved the dead-man fuzing problem by QP's. Deployed circa 1989-1990. Some earlier weapons then leased.



Additional Information Exists; Not Analyzed, Not Integrated in Briefing

- Yakuza arranged involvement of
  - Red Chinese
  - North Koreans
  - A Taiwanese element
- Aum Shinrikyo may have been used as "Red Herring" to deceive West
- Oriental faction plots to strike Russians after the successful first strike on West
- KGB/Russians aware, will counter
  - Plan pre-emptive strike against Oriental faction first
  - Have reserved most advanced, powerful energetics weapons for that purpose

The Tom Bearden Website

Help support the research

Kill of Arrow DC-8, Gander AFB, Dec. 12, 1985

- Slide 1
- Slide 2
- Slide 3
- Slide 4
- Slide 5
- Slide 6



KILL of ARROW DC-8

Gander AFB, Dec. 12, 1985

- Soviet EM missile weapon strike practice two weeks earlier at Cape Canaveral
  - Offset from night shuttle launch
  - EM missile photographed by Bob Gladwin
  - Associated marker beacon photographed
- Canadian Board split on findings
  - Half thought icing, half disagreed intensely
  - "Due to icing" approved with half absent
  - Separate dissenting finding issued
- U.S. officials hiding Iran/Contra affair
  - Feared terrorist bomb, MidEast sponsor
  - Pressured Board, Gen. Off. bulldozed site
- Lack of icing on aircraft later validated



KILL of ARROW DC-8
Gander AFB, Dec. 12, 1985

- Eyewitness observed beams form in the sky
- Saw streak-down and strike of EM missile
  - Struck right fuselage ahead of the engines
  - Hole was burned through fuselage there
  - Photo of hole published in AW&ST
  - No explosive residues on hole
- Consistent with ignition and outgassing of plastics in forward cabin
- Consistent with pre-crash HCN deaths



KILL of ARROW DC-8
Gander AFB, Dec. 12, 1985

- Combustion cooling reduced thrust during runup
- Emulated reducing specific thrust by icing
- Struck with EM missile, at liftoff
  - Hole in right fuselage, ahead of engines
  - Not normal explosion; no material ingested
  - EM missile explosively ignited plastics in forward cabin; outgassed poisonous HCN
  - *Autopsies: Half the passengers died from HCN inhalation before plane crashed*
  - Data recorders recorded vertical spike of hit
- Materials handlers later mysteriously sickened, with symptoms of longitudinal EM radation induced illness



KILL of ARROW DC-8
Gander AFB, Dec. 12, 1985

- Combustion cooling reduced thrust during runup
- Emulated reducing specific thrust by icing
- Struck with EM missile, at liftoff
  - Hole in right fuselage, ahead of engines
  - Not normal explosion; no material ingested
  - EM missile explosively ignited plastics in forward cabin; outgassed poisonous HCN
  - *Autopsies: Half the passengers died from HCN inhalation before plane crashed*
  - Data recorders recorded vertical spike of hit
- Materials handlers later mysteriously sickened, with symptoms of scalar-EM radiation induced illness
- *Eye witness observed formation and strike of the electromagnetic missile*



KILL of ARROW DC-8
Gander AFB, Dec. 12, 1985

- Soviet EM missile weapon strike practice two weeks earlier at Cape Canaveral
  - Offset from night shuttle launch
  - EM missile photographed by Bob Gladwin
  - Associated marker beacon photographed by George Suchary
- Canadian Board split on findings
  - Half thought icing, half disagreed intensely
  - "Due to icing" approved with half absent
  - Separate dissenting finding issued
- U.S. officials hiding Iran/Contra affair
  - Feared terrorist bomb, MidEast sponsor
  - Pressured Board, Gen. Off. had site bulldozed
- Lack of icing on aircraft later validated

Death of the Arrow DC-8


Dec. 12, 1985
Gander, Newfoundland
ENGINE THRUST IS REDUCING
AIRCRAFT GLOWING (THRUST REDUCED)
FUEL EXPLOSION
KINDLING (SELF-TARGETING)
EM MSL STRIKE (MULTIPLE INSTRUMENT SPIKES)
CYANIDE INHALATION
TAIL-DOWN CRASH
ELECTROSTATIC COOLING OF ENGINE COMBUSTION
EXPLOSIVE PLASTICS IGNITION, FIRE, OUTGASSING
ABOUT ONE-HALF THE OCCUPANTS DIE
GRAVITON RADIATION DECAY (EXPOSURE OF RECOVERY PERSONNEL TO LONGITUDINAL EM WAVE RADIATION
GRAVITON CHARGING OF ATOMIC NUCLEI
HIGHLY CHARGED PULSE INTO ATOMIC NUCLEI



Satellite Photos of Plumes in Soviet Arctic Since 1974*

- Two aircraft flew through for analysis
  - Solid material, mostly ice, a little clay
  - Much colder than surrounding air
  - *Signature of cold exhaust from exothermic scalar interferometry operations*
  - No volcanic material
  - No radioactive material
- May be 2 to 3 times as many incidents
  - Only examined satellite imagery in winter
  - Only periodic satellite coverage
  - Hypothesized methane venting, cloud seeding

© 1996 T.E. BEARDEN

*As of 1989, when this information was gathered

AUM SHINRIKYO

("SUPREME TRUTH" CULT)

Shoko Asahara, Leader

© 1995, 1998 T.E. BEARDEN



Ashkhabad Problem and Its Solution

- ***PROBLEM:***
  - Stress increasing in two-plate fault zone
  - 1,000 shocks yearly
  - Kara Kum canal
  - Hydraulic pressure
  - 1948: Ashkhabad 80% destroyed by quake
- ***SOLUTION:***
  - Stress-relieve plate stresses from fault
- ***IMPLEMENTATION:***
  - Induce nearby earthquake
  - Deceive by *predicting* a quake, setting off nuclear explosion

© 1996 T.E. BEARDEN



Strange Characteristics of Iran Quake, Sep. 1978

© 1996 T.E. BEARDEN

- Signatures
  - 7.4 on Richter scale
  - No aftershocks: 6.0 expected (normal)
  - Strange epicenter
  - Anomalous depth
- Deception
  - 10 MT Soviet nuclear explosion 36 hours before the quake
  - Prior disinformation regarding Soviet attempted development of focusing shock waves from underground nuclear explosions, to cause distant earthquakes



Iran Earthquake
Sept. 1978

- Killed 25,000 Iranians
- Soviet city of Ashkhabad saved
- Soviets "predicted" quake in advance; then induced it
- Quake had serious anomalies (signatures)
- Deception measures were used by Soviets
  - Prediction in advance
  - "Theory" of quake-induction by nuclear explosions
  - Fired underground nuclear explosion as "Red Herring" candidate for cause

© 1996 T E BEARDEN



Situation Now (Assessment)

- In May 1997: second A-10 pilot (lady), in pullup from night ordnance delivery on target, was struck with psychoenergetic weapon takeover. Sense of vertical was reversed. She perceived herself diving, sharply corrected, and dove headlong into the ground.
- Additional aircraft kills uncovered, including one 4-engine aircraft whose engines all failed. This closely repeats the earlier 1985-1987 scenario.
- Korean Airlines Flight 801 crashed on Guam on anniversary of loading of the atomic bomb that was dropped on Hiroshima in WW II. The Enola Gay, which dropped the bomb, took off from Guam in wee morning hours of August 6, 1945. The local opns order on Guam was also issued on Aug. 5.
- *Presently the Coalition (KGB/Communists/Aum Shinrikyo/Yakuza) is waiting for proper time to launch the final strike. It is still on.*



Situation Now (Assessment 2)

- April 97: Mind control test against Captain Button:
  - Demonstrates ability to control crewman in complex operations for more than one hour.
  - KGB requires one hour total QP crew control on a site to have crew disable insane QP wpns.
- Once QP systems disabled, Mindsnapper attacks and instantly kills every living thing in QP site area. Contaminates area for months (emits longitudinal EM wave radiation, which disrupt any life forms attempting to enter struck area). Sites nullified.
- Mind control over one crewman requires one weapon system plus up to 20-30 operators for controlling thoughts, hearing, perceptions, etc.
- *In Apr. 97, KGB building and deploying weapons and training crews. Ready for new attack 1999-2000.*



Aspects of Strong Local Asymmetry

- If local asymmetry is strong, conservation laws may be appreciably violated
  - Energy
  - Charge
  - Spin
  - Momentum
  - Angular momentum
- Properties of an object may differ appreciably for
  - Different observers
  - Different detecting means
  - One time to another
  - One position to another

© T. E. Bearden 1995, 1996



Mass Casualty Problem: Aerial Anthrax Spray on Washington, D.C.

- **One terrorist, one light aircraft with spray tank**
- **One kilogram of anthrax**
- **Flies over greater metropolitan Washington, D.C.**
- **Calm night**
- ***1-3 million casualties result****
- ***Most of those stricken will die***
- **Presently little can be done to save the stricken civilians**
- ***Attacks on several population centers might produce some 10 million or more casualties***

© 1998 T.E. BEARDEN

*Per OTA Report to Congress, 1993



Present Status of the WMD Threat to the United States

- Many foreign nations are hostile to the U.S. and sponsor terrorists
- Some 25 nations have WMD or are acquiring them
  - BW agents and weapons
  - Chemical agents and weapons
  - Nuclear materials and weapons
- Thousands of students and émigrés
- Infiltrated teams, BW, other WMD already
- Castro guerrillas infiltrated over the years
- Can do unacceptable damage to U.S. now
- ***May reach first strike knockout capability***

© [illegible] T.E. BEARDEN

*Per OTA Report to Congress, 1993



Some Present Problems in the U.S. WMD Defense Capabilities

- *No shelters (require overpressure, BW filtering, masks, showers, supplies)*
- *No stockpiled vaccines, medical supplies, immunoglobulins, masks, suits, food, fuel, generators, heaters, water purification units*
- Totally insufficient medical facilities, personnel, and emergency response teams
- Triage, full martial law will be required
- *No answer to massive decontamination problem*
- State, county, city inadequately staffed and insufficiently trained for mass casualties
- Terrorist teams, BW agents, other WMD on site, waiting
- Water supplies, food, crops, farm animals also vulnerable
- Electric power grid, bridges, trains, railroads vulnerable
- *Present medical science cannot save very many of the casualties, now or in the foreseeable future*

© [illegible] T.E. BEARDEN



Internal Terrorist Threat with Weapons of Mass Destruction: Now & Future

TODAY:

- Sabotage
- Chemicals
- Biological agents
- Nuclear materials
- Powerful explosives
- Assassination
- Kidnapping and hostages
- Contamination
- Shoulder-fired AD missiles
- Terrorism

FUTURE ADDITIONS:

- Orthodox EM weapons
- Energetics EM biological warfare
- Scalar EM (energetics) weapons
- Scalar EM disease induction
- Alteration of behavior and emotions
- Alteration of memory
- Direct control of thoughts, perception
- Quantum potential weapons
- Psychoenergetics weapons
- Action-at-a-distance effects

© [illegible] T. E. BEARDEN



Attempt to Ban Energetics Weapons Worldwide

- On June 13, 1975, in a major speech Brezhnev urged the United States to agree on a ban of research and development of new kinds of weapons "more terrible than anything the world has known."
- On July 2, 1975 Brezhnev repeated his proposed ban on development of frightful new weapons, to a group of U.S. Senators.
- In August 1975, Ponomarev called for a ban on frightful new weapons of mass destruction.
- On Sept. 23, 1975 Gromyko presented a draft treaty agreement to the 30th Session of the UN General Assembly, for banning development of frightful new weapons.
- ***No one had the foggiest notion what the Russians were talking about!***

© 1996 T.E. BEARDEN



Brezhnev's Schedule

"We are achieving with detente what our predecessors have been unable to achieve with the mailed fist..
...by 1985 our power will be so irresistible that we can do what we wish anywhere on the globe."

Leonid Brezhnev,
in a secret 1973 meeting in Prague
with European Communist leaders.

"By the early 1980's we and our allies will control the high seas, space, and most of the earth's land area."

Kosygin,
to Imelda Marcos,
July 1978

In 1985-87, the Soviets did attempt to move, still constrained by nuclear dead man fuzing. That attempt was blocked, primarily by scalar EM countering demonstrations and dead man fuzing.

In April 1986, the first Soviet lab prototype of a quantum potential weapon specifically designed toward 10-min neutralization of nukes worldwide was gingerly tested against our U.S. airstrike on Libya. It was weakly tested in the "induced EMI" mode, for deception.

By 1990 that weapon was deployed and a new attack preparation phase was entered, scheduled for 1997.

© 1996 T.E. BEARDEN





COLD EXPLOSION -- 9 April 1984 Near Kurils

And Formation and growth of spherical shell (globe)

not to scale

centerline
380 miles diameter
200 miles
expansion
© T.E. BEARDEN

Sequence of Events

- Geyser of water rose rapidly from surface, mushroomed out
- Reached 60,000 feet altitude in two minutes
- Brilliantly glowing globe then appeared in top
- Globe increased greatly in size and altitude
- Reached diameter of 380 miles
- Center reached altitude of 200 miles
- Observed by multiple qualified pilots


not to scale
centerline
380 miles diameter
200 miles
expansion
© T.E. BEARDEN 1999

COLD EXPLOSION -- 9 April 1984 Near Kurils

And Formation and growth of spherical shell (globe)

What They Were

- Superpotential interferometry using LWs
- First, a cold explosion just above surface
- Then small intense shell of glowing EM energy for 1-on-1 targeting
- Larger globe for large area as for ICBM targets approaching in zone
- With ST engines, can dud incoming nukes and all electronics
- Use in or out of Earth's atmosphere



COLD EXPLOSION -- 9 April 1984 Near Kurils (Plus additional weapons effects)

Halo expanded to giant globe.
380 miles diameter, center over 200 miles high.

© T.E. BEARDEN 1996



Countering Insane Mad Systems: Find Loophole, Exploit It

- *If MADs not quantum potential systems, easily countered by instant QP strike which destroys targeted MAD weapons worldwide with certainty.*
- *Have to be certain of types of dead-man fuzing. All dead-man fuzing weapons must be included in the assured target list for the striking quantum potential weapon.*

© 1995, 1996 T.E. BEARDEN

- *Multiple targeted MADS require multiple vacuum engines in the striking quantum potentials.*
- *Uncertainty and risk introduced if not certain of all MAD systems and all dead-man fuzing systems.*
- *Newest generation psychoenergetic LW interferometry weapons can instantly take over minds of all personnel on targeted sites, with targeted crews quickly disarming their own MAD weapons' launch capability as well as the weapons themselves.*
- *Mindsnapper then kills all living things and contaminates sites.*
- *Next generation QP Psy-En weapons can disrupt and destroy minds of an entire targeted national population. The nature of warfare moves irrevocably to the human mind, where of course the fundamental problem arises anyhow.*



Next Generation Counter to Both Sane and Insane MAD Systems

- *Localized quantum potential in an area, used in psychoenergetics mode*
  - Gradually produces mild, continuous hypnotic state
  - Targeted population remains entirely conscious, functional
  - Internal "word thoughts" emerge directly in subconscious
  - Targeted persons all unaware of these "word thoughts"
  - Operates somewhat similar to "post hypnotic suggestion"
  - Gradually changes emotions, psychological outlook
  - Over a period of time, deviates and entrains entire target population's outlook, belief structure, temperament
- *Moves Psywar to inside the human component*
- *Human minds are the only battleground*
- *Can be accomplished without overt signature*
- *Countered only by inserting same methodology into deeper mind level (collective unconscious)*



Simultaneous Dudding of Nuclear Weapons Worldwide

- Via quantum potential joining U235 and Plutonium in warheads
- Includes weapons airborne, underwater, in storage
- These are *transmutations of the nuclides themselves*
- *Part of the initial barrage launched by Aum/Yakuza/KGB*
- *Will occur in the first minutes of the strategic strike, following psychoenergetically crew-disabling QP weapons*

Note: Duds both overt and covert nuclear weapons and weapons-grade materials -- including "suitcase-delivered" covert weapons on site in Russia which otherwise provide dead man fuzing

© T.E. BEARDEN 1996



Simultaneous Dudding of Nuclear Weapons Worldwide

- Via quantum potential joining U235 and Plutonium warheads
- Includes weapons airborne, underwater, in storage
- These are not explosions, but are ***transmutations and increased fissioning rates***
- *Part of the initial barrage launched by Aum/Yakuza/KGB*
- *Will occur in the first minutes of the strategic strike*

© T.E. BEARDEN 1996

Note: Duds both overt and covert nuclear weapons and weapons-grade materials.

The Tom Bearden Website

Help support the research

Operation Divine Wind II

Slide 1

Slide 2

Slide 3

Slide 4



YAKUZA &
AUM SHINRIKYO

U.S.

DIVINE WIND II

- ★ **A secret coalition of Yakuza/Aum Shinrikyo and KGB/Communist forces plan to launch a massive, surprise energetics attack on the United States, given a low-risk opportunity.**
- ★ Major weapons utilized will be the scalar EM (energetics) superweapons (including quantum potential weapons) that were developed, deployed, and operated by the KGB under the former Soviet Empire, and continuing after its dissolution.
- ★ Yakuza/Aum crews have extensively trained and test-fired, from on-site in Russia. They have *leased* operational control of the first three generation energetics superweapons (which work by superpotential interferometry).
- ★ *The Escalation Phase of interdicting and destroying actual U.S. targets (e.g., TWA-800, two A-10s) is already underway.*
- ★ *The first blow in the Strike Phase will dud all nuclear weapons and weapons materials worldwide, in minutes; destroy special ship and energetics weapon sites instantly, disable 99% of the U.S. population instantly, and kill 80% of targeted populations in from 10 minutes to 3 days.*

KGB

MINDSNAPPER AND PSYCHOENERGETICS

QUANTUM POTENTIAL

© 1995, 1996 T.E. BEARDEN



YAKUZA &
AUM SHINRIKYO

U.S.

DIVINE WIND II

- ★ A secret coalition of Yakuza/Aum Shinrikyo and KGB/Communist forces plans to launch a massive, surprise energetics attack on the United States and its allies, given the first low-risk opportunity.

© 1995, 1996, 1999 T.E. BEARDEN

KGB

- ★ Attack was thwarted twice in 1997 by a small nation countering with QP weapons.
- ★ KGB psychoenergetics counter for the last QP weapon counter was tested in April 1997.
- ★ Ready time for a new scheduled attack is latter quarter 1999 through first half of 2000.



YAKUZA &
AUM SHINRIKYO

U.S.

DIVINE WIND II

© 1995, 1996 T.E. BEARDEN

★ **A secret coalition of Yakuza/Aum and KGB/Communist forces will launch a massive, surprise, strategic attack on the United States in 1997.**

★ Major weapons utilized will be the scalar EM (energetics) superweapons that were developed, deployed, and operated by the KGB under the former Soviet Empire, and continuing after its dissolution.

★ Yakuza/Aum crews have extensively trained and test-fired, from on-site in Russia. They have *leased* operational control of the energetics superweapons.

★ *Escalation Phase of interdicting and destroying actual U.S. targets (e.g., TWA-800) is already underway.*

★ *The first blow in the Strike Phase will dud all nuclear weapons and weapons materials worldwide, in minutes; destroy special ship and energetics weapon sites instantly, and kill 80% of targeted populations in 3 days.*

KGB/COMMUNISTS

MINDSNAPPER

QUANTUM POTENTIAL



OPERATION DIVINE WIND II

Three Phases and Support

Operational Phases

- Phase I: On-Site Training Phase (Completed)
- Phase II: Escalation Phase (In Progress)
- Phase III. 1997 Strategic Strike on the U.S.
  - *First strike (QP) in Phase III duds all nuclear weapons and nuclear powerplants worldwide, in minutes*
  - *Psychoenergetic strike (QP) disables people instantly*
  - *Mindsnapper attack of special assets for 100% success*
  - *QP initiation of fast-acting, lethal diseases kills 80% of targeted populations in three days or less*

Support Plans

- Plan A: Feints, Deception, Sabotage, and Terrorism
- Plan B: Testing and Test Range
- Plan C: Worldwide Weather Engineering
- Plan D: Strategic and Combat Intelligence

© 1995, 1996 T.E. BEARDEN



Advanced EMBW Applications

- Covert EMBW: Examples
  - Activate materials and their potentials with ST disease engines. Potentials superpose and their infolded ST dynamics diffuse
  - Activate water's structuring (H-bonding) potential with disease engines
  - Bias electrical power grid ground fields by weak diseases
  - Employ disease-structured quantum potential in distant area
- Overt death ray (mind snapper)
  - Powerful scalar EM pulse in target area "jerks" rate of flow of time
  - The "time snap" sharply separates mind from body and each cell
- EMBW CM:
  - Irradiate bodies with longitudinal EM waves; self-converts to t-pumping and produces exact amplified ST antiengine
  - Antiengine arises out of local ST, affects all parts of all cells
  - Cells are t-charged with antiengine structure
  - Continuing action restores regenerative and immune systems and reverses cellular damage

© T.E. BEARDEN 1995, 1999



EM Biological Warfare (EMBW)

- KGB/Communists have developed highly effective
  - Electromagnetic biological warfare (EMBW)
  - Counters to orthodox biological warfare
  - Mass death ray weapons
    - Small version of "mindsnapper" tested in Afghanistan
    - Killed occupants in two villages, in separate strikes
    - Unusual aspects (so-called "smerch" gas)
- Russia/KGB is the only group with a complete counter to biological warfare, either covert or overt, and to EMBW
- EMBW (covert and overt) is a preferred option for KGB
  - MAD Doctrine is completely destabilized for a sufficiently covert Russian EMBW strike
  - Situation has existed for at least two decades
  - Can alter germs, bacteria, viruses of specific kind, in a specific target area, to produce antibiotic-resistant strains
  - Can induce any kind of cellular disease or damage at a distance
- U.S. national characteristic: no reaction to slowly increasing threat

© T.E. BEARDEN 1999



Microwave Radiation of U.S. Embassy in Moscow

Former U.S. Embassy in Moscow.

BACKGROUND

- Began in latter 1950s
- Discovered on VP Nixon's trip
- Initially thought to be *nuclear* radiation (Discovered w/Geiger counter?)
- High level target -- U.S. Ambassador
- Guarantees personal attention of:
  - U.S. Ambassador to USSR
  - U.S. President
  - NSA, CIA, DIA, NSC, etc.
  - Top consulting scientists
  - Leading U.S. scientific institutions
- Two U.S. Ambassadors died, another sickened
- Anomalous health changes in personnel, only in zero-field (zero pot'l gradient) areas!
- Four U.S. Presidents requested Soviets cease
  - Cut from 18 watts/sq cm to 2
  - Then again increased
- No one could understand what was going on
- Aluminum screens were placed over windows
- Moscow was declared a hazardous duty zone

© 1995, 1996 T.E. BEARDEN



Pentagon EMI Studies, 1989

Washington Post, 22 Jan. 1989, p. A4

- Analysts of severe EMI effects in strike on Libya, 1986
  - performed major 3-year, 66-man study
  - Blamed effects on U.S. forces' own signals
  - Did not know of any other "signals" present
  - Knew nothing of quantum potential weaponry, energetics weaponry
- 7-month preliminary study
  - Severe EMI Problem exists
  - EMI shielding often waived in our weapon systems
  - Thousands of conflicts possible
- Also studied UH60 Blackhawk helicopter problems (which *were* due to its lack of good EMI shielding, and not quantum potentials)
  - uncommanded turns
  - Five EMI crashes 1982-1989
  - $175 M program to shield it
- So found that U.S. transmission combinations can
  - Affect aircraft flight control
  - Turn off fuel supply
  - Cause uncommanded dive/turn
  - Bring down U.S. warplanes
- *Actually, Libyan EMI was induced by Soviet quantum potential tests which can do all those things and much more*

© 1996 T.E. BEARDEN

The Tom Bearden Website

Help support the research

EM Missile Practice

- EM Missile Practice
  Latter Sept. - Early Nov. 1996
  Melbourne, Australia

- Deception: Using EM Missile to Reinforce Notion of SAM Attack
  Saturday evening, Nov. 16, 1996

- Intelligence Probe: Insuring U.S. Still Unaware of Energetics Weaponry
  Thursday, December 12th, 1996

- EM Missile Strike, Offset from Night Shuttle Launch, Cape Canaveral, Florida
  The Smoking Gun in November 1985

- Distant Operator Onsite in Russia Slew Away Registration Point
  Marker Beacon over Night Shuttle Launch, 26 November, 1985

- EM Missile Practice and Deception
  November 17, 1996



EM Missile Practice
Latter Sept.-Early Nov. 1996

(Multiple Nights, Multiple Streaks Each)

(Many Witnesses)

© 1996 T.E. BEARDEN
~ 500 meters (one case)

Melbourne, Australia
Australian Associated Press
Nov. 2, 1996



Deception: Using EM Missile to Reinforce Notion of SAM Attack

Saturday Evening
Nov. 16, 1996

Note: Meteor shower was forecast, which provided perfect decoy to FBI investigators, to steer them off the true scent.

Pakistan International Airlines Flight 712, just after takeoff from John F. Kennedy Airport, on path similar to that taken by TWA Flight 800, July 17, 1996

© T.E. BEARDEN 1996



Intelligence Probe: Insuring U.S. Still Unaware of Energetics Weaponry

Thursday
Dec. 12, 1996

Pilot sighted what he called
a "green flare".
No danger, no evasive action.

Saudi Arabian Airlines 747
en route from Riyadh, Saudi Arabia
to John F. Kennedy Airport.
At 12,000 ft., not far from where
TWA Flight 800 was killed on July 17, 1996

FBI: *"Probably a meteorite."*

© T.E. BEARDEN 1996

EM Missile Strike, Offset from Night Shuttle Launch

Cape Canaveral, Florida



EM MISSILE STRIKE
26 NOV 1985

(LIGHT DEVELOPMENT)

OFFSET FROM NIGHT SHUTTLE LAUNCH

PHOTO BY BOB GLADWIN

MARKER BEACON

Over Night Shuttle Launch
Cape Canaveral, Florida

26 Nov 1985
Photographed by George Suchary

© T.E. BEARDEN 1996, 1999,

EM MISSILE STRIKE
26 NOV 1985

(DARK DEVELOPMENT)

OFFSET FROM NIGHT SHUTTLE LAUNCH



The Smoking Gun in Nov. 1985



Distant Operator Onsite in Russia Slews Away Registration Point

© T.E. BEARDEN 1995, 1999.

MARKER BEACON

Over Night Shuttle Launch
Cape Canaveral, Florida

26 Nov 1985
Photographed by George Suchary

28 Nov 1985

Two weeks later, the same weapon killed the Arrow DC-8 at its takeoff from Gander, Newfoundland.



EM MISSILE PRACTICE AND DECEPTION

Nov. 17, 1996 at 2220 hrs.

Speed Bird 226

Lufthansa 405

Note: 4-month anniversary
of kill of TWA-800.
"Inside gloating" by
Aum/Yakuza/KGB.

Vicinity of Long Island, New York
Not far from where TWA-800 was killed
Two aircraft sighted object

(c) 1996 T.E. BEARDEN



Subdivisions of Soviet Energetics

NONLIVING SYSTEMS

Energetics

- Nonliving systems
- Scalar Interferometry
- Action-at-a-Distance
- Quantum Potential
- Vacuum Engines
- Spacetime Structuring
- Material, Field Effects
- Nuclei, Lattice Changes
- Hidden EM Variables
- SWZ Effects

LIVING SYSTEMS

Bioenergetics

- Living Systems (Bodies)
- Cells, cellular changes
- Master Cell Control (Popp)
- Spacetime Structuring
- Disease Induction, Remission
- Action-at-a-Distance
- Quantum Potentials
- Scalar Interferometry
- Hidden EM Variables
- SWZ Effects

Psychoenergetics

- Living Systems (Minds)
- Thoughts, Memories, Emotions
- Conscious/Unconscious Minds
- Spacetime Structuring
- Species, Biospheric Minds
- Action-at-a-Distance
- Quantum Potentials
- Scalar Interferometry
- Hidden EM Variables
- SWZ Effects

© 1996 T. E. BEARDEN



Communism's Goal

- "War to the hilt between communism and capitalism is inevitable. Today, of course, we are not strong enough to attack... To win we shall need the element of surprise. The bourgeoisie will have to be put to sleep. So we shall begin by launching the most spectacular peace movements on record. There will be electrifying overtures and unheard-of concessions. The capitalist countries, stupid and decadent, will rejoice to cooperate in their own destruction. They will leap at another chance to be friends. As soon as their guard is down, we shall smash them with our clenched fist."

Dimitry Z. Manuilsky
Lenin School of Political Warfare, Moscow
(circa 1934)

© 1996 T.E. BEARDEN



Manuilsky's Goal vs. Status Today

Manuilsky, 1934	Situation, Dec. 1996
■ War is inevitable.	■ Has not changed.
■ Not strong enough to attack now.	■ Strong enough now; preparations completed. Need right opportunity.
■ Need surprise.	■ Have achieved total surprise.
■ Must put us to sleep.	■ We are sound asleep.
■ Need most spectacular peace movement on record.	■ Done. We think the Russian threat gone, cold war ended.
■ Electrifying overtures, unheard-of concessions.	■ Done, and still occurring every day. It has worked beautifully.
■ Capitalists will cooperate.	■ We are cooperating in spades!
They will leap to be friends.	■ We've leaped, and are leaping.
■ They will let down their guard. ■	■ No ABM, junked lots of nukes, shrunk our forces to the bone.
■ We'll strike them then.	■ They would have struck (twice) in 1997, but for deterence by another nation (not U.S.) having QP weapons ■ *They are still looking for a risk-free opening to strike*

© 1996, 1997 T.E. BEARDEN



Professor Hellman, German Scientist Released from Work in Soviet Union

- Worked in Soviet Union after WWII
- Eventually escaped to Germany, then to Brazil (handsome offer)
- Took part in highly unusual Soviet energetics development and experiments
- Large areas of the sea could be and were *suddenly frozen*
- *No particular attention was paid to this information by highly qualified scientists*
- *In intelligence terms, this is A-1 information of the highest caliber*
- *Bohm also was invited to Brazil, which started an energetics weapon program. Brazil developed such weapons including weak quantum potential weapons (0.95 confidence)*

© 1996 T.E. BEARDEN

Hemispheres of Light

- March 20th, 1969
  Caribbean and Western North Atlantic
- Hemisphere and Globes, 1977
  24 March, 1977
- Virgin Islands Incident
  August 1969
- Typical Shield Test, Northern Route to Japan
  June, 1982



Expanding Hemisphere of Light

Mar. 20, 1969
Caribbean and Western
North Atlantic

- Semicircle
- Milky white light
- Small, intense at first
- Dimmed as enlarged
- Grew to enormous size
- Lasted 10 minutes, then faded

MOON
50 degrees
70 degrees
Marine Observer
40:17, 1970


Hemisphere and Globes 1977
0855 GMT, 24 Mar 1977
M.V. Kinpurnie Castle
23° 05' N; 17° 25' W
Disappeared
after 10 minutes
2nd luminous
patch
Moderately
luminous
hemisphere
formed
Bright luminous
patch (1° diameter)
Required
3 minutes
to form
30°
For 10 sec,
"searchlight"
shined down
40°
© T.E. BEARDEN 1996
Marine Observer
48:21-22, 1978



1969 Virgin Islands Incident

8:15 P.M.
Thursday
Aug 1969
Seen by many residents

Faintly luminescent
Smooth, curved edge
NORTH DIRECTION

© T.E. BEARDEN [illegible]



Typical Shield Test, Northern Route to Japan

Asahi Evening News, Tokyo
June 22, 1982

Multiple tests seen per month, for years.
Pilots simply ceased reporting them.

© T.E. BEARDEN 1994, 1995



How Could Such Superweapons Ever Be Concealed?

- Arthur C. Clarke's law states:

  "Any sufficiently advanced technology is indistinguishable from magic."

- To U.S. scientists, "magic" means "impossible"
- Longitudinal EM waves and LW interferometers have been regarded as fantasy and impossible
- To deceive foe on rather open use of unknown technology without discovery:

  "Disguise its uses as understandable accidents, human error, acts of nature, other known technology, etc."

© T.E. BEARDEN [illegible]



Soviets Easily Concealed These Superweapons for Four Decades

- Intensive Soviet deception plan utilized
  - Embedded in other weapon system tests
  - Made to resemble natural acts, accidents, etc.
  - Open science releases coordinated to show Russian scientists worked on "normal" science
- West thought Russian scientists inferior
- U.S. scientific community was and is dogmatic, and fiercely suppresses real scientific innovation
- Terribly flawed electrodynamics not ruthlessly shaken and changed in West
- West had no basis for understanding energetics

© T.E. BEARDEN 1996, 1999


Precise spacetime curvature engine adds energy to 2He4 α-particles inside atomic nuclei, causing tunneling α-decay
POWER UNIT
BEAM UNIT
BEAM TRANSMITTER
REFLECTED BEAM RECEIVER
POWER UNIT
BEAM UNIT
BEAM TRANSMITTER
REFLECTED BEAM RECEIVER
MAIN POWER UNIT
PHOTO UNIT
CONTROLLER-SWITCHER UNIT
SCANNING ANTENNA HORNS
MAIN DISPLAY UNIT (MOVABLE)
Interference zone with spacetime curvature engines to add energy to α-particles, causing α-emission and decay
Plan View
OPERATOR STATION
Elevation View

Figure 26. Microscope-type, laser-like interferometer for inducing quick α-decay in samples of otherwise longer-lived isotopes.

© T.E. BEARDEN 1996



Longitudinal EM Wave Interferometry: Endothermic

Meeting of timed pulses causes explosive cooling

COOLING IN INTERFERENCE ZONE

Ambient vacuum potential in distant interference zone

Φ_a

subspace

subspace

Bias

Heat extracted

XMTR/RCVR

XMTR/RCVR

Φ_T

Electrical ground potential of transmitter

© T.E. BEARDEN 1996

Heat emerges at transmitter/receiver

Heat emerges at transmitter/receiver



Longitudinal EM Wave Interferometry: Exothermic

Energy input to transmitter/receiver

Energy input to transmitter/receiver

XMTR/RCVR

XMTR/RCVR

Φ_T

Electrical ground potential of transmitter

subspace

subspace

Bias

Heating in interference zone

Φ_a

Ambient vacuum potential in distant interference zone

Meeting of timed pulses causes explosive heating

ⓒ T.E. BEARDEN 1999

The Tom Bearden Website

Help support the research

U.S. Air Attack on Libya
April 1986

- Slide 1
- Slide 2
- "Washington Post" Article
  January 22, 1989



U.S. Airstrike on Libya April 1986*

- 33 U.S. AIRCRAFT IN STRIKE
- MANY HIGH-POWERED TRANSMITTERS
  - *COMMUNICATIONS*
  - *JAMMERS*
  - *RADARS*
- SEVERE, UNEXPECTED "EMI" ENCOUNTERED
  - *ONE F-111 DOWNED*
  - *NUMEROUS WEAPONS WENT ASTRAY*
  - *THREE FOREIGN EMBASSIES DAMAGED*
  - *SEVEN AIRCRAFT FORCED TO ABORT*
- COMMANDERS: *"US OR THEM?"*

Mild quantum potential weapon tested against electronics in U.S. aircraft and missiles

EM energy arises from every point in spacetime inside the electronics

*Washington Post, 22 Jan. 1989, p. A4



U.S. Air Attack on Libya in April 1986

- Established QP with the electronics in our aircraft and missile
- Subtly jammedthem with spurious EMI noise and signals

Longitudinal wave interferometry into distant mirror
Longitudinal wave interferometry into distant mirror
Distant Scalar Potential Interferometer
1
© T.E. BEARDEN 1997



Lightning Wall

- Aircraft on course of 270 degrees
- Approached "solid wall of lightning" in an otherwise cloudless sky
  - From very high altitude to near the water
  - Extended north-south as far as one could see
- Radar scope clear
- *Rigged aircraft for heavy weather*
- *Plunged directly through wall*
- *Wall was very thin*

circa 1959-1960
Interview with Patrol plane commander
U.S. Navy P5 aircraft
Over Atlantic, 200 miles east of Norfolk

© T.E. BEARDEN 1996



Lisitsyn's Report: Brain Code Broken

- THEORY DEVELOPED AND FITTED
- HYSTERESIS MEMORY LOOP
- CONTROLLED EM INDUCTION
  - IMAGES
  - SENSATIONS
  - PREDETERMINED EMERGENCE
- 23 EEG BANDS
  - UP TO 8.1×10^{20} HZ
  - 11 INDEPENDENT CHANNELS

S.K. Lisitsyn, "New Approach to the Analysis of Electroencephalograms,"
DDC Report AD73005, p. 16-25.

JCS-34

© 1976, 1985, 1991 T.E. BEARDEN



Large Longitudinal EM Wave Interferometer (LWI) Accident

- 1958 nuclear explosion near Urals
  - Contaminated 1200 square kilometers
  - Signature of large LWI accident
  - Buried atomic wastes suddenly exploded
  - Region contaminated to this day
- Soviets were well along with advanced LWI prototypes and testing
  - In Jan. 1960 Khrushchev announced these forthcoming "fantastic" weapons
  - 1958 difficulties would have been resolved by 1960

© T.E. BEARDEN 1996, 1999



Large Longitudinal EM Wave Interferometer (LWI) Accident

- Expected cause of 1958 accident
  - Huge LW energy beams built up
  - Catastrophic short-out in transmitter
  - LW energy flashed over into earth and spread
  - Struck and fissioned stored nuclear wastes
- Developed new safety circuits
  - For transmitter short-out, instantly activates to hold LW beam energy and prevent flash-over
  - Similar accident happened in 1986 at Chernobyl, except private U.S. group blew that transmitter to prevent catastrophic quake in California

© T.E. BEARDEN [illegible]

(Use of Hidden Information Content of the Field)
(Can Provide Action-at-a-Distance)


ϕ_1
ϕ_2
Note:
Whittaker's 1904 paper initiated the entire field of superpotential theory.
Interference Zone (Potential gradients)
Normal EM Energy: May be positive, or negative, or fixed
Hidden Bidirectional EM energy flow
Hidden Bidirectional EM energy flow
Scalar Potential Beams
XMTR
XMTR
Whittaker/Ziolkowski Transmitter Arrays
(8 to 20 harmonic wavepairs each)

© T. E. Bearden 1994, 1999

Figure 5. Scalar potential interferometry (between the two sets of bidirectional longitudinal EM wavepair functions) produces all EM force fields and waves.



Two Types of Mutual Assured Destruction (MAD) Systems

- **Sane system:**
  - Turned off or on standby
  - Wait until attacked or attack is imminent
  - Humans consider situation, make strike decision
  - Command order issued to weapons officers
  - Human finger initiates launch sequence
  - Usually requires code entry, etc. for assured launch control
- **Insane system:**
  - Computer periodically (e.g., every 2 hours) initiates launch
  - During sequence, there is a period (say, 2 min.) where operators can enter stop order (usually coded)
  - If correct stop not entered, weapons automatically launch
  - If correct stop entered, computer resets, and after another 2 hrs, automatically reinitiates the launch sequence

© 1996, 1997 T.E. BEARDEN



Psychoenergetics Weapons Teams Mentally Disable All Personnel

(COUNTERS ALL SANE MAD SYSTEMS)
(NULLIFIES HUMAN COMPONENT OF ALL WEAPON SYSTEMS)

ELECTRICAL THOUGHT-WORDS ARISE DIRECTLY IN BRAIN, HENCE IN MIND, BYPASSING SENSOR INPUTS

INSTANT HYPNOGOGIC STATE, WITH INSERTED THOUGHT-WORDS

Effects arise in local spacetime, simultaneously in all minds in the targeted area

INSTANT HYPNOGOGIC STATE: WITH WAKING DREAM

PERCEIVED REALITY NOW CONTROLLED

TARGETED POPULACE

- Site personnel instantly hypnogogic and mentally controlled.
- Distant weapon controller teams coord crew actions
- Standdown insane weapons to maintenance standby.
- Mindsnapper then strikes, kills all personnel, and nullifies site for months.

Indicators: Two A-10 incidents 1997, LIDA device since 1950s.

© 1998 T.E. BEARDEN



Strikes Against Special Ship and Energetics Weapon Sites

- Via powerful scalar EM pulses in each targeted area, so sharp time-jerks occur
  - Mind and its operations exist in time but not in 3-space
  - Coupling interaction of mind operations to body occurs through flow of time
  - Flow or change of flow of time must be smooth, for coupling of mind to body
- *Sharp jerk in time flow snaps mind's coupling to body, instantly separates mind*
- *Instant death for every virus, bacterium, cell, insect, mammal, living creature*
- *Contaminates struck sites for months, perhaps a year*

Note: In other words, this is the part of the "preparation barrage" that attacks the enemy's response capability (i.e., his "artillery" and his "airpower") and suppresses it. The use of the "mindsnapper" weapons provides 100% assurance of success.

© T.E. BEARDEN 1996



"MINDSNAPPER" ATTACK ON SPECIAL SHIPS & ENERGETICS WEAPONS SITES

"We have a new, fantastic weapon ... so powerful that, if unrestrainedly used, it could wipe out all life on earth."

Khrushchev,
speaking to Presidium,
Jan. 1960

XMTR
XMTR
POWERFUL SCALAR EM BURSTS
POWERFUL SCALAR EM BURSTS
POWERFUL SCALAR EM BURSTS
TARGETED AREAS
SHARP TIME JERKS PRODUCE MINDSNAPS

© 1996 T.E. BEARDEN

- Minds snapped loose from bodies (every living thing)
- Struck areas completely sterilized of all life
- LWs emitted; slow decay of time-charge makes contamination persistent
- Tested twice in Afghanistan

[The Tom Bearden Website](#)

[Help support the research](#)

How Much Off Guard Are We?

- [Slide 1](#)
- [Slide 2](#)
- [Slide 3](#)
- [Slide 4](#)
- [Slide 5](#)
- [Slide 6](#)
- [Slide 7](#)



How Much Off Guard Are We?

- *Legitimate U.S. forces have no energetics weapons or defenses against them*
- *No DoD general, military officer, or enlisted person reporting to the government of the United States has any:*
  - Training in energetics or energetics weapons
  - Experience in energetics or energetics weapons development and usage
  - Training in strategy, tactics, deployment, and employment of energetics weapons
  - Knowledge of energetics weapons effects and capabilities
  - Knowledge of the energetics weapons, tactics, deployment, and employment by the KGB/Russians
- *Civilian and military, scientific and intelligence, and news media personnel do not recognize energetics weapons effects happening right over their own heads*

© 1999 T.E. BEARDEN



How Much Off Guard Are We?

- *Kill of U.S.S. Thresher in 1963 not recognized. Left signatures.*
- *23 years of KGB weather engineering, particularly over U.S. and North America, ignored and not recognized.*
- *Decades of irradiation of U.S. Embassy, fatally injuring three U.S. Ambassadors, health changes in personnel shrugged off ineptly.*
- *Massive building of underground sites, all through former Soviet Union, lamely speculated as perhaps "ABM" system or?.*
- *1985, 1986 Soviet kills of U.S. aircraft, spacecraft, personnel ignored as "accidents" by legitimate U.S. communities.*
- *Quantum potential strike on soldiers in Gulf war ignored.*
- *Quantum potential deterioration of U.S. populace's immune systems ignored.*
- *Exchange of earthquakes and massive retaliatory destruction of Soviet missile ammunition storage sites, 1986-1989, ignored.*
- *U.S. scientific and military communities adamantly refuse to rework electromagnetics, though known to be seriously flawed.*
- *Refuse to apply Stoney/Whittaker work to engineer hidden variables, even though present quantum mechanics also known to be wrong because it does not contain such "hidden order."*
- *Refuse to develop, structure, and apply Bohm's quantum potential, for instantaneous action at a distance. Russians developed it.*

© 1996, 1999 T.E. BEARDEN



How Much Off Guard Are We?

- **Kill of U.S.S. Thresher in 1963**
  - Not recognized.
  - Left signatures.
- **23 years of KGB weather engineering**
  - Particularly over U.S. and North America
  - ignored and not recognized.
- **Decades of microwave irradiation of U.S. Embassy**
  - Fatally injured three U.S. Ambassadors
  - Induced health changes in personnel
  - Shrugged off ineptly.
- **Massive building of underground sites**
  - All through former Soviet Union
  - Lamely speculated as perhaps "ABM" system or?.



How Much Off Guard Are We?

- 1985, 1986 Soviet kills of U.S. aircraft, spacecraft, personnel ignored as "accidents" by legitimate U.S. communities.
- Quantum potential strike on soldiers in Gulf war not recognized, ignored.
- Quantum potential deterioration of U.S. populace's immune systems ignored.
- Exchange of earthquakes and massive retaliatory destruction of Soviet missile ammunition storage sites, 1986-1989, ignored.



How Much Off Guard Are We?

- U.S. scientific and military communities adamantly refuse to rework electromagnetics, though known to be seriously flawed.
- Refuse to apply Stoney/Whittaker work to engineer hidden variables, even though present quantum mechanics also known to be wrong because it does not contain such "hidden order."
- Refuse to develop, internally structure, and apply Bohm's quantum potential, which gives instantaneous action at a distance and great energy amplification.
- Russians developed quantum potential weapons, which obsolete all other weapons.

© 1996 T.E. BEARDEN



JUST HOW MUCH OFF GUARD ***ARE*** WE?

Kill of
TWA-800
1996

Kill of
USS
Thresher
1963

Cold
Explosion
Off Japan
Apr 1984

Kill of
Space
Shuttle
Challenger
1986

President's
party
airplane
crash
1996

From The Huntsville (AL) Times 18 Sep 96:

"Retired Gen. Wayne Downing concluded that U.S. forces are so far superior to potential foes that opponents have turned to terrorism as the only way of challenging them."

The Times also provided the information that Defense Secretary William Perry agreed with Gen. Downing's conclusion.

3 Dead U.S.
Ambassadors
from Moscow
Embassy
Radiation

- *QP Gulf War Syndrome: 16,000 persons disabled*
- *QP jamming, U.S. air attack on Libya, 1996*

Kill of
Arrow DC-8
Gander AFB
Dec 1985



JUST HOW MUCH OFF GUARD ARE WE?

3 Dead U.S Ambassadors, U.S. Weather Engineered 20 years

Kill of USS Thresher Nuclear Submarine Apr 1963

QP Test on U.S. Troops in Persian Gulf, 1991 (Gulf War Syndrome)

TWA-800 1996; President's C-130 crash 1996

Arrow DC-8 Gander AFB Dec 1985

Challenger 1986

Quantum Potential Jamming of Air Attack on Libya Apr 1986

Blind Euphoria to Even the Ballistic Missile Threat

- U.S. National Intelligence Estimate (NIE) released in Nov. 1996 states there is no foreseeable threat to the U.S. from "indigenous missiles" for at least 15 years.
- Clinton has claimed a program for ABM defense is too expensive, would violate ABM Treaty with former USSR.
- Soviets developed an ABM system in violation of the treaty.
- In June 96 Russia test-launched an SS-19, their 26th ICBM test in 5 years.
- *"Russia still retains and is modernizing a vast nuclear arsenal... still the only nation of earth that could destroy America in a matter of minutes. Indeed, given the weakness of the Russian Army, Russia's superpower ambitions rest more than ever on its nuclear capabilities."* *
- "For the first time since the dawn of the nuclear age, there is not a single Russian missile pointed at America's children." **

Comment: Punch a computer button and the missiles are pointed! The armed missiles are still there, ready and waiting.

Bulleted info courtesy Washington Inquirer, June 24, 1996.

* House Nat'l Security Chmn, Floyd Spence.
** Bill Clinton, State of the Union Message.

© 1996 T.E. BEARDEN



Possible Targets: 1995-9
Escalation Phase

(Based on 1985-87 test program)

Earthquakes
Missiles
Power Grids &
Distribution Systems
Satellites
Ships
Shuttle
Launches
& Flights
JETLINERS
Radio/TV
Subs
Microwave Nets
Radars &
Nets
Communications
and Computer Nets

© 1996 T.E. BEARDEN



Propagation of Weapon Effects

- **All conventional weapons use propagation through 3-space of matter or energy or both**
  - *Matter (bombs, missiles, projectiles, etc.)*
  - *Energy (EM force fields, sonic force fields, etc.)*
  - *Basically one-to-one, or one "bus" to many-on-many*
  - *Finite propagation velocity v: where $0 < v \leq c$*
  - *Time delay: Shielding and pre-strike retaliation possible*
- **Structured quantum potential propagates vacuum ordering (vacuum engines), instantly**
  - *Zero time delay (through multiply-connected spacetime)*
  - *No propagation "through space", no "velocity" as such*
  - *Easily one-to-many, without limit*
  - *Dramatic energy amplifier (gates, amplifies flux ordering)*
  - *Effects arise in local spacetime; no shielding possible*
  - *No range limit, since striking distance always zero*
- **QP weapons obsolete all other weapons**

© 1989, 1995, 1998 T. E. BEARDEN



Yugoslav Earthquake, Followed by Cold Explosion

Apr. 15
1979

- Magnitude 7.2 on Richter scale
- Epicenter 33 km. deep
- More than 100 aftershocks
- At Kamenari:
  - Adriatic sea mushroomed up
  - Like atomic bomb explosion
  - Signature of a cold explosion
  - Similar to Apr. 1984 test off coast of Japan, near Kurils (see inset graphics)
- Note that April is a significant test month for the Communists (preparing official reports for May Day?)

© T.E. BEARDEN 1994, 1996



COUNTERING AN INSANE QP WEAPON:

Quantum Potential Psychoenergetics
Strike Mentally Controls All Personnel

CONTROLLED PERSONNEL DISABLE INSANE QP SYSTEM
(FOLLOWED BY PERSONNEL KILL OF ENTIRE CADRE BY MINDSNAPPER)

ELECTRICAL DREAMTHINKING ARISES DIRECTLY IN BRAIN, HENCE IN MIND, BYPASSING SENSOR INPUTS

Effects arise in local spacetime, simultaneously in all minds in the targeted area

INSTANT HYPNOGOGIC STATE, WITH INSERTED DREAM-THINKING

INSTANT HYPNOGOGIC STATE: WITH WAKING DREAM

PERCEIVED REALITY NOW CONTROLLED

TARGETED CADRES

MINDS ARE INSTANTLY PLACED INTO WAKING-- BUT DEEP -- HYPNOGOGIC TRANCE STATE. INSERTED THOUGHTS ANALOGOUS TO HYPNOTIST. PERSONNEL FUNCTION IN AN ALTERED, COMPLETELY CONTROLLED PERCEIVED REALITY.

© 1996 T.E. BEARDEN

Indicators: Captain Button's lengthy A-10 incident in 1997, LIDA device since 1950s.



Gulf War Disease: KGB QP Weapon Induced ST Curvature Engines for a Cocktail of Diseases

LEBANON
SYRIA
ISRAEL
JORDAN
IRAQ
IRAN
KUWAIT
QATAR
LIBYA
EGYPT
SAUDIA ARABIA
CHAD
SUDAN
OMAN

© 1999 T. E. BEARDEN

Distant Scalar Potential Interferometer with iterative self-targeting



Self-Targeting in Inner EM Channel Can Produce a Quantum Potential

Once QP is established, energy transmission is direct and instantaneous. Energy input to one single participant will simultaneously appear in all other participants, the amount depending on their fractions of participation with the input station.

NARROWING OF INTERACTING POTENTIALS INTO LASER-LIKE BEAMS, BETWEEN TWO PUMPED SOURCES. NOW ONLY LONGITUDINAL WAVES CONNECT THE LINKED OBJECTS.

SELF-TARGETING EFFECT AMONG ALL PAIRS OF INTERACTING PUMPED SOURCES

© 1999, 1995, 1996 T.E. BEARDEN



a. Iterative retroreflection between any pair of nodes narrows the interconnecting potentials to a laser-like, bidirectional beam. Iterative phase conjugate reflection provides self-targeting.

b. The quantum potential exists as narrow, laser-like beams between participating nodes, even when the nodes are widely separated. The beam space is multiply-connected; transmission is instantaneous.

© 1989, 1995 T.E. BEARDEN

Consider the hidden Stoney/Whittaker bidirectional EM waves that comprise the potential from each source node. If these nodes have sufficient intersymmetry of dynamic material form, then self-targeting occurs between the two nodes of any nodal pair. By iterative phase conjugate reflection, the scattering is narrowed into interconnecting wavepairs, in laser-like beams, between each two nodes. Thus the interconnecting potentials narrow into laser-like, bidirectional beams. The Coulomb gauge may apply, and a quantum potential may be formed.

Figure 30. Mechanism for generating a quantum potential, by iterative self-targeting induced into a system of multiple scattering nodes. Once a QP is established, spatial separation has little or no effect.



Major Principles for Use of Quantum Potential Weapons

- Must disable dead-man fuzing prior to massive use of scalar interferometry weapons.
- Must assure immediate, complete nullification of unique enemy assets (quantum potential assets, special ships, and energetics weapons).
- Personnel can be destroyed instantly with mindsnapping; area is sterilized of life, and effect persists, gradually dying away.
- Personnel can be disabled instantly with various psychoenergetic weapons; area not sterilized.
- Personnel can be destroyed in short order by using EM BW weapons; area not sterilized.
- If foe has energetics weapons, then it is a quick-draw "gunslinger" contest unless insane MAD systems deployed.
- Complete surprise is of decisive importance.
- Tailor effect used to specific target, objective.
- *Note: Must use "insane" MAD systems to deter.*

© 1996 T.E. BEARDEN



Quantum Potential Weapons: Major Principles (Continued)

© 1996 T.E. BEARDEN

- Three major classes of use exist:
  - Use of bulk energy only (as in bulk heating or cooling) without substructuring
  - Use of internal structuring of the bulk energy, so that *vacuum engines* appear in target
  - Use of more deeply nested engines allows direct intervention in mind, long term memory, perception, thoughts, emotions, personality
- Use of vacuum engines allows engineering at a distance of:
  - *Atomic nuclei* including structures, reactions, and transmutations
  - *Bulk matter* including translations, lattice bonding, chemistry, chemical interactions, electromagnetic interactions
  - *Deep biological control systems* such as
    - Becker's cellular control (recovery) system
    - Popp's cellular control system
  - *Cells* including:
    - Structuring, differentiation and dedifferentiation
    - Genetic changes, chemical changes
    - Induction of disease states without normal disease vectors
  - *Mind/matter interface*, including long-term memory, perception, emotion, thought, mental state



Instantaneous Communication by a Quantum Potential

Note: The term "quantum potential" is used in an extended sense.

© 1989, 1995 T.E. BEARDEN

Selected clipart © by Lotus SmartPics™



Participants in a quantum potential share a common multiply-connected spacetime (MCST)

- Separated points are superposed in MCST
- Connection is instant and bidirectional
- Propagation through ST does not apply
- Energy or vacuum engine input to one station instantly appears at each and every other station, undiminished in magnitude

- Any station may insert energy and engines
- Phase conjugation insertion negates

© T.E. BEARDEN 1998



Quake in Tangshan, China

28 July, 1976

- 7.8 on Richter scale
- Hundreds of thousands killed
- Accompanied by extensive light, electrical effects
  - Starting 3 to 5 days before
  - Communications interference within 250 km
  - Sky lighting observed
- [Personal comments]

© T. E. BEARDEN 1999



Counting Rifles: Put up or shut up!

(Exchanging Earthquakes)

Opening bet

- Quebec 25 Nov 88
- Pasadena 3 Dec 88

Raise you

- Armenia 7 Dec 88

Call - what do you have?

- Malibu 18 Jan 89

Four aces

- Soviet Central Asia 23 Jan 89

Clear table (stress relief)

- Bakersfield et al various

© T.E. BEARDEN 1990

Instant Communication by a Quantum Potential



The space is multiply connected; i.e., a power change of 1 watt on any single node has a fraction of that power also appear simultaneously at each other node. Once the QP is established, spatial separation has no effect.

N's are nodes participating in the QP

N_3
RCVR
XMTR
SATELLITE
N_5
RCVR
XMTR
SATELLITE
N_1
RCVR
XMTR
MASTER
N_4
RCVR
XMTR
SATELLITE
N_2
RCVR
XMTR
SATELLITE

© 1989, 1995 T.E BEARDEN



Westerners Do Not React to Slow Threats

BOA CONSTRICTOR
LIGHTNING STRIKE

Westerners tend not to react to slowly increasing things,
but react to rapidly increasing things.

© 1995 T.E. BEARDEN


CHARACTERIZING A GIVEN RISK OR RISK FACTOR
Probability of Materializing
Very Likely
Likely
Unlikely
Very Unlikely
1.00
0.75
0.500
0.25
0.00
Low Risk
Moderate Risk
High Risk
Crisis
0.00
0.25
0.500
0.75
1.00
Negligible
Marginal
Critical
Crisis
Consequence (or Disutility) of Risk



TECHNICAL RISK MANAGEMENT

SUPPORT RESEARCH IS TECHNICAL RISK REDUCTION AND MANDATORY FOR ANY EMERGING TECHNOLOGY



Aum Shinrikyo's Sarin Facility

The interior of Satian No. 7, a suspected sarin production plant

Chemical plant (the first four stages for production)

SOLVENT RECOVERY
STEPS 2 & 3
STEP 1
emergency stairs
emergency stairs
compressor room
shower room
a room for taking a nap
machine operating room
electrolysis room
prefabricated chemical laboratory
office
stairs
a room with liquid injectors
elevator
STEPS 4 & 5
chemical tanks (the 5th-stage production)
storage room
shutter
door
STORAGE

NOTE: Group was preparing to produce 70 tons of sarin in a 30 day period.

Reference: Senate Subcommittee Hearings



In Scalar Beam Interference Zone

- De-phasing of wave/antiwave pairs occurs
- Zero-summation destroyed
- Ordinary EM reappears [Whittaker 1904]
- Ordinary energy appears or disappears (i.e., may produce heating or cooling)
- Energy bottle effect
- Can add or extract EM energy
- Can produce specific ST curvature engines

© T. E. BEARDEN 1999



Physicist Schappeller Auralaz Munster, Austria:

- British Intelligence interview, about 1948
  - Used Kaluza-Klein theory
  - Worked with Russians
- Schappeller claimed he could:
  - Cause "implosions" rather than explosions
  - Use gravitational and electromagnetic energy
  - Cause large areas of the ocean to freeze
  - Tap earth-ionospheric field
  - Produce enormous energy
- *This is precisely what Hellman worked on in the USSR, after WW II!*

© 1996 T.E. BEARDEN



Initial Soviet Plan for Cold War, After WW II

- Develop and deploy SAM bomber defense
- Catch up in atomic weapons
- Master and apply rocketry
- Wed atomic warheads to rockets
- Initiate "Cold" War
  - Bleed the dragon
  - Guerrilla wars
  - Terrorism
  - Insurgencies
- *Find, develop, and weaponize next great technical breakthrough area as highest national priority*

© 1996 T.E. BEARDEN



Josef Stalin: Absolute Dictator

- Secret police and spies everywhere
- Purged his own officer corps
- Always deeply suspicious
- Regularly purged his enemies or those perceived to be shaky or untrustworthy
- Absolute power, justice had nothing to do with it
- Opponents often just disappeared in the night, never to be seen again
- Secret police often tortured, killed them
- Others sent to slave labor camps to die by severe work, starvation, and beatings or downright massacre
- Had experienced unusual abilities of Wolf Messing, so knew that some persons could do unusual things
- Forced Soviet weapon physics into this psychoenergetics realm also

One of the greatest mass murderers in history.

© T.E. BEARDEN 1997



Exploding any Resistance by Operational Scientists

The Communists slaughtered 20 million Russian Kulaks to collectivize Soviet farming

"The destiny of communism has been frustrated by the U.S. development of the atomic bomb. That is not the last great technical breakthrough. The next one WILL be Soviet! You will provide me with that great new technical breakthrough at all speed, or I will have your heads. Do I make myself clear, comrades?"



Significant Soviet Statements

- "In the final revolution, it does not matter if three-quarters of the earth is destroyed, so long as the other quarter emerges communist." *[Lenin]*
- "If a means of total neutralization of foreign missiles is to be found, it can only come from a group of new principles in physics, called energetics." *[Nobelian Petr Kapitsa, to Nikita Khrushchev, in answer to Khrushchev's demand for a 100% method of defense against long range missile attack.]*
- "We will bury you." *[Khrushchev, to Nixon, Kitchen Debate*]
- "We have a new weapon, just within the portfolio of our scientists, so to speak, which is so powerful that, if unrestrainedly used, it could wipe out all life on earth. It is a *fantastic* weapon." *[Khrushchev, speaking to the Presidium, Jan. 1960]*

© 1996 T.E. BEARDEN



CAPTAIN SVOBODA DIVES HEADLONG TO HER DEATH

COMPANION A-10s
CAPTAIN AMY SVOBODA

© T.E. BEARDEN 1999

- Night training mission May 27, 1997
- From same wing as Captain Button
- This was a second psychoenergetics strike



T-Polarized Beam Projector

For Intercepting and Changing Distant Masses at Various Angles and Distances

A beam projector interferometer may be swept in azimuth and elevation, under computer control. The interference zone can be quickly swept through the surrounding volume of space.

Spacetime curvature engines act within any intercepted mass
Time-Density waveset generator 1
Time-Density waveset generator 2
Small Delay generator
Pulse 1
Pulse 2
Pulse 1
Pulse 2
Pulse 1
Pulse 2
Interference zone for time-density waves
© T.E. BEARDEN 1996



Possible Tests (1)

- 1958 nuclear accident in Urals
- Disease induction in U.S. Embassy personnel in Moscow
- Siberian disease/death transmission experiments
- Destruction of USS Thresher nuclear submarine, Apr. 10, 1963
- Nuclear explosion transmitted into ocean underwater, 100 miles north of Puerto Rico, Apr. 11, 1963

© 1996 T. E. BEARDEN



Possible Tests (2)

- Eight F-111's downed in Vietnam immediately after deployment
- Several large earthquakes
- Mysterious aircraft losses in groupings
- Numerous underground "nuclear" tests
- Nuclear tests at Semipalatinsk without associated seismic activity
- High altitude rumbles, snaps, booms
  - *Off English coast*
  - *Off East coast of U.S.*
  - *Over West Coast of U.S. in thunderstorms*

© 1996 T.E. BEARDEN



Possible Tests (3)

- Blinding of several U.S. satellites (up to 4 hours in duration)
- Cold Explosion off Kurils 1984
  - First, a cold explosion
  - Then test of giant Tesla shield 300 mi. dia.
- Tests offset from shuttle launch Nov. 85
- Kill of Arrow DC-8,Gander, NFLD Dec. 1985
- Titan kill, Vandenberg AFB, CA early 1986
- Kill U.S. Challenger, off Cape Canaveral 1986
- Earthquakes induced, 1986-88
- Dozens of tests of shields around the world
- Decades of radiating U.S. Embassy in Moscow

© 1996 T.E. BEARDEN



Possible Tests (4)

- Extensive tests 1990-99 in Western Australia
- Engineering of weather since 1990 by Yakuza
- Possible nuclear dudding test in WA in 90s by Aum Shinrikyo
- C-130 engine flameout kill
- TWA-800 kill 1997
- Gulf War Disease Induced, 1991
- Spreading of immune systems of U.S. populace, 1990s
- Psychoenergetic control of Captain Button
- Psychoenergetic control of Captain Svoboda
- Twice in 1997, within days of full strategic destruction of U.S.

© 1996 T.E. BEARDEN



Mushroom cloud rising from sea

- 0514 hrs, 9 April 1984
- Gray-white cloud appeared
- Rose 60,000 feet in 2 minutes
- South of Kuril Islands
  - *180 miles southeast of Hokaido*
  - *200 miles from Tokyo*
- Soviet missile testing scheduled about 350 miles away, at 2100 hrs, 9 April 1984

© 1999 T. E. BEARDEN

Launches from Cape Canaveral and Vandenberg AFB Provided Practice Targets of Opportunity



The sinking U.S.S. Thresher, with her controls jammed, implodes when she reaches crush depth



© 1978 HAL CRAWFORD
USED BY PERMISSION


Thermometers
C-1
C-2
C-3
C-4
Calorimeters
Film Radiation Detectors
D-1
D-2
D-3
D-4
Radiation Counters
RC-1
RC-2
RC-3
RC-4
RC-5
RC-6
Power Meter
Experimental Region

Figure 32. Embodiment of an instrumental array sufficient to discriminate when time-density charging has occurred, and that transduction of time-charge decay is occurring.

© T.E. BEARDEN 1998

Time-Polarized EM Wave interferometer Creating Space-Time Curvature Engines in a Distant Interference Zone


TRANSVERSE WAVE GENERATOR #1
PHASE CONJUGATOR #1A
PHASE CONJUGATOR #1B
SPACETIME CURVATURE ENGINE / XMTR #1
CONTROLLER
LONGITUDINAL EM WAVES
TIME-DENSITY EM WAVES
IZ
PHASE CONJUGATOR #2A
PHASE CONJUGATOR #2B
SPACETIME CURVATURE ENGINE / XMTR #2
POWER SUPPLY
TRANSVERSE WAVE GENERATOR #2
© T.E. BEARDEN 1998



Transmutation of Radioactive Nuclei at a Distance

Interferometer (may be multiple beam or single beam) is played through the radioisotopes of the nuclear wastes to be neutralized. Specific engines may be used for altering specific isotopes.

Spacetime curvature engines act within any intercepted radioactive wastes
Active Spacetime Curvature Engines Zone of action
Waveset 1 generator
Engines Calculation
Waveset 2 Generator
Trans-mission Control
Nuclear wastes in storage, in ditches, in containers, etc.
© T.E. BEARDEN 1998



Transmutation of Radioactive Nuclei (2)

Specific spacetime curvature engines used are to add excess energy to selected radionuclei, including intermediate decay isotopes. In this way, decay is dramatically speeded up.

Spacetime curvature engines act within any intercepted radioactive wastes, adding excess energy

Active Spacetime Curvature Engines Zone of action

Nuclear wastes in storage, in ditches, in containers, etc.

Waveset 1 generator

Engines Calculation

Waveset 2 Generator

Trans- mission Control

© T.E. BEARDEN 1998



Typical Shield Test, Northern Route to Japan

Asahi Evening News, Tokyo
June 22, 1982

Multiple tests seen per month, for years.
Pilots simply ceased reporting them.

© T. E. BEARDEN 1994, 1995



A Curious Tide in Human Affairs

To win its freedom in the long run, usually a group must defeat its attackers or suppressors *at least twice*.

- We fought the British twice for our independence.
- We are fighting ourselves twice to free the slaves.
  - American Civil War
  - Civil rights struggle
- We beat the Germans twice, in WW I and WW II
- We beat the Hispanics in the Spanish-American War. *That's once*. (They're winning the second by crossing the border. The U.S. is becoming a Hispanic Nation).

But we also have some unfinished business at hand.

- We checked the Russians in the Cold War. *Once*.
- We checked the Japanese in WW II. *Once*.
- We checked the KGB in the Cold War. *Once*.
- We checked the Communists in the Cold War. *Once*.
- We checked Saddam Hussein in the Gulf War. *Once*.



Large Scalar EM Interferometer (LASI) Accident Near Urals, 1958

- 1958 nuclear explosion near Urals
  - Signature of large scalar interferometer (LASI) accident
  - Buried atomic wastes suddenly exploded
  - Large region contaminated to this day
- Soviets were well along with advanced LASI prototypes and testing
  - Khrushchev announced forthcoming advent of these "fantastic" weapons in Jan. 1960
  - 1958 difficulties could have been resolved by 1960
- Expected 1958 cause: transmitter short-out and failure in a nearby LASI discharged its cumulated energetics beam energy into the ground
- *Spreading ground pulse struck nearby atomic wastes, fissioning nuclei*



The Superpower Paradox: Asymmetric Cheap WMD Strategic Strike and Destruction

Complex, expensive, high tech
IRAN
IRAQ
LIBYA
EGYPT
SAUDI ARABIA
SUDAN
Simple, cheap, low tech

© 1990, 1996, 1998 T. E. BEARDEN



THE KGB/YAKUZA-AUM WAR PLAN

- *Dud all quantum potential weapons in other nations via psychoenergetics.*
- *Remove U.S., Israel, Brazil, West Europe as military powers.*
- *Destroy nuclear weapons, hostile energetics weapons, hostile ships, 80% of targeted populaces in first hour of strikes.*

LEASE

1990-91

Aum/Yakuza Acquired Use of on-site Russian Scalar EM (Energetics) Weapons.

Began Geosurvey of Test Range (Western Australia) for training.

KGB Tested QP population wpn (Gulf War Syndrome)

TRAIN

1991-94

Began extensive training of AUM-Yakuza crews in Russia, with practice firing into Western Australia. J-team took over worldwide weather engineering. Preparing for occupation of West Australia.

ESCALATE

1995-99

Began EM kill of selected lone U.S. targets, iaw strategic deception plan.

U-2 a/c? USAir 747 ?
TWA-800 C-130
ValueJet? A-10s

Surged electrical grids. Worldwide practice kills, scalar interferometry. QP modification of selected pathogens

STRIKE!

Plan:
Trigger terrorist BW, & WMD attacks.
Enhance BW infections with QP wpn.
When ready, counter insane QPweapons with psychoenergetics. Destroy QP wpns.
Dud all nuclear weapons worldwide;
Time-snap ships, scalar weapons sites;
Attack major target populations w/QP.
Then cleanup with interferometry strikes.

© 1996, 1999 T.E. BEARDEN



Why Western Science is Ignorant of KGB Energetics

- *Foundations* of electrodynamics and much of Western physics are seriously flawed
- Only just rediscovering longitudinal EM waves
- No knowledge of using time-polarized EM waves
- Does not know a powerful GR is hidden in EM
- Ignores inner structure of potentials, waves, fields
- Hotly defends errors, ignores for a century
- Determined to push big nuclear science
- Suppresses research to approved dogma by rigorously controlling precisely what research the funds can be used for



Transmutation of Radioactive Nuclei at a Distance

Interferometer (may be multiple beam or single beam) is played through the radio-isotopes of the nuclear wastes to be neutralized. Specific engines may be used for altering specific isotopes.

Spacetime curvature engines act within any intercepted radioactive wastes
Active Spacetime Curvature Engines Zone of action
Waveset 1 generator
Engines Calculation
Waveset 2 Generator
Trans-mission Control
Nuclear wastes in storage, in ditches, in containers, etc.

© T.E. BEARDEN 1998

THE YAKUZA

(JAPANESE MAFIA)

To do business with Japan is to do business with the Yakuza

The Last Samurai, Defending Bushido



- 3 Major Yakuza Groups, In Coalition.
- Penetrate Japanese Government.
- Open Offices, Signs on Street.
- Public Romanticizes Yakuza as Last Japanese Samurai
- In Large High-Tech Corporations.
- In Control of Japanese Banks.
- Japanese Real-Estate Rip-off.
- $500 - 1,000 Billion per Year Income.
- Rapidly Spreading in U.S.
- Uniting Mafia Groups Worldwide.
- Coalition with Aum Shinrikyo.
- Leased Russian Energetics Weapons.
- Crews On-site in Russia, Trained.
- Practice Firings into Western Australia for Three Years. (Dozens of Shots per Month)
- Now in Escalation Phase, Killing U.S. Targets.
- All-out Strike on U.S. ready 1999-2000.
- Now held in check by KGB, dead-man fuzed by small nation friendly to U. S.

© 1995, 1996, 2001 T.E. BEARDEN



Yugoslav Earthquake, Followed by Cold Explosion

Apr. 15
1979

- Magnitude 7.2 on Richter scale
- Epicenter 33 km. deep
- More than 100 aftershocks
- At Kamenari:
  - Adriatic sea mushroomed up
  - Like atomic bomb explosion
  - Signature of a cold explosion
  - Similar to Apr. 1984 test off coast of Japan, near Kurils (see inset graphics)
- *Note that April is a significant test month for the Communists (preparing official reports for May Day?)*

OFF JAPAN, NEAR KURILS

1984 COLD EXPLOSION
SIMILAR TO THIS ONE

© T.E. BEARDEN 1994, 1996

Briefing to
Request for Information Symposium

14 February 2000

Air Force Research Laboratory

Directed Energy Directorate
AFRL/DE

Kirtland AFB, New Mexico

Colonel Doug Beason
Deputy Director

"VICTORY SMILES UPON THOSE WHO ANTICIPATE THE CHANGES IN THE CHARACTER OF WAR"

Guilio Douhet

U.S. AIR FORCE

Directed Energy Directorate

A paradigm shift in weapon system technology for the 21st Century.



Our Mission

- ***To support*** user needs for DEW applications and to address mission area deficiencies
- ***To exploit*** the relevance of Directed Energy technology to Air Force and DoD needs
- ***To foster*** user awareness of the potential of Directed Energy for Air Force and DoD applications
- ***To avoid*** technological surprise
- ***To explore*** DE technology avenues that offer high payoff to directed energy capabilities and applications

To do what has never been done before!

Directed Energy Directorate

Our Vision of the Future:
Directed Energy will Dominate the Battlespace of the 21st Century

Strike

We will strike deep in the enemy's territory at the speed of light, with little or no collateral damage or loss of life, crippling his ability to wage aggression.



Protect



Our high value and limited military assets will be protected by invisible shields of directed energy.

Graduated Deterrence

We will provide our warfighters with weapons that provide a wide range of graduated force for every military contingency.



Awareness

Our battleflield awareness will be greatly enhanced with directed energy tools capable of detection and identification



Security & safety in isolated canyons

Access to 50,000 acres for testing



Remote sites

Ideal weather “thin” atmosphere

Kirtland AFB

Unique & ideally suited for the nation’s directed energy technology development

Dark skies No light “pollution”



Sandia National Laboratories

Many diverse, high tech tenants

International airport & metro area

Directed Energy Directorate
Remote Sites

- Maui, HI (leased land)
    - Relay Mirror Experiment Facility
    - Maui High Performance Computer Center
    - Maui Space Surveillance Complex



- North Oscura Peak, NM
    - Telescope site at White Sands Missile Range
    - Supports Space Imaging R&D (ABL Technology)

Lasers and Microwaves

Synergistic, Complementary and Capable


Radiation Wavelength
. 1µm
1µm
10µm
100µm
1mm
1cm
10cm
1m
10m
100m
Lasers
Microwaves

High Energy Lasers	High Power Microwave s
Small spot: surgical attack	**Flood target area: multiple simultaneous targets**
Affects targets from outside: structural destruction	**Affects components inside: electronic disruption**
Weather sensitive: clouds, dust, molecular absorption	**Weather insensitive: sees through clouds and dust.**
Modest apertures: glass mirrors, coatings	**Big apertures: metal antennas, ground planes**

But on the other hand,... they both

- **Travel at the speed of light to the target**
- **Capable of graduated effects from deny, disrupt, degrade, and destroy.**
- **Minimum collateral damage**

Directed Energy Directorate

Broad Technology Investments



Laser Technology Thrust

Advanced Optical Tech Thrust

High Power RF Tech Thrust

Directed Energy Directorate

12 Major DE Technology Programs


Ground Based Laser Technology Program


Airborne Laser Technology Program


High Power Laser Program

Scalable Multi-Wavelength Laser Program

High Efficiency Electric Laser Program


HPM Sources Program


Remote Sensing

HPM Pulsed Power Program


Large Optics


Space Awareness Program

HPM Applications Program

HPM Effects Program

AFRL
Directed Energy Directorate

Mission

Develop, integrate and transition science & technology for Directed Energy to include high power microwaves, lasers, adaptive optics, imaging and its effects to assure the preeminence of US in air & space

DANGER
HIGH VOLTAGE

Major Technology Programs

Ground Based Laser	Space Awareness
Airborne Laser	HPM Applications
High Power Lasers	HPM Effects
Multi-Wavelength Laser	HPM Pulsed Power
Electric Lasers	HPM Sources
Large Optics	Remote Sensing

AFRL/DE - factoids

- **952 people (Civ, Mil, Contr)**
- **$109M FY00 budget**
- **4,325 acres**
- **757,000 sf of space**
- **Located throughout Kirtland**
- **Sites at Maui & WSMR**

Air Force Research Laboratory

Directed Energy Directorate



Directed Energy Directorate

Director Dr Earl Good
Deputy Col Douglas Beason
Chief Scientist Dr Barry Hogge

Starfire Optical Range
Major Jim Brown
Dr Bob Fugate

Advanced Optics and Imaging
Dr Chris Clayton
Dr Connie Guiliano

Laser Technology
Col Greg Schneider
Dr Harro Ackermann

High Power Microwave Microwave
LtCol Mark Franz
Dr Bill Baker

Technology Assessment
Dr Dave Dinwiddie
Lt Col Terry Franks
Mr Bill Thompson

Integration & Operations
Mr Leonard Contreras

Directed Energy Directorate

Major Kirtland Facilities

Lasers, Optics, Imaging

Starfire Optical Range



Advanced Laser Facility

Argus Facility

Optics Development
& Beam Control Laboratory



Chemical-Oxygen-Iodine-
Laser Facility

Optics Coating & Components Evaluation Laboratory

Laser Effects Test Facility

Directed Energy Directorate

Major Facilities - High Power Microwave

High Energy Microwave Laboratory

High Energy Research
& Technology Facility



Plasma Research
Laboratory

Electromagnetic Energy/RF Effects Laboratory



Electric Research Laboratory

Directed Energy Directorate

Manning



Assigned Personnel
952



Government S&E Education Levels

Directed Energy Directorate

FY00 AFRL PB Resources



AFRL TOTAL S&T: $1,037.98M



Directed Energy Total: $109.11M

Directed Energy Directorate

Potential Areas for Collaboration

- Electric Lasers
- Beam Control
- Large, Lightweight Optics
- Optical Coatings

- High Power RF Sources
- High Power RF Antennae
- Atmospheric Compensation
- Remote Sensing

For Information contact Mr Rich Garcia, AFRL/DEOB-PA (505)846-4583

AiMT Advances in Military Technology
Vol. 4, No. 2, December 2009

Directed Energy Weapons in Modern Battlefield

L. Palíšek[*]

Division VTÚPV Vyškov, VOP-026 Šternberk, s.p., Czech Republic

The manuscript was received on 25 June 2009 and was accepted after revision for publication on 21 September 2009.

Abstract:

The paper deals with electromagnetic threats caused due to Directed Energy Weapons (DEW). The area of interest is focused on HPM (High Power Microwaves) and UWB (Ultra Wide Bandwidth) as an important part of DEW area. Possible impact on electronic structures which can be part of military systems is considered in this paper. Some practical results achieved during experiments related to assessment of electronic equipment vulnerability is provided with overview of immunity of some equipment to HPM and UWB signals at the end of this study.

Keywords:

DEW, HPM, UWB, electromagnetic threats, NEC, vulnerability

1. Introduction

Directed Energy Weapons (DEW) with various principles seem to be more important in the future battlefield. There are several principles which are considered for use in the DEW area. Special optical technologies (lasers), sound technologies as well as microwave technologies are developed and can be used in special weapon systems to disturb military system behaviour or can be used for counter personnel weapons (for example Active Denial System working on frequency 94 GHz, see Fig. 1). DEW has been mainly considered as technologies suitable for less-lethal or even non-lethal technologies which have been subjects of interest within the past years.

Recent developed military systems consist of equipment which is more and more sophisticated and relying on electronics. Very high importance of electronics within the military systems is obvious from development of Network Enabled Capabilities (NEC) which is a key task of the Czech Armed Forces as well as within the NATO (NNEC – NATO Network Enabled Capability). The stage related to "Communication and information sharing" has been topical in recent years and characterised by development of communication networks. Common network infrastructure can be considered as a fundament of integrated NEC environment. Communication network and especially its reliability will have significant influence on mission success. Disturbance of these networks could be obviously critical.

---

[*] *Corresponding author: Division VTÚPV Vyškov, VOP-026 Šternberk, s.p., Olomoucká 1841/175, 785 01 Šternberk, Czech Republic, phone: +420 517 303 638, E-mail: l.palisek@vtupv.cz*

Power electromagnetic fields can be generated by relevant power technologies and focused (directed) towards the target with electronics. Shortcuts like HPM (High Power Microwave) and UWB (Ultra Wide Bandwidth) are widely used in this area as well as HPEM (High Power Electromagnetics) and IEMI (Intentional Electromagnetic Interference). Examples of developed technologies which could be easily used like DEW against electronics are shown in Figs 2-6 (these technologies were offered or presented mainly during relevant conferences in past few years, radiated pulse power was hundreds of MW or higher in frequency range of microwaves).



Fig. 1 Humvee with ADS (Active Denial System) mounted [1]



Fig. 2 HPM system DS-110 (built in suitcase, pulse power 250 MW [2]



Fig. 3 HPM system with antenna array [2]



Fig. 4 HPM system with antenna array installed on a tank [2]

Fig. 5 Electromagnetic System for Selective Car Stopping [2]

Fig. 6 JOLT hyperband system, UWB system [3]

2. Electromagnetic Threats

As it was mentioned in the introduction an important group of DEW technologies, non-lethal technologies, was represented by weapons with use of power electromagnetic field destructive effects.

Next electromagnetic environments are typically considered related to DEW (see Fig. 7):

- HPM: High Power Microwaves, narrowband signals in frequency range from hundreds of MHz up to several GHz, electromagnetic strength at the place of target typically up to tens of kV/m (strong dependence on range).
- UWB: Ultra Wide Bandwidth, pulses with rise time typically in hundreds of picoseconds and with duration of several nanoseconds, electromagnetic strength at the place of target typically up to tens of kV/m (strong dependence on range).

Because HPM and UWB environment is strongly dependent on range and moreover these environments may have a wide variety of wave shapes, their standardization is very difficult. Now there are only few standards which describe HPM and UWB environment generally (e.g. IEC 61000-2-13 [4]). A possible approach is to consider various types of HPM and UWB environments that have been produced and to consider their possible use in the future against sensitive targets. It is always necessary to make relevant analysis of electromagnetic threat where the shortest possible distance from HPM or UWB source is a very important parameter.

2.1. Electromagnetic Strength Assessment

As a typical possible scenario can be considered HPM (UWB) source with real pulse power P = 1 GW and as a worst case special antenna with extremely narrow radiation pattern (G = 40 dB, respectively D = 8 750). Now the expected electromagnetic strength at the place of threatened equipment (system) can be calculated according to next Eq. (1)

$$E = \frac{\sqrt{30PD}}{r} \qquad (1)$$

where P is radiated power, D is directivity of antenna, r is a distance of threatened equipment (system) from radiating antenna.

Note: Eq. (1) is valid only for direct propagation where reflections are neglected. This simplified equation is usually used for the microwave area and short distances.



a) Narrow band extending from ~0,2 to ~5 GHz
b) Not necessarily HPEM
c) Significant spectral components up to ~10 MHz depending on range and application

Fig. 7 HPM and UWB comparison with other electromagnetic threats [4]



Fig. 8 RF energy propagation from source (HPM or UWB) to equipment (system)

It is obvious from Eq. (1) that for most cases (distance of directed energy weapon from equipment (system) is generally tens of meters), it is possible to consider electromagnetic strength up to tens of kV/m.

2.2. *Critical Frequencies Assessment*

It is very useful to consider transfer function (*T*) of investigated equipment (system) for critical frequencies assessment. Transfer function T_O (outer) is combined with T_I (internal) to form a composite transfer function from incident fields to response box inputs in Fig. 9 [5]. Note: T_O typically corresponds to relationship between incident electromagnetic field and surface current and charge densities on the outer surface. T_I corresponds to transfer function from the surface current and charge densities on the outer surface to some interior port of interest, producing voltage and current waveforms there.

From Fig. 9 it is obvious the most important part related to critical frequencies of considered system (equipment) is band 2 – resonance region. It is possible to use first of all analysis where sizes of equipment (system) as well as used cable lengths are considered and next it is important to make relevant measurement of transfer functions (shielding effectiveness of used boxes, induced currents and voltages etc.) for transfer function (*T*) assessment.

Considered frequency spectrum is divided as follows [5] (see Fig. 9):

Band 1: $f \le f_l \approx \dfrac{c}{4l}$ (aperture and small antenna coupling region),

Band 2: $f_1 \le f \le f_h \approx \dfrac{5c}{l}$ (resonance region, external and internal),

Band 3: $f_h \le f$ (integration region),

where l is characteristic dimension of the object, c is speed of the light, f is considered frequency.



Fig. 9 System response as a function of frequency (logarithmic scales) [5]

3. HPM and UWB Impact on Electronics

Electronic systems can be affected by high intense electromagnetic fields causing the disturbance or even the permanent damage of the system. According to relevant EMC (Electromagnetic Compatibility) standards next performance criteria are usually used:

A - normal performance within the specification limits

B - temporary loss or degradation of function (self-recoverable)
C - temporary loss of degradation of function, which requires operator intervention or resetting
D - degradation or loss of function which is not recoverable due to damage of equipment (components) or software damage

On the one hand performance criteria are a very important parameter on the other hand consequence of IEMI (Intentional Electromagnetic Interference) attack has to be considered too. For consequence scaling it is possible to use for example such terms like "very limited", "limited", "severe", "very severe" and "catastrophic" [6].

4. Vulnerability Assessment

First of all it is necessary to make analysis where electromagnetic threat assessment is done (see chapter 2). Moreover it is necessary to consider criticality of relevant system (consequences – see chapter 3). Finally testing plan and testing can be prepared. The best way is to start with transfer function measurements (shielding effectiveness measurement, induced currents and voltages measurement) which is possible to carry out in wide frequency range up to few GHz or higher. After that it is necessary to choose possible critical frequencies according to transfer function measurements and according to analysis. Chosen frequencies can be used for final high power electromagnetic field measurement with HPM and UWB simulator use. Possibilities of these simulators are restricted to parameters which cannot be changed or changing these parameters takes too much time. Due to this fact it is necessary to choose suitable parameters according to analysis and transfer function measurement results for this testing. The data gained from analyses and testing has to be considered together with possible consequences which can occur. Such data can be used for vulnerability assessment.

5. Practical Results

A lot of experiments related to electronic equipment vulnerability have been carried out in previous projects within the last few years.

Transfer function measurements were carried out for better understanding of electromagnetic field coupling into relevant cables. Tested cables were irradiated with electromagnetic field with vertical polarisation and induced voltages were measured in frequency range 30 MHz to 1 GHz. It was low power measurement, electromagnetic strength of incident electromagnetic field was 1 V/m and measured results were recalculated for expected high power electromagnetic field 10 kV/m. Mainly cables which are widely installed in computer technologies were used for the purpose of these experimental measurements. Few examples are shown in Figs. 10-12. It is possible to expect induced voltage levels on regular widely used cables approximately up to 1 kV during electromagnetic field incidence with electromagnetic strength 10 kV/m on the basis of presented results. The highest induced voltages occur when the length of cables is comparable with wavelength of used signal (resonant region, see Figs. 10-12). For lower frequencies as well as for higher frequencies induced voltages are becoming lower.



Fig. 10 Induced voltages on USB cables for electromagnetic strength E = 10 kV/m



Fig. 11 Induced voltages on SATA cables for electromagnetic strength E = 10 kV/m



Fig. 12 Induced voltages on IDE cables for electromagnetic strength E = 10 kV/m

Other kinds of experiments in this area are testing with high power electromagnetic field irradiation of possible "targets" and evaluation of effects which can occur.

Some examples of tested setups are shown in Figs 13-15. It was verified that HPM signals can be used for stopping the car engine (see Fig. 13, HPM generator working on frequency 3 GHz with pulse power 500 kW was used for this experiment in shielded semi-anechoic chamber) as well as for effective disrupting of computer technologies and data transfers (see Figs. 14-16). Standard performance criteria (see chapter 3) are usually used for the evaluation of effects. From experiments which were carried out it was obvious that electromagnetic strength of few kV/m can be enough to achieve effective disturbance on electronics.

Repetition rate as a parameter of HPM and UWB signals can have an influence on some kind of temporary failures (see Fig. 16). Overview of immunity of some equipment to HPM and UWB signals is shown in Fig. 17. Typical electronic equipment was tested against effects of HPM 3 GHz, 6 GHz, and 9 GHz signals with pulse widths in hundreds of ns, repetition rates in hundreds of Hz and against effects of UWB signal with rise time of 0.5 ns, pulse duration of 3 ns in single shot regime. The most effective signal to disturb electronics from used ones was HPM 3 GHz. Very often the sensitivity level was very close to damage level (see Fig. 17). For UWB signal it was more typical to achieve temporary failures (sensitivity level) rather than some kind of damage. The results from testing showed the most vulnerable parts of recent systems are computer technologies including data transfers.



Fig. 13 Stopping the car engine with HPM irradiation use (HPM 3 GHz)



Fig. 14 PC setup irradiated with HPM 9 GHz



Fig. 15 Data transfer through UTP cable irradiated with UWB signal



Fig. 16 UTP 2 m irradiated with UWB



Fig. 17 Sensitivity and damage levels comparison for tested equipment against HPM and UWB effects

6. Conclusion

Electromagnetic threats HPM and UWB as a part of DEW technologies were briefly defined in this paper. Electromagnetic threats assessment as well as vulnerability assessment was introduced. Vulnerability of chosen tested equipment was presented on relevant examples. It was demonstrated that electronic equipment was vulnerable due to electromagnetic field irradiation. In case sensitive electronic equipment is used in crucial applications it is necessary to evaluate vulnerability of the system to such threats.

Gained results in the past have lead to starting a new project for the Ministry of Defence of the Czech Republic (OSPROZ-DEW1) focused on the assessment of vulnerability of weapon systems and parts of communication and information systems integrated in NEC which are installed to ordnance of the Army of the Czech Republic now. Assessment will be carried out on the basis of relevant analyses as well as relevant experimental measurements. The project started in 2009.

References

[1] *Wikipedia* [online]. Wikipedia, the Free Encyclopaedia. [cited 2009-09-15]. Available from: <http://en.wikipedia.org/wiki/Active_Denial_System>.

[2] *DIEHL Defence* [online]. DIEHL Defence. [cited 2009-09-15]. Available from: <http://www.diehl-bgt-defence.de>.

[3] GIRI, DV. *High – Power Electromagnetic Radiators: Nonlethal Weapons and Other Applications.* Cambridge (Massachusetts) and London : Harvard University Press, 2004. 194 p. ISBN 0-674-01569-X.

[4] International Standard IEC 61000-2-13 *Electromagnetic compatibility (EMC) – Part 2-13: Environment – High-power electromagnetic (HPEM) environments – Radiated and conducted*. 1st ed., 2005.

[5] TAYLOR, CD. and GIRI, DV. *High-Power Microwave Systems and Effects*. Washington : Taylor and Francis, 1994. 199 p. ISBN 1-56032-302-7.

[6] MANSSON, D., THOTTAPPILLIL, R. and BACKSTROM, M. Methodology for Classifying Facilities With Respect to Intentional EMI. *IEEE Trans. on Electromagnetic Compatibility*, 2009, vol. 51, p. 46-52. ISSN 0018-9375.

Acknowledgement

This paper is a part of study of the project OSPROZ-DEW1 "Defence capabilities against DEW – Vulnerability assessment of weapon systems and infrastructure C2" supported by the Ministry of Defence of the Czech Republic.

will be available to treat and possibly cure diabetes, hemophilia and other life-threatening and chronic illnesses.

Space manufacturing will develop the new metal alloys needed for high-temperature processing using advanced nuclear and fusion energy sources. Larger and more perfect crystals for the electronics and other industries will be produced.

By themselves, these new industries created by exploiting the unique environment of space, "pay" for the NASA programs. But the indirect impact to the economy has been even greater, and more important. These are the so-called "spin-offs" from space exploration which have been developed by industry using technological breakthroughs funded by NASA.

New materials, such as refractory ceramics and new alloys which withstand the temperature extremes of space flight, are used in everything from nuclear power plants to everyday kitchen implements. Developments in electronics, including miniaturization and sophisticated automation techniques, have streamlined the functioning of industry and shortened the time (thereby increasing the productivity) of almost everything we do.

The machines that monitor all of the vital bodily functions of the astronauts who walked on the Moon, now monitor premature infants in incubators, and have provided heart monitors and miniaturized pacemakers for thousands of people.

The same qualitative impact, magnified many times, will result from the development of beam weapons combined with the recommitment of the civilian space program to establish a permanently manned station in space toward the goal of colonizing the Moon and other planets.

However, studies done by Chase Econometrics and confirmed by independent studies using the Fusion Energy Foundation's econometric model show that there is a much greater impact that the development of a qualitatively new technology has on an economy. This impact is, strictly speaking, not measurable by adding up all the new products and new techniques that a new technology introduces; it is the *increase in productivity* throughout the economy as the result of the combination of higher manpower skill levels and new scientific knowledge entering industrial production. One study of this induced productivity effect estimated that U.S. productivity increased 0.1 percent for every billion dollars spent on the space program. This change in productivity alone represented an additional $3 billion to the GNP every year it was present. An interesting comparison is possible between the expenditure of a $1 billion aliquot of the federal budget on a high-technology R&D oriented program (like the Apollo program or the development of a beam weapon) and its expenditure on transfer payments, bureaucratic services, or the like. The Chase Econometrics study showed that the expenditure of this money on high-technology R&D actually *lowered* inflation, while the other expenditure had the opposite effect, raising inflation by 0.2 percent.

Four types of directed-energy weapons

by Mary McCourt

In his *EIR* multi-client report, *Beam Weapons: The Science to Prevent Nuclear War,* Dr. Steven Bardwell describes the types of beam weapons on line for development. Each type, laser beams, particle beams, microwave beams, and plasma beams, is, Bardwell states, "in principle capable of generating the required power and energy [to reach and disarm its target] in a form efficiently absorbed by the missile." A beam weapon effectively disarms a nuclear warhead. A hydrogen bomb can be detonated only by an initial powerful atomic-bomb explosion capable of setting off a chain reaction in the lithium-deuterium fuel. A beam weapon, by pumping energy into the very delicately balanced triggering mechanism, prevents the initial explosion and essentially turns the warhead into a "dud." The missile, like a satellite, might fall to the earth, but it can no longer be detonated.

Scientists agree that laser-defense battle stations, even with the lowest level of laser-beam technology, can be defended from other beam weapons themselves. But a missile cannot be effectively defended from the beam without such massive protection that it would lose both the necessary speed and distance.

Laser-beam weapons

Laser beams, particularly the chemical laser, will likely be the first deployable beam weapons developed. A laser is a beam of very intense, single wavelength electromagnetic waves, either of light or high energy X-rays. Such a weapon can be focused very precisely because either the light or X-ray wavelengths all have the same frequency and phase. The five different types of lasers, which can be applied to fusion energy as well as beam weapons, are all being researched at U.S. laboratories.

The **chemical laser,** which could be developed for military deployment within five years, uses a gaseous medium in which a chemical reaction is induced. The product of the reaction emits laser light. The Soviet Union used such a laser last year in tests that downed a ballistic missile.

In a **gas laser,** a burning gas such as a hydrogen and fluorine mixture is suddenly compressed, and the energy distribution that results from the compression is then stimulated to emit single-frequency light waves at very high energy. Both the United States and Japan are currently using huge gas lasers for nuclear fusion development.

An **electron discharge laser** uses replaceable energy

© 1982 EIR News Service Inc. All Rights Reserved. Reproduction in whole or in part without permission strictly prohibited.

from an electron beam to create the source of laser light. Such a laser would be very efficient for use in space because its energy source is electricity, not an exhaustible chemical fuel.

Two other types of lasers, **X-ray lasers** and **free-electron lasers,** yet to be perfected technologically, have greater advantages of energy density and flexibility than those listed above. The **X-ray laser** is widely recognized as the most promising long-range laser for ballistic missile defense, based in space. The X-ray laser, which is just a single pulse, is by far the most energy-dense, delivering thousands of times more energy per pulse than conventional lasers. In addition, the target absorbs the X-rays very efficiently, making this weapon capable of very efficient destruction of missiles.

Particle-beam weapons

Particle beams also deliver energy in a highly controlled pulse traveling at near the speed of light. But instead of a pulse of intense electro-magnetic radiation, the particle beam consists of **subatomic particles, (electrons** or **protons), neutral atoms** (usually hydrogen), or (usually magnetized) **macroscopic particles** accelerated to high speeds. A particle beam destroys its target, the triggering mechanism, by creating a very intense shock wave within the mechanism, like a very small, but extremely heavy and powerful hammer striking down on the target.

Electron beams can be generated in the range of millions of volts. Scientists researching the electron beam for military or civilian energy use have discovered that the electron beam becomes a complex structure of electrons and a magnetic field. Such structured beams are capable of carrying higher currents and more energy for much longer distances at much great levels of power output.

Proton beams, which have been researched intensively for the past 30 years, use an electron beam as a seed and then are accelerated in their own right. As protons are 2,000 times heavier than electrons, a proton beam of the same velocity has 2,000 times the energy of an electron beam.

Neutral particles eliminate many of the problems of charged-particle beams, which can degrade both the efficiency and controllability of the beam. By spring of 1983, U.S. researchers will have produced a beam of protons at an energy of 2.5 million electron volts, capable of traveling at 99 percent of the speed of light.

Control and targeting of a **macroscopic particle beam** would be more difficult, but the unparalleled power density of the beam—due to the large mass of the particles—gives it great potential as a beam weapon.

Microwave and **plasma beams** have only been discussed in the United States in the past two years, although it is estimated that the Soviet Union is two or three years ahead in the production of microwaves. Intense, directional microwaves are generated when electron beams are propagated at or near the speed of light through a plasma. Such beams, if focused, could destroy delicate electronic equipment in a target.

A plasma beam consists of the highest energy-dense form of matter, a gas so hot that the electrons and neutrons have separated. The plasma forms itself into a complex structure of particles and magnetic fields. The unique feature of a plasma beam is that it actually requires the atmosphere, which hinders the guidance and propagation of other beams, to hold in the plasma and sustain the structure.


Space-based Beam Weapon System
Orbital Beam or Laser Battlestation
Early Warning
Probe-carried Infrared Sensors
Launch
Command and Control
Ground-based Beam Weapon System
Beacon Transmitter & Data Link
Orbital Mirror
Focused on Target
Hardened Laser Site

Executive Intelligence Review Special Reports

Space-based beam weapons, (left) provide the only feasible means for area defense against nuclear-armed ballistic missiles. The deployment of a weapon capable of generating an intense beam of laser light, atomic particles, or plasma, in an orbit around the earth, would protect the entire United States from incoming ballistic missiles. **Ground-based beam weapons** (right) can provide both area and point defense. Shown here is a conceptual design of a laser beam-weapon system built on a mountaintop, which uses a relay mirror to provide aiming and tracking for the weapon.

ResearchGate

See discussions, stats, and author profiles for this publication at: https://www.researchgate.net/publication/242532678

ELECTROMAGNETIC DIRECTED ENERGY WEAPONS FOR ELIMINATING ELECTRONIC SYSTEMS

Article

CITATIONS
2

READS
40

1 author:

Jan Valouch
Tomas Bata University in Zlín

28 PUBLICATIONS 20 CITATIONS

SEE PROFILE

All content following this page was uploaded by Jan Valouch on 06 March 2015.

The user has requested enhancement of the downloaded file.

ELECTROMAGNETIC DIRECTED ENERGY WEAPONS FOR ELIMINATING ELECTRONIC SYSTEMS

Capt. Dipl. Eng. Jan VALOUCH

Annotation:

The article presents information on the current situation in the development and application of electromagnetic weapons and indicates possible trends of their future employment. Under the term electromagnetic weapons we understand means and systems that use technology generating directed power electromagnetic pulses degrading the activities or destructing the electronic circuits of the enemy equipment. This will also enable to neutralize or completely destroy the operation of information, communication, control, firing and other electronic devices. Electromagnetic weapons are currently in use and greater number of countries realizes the perspectives of their future development.

✶✶✶

1. CURRENT SITUATION OF DEVELOPMENT AND USE OF ELECTROMAGNETIC WEAPONS IN FOREIGN COUNTRIES

Principle of electromagnetic weapon activities

Typical representative of electromagnetic (EMC) weapons are so called **Directed Energy Weapons** (DEW) employing the technology of **High Power Microwave** (HPM). These weapons represent highly sophisticated technology of 21st century. Their destructive effect results from the electromagnetic field and they threaten the operation of all devices equipped with electronic circuits, especially by the effect of arcing, overload or by discharge of single electronic component parts. These weapons have strong physical and psychological impact.

In general, DEW consists of impulse source of energy, source of microwave radiation and antenna. The impulse source transforms accumulated energy to high power electric pulse with the length of duration in units of nanoseconds. Accumulated energy can be in kilo-Joule with the power of gigawatt. In the source of microwave radiation this impulse then acts upon diode and generates a beam of electrons with energy – approx, 400 kV, 10—60 kA. This energy is dissipated by the directional antenna.

Electromagnetic weapons can fundamentally differ in terms of its design and application e.g. according to the used frequency band. EMC wide band weapons emit in wide frequency range but with low density of energy. These equipments are suitable where it is not possible to exactly identify the characteristics of the target – especially its working frequencies. Contrary to the narrow-band EMC weapons emit pulses on individual frequencies with enormously high power. Their action upon the target is very effective since impulse resonate with the known frequency of the attacked device.

Development and application of electromagnetic weapons

Concerning a development and application of electromagnetic weapons we can say that after the EMC weapons emerged from “the unknown” world of classified projects, now they are tuned and EMC weapon capability is enhanced. And they are gradually mounted on suitable carriers – vehicles, aircraft, ships, bombs, missiles and even space ships. The interest is focused not only on single pieces of equipment but also on complete systems incl. sensors and equipment to control the combat functions.

Within the armed forces the employment of EMC weapons have the following advantages:

- very rapid effect against the enemy targets,
- usage irrespective of the weather conditions,
- coverage of a great amount of various targets with minimum need to be informed about their characteristics,
- threat to less available target – under ground,
- operational attack (neutralization, destruction or denial of activities of electronic assets) at selected levels of warfare,
- minimum of collateral destruction in politically sensitive environment and use of this environment after the end of conflict,
- reduction of minimum time for tracking and guidance to target.

USA, Russia, France, China and UK are the countries that achieved the greatest progress in the development and application of electromagnetic weapons. The interest of other countries (Germany, Belgium, the Netherlands, Denmark, Norway …) is for a long time focused on High Power Microwave (HPM) especially on protection against the effects of HPM. As to my opinion this is the beginning of the path for research in the Czech Republic.

Currently, discussions are held on their employment in Iraqi by the U.S. armed forces. They could facilitate quickly eliminate the command and control systems of Iraq and eliminate communication of their forces without any loss of lives and any collateral damage. There were some intentions to employ these weapons of electromagnetic warfare by the U.S. force in Kosovo and Afghanistan at least in trial operation. It is also interesting the assumption that Russian forces used DEW prior the action against terrorists in Moscow theatre in 2002. This weapon was designed to disable the electronic detonating primers. The fact is that no Chechen managed to initiate her primer.

Misuse of electromagnetic weapons

More frequent are the attacks of terrorists and criminal underworld using the electromagnetic means. Among the targets of terrorists can be financial institutions, medical facilities, aircraft, automobiles, computer network and other daily used civilian and military equipment. The EMC radiation generators can be for example in the briefcase and that is why it is quite easy to prepare such an attack. First known terrorist application of electromagnetic weapons is from 1995 when Chechen rebels used this technology against the security system of Russian facility.

Nobody knows about the use of DEW for criminal activities and terrorist attacks with exception of the offenders themselves and their victims. The German experts even officially recommended application of these means to the German police units since there were recorded several cases of use of DEW by the German underground. With DEW it is possible to commit perfect crime, as they leave no evidence. No doubt, in future a wide use of these weapons can be expected which can means an increased risk of their misuse.

Future of electromagnetic weapons

Future of DEW is often discussed in many articles and literature. A part of study called Air Force 2025 also deals with the future of DEW employment that was developed by the Air University Maxwell Air Force Base, Alabama. This study discusses a possibility to employ these means in the spaceships or satellites in order to destroy the hostile satellite information and communication channels.

Development of DEW in terms of their employment is mainly connected with mutual co-operation of the army, air force and navy forces. These will be the components that are the potential users of DEW. Protection of the aircraft and ships against the effects of enemy DEW is being solved. Further, e.g. active use of DEW against the air defense and employment of DEW in the aerospace. Within 3—5 years it is expected that DEW will be installed into the drones (USA). In respect of technologies for DEW, the research will be especially focused on increase of input power of DEW, reduction of size and weight and improvement of antenna systems. A very interesting is also a research of biological impact of DEW on human being and hazard for the personnel.

2. CURRENT SITUATION IN THE AREA OF ELECTROMAGNETIC WEAPONS IN THE CZECH REPUBLIC

The following part of this article briefly discusses NATO RTO – Research and Technology Organization (http://www.rta.nato.int), or the activities of selected panels with representation of the Czech Republic and which deal with the mentioned issue.

The panels dealing with this topic are:

- SCI–119 Tactical Implications of High Power Microwaves,
- SCI–132 High Power Microwave Threat to Infrastructure and Military Equipment.

Since most of activities of these technical panels is classified as NATO SECRET, only general character information not subject to classification are provided.

Panel SCI–119 Tactical Implications of High Power Microwaves started its activities in 1998 and terminated it in this year. The objective of the work of its members have been mainly solution of issues of use of HPM in the military sector both in terms of defense as well as of potential active employment in attack. The most important areas solved:

- design of resources generating HPM,
- vulnerability of information technology of military infrastructure,
- risk of back effect of electromagnetic weapons on friendly troops,
- testing of HPM effects on the off-the-shelf equipment equipped with electronic components (personal computers, cellular phones, vehicles, aircraft …),
- content of HPM national programs from the viewpoint of:
  - earmarking of specialized workplaces,
  - refinement of the content of solution in the given country,
  - allocation of funds,
  - planning of the number of students studying HPM at the universities,
  - gathering of results.

The issue of HPM is solved by NATO systematically since the beginning of 80-ies of the last century. In the short time, it is assumed that new advanced HPM weapons will be developed and within NATO this process must be systematically controlled. In this area – development of electromagnetic weapons – USA, Russian, France and the UK have the greatest success.

Panel SCI–132 High Power Microwave Threat to Infrastructure and Military Equipment commenced its activity by the introductory session in October 2002, held in Munster in Germany. Its orientation is linked to the preceding activity of the Panel SCI–119. The main activities of the Panel are planned for the period of 2003—2005 and single members will deal with the following issues:

- identification of potential threat of HPM on the military and civilian infrastructure and equipment,

- research of the penetration and dissemination of HPM in specific devices,
- research of DEW (Directed Energy Weapons),
- possibilities how to protect the military equipment against the effect of weapon assets on the basis of HPM.

Other areas considered important by the member of the Panel SCI–132 and that are to be in the area of interest are:

- resistance of military equipment against HPM,
- implication of HPM in the military field test and system of their evaluation,
- EMC terrorism.

The Panel consists of representatives of the following countries: Canada, Czech Republic, Denmark, Germany, France, UK, USA, the Netherlands, Norway and Italy.

CONCLUSION

Currently, the use of electromagnetic weapons plays the more important role. Though, the wider employment of these weapons is expected within 5—10 years, there already exist and are used the devices/equipment capable to reliably effect on the enemy electronic assets (control, information, communication…) and deny the enemy any further operations. The issue of electromagnetic weapons in the Czech Republic is in the stage of research and that is why the representation and involvement of the Czech representatives in the special Panels of NATO RTO or any other international organizations and boards is desirable.

REFERENCES

[1] MUNZERT, Reinhard: Targeting the Human with Directed Energy Weapons, 2002, Erlangen, Germany

[2] MERKLE, Laurence D.: Virtual Prototyping of RF Weapons, 2002, The Air Force Research Laboratory, Kirtland.

[3] COOP, Carlo: The Electro-magnetic Bomb: A Weapon of Electronic Mass Destruction, 2000, Melbourne Australia.

[4] VALOUCH, Jan: Activities of VTÚ PV Vyškov in the area of EMC and DEW, presentation of NATO RTO / SCI–132, 2002, Munster, Germany.

Selection of unclassified documents from the session of Panel NATO RTO/SCI:

[5] SCI–119 Workshop Tactical Implications of High Power Microwaves, Copenhagen, Denmark, 11—13.6.2002.

[6] Open Meeting of NATO RTO/SCI–132 on High Power Microwave to Infrastructure and Military Equipment, Munster, Germany, 22—24.10.2002.

View publication stats

James Madison University

From the SelectedWorks of George H Baker

August, 2011

High Power Electromagnetic Weapons: A Brief Tutorial

George H Baker, III, *James Madison University*

Available at: https://works.bepress.com/george_h_baker/33/

High Power Electromagnetic Weapons: A Brief Tutorial

George H. Baker

Background. High power electromagnetic weapons, also referred to as high power radiofrequency (HPRF) weapons, are a type of directed energy weapons. The system effects of high power electromagnetic environments are well recognized by world scientific and military communities. Former CIA Director John Deutch has said that, "the electron is the ultimate precision-guided weapon." In the course of the investigation ofnuclear EMP effects on electronics during the Cold War period, it became evident that garden variety, unprotected electronics would malfunction, in some cases burn out, in the presence of electromagnetic fields in the hundreds to thousands of volts per meter. The EMP experience has led to the development of non-nuclear high power electromagnetic sources to create fields that equal or exceed EMP levels, albeit over relatively small ranges. Achievable electronic effects could have serious consequences in terms of interruption or termination of critical system operation. The effects are of particular interest to the military in the context of information warfare and missile defense. Because most critical infrastructures are controlled by electronics, HPRF weapons are a concern for civilian systems as well. The weapons could be used to disrupt computer electronics controlling electric power grids, telecommunications networks, financial institution databases, security systems, and aircraft.

Military forces in many countries are pursuing the development of HPRF weapons. These programs are normally classified. HPRF weapons represent a revolutionary concept because they operate at the speed of light, can be used covertly, and harm equipment rather than humans (non-lethal). HPRF weapons may be enclosed in briefcases, packing containers, truck beds, or aircraft and maneuvered to expose critical military or infrastructure systems.

Electromagnetic Weapon Characteristics. There are three elements to be considered in discussing HPRF weapons systems: the weapon itself, the propagation of the weapon output to the target, and the target response (see Figure 1).



Figure 1. High Power RF Weapon Operation Elements

©2011 George H. Baker

Weapon Design. An HPRF weapon consists of a power source, or driver and a radiating antenna. The source is normally pulsed. Outputs may be sine waves (providing a narrow frequency band signal) or pulses (providing a wide frequency band signal). High power electromagnetic source technology includes electron beam devices (magnetrons, vircators, gyrotrons, backward wave oscillators), solid-state devices (bulk avalanche, optical switches, silicon carbide circuits) and explosive generators (magnetic flux compression using high explosives). Output power levels in the gigawatts are feasible over a wide range of frequencies. Design details will determine output characteristics. Power, frequency, bandwidth, repetition rate, and duty cycle are the important HPRF weapon output parameters.

The HPRF weapon source must be connected to an antenna with sufficient gain to "beam" the RF energy to a useful range. Portability requirements impose major limits on antenna area which in turn largely governs the maximum intensity (power per area) that can be delivered to a target system at a given range. Compact sources that may be moved covertly in briefcases, packing containers, truck beds, or aircraft and maneuvered for close-up exposures of critical military or infrastructure systems are of most interest. Antenna size limits largely determine the maximum intensity (power/area) that can be delivered to a target system at a given range. A table of approximate relative portable platform sizes is provided below.

Table 1. Portable Platform Size Comparisons (Approximate)

Capacity: Platform:	Volume	RF system Weight	Basis
Briefcase	0.02 m^3	5 kg	Typical hard side
Footlocker	0.15	40 kg	1 person portable
Pickup truck	4 m^3	1000 kg	1 ton capacity
Econoline van	8 m^3	2000 kg	Bed volume
Tractor trailer	80 m^3	20,000 kg	20 ton capacity

High Power Electromagnetic Wave Propagation. Electromagnetic waves propagate at the speed of light through the atmosphere. Under most conditions, the atmosphere will not attenuate HPRF waves as they travel from source to target. However, if the electromagnetic wave's peak field level exceeds the air ionization threshold a cascade process will occur in which an atmospheric plasma is created that will absorb most or all of the energy in the wave. This phenomenon is referred to as air breakdown.

A typical threshold for breakdown at sea level is approximately 1 megawatt/cm^2 . As an example, a 1 Gigawatt source radiating through a 1-foot radius circular antenna will produce an average intensity over the antenna of 0.35 megawatts/cm^2, a factor of 3 below air breakdown. Once away from the antenna, EM intensity falls off as the beam spreads (typically as $1/4\pi r^2$ where r is the distance to the target).

©2011 George H. Baker

The HPRF signal intensity on target depends on source transmission power (P_t), antenna gain, and range according to the following equation:

$$S_t = \frac{ERP}{4\pi r^2} = \frac{P_t \cdot G}{4\pi r^2} \frac{watts}{m^2}$$

The antenna gain may be approximated by $G \approx \frac{4\pi A_e}{\lambda^2}$ where A_e is the effective antenna area and λ is the wavelength of the radiated HPRF signal. This yields a simple formula for the intensity on target:

$$S_t = \frac{P_t A_e}{r^2 \lambda^2}$$

So, for example, a 1 Gigawatt source radiating at 1 GigaHz ($\lambda = 0.3$m) with a 1-m^2 antenna will produce a beam intensity of 11 kW/m^2 (or 1.1 watts/cm^2) on a target 1000 meters away. If the pulse duration were 1 microsecond, the energy fluence on target would be power x time or, 1.1 microjoules/cm^2.

Target Response. Once the electromagnetic wave signal reaches the target, its energy couples to the system in a very complex manner through various paths associated with the topology of the target system. The HPRF signal will induce currents on any external conductors (antennas, wires, etc) that penetrate to the system interior. The signal will also couple to any external metal shielding and then may reradiate to internal conductors. Signal waves will penetrate through any holes in external shielding to interior portions of the system. The main concern is the amount of energy that finds its way to critical electronic circuits, causing the system to malfunction.

To simplify coupling calculations, it is possible to determine an effective “coupling cross section” for critical internal circuits. In effect, this treats each internal circuit as a receiver. The power received by the circuit may be expressed as a simple function in incident wave power and an effective coupling cross section:

$$P_i = S_t \mathrm{A}_\sigma$$

P_i is the power induced in the internal circuit, S_t is the incident power at the system’s exterior, and A_σ is the coupling cross section of the internal circuit. A_σ is a function of frequency and incorporates all the complexity of coupling including multiple paths, layers and mechanisms. There are two major coupling modes, front door and back door, as shown in figure 2.

©2011 George H. Baker


Antennas
Dishes
Optical Apertures
Direct (Front Door)
- In-band
- Out of band
Coax,
Cable,
Waveguide
Mission Critical
Electronic
Systems
System & Subsystem
Elements
Indirect (Back Door)
- System &
Subsystem
Coupling
Shields,
Apertures,
Penetrations
Coupling through
Cracks, Seams,
Unprotected
Cables

Figure 2. Front Door and Back Door Coupling Modes

The physics of front and back door coupling are the same. In each case, energy resident in the incident wave induces currents in the system that flow to a sensitive system circuit. Each can be characterized parametrically by equation $P_i = S_t A_\sigma$. The coupling cross-section, A_σ, is typically large for front door coupling and small for back door coupling. The coupling cross sections for front door coupling are of the order of the physical area of the antenna or aperture. Effective coupling cross section values for back door coupling of unhardened systems range from $10^{-4} - 10^{2}$ cm^2. Coupling cross-sections are hard to predict analytically and can be determined confidently only by direct measurement. This creates a problem for an attacker's confidence since HPRF effects are subject to much higher uncertainties than conventional weapon effects.

HPRF Weapon Effects on Systems. EMP and HPRF affect systems by disrupting the operation of electronic components either temporarily (upset or latchup) or permanently (component damage). Damage may be "direct" where energy inherent in the EMP/HPRF field is sufficient to cause malfunctions or "indirect" where EMP/HPRF energy triggers effects involving a system internal power supply. Even though the power delivered to a circuit by the HPRF field is small, the much larger energy available in the system's power supply (or fuel and ordnance) can be improperly diverted by an HPRF induced overvoltage arc or malfunction of system digital control circuit, causing major system damage.

Upset refers to an induced change of state in a digital circuit in which the system continues to operate, although possibly with erroneous data bit streams. Latchup refers to changes of state in digital circuits where the affected portion of the system ceases to operate until the system resets itself or (worse) a manual reset is required. In either case, system components are not directly damaged and recovery is often possible (depending on time criticality of affected function).

Exploitation of upset effects should not be discounted. In some cases they are tantamount to permanent damage. Upset may result in major system damage, e.g., a missile plunges into ocean due to a guidance system upset, or computer equipment is destroyed by an upset sprinkler system. Small, upset-level transient pulses can also act to

©2011 George H. Baker

trigger the release of energy from a system's own power supply causing components to burn out at fluences much lower than would normally cause permanent damage.

To give an indication of HPRF wave energies required to cause system effects, ITT industries (formerly Kaman Sciences) openly exposed circuit cards to 2.9 GHz microwave pulses with duration 1 microsecond. Onset of upset occurred at 1 watt/ cm^2 (equivalent to 1 microjoule/cm^2 for this pulse duration). All components were upset at wave intensities of 1000W/cm^2. Onset of damage occurred at 100W/cm^2 (for a 1 microsecond pulse, this is equivalent to 100 microjoules/cm^2). All components were damaged at wave intensities of 1000 W/ cm^2 (equivalent to 1000 microjoules/cm^2).

System Protection. System hardening involves a combination of operational and hardware techniques. Operational techniques may include the provision of spares for soft critical subsystems or boxes, disconnecting susceptible circuits upon warning, and/ or establishment of a physical keep-out perimeter (with barriers and/or security force) or zones around critical equipment to prevent positioning of HPRF weapons at close ranges. Operational controls may also be built into software to provide circumvention and reset, error-correcting codes, voting logic, and status detection. For some non time-sensitive systems, provisions for rapid system repair may be an option.

Conceptually, hardware approaches involve placing a conducting material between the incident HPRF wave and susceptible internal circuits. Hardening techniques have been successfully demonstrated and codified for EMP (ref. article on nuclear EMP). The EMP community has placed a heavy reliance on exterior shielding while limiting the number of penetrations that have to be individually protected. Such protection applied at the system exterior allows interior boxes to go untreated. This approach works well when designed in from the start. For retrofit protection, however, it is often prohibitively expensive.

Hardware approaches for HPRF protection, while conceptually similar, have some differences in emphasis from EMP. Because EMP is extremely broadband, typically only a small fraction of the energy comes through the front door in band. HPRF weapons can be tuned to the front door center frequency such that all the beam energy flows into the system. Also since HPRF weapons operate at higher frequencies, attention to smaller apertures (including cracks and seams) is required and dimensions of waveguide-beyond-cutoff penetration treatments will require changes (longer and more narrow waveguides are needed).

Front door in-band protection is one of the more challenging (but not insurmountable) HPRF protection problems. The high gains associated with most front door paths make these potentially the most susceptible portion of the system. However these well-characterized front door receive paths have received much attention in terms of protection engineering. Radar systems are often protected from their own or neighboring transmitters by a receiver protector or RP. Similar protection can be applied to communication receivers against in band HPRF environments. Table 2 summarizes HPRF hardening techniques.

©2011 George H. Baker

Table 2. HPRF Hardening Methods

Operational Techniques	Hardware Techniques	
	Front Door	**Back Door**
Disconnect on warning	Tuned metallic radomes	Shielding, topology control
Spares	Bandstop reflectors	Internal cable shields
Physical keep-out perimeters or zones	Antenna gain pattern control	Non corrosive mating surfaces
Software Techniques: Circumvention/reset Error correcting codes Voting logic Status detection/ alarm	Filters	Closely spaced fasteners
	TR devices/ limiters	RF gaskets and seals
	Terminal protection devices	Aperture screens and conductive films
		Selection of hard circuits and components
		Pin protection
		Fiber Optics
		Filtering, limiting at penetration points

Future Directions. HPRF generation techniques have matured to the point where practical devices have become technically feasible. Miniaturization of pulse-power source components, more efficient power supplies, and advances in electronic pulse forming, energy conversion, and antennas enable reduced size and increased efficiency of HPRF generation hardware. Simple weapons can also be built using inexpensive magnetrons from common microwave ovens.

Military trends to computerized battle management, weapons tracking, and landline/wireless network communications are a double-edged sword, introducing serious HPRF vulnerabilities. Military use of commercial off-the-shelf equipment and dependence on civilian infrastructure exacerbate the problem. Senior military officials have dropped hints about pursuing offense technology but there are no officially published details concerning weapon availability or capabilities.

Several other countries also have extensive background in the development of RF weaponry. The former Soviet Union pioneered the development of HPRF weapon technology and this technology is now being offered to other countries. According to a recent report from the Office of the US Secretary of Defense on the military power of China, "Captain Shen Zhongchang from the Chinese Navy Research Institute…envisions a weaker military defeating a superior one by attacking its space-based communications and surveillance systems…in future wars, Shen highlights radar, radio stations, communications facilities, and command ships as priority targets vulnerable to smart weapons, electronic attack, and electromagnetic pulse weapons." It is expected that in future conflicts the United States will encounter adversaries using HPRF weapons as part of asymmetric tactics to disrupt information systems.

©2011 George H. Baker

See also: Nuclear Electromagnetic Pulse (EMP)

References and Further Reading

Abrams, M., "The Dawn of the E-bomb," IEEE Spectrum, October, 2003.

Backstrom, M. et al; *Preliminary Study Regarding the Resistance of Critical Societal Systems to High Intensity Electromagnetic Radiation*; Royal Swedish Defense Research Agency; Report FOA-R-97-00538-612-SE; August, 1997.

Barker, R., Schamiloglu, E., *High-Power Microwave Sources and Technologies,* Wiley-IEEE Press, 2001.

Benford, J., Segle, J., *High Power Microwaves*, 2nd Edition, Institute of Physics, 2004.

Guyatt, D. G., "Some Aspects of Antipersonnel Electromagnetic Weapons," ICRC Symposium on the Medical Profession and the Effects of Weapons, February, 1996.

Kopp, C., "The E-Bomb – A Weapon of Electrical Mass Destruction," INFOWAR Conference, Washington, D.C. September 1996.

Lucier, J. P., "Backyard Terrorism - E-Zapper Could Break the Bank," Insight Magazine, April 1, 2002.

McKenna, T., "Flash in the Plan," Journal of Electronic Defence, May 2003.

Price, D. et al, "Compact Pulse Power for Directed Energy Weapons," Journal of Directed Energy, Volume 1, Fall 2003.

Saxton, J., Chairman, *Congressional Hearing on Electromagnetic Weapons*, Joint Economic Committee, Intelligence and Security, Source: http://www.house.gov/jec/hearings/02-25-8h.htm, June 17, 1997.

National Research Council, Technology for the United States Navy and Marine Corps, 2000-2035, Volume 2: Technology, National Academy Press, Washington, DC, 1997.

About the author: George Baker is Professor of Integrated Science and Technology at James Madison University. He also serves as Technical Director of the University's Institute for Infrastructure and Information Assurance (IIIA). He is a consultant in the areas of critical infrastructure assurance, high power electromagnetics, nuclear and directed energy weapon effects, and risk assessment. He served as senior staff on the Congressional EMP Commission. Baker is former director of the Defense Threat Reduction Agency's Springfield Research Facility, a national center for critical system vulnerability assessment. Much of his career was spent at the Defense Nuclear Agency (DNA) as the Integrated Electromagnetics Team Leader directing the development of

©2011 George H. Baker

electromagnetic protection, underground testing, and standards including MIL-STD-188-125, MIL-STD-2169B, and MIL-HDBK-423. He also headed the Agency's Innovative Concepts Division overseeing the joint US-Russian space nuclear power technology, electro-thermal chemical (ETC) gun development, radiofrequency directed energy source concept development and testing, and DNA's university grants programs. Baker received the Agency Legacy Award for his leadership and innovation. He is a member of the NDIA Homeland Security Executive Board, the Institute of Electrical and Electronic Engineers, the Directed Energy Professional Society (Charter Member), and the Association of Old Crows. He is a Summa Foundation EMP Fellow and holds a Ph.D. from the U.S. Air Force Institute of Technology.

©2011 George H. Baker

archived as **http://www.stealthskater.com/Documents/Hamilton_04.pdf**

more of Dan Burisch is at ***http://www.stealthskater.com/Burisch.htm***

note: because important websites are frequently "here today but gone tomorrow", the following was archived from http://www.skywatch-research.org/QuantumHolographic.htm on April 8, 2004 . This is NOT an attempt to divert readers from the aforementioned web-site. Indeed, the reader should only read this back-up copy if it cannot be found at the original author's site.

The Biophotonic Quantum Holographic Matrix

by **William F. Hamilton III**

ABSTRACT: *This paper is an attempt to integrate studies of the quantum potential, quantum holography, biophotonics and the enveloping matrix of biointegration, biocommunication, and bioinformation that composes the web of light and life in living organisms and their possible genesis in an electromagnetic infoton.*

Introduction:

Theoretical physicist David Bohm proposed a new hidden variables theory of Quantum Mechanics. He assumes the wave function does not represent just a set of probabilities but an actual field. This field exists and acts upon particles the same way a classical potential does. Thus it is a quantum potential which is associated to this field and is a function of the wave function. It is postulated here that the quantum potential is active -- as a field -- in living cells and organisms and acts upon them.

The equation Bohm used to represent this quantum potential is:

$$U = -\sum_k \left(\hbar^2 / 2m_k\right)\left(\partial_k^2 R / R\right) \tag{1}$$

Research reveals that Bohmian quantum potential is still used, but that it may only represent a means to extend Quantum Theory into a realistic theory of particles and fields.

It resolves the dilemma of the appearance -- in one and the same phenomenon -- of both particle and wave properties in a rather straightforward manner. Bohmian mechanics is a theory of motion describing a particle (or particles) guided by a wave. This guiding wave is usually attributed to atomic particles. But it might be more insightfully seen as a traveling **soliton** or vortex.

Bohmian mechanics is manifestly nonlocal, and the velocity may depend upon the positions of other -- even distant -- particles whenever the wave function of the system is entangled.

The behavior of the particle is determined by the particle's position and momentum, the wave field, and the sub-quantum fluctuations.

Bohm's quantum potential binds the entire Universe together into what he liked to call a seamless "unbroken wholeness". Every particle in the Universe is connected by the quantum potential to every other particle. He likened the cosmos to a **hologram** in which each point on the film carries information about the entire picture. Bohm's GWT -- far more sophisticated than de Broglie's crude version -- is a "holistic" vision in which all parts of the Universe are joined to every other part. "Interconnectedness" was one of Bohm's favorite words. He saw the Universe as resembling the unity of a living organism. A kind of pantheism not unlike Spinoza's -- a pantheism Einstein himself favored.” **[2]**

Bohm referred the holomovement as the basic reality. The pattern formed on a photographic plate by light waves that interfere and create a hologram. This pattern is the interaction or interference pattern of two parts of a laser light (coherent light). One beam reflects off an object, the other off a mirror. In addition, any portion of the holographic plate contains information on the whole object.

Biohologram:

Every cell in the human body contains nuclear DNA. Information on the whole body -- much like a hologram -- only the cells can go through a process of division and reproduction (mitosis).

In quantum holography, things are spookier still. While holograms are typically constructed with interfering beams of light, in quantum holography the researchers measure the simultaneous arrivals of an illuminating photon that is sent into a chamber and a companion photon in the other entangled beam.**[2]**



Quantum holography -- as depicted in this cartoon -- is a way that physicists could produce 3-dimensional images of objects that would be invisible to systems relying on classical physics. A source **S** produces 2 photon beams (**h_1** and **h_2**). The photons in **h_1** are quantum mechanically **entangled** with the photons in **h_2**. When a photon in **h_1** enters chamber **C**, it encodes 3-dimension information about the enclosed object (in this case a Grecian bust) in the interference of the 2 paths it could take -- a path that intercepts the object and subsequently is reflected to the chamber wall, and a path that misses the object and strikes the chamber wall directly. The second beam **h_2** passes through conventional optics and strikes a detector array **D**. A coincidence counter extracts the holographic information by monitoring the relative time between a photon in **h_1** striking the chamber wall and its entangled mate in **h_2** arriving at detector **D**.

Wave Genetics Inc. and the Moscow Institute of Control Sciences are exploring a new concept of the genetic code that asserts:

(1) that the evolution of biosystems has created genetic "texts" -- similar to natural context dependent texts in human languages -- shaping the text of these speech-like patterns.

2) that the chromosome apparatus acts simultaneously both as a source and receiver of these genetic texts, respectively decoding-and-encoding them.

3) that the chromosome continuum of multicellular organisms is analogous to a static-dynamical multiplex time-space holographic grating, which comprises the space-time of an organism in a convoluted form.

That is to say, the DNA action -- theory predicts and which experiment confirms -- is …

(i) that of a "gene-sign" laser and its solitonic electro-acoustic fields, such that the gene-biocomputer "reads and understands" these texts in a manner similar to human thinking but at its own genomic level of "reasoning". It asserts that natural human texts (irrespectively of the language used) and genetic "texts" have similar mathematical-linguistic and entropic-statistic characteristics, where these concern the fractality of the distribution of the character frequency density in the natural and genetic texts and where -- in case of genetic "texts" -- the characters are identified with the nucleotides, and

(ii) that DNA molecules -- conceived as a gene-sign continuum of any biosystem -- are able to form holographic pre-images of biostructures and of the organism as a whole as a registry of dynamical "wave copies" (or "**matrixes**”) succeeding each other. This continuum is the measuring, calibrating field for constructing its biosystem.

“Complex information can be encoded in EM fields, as we all know from coding-and-decoding of television and radio signals. Even more complex information can be encoded in holographic images. DNA acts as a holographic projector of acoustic and EM information which contains the informational quintessence of the biohologram. Only 3% of human DNA encodes the physical body. The remaining 97% of the 3 billion base pair genome contains over a million genetic structures -- called transposons -- that have the capacity to jump from one chromosomal location to another (Kelleher, 1999). We are 99.9% alike in our genetic legacy. Our individuality is expressed in 3 million small variations in our cells called single nucleotide polymorphisms.

"**Gene-expression** is the mechanism by which new patterns are called into being (Rossi, 2000). There is also a strong correlation between modulation of the brain’s EM field and consciousness (Persinger, 1987; McFadden, 2002). The Gariaev group has discovered a wave-based genome and DNA phantom effect which strongly supports the holographic concept of reality (Miller, Webb, Dickson, 1975). This main information channel of DNA is the same for both photons and radio waves. Superposed coherent waves of different types in the cells interact to form diffraction patterns, first in the acoustic domain and second in the electromagnetic domain -- a **quantum hologram** -- a translation process between acoustical and optical holograms.” **[4]**

The distribution of the character frequency in genetic texts is fractal, so the nucleotides of DNA molecules are able to form holographic pre-images of biostructures. This process of "reading and writing" the very matter of our being manifests from the genome's associative holographic memory in conjunction with its quantum nonlocality. Rapid transmission of genetic information and gene-expression unite the organism as holistic entity embedded in the larger Whole. The system works as a biocomputer -- a **wave biocomputer**.

The quantum nonlocality of the genetic information is fundamental. Experimental work of the Gariaev group shows how quantum nonlocality is directly related to laser radiation from chromosomes (coherent light), which jitterbugs its polarization plane to radiate or occlude photons. DNA and the genome have now been identified as active "laser-like" environments. Roughly speaking, DNA can be considered as a liquid crystal gel-like state that acts on the incoming light in the manner of a solitonic lattice. **[5]**


DNA the molecule of life
Trillions of cells
Each cell:
46 human chromosomes
2 meters of DNA
3 billion DNA subunits (the bases: A, T, C, G)
Approximately 30,000 genes code for proteins that perform most life functions
chromosomes
cell
gene
DNA
protein

Biophotonics

This entire section is extracted from the History of Biophotonics website:

Around 1923, Alexander Gurwitsch discovers an "ultra-weak" photon emission from living systems (onions, yeast, ...), since he suggested connections between photon emission and cell division rate. He calls this **photonemission "mitogenetic radiation**". His experiments indicate that the wavelength is in the range around 260 nm (Bibliography under Gurwisch and also Ruth (1977, 1979)).

Around 1950, Russian scientists rediscover "ultra-weak photon emission" from living organisms. Most results are published in "Biophysics" (Engl.) and originally in "Biofizika"). (Bibliography under Ruth, 1979).

Italian nuclear physicists discover by chance "bioluminescence" of seedlings. They do not think that this finding is significant, but they publish the results (Colli et al. 1954, 1955, Ruth 1979).

The Russian biophysicist and the American chemist enunciate the first theory of ultra-weak photonemission (UWPE) from biological systems -- the so called "**imperfection theory**". UWPE shall be an expression of the deviation from equilibrium -- some kind of distortion of metabolic processes (Zhuravlev 1972, Seliger 1975, Ruth 1979).

Independently from each other and by different motivations, scientific groups in Australia (Quickenden), Germany (Fritz-Albert Popp), Japan (Inaba), and Poland (Slawinski) show evidence of ultra-weak photon emission from biological systems by use of modern single-photon counting systems. Bibliography (Quickenden, Inaba, Popp &Ruth, Slawinski).

While Quickenden, Slawinski, and Inaba prefer the imperfection theory, Popp and his group enunciate just the opposite theory:

1. The radiation originates from an almost perfect coherent photon field.

2. Essential sources are the DNA and corresponding resonators in the cells.

3. The mechanism describes photon storage in cavities and information channels, tuned by Casimir forces.

4. There is a close connection to delayed luminescence which corresponds to excited states of the coherent photon field.

5. The radiation is not the product but essentially the initiator of chemical reactions in the cells. The radiation submits the information within and between cells.

6. The radiation is not limited to the optical range but follows an **f = const** rule (the occupation probability of the phase space is equal for all wavelengths) and extends to longer wavelengths including the so-called heat radiation of the body.

7. This radiation is the proper regulator and information carrier of life.

The Marburg group of Fritz-Albert Popp calls this phenomenon "**biophotons**" in order to stress the difference to "bioluminescence". Biophotons are single quanta which are permanently-and-continuously emitted by all living systems. They are subjects of quantum physics, and they display a universal phenomenon attributed to all living systems. Worldwide, all scientists who agree with these statements call the radiation "biophotons" and the scientific field "**biophotonics**".

From 1972 to 1980, the Marburg group of the leader -- the physicist and Dr. Habil Fritz-Albert Popp -- evaluated experimentally all the essential physical properties of biophotons.

1. The intensity ranges from a few up to some hundreds photons/(sec-cm^2).

2. The spectral distribution follows in the time average an **f = const** rule.

3. The modes are strongly coupled.

4. The delayed luminescence that approaches continuously the biophoton emission follows a hyperbolic rather than an exponential relaxation function.

5. The biophotons origin from an almost fully coherent field.

6. Cells are able to establish cavity resonators which contribute to biophoton regulation.

7. The essential source of non-equilibrium biophoton emission is the DNA.

This group introduces the first time photocount statistics (PCS) into biophotonics. They show evidence that biophotons are emitted according to a Poissonian PCS. Furthermore, they show evidence that (1) the delayed luminescence follows a hyperbolic relaxation function rather than an exponential one; (2) the modes are strongly coupled; and (3) there are hyperbolic oscillations around the continuous hyperbolic relaxation function. The group finds the first time intercellular communication by means of biophotons. Later this was confirmed by Albrecht-Bühler (Bacteria), Popp and Chang (dinoflagellates), Galle (daphnia), Shen (blood), and Vogel (bacteria).

(Bibliography under Popp and coworkers, i.e., Bahr, Böhm, Grass, Grolig, Herrmann, Kramer, Rattemeyer, Ruth, Schmidt, Wulle, Albrecht-Bühler, Chang, Galle, Shen, Vogel).

The papers of Popp and his group are examined mainly by the group of B. Chwirot (Kopernikus University, Torun). They confirm the essential results (Bibliography Chwirot et al.).

Herbert Klima (Atom Institute Vienna) performs his dissertation in Popp`s group at the University in Marburg. He transfers "Biophotonics" to the University in Vienna -- in particular investigations on laser excitation of living systems.

(Bibliography Klima or Atominstitut Wien).

J.Slawinski cooperates with the groups in Japan, USA and the Popp-group in Germany. He follows mainly the links between biophotons and biochemical reactions. There arises a branch biochemical biophotonics that becomes an essential part mainly in Japan and USA.” **[6]**

Bioinfotons

This term “**bioinfoton**” is one that I am adopting to specify any particle (such as the **Ganesh Particle***), wave, or biomolecule that transfers information from an emitter to a receptor. It is possible that if a biophoton is emitted from a coherent source that it will carry holographic information as a form of modulation (possibly frequency-modulated) and produce action or results in biological systems.

It is possible that biophotons may even be carriers of ***psi*** information and that a coherent coupling can be established between 2 conscious lifeforms resulting in a transference of information from a higher potential field to a field at lower potential. Even though this is conjecture at this point, it suggests other means by which disparate lifeforms can communicate. We know there is a process by which trees communicate and even signal each other in the face of danger. We may be exchanging information with pets and other animals through biophotonic communication. This may be how some people who have a "green thumb" affect plants they care for.

Even communication with other intelligent life forms in the Cosmos may be effected by the amplification and vectoring of biophotons or -- via the quantum potential -- produce information at a distance.

A virtual photon flux in the quantum potential may be integrating the coordinated wholeness of the organism while the action of bioinfotons may keep every part of the organism in communication with every other part.

Conclusions

Life and living organisms are more than the sum of their parts and are composed of material and non-material parts. The spiral form of DNA evidently produces an electromagnetic wave field that informs the organism's growth and structure.

Scientist Richard Alan Miller is a pioneer in this field and has written:

"In a hologram, wave fields interfere with one another to lay the foundations for the reconstruction of the image of an object. But how are the wave fields produced?

The term "holography" comes from the Greek roots meaning "entire" and "to write". In holography, the image is projected by a coherent light source split into both the object wave and the reference wave background. This dichotomous nature is reflected in the particle/wave nature of the DNA molecule, which can be "read out" with biophotons from chromosomes to set up a holographically-produced wave field. This superposition of wave fields (object wave and reference wave) creates a wave guide for the formation of biological structure. The image is constructed according to the reference information contained in the genes. The reconstructed object wave is identical with the object wave field. The reconstructed wave fields reproduce exactly the recorded ones (the DNA with genetic code)." **[7]**

Mr. Miller also proposes this hypothesis:

> **"QUANTUM BIOHOLOGRAPHY**
>
> **Hypothesis: The organization of any biological system is established by a complex electrodynamical field that is, in part, determined by its atomic physiochemical components. These, in part, determine the behavior and orientation of these components. This dynamic is mediated through wave-based genomes wherein DNA functions as the holographic projector of the psychophysical system -- a quantum bioholograms."**

I propose that the biohologram is embedded as an integral part of the biocosmic hologram we call the"Universe".

Dr. Dan Burisch has seen evidence that a **Ganesh Particle*** can transmute itself into a fully functional atypical eukaryotic cell in a matter of seconds -- not eons. Such evidence -- when it becomes available -- will change our entire perspective on the existence of a universal holonomic mind that informs its creation.

**Ganesh Particles are charged clusters that extracted from ancient bedrock and have a seemingly unknown origin, but carry information which is transferred to cells via a crossbridge. (discovered by Dr. Dan B.C. Burisch)*

References:

1. **http://plato.stanford.edu/entries/qm-bohm/#qp**
2. **http://www.ksharpe.com/Word/BM05.htm**

3. http://www.aip.org/enews/physnews/2001/split/566-1.html
4. http://www.rialian.com/rnboyd/dna-wave.doc
5. http://www.geocities.com/iona_m/Chaosophy4/bioholography/bioholography.htm
6. http://www.lifescientists.de/history.htm
7. http://www.nwbotanicals.org/oak/newphysics/Helix%20to%20Hologram.pdf

if on the Internet, Press <BACK> on your browser to return to the previous page (or go to www.stealthskater.com)

else if accessing these files from the CD in a MS-Word session, simply <CLOSE> this file's window-session; the previous window-session should still remain 'active'

The Tom Bearden Website

Help support the research

Foundations of Electro-Magnetism
Slide Series

- Major Points of Presentation
- Chung's Carbon Filament Negative Resistor
- Aharanov-Bohm Effect
- Absorption and emission reactions (1)
- Absorption and emission reactions (2)
- Anti-engine for cell's deviation reverses cell back to normal
- Asymmetric regauging produces excess force, which can be used to do work on the system
- Asymmetric regauging produces excess force, which can be used to do work on the regauging system
- Becker's bone fracture healing experiments
- Becker's theoretical control system governing regeneration
- Becker's theoretical DC control system involved with response to injury
- Geometrical Distortion of Poynting Energy Flow
- Cosmic Bootstrap: Before the Big Bang
- Bridging Enables COP > 1

- Aspects of Strong Local Symmetry
- Other Aspects of Strong Local Symmetry
- Bunge on the Status of Electrodynamics
- Bunge on the Status of Electrodynamics and Physics
- Bunge on the Status of Classical and Quantum Physics
- Fractions of BW Casualties Surviving
- First Step in Self-Promotion of Cancer Due to Hypoxia
- Differentiation and Dedifferentiation Timelines
- Evolution of Cells on Earth
- A Charged Particle q is a Coupled System of m and Ø
- The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry (1)
- The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry (2)
- The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry (3)
- A Charged Particle is a Coupled System
- The Anomalies in Navy Electrolyte Experiments at China Lake
- Chung's Carbon Filament Negative Resistor

- Typical circuit has about 10^{-13} energy collection efficiency
- Classical View of EM
- Curved Spacetime acts as source or sink
- Chronic Disease Puzzling
- Cancer Characteristics
- Solving a Cancer Enigma
- Cancer: Characteristics
- Nonlinear Optics Distortion Correction Theorem
- The Electronuclear Reaction: Nuclear Reactions in TR-Zones (1)
- The Electronuclear Reaction: Nuclear Reactions in TR-Zones (2)
- The Electronuclear Reaction: Nuclear Reactions in TR-Zones (3)
- In Time-Reversed Zone: Nuclear reactions are biased
- In Time-Reversed Zone: Dynamics may be reversed
- Time-Reversed Zone: Significant only after time-density charging
- A New Conservation of Energy Law
- Questions on Carcinogens and EM

Radiation

- AS DEFINED, fields and potentials only exist in and on charged matter
- Serious flaws and errors in classical EM theory
- Electrodynamicists' Reaction to Removal of the Material Ether
- Reaction to Loss of Material Ether (1)
- Reaction to Loss of Material Ether (2)
- Some EM waves in Spacetime
- Air Medium Disturbances Generated When Air is Perturbed by a Plucked Taut String
- Launching a Spacetime Perturbation ("EM Wave") from a Wire Antenna
- Phase Conjugate Wavepairs Produce New Waves
- Scalar Electromagnetics (Energetics) View of EM (1)
- Scalar Electromagnetics (Energetics) View of EM (2)

- Scalar Electromagnetics (Energetics) View of EM (3)
- Extended General Relativity Principle
- Extension of Work-Energy Theorem
- 34 Flaws in Classical EM Theory
- MTW's General Relativity Principle
- Use of General Relativity (GR) in Particle Physics
- The Missing Infolded Electrodynamics
- Infolded Engines: Excluded by Present Physics
- Mass curves and structures spacetime; ST curvatures change and structure mass (1)
- Mass curves and structures spacetime; ST curvatures change and structure mass (2)
- At Infinite Velocity: Each Is Every Other
- Lisitsyn's Report: Brain Code Broken
- Lorentz Closed Surface Integration
- Lorentz's physically insignificant energy flow can be collected and utilized
- Lorentz surface integration of the Poynting vector around a closed surface
- Longitudinal EM Photon Interaction with Charge
- Mass is transparent to longitudinal EM waves, which move through the infolded interiors of internal waves, potentials, and fields in the mass.

- Pumping with Longitudinal EM waves Time-reverses the Mass
- Maxwell's Quaternion Theory
- Maxwellian Systems before and after Regauging
- Maxwell's four equations reduce to: Page 1
- Maxwell's four equations reduce to: Page 2
- More to come



Major Points of Presentation

- Electrodynamic is seriously flawed
  - Some major flaws
  - Corrections indicated
- Why past corrective attempts failed
  - Force field concept is material
  - Missing two infolded transforms (M->ST; ST->M)
- Missing infolded general relativity inside electrodynamics
- Several Kinds of EM Waves in Space
  - How to make
  - Transduction
- A French medical example as a deep experimental demonstration
  - Spectacular regenerative cures funded by French Govt
  - Not comprehended, therefore suppressed
- Cold Fusion examples of time-density wave effects
  - China Lake instrumental anomalies in electrolysis
  - Explanation of anomalous behavior of instruments
  - Explanation of new nuclear reactions
  - Wave energy transduction provides excess heat
- Urge theorists to consider dramatically new reactions

Chung's Carbon Filament Negative Resistor

UNIVERSITY AT BUFFALO, NY


Win
CROSSED CARBON
FILAMENT LAYERS
Wout > Win

© [illegible] T.E. Bearden



Aharonov-Bohm Effect

© T.E. BEARDEN 1996

- In field-free regions
  - E-field is zero
  - B-field is zero
- Potentials still exist, just no gradients
  - Cause real effects
  - Interference is the key
  - Contain sum-zeroed substructures
- Does not follow from
  - Mechanics
  - Classical electromagnetics
- Required by quantum mechanics



Absorption and emission reactions

ELECTRON ABSORBS PHOTON ENERGY, MOVES TO HIGHER ENERGY LEVEL. DECAYS BY EMITTING PHOTON

ELECTRON ABSORBS TIME DENSITY, MOVES TO DIFFERENT TIME DENSITY LEVEL. DECAYS BY EMITTING LONGITUDINAL OR PSEUDOLONGITUDINAL PHOTON

© T.E. BEARDEN 1998

PARTICLE ABSORBS ENERGY, MOVES TO HIGHER ENERGY SHELL. DECAYS BY EMITTING ENERGETIC PARTICLE. OBSERVABLE..

PARTICLE ABSORBS TIME, MOVES TO HIGHER TIME DENSITY. DECAYS BY EMITTING TIME-LIKE PARTICLE, NONOBSERVABLE BY PRESENT MEANS.

ENTIRE NUCLEUS ABSORBS ENERGY, EACH PARTICLE ABSORBS OWN. DECAY OCCURS BY COMPLEX MODES, INCLUDING FISSION OR FUSION. DECAY BYPRODUCTS OBSERVABLE.

ENTIRE NUCLEUS ABSORBS TIME, EACH PARTICLE ABSORBS OWN. DECAY OCCURS BY COMPLEX MODES, INCLUDING FISSION OR FUSION. SOME DECAY BYPRODUCTS ARE NONOBSERVABLE (SPACE ABSORBS)



Absorption and emission reactions

TRANSVERSE PHOTON

ELECTRON ABSORBS PHOTON ENERGY, MOVES TO HIGHER ENERGY LEVEL. DECAYS BY EMITTING PHOTON, REMOVING Δt

ΔE
nucleus
Δt coupled and emitted quickly

Figure A. Excited energy density level in one jump.

STREAM OF TIME-POLARIZED PHOTONS

ELECTRON ABSORBS TIME DENSITY, MOVES TO $1/c_2$ DIFFERENT TIME DENSITY LEVEL. DECAYS BY EMITTING LONGITUDINAL OR PSEUDOLONGITUDINAL PHOTONS

Δt
nucleus
Δt increases quasi-statically then slowly decays

Figure B. Excited time density level significant only after enormous number of increases.

© T.E.BEARDEN 1998



ANTI-ENGINE FOR CELL'S DEVIATION REVERSES CELL BACK TO NORMAL

PHYSICAL CELL (DISEASED)
+
EXTENDED TIME DELAY FOR RENORMALIZATION
PHYSICAL CELL (NORMAL)
VACUUM ENGINE FOR DISEASED CELL
VACUUM/SPACETIME ANTI-ENGINE FOR CELL'S DISEASE DELTA

© 1994, 1995 T.E. BEARDEN

By pumping the internal EM channel, process is dramatically accelerated.
This is the body's normal recovery mechanism, within its limits.



Asymmetric Regauging Produces Excess Force, Which Can be Used to Do Work on the System

Net Symmetric Regauging Does No Excess Work on the System

This little bird put one foot on wire A, and then the second foot on wire A also. He *net symmetrically* regauged, so he had no net excess force across him, even though his potential energy was increased. He asymmetrically regauged each foot, but both simultaneously so that one countered the other. Wise little bird!

Net Asymmetric Regauging *Can* Do Excess Work on the System

This little bird put one foot on wire A, and then the second foot on wire B. He *net asymmetrically* regauged, so he had lots of net excess force across him. That force then violently translated his little body parts every which way, doing lots of work in and on him. Bummer!

ⓒ T.E. BEARDEN 1999



Net Symmetric Regauging Does No Excess Work on the System

This little bird put one foot on wire A, and then the second foot on wire A also. He *net symmetrically* regauged, so he had no net excess force across him, even though his potential energy was increased. He asymmetrically regauged each foot, but both simultaneously so that one countered the other. Wise little bird!

Net Asymmetric Regauging *Can* Do Excess Work on the System

This little bird put one foot on wire A, and then the second foot on wire B. He *net asymmetrically* regauged, so he had lots of net excess force across him. That force then violently translated his little body parts every which way, doing lots of work in and on him. Bummer!

ⓒ T.E. BEARDEN 1996

Figure 32. Asymmetric regauging produces excess force, which can be used to do work on the regauging system.

Selected clipart © by Lotus SmartPics™



Becker's bone fracture healing experiments

- Tiny DC currents (picoamperes)
- Pulsed DC current can be utilized
- Pulsed magnetic fields may be utilized

(+)
ELECTRODE
(-)
ELECTRODE
DC
POWER
SOURCE
BONE
BONE
FRACTURE SITE

RED BLOOD CELL DEDIFFERENTIATES

Shucks hemoglobin coat
Grows nucleus

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes cartilage

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes bone
Deposits in fracture site, healing the fracture

© 1993, 1995 T.E. BEARDEN



Becker's theoretical control system governing regeneration*

Trauma Producing Tissue Loss

Local cellular effect

Local nerve effect

CNS effect

Alterations in hormone pattern (prolactin)

Alterations in local DC field pattern

Local electrical effects

Local and systemic pools of target cells

Dedifferentiation into primitive mesenchymal cells

Phase I

Blastema formation

growth

Phase II

Redifferentiation into required cell types

Restoration of body part or tissue

*Becker & Spadaro, "Electrical stimulation of partial limb regeneration in mammals," Bul. N.Y. Acad. Med., 48(4), May 1972, p. 629.



Becker's theoretical DC control system involved with response to injury*

INJURY

INPUT STIMULATION DC SYSTEM (PAIN)

CENTRAL DC SYSTEM

LOCAL CELL INJURY FREE RADICALS

OUTPUT DC SYSTEM

GROWTH DIFFERENTIATION

TOTAL CURRENT OF INJURY DC SYSTEM

STIMULATION OF REPAIR CELLS

MITOSIS DEDIFFERENTIATION

*Robert O. Becker, "The significance of bioelectrical potentials," Bioelectrochemistry and Bioenergetics, Vol. 1, 1974, p. 191.



Geometrical Distortion of Poynting Energy Flow

At or near resonance frequency, in the case shown the energy collection fraction (reaction cross section) increases dramatically.

a. Around an aluminum sphere at light energy 8.8 eV. Absorption efficiency = 18.00.

b. Around an aluminum sphere at light energy 5eV. Absorption efficiency = 0.1.

Figures per Craig F. Bohren, "How can a particle absorb more than the light incident upon it?", American Journal of Physics, 51(4), Apr. 1983, p. 326.



Cosmic Bootstrap: Before the Big Bang:

- *Cosmic repulsion behaved like a fluid with negative pressure*
- *The "universe" inflated (expanded) as a "false vacuum"*
- *As the negative-pressure fluid expanded, its energy went up rather than down*
- *When inflation stopped, the false vacuum decayed from its excited state*
- *Its excitation energy was released in a single great burst*

Paul Davies, Superforce, 1984, p. 194



BRIDGING ENABLES COP > 1.0

S-flow, dϕ /dt flow, and EMF flow

V>>0

source

i ≈ 0

dQ/dt
BLOCKER
(Conductor)

V>>0

i>>0

LOAD

Closed Current
Loop A

Closed Current
Loop B

BRIDGE

Current loop B is asymmetrically regauged by
S, dϕ /dt, and EMF flow from current loop A.

Patent Pending

© 1998 T.E. BEARDEN



Aspects of Strong Local Asymmetry

- If local asymmetry is strong, conservation laws may be appreciably violated
  - Energy
  - Charge
  - Spin
  - Momentum
  - Angular momentum

© T. E. Bearden 1995, 1996

- Properties of an object may differ appreciably for
  - Different observers
  - Different detecting means
  - One time to another
  - One position to another
- STRUCTURING THE INFOLDED EM INSIDE POTENTIALS, FIELDS, AND WAVES
  - Strongly breaks local symmetry
  - Provides spacetime engines giving the above effects



Other Aspects of Strong Local Asymmetry

© T. E. Bearden 1995, 1996

- Local spacetime is curved
- Lorentz invariance of vacuum is violated
- May be a local "sink" or "source"
- Gravitational-inertial effects from EM
- Translation between virtual and observable
- Electrogravitational solitons
- Action at a distance
- Transmutation effects may exist
- Scalar/pseudoscalar field translation
- COMMENT: Thus the use of infolded longitudinal EM fields and waves to strongly break local symmetry allows internested clustering of spacetime curvatures. These spacetime structures are *vacuum engines*, or *spacetime engines*.



Bunge on the Status of Electrodynamics

"... it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state..."

"... the best modern physicist is the one who acknowledges that neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling..."

*Mario Bunge, Foundations of Physics, Springer-Verlag, New York, NY, 1967, p. 176..

© 1996 T.E. BEARDEN



Bunge on the Status of Electrodynamics and Physics

"... it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state...

"... neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling..."

© 1996 T.E. BEARDEN

*Mario Bunge, Foundations of Physics, Springer-Verlag, New York, NY, 1967, p. 176..



Bunge on the Status of Classical and Quantum Physics

"... it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state... the best modern physicist is the one who acknowledges that neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling not only to better cover their own domains but also to join smoothly so as to produce a coherent picture of the various levels of physical reality."

'Mario Bunge, Foundations of Physics, Springer-Verlag, New York, NY, 1967, p. 176..

© 1996 T.E. BEARDEN


Fraction of Casualties Surviving
FRACTION SURVIVING
N = 1 - 40 million
1.0
0.8
0.6
0.4
0.2
0.0
N CASUALTIES
0.1
0.7
0.9
0.95
CASUALTIES
TYPE TREATMENT RECEIVED
© 1998 T. E. BEARDEN
EXPRESSED IN FRACTION SURVIVING
🟩 With conventional treatment
🟨 With 1st generation P-treatment
🟨 With 2nd generation P-treatment
🟥 With 3rd generation P-treatment



FIRST STEP IN SELF-PROMOTION OF CANCER DUE TO HYPOXIA

MULTICELL
AEROBIC*
(INCLUDES MAN)

SINGLE CELL
ANAEROBIC

SINGLE CELL
AEROBIC*

CENTRAL CONTROL

OXYGEN-RICH

TIME-FORWARD
PATH AS IT
DEVELOPED

CANCER CELL

PARTIALLY
ANAEROBIC

SINGLE CELL
AEROBIC

TIME-REVERSED
PATH FOR SUSTAINED
OXYGEN DEFICIENCY

FIRST STEP IN OXYGEN-DEFICIENCY
DEDIFFERENTIATION

© 1993 T.E. Bearden


Differentiation and Dedifferentiation Timelines
CENTRALIZED CONTROL OF CELLULAR GROWTH AND REGENERATION
PRIMORDIAL SINGLE CELL ANAEROBIC
SINGLE CELL AEROBIC
OXYGEN-RICH ENVIRONMENT
NORMAL HEALTHY CELLS AND FUNCTIONS
WITH SOME DISEASED OR DAMAGED CELLS
TIME-FORWARD PATH AS IT DEVELOPED
NORMAL "DEDIFFERENTIATION" FOR HEALING OF CELL DAMAGE
SINGLE CELL MORE ANAEROBIC
SINGLE CELL AEROBIC
TIME-REVERSED PATH FOR SUSTAINED OXYGEN DEFICIENCY
TIME-REVERSED PATH WHEN NORMAL PUMPING FAILS TO HEAL CELL

© 1993, 1998 T.E. Bearden



Evolution of Cells on Earth

ESSENTIALLY ANAEROBIC ATMOSPHERE

CHANGE OF ATMOSPHERE TO AEROBIC (INCLUDES OXYGEN)

BIOGENESIS

SINGLE CELL ANAEROBIC

OBLIGATORY ANAEROBES SINGLE CELL SHIELDED FROM OXYGEN

FACULTATIVE ANAEROBES (SINGLE CELL BOTH AEROBIC AND ANAEROBIC)

EVOLVE TO

SINGLE CELL AEROBIC*

EVOLVE TO MULTICELL AEROBIC* (INCLUDES MAN)

CENTRAL CONTROL

SINGLE CELL COMPONENTS

- IMMUNE SYSTEM
- RED CELLS
- WHITE CELLS
- KILLER CELLS
- ETC.

MULTICELL COMPONENTS

- TISSUES
- MUSCLES
- BONES
- ORGANS
- SKIN
- STRUCTURES

*NOTE: LIMITED ANAEROBIC RESPIRATION STILL TAKES PLACE IN HIGHER AEROBIC LIFE FORMS, INCLUDING MAN.

EVOLUTIONARY TIME

© 1999 T. E. BEARDEN



A Charged Particle q Is a Coupled System of m and ϕ

(A proposed formal definition of a charged mass)

Note: X is a coupling operator

$$q \equiv f_q \times m_q$$

Also note that the ϕ portion of the charged particle can be internally structured, per Stoney-Whittaker-Ziolkowski, with hidden bidirectional EM wavepairs (their sums and products). Note that this constitutes an EM application of Bohm-type hidden variable theory, with many ramifications.

"...curiously enough, we do not know exactly what charge is, only what it does. Or, equally significantly, what it does not do."

M.P. Silverman, And Yet It Moves: Strange Systems and Subtle Questions in Physics, Cambridge University Press, 1993, p. 127.

© T.E. BEARDEN 1997

An electric charge Q consists of a massless flux component and a mass component, coupled together (interacting). Q is a broken symmetry. The mass of the charge continually and violently exchanges virtual photons with the surrounding vacuum.

Thus Q is energetically driven by the surrounding vacuum potential, which itself is to first order just a violent virtual photon flux.



The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry

You really need
a Maxwell's demon,
to do some free work.

Your electrodynamicist
says he can make one,
by regauging.

© T.E. BEARDEN 1999



The Ubiquitous Assumption: *Two* Asymmetrical Regaugings for Net Symmetry

He says he will do the regauging for you. Hey, what a swell guy!

He regauges *twice*, and makes two Maxwell's demons equal and opposite. They won't do any net work for you!

© T.E. BEARDEN 1999



The Ubiquitous Assumption: Two Asymmetrical Regaugings for Net Symmetry

YE OLDE ELECTRO-
DYNAMICIST

He disdainfully says,
"We *always* do it that way!
We *must* enforce local
equilibrium and the second
law of thermodynamics!".

You decide to have a
little chat with your
electrodynamicist!
With friends like that,
who needs enemies!

© T.E. BEARDEN 1999



A Charged Particle Is a Coupled System

(The first formal definition of charge)

$$q \equiv \phi_q \ \mathrm{x} \ m_q$$

Note: X is a coupling operator

© 1994 T.E BEARDEN

"...curiously enough, we do not know exactly what charge is, only what it does. Or, equally significantly, what it does not do."

M.P. Silverman, And Yet It Moves: Strange Systems and Subtle Questions in Physics, Cambridge University Press, 1993, p. 127.

An electric charge q is a broken symmetry in its fierce energy exchange with the active vacuum. It coherently integrates some of the virtual energy absorbs and outputs it as Poynting energy flow.

Chung's Carbon Filament Negative Resistor


UNIVERSITY AT BUFFALO, NY
© 1996 T.E. Bearden
Win
Wout > Win
CROSSED CARBON
FILAMENT LAYERS



Typical circuit has about 10_{-13} energy collection efficiency

Distance traveled by S in one hour is 1.08x10exp(12) meters.

Example: 1.3 amps flowing in DC circuit, 1.8 mm diameter copper wire. J = 51 A/cm ^{2}

d_i = 0.1368 meters

S violently transports ϕ provided from the source.
j ϕ sluggishly transports the energy collected and dissipated in the circuit..

For the case discussed, the electron drift velocity in the circuit is about 3.8 x 10 $^{-5}$ meters/sec. So Jϕ moves about 0.1368 meters in one hour. Thus Jϕ has collected about 0.1368 meters of the ϕ-filled S-tube. During that same hour, the S-flow evoked by the power source will have traveled 1.08x10^{12} meters. The ϕ of both currents is the same. Both are involved in the same energy-filled tube. Thus S has provided and transported about 7.89x10^{12} times as much energy along the circuit in one hour as the jϕ has been able to collect, transport, and dissipate as work in the circuit. Thus this circuit provides about 10^{13} collection efficiency.



Classical View of EM

- Potentials just mathematical conveniences
  - Not real
  - No internal structure, just magnitude
- Force fields primary, causative, can exist in space in absence of observable mass
  - All EM actions due to force fields, none when zero
  - No action at a distance
- Vacuum empty; without energy or structure
  - No locally curved spacetime
  - No gravity effects
  - No quantum effects
- Maxwell's equations complete
  - Symmetrically regauged ***arbitrarily***
  - Topology dramatically reduced



Curved Spacetime acts as source or sink

- May emit excess radiation and energy (e.g., heat)
- May absorb radiation and energy (e.g., cool)
- May transduce waves
  TW ⇔ LW ⇔ TDW
- New energy conservation law applies

© 1998 T.E.BEARDEN



CHRONIC DISEASE PUZZLING

- SCIENCE REALLY DOES NOT UNDERSTAND THE MECHANISMS OF A SINGLE CHRONIC DISEASE, INCLUDING CANCER
- MANY TROUBLING FACTORS EXIST
  - *MIND*
  - *STRESS*
  - *SPONTANEOUS REMISSION*
  - *PLACEBO EFFECTS*
  - *COMBINATIONS*
- GENERATION OF THE PLACEBO EFFECT BY THE CELLULAR REGENERATION SYSTEM IS UNRECOGNIZED

© 1994, 1995 T.E. Bearden



Cancer Characteristics

- Not one disease, but a whole range
- Starts in damaged aerobic cell
- Cell shakes off body's central control
  - Starts uncontrolled division
  - Becomes a lump
- Can send forth cancer cells
  - Through blood
  - Through lymph
- Form metastases (secondary tumors)
- Often become anaerobic

© 1993 T.E. Bearden



Solving a Cancer Enigma

- An enigma has been failure of immune system to attack some tumor cells
  - Suppressor cells may curb immune system?
  - Tumor may lack antigens normally identified by the immune system?
- *Promotion of damaged cell to cancer is usually ordered by cellular control system*
  - *Regenerative and recovery system forces cell back toward anaerobe*
  - *First step breaks free from central growth*
  - *Control continues to recognize cell as self*

© 1993 T.E. Bearden



CANCER: CHARACTERISTICS

- NOT ONE DISEASE BUT A WHOLE RANGE
- STARTS IN ORDINARY (AEROBIC) CELL
- CELL SHAKES OFF BODY'S DICTATORIAL CONTROL*
- STARTS UNCONTROLLED DIVISION
- BECOMES A LUMP
- CAN SEND FORTH CANCER CELLS
  - THROUGH BLOOD
  - THROUGH LYMPH
- THESE FORM METASTASES (SECONDARY TUMORS)
- OFTEN BECOME ANAEROBIC (NON-OXYGEN USING)
- ENIGMA IS FAILURE OF IMMUNE SYSTEM TO ATTACK SOME TUMOR CELLS
  - SUPPRESSOR CELLS MAY CURB IMMUNE SYSTEM
  - TUMOR MAY LACK ANTIGENS NORMALLY IDENTIFIED BY THE IMMUNE SYSTEM

*R&R system forces cell back toward anaerobe

© 1993 T.E. Bearden



Nonlinear Optics
Distortion Correction Theorem

E_1 = INCIDENT WAVE

E_2 = TIME-REVERSED WAVE

© 1994, 1995, 1998 T.E BEARDEN

"If a scalar wave $E_1(r)$ propagates from left to right through an arbitrary but lossless dielectric medium, and if we generate in some region of space [say near z = 0] its phase conjugate replica $E_2(r)$, then E_2 will propagate backward from right to left through the dielectric medium, remaining everywhere the phase conjugate of E_1."



The Electronuclear Reaction: Nuclear Reactions in TR-Zones (1)

- **Nucleon interchange**
  - Changes neutron into proton and vice versa
  - At high rate (flat spacetime assumed)
- **Statistics become skewed due to curved ST**
- **Can bias statistics toward either neutron or proton end**
  - Biases toward transmutation of elements along isomer chains
  - Concept of "isomer" is vastly expanded



The Electronuclear Reaction: Nuclear Reactions in TR-Zones (2)

- Normal dynamics (impulses) may reverse
  - *Like charges attract, unlike charges repel*
  - *Positive charges cluster (are drawn together)*
  - *H+ ions (protons) may form quasi-nuclei*
  - *Nucleus coulomb barrier becomes assistant*
- Many "impossible" reactions now possible
  - *Quark access and quark flipping by EM*
  - *Ion clustering*
  - *Positive charges as phase conjugate mirrors*
  - *Time-density waves and time-energy charging*



The Electronuclear Reaction: Nuclear Reactions in TR-Zones (3)

- **Not observed until time-energy charging has become substantial**
  - *Time delay (hours, days)*
  - *Transduction of LW --> TW involved*
  - *Specific time-charging history of detectors is involved in twhether they detect or not*
  - *Longitudinal EM waves become significant*
- **Curved spacetime can act as source or sink**
  - *May emit excess radiation*
  - *May absorb excess radiation*



In Time-Reversed Zone:
Nuclear reactions are biased

- In normal flat ST, n ⇔ p at high rate
- Curved ST skews statistics
- Biases to either n or p
- Biases to transmutation along isomer chain
- "Isomer" concept greatly expanded

© 1998 T.E. BEARDEN



In Time-Reversed Zone:
Dynamics may be reversed

- Like charges may attract and unlike charges repel
- Coulomb barrier becomes Coulomb assistant
- Clusters like charges and forms artificial nuclei
- "Impossible" nuclear reactions at low energy
- Time-density interactions



Time-Reversed Zone:

Significant only after time-density charging

- Hours, for "fast" onset
- Days, for "slower" onset
- Transduction involved for TW ⇔ LW ⇔ TDW
- Time-history of each detector is significant
- Longitudinal EM waves become significant



A New Conservation of Energy Law

- Physics conserves total "energy and mass-energy"
- Now also must consider "time-energy"
- Conserve total mass-time-energy (spatiotemporal energy)
- Let E_T = total energy, E_M = mass energy, E_E = ordinary energy, and E_t = time energy. Then

$$E_T = E_E + E_M + E_t$$

© 1998 T.E. Bearden

$$(kE_t \Rightarrow E_E > 0) \;\; \Rightarrow \;\; E_T > (E_M + E_E)$$

- If some E_t is transduced into E_E, the experiment will violate the old spatial mass-energy conservation law



QUESTIONS ON CARCINOGENS AND EM RADIATION

- UNRESOLVED QUESTIONS ON EM RADIATION
  - DOSAGES
  - ACTIVE MECHANISMS
  - REPLICATION DIFFICULTIES
  - MEASUREMENT DIFFICULTIES
  - WHERE, WHEN, HOW ILL EFFECTS OCCUR
- SIMILAR QUESTIONS EXIST ABOUT EVERY CARCINOGEN
- SCIENCE REALLY DOES NOT UNDERSTAND THE MECHANISMS OF A SINGLE CHRONIC DISEASE, INCLUDING CANCER
  - FACTORS SUCH AS MIND, STRESS, SPONTANEOUS REMISSION, PLACEBO EFFECTS, AND COMBINATIONS OF FACTORS ARE PARTICULARLY TROUBLESOME
  - GENERATION OF THE PLACEBO EFFECT BY THE REGENERATION & RECOVERY SYSTEM IS UNRECOGNIZED

© 1994, 1995 T.E. Bearden



As defined, fields and potentials only exist in and on charged matter

$E \equiv F/q$

$S = E \times H$

Note problem:
No "E" or "H" in vacuum.

Source q is a broken symmetry in vacuum flux

$S = E \times H$

SOURCE CHARGE

Assumed perpetual motion machine in classical EM

"pileup" in front
So $E \equiv -\nabla\phi$

Point coulomb

$\phi \equiv$ joules continuously in geometrical flow distortion zone around a point coulomb

Electrodynamics has nothing to say about what exists in space in the absence of mass.

© 1997 T.E. BEARDEN



Serious flaws and errors in classical EM theory.

1. Eliminates the Internal EM Inside the Scalar Potential.
2. No Definition of Electrical Charge or of Scalar Potential.
3. Equations Still Assume Material Ether Per Maxwell (Unchanged).
4. Use of Force Fields in Vacuum is False (and Known to be So).
5. Treats Charge q as Unitary Instead of Coupled System $q = \phi[q]m(q)$.
6. Confuses Massless Potential Gradients as Forces (See #3, #4).
7. Does Not Utilize Mass as a Component of Force (See #23).

8. Erroneously Assumes EM Force Fields as Primary Causes.
9. Topology of EM Model Has Been Substantially Reduced.
10. Does Not Include Quantum Potential or Action at a Distance.
11. Does Not Include Superluminal Velocity of Inner EM Components.
12. Does Not Utilize Extended Near-Field Coulomb Gauge Effects.
13. Does Not Include EM Generatrix Mechanism for Time Flow.
14. Does Not Unify Photon and Wave Aspects (Requires 7-D Model).

15. Does Not Include Electron Spin and Precession (See #19, #24).
16. Treats EM Energy As Existing In "Chunks," Instead of as Flow.
17. Confuses Energy and Energy Collection (See #16).
18. Discards Half of Every EM Wave in Vacuum (See #22).
19. Erroneously Uses Transverse Vacuum Wave; It's Longitudinal.
20. Arbitrarily Regauges Maxwell's Equations to Eliminate Overunity.
21. Omits Phase Conjugate Optics Effects (The *Rule* in Internal EM).
22. Does Not Include EM Cause of Newtonian Reaction Force.
23. Erroneously Assumes Separate Force Acting on Separate Mass.
24. Confuses Detected Electron Precession Waves as Proving Transverse EM Waves in Vacuum (Remnant of Old "EM Fluid" Concept).
25. Due to Error in String Wave, Omits the Ubiquitous Antiwave.
26. *Assumes* Equilibrium; Not True Unless Include Vacuum Interactions.
27. Higher Topology Required, to Model Electromagnetic Reality.
28. Lorentz surface integration discards Poynting energy transport.
29. Has nothing at all to say about form of EM entities in massless space.
30. Eliminates the infolded general relativity using EM-force as curve agent.
31. Does not include longitudinal EM waves as time domain oscillations.
32. Does not include EM mechanism that generates time flow and flow rate.

© T.E. BEARDEN 1991,1997


NONMATERIAL SPACETIME
© T.E. BEARDEN 1998
Einstein's spacetime hasn't been born yet!
Michelson-Morley experiments, 1880's
Our material ether is gone, so only inert space is left!
1880s
MAXWELL
Material Fluid Perturbation Equations
MAXWELL
Φ
, H
Material Electric Fluid Disturbed
Material Electric Fluid Disturbed
???
Now we are not using a material ether. Trust us! The equations do not need changing.
ELECTRODYNAMICISTS

Electrodynamicists' Reaction to Removal of the Material Ether



REACTION TO LOSS OF MATERIAL ETHER

Material Ether Assumed in Equations

Potentials, Fields, and Waves Assumed Material

Not a single equation was changed!

Now we are not using a material ether. Trust us! The equations do not need changing.

ELECTRODYNAMICISTS

© T.E. BEARDEN 1998


NONMATERIAL SPACETIME
MASSLESS SPACETIME PERTURBATIONS NOT ADDRESSED
Einstein's spacetime hasn't been born yet!
MAXWELL
Falsely Assumed Matter-in-Space Perturbations
MAXWELL
1888
H
ϕ
Material Electric Fluid Disturbed
CAUSE
Okay! We will just measure material entities, and call them nonmaterial.
ELECTRODYNAMICISTS
Material Electric Fluid Disturbed
EFFECT
???
© T.E. BEARDEN 1998



Some EM Waves in Spacetime

SPACE

TIME

GALLOPING WAVE. TRANSVERSE WAVE THAT VARIES VELOCITY ALONG Z-DIRECTION, IN WAVE FASHION. (Ex: 0.01 c - 100 c)

TIME-POLARIZED (TIME-ENERGY) OSCILLATIONS

3-SPATIAL ENERGY DENSITY OSCILLATIONS

SCALAR WAVES. X, Y, Z FIXED. T VARIES. NONOBSERVABLE.

TRANSVERSE WAVES. X AND Y ENERGY DENSITY VARIES; Z FIXED.

TRANSDUCTION

TIME DENSITY OSCILLATIONS. X, Y, Z ENERGY DENSITY DO NOT VARY.. TIME DENSITY VARIES ALONG TIME DENSITY NOTOBSERVABLE, BUT TRANSDUCTION IS OBSERVABLE.

PSEUDO-LONGITUDINAL WAVES. X AND Y VARY A LITTLE, SURGE OSCILLATIONS IN Z DIRECTION.

TIME DENSITY OSCILLATIONS. X, Y, Z ENERGY DENSITY FIXED. TIME DENSITY IS NONOBSERVABLE, BUT TRANSDUCTION IS OBSERVABLE.

LONGITUDINAL WAVES. X AND Y FIXED; SURGE OSCILLATIONS IN Z DIRECTION.

TRANSDUCTION

© T.E. BEARDEN 1998

Air Medium Disturbances Generated When Air is Perturbed by a Plucked Taut String



The string wave and the holder wave never leave the string and holder respectively.

String slaps air medium

WAVE IN STRING (TRANSVERSE)
Lower degree of freedom for string.
Can only vibrate mostly laterally.

Drude Electron Gas waves

Wave is alternatively compressive and rarefactive

Nuclear proton waves

ANTIWAVE IN HOLDER
(Highly damped; not shown to scale)

Body slaps air medium

© 1993, 1995 T. E. BEARDEN

Launching a Spacetime Perturbation ("EM Wave") from a Wire Antenna



ANTENNA

ELECTRON SHELLS (DAMPED)

NUCLEI (HIGHLY DAMPED)

VACUUM

GRAVITON

time forward slap (electron)

time reversed slap (proton)

Modulations of virtual photon flux intensity of the QM vacuum

By omitting the nuclei perturbation wave, Maxwell omitted Newton's third law from electrodynamics

© T.E. BEARDEN 1994, 1995



Phase Conjugate Wavepairs Produce New Waves

TRANSVERSE EM WAVE PLUS
PHASE CONJUGATE REPLICA WAVE

LONGITUDINAL EM SURGE WAVE

$(\dot{t})$

TIME DENSITY WAVE

Oscillates rate of flow of time about some average value

LONGITUDINAL EM WAVE PLUS
PHASE CONJUGATE REPLICA WAVE

© T.E. BEARDEN 1994, 1995



Scalar Electromagnetics (Energetics) View of EM

- Potentials real; primary causes of EM phenomena
  - Force fields made by differentiations of potentials
  - Force fields are effects, not primary causes
  - Force fields exist only in, on mass particles
- Actions due to potentials and their interference
  - Action at a distance or locally
  - Quantum potential and hidden variables
- Locally curved spacetime, engineerable by EM
  - Gravity effects not necessarily negligible
  - Strong EM force or time used as agent of curvature

© T.E. BEARDEN 1990, 1996



Scalar Electromagnetics (Energetics) View of EM (Cont'd)

- Potentials have internal structure
  - Stoney/Whittaker structure
  - Longitudinal EM phase conjugate wavepairs
  - Each wavepair is a time-polarized EM wave
- Vacuum EM is a potential and has microstructure
  - Stoney-Whittaker biwaves/t-polarized waves
  - Fluctuations exhibit chaos
- Spacetime ≡ Vacuum ≡ Potential ≡ Flux

© T.E. BEARDEN [illegible]



Scalar Electromagnetics (Energetics) View of EM (Cont'd)

- Statistics may have hidden order (already chaotic)
- Uses spacetime curvature engines to alter matter (inside-out or outside-in)
- Engineerable EM mechanism generates rate of flow of a mass through time
- Quantum potential with specific QP can be used for instant action at a distance



Extended General Relativity Principle

- "All levels of energy structures and all levels of time structures mold spacetime geometry.
- This is called a ***vacuum engine*** (spacetime engine).
- Spatial and temporal structuring act upon mass at all levels.
- This produces ***templates*** of forces, for translations and stresses."

© T.E. BEARDEN 1990

ACTIVE SPACETIME
DYNAMIC MASS
STRUCTURING OF ACTIVE SPACETIME CURVATURES



Extension of Work-Energy Theorem

© T.E. BEARDEN 1997

- *Theorem*: $W = k_f - k_i = \Delta k$ [1]
- k must be interpreted not as energy *per se*, but as *collected/collecting* energy.
- The reaction cross section λ for the collecting process must be included.
- *Extension*: $W = \lambda(k_f - k_i) = \lambda\Delta k$ [2]
- Normally $\lambda \leq 1$, as for elastic collision or Stokes emission.
- However, $\lambda > 1$ is now possible, for processes which asymmetrically self-regauge. An example is Letokhov's negative absorption of the medium.
- Working models are the Patterson Power Cell® and Lawandy lasing without population inversion.



MTW's General Relativity Principle

- "Space acts on matter, telling it how to move.
- In turn, matter reacts back on space, telling it how to curve."

ACTIVE SPACETIME
DYNAMIC MASS
STRUCTURING OF ACTIVE SPACETIME CURVATURES

© T.E. BEARDEN 1998



Use of General Relativity (GR) in Particle Physics

© 1998 T.E. Bearden

- GR seldom used in particle physics
- In cold fusion, Matsumoto* has applied general relativity
- Consistent with important cold fusion results
- Used spacetime (ST) curvature by energy density
- Matsumoto did not utilize:
  - Longitudinal EM waves
  - Time density waves
  - Time density curvatures of ST (gain = $9x10_{16}$)

* T. Matsumoto, "Mechanisms of Electro-Nuclear Collapse," Proc. ICCF-7, Vancouver, BC, Canada, Apr 1998, p. 98



THE MISSING INFOLDED ELECTRODYNAMICS

Maxwellian electrodynamics has nothing at all to say about EM entities in space or their form

Material Electric Fluid Disturbed

MATTER-TO-MATTER TRANSFORM

Material Electric Fluid Disturbed

MATTER-TO-SPACETIME TRANSFORMATION

INFOLDED INSIDE MAXWELLIAN EM AS HIDDEN EM VARIABLES

SPACETIME-TO-MATTER TRANSFORMATION

INTERNESTED SPACETIME CURVATURES

(VACUUM ENGINES)

INFOLDED GENERAL RELATIVITY

EINSTEIN'S SPACETIME

© T.E. BEARDEN 1998



Infolded Engines: Excluded by Present Physics

- The infolded dynamics of EM systems are not considered in general relativity, electromagnetics, or quantum mechanics
- None of these disciplines include such spacetime curvature engines (vacuum engines)
- Thus GR, EM, and QM cannot be unified, since ST curvature engines are where the unification mainly occurs

© 1999 T. E. BEARDEN



ST curvatures propagate

© T.E. BEARDEN 1998

mass perturbation (Drude Electrons)

Transmitter

mass-to-spacetime transformation

altered spacetime (curvatures)

spacetime-to-mass transformation

altered spacetime (curvatures)

mass perturbation (Drude Electrons)

Receiver

Complex of ST curvatures (vacuum engine, or spacetime engine)

Spacetime disturbance (engine) propagates

The *mass-to-mass transform* contains two hidden infolded transforms: (i) the *mass-to-spacetime transform* and (ii) the *spacetime-to-mass* transform. What is transmitted and propagates in space is a *spacetime perturbation.*



Mass curves and structures spacetime; ST curvatures change and structure mass

ST curvatures propagate

mass

mass-to-spacetime transformation

spacetime-to-mass transformation

mass

altered spacetime

altered spacetime

ST curvature complex (vacuum engine)

© T.E. BEARDEN 1996

spacetime disturbance propagates



At Infinite Velocity:

Each Is Every Other

SPACETIME

VIRTUAL PARTICLE FLUX

POTENTIAL

MIND AND MIND LEVELS

MASS

PLANET

LIVING ORGANISMS

© 1997 T.E. Bearden



Lisitsyn's Report: Brain Code Broken

- THEORY DEVELOPED AND FITTED
- HYSTERESIS MEMORY LOOP
- CONTROLLED EM INDUCTION
  - IMAGES
  - SENSATIONS
  - PREDETERMINED EMERGENCE
- 23 EEG BANDS
  - UP TO 8.1 X 10^{20} HZ
  - 11 INDEPENDENT CHANNELS

© 1978, 1985, 1991 T.E. BEARDEN

S.K. Lisitsyn, "New Approach to the Analysis of Electroencephalograms," DDC Report AD73005, p. 16-25.



Lorentz Closed Surface Integration

Selects only the locally divergent portion of the Poynting energy flow that powers the component.

POYNTING GENERATOR
S.S. LORENTZ
Only the wind on my ship is of physical significance!

© 1997 T.E. Bearden



Lorentz Closed Surface Integration

Selects only the locally divergent portion of the Poynting energy flow that powers the component.

How can they use that old physically insignificant wind?!!

© T E BEARDEN 1998

Lorentz's physically insignificant energy flow can be collected and utilized.



Lorentz surface integration of the Poynting vector around a closed surface

See Panofsky & Phillips, Classical Electricity and Magnetism, 2nd, edn., Addison Wesley, 1962, p. 178-181.

1a. Lorentz surface integration.

1b. Actual S in and S out.

Note: If the S-vector is integrated over the closed surface, then all energy *transport* passage is zeroed, leaving only the very small component of the input S-flow that is powering the joule heating of the resistor. In short, only the small component of the S-flow that is equal in magnitude to the Slepian vector $j\phi$ remains. This measures only the tiny portion of the S-flow that is "collecting" on electrons passing through the resistor, and therefrom being dissipated out of the resistor as joule heating. It discards everything else (all S_{TR}'s and S_{OUT}). S_{IN} becomes S_R.

© 1997 T.E. BEARDEN



Longitudinal EM Photon Interaction with Charge

- Creates time-density wave pumping
- Slowly creates time-density charging

Transverse photon

CHARGED MASS

Excited Energy Density State

Time-density (scalar) photon

Longitudinal photon

Phase Conjugate Added by Charged mass

CHARGED MASS

Excited Time Density State

© 1990 T.E. Bearden

- Fundamental units are arbitrary in physics
- Can express all physics in one unit -- e.g., time
- Time is highly compressed energy
- 1 sec = 9 x 10_{16} joules of transverse EM wave energy



Figure 1-8. Infolded biwave composition of a scalar potential.

Mass is transparent to longitudinal EM waves, which move through the infolded interiors of internal waves, potentials, and fields in the mass

MASS MEDIUM
EMWave
Ambient Vacuum Potential
Static EM Field
© T.E. BEARDEN 1997
Ambient Vacuum Potential
D.C. Potential

Mass is mostly ambient vacuum potential, modified by internal potentials, fields, and waves. Any wave or field is just two scalar potential functions, by Whittaker 1904.



Pumping with Longitudinal EM Waves Time-reverses the Mass

vacuum (spacetime) engine in the mass is the input

longitudinal EM pump wave

MASS previous state

CELL MASS

highly nonlinear to any and all LW frequencies

Antiengine acts upon mass at all levels

AN AMPLIFIED VACUUM (SPACETIME) ANTIENGINE IS FORMED AND ACTS ON THE MASS, TIME-REVERSING IT AND ALL ITS COMPONENTS NO MATTER HOW SMALL

longitudinal EM pump wave

© T.E.BEARDEN 1997



Maxwell's Quaternion Theory

- Quaternions:
  - Discovered by Hamilton in 1843
  - A quaternion has a vector part
  - A quaternion has a scalar part
  - First significant non-arithmetic number system
  - Higher topology than vector or tensor algebra
- Maxwell's theory was in quaternion equations
  - 20 equations in 20 unknowns
  - Reduced to a small 4-equation subset by Heaviside and Gibbs
  - EM topology dramatically reduced

© T.E. BEARDEN 1995, 1996

Maxwellian Systems
Before regauging, after symmetrical regauging, and after asymmetrical regauging

Note: Any system must first break equilibrium in its vacuum exchange, before it can energize Drude electrons and "power" the load. Asymmetric regauging is always utilized. Powering loads and losses is a symmetry-restoring operation.



MAXWELL'S EQUATIONS BEFORE THEIR REGAUGING

BEFORE REGAUGING

OPEN SYSTEMS NOT IN THERMODYNAMIC EQUILIBRIUM

OPEN SYSTEMS IN THERMODYNAMIC EQUILIBRIUM

ASSUMED "CLOSED" SYSTEMS

SYSTEMS WHICH REGAUGE, FREELY CHANGE ENERGY, AND SHOW COP<1.0 BY DESIGN

SYSTEMS WHICH REGAUGE, FREELY CHANGE ENERGY, AND SHOW COP>1.0 BY DESIGN

SYSTEMS REGAUGE, CHANGE ENERGY, BUT USE HALF THE ENERGY TO DESTROY SOURCE DIPOLE

TRULY CLOSED SYSTEMS (NONE EXIST)

ASYMMETRICAL REGAUGING

SYMMETRICAL REGAUGING

Ⓒ 1996, 1997 T.E BEARDEN

Selected clipart© by Lotus SmartPics™



Page 1 of 2.

Maxwell's four equations reduce to:

$$\nabla^2\Phi + \frac{1}{c}\frac{\partial}{\partial t}(\nabla \bullet A) = -4\pi\rho \qquad [1]$$

$$\nabla^2 A - \frac{1}{c^2}\frac{\partial^2 A}{\partial t^2} - \nabla\left(\nabla \bullet A + \frac{1}{c}\frac{\partial\Phi}{\partial t}\right) = -\frac{4p}{c}J \qquad [2]$$

A is replaced by A', where

$$A' = A + \nabla\Lambda \qquad [3]$$

The new B' field then becomes

$$B' = \nabla \times (A + \nabla\Lambda) = \nabla \times A + 0 = \nabla \times A = B \qquad [4]$$

A new E-field will also be formed. So let

$$\Phi' = \Phi - \frac{1}{c}\frac{\partial\Lambda}{\partial t} \qquad [5]$$

© T.E. BEARDEN 1997



Page 2 of 2.

Per Jackson, (A,Φ) are *habitually* chosen so that

$$\nabla \bullet A + \frac{1}{c}\frac{\partial \Phi}{\partial t} = 0 \qquad [6]$$

The *net symmetrical* regauging separates variables.

Two inhomogeneous wave equations result:

$$\nabla^2\Phi - \frac{1}{c^2}\frac{\partial^2\Phi}{\partial t^2} = -4\pi\rho \qquad [7]$$

$$\nabla^2 A - \frac{1}{c^2}\frac{\partial^2 A}{\partial t^2} = -\frac{4\pi}{c}J \qquad [8]$$

© T.E. BEARDEN 1997

Equations [1] and [2] *arbitrarily* changed to [7] and [8]

The Tom Bearden Website

Mind Control and EM Wave Polarization Transductions - Part I, II & III

Reprinted from "Explore" magazine, 1999

Part I

- Page 1
- Page 2
- Page 3
- Page 4
- Page 5
- Page 6
- Page 7
- Page 8
- Page 9
- Page 10

Part II

- Page 1
- Page 2
- Page 3
- Page 4
- Page 5
- Page 6
- Page 7
- Page 8

Part III

- Page 1
- Page 2
- Page 3
- Page 4
- Page 5
- Page 6
- Page 7
- Page 8
- Page 9

- The U.S. approach to mind control
- "Voices in my head"
  Flanagan's neurophone - used to give instructions to diplomats during negotiations, etc.

The Tom Bearden Website

ORDER BOOKS & DVDs



Articles

- **Job Opportunities in Energy**
  25 August, 2010

- **THE WORLD ENERGY CRISIS IN PERSPECTIVE:**
  The Breakthrough Technology that Solves it Quickly
  22 March, 2010

- Direct Engineering of Physical Reality Itself
  3 June, 2009
- Solving The Problem of Freely Using EM Energy from the Vacuum
  18 September, 2008
- How an EM circuit powers its load - and solving the world energy crisis
  16 September, 2008
- Rapid and Decisive Solution of the World Energy Crisis and Global Warming
  Updated
  9 September, 2008
- On Negative Energy EMP Weapons
  26 July, 2008
- In Memoriam - Howard Johnson
  31 March, 2008
- Suppression of the Self-Powering Battery?
  1st December, 2007
- Never Mind - Junk Science

and All That
11 September, 2007

- **The Deliberate Discard of Asymmetric Maxwellian Systems, Thus Preventing COP>1.0**
  and Self-Powering Energy-from-the-Vacuum Systems
  21 June, 2007

- **What We Have to Get Across to Our Electrical Engineering Profession:**
  To the EE Departments, Professors, Students, Curricula, and Textbooks
  May 24, 2007

- **Phases of Research and Development and Some Problems**
  18 February, 2007

- **Scalar Electromagnetic Weapons and their Terrorist Use: Immediate Strategic Aspects of the Asymmetric War on the U.S.**
  11 September, 2004

- **Reducing our Dependence on Fossil Fuels**
  28 April, 2003

- **Flash News: Second Law of Thermodynamics Curtailed**
  4th August, 2002

- **Maxwell's demons are alive and thriving**
  4 July, 2002

- **Clean Electrical Energy from the Active Vacuum**
  January, 2002

Mind Control and EM Wave Polarization Transductions

Part I
Vol. 9, No. 2 1999

Part II
Vol 9, No. 3 1999

Part III
Vol 9, No. 4,5 1999

Vacuum Engines and Priore's Methodology - The True Science of Energy-Medicine

Part I
Vol. 6 No. 1 1995

Part II
Vol. 6 No. 2 1995

Paranormal Pictures
Psychic Observer 39(3) ~ 224, 255-258

Many of Tom Bearden's older articles on a wide range of topics can be found in the back issues of Explore! magazine.

See http://www.explorepub.com

Mind Control and EM Wave Polarization Transductions, Part 1

©Copyright 1999 by T.E. Bearden, USA

Special Note

This article refers to experimental research techniques which can be detrimental or lethal in the hands of any but highly skilled, qualified experimental scientists proceeding under proper laboratory safety procedures. The purpose of this article is strictly for information to properly qualified and authorized scientists in certified laboratories. We do not propose or condone any use of these procedures for nonapproved practice of medicine without a license. Neither the publisher nor the author are responsible for accidents or outcomes in the use of these experimental pro-cedures and techniques. Any researcher who performs these procedures and experiments is acting on his or her own volition, and is solely responsible for insuring safety, qualifications, and legality of the acts and their results. We neither suggest nor condone unauthorized experimentation on human subjects. Such is a criminal violation of the constitutional rights of the subject under Federal and State laws, and is both illegal and immoral.

Abstract

For some time we have been repeatedly queried about the technical mechanisms and unusual electrodynamics of advanced mind control research, both in the West and abroad. Calling full attention to the special note above, in this paper we present a high-level over-view of the novel electromagnetic nature of mind operations, mind and body coupling, and *intent*•the induction of physical 3-space EM energy changes into the brain and nervous system, and into every cell of the body, from the mind's time-like coherent operations. We summarize the time-polarized electrodynamics used to engineer and affect mind operations and the mind-body coupling loop. Transduction mechanisms whereby differing EM wave polarizations can be transformed one-into-the-other are presented. We give two specific examples of lethal foreign military tests in 1997 of advanced mind control weapons against two military pilots over the central U.S. Some dangers and potential benefits of the emerging mind control technology are pointed out


Mechanisms for Physical Change and the Flow of Time
SPATIAL
SPATIOTEMPORAL
PHOTON
SPATIAL
PHOTON
L^2T
MASS
L^3
MASSTIME
L^3T
L^2T
MASS
L^3
SPATIAL AND SPATIOTEMPORAL
"MASS"
MASSTIME
L^3T
MASS
MASS
MASSTIME
L^3T
"MASS"

$$(\Delta E)(\Delta t) + M \Rightarrow (M+\Delta M)\Delta t \Rightarrow M + (\Delta E)(\Delta t)$$

Flow of macroscopic time (observable photon interactions)

Flow of microscopic time (via virtual photon interactions)

The photon interaction generates an observed quantum change and a discretized jump in the rate of time flow. A particle observably changes by only a single Δt at a time. The background flow of time in which the jump in rate occurs, is created by the continual absorption and emission of virtual photons.

© 1994 T.E. BEARDEN

Figure 1. Mechanism that generates a mass's flow through time.

EXPLORE! VOLUME 9, NUMBER 2, 1999

Introduction and Background

In quantum field theory, there are four polarizations of photons.[1] Using 4-space and the z-direction as the direction of propagation, we have x- and y- polarizations where the 3-spatial energy of the photon is oscillating laterally, in the x- or y- direction. These are *transverse polarized* photons, as is any combination of the two. The third polarization is along the z-direction, which is a longitudinal polarization. In other words, the 3-spatial energy of the longitudinal photon cannot oscillate in the x- or y- direction, and so it is oscillating to-and-fro along the line of motion, z-. The fourth polarization occurs when the energy is frozen in all three spatial dimensions x-, y-, and z- and it cannot oscillate in any of those directions. In that case, the photon oscillates its energy in the t- direction, providing the t-polarized photon. We will later discuss how time is actually highly condensed energy.

In Minkowski 4-space, body operations are space-like, and are so treated in conventional materialistic physics. Mind and mind-operations are time-like, not space-like, even though they are totally electromagnetic in nature.[2]

As is well-known, all observation in physics is considered 3-spatial..[3] Mass is a 3-spatial concept, and we detect changes to mass (as, e.g., in the shift of electrons in the circuits of electrical instruments). So one may model the common physical observation mechanism as a *time-differentiating process* which *a priori* discards time-change and retains 3-spatial energy change.[4] That is, Minkowski reality is modeled in the fundamental units of L^3t. Physical observation (via the transverse photon interaction) is the process given by applying the operator $\partial/\partial t$ to L^3t, yielding an L^3 output. Hence mind and mind operations are excluded by the usual physics instruments and observation, which simply exclude the time domain in their outputs and do not "measure" it.

For this reason, physicists have erroneously considered mind to be "metaphysical" and nonreal. Indeed, most physicists to one extent or the other are materialists, and consider the "mind" to be nothing but the operations ongoing in a "meat computer." Nonetheless, in the time-domain the time is absolutely real, and it is completely electrodynamic in nature. There is no metaphysics involved, and the temporal domain—along with mind and mind operations—is simply an erroneously neglected area of physics. In present physics, the notion of mind is comfortably disposed of by imposing the use of the "observer" concept, with out ever specifying that the observer has a consciousness and a mind. Indeed, "observation" is only about what that "observer" perceives. Obviously, one has a dramatically crippled physics if one eliminates that nonobservable called "time." Similarly, one also has a dramatically crippled physics when one eliminates the mechanisms and physics ongoing in those time-like and dynamic "things" such as mind, that occupy time and function in it.

From this viewpoint, Western physics adheres to its 3-spatial measurement foundation only by ignoring the transduction of time-polarized EM changes into detectable longitudinal and transverse EM wave changes. In this aspect, present Western physics is severely self-crippled.

Time is totally electromagnetic and energetic in nature. The flow of time is not a separate external river on which a mass floats along like a boat drifting down the current of a great flowing river. Instead, the flow of time is generated directly on every mass by its total set of photon interactions, both virtual and ob servable. We have previously presented the exact mechanism for the flow of time. *[Figure 1]*


TRANSVERSE EM WAVE PLUS
PHASE CONJUGATE REPLICA WAVE
LONGITUDINAL EM SURGE WAVE
LONGITUDINAL EM WAVE PLUS
PHASE CONJUGATE REPLICA WAVE
$\dot{(t)}$
TIME DENSITY WAVE
Oscillates rate of flow of time
about some average value
© T.E. BEARDEN 1994, 1995

Figure 2. Transduction of EM wave type by successive phase conjugate pairing.

EXPLORE! VOLUME 9, NUMBER 2, 1999

Further, a photon is comprised of angular momentum, therefore of (energy)x(time). It transports both energy and time, not just energy alone. When absorbed by a mass, not only does it "energy-excitation" charge the mass, but also it "time-excitation" charges it, converting the former "mass" to "mass time". Rigorously it is *masstime* that emits a photon, not *mass*. So a mass moves through time in little spurts, by the continual macroscopic addition and subtraction of little Dt components. Further, in being driven through time, mass is continually altered to masstime (a quite different critter from mass), to mass, to masstime, to mass, etc.

In any masstime state, a myriad of tiny virtual photon interactions made of very tiny (DE)(Dt)'s interact with that same mass during that particular larger Dt of the masstime state (m+Dm)(Dt). Hence mass in its alternate masstime state has that state internally structured by its surrounding environment's interactions with it. The masstime state is internally structured energetically in its (DE) component, and also internally structured temporally in its (Dt) component.

A standard charged fundamental particle such as an electron, e.g., is not necessarily identical with another, when the internal structuring of its masstime state is considered. Further, by two papers by Whittaker,[5] interferometry of masstime states with either energy reactions or temporal reactions can yield observable effects and changes due to these neglected "hidden variables" in the electron's masstime alternative states. To engineer the mind and its operations directly, one must perform electrodynamic engineering in the *time* domain, not in the 3-space EM energy density domain. The direct engineering of time-like mind and mind operations—in all levels and all aspects—requires the use of *time-polarized photons and time-polarized EM waves*. This is the rarest form of electrodynamics, almost untouched by Western physicists.

One can either painfully produce such time-polarized photons and EM waves and directly irradiate a target mass with specific assemblies of them, or one can force the mass itself to iteratively transduce ordinary transverse EM waves first into longitudinally-polarized EM waves and then into time-polarized EM waves. Both will be discussed briefly.

In the West, it appears that the present author's discovery of mechanisms for producing time-polarized (scalar) EM waves [see *Figure 2*] and for transducing between wave polarizations has no precedent. [See *Figure 3*]. While scalar (time-polarized) photons are known in the literature,[1] the creation and use of time-polarized EM waves does not seem to appear in the Western physics literature.[6]

Wave transduction or *polarization transductions* are terms used by the author for the process of transforming an EM wave's particular polarization into another polarization type. Such transduction to other than transverse polarization forms is little known in the West. It appears essentially haphazardly in some experiments, usually without any recognition by the experimenters themselves. Significant transduction in experiments will also produce "strange" and unexplained anomalies in the instruments being used for experimental measurements.[7]

So most probably Western mind control researchers have not recognized the methodology and mechanisms[8] for transducing one type of EM wave polarization directly into another.[9] They continue to seek the "mind" in 3-space and hence in the brain, rather than in the time domain. On the other hand, it appears



Figure 3. Interference processes for transducing higher EM wave polarizations into lower polarization states.

EXPLORE! VOLUME 9, NUMBER 2, 1999

that the Russian KGB *energetics*[10] weapons scientists—particularly those in *psychoenergetics*[11]—have known and used methods of transducing one wave polarization into another, for at least two decades. It follows that those same scientists have very probably developed *mind engineering* and *mind control* via novel time-polarized EM wave means and a dramatically extended electrodynamics of the time-like mind operations.

In the present paper we briefly develop the wave transductions and the basis for mind engineering, including the specialized use of ordinary transverse wave (TW) EM spectra to force internal EM wave transductions and time-domain operations inside irradiated bodies, cells, and tissues. Through the mind-body coupling mechanism, these transductions of transverse EM waves can operate upon the mind and its deepest operations as well as upon the body, every cell, and every part of every cell.

Russian Mind Control Uses Higher EM Wave Polarizations

It is apparent that the KGB psychoenergetics weapons scientists know and use the full extended EM wave polarization range. As a postulation, one would expect our own weapons scientists to know and utilize the orthodox transverse wave (TW) EM for similar research and experimentation. However, in the West scientists are *just beginning* to realize the importance of a very general (and weaker) type of longitudinal EM wave (LW) polarization, as evidenced by the appearance of dozens of papers on "undistorted progressive waves" (UPWs, which are essentially imperfect LW s with TW residues remaining). The Los Alamos National Laboratory web site has a number of such papers—particularly by Rodrigues[12] and Lu—available for free downloading. UPWs have very interesting characteristics. If they were perfect longitudinal EM waves, they would have infinite energy and infinite speed. Since only imperfect UPWs can be physically made, their speed can vary from slower than the speed of light to faster than the speed of light. Their energy can also vary over a great range.

Another characteristic of UPWs that are reasonably good longitudinal EM waves, is that they pass readily through a large depth of water and mass, including through the ocean and the earth with only small interactions and losses. Yet by interfering two such beams of "high quality" UPWs at a great distance, then in the interference zone ordinary EM energy will rise directly out of local spacetime potential, as essentially shown by Whittaker[13] nearly a century ago. Russian weapon research facilities have weaponized these effects[14] for nearly 50 years, under rigid KGB control and operation. Nonetheless, even if using only ordinary TW waves, Western mind control researchers may get some fairly good results, brute-force-like, by using gross correlates between just the input irradiating TWs and the exhibited behavioral responses of the individual. The net input-output correlations can be determined, even though not taking into account the actual wave polarization transduction mechanisms ongoing inside the irradiated dielectric (or brain, or mind, etc.). However, Western researchers appear to have no knowledge of the exact mechanisms by means of which coherent time-like mind operations of a biological organism couple to the organism's 3-spatial body to provide the mental control loop. They also appear unaware of how the coherent 3-spatial behavior responses of the body couple back to the time-like mind to provide it with a sensory feedback of the body's responses.


Vacuum Engine: Working ST Demons
Internested patterns of spacetime curvatures
Structured Einsteinian spacetime
Maxwell Demons: EM hidden variables
Dynamic structures at all levels
Demons work at all levels
© 1997 T.E. Bearden

Figure 4. A spacetime curvature engine has myriads of small ST curvature components which act upon mass at all levels.

EXPLORE! VOLUME 9, NUMBER 2, 1999

General Relativity Aspects

Both these coupling mechanisms can be taken directly from general relativity, if one puts one's mind to it. However, unless the wave polarization transformations are known, it is difficult or impossible to apply the ordinary GR *directly*, since relativists usually concentrate upon spacetime curvature by altering 3-space energy density rather than by altering time-polarized "time-energy" density.

In applied general relativity, spacetime itself is an active medium. One speaks of a change in spacetime as a "spacetime curvature". Any curvature of spacetime in a local region directly performs continuous work upon any mass embedded in that region. Vice versa, any mass (or other concentration of energy) in a local spacetime continuously acts upon that spacetime to "curve" it.

So if one wishes to perform actions upon mass in a distant region, one may generate local curvatures of spacetime in that region, and these curvature "engines" will directly act upon the mass at all levels. *[Figure 4]* This is very different from energy propagation through space from one point to another. Now the "ordinary EM energy and actions" arise from every spatiotemporal point within the mass, at every level, and move upwards (from inside to outside). So we speak of specific forms of "templates" of nested spacetime curvatures formed and utilized to engineer mass "from inside out" as *spacetime curvature engines or vacuum engines*.

Use of vacuum (spacetime curvature) engineering[15] is a far more powerful form of engineering than is provided by energy propagation through space. As an example, it is easy to alter the quarks in a nucleon, using spacetime curvature engines and time-charging decay. Indeed, we have developed the mechanisms for cold fusion and the electronuclear interaction (formation of new nuclides) at feeble energy. An Invention has been filed with the U.S. Patent Office, and formal patent applications are in preparation. Some information on these mechanisms and principles has been released[17].

Time as Dense EM Energy and a Strong Spacetime Curvature Agent

The advantage of using the time-polarized "time-energy" for spacetime curvature is that time is ordinary energy compressed by a factor of at least c^2—which, in the MKS system of units, is some 9¥10^{16}. Thus use of time-polarized EM photons and waves as ST curvature agents gives an amplification of 9 ¥10^{16} over the use of transverse-polarized EM waves for that purpose. In turn, the use of the strong EM force in ordinary TW waves as an agent of ST curvature is already a nominal 10^{40} times as strong as is the weak G force used as the agent of ST curvature.

The bottom line is this: For spacetime curvature effects, the use of the t-polarized domain provides amplification of some 9¥10^{56} greater than the weak G-force ST curvature agent usually considered in general relativity[18].

Western Science Remains Largely Materialistic

Ironically, most Western scientists are materialists and consider "mind" as a mystical and nonscientific concept. They tend to consider mind operations and functions either to be simply "meat computer" operations and functions, or at best to be very weak ordinary transverse-wave EM operations and functions in the brain and nervous system.[8] This serious self-limitation exists because in the body we *measure* only weak TW EM operations and functions correlated to biological behavior and brain operations. We simply do not know how to

Disclosure[16] on this work

measure "mind operations" directly.


MIND DOMAIN
BODY DOMAIN
START
STOP
COHERENT MIND CHANGES (INTENT)
NO
YES
DIFFER?
COHERENT INTEGRATION IN MIND DOMAIN PRODUCES COHERENT OBSERVABLE MIND CHANGES
COHERENT ROTATIONS PRODUCE COHERENT TIME-LIKE VIRTUAL PROJECTIONS IN MIND DOMAIN
COHERENT ROTATIONS IN 4-SPACE PRODUCE COHERENT VIRTUAL 3-SPACE PROJECTIONS
COHERENT VIRTUAL ST ENGINES FOR COHERENT PHYSICAL CHANGES & BEHAVIOR
COHERENT INTEGRATION IN BRAIN/BODY PRODUCES COHERENT OBSERVABLE ST CURVATURE ENGINES
YES
ZERO?
NO
COHERENT BODY CHANGES PRODUCE OBSERVABLE CURVATURE ANTI-ENGINES

Figure 5. Mind-to body coupling and body-to-mind coupling.

EXPLORE! VOLUME , NUMBER 2, 1999

With no mind measurements possible and no instruments, it is understandable that Western science considers only the physical side of the mind-matter interface.

Presently our scientists do not measure the longitudinally-polarized EM wave operations and functions in the body and around it in nature. Few of them are aware that a maelstrom of such LW functions exist in the body and in all of nature in general. Presently only highly theoretical quantum field theorists seem to even be aware of the existence of scalar (t-polarized) photons, and even they are unaware of t-polarized EM waves. Certainly our scientists do not measure t-polarized EM waves in and around the body and in nature, nor do they make them in the laboratory. Apparently they have not studied such waves and their interactions with matter—living and inert—at all.

But it's even worse. In ignoring the time component transported by photons and EM waves, science has also erroneously omitted half of the excitation charging and excitation decay processes whenever a mass interacts with photons and EM waves. More on that later.

Brute Forcing Time Functions versus Fine Control Methods

Ironically, Western mind control researchers using transverse EM waves for mind control research, are using a brute force method of evoking and using vacuum engines (spacetime curvature engines) and a special form of general relativity, although they do not appear to realize it.

While KGB scientists also use TW EM "brute force" TW waves when necessary, they do "imprint" or "activate" those waves with the desired internal LW and time-polarized EM wave and photon structures required to directly perform the mind engineering desired. They also do not hesitate to use LWs and t-polarized waves overtly. So in blunt terms, Western compared to Russian mind control research is probably like comparing an automobile body shop with a fine surgical ward. Having long ago worked out all those "exact correlates" to the internal "information content of the field" is where the KGB scientists are at least 20 years ahead of the West.

The reason one can get mind and behavior results with the TW electromagnetics, while bypassing the real mechanism which uses t-polarized waves and photons, is due to (1) the very peculiar nature of the EM emission from a dielectric, and (2) what can be done by re-radiating that dielectric with its emitted spectrum, deliberately and very carefully altered in selected parts. We will return to that important feature later.

Polarization and Observability

As we stated, there are four photon polarizations and therefore there must be correspondingly four EM wave polarizations[1] The first three polarizations are the x-, y-, and z- spatial polarizations. The x- and y- polarizations are transverse polarizations and the z-polarization is a longitudinal polarization along the direction of propagation (along the z-axis, by standard notation). Simply put, we may visualize the transverse polarizations as rather like the wiggling of a fish's tail from side to side as the fish moves forward, or a whale's flukes up and down as the whale moves forward, or some combination thereof. We may visualize the longitudinal polarization as a sort of "repetitive accordion effect" along the line of motion of the wave. Usually the z- polarization is neglected in EM wave theory, although in recent years physicists have "rediscovered" longitudinal EM waves and are now intensely researching the use and characteristics of such waves.[12]



Energetics

NONLIVING SYSTEMS | **LIVING SYSTEMS**

Energetics

- Nonliving systems
- Scalar Interferometry
- Action-at-a-Distance
- Quantum Potential
- Vacuum Engines
- Spacetime Structuring
- Material, Field Effects
- Nuclei, Lattice Changes
- Hidden EM Variables
- SWZ Effects

Bioenergetics

- Living Systems (Bodies)
- Cells, cellular changes
- Master Cell Control (Popp)
- Spacetime Structuring
- Disease Induction, Remission
- Action-at-a-Distance
- Quantum Potentials
- Scalar Interferometry
- Hidden EM Variables
- SWZ Effects

Psychoenergetics

- Living Systems (Minds)
- Thoughts, Memories, Emotions
- Conscious/Unconscious Minds
- Spacetime Structuring
- Species, Biospheric Minds
- Action-at-a-Distance
- Quantum Potentials
- Scalar Interferometry
- Hidden EM Variables
- SWZ Effects

Figure 6. The three divisions of Soviet energetics and their characteristics.

EXPLORE! VOLUME 9, NUMBER 2, 1999

Unfortunately, in quantum field theory there has been a tendency to regard the t-polarized or "scalar" photon—where the local rate of time is oscillated—as unobservable. Oscillation of the local rate of time produces powerful oscillations of local space-time curvatures, due to the extreme energy density of time. Individually, the t-polarized photon tends to be unobservable. However, a *coherent sequential group* of such t-polarized photons, each individually in the virtual state with respect to the external observer, may simply integrate in its interaction with mass over a short time period into observable change because of the coherent integration of virtual spacetime curvatures into a larger, observable spacetime curvature.

Rotations and Projections in 4-Space

Relativistically, any velocity change in 4-space is a rotation. Any such rotation in the time-domain also creates a tiny projection component into 3-space. Any such rotation in the 3-spatial domain also creates a tiny projection component into the time domain.

Hence a sufficient series of coherent time-domain (mental) changes produces a coherent series of virtual changes in 3-space (the body), thereby coherently integrating into an observable energy change in the body. A sufficient series of coherent 3-spatial energy changes produces a coherent series of virtual changes in the time domain which coherent integrate into an observable time-domain change.

Solution to the Age-Old Philosophical Problem of Intent

This is in fact the solution to the age-old problem of *intent*, or how the nonmaterial (i.e., non-3-spatial and non-observable) mind induces a 3-spatial, observable energy change upon the 3-spatial body. It is also the solution to the problem of *awareness*; i.e., how the mind is aware of itself[19] and of the responses of the body. Together the two form a closed loop coupling of the mind and body. The time delay in the loop together with memory recall for comparison, creates the sense of "persistence" of self in time. This also creates the sense of being a "separate, closed being" (i.e., of separate persistence in time—in the living entity). The sense of "separation of self from an external world" is created by comparing those body-to-mind sensory feedbacks which are not correlated to the mind's previous feed-forward intent.

Time As Energy and Why It Is Very Dense Energy

In addition to the three spatial polarizations of photons and EM waves, there is a very, very useful t-polarization along the time axis. In this polarization, the 3-spatial energy is not oscillating at all. Instead, the time or time-energy is oscillating. Time can be taken to be energy compressed by at least c^2, so it has at least the same energy density as mass. In other words, one second is $9x10^{16}$ joules of time-energy (energy compressed into time). The t-polarized photon or EM wave is called the scalar photon or scalar EM wave, respectively.

To demonstrate why time can be regarded as energy, we need only point out that the choice of fundamental units in any physics model is totally arbitrary. We usually choose these units to ease the mathematical manipulation, ease our understanding, and simplify the ability to visualize or "grasp" the physics. However, if one wishes, one can build all of physics from a single fundamental unit—e.g., energy. In that case, one readily sees that time is a function of energy and only energy. Hence it is perfectly proper to regard time as energy, and to seek out what form the function takes in our normal system of units (say, the MKS system).



Lisitsyn's Report: Brain Code Broken

- THEORY DEVELOPED AND FITTED
- HYSTERESIS MEMORY LOOP
- CONTROLLED EM INDUCTION
  - IMAGES
  - SENSATIONS
  - PREDETERMINED EMERGENCE
- 23 EEG BANDS
  - UP TO 8.1×10^{20} HZ
  - 11 INDEPENDENT CHANNELS

© 1978, 1985, 1991 T.E. BEARDEN

S.K. Lisitsyn, "New Approach to the Analysis of Electroencephalograms," DDC Report AD73005, p. 16-25.

Figure 7. In the 1960s, Lisitsyn revealed Russian scientists had deciphered the human brain code.

EXPLORE! VOLUME 9, NUMBER 2, 1999

In that system, it appears that any change in time Δt can be taken as always a function of a corresponding change in energy ΔE, where $\Delta t \leq (\Delta E) \div c^2$ [1] from which it follows that $\Delta E \geq (\Delta t) \times c^2$ [2] For convenience, we take the special case where $\Delta t = (\Delta E) \div c^2$ [3] $\Delta E = (\Delta t) \times c^2$ [4].

Observation as Used in Physics Is Spatial

We note that all mind operations are time-like, i.e., they are comprised as scalar EM photon functions and scalar EM wave functions. Thus the mind is a very special kind of electromagnetic system, existing in the time domain, and thus "lost" by the stripping away of time in the ordinary observation process. Physical observation is essentially a time-differentiating mechanism applied to a 4-spatial change, or in terms of MKS fundamental units L and t, observation θ is $\theta = \partial/\partial t(L^3t) = L^3$ [5].

Thus, as is well-known in quantum mechanics, physical observation is 3-spatial, and time is not a physical observable, even in theory. Since mind is time-like, it follows that mind is not a physical observable either, since discarding the time dimension also discards the mind. In short, one may also take physical operation as the mechanism that separates mind and body. To observe is to separate. We point out, however, that merely "separating and discarding" the time domain (as in physical observation of a single change) does not eliminate it, nor does it eliminate the single time-like mind change that may be involved in an intentional volition. The time domain certainly remains, even though only the 3-spatial intersection of the 4-spatial mechanism and the resulting "outputs". So a series of coherently integrated "mental intent" changes introduced into the human body's overall servo-mechanism provides the continuing input. From there, ordinary physics will generate the resulting actions induced in the body by that servomechanism and its amplifying mechanisms.

Two Coupling Mechanisms Make a Closed Loop

This is the "mind-to-body" coupling mechanism. [See *Figure 5*] It is the mechanism whereby the mind is coupled to the body, and whereby mental intent is able to induce a series of physical inputs into the body servomechanism.

So the body's servomechanism then generates the responses of the body (including everything from chemistry to electrical changes to muscular movements, etc.). These responses are changes in 3-space.

The conscious mind is a *serial processor*, though extremely rapid. It produces the series of coherent intent inputs for volitional behavior.

The unconscious mind is a *massively parallel processor*.[20] It continually produces the vast series of coherent "unconscious intent inputs" for control of all the deeper processes in the body, beyond usual conscious awareness.

However, as the body moves or changes in 3-space, each resulting quantum change in body 3-space is also a slight rotation out of 3-space and toward the time axis. Hence it induces—in the "virtual state" in the time domain—a precisely correlated projection. The body's responses are in general

Minkowski change is given by physical observation. So we may say *that the time-change remains in the virtual state, with respect to attempted physical observation of a single Minkowski 4-space change.*

Rotation, Coherent Integration, and Intent

Previously we pointed out that any change in a 4-space entity may be regarded as a rotation away from the "trajectory" of the entity. Hence each and every t-polarized change creates a very small projection into 3-space by its rotation slightly away from the time axis. All mind changes in the time-domain actually produce virtual 3-spatial projections in 3-space (in the physical domain). We define "intent" as the continued production of successively coherent mental changes, producing coherent virtual changes in the 3-space body system, with coherent integration of those 3-space virtual changes into observable 3-space energy inputs into the 3-space body system. Successively coherent mind-changes will produce successively coherent 3-space virtual changes. In short, coherent mind-changes will produce coherent integration of those 3-space virtual projections into an observable 3-space change. This is the creation of an ordinary 3-spatial energy change induced upon the 3-space body. In short, this is the mechanism whereby time-like mental intent is able to produce a series of coherent observable quantum changes in the physical body (as in the brain and nervous system).

The Body as a Servomechanism

From the standpoint of control theory, we may consider the body system to be a coherent, so a coherent series of virtual state changes in the time-domain (in the mind realm) are created successively. In short, again we have coherent integration, this time in the mind or time domain. This produces "observable" changes in the time-mind domain, which are coherent with the body's 3-spatial changes actually performed. Thus the mind receives feedback directly from the physical movements and changes of the body. This is the manner in which the body is coupled back to the mind.[21]

By comparing the "intent" behavioral move that was "fed forward" into the body, with the return "response" move analog that was "fed back" from the body to the mind, the mind is able to determine errors and differences, and originate additional correctional commands.

Thus the entire mind-body loop is a closed-circuit system of feedforward and feedback, together with corrections. It also has multiple levels of such, infolded in the larger volitional levels. See again *Figure 4*.

This solves the age-old problem of the mechanisms for the mind-body coupling, intent, volition, conscious and unconscious functioning, sense of the external world, sense of the internal world, sense of "being in" the external world, etc.[22]

All This Is Included in Russian Psychoenergetics

This is the highly summarized basis for *psychoenergetics*, the KGB's division of energetics that deals with the mind and body coupling and functions, and direct engineering of (1) the mind-body coupling and (2) the mind operations directly. [See *Figure 6*] The KGB intent, of course, has always been to exploit this science for the complex servomechanism system comprised of many subordinate servo systems with feedback and feedforward looping.

Given the input from intent, ordinary servo theory will take it from there. Once a servo has an input, servomechanism theory describes the response of the

degradation, killing, and control of human beings, including all humanity.

The Russians know full well that, if you produce and utilize scalar EM photons and t-polarized EM waves, you can directly affect and engineer mind and mind operations at any and all levels. Western researchers, who know nothing of how to make

EXPLORE! VOLUME 9, NUMBER 2, 1999

time-polarized photons and time-polarized EM waves, do not yet know that. Consequently the Russians have developed a highly secret science of *directly* engineering the mind and its operations, including thought, images, perceptions, feelings, emotions, memory, and mind processing. Indeed, Lisitsyn[23] wrote quite specifically of this capability in the 1960s. [See *Figure 7*]

Western clandestine mind control researchers are apparently still slowly and painfully fitting TW EM irradiation correlates to induced or resulting mental and physical behavior responses. They seem unaware of the actual wave transductions occurring inside the body and mind, but are unwittingly inducing those transductions in hidden fashion anyway and in "brute-force input-response fitting" models.

These "fitted brute-force models" certainly can be very powerful, and certainly can produce the exact results shown in the experimental verifications of the fittings. However, they do not of themselves allow sophisticated design—for example—of the necessary time-polarized wave assemblies for engineering the entire human collective unconscious simultaneously, or for engineering the entire collective unconscious of all species on Earth (i.e., Gaia's collective unconscious), or even for precisely engineering the memory and knowledge base of an individual.

This fine research article will be continued in Part II with Russian Methodology, Waves and Wave

spacetime that is highly active. The mind is rooted in the time-domain and projects from that domain into 3-space. The body is rooted in the 3-space domain and projects into the time-domain. To "change" or "function" in one domain is automatically to function in the other. EM and gravitational phenomena are still modeled separately by human scientists, but not by nature.

3. In quantum mechanics, time is not an observable, but merely a parameter.

4. It is convenient to consider mass as a 3-spatial form of condensed energy.

5. E. T. Whittaker, "On the Partial Differential Equations of Mathematical Physics, " Mathematische Annalen, Vol. 57, 1903, p. 333-355;— "On an Expression of the Electromagnetic Field Due to Electrons by Means of Two Scalar Potential Functions, "Proc. Lond. Math. Soc., Series 2, Vol. I, 1904, p. 367-372.

6. A NERAC document search yielded some 16 good references on t-polarized photons, but not a single reference on t-polarized EM waves.

7. E.g., such previously inexplicable instrument anomalies have accompanied some excellent and rigorous electrolyte experiments at U. S. Navy research facilities at China Lake. For a description, see Melvin H Miles and Benjamin F. Bush, "Radiation measurements at China Lake: Real or Artifacts?", Proc. ICCF - 7 (International Conference on Cold Fusion—7, Vancouver, BC, Canada, Apr. 1998, p. 101. For a brief explanation of the anomalies, see T. E. Bearden, "EM Corrections Enabling a Practical Unified Field Theory with Emphasis on Time-Charging Interactions of Longitudinal EM Waves, " Explore!, 8(6), 1998, p. 7-16;— "Toward a Practical Unified Field Theory and a Deep Experimental Example," Proc. INE Symposium, Univ. Utah, Aug. 14-15, 1998.

8. Many U. S. researchers and journalists—and even many scientists—have wrestled with the problems of mind, intent, and mind-body

Transduction, The Cellular Control System, and other matters of interest. ♦

ABOUT THE AUTHOR

President and Chief Executive Officer, CTEC, Inc. Lieutenant Colonel US. Army (Retired). MS Nuclear Engineering, Georgia Institute of Technology. BS mathematics, Northeast Louisiana University. Graduate of Command & General Staff College, US. Army. Graduate of Guided Missile Staff Officers Course, U. S. Army (equivalent to MS in Aerospace Engineering). Numerous electronic warfare and counter-countermeasures courses.

Tom is the leading advocate of scalar potential electromagnetics and the Fogal charge-blocking semiconductor: He is involved in alternate energy devices and scalar electromagnetic system prototypes. He has defined charge q as a coupled system of two components, advanced a mechanism for a vacuum engine, whereby the vacuums virtual particle flux is organized and used to energetically shape and manipulate matter and energy, and advanced a mechanism for a Bohm-type quantum potential, which theoretically allows the engineering of action at a distance in physical systems.

He is president of the Association of Distinguished American Scientists (ADAS), a life member of the Alabama Academy of Science, Emeritus member of the American Association of Physics Teachers, and has served on the Board of Directors of several associations

coupling. Enumeration of those efforts would itself require an entire book. For an introduction into that domain, the reader is referred to the very determined exposé by Cheryl Welsh in her very timely book, The 1950's Discovery of the Code of the Brain, May 1988, published on the Internet. Simply employ any Net search engine and search on the name Cheryl Welsh. A connection to the site and to Welsh's book will immediately be found Welsh's important compendium is highly recommended, giving the reader a "birds eye view", so to speak, of how Western scientists think and proceed regarding the subject of mind control by electromagnetic means. Unfortunately all journalists so far researching the area have not been aware that Western electrodynamics itself is seriously flawed, and that the great Russian advances in mind engineering and mind control are a result of their secret but complete revision and correction of Western electrodynamics to provide the basis for energetics. Until Western scientists revise their own decrepit old electrodynamics fouling the textbooks, they will never catch up to the Russian mind control developments springing from intense development programs that did that revision in the late 1940s and early 1950s.

9. An Invention Disclosure on these processes and enhancement embodiments has been filed with the U. S. Patent Office. Formal patent applications are also in preparation.

10. Energetics is a unified science of an extended electrodynamics possessing a hidden infolded general relativity inside the potentials, fields, and waves. It deliberately employs higher polarizations (longitudinal and tempic) of photons and EM waves to engineer action at a distance, use of specific patterns of spacetime curvature created at a distance, and direct engineering of either inert or living bodies. It also encompasses the direct engineering of time-like mind and mind functions. It is divided into three divisions, depending upon the nature of the target. Targeted against inert materials, structures, fields, and waves it is called "energetics. "Against living bodies, their fields,

and corporations. Tom is a guitarist, a retired aikidoist (Sandan, Yoseikan style), is happily married and has two sons and two daughters. He and his wife Doris live in Huntsville, Alabama where Tom is retired from aerospace, continues private research, and serves as a consultant to industry on Scalar electromagnetics processes.

REFERENCES

---

1. E.g., see Lewis H Ryder, Quantum Field Theory, Cambridge University Press, 2nd Edition, 1996, p. 147+. For an even deeper discussion of photon polarization, see F. Mandl and G. Shaw, Quantum Field Theory, Wiley, 1984, under the heading "Covariant Quantization of the Photon Propagator" in Chapter 5. Mandl and Shaw argue that the longitudinal and scalar polarizations are not directly observable, but only in combination, where they manifest as the "instantaneous" Coulomb (i.e. electrostatic) potential.
2. Nature is unified and not separated into the "separate" disciplines our science has prescribed. Thus the mind is also totally electrogravitational. The mind works not just with EM
forms in an inert space, but also with spacetime curvatures in a

and biochemistry, it is called "bioenergetics." Against the mind and mind functions, it is called "psychoenergetics".
11. Psychoenergetics is that branch of energetics used to directly affect and engineer the mind, memory, perception, thought, emotion, sensation, personality, and other mind functions of a living biological organism. It is usable against a single personal conscious (serial processor) mind and a single personal unconscious (massively parallel) processor mind In theory it is also usable against lungs collective unconscious mind and its functions, as well as the deeper unconscious for all species on Earth (i.e., against Gaia). We are speaking of physics, not metaphysics.
12. W A. Rodrigues Jr.. and J.-Y. Lu, "On the existence of undistorted progressive waves (UPWs) of arbitrary speeds $0 \leq v < \infty$ in nature," Foundations of Physics, 27(3), 1997, p. 435-5•08 A slightly corrected version is downloadable as hep-th/9606171 on the Los Alamos National Laboratory website.
13. E. T. Whittaker, "On an Expression of the Electromagnetic Field Due to Electrons by Means of Two Scalar Potential Functions, "Proc. Lond. Math. Soc., Series 2, Vol. I, 1904, p. 367-372. The paper was published in 1904 and orally delivered in 1903.
14. E.g., see T. E. Bearden, Fer-de-Lance, Tesla Book Co., 1986;—AIDS: Biological Warfare, Tesla Book Co., 1988;—Soviet Weather Engineering Over North America, 1-hour videotape, 1985,—Gravitobiology; A New Biophysics, Tesla Book Co., P.O. Box 121873, Chula Vista, CA 91912, 1991,—Energetics of Free Energy Systems and Vacuum Engine

EXPLORE! VOLUME 9, NUMBER 2, 1999

Therapies, Tara Publishing, Internet node www. tarapublishing.com/books, July 1997; — Energetics: Extensions to Physics and Advanced Technology for Medical and Military Applications, CTEC Proprietary, May 1, 1998, 200+ pages furnished to selected government agencies and key Congressional committee leaders.

15. E.g., see T.D. Lee, Particle Physics and Introduction to Field Theory, Harwood; New York, 1981. On P.383, Nobelist Lee points out that the microstructure of the scalar vacuum field (i.e., of vacuum charge) is not utilized. Particularly see Lee's own attempt to indicate the possibility of using vacuum engineering, in his "Chapter 25; Outlook; Possibility of Vacuum Engineering, " p. 824-828. With wave transductions and use of higher polarization EM waves, there are far better and more powerful ways to do vacuum (spacetime curvature) engineering.

16 T.E. Bearden, "Formation and Use of Time-Reversal Zones, EM Wave Transduction, Time-Density (Scalar) EM Excitation and Decay, and Spacetime curvature Engines to Alter Matter and Convert Time Into Energy," Invention Disclosure Document #446522, Oct. 26, 1998.

17. T.E. Bearden, "EM Corrections Enabling a Practical Unified Field Theory with Emphasis on Time-Charging Interactions of Longitudinal EM Waves, "Explore!, 8(6), 1998, p. 7-16; — "Toward a Practical Unified Field Theory and a Deep Experimental Example," Proc. INE Symposium, Univ. Utah, Aug. 14-15, 1998.

18. We have used the enormous energy density of time in our approach to a totally new kind of electronuclear interaction at feeble spatial energy. By use of a time-reversal zone (TRZ) in a fluid; the free H+ ions—which are free protons—can be induced to attract each other so tightly that the edge of the nuclear force region is entered. In that case the protons form a quasi-nucleus. When the TRZ decays back to a time-forward zone (TRZ), this new quasi-nucleus decays by changing quarks in one or more

means "sense of existing in time".

20. The "unconscious" is totally conscious, just multiply so. The conscious mind can see only "a single slide in the slide projector at a time, " so to speak. When it "looks" at the ongoings and outputs of the unconscious, it "sees" millions of slides in the slide projector simultaneously. Hence it cannot distinguish "one and one only". So it just sees nothing, where by "nothing" we mean "no single distinguishable thing." It therefore is unable to consciously perceive the actions of the unconscious. When the unconscious wishes to communicate with the conscious (because of unresolved conflicts, etc.), it must produce large groupings integrated into "symbolic scenarios". Hence the symbolism of the unconscious, and the basis for therapeutic psychology and psychiatry. A "symbol", after all, is just a thing which can have many different meanings, all folded into one.

21. The mind continually has activities of its own, each of which produces coherent changes in the body to a much smaller degree. The interweaving of these "smaller self-changes" infolded inside the 3-space major intent changes also produces slight body changes, which in turn "project back" into the mind. This huge group of "infolded self-loops" produces the sense of "my body" being "volitionally directed or occupied" simultaneously with the "greater intent" loops which represent "my intentional actions with my body". Further; the body servo continually receives a myriad of inputs from its sensory systems, both from changes inside the body and from incoming changes from the external universe. This interweaving produces the awareness of "being in the external world" by having (i) changes whose feedback do not match mind-intent changes, and (ii) changes whose feedback does match mind-intent changes. This of course applies to both the conscious and unconscious levels. The purpose here is to demonstrate that there exists an actual physics of the living being, the mind as well as

nucleons, thereby producing new nuclides. We point out that this is actually a very high energy reaction; however; since the time-energy is used and is very, very dense, the amount of 3-spatial energy that must be used is very small. If this new mechanism holds, it represents a revolution in particle physics.

19. "Self-awareness" refers to be continually "refreshed" by time-delayed coherent feed-back inputs from the body to the mind; where these inputs compare to the recalled memory of the minds inputs to the body. In short, the time-delay coherence creates the sense of "existing in time". Awareness usually the body, and the coupling and interfiinctioning of mind and body.

22. The methodology also easily extends to include deeper interlays for the collective human unconscious mind and for Gaia—the collective unconscious mind level for all the species on earth.

23. S. K Lisitsyn, "New Approach to the Analysis of Electroencephalograms, " in Problems of Bionics— (Selected Articles), Defense Documentation Center Report AD 73005, date unknown, p. 16-25. Available through the National Technical Information System (NTIS).

Mind Control and EM Wave Polarization Transductions, Part 2

©Copyright 1999 by T.E. Bearden, USA

This article continues on with T.E. Bearden's article, Part 1 of which was published in Volume 9, #2 of Explore! for the Professional. Because we feel that Col. Bearden's caution below is so very important we are repeating its publication in all parts of this article.

Special Note

This article refers to experimental research techniques which can be detrimental or lethal in the hands of any but highly skilled, qualified experimental scientists proceeding under proper laboratory safety procedures. The purpose of this article is strictly for information to properly qualified and authorized scientists in certified laboratories. We do not propose or condone any use of these procedures for non-approved practice of medicine without a license. Neither the publisher nor the author are responsible for accidents or outcomes in the use of these experimental procedures and techniques. Any researcher who performs these procedures and experiments is acting on his or her own volition, and is solely responsible for insuring safety, qualifications, and legality of the acts and their results. We neither suggest nor condone unauthorized experimentation on human subjects. Such is a criminal violation of the constitutional rights of the subject under Federal and State laws, and is both illegal and immoral.

A Strategic Threat Completely Unrecognized by the West

The Russian methodology leads directly to rather mind-bending, extended capabilities. KGB psychoenergetics scientists seem fixed on an eventual goal of directly engineering Jung's collective human unconscious, thereby converting the entire human species into a sort of "ant" species. In short, they seek to engineer what they regard as "perfect communism and perfect order" directly in the entire species. *Figure 8* indicates the direct connection of every human's conscious and unconscious mind to the collective species unconscious and to Gaia, the collective unconscious for all species on Earth. Since time is internally structured and layered, it follows that time-like mind levels are also internested and layered.

This appears to be a significant strategic threat, *well along in its development*, that our scientific and intelligence communities have completely failed to recognize.

The direct engineering of the entire human collective species is a doable.[1] It is going to be done, whether we like it or not. In that race (which may eventually determine whether or not we retain any personal freedom at all), the "democratic" nations are woefully behind. In fact, the West has not even realized there is such a new kind of "arms race" for dictatorship and control of the "collective species mind" and we have already almost lost it. The West has not yet even developed the overall theory of psychoenergetics.

Waves and Wave Transductions

A pure longitudinal EM wave (LW) would have infinite energy and infinite speed. In practice, one can only approach this perfect LW wave, and one always has transverse residues remaining. Hence the "imperfect" longitudinal EM waves we can make in suitable equipment and techniques, are known as "undistorted progressive waves" (UPWs). The UPWs may have velocity far greater than the speed of light, or less than the speed of light. So the speed v of UPWs can vary as

$$0 < v < \infty \qquad [6]$$

The Russians also know that, when a nearly-pure longitudinal EM wave interacts with matter (it usually doesn't interact very much, and has a low reaction cross section), the mass immediately adds the phase conjugate replica to the interacting LW portion, regardless of frequency, thereby transducing the input LW interactions into scalar (time-polarized) EM interactions.

One transduces from TW to LW to Scalar EM via iterative phase conjugation. One transduces from scalar EM to LW to TW via iterative interferometry. It took the present author 20 years to discover this simple thing; we now have filed an invention disclosure on the process and embodiments for performing it, and will be following with formal patent applications. Let TW = transverse EM wave, LW = longitudinal EM wave, and TDW = time-density EM wave (another name I use for t-polarized or scalar EM waves, since the density of time-energy is what is varying). Let (I) = interfering with, PCR = phase conjugate replica wave with a coupled set of parentheses enclosing the type of wave. The rules for wave type transduction are:

$$\mathrm{TW} + \mathrm{PCR(TW)} \Rightarrow \mathrm{LW} \qquad [7]$$

$$\mathrm{LW} + \mathrm{PCR(LW)} \Rightarrow \mathrm{TDW} \qquad [8]$$

Going the other way, the rules are:

$$\mathrm{TDW\ (I)\ TDW} \Rightarrow \mathrm{LW} \qquad [9]$$

$$\mathrm{LW\ (I)\ LW} \Rightarrow \mathrm{TW} \qquad [10]$$

In EM smog (dense EM signals, even though very weak), there is increased nonlinear multiwave interactions, both interferometric and phase conjugative. So in such EM smog there exists an increased, non-negligible component of LW and TDW irradiation, formed by the above transduction interactions in the irradiated living cells and bodies. This latter part accounts for many of the long term effects which show up in "correlative" studies, but which do not show up in the normal limited-frequencies TW experiments produced by so-called "physical experiments."

The standard EM bioeffects manner of experimenting uses a theoretical model of simple, direct energy deposition by means of absorption in cells and tissues. Now we must utilize an "open system" throughout the body dielectric in which higher polarized EM energy (either LW or t-polarized) travels readily throughout all areas of the body.

Explore! Volume 9, Number 3, 1999

EM Bioeffects and Wave Transductions

In the EM bioeffects experiments to date, there has been absolutely zero control of the internal transductions, and there has been no consideration of them. Almost all transductions of TWs into LWs will immediately result into transduction into TDW and time-excitation charging of the cells and all their internal components. These time-excitation charges (excited states of time-charging) will then slowly decay, emitting longitudinal EM waves in the process which travel throughout the body. These emitted LWs interfere with each other and the LW processes in the body, producing low level TW "noise jamming" of the cellular processes and—most especially—of the deep cellular control system of the body. The latter system functions by means of LWs and TDWs. Long-term effects of such "noise jamming" of biochemistry reactions and the control systems of the cells and body, can lead to degenerative diseases such as arthritis, atherosclerosis, Alzheimer's disease, heart disease, cataracts, tumors, leukemia, somewhat accelerated aging, immune system weakening and depressing, etc. As the body's natural defense and regeneration ability weakens, opportunistic infections further add to the degeneration.

It was shown by Whittaker in 1903 that any scalar EM potential is comprised of a harmonic series of bidirectional longitudinal EM wavepairs. [See *Figure 9*] Each longitudinal EM wave pair in the harmonic series is a phase conjugate pair. Unknown to Whittaker, that "LW phase conjugate pair" is actually a time-polarized EM "photon" structure, containing a phase conjugate LW photon substructure. So staid old "voltage" (potential) is comprised of a harmonic series of time-polarized EM waves!

The corresponding "t-polarized photons" are actually spin-4 *supergravitons* comprised of coupled antipairs of LW "photons". Each LW photon is a spin-2 *graviton* comprised of a coupled TW photon-antiphoton pair. Each TW photon and antiphoton in the coupled pair has spin-1. The couplet, being the longitudinal "photon" or graviton, thus has spin-2. And so on.

In 1904, Whittaker showed that any EM field or wave pattern can be decomposed into two scalar potential functions. By applying Whittaker 1903 decomposition to each scalar potential function, any EM field or wave has an enormously rich internal structure, comprised of scalar potential functions in interference. Each scalar potential function is comprised of time-polarized EM waves (made of spin-4 supergravitons). Each time-polarized EM wave is further comprised of bidirectional longitudinal EM wavepairs. Each longitudinal EM wave is further comprised of phase-conjugate pairs of transverse EM waves. Each transverse EM wave is further comprised of two scalar potential functions, each of which is in turn comprised of an infinite harmonic series of time-polarized EM waves, and so on *ad infinitum* and *ad nauseum*. Obviously all EM potentials, fields, and waves have an enormous "internal structure" or internal "information content of the field".

The Cellular Control System Uses t-Polarized EM Photons and Waves

The master cellular control system (MCCS) in the body utilizes these photon-gravitons, their corresponding EM wave polarizations, and transductions between them. By the use of very powerfully condensed gravitons and supergravitons, it is able to utilize small but highly significant direct curvatures of spacetime. It does not merely send a "signal" and hope the cell itself acts upon it. Instead, it sends an "engine" which alters the local spacetime in which the cell and all its components are embedded. This "local ST curvature engine" then physically works directly upon the cell and all its parts, to alter the cell according to the specific "template" of the engine.

This is the direct application of the Wheeler's simple statement of general relativity: *Mass (trapped energy) acts upon spacetime to curve it, and curved spacetime acts upon mass to change it.*

Popp's "ordinary photon" study of this cellular control system[2] therefore will detect the coherent ordinary TW photon residues which result from the photon polarization transductions occurring from the actions of the ST curvature engines upon the cells.

Cellular division, biochemical processes, growth and growth control, cell differentiation and dedifferentiation, etc. are all controlled by the MCCS or one of its subsystems, using spacetime curvature engines. The ordinary TW electronic activity our biophysicists detect and correlate are simply the intermediate components of the actual ongoing polarization transductions.

The Cellular Control System Uses EM Time-Energy

One important subsystem of the MCCS controls the immune system's functions, including the deepest and most subtle functioning performed by all elements of the immune system. This system has been rather intensively studied, but since our biophysicists have not possessed the full electrodynamics utilized, only the correlated residue of normal TW EM waves and photons have been recognized and studied. Hence Western biophysics is in its very crude infancy.

Incorporation of the total wave and photon polarizations, together with their transductions, will eventually present a revolution in both biomedicine and biophysics. Unfortunately, presently our entire medical community is very firmly entrenched in only ordinary TW EM polarizations and ordinary biochemistry. Our scientists thus are studying less than 1% of the functioning of the living organism.

As an example, since Western scientists have no knowledge or research into the time-polarized mind domain and mind-body coupling, the mystery of the *placebo effect*—in which the mind has been verified to produce actual physical effects – will indefinitely remain a mystery.[3] As one result of that "crippling" of our medical theory, medical experimenters have to deliberately drive experiments on drug effects, etc. beyond the "mind's own threshold" of physical effect. In short, they have to drive the experimental results over and above the results being accomplished by the placebo effect. They must perform valid placebo control experiments, and subtract the placebo component results from their own experimental results, to determine the "delta" induced purely by the drugs.

The Regenerative Subsystem

Another important subsystem of the MCCS controls the *regenerative system* of the body. The regenerative system has various mechanisms, including growth control, differentiation and dedifferentiation of cells, etc. Becker's portrayal of the regenerative system is shown in *Figure 10*. One of its most important functions is healing and restoring damaged or diseased cells. It does that by a most remarkable process.

This system has been very poorly studied, mostly by Becker[4] powerfully condensed gravitons and supergravitons, it is able to utilize small but highly significant direct curvatures of spacetime in precise patterns. In short, it utilizes general relativistic spacetime curvature engines, rather than "EM photon signals", to accomplish its control of the cells and their processes. It does

does that by a most remarkable process.

This system has been very poorly studied, mostly by Becker[4] *et al.*, although there is still sporadic, ill-funded, and ill-planned research on regenerative effects from time to time.[5] Becker and his colleagues came closest, and—considering the severe limitations of the orthodox U(1) EM model available to them—Becker's work is particularly revolutionary. He demonstrated beyond question that simple DC potentials could generate cellular differentiation and redifferentiation, and produce results at global sites in the body and not just at the local injury sites where the DC potentials were applied.

Becker was nominated for a Nobel Prize for his Herculean efforts and remarkable results. For his trouble he was hounded, his funds were withdrawn, and he was forced to retire at an early age in his 50s. His biggest "heresy" was to bravely point out that power line radiations had deleterious effects upon biological systems, and to testify to it in a series of hearings and court cases where a very powerful electrical power industry essentially ran rough shod over science and the public.

Organized Science Is Highly Politicized and Imperfect

It is not only politicians that are "bought and paid for" by powerful vested financial interests. In organized science, precisely the same arrangement holds true. Scientists are no better or no worse than any other segment of humanity. A surprising percentage will produce the results desired by their benefactors, if provided with cushy jobs, good income, prestige, and secure positions.

It has been said that money is power. It has also been said that power corrupts, and absolute power corrupts absolutely. In the scientific community, as well as in the political community, this "great corruption" by great financial power has been elevated to an art form. Simply examine the funds made available to scientists. There is not enough for all the scientists, so it is fiercely competitive. If the scientist does not get grants (e.g., a would-be professor at a university), he does not bring in extra money to the university. He cannot get his graduate students funded, so his own innovative (read: heretical) research is thwarted. His papers are rejected by the journals, and before long he has no funded position in science. If lucky, he will be employed in the grocery store or the butcher shop.

Every bit of funding available for the scientists to compete for (and apply for grants) already has firmly fixed controls of exactly what research can be done with that money. The "science" that will be applied is already formulated. That and only that can be done. It is a tribute to the dedication and resourcefulness of our working scientists themselves, that anything innovative at all gets done.

One can have a very fine scientific career, tenure as a professor, get one's graduate students funded, get one's papers published in prestigious journals, win awards and achieve stature and prestige, if one just plays the desired game prescribed by the "old boys schools" in control of almost all the scientific funding. Yes, one can permissibly move the decimal point in the present models a bit, and be rewarded handsomely for doing so. But one is damned if one attempts any serious change or overthrow of obsolete scientific models and practices favored by the "system".



Figure 8. Nested levels of consciousness and unconsciousness.
The mind levels contain the "life" and "mind" dynamics.

EXPLORE! VOLUME 9, NUMBER 3, 1999



That is precisely why all our universities continue to teach a terribly flawed electrodynamics that is a caricature with at least 32 major foundations flaws in it.[6]

And that's why the organized Western scientific community has betrayed the taxpayers who largely fund its research. In short, the scientific community fiercely enforces dogma, suppresses innovation, and has denied the U.S. the very defense we need to survive against our pressing enemies who have not been so scientifically dogmatic.

Microwave Radiation of the U.S. Embassy in Moscow

Because of the strongly enforced adherence to the insane foundations errors in classical electrodynamics, our scientists still do not comprehend the decades of so-called "microwave radiation" of personnel in the U.S. Embassy in Moscow.[7] All diseases and health changes produced in those personnel were in *field-free areas* (i.e., where the potentials were persistent and unchanging, with no gradients etc.)[8] No one even thought to look at the "inner longitudinal EM phase conjugate biwave composition" of those potentials, where they would have found the Whittaker internal bidirectional longitudinal EM wavepairs and the internal time-polarized EM waves. They would also have found the infolded, very powerful general relativity: the spacetime curvatures deterministically formed and being utilized to directly alter the irradiated cells and their constituents.

Instead, government-funded studies did a rather straightforward "force field" analysis, and concluded that, since there were no fields there, it could not have been the microwave radiation.

Elementary statistics would immediately indicate a different conclusion: The diseases and health changes were 100% correlated to the presence of potentials, and 100% anticorrelated to the presence of fields. Hence it was the field-free potentials that had to be inducing the diseases and health changes. If it were NOT the radiation at all, then some changes would have occurred in personnel in areas where fields were *present*, as well as in areas where fields were *absent*. Since this did not occur, such a premise is destroyed by self-contradiction. In short, the data actually proved (i) it was indeed the radiation that was causing the diseases and health changes, and (ii) further, it was the field-free potentials that were the culprit.

That this elementary statistical conclusion eluded our scientific community and our government community, is absolutely inexplicable.

Three U.S. Ambassadors eventually died of diseases induced by their exposure to the Embassy radiation. Ironically, Kaznacheyev[9] had openly released some of the results of thousands of Soviet military experiments showing that any kind of cellular disease or disorder could be induced in targeted cells by novel EM radiation emitted from diseased or damaged cells. Apparently no one in the West deciphered the mechanisms involved in Kaznacheyev's epochal work.



The Structure Is:

- A harmonic set of longitudinal phase conjugate wavepairs.
- In each wavepair the two waves superpose spatially after detection, but travel in opposite directions.
- The convergent wave set is in the imaginary plane, and hence is not observable. It is EM energy incoming to the potential (dipolarity) from the time domain.
- The charge's spin is 720 degrees, 360 in the real plane and 360 in the imaginary plane.
- Hence the charge receives the complex convergent EM energy, transduces it into real EM energy, and emits enormous energy at the speed of light in all directions -- which includes bidirectional pairs in 3-space (after the reaction, being after "observation").
- This produces the fields and potentials from the "source charge or dipole."
- Mandl and Shaw argue that the scalar (time-polarized) photon and longitudinal photon are observable only in similar pairs, which then makes the instantaneous scalar potential. Thus their quantum field



- Mandl and Shaw argue that the scalar (time-polarized) photon and longitudinal photon are observable only in similar pairs, which then makes the instantaneous scalar potential. Thus their quantum field theory work strongly supports the "negative resistor" interpretation of the scalar potential and our solution to the source charge and source dipole problem.

Figure 9. Infolded longitudinal biwaves (time-polarized EM waves) composition of a scalar potential.

EXPLORE! VOLUME 9, NUMBER 3, 1999

Figure 10



The Present Situation in Western EM Bioeffects Research

Our scientific community has not even *designed physical experiments* to validate long-term EM bioeffects of the kind caused by induced wave transductions and long-term effects inside the absorbing human cells and in the body's regenerative and immune systems. Western science has no knowledge of these technical internal "wave polarization transduction" mechanisms. Yet the basis for such mechanisms has existed in the hard physics literature for decades. Leading EM bioeffects researchers seem totally unaware of small reaction cross sections inside the body cells and tissues for the transduction of transverse EM signals into LW and t-polarized EM signals. Conventional Western researchers have not investigated it, and often will not believe it when it is pointed out to them along with the supporting basis in the literature.

A major part of the mainline "EM bioeffects" community, of course, seems comfortably funded largely by the power industry etc.[11] The record is clear that this dominant, well-funded group has little or no intention of "finding" anything that will question powerline radiation safety and upset their cushy positions.

In fact, leading bioeffects researchers have pointed out this deliberate biasing of EM bioeffects as a research area. Quoting Dr. Andrew A. Marino, one of the great pioneers in the area of EM bioeffects[10] and powerline radiation assessment.[11]

"Neither scientists nor the public can rely on power-industry research or analysis to help decide whether powerline electromagnetic fields affect human health because power-industry research and analysis are radically misleading."

Dr. Marino then gives the specific details to prove it, and he shows specifically how they slant and mangle their experiments and interpretations of the results, to do it. If the major financial interests cannot *scientifically* destroy determined, honest researchers such as Marino and Becker, they do not hesitate to attempt to destroy them in lawsuits.

The "Diffusion Mixmaster" at All Body and Cellular Levels

Every mass and all its particles are in a violent energy exchange with the active vacuum. A human body and every part of it is in a continual exchange of EM energy with its environment(s), including transverse, longitudinal, and t-polarized (scalar) EM energy exchanges. Further, within the dielectric body there is a sort of intensive "diffusion" of special kind, actually due to iterative phase conjugation and iterative interferometry of the dense signals environment impinging upon it. This internal "diffusion" and transduction (iterative multiwave phase conjugation and iterative multiwave interferometry) thoroughly "mixes up and transduces" one type of EM wave or signal into the other, including many of the body's own TW, LW, and TDW signals.

Continual or sustained TDW exposure (irradiation by t-polarized EM waves) charges the body and its particles with time-excitation charging, something which has been erroneously omit-


Becker's theoretical control system governing regeneration*
Trauma Producing Tissue Loss
Local cellular effect
Local nerve effect
CNS effect
Alterations in hormone pattern (prolactin)
Alterations in local DC field pattern
Local electrical effects
Local and systemic pools of target cells
Dedifferentiation into primitive mesenchymal cells
Phase I
Blastema formation
growth
Phase II
Redifferentiation into required cell types
Restoration of body
*Becker & Spadaro, "Electrical stimulation of partial limb regeneration in mammals," Bull. N. Y. Acad. Med, 48(4), May 1972, p. 629.


Restoration of body part or tissue
Bull. N. Y. Acad. Med, 48(4), May 1972, p. 629.

Figure 10. Becker's model of the Regenerative system of the body.

EXPLORE! VOLUME 9, NUMBER 3, 1999

ted in physics, but is true nonetheless. Inexplicably, physicists just ignore what happens time-wise when a mass absorbs a photon. We have covered that elsewhere.

So inside the body dielectric, there is a "diffusion mix" correlate of any and every type of the waves, to any or all of the exchanges, plus the additional internal interactions of the body in its TW, LW, and scalar EM wave transductions. There is a one-to-one correspondence to any one of the three types of polarization waves (transverse, longitudinal, and scalar) and everything going on anywhere in the body.

Note that the type of LW we are using is actually made of phase conjugate pairs of transverse EM waves, so its "photons" are made of photon/antiphoton pairs. That is, our longitudinal EM wave has an internal TW structure, and the LW wave is comprised of spin-2 *gravitons*. Our longitudinal EM wave has an internal structure, and it dramatically differs from the LW used by the U.S. scientific community which ignores wave, field, and potential infolded substructures. Our LW (which seems to be what the Russians use) is also a gravitational wave because it is comprised of oscillations in its distributions of spin-2 photon/antiphoton pairs (i.e., *gravitons*).

The type of t-polarized (scalar) EM wave we are using is a phase conjugate coupled pair of the specialized electrogravitational (EG) LWs. The "t-polarized photons" comprising this t-polarized "EM" wave are comprised of spin-4 *supergravitons*. These are, I believe, what the KGB energetics weapons scientists use also. By iteration, we can go into as deep an internal multilevel structuring of EM and EG waves, of any type, via methods shown by Whittaker.[12]

Now let us examine a body as a dielectric, sitting there in its exchange, in relative equilibrium. It turns that every tiniest piece of a dielectric participates in any emission from it[13]—even the emission of a single photon, graviton, or supergraviton. Well, it *would* so participate, due to the special sort of correlated diffusion and interferometry and phase conjugation that we pointed out. Anything that escapes (is re-emitted) from the body, has been through this "diffusion wringer". It has escaped from each and every internal part of the body.

Novel Signatures in Body-Emitted EM Radiation of Any Polarization

A single photon or wave emitted from a dielectric carries in its internally structured time component a *template* of the exact internal time structuring of every part of the dielectric emitting that photon. It carries in its internally structured energy component a *template* of the internal energy structuring of every part of the dielectric emitting it. An emitted EM wave, being a collection of emitted photons and photon structures, thus carries the same internal structuring of both its transported energy and its transported time.[14] Western scientists do not use the internal


RETRORADIATION WITH EMITTED TW EM WAVES
Recorders & Broadband Amps
Broadband Antenna Unit
Control Unit
Receiver-transmitters
©T. E. BEARDEN 1998
Adjusting broadband signals bandwidth and amplification
Using an amplified replica of the body's own dense, broadband signal complex to irradiate it, producing deeply-penetrating and precise longitudinal EM wave sets that pump cells and reverse cellular disease and damage

Figure 11.

structuring of photons and EM sine waves, have no instruments for that, and so do not know it. The Russians know it,[15,16] use it, and have developed sophisticated instruments for it for the last 30 years or more.

Shortly we will postulate how conventional scientists experimenting with mind and behavior control electromagnetically might utilize an immediate consequence of the fact that the specific emission from a body at any time—whatever type of wave component we look at—is a total correlate to all that body's internal functions, its energy exchanges with its environment, its states, its mental states and conditions, etc.

And we accent that the coherently integrated intent-changes in that body from its coupled mind's operations are also in the substructure of photons and EM waves emitted from the living body into its environment.

How Western Mind Control Scientists Might Proceed

Conventional scientists would ignore scalar photons and waves, determine the TW spectrum, and then slowly and painfully correlate that to the various physical, mental, and emotional things. That's the way they would *have* to do it, since apparently they use only standard electrodynamics. They can in fact do this via brute force, because that emission TW spectrum is of waves escaping from the entire "diffusion machinery" mixmaster in the body dielectric. It does contain all those integrated *mind-intent* 3-space correlates as well as the ordinary body 3-space energy correlates.

Anyhow, in envisioning Western procedures, the test body would be sitting there, in its normal (let's say fairly normal and quiet) EM environment. [See *Figure 11*] Let's assume this body is not sick, but is healthy and normal. Its emissions are a part of its equilibrium condition. It follows that the totality of its TW emissions is correlated to the sum total of everything that interacted with the body, plus its own internal reactions, including from mind-body coupling. Indeed, everything that has ever happened to that entity—physically, mentally, emotionally, etc.—has internal correlates infolded inside the emitted transverse EM wave spectrum.[17]

So first the scientists would simply measure the full environmental TW spectrum down to very tiny levels in all frequency bands possible—everything that is coming in to the body from its environment. They would probably perform the experiments in a triply-shielded Faraday cage, so the external environment outside the cage contributes very little transverse EM wave noise (perhaps some Schumann resonance). Magnetic wave shielding and ELF shielding is something else again, and longitudinal EM wave shielding is in general not possible unless longitudinal EM waves are employed in the shielding. But a "quiet external TW environment" enhances the isolation and measurement of the specific TW signal transforms the Western experimenters would be seeking.

Then they would measure everything likewise that the body is *emitting* when in that environment. That is the "zero reference" or "normal reference" level. They would measure every aspect: frequency, amplitude, phase, wave shape, modulation, etc.

Probable Experimental and Measurement Techniques

Next they would selectively irradiate the body with specific signals, frequencies, waveforms, etc. They would begin by using

They would consider the body dielectric as a "ship with portholes". Light (EM transverse wave energy) coming out of the portholes has originated and adapted from everywhere inside the ship and its operations. When the experimenters reinsert energy through one or more portholes, they are interested in determining precisely which operations inside the ship are affected. So the body physiological functions are also heavily instrumented.

By feeding back in the exact EM pattern and magnitude escaping the body dielectric through a single porthole, one "nullifies" that part of the emission by producing a net equilibrium in that component. This will in turn produce changes elsewhere in the spectrum emission from other portholes, and this can be measured. It will also produce "stress changes" in specific portions of the body dielectric, and in the heavily instrumented body these physiological, chemical, electrical, etc. changes can also be detected. Monitoring of the skin conductance, e.g., indicates the level of stress, and EEG monitoring with sophisticated instrumentation can indicate something of the brain wave states.

In short, the necessary measurements from which to construct specific correlates can be performed, recorded, and later analyzed.

This article will be concluded in Volume 9, #4 with Improving the Methodology, Further Phenomenology Experiments, Rejuvenation and other matters. ◆

ABOUT THE AUTHOR

President and Chief Executive Officer, CTEC, Inc. Lieutenant Colonel U.S. Army (Retired). MS Nuclear Engineering, Georgia Institute of Technology. BS mathematics, Northeast Louisiana University. Graduate of Command & General Staff College, U.S. Army. Graduate of Guided Missile Staff Officer's Course, U.S. Army (equivalent to MS in Aerospace Engineering). Numerous electronic warfare and counter-countermeasures courses.

Tom is the leading advocate of scalar potential electromagnetics and the Fogal charge-blocking semiconductor. He is involved in alternate energy devices and scalar electromagnetic system prototypes. He has defined charge q as a coupled system of two components, advanced a mechanism for a vacuum engine, whereby the vacuum's virtual particle flux is organized and used to energetically shape and manipulate matter and energy, and advanced a mechanism for a Bohm-type quantum potential, which theoretically allows the engineering of action at a distance in physical systems.

He is president of the Association of Distinguished American Scientists (ADAS), a life member of the Alabama Academy of Science, Emeritus member of the American Association of Physics Teachers, and has served on the Board of Directors of several associations and corporations. Tom is a guitarist, a retired aikidoist (Sandan, Yoseikan style), is happily married and has two sons and two daughters. He and his wife Doris live in Huntsville, Alabama where Tom is retired from aerospace, continues private research, and serves as a consultant to industry on Scalar electromagnetics processes.

REFERENCES

1. *In fact, it simply applies in the laboratory that method that is already used by species for the so-called "directed evolution" component of evolution. The exact mechanisms for directed evolution also arise naturally in the new approach. Directed evolution is required; e.g., no reptilian species could have evolved slowly into a bird. As it started slow changes, it would have not been able to fly or to run, and would have been simply destroyed immediately by*



Next they would selectively irradiate the body with specific signals, frequencies, waveforms, etc. They would begin by using portions of the same frequencies that are being emitted from the body in the "zero reference" environment. They would insure that the returned signal was of higher amplitude than the usual signal being emitted by the body at that same frequency and type.



reptilian species could have evolved slowly into a bird. As it started slow changes, it would have not been able to fly or to run, and would have been simply destroyed immediately by predators. Instead, such evolution occurs in a single jump in a species hard-pressed for a lengthy period. In the evolution of birds, one day every reptile egg that hatched, now hatched into a complete and functional bird with light bones, feathers, etc. A continuing debate (with perhaps more emotion than science) continues to this day on directed evolution. But it is real, and the mechanism can readily be generated (we've already done the gist of it).

EXPLORE! VOLUME 9, NUMBER 3, 1999

2. *Fritz Albert Popp, "Photon Storage in Biological Systems," in Fritz Albert* Popp et al, *eds.*, Electromagnetic Bio-Information: Proceedings of the Symposium, Marburg, Federal Republic of Germany, Sep. 5, 1977; *Urban & Schwarzenberg, Baltimore, 1979, p. 123-149;—"On the coherence of ultraweak photoemission from living tissues,"* in Disequilibrium and Self-Organization, *ed. by C. W. Kilmister, D. Reidel, Hingham, MA, 1986;*—et al., *"Physical aspects of biophotons,"* Experientia, *Vol. 44, 1988, p. 576-585;—"Biophoton emission: New evidence for coherence and DNA as source,"* Cell Biophys., *Vol. 6, 1984, p. 33-52. See particularly Fritz Albert Popp, Ke-hsueh Li, and Qiao Gu, Eds.*, Recent Advances in Biophoton Research and its Applications, *World Scientific Publishing Co., New York, NY, 1992.*
3. *With novel use of EM time-energy to curve spacetime, the physical actions of the "placebo effect" are due to the use of such "spacetime curvature engines" to produce actual physical effects—at least temporarily —in the cells and throughout the body's chemistry, physiology, etc. Experimental detection of these physical effects are well-established in the orthodox medical literature.*
4. *For example, see particularly R. O. Becker, "The direct current field: A primitive control and communication system related to growth processes,"* Proceedings of the. XVI International. Congress of Zoology, *Washington, D.C., Vol. 3, 1963, p. 179-183;— "The direct current control system: A link between environment and organism,"* New York State Journal of Medicine, *Vol. 62, 1962, p. 1169-1176;—and D. G. Murray, "A method for producing cellular dedifferentiation by means of very small electrical currents,"* Trans. N.Y. Acad. Sci., *Vol. 29, 1967, p. 606-615;—and Joseph A. Spadaro, "Electrical stimulation of partial limb regeneration in mammals,"* Bulletin of the New York Academy of Medicine, *Second Series, 48(4), May 1972, p. 627-64.*
5. *E.g., a popular discussion is given by John Travis, "Starting Over: Some Animals can regenerate limbs or even most of their bodies. How?",* Science News, *152(18), Nov. 1, 1997, p. 280-282. For a typical technical paper, see Jeremy P. Brockes, "Amphibian limb regeneration: Rebuilding a complex structure,"* Science, *276(5309), Apr. 4, 1997, p. 81-87.*
6. *I have one viewgraph which lists those 32 major flaws in electrodynamics. Further, leading theorists (Evans, Crowell, and others) in the Alpha Foundation's Institute for Advanced Study (AIAS)—of which I am a Fellow Emeritus by AIAS's kind tolerance—have added about another very technical and very fundamental dozen or so errors to my own list. A leading foundations scientist with over 500 papers in the literature commented dryly to the AIAS that "I broadly agree. that the transverse plane wave view of vacuum electrodynamics is the biggest blunder of twentieth century science. Faraday visualized that "EM disturbances" surrounding wires, magnets, etc. were simply the transverse plucking of taut strings. As he states in his book, Maxwell—who also firmly believed in the material ether—simply captured Faraday's thinking and assumed that transverse "plucked string" wave disturbance in the material ether. At the time all this was expressed, the electron had not been discovered, the atom had not been discovered, the molecule was a featureless blob, and no one had the slightest notion of an atomic nucleus filled with protons and neutrons. Charge was simply a "certain volume of electric fluid" and everything electromagnetic was expressed in fluid dynamics. As an example, that "material fluid" and "material ether" theory was destroyed in the late 1880s by the Michelson-Morley experiment. All the Maxwell equations assume that material ether to this day; not a single equation was ever changed to eliminate the material ether assumptions during the last 110 years.*
7. *For full explanations of the "Moscow Signals," see T. E. Bearden, .,* Gravitobiology: A New Biophysics, *Tesla Book Co., P.O. Box 121873, Chula Vista, CA 91912, 1991;—* AIDS: Biological Warfare, *Tesla Book Co., 1988. For an excellent Government study of the Embassy radiation by excellent but orthodox Johns Hopkins scientists, see A. M. Lilienfeld* et al., Foreign Service Health Status Study: Evaluation of Health Status of Foreign Service and Other Employees from Selected Eastern European Posts, *Department of Epidemiology, of Hygiene and Public Health, The Johns Hopkins University, Baltimore, Maryland, Final Report, July 31, 1978. On p. 245, it is noted that a marked excess of symptoms were noted in the Moscow employee group as compared to other East European employees in other East European nations.*
8. *Johns Hopkins researchers established the exact field patterns present in the Embassy from the microwave carrier radiation; see Robert C. Mallaliew,* A Model of the Microwave Intensity Distribution within the U.S. Embassy, *Moscow 1966 to 1977, Report FS-80-166, Applied Physics Laboratory, Johns Hopkins University, Aug. 1980. Nowhere in any of the Government-funded studies is there any consideration of field-free scalar potentials and their internal time-polarized EM wave structures (the bidirectional phase conjugate wavepairs shown by Whittaker to comprise the scalar potentials). Yet the field radiation patterns surprisingly showed that in just such field-free, persistent potential zones was where 100% of the health changes occurred.*

issue, see "A Comment" by William A. McGarey, p. 143; "A Comment" by Arthur C. Hastings, p. 143-144. See also Vlail Kaznacheyev, "Apparent information transfer between two groups of cells," Psychoenergetic Systems, *1(1), Dec. 1974. The Soviet Union awarded Kaznacheyev a very high medal for his achievements.*

10. *For a very nice summary of EM bioeffects from the more conventional view, see Robert O. Becker and Andrew A. Marino,* Electromagnetism and Life, *State University of New York Press, Albany, 1982. The book is also available at http://www.ortho.lsumc.edu/Faculty/Marino/EL/ELPub.html.*
11. *Andrew A. Marino,* Powerline Electromagnetic Fields and Human Health, *http://www.ortho.lsumc.edu/Faculty/Marino/Marino.html. This book is highly recommended. Particularly see "Chapter 5, Blue-Ribbon Committees and Powerline EMF Health Hazards," and "Chapter 6: Power-Industry Science and Powerline EMF Health Hazards." Biophysicist Marino is one of the leaders in the field and has been personally involved in many skirmishes with powerline-dominated studies and findings.*
12. *E. T. Whittaker, "On the Partial Differential Equations of Mathematical Physics,"* Mathematische Annalen, *Vol. 57, 1903, p. 333-355; — "On an Expression of the Electromagnetic Field Due to Electrons by Means of Two Scalar Potential Functions,"* Proc. Lond. Math. Soc., *Series 2, Vol. 1, 1904, p. 367-372.*
13. *Reali, G. C., "Reflection from dielectric materials,"* American Journal of Physics, *50(12), Dec. 1982, p. 1133-1136. The reflected field from a dielectric material is not generated just at its surface but comes from everywhere in the interior of it.*
14. *Present physics models the EM wave as transporting energy, but erroneously omits that it also transports time. A photon is made of angular momentum, or "energy x time". Since EM waves are made of photons, it follows that they transport both the energy components and the time components making up those photons. An EM wave is a wave of angular momentum, not just a wave of energy.*
15. *KGB energetics weapons scientists call this internal structuring the "information content of the field." However, the Russians use a good deception plan, which implies that the "information content of the field" is just the normal transverse EM spectral content of EM signals. Appreciable "pertinent" work using that phrase is produced by the open Russian scientific community, thus confusing the issue. Our electrodynamicists seem to buy it hook, line, and sinker. The deception plan also tricks Western scientists into thinking that psychoenergetics is nothing but a Russian version of Western parapsychology. Again, our scientists comfortably accept this with smug satisfaction.*
16. *Presently the Russians are in a great new version of this deception plan, with the goal of deceiving Western scientists into thinking that the "secret" Russian energetics is based on torsion fields. Consequently they are releasing substantial material on torsion wave theory, including replicable experimental results. The released version of torsion fields has one glaring omission: the time components and structuring. This deception plan is excellent, because the torsion field theory that is released, is indeed "real" and testable. It is also revolutionary, with respect to present Western science. It almost positively assures diverting the attention of much of the Western science community into this highly limited subset of the full Russian torsion theory—effectively diverting the West away from psychoenergetics and the direct use of t-polarized EM waves and fields, torsion or otherwise.*
17. *We point out that E. T. Whittaker, in "On the Partial Differential Equations of Mathematical Physics,"* Mathematische Annalen, *Vol. 57, 1903, p. 333-355, showed that every scalar potential is comprised of an internal structure of bidirectional longitudinal EM phase conjugate wavepairs in an infinite set of harmonics. Each of those phase conjugate longitudinal EM wavepairs comprises a time-polarized EM wave. So the common potential contains an internal longitudinal EM wave structure that is further organized into an internal time-polarized EM wave structure. The mind-intent correlates and the total mind and emotional experience correlates from fertilization of the egg that led to development of that person, is in the internal substructure of every potential in the living body. In his "On an Expression of the Electromagnetic Field Due to Electrons by Means of Two Scalar Potential Functions,"* Proc. Lond. Math. Soc., *Series 2, Vol. 1, 1904, p. 367-372, Whittaker also showed that any EM field or wave is comprised of two scalar potential functions. It follows from Whittaker and Reali that the EM emissions from the living body carry the internal correlates of everything that has been experienced by that person from conception in the womb. Sometimes this deep embedded "hidden information content" can even be accessed in deep hypnosis. I once observed the deep hypnotic regression of a subject back to her prenatal experiences prior to birth, where the subject relived hearing words of rejection by the father, before the subject was born. The occurrence of the incident and the father's words were directly confirmed on the spot by the mother, who was closely observing the session as it occurred. It turned out that this particular rejection of the baby still in the womb had played a major role in subsequent deep psychological*

scalar potentials). Yet the field radiation patterns surprisingly showed that in just such field-free, persistent potential zones was where 100% of the health changes occurred.

9. *Vlail Kaznacheyev and L. P. Mikhailova,* Ultraweak Radiation in Intercellular Interactions, *[in Russian], Novosibirsk, 1981 [an English exposition of much of the Kaznacheyev work is given in Vlail Kaznacheyev, "Electromagnetic Bioinformation in Intercellular Interactions,"* Psi Research, *1(1), Mar. 1982, p. 47-76.]. See also Vlail Kaznacheyev* et al., *"Distant intercellular interactions in a system of two tissue cultures,"* Psychoenergetic Systems, *1(3), Mar. 1976, p. 141-142. In the same*

observing the session as it occurred. It turned out that this particular rejection of the baby still in the womb had played a major role in subsequent deep psychological problems experienced by that person all her life. To resolve the problem, use of a powerful "simulated" reliving pre-birth experience was conducted with the subject again in the pre-birth state and actively participating, but now with the father figure directly expressing love, acceptance, and cuddling and hugging his daughter. This led to a rather dramatic remission of most of the deep psychological problems within 24 hours.

EXPLORE! VOLUME 9, NUMBER 3, 1999

Mind Control and EM Wave Polarization Transductions, Part 3 of 3

©Copyright 1999 by T.E. Bearden, USA

This outstanding article is the last, Part 3, Part I and 2 of which were published in Volume 9, #2 and #3 of Explore! for the Professional. Because we feel that Col. Bearden's Special Note below is so very important we are repeating its publication in all 3 parts of this article.

Special Note

This article refers to experimental research techniques which can be detrimental or lethal in the hands of any but highly skilled, qualified experimental scientists proceeding under proper laboratory safety procedures. The purpose of this article is strictly for information to properly qualified and authorized scientists in certified laboratories. We do not propose or condone any use of these procedures for nonapproved practice of medicine without a license. Neither the publisher nor the author are responsible for accidents or outcomes in the use of these experimental procedures and techniques. Any researcher who performs these procedures and experiments is acting on his or her own volition, and is solely responsible for insuring safety, qualifications, and legality of the acts and their results. We neither suggest nor condone unauthorized experimentation on human subjects. Such is a criminal violation

achieving many more effects in the targeted bio-organism or groups of them. With Hunt's method, the system as an *open dissipative system far from thermodynamic equilibrium in its environment* is being measured as such. This more directly allows for determination of the environmental inputs on a much broader range of subsystems, both space-like and time-like. Particularly for mental and emotional correlates to environmental stimuli, such measurements and correlations are essential.

More Comprehensive Phenomenology Experiments

To return: Now the scientists would perform many phenomenology experiments, making one little change at a time and profusely recording the data. Each time, they would establish the physical change(s) that occur in the body and/or the mental and emotional changes that occur in the mind for each spectral reinsertion back through the "ship's portholes". They would simply but painstakingly (over some years) build up an extensive database of those individual correlates.

In these experiments, the experimenters will eventually be able to provoke any body or mind change they wish. Strong emotion.

of the constitutional rights of the subject under Federal and State laws, and is both illegal and immoral.

Two Ways to Improve the Methodology and Experimental Correlates

We diverge momentarily: If they wish to improve this methodology, they will consider the body dielectric as a nonlinear isotropic medium. Then they will pretend that the spectrum of *difference frequencies* between each two adjacent waves is the spectrum of "emissions" from the body. They would also use those, as if they were actual emitted spectral signals, instead of the actual signals emitted. That procedure will give superior correlations, but it is more complicated. Part of that is known for underwater sonar,[1] and so our own scientists may or may not have realized it for use in mind and behavior correlate determination with respect to the body dielectric.

Another dramatic improvement in the depth to which the correlates can be constructed, is provided by detecting each porthole output in a two-channel device, where one channel has an adjustable time-delay as utilized by Dr. Valerie Hunt.[2] The two channels—one real-time and one slightly delayed—are then mixed, as by Hunt's method, producing an instrumental measurement of the chaotic part of the functions. Again, this can be measured, recorded, and later analyzed. It adds (i) a completely different kind of thermodynamics in the system measurements, (ii) a dramatically extended set of correlates, (iii) more direct measurement of the time-polarization causative signals, and (iv) an applications Intense pain. Intense pleasure. Painful thoughts. Images. Memories. Perceptions. Dreams. Visions. Memory losses. Memory changes. Personality changes. Etc. The "delta" in the emission spectrum (the changes from zero reference spectrum) represent the precise totality of all mental, physical, organic, chemical, etc. changes and interactions.

A particularly vulnerable aspect of every mammal is the pleasure center in the brain. Experiments have shown that, when this center is stimulated, it is the most addictive experience possible. Rats will forego food, endure electrical shocks, starve, and even die to obtain stimulation of this center. Obviously a device capable of generating signals that evoke direct stimulation of the pleasure center in humans would be a powerful weapon.[3]

Extending the Data Base

See Figure 12. After the researchers have made an "individual porthole signal insertion" correlate database, then they would make a "two, three, four," porthole signal insertion correlate database by inducing selected multiple changes at once. Again they would analyze everything; the program would need one or more supercomputers. It would also require quite a highly qualified multidisciplinary team, extensive facilities, substantial funding, and would be many years in duration. We are describing a decades-long program. But it's a doable.

With sufficient development and performance of such a program, the researchers would have produced (with sufficient testing and analysis, and sufficient retest validation and verification) a database of "specific correlates for a given overall technology eventually having many additional degrees of freedom and therefore capable of

desired physical, mental, or physical and

EXPLORE! VOLUME 9, NUMBER 4 & 5, 1999

mental delta."

A second stage in the research would be to test the correlates and porthole insertions upon a statistically significant cross section of ordinary people, and/or specialized populations (such as toughened soldiers). The program would evolve a highly complex, very effective, ever-improving science and technology of mind and behavior control and engineering mechanisms, complete with finished database and developed applications equipment.

The Dielectric Body as a Ship With Portholes

Again let us review what the EM transverse wave irradiation from the body dielectric represents. Think of the body dielectric as a sort of "ship", with lots of portholes. When it gets irradiated, certain operations happen internally to that radiation, i.e., certain "processes" and "interactions" occur, which change both the mental and physical states. The output emissions back from the body dielectric, out through the filtering "portholes", will directly correlate to what has happened inside the ship.

It is terribly important to realize that one can use the same frequencies and spectra coming back out of those "portholes" to insert EM signals and waves etc. back in there, and into the deepest processes going on in the body and in the mind (at all levels, times. So it will reach directly into and affect any and every part of the dielectric, as you wish, and in whatever manner you have correlates for.

We filed an invention disclosure[4] on the above correlate and "back-porthole" process for use in directly inducing full and efficient conversion directly to time-density (scalar, or time-polarized) EM waves inside the body/ cells, *therefore immediately and directly time-excitation charging the body cells and all their internal components.*

Subtracting the Normal Correlates to Obtain the Deltas

A specifically diseased body, e.g., has a specifically tailored change in its "normal" emission spectra, because of the disease condition alteration of its resident spacetime curvature engine. By having a database for the normal emission spectra of the healthy body, one can subtract it from the actual emitted spectra, to obtain the "delta spectrum".

If the correlates have been previously determined by the above mentioned research program, then one may simply introduce an amplified "delta spectrum" into the body, i.e., through the portholes. This will immediately time-excite the cells and their components throughout the body, particularly where that disease does exist. It turns out that the time-excitation charging by that method will "pump" those diseased including the deep unconscious).

Remember, whatever you put back in there, is going back through the "mixmaster" hopper. It will be iteratively phase conjugated and interfered with by everything, countless cells in the time domain. The cells themselves (and all their parts) are highly nonlinear—to time-excitation charging, they are *totally* nonlinear. So they will act as rather perfect pumped phase conjugate mirrors, but pumped in the time-energy domain rather than in the spatial


RE-RADIATION WITH ALTERATIONS
Alterations Database
Recorders & Broadband Amps
© T. E. BEARDEN 1998
Control Unit
Broadband Antenna Unit
Receiver-transmitters
Adjusting broadband signals bandwidth and amplification by selecting indicated alterations from database
TIME EXCITATION CHARGE IS STRUCTURED TO CONTAIN THE PRECISE SPACETIME CURVATURE ENGINES FOR TIME-REVERSAL AND STEERING. CHARGING OCCURS QUICKLY. ENGINES CONTINUE TO WORK FOR AN EXTENDED PERIOD AFTER CHARGING CEASES.

Figure 12. Using an amplified replica of the body's own dense, broadband signal complex, containing added alterations, to irradiate the body and produce deeply-penetrating precise time-density charging for cellular time-reversal while steering the time-reversal trajectory to also correct a congenital condition.

EXPLORE! VOLUME 9, NUMBER 4 & 5, 1999

energy domain. This is a dramatic extension to nonlinear phase conjugate optics theory.[5]

General relativity tells us that each specific detail of the mass and energy structure of each cell and all its parts—down to the finest details—is accompanied by a precise set of spacetime curvatures. By reintroducing the same energy as the disease delta TW waves, the affected cells add the phase conjugates, converting the inserted TW signals into longitudinal EM wave signals. The longitudinally-pumped cells again phase conjugate, converting these longitudinal EM waves to time-polarized EM waves, and "charging" the cells and all their parts in the time domain.

Suddenly, at that point the *resident spacetime curvature engine*—rather than TW or LW EM waves-serves as the "input signal" to the cell-and-its-parts as pumped phase conjugate mirrors (PCMs), pumped in the time domain. An extension to the distortion correction theorem of nonlinear optics results. An exact, amplified antiengine for the diseased cells—i.e., a phase conjugate replica of the resident spacetime curvature engine—is formed. This amplified antiengine overpowers the resident disease engine, powerfully time-reversing the cells and their components back to a previous healthy state. The time-reversal actually occurs over a period of time after the "time excitation charge-up" ceases, say over the next week or two. Usually two to three quick irradiations are required, one week apart, to give a time-reversing period of three to four weeks.

force upon the cells or any part. E.g., as Pepper[6] states,

"On a more fundamental level, the ideal lossless PCM reverses all the quantum numbers of the incident photon (i. e., linear momentum, angular momentum, etc.). It can be shown that the PCM therefore experiences no linear or angular momentum transfer from the incident photons; hence, the PCM is free from photon radiation pressure and torques."

Note that, in ordinary EM theory, it is precisely translation forces that are engendered upon charged mass by EM fields. This process is quite different. In biological terms, this process dedifferentiates (in physics: time-reverses) the diseased cells and all their components—including the genes—back to an earlier healthy state.

By taking a diseased body and feeding back into it an exact amplified replica of its emitted TW spectrum, one can force the body to "time-excitation charge" all cells and their components immediately, with high efficiency. The human body and every cell and every part of every cell does the necessary "calculation" for the exact antiengine for each part. Since time is extremely condensed spatial EM energy (by a factor of almost 10^{17}), a startling contraction occurs in the radiation time required to time-charge the cells and their components and charged particles. This is a method for instant initiation of time-charging, hence it is extremely rapid. What took Priore several hours of LW irradiation to accomplish in the body,[7] can now be done

Even though appreciable forces are operating internally upon the cells and all their parts, there is no net translation

in seconds with this "thwarting" and spectrum transduction method. In fact, it is an intense stress on the body, and—say—should only


Portable Priore-Type Treatment System
Equipment Case
Computer Control Unit
Infolding Function Generator
Antenna Pad

Figure 13. Portable first-method treatment unit proposed to the Department of Defense. For treating and curing mass casualties from terrorist BW attacks on U.S. population centers.

EXPLORE! VOLUME 9, NUMBER 4 & 5, 1999

be continued for 30 seconds or so. We highly stress that overcharging in this time domain can be detrimental or even lethal if prolonged.

At the end of the very short time-excitation charging time, the body is "time-excitation charged in all its minutest particles". So everything is therefore pumped in the time domain for the next several days after the irradiation is removed, since the time-charge decays very gradually over a period of time. During that decay period, every part of the cell and body acts as a pumped phase conjugate mirror material, pumped in the time domain rather than in the 3-space energy domain. When time-pumped, the mass itself reverses to a previous physical state. This can be used for both nonliving and living masses. Because there is no forcible translation manipulation of the cells and their parts, it can be utilized on living cells in vivo. In the case of diseased cells—e.g., AIDS-it appears that three precisely determined 30-second "AIDS correlate" irradiations a week apart, should be sufficient to completely cure AIDS, including removal of all HIV-genetics changes from every previously infected cell of the body. Also, it would accomplish considerable rejuvenation of the body (making the body younger).

Rejuvenation: Restore the Telomeres and Produce Immortal Cells

Saving Most of the Casualties from Mass Terrorist Attacks

To defend against things like anthrax attacks on our civilian population centers, we also have recommended to the U.S. Government the crash development of small, portable treatment machines—using similar "antiengine-forming" and cellular reversing "porthole technology". [See Figure 13 on previous page]. Such portable machines could be developed cheaply and quickly, and present government facilities could be used to massively attack the correlate database production problem. The portable treatment units could be cranked out by the hundreds of thousands and flooded down through emergency response agencies such as the police forces, the National Guard, emergency hospitals, emergency response teams, etc.

Each device could be used in "assembly line" fashion upon hundreds of sickened patients, in case of a WMD (weapons of mass destruction) attack upon one or more of our cities. The first generation equipment would save probably 70% of the stricken (as from anthrax, etc.). With second generation equipment, one would expect 90% of the stricken casualties could be saved.

Just now, there is a very dim prognosis for all those casualties, using present available treatment capabilities. Time and lack of vaccines defeats just about everything that can be done. Brutally speaking, most of those unfortunate enough to breath in

In fact, it is now known that the gradual loss of the telomeres—the natural ends of chromosomes—in a cell's chromosomes is what causes the cell to age. The gradual loss of the telomeres and the resulting shortening of the chromosomes represents a cellular "disease state" or "disorder" state" accompanied by a precise delta in the spacetime curvature engine accompanying every affected (aging) cell.

By determining the correlate for that precise telomere loss in the aging body's emitted radiation spectrum, an effective telomere regeneration process immediately emerges. One simply amplifies that aging "precise telomere reduction" correlate and reradiates the body with it, passing an amplified correlate back into every cell of the body. The cells and all their parts—including the chromosomes—add *the phase conjugate replicas*, converting the incoming TW EM correlates to longitudinal EM wave correlates. The cells again phase conjugate the LWs and add *the phase conjugate replicas*, converting the LW correlates to time-polarized EM wave pumping correlates. This latter process *time-excitation-charges* the aging cells and all their parts, including the genes and chromosomes. The cellular matter itself produces the amplified "aging antiengine" for each and every cell and telomere ending. The result is to again add telomeres, converting the cell back to a younger, more vigorous cell, and reversing the process of aging.

We point out without further elaboration that these methods also introduce direct engineering signals into the body's master cellular control system, including the regenerative subsystem. Hence the body's regenerative subsystem is involved in helping produce the necessary engines and anthrax spores from an attack, are going to die. At least 80% of them will expire, in spite of everything the present system can do for them.

Note each device could rapidly treat a whole series patients, one right after the other, merely laying them between "blankets" containing wire antennas, irradiating with the proper correlate spectrum quickly, moving on to the next patient, irradiating quickly (seconds), etc. The entire apparatus could be made to fit in a large suitcase-sized container, and it would be highly portable and controlled by a laptop-sized computer.

Unfortunately, so far the DOD doesn't even understand what the heck we're talking about! The National Institute of Health (NIH) and the National Science Foundation (NSF) are not interested at all. After all, it isn't drugs, vaccines, antibiotics, etc. — which are simply not going to do the job. However, those are what the government and scientific communities are going to finance to the tune of hundreds of millions of dollars. They are then going to lose almost all those mass casualties when the terrorist attacks on our population centers inevitably occur.

Those are Americans. They are going to die. Most of them could be saved. We ought to save them.

For any change in state (physical, chemical, emotional, mental, perceptual), the body dielectric "portholes" change and the output spectrum changes. The delta from zero reference now represents that exact change.

Where Western Mind Control Research Has Probably Arrived

Western mind control researchers

operate upon the short telomere chains to add back telomeres. More specifically, the regenerative subsystem is changed into perfect consonance with the external introduction of the amplified antiengines.

That exact process can be used to rejuvenate the aged population and remedy most of the debilities of growing old. That is how we eventually intend to do it, if we can convince the U.S. government and the U.S. scientific community to perform the necessary research and validation.

probably first established a correlation database of porthole emission correlates to changes in internal states, both physical and mental. They almost certainly recognize the peculiar participation of every part of the body dielectric in the TW emission spectrum from the body. They will almost certainly have opted for this "porthole" notion of some similar expression of it, and the "thwarting" of these "relaxation and release" emission processes to engender internal physical changes in the body and in the brain-meat-computer, as they see it.

EXPLORE! VOLUME 9, NUMBERS 4 & 5, 1999

They probably experimented with different TW EM radiation mixes, to see what the body emission change to, and what states are induced. Undoubtedly they found that the induced states began to correlate with the former emission delta data base. That is, they found out which delta emissions spectra, reversed and amplified and fed back thorough the portholes, produce what internal changes.

Use for healing is the simplest of all. Use for killing or debilitating is more complicated. Of course weapons researchers wish to look only at the killing aspects. That is something they understand. They do not understand healing, for they do not even have the "regenerative" or "healing" mechanism in any of the scientific papers or texts. Becker[8] came closest in this country, and Priore did it in France. Both of those scientists were suppressed and paid a bitter price for their revolutionary and innovative research.

But look at what has been done, by "input-output" correlation research. The scientists will have a database now, that tells what state emerges in the body and in the mind, for what irradiation spectra (frequency, relationships, phases, amplitudes, wave shapes, etc.) one uses. And they did not work out all the wave-to-wave transductions ongoing in the mind and body connection and in the body and in the mind, individually, between TWÛLWÛTDW.

We suspect that this is the course Western mind control researchers will have taken, without even realizing the internal wave transductions occurring. And they would not be concerned with that. They would have what they want, for weapons, mind control, and behavior control. And they of the internal "mix" of the dielectric and all its tiniest portions. So Western mind control researchers and rogue groups probably do get good results.

We are not just picking on the U.S. government here! Internal divisive groups exist in all large and powerful groups, and joust for power. In highly classified groups, these groups are greatly enabled to joust more widely, unethically, and immorally because it is so deeply hidden. So very deep classification evokes the growth and intensity of rogue groups. It's the old "Power corrupts, and absolute power corrupts absolutely" routine.

The implication is that in the West one or more highly classified, sustained, heavily funded developments in advanced mind control programs, probably exists and probably has existed for some time. Due to loose formation of rogue groups inside such programs, they may have dual or triple purposes, may not operate under very much legitimate government control at all, and may operate specifically for the purposes of the rogue group or groups that have gained control.

In a nutshell, that's what may be going on in the clandestine mind control projects in several Western governments. The involvement of at least some rogue groups, some being "cowboys" who operate well outside all laws and ethics, could also result in such things as assassinations, clandestine testing on individuals without their consent, etc. In short, *it could account for what seems to be actually occurring*. As also is "usual" in such a mess, one or more of the rogue groups eventually may become very powerful because their secret weapons are very powerful. They may become confident, thinking they have the "best in the would of course ignore the healing aspects. And they would get results of course, revolutionary results. So they would undoubtedly classify the program very highly, thinking that they had the best of the best.

Rogue Groups May Also Have Arisen to Divert the Purpose of the Projects

And that is where real problems may arise. Every human group has within it competing subgroups, jousting for power. The more highly classified the group and its activities, and the less that is known about it outside its confines, the more strongly and secretly the subgroups can play. So they can emerge as **rogue groups** pursuing their own agendas, not that of their duly elected governments. In the extreme, such a deep black program can even become a "captured" program, which is totally in the hands of rogues and no longer reports to or is bound by the dictates of the parent government.

It has long been suspected in some quarters that even the US's highly classified research community may be riddled by such rogue groups, and so may be certain highly sensitive parts of the Research and Development community.

Remember that, in every large and powerful human organization, the basis for rogue groups is power and secrecy. They are always seeking to increase their power, control, influence, prestige, etc. Nothing else. Patriotism and mission are—to rogue groups—often just idle words. They have their own agendas. And being rogue groups, they may well bring in unethical, immoral tricks: assassination, bribery, entrapment, disinformation, plausible deniability, etc. A world." They may actually believe they are ahead of the Russians.

Where the Russians Probably Have Arrived

On the other hand, the Russians will have developed instruments for detecting and isolating the LWs and the scalar waves, in addition to the ordinary mundane instruments for measuring the TWs. So they will have not only the TW correlates, but also the much finer TWÛLWÛTDW (scalar EM wave) correlates. They will understand and employ the use of vacuum engines (spacetime curvature engines) which Western researchers will often invoke but not understand or even be aware that this is what is being invoked. In other words, Western researchers probably just use the old method of "input fi set of functions fi output". That is the standard basis for almost all Western system analysis. With it, one doesn't have to know the exact functions and processes going on in the middle. One just determines a transfer function from a given input to the output that results. Then one catalogs that transfer function. One does that for lots and lots of transfer functions for particularly desirable results, and one has the system analysis. One also has the immediate basis for a rapidly-developed applications technology.

Western scientists are good system analysts. But they have little or no comprehension of what is really going on in that "inside the ship functions" portion, even though they have determined the transform function which acts upon the input to give the "from the portholes" output.

The Russians, with their additional knowledge of the actual mechanisms in the transforms, will be much more advanced certain percentage of a highly secret rogue group will wind up using all these things and more. It's a **human** characteristic, the old primate dominance game. Only now disguised and hidden under deep classification.

Nonetheless, the "simplified" TW EM "porthole correlate" approach will yield very positive results, due to the correlation existing with the LW s and scalar portions than the West, because their fundamental psychoenergetics science is far more advanced, so long as we continue to use the old U(l) electrodynamics. Further, the Russians have decades of use of longitudinal interferometry beams to reach right through the earth and ocean and produce stringent EM effects at a distance. So they will also be able to do the same things here in "mind control" with LW interferometers, through intervening mass

EXPLORE! VOLUME 9, NUMBER 4 & 5, 1999

including the earth and ocean. Western mind-control scientists and their rogue groups—assuming they exist as postulated—largely will not be able to do that, and probably won't even recognize Russian testing of psychoenergetics weapons directly in or over Western nations.

Russian Lethal Psychoenergetics Mind Control Tests Over the U. S.

In fact, the KGB tested just such highly advanced mind control weapons over the middle of the United States in 1997 on two occasions. The tests were conducted against Captain Button in his A-10 "Warthog" aircraft on April 2, 1997 [See Figure 14], and upon Captain Svoboda in her A-10 "Warthog" on May 27, 1997. [See Figure 15].

Over Arizona, Captain Button was thrown into a hypnogogic state, and his perceptions instantly altered and controlled. In his instant "dream-waking" state, everything seemed perfectly normal. His sense of direction was altered a bit more than 90 degrees, so he simply corrected and turned and "flew toward the range", actually flying off course by more than 90 degrees and ignoring radio contacts. He flew right on out of Arizona. At one point he circled, probably thinking he was over the range, and he probably dropped his ordnance there. Then he "flew on back toward home," as he thought in his waking dream state, until his fuel ran out and he crashed and died in the explosion—dream-thinking until he died that everything was normal. All the while, his sense of the passage of time was altered. To him, in his dream-thinking, dream-acting state, everything was normal and nothing untoward had happened. So the distant KGB transmitters and associated psychoenergetics team controlled him for over an hour.

Indeed, that was the exact purpose of the test: demonstrate control (at a great distance) of a skilled person performing highly skilled tasks. A secondary purpose was to stimulate the U.S. government, watch its investigation and findings, and ascertain if the U.S. knew of the extent to which Russian KGB mind control weaponry had advanced. Obligingly, we proved to me KGB that we did not understand what had actually happened to Captain Button.

Captain Svoboda was from the same Wing as Captain Button and was its most experienced night fighter A-10 pilot. In fact, she taught other pilots the fine points of night flying combat missions in the A-10. About two months after Captain Button's bizarre flight and death, Svoboda was engaged in night target bombing on the range. Rising from her ordnance drop on me target, Svoboda was suddenly struck and rendered hypnogogic and in a waking-dream state. Her sense of the vertical was instantly reversed. Superb pilot that she was, she immediately dream-perceived she was diving, not climbing out of the delivery. She instantly corrected to "climb out". So in the real world she dived sharply into the ground and her aircraft exploded.

This test demonstrated the instant alteration of a skilled pilot's perception, causing that pilot to inadvertently react promptly in an unintentionally suicidal manner. A secondary purpose of the test was to stimulate the U.S. government system again, to see if the system recognized what had

A-10 Mysterious Flyaway and Crash

April 2, 1997


UTAH
COLO.
Area enlarged
1:40 p.m.
Vail
1:22 p.m.
Aspden
1:05 p.m.
Telluride
12:53 p.m.
Cortez
ARIZONA
11:58 a.m.
Breaks Formation
near Goldwater Range
12:20 p.m.
Young
NEW MEX
12:11 p.m.
Apache Junction
Barry M. Goldwater
Air Force Range
DEPARTS
10:30 a.m.
Tucson
Tombstone
Eagle
Vail
Glenwood
Springs
COLO.
Hardscrabble
Range
New York
Mountain
Sawatch Range
▪▪▪▪ Flightpath
Aspden

Armed with:

- Four 500-lb bombs
- 30 mm Gatling gun

Figure 14a. Captain Button's mysterious flyaway and eventual crash.

EXPLORE! VOLUME 9, NUMBER 4 & 5, 1999

occurred. Sad to say, it did not and it has not. It was lamely speculated that Svoboda probably looked over her shoulder like a rank greenhorn, and inadvertently dived her aircraft into the ground while looking back at the target. If there was one pilot in the USAF who would have not done that, it was Captain Svoboda. At any rate, the KGB determined that the U.S. scientific, intelligence, and governmental communities did not have the foggiest notion of what had occurred.

In private proprietary communications[9] we have explained further, to proper parties, exactly the reasons for these two tests, and what exactly was being tested, and what is its planned strategic use.

The Final Race for Direct Mind Control of the Entire Human Species

The KGB psychoenergetics weapons scientists—because of their direct measurements and detections (and use) of t-polarized waves and LWs for decades—also understand that Jung's collective unconscious mind (of the entire human species) also has its own time-like operations and correlates, which one measures also when using t-polarization measurements and sorting it all out. The collective unconscious mind operations are buried several levels deeper inside the recursive Whittaker structuring inside the EM fields, waves, and potentials.

The KGB scientists also know that something very like Gaia— a collective unconscious mind for all species on earth—also exists, and they are striving to be able to sort out and measure that one as well. The Gaia operations are buried even deeper in the recursive structuring inside the EM fields, waves, and potentials. If one reads some later books by Kaznacheyev,[10] e.g , this human species unconscious mind aspect and the biosphere unconscious mind aspect emerges loud and clear, if one interpolates between the lines, so to speak. Actually, from day one, the Russian mind control scientists have had their eventual goal set upon this "deeper area of mind and possible mind control" of the entire human species.

I am convinced that the KGB psychoenergetics scientists understand this deeper area. If they can learn to directly engineer the collective human species unconscious, they can then convert the human species easily into a sort of "ant" society, modeled along ideal Communism lines, except of course with an excluded "hierarchy at the top" running everything. The "ant society"—communist style—is still a variation of feudalism (all systems tend to feudalism or some form thereof).

The KGB psychoenergetics weapon scientists are seriously pressing on toward that very goal. In my opinion they are not very far from it right now. It is simply a matter of developing sufficiently complex equipment to be able to directly engineer the time-domain substructuring at sufficiently deep levels. It is a doable, although it is very, very complex and very, very difficult. On the other hand, they have been at it for decades. Even in the 50s the Russians already had the old LIDA device,[11] capable of inducing a catatonic trance-like state in a mammal—either a human or a cat,[12] for example. Some versions of Russian mind control devices were used on Russian soldiers in the


CAPTAIN SVOBODA
DIVES HEADLONG
TO HER DEATH
COMPANION A-10s
© T. E. BEARDEN 1999
CAPTAIN AMY SVOBODA
● Night training mission May 27, 1997
● From same wing as Captain Button
● This was a second psychoenergetics strike

Figure 15. Captain Svoboda dives headlong to her death.

EXPLORE! VOLUME 9, NUMBER 4 & 5, 1999

Afghan War to condition them for performance of merciless acts.[13]

Potential U.S. Rogue Groups and Two Recent Examples

Meanwhile, rogue groups amongst Western clandestine mind control researchers will probably arise if they have not already done so. They will likely seek to increase their personal control and further isolate the programs from orthodox government review and from government and legislative control. They may even divert the research into highly illegal and unethical means, because it furthers their own rogue agendas. That is how clandestine U.S. government research can sometimes go sour, unless great care is exercised by the oversight committees in the House and the Senate.

Sometimes when rogue groups do gain control and total secrecy of a given new technological area, then what appears to be "U.S. government operations" do start to encompass a criminal and unethical operations, hidden usually beneath the deep veil of high classification. Also, if it's "scientific," no one is ever brought to justice, even if the "evil science actions" are uncovered and publicly revealed.

We Certainly Have Proof of Such Rogue Activity. For Example, Here are Two Prominent Cases:

as a result of those ghoulish experiments. So what happened when this gruesome thing was revealed? Again President Clinton publicly apologized! The head of the Executive Branch did not turn the macabre matter over to his Attorney General to prosecute. How many of these scientists were indicted? Not one. How many are going to be indicted? Not one. Suppose again this had been done by a private doctor in his own private clinic. You get the point.

There is Little or No Punishment of Rogue Scientific Groups

Shockingly, the U.S. government at the highest level has directly shown (and these are not all such cases by any means!) that mass crimes against U.S. civilians, *perpetrated by portions of the U.S. scientific community in direct conspiracy and in secret*, will likely be condoned. The perpetrators will not be indicted, tried, or convicted.

Note the connection of the "rogue groups" thesis to the above incidents. Note how rogue **scientific** groups got away with it in both these cases. There may be other rogue

1. For three decades, scientists from the U.S. government, universities, and civilian contractors secretly conspired to treat unsuspecting human patients with whole body nuclear radiation, including some retarded children and cancer patients. Some of those patients—including some of the retarded children—died as a result. These illegal experiments were conducted in great secrecy, and the results were highly classified. Eventually these actions were revealed, and a Presidential investigation committee investigated. These experiments would seem to be little different from the WWII Nazi and Japanese experiments on human prisoners. Are those U.S. scientists who were responsible for those retarded children's' deaths any different from the Nazi scientists and criminals we executed at Nuremberg? So what happened when this terrible thing finally came out into the open? President Clinton publicly apologized! How many of the responsible scientists were indicted for murder? Not one. None is ever going to be.
   Suppose a doctor here in South Alabama, with his own private clinic, had secretly irradiated those human patients and retarded children with whole body nuclear radiation, over a period of 30 years, resulting in some agonizing deaths. How many state and federal agencies would have come after him with arrest warrants? Probably about 50 or so. Would he have been indicted, tried, convicted, and executed or sent to prison for scientific groups getting away with such things today. They should not be able to get away with it. But they can.

Perhaps a most startling additional part of those two incidents is that there was no great public outcry from the scientific community, deploring these murders and demanding that the criminal scientists be indicted and tried.

As the old saying goes, "By their silence they have convicted themselves." The organized scientific community, **as a community**, has shown that it has little or no ethics, and—while deploring any scientific murdering that "gets revealed,"—is not really interested in justice. In short, much of the U.S. scientific community may now have very little ethics left.

We are **not** talking about normal individual scientists, but the Big Science community. There is a whale of a lot of difference between the two. In the Big Science community, there can be and there are rogue groups. Lots of them. There is deep cover, deep classification. And there is very probably advanced mind control research and testing, be it legal or illegal. Hopefully most of it is legal and constrained. However, some of it is almost certain to be illegal and ill constrained.

Human beings are still human beings. All the good and evil is still there, regardless of the group. The stage settings change, but the cast of characters and the play never change.

It's sad, but 'twas ever thus. Hidden parts of our own governments—and other governments throughout the world—are no different from the old medieval groups, where nobles etc. were always plotting against the king, or using the king's power for their own nefarious end. The rogue groups today are no different from all the scheming and conniving groups that life? Absolutely! Would the President of the United States have apologized? Not on your life; he would have turned it over to the U.S. Attorney General with a strong directive to investigate and prosecute on criminal charges.

2. Again for three decades, scientists from (i) the U.S. Government, (ii) universities, and (iii) civilian contractors conspired to give poor syphilitic blacks in Tuskegee, Alabama a placebo while ostensibly treating them for syphilis. The purpose of the program was to deliberately observe and record the ravages of the disease to its fruition in their wracked bodies. So the scientists deliberately sat there and watched their brains rot and their bodies rot. They kept meticulous notes, of course. It was very scientific. And it was macabre. They "treated" some 400 blacks in the "program." Over 100 blacks died

destroyed the Roman Empire. *Great empires fall from within, not usually from without!*

Conclusion

This concludes our brief portrayal of the probable directions that mind control research has taken, in Russia and in the West. It is a novel and powerful area, and it poses both severe dangers and great benefits to all the peoples of the Earth.

Let us hope this great new area, already off to a bad start, can be bridled and steered in the direction of helping and healing people, rather than killing or abusing them. The excesses in its bad use are a potent threat to all nations on earth. Yet it can revolutionize medical science, education, communication, and psychology. Eventually it can engineer the mind and memory directly, beneficially. We foresee the day—perhaps 30 years hence—when education will be

EXPLORE! VOLUME 9, NUMBER 4 & 5, 1999

accomplished *by directly loading the software into the mind.* Then in three weeks one will "load" a doctorate, say, in physics. In three more weeks one will also load a doctorate in chemistry. Another three weeks, in electrical engineering. Another three weeks, an M. D. And so on. When that happens, then truly everyone on earth can be educated. Freedom from ignorance may well be another great freedom that is legally recognized. There will be no impoverished large groups lacking the education to find decent, productive jobs.

We urge all nations to use the principles involved: not for human abuse, but for healing, educating, uplifting, and life-expanding of every person on Earth. If we do, we shall all have a far brighter future. Then we shall check what has started out to

446955, Oct. 23, 1998, forwarded to US. Patent Office on Nov. 4, 1998.

5. A very good introduction to nonlinear phase conjugate optics is given by David M. Pepper, "Nonlinear Optical Phase Conjugation," Optical Engineering, 21(2), March/April 1982, p. 156-183. Also see David M. Pepper, "Applications of Optical Phase Conjugation," Scientific American, 254(1), Jan. 1986, p. 74-83.

6. Pepper, Optical Engineering, ibid., p. 158.

7. See T.E. Bearden, Energetics of Free Energy Systems and Vacuum Engine Therapies, Tara Publishing, Internet node www.tarapublishing.com/books,July 1997. See also T.E. Bearden, "Energetics Update and Summary, " Part I, Explore, 7(6), 1997, p. 60-67, Part II, Explore!, 7(7), 1997, p. 53-56; Part III Explore!, 8(1), I997, p. 53-56; Part IV; Explore!, 8(3), 1997, p. 56-63. See also T.E. Bearden, "Vacuum Engines and Priore’s Methodology: The True Science of Energy-Medicine: Parts I and II " Explore!, 6(1), 1995, p. 66-76; 6(2), 1995, p. 50-62.

8. E.g., see R.O. Becker; Charles H. Bachman, and Howard Friedman, The direct current system: A link between the environment and the organism, " New York State Journal of Medicine, Vol. 62,

be the Sword of Damocles and turn it into the golden Millennium.

We are reminded of a poignant quote from Teilhard de Chardin:

"Someday, after we have mastered the winds, the waves, the tides and gravity, we shall harness for God the energies of love. Then for the second time in the history of the world man will have discovered fire."

May the nations of the world utilize the new mind engineering science to truly free all minds into a common love of, and respect for, their fellow humans of every color, creed, and circumstance. As de Chardin envisioned, may we use the new science to discover a new fire, burning clearer and brighter than anything that has gone before.

♦

ABOUT THE AUTHOR

President and Chief Executive Officer, CTEC, Inc. Lieutenant Colonel US. Army (Retired). MS Nuclear Engineering, Georgia Institute of Technology. BS mathematics, Northeast Louisiana University. Graduate of Command & General Staff College, US. Army. Graduate of Guided Missile Staff Officers Course, U. S. Army (equivalent to MS in Aerospace Engineering). Numerous electronic warfare and counter-countermeasures courses.

Tom is the leading advocate of scalar potential electromagnetics and the Fogal charge-blocking semiconductor: He is involved in alternate energy devices and scalar electromagnetic system prototypes. He has defined charge q as a coupled system of two components, advanced a mechanism for a vacuum engine, whereby the vacuums virtual particle flux is organized and used to energetically shape and manipulate

April 15, 1962, p. 1169-1176. See also R. 0. Becker; "The direct current field: A primitive control and communication system related to growth processes, "Proceedings of the XVI International Congress of Zoology, Washington, D.C., VOL.3, 1963, p. 179-183; —"The neutral semiconduction control system and its interaction with applied electrical current and magnetic fields," Proc. 1lth International. Cong. Radiol., Amsterdam, Excerpta Medica Foundation, 1966, Series 105, p. 1753-1759. See particularly Robert O. Becker and David G. Murray, "The electrical control system regulating fracture healing in amphibians," Clinical Orthopaedics and Related Research, Vol. TBD, No. 73, Nov.-Dec. 1970, p. 169-198.

9. Bearden, T.E., Energetics: Extensions to Physics and Advanced Technology for Medical and Military Applications, CTEC Proprietary, May 1, 1998, 200+ page enclosure to CTEC Letter, "Saving the Lives of mass BW Casualties from Terrorist BW Strikes on US. Population Centers," distributed to selected high U.S. Government agencies and Legislative subcommittees, May. 4, 1998.

10. E. g. , Vlail Petrovich Kaznacheyev, V. I. Vernadsky's Study on Biosphere and NooSphere, 1989 [in Russian]. Vernadskys concepts included living matter, biosphere, and human-transformed biosphere (noosphere). Kaznacheyev writes of evolution and

matter and energy, and advanced a mechanism for a Bohm-type quantum potential, which theoretically allows the engineering of action at a distance in physical systems.

He is president of the Association of Distinguished American Scientists (ADAS), a life member of the Alabama Academy of Science, Emeritus member of the American Association of Physics Teachers, and has served on the Board of Directors of several associations and corporations. Tom is a guitarist, a retired aikidoist (Sandan, Yoseikan style), is happily married and has two sons and two daughters. He and his wife Doris live in Huntsville, Alabama where Tom is retired from aerospace, continues private research, and serves as a consultant to industry on Scalar electromagnetics processes.

R E F E R E N C E S

---

1. Owen Flynn, "Parametric arrays: A new concept for sonar, "Electronic Warfare Magazine, June 1977, p. 107-112.
2. Valerie Hunt, presentation to the U.S. Psychotronics Associations Annual Symposium, Bergamo Center, Ohio, 1988. Hunt presented epochal work showing chaos—and thus hidden order—in recorded ELF electromagnetic radiation from human bodies. Hunt split the received EM signals into two identical channels, time-delayed one channel by a very slight amount, then recombined (mixed) the nondelayed and delayed signals. The result was that attractors precisely indicative of chaos appeared. This positively proves that human systems produce ordered time-

organization of the living matter as the biosphere of the earth. Without specifying the exact technical details, Kaznacheyev discusses the gist of much of what is in this present article. The present author has an autographed copy of Kaznacheyevs book referenced above.

11. Rabichev, Lev Yakovlevich; Vladislav Fedorovich Vasiliev; Alexandr Sergeevich Putilin; Tatyana Grigorievna Ilina; Petr Vasilievich Raku; and Leopold Pavlovich Kernitsky, "apparatus for the treatment of neuropsychic and somatic diseases with heat, light, sound; and VHF electromagnetic radiation," U.S. Patent. No. 3,773,049, Nov. 20, 1973. This is the U. S. patent for the LIDA machine, developed by the Russians prior to the Korean War. Additional patents or applications are as follows: Italy, #619,129, March 1961. Germany, #1,183,607, Dec. 1964. Great Britain, #826,766, Jan. 1960.

12. Stefan T. Possony, "Psy-War: Soviet Device Experiment," Defense & Foreign Affairs Daily, 12(104), June 7, 1983, p. 1-2. Reports on Dr. Ross Adey's investigation of the Soviet device called LIDA which is used to bombard human brains with radio waves in the 40-MHz region. Also reports on work by A.S. Davydov of the Ukrainian Academy of Sciences, who discovered how the blood-brain barrier can be penetrated by low-frequency radio waves so that brain cells are affected. See also "Soviet device uses radio

structuring of EM.

3. Years ago, I read an obscure reference to Russian research directly along that line, with successful development of just such a portable device. Unfortunately I lost the reference in a disastrous flood in my basement and have been unable to recover it.
4. T. E. Bearden, "Alteration of Materials by Wideband Multiwave Irradiation Combined with Selective Emission Manipulation," Invention Disclosure Document Number

waves as tranquilizer, " Associated Press release, Huntsville [Alabama] Times, May 19, 1983. Dr. Ross Adey tested the Soviet LIDA machine on a cat, and in two or three minutes the cat was sitting quietly, almost as though transfixed, and uninterested in its surroundings. The animal remained uninterested in its surroundings for some 20 to 30 minutes after the machine was turned off.

13. "KGB Used PIS to Program Soldiers, "Resonance, No. 30, Mar. 1996, p.29. Quoting: "During the 1970s, the Soviet KGB developed a Psychotronic Influence System (PIS) that was used to turn people into programmable "human weapons." Soldiers fighting in the Afghan conflict were trained using the system which employs a combination of high frequency radio waves and hypnosis. Commands are activated by code words or cyphers. The purpose of PIS was to render regular soldiers and members of the special forces incapable of feeling sympathy.

EXPLORE! VOLUME 9, NUMBER 4 & 5, 1999

The Tom Bearden Website

Latest cloning research findings by Bedini/Bearden

The huge dangers of current cloning technology

Mystery of the death of Australia's cloned sheep explained

"Spark of Life"

From "Stranger than Science"

by Frank Edwards © 1959, 1987

Did an obscure amateur scientist discover the spark of life? Did Andrew Crosse accidentally stumble upon a mixture of chemicals and electricity which produced living things from a lifeless compound? If he did not, then just what did he accomplish? The record of his work is clear, only the enigma of the results remains to plague science.

The neighbors of Andrew Crosse regarded him as more devil than man. They did not understand the bright flashes that lighted his laboratory windows at night when he was tinkering with his crude electrical devices. Not only was he dreaded and shunned as "the thunder and lightning man," but he was denounced as an atheist, a blasphemer, and a Frankenstein who had best be put in chains for the common safety.

Andrew Crosse minded his own business, it is true, but his was a very strange business for the early 1800's. And one of his experiments remains a very strange business to this day.

Andrew was an enthusiastic amateur experimenter in the new field of electricity. Out of touch with others in the same work, he labored under the double handicap of not knowing what had already been done - and of not understanding what he was doing himself. Yet it may have been this very lack of knowledge which led him to undertake the experiments which were to inscribe his name, however faintly, in the annals of science.

He decided to induce the development of artificial crystals by subjecting chemicals to prolonged exposure to weak electrical currents. Andrew mixed up some silicate of potash and hydrochloric acid and into this he dropped a fistsized chunk of oxide of iron. By inducing the current from a small battery to trickle through the solution to the oxide of iron, he hoped to bring about the growth of artificial crystals of silica.

Having arranged this combination of chemicals and current, Andrew set it aside and went back to his favorite pastime of studying the spark-gap - the flashes which alarmed his neighbors.

Did he accidentally stumble upon an arrangement which created life from inorganic matter?

In a paper which he wrote for the London Electrical Society in that same year of 1837, Andrew set down this account of his experience.

He wrote "On the fourteenth day after the commencement of this experiment, I observed through a small magnifying lens a few small whitish specks clustered around the middle of the electrified stone. Four days later these specks had doubled in size and had struck out six or eight fine filaments around each speck . . . the filaments longer than the hemisphere from which they projected.

"On the 26th day of the experiment, the objects assumed the form of perfect insects, standing erect on the bristles which they were growing. Although I regarded this as most unusual I attached no singular significance to it until two days later, the 28th day of the experiment, when the magnifying lens showed that these things were moving their legs. I must say now that I was quite astonished. After a few more days they detached themselves from the stone and moved about through the caustic acid solution.

"In the course of a few weeks more than a hundred of them made their appearance on the oxide of iron. Under a microscope I examined them and found that the smaller ones had six legs, the larger ones had eight. Others who have examined them pronounced them to be of the genus acari, but some say they are an entirely new species.

"I have never ventured an opinion on the cause of their birth for the reason that I have never been able to form one. I thought they might have been airborne creatures that had drifted into the liquid and prospered, but later experiments with closed vessels, in which the ingredients had been purified by baking in the oven, produced identical creatures; therefore, I suggest that they must originate in the electrified liquid by some process unknown to me."

Andrew Crosse realized that he was walking a tightrope before the top scientists of his day. He was describing an experience foreign to their accepted understanding and therefore he was inviting ridicule. He did not have long to wait. Cries of fraud and hoax engulfed him. He and his alleged insects were denounced as nothing more than humbugs.

Amid all the furor that his announcement had created, Crosse stood alone and helpless. Even other scientists who had duplicated his tests with similar results kept their silence.

All but one. That voice was raised in his defense and it was such a powerful voice that none dared challenge it; for it belonged to the great Michael Faraday. At last Crosse had found his champion.

Faraday reported to the Royal Institution that he too had experienced development of these little creatures in the course of his experiments. But he added that he could not decide whether they had been created in the sterile solutions or brought back to life by the electricity! Either development would have constituted a milestone in scientific advance, as Faraday realized, but he left it to his fellow scientists to make the decision, if any.

Crosse never claimed to have discovered anything. He was merely reporting what had happened. After the attacks upon him subsided, he retired to his home in the Quontock hills for many more happy years among his test tubes and batteries.

Although he spent his long life as a humble searcher after scientific truths, the contribution for which he is remembered is the controversy over his acari - unwanted then, and unexplained to this day.



Genus Acari

Tom Bearden comments (finalized and slightly updated in March 2001).

It is difficult to make an understandable comment on the business of life, because presently scientists have not the foggiest notion what mind, being, life, death, time, etc. are. For that matter, they don't really know what matter and energy and charge are either. In the scheme of things, our modern "science" is only about three hundred years old, and that's a snap of the finger in even just the existence of this world. Much of modern science still considers the mind as a "meat computer", or just the physical electrodynamic activity of the brain, etc. Materialism has not died, even though quantum mechanics essentially wiped it out decades ago, and the old concept of "mass" as something hard, permanent, and "material" has also long since vanished. One is referred to the works of Max Jammer to see what the present view of "mass" is. Also, without looking up the references again, recent experiments with quarks and gluons wound up with experiments in which it mattered not a whit whether one considered the mass as zero or nonzero. Nature, it seems, does not have to play by our usual "either-or" rules. In physics, of course, this is the duality problem, which to this day has not been resolved because attempts to resolve it have applied Aristotelian logic -- and there is no solution to the problem of "opposites being identical" in that logic, which forbids that very thing by authoritarianism.

The modern biogenesis experiments, e.g., never took place in the absence of life. There was no "statistical generation of living or quasi-living forms" in the absence of engines for such forms. The great rush of Poynting energy flow around the earth, generally parallel to the equator, alone carries the "engines" (internal sets of spacetime curvatures) for every form of life that ever existed upon the earth. So the experiments were bathed in "living forms and dynamics", if one accounts for the internal Whittaker-structuring of electrodynamics -- noted but ignored by our scientists for nearly 100 years.

Quite some time ago, we worked out the nature of mind, and the mind-matter coupling mechanism (which is engineerable). We did that in pursuit of the mechanisms in the KGB/Russian psychoenergetics weapon work. I had the last of a 3-part article published in "Explore", dealing briefly with mind control technology both the way it is probably done clandestinely in this country and how it is done by the KGB/Russians. I'm still trying to get the proper parties to believe it; not much progress. However, some very neat information has been released on the Internet that very probably reveals why officially there is no interest. It's because three decades ago some of our "spooky folks" found (in deep hypnosis experiments) that humans are inordinately sensitive to extremely low-level EM signals and fields. Even though no detection or sensation may rise to the conscious level, the unconscious (which is totally conscious, just massively parallel rather than serial) does sense these signals. Voila! It would appear that "very deep black" parts of the community probably developed quite good mind influence and mind and behavior control or interference using techniques adapted from that work. The reader must always remember that just because the *overt* government does not know something or have something, does not at all mean that the *covert* government doesn't have it. And even in the covert government, there are layers within layers. So there, even when the upper levels do not have something, it still does not mean that the deeper levels do not have it. The problem with the best knowledge and technology, when unknown to the upper covert levels and the overt level, is that it is then quite likely to be subverted into the deepest levels, which may have their own agendas and may not report to the duly elected U.S. government at all. Indeed, such levels often assume that the President himself does not have a "need to know".

Present physics has erroneously omitted the time increment carried by the photon. The overemphasis on the so-called transverse wave (which does not exist as such in vacuum, fairly readily shown) has led to our missing the greatest and most important part of electrodynamics: the longitudinally polarized EM wave and the time-polarized EM wave. For example, mind and mind operations are totally electromagnetic, but use time-polarized EM waves rather than the standard stuff. Overtly we do not even have detectors for LPWs and TPWs yet; the Russians do. However, every major weapons lab on earth now is aware of longitudinal EM waves and their powerful characteristics. Simply read some of the summary material on Undistorted Progressive Waves (UPWs) on the Los Alamos National Laboratory website, e.g. by Rodrigues et al. A UPW is an "imperfect" longitudinal EM wave with some remaining transverse wave residue (that is the way it is modeled).

Let me give you one example of how fouled we are. We still use Aristotelian logic primarily. Yet it is an incomplete logic. Let me show you instantly. Take the simple Venn diagram of a rectangle lying on its side, divided in half by a vertical line in the middle. Label the right rectangular area A. Label the left rectangular area "not-A". What is the line in the middle and the border? Both A and not-A, so that A is identical to not-A. Yet the third law (law of the excluded middle) forbids A identical to not-A. Apply the third law to the Venn diagram. The border disappears, and the middle dividing line disappears. The logic self-destructs, because now there is no separate A and no separate not-A. Yet so far as I can determine, no one seems to have seen that very simple thing and questioned it. Aristotelian logic cannot be applied to the very Venn diagrams used to establish and "prove by demonstration" its propositions. We corrected that nearly 20 years ago, and got called every kind of lunatic imaginable -- the usual reaction when something fundamentally wrong is pointed out in a comfortable part of the prevailing paradigm. These days I simply point to Morris Kline's "Mathematics: The Loss of Certainty" to the Aristotelians, and tell skeptics to go and read it and then we will discuss the foundations of logic. With a 5-law logic (or 4-law with an additional applications rule), one solves the "dividing line" problem nicely. Then suddenly things like spacetime and being and mind and nothing etc. can be solved -- in the 5-law logic, but never in the 3-law logic. The problem of life itself -- whether terrestrial or extraterrestrial -- has no solution in 3-law logic.

The entire method of Zen is to try to break up the iron Aristotelian bent of the conscious (serial processor) mind, and get into the far broader unconscious (totally conscious, massively parallel processor) mind. Few have done that. But one cannot present a 5-law solution to a 3-law processor; it just "does not compute". It's like putting a thousand slides at once on the normal "single slide at a time" projector. The "conscious mind" can see only a single slide at a time. So it just sees "black" or "nothing at all". That's why we "see" the "massively parallel conscious" mind as "unconscious"! It isn't. But it is a quite different *form* of consciousness which we all have.

Time is never observed, and no observable is a *cause*, a priori, because an observable is only a frozen, nonchanging 3-spatial "instant snapshot" and therefore the *output* of the observation process, while the *causal input* is what exists in 4-space prior to its interaction with the observation process. When one adds time and time dynamics to one's science, one moves far in front of much of present Western physics. E.g., physics has nearly hopelessly confused the *causal* side of the observation mechanism/process with the *effect* side, everywhere, throughout physics -- simply by assuming that observables persist in time -- a non sequitur since an observation is a frozen 3-space snapshot at one single instant.

And sadly, the physicists do not seem to have even realized it!. Not a single paper or text in the West, e.g., illustrates an EM wave in spacetime prior to its interaction with a unit point charge. E.g., simply check a fine editorial by Romer. Romer is the editor of American Journal of Physics, and we are referring to Robert H. Romer, "Heat is not a noun," American Journal of Physics, 69(2), Feb. 2001, p. 107-109; and specifically to his end note #24, p. 109. Romer takes to task *"…that dreadful diagram purporting to show the electric and magnetic fields of a plane wave, as a function of position (and/or time?) that besmirch the pages of almost every introductory book. …it is a horrible diagram. 'Misleading' would be too kind a word; 'wrong' is more accurate." "…perhaps then, for historical interest, [we should] find out how that diagram came to contaminate our literature in the first place."*

But in general physicists continue to charge on, confusing effect as cause. Electrodynamics, e.g., is particularly guilty of greatly confusing the two, which is really what is preventing a successful and engineerable unified field theory. Further, contemporary classical electrodynamicists do not calculate either the field or the potential; instead they calculate the *reaction cross section* of each, interacting with a unit point charge assumed out of nowhere. In short, they calculate how much is diverged from the actual field or potential, and then call that "little extracted part" the field or potential! Again, they mistake the causal entity existing before the interaction with the effect entity existing after the interaction. Well, after the interaction has occurred, that result is the *effect*, not the *cause prior to interaction*. Physics has this so hopelessly snarled that it will require 50 to 100 years before the journals and physics societies are likely to even realize it and admit it, and then it will require them another 50 years to straighten it out and purge this huge non sequitur from physics theory and modeling.

Anyway, we did model how mind and mind operations operate, including their precise nature, how they fit into all this, etc. We thus were able to resolve many previously unsolved riddles such as the nature of intent, how a space-less mind operation can generate a spatial input to a spatial body and vice versa, etc. We also worked out how to use "effects" systems to generate "causal" systems, completely independent of mass -- because the KGB has recently completed a completely different kind of weaponry based on this, and different from anything that has ever existed in the history of mankind (at least on this planet!). The Russians of course were already there; I got there much more crudely by intensely working on how to explain what they were doing.

To see that the effect can generate the cause, just consider the normal "forward time" observation process having to operate in a "time-reversed" process. You see, not only must we shift observers from frame to frame, but we must also be able to shift them from forward-time (of some conveniently chosen outside reference observer) to reversed time (of that same reference observer).

At any rate, it turns out that the entire universe is already "alive" in a very special sense. There is no death; there is mind (I use the term "mind" in the most general sense, not just the conscious mind which is merely a "periscope" put up and taken down from the unconscious). And mind is not a part of the brain, and it is indeed separated from body but intimately linked to it by the mind-body coupling dynamics. Further, any life that has "ever existed" still dynamically exists in a special kind of more fundamental electrodynamics infolded inside all normal EM fields, waves, and potentials. The Tibetans knew much of this very well, but of course in terms that our materialistic science rejects or completely fails to understand (as we stated, most of our scientists believe the human is a robot and the mind is simply the electrochemical reactions of a "meat computer"!).

Since ambient spacetime may be modeled as a special kind of "scalar" potential with intense energy density, it then decomposes into a series of bidirectional EM longitudinal wavepairs, a la Whittaker 1903, except one must use impulse waves so as to include the time dynamics part of spacetime, rather than forcefield 3-space type waves. The entire thing -- mind, life, matter, fields, waves, spacetime, etc. -- then becomes structurable and directly engineerable by novel EM means (such as the O(3) higher symmetry electrodynamics pioneered by Evans and Vigier). Longitudinal EM wave technology is the key to developing such mind-body coupling mechanisms and engineering of them, at all. One only gets the time-polarized EM wave technology *after* the LPW technology has "done its thing" -- the time-polarized technology is far and away the most powerful and primary.

Also, low frequency photons have far more energy than high frequency photons, if one includes the time component, since time is spatial energy compressed by c-squared and has the same energy density as mass. Time-energy (highly compressed spatial energy, compressed by c-squared but in the time domain rather than in 3-space) and spatial energy in the photon are canonical. As the frequency of the photon decreases, its spatial energy decreases also with the decreasing frequency. However, the time-energy component increases, and its compacted energy increases as the square of the time-component expressed in seconds. Hence at lower frequencies the total energy (sum of spatial energy and time energy) in the photon increases. Indeed, if one wishes to engineer gravitational effects, it is the low frequency photons (low ELF) that are important, because they have far and away more "spacetime curving energy" than high frequency photons such as gamma rays.

At least eight nations on earth now have longitudinal EM wave technology weapons to one extent or another. Several of them -- hostile to one another -- are using Western Australia as a convenient nearly uninhabited target range.

Anyway, when you come at the mind-body-life problem with that background (which unfortunately required more than 20 years of very hard work!) there appears to be no great difficulty in explaining the Faraday, Crosse, Fox, Miller, and Urey biogenesis experiments. And yes, there appears to be no difficulty in explaining the "appearance" of "life on earth" in the prebiotic soup. It did not really appear out of nowhere spontaneously at all, but simply was a sort of sympathetic resonant coupling of physical forms to mind-forms already there. None of the experimenters realized that the great Poynting energy flow (and one must add back in the missing Heaviside component which is some 10exp13 times larger than the accounted Poynting flow) around the earth parallel to the equator and from West to East, is already internally structured with every possible form of life ever in the universe anywhere. If we further multiply that Heaviside component by c-squared, so that we can account for the time-energy portion of that great energy flow, we can see immediately that life and its environment are both living and intercommuting all the while. The creator in fact created a living universe, not an inert one (as best we can speak it in the inadequate 3-law logic). If one believes in big bangs, then life structuring emerged right along in all the fields and waves and energy, right in and out of the big bang. There is not a single point in the universe anywhere that is absent of energy and therefore absent of life, in the view of the model I am using.

Understand, one does not have to agree with this model! That is one's own decision. We are just pointing out that, if we correct many of the errors known to be in the presently used models, this is the kind of reality that readily emerges. We get a physics that is not just an "inert" physics, but a living physics where literally the entire universe is "alive" in very special manner.

In deciphering (after 14 years!) the Priore mechanism, I found that incredibly the cellular regenerative system does retain the form and "memory" of all the precessor cellular forms. Cancer, in fact, is very often due to a direct "order" by that system to a cell (aerobic) to start back down the "chain" to an anaerobic cell, because of severe hypoxia and the sustained inability of the regenerative system to maintain the cell in aerobic form. It doesn't just send an "order", but sends a "precise set of spacetime curvature engines" that go to work on that cell and all its parts. The first major step back is to break it loose from centralized control of its growth -- whereupon we recognize it as a tumor cell. There are two requirements: (1) cellular damage, and (2) "promotion". Biologists do not really understand "promotion", because they do not understand the cellular regenerative system—which used time-polarized EM waves, and nonlinear optical pumping of the cell and all its parts in the TIME-energy domain rather than the SPATIAL energy domain. That sort of pumping creates an "antiengine" to its forward time engine resident in the sick cell, thereby time-reversing the cell and all its parts back to a previous state on the trail from the early anaerobic single cells to the present aerobic cells.

By the way, recent experiments in cloning are beginning to bear out the fallacy that exact electrochemical processes produce the same end physical results, particularly when the persistence of the created forms is examined. E.g., cloned rats may live half their lives in apparently normalcy—then suddenly grow greatly obese and die. Many other anomalies are being uncovered in this fashion. The reason is quite simple: We have some diagrams showing that one may introduce an additional "engine" to the pumping of a diseased or damaged cell (or a healthy one for that matter), and in the time-reversal process then induced, the "time-reversal" process will be diverted from the original trajectory. In short, the original full state will not be recovered.


A DRAMATIC EXTENSION TO NONLINEAR OPTICAL PUMPING
© T.E. BEARDEN 1997
VACUUM ENGINE A'
VACUUM ENGINE (A' +B')
VACUUM ENGINE B'
TIME AXIS A
TIME AXIS (A+B)
TIME AXIS B
A 2
MASS
AMPLIFIED VACUUM ANTIENGINE [A' + B']
After adding a second vacuum engine, pumping with longitudinal EM waves (pumping in the time domain) deviates the time-reversed trajectory. The mass and its internal structure are translated into a new form with a new structure, which it need never have had.
VACUUM ENGINE B
VACUUM ENGINE A
A 1
A + B

This, we pointed out, is a second generation technology to be developed, where a disease or disorder must be treated and where also there was never a normal past state anyway. A case in point is birth defects, etc. Eventually, if the technology ever is allowed to be funded and developed, even those kinds of medical conditions will be treatable and curable. The point is that in cloning, one does not use the normal sperm cell and egg, without abnormal disruption. There is indeed an abnormal disruption -- and every such physical action or change and dynamics certainly involves an additional set of engines. In short, with present methods the cloned entity also has introduced into the equation an additional "engine". In the fertilization process, there is quite a jump back to a "time-reversed" situation (fertilization is the beginning of a physical embodiment, hence from two parts of an embodiment already in being, there is a rather dramatic "jump backwards"). The "normal" backwards jump of that kind is a normal fertilization of the egg by the sperm. Any change to that procedure, represents the insertion of an abnormal engine to be processed in that same "jump back". For the methods being used, it appears that the abnormal engines are sufficiently weak that, in the cloned animal, some time must expire in its lifetime before the impact of that little constant deviation from normal grows to become suddenly significant.

Indeed, all "living forms" are materialized from energy, but from both matter-energy and time-energy and the dynamics of the two. Natural processes include fertilization, birth, etc., but there is no technical reason whatsoever that the process cannot be direct and even directly engineerable. In this "expanded energy" sense, mind energy and dynamics can be engineered as well as body matter energy and dynamics.

To cinch the matter of "engineering living forms", I once participated in a accidental and unplanned experiment where Golden materialized living things. Not little bitty things, but big things. In my view we actually materialized thought forms, since much later we were able to piece together exactly what apparently engendered each part of the phenomena. There were multiple (scared) witnesses who prefer never to discuss it. The experiment also altered all the clocks in the area for four days before the "time-energy charge" we had inadvertently created dissipated. Let me just say that it really got my attention! We never repeated that experiment again. But the changes were substantial and the phenomena were substantial, and to this day I prefer not to discuss that experiment. It simply cannot be understood without the outline sketch we are speaking of, where one accounts for time-energy and dynamics as well as material energy and dynamics, and also for the coupling dynamics between the two.

Not only can one have a "material entity" or thing communicating with another "material entity" or thing, but one can also have a "mental thing" (time-domain thing with no spatial existence) communicating with a "material entity or thing" with only spatial existence, and vice versa. There is indeed a coupling two-way mechanism

Look at the so-called "physical form" -- which almost always one is speaking of as purely 3-space. Most scientists have not yet understood that a priori a piece of 3-dimensional mass *as observed* cannot even persist in time! Masstime exists in time, but "mass" is a frozen 3-spatial intersection of the spacetime entity. It is exactly comparable to a frozen frame in a movie film. The individual frame never has any existence except at a frozen moment in the slide projector. "Motion" and "movement" etc. involve the time domain a priori -- hence something without any time-component at all, cannot persist or even exist except at one frozen moment in time. Hence any observable existed in that single "observation slice" and at that "point in time" only. After all, a "point in time" is where time symmetry is broken or ceases. In short, it is a time-discontinuity. All observations are such time-discontinuities.

The SETI problem will not be solved, in my personal opinion (understand, I do not object at all if others do not see it this way) until a far greater and deeper understanding is reached by our modern physics. Forget communicating with "transverse" waves; longitudinal EM waves can travel at any velocity, limited only by how much "residue" of the normal EM wave junk is still hanging in there (how much "transverse EM wave noise" is still present. A pure LW moves at infinite velocity. As we suggested, simply download the Rodrigues and Lu papers carried on the Los Alamos National Laboratory Web site. It appears that now most major weapon labs have "discovered" the fact that there can be longitudinal EM waves, and some eight or so nations have developed weapons technology from such. If one has such technology, all the rest is obsolete.

For the skeptic, here is a statement made in 1997 by Dr. William Cohen, then Secretary of Defense:

> *"Others [terrorists] are engaging even in an eco-type of terrorism whereby they can alter the climate, set off earthquakes, volcanoes remotely through the use of electromagnetic waves… So there are plenty of ingenious minds out there that are at work finding ways in which they can wreak terror upon other nations…It's real, and that's the reason why we have to intensify our [counterterrorism] efforts."*
>
> [Secretary of Defense William Cohen at an April 1997 counterterrorism conference sponsored by former Senator Sam Nunn. Quoted from DoD News Briefing, Secretary of Defense William S. Cohen, Q&A at the Conference on Terrorism, Weapons of Mass Destruction, and U.S. Strategy, University of Georgia, Athens, Apr. 28, 1997.].

Any technological civilization that has not solved the fundamental "self-killer" problem of the technological species, must and will self-destruct. This follows from simple servo-mechanism theory, as we have previously pointed out. The KGB is working on a "solution" that is far along: engineer the entire human species quantum potential so that the human species can be turned into an "antlike" species, which of course would be the "ideal" communist state, in the minds of many Communist party theoreticians. Our guys haven't even got started on engineering the quantum potential yet. They have not yet even discovered the big ball park, let alone the big ball game.

Anyway, that is just some comments for your personal information. What really is happening in the "hidden weapons" area and "hidden weapons science area" is already so advanced in some quarters that science fiction pales by comparison. The real question is whether we shall survive very much longer, and whether we shall mature rapidly enough to begin to use these technologies for the benefit of humanity, rather than for its destruction.

Sincerely,
Tom Bearden

Additional Comments from Tom dated 9 July, 2001

CHENIERE
PRESS

The Tom Bearden Website

Return to Order *Excalibur Briefing*



Help support the research

CHECK ONLINE STORE FOR UPDATES

EXCALIBUR BRIEFING

THE NEUROPHONE

Another device that uses the new hyperspatial, virtual state, nested modulation technology (and has done so for seventeen or eighteen years) is Dr. Pat Flanagan's neurophone. With brilliant insight and intuition far beyond that of science at the time, Pat invented and patented the instrument by the time he was seventeen years old. The neurophone is a device that, contrary to all present theory and knowledge, will directly “pump the brain” and reproduce sound and information directly in the brain and mind system, without going through the auditory system at all. A simplified diagram of Pat's improved neurophone is shown in Figure 11.



Figure 11. A simplified diagram of the improved Flanagan neurophone

Briefly, the device takes a complex signal, such as the sound of an orchestra playing a musical interlude, and electrically processes it as shown in the figure. First the signal is passed into a section that clips everything into a series of square waves, remarkably analogous to the sort of clipped waves Lisitsyn confirms are the information carriers of the human brain. Next the square waves are differentiated, yielding a series of sharp spikes (note that these spikes retain the pulse-time content of the clipped signal). These spikes are again differentiated, and since these are finite spikes with real nonzero rise times and decay times rather than theoretical constructs, a series of noisy spikes results from the second differentiator section. From here, the noisy spikes are introduced to special contact electrodes, one of which is normally placed on the forehead, while the other may be placed almost anywhere, including on the foot. Nowhere are any sound waves introduced to the head.

The square-wave clipper section reduces the complex signals, their overtones, and their complex modulations to square waves, retaining the temporal content of the wave mix but not the waves themselves. The first and second differentiators heighten or filter through the temporal content of the higher-order differentiations, that is, they serve as a band pass filter unit to accent the time keying of the neutrinic and mindfield portions or aspects of the signal. When these time spikes are then introduced across the body as pulsed voltages, they are modulated directly on the dendrite firings of the brain and nervous system, providing direct and pulsed modulation of the neutrinic and mindfield component channels of the mind-brain-consciousness-life loop itself. Thus the neurophone directly inputs information into the brain and nervous system, bypassing all the normal sensory systems that lie between the mind-brain loop and the outside environment.

Indeed, a similar development has been reported by two University of Missouri researchers. Dr. Donald York, a neurophysiologist, and Dr. Thomas Jensen, a speech pathologist, have recently reported identifying and decoding twenty-seven words and syllables in specific brain wave patterns and correlating these electroencephalographic patterns with both the spoken word and the silently thought word in about forty subjects. At present, Dr. York and Dr. Jensen are programming a computer with a brain wave vocabulary, to monitor and read the EEG of a stroke victim's brain and help stroke victims who have lost their powers of speech to communicate.

While all such developments can obviously be misused, their potential for assistance to mankind is enormous. Indeed, my own premise that brain linkage is possible and can be used to advance all mankind to the sixth stage of species evolution is slowly being proven. It is within our reach now to develop a multi-channel communications system that will directly link brains, minds, and consciousness into a single functional being; and I have already pointed out that the psychokinetic power of the emergent entity increases exponentially with the number of linked stages. The normal corpus callosum linkage of the two cerebral halves in each human head proves that brains, minds, and beings can be linked and integrated into one.

The Excalibur Briefing details the basic concepts of the theory involved in hyperspace-virtual state engineering, and thus in the engineering of mind-life-consciousness links to multicellular organisms here on earth. Pat Flanagan's neurophone proves that complex information can be implanted directly in the brain and mind, bypassing the normal isolating barriers. Drs. York and Jensen have shown that the brain wave does indeed contain recognizable, decodable information analogues. Lisitsyn has already reported measuring the number of independent channels involved and has documented the importance of the clipped brain waves as opposed to the sine-wave content. If we have the vision, we can still develop a brainlink and rapidly apply it to link sixty to one hundred persons, thereby opening a conscious, multidimensional “eye” for the collective human unconsciousness, gently rousing ZARG into wakefulness, and fulfilling human destiny without undergoing the psychotronic Armageddon planned by the Soviets. The time is short, but it can still be done if the funding, the vision, and the team can be established on a crash priority basis.

SOVIET “WOODPECKER” SIGNALS

But, as I have said, all this can be used for the detriment of mankind as well as for its benefit. Unfortunately, it appears that the Soviet Union has chosen to weaponize the effects on a global scale. A prime example is the “woodpecker” signals emanating from the USSR in the 5-30 megahertz region and interfering with communications around the earth.

These complex woodpecker signals appear to originate from two or three dozen powerful Soviet transmitters, each with a power estimated as high as 40 megawatts (Figure 12).



Figure 12. The Soviet “woodpecker” signals

The pioneering experimental measurements of these signals by Dr. Robert Beck and William Bise have shown just how deadly a potential may be possessed by the signals. These measurements have been performed in Eugene and Portland, Oregon; Los Angeles, California; Huntsville, Alabama; and several other locations. They have been particularly significant on the West Coast in and around Eugene, Oregon because of the presence of a direct current transmission line several hundred miles long, which has acted as a long wire antenna, picking up the signals and rebroadcasting them with appreciable gain in the vicinity.

Typically the signals may be found on, say, sixteen different carriers between 10 and 20 megahertz. Twelve of the carriers may appear normal, with normal side-bands, and the other four may have the carrier and both sidebands suppressed but still show the biologically significant modulation (for example, 10 hertz). On all sixteen channels a strong 10 hertz modulation may appear, all perfectly time synchronized and in phase channel-to-channel. The received signal from one of these carriers may be twenty-five to thirty times as strong as the earth's back-ground magnetic field, which is oscillating at approximately 7.0 to 7.5 hertz. Other complex modulation frequencies, many of them changing, are present on the various channels.

Normally, the brainwaves of mammals in an area are gently entrained by the normal oscillations of the earth's magnetic field and are oscillating along at, say, 7.5 hertz. Under continuous radiation from the Soviet woodpecker signals, a percentage (say 30 percent) of the mammalian brains may be captured by the 10 hertz modulation on the overpowering Soviet signals. These captured brains are now in forced oscillation and are riding along in phase with the 10 hertz Soviet modulation. In other words, a certain percentage of the human brains in an area will phase lock to the 10 hertz modulation, and that will effectively lock into those brains the sixteen carrier frequencies with their concomitant frequency mixes and complex signal modulations. If the signals are made much more powerful (for example, by focusing them onto one particular area or increasing the power of the transmitters), then a much higher percentage of brainwave entrainment can be accomplished in the targeted area. By simply adding on the desired modulation patterns, the Soviets can now pump material directly into the mind-brain-consciousness-life loops of the entrained brains. The weapon implications are enormous: raw emotion such as sheer terror or panic can be transmitted; death or disease patterns of all kinds can be transmitted; informational content (thoughts and ideas) can be impressed directly into the captured brains and minds and processed as if originating inside each brain itself. Indeed, as long as the Soviets keep the effects rather gentle, an entire population can be subtly influenced without governmental notice. Certain specific ELF frequencies can rapidly disable or even kill, and for wartime use those frequencies can be directly implanted in the captured brains themselves by the woodpecker signals. It appears that 1984 came a little early, and one can perhaps now understand Brezhnev's strange 1975 proposal to the SALT negotiations that we should also consider outlawing the development of new weapons more frightful than the mind of man has ever conceived.

The signals also have direct application against strategic targets other than personnel. For example, by incorporating the correct nested modulation pattern, the positron kindling (electron squelching) pattern can be impressed. By beaming through the earth (with a circularly polarized signal or with other complex modulation forms), a beam with a strong neutrinic component, which will squelch electrons and which will interact with great preference for strong voltages or strong magnetic fields, can be directed at a target complex. In the targeted area aircraft and communications systems can be disabled; automobile, truck, and other ignition systems will fail; power transformers and large motors and generators will fail; power transmission systems with their associated high voltages will fail; and so on. Even independent, self-contained emergency power equipment, such as at military installations and strategic missile sites, will fail to operate. Further, to some of these signals, the earth and the sea are as transparent as glass, and so underwater nuclear submarines can be electrically disabled on station before their missiles can be fired, while strategic missile complexes can be electrically disabled before their deadly nuclear missiles can be hurled toward their distant targets. If some submarines and land complexes succeed in firing missiles before being disabled, these missiles can be electrically dudded and scrubbed from the sky over Soviet territory while still far from their intended targets.

So, as stated at the end of *Excalibur*, the players are on stage and in place. The final act begins. One thing is sure—mankind will never be the same again after seeing the play!

Return to top of page

LASER WEAPON SYSTEMS

TURNING UP THE HEAT WITH SPEED-OF-LIGHT RESPONSE

LOCKHEED MARTIN
We never forget who we're working for®

LASER WEAPON SYSTEMS

Lockheed Martin has specialized in laser weapon system development for 40 years, with advancements in areas such as precision pointing and control, line-of-sight stabilization and adaptive optics – essential functions in harnessing and directing the power of a laser beam – and in compact, robust, spectrally beam-combined fiber laser devices that provide unmatched performance.

Lockheed Martin's directed energy (DE) laser program draws upon our proven expertise across a broad range of capabilities, as well as our spirit of innovation. Our experience includes:

- The beam-control/fire-control system for a megawatt-class laser that destroyed a ballistic missile in flight
- High-power spectrally beam-combined fiber lasers that provide the most efficient conversion of platform prime power into lethal power on target
- Unique SWIR component capabilities that significantly extend the ISR (intelligence, surveillance, and reconnaissance) range of the DE laser system
- Widespread weapons-system and platform integration experience across all DoD services

REVOLUTIONARY TECHNOLOGY

Laser weapons are a revolutionary technology because of the advantages of speed, flexibility, precision and low cost per engagement that are only possible with lasers.

These advantages apply to stand-alone DE laser systems as well as to weapon systems that combine DE and kinetic energy capabilities. In these cases, DE operates as a force multiplier, enabling the warfighter to counter a growing range of emerging threats.

DE weapons are characterized by:

- Very deep magazine
- Extremely low cost per engagement
- Speed of light delivery

These strengths mean that they are well-suited to countering large numbers of inexpensive, highly maneuverable threats that might otherwise exhaust the magazines of our current defensive kinetic energy (KE) weapons. By using DE and KE weapons together, the warfighter will be able to neutralize emerging swarming threats while reserving our most capable kinetic weapons to defend against our adversaries' largest and most hardened threats. DE weapon systems support multi-mission scenarios, and can be readily augmented by communications functions, as well as unprecedented intelligence, surveillance and reconnaissance range, and precision.

In addition, Lockheed Martin's directed energy weapons bring some important and unique advantages to the warfighter:

- A robust and highly-maintainable laser architecture that is designed to minimize life-cycle cost and to maximize up-time
- Output laser power that can be rapidly adjusted between low and maximum power to support disrupt, disable, and destroy capabilities
- Highly parallel laser architecture that supports graceful degradation by eliminating almost all single points of failure



- Highest system efficiency demonstrated in any DE laser system; minimizing size weight and power requirements for DE platforms such as Army and Marine Corps ground vehicles, Navy DDG and LCS ships, and SOCOM AC-130
- Highest lethality laser to minimize engagement time

LOCKHEED MARTIN IS ADVANCING AND DEMONSTRATING A RANGE OF LASER WEAPON SYSTEM TECHNOLOGIES:

ADAM (Area Defense Anti-Munitions)

- Autonomous operations for rocket threats; accepts external sensor cue when required; capable of continuous operation
- Successfully engaged constrained and free-flying rockets, an unmanned aircraft systems (UAS) target in flight, and a small boat
- Affordable commercial-off-the-shelf (COTS) based system with very low cost-per-kill; deep magazine; scalable precision effects
- Capable of close-in defense (1-4 km)

ALADIN (Accelerated Laser Demonstration Initiative)



- 30-kilowatt laser made by combining many fiber lasers into a single, near-perfect-quality beam of light
- Uses approximately 50 percent less electricity than alternative solid-state laser technologies
- Spectral Beam Combining sends beams from multiple fiber laser modules, each with a unique wavelength, into a combiner that forms a single, powerful, high-quality beam

ATHENA (Advanced Test High Energy Asset)

- Represents highest power level documented by a laser weapon system of this type, while retaining excellent beam quality and electrical efficiency
- First field testing of an integrated 30-kilowatt single-mode fiber laser weapon system prototype
- Uses the proven high-energy laser weapon system architecture from our ADAM system, and incorporates the 30-kilowatt ALADIN laser

ABC Turret (Aero-adaptive Aero-optic Beam Control)

- Prototype turret with the ability to fire in any direction mounted on tactical aircraft
- First turret to demonstrate a 360-degree field of regard for laser weapon systems on an aircraft flying near the speed of sound
- Validated performance with nearly 60 flight tests conducted in 2014 and 2015 using a business jet as a low-cost flying test bed

RELI (Robust Electric Laser Initiative) for Army HELMTT (High Energy Laser Mobile Test Truck) Demonstrator



- Modular 60-kW laser in development for the U.S. Army
- Proven affordable weapon architecture that supports size, weight and power constraints for air, sea and land platforms
- Scalable design combines multiple kilowatt lasers to attain various weapon power levels
- Modularity results in a reliable and low maintenance laser system that minimizes single points of failure

WE'RE ENGINEERING A BETTER TOMORROW

Lockheed Martin Corporation
Rotary and Mission Systems
300 M Street, SE
Washington, D.C. 20003
www.lockheedmartin.com/laserweapons

© 2016 Lockheed Martin Corporation

PIRA# OWG201601004

65213

Axial Vircator for Electronic Warfare Applications

Libor DRAŽAN, Roman VRÁNA

Dept. of Radar, University of Defence, Kounicova 65, 662 10 Brno, Czech Republic

libor.drazan@unob.cz, roman.vrana@unob.cz

Abstract. *This paper deals with a high power microwave generator with virtual cathode – vircator in axial release for electronic warfare applications. The classification of directed energy weapons microwave (DEWM) is introduced together with basic block diagrams of a particular class of DEWM. In the paper, methods for designing vircator pulsed power supply, axial vircator structure, measurement methods and experimental results are presented. The vircator in electromagnetic ammunition is powered by magneto-cumulative generator and in weapons for defense of objects (WDO), it is powered by Marx generator. The possible applications of a vircator in the DEWM area are discussed.*

Keywords

Electronic warfare, directed energy weapons microwave, high power microwave, magneto-cumulative generator, Marx generator, pulse forming line, vircator.

1. Introduction

Electronic warfare (EW) is defined as the art and science of preserving the use of the electromagnetic spectrum for friendly use while denying its use to the enemy. Electromagnetic spectrum is, of course, reaching from DC to light (and beyond). Thus, electronic warfare covers the full radio frequency spectrum, the infrared spectrum, the optical spectrum, and the ultraviolet spectrum.

Electronic warfare has classically been divided into:

- Electronic warfare support (ES), which includes the receiving part of EW.
- Electronic attack (EA), which includes jamming, chaff, flares used to interfere with the operation of radars, military communication, and head-seeking weapons. Over the last years, EA also includes antiradiation weapons (ARW) and directed energy weapons (DEW).
- Electronic protection (EP), which is directed into design or operation of radars or communication systems to counter the effect EA.

A detailed classification of EW can be found in [1].

Today the directed energy weapons (DEW) are significant in terms of the electronic attack (EA). Considerable financial resources are directed especially to the research of DEW working in microwave band (directed energy weapons microwave − DEWM), which derive their benefits from incidence of electromagnetic pulses (EMP) on electronic devices. The EMP effect was first observed during the early testing of high altitude airburst nuclear weapons [2]. The effect is characterized by production of a very short (hundreds of nanoseconds) but intense electromagnetic pulse, which propagates away from its source with ever diminishing intensity, governed by the theory of electromagnetism. The EMP is in effect an electromagnetic shock wave. This pulse of energy produces a powerful electromagnetic field, particularly within the vicinity of the weapon burst. The field can be sufficiently strong to produce short lived transient voltages of hundreds of volts to kilovolts on exposed electrical conductors, such as wires or conductive tracks on printed circuit boards.

At present, a high intensity EMP can be successfully generate without using nuclear weapons. This fact is very significant especially for applications in the EW area. It is this aspect of the EMP effect which is of military significance, as it can result in irreversible damage to a wide range of electrical and electronic equipment, particularly computers and radio or radar receivers. Depending on the electromagnetic hardness of the electronics (a measure of the equipment's resilience to this effect) and the intensity of the field produced by the weapon, the equipment can be irreversibly damaged or even electrically destroyed. The damage inflicted is not unlike the damage experienced by exposure to close proximity lightning strikes, and may require complete replacement of the equipment, or at least substantial portions of it [3], [4].

2. Directed Energy Weapons Microwave

Directed energy weapons microwave (DEWM) generate very high-powered electromagnetic impulse (EMP) in the microwave band. From the generated signal bandwidth point of view, there are two classes of generators for the design and construction of DEWM in order to produce electromagnetic field with sufficient power:

- Narrowband – very similar to the radar transmitters; usually generate a modulated harmonic signal. This class is called the high power microwave (HPM).
- Ultra-wideband (UWB) – generates high power videosignal illuminated by a broadband antenna.

The application of directed energy weapons microwave (DEWM) determines their design. There are two groups of directed energy weapons microwave:

- Single shot DEWM,
- Repetitive pulsed power systems.

The electromagnetic weapon modes closely relate to the mission of these weapons. Electromagnetic ammunition usually uses single shot DEWM while weapons for defense of objects (WDO) usually use repetitive pulsed power systems. The typical pulse repetition frequency of DEWM is nearly one thousand pulses per seconds. Recently, there has been a trend of increase in the pulse repetition frequency beyond tens of thousands pulses per seconds. The actual DEWM construction depends on the concrete supposed combat use, on the required measure, range and so on. The following text will be dedicated to experimental verification of some technology usable in narrowband DEWM or HPM. Questions regarding classification, construction and possible use of generators for DEWM are answered in more detail in [4], [5] and [6].

2.1 Basic Block Diagram of DEWM

HPM design depends on the specific assumed application of DEWM. There are difference approaches to the design and realization of electromagnetic ammunition and to the design and realization of weapons for defense of objects (WDO). These differences mostly affect the choice of the power sources and the construction of modulators. In electromagnetic ammunition, a highly limiting factor is the demand for low weight and small proportions. This fact also sharply limits the choice of the power microwave tube.

Electromagnetic ammunition usually uses single shot DEWM. The single shot high-energy high-voltage pulsed source has to fulfill hard requirements on the high amount of the delivered energy with respect to the source volume [MJ/m^3]. The best solution of this requirement is a magneto-cumulative generator that reaches up to 8000 MJ/m^3. A block diagram of a HPM generator in electromagnetic ammunition is shown in Fig. 1.



Fig. 1. Block diagram of a HPM generator in electromagnetic ammunition.

In the block diagram, the primary source feeds the stator coil of a magneto-cumulative generator (MCG), which creates a powerful magnetic field in the surrounding fittings filled with an explosive. At the moment of achieving the primary current peak value, the explosive is shooting. The explosion causes expansion of fitting that performs compression of the magnetic field inside the stator coil of MCG. Compression of magnetic field causes dramatic growth of the current flowing through MCG (hundreds of kiloamperes). The MCG output is connected to a pulse forming network that provides transformation of heavy current to an impulse high voltage (hundreds of kilovolts), which feeds a high power microwave electron tube (HPM ET). The generated microwave is emitted through antenna (ANT) to the space.

A block diagram of a HPM generator in weapons for defense of objects (WDO) is shown in Fig. 2.



Fig. 2. The block diagram of HPM generator in Weapons for Defense of Objects (WDO).

In weapons for defense of objects (WDO), the HPM generator works similarly as the HPM generator in electromagnetic ammunition. Since WDOs usually generate power microwave pulses repetitively, a modulator with this capability has to be used instead of MCG. Modulators with Marx capacitor banks, Tesla transformers or transductors with fast opening switches are used most often. In this class of DEWM, other types of high power microwave electron tubes (HPM ET) are also used. They may generate microwave pulses with high pulse repetition frequency.

3. Energy Sources for Directed Energy Weapons Microwave

The electromagnetic pulse sources for DEWM are entirely based on energy acquired from the chemical energy of explosion that compresses the magnetic flux made by coil (MCG) or by discharging a capacitor bank. These two possibilities are the best solutions for generation of pulses with sufficient amount of energy in a short time. Other methods were used to generate pulses in the beginning of DEWM research or in laboratory.

3.1 Helical Magneto-Cumulative Generator

MCGs are entirely based on the energy acquired from chemical energy of explosion that compresses magnetic flux made by coil. MCG physical principles, classification and applications are described in more detail in [7]. The main part of research was focused on the possibility of using a magneto-cumulative generator for electromagnetic ammunition power supply. For that reason, 4 versions of low power MCGs were designed, realized and tested in order to verify their characteristics, construction principle, explosive initialization method and verifying a measurement method.

The tested magneto-cumulative generator in Fig. 3 consists of an aluminous cylindrical stator, inside is a 16 screw helical coil from 2 mm copper wire, a copper armature tube with 38 mm outer diameter and 4 mm wall thickness filed by octogen (explosive). The explosive is electrically initiated. The load coil represented by a copper strip in shape of a loop connects the stator with the armature. In the right side of stator, there is a crowbar switch made of a brass plate to perform disconnecting of the primary current source. An insulator circle is responsible for separation of the stator and the armature.



Fig. 3. Low power MCG.

Low power magneto-cumulative generator characteristics:

C_1 = 190 μF − primary capacitor capacity
U_0 = 800 V − voltage of capacitor
L_G = 13.1 μH − stator coil inductance
R = 0.0175 Ω − stator coil resistance
T_0 = 3.13 x 10^{-4} s − primary current period
I_m = 2750 A − maximum primary current
T_d = 73 μs − explosive initiation delay

Fig. 4 presents the low power magneto-cumulative generator output current time history calculated from the voltage measured by Rogowski coil. The primary current $I_m = 2750$ A gives the generator peak output current $I_{out} = 27$ kA. The detailed test description and measured results can be found in [8], [9], [10] and [11]. The purpose of the mentioned tests was:

- Verify the method of generating a high energy pulse by magnetic flux compression using explosive;
- Solve the primary current magneto-cumulative generator power supply;
- Find the peak primary current and an explosive initiation synchronization method;
- Find a high current measurement method.

All the requirements were met.

To use a magneto-cumulative generator for single shot high power high voltage pulse generator, it is necessary to obtain a high-level output current. Because of that reason, a middle power MCG was designed and realized. It is a two-stage helical magneto-cumulative generator using a dynamic transformer to increase the output voltage. In Fig. 5, there is a schematic plot of the generator's first stage. The magneto-cumulative generator power supply primary current, the initiation of the explosive and the output high current measure was analogical to the low power magneto-cumulative generator described above.



Fig. 4. Low power magneto-cumulative generator output current time history.



1 – First stage coil, 2 – Load coil, 3 – Armature with explosive, 4 – Insulator

Fig. 5. Schematic drawing of first stage of middle power MCG.

Fig. 6 shows a photo of the middle power magneto-cumulative generator's first stage prepared to the test.

Magneto-cumulative generator characteristics:

C_1 = 125 μF − primary capacitor capacity
U_0 = 5000 V − voltage of capacitor
L_G = 323 μH − stator coil inductance
T_0 = 3x10^{-3} s − primary current period
I_m = 2650 A − maximum primary current value
L_L = 300 nH − load inductance



Fig. 6. The picture of middle power MCG prepared to testing.



Fig. 7. Middle power magneto-cumulative generator output current time history.

In Fig. 7, the generator output current time history measured during test is shown. The primary current $I_m = 2650$ A gave the generator peak output current $I_{out} = 350$ kA.

The next step in the magneto-cumulative generator research is the implementation and verification of a dynamic transformer. The dynamic transformer's role is an increase of the output voltage to about 70 kV. Magneto-cumulative generator's second stage supplies a load coil through an electric breaker. The beaker interrupts the current in the load circuit in a very short time to enable transfer of the energy from the magnetic field to the high voltage pulse. These activities will be done in the next step of the research and development. The further trends are described in [12].

3.2 Pulsed Power Supply With Capacitive Storage of Energy

For some pulse applications in weapons for defense of objects (WDO), it is desirable to couple the Marx generator directly to the vacuum diode; however, the pulse rise time is then limited by the Marx inductance and capacitance, and the impedance of the generator is greater than typically several tens of ohms. In order to produce short, fast-rising, low-impedance beam outputs, it is customary to use the Marx to charge a pulse-forming line (PFL). Although the PFLs may be constructed in a variety of shapes (strip, coaxial, radial, etc.), they are typically used in only two types of circuits— the simple transmission line, and the double, or Blumlein line. In contrast to the simple transmission line, an alternate circuit invented by A. D. Blumlein is capable of producing an output pulse into a matched load that equals the charge voltage. A cylindrical version of the Blumlein circuit fabricated by our team is represented in Fig. 8. It consists of three coaxial cylinders with the intermediate cylinder being charged by the Marx generator. The Marx generator is shown in Fig. 9. The center cylinder is connected to the outer grounded cylinder by an inductor. Ideally the inductor acts as a short during the charge cycle, and then as an open for the short duration of the output pulse [13]. Pulsed power supply parameters are shown in Tab. 1.

Marx generator		Pulse forming line	
Number of stage	n=18	Impedance	9,1 Ω
Capacity of 1stage	100 nF	Length	1 m
Input voltage	U_{in}=25 kV	Pulse duration	60 ns
Output voltage	U_{out}=450 kV	Working medium	water

Tab. 1. Pulsed power supply parameters.



Fig. 8. Cylindrical version of the Blumlein circuit.



Fig. 9. Marx generator.

4. High Power Microwave Generator

A wide range of HPM devices exists. Relativistic klystrons, magnetrons, slow wave devices, reflex triodes and vircators are all examples of the available technology base [5]. From the perspective of an electromagnetic weapon or warhead designer, the device of choice will be the vircator at this time. The vircator is mainly a one shot device capable of producing a very powerful single pulse of radiation, yet it is mechanically simple, small and robust, and can operate over a relatively broad band of microwave frequencies. The physics of the vircator tube are substantially more complex than those of the preceding devices. The fundamental idea behind the vircator is that of accelerating a high current electron beam against a foil or a grid anode. Many electrons will pass through the anode, forming a bubble of space charge behind the anode. Under the proper conditions, this space charge region will oscillate at microwave frequencies. If the space charge region is placed in a resonant cavity which is appropriately tuned, very high peak powers may be achieved. Conventional microwave engineering techniques may then be used to extract the microwave power from the resonant cavity. Because the frequency of oscillation is dependent upon the electron beam parameters, vircators may be tuned or chirped in frequency, where the microwave cavity will support appropriate modes. Power levels achieved in vircator experiments range from 170 kW to 40 GW over frequencies spanning the decimeter and centimeter bands [5].

4.1 Vircator Operation Fundamentals

The basic idea of the vircator is to accelerate a dense flush of an electron beam against a grid or a foil anode. Plenty of electrons pass through the anode and form a region of a space charge behind the anode called ”virtual cathode“. This region of a space charge at corresponding conditions can oscillate in a region of microwave frequencies. It is possible to tune the vircator in a broad band of frequencies using only a change of a space charge density. There is no necessity to have an external magnetic field for a correct vircator function. In Fig. 10, an axial vircator is shown. Electron beam passes through the foil or the grid anode. Microwave power is brought out axially, too. Frequency changes appear in vircator with standard geometry when the distance between the anode and the cathode gets smaller due to filling the working space by plasma. Efficiency of a standard geometry vircator is ordinarily about ones percent.



Fig. 10. Schematic drawing of axial vircator.

Despite its low efficiency, vircator is very attractive for army applications because it is very simple to be made, it is a compact device and there it is no need to have an external magnetic field. For more information about construction and properties of various types of vircators you can see e. g. [5], [13] and [14].

4.2 Mathematical Description of Vircator Operation

For microwave frequency generation, it is necessary to meet a number of conditions relevant to the power supply and geometric proportions of a vircator electrode. Determination of these conditions results from [15] and we use simplified geometry displayed in Fig. 11 to derive the mathematical characterization.

The most common case is that a pulse duration τ is much longer than a beam transit time across cavity $\tau >> L/C$.

We assume that an external axial magnetic field obstructs transverse electron motion. The space charge of the beam makes a negative potential energy $e\Phi$ in drift space which breaks the electrons. If the space charge potential reaches the value of accelerating voltage (electrons are stopped in beam), the beam with bigger current cannot expand. There is a value of current which causes stopping of electrons. This value is called the vacuum critical current. There has to be the above mentioned critical current to make the vircator generate microwave oscillations.



Fig. 11. Simplified geometry of axial vircator.

We suppose a hollow beam; whose charge is concentrated in a thin layer with radius r. Behind the transition space (which is comparable to the radius of chamber – backward conductor), there is nearly homogenous potential. It is possible to determine the potential quantity with consideration that it is a coaxial capacitor and its inner cylinder is saturated by beam charge.

Capacity of the coaxial capacitor is given by

$$C = \frac{2 \cdot \pi \cdot \varepsilon_0}{\lg\left(\frac{R}{r}\right)} \tag{1}$$

where ε_0 is the vacuum electric permittivity, R is the chamber radius, r is the beam radius.

The potential is given by the equation

$$\Phi = \frac{Q}{C} \tag{2}$$

where Q is the charge linear density, C is the capacity per length unit. We can define the charge linear density as

$$Q = \frac{I}{v} \tag{3}$$

where v is an electron module velocity and the current is defined by the equation

$$I = e \cdot n \cdot v \cdot S \tag{4}$$

where e is the charge of an electron, n is the linear electron density, S is the profile of the electron beam.

When (1) and (3) are substituted into (2), we can obtain expression for the potential in the form

$$\Phi = \frac{Q}{C} = \frac{I \cdot \lg\left(\frac{R}{r}\right)}{2 \cdot \pi \cdot \varepsilon_0 \cdot v}. \tag{5}$$

The electron velocity v is associated with its initial energy and potential by the energy preservation law

$$m_e \cdot \gamma_0 \cdot c^2 + e\Phi = m_e \cdot \gamma \cdot c^2 \tag{6}$$

where γ_0 is the initial relativistic factor of the beam, γ is the relativistic factor inside a system reduced due to potential.

The relativistic factor inside a system can be expressed by the equation

$$\gamma = \gamma_0 + \frac{e\Phi}{m_e \cdot c^2} \tag{7}$$

where m_e is the electron mass and c is the speed of light. The relativistic factor can also be expressed by

$$\gamma = \frac{1}{\sqrt{1 - \frac{v^2}{c^2}}} \cdot \tag{8}$$

The electron velocity in drift space v can be specified from following equations:

$$\gamma^2 = \left(\gamma_0 + \frac{e\Phi}{m_e \cdot c^2}\right)^2 , \tag{9}$$

$$v = c \cdot \sqrt{1 - \frac{1}{\left(\gamma_0 - \frac{e\Phi}{m_e \cdot c^2}\right)^2}} \cdot \tag{10}$$

Substituting (10) into (3) and multiplying by $(e \cdot v) / (m \cdot c^3)$, we can get

$$F(\Phi) = \frac{e \cdot \Phi}{m \cdot c^2} \cdot \sqrt{1 - \frac{1}{\left(\gamma_0 - \frac{e\Phi}{m_e \cdot c^2}\right)^2}} = \frac{e \cdot I \cdot \lg\left(\frac{R}{r}\right)}{2 \cdot \pi \cdot \varepsilon_0 \cdot m \cdot c^3} . \tag{11}$$

The function $F(\Phi)$ has its peak value under the conditions describes by

$$\frac{e \cdot \Phi}{m \cdot c^2} = \gamma_0 - \gamma^{\frac{1}{3}} . \tag{12}$$

The evaluation is written in the form

$$F(\Phi) = \sqrt{\left(\gamma^{\frac{2}{3}} - 1\right)^3} = \frac{e \cdot I \cdot \lg\left(\frac{R}{r}\right)}{2 \cdot \pi \cdot \varepsilon_0 \cdot m \cdot c^3} . \tag{13}$$

There is no possibility to find the solution of (11) for bigger values of function $F(\Phi)$. According to (13), the critical vacuum current is

$$I_{cr} = \frac{2 \cdot \pi \cdot \varepsilon_0 \cdot m \cdot c^3}{e \cdot I \cdot \lg\left(\frac{R}{r}\right)} \sqrt{\left(\gamma^{\frac{2}{3}} - 1\right)^3} . \tag{14}$$

When we substitute the known constants (like π = 3.1415), we obtain the equation

$$I_{cr} = \frac{8.5}{\lg\left(\frac{R}{r}\right)} \sqrt{\left(\gamma^{\frac{2}{3}} - 1\right)^3} \tag{15}$$

where I_{cr} is the critical vacuum current [kA].

For vircator implementation, energy of electrons of about 500 keV is considered, which corresponds to the relativistic factor of $\gamma_0 = 2$. Thus planar diode current limited by space charge follows the three-half Child-Langmuir law

$$I \approx \frac{U^{\frac{3}{2}} \cdot S_k}{d_{ka}^{\ 2}} \tag{16}$$

where U is the voltage between anode and cathode, S_k is the surface of cathode, d_{ka} is the distance between anode and cathode.

An important characteristic of a vacuum planar diode is its impedance, which is given by

$$Z = 1.36 \cdot 10^5 \cdot U^{-\frac{1}{2}} \cdot \frac{d_{ka}^2}{r_k^2} \tag{17}$$

where r_k is the radius of the cathode.

The vacuum critical current is the maximal current that can distribute itself through vacuum. It means it is possible to measure the same current until the distance is bigger than the diameter of beam. It is just the same value when the potential of space charge of electron beam is equal to the accelerating voltage. That is the limit where the virtual cathode is generated and the vircator starts working. The generated frequency depends on the plasma frequency of the electron beam. The plasma frequency is determined by the electron beam current density. The plasma frequency is the frequency of electrons in space charge field oscillations. The electrons can oscillate due to the influence of repulsive force which takes effect between particles with the same charge. The plasma frequency depends on the concentration of electrons in the beam. The current density is given by the number of charges which are able to pass through the surface of 1 m^2 per one second. Thus we can calculate the current density i [Am^{-2}]

$$i = e \cdot n_V \cdot c_e \tag{18}$$

where e is the electron charge, n_V is the electron volume density and c_e is the electron velocity.

Plasma frequency of the electron beam is approximately given by

$$f_{pe} = 9 \cdot 10^7 \cdot \sqrt{i} \ . \tag{19}$$

4.3 Axial Vircator Design

Following the theoretical assumptions given above, the axial vircator with grid anode was fabricated. The structure of the grid anode enables repeated operation in contradistinction to vircator with a foil anode. The cathode diameter $r_k = 17.5$ mm and the working chamber radius $R = 40$ mm were chosen in order to decrease the value of the vacuum current. The critical vacuum current is $I_{cr} = 4.63$ kA in this configuration. The vircator impedance matching to the forming line is a very important requirement for vircator's correct operation. Because of that, a cathode with a possibility to change the distance d_{ka} between cathode and anode is fabricated. The cathode is made as a cylindrical carbon block. The anode grid is made from pyrolitic carbon.

In Fig. 12, there is section picture of the built-up axial vircator with the possibility to the change distance between anode and cathode. In Fig. 13, there is a view of the fabricated vircator. The vircator is fed by a pulse generator formed by Marx generator and pulse forming line described in Section 3.2. The connection between the axial vircator and the output of pulse forming line is shown in Fig 14. Vircator voltage is measured by a cylindrical capacitive probe, which is a part of pulse forming line output circuit. Vircator current is measured by Rogowski coil placed in the outer cylinder of the pulse forming line. Vircator voltage time history is displayed in Fig. 15 and vircator current time history is displayed in Fig. 16.

Compared to other types of microwave tubes, the microwaves generated by an axial vircator cover a relatively wide frequency band. In Fig. 17, the frequency spectrum of the signals generated by the realized axial vircator is shown. The dominant frequencies of the generated microwave signals are placed in the band of 0.5 to 1.5 GHz. The frequency spectrum was acquired on the basis of information measured by a digital oscilloscope Tektronix TDS 7704B connected to broadband antenna EMCO 3115. For the measurement the microwave output power of the vircator, a measuring device was designed and made, using calorimetric method for the power measurement. A detailed power sensor description can be found in [18]. A more detailed description the of axial vircator research results is given in [6], [14], [16] and [17].



1 cathode contact ring, *2* ceramic insulator, *3* anode contact ring, *4* pipe for vacuum pumping shelter

Fig. 12. Section picture of built-up axial vircator with possibility to change distance between anode and cathode.



Fig. 13. View of fabricated axial vircator with adjustable distance between anode and cathode.



Fig. 14. View of fabricated axial vircator connected to the pulse forming line.



Fig. 15. Vircator current time history.



Fig. 16. Vircator voltage time history.



Fig. 17. Frequency spectrum of signals generated by realized axial vircator.

5. Conclusion

The research of directed energy weapons microwave validated substantial technology applicable in electromagnetic ammunition and in weapons for defense of objects (WDO). The axial vircator is the most important component part applicable in both categories of DEWM. Dominant frequencies of the generated microwave signal are placed in band of 0.5 to 1.5 GHz. To fulfill the vircator minimal proportion requirements to be able to use the vircator as a DEWM, it is necessary to shift the vircator dominant frequencies to the 3 GHz band. This requirement can be reached by arranging the cathode size efficiently and consequentially optimizing the distance between anode and cathode. Great attention also has to be paid to increase the specific dielectric strength of the output window of the axial vircator.

Acknowledgements

Research of the directed energy weapons microwave substantial technology was realized within the scope of ŽELETON, APPM and GENVLN research projects supported by the Ministry of Defense of Czech Republic.

References

[1] ADAMY, D. *EW101: A First Course in Electronic Warfare*. Norwood: Artech House, 2001.

[2] GLASSTONE, S., DOLAN, P. *The Effect of Nuclear Weapons.* 3rd ed. USA: United States Department of Defence, 1977.

[3] COOP, C. *An Introduction to the Technical and Operational Aspects of the Electromagnetic Bomb.* Canberra: RAAF Air Power Studies Centre Technical Reports, 1996.

[4] TAYLOR, C. D., GIRI, D. V. *High-Power Microwave Systems and Effects*. Washington: Taylor and Francis, 1994.

[5] BARKER, R. J., SCHAMILOGLU, E. *High-Power Microwave Sources and Technologies.* IEEE Press, 2002.

[6] DRAŽAN, L. *The Chosen Problems of Directed Energy Weapons Radio Frequency and Microwave Design.* Inaugural dissertation. Brno: University of Defence, 2008. 144 p. [in Czech].

[7] ALGILBERS, L. L., GRISHNAEV, I., TKACH, Y. *Magnetocumulative Generators.* New York: Springer-Verlag, 2000.

[8] DRAŽAN, L., ZAJONC, J. *Magneto-cumulative generator test results - version G3 and G4 (22.10.2002).* APPM project technical report. Brno: Military Academy, 2002. [in Czech].

[9] DRAŽAN, L., ZAJONC, J. *Magneto-Cumulative Generator Test Results, ver. G3 and G4 (26.11.2002).* APPM project technical report. Brno: Military Academy, 2002. [in Czech].

[10] DRAŽAN, L., ZAJONC, J. *Magneto-Cumulative Generator Test Results – ver. G3 (9.12.2002).* APPM project technical report. Brno: Military Academy, 2002. [in Czech].

[11] DRAŽAN, L., ZAJONC, J. *Magneto-Cumulative Generator Test Results – ver. G3 (7.1.2003).* APPM project technical report. Brno: Military Academy, 2003. [in Czech].

[12] DRAŽAN, L., ZAJONC, J. *Magneto-Cumulative Generator Optimisation Possibility.* APPM project technical report. Brno: Military Academy, 2003. [in Czech].

[13] MILLER, R., B. *An Introduction to the Physics Intense Particle Beams.* New York: Plenum Press, 1982.

[14] BEZDĚK, M., TECL, S., DRAŽAN, L. *Report Concerning the Vircator Research Results.* Research report. Vyškov: VOP-026 Šternberk, 2005. [in Czech].

[15] ŠUNKA, P. *High Power Pulse Generation*. Lectures collection. Prague: Academy of Sciences of the Czech Republic, Institute of Plasma Physics, 2004. [in Czech].

[16] DRAŽAN, L.,ZAJONC, J. *Test of Pulse Forming Line and Design of Microwave Generator with Virtual Cathode.* APPM project technical report. Brno: Military Academy, 2003. [in Czech].

[17] DOSTÁL, F., PLCH, Z. *GENVLN - Measurement.* Technical report. Vyškov: VOP 026 Šternberk, 2008. [in Czech].

[18] DREXLER, P., FIALA, P. Methods for high power EM pulse measurement. *Radioengineering*, 2006, vol. 15, no. 4, p. 43-49.

About Authors…

Libor DRAŽAN was born in Strakonice, Czech Republic, in 1960. He received his Ing. (M.Sc.) and CSc. (Ph.D) degrees from Brno Military Academy in 1984 and 1998, respectively. Since 1990, he has been with the Dept. of Radar at Military Academy and University of Defence in Brno, as an assistant professor (1990 to 2002), head of Dept. (since 2003) and associate professor (since 2008). His research interests include active and passive radar theory, electronic warfare and directed energy weapons microwave.

Roman VRÁNA was born in Havířov, Czech Republic, in 1972. He received his Ing. (M.Sc.) degree from Brno Military Academy in 1995. Since 1999, he has been with the Dept. of Radar, Military Academy and University of Defence in Brno, as an assistant professor (since 2008). His research interests include active radar theory and electronic warfare.

DARPA NESD

INDUSTRY GROUP

The *Biological Technologies Office (BTO)* of the *Defense Advanced Research Projects Agency (DARPA)* is sponsoring an Industry Group to support the *Neural Engineering System Design (NESD) Program*.

NESD is a highly interdisciplinary program requiring extensive integration of new research and technology. To facilitate the development and adoption of NESD technologies, DARPA has organizedan industry group for potential proposers. Members of this group have agreed to provide access to rapid prototyping and manufacturing of advanced neuro-engineering components, including state-of-the-art electronics, photonics, computing, assembly and packaging.

This document contains all responses to **Special Notice 16-17** as of March 10, 2016. Any updates will be posted at **http://www.darpa.mil/work-with-us/opportunities**.



ALLEN INSTITUTE *for*
BRAIN SCIENCE

Allen Institute for Brain Science

Primary Contact

Christof Koch, Ph.D. / christofk@alleninstitute.org

About

The Allen Institute for Brain Science is an independent, non-profit medical research organization that has embarked on a concerted, ten-year effort, involving more than 300 scientists, engineers, technologists and other specialists, to understand the cerebral cortex in the mouse and in the human at the cellular level. We are built upon the notion of Big Science, Team Science and Open Science in the service of Basic Science with an explicit mission to accelerate understanding of the human brain in health and disease. Our data are freely and publicly available at www.brain-map.org.

Capabilities

- We seek to experimentally and computationally characterize the components (cell types) of the rodent visual thalamo-cortical system at the molecular, transcriptional, electron-microscopic, electrophysiological, morphological and functional levels to study how these components integrate information to generate high-level cognitive functioning such as object recognition.
- To study such high-level functioning, we use various in vivo perturbation and monitoring techniques (e.g. optical stimulation, extracellular depth recordings, wide and narrow-field Ca-imaging, etc.), very high density silicon probes (364 probes per shaft) as well as state-of-the art computer models that capture cortical information processing at varying levels of granularity.
- To understand the human brain, the Institute is also engaged in cell typing from human brain tissue harvested from patients undergoing brain surgery.
- Thus, we are routinely recording intracellularly from single and multiple cells from ex vivo human lateral temporal cortex and as well as performing morphological characterization on these same cells).





Capabilities

- We also have extensive experience with the genomic and transcriptional architecture of the human brain.
- We are interested in applying this knowledge for medical and translational purposes and to help facilitate advancement of CNS disorder therapies.

Facilities II

The Allen Institute headquarters, a 270,000 square foot life sciences building, is located in Seattle's South Lake Union neighborhood, the city's biotechnology hub. We are a high-throughput facility, home to custom-designed robotic systems, automated technologies, premier bench laboratory space and all the high-powered computing hardware and software necessary for processing petabytes of data.

Additional Contacts

Erica Sessle, MPH, MPhil / ericas@alleninstitute.org
Jennifer Pawlosky / jenniferp@alleninstitute.org

Bionics Institute

Primary Contact

Rob Shepherd / rshepherd@bionicsinstitute.org

Capabilities

Medical device safety and efficacy testing (in vitro and in vivo)

- Design, rapid prototyping & validation testing
- Accelerated aging & flexion testing
- Electrochemical impedance spectroscopy
- Acute feasibility studies
- Chronic safety and biocompatibility studies
- Drug delivery techniques
- Histology & data analysis
- Scanning electron microscopy of implanted materials
- Preclinical animal model development

Custom device prototyping & fabrication

- Design and fabrication of custom electrode arrays and surgical tools
- Use of FDA approved materials

‘First in human’ clinical trials

Clinical and Scientific Track Record

- 35 years of internationally recognised experience & scientific excellence
- Extensive clinical, academic & commercial partnerships
- Proven research & clinical development pathways

Staff and Facilities

- Experienced and qualified scientists, engineers and clinicians
- Co-located in a major Australian hospital
- Purpose built equipment and facilities

Boston Micromachines Corp

Primary Contact

Paul Bierden / pab@bostonmicromachines.com

About

Boston Micromachines Corporation (BMC) is the leading provider of microelectromechanical systems (MEMS) deformable mirror products and has expertise in the design of adaptive optics systems. The company's suite of award-winning compact DM products is the most cost-effective, highest performance mirrors in the market today. By applying wavefront correction, BMC devices can be used in a variety of applications which include laser beam shaping, microscopy, astronomy, and vision science. Located in Cambridge, MA, BMC is privately held and offers custom-designed manufacturing services in addition to its portfolio of standard DM products and adaptive optics systems.

Capabilities

The specific capabilities/services the company provides in relation to the NESD falls into two categories:

Deformable mirrors systems for use in neurological imaging instruments

- MEMS deformable mirrors ranging in size from 140 – 1000 actuators
- Mirror surface geometries of continuous, segmented, and hexagonal tip-tilt
- High speed drive electronics



These devices are currently being used in in vivo neural imaging systems at various premier research institutions around the country. Boston Micromachines also provides research and development services for advancing the deformable mirror and drive electronics technology and design to better fit specific applications.

- Advanced imaging systems utilizing adaptive optics to improve resolution and contrast in in vivo subsurface imaging application (i.e. deep penetration brain imaging)

Boston Scientific
Advancing science for life™

Boston Scientific

Primary Contact

Rafael Carbunaru / Rafael.Carbunaru@bsci.com

Capabilities

- Lead prototyping
- Firmware modifications to the implantable pulse generators (IPG)
- Software modifications to the computer programmers (CP)
- Use of advanced computational models and predictive algorithms for parameters and programming guidance for neurostimulation

Additional Contacts

- Stephen Carcieri / Stephen.Carcieri@bsci.com
- Hemant Bokil / Hemant.Bokil@bsci.com
- Michael Moffitt / Michael.Moffitt@bsci.com



Chronocam

Primary Contact

Luca Verre / lverre@chronocam.com

Capabilities

- Extensive know-how in designing, developing and industrialising asynchronous, event-based, bio-inspired vision sensors
- Expertise in developing and customising event-based, bio-inspired computer vision algorithms for a large number of applications spanning from autonomous navigation, security and surveillance, aerospace and defence to biomedical devices and smart objects
- System integration capabilities: development of camera systems relying on Chronocam's proprietary vision sensors and development of embedded software porting Chronocam’s proprietary computer vision algorithms on a large number of processing platforms (such as: CPUs, GPUs, FPGA)

Additional Contacts

Christoph Posch / cposch@chronocam.com
Xavier LaGorce / xlagorce@chronocam.com
Thomas Finateau / tfinateu@chronocam.com

Cirtec

Primary Contact

Heather Dunn / Heather.Dunn@cirtecmed.com

About Cirtec

Cirtec Medical has been providing contract design, development, and manufacturing services to the medical device industry since our founding in Massachusetts in 1986. Today, Cirtec has over 150 employees in our two facilities on the east and west coasts.

Cirtec has supported active implantable developers throughout our history. Early projects focused on hermetic welding and testing services for implantable neurostimulation devices, with service offerings expanding to provide full design and development. In all, Cirtec has worked with over 60 different companies and institutions developing active implantable devices, with over 30 in the neuromodulation space. We work with companies and institutions of all sizes, from early stage starts-ups to large, well-established medical device manufacturers. We also work frequently with research laboratories and academic groups; our current projects include development and manufacturing of an implantable neurostimulator used for research and recently approved for clinical study under a feasibility IDE.

Capabilities

Cirtec is ISO 13485 certified and FDA registered.
Cirtec supports the full product development cycle from conceptual development and requirements definition through clinical and commercial manufacturing.





Our engineering teams including mechanical, electrical, and software design resources as well as process development, manufacturing, and quality engineering. Cirtec has a robust and flexible quality system; start-up companies and research groups often choose to work under our quality system rather than developing their own. We provide design history file management and document control services. We can also perform or contribute to requirements documentation, risk management activities, and design verification activities. Our manufacturing capabilities relevant to active implantable devices include:

- Laser welding
- Resistance welding
- Electrical assembly
- Laser marking
- Laser ablation
- Surface treatment
- Ultrasonic cleaning
- Epoxy molding and adhesion
- Silicone molding and adhesion
- Packaging and labelin

Manufacturing capabilities are supported by in-house test capabilities. These include mechanical testing, hermetic leak testing, bench level and automated electrical testing, environmental conditioning, and custom test setups such as soak or pressure testing.

Our manufacturing infrastructure includes multiple ISO class 7 cleanrooms and ESD safe handling procedures for all devices. Cirtec provides complete supply chain management services, leveraging our extensive Approved Supplier List and robust inventory management and material traceability procedures.





VALUE TO PROPOSING TEAMS: There are six primary areas where Cirtec capabilities provide value to proposing teams.

Hermetic barrier development	Hermetic package and barrier design
	Leak specification development
	Internal moisture management: Vacuum bake, desiccant handling, residual gas analysis testing
	Hermetic sealing (welding, brazing) and testing
Electrical assembly	Soldering, wire bonding, and die bonding
	Coil winding
	ESD-safe workspaces
	Lithium battery safe handling procedures
	Bench and automated testing
Interconnect development	Feedthrough design and sourcing
	Hardwired and disconnectable design
	Fabrication and testing
Encapsulation	Epoxy, silicone, and parylene encapsulation
	Layered encapsulation design to manage fluid ingress
	In-house design, tooling, molding, testing
Sterile packaging	Package design
	Pouch and tray packaging and labeling
	Off-the-shelf double sterile tray system
	Sterilization service provider management
Quality system support	Design control support and design history file maintenance
	GMP manufacturing
	Supply chain management
	Procedures for and support of requirements definition, risk management, design verification, and process validation



Dragon ID

Primary Contact

Eugene Malinskiy / eugene@dragonid.com

Capabilities

- Our staff is very experienced working within the complexities of the medical system from observing physicians in the operating room to bringing devices through regulatory approval.
- We have engineers with process development and industrial experience, including interfacing directly with manufacturers.
- We have software engineers experienced in both hardware and software engineering and experience in microcode and embedded systems, end user applications, and high performance computing.
- In addition to engineering talent, we staff researchers, designers, and SMEs to bring a truly interdisciplinary approach to innovation and design for a project.
- We have experience recruiting, establishing, and coordinating relationships between global stakeholders for complex projects to maximize accountability and efficiency for a product while minimizing bureaucracy required.
- We work with our world--class partners in industries such as industrial design, rapid multi--material prototyping, materials selection, and manufacturing in order to round out our capabilities for a product.



Freedom Photonics LLC

Primary Contact

Leif Johansson / leif@freedomphotonics.com

About

Founded in 2005 we are privately held Limited Liability Company based in Santa Barbara, California with ISO Qualification in process, certification in Q2 2016. We develop, manufacture and market complete photonic integrated circuit based products (Indium Phosphide, PLC, Si Photonics).

Our main markets in components, modules and subsystems are for fiber-optic communication, free-Space-optical (FSO) communication and infrared sensors and illuminators.

Capabilities

We offer electronics design, assembly and testing with expertise in photonic design, packaging, control electronics, manufacturing and qualification.

We offer services across development and have a premier R&D compound semiconductor facility with lithography (steppers, DUV stepper, EBL), wet and dry etching, deposition and characterization capabilities.

Our Business Model

Conceptualization, prototyping and development

- Fast R&D turn-around and low cost device fabrication in Nanotech cleanroom facility (Freedom Photonics employees)
- Internal multi-project wafer runs

Volume device production with commercial foundries worldwide

- Fabrication processes designed for manufacturability
- Access to manufacturability and production capacity, qualified processes
- Experience in outsourcing volume device manufacturing

Significant internal capability for assembly, packaging, test





Capabilities and Facilities I – Photonics Design and Fabrication

Design

- Commercial and proprietary tools for passive and active PIC modeling, (Lumerical, native FDTD/BPM code, mode solvers, mask layout, SOA/active region models, Simwindows, SRIM)

Mask layout

- Proprietary scripting tool, with design rule checker and automated mask plate layout

Fabrication

- Full wafer process, die pick-and-place, wedge bonder, ball- bonder, auto-cleaver, pull-tester, etc.

Capabilities and Facilities II – Photonics Production Test

- Photonic device bar level probe
- Chip-on-carrier level (probe card)
- Package; DC, spectral, and data testing
- Burn in – monitored, environmental chambers

Capabilities & Facilities III – Packaging

Several in-house systems with laser welding and UV curing capability.

- Custom tooling, TOSA packages, 14 pin butterflies etc.
- ZEMAX commercial optical train design tool

Capabilities and Facilities IV – Electronics

- Digital and Analog Electronics
- FPGA design and verification tools in house
- Commercial tools for board layout
- Outside foundry for PCB fabrication and stuffing
- Electronics workstations for assembly and test
- Oscilloscopes, sources, multi-meters

We perform contract fabrication and engage with a number of domestic and international fabrication providers, both full process or selected fabrication steps are available.



IMEC

Primary Contact

Barun Dutta / Barundeb.Dutta@imec.be

Capabilities

IMEC is interested in making its comprehensive capabilities available for joint-research programs for solutions in Life Sciences Technologies, Healthcare and Bio-medical engineering, including:

- Semiconductor/nanotechnology
- Process technology
- Design technology and systems/software technologies

Additional Contacts

Maarten Willems / Maarten.Willems@imec.be



Infinite Arthroscopy

Infinite Arthroscopy

Primary Contact

Daniel Dudley / d.dudley@infinitearthro.com

About

We are exclusively focused on developing new medical technologies with an emphasis on translating innovations from other industries to the operating theatre. We have experience in the full life cycle of medical device development from initial conception to regulatory submission. We have large number of rapid prototyping and fabrication techniques available in-house including but not limited to software-based design, stereolithography, fused deposition modelling, PCB milling, and machining. Our staff includes designers, engineers, health care professionals, and subject matter experts from a diversity of industries allowing us to leverage a far wider knowledge base than the standard medical device company. We maintain a nationwide network of leading physicians and institutional partners to develop, refine, and validate our technologies according to contemporary healthcare practice and needs.

Capabilities

Infinite Arthroscopy also maintains a portfolio of intellectual property derived from our medical device technologies that would be available to the NESD Industry Group. Two relevant examples are listed below.





Infinite Arthroscopy, Inc. Proprietary Technologies:

Novel Light Source

- Miniaturized / Ruggedized
- Low power (sub 1 watt)
- Low heat (to LEDs of comparable lumen-output)
- High lumen output
- Long Lifetime (50,000+ hours)
- Emits only target wavelength(s) (Capacity to customize to project needs)

Command/Control Architecture for Medical Devices

- HIPAA/FTC Approved for use in Operating Rooms
- Uninterrupted High-bandwidth capacity
- Transmission below standard RF noise floor
- Encrypted protocol

Additional Contacts

Howard Fein / h.fein@infinitearthro.com

Inscopix

Primary Contact

Pushkar Joshi / pushkar@inscopix.com

Capabilities

- Neuroscience application development and validation (surgical procedures for rodents and non-human primates, application of biological reagents within our own life science lab)
- Optical system development (lens design and simulation, LED light source development, prototyping)
- Hardware system (FPGA-based and/or microcontroller based mixed-signal systems especially involving imaging, mechanical packaging) development, testing, and prototyping
- Software (application, image processing, computer vision, analytical) development and testing
- Mechanical accessories development (design, prototyping via 3D printing)
- With these capabilities, we can customize Inscopix's existing and emerging systems and applications, or develop new systems and applications for or with other proposers in support of this program.

Additional Contacts

Shung Chieh / schieh@inscopix.com

Nanomedical Diagnostics

Primary Contact

Brett Goldsmith / brgoldsmith@nanomedicaldiagnostics.com

Capabilities

- Graphene FET sensor array chips appropriate for integration with nearly any biochemical or electrochemical interaction
- Current sensor hardware capable of measuring biochemical and bioelectric interactions over time with 10 millisecond time resolution, and spatial resolution less than 10 microns
- Capability to produce sensor hardware with time resolution approaching one microsecond with a spatial resolution less than 2 microns
- Expertise in combining electronic materials, packaging and assembly with active biological materials
- Projected FDA clearance for an in vitro clinical product, and associated manufacturing chain, using graphene sensors by mid 2017
- Graphene appropriate for use in medical sensors integrated into an electronic or implantable platform of your choosing
- Chemical and biochemical expertise in biochemical attachment and blocking techniques specialized for boosting specificity of electronic readout of biological interactions
- A complete "turnkey" R&D system for using graphene sensor chips
- Hardware and software appropriate for reading graphene biosensors

Additional Contacts

Francie Barron / fbarron@nanomedicaldiagnostics.com



Naval Research Laboratory

Primary Contact

Dr. Jas. S. Sanghera / sanghera@nrl.navy.mil

About

NRL is the corporate research laboratory for the Navy and Marine Corps and conducts a broad program of scientific research, technology and advanced development.

The Optical Materials and Devices Branch has five primary areas: high purity chemicals, specialty optical materials, silica fiber technology, optical devices and advanced concepts.

Capabilities

We have expertise in the research, development and fabrication of glasses, glass-ceramics, ceramics, crystals, bulk optics, films, waveguides and optical fibers.

We offer a full suite of capabilities to make transparent ceramics to solve the ceramic packaging needs of NESD, some key properties:

- UV to RF transparency tailoring
- Tougher, stronger, harder than glass
- Electrically inert
- Demonstrated conformal shapes
- Demonstrated bonding technologies
- Vertical integration

Our facilities include class 100 clean rooms, powder processing equipment, sintering systems, and characterization capabilities (XRD, SEM, TEM, optics labs, mechanical testing).

Some of our prior applications include: Conformal Optics, IR simulators, photonic mast design, flexible PV’s, IRCM, and Directed Energy Weapons.

Additional Contacts

Shyam Bayya / shyam.bayya@nrl.navy.mil

Star Lab

Primary Contact

Adam Fraser / adam.fraser@starlab.io

About

Star Lab is a high-tech small business focused on complex systems security research and development, with significant expertise and a pedigree of success developing security technologies for safety-critical and mission-critical systems. The company specializes in the areas of high-assurance operating systems, technology protection, applied cryptography, and anti-tamper, and is also a leader in kernel/hypervisor/embedded software development. Star Lab has offices in Washington D.C. and Huntsville, AL.

Additional Contacts

Irby Thompson / irby@starlab.io

Qualcomm

Primary Contact

Karim Arabi / karabi@qti.qualcom.com

Capabilities

- Experience in building an end-to-end platform as a reference design for interface with brain
- Experience in driving an industry wide standard effort to standardize a communication medium and protocol for brain interface
- Advanced low power wireless solutions, RF interface, MODEM system solutions and related electronics for brain interface
- Advanced wireless charging and powering solutions for brain implants
- Ultra low power electronic design solutions at advanced technology nodes suitable for brain implants to enable always on monitoring and processing
- Ultra low power DSP solutions, stream data processing and data compression and decompression solutions

Additional Contacts

Rudy Beraha / rberaha@qti.qualcomm.com



New World War

Revolutionary Methods for Political Control

Mind-Reading

History

Probably no more “intrusive and persistent” method of obtaining information about a person exists than reading their mind.[1] Research on mind-reading has been vigorously pursued by US government agencies and various academic centers since the 1970s, and continues to this day.

Since 1973 DARPA has been studying mind-reading with EEG hooked to computers, using scientists at the University of Illinois, UCLA, Stanford Research Institute, Massachusetts Institute of Technology, and the University of Rochester.

They developed a system that could determine how a person perceived colors or shapes and were working on methods to detect daydreaming, fatigue, and other brain states. Although the device had to be calibrated for each person’s brain by having them think a series of specific thoughts, the calibration was quick.

In 1974 another very basic mind-reading machine was created by researchers at Stanford Research Institute. It used an EEG hooked to a computer which allowed a dot to be moved across a computer screen using thought alone. When interpreting people’s brainwaves, it was right about 60% of the time. During these tests scientists discovered that brain patterns are like fingerprints, each person has their own. So, each computer would have to be calibrated for a specific person.

Another method to address this issue was to store a large amount of generic patterns on the computer, so when it encountered a brain pattern it didn’t recognized, it used one that most resembled it. Since then, DARPA has sponsored Brain-Computer Interface (BCI) and mind-reading programs at Duke University, MIT, University of Florida, and New York State University, Brooklyn.

The Human Computer Interaction group at Tufts University has studied mind-reading funded by grants from a government research and education agency known as the National Science Foundation (NSF). Carnegie Mellon University, Stanford University, and the MIT Sloan School of Management have studied mind-reading. The Computer Laboratory at the University of Cambridge in England has developed mind-reading machines based on facial expressions.

Other academic institutions that have participated in mind-reading projects include the University of California, Berkeley, University of Maryland, and Princeton University in New Jersey. Microsoft has studied mind-reading using EEG to better accommodate its users. Emotiv Systems built a mind-reading gaming device which uses EEG to infer the mental states of video game

Main Menu

Home

Read *New World War* Online

Articles

Solutions

Biography

Download my books for free

Updates

Update: January 20, 2018
A freemasonic death threat....more

Important Updates

All Previous Updates

Donations

Your Donations Are Appreciated

Available Books

PDF, Kindle, & ePub editions of my books can be downloaded for free, or purchased on Amazon & LuLu.

players. Honda Motors and Advanced Telecommunications Research Institute International (ATR) have studied mind-reading.

Neuroimaging Devices

Scientists discovered that the neural code of the human brain is similar to the digital code of a computer. To some extent, they have deciphered this code. Prior to this, they assumed that it was necessary to identify the neurons associated with specific acts, which would have made mind-reading much more difficult.[2]

They now understand that it's not necessary to monitor billions of neurons to determine which are connected to a particular thought or act. Only a small number of them need to be monitored to accomplish this. To monitor these neurons researchers use neuroimaging devices. They include event-related optical signal (EROS), functional magnetic resonance imaging (fMRI), electroencephalography (EEG), functional near-infrared imaging (fNIR), magnetoencephalography (MEG), and positron emission tomography (PET).[3] These devices may be combined for a more accurate reading.

There are basically two types of measurements, *direct* methods and *indirect* methods. Direct methods measure changes in electromagnetic fields and currents around the brain which are emitted from the surface of the scalp, or they monitor the neurons themselves. Indirect methods measure hemodynamic (blood movement) changes of hemoglobin in specific tissue compartments.

Both of these methods are almost simultaneous with neuronal activity. Regarding sensors, there are invasive ones which must be implanted, and non-invasive ones which can be worn on the scalp, in the form of a headband.

Electroencephalography (EEG) provides a direct method for determining brain states and processes by measuring the electrical activity on the scalp produced by the firing of neurons in the brain. EEG has been around for over 100 years. EEG is commonly used in neuroscience, cognitive science, and cognitive psychology. It is inexpensive, silent, non-invasive, portable, and tolerates movement.

Wireless EEG which uses non-invasive sensors that have physical contact with the scalp can transmit the signals to a remote machine for deciphering. Although, in 1976 the *Los Angeles Times* reported that DARPA was working on an EEG to detect brain activity several feet from a person's head, which was to be completed in the 1980s. EEG normally produces only a general indicator of brain activity.

However, in 2008 *Discovery News* reported that a company called Emotiv Systems developed an algorithm that decodes the cortex, providing a more accurate measurement. "We can calibrate the algorithm across a wide range of technologies with the same resolution you would get from placing an invasive chip inside the head," said Tan Le, president of Emotiv Systems.

Functional magnetic resonance imaging (fMRI) measures the blood flow in the brain in response to neural activity. Active neurons use oxygen, which is brought to them by blood. The more active a region of the brain is the more

GEOENGINEERING
PLANETARY
SABOTAGE
&
HUMAN
EXTERMINATION
Mark M. Rich



blood flows in the area. This movement of blood is referred to as *hemodynamic activity*. FMRI can detect which areas are receiving blood, which indicates that they're processing information.

The fMRI provides an indirect measurement of brain processes. It is the most common method of neuroimaging, and can produce 2 and 3-dimensional images. It is non-invasive, and can record signals from all brain regions, unlike EEG which focuses on the surface only.

Functional near-infrared imaging (fNIR) provides an indirect measurement of brain activity by detecting hemodynamic changes in the cortex. Although it is based on different principles, in that it uses light, it functions in the same manner as fMRI. FNIR can provide an almost continuous display of these changes in the cortex. It is inexpensive, non-invasive, and portable. A wireless headband with sensors exists for this device.

Event-related optical signal (EROS) is a brain-scanning device that focuses near-infrared light into the cerebral cortex to detect the density of neurons indicated by the transparency of brain tissue. Because it can only detect these changes a few centimeters deep, it can only image the cerebral cortex. Unlike fNIR, which is an optical method for measuring blood flow, EROS detects the intensity of neurons themselves and provides a direct measurement of brain activity. It is very accurate, portable, inexpensive, and non-invasive. A wireless headband with sensors exists for this device.

Capabilities

Mind-reading can be accomplished by first having a computer learn which brain patterns are associated with specific thoughts, then store the decoded information in a database. This machine learning is accomplished using a type of *artificial intelligence* (AI) called an *algorithm*. A very basic algorithm is a spell checker, which uses a database of common mistakes associated with a particular sequence of letters to present suggestions to a user.

"The new realization is that every thought is associated with a pattern of brain activity," proclaimed neuroscientist John Dylan Haynes, in *Newsweek International* on February 4, 2008. "And," says Haynes, "you can train a computer to recognize the pattern associated with a particular thought."

In a January 2000 issue of *US News and World Report*, Lockheed Martin neuroengineer Dr. John Norseen announced, "Just like you can find one person in a million through fingerprints ... you can find one thought in a million." This can be accomplished using AI and HCI, or what Dr. Norseen calls biofusion.

The decoded brain signals can be stored in a database. Then when someone is scanned, the computer detects the pattern and matches the signals to the database of known meanings. But it's not necessary to scan a brain to decode its signals for every single thought, such as a picture.

Instead, after the machine has learned how to decipher patterns associated with specific thoughts such as images, more images can be added to the program and the computer can use the process it used for the other images as a model to somewhat accurately detect additional thoughts.


The Hidden Evil
The Financial Elite's Covert War Against The Civilian Population
Mark M. Rich


Invisible Eugenics
How The Medical System And Public Schools Are Killing Your Children
Mark M. Rich

New World War: Revolutionary Methods for Political Control

Dedication & Thanks

Peer Review & Thanks

Dedication

Volume I: Current Political Situation

Overview

Introduction

Revolution in Warfare

The Other World

Dictatorship Creation

The Groups Facilitating the Revolution

Their Goal is Neo-Feudalism

Problem-Reaction-Solution

Volume I Commentary

Both words and images can be detected using mind-reading devices with varying degrees of accuracy. This can occur for words and images being viewed by a person on an external display, such as a book, or words and images just being thought of with no external stimuli.

“It is possible to read someone’s mind by remotely measuring their brain activity,” announced *New Scientist* in their *Mind-Reading Machine Knows What You See* article of April of 2005. The Computational Neuroscience Laboratories at the Advanced Telecommunications Research Institute International (ATR) in Kyoto Japan, and Princeton University in New Jersey, proved that by monitoring the visual cortex with fMRI they could determine which basic objects (sets of lines) a person was looking at.

When the objects were combined, they could even determine which one was being focused on. According to the scientists, it may be possible not only to view but also to record and replay these images. They announced that the technology could be used to figure out dreams and other secrets in people’s minds.

Vanderbilt University in Nashville has conducted simple mind-reading tests using an fMRI/Computer, which learned what basic images a group of test subjects was looking at. They were able to predict with 50% accuracy which objects the test subjects were thinking of when they were asked only to remember what they had seen, without being shown the images.

On March 6, 2008 *ABC News* reported that neuroscientists at the University of California at Berkeley accomplished mind-reading by monitoring the visual cortex with an fMRI connected to a self-learning (artificial intelligence) computer program.

First, they used 1750 pictures to build a computational database for the computer to learn with by flashing the pictures in front of test subjects connected to an fMRI. This allowed the algorithm to decipher the brain patterns and associate them with the images.

In addition to deciphering these brain patterns, the computer recorded the process that it used to accomplish this, and built a model based upon it. Then, without scanning the test subjects, they added 120 new pictures to the program and allowed it to create its interpretation of what the new brain signals would be, based on the previous model.

Then they had the test subjects look at these pictures which they had never seen while being scanned. The computer predicted what they were looking at 72% of the time. The scientists announced that the model could be used as a basis to predict the brain activity associated with any image.

What this means is that it’s not necessary to scan a brain to obtain the meaning of each signal. Once the model had been developed, they could simply add new pictures to the database/dictionary. The scientists suggested that out of 1 billion pictures, the computer would be accurate about 20% of the time.

Images which are not consciously seen by a person can even be detected by mind-reading machines. Researchers at University College London flashed

Volume II: The New War

- The New War
- The New Enemy
- Initiatives to Remove Civil Liberties
- The Investigation
- Surveillance Technology and Methods
- Mind-Reading
- Volume II Commentary

Volume III: Weapons of The New War

- Introduction to Nonlethal Weapons
- Psychological Operations
- Introduction to Directed-Energy Weapons
- High-Powered Microwaves
- High-Powered Lasers
- Sonic Weapons
- Computer Network Operations
- Microwave Hearing
- Silent Subliminals
- Use of Citizen Informants
- Chemical and Biological
- Weather Warfare
- Miscellaneous Weapons and Tactics
- Volume III Commentary

Volume IV: The Coverup

- Volume IV Introduction
- Schizophrenia Spectrum Disorders
- Control of the Medical Industry
- Another Look at Schizophrenia
- Political Considerations
- Punitive Psychiatry in Communist Russia
- Coverup Initiatives
- Volume IV Commentary
- Conclusion

Appendix

- A Brief History of PsyOp
- Small-Scale Wars
- Nongovernmental Organizations
- Human-Computer Intelligence Network

pictures in quick succession to test subjects connected to an fMRI. Although some of these pictures were invisible to the subjects, they were accurately recorded 80% of the time by the computer.

Like a fingerprint, each person has their own *brainprint*. Therefore, calibration for each brain is necessary. This is accomplished by having the person think a series of specific thoughts. In the case of EEG, this calibration can take less than a minute. However, because the signals which represent thoughts are similar from one person to the next, a universal mind-reading database has been suggested.

Using fMRI, scientists at Carnegie Mellon University (CMU) discovered that the brain patterns associated with specific thoughts are quite similar among multiple people. This, they stated, would provide the opportunity to create a universal mind-reading dictionary.

Scientists at the University of California at Berkeley mentioned that a "general visual decoder" would have great scientific use. Likewise, the brain patterns associated with specific words that occur when people are reading are also basically the same. This similarity of brain functions associated with words seems to have been an evolutionary development which allowed for an advantage in communication.

A mind-reading machine capable of determining the brain pattern associated with a specific word was developed by scientists at CMU. Brain scans using fMRI were taken of test subjects who were given a variety of words to think of in order to train the computer. An important consideration here is that they were not viewing these words on an external display, only thinking about them. After the computer identified the brain patterns associated with those words, the subjects were given two new words to think about, which the computer accurately determined.

Although, in this particular study only a couple of words were tested, it proves that after a model of how to decipher brain signals was created, AI could accurately determine new words that subjects were thinking about. "These building blocks could be used to predict patterns for any concrete noun," proclaimed Tom Mitchell of the Machine Learning Department.

In February of 2004 *Popular Science* announced that a mind-reading computer could, in theory, translate a person's working verbal memory onto a computer screen. "You could imagine thinking about talking and having it projected into a room 2,000 miles away," says Professor Craig Henriquez at Duke University's Center for Neuroengineering, who has studied mind-reading for DARPA. He added, "It's very, very possible."

FMRI can be used to determine if someone is reading or writing. Neuroscientists can determine when a person is reading by monitoring their brainwaves. They can almost determine exactly what they're reading. And because these patterns are similar from one person to the next, a universal device for determining what people are reading is possible.

In March of 2008 both Technology Review and *ABC News* revealed that an fMRI could in theory be used to display a person's dreams. Then in December of 2008, scientists at ATR in Kyoto Japan announced that they developed a

Electronic Tyranny
Other Devices Connected to the GIG
My Experience

Sources

Other Sites

www.TheHiddenEvil.com
www.RichEssence.com

technology that would eventually allow them to record and replay a person's dreams.

Emotions from love to hate can be recognized by neuralimaging. The level of stress a person is experiencing can also be measured. Brain states such as honesty, deception, and even self deception, can be measured.

Patterns associated with decisions can also be read. Scientists from CMU, Stanford University, and the MIT Sloan School of Management were able to accurately predict the purchasing decisions of test subjects in a virtual shopping center. They monitored the subject's level of interest in a product as well as their decision to purchase it.

Neuroimaging can also detect decisions about how someone will later do a high-level mental activity. Neuroimaging can be used to determine if someone is speaking or reading. It can be used to detect areas of the brain that are active when someone is hearing a sound, or touching an object.

Brain patterns associated with specific physical movements, such as a finger, can be deciphered with neural imaging. The mere intention to make a physical movement can be detected before the actual movement is made.

Cameras

A type of mind-reading is possible with cameras connected to computers. One such device, called the Emotional Social Intelligence Prosthetic (ESP), was developed at the MIT Media Laboratory in 2006. It consists of a tiny camera that can be worn on a hat, an earphone and a small computer that is worn on a belt. It infers a person's emotional state by analyzing combinations of subtle facial movements and gestures.

When an emotional state is detected, the wearer is signaled through the earphone to adjust their behavior in order to gain the attention of the target. The computer can detect 6 emotional states. It can also be adjusted for cultural differences and configured specifically for the wearer.

Around this time, the Computer Laboratory at the University of Cambridge, UK, developed a similar camera-based mind-reading machine. It uses a computer to monitor, in real-time, combinations of head movement, shape, color, smiles, and eyebrow activity to infer a person's emotional state.

It detects basic emotional states such as happiness, sadness, anger, fear, surprise, and disgust, as well as more complex states. It's accurate between 65 and 90 percent of the time. "The mind-reading computer system presents information about your mental state as easily as a keyboard and mouse present text and commands," they announced.

Used for Surveillance

Mind reading exists. The DOD and various institutions have vigorously researched this subject since at least the mid 1970s. "Mapping human brain functions is now routine," declared *US News and World Report*, in an article entitled *Reading Your Mind—And Injecting Smart Thoughts*, of January of 2000.

Both words and images, being viewed or thought, can be mind-read. Various emotional states as well as mental processes such decisionmaking, reading, writing, movement and the intention to make a movement, can be detected with mind-reading devices. Perceptions such as touch, sound, and light can also be detected.

The proposed uses for mind-reading technology are positive. Some include determining if people in comas can communicate, helping stroke patients and those who suffered brain injuries, aiding those with learning disorders, assisting with online shopping, and improving people's communications skills.

However, other uses that have been suggested include the monitoring of unconscious mental processes, and interrogation of criminal suspects and potential terrorists. Dr. John Alexander mentioned that the recent developments in mind-reading technology would take surveillance to new levels by allowing investigators to "peer into the inner sanctum of the mind," in order to determine if a suspect has caused, or will likely cause a crime.

Dr. Norseen has sent R&D plans to the pentagon to have tiny mind-reading devices installed at airports to profile potential terrorists. He suggested that these devices could be functional by 2005. In August of 2008, *CNN* stated that the US military's knowledge obtained from mind-reading research could be used to interrogate the enemy.

Law Enforcement Technology announced in September of 2005 the existence of a new forensic technology known as *Brain Fingerprinting*, which has already been used in hundreds of investigations as a lie detector by the CIA, FBI and law enforcement agencies in the United States.

Brain Fingerprinting is admissible in court, because unlike a polygraph, which relies on emotional responses, it uses EEG to see how the brain reacts to words and pictures related to a crime scene. Dr. Larry Farwell, its inventor, says it is completely accurate. According to the report it will be used to help speed-up investigations.

Sources Next

Endnotes

[1] Another possible method to obtain information is Remote Viewing. RV is the ability to produce correct information about people, events, objects, or concepts that are somewhere else in space and time, and are completely blind to the viewer collecting the information. It can be used to describe people or events, produce leads, reconstruct events, make decisions, and make predictions about the future. See *Remote Viewing Secrets* by Joseph McMoneagle. RV tests were conducted by the US government over a 20-year period during Project Stargate, a classified initiative by the CIA which began in 1972 and lasted until about 1994. Most of the 154 tests and 26,000 trials took place at the Cognitive Sciences Laboratory at Forte Meade, Maryland. A majority of the results of the project are still classified. See the *Journal of Parapsychology* articles, *Remote Viewing by Committee*, September 22, 2003, by Lance Storm and *Experiment One of the SAIC Remote Viewing Program*, of December 1, 1998, by Richard Wiseman and Julie Milton. The success of the project varies depending on the source. Allegedly the original tests were conducted under rigid scientific conditions, which had impressive results. However, the same sources describe RV

in general as ineffective. See *Discover Magazine's* article, *CIA ESP*, on April 1, 1996, by Jeffrey Kluger, and the *Washington Post's* report, *Many Find Remote Viewing a Far Fetch from Science*, on December 2, 1995, by Curt Suplee. According to author McMoneagle, an original viewer during Project Stargate, it is accurate about 50 or 60 percent of the time. Nevertheless, RV will be used to obtain intelligence, according to John B. Alexander. See *The New Mental Battlefield*, which appeared in the December 1980 issue of *Military Review*. Also see the June 1998 *Research Report Number 2* of the University of Bradford's Non-Lethal Weapons Research Project (BNLWRP), for how RV has been added to the NLW arsenal. According to multiple sources, US government agencies are now using the consulting services of RV professionals. This was reported on January 9, 2002 in the *University Wire's (Colorado Daily)* article, *Clairvoyant Discusses Reveals Details of Remote Viewing*, by Wendy Kale, and in the *Bulletin of the Atomic Scientists* on September 1, 1994, in its report, *The Soft Kill Fallacy* by Steven Aftergood. In his book *Winning The War: Advanced Weapons, Strategies, and Concepts for the Post-911 World*, Alexander had this to say regarding RV: "Since the beginning of history, humans have made anecdotal references to innate abilities to foretell the future, to know what was occurring at distant locations or the status of people separated from them, and to find resources they need without any traditional means of accessing that information." He continued: "Studies have demonstrated beyond any doubt that these nontraditional capabilities exist. ... [RV can] radically change our means of gathering intelligence. It holds the promise of providing information about inaccessible redoubts and advances in technology. More importantly, once these skills are understood, those possessing them will be able to determine an adversary's intent and be predictive about the events."

[2] Because neuroimaging technology decodes brain patterns to thoughts, some argue that it technically doesn't read a person's mind. However, because specific thoughts and brain states can be deciphered, here it is referred to as mind-reading. Additionally, most mainstream documents refer to this as mind-reading, despite the fact that it is actually brainwave-reading.

[3] Magnetoencephalography (MEG) and positron emission tomography (PET) can also be used to infer a person's neurophysiological state. But because they are impractical for field use due to their large size and harmful radiation, MEG and PET won't be considered here. However, DARPA is in the process of developing a small helmet-sized MEG device which would be connected to a portable computer. See the article *Mind over Machine* in the February 1, 2004 issue of *Popular Science*, by Carl Zimmer.

Copyright © 2011 Mark Rich. All rights reserved. Mark (at) NewWorldWar.org

Congressional Research Service
Informing the legislative debate since 1914

Navy Lasers, Railgun, and Hypervelocity Projectile: Background and Issues for Congress

Ronald O'Rourke
Specialist in Naval Affairs

May 25, 2016

Congressional Research Service
7-5700
www.crs.gov
R44175

CRS REPORT
Prepared for Members and
Committees of Congress

Summary

The Navy is currently developing three potential new weapons that could improve the ability of its surface ships to defend themselves against enemy missiles—solid state lasers (SSLs), the electromagnetic railgun (EMRG), and the hypervelocity projectile (HVP).

Any one of these new weapon technologies, if successfully developed and deployed, might be regarded as a "game changer" for defending Navy surface ships against enemy missiles. If two or three of them are successfully developed and deployed, the result might be considered not just a game changer, but a revolution. Rarely has the Navy had so many potential new types of surface-ship missile-defense weapons simultaneously available for development and potential deployment.

Although the Navy in recent years has made considerable progress in developing SSLs, EMRG, and HVP, a number of significant development challenges remain. Overcoming these challenges will likely require years of additional development work, and ultimate success in overcoming them is not guaranteed.

The issue for Congress is whether to approve, reject, or modify the Navy's funding requests and proposed acquisition strategies for these three potential new weapons. Potential oversight questions for Congress include the following:

- Using currently available approaches for countering anti-ship cruise missiles (ASCMs) and anti-ship ballistic missiles (ASBMs), how well could Navy surface ships defend themselves in a combat scenario against an adversary such as China that has large numbers of ASCMs (including advanced models) and ASBMs? How would this change if Navy surface ships in coming years were equipped with SSLs, EMRG, HVP, or some combination of these systems?
- How significant are the remaining development challenges for SSLs, EMRG, and HVP?
- Are current schedules for developing SSLs, EMRG, and HVP appropriate in relation to remaining development challenges and projected improvements in enemy ASCMs and ASBMs? To what degree are current schedules for developing SSLs, EMRG, or HVP sensitive to annual funding levels?
- When does the Navy anticipate issuing roadmaps detailing its plans for procuring and installing production versions of SSLs, EMRGs, and HVP on specific Navy ships by specific dates?
- Will the kinds of surface ships that the Navy plans to procure in coming years have sufficient space, weight, electrical power, and cooling capability to take full advantage of SSLs (particularly those with beam powers above 200 kW) and EMRG? What changes, if any, would need to be made in Navy plans for procuring large surface combatants (i.e., destroyers and cruisers) or other Navy ships to take full advantage of SSLs and EMRG?
- Are the funding sources for SSLs, EMRG, and HVP in Navy and Defense-Wide research and development accounts sufficiently visible for supporting congressional oversight?

Contents

Introduction 1
  Issue for Congress 1
  Scope of Report 1
Background 2
  Strategic and Budgetary Context 2
    Concern about Survivability of Navy Surface Ships 2
    Depth of Magazine and Cost Exchange Ratio 3
  SSLs, EMRG, and HVP in Brief 4
    SSLs 4
    EMRG 13
    HVP 16
  Indirectly Improving Ability to Counter ASCMs and ASBMs 22
  Remaining Development Challenges 22
    SSLs 23
    EMRG and HVP 24
Issues for Congress 26
  Potential Oversight Questions 26
Legislative Activity for FY2017 27
  Summary of Congressional Action on FY2017 Funding 27
  FY2017 National Defense Authorization Act (H.R. 4909/S. 2943) 27
    House 27
    Senate 30
  FY2017 DOD Appropriations Act (H.R. 5293) 33
    House 33
  Directed Energy Weapon Systems Acquisition Act of 2016 (H.R. 4964/S. 2778) 34
    House 34
    Senate 35

Figures

Figure 1. Laser Weapon System (LaWS) on USS Ponce 7
Figure 2. Laser Weapon System (LaWS) on USS Ponce 7
Figure 3. Laser Weapon System (LaWS) on USS Ponce 8
Figure 4. Laser Weapon System Demonstrator (LWSD) on Self Defense Test Ship 10
Figure 5. Laser Weapon System Demonstrator (LWSD) on Self Defense Test Ship 11
Figure 6. ONR Graphic of LWSD Components 12
Figure 7. Industry-Built EMRG Prototype Demonstrator 14
Figure 8. Industry-Built EMRG Prototype Demonstrator 15
Figure 9. EMRG Prototype Demonstrator Installed on a JHSV 16
Figure 10. Photograph Showing HVP 17
Figure 11. HVP 18
Figure 12. HVP Launch Packages 19
Figure 13. HVP Application to Various Launchers 20

Figure 14. Navy Slide Depicting Operations Against Various Target Types 21
Figure 15. Development Challenges for SSLs 24
Figure 16. Development Challenges for EMRG 25

Tables

Table 1. Summary of Congressional Action on FY17 Funding.. 27

Appendixes

Appendix. Potential Advantages and Limitations of Shipboard Lasers 38

Contacts

Author Contact Information 40

Introduction

Issue for Congress

This report provides background information and issues for Congress on three potential new weapons that could improve the ability of Navy surface ships to defend themselves against enemy missiles—solid state lasers (SSLs), the electromagnetic railgun (EMRG), and the hypervelocity projectile (HVP).[1]

Any one of these new weapon technologies, if successfully developed and deployed, might be regarded as a "game changer" for defending Navy surface ships against enemy missiles. If two or three of them are successfully developed and deployed, the result might be considered not just a game changer, but a revolution. Rarely has the Navy had so many potential new types of surface-ship missile-defense weapons simultaneously available for development and potential deployment. Although the Navy in recent years has made considerable progress in developing SSLs, EMRG, and HVP, a number of significant development challenges remain.

The issue for Congress is whether to approve, reject, or modify the Navy's funding requests and proposed acquisition strategies for these three potential new weapons. Congress' decisions on this issue could affect future Navy capabilities and funding requirements and the defense industrial base.

Scope of Report

SSLs are being developed by multiple parts of the Department of Defense (DOD), not just the Navy. SSLs, EMRG, and HVP, moreover, have potential application to military aircraft and ground forces equipment, not just surface ships. And SSLs, EMRG, and HVP can be used for missions other than defending against ASCMs and ASBMs.[2] This report focuses on Navy efforts to develop SSLs, EMRG, and HVP for potential use in defending Navy surface ships against ASCMs and ASBMs. It supersedes an earlier CRS report that provided an introduction to potential Navy shipboard lasers.[3]

Note that while fictional depictions of laser weapons in popular media often show them being used to attack targets at long ranges, the SSLs currently being developed by the Navy for potential shipboard use would be used to counter targets at short ranges of about a mile to perhaps a few miles.

---

[1] Railgun is also spelled as rail gun; EMRG is also abbreviated as EM railgun; hypervelocity is also spelled as hyper-velocity or hyper velocity.

[2] As discussed later in the report, the Navy is exploring the potential for using shipboard lasers to counter small boats and unmanned aerial vehicles (UAVs), and EMRG can be used to attack land targets.

[3] CRS Report R41526, *Navy Shipboard Lasers for Surface, Air, and Missile Defense: Background and Issues for Congress*, by Ronald O'Rourke. This earlier CRS report has been archived and remains available as a supplementary reference source on potential Navy shipboard lasers.

Background

Strategic and Budgetary Context

Concern about Survivability of Navy Surface Ships

Although Navy surface ships have a number of means for defending themselves against anti-ship cruise missiles (ASCMs) and anti-ship ballistic missiles (ASBMs),[4] some observers are concerned about the survivability of Navy surface ships in potential combat situations against adversaries, such as China, that are armed with advanced ASCMs and with ASBMs.[5] Concern about this issue has led some observers to conclude that the Navy's surface fleet in coming years might need to avoid operating in waters that are within range of these weapons, or that the Navy might need to move toward a different fleet architecture that relies less on larger surface ships and more on smaller surface ships and submarines.[6] Such changes in Navy operating areas and fleet architecture could substantially affect U.S. military strategy and the composition of the Navy's shipbuilding expenditures.

Navy surface fleet leaders in early 2015 announced a new organizing concept for the Navy's surface fleet called distributed lethality. Under distributed lethality, offensive weapons such as ASCMs are to be distributed more widely across all types of Navy surface ships, and new operational concepts for Navy surface ship formations are to be implemented. The aim of distributed lethality is to boost the surface fleet's capability for attacking enemy ships and make it less possible for an enemy to cripple the U.S. fleet by concentrating its attacks on a few very-high-value Navy surface ships (particularly the Navy's aircraft carriers).[7] Perspectives on whether it would be cost effective to spend money spreading offensive weapons across a wider array of Navy surface ships might be influenced by views on whether those surface ships can adequately defend themselves against enemy missiles.

---

[4] These include the following: operating ships in ways that make it hard for others to detect and accurately track Navy ships; jamming or destroying enemy targeting sensors; interfering with the transmission of targeting data from sensors to weapon launchers; attacking weapon launchers (which can land-based launchers or launchers on surface ships, submarines, or aircraft); and countering ASCMs and ASBMs headed toward Navy ships. Navy measures for countering ASCMs and ASBMs headed toward Navy ships include the following: jamming a missile's guidance system; using decoys of various kinds to lure enemy missiles away from Navy ships; and shooting down enemy missiles with surface-to-air missiles and the Phalanx Close-In Weapon System (CIWS), which is essentially a radar-controlled Gatling gun. Employing all these measures reflects a long-standing Navy approach of creating a multi-layered defense against enemy missiles, and of attacking the enemy's "kill chain" at multiple points so as to increase the chances of breaking the chain. (The kill chain is the sequence of steps that an enemy must complete to conduct a successful missile attack on a Navy ship. This sequence includes, at a basic level of description, detecting and tracking the Navy ship, passing that information from sensors to the weapon launcher, launching the weapon, and guiding the weapon all the way to the Navy ship. Interfering with any one of these actions can break the kill chain and thereby prevent or defeat the attack.)

[5] See, for example, Andrew F. Krepinevich, Maritime Warfare in a Mature Precision-Strike Regime, Washington, Center for Strategic and Budgetary Assessments, 2014, 128 pp. For more on China's ASCMs and ASBMs, see CRS Report RL33153, *China Naval Modernization: Implications for U.S. Navy Capabilities—Background and Issues for Congress*, by Ronald O'Rourke.

ASCMs and ASBMs are not the only reasons that some observers are concerned about the future survivability of U.S. Navy surface ships in combat situations; observers are also concerned about threats to U.S. Navy surface ships posed by small boats, mines, and torpedoes.

[6] See, for example, Phillip E. Pournelle, "The Deadly Future of Sea Control," *U.S. Naval Institute Proceedings*, July 2015: 26-31.

[7] See, for example, Thomas Rowden, Peter Gumataotao, and Peter Fanta, "Distributed Lethality," *U.S. Naval Institute Proceedings*, January 2015: 18-23; Sam LaGrone, "SNA: Navy Surface Leaders Pitch More Lethal Ships, Surface Action Groups," *USNI News*, January 14, 2015; Kris Osborn, "Navy Unveils New Surface Warfare Strategy," *Military.com*, January 14, 2015; Sydney J. Freedberg Jr., "'If It Floats, It Fights,': Navy Seeks 'Distributed Lethality,'" *Breaking Defense*, January 14, 2015; Mike McCarthy and Megan Eckstein, "Navy Eyeing A 'Hunter Killer' Surface (continued...)

Depth of Magazine and Cost Exchange Ratio

Two key limitations that Navy surface ships currently have in defending themselves against ASCMs and ASBMs are limited depth of magazine and unfavorable cost exchange ratios. Limited depth of magazine refers to the fact that Navy surface ships can use surface-to-air missiles (SAMs) and their Close-in Weapon System (CIWS) Gatling guns to shoot down only a certain number of enemy unmanned aerial vehicles (UAVs) and anti-ship missiles before running out of SAMs and CIWS ammunition[8]—a situation (sometimes called "going Winchester"), that can require a ship to withdraw from battle, spend time travelling to a safe reloading location (which can be hundreds of miles away),[9] and then spend more time traveling back to the battle area.

Unfavorable cost exchange ratios refer to the fact that a SAM used to shoot down a UAV or anti-ship missile can cost the Navy more (perhaps much more) to procure than it cost the adversary to build or acquire the UAV or anti-ship missile. In the FY2016 defense budget, procurement costs for Navy SAMs range from about $900,000 per missile to several million dollars per missile, depending on the type.[10]

In combat scenarios against an adversary with a limited number of UAVs and anti-ship missiles, an unfavorable cost exchange ratio can be acceptable because it saves the lives of Navy sailors and prevents very expensive damage to Navy ships. But in combat scenarios (or an ongoing military capabilities competition) against a country such as China that has many UAVs and anti-ship missiles and a capacity for building or acquiring many more, an unfavorable cost exchange ratio can become a very expensive—and potentially unaffordable—approach to defending Navy surface ships against UAVs and anti-ship missiles, particularly in a context of constraints on U.S. defense spending and competing demands for finite U.S. defense funds.

(...continued)

Fleet, Would Require Upgunning Existing Ship Fleets," *Defense Daily*, January 15, 2015: 1-3; Richard Scott, "Offensive Language: USN Sets Out Surface Firepower Strategy," *Jane's International Defence Review*, May 2015: 42-47; Megan Eckstein, "Navy Studying Implications of Distributed Lethality in Wargames Series," *USNI News*, July 9, 2015; Lara Seligman, "Navy Establishes Task Force To Study Impact of Distributed lethality," *Inside the Navy*, July 10, 2015.

[8] Navy cruisers have 122 missile cells; Navy destroyers have 90 or 96 missile cells. Some of these cells are used for storing and launching Tomahawk land attack cruise missiles or anti-submarine rockets. The remainder are available for storing and launching SAMs. A Navy cruiser or destroyer might thus be armed with a few dozen or several dozen SAMs for countering ASCMs and ASBMs. Countering ASCMs or ASBMs with SAMs might sometimes require shooting two SAMs at each ASCM or ASBM.

[9] The missile cells on a Navy cruiser or destroyers are clustered together in an installation called a Vertical Launch System (VLS). VLS cells cannot be reloaded while the ship is underway; a ship needs to return to a port or a calm anchorage to reload its VLS.

[10] Unit procurement costs for ship-launched SAMs in the FY2016 are as follows: about $900,000 for the Rolling Airframe Missile (RAM), about $1.1 million to about $1.5 million for the Evolved Sea Sparrow Missile (ESSM), about $3.9 million for the SM-6 Block 1 missile, about $14 million for the SM-3 Block 1B missile, and more than $20 million for theSM-3 Block IIA missiles. RAM and ESSM are short-range missiles for defense against aircraft and ASCMs. The SM-6 Block 1 is a medium-range missile used for both defense against aircraft and ASCMs, and terminal (i.e., endo-atmospheric) defense against theater-range ballistic missiles. The SM-3 Block 1B and SM-3 Block IIA are used for mid-course (i.e., exo-atmospheric) defense against theater-range ballistic missiles.

SSLs, EMRG, and HVP offer a potential for dramatically improving depth of magazine and the cost exchange ratio:

- **Depth of magazine.** SSLs are electrically powered, drawing their power from the ship's overall electrical supply, and can be fired over and over, indefinitely, as long as the SSL continues to work and the ship has fuel to generate electricity. The EMRG's projectile and the HVP (which are one and the same—see next section) can be stored by the hundreds in a Navy surface ship's weapon magazine.[11]
- **Cost exchange ratio.** An SSL can be fired for a marginal cost of less than one dollar per shot (which is the cost of the fuel needed to generate the electricity used in the shot), while the EMRG's projectile/HVP has an estimated unit procurement cost of about $25,000.[12]

For additional discussion of the strategic and budgetary context in which the programs discussed in this report and other Navy programs may be considered, see CRS Report RL32665, *Navy Force Structure and Shipbuilding Plans: Background and Issues for Congress*, by Ronald O'Rourke.

SSLs, EMRG, and HVP in Brief

SSLs

Overview

The Navy in recent years has leveraged both significant advancements in industrial SSLs and decades of research and development work on military lasers done by other parts of DOD to make substantial progress toward deploying high-energy SSLs[13] on Navy surface ships. Navy surface ships would use high-energy SSLs initially for countering small boats UAVs, and potentially in the future for countering ASCMs and ASBMs as well.[14] High-energy SSLs on Navy ships would be short-range defensive weapons—they would counter targets at ranges of about one mile to perhaps eventually a few miles.[15]

---

[11] In July 2015, the Navy issued a request for information (RFI) to industry for the fabrication of a prototype EMRG mount that would store a minimum of 650 rounds. (RFI for Fabrication of Prototype Mount for Naval Railgun, Solicitation Number: N00024-15-R-4132, FedBizOpps.gov, July 29, 2015. See also Justin Doubleday, "Navy Developing Integrated Mount For Electromagnetic Railgun," *Inside the Navy*, July 31, 2015.)

[12] Sources for cost of HVP: David Martin, "Navy's Newest Weapon Kills at Seven Times the Speed of Sound," CBS News (cbssnews.com), April 7, 2014; Kris Osborn, "Navy Will Test its Electromagnetic Rail Gun aboard DDG 1000," *DefenseTech*, April 15, 2015.

[13] In discussions of potential Navy shipboard lasers, a high-energy laser is generally considered to be a laser with a beam power of at least 10 kilowatts (kW).

[14] In general, lasers would counter small boats and missiles by heating and burning holes in their skins, and causing thermal damage to their interiors. Lasers can also be used to "dazzle" (i.e., interfere with) electro-optical sensors on a boat or missile.

[15] The Navy has also performed research and development work on a different kind of laser, called the free electron laser (FEL). In recent years, Navy research and development work on potential shipboard lasers has shifted more to SSLs. For background information on the FEL, see CRS Report R41526, *Navy Shipboard Lasers for Surface, Air, and Missile Defense: Background and Issues for Congress*, by Ronald O'Rourke.

In addition to a low marginal cost per shot and deep magazine, potential advantages of shipboard lasers include fast engagement times, an ability to counter radically maneuvering missiles, an ability to conduct precision engagements, and an ability to use lasers for graduated responses ranging from detecting and monitoring targets to causing disabling damage. Potential limitations of shipboard lasers relate to line of sight; atmospheric absorption, scattering, and turbulence (which prevent shipboard lasers from being all-weather weapons); an effect known as thermal blooming that can reduce laser effectiveness; countering saturation attacks; possible adversary use of hardened targets and countermeasures; and risk of collateral damage, including damage to aircraft and satellites and permanent damage to human eyesight, including blinding. These potential advantages and limitations are discussed in greater detail in the **Appendix**.

Selected Key Developments

Key developments in the Navy's high-energy SSL development effort include the following:

- Between 2009 and 2012, the Navy successfully tested a prototype SSL called the Laser Weapon System (LaWS) against UAVs in a series of engagements that took place initially on land and subsequently on a Navy ship at sea.
- Between 2010 and 2011, the Navy tested another prototype SSL called the Maritime Laser Demonstration (MLD) in a series of tests that culminated with an MLD installed on a Navy ship successfully engaging a small boat.
- In April 2013, the Navy announced that it planned to install LaWS on the USS *Ponce* (pronounced pon-SAY)—a converted amphibious ship that is operating in the Persian Gulf as an interim Afloat Forward Staging Base (AFSB[I]) [16]—to conduct evaluation of shipboard lasers in an operational setting against swarming boats and swarming UAVs.[17] The system was installed in August 2014 (see **Figure 1**, **Figure 2**, and **Figure 3**).
- In March 2014, it was reported that the Navy anticipated moving to a shipboard laser program of record in "the FY2018 time frame" and achieving an initial operational capability (IOC) with a shipboard laser in FY2020 or FY2021.[18]

---

[16] An AFSB operates as a "mother ship" for Navy helicopter and small boat operations. The Ponce is serving as an interim AFSB pending the arrival of a new AFSB that is currently being built.

[17] "Navy Leaders Announce Plans for Deploying Cost-Saving Laser Technology," *Navy News Service*, April 8, 2013; Thom Shanker, "Navy Deploying Laser Weapon Prototype Near Iran," *New York Times*, April 9, 2013: 4; Mike McCarthy, "Navy Deploying Laser For Taking Out Drones," *Defense Daily*, April 9, 2013; Graham Warwick, "U.S. Navy Planning Gulf Deployment For Laser Weapon," *Aerospace Daily & Defense Report*, April 9, 2013: 6; Megan Eckstein, "Navy-Built Laser Weapon System Will Begin Demo On Ponce In Early 2014," *Inside the Navy*, April 15, 2013. See also Lara Seligman, "Navy-built LaWS To Begin Demo This Summer, IOC Slated For FY-20-21," *Inside the Navy*, March 24, 2014; Office of Naval Research, "All Systems Go: Navy's Laser Weapon Ready for Summer Deployment," *Navy News Service*, April 7, 2014.

Swarming refers to the use of boats and UAVs in large numbers, or swarms, in an attempt to confuse and overwhelm a target ship's defensive systems.

[18] Lara Seligman, "Navy-built LaWS To Begin Demo This Summer, IOC Slated For FY-20-21," *Inside the Navy*, March 24, 2014. A program of record, or POR, is a term sometimes used by DOD officials that means, in general, a program in the Future Years Defense Plan (FYDP) that is intended to provide a new, improved, or continuing materiel, weapon, or information system or service capability in response to an approved need. The term is sometimes used to refer to a program in a service's budget for procuring and deploying an operational weapon system, as opposed to a research and development effort that might or might not eventually lead to procurement and deployment of an operational weapon system.

- In December 2014, the Navy declared LaWS on the Ponce to be an "operational" system.[19]
- In January 2016, the Navy stated that it anticipated releasing a directed energy weapon roadmap in February 2016.[20]

---

[19] A December, 11, 2014, press report stated

> The Navy's first-of-a-kind laser deployed on a vessel sailing in the Persian Gulf has been declared operational and can be used by the crew to defend itself against potential threats, the service's head of the Office of Naval Research said on Wednesday [December 10, 2014].
>
> Rear Adm. Matthew Klunder told reporters on a conference call that Central Command has been green lighted to use the laser in the event of a threat, approval that has been passed along to the ship's commanding officer. The 30-kilowat laser, known as the Laser Weapon System, or LaWS, was installed on the USS Ponce in August [2014].
>
> The ship later departed for the Persian Gulf and the LaWS successfully carried out operational testing recently by striking a fast attack boat and drone, Klunder said, adding that this marks the "historic" first ever operational deployment of a directed energy weapon.
>
> (Mike McCarthy, "Navy Authorized To Use Ship-Based Laser In Battle," *Defense Daily*, December 11, 2014: 3. See also Sam LaGrone, "U.S. Navy Allowed to Use Persian Gulf Laser for Defense," *USNI News*, December 10, 2014; Philip Ewing, "Navy Declares Laser Weapon 'Operational,'" *Politico Pro (Pro Defense Report)*, December 10, 2014.)

The Navy testified on February 24, 2016, that

> the Solid State Laser Quick Reaction Capability (SSL-QRC) was fielded as a science and technology demonstration aboard the USS PONCE. It was successfully demonstrated as an effective weapon system and was subsequently transitioned to the fleet in the Central Command area of responsibility and is now an operational system.
>
> (Statement of Rear Admiral Mathias W. Winter, United States Navy, Chief of Naval Research, Before the Emerging Threats and Capabilities Subcommittee of the House Armed Services Committee on The Fiscal Year 2017 Budget Request, February 24, 2016, p. 15.)

[20] Justin Doubleday, "Winter: Navy Directed-Energy Strategy To Be Released This Month," *Inside the Navy*, February 1, 2016.

Figure 1. Laser Weapon System (LaWS) on USS Ponce



Source: Navy photograph dated November 16, 2014, accompanying David Smalley, "Historic Leap: Navy Shipboard Laser Operates in Arabian Gulf," *Navy News Service*, December 10, 2014, accessed August 12, 2015, at http://www.navy.mil/list_all.asp?id=84805.

Figure 2. Laser Weapon System (LaWS) on USS Ponce



Source: Navy photograph dated November 17, 2014, accompanying David Smalley, "Historic Leap: Navy Shipboard Laser Operates in Arabian Gulf," *Navy News Service*, December 10, 2014, accessed August 12, 2015, at http://www.navy.mil/list_all.asp?id=84805.

Figure 3. Laser Weapon System (LaWS) on USS Ponce



Source: Navy photograph dated November 16, 2014, accompanying David Smalley, "Historic Leap: Navy Shipboard Laser Operates in Arabian Gulf," *Navy News Service*, December 10, 2014, accessed August 12, 2015, at http://www.navy.mil/list_all.asp?id=84805.

SSL Technology Maturation (SSL-TM) Program

LaWS has a reported beam power of 30 kilowatts (kW),[21] which is strong enough to counter small boats and UAVs. As a follow-on effort to LaWS and MLD, the Navy initiated the SSL Technology Maturation (SSL-TM) program, in which industry teams led by BAE Systems, Northrop Grumman, and Raytheon, among others, competed to develop a shipboard laser with a beam power of 100 kW to 150 kW, which would provide increased effectiveness against small boats and UAVs.[22] Boosting beam power further—to something like 200 kW or 300 kW—could permit a laser to counter at least some ASCMs. Even stronger beam powers—on the order of at least several hundred kW, if not one megawatt (MW) or more—could improve a laser's effectiveness against ASCMs and enable it to counter ASBMs.[23]

---

[21] See, for example, Mike McCarthy, "Navy Authorized To Use Ship-Based Laser In Battle," *Defense Daily*, December 11, 2014: 3.

On October 22, 2015, DOD announced that it had selected Northrop Grumman as the winner of the SSL-TM competition. DOD's contract-award announcement stated:

> Northrop Grumman Space and Mission Systems Corp., Redondo Beach, California, is being awarded a $53,151,809 cost-plus-fixed-fee contract for the Solid State High Power Laser Weapon System Demonstrator (LWSD) program.... The Office of Naval Research seeks to continue the advancement of SSL weapon system designs, architectures, and component technologies. The government believes that improvements in lethality may be achieved through maturation and optimization of a variety of system characteristics, including laser power, beam quality, beam director architecture, and other physical and optical aspects of the laser, beam director, and system design. Leveraging our experience and internal investments, the Northrop Grumman team is ready to fully support the three phases of the LWSD program. This contract contains options, which if exercised, will bring the contract value to $91,057,597. Work will be performed in Redondo Beach, California, and is expected to be completed Oct. 21, 2016. If options are exercised, work will continue through July 7, 2018.... This contract was competitively procured under the Office of Naval Research broad agency announcement 15-0005 entitled "Solid State, High Power Laser Weapon System Demonstrator (LWSD) Design, Development and Demonstration for Surface Navy, USN." Six proposals were received in response to this solicitation.[24]

A December 22, 2016, Northrop Grumman news release about the October 22, 2016, contract award stated:

> During Phase 1 of the LWSD contract, Northrop Grumman will develop a detailed design for the new system. Phase 2 will include assembly and ground test of the system, while Phase 3 will comprise at-sea testing of the system aboard the Navy's Self Defense Test Ship (SDTS). The Navy will lead this testing with Northrop Grumman providing technical support. The SDTS is the former USS Paul F. Foster (DD-964).
>
> According to Renard, Northrop Grumman's LWSD is well suited to support the Navy's planned initial testing on the SDTS. The company has designed its system to be installed, however, with minimal modification or additional costs, for demonstration on the Navy's DDG-51 FLT II class destroyers.[25]

---

[22] For more on the SSL-TM program, see Office of Naval Research, "Solid-State Laser Technology Maturation Program," accessed August 11, 2015, at http://www.onr.navy.mil/Media-Center/Fact-Sheets/Solid-State-Laser-Technology-Maturation-Program.aspx; Office of Naval Research, "Solid State Laser Technology Maturation Program," September 2012, accessed August 11, 2015, at http://www.onr.navy.mil/~/media/Files/Fact-Sheets/35/Solid-State-Laser-Technology-Maturation-Program-2012-a.ashx; Office of Naval Research, "Research and Development/Technology Maturation of Solid State High Power Laser Weapon Systems, Subsystems, and/or Components for Surface Navy, USN, Broad Agency Announcement (BAA)," ONR BAA # 12-019, 2012, accessed August 11, 2015, at http://www.onr.navy.mil/~/media/files/funding-announcements/baa/2012/12-019.ashx; Future Force, "Developing a High-Energy Laser for the Navy," January 23, 2015, accessed August 11, 2015, at http://futureforce.navylive.dodlive.mil/2015/01/high-energy-laser/.

[23] For additional discussion, see CRS Report R41526, *Navy Shipboard Lasers for Surface, Air, and Missile Defense: Background and Issues for Congress*, by Ronald O'Rourke, particularly the section entitled "Required Laser Power Levels for Countering Targets" and Appendix A on "Laser Power Levels Required to Counter Targets."

[24] DOD contract award announcements for October 22, 2015, accessed December 18, 2015, at: http://www.defense.gov/News/Contracts/Contract-View/Article/625630.

[25] "US Navy Selects Northrop Grumman to Design and Produce Shipboard Laser Weapon System Demonstrator," (continued...)

Figure 4 shows an artist's rendering of LWSD installed on the Navy's Self Defense Test Ship (the USS Paul F. Foster [DD-964], an old Spruance [DD-963] class destroyer).

Figure 4. Laser Weapon System Demonstrator (LWSD) on Self Defense Test Ship

Artist's rendering



Source: Cropped version of image accessed on March 18, 2016, at http://media.globenewswire.com/cache/189/hires/39412.jpg.

Figure 5 is a detail from the above photo.

(...continued)

December 22, 2016, accessed March 18, 2016, at: http://www.globenewswire.com/newsarchive/noc/press/pages/news_releases.html?d=10158731 . See also Richard Scott, "Northrop Grumman To Build on MLD for SSL Demonstrator," *IHS Jane's International Defence Review*, February 2016: 5.

Figure 5. Laser Weapon System Demonstrator (LWSD) on Self Defense Test Ship

Artist's rendering



Source: Cropped version of image accessed on March 18, 2016, at http://media.globenewswire.com/cache/189/hires/39412.jpg.

Figure 6 Is an Office of Naval Research (ONR) graphic illustration of the LWSD's major components.

Figure 6. ONR Graphic of LWSD Components

Artist's rendering



SSL-TM Components

Hybrid Predictive Avoidance Safety Subsystem (HPASS)

Mission System Modules
- Low Power Module
- Optical MSM

Laser & Beam Director

SPS-48 Radar

SPS-49 Radar

SPQ-9B Radar

Common Display System/ Common Electronics Module (CDS/CEM, Gov't Design)

Thermal Storage Module

Ship Integration

NAVSEA 05D Ship Integration Studies

Surrogate Combat System Emulated by Virtual Test Bed (Gov't Combat System Simulator Interface and Fire Control Module, leveraging AEGIS combat system knowledge base)

Energy Storage Module

Distribution A – Approved For Public Release – Distribution Unlimited

8

Source: Slide from February 2016 ONR briefing to CRS on SSL-TM program, received from Navy Office of Legislative Affairs February 26, 2016.

Directed Energy Roadmap

A July 28, 2015, press report stated:

> [Secretary of the Navy Ray] Mabus said he would release a DE [directed energy][26] roadmap this fall that "charts our course for research, development, and fielding of high power radio frequency weapons, lasers, and directed energy countermeasures. And I will follow it up with my guidance to the Program Objective Memorandum for [Fiscal Year 2018],[27] which, importantly, establishes a resource sponsor and a program of record."...
>
> Also meant to help quicken the pace of progress, the Office of Naval Research will take lessons learned from the [USS] Ponce to inform the Solid State Laser Technology Maturation program that aims to produce a 100-150 kilowatt laser prototype for at-sea testing in 2018, or sooner if possible. Rear Adm. Bryant Fuller, Naval Sea Systems Command (NAVSEA) chief engineer, said... that everything the Navy learned about rules

---

[26] Lasers and another class of weapons called high-power microwave (HPM) weapons are referred to collectively as directed-energy weapons because they achieve their effects by directing electromagnetic energy at their targets.

[27] The Program Objective Memorandum (POM) is an internal DOD document that guides the preparation of a budget for a particular fiscal year.

> of engagement and how to use LaWS in an operational environment would apply to larger laser weapons as well. Leveraging the operational knowledge Ponce gained will help the Navy field whatever comes out of the SSL-TM effort much more rapidly.
>
> In the meantime, Mabus said the Laser Weapon System (LaWS) will continue its work in the Middle East after early success led officials to extend its deployment.[28]

EMRG

In addition to SSLs, the Navy since 2005 has been developing EMRG, a cannon that uses electricity rather than chemical propellants (i.e., gunpowder charges) to fire a projectile.[29] In EMRG, "magnetic fields created by high electrical currents accelerate a sliding metal conductor, or armature, between two rails to launch projectiles at [speeds of] 4,500 mph to 5,600 mph,"[30] or roughly Mach 5.9 to Mach 7.4 at sea level.[31] Like SSLs, EMRG draws its power from the ship's overall electrical supply.[32] The Navy originally began developing EMRG as a naval surface fire support (NSFS) weapon for supporting U.S. Marines operating ashore, but subsequently determined that the weapon also has potential for defending against ASCMs and ASBMs.[33] In response to Section 243 of the FY2012 National Defense Authorization Act (H.R. 1540/P.L. 112-81 of December 31, 2011), the Navy in September 2012 submitted to the congressional defense committees a report on the EMRG development effort.[34]

Following tests with early Navy-built EMRG prototypes, the Navy funded the development of two industry-built EMRG prototype demonstrators, one by BAE Systems and the other by General Atomics (see **Figure 7** and **Figure 8**).

---

[28] Megan Eckstein, "Mabus: Adversaries Showing Interest in Directed Energy; Navy Needs to Move Faster," *USNI News*, July 28, 2015.

[29] Because it uses electricity rather than a powder charge to accelerate the projectile, Navy officials sometimes refer to EMRG as a launcher rather than a gun or cannon.

[30] Grace Jean, "With a Bang, Navy Begins Tests on EM Railgun Prototype Launcher," Navy News Service, February 28, 2012, accessed August 12, 2015, at http://www.navy.mil/submit/display.asp?story_id=65577.

[31] The speed of sound in air (i.e., Mach 1), varies with altitude; at sea level, it is approximately 761 miles an hour. (See for example, the table entitled "Speed of Sound at Different Altitudes," accessed August 12, 2015, at http://www.fighter-planes.com/jetmach1.htm.

[32] Unlike SSLs, however, EMRG is not a directed energy weapon, because it achieves its effects by firing a physical projectile at the target, not by directing electromagnetic energy at the target. See also footnote 26.

[33] For a recent article discussing the use of EMRG in countering ASCMs and ASBMs, see Sam LaGrone, "Navy Wants Rail Guns to Fight Ballistic and Supersonic Missiles Says RFI," *USNI News*, January 5, 2015.

[34] U.S. Navy, *Electromagnetic Railgun System: Final Report to the Congressional Defense Committees*, August 2012, with cover letters dated September 18, 2012. For a press report discussing the Navy's report to Congress, see Dan Taylor, "Stackley: Navy Identifies Four Technical Hurdles To Railgun Development," *Inside the Navy*, November 19, 2012.

Figure 7. Industry-Built EMRG Prototype Demonstrator

BAE prototype



Source: Navy photograph dated July 8, 2014, associated with Office of Naval Research Public Affairs, "From Research to Railgun: Revolutionary Weapon at Future Force EXPO," *Navy News Service*, January 13, 2015, accessed August 12, 2015, at http://www.navy.mil/submit/display.asp?story_id=85166.

Figure 8. Industry-Built EMRG Prototype Demonstrator

General Atomics prototype



Source: navy photograph dated July 8, 2014, accessed August 12, 2015, at http://www.navy.mil/view_image.asp?id=180994.

The two industry-built prototypes are designed to fire projectiles at energy levels of 20 to 32 megajoules,[35] which is enough to propel a projectile 50 to 100 nautical miles.[36] (Such ranges might refer to using the EMRG for NSFS missions. Intercepts of ASCMs and ASBMs might take place at much shorter ranges.) The Navy began evaluating the two industry-built prototypes in 2012.

In April 2014, the Navy announced that it plans to temporarily install a prototype EMRG aboard a Navy Joint High Speed Vessel (JHSV) in FY2016, for use in at-sea tests.[37] **Figure 9** is an artist's rendering of that installation.

In January 2015, it was reported that the Navy is projecting that EMRG could become operational on a Navy ship between 2020 and 2025.[38] In April 2015, it was reported that the Navy is considering installing an EMRG on a Zumwalt (DDG-1000) class destroyer by the mid-2020s.[39]

---

[35] The Navy states that "a megajoule is a measurement of energy associated with a mass traveling at a certain velocity. In simple terms, a one-ton vehicle moving at 100 mph equals a magajoule of energy." (Office of Naval Research Public Affairs, "Navy Sets New World Record with Electromagnetic Railgun Demonstration," *Navy News Service*, December 10, 2010, accessed August 12, 2015, at http://www.navy.mil/submit/display.asp?story_id=57690.)

[36] Grace Jean, "With a Bang, Navy Begins Tests on EM Railgun Prototype Launcher," Navy News Service, February 28, 2012, accessed August 12, 2015, at http://www.navy.mil/submit/display.asp?story_id=65577.

[37] Naval Sea Systems Command Office of Corporate Communication, "Navy to Deploy Electromagnetic Railgun Aboard JHSV," *Navy News Service*, April 7, 2014, accessed August 12, 2015, at http://www.navy.mil/submit/display.asp?story_id=80055.

[38] Sam LaGrone, "Navy Wants Rail Guns to Fight Ballistic and Supersonic Missiles Says RFI," *USNI News*, January 5, 2015.

[39] Sam LaGrone, "Navy Considering Railgun for Third Zumwalt Destroyer," *USNI News*, February 5, 2015 (updated (continued...)

Figure 9. EMRG Prototype Demonstrator Installed on a JHSV

Artist's rendering



Source: Briefing slide entitled "FY16 At-Sea Test of Railgun" in Navy briefing entitled "Railgun Program Overview," undated but posted at InsideDefense.com on April 14, 2015. (InsideDefense.com states that the briefing was presented at a public conference on April 14, 2015.)

HVP

As the Navy was developing EMRG, it realized that the guided projectile being developed for EMRG could also be fired from 5-inch and 155mm powder guns.[40] Navy cruisers each have two

---

(...continued)

February 11, 2015); Mike McCarthy, "Navy Aiming To Put Railgun On Third Zumwalt Destroyer," *Defense Daily*, February 6, 2015; Kris Osborn, "Navy Will Test its Electromagnetic Rail Gun aboard DDG 1000," *DefenseTech*, April 15, 2015. For more on Zumwalt-class destroyers, see CRS Report RL32109, *Navy DDG-51 and DDG-1000 Destroyer Programs: Background and Issues for Congress*, by Ronald O'Rourke.

[40] The Navy describes the HVP as "a next generation, common, low drag, guided projectile capable of completing multiple missions for gun systems such as the Navy 5-Inch, 155-mm, and future railguns.... HVP's low drag aerodynamic design enables high velocity, maneuverability, and decreased time-to-target. These attributes coupled with accurate guidance electronics provide low cost mission effectiveness against current threats and the ability to adapt to air and surface threats of the future." (Office of Naval Research, Hypervelocity Projectile," September 2012, accessed August 14, 2015, at http://www.onr.navy.mil/~/media/Files/Fact-Sheets/35/Hypervelocity-Projectile-2012B.ashx.) The Navy states that HVP weighs 23 pounds. (Source: David Martin, "Navy's Newest Weapon Kills at Seven Times the Speed of Sound," *CBS News (cbssnews.com)*, April 7, 2014.)

BAE Systems states that HVP is 24 inches long and weighs 28 pounds, including a 15-pound payload. The total length and weight of an HVP launch package, BAE Systems states, is 26 inches and 40 pounds. BAE states that the maximum rate of fire for HVP is 20 rounds per minute from a Mk 45 5-inch gun, 10 rounds per minute from the 155mm gun on DDG-1000 class destroyers (called the Advanced Gun System, or AGS), and 6 rounds per minute from EMRG. HVP's firing range, BAE Systems states, is more than 40 nautical miles (when fired from a Mk 45 Mod 2 5-inch gun), more than 50 nautical miles (Mk 45 Mod 4 5-inch gun), more than 70 nautical miles (155mm gun on DDG-1000 class destroyers), and more than 100 nautical miles (EMRG). (BAE Systems, "Hypervelocity Projectile (HVP)," 2014, (continued...)

5-inch guns, and most Navy destroyers each have one 5-inch gun. The Navy's three new Zumwalt class (DDG-1000) destroyers, which are under construction, each have two 155mm guns.

The projectile is a hypervelocity projectile when fired from either EMRG or a powder gun, but the term HVP tends to be used more frequently in connection with the concept of firing it from a powder gun. **Figure 10** and **Figure 11** show the HVP.

Figure 10. Photograph Showing HVP



Source: Navy photograph dated April 4, 2014, with a caption that reads: "Rear Adm. Matthew Klunder, chief of naval research, shows off a Hypervelocity Projectile (HVP) to CBS News reporter David Martin during an interview held at the Naval Research Laboratory's materials testing facility. The HVP is a next-generation, common, low drag, guided projectile capable of completing multiple missions for gun systems such as the Navy 5-inch, 155-mm, and future railguns," accessed August 12, 2015, at http://www.navy.mil/view_image.asp?id=174517.

(...continued)

accessed August 14, 2015, at http://www.baesystems.com/download/BAES_178505/hyper-velocity-projectile-hvp-datasheet.)

In July 2015, the Navy issued a request for information (RFI) to industry for the fabrication of a prototype EMRG mount capable of handling an integrated launch weight package of 22 kg, or about 48.5 pounds. (RFI for Fabrication of Prototype Mount for Naval Railgun, Solicitation Number: N00024-15-R-4132, FedBizOpps.gov, July 29, 2015. See also Justin Doubleday, "Navy Developing Integrated Mount For Electromagnetic Railgun," *Inside the Navy*, July 31, 2015.)

Figure 11. HVP



Multi-Mission HVP

Missions

Anti-Air

NSFS - Strike

Missiles

Anti-Surface

Technologies

High-G Electronics

Packaging

Miniaturization

Thermal Protect

Adv. Energetics

Hyper Velocity Projectile

Weapon Systems

5-Inch Mk 45

Railgun

155 mm – AGS

155 mm

- High speed launch enables effectiveness
- High density electronics enables packaging & survivability
- High computational power enables advanced tracking & guidance algorithms

Distribution A

Slide 7

6/3/2014

Source: Slide 7 from Navy briefing entitled "Electromagnetic Railgun," NDIA Joint Armaments Forum, Exhibition & Technology Demonstration, May 14, 2014, LCDR Jason Fox, USN, Assistant PM [Program Manager], Railgun Ship Integration, Distribution A, Approved for Public Release, accessed August 13, 2015, at http://www.dtic.mil/ndia/2014armaments/WedFox.pdf.

When fired from 5-inch powder guns, the projectile achieves a speed of roughly Mach 3, which is roughly half the speed it achieves when fired from EMRG, but more than twice the speed of a conventional 5-inch shell fired from a 5-inch gun.[41] This is apparently fast enough for countering at least some ASCMs. The Navy states that "The HVP—combined with the MK 45 [5-inch gun][42]—will support various mission areas including naval surface fire support, and has the capacity to expand to a variety of anti-air threats, [and] anti-surface [missions], and could expand the Navy's engagement options against current and emerging threats."[43]

One advantage of the HVP/5-inch gun concept is that the 5-inch guns are already installed on Navy cruisers and destroyers, creating a potential for rapidly proliferating HVP through the cruiser-destroyer force, once development of HVP is complete and the weapon has been integrated into cruiser and destroyer combat systems. **Figure 12** shows HVP launch packages configured for 5-inch guns, 155mm guns, and EMRG.

---

[41] Source: Sam LaGrone, "Updated: Navy Researching Firing Mach 3 Guided Round from Standard Deck Guns," *USNI News*, June 1, 2015 (updated June 2, 2015).

[42] The type of 5-inch gun on Navy cruisers and destroyers is called the Mark 45.

[43] Naval Surface Warfare Center Dahlgren Division Corporate Communications, "DEPSECDEF Loads HVP on Test Range, Observes Repetitive Rate Electromagnetic Railgun's Commissioning Series," *Navy News Service*, May 8, 2015, accessed August 12, 2015, at http://www.navy.mil/submit/display.asp?story_id=86987.

Figure 12. HVP Launch Packages

Launch packages for 5-inch gun, 155mm gun, and EMRG



Source: BAE Systems, "Hypervelocity Projectile (HVP)," 2014, accessed August 14, 2015, at http://www.baesystems.com/download/BAES_178505/hyper-velocity-projectile--datasheet.

Figure 13 is a slide showing the potential application of HVP to 5-inch power guns, 155mm powder guns, and EMRG. The first line of the slide, for example, discusses HVP's use with 5-inch powder guns, stating that it uses a high-explosive (HE) warhead for the NSFS mission;[44] that a total of 113 5-inch gun barrels are available in the fleet (which could be a reference to 22 cruisers with two guns each, and 69 destroyers with one gun each); and that as a game-changing capability, it is guided and can be used at ranges of up to 26 nautical miles to 41 nautical miles for NSFS operations, for countering ASCMs, and for anti-surface warfare (ASuW) operations (i.e., attacking surface ships and craft).

---

[44] The "KE" in the next line down means that when fired from EMRG, the projectile can alternatively attack targets using its own kinetic energy (i.e., by simply impacting the target at hypersonic speed).

Figure 13. HVP Application to Various Launchers



Commonality Approach

GUN SYSTEM	PROJECTILE (SABOTED & SUB-CALIBER)	MISSION & WARHEAD TYPE	TRANSITION OPPORTUNITES	GAME CHANGING CAPABILITY
5" MK 45 MOD 2/4		NSFS – HE	113 Barrels (PEO IWS)	GUIDED 26 – 41 NM NSFS/ASCM/ASuW
20 – 32 MJ Railgun		NSFS – HE NSFS - KE	FUTURE (PMS405/PEO IWS)	GUIDED 50 - 100 NM NSFS/ASCM/ASuW/ Future Threats
155 mm – AGS		NSFS – HE	6 Barrels (PEO IWS)	GUIDED 40 NM NSFS/ASCM/ASuW
155 mm		Ground Fires – HE	800 ARMY 300 MARINE ASSETS	GUIDED 17 NM Fires/CMD

Multi- Barrel , Multi- Mission, & Multi-Service Applications

Distribution A

Slide 16

6/3/2014

Source: Slide 16 from Navy briefing entitled "Electromagnetic Railgun," NDIA Joint Armaments Forum, Exhibition & Technology Demonstration, May 14, 2014, LCDR Jason Fox, USN, Assistant PM [Program Manager], Railgun Ship Integration, Distribution A, Approved for Public Release, accessed August 13, 2015, at http://www.dtic.mil/ndia/2014armaments/WedFox.pdf.

Figure 14 is a not-to-scale illustration of how HVPs fired from EMRGs and 5-inch guns can be used to counter various targets, including ASCMs and ASBMs.

Figure 14. Navy Slide Depicting Operations Against Various Target Types



Railgun and Hyper Velocity Projectile

An Affordable Multi-Mission Asymmetric Capability

DISTRIBUTION STATEMENT A. Approved for public release.

5

Source: Slide 5 from Navy briefing entitled "Electromagnetic Railgun," NDIA Joint Armaments Forum, Exhibition & Technology Demonstration, May 14, 2014, LCDR Jason Fox, USN, Assistant PM [Program Manager], Railgun Ship Integration, Distribution A, Approved for Public Release, accessed August 13, 2015, at http://www.dtic.mil/ndia/2014armaments/WedFox.pdf.

An April 11, 2016, press report states:

> The Pentagon wants to take a weapon originally designed for offense, flip its punch for defense and demonstrate by 2018 the potential for the Army and Navy to conduct missile defense of bases, ports and ships using traditional field guns to fire a new hypervelocity round guided by a mobile, ground variant of an Air Force fighter aircraft radar.
>
> The Strategic Capabilities Office is working with the Army, Navy and Air Force to craft a Hypervelocity Gun Weapon System that aims, in part, to provide China and Russia an example of a secret collection of new U.S. military capabilities the Defense Department is bringing online in an effort to strengthen conventional deterrence.
>
> "It is a fantastic program," Will Roper, Strategic Capabilities Office director, said in a March 28 interview with reporters, who said the project aims "to completely lower the cost of doing missile defense" by defeating missile raids at a lower cost per round and, as a consequence, imposing higher costs on attackers.[45]

A May 5, 2016, press report states:

---

[45] Jason Sherman, "SCO Aims To Flip The Script on Missile Defense With Hypervelocity Gun," *Inside the Navy*, April 11, 2016.

> Come January [2017], the Pentagon will almost assuredly have new leadership, complete with a new vision for how the Department of Defense should operate, organize and plan for the future.
>
> It's a reality facing down Defense Secretary Ash Carter and Deputy Secretary Bob Work as they try to complete a transformation at the Pentagon, one which both men have said is vital to making sure the US is able to maintain its technological edge against great powers like Russia and China in the future.
>
> While Carter has made his reach-out to nontraditional communities the centerpiece of his initiative, Work's focus has been the "Third Offset," a series of technological bets, largely focused on man-unmanned teaming, that he believes will pay off in the future.
>
> So how do you make sure that a long-term project like the Third Offset keeps going under a new administration?
>
> "We have three really complimentary ways to go about this," Work said Monday at an event hosted by the Atlantic Council.
>
> The first, he explained, is giving many options to the next administration.
>
> "First of all, I'm going to be central to the transition, so I am going to be able to personally talk with the transition team and explain to them what we have pursued and why we have pursued it, and let them make their own decisions," Work said.
>
> "One of the things we have done in our program is build in a lot of different options that they can pull levers on," Work explained.
>
> As an example, he pointed to the idea of an electromagnetic railgun. Initially, Work and his team thought that was an area that would be a major focus of development, but as they experimented they realized that a powder gun with a hypervelocity round could have almost the same impact — but at a fraction of the cost, because it did not require the development, testing and adaptation of a new gun.
>
> "We're going to say 'look, this is the place where [we think] you want to put your money,' but we're going to have enough money in both the electromagnetic railgun and the powder gun that if the new administration says 'I really want the electromagnetic railgun, this is the way I want to go,' knock yourself out," Work said. "We've set you up for success."[46]

Indirectly Improving Ability to Counter ASCMs and ASBMs

As discussed earlier, SSLs currently under development have enough beam power to counter small boats and UAVs, but not enough to ASCMs or ASBMs. Even so, such SSLs could indirectly improve a ship's ability to counter ASCMs and ASBMs by permitting the ship to use fewer of its SAMs for countering UAVs, and more of them for countering ASCMs and ASBMs. Similarly, even though HVPs fired from 5-inch powder guns would not be able to counter ASBMs, they could indirectly improve a ship's ability to counter ASBMs by permitting the ship to use fewer of its SAMs for countering ASCMs and more of its SAMs for countering ASBMs.

Remaining Development Challenges

Although the Navy in recent years has made considerable progress in developing SSLs, EMRG, and HVP, a number of significant development challenges remain. Overcoming these challenges will likely require years of additional development work, and ultimate success in overcoming them is not guaranteed.[47]

---

[46] Aaron Mehta, "Pentagon No. 2: How to Keep Third Offset Going in the Next Administration," *Defense News*, May 5, 2016.

SSLs

As shown in **Figure 15**, remaining development challenges for SSLs include, among other things, making the system rugged enough for extended shipboard use, making the beam director (the telescope-like part of the laser that sends the beam toward the target) suitable for use in a marine environment (where moisture and salt in the air can be harsh on equipment), and integrating the system into the ship's electrical power system and combat system.

A January 23, 2015, blog post co-authored by the Office of Naval Research's program officer for the Navy's SSL program states:

> In the near term, many challenges remain to develop and operate high-energy laser systems in the maritime environment that are unique to the Navy and Marine Corps. Among these challenges is dealing with the heat generated as power levels increase. A second issue is packing sufficient power on the platform, which will require advanced battery, generator, power conditioning, and hybrid energy technologies. Current laser technologies are approximately 30 percent electrically efficient. Corrosion and contamination of optical windows by shipboard salt spray, dirt, and grime also are technical challenges. In addition, atmospheric turbulence resulting from shifting weather conditions, moisture, and dust is problematic. Turbulence can cause the air over long distances to act like a lens, resulting in the laser beam's diffusing and distorting, which degrades its performance.
>
> Much progress has been made in demonstrating high-energy laser weapon systems in the maritime environment, but there is still much to be done. Additional advances will be required to scale power levels to the hundreds of kilowatts that will make high[-]energy lasers systems robust, reliable, and affordable. Higher power levels are important for the ability to engage more challenging threats and improve the rate and range at which targets can be engaged.
>
> The programs managed by ONR are addressing these remaining issues while positioning this important warfighting capability toward an acquisition program and eventual deployment with the fleet and force.[48]

---

[47] Laser skeptics sometimes note that laser proponents over the years have made numerous predictions about when lasers might enter service with DOD, and that these predictions repeatedly have not come to pass. Viewing this record of unfulfilled predictions, skeptics might argue that "lasers are X years in the future—and always will be." Laser proponents acknowledge the record of past unfulfilled predictions, but argue that the situation has now changed because of rapid advancements in SSL technology and a shift from earlier ambitious goals (such as developing megawatt-power lasers for countering targets at tens or hundreds of miles) to more realistic goals (such as developing kilowatt-power lasers for countering targets at no more than a few miles). Laser proponents might argue that laser skeptics are vulnerable to what might be called cold plate syndrome (i.e., a cat that sits on a hot plate will not sit on a hot plate again—but it will not sit on a cold plate, either).

[48] Peter Morrison and Dennis Sorenson, "Developing a High-Energy Laser for the Navy," Future Force, January 23, 2015, accessed August 13, 2015, at http://futureforce.navylive.dodlive.mil/2015/01/high-energy-laser/. The authors are identified at the end of the post as follows: "Peter Morrison is the Office of Naval Research's program officer for the Navy's Solid-State Laser program. Dennis Sorenson is a contractor with the Office of Naval Research."

Figure 15. Development Challenges for SSLs

As of February 2013



ONR

Laser Weapon Technical Risk Areas

- **System Ruggedization (Shock & Vibe)**
- **Beam Director Marinization**
  - Durability & Survivability
  - Beam Efficiency and Quality
  - Pointing Accuracy
  - Optical Coatings
- **Dynamic Atmospheric Characterization**
- **Shipboard Integration**
  - Electrical Power Management & Thermal Dissipation
  - Fire Control & C4ISR
  - Reliability, Maintainability, Sustainability
- **Operational Concepts of Operation**

OFFICE OF NAVAL RESEARCH 5

Source: Slide from Navy briefing entitled "Navy Solid State Laser Program Overview," ASNE Day 2013, Mr. Peter "Rollie" Morrison, ONR 35 S&T Program Office, February 22, 2013, accessed August 13, 2015, at https://www.navalengineers.org/ProceedingsDocs/ASNEDay2013/Morrison_Pres.pdf.

EMRG and HVP

As shown in **Figure 16**, remaining development challenges for EMRG involve items relating to the gun itself (including increasing barrel life to desired levels), the projectile, the weapon's electrical power system, and the weapon's integration with the ship. Fielding HVP on cruisers and destroyers ships equipped with 5-inch and 155mm powder guns would additionally require HVP to be integrated with the combat systems of those ships.

Figure 16. Development Challenges for EMRG

As of May 2014



Naval Railgun – Focus of Effort

Launcher

- Multi-shot barrel life
- Barrel construction to contain rail repulsive forces
- Scaling from 8MJ (state of the art) to 32MJ
- Thermal management techniques
- M&S – Represent interaction between bore and projectile

Projectile

- Dispensing and Unitary Rounds
- Gun launch survivability
  - – 20 to 45 kG acceleration
  - – Aero Thermal Risk Management
- Hypersonic guided flight for accuracy
- Lethality mechanics

Power & Energy

Pulsed Power Capacitors

Batteries

- Energy Density
- Rep rate operation & thermal management
- Switching

Ship Integration

- Dynamic Power Sharing
- Space and Weight
- Cooling
- EM Field Management

Distribution A

Slide 9

6/3/2014

Source: Slide 9 from Navy briefing entitled "Electromagnetic Railgun," NDIA Joint Armaments Forum, Exhibition & Technology Demonstration, May 14, 2014, LCDR Jason Fox, USN, Assistant PM [Program Manager], Railgun Ship Integration, Distribution A, Approved for Public Release, accessed August 13, 2015, at http://www.dtic.mil/ndia/2014armaments/WedFox.pdf.

The Navy states:

> The EMRG effort began in FY 2005 with a focus on the barrel, power storage, and rail technology. In 2015, the Navy is testing full-scale industry advanced composite launchers for structure strength and manufacturability, and has advanced the pulsed-power system design from single-shot to actively cooled repeated rate operations. Building on the success of the first phase, the second phase started in 2012 with a focus on developing equipment and techniques to fire ten rounds per minute. Thermal-management techniques required for sustained firing rates are in development for both the launcher system and the pulsed-power system. The Office of Naval Research will develop a tactical prototype EMRG launcher and pulsed-power architecture suitable for advanced testing both afloat and ashore. Railgun demonstration has been funded to occur in FY 2016.[49]

A June 2015 press report states:

> As the Navy prepares to test its electromagnetic railgun at sea for the first time in 2016, service leaders said one of the biggest challenges will be integrating the new technology onto existing platforms.....

---

[49] U.S. Navy, *U.S. Navy Program Guide 2015*, p. 169.

> [Vice Adm. William Hilarides, commander of Naval Sea Systems Command] said he is positive the Navy will successfully demonstrate the weapon's ability to fire from the Trenton, but one of the biggest challenges will be configuring the railgun so that it fits within the power structure of other existing platforms.
>
> "Those are not 600-ton margin ships," he said [meaning ships with 600 tons of growth margin available to accommodate EMRG]. "If they have 60 tons, if they have 16 tons, then we'll be talking about what do we take off our existing destroyers, cruisers and other ships in order to get this incredible capability [on them]."
>
> These types of discussions are influencing ship designs as program managers look at what systems are indispensable and what can be exchanged, Hilarides said.
>
> Integrating the railgun into the fleet won't be a swift process.
>
> It will be at least 10 years until the railgun is fielded on new ships and potentially 30 years past that before the Navy considers removing powder guns from the fleet entirely and transitioning to energy weapons alone, according to Hilarides.[50]

Issues for Congress

Potential Oversight Questions

Potential oversight questions for Congress regarding Navy programs for SSLs, EMRG, and HVP include the following:

- Using currently available approaches for countering ASCMs and ASBMs, how well could Navy surface ships defend themselves in a combat scenario against an adversary such as China that has large numbers of ASCMs (including advanced models) and ASBMs? How would this change if Navy surface ships in coming years were equipped with SSLs, EMRG, HVP, or some combination of these systems?
- How significant are the remaining development challenges for SSLs, EMRG, and HVP?
- Are current schedules for developing SSLs, EMRG, and HVP appropriate in relation to remaining development challenges and projected improvements in enemy ASCMs and ASBMs? To what degree are current schedules for developing SSLs, EMRG, or HVP sensitive to annual funding levels?
- When does the Navy anticipate issuing roadmaps detailing its plans for procuring and installing production versions of SSLs, EMRGs, and HVP on specific Navy ships by specific dates?
- Will the kinds of surface ships that the Navy plans to procure in coming years have sufficient space, weight, electrical power, and cooling capability to take full advantage of SSLs (particularly those with beam powers above 200 kW) and EMRG? What changes, if any, would need to be made in Navy plans for procuring large surface combatants (i.e., destroyers and cruisers) or other Navy ships to take full advantage of SSLs and EMRG?

---

[50] Allyson Versprille, "Integration Biggest Challenge for Railgun," *National Defense*, June 2015. See also Lance M. Bacon, "3-Star: 'Lot of Work' Before Railgun Arrives in Fleet," *Navy Times*, February 5, 2015.

- Are the funding sources for SSLs, EMRG, and HVP in Navy and Defense-Wide research and development accounts (see "Summary of Congressional Action on FY2017 Funding" below) sufficiently visible for supporting congressional oversight?

Legislative Activity for FY2017

Summary of Congressional Action on FY2017 Funding

Funding in the defense budget for research and development work on Navy SSLs, EMRG, and HVP is spread across several research and development account line items (which are known as program elements, or PEs). The PEs shown in **Table 1** capture much but not necessarily all of the funding for developing Navy SSLs, EMRG, and HVP. The PEs shown in the table, moreover, include funding for efforts other than Navy SSLs, EMRG, and HVP, so congressional changes from requested amounts might or might not relate to SSLs, EMRG, or HVP.

Table 1. Summary of Congressional Action on FY17 Funding

In millions of dollars, rounded to nearest tenth

Program Element (PE) number, PE name, FY16 budget line number	Req.	Authorization			Appropriation		
		HASC	SASC	Conf.	HAC	SAC	Conf.
0602114N, Power Projection Applied Research, line 4	41.4	41.4	41.4		41.4		
0602750N, Future Naval Capabilities Applied Research, line 13	165.1	165.1	165.1		157.1		
0603114N, Power Projection Advanced Technology, line 16	96.4	106.4	81.4		76.6		
0603673N, Future Naval Capabilities Advanced Technology Development, line 21	249.1	249.1	239.1		252.1		
0603925N, Directed Energy and Electric Weapon System, line 75	32.7	32.7	32.7		32.7		
0604250D8Z, Advanced Innovative Technology, line 95	844.9	804.9	844.9		844.9		

Source: Table prepared by CRS based on Navy FY17 budget submission and committee and conference reports.

Notes: HASC is House Armed Services Committee; **SASC** is Senate Armed Services Committee; **HAC** is House Appropriations Committee; **SAC** is Senate Appropriations Committee; **Conf.** is conference agreement. The PEs shown in the table below capture much but not necessarily all of the funding for work on Navy SSLs, EMRG, and HVP. The PEs shown in the table, moreover, include funding for efforts other than Navy SSLs, EMRG, and HVP.

FY2017 National Defense Authorization Act (H.R. 4909/S. 2943)

House

The House Armed Services Committee, in its report (H.Rept. 114-537 of May 4, 2016) on H.R. 4909, recommended the funding levels shown in the HASC column of **Table 1**. The recommended increase of $10 million for PE 0603114N, Power Projection Advanced Technology (line 16) is for "Program increase for common mount." (Page 498) The recommended reduction of $40 million for PE 0604250D8Z, Advanced Innovative Technology (line 95) is for "SCO" (the Strategic Capabilities Office). (Page 518) H.Rept. 114-537 states:

> *Common mount for electromagnetic railgun*
>
> The budget request contained $96.4 million in PE 63114N for power projection advanced technology. Of this amount, $15.4 million was included for the Navy's electromagnetic railgun prototype.
>
> The committee remains supportive of the Navy's program for developing and deploying an electromagnetic railgun. The committee recognizes the growing imperative for the Navy to field this type of weapon, not only to increase capabilities for naval surface fire support and ballistic missile defense, but to also decrease the cost exchange model when comparing the railgun to conventional missiles or guns. However, the committee is increasingly concerned that the shift in emphasis to the hypervelocity projectile by the Strategic Capabilities Office has left the Navy with a funding gap in developing the requirements and design for a common mount, which is a necessary prerequisite to getting this capability into operational use. Therefore, the committee directs the Secretary of the Navy to provide a briefing to the House Committee on Armed Services by February 15, 2017, on the plan and milestone schedule for demonstrating and deploying a common railgun mount for sea- and land-based applications.
>
> The committee recommends $106.4 million, an increase of $10.0 million, in PE 63114N to support the development of a common mount for the sea-based and land-based electromagnetic railgun. (Page 61)

H.Rept. 114-537 also states:

> *Strategic Capabilities Office*
>
> The budget request contained $844.9 million in PE 64250D8Z for development activities of the Strategic Capabilities Office (SCO).
>
> Created in 2012 by the Deputy Secretary of Defense, SCO has the mission to identify, analyze, demonstrate, and transition game-changing applications of existing and near-term technology to shape and counter emerging threats. SCO is comprised of a relatively small number of personnel and relies on other program office personnel and resources to execute its mission. The committee appreciates the nature of SCO's mission and sustained leanness of the organization; however, the committee notes the budget for SCO has grown exponentially each fiscal year. For example, the fiscal year 2017 budget request is nearly double the request for fiscal year 2016.
>
> The committee is concerned that such rapid budget growth may bring with it some risks, including the demands on SCO's small staff, demands on other Department of Defense personnel, and impact of SCO decisions on existing programs. For example, the committee is aware of SCO's inclusion on the electromagnetic railgun development, and subsequent reprioritizing of its planned investment in that program for fiscal year 2017, resulting in a funding gap that could not be covered by the program office.
>
> Additionally, the committee remains concerned that the transition of technologies from SCO has not been adequately captured and conveyed to the oversight committees. The report required by the committee report (H. Rept. 114–102) accompanying the National Defense Authorization Act for Fiscal Year 2016 has not been delivered and is now almost 6 months late. In order to support prudent use of taxpayer resources, and to ensure proper oversight of these activities, the committee believes this report should be provided and concerns addressed before supporting full funding of planned activities.
>
> Therefore, the committee recommends $804.9 million, a decrease of $40.0 million, in PE 64250D8Z for development activities of the Strategic Capabilities Office. (Page 92)

Section 220 of H.R. 4909 as reported states:

> SEC. 220. Designation of Department of Defense senior official with principal responsibility for directed energy weapons.
>
> Not later than 180 days after the date of the enactment of this Act, the Secretary of Defense shall—
>
> (1) designate a senior official already serving within the Department of Defense as the official with principal responsibility for the development and demonstration of directed energy weapons for the Department; and
>
> (2) set forth the responsibilities of that senior official with respect to such programs.

H.Rept. 114-537 also states:

> *Five-inch precision guided projectile development for naval surface fire support*
>
> In the committee report (H. Rept. 114–102) accompanying the National Defense Authorization Act for Fiscal Year 2016, the committee noted "that current surface Navy gunnery requirements are outdated and that new technologies such as railgun and directed energy weapons are nearing readiness for technology transition." The committee referenced the Advanced Naval Surface Fires (ANSF) initiative and noted the ANSF was assessing options for providing a near-term 5-inch guided munition capability. The committee understands this capability would provide for improved and extended-range naval surface fire support. The committee continues to support the need for this precision guided capability and is also aware of the Hypervelocity Gun Weapon System (HGWS) program that is currently under consideration by the Strategic Capabilities Office (SCO). The committee notes the HGWS program would "flip the cost equation using conventional guns to defend forward bases against raids of advanced cruise and ballistic missiles" and believes there could be applications for use in 5-inch gun systems for naval surface fires support. The committee is encouraged by the development of both of these initiatives and expects the Navy and SCO to coordinate on these capabilities. The committee also expects the Navy to proceed forward with an accelerated development and acquisition strategy for this needed capability that is consistent with acquisition reform principles. (Pages 62-63)

H.Rept. 114-537 also states:

> *Technology enablers for directed energy weapon systems*
>
> The committee is aware that the Department of Defense has made significant advances in the development and operational demonstration of directed energy weapons systems. Each military department has demonstrated a marquee program in this area, such as the Navy's Laser Weapon System deployed on the USS Ponce, the Army High Energy Laser Mobile Demonstrator, and the Marine Corps' Ground Based Air Defense System. Along with technology demonstration activities like the Robust Electric Laser Initiative and the High Energy Liquid Laser Area Defense System, each of these programs demonstrated the increased power output and power on target necessary to develop a militarily useful directed energy weapon.
>
> However, as the Department has made progress in raising the power levels of these systems, it has also demonstrated the need for emphasis on development in other technology areas necessary to realize the full potential of laser weapons. For example, higher power output requires improved beam control to engage targets at greater distances, as well as better thermal management systems to dissipate the increased heat load. As the Department has been overcoming foundational technical challenges, new challenges have emerged that will impact the operational uses for directed energy weapons.

> Therefore, the committee directs the Assistant Secretary of Defense for Research and Engineering, in coordination with the research components of the military departments and the High Energy Laser Joint Technology Office, to provide a briefing to the House Committee on Armed Services by January 20, 2017. This briefing should provide a roadmap for enabling technologies, including:
>
> (1) Beam directors and adaptive optics, including deformable mirrors;
>
> (2) Thermal management needs and capabilities;
>
> (3) Integration challenges with fire control systems, including potential
>
> future needs for fire control for laser systems;
>
> (4) Power architectures and power electronics needs;
>
> (5) Facilities and test range capabilities; and
>
> (6) Other areas as deemed by the Secretary. (Page 93)

Senate

The Senate Armed Services Committee, in its report (S.Rept. 114-255 of May 18, 2016) on S. 2943, recommended the funding levels shown in the SASC column of **Table 1**. The recommended reduction of $15 million to PE 0603114N, Power Projection Advanced Technology (line 16) is for "General decrease." (Page 481) The recommended reduction of $10 million to PE 0603673N, Future Naval Capabilities Advanced Technology Development (line 21) is for "Capable manpower, and power and energy." (Page 481).[51] S.Rept. 114-255 states:

> **Power projection advanced technology**
>
> The budget request included $96.4 million in PE 63114N for power projection advanced technology. The committee notes that the Navy, Air Force, Defense Advanced Research Projects Agency, Strategic Capabilities Office, and other elements within the Department of Defense are all pursuing advanced power projection technologies and systems. The committee is concerned that these efforts are not well-coordinated and have uncertain pathways for transition to programs of record. In addition, the committee notes that the budget request represents an almost 200 percent increase over the amount enacted for fiscal year 2016. The committee believes that such a large increase in budget is not warranted and is concerned about the ability of the programs to absorb the additional funding. Consequently, the committee recommends a decrease of $15.0 million in PE 63114N, but directs that this reduction not be assessed against solid state laser maturation efforts. (Page 52)

Section 216 of S. 2943 as reported states:

---

[51] This recommended reduction of $10 million does not appear to relate (at least not directly) to lasers, the electromagnetic railgun, or the HVP. S.Rept. 114-255 states:

> **Capable manpower and power and energy**
>
> The budget request included $249.1 million in PE 63673N for future naval capabilities advanced technology developments. The activities listed under this program element include capable manpower and power and energy. The committee believes that the work plans for fiscal year 2017 on these activities does not warrant the level of funding included in the budget request. For example, the committee notes that the research included in these two projects include development of new personnel and management methodologies, and capabilities in energy security. Both of these efforts could be better coordinated with other organizations performing similar research. Consequently, the committee recommends a decrease of $10.0 million in PE 63673N to be distributed appropriately from capable manpower and power and energy. (Page 53)

SEC. 216. Directed energy weapon system programs.

(a) Inclusion of Directed Energy Weapon System programs in the rapid acquisition authority program.—

(1) IN GENERAL.—Section 806(c)(1) of the Bob Stump National Defense Authorization Act for Fiscal Year 2003 (Public Law 107–314; 10 U.S.C. 2302 note) is amended by adding at the end the following new subparagraph:

"(D) (i) In the case of any supplies and associated support services that, as determined in writing by the Secretary of Defense without delegation, are urgently needed to eliminate a deficiency in directed energy weapon systems, the Secretary may use the procedures developed under this section in order to accomplish the rapid acquisition and deployment of needed offensive or defensive directed energy weapon systems capabilities, supplies, and associated support services.

"(ii) For the purposes of directed energy weapon systems acquisition, the Secretary of Defense shall consider use of the following procedures:

"(I) The rapid acquisition authority provided under this section.

"(II) Use of other transactions authority provided under section 2371 of title 10, United States Code.

"(III) The acquisition of commercial items using simplified acquisition procedures.

"(IV) The authority for procurement for experimental purposes provided under section 2373 of title 10, United States Code.

"(iii) In this subparagraph, the term 'directed energy weapon systems' means military action involving the use of directed energy to incapacitate, damage, or destroy enemy equipment, facilities, or personnel.".

(2) CONFORMING AMENDMENTS.—Section 2373 of title 10, United States Code, is amended—

(A) in subsection (a), by striking "and aeronautical supplies" and inserting ", aeronautical supplies, and directed energy weapon systems"; and

(B) by adding at the end of the following new subsection:

"(c) Directed energy weapon systems defined.—In this section, the term 'directed energy weapon systems' means military action involving the use of directed energy to incapacitate, damage, or destroy enemy equipment, facilities, or personnel.".

(b) Joint Directed Energy Program Office.—

(1) REDESIGNATION.—The High Energy Laser Joint Technology Office of the Department of Defense is hereby redesignated as the "Joint Directed Energy Program Office" (in this subsection referred to as the "Office").

(2) STRATEGIC PLAN FOR DEVELOPMENT AND FIELDING OF DIRECTED ENERGY WEAPONS CAPABILITIES.—In addition to the functions and duties of the Office in effect on the day before the date of the enactment of this Act, the Office shall develop a strategic plan for development and fielding of directed energy weapons capabilities for the Department, in which the Office may define requirements for directed energy capabilities that address the highest priority warfighting capability gaps of the Department.

(3) ACCELERATION OF DEVELOPMENT AND FIELDING OF DIRECTED ENERGY WEAPONS CAPABILITIES.—

(A) IN GENERAL.—To the degree practicable, the Office shall use the policies of the Department that are revised pursuant to this section and new acquisition and management

> practices established pursuant to this section to accelerate the development and fielding of directed energy capabilities.
>
> (B) ENGAGEMENT.—The Secretary shall ensure that use of policies and practices described in subparagraph (A) include engagement with defense and private industries, research universities, and unaffiliated, nonprofit research institutions.

Regarding Section 216, S.Rept. 114-255 states:

> **Directed energy weapon system programs (sec. 216)**
>
> The committee remains concerned about the Department of Defense's inability to field an operational directed energy system. The committee is aware that the military services and industry partners have developed sufficient directed energy weapon capabilities for specific scenarios—like the High Energy Laser Mobile Demonstrator (HEL–MD) to counter rocket, artillery and mortar for base protection purposes and the Counter Electronics High Powered Microwave Advanced Missile Project (CHAMP) for disabling an adversary's electronics while avoiding collateral damage. These programs, as well as other high energy laser weapon systems, have been tested and demonstrated, but have failed to transition to acquisition programs of record.
>
> The committee notes that directed energy capabilities have the potential to support many operational missions in cost effective and efficient manners. In response to these factors, the committee recommends a provision that would amend section 806 of the Bob Stump National Defense Authorization Act for Fiscal Year 2003 (Public Law 107–314) to grant rapid acquisition authorities for directed energy weapon systems to accelerate the development and fielding of this technology and to help offset the gains of potential adversaries.
>
> The committee notes that since 1960, the Department of Defense has invested more than $6.0 billion in directed energy science and technology initiatives. However, the committee remains concerned that, despite this significant investment, the Department's directed energy initiatives are not resourced at levels necessary to transition them to full-scale acquisition programs. The committee notes with concern that years of investment have not to date resulted in any operational systems with high energy laser capability.
>
> The committee highlights that the Defense Science Board Task Force on Directed Energy Weapon Systems and Technology Applications found that "directed energy offers promise as a transformational 'game changer' in military operations, able to augment and improve operational capabilities in many areas." The task force further concluded that the range of potential applications is sufficient to warrant significantly increased attention to the scope and direction of efforts to assess, develop, and field appropriate laser, microwave, and millimeter wave weapons. Consistent with the findings of the task force, the committee believes that directed energy weapons systems offer significant benefits in terms of cost effectiveness, sustainability, magazine capabilities, and precision targeting. (Pages 46-47)

S.Rept. 114-255 also states:

> **High energy laser joint technology office**
>
> The budget request included $42.3 million in PE 62890F for high energy laser research. The committee notes that this program element funds defense high energy laser applied research through the High Energy Laser Joint Technology Office. However, the committee is concerned that the Joint Technology Office has not received sufficient funding in recent years to drive the maturation of high energy laser technology. As an example, the committee notes with concern that no laser technologies have yet been fielded or deployed, despite promising development and field tests. Given the importance of directed energy weapons systems in general as noted elsewhere in this Act, and of high energy laser systems in particular, the committee is concerned that budget request for this

> program element will be insufficient for supporting the joint technology office. Accordingly, the committee recommends an increase of $5.0 million in PE 62890F for the high energy laser joint technology office. (Pages 54-55)

S.Rept. 114-255 also states:

> **Directed energy systems prototyping**
>
> The budget request included no money in PE 64342D8Z for defense technology offsets. The committee notes with disappointment that the administration did not view it as a priority to request funds through this program element. Particularly with the high-profile emphasis placed on the Department of Defense's Third Offset Strategy, the committee is disappointed to see this program be unfunded. In addition, as noted elsewhere in this report, the committee is deeply disappointed with how the technology offset funding enacted in fiscal year 2016 was allocated. As noted, none of the money was put towards directed energy, in contradiction to the clear intent of Congress that half of the money be used to bolster directed energy technologies. While the committee does not recommend additional unrestricted funds for the technology offsets program, the committee underscores that directed energy systems are still critical areas of work in need of greater support and attention. The committee believes that the Department needs to focus in particular on the transition from lab development to deployment and fielding. Consequently, the committee recommends a general increase of $25.0 million in PE 64342D8Z to be used only for the purposes of directed energy systems prototyping. (Pages 59-60)

S.Rept. 114-255 also states:

> **Laser weapon system demonstrator**
>
> The Committee commends the Navy for initiating and funding the Laser Weapon Systems Demonstrator (LWSD) and believes that this is an important step toward maturing technologies that could ultimately enable the deployment of a shipboard maritime laser weapons system. While the Committee understands that the Navy envisions transitioning laser weapons to a formal Program of Record in the 2020s, it appears that the Navy has not programmed funding beyond the LWSD sea-based tests to support the installation of LWSD on a DDG or for the design and procurement of a formal maritime laser program.
>
> The committee expects that the Secretary of the Navy will keep the congressional defense committees updated on its plan to seamlessly transition the LWSD to a shipboard weapons system following sea-based testing and to a formal maritime laser Program of Record, technical progress toward developing the capability, and programmatic steps being taken to move to demonstration and deployment of advanced laser systems. (Page 70)

FY2017 DOD Appropriations Act (H.R. 5293)

House

The House Appropriations Committee, in its report (H.Rept. 114-577 of May 19, 2016) on H.R. 5293, recommended the funding levels shown in the HAC column of **Table 1**. The recommended reduction of $8 million to PE 0602750N, Future Naval Capabilities Applied Research (line 13) is for "FORCENET excessive growth" ($5 million), "Power and energy previously funded efforts" ($2 million), and "Sea shield previously funded efforts" ($1 million). (Page 228) The recommended reduction of $19.8 million to PE 0603114N, Power Projection Advanced Technology (line 16) is for "Precision strike technology excess growth." (Page 228) The recommended net reduction of $3 million to PE 0603673N, Future Naval Capabilities Advanced

Technology Development (line 21) consists of a reduction of $2 million for “Power and energy previously funded efforts,” a reduction of $2 million for “Sea shield previously funded efforts,” and an increase of $7 million for “Program increase—ASW [antisubmarine warfare] research.” (Page 228)

H.Rept. 114-577 states:

> HIGH ENERGY LASERS
>
> The Committee is aware of efforts within the High Energy Laser Joint Technology Office to develop advanced, directed-energy, high energy laser weapons that have the potential to perform a wide variety of military missions. The Committee encourages the Secretary of Defense to explore further development and evaluation of this important technology. (Page 264)

Directed Energy Weapon Systems Acquisition Act of 2016 (H.R. 4964/S. 2778)

House

H.R. 4964 was introduced in the House on May 5, 2016. The text of H.R. 4964 as introduced states:

> SECTION 1. Short title.
>
> This Act may be cited as the “Directed Energy Weapon Systems Acquisition Act of 2016”.
>
> SEC. 2. Findings.
>
> Congress makes the following findings:
>
> (1) The Committee on Armed Services of the Senate noted in the report accompanying S. 1356 (S. Rept. 114–49; 114th Congress) that since 1960, the Department of Defense has invested more than $6,000,000,000 in directed energy science and technology initiatives, and that the Committee is concerned that, despite this significant investment, the Department's directed energy initiatives are not resourced at levels necessary to transition them to full-scale acquisition programs.
>
> (2) The Defense Science Board Task Force on Directed Energy Weapon Systems and Technology Applications (the “Task Force”) found that “directed energy offers promise as a transformational ‘game changer’ in military operations, able to augment and improve operational capabilities in many areas”.
>
> (3) Despite this potential, years of investment have not resulted in any operational systems with high energy laser capability.
>
> (4) The Task Force believes that the range of potential application is sufficient to warrant significantly increased attention to the scope and direction of efforts to assess, develop, and field appropriate laser, microwave, and millimeter wave weapons.
>
> SEC. 3. Inclusion of directed energy weapon system programs in the rapid acquisition authority program.
>
> (a) In general.—Section 806(c)(1) of the Bob Stump National Defense Authorization Act for Fiscal Year 2003 (Public Law 107–314; 10 U.S.C. 2302 note) is amended by adding at the end the following new subparagraph:
>
> “(D) (i) In the case of any supplies and associated support services that, as determined in writing by the Secretary of Defense without delegation, are urgently needed to eliminate

> a deficiency in directed energy weapon systems, the Secretary may use the procedures developed under this section in order to accomplish the rapid acquisition and deployment of needed offensive or defensive directed energy weapon systems capabilities, supplies, and associated support services.
>
> "(ii) For the purposes of directed energy weapon systems acquisition, the Secretary of Defense shall consider use of the following procedures:
>
> "(I) The rapid acquisition authority provided under this section.
>
> "(II) Use of other transactions authority provided under section 2371 of title 10, United States Code.
>
> "(III) The acquisition of commercial items using simplified acquisition procedures.
>
> "(IV) The authority for procurement for experimental purposes provided under section 2373 of title 10, United States Code.
>
> "(iii) In this subparagraph, the term 'directed energy weapon system' means military action involving the use of directed energy to incapacitate, damage, or destroy enemy equipment, facilities, or personnel.".
>
> (b) Conforming amendments.—Section 2373 of title 10, United States Code, is amended—
>
> (1) in subsection (a), by striking "and aeronautical supplies" and inserting ", aeronautical supplies, and directed energy weapon systems"; and
>
> (2) by adding at the end of the following new subsection:
>
> "(c) Directed energy weapon system defined.—In this section, the term 'directed energy weapon system' means military action involving the use of directed energy to incapacitate, damage, or destroy enemy equipment, facilities, or personnel.".
>
> SEC. 4. Joint Directed Energy Program Office.
>
> (a) Redesignation.—The High Energy Laser Joint Technology Office of the Department of Defense is hereby redesignated as the "Joint Directed Energy Program Office" (in this section referred to as the "Office").
>
> (b) Strategic plan for development and transition of directed energy weapons capabilities toward fielding.—In addition to the functions and duties of the Office in effect on the day before the date of the enactment of this Act, the Office shall develop a strategic plan for development and transition of directed energy weapons capabilities toward fielding for the Department, in which the Office may define requirements for directed energy capabilities that address the highest priority warfighting capability gaps of the Department.
>
> (c) Acceleration of development and transition of directed energy weapons capabilities toward fielding.—
>
> (1) IN GENERAL.—To the degree practicable, the Office shall use the policies of the Department that are revised pursuant to this Act and new acquisition and management practices established pursuant to this Act to accelerate the development and transition of directed energy capabilities toward fielding.
>
> (2) ENGAGEMENT.—The Secretary shall ensure that use of policies and practices described in paragraph (1) include engagement with defense and private industries, research universities, and unaffiliated, nonprofit research institutions.

Senate

S. 2778 was introduced in the Senate on April 12, 2016. The text of S. 2778 as introduced states:

SECTION 1. Short title.

This Act may be cited as the “Directed Energy Weapon Systems Acquisition Act of 2016”.

SEC. 2. Findings.

Congress makes the following findings:

(1) The Committee on Armed Services of the Senate noted in the report accompanying S. 1356 (S. Rept. 114–49; 114th Congress) that since 1960, the Department of Defense has invested more than $6,000,000,000 in directed energy science and technology initiatives, and that the Committee is concerned that, despite this significant investment, the Department's directed energy initiatives are not resourced at levels necessary to transition them to full-scale acquisition programs.

(2) The Defense Science Board Task Force on Directed Energy Weapon Systems and Technology Applications (the “Task Force”) found that “directed energy offers promise as a transformational ‘game changer’ in military operations, able to augment and improve operational capabilities in many areas”.

(3) Despite this potential, years of investment have not resulted in any operational systems with high energy laser capability.

(4) The Task Force believes that the range of potential application is sufficient to warrant significantly increased attention to the scope and direction of efforts to assess, develop, and field appropriate laser, microwave, and millimeter wave weapons.

SEC. 3. Inclusion of directed energy weapon system programs in the rapid acquisition authority program.

(a) In general.—Section 806(c)(1) of the Bob Stump National Defense Authorization Act for Fiscal Year 2003 (Public Law 107–314; 10 U.S.C. 2302 note) is amended by adding at the end the following new subparagraph:

“(D) (i) In the case of any supplies and associated support services that, as determined in writing by the Secretary of Defense without delegation, are urgently needed to eliminate a deficiency in directed energy weapon systems, the Secretary may use the procedures developed under this section in order to accomplish the rapid acquisition and deployment of needed offensive or defensive directed energy weapon systems capabilities, supplies, and associated support services.

“(ii) For the purposes of directed energy weapon systems acquisition, the Secretary of Defense shall consider use of the following procedures:

“(I) The rapid acquisition authority provided under this section.

“(II) Use of other transactions authority provided under section 2371 of title 10, United States Code.

“(III) The acquisition of commercial items using simplified acquisition procedures.

“(IV) The authority for procurement for experimental purposes provided under section 2373 of title 10, United States Code.

“(iii) In this subparagraph, the term ‘directed energy weapon system’ means military action involving the use of directed energy to incapacitate, damage, or destroy enemy equipment, facilities, or personnel.”.

(b) Conforming amendments.—Section 2373 of title 10, United States Code, is amended—

(1) in subsection (a), by striking “and aeronautical supplies” and inserting “, aeronautical supplies, and directed energy weapon systems”; and

(2) by adding at the end the following new subsection:

"(c) Directed energy weapon system defined.—In this section, the term 'directed energy weapon system' means military action involving the use of directed energy to incapacitate, damage, or destroy enemy equipment, facilities, or personnel.".

SEC. 4. Joint Directed Energy Program Office.

(a) Redesignation.—The High Energy Laser Joint Technology Office of the Department of Defense is hereby redesignated as the "Joint Directed Energy Program Office" (in this section referred to as the "Office").

(b) Strategic plan for development and transition of directed energy weapons capabilities toward fielding.—In addition to the functions and duties of the Office in effect on the day before the date of the enactment of this Act, the Office shall develop a strategic plan for development and transition of directed energy weapons capabilities toward fielding for the Department, in which the Office may define requirements for directed energy capabilities that address the highest priority warfighting capability gaps of the Department.

(c) Acceleration of development and transition of directed energy weapons capabilities toward fielding.—

(1) IN GENERAL.—To the degree practicable, the Office shall use the policies of the Department that are revised pursuant to this Act and new acquisition and management practices established pursuant to this Act to accelerate the development and transition of directed energy capabilities toward fielding.

(2) ENGAGEMENT.—The Secretary shall ensure that use of policies and practices described in paragraph (1) include engagement with defense and private industries, research universities, and unaffiliated, nonprofit research institutions.

Appendix. Potential Advantages and Limitations of Shipboard Lasers

This appendix presents additional information on potential advantages and limitations of shipboard lasers.

Potential Advantages

In addition to a low marginal cost per shot and deep magazine, potential advantages of shipboard lasers include the following:

- **Fast engagement times.** Light from a laser beam can reach a target almost instantly (eliminating the need to calculate an intercept course, as there is with interceptor missiles) and, by remaining focused on a particular spot on the target, cause disabling damage to the target within seconds. After disabling one target, a laser can be redirected in several seconds to another target.
- **Ability to counter radically maneuvering missiles.** Lasers can follow and maintain their beam on radically maneuvering missiles that might stress the maneuvering capabilities of Navy SAMs.
- **Precision engagements.** Lasers are precision-engagement weapons—the light spot from a laser, which might be several inches in diameter, affects what it hits, while generally not affecting (at least not directly) separate nearby objects.
- **Graduated responses.** Lasers can perform functions other than destroying targets, including detecting and monitoring targets and producing nonlethal effects, including reversible jamming of electro-optic (EO) sensors. Lasers offer the potential for graduated responses that range from warning targets to reversibly jamming their systems, to causing limited but not disabling damage (as a further warning), and then finally causing disabling damage.

Potential Limitations

Potential limitations of shipboard lasers include the following:

- **Line of sight.** Since laser light tends to fly through the atmosphere on an essentially straight path, shipboard lasers would be limited to line-of-sight engagements, and consequently could not counter over-the-horizon targets or targets that are obscured by intervening objects. This limits in particular potential engagement ranges against small boats, which can be obscured by higher waves, or low-flying targets. Even so, lasers can rapidly reacquire boats obscured by periodic swells.
- **Atmospheric absorption, scattering, and turbulence.** Substances in the atmosphere—particularly water vapor, but also things such as sand, dust, salt particles, smoke, and other air pollution—absorb and scatter light from a shipboard laser, and atmospheric turbulence can defocus a laser beam. These effects can reduce the effective range of a laser. Absorption by water vapor is a particular consideration for shipboard lasers because marine environments feature substantial amounts of water vapor in the air. There are certain wavelengths of light (i.e., "sweet spots" in the electromagnetic spectrum) where atmospheric absorption by water vapor is markedly reduced. Lasers can be

designed to emit light at or near those sweet spots, so as to maximize their potential effectiveness. Absorption generally grows with distance to target, making it in general less of a potential problem for short-range operations than for longer-range operations. Adaptive optics, which make rapid, fine adjustments to a laser beam on a continuous basis in response to observed turbulence, can counteract the effects of atmospheric turbulence. Even so, lasers might not work well, or at all, in rain or fog, preventing lasers from being an all-weather solution.

- **Thermal blooming.** A laser that continues firing in the same exact direction for a certain amount of time can heat up the air it is passing through, which in turn can defocus the laser beam, reducing its ability to disable the intended target. This effect, called thermal blooming, can make lasers less effective for countering targets that are coming straight at the ship, on a constant bearing (i.e., "down-the-throat" shots). Other ship self-defense systems, such as interceptor missiles or a CIWS, might be more suitable for countering such targets. Most tests of laser systems have been against crossing targets rather than "down-the-throat" shots. In general, thermal blooming becomes more of a concern as the power of the laser beam increases.
- **Saturation attacks.** Since a laser can attack only one target at a time, requires several seconds to disable it, and several more seconds to be redirected to the next target, a laser can disable only so many targets within a given period of time. This places an upper limit on the ability of an individual laser to deal with saturation attacks—attacks by multiple weapons that approach the ship simultaneously or within a few seconds of one another. This limitation can be mitigated by installing more than one laser on the ship, similar to how the Navy installs multiple CIWS systems on certain ships.
- **Hardened targets and countermeasures.** Less-powerful lasers—that is, lasers with beam powers measured in kilowatts (kW) rather than megawatts (MW)—can have less effectiveness against targets that incorporate shielding, ablative material, or highly reflective surfaces, or that rotate rapidly (so that the laser spot does not remain continuously on a single location on the target's surface) or tumble. Small boats (or other units) could employ smoke or other obscurants to reduce their susceptibility to laser attack.[52] Measures such as these, however, can increase the cost and/or weight of a weapon, and obscurants could make it more difficult for small boat operators to see what is around them, reducing their ability to use their boats effectively.
- **Risk of collateral damage to aircraft, satellites, and human eyesight.** Since light from an upward-pointing laser that does not hit the target would continue flying upward in a straight line, it could pose a risk of causing unwanted collateral damage to aircraft and satellites. The light emitted by SSLs being developed by the Navy is of a frequency that can cause permanent damage to human eyesight, including blinding. Blinding can occur at ranges much greater than ranges for damaging targeted objects. Scattering of laser light off the target or off fog or particulates in the air can pose a risk to exposed eyes.[53]

---

[52] See, for example, "Kelsey D. Atherton, "China Plans To Defeat American Lasers With Smoke," *Popular Science*, May 3, 2016.

[53] The United States in 1995 ratified the 1980 Convention on Prohibitions or Restriction on the Use of Certain Conventional Weapons Which May be Deemed to be Excessively Injurious or to Have Indiscriminate Effects. An (continued...)

For additional background information on potential Navy shipboard SSLs, see CRS Report R41526, *Navy Shipboard Lasers for Surface, Air, and Missile Defense: Background and Issues for Congress*, by Ronald O'Rourke.

Author Contact Information

Ronald O'Rourke
Specialist in Naval Affairs
rorourke@crs.loc.gov, 7-7610

(...continued)

international review of the convention began in 1994 and concluded in May 1996 with the adoption of, among other things, a new Protocol IV on blinding laser weapons. The protocol prohibits the employment of lasers that are specifically designed to cause permanent blindness to the naked eye or to the eye with corrective eyesight devices. The United States ratified Protocol IV on December 23, 2008, and it entered into force for the United States on July 21, 2009. DOD views the protocol as fully consistent with DOD policy. DOD believes the lasers discussed in this report are consistent with DOD policy of prohibiting the use of lasers specifically designed to cause permanent blindness to the naked eye or to the eye with corrective eyesight devices. For further discussion, see Appendix I ("Protocol on Blinding Lasers") in CRS Report R41526, *Navy Shipboard Lasers for Surface, Air, and Missile Defense: Background and Issues for Congress,* by Ronald O'Rourke.

Torpedo & Directed Energy Weapons Indian Navy Perspective

RAdm Om Prakash Singh Rana, VSM,
Director General of Naval Armament Inspection



IN **supporting Indigenisation**

IN **Indigenisation Plan 2015-30**

Maritime Cap Perspective Plan

Self-Reliance



90%

Float

50-60%

Move

Fight

30%

Scope

MAD
RF
Sonobuoy
Lightweight Torpedo
Decoy
HMS
Lightweight Torpedo
TAS
Decoy
Dipping Sonar
Sonobuoy
Lightweight Torpedo

- Torpedo & Directed Energy Weapons
  - – Technological advancement
  - – Availability
- QRs for Torpedo & DEWs
- Way Ahead

Advancement
in
Torpedo Technology

Torpedo…….

Advancement in Torpedo Technology Contd...



- Broadband sonar, multi-beam & INS
- Multi target tracking capability
- S/W based & high speed sig processing
- Re-programmable S/W & search pattern
- ACCM features
- Digital servo and retractable controls

Torpedo…….

Advancement in Torpedo Technology Contd...

- Al-Ag_2O, Li-ion & Cu-Ni batteries



- Brushless motor & pump jet propulsion


How Supercavitation Works
SUPERCAVITY
GUIDANCE WIRE
SHKVAL TORPEDO

- Semi open/close loop thermal propulsion
- Super-cavitation propulsion



- Tandem shaped charge insensitive W/H

Advance Torpedoes

Torpedo	Origin	Speed (Kts)	Range (Kms)
Black Shark Adv	Italy	18- 50	>50
DM2 A4 Sea Hake	Ger	50	> 50
A244S MOD-3	Italy	36	13.5
Flash Black	Italy	50	20
F21 HWT	France	25-50	> 50
Spearfish HWT	UK	40	48
Torpedo (2000)	Swed	40	> 40
MU-90	Eutorp	50	23
MK 48 ADCAP	USA	55	38
MK 54	USA	28 -43	12
Shkval E	Russia	> 200	7 - 10
UGST	Russia	50	40

SeaHake
A·244/S mod.3
F21

Torpedoes in Indian Navy

Torpedo		Origin/ Country
A244S		Italy
AT1ME		Russian
MK 54		USA
TAL MK-I		India
53-65 KE		Russian
CET 65 E		Russian
TEST 71ME		Russian
SUT		Germany
Varunastra		India

Directed Energy Weapons

Directed Energy Weapons



- Emit high energy beam
- High power microwaves
- High energy laser

DEW Advantages

- High Speed of Engagement
- Effective for Defensive/Offensive Role
- Immunity from Gravitation Constraints
- Space Requirement – Limited
- Effective against Moving Air Targets
- Minimal Collateral Damage
- Low Marginal Cost per Shot


High Energy Laser (HEL)
on Rocket from 1.6km away

DEWs from Sea, Air & Land Platforms

HE Laser Mobile Demonstrator
(USA)

Electromag Rail Gun
(USA)

Active Denial System
(USA/ Israel)



Airborne Ballistic Laser
(USA)



Vigilant Eagle
(USA)

Laser Weapon System
(USA)

DEWs in Indian Navy

DEWs not as potential destroyer

10 KW HEL demonstrated by DRDO

Work in progress for 25 KW HEL

Develop 100-500 KW HEL

Qualitative Requirements (QRs)

QRs….

QRs for Torpedoes

Require-ment	**Remark**
Speed	Upto 55 Knot with variable speed
Range	Upto 40 Kms
Battery	$Mg\text{-}Cu_2Cl_2$, $Al\text{-}Ag_2O$ & Li-ion batteries
Propulsion	Gas turbine, brushless motor & super-cavitation
Warhead	Tandem insensitive munition W/H & prox EBW fuze
Guidance	CBASS & improved signal processing algorithm
Launch I/ P	Tactical S/W algorithm with target data & upgrades
Control	Intelligent digital controllers & actuators
Camouflage	ACCM features

QRs for DEWs

- 10-25 KW for non-lethal engagement
- 100-500 KW against:-
  - Missile
  - Rocket
  - Aircraft
  - UAVs

Way Ahead

Way Ahead….

Joint Venture

Requirement	**Scope for Designers & Industry**
Torpedo & Sub-systems	
Mech Parts, W/H & Prop	Al-Mg alloy, FRP & nano materials, **IM**, Mg-Cu, Al-Ag$_2$O & Li-ion batteries, brushless motor, GT, pump jet & supercavitation prop
Guidance & Control	Sonar imaging & det, CABSS, PCBs, tgt wake seeking, mag anomaly det & super quantum induction device homing, adv accl & sensors.
Process Control	Adv sig processing, tact S/W algorithm for tgt data, friendly forces positions, sound profile & mid-course upgrade, dig ctrl & actuator
Miscellaneous	Fibre optic cable, gene, invertor, shaft, bearing, gear box, bottle, gyro, pump, valve, fastener, cable, pipe, dynamic seal, loc & rec aids
Directed Energy Weapons	
DEW Systems	Ship borne 25-500 KW using High Power Microwaves or Lasers for non-lethal & lethal engagement

Way Ahead….



Government Policies

Staff Requirement

Design Agency

Industry Initiatives

Test Facilities

Life Cycle Management

Interface with Industry

Conclusion

- Govt promulgated various major policy guidelines
- ***IN*** "Indigenisation & MCPP"
- Harnessing knowledge base, infrastructures for "**Make in India**" prg under "**FIGHT**" category
- DEWs identified as core mil technology requirement
- Opportunities for strategic partnership

Thank You

5. Psychoenergetics

Mental entrainment, inducing hypnogogic trance, mind control, broadcasting thoughts and feelings, the Ant World, education via EM [LW] mental download, the "Feelies," revolution in spirituality, "enlightenment machine?" Scalar churches?

Psychoenergetics is simply *using the scalar interferometers to manipulate and engineer the human psyche*. To me it is the most mind-boggling and frightening aspect of longitudinal wave engineering.

The mind is electromagnetic in nature, and itself of the time-domain. It is not observable in 3-space. There is nothing you can point to that is the mind. As Bearden says, "The mind is time-like."

The longitudinal scalar EM waves are also of the time-domain. By overlaying certain infolded patterns (oscillations in time) on the longitudinal waves, a thought or feeling may be made to arise in a person or persons who are in the interference zone (where the wave beams cross).

The person will not notice anything, feeling that this thought or idea is his or her own idea. The longitudinal wave pattern might be a wave of panic or fear that spontaneously sweeps over you, perhaps inexplicably. It could even be in the form of a sudden intense patriotism. It could be explicit words and phrases, which everyone would think they had thought of by themselves. Or it could be rage and hatred, angry and violent. On the other hand It could also be a continuous sense of docility and placidity. This is the brave new world of *psychoenergetics and the coming "Mind Wars."*

Scalar Psychoenergetics in its most primitive form simply "entrains" all minds in the target area into a deep hypnogogic trance. In this state of mind people would be suddenly extremely suggestible, and would likely believe anything they are told, and would obey any orders given. Talk about winning the hearts and minds of the American People!

Tom Bearden makes me think of Paul Revere, who heroically conveyed important warnings for the sake of the new nation. But the words of the famous phrase have now strangely and curiously mutated into the once-inconceivable: "One if by land, Two if by mind."

Indeed one strategy in a Mind War would be to simply take over the minds of the "leaders" of the enemy nation. The targeted leader would not be aware that anything was amiss, although he might begin to make unexpected changes in policy.

And are, in fact, any of our "leaders" already having secret thoughts that are not their own? Who knows? Frighteningly, we can no longer be sure.

The new sciences of scalar electromagnetics and psychoenergetics are even now plunging humanity into a sudden science-fiction-like world beyond anything in humanity's previous imaginings.

> "The Russians reached the point in the mid 1990s that they could take over control of a person's mind, with modified longitudinal EM waves including some time-polarized EM waves, and with a team of specialists (estimate 25-30 per transmitter, and one transmitter and team per controlled person)."
> **Bearden: http://www.cheniere.org/misc/time.htm**

In a slide (below image) **Bearden** illustrates how a Scalar War would involve a psychoenergetics attack on the operators of the enemy scalar installation, entraining their minds into hypnogogic trance and getting them to shut down their systems.


COUNTERING AN INSANE QP WEAPON:
Quantum Potential Psychoenergetics
Strike Mentally Controls All Personnel
CONTROLLED PERSONNEL DISABLE INSANE QP SYSTEM
(FOLLOWED BY PERSONNEL KILL OF ENTIRE CADRE BY MINDSNAPPER)
ELECTRICAL DREAMTHINKING ARISES DIRECTLY IN BRAIN, HENCE IN MIND, BYPASSING SENSOR INPUTS
Effects arise in local spacetime, simultaneously in all minds in the targeted area
INSTANT HYPNOGOGIC STATE, WITH INSERTED DREAM THINKING
© 1996 T.E. BEARDEN
INSTANT HYPNOGOGIC STATE: WITH WAKING DREAM
PERCEIVED REALITY NOW CONTROLLED
TARGETED CADRES
MINDS ARE INSTANTLY PLACED INTO WAKING -- BUT DEEP -- HYPNOGOGIC TRANCE STATE. INSERTED THOUGHTS ANALOGOUS TO HYPNOTIST. PERSONNEL FUNCTION IN AN ALTERED, COMPLETELY CONTROLLED PERCEIVED REALITY.
Indicators: Captain Button's lengthy A-10 incident in 1997, LIDA device since 1950s.

And ultimately psychoenergetic warfare goes to the very heart of human identity itself.

For if my thoughts might no longer be "mine,"

- Then who and what am I?
- Can my very sense of being "me" be hijacked by some nefarious psychoenergetic scheme?
- Will the "secret government" eventually dictate directly into your mind how you feel about yourself?
- Or what you think you are?
- Or what you should do?

How Does Longitudinal EM Mind Control Work?

The physics of **scalar psychoenergetics** as expounded by **Col. Bearden** seems even more arcane and over-my-head than that of extracting energy from the vacuum. I can't understand it, but I look through it anyway. Each time another tiny understanding might occur, or a term might fall into place. I know the mathematics is forever beyond me.

One paper to begin with is **Mind Control** and **EM Wave Polarization Transductions.** This is such serious stuff that **Bearden** includes a strong warning about misuse of this knowledge.

Psychoenergetics weapons can mentally maim and physically kill.

Warning!

(From "Mind Control and EM Wave Polarization Transductions")

> "This article refers to experimental research techniques which can be detrimental or lethal in the hands of any but highly skilled, qualified experimental scientists proceeding under proper laboratory safety procedures. The purpose of this article is strictly for information to properly qualified and authorized scientists in certified laboratories.
>
> We do not propose or condone any use of these procedures for non-approved practice of medicine without a license. Neither the publisher nor the author are responsible for accidents or outcomes in the use of these experimental procedures and techniques. Any researcher who performs these procedures and experiments is acting on his or her own volition, and is solely responsible for insuring safety, qualifications, and legality of the acts and their results.
>
> We neither suggest nor condone unauthorized experimentation on human subjects. Such is a criminal violation of the constitutional rights of the subject under Federal and State laws, and is both illegal and immoral."
> **Bearden: http://www.cheniere.org/explore articles/mind control1/p01.htm**

After the serious warning comes the description of the paper. This is heady stuff for the layman.

> "Calling full attention to the special note above, in this paper we present a high-level overview of the novel electromagnetic nature of mind operations, mind and body coupling, and intent - the induction of physical 3-space EM energy changes into the brain and nervous system, and into every cell of the body, from the mind’s time-like coherent operations.
>
> We summarize the time-polarized electrodynamics used to engineer and affect mind operations and the mind-body coupling loop. Transaction mechanisms whereby differing EM wave polarization s can be transformed one-into-the-other are presented."
> **Bearden: http://www.cheniere.org/explore articles/mind control1/p01.htm**

I will leave it to the technically astute to try to understand the mechanisms of operation which are described in scientific language. But there are tidbits for the layman.

Here he speaks of the difficulty Western scientists have in opening up to the "immaterial" *(longitudinal wave)* nature of the human mind.

Western Science Remains Largely Materialistic

> "Ironically, most Western scientists are materialists and consider "mind" as a mystical and nonscientific concept. They tend to consider mind operations and functions either to be simply "meat computer" operations and functions, or at best to be very weak ordinary transverse-wave EM operations and functions in the brain and nervous system. This serious self-limitation exists because in the body we measure only weak TW [transverse wave] EM operations and functions correlated to biological behavior and brain operations. We simply do not know how to measure "mind operations" directly.
>
> "With no mind measurements possible and no instruments, it is understandable that Western science considers only the physical side of the mind-matter interface.
>
> "Presently our scientists do not measure the longitudinally-polarized EM wave operations and functions in the body and around it in nature. Few of them are aware that a maelstrom of such LW [longitudinal wave] functions exist in the body and in all of nature in general."
> Bearden: http://www.cheniere.org/explore articles/mind control1/p05.htm

Western methods of influencing the mind with EM waves have only used transverse waves, not the longitudinal waves of the vacuum.

If only transverse waves are used one pretty well has to hit the target mind with a sledgehammer of waves.

Western Science knows only transverse EM waves

Brute Forcing Time Functions versus Fine Control Methods

> "Ironically, Western mind control researchers using transverse EM waves for mind control research, are using a brute force method of evoking and using vacuum engines (spacetime curvature engines) and a special form of general relativity, although they do not appear to realize it.
>
> "While KGB scientists also use TW EM "brute force", TW waves when necessary, they do "imprint" or "activate" those waves with the desired internal LW and time-polarized EM wave and photon structures required to directly perform the mind engineering desired...
> Bearden
>
> "These "fitted brute-force models" certainly can be very powerful, and certainly can produce the exact results shown in the experimental verifications of the fittings. However, they do not of themselves allow sophisticated design for example of the necessary time-polarized wave assemblies for engineering the entire human collective unconscious simultaneously, or for engineering the entire collective unconscious of all species on Earth (i.e., Gaia's collective unconscious), or even for precisely engineering the memory and knowledge base of an individual.
> **Bearden: http://www.cheniere.org/explore articles/mind control1/p09.htm**

The seemingly magical operations of psychoenergetics, sometimes called "psychotronics," cannot be achieved with ordinary transverse EM wave energy. But they are possible with longitudinal scalar waves because the mind itself is scalar in nature.

> "We note that all mind operations are time-like, i.e., they are comprised as scalar EM photon functions and scalar EM wave functions. Thus the mind is a very special kind of electromagnetic system, existing in the time domain..."
> **Bearden: http://www.cheniere.org/explore articles/mind control1/p08.htm**

The engineering of the mind can only be accomplished with the waves of time.

The course of psychoenergetics development necessitates the building of a vast database of settings and patterns which bring about given mental and/or emotional states.

A kind of "gnome" of the psyche. Bearden describes the process of the decoding of this "gnome."

> "Now the scientists would perform many phenomenology experiments, making one little change at a time and profusely recording the data. Each time, they would establish the physical change(s) that occur in the body and/or the mental and emotional changes that occur in the mind for each spectral reinsertion back through the "ship’s portholes". They would simply but painstakingly (over some years) build up an extensive database of those individual correlates.
>
> "In these experiments, the experimenters will eventually be able to provoke any body or mind change they wish. Strong emotion. Intense pain. Intense pleasure. Painful thoughts. Images. Memories. Perceptions. Dreams. Visions. Memory losses. Memory changes. Personality changes. Etc. The "delta" in the emission spectrum (the changes from zero reference spectrum) represent the precise totality of all mental, physical, organic, chemical, etc. changes and interactions."
> **Bearden: http://www.cheniere.org/explore articles/mind control3/p01.htm**
>
> "A second stage in the research would be to test the correlates and porthole insertions upon a statistically significant cross section of ordinary people, and/or specialized populations (such as toughened soldiers). The program would evolve a highly complex, very effective, ever-improving science and technology of mind and behavior control and engineering mechanisms, complete with finished database and developed applications equipment."
> **Bearden: http://www.cheniere.org/explore articles/mind control3/p02.htm**

Summing up his paper Bearden speculates on what the actual situation the science of psychoenergetics probably is.

The intense secrecy with which this knowledge has been kept from the public has led to the current farce of the "government" pretending it all does not exist, and this secrecy may have now put us at great risk.

> "The implication is that in the West one or more highly classified, sustained, heavily funded developments in advanced mind control programs, probably exists and probably has existed for some time.
>
> Due to loose formation of rogue groups inside such programs, they may have dual or triple purposes, may not operate under very much legitimate government control at all, and may operate specifically for the purposes of the rogue group or groups that have gained control.
>
> "In a nutshell, that's what may be going on in the clandestine mind control projects in several Western governments. The involvement of at least some rogue groups, some being "cowboys" who operate well outside all laws and ethics, could also result in such things as assassinations, clandestine testing on individuals without their consent, etc. In short, it could account for what seems to be actually occurring.
>
> As also is "usual" in such a mess, one or more of the rogue groups eventually may become very powerful because their secret weapons are very powerful. They may become confident, thinking they have the "best in the world." They may actually believe they are ahead of the Russians..."
>
> "Remember that, in every large and powerful human organization, the basis for rogue groups is power and secrecy. They are always seeking to increase their power, control, influence, prestige, etc. Nothing else. Patriotism and mission are to rogue groups often just idle words. They have their own agendas.
>
> And being rogue groups, they may well bring in unethical, immoral tricks: assassination, bribery, entrapment, disinformation, plausible deniability, etc. A certain percentage of a highly secret rogue group will wind up using all these things and more. It's a human characteristic, the old primate dominance game. Only now disguised and hidden under deep classification."
>
> "The Russians, with their additional knowledge of the actual mechanisms in the transforms, will be much more advanced than the West, because their fundamental psychoenergetics science is far more advanced, so long as we continue to use the old U (l) electrodynamics.
>
> Further, the Russians have decades of use of longitudinal interferometry beams to reach right through the earth and ocean and produce stringent EM effects at a distance.
>
> So they will also be able to do the same things here in "mind control" with LW [longitudinal wave] interferometers, through intervening mass."
> **Bearden: http://www.cheniere.org/explore articles/mind control3/p05.htm**

Bearden cites two examples where he believes the Russian KGB tested the psychoenergetics capabilities of their scalar interferometers.

One was the case of Captain Button in his A-10 "Warthog" aircraft on April 2, 1997.

> "Over Arizona, Captain Button was thrown into a hypnogogic state, and his perceptions instantly altered and controlled. In his instant "dream-waking" state, everything seemed perfectly normal. His sense of direction was altered a bit more than 90 degrees, so he simply corrected and turned and "flew toward the range", actually flying off course by more than 90 degrees and ignoring radio contacts. He flew right on out of Arizona."
>
> "At one point he circled, probably thinking he was over the range, and he probably dropped his ordnance there. Then he "flew on back toward home," as he thought in his waking dream state, until his fuel ran out and he crashed and died in the explosion dream-thinking until he died that everything was normal.
>
> All the while, his sense of the passage of time was altered. To him, in his dream-thinking, dream-acting state, everything was normal and nothing untoward had happened. So the distant KGB transmitters and associated psychoenergetics team controlled him for over an hour.
>
>> "Indeed, that was the exact purpose of the test: demonstrate control (at a great distance) of a skilled person performing highly skilled tasks."
>
> **Bearden: http://www.cheniere.org/explore articles/mind control3/p06.htm**

The paper Mind Control and EM Wave Polarization Transductions ends with the most chilling and frightening possibility of all: the psychoenergetic engineering of the human species as a whole.

The Ant World

The Final Race for Direct Mind Control of the Entire Human Species

> "The KGB psychoenergetics weapons scientists because of their direct measurements and detections (and use) of t-polarized waves and LWs [longitudinal waves] for decades also understand that Jung's collective unconscious mind (of the entire human species) also has its own time-like operations and correlates, which one measures also when using t-polarization measurements and sorting it all out. The collective unconscious mind operations are buried several levels deeper inside the recursive Whittaker structuring inside the EM fields, waves, and potentials.
>
> "The KGB scientists also know that something very like Gaia a collective unconscious mind for all species on earth also exists, and they are striving to be able to sort out and measure that one as well. The Gaia operations are buried even deeper in the recursive structuring inside the EM fields, waves, and potentials."
>
> "Actually, from day one, the Russian mind control scientists have had their eventual goal set upon this "deeper area of mind and possible mind control" of the entire human species.
>
> "I am convinced that the KGB psychoenergetics scientists understand this deeper area. If they can learn to directly engineer the collective human species unconscious, they can then convert the human species easily into a sort of "ant" society, modeled along ideal Communism lines, except of course with an excluded "hierarchy at the top" running everything. The "ant society" communist style is still a variation of feudalism (all systems tend to feudalism or some form thereof).
>
> "The KGB psychoenergetics weapon scientists are seriously pressing on toward that very goal. In my opinion they are not very far from it right now...
>
> "Some versions of Russian mind control devices were used on Russian soldiers in the Afghan War to condition them for performance of merciless acts." 13
> **Bearden:** http://www.cheniere.org/explore articles/mind control3/p07.htm
> More about "The Ant World"

Whether it is the Russians planning an "ant world" society or rogue U.S. black-ops groups withholding a great boon from human race, the secrecy on all sides around has allowed largely criminal elements to take over this technology while leaving the civilized elements in the dark.

Openness and the spreading of this knowledge among good and decent people is essential, and for that we will have to overcome our frightened denial.

> "Meanwhile, rogue groups amongst Western clandestine mind control researchers will probably arise if they have not already done so. They will likely seek to increase their personal control and further isolate the programs from orthodox government review and from government and legislative control. They may even divert the research into highly illegal and unethical means, because it furthers their own rogue agendas. That is how clandestine U.S. government research can sometimes go sour, unless great care is exercised by the oversight committees in the House and the Senate.
>
> "Sometimes when rogue groups do gain control and total secrecy of a given new technological area, then what appears to be "U.S. government operations" do start to encompass a criminal and unethical operations, hidden usually beneath the deep veil of high classification. Also, if it's "scientific," no one is ever brought to justice, even if the "evil science actions" are uncovered and publicly revealed."
> **Bearden:** http://www.cheniere.org/explore articles/mind control3/p08.htm

Like the huge energy of the Tesla howitzers, the ability to engineer the mind with longitudinal waveforms is a seeming "magical" thing which can be used for good or ill. Bearden envisions that further developments will allow something like the "downloading" of knowledge via scalar interferometry. Everyone could be highly educated, and quickly and easily.

In the conclusion of the paper "Mind Control and EM Wave Polarization Transductions" Bearden makes a plea to the nations of the world regarding the use of psychoenergetic engineering.

> "Let us hope this great new area, already off to a bad start, can be bridled and steered in the direction helping and healing people, rather than killing or abusing them. The excesses in its bad use are a potent threat to all nations on earth.
>
> "Yet it can revolutionize medical science, education, communication, and psychology. We foresee the day - perhaps 30 years hence - when education will be accomplished by directly loading the software into the mind. Then in three weeks one will "load" a doctorate, say, in physics. In three more weeks on will also load a doctorate in chemistry. Another three weeks, in electrical engineering.
>
> Another three weeks, an MD And so on. When that happens then truly everyone on earth can be educated. Freedom from ignorance may well be another great freedom that is legally recognized.
>
> There will be no impoverished large groups lacking the education to find decent, productive jobs.
>
> "We urge all nations to use the principles involved: not for human abuse, but for healing, educating, uplifting, and life-expanding of every person on earth. If we do, we shall all have a far brighter future. Then we shall check what has started out to be the Sword of Damocles and turn it into the golden Millennium."
>
> **Bearden: http://www.cheniere.org/explore articles/mind control3/p08.htm**

(Perhaps after so many frightening topics a slight break is in order here to consider the lighter side of psychoenergetics. For example, what will be the ultimate impact on the entertainment industry?)

The Feelies at Last!

Psychoenergetics will be able to bring about at last, for better or for worse, Aldous Huxley's fanciful idea in his novel "Brave New World," an entertainment format which he called "The Feelies."

Those were something you went to, like going to the movies, but you would experience all the actual feelings themselves, as if the depicted events were actually happening to you.

Although our "leaders" seem too dim to grasp what is going on in the world of scalar electromagnetics, it should not take some young Hollywood genius too long to understand that The Feelies are now possible, and that the immense megabucks of potential profit more than justify heavy investment in bringing it to market.

One can imagine that first "Feelie" theater, "The Huxley" perhaps, a large comfortable area surrounded by nine giant screens (not just one screen!), which become 3D if you put on your headset. And The Huxley is fitted with the finest sound, and oh, by the way, a modest sized scalar interferometer with computer. And there are one or more new tracks now recorded on the film next to the sound track.

These are the digital patterns of thoughts, feelings, and ideas to be fed into the theater's interferometer. And these thoughts and feelings and ideas will be felt by the audience as if they were their own thoughts and ideas. It is an entirely new art form. Psychevision.

As important (and no doubt famous) as the actors would be the "feelers," those from whose minds the feelings were lifted in the original programming of the Feelie tracks. Because, for example, Brad Pitt might be a good and handsome actor, but can he really feel it? Like the dubbing of foreign language films, it might be necessary to dub the "emotional track" using a deeper and more profound person's feelings, thoughts and ideas.

It might even be engineered so that if you sat on one side of the theater you would feel like the hero, and on the other side you would feel exactly like the bad guy! What would that lead to?

We have all cried at a movie some time, most people have, though they might not want to admit it. But this would be deep sobbing and a flood of tears, if the director so desired it. You would feel it at your core. Or, take a big chase scene, you would be terrified. They are breathing down your neck! You would be gripped by panic.

For that matter, the whole genre of Horror-Feelie would be too much for many people to take. Do I really want to feel that an actual vampire is tearing at my throat with his fangs?

A Religious Feelie would make you feel the exaltation of a saint at his prayers, or give you the definite feeling that you are Christ suffering on the cross. All the pain could be there too. The stickiness of the blood. The very feeling itself: "Why hast thou forsaken me?" Who among us could come up that despair for scanning?

Had this been developed a bit earlier we might watch a documentary of, say, Mother Theresa, containing her own actual deep sense of compassion, which we would feel arising in us as our own.

Then again, a Psychedelic Feelie could induce an LSD-like state and simply blow the audience’s minds.

Even in its simplest most primitive mode, the hypnogogic trance induction with its increased suggestibility, would completely alter the experience of even ordinary current movie going.

Go Back to Scalar War

Go Back to Psychoenergetics

<<< Scalar Wars

The Brave New World of Scalar Electromagnetics

by Bill Morgan

(See also **NEW 2007**: Book Review of Bearden's "Oblivion - America at the Brink")


Tom Bearden (2001)
Lieutenant Colonel, U.S. Army (Retired)

For the past six months I have been undergoing the greatest **paradigm shift** I have ever had to go through. It has rattled my nerves and shaken my bones. This intense adjustment of my "world"has come about by studying the information given by Col. Tom Bearden at his website **Cheniere**. The new knowledge there has necessitated a total revision of my ideas about physical reality, the world we live in, and the future of humanity.

This paradigm shifting even actually made me dizzy on certain days as I tried to absorb and digest Bearden's vast amount of information. I am not a scientist at all, just a layman, and I have little comprehension of the math and high physics of this new science called "Scalar Electromagnetics."But there is a great deal of information at **Cheniere** which **needs to become common knowledge** as fast as possible, for the sake of the survival of life on earth.

To that end I have put together this small primer of Bearden's ideas, as a kind of "beginner's guide" to his website. (I have tried to underline certain words and phrases which are part of the new "jargon" of talking about these "new" phenomena. Also I have taken the liberty of **bolding** certain words and phrases to help them stick in the mind).

(Note: Throughout "**EM**" means "**electromagnetic,**" and "**LW**" means "**longitudinal wave**")
You can download this article in Word format

This article has six sections:

1. New Waves 2. Tapping the Waves 3. Weaponization 4. Healing 5. Psychoenergetics 6. As It Stands

2006 NOTE: Click here for a current status history of the MEG from Tom Bearden

1. New waves discovered

Longitudinal EM energy fills vacuum of space, the time domain of spacetime, time as compressed energy, E=tc2, waves of time, phase conjugate wave pairs.

> **"Electric power is everywhere present in unlimited quantities and can drive the world's machinery without the need of coal, oil, gas, or any other of the common fuels."** Nikola Tesla
>
> **"At any point and at any time, one can freely and inexpensively extract enormous EM energy flows directly from the active vacuum itself."** Tom Bearden

I guess the first thing to try to comprehend is that a **"new" kind of electromagnetic (EM) wave has been discovered** in the empty vacuum of space which, when engineered, can be an inexhaustible supply of energy in great magnitude at any place in the universe. The word "new" is in quotes because the



discovery really goes back to Nikola Tesla and his discovery of what he called "radiant energy." It is also not "new" because the Russians (KGB) have been working on this technology **for over 30 years** and have **weaponized** these "new" **longitudinal scalar waves** to a great degree.

These are the weapons Nikita Khrushchev spoke of in January, 1960.

> "By 1957-8 the Soviets had progressed to the point of a giant scalar EM accident in the Urals which exploded nearby atomic wastes, devastating the area. They had also progressed to development of great new superweapons using their new energetics - weapons to which Khrushchev referred in 1960 when he informed the Soviet Presidium of a new, fantastic weapon in development, a weapon so powerful that it could **wipe out all life on earth** if unrestrainedly employed.'" Tom Bearden

After over 30 years of development, and extensive testing around the globe, these new scalar electromagnetic weapons are up and running and ready to go. Tom Bearden, at his website Cheniere, dicusses the history of these new scalar electromagnetic weapons in his paper "Historical Background of Scalar EM Weapons."

Some Immediate Implications

> The implications of successful engineering of the longitudinal waves are enormous, and will change the world as we know it, one way or another. Among other things, these discoveries mean that:
>
> **1. The solutions to the energy crisis and the "oil problem" are in hand. These oil wars are unnecessary. There is endless energy available freely from the domain of time.**
>
> **2. Unbelievably powerful weapons are not only possible, but are already operating in several nations. The many powers of these weapons are unprecedented and mind-boggling.**
>
> **3. The cure of diseases such as cancer and AIDS, in fact nearly any disease, has become possible within a few years of sufficient funding. Everyone can be made healthy and stay healthy.**
>
> **4. Mind control on a mass scale has now become possible, and the machines to do it are already in place in certain nations. It has become possible to mentally enslave whole populations with the twist of a few dials.**

So the layman will need to understand that **there is a new kind of electromagnetic energy** that is altogether different from what he knows, e.g. radio, TV, cell phones, etc. The ordinary EM waves that we have known about are called **transverse** EM waves, to distinguish them from the new **longitudinal** EM waves. These scalar waves do not actually exist in our "material" world, but exist only in the vacuum of empty space, or the time domain. And we must keep in mind that this vacuum of space we speak of exists all through everything. Even our bodies are mostly empty space between atoms and molecules. So the gateway to this seething ocean of energy can be there at every point in the universe. This seething ocean of energy is all around us and all through us.

Emptiness is Full

This amazing discovery announces that **the "emptiness" of empty space is in fact not empty**, but a **great ocean** of seething energy!

Col. Bearden refers to this ocean of energy as being of the "time domain." Energy out of time? It seems like something from Star Trek but this is the point which the new science of scalar electromagnetics has reached. And where it is going may be beyond anything Star Trek could have dreamed of.

We live in a 3-dimensional world, which physics calls "3-space." But there is also **spacetime**, or 4-space, or the "4th dimension." Then suddenly comes this amazing new knowledge that **time itself is actually compressed energy**. And it is energy which is compressed by exactly the same factor by which **matter** is considered compressed energy: the speed-of-light-squared!

So we have a new companion to the famous **E=mc2**. It is now paired with **E=tc2** (where t is actually "delta-t," or change in time). Or (amaze your family and friends and) say:

"E equals em-cee-squared"
and
"E equals delta-tee-cee-squared"

It has a nice ring to it, like some freedom bell announcing a new era.

And as the atomic bomb released the compressed energy in matter, so can we now unleash **the tremendous energy that is compressed into time itself.** It gives a completely new meaning to the term "time bomb."

Some New Terminology of Scalar Electromagnetics

A new science, **several** new names

"Those [Russian] weapon scientists resurrected an old term from the history of electrodynamics, called "**energetics**". That is their approach to a **unified field theory**, where everything is based on "energetics". This model as its foundations uses a very similar approach to that "single fundamental unit" model, where energy is the unit. If one makes the energy EM in nature, then one has the Russian energetics approach. This unified approach gathers everything in, including all energy actions and relations in inert matter (the first branch of

> energetics, called by the same name), all field and matter interactions in living matter (the second branch of energetics, called "**bioenergetics**"), and all mind operations and mind-matter interactions (the third branch of energetics, called "**psychoenergetics**"). [ed: sometimes also called "psychotronics" by the Russians]
>
> "Note that the weaponeers sliced energetics into three branches, with each branch depending on the nature of the "targeting".
>
> "So I took a hint from them, since the stuff and the approach worked. They had already weaponized it highly."
>
> Bearden : http://www.cheniere.org/correspondence/021502a.htm
> See also "Subdivisions of Soviet Energetics"

Rick Andersen in an article called "What is Scalar Electromagnetics?" describes the **new science** this way:

"Scalar EM is the brainchild of Lt. Col. (retired) Thomas E. Bearden, a systems analyst and wargames specialist who has been advocating a view of electromagnetics which is based on the notion of a vast, unseen background of scalar energies (as opposed to vector energies) **which underlie all physical reality.**

"If Bearden is correct in his Scalar EM theory, then we can build devices which would enable us to **alter gravity**, time, inertia, and the apparent mass of an object. This of course has ENORMOUS implications for military applications, **space-vehicle drives, time-travel, teleportation, paranormal phenomena**, and just about every other area one can think of."
http://twm.co.nz/Beard_scalem.html

> **"Time-energy, time-currents, and time-structuring play the dominant role in electromagnetics. *Time-as-energy* eventually becomes engineerable, as easily as is spatial energy now. We are always dealing with *spacetime* and with *spacetime curvature*."**
>
> **Bearden:http://www.cheniere.org/techpapers/Vision%202000%20paper.doc**

The scalar energy discovered in the vacuum of space is sometimes called "**zero-point**" energy. Thomas Valone explains how this term came about.

What does "Zero Point" mean?

"Boyer traces the historical “creation of the vacuum” as proceeding in stages in parallel with the historical development of ideas about the vacuum. To paraphrase, he says that in the 17th century, it was thought that a totally empty volume of space could be created by simply removing all matter and, in particular, all gases. That was our first concept of the vacuum. Just get rid of all the gas.

Late in the 19th century, it became apparent that the region still contained thermal radiation. But it seemed that the radiation might be eliminated by cooling. So the second concept of getting a real

> vacuum is to cool it down to zero temperature. Just go all the way to absolute zero. Then we've got a real vacuum. Right? Well, since then, both theory and experiment have shown that **there is a non-thermal radiation in the vacuum** and that **it persists** even if the temperature could be **lowered to absolute zero**. Therefore, it was simply called the "**zero point**" radiation."
>
> Thomas Valone http://www.seaspower.com/InsideZeroPoint.htm

"For our very survival, it is absolutely imperative that informed citizens be aware of this dramatic change, which is just now starting. The powerful new science and engineering must be controlled and used for humanity's benefit, not its detriment. Else it will eventually be let loose unrestrainedly, to destroy all life on earth - a possibility indicated by Nikita Khrushchev in 1960." - Bearden

http://www.cheniere.org/explore%20articles/priore1/p4.jpg

2. Tapping the waves

Endless free energy, Tesla's radiant energy, the dipole as the gateway to the energy of the void, MEG in one year, Bedini, Yakuza, etc. End of Oil, geopolitical chaos, rogue groups

Move Over G.E. & Big Oil, Energy is Everywhere!

Third-world nations set to rise

> "Certain powerful interests did not wish the extended electromagnetics to be discovered or taught. That, after all, would lead to **free energy** and loss of economic control of the citizens. That was precisely why Nikola Tesla had already been suppressed ... Today it is still being suppressed by the orthodox establishment."
> http://www.cheniere.org/books/ferdelance/s25.htm

The vast seething ocean of energy of the vacuum, the longitudinal scalar EM waves of the time domain, can now be tapped and "transduced" into ordinary (transverse) EM energy in our 3-Space world. The process can be compared to putting a paddlewheel into a river. The energy acquired is free, since the river is there flowing whether we tap it or not. And it is a mighty river, and is not diminished by our paddlewheel.

This means that **a permanent solution to the "energy crisis" is at hand**, if only those who hold it **so secret** would give it up to humankind.

It means our species' **insane use of oil** is no longer necessary. We can make automobiles that need no fuel at all. We can build motors that power themselves. It means that unlimited electrical power can be available for free anywhere in the world. Every house and even shack can have its own power supply.

Of course there is the cost of the equipment at first, but the energy flow is free for the presumably very long life (no moving parts) of the generator. It will probably take decades to shift over to scalar power.

But the ability to tap the scalar (longitudinal) EM waves of the vacuum (which exists everywhere) also means that **unbelievably powerful weapons** can be, and already have been developed. In fact these weapons are so dangerous that the **fear engendered** becomes a psychological obstacle to the grasping of the facts.

I struggled with this myself for months, and even though Tom Bearden had completely convinced me already, it is hard to accept the fact that for everyone on earth the "worst that might happen" has suddenly gotten much worse. It takes time to deal with that, to realize it and get over it.

Indeed, the possibilities of these new weapons, which are tapping the **huge energies of time**, are so terrifying it is natural for the mind to simply say: "I don't want to hear about that."

And the government, likewise, pretends these weapons do not exist and tries to keep it secret from the people. Because **most people would indeed be truly alarmed** to know the actual situation. Col. Tom Bearden has decided that the people need to know the truth anyway. As a People on a Planet we must face this now, and **ban the use of scalar weapons in war or in mass mind control**. The current deployment of these weapons is a **world emergency** which we must all face.

The physics and mathematics of the longitudinal waves and the time domain are clearly beyond the layman, but I recommend scanning through them anyway just to get a sense of the wonder and the elegance of it all and some of the exotic terms which are used. Two of the most important papers by Col. Bearden are:

Giant Negentropy from the Common Dipole
The Final Secret of Free Energy.

Despite the complexity of the science involved, Bearden sums up the **essential secret** of it all in a few words.

> "There is no problem at all in extracting all the energy one wishes from the active vacuum, anywhere in the universe, at any time. **Just make a dipole.**
>
> The problem is in (1) catching some of that freely gushing EM energy in a circuit containing a load, and (2) dissipating the caught and collected EM energy in that load to power it, without using half the caught energy to destroy the source dipole's).
>
> That is the ONLY real energy problem on the planet, and always has been."
>
> http://www.cheniere.org/correspondence/022502.htm

A dipole could be a battery, which is polarized into negative and positive. Or the terminals of a generator. Or any magnet with its two poles. Or an atom with its positive and negative charges. Or the earth's magnetic field, the sun, and all heavenly bodies. Even a galaxy must be some kind of mega-dipole. Wherever there is a dipole there is already immense scalar EM energy ushering out of and back into the vacuum. And there have already been demonstrated a number of diverse methods for tapping that energy as it flows. (John Bedini, Edwin Gray, Bruce de Palma, and others). Bearden provides what he calls a "partial list" on his website.

> "In other words, **nature then gladly gives us** as much EM energy flow as we need, indefinitely — just for paying a tiny little bit initially to "make the little dipole." After that, we never have to pay anything again, and nature will happily keep on pouring out that 3-flow of EM energy for us. This is the **giant negentropy** mechanism I uncovered, performed in the simplest way imaginable: just make an ordinary little dipole." Bearden
> http://www.cheniere.org/techpapers/Unnecessary%20Energy%20Crisis.doc

Important note 2006: Since the enthusiastic early report below, the hopeful timetable envision has gone quite off track. Bearden had said that the MEG could appear as early as 1-2 years ***after getting funding*** for the final research and scale-up. They have **still** NOT gotten the funding as of 2006.

Click here for a current status history of the MEG from Tom Bearden

The original text of article continues here...

How to Buy a Free Energy Machine

Answer: Just wait one more year! 2003. Then get off the Grid!
[note 2006: The above line was unfortunately naive and overly optimistic! - author]

Perhaps the most eagerly awaited event now is the marketing of Bearden's **M**otionless **E**lectromagnetic **G**enerator (MEG) scheduled to begin in about a year's time. This is when the proof will hit the fan. Many people have said to me, when talking about free energy, "I'll believe it when I can go to the store and buy one." Hopefully in a year's time they will be able to order their own MEG. And then they will believe, because it works and is working.

Says Bearden: "I will admit that the chief scientist of an important experimental group in a large company was rather stunned at the type of output we were able to obtain. The MEG may look like just a transformer, but it is not. It is a completely different breed of cat."

Bearden : http://www.cheniere.org/correspondence/011202.htm

Soon the cat will be fully out of the bag. The first MEG units will supply 2.5 kilowatts of free electricity. Forever. Units can be connected together to double or triple the wattage. After that gets going, 10 kilowatt generators are planned. Energy will flow freely from the time domain indefinitely, and there are no moving parts to wear out. This manufacturing project is a heroic effort and will change the world as we know it. For once people are in possession of such devices there can be no further denial from anyone, including the government and/or "secret-government."



The Motionless Electromagnetic Generator
(Successfully replicated here by J. L. Naudin)

The physics of how the MEG works is explained in the paper "The Motionless Electromagnetic Generator: Extracting Energy from a Permanent Magnet with Energy Replenishment from the Active Vacuum."

The device was successfully replicated by J.L. Naudin in France, and others, like Steve Utne, are also working on their own models. But **Magnetic Energy Limited's MEG** is actually scheduled for production soon and looks to be the first commercially available free-energy generator in history!

I imagine it will not take long for tinkerers to put them into their electric cars and make the first fuelless automobiles since Tesla's unheralded (and unheeded) experiments. Or for builders to begin building houses powered by MEG's. Houses which will never see electric bills. How can they ever make enough of these to meet the demand that will suddenly be there? Bearden is right, it needs to be an all-out crash program of the government **on the order of the Manhattan Project**.

I must include here that Bearden is quick to point out that he is not himself the inventor of the MEG, but is a partner and advisor in bringing it to the public market through **Magnetic Energy Limited, Inc**. I must also admit that I am praying for the success of this venture, and the ending of the absurd and criminal withholding of this technology from the people by the black-ops military-industrial people. This secrecy has cost the planet over 30 years of unnecessary pollution.

The first units off the assembly line, which is being set up in a "friendly" unnamed nation, will usher the public at last into the new era of scalar electromagnetics.

As of December, 2001, the situation with the MEG was described by Bearden in a letter.

> "What we presently have with the MEG is a successful laboratory experiment. At least a year's very hard research will have to be done before we will be ready to put a commercial power supply into production.
>
> "Consequently, we have made an agreement with a foreign partner (the National Materials Science Lab of the National Academy of Sciences of a friendly foreign nation) to do that year's research. At the same time, we are trying to make an agreement with one or more large financial partners here in the U.S." http://www.cheniere.org/correspondence/121901.htm

> "So we are hopeful that we will be able to start introducing units on the market about a year from now. Quite simply, we will either succeed or we will fail. But we will give it our very best effort."
> http://www.cheniere.org/correspondence/012202a.htm

Bearden has given another technical explanation of how the MEG works here in a letter.

Update : Motionless Electromagnetic Generator patented, 3-26-2002

Click here to read the patent

"In Magnetic Energy Limited, all business discussions and arrangements are taken care of by Dr. Lee Kenny, Managing Partner. There are five of us who are co-inventors of the MEG, and two of the others are really the principal inventors." Bearden
http://www.cheniere.org/megstatus.htm

Lee Kenny can be reached by E-mail at: jlkenny@ingr.com

Free Energy has been Suppressed

Secret Government Aware of Free Energy

"In this world of contemporary times, all the agencies, CIA, FBI, KGB, NSA, Electric Power Research Institute, DARPA, Brookings Institution, Henry Kissinger, Edward Teller, et al., all are aware of [free-energy researcher Bruce] DePalma and his ideas.

"Because these individuals and institutions are employed by the ruling elite to forecast the future and satisfy present needs and demands, it is clear that **free energy is a threat** to the world order constructed by **business** and the **mindset of those who want to own the world**.

"Free energy represents Man's aspirations and dreams of freedom and equality, uniform division of resources and the ability to choose one's own future.

"The fact that free energy is suppressed speaks to the greed and self-interest of a ruling elite which, even in the face of an emergency of global starvation, resource depletion and environmental pollution, will not give one inch if it means loss of control. This is an attitude of **paranoid delusion** and fantasy which can only arise from the alienation of a **class of elitists** who, through their money, are completely **insulated** from the reality of the day to day fight for existence of the common man."

http://depalma.pair.com/Absurdity/Absurdity07/ProblemOfFreeEnergy.html

"Before the turn of the century, **Nikola Tesla** had discovered and was utilizing a **new type of electric wave**. Tesla repeatedly stated his

> waves were non-Hertzian, and his wireless transmissions did not fall off as the square of the distance. His discovery was apparently so fundamental (and his intent to provide free energy to all humankind was so clear) that it was responsible for the withdrawal of his financial backing, his deliberate isolation, and the gradual removal of his name from the history books."
>
> Bearden http://www.cheniere.org/books/part1/starting%20pages.htm

Bearden describes one clear case of the suppression of free energy when the Yakuza killed the **Kawai engine** in his very presence in Huntsville, Alabama.

> "That night a jet arrived from Los Angeles, with a Yakuza on board. The next morning Kawai no longer controlled his company, his invention, or his own fate. The Kawai party was in fear and trembling. The Yakuza coldly dissolved the agreement, they packed up the two Kawai engines we had, and left. And that was that."

So it is not only governments who are keeping this revolutionary technology from seeing the light of day. The Yakuza? KGB? The Aum Shinrikyo cult? Our "leaders" need to be honest about what is going on, otherwise they look foolish, acting out a kind of "Alice In Wonderland" script before the public, a script that has become completely unbelievable.

Concerning the criminal withholding of this scalar technology by the military black-budget people, and the cover-up of the actual situation regarding scalar weapons throughout the world, Tom has this to say:

> "The high government officials of the United States of America grossly violated our constitution and their sworn oaths of office. Our constitution specifically charges the government of the United States to **defend** the people of the United States. That means our officials are specifically charged with defending our people. Yet they deliberately agreed not to do so, and they deliberately sacrificed us in advance.
>
> **"They committed treason of the highest kind, by deliberately surrendering us to total destruction anytime the big balloon goes up.**"
>
> Bearden http://www.cheniere.org/books/ferdelance/s75.htm

Energy Crisis Solved

One of the "must read" documents at Cheniere is The Unnecessary Energy Crisis: How to Solve It Quickly, especially since the "**oil wars**," which Bearden has foreseen for decades, have now already begun.

Here are some clips from that Document:

> "To avoid the impending collapse of the world economy and/or the destruction of civilization and the biosphere, we must quickly replace much of the "electrical energy from oil" heart of the crisis at great

> speed, and simultaneously replace a significant part of the "transportation using oil products" factor also.
>
> "The technical basis for that solution and part of the prototype technology required, are now at hand. We discuss that solution in this paper." Bearden

And although the solution to the energy problem and the oil wars may be at hand, Bearden suggests there is still an urgent rush that needs to be made to save human civilization from collapse.

> "Once the technology hardware solutions are ready for mass production, even with a massive worldwide deployment effort some five years are required to deploy the new systems sufficiently to contain the problem of world economic collapse. This means that, by the end of 2003, those hardware technology solutions must have been completed, and the production replacement power systems must be ready to roll off the assembly lines en masse.
>
> "The 2003 date appears to be the critical "point of no return" for the survival of civilization as we have known it.
>
> "Reaching that point, say, in 2005 will not solve the crisis in time, and the collapse of the world economy as well as the destruction of civilization and the biosphere will still almost certainly occur, even with the solutions in hand."
>
> "The **good news** is that we now know how to easily initiate continuous and powerful "electromagnetic winds" from the vacuum at will. Once initiated, each free EM energy wind flows continuously so long as the simple initiator is not deliberately destroyed."

On page 9 he explains the concept of the **dipole**, and how there is already huge scalar energy flowing in the time domain around any dipole. Hold a magnet or a battery in your hand and you hold a stress in time and a beautiful flowing loop of longitudinal waves!

Bearden decries the scientific community in the West for being unable to let go of their dogma long enough to see that the **greatest discovery in human history** lies at their feet, but for their stubborn ignorance.

> "The present energy crisis then is due totally to that "**conspiracy of ignorance**" we referred to, that is maintained by the scientific community, and that has been maintained by it for more than 100 years.
>
> "This is the real situation that the environmentalists must become aware of, if they are to see the correct path into which their energies and efforts should be directed — to solve both the energy crisis and the problem of gigantic pollution of the biosphere."

As far as anyone in the legislative branch of government ever understanding the profundity of the discovery and engineering of scalar waves, Tom Bearden says they are at a great disadvantage in doing so.

> "The nontechnical person — e.g., a Senator or a Congressperson — is operating under a distinct disadvantage. If he or she takes the stance that much better electrical power systems can readily be achieved, **he or she is in fact opposing almost the entire set of University, Government Technical, Power Company, Battery Company, and Organized Science communities**. Further, in most cases his technical advisors are themselves from one or the other of those communities, and likely to go back into that community or those communities when the Senator or Congressperson leaves office, or even before. So the Congress and the non-technical government community at large operate at a great disadvantage...Bearden

National Emergency Declaration is Needed

"The Government *Non-Technical* community (the Senate and the Congress, in particular) are in far better shape than the Government *Technical* community, to appreciate the **world implications of the pending economic disaster**. I am hopeful that both the environmentalists and the Government Non-Technical community will rapidly unite in a common goal to **get this vacuum energy program launched**, under a **National Emergency** declaration. If so, then they can solve the energy crisis and the pending economic crisis, in fairly short order, and permanently."

unnecessary_energy_crisis.htm#congress_disadvantage

In the conclusion of his paper The Unnecessary Energy Crisis: How to Solve It Quickly Bearden again states the urgency of replacing our centralized power grids with highly dispersed and local taps on the freely flowing energy of the active vacuum. Given the abilities of the Tesla howitzers, the power grids of all nations are sitting ducks.

"Personally, the present author regards the increasing **energy crisis as the greatest strategic threat** to the United States in its entire history. I will do anything within my power to help prevent what I perceive to be the looming economic collapse of the Western world, preceded or accompanied by a sudden, explosive, all-out and continuing exchange of the WMD arsenals of most of the world.

...*In the name of all humanity, let us begin!* Else by the time this first decade of the new millennium ends, much of humanity may not remain to see the second decade."

---

3. Weaponization

Scalar interferometry, Tesla howitzer, Tesla dome, heat/cold, dudding, 10 nations have them, dead-man fusing & Insane Systems, scalar strategy, earthquakes and weather wars, solar storms, mind attacks, leased to Yakuza, many examples of testing, quantum potential weapons.

> **"Indeed, Soviet energetics weapons are now capable of destroying both our triad shield, our homeland, our armed forces in the field, and our population, quickly and efficiently. We have a new "gap" of monumental proportions: not a missile gap, not a submarine or bomber gap, and not even a particle beam or laser gap. We have a scalar electromagnetics or electrogravitation gap."** Bearden
> http://www.cheniere.org/books/ferdelance/intro.htm
>
> "**We have a new weapon, just within the portfolio of our scientists, so to speak, which is so powerful that, if unrestrainedly used, it could wipe out all life on earth. It is a fantastic weapon."** Khrushchev, to the Presidium, Jan. 1960
>
> "We've totally missed the most incredible "secret superweapons" development program of all times, and the worldwide testing of the weapons themselves.
>
> "Hiroshima and Nagasaki should serve as object lessons in the price of ignorance of such technological breakthroughs.
>
> "History does repeat itself. But this time it's not we Americans who got the great new superweapon first."
>
> Bearden http://www.cheniere.org/books/ferdelance/s75.htm

Warfare has been changed forever by the development of these scalar energy longitudinal wave howitzers. To get a basic understanding of scalar waves is to have the imagination suddenly run wild as all the implications and possibilities regarding warfare fall into place. One realizes with a certain horror that the world has totally changed, and that there are some very fearsome possibilities. Remember, the power for these weapons comes from the time domain, longitudinal EM waves in the vacuum of empty space, and the power is tremendous and mind-boggling. Being able to blast away at any target from a distant control booth is something that has never happened before. This is incredible power to be in control of and it divides the history of weaponry into "before" and "after." And the destructive power of these weapons is delivered instantaneously to the target **from the local vacuum at the place of the target.**

From an interview:

Questioner: "Are you saying that real energy can be transmitted faster than the speed of light?"

Bearden: "Yes. But hyperspatially. Not through 3-space, but "around" it. Again, this means that it's possible to produce energetic changes in a distant system at a distant place, without transmitting energy "through space" in the normal sense. You transmit "around" space, so to speak, and directly in time or through a higher dimension, depending on the model you're using to understand this. Further, the speed of the internal EM energy transmission is not limited to the speed of light."

http://twm.co.nz/beard_interview.htm

Here are some initial considerations about scalar weapons and scalar wars

1. Tesla Howitzer 2. Tesla Domes 3. Rogue groups 4. WW III 5. Russian "UFOs?"

1. The Tesla Howitzer and its modes of action

Source: Tom Bearden's weapons slides and Fer-de-Lance Briefing

For one thing there is no delivery of any thing to any place. Bombs are obsolete. So are the planes to get them there. No helicopters necessary. All current nuclear devices are rendered nearly useless by electronic "dudding." All distant-destruction can be done from a control room, and to any point on earth. The destructive power of "men" has just increased by orders of magnitude. The new weapons could even cause storms on the sun! Thus there is great urgency to make these **new facts public** and known, with the hope that all nations would come together to ban the use of scalar weapons.

Two scalar antennae together along with the computers to control them, make up a scalar interferometer, and according to Col. Bearden the Russians have hundreds of such installations already. These interferometers are called "**Tesla Howitzers**." They can deliver a giant blast of energy to the distant target site, true "action-at-a-distance".

The **first howitzer mode** is called the "**exothermic**" mode of operation because immense EM energy blasts outward at the target site. The blast of a scalar howitzer can be of near nuclear level in destructiveness, and can be repeated easily, at that place, or nearby, or anywhere.

The howitzer can use a lesser exothermic power setting and simply **destroy all electronics** in the target area. Thus they can render our nuclear missiles inoperable as they sit in their silos by "frying" the electronic circuits that guide them. They can bring down any airplane, anywhere in the world, at any time. Any person anywhere, if their exact position is known, can be assassinated without a shot being fired.

The howitzers can also bring down power grids anywhere in the world, at any time. Thus they could bring Wall Street to an instant halt by disabling all its electronics. Even this one little easy tweak of the howitzer could cripple the U.S. economy in a single day. No wonder the "**leaders**" don't want you to know! This is a new era we are in. The discovery and development of scalar interferometry has put us in a **new world**, whether we like it or not. Anyone could be expected to go into denial, the **befuddled** senators and congressmen included. But we have **to wake up**.

In a **second howitzer mode** called the "**endothermic**" mode, the howitzer sucks energy out of the target area, essentially creating a blast of cold at the distant target. It is even capable of freezing parts of the ocean. Bearden gives a number of cases where these "**cold explosions**" have been witnessed, mostly by airline pilots. April 9, 1984: 1 2 3) A huge mushroom cloud of mostly water is seen rising miles into the sky from out of the ocean, an awesome sight.

In the endothermic mode the sucked-out energy must go somewhere, so it is vented out at some other chosen spot on the earth. These endothermic plumes have been photographed by satellite.



"The exhaust in the left picture is about 150 miles long, and is nearly horizontal (about 1.5 degrees above the horizontal). It is entirely consistent with the continuous exhaust from a "dumping transfer" scalar EM howitzer in the continuous exothermic mode. (The primary howitzer, of course, was activated in the endothermic mode.)" Bearden More Plumes

By using both of these **heat** (exothermic) and **cold** (endothermic) modes together the weather can be altered anywhere. Warm the air over here, cool it down over there, put a curl in the jet stream, dissipate clouds, create clouds, whip up a tornado. Bearden speaks about using the **endothermic howitzer mode** as a weapon of war:

> "Cold explosions can be used to freeze tanks, personnel, and equipment. The equipment and tanks thaw out. The personnel thaw out too, but they are dead when they do." Bearden, Fer-de-Lance

(This endothermic mode of the howitzers makes me think that there might one day be a cure for the problem of global warming after all. Could not a big device, situated in space or on the moon, be able to vent a great deal of excess heat outside the atmosphere into space, thus functioning as a kind of planetary thermostat?)

While the United States has experimented with electomagnetic weapons using ordinary **transverse** EM waves, the **longitudinal** [**LW**] weaponized waves are truly of another order altogether.

For one thing they do not have to travel through space, for they come from the time domain, which is everywhere. The energy of the blast, the heat or light or whatever, comes from the vacuum of space **at the location of the target itself**. This is astonishing. The weapons actually just trigger the release of immense energy from the vacuum at the target location.

> "... it is possible to focus the potential for the effects of a weapon **through spacetime itself**, in a manner so that mass and energy do not "travel through space" from the transmitter to the target at all. Instead, ripples and patterns in the fabric of spacetime itself are manipulated to meet and interfere in and at the local spacetime of some distant target. There **interference of these ripple patterns** creates the desired energetic effect (hence the term energetics) directly in and through the target itself, emerging from the very spacetime (vacuum) in which the target is imbedded at its distant location." Bearden Fer-de-Lance

The big Tesla howitzers are aimed at their targets by using a worldwide electromagnetic pattern called the "Woodpecker Grid," begun by the Russians in 1976.



You can hear the Woodpecker signal here:
http://www.cheniere.org/misc/woodpeckersound.htm

The woodpecker grid is just that, a grid of EM waves which provide a channel for the **LW** waves to any point on earth. Computers use the woodpecker grid information to hone down the aiming of the howitzers **to a pinpoint location on earth**. (For that matter, it could be under the earth, in space, or under the sea).

A third howitzer mode is what Col. Bearden calls "**Mindsnapper**" mode. This is a truly frightening mode which affects the electromagnetic mind-body connection. Being mind-snapped at a low level would cause you to lose consciousness. Being mind-snapped at a slightly higher power would "entrain" all minds in the target area into a kind of hypnogogic trance, a state in which they would all be highly susceptible to suggestions and orders.

Being mind-snapped at high level would so disrupt the mind-body connection that everyone in the target area would fall down, instantly dead. Not only that, everything around you and inside you would be killed, so that your sterilized body would **not rot** for quite a long time.

The **Mindsnapper** can be used for a small area, or to **kill an entire population**. In fact, using the scalar waves to affect the human mind has become a new field in its own right, and has been dubbed "psychoenergetics." (This is discussed below in section 5).

Bearden describes the use of the howitzer in **mind-snapping mode** against people, to cause unconsciousness or death:

> "From a military viewpoint, these scalar EM weapons are really quite all-around weapons.
>
> "For example, they are very lethal against personnel.
>
> "Set in the "high intensity pulse mode," one blast and a person's nervous system is destroyed instantly. Total, instantaneous death results. One can blast away at entire groups of infantrymen, for

> example. It's the peak power that's important, not the average power. So the weapon doesn't require too much battery power.
>
> "Set on a lower intensity pulse mode, one zap can simply knock out a person, rendering him instantly unconscious. Quite useful if one needs prisoners to interrogate. Also very silent, which is useful in operations employing stealth and surprise." Bearden http://www.cheniere.org/books/ferdelance/s80.htm
>
> "Those hit by the scalar EM weapon, however, have a most peculiar death mode.
>
> "Death comes-instantly and totally. There is no convulsion, no response. The entire nervous system is destroyed instantly. Every living cell in the body is killed instantly, including all bacteria, germs, etc.
>
> "A body hit with this thing falls like a limp rag and lies where it falls. It doesn't decay in even 30-45 days. In a macabre fashion, it's been reduced to something like food irradiated with nuclear radiation; everything is killed, so the material is preserved for an extended period before any decay can set in."
>
> Bearden http://www.cheniere.org/books/ferdelance/s81.htm

He goes on to say that the same "bazooka-sized scalar EM pulse weapon" can also be used to knock out a tank with one shot (or pulse). So tank warfare is obsolete. Helicopters? Bearden points out: "... if he's attacked by a helicopter or a fixed-wing aircraft, he can bring the same weapon to bear on it. He can knock down a chopper or a jet. With one shot."

Obituary for Tank Warfare

Tanks useless against portable LW weapons

"For example, suppose one attacks a tank. [with an LW weapon]
With scalar EM pulse, the personnel die instantly. Total personnel kill is achieved.
All electronic systems of the tank are dudded. Total systems kill is achieved.
The ammunition in the tank explodes. Total kill is achieved.
The fuel explodes. This is another total kill mechanism.
That tank has been killed totally, by a variety of mechanisms, all simultaneously.
That's a k-kill in any analyst's book.
And don't worry about retrieval and repair. That tank is finished permanently.
Even the most modern tank is just as vulnerable as the most obsolete."

Bearden http://www.cheniere.org/books/ferdelance/s88.htm

One begins to get the idea how profoundly the conventional means of warfare have been obsoleted. All the usual weapons of war have been rendered nearly useless! And **Star Trek's "Phaser**," with its "stun" and "kill" modes is here at last.

Although it is the weapons aspect of scalar electromagnetic which has received the most developmental effort, Bearden points out that a great many other amazing things that may be accomplished in this new field of science. Beam me up Scotty!

> "Superluminal communications systems, hyperspace drive, and **materialization** and **dematerialization** are all hypothetically possible, using scalar electromagnetics. As the technology develops, we should see the development of many of the systems long thought impossible except in science- fiction."
>
> Bearden http://www.cheniere.org/books/ferdelance/s15.htm

Bearden describes a huge test of the Russian scalar weapons systems which occurred in 1985, a test that went completely unnoticed by western scientists:

> "Just before May 1, 1985 the Soviet Union performed a "full-up" operational test of their entire strategic scalar EM weapons complex. This test was detected and monitored periodically by Frank Golden. Some 27 of these giant Soviet "power taps" were locked into the molten core of the earth, producing forced (entrained) scalar resonance of the entire planet on 54 controlled frequencies under our very feet. The remainder of the scalar frequency spectrum was ablaze with literally hundreds of Soviet scalar transmitters: probably the entire strategic scalar command and control system to underwater submarines, higher command centers, distant commands, etc. was activated in the giant exercise.
>
> "For several days, the system was exercised on a mind-boggling scale, apparently as part of the Soviet Union's highly accentuated 40th anniversary celebration of the end of World War II.
>
> "Ironically, not a single U.S. intelligence agency, laboratory, or scientist detected this monstrous exercise for the new Soviet leader, Gorbachev. Not a one of them had a detector for scalar EM radiation, and not a one of them officially believes the exercise ever happened."
>
> Bearden http://www.cheniere.org/books/ferdelance/s38.htm
>
> "The **Woodpecker grid/howitzer** weapon system can be placed over the ocean and used against cruise missiles, naval surface-to-air and surface-to-surface missiles, submarine-launched ballistic and cruise missiles, etc. Placed over a carrier task force, it can also take care of the aircraft launched by the carrier as fast as they are launched. It can also handily take care of the missiles launched by guided-missile cruisers of the accompanying task force."
>
> (Bearden http://www.cheniere.org/books/ferdelance/s65.htm)

The whole series of the Fer-de-Lance briefing slides and comments is a "must read" for anyone wanting to be aware of the actual state of things in this world right now. It is a new world and it takes some getting used to. Fer-de-Lance speaks clearly, for the layman, of the way things stand.

What is it like to operate these Tesla Howitzers? Col. Bearden gives us an idea in his "Fer-de-Lance" briefing, Slides 66-71.

Who needs armies anymore? A entire war can be fought and won by a handful of men sitting in a comfortable control booth! The scalar electromagnetics revolution has made all previous forms of warfare nearly obsolete.

Why haven't the Russians used the scalar weapons yet?

Bearden gives his thoughts on this in "Fer-de-Lance." The power of these weapons is so great that an accident or war could wipe out all life on earth, and even **affect the sun**.

> "As can be appreciated, this entire concept [MAD] is now totally obsoleted by the Soviet possession of scalar EM weapons.
>
> 'The "mutual assured destruction" capability -- or MAD concept as it was so aptly named! -- is **no longer mutual.** And for two reasons: (1) the Soviet surprise attack could destroy essentially all our Triad forces wherever they are, in the first attack. (2) Even if a very small number of our strategic forces survive, the puny strike we could attempt to launch could be repeatedly decimated from launch to terminal phase.
>
> 'The restraint on the Soviets is not because of our Triad forces. The restraint is twofold:
>
> > (1) a second nation has scalar EM weapons, and would undoubtedly unleash them upon the Soviet Union with great violence if such a massive world-wide destruction of U.S. forces occurred or was threatened (is it really "accidental" that six major Soviet missile ammunition storage sites mysteriously exploded within seven months?);
> >
> > (2) the closed-loop **scalar radiation exchange system of Earth-Sun could be inadvertently "tweaked"** in the feedback loop from Earth to Sun, so that a large solar scalar resonance was stimulated. In that case the Sun could emit a mighty resonant "burp" that would simply **wipe out all life on Earth in a fiery shower**.
>
> 'The "terror" in the "balance of terror" between nations has just increased by many, many orders of magnitude.
>
> 'The biblical prophecy that the Earth will be wiped out by "fire and brimstone from heaven" is very near fulfillment now.
>
> 'Put another way, the pucker factor -- even on the Russians who may contemplate unleashing Armageddon -- is higher than any Western strategic analyst has ever imagined, even **in his wildest nightmares**.
>
> 'Truly these weapons are "more frightening than the mind of man has imagined," as Brezhnev put it in 1975.
>
> 'The frightening scalar EM weapons can be used, but only very, very gingerly indeed. If a slight mistake is made, everybody loses everything."
>
> Bearden http://www.cheniere.org/books/ferdelance/s74.htm

But the Russians (KGB) are not the worst of it. Bearden claims that some of the scalar weapons have been leased to the Yakuza for about a billion a year, and that only the KGB is holding the Yakuza in check from making a **full-scale all out scalar attack on the west.**

U.S. Defense Secretary William Cohen

Warns about eco-terrorism using scalar electromagnetic weapons

> "Others [terrorists] are engaging even in an eco-type of terrorism whereby they can **alter the climate, set off earthquakes, volcanoes remotely through the use of electromagnetic waves...** So there are plenty of ingenious minds out there that are at work finding ways in which they can wreak terror upon other nations...**It's real**, and that's the reason why we have to intensifour [counter terrorism] efforts." - Defense Secretary William Cohen, 1997

In a letter to a writer named "Russell" Bearden says,

"In short, Russell, the Secretary of Defense of the United States confirmed that there are indeed novel kinds of EM weapons, right now and have been for some time, which have been and are being used to (1) initiate earthquakes, (2) engineer the weather and climate, and (3) initiate the eruption of volcanoes. We wrote about those exact uses of the weaponry decades ago. Several nations now have such weapons. Three of them (two on one side and the other on a hostile side) are even firing practice shots into Western Australia, as a convenient test range."

http://www.earthchangestv.com/ufo/0209gandor.htm

See Also:
Examples of scalar weapons testing around the globe

See Also: Powers of the Longitudinal Interferometers

Tesla Howitzers in Weather mode

How to Make Weather

"Engineering the weather is **duck soup**; they tested that over the U.S. in 1967, and entered upon continuing operations over North America on July 4, 1976 as a grim kind of KGB "Bicentennial Gift" to the United States. Here's how it is done with several interferometers.

"First, the interferometers can deliberately make "high pressure areas" (cool the air so it shrinks and its "footprint" pressure on the ground increases because its density increases) and "low pressure areas" (heat the air so that expands and its "footprint" pressure on the ground decreases because its density decreases). Well, if one makes the highs and lows where one wishes them, and judiciously and somewhat slowly moves them along a given path, these highs and lows will entrain the jet streams and thus "steer" the weather.

"So if you wish a very cold snap or attack, go up into Canada and start these actions to steer down some streams that bring some very frigid air. Establish other highs and lows judiciously to "block" or "slow" other jet streams and flows as desired. In this way, one can pull the "large cold air masses coming down from Canada" deep into the southern U.S. at will. They do it regularly. If you wish an ice storm, add an additional current of warm moist air you bring up (steer up by using artificial highs and lows) from the ocean. Where they meet, you will get freezing rain, then sleet, then severe icing accumulating. This type of attack does rather large damage to the struck area."

http://www.earthchangestv.com/ufo/0209gandor.htm

Whole websites have now sprung up showing weather **radar anomalies** which may well be indications of scalar weather engineering. One list of over 500 images is here. Cheniere has its own collection here.

Here is an animated anomaly with cloud formation.

In another section at Cheniere are many photos of **cloud anomalies** which reveal the underlying grid along which the clouds are forming or un-forming. Bearden relates a startling incident in these **ongoing "weather wars**."

> "During the spring of 1986, abnormally strong Soviet weather engineering occurred over the U. S., causing a drastic drought in the southeastern U.S. **This drought was broken by a colleague who used an extremely powerful scalar EM device** to redirect jetstreams. A most unusual and unique signature of the "blocking" against the Soviet scalar EM actions resulted: Two huge circulations developed in the atmosphere, clearly showed as two adjacent giant "holes" in the swirling cloud cover over the middle and eastern U.S.
>
> "Between these two giant holes, the cloud circulations formed a stream of clouds, moving to the south, looking very: much like a giant vertical "bar" of a huge "Y-shaped" cloud flow.* Several national weathermen commented on this unusual pattern, which had not been observed before. The pattern continued, day after day, as the blocking continued."
>
> * On the weather maps.
>
> http://www.cheniere.org/books/analysis/history.htm

Tesla Howitzers in Earthquake mode

How to Make an Earthquake

"Here's how you initiate a very large earthquake with such weapons. Take a convenient fault zone of set of them. Focus the interferometry on the fault zone, in the "diverging" mode, and deposit EM energy there in the rocks on both sides, increasing (slowly) the stress in the rocks by the reverse piezoelectric effect (deposit excess energy, get crystal mechanical movements).

"Do it slowly, and the stress will build up to large pressures well-above a plate slip minimum energy required. At some point, the rocks yield and one or both sides "slip" and move rather sharply, giving a very large earthquake in that zone.

"Do the same thing down in the earth (remember, LWs easily penetrate right through the earth and ocean at will, and so the "interference zone" focus can be inside the earth or beneath the ocean, at will.

"Anyway, focus this thing down to where the active part of the volcano is still slumbering, down where the hole in the plate has been made. Keep increasing the deposition of energy in the magma itself, and eventually the increasing pressure from deep within that volcano, underground, will cause an eruption. Build the energy slow, and the eruption will likely be much larger."

http://www.earthchangestv.com/ufo/0209gandor.htm

Yugoslav Earthquake, Followed by Cold Explosion
Strange Characteristics of Iran Quake, Sep. 1978

Tesla Howitzers in Tesla's "Big Eye" mode

How to make a Big Eye in the Sky

By using longitudinal wave interferometry in a weakly endothermic mode a new kind of "radar" is now possible, one which can look right through the earth and oceans. Because the endothermic mode extracts energy from the distant target, a pattern of the target area can be scanned for in the returned energy.

"Thus the receiver produces a representation of the energy extracted from various locations within the distant endothermic zone. By displaying the received signals on an appropriately scanned screen, a representation of the distant scene in the intersection zone can be created. Indeed this is a special kind of "microwave interferometry," and -- with modern techniques -- the imagery obtained might be surprisingly good. With development, it might even become as good as the image presently obtained by side-looking acquisition radars.

"Interestingly enough, since scalar EM beams will easily penetrate the earth or the ocean, one can also look beneath the earth or beneath the ocean with this type of scanning scalar interferometer.

"The importance of this capability to strategic and tactical reconnaissance is obvious. Camouflage, cover, and concealment have no effect on such a system. One can easily look inside buildings and into underground facilities. With a small system such as this, the U.S. Marines at Khe Sahn would have had little difficulty locating the tunnels continually dug under the perimeter by the Viet Cong. And targets under jungle canopies are directly visible."

Bearden http://www.cheniere.org/books/ferdelance/s42.htm

Tesla Howitzers can destroy all life on earth

How to Make a Storm on the Sun!!

(Just make a big mistake with your Tesla howitzers)

The **deepest dangers** of the use of scalar weapons are frighteningly pointed out by Bearden here where he considers that the sun, earth and moon (actually the whole solar system) is a delicately balanced arrangement of scalar (longitudinal) EM radiation. There is a scalar connection between the earth and the sun, which are both giant dipoles gushing energy in the time domain. Big scalar events on the earth could alter this balance causing **true catastrophe**.

"Indeed, a solar response could be stimulated so that the Sun would violently belch and destroy our biosphere, among other effects."

Unrestrained scalar warfare could cause huge solar storms? To realize that **human activity** could actually **affect the sun itself** is truly mind boggling.

Bearden goes on to say:

> "Accordingly, use of huge scalar EM weapons is a double-edged sword. Unless carefully employed, use of the weapons could cause a terrible backlash to the user as well as the victim, and even accidentally cause the **destruction of the earth itself**. It is not accidental that in 1960 Khrushchev stated that his new fantastic weapon could -- if unrestrainedly used -- destroy all life on earth.
>
> "This appalling backlash potential is apparently what prompted Brezhnev in 1975 to make so strong an effort to get agreement to outlaw the development of "new weapons of mass destruction" more frightful than the mind of man had even dreamed of. Gromyko even introduced such a draft agreement into the proceedings of the United Nations. The first article of the draft agreement indicated that the nature of the weapons referred to would be negotiated. Sadly, the entire Western

> world did not even know what the Russians were talking about."
>
> http://www.cheniere.org/books/ferdelance/s24.htm

2. Tesla domes provide near-perfect defense shield.



(Slide from Cheniere.org)

The Tesla howitzers can be used in a nearly **impregnable defensive mode** whereby they throw up a dome (**Tesla Dome**) or a sphere (**Tesla Globe**) of highly powerful electromagnetic energy, enough to "dud" or destroy missiles which try to penetrate them. Once again, this energy is not going through space from the howitzer, but being made to emerge from the local vacuum **at the location of the shell**. KGB tests of these domes have been witnessed by airline pilots around the world. Bearden gives many examples of the Tesla domes being sighted around the world in his briefing paper "Fer-de-Lance." (Russian dome test, another globe incident, yet another globe test). These giant electromagnetic domes can be hundreds of miles across, or narrowed down more to total impermeability.

> "Such a shell may be several hundred miles in diameter at the base. The enormous energy required to form such a defense shell is obtained by a "scalar power tap" into the **molten core of the earth itself**, as previously explained. In late April/early May of 1985, 27 such "**power taps**" were placed in the earth by the Soviets. If each tap is capable of powering four to six large scalar EM weapons, then the **Soviet strategic scalar EM arsenal contains over 100 monstrous superweapons** capable of generating exothermic explosions, endothermic explosions, engineering the weather, locating and destroying underwater submarines, detecting and destroying ballistic missiles shortly after launch, detecting and

> destroying long range strategic bombers as soon as they are airborne, etc."
> http://www.cheniere.org/books/ferdelance/s52.htm

By using nested domes one can protect the domed area **even against nuclear radiation itself**. Tesla globes can be used to hit airborne targets by simply placing a globe of any chosen size in the flight path of the incoming missile. It does double duty because the missile hits it going in, and then the rubble hits it again going out the other side.

While the U.S. persists in its useless boondoggle "missile defense system" by shooting a missile with a missile (missiles which would already have been "dudded" by the Tesla howitzers), between the domes and the globes the Russians (KGB) have in hand (**operational**) a nearly **perfect missile defense system**. Someone should ask the Secretary of Defense if the U.S. Tesla domes are in place. And over which cities? How powerful are our American Tesla domes?

Bearden cites a number of examples of these domes being tested around the world: March 20, 1969 | March 24, 1977 | August 17, 1980 | June 17, 1966 | June 18, 1982 June 22, 1976

In a slide from the Fer-de-Lance briefing it is shown how the "woodpecker grid" itself also acts as a sensor, detecting any missile launch anywhere, and how the howitzers can respond instantly by delivering a blast to exactly the right coordinates, right along the channels of that same grid which is feeding the location information about the missile launch. This certainly beats "trying to hit a bullet with a bullet." Especially since YOUR bullet would probably be instantly inoperable in a real scalar war situation.

3. Rogue Groups in the government

Bearden fears that these scalar electromagnetic secrets may have fallen into the hands of what he called secret "**rogue groups**" within the labyrinthine depths of the black-ops special-access domain of the secret government. "In the extreme, such a deep black program can even become a "captured" program," he says, "which is totally in the hands of rogues and **no longer reports to or is bound by the dictates of the parent government**."

> "They have their own agendas. And being rogue groups, they may well bring in **unethical, immoral tricks**: assassination, bribery, entrapment, disinformation, plausible deniability, etc. A certain percentage of a highly secret rogue group will wind up using all these things and more. **It's a human characteristic, the old primate dominance game. Only now disguised and hidden under deep classification. ...**
>
> "In highly classified groups, these groups are greatly enabled to joust more widely, unethically, and immorally because it is so deeply hidden. So very deep classification evokes the growth and intensity of rogue groups. It's the old 'Power corrupts, and absolute power corrupts absolutely' routine. ... Due to loose formation of rogue groups inside such programs, they may have dual or triple purposes, **may not operate under very much legitimate government control at all**, and may operate specifically for the purposes of the rogue group or groups that have gained control."

> "The involvement of at least some rogue groups, some being "**cowboys**" who operate well **outside all laws and ethics**, could also result in such things as assassinations, clandestine testing on individuals without their consent, etc. In short, ***it could account for what seems to be actually occurring***. "
>
> http://www.cheniere.org/explore%20articles/mind%20control3/p05.htm

4. World War III has already begun

Because it is now possible to cripple the power grids and electronics of any nation, that nation could be reduced to economic ruin without ever firing an actual "shot." Without electricity Wall Street cannot operate. Without electricity you quickly need martial law. One no longer needs to wage a conventional war anymore at all. There are now **lots of new ways to bring any nation to its knees**.

> "We are at war, whether we like it or not. And we are going to have strategic strikes on an unparalleled scale for us. Pearl Harbor was nothing compared to what is coming down, once we consider the "augmentation" and such.
>
> "When that factor is considered, then it's a totally new ball game on replacing the power system. There isn't going to be much choice; the old one is going to be destroyed or so badly crippled that **it will collapse the U.S. economy** in a way we have not seen since **1929**. Of course, in such a case hitting us, we will be under martial law, the works, everywhere. For one thing, it's the only way you can keep the cities from imploding from within, by the criminal element, looting, robbing, killing, etc. Simply wait and see; it's on the way."

Although Bearden has for years decried the "scalar-gap," and chided the military for falling so far behind the Russian KGB in the field of scalar electromagnetics, recent statements indicate that things may at last have changed somewhat.

> "In the new war, the first phase of WW III has already been completed. Hence President Bush's recognition that this is a total war, and has to be taken to the enemy no matter where he may be hiding or in what sanctuary or in what foreign nation. This is an entirely different war than anything the U.S. has ever fought in its history. **And before it is over, it is going to kill more Americans than have died in all the previous wars in our history. The news media and the public have not yet recognized that awful situation and predicament.** Most are already thinking that, well, we won in Afghanistan so it's just about over. Instead, it has only just begun.
>
> "Anyway, that's a brief uptake on some of the weapon situation today. Some 10 nations or more now have LWIs, and five have the QPs. I'm still working on how many have the appalling negative EMP weapons, but would estimate 6 or 7 nations have them in one stage or the other, either deployed or in at least advanced development. And in my estimation, the Yakuza will have them within three to five years if they have to build them themselves, and quicker if they can buy them from the Russians, Chinese, or???" Bearden

When he was asked the question "**Does the government listen to Tom Bearden?**" Bearden said:

> "Let me speak carefully. I am very satisfied with how I've been listened to in the quarters where the rubber meets the road. **The West is no longer defenseless, not by any means.** Cannot amplify it further than that."
> http://www.cheniere.org/correspondence/021102a.htm

Bearden has briefed the government a number of times and the Cheniere website contains a great number of his graphic military briefing slides.

5. Are the Russians making "UFOs?"

Scalar electromagnetics engineering opens the possibility of antigravity vehicles and "hyperspace travel." In other words we can now make our own UFO's! Of such **scalar-powered antigravity vehicles**, which have now become possible, Bearden has this to say:

> "We might expect to see such vehicles glowing. Their various surface features and mechanisms might appear to be glowing or revolving lights, etc.
>
> "They could exhibit incredible "aerodynamic performance," seemingly in the atmosphere. **Actually they would not be moving "through" the atmosphere at all, but through a higher space outside each particle of atmospher**e.
>
> "They could seem to **materialize** and **dematerialize**.
>
> "They could seem to plunge into the ocean or rise out of it.
>
> "They could even seem to operate under the ocean or inside the earth itself.
>
> "**Such anomalous vehicle performances have been seen all over the world**, particularly since a few years after WWII.
>
> "It appears that one or more nations of Earth are operating such vehicles now **in great secrecy**. Our own "government" may even be one of these.
>
> "If so, it **isn't** our true "government/government." Instead, it's the "control group/government." It's government at the operational level, but at higher level **it belongs to certain control groups who have penetrated our government's vitals and taken over all such projects**."
>
> Bearden http://www.cheniere.org/books/ferdelance/slide32.htm

In an excellent article on her Earthfiles website, Linda Moulton Howe reports on the utter bafflement of Norwegian scientists over mysterious lights appearing in the valley of Hessdalen, Norway.

She writes of the research there: "The results can be broken down into two groups: 95% are thermal plasmas and 5% are unidentified solid objects. The plasmas emit long wave radio frequencies and strangely, their temperatures do not vary with change in size or brightness." She quotes the scientists' research summary:

> "1) most of the luminous phenomenon is a thermal plasma;
> 2) the light-balls are not single objects but are constituted of many small components which are vibrating around a common barycenter;
> 3) the light-balls are able to eject smaller light-balls;
> 4) the light-balls change shape all the time;
> 5) the luminosity increase of the light balls is due to the increase of the radiating area. **But the cause, and the physical mechanism with which radiation is emitted, is currently unknown**."

This would almost certainly seem to be another example of the testing of the scalar howitzers. It is baffling because, as Bearden points out repeatedly, Western scientists have limited knowledge of the scalar electromagnetic principles by which the howitzers operate. The Hessdalen scientists were completely **baffled** as to where the energy of these plasma balls **was coming from**.

Ms. Howe interviews Massimo Teodorani, Ph.D., Astrophysicist, who released the report on the 2001 Hessdalen sightings. The scientist speaks of the baffling phenomon observed.

> "I don't know how it is possible that Nature is spontaneously able to do that. Anyway, we deduce that the plasma is trapped inside a sort of magnetic cage and the magnetic cage closes around the plasma and keeps it fixed in some way, prevents it from expanding. **But where does it come from? We don't know**."

By what we have been considering here, we can recognize the signatures of scalar electromagnetic engineering. If it is a Tesla howitzer, then the energy for the plasma balls **is coming from the vacuum of spacetime** at the very **location of the balls themselves**, triggered by scalar interferometers aimed through the woodpecker grid.

These kind of balls can be used as **marker beacons** giving feedback for precision aiming of the howitzers. The energy of the marker beacon can be read back into the computers giving precise location information for pinpoint aiming. The target area can be very small, or widened out.

There is a little movie of one of the Hessdalen plasma balls here. It would seem to be a clear documentation of a scalar howitzer marker-beacon. How many other current "UFO" sightings are actually the witnessing of Tesla howitzer tests?

In fact there are a great many **anomalous events** of the past few decades which might very well be explained by the Russian testing of their longitudinal electromagnetic weapons. It would seem that the mysterious appearance of crop circles around the world could be accomplished by feeding a precise mathematical graphic pattern into the computerized aiming software and change the very molecular structure of the crops themselves along the lines of that pattern. The stalks fall over from the localized effect of the longitudinal waves. A plasma ball tracing patterns? Are they slyly sending a message to see if we are "getting it" yet?



The "Cambridge Angel" - Made by Russian scalar plasma balls?

Also see: Interview with Tom Bearden



Attempt to Ban Energetics Weapons Worldwide

- On June 13, 1975, in a major speech Brezhnev urged the United States to agree on a ban of research and development of new kinds of weapons "more terrible than anything the world has known."
- On July 2, 1975 Brezhnev repeated his proposed ban on development of frightful new weapons, to a group of U.S. Senators.
- In August 1975, Ponomarev called for a ban on frightful new weapons of mass destruction.
- On Sept. 23, 1975 Gromyko presented a draft treaty agreement to the 30th Session of the UN General Assembly, for banning development of frightful new weapons.
- No one had the foggiest notion what the Russians were talking about!

© 1996 T.E. BEARDEN

(Slide from Cheniere.org)

4. Healing powers of longitudinal waves

Healing via longitudinal waves, time reversal of cells (de-differentiation), Priore's machine, Bearden's proposed "blanket" version, using the electric power grid for healing waves or for broadcasting disease patterns. Scalar Biowar.

The good news!

"**Any sort of disease whatsoever - physical or mental** - will be rapidly curable, simply and cheaply. It will be possible to reverse aging and rejuvenate the person. It will be possible to regrow limbs and straighten misshapen spines - and directly remove the causes of mental diseases and cure them as well. Lifespan will be staggeringly increased, without 'old age's debilitation.' AIDS, cancer, leukemia, and genetic diseases will be completely conquered. The potential for a true golden era is upon us, for all humanity."

Bearden- http://twm.co.nz/beard_interview.htm

Proof of the healing powers of longitudinal waves from the vacuum is seen in the work of Antoine Priore who produced longitudinal scalar waves using a **gigantic glass tube** filled with plasma. He himself did not understand why it worked or how it cured cancer in animals.

> "The Priore team cured terminal tumors, trypanosomias, and other dread diseases in laboratory animals in France, in the 1960s and 1970s, under rigorous scientific protocols by eminent scientists. The Priore

project was funded by the French Government to the tune of several millions of dollars (equivalent). http://www.explorepub.com/articles/energetics.html

> ". . . Prioré's machines concretely demonstrated a nearly 100% cure of all kinds of terminal cancers and leukemias, in thousands of rigorous laboratory tests with animals. These results were shown to medical scientists as early as 1960." http://www.cheniere.org/priore/index.html

Bearden has stated that the longitudinal EM waves can have a healing effect because they always come in pairs called "**phase conjugate pairs**" and one of the pair is **time-reversed**. This enables engineering of the waves to "pump" the cells of the body (with waves from the time domain) and actually **time-reverse the cells** back to a previous healthy condition. The scalar cure of cancer does not involve killing the cancer cells but rather pumping them with time energy into a previous condition. I know, this seems miraculous, and is it not?

Priore and his giant plasma tube

This healing power in the longitudinal waves of the time domain is a mind-boggling thing to face. It took me months to get through it, and to **suffer the fact** that the **cure** for cancer and AIDS was right there, **in this new scalar electromagnetics technology**, and that it has been kept back from the people for so many decades now.

Bearden has a great deal to say about the work of Antoine Prioré, who himself did not understand why his machine worked. Priore did not know about the longitudinal scalar waves of the time domain. In fact, Tom Bearden has supplied, at last, the missing explanation as to how that **big giant two-story glass tube** consistently cured cancer in animals.

> "**The medical implications are enormous**. By just reversing the damaged cells back to a previous physical state, this gives a physics mechanism for *controlled cellular dedifferentiation*, in biology terms. Physicians will **time-reverse diseased, damaged or aged cells** back to an earlier healthy condition, including all the cellular genetics. Normal cells are just reversed to a slightly younger condition."
>
> "We believe this mechanism explains the revolutionary but baffling electromagnetic cures achieved by a team of outstanding French scientists in the 1960s and early 70s, working with inventor **Antoine Prioré**. In lab animals, cures were achieved for terminal tumors, infectious diseases such as trypanosomiasis, and atheriosclerosis. In addition, deliberately suppressed immune systems were dramatically restored.

> "We hypothesize that this is the long-sought mechanism of how the living body heals itself. In short, the body's cellular control system induces **cellular reversal by weak time-domain pumping** of the damaged cells and the affected area. The cellular regeneration system performs all healing of cellular damage in the body; the immune system heals nothing, not even its own damaged cells) .
>
> "For the first time medical science can develop as a science of *healing* rather than a science of *intervention*. And it will develop as a science of *unlimited* healing, since **no pathogen can resist action by curved spacetime engines**." Bearden

http://www.cheniere.org/techpapers/Vision%202000%20paper.doc

See Priore's machine See Slides of how it works.

Bearden has extended the Priore work, with the previously missing knowledge now in place, and designed a revised system (for irradiating the body with longitudinal waves) which gets rid of Priore's giant glass plasma tube and uses instead an **antenna unit which surrounds the body**. He has also provided the missing explanation of how it works. There is an article from "Explore" magazine, Part I and Part II.



RETRORADIATION WITH EMITTED TW EM WAVES

Adjusting broadband signals bandwidth and amplification

Using an amplified replica of the body's own dense, broadband signal complex to irradiate it, producing deeply-penetrating and precise longitudinal EM wave sets that pump cells and reverse cellular disease and damage

(Slide from Cheniere.org)

In fact, Bearden has presented to the U.S. government a plan to use a **portable version** of a **Scalar Healing Blanket** where wire channels in the blanket act as a scalar antenna, which can both send and receive scalar electromagnetic waves. A **two minute treatment** of the waves is sufficient to restore the body to its earlier healthy condition. Thus even **thousands could be treated easily and quickly in a biowar mass attack** situation.

> "To defend against things like anthrax attacks on our civilian population centers, we also have recommended to the U.S.

> Government the crash development of small, portable treatment machines—using similar "antiengine-forming" and cellular reversing "porthole technology". [See Figure 13 on previous page]. Such portable machines **could be developed cheaply and quickly**, and present government facilities could be used to massively attack the correlate database production problem.
>
> "The portable treatment **units could be cranked out by the hundreds of thousands** and flooded down through emergency response agencies such as the police forces, the National Guard, emergency hospitals, emergency response teams, etc." - Bearden


Portable Priore-Type Treatment System
Equipment Case
Computer Control Unit
Infolding Function Generator
Antenna Pad

(Slide from Cheniere.org)

The **Scalar Healing Blanket** would fit into large suitcase. It has three basic parts, the longitudinal wave generator, a laptop computer, and the antenna-blanket. The plan was a stroke of Bearden's genius, but unfortunately it fell on **befuddled government ears**. "Unfortunately, so far the DOD [Dept. of Defense] doesn't even understand what the heck we're talking about!"

Article "Healing with Energy": http://www.explorepub.com/articles/energetics.html

> "We tried very hard in 1998 to call attention to the extreme national need for the most urgent possible development of a portable computer-controlled treatment device based on the experimentally proven Prioré methodology, but extended to a much simpler and far more rapid method of treatment.
>
> "Quick development of this technology could lead to **a suitcase size device, capable of treating a patient in less than one minute, and stopping the symptoms and disease progress cold, then reversing it**. Three "less than a minute" treatments one week apart would be required for complete cure. As an added advantage, partial reversal of aging in older patients would also be accomplished as a bonus, in addition to time-reversing the damaged and diseased cells...
>
> "The method proposed to the DoD in 1998 used normal EM in a peculiar way to force the body itself to make its own time-polarized

> EM waves, and pump every part of its cells -- including the genetics -- in the time domain.
>
> "Quite simply, we are going to be struck this way (QP spreading the immune systems of the populace plus professional smallpox, anthrax, etc. BW attacks on our population centers) and by other means we've spoken of in other papers and briefings."
>
> Bearden http://www.cheniere.org/correspondence/021401.htm

The Dark Side of the Force:

Creating and broadcasting disease

Speaking of the scalar wave induction of disease by longitudinal wave patterns Bearden refers to work by French scientist Kervran and Russian scientist Kaznacheyev, who proved that any disease could be transmitted electromagnetically.

> "It works this way: the Kaznacheyev experiments (and others) demonstrated that any cellular disease or disorder can be initiated into cells at a distance, by electromagnetic means (albeit unusual EM in nature). The decades of microwave radiation of the U.S. Embassy in Moscow, was an ongoing set of "stimuli" to ping the U.S. system and, by its response, ascertain how far along (or if it was "along") in its knowledge of such weapons. The radiation was responsible for many health changes in personnel and for the **eventual deaths of three U.S. Ambassadors**." Bearden http://www.cheniere.org/correspondence/021702a.htm

In a letter he writes,

"Yes, the Kaznacheyev experiments were quite real; 15,000 or so in military research institutes in Siberia. As with so many other novel areas investigated and developed by the Soviets, most U.S. investigators just assumed normal EM, which is not what the Kaznacheyev experiments involved, and not what was carrying disease induction patterns from one cell culture to another in rigorous lab tests."

How to "Broadcast" Diseases

Longitudinal EM Biowars

Bearden explains how the new quantum potential weapons can be used to induce disease-at-a-distance in a population, or to "spread" the immune system so thin that a **conventional bio-attack would be greatly potentiated**. By "broadcasting" virtual disease patterns over a population, the immune system is so overloaded by the presence of the **"shadow" diseases** that its effectiveness is thinned out.

> "In short, alter the internal wavestructure, and one creates a curved spacetime 'engine' that acts on mass in any fashion one chooses to design -- including initiate diseases . . . Now visualize one of these '**vacuum engines**' or 'spacetime curvature engines' that **acts on mass** to **generate the exact effects produced by anthrax**. (Or any other disease one wishes) . . .

Call the virtual state of a disease engine the disease pattern in the "shadow" state, just prior to becoming observable. . . .

"And the master cellular control system responds to "coming events that cast their shadows before". In short, it responds to the upper level of the **"shadow state" of a disease**, still in the virtual state! (Hey, virtual particles are real, virtual photons are real, virtual ST curvatures are real --- just very fleeting, only for another to immediately arise). The exchange of virtual particles is known to generate all forces in physics anyway! . . .

"So the cellular control system responds to "shadow state" disease patterns. Enter a QP weapon application. Place a quantum potential weapon "area" on the United States, so that the entire populace is in it. The slowly introduce and bring up in the shadow state, the **necrotizing fasciitis disease engine**. At some point, the cellular control systems will react, and order the immune system into action. In other words, immune system resources will be committed against this "immediately coming" enemy. Bring it on up a little, but still just in the shadow state. Voila! Humans form a bell-shaped distribution curve. And even if the structure of the QP fluctuates a little, fluctuating a bit stronger and a bit weaker, etc. **A few of those targeted bodies will now actually develop necrotizing fasciitis**. So far, just like the U.S. Embassy targeting, except a different "carrier".

"But now there is an exact signature that this is what is doing it, and not normal vector carriers of disease and contact or exposure infection. **The few cases of necrotizing fasciitis that break out will be most puzzling.** They will be randomly scattered across the entire nation, and so few that the vector carrier and contact or exposure explanation completely fails."

"And that one happened, right here in the U.S., not so long ago. Check it out.

"So carefully adjust the **patterns** for, say, 12 major terrible diseases, to that "adjusted and desired shadow state level". Now add all 12 patterns into the internal structure of the quantum potential. Now it has **12 shadow state disease engines** in it.

"**Place that one on a populace**. The cellular control systems order the immune systems into action, and they now have to commit their finite resources to 12 different areas. This greatly thins the response an immune system can make to any one of those 12 disease patterns! In short, it "**spreads**" the capabilities of the immune system, which can be galvanized to great effort, but only can perform a small bit against each area.

"Suppose one of those "galvanized" areas in the targeted populace's immune systems is anthrax. And suppose the bad guys now hit one or more of those cities with a professional anthrax attack. A former OTA study showed that a professional anthrax aerial spray attack against Washington D.C., dispensing

> 100 kilograms of anthrax spores in the spray, will account for 1 to 3 million casualties. And that's in an "unthinned" set of immune systems. **In the "thinned" set, one can at least double or triple, and even up to five times, that estimate.** So conservatively, now there would be from 2 to 6 million casualties. And even mild anthrax spray attacks in other "thinned" cities would also be amplified.
>
> "**That one is being set up, or already set up, right now.** There are other such "augmentation" setups also under way.
>
> **"So the weapons alluded to by the SecDef in 1997 are already being employed. WW III has already begun, and our populace (and our scientific community) is blissfully unaware of it."**
>
> http://www.cheniere.org/correspondence/021702a.htm

Most of us can remember the strange outbreaks of the so-called "**flesh eating disease**." It seemed to break out here and there randomly with no known cause. Bearden believes this was a test of the newer quantum potential weapons which go even beyond the capabilities of the Tesla howitzers.

> "The Kaznacheyev "disease induction by novel electrodynamics" work is also the basis for the spacetime curvature engines (not EM signals!) carried by quantum potential EM biological weapons for distant induction of diseases etc. into the population of an entire nation or area, such as the U.S.
>
> "This **quantum potential disease induction weapon** -- capable of attacking an entire population of a nation or area -- has been tested several times in the U.S. at very low levels, in the shadow state only (we explain shortly) and it has a most peculiar signature. E.g., **one test used necrotizing fasciitis (flesh-rotting disease) engines**.
>
> "The disease 'engine' was deliberately kept down in the 'shadow state' (virtual state, just below the observable state) so that only a tiny bit of the populace with depressed thresholds would "breach the observable threshold' due to the population forming a bell-shaped curve as to the threshold level. **The major signature of the test was that the cases of the disease broke out totally statistically and randomly**, spread all over, without any 'disease vector' in between.
>
> "In short, it was not spread in any manner required by normal deterministic disease vectoring, **but was a totally random set of occurrences**. Several other diseases were also tested this way in the American populace, with precisely the same signature."
>
> Bearden http://www.cheniere.org/correspondence/021401.htm
>
> "Apparently one planned use of such an augmented clandestine BW weapon will be smallpox, e.g. As you know, the Russians

> did develop smallpox for biological warfare, and even developed a new strain against which previous vaccination is ineffective.
>
> "The vast numbers of expected casualties, coupled with immune system spreading, are absolutely irresistible to the Russian mind. You can count on it that they have seen that the smallpox is already on site here, in the U.S. and in the hands of professional terrorist teams. Of course, the Russians/KGB will protest they have nothing to do with that! Yet likely the KGB will have flatly arranged it or at least assisted it. The capability for mass destruction of the nation is so lucrative and easy to achieve in advance, that **they would never be able to resist doing it**."
>
> Bearden http://www.cheniere.org/correspondence/021401.htm

Bearden believes the **Gulf War Syndrome** involved the use of scalar technology to induce a disease state, as he stated in a 1997 interview:

> **"I'll say this flatly, and I won't answer any further questions about it; the Gulf War Syndrome was induced...** It was induced with this stuff. All the rest... was contributing factors that everybody's talking about... There are some deeper signatures, if you look into it very deeply, that show you exactly how it was done and the fact that it was induced. It was a test. It was a test of a very special kind of weapon I have not talked about yet. Anyway you can use it to create diseases."
>
> Bearden http://twm.co.nz/beard_weapon.htm

Besides using the woodpecker grid to target a population, the entire **electrical grids** of nations can be used as "channels" for disease patterns to be broadcast to all people near that grid. Your own house wiring can become an antenna, broadcasting these "shadow" patterns of disease, weakening your immune system.

And here one faces the frustrating fact that the same power grids could be set to channel patterns which would keep the entire population healthy, rejuvenated, continuously bathing in the time-reversing old-age-defying energy of the spacetime vacuum. We have **no idea yet** of how long the human life span could be increased with this new technology. People might be able to live two centuries given full humane development of this technology.

5. Psychoenergetics

Mental entrainment, inducing hypnogogic trance, mind control, broadcasting thoughts and feelings, the Ant World, education via EM [LW] mental download, the "Feelies," revolution in spirituality, "enlightenment machine?" Scalar churches?

Psychoenergetics is simply using the scalar interferometers to manipulate and **engineer the human psyche**. To me it is the most **mind-boggling and frightening** aspect of longitudinal wave engineering.

The mind is electromagnetic in nature, and itself of the time-domain. It is not observable in 3-space. There is no **thing** you can point to that is the mind. As Bearden says, "**The mind is time-like**."

The longitudinal scalar EM waves are also of the time-domain. By overlaying certain infolded patterns (oscillations in time) on the longitudinal waves, **a thought or feeling may be made to arise in a person** or persons who are in the interference zone (where the wave beams cross).

The person will not notice anything, feeling that this thought or idea is his or her own idea. The longitudinal wave pattern might be a wave of panic or fear that spontaneously sweeps over you, perhaps inexplicably. It could even be in the form of a sudden intense patriotism. It could be explicit words and phrases, which everyone would think they had thought of by themselves. Or it could be rage and hatred, angry and violent. On the other hand It could also be a continuous sense of docility and placidity. This is the brave new world of psychoenergetics and the coming "**Mind Wars**."

Scalar Psychoenergetics in its most **primitive form** simply "entrains" all minds in the target area into a **deep hypnogogic trance**. In this state of mind people would be suddenly extremely suggestible, and would likely believe anything they are told, and would obey any orders given. Talk about winning the hearts and minds of the American People!

Tom Bearden makes me think of **Paul Revere**, who heroically conveyed important **warnings** for the sake of the new nation. But the words of the famous phrase have now strangely and curiously mutated into the once-inconceivable: "**One if by land, Two if by mind.**"

Indeed one strategy in a **Mind War** would be to simply **take over the minds of the "leaders"** of the enemy nation. The targeted leader would not be aware that anything was amiss, although he might begin to make unexpected changes in policy.

And are, in fact, any of our "leaders" already having secret thoughts that are not their own? Who knows? Frighteningly, we can no longer be sure. The new sciences of scalar electromagnetics and psychoenergetics are even now plunging humanity into a sudden science-fiction-like world beyond anything in humanity's previous imaginings.

> "The Russians reached the point in the mid 1990s that they could **take over control of a person's mind**, with modified longitudinal EM waves including some time-polarized EM waves, and with a team of specialists (estimate 25-30 per transmitter, and one transmitter and team per controlled person)." Bearden

In a slide Bearden illustrates how a Scalar War would involve a **psychoenergetics attack** on the operators of the enemy scalar installation, entraining their minds into hypnogogic trance and **getting them to shut down their systems**.

And ultimately psychoenergetic warfare goes to the very heart of **human identity itself**. For if my thoughts might no longer be "mine," then **who and what am I?** Can my very sense of being "me" be hijacked by some nefarious psychoenergetic scheme? Will the "secret government" eventually dictate directly into your mind how you feel about yourself? Or what you think you are? Or what you should do?

How Does Longitudinal EM Mind Control Work?

The physics of scalar psychoenergetics as expounded by Col. Bearden seems even more arcane and over-my-head than that of extracting energy from the vacuum. I can't understand it, but I look through it anyway. Each time another tiny understanding might occur, or a term might fall into place. I know the mathematics is forever beyond me.

One paper to begin with is Mind Control and EM Wave Polarization Transductions This is such serious stuff that Bearden includes a **strong warning about misuse of this knowledge**. Psychoenergetics weapons can mentally maim and physically kill.

Warning!

(From "Mind Control and EM Wave Polarization Transductions")

> "This article refers to experimental research techniques which can be detrimental or lethal in the hands of any but highly skilled, qualified experimental scientists proceeding under proper laboratory safety procedures. The purpose of this article is strictly for information to properly qualified and authorized scientists in certified laboratories. We do not propose or condone any use of these procedures for nonapproved practice of medicine without a license. Neither the publisher nor the author are responsible for accidents or outcomes in the use of these experimental procedures and techniques. Any researcher who performs these procedures and experiments is acting on his or her own volition, and is solely responsible for insuring safety, qualifications, and legality of the acts and their results. **We neither suggest nor condone unauthorized experimentation on human subjects. Such is a criminal violation of the constitutional rights of the subject under Federal and State laws, and is both illegal and immoral**." Bearden

After the **serious warning** comes the description of the paper. This is heady stuff for the layman.

> "Calling full attention to the special note above, in this paper we present a high-level overview of the novel electromagnetic nature of mind operations, mind and body coupling, and intent - the induction of physical 3-space EM energy changes into the brain and nervous system, and into every cell of the body, from the mind's time-like coherent operations. We summarize the time-polarized electrodynamics used to engineer and affect mind operations and the mind-body coupling loop. Transduction mechanisms whereby differing EM wave polarizations can be transformed one-into-the-other are presented." Bearden

I will leave it to the technically astute to try to understand the mechanisms of operation which are described in scientific language. But there are tidbits for the layman. Here he speaks of the difficulty Western scientists have in opening up to the "immaterial" (longitudinal wave) nature of the human mind.

Western Science Remains Largely Materialistic

"Ironically, most Western scientists are materialists and consider "mind" as a mystical and nonscientific concept. They tend to consider mind operations and functions either to be simply "meat computer" operations and functions, or at best to be very weak ordinary transverse-wave EM operations and functions in the brain and nervous system. This serious self-limitation exists because in the body we measure only weak TW [transverse wave] EM operations and functions correlated to biological behavior and brain operations. We simply do not know how to measure "mind operations" directly.

"With no mind measurements possible and no instruments, it is understandable that Western science considers only the physical side of the mind-matter interface.

"Presently our scientists do not measure the longitudinally-polarized EM wave operations and functions in the body and around it in nature. Few of them are aware that a maelstrom of such LW [longitudinal wave] functions exist in the body and in all of nature in general." Bearden

Western methods of influencing the mind with EM waves have only used transverse waves, not the longitudinal waves of the vacuum. If only transverse waves are used one pretty well has to hit the target mind with a **sledgehammer of waves**.

Western Science knows only transverse EM waves

Brute Forcing Time Functions versus Fine Control Methods

"Ironically, Western mind control researchers using transverse EM waves for mind control research, are using a brute force method of evoking and using vacuum engines (spacetime curvature engines) and a special form of general relativity, although they do not appear to realize it.

"While KGB scientists also use TW EM "brute force" TW waves when necessary, they do **"imprint" or "activate" those waves with the desired internal LW and time-polarized EM wave and photon structures** required to directly perform the mind engineering desired... Bearden

"These "fitted brute-force models" certainly can be very powerful, and certainly can produce the exact results shown in the experimental verifications of the fittings. However, they do not of themselves allow sophisticated design for example of the necessary time-polarized wave assemblies for **engineering the entire human collective unconscious simultaneously**, or for engineering the entire collective unconscious of all species on Earth (i.e., Gaia's collective unconscious), or even for precisely **engineering the memory and knowledge base of an individual**. Bearden

The seemingly magical operations of psychoenergetics, sometimes called "psychotronics," cannot be achieved with ordinary transverse EM wave energy. But they are possible with longitudinal scalar waves because the mind itself is scalar in nature.

> "We note that **all mind operations are time-like**, i.e., they are comprised as scalar EM photon functions and scalar EM wave functions. Thus the mind is a very special kind of electromagnetic system, existing in the time domain..." Bearden

The engineering of the mind can only be accomplished with the waves of time.

The course of psychoenergetics development necessitates the building of a vast database of settings and patterns which bring about given mental and/or emotional states. A kind of "**genome**" of the psyche. Bearden describes the process of the decoding of this "genome."

> "Now the scientists would perform many phenomenology experiments, making one little change at a time and profusely recording the data. Each time, they would establish the physical change(s) that occur in the body and/or the mental and emotional changes that occur in the mind for each spectral reinsertion back through the "ship's portholes". They would simply but painstakingly (over some years) build up an extensive database of those individual correlates.
>
> "In these experiments, the experimenters will eventually be able to **provoke any body or mind change they wish**. Strong emotion. Intense pain. Intense pleasure. Painful thoughts. Images. Memories. Perceptions. Dreams. Visions. Memory losses. Memory changes. Personality changes. Etc. The "delta" in the emission spectrum (the changes from zero reference spectrum) represent the precise totality of all mental, physical, organic, chemical, etc.changes and interactions." Bearden
>
> "A second stage in the research would be to **test the correlates** and porthole insertions upon a statistically significant cross section of ordinary people, and/or specialized populations (such as toughened soldiers). The program would evolve a highly complex, very effective, ever-improving science and technology of mind and behavior control and engineering mechanisms, complete with finished database and developed applications equipment." Bearden

Summing up his paper Bearden speculates on what the actual situation the science of psychoenergetics probably is. The intense secrecy with which this knowledge has been kept from the public has led to the **current farce of the "government" pretending** it all does not exist, and this secrecy may have now put us at great risk.

> "The implication is that in the West one or more highly classified, sustained, heavily funded developments in advanced mind control programs, probably exists and probably has existed for some time. Due to loose formation of rogue groups inside such programs, they may have dual or triple purposes, **may not operate under very much legitimate government control at all**, and may operate specifically for the purposes of the rogue group or groups that have gained control.

> "In a nutshell, that's what may be going on in the **clandestine mind control projects** in several Western governments. The involvement of at least some rogue groups, some being "cowboys" who operate well **outside all laws and ethics**, could also result in such things as assassinations, clandestine testing on individuals without their consent, etc. In short, ***it could account for what seems to be actually occurring***. As also is "usual" in such a mess, one or more of the rogue groups eventually may become very powerful because their secret weapons are very powerful. They may become confident, thinking they have the "best in the world." They may actually believe they are ahead of the Russians..."
>
> "Remember that, in every large and powerful human organization, the basis for rogue groups is **power** and **secrecy**. They are always seeking to increase their power, control, influence, prestige, etc. Nothing else. Patriotism and mission are—to rogue groups—often just idle words. They have their own agendas. And being rogue groups, they may well bring in unethical, immoral tricks: assassination, bribery, entrapment, disinformation, plausible deniability, etc. A certain percentage of a highly secret rogue group will wind up using all these things and more. It's a **human** characteristic, the **old primate dominance game**. Only now disguised and hidden under deep classification."
>
> "The **Russians**, with their additional knowledge of the actual mechanisms in the transforms, will be **much more advanced than the West,** because their fundamental psychoenergetics science is far more advanced, so long as we continue to use the old U(l) electrodynamics. Further, the Russians have decades of use of **longitudinal interferometry beams to reach right through the earth and ocean** and produce stringent EM effects at a distance. So they will also be able to do the same things here in "mind control" with LW [longitudinal wave] interferometers, through intervening mass." Bearden

Bearden cites two examples where he believes the Russian KGB tested the psychoenergetics capabilities of their scalar interferometers. One was the case of Captain Button in his A-10 "Warthog" aircraft on April 2, 1997.

> "Over Arizona, Captain Button was thrown into a hypnogogic state, and his perceptions instantly altered and controlled. In his instant "dream-waking" state, everything seemed perfectly normal. His sense of direction was altered a bit more than 90 degrees, so he simply corrected and turned and "flew toward the range", actually flying off course by more than 90 degrees and ignoring radio contacts. He flew right on out of Arizona."
>
> "At one point he circled, probably thinking he was over the range, and he probably dropped his ordnance there. Then he "flew on back toward home," as he thought in his waking dream state, until his fuel ran out and he crashed and died in the explosion—**dream-thinking until he died that everything was normal**. All the while, his sense of the passage of time was altered. To him, in his dream-thinking, dream-acting state, everything was normal and nothing untoward had happened. **So the distant KGB transmitters and associated psychoenergetics team controlled him for over an hour**.

> "Indeed, that was the exact purpose of the test: demonstrate control (at a great distance) of a skilled person performing highly skilled tasks."

The paper Mind Control and EM Wave Polarization Transductions ends with the most chilling and frightening possibility of all: the **psychoenergetic engineering of the human species** as a whole.

The Ant World

The Final Race for Direct Mind Control of the Entire Human Species

"The KGB psychoenergetics weapons scientists—because of their direct measurements and detections (and use) of t-polarized waves and LWs [longitudinal waves] for decades—also understand that Jung's collective unconscious mind (of the entire human species) also has its own time-like operations and correlates, which one measures also when using t-polarization measurements and sorting it all out. **The collective unconscious mind operations are buried several levels deeper inside the recursive Whittaker structuring inside the EM fields, waves, and potentials**.

"The KGB scientists also know that something very like **Gaia** — a collective unconscious mind for all species on earth — **also exists**, and they are striving to be able to sort out and measure that one as well. The Gaia operations are buried even deeper in the recursive structuring inside the EM fields, waves, and potentials."

"Actually, from day one, the Russian mind control scientists have had their eventual goal set upon this "deeper area of mind and possible mind control" of the entire human species.

"I am convinced that the KGB psychoenergetics scientists understand this deeper area. If they can learn to directly engineer the collective human species unconscious, they can then **convert the human species easily into a sort of "ant" society**, modeled along ideal Communism lines, except of course with an excluded "hierarchy at the top" running everything. The "ant society" — communist style — is still a variation of feudalism (**all systems tend to feudalism or some form thereof**).

"The KGB psychoenergetics weapon scientists are seriously pressing on toward that very goal. In my opinion they are not very far from it right now...

"Some versions of Russian mind control devices were used on Russian soldiers in the Afghan War to **condition them for performance of merciless acts**." [13]

http://www.cheniere.org/explore%20articles/mind%20control3/p07.htm

More about "The Ant World"

Whether it is the Russians planning an "ant world" society or rogue U.S. black-ops groups withholding a great boon from human race, the secrecy on all sides around has allowed **largely criminal elements** to take over this technology while leaving the civilized elements in the dark. Openness and the spreading of this knowledge among good and decent people is essential, and for that **we will have to overcome our frightened denial**.

> "Meanwhile, **rogue groups** amongst Western clandestine mind control researchers will probably arise if they have not already done so. They will likely seek to increase their personal control and further isolate the programs from orthodox government review and from government and legislative control. They may even divert the research into highly illegal and unethical means, because it furthers their own rogue agendas. That is how clandestine U.S. government research can sometimes go sour, **unless great care is exercised by the oversight committees in the House and the Senate**.
>
> "Sometimes when rogue groups do gain control and total secrecy of a given new technological area, then what appears to be "U.S. government operations" do start to encompass a criminal and unethical operations, hidden usually beneath the deep veil of high classification. Also, if it's "scientific," no one is ever brought to justice, even if the "evil science actions" are uncovered and publicly revealed." Bearden

Like the huge energy of the Tesla howitzers, the ability to engineer the mind with longitudinal waveforms is a seeming "magical" thing which can be used for good or ill. Bearden envisions that further developments will allow something like the "downloading" of knowledge via scalar interferometry. Everyone could be highly educated, and quickly and easily.

In the conclusion of the paper "Mind Control and EM Wave Polarization Transductions" Bearden makes **a plea to the nations of the world** regarding the use of psychoenergetic engineering.

> "Let us hope this great new area, already off to a bad start, can be bridled and steered in the direction helping and healing people, rather than killing or abusing them. **The excesses in its bad use are a potent threat to all nations on earth**.
>
> "Yet it can revolutionize medical science, education, communication, and psychology. We foresee the day -- perhaps 30 years hence -- when **education will be accomplished by directly loading the software into the mind**. Then in three weeks one will "load" a doctorate, say, in physics. In three more weeks on will also load a doctorate in chemistry. Another three weeks, in electrical engineering. Another three weeks, an M.D. And so on. When that happens then truly everyone on earth can be educated. Freedom from ignorance may well be another great freedom that is legally recognized. There will be no impoverished large groups lacking the education to find decent, productive jobs.
>
> "We urge all nations to use the principles involved: not for human abuse, but for healing, educating, uplifting, and life-expanding of every person on earth. If we do, we shall all have a far brighter future. Then we shall check what has started out to be the Sword of Damocles and turn it into the golden Millennium." Bearden

(Perhaps after so many frightening topics a slight break is in order here to consider the **lighter side of psychoenergetics**. For example, what will be the ultimate impact on the entertainment industry?)

The Feelies at Last!

Psychoenergetics will be able to bring about at last, for better or for worse, Aldous Huxley's fanciful idea in his novel "**Brave New World**," an entertainment format which he called "**The Feelies**." Those were something you went to, like going to the movies, but you would **experience** all the actual feelings themselves, as if the depicted events were actually happening to you. Although our "leaders" seem too dim to grasp what is going on in the world of scalar electromagnetics, it should not take some young Hollywood genius too long to understand that **The Feelies are now possible**, and that the immense megabucks of potential profit more than justify heavy investment in bringing it to market.

One can imagine that first "Feelie" theater, "The Huxley" perhaps, a large comfortable area surrounded by nine giant screens (not just one screen!), which become 3D if you put on your headset. And The Huxley is fitted with the finest sound, and oh, by the way, a modest sized scalar interferometer with computer. And there are one or more **new tracks** now recorded on the film next to the sound track. These are the digital patterns of thoughts, feelings, and ideas to be fed into the theater's interferometer. And these thoughts and feelings and ideas will be felt by the audience as if they were their own thoughts and ideas. It is an entirely new art form. Psychevision.

As important (and no doubt famous) as the actors would be the "feelers," those from whose minds the feelings were lifted in the original programming of the Feelie tracks. Because, for example, Brad Pitt might be a good and handsome actor, but **can he really feel it?** Like the dubbing of foreign language films, it might be necessary to dub the "emotional track" using a deeper and more profound person's feelings, thoughts and ideas.

It might even be engineered so that if you sat on one side of the theater you would feel like the hero, and on the other side you would feel exactly like the bad guy! What would that lead to?

We have all cried at a movie some time, most people have, though they might not want to admit it. But this would be **deep sobbing** and a **flood of tears**, if the director so desired it. You would feel it at your core. Or, take a big chase scene, **you would be terrified**. They are breathing down your neck! You would be gripped by panic.

For that matter, the whole genre of **Horror-Feelie** would be too much for many people to take. Do I **really** want to feel that an **actual vampire** is tearing at my throat with his fangs?

A Religious Feelie would make you feel the exaltation of a saint at his prayers, or give you the **definite** feeling that you are Christ suffering on the cross. All the pain could be there too. The stickiness of the blood. The very feeling itself: "Why hast thou forsaken me?" Who among us could come up **that** despair for scanning? Had this been developed a bit earlier we might watch a documentary of, say, Mother Theresa, containing her own actual deep sense of compassion, which we would feel arising in us as our own.

Then again, a Psychedelic Feelie could induce an LSD-like state and simply blow the audience's minds.

Even in its simplest most primitive mode, the hypnogogic trance induction with its increased suggestibility, would completely alter the experience of even ordinary current movie going.

6. As it Stands - 2002

[Note 2006: Click here for a current status history of the MEG from Tom Bearden]

> "**Anyway, it's presently a "Mexican stand-off**" with the various parties maneuvering with check and countercheck. That is the real "balance of terror" that is held by such a fragile balance."
>
> "You can see the implications if such weapons fall into the hands of the radical terrorists. Ordinary positive energy EMP shooters **can be made fairly readily and cheaply** from nearly just **Radio Shack parts** or surplus parts. It just takes some know-how... When and if the Yakuza [Japanese mafia] gets those (and they will, it's just a question of time), you can begin to appreciate some of the turns this present terrorism and our war on it will take." Bearden

The very thought of the building of one of these howitzers by "some lone-nut gunman" from Radio Shack parts makes one realize how serious it is for humanity to face the crisis it has come to.

Once again, as at the dawn of the nuclear era, humanity finds itself at the crossroads of Heaven and Hell. As a species, we must stop and consider. And there is at least one real difference between this visit to the crossroads and the last: *this* time there is a very real possibility of a true "earthly heaven" on the Heaven side.

The poor nations could come to a good life. Disease could be largely eliminated. Fossil fuel pollution could end. Global warming could be solved, and the weather could be managed in a humane way, bringing water where there is drought, and sunny skies where there is flood. Scalar interferometry would be there to avert any possible hits by asteroids or comets. Mars could be colonized and terraformed. Everyone would be highly educated through psychoenergetic downloading of knowledge. And the **wisdom of the wise** could be realized directly through scalar connection to their minds and hearts.

These stunning sudden possibilities give me pause to think: if our species has reached this crossroads in such a short span of centuries, then surely other species in this vast universe have passed this way before and long ago. And of those who chose the path to "planetary heaven," what is their life like now? It might be good if some of them were with us now, to guide us through this last struggle over this pesky old good-and-evil problem. **It is our last chance to choose the path which benefits the whole species, and not just some elite group or faction**.

The Disclosure Project

One person working tirelessly to bring to bring these technologies into the open is Dr. Stephen Greer of the Disclosure Project, which is calling for congressional hearings into the issues of UFOs and the free energy technology that was, perhaps in part, reverse-engineered from them.

> "Once abundant and nearly free energy is available in impoverished areas for agriculture, transportation, construction, manufacturing and electrification, **there is no limit to what humanity can achieve**. It is ridiculous — obscene even — that mind-boggling poverty and famine exists in the world while we sit on classified technologies that could completely reverse this situation.
>
> "So why not release these technologies? **Because the social, economic and geo-political order of the world would be greatly altered**. Every deep insider with whom I have met has emphasized that this would be the greatest change in known human history. The matter is so highly classified not because it is so silly, but because its implications are so profound and far reaching. By nature, those who control such projects do not like change. And here we are talking about the biggest economic, technological, social and geo-political change in known human history. Hence, the status quo is maintained, even as our civilization hurtles towards oblivion...
>
> "With the types of weapons currently in the **covert arsenal** — weapons more fearsome even than thermonuclear devices — there is no possibility of a survivable conflict. Yet in the darkness of secrecy, actions have been taken on behalf of every human that may endanger our future. Only a full, honest disclosure will correct this situation. **It is not possible for me to convey in words the urgency of this**."
>
> Dr. Stephen Greer http://www.disclosureproject.org/ES-DisclosureImplications-2.htm

Greer and his team have assembled hundreds of witnesses, many of whom are military or ex-military, who are ready to testify to congressional hearings what they know about the covert black projects which have kept free-energy and antigravity propulsion technology secret from the people.

Greer points out the need to regulate these technologies so they are limited to peaceful uses, but this is of course difficult when the government simply chooses to pretend they do not exist. In the meantime, as the President and the Defense Department continue the charade of war-as-usual, those scalar (longitudinal wave) installations which DO exist continue to fall into ever more sinister hands. And there is no reporter in the press brave enough to ask, "**Mr. Secretary of Defense, what steps are you taking to defend our MINDS from attack by the big Russian longitudinal interferometers?**"

Longitudinal Interferometers are Proliferating

In a later statement Bearden reveals that in fact the Yakuza [Japanese mafia] has **already leased** some of the interferometers with a nearly $1 billion "down payment:"

> "After the collapse of the Soviet Union's economy, lots of things got available for lease or purchase that would never have been under the old system. That happened in the resulting economic chaos. The Russian Mafia rose to prominence, as did some wheeling and dealing entrepreneurs who played both ends against the middle.
>
> "**In that atmosphere, and in the need for money, the KGB allowed leasing of the earlier longitudinal EM wave interferometers to a consortium of the Yakuza and Aum Shinrikyo.** They did this only after they had tested and deployed their great new quantum potential weapons. That class of weapon is the dominant weapon on earth. Five nations now have it: Brazil, Russia (KGB), China, and two nations friendly to the U.S. The deal to lease many of the earlier LWIs [longitudinal wave interferometers] to the Japanese Yakuza and Aum Shinrikyo was consummated at the end of 1989, with a down payment of $900 million in gold bullion as "up front" money. I don't know what the lease per year was and is, but probably something like a billion dollars a year. **So the rogue Japanese acquired longitudinal EM weapons** and that technical know-how. In fact, the Yakuza is producing certain kinds of those in its own facilities in Japan now."
>
> http://www.cheniere.org/correspondence/030202a.htm

Personally, I am a little uncomfortable with the knowledge that the Japanese mafia may now be able to insert things into my mind. I'd like to sleep at night knowing that my dreams are my own, such as they may be, and not some weird fantastic visions cooked up by a criminal organization. **This is a world emergency**.

And in Bearden's analysis, it all comes back to the issue of **energy**. It is the energy crisis which is now provoking the current "oil wars," since oil production has hit the "Hubbard Peak" and will decline. And the electrical power grids must be replaced with scalar power as fast as possible, for these grids are now totally vulnerable to any possessor of longitudinal interferometers. They can all be wiped out in minutes. By anyone who possesses or controls a Tesla howitzer.

> "Anyway, in my personal view, we should have a national **Manhattan Project** right now, to develop decentralized electrical power systems taking their energy from the vacuum . . . The MEG is real and so are several other systems invented by private inventors and colleagues. All these efforts should be massively funded and massively and quickly developed. The survival of this nation is going to depend upon it. . . . There are many other facets, but the major point is that **our scientific apparatus and the public are still unaware of what a desperate struggle we have entered, since it was thrust upon us. 9-11 was a wake-up call**. It was certainly bad enough, and one grieves for those lost American lives. But I fear the **worst is yet to come**, and it is coming at us like a runaway train hurtling right down the track at us."
>
> http://www.cheniere.org/correspondence/021702a.htm
>
> "The electromagnetic weapons mentioned by the Secretary of Defense in April 1997 **are in terrorist hands also**, including the **Yakuza and Aum Shinrikyo**. That rogue group leased those earlier weapons on site in Russia, from the KGB, at the end of 1989. The SecDef stated that such weapons were being used to initiate earthquakes, initiate volcanoes into eruption, and control and engineer the weather. Quite true. And presently

there is a truly massive set of weather engineering operations going on over North America, from that rogue Japanese group manning the weapons in Russia. Some 10 nations of the world now have the type of longitudinal EM wave interferometer weapons (which are what the SecDef was most probably referring to). There are other even more fearsome weapons, possessed by five nations. **So a great deal of the state of the world is not covered in the news at all, and will not be . . .**

"We have been in an undeclared war of an eerie kind for some decades. That war seems now to have started to heat up also. The destructive capability of some of these weapons is awesome, and far greater than nuclear."

http://www.cheniere.org/correspondence/021702a.htm

"In that sense, the first phase of WW III is already completed. Now we are only waiting for Phase II.

"It is against that backdrop that I think one must "analyze" such things as how fast we will be replacing the power grid (**it's going to go anyway, and catastrophically, the terrorists will see to that**). And everything we have is critically dependent upon energy, from the economy to jobs to mobility, to the millions of trucks that transport our goods every day, etc.

"As far as I am concerned, we are already late in declaring a great national emergency in energy, because of the coming destruction of the present energy infrastructure. The scientific community should lead, follow, or get out of the way. The emergency is not in seeking "alternative but conventional" systems. It is in developing "energy from the vacuum" on an emergency, crash basis.

"Unfortunately, everywhere I look I just see business as usual. Most Americans (and news media) seem to think, hey, Afghanistan is finished except for a bit of cleanup, and it's just about over).

"It isn't. It has only just begun."

http://www.cheniere.org/correspondence/021702a.htm

Beyond the Howitzers: Quantum Potential Weapons

Do not use EM propagation through space

As more and more nations acquire the scalar interferometers, Bearden speculates on the next generation of longitudinal weapons called "quantum potential" [QP] weapons.

> "The **quantum potential weapons** are presently only held by three nations: Russia (in the hands of the KGB, which is now know by its new name), Brazil, and the "friendly little nation." Red China may be working on them, but is just at the beginning...

> "The QP weapons have been highly reserved by the Russians. However, the complete extent of their capabilities is still being figured out...
>
> "The quantum potential weaponry (possessed by only three nations) is supreme, because **it uses multiply connected spacetime**, and DOES NOT involve propagation of EM energy through space as does the longitudinal EM wave interferometers.
>
> http://www.cheniere.org/misc/qp.htm
>
> "The operational deployment of full-scale strategic QP weapons on site in Russia occurred at the end of 1989, which is when the formal weapons first went operational. These weapons are not in the inventory of the regular Russian armed forces, but all research and development, manufacturing, deployment, an manning and employment is under the ruthless control of the KGB. Shortly thereafter (within weeks), the KGB leased many of their earlier longitudinal EM wave interferometer (LWI) weapons to a rogue Japanese group comprised of the Aum Shinrikyo and Yakuza."
>
> Bearden http://www.cheniere.org/correspondence/021401.htm

In another paper, "Time Polarization - Significance and Weaponization," Bearden tells the story of how a KGB longitudinal wave attack was averted by the longitudinal weapons of a "friendly small nation."

So as it stands, it is precarious. Not until the people demand an end of what author Jim Marrs has dubbed the "**Rule by Secrecy**," can the people's representatives tackle the big problems of a worldwide ban on Scalar Wars and the shifting over to an essentially oil-free economy.

Latest Update from Tom Bearden - March 2002

The whole situation is changing so fast that when I asked Tom to look over this article he mentioned the seeming contradiction when some of the above statements are taken together. At different times the information he has is updated so one has to keep a kind of running track. He was kind enough to clear up the confusion here with the situation as it stands as of March, 2002.

> "We knew of three nations having the QP weapons for some time. Then we found out last year that five nations had it. So that explains my using the figure "three" first (which represented what I knew at the time). Later I found out about the other two nations. China, e.g., only deployed its QP weapon this past year. So that explains the apparent contradiction between me using "five" in later papers and "three" in earlier ones. It was the best information I had at that time. Might mention that so the reader will understand the apparent discrepancy." Tom Bearden

Emptiness is Full of Energy

"The Tao is an empty vessel;
it is used, but never filled.
Oh, unfathomable source
of ten thousand things!

"Oh, hidden deep but ever present!
I do not know from whence it comes.
It is the forefather of the gods."

Lao Tzu -Tao te Ching

Afterword

Because of the extreme seriousness of the topics brought forward in this article, I asked Tom Bearden to look it over to make sure I had not gotten anything too terribly wrong or mixed up. I did not want to pass on any misunderstanding of my own. I felt a little nervous writing to an eminent scientist, and hoped I had not presumed upon his time.

But Tom was so kind as to answer immediately, and to my relief I had not gotten anything too terribly wrong. Here is his letter, in which he clears up a misunderstanding, and reports on his current health treatment, and gives a call to the young grad students to turn themselves loose in the whole new field of scalar electromagnetics and free energy.

> Subject: RE: Article on Tom Bearden and "Scalar Wars"
> Date: Fri, 22 Mar 2002 22:54:01 -0600
>
> Bill,
>
> Well, I must say I'm astounded at your persistence and hard work in congealing all that together. My compliments on a hard job quite well done.
>
> Couple tiny things: In the area mentioning Kervran and Kaznacheyev: Kervran was French; Kaznacheyev was and is Russian. Little typo of "spredding" the immune system. Should be "spreading".
>
> We knew of three nations having the QP weapons for some time. Then we found out last year that five nations had it. So that explains my using the figure "three" first (which represented what I knew at the time). Later I found out about the other two nations. China, e.g., only deployed its QP weapon this past year. So that explains the apparent contradiction between me using "five" in later papers and "three" in earlier ones. It was the best information I had at that time. Might mention that so the reader will understand the apparent discrepancy.

Otherwise, it's pretty accurate.

Just now I'm letting the weapons take care of themselves; have to, as I will be recovering now for nearly a year from now after the heart attack last year and discovering that I had contracted mycoplasia (the BW modified kind) in Canada in 1968. Finally got a test which confirmed the chronic mycoplasia (which I had for 33 years!). The stuff burrows inside one's red corpuscles, then draws nutrients from the hemoglobin, hardening it and reducing its ability to take on oxygen (by as much as 50% or more). The resulting symptom is loss of endurance (which I had for that 33 years) -- the so-called "chronic fatigue syndrome".

Many of the Gulf War Veterans who are sick also have it, though they apparently have other complicating factors as well. A very high percentage of persons with chronic fatigue syndrome also have mycoplasia. The treatment for the long-standing mycoplasma infection of that nature is to stay on antibiotics for a year. The only time the mycoplasma is vulnerable is when one wears out a red cell in normal usage, and the body makes a new red cell to replace it. The mycoplasma comes out of the dying cell to infect the new replacement cell, so it is exposed and vulnerable at that specific time and that time only. The antibiotics kills it at that time. Hence the necessity to stay on antibiotics for such a long time so it is continuously in your bloodstream (I've already been on antibiotics for over two months, and have at least 10 more months to go). We also take a little medical oxygen every day.

Another symptom of the mycoplasma infection is the association of runaway fibrillation of the heart. To stop that, there are pills one takes, and they stop it. But they also further reduce the volume of blood pumped by the heart, so that this projects one right back into the hypoxia, dizzy, loss of balance, etc. Catch 22 situation; the fibrillation will build and cause heart attack, stroke, etc. if not stopped, and if stopped it puts you back in the hypoxia which can cause many things! With the conventional treatment, you're damned if you do and damned if you don't. Hence the need for a little extra medical oxygen, so you can take the "heart clamp" pill and stop the fibrillation, but also augment the oxygen enough to continue to survive without a stroke or some such. Interestingly, it's very difficult to even obtain a mycoplasma test, and Medicare fights you tooth and nail over paying for the oxygen. Either they will pay for it or I'll pay for it myself; it is absolutely necessary.

After a heart attack, one is treated in the heart clinic by specialists who are very caring and excellent practitioners, but know nothing of mycoplasma infection, so not consider it even a part of "heart disease", and who are rather puzzled when one has no clogging of the arteries, has the right count of red corpuscles (largely nonfunctional, of course, but there), pumps the right amount of blood, etc. So they identify and treat only the runaway fibrillation, do not prescribe the oxygen -- and essentially place you on a regime as best they know, but one that is guaranteed to kill or maim you or turn you into a totally disabled person or human vegetable via stroke, paralysis, etc. Fortunately my family doctor will prescribe the oxygen anyway, though I may have to pay for it myself. Whatever works!

However, I'm slowly improving little by little, working as much as I'm able to and trying to finish my book: Energy from the Vacuum: Concepts and Principles, and get it to the publisher for publication later this year. Hopefully the book will turn all the interested young grad students and post-docs loose in the free-energy area. They will not have to spend 30 agonizing years to get to where I am, and where a few others are, but can simply start here and go forward. Since speed to develop energy from the vacuum is of the essence because of the world situation, I'm moving on it as fast as I am physically able to.

Meanwhile, working with the AIAS (Alpha Foundation's Institute for Advanced Study), the AIAS (15 authors) has now gotten about 20 scientific papers published in leading journals (Foundations of Physics, Foundations of Physics Letters, Physical Scripta, Optik, etc.) dealing with electromagnetic energy from the vacuum. Several more are either approved for publication or in the review process also. So slowly we are getting it into the mainstream scientific literature. Hopefully it will be in time, but it's cutting it close.

Very best wishes,

Tom Bearden

Late update

Massive display of longitudinal interferometers?

UFO Fleet Taped
Over Bedhampton, England

Is this sighting a case of the testing of all the Russian (KGB) longitudinal interferometers at once? And coordinating their targeting through the woodpecker grid to a common place, as an exercise in making a massive scalar attack upon a given region? Was this a confluence of Russian Tesla howitzer marker-beacons?

Bedhampton, England - March 22, 2002 - Video Frames by: Anthony Woods

Certainly for a massive all-out scalar attack you would want coordinated movements of the target areas of many howitzers at once, for you could then just cut a bloody swath across a wide area, all the howitzer blasts marching across the land in a kind of scalar version of the "scorched-earth policy." All in a line, blasting, and heat, and mind waves. Or you might want to put the blasts all in the same place for a truly horrendous destruction. And on top of that biowar on citizens whose immune systems have been weakened with the quantum potenial weapons. This is the latest version of Armageddon.

And should any madmen gain control of these weapons, any rogue group at all, and should they have some aggenda to radically depopulate the world, to simply kill by the billion, the means will be in their hands to do so.

Update: MEG patent granted

Motionless Electromagnetic Generator Patent Granted

This message is from **Jean-Louis Naudin**, the French scientist who successfully replicated the Motionless Electromagnetic Generator (MEG) in France. He announces the granting of the patent to the MEG Builder's group at Yahoo.

----- Original Message -----
From: jnaudin509@aol.com
To: jlnlabs@yahoogroups.com
Sent: Tuesday, March 26, 2002 2:20 PM
Subject: [jlnlabs] (Info) GOOD NEWS : The Tom Bearden's MEG IS PATENTED

Dear ALL,

GOOD NEWS !!!!

The **Motionless Electromagnetic Generator**
from Tom Bearden is now PATENTED
US **6362718** granted on March 26, 2002

US Patent 6,362,718 :
Motionless Electromagnetic Generator (MEG)

Abstract: An electromagnetic generator without moving parts includes a permanent magnet and a magnetic core including first and second magnetic paths. A first input coil and a first output coil extend around portions of the first magnetic path, while a second input coil and a second output coil extend around portions of the second magnetic path. The input coils are alternatively pulsed to provide induced current pulses in the output coils. Driving electrical current through each of the input coils reduces a level of flux from the permanent magnet within the magnet path around which the input coil extends. In an alternative embodiment of an electromagnetic generator, the agnetic core includes annular spaced-apart plates, with posts and permanent magnets extending in an alternating fashion between the plates. An output coil xtends around each of these posts. nput coils extending around portions of the plates are pulsed to cause the induction of current within the output coils.

Inventors: Patrick; Stephen L. (2511 Woodview Dr. SE., Huntsville, AL 35801); Bearden; Thomas E. (2211 Cove Rd., Huntsville, AL 35801); Hayes; James C. (16026 Deaton Dr. SE., Huntsville, AL 35803); Moore; Kenneth D. (1704 Montdale Rd., Huntsville, FL 35801); Kenny; James L. (925 Tascosa Dr., Huntsville, AL 35802)

Appl. No.: 656313
Filed: September 6, 2000

For some technical info see my web site at : http://jnaudin.free.fr/html/meg.htm

Best Regards
Jean-Louis Naudin
Email: JNaudin509@aol.com
Main Web site : http://jlnlabs.org
Site France : http://jlnlabs.multimania.com

Click here to view patent # **6,362,718**

Patent Story on Rense.com:

Important Note 2006! MEG delayed: **Click here for a current status history of the MEG from Tom Bearden**

Rense.com

MEG Scalar Energy Device Patented - Production Starts Next Year

From Bill Morgan
3-28-2

Patent was granted on March 26, 2002 for "The Motionless Magnetic Generator," (MEG) US Patent 6,362,718, which is likely to become the first commercially available free energy device in history in about one year from now. The machine will provide free electricity from the vacuum, for the life of the device, which should be a very long life since it has no moving parts. You can see a picture of scientist Jean-

Louis Naudin's MEG replication model at: http://jnaudin.free.fr/html/meg.htm.

It has strong magnets, coils, and a controller unit with the electronics. Naudin made the announcement to the MEG-builder's Yahoo group. The announcement has significance since the patent office has always been skeptical of devices which seem to "get-something-for-nothing." But according to the new science of scalar electromagnetics, the MEG does not break the law of conservation of energy. It's just that the energy is conserved in the fourth dimension, time, and not our 3-space world.

The MEG provides electrical energy by tapping the longitudinal electromagnetic (EM) waves which exist in almost infinite abundance in the vacuum of space. This ocean of energy which permeates everything is sometimes called the "zero point" energy, since it remains there even at absolute zero temperature.

Four inventors are listed: Stephen L. Patrick, Thomas E. Bearden, James C. Hayes, Kenneth D. Moore.

Tom Bearden has explained the operation of the MEG on his website Cheniere.org, and also speaks about the new fearful weapons that can and have been made using the same "longitudinal waves" of the vacuum.

The complicated physics of how the MEG works is explained in the paper "The Motionless Electromagnetic Generator: Extracting Energy from a Permanent Magnet with Energy Replenishment from the Active Vacuum," which can be found at Tom Bearden's website:

cheniere.org.(http://www.help4all.de/energy/MEGpaper.pdf)

The first MEG units to be produced for sale will output 2.5 kilowatts of free electricity. Forever. They should be in production about a year from now. Facilities for manufacturing the device are being set up in an unnamed "friendly nation."

This free electricity will flow indefinitely, without much, or any maintenance. The units may be hooked together to provide more wattage, so four of them would provide 10 kilowatts. After some production experience units will be made which output 10 kilowatts each. With a couple of those units a house could get off the electrical grid.

Tom Bearden, one of the inventors has said "I will admit that the chief scientist of an important experimental group in a large company was rather stunned at the type of output we were able to obtain. The MEG may look like just a transformer, but it is not. It is a completely different breed of cat." This cat, it would seem, is out of the bag now.

The ordinary EM waves we are familiar with are called "transverse" waves, to distinguish them from the new "longitudinal" EM waves of the vacuum. Bearden has explained in depth on his website cheniere.org that wherever there is a dipole (battery, generator, magnet) there is an unseen flow of longitudinal EM waves in that local vacuum, the only problem is in tapping that energy and "transducing" it to electricity. Bearden says that the problem with all the electrical circuits we have is that they are two-wire circuits, a loop by which half the energy goes back to destroy the dipole. In the MEG that closed loop is never made. So the dipole is not being destroyed.

Patents are not granted on devices which do not work, so in a sense this announcement proclaims a new era. The MEG device itself proclaims and proves that energy is abundantly available everywhere, for free. We only have to build the devices to tap it. MEG type devices could be put into a car with an electric engine to make a truly fuel-less automobile. Electricity can be available in very remote places. People will be able to get off our very terrorist-vulnerable power grids. In an era of terrorism a highly dispersed power system would be most desirable rather than our centralized systems.

What is somewhat astonishing to me is the discovery by Bearden et. al. that time itself is actually compressed energy, and that this free energy is actually coming from the time domain, the ocean of longitudinal EM waves which fill the empty vacuum of spacetime. In fact, time is energy compressed by the same factor that matter is compressed energy: the speed-of-light squared. Thus there is a new companion to Einstein's E=mc2. Can you say "E equals delta-tee-cee-squared?" The "tee" is time and delta-tee is change in time.

A company has been set up to manufacture the MEG called Magnetic Energy Limited.

The ramifications of free energy are enormous. The oil wars are not necessary. If we threw as much money at this technology as we are spending on the oil wars we would be free of the need for oil in less than a decade. With fuel-less cars air pollution will be greatly lessened. Third world nations can raise their standard of living eventually. And the energy is free. And it never runs out.

I have put together a kind of "Bearden for Beginners" article which explains some of the basic concepts of the current state of scalar technology.

http://www.prahlad.org/pub/bearden/scalar_wars.htm

The granting of the MEG patent is the herald of the new era of scalar electromagnetics, and the free energy which flows forever and never runs out.

Bill Morgan

Status History of the MEG

updated Oct. 26, 2006

Important notes on the status of the MEG (Motionless Electromagnetic Generator)

Since the time this "**Scalar Wars**" article was written the timetable of the **MEG** has been thrown off considerably. Bearden had originally said the MEG could be marketed within 1-2 years ***of receiving funding for final research and scale-up costs***. I thought certainly it would not take very long, but over 5 years later they still have not gotten the $10 million or so necessary. There are various reasons for this, some of which Tom Bearden has written about.

The place for updates on the MEG status is Tom Bearden's correspondence section at his website Cheniere.org:

http://www.cheniere.org/correspondence/index.html

Here are a few of his reports which detail the history of the MEG status :

Mar. 6, 2006
http://www.cheniere.org/correspondence/030206.htm

May 16, 2005
http://www.cheniere.org/correspondence/051605.htm

Jan. 19, 2005
http://www.cheniere.org/correspondence/011905.htm

Dec. 5, 2004
http://www.cheniere.org/correspondence/120504.htm

Do the magnets run down after a while?

Further developments

Tom Bearden clears up a question

When the MEG patent was released many questioned the patent language which seemed to imply that permanent magnets of the MEG would "wear out" after awhile. I myself wondered about the same thing so I put the question to Tom, and here is his reply.

> Dear Bill,
>
> Thanks for the kind words; much appreciated.
>
> I'm not up to going on radio or TV, and won't be for quite some time. Still suffering from hypoxia, though very slowly improving, and will still be on antibiotics for 10 more months at least (maybe longer).
>
> Obviously an extensive dialog developed between the Patent office and our patent attorneys. As best I can understand it, the Patent office accepts the fact that a permanent magnet produces and emits energy, or has a history of accepting it. They do not appear to be at all cognizant of the broken symmetry of opposite charges, and hence of a dipole. So in their opinion (which seems to be vague), the magnet has to use itself up very gradually, or some such. So some rewrites were essentially required by the Patent office.
>
> All I can say is that a magnet is a very durable thing, so long as you don't heat it up too much or shock it to much. Certainly one will make a good 20 years, and of course there are plenty of magnets that have been around awhile longer.
>
> That said, in our earliest experiments we did "measure" some such effect, or so we thought, until we found that a particular instrument was bad and giving erroneous readings. So with a new instrument, we have not observed since then any such readings.
>
> Out of all that fuzziness came the inclusion of "using up the magnets gradually". So far as we are aware (after correcting those early readings on a defective instrument), we have seen no such measurements or effects since then at all. Nonetheless, just in case there is some very small effect in that respect, at least it's in there.
>
> Actually, as you are aware, capacitors and solid state components are the major concerns for failure, and any system does require maintenance, both periodic and whenever malfunction or failure occurs. The MEG is no different from any other device in that respect, so of course it will have a component failure rate and maintenance required from time to time, just as any other electromagnetic device. But without moving parts, it can be ruggedized and made very durable indeed.
>
> Please give Jeff Rense my regrets, and I do admire his work and his show. He's laying it in there.
>
> The depth of the scientific mindset against COP>1.0 is inexplicable, particularly when physics itself already has COP>1.0 validated

experiments (such as Bohren's experiment, which outputs 18 times as much as one inputs by Poynting calculations), and it works every time. Any competent university optics lab can perform the experiment. Also, even the conventional texts admit that a charged capacitor or electret laid on a permanent magnet, so that the E of the cap or electret and the H of the magnet are at right angles, is a "free energy machine". That silly thing will just sit there and pour out Poynting energy S = EXH indefinitely. Years and years and years. If you wait just a single year, that silly thing has changed the energy density of a volume of space a light year in radius, reaching out well beyond the solar system. Now that's a WHALE of a lot of EM energy that beast poured out in that year, and it will still be going strong and pouring it out at a steady rate. The charges and dipoles in original matter in the universe have been pouring out EM energy in that fashion for some 14 billion years, give or take a billion or so. It's also easy to see that, prior to Lorentz's ARBITRARY symmetrical regauging of the Maxwell-Heaviside equations, those equations prescribe both EM systems in equilibrium with their active environment, and EM systems not in equilibrium with it. The latter systems are permitted by the thermodynamics of open disequilibrium systems to perform five magic functions: (1) self-order, (2) self-oscillate or self-rotate, (3) output more energy than the operator inputs (the active environment inputs the rest of it), (4) power itself and its load (the active environment inputs all the energy, like a windmill), and (5) exhibit negentropy. That is a well-established thermodynamics. Lorentz arbitrarily discarded all such open disequilibrium EM systems in order to get simpler equations having analytical solutions and not requiring numerical methods. So he simply scrapped all the really interesting and challenging EM systems in Maxwell's theory. ARBITRARILY!

That our scientific establishment continues to teach only that "half" of the theory, and not point out the rest to the young students, and not fund research into developing such systems that take energy from the vacuum, is simply inexplicable. It's a matter of total dogma, not science at all.

But hopefully it is changing a little bit. At least now we cite chapter and verse when these things were done, and what they are, and the young grad students and post docs can go check the papers and make up their own minds.

That is the real hope of the future: that we get a generation of young fellows, with excellent skills, who now know where all the skeletons got hidden in the closet, and understand that the electrical engineering model arbitrarily assumes an inert vacuum environment (falsified for more than a half century in particle physics) and a local flat spacetime (falsified for nearly a century by general relativity).

Once they know that past history, and go read into what broken symmetry of opposite charges means for a dipole and for all dipolar EM circuits, they will set to and change that more than a century of error. In that case, we shall have numerous solutions to the energy crisis rather quickly, popping up all over.

Good thing. It will certainly displace some great energy barons, but it will also free the populace. One can extract all the EM energy from the vacuum one wishes, anywhere, anytime, with ridiculous ease. One can produce that "electrical wind of energy" at will, by making a simple dipole and then letting it alone. The only energy problem is in how to then intercept some of that energy flow and "catch" it in a circuit, discharge it in a load to power it, and not use half the "caught" energy to kill that dipole that is gushing out the extracted EM energy from the vacuum.

Very best wishes,

Tom Bearden

END

Revised: May 16, 2007

Download this article in Ms Word format
(ScalarWars.doc)
Send a comment to Bill Morgan

See also:

Scalar Electromagnetics

Scalar Wars:
The Brave New World of Scalar Electromagnetics
(Read this one first!)

Horrifying US Secret
Weapon Unleashed In Baghdad

Scalar Heaven or Hell:
Psychoenergetics

Engineering the Mind

Sacred_Scientist thread at Rumor Mill News

Are any of these Earthquakes Being caused by Scalar Weapons?

Safe Places, Earth Changes, and Gordon Scallion

Examples of probable Scalar Weapons Tests

Iraq: World's First Scalar War?

Space Energy Access Inc. Announces
New Free Energy Device

SINGLE MOST IMPORTANT BREAKTHROUGH IN HISTORY

Comparison: Ebomb and Scalar Waves

IT COULD COME AS SIMPLY AS THIS
Scalar destruction of U.S. power grid

WHAT A SCALAR "SMOKING GUN" WOULD BE

BEARDEN REPONDS TO SCALAR ATTACK POSSIBILITY (Columbia)

THE SCALAR ATTACK POSSIBILITY
Columbia Disaster

TOM BEARDEN ON THE CHALLENGER DISASTER

ANOTHER BEARDEN ACCOUNT OF '86 CHALLENGER SCALAR ATTACK

Broadcasting Thoughts & Disease

Thoughts on Diane Harvey's Appeal to the U.N.

Scalar War Has Already Begun

Musings on Scalar Electromagnetic Phenomena

The New Scalar Paradigm

ELECTROMAGNETIC WEAPONS TO BE USED

SCALAR: BEARDEN SAYS U.S. NOW DEFENDED

American Karma & The River of Tears

Open Letter to Donald Rumsfeld

My Rumor Mill Posts on All Topics

Your comments are welcome: prema@prahlad.org

Journal of Directed Energy, **1**, Fall 2003, 48–72

Compact Pulsed Power for Directed Energy Weapons

David Price,* Carl Bloemker, Edward Goldman, David Nett, Sidney Putnam, Doug Weidenheimer, Roger White, and Tony Wynn

Titan Corporation, 2700 Merced Street, San Leandro, California 94577

The Titan Corporation has been developing directed energy technologies since the early 1980s. Over this time Titan has provided advanced power supplies for electromagnetic gun and laser research while making broader contributions in the field of high-power microwaves (HPM). Titan's HPM work expanded from initial efforts fielding and operating the first gigawatt-level oscillators for susceptibility test applications, to research and development maximizing the peak and average output powers and overall efficiency realized from such systems. As interest in HPM technology has spread globally, Titan has leveraged this core competency and provided the HPM equipment for nearly all of the major European effects test facilities. Titan's current interests focus on compact, efficient and reliable directed energy weapon systems and the advanced subsystems and components that enable the same. Specific subsystems of interest include pulse-forming networks and intermediate energy storage and power conditioning elements (electronically reconfigurable batteries and power ride-thru subsystems). These subsystems are designed for reduced size and weight while still meeting severe service, platform integration, lifetime, and thermal management constraints. Specific components under development at Titan include laser-gated solid-state switches and both high peak and high average power, frequency-agile, HPM oscillators. Status and recent results from this research are presented.

KEYWORDS: Electronically reconfigurable batteries, High-power microwaves, Laser-gated solid-state switches, Magnetron, Power-ride thru, Pulsed power, Reltron

1. Introduction and Previous Work

Directed energy weapons (DEWs) are emerging as a key defense technology of the early 21st century. The first laser antimissile and antiartillery systems are within perhaps five years of deployment, and newly envisioned information warfare and nonlethal point defense missions are hastening the deployment of high-power microwave (HPM) systems. Department of Defense (DoD) programs in "more electric" and "all-electric" platforms and electrically driven weapon and self-defense systems are promoting the development of laser, high-power radio frequency (RF) and both electromagnetic (EM) and electrothermal/chemical (ETC) gun technologies. In fact, the DoD's current fundamental "transformation" efforts are based on stressing the development of capabilities to deal with threats emerging in the

---

Received February 13, 2003; revision received May 28, 2003.

*Corresponding author; e-mail: dprice@titan.com.

© 2003 Directed Energy Professional Society

Table 1. Triservice directed energy applications

U.S. Army [Future Combat System (FCS)—hybrid electric drive vehicles]
- Advanced armaments—electrothermal/chemical guns
- Enhanced area air defense—solid-state heat capacity laser system
- Counter-HARM
- Counter-ATGM
- Countermine (electronically fuzed and wide-area threats)

U.S. Navy [All-Electric Ship Programs (Integrated Propulsion System and DDX)]
- Advanced stand-off shore bombardment—electromagnetic guns
- Advanced anti-ship missile defense (free-electron laser and HPM)
- Nonlethal area denial

U.S. Air Force (more electric aircraft program and advanced UAV programs)
- Enhanced self-defense—solid-state heat capacity laser system
- Space-based laser program
- Airborne laser
- Suppression of enemy air defense
- Aircraft self-defense
- Close air support
- Defensive and offensive counter air
- Strategic attack/strike warfare, attack operation/air interdiction
- Combat search and rescue
- Area denial
- Cruise missile defense

Table 2. Countries now developing high-power RF technology

Programs	Countries
Major	United States, China
Medium-scale	United Kingdom, France, Germany, Russia
Emerging	Sweden, Japan, India, Taiwan, Australia, Israel, South Korea

Information Age instead of emphasizing countermeasures to specific threats. DEWs hold the promise of engaging multiple threats and multiple threat types, thereby fitting very well into this conceptual paradigm. Some specific examples of defense applications of DEW technologies are shown in Table 1.

The initiatory HPM programs in the USSR and United States have evolved and influenced foreign allies and threats to take an interest (Table 2). The collapse of the USSR led to the dispersal of Russian and Ukrainian HPM workers and the proliferation of the Soviet technology to the Third World. This global emergence is driven by at least two factors: 1) The dependence of both military systems and civilian support infrastructure on sensitive electronics is increasing, and 2) after a more-than-20-year effort, an understanding of the susceptibilities of both military and commercial systems to HPM threats is maturing.

For these reasons the Titan Corporation has taken a keen interest in the development of systems, subsystems, and advanced components across several different technologies to support HPM and laser directed energy programs.

In 1997, Maxwell Technologies purchased Physics International (PI) from Primex Technologies and merged two of the three most prominent, commercial, pulsed power entities in the United States. PI and Maxwell pulsed power capabilities were combined into a new entity, Maxwell Physics International, which became a component of Maxwell's Systems Division. Maxwell subsequently decided to leave the DoD and Department of Energy (DOE) pulsed power business altogether and sold the combined Maxwell/PI pulsed power divisions to the Titan Corporation, the parent company of Pulse Sciences Incorporated (PSI). Now, the three most prominent names in commercial pulsed power are combined as the Pulse Sciences Division (Titan-PSD) of the Titan Corporation.

In March 2002, Titan completed the acquisition of Jaycor and its subsidiary California Tube Laboratory (CTL). This acquisition established Titan as one of the world's primary industrial authorities on electromagnetic effects and suppliers of RF and narrow-band microwave DEW technologies and associated electrical power systems. High average power, high efficiency, magnetrons; high peak power, pulsed, relativistic magnetrons and super-reltrons; short pulsed, ultra-broad-bandwidth systems and megawatt-class power supplies and power conditioning subsystems are all designed and manufactured by Titan. This paper will chronicle some of the past and report on some of the current contributions that Titan has made to the development of pulsed power technology for DEW applications.

1.1. Previous Titan work in support of HPM programs

Titan-PSD has been developing directed energy technologies since the early 1980s. In this time, Titan has delivered capacitor banks for electromagnetic gun research with a total stored energy exceeding 200 MJ and advanced pulsed power systems for several large laser systems (Fig. 1). Over 40 years, Titan-PSD has delivered more than 200 pulsed power systems for electromagnetic pulse (EMP), x-ray, and lightning simulation; flash radiography; and other applications worldwide. Although somewhat peripheral to DEW research proper, these projects have nonetheless formed much of the experience base supporting Titan's directed energy technologies contributions.

Titan's primary contributions have been in the field of HPM (Fig. 2). Work started in 1984 when Titan set up and began operating a susceptibility effects test facility for the Defense Threat Reduction Agency (DTRA). A 30 × 20 × 16 ft anechoic chamber to support this work was originally designed to operate in X-band and above. At the outset of the U.S. HPM directed energy program the community felt that the higher gains possible from fixed antenna sizes at higher frequencies would drive technology development into these bands. Over the next 10-plus years, the 25 effects test programs conducted on strategic and tactical systems in the Titan facility and tests conducted at other sites both confirmed that the lowest susceptibility thresholds are observed in the S-band and below. HPM source development history has mirrored these findings.

1.1.1. HPM source developments at Titan. In 1983 Titan initiated HPM source research in its test facility by developing first C-X band overmoded vircators[17] and later an L-band vircator.[13] These systems produced gigawatt outputs through the oscillating virtual cathode mechanism. Their main shortcoming was their broad bandwidth due to chirping induced by diode gap closure. To address this shortcoming Titan developed the first cavity vircator[3] that reduced the output bandwidth from several hundred megahertz to a few tens of megahertz. Versions of these devices were soon after sold to Nucletudes in France



(a) (b) (c)

(d) (e) (f)

Fig. 1. Titan-PSD has designed, fabricated, and delivered the pulse power subsystems for most of the major electric gun facilities worldwide: (a) the decommissioned 32-MJ Thunderbolt System built for a Strategic Defence Initiative Office (SDIO) project; (b) the existing 32-MJ Kirkcudbright system currently being operated by the United Kingdom; (c) the first transportable pulse power subsystem designed for an electric weapon system. [This 8.5-MJ stored energy subsystem, consisting of four separate PFNs, was designed by Titan-PSD under the Army/Army Research Development and Engineering Center (ARDEC) Balanced Technology Initiative and was capable of delivering up to 5 shots at 3 rounds per minute.]; (d) the 52-MJ bank delivered to the ARDEC for electromagnetic and coil gun research; (e) the pulsed power driver for the 40-MJ OMEGA laser at the University of Rochester; and (f) a portion of the 100-Hz, 750-kV, 1.25-μs modulator for NRL's EMRLD laser.

and Culham Laboratory in the United Kingdom to help kick-start HPM effects testing and technology development programs at each location.

Titan initiated work on magnetrons by acquiring S- and X-band, A-6 versions from Bekifi at the Massachusetts Institute of Technology.[2] These devices were integrated into the Titan test facility, and within two years an L-band version of this same design was developed.[16] An S-band magnetron was sold commercially to Thales in France in 1987 to help kick-start HPM effects testing and technology development programs there.

This HPM source development work soon expanded from the initial efforts to field gigawatt-level vircators and magnetrons for the effects testing applications to the development of other high-power sources. These include narrow-band klystrons (both high- and low-perveance variants) and reltrons, as well as ultra-wide-band systems. In parallel, the peak and average power and spectral characteristics of these HPM sources were being explored in research involving phase locking, repetitive pulsing, and frequency agility. Other related Titan work included the development of pulsed power systems to drive these HPM sources involving several different architectures [pulse-forming networks (PFNs) with capacitive energy storage and voltage adders with magnetic compression power conditioning]. These advancements are described briefly in the following.


1980
1990
2000
Compact Systems
High Duty GW-Level HPM
0.7-3.0 GHz Reltrons
1 μs Reltrons
High Energy Magnetrons
L-X-Band Magnetrons
Tunable Magnetrons
φ-Locked Oscillators
Susceptibility Testing
L-X-Band Vircators
HPM Test Facilities
WIS (Germany)
Hyperion (France)
Orion (UK)
Effects Testing
Source Exploration and Development
System Development

Fig. 2. Titan contributed to the field of HPMs in three distinct eras: 1) susceptibility effects testing, 2) HPM source development, and (currently) 3) DEW system development. The effects testing work started in 1984. Then, Titan operated the DTRA susceptibility effects test facility supporting tests for external DoD users. Soon thereafter Titan began using the facility for its own end-to-end DEW research programs. In parallel, Titan HPM source development efforts initially focused narrowly on providing the facility with minimum essential capability but soon expanded to meet specific weaponization and testing requirements. During this period, Titan performed some of the seminal narrowband HPM work associated with phase-locking, frequency agility, and repetitive operation. Source development work continues today, focusing on improving energy output and tunable bandwidth. These efforts are combined with the development of other advanced pulsed power subsystems and components needed to realize compact, efficient, and reliable DEW systems.

In the late 1980s, Titan S-band magnetrons were used in a three-year effort to understand how to achieve output powers exceeding 10 GW from a phase-locked array.[9] Many mission scenarios for DEW systems that could produce burnout or upset in military targets using only a single HPM pulse drove output requirements to this 10-GW level. The combination of gigawatt-level sources locked in phase appeared an effective way to realize this output level without increasing the RF fields and beam energies within individual diodes (and dealing with the RF breakdown and thermal issues that would certainly ensue). In this effort both master/slave and peer configurations were investigated to understand the optimal architecture for such an array. In the end, a module of seven "peer-coupled," 2.8-GHz, magnetrons was built that produced an output power of 2.9 GW. Extrapolation to even higher output levels appeared feasible.

At this time, the HPM community was beginning to recognize that there must exist a middle ground between HPM and electronic warfare (EW) DEW concepts. The HPM approaches were characterized by superpower, single-shot, single-frequency, pulse formats, while the EW approaches made use of very low powers but incorporated modulations in the output pulse formats to effectively exploit susceptibilities within their intended targets. To access this middle ground the HPM sources had to first be shown capable of operation in repetitive or burst modes. This burst capability would be surely required of any DEW system, if only to engage multiple threats deployed in sorties or clusters. In response to these weaponization considerations Titan-PSD developed relativistic magnetrons capable of operation in 1-kHz bursts.[4] A 1.1-GHz, L-band, magnetron was driven by a magnetic pulse compression modulator (see discussion below) and achieved 250-pps repetitive operation at 1.2-GW peak power, in a burst of 100 shots. The average power of 12.6 kW during the burst remains today the state of the art for gigawatt peak power sources. To demonstrate that the magnetron's diode could recover in a time short enough to support higher repetition rates, the device was run for ~5 pulses (limited by the modulator) with 1 ms between individual pulses.

In the early 1990s both Jaycor and PI were actively extolling the use of frequency-agile waveforms to enhance lethality in backdoor attacks. Frequency agility exploits the characteristics of typical coupling cross sections that show pronounced dependence on microwave frequency. An HPM source that can sweep or hop frequency across a band has a higher probability of matching to a coupling resonance than a source fixed at a single frequency. Because of this strong dependence of backdoor coupling and susceptibility levels on microwave frequency, it was apparent that test facilities needed the capability to vary frequency continuously in order to obtain a comprehensive and accurate assessment of any given test asset's susceptibilities. In response to these testing and weaponization considerations Titan-PSD developed frequency-tunable magnetrons. These oscillators can be tuned ±17% about a central frequency,[10] which today still represents the state of the art. In the mid-1990s these magnetrons were integrated into advanced concept demonstrations for the Army and were also exported to the United Kingdom as part of an HPM test facility.

In the late 1980s and early 1990s Titan-PSD developed several ultra-broad-bandwidth (UWB) systems for Army and Air Force DEW research programs. The first system was based on a spark gap-switched Marx that drove a variety of different broadband antennas. It could launch 200-MW total RF power in 3-ns pulses with rise times of ~300 ps at a repetition rate of a few pulses per second. This compact, self-contained system was used in both indoor susceptibility tests and outdoor technology demonstrations. A second project produced a system that could launch impulse waveforms at 200 pps in burst mode.[15] A 3.66-m-diameter paraboloidal reflector was driven at its feed by a hydrogen switch that was integrally coupled to a novel electromagnetic lens. The radiated waveform had a rise time of ~100 ps and a 10–90 rise-to-fall pulse width of 45 ns. The peak electric field on bore-sight measured at 305 m was 4.2 kV/m.

Titan invented the super-reltron in 1992. A suite of tubes that operate between 0.7 and 4.5 GHz has been developed since that time.[12] These novel tubes represent a marriage between pulse power and conventional high-power klystron techniques. An energetic electron beam is modulated by periodic virtual cathode formation, and the bunched electron beam is postaccelerated to energies approaching 1 MeV. Microwave power is extracted with ~50%

Table 3. Operating parameters of Titan-built modulators for DEW applications

Modulator	Voltage, kV	Current	Pulse width	Pulse repetition frequency	Pulse energy	Average power	Switch type
LS-15	50	10 kA	100 ns	1.9 kHz	50 J	95 kW	Spark gap
NED laser driver	±40	260 A	2 μs	10 Hz	3 kJ	30 kW	Thyratron
EMRLD PFN	750	38 kA	1.3 μs	125 Hz	35 kJ	4.4 MW	Spark gap
EMRLD (trigger)	600	260 A	400 ns	125 Hz	100 J	12.5 kW	Spark gap
OMEGA[a] laser driver	15	128 kA	200 μs	Single shot	40 MJ	—	Ignitrons
CLIA HPM driver	750	10 kA	100 ns	250 Hz	750 J	188 kW	Magnetic
ORION HPM driver	500	10 kA	50–500 ns	100 Hz	250 J	25 kW	Thyratron
Compact HPM driver	450	9 kA	450 ns	10 Hz	1.8 kJ	18 kW	Spark gap

[a] 120 modules, each storing 0.33 MJ.

conversion efficiency downstream in a dual-cavity output section that is tuned to the bunch frequency. The reltrons can produce microwave pulse widths approaching 1 μs and pulse energies of a few 100 J, outstripping the relativistic magnetrons that to date are limited to pulse widths of about 100 cycles and pulse energies below 100 J.

In response to the HPM effects testing considerations discussed above, Titan developed frequency-tunable reltrons. These oscillators can be tuned ±10% about a central frequency.[11] These devices are still in development today (see Sec. 2) and have been provided to both France and Germany as HPM threat simulators.

1.1.2. Development of pulse power modulators for DEW applications at Titan. Titan has developed a large number of modulators for a variety of laser and HPM DEW applications, with voltage ratings from tens of kilovolts to several megavolts and average power levels from tens of kilowatts to multimegawatts (Table 3). They also range from relatively simple units to complex, state-of-the-art devices with various different architectures and subsystems. These include PFNs for generating the required pulse shapes; thyratron switching for precise timing of the pulse switching into the load; low inductance layouts for fast output pulse rise times and high-turns-ratio pulse transformers for generating the high voltage outputs. The switching technologies include thyratrons, spark gaps, magnetic switches, and solid-state devices, such as metaloxide semiconductor field effect transistors (MOSFETs), insulated gate bipolar transistors (IGBTs), and thyristors (Fig. 3).

Several of these modulators have been designed for long-lifetime, reliable operations. Such features are essential if these systems are to find their way into military applications. As an example, the Defense Advanced Research Projects Agency (DARPA) excimer Raman-shifted laser device (EMRLD) modulator (a 100-Hz, 750-kV, 1.25-μs, lumped-element PFN to pump an excimer laser) was specifically designed for and demonstrated a lifetime of 10^{10} shots.

The ORION pulser (Fig. 3b) design has command resonant charge and intermediate energy storage sections each switched by thyratrons that drive a step-up transformer and


(a) (b) (c)

Fig. 3. Titan-PSD pulsed power systems based on (a) spark gap, (b) thyratron, and (c) magnetic switching.

Table 4. Key operating parameters in European HPM test facilities

HPM facility	Power density, W/cm^2	Range, m	Frequency, MHz	Maximum pulse width, ns	Maximum repetition rate, Hz	Shots per burst	Source type
UK—Orion	>120	100	1,070–3,300	100	100	100	Magnetrons
France—Hyperion	>1,000	~100	700–3,300	300	1	—	Reltrons and magnetrons
Germany	>170	15	700–1,450	300	10	100	Reltrons
Sweden[a]	~120	15–25	L-Ku	500–5,000	1,000	Continuous	Reltrons

[a] This facility uses conventional high power klystrons in L-, S-, C-, X-, and Ku-bands, with maximum power 25–0.25 MW.

PFN. The modulator can fire 1,000 pulses in a burst at repetition rates up to 100 pps and produces 500 kV into a 50Ω load. It has been used to drive relativistic magnetrons[6] for HPM effects measurements.

The Compact Linear Induction Accelerator (CLIA) (Fig. 3c) was developed for moderate-repetition-rate HPM source research and development.[1] CLIA operates at 250 pps with 750-kV, 10-kA, 100-ns output pulses. The system uses thyratron and magnetic switching throughout and produces 188-kW average power into the load. CLIA is not actively cooled and so is restricted to burst operation with 5,000 pulses in a burst. CLIA has been used to drive both magnetron and klystron loads. This technology is scalable to kilohertz repetitive operation.

1.1.3. Titan pulse power systems for HPM simulation.

In addition to work done supporting domestic RF and microwave DEW research and development, Titan has provided HPM simulation systems for all of the world's major HPM test facilities in Sweden, France, the United Kingdom,[14] and, most recently, Germany. The microwave test parameters and operational capabilities achievable in these international facilities are summarized in Table 4. The types of Titan HPM sources that produce the intense microwave environments are also given. Work continues today upgrading those systems and providing similar hardware for several non-European countries.

2. Most Recent Contributions

Titan-PSD has taken an interest in the full spectrum of developments of advanced subsystems and components that the three U.S. services will require to realize their DEW and electric platform goals. These developments enable many different military missions and cut across many different technologies: advanced capacitors, switches, transmission systems, RF, and optical systems. Some of the pulse power and power electronic subsystem and component developments that Titan is pursuing are summarized in Table 5.

The following subsections describe five electrical subsystems and three components that Titan-PSD is currently developing for DEW applications.

2.1. Titan-PSD development of subsystems for DEW applications

2.1.1. HPM modulator. Titan-PSD has a conceptual design of a high-voltage-pulse power subsystem for a short-pulse HPM system. The given RF pulse output parameters led us to choose a specific tube that is compatible with the constraints of an airborne system, namely the magnetron with a 20Ω impedance and 33% efficiency in a short-pulse mode. Our pulse power design concept is driven by the tube input requirements (20Ω load, 40-ns pulse width, 10 pps) and comprises a low-impedance, water-filled, stepped-pulse forming line (PFL) charged by a fast Marx and discharged through a self-breaking, spark-gap output switch. An advantage to using a liquid dielectric PFL is that its impedance can be easily varied along its length to accommodate variations in load impedance. Input power to the Marx is from two 400-V series strings of lithium ion batteries with solid-state switched intermediate voltage multipliers providing ±40 kV. Batteries are recharged from aircraft power through a small voltage converter.

Figure 4 is a simplified circuit diagram of the pulse power modulator coupled to a 20Ω constant impedance load though a transit-time isolator. The transit-time isolation is integral to the two parallel cables that couple the output of the pulsed power modulator to the microwave source. The Marx stores 1,140 J at a voltage of ±40 kV. It erects to a 1,280-kV open circuit voltage after a trigger pulse is applied to several of its switches from the trigger generator. Near peak PFL voltage, the self-firing spark gap closes, and energy is transferred to the tube at a peak voltage of 640 kV.

Figure 5 shows the voltage and current in the load computed from a more detailed version of the circuit depicted in Fig. 4. Note that the current is multiplied by a factor of 10. Voltage rises in about 11 ns (10–90%), and the width at the peak is approximately 40 ns. We recognize that the impedance of the magnetron can vary during RF generation, but the constant impedance model is sufficient here. An advantage to using a liquid dielectric PFL



Fig. 4. Simplified circuit diagram of the pulse power modulator coupled to a 20Ω constant impedance load though a transit time isolator. This impedance represents a magnetron electron tube load.

Table 5. Titan advanced DEW power technology development rationales

What need does the development of pulsed power technology fulfill?		What need does the development of high power/high current technology fulfill?	
It is an enabler for advanced electric weapons and self-defense systems.		It is an enabler for advanced electric weapons and self-defense systems.	
System	User	System	User
Dynamic protection	Army (FCS), Navy (carrier)	Solid-state lasers	Army (Anti-Aircraft and Anti-Missile), Navy (ASMD)
ETC	Army (FCS), Navy (shore bombardment)	HPM	Army (FCS), Navy (non-lethal area denial)
HPM/electromagnetic pulse	Army (FCS), Navy (non-lethal area denial and ASMD), Air Force (SEAD)	EMALS	Navy (carriers)
EM gun	Navy (shore bombardment)	Electric arresting gear	Navy
UWB	All services (counter C4I)	Ride-thru	All services
		It is an enabler for electrically driven platforms: • FCS platforms for the Army • Combatants such as DD21 for the Navy • More electric aircraft for the Air Force	
It is an enabler for commercial spin-offs: • Environmental remediation systems • Material surface treatments • Pulsed thrusters for satellite station keeping		It is an enabler for commercial spin-offs: • Electric vehicles • Commercial power distribution and control • Advanced semiconductor lithography	
What must we accomplish at the subsystem level? • Develop compact, reliable, affordable PFNs • Develop compact, reliable, affordable modulators • Develop compact, reliable, affordable intermediate energy stores		What must we accomplish at the subsystem level? • Develop compact, reliable, affordable prime power, power conversion and controls • Develop compact, reliable, affordable intermediate energy stores • Develop compact, reliable, affordable ride-thru systems	
What must we accomplish at the component level? • Develop high-energy-density, fast-discharge capacitors • Develop long-life, reliable, high-current switches • Develop compact inductors for pulse control • Develop affordable ultracapacitors • Develop compact, reliable, efficient, high-average-power HPM sources		What must we accomplish at the component level? • Develop high-current-density, high-voltage stand-off solid-state switches • Develop affordable ultracapacitors • Develop compact, reliable, efficient, high-average-power HPM sources	



Fig. 5. Voltage and current (multiplied 10×) in the magnetron load computed using detailed version of the simplified circuit diagram in Fig. 4.

is that its characteristic impedance can easily be varied along its length to accommodate variations in load impedance.

Our compact pulse power system conceptual design mounts all of the subsystems and components in a frame that is 24 in. wide × 24 in. high × 144 in. long. The total weight of the system, including the frame, sealed enclosures, and internal mountings, is 1,420 lb. Figure 6 is a dimensioned diagram of the subsystem that is designed to fit into the port bay of an unmanned aerial vehicle (UAV) with the source in the starboard bay. Frames and supports have been omitted for clarity.

2.1.2. Compact PFN. Titan-PSD has designed, fabricated, and delivered the pulse power subsystems for most of the major electric gun facilities worldwide. These facilities were dedicated to electric gun research and for this reason were designed with a premium on reliability and ease of use of the pulse power subsystem. Compactness was a secondary consideration given the large amount of real estate available for the subsystem.

The 8.5-MJ stored energy subsystem, consisting of four separate PFNs (Fig. 1c), was the first design to use the high-energy-density, 2.5-J/cc (2.5-MJ/m^3) polyvinylidene fluoride (PVDF) Aerovox capacitors; the overall energy density of the PFNs is less than 0.5 MJ/m^3. This low energy density is partially due to the use of "jelly-roll" inductors whose large external fields forced the separation of components and resulted in a low component packing fraction.

Figure 7 is a photograph of a 250-kJ PFN that was constructed under a DTRA/Navy-sponsored ETC gun development project and that was incorporated for a time into the Army/Tank-Automotive and Armaments Command (TACOM) Combat Hybrid Power System (CHPS) system integration laboratory.^{5} Titan-PSD designed this PFN module for compactness by developing innovative bus work and a closed-field inductor for use with the 2.5-J/cc PVDF capacitors. These advances in component design allowed us to achieve a


144"
75"
14"
61"
40"
12"
17"
24"
Marx Pwr. Supply & Trigger Generator
Marx Assy (SF6) (435 lb.)
PFL (H_2O) (327 lb)
SF6
110(lb)
Cable Interface
SB Gas Switch (SF6)
Additional ABR Volume
Top View
Ancillary Systems, Batteries, Rectifiers (A, B, R's), 4 plcs.
16.2-ft. Ideal Length Cables (44 Ω ea.) (65 lb)
PFL OD
Marx Vessel OD
Cable Ports
24"
24"
End View
(Vac.)
SF6
100(lb)
Vacuum Bushing (into source)

*Add 250 lb. for internal supports and space frame

Fig. 6. Top and end views of the pulse power subsystem concept design. The upper portion will be mounted in a frame and placed in one bay of a UAV. The vacuum bushing and the source will be placed in a second bay.

very high packing factor and an overall energy density of 1.25 MJ/m^3. This module designed in 1994 still represents the state of the art in PFN design. Minor variants to the design are under consideration today for EM gun applications.

Titan-PSD has estimated the increases in the overall energy density of small (250–500-kJ) PFN modules that could be realized by achieving specific advances in component technologies.† This includes the use of an existing, more compact vacuum output switch (developed by Titan-PSD) and existing, more compact diodes for the crowbar switches. We would design a higher-energy-density, closed-field inductor and eliminate the dump resistors and associated hardware. Rather than having to dump energy into a resistor, advanced pulsed power systems would be charged by four-quadrant converters capable of returning energy from the PFN to an intermediate energy store. When 5-J/cc film or ceramic, high-energy, reversal tolerant capacitors become available, the utilization of advanced components would lead to a PFN design with an energy density of 3.25 MJ/m^3.

2.1.3. Power supplies for laser applications. Titan-PSD's San Diego operations are actively engaged in building innovative high-average-power systems. Titan is currently delivering power conditioning and control elements for the high-power RF klystrons that will power the DOE Spallation Neutron Source that is now under construction at Oak Ridge, Tennessee, and a series of multimegawatt rectifiers for the U.S. Navy's Electro-Magnetic

---

† Higher energy densities could be achieved in the design of larger modules due to economics of scale.



Fig. 7. Photograph of the 250-kJ PFN with the state-of-the-art, 1.25-MJ/m^3 overall energy density. Titan-PSD has operated this PFN into resistive loads at a rate of 1/3 Hz for extended periods. Operational limits were imposed by the heating of the load, not by the performance of any component of the PFN.

Aircraft Launch System (EMALS). Most recently, Titan has developed conceptual compact power supply designs for deployable pulse power systems for the Strategic Illumination Laser (SIL). The SIL is a diode-pumped, solid-state laser for use as a designator as a part of the U.S. Air Force's Missile Defense Agency's Airborne Laser (ABL). These power supplies will drive compact arrays of light-emitting diodes (LEDs), which will in turn pump the solid-state lasing medium.

Titan's proposed SIL power supply system will consist of a group of innovative ballast-type isolated power converter modules, each fed by its own active-power-factor-corrected rectifier module. By this method the input current harmonic distortion will be minimized, resulting in an overall system power factor of 0.995, which will be acceptable for the Boeing-747 type aircraft (ABL platform) power system. The whole power system will be protected against faults by appropriate fuses and circuit breakers. Initial size and weight estimates for the total power system is 65 liters of total volume and 140 kg of mass. The driving factor in the weight and volume is the need to meet the power factor requirements. Given a dedicated power source, the size and weight could be halved.

Two basic topologies have been examined for power factor correction. They are the "Vienna rectifier,"[8] first proposed by researchers in the Vienna Technical University, and the hex-bridge bidirectional inverter. Both topologies do not contain any magnetic components, operating at line frequency, and both can provide a power factor over 0.99. All merits and drawbacks of both topologies have been initially analyzed, and the Vienna approach is favored for this application.

For the ballast inverter Titan-PSD selected the variable-frequency, zero-power switching full bridge quasi-resonant inverter topology. It is new and until recently not well known but is very promising for multikilowatt power supplies. It shows excellent average to peak ratio for the semiconductor switches, close to the theoretical limit of 50%, and a good power transformer copper utilization factor, typically 90%. It is intrinsically output current limiting and therefore operates well in a current regulated mode and is tolerant to output short circuits. Using this converter topology allows the design to reach unprecedented power conversion efficiency (real value 95%) with excellent reliability.

2.1.4. Electronically reconfigurable battery. We consider a DEW power system in which a 10-kV capacitive store is required to operate repetitively. If the system operates at 3 pps, even for a short period of time, the recharge time would be about 300 ms and the recharge power would be about 500 kW_{avg} (1 MW_{pk}). An important system issue is the size and weight of the 500-kW power conditioning unit.

Titan-PSD has developed a means to eliminate the need for intermediate power conditioning for many DEW systems mounted on hybrid electric vehicles by using the on-board batteries to charge the capacitive store directly. Our approach uses electronic switching to convert the battery modules in the mobility store from a parallel configuration providing vehicle load leveling and/or silent mobility capability, to a series configuration that delivers 500 kW at 10 kV to recharge the capacitor bank and back again. We refer to this as an "electronically reconfigurable battery" (ERB). Note that all of the batteries are recharged in parallel. A similar approach is used in capacitive Marx generators to achieve very high voltage pulsed output.

Figure 8 is a schematic drawing of the circuit of an ERB in a hybrid electric drive vehicle. In this schematic circuit, some battery modules are always in parallel and connected to the vehicle bus. Others, along the left-hand side of the drawing, can be switched between a parallel configuration, which supports the vehicle bus, and series operation for charging the DEW store. Electronic reconfiguration requires three switches per battery module. All switches, with the exception of the output switch, need only block the voltage of a single battery module and open at near zero current (characteristic of capacitor charging) in normal operation. Passive snubbing controls the transient conditions during erection and de-erection. Reconfiguration can be accomplished in less than 1 ms using off-the-shelf, solid-state switches such as IGBTs or MOSFETs.

Figure 8 shows an erectable battery module charging a Guillemin E-type network. Switches 2 and 3 are battery isolation switches, and switch 4 is a series switch. These switches are rated only for the module voltage (1 kV in this case). Mechanical contactors parallel the isolation switches for better efficiency during periods when the pulse power system is not in use. Switch 5 is the output switch, which is rated for the full output of the ERB (10 kV and 50 A) and is most likely a series stack of the same switches used for 2–4. For fault protection and charge interrupt at current, a vacuum contactor and fuse are placed in series with the output switch. All switches are optically isolated with gate power drawn from their adjacent modules. Switch 6 is a high-voltage and current-closing switch, either vacuum or solid state.

Assuming a 20-ton-class vehicle and extrapolating from CHPS requirements, we have developed a conceptual design of an ERB for a hybrid electric vehicle with a system meeting the following requirements: 1) Deliver up to 400 kW to the vehicle bus at 1 kV in parallel operation; 2) recharge a 150-kJ capacitive store to 10 kV in 300 ms; and 3) support 30–45-min silent operation at 80 kW. These requirements mandate the use of very high energy


PFN
6
5
2
3
4
1
Battery Isolation Switches
• Open and close
• Direct or indirect optical gating
• SiC – reduced thermal management and fast recovery
• Si – wide choice of near-term devices
• Parallel Mechanical Contacts (option)
• Use diodes with some loss in flexibility
Battery Series Switches
• Open and close
• Direct or indirect optical gating
• SiC – reduced thermal management and fast recovery
• Si – wide choice of near-term devices
Lithium-ion battery modules

Fig. 8. Schematic circuit of the ERB. Shown is a generic circuit topology for charging a Guillemin E-type network. For the present application, the 10 modules in the dynamic store are all erected in series to produce a 10-kV output. A feature of the ERB is that the dynamic portion of the store may be erected in combinations of series/parallel modules to provide any output voltages that are an integer multiple of the DC bus voltage. This voltage agility, in theory, would allow a single dynamic store to power several loads with different input voltage requirements on the same platform such as ETC guns and HPM systems.

and power density batteries such as the HP series of lithium ion batteries being developed by SAFT and the lithium polymer batteries produced by Ultralife Batteries, Inc., for use in cell phones. The SAFT batteries have a slight advantage in usable power density and packaging for military use, whereas the Ultralife batteries have an advantage in cost due to volume production and a potential for more compact packaging (thin, rectangular) in ERB service. A design and trade study will select the most appropriate cell for the application. We chose the Ultralife cells for the conceptual design used for purposes of discussion in this paper because of our experience with them in our laboratory tabletop ERB and because of the availability of these cells over a range of capacities from 120 mA-h to 3.5 A-h.

The ERB system in this case constitutes only 1/3rd of the total battery for erected (dynamic) operation. The remaining 2/3rds of the store (static) is dedicated to load leveling and silent mobility. The total capacity of ~290 MJ (80 kW-h) accommodates silent mobility requirements. With only 1/3rd (90 MJ, 25 kW-h) of the total capacity configured for on-command electronic erection and de-erection, the vehicle energy storage system maintains its load leveling and silent operation capability even when the pulse power system is active.

For our conceptual design, we assemble 53 Ultralife polymer batteries into individual 200-V stacks. Five of these stacks are placed in series to obtain an output voltage equal to that of the vehicle bus. In the static portion of the store, 20 such series stacks of the UBC34106102 cells (5,300 total cells) are needed to provide the 200-MJ nominal capacity. In the dynamic portion of the store, the UBC383562 cell is used because of its higher current rating. Due to the smaller size of these cells, there can be as many as 4 in parallel by 53 in series per 200-V unit, and five such units will form an erectable module. The module will incorporate all necessary switches and isolation and thermal management hardware.

Ten modules will constitute the entire dynamic store (~90 MJ, 10,600 total cells). The total battery volume in the static and dynamic stores is ~0.282 m^3, and the accessories are expected to add another 0.4–0.6 m^3 for a total volume of less than 1 m^3. The weight for just the batteries would be ~572 kg, with accessories of much lower density adding another 100–200 kg, for a total weight of less than 700 kg. Charging of the ERB is always performed at bus voltage with the dynamic store in parallel configuration.

In load leveling or silent mobility operation, the charge state of the ERB is continuously monitored and controlled by the vehicle's systems. When the pulse power mode is activated, the mechanical contactors bypassing the isolation switches are opened. Next, all isolation switches are opened, followed by the closing of all series switches, and the ERB begins charging the capacitive store. Initially, the load looks like a short circuit, and the charging current is limited by the internal impedance of the ERB cells. As the charge on the bank increases, the charging current diminishes, and the cell voltage begins to rise. Near full charge, the current approaches zero and the ERB output voltage rises to its maximum of ~10 kV. Voltage on the store is monitored and is regulated by chopping the ERB output (i.e., opening and closing the series and output switches as necessary to maintain charge against leakage; this has been demonstrated in the laboratory at rates of up to 1 kHz). When the store discharges, the output switch opens immediately and remains open long enough for the closing switch to recover (1–10 ms). The ERB can remain erected for as long as the pulse power system is active. Recharging of the store is then initiated by reclosing the ERB output switch. When the pulse power system is deactivated, the dynamic store is returned to its parallel configuration by opening the series switches (de-erecting). The dynamic store can then be recharged from the vehicle power bus.

We have created an ERB laboratory demonstration consisting of five erectable modules of 40 V. The Ultralife UBC383562 cells were used and arranged on PC boards that were in turn stacked via standoffs. Isolation and series switching was via optically coupled IGBTs. Some figures of merit (FOM) from the ERB testing include a demonstrated current rise time to 80 A of 4 μs at 200 V and an erection/de-erection frequency of 1 kHz for use in voltage regulation. A FOM from the four series cell tests is a demonstrated current rise time to 120 A of 1 μs, in a maximum power transfer configuration.

2.1.5. Intermediate energy storage. In the preceding section Titan-PSD identified a need for and established the technical feasibility of an advanced technology power conditioning element to charge capacitive stores in DEW systems. The ERB is the solution with the highest efficiency and energy and power density possible. This is critical in order to realize a manageably sized DEW system. A second similar, critical issue in the design and use of pulsed electrical weapon systems involves the level of available platform power. If this power is insufficient to support the required operational burst length and repetitive fire rate of the system, then it may be necessary to incorporate intermediate energy storage into the system design. Intermediate storage could be practically achieved through the use of secondary batteries, flywheels, and ultracapacitors (also referred to as electric double-layer capacitors or EDLCs). Figure 9 is a schematic diagram of intermediate energy stores in two DEW systems.

Figure 10 shows a present application of an EDLC energy storage system in providing ride-through of voltage sags and momentary outages for an induction motor. The output of the store is connected across the direct current (DC) link of the asynchronous drive and supports its voltage. Titan-PSD has manufactured a ride-through system that has been demonstrated to respond to sags and outages within 10 ms. It can provide


Controls
Fault Detection
From A/C Bus ~270 V
~400 V
7 - 40 kV
To HPM Source 250 – 1000 kV 100 ns to 100 μs
IES Recharger
Intermediate Energy Store (IES)
Power Conditioning
Pulsed Power
Ultracapacitors Li Ion Batteries
Voltage Controlled Switching
Controls
Fault Detection
From A/C Bus ~270 V
~270 V
To Laser Diodes ~ 120 V
IES Recharger
Intermediate Energy Store (IES)
Power Conditioning
Ultracapacitors Li Ion Batteries
Current Controlled Switching

Fig. 9. Two DEW block system schematics with intermediate energy storage.


Ride-through System
Charger
Boost Converter
V_{uc}
Ultra Capacitors
C_{out}
V_{out}
High Voltage Interface and Charger Control
User Interface
DSP Controller
DC
DC
Logic Power Supply
Utility
ASD
IM
time delayed
24 V contactor

Fig. 10. Circuit diagram of an EDLC ride-through system supporting the DC link of an asynchronous drive (ASD).

100 kW for up to 5 s, which is sufficient to allow for orderly shutdown in a prolonged outage.

Titan-PSD has also developed several concept designs of EDLC energy storage systems for military applications. For example, one EDLC system design would be capable of supporting the DC link in a Navy shipboard system at 480 V for 12.5 s at 250 kW. This system is estimated to be 50% smaller and lighter than a corresponding flywheel system (i.e., the Caterpillar UPS-250 system). With minor modifications, the same system (or several systems in parallel) could be used as an intermediate energy store for DEW systems.

2.2. Titan advanced component developments to enable DEWs

2.2.1. Solid-state switches for severe service. The key enabling technology for nearly all pulse power systems for DEW applications is the switch that initiates and delivers the pulsed electrical output from the electrical energy store to the load. This switch must hold off high voltage (typically $\geq$10 kV), close rapidly ($<$1 μs), carry high peak current (100–500 kA) with high initial rate of rise (50–100 kA/μs), sustain a high total action ($\geq 10^7$ A^2-s), and recover rapidly ($<$10 ms). In addition, the switch must support high current density, operate reliably under mechanically stressing conditions, have minimum weight and volume claims, and not require ancillaries such as vacuum pumps or gas flow subsystems. At present, the hydrogen thyratron is most frequently selected to meet these simultaneous requirements, but thyratrons are large and heavy devices, with auxiliary equipment that consumes several kilowatts and often require immersion in oil. The Army Research Laboratory has been actively seeking solid-state devices for DEW utility[7] and Titan-PSD is weighing in by developing a high fluence, laser gated and pumped (silicon) thyristor (LGPT) that will satisfy these requirements.

High fluence optical gating of thyristor switches has been chosen for numerous pulsed power switching applications. Light activation with high fluence laser sources enables the use of solid-state switching devices in performance parameter spaces previously serviced only by vacuum and gas spark gaps. If the output from the high fluence source is properly distributed within the switching medium, the $\mathrm{d}i/\mathrm{d}t$ capability of the switch does not depend on the rate of plasma spreading. Rather, $\mathrm{d}i/\mathrm{d}t$ becomes a function of the rate of rise of the optical fluence. In addition, optical gating eliminates the extensive and intrusive physical gate structure that limits the conduction area of the highest $\mathrm{d}i/\mathrm{d}t$ conventional solid-state devices. Properly designed laser-gated devices are typically capable of higher $\mathrm{d}i/\mathrm{d}t$, peak current, and charge transfer for a given silicon area than conventional solid-state devices.

The band edge for intrinsic silicon is ~1.12 eV, corresponding to ~1,111 nm. However, silicon is an indirect band-gap material so that the optical phonon energy (0.063 eV) adds to the photon energy to create e–h pairs out to 1,170 nm. In most previous efforts involving direct laser-gating of silicon devices, a solid-state laser was used; typically either Nd:YAG or Nd:YVO at 1,064 nm. However, over the past 10 years, the development of compact diode-pumped solid-state lasers has significantly reduced the size of the requisite optical sources and improved their lifetime and reliability. More important, the InGaAs laser diode bars that were developed for pumping these solid-state lasers have been pushed to longer wavelengths, approaching and exceeding that of the silicon band edge. In principle, the center wavelength of InGaAs laser diode bars is selectable by design over a continuum from 850 nm through at least 1,150 nm. This allows direct optical gating and pumping of silicon by the diodes without any of the intermediary options of the preceding paragraph. Figure 11 is an illustration of an on-board laser diode gated and pumped silicon thyristor, which is one of the candidate approaches in development now.

Titan-PSD is currently performing on two programs and has finished a third that provide technical leverage for further switch development. Our Electra Advanced Pulsed Power Program is a five-year, Naval Research Laboratory (NRL)/DOE-sponsored effort to develop advanced pulsed power components and systems for KrF laser IFE (krypton fluoride laser inertial fusion energy). The most critical component is the primary switch, and we are



Fig. 11. Illustration of a laser gated and pumped thyristor.

developing an on-board LGPT for this role. The switching requirements are repetitive, high peak current and di/dt, as well as high efficiency (the switch dissipates $<1.5\%$ of stored energy) and long lifetime (10^9 shots). The LGPT is to be used in a Marx generator, and the single device operating parameters are 16.4-kV working voltage, current density 2.25 kA/cm^2, peak current 225 kA, max di/dt 900 kA/μs, pulse width 800 ns, and repetition rate 5 pps continuous. The lifetime requirement limits the thermal excursion per pulse to a few degrees, and therefore the action per square centimeter is low ($\sim$2 A^2-s).

Another current Titan-PSD program is to develop compact pulsed power components for the Air Force Research Laboratory (AFRL) at Kirtland Air Force Base. Components under development enable a compact, long-lifetime Marx-PFN driver for a narrowband HPM source. The di/dt requirement is a few hundred kA/μs/cm^2(Si) or 2 MA/μs total, with a peak current of 30 kA. To satisfy the switching requirements for this application, we are considering the LGPT, a solid-state laser activated switch, and a hybrid combination of the two.

Although the action and charge transfer in these Electra and AFRL applications are substantially less than that found in some pulse power applications, they serve to illustrate our confidence in the high power laser diode bars for high di/dt service. In both cases, the pulse width of the energy transfer is short enough that thyristor action has barely begun by the time the pulse is over. Because of this, a large fraction of the total charge conducted during the pulse must be supplied optically. The diode laser bars and their drive circuitry are capable of supplying an illumination fluence of up to 6 kW/cm^2(Si) within 20 ns and sustaining that level for at least several microseconds. Fluence of several kilowatts per square centimeter is desirable for initial gating in many DEW applications. The required fluence drops to 250–500 W/cm^2 for continuous pumping.

Another effort was recently undertaken in a conceptual design study for an optically gated and pumped switch for rectification of compulsator (pulsed alternator) output for driving an electromagnetic gun. This completed study was performed by Titan-PSD and the Optiswitch Technology Corporation for the Institute for Advanced Technology (IAT). The on-board LGPT design was chosen because of the customer's desire to reduce the overall device count and silicon area compared with conventional devices. Specifically, we designed a 16.7 kV, 100–115-cm^2 asymmetric (blocks voltage forward direction only) thyristor and series diode. Depending on the allowable temperature excursion per shot, our approach replaces ~80 conventional devices with 3–5 series pairs (6–10 devices total; 340–500 cm^2 active) for the same forward losses. This is possible because continuous pumping of thick (2.5-mm), high-voltage (15–20-kV) devices with photo-carriers mitigates the carrier population deficit in the n-base. Electrically gated devices of the same voltage capability typically exhibit huge commutation and conduction losses and are therefore impractical for this type of service. Reverse blocking was handled by a series optically pumped diode. Separating the forward and reverse blocking functions allowed more freedom in designing for reverse recovery, a feature deemed necessary due to repeated failures of symmetric (blocks voltage both directions) devices in this service. Laser diode pumping served to reduce the forward losses in the series diode element as in the thyristor.

The switch was designed to handle a peak current of 1.6 MA (3.3–4.7 kA/cm^2) for 600 μs when installed in a half-wave, four-phase rectifier. Nine total cycles are rectified per shot of the electromagnetic gun. The initial design (500 cm^2 active) limited the temperature excursion per shot to ~100°C, commensurate with a service life of ~10^4 shots. In the extreme, the current density could be pushed to 4.7 kA/cm^2 and optical pump power doubled, resulting in a ΔT approaching 180°C and ~200-shot lifetime. The laser diode bars in the initial case provided a constant 500 W/cm^2 of silicon for each 600-μs conduction phase. This goes to 1 kW/cm^2 in the extreme case.

2.2.2. Next generation reltron microwave generator development. Reltron HPM sources were invented and developed by R. Bruce Miller of Titan Advanced Innovative Technologies from the mid-1980s through 1998. The PSD of Titan assumed responsibility for reltron contracts in 1998. Projects included one complete HPM simulator for a government research laboratory in Germany and eight reltron tubes of various specifications. In developing these eight tubes, enough mechanical and electrical modifications have been included to justify their designation as "second-generation" designs.

Reltrons are both compact and efficient. The electron beam is highly modulated over ~10 cm and postaccelerated prior to drifting to the output cavities and beam collector. This beam transport requires only ~75-cm overall length for L-band tubes (Fig. 12). The output cavities are incorporated into a standard rectangular waveguide. Microwave power is efficiently extracted (~80%) directly in TE$_{10}$ mode. The overall efficiency (peak electrical to microwave power) is 30–40%.

In general these new tubes move the reltron technology base in the directions of longer pulsewidths (~1–2 μs), increased frequency tunability (~±13%), lower driver voltages (500–600 kV), and higher repetition rates (~10 Hz for demountable versions, ~300 Hz for sealed tubes). Second-generation improvements include a new high voltage insulator design, new movable current contacts for the modulation and output cavity tuners, reduced outgassing, and monolithic grids. The frequency range for these eight tubes covers 700–1,450 MHz. Programs are in place now to extend this range.

In addition to the objective to extend the frequency coverage, efforts are underway to improve beam optics to reduce current losses and thereby improve efficiency and microwave output power. A new beam current diagnostic package has been recently implemented to



Fig. 12. L-band reltron capable of generating flat 200-MW, 900-ns pulses with frequency stability $\delta f/f < 0.3$. This generation of reltrons is capable of RF pulse widths of ~300 RF cycles, repetitive pulse operation from single-shot to 10 Hz, and ±10% continuous-frequency tunability.

better infer basic performance parameters and to assist in comparing benchmarking simulations. These calculations simulate performance in the actual geometry and are generated with a three dimensional particle-in-cell code (the LSP code from Mission Research Corporation). Measured waveforms generated by a recently delivered L-band tube are shown in Fig. 13. This tube produces ~185 MW in flat, 900-ns pulses with excellent frequency stability. The LSP code was essential during this tube's development. A new era in microwave tube design has emerged with the development of accurate three-dimensional models.

2.2.3. HEM magnetron. Backdoor microwave effects on electronics systems in modern weapons fall into three broad categories. Two categories are characterized by high peak power density and microwave formats that overwhelm the target system with an electric field that is high enough to cause circuit upset or burnout. In the third category, effects are caused by coupling spurious signals into the target system, akin to classical smart jamming, interference or spoofing[‡] techniques used by the EW countermeasures community. The DEW microwave pulse formats appropriate to the latter class of effects are generally distinguished from upset and damage pulse formats by lower peak power density thresholds but more specific requirements on frequency and amplitude modulations and

---

[‡] Low incident microwave levels can cause "interference" with the operation of threat weapon electronic systems, producing high levels of noise in sensitive circuitry to "mask" true signals. The incident microwave signal is said to "spoof" if it is tailored to "mimic" the true signal and to thereby produce false commands.



Fig. 13. Waveforms from the 185-MW L-band reltron: the top trace is the heterodyne (l.o. = 1.3 GHz) showing excellent frequency stability, and the second trace is the steady, flattop output power measured with a calibrated directional coupler. (The data are conditioned with a low-pass filter; higher harmonic content is know to be more than 13 dB below the primary L-band signal.) The third trace is the radiated power monitored with an uncalibrated, free-field B-dot, and the last trace is an uncalibrated profile of the Marx current.



Fig. 14. Titan's L-band HEM magnetron. This is the highest-average-power magnetron that is commercially available.



Fig. 15. The principal system elements of the ATD system are a power supply, a modulator, an HEM source, and an antenna. These components are supported by a control system and a cooling system. For the DTRA ATD ground-based system the power supply and operators' console(s) are housed in a shelter mounted on one flatbed trailer while the remaining components are mounted on another flatbed trailer (out of the field of view to the right). The system was designed to broadcast 2-MW peak power pulses with an average power of 300 kW for 30-s missions. This yields a peak fluence of 1 mW/cm^2 at a range of 2,400 m.

repetition rate. All three categories of effects can be induced by DEW systems based on high-power RF, narrow-band, pulsed HPM or long-pulse, high-energy microwaves (HEMs).

Titan has developed an HEM laboratory source and an HEM advanced technology demonstration (ATD) source for DEW purposes at its California Tube Laboratory. These HEM sources have efficiencies of approximately 85%. This high efficiency minimizes prime power and cooling requirements, thus significantly minimizing overall DEW system size and weight. The HEM magnetron, shown in Fig. 14, has produced 900-kW peak and 150-kW average powers and can easily be upgraded to 300-kW average power. The unique modulation characteristics of this magnetron can produce modulation effects of 30 MHz or greater in the target systems. More operational details are given in Table 6.

The ATD system shown in Fig. 15 combines the outputs of two 150-kW-average-output power magnetrons. The maximum peak output power obtained to date is 1.2 MW. The magnetrons with their respective magnet yokes each weigh about 200 lb, and each takes up about 4 ft^3. When combined their efficiency is over 76%, therefore together they absorb only 95 kW and are actively cooled. Variants of this RF system are suitable for Army, Navy, and Air Force missions.

Table 6. California tube laboratory HEM magnetron operational specifications

Parameter	Value
Frequency, fixed	915 MHz (890–920 MHz possible as well)
Power output	
Continuous wave	300-kW minimum
Pulse	600-kW peak (900 actually achieved) 300-kW avg (nominal 50% duty)
Pulse width	10s of microseconds to 5 ms
Peak anode voltage	42 kV
Peak anode current	17 A
Beam efficiency	88% typical
Water-cooled anode	20 gpm typical
Filament	12 VAC, 200-A typical standby

3. Conclusions and Significance

The first laser and HPM DEWs are just now being deployed, and new threats emerging in the information age will sustain the need for continued DEW development and acceptance. The deployment of even more advanced DEW systems and in fact the DoD's intent to field more (or all) electric fighting platforms depend critically on the availability of compact, lightweight, efficient pulsed power subsystems and long-lived, reliable advanced power conditioning and front-end components.

Titan has been supporting U.S. directed energy programs by providing services and analysis and developing advanced technologies since the early 1980s. Today, Titan is the only U.S. industrial supplier of commercial HPM generators. We have advanced pulsed power and power electronics technology development programs involving intermediate and primary electrical energy storage, solid-state switching, power conditioning, electrical-to-microwave conversion, and novel microwave antennas underway now. Titan is focused on providing pulsed power and C4ISR (command, control, communications, computers, intelligence, surveillance, and reconaissance) solutions for national defense and is intent on maintaining its industrial leadership in military information technologies.

Acknowledgments

The authors recognize and acknowledge contributions made by Jim Benford, Jerry Levine, R. Bruce Miller, and David Blank to the development of the primary narrow-band microwave sources that were the precursors of much of the HPM and HEM technology that Titan offers today.

References

[1] Ashby, S., D. Drury, G. James, P. Sincerny, and L. Thompson, "CLIA—A Compact Linear Induction Accelerator System," *Proceedings 8th International IEEE Pulsed Power Conference*, San Diego, CA, p. 940 (1991).

[2] Bekifi, G., and T.J. Orzechowski, Phys. Rev. Lett. **37**(6) 379 (1976).

[3] Benford, J., D. Price, H. Sze, and D. Bromley, J. Appl. Phys. **61**(5), 2098 (1987).

[4] Benford, J.N., N.J. Cooksey, J.S. Levine, and R.R. Smith, IEEE Trans. Plasma Sci. **21**(4), 388 (1993).

[5]Bhasavanich, D., C.M. Gilman, H.G. Hammon, and K. Nielsen, "80 kW, 1/3 Hz Repetitive-Fire PFN for Electrothermal Launchers," *Proceedings 10th International IEEE Pulsed Power Conference*, Albuquerque, NM, p. 155 (1995).

[6]Hammon, J., S.K. Lam, and S. Pomeroy, "A Transportable 500 kV, High Average Power Modulator with Pulse Length Adjustable from 100 ns to 500 ns," *Proceedings 10th International IEEE Pulsed Power Conference*, Albuquerque, NM, p. 429 (1995).

[7]Kingsley, L.E., R. Pastore, and H. Singh, "Solid-State Power Switches for HPM Modulators," *Proceedings 10th International IEEE Pulsed Power Conference*, Albuquerque, NM, p. 65 (1995).

[8]Kolar, J.W., and F.C. Zach, "A Novel Three-Phase Interface Minimizing Line Current Harmonics of High-Power Telecommunications Rectifier Modules," *Record of the 16th IEEE International Telecommunications Energy Conference*, Vancouver, Canada, p. 367 (1994).

[9]Levine, J.S., N. Aiello, J. Benford, and B. Harteneck, J. Appl. Phys. **70**(5), 2838 (1991).

[10]Levine, J.S., B. Harteneck, and H.D. Price, *Intense Microwave Pulses III*, SPIE Vol. 2557, p. 74 (1995).

[11]Miller, R.B., K.W. Habiger, W.R. Beggs Jr., and J.R. Clifford, "Advances in Super-Reltron Source Development," *Intense Microwave Pulses III*, SPIE Vol. 2557, p. 2 (1995).

[12]Miller, R.B., C.A. Muehlenweg, K.W. Habiger, J.R. Smith, and D.A. Shiffler, *Intense Microwave Pulses II*, SPIE Vol. 2154, p. 99 (1994).

[13]Price, D., D. Fittinghoff, J. Benford, H. Sze, and W. Woo, IEEE Trans. Plasma Sci. **16**(2), 177 (1988).

[14]Price, D., J.S. Levine, and J. Benford, "ORION-A Frequency-Agile HPM Field Test System," *Seventh National Conference on High Power Microwave Technology*, Laurel, MD (1997).

[15]Smith, I.D., D.W. Morton, D.V. Giri, H. Lackner, C.E. Baum, and J.R. Marek, "Design, Fabrication and Testing of a Paraboloidal Reflector Antenna and Pulser System for Impulse-Like Waveforms," *Proceedings 10th International IEEE Pulsed Power Conference*, Albuquerque, NM, p. 56 (1995).

[16]Smith, R.R., J. Benford, D. Harteneck, and H.M. Sze, IEEE Trans. Plasma Sci. **19**(4), 628 (1991).

[17]Sze, H., J. Benford, W. Woo, and B. Harteneck, Phys. Fluids **29**(11), 3873 (1986).

The Tom Bearden
Website

TOWARDS A NEW ELECTROMAGNETICS
PART I: SOLUTION TO TESLA'S SECRETS AND THE SOVIET TESLA WEAPONS

Table of Contents

Foreword **NEW**

Starting Pages **NEW**

Soviet Tesla Weapons

References

The Tom Bearden Website

TABLE OF CONTENTS

Acknowledgements

Foreword

Part I

Solutions to Tesla's Secrets and the Soviet Tesla Weapons

References

Part II

Reference Articles for Solutions to Tesla's Secrets

Bottone, A., "Nikola Tesla's New Wireless", *Electrical Engineer*, London, Dec. 24, 1909.

"Tesla's New Device Like Bolts of Thor", *N. Y. Times*, Dec. 8, 1915.

Secor, H. Winfield, "Tesla's views on Electricity and the War", *Electrical Experimenter*, Aug., 1917.

Tesla, Nikola, "The Effect of Statics on Wireless Transmission", *Electrical Experimenter*, Jan., 1919.

Gernsback, H., "Underground Wireless", *Electrical Experimenter*, March, 1919

Secor, H. Winfield, "America's Greatest War Invention, The Rogers Underground Wireless", *Electrical Experimenter*, March, 1919.

Tesla, Nikola, "Tesla on High Frequency Generators", *Electrical Experimenter*, April, 1919.

Tesla, Nikola, "The True Wireless", *Electrical E:x:perimenter*, May, 1919.

Tesla, Nikola, "My Inventions, v. The Magnifying Transmitter", *Electrical Experimenter*, June, 1919.

"The Rogers Underground Aerial For Amateurs", *Electrical Experimenter,* June, 1919.

"A Giant Eye to See Round the World", *Albany Telegram,* Feb. 25, 1923.

Tesla, Nikola, "'World System' of Wireless Transmission of Energy", *Telegraph and Telephone Age,* Oct. 16, 1927.

Secor, H. Winfield, "Tesla Maps Out Our Electrical Future", *Science and Invention,* April, 1930.

Tesla, Nikola, "Man's Greatest Achievement, *N.* Y. *American,* July 6, 1930.
"Tesla at 75", *Time,* July 20, 1931.

Gernsback, Hugo, "Faster Than Light:", *Everyday Science and Mechanics,* Nov., 1931.

"No High Speed Limit, Says Tesla", *The Literary Digest,* Nov. 7, 1931.

O'Neill, John J., "Tesla Cosmic Ray Motor May Transmit Power 'Round Earth", *Brooklyn Eagle,* July 10, 1932.

"Tesla, 76, Reports His Talents At Peak", *N. Y. Times,* July 10, 1932.

Tesla, Nikola, "Pioneer Radio Engineer Gives Views on Power", *N. Y. Herald Tribune,* Sept., 11, 1932.

Bird, Carol, "Tremendous New Power Soon to be Unleashed", *Kansas City Journal-Post,* Sept. 10, 1933

"Tesla 'Harnesses' Cosmic Energy", *Philadelphia Public Ledger,* Nov. 2, 1933.

"Tesla Sees Evidence Radio and Light are Sound", *N.* Y. *Times,* April 8, 1934.

"Invents Peace Ray", *N. Y. Sun,* July 10, 1934.

"Death-Ray Machine Described", *N. Y. Sun,* July 11, 1934.

"Tesla, at 78, Bares New 'Death-Beam'", *N. Y. Times,* July 11, 1934.

Alsop, Joseph W., Jr., "Beam to Kill Army at 200 Miles, Tesla's Claim",
N. Y. Herald Tribune, July 11, 1934

Tesla, Nikola, "Tesla on Power Development and Future Marvels", *N. Y. World Telegram,* July 24, 1934.

Wilshimer, Helen, "Dr. Tesla Visions the End of Aircraft in War", *Every Week Magazine,* Oct. 21, 1934.

"A Machine to End War", by Nikola Tesla as told to George Sylvester Viereck,
Liberty, Feb., 1935.

"Tesla Predicts Ships Powered by Shore Beam", *N. Y. Herald Tribune,*
June 5, 1935.

"3 Tesla Inventions", *N. Y. Sun,* July 9, 1935.

Sparling, Earl, "Nikola Tesla, at 79, Uses Earth to Transmit Signals;
Expects to Have $100,000,000 Within Two Years", *N. Y. World Telegram,*
July 11, 1935.

"Tesla's Controlled Earthquake", *N. Y. American,* July 11, 1935.

"Tesla, 79, Promises to Transmit Force", *N. Y. Times,* July 11, 1935.

Tesla, Nikola, "Expanding Sun will Explode Someday Tesla Predicts",
N. Y. Herald Tribune, Aug. 18, 1935.

"Tesla, 80, Reveals New Power Device", *N. Y. Times,* July 11, 1936.

"Sending of Messages to Planets Predicted by Dr. Tesla on Birthday",
N. Y. Times, July 11, 1937.

"Tesla Has Plan to Signal Mars", *N. Y. Sun,* July 12, 1937.

"In the Realm of Science: Tesla, Who Predicted Radio, Now Looks Forward
to Sending Waves to the Moon", *N.* Y. *Herald Tribune,* Aug. 22, 1937.

"Aerial Defense 'Death-Beam' Offered to U. S. By Tesla", *Baltimore Sun,* July 12, 1940.

"'Death Ray' for Planes", *N. Y. Times,* Sept. 22, 1940.

"Proposing the 'Death Ray' for Defense", *Philadelphia Inquirer,* Oct. 20, 1940.

Swezey, Kenneth M., "Nikola Tesla", *Science,* May 16, 1958.

"Cableless Power", *Electronics* (Digest), July 22, 1960.

"Fireballs for Defense?", *Christian Science Monitor,* Feb. 7, 1962.

Lagus, George W., "The Use of Ground in High-Frequency Circuits", *Radio-TV and Science and Electronics,* June-July, 1969.

Jamison, S. L., "Life Energy", *Probe, The Unknown,* June, 1973.

Jueneman, Frederic B., "The First Law of Thermodynamics", *Industrial Research,* Feb., 1974.

Wade, Nicholas, "Charged Debate Erupts over Russian Beam Weapons", *Science,* May 27, 1977.

Benford, Gregory, "Zeus in Orbit", *Omni,* Sept., 1981.

JAMES HARRIS ROGERS' PATENTS

(In order of patent application date)

958,829, Method and Apparatus for Producing High Frequency Oscillating Currents. James H. Rogers. Filed Jan. 20, 1910.

1,220,005, Wireless Signaling System. James Harris Rogers and Henry H. Lyon. Filed Nov. 10, 1916.

1,322,622, wireless Signaling System, James H. Rogers and Henry H. Lyon, Filed Nov. 10, 1916.

1,349,103, Radiosignaling System. James Harris Rogers. Filed May 2, 1917.

1,315,862, Radiosignaling System. James Harris Rogers. Filed Jan. 17,

1918.

1,349,104, Radiosignaling System. James Harris Rogers. Filed Jan. 17, 1918.

1,303,729, Wireless Signaling System. James Harris Rogers. Filed Jan. 10,
1919.

1,303,730, Radiosignaling System. James Harris Rogers. Filed Jan. 11, 1919.

1,316,188, Radiosignaling System. James H. Rogers. Filed Mar. 28, 1919.

ACKNOWLEDGEMENTS

PART I

I am much indebted to Mr. Carey Briggs for furnishing references which strongly support the existence of scalar potential waves and scalar interferometry. Among those papers are Whittaker (1903), Nisbet (1955) , and other papers dealing with Hertzian potential theory. As ever, my profound gratitude is due Hal Crawford for his splendid illustrations which accompany this paper. I am also indebted to John Ratzlaff and the Tesla Book Company for graciously furnishing important Tesla references for me to analyze. My sincere thanks go to Messrs. Jim Beal and Williard Van de Bogart for furnishing important references on exoelectron emission and tectonic fault zones, and to Dr. Robert Beck for furnishing important material on the Rogers underground and undersea transmission system. Additional assistance was also received from Mr. Peter Kelly, Joe Siegeldorf, Joe Gambill, and Bob Beutlich. I am also very appreciative of the information furnished by Bob Jones and Vestigia on the beautiful Vestigia mystery light experiments.

PART II

A. L. Lez, San Anselmo, Calif.
Thorn L. Mayes, Saratoga, Calif.
Bob Nelson, Berkeley, Calif.
Mildred Ratzlaff, Millbrae, Calif.

The Tom Bearden Website

FOREWORD

The long-searched-for Tesla secrets have been solved by Tom Bearden. Part I contains the specific description of the solutions to Tesla's secrets and the Soviet Tesla weapons.

The present electromagnetic theory has several flaws, and it is these errors that have hidden the long-sought unified field theory. The explanations presented by the author provide clarity and understanding to related Tesla writings and patents.

Before the turn of the century, Nikola Tesla had discovered and was utilizing a new type of electric wave. Tesla repeatedly stated that his waves were non-Hertzian, and that his wireless transmissions did not fall off as the square of the distance. The author has found that the wave which Tesla was using is a longitudinal scalar wave, capable of many times the speed of light. When coupled with another scalar wave (Tesla wave),
the resulting vector wave can be the source of electromagnetic energy for electrical power, a protective force field, or a destructive weapon.

The booklet is well illustrated with special drawings by Hal Crawford. The bibliography includes corroborating information on all major points. Part II presents reprints or the entire subject matter of selected articles from the bibliography, plus additional references of importance. Articles are arranged in chronological order. Also included are nine patents by James Harris Rogers which were the basis of successful wireless communication during World War I. These principles of underground and sub-sea wireless were based on Tesla's discoveries.

Bearden's solutions are truly a major breakthrough, and an absolute necessity to the understanding of existing Tesla writings. It is also important that more should be known of this extraordinary individual, Thomas E. Bearden.

BIOSKETCH:

A nuclear engineer, wargames analyst, and military tactician, Lieutenant Colonel (Retired) Tom Bearden has over 26 years experience in air defense systems, tactics and operations; technical intelligence, anti-radiation missile countermeasures; nuclear weapons employment, computerized wargames; and military systems requirements.

He is currently with the Alabama division of a large aerospace company where he is involved in determining the future requirements for laser weapons.

Lieutenant Colonel Bearden obtained a Master of Science degree in nuclear engineering from the Georgia Institute of Technology and a Bachelor of Science degree in mathematics from Northeast Louisiana University. He is also a graduate of the U.S. Army Command and General Staff College and several U.S. Army artillery and missile schools.

He has had direct experience with tube artillery and with the Ajax, Hercules, Hawk, and Patriot missile systems and the production of technical intelligence on Soviet surface-to-air missile systems for the U.S. Army/Department of Defense.

Tom holds a Sandan (third degree black belt) in Yoseikan aikido; is a singer, guitarist and songwriter; member of Mensa, Society for the Investigation of the Unexplained, Vestigia, the American Association of Meta-Science: and is on the board of governors of the U.S. Psychotronics Association. In addition, he is Alabama Director of a small nonprofit foundation, the Association of Distinguished American Scientists and is a MUFON adviser on nuclear engineering.

He also edits *Specula,* Journal of the American Association of Meta-Science.

Tom is primarily active as a theorist on UFOs, parapsychological and paranormal phenomena, and psychotronics. He is the author of a book, *The Excalibur Briefing,* Strawberry Hill Press, 2594 15th Avenue, San Francisco, California 94127 and has numerous technical papers dealing with new paradigm physics, paranormal phenomena, and Soviet psychotronic weapons.

Finally, Bearden's *Solutions to Tesla's Secrets and the Soviet Tesla Weapons* promises to be recognized in the future as a major contribution to our present technology.

JTR

TESLA'S SECRET AND THE SOVIET TESLA WEAPONS

© T.E. Bearden 1981

With Special Drawings by Hal Crawford

Before the turn of the century, Nikola Tesla had discovered and was utilizing a new type of electric wave. Tesla repeatedly stated his waves were non-Hertzian, and his wireless transmissions did not fall off as the square of the distance. His discovery was apparently so fundamental (and his intent to provide free energy to all humankind was so clear) that it was responsible for the withdrawal of his financial backing, his deliberate isolation, and the gradual removal of his name from the history books.

By 1914 or so, Tesla had been successfully isolated and was already nearly a "nonperson." Thereafter Tesla lived in nearly total seclusion, occasionally surfacing (at his annual birthday party for members of the press) to announce the discovery of an enormous new source of free energy, the perfection of wireless transmission of energy without losses, fireball weapons to destroy whole armies and thousands of airplanes at hundreds of miles distance, and a weapon (the "Tesla Shield," I've dubbed it) that could provide an impenetrable defense and thus render war obsolete.

In my pursuit of Tesla's secret, it gradually became apparent to me that present orthodox electromagnetic theory is seriously flawed in some fundamental respects. One of these is in the definition and use of ϕ, the scalar electrostatic potential. It is this error which has hidden the long-sought unified field theory from the theorists.

In the theory of the scalar electrostatic potential (SEP), the idea is introduced of work accomplished on a charge brought in from a distance against the scalar field. The SEP is not a vector field, but is a scalar field. Indeed, scalar potential cannot of itself perform work on a charged mass; if it could do so, then tremendous force would exist on every mass due to the extremely high SEP of the vacuum itself. Only a differential of SEP between two spatial points can produce force or accomplish work. (Rigorously, a differential of scalar potential between two spatial points constitutes a vector. Only a vector can produce force and do work.)

Also, work can only be done on a mass. Further, it takes time* to move an electron or other charged mass between two spatial points, and so the work performed by a spatial differential of the ϕ-field requires time. Rigorously, the delta SEP is voltage, not SEP per se, and is directly related to

E field. The entire voltage concept depends on the work performed in moving a mass, after that mass has moved. The idea of "voltage" always implies the existence of a steady differential of ϕ between two spatial points for a finite length of time, and it also involves the assumption of a flow of actual mass having occurred. SEP, on the one hand, is always a single-point function; on the other hand, difference in potential (i.e., V) is always a two point function, as is any vector.

Yet many graduate level physics and electromagnetics papers and texts erroneously confuse ϕ and V in the static case! Such an interpretation is of course quite incorrect.

---

* *Two spatial points involve at least* $\Delta t = \Delta L/c$ *in time. All vectors and gradients involve 2 separated spatial points, and thus present timelines in 4-space.* ϕ_4 *is a point, not a line, in 4-space.*

Another common assumption in present EM theory -- that the electrostatic potential (ϕ_0) of the normal vacuum is zero -- has no legitimate basis. In fact, we know ϕ_0 is nonzero because the vacuum is filled with enormous amounts of fluctuating virtual state activity, including incredible charge fluctuations. And by virtue of its point definition, ϕ_0 must be the "instantaneous intensity" of these fluctuations -- but both in space and time. The scalar electrostatic potential is therefore the "instantaneous stress" on spacetime itself, and a measure of the intensity of the virtual state flux through a 4-dimensional spacetime point.

Potential theory was largely developed in the 1800's, before the theory of relativity. Time flowrate was then regarded as immutable. Accordingly, electrostatic "intensity" was chosen as "spatial intensity," with the connotation of "spatial flux density." This assumes a constant, immutable rate of flow of time, which need not be true at all if we believe relativity. Such a spatial "point" intensity is actually a "line" in 4-space, and not a 4-dimensional "point" at all. Thus the spatial potential -- ϕ_3 -- is a very special case of the real spacetime potential -- ϕ_4, or charge and electromagnetic theory today is accordingly a special case of the real 4-space electromagnetism that actually exists! Note also that charge is a 4-dimensional concept.

Now mass is a spatial, 3-dimensional concept. Rigorously, mass does not exist in time -- masstime exists in time. Mass and charge are thus of differing dimensionalities!

Also, according to quantum mechanics, the charge of a particle -- e.g., of an electron -- is due to the continual flux of virtual particles given off and absorbed by the observable particle of mass. Thus charge also is conceptually a measure of the virtual flux density, and directly related to ϕ. Further, since the charge exists in time, it is the charge of a particle of spatial mass that gives it the property of masstime, or existing in time.

Here a great confusion and fundamental error has been thrown into the present EM theory by the equating of "charge" and "charged mass." As we have seen, the two things are really very different indeed.

To speak of a spatial "amount" of charge erroneously limits the basic EM theory to a fixed time flowrate condition (which of course it was considered to be, prior to Einstein's development of relativity). Thus when the limited present theory encounters a "relativistic" case (where the time flowrate changes), all sorts of extraordinary corrections must be introduced. The real problem, of course, is with the fundamental definitions of electrostatic potential and charge. The spatial "amount" of charge (i.e. the coulomb) as we presently erroneously use the term, is actually the spatial amount of observable "charged mass." To correct the theory, one must introduce the true 4-space SEP and separate the definitions of charge and charged mass.

Only when a mass is moved does one have work -- and voltage or vector fields. (The reason one has voltage and E field connected to a normal electrostatically charged object in the laboratory is because an excess of charged-particle masses are assembled on the object, and these masses are in violent motion! A true static charge would have no E field at all.)

Table 1. Some Present Theoretical Facts

- $Ø_3$-FIELD CONCEIVED BEFORE RELATIVITY
    - POINT FUNCTION IN SPACE
    - LINE FUNCTION IN SPACETIME
    - TIME FLOWRATE CONSIDERED IMMUTABLE
    - SPECIAL CASE OF $Ø_4, \ldots\ldots, Ø_N$
- GRADIENT BETWEEN TWO POINTS IN $Ø_3$ FIELD
    - PRODUCES VOLTAGE
    - PRODUCES E FIELD
    - MOVES ELECTRON
    - IS AN AREA IN 4-SPACE
- GRADIENT MAY BE BETWEEN SEPARATED POINTS IN TWO SUPERPOSED Ø-FIELDS
- Ø-FIELD CAN "MOVE" AT INFINITE VELOCITY*

* JACKSON, CLASSICAL ELECTRODYNAMICS, 2ND EDITION, P. 223

Table 2. Some Proposed $\emptyset_4$ Characteristics



- SPATIOTEMPORAL $\emptyset_4$ FIELD
  - STRESS ON SPACETIME
  - CAN CHANGE RATE OF FLOW OF TIME
- GRADIENT BETWEEN 2 POINTS IN $\emptyset_4$ FIELD
  - PRODUCES COMPLEX V_4
  - WILL MOVE ELECTRON IF
    - $V_3 \neq 0$, AND
    - $\nu_1 = \nu_2 = c$
  - WILL NOT MOVE ELECTRON IF
    - $V_3 = 0$, OR
    - $\nu_1 \neq \nu_2$
- GRADIENT MAY BE BETWEEN SEPARATED POINTS IN TWO SUPERPOSED $\emptyset_4$ FIELDS
- $\emptyset_4$ WAVE MOVES AT $0 \leq \nu_4 \leq \infty$
- $\emptyset_4$ WAVE IS COMPLEX AND LONGITUDINAL

ϕ-field need not involve observable mass accumulation, but only charge (virtual flowrate intensity) accumulation. Accumulated masses are like so many gallons of water; accumulated charge is like so much pressure on both the water (space) and the time in which the water is existing.

Now, if one varies the SEP solely as a point function, one would have a purely scalar complex longitudinal wave, and not a vector wave at all. This is the fundamentally new electrical wave that Tesla discovered in 1899.

Rigorously, all vector fields are two-point functions and thus decomposable into two scalar fields, as Whittaker showed in 1903. It follows that any vector wave can be decomposed into two scalar waves. By implication, therefore, a normal transverse EM vector wave, e.g., must simply be two coupled scalar (Tesla) waves -- and these scalars independently would be longitudinal if uncoupled. An ordinary transverse EM vector wave is thus two pair-coupled Tesla scalar longitudinal waves, and only a single special case of the much more fundamental electromagnetics discovered by Nikola Tesla.

A Tesla (scalar potential) wave -- i.e., a massless wave in pure ϕ_0, the stress of the spacetime medium would have very strange characteristics indeed. For one thing, since it moves in a complex 4-space, it has many more modes of movement than does a simple wave in 3-space. And for another thing, it need not be bound at all by the speed of (vector) light. In current theory, one ϕ_3-field does not directly interact or couple with other existing ϕ_3-fields except by simple superposition. Therefore presently the ϕ-field is considered to have no drag limitation at all, hence infinite velocity. (E.g., as stated in Jackson, Classical Electrodynamics, 2nd edition, page 223.)

Actually, a ϕ_4-wave can and will interact with some of the other existing ϕ_4-waves in the medium transversed, and this interaction can involve pair-coupling into EM vector fields and waves, an interaction not presently in the electrodynamics theory. The result of scalar pair-coupling creates a finite amount of vector "drag" on the ϕ_4-wave, so it then has less than infinite velocity. However, if this drag is small due to limited pair-coupling, the scalar wave's velocity through the slightly dragging medium still may be far greater than the speed of vector EM waves (light) in vacuum. On the other hand, if the pair-coupling is made severe, the ϕ-wave may move at a speed considerably below the speed of vector light waves in vacuum. The velocity of the ϕ_4-wave is thus both variable and controllable or adjustable (e.g., simply by varying its initial amplitude, which through a given medium changes the percentage of pair-coupling and hence the degree of drag on the scalar wave). The Tesla scalar wave thus can have either subluminal or superluminal velocity, in contradiction to present theory.

Note that the scalar wave also violates one of Einstein's fundamental postulates -- for the speed of our "new kind of light" wave is not limited to c, and need not be the same to every observer. Thus Tesla scalar waves lead to a new "superrelativity" of which the present Einstein relativity is only a highly special case!

Table 3. Tesla Waves Can:

- **ESTABLISH STANDING WAVES**
    - **- in the earth**
    - **- in the ionosphere**
- **TAP ENERGY FROM THE EARTH'S CORE**
- **TRAVEL FASTER OR SLOWER THAN LIGHT**
- **CHANGE RATE OF TIME FLOW**
- **AFFECT ALL FIELDS, INCLUDING GRAVITY**
- **COMMUTE BETWEEN VIRTUAL AND OBSERVABLE**



Figure 1. Tesla's Standing Columnar Wave

But let us now look for some subtle but real examples of scalar waves and scalar pair-coupling in nature. As is well known, a tectonic fault zone can provide anomalous lights, sounds, etc. from stresses, piezoelectrical activity, and telluric currents in the earth and through the fault zone. In examining the fault zone phenomena, I finally realized that a fault zone was literally a scalar interferometer i.e., if one can have scalar ϕ_4-waves, they can interfere, either constructively or destructively. Their interference, however, produces scalar pair-coupling into vector EM waves. This coupling may be at a distance from the interferometer itself, and thus the interferometer can produce energy directly at a distance, without vector transmission through the intervening space. Coupling of ϕ waves with the paired scalars comprising ordinary EM vector waves can also occur. If this triplex coupling forms additional EM vector waves 180 degrees out of phase, the ordinary EM wave is diminished or extinguished. If the scalar triplex coupling occurs so as to create vector EM waves in phase with the interacting vector EM wave, the amplitude of the ordinary vector wave is increased.

Scalar potential waves can thus augment or diminish, or create or destroy, ordinary EM waves at a distance by pair-coupling interference under appropriate conditions, and this is in consonance with the implications of Whittaker's fundamental 1903 work.


V_2
V_1
ΔL
ΔT
T_1
T_2

ALL VECTORS AND VECTOR FIELDS ARE CREATED BY SCALAR INTERFEROMETRY AND PAIR COUPLING

EM COUPLING CONDITION

$$\Delta L/c = \Delta T$$

Figure 2. Pair Coupling: Producing EM at a Distance


ϕ_1
ϕ_2
STRESS RELIEVED
STRESS
STRESS
QUARTZ-BEARING ROCK

LOCKED-IN STRESSED CRACKS

EACH TINY STRESSED CRACK ACTS AS A SCALAR INTERFEROMETER

BECOMES A PRIGOGINE CRYSTAL

Figure 3. Natural Scalar Interferometers

An earthquake fault zone is such a scalar interferometer. Stresses and charge pileups exist in the plates on each side adjacent to the fault, with stress relief existing in the middle in the fault fracture itself. Since the rock is locally nonlinear, the mechanical stresses and electrical currents in it are also locally nonlinear. This results in the generation of multiple frequencies of ϕ_4-waves from each side of the fault interferometer, yielding two complex Fourier expansion patterns of scalar potential waves. On occasion these two Fourier-transformed scalar wave patterns couple at a distance to produce stable ordinary electromagnetic field in a 3-dimensional spatial pattern -- e.g., a stress light such as the Vestigia light covered in Part I of The Excalibur Briefing. Driven by the erratic two scalar Fourier expansion patterns of the scalar interferometer (whose input stresses normally slowly change), an erratic, darting, hovering "spooklight" of the variety studied by Vestigia is produced.

As the stresses change in each side of the interferometer, the distant scalar coupling zone is affected. Thus the stresslight moves and its form changes, but it may be relatively stable in form for seconds or minutes. Since the stresses in the rock may be intense, the stress light may involve an intense pair of ϕ-patterns coupling into the sphere or ball of vector EM energy. The atoms and molecules of the air in the region of the coupled stresslight ball thus become highly excited, giving off radiant energy as the excited states decay.

Since much of the piezoelectric material in the stressed rocks is quartz grains, the features of quartz are of particular interest. Each little quartz grain is itself highly stressed, and has stress cracks. It is therefore a little scalar interferometer. Further, quartz is transparent to infrared and ultraviolet; and the random orientation of all the quartz scalar interferometers may also form a Prigogine system far from thermodynamic equilibrium. If so, this system can tap into highly energetic microscopic electromagnetic fluctuations to produce large-scale, ordered, relatively stable patterns of electromagnetic energy at a distance.

In short, all of this lends support to the formation of relatively stable but somewhat erratic patterns of electromagnetic energy at a distance from the fault itself. In the atmosphere, such scalar interferometers could form in clouds or even in the air or between clouds and earth. If so, such rare but occasional "weather" scalar interferometers could account for the rare phenomenon of ball lightning. The intense energy of the ball of lightning, as compared to the lesser energy of an earthstress light, could well be due to the enormous electrical charges between clouds or between cloud and earth, available to fuel the scalar interferometer. Very probably it is this phenomenon which gave Tesla the clue to scalar wave interferometry.

Thus such phenomena as earthstress lights, ball lightning, and the Tesla system of wireless transmission of energy at a distance with negligible losses and at speeds exceeding the speed of light may be explained. They are complex, however, and involve fundamental changes to present electromagnetic theory. These changes include utilizing 4-space scalar electrostatic potentials, scalar waves, pair coupling, ordinary 3-dimensional Fourier expansion, the Prigogine effect, and the properties of piezoelectric materials in rocks.

Since the scalar potential also stresses time, it can change the rate of flow of time itself. Thus it affects anything which exists in time -- including the mind, both of the individual and at various levels of unconsciousness. Therefore the same functions that result in earthstress lights also affect mind and thought, and are in turn affected by mind and thought. This is the missing ingredient in Persinger's theory that UFO's are correlated with, and a result of, fault zones and earth stresses. While Persinger seems to feel this is a "normal physics" explanation, it indeed involves a paranormal explanation.

The time-stressing ability of the true ϕ scalar wave also explains the interaction of such earthstress lights with humans and human intent, as noted by other researchers. (E.g., the lights that repeatedly seemed to react to the observers, as detailed by Dr. Harley Rutledge in his epoch-making Project Identification, Prentice-Hall, 1981.)

These ideas in condensed form comprise the concepts required to violate the speed of light and produce an ordinary electromagnetic field at a distance, using scalar interferometry, without losses -- as Tesla had done in his wireless transmission system which he had tested prior to 1900 and had perfected by the 1930's. Scalar interferometry can give stable regions of EM or "light energy" at a distance without losses, particularly as detailed in the beautiful Vestigia experiments, and it is within our grasp to utilize the new effects. Indeed, any stress crack in a material can result in the scalar potential interferometer effect. Exophoton and exoelectron emission -- poorly understood but already known in fatiguing of materials -- must be at least partly due to the scalar interferometer effect.

However, one additional caution should be advanced. Normal movement of electrons allows so much "sideplay" movement of the electrons -- and there is so much such sideplay electron motion in the surrounding vicinity -- that pair coupling is almost instantaneous for small waves. Thus orbital electrons in atoms seem to absorb and emit vector EM photons. Actually they also emit some percentage of scalar waves as well. Since a scalar wave is comprised exclusively of disturbance in the virtual state, it need not obey the conservation of energy law. Further, a scalar wave of itself does not "push electrons" or other charges; hence it is nearly indetectable by present detectors. Ionization detectors such as a Geiger counter tube, e.g., are exceptions if the scalar wave encountered is fairly strong. In that case sufficient triplex coupling with the ionized gas occurs to produce additional ionization or charge, breaching the tube's cutoff threshold and producing a cascade discharge of electrons and voltage which is detected. But weak scalar waves are presently indetectable by ordinary instruments. However, these small scalar waves are detectable by sensitive interferometry techniques e.g., such as an electron interferometer. Since the use of such instruments is quite rare, then indeed we have been living immersed in a sea of scalar waves without knowing it.

Finally, the percentage of scalar waves produced by changes in charged mass pileups can be increased by utilizing charged mass streaming. Essentially the charged masses must be moved suddenly, as quickly as possible, at or near the complete breakdown of the medium. For this reason, Tesla utilized sparkgaps in his early transmission systems, but also found that he could induce ionized media to "breakdown" in such fashion by a slow growth process. One of his early patented atmospheric wireless transmission systems is based on this fact. However, it was necessary to use a very high voltage, insuring extreme stress on the medium and hence some spillover stress onto time itself. In other words, ϕ_3 is always an approximation; at sufficiently high spatial stress, sufficient spillover ϕ_4 exists to give Tesla scalar waves. For this reason, Tesla used very high voltages and extremely sharp discharges to give "streaming" of the charged masses and thus high percentages of ϕ_4 waves. This suggests that the breakdown of dielectrics is a much richer phenomenon than is presently allowed for in the conventional theory.

To summarize, electrostatic potential -- ϕ-field is stress on the spacetime medium at a four-dimensional point. I. e. , it is a sort of pressure on the medium, but pressure on all four dimensions, not just on the three spatial dimensions. Thus in the new standard theory, ϕ_4 may have complex values. In addition, a ϕ-wave is to be interpreted as a scalar longitudinal wave in complex spacetime -- directly in ϕ_0, the normal average 4-space stress itself. And charge and charged mass must be recognized as two separate concepts. This is the gist of what I finally recognized about Nikola Tesla's work and fundamental discovery.

This is exciting, for it means that Tesla stress waves can affect either space or time individually, or both space and time simultaneously, or even oscillate back and forth between primarily affecting time and primarily affecting space, Tesla's waves were actually these ϕ-field scalar waves. As such, they were fundamentally different from ordinary electromagnetic waves, and had entirely different characteristics, just as Tesla often stated. E. g., a Tesla wave can either move spatially, with time flowing linearly; move temporally only (sitting at a point and waxing and waning in magnitude -- but changing the rate of flow of time itself in doing so, and affecting gravitational field, fundamental constants of nature, etc,), or move in a combination of the two modes. In the latter case, the Tesla wave moves in space with a very strange motion -- it oscillates between (1) spatially standing still and flexing time, and (2) moving smoothly in space while time flows smoothly and evenly. I.e., It stands at one point (or at one columnar region), flexing for a moment; then slowly picks up spatial velocity until it is moving smoothly through space; then slows down again to a "standing column," etc. This is Tesla's fabulous "standing columnar wave."


−∞
DIRAC SEA
PRIGOGINE
TUNNEL
+∞
0⁻
0⁺
TEMPERATURE
β EMITTER IN
PRIGOGINE CONDITION
e⁻
e⁻
DIRAC SEA
NEGATIVE ENERGY

Figure 4. Exoelectric Emission


TESLA ANGLE
ENERGY FLOW
STANDING WAVE
TRANSMITTED EARTH SIGNAL
KINDLING
EARTH
MOLTEN CORE
MANTLE
ENERGY FLOW
ENERGY FLOW
COHERENT TRANSMITTED SIGNALS
KINDLING
MOLTEN CORE
EARTH
MANTLE
TRANSMITTED SIGNAL
COHERENT
STANDING WAVE COLLECTOR
KINDLED ENERGY
MOLTEN CORE OF THE EARTH

TESLA EFFECT, TYPE 1

TESLA EFFECT, TYPE 2

TESLA EFFECT: TRIODE OPERATION

Figure 5. The Tesla Effect

Another wild characteristic of the Tesla wave is that it can affect the rate of flow of time itself; hence it can affect or change every other field including the gravitational field -- that exists in time flow. It can also affect all universal constants, the mass of an object, the inertia of a body, and the mind and thoughts as well! All of these exist in the flow of time, and they are affected if the time stream in which they exist is affected. This was the awful secret that Tesla partially discovered by 1900, and which he came more and more to fully realize as he pursued its nature and its ramifications into the 1920's and 1930's.

Tesla also found he could set up standing ϕ-field waves through the earth. He in fact intended to do so, for he had also discovered that all charges in the highly stressed earth regions in which such a standing wave existed produced ϕ-fields which would feed (kindle) energy into the standing ϕ-field wave by pair coupling. I.e., normal vector field energy would "assemble" onto the scalar matrix wave by means of pair-coupling. Thus by transmitting a scalar standing wave into the earth, he could easily tap the fiery scalar fields produced in the molten core of the planet itself, turning them into ordinary electromagnetic energy. In such case, a single generator would enable anyone to put up a simple antenna and extract all the free energy desired.

When Tesla's alarmed financial backers discovered this was his real intent, they considered him a dangerous madman and found it necessary to ruthlessly stop him at all costs. And so his financial support was withdrawn, he was harassed in his more subtle patent efforts (and the patents themselves were adulterated), and his name gradually was removed from all the electrical textbooks. By 1914 Tesla, who had been the greatest inventor and scientist in the world, had become essentially a nonperson.

A few other persons in the early 1900's also were aware that potential and voltage are different. And some of them even learned to utilize Tesla's ϕ-field, even though they only vaguely understood they were utilizing a fundamentally different kind of electromagnetic wave. For example, James Harris Rogers patented an undersea and underground communications system which Tesla later confirmed utilized Tesla waves. The U.S. secretly used the Rogers communications system in World War I to communicate with U.S. submarines underwater, and to communicate through the earth to the American Expeditionary Force Headquarters in Europe. The Rogers system was declassified after the War and very shortly after that, it had mysteriously been scrubbed off the face of the earth. Again, potential stress waves -- Tesla waves -- were eliminated and "buried."

Probably the most brilliant inventor and researcher into Tesla's electromagnetics was T. Henry Moray of Salt Lake City, Utah. Dr. Moray actually succeeded in tapping the limitless zero-point energy of vacuum (spacetime) itself. By 1939, Dr. Moray's amplifier contained 29 stages and its output stage produced 50 kilowatts of power from vacuum. Interestingly, another 50 kilowatts could be tapped off any other stage in the device -- which consequently could have produced almost 1.5 megawatts of electrical power! Dr. Moray's epoch-making work was suppressed also. His device -- which represented over 20 years of heartbreaking accumulation of 29 working tubes from thousands made -- was destroyed by a Soviet agent in 1939, but not before the agent had obtained the drawings for building the tubes and the device itself. Today the Moray amplifier is a standard component of many of the Soviet secret superweapons and Tesla weapons.

In the 20's and 30's, Tesla announced the final perfection of his wireless transmission of energy without losses even to interplanetary distances. In several articles (e.g., H. Winfield Secor, "Tesla Maps Our Electrical Future, " Science and Invention, Vol. XVII, No.12, pp. 1077, 1124-1126), Tesla even revealed he used longitudinal stress waves in his wireless power transmission. Quoting from the article, "Tesla upholds the startling theory formulated by him long ago, that the radio transmitters as now used, do not emit Hertz waves, as commonly believed, but waves of sound." "He says that a Hertz wave would only be possible in a solid ether, but he has demonstrated already in 1897 that the ether is a gas, which can only transmit waves of sound; that is such as are propagated by alternate compressions and rarefactions of the medium in which transverse waves are absolutely impossible." The wily Tesla did not reveal, of course, that such scalar waves nearly always immediately pair-coupled into vector waves when produced by normal means. Tesla himself was working with longitudinal scalar waves.

Table 4. Rogers' Undersea and Underground Communication System

- **SECRETLY USED BY U.S. IN WWI**
- **COMMUNICATED TO SUBS UNDERWATER**
  - **ANY DEPTH, UP TO 30 KHZ**
  - **REDUCED DEPTH, >30 KHZ**
- **COMMUNICATED TO EXPEDITIONARY HQ OVERSEAS**
  - **5,000 TIMES STRONGER THAN AERIAL**
  - **STATIC-FREE**
- **DECLASSIFIED IN 1919**
  - **TO REVOLUTIONIZE COMMUNICATIONS**
  - **TO END ALL SURFACE ANTENNAS**
- **MYSTERIOUSLY "LOST"**
- **REDISCOVERED AND "LOST" THREE TIMES AFTER WWII**

continued

BEARDEN
FER DE LANCE
12.14 15:24
BRIEFING ON SOVIET SCALAR ELECTROMAGNETIC WEAPONS

ORDER THE ALL NEW 2ND EDITION OF "FER DE LANCE"

Updated to the year 2002

Stunning new revelations about the secret scalar EM wars the media ignores

THIS BOOK IS THE ONLY SOURCE FOR THIS INFORMATION

The Tom Bearden Website



Scalar Potential Interferometer

Figure 6. Multimode Tesla Weapon

In the 1930's Tesla announced other bizarre and terrible weapons: a death ray, a weapon to destroy hundreds or even thousands of aircraft at hundreds of miles range, and his ultimate weapon to end all war -- the Tesla shield, which nothing could penetrate. However, by this time no one any longer paid any real attention to the forgotten great genius. Tesla died in 1943 without ever revealing the secret of these great weapons and inventions.

Unfortunately, today in 1981 the Soviet Union has long since discovered and weaponized the Tesla scalar wave effects. Here we only have time to detail the most powerful of these frightening Tesla weapons -- which Brezhnev undoubtedly was referring to in 1975 when the Soviet side at the SALT talks suddenly suggested limiting the development of new weapons "more frightening than the mind of man had imagined." One of these weapons is the Tesla howitzer recently completed at the Saryshagan missile range and presently considered to be either a high-energy laser or a particle beam weapon, (See Aviation Week & Space Technology, July 28, 1980, p. 48 for an artist's conception.)



Aviation Week & Space Technology July 28, 1980


FOURIER TRANSFORM SECTIONS
(12 WAVELENGTHS EACH)
SCALAR ANT
SCALAR ANT
REFERENCE
CONTROL & PHASING
COMPUTER FACILITY
POWER FOR PULSE MODES
EXPLOSIVE GENERATORS BANK
POWER FOR CONTINUOUS MODES
EXTRA GENERATOR POWERS COMPUTER FACILITY
MORAY POWER UNITS

Figure 7. Tesla Weapons at Saryshagan

The Saryshagan howitzer actually is a huge Tesla scalar interferometer with four modes of operation. One continuous mode is the Tesla shield, which places a thin, impenetrable hemispherical shell of energy over a large defended area. The 3-dimensional shell is created by interfering two Fourier-expansion, 3-dimensional scalar hemispherical patterns in space so they pair-couple into a dome-like shell of intense, ordinary electromagnetic energy. The air molecules and atoms in the shell are totally ionized and thus highly excited, giving off intense, glowing light. Anything physical which hits the shell receives an enormous discharge of electrical energy and is instantly vaporized -- it goes pfft! like a bug hitting one of the electrical bug killers now so much in vogue.

If several of these hemispherical shells are concentrically stacked, even the gamma radiation and EMP from a high altitude nuclear explosion above the stack cannot penetrate all the shells due to repetitive absorption and reradiation, and scattering in the layered plasmas.

In the continuous shield mode, the Tesla interferometer is fed by a bank of Moray free energy generators, so that enormous energy is available in the shield. A diagram of the Saryshagan-type Tesla howitzer is shown in figure 7. Hal Crawford's fine drawing of the interferometer end of the Tesla howitzer is shown in figure 6. Hal's exceptional rendition of the Tesla shield produced by the howitzer is shown in figure 8.


3–D SCALAR
INTERFEROMETRY
(HEMISPHERICAL SHELL)

Figure 8. The Tesla Shield


DECOYS
WARHEAD
GAMMA RAYS
EMP
DEBRIS
SCATTERING AND ABSORPTION
SCATTERING AND ABSORPTION
SCATTERING AND ABSORPTION
HEMISPHERES
OF INTENSE
LIGHT BANDS

Figure 9. Tesla Terminal Area Defense System

In the pulse mode, a single intense 3-dimensional scalar phi-field pulse form is fired, using two truncated Fourier transforms, each involving several frequencies, to provide the proper 3-dimensional shape (Figure 10). This is why two scalar antennas separated by a baseline are required. After a time delay calculated for the particular target, a second and faster pulse form of the same shape is fired from the interferometer antennas. The second pulse overtakes the first, catching it over the target zone and pair-coupling with it to instantly form a violent EMP of ordinary vector (Hertzian) electromagnetic energy. There is thus no vector transmission loss between the howitzer and the burst. Further, the coupling time is extremely short, and the energy will appear sharply in an "electromagnetic pulse (EMP)" strikingly similar to the 2-pulsed EMP of a nuclear weapon.

This type weapon is what actually caused the mysterious flashes off the southwest coast of Africa, picked up in 1979 and 1980 by Vela satellites. The second flash, e.g., was in the infrared only, with no visible spectrum. Nuclear flashes do not do that, and neither does superlightning, meteorite strikes, meteors, etc. In addition, one of the scientists at the Arecibo Ionospheric Observatory observed a gravitational wave disturbance -- signature of the truncated Fourier pattern and the time-squeezing effect of the Tesla potential wave -- traveling toward the vicinity of the explosion.


T₀
SLOW WAVE
T₁
ΔL1
FAST WAVE
T₁
T₂
ΔL2
T₂
ΔL3
T₃

$$\frac{\Delta L_3}{c} = \Delta T_3 \Rightarrow EM_3$$

TESLA HOWITZER
(SCALAR INTERFEROMETER)

Figure 10. "Nuclear" Flashes off the Coast of Africa



Lithuania - 10 Sep 1976 - British European Airways Flight #831 between Moscow and London

CIA Report Released under FOIA

Figure 11. Continuous Tesla Fireball

The pulse mode may be fed from either Moray generators or -- if the Moray generators have suffered their anomalous "all fail" malfunction -- ordinary explosive generators. Thus the Tesla howitzer can always function in the pulse mode, but it will be limited in power if the Moray generators fail.

In the continuous mode, two continuous scalar waves are emitted -- one faster than the other -- and they pair-couple into vector energy at the region where they approach an in-phase condition. In this mode, the energy in the distant "ball" or geometric region would appear continuously and be sustained -- and this is Tesla's secret of wireless transmission of energy at a distance without any losses. It is also the secret of a "continuous fireball" weapon capable of destroying hundreds of aircraft or missiles at a distance. An example of a Soviet test of this mode of operation is shown in figure 11.

Witness to a super weapon?



Nick Downie describes the strange lurid glow that flared silently over the Hindu Kush

THE SUNDAY TIMES, 17 AUGUST 1980

(Multiple incidents in Sept., 1979)



TEHERAN, IRAN 17 JUNE 1966

SEEN FROM NEAR MEHRABAD AIRPORT

OBSERVED 4-5 MINUTES

SEEN BY 2 AIRCRAFT

CIA REPORT RELEASED UNDER FOIA

Figure 12. Tesla EMP Globe

The volume of the Tesla fireball can be vastly expanded to yield a globe which will not vaporize physical vehicles but will deliver an EMP to them to dud their electronics. A test of this mode is shown in figure 12. (See also Gwynne Roberts, "Witness to a Super Weapon?", the London Sunday Times, 17 August 1980 for several other tests of this mode at Saryshagan, seen from Afghanistan by British TV cameraman and former War Correspondent Nick Downie.)

If the Moray generators fail anomalously, then a continuous mode limited in power and range could conceivably be sustained by powering the interferometer from more conventional power-sources such as advanced magnetohydrodynamic generators.


DETECTION AND TRACKING
CONTINUOUS TESLA EMP GLOBE (DUDS ELECTRONICS)
TESLA FIREBALL (CONTINUOUS) (VAPORIZES VEHICLE)
TESLA FIREBALL (PULSE)
TESLA HOWITZER
EARTH'S SURFACE
USSR
U.S.
TESLA SHIELD

Figure 13. Tesla ABM Defenses



Figure 14. Moray/Tesla Technology: Star Wars Now

Typical strategic ABM uses of Tesla weapons are shown in figure 13. In addition, of course, smaller Tesla howitzer systems for anti-tactical ballistic missile defense of tactical troops and installations could be constituted of more conventional field missile systems using paired or triplet radars, of conventional external appearance, in a scalar interferometer mode.

With Moray generators as power sources and multiply deployed reentry vehicles with scalar antennas and transmitters, ICBM reentry systems now can become long range "blasters" of the target areas, from thousands of kilometers distance (figure 14). Literally, "Star Wars" is liberated by the Tesla technology. And in air attack, jammers and ECM aircraft now become "Tesla blasters." With the Tesla technology, emitters become primary fighting components of stunning power.

The potential peaceful implications of Tesla waves are also enormous. By utilizing the "time squeeze" effect, one can get antigravity, materialization and dematerialization, transmutation, and mindboggling medical benefits. One can also get subluminal and superluminal communication, see through the earth and through the ocean, etc. The new view of phi-field also provides a unified field theory, higher orders of reality, and a new super-relativity, but detailing these possibilities must wait for another book.

With two cerebral brain halves, the human being also has a Tesla scalar interferometer between his ears. And since the brain and nervous system processes avalanche discharges, it can produce (and detect) scalar Tesla waves to at least a limited degree. Thus a human can sometimes produce anomalous spatiotemporal effects at a distance and through time. This provides an exact mechanism for psychokinesis, levitation, psychic healing, telepathy, precognition, postcognition, remote viewing, etc. It also provides a reason why an individual can detect a "stick" on a radionics or Hieronymus machine (which processes scalar waves), when ordinary detectors detect nothing. Unfortunately there is not room to develop the implications of this human Tesla interferometry in detail, for that must wait for yet another book, presently in its initial stages, that Hal Crawford and I are writing.

Table 5. Orders of Reality

- **PHOTONS ARE**
  - **> PAIR-COUPLED SCALARS**
  - **> VELOCITY-LIMITED TO C**
  - **> CARRIERS OF T**

- **PHOTON INTERACTION**
  - **> IS UBIQUITOUS**
  - **> PRODUCES $\dot{t}$ = C**
  - **> YIELDS 1st ORDER REALITY**

- **SCALAR O WAVES**
  - **> NOT VELOCITY-LIMITED**
  - **> YIELD HIGHER ORDER REALITIES**


EXECUTIVE (METAMATRIX)
(multiple realities)
PROBLEM PARAMETERS, CONDITIONS
MATH MATRIX
SOLUTIONS
FRAMES
CONSTANTS
FORMULAE
ETC.
(single reality)

Figure 15. Implications of Tesla Potential

At the July 1981 U.S. Psychotronics Association's Annual Conference in Dayton, Ohio, I presented the first rough paper on the Tesla secret and scalar interferometry. A videotape of the presentation was made and will shortly be available. I am also scheduled to make a special presentation at the Alternate Energy Conference in Toronto, Canada in latter October, 1981. A professional, videotaped two-hour presentation on this subject is also being prepared. Wide distribution of the material through the international underground physics and technology network has already been made. This time, God willing, Tesla's secret will not be suppressed for another 80 years!

And perhaps it is not yet too late. The material has cost me (now) some 16 years of agonizing labor and nearly $100,000 of my own personal funds. No orthodox university, scientific group, foundation, or governmental agency would support such an effort, either financially or otherwise. Indeed, most ordinary journals will not even accept material on such matters. Nonetheless, the area is of overwhelming importance and I truly believe Tesla's lost secret will shortly affect the lives of every human being on earth.

Perhaps with the free and open release of Tesla's secret, the scientific and governmental bureaucracies will be. shocked awake from their slumber, and we can develop defenses before Armageddon occurs. Perhaps there is hope after all -- for even Brezhnev, in his strange July, 1975 proposal to the SALT talks, seemed to reveal a perception that a turning point in war and weaponry may have been reached, and that human imagination is incapable of dealing with the ability to totally engineer reality itself. Having tested the weapons, the Soviets must be aware that the ill-provoked oscillation of timeflow affects the minds and thoughts -- and the very lifestreams and even the collective species unconsciousnesses -- of all lifeforms on earth. They must know that these weapons are two-edged swords, and that the backlash from their use can be far more terrible to the user than was the original effect to his victim.

If we can avoid the Apocalypse, the fantastic secret of Nikola Tesla can be employed to cure and elevate man, not kill him. Tesla's discovery can eventually remove every conceivable external human limitation. If we humans ourselves can elevate our consciousness to properly utilize the Tesla electromagnetics, then Nikola Tesla -- who gave us the electrical twentieth century in the first place -- may yet give us a fantastic new future more shining and glorious than all the great scientists and sages have imagined.

References

The Tom Bearden Website

REFERENCES

1. Whittaker, E. T., Proc. Lond. Math. Soc. 1, 367 (1903).

2. Debye, P., Ann. Phvs. (Leipz.) 30, 57 (1909).

3. Bromwich, T. J. I'A. Phil. Trans. A, 220, 175 (1920); also Phil. Mag., 38, 143 (1919).

4. Laporte, O. & Uhlenbeck, G. E., Phys. Rev. 37, 1380 (1931).

5. Nisbet, A., Proc. R. Soc. London A 231, 250 (1955).

6. Essex, E. A., Am. Jour. Phys. 45, 1099 (1977).

7. Braunlich, P., Ed., Thermally Stimulated Relaxation in Solids, Springer-Verlag, New York, 1979.

8. Ratzlaff, John. T., Dr. Nikola Tesla: Selected Patent Wrappers, Volumes I, II, III, & IV, Tesla Book Company, 1580 Magnolia Avenue, Millbrae, CA 94030, 1980.

9. Ratzlaff, John T. & Anderson, Leland I., Dr. Nikola Tesla Bibliography, Ragusan Press, 936 Industrial Ave., Palo Alto, CA 94303, 1979.

10. "Tesla- 85th Birthday," N. Y. Sun, July 11, 1941. (Tesla says he could build, within three months, a plant at a cost of $2 million that would melt the engines of an approaching aircraft at a distance of thousands of miles.)

11. "Tesla Promises to Light Dark Spot on Moon. It's Part of a Scheme of His for Interplanetary Radio; Distance Means Nothing. Has 4 New Inventions. Tells of Them on 81st Birthday; 2 Nations Honor Him," N. Y. Herald Tribune, July 11, 1937.

12. O'Neill, John J., "In the Realm of Science: Tesla, who predicted radio, now looks forward to sending waves to the Moon," N. Y. Herald Tribune, Aug. 22, 1937. (Inventor hopes to use energy-transmitting device to make spot glow on the lunar surface. Theory is traced to 1897 experiments. His mechanism is to use vast natural forces, possibly cosmic rays.)

13. "Tesla, 80, Reveals New Power Device," N. Y. Times, July 11, 1936, p. 13, col. 2. (Says his wireless system of power transmission will supply the earth with energy for industry.)

14. Sparling, Earl. "Nikola Tesla, at 79, Uses Earth to Transmit Signals; Expects to have $100,000,000 Within Two Years," N. Y. World-Telegram, July 11, 1935. (Inventor tells of 'quake' in his laboratory that brought police and ambulances during experiments with mechanical oscillator.)

15. "Tesla's Controlled Earth Quakes Power Through the Earth, A Startling Discovery," N. Y. American, July 11, 1935, Section 2. (Announces the successful passage of an induction current with a varying flux through a circuit without the use of a commutator. Cosmic ray studies indicate many tenets of theory of relativity to be fallacious. Possible to convey mechanical effects to any distance.)

16. "Tesla, 79, Promises to Transmit Force -- Transmission of Energy Over World," N. Y. Times, July 11, 1935, p. 23, col. 8. (Tesla has plans to send energy over the entire world. Measurement of cosmic rays said to be 50 times greater than the speed of light, demolishing the theory of relativity.)

17. Tesla, Nikola, "Expanding Sun Will Explode Some Day, Tesla Predicts," N. Y. Herald-Tribune, Aug. 18, 1935. (Present literature on cosmic rays is erroneous. Some cosmic rays reach speeds 50 times that of light. Sun will increase in mass and energy and will ultimately explode. Tesla's view is that the condensation of primary substance is going on continuously. Finds secret of cosmic rays in the positive electrical charge of the sun. Discusses radioactive emanations.)

18. "3 Tesla Inventions -- Famous Scientist Will Tell Them. Tomorrow," N. Y. Sun, July 9, 1935. (One of the discoveries is a new way of transmitting energy, an entirely new principle, nothing like wireless. Also method of harnessing cosmic rays.)

19. Welshimer, Helen, "Dr. Tesla Visions the End of Aircraft in War," Every Week Magazine, Oct. 21, 1934, p. 3. (Claims to have created a new agent, which kills without a trace and yet pierces the thickest armor. Can destroy armies or aircraft.)

20. Tesla, Nikola. "Tesla on Power Development and Future Marvels," N. Y. World Telegram, July 24, 1934. (Source of reference is Prodigal Genius by J. J. O'Neill, p. 241. Reply to articles of June 29, July 12, and July 13, 1934. Praises Westinghouse and Insul to create the power system he had barely suggested in 1893. With regard to death ray effect, Tesla employs an agent

in which intensity does not diminish with the square of the distance.)

21. Dunlap, Orrin E., Jr., "Tesla Sees Evidence That Radio and Light Are Sound, " N. Y. Times, Apr. 8, 1934, X, p. 9, Col. 1. (Tesla points to errors of the past, explains radio as he sees it at age 77. He expects television.). (Note: Sound is a longitudinal wave -- as is the Tesla wave. Hertzian waves are transverse waves, not longitudinal.)

22. Bird, Carol, "Tremendous New Power Soon to be Unleashed," Philadelphia Public Ledger, Sep. 10, 1933, Magazine Section, p. 6. (Revolutionary power project by Tesla, who is also completing process for thought photography.) (Note: Here we have a possible clue that the same principle may be used both in Tesla's energy device and in Tesla's approach to thought photography.)

23. "Tesla 'Harnesses' Cosmic Energy," Phila. Public Ledger, Nov. 2, 1933. (A principle has been discovered to derive cosmic energy which operates the universe. Power is "everywhere present in unlimited quantities." Will eliminate the need for coal, oil, gas, or any of the common fuels.) (Note: Was Tesla referring to what we today call "zero-point energy of the vacuum"? His principle will tap it.)

24. Blakeslee, Howard W., "Discovery of Force to Surround Nations & Smash Attacker Claims of Aged Inventor - Nikola Tesla Makes Announcement on 75th Birthday -- Will Turn Plans Over to Geneva," Minneapolis Tribune, July 11, 1934. (Note: Here the inventor is referring to the "Tesla Shield.")

25. "Tesla, at 78, Bares New 'Death Beam'", N. Y. Times; July 11, 1934, p. 18, col. 1. (Invention powerful enough to destroy 10,000 airplanes at 250 miles away. Defense weapon only.)

26. Alsop, Joseph W., Jr., "Beam to Kill Army at 200 Miles Tesla's Claim on 78th Birthday," N. Y. Herald Tribune. July 11, 1934, pp. 1, 15. (Beam of force similar to death ray, involves four electrical devices. Can also be used in peacetime to transmit power over distances limited only by the curvature of the earth.) (Note: In this reference, we note that the Tesla death ray and the Tesla wireless transmission devices apparently use the same effect or basic principle. There appear to be four devices involved in an operational system.)

27. "A Giant Eye to See 'Round the World' ", Albany Telegram, Feb. 25, 1933. (Based on the mechanism of the human eye. The first two parts of Tesla's invention have been completed. Will allow man to see any part of the earth.) (Note: Similarity of binocular vision to interferometry.)

28. Tesla, Nikola. "Pioneer Radio Engineer Gives Views on Power," N. Y. Herald Tribune, Sept. 11, 1932. (Tesla says wireless waves are not electromagnetic, but sound in nature. Holds space is not curved.) (Note again that sound waves are longitudinal, as are Tesla's waves. Electromagnetic waves are transverse.)

29. "No High-Speed Limit, Says Tesla, " Literary Digest, Nov. 7, 1931, p. 28. (Speeds greater than light, deemed impossible by the Einstein theory, have been accomplished. As early as 1900 Tesla showed that power from his transmitter passed over the earth at a speed of 292,830 miles per second.) (Note: As is well known, velocity represents the rotation of an object out of the normal 3-dimensional space toward a 4th dimensional direction. The speed of light, c, represents a full orthogonal turn. A normal electromagnetic wave, being transverse oscillatory, is a priori limited to a single orthogonal turn, for that is all it possesses. It thus moves at the speed c. A longitudinal scalar wave, on the other hand, need not be so limited at all.)

30. O' Neill , J. J. "Sun Emits Super Ray, Nikola Tesla Asserts, " Brooklyn Eagle, Feb. 8, 1932, p. 4, col. 1. (Note: Logically, the sun should also emit scalar waves as well as transverse vector waves.)

31. O'Neill, J. J., "Tesla Cosmic Ray Motor May Transmit Power 'Round Earth'", Brooklyn Eagle, July 10, 1932, A, 1:4, pp. 1, 17. (Efforts by Tesla to harness cosmic rays started 25 years ago, and he now announces success in operating a motive device by means of these rays. Hopes to build a motor on a large scale.)(Note: possibly implies that all these Tesla devices for the last 25 years have been dealing with the same basic principle.)

32. "Tesla, 76, Reports His Talents at Peak," N. Y. Times, July 10, 1932, p. 19, col. 1. (New invention in tapping tremendous and unused source of energy. One invention to permit generation of all kinds of rays of almost unlimited intensity.) (Note: By scalar interferometry, electromagnetic waves of any frequency -- and hence of any "type" can be assembled by coupling the appropriate scalars together. A Hertzian wave is just two coupled Tesla scalar waves.)

33. Tesla, Nikola, "Man's Greatest Achievement," N. Y. American, July 6, 1930, p. 10. (Editorial Section). ("To create and annihilate material substance, cause it to aggregate in forms according to his desire...would place him beside his Creator and fulfill his ultimate destiny.") (Note: Here Tesla seems to be referring to controlled materialization and dematerialization of matter.)

34. Tesla, Nikola. "World System of Wireless Transmission of Energy," Telegraph & Telephone Age -- N. Y., Oct. 16, 1927, pp. 457-460.

Transmission of power without wires is not a theory, but "a fact demonstrated by Tesla." Mode of propagation of currents from transmitter has mean speed 57% greater than Hertz waves.) (Note: a faster than light, non-Hertzian type of wave is involved. The Tesla wave is not a normal Hertzian wave.)

35. Secor, H. Winfield, "The Rogers Underground Wireless, Electrical Experimenter, Mar., 1919, pp. 787-789, 832-835, 839. (Rogers system does away with aerial wires.)

36. Gernsback, Hugo, "Underground Wireless," Electrical Experimenter, Mar. 1919, p. 762. (Development of James H. Rogers. Receives messages from Europe during thunderstorm. Tesla agrees that messages are not Hertzian waves.)

37. Tesla, Nikola, "The True Wireless," Electrical Experimenter, May 1919, pp. 28-30, 61-63, 87. (Tesla says Hertz wave theory is a delusion. Signals must be from earth currents. Note again that Tesla does not like Hertzian waves, but himself has something more fundamental.)

38. Tesla, Nikola. "The Effects of Statics on Electrical Transmission," Electrical Experimenter, Jan., 1919, pp. 627, 658. (Tells of defects in Hertz waves. System devised by Tesla releases energy at infinite velocity.) (Note: electrostatic potential is already known to be able to travel at infinite velocity. See Jackson, Classical Electrodynamics, 2nd Edition, 1975, p.223. This is strong evidence that Tesla used scalar potential waves or Ø-fields.)

39. Bot tone, A., Nikola Tesla's New Wireless," Electrical Engineer, London, Dec. 24, 1909, p. 893. (Experiments conducted on Long Island have resulted in principles of transmission which are direct opposite of Hertzian wave transmission.) (Note: In other words, using uncoupled scalar waves -- Tesla waves instead of pair-coupled scalar waves -- Hertzian waves?)

40. Tesla, Nikola. "Electrical Control of the Weather Will Soon Be an Accomplished Fact," St. Louis Republic, Nov. 15, 1908, V, p. 3. (Tesla concurs in concept of electrical control of weather.)

41. Swezy, Kenneth M. , "Nikola Tesla, " Science, May 16, 1958 , pp. 1147-1158. (Electricity today is generated, transmitted, and converted to mechanical power by means of his inventions.)

42. Ramsay, Jack, "Cableless Power, " Electronics (Digest) , July 22, 1960, pp. 6, 8. (Soviet attempt at development of wireless power transmission, but a failure according to Swedish observers, and the idea having been bandied about in the U. S. since Tesla.) (Note: Establishes that the Soviets were at least trying to work with the Tesla techniques.)

43. Anderson, Leland I., "Correspondence: Sub-Surface Communications Systems," Proceedings of the I.R.E., Mar., 1961, p. 645. (Reference to subsurface or "earth current" communication systems. Pioneering work by Nikola Tesla and James H. Rogers.)

44. Rebert, Edwina, "Fireballs For Defense?", Christian Science Monitor, Feb. 7, 1962, p. 9c. (Feature article on possibility of using ball lightning as defense weapon -- may be inspired by early experiments of Tesla at Colorado Springs.)

45. Matsch, Lee and Rice, Warren, "Potential Flow Between Two Parallel Circular Disks with Partial Transmission," Journal of Applied Mechanics, Trans. ASME, Mar., 1967, Vol. 34, Series E., No.1, pp. 239-240. (Reference article -- bladeless turbines.)

46. Lagus, George W., "The Use of Ground in High-Frequency Circuits," Radio-TV Experimenter and Science and Electronics, June-July, 1969, PP. 71, 72. (Tesla gave several demonstrations of feasibility of electrifying large areas of land by ground propagation of high frequency currents.)

47. Jamison, S. L. , "Life Energy, " Probe. The Unknown, June , 1973, pp. 3,4. (Letter to editor -- report that vitamins and minerals could be impressed on the body using a Tesla coil.)

48. Jueneman, F. B. J. , "The First Law of Thermodynamics, " Industrial Research, Feb., 1974, pp. 17-18. (Nikola Tesla, at Colorado Springs in 1899, found that the earth was a large electron sink, and electrical storms generated standing wave potentials.)

49. Puharich, Andrija, "The Work of Nikola Tesla Ca. 1900 and its Relationship to Physics, Bioenergy and Healing," paper read at the International Inter-disciplinary Conference on Consciousness and Healing, Oct. 13, 1976, University of Toronto.) ,

50. Golka, Robert K. and Bass, Robert W., "Tesla's Ball Lightning Theory, a BKG-Wave, The Ransworth Effect, and the 'Hydrotron' Electrostatic-Inertial Self-Confined Plasmoid Concept." (Paper presented at the Annual Controlled Fusion Theory Conference, San Diego, California, May 4-6, 1977.)

51. Popovic, Prof. Vojin, "Research of Nikola Tesla in the Light of His Diary From Colorado Springs," 10 pp. (Diary contains details of investigations for determining nodal points in the earth as a conductor of waves. Comments on "fire globes.")

52. Curtis, George D., PhD, "An Electromagnetic Radiation Pattern Over the Ocean," Undersea Technology, Vol. 5, no.8, August 1964. Curtis reports the presence of a previously unknown weak electromagnetic radiation pattern over the ocean. When all known effects are accounted for, the anomalous pattern still remains.

53. Santilli, R. M., "Partons and Gravitation: Some Puzzling Questions," Annals of Physics, Vol. 83, No.1, March 1974, pp. 108-157. In this paper Santilli proved that one of the cornerstone assumptions of physics -- that electric field and gravitation are separate things -- is false. One is therefore left with only two alternatives: either they are totally the same thing, or they are partially the same thing. (Comment: Note that the ~4 Tesla potential provides the unifying connection.)

54. Science News, Vol. 113, No.1, January 7, 1978, p. 3. A photograph by T. Kuribayashi of the earthquake lights involved in the Matsushiro earthquake swarm (1965-1967). This is the only known photo of earthquake lights.

55. Wiedemann, C. Louis, "Results of the N.J. 'Spook Light' Study," Vestigia Newsletter, Vestigia, RD 2, Brookwood Rd., Stanhope, NJ 07874, May 1977, pp. 1-3. This article describes an ongoing Vestigia experiment in which a nocturnal light or "mystery light" was scientifically photographed in conjunction with visual sightings and instrumental recordings of data. Various later issues of the Vestigia Newsletter contain other update articles on the phenomenon.

56. Moray, T. Henry, The Sea of Energy, fifth edition, History and Biography by John E. Moray, Foreword by Tom Bearden; Cosray Research Institute, 2505 South 4th East, Salt Lake City, Utah 84115, 1978. In addition to his free-energy device, Moray also built a special radio which he used to clearly listen to Admiral Byrd at the South Pole. No static was experienced on Moray's radio, showing he was' not using ordinary electromagnetics. In addition, he built a device which he could tune to listen to persons several miles distant, so that their voices sounded as if they were immediately nearby. Both these devices were demonstrated to a visiting Russian Colonel/ PhD.

57. I. Procaccia, J. Ross, Science, 198, 716 (18 Nov 1977). Describes Prigogine's Nobel Prize-winning work on thermodynamics of nonlinear systems far from thermodynamic equilibrium. Prigogine's work shows that such a system can indeed demonstrate negentropy. Out of unrestrained disorder can and does arise order, contrary to the old thermodynamics.

58. "Persinger's 'Earthquake Lights' ...Ho-Hum," Frontiers of Science, Vol. III, No.3, March-April 1981, p. 15-16. Gives cogent and "fatal" objections to

Persinger's "earthquake light" scheme for explaining UFO's. Mentions Dr. Brian Brady's experiments obtaining fast, short electrical lights or sparks from crushing quartz-bearing granite cylinders. (Comment: Brady's experiments are certainly repeatable, so it is true that "earthstress lights" can be produced at a distance, although the piezoelectric effect alone in no way explains the production of the phenomena outside the piezoelectric crystal. The fact that UFO's occurring near a fault zone are not necessarily repeatable simply means that at least one other major factor must be involved in the production of UFOs than is involved in the production of earthstress lights. UFOs may sometimes involve scalar interferometry from a fault zone, but other causative factors must also be involved. Earthstress lights, on the other hand, need have no additional causative factors than what lies in the earth itself.)

59. Jackson, John David, Classical Electrodynamics, Second Edition, John Wiley & Sons, New York, 1975, p. 223.

60. Roberts, Gwynne, "Witness to a Super Weapon ?", The Sunday Times, London, 17 August, 1980. Article deals with a strange semicircular phenomenon seen inside the Soviet Union from Afghanistan in September, 1979 by Nick Downie, a former member of the SAS who has established a considerable reputation as a war cameraman. Downie saw the phenomenon twice, and later met an Afghan who had seen it several months before. A possibly related phenomenon is reported in Brackenbridge, M., "Unidentified Phenomenon," Marine Observer, 48: 21-22, 1978. Note the first "nuclear flash" was detected by Vela satellite on September 22, 1979 - close in time to Downie's sightings.

61. Bearden, Tom and Crawford, Hal, "Possible Soviet Test of a Tesla Weapon," Specula, Journal of the A.A.M.S., Vol. 3, No.2, April-June 1980, p. 29. See also Specula 3, 2, 30-32 by Bearden and Crawford. These reports are from CIA reports released under the Freedom of Information Act.

62. Bearden, Thomas E., The Excalibur Briefing, Strawberry Hill Press, San Francisco, 1980.

63. Muldrew, D. B., "Generation of Long-Delay Echoes," Journal of Geophysical Research, 84: 5199-5215, 1979. For anomalous long delays of electromagnetic signals in the atmosphere, Muldrew favors a rather complex interaction between signals from separate transmitters that (theoretically at least) can create a long-lived electrostatic wave that travels in the ionosphere -- a sort of natural memory device. The coded signals could then be read out much later when the proper natural conditions developed. Delays of up to 40 seconds might be possible with this "ionospheric memory."

64. Zhugzhda, Yu. D., Institute of Terrestrial Magnetism, Ionosphere and Radio Wave Propagation, "Magnetogravitational Waves in a Conducting Isothermic Atmosphere," Moscow ASTRONOMICHESKIY ZHUGZHDA, Vol. 56, No.1, 1979, pp. 74-83. Among other things, the paper indicates the possibility of transforming longitudinal waves into transverse waves in the region of a strong magnetic field.

65. Ranada, Antonio and Vazquez, Luis, "Kinks and the Heisenberg Uncertainty Principle," Physical Review D, Vol. 19, No.2, 15 January 1979, pp. 493-495. Shows that the velocity and position of the center of a kink, soliton, or solitary wave can be known with arbitrary precision, in violation of the Heisenberg uncertainty principle. (Comment: A Fourier-transformed scalar Tesla wave pattern is either a soliton or closely related to it.)

66. Don Moser, Photographs by Blair Pittman, "Big Thicket of Texas, National Geographic, Vol. 146, No.4, October 1974, pp. 504-529. The author photographed a "ghost light" or nocturnal spooklite -- i.e., an earths tress light. The photo is shown in the article.

67. Gehring, Gillian, "Actinide magnetism: an extraordinary tale," Nature, Vol. 279, 3 May 1979, pp. 16-18. Anomalous magnetic properties -- including spin orbit coupling as a large effect -- are exhibited by actinide intermetallics containing uranium. Present theory cannot explain these effects.

68. Gintsburg, M. A., Institute of Terrestrial Magnetism, the Ionosphere, and Radio-Wave Propagation, Academy of Sciences of the USSR, Astron. Zh. 51: 218-221, Jan-Feb 1974, English translation in Sov. Astron., Vol. 18, No.1, July-August 1974, pp. 128-130. Among other things, the article points out that thus far a Fourier analysis in mass electrodynamics has not been made. One property characteristic of mass electrodynamics is the existence of longitudinal electromagnetic waves in vacuo, i.e., longitudinal photons. They have not yet been discovered but theoretically they are entirely possible.

69. Burman, R., "A Photon rest mass and the propagation of longitudinal electric waves in interstellar and intergalactic space," J. Phvs. A: Math. Nucl. Gen., Vol. 6, March 1973, pp. 434-444. This paper on longitudinal electric waves in plasma may be very important. Weber may be detecting longitudinal electric waves. Proca waves can go faster or slower than c.

70. Klass, Philip J., "Anti-Satellite Laser Use Suspected," Aviation Week & Space Technology, December 8, 1975, pp. 12-13. Some details on the "laser blinding" of U. S. satellites by the Soviets. On one occasion, the satellite was blinded for 4 hours. (Comment: difficult to explain with current laser

technology, but simple to explain with Tesla scalar interferometry.)

71. "Soviets Build Directed-Energy Weapon," Aviation Week & Space Technology, July 28, 1980, pp. 57-50. Presents a background summary in Soviet particle beam weapon work, particularly the device being constructed at Saryshagan.

72. "Scientists Fail to Solve Vela Mystery," Science, Vol. 207, 1 February 1980, pp. 504-506. See also article in Science, 30 November, 1979.

73. "Satellite Evidence Shows 'Possibility' of Nuclear Test, DOD Says," Aerospace Daily, October 29, 1979, p. 286.

74. "A Flash of Light," Newsweek, November 5, 1979, pp. 64-65.

75. "Was It a Nuclear Device?", Newsweek, July 21, 1980, p. 19.

76. "A Nuclear Blast -- or 'Zoo Animals'?", Newsweek, April 7, 1980, p. 21.

77. "Diverging Views," Washington Roundup, Aviation Week & Space Technology, July 21, 1980, p. 15.

78. Klass, Philip J. , "Clandestine Nuclear Test Doubted," Aviation Week & Space Technology, August 11, 1980, pp. 67, 69, 71-72.

79. "Debate Continues on the Bomb That Wasn't," Science, Vol. 209, 1 August 1980, pp. 572-573.

80. "Navy Lab Concludes the Vela Saw a Bomb," Science, Vol. 209, 29 August, 1980, pp. 996-997.

81. Bloch, Ingram and Crater, Horace; "Lorentz-invariant potentials and the nonrelativistic limit," Am. J. Phys. 49(1), Jan. 1981, pp. 67-75. Among other things, this interesting paper points out some decidedly unusual and unfamiliar influences of the size of the scalar potential upon what is considered nonrelativistic behavior. For scalar potential energyof appreciable size relative to a particle's rest energy, ordinary Newtonian mechanics and the Schrodinger equation may be inadequate, even if v/c is small. This reference by itself is sufficient to establish that Ø-field alone can alter the flow rate of time.

82. Semon, Mark D. and Schmieg, Glenn M., "Note on the analogy between inertial and electromagnetic forces," Am. J. Phys. 49(7), July 1981, pp. 689-690. Compares physical forces in a rotating frame with electromagnetic forces in a Newtonian frame. The transverse mechanical force in a rotating

frame is associated with an induced EMF in a Newtonian frame.

83. Harlacher, Von Wolfgang M., "Bomben aus dem Hyperraun," Esotera, 4 April 1979, pp. 359-365.

TOWARD A NEW ELECTROMAGNETICS
PART III: CLARIFYING THE VECTOR CONCEPT

TABLE OF CONTENTS

Cover

List of Figures

Implications

Electrical Physics Presently Has a Mindset

It Started With Geometry and Grew

Points and Motion

Four Types of Vectors Actually Emerged

Quantum Mechanics Compounds the Problem

To Summarize Briefly

Uncharged Spatial (Massless) System Vector

Chargeless Mass System Vector

What Force Is

Force and Hertzian Waves Cannot Exist in Vacuum

Charged-Mass-System Vector

Charged Spatial (Massless) Vector

The Shadow Vector

A Scalar is a Zero Vector

Virtual and Observable Aspects

Scalars and Vectors Have Substructures

Substructures, Virtual Levels, and Hyperspaces

Notes and References

Additional Notes and References

TOWARD A NEW ELECTROMAGNETICS

PART III: CLARIFYING THE VECTOR CONCEPT

by

T. E. Bearden

© Copyright 1983

by T. E. Bearden

All rights reserved

LIST OF FIGURES

1. Uncharged spatial (massless) system vector
2. Chargeless mass system vector
3. Detection of "transverse" and longitudinal waves
4. Charged mass system vector
5. The "charge" on an electron mass consists of a flux of virtual particles on and off the mass
6. A test charge (charged mass) brought near a fixed charge (charged mass) experiences an acceleration
7. A charged mass system vector
8. Repeating the "test charge" experiment
9. Charged spatial (massless) vector
10. Removing the bare particle (mass) from a charged particle leaves the charge. The vacuum is DEFINED AS the charge
11. Assigning a spatial vector to the charged vacuum
12. A "shadow vector" ε_s
13. Substructures of a "zero resultant" spatial vector. (The substructures of two zero vectors may be vastly different)

The Tom Bearden Website

TOWARD A NEW ELECTROMAGNETICS

Part III: Clarifying the Vector Concept

© 1983 T.E. Bearden

-- IMPLICATIONS --

Some of the fundamental concepts of the new Tesla electromagnetics are presented. The new concepts have startling implications:

(1) No force or force field exists as such in vacuum.

(2) Hertzian (transverse) electromagnetic waves do not travel through the vacuum, just as Tesla stated.

(3) Forceless, massless Tesla (scalar) longitudinal waves actually transit the vacuum. Tesla called them "electrical sound waves."

(4) At present there are actually four different FUNDAMENTAL TYPES of vectorial entities in physics, erroneously confused as one and the same.

(5) Tesla longitudinal scalar waves are also "time" waves and can affect anything and everything that exists in time.

(6) The fundamental constants of nature (which exist in time) can be altered by Tesla scalar waves, which oscillate the values of the constants.

(7) Every vector and scalar has an internal substructure, which can be independently affected and changed. This allows the direct engineering of the virtual state and the vacuum itself.

(8) All observable forces (electrical, mechanical, gravitational, etc.) arise in, on, and OF the actual substructure of the "accelerating mass particle" itself, not as an "external" massless force or force field applied "to" a mass .

(9) Physical reality itself -- and the "physical laws of nature"

can be deliberately changed and engineered.

(10) All "physical reality" is totally internal to the physical changes of the mass particles of the detector system of the observer.

(11) Relativity's speed of light limitation applies only to the changes of the basic mass particles of the detecting instrument.

(12) Detection of superluminal effects cannot be accomplished by a "single stage" or "single shift " (single interaction) detector .

(13) Detection of superluminal effects is permitted by "multiple stage" or "multiple shift" interactions where the last interaction is a conventional interaction of photon vs. detector particle. (The two-slit apparatus for detection of electron diffraction is an example. First, the superluminal DeBroglie waves interact with the slits, which are "tuned" toward the electron's DeBroglie wavelength. The interaction with TWO slits produces subluminal interference effects, which then interact back upon the physical electron. The apparatus is thus an electron interferometer capable of detecting superluminal waves by a two-stage interaction).

(14) Interference is the most common first-stage superluminal interaction to accomplish "downshifting" superluminal entities to luminal or subluminal velocities. Superposition of superluminal "phase" waves (such as deBroglie waves, which individually always move faster than the speed of light) interferes the waves to create a subluminal group velocity, which may then interact with an ordinary mass particle in the detection system.

(15) Any otherwise physical vector must exist as an unzipped (segmented) or "shadow" vector in vacuum. "Radiation" of a vector EM wave from the electron gas in an antenna into vacuum results in the "choking off" of the mass of the transversely oscillating electrons in the antenna. Since the spinning electron mass is the "zipper" that makes or comprises the physical vector in the first place, this throttling of the mass flow unzips the E and B vectors, leaving whirling (massless magnetic scalar potential) segments of massless charge flux (massless electrostatic scalar potential). This unzipped whirling pattern of charge flux (scalar massless A/Ø) is what radiates into vacuum and propagates through it. This is a special kind of

scalar wave pattern, not a physical or vector wave.

(16) The spin of a charged particle is the mechanism for integrating or "zipping together" the individual virtual fragments of a shadow vector into a real (observable) vector. For "uncharged particles" such as neutrons, it is the spins of its virtual charged components. that accomplish the integration or zipping.

(17) All fundamental charged particles are constantly accelerated. There is no such thing as an "unaccelerated" particle, except as a gross average over time or length. Further, all of them are spinning.

(18) All changes to and from a physical vector or scalar system must arise in and come from its own internal substructure, which is zipped to its spinning particle of mass.

(19) All fundamental particles are charged internally. That is, they are dynamic assemblages of smaller charged particles. If the average sum of the total internal charge is essentially zero over some finite, small increment of time, the particle is externally uncharged. If the sum is not essentially zero, the particle is also externally charged.

(20) There are no static physical things in existence. In physical reality, something appears "static" only at a particular level. Upon sufficiently fine examination, it is composed of accelerating parts, and thus comprised of "fluctuations."

(21) Since (a) the basic physical (mass) vector consists of a "smeared particle," where particle and smear are inseparable, (b) the conceptual particle also is accelerated, and (c) the "smearing" is for a small increment of time and a small increment of length; then the basic constituency of "physical reality" is inseparable "force x time x length," or action. The basic "quantum" of physical change is thus comprised of action.

(22) Since to "detect" we must "stop" the action, separate or split the quantum into two pieces ("canonical" pieces) , and compare (measure) one piece by throwing away the other, then each physical observable must have a differential operator (the "separating agent") corresponding to it. This accounts for the fundamental postulate of quantum mechanics whereby every observable has a corresponding operator. Further, since what remains is totally relative to what was split out and thrown away, physical change

is totally "relative." This accounts for the fact that observed reality is relative, each part to each other.

(23) As a special case, we may assume that we can evaluate a physical change at a point (without length). If so, when we discard length, the remaining basic vector is momentum. This approximation holds only so long as the system to which it is applied essentially does not change over the quantal fragment of length discarded -- i.e., it holds for the linear case. Conservation of momentum, then, is violated when sufficient nonlinearity in length is present.

(24) As a second special case, we may assume that we can evaluate a physical change in a spatial manner (without time). If so, when we discard time, the remaining basic vector is energy (has the units of energy or work). This approximation holds only so long as the system to which it is applied essentially does not change over the quantal fragment of time discarded -- i.e., it holds for the linear case. Conservation of energy, then, is violated when sufficient nonlinearity in time is present. Since a "virtual change" a priori is defined as a total nonlinearity in the observer's quantal time increment but not outside it, then virtual interactions can and do violate conservation of energy within that time increment, but not out of it -- so long as the time interval itself is considered linear. If the time interval is sufficiently nonlinear, then the virtual change may result in violation of the conservation of energy externally to the time increment. In that case, an "observable change" results .

(25) As a third special case, we may assume that we can evaluate the "instantaneous value" of a physical change at a static point in space. To do so, we must discard both time (to be instantaneous) and length (to be at a spatial point), and the remaining basic vector is force. This approximation holds only so long as the system to which it is applied essentially does not change over the quantal fragment of time or the quantal fragment of length discarded. Conservation of force, then, is violated when sufficient nonlinearity in time or length is present.

(26) A new conservation of energy law is required, one which unites the present conservation of energy law with an altered form of the conservation of charge law. Briefly, the total equivalent of mass,

observable energy, and massless charge (anenergy) is conserved.

(27) All AL and At fragments are produced and destroyed one at a time, in the action fissioning of a single quantum of action (detection process). Each ∇L and ∇t is discretized but not quantized. Since quanta do not superpose, the "external universe" is continually created and destroyed in the detector's mass system, one quantum at a time, at a very high rate. This interpretation gives physical meaning to the creation and annihilation operators of quantum mechanics.

(28) Since the detecting mass system is itself continually created and destroyed one quantum at a time, ultimately all is mind changes, and only mind changes. The observer's life, mind, and being transcend all materialistic interpretations of reality -- as indeed does the very fact of the "existence" of a perceived external universe.

Next Page

TOWARD A NEW ELECTROMAGNETICS
PART III: CLARIFYING THE VECTOR CONCEPT

-- Electrical Physics Presently Has a Mindset --

In examining the foundations of geometry, mechanics, and electromagnetics, it becomes strikingly clear that substantial -- even grave theoretical errors were made early on and perpetuated into the existing theory. These errors are now so firmly entrenched that they form a part of the "mindset" of almost all physicists, engineers, and scientists.

So ingrained are these errors and inconsistencies that the orthodox scientist/theoretician finds it almost impossible to break out of them.

The present mindset is analogous to the Newtonian mindset which so fiercely resisted the new ideas of relativity, shortly after the turn of the century. However, after a few scientists formulated the rules and theory of the "relativity mathematics game," a new generation of students, not yet so firmly engrained in the Newtonian mindset, could grasp the new relativity when their teachers expounded it.

In this short series of papers[1],[2] I will roughly outline where the founders of mechanics and electromagnetics went wrong, and indicate the way to correct the fundamental errors. In addition, I will briefly point out some of the implications, and speak of some direct experimental proof.

Next Page

TOWARD A NEW ELECTROMAGNETICS
PART III: CLARIFYING THE VECTOR CONCEPT

NOTES AND REFERENCES

1. Bearden, T. E., "Comments on the New Tesla Electromagnetics: Part I: Discrepancies in the Present EM Theory;" "Part II: The Secret of Electrical Free Energy," Tesla Book Company, 1580 Magnolia Ave., Millbrae, CA 94030, 1982.

2. Bearden, T. E., "Solutions to Tesla's Secrets and the Soviet Tesla Weapons," Tesla Book Co., 1981. Also Ratzlaff , John T., "Reference Articles for Solutions to Tesla's Secrets," Tesla Book Co., 1982.

3. Note we are applying the rule, "A thing is that which it does, and it does that which it is." Actually this is one statement of a fourth fundamental law of logic not incorporated by Aristotle. See Bearden, "A Conditional Criterion for Identity, Leading to a Fourth Law of Logic," DTIS report, available through the National Technical Information System, Port Royal Road, Springfield, VA 22161.

4. Specifically, the resulting theory becomes a curtailed, special case of the much more fundamental electrodynamics and electromagnetics that actually exist .

5. We point out here that measuring a field of force existing in the electron gas in a probe of the measuring instrument is not at all the same thing as measuring a force in the vacuum, nor does it establish that a force exists in vacuum. Indeed, it is already well known that the FIELD concept itself will not withstand rigorous logical examination. For a discussion rather clearly showing the present difficulty in defining a field, see Robert Bruce Lindsay and Henry Margenau, Foundations of Physics, Dover Publications, New York, 1963, pp. 283-287. Note particularly on p. 283 that a "field of force" at any point is actually DEFINED only for the case when a unit mass is present at that point. It is then illogically ASSUMED that the force

continues to exist at the point in the ABSENCE of the mass, which of course need not follow at all. On p. 284, note the similar logical paradox connected with the idea of a scalar gravitational potential field. The potential (field) is only defined at a point when mass is present at that point, .and it is specifically defined as the potential energy per unit mass for a particle present at that point. IF THERE IS NO MASS PRESENT, NEITHER A FORCE VECTOR FIELD NOR A SCALAR POTENTIAL FIELD IS DEFINED THERE. ASSIGNMENT OF THESE FIELDS TO THE POINT IN THE ABSENCE OF THE MASS IS AN ASSUMPTION, NOT AT ALL A DEFINITION. SINCE A TRUE DEFINITION IS AN IDENTITY, THEN THE ENTITY IDENTIFIED (DEFINED) TO INCLUDE THE PRESENCE OF MASS IS NOT IDENTICAL TO THE ENTITY RESULTING WHEN THAT MASS IS ABSENTED.

To see just how arbitrary and postulational are present. "definitions" of mass and force, see Lindsay and Margenau, op. cit., pp. 84-101. Also see Richard P. Feynman, Robert B. Leighton, and Matthew Sands, The Feynman Lectures on Physics, Addison-Wesley, New York, Vol.1,. 1963, Fourth Printing July 1966, p.2-4 for a definition of the electric field in the context of its POTENTIALITY for producing a force. Again, the force only exists when a particle of mass is present. From these examples, one can see the implication that A PHYSICAL FIELD IS SOMETHING SUCH THAT, WHEN A MASS IS INTRODUCED INTO IT, THE MASS EXHIBITS AN EFFECT. For a "force field," this is tantamount to stating that there exists some mechanism connected with a field which, in the presence of a mass causes a force to be exhibited. In that case the force is an EFFECT, not a cause, and there is a more fundamental mechanism that GENERATES FORCE ITSELF. See also field discussions in Feynman, Richard, The Character of Physical Law, M.I.T. Press, Cambridge, MA, March 1967, 2nd printing September 1967, passim.

6. While in Europe prior to 1881, Albert Abraham Michelson performed his first interferometer experiments to determine the velocity of the earth through the ether, obtaining essentially null results. At the Case School of Applied Science in Cleveland,

Ohio, he perfected his interferometer experiment from 1883 to 1887, assisted by a colleague, chemist Edward Williams Morley. By 1887 the results were ready and announced. Michelson himself thought his experiment had proven Stokes' theory of an ether dragged along by the earth in motion, and thus motionless with respect to the earth. This was at odds, however, with certain other experiments indicating a moving ether. The Michelson-Morley experiment was finally reconciled with these other experiments by Fitzgerald's suggestion in 1892 that the physical dimensions of material bodies are altered when they are in motion. In 1907 Michelson was awarded the Nobel prize, the first American to receive it in the sciences.

7. See Lindsay and Margenau, Foundations of Physics, 1963, pp. 324-326; D. C. Miller, "The Ether Drift Experiment and the Determination of the Absolute Motion of the Earth," Reviews of Modern Physics, Vol. 5, p. 203, 1933. Actually the experiments did not yield a conclusively null result, but rather showed large systematic trends. For a typical elimination of the systematic trends, see Handschy, M. A., "Re-examination of the 1887 Michelson-Morley experiment," American Journal of Physics, Vol. 50, No. 11, Nov. 1982, pp. 987-990. See Rho Sigma, Ether-Technology, CSA Printing & Bindery, Lakemont Georgia, 30552, 1977 for several enlightening points on the vacuum ether: See A. K. Lapkovskii, "Relativistic Kinematic Equations and the Theory of Continuous Media," Soviet Physics Journal, Vol. 21., No. 6, June 1978 for an abstract describing Soviet utilization of the concept of a small particle (called by Bearden a quiton, in Quiton/Perceptron Physics, DTIS, 1973) of the medium. See Belyaev, B. N. , "On Random Fluctuations of the Velocity of Light in Vacuum," Azvestiya Vysshikh Uchebnykh Zavedenii, Fizika, No. 11, Nov. 1980, pp. 37-42, translation by Plenum, for discussion of the proven variation of the speed of light in vacuum; the velocity of light in a vacuum on earth is measured to be higher than the velocity of light in the vacuum of deep space. See Graham, G. M. & Lahoz, D. G., "Observation of static electromagnetic angular momentum in vacuo," Nature, Vol. 285, 15 May 1980, pp. 154-155 for the first direct observation of free electromagnetic angular

momentum in vacuum. See Davies, Paul, "Something for nothing," New Scientist, 27 May 1982, pp. 580-582 for a discussion showing that modern theories of the vacuum reveal that even empty space is seething with activity; an ether of sorts emerges from vacuum fluctuations due to quantum mechanics considerations. See Hooper, William J., "All-Electric Motional Electric Field Generator," U. S. Patent No. 3,610,971, October 5, 1971 for a generator which produces a gravitational or inertial field. Einstein suggested that vacuum, complete with electromagnetic and gravitational fields, be called the ether. Dirac certainly did not abandon an ether, for in 1954 he stated "The aetherless basis of physical theory may have reached the end of its capabilities and we see in the aether a new hope for the future." James Clerk Maxwell derived his famous equations based on an ether theory. Sir Arthur Eddington also believed firmly in an ether. Sir Oliver Lodge actually pointed out the dilemma which yields the approach in this paper: writing of the ether in his book, The Ether of Space, Harper & Bros., New York, 1909, he stated: "We have no means of getting hold of the ether mechanically; we cannot grip it or move it in the ordinary way: we can only get it electrically. We are straining the ether when we charge a body with electricity; it tries to recover, it has the power of recoil.. . . "But when electrical theory was being founded, scientists thought of space as something rather fixed, and FILLED WITH a thin material ether. They did not realize that space itself does not exist except after an observation; before the observation, spacetime exists -- indefinite in both length and time. They did not know that electrostatic scalar potential in fact was spacetime, hence also the vacuum and the ether. In assuming that the charge of vacuum is zero and that charge and charged mass are identical, they hid the answer to the dilemma and placed the foundations of electromagnetics on its present unsound basis.

8. The field, of course, is indeed a highly useful concept and this author certainly does not recommend its abandonment. Instead, he recommends that it be placed on a sounder logical basis.

9. Specifically, they came to feel that the "electric

field" which was improperly defined -- was what was waving.

10. In fact Einstein once proposed that the vacuum, complete with its electromagnetic and gravitational fields, should be called the ether. His proposal was not adopted. (See Born, Max, Einstein's Theory of Relativity, Revised Edition, Dover Publications, New York, 1965, p. 224.)

11. Particularly from the work of Schrodinger, Born, Dirac and others.

12. For example, see Lindsay and Marge. nau, op. cit., pp. 287-288. A physical vector is thought to be defined by its magnitude, its direction in space, and its transformation characteristics. Actually that is a geometrical vector, not a physical vector. It does not tell us WHAT A VECTOR CONSISTS OF, but only tells us some of its important characteristics. Remember that a true definition must be an identity.

13. Here a reading of Lindsay and Margenau, op. cit., pp. 79-81 may prove enlightening. Also note that velocity, or L/T considered "at an instant" (stopped), represents an idea of "motionless motion" and is an application of the fourth law of logic. For a discussion of the fourth law of logic and its usage, see Bearden, Thomas E., "A Conditional Criterion for Identity, Leading to a Fourth Law of Logic," Specula, Journal of the A.A.M.S., P.O. Box 1182, Huntsville, AL 35807, combined Vol. 3, No. 4/Vol. 4, No. 3, Oct 1980 - Mar 1981, pp. 50-57 (also available from Defense Technical Information Service).

14. Note this is an identity of opposites, which explicitly violates the three Aristotlean laws of logic. See Bearden, "A Conditional Criterion for Identity, Leading to a Fourth Law of Logic," loc. cit., 1981.

15. Again note the fourth law of logic: zero motion (the absence of motion) being recognized as a special case of the presence of motion. Also, physical reality consists of internested levels, and any physical object has an internal substructure of nested levels of finer structure, extending down into the virtual (nonobserved) state. For a vector to model (apply to) a

physical object, it itself must be modeled in such fashion as to reflect this kind of substructure. Thus the use of geometrical vectors as models of physical objects in motion is presently flawed in a fundamental fashion.

16. The reader is most strongly urged to read Morris Kline, Mathematics: The Loss of Certainty, Oxford University Press, New York, 1980 as a prelude to understanding what mathematics is and is not, and what it does and does not.

17. Refer to Lindsay & Margenau, op. cit., pp. 79-81 to see how the ideas of motion and vector are inextricably entangled with the idea of a particle.

18. Call it uncertainty or call it constituency; a quantum change is composed of two canonical entities inextricably welded together into a single entity.

19. Time is an unavoidable, nonexclusive constituency of the welded quantum.

20. Simply from the definition of force as CONSISTING OF a time- and length-smeared mass motion change.

21. The force is an effect, not a cause. It IS the smeared charged particle. It is CAUSED by a more fundamental mechanism. It is the result of the combination of (1) a nonzero del phi, and (2) the presence of a spinning charged particle. IN A DEL PHI, THE SPINNING CHARGED PARTICLE ACCELERATES ITSELF! This is the fundamental secret of free energy that was suppressed, to bury the fundamental work of Nikola Tesla, shortly after Tesla was forced to abort his Wardenclyffe attempt to provide the world with free energy.

22. To quote: "The Hertz wave theory of wireless transmission may be kept up for a while, but I do not hesitate to say that in a short time it will be recognized as one of the most remarkable and inexplicable aberrations of the scientific mind which has ever been recorded in history. " Nikola Tesla, "The True Wireless, " Electrical Experimenter, May 1919, p. 87.

23. De Beauregard, O. Costa, "Running backwards the Mermin device: Causality in EPR correlations," American Journal of Physics, Vol. 51, No. 6, June 1983, p. 515.

24. Note the Soviet scientist Kozyrev's experiments with time waves. See Kozyrev, N. A., "Possibility of Experimental Study of the Properties of Time," September 1967, pp. 1-49, in JPRS 45238, May 1968. Kozyrev reports real physical effects from the oscillation of time. Also, note that scalar potential energy of appreciable size with respect to a particle's rest energy can force the situation to be relativistic, even though the velocity of the particle with respect to the velocity of light is small. That is, electrostatic scalar potential alone can cause variation in the rate of flow of time and hence vary physical characteristics. See Bloch & Crater, "Lorentz-invariant potentials and the non-relativistic limit," American Journal of Physics, Vol. 49, No.1, 1981, pp. 67-75. By inference, oscillating the electrostatic scalar potential can produce time waves and lead to direct physical effects.

25. It is already shown in the literature that the electrostatic scalar potential (ESP) can affect spacetime (ST) in the same manner as velocity. Cf Bloch & Crater, op. cit., 1981. Now note that, to any quantal or macroscopic observer, the existence of the 4-space volume of ST implicit in $(\Delta t)(\Delta v)$, where v is volume, cannot be separated from the existence of the subquantal entities that exist therein. We therefore DEFINE the magnitude of the ESP as the summation of the absolute values of all the internal virtual vectors in the $(\Delta t)(\Delta v)$ quantum of ST, divided by the absolute value (magnitude) of $(\Delta t)(\Delta v)$. We take the view that no such thing as "unstressed" ST physically exists, and that "spacetime" and "stressed spacetime" are identical. Hence ESP and ST are one and the same thing. Note that this implies that the virtual density of ST is variable, and is nothing but the magnitude of the ESP. In EM theory, the assumption that the ESP of vacuum ($Ø_O$) is equal to zero is in serious error. In fact, $Ø_O$ IS "spacetime of the laboratory observer," in the new view.

26. For example, the definition of the electrostatic

potential (ESP) is usually taken as "the work which must be done against electric forces to bring a unit charge from a reference point to the point in question; the reference point is located at an infinite distance, or, for practical purposes, at the surface of the earth or some other large conductor." (McGraw-Hill Dictionary of. Scientific and Technical Terms, ed. Daniel N. Lapedes, second edition, 1978, p. 518.) Note that this is NOT a definition at all, for it is not an identity. Instead, it is the statement that, if an ESP exists at a point and a unit charged mass (assumed to be at a point) is brought in from infinity toward the ESP location point, the amount of work it is necessary to expend upon the mass of the particle is equal to the magnitude of the ESP. The ESP exists whether or not any work at all is expended, and whether or not a charged unit mass is brought in. To adequately define ESP, we must define its identity, or what it consists of, in the absence of mass, since we have conceived the ESP to exist at a vacuum point. Further, the definition usually taken is completely a 3-space definition. Instead, in our new view the ESP is to be taken at a point in n-space, where n is equal to or greater than 4.

27. See Bearden, Quiton/Perceptron Physics, 1973, available through the DTIS. See also Bearden, The Excalibur Briefing, Strawberry Hill Press, San Francisco, CA, 1980. Ultimately all physical phenomena are mindchanges in the minds of all the observers.

28. And then assumes this summation value is zero.

29. See note 25 above.

30. Bearden, The Excalibur Briefing, Strawberry Hill Press, San
Francisco, CA, 1980.

31. Cf Rauscher, E. A., "Electromagnetic and Non-Linear Phenomena in Complex Minkowski Spaces," Tecnic Research Laboratories, 64 Santa Margarita, San Leandro, CA 94579. Presented at the 1983 March Meeting of The American Physical Society in Los Angeles, CA 21-25 March, 1983. This is a truly remarkable paper of great significance. Rauscher, a world-class physicist, has presented a new theoretical

model for some rather extraordinary possible extensions of present electromagnetics.

32. Cf Muses, Charles, Introduction to Jerome Rothstein's Communication, Organization, and Science, The Falcon's Wing Press, Indian Hills, Colorado, 1958. The entire foreword by Muses is a remarkable document, which analyzes the structure of time itself. See also his profound summary paper, "Hypernumbers II" in the January 1978 issue of Applied Mathematics and Computation, published by Elsevier.

Next Page

TOWARD A NEW ELECTROMAGNETICS PART III: CLARIFYING THE VECTOR CONCEPT

Help support the work

ADDITIONAL NOTES AND REFERENCES

Although quotes and direct utilization of material from these references were not incorporated in this paper, the following references were also consulted. In addition,' several notes are added for further clarity.

33. Rupert Sheldrake, A New Science of Life: The Hypothesis of Formative Causation, J. P. Tarcher, Inc., Los Angeles, CA, 1981. Ø, the electrostatic scalar potential field, in my opinion is actually the morphogenetic field that Sheldrake proposes.

34. Briefly, by a "particle" we mean an entity so constructed that, if any part of it changes all of it changes. From the viewpoint of the particle, this implies that to change is to detect, and to detect is to change. Also, internal and external become synonymous, in the "detected" sense. The idea of a "fundamental particle" in physics actually invokes the fourth law of logic implicitly.

35. Only if a thing dimensionally contains time, can it "occupy time." This point is so obvious that one wonders how so many of the scientists and mathematicians seem to have missed it. By this criterion, e.g., mass does not exist in time, a priori. To "observe" or detect, in fact, means to stop time, thus collapsing the wave function. However, it reduces the observable or detectable to a spatial quantity, not a spatiotemporal quantity. In other words, the ordinary scientific method destroys a part of reality in each detection or measurement, yielding only a partial truth. not fundamental truth.

36. Note that electrostatic scalar potential is actually infinite-dimensional and hyperspatial. The coverage of

this paper is still only a special case. By Tesla technology, it is possible to do direct engineering in hyperspace -- beyond our present space and time, with all that that statement implies.

37. Bob Sloan, "Nikola Tesla: The Greatest Inventor of all Time?". IEEE Antennas and Propagation Society Newsletter, June 1983, pp. 9-11. A very succinct summary of the importance Tesla played in ushering in the modern age.

38. Gerald E. Brown and Mannque Rho, "The structure of the nucleon," Physics Today, Vol. 36, No.2, February 1983, pp. 24-32. Recommended as a summary of the new thinking as to the structure of the nucleon: a bag containing three quarks, surrounded by a cloud of mesons which squeeze the bag.

39. John J. O'Neill. Prodigal Genius: The Life of Nikola Tesla. Angriff Press, P.O. Box 2726, Hollywood, CA 90028, new printing 1981.

40. Margaret Cheney, Tesla: Man Out of Time, Prentice-Hall, Englewood Cliffs, NJ, 1981.

41. John T. Ratzlaff and Leland I. Anderson. Dr. Nikola Tesla Bibliography. Palo Alto. CA, 1979. Indispensable.

42. Dr. Nikola Tesla: Selected Patent Wrappers, compiled by John T. Ratzlaff, multiple volumes. 1980. Available from The Tesla Book Company, 1580 Magnolia, Millbrae, CA 94030. Tesla's correspondence with the U.S. Patent Office, when patiently trying to obtain patents. He spent a great deal of time trying to convince the Patent Office that his inventions would indeed work. Some of them required 12 years to obtain, and then were "watered down" in the process.

43. Thomas Commerford Martin, The Inventions, Researches and Writings of Nikola Tesla, Originally published in 1894 by The Electrical Engineer, New York; republished in 1977 by Omni Publications, Hawthorne, CA 90250.

44. Ernest Nagel and James R. Newman, Godel's

Proof, New York University Press, 1958.

45. Yakov P. Terletskii, Paradoxes.in the Theory of Relativity, With a Foreword by Banesh Hoffman, translated from the Russian, Plenum Press, New York, 1968. Of particular interest is the discussion on particles with imaginary masses, moving faster than the speed of light, contained in pp. 104-107. Such particles can in principle be experimentally detected. In fact, it would appear that the well known exchange of virtual particles between two other particles, such that each turns into the other, is such a case. (Note that protons and neutrons in the nuclei of atoms do precisely this.)

46. Robert M. Besancon, Ed., The Encyclopedia of Physics, Second Edition, Van Nostran Reinhold, New York, 1974. Particularly see the discussion on the electron, pp. 272-274. Note this discussion predates Stanford University's experiments yielding fractional charge, though it does point out that several physicists had also reported measuring fractional charges on the electron. See also the discussions of ionization, Michelson-Morley experiment, the photon, and propagation of electromagnetic waves.

47. Robert Eisberg and Robert Resnick, Quantum Physics of Atoms, Molecules, Solids, Nuclei, and Particles, John Wiley & Sons, New York, 1974.

48. R. K. Bullough and P. J. Caudrey, eds., Solitons, Springer-Verlag, New York, 1980.

49. James Dale Barry, Ball Lightning and Bead Lightning, Plenum Press, New York, 1980. Note particularly p.196, for a short discussion on flashless discharges. An extensive bibliography is also included.

50. Harley D. Rutledge, Project Identification, The First Scientific Field Study of UFO Phenomena, Prentice-Hall Inc., Englewood Cliffs, NJ, 1981.

51. John J. Reitz, Frederick J. Milford, and Robert W. Christy, Foundations of Electromagnetic Theory, Third Edition, Addison-Wesley, Reading, MA, 1979.

52. The entire series of handbooks by William Corliss, dealing with anomalies and unusual natural phenomena

of all kinds. Corliss is a national treasure, and his handbooks are absolutely indispensable.
See particularly his Handbook of Unusual Natural Phenomena, The Sourcebook Project, Box 107, Glen Arm, MD 21057, 1977 and his Lightning, Auroras, Nocturnal Lights, and Related Luminous Phenomena, 1982.

53. Bernard d'Espagnat, Conceptual Foundations of Quantum Mechanics, W. A. Benjamin, Menlo Park, CA, 1971.

54. D.W.G. Ballentyne and D.R. Lovett, A Dictionary of Named Effects and Laws in Chemistry, Physics and Mathematics, Fourth Edition, Chapman and Hall, New York, 1980. Check this neat little book to discover some very odd effects in materials.

55. David Bohm, The Special Theory of Relativity, W. A. Benjamin, New York, 1965.

56. Albert Einstein, Relativity: The Special and the General Theory, Crown Publishers, New York, 1961. See particularly the discussion of relativity and the problem of space, in Appendix V.

57. Edwin F. Taylor and John Archibald Wheeler, Spacetime Physics, W. H. Freeman and Co., San Francisco, 1966. Note particularly the discussion on observers and frames in the first two dozen pages. On p.19, note that the notion of a frame requires an infinite observer distributed through each and every "point" that was clock-synchronized in a frame. Since all observers are localized, a better idea is to realize that all the "external" modeling just represents the relative changes inside the physical detection system of the observer himself/herself. All detection/observation is totally inside the physical observer.

58. Paul Edwards, Ed. in Chief, The Encyclopedia of Philosophy, Vols. 1-8, Macmillan Publishing Co., New York, 1967.

59. Michael A. Persinger and Gyslaine F. Lafreniere, Space-Time Transients and Unusual Events, Nelson-Hall, Chicago, IL, 1977.

60. John David Jackson, Classical Electrodynamics, Second Edition, John Wiley & Sons, New York, 1975.

61. James Clerk Maxwell, A Treatise On Electricity & Magnetism, Vols. 1 & 2, Third Edition, Dover Publications, New York, 1954. An unabridged, slightly altered, republication of the third edition, originally published by the Clarendon Press in 1891.

62. Jack S. Greenberg and Walter Greiner, "Search for the sparking of the vacuum," Physics Today, August 1982, pp. 24-32. A beautiful summary article on the present concept of the vacuum, from the standpoint of quantum mechanics and quantum field theory. I specifically urge anyone interested in tapping the vacuum energy to read this article.

63. Max Jammer, Concepts of Mass, Harvard University Press, Cambridge, MA, 1961. Recipient of the monograph prize of the American Academy of Arts and Sciences for the year 1960 in the field of physical and biological sciences. This book, strange as it may seem, was the first monograph to subject the notion of mass to an integrated and coherent historical investigation, something which had never before been done. The reading of this book is an absolute must for anyone seriously concerned about whether or not science speaks fundamental truth, or to what degree it does so. Most scientists assume foundations concepts such as "field," "force," "mass," "time," etc. are well-defined and well-understood in physics, since they are ubiquitous and so familiar. In fact, none of the absolute fundamentals in the foundations of physics is unambiguously understood!

The last paragraph by Jammer is illuminating: "The modern physicist may rightfully be proud of his spectacular achievements in science and technology. However, he should always be aware that the foundations of his imposing edifice, the basic notions of his discipline, such as the concept of mass, are entangled with serious uncertainties and perplexing difficulties that have as yet not been resolved."

64. G. Burniston Brown, "Gravitational and inertial mass," American Journal of Physics, Vol. 28, p. 475, 1960: "...one of the most astonishing features of the

history of physics is the confusion which surrounds the definition of the key term in dynamics, mass."

65. Whittaker, Sir Edmund, A History of the Theories of Aether and Electricity, Vol. 1: The Classical Theories, and Vol. 2: The Modern Theories 1900-1926, Harper Torchbooks, Harper & Brothers, New York, 1960.

66. Weyl, Hermann, Space -- Time -- Matter, Fourth Edition, translated from the German by Henry L. Brose, Dover Publications, New York, 1922.

67. Jammer, Max, Concepts of Space: The History of Theories of space in Physics, Second Edition, Foreword by Albert Einstein, Harvard Univ. Press, Cambridge, MA, 1969.

TOWARD A NEW ELECTROMAGNETICS PART III: CLARIFYING THE VECTOR CONCEPT

Help support the work

-- It Started With Geometry and Grew --

At the very beginning of what we call the "scientific period," mathematics was both king and queen, and Euclidean geometry was its handmaiden. So we ask, "What precisely is geometry?" Here we are not interested in a "textbook" answer, but in an answer indicating what geometry really does.[3] In other words, with what does geometry concern itself, and what is the fundamental nature of those things with which it concerns itself?

Briefly, geometry -- at its foundation -- is totally spatial. It is fitted to, and expressed in terms of, the TOTAL ABSENCE OF MASS. Thus the geometer deals in abstract, massless entities called "points," "lines," "planes" etc. When the geometer speaks of "motion," he speaks of a time-smeared, length-smeared point. Geometry at heart is massless, and a "geometer's vector" is a highly specific type of "system." In fact, it represents the "time-smearing" and "length-smearing" of a point. A priori, the fundamental concept of the geometrical vector has taken a "spatial" entity and introduced a hidden involvement with "time."

Modern mathematics and physics have followed an intertwined development for several hundred years. And both sprang as offshoots of the original work of the geometers. Let us briefly sketch the overall path of interest taken by these two developing disciplines.

With the advent of Descartes's fundamental work, algebra was combined with geometry to yield analytic geometry, a new and powerful mathematical tool. With the invention of calculus by Leibniz and Newton, both mathematics and physics received a giant impetus. Differential geometry and vector mathematics arose in full splendor and, in physics, mechanics leaped to the forefront with Newton's profound work.

But the mechanics made a most fundamental error when they simply applied the geometer's vector to a mass, to produce -- so they thought -- a mass vector. That which rigorously applies only to the absence of mass cannot be so lightly applied to the presence of mass without the risk of serious limitations in the resulting theory. The precise difference between a geometer's massless vector and a mechanic's mass-vector is one of the issues to be developed in this thesis.

As rapid development continued in mechanics and mathematics, certain physicists were involved in intense experimental work on charged matter, becoming the first electricians. Both the preceding mathematical ideas and constructs as well as the preceding (partially erroneous) mechanics constructs and ideas were applied by the electricians, struggling with their pith balls, cat fur, and glass rods to understand, quantify, and model electrical forces and the phenomena of charged matter. In other words, the electricians strove to formulate the physics and dynamics of charged matter and its interactions by simply "adding to" the work of the geometers and mechanics. Here again, a fundamental logical error was made. That (geometry) which a priori applies only to the absence of mass, and that (mechanics) which a priori applies only to the absence of charge, cannot be lightly applied to the presence of charged mass (both mass and charge)[4] without risking the incorporation of grave limitations in the resulting theory.

After the profound work of Maxwell, the idea of FIELDS OF FORCE became more prominent, until the field concept ruled the day[5]. The electricians continued, pushing the idea of fields into space and vacuum itself, along the way inventing the idea of "charge effects" existing even in the massless vacuum, with concomitant fields. Meanwhile, they had thoroughly confused chargeless point-smeared, chargeless mass-smeared, length-smeared and time-smeared vectors.

After a set of fundamental experiments designed to detect motion of the material ether yielded essentially null results[6], Michelson and Morley were regarded as having completely disposed of the ether -- even though the experiments only disposed of material ethers, and not Lorentz-invariant non-material ethers[7]. Maxwell's equations and the field concept were elevated to profound importance.[8] Then, after Einstein's fundamental relativity work shortly after the turn of the century, the ether concept faded away and the field concept reigned supreme. Indeed, in their enthusiasm the interpreters of relativity went so far as to affirm that one can have a wave without any medium; that is. that something can be moving (waving) without anything there to move![9] And with great glee they pronounced the final end to the idea of "ether" as a medium, even though Einstein himself never did any such thing.[10] With the advent of Einstein's General Theory of Relativity, even matter came to be regarded as just a special "kink" or curvature in spacetime or "vacuum nothing."

Quantum mechanics arose and even certainty and determination fell. Chaos, probability, and randomness now assumed the ruling position. Probability waves (and probability fields) arose,[11] as did quantum fields of various kinds. The intermingling of these concepts with the concepts of electrodynamics pushed the idea of the field even farther into esoteric realms.

The point is, each of these developing disciplines incorporated and built on the foregoing disciplines. From the beginning of geometry, there was no rigorous definition of a vector, and there is none today.[12] From the beginning of mechanics, in their foundations the theorists made grave logical errors by incorporating the geometer's vector; errors so great that today mechanics and electromagnetics are severely flawed, as is everything that came after them and built upon their illogical foundations.

Next Page

Help support the work

TOWARD A NEW ELECTROMAGNETICS PART III: CLARIFYING THE VECTOR CONCEPT

Help support the work

-- Points and Motion --

It is my purpose in this paper to expose in a very simple fashion the most basic errors that were made. One basic error involves the idea of motion itself.[13]

In formulating concepts of motion, the geometers used a "point in motion" to determine or specify, for example, velocity. Now a "point" is a static concept a priori. To determine (or even to think and perceive) motion, one must determine that it occupies two different points (positions or locations) at two different times, yet consider both points at the same time. Indeed, that is precisely what the arrow means that is used to represent a vector. A "point in motion" therefore represents a contradiction of opposites. That is, it represents the idea that "that which is motionless has motion.".[14] Even with this, there is a difference in a spatial point and a spatiotemporal (spacetime) point. To exist at all, a spatial point must be moving in time; in other words, it is a spatiotemporal line, even if it is a static spatial point.

Vector analysis was constructed in the abstract -- again, a massless point in motion possessed or constituted a velocity vector, etc. In massless (and timeless) space, FIELDS were defined: "scalar" fields constituted the assignment of a simple motionless number (magnitude) to each spatial point, while "vector" fields constituted the assignment of a "simple vector" (magnitude and velocity) to each spatial point. But the MATHEMATICAL vector system consisted of massless (point) motional relationships, recognizing zero motion as a special case of motion.[15]

Of course mathematics development was also always intertwined with practical problems. With the sustained application of mathematics to gross physical material problems, mechanics slowly arose.

These developments required decades and even centuries to occur completely. All along the way, innovations and changes -- and additions to the mathematical formulism were being derived and taught to students as the "natural" system of reality. A permanent mindset was being forged.

Indeed, mathematics was regarded as THE single human expression of fundamental truth. Not until Godel's work in the twentieth century did it become evident that MATHEMATICS IS SIMPLY A GAME PLAYED ACCORDING TO ASSIGNED RULES, AND THERE IS NO ULTIMATE TRUTH IN MATHEMATICS ALONE.[16] It is a most useful game, of course, since it is the game fitted to perception. Thus it applies, essentially, to whatever can be perceived. But to be applied to physical systems, it must be changed, altered, updated, and fitted as the perceiving/detecting instruments become ever more subtle.

Next Page

Help support the work

TOWARD A NEW ELECTROMAGNETICS
PART III: CLARIFYING THE VECTOR CONCEPT

-- Four Types of Vectors Actually Emerged --

As the physical sciences slowly developed and incorporated abstract geometry and mathematics, in actuality four major types of vectors and two major states of observation evolved, although this fact did not become apparent to the scientists. Specifically, the mathematicians and scientists failed to recognize the differences in the four types of vectors, hopelessly intermingling them and confusing them as a single class of vector. Further, they did not appreciate that a fundamental vector conceptually is a UNITARY SYSTEM, and the system represented by one of these four types of vectors utilizes and is comprised of different components, "welded together with no seam in the middle."

Conceptually (and from a systems viewpoint), the four types of vectors are (1) the chargeless, massless spatial system vector (geometer's vector), (2) the uncharged mass system vector (mechanic's vector), (3) the charged mass system vector (electrician's vector), and (4) the charged space system vector (advanced electrician's vector). These four fundamentally different vectors are shown in Figures 1, 2, 4, and 9 in a simplified manner.

The major problem was that, beginning with the geometer's vector, these four major types of vectors were not treated as systems. Instead, their "vector" aspects were hopelessly confused and intermeshed, and no distinctions were made between them. And in the foundations of the mathematical constructs, time-smearing was not recognized at all.

Next Page

TOWARD A NEW ELECTROMAGNETICS
PART III: CLARIFYING THE VECTOR CONCEPT

-- Quantum Mechanics Compounds the Problem --

In addition, the two presently recognized observation states -- observable and nonobservable (virtual) -- were of course unknown to the early geometers and electricians, and these ideas were not incorporated directly into the theoretical foundation.

From particle physics and quantum mechanics, we now understand that physical reality is structured of an observable state, underlaid with an infinite number of ever finer, successive levels of virtual (unobservable) states. At least reality is most accurately modeled in that fashion, according to particle physics today.

It is also well known, for example, that at the most fundamental level, one cannot actually separate nonmotion from motion (which implies, for example, that one cannot separate mass and velocity). In other words, a "mass in motion" idea is actually incorrect, at the most basic level. What actually exists is a sort of "smeared mass". That is, "mass-motion" is fundamentally what exists, not mass IN motion .

Actually, all that the Heisenberg Uncertainty Principle implies is this fact: If one examines the concept of "static (non-smeared) thing in non-static (smeared) motion", in ever finer detail, one reaches a degree of fineness where the "smearing" is paramount and one cannot have an un-smeared or "separate static thing" to be in motion. Instead, one only has the smeared, 4-dimensional spacetime entity, without 3-dimensional spatial separations.

This means, for example, that at the most basic level, it is actually incorrect to represent a momentum with a little static particle of mass connected to a spatial velocity vector. It is incorrect to think of the system as comprised of TWO SEPARATE ENTITIES, (1) a mass, and (2) a massless spatial system velocity vector (a geometer's vector).

We mention in passing that, presently, we understand that every particle is continually accelerating. First, the particle has spin, which involves rotation, which means that every "part" of the periphery of the particle is accelerated toward the center axis of spin. Second, every particle is continuously "fluctuating," and these fluctuations are accelerations. Further, we must consider any change such as an acceleration -- as existing in a small time increment, and occurring in a small length increment. Thus mass particles actually exist as (mass x acceleration x time x length). This of course has the dimensions of ACTION or angular momentum. The "real" world of physical matter, then, is composed of building blocks of action, called "quanta." Any other physical "quantity" must be obtained by fissioning (differentiating) the action quantum. For this reason, quantum mechanics presently must postulate that to every observable there corresponds an operator.

Next Page

-- To Summarize Briefly --

Let us now summarize these concepts and further examine their impact.

In physics, there must actually exist four major KINDS of vectors, rather than just one as prescribed by present interpretation. These vectors are "built" starting with four major kinds of particles.[17] These are: (1) the spatial point, (2) an uncharged mass particle, (3) a charged mass particle, and (4) a charged spatial point. Further, each of the four vectors at its most fundamental level (that is, at the quantum level)[18] is actually an inseparable, unitary SYSTEM welded into a single undivided entity containing time and existing nonexclusively in time.[19] When we look at or represent the so-called "parts" of the system, we are looking at them before they are welded together into the physical vector. That is, whenever we speak of "parts, " we imply that a "cutting" or "differentiating" action has been implied to separate the system into such "parts."

From such considerations, four different kinds of system vectors result.

Next Page

Help Support the Work

TOWARD A NEW ELECTROMAGNETICS
PART III: CLARIFYING THE VECTOR CONCEPT



(GEOMETER'S VECTOR)

Figure 1. Uncharged spatial (massless) system vector.

UNCHARGED SPATIAL (MASSLESS) SYSTEM VECTOR
-- (Figure 1) --

This is the geometer's abstract vector, consisting of a "point in motion." (Actually, it is a "smeared point," for example.) However, so ingrained is the concept of a "point in motion" velocity vector that we now consider it to be "natural" because of its total familiarity. But simply ask, "WHAT is in motion?"[17] and you immediately see the difficulty. To have a WHAT, one must "stop the action" (detect or measure), separating "static" from "non-static." Acceleration and other vectors, etc. have also been derived by the geometer and utilized in similar fashion. All are massless.

Next Page

TOWARD A NEW ELECTROMAGNETICS
PART III: CLARIFYING THE VECTOR CONCEPT



(MECHANIC'S VECTOR)

Figure 2. Chargeless mass system vector.

CHARGELESS MASS SYSTEM VECTOR
-- (Figure 2) --

This type of vector actually is the essential vector of mechanics, involving mass-motion (momentum), force (mass-motion change), etc. The fundamental difference between this type of vector and the geometer's vector is the presence of smeared mass existing in time (i.e., mass-time), welded together with a geometer's vector, but with no seam in the middle, into a new kind of "vector" AS A SYSTEM. The vector is the SYSTEM EXISTING IN TIME .

To illustrate:

"Momentum" is more properly referred to as "mass-motion" rather than "mass in motion." That is, at the fundamental level, the mass is NOT "separate" from its motion. It is NOT separated from the time in which the smearing occurs. The idea of momentum, however, is really to express the time-density of the mass-smeared-through-length. It is, in other words, the time rate of length-smearing of mass. Now in our minds we have conceived that

$$\bar{p} = m \odot \bar{v} \qquad (1)$$

where, by the symbol $\odot$ we mean "coupled to"; but we actually have

$$\bar{p} \equiv [\overline{m\bar{v}}] \qquad (2)$$

where we are not allowed to separate (even in thought) m and $\bar{v}$. Quantum mechanics agrees with this essentially, because $\bar{p}$ is a canonical variable linked to length, in any observable physical change. (The REASON p is canonically linked to ΔL is because $\bar{p}$ is the time-rate of length-smearing of m. If there is no length, there is no length-smearing of m to have a time rate OF in the first place.)

Note that, not only is

$$\bar{p} = [\overline{m\bar{v}}] \qquad (3)$$

but also

$$\bar{p} \equiv [\overline{m\bar{v}}] \qquad (4)$$

which is a much stronger and quite different statement. That is, $\bar{p}$ is IDENTICALLY $(\overline{mv})$, not just calculably EQUAL TO (m)($\bar{v}$). This means that $\bar{p}$ is a SYSTEM that is COMPRISED of mass-motion.

Next Page

TOWARD A NEW ELECTROMAGNETICS
PART III: CLARIFYING THE VECTOR CONCEPT

-- What Force Is --

We now note that force, for example, is -- and may be defined as -- the time-rate of change of momentum, or

$$\bar{F} \equiv d/dt[\bar{p}] \qquad (5)$$

and this identity states that a force -- any force is COMPRISED OF time-changing "mass-motion." As such, the force vector is a mass-system vector, not just a massless spatial vector. Fundamentally, this mass-system vector is a totally different creature from a massless spatial vector. Our present manner of considering force as a geometer's vector "separately applied to" a mass particle is completely erroneous at the quantum level. Instead, fundamentally force is always a mechanic's vector. Force is an EFFECT, not a CAUSE.

And here mechanics made a most fundamental error, in not recognizing the difference between its kind of vector and that of the geometer.

Next Page

TOWARD A NEW ELECTROMAGNETICS
PART III: CLARIFYING THE VECTOR CONCEPT

--Force and Hertzian Waves Cannot Exist in Vacuum --

Note that one cannot have an observable "force vector" existing' in vacuum a priori.

For example, we have the definition of force as

$$\bar{F} \equiv \frac{d\bar{p}}{dt} \qquad (6)$$

or

$$\bar{F} \equiv \overline{[m\bar{a} + \dot{m}\bar{v}]} \qquad (7)$$

and we see that, rigorously, a force vector CONSISTS OF (not, "is equal to") a time-changing mass-motion vector system. IF THERE IS NO OBSERVABLE ACCELERATING MASS PRESENT, THEN THERE CAN BE NO OBSERVABLE FORCE PRESENT. The mass can accelerate in time (increase or decrease of mass) or space (increase or decrease of velocity) or both.

Observable force CANNOT exist in vacuum (in the absence of mass), a priori.[20]

However, assume for a moment that one could have a massless force vector, as assumed in present electrical theory. Let this force vector appear at a point in the vacuum. Since the vacuum has zero observable mass, it would have zero inertial resistance to this hypothetical observable force -- hence the observable force would instantly produce an "infinite" acceleration of its point of application, vanishing with it into the infinite distance. Therefore our fictitious force would disappear the instant it appeared! In any case, it could not be retained at a point in the vacuum for any finite length of time, however small.

The direct implications are that (1) something other than an observable electrical force field exists in the vacuum, and (2) there must exist a more fundamental mechanism by which this "something else" generates or CREATES a force on/of a moving electrically charged mass. (Note again that, at the most basic level, any particle of mass is always quivering, in motion, and accelerating. from quantal considerations alone.)

Thus immediately we have discovered something unique about so-called "force-fields" in vacuum: for example, about gravitational field, electrical field, and magnetic field (and the strong force and the weak force as well). These fields do not exist at all as ordinary force vectors -- and real force fields -- in vacuum! $\bar{\mathbf{E}}$ and $\bar{\mathbf{B}}$ fields, e.g., are defined in terms of force per unit electrical charged mass and magnetically charged mass, respectively. In the absence of mass, they cannot exist.

And this in turn means that transverse $\bar{\mathbf{E}}-\bar{\mathbf{H}}$ field waves (Hertzian waves) cannot exist in a vacuum. Indeed, they appear on, and ARE CONSTITUTED of, the charged-mass-motion that changes, and they appear where such change occurs, as a result of an introduced mass.[21] But in the absence of the spinning charged particle of mass, they do not exist as force fields at all.

Hertzian waves exist in a transmitting whip antenna, for example, in the oscillating electron gas along its length. Something else entirely different exists in vacuum between the transmitting antenna and the receiving antenna. Then in the receiving antenna, Hertzian waves again exist in the oscillating electron gas along its length. (See Figure 3.)


ANT
NORMAL
EM
NORMAL XMTR
"transverse"
EM wave
transverse oscillations induced in electron gas
DETECTION
(Actually a special type of scalar wave.)
ANT
NORMAL
EM
XLTR/XMTR
longitudinal
EM wave
no detection
NORMAL DETECTOR
no transverse oscillations induced
special ant
SPECIAL DETECTOR
detects

Figure 3. Detection of "transverse" and longitudinal waves

This is interesting, for Nikola Tesla stated several times that HERTZIAN WAVES CANNOT BE PRODUCED IN A VACUUM, NOR CAN THEY TRAVEL IN A VACUUM.[22]

Tesla was correct, as we are beginning to see.

We shall later return to show in what form so-called "force-fields" actually exist in vacuum.

For now, I point out that I am stating a fundamental change to all of physics, including both mechanics and electromagnetics.

Next Page

TOWARD A NEW ELECTROMAGNETICS PART III: CLARIFYING THE VECTOR CONCEPT

Help support this work



(ELECTRICIAN'S VECTOR)

Figure 4. Charged mass system vector.

-- CHARGED-MASS-SYSTEM VECTOR --
-- (Figure 4) --

The third type of vector we meet is the vector mass system where the mass is charged. First, we point out a serious error in present electromagnetic (EM) theory. That is, in present theory it is implicitly assumed that

$$\mathbf{q} \equiv \mathbf{q_m} \qquad (8)$$

In other words, "charge" and "charged mass" are erroneously assumed to be identically the same thing.

In the days when electricians were playing with pith balls and striving to uncover the secrets of electricity, they knew nothing at all about the virtual state, and consequently nothing about a "virtual particle flux" on a particle of mass causing (and comprising) the "charge" of that mass.

Today, of course, we know from particle physics and quantum mechanics that the "charge" on an observable particle of mass IS due to a flux of virtual (nonobservable) particles on and off the mass of the observable particle (see figure 5). A charged mass is thus presently known to be a SYSTEM: a massless charge flux, coupled to a bare particle (chargeless mass) constitutes a "charged particle."



Figure 5. The "charge" on an electron mass consists of a flux of virtual particles on and off the mass.

Thus, actually the "charge" is the virtual (unobservable, or SPATIO-TEMPORAL) flux to and from the observable SPATIAL particle of mass. So, rigorously,

$$\mathbf{q \not\equiv q_m} \qquad (9)$$

But instead,

$$\mathbf{q \equiv [d/dm(q_m)]} \qquad (10)$$

and this is a definition and therefore an identity. This definition alone affects all present electromagnetics theory.

To illustrate: In founding electrical theory, early scientists dealt with forces generated by charged masses (for example, charged pith balls). They later extrapolated the experimental results they obtained (or thought they obtained) with the smallest charged mass, a charged particle. In Figure 6, I show the classic situation for derivation of the idea of E-field (except we have used an electron for our test charge, rather than a pith ball).



A negatively charged test mass q_{m_2} (for example, an electron) brought into the vicinity of a fixed charged mass q_{m_1} experiences an acceleration as shown. At the quantum level, the smeared electron cannot be separated from the smearing, and it BECOMES the charged-mass-motion-changing vector $\bar{F}_{cm_2}$

Figure 6. A test charge (charged mass) brought near a fixed charge (charged mass) experiences an acceleration.

Now note that what actually happens is that the unrestrained test charge becomes a CHARGED MASS SYSTEM VECTOR (a "smeared charged mass-motion changing"). The "test charge" BECOMES a charged mass force vector; it does not have a separate geometer's vector "appear on it." What actually happens is shown in Figure 7.



Figure 7. A charged-mass-system vector.

That is, in the simplest (nonrelativistic) case, for an electron what happens is

$$\bar{F}_{cm} \equiv [\overline{q_e \odot m_e \odot \bar{a}_s}] \qquad (11)$$

and this is a DEFINITION. That is, considered instantly, the electron exists as a charged-mass electrical force CONSISTING OF/COMPRISED OF a charge flux q_e canonically coupled to a mass, with that subsystem then canonically coupled to a spatial acceleration vector, ALL AS A SINGLE ENTITY, WITHOUT ANY "SEAMS" BETWEEN ITS "PARTS." The $\bar{F}_{cm}$ IS THE ELECTRON SYSTEM ITSELF; it is NOT a "spatial vector." Rigorously, it does not exist in the absence of the smeared electron mass, a priori.

Again, in assuming this force exists in the absence of the smeared mass of the moving particle, electromagnetics theory is in serious logical error.

Referring back to Figure 6, we see that, if we repeat the experiment many times and with the test charge in many locations, we have the situation shown in Figure 8.



Figure 8. Repeating the "test charge" experiment.

It is found that, rigorously,

$$|\bar{F}_{cm}| \propto \left|\frac{q_{m_1} q_{m_2}}{r^2}\right| \qquad (12)$$

where $\bar{\mathbf{F}}_{cm}$ is a charged mass system vector. Erroneously, this has been stated one way or another as

$$|\bar{F}| \propto \left|\frac{q_1 q_2}{r^2}\right| \qquad (13)$$

where $\bar{\mathbf{F}}$ is assumed to be a spatial system vector. Further, this confusion has been carried over into the definition of the $\bar{\mathbf{E}}$-field as:

$$\bar{E}_{cm} \equiv \frac{\bar{F}_{cm}}{m_{cm}} \qquad (14)$$

In this definition, $\bar{E}$ -- which is a charged mass system vector -- has been confused as a charged spatial system vector, where $\bar{F}$ is regarded simply a spatial system vector! Actually, the definition of the $\bar{E}$-field should be

$$\bar{E}_{cm} \equiv \frac{\bar{F}_{cm}}{m_{cm}} \qquad (15)$$

where $\bar{F}_{cm}$ is a charged mass system vector. Failure to properly define the $\bar{E}$-field has caused the conception of the $\bar{E}$-field to be falsely perpetuated as existing in vacuum.

The $\bar{E}$-field is TREATED this way in present EM theory. Hence present theory falsely assumes that the observable $\bar{E}$-field can exist in vacuum.

What actually exists in space, $\bar{E}$-field-wise, is a special kind of ordered virtual state pattern in a series of spinning "scalar" fields. This virtual state pattern or "shadow vector" field will be explained later.

Note again that one cannot have a "force vector" existing in vacuum - a priori.

However, assume for a moment that one could have a massless force vector, as presently assumed. Let this force vector appear at a point in the vacuum. Since the vacuum has zero observable mass, it would have zero inertial resistance to this hypothetical observable force hence the observable force would instantly produce an "infinite" acceleration of its point of application, vanishing with it into the distance. Therefore our fictitious force would disappear the instant it appeared! In any case, it could not be retained at a point in the vacuum for any finite length of time, however small.

The direct implications are that (1) something other than an observable electrical force field exists in the vacuum, and (2) there must exist a more fundamental mechanism by which this "something else" generates or CREATES a change on/of an accelerating electrically charged mass particle. (Note again that at the basic level, any particle of mass is ALWAYS quivering and accelerating, from quantal fluctuation considerations alone.) Causality has no arrow microscopically.[23]

Next Page

Help support this work

TOWARD A NEW ELECTROMAGNETICS PART III: CLARIFYING THE VECTOR CONCEPT

Help support the work



(ADVANCED ELECTRICIAN'S VECTOR)

Figure 9. Charged spatial (massless) vector.

-- CHARGED SPATIAL (MASSLESS) VECTOR --

We recognize now that

$$q_c \not\equiv q_m \qquad (16)$$

and that q_c is simply the virtual-particle flux that constitutes charge -- and indeed constitutes vacuum itself!

We DEFINE vacuum, based on Figure 5, as shown in Figure 10.


There is no "emptiness filled with charge." Rather, there is massless charge, from which emptiness is constructed, and from which spacetime is constructed, and from which mass and motion are constructed.
Ø
Ø
Ø
Ø
Ø
Ø
Ø
Ø
e_m

Figure 10. Removing the bare particle (mass) from a charged particle leaves the charge. The vacuum is DEFINED AS the charge.

That is, vacuum may be defined as pure massless charge flux. This flux IS identically "spacetime" as well. Vacuum is pure Ø-field (electrostatic scalar potential). Here again, in present theory it is assumed that

$$Ø_O \equiv 0 \qquad (17)$$

which, by our new definition of vacuum, is quite false.

We now note that, if we insist on assigning a spatial vector to the vacuum, we have the situation shown in Figure 11.


$\bar{\varepsilon}_s$
$Ø_1$
$Ø_2$

Figure 11. Assigning a spatial vector to the charged vacuum

Next Page

Help support the work

TOWARD A NEW ELECTROMAGNETICS PART III: CLARIFYING THE VECTOR CONCEPT

Help support the work

-- THE SHADOW VECTOR --

Note that this spatial vector $\bar{\varepsilon}_s$ represents $-\overline{\nabla \phi_s}$, that is,

$$\bar{\varepsilon}_s = -\overline{\nabla \phi}_s \qquad (18)$$

but $\bar{\varepsilon}_s$ cannot be a force (mass system) vector. It can only exist as an ordered pattern in the virtual flux between two separated points of the vacuum; that is, as an ordered pattern in the virtual state. Literally, $\bar{\varepsilon}_s$ exists only as a tiny bit of order existing in great disorder.

In other words, the present EM theory is incorrect in stating that

$$\bar{E}_m = -\overline{\nabla \phi}_s \qquad (19)$$

in vacuum in the absence of an observable spinning charged particle, since

$$\bar{\varepsilon}_s \not\equiv \bar{E}_m \qquad (20)$$

The actual existence of $\bar{\varepsilon}_s$ may be visualized in terms of successive differentials of $\bar{E}_m$, broken into differentials $\bar{e}_m$ so small that, observably, each little differential's mass component m has become virtual, so that

$$\bar{e}_m \equiv \bar{e}_{vm} \qquad (21)$$

where subscript m stands for mass, subscript v for virtual, and observably

$$\bar{e}_{vm} \equiv \overline{dE}_m \qquad (22)$$

but, in the absence of a spinning charged particle,

$$\bar{E}_m \neq \int \overline{dE}_m \qquad (23)$$

since the $\bar{e}_{vm}$ components remain individually separated. That is, in macro-time a SHADOW force vector exists, made of microscopically ordered BUT UNJOINED (unintegrated) "virtual state" vector differentials of what would be an observable mass system force vector $\bar{E}_m$ if integrated.

Thus, the "$\bar{E}$-vector" $\bar{\epsilon}_s$ that exists in vacuum is a "shadow" vector as shown in figure 12.



Figure 12. A "shadow vector" $\bar{\epsilon}_s$

We say that such a previous mass system vector, broken into ordered but unjoined virtual vectors by the absenting of all mass, is a SHADOW VECTOR, and we label it with a subscript vm, to represent "virtual mass" system. To the macro observer, this is the kind of "vector" that exists in vacuuo.

Note that, observably, the shadow vector merely represents a special ordering in $\nabla\phi$. It is NOT an OBSERVABLE (mass system) vector, but it IS an ordered series of consecutive virtual vectors.

With each virtual bit vector, a virtual time exists as well, and these "virtual time bits" are also ordered consecutively (in macrotime).

I point out that any observable vector must be finite, and so it must have a finite magnitude (finite length). In the simplest case, this length ΔL is related to a Δt by

$$\Delta L = c\Delta t \qquad (24)$$

What I am saying is that ANY observable spatial vector is actually a spatiotemporal vector, and the MAGNITUDE of any vector is related to TIME (to the existence of that vector in time) at the most fundamental level. Suffice it to say that, if the fundamental quantum level (Δt) aspect of a vector is interfered with, then the MAGNITUDE of the vector is interfered with.[24] That is, if we can make a time wave, we can change or affect ANY vector's magnitude, including the magnitude of mass system vectors and charged mass system vectors. Such a "time wave" can be made easily, and it has been.

Next Page

TOWARD A NEW ELECTROMAGNETICS PART III: CLARIFYING THE VECTOR CONCEPT

Help support the work

-- A Scalar is a Zero Vector --

Now let us look at the idea of a scalar.

A "scalar" may in a general sense be considered as the sum of the "absolute values" of the individual vector components of a system of vectors whose observable resultant is zero. That is, it represents the magnitude of the internal stress of a vector system, with the absence of a single observable directionality of the system. It also follows that every scalar is actually a stressed zero vector, and every zero vector is a scalar.

Thus we have four major types of scalars related to the four types of vectors:

(a) $S_1 = |\overline{v}_s|$ (25)

(b) $S_2 = |\overline{v}_m|$ (26)

(c) $S_3 = |\overline{v}_{cm}|$ (27)

(d) $S_4 = |\overline{v}_{cs}|$ (28)

where S stands for scalar, $\overline{\mathbf{V}}$ for vector, and subscript s for spatial, m for mass, and c for charged.

For example, comparing equations (25) and (26), it can easily be seen that twice as many "point-motions" is not at all the same thing as twice as many "gram-mass-motions." The two resulting vector systems are quite different.

Next Page

TOWARD A NEW ELECTROMAGNETICS PART III: CLARIFYING THE VECTOR CONCEPT

Help support the work

-- Virtual and Observable Aspects --

We must also examine some aspects of "virtual" and "observable."

For example, we construct several spatial vector summations in Figure 13. The "resultants" of these spatial vectors are all equal. However, the actual sums, even though equal, are quite different, because their internal "stresses" (substructure forms) are quite different.



SUPERPOSITION DOES NOT ELIMINATE THE VIRTUAL SUBSTRUCTURE.

When the time aspects of the vector systems of Figure 13 are considered, one can easily understand the problem. That is, the resultant of each of these "systems" is zero, and so one can say that the vectorial "magnitude" of the system is zero since the magnitude of the resultant vector is zero. However, in each case the "action" represented by each vector element actually occurs in a finite tiny Δt. So: (1) The zero resultant must exist for a finite Δt, and (2) all the actions indicated by the system component vectors actually occur in that Δt. The absolute value of the "activity per unit time per unit volume" of such a zero-resultant system thus has physical meaning, and one may refer to this notion as the "stress" on spacetime[25], or the "electrostatic scalar potential" of the system. Note that this differs from the present definition of electrostatic scalar potential, which becomes just a special case of the more fundamental potential defined here.[26]

The derivatives of this spatiotemporal stress also have physical meaning. The time derivative is indicative of the stress on the flow of macroscopic time at a fixed spatial point, and the spatial derivative is indicative of the stress on space. Here one is confronted with the fact that what we call "space" and "time" are continually being created, directly in the physical observing/detecting apparatus itself.[27] That is, rigorously, "detected physical reality" exists totally in and of the mass-changes of the observer's mass or his detecting instruments. In the fundamental detection process itself, there is a flow of the rate of creation of spatial lengths and a flow of the rate of creation of time lengths. Indeed, to a linear observer the stress on the creation of the flow of time controls the flow of the creation of space, and the stress on the creation of the flow of space controls the flow of the creation of time. The change in the stress on 4-space (ordinary Minkowskian space-time) controls the "curvature of that spacetime" in the fifth dimension. The change in the stress on 5-space controls the "curvature of that 5-space spacetime" in 6-space, and so on. Development of these facets of the new concepts is beyond the scope of this paper.)

Next Page

TOWARD A NEW ELECTROMAGNETICS PART III: CLARIFYING THE VECTOR CONCEPT

Help support the work

-- SCALARS AND VECTORS HAVE SUBSTRUCTURES --

As can now be seen, the sum of each structure in figure 13 is observably zero. Therefore we might define the sum as a "zero spatial vector." We note, however, that it actually exists for a time Δt and is thus a spatiotemporal entity, rigorously.

If we define the internal stress action A in a region $\Delta s^3 \Delta t$ of spacetime as

$$A_{(s^3t)} \equiv \sum_{k=1}^{n} |\bar{i}_s| \qquad (29)$$

and the 4-space internal stress intensity or potential as

$$S \equiv \lim_{(\Delta s^3 \Delta t)\to 0} \left[\frac{A(s^3t)}{\Delta s^3 \Delta t} \right] \qquad (30)$$

where $\bar{i}_s$ is any internal vector in the substructure, Δs^3 is the spatial volume (about a point) containing vector $\bar{i}_s$, and Δt is the inseparable time during which these component actions occurred, then we see that, stress-wise, all the "zero-vectors" in figure 13 are quite different in their internal stresses, 4-space potentials, and internal substructures. For the five "zero sum" vectors, OBSERVABLY we have

$$\bar{0}_1 = \bar{0}_2 = \bar{0}_3 = \bar{0}_4 = \bar{0}_5 \qquad (31)$$

whether or not

$$\Delta s^3 \Delta t_m = \Delta s^3 \Delta t_n \; (m \neq n;\; 1 \leq m \leq 5;\; 1 \leq n \leq 5) \qquad (32)$$

But considering the substructures,

$$\bar{0}_m \neq \bar{0}_n \quad (1 \leq m \leq 5;\ 1 \leq n \leq 5;\ m \neq n) \qquad (33)$$

I now point out that a scalar can be regarded as a stressed zero-sum vector, where the magnitude S of the scalar represents the internal stress intensity caused by the substructure of the zero-vector.

Thus, generally,

$$S(s^n t) \equiv \lim_{\Delta s^n \Delta t \to 0} \left[\frac{\sum_{n=1}^{k} |\bar{i}_s|}{\Delta s^n \Delta t} \right] \qquad (34)$$

That is, in general any observable scalar has, consists of, and is comprised of a VIRTUAL (unobservable) substructure that is very real indeed. One must also consider the scalar as existing for some finite time Δt, (at least for the time of one quantum change), and the intensity of the virtual actions occurring in the spatiotemporal substructure of the scalar during that time Δt is proportional to the magnitude of the scalar.

Normally, the concept of a scalar -- as presently used -- makes no allowance for the scalar to exist in time, or for a virtual vector substructure, or for any patterning inside the substructure. This is equivalent to assuming that

$$A \equiv 0 \qquad (35)$$

and that all $\bar{i}_s$'s are evenly distributed. That is, from this new viewpoint, presently the mathematical theory assumes all scalars to have an equal density of virtual activity per spatiotemporal volume in its virtual substructure, and an isotropic virtual pattern distribution of an infinite number of equal virtual vectors in its 4-space substructure.[28]

In the new approach, neither of these two assumptions need hold -- though in special cases they can hold. Thus present orthodox theory is just a single special case of a more fundamental approach indicated here.

Note that, by directly affecting and changing the virtual substructures of scalars and vectors, we can directly perform virtual. state engineering, and this allows us to directly "engineer" the so-called "laws of nature" of the normal observable laboratory state and thus ENGINEER AND CHANGE PHYSICAL REALITY ITSELF.[29]

In the new approach, we can (observably) have

$$2 + 2 \neq 4 \qquad (36)$$

or

$$2 + 2 = 4 \qquad (37)$$

by the following means: In the first case (equation 36), we assume that the virtual substructures are patterned, and interact nonlinearly in such a way as to produce an extra observable. Thus we have a delta added to the normal observable scalar results of the interaction, as follows:

$$2_o + 2_o = 4_o + \Delta_{v\text{->}o} \qquad (38)$$

where subscript "o" means observable and "v" means virtual. Note that

$$\Delta_{v\text{->}o} \qquad (39)$$

indicates a delta due to virtual substructure interactions yielding an extra observable delta. This extra delta may be either scalar or vector in nature, depending on the circumstances and the particular interactions.

Note also that any vector or scalar must now be considered to HAVE, CONTAIN, and CONSIST OF an infinite substructure. And note that, similar to the scalar case, from the new viewpoint the present theory assumes each scalar (point) of the vector to have a structure similar to that of equation (34), except that now the scalars are ordered, with a linearly decreasing internal stress density per unit scalar along the line of the vector.

In the new approach, vector interaction (superposition, for example) can now violate present theory, if the two virtual substructures interact nonlinearly to produce a nonzero, observable delta. Observably (macroscopically) , this delta, again, may be either "scalar" or "vector."

This approach now becomes consistent with quantum mechanics at the foundation level.

Next Page

TOWARD A NEW ELECTROMAGNETICS PART III: CLARIFYING THE VECTOR CONCEPT

Help support the work

-- Substructures, Virtual Levels, and Hyperspaces --

In the new approach, our definitions and assumptions immediately drive us to a picture of an infinite set of nested levels of substructures in the virtual state. That is, anyone component (scalar or vector) in one level of virtual state has an infinite number of even finer virtual components, one level more subtle.

AND THAT IS WHAT PARTICLE PHYSICS AND QUANTUM MECHANICS ALREADY REVEAL ABOUT THE STRUCTURE OF PHYSICAL REALITY.

So these definitions and assumptions now provide the basis for a new vector mathematics that is in accord with, and fitted to, modern physical observations.

We have a picture such that any observable scalar or vector contains a virtual substructure (virtual level 1). Any scalar or vector in virtual level 1 also contains a finer virtual substructure, in virtual level 2. And so on ad infinitum.

Each succeedingly finer level of virtual state can be modeled as a hyperdimension (higher spatial dimension) as I pointed out in Appendix 1 to my book, The Excalibur Briefing.[30]

Thus this approach immediately ties into hyperdimensional or hyperspatial theory -- such as Elizabeth Rauscher's 8-dimensional theory[31] and C. Muses's hypernumber theory.[32]

The new definitions and assumptions are far richer than what is allowed by tensors, though there are many similarities. Muses's work, however, essentially can encompass most of these definitions and concepts, except the distinct types of vectors are not so clearly delineated in his theory (at least to my comprehension of it.) His theory does provide a nested, hyperdimensional structure of time, however, and thus allows "scalar" waves in the hyperspatial structure of time -- in other words, observably "scalar" waves in the virtual state structure of spacetime, or pure Tesla waves, or simply "time" waves.

These are the bare notes; from this approach, already new (proprietary) mechanisms and exact specifications to make scalar waves -- in essentially whatever quantity and degree desired -- appear to have been successfully accomplished by my close colleagues.

The new approach is real and it leads to a new physics. And I believe that the very beginnings of the new physics are already working on the laboratory bench.

Nikola Tesla discovered the most essential features of the new electromagnetics over eighty years ago and was simply suppressed for his efforts. Now, although it has been eighty years in the reborning, Tesla electromagnetics is once again loose in the Western world.

This time, let us hope that it fares better at the hands of orthodox science and large financial control groups than it did for Nikola Tesla.

Next Page

TOWARDS A NEW ELECTROMAGNETICS
PART 4: VECTORS AND MECHANISMS CLARIFIED

by Lt. Col. T.E. Bearden (retd.), 1983
Copyright

Title Page

Foreword

1. TOWARDS A NEW ELECTROMAGNETICS - ACKNOWLEDGEMENTS
2. OUTLINE
3. CHARACTERISTICS OF SELECTED CONCEPTS
4. QUOTE FROM NIKOLA TESLA
5. FORCE BETWEEN TWO LIKE CHARGES
6. REPETITIONS LEAD TO THE VECTOR "FIELD" CONCEPT
7. A SCALAR HAS A HIDDEN (VIRTUAL) VECTOR SUBSTRUCTURE
8. SCALAR AND VECTOR SUBSTRUCTURES
9. SUPERPOSITION DOES NOT ELIMINATE THE VIRTUAL SUBSTRUCTURE
10. PHYSICAL VECTORS
11. THE FOUR VECTORS OF PHYSICS
12. FORCE DEFINITION
13. FORCE IS AN EFFECT, NOT A CAUSE
14. FORCE AND Ë-FIELD DO NOT EXIST IN VACUUM
15. COROLLARIES
16. ENERGY IS DERIVED, NOT FUNDAMENTAL
17. EXISTENCE IN, AND PASSAGE THROUGH, TIME
18. SOME IMPLICATIONS
19. CONSERVATION OF ANENERGY (AE): (AN EXPANDED CONSERVATION LAW)
20. FREE ENERGY IS ALLOWED

21. SCALAR POTENTIAL CAN FORCE THE RELATIVISTIC CASE
22. SCALAR STRESS WAVE (Ö-WAVE) (TESLA WAVE)
23. SCALAR Ö-WAVE PRODUCTION
24. A SIMPLIFIED CHARGED PARTICLE
25. A CHARGED PARTICLE IS A SPECIAL KIND OF "SPRAY NOZZLE"
26. AN OBSERVABLE CHARGED PARTICLE IS DIRECTLY CONNECTED TO VIRTUAL PARTICLE FLUX VACUUM
27. SPIN COUPLES VACUUM TO PARTICLE
28. ELECTRON PRECESSION (SIMPLIFIED)
29. VACUUM/SPACETIME IS PURE VIRTUAL PARTICLE FLUX ($Ø_0$)
30. VACUUM IS:
31. GRADIENT OF ELECTROSTATIC POTENTIAL
32. IN A ∇Ø, A CHARGED PARTICLE MOVES ITSELF
33. ELECTROMAGNETIC WAVES IN ELECTRON GAS IN A CONDUCTOR
34. ELECTROMAGNETIC WAVES IN VACUUM
35. DETECTION OF TRANSVERSE AND LONGITUDINAL WAVES
36. CREATING A "RIVER" OF ANENERGY
37. A 2-WIRE SYSTEM IS CONSERVATIVE
38. A HOLLOW CHARGED SPHERE
39. ONE-WAY GATE VALVE
40. SIMPLE FREE ENERGY MOTOR
41. THE TRANSLATOR
42. TRANSVERSE WAVE INTERFERENCE
43. LONGITUDINAL WAVE INTERFERENCE (SCALAR WAVES)
44. CREATING ENERGY AT A DISTANCE
45. NONLINEARITIES CAUSE SHIFTING (PARTIAL TRANSLATION)
46. THE SCALAR AURA.
47. VIRTUAL FLUX AND MAGNETIC FIELD (LINEAR CASE)
48. PRODUCING MAGNETIC MONOPOLES
49. BREAKING METAL WITH MAGNETIC MONOPOLES
50. CREATING AN INERTIAL FIELD (ANTIGRAVITY)
51. EFFECTS ON HUMANS
52. INITIATING SPECIFIC BIOLOGICAL EFFECTS
53. GROUND-TO-AIR USE

54. TACTICAL AIR-TO-GROUND USAGE
55. INTEGRATED WEAPONS DISPLAY (MODIFIED JAMMER)
56. RADAR INVISIBILITY
57. NETWORK OF VIRTUAL TRANSMITTERS
58. CONCLUSION

Return to Homepage

TOWARD A NEW ELECTROMAGNETICS

PART 4: VECTORS AND MECHANISMS CLARIFIED

(©) 1983 T. E. Bearden

All rights reserved.

Delivered to the 1983 Annual Conference

of the

U. S. Psychotronics Association

July 20-24, 1983

at the

University of Portland

Portland, Oregon

The Tom Bearden Website

--FOREWORD --

This paper is an adaptation of the oral/visual presentation given by the author at the 1983 Annual Conference of the U. S. Psychotronics Association on Saturday, July 23, 1983.

The presentation was delivered directly from the vugraphs alone, and not from a formal, written text.

The title of the presentation at the conference was "New Electromagnetics: Where the 'Old Math' Took the Wrong Turn."

As originally conceived, the lecture was to be given in a single period of some 45 minutes and cover only the first part of this paper, the clarification of the vector concept in physical theory. The Symposium director so graciously scheduled two periods instead, allowing time to present additional material further clarifying vector and scalar waves, and to present a variety of unusual physical mechanisms that apply the concepts.

After the conference, the author prepared this paper directly from the same slides, in the same order. However, no attempt was made to match the words in this paper to the words actually delivered in the formal presentation. The gist of the two, however, are the same -- except that, in the conference lecture, the author covered (as an aside) some important additional material: (1) the nature of what actually occurs in an "electrical ground," and (2) the author's explanation of the theory of Tesla's magnifying transmitter.

An audio tape and a videotape of the author's USPA presentation were made by the conference officials. Copies are available at nominal cost from Mr. Robert Beutlich, Secretary/ Treasurer, U. S. Psychotronics Association, 3459 Montrose Avenue, Chicago, Illinois 60618, U.S.A.,
phone (312) 478-7715.

SLIDE 1.

TOWARD A NEW ELECTROMAGNETICS

© 1983 T.E. BEARDEN

ALL RIGHTS RESERVED

ACKNOWLEDGEMENTS

I would like to express my deep appreciation to two of my fellow colleagues, Dr. William Tiller and Mr. Frank Golden, for many fruitful hours of discourse and interchange on these and related subjects.

Also, I wish to thank the Association of Distinguished American Scientists (A.D.A.S.) for support and assistance in the long and arduous struggle to revise the basic foundations of electromagnetics and mechanics.

Next Slide

The Tom Bearden Website

SLIDE 2.

OUTLINE

- **MAIN BRIEFING**
  - **> TRANSLATOR EFFECTS**
  - **> POTENTIAL WEAPONS**
  - **> INCIDENTS**
  - **> CONCLUSION**
- **HISTORICAL BACKGROUND**
  - **> TESLA/MORAY**
  - **> WWII AND AFTER**
- **ELEMENTS OF THE EMERGING THEORY**
  - **> LONGITUDINAL/ TRANSVERSE WAVES**
  - **> VACUUM/MASS EFFECTS**
  - **> FLAWS IN VECTOR THEORY**
  - **> IMPLICATIONS**

This presentation is one part of a three part presentation, consisting of the main briefing on physical effects, the historical background, and the elements of the emerging new electromagnetics.

In this present briefing I will not cover the historical background. Instead, first I will address the concepts of the new theory, and then I will give an abbreviated main briefing, including some weapon aspects. I will present one simple free energy motor and show how it works, and where it gets its energy.

Much of this material I have known for some time, but have hesitated to release it because it enables one to develop -- in a fairly straightforward manner -- weapons and beams (ray) systems that can disable electronics, computers, communications, and people. Anyone handy in electronics, who has a few thousand dollars and access to bench equipment and an electronics parts supply house, can develop these weapons in his or her basement workshop. But because certain very radical elements in this country already know some of this information and may plan to utilize such devices in criminal activities, I am openly releasing the information as a warning, to be prepared.

Of course there are many good things that can be developed with this technology, including machines to heal a remarkable variety of ailments and illnesses. I strongly urge everyone to use this information wisely and only to benefit other human beings. There exists a cosmic or karmic law for those who misuse it against their fellow persons; if one does that, one will assuredly suffer the consequences.

Also, I strongly urge the development of Western defenses against the Soviet strategic and tactical weapons; already developed utilizing these principles. Unless the West wakes up to the extreme urgency of this task, in the near future we may be overwhelmed in short order by a much harsher, dictatorial system. If that should happen, it will plunge the human race into a new dark ages far more terrible than that dark period in history following the fall of Rome.

These are the final times, and this is the beginning of the final technology. The ability to directly engineer physical reality itself has been laid in our laps. Pandora's box is already spilled open, and there is no longer any stopping the new technology.

Let us prepare, then, for that which is to come.

With these introductory remarks, let us now turn to the main presentation.

Next Slide

The Tom Bearden Website

SLIDE 3.

CHARACTERISTICS OF SELECTED CONCEPTS

CONCEPT	CHARACTERISTIC
• ENERGY	FLOW OF OBSERVABLE MASS PARTICLES
• ANENERGY	FLOW OF VIRTUAL PARTICLES
• PRESENT "CHARGE"	VIRTUAL PARTICLE FLUX TIED TO OBSERVABLE MASS PARTICLES
• TRUE CHARGE	VIRTUAL PARTICLE FLUX WITHOUT MASS
• FLUX	MULTI-DIRECTIONAL FLOW THROUGH A POINT
• FLOW	UNI-DIRECTIONAL MOVEMENT OF A FLUX [GRADIENT]
• CURRENT	UNI-DIRECTIONAL GRADIENT OF A [USUALLY CONSTRAINED] FLUX

On this slide I show some fundamental defining characteristics of energy, "charge" or charged mass as presently in the theory, flux, flow, and current. These fundamental concepts are often somewhat confused in the literature.

Particularly note that the concept of energy, being tied to "the capacity to do work," is specifically tied to the concept of mass. Eventually, energy must be expressed in terms of moving masses -- specifically, in accelerating or decelerating masses.

I introduce the term "anenergy" here, specifically in relation to

the concept of a virtual particle. Anenergy is roughly equivalent to the present idea of "virtual energy,"
except it more precisely implies the flow or flux of virtual particles.

We also redefine charge as virtual particle flux, in order to remove the present error in EM theory where "charge" always implies a charged mass. The electrostatic scalar potential, phi (Ø) , then merely becomes the intensity of the massless charge -- that is, the intensity of the virtual particle flux -- at a point. Let me point out, however, that in the new view this "point" is always in n-dimensional space, where n is equal to or greater than four. The present 3-space formulation of Ø is thus a highly special case.

Next Slide

The Tom Bearden Website

SLIDE. 4

QUOTE FROM NIKOLA TESLA:

"THE HERTZ WAVE THEORY OF WIRELESS TRANSMISSION MAY BE KEPT UP FOR A WHILE, BUT I DO NOT HESITATE TO SAY THAT IN A SHORT TIME IT WILL BE RECOGNIZED AS ONE OF THE MOST REMARKABLE AND INEXPLICABLE ABERRATIONS OF THE SCIENTIFIC MIND WHICH HAS EVER BEEN RECORDED IN HISTORY."

Nikola Tesla
"The True Wireless,"
The Electrical Experimenter

One of the things we will find is that Hertz or transverse electromagnetic waves are strictly mass waves in a charged mass particle medium.

For example, transverse EM waves do not, and CAN not, exist in vacuum. Vacuum EM waves are longitudinal waves of compression and rarefaction. What is compressed and rarified is the virtual particle flux that comprises vacuum itself. Vacuum EM waves in this virtual flux are just like sound waves in air -- in the flux of molecules and atoms that comprise the atmospheric gas.

Nikola Tesla, of course, knew this and he frequently pointed out the falsity of the accepted transverse wave theory. Here is one Tesla quote, for example, taken from The Electrical Experimenter. (PAUSE)

Almost every scientist -- even the "Tesla bugs" -- have thought Tesla wrong in his adamant opposition to the idea of Hertzian waves in the vacuum.

As we shall see, Tesla was right and all the present scientists and textbooks are wrong .

Next Slide

The Tom Bearden Website

SLIDE 5.

FORCE BETWEEN TWO LIKE CHARGES



A NEGATIVELY CHARGED
TEST MASS
[e.g., AN ELECTRON]
BROUGHT INTO
THE VICINITY OF q_1
EXPERIENCES
A FORCE $\bar{F}_2$ AS SHOWN.
NOTE THE
ELECTRON ACTUALLY IS
SPINNING.
THIS HAS NEVER BEEN
DONE WITH A
TRUE "STATIC CHARGE",
FOR THERE
IS NO SUCH THING IN
NATURE.

In my presentation last year, I noted some 22 fundamental flaws in present electromagnetics theory. One of these flaws was in the actual vector theory itself. As we shall discover, one cannot simply plug geometrical vectors into physical systems without making fundamental errors. The vector concept itself must be adapted, for there are now four different kinds of vectors in physics, all confused as the same thing. We will come to that shortly.

To begin, let us look at the fundamental kind of experiment, shown on this slide, from which the idea of electrical force and electric field was taken.

We have a fixed static charged object q(l) in the laboratory, and we bring in a test charged mass q(2). The test charged mass may even be a single electron, as we illustrate here. We show in our example the fixed charge to be negative. When we release the test charge electron, it accelerates away from the fixed charged mass, as shown on the diagram. Note that we have no force at all until we bring in the test charged mass. Indeed, we shall find that the force is actually COMPRISED OF the accelerating test electron. Specifically, it is not something mysterious which appears in vacuum and PUSHES on the electron. We shall find that FORCE IS AN EFFECT, NOT A CAUSE. It CONSISTS OF the "smeared mass" that is accelerating -- in this case, it consists of the smeared, accelerating electron.

We summarize the experiment: in the absence of the charged test particle, no force exists in the vacuum. When we bring in the test charged mass, it accelerates away, and THE FORCE CONSISTS OF THAT ACCELERATING CHARGED MASS PARTICLE. The experiment does not at all address or deal with WHAT EXISTS IN THE VACUUM AROUND CHARGED MASS Q(l) IN THE ABSENCE OF TEST CHARGED MASS Q(2). Any assumption of a force existing in the vacuum is sheer speculation and not based on this experiment.

Next Slide

[The Tom Bearden Website](http://www.cheniere.org)

SLIDE 6.

REPETITIONS LEAD TO THE VECTOR "FIELD" CONCEPT



REPEATING FIGURE 4 A NUMBER OF TIMES LEADS TO SETS OF FORCE ARROWS, WHICH WE THEN VISUALIZE IN TOTAL AS A FIELD, Ë, OF FORCE(S) ABOUT q_1

RIGOROUSLY, THIS "FORCE FIELD" WOULD REQUIRE THAT A SPINNING CHARGED PARTICLE OF MASS EXIST AT EACH AND EVERY POINT IN SPACE ABOUT q_1

On this slide, we show that, as we repeat the experiment by bringing in the test charged mass from differing directions, the same thing happens around the fixed charged mass q(l). Test charged mass q (2) -- our electron -- accelerates radially away from q(l).

As we repeat the experiment and draw many of the little arrows radially outward, gradually the idea of a "vector field" emerges. That is, we form the idea that, at every point in space around fixed charge q (l), there exists one of our little vector arrows. Thus we assign a vector field to the space: to every point of it, there is assigned both a magnitude and a direction.

However, note that this does not describe the situation as it exists, at any time, in the "present." That is, rigorously any one arrow only exists whenever a little test charged mass is present and accelerating radially away.

We may take the view that the arrow WILL exist WHEN a test charged mass is brought to that point and released. In that case, the arrow WILL exist in the FUTURE, not the present. And we may refer to that as, it POTENTIALLY exists, when and if.. ..etc.

So already we see a fundamental logical problem in the idea of such a field. It WILL exist in the future, but only POTENTIALLY exists in the present.

Of course I am not the first one to point out such difficulties; the fact that the field concept is erroneous is already well-known to foundations scientists. But it is such a USEFUL concept that it is retained.

Now the Ë-field, or electric field, is defined as "the accelerating force on a charged mass per unit charged mass accelerated by it." If there is no charged mass present to be accelerated, then there can be no Ë-field present.

So Ë-field cannot exist in vacuum, for vacuum presupposes the absence of all observable mass.

So we can rigorously say that no Ë-field of force exists around the charged mass q(l) IN THE PRESENT. At best, it can only POTENTIALLY exist IN THE FUTURE.

Next Slide

The Tom Bearden Website

SLIDE 7.

A SCALAR HAS A HIDDEN [VIRTUAL] VECTOR SUBSTRUCTURE


VESSEL
PRESSURE P AT A POINT IN A CONTINUOUS FLUID IN A CLOSED VESSEL
THE ACTUAL MICROSCOPIC SITUATION AT POINT P
$\bar{F}_n$
$\bar{F}_2$
$\bar{F}_1$

Our next slide shows that a physical scalar quantity has a hidden vector substructure.

For example, we show on the left a closed vessel containing a pressurized gas. The pressure at a point in the gas is a scalar quantity, since it has a magnitude but not a direction. However, physically what we have in the gas is a flux of individual molecules continually through any small volume, which we may let approach a point in the limit. Thus we have a flux in all directions through the point at which we specify pressure.

That is, the scalar "pressure" at a point may be said to contain a substructure of individual molecule flow vectors.

All physical process scalars have such hidden substructures. In the equilibrium case, the summation of all the individual flux vectors yields a resultant vector zero.

Thus we take the view that ANY PHYSICAL PROCESS SCALAR IS ALSO A ZERO VECTOR, AND ANY ZERO VECTOR IS A SCALAR AND CONTAINS A SUM-ZERO HIDDEN VECTOR SUBSTRUCTURE.

Next Slide

The Tom Bearden Website

SLIDE 8.

SCALAR AND VECTOR SUBSTRUCTURES



$S_1 = \bar{0} = \sum_i \bar{f}_i$
V_1
S_1
S
f_1
f_2
f_3
f_4
f_5
f_6
f_7
f_8
p_1
$p_1 = \sum_i \bar{P}_i = \bar{0}_p$
P_1
P_2
P_3
P_4
P_5
P_6
P_7

Now let us see if we can do some unusual thinking about the hidden vector substructure of a scalar or zero-vector.

On the leftmost figure in this slide, we show a plate with balanced opposing forces. The vector summation of all the forces' is zero, so the system has no resultant vector. The plate therefore does not move. However, the plate -- that is, the medium in which the forces act -- is stressed, much like the previous example of pressure in a gas. The difference is that now the stress is patterned in its substructure, and not random. Now suppose we rhythmically vary the forces, each the same, in a regular manner in time. Yet we maintain a continuous balance, so there is never a system resultant greater than zero. In this case, we maintain our vector zero, but we are producing regular stress waves in the plate medium..

I think you now can see that I can vary the individual opposing vector pairs so that rhythmic waves flow from top to bottom, or from bottom to top. That, of course, will describe a vector gradient traveling through the medium, and that will be an ordinary "vector wave." Is there any way I can make waves through the medium, and not have such vector waves ever appear?

Indeed there is, if I look further into the substructure. Take one point on one of the vectors shown acting on the plate in the left diagram. That point is a scalar, and it also has a substructure of even finer vectors, as shown in the lower middle figure. And any point in one of these second-order hidden vectors is a scalar and composed of a still finer hidden vector substructure, as shown in the lower right figure. This process repeats ad infinitum, and all is structures within structures. At least it can be modeled that way, for it already is treated that way in particle physics.

Now go back to the second order vector substructure. Here I can establish whatever patterns I wish, and not affect the first order pattern shown in the figure on the left. I can even rhythmically vary things in the second order substructure, and leave a blissfully unchanged first order substructure, to the first order observer.

So I can make as many waves; as I wish through the medium, as long as I stay second order or higher, and the external observer will never see any change at all unless he has a special detector of some sort to detect the lower substructure changes.

As I showed in the Appendix to my book, The Excalibur Briefing, these substructures are in reality the same thing as hyperspaces. And movements in them can proceed much faster than the speed of light.

So I can have higher order signals and waves through the stressed medium without changing the overall first order stress in the medium.

This is a sort of super-relativity; the present relativity is just a special case.

Superluminal communication systems are perfectly possible, but not with the present first order transmitters and receiver/detectors.

Note also that higher order stresses -- stresses in the higher order substructures -- represent special stresses in time, and time has an internal stress-pattern substructure. The higher order stress waves are phase waves or phase fluctuations in that respect.

Also note that Charles Musés has already created the hypernumber mathematics of the structure of time, and it is largely in his mathematics that these concepts will have to be mathematically modeled.

Next Slide

The Tom Bearden Website

SLIDE 9.

SUPERPOSITION DOES NOT ELIMINATE THE VIRTUAL SUBSTRUCTURE



TWO OR MORE MACROSCOPICALLY "EQUAL" VECTORS OR SCALARS CAN DIFFER DRASTICALLY IN THEIR VIRTUAL SUBSTRUCTURE DISTRIBUTIONS. EVEN TWO "ZEROS" MAY BE DYNAMICALLY DIFFERENT DUE TO THEIR DIFFERING SUBSTRUCTURES.

Next we show some simple substructures of a zero vector. All of these vector systems sum to zero vectorially. Note that if we superpose two of these structures, all substructure vectors are still present., and the vector summation is still zero.

Also notice that, from the standpoint of substructuring, zeros can be and are drastically different.

We can even make rhythmic waves in the substructure by superposing patterned zero vectors in a regular fashion.

Next Slide

The Tom Bearden Website

SLIDE 10.

PHYSICAL VECTORS

- **VECTOR: A "SMEARED PARTICLE"**
- **FOUR MAJOR PARTICLES IN PHYSICS:**
  - POINT [MASSLESS, CHARGELESS]
  - MASS [CHARGELESS]
  - CHARGED MASS
  - CHARGED POINT [MASSLESS}
- **LEADS TO FOUR MAJOR VECTORS:**
  - GEOMETER'S
  - MECHANIC'S
  - ELECTRICIAN'S
  - ADVANCED ELECTRICIAN'S

In quantum mechanics, as we approach the quantum level, we find that the notions of a particle (static concept) and a wave become inseparable. That is, any particle becomes a "smear" in length and time, and it becomes inseparable from its smear. At the quantum level, there is no separate energy, length, mass, momentum, energy, or time -- all are welded together inextricably into a quantity called "action," having the units of angular momentum.

So at the fundamental quantum level, a moving point becomes a smear, and a vector represents a physical, undifferentiated entity.

To go quickly, we now define a vector as consisting of a smeared particle. That is, the particle is smeared in both time and length, and it is not differentiated from time or length.

There are four kinds of particles in physics which can be smeared to form vectors. First, there is a point in space or spacetime. This point may be approximated as massless and chargeless. At least that is the way the geometers of old conceived it in the abstract, and so the idea of a "point" in space assumes it to be chargeless and massless. Second, there is a tiny particle of mass, often abstracted to be a "point-mass," but visualized as having no charge. This is the mechanic's particle. Third, there is a tiny charged mass, such as an electron, and this is the electrician's particle. Again, it is often abstracted as a charged point-mass. Fourth, there is a charged point, having no mass, and this is the advanced electrician's particle, which he uses to form the idea of potentials and fields.

Smearing these four particles at the fundamental quantum level produces four different kinds of physical vectors: the geometer's, the mechanic's, the electrician's and the advanced electrician's vectors. They are all different.

Next Slide

The Tom Bearden Website

SLIDE 11.

THE FOUR VECTORS OF PHYSICS


① MASSLESS SPATIAL SYSTEM VECTOR
(GEOMETER'S VECTOR)
② MASS SYSTEM VECTOR
(MECHANIC'S VECTOR)
③ CHARGED MASS SYSTEM VECTOR
(ELECTRICIAN'S VECTOR)
④ CHARGED SPATIAL SYSTEM VECTOR
(ADVANCED ELECTRICIAN'S VECTOR)

On this slide we show a graphic illustration of each of these vectors.

Note that they may be visualized as smeared particles, but the particle is not separate from the smear in time and length.

Each vector must be considered as a unitary entity -- it is a special kind of quantum, if you will.

Each is a special quantum of motion.

And Dewey Larson has it right when he says, "All is motion."

Next Slide

The Tom Bearden Website

SLIDE 12.

FORCE DEFINITION

- ***A TRUE DEFINITION IS AN IDENTITY.***

$$F \equiv d/dt\,(mv)$$

- **FORCE CONSISTS OF THE TIME RATE OF CHANGE OF MOMENTUM**
- **MOMENTUM IS A MASS SMEARED THROUGH A LENGTH IN A CERTAIN TIME**
- **FORCE CONSISTS OF MASS-MOTION-CHANGE**
- ***FORCE IS AN EFFECT, NOT A CAUSE !***

We now look a little closer at the concept of a force.

I point out that a true definition is an identity. If a supposed definition of an entity is not an identity for that entity, then it is not a definition at all, but only a statement ABOUT the entity.

It may come as somewhat of a shock to the normal engineer and scientist that the foundations concepts of physics -- such as force, mass, energy, etc. -- are ALL in serious difficulty and contain many unresolved logical conflicts.

Force is in that kind of difficulty, and it has that kind of logical conflict.

In fact, in its force equations, physics has not even applied its own present definition of force.

As we show here, force is generally defined as the time rate of change of momentum.

If that is true, then as an identity the definition states that a force CONSISTS OF the time rate of change of momentum.

And of course, momentum is mass times velocity. Hence momentum is a mass smeared through a length and through a certain time.

Force then consists of the time rate of change of that smearing. That is, we smear the mass through time and length, faster or slower.

But if force CONSISTS OF that smearing change, it does not CAUSE it.

Force is thus an effect or result, not a cause.

This implies that there is a more fundamental mechanism that causes or generates force itself -- ANY force. If we can find that hidden mechanism, we may well find the long-sought unified field theory, since it will unify all forces on a common mechanism.

Next Slide

The Tom Bearden Website

SLIDE 13.

FORCE IS AN EFFECT NOT A CAUSE



1. $\bar{P} = M\bar{V}$ (MACROSCOPIC)

2. $\bar{P} \equiv \overline{[M\bar{V}]}$ (MICROSCOPIC)

3. $\bar{F} = \frac{d\bar{P}}{dt}$ (MACROSCOPIC)

4. $\bar{F} \equiv \frac{d\bar{P}}{dt} \equiv \frac{d}{dt}\overline{[M\bar{v}]} \equiv \overline{[M\bar{v} + M\bar{a}]}$ (MICRO)

5. $F \equiv \overline{[M\bar{a}]}$ (NONRELATIVISTIC)

6. FORCE CONSISTS OF A "SMEARED MASS"

7. IT IS MASS-ACCELERATION, IT DOES NOT CAUSE IT.

8. FORCE IS AN EFFECT, NOT A CAUSE!

On this slide, we show briefly how one might express this idea in mathematical symbology.

Macroscopically, momentum consists of mass times velocity. Microscopically, the mass and the velocity are inextricable, and it is not proper to speak of a "mass in motion," but only of "mass-motion." We show this in equation 2.

We take the macro definition of momentum, as shown in equation 3, and express it for the microscopic, unseparated case, as shown in equation 4.

In the nonrelativistic case, we may consider m-dot to be zero, since the time rate of change of mass is almost zero. In that case, force may be defined for the microscopic case as a smeared accelerating mass, as shown in equation 5.

Force thus consists of the welded mass and acceleration, with no seam in the middle.

It IS mass-acceleration; it does not CAUSE it. Therefore force is an effect, not a cause.

Next Slide

The Tom Bearden Website

SLIDE. 14



FORCE AND $\bar{E}$-FIELD DO NOT EXIST IN VACUUM

1. $\bar{F}_p \equiv \overline{[M_p \circ \bar{a}_p]}$
2. WITHOUT M, THERE IS NO M_p, NOR $\bar{F}_p$
3. HENCE FORCE DOES NOT EXIST IN VACUUM.
4. $\bar{E}_{cm} \equiv \dfrac{\bar{F}_{cm}}{q_{cm}}$
5. WITHOUT M, THERE IS NO $\bar{F}_{cm}$, NOR q_{cm}.
6. HENCE $\bar{E}$-FIELD DOES NOT EXIST IN VACUUM.
7. SIMILARLY, $\bar{B}$ AND $\bar{G}$ DO NOT EXIST IN VACUUM.
8. NO FORCE FIELD EXISTS IN VACUUM.

But if force CONSISTS OF mass welded to acceleration, it cannot exist in the absence of mass.

Hence force does not exist in vacuum.

Further, the Ë-field (Electric field) of a charged particle is defined as the force on a charged mass, divided by the mass. That is, the Ë-field is thought to represent the force per unit charged mass. And then it is assumed to exist in vacuum.

But vacuum is without mass or charged mass, observably. Without mass, neither force nor charged mass exists.

Therefore the Ë-field does not exist in the vacuum.

Magnetic field (B) and gravitational field (G) are similarly defined, and they have the same logical difficulties.

Therefore neither magnetic field nor gravitational field exist in vacuum.

A priori, NO force field exists in vacuum.

The greatest error in physics has been the assignment of a force as a cause, and thus assigning it to the vacuum. The force is an effect, and it never exists in vacuum, a priori.

Next Slide

The Tom Bearden Website

SLIDE 15.

COROLLARIES

- **MORE PRIMARY MECHANISM CAUSES/GENERATES FORCE -- ANY FORCE**
- **FORCE DOES NOT EXIST IN VACUUM, SINCE VACUUM IS THE ABSENCE OF MASS**
- **FORCE FIELDS DO NOT EXIST IN VACUUM**
    - **E-FIELD**
    - **B-FIELD**
- **TRANSVERSE [HERTZIAN] WAVES DO NOT EXIST IN VACUUM**

Without belaboring the issue, I now point out and summarize some of these conclusions.

First, a more primary mechanism causes or generates force -- ANY force.

Second, force implies the presence of mass a priori. Force does not exist in vacuum, since vacuum is the absence of mass.
_

Third, no force fields of any kind exist in vacuum, including Ë-field, B-field, and gravitational field.
_

Fourth, since Hertzian waves are defined in terms of Ë and H force fields, and these fields do not exist in vacuum, then Hertzian waves do not exist in vacuum.

Tesla pointed out long ago that vacuum EM waves are longitudinal waves, not Hertz waves. Vacuum EM waves are similar to sound waves in a gas.

The Hertz wave exists as a matter wave in the electron gas in a transmitting antenna, and in the electron gas in a receiving antenna, but does not exist in the vacuum in between the two antennas. Between them, EM waves are longitudinal waves.

Next Slide

The Tom Bearden Website

SLIDE 16.

ENERGY IS DERIVED, NOT FUNDAMENTAL



- ENERGY IS CONGRUENT TO WORK

  $$dW = \bar{F} \cdot \bar{d}S$$

- BUT FORCE IS AN EFFECT, NOT A CAUSE
- THUS WORK IS AN EFFECT, NOT A CAUSE
- ENERGY≅WORK CAPACITY
- A MORE FUNDAMENTAL MECHANISM GENERATES "ENERGY"

  $$\Delta E = \frac{\Delta A}{\Delta T}$$

- ENERGY IS AN EFFECT, NOT A CAUSE

Energy is usually taken as "the capacity to do work" at some future time. In other words, when we refer to the energy of something, we refer to HOW MUCH WORK IT CAN DO IN THE FUTURE, IF AND WHEN WE ARRANGE FOR IT TO DO IT. Rigorously, a body has no "work" at a particular instant in time, so we use "energy" to refer to potential work that can, or will, be done in the future. Thus energy is always congruent to work in the future.

And for that reason, the units of energy are the units of work; the only difference is in the time the work is done, relative to the "now" or "present" we are speaking of.

Energy is the potential for work to be done in the future.

But what is work?

Well, work is defined in terms of the movement of a force through a distance. And it is understood that only the projection of the force along the line of movement is "working." Thus work is defined differentially as shown on the slide. The differential of work is equal to the dot product of the moving force times the differential of displacement.

But as we have seen, force is an effect, not a cause.

That is, when we calculate the work done, it's always in the past, never in the present or future. It's always been DONE, and has been expended.

Being in the past, it's gone forever, so it certainly isn't the CAUSE of anything which happens in the future.

Thus work is an effect, not a cause.

That's interesting, because then it certainly does not directly generate "energy," since energy is something in the present which speaks of future work to be done.

Rigorously, the fundamental quantum -- which is what exists in the present, in unseparated and unquantized form -- consists of action. NOT energy, NOT time, NOT length, NOT momentum exclusively, but all of these INclusively.

And a change in energy occurs when a quantum is separated at a certain rate in time. Thus delta energy equals the time rate of change of action, or delta action divided by the delta time used in separating the quantum and fissioning it into parts (collapsing the wave function).

Thus energy itself is an effect or result of a more fundamental mechanism, and it is not a cause.

In quantum mechanics all this has been neatly "buried" in the mysterious "collapse of the wave function," which is supposedly what "causes" everything to happen. And then we swear that what results after the collapse is a totally statistical selection from the possible states of the system we are examining. We thus say that the microworld is totally statistical at base. Of course we also build a wave equation or wave function which propagates forward in time with rigorous causality, and that wave or function absolutely controls the basket of "possible states" allowed .

All that says is that the "wave function times time" is what exists in the present, when observation has not been made by "stopping time." And then we "stop time" in a rather blunt manner, somewhat like firing a billiard ball blindly into a group of billiard balls on a table, and we live with what gets hit and pops out.

If we examine this "time" that is flowing, look into its substructure, and arrange that substructure as we will, we can control which "billiard ball" is hit and which pocket it goes into. By working on the vector substructures of time, we can thus deliberately control the microworld and make it causal, not statistical. Quantum mechanics is in error in stopping where it has; it is presently only a first order approximation of the real quantum mechanics that awaits.

Einstein was correct after all; God does NOT play dice with the universe when one considers all levels.

One finds oneself in a statistical situation at one level only when the constituent sublevels of it are uncontrolled.

Next Chapter

The Tom Bearden Website

SLIDE 17.

EXISTENCE IN, AND PASSAGE THROUGH, TIME

- **IN RELATIVITY, TRANSLATION OF A BODY AND PASSAGE THROUGH TIME ARE RELATED**

  $$\Delta L = C \Delta T$$

- **"MASS" IS SPATIAL**
  - **DOES NOT EXIST IN TIME**
  - **"MASS-TIME" EXISTS IN TIME**

- **VIRTUAL FLUX TO AND FROM A BARE PARTICLE DETERMINES ITS "PASSAGE THRU TIME"**

- **SPHERICAL SPIN OF A MASS PARTICLE $[L^3]$ COUPLES IT TO THE SPACETIME VACUUM $[L^3T]$ VIRTUAL PARTICLE FLUX**

- **PASSAGE THROUGH ORDINARY TIME IS CONTROLLED BY CREATION AND ANNIHILATION OF QUANTA**

On this slide, we simply point out that translation of a body through space and its passage through time are related, according to relativity.

Now "mass" is spatial.

It does not exist in time.

Only things which contain the unit of time can "exist in time."

Otherwise, the thing only exists as such when the passage of time has been momentarily stopped -- usually by photon emission and the consequent carrying off of the time unit by the photon.

Since every mass that has temperature -- and every mass does -- is continually absorbing and emitting photons, then the mass is continually grabbing a time tail (absorption) and losing it (emission) shortly thereafter.

Masstime is what exists in time, not mass.

And every mass particle is continually turning from mass to masstime to mass, etc.

Indeed, it is the summation of the absorption and emission of virtual subquanta by a mass particle -- i.e., its "charge" **--** that determines its rate of flow through "time."

And the spherical spin of a mass particle couples the particle of mass to the spacetime vacuum; that is, to the virtual particle flux.

Passage through ordinary time is controlled by creation and annihilation of quanta, and these processes are controlled by substructure (subquantal) actions and interactions.

Next Slide

The Tom Bearden Website

SLIDE 18.

SOME IMPLICATIONS

- **MODIFIES CONSERVATION OF CHARGE**
- **MODIFIES CONSERVATION OF ENERGY**
    - ***MASS***
    - ***ENERGY***
    - ***ANENERGY (MASSLESS CHARGE)***
- **MODIFIES NEWTON'S LAW**
    - ***FOR EVERY ACTION, THERE IS AN OPPOSITE AND EQUAL REACTION***
    - ***REACTION NEED NOT BE LOCAL***
    - ***REACTION NEED NOT BE ANTIPARALLEL***
- **UNIFIED FIELD THEORY**

Without belaboring the issue, I now simply point out some implications of the new approach.

First, we modify two laws -- the conservation of charge and the conservation of energy -- by combining them into one law, a new conservation law in which anenergy is conserved.

Neither charge per se nor energy per se need be conserved; but the overall anenergy (massless charge) equivalency is what is conserved. This allows us to derive mechanisms for free energy from the vacuum, for example. These mechanisms readily violate the present conservation of energy law, but do not violate the overall conservation of anenergy law.

It is the total anenergy equivalency of mass, energy, and massless charge that is now to be conserved in general. The old laws are now just special cases.

Also, Newton's third law -- for every action there is an equal and opposite reaction -- is modified. It still applies, but in changed form.

The reaction still occurs, but it need not be local, and it need not be antiparallel to the original action.

Thus it is now possible to design and build a "locally reactionless" inertial space drive for a vehicle.

The final implication is that the common mechanism producing force -- any force -- provides a unified field theory. Specifically, it provides one which easily lends itself to direct engineering. It is not esoteric nor mysterious. It is practical and physical, and it can be done with some modifications to our present electrical circuits and devices.

Next Slide

The Tom Bearden
Website

SLIDE 19.

CONSERVATION OF ANENERGY (AE):
(AN EXPANDED ENERGY CONSERVATION LAW)



1. CONSERVATION OF CHARGE:
   - "CHARGE" = MASS (M_C) + CHARGE (AE_C)
   - $|M_C| + |AE_C| = K_1$
2. CONSERVATION OF ENERGY:
   - DYNAMIC ENERGY (E)
   - ENERGY EQUIVALENCE OF MASS (M_E)
   - $|E| + |M_E| = K_2$
3. ADDING (1) AND (2):

   $|M_C| + |AE_C| + |E| + |M_E| = K_1 + K_2 = K_3$
4. LETTING $|M| = |M_C| + |M_E|$,

   $|M| + |E| + |AE_C| = K_3$
5. LETTING $|M| = AE_1$, $|E| = |AE_2|$, $|AE_C| = AE_3$,

   $AE_1 + AE_2 + AE_3 = K_3$

We briefly show a simplified derivation of the new conservation of anenergy law.

We express the conservation of charge law by correcting the term "charge" to show its true meaning: charged mass. We use the absolute value symbol to mean the "anenergy equivalency."

As shown on the slide, we account separately :for the mass (m-sub-c) of the conserved charges and the virtual particle charge flux (the anenergy -- AE-sub-c) of the charges conserved. That law now says that the absolute values of the masses and the massless charge fluxes have a total constant summation.

For a dynamic mass, we do a similar thing, in this simplified case ignoring potential energy of position, and taking the energy equivalence of the dynamic energy (M-sub-E) and the rest mass energy of the particles, M-sub-E. The conservation of energy now states that these two terms have a constant absolute value summation.

We add equations 1 and 2, getting equation 3. We consolidate like terms to get equation 4.

Expressing all terms in their anenergy equivalencies (absolute values), we get equation 5, which is the overall conservation of anenergy equivalency.

Note that we now can change mass into energy or anenergy (massless charge), energy into mass or anenergy, and anenergy into mass or energy.

Thus we can turn everything into pure vacuum ether (pure massless charge, pure anenergy, pure electrostatic scalar potential, pure stress on spacetime) or we can turn part of the vacuum into energy or particles of mass.

Vacuum now becomes a very real thing indeed.

It is pure anenergy.

Pure massless charge, pure electrostatic scalar potential, pure "broken bits" (subquantal bits) of (quantized) energy.

The vacuum is identically the virtual state.

It is not an emptiness filled with virtual things; rather, it IS the sum total of those virtual things, for they are totally unseparated until some sort of "conceptual observation" is invoked.

Physics should have adopted Einstein's suggestion that the vacuum, complete with its EM and gravitational fields, be called the ether.

Next Slide

The Tom Bearden Website

SLIDE 20.

FREE ENERGY IS ALLOWED

- **ANY ONE-WAY GATING PROCESS FROM ANENERGY TO ENERGY YIELDS "FREE ENERGY" SINCE THE ANENERGY IS AUTOMATICALLY REPLENISHED BY THE UNIVERSE.**


PRESENT
MASSLESS CHARGE
ENERGY
MASS
NEW

Now we can put the search for free energy devices on a rigorous scientific basis.

As shown here, mass and energy are translatable one into the other. So are massless charge and energy.

And the universe is filled with fantastic amounts of anenergy; ultimately, that is what the universal vacuum IS.

Any one-way gating process from anenergy to energy yields "free energy" since the anenergy is automatically replenished by the universe.

A sort of Maxwell's demon, after all, is what we need. Only we need one which works with the virtual state, not observable molecules.

Fortunately nature has provided several Maxwell's demons of this sort, if we but recognize them and learn to use them.

Next Slide

The Tom Bearden Website

SLIDE 21.

SCALAR POTENTIAL CAN FORCE THE RELATIVISTIC CASE

- **FOR SCALAR POTENTIAL ENERGY**
  OF APPRECIABLE SIZE RELATIVE TO
  A PARTICLE'S REST ENERGY.
    - **NEWTONIAN MECHANICS AND**
    - **THE SCHRODINGER EQUATION**

- **MAY BE INADEQUATE**
    - **EVEN IF V/C IS SMALL**

Bloch & Crater, "Lorentz-invariant potentials and the non-relativistic limit," American Journal of Physics, Vol. 49, No. 1, Jan. 1981, pp. 67-75

First, let us now digress to point out that one does not have to have relativistic velocity to obtain relativistic effects.

One can use the common electrostatic scalar potential to drive the situation relativistic. On this slide we show just one of several references in the standard literature that address this fact.

Let's understand what we are saying.

Anything you get from a relativistic situation, you can get directly by cleverly applying electrostatic scalar potential.

You can get a change in the passage through time, you can get energy changes, mass changes, inertial resistance changes, etc.

You can bend, warp, and twist spacetime like a pretzel.

If you "wave" the scalar potential by simply varying it , you can create pure time waves. You can also produce pure inertial field waves, pure gravitational waves, etc.

The ability to engineer the curving of spacetime allows the direct ability to engineer physical reality itself.

Next Slide

The Tom Bearden Website

SLIDE 22.

SCALAR STRESS WAVE [O̅-WAVE] [TESLA WAVE]


$+\phi_S$
$+\vec{E}$
ϕ_o
VELOCITY
$-\vec{E}$
$\nabla\phi_S$ IS LONGITUDINAL
$-\phi_S$
$\nabla\phi_S \neq -\vec{E}$

On this slide we now show a simple way to make a scalar, zero-vector wave -- the kind of wave originally discovered by Nikola Tesla.

It's simple. We just believe that a sum-zero vector substructure makes a scalar quantity, and we MAKE some scalars that way.

We also understand that a zero-gradient of a scalar is a zero vector, so that the scalar itself may be taken to be a zero vector.

The simplest explanation of this wave is as follows:

First, in physics we have two competing, mutually exclusive theories as to the nature of electromagnetic energy: the wave theory and the particle theory. Physicists argued for decades over these theories, for some experiments support one and some support the other. They never solved the problem; they just agreed to quit arguing. They formulated the "duality" principle to allow the saving of face to both sides.

Briefly, the duality principle implies that, whatever the nature of electromagnetic energy is before an interaction, in the interaction you can get it to act as a wave or as a particle. In other words, AS IT EXISTS, BEFORE THE INTERACTION, it is implicitly both particle and wave, joined together in some fashion, without being explicitly either one.

With the fourth law of logic, this becomes perfectly clear. With three-law Aristotlean logic, the problem is unresolvable.

Let us use this idea of "explicit duality without implicit duality" to analyze the wave shown on the slide.

First, from a wave aspect, the E-fields and the B-fields of the two waves do superpose and vectorially add. Since the waves are 180 degrees out of phase, the exterior resultant wave has a zero electric field and a zero magnetic field. Therefore it is a "zero-vector" wave, or "scalar" wave. It's a wave of pure stress in spacetime.

However, this scalar wave has a precisely determined substructure, consisting_of two ordinary sine waves, each of which comprises an ordinary E-H vector EM wave.

Now we apply the photon consideration (remember, before we interact with the wave, it must implicitly possess BOTH wave and particle natures combined, and we have so far only examined the implication of the wave nature.

The theory of photons' states that they are monocular critters. Photons pass right through other photons without interaction, in a linear situation. Therefore they can coexist without interaction, which is what we show here.

One photon, by the way, is one wavelength .

The photon theory requires that both substructure waves continue to exist as independent photons. Therefore we are assured that our substructure is intact.

However, notice that the totality of the two waves stresses spacetime. In other words, we have twice the stress on spacetime now as we would have from either wave separately.

This wave is therefore just a pure stress wave in spacetime itself.

This thing oscillates time, oscillates the relativity of the situation, and can affect energy, time flow rate, inertia, gravity, etc. aspects of an absorbing system.

Note that we have a rhythmic oscillation in phi (Ø), and we have a longitudinal stress wave, very similar to a sound wave. The MEDIUM for this wave is the virtual particle flux that identically comprises vacuum spacetime itself.

Next Slide

The Tom Bearden Website

SLIDE 23.

SCALAR Ö-WAVE PRODUCTION


VIRTUAL GROUND
+5
$+\bar{E}$
$\bar{E}_0 = \bar{0}$
$-\bar{E}$
-5
SPINNING CHARGED PARTICLE WILL NOT PRECESS
+10
$+\phi$
COMPRESSIVE STRESS
$\phi_0 = \bar{0}$
$-\phi$
TENSILE STRESS
-10
STRESS LEVEL ON SPACETIME

On this slide we show how to regard the magnitude of the stress, by using one wave envelope as "virtual ground." In the top diagram, the original E-field stress of each wave has a magnitude of 5, and the composite stress wave now has a magnitude of 10, in whatever units we choose to express them.

We show in the bottom diagram that during one half cycle we have compressive stress in the virtual particle vacuum flux, and during the second half cycle we have tensile stress.

This shows the wave is like a sound wave in the gaseous molecules of the air.

However, this wave has one difference. It also oscillates time, and thus has at least one additional degree of freedom, compared to ordinary EM waves.

In fact, this wave can be made n-dimensional and hyperspatial.

As a first order approximation, we can treat such a wave in
a spatial fashion, if the wave is not too great in magnitude and the relativistic oscillation of time and inertia is not too large.

Next Slide

The Tom Bearden Website

SLIDE 24.

A SIMPLIFIED CHARGED PARTICLE



(THINK OF THE FLUX IN AND OUT, EXCEPT GRADIENTS ARE SPIRAL-LIKE, DUE TO PARTICLE'S SPIN)

We now digress slightly to pick up some more concepts.

On this slide, we show a simplified physical model of a charged particle. According to present particle physics, we model it as an observable, spinning bare mass in the middle, connected to a spray of virtual particles on and off the mass in all directions.

It is the spin of the mass that "attaches" the spray of virtual particles to and from itself.

Note that, because of the spin, the gradient lines of flux will actually be spiral or vortex in nature.

Also note that, when EM theory was founded, no one knew that an electron was spinning. Electron spin was therefore omitted from the foundations of present electromagnetic theory, and compensated for later by strictly ad hoc measures.

Next Slide

The Tom Bearden Website

SLIDE 25.

A CHARGED PARTICLE IS A SPECIAL KIND OF "SPRAY NOZZLE"


SPRAY ON AND OFF
POINT IN 4-SPACE
SPINNING CHARGED PARTICLE
Ø IS INTENSITY OF FLUX OR SPRAY
Ø-FLUX

(SPRAY IS THROUGH 4 DIMENSIONS, NOT JUST 3)

Here we show a very important concept, and a very important fact of nature.

A charged particle may be idealized as a special kind of spray nozzle.

The 3-dimensional particle of mass is spraying out virtual particle fluid, and sucking in virtual particle fluid, in four or more dimensions.

We never have to furnish or replenish the spray. Nature provides that. And it's inexhaustible. It comes from the entire virtual particle flux vacuum of the universe. It's already connected firmly to matter, by its connection to the spinning charged particle of mass.

I repeat and strongly stress: This tremendous, continuous spray of virtual particles is absolutely free, and absolutely furnished by the universe.

We don't have to create the basic pumps for the fluid. We just move the spray nozzles around, by moving the spinning charged masses around.

We never furnish any ultimate energy to or in our present EM circuits. We just pump around the spray nozzles, gating the spray furnished by the universe.

Next Slide

The Tom Bearden
Website

SLIDE 26.

AN OBSERVABLE CHARGED PARTICLE IS DIRECTLY CONNECTED TO VIRTUAL PARTICLE FLUX VACUUM



On this slide we accent that our 3-dimensional particle of mass is directly connected by its spin to the vacuum ether itself. To the virtual particle flux that identically IS the vacuum spacetime.

Interestingly, relativity states that the mass itself is nothing but a "kink" or curvature in spacetime .

The fact that the surface of the particle is spinning at right angles to the virtual particle vacuum flux "drags" part of the flux along with it, spiraling it, and certainly "kinking" or "bending" the vacuum flux .

That's the MECHANISM for the bending of spacetime. And that's what MAKES the particle of mass in the first place, and reduces its dimensionality to three.

Also note that the vacuum IS phi-sub-zero, and that is never a zero value. This is contrary to present EM theory, which erroneously assumes phi-sub-zero -- the charge of vacuum -- to be zero or non-existent.

Next Slide

The Tom Bearden Website

SLIDE 27.

SPIN COUPLES VACUUM TO PARTICLE

- **SPHERICAL ROTATION IS THE KEY**
- **A PARTICLE CAN BE MODELED AS A SPHERICALLY ROTATING VORTEX OF SPACETIME**
- **ITS MASS IS DUE TO ITS SPIN**
- **THE SPINNING OBJECT IS CONTINUALLY CONNECTED TO ITS ENVIRONMENT**
- **VERY HIGH VALUES OF ELECTROSTATIC POTENTIAL CAN INDUCE RELATIVISTIC CONDITIONS**
    - **CHANGE RATE OF FLOW OF TIME**
    - **EVEN THOUGH VELOCITY IS NONRELATIVISTIC**

E.P.BATTEY-PRATT AND T.J.RACEY
"GEOMETRIC MODEL FOR FUNDAMENTAL PARTICLES,"
INTL. J. OF PHYS. 19, NO. 6, 437-475, 1980

In fact, the bits and pieces of many of the new concepts are strewed all through the scientific literature. Here we show one example, establishing a good model that spin of a particle couples the particle to the vacuum .

This paper is by E.P. Battey-Pratt and T.J. Racey, and was . published in the International Journal of Physics in 1980.

Note again that very high values of electrostatic potential
can induce relativistic conditions, even though relativistic velocity is not present.

Next Slide

The Tom Bearden Website

SLIDE 28.

ELECTRON PRECESSION (SIMPLIFIED)



ϕ
SPIN AXIS
MOVING PRECESSION AXIS
"NORMAL" EM SCALAR WAVE
A_S
ϕ_0
A_S
VELOCITY
ELECTRON PATH
FREE ELECTRON
PRECESSION AXIS

On this slide I show the effects of precession of an electron when it encounters a longitudinal scalar wave that contains "spin vortex holes" for the electrons to fall into and mesh its spin with.

The basic idea here -- that electron precession accounts for the Hertzian waves in the electron gas in a transmitting antenna and in a receiving antenna, came from my close colleague and friend, Frank Golden, and I am most happy to give him full credit for this important insight.

As we have previously stated, transverse (force) waves cannot exist in vacuum in the absence of mass. Hertz waves therefore cannot exist in vacuum, just as Tesla stated.

Yet we know that Hertz waves exist in the electron gas in our transmitting antennas and in the electron gas in our receiving antennas. How then do we get Hertz waves here, if only longitudinal waves can exist in the vacuum in between?

Electron precession is the key.

We never measure what's happening in vacuum with our instruments. Instead, almost always we measure what is happening to and in the electron gas in our antenna or probe and feeding current to the instrument.

Here we show a "normal" EM vacuum wave -- which is a longitudinal wave containing spin vortexes from the electrons that generated it -- approaching and striking a spinning charged electron. As the peak and trough of the wave passes, it is as if we had a force pressing against the spinning electron, first along the line of wave travel, and then antiparallel to the wave travel. *(that is, "explaining" it in present concepts.)*

The electron acts as a little gyroscope, and precesses laterally, first in one direction and then the other.

Therefore the wave recovered in the electron gas in our receiving antenna or instrument probe is a transverse Hertzian matter wave.

Hertz waves are always matter vector waves.

Vacuum EM waves are always nonmaterial longitudinal scalar waves.

Longitudinal scalar waves in vacuum normally contain many spinning vortex "holes" of flux, created from the spinning electrons which launched the wave and stayed behind in the transmitting antenna. This kind of longitudinal wave is directly detectable by a normal free electron charged gas in a receiving antenna or probe. It also directly interacts with free electrons in a conducting metal shield, and so is shielded by Faraday cages.

On the other hand, our zero-vector longitudinal wave, made
by opposing waves, contains opposing spin holes which annihilate or cancel each other.

In the absence of spin holes, the longitudinal wave will not mesh with spinning electrons in a conductor, and so it is not detectable in the normal fashion. It also does not interact with free electrons in a conducting metal shield, so it readily penetrates Faraday cages.

An easy way to see that electrons do not interact with that substructured longitudinal zero-vector wave is to visualize both substructure component waves interacting on the electron simultaneously, pushing in opposite directions equally. In that case the electron tries to precess in both directions, equally, and so it does not precess in either direction. Therefore it does not "detect" the passing wave.

The wave without "golf ball holes", however, is detectable by any circuit having high nonlinearity actions occurring in it. Such highly nonlinear dynamic areas act to provide a phase shifting between the composite substructure waves. This phase shift results in violation of the sum-zero condition, producing a "normal" EM wave which deposits energy in the out-of-phase area.

From the spin vortex "golf ball hole" concept, the out-of-phase condition means that now we have an alternating preponderance of spin holes, spinning first in one direction and then in the other. Thus the electrons in the nonlinear, phase shift area are hooked and oscillated (precessed) to and fro, producing energy.

Solid state, highly doped transistors are particularly vulnerable to this effect, as are gas discharge tubes, spark and cascade ion discharges, plasmas, etc.

Next Slide

The Tom Bearden Website

SLIDE 29.

VACUUM/SPACETIME IS PURE VIRTUAL PARTICLE FLUX ($Ø_o$)



VACUUM IS IDENTICAL TO:

- **VIRTUAL PARTICLE FLUX**
- **SPACETIME**
- **ANENERGY**
- **$Ø_0$**
- **MASSLESS CHARGE**

VACUUM IS:

- **MADE OF UNQUANTIZED ACTION**
- **WITHOUT DEFINITE LENGTH INTERVALS**
- **WITHOUT DEFINITE TIME INTERVALS**
- **N-DIMENSIONAL (UNFIXED)**

We pause here to again summarize some important things we now know about vacuum.

Vacuum IS IDENTICAL TO virtual particle flux, spacetime, anenergy, Phi-subzero, massless charge, unquantized action, and infolded energy, momentum, length, time, power, velocity, acceleration, etc.

Vacuum is made of unquantized action, dimensionally.

It is without definite length or time, as Einstein stated.

It is n-dimensional, where n is always four or greater.

It is not an emptiness filled with things. Rather, it is identically a plenum filled with things which are totally unseparated, unfixed, and undetermined.

From vacuum: mass, energy, time, frames, and all the rest of physical reality are dynamically made.

Vacuum is the ether. The ether has never been eliminated from physics. Ether just has become much more subtle, and physicists have used other names for it.

Next Slide

The Tom Bearden Website

SLIDE 30.

VACUUM IS:

- **SPACETIME (L^nT, WHERE $n \geq 3$)**
- **CHARGE (MASSLESS)**
- **ELECTROSTATIC SCALAR POTENTIAL $\varnothing_0 \neq 0$**
  ERROR IN PRESENT THEORY
- **BROKEN BITS OF ENERGY (SUBQUANTAL)**
- **PURE VIRTUAL PARTICLE FLUX**
- **O-WAVE FLUX**
- **MULTILEVEL, STRUCTURED, PATTERNED**
- **A VIRTUAL PLENUM**
- **AN OBSERVABLE EMPTINESS**

Again, we list some of the things that vacuum identically is.

It is spacetime, massless charge, electrostatic scalar potential, broken bits (subquantal) of energy, pure virtual particle flux, zero-vector wave flux, multilevel, structured, patterned, a virtual plenum, and an observable emptiness.

It is all things and contains all things in potential state.

It is not, in that it is not observable. But from it comes all observables.

It is both ordered and disordered, simultaneously.

It involves four-law logic, not just three-law Aristotlean logic.

Next Slide

The Tom Bearden Website

SLIDE 31.

GRADIENT OF ELECTROSTATIC POTENTIAL

IN VACUUM

$$\nabla \text{Ø} \neq \ddot{E}$$

ON AND OF A MOVING CHARGED PARTICLE

$$\nabla \text{Ø} = \ddot{E}$$

Again I accent that, in vacuum in the absence of a charged spinning particle of observable mass, del-phi does not yield an Ë-field, and the conventional equations of EM are wrong in that respect.

In the presence of a spinning charged particle, in a del-phi which contains electron-vortex-holes to mesh with, the charged particle attaches itself to the moving del-phi flux gradient, moving itself with the river. This produces an Ë field. The Ë-field CONSISTS OF the smeared electron, it does not CAUSE THE MOVEMENT of the electron. It is an effect, not a cause. The conventional equation for del-phi equals E is correct for matter waves in electron gases; it is not correct in vacuum itself.

Next Slide

[The Tom Bearden Website](http://www.cheniere.org)

SLIDE 32.

IN A ∇Ø, A CHARGED PARTICLE MOVES ITSELF

∇Ø>0 IMPLIES A MOVING RIVER, AND THE CHARGED PARTICLE IS "HOOKED TO" THE RIVER



We show clearly on this slide that a spinning charged particle, when it hooks to a spin-hole in a del-phi river, MOVES ITSELF.

Note that a del-phi implies a "pressure difference" in phi-flux between two points. Therefore there is a moving river -- a gradient -- of phi-dot, moving from the higher pressure to the lower.

If a charged particle is attached to this moving river, it flows along with the river. It is just like putting a boat into a moving stream of water. If the boat "latches" to the moving water, it moves with the river.

Electron spin and spin vortexes in the del-phi mesh, to accomplish the "hooking" or "latching."

Once hooked into a moving river, the electron moves itself. One does not have to furnish work to move it.

If the river is accelerating, the electron will accelerate itself.

By cleverly gating such rivers into and onto sources of free electrons, one can directly produce free energy.

The extra energy comes from converting anenergy (massless charge, vacuum flux) to energy of a moving mass.

Next Slide

The Tom Bearden Website

SLIDE 33.

ELECTROMAGNETIC WAVES IN ELECTRON GAS IN A CONDUCTOR

- **VECTOR WAVES**
- **CONTAIN E, B FIELDS**
- **GENERATED BY SPIN COUPLING OF ELECTRONS WITH SCALAR WAVE "SPIN-HOLES"**
- **WAVES OF FORCE**
- **HERTZIAN WAVES**
- **TRANSVERSE WAVES**
- **WAVES OF ELECTRON PRECESSION**

Here we pause to summarize the characteristics of electromagnetic waves in the electron gas of a conductor.

First, these are vector EM waves in the accepted sense.

They contain E and B fields.

They are generated by spin coupling of electrons with spin-holes in a scalar wave delta-phi river. The electrons move themselves under that condition, producing work and forces.

They are waves of force or force field variations.

They are Hertzian waves.

They are transverse oscillatory, not longitudinal.

They are matter waves.

They are waves of electron precession.

Next Slide

The Tom Bearden Website

SLIDE 34.

ELECTROMAGNETIC WAVES IN VACUUM

- **SCALAR LONGITUDINAL WAVES**
- **VECTOR ZERO [Ö] WAVES**
- **WITHOUT Ë, B FIELDS**
- **INTERNALLY STRUCTURED**
- **PATTERNED**
- **MAY CONTAIN ELECTRON "SPIN-HOLES"**

Here we summarize the characteristics of electromagnetic waves in vacuum.

They are scalar longitudinal waves of alternate compression and rarefaction of the vacuum virtual particle flux.

That is, they are waves of electrostatic potential.

They are zero-vector waves.

They are internally structured and patterned.

They usually contain electron "spin holes" unless made in a fashion so as to make opposing spin holes that cancel each other.

Since they are pure phi-waves, they need not be limited in velocity to the speed of light.

They are hyperspatial waves.

They are waves in virtual state itself.

Next Slide

The Tom Bearden
Website

SLIDE 35.

DETECTION OF
TRANSVERSE AND LONGITUDINAL WAVES


ANT
NORMAL
EM
NORMAL XMTR
"transverse" EM wave
transverse oscillations induced in electron gas
DETECTION
(Actually a special type of scalar wave.)
ANT
no detection
NORMAL
EM
XLTR/XMTR
longitudinal EM wave
NORMAL DETECTOR
no transverse oscillations induced
special ant
SPECIAL DETECTOR
detects

In the top drawing on this slide, we show a normal transmitter putting out a normal EM wave, which received in a normal antenna/receiver. What we call a "transverse" wave rigorously exists only in the electron gas in the transmitting antenna and in the electron gas in the receiving antenna. Specifically, a longitudinal wave exists in the vacuum in between the two antennas. However, due to the method of production, the longitudinal wave contains spin-holes for electrons, so the electrons in the receiving antenna readily couple with the wave by falling into and meshing their spins with the spins of the spin-vortex holes. Electron precession produces electron gas waves that are transverse oscillatory, hence Hertzian waves in nature.

In the bottom drawing, we show a translator/

transmitter. In other words, we oppose ordinary EM waves in a sum-zero substructure, deliberately producing longitudinal EM waves in vacuum with the spin-hole vortexes canceling each other. This type of wave does not "hook" spinning electrons in the normal receiving antenna, and thus it is not detected. The normal antenna/receiver system never sees it at all.

However, by means of a special antenna which generates nonlinear phase shifts in the composite substructure waves, "hooking" holes are restored in an oscillatory nature. Electrons then hook with this output and detect the wave.

Note that it requires a two-stage detector, operated in an interferometer fashion, to detect this pure scalar wave.

Next Slide

The Tom Bearden Website

SLIDE 36.

CREATING A "RIVER" OF ANENERGY



PROVIDE TWO "LOCKED-IN" SEPARATED ϕ-SOURCES OF DIFFERENT MAGNITUDES

"RIVER" OR FLOW VECTOR OF VIRTUAL PARTICLES

$\nabla\phi$ IS A REGION OF CURVED SPACETIME, AND ENERGY IS NOT CONSERVED

IN VACUUM, THIS IS NOT YET A VOLTAGE DROP (NO MASS FLOW),
NOR IS THERE AN Ë-FIELD

Now if we wish to get free energy, we are going to have to provide a continuous anenergy river, and a means of tapping it to produce mass movement.

This slide shows one easy way to make an anenergy river.

We simply pump some electrons (spray nozzles) onto an elevated charged ball, and we LEAVE them there. A second ball is connected to ground. A higher phi -- that is, a denser spray -- is now in the vicinity of the elevated ball on the left. A lower phi -- that is, a less dense spray -- is in the vicinity of the lower ball on the right. Between the two balls, now, there is a gradient in phi, and a virtual flux flowing from the "higher virtual pressure" to the "lower virtual pressure."

This del-phi river does NOT constitute an Ë-field, as we have previously pointed out.

The del-phi region, however, is definitely a region of curved spacetime. As is well known from general relativity, in such a region energy need not be conserved.

Therefore it is entirely possible -- consistent with ordinary physics -- to violate conservation of energy in this del-phi river, if one believes general relativity. If one argues adamantly that conservation of energy cannot be violated under any circumstances, then one must throw out general relativity. Also, one must throw out most of particle physics, whose explanations presently involve virtual interactions, each of which violates the conservation of energy.

Next Slide

The Tom Bearden Website

SLIDE 37

A 2-WIRE SYSTEM IS CONSERVATIVE



- HAS LOSSES
- DOES NOT BREAK EVEN
- DOES NOT PRODUCE FREE ENERGY

ELECTRON "SPRAY NOZZLES" DISSIPATED

REPLENISH SPRAY NOZZLES BY PUMPING MORE ELECTRONS. (MOVING ELECTRON MASSES AGAINST A "SPRAY PILEUP" REQUIRES WORK.

Here we show that, as engineers, we've all been tricked into releasing our virtual rivers so that we would not discover free energy.

While I cannot prove this as yet, I tentatively suspect that J. P. Morgan and Thomas Edison are directly responsible for this occurring. Tesla utilized a single-wire system; we have all been taught to utilize only two-wire systems.

What we in effect do is connect a wire or circuit to our charged ball, allowing our hose nozzles to drain away.

In other words, we first do some work to pump hose nozzles (electrons) into and onto our elevated reservoir, so we will obtain a denser flux, and a flux river to utilize. Then we release the nozzles themselves, and let THEM move on the flux river, deplenishing our river. Of course we can get back as much energy as we pumped up there in the first place. But this two-wire system is at best theoretically even. Since real circuits have losses, we can never even quite break even. Thus we have to continue to pump hose nozzles, and let them bleed off to provide energy, in a less-than-100% fashion.

By foolishly releasing our hose nozzles, we guarantee that we will never achieve free energy. And that's nice, because the people who control things, and for their own wealth and power depend on selling us energy at high prices, are guaranteed to stay in power and control.

One is never truly free unless one is energy independent, in a self-contained fashion.

Tesla nearly succeeded in giving us free or very cheap, inexhaustible energy -- and for that reason was quickly and dramatically suppressed.

Only three graduate schools of electrical engineering existed in the U.S. The only one of any real importance was at Columbia University.

Only one or two professors were necessary to "reach" to modify and subtly direct the entire foundations of the emerging electrical theory.

Professors were in general poor, and had no research funds unless some rich industrialist or philanthropist gave them a few dollars.

The setup then was certainly very ripe for Morgan and Edison to stop free energy, and suppress Tesla at the same time. They could have done so by influencing only one -- or at most two -- theoreticians at Columbia.

At any rate, the theory was developed in such fashion as to rule out the single wire circuit and the longitudinal wave. Free energy was suppressed, and the financial empires of Morgan and Edison stayed secure.

Next Slide

The Tom Bearden Website

SLIDE 38.

A HOLLOW CHARGED SPHERE


A FREE
ANENERGY
PUMP
$\nabla\phi$ INSIDE = 0
ϕ INSIDE > ϕ_0
TRAPPED
CHARGES
TRAPPED
ANENERGY
WIRE
$\nabla\phi \neq 0$
ϕ_0

Here we show another easy source of a higher vacuum charge, hence an easy source for a free river.

Simply charge up a sphere. As is well known, inside that sphere one has no del-phi. So one can introduce an electron therein and not produce an Ë-field .

However, since we've piled up additional spray nozzles, the density of the spray inside the sphere (as well as outside it) is certainly higher.

In other words, the inside of the sphere is also a source
for an increased del-phi river. In the bottom drawing, we drill
a tiny hole in the sphere, insulate a thin wire running into the inside of the sphere, and run the wire out to a terminal opposing another grounded terminal. Between the two terminals now there must exist a del-phi river.

And between those terminals there now exists a curvature of spacetime, hence the theoretical possibility to obtain free energy without violation of principles.

Next Slide

SLIDE 39.

ONE-WAY GATE VALVE

(ANENERGY TO ENERGY)



IF PROPERLY OSCILLATE ø-APPLICATION, GET STEADY EMISSION (MORAY EFFECT)

IN A TRAPPED ø-FIELD, ELECTRON CAN LIFT ITSELF TO AN EXCITED STATE. REMOVING THE ø ALLOWS DECAY, WITH EMISSION OF A NORMAL PHOTON

ANENERGY (ø-FIELD) IS CONVERTED TO ENERGY, YIELDING "FREE ENERGY" FROM THE VACUUM

- SIMILAR THING IN NUCLEUS
- TRANSMUTE ELEMENTS (KERVRAN EFFECT)
- SPEED UP RADIOACTIVITY (REICH EFFECT)

Here we show one way to provide a one-way gate valve from a del-phi river to energy released into the outside world.

By providing a properly tuned, oscillating phi wave, one can cause an orbital electron in an atom to raise itself to an excited state. Remember, in a del-phi, an electron that hooks to it raises itself.

We then switch out the phi application, and the excited electron decays in normal fashion, emitting a normal photon of energy.

By phase locking the processes, one produces a steady stream of photons.

By absorbing or directing the photons, one can produce heat, light, energy beams, etc.

By this means, one produces free energy by gating anenergy into energy.

And if one does not release spray nozzles in the phi-oscillations which feed the mechanism, one has an inexhaustible energy production.

A very similar thing can be done with the excited states of the nucleus. For example, by using a radioactive material with a predisposition to emit some particle -- say an electron -- the nucleus can be made to continually emit the particles WITHOUT ITSELF DECAYING INTO BYPRODUCTS. In other words, an electron is lifted from the Dirac sea of vacuum to instantly replace the electron emitted from the nucleus.

This provides a one-way gate valve from the Dirac sea to the external universe.

Theoretically, these mechanisms are no more mysterious than a hydraulic ram, which raises water higher than the stream that feeds the ram.

In the 20's and 30's, T. Henry Moray successfully built such gating devices for converting vacuum anenergy to external energy.

In the Kervran effect, living systems are able to directly transmute elements, even though they only possess feeble energies, by influencing the virtual particle interactions in the nucleus that furnish its binding energy.

Reich used an adaptation of a cloudbuster -- which emits scalar waves -- to drastically speed up radioactive decay of radioelements.

Both plants and animals transmute elements by similar processes.

Next Slide

TOWARDS A NEW ELECTROMAGNETICS
PART 4: VECTORS AND MECHANISMS CLARIFIED

SLIDE 40,

SIMPLE FREE ENERGY MOTOR

BATTERY RECHARGES ITSELF


BATTERY
DC SERIES MOTOR
SENSOR
CONTROLLER
WORK
ENERGIZER
$\emptyset_1$ (MASSLESS)
BATTERY POWER TO MOTOR
$\emptyset_1$ TO BATTERY TERMINAL

On this slide, we show a theoretical scheme which several researchers have discovered and used to build simple free energy motors.

In this scheme, we drive an ordinary d.c. series motor by a two wire system from an ordinary battery. The motor produces shaft horsepower, at -- say -- some 30 or 40 percent efficiency, compared to the power drained from the battery. This much of the circuit is perfectly ordinary.

The trick here is to get the battery to recharge itself, without furnishing normal power to it, or expending work from the external circuit in the process.

To do this, recall that a charged particle in a "hooking" del-phi river moves itself. This is true for an ion, as well as for an electron. We need only make the del-phi in correct fashion and synchronize it; specifically, we must not release the hose nozzles we utilize to produce our del-phi river or waves.

The inventors who have discovered this have used various variations, but here we show a common one.

First, we add an "energizer" (often referred to by various other names) to the circuit. This device makes the del-phi waves we will utilize, but does NOT make currents of electron masses. In other words, it makes pure Ø-dot. It takes a little work to do this, for the energizer circuit must pump a few charges now and then. So the energizer draws a little bit of power from the motor, but not very much.

Now we add a switching device, called a controller, which breaks up power to the motor in pulses. During one pulse, the battery is connected and furnishes power to the motor; during the succeeding pulse, the battery is disconnected completely from the motor and the output from the energizer is applied across the terminals of the battery.

If frequency content, spin-hole content, etc. are properly constructed by the energizer, then the ion movements in the battery reverse themselves, recharging the battery. Again, remember that these ions MOVE THEMSELVES during this recharge phase. Specifically, we are NOT furnishing ordinary current to the battery, and we are not doing work on it from the energizer.

If things are built properly, the battery can be made to more than recover its charge during this pulse cycle.

To prevent excess charge of the battery and overheating and destroying it, a sensor is added which senses the state of charge of the battery, and furnishes a feedback signal to the controller to regulate the length of recharge time per "power off" pulse. In other words, the system is now self-regulating.

The relation between power pulses and recharge pulses is shown on the graphs at the bottom. Note that regulation may decrease the time of recharge application of the del-phi river.

This system, if properly built and tuned, will furnish "free shaft energy" continually, without violating conservation of anenergy. Remember that the del-phi condition across the battery terminals means that spacetime is suddenly curved there, and conservation of energy need no longer apply.

Again, this system is consistent with general relativity and with the fact that Ø-field alone can drive a situation relativistic. We have deliberately used these facts to do direct engineering. Our "extra energy" comes from shifting phi-flux -- the energy of the universal vacuum spacetime -- directly into ordinary energy for our use. Thus we draw on an inexhaustible source, and our device is no more esoteric than a paddlewheel in a river. The only difference is that, in this case, we have to be clever enough to make and divert the river in the right timing sequency.

This is a free energy device which an ordinary person, who knows a little electronics, can experiment with in the basement. To develop it, one is talking several thousands of dollars and a lot of persistence and tinkering; one is not talking millions.

WARNING: THE PRECEDING EXPERIMENTS ARE HAZARDOUS. DO NOT ATTEMPT THESE EXPERIMENTS UNDER ANY CIRCUMSTANCES UNLESS YOU ARE AN EXPERIENCED ELECTRICAL RESEARCHER, EXPERIENCED IN PERFORMING EXPERIMENTS WITH LEAD-ACID BATTERIES AND PULSE CHARGE AND DISCHARGE OF SAME, AND UNLESS YOU ALSO USE ALL SAFETY PRECAUTIONS SUCH AS GOGGLES

AND PROTECTIVE GLOVES, SLEEVES, AND APRON. YOU MUST NOT HAVE OTHER INFLAMMABLE LIQUIDS OR OTHER SUBSTANCES PRESENT WHICH COULD BE IGNITED AND BURN OR EXPLODE. SURGED LEAD-ACID BATTERIES PRODUCE HYDROGEN GAS, WHICH CAN EASILY EXPLODE SINCE SPARKING ALSO CAN OCCUR. THE ACID FROM SUCH AN EXPLOSION CAN EASILY BLIND YOU IF IT GETS IN YOUR EYES, AND IT CAN BURN YOUR SKIN. IN ADDITION, LEAD AND LEAD COMPOUNDS ARE POISONS, AND ARE TO BE HANDLED ONLY BY EXPERIENCED RESEARCHERS. THESE EXPERIMENTS ARE NOT FOR AMATEURS UNDER ANY CIRCUMSTANCE, BUT ONLY FOR EXPERIENCED PROFESSIONALS WITH PROPER KNOWLEDGE AND TRAINING, AND USING PROPER PRECAUTIONS. NEITHER THE AUTHOR NOR THE PUBLISHER IS REPONSIBLE OR LIABLE FOR ANY ACCIDENTS OR DAMAGE YOU MAY ENCOUNTER, AND ALL EXPERIMENTATION WITH THESE DEVICES AND PROCEDURES IS AT YOUR OWN ASSUMED PERSONAL RISK.

Next Slide

SLIDE 41.

THE TRANSLATOR



We now turn to a fundamental concept we need in order to understand some of the effects used by the Soviets in their Tesla weapons.

Note that one other country -- one not hostile to the U.S. -- also has such weaponry.

This slide shows the concept of a TRANSLATOR. Briefly, if we input a transverse matter wave, the translator outputs a scalar longitudinal wave without spin vortex hooks. If we input a scalar longitudinal wave -- even one without hooks -- the translator puts out a normal vector transverse matter wave.

We define a translator as anything which will accomplish one or both of those functions (usually both).

Basically, any device which is TOTALLY nonlinear to transverse waves will produce scalar waves from a transverse wave input. Any device which is totally nonlinear to longitudinal waves will produce transverse waves from a longitudinal wave input.

It is comparable to certain plasmas, which, as is well
known, produce such a translator effect. If you input longitudinal waves, you get transverse waves. If you input transverse waves, you get longitudinal waves. And the plasma is rather totally nonlinear.

Again, if our translator outputs non-hooking waves, it means that the component substructure waves oppose each other in sum zero fashion, and "kill" or nullify the vortex spin-holes.

Next Slide

The Tom Bearden Website

SLIDE 42.

TRANSVERSE WAVE INTERFERENCE



On this slide we show "normal " transverse wave interference, as we presently teach it in our textbooks.

We visualize two identical transmitters, each producing a beam in a pattern of about 55 degrees of so.

Where these beams overlap -- in the ideal, perfect case, we have constructive and destructive interference, with absolute zero-vector linear regions being formed. We put in the energy, and out-of-phase interference creates the zero zones, which contain no energy as such.

We point out, however, that these zero-lines are scalars,
and contain high stresses on spacetime.

Next Slide

The Tom Bearden
Website

SLIDE 43.

LONGITUDINAL WAVE INTERFERENCE [SCALAR WAVES]


XMTR #1
XMTR #2
$\bar{0}$-WAVES
$\bar{0}$-WAVES
ZERO ENERGY LINES
ENERGY BOTTLE
(Interference zone)
VECTOR ENERGY ZONES

On this slide we show the interference pattern that emerges from the interference of two identical scalar wave beams from translator/transmitters.

Now note we are interfering two zero-vector waves, each containing a substructure. In this case we assume similar substructures.

What happens now is that we get a similar interference pattern, but with some startling differences.

First, we put in the zero-lines. These represent in-phase conditions for the substructures.

. Second, the substructures themselves interfere, and form energy in the grid zones between intersecting zero-lines.

In the perfect case, however, this energy cannot radiate away. It is physically created and trapped as if in an "energy bottle." We are CREATING this energy at a distance, and storing it in a bottle. If the bottle were perfect, we would continue to accumulate energy in the grid zones -- notice we are continuing to pour energy into both transmitters, and there is zero ordinary energy anywhere else except in the grid zone "bottles."

If we turn off the transmitters smoothly, we extinguish the energy in the bottle completely. It is sucked right out of there, and the vacuum returns to its normal condition.

If we erratically and nonlinearly turn off the transmitters, we destroy the bottle and "dump" the energy suddenly. This is exactly like a sudden EMP from a nuclear weapon. A sudden pulse of energy is freed to radiate and interact in the region where the bottle was.

The high altitude booms off the East coast of the U.S. a few years ago were made in precisely this fashion, from such a weapon being adjusted and calibrated in the Soviet Union.

Next Slide

The Tom Bearden Website

SLIDE 44.

CREATING ENERGY AT A DISTANCE

(Use of Hidden Information Content of the Field)

(Can Provide Action-at-a-Distance)



ϕ_1

ϕ_2

Note:
Whittaker's 1904 paper initiated the entire field of superpotential theory.

Interference Zone
(Potential gradients)
Normal EM Energy:
May be positive, or negative, or fixed

Hidden
Bidirectional
EM energy flow

Hidden
Bidirectional
EM energy flow

Scalar Potential
Beams

XMTR

XMTR

Whittaker/Ziolkowski
Transmitter Arrays

(8 to 20 harmonic wavepairs each)

© T. E. Bearden 1994, 1999

Figure 5. Scalar potential interferometry (between the two sets of bidirectional longitudinal EM wavepair functions) produces all EM force fields and waves.

But let us look at one way to do this sort of thing more efficiently.

Here we show two scalar transmitters (that is, two translator /transmitters) which form narrow beams, and which cross those beams at a distance.

In the crossing zone, scalar interference is established, making an energy bottle and producing trapped or locked in energy.

If I have a physical target in that crossed zone, I can
literally "fry" the target, for I get all the power inputted to the transmitters contained in the bottle zone. I don't have any square law losses.

I can heat a metal object white hot at a distance, for example. Because all real bottles are slightly imperfect, the real bottle is leaky and some photons escape. I can observe the white hot steel in the bottle, and I can record and measure the temperature from the escaping photons, by simple radiometric methods.

Now if I smoothly turn off both transmitters linearly, all the energy in the bottle disappears immediately. I can immediately reach in and pick up a black, cool piece of steel. And that cannot be done with ordinary inductive or radiowave heating.

That has been done in a laboratory on the North American continent.

Next Slide

The Tom Bearden Website

SLIDE 45.

NONLINEARITIES CAUSE SHIFTING [PARTIAL TRANSLATION]


TRANSVERSE VECTOR WAVE
REAL OBJECT
WITH NONLINEARITY
VECTOR WAVE
SCALAR COMPONENT
LONGITUDINAL SCALAR WAVE
REAL OBJECT
WITH NONLINEARITY
SCALAR WAVE
VECTOR COMPONENT

Here we show the results of electrical nonlinearities in an object which encounters a true translated (non-hooking) scalar wave. All objects have some electrical nonlinearities in them, and so all act partially as translators.

This means that any real object creates a small scalar aura around itself from its continual temperature interactions -- from absorbing and radiating ordinary EM waves. In addition, the object normally is subject to undetected scalar wave radiations, and so it also produces a small aura of transverse vector waves around itself by translation.

All real objects accomplish at least a little bit of translation.

Next Slide

TOWARDS A NEW ELECTROMAGNETICS
PART 4: VECTORS AND MECHANISMS CLARIFIED

SLIDE 46.

THE SCALAR AURA


INCIDENT
HERTZ WAVES
REAL OBJECT
WITH
INTERNAL
NONLINEARITIES
TRANSLATED
SCALAR
LONGITUDINAL WAVES

We examine now an object with temperature, that is, a normal object continually absorbing ordinary EM radiation and continually emitting EM radiation.

The object has a small fraction of its incident energy expressed as a scalar aura around it, because of translation. Note that normal detectors will not detect this aura, but special two-stage interferometric detectors will detect it. Also note that the object replenishes- the ordinary radiation flow by its translation of some of its incident scalar radiation into the normal or "transverse" (so-called) radiation.

The entire internal pattern -- all interactions and functions of the body -- are precisely present in its scalar aura, down to the finest detail. This makes an x-ray pale by comparison.

True psychics actually use the nonlinearity of their nervous systems (note the avalanche ion discharges across dendrite gaps) and the interferometric aspects (note two cerebral hemispheres, connected by a corpus callosum) to detect the scalar aura. This is a physical fact and not esoteric delusion. To control this, however, is normally as difficult as learning to walk a high wire and do acrobatics on it. There are not many high wire walkers in the world, but it certainly is a skill within human control capability and purview.

T. Galen Hieronymus was absolutely correct when he stated that the entire internal working pattern of an object is radiated by that object in terms of an extraordinary energy, which he called "eloptic" energy. It is actually translated scalar wave energy, and entirely consistent with present EM theory when the glaring errors in its foundations are corrected.

Shortly I hope we will see instrumentation which can directly examine the scalar aura in the finest detail, seeing every illness, and simply setting dials to radiate the body with gentle, harmless scalar waxes to directly correct illnesses.

Next Slide

The Tom Bearden Website

SLIDE 47.

VIRTUAL FLUX AND MAGNETIC FIELD [LINEAR CASE]


NONZERO SUMMATION GIVES MAGNETIC FIELD
MICRO MAGNETS (DOMAINS)
N S
OBSERVABLE STATE
VIRTUAL STATE
VIRTUAL FLUX
QUANTUM THRESHOLD
BAG (SNAPSHOT) AROUND A VIRTUAL MAGNET

Briefly, let's look at some nice things we can do with magnetism. Specifically, let's find out how to make magnetic monopoles and use them to do things in the laboratory. This again has been done in a laboratory on the North American continent.

First, about all the present science can tell us about a magnet is that "a big magnet is made of littler magnets." And if we examine one of the smaller magnets, it's made of even smaller magnets. This is like saying big dirt piles are made of smaller dirt piles, and that explains what dirt is.

However, let's use that with our knowledge of the virtual flux vacuum.

In this slide, we show diagrammatically the situation for a common magnet. Note that domains in the magnetic material are themselves little magnets, and their alignment and vector summation determine whether or not there's said to be a magnetic field present. Nonzero summation states that there's a resultant magnetic vector, and hence an external magnetic field. Zero summation states there's no external nonzero resultant, hence no external magnetic field.

Actually, there's an external scalar magnetic potential field, even when the external vector magnetic field is zero. The substructure is still there.

If we pursue this "big magnets are composed of smaller magnets," eventually we reach the quantum threshold, and we have a substructure of virtual, subquantal magnets in vacuum, in the virtual particle flux. At least we conceive each little virtual particle as if it were spinning, and hence a little magnet.

We put a conceptual bag around each little virtual magnet.

In a linear situation, the north pole is as strong as the south pole, and so just outside the bag, the poles cancel or appear zero. Since the virtual bag appears to be zero length to an external macro observer, the poles seem to be directly superposed on top of each other, yielding no pole at all to the observer.

However, you and I now know that both poles are still in there, in the virtual substructure, and we certainly have remaining with us a translated scalar magnetic field.

There's a virtual flux to and from each observable particle of charged mass in the observable state as shown, but this flux is now scalar in virtual magnets, except for nonlinearities in the structures above the quantum level. Thus accelerated portions -- atoms with electrons in whirling orbit, spinning electrons, protons, etc. -- possess nonzero ordinary vector magnetic fields by translation. Again, notice the successive interlocking levels of reality, all the way from deep in the virtual state into interlocking levels in observable state.

Next Slide

SLIDE 48.

PRODUCING MAGNETIC MONOPOLES


NODAL POINTS
N
S
N
S
SUSTAINED BY INPUT
STANDING WAVE INTERFERENCE IN TARGET MATERIAL
OBSERVABLE
VIRTUAL
QUANTUM THRESHOLD
(N)
N S
(N)
N S
(N)
N S
(S)
S N
S N
N S
NONLINEAR

Now let us look at a non-linear case of the same sort of thing. Now the bags are still around the little virtual magnets, but they are nonlinear. This means that, to an observer outside the bag, one pole seems bigger or more powerful than the other. In other words, to the quantum observer, this bag appears to be a magnetic monopole at a point.

In the flux still on and off each observable spinning charged mass, we now have a steady component of "monopoles". If we have a standing scalar wave present in a physical material in which the nonlinearity exists -- and the scalar waves can even be PRODUCING that nonlinearity -- we will have nodes available at which the monopoles will congregate and emerge and interact.

North monopoles will congregate at one node, while south monopoles will congregate at the next, and so on in alternating fashion.

That means that, at anyone node, monopoles of the same kind are steadily being "deposited" in the material. These monopoles strongly repel each other, and so the material at that node is increasingly stressed in a tensile fashion.

Eventually the material will be torn apart at the node,
stress relieving the situation. Movement of the material will release the nonlinear condition, stopping monopole production and deposit. However, at a break node, the same kind of magnetic pole will appear on each side of the break.

That is, the breaks will be N-N, S-S, N-N, S-S, etc.

An ordinary magnetic does not do that when it breaks. Instead, it breaks N-S, N-S, etc.

Next Slide

The Tom Bearden Website

SLIDE 49.

BREAKING METAL WITH MAGNETIC MONOPOLES



Again, metal has been broken in a North American laboratory utilizing the production and deposit of magnetic monopoles in this fashion.

On this slide we show what was done.

An ordinary bar of steel was exposed to standing scalar
waves in a nonlinear situation, depositing magnetic monopoles at the wave nodal points in the metal bar. The breaks occurred as shown on this slide.

Much of what I am presenting is based on certain experiments accomplished in experimental laboratories here and abroad. Most of the mechanisms have actually been produced in the lab. However, these are proprietary labs and I cannot violate trust and reveal the precise construction details utilized. In some cases I have not seen the precise constructions, but only the direct results.

But ironically, the production of magnetic monopoles -- which has fiercely resisted the normal scientific approach -- yields readily to the new approach.

Next Slide

The Tom Bearden Website

SLIDE 50.

CREATING AN INERTIAL FIELD (ANTIGRAVITY)



We now show schematically how to produce an inertial field, or antigravity. Also an inertial space drive can be produced in this manner.

This again has been done in a North American laboratory. In fact, inertial fields have been produced in more than one lab here in North America.

In the setup shown here, three translator/ transmitter projectors are used and oriented so as to give three-dimensional interference, or interference along all three spatial axes.

By controlling the substructures of the three projectors all together, one can control the precise phasing in all substructures, with respect to a common time reference.

By this means, a unilateral force can be created of each and every charged mass particle (that is, on each proton) in the nucleus.

Since we know that the neutrons and protons in a nucleus of an atom are continually interchanging, one into the other, back and forth, all of the nucleons can be treated as "diffuse protons" for mass purposes, and scalar wave interaction purposes.

Thus if we have the correct pattern to affect protons, we can control the phases of the substructure waves of the projectors so as to produce unilateral, parallel forces on and of each spinning proton in the nucleus.

This means we can produce unilateral thrust in an object exposed to the triad interference of the projectors.

In short, this produces antigravity. If sufficient force is produced, the test object in the interference zone simply lifts itself off against earth gravity. This has been done in North America.

If we phase the projectors so that counterbalancing forces are produced on each proton, we can either make the proton "lighter" inertially or "heavier."

In fact, we could "freeze" a common pistol so that it could not be moved and its trigger could not be pulled, simply by sufficiently increasing its inertia. This was done in experimental demonstrations in Toronto, Canada in 1969, and witnessed by the Chief of the Homicide Squad of the Toronto police. It was his pistol that was frozen for the demonstration.

If the projectors themselves are on board a space capsule, for example, they can produce such a unilateral thrust in and of a central mass or disc attached to the of the craft. By this means, an inertial spacedrive can be built.

Next Slide

The Tom Bearden Website

SLIDE 51.

EFFECTS ON HUMANS



Now let us look at some of the effects on humans, when radiated with a true scalar wave beam from a translator/transmitter.

First, the human nervous system is highly nonlinear. Essentially, across billions of synapses, sudden ion discharges -- analogous to spark discharges -- are continually or periodically occurring. Brain waves, for example, are not waves along wires; instead, they are waves of avalanche discharges across tremendous numbers of nerve cell gaps.

The central nervous system is thus highly nonlinear, and the gap firings of the nerve endings act as translators.

These translators partially translate incident scalar waves, so that additional transverse matter waves -- or ordinary energy inputs -- occur in the ion discharges.

Thus additional energy is being added to the nervous system by incident scalar waves.

Many long-term effects of the environment on the body are gradually kindled in this fashion, even over a period of years.

For a stronger dosage of scalar waves, the nervous system experiences "jamming" of its signals. This leads to four basic "noise jamming" effects.

If a small dose is absorbed, the interference is slight. One feels as if one had taken a whiff of anaesthesia -- an unreal, dreamy feeling.

If a slightly larger dose is absorbed, the interference is moderate. Now the single channel system -- the motor system -- goes, and the individual is paralyzed. Mentally he is barely conscious, in a sort of hypnogogic, waking dream state. Any tendency toward epileptic seizure or other nervous disorder may surface here, as may heart palpitations or even heart failure.

For a heavier dosage yet, the interference is now strong. Now the multiple systems start failing. Consciousness is lost and the individual is in a deep coma. In addition, seizures and convulsions, and loss of control of some body functions, may occur. The autonomic nervous system is keeping the heart beating with difficulty and keeping the body gasping for breath.

For a very strong dosage, the entire nervous system fails and death results almost immediately. This is quite similar to the effects of nerve gas.

These are the four major symptoms of scalar wave radiation of the body and translating absorption by the nervous system in an uncoordinated fashion.

Next Slide

The Tom Bearden
Website

TOWARDS A NEW ELECTROMAGNETICS
PART 4: VECTORS AND MECHANISMS CLARIFIED

SLIDE 52.

INITIATING SPECIFIC BIOLOGICAL EFFECTS


NOTE:
• PAVLITA'S 64 POINTS
• ADAMENKO'S PLEXUSES
CONTROLLED SPECIFIC EFFECTS
XLTR/ XMTR
MODULATION
HUMAN TARGET
SELECTOR FREQ, PATTERN

If we now add precisely patterned modulations to the substructure waves of the scalar zero vector beam, we can induce deliberate patterns in the dosage absorbed by a biological system.

As Kaznacheyev's experiments showed, any death or disease pattern can be induced upon an electromagnetic carrier -- specifically, upon the near-ultraviolet as an example. Some of his experiments were duplicated at the University of Marburg in West Germany, utilizing infrared carriers. These patterns can be dumped into cell cultures, eventually kindling the pattern of death or disease in the target cells.

The same can be done to a human from an external source. The major entry point is the acupuncture system, which reacts to scalar waves and transfers them to the nervous system for translation.

Pavlita, Czechoslovakian engineer, has built "psychotronic generators" for over 30 years that affect the human body. Adamenko, Soviet physicist, found that the acupuncture points formed groupings or plexuses that were frequency sensitive. In other words, certain frequency bands affect one plexus more than others. Further, these acupuncture points are known to be connected to effects produced at remote locations in the body.

Pavlita stated he had found 64 different sensitive "points" on the body, and had succeeded in building a generator for each. If by his points he meant Adamenko's plexuses, then frequency patterns can be created that affect certain acupuncture groupings -- and thereby certain specific body locations and effects -- more than others.

It thus appears reasonable that, by placing the proper frequency pattern in the modulations of the substructure waves feeding into the translator/ transmitter, the scalar ray or beam can be made highly selective as to body part affected and the effect generated or kindled in the body.

By this means, specifically tailored attacks on the body can be created.

Strong emotions such as sheer terror, overpowering rage, blind panic, etc. can be induced. Or physical effects such as epileptic seizure, loss of control of internal functions, loss of muscular control, severe weakness, specific failure of an individual organ such as the heart or liver, or blackouts and comas can be induced. In addition, patterns for specific toxins and diseases can be induced. With a strong absorption, these changes can be effected quickly. Imagine bubonic plague developing in 30 seconds, for example, or the effects of a cobra bite developing in 10 seconds.

If the individual is placed in crossed interference beams (that is, in the interference zone of a scalar interferometer), strong effects can be produced essentially instantly, including instantaneous death.

Of course BENEFICIAL effects can also be accomplished. As instrumentation is developed, one should be able to scan the aura, do a computerized readout to show the different medical problems either developed or developing in the body, have the computer compose a "cancellation or offsetting pattern," and radiate the body with a totally beneficial pattern, customized for that particular condition at that particular time. One should be able to quickly cure cancers and leukemias, for example, even of the brain and of the bone marrow. One may even be able to quickly reverse the effects of aging; at least there is no foreseeable reason why it should not be possible.

The new technology is a very powerful tool, and it can be used for either good or bad, depending upon the intent of the developer and the user.

Next Slide

The Tom Bearden Website

SLIDE 53.

GROUND-TO-AIR USE



Here we show another use of the scalar beam technology already developed by foreign powers.

A modified track radar -- either continuous wave or pulsed -- transmits a scalar wave beam. It radiates an incoming hostile aircraft, keeping the beam on it, and kindling energy in the nonlinear electronic circuits of the aircraft by translation. Communications, navigation systems, avionics systems, electronic fuze systems, ignition and control systems, airborne radar, missile armament electronics, etc. are all vulnerable to this translation kindling of internally jamming energy from the incident scalar beam.

The electronics can be knocked out and the aircraft knocked down.

The pilot himself is also vulnerable because of his highly nonlinear central nervous system.

Some or all of the eight F-111's mysteriously

lost in
Vietnam may have been bagged by modified SA-2
FANSONG radars, using this effect.

Next Slide

The Tom Bearden Website

SLIDE 54.

TACTICAL AIR-TO-GROUND USAGE



As shown on this slide, the technology is also usable from aircraft against ground targets, particularly ground-based radars and communications systems.

As shown, the aircraft has a modified jammer, able to emit a beam of scalar energy from one or more translator/transmitters.

By simply training a beam on the radar, eventually the radar can be knocked out. That is the simplest use.

A more sophisticated usage is provided by more than one translator/transmitter, acting as a scalar interferometer.

In this mode, each translator/transmitter emits multiple scalar carrier frequencies. Two Fourier expansions are established, so that a three dimensional "ball" or sphere of interference-zone energy is established. By pulsing or phasing, this ball is moved to strike the location of the radar, delivering a large burst of energy to it and knocking it out. Alternatively, the energy bottle is "dumped" when it reaches the targeted radar or its near vicinity.

A still better way is to fire one Fourier scalar pattern directly at the target radar, then fire a second pulse faster so that it overtakes the first directly upon the target. (The ensemble of such a pattern acts as a soliton, and its velocity is controllable by controlling the amplitude of the pattern generated).

When the second scalar overtakes the first, a sharp interference is formed, with a fast energy bottle, which is then nonlinearly dumped in microseconds or milliseconds. In this fashion, all the energy put out by the jammer is delivered directly upon and into the target in one sharp EMP pulse, much like that from a small nuclear explosion. The target is destroyed.

Note that such a weapon can be utilized against tanks, vehicles, explosives, missiles, ammunition, bridges (the airblast), bunkers (the blast can occur INSIDE the enclosure), ships, planes, personnel, and targets of varied types.

The Soviets have had such secret weapons for years.

One additional country has them also.

Next Slide

The Tom Bearden
Website

SLIDE 55.

INTEGRATED WEAPONS DISPLAY (MODIFIED JAMMER)



Here we show diagrammatically what a modified Soviet integrated weapons display for a modified jammer might be, to employ scalar interferometer weaponry.

As the "main bang" is emerging from the antenna of the
target radar on the ground, the phi-field from it reaches to infinity, including through the aircraft with a finite magnitude. In the a1rcraft, two channels act in interferometer fashion as a scalar detector for phi-dot. The main bang creation (phi-dot) is detected, and displayed as the leftmost pulse.

At that time, a computer time-base starts clocking off microseconds.

At some time later, the third channel, acting as a normal receiver, receives the ordinary "Hertz" pulse from the radar, which has traveled to the aircraft at the speed of light.

The computer converts elapsed time between the scalar pulse and the Hertz pulse to range.

Azimuth and elevation angle to the radar are obtained by normal angle tracking.

At this time, the computer has the exact coordinates of the radar, allowing for motion of the aircraft during the lapse time.

The computer switches the interferometer into transmit mode, and arranges amplitude patterns to target the radar.

It fires the first scalar pulse, then fires the second so as to create the full EMP directly upon the target.

The EMP flash occurs, destroying the radar.

At that time, another target can be processed.

In a more advanced weapon, scanning may be used to detect, locate, target, and engage multiple targets, including incoming air-to-air and surface-to-air missiles, one after another.

The same weapon is usable against a variety of aerial and ground based targets.

The major weapon is the electronic emitter, not a missile or ordinary ordnance.

Hordes of such special "jammer aircraft" now become a potent force on the battlefield, destroying all before them with annihilating ray weapons.

Star war is a reality now.

The High Frontier is already seriously obsolete.

Our entire defense establishment is completely vulnerable to these weapons at present, for we have not developed countermeasures or defenses.

Next Slide

The Tom Bearden
Website

TOWARDS A NEW ELECTROMAGNETICS
PART 4: VECTORS AND MECHANISMS CLARIFIED

SLIDE 56

RADAR INVISIBILITY


energy captured
(no reflection)
ACQ RADAR
ENERGY BOTTLE
(Interference pattern
between fourier
expansion patterns)
TRACK
RADAR

On this slide we show another effect which can be obtained. We can make an airplane invisible to ordinary radar.

Imagine now the same "jammer" type aircraft with three channels, one for use in scalar interferometry and one as an ordinary channel.

This time, a Fourier interference pattern is established around the aircraft, so this establishes an "energy bottle" around the plane. We specifically arrange this bottle in the frequency band of the hostile radar we wish to avoid. For multiple bands, we establish multiple bottles -- this just requires more frequencies or more translator/transmitters.

The beam from the ground radar now strikes the energy bottle, and its energy enters and is trapped in the bottle grids. Since the bottle is leaky, the incident energy gradually disperses and "leaks" out all around, with very little emerging energy.

The ground radar receives no return pulse or reflection.

Therefore it sees no target.

The same interferometer system is usable both in this defensive screen fashion and in the attack fashion previously discussed.

Use of this system has been demonstrated internationally.

An energy bottle has been created in a North American laboratory as well.

Next Slide

The Tom Bearden Website

SLIDE 57.

NETWORK OF VIRTUAL TRANSMITTERS



As is well-known, for years the Soviets have blanketed the world with large, powerful transmitter signals in the communications band, referred to as the "Woodpecker" signals because of the staccato noise the chirped signals make to the ear. The carriers have been modulated with known harmful bioactive ELF frequencies. At least some effects have been noted on humans from these signals, and other human effects are suspected but not proven.

In addition, evidence exists that such transmitters, utilized in the scalar transmission mode, may have been used to cause earthquakes and to control the weather. High altitude bursts off the coast of the Eastern United States and Canada, over

Timmons, Ontario, Canada, and off the coast from St. Petersburg, Florida have occurred also.

Mysterious "blackouts" of U. S .satellites -- and British satellites -- have occurred. These would be difficult to explain as the result of illumination from a ground laser, but easily explained as the result of illumination from a ground-based scalar beam or scalar interferometer.

Strange patterns of micro sky quakes and micro earthquakes occurred at various locations throughout the U.S. just before and shortly after the death of Leonid Brezhnev. These strongly appear to be connected with the adjustment of a scalar interference pattern -- a gigantic "energy bottle" across North America, as shown on this slide.

Shortly after this suspected adjustment and alignment, the underground net in the U.S. detected the emergence of numerous ELF-modulated signal carriers throughout the U.S., generally utilizing carriers in the vicinity of 40 MHz. Locations of the apparent transmitters were such places as Atlanta, North Georgia, St. Petersburg, Florida; Mississippi; Alabama; in the vicinity of Washington, D.C.; near Boston; around the Great Lakes; Michigan; in the Pacific Northwest (Washington and Oregon); and in both northern and southern California.

Researchers knowledgeable of the Soviet woodpecker signals and ELF modulations detected and reported these signals.

Physical effects were reported and correlated to the signals, including wakefulness at night, restlessness, fatigue, headaches, nausea, ringing in the ears, anxiety, disturbed dreams, etc.

What appears to have occurred is the adjustment and
alignment of a vast scalar interference pattern across the U.S. Recall that energy emerges in each grid, by phase interference between the composite substructure waves of the scalar beams.

Thus the Woodpecker "over-the-horizon radars," as accepted
by Western intelligence analysts, may have acquired a diabolical new strategic capability.

It is as if the Soviets had been permitted to build a vast network of transmitters directly on U.S. soil, for hostile employment against U.S. citizens.

Shortly after the net was aligned, a curious pattern of weather assaults on the U.S. began.

Storms assaulted California unceasingly. Then they roared across the Rockies, dipping sharply down to hit the Texas Panhandle, and bending northeast again to assault the South and the East.

The mighty jetstreams themselves were diverted and "kinked" into this looped, distorted pattern.

And the storms and floods assaulted the U.S. one after the other in this highly unusual fashion.

I maintain that the virtual transmitter net, just established by the Soviets and adjusted in on the U.S., was tested in the weather control mode. If so, it proved highly effective. Imagine what would have happened to the U.S. if it had been unleashed full force, and not just "gently tested."

And imagine what happens when disease, death, and nervous system disturbances are modulated upon these blanketing signals. The "transmitters" for the patterns are in each grid, all across the U.S.! And there are no physical transmitters there to destroy.

A counter is needed quickly. A simple one would consist of recording the signals in each grid zone, analyzing the substructure, reversing the signals and their structured patterns 180 degrees, and feeding the "cancellation signals" out in each area.

A great strategic Russian weapon of devastating power and potential is now operating directly on U.S. soil. The need for a crash countermeasures program is urgent.

In 1975 Brezhnev had introduced to the SALT talks the
strange proposal that we should also consider outlawing the development of new weapons more frightful than the mind of man
had ever imagined. We didn't know what the Russians were talking about. When we asked them later what weapons they meant, they referred vaguely to weapons of an electromagnetic nature.

The presentation I have just given you is part of what Brezhnev meant.

Next Slide

The Tom Bearden Website

SLIDE 58.

CONCLUSION



In conclusion, today I have released a number of powerful mechanisms that result from the new technological concepts. Many of these were originally discovered -- at least in rudimentary form -- by Nikola Tesla. In the West, the suppression of Tesla led to the suppression of these effects. And our knowledge of them went to the grave with Tesla.

After World War II, the Soviet Union mounted a massive campaign to obtain all the scientific literature of the West and thoroughly digest it. Great centers were set up, and thousands

of PhD's devoted to this purpose. Gradually they synthesized
this technology from the errors in EM foundations they uncovered, and from obscure, ignored papers published in the orthodox
Western scientific literature.

They rediscovered the technology of Tesla, Moray, and
Rogers. And they have highly weaponized the effects, and adjusted and aligned the weapons upon us.

Now the radical movements are onto part of this technology. As late as about six months ago, one such group discovered how to build a translator and a scalar beam projector. Excitedly, they planned to build them the size of a large pistol, powered by a portable battery pack, and sell them to street criminals to kill or stop the police. They planned to get rich by this illicit means. At that time, a personal friend of mine, who moves in underground circles, was attempting to purchase one of the prototypes for my analysis. Fortunately, the inventor stepped into the beam of one of his devices and was almost killed. This frightened the group, and at least for now they have desisted. But be forewarned: this technology is coming down the pipe, and the police establishments in the West are in for the shock of their lives if the scientific community does not wake up and prepare defenses.

Again I urge my fellow colleagues to experiment vigorously with these new concepts, but build equipment for the benefit of man. Insect control, disease elimination and control -- both are noble purposes. Defense against the hostile use of such devices is also a fitting purpose.

We are in the final days, and the final technology is upon us. It is a stupendous tool for either good or bad, and assuredly it will be utilized for both means. I call attention once again to the fact that my ultimate purpose is to use this technology benevolently to achieve mind linkage, and elevate man from his present brutish state to the lofty state that is his destiny and his true God-nature.

For better or worse, Tesla technology is once again loose in the world, this time for good, and on a massive scale.

Let us prepare ourselves for a wild canoe ride, for the real white water lies just ahead.

Thank you for your attention, and good evening.

LEADING EDGE

Volume 7, Issue No. 4



DIRECTED ENERGY

Applications Across Land, Air, and Sea

NAVSEA
WARFARE CENTERS
DAHLGREN

Challenges & Solutions for the 21st Century

LEADING EDGE
Volume 7, Issue No. 4

TABLE OF CONTENTS

Directed Energy



3 LEADING EDGE DIRECTED-ENERGY RDT&E
Captain Michael H. Smith

4 DIRECTED-ENERGY TOPICS IN THIS ISSUE
Mr. Dale Sisson

PAST, PRESENT, AND FUTURE

6 NAVAL DIRECTED-ENERGY WEAPONS – NO LONGER A FUTURE WEAPON CONCEPT
David C. Stoudt

12 HISTORICAL OVERVIEW OF DIRECTED-ENERGY WORK AT DAHLGREN
Stuart Moran

26 HISTORY OF LASER WEAPON RESEARCH
Melissa Olson

36 LASER WEAPON SYSTEM (LAWS) ADJUNCT TO THE CLOSE-IN WEAPON SYSTEM (CIWS)
Robin Staton and Robert Pawlak

RDT&E, ACQUISITION, AND WARFARE MANAGEMENT

44 THE ACQUISITION CHALLENGE ASSOCIATED WITH DIRECTED-ENERGY RDT&E
Mike Kotzian

TECHNOLOGY, MODELING, AND ASSESSMENT

50 THE BASICS OF ELECTRIC WEAPONS AND PULSED-POWER TECHNOLOGIES
Stuart Moran

58 SOLID MODELING OF DIRECTED-ENERGY SYSTEMS
Joseph F. Sharrow

64 A FUNDAMENTAL KEY TO NEXT-GENERATION DIRECTED-ENERGY SYSTEMS
Directed Energy Division, Electromagnetic and Sensor Systems Department

70 ACTIVE DENIAL ARRAY
Randy Woods and Matthew Ketner

74 DIRECTED ENERGY IN THE MILITARY ENVIRONMENT
LT Leedjia Svec, Jeremy Beer, and Dave Freeman

HIGH-POWER MICROWAVE

78 DIRECTED ENERGY USING HIGH-POWER MICROWAVE TECHNOLOGY
Jacob Walker and Matthew McQuage

HIGH-ENERGY LASER

82 LASER COUNTER ROCKET, ARTILLERY, AND MORTAR (C-RAM) EFFORTS
Michael Libeau

NONLETHAL CAPABILITIES

86 MULTIFREQUENCY RADIO-FREQUENCY (RF) VEHICLE STOPPER
Stephen A. Merryman

92 HIGH-POWER ELECTRICAL VEHICLE-STOPPING SYSTEMS
Jordan Chaparro and Melanie Everton

96 NONLETHAL SMALL-VESSEL STOPPING WITH HIGH-POWER MICROWAVE TECHNOLOGY
Jacob Walker

LEADING EDGE

Naval Surface Warfare Center, Dahlgren Division (NSWCDD)
Captain Michael H. Smith, *Commander*
Carl R. Siel, Jr., *Technical Director*
David C. Stoudt, *Distinguished Engineer for Directed Energy (ST) and NAVSEA Technical Warrant for Directed Energy and Electric Weapon Systems*
Janice Miller, *Corporate Communications Director (Acting)*
Steve Zehring, *Managing Editor*
Margie Stevens, *Production Coordinator*
Patrice Waits, *Editor & Layout*
Clement Bryant, *Layout Design & Graphic Artist*
Kellie Yeatman, *Graphic Artist*
Trey Hamlet, *Graphic Artist/3-D Modeling*

Electromagnetic & Sensor Systems
Dale Sisson, *Head, Q Department*
Brandy Anderson, *Graphic Artist/Cover Design*

NSWCDD
Jordan Chaparro
Melanie Everton
Matthew Ketner
Michael Libeau
Matthew McQuage
Stephen A. Merryman
Stuart Moran
Melissa Olson
Robert Pawlak
Joseph F. Sharrow
Robin Staton
Jacob Walker
Randy Woods

Defense Acquisition University
Mike Kotzian

Naval Medical Research Unit – San Antonio
Jeremy Beer
Dave Freeman
LT Leedjia Svec

The Leading Edge *magazine is produced by the Naval Surface Warfare Center, Dahlgren, Virginia. The purpose of the publication is to showcase technical excellence across the Warfare Centers and promote a broader awareness of the breadth and depth of knowledge and support available to the Navy and DoD.*

Address all correspondence to Corporate Communications, C6
Email: dlgr_nswc_c6@navy.mil; or write to
Commander
Naval Surface Warfare Center, Dahlgren Division
Corporate Communications, C6
6149 Welsh Road, Suite 239
Dahlgren, VA 22448-5130

NSWCDD/MP-09/34
Approved for public release; distribution is unlimited.

NAVSEA
WARFARE CENTERS
DAHLGREN



Introduction

Leading Edge Directed-Energy RDT&E

Captain Michael H. Smith, USN
Commander, NSWCDD

Dahlgren first launched research and development efforts devoted to harnessing the power of electromagnetic energy over 40 years ago. From early work with voltage multipliers and pulse-powered technology, to today's high-energy lasers and high-power microwave technologies, the Naval Surface Warfare Center, Dahlgren Division (NSWCDD) has led, and continues to lead, cutting-edge directed-energy research, development, testing, and evaluation. Our commitment in this area only grows stronger—evidenced by our chartering of the Directed Energy Warfare Office (DEWO)—in order to provide increased focus on warfighting applications of these technologies.

Today's military forces face a wide array of challenges in diverse operating environments around the world. Directed energy offers unique and flexible options to address today's challenges, as traditional kinetic weapons are often of limited value in peacekeeping missions and in urban environments, where restricted rules of engagement typify the norm. Kinetic weapons can also be more costly or ineffective to employ against asymmetric threats.

The Chief of Naval Operations (CNO) recently placed added emphasis on directed energy and on expanding the range of directed-energy capabilities. In response, scientists and engineers at NSWCDD are actively developing prototype systems in a number of areas that you will read about in this issue—areas that have been successfully demonstrated and tested in our Navy laboratories and ranges.

In this issue of *The Leading Edge* magazine, you will trace the rich history of directed-energy work at Dahlgren, gain insight into directed-energy weapons already fielded or being readied for the field, and learn about prototypes that show real promise for providing incredibly effective offensive and defensive directed-energy solutions. For example, scientists and engineers at NSWCDD are leading the way toward realizing small, lightweight radio frequency (RF) transmitters using high-power, solid-state switching amplifiers for the development of counter-improvised explosive device detection and neutralization systems. You will also learn about diverse applications of directed-energy technology—such as research and testing of laser glare devices and laser eye protection—and have the opportunity to gain a better understanding of the Department of Defense (DoD) acquisition framework and the challenge of maintaining cost and schedule estimates while delivering weapons systems that are critical to the warfighter.

From lasers to high-power electrical vehicle-stopping systems, I am sure you will be fascinated and, along with me, be impressed with the advancements our scientists, engineers, and technical staff are achieving in the directed-energy arena to support of our men and women in uniform.

Directed-Energy Topics in This Issue

Dale Sisson
Head, Electromagnetic and
Sensor Systems Department
NSWCDD Dahlgren, Virginia



Welcome to our Directed Energy issue of the *Leading Edge* magazine. This issue represents the third in a trilogy of issues covering the truly fascinating and incredibly challenging area of naval warfare in the operational electromagnetic environment. In our first issue, we covered the full range of operational and readiness implications when operating in the electromagnetic environment. Then, in our second issue, we highlighted the complexities and dynamics of providing relevant and effective sensors and radars to our warfighters. Now, we focus on directed energy and relate how the Naval Sea Systems Command (NAVSEA) Warfare Centers, and the Naval Surface Warfare Center, Dahlgren Division's (NSWCDD's), in particular, are working on state-of-the-art directed-energy weapons capabilities for the warfighter.

In this issue, we first look back to the early years, decades ago, when directed-energy weapons research began. We examine the history of directed energy, and we cover significant discoveries and achievements made by NAVSEA Warfare Center scientists and engineers, and others in the scientific community. We then relate information about several of our current directed-energy initiatives, and about how we're working hard to solve some of the most complex technical challenges associated with directed-energy weapons. We highlight how others in the Navy, such as the Naval Medical Research Unit in San Antonio, Texas, are also conducting research into directed energy and how our forces can better protect themselves from the effects of directed energy. We show how directed energy can be employed in a variety of offensive and defensive, lethal and nonlethal situations. We explain how directed-energy weapons work and how they can be employed in various environments against a wide range of situations. Lastly, we look forward as we provide technical and strategic leadership for the efficient and effective development, acquisition, and fielding of directed-energy systems for the warfighter.

So, if you want to learn about what the NAVSEA Warfare Centers and others in the Navy are doing in the area of directed-energy weapons, look no further than this issue of the *Leading Edge* magazine. I'm confident that you will be impressed by the progress made in this most important technology field.



DIRECTED ENERGY

DIRECTED
ENERGY

Naval Directed-Energy Weapons – No Longer A Future Weapon Concept

By David C. Stoudt

Dr. Stoudt is the Distinguished Engineer for Directed Energy (ST) and the NAVSEA Technical Warrant for Directed Energy and Electric Weapon Systems.

Directed-energy weapon (DEW) technologies typically take the form of high-energy lasers (HELs), high-power microwaves (HPMs), and charged-particle beams. This article focuses on the first two technology areas, as they have reached the point of being ready for operational testing and evaluation, and in some cases, operational use on the battlefield. DEWs have been popularized in science-fiction writings for over a hundred years. The Department of Defense (DoD) has been investing in their development since the 1970s. This article will not go into technical depth regarding the various directed-energy (DE)-related efforts currently underway in the Navy, but rather, it will overview DE areas under development and relate recent Navy leadership activity. Other articles in this issue of *The Leading Edge* magazine will provide the reader with much greater technical and programmatic details on various DE efforts.

High-Energy Laser Weapons

HEL weapon systems have been envisioned for a great many years, to include being referred to as Martian "Heat Ray" weapons in H.G. Wells' epic novel *The War of the Worlds*, originally published in 1898. In reality, a high-average-power laser weapon system is very similar to a "heat ray", or even a blow torch. During the early years of DoD investments in DE technology, the Navy led the development of HEL with the creation of the world's first megawatt-class, continuous-wave, Mid-Infrared Advanced Chemical Laser (MIRACL), located at White Sands Missile Range (WSMR). Roughly 80 years after the work of H.G. Wells, the U.S. Navy tested the MIRACL laser and ultimately used that laser system to engage static and aerial targets in the desert of WSMR in the following years. While that laser proved to be the wrong choice for the Surface Navy's self-defense mission, it did spawn work by the Air Force on the Airborne Laser (ABL), and the Army on the Tactical High-Energy Laser (THEL). In 2000 and 2001, the THEL successfully shot down 28 supersonic Katyusha artillery rockets and 5 artillery shells.

In 2010, the ABL successfully engaged and destroyed tactical ballistic missiles during the boost phase of their flight. All three of these laser systems—the MIRACL, the ABL, and the THEL—are chemical lasers that utilize toxic chemicals and operate in less than optimal wavelengths that make them a poor choice for most naval applications. The MIRACL is shown in Figure 1.

Recent advances in solid-state lasers, to include fiber lasers, have moved these electric lasers to the forefront of the Department's research and development (R&D) for near-term HEL applications in the services. The Navy has particular interest in electric lasers, to include the free-electron laser (FEL), for shipboard self-defense and force protection applications. The speed-of-light delivery of HEL energy can defeat the high-g maneuvers of newly developed foreign antiship cruise missiles (ASCMs). Thus, the Office of Naval Research (ONR) started an FEL Innovative Naval Prototype (INP) program in FY10, with a goal of reaching the output power of 100 kW. The eventual goal of the FEL program is to reach the multi-megawatt power level with wavelength selectivity. The Naval Sea Systems Command (NAVSEA) Directed Energy and Electric Weapons Program Office (PMS 405) has been actively developing a fiber laser-based Laser Weapon System (LaWS) that could be a retrofit to augment the current capabilities of the Close-In Weapon System (CIWS) currently deployed on many surface combatants. The Naval Surface Warfare Center, Dahlgren Division (NSWCDD), is the Technical Direction Agent and lead system integrator for PMS 405 on the LaWS program. The Naval Air Systems Command (NAVAIR) has interest in compact, solid-state HEL systems for aircraft self-protect and air-to-ground engagements, and will be starting a



Figure 1. Mid-Infrared Advanced Chemical Laser (MIRACL)

fiber laser-based ONR Future Naval Capability effort in FY12. LaWS is shown in Figure 2.

High-Power Microwave Weapons

Like lasers, microwave weapons have been fantasized about ever since the invention of microwave power generators. In fact, in 1932 it was generally recognized by the British government that bombers, ostensibly German bombers, would be able to penetrate British air space and bomb its civilian population and infrastructures. In 1934, the Air Ministry initially asked Robert Watson-Watt, of the National Physical Laboratory, if he could build a "death ray" that could kill enemy pilots or detonate bombs while they are still on the planes of enemy aircraft. Such a "death ray" had been proposed to the Air Ministry by Harry Gindell-Mathews 10 years earlier in 1924. Watson-Watt, a former meteorologist who had become an expert on radio signals, suggested that energy reflected from an aircraft could be used to locate it. His experiments were successful and RADAR (radio detection and ranging), a name coined by the U.S. Navy in 1940, was born. While RADAR is not a DEW in the way they are thought of today, its roots can clearly be traced to the military's desire for such capabilities.

The Navy's HPM, or high-power radio-frequency (RF) systems, have been progressively increasing in power density to the point where it is now feasible to integrate the technology into weapon systems for deployment. While initial HPM applications suffered from their inability to obtain militarily useful outcomes, either due to technology limitations, difficult concept of operations (CONOPS), or inherent robustness of potential target systems, many feasible military applications for using HPM



Figure 2. Laser Weapon System (LaWS)

devices have surfaced over recent years to include nonlethal, antipersonnel weapons and nonkinetic, antimateriel weapons. While these concepts offer unique capabilities to the warfighter due to the nonkinetic effects they generate, other warfighting concepts—such as stopping vehicles, or countering hidden roadside bombs or improvised explosive devices (IEDs)—are difficult to achieve by any other means. The multifrequency Radio-Frequency Vehicle Stopper (RFVS) system is shown in Figure 3.

In addition, the difficulty in overcoming the propagation losses associated with HPM has driven some concepts into platforms such as unmanned aerial vehicles (UAVs) or cruise missiles that deliver the HPM device to the target for a close-in engagement. Over the past 10 years, field-testable prototypes have been developed to demonstrate the operational utility of these concepts, and in some cases, those prototypes have or will be deployed operationally to support our troops in theater. It is only through the hard work and perseverance of the Naval Research Enterprise (NRE), as well as other DoD laboratories, that concepts that were once only laboratory curiosities are now making their way onto the battlefield and contributing to the fight.

Foreign Directed-Energy Weapon (DEW) Development

While the United States has been very active in this warfighting area, significant foreign DEW development also has elevated the need for the Navy to afford these threats a higher priority. This can be done either by incorporating the necessary DEW countermeasures into weapon systems, platforms, and critical infrastructures, or by adapting the CONOPS and tactics, techniques, and procedures (TTPs) employed by our armed forces to properly account for those foreign DEW systems. Materiel developers need to understand how this threat



Figure 3. Multifrequency RF Vehicle-Stopper (RFVS) System

is evolving and properly address it during the design of their systems. They also need to address DE in the development of their system threat assessments. There has been movement on the HPM side to modify existing military standards, such as MIL STD 464[1] and others, to now include information on potential HPM threats. For example, in the HEL arena, work has been accomplished in the development of protective measures for eyes; however, this threat needs to be considered during the system development process. It is well known that building in countermeasures is much cheaper during the initial development of a system, vice trying to retrofit systems with countermeasures once a new threat is on the battlefield. As analysts evaluate the foreign development of DE technologies, and the trends become clearer, it is the responsibility of the acquisition community to take this threat into consideration and ensure that weapon systems, platforms, and infrastructures will be available and at full capability when needed. By accounting for foreign threat developments, assessing blue force susceptibilities and vulnerabilities, and adopting appropriate measures to negate or counter these threats, naval forces will avoid technological surprise on the battlefield in the future.

Requirements

The DE programs briefly mentioned in this article, and covered more deeply in this and other publications, offer warfighters unique capabilities not currently found in their arsenal. The continuing problem, however, is matching those unique capabilities to vetted operational requirements. The DE technical community has made great strides in helping the operational community understand the capabilities of DE weapons and their potential military effects on targets. The lack of formal requirements, however, has yielded more of a technology push—rather than an operational pull—of various DE capabilities. Progress has been made, but more effort is required if DE capabilities are to be developed and transitioned between science and technology (S&T), and formal programs of record. Notwithstanding, the current outlook and trends are positive.

A Resurgence of Navy Interest in Directed Energy

The Navy's interest in DEWs for future maritime operations has increased in recent years due to a number of weapons development successes. Recognizing the importance and value of DEWs, NAVSEA reestablished the Navy Directed Energy Weapons Program Office (PMS 405) in 2004. Accordingly, PMS 405 was designated as the point of contact for matters related to DE and electric weapon systems (EWS) development and acquisition initiation for NAVSEA, and for matters being coordinated with other federal agencies and military services. PMS 405's mission is to transition technology from the laboratory to prototype/advanced development/testing for operational development and use.[2,3]

The Navy also established its first formal executive position for DE (ST-level), the Navy's Distinguished Engineer/Scientist for Directed Energy, at NSWCDD in August 2004. Following the establishment of this position, NAVSEA then formally established a Technical Authority Warrant for Directed Energy and Electric Weapon Systems (DE&EWS)—Surface Ships in July 2008. The scope of the warrant includes the transition of S&T development to weapon system development of lethal and nonlethal capabilities associated with the DE&EWS for Surface Ships.[4] This included, but was not limited to, the following:

- Laser Weapon Systems
  - High-Energy Lasers
  - Solid-State Lasers
  - Free-Electron Lasers
  - Femtosecond Ultrashort Pulse Lasers
  - Laser-Induced Plasma Channel
  - Lethality/Vulnerability
- Electromagnetic Rail Gun Weapon System
- High-Power Microwave
  - Active Denial System
  - Laser-Guided Energy
- Maritime Directed Energy Test Center
- Electromagnetic Launch of Weapons (excluding the Electromagnetic Aircraft Launch System (EMALS))

Then, within the NAVSEA Warfare Center Enterprise, Warfare Center leadership established two technical capabilities (TCs): an NSWCDD TC for DE systems research, development, test, and evaluation (RDT&E); and a Naval Surface Warfare Center, Port Hueneme Division (NSWCPHD) TC for in-service engineering, test and evaluation (T&E), and integrated logistics support to DE systems. NSWCDD leads all S&T and RDT&E for the development and weaponization of DE systems for surface, air, and ground environments. It also leads the development of offensive and defensive DE technologies needed to characterize and exploit vulnerabilities, provide weapons, and protect against attack. NSWCDD provides the technologies, devices, and systems designed to create or control electromagnetic energy used to cause persistent disruption or permanent damage by attacking target materials, electronics, optics, antennas, sensors, arrays, and personnel, including nonlethal applications. NSWCPHD provides in-service engineering, T&E, and integrated logistics support to DE systems throughout the system life cycle.

The Navy further demonstrated increased interest in DE when Assistant Secretary of the Navy (Research, Development & Acquisition (ASN(RDA)) designated NAVAIR offensive and defensive leads for naval aviation DE activities:

- Program Executive Officer for Unmanned Aviation and Strike Weapons (PEO(U&W)), assigned as the offensive DE lead for naval aviation
- PEO for Tactical Aircraft Programs (T), assigned as the defensive lead for naval aviation

Concerning future initiatives, the Chief of Naval Operations (CNO) tasked the Strategic Studies Group (SSG) to examine a topic entitled "Maritime Operations in the Age of Hypersonic and Directed-Energy Weapons."[5] The intent of the study was to provide Navy leadership with an understanding of where DE technologies and weapons are today and how they might influence future maritime operations. The theme of the study was completed during FY10, the results of which discuss many DE concepts, as well as tactics for the employment of DE capabilities. The study's findings are currently under review and consideration by senior Navy leadership.

CONCLUSION

While H.G. Wells' *The War of the Worlds* novel and television programs like *Star Trek* popularized the notion of using DE for weapons in years past, today— through persistent DEW RDT&E—Navy leadership is realizing the great potential that DEWs offer naval warfighters and homeland defenders. The scientific and technical advances the Navy has made in HEL and HPM in recent years have been nothing short of extraordinary. Moreover, future technological and engineering advances undoubtedly will result in profound differences in our nation's future warfighting capabilities. Naval DEWs, therefore, are no longer just a future weapon concept…they are here today.

REFERENCES

1. *Department of Defense Interface Standard, Electromagnetic Environmental Effects—Requirements for Systems*, MIL-STD-464, 18 March 1997.
2. NAVSEA Notice 5400, Ser 09B/240, Subject: Establishment of the Navy Directed Energy Weapons Program Office (PMS 405), dated 4 January 2002.
3. NAVSEA Instruction 5400.101, Ser SEA 06/058, Subject: Directed Energy and Electric Weapons Program Office (PMS 405) Charter, dated 21 July 2004.
4. NAVSEANOTE 5400 Ser 09B/240 of 4 January 2002 and NAVSEAINST 5400.101 Ser SEA 06/058 of 21 July 2004.
5. Letter from the CNO tasking the SSG XXIX Theme—"Maritime Operations in the Age of Hypersonic and Directed-Energy Weapons," dated 23 September 2009.



HISTORICAL OVERVIEW OF DIRECTED-ENERGY WORK AT DAHLGREN

By Stuart Moran

In 1962, the United States set off a megaton nuclear weapon 250 miles above the Pacific. The blast caused a large imbalance of electrons in the upper atmosphere that interacted with the Earth's magnetic field to create oscillating electric fields over a large area of the Pacific. These fields were strong enough to damage electronics in Hawaii, a thousand miles away, and clearly demonstrated the effects of an electromagnetic pulse (EMP). It didn't take long for the military to begin considering ways to create such pulses without using nuclear weapons.

In the late 1960s, the Special Applications Branch at the Naval Weapons Laboratory at Dahlgren began studying ways to generate high-power oscillating electric fields that could be used as a weapon to damage enemy electronics. These devices were basically high-power versions of the old spark-gap transmitters used in the early days of radio. To construct a device that could produce nuclear EMP-like fields, stored electrical energy was converted to radio-frequency (RF) energy that could be radiated from an antenna through the atmosphere to a target. These devices typically would store energy in a high-voltage capacitor and release the energy quickly using a spark-gap switch. This would then drive oscillating currents on an antenna, causing it to radiate. To achieve field strengths of thousands of volts per meter, typical of a nuclear EMP, devices operating at hundreds of thousands of volts or more were needed.

A number of radiating devices were studied in the early 1970s. Most belonged to a class of devices called Hertzian oscillators. A capacitor is charged to high voltage, the switch is closed, and current flows in the circuit, causing the stored energy to oscillate between the electric field of the capacitor and the magnetic field of the inductor. To charge the capacitor to extremely high voltages, a step-up transformer of some type must be used. One of the fastest voltage multipliers, the Marx generator, was frequently used. The losses from internal resistance and external radiation damp the oscillating waveform, typically after a few cycles. The radiated pulses are, therefore, short in time and broad in frequency content.[1] A simple diagram of the inductance-capacitance oscillator (L-C oscillator) is shown in Figure 1.

SINGLE-PULSE BURNOUT DEVICES

Many types of Hertzian devices were designed, constructed, and tested at Dahlgren during the 1970s. The transmission-line oscillator, or cavity oscillator, used a quarter-wavelength



Figure 1. Inductance-Capacitance Oscillator (L-C Oscillator) Diagram

coaxial pipe, which was switched at one end, to create the oscillating waveform. A frozen wave generator, a different type, had quarter-wave sections of cable that were charged plus and minus to create a two-cycle waveform "frozen" in the cable. All sections were simultaneously switched, causing the wave to travel to an antenna. A special folded design was developed so one switch could be used, eliminating the multiswitch synchronization problem. A Ross circuit used a square wave pulse, which traveled down cable "tees," creating reflections, which were timed to create several RF cycles. In the Travetron, the turn-on time of a series of spark-gap switches was incorporated as a designed delay, creating reflections through a series of gaps to produce the waveform. This design allowed higher frequencies. All of these devices were designed, built, and tested to determine power and frequency capabilities, as well as efficiency.

Scientists and engineers at Dahlgren built and tested versions of Hertzian oscillators operating up to half a million volts. These devices powered relatively simple monopole or dipole antennas that could produce very high electric fields at hundreds of meters. In the early 1970s, a special outdoor field-measurement range was constructed. It housed high-voltage systems in underground trailers that fed antennas above ground on a specially-built, 100-m-long ground plane that was constructed for testing and field measurements. A picture of the ground place in a fielded measurement range is shown in Figure 2. Field probes were even carried aboard helicopters to make measurements above ground effects, as shown in Figure 3.

Other types of devices to produce pulses were constructed, too. Vector inversion generators used spiral-wound capacitive plates to generate high voltages without transformers.[2,3] The Landecker ring used a paddle-wheel arrangement of capacitors and inductors charged in parallel and discharged in series. The circular arrangement was designed so the entire system would radiate as a magnetic dipole, thus forming its own antenna.[4] Switch timing was critical, and Dahlgren engineers attempted to verify reports that Landecker developed a specific type that brought all capacitor leads into a single-center spark gap.

Scientists and engineers also looked at devices that used explosives to generate the electrical energy needed. These included explosive flux compressors of several types, which generated fields and then explosively squeezed the fields between conductors to amplify the peak power. In the early 1970s, a large (70-ft clear zone) anechoic chamber was constructed at Dahlgren with an explosive chamber in one end. Explosives would be set off in the chamber to drive various types of flux compressor schemes that would generate electrical pulses fed into an oscillator and antenna in the anechoic chamber. Pulse parameters and field strengths could be measured. Impedance-matching networks, matching transformers, and methods of improving efficiency were studied. Tests were performed at Dahlgren and at Los Alamos using large antennas suspended from balloons.[5] In other schemes, piezoelectric devices were developed, which could be compressed hydraulically and then quickly released to produce high voltages. The concept was to use explosives to generate the high



Figure 2. Field Measurement Range



Figure 3. Airborne Electric Field Measurements

pressures. Ferroelectric and ferromagnetic transducers driven by explosives were also tested.[6]

Special Effects Warhead (SEW) Program

In 1973, Dahlgren began the SEW Program to look at the feasibility of "burning out" enemy radar and missile systems using single-shot, very high-peak-power EMPs. The program looked at the feasibility of constructing an electromagnetic warhead that could disable electronics beyond a normal hard-kill explosive range as far as a mile away. The program was funded at several million dollars a year through most of the 1970s.

A major thrust of the SEW Program was to better understand the effects of high fields on military electronics. Little information was available on the vulnerability of foreign or U.S. electronics, particularly entire systems. A trailer-based RF impulse system, employing a Marx-driven L-C oscillator charged at two million volts, was constructed at Dahlgren. This Transportable Oscillating Pulser System (TOPS) was connected to a large bounded-wave structure that produced uniform fields over a region large enough to place an entire radar or missile system. The electric field emitted from the throat of this system was so high that a special bag of high-voltage gas was needed until the radiating structure became large enough to transition to the normal atmosphere. A picture of TOPS is shown in Figure 4.

Since many important target systems were not available for testing, much of the vulnerability information was obtained from U.S. electronics, and estimates were then made for foreign systems. In addition to the tests done at Dahlgren, pulsers were also constructed in mobile trailers that could be transported to other sites for testing against simulated or actual targets. The Mobile Oscillating Pulser System (MOPS) was an example that was carried to test sites, such as China Lake, to perform tests against radars and simulated foreign systems.

A key requirement for the SEW Program was to demonstrate enforceable target vulnerability, which means that a high percentage of the time a large percentage of the targets are affected. One important finding was the broad difference between an electromagnetic safety concern—where a 1 percent vulnerability was far too great—and a weapon concern—where a 10 percent vulnerability was not good enough. The field strengths between the safety requirements and weapon requirements often were many orders of magnitude apart.

The SEW Program looked at many types of electronic component vulnerability, subsystem vulnerability, and complete system vulnerability. As a result, energy tables for burnout effects were developed. Subsequently, Dahlgren performed numerous field tests against radar and communications systems between 1973 and 1978, and funded component and subsystem testing on missiles.



Figure 4. Transportable Oscillating Pulser System (TOPS)

Repetitive Systems for Electronic Warfare

The electric fields required to damage military electronics in the 1970s often were very high, and ranges typically were limited. As a spinoff of programs trying to damage targets with a single pulse, some of these devices were reduced in size and power, and operated in a repetitive mode to generate noise pulses for the purpose of electronically jamming target systems. In 1976, the Naval Air Systems Command (NAVAIR) began the Electromagnetic Countermeasures Program to study the application of high-repetition-rate Hertzian devices for use as noise jammers. The initial targets were low-frequency radars.

In late 1976, Dahlgren performed effectiveness tests against various radars using helicopter-mounted Hertzian jammers. These devices were able to screen incoming target aircraft at useful ranges. The concept of a forward-launched rocket to deliver a parachute-suspended Hertzian jammer also was investigated. Dahlgren teamed with engineers at China Lake to study packaging concepts of utilizing an extended 5-inch Zuni rocket as a forward-fired delivery vehicle. A prototype is shown in Figure 5.

Similar Hertzian devices were considered for use as communications and data-link jammers. Several antenna deployment schemes were developed, and by fall 1978, successful ground launches had been performed in which the deployment sequence and jammer operation were demonstrated. The name Zuni Expendable Pulsed-Power Oscillator (ZEPPO) was given to the project. Dahlgren teamed with the Naval Avionics Center (NAC) to build the systems. By 1980, China Lake fired the first air-launched prototypes at both low and high altitudes. Devices, batteries, spark gaps, and antennas continued to be developed, and new targets—such as spread-spectrum systems—were tested. Other delivery systems besides rockets were also considered.



Figure 5. ZEPPO Payload

The Pulsed Power Technology Program

Large directed-energy weapons (DEWs) often required megawatts or gigawatts of peak power, so methods of supplying and modifying this power were needed. As Dahlgren became involved in a broad range of DEW systems, one attribute became more and more obvious: the size, weight, and cost of a directed-energy (DE) system were dominated by the pulsed-power technologies needed to drive the system, not by the source device itself. Consequently, more effort began to be devoted to the power-delivery technologies needed for many of the weapon concepts. Pulsed-power components enabled energy to be stored over long periods of time (seconds) and released very quickly (nanoseconds) to obtain a billion times increase in peak power.

Dahlgren hosted a pulsed-power systems symposium and workshop in 1976 and helped initiate the International Pulsed Power Conferences, which began in 1977 and continues today under the Institute of Electrical and Electronics Engineers (IEEE). As Dahlgren's involvement with systems design increased, it became apparent that new technologies were needed in the prime-power and pulsed-power area to support a variety of new concepts. Dahlgren urged the Navy to initiate a Pulsed Power Technology Program to develop power sources, energy storage systems, high-power switches, and power conditioning systems needed for a variety of future weapons. This program was initiated in 1978 and was originally funded by NAVAIR and then by the Directed Energy Program Office (PMS 405) in the early 1980s. In addition to the Pulsed Power Technology Program, PMS 405 also began funding free-electron lasers (FELs), chemical lasers, high-power microwaves (HPMs), and charged-particle beams (CPBs). The Pulsed Power Technology Program at Dahlgren, in turn, funded many areas of research, both internal and external, over the next 10 years. Dahlgren served as the focal point for the Navy's science and technology (S&T) in pulsed power and funded many universities, government laboratories, and commercial companies under the Pulsed Power Technology Program.

To provide large amounts of electrical prime power, new types of rotating machines were studied, including flywheels, conventional alternators, homopolar generators, rotary flux compressors, and compensated pulsed alternators. These machines attempted to produce fast, high-power pulses using special materials to reduce losses, eddy currents, and mechanical stresses. MHD generators were developed using rocket-motor propellant that could be started and stopped. In the mid-1980s, a full-scale hybrid (solid fuel/liquid oxidizer) combustor was fabricated and tested at 10 MW, achieving world records for power-to-weight ratio and conductivity. By 1980, new types of energy storage systems were studied, including inductive storage and advanced capacitors using new types of insulating materials and geometries. During the late 1980s, programs such as the Mile-Run Capacitor Program reduced the capacitor size by a factor of 10 through better synthesis of polymer films.

Beginning with internal independent research funds, Dahlgren developed liquid dielectric materials based on water/glycol mixtures at low temperatures. These water-capacitor devices could hold energy for orders-of-magnitude longer time periods than ever before, allowing pulseforming lines to be constructed that could be charged directly from rotating machines. Dahlgren scientists developed a world-record high-voltage water capacitor that could hold pulses for milliseconds and became internationally recognized experts in water breakdown.[7,8]

High-power fast switching was another important area of research. Dahlgren funded companies to develop new types of multistage thyratrons that could operate at very high voltages. By the early 1980s, multistage thyratrons capable of operating at over 200 kV, 40 kA with 20 nsec risetimes were demonstrated. Vacuum switches, ignitrons, plasma pinch switches, pseudospark switches, back-lighted thyratrons, and e-beam switches all were studied, as well as a variety of spark-gap switches. Higher power solid-state switches were developed, too, using new geometries and substrate material. Superconducting coils were considered, both for energy storage and as opening switches. Dahlgren engineers developed exploding-wire opening switches, and several types of plasma pinch switches were funded. They also worked on stacked cable pulsers. Additionally, concepts for electromagnetic armor were developed. These systems used high-density capacitors to blunt penetrators. Inductive energy storage—which could be far denser than capacitors—was studied, including methods of generating the seed current and the problematic high-voltage opening switch. Opening switches—which were needed for inductive energy store systems—were studied, as well as magnetic switches, which used saturating magnetic material to sharpen pulses. Magnetic switches operating at 10 kHz were demonstrated by 1983.[9]

In 1985, Dahlgren used internal funds to upgrade a facility to provide controls, diagnostics, and 200 kW of average power at 50 kV to accommodate testing of new switches and water-based capacitors. This facility could control the power with a vacuum-tube pulser and could generate over a million volts with a rep-rated Marx generator. The facility was used to:

- Develop water-dielectric energy storage, rep-rated spark gaps, and pseudospark switches.
- Test a variety of switches developed by contractors, such as back-lighted thyratrons.[10, 11]

A picture of one system being tested—a water pulse-forming line and spark-gap switch—is shown in Figure 6.

Dahlgren concentrated in-house switching efforts in spark gaps. New types of gases were studied, as well as electrode materials, gas-flows, switch geometries, and triggering techniques to produce high-repetition-rate switches for electronic warfare, as well as particle-beam weapons.[12] Dahlgren scientists and engineers demonstrated 100-µs recovery of spark-gap switches after handling kilojoules of energy at hundreds of kilovolts, a world record.[13] The High Energy 2-Pulse System for fast recovery experiment is shown in Figure 7.

In 1986, Dahlgren ran a workshop on high-power switching for Navy tactical and Department of Defense (DoD) strategic applications and became involved with numerous DoD working groups on electromagnetic propulsion, high-power diagnostics, advanced energy conversion, power modulators, and pulsed power. Spark gaps were investigated to create underwater noise for submarines. Dahlgren also led four North Atlantic Treaty Organization (NATO) Advanced Study Institutes in Europe and the UK on various pulsed-power topics. International assessments of key pulsed-power technologies were also performed.

Particle-Beam Weapons

Particle-beam weapons were a major focus of DE work during the 1970s and 1980s. A CPB weapon takes subatomic particles, generally electrons, and accelerates them to near the speed of light before sending them toward a target. These fast electrons penetrate deeply into most materials, so they are difficult to counter. The high-current electron beam was to be accelerated by an induction-type



Figure 6. A Water Pulse-Forming Line and Spark-Gap Switch Test



Figure 7. High Energy 2-Pulse System

accelerator, repetitively pulsed. High electron-beam currents (kiloamps) and a hole-boring series of pulses were anticipated to create a stable, long-range beam. Since the beam was capable of penetrating quickly and deeply into any target material, it had the potential to damage electronics and set off explosives before salvage fuzing could occur. The beam was predicted to be all-weather and essentially countermeasure-proof. Even a near miss could cause substantial damage from high fields and X-rays produced by the deceleration of electrons as they hit air molecules near the target. The CPB concept is shown in Figure 8.

Scientists and engineers from Dahlgren worked on the pulsed-power technologies needed to drive these machines beginning in 1980, and it became a major focus of the Pulsed Power Technology Program.[14] The White Oak Laboratory developed beam-steering concepts and looked at material interactions. By 1989, the program investigated:

- Propagation
- Compact Recirculating Accelerators
- Pointing and Tracking
- Prime Power
- Material Interaction
- Fratricide

For a compact shipboard system, recirculating accelerators were needed to make multiple passes of the electron beam past the accelerating cavities. This required a high-power, fast recovery switch, which Dahlgren began working on in 1988. Using patented hydrogen switches and special triggering techniques—efforts that had begun with internal research funds—Dahlgren demonstrated spark-gap switches, the only technology that could meet the current, voltage, and recovery requirements at that time.[15] The High-Voltage 5-Pulse System experiment is shown in Figure 9.

During these technology efforts, significant advances were achieved in all aspects of the program. These included:

- Generating high-current, high-energy beams (although still below weapons parameters)
- Demonstrating a 360° turn in a high-current beam
- Propagating a single pulse through the air
- Demonstrating beam steering on a small scale
- Performing target interaction measurements

Multipulse, long-range propagation was never demonstrated. A comprehensive tri-service summary called the Net Technical Assessment for CPB was sponsored by the Defense Advanced Research Projects Agency (DARPA) in 1987 to describe the accomplishments of the program. The report said compact accelerators were the most pressing technology need. As a result, most funding was directed toward this topic. Funding was stopped in the early 1990s, however, due to the high expense, stretched timelines, and changes in the threat.

Pulsed Power and Electromagnetic Launchers

During the 1980s, the Army and Air Force looked at short-range electromagnetic weapons to penetrate stronger armor with higher velocities. The Navy worked on concepts for a weapon that could be mounted on ships to intercept missile systems at line-of-sight distances. The Navy—then the biggest user of space systems—was also interested in studies showing that small satellites could



Figure 8. Charged-Particle Beam (CPB) Concept



Figure 9. High-Voltage 5-Pulse System Experiment

be electromagnetically launched into low Earth orbit for the fraction of the cost for a normal launch.

Through the 1980s, electric guns were funded by independent research and independent exploratory development programs at Dahlgren, studying electric gun concepts for both rail guns and electrothermal (ET) guns. Kinetic energy weapons were also investigated as part of the Pulsed Power Technology Program. Under these programs, pure electric launchers were developed and tested at Dahlgren, including ones that self-formed projectiles.[16–18] Also studied were ET guns that used the discharge of electrical energy at the gun breech to generate a plasma jet. This plasma jet heated a low-molecular-weight working fluid, such as water, to produce a heated gas that accelerated the projectile to higher velocities than conventional explosives. The Electrothermal-Chemical (ETC) Gun concept augmented the electrical energy generating the plasma jet with a chemical reaction. A 127mm ETC gun was investigated, and a 60mm ETC gun was tested at Dahlgren, with the ability to fire short bursts at a rate of 100 rounds per minute.[19]

Early Dahlgren work on electromagnetic launchers—along with capacitor development and switch advances from the Pulsed Power Technology Program—allowed Dahlgren to provide the Navy with detailed conceptual designs in the late 1990s for near-term, long-range rail guns based on capacitor energy store. These efforts helped support the decision to begin a long-range rail-gun program at Dahlgren that continues today, resulting in world-record achievements. Capital investment funds were used to construct a high-energy facility in 2005 to test pulsed-power components and module designs for use in electromagnetic launcher programs. An early electromagnetic launcher is shown in Figure 10.

High-Energy Lasers (HELs)

In general, megawatts of continuous laser power are required to kill hard targets at long ranges. Laser technologies that can produce this much power are very limited. The Navy was a leader in developing powerful chemical lasers in the 1970s and 80s. These lasers burned chemical reactants to



Figure 10. Early Electromagnetic Launcher at Dahlgren

generate the excited states for lasing, thus reducing the need for large amounts of electrical power. The Navy built an entire HEL system, including the Mid-Infrared Advanced Chemical Laser (MIRACL) and the Sea-Lite beam director. By 1990, this building-sized system demonstrated shooting boosters, missiles in flight, and supersonic vehicles. However, the system had drawbacks because it:

- Used hazardous, expensive chemicals
- Had propagation problems at the mid-infrared wavelength
- Was large in size and high in cost

FELs require electron accelerators similar to CPB weapons, so they also are large and complex. However, they can be designed to operate at optimum wavelengths and scale nicely to higher powers. The Strategic Defense Initiative began working on FELs in the late 1980s, funding the advanced test accelerator at LLNL, originally developed for CPBs. FELs were also studied under the Strategic Defense Initiative Organization (SDIO) to be used as an antisatellite weapon. These lasers went from milliwatts to watts under SDIO, and then to kilowatts more recently with work at the Thomas Jefferson National Accelerator Facility in Virginia. Space-based lasers and relay mirror systems were studied under SDIO funding, too, including the development of the Advanced Beam Control System for beam steering, beam control, rapid optical retargeting, and self-alignment.

Dahlgren engineers concentrated its internal laser efforts on medium-power soft-kill weapons. They performed tests against sensors and cameras, and investigated damage thresholds. In the late 1980s, Dahlgren engineers worked with optical augmentation to locate enemy optics for targeting and on green laser dazzlers for defense against small-boat attack. There were efforts to harden electro-optical equipment, including sights and night-vision systems for the Marines, and laser eye-protection filters for goggles and binoculars. Laser systems were also investigated for remotely cutting holes and wires to disable electronics. Lethality work continued under funding from the Joint Technology Office for High-Energy Lasers to look at alternative wavelengths and pulse shapes in addition to modern target materials.[20]

Dahlgren scientists continued to investigate laser-damage thresholds for materials, components, and subsystems for a variety of laser technologies. Near the start of the 21st century, commercial lasers based on pumping optical fibers with semiconductor lasers became common and more powerful. Dahlgren purchased the Navy's largest collection of fiber lasers in 2004 and began investigating ways to combine multiple beams into a laser weapon. These lasers have very high efficiencies, above 20 percent, and the fiber-optic output reduces the requirement for complex optical paths. In 2008, Dahlgren engineers demonstrated a laser capability to ignite spinning mortar rounds, and in 2009, engineers demonstrated the capability of fiber lasers in a shoot down of soft targets at China Lake, California.

Resurgence of Directed Energy

With the fall of the Soviet Union and a greatly altered threat, DoD funding (particularly technology funding) experienced an overall decline in the late 1980s and early 1990s. This caused Navy managers to emphasize near-term, lower risk, evolutionary concepts. The Pulsed Power Technology Program and the Navy's Charged Particle Beam Program both came to an end. Investigations into HPM weapons declined as the difficulty of burnout of military electronics—particularly analog components—became apparent. Problems with propagation and cost caused the Navy to greatly reduce efforts on chemical lasers. With the cancellation of major programs, Dahlgren used internal funding in 1990 to keep a core technical capability together, which was necessary for the Center to remain in the mainstream of tactical DE and its associated technologies. Efforts continued in water breakdown, testing of contractor-developed pulsed-power components, and electric guns. New talent and technologies from universities were brought in to jump-start new projects. Tunable waveform generators using unique semiconductor materials were developed. These used bulk semiconductor material, fabricated in-house, that could be used as a fast switch controlled by laser light for both on and off operation. This allowed faster repetition rates and better triggering than could be done with small spark gaps, as well as the ability to create specific waveforms.[21] "Green" technologies were also investigated using nonthermal plasmas and spark-gap shock waves for cleaning and pollution reduction.[22] New types of particle detectors and magnetic field sensors were developed, and new methods of infrastructure protection were investigated.[23] Soft-kill weapons, both optical and HPM, continued to be studied. Short-pulse jamming of spread-spectrum systems was investigated, as well as beat-wave coupling and special waveforms.[24]

A number of trends led to a resurgence of DEWs by the end of the 20th century. The DoD trend in using digital electronics and off-the-shelf commercial technologies increased dramatically. The pace of change in electronics and computers changed rapidly, too. Most of these new electronic systems had never been tested for vulnerability, and there was a question of how much they would increase military vulnerability to RF or HPM attack. The reduced emphasis on nuclear EMP shielding meant more military electronics were not as well protected from RF attack. Consequently, interest in protecting U.S. military and civilian infrastructure increased, including systems in foreign countries. Moreover, with the increasing reliance on civilian infrastructure, such as power, communications, and emergency and industrial systems—all of which were controlled by digital electronics—the potential that an adversary could attack infrastructure systems to affect or divert military operations became an increasing concern. Following several major terrorist attacks during this time period, there was also concern about the impact of an RF attack on airport towers, financial systems, alarm systems, and industrial plants. Human factors—such as a state of confusion experienced by humans—also played an important part in determining the overall effects of an RF attack.

The asymmetric threat—where large numbers of cheap weapons in a swarm attack could overrun a few sophisticated weapons—caused more concern. As the asymmetric threat to the surface Navy pushed the limits of conventional defensive systems, DE—with it speed-of-light propagation, soft-kill potential, and cheap rounds—offered tactical advantages, either as an adjunct to conventional systems or as stand-alone systems. Additionally, there was an increased emphasis on nonlethal, precise accuracy and graduated effects that could be used. Moreover, the idea that future battles would be fought together with civilians and friendly forces on the battlefield increased the importance of low collateral damage and antimateriel attacks.

The Joint Program Office for Special Technology Countermeasures (JPO/STC), located at Dahlgren, began efforts concerning the vulnerability of new digital systems to RF attack. The program also established a DoD-wide database of vulnerability data, source designs, and RF-effects information—bringing together much of the information collected by the services over the years. The program looked at the protection of modern digital infrastructure systems and funded a facility constructed in 1992 to test large-scale electromagnetic vulnerabilities to various methods of attack.

In the late 1990s and early 2000s, Dahlgren initiated programs regarding the potential for RF attack using nonkinetic disruption, with minimal collateral damage. Capital investment funds were used to construct a test facility for this effort in 1998. Dahlgren developed RF payloads for remotely piloted vehicles and demonstrated their effectiveness in field tests in 1999, and in similar tests in 2007. The successful completion of Project Guillotine was DoD's first demonstration of this type of HPM technology. As the need for statistical vulnerability to commercial digital systems became apparent, Dahlgren constructed instrumented test facilities in 1999 and 2002. Two multistory buildings could be reconfigured to reflect different types of building construction and electromagnetic shielding. Large complexes of electronics, computer networks, server systems, telephone systems, security systems, and various types of digital industrial controls could be assembled, instrumented and exposed to attack from an external device or technique. This program-funded complex—called the Maginot Open Air Test Site (MOATS) facility—continues to be used to test target systems, as well as a variety of RF weapon technologies developed internally and by external and international organizations. A picture of the MOATS facility is shown in Figure 11.

As the need for additional DE laboratory space and testing capabilities became apparent, Dahlgren applied for military construction funds, and in 2008, constructed the Naval Directed Energy Center (NDEC), with access to Dahlgren's overwater test range. Other construction funds were used to construct a remote facility at the Pumpkin Neck Explosive Test Range to serve as a laser backstop and measurement facility, as well as an explosive-test staging area. These facilities already have been used to develop and test fiber lasers against modern threat targets. Construction is currently underway to build an expansion of the NDEC and a 120-m laser test laboratory building using an existing tunnel structure. This collection of facilities represents very important capabilities to develop and test future DE systems.

Conclusion

For over 40 years, the Naval Surface Warfare Center, Dahlgren Division (NSWCDD) has been a leader in developing DE devices, pulsed-power systems, and electric weapons. Its people have contributed many publications and patents, and set world records. DEWs tend to be complex and technically challenging to build. Regardless, these weapons offer important, powerful advantages, such as:

- Deep Magazines
- Cheap Rounds
- Fast Targeting
- Variable Lethality
- Pinpoint Targeting

As a result of NSWCDD's leadership, persistent scientific initiatives, and leading-edge engineering



Figure 11. MOATS Facility Undergoing Testing with an RF Weapon (on right)

over the years, naval warfighters will increasingly find themselves turning to DEWs when dealing with situations spanning the spectrum of conflict.

References

1. Moran, S.L., "High Repetition Rate L-C Oscillator," *IEEE Transactions on Electron Devices*, Vol. ED-26 No. 10, October 1979.
2. Fitch, R.A. and Howell, V.T.S., "Novel Principle of Transient High-Voltage Generation," *Proceedings IEEE*, Vol. III, April 1964.
3. Ramrus, A. and Rose F., "High-Voltage Spiral Generators," 1*st International Pulsed Power Conference*, Lubbock Texas, pIIIC9, November 1976.
4. Landecker, K.; Skatterbol, L.V. and Gowdie, D.R., "Single Spark Ring Transmitter," *Proc. IEEE*, Vol. 59, No. 7, July 1971, pp. 1082–1090.
5. Erickson, D.J.; Fowler, C.M. and Caird, R., *EM Radiation from an Explosive Generator System Coupled to a Large Antenna*, Los Alamos Scientific Laboratory Report M-6-258, March 1978.
6. Fowler C.M. and Brooks, M.L., *Explosive Flux Compression Devices Project*, ARPA Order No. 2161, Semiannual Technical Report, 1 March 1972–31 August 1972.
7. Zahn, M.; Ohki, Y.; Fenneman, D.; Gripshover, R. and Gehman, V., "Dielectric Properties of Water and Water/Glycol Mixtures for Use in Pulsed Power System Design," *Proceedings of the IEEE*, September 1986, pp. 1182–1221.
8. Gehman, Jr., V.H.; Gripshover, R.J.; Berger, T.L.; Bowen, S.P. and Zia, R.K.P., "Effects of Filtration on the Impulse Breakdown Strength of High-Purity Water," *IEEE 1995 Tenth International Pulsed Power Conference*, Albuquerque, New Mexico, 10–13 July 1995.
9. Moran, S.L., *Pulsed-Power Technology Program: Accomplishments in Switching*, NAVSWC Tech Note TN-89-259, 1990.
10. Berger, T.L.; Gehman, Jr., V.H.; Lindberg, D.D. and Gripshover, R.J., "A 2.5 Gigawatt Liquid Dielectric Coaxial Pulse Forming Line," *Proceedings of the 6th IEEE International Pulsed Power Conference*, Arlington, Virginia, 29–30 June and 1 July 1987.
11. Bernardes, J.S., "A High Power Fast Response Switch Testing System," *7th IEEE Pulsed Power Conference*, June 1989.
12. Moran, S.L. and Hutcherson, R.K., *High-PRF High-Current Switch*, U.S. Patent No. 4,912,396, 27 March 1990.
13. Moran, S.L. and Hardesty, L.H., "High-Repetition-Rate Hydrogen Spark Gap," *IEEE Transactions on Electron Devices*, Vol. 38, No.4, April 1991.
14. Rose, M.F. and Huddleston, C.M., *Pulsed Power and Directed Energy Technology*, 10th Anniversary Technical Symposium, NSWC MP 84-560, October 1984.
15. Moran, S.L., "Hydrogen Spark Gap for High-Repetition-Rate Compact Accelerators," *NSWCDD Technical Digest*, NSWCDD/MP-92/104, September 1992, pp. 126–139.
16. Bernardes, J.S. and Merryman, S.,"Parameter Analysis of a Single Stage Induction Mass Driver," *Proceedings of the Fifth IEEE Pulsed Power Conference*, Arlington, Virginia, June 1985, pp. 552–555.
17. Bernardes, J.S., "Muzzle Velocity Control with Electrothermal Guns," *Proceedings First Navy Independent Research/Independent Exploratory Development Symposium*, Laurel, Maryland, June 1988, Vol. 2, pp. 123–131.
18. Bernardes, J. S., "Focusing Induction Accelerator," *Proceedings of the Sixth IEEE Pulsed Power Conference*, Arlington, Virginia, June 1987, pp. 735–738.
19. Bernardes, J.S., *Sliding Breech-Block for Repetitive Electronic Ignition*, Patent Number: 5,233,902, 10 August 1993.
20. Kim, H.S. et al., "Effects of Chopping Laser Penetration of Metal Targets," *Applied Physics Letters*, 55 (8), 21 August 1989.
21. Stoudt, D.C. and Schoenbach, K.H., "The Electrical Characteristics of Semi-Insulating GaAs for High-Power Switches," *7th IEEE Pulsed Power Conference Proceedings*, June 1989.
22. Grothaus, M.G. et. al., "Gaseous Effluent Treatment using a Pulsed Corona Discharge," *Proceedings of 10th IEEE Pulsed Power Conference*, Albuquerque, New Mexico, July 1995.
23. Gripshover, R.J. et. al., *Power Frequency Magnetic Field Detection Systems*, Patent No. 6,483,309, 19 November 2002.
24. *Spread Spectrum Countermeasures Final Report*, E-Systems, Inc., Melpar Division under NSWC contract # N68786-82-C-0109.



HISTORY OF LASER WEAPON RESEARCH

By Melissa Olson

The idea of using light as a weapon can be traced back to Hippocrates, commander of the Greek forces in 212 B.C. His forces supposedly set fire to the sails of the Roman fleet by focusing sunlight with mirrors. Weapons systems based on lasers and "ray guns," long a staple of science fiction, have captured the imagination of people everywhere. But with steady progress toward the development of lasers in the last 40 years, viable, state-of-the-art laser weapon systems have now become a reality.

The production of lasers in the modern scientific world is fairly new. The first laser was developed in the 1960s and represented the beginning of a drastic change in how the military viewed warfare. The late 1970s and 1980s, too, marked a busy time period for developing lasers into possible weapon systems. All branches of the military and industry were striving to master high power levels, beam control, and adaptive optics. In 1999, the Department of Defense (DoD) formally recognized lasers as future weapons and began research and development (R&D). In 2000, the Joint Technology Office for High Energy Lasers was formed to bring all laser technologies together to develop a complete laser weapon system that could be used by the warfighter.

ELECTROMAGNETIC SPECTRUM

The electromagnetic spectrum contains all the types of electromagnetic energy, including radio waves, microwaves, infrared, visible light, ultraviolet, and gamma rays. ***Laser*** is an acronym for "light amplification by stimulated emission of radiation." Light, therefore, is a type of electromagnetic radiation. Light is made up of tiny packets of energy called photons. The amount of energy is what determines the wavelength. Lasers are usually infrared (1 mm to 750 nm) and visible light (750- to 400-nm wavelength). Microwaves are mostly high-frequency radio waves (millimeters to centimeters), with wavelengths 10,000 times longer than lasers. Diffraction of any electromagnetic radiation beam is based on the wavelength and aperture size. For the same aperture size, lasers diffract 10,000 times less than microwaves. This allows the beam to reach farther ranges while maintaining a small spot size of concentrated energy on the target. Lasers are preferred in specific scenarios because of minimal diffraction. The electromagnetic spectrum is shown in Figure 1.

LASER FUNDAMENTALS

The quantum mechanical idea of stimulated emission of light was discovered by Albert Einstein in 1917 and is one of the fundamental ideas behind the laser. Einstein


Wavelength (in meters)
10^{3}
10^{2}
10^{1}
1
10^{-1}
10^{-2}
10^{-3}
10^{-4}
10^{-5}
10^{-6}
10^{-7}
10^{-8}
10^{-9}
10^{-10}
10^{-11}
10^{-12}
longer
shorter
Size of a wavelength
Soccer Field
House
Baseball
This Period
Cell
Bacteria
Virus
Protein
Water Molecule
Common name of wave
Radio Waves
Infrared
Visible
Ultraviolet
"Hard" X-Rays
Microwaves
"Soft" X-Rays
Gamma Rays
Sources
AM Radio
RF Cavity
FM Radio
Microwave Oven
Radar
People
Light Bulb
The ALS
X-Ray Machines
Radioactive Elements
Frequency (waves per second)
10^{6}
10^{7}
10^{8}
10^{9}
10^{10}
10^{11}
10^{12}
10^{13}
10^{14}
10^{15}
10^{16}
10^{17}
10^{18}
10^{19}
10^{20}
lower
higher
Energy of one photon (electron volts)
10^{-9}
10^{-8}
10^{-7}
10^{-6}
10^{-5}
10^{-4}
10^{-3}
10^{-2}
10^{-1}
1
10^{1}
10^{2}
10^{3}
10^{4}
10^{5}
10^{6}

Figure 1. Electromagnetic Spectrum

theorized that when a photon interacts with an atom or molecule in an excited state, two photons are produced when the atom or molecule leaves the excited state. Population inversion occurs when the atoms or molecules are in the excited state. In order for molecules to come out of the normal "ground" state, a source of power must be introduced to the system energizing the atoms to the excited state. When many photons are passed through many excited atoms, more and more photons are produced. The photons are contained and reflected back and forth in a cavity, with mirrors usually on each end. The mirror on the output end is only partially reflective, allowing some photons to leak through, creating the laser beam.

The difference between an everyday light bulb and the light of a laser is temporal and spatial coherence. In a light bulb, the light emits photons equally in all directions. The light is random, out of phase, and multiwavelength. A laser emits coherent light, so photons travel in identical direction and phase. A laser is also monochromatic, i.e., light of one wavelength. Another significant difference is that laser light is highly collimated, which means the laser beam can travel long distances with minimum spreading.

The laser gain medium through which the photons travel to become amplified or magnified can vary. The source of power used to excite the medium, achieving population inversion, can be the result of a chemical reaction, an electric discharge, a flash lamp, another laser, or some other excitation mechanism. The type of the lasing medium determines the type of laser. The three categories in which lasers are usually classified are chemical, gas, and solid state. A laser can also be continuous wave (CW) or pulsed. Each type of laser produces a specific wavelength of radiation. It is important to note that different wavelengths of radiation interact with the atmosphere differently. A laser beam is either scattered or absorbed by air molecules, water vapor, or dust. Longer wavelengths scatter less and are absorbed more than shorter wavelengths; our sky is blue because the shorter blue wavelengths of light are scattered more than the longer wavelengths.[1] Gamma rays are so highly absorbed that they cannot propagate more than a few feet in the air. Thus, some laser wavelengths are scattered or absorbed more than others. This makes laser wavelengths with minimum absorption better for use as directed-energy weapons since they propagate through the atmosphere better than others. For example, the carbon-dioxide (CO_2) laser is strongly absorbed by water vapor, so any use near the ocean will be negatively affected. Near-infrared and infrared lasers have shorter wavelengths with negligible absorbance. The optimal laser choice, therefore, would be a wavelength-tunable laser that could vary depending on the atmospheric conditions, such as the free-electron laser (FEL).

Lasers have affected almost every type of modern technology. Most laser technologies use low powers and were mastered very quickly. They are used in many everyday appliances, such as scanning/inventory devices, surgery/medicine, hair removal, presentation pointers, law enforcement, ranging and sighting devices, welding applications, and much more. Using a laser as a weapon has many advantages. For example, a laser:

- Is unaffected by gravity
- Causes minimal collateral damage
- Travels at the speed of light
- Can precisely reach far distances
- Is capable of causing a specific, predetermined amount of damage to targets

The theory behind these capabilities makes the laser weapon a prime choice in multiple engagement scenarios. However, developing lasers with higher powers to use as a weapon has proven more difficult than first considered.

MILITARY LASER HISTORY AND LASER TYPES

Generally, a laser weapon is any laser used against the enemy with more than 50 kW to megawatts of power. This is much greater power than commercial lasers. Accordingly, they have greater support needs, including:

- Environmental and personnel safety
- Mirror coatings
- Chilling requirements
- Power requirements
- Laser fuel storage
- Alignment and tracking requirements

In 1960, the very first laser (a ruby laser) was built, producing minimal power. This event was followed by many other laser technology developments. The first chemical laser, hydrogen fluoride (HF), was built in 1965, producing 1 kW. It was then that DoD became interested in researching and developing a more powerful laser for weapon applications. Subsequently, in 1968, the Defense Advanced Research Projects Agency (DARPA) Baseline Demonstration Laser produced 100 kW, and the Navy-ARPA Chemical Laser (NACL) produced 250 kW in 1975. The very first laser is depicted in Figure 2.

Solid-State Lasers (SSLs)

An SSL uses a solid lasing medium, such as a rod made up of glass or crystal, or a gem, like the ruby laser. Along with the rod or host material is an active material, such as chromium, neodymium, erbium, holmium, or titanium. Chromium is the active material used in ruby lasers. Neodymium is the active material in the most widespread applications. A flash lamp, arc lamp, or another laser carries out the optical cavity pumping to achieve population inversion and stimulate the laser beam. The Neodymium Yttrium-aluminum garnet (Nd:YAG) laser is a popular SSL. It operates at a 1064.5-nm wavelength and can be pulsed wave or CW. A great advantage of these lasers is that the wavelength and pulse duration can be varied considerably.[1] The power level can reach up to megawatts when using Q-switching to achieve



Figure 2. First Ruby Laser Developed in 1960 by Research Physicist Theodore H. Maiman

short pulse lengths. The various interactions with the laser and different crystalline materials can double the electromagnetic frequency, which will halve the wavelength, bringing the laser beam into the visible range, 532 nm (green). The wavelength can be further divided down three or four times, making this laser range from the near-infrared to the ultraviolet wavelength. These lasers are commonly used for rangefinders and target designators. Other advantages of these lasers are that they can be made very small, rugged, cheap, and battery-powered. Characteristics of SSLs are shown in Table 1.

Chemical Lasers

A chemical laser uses chemical reaction to create population inversion in the lasing medium. One example is the Mid-Infrared Advanced Chemical Laser (MIRACL) developed in the mid-1980s. The MIRACL is a continuous-wave, mid-infrared (3.8-μ) laser. Its operation is similar to a rocket engine in which a fuel (ethylene, C2H4) is burned with an oxidizer (nitrogen trifluoride, NF3).[2] Free, excited fluorine atoms are among the combustion products. Just downstream from the combustor, deuterium and helium are injected into the exhaust. Deuterium (U) combines with the excited fluorine to create excited deuterium fluoride (DF) molecules, while the helium stabilizes the reaction and controls the temperature.[2] The laser's resonator mirrors are wrapped around the excited exhaust gas, and optical energy is extracted. The cavity is actively cooled and can be run until the fuel supply is exhausted. The laser's megawatt-class output power can be varied over a wide range by altering the fuel flow rates and mixture. The laser beam in the resonator is approximately 21-cm high and 3-cm wide. Beam-shaping optics are used to produce a 14- × 14-cm (5.5- × 5.5-inch) square, which is then propagated through the rest of the beam train. Diagnostics for evaluating the beam shape, absolute power, and intensity profile are used on each firing of the laser. The beam can be directed to a number of different test areas or to the SEA LITE beam director.[2] The DF Chemical Laser (MIRACL) and the Sea Lite Beam are shown in Figure 3.

The laser and beam director were integrated in the mid-1980s at the Army's High Energy Laser Systems Test Facility (HELSTF) at White Sands Missile Range, New Mexico. Following integration, extensive tests were conducted in the areas of:

- High-power optical components and beam-path conditioning
- Beam-control techniques
- High-power propagation
- Target damage and vulnerability
- Target lethality[3]

Tests supported by the MIRACL included:

- The high-power dynamic with flying drone (BQM-34)
- Conventional defense initiative with flying drone
- High-velocity target test with Vandal Missile
- High-altitude target tests with flying drone
- Missile and plume tests using the 1.5-m aperture
- Radiometrically calibrated images and spectral radiometry

These successful tests are what made many believe that MIRACL was the first and only successful laser weapon system developed by the Navy prior to the Navy Laser Weapon System (LaWS).[3]

Gas Lasers

Gas lasers are a type of chemical laser that uses a pure gas or gas mixture to produce a beam. The typical gas laser contains a tube with mirrors on each end. One end transmits the beam out of the cavity. Most gas lasers use electron-collision pumping, with electric current passing through the gas. Some use optical pumping with flash lamps. The helium

Table 1. Characteristics of Solid-State Lasers

Name	Wavelength (nm)	Typical Power	Typical Operation
Alexandrite	700-830	5 watts	Pulsed/CW tunable
Erbium	850/1230/1540/1730/2900	8 watts	Pulsed
Holmium: glass	1950	milliwatts	Pulsed
Neodymium	1064/1123/1318/1370	megawatts	Pulsed
Neodymium: glass	1060	megawatts	Pulsed
Neodymium: YAG	1064.5	megawatts	Pulsed/CW
Ruby	694.3	10–15 watts	Pulsed
Titanium-sapphire	660–1060	15 watts	Pulsed/CW tunable



DF Chemical Laser (MIRACL)

Sea Lite Beam

Figure 3. DF Chemical Laser (MIRACL) and Sea Lite Beam

neon (HeNe) laser is a very well-known gas laser. It produces a bright red, continuous beam of low power. It is used for many applications such as scanning, alignment, measurement, and stabilization devices. University students use them in optical training laboratories. Many larger lasers contain a HeNe inside the beam path, as well to verify beam alignment. HeNe lasers are fairly cheap and very rugged. They can work continuously for thousands of hours.

CO_2 lasers are in the gas family. These lasers were the earliest, truly high-power lasers and have been among the most crucial lasers used in R&D for high-energy laser (HEL) weapons. In industry, the more powerful CO_2 lasers are used for welding, drilling, and cutting. There are many different types of CO_2 lasers that vary in pumping design. CO_2 lasers work by burning a hydrocarbon fuel (like kerosene or methane) in oxygen or nitrous oxide. The hot gas flows through a comb of nozzles, expands quickly, and achieves population inversion. The gas then flows through an optical resonator at supersonic speeds, resulting in stimulated emission and a laser beam.[4]

CO_2 lasers have been researched for use as nonlethal weapons. The wavelength produced by a CO_2 laser is also absorbed by glass. For example, the beam does not penetrate a windshield. Thus, shooting a CO_2 laser at a vehicle's windshield could deter a threat by damaging the windshield or by causing a dazzling effect to reduce the visibility of the driver, while not reaching the driver at all.

The gas dynamic laser (GDL) is a CO_2 laser based on differences in relaxation velocities of molecular vibrational states. The laser medium's gas has properties such that an energetically lower vibrational state relaxes faster than a higher vibrational state; thus, a population inversion is achieved in a particular time. A GDL is shown in Figure 4. Characteristics of chemical and gas lasers are identified in Table 2.

Fiber Lasers

Modern fiber lasers are considered SSLs. They are powered by electricity, making them highly mobile and supportable on the battlefield. Fiber lasers use optical fibers as the gain media. In most cases, the gain medium is a fiber doped with rare earth elements—such as erbium (Er3+), neodymium (Nd3+), ytterbium (Yb3+), thulium (Tm3+), or praseodymium (Pr3+)—and one or several laser diodes are used for pumping. Optical fibers have been used in industry, specifically for telecommunications to transport information via light. With developing technology, optical fibers have become high-energy, powerful laser energy sources. Fiber lasers have proven to have much benefit over traditional SSLs. They are rugged and do not require a clean room to operate or maintain, as most other laser systems do. They also are extremely efficient; however, they cannot operate well in all weather conditions. One example is the IPG CW fiber lasers, which produce moderate beam quality, causing damage to materials and components through thermal heating and burn-through. The Naval Surface Warfare Center, Dahlgren Division (NSWCDD) purchased eight commercially available 5.5-kW IPG lasers, where two multimode (seven fibers) lasers are housed per cabinet. This type of laser is easy to mount due to the flexible fibers. The IPG CW Fiber Laser is shown in Figure 5.

Miscellaneous Lasers

There are other types of lasers that do not necessarily fit into the chemical or solid-state categories. These include semiconductor lasers, used in:

- Television
- CD Players
- Dye Lasers
- Spectroscopy
- Radios
- Telecommunications
- Medicine
- Astronomy

There also are the FELs mentioned previously. The FEL is a completely different breed of laser.



Figure 4. A laser engineer inspects a gas dynamic laser after installation aboard an NKC-135 airborne laser laboratory.

Table 2. Characteristics of Chemical/Gas Lasers

Name	Wavelength (nm)	Typical Power	Typical Operation
Helium-Neon	543/632.8	.0001–.001 watts	CW
Krypton	350–647	.0001–.05 watts	CW
Argon	350–514.5	.001–6.0 watts	CW
Xenon fluoride (excimer)	351	.001–20 watts	CW
Argon fluoride (excimer)	193	.05–30 watts	Pulsed
Krypton fluoride (excimer)	249	7–100 watts	Pulsed
Deuterium fluoride (chemical)	3,000–4,200	.01–100 megawatts	Pulsed/CW
Hydrogen fluoride (chemical)	2,600–3,000	.01–150 megawatts	Pulsed/CW
Carbon dioxide	9,000–12,000	.1–15,000 megawatts	Pulsed/CW
GaAlAs (semiconductor)	750–900	10–4,000 milliwatts	Pulsed



Figure 5. IPG CW Fiber Laser System

It uses electrons to create photons instead of some type of matter. The electrons are produced, collected, and directed to flow at very high speeds. To excite the electrons, they are passed through a "wiggler," i.e., a series of magnets positioned in such a way that electromagnetic radiation (light) is produced when the electrons release photons. The significant feature of the FEL is that the wavelength can be controlled, depending on the magnet positions and the speed of electrons. This versatility makes the FEL particularly appealing. However, the footprint of the FEL system is too large to transform into any ideal defense weapon. The Jefferson Laboratory in Newport News, Virginia, has an FEL and continues to maintain and test its capabilities and effects. This laser was new to the military in the late 1990s and received funding to optimize its capabilities and integrate as a defense weapon. Although great progress has been made, the required footprint could be much larger than desired. Consequently, some interest in the FEL has shifted to other HEL sources.

Many scientists foresee the probability of using the laser as a global weapon. This possibility is proven through basic laws of physics. Actually implementing such a system, however, can be more difficult. The global weapon concept uses a base laser with optics and is strategically positioned in space to be able to direct its beam multiple places on Earth at the speed of light with maximum power levels. This idea faces significant problems, including appropriate power levels, optics to handle such levels, propagation issues, and the ethical measures behind any global weapon. Still, the idea presents interesting possibilities.

Laser Weapon Development

The following paragraphs highlight some of the laser weapons that have been successfully developed over the last 40 years.

Baseline Demonstrator Laser (BDL) Hydrogen Fluoride (HF)

In 1973, TRW Inc. produced the world's first high-energy chemical laser, the Baseline Demonstration Laser, for DoD. After that, TRW Inc. produced and demonstrated six more HELs, including the MIRACL (1985) and Alpha (2000), the nation's only megawatt-class chemical lasers.

Navy-ARPA Chemical Laser (NACL) HF

The NACL was mated with the Navy Pointer Tracker at TRW Inc.'s San Juan Capistrano, California, facilities in the 1975–1978 time frame. This was the Navy's initial, integrated HEL system test bed and was used to provide the first demonstrated kill of an operational missile in 1978.

Alpha HF—Built for Strategic Defense Initiative (SDI) Space-Based Laser (SBL)

Alpha, an HF laser, was the baseline technology for the SBL readiness demonstration (SBLRD). In 1991, the Alpha laser demonstrated megawatt-class power levels similar to MIRACL, but in a low-pressure, space operation environment. Alpha demonstrated that multimegawatt, space-compatible lasers can be built and operated.

Tactical High-Energy Laser (THEL)

The THEL is a DF chemical laser developed by the Army. In 2000 and 2001, THEL shot down 28 Katyusha artillery rockets and 5 artillery shells. On 4 November 2002, THEL shot down an incoming artillery shell and a mobile version successfully completed testing. Subsequently, during a test conducted on 24 August 2004, the system successfully shot down multiple mortar rounds. These tests represented actual mortar threat scenarios in which both single mortar rounds and salvo were tested and intercepted. A photograph of THEL is shown in Figure 6.

Advanced Tactical Laser (ATL)

The ATL uses a closed-cycle, chemical oxygen-iodine laser (COIL) with beam control, which lases at a 1.315-μ wavelength. The ATL was developed to engage tactical targets from a moving platform at ranges of approximately 10 km. It can spot a 10-cm-wide beam on a distant target for up to 100 shots. This beam has enough power to slice through metal at a distance of 9 miles. The aircraft equipped with the ATL weapon system is shown in Figure 7.

A specially modified 46th Test Wing NC-130H aircraft equipped with the ATL weapon system fired its laser while flying over White Sands Missile Range, New Mexico, successfully hitting a target board located on the ground. Equipped with a chemical laser, a beam control system, sensors, and weapon-system consoles, the ATL is designed to damage, disable, or destroy targets with little or no collateral damage.

Airborne Laser (ABL) (CO_2) Chemical Oxygen

The ABL C-130H aircraft contains three laser beam systems: the powerful killing primary laser beam (ATL), a set of illuminating laser beams for infrared surveillance and high-speed target acquisition, and a beacon laser for a high-precision laser target tracking beam control system. The primary



Figure 6. Tactical High-Energy Laser (THEL)



Figure 7. 46th Test Wing NC-130H Aircraft Equipped with the ATL Weapon System

laser beam is generated by a megawatt COIL located at the rear of the fuselage. The high-power laser beam travels towards the front of the aircraft through a pipe. The pipe passes through a Station 1000 bulkhead/airlock, which separates the rear fuselage from the forward cabins. The high-power beam passes through the fine beam control system mounted on a vibration-isolated optical bench. Beam pointing is achieved with very fast, lightweight steering mirrors, which are tilted to follow the target missile. The ABL finally destroyed a target while in flight at White Sands Missile Range in August 2009. The 12,000-lb ABL locked onto an unspecified ground target and fired the laser, making the target disappear. Although it was successful at this demonstration, using the ABL in the fleet has fallen out of favor due to affordability and technology problems. The ABL is shown on an aircraft in Figure 8.

Joint High-Power Solid-State Laser (JHPSSL)

In hopes of accelerating SSL technology for military uses, work is being performed by the U.S. Army Space and Missile Defense Command (SMDC) and the Army Test and Engineering Center at White Sands Missile Range. The technology uses an electric laser diode to shoot light into 32 garnet crystal modules that combine to create "laser amplifier chains" producing 15 kW. By using seven chains and by combining multiple beams, they have reached 105 kW in the laboratory operating in a clean room. The program's ultimate goal is for a laser system to reach high powers outside a laboratory environment. Fielding such a delicate optical structure can present significant barriers for this laser system. Nonetheless, it will be a great accomplishment for a variety of force protection missions, such as shipboard defense against cruise missiles. The JHPSSL system is shown in Figure 9.

Navy Laser Weapon System (LaWS)

The Navy LaWS is the most recent, successful laser weapon. It uses an electric-fiber laser design, avoiding the problems that chemical lasers present. In the summer of 2009, the Naval Sea Systems Command (NAVSEA)—with support from NSWCDD—successfully tracked, engaged, and destroyed unmanned aerial vehicles (UAV)



Figure 8. Airborne Laser (ABL)



Figure 9. Joint High-Power Solid-State Laser (JHPSSL) System

in flight at the Naval Air Warfare Center, China Lake, California. A total of five targets were engaged and destroyed during the testing, which represented a first for the U.S. Navy. The laser was fired through a beam director on a Kineto Tracking Mount similar to the Sea Lite beam director. The system used fiber lasers in the configuration and has proven to be a rugged and dependable choice for the warfighter's needs. A photograph of LaWS is shown in Figure 10.

Laser weapon systems development in recent years has taken giant steps forward. Dedicated R&D has advanced the state of the art considerably. What was unimaginable only a few short years ago, today has become reality. Accordingly, given continued R&D, warfighters in the near term will have additional weapon options to choose from for dealing with a spectrum of threats and contingencies.

References

1. Beason, Doug Ph.D., *The E-Bomb: How America's New Directed Energy Weapons Will Change The Way Future Wars Will Be Fought*, Da Capo Press, 2005.
2. Pike John, *Mid-Infrared Advanced Chemical Laser (MIRACL)*, FAS Space Policy Project, Military Space Programs, March 1998, http://www.fas.org/spp/military/program/asat/miracl.htm
3. Albertine, John R., "History of Navy HEL Technology Development and Systems Testing," (Proceedings Paper), *Proc. SPIE*, Vol. 4632, Laser and Beam Control Technologies, Santanu Basu and James F. Riker, Eds., pp. 32–37.
4. Anderberg, Major General Bengt and Dr. Myron L. Wolbarsht, *Laser Weapons: The Dawn of a New Military Age*, Plenum Press, New York, 1992.



Figure 10. Navy Laser Weapon System (LaWS)

LASER WEAPON SYSTEM (LAWS) ADJUNCT TO THE CLOSE-IN WEAPON SYSTEM (CIWS)

By Robin Staton and Robert Pawlak

The Naval Sea Systems Command (NAVSEA) established the Navy Directed Energy Weapons Program Office in January 2002 and subsequently chartered the Directed Energy and Electric Weapon Systems Program Office (PMS 405) in July 2004.[1, 2] Its mission is to change the way the Navy fights in the 21st century by transitioning directed-energy and electric weapon technology, providing the warfighter with additional tools to fight today's and tomorrow's wars. In support of this mission, the Laser Weapon System (LaWS) was developed, which potentially adds a suite of tools for offensive and defensive operations.

The LaWS program is managed by PMS 405 in cooperation with the Program Executive Office Integrated Warfare Systems (PEO IWS), the Navy's Close-In Weapon System (CIWS) manager. A multilaboratory/multicontractor organization led by the Naval Surface Warfare Center, Dahlgren Division (NSWCDD), has been executing the program since March 2007. The potential advantages of a lethal, precise, speed-of-light weapon are numerous and have been recognized for many years. However, even in light of these advantages, there are realities that need to be considered for any program to succeed to the point that an actual system is placed in the hands of the warfighters.

The LaWS system offers viable solutions for an important subset of threats while fitting into acceptable size and weight constraints. In addition, since LaWS is a fully electric laser, the operation of the system does not require the handling and storage of hazardous chemicals, such as hydrogen fluoride. As will be discussed later, due to the incorporation of high levels of commercial off-the-shelf (COTS) technology, the LaWS system also has advantages for topside design, logistic supportability, and cost. Thus, LaWS could enable the Navy to address adverse cost-exchange situations, which can occur when engaging proliferated inexpensive threats such as unmanned aerial vehicles (UAVs).

BACKGROUND

Based on mission analysis work conducted prior to the LaWS program and additional work done as part of the program, it became clear that a number of factors require careful consideration. First, a high-power laser is not likely to replace anything on a ship in the next 5 years. For a new system to be added to a ship, a high-power laser must supplement current capabilities or provide new capabilities that clearly justify its addition. Second, because a laser provides such a diverse set of capabilities, conventional air-to-air warfare (AAW) models—such as the Fleet AAW Model for Comparison of Tactical Systems (FACTS), Antiair Warfare Simulation (AAWSIM), and Extended Air Defense Simulation (EADSIM), as well as other existing AAW analysis approaches—are not well suited for showcasing current or near-term laser-weapon capabilities. While they can (and have) been used for laser-weapon analysis, their application to a megawatt-class laser that could "instantly" destroy boats or cruise missiles (akin to missile engagements) is a more straightforward application of the existing models and techniques.

In November 1995, the Chief of Naval Operations requested that the National Research Council initiate, through its Naval Studies Board, a thorough examination of the impact of advancing technology on the form and capability of the naval forces to the year 2035. A major observation of the report is quoted below:

> Numerous laboratory and field-test versions of laser weapons have been developed and demonstrated. They have worked as expected and demonstrated suitable lethality against their intended targets. The primary factors that have inhibited the transition of the technology into deployed systems are size and weight. Generally, the conceptual designs of laser weapons that are scaled for combat effectiveness are too large to be appealing to users; conversely, weapons that are sized for platform convenience generally lack convincing lethality.[3]

Subsequently, an August 2006 U.S. Air Force (USAF) Scientific Advisory Board Study examined the increasing threat posed by UAVs in some detail. Key conclusions included:

> No single system can completely address the UAV threat. A single sensor solution is inadequate because of the size and speed challenges presented by small UAVs. A single-weapon-layer solution fails to provide for adaptability to multiple scenarios or adequate probability of kill.

Key recommendations of the USAF Advisory Scientific Board Study included:

> Develop and field longer-term upgrades to counter increased UAV threats. They include:…a small, multimission air/air and air/ground weapon; and directed-energy air defense weaponry.[4]

In addition to the USAF Scientific Advisory Board study, a 2007 OPNAV Deep Blue Study noted the potential advantage of nonkinetic defeat options and recommended that the Navy accelerate development of nonkinetic systems to include high-energy lasers (HELs).[5]

The laser power levels likely to be available in the near term, within reasonable size and cost, are in the neighborhood of 100 kW of radiated power. While this power level is not adequate to engage certain threats, such as cruise missiles or tactical ballistic missiles at tactically useful ranges, there is still a wide spectrum of threats that could be engaged at ranges that are comparable to many current ship-defense weapons, including minor-caliber guns and small missiles. The spectrum of threats includes:

- UAVs
- Missile Seekers
- Intelligence, Surveillance, and Reconnaissance Systems
- Rockets
- Man-Portable Air-Defense Systems (MANPADS)
- Mortar Rounds
- Floating Mines
- Artillery Rounds

LaWS on CIWS

The Mk 15 Phalanx CIWS can often detect, track, and (sometimes) identify potential threats at ranges well outside the effective range of the 20mm gun. These functions are accomplished using the search/track radar system and the Phalanx Thermal Imager (PTI). When added to the Phalanx mount and pointed in the same direction as the gun (see Figure 1), a laser weapon could potentially add a number of useful functions and capabilities to the mount, but technical challenges must be overcome. Preliminary analyses of the mechanical characteristics of the mount suggest that the additional weight that could be added to the mount must be kept under approximately 1200–1500 lb. Additionally, it is highly desirable that the addition of the laser weapon not substantially affect the train/elevation operation of the mount in angle, peak velocity, or acceleration. Consequently, use of rapidly evolving fiber laser technology appears to be the only currently foreseeable path to adding significant laser energy directly to the mount within these constraints.

One major driver in the genesis of the LaWS system was the availability of relatively low-cost COTS fiber-optic lasers. Because these fibers are flexible, they obviate the need for an expensive coudé path system (an optical mirror/lens assembly that turns radiation 90° and may also support rotation of the beam director), thus allowing the use of low-cost mount technology, as well as the retrofitting of the system on existing mounts. The last factor is extremely important because of the scarcity of topside real estate on today's ships. These fiber-optic lasers do have limitations in terms of power, although power levels are growing with advancing technology. The reality today is that, in order to get adequate lethality from a system based on this technology, the use of a beam-combining apparatus utilizing several individual fibers is necessary. (Figure 2 depicts combining multiple fibers in the same beam director.) Furthermore, a smaller beam size is desirable since this drives power density up—increasing the performance required for the tracking and pointing elements of the system. Thus, a high-resolution fine track sensor is needed, as well as an appropriately robust line-of-sight control.

A Potential Suite of LaWS-Related Capabilities

Potential added capabilities that an adjunct LaWS could contribute to the total ship combat system are briefly outlined in the following subsections.



Figure 1. LaWS Mounted on CIWS



Figure 2. Cutaway View of the LaWS Beam Director

Target Identification, Tracking, and Intent Determination at Range

The optics that would be added for the laser to detect and track targets in support of a laser engagement would immediately contribute additional capabilities to the entire ship combat system even without operating the laser. A laser-gated illuminator, part of the tracking system, significantly increases the signal to the background level of tracked targets and provides good range resolution as well. The additional sensitivity and angle resolution provided by the LaWS optics would allow the identification, precision tracking, and "monitoring" (at high resolution) of potential threats or vehicles of interest at substantially greater ranges than could be achieved by the PTI alone. The Phalanx radar, or another source, would have to provide an initial, accurate cue to facilitate initial acquisition. Once acquired, the target could be examined and monitored with high resolution at range. This capability could make a substantial contribution to identification efforts—efforts to determine intent and potentially even to documenting target behavior to resolve issues with rules-of-engagement doctrine. It is widely recognized that rules-of-engagement issues, such as threat identification and intent determination, are among the most difficult problems faced by ship commanding officers.

Unambiguous Warning at Range

If a fraction of the laser energy is routed through a frequency-doubling crystal, an intense, visible beam can be projected to significant ranges to provide a clear, unambiguous warning that a potential target is about to be engaged unless an immediate change in behavior is observed. This feature also would have utility for dazzling aircraft, surface vehicle, or submarine sensors, and would provide exceptional long-range, unambiguous warning to boats or aircraft at night.

Sensor Destruction at Range

Many electro-optical (EO) sensors are quite susceptible to damage by laser energy in the fiber-laser band as is the case with infrared (IR) missile seekers with germanium optics. The frequency-doubling feature described in the previous paragraph also would be useful to ensure that a band-pass filter at a single frequency could not be applied as an effective countermeasure. The intent here would be to destroy the seeker or imager at ranges well beyond those achievable by the Phalanx 20mm gun. Other examples include intelligence, surveillance, reconnaissance, and targeting sensors on UAVs or unmanned surface vehicles (USVs).

IR Missile Assist at Range

Many targets of interest—including UAVs, USVs, and small boats—are somewhat "marginal" from a target-signature standpoint, particularly at the maximum range of existing IR guided missiles such as the FIM-92 Stinger, the FGM-148 Javelin, the RIM-116 RAM, and the AIM-9X Sidewinder. The CIWS laser adjunct could potentially "correct" this situation by laser heating target vehicles to enhance their signature to existing IR guided missiles. Note that this is NOT "conventional" semiactive-laser (SAL) guidance—the LaWS is not a coded illuminator, nor do the seekers in question rely on this coding. The IR missiles would be unmodified weapons taken from inventory. The LaWS adjunct would simply contribute laser energy that heats the target and enhances its signature for the missile. While, at the ranges envisioned, this laser heating alone would not be sufficient to "kill" the target, it could definitely heat the target. It should also be noted that the laser "illumination" could potentially be used to preferentially select a specific target from among a group of targets for engagement by a missile. It is expected that these engagements could occur at ranges of two to four times the effective Phalanx gun engagement ranges. Use of LaWS in this manner would be exactly analogous to the use of a SAL designator for a SAL guided missile, such as the AGM-114 Hellfire. It is expected that similar rules of engagement would apply.

Direct Target Destruction by Laser Heating

Some threats are known to be vulnerable to direct destruction by the application of laser energy for an appropriate period of time. The currently envisioned system would be able to destroy a subset of naval threats at ranges comparable to, and in some cases greater than, the ranges achieved with modern, stabilized guns using EO fire control systems and modern ammunition. In the case of a LaWS adjunct, the addition of the laser would open new options for a firing/engagement doctrine and would be expected to conserve CIWS rounds for use on threats that are not appropriate for this laser power level. While the laser is often quoted as having an "unlimited magazine," the true number of threats that can be engaged by the laser in any period of time is limited by the required illumination time and by the time required to evaluate a kill and transition to the next target. Thus, for particular target velocities and numbers, the "effective laser magazine" might be added to the CIWS magazine to increase the total number of targets engaged by the combined system.

LaWS Accomplishments

A government/industry team, led by government technical personnel, have achieved significant accomplishments since the start of the LaWS program in 2007; specifically, the team:

- Conducted mission analyses
- Developed threat lethality estimates
- Performed industry surveys for critical components and subsystems
- Performed extensive trade-off analyses
- Designed a prototype system
- Constructed the system—the prototype director and mount (see Figure 3)
- Performed numerous laboratory-based tests of subsystems and the complete prototype
- Validated system operation with a full-up field test at high power using BQM-147A UAV target drones

Additionally, the team was able to minimize the cost of the prototype by leveraging hardware that had already been developed or procured for other applications, including an L3-Brashear tracking mount, a 50-cm telescope, and high-performance IR sensors. Some components were commercially procured, such as the 5.4-kW fiber lasers. Figure 4 shows three laser cabinets, containing two lasers apiece, resulting in a total power output of 32.4 kW. Other components, such as the beam combiner and much of the system software required for operation and target tracking, had to be specifically designed, fabricated, and tested.

The LaWS program achieved a highly successful field test/demonstration in June 2009 when the prototype successfully engaged and destroyed five drone targets at tactically significant ranges at the China Lake, California, test range (see Figure 5).

Additional Work to be Done

Since the LaWS prototype sits on a dedicated gimbal, much additional work needs to be done


L3 communications

Figure 3. Photo of LaWS During Testing at the Naval Weapons Center, China Lake



Figure 4. IPG Laser Cabinets



Figure 5. BQM-147A During LaWS Engagement

to place the weapon on the CIWS mount. The latter would require new control systems and optomechanical hardware for line-of-sight stabilization. Other aspects of the shipboard environment are also more stressful, and future mission areas may require an increasingly robust capability to deal with optical turbulence and the high-clutter environment of the ocean surface. Additional laser power might also be required. These modifications, depending on the level of capability desired, will require engineering modifications to the system. Engineering analysis and design to address these issues is currently underway at NSWCDD.

While the aforementioned engineering issues are important to address, there are additional technical issues that have yet to be analyzed. These issues are concerned with the potential utility of the system. Indeed, most of the detailed technical analyses and experiments performed thus far have focused on target destruction, with some effort expended on the issue of seeker damage/destruction. Developing credible lethality estimates for various potential threat targets is clearly very important, but one consequence of the lethality focus is that necessary, detailed, defendable technical analysis, analytic model development, and experiments have not been performed to explore the other functions/features that a CIWS Adjunct LaWS might provide to the overall ship combat system. Some of these contributions might become “routine” if the LaWS were available.

For example, a hard-kill engagement of a target by a Navy shipboard weapon is a relatively rare event, even during wartime conditions. On the other hand, ships in combat zones—and elsewhere—constantly have the problem of detecting potential threats, tracking them, identifying them, determining their intent, and providing warning. Thus, use of the LaWS system, at less than its full lethal potential, could become a daily, standard practice. It is still not clear how these potential benefits and capabilities could be measured or quantified to the satisfaction of key decision makers.

Likewise, other potential advantages of laser weapons—such as the potential for precision engagement, covert engagement, fire starting, graduated lethality, low cost per shot, and “unlimited” magazine—have not been subjected to rigorous technical analysis for feasibility, utility, and practicality. These investigations need to be performed and are gradually being addressed within the LaWS program.

Although the Phalanx CIWS system is currently installed on a number of Navy surface warships—either a single mount or a double mount—there are still significant numbers of ships that do not have a Phalanx system. It is highly desirable to make LaWS potentially available to virtually any ship that could benefit from the enhanced capabilities.

While the technical issues associated with the addition of LaWS to the Phalanx CIWS will be somewhat different from those associated with adding a LaWS system to other weapon systems—or the provision of a "stand-alone" LaWS—they do not appear to be insurmountable. For example, a LaWS beam director might be added to the stabilized Mk 38 Mod 2 25mm gun or the Mk 46 Mod 2 30mm gun. A LaWS beam director might be added to (or even substituted for) the Mk 46 EO Sight on DDGs or added to the trainable RAM launcher. Other options may exist as well.

The issue of defending combat logistics force ships, joint sealift ships, and certain support vessels from attacks from small boats or UAVs is also relevant. These ships often have little or no installed defensive capabilities for potential terrorist or pirate threats, and expeditionary security detachments do not have decisive warning or engagement capability. In addition, there are severe limitations placed on concept of operations (CONOPS) and rules of engagement due to the limited objectives/limited means of the various missions.

A system such as LaWS could provide graduated lethality from warning to destruction. It also could provide additional applications to minimize risk to sea base platforms and enhance sea shield capabilities against nonstate threats. If acceptable rules of engagement can be established, the advantages of graduated lethality might be extended to ships in port or entering/exiting harbors.

While considerable additional work needs to be done to produce a tactical system, the LaWS program's recent demonstration of capability provides strong evidence that a useful, tactical system could be produced within reasonable cost, volume, weight, and power constraints to provide the warfighter with a suite of additional tools to fight today's and tomorrow's wars.

REFERENCES

1. NAVSEA Notice 5400, Ser 09B/240, "Establishment of the Navy Directed Energy Weapons Program Office (PMS 405)," 4 January 2002.
2. NAVSEA Instruction 5400.101, Ser SEA 06/058, "Directed Energy and Electric Weapon Systems Program Office (PMS 405) Charter," 21 July 2004.
3. *Technology for the United States Navy and Marine Corps 2000–2035: Becoming a 21st-Century Force*, Naval Studies Board, National Research Council, National Academy Press, 1997, Volume 5: Weapons, Chapter 6, "Navy and Marine Corps Applications for Laser Weapons."
4. *Report on the Air Defense Against Unmanned Vehicles*, USAF Scientific Advisory Board, SAB-TR-06-01, August 2006.
5. "Counter Unmanned Aerial Systems (UAS)," *OPNAV Deep Blue Report 08-01*, August 2007.



THE ACQUISITION CHALLENGE ASSOCIATED WITH DIRECTED-ENERGY RDT&E

By Mike Kotzian

An already tense situation quickly escalated. Everyone within the combat information center of the Navy's newest all-electric ship suddenly realized that two surface-skimming, antiship missiles were bearing down on their destroyer. With less than 30 seconds to impact, the tactical warfare officer gave the order to fire. Seconds later, the first surface-skimming missile vanished from all tracking consoles. Another order to fire closely followed, and the second missile threat was also destroyed. Consequently, within a matter of 10 seconds from threat recognition to threat elimination, the Navy's newest all-electric ship was able to destroy two incoming threats by using one of the Navy's newest weapon systems—the free-electron laser.

Does this scenario of a Navy all-electric ship, employing a high-energy laser to shoot down enemy surface-skimming antiship missiles, sound like inevitable reality or unattainable science fiction? For scientists and engineers working on directed-energy systems for the Navy, the answer does not lie solely in the advanced technical challenges associated with developing directed-energy weapons. Rather, the answer also lies in how well scientists and engineers understand and adhere to the Department of Defense's (DoD's) Defense Acquisition Management System (DAMS) framework governing the development of new weapon systems.

EVOLUTION OF DEFENSE ACQUISITION

The way in which DoD identifies needs and subsequently develops, tests, procures, and sustains weapon systems has evolved over time. Today's acquisition foundation can be traced back to the Packard Commission report in 1986, where many of this report's recommendations became part of the Goldwater-Nichols DoD Reorganization Act of 1986. This evolution continued along three tracks:

1. Requirements moving from threat-based to capability-based
2. The resource allocation system adding execution reviews with concurrent program and budget reviews

3. The acquisition process attempting to incorporate a more flexible and tailored process

These three tracks form the Defense Support System organizational structure: the Joint Capabilities Integration and Development System (JCIDS) process; the Planning, Programming, Budgeting, and Execution (PPBE) process; and the DAMS process, respectively. These three processes operate as "systems of systems" and are referred to as the "Big A" acquisition process shown in Figure 1.[1]

While all three of these phases hold their own level of importance, the major focus for scientists and engineers at research and development (R&D) facilities is the "Little a" acquisition process. It is this "Little a" acquisition process, where the rules and processes are found, that governs how DoD goes about developing a new materiel solution to a validated warfighter requirement. These rules and processes are codified within DoD Instruction 5000.02, *Operation of the Defense Acquisition System*, which was issued in December 2008.

The acquisition framework associated with DoD Instruction 5000.02 is the DAMS structure. This framework, shown in Figure 2, consists of numerous strategically placed milestones and major program reviews to ensure proper programmatic oversight.[2] Each of the milestones has specific


Big "A" Acquisition Process
Effective Interaction Essential for Success
Planning Programming, Budgeting and Execution
Joint Capabilities Integration & Development System (JCIDS)
DOD 5000.2 Acquisition Process
Little "a" Acquisition Process
(Most Previous Efforts Focused Here)

Figure 1. Defense Support System Organizational Structure


• The materiel development decision precedes entry into any phase of the acquisition management system
• Entrance criteria met before entering phase
• Evolutionary acquisition or single step to full capability
User Needs
Technology Opportunities & Resources
A
B
(Program Initiation)
C
IOC
FOC
Materiel Solution Analysis
Materiel Development Decision
Technology Development
Engineering and Manufacturing Development
Post - PDR A
Post - CDR A
Production & Deployment
LRIP/IOT&E
FRP Decision Review
Operations & Support
Pre-Systems Acquisition
Systems Acquisition
Sustainment
= Decision Point
= Milestone Review
= Decision point if PDR is not conducted before Milestone B

Figure 2. DoD Acquisition Framework

criteria that must be satisfied before a program is allowed to further proceed along the DAMS. The program's Milestone Decision Authority (MDA) rests with the individual responsible for deciding if the milestone criteria have been met and, if so, for allowing the program to proceed to the next phase of the acquisition process. Designation of a program's MDA depends on a program's level of research, development, test, and evaluation (RDT&E) and procurement funding. For example, an Acquisition Category (ACAT) I program is defined as an eventual total expenditure for RDT&E of more than $365 million in fiscal year (FY) 2000 constant dollars or, for procurement, of more than $2.19 billion in FY 2000 constant dollars. In this case, for an ACAT ID ("D" refers to the Defense Acquisition Board (DAB)) the Under Secretary of Defense for Acquisition, Technology and Logistics (USD(AT&L)) is the MDA; for an ACAT IC ("C" refers to Component or Service), the MDA is the Head of the DoD Component or, if delegated, the Component Acquisition Executive.[3]

In addition, civilian and military workforce members within the DoD whose job responsibilities are deemed acquisition-related find themselves with a training requirement necessary to carry out their acquisition-related job responsibilities. Specifically, these workforce members are required to gain acquisition training and education with the passage of the Defense Acquisition Workforce Improvement Act (DAWIA) signed into law in 1990. The current certification process comprises three levels covering 16 different career fields. Each of these 16 career fields has a set of specific training, education, and experience requirements that must be met in order for an individual to achieve Level 1, Level 2, or Level 3 certification. The Defense Acquisition University (DAU) provides the necessary training classes required for the certification. DAU identifies "core-plus" training classes and continuous learning modules for each level of certification. The core-plus classes and modules are not required for certification but are identified as additional sources of information to assist individuals in becoming more knowledgeable about their career field beyond the minimum standards required for certification. The most up-to-date certification frameworks for all 16 career fields can be found at the following DAU website: http://icatalog.dau.mil/onlinecatalog/CareerLvl.aspx

Defense Acquisition Reform

The DoD acquisition environment is undergoing continuous change. The issuance of DoD Instruction 5000.02 marked the opening salvo of what has become seemingly constant updates, modifications, and guidance impacting how DoD procures weapon systems to meet warfighter requirements. In addition to DoD's issuance of DoD Instruction 5000.02, the Government Accountability Office published a stream of reports and findings that indicate significant cost growth and schedule delays in major defense acquisition programs. In 2009, Secretary of Defense Robert M. Gates proclaimed

a new way of doing business within DoD when it comes to weapon systems acquisition. Pressures are building for every program to maintain cost and schedule estimates while delivering the technical requirements originally developed to support the warfighter.

Moreover, there have been two major policy issuances. As previously mentioned, the first was DoD Instruction 5000.02 in December 2008. This update of the rules and processes governing DoD weapon systems acquisition primarily impacted the early part of the DAMS framework. The problem was that weapon system programs were failing their initial operational test and evaluation phases at alarming rates—many times traced to program offices attempting to design weapon systems with immature technology. Such failures were preventing those programs from proceeding to a full-rate production decision review and, more importantly, causing a repeat of some of the DAMS framework, which translated to increased costs and delayed initial operational capability timelines.

DoD Instruction 5000.02 attempted to solve this problem with three main emphases. First, a mandatory requirement was inserted for competitive prototyping prior to program initiation at Milestone B. The intent was to ensure a competition among contractors competing for a contract award. The theory was that such a competition would reduce technical risk, validate designs, improve cost estimates, evaluate manufacturing processes, and refine requirements. Reducing technical risks was especially important because weapon system programs were expected to demonstrate a technology readiness level (TRL) of six—where the system/subsystem model or prototype is demonstrated in a relevant environment—by the time a program reached Milestone B. TRLs are categorized on a scale of 1 to 9. A TRL of 1 is the lowest level of technology readiness, where scientific research begins to be translated into applied R&D. A TRL of 9 is the highest level of technology readiness, where the actual system is proven through successful mission operations. A TRL of 6 represents a major step up in a technology's demonstrated readiness. Using TRLs enables consistent comparisons of technical maturity across different types of technologies, giving program decision makers a common benchmark to consider when assessing program risk. Note that TRLs are meant to capture a level of technical maturity, not the probability of occurrence (i.e., the likelihood of attaining a required maturity level) or the impact of not achieving a level of technical maturity.[4]

The second emphasis was on a stricter adherence to systems engineering processes and technical reviews. Too often weapon system programs were not closely following systems engineering processes or avoiding due diligence when it came to the definition of successful exit criteria for a technical review. Consequently, all technical efforts must be outlined in a program's systems engineering plan. The program manager will use the eight technical management processes—decision analysis, technical planning, technical assessment, requirements management, risk management, configuration management, technical data management, and interface management—to manage the technical development of the system increments, including the supporting or enabling systems.[5] The program manager will use the eight technical processes—stakeholders requirements definition, requirements analysis, architectural design, implementation, integration, verification, validation, and transition—to design the system, subsystems, and components, including the supporting or enabling systems required to produce, support, operate, or dispose of a system.[6] Figure 3 provides an overlay of the new DoD Instruction 5000.02 and Secretary of the Navy (SECNAV Instruction) 5000.2D (Implementation and Operation of the Defense Acquisition System and the JCIDS), and shows the timing of specific systems engineering technical reviews as a program matures through the DAMS.

The third emphasis was a more prominent role of the MDA, starting with a mandatory requirement that all weapon system programs seeking a full or partial materiel solution must hold a Materiel Development Decision chaired by the MDA. Thus, the old Design Readiness Review was replaced with the Post-Critical Design Review Assessment chaired by the MDA. In short, the MDA was to become a more prominent figure in the oversight of a weapon system program's progress.

The second relatively recent major policy issuance was the Weapon Systems Acquisition Reform Act (WSARA) of 2009, implemented by Directive-Type Memorandum (DTM) 09-027 in December 2009. This DTM amended DoD Instruction 5000.02, the *Defense Federal Acquisition Regulation Supplement (DFARS)*, and associated business practices within the *Defense Acquisition Guidebook (DAG)*. The WSARA implementation brought about changes to policies and procedures across 13 categories. Some of the WSARA changes most relevant to the Navy directed-energy community include:

- Analysis of alternatives study guidance
- Acquisition strategies to ensure competition
- Competitive prototyping
- Developmental test and evaluation
- Systems engineering
- Preliminary design reviews
- Critical cost growth

THE ACQUISITION IMPACT

So why should the directed-energy community care about these acquisition policy changes? Because these policy changes impact the community's


Acquisition Milestones / Phases
PHASE I
A
PHASE II
PHASE III
B
PHASE IV
C
IOC
FOC
Materiel Solution Analysis (MSA)
System Requirements & Technology Development
System Architecture & Technology Demonstration
Engineering & Manufacturing Development
Production & Deployment
Operations & Support
Materiel Development Decision
Service Approved CDD
Prototypes
LRIP /IOT&E
FRP Decision Review
Sustainment & Disposal
Products
Acquisition Gate Reviews
1
2
3
4
5
6
PASS 1
PASS 2
Technical Reviews
TRA
SSR
IRR
TRA
ITR
ASR
SRR-I
SRR-II
SFR
PDR
IBR
PDR1
CDR
TRR
FRR
OTRR
SVR/ FCA/PRR
PCA
ISR
Technical Baseline
Preferred System Concept
System Specification
System Functional Baseline
Allocated Baseline
Product Baseline
Product Baseline
▼ Technical Readiness Assessment
▼ Software-Related Reviews
▲ Technical Reviews
▲ Program Reviews
○ Acquisition Review Gates

ASR – Alternate System Review
CDR – Critical Design Review
FCA – Functional Configuration Audit
FRR – Flight Readiness Review
IBR – Integrated Baseline Review
IRR – Integration Readiness Review
ISR – In-Service Review
ITR – Initial Technical Review
OTRR – Operational Test Readiness Review
PCA – Physical Configuration Audit
PDR – Preliminary Design Review
PRR – Production Readiness Review
SFR – System Functional Review
SRR – System Requirements Review
SSR – Software Specification Review
SVR – System Verification Review
TRR – Test Readiness Review

Figure 3. Systems Engineering Technical Review Timing

ability to develop, produce, and/or sustain directed-energy weapon systems. The ultimate goal of the directed-energy community is to deploy directed-energy weapons to the fleet. Accordingly, regardless of which phase or phases an organization in the community supports, its actions are impacted by the language in DoD Instruction 5000.02 and the WSARA of 2009. The more scientists and engineers in the organization are aware of governing policy documents like DoD Instruction 5000.02, the better their chances are of meeting DoD leadership's expectations in terms of cost, schedule, and technical effectiveness.

Actions have shown that DoD senior leadership has come to expect all weapon system programs to adhere to the current acquisition-related policy and guidance changes. As mentioned earlier, major weapon system programs have recently been canceled or restructured for not meeting DoD senior leadership expectations—something that rarely occurred previously. In today's environment, technology alone will not carry the argument for a program's survivability. Directed-energy weapons definitely carry the allure of a "Star Wars-like" capability, but these same weapon systems will need to show sustainable cost and schedule compliance if they are to come to fruition. Resources are too limited, and the warfighter has too many needs to allow unsustainable weapon system programs to continue. Therefore, everyone involved with the development, procurement, and/or sustainment of a directed-energy weapon system needs to have an adequate understanding of the acquisition underpinnings now governing DoD.

Summary

The proverbial "winds of change" are blowing across the DoD acquisition landscape. The management of major weapon systems dependent upon cutting-edge technologies—such as those of directed energy—cannot afford to conduct business in a manner reminiscent of bygone days. Everyone involved with the development, production, or sustainment of a directed-energy weapon system needs to understand the "rules of engagement" laid down by the most recent DoD acquisition policy guidance. Highly skilled scientists and engineers typically already understand the need for a structured systems engineering approach to problem solving. Today, though, more than ever, cost and schedule must be factored in as potential tradespace to deliver the ultimate goal: a cost-effective, directed-energy weapon system delivered in a timely manner while meeting the warfighter's requirements. Scientists and engineers who adhere to these recent acquisition changes will help their organizations achieve this goal, thereby ensuring that warfighters will be armed with the most technologically superior weapons possible.

References

1. Congressional Research Service Report 7-5700, 10 July 2009, p. 3.
2. Ibid., p. 8.
3. DoD Instruction 5000.02, 8 December 2008, p. 33.
4. *Defense Acquisition Guidebook*, 5 May 2010, paragraph 10.5.2.2.
5. Ibid., paragraph 4.2.3.1.
6. Ibid., paragraph 4.2.3.2.

THE BASICS OF ELECTRIC WEAPONS AND PULSED-POWER TECHNOLOGIES

By Stuart Moran

WHAT ARE ELECTRIC WEAPONS?

Most conventional weapons rely on chemical energy (explosives) as their destruction mechanism, either to explode on target, like bombs, or to create kinetic energy, like a bullet. Electric weapons are different. Electric weapons use stored electrical energy, rather than explosives, to attack or destroy the target. Electric weapons generally fall into two categories: directed-energy weapons (DEWs) and electromagnetic (EM) launchers. DEWs send energy, instead of matter, toward a target, and can be separated into three types: laser weapons, particle-beam weapons, and high-power microwave (HPM) or radio-frequency (RF) weapons. EM launchers use electrical energy to throw a mass at a target, thus making them distinct from directed energy. There are also three types of EM launchers: rail guns, coil guns, and induction drivers. All involve the use of strong magnetic fields to push against projectiles. While electric guns are an electric weapon, they are not a DEW.

High electrical powers and large energies are needed for all these weapons. Technologies for storing and controlling electric power are needed and are commonly called pulsed-power technologies. Electric guns are often associated with DEWs due to their common reliance on pulsed-power technology. The types of electric weapons are shown in Figure 1.


Electric Weapons
Directed Energy
Electromagnetic Launchers
High-Energy Lasers
Charged-Particle Beams
High-Power Microwaves
Rail Guns
Coil Guns
Induction Drivers

Figure 1. Types of Electric Weapons

There are a number of powerful advantages of electric weapons over conventional explosives:

- DEWs have a near-zero time of flight compared to conventional ordnance, allowing longer decision times and quicker reaction times.
- Electric weapons have a large "magazine" capacity, often limited only by the ability of the power source to recharge the system. The firing rate depends on how fast the system can be recharged, which in turn, depends on the available power source.
- The cost of engagement is greatly reduced. With increasingly sophisticated conventional weapons, the cost of practice rounds, such as a missile, can be millions. For an electric weapon, the cost per engagement is greatly reduced, making the attack of small targets (the asymmetric threat) less costly and training much more affordable.
- There is the potential for variable lethality, where the weapon effects can be controlled or attenuated to provide a warning or nonlethal effect. Otherwise, a full-power setting can be used to destroy the target.
- Electric weapons have the benefit of increased safety since less ordnance needs to be stored. Logistics costs less, and underway replenishment is easier since explosives are reduced or eliminated.
- Electric weapons can be used in conjunction with conventional weapons to heighten overall combat system effectiveness, such as knocking out electronics before engaging with a kinetic weapon.

Historically, the key Navy scenario for using directed-energy technologies has been close-in protection of naval vessels from antiship cruise missiles, particularly in a littoral environment. The ability of a DEW's speed-of-light engagement is particularly attractive under conditions of short warning times from supersonic stealthy missiles. However, increasingly difficult and problematic threats from nonmilitary aircraft and surface ships, countersurveillance platforms, fast patrol boats, unmanned aerial vehicles (UAVs), and terrorist inflatable boats or jet skis present different challenges. The threat has shifted from small numbers of expensive targets in open water to large numbers of small and cheap targets among neutral forces. The unique characteristics offered by DEWs, when compared to traditional weapon systems, allow them to be applied across a spectrum of threat roles, particularly in friendly or neutral-rich regions where precision pointing or less-than-lethal capability is paramount. The potential for HPM to counter electronics at levels below human effects makes them ideal nonlethal weapons. Electromagnetically launched projectiles allow longer range, shorter flight times, reduced reliance on air strikes and missiles, and safer storage and replenishment. With military budgets being squeezed, the low cost of directed-energy engagements, which often require just a few gallons of fuel, cannot be overemphasized. Instead of million-dollar missile shots, electric weapons allow new tactics, warning shots, and continual fire against large and small targets. They also allow inexpensive practice and training for improved readiness.

PULSED POWER FOR ELECTRIC WEAPONS

A useful rule of thumb is that a stick of TNT contains about a megajoule (MJ) of chemical energy, and this amount is often needed to destroy a military target. To destroy a target with an electric weapon, the electrical energy must also be deposited quickly. Surprisingly, a candy bar also has a megajoule of chemical energy, but it is released very slowly when we eat it. Many electric weapons require peak powers of more than a gigawatt (GW) or energies more than a megajoule. The time scales for delivery range from milliseconds to nanoseconds. As an example, delivering 1 MJ of energy in 10 μs requires 100 GW of power, which is more than a commercial power plant can produce. It is not practical to build continuous power supplies to directly drive most electric weapons. Consequently, pulsed-power technologies are needed to store energy at low power rates and release it quickly for weapon use. A pulsed-power system takes electrical power from a prime source (like a motor), stores it, and transforms the power to meet specific user requirements. The importance of a pulsed-power system is often underappreciated. For most electric weapon systems, the system size, weight, volume, and reliability are dominated by the pulsed-power chain. Pulsed-power components must be improved along with the weapon technology to make electric weapons systems practical. A block diagram of a pulsed-power system is shown in Figure 2.

Electrical energy can be stored in many ways, such as a battery (actually a chemical storage). A car battery has about a megajoule of energy, but it takes many seconds to drain it. A much faster method of storing electrical energy is in a capacitor, which can be discharged in milliseconds or faster. Inductive methods store the energy in the magnetic fields of a coil. This has the potential of achieving higher energy density than capacitors, but


Seconds
kWs
ms
MWs
µs
GWs
ns
TWs
ENERGY STORAGE 1 (INDUCTIVE)
• COIL
SWITCHING (OPENING)
• DENSE PLASMA FOCUS
• EXPLODING FOILS
PRIME POWER
• POWER SUPPLY
• WALL PLUG
• MOTOR
ENERGY STORAGE 1 (KINETIC)
• COMPULSATOR
• FLYWHEELS
ENERGY STORAGE II (CAPACITIVE)
SWITCHING (CLOSING)
• THYRATRONS
• SPARK GAPS
• MAGNETIC ASSIST
POWER CONDITIONING
• TRANSFORMER
• PULSE-FORMING
• LINES
WEAPON
• PULSED LASERS
• MICROWAVE DEVICES
• EM LAUNCHER
ENERGY STORAGE 1 (CAPACITIVE)
• CAPACITORS

Figure 2. Block Diagram of a Pulsed-Power System

when the supporting systems are considered, the technology becomes less attractive. Energy storage for electric weapons can also be done with chemical explosive energy, where an explosive force is converted into electrical energy using techniques such as flux compression. Energy can be stored in the inertia of rotating machines and flywheels, but the energy can be released only as fast as the flywheel or motor can be stopped, usually in seconds. In many cases, several stages of energy store are used where each stage is faster than the last. Once the energy is stored, it must be released quickly using a high-power switch. There are many types of switches. Perhaps the most common type for electric-weapon applications has been the spark gap. Many types of controlled spark gaps exist, including pin-triggered, laser-triggered, field distortion, and simple overvolted. To achieve high repetition rates, flowing oil or gas can be used to flush the hot spark products, or sealed gaps using special fast-recovery gases, such as hydrogen, can be employed. Other switches, such as vacuum tubes and solid-state switches, can be used if they can handle the voltages and currents needed. Solid-state technologies, such as thyristers, have become very capable in recent years. Once the energy is switched out, there is usually some additional power conditioning, where transformers or pulse-forming networks are used to provide the desired pulse shape, voltage, and current required for the weapon. For rapid firing rates or continuous use, high average input powers are needed.

All-Electric Ship

One of the major impediments to the development of electric weapons systems for Navy ships has been a lack of electrical prime power. Current surface combatant designs employ up to 90 percent of engine power mechanically dedicated solely to propulsion. These designs are unable to provide the tens to hundreds of megawatts (MW) of electrical power capacity required for many electric weapons. The solution is an electric-drive ship that uses all the engine power to generate electricity, enabling it to allocate power to weapons or propulsion as needed. In recent years, the Navy has been investigating cost-effective power-system options to meet future platform requirements.

High-Power Microwave (HPM) and RF Weapons

Microwave weapons are generally considered to use frequencies above a gigahertz, whereas lower frequencies are generally called RF weapons. These weapons are more powerful than electronic warfare systems and are designed to create extended disruption or permanent damage. An HPM weapon is considered to have a peak power of more than 100 MW, or energies above 1 J. The energy can enter a target through intended RF paths, such as target antennas (front door), or unintended paths, such as housing joints, cavities, and circuit wires (back door). Pulses ranging from a few nanoseconds to microseconds in duration can be sufficient to reset computers, cause loss of stored data, or cause microprocessors to switch operating modes. Nonlinear circuits and components can rectify signals and absorb energy outside of their normal operating parameters. Figure 3 illustrates some of the vulnerability areas on a missile body.

RF or HPM devices can be divided into narrowband or wideband systems, dependent upon the employed pulse length. Narrowband systems are similar to high-power radar pulses and produce RF radiation with a very narrow bandwidth (frequency coverage). The damage concept is to create enough energy in a target to overheat or overload electronic components. Wideband systems generally produce very short pulses (nanoseconds) and typically operate in lower frequency ranges. Wideband systems produce much lower average powers and rely on high-peak electric fields to produce reset or arcing of digital components. Creating short pulses—often only a few RF cycles long—generates a very broad frequency output to take advantage of a target's weak point. But, it also means that the energy is spread over many frequencies, so there may be very little energy at a specific vulnerable frequency. Vulnerability data is critical to estimate the effectiveness of HPM weapons. Ultimately, air breakdown will limit the amount of energy out of an antenna to around 1 MW/cm^2.

HPM devices can produce effects that range from denying the use of electronic-based equipment to disrupting, damaging, or destroying such equipment. HPM weapon advantages include all-weather capability, low precision pointing requirements, and effects persistence after the radiated EM energy "beam" has been turned off. One major advantage of HPM is that electronics are generally more vulnerable to high fields and high energies than humans. This provides the ability to attack electronics without harming people, which makes HPM an ideal choice for nonlethal applications.

Two major challenges of implementing HPM technologies into an operational weapon systems platform are:

1. Fratricide, or self-destruction, can be a problem because of the large areas affected by the sidelobes and near field of any meaningful HPM weapon system. Therefore, when attacking a target of interest with an HPM weapon, there is a greater risk of disruption to systems that were not intended to be targeted but fell within the sphere of influence. Host platforms, therefore, may need to undergo interference hardening.
2. With regard to battle damage assessment, kinetic weapons have the advantage of typically leaving visual evidence. HPM weapon systems do not leave large holes in a target but create more subtle influences as a result of attacking critical electronic components. Consequently, it can be more difficult to ascertain whether a target's capabilities have been sufficiently degraded or destroyed—and for how long—in determining whether a mission was successful.

For HPM system development, a fundamental challenge is the understanding of what it takes to affect the target. Coupling mechanisms, where EM energy enters and affects the target system, are extremely complex. The vulnerability of components is often vastly different if it is outside or inside a circuit board or enclosure. Effects depend upon the interactions with other components, connectors, and nearby conductors. The effects on a component can vary many orders of magnitude depending on frequency, orientation, cracks and seams, protective circuits, pulse energy, and duration. Research regarding effects on missiles has shown large variations not only between designs, but also between different serial numbers due to assembly methods, cable routing, and component variations. With the increasing use of commercial equipment by the military, such as computers and radios, effects are difficult to predict due to constant design and component changes. In general, electronics are getting smaller and operating at lower voltages, making them more sensitive to high fields. But smaller components often have lower pickup areas, and the proliferation of interfering signals has increased the amount of shielding on modern electronics. When



Figure 3. HPM Coupling Paths on Missile Body

target systems are located inside structures or buildings, it becomes even more difficult to predict. Efforts to predict reflections and interference inside complex structures become extremely complicated. Accordingly, generic electronics kill using universal waveforms is not likely. There continues to be a lot of hype about what RF weapons can do, but the idea that a backpack device can wipe out all electronics in a city is no more realistic than a hand-held laser cutting through a bank vault door.

High-Energy Lasers (HELs)

A laser generally produces a beam of coherent light at a specific wavelength dependent on the atomic structure of the lasing substance. Only certain substances have the atomic properties appropriate for producing laser light, and these are often limited in power. Lasers are characterized by the substance being lased (gas, liquid, or solid) and the "pumping" process (light energy, electricity, or chemical reaction). A resonant optical cavity provides the means for aligning the energy in the beam and extracting that energy. A military laser system also includes beam processing or beam-path conditioning, beam pointing and control and—for long-range applications—adaptive optics to compensate for the atmosphere.

Until recently, HELs have been driven by chemical energy, so very little electrical power or pulsed power was needed. Chemical lasers use the reactions of gases or liquids to create the excited energy states necessary for laser emission. Large chemical lasers and beam directors have been developed by the Navy in recent decades and have successfully ruptured fuel tanks and downed supersonic missiles. However, these lasers required high-velocity, chemical-reaction chambers and emitted hazardous gaseous by-products. They often operated at wavelengths where the atmosphere absorbed much of the energy. Absorption creates thermal blooming, whereby absorbed energy in the air creates a negative lens that defocuses the beam. Increasing the power of the laser increases the energy absorbed and worsens the problem. The Army and Air Force are developing chemical lasers for airborne applications, where atmospheric absorption is less of a problem. Recent Navy interest in HELs has concentrated on lasers that are electrically powered, rather than chemically powered, and that operate at shorter wavelengths to allow smaller optics and more efficient propagation near the water.

Small semiconductor (or diode) lasers use current flow through an electrical junction to excite electrons and create laser light. These lasers are very limited in power, so research has focused on using large numbers of lasers assembled into a coherent array. Semiconductor lasers also create efficient light to excite or "pump" other types of lasers. Solid-state lasers (SSLs) use crystalline materials mixed (doped) with elements needed for proper lasing. SSLs show strong promise for compact, medium-power HEL weapon systems. Scaling these systems up to megawatt levels creates extreme heat in the crystal material, making it very difficult to prevent internal damage. Forced cooling and the heat capacity of large masses are under study.

Fiber lasers—which use semiconductor diode lasers to pump a flexible, doped crystalline fiber (similar to a fiber-optic line)—have demonstrated high efficiency and relatively high power. The technology is being used in the welding and cutting industries. Methods of pumping large numbers of fiber-optic lasers and combining them are being investigated. An example is shown in Figure 4.

The free-electron laser (FEL) operates differently from a conventional laser. An FEL uses a high-voltage electron accelerator to push electrons through a magnetic "wiggler" to create light radiation across a tunable band of frequencies. The FEL is extremely complex and large, but scaling to very high powers may be possible. Perhaps the biggest promise of the FEL is the ability to design the laser at an ideal atmospheric propagation wavelength. Significant technical hurdles remain in reaching the status of a deployable FEL, in scaling the beam to megawatt powers and in providing the necessary engineering to turn a laboratory device into a weapon system of reasonable size. For Navy application, FELs will require improvements in areas of radiation shielding, high vacuum, high-current photo-injectors, and probably cryogenic cooling—all of which must be integrated into a ship's basic design.

Fiber lasers and SSLs are the leading-candidate Navy lasers for medium power, as FELs are for high power. All are electrically driven and can meet the requirement for shorter wavelength, capable of transmitting at the "maritime window" of approximately 1 μ.

HEL weapons' advantages include a highly directional and narrowly focused beam, providing:

- Minimal collateral damage
- Speed-of-light delivery
- Rapid retargeting
- Low cost of engagement

Disadvantages center on:

- Limited range due to atmospheric attenuation
- Weather limitations
- Low efficiency (often less than 10 percent)
- Need for eye protection
- Relatively large size and weight requirements



Figure 4. Drawing of Laser Weapon System (LaWS)

Long dwell times (seconds) will be needed for most targets. As with RF systems, there is a potential nonlethal or variable lethality capability since the energy can be easily defocused. A critical challenge is the understanding of a laser beam's propagation through a maritime boundary layer environment, where the sea and air interface creates turbulence and moisture gradients. Measuring the atmosphere and compensating for variations in real time may require adaptive optics or "rubber mirrors" that can be constantly adjusted to compensate for changes. Focusing a small spot at long range will require high beam quality and large optics, probably meter-size mirrors that are very highly reflective and very clean.

HELs in the future are expected to be able to focus energy to a spot size of much less than a meter at ranges of kilometers. This will necessitate very accurate target tracking systems, and precise stabilization and beam-pointing systems, both of which are difficult but should be feasible in the near term. Real-time atmospheric measuring systems will be needed for compensation techniques. Methods to protect the sensitive optical system from salt spray and corrosion will also be needed.

From a lethality perspective, three considerations need to be better understood before a HEL can be deemed a true weapon system:

1. Achievable spot size of beam on target at range
2. Amount of coupling into the target material
3. Subsequent effects of the damage inflicted

For the more severe threats, such as high-speed, antiship cruise missiles, HELs face the difficult task of engaging maneuverable, stealthy, inbound missiles. As such, a better quantitative understanding of the interactions among a laser beam's energy deposition, target material, and flight dynamics is needed.

Particle Beams

A particle-beam weapon is a directed flow of atomic or subatomic particles. These particles can be neutral or electrically charged. Neutral beams need to be used outside the atmosphere (in space), where charged particles would repel and fly apart. Charged-particle beams (CPBs) are easier to make and are used within the atmosphere, where air molecules can constrain the beam. A CPB weapon transmits matter—not just EM waves—like lasers and microwave weapons. The particles are near the speed of light and deposit their kinetic energy deeply into any target material. They have the potential to be highly destructive weapons and are very difficult to shield against.

Charged particles are produced by applying a strong electric field near a material that emits electrons. These electrons then pass through accelerating stages with high voltage gradients (often megavolts), which increase the electron's velocity. As the electrons pass each stage, the velocity increases until they approach the speed of light (become relativistic), at which point they have substantial energy to penetrate a target. The accelerating systems can be linear, but a recirculating design is more compact and can reuse stages. These systems are basically high-current versions of scientific particle accelerators.

Once the electron beam is produced, it must propagate to the target. High-velocity electrons will not go far before they collide with air molecules and lose energy. The fact that air molecules struck by the beam are heated and moved out of the way for a short period of time creates a rarified "hole" in the atmosphere through which a second pulse can travel farther. In this manner, a fast series of pulses can "hole-bore" to the target, each pulse going farther than the last. The final pulse must have enough energy to damage the target. The deceleration of electrons in the atmosphere causes

Bremsstrahlung radiation in the forward direction toward the target, creating gamma rays that, in turn, create X-rays and RF radiation.[a] These effects can cause electronic upset and "soft-kill" mechanisms even if the beam slightly misses the target.

The beam of electrons is typically a few centimeters in diameter. When a beam strikes a target, the energy is deposited deep in the material (the collision cross section is small because of the relativistic speeds) in microseconds (much faster than a laser), creating thermal shock that is very difficult to shield against. For an explosive target, there is also the possibility of causing a deflagration or low-order burn, disrupting the normal warhead mechanism.

Scientists studying CPB weapons made significant technical advancements in the 1980s, but the weapons are still far from being practical. A CPB weapon is technically very challenging and expensive to build. Studies project that the volume requirements necessary for a CPB system could be on the order of a 5-inch gun system. Advantages of a CPB weapon include rapid penetration, a deep magazine, all-weather capability, and soft-kill mechanisms for a near miss. Problems include complexity, size, limited range, and the need to demonstrate compact accelerators and propagation mechanisms.

ELECTROMAGNETIC (EM) LAUNCHERS

A number of technology concepts to launch projectiles exist using electrical energy. These systems rely on large currents in conductors, creating strong magnetic fields that drive a projectile. The velocity of a normal powder gun projectile is limited by the expansion speed of the explosive powder, and present military guns are reaching that limit. With an electric gun, the fields can push projectiles much faster, providing longer ranges and increased kinetic energies. The simplest version is an EM rail gun, shown in Figure 5.

In any conducting loop, the generated magnetic field tries to expand the loop. If everything is held in position, the only movable item is the conducting projectile, which moves down the rails in an attempt to expand the loop. Since megajouoles of projectile energy are needed for EM rail guns, energy storage


MAGNETIC FIELD GENERATED AROUND RAILS AS CURRENT FLOWS THROUGH CIRCUIT
LORENTZ FORCE ACCELERATES ARMATURE AND PROJECTILE DOWN BARREL
MAGNETIC FIELD INTERACTS WITH ARMATURE CURRENT, GENERATING A LORENTZ FORCE
SWITCH CLOSES, CURRENT FLOWS THROUGH RAILS & ARMATURE
ENERGY
CURRENT FLOWING IN THE RAILS CREATES A MAGNETIC FIELD, WHICH INTERACTS WITH THE CURRENT IN THE ARMATURE TO GENERATE A LORENTZ (JxB) FORCE
Millions of amps are needed!

Figure 5. Electromagnetic (EM) Rail Gun Concept

mechanisms that can store about 100 MJ are needed, along with the ability to discharge the energy in milliseconds. To generate useful forces, millions of amps of current are needed—a major challenge and significant loss mechanism. Large capacitor banks with very high-current switches are required. Spark gap switches have historically been the only option, but new high-current solid-state switches are now becoming available. Capacitor energy densities, too, have improved an order of magnitude in the last few decades. Rotating machines have also been considered because they are smaller than equivalent capacitor banks, but extracting the energy quickly, without tearing the machine apart, has been problematic. The launch energy of various projectiles is shown in Figure 6.



- 20 mm --0.1 Megajoules
- 76 mm --1 Megajoule
- 5”/54 --10 Megajoules
- 8”/55 --40 Megajoules
- 16” gun --300 Megajoules
- Aircraft --50 Megajoules (30,000 kg @ 50 m/sec)

Kinetic Energy of Conventional Launch Packages

Figure 6. Launch Energy of Various Projectiles

A rail gun is probably the most compact form of electric launcher. However, it requires direct electrical contact between the projectile and barrel rails, creating the potential for arcing, melting, and erosion. Coil guns use a series of sequentially fired coils around a “barrel” to push the projectile in stages. This does not require direct electrical contact, so it avoids rail erosion but requires a series of fast timed switches and more space. Linear induction motors are basically unrolled electric motors and have been used on electric trains and roller coasters, typically with magnetic levitating systems to avoid contact erosion. This concept is being developed by the Navy for launching aircraft. The energy to launch an aircraft is similar to a large-caliber projectile—more weight but less speed. The slower speeds are more suitable for rotating machines since the launch times are seconds rather than microseconds.[1] Electrothermal guns and electrothermal-chemical (ETC) guns use a combination of electricity and chemicals. Electrical energy is used to initiate chemical reactions that can produce lightweight driving gases, like steam, or allow more energetic propellants that are difficult to ignite in a conventional fashion.

Some advantages of electrically driven projectiles include:

- Higher projectile velocity (over conventional explosives)
- Very long range (>100 miles) with lower cost than missiles
- Time-critical delivery (because of shorter time of flight)
- Safer projectile stowage (minimal explosives)
- Potentially adjustable velocity levels, for better accuracy and controllable damage

The potential of having nonexplosive rounds and magazines is very attractive for the Navy. For long-range, large-caliber EM projectiles, the kinetic energy from the projectile velocity is greater than the chemical explosive energy in a conventional round traveling much slower. Therefore, damage can be equivalent even without explosives. System size and lifetime are still behind conventional systems, but getting close.

OUTLOOK

Challenges remain for many electric weapon concepts. These weapon systems appear promising to meet the increasingly important asymmetric threats with low-cost precision rounds. They also can be employed across the energy spectrum for nonlethal targeting. Electric weapon systems will, in many cases, continue to supplement existing kinetic weapon systems in the near term. Despite technology challenges, directed-energy and electric weapons hold great promise in offering the future warfighter unique combat capabilities not currently available.

ENDNOTE

a. Bremsstrahlung—a type of radiation emitted when high-energy electrons are decelerated. (German for ***braking radiation***)

REFERENCE

1. Shope, S. et al., *Long-Range Naval Fire Support with a Coilgun*, Sandia Report 2001-3832, February 2002.

SOLID MODELING OF DIRECTED-ENERGY SYSTEMS

By Joseph F. Sharrow

Not long ago, around the mid-1980s, development of most new mechanical systems—such as automobiles, consumer products, and military devices—was performed manually on a drafting table or drawing board, much like the present-day version shown in Figure 1. These tables and boards performed a necessary function, but they offered little assistance other than for drawing lines. Engineers used them to prepare layouts, or two-dimensional sketches of what they were designing. They then would take these layouts to a draftsman, who would create drawings of each part in the device. The drawings would subsequently be sent to a manufacturing facility.

This layout and drawing preparation process typically would need to be repeated multiple times because mistakes would be made, or design issues would be discovered late in the process. Similarly, the manufacturing process would sometimes require multiple iterations as well because of the inherent limitations in designing three-dimensional (3-D) devices on two-dimensional boards. This less-than-ideal process made it difficult to design and manufacture even mundane products and frequently resulted in things that just didn't work. With the emergence of early computerization, numerical analyses of more complex systems began to be performed. These analyses were conducted to ensure that the systems worked in the real world. For example, engineers might conduct a structural analysis of the forces in a loaded dump-truck bed to make sure that the frame wouldn't bend and fail. Because of the difficulty in performing these analyses, they would often require a specially trained group of structural engineers, expensive software, and large mainframe computers, limiting their use to only the largest, most well-funded companies or organizations.

EMERGENCE OF COMPUTER-AIDED DESIGN (CAD) AND SOLID MODELING

With the availability of smaller scale computers and more economical software in the mid-to-late 1980s, CAD was born, initiating a period of rapid improvement in the design process. This was driven, in part, by the introduction of software packages such as AutoCAD. Initially, these software packages only attempted to automate drawing lines by making wireframe (stick-figure) versions on the computer of what previously had been made by hand on the drafting board. This reduced the difficulty in making changes in the development process, but it still limited the engineer's pallet to a two-dimensional space. What was really needed was a 3-D method of design. Solid modeling


Solid Modeling in the Development Process
Need → Design/Analysis → Documentation → Manufacturing → Solution
Solid Modeling Software
Idea
Part
Part
Assembly
Part
Part
Part Drawing
Assembly Drawing
Machine Shop
Assembly Manual
Rapid Prototyping
CNC tool paths
Product
Structural
Thermal
Modal
Analyses

Figure 1. Drawing Board

addressed this need beginning in the late 1980s to early 1990s.

Solid modeling is analogous to taking blocks of clay and cutting and forming them into the shape of a solid part on a computer. These 3-D parts are then put together in an assembly, more accurately representing real-world devices. Though originally used only in a limited way for specialized applications in the aircraft and automobile industries, it wasn't until the 1990s that solid modeling experienced widespread availability and mainstream acceptance due to software packages such as Pro/ENGINEER. Figure 2 summarizes how Pro/ENGINEER and other similar packages fit into the development of new products. The general flow of the process moves from left to right.

Initially, nearly all 3-D solid modeling packages required significant computing and graphics display power, necessitating the use of large graphics workstations running the UNIX operating system. Rapid advances in computing and graphics power have since enabled nearly all packages to run efficiently on personal computers (PCs) and laptops, bringing solid modeling and analysis capability into the mainstream.


Need → Design/Analysis → Documentation → Manufacturing → Solution
Solid Modeling Software
Idea
Part
Part
Assembly
Part
Part
Part Drawing
Assembly Drawing
Machine Shop
Assembly Manual
Rapid Prototyping
CNC Tool Paths
Product
Structural
Thermal
Modal
Analyses

Figure 2. Solid Modeling in the Development Process

SOLID MODELING OF DIRECTED-ENERGY SYSTEMS

Engineers working in the Directed Energy Division at the Naval Surface Warfare Center, Dahlgren Division (NSWCDD), use solid modeling to develop hardware for nearly all of its programs. Both Pro/ENGINEER and SolidWorks are used extensively to develop new products in virtual 3-D space. Additionally, the structural simulation package within Pro/ENGINEER is used to determine stresses and natural frequencies of parts and assemblies. Consequently, these packages have enabled a single mechanical engineer in the Directed Energy Division and a draftsman in the Engagement Systems Department at Dahlgren to perform the design and analysis work that would have required an entire group of engineers and draftsmen just a few years ago. Today, collaboration among many organizations using similar packages has become commonplace. Insofar as solid modeling has become an indispensable tool for development and collaboration, its successful implementation requires proper training and experience before engineers can use it effectively, just as medical surgeons require training in the use of advanced robotic surgical devices before they can be used effectively. Thus, while these high-tech modeling systems not only have reduced the number of personnel needed for design and development, they have enabled the Navy to get significantly more bang for its buck while supporting warfighting needs. An example of how solid modeling is currently being used is discussed below.

NAVY LASER WEAPON SYSTEM (LAWS) BEAM DIRECTOR

The Directed Energy Warfare Office (DEWO) and Directed Energy Division at Dahlgren are currently developing the Navy LaWS for the Naval Sea Systems Command's Directed Energy and Electric Weapon Systems (DE&EWS) Program Office (PMS 405). The program's goal is to take advantage of currently available industrial laser technology and incorporate it into a future naval weapon system. As part of the development process, major subsystems have been integrated with a Kineto Tracking Mount (KTM) into a LaWS beam director. The KTM/beam director was modeled and analyzed using Pro/ENGINEER. Ultimately, the resulting LaWS will be installed on Navy ships on the Close-In Weapon System (CIWS) gun mount. During field testing in June 2009 at the Naval Air Warfare Center, China Lake, California, the prototype KTM/beam director successfully destroyed five unmanned aerial vehicles (UAVs). The actual beam director used in the China Lake testing is shown in Figure 3; the Pro/ENGINEER assembly model used for development is shown in Figure 4.

The LaWS effort took advantage of many aspects of solid modeling including collaboration, structural and modal analysis, and manufacturing drawing creation. The project required development of new, unique hardware, as well as the integration of electronic models from commercial vendors. The KTM model was provided by L-3 Brashear and was originally designed using Pro/ENGINEER. The beam-directing telescope model was provided by RC Optical Systems, Incorporated, and was originally made in SolidWorks. These models were combined with many new optical and structural components developed by the Directed Energy Division into a single, comprehensive assembly model. This model was instrumental in understanding the interaction of the many components, and its use increased accuracy and precision that would have been impossible with old-fashioned two-dimensional development processes. Figure 5 shows a cross section through the main portion of the beam director, revealing the complexity of the many parts and subassemblies required for such a device. In addition to modeling the mechanical components, the actual laser beams were also included to better understand their path through the various mirrors and optical devices in the beam director, and to better highlight any interference they might have with structural components within the KTM or telescope.

Numerous analyses were performed to make sure that everything worked the way it was intended. One major analysis addressed the telescope mount. To ensure that the beams were stable at range, the mount had to be extremely stiff. The best way to ensure this was to perform a structural analysis using the structural simulation package within Pro/ENGINEER. Figure 6 shows the results of that analysis: a displacement plot in which different colors represent how much the telescope will move when the KTM rotates at its maximum speed. The large cylindrical object simulates the mass of the telescope. The minimum amount of displacement is indicated by blue, and the maximum is shown in red. This analysis verified that the movement of the telescope, relative to the optical components within the optics breadboard, was acceptable and should perform well at the range specified by the program office.

After modeling and analysis were completed, manufacturing drawings of custom parts were created by the Engagement Systems Department to be


L3 communications

Figure 3. LaWS Beam Director



Figure 4. LaWS Beam Director Assembly Model



Figure 5. LaWS Beam Director Cutaway


Displacement Mag (WCS)
(in)
Deformed
Max Disp +4.8619E - 04
Scale 1.0000E+00
Loadset:LoadSell
4.862e – 04
4.500e – 04
4.000e – 04
3.500e – 04
3.000e – 04
2.500e – 04
2.000e – 04
1.500e – 04
1.000e – 04
5.000e – 05
0.000e – 00

Displacement – 250-lb Telescope – 2-G Lateral Load

Figure 6. Displacement Plot

sent to manufacturing facilities, such as machine shops. One example is shown in Figure 7, which shows the first sheet of the multisheet drawing needed to manufacture the large plates that support the telescope from the center platform of the KTM. One of these plates is also shown in the displacement plot in Figure 6.

Even though it would be possible for one person to do all of the modeling, analyses, and drawings for a particular program, a more efficient process takes advantage of using the best skills available by collaborating with other experts. Collaboration enables assembly, part, and drawing files to be sent electronically, eliminating the need for collocating personnel. Drawings for the LaWS program, for instance, were made using noncollocated personnel across base at NSWCDD. They could just as easily have been made using personnel from across the country.

The LaWS program exemplifies how the Directed Energy Division uses solid modeling to enhance the quality and effectiveness of Navy directed-energy capabilities. As a result, warfighters will be better armed with more effective weapons and capabilities for future naval conflicts.

Acknowledgment

The author would like to acknowledge the valuable contributions of the Engagement Systems Department's drafting group in support of numerous DEWO and Directed Energy Division programs.


NOTES:
1. SURFACE FINISH: CHEMICAL COAT (GOLD IRIDITE) PER MIL-DTL-5541, TYPE 1, CLASS 1A
2. INTERPRET DIMENSIONING AND TOLERANCING IAW ASME Y14.5M-1994.
G
A
C
D
E
PLATE, ADAPTER, SHELF, CENTER
D 07609
TSS-005
DEPARTMENT OF THE NAVY

Figure 7. Manufacturing Drawing

A FUNDAMENTAL KEY TO NEXT-GENERATION DIRECTED-ENERGY SYSTEMS

By Directed Energy Division, Electromagnetic and Sensor Systems Department

Imagine an explosive ordnance disposal (EOD) unit on a routine scouting patrol deep in the notorious "Triangle of Death" south of Baghdad, where Marines, Sailors, and Soldiers frequently find themselves exposed to improvised explosive devices (IEDs). Fortunately, this newly outfitted unit is equipped with the latest unmanned, mobile, remote-controlled, radio frequency (RF) transmitter used as a directed-energy weapon (DEW). The integrated system provides comprehensive IED prediction, detection, prevention, and neutralization capabilities. Lightweight, pocket-sized transmitters carried by each warfighter constantly communicate sensor intelligence, key vital signs, critical conditions, and location telemetry to a geostationary satellite (GEOSAT). It intercepts, collects, and retransmits intelligence and situational awareness data simultaneously to any command post in the world and to each member of the unit on patrol. Highly efficient, miniature, switch-mode, RF amplifiers with high-power density (small size and weight with high-power output) enable these visions of future capabilities as their systems' transmitter backbone.

To civilians, the miniaturization of modern wireless (electromagnetic) devices is considered a mere convenience or luxury, i.e., Blackberries, mobile phones, and high-speed wireless network connections. To the next-generation warfighter, miniaturized, wireless, directed-energy (DE) systems open the door to the realization of a whole new set of effective and efficient wireless modalities. And while the capabilities mentioned in the above scenario are not yet available to warfighters, researchers believe they have uncovered the key to next-generation DE systems leading to the miniaturization of DE devices.

NEXT-GENERATION DE SYSTEM REQUIREMENTS

At the Naval Surface Warfare Center, Dahlgren Division (NSWCDD), key system requirements for effective next-generation DE systems are being researched and developed for applications to counter IEDs, to detect explosively formed penetrators (EFPs), to neutralize explosives, and to predict threat locations. Next-generation DE systems must yield a high probability of mission success and be inherently safe to operate. By design, they must minimize or eliminate the risk of hostile attack or collateral damage especially during screening missions. Considering the DEW example above, practical

080102-N-1132M-006 SHEIK SA'ID, Iraq (2 January 2008) U.S. Army Soldiers attached to 3rd Squadron, 2nd Cavalry Regiment patrol and search for weapons or Improvised Explosive Devices (IEDs) during a clearing mission. (U.S. Navy photo by Mass Communication Specialist 1st Class Sean Mulligan/Released)

next-generation DE systems must be physically characterized by:

- Low mass (weight)
- Small size (volume)
- High-power output with respect to size or high-power density
- High efficiency for extended mission use
- Minimized prime power and cooling support
- Portability
- Mobility
- Configurability

They must also ensure a high probability of mission effectiveness. The DEW must be easily transportable and agile, adapting to the immediate, local military mission requirements in various warfighting environments. Additionally, DE systems must be mechanically robust and able to withstand the shock and vibration of combat missions in rough and rugged environments. The key requirement—efficiency—fundamentally facilitates all required characteristics, including mass and size.

Moving Beyond Requirements

Scientists at NSWCDD, sponsored by the Office of Naval Research (ONR), are researching and developing key system requirements for effective next-generation DE systems to counter IEDs, to detect EFPs, to neutralize explosives, and to predict threat locations.

Researchers at NSWCDD are leading the way toward realizing small, lightweight, RF transmitters using high-power, solid-state, switch-mode amplifiers, theoretically 100 percent efficient. These practical switch-mode amplifier realizations are at least 1/100 the volume and weight of any commercially available linear solid-state amplifier of comparable power output. The challenges included assessing what type of active amplifier device and operation would provide the greatest power density (power output per unit volume and mass) with its necessary auxiliary systems, such as prime power generation and cooling of waste heat. Such a device also needed to provide sufficient output power based on required standoff range and IED system-coupling efficiency while also maintaining a manageably-sized, easily transportable system. Researchers initially considered tube-based systems, but large, heavy, direct-current (DC) power supplies are required, and typically 40 percent of the input power is dissipated in heat, which negates any possibility of miniaturization.

Upon a practical review of amplifier-class operations and suitable active amplifier devices, however, research pointed to contemporary switch-mode amplifier schemes (e.g., Class-E and Class-F) using solid-state technology—such as the high-electron mobility transistor (HEMT)—as satisfying the high-power density and abusive mechanical requirements for expected worst-case transportation and operation in a rugged environment. To significantly impact reduction of size and weight, practical, high-efficiency thresholds were defined for next-generation DE systems at 90 percent and greater. The key technology enabler to realize amplifier high efficiency in high-power amplifiers up to 60 kW was found in exploiting contemporary switch-mode amplifier architecture with efficient power combining. Particularly, switch-mode schemes in Class-E and Class-F operation as solid-state, active-hybrid planar topology designs were found to be necessary and sufficient for DE applications. These analyses led to a novel, Class-E RF switch-mode amplifier design. A Class-E RF switch-mode amplifier can theoretically operate at 100-percent efficiency. For every input watt supplied, an RF output watt is produced. The conductors and dielectric substrate of the hybrid planar load network and the commercial off-the-shelf (COTS) transistor all exhibit some small degree of power loss, suggesting an estimated practically realized efficiency of 90 percent.

Moreover, the amplifier under research consisted of a novel microwave load network operating with high-power output at ultrahigh frequency (UHF). This research led to the state of the art in Class-E designs leading by hundreds of watts, several hundred megahertz in frequency, and roughly 10 percentage points in efficiency. A common, solid-state, high-power amplifier design technique sums the phase and amplitude of smaller amplifier units to the large values required for DE systems. A practical hardware limitation exists that limits the theoretically infinite number of fixed RF output power units to a finite number. Approximately 60-kW RF output power sets the boundary as the largest hardware realization. By applying spatial power combining in the propagating medium, phased-array antennas can be employed with constructive wave interference in air that would allow sufficient RF power densities on target, based on the number of elements in the array. This technique eliminates the traditional hardware necessary to power combine the smaller power-amplifier elements, realizing a much simplified DE system with enhanced power density in the transmitter, and reduced mass and volume.

The key to ultrahigh efficiency in a switch-mode amplifier, such as Class-E or Class-F, is found in zero-voltage switching (ZVS). Here, the load network is not only designed to be resonant at and around a particular desired switching frequency, it must simultaneously act to force the voltage across the switch to be zero when current flows and when it switches off; hence, theory suggests that no power is dissipated because the product of current through, and voltage across, the switch is zero. It is this aspect of the design that makes the job of switch-mode amplifier realization difficult. Of course, in practice, a small voltage exists for a very short time during the switching action, resulting in a small amount of input power being dissipated in heat. This theoretical description also assumes that all components are ideal (i.e., no impedance to current flow exists in the switch when turned on). All realistic switches exhibit finite impedance when turned on, which does dissipate some wasted energy, but again, this is very small in modern HEMT devices using the ZVS technique.

Class-E switch-mode amplifier theory development began in the United States during the 1960s, with details published in 1975, although some earlier reports were published in Russia. Lumped element electrical components (RF choke inductors and metal film capacitors) were initially used in lower frequency (3 to 30 MHz) prototypes. As engineers attempted higher frequency designs in the very high frequency (VHF) range, solid-state transistor switch parasitic intrinsic and packaging elements found inside the transistor began to be used as some of the key components necessary for ZVS. These parasitic elements included stray capacitance caused by differences of potential between parts inside the transistor and inductance caused by bond wire length that is used to connect the transistor to accessible terminals in its packaging. At microwave frequencies, these parasitic elements become sensitive, invoking unintended significant changes to load networks designed to operate with the transistors. Intrinsic elements include drain-to-source breakdown voltage capability and peak current capability. As the need for higher frequency operation and higher power increased, constraints of key transistor parameters became difficult to produce in traditional silicon technology:

- High instantaneous transient (peak) current capability through the transistor
- Moderate breakdown potential across the transistor
- Low output capacitance

Only within the past few years have transistor manufacturers produced COTS transistors that meet the required capabilities necessary to operate in switch mode for microwave frequencies and

081107-N-1120L-072 RAMADI, Iraq (7 November 2008) Joint EOD Rapid Response Vehicles (JERRVs) assigned to Naval Mobile Construction Battalion (NMCB) 7's convoy security element are secured following an escort mission from a forward operating base. The Cougar-type JERRVs are employed by coalition forces for escort and logistics missions, and to protect personnel from IEDs. NMCB 7 is deployed to U.S. Forces Central Command to provide contingency construction support to coalition forces in support of Operations Enduring Freedom and Iraqi Freedom. (U.S. Navy photo by Mass Communication Specialist 2nd Class Michael B. Lavender/Released)

high-power output. Selection is still somewhat limited for designers.

New transistor technology known as gallium nitride (GaN) HEMTs—using state-of-the-art manufacturing processes with GaN on silicon carbide materials—now facilitates Class-E high-power amplifier (100-W) designs at ultrahigh frequencies. The design process for switch-mode amplifiers is radically different than linear amplifiers, so engineers have tended to continue using linear amplifier design techniques due to familiarity, rather than advance to the switch-mode designs. Today, the Class-E and Class-F unit power output (greater than 100 W) capability and upper frequency limitation is based on a lack of available HEMTs with the necessary parameter capabilities.

Most recently, transistor manufacturers have limited their investment in the Class-E amplifier solid-state switch market due to no commercial market mandate. An assortment of presently available HEMTs provides a low-power capability in terms of 1- to 10-W output power for Class-E amplifiers in the cell phone market. The need remains to continue advancing in commercially manufactured HEMTs with key capabilities necessary to realize larger unit power output, hundreds of watts to a thousand watts, for practical implementation in DE systems.

POSSIBLE MULTIPLE APPLICATIONS

Directed-Energy Weapon Systems

Expanding on the vision of the next-generation DEW system mentioned at the beginning of this article, further imagine that EOD scouts detect a laser fluorescence signature of C4 high explosive and chlorine outgasses in the vicinity of an abandoned vehicle 2-km north of their current position. An electronic support measure (ESM) team on board an approaching clearing vehicle initiates RF jamming and electromagnetic surveillance procedures. Electronic specialists also scan the area with ground-surface differential thermography—particularly to detect possible buried IEDs and EFPs or their tiny command wires, crush wires, or pressure plates—while clearing a pathway to the abandoned roadside vehicle.

Upon arrival at a 500-m safe distance, the EOD specialists command the RF transmitter's robotic platform, also equipped with sensitive gamma-ray planar and computed tomography (CT) imaging to navigate toward and around the vehicle, interrogating every possible hiding place. It discloses an IED in the fuel tank. The specialist lifts the transmitter arming safety and commands the remote transmitter to radiate a prescribed dose of RF energy directed at a carefully chosen component of the vehicle-borne IED (VBIED) system. Without entering the vehicle, the advanced screening system detects and defuses the deadly IED buried within the rusty, metal vehicle chassis. Within minutes, the suspected VBIED threat is entirely neutralized, with absolutely no wounded warfighters or casualties.



Pictured here is the National Aeronautics and Space Administration/National Oceanic and Atmospheric Administration (NASA/NOAA) Geostationary Operational Environmental Satellite-P (GOES-P) launching from Cape Canaveral Air Force Station, Florida, aboard a Delta IV rocket procured by Boeing Launch Services on 4 March 2010. Built by Boeing Space and Intelligence Systems, GOES-P will provide NOAA and NASA scientists with data to support weather, solar, and space operations, and will enable future science improvements in weather prediction and remote sensing. Additionally, GOES-P will provide data on global climate changes and capability for search and rescue.

Mobile Ad-Hoc Wireless Network (MANET)

Beyond IED detection and neutralization, imagine an expeditionary unit on patrol, with each member equipped with an RF transceiver about the size and weight of a cigarette pack with an ultrahigh-efficient switch-mode amplifier. The miniature transceiver constantly communicates sensor intelligence, key vital signs, critical conditions, and location telemetry to a GEOSAT. This small switch-mode amplifier has the needed output power to reach an altitude of 35786 km, where the GEOSAT intercepts, collects, and retransmits this intelligence and situational awareness data to any command post in the world and to each member of the unit on patrol simultaneously. The expeditionary unit, spread out over a wide area with large interspacing, shares the situational awareness and intelligence data of each other at the speed of light. Thus, near real-time, worldwide communications with ubiquitous secure access from the battlefield is possible in a multiple-input, multiple-output (MIMO) architecture. The same system could provide a soldier-to-soldier MANET.

Next-generation switch-mode RF amplifier designs could also optimize payload weight and volume on board new communication satellites while supplying higher power density and making efficient use of the solar power supply budget. Improved switch-mode amplifier power output, when combined with enhanced antenna design, would minimize Earth-station antenna size requirements. The recently launched satellite shown at left demonstrates an example of the latest antenna technology.

Looking Forward

Miniaturizing next-generation DE systems opens up a whole new world of applications to support warfighters in ways unimaginable just a few years ago. Reduction of transmitter mass and volume, accompanied with high efficiency, creates a welcome trickle-down effect. Low profile, small, lightweight DE systems means:

- Less vulnerability to attack
- Greater mobility and maneuverability
- Simplified logistics with less fuel-supply demands
- Less impact on the environment

Clandestine operations, too, could be executed with greater ease and simplified logistics support. In the case of MIMO MANETs, miniaturized high-power density transmitters could further expand capabilities for the warfighter, enabling them to carry high-power transmitters to communicate with satellites or other supporting platforms. The



satellite industry itself could benefit from miniaturized switch-mode amplifiers with much higher power density microwave transmitters, resulting in reduced payload mass and volume; this also reduces Earth-station antenna gain and size requirements.

CONCLUSION

NSWCDD is meeting the demanding requirements of next-generation DE systems with Class-E RF transmitter switch-mode amplifiers designed to operate at ultrahigh efficiency, greater than 90 percent. Having discovered the key to next-generation DE systems, researchers at NSWCDD are focusing on the urgent need to counter IED systems with small, lightweight, highly efficient transmitters that use switch-mode amplifiers. Considering the multiplicity of additional applications, all advancements made in amplifier counter-IED applications can be transferred to other applications in the future. Accordingly, while the capabilities suggested in this article might seem somewhat far-fetched, in reality, they are realizable in the near term. It is projected that NSWCDD will soon have its first 250-W UHF amplifier unit prototype ready. These units will fit in the palm of an average-sized adult's hand and can be power combined to the level necessary for platform and mission requirements. A fully realized, fieldable DEW system prototype is possible in just a few years.



ACTIVE DENIAL ARRAY

By Randy Woods and Matthew Ketner

Active Denial Technology (ADT)—which encompasses the use of millimeter waves as a directed-energy, nonlethal, counterpersonnel weapon—has the potential to provide an important new escalation-of-force capability to U.S. operating forces. ADT projects a focused beam of 95-GHz millimeter waves to induce an intolerable heating sensation on an adversary's skin, repelling the individual with minimal risk of injury. More than a decade of research has established the biological and behavioral effects of ADT for large spot size systems, such as Active Denial System 1 (Figure 1). While the effects of this large spot size system have been successfully established, the technology that produces those effects has the potential to progress in a number of ways, particularly with the development of smaller, lighter, and lower-cost systems.

One research effort focuses on the development of smaller, lighter, and lower cost ADT demonstrators that produce commensurate "ADS-effects," with effective spot size and power densities on target. In support of this effort, the Joint Non-Lethal Weapons Program (JNLWP) sponsored the Naval Surface Warfare Center, Dahlgren Division (NSWCDD) to develop a "smart target system," which measures the millimeter-wave beam using fast-response, 95-GHz diode detectors. NSWCDD subsequently developed and tested the W-Band Beam Diagnostic Array to characterize the system's beam with a temporal resolution of 30 Hz and a high spatial resolution of 1 inch.

The current method of measuring the 95-GHz beam is to use carbon-loaded Teflon (CLT) to produce an average power beam image. This method works as the CLT is exposed to the system's beam. The material heats, over a period of seconds, proportional to the magnitude of the radio frequency (RF) field, resulting in an image as shown in Figure 2. After the exposure, the specific heat capacity of the CLT can be used with the temperature increase in the CLT to provide an indication of the total energy deposited in the material. This method produces a good representation of the average RF field; however, any peak variations in the beam are averaged out.

To allow for high temporal-resolution measurements of the 95-GHz beam, a high-density, 95-GHz diode-detector array was commissioned by the Joint Non-Lethal Weapons Directorate (JNLWD), and was designed and built by NSWCDD, with support from Millitech, Inc. The array consists of a center 11 × 11 matrix (shown in Figure 3) with four removable arms that can be attached (shown in Figure 4), resulting in a measurement area of approximately 1 × 1 m.



Figure 1. Active Denial System 1

Each element's profile consists of the individual horn antenna from the array, an attenuator, a detector, and a SubMiniature version A (SMA) connection to the digitizer circuitry. This configuration allows for the power received from the antenna to be attenuated and converted to a direct current (DC) output capable of being measured by an analog-to-digital converter. The machined antenna elements provide a uniform effective area for each element, allowing field strength (W/cm^2) to be converted into power received (W or dBm). The aperture antennas also provide an impedance match between free space and the waveguide system. A cross-sectional view of the array element is shown in Figure 5, followed by a signal flow diagram shown in Figure 6.



Figure 2. CLT Representation of Small, 95-GHz Spot

The basic principle of operation behind the array is that the derivative of the diode detector's power vs. output voltage curve is very repeatable between detector elements. Therefore, when the detector elements arrived at NSWCDD, each detector element was paired with a variable


34.00cm
3.00
3.00
3.00
3.00
3.00
3.00
3.00
3.00
3.00
3.00
34.00cm
3.00
3.00
3.00
3.00
3.00
3.00
3.00
3.00
3.00
3.00

Figure 3. Main Array Face



Figure 4. Full W-Band Array

attenuator and calibrated as a single unit. The calibration was accomplished by inserting a known input power of +5 dBm into the input of the attenuator and setting the DC output voltage at a predetermined millivolt (mV) output. This allowed the detector's individual offset voltages to be removed and caused the detectors to behave in a repeatable manner. The attenuator is able to be adjusted by varying the depth that the aluminum nickel card is inserted into the section of waveguide.

The final section of the electrical system converts the DC voltage output from the detectors to a digital signal to send back to the operator station. For this, it was determined that a 16-bit digitizer would be required to enable measuring the microvolts output by the detectors on the low end of their range, while still allowing the digitizer to measure the full output voltage of 1.8 V for high-input powers. Also, due to the proximity of the operator to the array and overall system flexibility, it was determined that Ethernet communications would provide a sufficient means of reading the system data.

To display the data to the operator, a two-dimensional array is populated and displayed for the user (shown in Figure 7). This allows values to be


4.0
0.005
0.375
CIRCUIT BOARD ASSEMBLY
1.5
0.70
ALUMINUM SHEET
KAPTON FILM
SMA TO SMB
CABLE
HORN ARRAY
– KAPTON FILM
– GAIN
– S11
ATTENUATOR
– TEMPERATURE
– SETTING ACCURACY
DETECTOR
– TEMPERATURE
– MEASUREMENT
ACCURACY
BOARD
– DIGITIZATION ERROR
– SIGNAL LOSS

Figure 5. Cross-Sectional View of Array Element


W/cm^2
ANTENNA
$A_{eff} = \frac{\lambda^2}{4\pi} \cdot G$
dBm
ATTENUATOR / DETECTOR
mV(DC)
ATTENUATOR / DETECTOR
x32
MUX
+1.25
ADC

Figure 6. Signal Flow Diagram


Intensity Graph 3
Y
X
Amplitude
0
1
2
3
4
5
6
7
8
9
10
11
2.10
2.00
1.90
1.80
1.70
1.60
1.50
1.40
1.30
1.20
1.10
1.00
0.90
0.80
0.70
0.60
0.50
0.40
0.30
0.20
0.10
0.00

TL Temp 2: 75.726

MAX Main Array: 2.00892

TR Temp 2: 76.333

BL Temp 2: 77.571

BR Temp 2: 74.187

Cursors:	X	Y	Z
Cursor0	6	4	0.61

Figure 7. Array's Operator Interface Showing a Small Spot Source

read directly from the display corresponding to the watts per centimeter squared (W/cm^2) present at the array face. Data also is recorded so that it can be viewed later in a player application, such as a video file, or it can be viewed in a spreadsheet application, frame by frame. The data shown in Figure 7 is representative of small-source testing performed recently and very clearly shows the beam profile.

Conclusion

NSWCDD engineers successfully met the W-band array's design goals of providing a high temporal-resolution image of 95-GHz beams. The system has been tested against two active denial systems, providing good agreement with the currently accepted methods, as well as valuable information regarding the system's beam characteristics. These accomplishments will allow future system development to take advantage of this better understanding to possibly reduce system size and increase the effective range. A better understanding of the 95-GHz beam helps to facilitate future ADT development for this much-needed, nonlethal escalation-of-force capability for U.S. warfighters, homeland defenders, and law enforcement personnel.



DIRECTED ENERGY IN THE MILITARY ENVIRONMENT

By LT Leedjia Svec, Jeremy Beer, and Dave Freeman

The military operates in the land, air, and maritime environments. In each of these environments, lasers and laser devices are increasingly being seen and used in a variety of ways. Accordingly, the military must protect itself and civilians from the potentially dangerous effects of lasers and other directed-energy devices.

Lasers are being used on the ground to determine the intentions of people who approach checkpoints and to dissuade aircraft from entering restricted airspace. Laser weapons are also being developed for use in the maritime environment. With the use of lasers comes the requirement for eye protection. The eye is particularly sensitive to lasers and its anatomy includes optical components that amplify the power of incoming light. Consequently, the potential for injury or blinding is great.

Naval Medical Research Unit – San Antonio (NAMRU-SA) is poised to lead the way in researching and testing laser glare devices and laser eye protection. The mission of the NAMRU-SA is to conduct medical, dental, and directed-energy biomedical research, which focuses on ways to enhance the health, safety, performance, and operational readiness of Navy and Marine Corps personnel, and addresses their emergent medical and dental problems in routine and combat operations. NAMRU-SA was officially commissioned on 6 May 2009 and is a subordinate command under the Naval Medical Research Center (NMRC) in Silver Spring, Maryland, reporting to Navy Medicine Support Command (NMSC) in Jacksonville, Florida. NAMRU-SA consolidates the Naval Health Research Center Detachment Directed Energy Bioeffects Laboratory, the Naval Institute for Dental and Biomedical Research in Great Lakes, and the NMRC Combat Casualty Care research function. As part of the Base Realignment and Closure (BRAC) 2005, NAMRU-SA has moved to Fort Sam Houston. Two new buildings that have been constructed are the Battlefield Health and Trauma Research Institute and the Tri Service Research Laboratory. A conceptual drawing of the NAMRU-SA Tri-Service Research Laboratory (to house directed-energy research) is shown in Figure 1.

Many factors must be considered when lasers operate in military environments. On the ground, lasers offer a greater likelihood of close contact exposure. In aviation and maritime environments, the mobility of lasers is limited to permanent fixtures on aircraft or ships, so target acquisition can be much more complicated. Often ignored, but just as important and common to all environments, are the psychological factors that need to be explored. These factors include clarifying intentions, communications, and effectiveness. In certain situations,

Figure 1. Naval Medical Research Unit – San Antonio Tri-Service Research Laboratory at Fort Sam Houston, San Antonio, Texas (artist's concept)

sometimes lasers are coupled with other modalities, such as auditory instructions.

On the ground, laser exposure has been shown to interfere with driving vehicles, making color judgments, and target shooting. In aviation, lasers can interfere with pilot vision, causing afterimages, glare, or temporary ocular injury, with attendant effects on navigation and control. In the maritime environment, lights frequently are used to signal a variety of messages, from direction (left, right, etc.) to more complicated messages such as "man overboard." More prolific use of lasers underscores the need for laser eye protection, a dynamic area of research, which must respond to changing threat wavelengths and changing environments. Figure 2 shows NAMRU-SA personnel executing an operational field test at Kennedy Space Center, July 2009.

Recent studies undertaken by NAMRU-SA have investigated the use of laser dazzlers on sailors in small boats.[a] In these studies, participants were exposed to the laser glare at different angles and distances, in both day and night conditions. Study protocols were approved in accordance with the Institutional Review Board in compliance with all applicable federal regulations governing the protection of human subjects. Participants were given a survey assessing their subjective response to the laser, as well as a more objective visual eye chart. The



Figure 2. NAMRU-SA personnel execute operational field test at Kennedy Space Center, July 2009, in which a nonlethal laser prototype is evaluated for power delivery (stability and beam propagation) at range and human visual effectiveness aboard a maritime target.

results suggested that participants were most affected by the laser at night when they were looking straight at it (as opposed to many degrees away) and at the closest exposure distances. The most surprising finding, however, was that some participants reported being drawn to the laser rather than away from it, especially at farther distances. Participants remarked that they couldn't tell what the signal was, so they would want to go closer to find out. This illustrates that the assumption (by some)—that distant laser lights will deter and repel innocent mariners—might not always be true. Further research is needed to verify this finding, however, before employing laser glare devices in the maritime environment. Figure 3 shows NAMRU-SA personnel executing operational field tests, which were conducted at Cheatham Annex, Virginia, and Panama City, Florida, in 2008–2009.



Figure 3. A compact hand-held laser is evaluated for effectiveness in maritime defense against small-boat attacks.

These studies also brought the factor of communication to light. Participants remarked that "green is not a threatening color," and some thought "it could be a signal for help." Many felt curious about the "blinking light" used in the study and would go closer or try to contact the vessel to determine the intent of the message. Green lasers are used because they are more visually salient; however, they may not be as psychologically salient. Participants remarked that if the signal were paired with another signal, such as an auditory one, then the message of "warning" or "do not come closer" might be clearer.

Lastly, these studies brought to light the matter of effectiveness. Laser glare devices are used to stop or alter the behavior of the recipient, but one study yielded mixed results. At close distances, participants noticed the signal, felt affected by it, and reported that their behavior changed in the manner desired by the person pointing the laser. But at greater distances, behavior might not change. Thus, these findings need to be replicated in different maritime scenarios in order to be truly useful in developing laser glare devices. This particular study was encouraging regarding the effectiveness and visual usefulness of glare devices, but it brought up new questions about their psychological impact on behavior. Resolving these questions must be an integral goal of technical research and development studies to determine the operational effectiveness of directed-energy devices, not just for the maritime environment, but for all military environments.

Endnote

a. Results and technical reports are available upon request from the corresponding author or from the NAMRU-SA Public Affairs Officer.

DIRECTED ENERGY USING HIGH-POWER MICROWAVE TECHNOLOGY

By Jacob Walker and Matthew McQuage

The Directed Energy Warfare Office (DEWO) and Directed Energy Division at the Naval Surface Warfare Center, Dahlgren Division (NSWCDD) merge past research and data with continuous innovation in the field of high-power microwave(s) (HPM) to address the critical need for nonlethal, nonkinetic weapons. HPM weapons can be described as nonkinetic devices that radiate electromagnetic energy in the radio frequency (RF) or microwave spectrum. They are designed to disrupt, deny, degrade, damage, or destroy targets. In essence, this is achieved when high-power electromagnetic waves propagate through air and interdict targets by traveling through the exterior layers of structures and coupling energy to critical electronic components. Since effectiveness against a wide range of targets is the goal, HPM has become a collective term for various technologies: wave shapes, source frequencies, and the distribution of varying signal bandwidths. It is the objective of HPM research and assessment, therefore, to address targets for which no engagement option currently exists. NSWCDD is working to identify optimal HPM mission platforms and move relevant technologies into the field.

HPM INITIATIVES

NSWCDD has actively pursued HPM research since the advent of the field in the 1970s. Since then, scientists and engineers have conducted HPM research and development in many areas, including hydrogen spark-gap switching, spiral generators, and related technologies. More currently, the Directed Energy Division developed a variety of high-power wideband RF systems based on pulsed power and Marx generators (Figure 1). In addition to the extensive work accomplished in HPM and RF source development, NSWCDD contributed substantially to the area of counter-HPM vulnerability assessments. Researchers developed site assessment guides and threat brochures, as well as a number of wideband RF sources, to determine the susceptibility of electronic equipment to high-power RF interference. This latter effort involved assessing and exploiting the weaknesses of specified electronic targets to various HPM and RF threats. Data gleaned from these efforts was then used to support optimized prototypes and system designs employing effects-based design methodology. NSWCDD utilized these wideband RF sources to determine the susceptibility of a multitude of military





Figure 1. Examples of NSWCDD Marx Generators

and electronic infrastructure equipment to high-power RF interference.

HPM Counterattack Operational Overview

Research in support of HPM-driven electronic attack increased significantly as the demand for nontraditional warfare emerged. Traditional kinetic weapons often are of limited value in peace-keeping missions, for example, as today's enemies frequently are embedded within civilian populations and structures. This creates the need for novel HPM technologies that minimize the risk of collateral damage while effectively neutralizing threats. Dahlgren researchers conduct HPM system research and development—as well as lethality and weapon effectiveness assessments—to address this need while developing technologies against a wide variety of electronic targets. These projects leverage NSWCDD's assets, including the Maginot' Open Air Test Site (MOATS), state-of-the-art RF diagnostics, and modeling and simulation tools to identify applications and platforms in which HPM technologies can be employed. Figure 2 shows a computer model of the MOATS facility and a modeling and



(a)



(b)

Figure 2. Modeling and Simulation Depicting (a) NSWCDD Test Facility and (b) Simulation of Radiated RF

simulation graphic depicting the RF emitted by an HPM dipole antenna.

Potential platforms for HPM integration include: man-portable, aerial, vehicle, and vessel-mounted systems. These platforms all provide unique methods for delivery of HPM sources. For example, aerial delivery—which, in many ways, is the most challenging due to size and weight constraints—can increase the effective range of these systems and can engage multiple targets at close range without endangering personnel. Likewise, vehicles and vessel-mounted HPM systems provide a way for law enforcement and the military to stop vehicles in chase scenarios almost as soon as they begin. The goal of all of these projects is to provide military forces with the ability to employ nonkinetic, electronic strike technologies against an adversary's electronics.

The DEWO and Directed Energy Division are uniquely positioned to provide numerous capabilities for in-house development while engaging with the private sector to test and provide feedback on HPM systems developed externally. In the past decade, NSWCDD has evaluated several HPM systems at Dahlgren to determine their effectiveness against various electronic targets while maintaining the Office of the Secretary of Defense's Tri-Service RF Directed Energy Weapon (DEW) Database. This database contains all effects data collected from directed-energy tests performed within the U.S. Air Force, Army, and Navy.

CONCLUSION

NSWCDD continues to pioneer HPM source development and lethality and integration studies, leading to the demonstration and delivery of prototype capabilities. It also is committed to researching and developing critical subsystems for HPM delivery. By leveraging numerous target assets and sophisticated diagnostic equipment—in conjunction with MOATS—NSWCDD has positioned itself at the forefront of HPM electronic attack, leading the way in the development and delivery of these capabilities to the warfighter.

ACKNOWLEDGMENT

Nancy Muncie, Bowhead, contributed to this article.

LASER COUNTER ROCKET, ARTILLERY, AND MORTAR (C-RAM) EFFORTS

By Michael Libeau

Mortars and rockets are common weapons confronting U.S. troops abroad. Insurgents fire the inexpensive projectiles into populated areas, intending to kill or injure service members and to inflict physical damage. While kinetic solutions like guns and missile interceptors are used to counter rockets and mortars, laser counter rocket, artillery, and mortar (C-RAM) systems present a promising solution to counter these challenging threats in the near future.

Scientists and engineers at the Naval Surface Warfare Center, Dahlgren Division (NSWCDD) have been researching, developing, testing, and evaluating laser C-RAM systems through collaboration, modeling and simulation, and experimentation. The Joint Technology Office (JTO) and the Directed Energy and Electric Weapons Program Office (PMS 405) sponsored the first year of these initiatives in 2007. Consecutive and current work has been sponsored by the Office of Naval Research (ONR) Expeditionary Maneuver Warfare and Combating Terrorism S&T Department.

BACKGROUND

In preparation for the development of a laser C-RAM system, an understanding of the vulnerability of rockets and mortars to laser energy was crucial. Engineers from NSWCDD and the U.S. Army Space and Missile Defense Command (SMDC) collaborated on laser C-RAM efforts. Engineers analyzed the RAM threat and examined a variety of targets, accessing RAM vulnerabilities to laser energy by utilizing theoretical, numerical, and experimental work. They then developed theoretical models that captured the physics of the laser-induced failures of targets containing high explosives (HE). Additionally, NSWCDD engineers enhanced lethality simulations using a tool called the Effectiveness Toolbox to model engagements of RAM targets with laser energy. Figure 1 shows a screen capture from the Effectiveness Toolbox.

The resulting simulations included results from a laser atmospheric propagation model and a thermal model to determine the effect of the laser energy on the target. The simulations also incorporated target trajectories necessary for modeling the changing laser conditions on the target resulting from the engagement of a ballistic target. Subsequent to modeling these effects, live testing was performed. Figure 2 shows the lasing and destruction of a RAM target during live testing.



Figure 1. Screen Capture from the Effectiveness Toolbox Showing the Laser Engagement of a Mortar Target



Figure 2. Explosive Target is Destroyed with NSWCDD's Fiber Lasers

NSWCDD engineers conducted two large experimental tests to determine the vulnerability of HE targets to laser energy using NSWCDD's High-Energy Fiber lasers. The first test was conducted jointly with SMDC. During these two tests, over 40 RAM targets were destroyed under different laser conditions, producing significant information on laser lethality. Researchers measured the failure times of multiple targets for different laser powers, spot sizes, incidence angles, and aimpoints. The experimental data yielded by the tests increased engineers' understanding of the vulnerability of targets containing energetic materials. This data was then used to benchmark predictive models.

Future tests are planned with additional HE targets to further the knowledge of RAM vulnerability. These tests are controlled and conducted carefully to ensure that good data is obtained. Accurate measurements of laser power on the target and the resulting target failure times must be made during the tests. To that end, NSWCDD engineers leverage Division-wide expertise in lasers and optics with its long history of explosives testing to achieve meaningful test results. NSWCDD personnel have been instrumental in improving techniques to measure the spatial profile of laser power on a target. The spatial distribution of laser power on a target is critical to understanding the target's failure. Figure 3 shows a laser beam's spatial power distribution measured during a test.

ONGOING LASER C-RAM INITIATIVES

Recent advances in fiber lasers have increased the power outputs of these rugged, solid-state devices. Both government and contractor efforts are examining the application of commercial off-the-shelf (COTS) lasers and other electric lasers for application into advanced weapon systems. The Navy's Laser Weapon System (LaWS) Program, for example, is examining a laser system built around efficient fiber lasers. This is significant because a high-energy fiber laser system offers two critical advantages over gun and missile interceptor C-RAM systems. First, the laser has a great depth of magazine since it requires only electricity for operation. Consequently, unlike a gun system, which has a limited supply of ammunition, a laser system is limited only by its supply of electrical energy. Second, a laser system offers a cost per kill that is significantly lower than alternative systems because only electricity is being expended instead of gun ammunition or a costly missile interceptor. This low cost per kill also better matches the low cost of the RAM target being engaged.

High-Energy Fiber Laser C-RAM systems will provide significant advantages in defeating the RAM threat while augmenting existing C-RAM solutions. More importantly, laser C-RAM systems will help protect members of the armed forces from the inexpensive, yet often deadly threats posed by rockets and mortars.



Figure 3. Laser Power Spatial Variation from a C-RAM Test



MULTIFREQUENCY RADIO-FREQUENCY (RF) VEHICLE STOPPER

By Stephen A. Merryman

The widespread use of vehicle-borne improvised explosive devices (VBIEDs) in Iraq and Afghanistan has resulted in large numbers of military and civilian personnel being killed or injured. Consequently, the Joint Non-Lethal Weapons Directorate's (JNLWD) top priority is to identify, investigate, and develop technologies and capabilities to nonlethally stop both vehicles and vessels outside of minimum "keep-out ranges" (i.e., ranges where the rules of engagement would dictate the use of lethal force) and to mitigate the blast effects from a VBIED.

One of these technologies is the multifrequency Radio-Frequency (RF) Vehicle Stopper (RFVS), a high-power microwave (HPM) weapon under development at the Naval Surface Warfare Center, Dahlgren Division (NSWCDD). A prototype RFVS system, designed to meet the mission criteria for fixed-checkpoint protection and compound protection, is slated for completion in FY13. Science and technology (S&T) work continues in parallel to the prototype system's construction to broaden its applicability to include convoy protection and the establishment of a quick safe zone. This article describes the 4-year research effort that resulted in the specification of the RFVS system design. Figure 1 shows an illustration of a candidate RFVS platform with the system set up for fixed-checkpoint protection.

The RFVS system uses high-power magnetron tubes to generate intense RF pulses that interfere with a vehicle's electronics, rendering it temporarily inoperable. The engine cannot be restarted while the RF is on but is readily restarted once the RF is turned off. Thus, the RFVS system allows for the maintenance of a safe keep-out zone in situations that might otherwise require the use of lethal force. The defined measure of success for this system is a demonstrated, effective capability against more than 80% of the candidate target-vehicle-class list, which includes passenger cars and large vehicles.

As a nonlethal capability, the effects to the target vehicle are short term and almost always reversible, so that the vehicle is not stranded, which would burden the warfighter with the task of its removal. Moreover, as with all directed-energy weapons, the RFVS system delivers energy at the speed of light. In contrast with other nonlethal vehicle stopping concepts and systems, however, RFVS does not need to be pre-emplaced and has a limitless magazine.



Figure 1. Illustration of Candidate RFVS System Setup for Checkpoint Protection

BACKGROUND

Using HPM or RF energy to stop an automobile engine is not a new concept; it has been under investigation for some time in private, academic, and military sectors. To that end, the RFVS program leveraged as much historic work as possible while collaborating with academic and military laboratories and while aggressively pursuing contacts in the automobile industry to gain knowledge of vehicle electronic design and function.

In 2005, the JNLWD funded the then-Directed Energy Technology Office (DETO) at NSWCDD to perform an extensive reverberation chamber test series to characterize the vulnerability of a representative cross section of automobiles to a wide range of HPM source frequencies.[a] The purposes of the tests were twofold. First, the applicability of the Army's Ground Vehicle Stopper (GVS) data set needed to be established for newer vehicles, and second, a thorough, source-technology independent assessment of vehicle vulnerabilities needed to be performed. The rationale behind the latter was to establish vehicle vulnerabilities without inadvertently biasing the process. Only after the full assessment was performed would factors such as concept of operations (CONOPS) and system requirements come into play. Figure 2 is a photograph of reverberation chamber testing.

Over the past decade, a significant number of private, academic, and military laboratories have investigated the susceptibility of automobiles to HPM energy. The range in approaches spans the gamut from isolated component testing, through direct injection and radiated testing of electronic control units (ECUs), and continuing through full vehicle radiated testing. Each of the different test methods has its strengths and weaknesses. Testing of isolated ECUs in controlled laboratory conditions is arguably the best way to determine exactly how a specific unit is responding to the RF. However, whether or not the identified susceptibilities continue to hold true when the unit is in place in a



Figure 2. Vehicle on a Dynamometer in the NSWCDD Reverberation Chamber

vehicle, or whether the results apply to other vehicles' ECUs, remains a significant question that limits the applicability of the results.

Full vehicle testing and failure analysis of the ECU can be a daunting task. That said, full vehicle testing affords the advantage of ensuring that the response is commensurate with expectations of genuine engagements. The test approach one chooses to take depends upon resources, test facility availability, and most importantly, the objectives of the program. For the RFVS program, the objectives were to identify an HPM waveform that is effective against a broad class of the candidate target vehicles and to ensure that the identified waveform could be generated with a source that can be packaged in a footprint and cost amenable to military users. To meet the program's objectives, the RFVS program chose to invest the majority of its resources in full vehicle testing. While the focus of the effects testing portion of the RFVS program has remained on full vehicle testing, both time and resources have been devoted to fostering and maintaining connections with academia and the auto industry. There is concerted effort to keep abreast of the latest trends in automotive technology, to ensure that the current RFVS system design will continue to be effective against future vehicle designs, and to leverage all research that might aid in future RFVS designs.

SYSTEM OPERATION

The majority of current HPM system concepts employ a narrowband, single-frequency HPM source. In contrast, RFVS utilizes multiple HPM frequencies. The rationale for using multiple frequencies is associated with increased system effectiveness. Electromagnetic (EM) energy can be used to disrupt or damage an electronic target. In order for the energy to affect the electronics, however, it must be able to reach a critical component(s) inside the target. This involves a process referred to as coupling. Different EM waveforms are more or less effective against specific targets depending, in part, on their frequency, as different frequencies couple better or worse depending on varying target geometries. To be specific, each piece of electronics has specific resonance frequencies that most effectively facilitate coupling energy to the target. Unfortunately, these resonant frequencies can be unique to each piece of equipment. Consequently, a single-frequency waveform might be very effective against one target, but less effective against another target. Therefore, a system that utilizes either a sweep of frequencies or multiple frequencies will be more effective against a larger target set. This is not a novel idea, but rather one that has been readily acknowledged within the HPM community for some time and fervently embraced by the RFVS program. Current technology limitations prohibit high-power-swept frequency sources as viable options, leading to the idea of a multifrequency source. The more frequencies that are used, the more effective the system; however, a trade-off is made with system size and cost as the number of source frequencies is increased.

BRASSBOARD SYSTEM

After completion of the exhaustive vehicle effects characterization testing in 2006, the RFVS program identified the optimal number of frequencies needed to meet mission requirements. It then used this information in the design and construction of the Brassboard System. The purpose in constructing the Brassboard System was to demonstrate the benefit of the multifrequency approach and the ability to meet mission objectives with specified power on target requirements. Construction of the RFVS Brassboard System began in 2007 and was completed in 2008. The Brassboard System was not constructed with specific system footprints in mind. Thus, the antenna and conex used are significantly larger than those in the prototype design. The RFVS team collaborated with a Marine Corps service representative identified by the JNLWD to flesh out the specifics of the mock checkpoint to be used in the RFVS Brassboard System Demonstration. Figure 3 provides a diagram of the checkpoint setup used in the RFVS Brassboard Demonstration. Figure 4 provides photographs of the RFVS Brassboard System.



Figure 3. Schematic of Checkpoint Setup


Demonstration Test Setup

Figure 4. Photograph of the RFVS Brassboard System and Demonstration Setup

The Brassboard System Demonstration was conducted in Spring 2008. The Demonstration was a success, and funding for the RFVS prototype was consequently approved. To date, 42 passenger vehicles (cars, pickup trucks, vans, and sport utility vehicles (SUVs)) and 3 large trucks (dump truck and tractors) have been tested as part of the RFVS program.

Way Ahead

The JNLWD continues to work with the Directed Energy Warfare Office (DEWO) toward the development of a fieldable multifrequency RFVS system. Once the capability is fully developed, tested, and certified ready for operational use, warfighters and civilians alike will benefit greatly. Lives will no doubt be saved using the ability to stop vehicles nonlethally and mitigate the blast effects from VBIEDs.

Acknowledgment

Dr. Cynthia Ropiak (SAQ Consulting) contributed to this article.

Endnote

a. The Directed Energy Technology Office (DETO) was renamed the Directed Energy Warfare Office (DEWO) in August 2009. For reference, see the charter for the DEWO, NSWCDD, 17 August 2009.

HIGH-POWER ELECTRICAL VEHICLE-STOPPING SYSTEMS

By Jordan Chaparro and Melanie Everton

The military needs devices that can safely and reliably stop or arrest vehicles. The primary concern is security at entry control points and vehicle check points similar to the one shown in Figure 1. In such scenarios, it is desirable to be able to stop unauthorized vehicles at predefined standoff ranges to protect personnel, equipment, and critical infrastructure.

Both the military and civilian law enforcement agencies face similar issues with chase scenarios, where concerns over bringing an offending vehicle to a stop without killing or injuring innocent civilians, or causing collateral damage, often prolongs high-speed pursuits. That said, currently employed nonlethal options for arresting vehicles have significant logistical limitations and carry a high cost per use.

The Naval Surface Warfare Center, Dahlgren Division's Directed Energy Warfare Office (DEWO), under the sponsorship of the Joint Non-Lethal Weapons Directorate (JNLWD), investigated compact systems designed to couple high-power electrical impulses to a target vehicle to stop its engine. Such systems are highly portable, can operate remotely, can be deployed quickly by a two-man team, and can engage hundreds of targets before requiring any significant maintenance.

SYSTEM OVERVIEW

Conceptually, electrical vehicle-stopping systems are fairly simple devices. The systems use several stages of energy compression to take a low-peak power source—like a battery pack—and create very intense, short-duration, oscillating electrical impulses. The block diagram, shown in Figure 2, illustrates the principal components of such a system.

A high-energy density, 300-V lithium battery pack, similar to what might be found in a hybrid vehicle, serves as the prime power source for the device. These batteries are capable of driving the system for hundreds of engagements before requiring recharge.

The direct current bus from the batteries is stepped up to several kilovolts in order to charge a capacitive voltage multiplier, such as a Marx Generator, Spiral Line Generator, or Tesla Transformer. Once triggered, these generators charge a resonant circuit to hundreds of kilovolts which, when switched, generate the desired oscillating waveform. Coupling this electrical pulse to a target may be accomplished by direct electrode contact, by radiating the waveform from a broadband antenna structure, or by a combination of both methods.

Figure 1. An Azerbaijani Soldier Guarding Entry Control Point 1 at the Haditha Dam in Support of Operation Iraqi Freedom


~300V DC
10–50 kV
100 s kV
~µs pulse
Battery Pack
High-Voltage DC Power Supply
High-Voltage Generator
1–100 MHz Oscillator
Direct Contact Electrodes
+
–
> 1µs pw
1–100 MHz
Laptop Computer
System Controller
Trigger Generator
Vehicle Position Sensors
0.1–1 GHz Oscillator
Wideband Antenna
> 100 ns pw
100–1000 MHz

Figure 2. System Block Diagram for Generic Electrical Vehicle-Stopping Systems

The system is monitored and controlled by an integrated system computer. A laptop computer, remotely connected to the system controller through either fiber optic or a wireless network, can be used to arm the system. At this point, motion detection sensors trigger the pulse train upon the targeted vehicle. The laptop can also be used to monitor the system's status, change system parameters, and receive data collected during the last engagement event.

A conceptual rendering of how such a system might look when in use is shown in Figure 3. Traffic would be funneled with barriers to a single lane. When not engaged, the system electrodes would sit flush with the roadway unit, with an exposed height of less than 3 inches. When required, the electrodes could be released to make contact with a vehicle's undercarriage and deliver the electrical impulses.

Comparison with Existing Systems

Tire spike systems are frequently employed but do not limit the momentum, drive, or control of a vehicle to an extent that could be useful in any type of control or checkpoint scenario. Consequently, while tire spike systems are primarily used in high-speed pursuit applications, they are limited, in that they cripple the target just enough to allow law enforcement to force the vehicle to a stop.

Restraining nets are most comparable to electrical vehicle stoppers with respect to their intended application and desired effect. Restraining net systems and electrical vehicle stoppers both completely arrest vehicles, although by different means. Restraining nets bind the front axle of the vehicle, causing it to forcibly lose momentum and skid to a stop. Thus, the vehicle operator loses the ability to steer the vehicle, further resulting in a lower potential for collateral damage. Electrical systems stop the engine of the vehicle, leaving the operator with control for the duration of the vehicle's momentum. Physical barrier structures can then be employed to force an affected vehicle to stop in a fairly short distance. Modern vehicles lose power steering when the engine is cut off, such that the maneuverability of the vehicle is limited enough to


Resonant Circuit and Contact Electrodes
Prime Power, Supply, and Control Hardware
Transmission Line
High-Voltage Generator
Security Checkpoint
Standoff Range
3-Piece Serpentine Barriers
Device
2-Piece Serpentine Barriers

Figure 3. Conceptual Rendering of an Employed Electric Vehicle Stopping System

allow normally nonrestrictive serpentines to be effective at limiting roll-off distances.

One key logistical advantage of electrical vehicle stoppers, compared to restraining nets, is the average cost per engagement. Restraining net systems are one-time use devices that cost several thousand dollars each. Electrical systems initially cost tens of thousands of dollars but can perform thousands of stops within the expected lifetime of the device. Also, there is no requirement to physically reset or reload an electrical system, as with restraining nets. The maintenance required for electrical systems involves the occasional replacement of electrode arms and the inspection of the system connections and pressure levels.

Operationally, both systems have limitations on the types of targets that can be effectively stopped. Restraining nets are limited by vehicle momentum, which can be a product of high speeds or large vehicles. Electrical systems are not limited by vehicle size or speed, but they require additional support from structures—such as serpentines or speed bumps—to force the target to brake and dissipate its momentum once the engine has been stopped.

Both devices typically cause damage to targeted, stopped vehicles. Restraining nets almost always cause tire damage. Less commonly, brake lines, front axles, wheels, and transmissions also might be damaged. Electrical systems typically damage engine controllers, security modules, and engine sensors. In addition, noncritical parts—such as gauges, radios, and cabin fans—also might be damaged. Moreover, moving affected targets is much less of an issue with electrical stoppers than vehicles stopped by net systems, which must first have the net cut away and freed before the target is moved to the side of the roadway.

System Refinement and Look Forward

Previous attempts to field electrical vehicle-stopping systems have been hampered by limited success rates on a large population of vehicles. Many models of vehicles are easily affected by any type of large injected current, while others are fairly resistant. Through carefully designed and controlled experiments, and logistical regression modeling techniques, the DEWO team has been able to determine key waveform attributes that scale with stopping effectiveness rates on a representative population of vehicles. Successful stop rates exceeding 90 percent have been achieved on a diverse vehicle test set by engineering system resonators to enhance system performance The DEWO team, through continued research, testing, and evaluation, is continuing its work to increase the reliability and effectiveness of these systems to make them more compact and to improve their functionality for future military and law enforcement applications.

NONLETHAL SMALL-VESSEL STOPPING WITH HIGH-POWER MICROWAVE TECHNOLOGY

By Jacob Walker

The employment of small vessels to attack merchant ships and other seafaring units has emerged as a significant threat to international navigation and safe operations on the high seas. Along with swarm tactics, small vessels have been known to carry improvised explosive devices, help smuggle terrorists and weapons, and serve as attack platforms on the water for larger weapons. While kinetic solutions serve as the decisive option, alternative solutions that employ nonlethal means are being explored. A depiction of a swarm of small vessels ready to attack is shown in Figure 1.

The Naval Surface Warfare Center, Dahlgren Division's (NSWCDD's) Directed Energy Warfare Office (DEWO) is evaluating directed-energy (DE) concepts based on high-power microwave (HPM) technology for nonlethal vessel-stopping applications. Nonlethal weapons are defined by the Department of Defense (DoD) as weapons that are explicitly designed and primarily employed so as to incapacitate personnel or materiel while minimizing fatalities, permanent injury to personnel, and undesired damage to property and the environment.[1]

Several methodologies exist for using nonlethal means to stop small vessels. They include:

- Running-gear or prop entanglement systems
- Exhaust stack blockers
- A sea-anchor vessel-stopping system, which casts a net across the bow of a vessel to impart resistance
- Small-craft disablers, which insert a spear into the hull and deploy a fin that drags in the water, making steering impossible

Prop entanglement systems, exhaust stack blockers, and sea-anchor systems are useful and effective, but all are operationally difficult to deliver when deployment methods rely on positioning them in front of, or directly over, a vessel moving

Figure 1. Depiction of a Small-Vessel Swarm Ready to Attack

at high speeds. Small-craft disablers also are a formidable vessel-stopping solution and may be easier to deploy, but they cause permanent damage to the vessel in question.

Under the direction of the Joint Non-Lethal Weapons Directorate (JNLWD), the DEWO is in the initial stages of a multiyear effort to evaluate DE concepts for nonlethal vessel-stopping applications. It is currently focusing on HPM technology. This technology uses HPM sources to radiate radio frequency (RF) pulses downrange to interfere with motor-control electronics and significantly impede or stop small-vessel motors with minimal collateral damage. These RF pulses can be generated using different technologies ranging from wideband LC oscillators and microwave tubes (e.g., magnetrons, klystrons, and backward wave oscillators) to emerging solid-state technologies (e.g., nonlinear transmission line and photo-conductive switching). An outboard motor on a test stand is shown in Figure 2.

In comparison to kinetic weapons or other nonlethal systems, HPM avoids gross physical destruction to the vessel while, more importantly, providing zero-to-low risk of human injury. HPM accomplishes this at safe distances using speed of light delivery, therefore making evasion difficult, if not impossible, with the added benefit of scalable effects ranging from disruption to damage. Despite its numerous advantages, the use of HPM technology as a nonlethal weapon presents challenges as well, including a trade-off between system size and standoff range. This is particularly important when considering the use of HPM systems in different environments.

Upfront HPM source development costs represent one of the biggest challenges. However, long-term savings associated with HPM technology can offset this challenge. For example, prop entanglement systems might be deployed only once before they are rendered useless. HPM sources integrated onto a ship or other military vehicle can be employed in potentially thousands of missions, therefore resulting in a lower cost per single use, bringing overall associated costs of the system down significantly. Priorities for HPM nonlethal weapons include developing a system effective against different types of small vessels.

NSWCDD’s Directed Energy Division began HPM susceptibility testing to determine the effectiveness of HPM weapons against relevant outboard engines. This involves testing small vessels in



Figure 2. Outboard Motor Test Stand

a variety of environments, including reverberation and anechoic chambers, and open-air testing. All help identify different, effective waveform parameters such as frequency, pulse width, rise time, and required power or energy on target. They further facilitate the identification of design specifications necessary for an eventual HPM source. This source, once developed, will then be integrated into one of several potential platforms. Candidate concepts of deployment include U.S. Coast Guard and naval vessels in addition to unmanned surface or aerial vessels. Another potential application might be to supplement existing Coast Guard or Navy platforms used for fast-boat interdiction with an HPM vessel-stopping capability. A small-vessel test using an HPM source is shown in Figure 3.

Developing solutions for the growing threat that small vessels pose to navigation and safe operations in the world's oceans is one of JNLWD's top priorities. Using nonlethal HPM weapons to stop vessels will provide the warfighter with a viable option for swarm threat and fast-boat interdiction. DEWO is working diligently to accelerate this technology and provide a DE alternative to kinetic weapons and fulfill this long overdue capability gap.

Reference

1. *Department of Defense Dictionary of Military and Associated Terms*, Joint Publication 1-02, 12 April 2001 (as amended through 19 August 2009).





Figure 3. Small-Vessel Testing Using a High-Power Microwave Source

LEADING EDGE
Volume 7, Issue No. 4



Directed Energy

We look forward as we provide enterprise-wide technical and strategic leadership for the efficient and effective development, acquisition, and fielding of directed-energy systems for the warfighter.

Dale Sisson
Head, Electromagnetic and
Sensor Systems Department
NSWCDD, Dahlgren, Virginia

LEADING EDGE

Volume 7, Issue No. 4

Fallen Warriors

Here we honor those who died while serving their country

NAVSEA
WARFARE CENTERS
DAHLGREN

NSWCDD/MP-09/34

Statement A: Approved for public release; distribution is unlimited

2013

NAWCWD TP 8347
Fourth Edition

Electronic Warfare and Radar Systems

Engineering Handbook

A Comprehensive Handbook for
Electronic Warfare and Radar Systems Engineers

Naval Air Warfare Center Weapons Division, Point Mugu, California

DISTRIBUTION STATEMENT A: Approved for public release.

NAWCWD TP 8347
Fourth Edition

Electronic Warfare and Radar Systems Engineering Handbook

by
Avionics Department

OCTOBER 2013

NAVAL AIR WARFARE CENTER WEAPONS DIVISION
POINT MUGU, CA 93042

DISTRIBUTION STATEMENT A: Approved for public release.

Naval Air Warfare Center Weapons Division

FOREWORD

This handbook is designed to aid electronic warfare and radar systems engineers in making general estimations regarding capabilities of systems. This handbook is sponsored by the NAVAIR Director of Electronic Warfare/Combat Systems Department. This fourth edition updates technical information in Sections 3-7 and 3-8 from previous editions.

This document was reviewed for technical accuracy by Dr. Andrew Chen.

Approved by
DR. R. E. SMILEY, *NAVAIR Director*
EW/Combat Systems Department
30 September 2013

Under authority of
M. MORAN
RDML, U.S. Navy
Commander

Released for publication by
S. O'NEIL
Director for Research and Engineering

NAWCWD Technical Publication 8347

Published by	Technical Communication Office
Collation	Cover, 226 leaves, + Tabs
Previously published as NAWCWPNS TS 92-78 (1st through 3rd Edition)	4,040 paper
First Edition	105 paper
Second Edition	500 paper
Third Edition	1,000 paper
Fourth Edition	100 paper, 500 electronic

REPORT DOCUMENTATION PAGE

Form Approved
OMB No. 0704-0188

The public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing the burden, to the Department of Defense, Executive Service Directorate (0704-0188). Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.
PLEASE DO NOT RETURN YOUR FORM TO THE ABOVE ORGANIZATION.

1. REPORT DATE *(DD-MM-YYYY)*
01-10-2013

2. REPORT TYPE
Technical publication

3. DATES COVERED (From - To)
1 January 2012 – 30 September 2013

4. TITLE AND SUBTITLE
Electronic Warfare and Radar Systems Engineering Handbook (U)

5a. CONTRACT NUMBER
N/A

5b. GRANT NUMBER
N/A

5c. PROGRAM ELEMENT NUMBER
N/A

6. AUTHOR(S)
Avionics Department

5d. PROJECT NUMBER
N/A

5e. TASK NUMBER
N/A

5f. WORK UNIT NUMBER
N/A

7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES)
Naval Air Warfare Center Weapons Division
575 I Avenue, Suite 1 (Code 450000E)
Point Mugu, California 93042

8. PERFORMING ORGANIZATION REPORT NUMBER
NAWCWD TP 8347

9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)
N/A

10. SPONSOR/MONITOR'S ACRONYM(S)
N/A

11. SPONSOR/MONITOR'S REPORT NUMBER(S)
N/A

12. DISTRIBUTION/AVAILABILITY STATEMENT
Approved for public release.

13. SUPPLEMENTARY NOTES
None.

14. ABSTRACT

(U) This handbook is designed to aid electronic warfare and radar systems engineers in making general estimations regarding capabilities of systems. This handbook is sponsored by the NAVAIR Director of Electronic Warfare / Combat Systems Department.

15. SUBJECT TERMS
Aircraft Dynamics, Antenna, Data Transfer Busses, Electro-Optics and Infrared, Ethernet, Internet Protocol, Maneuverability, Microwave Components, Polarization, Radar Equations, Radiation Patterns, Receiver Characteristics, Receiver Sensitivity, Receiver Tests, Radio Frequency Components, RS-232 Interface, RS-422 Balanced Voltage Interface, RS-485 Interface, Transmission Control Protocol

16. SECURITY CLASSIFICATION OF:			**17. LIMITATION OF ABSTRACT**	**18. NUMBER OF PAGES**	**19a. NAME OF RESPONSIBLE PERSON**
					Timothy Stolsig
a. REPORT	**b. ABSTRACT**	**c. THIS PAGE**			**19b. TELEPHONE NUMBER** *(include area code)*
UNCLASSIFIED	UNCLASSIFIED	UNCLASSIFIED	SAR	450	(805) 989-3452

Standard Form 298 (Rev. 8-98)
Prescribed by ANSI Std. Z39.18

CONTENTS

Section
ABBREVIATIONS AND ACRONYMS 1-1

FUNDAMENTALS
Constants, Conversions, and Characters 2-1
Mathematical Notation 2-2
Frequency Spectrum 2-3
Decibel (dB) 2-4
Duty Cycle 2-5
Doppler Shift 2-6
Electronic Formulas 2-7
Missile and Electronic Equipment Designations 2-8
Radar Horizon / Line of Sight 2-9
Propagation Time / Resolution 2-10
Modulation 2-11
Transforms / Wavelets 2-12

ANTENNAS
Antenna Introduction / Basics 3-1
Polarization 3-2
Radiation Patterns 3-3
Frequency / Phase Effects of Antennas 3-4
Antenna Near Field 3-5
Radiation Hazards 3-6
Active Electronically Scanned Arrays (AESA) 3-7
Fractal Antennas 3-8

RADAR EQUATIONS
Field Intensity and Power Density 4-1
Power Density 4-2
One-Way Radar Equation / RF Propagation 4-3
Two-Way Radar Equation (Monostatic) 4-4
Alternate Two-Way Radar Equation 4-5
Two-Way Radar Equation (Bistatic) 4-6
Jamming to Signal (J/S) Ratio - Constant Power [Saturated] Jamming 4-7
Burn-Through / Crossover Range 4-8
Support Jamming 4-9
Jamming to Signal (J/S) Ratio - Constant Gain (Linear) Jamming 4-10
Radar Cross Section (RCS) 4-11
Emission Control (EMCON) 4-12
EW Jamming Techniques 4-13

RADAR AND RECEIVER CHARACTERISTICS & TEST
RF Atmospheric Absorption / Ducting 5-1
Receiver Sensitivity / Noise 5-2
Receiver Types and Characteristics 5-3
Radar Modes 5-4
General Radar Display Types 5-5
IFF - Identification - Friend or Foe 5-6
Receiver Tests 5-7
Signal Sorting and Direction Finding 5-8

MICROWAVE / RF COMPONENTS

Microwave Waveguides and Coaxial Cable 6-1
Voltage Standing Wave Ratio (VSWR) / Reflection Coefficient
Return Loss / Mismatch Loss 6-2
Microwave Coaxial Connectors 6-3
Power Dividers and Directional Couplers 6-4
Attenuators / Filters / DC Blocks 6-5
Terminations / Dummy Loads 6-6
Circulators and Diplexers 6-7
Mixers and Frequency Discriminators 6-8
Detectors 6-9
RF / Microwave Amplifiers 6-10
Signal Generation 6-11
Digital Processing Components 6-12
Microwave Measurements 6-13

ELECTRO-OPTICS AND IR 7-1
Introduction 7-1.1
Optical Spectrum 7-1.1
Radiometric Quantities and Terminology 7-1.2
Photometric Quantities 7-1.3
Basic Principles 7-1.4
Basic Radiant Power Relationships 7-1.5
Infrared Source Characteristics 7-1.10
Atmospheric Transmission 7-1.14
EO Components and Sensors 7-1.16
IR Threats to Aircraft and Their Countermeasures 7-1.30
IRCM 7-1.36
Lasers 7-1.38
Fiber Optics 7-1.41
Laser Safety 7-2

AIRCRAFT DYNAMICS CONSIDERATIONS

Free Fall / Aircraft Drag 8-1
Mach Number and Airspeed vs Altitude 8-2
Maneuverability 8-3
EMP / Aircraft Dimensions 8-4

DATA TRANSFER BUSSES

Data Busses 9-1
RS-232 Interface 9-2
RS-422 Balanced Voltage Interface 9-3
RS-485 Interface 9-4
IEEE-488 Interface Bus (HP-IB/GP-IB) 9-5
MIL-STD-1553 & 1773 Data Bus 9-6
Ethernet 9-7
Transmission Control Protocol / Internet Protocol 9-8

GLOSSARY 10-1

ABBREVIATIONS AND ACRONYMS

a	Acceleration or atto (10^{-18} multiplier)
A	Ampere, Area, Altitude, Angstrom (Å), Antenna Aperture, or Aerial
A-799	No evidence of failure report
A/A, A-A, AA	Air-to-Air or Anti-Aircraft
AA-()	Air-to-Air missile number ()
AAA	Anti-Aircraft Artillery
AAAA	Army Aviation Association of America
AAED	Advanced Airborne Expendable Decoy
AAM	Air-to-Air Missile
AARGM	Advanced Anti-Radiation Guided Missile
AAW	Anti-Air Warfare
A-BIT	Automatic Built-in-Test
ABM	Air Breathing Missile or Anti-ballistic Missile
A/C	Aircraft (also acft.)
AC	Alternating Current
ACA	Associate Contractor Agreement or Airspace Coordination Area
ACAT	Acquisition Category
ACC	Air Combat Command
ACCB	Aircraft Configuration Control Board
Acft	Aircraft (also A/C)
ACLS	Aircraft Carrier Landing System
ACM	Advanced Cruise Missile or Air Combat Maneuvering
ACQ	Acquisition
ACS	Antenna Coupler Set
ACTD	Advanced Concept Technology Demonstration
A/D	Analog to Digital
ADM	Advanced Development Model
ADP	Automatic Data Processing or Advanced Development Program
AEA	Airborne Electronic Attack
AEC	Aviation Electronic Combat (Army)
AEGIS	Automatic Electronic Guided Intercept System
AEL	Accessible Emission Limit
AESA	Active Electronically Scanned Array
AEW	Airborne Early Warning
AF	Antenna Factor, Air Force, or Audio Frequency
AFB	Air Force Base or Airframe Bulletin
AFC	Automatic Frequency Control or Airframe Change
AFIPS	Automated Financial Information Processing System
AFOTEC	Air Force Operational T&E Center
A/G	Air-to-Ground
AGB	Autonomous Guided Bomb
AGC	Automatic Gain Control
AGI	Auxiliary General Intelligence (Intelligence-gathering Ship)
AGL	Above Ground Level
AGM	Air-to-Ground Missile
AGS	Angle Gate Stealer
AHWS	Advanced Helicopter Weapons System
AI	Artificial Intelligence, Air Intercept, or Airborne Interceptor
AIAA	American Institute of Aeronautics and Astronautics
AIC	Air Intercept Control
AIM	Air Intercept Missile
AIRLANT	Commander, U.S. Naval Air Forces, Atlantic Fleet
AIRPAC	Commander, U.S. Naval Air Forces, Pacific Fleet
AJ	Anti-jamming or Anti-Jam
A-Kit	Aircraft wiring kit for a system (includes cabling, racks, etc. excluding WRAs)
ALC	Air Logistics Center
AM	Amplitude Modulation
AMD	Aircraft Maintenance Department
AMES	Advanced Multiple Environment Simulator
AMLV	Advanced Memory Loader/Verifier
Amp	Amplifier
AMRAAM	Advanced, Medium-Range, Air-to-Air Missile
ANSI	American National Standards Institute
ANT	Antenna
Ao	Operational Availability
AO	Acousto-Optical
AOA	Angle of Arrival, Angle of Attack, or Analysis of Alternatives (similar to COEA)
AOC	Association of Old Crows (Professional EW Society) or Award of Contract
AOT	Angle Only Track, Angle Off Tail, or Acquisition-on-Target
APC	Amphenol Precision Connector or Armored Personnel Carrier
APN	Aircraft Procurement, Navy
APO	Armed Forces (or Army or Air) Post Office, Acquisition Program Office

APU	Auxiliary Power Unit
AR	Anti-reflection or Aspect Ratio
ARM	Anti-radiation Missile
ARO	After Receipt of Order
A/S, A-S, AS	Air-to-Surface
ASC	Air Systems Command
ASCM	Anti-ship Cruise Missile
ASE	Aircraft Survivability (or Survival) Equipment, Allowable Steering Error, or Automatic Support Equipment
ASIC	Application Specific Integrated Circuit
ASK	Amplitude Shift Keying
ASM	Air-to-Surface Missile
ASO	Aviation Supply Office
A-Spec	System Specification
ASPJ	Airborne Self-Protection Jammer
ASPO	Avionics Support (also Systems) Project Office (also Officer)
ASR	Advanced Special Receiver or Airport/Airborne Surveillance Radar
ASRAAM	Advanced Short Range Air-to-Air Missile
ASTE	Advanced Strategic and Tactical Expendables
ASW	Anti-submarine Warfare
ATA	Advanced Tactical Aircraft
ATARS	Advanced Tactical Air Reconnaissance System
ATC	Air Traffic Control
ATD	Advanced Technology Demonstration
ATE	Automatic Test Equipment
ATEDS	Advanced Technology Expendables and Dispenser Systems
ATF	Advanced Tactical Fighter (F-22)
ATIMS	Airborne Turret Infrared Measurement System or Airborne Tactical Information Management System
ATIRCM	Advanced Threat Infrared Countermeasures
ATP	Acceptance Test Procedure
ATR	Autonomous Target Recognition, Airborne Transportable Rack, Atlantic Test Range
ATRJ	Advanced Threat Radar Jammer
AUTODIN	Automatic Digital Network
AUX	Auxiliary
avdp.	Avoirdupois (system of measures)
Avg	Average
AWACS	Airborne Warning and Control System
AZ	Azimuth (also Az)

B	Bandwidth (also BW) or Magnetic inductance
BAFO	Best and Final Offer
BAU	Bus Adapter Unit
BC	Bus Controller
BDA	Battle Damage Assessment
BDI	Battle Damage Indication
BFO	Beat Frequency Oscillator
BI	Background Investigation
BIFF	Battlefield Identification, Friend, or Foe
BIT	Built-in-Test, Binary Digit or Battlefield Information Technology
BITE	Built-in-Test Equipment
BIU	Bus Interface Unit
B-Kit	Avionics "Black Box" WRAs
B/N	Bombardier/Navigator
BNC	Bayonet Navy Connector
BOA	Basic Ordering Agreement
BOL	Swedish chaff dispenser in a launcher
BPF	Band Pass Filter
BPS	Bits Per Second
BUMED	Bureau of Medicine (Navy)
BUNO	Bureau Number (aircraft)
BUR	Bottom Up Review
BVR	Beyond Visual Range
BW	Beamwidth (referring to an antenna) or sometimes Bandwidth
BWA	Backward Wave Amplifier
BWO	Backward Wave Oscillator

c	Speed of Light = 3x10^{8} meters/sec = 1.8x10^{12} furlongs per fortnight or 1.8 terafurlongs per fortnight, or centi (10^{-2}) multiplier
C	Electron Charge, Coulomb, Capacitance, Celsius, Centigrade, Confidential, Roman numeral for 100, or a programming language (also C+ and C++)
C^2	Command and Control
C^3 (C^4)	Command, Control, Communications (and Computers)
C^3I (C^4I)	Command, Control, Communications, (Computers) and Intelligence
CAD	Computer-Aided Design
CAE	Computer-Aided Engineering
CAG	Carrier Air Group
CAGE	Commercial and Government Entry
CAIV	Cost as an Independent Variable
CAL	Calibration

CAM	Computer-Aided Manufacturing or Constant Addressable Memory
CAO	Competency Aligned Organization or Contract Administrative Officer
CAP	Combat Air Patrol
CAS	Close Air Support or Calibrated Airspeed
CASS	Consolidated Automated Support System
CAT	Catapult or Cockpit Automation Technology
CB	Citizens Band (also see Seabee)
CBD	Commerce Business Daily
CBIT	Continuous Built-in-Test
CBO	Congressional Budget Office
CCA	Circuit Card Assembly
CCB	Configuration Control Board
CCD	Charge Coupled Device
CCM	Counter-Countermeasures
CCN	Contract Change Number or Configuration Change Notice
CCU	Cockpit Control Unit
cd	Candela (SI unit of luminous intensity)
CD	Compact Disk or Control and Display
CDC	Combat Direction Center
CDR	Critical Design Review
CDRL	Contract Data Requirements List
CE	Conducted Emission
CECOM	Communications and Electronics Command (Army)
CEESIM	Combat Electromagnetic Environment Simulator
CEP	Circular Error Probability
CFA	Cognizant Field Activity
CFAR	Constant False Alarm Rate
CFE	Contractor Furnished Equipment
CG	Center of Gravity, Commanding General, Command Guidance, or Cruiser
CI	Configuration Item
CIA	Central Intelligence Agency
CIC	Combat Information Center (now called CDC)
CID	Combat Identification or Charge Injection Device
CILOP	Conversion in Lieu of Procurement
CINC	Commander in Chief
CIP	Capital Improvement Program
CIS	Commonwealth of Independent States (11 of 15 former Soviet Union territories except Estonia, Georgia, Latvia, and Lithuania)
CIWS	Close-In Weapon System
CJ	Coherent Jamming
CLC	Command Launch Computer
cm	Centimeter
CM	Countermeasures or Configuration Management
CMC	Command Mission Computer or Commandant Marine Corps
CMDS	Countermeasure Dispensing System
CMOS	Complementary Metal-Oxide Semiconductor
CMP	Configuration Management Plan
CMWS	Common Missile Warning System
CNAF	Commander, Naval Air Forces
CNAL	Commander, Naval Air Forces Atlantic (also COMNAVAIRLANT)
CNAP	Commander, Naval Air Forces Pacific (also COMNAVAIRPAC)
CNI	Communications, Navigation, and Identification
CO	Commanding Officer, Contracting Officer, Change Order, or Carbon Monoxide
COB	Close of Business
COCOM	Combatant Command
COEA	Cost and Operational Effectiveness Analysis
COG	Center of Gravity or Cognizant
COMM	Communications
COMSEC	Communications Security
CONSCAN	Conical Scanning Radar
CONUS	Continental United States
CO-OP	Cooperative (countermeasures)
COR	Contracting Officers Representative
CORPORAL	Collaborative On-Line Reconnaissance Provider/Operationally Responsive Attack Link
Cos	Cosine
COSRO	Conical-Scan on Receive Only
COTS	Commercial Off-The-Shelf (hardware/software)
CP	Circularly Polarized (antenna), Central Processor, or Command Post
CPS	Computer or Control Power Supply (depends on application)
CPU	Central Processing Unit
CRC	Originally Chemical Rubber Company, now published reference books by CRC Press
CRFM	Coherent RF Memory
CRISD	Computer Resources Integrated Support Document
CRLCMP	Computer Resources Life Cycle Management Plan

CRO	Countermeasures Response Optimization
CRT	Cathode Ray Tube or Combat Rated Thrust (afterburner)
CSAR	Combat Search and Rescue
Crypto	Cryptographic
CS	Conducted Susceptibility
CSC	Commodity Software Change
CSCI	Computer Software Configuration Item
C-Spec	Product Specification
CSS	Contractor Support Services
CTR	Chesapeake Test Range
CV	Aircraft Carrier
CVN	Nuclear Powered Aircraft Carrier
CVR	Crystal Video Receiver
CW	Continuous Wave or Chemical Warfare
CWBS	Contract Work Breakdown Structure
CWI	Continuous Wave Illuminator
CY	Calendar Year

d	Distance, Diameter, or deci (10^{-1} multiplier)
D	Distance, Diameter, Electron displacement, Detectivity, Doppler, Density, or Roman numeral for 500
da	deca (10^0 multiplier)
D/A	Digital-to-Analog
DAB	Defense Acquisition Board
DAC	Digital to Analog Converter or Dept of Army Civilian
DAR	Defense Acquisition Regulation
DARPA	Defense Advanced Research Projects Agency
DB	Database
dB	Decibel
dBc	dB referenced to the Carrier Signal
dBi	Decibel antenna gain referenced to an isotropic antenna
dBm	Decibel referenced to the power of one milliwatt
DBOF	Defense Business Operations Fund
dBsm	Decibel value of radar cross section referenced to a square meter
dBW	Decibel referenced to the power of one watt
DC	Direct Current, Discrete Circuit, or District of Columbia
DCE	Data Communication Equipment
DCS	Direct Commercial Sales or Distributed Control System
DDI	Digital Display Indicator
DDS	Direct Digital Synthesizers
DECM	Deceptive Electronic Countermeasures (also Defensive ECM)
deg	Degree
DEMVAL	Demonstration Validation (also DEM/VAL)
DET	Detachment
DF	Direction Finding
DFT	Discrete Fourier Transform
DI	Data Item
DIA	Defense Intelligence Agency or Diameter
DID	Data Item Description
DIRCM	Directed Infrared Countermeasures
DJ	Deceptive Jamming
D-Level	Depot Level Maintenance
DM	Data Management (also manager)
DMA	Direct Memory Address or Defense Mapping Agency
DME	Distance Measuring Equipment
DNA	Defense Nuclear Agency, Does Not Apply, or Deoxyribonucleic Acid
DOA	Direction of Arrival
DOD or DoD	Department of Defense
DoDISS	DoD Index of Specifications and Standards
DOM	Depth of Modulation
DON	Department of the Navy
DOS	Disk Operating System
DOT&E	Director, Operational Test & Evaluation
DPRO	Defense Plant Representative Office
DRB	Defense Review Board
DRFM	Digital RF Memory
DSARC	Defense Systems Acquisition (and) Review Council
DSN	Defense Switching Network
DSO	Dielectrically Stabilized Oscillator
DSP	Digital Signal Processor
D-Spec	Process Specification
DT (&E)	Development or Developmental Test (and Evaluation)
DTC	Design to Cost
DTE	Data Terminal Equipment
DTO	Digitally Tuned Oscillator or Defense Technology Objectives
DTRMC	Defense (or DoD) Test Recourse Management Center

e	Electron charge or base of natural logarithms (2.71828...)
E	Electric Field Intensity or Strength, Energy, East, or Exa (10^{18} multiplier)
E^3	Electromagnetic Environmental Effects
EA	Electronic Attack (similar to older term of ECM)
EC	Electronic Combat
ECAC	Electromagnetic Compatibility Analysis Center (DOD), now Joint Spectrum Center
ECCM	Electronic Counter-Countermeasures (similar to newer term of EP)
ECL	Emitter Coupled Logic
ECM	Electronic Countermeasures (similar to newer term of EA)
ECN	Engineering Change Notice
ECO	Engineering Change Order
ECP	Engineering Change Proposal or Egress Control Point
ECR	Electronic Combat Range (China Lake) or Electronic Combat & Reconnaissance
ECS	Environmental Control System
ECSEL	Electronic Combat Simulation and Evaluation Laboratory
ECU	Electronic Control Unit
EDM	Engineering Development Model
EED	Electro-Explosive Device
EEPROM	Electrically Erasable/Programmable Read-only Memory
EHF	Extremely High Frequency [30 to 300 GHz]
EIA	Electronic Industries Associates
EID	Emitter Identification Data
EIRP	Effective Isotropic Radiated power
EL	Elevation (also El)
ELF	Extremely Low Frequency [3 Hz to 3 kHz]
ELINT	Electronics Intelligence
ELNOT	Emitter Library Notation
EM	Electromagnetic
E-Mail	Electronic Mail
EMC	Electromagnetic Compatibility
EMCAB	EMC Advisory Board
EMCON	Emission Control
EMD	Engineering and Manufacturing Development
EME	Electromagnetic Environment
EMI	Electromagnetic Interference
EMP	Electromagnetic Pulse
EMR	Electromagnetic Radiation
EMS	Electromagnetic Susceptibility, Electromagnetic Spectrum
EMV	Electromagnetic Vulnerability
EO	Electro-Optic, Electro-Optical, or Engineering Order
EOB	Electronic Order of Battle or Expense Operating Budget
EOCM	Electro-Optic Countermeasures
EOF	Electro-Optical Frequency (300 to 3 x 10^7 GHz)
EP	Electronic Protection (similar to older terms of ECCM and DECM)
EPA	Environmental Protection Agency
EPROM	Electrically Programmable Read-only Memory
ERAM	Electronic Counter-Countermeasures (also Protection) Requirements and Assessment Manual
ERP	Effective Radiated Power
ES	Electronic Surveillance (similar to older term of ESM)
ESD	Electrostatic Discharge
ESM	Electronic Support Measures (similar to newer term of ES)
ESSM	Evolved Sea Sparrow Missile
ET	Electronics Technician
ETI	Elapsed Time Indicator
ETIRMS	EW Tactical Information and Report Management System
ETR	Estimated Time to Repair
EVM	Earned Value Management
EW	Electronic Warfare , Early Warning, or Expeditionary Warfare
EWBM	EW Battle Management
EWDS	EW Data Systems
EWIA	EW Intelligence Analysis
EWIR	Electronic Warfare Integration & Reprogramming (USAF database)
EWMP	Electronic Warfare Master Plan
EWO	Electronic Warfare Officer
EWRL	Electronic Warfare Reprogrammable Library (USN)
EWSI	EW Systems Integration
EWSSA	EW Software Support Activity
EXP	Expendable Countermeasure
f	femto (10^{-15} multiplier), Frequency (also F), or lens *f* number
F	Frequency (also *f*), Force, Farad, Faraday Constant, Female, Fahrenheit, Noise Figure, Noise Factor or "Friendly" on RWR display

F2T2EA	Find, Fix, Track, Target, Engage, Assess (targeting of hostile forces)
F/A	Fighter/Attack
FAA	Federal Aviation Administration
FAC	Forward Air Controller
FAR	Federal Acquisition Regulations or False Alarm Rate
f_c	Footcandle (unit of illuminance)
FCA	Functional Configuration Audit
FCR	Fire Control Radar
FDR	Frequency Domain Reflectometry
FEBA	Forward Edge of the Battle Area
FET	Field-Effect Transistor
FEWC	Fleet EW Center
FFT	Fast Fourier Transform
FIFO	First In / First Out
FIPR	Federal Information Processing Resources
fl	fluid
FLAK	AAA Shrapnel, from the German "Flieger Abwher Kanone" (AAA gun that fires fast and furiously)
FLIR	Forward Looking Infrared
FLPS	Flightline Payload Simulator
FLT	Flight
FM	Frequency Modulation or Failure Mode
FME	Foreign Material Exploitation
FMEA	Failure Mode and Effects Analysis
FMS	Foreign Military Sale(s)
FOC	Full Operational Capability
FOD	Foreign Object Damage
FORCECAP	Force Combat Air Patrol
FOT&E	Follow-On Test and Evaluation
FOTD	Fiber Optic Towed Device
FOUO	For Official Use Only
FOV	Field of View
FPA	Focal Plane Array
fps	feet per second
FRACAS	Failure, Reporting, Analysis, and Corrective Actions System
FRB	Failure Review Board
FRD	Functional Requirements Document
FSD	Full Scale Development
FSED	Full Scale Engineering Development
FSK	Frequency Shift Keying
FSU	Former Soviet Union
ft	Feet or Foot
FTC	Fast Time Constant
FTD	Foreign Technology Division (USAF)
FWD	Forward
FY	Fiscal Year

g	Gravity (also G)
G	Universal Gravitational Constant (also K), Giga (10^9 multiplier), Conductance, or Gain
G&A	General and Administrative (expense)
GaAs	Gallium Arsenide
GACIAC	Guidance and Control Information Analysis Center (DoD)
gal	Gallon
GAO	General Accounting Office
GBU	Guided Bomb Unit
GCA	Ground Controlled Approach
GCI	Ground Control Intercept
GENSER	General Service
GEN-X	Generic Expendable
GFE	Government Furnished Equipment
GHz	GigaHertz
GI	Government Issue
GIDEP	Government Industry Data Exchange Program
GIG	Global Information Grid
GIGO	Garbage In / Garbage Out
GOCO	Government Owned Contract Operated
GOFO	General Officer / Flag Officer
GP	General Purpose
GPI	Ground Plane Interference
GPIB	General Purpose Interface Bus
GPS	Global Positioning System
GSE	Ground Support Equipment

h	hours, hecto (10^2 multiplier), Plank's constant, or height (also H)
H	Height (also h), Henry (Inductance), or Irradiance
HARM	High-speed Anti-Radiation Missile
HAWK	Homing All the Way Killer
HDBK	Handbook
HDF	High Duty Factor
HE	High Explosive
HEF	High Energy Frequency ($3x10^7$ to $3x10^{14}$ GHz)
HEL	High Energy Laser
HELO	Helicopter
HERF	Hazards of Electromagnetic Radiation to Fuel
HERO	Hazards of Electromagnetic Radiation to Ordnance
HERP	Hazards of Electromagnetic Radiation to Personnel
hex	hexadecimal
HF	High Frequency [3 - 30 MHz]
HIL or HITL	Hardware-in-the-Loop

HOJ	Home-On-Jam
HOL	Higher Order Language
HPF	High-Pass Filter
HP-IB	Hewlett-Packard Interface Bus
HP-IL	Hewlett-Packard Interface Loop
HPM	High Powered Microwave
HPRF	High Pulse Repetition Frequency
hr	hour
HSDB	High Speed Data Bus
HUD	Heads-Up Display
HV	High Voltage
H/W	Hardware
HWCI	Hardware Configuration Item
HWIL	Hardware-in-the-loop
Hz	Hertz (Cycles per second)
i	current (also I)
I	Current (also i), Intensity, Irradiance, Intermediate, or Roman Numeral for One
IA	Information Assurance
IADS	Integrated Air Defense System
I&Q	In-Phase and Quadrature
IAS	Indicated Airspeed
IAW	In Accordance With
IBIT	Initiated Built-in-Test
IBU	Interference Blanker Unit
IC	Integrated Circuit
ICD	Interface Control Document Initial Capabilities Document
ICMD	Improved Countermeasure Dispenser
ICNIA	Integrated Communication, Navigation, Identification Avionics
ICS	Inverse Conical Scan or Intercommunications System (aircraft)
ICW	In Compliance With
ID	Identification
IDA	Institute For Defense Analysis
IDECM	Integrated Defensive Electronic Countermeasures
IEEE	Institute of Electrical and Electronic Engineers
IF	Intermediate Frequency
IFF	Identification Friend-or-Foe
IFM	Instantaneous Frequency Measurement
IFR	Instrument Flight Rules
IG	Inspector General
IIR	Imaging Infrared
I-Level	Intermediate Level of Repair (also "I" Level)
ILS	Integrated Logistic Support, Instrument Landing System, or Inertial Locator System
ILSMT	Integrated Logistic Support Management Team
IM	Intermodulation or Item Manager
IMA	Intermediate Maintenance Activity
in	Inch
INEWS	Integrated Electronic Warfare System
INS	Inertial Navigation System
INT	Intensity
IO	Information Operations
I/O	Input/Output
IOC	Initial Operational (also Operating) Capability
IOT&E	Initial Operational Test and Evaluation
IPO	International Projects (Program) Office
IPR	In-Progress/Process Review
IPT	Integrated Product (also Program) Team
IR	Infrared
IR&D	Independent Research and Development
IRCM	Infrared Countermeasures
IRDS	Infrared Detecting System
IREXP	IR Expendables
IRIG-B	Inter-range Instrumentation Group B
IRLS	Infrared Line Scanner
IRS	Interface Requirements Specification, IR Suppression or Internal Revenue Service
IRST	Infrared Search and Track
ISAR	Inverse Synthetic Aperture Radar
ISO	Derived from the Greek "isos" meaning "equal," the official title is International Organization for Standardization
ISP	Integrated Support Plan Intelligence Support Plan
ISR	Interference to Signal Ratio (also I/S)
ITU	International Telecommunications Union
IV&V	Independent Validation and Verification
IW	Information Warfare

J	Jamming, Radiance, Current Density, or Joules
JAAS	Joint Architecture for Aircraft Survivability
JAFF	Jammer (illuminating) Chaff
JAG	Judge Advocate General
JAMS	Jamming Analysis Measurement System
JARS	Jamming Aircraft & Radar Simulation
JASSM	Joint Air-to-Surface Standoff Missile
JAST	Joint Advanced Strike Technology
JATO	Jet Assisted Takeoff or JAmmer Technique Optimization
JC2WC	Joint Command and Control Warfare Center (now JIOWC)
JCTD	Joint Concept Technology Demonstration
JCS	Joint Chiefs of Staff or Joint Spectrum Center (formerly ECAC)
JDAM	Joint Direct Attack Munition
JEACO	Joint Electronic Attack and Compatibility Office
JED	Journal of Electronic Defense (Published by the Association of Old Crows)
JEM	Jet Engine Modulation
JETS	Joint Emitter Targeting System
JEWC	Joint EW Conference or Joint EW Center (then JC2WC & now JIOWC)
JEWEL	Joint Electronic Warfare Effects Laboratory
JIOWC	Joint Information Operations Warfare Command
JMEM	Joint Munitions Effectiveness Manual
JMR	Jammer
JOVIAL	Julius' Own Version of International Algorithmic Language (Air Force computer programming language)
JPATS	Joint Primary Aircraft Training System
J/S	Jamming to Signal Ratio
JSF	Joint Strike Fighter
JSGCC	Joint Services Guidance and Control Committee
JSIR	Joint Spectrum Interference Resolution (signal interference portion of MIJI)
JSOW	Joint Stand-Off Weapon (AGM-154A)
JSTARS	Joint Surveillance Target Attack Radar System
JTA	Jammer Threat Analysis
JTAT	JATO Techniques Analysis and Tactics
JTCG/AS	Joint Technical Coordinating Group for Aircraft Survivability
JTCG/ME	Joint Technical Coordinating Group for Munitions Effectiveness
JTIDS	Joint Tactical Information Distribution System
JV or J/V	Joint Venture

k	kilo (10^3 multiplier) or Boltzmann Constant
K	Kelvin, Cathode, Universal gravitational constant (also G), or Luminous efficacy
KCAS	Knots Calibrated Airspeed
kg	kilogram
kHz	KiloHertz
KIA	Killed in Action
KIAS	Knots Indicated Air Speed
km	Kilometer
KSLOC	Thousand Source Lines of Code (software)
kt	Knot (nautical miles per hour)
kW	Kilowatt

l	length (also L) or liter
L	Length (also l), Loss, inductance, Luminance, or Roman Numeral for fifty
LADAR	Laser Detection and Ranging (i.e., laser radar)
LAN	Local Area Network
LANTIRN	Low Altitude Navigation & Targeting Infrared for Night
LASER	Light Amplification by Stimulated Emission of Radiation
LAT	Latitude (0-90° N or S from equator)
lbs	pounds
LCC	Life Cycle Cost(s)
LCD	Liquid Crystal Display or Lowest Common Denominator
LCP or LHCP	Left-hand Circular Polarization
LDF	Low Duty Factor
LDS	Laser Detecting Set
LED	Light-Emitting Diode
LEX	Leading Edge Extension
LGB	Laser Guided Bomb
LF	Low Frequency [30 - 300 kHz]
LIC	Low Intensity Combat or Laser Intercept Capability

LISP	List Processing (A programming language used in artificial intelligence)
LLL	Low Light Level (as in LLL TV)
lm	lumen (SI unit of luminous flux)
ln	Natural Logarithm
LO	Local Oscillator or Low Observable
LOA	Letter of Agreement (or Acceptance)
LOB	Line of Bearing (see also AOA)
LOG	Logarithm to the base 10 (also log) or Logistician
LONG	Longitude (0-180° E or W from Greenwich, U.K.)
LOR	Level of Repair
LORA	Level of Repair Analysis
LORAN	Long Range Navigation
LORO	Lobe on Receive Only
LOS	Line-of-Sight
LPAR	Large Phased-Array Radar
LPD	Low Probability of Detection
LPF	Low Pass Filter
LPI or LPOI	Low Probability of Intercept
LPRF	Low Pulse Repetition Frequency
LR	Lethal Range
LRA	Line Replaceable Assembly
LRF	Laser Rangefinder
LRIP	Low Rate Initial Production
LRU	Line Replaceable Unit
LSA	Logistic Support Analysis
LSAR	Logistic Support Analysis Record
LSB	Least Significant Bit
LSI	Large Scale Integration
LSO	Landing Signal Officer
LSSO	Laser System Safety Officer
LTBB	Look Through Blanking Bus
LWIR	Long Wave Infrared
LWR	Laser Warning Receiver
lx	Lux (SI unit of illuminance)
LZ	Landing Zone

m	milli (10^{-3} multiplier), meter, or electron mass
M	Mega (10^6 multiplier), Male, Mach number, or Roman numeral for 1,000
MA	Missile Alert or Missile Active
MAD	Magnetic Anomaly Detection (also Detector)
MADD	Microwave Acoustic Delay Device
MAF	Maintenance Action Form
MAG	Marine Aircraft Group or Magnetic
MAGTF	Marine Air-Ground Task Force
MANPADS	Man-portable Air Defense System
M&S	Modeling and Simulation
MASER	Microwave Amplification by Simulated Emission of Radiation
MATE	Modular Automatic Test Equipment
MAW	Missile Approach Warning system (also MAWS) or Marine Aircraft Wing
MAX	Maximum or Maximum aircraft power (afterburner)
MBFN	Multiple Beam Forming Network
MC	Mission Computer
MCIOC	Marine Corps Information Operations Center
MCP	Micro-Channel Plate
MDF	Mission Data File
MDI	Multiple Display Indicator or Miss Distance Indicator
MDG	Mission Data Generator
MDS	Minimum Discernible Signal or Minimum Detectable Signal
MDU	Multipurpose Display Unit
MF	Medium Frequency (300 kHz to 3 MHz)
MFD	Multifunction (video) Display
MG	Missile Guidance
MHz	MegaHertz (10^6 Hz)
MIA	Missing in Action
MIC	Microwave Integrated Circuit or Management Information Center
MICRON	10^{-6} meter
MiG	Mikoyan-Gurevich (Soviet aircraft manufacturer)
MIGCAP	MiG Combat Air Patrol
MIJI	Meaconing, Intrusion, Jamming, & Interference (also see JSIR)
mil	One-thousandth of an inch
MIL	Military power (100%, no afterburner) or Military
MILCON	Military Construction
MILSPEC	Military Specification
MILSTRIP	Military Standard Requisitioning and Issue Procedure(s)
MIMIC	Microwave Monolithic Integrated Circuit (also MMIC)
MIN	Minimum
Mincon	Minimal Construction
MIPPLE	RWR display switching between ambiguous emitters
MIPS	Millions of (Mega) Instructions Per Second
ML	Missile Launch
MLC	Main Lobe Clutter
MLV	Memory Loader Verifier
MLVS	Memory Loader Verifier Set

mm	Millimeter
MM	Man Month
MMIC	Microwave Monolithic Integrated Circuit (also MIMIC)
MMW	Millimeter Wave (40 GHz or higher per IEEE, but commonly used down to 30 GHz)
MOA	Memorandum of Agreement
MOE	Measure of Effectiveness
MOM	Methods of Moments (also MoM) or Metal-Oxide-Metal
MOP	Modulation on Pulse or Measure of Performance
MOPS	Million Operations Per Second
MOS	Minimum Operational Sensitivity, Military Occupational Specialty, Metal-Oxide Semiconductor, or Measure of Suitability
MOSAIC	Modeling System for Advanced Investigation of Countermeasures
MOU	Memorandum of Understanding
MPD	Multi-Purpose Display or Microwave Power Device
MPE	Maximum Permissible Exposure
mph	Miles per Hour
MPLC	Multi-Platform Launch Controller
MPM	Microwave Power Module
MPPS	Million Pulses Per Second
MPRF	Medium Pulse Repetition Frequency
mr or mrad	Milliradian
MRC	Maintenance Requirement Card or Medium Range CAP
MRE’s	Meals Ready to Eat
ms	Milliseconds
MSB	Most Significant Bit
MSI	Multi-Sensor (also Source) Integration, Management Support Issues, or Medium Scale Integration
MSIC	Missile and Space Intelligence Center
MSL	Mean Sea Level (altitude) or Missile
MTBF	Mean Time Between Failures
MTI	Moving Target Indicator (or Indication)
MTTR	Mean Time To Repair
MUXBUS	Multiplex Bus
MVS	Minimum Visible Signal
mw	Microwave
mW	Milliwatt
MWIR	Mid Wave Infrared
MWS	Missile Warning Set
MY	Man Year

n	nano (10^{-9} multiplier) or number of elements
N	Noise, Newton (force), Radiance, North, or No
n/a	Not Applicable (also N/A)
NA	Numerical Aperture
NADEP	Naval Aviation Depot
NASA	National Aeronautics and Space Administration
NATO	North Atlantic Treaty Organization
NATOPS	Naval Air Training and Operating Procedures Standardization
NAV	Navigation
NAVAIR	Naval Air Systems Command (also NAVAIRSYSCOM)
NavMPS	Naval Mission Planning System
NAVSEA	Naval Sea Systems Command (also NAVSEASYSCOM)
NAWCAD	Naval Air Warfare Center Aircraft Division
NAWCWD	Naval Air Warfare Center Weapons Division
NBC	Nuclear, Biological, Chemical
NCTR	Non-Cooperative Target Recognition
NDI	Non-Developmental Item or Non Destructive Inspection
NEI	Noise Equivalent Power
NEMP	Nuclear Electromagnetic Pulse
NEOF	No Evidence of Failure
NEP	Noise Equivalent Power
NF	Noise Figure or Noise Factor (also F)
NFO	Naval Flight Officer
NGJ	Next Generation Jammer
NIOC	Navy Information Operations Command
NIPO	Navy International Program Office
NIR	Near Infrared
nm	nanometer or Nautical Mile (also NM or NMI)
NM or NMI	Nautical Mile (also nm)
NMCI	Navy Marine Corps Intranet
NNWC	Naval Network Warfare Command
NOHD	Nominal Ocular Hazard Distance
NORAD	North American Air Defense Command
NPG or NPGS	Naval Post Graduate School
NRE	Non-Recurring Engineering
NRL	Naval Research Laboratory
NRZ	Non Return to Zero
NSA	National Security Agency
nsec or ns	Nanosecond
NSN	National Stock Number
NSWC	Naval Surface Weapons Center
nt	Nit (SI unit of luminance)

NUWC	Naval Undersea Warfare Center
NVG	Night Vision Goggles
NWIP	Naval Warfare Information Publication
NWP	Naval Warfare Publication
O	Optical
OADR	Originating Agency's Determination Required
OAG	Operational Advisory Group
O&MN	Operations and Maintenance, Navy (also O&M,N)
OBE	Overtaken (Overcome) By Events
OCA	Offensive Counter Air
OEWTPS	Organizational Electronic Warfare Test Program Set
OFP	Operational Flight Program
OJT	On-the-Job Training
O-Level	Organizational Level of Repair (also "O" Level)
OMA	Organizational Maintenance Activity
OMB	Office of Management and Budget
OMEGA	Optimized Method for Estimating Guidance Accuracy (VLF Navigation System)
ONR	Office of Naval Research
OOK	On-Off Keying
OPEVAL	Operational Evaluation
OPM	Office of Personnel Management
OPSEC	Operational Security
OPTEVFOR	Operational Test and Evaluation Force
OR	Operational Requirement or Operationally Ready
ORD	Operational Requirements Document
OSD	Office of the Secretary of Defense
OSHA	Occupational Safety and Health Act
OSIP	Operational Safety Improvement Program
OSM	Operating System Memory or SMA connector made by Omni-Spectra
OSRB	Operational Software Review Board
OT (&E)	Operational Test (and Evaluation)
OTD	Operational Test Director
OTH	Over the Horizon
OTH-B	Over-the-Horizon Backscatter
OTH-R	Over-the-Horizon Radar
OTH-T	Over-the-Horizon Targeting
OTRR	Operational Test Readiness Review
OUSD	Office of the Under Secretary of Defense
oz	ounce
p	pico (10^{-12} multiplier) or page
P	Power, Pressure, or Peta (10^{15} multiplier)
P^3I	Pre-Planned Product Improvement
Pa	Pascal (pressure)
PA	Public Address or Program Analyst
PBIT	Periodic Built-in-Test
PC	Pulse Compression, Personal Computer, or Photoconductive
PCA	Physical Configuration Audit
PCM	Pulse Code Modulation
P_d	Probability of Detection
PD	Pulse Doppler
PDI	PD Illuminator or Post Detection Integration
PDP	Plasma Display Panel
PDQ	Pretty Darn [sic] Quick
PDR	Preliminary Design Review
PDW	Pulse Descriptor Word
PEL	Personnel Exposure Limits
PEM	Photoelectromagnetic
PEO	Program Executive Officer
pf	Power Factor or Pico Farads
PFA	Probability of False Alarm
PGM	Precision Guided Munition
ph	Phot (unit of illuminance)
P_h	Probability of Hit
pi	Greek letter π
P_i	Probability of Intercept (also POI)
PID	Positive Identification
PIN	Personal Identification Number
PIP	Product Improvement Plan or Predicted Intercept Point
Pixel	Picture Element
P_k	Probability of Kill or Peak
PLSS	Precision Location Strike System
PM	Phase Modulation or Program Manager
PMA	Program (also Project) Manager, Air
PMAWS	Passive Missile Approach Warning System
PMS	Program Manager, Ship
PMT	Photomultiplier Tube
PMW	Program Manager, Warfare
P-N	Positive to Negative Junction (also p-n)
PN or P/N	Part Number
POC	Point of Contact
POET	Primed Oscillator Expendable Transponder
POI	Probability of Intercept (also PI)
POL	Polarization
POM	Program Objective Memorandum

POP	Pulse-on-Pulse or Product Optimization Program
POST	Passive Optical Seeker Technology (Stinger missile)
PPI	Plan Position Indicator
PPS	Pulses Per Second
PRF	Pulse Repetition Frequency
PRI	Priority or Pulse Repetition Interval
PROM	Programmable Read-only Memory
PRR	Production Readiness Review or Pulse Repetition Rate
PRT	Pulse Repetition Time
P_s	Probability of Survival
P's & Q's	Pints and Quarts (small details)
PSK	Phase-shift Keying
PUPS	Portable Universal Programming System
PV	Photovoltaic
pw or PW	Pulse Width
PWB	Printed Wiring Board

q	electron charge
Q	Quantity Factor (figure of merit), Quadrature, aerodynamic pressure, or Charge (coulomb)
QA	Quality Assurance
QC	Quality Control
QED	Quod Erat Demonstradum (end of proof)(Satirically "quite easily done")
QML	Qualified Manufacturer Listing
QPL	Qualified Parts List
QRC	Quick-Reaction Capability
QRD	Quick Reaction Demonstration
QRT	Quick-Reaction test

r or R	Radius or Range
R	Resistance, Reliability, or Roentgen
rad	Radian
R&D	Research and Development
RADAR	Radio Detection and Ranging
RADHAZ	Radiation Hazard
RAM	Random Access Memory, Radar Absorbing Material, Rolling Airframe Missile, or Reliability, Availability, and Maintainability
R&M	Reliability and Maintainability
RAT	Ram Air Turbine
RBOC	Rapid Blooming Offboard Chaff
RCP or RHCP	Right-hand Circular Polarization
RCS	Radar Cross Section
RCVR	Receiver
RDT&E	Research, Development, Test, & Evaluation
RDY	Ready
RE	Radiated Emissions
REC	Receive
RET	Return
RF	Radio Frequency
RFEXP	RF Expendables
RFI	Radio Frequency Interference, Ready-For-Issue, or Request for Information
RFP	Request for Proposal
RFQ	Request for Quotation
RFSS	Radio Frequency Simulation System (Army)
RGPO	Range Gate Pull Off
RGS	Range Gate Stealer
RGWO	Range Gate Walk Off (see RGPO)
RHAW	Radar Homing and Warning Receiver or Radar Homing All the Way
RHAWS	Radar Homing and Warning System
RINT	Radiation Intelligence
RIO	Radar Intercept Officer
RM	Radar Mile
rms or RMS	Root Mean Square
RNG	Range
ROC	Required Operational Capability
ROE	Rules of Engagement
ROI	Return on Investment
ROM	Read-only Memory or Rough Order of Magnitude
ROR	Range Only Radar or Rate of Return (financial)
ROT	Rate of Turn
ROWG	Response Optimization Working Group
RPG	Receiver Processor Group
RPM	Revolutions per Minute
RPT	Repeat
RPV	Remotely Piloted Vehicle
RRT	Rapid Reprogramming Terminal (a type of MLVS)
RS	Radiated Susceptibility or Remote Station
RSDS	Radar Signal Detecting Set
RSO	Range Safety Officer or Receiver, Set-on
RST	Receiver Shadow Time
RT	Remote Terminal, Termination Resistance, or Receiver/Transmitter (also R/T)
RUG	Radar Upgrade
RWR	Radar Warning Receiver
Rx	Receive

s, S, or sec	seconds
S	Signal Power, Surface Area, Secret, Electrical conductance (siemens), South, Scattering (as in S-parameters), or Seconds
SA	Situational Awareness, Semi-Active, Spectrum Analyzer, or Surface-to-Air (also S/A or S-A)
SA-()	Surface-to-Air missile number ()
SAE	Society of Automotive Engineers
SAM	Surface-to-Air Missile
SA-N-()	Naval Surface-to-Air missile number
SAR	Synthetic Aperture Radar, Special Access Required, Semi-Active Radar, Search and Rescue, or Specific Absorption Rate
SATS	Semi-Active Test System
SAW	Surface Acoustic Wave
SBIR	Small Business Innovative Research
SCI	Sensitive Compartmented Information
SCIF	Sensitive Compartmented Information Facility
SCN	Specification Change Notice
SCR	Software Change Request
SCP	Software Change Proposal
SCRB	Software Configuration Review Board
SCUD	Soviet short-range surface-to-surface missile
SE	Support Equipment
SDLM	Standard Depot Level Maintenance
SDI	Strategic Defense Initiative
SEAD	Suppression of Enemy Air Defense (pronounced “seed” or “C add”)
SEAL	Sea-Air-Land (Navy special forces)
sec	seconds (also S or s)
SECDEF	Secretary of Defense
SEI	Specific Emitter Identification
SEMA	Special Electronic Mission Aircraft
SERD	Support Equipment Recommendation Data
SHAPE	Supreme Headquarters Allied Powers Europe (NATO military command)
SHF	Super High Frequency (3 to 30 GHz)
SI	Special Intelligence or System International (Units)
SIF	Selective Identification Feature
SIGINT	Signals Intelligence
SIJ	Stand-In Jamming (also S/J)
SIM	Simulation
sin	Sine
SINCGARS	Single Channel Ground and Airborne Radio System
SIRCM	Suite of IR Countermeasures
SIRFC	Suite of Integrated RF Countermeasures
SJ	Support Jamming
S/J	Stand-In Jamming or Signal to Jamming Ratio
SL	Side lobe or Sea Level (also S.L.)
SLAM	Standoff Land Attack Missile
SLAR	Side-Looking Airborne Radar
SLC	Side Lobe Clutter
SLOC	Source Lines of Code or Sea Lines of Communication
SM	Statute Mile (also sm) or Standard Missile
SMA	Scheduled Maintenance Action or Sub-Miniature A connector
SMC	Sub-Miniature C connector
SME	Subject Matter Expert
SML	Support Material List
SMS	Stores Management Set or Status Monitoring System
S/N or SNR	Signal-to-Noise Ratio
SNORT	Supersonic Naval Ordnance Research Track
SNTK	Special Need to Know
SOF	Safety of Flight
SOJ	Stand-off Jammer
SONAR	Sound Navigation and Ranging
SOO	Statement of Objectives (replacing SOW)
SOP	Standard Operating Procedures
SORO	Scan-on-Receive Only
SOS	“Save Our Ship” (distress call with easy Morse code, i.e. • • • – – – • • •)
SOW	Statement of Work (being replaced by SOO)
SPAWAR	Space and Naval Warfare Systems Command
SPEC	Specification
SPIRITS	Spectral Infrared Imaging of Targets and Scenes
SPO	System Program Office
SPY	Radar on an AEGIS ship
sq	Square
sr	Steradian
SRA	Shop Replaceable Assembly
SRAM	Static Random Access Memory
SRB	Software Review Board
SRBOC	Super Rapid Blooming Offboard Chaff
SRD	Systems Requirements Document
SRS	Software Requirements Specification
SRU	Shop Replaceable Unit

SSA	Software (also Special or System) Support Activity, Source Selection Activity, or Solid State Amplifier
SSB	Single Side Band
SSI	Small Scale Integration
SSJ	Self Screening Jamming
SSM	Surface-to-Surface Missile
SSRO	Sector Scan Receive Only
SSW	Swept Square Wave
S&T	Science and Technology
STANAG	Standardization Agreement (NATO)
STAR	System Threat Assessment Report
stat	Statute
STBY	Standby
STC	Sensitivity Time Control, Short Time Constant or SHAPE Technical Center
STD	Software Test Description, Standard, or Sexually Transmitted Disease
STE	Standard Test Equipment
STOVL	Short Takeoff and Vertical Landing
STP	Software Test Plan, or Standard Temperature and Pressure (0°C at 1 atmosphere)
STR	Software (also System) Trouble Report
STT	Single Target Track
STU	Secure Telephone Unit
SUBSAM	Subsurface-to-Air Missile
SUT	System Under Test
S/W	Software (also SW)
SWAP	Size, Weight, And Power
SWC	Scan With Compensation
SWM	Swept Wave Modulation
SYSCOM	Systems Command
t	Time (also T)
T	Time (also t), tera (10^{12} multiplier), Temperature, or Telsa
TA	Target Acquisition or Terrain Avoidance
TAAF	Test, Analyze, and Fix
TAC	Tactical Air Command (now ACC)
TACAIR	Tactical Aircraft
TACAMO	Take Charge and Move Out (airborne strategic VLF communications relay system)
TACAN	Tactical Air Navigation
TACDS	Threat Adaptive Countermeasures Dispensing System
TACTS	Tactical Aircrew Combat Training System
TAD	Threat Adaptive Dispensing, Temporary Additional (also Active) Duty, or Tactical Air Direction
T&E	Test & Evaluation
TALD	Tactical Air Launched Decoy
TAMPS	Tactical Automated Mission Planning System
TAR	Target Acquisition Radar or Training Administrative Reserve
TAS	True Airspeed
TBA	To Be Announced
TBD	To Be Determined
TBMD	Theater Ballistic Missile Defense
TD	Technical Directive (also Director)
TDD	Target Detection Device
TDM	Time Division Multiplexing
TE	Transverse Electric
TEA	Technology Exchange Agreement
TEAMS	Tactical EA-6B Mission Support
TECHEVAL	Technical Evaluation
TEL	Transporter Erector Launcher
TEM	Transverse Electromagnetic
TEMP	Test and Evaluation Master Plan
TEMPEST	Not an acronym. Certification of reduced electromagnetic radiation for security considerations
TENA	Training Enabling Architecture
TERPES	Tactical Electronic Reconnaissance Processing and Evaluation System
TGT	Target
TIM	Technical Interchange Meeting
TM	Telemetry, Transverse Magnetic, or Technical Manual
TMD	Theater Missile Defense
TNC	Threaded Navy Connector
TOA	Time of Arrival
TOJ	Track on Jam
TOO	Target of Opportunity (HARM operating mode)
TOR	Tentative (also Tactical) Operational Requirement or Time of Receipt
TOS	Time on Station
TOT	Time on Target
TOW	Tube-Launched, Optically-Tracked, Wire-guided
TPI	Test Program Instruction
TPS	Test Program Set or Test Pilot School
TPWG	Test Plan Working Group
TQM	Total Quality Management
T/R	Transmit / Receive
TRB	Technical Review Board
TRD	Test Requirements Document
TREE	Transient Radiation Effects on Electronics

TRF	Tuned Radio Frequency
TRR	Test Readiness Review
TS	Top Secret
TSS	Tangential Sensitivity
TSSAM	Tri-Service Standoff Attack Weapon
TT	Target Track
TTI	Time To Impact/Intercept
TTG	Time-to-Go
TTL	Transistor-Transistor Logic
TTR	Target Tracking Radar
TV	Television
TVC	Thrust Vector Control
TWS	Track While Scan or Tail Warning System
TWSRO	Track While Scan on Receive Only
TWT	Traveling Wave Tube
TWTA	Traveling Wave Tube Amplifier
Tx	Transmit
TYCOM	Type Commander

u or µ	micron / micro (10^{-6} multiplier)
U	Unclassified, Unit, or Unknown (on RWR display)
UAS	Unmanned Aerial System
UAV	Unmanned (also uninhabited) Air (or Aerial) Vehicle
UCAV	Uninhabited Combat Air Vehicle (new USAF term for UAV)
UDF	User Data File
UDFG	User Data File Generator
UDM	User Data Module
UHF	Ultra High Frequency (300 MHz to 3 GHz)
ULF	Ultra Low Frequency (3 to 30 Hz)
µm	Micrometer
UN	United Nations
UNK	Unknown (also U)
UPC	Unique Planning Component
UPS	Uninterruptable Power Supply
us or µs	Microseconds
U.S.	United States
USA	United States of America or United States Army
USAF	United States Air Force
USMC	United States Marine Corps
USN	United States Navy
UTA	Uninhabited Tactical Aircraft
UUT	Unit Under Test
UV	Ultraviolet

v	Volts (also V), Velocity (also V or v_t)
V	Volts (also v), Velocity (also v or v_t), Volume, or Roman Numeral for five
VA	Veterans Administration, Volt-Amperes
VAQ	Prefix for Navy tactical EW squadron
V&V	Validation and Verification
VCO	Voltage Controlled Oscillator
Vdc or VDC	Volts Direct Current
VDT	Video Display Terminal
VECP	Value Engineering Change Proposal
VF	Prefix for Navy fighter squadron
VFO	Variable Frequency Oscillator
VFR	Visual Flight Rules
VGPO	Velocity Gate Pull Off
VGS	Velocity Gate Stealer
VGWO	Velocity Gate Walk Off
VHF	Very High Frequency (30 - 300 MHz)
VHSIC	Very High Speed Integrated Circuit
VID	Visual Identification
VLF	Very Low Frequency (3 to 30 kHz)
VLSI	Very Large Scale Integration
VLSIC	Very Large Scale Integrated Circuit
VMAQ	Prefix for Marine Tactical EW Squadron
VP	Prefix for Navy patrol squadron
VQ	Prefix for Navy special mission (usually reconnaissance) squadron
VRAM	Video Random Access Memory
VS or vs	Velocity Search or Versus (also vs.)
V/STOL	Vertical/Short Take-off and Landing (also VSTOL)
vt	Velocity (also V or v)
VTOL	Vertical Takeoff and Landing
VSWR	Voltage Standing Wave Ratio
VVA	Voltage Variable Attenuator

W	Watts, Weight, or West
W&T	Warning & Targeting
WARM	Wartime Reserve Mode
wb	Weber (magnetic flux)
WBS	Work Breakdown Structure
WC	Waveguide, circular
WFT	Windowed Fourier Transform
WGIRB	Working Group on Infrared Background
WORM	Write Once Read Many [times] (Refers to optical disks)
WOW	Weight on/off Wheels (also WonW or WoffW)
WPN	Weapons Procurement, Navy or Weapon

WR	Waveguide, rectangular
WRA	Weapon Replaceable Assembly
WRD	Waveguide, rectangular double ridged
WSSA	Weapons System Support Activity
WVR	Within Visual Range

x	Multiplication symbol
X	Reactance, Experimental, Extraordinary, Roman Numeral for ten, or X axis
X-EYE	Cross Eye
X-POL	Cross Polarization
XMIT	Transmit
XMTR	Transmitter

Y	Yes or Y-Axis
YAG	Yttrium-Aluminum Garnet
yd	Yard
YIG	Yttrium-Iron Garnet

Z	Impedance, Zenith, or Z-Axis

1xLR, 2xLR	One (or two or three etc.) Times Lethal Range
1v1 or 1-v-1	One versus One (Aerial engagement)

2D	Two Dimension

3D	Three Dimension
3M	Navy Maintenance and Material Management System

FUNDAMENTALS

Constants, Conversions, and Characters 2-1
Mathematical Notation 2-2
Frequency Spectrum 2-3
Decibel (dB) 2-4
Duty Cycle 2-5
Doppler Shift 2-6
Electronic Formulas 2-7
Missile and Electronic Equipment Designations 2-8
Radar Horizon / Line of Sight 2-9
Propagation Time / Resolution 2-10
Modulation 2-11
Transforms / Wavelets 2-12

This page intentionally left blank.

CONSTANTS, CONVERSIONS, and CHARACTERS

DECIMAL MULTIPLIER PREFIXES

Prefix	Symbol	Multiplier
exa	E	10^{18}
peta	P	10^{15}
tera	T	10^{12}
giga	G	10^{9}
mega	M	10^{6}
kilo	k	10^{3}
hecto	h	10^{2}
deka	da	10^{1}
deci	d	10^{-1}
centi	c	10^{-2}
milli	m	10^{-3}
micro	µ	10^{-6}
nano	n	10^{-9}
pico	p	10^{-12}
femto	f	10^{-15}
atto	a	10^{-18}

EQUIVALENCY SYMBOLS

Symbol	Meaning
∝	Proportional
~	Roughly equivalent
≈	Approximately
≅	Nearly equal
=	Equal
≡	Identical to, defined as
≠	Not equal
>>	Much greater than
>	Greater than
≥	Greater than or equal to
<<	Much less than
<	Less than
≤	Less than or equal to
∴	Therefore
°	Degrees
′	Minutes or feet
“	Seconds or inches

UNITS OF LENGTH

1 inch (in) = 2.54 centimeters (cm)
1 foot (ft) = 30.48 cm = 0.3048 m
1 yard (yd) ≅ 0.9144 meter
1 meter (m) ≅ 39.37 inches

1 kilometer (km) ≅ 0.54 nautical mile
≅ 0.62 statute mile
≅ 1093.6 yards
≅ 3280.8 feet

1 statute mile ≅ 0.87 nautical mile
(sm or stat. mile) ≅ 1.61 kilometers
= 1760 yards
= 5280 feet

1 nautical mile ≅ 1.15 statute miles
(nm or naut. mile) ≅ 1.852 kilometers
≅ 2025 yards
≅ 6076 feet
1 furlong = 1/8 mi (220 yds)

UNITS OF SPEED

1 foot/sec (fps) ≅ 0.59 knot (kt)*
≅ 0.68 stat. mph
≅ 1.1 kilometers/hr

1000 fps ≈ 600 knots

1 kilometer/hr ≅ 0.54 knot
(km/hr) ≅ 0.62 stat. mph
≅ 0.91 ft/sec

1 mile/hr (stat.) ≅ 0.87 knot
(mph) ≅ 1.61 kilometers/hr
≅ 1.47 ft/sec

1 knot* ≅ 1.15 stat. mph
≅ 1.69 feet/sec
≅ 1.85 kilometer/hr
≅ 0.515 m/sec

*A knot is 1 nautical mile per hour.

UNITS OF VOLUME

1 gallon ≅ 3.78 liters
≅ 231 cubic inches
≅ 0.1335 cubic ft
≅ 4 quarts
≅ 8 pints

1 fl ounce ≅ 29.57 cubic centimeter (cc) or milliliters (ml)

1 in^3 ≅ 16.387 cc

UNITS OF AREA

1 sq meter ≅ 10.76 sq ft

1 sq in ≅ 645 sq millimeters (mm)
= 1,000,000 sq mil
1 mil = 0.001 inch

1 acre = 43,560 sq ft

UNITS OF WEIGHT

1 kilogram (kg) ≅ 2.2 pounds (lbs)

1 pound ≅ 0.45 Kg
= 16 ounce (oz)
1 oz = 437.5 grains
1 carat ≅ 200 mg
1 stone (U.K.) ≅ 6.36 kg

NOTE: These are the U.S. customary (avoirdupois) equivalents, the troy or apothecary system of equivalents, which differ markedly, was used long ago by pharmacists.

UNITS OF POWER / ENERGY

1 H.P. = 33,000 ft-lbs/min
= 550 ft-lbs/sec
≅ 746 Watts
≅ 2,545 BTU/hr
(BTU = British Thermal Unit)

1 BTU ≅ 1055 Joules
≅ 778 ft-lbs
≅ 0.293 Watt-hrs

SCALES

OCTAVES

"N" Octaves = Freq to Freq x 2^N
i.e., One octave would be 2 to 4 GHz
Two Octaves would be 2 to 8 GHz
Three octaves would be 2 to 16 GHz

DECADES

"N" Decades = Freq to Freq x 10^N
i.e., One decade would be 1 to 10 MHz
Two decades would be 1 to 100 MHz
Three decades would be 1 to 1,000 MHz

TEMPERATURE CONVERSIONS

°F = (9/5) °C + 32
°C = (5/9)(°F - 32)
°K = °C + 273.16
°F = (9/5)(°K - 273) + 32
°C = °K - 273.16
°K = (5/9)(°F - 32) + 273

UNITS OF TIME

1 year = 365.2 days
1 fortnight = 14 nights (2 weeks)
1 century = 100 years
1 millennium = 1,000 years

NUMBERS

1 decade = 10
1 Score = 20
1 Billion = 1 x 10^9 (U.S.) (thousand million)
= 1 x 10^{12} (U.K.) (million million)

RULE OF THUMB FOR ESTIMATING DISTANCE TO LIGHTNING / EXPLOSION:

km: Divide 3 into the number of seconds which have elapsed between seeing the flash and hearing the noise.
miles: Multiply 0.2 times the number of seconds which have elapsed between seeing the flash and hearing the noise.

Note: Sound vibrations cause a change of density and pressure within a media, while electromagnetic waves do not. An audio tone won't travel through a vacuum but can travel at 1,100 ft/sec through air. When picked up by a microphone and used to modulate an EM signal, the modulation will travel at the speed of light.

Physical Constant	Quoted Value	S*	SI unit	Symbol
Avogadro constant	6.0221367 x 10^{23}	36	mol^{-1}	N_A
Bohr magneton	9.2740154 x 10^{-24}	31	J•T^{-1}	μ_B
Boltzmann constant	1.380658 x 10^{-23}	12	J•K^{-1}	k(=R N_A)
Electron charge	1.602177 33 x 10^{-19}	49	C	-e
Electron specific charge	-1.758819 62 x 10^{11}	53	C•kg^{-1}	-e/m_e
Electron rest mass	9.1093897 x 10^{-31}	54	kg	m_e
Faraday constant	9.6485309 x 10^{4}	29	C•mol^{-1}	F
Gravity (Standard Acceleration)	9.80665 or 32.174	0	m/sec^2 ft/sec^2	g
Josephson frequency to voltage ratio	4.8359767 x 10^{14}	0	Hz•V^{-1}	2e/hg
Magnetic flux quantum	2.06783461 x 10^{-15}	61	Wb	φ_o
Molar gas constant	8.314510	70	J•mol^{-1}•K^{-1}	R
Natural logarithm base	≅ 2.71828	-	dimensionless	*e*
Newtonian gravitational constant	6.67259 x 10^{-11}	85	m^3•kg^{-1}•s^{-2}	G or K
Permeability of vacuum	4π x 10^{-7}	d	H/m	μ_o
Permittivity of vacuum	≅ 8.8541878 x 10^{-12}	d	F/m	ε_o
Pi	≅ 3.141592654		dimensionless	π
Planck constant	6.62659 x 10^{-34}	40	J•s	h
Planck constant/2π	1.05457266 x 10^{-34}	63	J•s	h(=h2π)
Quantum of circulation	3.63694807 x 10^{-4}	33	J•s•kg^{-1}	h/2m_e
Radius of earth (Equatorial)	6.378 x 10^{6} or 3963		m miles	
Rydberg constant	1.0973731534 x 10^{7}	13	m^{-1}	R_χ
Speed of light	2.9979246 x 10^{8}	1	m•s^{-1}	c
Speed of sound (dry air @ std press & temp)	331.4	-	m•s^{-1}	-
Standard volume of ideal gas	22.41410 x 10^{-3}	19	m^3•mol^{-1}	V_m
Stefan-Boltzmann constant	5.67051 x 10^{-8}	19	W•K^{-4} •m^{-2}	σ

* S is the one-standard-deviation uncertainty in the last units of the value, d is a defined value.
(A standard deviation is the square root of the mean of the sum of the squares of the possible deviations)

THE SPEED OF LIGHT

ACTUAL	UNITS	RULE OF THUMB	UNITS
≅ 2.9979246×10^8	m/sec	≅ 3×10^8	m/sec
≅ 299.79	m/μsec	≅ 300	m/μsec
≅ 3.27857×10^8	yd/sec	≅ 3.28×10^8	yd/sec
≅ 5.8275×10^8	NM/hr	≅ 5.8×10^8	NM/hr
≅ 1.61875×10^5	NM/sec	≅ 1.62×10^5	NM/sec
≅ 9.8357105×10^8	ft/sec	≅ 1×10^9	ft/sec
≅ 9.8357105×10^2	ft/μsec	≅ 1×10^3	ft/μsec

**SPEED OF LIGHT
IN VARIOUS MEDIUMS**

The speed of EM radiation through a substance such as cables is defined by the following formula:

$$V = c/(\mu_r\varepsilon_r)^{1/2}$$

Where: μ_r = relative permeability
ε_r = relative permittivity

The real component of ε_r = dielectric constant of medium.

EM propagation speed in a typical cable might be 65-90% of the speed of light in a vacuum.

APPROXIMATE SPEED OF SOUND (MACH 1)

Sea Level (CAS/TAS)		**36,000 ft*** (TAS)	(CAS)
1230 km/hr	Decreases	1062 km/hr	630 km/hr
765 mph	Linearly	660 mph	391 mph
665 kts	To ⇒	573 kts	340 kts

* The speed remains constant until 82,000 ft, when it increases linearly to 1215 km/hr (755 mph, 656 kts) at 154,000 ft. Also see Section 8-2 for discussion of Calibrated Air Speed (CAS) and True Airspeed (TAS) and a plot of the speed of sound vs. altitude.

**SPEED OF SOUND
IN VARIOUS MEDIUMS**

Substance	Speed (ft/sec)
Vacuum	Zero
Air	1,100
Fresh Water	4,700
Salt Water	4,900
Glass	14,800
Steel	20,000

DECIMAL / BINARY / HEX CONVERSION TABLE

Decimal	Binary	Hex	Decimal	Binary	Hex	Decimal	Binary	Hex
1	00001	01h	11	01011	0Bh	21	10101	15h
2	00010	02h	12	01100	0Ch	22	10110	16h
3	00011	03h	13	01101	0Dh	23	10111	17h
4	00100	04h	14	01110	0Eh	24	11000	18h
5	00101	05h	15	01111	0Fh	25	11001	19h
6	00110	06h	16	10000	10h	26	11010	1Ah
7	00111	07h	17	10001	11h	27	11011	1Bh
8	01000	08h	18	10010	12h	28	11100	1Ch
9	01001	09h	19	10011	13h	29	11101	1Dh
10	01010	0Ah	20	10100	14h	30	11110	1Eh

When using hex numbers it is always a good idea to use “h” as a suffix to avoid confusion with decimal numbers.

DECIMAL TO HEX CONVERSION

Both the following methods must use long division. Method one computes the digits from right to left while method two works from left to right.

Method one: To convert a decimal number above 16 to hex, divide the number by 16, then record the integer resultant and the remainder. Convert the remainder to hex and write this down - this will become the far right digit of the final hex number. Divide the integer you obtained by 16, and again record the new integer result and new remainder. Convert the remainder to hex and write it just to the left of the first decoded number. Keep repeating this process until dividing results in only a remainder. This will become the left-most character in the hex number (i.e., to convert 60 (decimal) to hex we have 60/16 = 3 with 12 remainder). 12 is C (hex) - this becomes the right most character. Then 3/16=0 with 3 remainder. 3 is 3 (hex). This becomes the next (and final) character to the left in the hex number, so the answer is 3C.

Method two: Use table of powers to work the digits from left to right:

For example: Here is your Decimal Number - 9379

Step 1 - Set up your chart:

65536	4096	256	16	1
16^4	16^3	16^2	16^1	16^0

Step 2 - Look in the table for the highest divisible number in the chart.
9379 / 4096 = 2 (the left-most Hex digit)
Must use long division to calculate the remainder (1187)

Step 3 - Divide the remainder with its highest divisible number in the chart:
1187 / 256 = 4 (the next digit to the right)
Must use long division to calculate the remainder (163)

Step 4 - Divide the remainder with its highest divisible number in the chart:
163 / 16 = 10 (or "A" from table L-1) (the next digit to the right)
Must use long division to calculate the remainder (3)

Step 5 - The remainder will not divide: remainder = 3 (the right-most Hex digit)

65536	4096	256	16	1
16^4	16^3	16^2	16^1	16^0
	2	4	A	3

HEX TO DECIMAL CONVERSION

To convert a hex number to decimal, multiply each hex digit converted to decimal by the decimal equivalent of the hex power represented and add the results.

For example: Here is your Hex Number - 24A3

Step 1 - Set up your chart:

4096	256	16	1
16^3	16^2	16^1	16^0

Step 2 - Place the numbers in a table:

4096	256	16	1
16^3	16^2	16^1	16^0
2	4	A	3

Step 3 - Multiply the Hex number times the power value:

2 x 4096 = 8192
4 x 256 = 1024
A(10) x 16 = 160
3 x 1 = 3

Step 4 - Add up your values:

Decimal value is 9379

GREEK ALPHABET

Case		Greek Alphabet Name	English Equivalent
Upper	Lower		
Α	α	alpha	a
Β	β	beta	b
Γ	γ	gamma	g
Δ	δ	delta	d
Ε	ε	epsilon	e
Ζ	ζ	zeta	z
Η	η	eta	e
Θ	θ , ‘	theta	th
Ι	ι	iota	i
Κ	κ	kappa	k
Λ	λ	lambda	l
Μ	μ	mu	m

Case		Greek Alphabet Name	English Equivalent
Upper	Lower		
Ν	ν	nu	n
Ξ	ξ	xi	x
Ο	ο	omicron	o
Π	π	pi	p
Ρ	ρ	rho	r
Σ	σ	sigma	s
Τ	τ	tau	t
Υ	υ	upsilon	u
Φ	φ	phi	ph
Χ	χ	chi	ch
Ψ	ψ	psi	ps
Ω	ω	omega	o

LETTERS FROM THE GREEK ALPHABET COMMONLY USED AS SYMBOLS

Symbol	Name	Use
α	alpha	space loss, angular acceleration, or absorptance
β	beta	3 dB bandwidth or angular field of view [radians]
Γ	Gamma	reflection coefficient
γ	gamma	electric conductivity, surface tension, missile velocity vector angle, or gamma ray
Δ	Delta	small change or difference
δ	delta	delay, control forces and moments applied to missile, or phase angle
ε	epsilon	emissivity [dielectric constant] or permittivity [farads/meter]
η	eta	efficiency or antenna aperture efficiency
Θ	Theta	angle of lead or lag between current and voltage
θ or ‘	theta	azimuth angle, bank angle, or angular displacement
Λ	Lambda	acoustic wavelength or rate of energy loss from a thermocouple
λ	lambda	wavelength or Poisson Load Factor
μ	mu	micro 10^{-6} [micron], permeability [henrys/meter], or extinction coefficient [optical region]

ν	nu	frequency
π	pi	3.141592654+
ρ	rho	charge/mass density, resistivity [ohm-meter], VSWR, or reflectance
Σ	Sigma	algebraic sum
σ	sigma	radar cross section [RCS], Conductivity [1/ohm-meter], or Stefan-Boltzmann constant
Τ	Tau	VSWR reflection coefficient
τ	tau	pulse width, atmospheric transmission, or torque
Φ	Phi	magnetic/electrical flux, radiant power [optical], or Wavelet's smooth function [low pass filter]
φ	phi	phase angle, angle of bank, or beam divergence [optical region]
Ψ	Psi	time-dependent wave function or Wavelet's detail function [high pass filter]
ψ	psi	time-independent wave function, phase change, or flux linkage [weber]
Ω	Omega	Ohms [resistance] or solid angle [optical region]. Note: inverted symbol is conductance [mhos]
ω	omega	carrier frequency in radians per second

MORSE CODE and PHONETIC ALPHABET

A - alpha	● –	J - juliett	● – –	S - sierra	● ● ●	1	● – – – –
B - bravo	– ● ● ●	K - kilo	– ● –	T - tango	–	2	● ● – – –
C - charlie	– ● – ●	L - lima	● – ● ●	U - uniform	● ● –	3	● ● ● – –
D - delta	– ● ●	M - mike	– –	V - victor	● ● ● –	4	● ● ● ● –
E - echo	●	N - november	– ●	W - whiskey	● – –	5	● ● ● ● ●
F - foxtrot	● ● – ●	O - oscar	– – –	X - x-ray	– ● ● –	6	– ● ● ● ●
G - golf	– – ●	P - papa	● – ●	Y - yankee	– ● – –	7	– – ● ● ●
H - hotel	● ● ● ●	Q - quebec	– – ● –	Z - zulu	– – ● ●	8	– – – ● ●
I - india	● ●	R - romeo	● – ●	0	– – – – –	9	– – – – ●

Note: The International Maritime Organization agreed to officially stop Morse code use by February 1999, however use may continue by ground based amateur radio operators. (The U.S. Coast Guard discontinued its use in 1995.)

BASIC MATH / GEOMETRY REVIEW

EXPONENTS

$a^x a^y = a^{x+y}$

$a^x / a^y = a^{x-y}$

$(a^x)^y = a^{xy}$

$a^0 = 1$

Example:

$$\frac{x}{\sqrt{x}} = x \bullet x^{-\frac{1}{2}} = x^{(1-\frac{1}{2})} = x^{\frac{1}{2}} = \sqrt{x}$$

LOGARITHMS

$\log (xy) = \log x + \log y$

$\log (x/y) = \log x - \log y$

$\log (x^N) = N \log x$

If $z = \log x$ then $x = 10^z$

Examples: $\log 1 = 0$
$\log 1.26 = 0.1$; $\log 10 = 1$

if $10 \log N = \text{dB\#}$,
then $10^{(\text{dB\#}/10)} = N$

TRIGONOMETRIC FUNCTIONS

$\sin x = \cos (x-90°)$

$\cos x = -\sin (x-90°)$

$\tan x = \sin x / \cos x = 1 / \cot x$

$\sin^2 x + \cos^2 x = 1$

A radian is the angular measurement of an arc which has an arc length equal to the radius of the given circle, therefore there are 2π radians in a circle. One radian = 360°/2π = 57.296....°

ELLIPSE



Area = π a b

Approx circumference

$= 2\pi\sqrt{\frac{a^2 + b^2}{2}}$

RECTANGLULAR SOLID



Area = lw

Volume = lwh

CYLINDER



Volume − $\pi r^2 h$

Lateral surface area = $2\pi rh$

ANGLES

$r^2 - x^2 + y^2$



Sin θ = y/r　Cos θ = x/r

Tan θ = y/x

SPHERE

Surface area = $4\pi r^2$

Volume = $4/3\ \pi r^3$

Cross Section (circle) Area = πr^2



TRIANGLES

Angles: A + B + C = 180°

$c^2 = a^2 + b^2 - 2ab \cos C$

Area = 1/2 hc = 1/2 ab sin C

$b = \sqrt{e^2 + h^2}$



DERIVATIVES

Assume: a = fixed real #; u, v & w are functions of x

d(a)/dx = 0 ; d(sin u)/dx = du(cos u)/dx

d(x)/dx = 1 ; d(cos v)/dx = -dv(sin v)/dx

d(uvw)/dx = uvdw/dx + vwdu/dx + uwdv/dx +...etc

INTEGRALS

Note: All integrals should have an arbitrary constant of integration added, which is left off for clarity

Assume: a = fixed real #; u, & v are functions of x

$\int a\,dx = ax$ and $\int a\,f(x)dx = a\int f(x)dx$

$\int (u + v)dx = \int u\,dx + \int v\,dx$; $\int e^x dx = e^x$

$\int(\sin ax)dx = -(\cos ax)/a$; $\int(\cos ax)dx = (\sin ax)/a$


Differentiating Circuit
C
+
-
Vin
Vout = - RC dv/dt
Square Wave Input Signal
Integrating Circuit
R
C
Vin
Vout = - 1/RC ∫v dt
+
-
Period of input smaller than RC
Period of input larger than RC
0
Increasing rep rate reduces amplitude of triangular wave.(DC offset unchanged)
0

MATHEMATICAL NOTATION

The radar and EW communities generally accept some commonly used notation for the various parameters used in radar and EW calculations. For instance, "P" is almost always power and "G" is almost always gain. Textbooks and reference handbooks will usually use this notation in formulae and equations.

A significant exception is the use of "α" for space loss. Most textbooks do not develop the radar equation to its most usable form as does this reference handbook, therefore the concept of "α" just isn't covered.

Subscripts are a different matter. Subscripts are often whatever seems to make sense in the context of the particular formula or equation. For instance, power may be "P", "P_T", "P_t", or maybe "P_1". In the following list, generally accepted notation is given in the left hand column with no subscripts. Subscripted notation in the indented columns is the notation used in this handbook and the notation often used in the EW community.

α = Space loss
α_1 = One way space loss, transmitter to receiver
α_2 = Two way space loss, xmtr to target (including radar cross section) and back to the rcvr
α_{1t} = One way space loss, radar transmitter to target, bistatic
α_{1r} = One way space loss, target to radar receiver, bistatic

Other notation such as α_{tm} may be used to clarify specific losses, in this case the space loss between a target and missile seeker, which could also be identified as α_{1r}.

A = Antenna aperture (capture area)
A_e = Effective antenna aperture
Å = Angstrom

B = Bandwidth (to 3dB points)
B_{IF} = 3 dB IF bandwidth of the receiver (pre-detection)
B_J = Bandwidth of the jamming spectrum
B_{MHz} = 3 dB bandwidth in MHz
B_N = Equivalent noise bandwidth, a.k.a. B
B_V = 3 dB video bandwidth of the receiver (post-detection) (Subscript V stands for video)
BF = Bandwidth reduction factor (jamming spectrum wider than the receiver bandwidth)
BW = Beamwidth (to 3 dB points)

c = Speed of Light

f = Frequency (radio frequency)
f_c = Footcandle (SI unit of illuminance)
f_D = Doppler frequency
f_R = Received frequency
f_T = Transmitted frequency

G = Gain
G_t = Gain of the transmitter antenna
G_r = Gain of the receiver antenna
G_{tr} = Gain of the transmitter/receiver antenna (monostatic radar)
G_J = Gain of the jammer
G_{JA} = Gain of the jammer antenna
G_{JT} = Gain of the jammer transmitter antenna
G_{JR} = Gain of the jammer receiver antenna
G_σ = Gain of reflected radar signal due to radar cross section

h = Height or Planks constant
h_{radar} = Height of radar
h_{target} = Height of target

J = Jamming signal (receiver input)
J_1 = Jamming signal (constant gain jammer)
J_2 = Jamming signal (constant power jammer)
J/S = Jamming to signal ratio (receiver input)

k = Boltzmann constant
$K_{1,2,3,4}$ = Proportionality constants, see Sections 4-3, 4-4, 4-5, and 4-1 respectively.

λ = Lambda, Wavelength or Poisson factor

L = Loss (due to transmission lines or circuit elements)

N = Receiver equivalent noise input (kT_oB)
NF = Noise figure

P = Power
P_d = Probability of detection
P_D = Power density
P_J = Power of a jammer transmitter
P_n = Probability of false alarm
P_r = Power received
P_t = Power of a transmitter

R = Range (straight line distance)
R_1 = Bistatic radar transmitter to target range
R_2 = Bistatic radar target to receiver range
R_J = Range of jammer to receiver (when separate from the target)
R_{NM} = Range in nautical miles

σ = Sigma, radar cross section (RCS)

S = Signal (receiver input)
S_R = Radar signal received by the jammer
S_{min} = Minimum receiver sensitivity

t = Time
t_{int} = Integration time
t_r = Pulse Rise Time
τ = Pulse Width

V = Velocity
V_r = Radial velocity

This page intentionally left blank.

FREQUENCY SPECTRUM

Figure 1, which follows, depicts the electromagnetic radiation spectrum and some of the commonly used or known areas. Figure 2 depicts the more common uses of the microwave spectrum. Figure 3 shows areas of the spectrum which are frequently referred to by band designations rather than by frequency.

Section 7-1 provides an additional breakdown of the EO/IR spectrum.

To convert from frequency (f) to wavelength (λ) and vice versa, recall that f = c/λ, or λ = c/f; where c = speed of light.

$$\lambda_{meter} = \frac{3x10^8}{f_{Hz}} = \frac{3x10^5}{f_{kHz}} = \frac{300}{f_{MHz}} = \frac{0.3}{f_{GHz}} \quad \text{or} \quad f_{Hz} = \frac{3x10^8}{\lambda_{meter}} \quad f_{kHz} = \frac{3x10^5}{\lambda_{meter}} \quad f_{MHz} = \frac{300}{\lambda_{meter}} \quad f_{GHz} = \frac{0.3}{\lambda_{meter}}$$

Some quick rules of thumb follow:

Metric:

Wavelength in cm = 30 / frequency in GHz
For example: at 10 GHz, the wavelength = 30/10 = 3 cm

English:

Wavelength in ft = 1 / frequency in GHz
For example: at 10 GHz, the wavelength = 1/10 = 0.1 ft


HERTZ
KILOHERTZ
MEGAHERTZ
GIGAHERTZ
TERAHERTZ
PENTAHERTZ
EXAHERTZ
1
10^1
10^2
10^3
10^4
10^5
10^6
10^7
10^8
10^9
10^{10}
10^{11}
10^{12}
10^{13}
10^{14}
10^{15}
10^{16}
10^{17}
10^{18}
10^{19}
10^{20}
10^{21}
10^{22}
10^{23}
ν FREQUENCY (HERTZ)
15
AUDIO
20K
AM
Mobile Radio Shortwave Radio
VHF TV
FM
UHF TV
MICROWAVES
INFRARED
Fiber Optic Comm
VISIBLE LIGHT
ULTRAVIOLET
X-RAYS
GAMMA RAYS
COSMIC RAYS
ULF
ELF
VLF
LF
MF
HF
VHF
UHF
SHF
EHF
EOF - Electro-Optical Freq
HEF - High Energy Freq
10^8
10^7
10^6
10^5
10^4
10^3
10^2
10
1
10^{-1}
10^{-2}
10^{-3}
10^{-4}
10^{-5}
10^{-6}
10^{-7}
10^{-8}
10^{-9}
10^{-10}
10^{-11}
10^{-12}
10^{-13}
10^{-14}
λ WAVELENGTH (METERS)
KILOMETER, km
METER, m
CENTIMETER, cm
MILLIMETER, mm
MICROMETER, μm
NANOMETER, nm
ANGSTROM, Å
PICOMETER
X-UNIT, XU

Figure 1. Electromagnetic Radiation Spectrum.


Military Search Radar
UHF Broadcast TV
Mobile Radio
ATC Transponder
Space Telemetry
Microwave Heating
Airport Search Radar
Microwave Relay
Satellite Down Communications
Satellite Up Communucations
STL Microwave Relay
Police Radar (C Band)
Airborne FC Radar
Microwave Relay
Satellite Down Communications
Police Radar (K Band)
Satellite Up Communucations
Missile Seeker
0.3
0.4
0.5
0.6
0.8
1.0
GHz
2
3
4
5
6
8
10
GHz
20
30
40
50
60
80
100
GHz
1 m
10 cm
1 cm

Figure 2. The Microwave Spectrum.


FREQUENCY (MHz)
20
30
100
200
300
500
FREQUENCY (GHz)
1.5
2
3
4
5
6
8
10
12
15
18
20
27
30
40
60
80
100
110
200
300
400
HF
VHF
UHF
L
S
C
X
K*u
K
K*a
V
W
Millimeter
Sub-MM
U.S. INDUSTRY STANDARD BANDS (IEEE Radar Designation)
7 (HF)
8 (VHF)
9 (UHF)
10 (SHF)
11 (EHF)
12
INTERNATIONAL STANDARD BANDS
250
A
B
C
D
E
F
G
H
I
J
K
L
M
MILITARY STANDARD BANDS
* "u" stands for unabsorbed or under K; "a" stands for absorption region or above K

Figure 3. Frequency Band Designations.

See Section 7, Figure 1 for a more detailed depiction of the UV and IR spectrum.

DECIBEL (dB)

The Decibel is a subunit of a larger unit called the bel. As originally used, the bel represented the power ratio of 10 to 1 between the strength or intensity i.e., power, of two sounds, and was named after Alexander Graham Bell. Thus a power ratio of 10:1 = 1 bel, 100:1 = 2 bels, and 1000:1 = 3 bels. It is readily seen that the concept of bels represents a logarithmic relationship since the logarithm of 100 to the base 10 is 2 (corresponding to 2 bels), the logarithm of 1000 to the base 10 is 3 (corresponding to 3 bels), etc. The exact relationship is given by the formula

$$\text{Bels} = \log(P_2/P_1) \qquad \textbf{[1]}$$

where P_2/P_1 represents the power ratio.

Since the bel is a rather large unit, its use may prove inconvenient. Usually a smaller unit, the Decibel or dB, is used. 10 decibels make one bel. A 10:1 power ratio, 1 bel, is 10 dB; a 100:1 ratio, 2 bels, is 20 dB. Thus the formula becomes

$$\text{Decibels (dB)} = 10 \log(P_2/P_1) \qquad \textbf{[2]}$$

The power ratio need not be greater than unity as shown in the previous examples. In equations [1] and [2], P_1 is usually the reference power. If P_2 is less than P_1, the ratio is less then 1.0 and the resultant bels or decibels are negative. For example, if P_2 is one-tenth P_1, we have

$$\text{bels} = \log(0.1/1) = -1.0 \text{ bels}$$

and $$\text{dB} = 10 \log(0.1/1) = -10 \text{ dB}.$$

It should be clearly understood that the term decibel does not in itself indicate power, but rather is a ratio or comparison between two power values. It is often desirable to express power levels in decibels by using a fixed power as a reference. The most common references in the world of electronics are the milliwatt (mW) and the watt. The abbreviation dBm indicates dB referenced to 1.0 milliwatt. One milliwatt is then zero dBm. Thus P_1 in equations [1] or [2] becomes 1.0 mW. Similarly, the abbreviation dBW indicates dB referenced to 1.0 watt, with P_2 being 1.0 watt, thus one watt in dBW is zero dBW or 30 dBm or 60 dBμW. For antenna gain, the reference is the linearly polarized isotropic radiator, dBLI. Usually the “L” and/or “I” is understood and left out.

dBc is the power of one signal referenced to a carrier signal, i.e., if a second harmonic signal at 10 GHz is 3 dB lower than a fundamental signal at 5 GHz, then the signal at 10 GHz is -3 dBc.

THE DECIBEL, ITS USE IN ELECTRONICS

The logarithmic characteristic of the dB makes it very convenient for expressing electrical power and power ratios. Consider an amplifier with an output of 100 watts when the input is 0.1 watts (100 milliwatts); it has an amplification factor of

$$P_2/P_1 = 100/0.1 = 1000$$

or a gain of:

$$10 \log(P_2/P_1) = 10 \log(100/0.1) = 30 \text{ dB}.$$

(notice the 3 in 30 dB corresponds to the number of zeros in the power ratio)

The ability of an antenna to intercept or transmit a signal is expressed in dB referenced to an isotropic antenna rather than as a ratio. Instead of saying an antenna has an effective gain ratio of 7.5, it has a gain of 8.8 dB (10 log 7.5).

A ratio of less than 1.0 is a loss, a negative gain, or attenuation. For instance, if 10 watts of power is fed into a cable but only 8.5 watts are measured at the output, the signal has been decreased by a factor of

$$8.5/10 = .85$$

or

$$10 \log(.85) = -0.7 \text{ dB.}$$

This piece of cable at the frequency of the measurement has a gain of -0.7 dB. This is generally referred to as a loss or attenuation of 0.7 dB, where the terms “loss” and “attenuation” imply the negative sign. An attenuator which reduces its input power by factor of 0.001 has an attenuation of 30 dB. The utility of the dB is very evident when speaking of signal loss due to radiation through the atmosphere. It is much easier to work with a loss of 137 dB rather than the equivalent factor of 2×10^{-14}.

Instead of multiplying gain or loss factors as ratios we can add them as positive or negative dB. Suppose we have a microwave system with a 10 watt transmitter, and a cable with 0.7 dB loss connected to a 13 dB gain transmit antenna. The signal loss through the atmosphere is 137 dB to a receive antenna with an 11 dB gain connected by a cable with 1.4 dB loss to a receiver. How much power is at the receiver? First, we must convert the 10 watts to milliwatts and then to dBm:

$$10 \text{ watts} = 10{,}000 \text{ milliwatts}$$

and

$$10 \log (10{,}000/1) = 40 \text{ dBm}$$

Then

$$40 \text{ dBm} - 0.7 \text{ dB} + 13 \text{ dB} - 137 \text{ dB} + 11 \text{ dB} - 1.4 \text{ dB} = -75.1 \text{ dBm.}$$

-75.1 dBm may be converted back to milliwatts by solving the formula:

$$\text{mW} = 10^{(\text{dBm}/10)}$$

giving:

$$10^{(-75.1/10)} = 0.00000003 \text{ mW}$$

Voltage and current ratios can also be expressed in terms of decibels, provided the resistance remains constant. First we substitute for P in terms of either voltage, V, or current, I. Since P=VI and V=IR we have:

$$P = I^2R = V^2/R$$

Thus for a voltage ratio we have:

$$\text{dB} = 10 \log[(V_2^2/R)/(V_1^2/R)] = 10 \log(V_2^2/V_1^2) = 10 \log(V_2/V_1)^2 = 20 \log(V_2/V_1)$$

Like power, voltage can be expressed relative to fixed units, so one volt is equal to 0 dBV or 120 dBμV.

Similarly for current ratio: $\text{dB} = 20 \log(I_2/I_1)$

Like power, amperage can be expressed relative to fixed units, so one amp is equal to 0 dBA or 120 dBμA.

Decibel Formulas (where Z is the general form of R, including inductance and capacitance)

When impedances are equal:

$$dB = 10\log\frac{P2}{P1} = 20\log\frac{E2}{E1} = 20\log\frac{I2}{I1}$$

When impedances are unequal:

$$dB = 10\log\frac{P2}{P1} = 20\log\frac{E2\sqrt{Z1}}{E1\sqrt{Z2}} = 20\log\frac{I2\sqrt{Z2}}{I1\sqrt{Z1}}$$

SOLUTIONS WITHOUT A CALCULATOR

Solution of radar and EW problems requires the determination of logarithms (base 10) to calculate some of the formulae. Common “four function” calculators do not usually have a log capability (or exponential or fourth root functions either). Without a scientific calculator (or math tables or a Log-Log slide rule) it is difficult to calculate any of the radar equations, simplified or “textbook.” The following gives some tips to calculate a close approximation without a calculator.

DECIBEL TABLE

DB	Power Ratio	Voltage or Current Ratio	DB	Power Ratio	Voltage or Current Ratio
0	1.00	1.00	10	10.0	3.16
0.5	1.12	1.06	15	31.6	5.62
1.0	1.26	1.12	20	100	10
1.5	1.41	1.19	25	316	17.78
2.0	1.58	1.26	30	1,000	31.6
3.0	2.00	1.41	40	10,000	100
4.0	2.51	1.58	50	10^5	316
5.0	3.16	1.78	60	10^6	1,000
6.0	3.98	2.00	70	10^7	3,162
7.0	5.01	2.24	80	10^8	10,000
8.0	6.31	2.51	90	10^9	31,620
9.0	7.94	2.82	100	10^{10}	10^5

For dB numbers which are a multiple of 10

An easy way to remember how to convert dB values that are a multiple of 10 to the absolute magnitude of the power ratio is to place a number of zeros equal to that multiple value to the right of the value 1.
40 dB = 10,000 : 1 (for power)

Minus dB moves the decimal point that many places to the left of 1.
-40 dB = 0.0001 : 1 (for power)

For voltage or current ratios, if the multiple of 10 is even, then divide the multiple by 2, and apply the above rules.
40 dB = 100 : 1 (for voltage)
-40 dB = 0.01 : 1

If the power in question is not a multiple of ten, then some estimation is required. The following tabulation lists some approximations. Some would be useful to memorize.

DB RULES OF THUMB

Multiply Current / Voltage By			Multiply Power By:	
if +dB	if -dB	**dB**	if +dB	if -dB
1	1	0	1	1
1.12	0.89	1	1.26	0.8
1.26	0.79	2	1.58	0.63
1.4	0.707	3	2	0.5
2.0	0.5	6	4	0.25
2.8	0.35	9	8	0.125
3.16	0.316	10	10	0.1
4.47	0.22	13	20	0.05
10	0.1	20	100	0.01
100	0.01	40	10,000	0.0001

You can see that the list has a repeating pattern, so by remembering just three basic values such as one, three, and 10 dB, the others can easily be obtained without a calculator by addition and subtraction of dB values and multiplication of corresponding ratios.

Example 1:

A 7 dB increase in power (3+3+1) dB is an increase of (2 x 2 x 1.26) = 5 times whereas
A 7 dB decrease in power (-3-3-1) dB is a decrease of (0.5 x 0.5 x 0.8) = 0.2.

Example 2: Assume you know that the ratio for 10 dB is 10, and that the ratio for 20 dB is 100 (doubling the dB increases the power ratio by a factor of ten), and that we want to find some intermediate value.



We can get more intermediate dB values by adding or subtracting one to the above, for example, to find the ratio at 12 dB we can:

work up from the bottom; 12 = 1+11 so we have 1.26 (from table) x 12.5 = 15.75
alternately, working down the top 12 = 13-1 so we have 20 x 0.8 (from table) = 16

The resultant numbers are not an exact match (as they should be) because the numbers in the table are rounded off. We can use the same practice to find any ratio at any other given value of dB (or the reverse).

dB AS ABSOLUTE UNITS

Power in absolute units can be expressed by using 1 Watt (or 1 milliwatt) as the reference power in the denominator of the equation for dB. We then call it dBW or dBm. We can then build a table such as the adjoining one.

From the above, any intermediate value can be found using the same dB rules and memorizing several dB values for determining the absolute power, given 48 dBm power output, we determine that 48 dBm = 50 dBm - 2 dB so we take the value at 50 dB which is 100W and divide by the value 1.58 (ratio of 2 dB) to get:

100 watts/1.58 = 63 W or 63,291 mW.

dB AS ABSOLUTE UNITS

dBµW	dBm	POWER	dBW
120	90	1 MW	60
90	60	1 kW	30
80	50	100 W	20
70	40	10 W	10
60	30	1 W (1000 mW)	0
50	20	100 mW	-10
40	10	10 mW	-20
33	3	2 mW	-27
32	2	1.58 mW	-28
31	1	1.26 mw	-29
30	0	1 mW	-30

Because dBW is referenced to one watt, the Log of the power in watts times 10 is dBW. The Logarithm of 10 raised by any exponent is simply that exponent. That is: $\text{Log}(10)^4 = 4$. Therefore, a power that can be expressed as any exponent of 10 can also be expressed in dBW as that exponent times 10. For example, 100 kW can be written 100,000 watts or 10^5 watts. 100 kW is then +50 dBW. Another way to remember this conversion is that dBW is the number of zeros in the power written in watts times 10. If the transmitter power in question is conveniently a multiple of ten (it often is) the conversion to dBW is easy and accurate.

This page intentionally left blank.

DUTY CYCLE

Duty cycle (or duty factor) is a measure of the fraction of the time a radar is transmitting. It is important because it relates to peak and average power in the determination of total energy output. This, in turn, ultimately affects the strength of the reflected signal as well as the required power supply capacity and cooling requirements of the transmitter.

Although there are exceptions, most radio frequency (RF) measurements are either continuous wave (CW) or pulsed RF. CW RF is uninterrupted RF such as from an oscillator. Amplitude modulated (AM), frequency modulated (FM), and phase modulated (PM) RF are considered CW since the RF is continuously present. The power may vary with time due to modulation, but RF is always present. Pulsed RF, on the other hand, is bursts (pulses) of RF with no RF present between bursts. The most general case of pulsed RF consists of pulses of a fixed pulse width (PW) which come at a fixed time interval, or period, (T). For clarity and ease of this discussion, it is assumed that all RF pulses in a pulse train have the same amplitude. Pulses at a fixed interval of time arrive at a rate or frequency referred to as the pulse repetition frequency (PRF) of so many pulse per second. Pulse repetition interval (PRI) and PRF are reciprocals of each other.

$$PRF = 1/T = 1/PRI \qquad \textbf{[1]}$$

Power measurements are classified as either peak pulse power, P_p, or average power, P_{ave}. The actual power in pulsed RF occurs during the pulses, but most power measurement methods measure the heating effects of the RF energy to obtain an average value of the power. It is correct to use either value for reference so long as one or the other is consistently used. Frequently it is necessary to convert from P_p to P_{ave}, or vice versa; therefore the relationship between the two must be understood. Figure 1 shows the comparison between P_p and P_{ave}.



Figure 1. RF Pulse Train.

The average value is defined as that level where the pulse area above the average is equal to area below average between pulses. If the pulses are evened off in such a way as to fill in the area between pulses, the level obtained is the average value, as shown in Figure 1 where the shaded area of the pulse is used to fill in the area between pulses. The area of the pulse is the pulse width multiplied by the peak pulse power. The average area is equal to the average value of power multiplied by the pulse period.

Since the two values are equal:

$$P_{ave} \text{ x } T = P_p \text{ x } PW \qquad \textbf{[2]}$$

or

$$P_{ave}/P_p = PW/T \qquad \textbf{[3]}$$

Using [1]

$$P_{ave}/P_p = PW/T = PW \text{ x } PRF = PW/PRI = \text{duty cycle} \qquad \textbf{[4]}$$

(note that the symbol τ represents pulse width (PW) in most reference books)

The ratio of the average power to the peak pulse power is the duty cycle and represents the percentage of time the power is present. In the case of a square wave the duty cycle is 0.5 (50%) since the pulses are present 1/2 the time, the definition of a square wave.

For Figure 1, the pulse width is 1 unit of time and the period is 10 units. In this case the duty cycle is:

PW/T = 1/10 = 0.1 (10%).

A more typical case would be a PRF of 1,000 and a pulse width of 1.0 microseconds. Using [4], the duty cycle is 0.000001 x 1,000 = 0.001. The RF power is present one-thousandth of the time and the average power is 0.001 times the peak power. Conversely, if the power were measured with a power meter which responds to average power, the peak power would be 1,000 time the average reading.

Besides expressing duty cycle as a ratio as obtained in equation [4], it is commonly expressed as either a percentage or in decibels (dB). To express the duty cycle of equation [4] as a percentage, multiply the value obtained by 100 and add the percent symbol. Thus a duty cycle of 0.001 is also 0.1%.

The duty cycle can be expressed logarithmically (dB) so it can be added to or subtracted from power measured in dBm/dBW rather than converting to, and using absolute units.

$$\text{Duty cycle (dB)} = 10 \log(\text{duty cycle ratio}) \qquad \textbf{[5]}$$

For the example of the 0.001 duty cycle, this would be 10 log(0.001) = -30 dB. Thus the average power would be 30 dB less than the peak power. Conversely, the peak power is 30 dB higher than the average power.

For pulse radars operating in the PRF range of 0.25-10 kHz and PD radars operating in the PRF range of 10-500 kHz, typical duty cycles would be:

Pulse	~	0.1 - 3%	=	0.001 - .03	=	-30 to -15 dB
Pulse Doppler	~	5 - 50%	=	0.05 - .5	=	-13 to -3 dB
Continuous Wave	~	100%	=	1	=	0 dB

Intermediate Frequency Bandwidths of typical signals are:

Pulse	1 to 10 MHz
Chirp or Phase coded pulse	0.1 to 10 MHz
CW or PD	0.1 to 5 kHz

PRF is usually subdivided into the following categories: Low 0.25-4 kHz; Medium 8-40 kHz; High 50-300 kHz.

DOPPLER SHIFT

Doppler is the apparent change in wavelength (or frequency) of an electromagnetic or acoustic wave when there is relative movement between the transmitter (or frequency source) and the receiver.

Summary RF Equation for the Two-Way (radar) case

$$f_{Rec} = f_{Xmt} + f_D = f_{Xmt} + \frac{2(V_{Xmtr} + V_{Tgt})\, f_{Xmt}}{c}$$

Summary RF Equation for the One-Way (ESM) case

$$f_{Rec} = f_{Xmt} + f_D = f_{Xmt} + \frac{V_{Xmtr\ or\ Rec}\ f_{Xmt}}{c}$$

Rules of Thumb for two-way signal travel
(divide in half for one-way ESM signal measurements)
At 10 GHz, $f_D \cong$
35 Hz per Knot
19 Hz per km/Hr
67 Hz per m/sec
61 Hz per yd/sec
20 Hz per ft/sec

To estimate f_D at other frequencies, multiply these by:

$$\left[\frac{f_{Xmt}(GHz)}{10}\right]$$

The Doppler effect is shown in Figure 1. In everyday life this effect is commonly noticeable when a whistling train or police siren passes you. Audio Doppler is depicted, however Doppler can also affect the frequency of a radar carrier wave, the PRF of a pulse radar signal, or even light waves causing a shift of color to the observer.



Figure 1. Doppler Frequency Creation From Aircraft Engine Noise.

How do we know the universe is expanding?

Answer: The color of light from distant stars is shifted to red (see Section 7-1: higher λ or lower frequency means Doppler shift is stretched, i.e., expanding).

A memory aid might be that the lights from a car (going away) at night are red (tail lights)!

Doppler frequency shift is directly proportional to velocity and a radar system can therefore be calibrated to measure velocity instead of (or along with) range. This is done by measuring the shift in frequency of a wave caused by an object in motion (Figure 2).

- * Transmitter in motion
- * Reflector in motion
- * Receiver in motion
- * All three

For a closing relative velocity:

- * Wave is compressed
- * Frequency is increased

For an opening relative velocity:

- * Wave is stretched
- * Frequency is decreased


TRANSMITTER MOVING
SURFACE ESM/RWR MEASURES DOPPLER
(One-way Doppler Change)
TRANSMITTER
RECEIVER
RECEIVER MOVING
AIRBORNE ESM/RWR MEASURES DOPPLER
(One-way Doppler Change)
RECEIVER
TRANSMITTER
REFLECTOR MOVING
SURFACE RADAR MEASURES DOPPLER
(Two-way Doppler Change)
REFLECTOR
TRANSMITTER &
RECEIVER
ALL THREE MOVING
AIRBORNE RADAR MEASURES DOPPLER
(Two-way Doppler Change)
TRANSMITTER &
RECEIVER
REFLECTOR

Figure 2. Methods of Doppler Creation.

To compute Doppler frequency we note that velocity is range rate; V = dr/dt

For the reflector in motion case, you can see the wave compression effect in Figure 3 when the transmitted wave peaks are one wavelength apart. When the first peak reaches the target, they are still one wavelength apart (point a).

When the 2nd peak reaches the target, the target has advanced according to its velocity (vt) (point b), and the first reflected peak has traveled toward the radar by an amount that is less than the original wavelength by the same amount (vt) (point c).

As the 2nd peak is reflected, the wavelength of the reflected wave is 2(vt) less than the original wavelength (point d).


λ
λ
(a)
vτ
vτ
(b)
(c)
λ-2vτ
(d)
Tx PHASE
STATIONARY
TARGET
Φ
Rx PHASE
Φ CONSTANT
Tx PHASE
CLOSING
TARGET
Φ
Rx PHASE
Φ VARIABLE

Figure 3. Doppler Compression Equivalent to Variable Phase Shift.

The distance the wave travels is twice the target range. The reflected phase lags transmitted phase by 2x the round trip time. For a fixed target the received phase will differ from the transmitted phase by a constant phase shift. For a moving target the received phase will differ by a changing phase shift.

For the closing target shown in Figure 3, the received phase is advancing with respect to the transmitted phase and appears as a higher frequency.

Doppler is dependent upon closing velocity, not actual radar or target velocity as shown in Figure 4.

For the following equations (except radar mapping), we assume the radar and target are moving directly toward one another to simplify calculations (if this is not the case, use the velocity component of one in the direction of the other in the formulas).


RADAR VELOCITY
A
CLOSING VELOCITY
CLOSING VELOCITY =
RADAR VELOCITY COS(A) + TARGET VELOCITY COS (B)
B
NOTE: If altitude is different, then additional angular components will have to be considered
TARGET VELOCITY

Figure 4. Doppler Depends Upon Closing Velocity.

For the case of a moving reflector, doppler frequency is proportional to 2x the transmitted frequency:
Higher rf = higher doppler shift
$f_D = (2 \text{ x } V_{Target})(f/c)$

Likewise, it can be shown that for other cases, the following relationships hold:

For an airplane radar with an airplane target (The “all three moving” case, aircraft radar transmitter, target, and aircraft radar receiver)
$f_D = 2(V_{Radar} + V_{Target})(f/c)$

Speed of Light
Conversions

* * *

$c \cong 2.9979 \text{ x } 10^8$ m/sec
$c \cong 5.8275 \text{ x } 10^8$ nm/hr (knots)
$c \cong 9.8357 \text{ x } 10^8$ ft/sec

For the case of a semi-active missile receiving signals (Also “all three moving”)
$f_D = (V_{Radar} + 2V_{Target} + V_{Missile})(f/c)$

For the airplane radar with a ground target (radar mapping) or vice versa.
$f_D = 2(V_{Radar} \cos\theta \cos\varphi)(f/c)$, Where θ and φ are the radar scan azimuth and depression angles.

For a ground based radar with airborne target - same as previous using target track crossing angle and ground radar elevation angle.

For the ES/ESM/RWR case where only the target or receiver is moving (One-way Doppler measurements)
$f_D = V_{Receiver\ or\ Target}\ (f/c)$

Note: See Figure 4 if radar and target are not moving directly towards or away from one another.

Figure 5 depicts the results of a plot of the above equation for a moving reflector such as might be measured with a ground radar station illuminating a moving aircraft.

It can be used for the aircraft-to-aircraft case, if the total net closing rate of the two aircraft is used for the speed entry in the figure.

It can also be used for the ES/ESM case (one-way doppler measurements) if the speed of the aircraft is used and the results are divided by two.



Figure 5. Two-Way Doppler Frequency Shift.

SAMPLE PROBLEMS:

(1) If a ground radar operating at 10 GHz is tracking an airplane flying at a speed of 500 km/hr tangential to it (crossing pattern) at a distance of 10 km, what is the Doppler shift of the returning signal?

Answer: Since the closing velocity is zero, the Doppler is also zero.

(2) If the same aircraft turns directly toward the ground radar, what is the Doppler shift of the returning signal?

Answer: 500 km/hr = 270 kts from Section 2-1. From Figure 4 we see that the Doppler frequency is about 9.2 KHz.

(3) Given that a ground radar operating at 7 GHz is Doppler tracking an aircraft 20 km away (slant range) which is flying directly toward it at an altitude of 20,000 ft and a speed of 800 ft/sec, what amount of VGPO switch would be required of the aircraft jammer to deceive (pull) the radar to a zero Doppler return?

Answer: We use the second equation from the bottom of page 2-6.3 which is essentially the same for this application except a ground radar is tracking an airplane target (vs. an airplane during ground mapping), so for our application we use a positive elevation angle instead of a negative (depression) angle.

$f_D = 2(V_r \text{ Cos } \theta \text{ Cos } \varphi)(f/c)$, where θ is the aircraft track crossing angle and φ is the radar elevation angle.

Since the aircraft is flying directly at the radar, θ = 0°; the aircraft altitude = 20,000 ft = 6,096 meters.

Using the angle equation in Section 2-1, sin φ = x/r = altitude / slant range, so:
$\varphi = \sin^{-1}$ (altitude/slant range) = $\sin^{-1}$ (6,096 m / 20,000 m) = 17.7°

F_D = 2(800 ft/sec Cos 0° Cos 17.7°)(7x10^9 Hz / 9.8357 x 10^9 ft/sec) = 10,845 Hz

This page intentionally left blank.

ELECTRONIC FORMULAS

Ohm's Law Formulas for D-C Circuits. $E = IR = \frac{P}{I} = \sqrt{PR}$ $P = I^2 R = EI = \frac{E^2}{R}$

Ohm's Law Formulas for A-C Circuits and Power Factor.

$$E = IZ = \frac{P}{I \cos \Theta} = \sqrt{\frac{P\,Z}{\cos \Theta}} \qquad P = I^2\, Z \cos \Theta = IE \cos \Theta = \frac{E^2 \cos \Theta}{Z}$$

In the above formulas Θ is the angle of lead or lag between current and voltage and cos Θ = P/EI = power factor or *pf*.

$$pf = \frac{Active\ \ power\ (in\ watts)}{Apparent\ \ power\ (in\ volt\text{-}amps)} = PoverE\ I \qquad pf = \frac{R}{Z}$$

Note: Active power is the "resistive" power and equals the equivalent heating effect on water.

Voltage/Current Phase Rule of Thumb Remember "ELI the ICE man"

ELI: Voltage (E) comes before (leads) current (I) in an inductor (L)
ICE: Current (I) comes before (leads) Voltage (E) in a capacitor (C)

Resistors in Series $R_{total} = R_1 + R_2 = R_3 + \ldots$

Two Resistors in Parallel $R_t = \frac{R_1\, R_2}{R_1 + R_2}$

Resistors in Parallel, General Formula

$$R_{total} = \frac{1}{\frac{1}{R_1} + \frac{1}{R_2} + \frac{1}{R_3} + \ldots}$$

Resonant Frequency Formulas *Where in the second formula f is in kHz and L and C are in microunits.

$$f = \frac{1}{2\pi\sqrt{LC}}\ ,\ \ or\ \ \ f = \frac{159.2^*}{\sqrt{LC}} \quad L = \frac{1}{4\pi^2 f^2 C}\ ,\ \ or\ \ \ L = \frac{25{,}330^*}{f^2 C} \quad C = \frac{1}{4\pi^2 f^2 L}\ ,\ \ or\ \ \ C = \frac{25{,}330^*}{f^2 L}$$

Conductance $G = \frac{1}{R}$ $(for\ D\text{-}C\ circuit)$ $G = \frac{R}{R^2 + X^2}$ $(for\ A\text{-}C\ circuit)$

Reactance Formulas $X_C = \frac{1}{2\pi\, f\, C}$ $C = \frac{1}{2\pi\, f\ X_C}$ $X_L = 2\pi\, fL$ $L = \frac{X_L}{2\pi\, f}$

Impedance Formulas $Z = \sqrt{R^2 + (X_L - X_C)^2}$ $(for\ series\ circuit)$

$$Z = \frac{RX}{\sqrt{R^2 + X^2}} \quad (for\ R\ and\ X\ in\ parallel)$$

Q or Figure of Merit $Q = \frac{X_L}{R}\ \ or\ \ \frac{X_C}{R}$

Frequency Response

	Inductor *	Capacitor *	Resister
DC	Pass	Block	Attenuate
Low Freq AC	Attenuate *	Attenuate *	Attenuate
High Freq	Block	Pass	Attenuate

* Attenuation varies as a function of the value of the each device and the frequency

"Cartoon" memory aid



Sinusoidal Voltages and Currents



Effective value = 0.707 x peak value
[Also known as Root-Mean Square (RMS) value]

Half Cycle Average value = 0.637 x peak

Peak value = 1.414 x effective value

∴ Effective value = 1.11 x average value

Three-phase AC Configurations



(120° phase difference between each voltage)

If the connection to a three phase AC configuration is miswired, switching any two of the phases will put it back in the proper sequence.

Electric power for ships commonly uses the delta configuration, while commercial electronic and aircraft applications commonly use the wye configuration.

Color Code for House Wiring:	**PURPOSE:**	**Color Code for Chassis Wiring:**
Black or red	HOT	Red
White	NEUTRAL (Return)	White
Green or bare	GROUND	Black

Color Code for Resistors: **First and second band**:
(and third band # of zeros if not gold/silver)

				Third band **Multiplier**		**Fourth band** **Tolerance**	
0	Black	5	Green	.1	Gold	5%	Gold
1	Brown	6	Blue	.01	Silver	10%	Silver
2	Red	7	Violet			20%	No color
3	Orange	8	Gray				
4	Yellow	9	White				

The third color band indicates number of zeros to be added after figures given by first two color bands. But if third color band is gold, multiply by 0.1 and if silver multiply by 0.01. Do not confuse with fourth color-band that indicates tolerance. Thus, a resistor marked blue-red-gold-gold has a resistance of 6.2 ohms and a 5% tolerance.

MISSILE AND ELECTRONIC EQUIPMENT DESIGNATIONS

Missiles are designated with three letters from the columns below plus a number (i.e., AIM-7M) Suffixes (M in this case) indicate a modification.

First Letter Launch Environment	**Second Letter** Mission Symbols	**Third Letter** Vehicle Type
A Air	D Decoy	M Guided Missile
B Multiple	E Special electronic	N Probe (non-orbital instruments)
C Coffin	G Surface attack	R Rocket (without installed or remote control guidance)
H Silo stored	I Intercept, aerial	
L Silo launched	Q Drone	
M Mobile	T Training	
P Soft Pad	U Underwater attack	
R Ship	W Weather	
U Underwater		

U.S. military electronic equipment is assigned an identifying alphanumeric designation that is used to uniquely identify it. This system is commonly called the “AN” designation system, although its formal name is the Joint Electronics Type Designation System (JETDS). The letters AN preceding the equipment indicators formerly meant “Army/Navy,” but now are a letter set that can only be used to indicate formally designated DOD equipment. The first three letters following the “AN/” indicate Platform Installation, Equipment Type, and Equipment Function, respectively. The appropriate meaning is selected from the lists below. The letters following the AN designation numbers provide added information about equipment. Suffixes (A, B, C, etc.) indicate a modification. The letter (V) indicates that variable configurations are available. The letter (X) indicates a development status. A parenthesis ( ) without a number within it indicates a generic system that has not yet received a formal designation, e.g., AN/ALQ( ). Quite often the () is pronounced “bow legs” since they look like the shape of cowboy legs.

First Letter Platform Installation	**Second Letter** Equipment Type	**Third Letter** Function or Purpose
A Piloted aircraft	A Invisible light, heat radiation	B Bombing
B Underwater mobile, submarine	C Carrier	C Communications
D Pilotless carrier	D Radiac	D Direction finder, reconnaissance and/or surveillance
F Fixed ground	F Photographic	E Ejection and/or release
G General ground use	G Telegraph or teletype	G Fire control or searchlight directing
K Amphibious	I Interphone and public address	H Recording and/or reproducing
M Mobile (ground)	J Electromechanical or inertial wire covered	K Computing
P Portable	K Telemetering	M Maintenance and/or test assemblies
S Water	L Countermeasures	N Navigation aids
T Ground, transportable	M Meteorological	Q Special or combination of purposes
U General utility	N Sound in air	R Receiving, passive detecting
V Vehicular (ground)	P Radar	S Detecting and/or range and bearing, search
W Water surface and underwater combination	Q Sonar and underwater sound	T Transmitting
Z Piloted-pilotless airborne vehicle combination	R Radio	W Automatic flight or remote control
	S Special or combinations of types	X Identification and recognition
	T Telephone (wire)	Y Surveillance and control
	V Visual and visible light	
	W Armament	
	X Facsimile or television	
	Y Data Processing	

This page intentionally left blank.

RADAR HORIZON / LINE OF SIGHT

There are limits to the reach of radar signals. At the frequencies normally used for radar, radio waves usually travel in a straight line. The waves may be obstructed by weather or shadowing, and interference may come from other aircraft or from reflections from ground objects (Figure 1).



Figure 1. Radar Horizon and Shadowing.

As also shown in Figure 1, an aircraft may not be detected because it is below the radar line which is tangent to the earth's surface.

Some rules of thumb are:

Range (to horizon):

$$R_{NM} = 1.23\sqrt{h_{radar}} \quad \text{with } h \text{ in ft}$$

Range (beyond horizon / over earth curvature):

$$R_{NM} = 1.23\left(\sqrt{h_{radar}} + \sqrt{h_{target}}\right) \quad \text{with } h \text{ in ft}$$

In obtaining the radar horizon equations, it is common practice to assume a value for the Earth's radius that is 4/3 times the actual radius. This is done to account for the effect of the atmosphere on radar propagation. For a true line of sight, such as used for optical search and rescue, the constant in the equations changes from 1.23 to 1.06.

A nomograph for determining maximum target range is depicted in Figure 2. Although an aircraft is shown to the left, it could just as well be a ship, with radars on a mast of height "h." Any target of height (or altitude) "H" is depicted on the right side.



Figure 2. Earth Curvature Nomograph.

See also Section 5-1 on ducting and refraction, which may increase range beyond these distances.

This data was expanded in Figure 3 to consider the maximum range one aircraft can detect another aircraft using:

$$R_{NM} = 1.23\left(\sqrt{h_{radar}} + \sqrt{h_{target}}\right)$$

(with h in feet)

It can be used for surface targets if $H_{target} = 0$. It should be noted that most aircraft radars are limited in power output, and would not detect small or surface objects at the listed ranges.



Figure 3. Aircraft Radar vs. Aircraft Target Maximum Range.

Figure 4 depicts the maximum range that a ship height antenna can detect a zero height object (i.e., rowboat).



Figure 4. Ships Radar Horizon With Target on the Surface.

In this case "H" = 0, and the general equation becomes: $R_{\max}\,(NM) = 1.23\sqrt{h_r}$

Where h_r is the height of the radar in feet.

Figure 5 depicts the same for aircraft radars. It should be noted that most aircraft radars are limited in power output, and would not detect small or surface objects at the listed ranges.



Figure 5. Aircraft Radar Horizon With Target on the Surface.

Other general rules of thumb for surface "targets/radars" are as follows:

For Visual SAR:

$$R_{Visual}(NM) = 1.05\sqrt{Acft\ \ Alt\ \ in\ \ ft}$$

For ESM:

$$R_{ESM}(NM) = 1.5\sqrt{Acft\ \ Alt\ \ in\ \ ft}$$

This page intentionally left blank.

PROPAGATION TIME / RESOLUTION

1. ROUND TRIP RANGE: $R = \frac{c\,t}{2}$ with t = time to reach target

Rules of Thumb

In one µsec round trip time, a wave travels to and from an object at a distance of:	The time it takes to travel to and from an object at a distance of:
≅ 150 m	1 m ≅ 0.0067 µsec
≅ 164 yd	1 yd ≅0.006 µsec
≅ 500 ft	1 ft ≅ 0.002 µsec
≅ 0.08 NM	1 NM ≅ 12.35 µsec
≅ 0.15 km	1 km ≅ 6.7 µsec

2. ONE WAY RANGE: $R = ct$ with t = time to reach target

Time	Distance Traveled
1 milli sec (ms)	165 NM
1 micro sec (µs)	1000 ft
1 nano sec (ns)	1 ft

Distance	Time it Takes
1 NM	6.18 µsec
1 km	3.3 µsec
1 ft	1 nsec

3. UNAMBIGUOUS RANGE

(DISTANCE BETWEEN PULSES): $R = \frac{c \bullet PRI}{2}$

Normally a radar measures "distance" to the target by measuring time from the last transmitted pulse. If the inter-pulse period (T) is long enough that isn't a problem as shown in "A" to the right. When the period is shortened, the time to the last previous pulse is shorter than the actual time it took, giving a false (ambiguous) shorter range (figure "B").



Rules of Thumb

RNM ≅ 81Pms

RKm ≅ 150Pms

Where Pms is PRI in milliseconds

4. RANGE RESOLUTION

Rules of Thumb

500 ft per microsecond of pulse width

500 MHz IF bandwidth provides 1 ft of resolution.

5. BEST CASE PERFORMANCE:

The atmosphere limits the accuracy to 0.1 ft

The natural limit for resolution is one RF cycle.

This page intentionally left blank.

MODULATION

Modulation is the process whereby some characteristic of one wave is varied in accordance with some characteristic of another wave. The basic types of modulation are angular modulation (including the special cases of phase and frequency modulation) and amplitude modulation. In missile radars, it is common practice to amplitude modulate the transmitted RF carrier wave of tracking and guidance transmitters by using a pulsed wave for modulating, and to frequency modulate the transmitted RF carrier wave of illuminator transmitters by using a sine wave.

Frequency Modulation (FM) - As shown in Figure 1, an unmodulated RF signal in the time domain has only a single spectral line at the carrier frequency (f_c) in the frequency domain. If the signal is frequency modulated, as shown in Figure 2 (simplified using only two changes), the spectral line will correspondingly shift in the frequency domain. The bandwidth can be approximated using Carson's rule: $BW = 2(\Delta f + fm)$, where Δf is the peak deviation of the instantaneous frequency from the carrier and fm is the highest frequency present in the modulating signal. There are usually many more "spikes" in the frequency domain than depicted. The number of spikes and shape of the frequency domain envelope (amplitude) are based on the modulation index β. The modulation index is related to the same two factors used in Carson's rule. A high Δf means a higher modulation index with many more "spikes" spread across a wider bandwidth.


TIME DOMAIN PLOT
FREQUENCY DOMAIN
RF Carrier (e.g. 10 GHz)
Amplitude
Time
Amplitude
Carrier
at 10 GHz
Frequency

Figure 1. Unmodulated RF Signal.


TIME DOMAIN PLOT
RF Carrier = 10 GHz
e.g. 10 GHz
e.g. 10.5 GHz
e.g. 9.5 GHz
Amplitude
Time
t1
t2
t3
t4
FREQUENCY DOMAIN
Amplitude
9.5
Occurs from t3 to t4
10
Occurs from t1 to t2
10.5
Occurs from t2 to t3
Freq GHz

Figure 2. RF Signal With Frequency Modulation.

Amplitude Modulation (AM) - If the signal in Figure 1 is amplitude modulated by a sinewave as shown in Figure 3, sidebands are produced in the frequency domain at $F_c \pm F_{AM}$. AM other than by a pure sine wave will cause additional sidebands normally at $F_c \pm nF_{AM}$, where n equals 1, 2, 3, 4, etc.


TIME DOMAIN PLOT
RF Carrier (Fc), e.g. 10 GHz
Amplitude
Time
Amplitude Modulation Envelope
Detected Signal (FAM), e.g. 100 Hz
FREQUENCY DOMAIN
Amplitude
Fc
10 GHz
Frequency
GHz
Lower Sideband
9,999,999,900 Hz
Upper Sideband
10,000,000,100 Hz

Figure 3. Sinewave Modulated RF Signal.

Pulse modulation is a special case of AM wherein the carrier frequency is gated at a pulsed rate. When the reciprocal of the duty cycle of the AM is a whole number, harmonics corresponding to multiples of that whole number will be missing, e.g., in a 33.33% duty cycle, AM wave will miss the 3rd, 6th, 9th, etc. harmonics, while a square wave or


TIME DOMAIN PLOT
Square Wave AM Envelope
Amplitude
RF Carrier
Time
Detected Signal
FREQUENCY DOMAIN
Lower Sidebands
Upper Sidebands
Amplitude
Carrier
at 10 GHz
Frequency
Carrier Amplitude Modulated by a Square Wave

Figure 4. Square Wave Modulated RF Signal (50% Duty Cycle).

50% duty cycle triangular wave will miss the 2nd, 4th, 6th, etc. harmonic, as shown in Figure 4. It has sidebands in the frequency domain at $F_c \pm nF_{AM}$, where n = 1, 3, 5, etc. The amplitude of the power level follows a sine x / x type distribution.

Figure 5 shows the pulse width (PW) in the time domain which defines the lobe width in the frequency domain (Figure 6). The width of the main lobe is 2/PW, whereas the width of a side lobe is 1/PW. Figure 5 also shows the pulse repetition interval (PRI) or its reciprocal, pulse repetition frequency (PRF), in the time domain. In the frequency domain, the spectral lines inside the lobes are separated by the PRF or 1/PRI, as shown in Figures 7 and 8. Note that Figures 7 and 8 show actual magnitude of the side lobes, whereas in Figure 4 and 6, the absolute value is shown.

The magnitude of each spectral component for a rectangular pulse can be determined from the following formula:

$$a_n = 2A\frac{\tau}{T}\,\frac{\sin(n\pi\tau/T)}{n\pi\tau/T} \quad where: \begin{matrix} \tau = pulse\ width\ (PW) \\ T = period\ (PRI) \end{matrix} \quad and\ \ A = Amplitude\ of\ rectangular\ pulse \qquad [1]$$



Figure 5. Pulse Width and PRI/PRF Waveforms.



Figure 6. Sidelobes Generated by Pulse Modulation (Absolute Value).

Figure 7 shows the spectral lines for a square wave 50% duty cycle), while Figure 8 shows the spectral lines for a 33.33% duty cycle rectangular wave signal.



Figure 7. Spectral Times for a Square Wave Modulated Signal.



Figure 8. Spectral Lines for a 33.3% Duty Cycle.

Figure 9 shows that for square wave AM, a significant portion of the component modulation is contained in the first few harmonics which comprise the wave. There are twice as many sidebands or spectral lines as there are harmonics (one on the plus and one on the minus side of the carrier). Each sideband represents a sine wave at a frequency equal to the difference between the spectral line and f_c.



Figure 9. Square Wave Consisting of Sinewave Harmonics.

A figure similar to Figure 9 can be created for any rectangular wave. The relative amplitude of the time domain sine wave components are computed using equation [1]. Each is constructed such that at the midpoint of the pulse the sine wave passes through a maximum (or minimum if the coefficient is negative) at the same time. It should be noted that the "first" harmonic created using this formula is NOT the carrier frequency, f_c, of the modulated signal, but at $F_c \pm F_{AM}$.

While equation [1] is for rectangular waves only, similar equations can be constructed using Fourier coefficients for other waveforms, such as triangular, sawtooth, half sine, trapezoidal, and other repetitive geometric shapes.

PRI Effects - If the PW remains constant but PRI increases, the number of sidelobes remains the same, but the number of spectral lines gets denser (move closer together) and vice versa (compare Figures 7 and 8). The spacing between the spectral lines remains constant with constant PRI.

Pulse Width (PW) Effects - If the PRI remains constant, but the PW increases, then the lobe width decreases and vice versa. If the PW approaches PRI, the spectrum will approach "one lobe," i.e., a single spectral line. The spacing of the lobes remains constant with constant PW.

RF Measurements - If the receiver bandwidth is smaller than the PRF, the receiver will respond to one spectral line at a time. If the receiver bandwidth is wider than the PRF but narrower than the reciprocal of the PW, the receiver will respond to one spectral envelope at a time.

Jet Engine Modulation (JEM)

Section 2-6 addresses the Doppler shift in a transmitted radar signal caused by a moving target. The amount of Doppler shift is a function of radar carrier frequency and the speed of the radar and target. Moving or rotating surfaces on the target will have the same Doppler shift as the target, but will also impose AM on the Doppler shifted return (see Figure 10). Reflections off rotating jet engine compressor blades, aircraft propellers, ram air turbine (RAT) propellers used to power aircraft pods, helicopter rotor blades, and protruding surfaces of automobile hubcaps will all provide a chopped reflection of the impinging signal. The reflections are characterized by both positive and negative Doppler sidebands corresponding to the blades moving toward and away from the radar respectively.


FREQUENCY DOMAIN
Reflection of a stationary 10 GHz radar from a stationary target such as a metallic balloon.
Amplitude
10 GHz
Frequency
Reflection from a target such as a glider moving at 400 kts toward a stationary 10 GHz radar.
Amplitude
14 kHz
10 GHz
Frequency
Reflection from a jet or prop target moving at 400 kts toward a stationary 10 GHz radar.
Amplitude
Frequency

Figure 10. Doppler Return and JEM.

Therefore, forward/aft JEM does not vary with radar carrier frequency, but the harmonics contained in the sidebands are a function of the PRF of the blade chopping action and its amplitude is target aspect dependent, i.e., blade angle, intake/exhaust internal reflection, and jet engine cowling all effect lateral return from the side. If the aspect angle is too far from head-on or tail-on and the engine cowling provides shielding for the jet engine, there may not be any JEM to detect. On the other hand, JEM increases when you are orthogonal (at a right angle) to the axis of blade rotation. Consequently for a fully exposed blade as in a propeller driven aircraft or helicopter, JEM increases with angle off the boresight axis of the prop/rotor.

This page intentionally left blank.

TRANSFORMS / WAVELETS

Transform Analysis

Signal processing using a transform analysis for calculations is a technique used to simplify or accelerate problem solution. For example, instead of dividing two large numbers, we might convert them to logarithms, subtract them, then look-up the anti-log to obtain the result. While this may seem a three-step process as opposed to a one-step division, consider that long-hand division of a four digit number by a three digit number, carried out to four places requires three divisions, 3-4 multiplication's, and three subtractions. Computers process additions or subtractions much faster than multiplications or divisions, so transforms are sought which provide the desired signal processing using these steps.

Fourier Transform

Other types of transforms include the Fourier transform, which is used to decompose or separate a waveform into a sum of sinusoids of different frequencies. It transforms our view of a signal from time based to frequency based. Figure 1 depicts how a square wave is formed by summing certain particular sine waves. The waveform must be continuous, periodic, and almost everywhere differentiable. The Fourier transform of a sequence of rectangular pulses is a series of sinusoids. The envelope of the amplitude of the coefficients of this series is a waveform with a Sin X/X shape. For the special case of a single pulse, the Fourier series has an infinite series of sinusoids that are present for the duration of the pulse.



Figure 1. Harmonics.

Digital Sampling of Waveforms

To process a signal digitally, we need to sample the signal frequently enough to create a complete "picture" of the signal. The discrete Fourier transform (DFT) may be used in this regard. Samples are taken at uniform time intervals as shown in Figure 2 and processed.



Figure 2. Waveform Sampling.

If the digital information is multiplied by the Fourier coefficients, a digital filter is created as shown Figure 3. If the sum of the resultant components is zero, the filter has ignored (notched out) that frequency sample. If the sum is a relatively large number, the filter has passed the signal. With the single sinusoid shown, there should be only one resultant. (Note that being "zero" and relatively large



Figure 3. Digital Filtering.

may just mean below or above the filter's cutoff threshold.)

Figure 4 depicts the process pictorially: The vectors in the figure just happen to be pointing in a cardinal direction because the strobe frequencies are all multiples of the vector (phasor) rotation rate, but that is not normally the case. Usually the vectors will point in a number of different directions, with a resultant in some direction other than straight up.


"Strobe Light" Filters
100 Hz
200 Hz
300 Hz
400 Hz
Phasor Rotating At 300 Hz Represents Signal of Interest
0.02 sec = 2 strobes
0.02 sec = 4 strobes
0.02 sec = 6 strobes
0.02 sec = 8 strobes
Filter Integration over a 0.02 second interval
Only the 300 Hz Filter adds appreciably in Phase
= 0
= 0

Figure 4. Phasor Representation.

In addition, sampling normally has to taken at or above twice the rate of interest (also known as the Nyquist rate), otherwise ambiguous results may be obtained. Figure 4 is under-sampled (for clarity) and consequently does not depict typical filtering.

Fast Fourier Transforms

One problem with this type of processing is the large number of additions, subtractions, and multiplications which are required to reconstruct the output waveform. The Fast Fourier transform (FFT) was developed to reduce this problem. It recognizes that because the filter coefficients are sine and cosine waves, they are symmetrical about 90, 180, 270, and 360 degrees. They also have a number of coefficients equal either to one or zero, and duplicate coefficients from filter to filter in a multibank arrangement. By waiting for all of the inputs for the bank to be received, adding together those inputs for which coefficients are the same before performing multiplications, and separately summing those combinations of inputs and products which are common to more than one filter, the required amount of computing may be cut drastically.

- The number of computations for a DFT is on the order of N squared.

- The number of computations for a FFT when N is a power of two is on the order of N $\log_2$ N.

For example, in an eight filter bank, a DFT would require 512 computations, while an FFT would only require 56, significantly speeding up processing time.


Frequency
Time

Figure 5. Windowed Fourier Transform.

Windowed Fourier Transform

The Fourier transform is continuous, so a windowed Fourier transform (WFT) is used to analyze non-periodic signals as shown in Figure 5. With the WFT, the signal is divided into sections (one such section is shown in Figure 5) and each section is analyzed for frequency content. If the signal has sharp transitions, the input data is windowed so that the sections converge to zero at the endpoints. Because a single window is used for all frequencies in the WFT, the resolution of the analysis is the same (equally spaced) at all locations in the time-frequency domain.

The FFT works well for signals with smooth or uniform frequencies, but it has been found that other transforms work better with signals having pulse type characteristics, time-varying (non-stationary) frequencies, or odd shapes.

The FFT also does not distinguish sequence or timing information. For example, if a signal has two frequencies (a high followed by a low or vice versa), the Fourier transform only reveals the frequencies and relative amplitude, not the order in which they occurred. So Fourier analysis works well with stationary, continuous, periodic, differentiable signals, but other methods are needed to deal with non-periodic or non-stationary signals.

Wavelet Transform

The Wavelet transform has been evolving for some time. Mathematicians theorized its use in the early 1900’s. While the Fourier transform deals with transforming the time domain components to frequency domain and frequency analysis, the wavelet transform deals with scale analysis, that is, by creating mathematical structures that provide varying time/frequency/amplitude slices for analysis. This transform is a portion (one or a few cycles) of a complete waveform, hence the term wavelet.

The wavelet transform has the ability to identify frequency (or scale) components, simultaneously with their location(s) in time. Additionally, computations are directly proportional to the length of the input signal. They require only N multiplications (times a small constant) to convert the waveform. For the previous eight filter bank example, this would be about twenty calculations, vice 56 for the FFT.


Low frequencies are better resolved in frequency
High frequencies are better resolved in time
Frequency
Time

Figure 6. Wavelet Transform.

In wavelet analysis, the scale that one uses in looking at data plays a special role. Wavelet algorithms process data at different scales or resolutions. If we look at a signal with a large “window,” we would notice gross features. Similarly, if we look at a signal with a small “window,” we would notice small discontinuities as shown in Figure 6. The result in wavelet analysis is to “see the forest and the trees.” A way to achieve this is to have short high-frequency fine scale functions and long low-frequency ones. This approach is known as multi-resolution analysis.

For many decades, scientists have wanted more appropriate functions than the sines and cosines (base functions) which comprise Fourier analysis, to approximate choppy signals. (Although Walsh transforms work if the waveform is periodic and stationary). By their definition, sine and cosine functions are non-local (and stretch out to infinity), and therefore do a very poor job in approximating sharp spikes. But with wavelet analysis, we can use approximating functions that are contained neatly in finite (time/frequency) domains. Wavelets are well-suited for approximating data with sharp discontinuities.

The wavelet analysis procedure is to adopt a wavelet prototype function, called an "analyzing wavelet" or "mother wavelet." Temporal analysis is performed with a contracted, high-frequency version of the prototype wavelet, while frequency analysis is performed with a dilated, low-frequency version of the prototype wavelet. Because the original signal or function can be represented in terms of a wavelet expansion (using coefficients in a linear combination of the wavelet functions), data operations can be performed using just the corresponding wavelet coefficients as shown in Figure 7.

If one further chooses the best wavelets adapted to the data, or truncates the coefficients below some given threshold, the data is sparsely represented. This "sparse coding" makes wavelets an excellent tool in the field of data compression. For instance, the FBI uses wavelet coding to store fingerprints. Hence, the concept of wavelets is to look at a signal at various scales and analyze it with various resolutions.



Figure 7. Wavelet Filtering.

Analyzing Wavelet Functions

Fourier transforms deal with just two basis functions (sine and cosine), while there are an infinite number of wavelet basis functions. The freedom of the analyzing wavelet is a major difference between the two types of analyses and is important in determining the results of the analysis. The "wrong" wavelet may be no better (or even far worse than) than the Fourier analysis. A successful application presupposes some expertise on the part of the user. Some prior knowledge about the signal must generally be known in to select the most suitable distribution and adapt the parameters to the signal. Some



Figure 8. Sample Wavelet Functions.

of the more common ones are shown in Figure 8. There are several wavelets in each family, and they may look different than those shown. Somewhat longer in duration than these functions, but significantly shorter than infinite sinusoids is the cosine packet shown in Figure 9.

Wavelet Comparison With Fourier Analysis

While a typical Fourier transform provides frequency content information for samples within a given time interval, a perfect wavelet transform records the start of one frequency (or event), then the start of a second event, with amplitude added to or subtracted from, the base event.

Example 1.

Wavelets are especially useful in analyzing transients or time-varying signals. The input signal shown in Figure 9 consists of a sinusoid whose frequency changes in stepped increments over time. The power of the spectrum is also shown. Classical Fourier analysis will resolve the frequencies but cannot provide any information about the times at which each occurs. Wavelets provide an efficient means of analyzing the input signal so that frequencies and the times at which they occur can be resolved. Wavelets have finite duration and must also satisfy additional properties beyond those normally associated with standard windows used with Fourier analysis. The result after the wavelet transform is applied is the plot shown in the lower right. The wavelet analysis correctly resolves each of the frequencies and the time when it occurs. A series of wavelets is used in example 2.



Figure 9. Sample Wavelet Analysis.

Example 2.


High Pass Filter
(HPF)
Wavelet
Function
Y
512 Samples
d1
1024
Samples
Signal
INPUT
F
Low Pass Filter
(LPF)
Scaling
Function
HPF
LPF
256 Samples
d2
128 Samples
d3
64 Samples
d4
32 Samples
d5
16
d6
16
s6
Signal Without Noise
or
Signal With -5 dB Noise
S/N = +5 dB
decimate by 2
OUTPUTS of FILTERS
With No Noise Input
d1
d2
d3
d4
d5
d6
s6
With Noise Input
d4 S/N = +11 dB
d1
d2
d3
d4
d5
d6
s6

Figure 10. Example 2 Analysis Wavelet.

Figure 10 shows the input of a clean signal, and one with noise. It also shows the output of a number of “filters” with each signal. A 6 dB S/N improvement can be seen from the d4 output. (Recall from Section 4.3 that 6 dB corresponds to doubling of detection range.) In the filter cascade, the HPFs and LPFs are the same at each level. The wavelet shape is related to the HPF and LPF in that it is the “impulse response” of an infinite cascade of the HPFs and LPFs. Different wavelets have different HPFs and LPFs. As a result of decimating by 2, the number of output samples equals the number of input samples.

Wavelet Applications

Some fields that are making use of wavelets are: astronomy, acoustics, nuclear engineering, signal and image processing (including fingerprinting), neurophysiology, music, magnetic resonance imaging, speech discrimination, optics, fractals, turbulence, earthquake-prediction, radar, human vision, and pure mathematics applications.

See Andrew Bruce, David Donoho, and Hong-Ye Gao, “Wavelet Analysis,” *IEEE Spectrum*, Vol. 33 No. 10, October 1996.

ANTENNAS

Antenna Introduction / Basics....3-1
Polarization....3-2
Radiation Patterns....3-3
Frequency / Phase Effects of Antennas....3-4
Antenna Near Field....3-5
Radiation Hazards....3-6
Active Electronically Scanned Arrays (AESA)....3-7
Fractal Antennas....3-8

This page intentionally left blank.

ANTENNA INTRODUCTION / BASICS

Rules of Thumb:

1. The power gain of an antenna with losses, excluding input impedance mismatch, is given by:

$$G \approx \frac{4\pi\eta A}{\lambda^2} \quad \text{Where} \quad \begin{aligned} \eta &= \text{Efficiency} \\ A &= \text{Physical aperture area} \\ \lambda &= \text{wavelength} \end{aligned}$$

another is :

$$G = \frac{X\eta}{BW_\phi \, BW_\theta}$$

Where $BW_{\theta \text{ and } \phi}$ are the elev & az beamwidths in degrees.

For approximating an antenna pattern with :

(1) A rectangle; $X = 41253, \eta_{typical} = 0.7$

(2) An ellipsoid; $X = 52525, \eta_{typical} = 0.55$

2. Directive gain of rectangular X-Band Aperture
   $G = 1.4\,LW$ Where: Length (L) and Width (W) are in cm

3. Power gain of Circular X-Band Aperture
   $G = d^2\eta$ Where: d = antenna diameter in cm
   η = aperture efficiency



4. Directive gain of an imaginary isotropic antenna radiating in a uniform spherical pattern is one (0 dB).

5. Antenna with a 20 degree beamwidth has approximately a 20 dB directive gain.

6. 3 dB beamwidth is approximately equal to the angle from the peak of the power to the first null (see figure at right).

7. Parabolic Antenna Beamwidth: $$BW = \frac{70\lambda}{d}$$

   Where: BW = antenna beamwidth; λ = wavelength; d = antenna diameter.

The antenna equations which follow relate to Figure 1 as a typical antenna. In Figure 1, BW_φ is the azimuth beamwidth and BW_θ is the elevation beamwidth. Beamwidth is normally measured at the half-power or -3 dB point of the main lobe unless otherwise specified. See Glossary.

The gain or directivity of an antenna is the ratio of the radiation intensity in a given direction to the radiation intensity averaged over all directions.



Figure 1. Antenna Aperture.

Quite often directivity and gain are used interchangeably and it sometimes leads to overly optimistic antenna performance estimations. The difference is that directivity is based solely on antenna pattern shape estimation where antenna losses such as dielectric, ohmic resistance, and polarization mismatch are neglected. If these losses are included in the antenna gain calculations, the antenna gain is then referred to as the power gain. Moreover, if additional impedance mismatch or VSWR losses are included in the antenna system gain estimation, the antenna gain calculations are then referred to as the realized gain. However, using directive gain (or directivity) calculations is very convenient in practice for a first order idealized antenna performance estimation.

Normalizing a radiation pattern by the integrated total power yields the directivity of the antenna. This concept in shown in equation form by:

$$D(\theta,\phi) = 10 \,\mathrm{Log}\left[\frac{4\pi P\ (\theta,\phi)}{\iint P_{in}(\theta,\phi)\,\mathrm{Sin}\,\theta\, d\theta\, d\phi}\right] \quad \begin{matrix} 0 < \phi \leq 360° \\ 0 < \theta \leq 180° \end{matrix} \qquad [1]$$

Where $D(\theta,\varphi)$ is the directivity in dB, and the radiation pattern power in a specific direction is $P_d(\theta,\varphi)$, which is normalized by the total integrated radiated power. Another important concept is that when the angle in which the radiation is constrained is reduced, the directive gain goes up. For example, using an isotropic radiating source, the gain would be 0 dB by definition (Figure 2(a)) and the power density (P_d) at any given point would be the power in (P_{in}) divided by the surface area of the imaginary sphere at a distance R from the source. If the spacial angle was decreased to one hemisphere (Figure 2(b)), the power radiated, P_{in}, would be the same but the area would be half as much, so the gain would double to 3 dB. Likewise if the angle is a quarter sphere, (Figure 2(c)), the gain would be 6 dB. Figure 2(d) shows a pencil beam. The gain is independent of actual power output and radius (distance) at which measurements are taken.


(a) SPHERE (Isotropic source)
$P_D = \frac{P_{in}}{4\pi R^2}$
G = 0 dB
(b) HEMISPHERE
$P_D = \frac{2 P_{in}}{4\pi R^2}$
G = +3 dB
(c) QUARTER SPHERE
$P_D = \frac{4 P_{in}}{4\pi R^2}$
G = +6 dB
(d) 1.5° SEGMENT
$P_D = \frac{18334 P_{in}}{4\pi R^2}$
G = +43 dB

Figure 2. Notional Representation of Directive Antenna Gain.

Real antennas are different, however, and do not have an ideal radiation distribution. Energy varies with angular displacement and losses occur due to sidelobes. However, if we can measure the pattern, and determine the beamwidth we can use two (or more) ideal antenna models to approximate a real antenna pattern as shown in Figure 3.


IDEAL ANTENNA PATTERN
3D Views
Elliptical Model
Rectangular Model
2D Views
REAL ANTENNA PATTERN
-3 dB Beamwidth
(measured at the 0.5 power or 0.707 voltage points)

Figure 3. Antenna Beamwidth.

Assuming the antenna pattern is uniform, the gain is equal to the area of the isotropic sphere ($4\pi r^2$) divided by the sector (cross section) area.

$$G = \frac{Area\ of\ Sphere}{Area\ of\ Antenna\ pattern} \qquad [2]$$

It can be shown that:

$$G \approx \frac{4\pi}{BW_{\phi\, az}\, BW_{\theta\, el}} \quad or \quad \frac{4\pi}{\phi\theta\ (radians)} \quad where: \begin{matrix} BW_{\phi\, az} = Azmith\ beamwidth\ in\ radians \\ BW_{\theta\, el} = Elevation\ beamwidth\ in\ radians \end{matrix} \qquad [3]$$

From this point, two different models are presented:

(1) Approximating an antenna pattern using an elliptical area, and
(2) Approximating an antenna pattern using a rectangular area.

Approximating the antenna pattern as an **elliptical** area:



Where $\theta = BW_\theta$, and $\phi = BW_\phi$

Area of ellipse = $\pi a b = \pi[(r \sin \theta)/2][(r \sin \varphi)/2] = (\pi r^2 \sin \theta \sin \varphi)/4$

$$G = \frac{Area\ of\ Sphere}{Area\ of\ Antenna\ pattern} = (4\pi r^2)\left(\frac{4}{\pi r^2 \sin\theta \sin\phi}\right) = \frac{16}{\sin\theta \sin\phi}$$

For small angles, $\sin \varphi = \varphi$ in radians, so:

$$G = \frac{16}{\sin\phi \sin\theta} \approx \frac{16}{\phi\,\theta\ (radians)} = \frac{16}{\phi\,\theta}\left(\frac{360°\ 360°}{2\pi\ 2\pi}\right) = \frac{52525}{\phi\,\theta\ (degrees)}\ or\ \frac{52525}{BW_\phi\, BW_\theta\ (degrees)}$$ **[4]**

The second term in the equation above is very close to equation [3].

For a very directional radar dish with a beamwidth of 1° and an average efficiency of 55%:

Ideally: G = 52525, or in dB form: 10 log G =10 log 52525 = 47.2 dB

With efficiency taken into account, G = 0.55(52525) = 28888, or in log form: 10 log G = 44.6 dB

Approximating the antenna pattern as a **rectangular** area:



Where $\theta = BW_\theta$, and $\phi = BW_\phi$

$a = r \sin \theta$, $b = r \sin \varphi$, area = $ab = r^2 \sin \theta \sin \varphi$

$$G = \frac{Area\ of\ Sphere}{Area\ of\ Antenna\ pattern} = \frac{4\pi r^2}{r^2 \sin\theta \sin\phi} = \frac{4\pi}{\sin\theta \sin\phi}$$

For small angles, $\sin \varphi = \varphi$ in radians, so:
The second term in the equation above is identical to equation [3].

$$G = \frac{4\pi}{\sin\phi \sin\theta} = \frac{4\pi}{\phi\,\theta\ (radians)} = \frac{4\pi}{\phi\,\theta}\left(\frac{360°\ 360°}{2\pi\ 2\pi}\right) = \frac{41253}{\phi\,\theta\ (degrees)}\ or\ \frac{41253}{BW_\phi\, BW_\theta\ (degrees)}$$ **[5]**

Converting to dB, $G_{\max}(dB) = 10\ \mathrm{Log}\left[\frac{41253}{BW_\phi\, BW_\theta}\right]$ *with* BW_ϕ *and* BW_θ *in degrees* **[6]**

For a very directional radar dish with a beamwidth of 1° and an average efficiency of 70%:
Ideally (in dB form): 10 log G =10 log 41253 = 46.2 dB.
With efficiency taken into account, G = 0.7(41253) = 28877, or in log form: 10 log G = 44.6 dB

Comparison between elliptical and rectangular areas for antenna pattern models:
By using the rectangular model there is a direct correlation between the development of gain in equation [5] and the ideal gain of equation [3]. The elliptical model has about one dB difference from the ideal calculation, but will yield the same real antenna gain when appropriate efficiencies are assumed.



Figure 4. Antenna Sector Size vs. Gain.

The upper plot of Figure 4 shows the gain for an ideal antenna pattern using the elliptical model. The middle plot shows the gain for an ideal antenna using the rectangular model. The lower plot of Figure 4 shows the gain of a typical real antenna (rectangular model using an efficiency of 70% or elliptical model using an efficiency of 47%).

Gain as a function of λ:
When θ = 0, each wave source in Figure 5 is in phase with one another and a maximum is produced in that direction.

Conversely, nulls to either side of the main lobe will occur when the waves radiating from the antenna cancel each other. The first null occurs when there is a phase difference of λ/2 in the wave fronts emanating from the aperture. To aid in visualizing what happens, consider each point in the antenna aperture, from A to C in Figure 5, as a point source of a spherical wave front. If viewed from infinity, the electromagnetic waves from each point interfere with each other, and when, for a particular direction, θ in Figure 5, each wave source has a corresponding point that is one-half wavelength out of phase, a null is produced in that direction due to destructive interference.



Figure 5. Directional Gain vs. Wavelength.

In Figure 5, the wave emanating from point A is out of phase with the wave from point B by one-half of a wavelength. Hence, they cancel. Similarly, a point just to the right of point A cancels with a point just to the right of point B, and so on across the entire aperture. Therefore, the first null in the radiation pattern is given by:

$$\text{Sin } \theta = \lambda/L \text{ and, in radians, } \theta = \lambda/L \text{ (for small angles)} \qquad \textbf{[7]}$$

As the angle off boresight is increased beyond the first null, the intensity of the radiation pattern rises then falls, until the second null is reached. This corresponds to a phase difference of two wavelengths between the left and right edges of the aperture. In this case, the argument proceeds as before, except now the aperture is divided into four segments (point A canceling with a point halfway between A and B, and so on).

The angle θ is the angle from the center (maximum) of the radiation pattern to the first null. The null-to-null beam width is 2θ. Generally, we are interested in the half-power (3 dB) beamwidth. It turns out that this beamwidth is approximately one-half of the null-to-null beamwidth, so that:

$$BW_{3\,dB} \approx (½)(2\theta) = \lambda/L \qquad \textbf{[8]}$$

Therefore, beamwidth is a function of the antenna dimension "L" and the wavelength of the signal. It can be expressed as follows: Note: for circular antennas, L in the following equations = diameter

$$Bw_{\varphi(az)} = \lambda/L_{Az\ eff} \text{ and } BW_{\theta(el)} = \lambda/L_{El\ eff} \qquad \textbf{[9]}$$

Substituting the two variations of equation [9] into equation [3] and since $L_{Az\ eff}$ times $L_{El\ eff}$ = A_e (effective capture area of the antenna), we have:

$$G \approx \frac{4\pi}{BW_{\phi}\,BW_{\theta}\,(radians)} = \frac{4\pi\ L_{az}\ L_{el}}{\lambda^2} = \frac{4\pi\ A_e}{\lambda^2} \qquad \textbf{[10]}$$

Note: Equation is approximate since aperture efficiency isn't included as is done later in equation [12].

The efficiency (discussed later) will reduce the gain by a factor of 30-50%, i.e. real gain = .5 to .7 times theoretical gain.

Unity Gain Antenna.
If a square antenna is visualized and G=1, $A_e = \lambda^2 / 4\pi$. When a dimension is greater than 0.28 λ (~¼λ) it is known as an electrically large antenna, and the antenna will have a gain greater than one (positive gain when expressed in dB). Conversely, when the dimension is less than 0.28 λ (~¼λ)(an electrically small antenna), the gain will be less than one (negative gain when expressed in dB). Therefore, a unity gain antenna can be approximated by an aperture that is ¼λ by ¼λ.

Beamwidth as a Function of Aperture Length
It can be seen from Figure 5, that the wider the antenna aperture (L), the narrower the beamwidth will be for the same λ. Therefore, if you have a rectangular shaped horn antenna, the radiation pattern from the wider side will be narrower than the radiation pattern from the narrow side.

APERTURE EFFICIENCY, η

The Antenna Efficiency, η, is a factor which includes all reductions from the maximum gain. η can be expressed as a percentage, or in dB. Several types of "loss" must be accounted for in the efficiency, η:

(1) Illumination efficiency which is the ratio of the directivity of the antenna to the directivity of a uniformly illuminated antenna of the same aperture size,
(2) Phase error loss or loss due to the fact that the aperture is not a uniform phase surface,
(3) Spillover loss (Reflector Antennas) which reflects the energy spilling beyond the edge of the reflector into the back lobes of the antenna,

(4) Mismatch (VSWR) loss, derived from the reflection at the feed port due to impedance mismatch (especially important for low frequency antennas), and
(5) RF losses between the antenna and the antenna feed port or measurement point.

The aperture efficiency, η_a, is also known as the illumination factor, and includes items (1) and (2) above; it does not result in any loss of power radiated but affects the gain and pattern. It is nominally 0.6-0.8 for a planer array and 0.13 to 0.8 with a nominal value of 0.5 for a parabolic antenna, however η can vary significantly. Other antennas include the spiral (.002-.5), the horn (.002-.8), the double ridge horn (.005-.93), and the conical log spiral (.0017-1.0).

Items (3), (4), and (5) above represent RF or power losses which can be measured. The efficiency varies and generally gets lower with wider bandwidths. Also note that the gain equation is optimized for small angles - see derivation of wavelength portion of equation [7]. This explains why efficiency also gets lower for wider beamwidth antennas.

EFFECTIVE CAPTURE AREA

Effective capture area (A_e) is the product of the physical aperture area (A) and the aperture efficiency (η) or:

$$A_e = \eta A = \frac{\lambda^2 G}{4\pi} \qquad \textbf{[11]}$$

GAIN AS A FUNCTION OF APERTURE EFFICIENCY

The Gain of an antenna with losses is given by:

$$G = \frac{4\pi\eta A}{\lambda^2} \quad \begin{aligned} &\eta = \textit{Aperture Efficiency} \\ \textit{Where } &A = \textit{Physical aperture area} \\ &\lambda = \textit{wavelength} \end{aligned} \qquad \textbf{[12]}$$

Note that the gain is proportional to the aperture area and inversely proportional to the square of the wavelength. For example, if the frequency is doubled, (half the wavelength), the aperture could be decreased four times to maintain the same gain.

BEAM FACTOR

Antenna size and beamwidth are also related by the beam factor defined by:

Beam Factor = $(D/\lambda)\cdot$(Beamwidth) where D = antenna dimension in wavelengths.

The beam factor is approximately invariant with antenna size, but does vary with type of antenna aperture illumination or taper. The beam factor typically varies from 50-70°.

APERTURE ILLUMINATION (TAPER)

The aperture illumination or illumination taper is the variation in amplitude across the aperture. This variation can have several effects on the antenna performance:

(1) reduction in gain,
(2) reduced (lower) sidelobes in most cases, and
(3) increased antenna beamwidth and beam factor.

Tapered illumination occurs naturally in reflector antennas due to the feed radiation pattern and the variation in distance from the feed to different portions of the reflector. Phase can also vary across the aperture which also affects the gain, efficiency, and beamwidth.

CIRCULAR ANTENNA GAIN

Solving equation [12] in dB, for a circular antenna with area $\pi D^2/4$, we have:

$$10 \text{ Log } G = 20 \text{ Log } (D/\lambda) + 10 \text{ Log } (\eta) + 9.94 \text{ dB}; \quad \text{where } D = \text{diameter} \qquad \textbf{[13]}$$

This data is depicted in the nomograph of Figure 6. For example, a six foot diameter antenna operating at 9 GHz would have approximately 44.7 dB of gain as shown by the dashed line drawn on Figure 6. This gain is for an antenna 100% efficient, and would be 41.7 dB for a typical parabolic antenna (50% efficient).



Figure 6. Antenna Gain Nomograph.

An example of a typical antenna (with losses) showing the variation of gain with frequency is depicted in Figure 7, and the variation of gain with antenna diameter in Figure 8. The circle on the curves in Figure 7 and 8 correspond to the Figure 6 example and yields 42 dB of gain for the 6 ft dish at 9 GHz.

Example Problem: If the two antennas in the drawing are "welded" together, how much power will be measured at point A? (Line loss $L_1 = L_2 = 0.5$, and 10log L_1 or $L_2 = 3$ dB)

Multiple choice:

A. 16 dBm b. 28 dBm c. 4 dBm d. 10 dBm e. < 4 dBm



Answer:

The antennas do not act as they normally would since the antennas are operating in the near field. They act as inefficient coupling devices resulting in some loss of signal. In addition, since there are no active components, you cannot end up with more power than you started with. The correct answer is "e. < 4 dBm."

10 dBm - 3 dB - small loss -3 dB = 4 dBm - small loss

If the antennas were separated by 5 ft and were in the far field, the antenna gain could be used with space loss formulas to calculate (at 5 GHz): 10 dBm - 3 dB + 6 dB - 50 dB (space loss) + 6 dB -3 dB = -34 dBm (a much smaller signal).



Figure 7. Gain of a Typical 6-Foot Dish Antenna (With Losses).



Figure 8. Gain of a Typical Dish at 9 GHz (With Losses).

This page intentionally left blank.

POLARIZATION

Table 1 shows the **theoretical** ratio of power transmitted between antennas of different polarization. These ratios are seldom fully achieved due to effects such as reflection, refraction, and other wave interactions, so some practical ratios are also included.

Table 1. Polarization Loss for Various Antenna Combinations.

Transmit Antenna Polarization	**Receive Antenna Polarization**	**Ratio of Power Received to Maximum Power**					
		Theoretical		Practical Horn		Practical Spiral	
		Ratio in dB	as Ratio	Ratio in dB	as Ratio	Ratio in dB	as Ratio
Vertical	Vertical	0 dB	1	*	*	N/A	N/A
Vertical	Slant (45° or 135°)	-3 dB	½	*	*	N/A	N/A
Vertical	Horizontal	- ∞ dB	0	-20 dB	1/100	N/A	N/A
Vertical	Circular (right-hand or left-hand)	-3 dB	½	*	*	*	*
Horizontal	Horizontal	0 dB	1	*	*	N/A	N/A
Horizontal	Slant (45° or 135°)	-3 dB	½	*	*	N/A	N/A
Horizontal	Circular (right-hand or left-hand)	-3 dB	½	*	*	*	*
Circular (right-hand)	Circular (right-hand)	0 dB	1	*	*	*	*
Circular (right-hand)	Circular (left-hand)	- ∞ dB	0	-20 dB	1/100	-10 dB	1/10
Circular (right or left)	Slant (45° or 135°)	-3 dB	½	*	*	*	*

* Approximately the same as theoretical.
Note: Switching transmit and receive antenna polarization will give the same results.



The sum of the E field vectors determines the sense of polarization

Figure 1. Polarization Coordinates.

The polarization of an electromagnetic wave is defined as the orientation of the electric field vector. Recall that the electric field vector is perpendicular to both the direction of travel and the magnetic field vector. The polarization is described by the geometric figure traced by the electric field vector upon a stationary plane perpendicular to the direction of propagation, as the wave travels through that plane. An electromagnetic wave is frequently composed of (or can be broken down into) two orthogonal components as shown in Figure 1. This may be due to the arrangement of power input leads to various points on a flat antenna, or due to an interaction of active elements in an array, or many other reasons.

The geometric figure traced by the sum of the electric field vectors over time is, in general, an ellipse as shown in Figure 2. Under certain conditions the ellipse may collapse into a straight line, in which case the polarization is called linear.

In the other extreme, when the two components are of equal magnitude and 90° out of phase, the ellipse will become circular as shown in Figure 3. Thus linear and circular polarization are the two special cases of elliptical polarization. Linear polarization may be further classified as being vertical, horizontal, or slant.

Figure 2 depicts plots of the E field vector while varying the relative amplitude and phase angle of its component parts.


Ratio of
E_y / E_x
∞
2
1
1/2
0
Wave is travelling toward viewer - Out of the paper
Vertical polarization
Counter Clockwise
Clockwise
RHCP
LHCP
Horizontal polarization
-180°
-135°
-90°
-45°
0°
+45°
+90°
+135°
+180°
Phase angle between E Field Vectors

Figure 2. Polarization as a Function of E_y / E_x Ratio and Phase Angle.
Adopted from J.D. Kraus, "Antennas," 2nd ed., Figure 2-37

For a linearly polarized antenna, the radiation pattern is taken both for a co-polarized and cross polarized response. The polarization quality is expressed by the ratio of these two responses. The ratio between the responses must typically be great (30 dB or greater) for an application such as cross-polarized jamming. For general applications, the ratio indicates system power loss due to polarization mismatch. For circularly polarized antennas, radiation patterns are usually taken with a rotating linearly polarized reference antenna. The reference antenna rotates many times while taking measurements around the azimuth of the antenna that is being tested. The resulting antenna pattern is the linear polarized gain with a cyclic ripple. The peak-to-peak value is the axial ratio, and represents the polarization quality for a circular polarized antenna. The typical RWR antenna has a maximum 3 dB axial ratio within 45° of boresight.


Y
0
π/2
π
E_y
2π
4π
5π
6π
E_x
4π
2π
π
0
Z
X

Figure 3. Circular Polarization – E Field.

For any antenna with an aperture area, as the aperture is rotated, the viewed dimension along the axis remains constant, while the other viewed dimension decreases to zero at 90° rotation. The axial ratio of an antenna will get worse as the antenna is rotated off boresight because the field contribution from the axial component will remain fairly constant and the other orthogonal component will decrease with rotation.

The sense of antenna polarization is defined from a viewer positioned behind an antenna looking in the direction of propagation. The polarization is specified as a transmitting, not receiving antenna regardless of intended use.

We frequently use "hand rules" to describe the sense of polarization. The sense is defined by which hand would be used in order to point that thumb in the direction of propagation and point the fingers of the same hand in the direction of rotation of the E field vector. For example, referring to Figure 4, if your thumb is pointed in the direction of propagation and the rotation is counterclockwise looking in the direction of travel, then you have left hand circular polarization.


Thumb In The Direction Of Propagation Of Wave
Fingers in The Direction of Rotation of E Field Vector

Figure 4. Left Hand Polarization.

Optics people view an aperture from the front and therefore use the opposite reference.

The polarization of a linearly polarized horn antenna can be directly determined by the orientation of the feed probe, which is in the direction of the E-field.

In general, a flat surface or sphere will reflect a linearly polarized wave with the same polarization as received. A horizontally polarized wave may get extended range because of water and land surface reflections, but signal cancellation will probably result in "holes" in coverage. Reflections will reverse the sense of circular polarization.

If the desired antenna is used for receiving a direct transmission as shown in Figure 5, the same polarization sense (specified if transmitting) is required for maximum signal reception in this situation. Buy two right-hand or two left-hand circularly polarized antennas for this case. When you procure antennas, remember that the polarization is specified as if transmitting, regardless of intended use.

Wave propagation between two identical antennas is analogous to being able to thread a nut from one bolt to an identical opposite facing bolt.


XMTR
P_tG_t
RHCP
P_rG_r
RCVR
$RHCP_{Tx\ Antenna}$
$RHCP_{Tx\ Antenna}$
NOTE: This figure depicts an example only, all polarizations can be reversed.
In either case, the antennas should be identical.

Figure 5. Same Circular Polarization.

If the desired antenna is used for a receiving a wave with a single or odd number of reflections, such as a bistatic radar where separate antennas are used for transmit and receive as shown in Figure 6, then opposite circularly polarized antennas would be used for maximum signal reception. In this case buy antennas of opposite polarization sense (one left hand and one right hand).


XMTR
P_tG_t
RHCP Tx Antenna
RCVR
P_rG_r
LHCP Tx Antenna
RHCP
LHCP
Single Reflector Targets
e.g. Flat Plate or Sphere
NOTE: This figure depicts an example only, all polarizations can be reversed.
In either case, the antennas should have opposite polarization.

Figure 6. Opposite Circular Polarization.

In a corner reflector, waves reflect twice before returning to the receiver as shown in Figure 7, consequently they return with the same sense as they were transmitted. In this case (or any even number of reflections) buy antennas of the same polarization sense.


XMTR
P_tG_t
RHCP Tx Antenna
RCVR
P_rG_r
RHCP Tx Antenna
RHCP
LHCP
RHCP
Corner Reflector Targets
NOTE: This figure depicts an example only, all polarizations can be reversed.
In either case, the antennas should be identical.

Figure 7. Circular Polarization With Corner Reflector.

An aircraft acts as both a corner reflector and a "normal" reflector so the return has mixed polarization. Most airborne radars use the same antenna for transmitting and receiving in order to receive the corner reflections and help exclude receipt of reflections from rain (single polarization reversal), however in doing so there is about a 5-9 dB loss from the ideal receiver case. It should be noted that the return from raindrops is attenuated by approximately 20 dB.

RADIATION PATTERNS

The radiation pattern is a graphical depiction of the relative field strength transmitted from or received by the antenna. Antenna radiation patterns are taken at one frequency, one polarization, and one plane cut. The patterns are usually presented in polar or rectilinear form with a dB strength scale. Patterns are normalized to the maximum graph value, 0 dB, and a directivity is given for the antenna. This means that if the side lobe level from the radiation pattern were down -13 dB, and the directivity of the antenna was 4 dB, then the sidelobe gain would be -9 dB.

Figures 1 to 14 on the pages following depict various antenna types and their associated characteristics. The patterns depicted are those which most closely match the purpose for which the given shape was intended. In other words, the radiation pattern can change dramatically depending upon frequency, and the wavelength to antenna characteristic length ratio. See Section 3-4. Antennas are designed for a particular frequency. Usually the characteristic length is a multiple of $\lambda/2$ minus 2-15% depending on specific antenna characteristics.

The gain is assumed to mean directional gain of the antenna compared to an isotropic radiator transmitting to or receiving from all directions.

The half-power (-3 dB) beamwidth is a measure of the directivity of the antenna.

Polarization, which is the direction of the electric (not magnetic) field of an antenna is another important antenna characteristic. This may be a consideration for optimizing reception or jamming.

The bandwidth is a measure of how much the frequency can be varied while still obtaining an acceptable VSWR (2:1 or less) and minimizing losses in unwanted directions. See Glossary, Section 10.

A 2:1 VSWR corresponds to a 9.5 dB (or 10%) return loss - see Section 6-2.

Two methods for computing antenna bandwidth are used:

Narrowband by %, $B = \left(\frac{F_U - F_L}{F_C} \right)(100)$, where F_C = Center frequency

Broadband by ratio, $B = \frac{F_U}{F_L}$

An antenna is considered broadband if $F_U / F_L > 2$. The table at the right shows the equivalency of the two, however the shaded values are not normally used because of the aforementioned difference in broadband/narrowband.

Bandwidth	
%	Ratio
5	1.05 : 1
10	1.11 : 1
20	1.22 : 1
30	1.35 : 1
40	1.50 : 1
50	1.67 : 1
60	1.85 : 1
67	2 : 1
100	3 : 1
120	4 : 1
133	5 : 1
150	7 : 1
160	9 : 1
163	10 : 1

Should there be ever a need to express bandwidth of an antenna in one or the other alternative formats, a conversion between the two narrowband and broadband bandwidth quantities can be easily calculated using the following relationships:

Calculate broadband ratio B_{bb} given narrowband B%,

$$B_{bb} = (200 + B\%)/(200 - B\%) \qquad \textbf{[1]}$$

Calculate narrowband B% given broadband ratio B_{bb},

$$B\% = 200 * (Bbb - 1)/(Bbb + 1) \quad \textbf{[2]}$$

For an object that experiences a plane wave, the resonant mode is achieved when the dimension of the object is nλ/2, where n is an integer. Therefore, one can treat the apertures shown in the following figure as half wave length dipole antennas for receiving and reflecting signals. More details are contained in Section 8-4.



The following lists antenna types by page number. The referenced page shows frequency limits, polarizations, etc.

Type	Page	Type	Page
4 arm conical spiral	3-3.6	log periodic	3-3.8
alford loop	3-3.4	loop, circular	3-3.4
aperture synthesis	3-3.8	loop, alford	3-3.4
array	3-3.8	loop, square	3-3.4
axial mode helix	3-3.5	luneberg lens	3-3.9
biconical w/polarizer	3-3.6	microstrip patch	3-3.9
biconical	3-3.6	monopole	3-3.3
cavity backed circuit fed slot	3-3.5	normal mode helix	3-3.5
cavity backed spiral	3-3.9	parabolic	3-3.7
circular loop	3-3.4	patch	3-3.9
conical spiral	3-3.5	reflector	3-3.10
corner reflector	3-3.9	rhombic	3-3.3
dipole array, linear	3-3.8	sinuous, dual polarized	3-3.6
dipole	3-3.3	slot, guide fed	3-3.9
discone	3-3.4	slot, cavity backed	3-3.9
dual polarized sinuous	3-3.6	spiral, 4 arm conical	3-3.6
guide fed slot	3-3.9	spiral, conical	3-3.5
helix, normal mode	3-3.5	spiral, cavity backed	3-3.5
helix, axial mode	3-3.5	square loop	3-3.4
horn	3-3.7	vee	3-3.3
linear dipole array	3-3.8	yagi	3-3.8

Antenna Type	Radiation Pattern	Characteristics
MONOPOLE  	 	**Polarization: Linear** Vertical as shown **Typical Half-Power Beamwidth** 45 deg x 360 deg **Typical Gain:** 2-6 dB at best **Bandwidth:** 10% or 1.1:1 **Frequency Limit** **Lower:** None **Upper:** None **Remarks:** Polarization changes to horizontal if rotated to horizontal
λ/2 DIPOLE  	 	**Polarization**: Linear Vertical as shown **Typical Half-Power Beamwidth** 80 deg x 360 deg **Typical Gain:** 2 dB **Bandwidth:** 10% or 1.1:1 **Frequency Limit** **Lower:** None **Upper:** 8 GHz (practical limit) **Remarks:** Pattern and lobing changes significantly with L/f. Used as a gain reference < 2 GHz.

Figure 1. Monopole and Dipole Antenna Characteristics.

Antenna Type	Radiation Pattern	Characteristics
VEE  	 	**Polarization**: Linear Vertical as shown **Typical Half-Power Beamwidth** 60 deg x 60 deg **Typical Gain:** 2 to 7 dB **Bandwidth:** "Broadband" **Frequency Limit** **Lower:** 3 MHz **Upper:** 500 MHz (practical limits) **Remarks:** 24KHz versions are known to exist. Terminations may be used to reduce backlobes.
RHOMBIC  	 	**Polarization**: Linear Vertical as shown **Typical Half-Power Beamwidth** 60 deg x 60 deg **Typical Gain:** 3 dB **Bandwidth:** "Broadband" **Frequency Limit** **Lower:** 3 MHz **Upper:** 500 MHz **Remarks:** Termination resistance used to reduce backlobes.

Figure 2. Vee and Rhombic Antenna Characteristics.

Antenna Type	Radiation Pattern	Characteristics
CIRCULAR LOOP (Small)  	 Elevation: Z Y Azimuth: Y X	**Polarization:** Linear Horizontal as shown **Typical Half-Power Beamwidth:** 80 deg x 360 deg **Typical Gain:** -2 to 2 dB **Bandwidth:** 10% or 1.1:1 **Frequency Limit:** **Lower:** 50 MHz **Upper:** 1 GHz
SQUARE LOOP (Small)  	 Elevation: Z Y Azimuth: Y X	**Polarization:** Linear Horizontal as shown **Typical Half-Power Beamwidth:** 100 deg x 360 deg **Typical Gain:** 1-3 dB **Bandwidth:** 10% or 1.1:1 **Frequency Limit:** **Lower:** 50 MHz **Upper:** 1 GHz

Figure 3. Circular Loop and Square Loop Antenna Characteristics.

Antenna Type	Radiation Pattern	Characteristics
DISCONE  	 Elevation: Z Y Azimuth: Y X	**Polarization:** Linear Vertical as shown **Typical Half-Power Beamwidth:** 20-80 deg x 360 deg **Typical Gain:** 0-4 dB **Bandwidth:** 100% or 3:1 **Frequency Limit:** **Lower:** 30 MHz **Upper:** 3 GHz
ALFORD LOOP  	 Elevation: Z Y Azimuth: Y X	**Polarization:** Linear Horizontal as shown **Typical Half-Power Beamwidth:** 80 deg x 360 deg **Typical Gain:** -1 dB **Bandwidth:** 67% or 2:1 **Frequency Limit:** **Lower:** 100 MHz **Upper:** 12 GHz

Figure 4. Discone and Alford Loop Antenna Characteristics.

Antenna Type	Radiation Pattern	Characteristics
AXIAL MODE HELIX 		**Polarization:** Circular Left hand as shown **Typical Half-Power Beamwidth:** 50 deg x 50 deg **Typical Gain:** 10 dB **Bandwidth:** 52% or 1.7:1 **Frequency Limit** **Lower:** 100 MHz **Upper:** 3 GHz **Remarks:** Number of loops >3
NORMAL MODE HELIX 		**Polarization:** Circular - with an ideal pitch to diameter ratio. **Typical Half-Power Beamwidth:** 60 deg x 360 deg **Typical Gain:** 0 dB **Bandwidth:** 5% or 1.05:1 **Frequency Limit** **Lower:** 100 MHz **Upper:** 3 GHz

Figure 5. Axial Mode Helix and Normal Mode Helix Antenna Characteristics.

Antenna Type	Radiation Pattern	Characteristics
CAVITY BACKED SPIRAL (Flat Helix) 		**Polarization:** Circular Left hand as shown **Typical Half-Power Beamwidth:** 60 deg x 90 deg **Typical Gain:** 2-4 dB **Bandwidth:** 160% or 9:1 **Frequency Limit:** **Lower:** 500 MHz **Upper:** 18 GHz
CONICAL SPIRAL 		**Polarization:** Circular Left hand as shown **Typical Half-Power Beamwidth:** 60 deg x 60 deg **Typical Gain:** 5-8 dB **Bandwidth:** 120% or 4:1 **Frequency Limit:** **Lower:** 50 MHz **Upper:** 18 GHz

Figure 6. Cavity Backed Spiral and Conical Spiral Antenna Characteristics.

Antenna Type	Radiation Pattern	Characteristics
4 ARM CONICAL SPIRAL 		**Polarization:** Circular Left hand as shown **Typical Half-Power Beamwidth:** 50 deg x 360 deg **Typical Gain:** 0 dB **Bandwidth:** 120% or 4:1 **Frequency Limit:** **Lower:** 500 MHz **Upper:** 18 GHz
DUAL POLARIZED SINUOUS 		**Polarization**: Dual vertical or horizontal or dual Circular right hand or left hand with hybrid **Typical Half-Power Beamwidth:** 75 deg x 75 deg **Typical Gain:** 2 dB **Bandwidth:** 163% or 10:1 **Frequency Limit:** **Lower:** 500 MHz **Upper:** 18 GHz

Figure 7. Dual Polarized Sinuous Antenna Characteristics and 4 Arm Conical Spiral.

Antenna Type	Radiation Pattern	Characteristics
BICONICAL 		**Polarization:** Linear, Vertical as shown **Typical Half-Power Beamwidth:** 20-100 deg x 360 deg **Typical Gain:** 0-4 dB **Bandwidth:** 120% or 4:1 **Frequency Limit:** **Lower:** 500 MHz **Upper:** 40 GHz
BICONICAL W/POLARIZER 		**Polarization:** Circular, Direction depends on polarization **Typical Half-Power Beamwidth:** 20-100 deg x 360 deg **Typical Gain:** -3 to 1 dB **Bandwidth:** 100% or 3:1 **Frequency Limit:** **Lower:** 2 GHz **Upper:** 18 GHz

Figure 8. Biconical and Biconical With Polarizer Antenna Characteristics.

Antenna Type	Radiation Pattern	Characteristics
HORN 	 Z Elevation: Y 3 dB beamwidth = 56 λ/dz  3 dB beamwidth = 70 λ/dx	**Polarization:** Linear **Typical Half-Power Beamwidth:** 40 deg x 40 deg **Typical Gain:** 5 to 20 dB **Bandwidth:** If ridged: 120% or 4:1 If not ridged: 67% or 2:1 **Frequency Limit:** **Lower:** 50 MHz **Upper:** 40 GHz
HORN W / POLARIZER 	 Z Elevation: Y Azimuth: Y X	**Polarization:** Circular, Depends on polarizer **Typical Half-Power Beamwidth:** 40 deg x 40 deg **Typical Gain:** 5 to 10 dB **Bandwidth:** 60% or 2:1 **Frequency Limit:** **Lower:** 2 GHz **Upper:** 18 GHz

Figure 9. Horn and Horn w/Polarizer Antenna Characteristics.

Antenna Type	Radiation Pattern	Characteristics
PARABOLIC (Prime) 	 Elevation & Azimuth Y	**Polarization:** Takes polarization of feed **Typical Half-Power Beamwidth:** 1 to 10 deg **Typical Gain:** 20 to 30 dB **Bandwidth:** 33% or 1.4:1 limited mostly by feed **Frequency Limit:** **Lower:** 400 MHz **Upper:** 13+ GHz
PARABOLIC  Gregorian Z Y Cassegrain X	 Elevation & Azimuth Y	**Polarization:** Takes polarization of feed **Typical Half-Power Beamwidth:** 1 to 10 deg **Typical Gain:** 20 to 30 dB **Bandwidth:** 33% or 1.4:1 **Frequency Limit:** **Lower:** 400 MHz **Upper:** 13+ GHz

Figure 10. Parabolic (Prime) and Parabolic Antenna Characteristics.

Antenna Type	Radiation Pattern	Characteristics
YAGI 	 Elevation: Azimuth:	**Polarization:** Linear Horizontal as shown **Typical Half-Power Beamwidth** 50 deg X 50 deg **Typical Gain:** 5 to 15 dB **Bandwidth:** 5% or 1.05:1 **Frequency Limit:** **Lower:** 50 MHz **Upper:** 2 GHz
LOG PERIODIC 	 Elevation: Azimuth:	**Polarization:** Linear **Typical Half-Power Beamwidth:** 60 deg x 80 deg **Typical Gain:** 6 to 8 dB **Bandwidth:** 163% or 10:1 **Frequency Limit:** **Lower:** 3 MHz **Upper:** 18 GHz **Remarks:** This array may be formed with many shapes including dipoles or toothed arrays.

Figure 11. Yagi and Log Periodic Antenna Characteristics.

Antenna Type	Radiation Pattern	Characteristics
LINEAR DIPOLE ARRAY (Corporate Feed) 	 Elevation: Azimuth:	**Polarization:** Element dependent Vertical as shown **Typical Half-Power Beamwidth:** Related to gain **Typical Gain:** Dependent on number of elements **Bandwidth:** Narrow **Frequency Limit:** **Lower:** 10 MHz **Upper:** 10 GHz
APERTURE SYNTHESIS 	**Elevation & Azimuth** 	All characteristics dependent on elements **Remarks:** Excellent side-looking, ground mapping where the aircraft is a moving linear element.

Figure 12. Linear Dipole Array and Aperture Synthesis Antenna Characteristics.

Antenna Type	Radiation Pattern	Characteristics
CAVITY BACKED CIRCUIT FED SLOT (and Microstrip Patch) 	Elevation & Azimuth 	**Polarization:** Linear, vertical as shown **Typical Half-Power Beamwidth**: 80 deg x 80 deg **Typical Gain:** 6 dB **Bandwidth:** Narrow **Frequency Limit:** **Lower:** 50 MHz **Upper:** 18 GHz **Remarks:** The feed line is sometimes separated from the radiator by a dialetric & uses capacititive coupling. Large conformal phased arrays can be made this way.
GUIDE FED SLOT 	Elevation:  Azimuth: 	**Polarization:** Linear, **Typical Half-Power Beamwidth** Elevation: 45-50☜ Azimuth: 80☜ **Typical Gain:** 0 dB **Bandwidth:** Narrow **Frequency Limit:** **Lower:** 2 GHz **Upper:** 40 GHz **Remarks:** Open RF Waveguide

Figure 13. Cavity Backed Circuit Fed Slot and Guide Fed Slot Antenna Characteristics.

Antenna Type	Radiation Pattern	Characteristics
CORNER REFLECTOR 	Elevation: (Z-Y) Azimuth: (X-Y) Dependent upon feed emitter	**Polarization**: Feed dependent **Typical Half-Power Beamwidth** 40 deg x variable **Typical Gain:** 10 dB above feed **Bandwidth:** Narrow **Frequency Limit** **Lower:** 1 GHz **Upper:** 40 GHz **Remarks:** Typically fed with a dipole or colinear array.
LUNEBURG LENS 	Elevation & Azimuth 	**Polarization:** Feed dependent **Typical Half-Power Beamwidth:** System dependent **Typical Gain:** System dependent **Bandwidth:** Narrow **Frequency Limit** **Lower:** 1 GHz **Upper:** 40 GHz **Remarks:** Variable index dielectric sphere.

Figure 14. Corner Reflector and Luneburg Lens Antenna Characteristics.

This page intentionally left blank.

FREQUENCY / PHASE EFFECTS OF ANTENNAS

The radiation patterns of the antennas presented in the previous section are for antenna geometries most commonly used. The antenna should be viewed as a matching network that takes the power from a transmission line (50 ohm, for example), and matches it to the free space "impedance" of 377 ohms. The most critical parameter is the change of VSWR with frequency. The pattern usually does not vary much from acceptable to the start of unacceptable VSWRs (> 2:1). For a given physical antenna geometric size, the actual radiation pattern varies with frequency.

The antenna pattern depicted in Figure 1 is for the dipole pictured in Section 3-3. The maximum gain is normalized to the outside of the polar plot and the major divisions correspond to 10 dB change. In this example, the dipole length (in wavelengths) is varied, but the same result can be obtained by changing frequency with a fixed dipole length. From the figure, it can be seen that side lobes start to form at 1.25λ and the side lobe actually has more gain than the main beam at 1.5λ. Since the radiation pattern changes with frequency, the gain also changes.



Figure 1. Frequency Effects.

Figure 2 depicts phase/array effects, which are yet another method for obtaining varied radiation patterns. In the figure, parallel dipoles are viewed from the end. It can be seen that varying the phase of the two transmissions can cause the direction of the radiation pattern to change. This is the concept behind phased array antennas. Instead of having a system mechanically sweeping the direction of the antenna through space, the phase of radiating components is varied electronically, producing a moving pattern with no moving parts. It can also be seen that increasing the number of elements further increases the directivity of the array. In an array, the pattern does vary considerably with frequency due to element spacing (measured in wavelengths) and the frequency sensitivity of the phase shifting networks.



Utilizing these techniques, a phased array antenna can be constructed by simply electronically varying the phase in a progressive repetitive manner in order to create a specific scan pattern.

Figure 2. Phase / Array Effects*.

* Note: Assuming Figure 2 depicts x-y plane antenna pattern cross section, to achieve the indicated array patterns using dipole antennas, the dipole antenna elements must be aligned with the z-axis.

Two antennas that warrant special consideration are the phased array and the Rotman bootlace type lens. Both of these antennas find wide application in EW, RADAR, and Communications. The phased array will be described first.

LINEAR PHASED ARRAY

The linear phased array with equal spaced elements is easiest to analyze and forms the basis for most array designs. Figure 3 schematically illustrates a corporate feed linear array with element spacing d.



Figure 3. Corporate Fed Phased Array.

It is the simplest and is still widely used. By controlling the phase and amplitude of excitation to each element, as depicted, we can control the direction and shape of the beam radiated by the array. The phase excitation, $\varphi(n)$, controls the beam pointing angle, θ_o, in a phased array. To produce a broadside beam, $\theta_o=0$, requires phase excitation, $\varphi(n)=0$. Other scan angles require an excitation, $\varphi(n) = nkd \sin(\theta_o)$, for the nth element where k is the wave number ($2\pi/\lambda$). In this manner a linear phased array can radiate a beam in any scan direction, θ_o, provided the element pattern has sufficient beamwidth. The amplitude excitation, A_n, can be used to control beam shape and sidelobe levels. Often the amplitude excitation is tapered in a manner similar to that used for aperture antennas to reduce the sidelobe levels. One of the problems that can arise with a phased array is insufficient bandwidth, since the phase shift usually is not obtained through the introduction of additional path length. However, it should be noted that at broadside the corporate feed does have equal path length and would have good bandwidth for this scan angle.



Figure 4. Beam Distortion.

The linear array described above would yield a narrow fan beam in the plane normal to the plane containing the array and scan direction, with the narrow beamwidth in the plane of the array. To obtain a pencil beam it would be necessary to array several of these linear arrays in such a manner resulting in a planar array of radiating elements. A problem associated with all electronic scanning is beam distortion with scan angle. Figure 4 illustrates this phenomenon. It results in spread of the beam shape with a concomitant reduction in gain. This effect is known as "scan loss." For an ideal array element, scan loss is equal to the reduction in aperture size in the scan direction which varies as cos θ, where θ is the scan angle measured from the planar array normal.

When elements are spaced greater than $\lambda/2$ apart, grating lobes are possible when scanning. As the beam is scanned further from broadside, a point is reached at which a second symmetrical main lobe is developed at the negative scan angle from broadside. This condition is not wanted because antenna gain is immediately reduced by 3 dB due to the second lobe. Grating lobes are a significant problem in EW applications because the broad frequency bandwidth requirements mean that at the high end of the frequency band, the elements may be spaced greater than $\lambda/2$. Therefore in order to avoid grating lobes over a large frequency bandwidth, element spacing must be no greater than $\lambda/2$ at the highest frequency of operation.

There are many other factors to consider with a phased array such as coning, where the beam curves at large scan angles, and mutual coupling between elements that affect match and excitation. Excessive mutual coupling will invariably result in blind scan angles where radiation is greatly attenuated. These issues will not be covered in detail here.

Of interest is the gain of the array which is given by:

$$Array\ Gain = G_e(\theta) \bullet \sum_{n=1}^{N} A(n)\, e^{j\phi(n)}\, e^{j\,n\,k\,d\sin\theta}$$ Where each element is as described in Section 3-4.

$G_e(\theta)$ is the element gain which in this case has been taken the same for all elements. Note that if we set A(n)=1, and φ(n)=0, then at broadside where sin(θ) = 0, the gain would be (N G_e). This represents the maximum gain of the array, which typically will not exceed nπ, and is a familiar figure. It should be noted that in practical array design, the element pattern characteristics are greatly influenced by mutual coupling and that the characteristic of elements at the edge of the array can deviate significantly from those near the center.

ROTMAN BOOTLACE LENS



Figure 5. Rotman Bootlace Lens.

Another method of feeding an array of elements is to use a lens such as the Rotman (rhymes with rotten) Bootlace type shown in Figure 5. The lens consists of a parallel plate region (nowadays microstrip or stripline construction) and cables of specified length connecting the array of elements to the parallel plate region. The geometry of the lens and the cable lengths are designed so that all ray paths traced from a beam port on the right side to its associated wavefront on the left array port side, are equal. This tailoring of the design is accomplished at three focus points (beam ports 1, 4, and 7 in Figure 5). Departure from perfect focus at intermediate beam ports is negligible in most designs.

The Rotman lens provides both true time delay phase shift and amplitude taper in one lens component. The true time delay is one of the distinct advantages of the lens over the phase shifted array since that makes it independent of frequency. To understand how the taper is obtained requires knowledge of the parallel plate region. For a stripline design the unit would consist of a large flat plate-like center conductor sandwiched between two ground planes, and having a shape much like that of the plan view outline shown in Figure 5 with individual tapered launchers (connectors) attached to each beam port and array port. If the antenna is in the receive mode, the energy intercepted on the array port side can be controlled by the angle subtended by the tapered sections of the connector (launcher) much like a larger antenna would intercept a larger portion of energy from free space.

Unlike the phased array with its fine beam steering, the Rotman lens provides only a distinct set of beams. Fine steering is obtained by combining beams either equally or unequally to form intermediate beams. As can be seen in Figure 6, this results in a broader beam with less gain but lower side lobes than the primary beams.

High transmit power can be obtained using a Rotman lens by placing a low power amplifier between each lens output port and its antenna. In this case a separate Rotman lens would have to be used for receiving.



Figure 6. Primary and Intermediate Beam Formation in Lens Arrays.

This page intentionally left blank.

ANTENNA NEAR FIELD

As noted in the sections on RF propagation and the radar equation, electromagnetic radiation expands spherically (Figure 1) and the power density at a long range (R) from the transmitting antenna is:

$$P_D = \frac{P_t G_t}{4\pi R^2} \qquad \textbf{[1]}$$

When the range is large, the spherical surface of uniform power density appears flat to a receiving antenna which is very small compared to the surface of the sphere. This is why the far field wave front is considered planar and the rays approximately parallel. Also, it is apparent that at some shorter range, the spherical surface no longer appears flat, even to a very small receiving antenna.

The planer, parallel ray approximation is valid for distances greater than the distance where the phase error is 1/16 of a wavelength or 22.5 degrees. This distance is given by

$R_{ff} = \frac{2D^2}{\lambda}$ where λ is the wavelength and D is the largest dimension of the transmit antenna. **[2]**

Antenna measurements made at distances greater than R_{ff} generally result in negligible pattern error. Distances less than R_{ff} is termed the near-field.

If the same size antenna is used for multiple frequencies, R_{ff} will increase with increasing frequency. However, if various size antennas are used for different frequencies and each antenna is designed with D as a function of λ ($\lambda/2$ to 100λ), then R_{ff} will vary from $c/2f$ to $20000c/f$. In this case R_{ff} will decrease with increasing frequency. For example: a 10λ antenna at 3 GHZ has a D of 100 cm and corresponding R_{ff} of 20 m, while a 10λ antenna at 30 GHz has a D of 10 cm and corresponding R_{ff} of 2 m.

While the above analogy provides an image of the difference between the near and far fields, the relationship must be defined as a characteristic of the transmitting antenna.

Actual antennas, of course, are not ideal point source radiators but have physical dimensions. If the transmitting antenna placed at the origin of Figure 1 occupies distance D along the Z-axis and is boresighted along the Y-axis ($\varphi = 90$), then the geometry of point P on the sphere is represented in two dimensions by Figure 2. For convenience, the antenna is represented by a series of point sources in an array.



Figure 1. Spherical Radiation to Point "P" from an Ideal Point Source.

When point P is close to the antenna, as in Figure 2, then the difference in distance of the two rays r and R taken respectively from the center of the antenna and the outer edge of the antenna varies as point P changes.

Derivation of equation [2] is given as follows:

From Figure 2, the following applies:

$r^2 = z^2 + y^2$ **[3]**

$z = r \cos \theta$ **[4]**

$y = r \sin \theta$ and **[5]**



Figure 2. Near Field Geometry of Point "P" for a Non-Ideal Radiator With Dimension D.

$$R = \sqrt{y^2 + (z - z')^2} = \sqrt{y^2 + z^2 - 2z'z + (z')^2} \qquad \textbf{[6]}$$

Substituting [3] and [4] into [6] $R = \sqrt{r^2 + [-2(r \cos \theta) z' + (z')^2]}$ **[7]**
which puts point P into spherical coordinates.

Equation [7] can be expanded by the binomial theorem which for the first three terms, reduces to:

$$R = r - z' \cos \theta + \frac{(z')^2 \sin^2 \theta}{2r} + \ldots\ldots \qquad \textbf{[8]}$$

In the parallel ray approximation for far field calculations (Figure 3) the third term of [8] is neglected.

The distance where the far field begins (R_{ff}) (or where the near field ends) is the value of r when the error in R due to neglecting the third term of equation [8], equals 1/16 of a wavelength.

R_{ff} is usually calculated on boresight, so θ = 90° and the second term of equation [8] equals zero (Cos 90° = 0), therefore from Figure 3, where D is the antenna dimension, R_{ff} is found by equating the third term of [8] to 1/16 wavelength.

$$\frac{(z')^2 \sin^2 \theta}{2 R_{ff}} = \frac{\lambda}{16}$$

$\text{Sin}\,\theta = \text{Sin}\, 90 = 1 \text{ and } z' = D/2$ so: $\dfrac{\left(\frac{D}{2}\right)^2}{2 R_{ff}} = \dfrac{\lambda}{16}$

$$R_{ff} = \frac{16 (D/2)^2}{2\lambda} = \frac{2 D^2}{\lambda} \qquad \textbf{[9]}$$

Equation [9] is the standard calculation of far field given in all references.

Besides [9] some general rules of thumb for far field conditions are:

$$r >> D \quad \text{or} \quad r >> \lambda$$

If the sphere and point P are a very great distance from the antenna, then the rays are very nearly parallel and this difference is small as in Figure 3.



Figure 3. Far Field Parallel Ray Approximation for Calculations.

For reference purposes, a simplified alternative method to derive minimum far field distance approximation for an antenna or an antenna array with aperture size "d" is presented in Figure 4 without the need to resort to the spherical coordinate system and the Binomial Theorem. This approach illustrates a simple application of the Pythagorean Theorem. The P_{FF} symbol represents an arbitrary point in the far field at antenna boresight. Refer to relevant quantities shown in Figure 4.



Figure 4. Alternative Geometry for Far Field Estimation.

From Figure 4, the distance “r” is the maximum propagation path difference across a given antenna aperture endpoint locations. Expressing this propagation path difference in terms of a wavelength provides means to derive an equation for generalized far field range relationship. Note a slight change of notation between Figures 3 and 4. A derivation of results already shown in Equations [2] & [9] is given as follows. From Figure 4, the following applies:

$$(R + r)^2 = (d/2)^2 + R^2 \qquad \textbf{[10]}$$

Collecting terms and cancelling,

$$2Rr + r^2 = d^2/4 \qquad \textbf{[11]}$$

Simplifying with a noted valid assumption,

$$2Rr \approx d^2/4, \text{ since } r << R \qquad \textbf{[12]}$$

Solving for “r” (see Figure 4)

$$r \approx d^2/(8R) \qquad \textbf{[13]}$$

For far field condition assume $r \leq \lambda/16$. Substituting “r” in terms of lambda,

$$\lambda/16 \geq r \approx d^2/(8R) \;\rightarrow\; P_{FF} \geq 2d^2/\lambda \qquad \textbf{[14]}$$

As shown, Equation [14] represents the same result as Equation [9] derived earlier.

The power density within the near field varies as a function of the type of aperture illumination and is less than would be calculated by equation [1]. Thus, in the antenna near field there is stored energy. (The complex radiation field equations have imaginary terms indicating reactive power.) Figure 5 shows normalized power density for three different illuminations.

Curve A is for reference only and shows how power density would vary if it were calculated using equation [1].

Curve B shows power density variations on axis for an antenna aperture with a cosine amplitude distribution. This is typical of a horn antenna in the H-plane.

Curve C shows power density variations on axis for a uniformly illuminated antenna aperture or for a line source. This is typical of a horn antenna in the E-plane.

Curve D shows power density variations on axis for an antenna aperture with a tapered illumination. Generally the edge illumination is approximately -10 dB from the center illumination and is typical of a parabolic dish antenna.

Point E For radiation safety purposes, a general rule of thumb for tapered illumination is that the maximum safe level of 10 mW/cm^2 (~200 V/m) is reached in the near field if the level at R_{ff} reaches 0.242 mW/cm^2 as can be verified by computing the power density at point E in Figure 5. (10 mW/cm^2 at point E extrapolates to 0.242 mW/cm^2 [16 dB lower] at $R=R_{ff}$, or Y axis value =1). Figure 1 in Section 3-6 depicts more precise values for radiation hazard exposure.

Point F Far Field Point. At distances closer to the source than this point (near field), the power density from any given antenna is less than that predicted using Curve A. At farther distances, (far field) power densities from all types of antennas are the same.



Points are as defined in the preceeding paragraph.

The near field is the area "above" Point F, i.e. Y < 1.0

Power density above Point F increases by the dB value specified on the X axis.

The Y axis specifies range (normalized).

Figure 5. Antenna Near-Field On-Axis Power Density (Normalized) for Various Aperture Illuminations.

FOR FAR FIELD MEASUREMENTS:


ONE WAY SIGNAL STRENGTH (S)
S
6 dB
(1/4 pwr)
S decreases by 6 dB
when the distance doubles
2R
R
6 dB
(4x pwr)
S
S increases by 6 dB
when the distance is half
R
0.5 R


TWO WAY SIGNAL STRENGTH (S)
S
12 dB
(1/16 pwr)
S decreases by 12 dB
when the distance doubles
2R
R
12 dB
(16x pwr)
S
S increases by 12 dB
when the distance is half
R
0.5 R

When free space measurements are performed at a known distance from a source, it is often necessary to know if the measurements are being performed in the far field. As can be seen from Curve A on Figure 5, if the distance is halved (going from 1.0 to 0.5 on the Y axis), the power density will increase by 6 dB (going from 0 to 6 dB on the X axis). Each reduction in range by ½ results in further 6 dB increases. As previously mentioned, Curve A is drawn for reference only in the near field region, since at distances less than R_{ff} the power density increases less than 6 dB when the range is halved. In the far field, all curves converge and Equation [1] applies.

When a measurement is made in free space, a good check to ensure that is was performed in the far field is to repeat the measurement at twice the distance. The power should decrease by exactly 6 dB. A common error is to use 3 dB (the half power point) for comparison. Conversely, the power measurement can be repeated at half the distance, in which case you would look for a 6 dB increase, however the assumed extrapolation conclusion is not as certain, because the first measurement could have been made in the far field, and the second could have been made in the near field.

Care must be exercised in using the $\mathbf{2d^2/\lambda}$ far field measurement criterion. For antennas with moderate sidelobe levels (>-25 dB) pattern errors are negligible and the error in directivity is less than 0.1 dB and this measurement distance suffices in most cases. However low sidelobe antennas require longer measurement distances. For example, maintaining a 1 dB or less sidelobe error for a linear array with a -40 dB sidelobe level requires a measurement distance of $6d^2/\lambda$. (1). This corresponds to criterion for "r" in Equation [14] to be changed from $r \leq \lambda/16$ to $r \leq \lambda/48$ or 7.5 deg.

[1] R. C. Hansen. "Measurement Distance Effects on Low Sidelobe Patterns," *IEEE Transactions on Antennas and Propagation*, Vol. AP-32, No. 6, June 1984.

RADIATION HAZARDS

Radiation Hazard (RADHAZ) describes the hazards of electromagnetic radiation to fuels, electronic hardware, ordnance, and personnel. In the military these hazards are segregated as follows:

1) Hazards of Electromagnetic Radiation to Personnel (HERP)
2) Hazards of Electromagnetic Radiation to Ordnance (HERO)
3) Hazards of Electromagnetic Radiation to Fuel (HERF)

The current industrial specifications for RADHAZ are contained in ANSI/IEEE C95.1-1992 which was used as a reference to create the combined Navy regulation NAVSEA OP3565 / NAVAIR 16-1-529. Volume I contains HERP and HERF limits - its current version is REV 5. Volume II (REV 6) covers HERO. These limits are shown in Figure 1 although all values have been converted to average power density.

OP 3565 specifies HERO RADHAZ levels at frequencies below 1 GHz in peak value of electric field strength (V/m), while levels above 200 MHz are specified in average power density (mW/cm^2) - note the overlapping frequencies. Since Figure 1 depicts power density as the limits, you must convert the average values to peak field strength for use at lower frequencies. Also many applications of EMC work such as MIL-STD-461 use limits based on the electric (E) field strength in volts/meter. Remember that $P=E^2/R$, and from Section 4-2, we note that $R=377\Omega$ for free space. It can also be shown that the magnetic field strength (H field in Amps/meter) = I/m where I=E/R. Don't forget that RMS = 0.707 Peak. With the units of P_D in mW/cm^2, E in V/m, and H in A/m, then P_D (mW/cm^2) = E^2 / 3770 = 37.7 H^2. It should thus be noted that a 100 times increase in power (mW/cm^2) is only a 10 times increase in V/m.



Figure 1. Radiation Hazards to Personnel and Ordnance.

The potential dangers to ordnance and fuels are obvious because there could be an explosive "chain reaction" by exploding; consequently, these limits are generally lower than personnel limits. There are three **HERO** categories. The HERO limit 2 is for HERO "unsafe" or "unreliable" explosive devices with exposed wires arranged in optimum (most susceptible) receiving orientation. This usually occurs during the assembly/disassembly of ordnance, but also applies to new/untested ordnance until proven "safe" or "susceptible." The HERO limit 1 is for HERO susceptible ordnance fully assembled undergoing normal handling and loading operations. HERO safe ordnance requires no RF radiation precautions. A list of which specific ordnance (by NALC) falls into each category can be found in OP 3565 along with specific frequency restrictions for each piece of ordnance. For example, all missiles of one variety are susceptible

(HERO 1 limits), while another missile has both susceptible and safe variants (with no RADHAZ limits). Other ordnance may be HERO unsafe (HERO 2 limits).

The danger of **HERP** occurs because the body absorbs radiation and significant internal heating may occur without the individual's knowledge because the body does not have internal sensation of heat, and tissue damage may occur before the excess heat can be dissipated. As shown in Figure 1, the current "restricted" limit is for individuals more than 55" tall because they have more body mass. In other words, all people may be exposed to the lower limit, but only persons taller than 55" may be exposed to the higher limit of 10 mW/cm^2.

NAVSEA OP 3565 will be updated in the future to be compatible with DoD INST 6055.11 dated Feb 21, 1995 which supersedes it. The personnel radiation levels in Figures 2 and 3 were taken from the new release of DoD INST 6055.11.



Figure 2. Lower Frequency HERP from DoD INST 6055.11.

Unlike the existing "restricted limit" of NAVSEA OP 3565 discussed above, in the revised DoD instruction for personnel radiation hazards, a different approach to exposure was taken.



Figure 3. Radiation Hazards to Personnel from DoD INST 6055.11.

Two maximum hazard limits are defined;

1) Controlled Environments - where personnel are aware of the potential danger of RF exposure concurrently with employment, or exposure which may occur due to incidental transient passage through an area, and;
2) Uncontrolled Environments - A lower maximum level where there is no expectation that higher levels should be encountered, such as living quarters.

These Personnel Exposure Limits (PELs) are based on a safety factor of ten times the Specific Absorption Rate (SAR) which might cause bodily harm. The term PEL is equivalent to the terms "Maximum Permissible Exposure (MPE)" and "Radio Frequency Protection Guides (RFPG)" in other publications.

There are several exceptions to the max limits in Figs 2 and 3 (in some cases higher levels are permitted):

- High Power Microwave (HPM) system exposure in a controlled environment, which has a single pulse or multiple pulses lasting less than 10 seconds, has a higher peak E-Field limit of 200 kV/m.
- EMP Simulation Systems in a controlled environment for personnel who are exposed to broad-band (0.1 MHz to 300 GHz) RF are limited to a higher peak E-Field of 100 kV/m.
- The given limits are also increased for pulsed RF fields. In this case the peak power density per pulse for pulse durations < 100 msec and no more than 5 pulses in the period is increased to: PELPulse = PEL x TAVG / 5 x Pulse Width, and the peak E-field is increased to 100 kV/m. If there are more than 5 pulses or they are greater than 100 msec, a time averaged PD should not exceed that shown in Figure 3.
- A rotating or scanning beam likewise reduces the hazard, so although an on-axis hazard might exist, there may be none with a moving beam. The power density may be approximated with:
  PDscan = PDfixed (2 x Beam Width / scan angle)
- Many other special limitations also apply, such as higher limits for partial body exposure, so if in doubt, read the DoD Inst 6055.11 in detail. Field measurements may be measured in accordance with IEEE C95.3-1991.

The PELs listed in Figures 2 and 3 were selected for an average RF exposure time at various frequencies. In a controlled environment, this averaging time was selected as 6 minutes for 0.003 to 15,000 MHz. If the exposure time is less than 6 minutes, then the level may be increased accordingly. Similar time weighted averages apply to uncontrolled environments, but it varies enough with frequency such that DoD INST 6055.11 should be consulted.

NAVSEA OP 3565 contains a list of Navy avionics which transmit RF as well as radars along with their respective hazard patterns. Special training is required for individuals who work in areas which emit RF levels which exceed the uncontrolled levels. Warning signs are also required in areas which exceed either the controlled or uncontrolled limits.

Although E-Field, H-Field, and power density can be mathematically converted in a far-field plane wave environment, the relations provided earlier do not apply in the near field, consequently the E- or H-field strength must be measured independently below 100 MHz. It should be noted that the specifications in NAVSEA OP 3565 for lower frequency HERO limits are listed as peak E-field values, whereas lower RF limits in DoD INST 6055.11 on HERP are in average (RMS) E-field values. Upper frequency restrictions are based on average (RMS) values of power density in both regulations except for certain circumstances.

HERF precautions are of more general concern to fuel truck operators. However, some general guidelines include:

- Do not energize a transmitter (radar/comm) on an aircraft or motor vehicle being fueled or on an adjacent aircraft or vehicle.
- Do not make or break any electrical, ground wire, or tie down connector while fueling.
- Radars able to illuminate fueling areas with a peak power density of 5 W/cm2 should be shut off.
- For shore stations, antennas radiating 250 watts or less should be installed at least 50 ft from fueling areas (at sea 500 watts is the relaxed requirement).
- For antennas which radiate more than 250 watts, the power density at 50 ft from the fueling operation should not be greater than the equivalent power density of a 250 watt transmitter at 50 ft.

ACTIVE ELECTRONICALLY SCANNED ARRAYS (AESA)

Scanning phased arrays employing electronically controlled phase shifters (e.g., PiN diode, ferrite) have been used in high power radar applications since the early 1960s. These are planar arrays and generally use a corporate type feed structure to array rows of elements in one dimension of the array and use an analogous feed to array the rows in the orthogonal dimension of the array, resulting in a single feed point. A high power RF transmitter, usually employing some sort of liquid cooling, is used to excite the array. This architecture is cumbersome and difficult to package and the high power transmitter is a single point of failure for the system.

The maturation of solid state transmit/receive modules (T/R) using Gallium Arsenide (GaAs) technology or more recently Gallium Nitride (GaN) technology has made AESAs a practical reality. The T/R modules consist of a low noise amplifier (LNA) for the receive function and a solid state high power amplifier (SSPA) for realization of the transmit function. The T/R module may also contain the necessary phase control elements for beam scanning. A generic 8-element AESA for one dimension is shown in Figure 1.



Figure 1. Eight Element AESA.

Electronically scanned phased array designs with decade bandwidths have been reported in the open literature for many years. However those reported are only lab versions and none have been implemented in a fielded system. In addition, the high average power requirement, particularly for EW systems, calls for the use of GaN SSPA technology and this, in conjunction with the dense array packaging requirement, poses severe heat dissipation/cooling issues.

AESAs for EW applications impose design considerations vastly different from an AESA for radar. In contradistinction with high **peak** power radar applications (e.g., AN/APG79), the high **average** power large duty factors (sometimes CW) requirements for EW impose severe design requirements and constraints for the wide bandwidth AESA. Incorporation of an AESA in airborne environment, with its concomitant restrictive volume, further exacerbates design constraints.

The heat dissipation problem is of major concern in modern high power AESAs. Due to the behavior of microwave transistor amplifiers, the power added efficiency (PAE) of a TR module transmitter is typically a relatively small fraction of the total prime power consumption. As a result, an AESA will dissipate a lot of heat, which must be extracted. The reliability of GaAs and GaN MMIC chips improves if the RF amplifier system operates at reduced temperatures. Traditional air cooling used in most established avionic hardware is ill suited to the high packaging density of an AESA. As a result modern AESAs are predominantly liquid cooled. A typical liquid cooling system will use pumps to drive the coolant through channels in the cooling plenum of the array, and then route it to a heat exchanger. In comparison, with a conventional air cooled fighter radar, the AESA will be more reliable but will require more electrical power and more cooling infrastructure, and typically can produce much higher average transmit power.

ADVANTAGES OF AESA RADIATORS

AESAs add many capabilities of their own to those of the Passive Electronically Steered Array (PESAs). Among these are: the ability to form multiple beams, to scan without mechanical steering, to use each transmit/receive module for different roles concurrently, like radar detection, and, more importantly, their multiple wave and scanning frequencies create multiple difficulties for traditional, correlation-type radar detectors.

LOW PROBABILITY OF INTERCEPT

Radar systems work by sending out a signal and then listening for its echo off distant objects. Each of these paths, to and from the target, is subject to the inverse square law of propagation. That means that a radar's received energy drops with the fourth power of distance, which is why radar systems require high powers, often in the megawatt range, to be effective at long range.

The radar signal being sent out is a simple radio signal, and can be received with a simple radio receiver. It is common to use such a receiver in the targets, normally aircraft, to detect radar broadcasts. Unlike the radar unit, which must send the pulse out and then receive its reflection, the target's receiver does not need the reflection and thus the signal drops off only as the square of distance. This means that the receiver is always at an advantage over the radar in terms of range. It will always be able to detect the signal long before the radar can see the target's echo. Since the position of the radar is extremely useful information in an attack on that platform, this means that radars generally must be turned off for lengthy periods if they are subject to attack; this is common on ships, for instance.

Turning that received signal into a useful display is the purpose of the RWR. Unlike the radar, which knows which direction it is sending its signal, the receiver simply gets a pulse of energy and has to interpret it. Since the radio spectrum is filled with noise, the receiver's signal is integrated over a short period of time, making periodic sources like a radar add up and stand out over the random background. Typically RWRs store the detected pulses for a short period of time, and compare their broadcast frequency and pulse repetition frequency against a database of known radars. The rough direction can be calculated using a rotating antenna, or similar passive array, and combined with symbology indicating the likely purpose of the radar - airborne early warning, surface to air missile, etc.

This technique is much less useful against AESA radars. Since the AESA can change its frequency with every pulse, and generally does so using a pseudo-random sequence, integrating over time does not help pull the signal out of the background noise. Nor does the AESA have any sort of fixed pulse repetition frequency, which can also be varied and thus hide any periodic brightening across the entire spectrum. Traditional RWRs suffered significantly decreased effectiveness against AESA radars.

HIGH JAMMING RESISTANCE

Jamming is likewise much more difficult against an AESA. Traditionally, jammers have operated by determining the operating frequency of the radar and then broadcasting a signal on it to confuse the receiver as to which is the “real” pulse and which is the jammer’s. This technique works as long as the radar system cannot easily change its operating frequency. When the transmitters were based on klystron tubes this was generally true, and radars, especially airborne ones, had only a few frequencies to choose among. A jammer could listen to those possible frequencies and select the one to be used to jam.

Since an AESA could change its operating frequency with every pulse, and spread the frequencies across a wide band even in a single pulse, jammers are much less effective. Although it is possible to send out broadband white noise against all the possible frequencies, this means the amount of energy being sent at any one frequency is much lower, reducing its effectiveness. In fact, AESAs can then be switched to a receive-only mode, and use these powerful jamming signals instead to track its source, something that required a separate receiver in older platforms.

AESA radars can be much more difficult to detect, and so much more useful in receiving signals from the targets, that they can broadcast continually and still have a very low chance of being detected. This allows such radar systems to generate far more data than traditional radar systems, which can only receive data periodically, greatly improving overall system effectiveness.

OTHER ADVANTAGES

Since each element in an AESA is a powerful radio receiver, active arrays have many roles besides traditional radar. One use is to dedicate several of the elements to reception of common radar signals, eliminating the need for a separate radar warning receiver. The same basic concept can be used to provide traditional radio support, and with some elements also broadcasting, form a very high bandwidth data link.

AESAs are also much more reliable than either a PESA or older designs. Since each module operates independently of the others, single failures have little effect on the operation of the system as a whole. Additionally, the modules individually operate at lower powers and voltages so the need for a large high-voltage power supply is eliminated.

Replacing a mechanically scanned array with a fixed AESA mount can help reduce an aircraft’s overall RCS, but some designs (such as the Eurofighter Typhoon) forgo this advantage in order to combine mechanical scanning with electronic scanning and provide a wider angle of total coverage.

This page intentionally left blank.

FRACTAL ANTENNAS

The term fractal, which means broken or irregular fragments, was originally coined by B.B. Mandelbrot **[1]** to describe a family of complex shapes that possess self-similarity in their geometrical structure. In-depth studies of the patterns of nature provided inspiration for the development of fractal geometry where it has been used to model numerous natural objects. Recent advances in the antenna art have led to the application of fractal geometry instead of convention Euclidean geometric concepts to the design of wide bandwidth, low profile, compact antennas.

A fractal antenna is an antenna that uses a fractal, self-similar design to maximize the length, or increase the perimeter (on inside sections or the outer structure), of material that can receive or transmit electromagnetic radiation within a given total surface area or volume. The earliest published reference to use of the term fractal radiators and fractal antennas to refer to fractal shaped antenna elements appeared May 1994 **[2]**.

Such fractal antennas are also referred to as multilevel and space filling curves, but the key aspect lies in their repetition of a motif over two or more scale sizes, or "iterations." For this reason, fractal antennas are very compact, multiband or wideband, and have useful applications in many commercial and military systems.

A good example of a fractal antenna as a space-filling curve is in the form of a Minkowski Island (Figure 1). Here, each line of copper is just a small fraction of a wavelength **[3]**.

A fractal antenna's response differs markedly from traditional antenna designs, in that it is capable of operating with good-to-excellent performance at many different frequencies simultaneously. Normally standard antennas have to be "cut" for the frequency for which they are to be used — and thus the standard antennas only work well at that frequency. This makes the fractal antenna an excellent design for wideband and multiband applications.



Figure 1. An Example of a Fractal Antenna: a Space-Filling Curve Called a Minkowski Island.

Antenna elements (as opposed to antenna arrays) made from self-similar shapes were first created by Nathan Cohen, then a professor at Boston University, starting in 1995 **[4]**. Cohen's efforts with a variety of fractal antenna designs were first published in 1995 (thus the first scientific publication on fractal antennas), and a number of patents have been issued from the 1995 filing priority of invention. Most allusions to fractal antennas make reference to these "fractal element antennas."

Many fractal element antennas use the fractal structure as a virtual combination of capacitors and inductors. This makes the antenna have so that it has many different resonances that can be selected and adjusted by choosing the proper fractal design. Electrical resonances may not be directly related to a particular scale size of the fractal antenna structure. The physical size of the antenna is unrelated to its resonant or broadband performance. The general rule of antenna length being near target frequency wavelength does not apply itself in the same way with fractal antennas.

This complexity arises because the current on the structure has a complex arrangement caused by the inductance and self capacitance. In general, although their effective electrical length is longer, the fractal element antennas are physically smaller.

Fractal element antennas are shrunken compared to conventional designs and do not need additional components. In general, the fractal dimension of a fractal antenna is a poor predictor of its performance and application. Not all fractal antennas work well for a given application or set of applications. Computer search methods, optimization algorithms, and antenna simulations are commonly used to identify which fractal antenna designs best meet the need of the application.

Although the first validation of the technology was published as early as 1995 **[4]** recent independent studies show advantages of the fractal element technology in real-life applications, such as radio frequency identification and cell phones.

A different and also useful attribute of some fractal element antennas is their self-scaling aspect. In 1999, it was discovered that self-similarity was one of the underlying requirements to make antennas "invariant" (same radiation properties) at a number or range of frequencies. Previously, under Rumsey's Frequency Independent Antenna Principle, it was believed that antennas had to be defined by angles for this to be true; the 1999 analysis **[5]**, based on Maxwell's equations, showed this to be a subset of the more general set of self-similar conditions. Hence fractal antennas offer a closed-form and unique insight into a key aspect of electromagnetic phenomena to wit the invariance property of Maxwell's equations.

Antenna tuning units are typically not required on fractal antennas due to their wide bandwidth and complex resonance. However, if a transmitting antenna has deep nulls in its response or has electromagnetic structural issues that require equalization then an antenna tuning unit should be used.

In addition to their use as antennas, fractals have also found application in other antenna system components including loads, counterpoises, and ground planes. Confusion by those who claim "grain of rice"-sized fractal antennas arises, because such fractal structures serve the purpose of loads and counterpoises, rather than bona fide antennas.

Fractal inductors and fractal tuned circuits (fractal resonators) were also discovered and invented simultaneously with fractal element antennas. An emerging example of such is in metamaterials. A recent report demonstrates using close-packed fractal resonators to make the first wideband metamaterial "invisibility cloak" at microwave frequencies **[6]**. Fractal filters (a type of tuned circuit) are another example of fractal geometry in microwave componentry.

As fractals can be used as counterpoises, loads, ground planes, and filters, all parts that can be integrated with antennas, they are considered parts of some antenna systems and thus are discussed in the context of fractal antennas.

REFERENCES

[1] B. B. Mandelbrot. *The Fractal Geometry of Nature.* New York, W. H. Freeman, 1983.

[2] D. H. Wemer. "Fractal Radiators," *Proceedings of the 4th Annual 1994 IEEE Mohawk Valley~Section Dual-Use Technologies* and *Applications Conference,* Volume I, SUNY Institute of Technology at UticalRomc, New York, 23-26 May 1994, pp. 478-482.

[3] J. P. Gianvittorio and Y. Rahmat-Samii. "Fractal Antennas: A Novel Antenna Miniaturization Technique, and Applications," *Antennas and Propagation Magazine*, *IEEE*, Vol. 44, No. 1, February 2002, pp. 20-36.

[4] N. Cohen. "Fractal Antennas," *Communications Quarterly*, Vol. 9, Summer 1995.

[5] R. Hohlfeld and N. Cohen. "Self-Similarity and the Geometric Requirements for Frequency Independence in Antenna," *Fractals,* Vol. 7, No. 1, 1999, pp. 79–84. doi:10.1142/S0218348X99000098.

[6] D. Schurig, J. J. Mock, B. J. Justice, S. A. Cummer, J. B. Pendry, A. F. Starr, and D. R. Smith. "Metamaterial Electromagnetic Cloak at Microwave Frequencies," *Science,* Vol. 314, No. 5801, 10 November 2006, pp. 977-980. Published online 19 October 2006 [DOI:10.1126/science.1133628].

This page intentionally left blank.

RADAR EQUATIONS

Field Intensity and Power Density 4-1
Power Density 4-2
One-Way Radar Equation / RF Propagation 4-3
Two-Way Radar Equation (Monostatic) 4-4
Alternate Two-Way Radar Equation 4-5
Two-Way Radar Equation (Bistatic) 4-6
Jamming to Signal (J/S) Ratio - Constant Power [Saturated] Jamming 4-7
Burn-Through / Crossover Range 4-8
Support Jamming 4-9
Jamming to Signal (J/S) Ratio - Constant Gain [Linear] Jamming 4-10
Radar Cross Section (RCS) 4-11
Emission Control (EMCON) 4-12
EW Jamming Techniques 4-13

This page intentionally left blank.

FIELD INTENSITY and POWER DENSITY

Sometimes it is necessary to know the actual field intensity or power density at a given distance from a transmitter instead of the signal strength received by an antenna. Field intensity or power density calculations are necessary when estimating electromagnetic interference (EMI) effects, when determining potential radiation hazards (personnel safety), or in determining or verifying specifications.

Field intensity (field strength) is a general term that usually means the magnitude of the electric field vector, commonly expressed in volts per meter. At frequencies above 100 MHZ, and particularly above one GHz, power density (P_D) terminology is more often used than field strength.
Power density and field intensity are related by equation [1]:

$$P_D = \frac{E^2}{Z_0} = \frac{E^2}{120\pi} = \frac{E^2}{377} \qquad \textbf{[1]}$$

where P_D is in W/m^2, E is the RMS value of the field in volts/meter and 377 ohms is the characteristic impedance of free space. When the units of P_D are in mW/cm^2, then P_D (mW/cm^2) = $E^2/3{,}770$.

Conversions between field strength and power density when the impedance is 377 ohms, can be obtained from Table 1. It should be noted that to convert dBm/m^2 to dBμV/m add 115.76 dB. Sample calculations for both field intensity and power density in the far field of a transmitting antenna are in Section 4-2 and Section 4-8. Refer to chapter 3 on antennas for the definitions of near field and far field.

Note that the "/" term before m, m^2, and cm^2 in Table 1 mean "per," i.e., dBm per m^2, not to be confused with the division sign which is valid for the Table 1 equation $P=E^2/Z_o$. Remember that in order to obtain dBm from dBm/m^2 given a certain area, you must add the logarithm of the area, not multiply. The values in the table are rounded to the nearest dBW, dBm, etc. per m^2 so the results are less precise than a typical handheld calculator and may be up to ½ dB off.

VOLTAGE MEASUREMENTS

Coaxial cabling typically has input impedances of 50, 75, and 93Ω, (±2) with 50Ω being the most common. Other types of cabling include the following: TV cable is 75Ω (coaxial) or 300Ω (twin-lead), audio public address (PA) is 600Ω, audio speakers are 3.2 (4), 8, or 16Ω.

In the 50Ω case, power and voltage are related by:

$$P = \frac{E^2}{Z_0} = \frac{E^2}{50} = 50\, I^2 \qquad \textbf{[2]}$$

Conversions between measured power, voltage, and current where the typical impedance is 50 ohms can be obtained from Table 2. The dBμA current values are given because frequently a current probe is used during laboratory tests to determine the powerline input current to the system.

MATCHING CABLING IMPEDANCE

In performing measurements, we must take into account an impedance mismatch between measurement devices (typically 50 ohms) and free space (377 ohms).

Table 1. Conversion Table - Field Intensity and Power Density.
$P_D = E^2/Z_0$ (Related by free space impedance = 377 ohms)

E (Volts/m)	20 log 10^6 (E) (dBμV/m)	P_D (watts/m^2)	10 Log P_D (dBW/m^2)	Watts/cm^2	dBW/cm^2	mW/cm^2	dBm/cm^2	dBm/m^2
7,000	197	130,000	+51	13	+11	13,000	+41	+81
5,000	194	66,300	+48	6.6	+8	6,630	+38	+78
3,000	190	23,900	+44	2.4	+4	2,390	+34	+74
4,000	186	10,600	+40	1.1	0	1,060	+30	+70
1,000	180	2,650	+34	.27	-6	265	+24	+64
700	177	1,300	+31	.13	-9	130	+21	+61
500	174	663	+28	.066	-12	66	+18	+58
300	170	239	+24	.024	-16	24	+14	+54
200	166	106	+20	.011	-20	11	+10	+50
100	160	27	+14	.0027	-26	2.7	+4	+44
70	157	13	+11	1.3x10^{-3}	-29	1.3	+1	+41
50	154	6.6	+8	6.6x10^{-4}	-32	.66	-2	+38
30	150	2.4	+4	2.4x10^{-4}	-36	.24	-6	+34
20	146	1.1	+0	1.1x10^{-4}	-40	.11	-10	+30
10	140	.27	-6	2.7x10^{-5}	-46	.027	-16	+24
7	137	.13	-9	1.3x10^{-5}	-49	.013	-19	+21
5	134	.066	-12	6.6x10^{-6}	-52	66x10^{-4}	-22	+18
3	130	.024	-16	2.4x10^{-6}	-56	24x10^{-4}	-26	+14
2	126	.011	-20	1.1x10^{-6}	-60	11x10^{-4}	-30	+10
1	120	.0027	-26	2.7x10^{-7}	-66	2.7x10^{-4}	-36	+4
0.7	117	1.3x10^{-3}	-29	1.3x10^{-7}	-69	1.3x10^{-4}	-39	+1
0.5	114	6.6x10^{-4}	-32	6.6x10^{-8}	-72	66x10^{-4}	-42	-2
0.3	110	2.4x10^{-4}	-36	2.4x10^{-8}	-76	24x10^{-4}	-46	-6
0.2	106	1.1x10^{-4}	-40	1.1x10^{-8}	-80	11x10^{-4}	-50	-10
0.1	100	2.7x10^{-5}	-46	2.7x10^{-9}	-86	2.7x10^{-6}	-56	-16
70x10^{-3}	97	1.3x10^{-5}	-49	1.3x10^{-9}	-89	1.3x10^{-6}	-59	-19
50x10^{-3}	94	6.6x10^{-6}	-52	6.6x10^{-10}	-92	66x10^{-8}	-62	-22
30x10^{-3}	90	2.4x10^{-6}	-56	2.4x10^{-10}	-96	24x10^{-8}	-66	-26
20x10^{-3}	86	1.1x10^{-6}	-60	1.1x10^{-10}	-100	11x10^{-8}	-70	-30
10x10^{-3}	80	2.7x10^{-7}	-66	2.7x10^{-11}	-106	2.7x10^{-8}	-76	-36
7x10^{-3}	77	1.3x10^{-7}	-69	1.3x10^{-11}	-109	1.3x10^{-8}	-79	-39
5x10^{-3}	74	6.6x10^{-8}	-72	6.6x10^{-12}	-112	66x10^{-10}	-82	-42
3x10^{-3}	70	2.4x10^{-8}	-76	2.4x10^{-12}	-116	24x10^{-10}	-86	-46
2x10^{-3}	66	1.1x10^{-8}	-80	1.1x10^{-12}	-120	11x10^{-10}	-90	-50
1x10^{-3}	60	2.7x10^{-9}	-86	2.7x10^{-13}	-126	2.7x10^{-10}	-96	-56
7x10^{-4}	57	1.3x10^{-9}	-89	1.3x10^{-13}	-129	1.3x10^{-10}	-99	-59
5x10^{-4}	54	6.6x10^{-10}	-92	6.6x10^{-14}	-132	66x10^{-12}	-102	-62
3x10^{-4}	50	2.4x10^{-10}	-96	2.4x10^{-14}	-136	24x10^{-12}	-106	-66
2x10^{-4}	46	1.1x10^{-10}	-100	1.1x10^{-14}	-140	11x10^{-12}	-110	-70
1x10^{-4}	40	2.7x10^{-11}	-106	2.7x10^{-15}	-146	2.7x10^{-12}	-116	-76
7x10^{-5}	37	1.3x10^{-11}	-109	1.3x10^{-15}	-149	1.3x10^{-12}	-119	-79
5x10^{-5}	34	6.6x10^{-12}	-112	6.6x10^{-16}	-152	66x10^{-14}	-122	-82
3x10^{-5}	30	2.4x10^{-12}	-116	2.4x10^{-16}	-156	24x10^{-14}	-126	-86
2x10^{-5}	26	1.1x10^{-12}	-120	1.1x10^{-16}	-160	11x10^{-14}	-130	-90
1x10^{-5}	20	2.7x10^{-13}	-126	2.7x10^{-17}	-166	2.7x10^{-14}	-136	-96
7x10^{-6}	17	1.3x10^{-13}	-129	1.3x10^{-17}	-169	1.3x10^{-14}	-139	-99
5x10^{-6}	14	6.6x10^{-14}	-132	6.6x10^{-18}	-172	66x10^{-16}	-142	-102
3x10^{-6}	10	2.4x10^{-14}	-136	2.4x10^{-18}	-176	24x10^{-16}	-146	-106
2x10^{-6}	6	1.1x10^{-14}	-140	1.1x10^{-18}	-180	11x10^{-16}	-150	-110
1x10^{-6}	0	2.7x10^{-15}	-146	2.7x10^{-19}	-186	2.7x10^{-16}	-156	-116

NOTE: Numbers in table rounded off.

FIELD STRENGTH APPROACH

To account for the impedance difference, the antenna factor (AF) is defined as: AF=E/V, where E is field intensity which can be expressed in terms taking 377 ohms into account and V is measured voltage which can be expressed in terms taking 50 ohms into account. Details are provided in Section 4-12.

POWER DENSITY APPROACH

To account for the impedance difference, the antenna's effective capture area term, A_e relates free space power density P_D with received power, P_r, i.e. $P_r = P_D A_e$. A_e is a function of frequency and antenna gain and is related to AF as shown in Section 4-12.

SAMPLE CALCULATIONS

Section 4-2 provides sample calculations using power density and power terms from Tables 1 and 2, whereas Section 4-12 uses these terms plus field intensity and voltage terms from Table 1 and Table 2. Refer the examples in Section 4-12 for usage of the conversions while converting free space values of power density to actual measurements with a spectrum analyzer attached by coaxial cable to a receiving antenna.

Conversion Between Field Intensity (Table 1) and Power Received (Table 2).

Power received (watts or milliwatts) can be expressed in terms of field intensity (volts/meter or μv/meter) using equation [3]:

$$Power\ received\ (P_r) = \frac{E^2}{480\pi^2}\frac{c^2}{f^2}G \qquad [3]$$

or in log form: $$10 \log P_r = 20 \log E + 10 \log G - 20 \log f + 10 \log (c^2/480\pi^2) \qquad [4]$$

Then $$10 \log Pr = 20 \log E_1 + 10 \log G - 20 \log f_1 + K_4 \qquad [5]$$

$$Where\ K_4 = 10 \log\left[\frac{c^2}{480\pi^2} \bullet \left(\begin{matrix} conversions \\ as\ required \end{matrix}\ \frac{(Watts\ to\ mW)}{(volts\ to\ \mu v)^2\ (Hz\ to\ MHz\ or\ GHz)^2}\right)\right]$$

The derivation of equation [3] follows:

$P_D = E^2/120\pi$ Eq [1], Section 4-1, terms (v^2/Ω)

$A_e = \lambda^2 G/4\pi$ Eq [8], Section 3-1, terms (m^2)

$P_r = P_D A_e$ Eq [2], Section 4-3, terms $(W/m^2)(m^2)$

$\therefore\ P_r = (E2/120\pi)(\lambda^2 G/4\pi)$ terms $(v^2/m^2\Omega)(m^2)$

$\lambda = c/f$ Section 2-3, terms (m/sec)(sec)

$\therefore P_r = (E^2/480\pi^2)(c^2 G/f^2)$ which is equation [3]

terms $(v^2/m^2\Omega)(m^2/sec^2)(sec^2)$ or v^2/Ω = watts

Values of K_4 (dB)

P_r	E_1	f_1 (Hz)	f_1 (MHz)	f_1 (GHz)
Watts (dBW)	volts/meter	132.8	12.8	-47.2
	μv/meter	12.8	-107.2	-167.2
mW (dBm)	volts/meter	162.8	42.8	-17.2
	μv/meter	42.8	-77.2	-137.7

Table 2. Conversion Table - Volts to Watts and dBµA.
($P_x = V_x^2/Z$ - Related by line impedance of 50 Ω)

Volts	dBV	dBµV	Watts	dBW	dBm	dBµA
700	56.0	176.0	9800	39.9	69.9	142.9
500	53.9	173.9	5000	37.0	67.0	140.0
300	49.5	169.5	1800	32.5	62.5	135.5
200	46.0	166.0	800	29.0	59.0	132.0
100	40.0	160.0	200	23.0	53.0	126.0
70	36.9	156.9	98	19.9	49.9	122.9
50	34.0	154.0	50	17.0	47.0	120.0
30	29.5	149.5	18	12.5	42.5	115.5
20	26.0	146.0	8	9.0	39.0	112.0
10	20.0	140.0	2	3.0	33.0	106.0
7	16.9	136.9	0.8	0	29.9	102.9
5	14.0	134.0	0.5	-3.0	27.0	100.0
3	9.5	129.5	0.18	-7.4	22.5	95.6
2	6.0	126.0	0.08	-11.0	19.0	92.0
1	0	120.0	0.02	-17.0	13.0	86.0
0.7	-3.1	116.9	9.8×10^{-3}	-20.1	9.9	82.9
0.5	-6.0	114.0	5.0×10^{-3}	-23.0	7.0	80.0
0.3	-10.5	109.5	1.8×10^{-3}	-27.4	2.6	75.6
0.2	-14.0	106.0	8.0×10^{-4}	-31.0	-1.0	72.0
0.1	-20.0	100.0	2.0×10^{-4}	-37.0	-7.0	66.0
.07	-23.1	96.9	9.8×10^{-5}	-40.1	-10.1	62.9
.05	-26.0	94.0	5.0×10^{-5}	-43.0	-13.0	60.0
.03	-30.5	89.5	1.8×10^{-5}	-47.4	-17.7	55.6
.02	-34.0	86.0	8.0×10^{-6}	-51.0	-21.0	52.0
.01	-40.0	80.0	2.0×10^{-6}	-57.0	-27.0	46.0
7×10^{-3}	-43.1	76.9	9.8×10^{-7}	-60.1	-30.1	42.9
5×10^{-3}	-46.0	74.0	5.0×10^{-7}	-63.0	-33.0	40.0
3×10^{-3}	-50.5	69.5	1.8×10^{-7}	-67.4	-37.4	35.6
2×10^{-3}	-54.0	66.0	8.0×10^{-8}	-71.0	-41.0	32.0
1×10^{-3}	-60.0	60.0	2.0×10^{-8}	-77.0	-47.0	26.0
7×10^{-4}	-64.1	56.9	9.8×10^{-9}	-80.1	-50.1	22.9
5×10^{-4}	-66.0	54.0	5.0×10^{-9}	-83.0	-53.0	20.0
3×10^{-4}	-70.5	49.5	1.8×10^{-9}	-87.4	-57.4	15.6
2×10^{-4}	-74.0	46.0	8.0×10^{-10}	-91.0	-61.0	12.0
1×10^{-4}	-80.0	40.0	2.0×10^{-10}	-97.0	-67.0	6.0
7×10^{-5}	-84.1	36.9	9.8×10^{-11}	-100.1	-70.1	2.9
5×10^{-5}	-86.0	34.0	5.0×10^{-11}	-103.0	-73.0	0
3×10^{-5}	-90.5	29.5	1.8×10^{-11}	-107.4	-77.4	-4.4
2×10^{-5}	-94.0	26.0	8.0×10^{-12}	-111.0	-81.0	-8.0
1×10^{-5}	-100.0	20.0	2.0×10^{-12}	-117.0	-87.0	-14.0
7×10^{-6}	-104.1	16.9	9.8×10^{-13}	-120.1	-90.1	-17.1
5×10^{-6}	-106.0	14.0	5.0×10^{-13}	-123.0	-93.0	-20.0
3×10^{-6}	-110.5	9.5	1.8×10^{-13}	-127.4	-97.4	-24.4
2×10^{-6}	-114.0	6.0	8.0×10^{-14}	-131.0	-101.0	-28.0
1×10^{-6}	-120.0	0	2.0×10^{-14}	-137.0	-107.0	-34.0
7×10^{-7}	-124.1	-3.1	9.8×10^{-15}	-140.1	-110.1	-37.1
5×10^{-7}	-126.0	-6.0	5.0×10^{-15}	-143.0	-113.0	-40.0
3×10^{-7}	-130.5	-10.5	1.8×10^{-15}	-147.4	-117.4	-44.4
2×10^{-7}	-134.0	-14.0	8.0×10^{-16}	-151.0	-121.0	-48.0
1×10^{-7}	-140.0	-20.0	2.0×10^{-16}	-157.0	-127.0	-54.0

POWER DENSITY

Radio Frequency (RF) propagation is defined as the travel of electromagnetic waves through or along a medium. For RF propagation between approximately 100 MHz and 10 GHz, radio waves travel very much as they do in free space and travel in a direct line of sight. There is a very slight difference in the dielectric constants of space and air. The dielectric constant of space is one. The dielectric constant of air at sea level is 1.000536. In all but the highest precision calculations, the slight difference is neglected.

From chapter 3, Antennas, an isotropic radiator is a theoretical, lossless, omnidirectional (spherical) antenna. That is, it radiates uniformly in all directions. The power of a transmitter that is radiated from an isotropic antenna will have a uniform power density (power per unit area) in all directions. The power density at any distance from an isotropic antenna is simply the transmitter power divided by the surface area of a sphere ($4\pi R^2$) at that distance. The surface area of the sphere increases by the square of the radius, therefore the power density, P_D, (watts/square meter) decreases by the square of the radius.

$$\begin{matrix}\text{Power density from} \\ \text{an isotropic antenna}\end{matrix} = P_D = \frac{P_t}{4\pi R^2} \qquad \begin{matrix}\text{where : } P_t = \text{Transmitter Power} \\ R = \text{Range From Antenna (i.e., radius of sphere)}\end{matrix} \qquad [1]$$

P_t is either peak or average power depending on how P_D is to be specified.

Radars use directional antennas to channel most of the radiated power in a particular direction. The Gain (G) of an antenna is the ratio of power radiated in the desired direction as compared to the power radiated from an isotropic antenna, or:

$$G = \frac{\text{Maximum radiation intensity of actual antenna}}{\text{Radiation intensity of isotropic antenna with same power input}}$$

The power density at a distant point from a radar with an antenna gain of G_t is the power density from an isotropic antenna multiplied by the radar antenna gain.

Power density from radar, $$P_D = \frac{P_t G_t}{4\pi R^2} \qquad [2]$$

P_t is either peak or average power depending on how P_D is to be specified.

Another commonly used term is effective isotropic radiated power (EIRP), where **EIRP = P_t G_t.** ERP is also used but EIRP is preferred because it specifically defines the type of reference antenna as isotropic.

A receiving antenna captures a portion of this power determined by its effective capture Area (A_e). The received power available at the antenna terminals is the power density times the effective capture area (A_e) of the receiving antenna.

e.g., If the power density at a specified range is one microwatt per square meter and the antenna's effective capture area is one square meter then the power captured by the antenna is one microwatt.

For a given receiver antenna size the capture area is constant no matter how far it is from the transmitter, as illustrated in Figure 1. Also notice from Figure 1 that the received signal power decreases by 1/4 (6 dB) as the distance doubles. This is due to the R^2 term in the denominator of equation [2].


ONE WAY SIGNAL STRENGTH (S)
S
6 dB
(1/4 pwr)
S decreases by 6 dB
when the distance doubles
2R
R
6 dB
(4x pwr)
S
S increases by 6 dB
when the distance is half
R
0.5 R


Same Antenna
Capture Area
Range 1
Received Signal
Range 2
Received Signal

Figure 1. Power Density vs. Range.

Sample Power Density Calculation - Far Field
(Refer to Section 3-5 for the definition of near field and far field)

Calculate the power density at 100 feet for 100 watts transmitted through an antenna with a gain of 10.

Given: P_t = 100 watts G_t = 10 (dimensionless ratio) R = 100 ft

This equation produces power density in watts per square range unit.

$$P_D = \frac{P_t G_t}{4\pi R^2} = \frac{(100\ watts)(10)}{4\pi (100\ ft)^2} = 0.0080\ watts/\ ft^2$$

For safety (radiation hazard) and EMI calculations, power density is usually expressed in milliwatts per square cm. That's nothing more than converting the power and range to the proper units.

100 watts = 1 x 10^2 watts = 1 x 10^5 mW

100 feet = 30.4785 meters = 3047.85 cm.

$$P_D = \frac{P_t G_t}{4\pi R^2} = \frac{(10^5\ mW) \bullet (10)}{4\pi (3047.85cm)^2} = 0.0086\ mW/\ cm^2$$

However, antenna gain is almost always given in dB, not as a ratio. It's then often easier to express EIRP in dBm.

$$P_t\,(dBm) = 10\ \text{Log}\left[\frac{P_t\ watts}{1\ mW}\right] = 10\ \text{Log}\left[\frac{100}{.001}\right] = 50\ dBm$$

$$G_t\,(dB) = 10\ \text{Log}\left[\frac{G_t}{1}\right] = 10\ \text{Log}\,(10) = 10\ dB$$

EIRP (dBm) = P_t (dBm) + G_t (dB) = 50 + 10 = 60 dBm

To reduce calculations, the graph in Figure 2 can be used. It gives EIRP in dBm, range in feet and power density in mW/cm^2. Follow the scale A line for an EIRP of 60 dBm to the point where it intersects the 100 foot range scale. Read the power density directly from the A-scale x-axis as 0.0086 mW/cm^2 (confirming our earlier calculations).



Figure 2. Power Density vs. Range and EIRP.

Example 2

When antenna gain and power (or EIRP) are given in dB and dBm, it is necessary to convert back to ratios in order to perform the calculation given in equation [2]. Use the same values as in example 1 except for antenna gain.

Suppose the antenna gain is given as 15 dB: **G_t (dB) = 10 Log (G_t)**

$$Therefore: \quad G_t = [10]^{\left(\frac{G_t(dB)}{10}\right)} = [10]^{\left(\frac{15}{10}\right)} = 31.6228$$

$$P_D = \frac{P_t G_t}{4\pi R^2} = \frac{(10^5\ mW)(31.6228)}{4\pi\,(3047.85\ )^2} = 0.0271\ mW/\ cm^2$$

Follow the 65 dBm (extrapolated) EIRP line and verify this result on the A-scale X-axis.

Example 3 - Sample Real Life Problem

Assume we are trying to determine if a jammer will damage the circuitry of a missile carried onboard an aircraft and we cannot perform an actual measurement. Refer to the diagram at the right.



Given the following:

Jammer power: 500 W ($P_t = 500$)

Jammer line loss and antenna gain: 3 dB ($G_t = 2$)

Missile antenna diameter: 10 in

Missile antenna gain: Unknown

Missile limiter protection (maximum antenna power input): 20 dBm (100mW) average and peak.

The power density at the missile antenna caused by the jammer is computed as follows:

$$P_D = \frac{P_t G_t}{4\pi R^2} = \frac{500W\,(2)}{4\pi[(10ft)(.3048m/ft)]^2} = 8.56W/m^2$$

The maximum input power actually received by the missile is either:

$P_r = P_D A_e$ (if effective antenna area is known) or
$P_r = P_D G_m \lambda^2/4\pi$ (if missile antenna gain is known)

To cover the case where the missile antenna gain is not known, first assume an aperture efficiency of 0.7 for the missile antenna (typical). Then:

$P_r = P_D A \eta = 8.56\ W/m^2\ (\pi)[\ (10/2\ in)(.0254\ m/in)\ ]^2\ (0.7) = 0.3$ watts

Depending upon missile antenna efficiency, we can see that the power received will be about 3 times the maximum allowable and that either better limiter circuitry may be required in the missile or a new location is needed for the missile or jammer. Of course if the antenna efficiency is 0.23 or less, then the power will not damage the missile's receiver.

If the missile gain were known to be 25 dB, then a more accurate calculation could be performed. Using the given gain of the missile (25 dB= numeric gain of 316), and assuming operation at 10 GHz ($\lambda = .03$m)

$P_r = P_D G_m \lambda^2 / 4\pi = 8.56\ W/m^2\ (316)(.03)^2 / 4\pi = .19$ watts (still double the allowable tolerance)

ONE-WAY RADAR EQUATION / RF PROPAGATION

The one-way (transmitter to receiver) radar equation is derived in this section. This equation is most commonly used in RWR, communications, or ESM type of applications. The following is a summary of the important equations explored in this section:

ONE-WAY RADAR EQUATION

Peak Power at

Receiver Input, $P_r\,(or\ S) = P_D A_e = \dfrac{P_t G_t A_e}{4\pi R^2}$ $\quad$ $and\ Antenna\ Gain,\ G = \dfrac{4\pi A_e}{\lambda^2}$

$or:\ Equivalent\ Area,\ A_e = \dfrac{G \lambda^2}{4\pi}$

So the one-way radar equation is :

$$S\,(or\ P_r) = \frac{P_t G_t G_r \lambda^2}{(4\pi R)^2} = P_t G_t G_r \left[\frac{c^2}{(4\pi f R)^2}\right]^* \qquad (\ Note: \lambda = \frac{c}{f}\ )$$

* keep λ, c, and R in the same units

On reducing to log form this becomes:
$10\log P_r = 10\log P_t + 10\log G_t + 10\log G_r - 20\log f R + 20\log (c/4\pi)$

or in simplified terms:
$10\log P_r = 10\log P_t + 10\log G_t + 10\log G_r - \alpha_1$ (in dB)

Where: α_1 = one-way free space loss = $20\log (f_1 R) + K_1$ (in dB) and:
$K_1 = 20\log [(4\pi/c)$(Conversion factors if units if not in m/sec, m, and Hz)]

Note: To avoid having to include additional terms for these calculations, always combine any transmission line loss with antenna gain

Values of K_1 (in dB)

Range (units)	f_1 in MHz K_1 =	f_1 in GHz K_1 =
NM	37.8	97.8
km	32.45	92.45
m	-27.55	32.45
yd	-28.33	31.67
ft	-37.87	22.13

Note: Losses due to antenna polarization and atmospheric absorption (Sections 3-2 & 5-1) are not included in any of these equations.

Recall from Section 4-2 that the power density at a distant point from a radar with an antenna gain of G_t is the power density from an isotropic antenna multiplied by the radar antenna gain.

Power density from radar, $P_D = \dfrac{P_t G_t}{4\pi R^2}$

If you could cover the entire spherical segment with your receiving antenna you would theoretically capture all of the transmitted energy. You can't do this because no antenna is large enough. (A two degree segment would be about a mile and three-quarters across at fifty miles from the transmitter.)



Figure 1. Power Density vs. Range.

A receiving antenna captures a portion of this power determined by its effective capture Area (A_e). The received power available at the antenna terminals is the power density times the effective capture area (A_e) of the receiving antenna.

For a given receiver antenna size the capture area is constant no matter how far it is from the transmitter, as illustrated in Figure 1. This concept is shown in the following equation:
Peak Power at Receiver input,

$$P_R \text{ (or S)} = P_D A_e = \frac{P_t G_t A_e}{4\pi R^2} \quad \text{which is known as the one-way (beacon) equation} \qquad \textbf{[2]}$$

In order to maximize energy transfer between an antenna and transmitter or receiver, the antenna size should correlate with frequency. For reasonable antenna efficiency, the size of an antenna will be greater than λ/4. Control of beamwidth shape may become a problem when the size of the active element exceeds several wavelengths.

The relation between an antenna's effective capture area (A_e) or effective aperture and its Gain (G) is:

$$\textit{Antenna Gain, } G = \frac{4\pi A_e}{\lambda^2} \qquad \textbf{[3]}$$

$$\textit{or : Equivalent Area, } A_e = \frac{G\lambda^2}{4\pi} \qquad \textbf{[4]}$$

Since the effective aperture is in units of length squared, from equation [3], it is seen that gain is proportional to the effective aperture normalized by the wavelength. This physically means that to maintain the same gain when doubling the frequency, the area is reduced by 1/4. This concept is illustrated in Figure 2.


Lower Frequency Antenna Has Larger Area
Higher Frequency Antenna Has Smaller Area
Low Frequency Antenna Area
Received Signal
Higher Frequency Antenna Area
Received Signal

Figure 2. Capture Area vs. Frequency.

If equation [4] is substituted into equation [2], the following relationship results:

$$\textit{Peak Power at Receiver Input} = S \text{ (or } P_R) = \frac{P_t G_t G_r \lambda^2}{(4\pi)^2 R^2} = \frac{P_t G_t G_r \lambda^2}{(4\pi R)^2} \qquad \textbf{[5]}$$

This is the signal calculated one-way from a transmitter to a receiver. For instance, a radar application might be to determine the signal received by a RWR, ESM, or an ELINT receiver. It is a general purpose equation and could be applied to almost any line-of-sight transmitter to receiver situation if the RF is higher than 100 MHZ.


ONE WAY SIGNAL STRENGTH (S)
S
6 dB
(1/4 pwr)
S decreases by 6 dB
when the distance doubles
2R
R
6 dB
(4x pwr)
S
S increases by 6 dB
when the distance is half
R
0.5 R

Values of K_1 (dB)

Range (units)	f_1 in MHz K_1 =	f_1 in GHz K_1 =
NM	37.8	97.8
km	32.45	92.45
m	-27.55	32.45
yd	-28.33	31.67
ft	-37.87	22.13

The free space travel of radio waves can, of course, be blocked, reflected, or distorted by objects in their path such as buildings, flocks of birds, chaff, and the earth itself.

As illustrated in Figure 1, as the distance is doubled the received signal power decreases by 1/4 (6 dB). This is due to the R^2 term in equation [5].

To illustrate this, blow up a round balloon and draw a square on the side of it. If you release air so that the diameter or radius is decreased by 1/2, the square shrinks to 1/4 the size. If you further blow up the balloon, so the diameter or radius is doubled, the square has quadrupled in area.


PHYSICAL CONCEPT - One-way Space Loss
TRANSMITTER
P_t
$G_t = 1$
$G_r = 1$
RECEIVER
S (or P_r)
EQUIVALENT CIRCUIT - One-way Space Loss
TRANSMITTER
P_t
α_1, TRANSMITTER TO RECEIVER ONE-WAY SPACE LOSS
RECEIVER
S (or P_r)
EQUIVALENT CIRCUIT - One-Way Space Loss with Actual Antennas
TRANSMITTER
P_t
G_t
XMT ANTENNA GAIN
α_1
G_r
RECEIVE ANTENNA GAIN
RECEIVER
S (or P_r)

Figure 3. Concept of One-Way Space Loss.

The one-way free space loss factor (α_1), (sometimes called the path loss factor) is given by the term $(4\pi R^2)(4\pi/\lambda^2)$ or $(4\pi R/\lambda)^2$. As shown in Figure 3, the loss is due to the ratio of two factors (1) the effective radiated area of the transmit antenna, which is the surface area of a sphere ($4\pi R^2$) at that distance (R), and (2) the effective capture area (A_e) of the receive antenna which has a gain of one. If a receiving antenna could capture the whole surface area of the sphere, there would be no spreading loss, but a practical antenna will capture only a small part of the spherical radiation. Space loss is calculated using isotropic antennas for both transmit and receive, so α_1 is independent of the actual antenna. Using Gr = 1 in equation [11] in Section 3-1, $A_e = \lambda^2/4\pi$. Since this term is in the denominator of α_1, the higher the frequency (lower λ) the more the space loss. Since G_t and G_r are part of the one-way radar equation, S (or P_r) is adjusted according to actual antennas as shown in the last portion of Figure 3. The value of the received signal (S) is:

$$S\,(or\ P_R) = \frac{P_t G_t G_r \lambda^2}{(4\pi)^2 R^2} = P_t G_t G_r \left[\frac{\lambda^2}{(4\pi R)^2}\right] \qquad \textbf{[6]}$$

To convert this equation to dB form, it is rewritten as:

$$10\ \text{Log}\,(S\ or\ P_r) = 10\ \text{Log}\,(P_t G_t G_r) + 20\ \text{Log}\left[\frac{\lambda}{4\pi f R}\right] \qquad \textbf{[7]}$$

Since $\lambda = c / f$, equation [7] can be rewritten as:

$$10\ \text{Log}\,(S\ or\ P_r) = 10\ \text{Log}(P_t G_t G_r) - \alpha_1 \qquad \textbf{[8]}$$

Where the one-way free space loss, α_1, is defined as: $\alpha_1 = 20\ \text{Log}\left[\frac{4\pi f R}{c}\right]$* **[9]**

The signal received equation in dB form is: $10\log(P_r \text{ or } S) = 10\log P_t + 10\log G_t + 10\log G_r - \alpha_1$ **[10]**

The one-way free space loss, α_1, can be given in terms of a variable and constant term as follows:

$$\alpha_1 = 20\,\text{Log}\left[\frac{4\pi f\,R}{c}\right]^{*} = 20\,\text{Log}\, f_1 R + K_1 \quad (in\ dB) \qquad \textbf{[11]}$$

The value of f_1 can be either in MHz or GHz as shown with commonly used units of R in the adjoining table.

$$where\ K_1 = 20\,\text{Log}\left[\frac{4\pi}{c} \bullet (Conversion\ units\ if\ not\ in\ m/\text{sec}, m, and\ Hz)\right]$$

Note: To avoid having to include additional terms for these calculations, always combine any transmission line loss with antenna gain.

A value for the one-way free space loss (α_1) can be obtained from:

(a) The One-way Free Space Loss graph (Figure 4). Added accuracy can be obtained using the Frequency Extrapolation graph (Figure 5)

(b) The space loss nomograph (Figure 6 or 7)

(c) The formula for α_1, equation [11].

FOR EXAMPLE:

Find the value of the one-way free space loss, α_1, for an RF of 7.5 GHz at 100 NM.

(a) From Figure 4, find 100 NM on the X-axis and estimate where 7.5 GHz is located between the 1 and 10 GHz lines (note dot). Read α_1 as 155 dB. An alternate way would be to read the α_1 at 1 GHz (138 dB) and add the frequency extrapolation value (17.5 dB for 7.5:1, dot on Figure 5) to obtain the same 155 dB value.

(b) From the nomogram (Figure 6), the value of α_1 can be read as 155 dB (Note the dashed line).

(c) From the equation 11, the precise value of α_1 is 155.3 dB.

Remember, α_1 is a free space value. If there is atmospheric attenuation because of absorption of RF due to certain molecules in the atmosphere or weather conditions etc., the atmospheric attenuation is in addition to the space loss (refer to Section 5-1).



Figure 4. One-Way Free Space Loss.



Figure 5. Frequency Extrapolation.



If the nomograph does not cover the Desired ranges, multiply the f or R scale by 10^N and add 20N dB to path loss scale. N can be positive or negative, and the indicated procedure can be applied successively to the f and R scales.

Figure 6. One-Way Space Loss Nomograph for Distances Greater Than 10 Nautical Miles.



If the nomograph does not cover the Desired ranges, multiply the f or R scale by 10^N and add 20N dB to path loss scale. N can be positive or negative, and the indicated procedure can be applied successively to the f and R scales

Figure 7. One-Way Space Loss Nomograph for Distances Less Than 10 Nautical Miles.

Figure 8 is the visualization of the losses occurring in one-way radar equation. Note: To avoid having to include additional terms, always combine any transmission line loss with antenna gain. Losses due to antenna polarization and atmospheric absorption also need to be included.


NOTE: Drawing not to scale
ERP
SIGNAL STRENGTH in dBm
P$_T$
Transmitter Power
Transmit Antenna Gain
Space Loss Approaching Receiver
Note: In the example on page 4-3.16, the receiver antenna gain is negative vs positive.
If power is actually measured in this region, it is stated in either power density (mW/cm²) or field intensity (V/m)
Rcvr Antenna Gain
P$_R$
RWR / ESM Receiver
10 log P$_t$ + 10 log G$_t$
- α
+ 10 log G$_r$ = 10 log P$_r$
SIGNAL POSITION IN SPACE

Figure 8. Visualization of One-Way Radar Equation.

RWR/ESM RANGE EQUATION (One-Way)

The one-way radar (signal strength) equation [5] is rearranged to calculate the maximum range R_{max} of RWR/ESM receivers. It occurs when the received radar signal just equals S_{min} as follows:

$$R_{max} \cong \left[\frac{P_t G_t G_r \lambda^2}{(4\pi)^2 S_{min}}\right]^{\frac{1}{2}} \quad or \quad \left[\frac{P_t G_t G_r c^2}{(4\pi f)^2 S_{min}}\right]^{\frac{1}{2}} \quad or \quad \left[\frac{P_t G_t A_e}{4\pi S_{min}}\right]^{\frac{1}{2}} \qquad \textbf{[12]}$$

In log form:

$$20\log R_{max} = 10\log P_t + 10\log G_t - 10\log S_{min} - 20\log f + 20\log(c/4\pi) \qquad \textbf{[13]}$$

and since $K_1 = 20\log\{4\pi/c$ times conversion units if not in m/sec, m, and Hz$\}$
(Refer to Section 4-3 for values of K_1).

$$10\log R_{max} = \tfrac{1}{2}[\, 10\log P_t + 10\log G_t - 10\log S_{min} - 20\log f - K_1] \quad \text{(keep } P_t \text{ and } S_{min} \text{ in same units)} \qquad \textbf{[14]}$$

If you want to convert back from dB, then $R_{max} \cong \frac{10^{M\,dB}}{20}$, where M dB is the resulting number in the brackets of equation 14.

From Section 5-2, Receiver Sensitivity / Noise, S_{min} is related to the noise factor S:

$$S_{min} = (S/N)_{min}\,(NF)KT_oB \qquad \textbf{[15]}$$

The one-way RWR/ESM range equation becomes:

$$R_{max} \cong \left[\frac{P_t G_t G_r \lambda^2}{(4\pi)^2 (S/N)_{min} (NF) K T_o B}\right]^{\frac{1}{2}} \text{ or } \left[\frac{P_t G_t G_r c^2}{(4\pi f)^2 (S/N)_{min} (NF) K T_o B}\right]^{\frac{1}{2}} \text{ or } \left[\frac{P_t G_t A_e}{4\pi (S/N)_{min} (NF) K T_o B}\right]^{\frac{1}{2}} \qquad \textbf{[16]}$$

RWR/ESM RANGE INCREASE AS A RESULT OF A SENSITIVITY INCREASE

As shown in equation [12] $S_{min}^{-1} \propto R_{max}^2$. Therefore, $-10 \log S_{min} \propto 20 \log R_{max}$ and the following table results:

% Range Increase: Range + (% Range Increase) x Range = New Range
i.e., for a 6 dB sensitivity increase, 500 miles +100% x 500 miles = 1,000 miles
Range Multiplier: Range x Range Multiplier = New Range
i.e., for a 6 dB sensitivity increase 500 miles x 2 = 1,000 miles

dB Sensitivity Increase	% Range Increase	Range Multiplier	dB Sensitivity Increase	% Range Increase	Range Multiplier
+ 0.5	6	1.06	10	216	3.16
1.0	12	1.12	11	255	3.55
1.5	19	1.19	12	298	3.98
2	26	1.26	13	347	4.47
3	41	1.41	14	401	5.01
4	58	1.58	15	462	5.62
5	78	1.78	16	531	6.31
6	100	2.0	17	608	7.08
7	124	2.24	18	694	7.94
8	151	2.51	19	791	8.91
9	182	2.82	20	900	10.0

RWR/ESM RANGE DECREASE AS A RESULT OF A SENSITIVITY DECREASE

As shown in equation [12] $S_{min}^{-1} \propto R_{max}^2$. Therefore, $-10 \log S_{min} \propto 20 \log R_{max}$ and the following table results:

% Range Decrease: Range - (% Range decrease) x Range = New Range
i.e., for a 6 dB sensitivity decrease, 500 miles - 50% x 500 miles = 250 miles
Range Multiplier: Range x Range Multiplier = New Range
i.e., for a 6 dB sensitivity decrease 500 miles x .5 = 250 miles

dB Sensitivity Decrease	% Range Decrease	Range Multiplier	dB Sensitivity Decrease	% Range Decrease	Range Multiplier
- 0.5	6	0.94	-10	68	0.32
- 1.0	11	0.89	- 11	72	0.28
- 1.5	16	0.84	- 12	75	0.25
- 2	21	0.79	- 13	78	0.22
- 3	29	0.71	- 14	80	0.20
- 4	37	0.63	- 15	82	0.18
- 5	44	0.56	- 16	84	0.16
- 6	50	0.50	- 17	86	0.14
- 7	56	0.44	- 18	87	0.13
- 8	60	0.4	- 19	89	0.11
- 9	65	0.35	- 20	90	0.10

Example of One-Way Signal Strength: A 5 (or 7) GHz radar has a 70 dBm signal fed through a 5 dB loss transmission line to an antenna that has 45 dB gain. An aircraft that is flying 31 km from the radar has an aft EW antenna with -1 dB gain and a 5 dB line loss to the EW receiver (assume all antenna polarizations are the same).

Note: The respective transmission line losses will be combined with antenna gains, i.e.:

-5 +45 = 40 dB, -5 - 1 = -6 dB, -10 + 5 = -5 dB.

(1) What is the power level at the input of the EW receiver?

Answer (1): P_r at the input to the EW receiver = Transmitter power - xmt cable loss + xmt antenna gain - space loss + rcvr antenna gain - rcvr cable loss.

Space loss (from Section 4-3) @ 5 GHz = $20 \log f R + K_1 = 20 \log (5 \times 31) + 92.44 = 136.25$ dB. Therefore:

$$P_r = 70 + 40 - 136.25 - 6 = -32.25 \text{ dBm @ 5 GHz } (P_r = -35.17 \text{ dBm @ 7 GHz since } \alpha_1 = 139.17 \text{ dB})$$

(2) If the received signal is fed to a jammer with a gain of 60 dB, feeding a 10 dB loss transmission line which is connected to an antenna with 5 dB gain, what is the power level from the jammer at the input to the receiver of the 5 (or 7) GHz radar?

Answer (2): P_r at the input to the radar receiver = Power at the input to the EW receiver+ Jammer gain - jammer cable loss + jammer antenna gain - space loss + radar rcvr antenna gain - radar rcvr cable loss. Therefore:

$$P_r = -32.25 + 60 - 5 - 136.25 + 40 = -73.5 \text{ dBm @ 5 GHz. } (P_r = -79.34 \text{ dBm @ 7 GHz since } \alpha_1 = 139.17 \text{ dB and } P_t = -35.17 \text{ dBm}).$$

This problem continues in Sections 4-4, 4-7, and 4-10.

This page intentionally left blank.

TWO-WAY RADAR EQUATION (MONOSTATIC)

In this section the radar equation is derived from the one-way equation (transmitter to receiver) which is then extended to the two-way radar equation. The following is a summary of the important equations to be derived here:

TWO-WAY RADAR EQUATION (MONOSTATIC)

Peak power at the radar receiver input is:

$$P_r = \frac{P_t G_t G_r \lambda^2 \sigma}{(4\pi)^3 R^4} = P_t G_t G_r \left[\frac{\sigma c^2}{(4\pi)^3 f^2 R^4} \right]^*$$

Note : $\lambda = c/f$ and $\sigma = RCS$ ⊥

* keep λ or c, σ, and R in the same units

On reducing the above equation to log form we have:

$10\log P_r = 10\log P_t + 10\log G_t + 10\log G_r + 10\log \sigma - 20\log f - 40\log R - 30\log 4\pi + 20\log c$

or in simplified terms: $10\log P_r = 10\log P_t + 10\log G_t + 10\log G_r + G_\sigma - 2\alpha_1$ (in dB)

Note: Losses due to antenna polarization and atmospheric absorption (Sections 3-2 and 5-1) are not included in these equations.

Target gain factor, $G_\sigma = 10\log \sigma + 20\log f_1 + K_2$ (in dB)

K_2 Values (dB)

RCS (σ) (units)	f_1 in MHz K_2 =	f_1 in GHz K_2 =
m^2	-38.54	21.46
ft^2	-48.86	11.14

One-way free space loss, $\alpha_1 = 20\log (f_1 R) + K_1$ (in dB)

K_1 Values (dB)

Range (units)	f_1 in MHz K_1 =	f_1 in GHz K_1 =
NM	37.8	97.8
Km	32.45	92.45
m	-27.55	32.45
yd	-28.33	31.67
ft	-37.87	22.13

Figure 1 illustrates the physical concept and equivalent circuit for a target being illuminated by a monostatic radar (transmitter and receiver co-located). Note the similarity of Figure 1 to Figure 3 in Section 4-3. Transmitted power, transmitting and receiving antenna gains, and the one-way free space loss are the same as those described in Section 4-3. The physical arrangement of the elements is different, of course, but otherwise the only difference is the addition of the equivalent gain of the target RCS factor.


PHYSICAL CONCEPT
TRANSMITTER
P_t
P_r
RECEIVER
G_t
G_r
α_1, ONE-WAY SPACE LOSS
TARGET
G_σ
GAIN OF RCS
EQUIVALENT CIRCUIT
P_t
G_t
TRANSMITTER
TRANSMITTER TO TARGET
α_1, ONE-WAY SPACE LOSS
G_σ
GAIN OF RCS
RECEIVER
P_r
G_r
TARGET TO RECEIVER
α_1, ONE-WAY SPACE LOSS

Figure 1. The Two-Way Monostatic Radar Equation Visualized.

From Section 4-3, One-Way Radar Equation / RF Propagation, the power in the receiver is:

$$\begin{matrix}\textit{Received Signal}\\ \textit{at Target}\end{matrix} = \frac{P_t G_t G_r \lambda^2}{(4\pi R)^2} \qquad \textbf{[1]}$$

From equation [3] in Section 4-3: $$\textit{Antenna Gain}\,,\, G = \frac{4\pi A_e}{\lambda^2} \qquad \textbf{[2]}$$

Similar to a receiving antenna, a radar target also intercepts a portion of the power, but reflects (reradiates) it in the direction of the radar. The amount of power reflected toward the radar is determined by the Radar Cross Section (RCS) of the target. RCS is a characteristic of the target that represents its size as seen by the radar and has the dimensions of area (σ) as shown in Section 4-11. RCS area is not the same as physical area. But, for a radar target, the power reflected in the radar's direction is equivalent to re-radiation of the power captured by an antenna of area σ (the RCS). Therefore, the effective capture area (A_e) of the receiving antenna is replaced by the RCS (σ).

$$G_r = \frac{4\pi\sigma}{\lambda^2} \qquad \textbf{[3]}$$

so we now have:

$$\begin{matrix}\textit{Reflected Signal}\\ \textit{from target}\end{matrix} = \frac{P_t G_t \lambda^2\, 4\pi\sigma}{(4\pi R)^2 \lambda^2} \qquad \textbf{[4]}$$

The equation for the power reflected in the radar's direction is the same as equation [1] except that P_t G_t, which was the original transmitted power, is replaced with the reflected signal power from the target, from equation [4]. This gives:

$$\begin{matrix}\textit{Reflected Signal Received Back}\\ \textit{at Input to Radar Receiver}\end{matrix} = \frac{P_t G_t \lambda^2\, 4\pi\sigma}{(4\pi R)^2 \lambda^2} \times \frac{G_r \lambda^2}{(4\pi R)^2} \qquad \textbf{[5]}$$



If like terms are cancelled, the two-way radar equation results. The peak power at the radar receiver input is:

$$P_r = \frac{P_t G_t G_r \lambda^2 \sigma}{(4\pi)^3 R^4} = P_t G_t G_r \left[\frac{\sigma c^2}{(4\pi)^3 f^2 R^4} \right]^* \qquad \textbf{[6]}$$

* Note: $\lambda = c/f$ and σ = RCS. Keep λ or c, σ, and R in the same units.

On reducing equation [6] to log form we have:

$$10\log P_r = 10\log P_t + 10\log G_t + 10\log G_r + 10\log \sigma - 20\log f - 40\log R - 30\log 4\pi + 20\log c \qquad \textbf{[7]}$$

Target Gain Factor

If Equation [5] terms are rearranged instead of cancelled, a recognizable form results:

$$S\,(or\ P_r) = (P_t G_t G_r) \bullet \left[\frac{\lambda^2}{(4\pi R)^2}\right] \bullet \left[\frac{4\pi\sigma}{\lambda^2}\right] \bullet \left[\frac{\lambda^2}{(4\pi R)^2}\right] \qquad \textbf{[8]}$$

In log form:

$$10\log[S\,(or\ P_r)] = 10\log P_t + 10\log G_t + 10\log G_r + 20\log\left[\frac{\lambda}{4\pi R}\right] + 10\log\left[\frac{4\pi\sigma}{\lambda^2}\right] + 20\log\left[\frac{\lambda}{4\pi R}\right] \qquad \textbf{[9]}$$

The fourth and sixth terms can each be recognized as -α, where α is the one-way free space loss factor defined in Section 4-3. The fifth term containing RCS (σ) is the only new factor, and it is the “Target Gain Factor.”

In simplified terms the equation becomes:

$$10\log\,[S\ (or\ P_r)] = 10\log P_t + 10\log G_t + 10\log G_r + G_\sigma - 2\alpha_1 \qquad (in\ dB) \qquad \textbf{[10]}$$

Where α_1 and G_σ are as follows:

From Section 4-3, equation [11], the space loss in dB is given by:

$$\alpha_1 = 20\log\left[\frac{4\pi f\,R}{c}\right]^{*} = 20\log f_1 R + K_1 \quad where\ K_1 = 20\log\left[\frac{4\pi}{c} \bullet (Conversion\ units\ if\ not\ in\ m/sec, m, and\ Hz)\right] \qquad \textbf{[11]}$$

* Keep c and R in the same units. The table of values for K_1 is again presented here for completeness. The constant, K_1, in the table includes a range and frequency unit conversion factor.

One-way free space loss, α_1 = 20log (f_1R) + K_1 (in dB)			
K_1 Values (dB)	Range (units)	f_1 in MHz K_1 =	f_1 in GHz K_1 =
	NM	37.8	97.8
	Km	32.45	92.45
	m	-27.55	32.45
	yd	-28.33	31.67
	ft	-37.87	22.13

While it’s understood that RCS is the antenna aperture area equivalent to an isotropically radiated target return signal, the target gain factor represents a gain, as shown in the equivalent circuit of Figure 1. The Target Gain Factor expressed in dB is G_σ as shown in equation [12].

$$G_\sigma = 10\log\left[\frac{4\pi\sigma}{\lambda^2}\right] = 10\log\left[\frac{4\pi\sigma f^2}{c^2}\right] = 10\log\sigma + 20\log f_1 + K_2 \quad (in\ dB) \qquad \textbf{[12]}$$

$$where: K_2 = 10\log\left[\frac{4\pi}{c^2} \bullet \left(\begin{matrix} Frequency\ and\ RCS \\ conversions\ as\ required \end{matrix} \quad \frac{(Hz\ to\ MHz\ or\ GHz)^2}{(meters\ to\ feet)^2}\right)\right]$$

The "Target Gain Factor" (G_σ) is a composite of RCS, frequency, and dimension conversion factors and is called by various names: "Gain of RCS", "Equivalent Gain of RCS", "Gain of Target Cross Section", and in dB form "Gain-sub-Sigma".

If frequency is given in MHz and RCS (σ) is in m^2, the formula for G_σ is:

$$G_\sigma = 10\log\sigma + 20\log f_1 + 10\log\left[4\pi \bullet \left(\frac{\sec}{3\,x\,10^8\,m}\right)^2 \bullet m^2 \bullet \left(\frac{1x\,10^6}{\sec}\right)^2\right] \qquad \textbf{[13]}$$

or:

$$G_\sigma = 10\log\sigma + 20\log f_1 - 38.54 \quad (in\ dB) \qquad \textbf{[14]}$$

Target gain factor, G_σ = 10log σ + 20log f_1 + K_2 (in dB)

K_2 Values

(dB)	RCS (σ)	f_1 in MHz	f_1 in GHz
(units)	K $_2$ =	K $_2$ =	
m^2	-38.54	21.46	
ft^2	-48.86	11.14	

For this example, the constant K_2 is -38.54 dB. K_2 values for various area and frequency and frequency units are summarized in the adjoining table.

In the two-way radar equation, the one-way free space loss factor (α_1) is used twice, once for the radar transmitter to target path and once for the target to radar receiver path. The radar illustrated in Figure 1 is monostatic so the two path losses are the same and the values of the two α_1's are the same.

If the transmission loss in Figure 1 from P_t to G_t equals the loss from G_r to P_r, and $G_r = G_t$, then equation [10] can be written as:

$$10\log\,[S\text{ or }P_r] = 10\log P_t + 20\log G_{tr} - 2\alpha_1 + G_\sigma \quad \text{(in dB)} \qquad \textbf{[15]}$$

The space loss factor (α_1) and the target gain factor (G_σ) include all the necessary unit conversions so that they can be used directly with the most common units. Because the factors are given in dB form, they are more convenient to use and allow calculation without a calculator when the factors are read from a chart or nomograph.

Most radars are monostatic. That is, the radar transmitting and receiving antennas are literally the same antenna. There are some radars that are considered "monostatic" but have separate transmitting and receiving antennas that are co-located. In that case, equation [10] could require two different antenna gain factors as originally derived:

$$10\log\,[S\text{ or }P_r] = 10\log P_t + 10\log G_t + 10\log G_r - 2\alpha_1 + G_\sigma \quad \text{(in dB)} \qquad \textbf{[16]}$$

Note: To avoid having to include additional terms for these calculations, always combine any transmission line loss with antenna gain.

Figure 2 is the visualization of the path losses occurring with the two-way radar equation. **Note:** to avoid having to include additional terms, always combine any transmission line loss with antenna gain. Losses due to antenna polarization and atmospheric absorption also need to be included.


*If power is actually measured in region A or B, it is stated in either power density (mW/cm²) or field intensity (V/m)
Note: Not to scale
SIGNAL STRENGTH in dBm
P_T
ERP
Transmitter Power
Transmit Antenna Gain
A*
Space Loss Approaching Target
Target Gain Factor
B*
Space Loss Returning From Target
Rcvr Antenna Gain
P_R
Radar Receiver
10 log P_t + 10 log G_t
- α
+ G_σ
- α
+ 10 log G_r =10 log P_r
SIGNAL POSITION IN SPACE

Figure 2. Visualization of Two-Way Radar Equation.

RADAR RANGE EQUATION (Two-Way Equation)

The Radar Equation is often called the "Radar Range Equation." The Radar Range Equation is simply the Radar Equation rewritten to solve for maximum Range. The maximum radar range (R_{max}) is the distance beyond which the target can no longer be detected and correctly processed. It occurs when the received echo signal just equals S_{min}.

The Radar Range Equation is then:

$$R_{\max} \cong \left[\frac{P_t G_t G_r \lambda^2 \sigma}{(4\pi)^3 S_{\min}}\right]^{\frac{1}{4}} \text{ or } \left[\frac{P_t G_t G_r c^2 \sigma]}{(4\pi)^3 f^{\,2} S_{\min}}\right]^{\frac{1}{4}} \text{ or } \left[\frac{P_t G_t A_e \sigma}{(4\pi)^2 S_{\min}}\right]^{\frac{1}{4}} \qquad \textbf{[17]}$$

The first equation, of the three above, is given in Log form by:

$$40\log R_{max} \cong 10\log P_t + 10\log G_t + 10\log G_r + 10\log \sigma - 10\log S_{min} - 20\log f - 30\log 4\pi + 20\log c \qquad \textbf{[18]}$$

As shown previously, Since K_1 = 20log [(4π/c) times conversion units if not in m/sec, m, and Hz], we have:

$$10\log R_{\max} \cong \tfrac{1}{4}\left[10\log P_t + 10\log G_t + 10\log G_r + 10\log \sigma - 10\log S_{\min} - 20\log f_1 - K_1 - 10.99\ \text{dB}\right] \qquad \textbf{[19]}$$

If you want to convert back from dB, then

$$R_{\max} \cong 10^{\frac{M\ dB}{40}}$$

Where M dB is the resulting number within the brackets of equation 19.

One-way free space loss, α_1 = 20log (f_1R) + K_1 (in dB)

K_1 Values (dB)	Range (units)	f_1 in MHz K_1 =	f_1 in GHz K_1 =
	NM	37.8	97.8
	Km	32.45	92.45
	m	-27.55	32.45
	yd	-28.33	31.67
	ft	-37.87	22.13

From Section 5-2, Receiver Sensitivity / Noise, $S_{\min}$ is related to the noise factors by:

$$S_{\min} = (S/N)_{\min}(NF)kT_0B \qquad \textbf{[20]}$$

The Radar Range Equation for a tracking radar (target continuously in the antenna beam) becomes:

$$R_{\max} \cong \left[\frac{P_t G_t G_r \lambda^2 \sigma}{(4\pi)^3 (S/N)_{\min}(NF)kT_0B}\right]^{\frac{1}{4}} \text{ or } \left[\frac{P_t G_t G_r c^2 \sigma}{(4\pi)^3 f^2 (S/N)_{\min}(NF)kT_oB}\right]^{\frac{1}{4}} \text{ or } \left[\frac{P_t G_t A_e \sigma}{(4\pi)^2 (S/N)_{\min}(NF)kT_oB}\right]^{\frac{1}{4}} \qquad \textbf{[21]}$$

P_t in equations [17], [19], and [21] is the peak power of a CW or pulse signal. For pulse signals these equations assume the radar pulse is square. If not, there is less power since P_t is actually the average power within the pulse width of the radar signal. Equations [17] and [19] relate the maximum detection range to $S_{\min}$, the minimum signal which can be detected and processed (the receiver sensitivity). The bandwidth (B) in equations [20] and [21] is directly related to $S_{\min}$. B is approximately equal to 1/PW. Thus a wider pulse width means a narrower receiver bandwidth which lowers $S_{\min}$, assuming no integration.

One cannot arbitrarily change the receiver bandwidth, since it has to match the transmitted signal. The “widest pulse width” occurs when the signal approaches a CW signal (see Section 2-11). A CW signal requires a very narrow bandwidth (approximately 100 Hz). Therefore, receiver noise is very low and good sensitivity results (see Section 5-2). If the radar pulse is narrow, the receiver filter bandwidth must be increased for a match (see Section 5-2), i.e. a 1 μs pulse requires a bandwidth of approximately 1 MHz. This increases receiver noise and decreases sensitivity.

If the radar transmitter can increase its PRF (decreasing PRI) and its receiver performs integration over time, an increase in PRF can permit the receiver to “pull” coherent signals out of the noise thus reducing $S/N_{\min}$ thereby increasing the detection range. Note that a PRF increase may limit the maximum range due to the creation of overlapping return echoes (see Section 2-10).

There are also other factors that limit the maximum practical detection range. With a scanning radar, there is loss if the receiver integration time exceeds the radar’s time on target. Many radars would be range limited by line-of-sight/radar horizon (see Section 2-9) well before a typical target faded below $S_{\min}$. Range can also be reduced by losses due to antenna polarization and atmospheric absorption (see Sections 3-2 and 5-1).

Two-Way Radar Equation (Example)

Assume that a 5 GHz radar has a 70 dBm (10 kilowatt) signal fed through a 5 dB loss transmission line to a transmit/receive antenna that has 45 dB gain. An aircraft that is flying 31 km from the radar has an RCS of 9 m^2. What is the signal level at the input to the radar receiver? (There is an additional loss due to any antenna polarization mismatch but that loss will not be addressed in this problem). This problem continues in Sections 4-3, 4-7, and 4-10.

Answer:

Starting with: $10\log S = 10\log P_t + 10\log G_t + 10\log G_r + G_\sigma - 2\alpha_1$ (in dB)

We know that: $\alpha_1 = 20\log fR + K_1 = 20\log(5x31) + 92.44 = 136.25$ dB

and that: $G_\sigma = 10\log \sigma + 20\log f_1 + K_2 = 10\log 9 + 20\log 5 + 21.46 = 44.98$ dB (see Table 1)
(Note: The aircraft transmission line losses (-5 dB) will be combined with the antenna gain (45 dB) for both receive and transmit paths of the radar)

So, substituting in we have: $10\log S = 70 + 40 + 40 + 44.98 - 2(136.25) =$ **-77.52 dBm** @ 5 GHz

The answer changes to -80.44 dBm if the tracking radar operates at 7 GHz provided the antenna gains and the aircraft RCS are the same at both frequencies.

$\alpha_1 = 20\log(7x31) + 92.44 = 139.17$ dB, $G_\sigma = 10\log 9 + 20\log 7 + 21.46 = 47.9$ dB (see Table 1)

$10\log S = 70 + 40 + 40 + 47.9 - 2(139.17) =$ **-80.44 dBm** @ 7 GHz

Table 1. Values of the Target Gain Factor (G_σ) in dB for Various Values of Frequency and RCS.

Frequency (GHz)	RCS - Square meters						
	0.05	5	9	10	100	1,000	10,000
0.5 GHz	2.44	22.42	24.98	25.44	35.44	45.44	55.44
1 GHz	8.46	28.46	31.0	31.46	41.46	51.46	61.46
5 GHz	22.44	42.44	44.98	45.44	55.44	65.44	75.44
7 GHz	25.36	45.36	47.9	48.36	58.36	68.36	78.36
10 GHz	28.46	48.46	51.0	51.46	61.46	71.46	81.46
20 GHz	34.48	54.48	57.02	57.48	67.48	77.48	87.48
40 GHz	40.50	60.48	63.04	63.5	73.5	83.5	93.5

Note: Shaded values were used in the examples.

TWO-WAY RADAR RANGE INCREASE AS A RESULT OF A SENSITIVITY INCREASE

As shown in equation [17] $S_{min}^{-1} \propto R_{max}^4$. Therefore, $-10\log S_{min} \propto 40\log R_{max}$ and the table below results:

% Range Increase: Range + (% Range Increase) x Range = New Range
i.e., for a 12 dB sensitivity increase, 500 miles +100% x 500 miles = 1,000 miles
Range Multiplier: Range x Range Multiplier = New Range
i.e., for a 12 dB sensitivity increase 500 miles x 2 = 1,000 miles

Table 2. Effects of Sensitivity Increase.

dB Sensitivity Increase	% Range Increase	Range Multiplier	dB Sensitivity Increase	% Range Increase	Range Multiplier
+ 0.5	3	1.03	10	78	1.78
1.0	6	1.06	11	88	1.88
1.5	9	1.09	12	100	2.00
2	12	1.12	13	111	2.11
3	19	1.19	14	124	2.24
4	26	1.26	15	137	2.37
5	33	1.33	16	151	2.51
6	41	1.41	17	166	2.66
7	50	1.50	18	182	2.82
8	58	1.58	19	198	2.98
9	68	1.68	20	216	3.16

TWO-WAY RADAR RANGE DECREASE AS A RESULT OF A SENSITIVITY DECREASE

As shown in equation [17] $S_{min}^{-1} \propto R_{max}^{4}$ Therefore, $-10 \log S_{min} \propto 40 \log R_{max}$ and the table below results:

% Range Decrease: Range - (% Range Decrease) x Range = New Range
i.e., for a 12 dB sensitivity decrease, 500 miles - 50% x 500 miles = 250 miles

Range Multiplier: Range x Range Multiplier = New Range
i.e., for a 12 dB sensitivity decrease 500 miles x 0.5 = 250 miles

Table 3. Effects of Sensitivity Decrease.

dB Sensitivity Decrease	% Range Decrease	Range Multiplier	dB Sensitivity Decrease	% Range Decrease	Range Multiplier
- 0.5	3	0.97	-10	44	0.56
- 1.0	6	0.94	- 11	47	0.53
- 1.5	8	0.92	- 12	50	0.50
- 2	11	0.89	- 13	53	0.47
- 3	16	0.84	- 14	55	0.45
- 4	21	0.79	- 15	58	0.42
- 5	25	0.75	- 16	60	0.40
- 6	29	0.71	- 17	62	0.38
- 7	33	0.67	- 18	65	0.35
- 8	37	0.63	- 19	67	0.33
- 9	40	0.60	- 20	68	0.32

ALTERNATE TWO-WAY RADAR EQUATION

In this section the same radar equation factors are grouped differently to create different constants as is used by some authors.

TWO-WAY RADAR EQUATION (MONOSTATIC)

Peak power at the radar receiver input is:

$$P_r = \frac{P_t G_t G_r \lambda^2 \sigma}{(4\pi)^3 R^4} = \frac{P_t G_t G_{rsigma} c^2}{(4\pi)^3 f^2 R^4} * \quad (Note: \lambda = \frac{c}{f} \text{ and } \sigma \text{ is } RCS) \qquad \textbf{[1]}$$

* Keep λ or c, σ, and R in the same units. On reducing the above equation to log form we have:

or: $\mathbf{10\log P_r = 10\log P_t + 10\log G_t + 10\log G_r - \alpha_2}$ (in dB)

Where: $\alpha_2 = 20\log f_1 R^2 - 10\log \sigma + K_3$, and $K_3 = -10\log c^2/(4\pi)^3$

Note:
Losses due to antenna polarization and atmospheric absorption (Sections 3-2 and 5-1) are not included in these equations

K_3 Values:
(dB)

Range Units	f_1 in MHz σ in m^2	f_1 in GHz σ in m^2	f_1 in MHz σ in ft^2	f_1 in GHz σ in ft^2
NM	114.15	174.15	124.47	184.47
km	103.44	163.44	113.76	173.76
m	-16.56	43.44	-6.24	53.76
yd	-18.1	41.9	-7.78	52.22
ft	-37.2	22.8	-26.88	33.12

In the last section, we had the basic radar equation given as equation [6] and it is repeated as equation [1] in the table above.

In Section 4-4, in order to maintain the concept and use of the one-way space loss coefficient, α_1, we didn't cancel like terms which was done to form equation [6] there. Rather, we regrouped the factors of equation [5]. This resulted in two minus α_1 terms and we defined the remaining term as G_σ, which accounted for RCS (see equation [8] & [9]).

Some authors take a different approach, and instead develop an entirely new single factor α_2, which is used instead of the combination of α_1 and G_σ.

If equation [1] is reduced to log form, (and noting that $f = c/\lambda$) it becomes:

$$10\log P_r = 10\log P_t + 10\log G_t + 10\log G_r - 20\log (f R^2) + 10\log \sigma + 10\log (c^2/(4\pi)^3) \qquad \textbf{[2]}$$

We now call the last three terms on the right minus α_2 and use it as a single term instead of the two terms α_1 and G_σ. The concept of dealing with one variable factor may be easier although we still need to know the range, frequency, and radar cross section to evaluate α_2. Additionally, we can no longer use a nomograph like we did in computing α_1 and visualize a two-way space loss consisting of two times the one-way space loss, since there are now 3 variables vs. two.

Equation [2] reduces to:

$$\mathbf{10\log P_r = 10\log P_t + 10\log G_t + 10\log G_r - \alpha_2} \qquad \text{(in dB)} \qquad \textbf{[3]}$$

Where α_2 = 20log (f_1R^2) - 10log σ + K_3 and where f_1 is the MHz or GHz value of frequency and K_3 = -10log ($c^2/(4\pi)^3$) + 20log (conversion for Hz to MHz or GHz)+ 40log (range unit conversions if not in meters) - 20log (RCS conversions for meters to feet)

The values of K_3 are given in the table above.

Comparing equation [3] to equation [10] in Section 4-4, it can be seen that $\alpha_2 = 2\alpha_1 - G_\sigma$.

TWO-WAY RADAR EQUATION (BISTATIC)

The following table contains a summary of the equations developed in this section.

TWO-WAY RADAR EQUATION (BISTATIC)

Peak power at the radar receiver input is:

$$P_r = \frac{P_t\, G_t\, G_r\, \lambda^2\, \sigma}{(4\pi)^3\, R_{Tx}^2\, R_{Rx}^2} = P_t\, G_t\, G_r \left[\frac{\sigma\, c^2}{(4\pi)^3\, f^{\,2}\, R_{Tx}^2\, R_{Rx}^2}\right]^*$$

Note : $\lambda = c/f$ and $\sigma = RCS$

** keep λ or $c, \sigma,$ and R in the same units*

On reducing the above equation to log form we have:
$10\log P_r = 10\log P_t + 10\log G_t + 10\log G_r + 10\log \sigma - 20\log f + 20\log c - 30\log 4\pi - 20\log R_{Tx} - 20\log R_{Rx}$

or in simplified terms: $10\log P_r = 10\log P_t + 10\log G_t + 10\log G_r + G_\sigma - \alpha_{Tx} - \alpha_{Rx}$ (in dB)

Where α_{Tx} corresponds to transmitter to target loss and α_{Rx} corresponds to target to receiver loss.

Note: Losses due to antenna polarization and atmospheric absorption (Sections 3-2 and 5-1) are not included in these equations.

Target gain factor, $G_\sigma = 10\log \sigma + 20\log f_1 + K_2$ (in dB)

K_2 Values (dB)	RCS (σ) (units)	f_1 in MHz K_2 =	f_1 in GHz K_2 =
	m^2	-38.54	21.46
	ft^2	-48.86	11.14

One-way free space loss, $\alpha_{Tx\text{ or }Rx} = 20\log(f_1 R_{Tx\text{ or }Rx}) + K_1$ (in dB)

K_1 Values (dB)	Range (units)	f_1 in MHz K_1 =	f_1 in GHz K_1 =
	NM	37.8	97.8
	Km	32.45	92.45
	m	-27.55	32.45
	yd	-28.33	31.67
	ft	-37.87	22.13

BISTATIC RADAR

There are also true bistatic radars - radars where the transmitter and receiver are in different locations as is depicted in Figure 1. The most commonly encountered bistatic radar application is the semi-active missile. The transmitter is located on, or near, the launch platform (surface or airborne), and the receiver is in the missile which is somewhere between the launch platform and the target.

The transmitting and receiving antennas are not the same and are not in the same location. Because the target-to-radar range is different from the target-to-missile range, the target-to-radar and target-to-missile space losses are different.


PHYSICAL CONCEPT
G_t
P_t
TRANSMITTER
TRANSMITTER TO TARGET
α_{Tx}, ONE-WAY SPACE LOSS
G_σ
GAIN OF RCS
P_r
RECEIVER
G_r
TARGET TO RECEIVER
α_{Rx} ONE-WAY SPACE LOSS
EQUIVALENT CIRCUIT
P_t
TRANSMITTER
G_t
R_{Tx}
TRANSMITTER TO TARGET
α_{Tx}, ONE-WAY SPACE LOSS
G_σ
GAIN OF RCS
RECEIVER
P_r
G_r
TARGET TO RECEIVER
α_{Rx} ONE-WAY SPACE LOSS
R_{Rx}

Figure 1. Bistatic Radar Visualized.

The peak power at the radar receiver input is:

$$P_r = \frac{P_t\, G_t\, G_r\, \lambda^2\, \sigma}{(4\pi)^3\, R_{Tx}^2\, R_{Rx}^2} = P_t\, G_t\, G_r \left[\frac{\sigma\, c^2}{(4\pi)^3\, f^{\,2}\, R_{Tx}^2\, R_{Rx}^2} \right] \qquad (\,Note : \lambda = \frac{c}{f} \; and \; \sigma = RCS) \qquad \textbf{[1]}$$

Keep λ or c, σ, and R in the same units.

On reducing the above equation to log form we have:

$$10\log P_r = 10\log P_t + 10\log G_t + 10\log G_r + 10\log \sigma - 20\log f + 20\log c - 30\log 4\pi - 20\log R_{Tx} - 20\log R_{Rx} \quad \textbf{[2]}$$

or in simplified terms:

$$10\log P_r = 10\log P_t + 10\log G_t + 10\log G_r + G_\sigma - \alpha_{Tx} - \alpha_{Rx} \quad \text{(in dB)} \qquad \textbf{[3]}$$

Where α_{Tx} corresponds to transmitter to target loss and α_{Rx} corresponds to target to receiver loss, or:

$\alpha_{Tx} = 20\log(f_1 T_{Tx}) + K_1$ (in dB) and $\alpha_{Rx} = 20\log(f_1 T_{Rx}) + K_1$ (in dB)

with K_1 values provided on page 4-6.1 and with f_1 being the MHz or GHz value of frequency.

Therefore, the difference between monostatic and bistatic calculations is that two α's are calculated for two different ranges and different gains may be required for transmit and receive antennas.

To avoid having to include additional terms for these calculations, always combine any transmission line loss with antenna gain.

As shown in Figure 2, it should also be noted that the bistatic RCS received by the missile is not always the same as the monostatic RCS. In general, the target's RCS varies with angle. Therefore, the bistatic RCS and monostatic RCS will be equal for receive and transmit antennas at the same angle to the target (but only if all three are in a line, as RCS also varies with elevation angle).



Figure 2. Bistatic RCS Varies.

JAMMING TO SIGNAL (J/S) RATIO - CONSTANT POWER [SATURATED] JAMMING

The following table contains a summary of the equations developed in this section.

JAMMING TO SIGNAL (J/S) RATIO (MONOSTATIC)

$J/S = (P_j G_{ja} 4\pi R^2) / (P_t G_t \sigma)$ (ratio form)* or:

$10\log J/S = 10\log P_j + 10\log G_{ja} - 10\log P_t - 10\log G_t - 10\log\sigma^* + 10.99 \text{ dB} + 20\log R^*$

Note (1): Neither f nor λ terms are part of these equations

If simplified radar equations developed in previous sections are used:

$10\log J/S = 10\log P_j + 10\log G_{ja} - 10\log P_t - 10\log G_t - G_\sigma + \alpha_1$ (in dB)

Note (2): the $20\log f_1$ term in $-G_\sigma$ cancels the $20\log f_1$ term in α_1

JAMMING TO SIGNAL (J/S) RATIO (BISTATIC)

R_{Tx} is the range from the radar transmitter to the target. See note (1).

$J/S = (P_j G_{ja} 4\pi R_{Tx}^2) / (P_t G_t \sigma)$ (ratio form) * or:

$10\log J/S = 10\log P_j + 10\log G_{ja} - 10\log P_t - 10\log G_t - 10\log\sigma^* + 10.99 \text{ dB} + 20\log R_{Tx}^*$

If simplified radar equations developed in previous sections are used: see note (2).

$10\log J/S = 10\log P_j + 10\log G_{ja} - 10\log P_t - 10\log G_t - G_\sigma + \alpha_{Tx}$ (in dB)

* Keep R and σ in same units

Target gain factor, (in dB)
$G_\sigma = 10\log\sigma + 20\log f_1 + K_2$

K_2 Values (dB):

RCS (σ) (units)	f_1 in MHz $K_2 =$	f_1 in GHz $K_2 =$
m2	-38.54	21.46
ft2	-48.86	11.14

One-way free space loss (dB)

α_1 or $\alpha_{Tx} =$
$20\log (f_1 R) + K_1$

K_1 Values (dB):

Range (units)	f_1 in MHz $K_1 =$	f_1 in GHz $K_1 =$
NM	37.8	97.8
km	32.45	92.45
m	-27.55	32.45
ft	-37.87	22.13

This section derives the J/S ratio from the one-way range equation for J and the two-way range equation for S, and deals exclusively with active (transmitting) Electronic Attack (EA) devices or systems. Furthermore, the only purpose of EA is to prevent, delay, or confuse the radar processing of target information.

By official definition, EA can be either Jamming or Deception. This may be somewhat confusing because almost any type of active EA is commonly called “jamming,” and the calculations of EA signal in the radar compared to the target signal in the radar commonly refer to the “jamming-to-signal” ratio (“J-to-S” ratio). Therefore this section uses the common jargon and the term “jammer” refers to any EA transmitter, and the term “jamming” refers to any EA transmission, whether Deception or Concealment.

Jamming: “Official” jamming should more aptly be called Concealment or Masking. Essentially, Concealment uses electronic transmissions to swamp the radar receiver and hide the targets. Concealment (Jamming) usually uses some form of noise as the transmitted signal. In this section, Concealment will be called “noise” or “noise jamming.”

Deception: Deception might be better called Forgery. Deception uses electronic transmissions to forge false target signals that the radar receiver accepts and processes as real targets.

“J” designates the EA signal strength whether it originates from a noise jammer or from a deception system.

Basically, there are two different methods of employing active EA against hostile radars:

Self Protection EA
Support EA

For most practical purposes, Self Protection EEA is usually Deception and Support EA is usually noise jamming. As the name implies, Self Protection EA is EA that is used to protect the platform that it is on. Self Protection EA is often called “self screening jamming,” “Defensive EA” or historically “Deception ECM.” The top half of Figure 1 shows self-screening jamming.



Figure 1. Self Protection and Escort Jamming.

The bottom half of Figure 1 illustrates escort jamming which is a special case of support jamming. If the escort platform is sufficiently close to the target, the J-to-S calculations are the same as for self protection EA.



Figure 2. Support Jamming.

Support EA is electronic transmissions radiated from one platform and is used to protect other platforms or fulfill other mission requirements, like distraction or conditioning. Figure 2 illustrates two cases of support jamming protecting a striker - stand-off jamming (SOJ) and stand-in jamming (SIJ). For SOJ the support jamming platform is maintaining an orbit at a long range from the radar - usually beyond weapons range. For SIJ, a remotely piloted vehicle is orbiting very close to the victim radar. Obviously, the jamming power required for the SOJ to screen a target is much greater than the jamming power required for the SIJ to screen the same target.

When factoring EA into the radar equation, the quantities of greatest interest are “J-to-S” and Burn-Through Range.

“J-to-S” is the ratio of the signal strength of the jammer signal (J) to the signal strength of the target return signal (S). It is expressed as “J/S” and, in this section, is always in dB. J usually (but not always) must exceed S by some amount to be effective, therefore the desired result of a J/S calculation in dB is a positive number. Burn-through Range is the radar to target range where the target return signal can first be detected through the jamming and is usually slightly farther than crossover range where J=S. It is usually the range where the J/S just equals the minimum effective J/S (See Section 4-8).

The significance of “J-to-S” is sometimes misunderstood. The effectiveness of EA **is not** a direct mathematical function of “J-to-S.” The magnitude of the “J-to-S” required for effectiveness is a function of the particular EA technique and of the radar it is being used against. Different EA techniques may very well require different “J-to-S” ratios against the same radar. When there is sufficient “J-to-S” for effectiveness, increasing it will rarely increase the effectiveness at a given range. Because modern radars can have sophisticated signal processing and/or EP capabilities, in certain radars too much “J-to-S” could cause the signal processor to ignore the jamming, or activate special anti-jamming modes. Increasing “J-to-S” (or the jammer power) does, however, allow the target aircraft to get much closer to the threat radar before burn-through occurs, which essentially means more power is better if it can be controlled when desired.

IMPORTANT NOTE: If the signal S is CW or PD and the Jamming J is amplitude modulated, then the J used in the formula has to be reduced from the peak value (due to sin x/x frequency distribution). The amount of reduction is dependent upon how much of the bandwidth is covered by the jamming signal. To get an exact value, integrals would have to be taken over the bandwidth. As a rule of thumb however:

- If the frequency of modulation is less than the BW of the tracking radar reduce J/S by 10 Log (duty cycle).
- If the frequency of modulation is greater than the BW of the tracking radar reduce J/S by 20 Log(duty cycle).

For example; if your jamming signal is square wave chopped (50% duty cycle) at a 100 Hz rate while jamming a 1 kHz bandwidth receiver, then the J/S is reduced by 3 dB from the maximum. If the duty cycle was 33%, then the reduction would be 4.8 dB. If the 50% and 33% duty cycle jamming signals were chopped at a 10 kHz (vice the 100 Hz) rate, the rule of thumb for jamming seen by the receiver would be down 6 dB and 9.6 dB, respectively, from the maximum since the 10 kHz chopping rate is greater than the 1 kHz receiver BW.

J/S for SELF PROTECTION EA vs. MONOSTATIC RADAR

Figure 3 is radar jamming visualized. The Physical concept of Figure 3 shows a monostatic radar that is the same as Figure 1, Section 4-4, and a jammer (transmitter) to radar (receiver) that is the same as Figure 3, Section 4-3. In other words, Figure 3 is simply the combination of the previous two visual concepts where there is only one receiver (the radar’s).



Figure 3. Radar Jamming Visualized.

The equivalent circuit shown in Figure 4 applies to jamming monostatic radars with either self protect EA or support EA. For self protect (or escort) vs. a monostatic radar, the jammer is on the target and the radar receive and transmit antennas are collocated so the three ranges and three space loss factors (α's) are the same.


MONOSTATIC
EQUIVALENT CIRCUIT
For Monostatic
R = R_Tx = R_Rx = R_Jx
α1 = α Tx = α Rx = α Jx
P_t
G_t
α_1 or Tx, ONE-WAY SPACE LOSS
R_Tx
G_σ
COLLOCATED
TRANSMITTER
RADAR
ANTENNA
GAIN
α_1 or Rx, ONE-WAY SPACE LOSS
GAIN OF RCS
COLLOCATED
R_Rx
TARGET
RECEIVER
P_r
G_r
α_1 or Jx, ONE-WAY SPACE LOSS
R_Jx
G_JA
P_t
(TOTAL SIGNAL = J + S)
JAMMER
ANTENNA
GAIN (G_JA)
JAMMER
POWER (P_J)
SIGNAL = POWER + GAINS - LOSSES (in dB)

Figure 4. Monostatic Radar EA Equivalent Circuit.

J-S Ratio (Monostatic) - The ratio of the power received (P_{r1} or J) from the jamming signal transmitted from the target to the power received (P_{r2} or S) from the radar skin return from the target equals J/S.

From the one way range equation in Section 4-3: $P_r 1 \text{ or } J = \dfrac{P_j\, G_{ja}\, G_r\, \lambda^2}{(4\pi R)^2}$ **[1]**

From the two way range equation in Section 4.4: $P_r 2 \text{ or } S = \dfrac{P_t\, G_t\, G_r\, \lambda^2\, \sigma}{(4\pi)^3\, R^4}$ **[2]**

so $$\frac{J}{S} = \frac{P_j\, G_{ja}\, G_r\, \lambda^2 (4\pi)^3\, R^4}{P_t\, G_t\, G_r\, \lambda^2\, \sigma\, (4\pi R)^2} = \frac{P_j\, G_{ja}\, 4\pi\, R^2}{P_t\, G_t\, \sigma}^{*} \qquad \textit{(ratio form)} \qquad \textbf{[3]}$$

* Keep R and σ in the same units.

On reducing the above equation to log form we have:

$10\log J/S = 10\log P_j + 10\log G_{ja} - 10\log P_t - 10\log G_t - 10\log \sigma + 10\log 4\pi + 20\log R$ **[4]**

or $10\log J/S = 10\log P_j + 10\log G_{ja} - 10\log P_t - 10\log G_t - 10\log \sigma + 10.99\text{ dB} + 20\log R$ **[5]**

Note: Neither *f* nor λ terms are part of the final form of equation [3] and equation [5].

J/S Calculations (Monostatic) Using a One Way Free Space Loss - The simplified radar equations developed in previous sections can be used to express J/S.

From the one way range equation Section 4-3:

$$10\log(P_{r1} \text{ or } J) = 10\log P_j + 10\log G_{ja} + 10\log G_r - \alpha_1 \qquad \text{(in dB)}$$ **[6]**

From the two way range equation in Section 4.4:

$$10\log(P_{r2} \text{ or } S) = 10\log P_t + 10\log G_t + 10\log G_r + G_\sigma - 2\alpha_1 \qquad \text{(in dB)}$$ **[7]**

$$10\log(J/S) = 10\log P_j + 10\log G_{ja} - 10\log P_t - 10\log G_t - G_\sigma + \alpha_1 \qquad \text{(in dB)}$$ **[8]**

Note: To avoid having to include additional terms for these calculations, always combine any transmission line loss with antenna gain. The $20\log f_1$ term in $-G_\sigma$ cancels the $20\log f_1$ term in α_1.

Target gain factor, $G_\sigma = 10\log\sigma + 20\log f_1 + K_2$ (in dB)

K_2 Values (dB)	RCS (σ) (units)	f_1 in MHz $K_2 =$	f_1 in GHz $K_2 =$
	m^2	-38.54	21.46
	ft^2	-48.86	11.14

One-way free space loss, $\alpha_1 = 20\log(f_1R) + K_1$ (in dB)

K_1 Values (dB)	Range (units)	f_1 in MHz $K_1 =$	f_1 in GHz $K_1 =$
	NM	37.8	97.8
	km	32.45	92.45
	m	-27.55	32.45
	yd	-28.33	31.67
	ft	-37.87	22.13

J/S for SELF PROTECTION EA vs. BISTATIC RADAR

The semi-active missile illustrated in Figure 5 is the typical bistatic radar which would require the target to have self protection EA to survive. In this case, the jammer is on the target and the target to missile receiver range is the same as the jammer to receiver range, but the radar to target range is different. Therefore, only two of the ranges and two of the α's (Figure 6.) are the same.



Figure 5. Bistatic Radar.

In the following equations:

α_{Tx} = The one-way space loss from the radar transmitter to the target for range R_{Tx}
α_{Rx} = The one-way space loss from the target to the missile receiver for range R_{Rx}

Like the monostatic radar, the bistatic jamming and reflected target signals travel the same path from the target and enter the receiver (missile in this case) via the same antenna. In both monostatic and bistatic J/S equations this common range cancels, so both J/S equations are left with an R_{Tx}^2 or $20\log R_{Tx}$ term. Since in the monostatic case $R_{Tx} = R_{Rx}$ and $\alpha_{Tx} = \alpha_{Rx}$, only R or α_1 is used in the equations. Therefore, the bistatic J/S equations [11], [13], or [14] will work for monostatic J/S calculations, but the opposite is only true if bistatic R_{Tx} and α_{Tx} terms are used for R or α_1 terms in monostatic equations [3], [5], and [8].

The equivalent circuit shown in Figure 6 applies to jamming bistatic radar. For self protect (or escort) vs. a bistatic radar, the jammer is on the target and the radar receive and transmit antennas are at separate locations so only two of the three ranges and two of the three space loss factors (α's) are the same.


BISTATIC
EQUIVALENT CIRCUIT
For Bistatic
$R_{Rx} = R_{Jx} \neq R_{Tx}$
$\alpha_2 = \alpha_{Rx} = \alpha_{Jx} \neq \alpha_{Tx}$ and α_1
COLLOCATED
P_t
TRANSMITTER
G_t
RADAR ANTENNA GAIN
$\alpha_{1 \text{ or } Tx}$, ONE-WAY SPACE LOSS
R_{Tx}
G_σ
GAIN OF RCS
TARGET
$\alpha_{2 \text{ or } Rx}$, ONE-WAY SPACE LOSS
R_{Rx}
RECEIVER
P_r
G_r
SEPARATE LOCATIONS
(TOTAL SIGNAL = J + S)
$\alpha_{2 \text{ or } Jx}$, ONE-WAY SPACE LOSS
R_{Jx}
G_{JA}
P_t
JAMMER ANTENNA GAIN (G_{JA})
JAMMER POWER (P_J)
SIGNAL = POWER + GAINS - LOSSES (in dB)

Figure 6. Bistatic Radar EA Equivalent Circuit.

J-to-S Ratio (Bistatic) When the radar's transmit antenna is located remotely from the receiving antenna (Figure 6), the ratio of the power received (P_{r1} or J) from the jamming signal transmitted from the target to the power received (P_{r2} or S) from the radar skin return from the target equals J/S. For jammer effectiveness J normally has to be greater than S.

From the one way range equation in Section 4-3: $P_r 1 \text{ or } J = \frac{P_j G_{ja} G_r \lambda^2}{(4\pi R_{Rx})^2}$ $(R_{Jx} = R_{Rx})$ **[9]**

From the two way range equation in Section 4.4: $P_r 2 \text{ or } S = \frac{P_t G_t G_r \lambda^2 \sigma}{(4\pi)^3 R_{Tx}^2 R_{Rx}^2}$ **[10]**

so

$$\frac{J}{S} = \frac{P_j G_{ja} G_r \lambda^2 (4\pi)^3 R_{Tx}^2 R_{Rx}^2}{P_t G_t G_r \lambda^2 \sigma (4\pi R_{Rx})^2} = \frac{P_j G_{ja} 4\pi R_{Tx}^2}{P_t G_t \sigma}^{*} \qquad \textit{(ratio form)} \qquad \textbf{[11]}$$

* Keep R and σ in the same units.

On reducing the above equation to log form we have:

$$10\log J/S = 10\log P_j + 10\log G_{ja} - 10\log P_t - 10\log G_t - 10\log \sigma + 10\log 4\pi + 20\log R_{Tx} \qquad \textbf{[12]}$$

or

$$10\log J/S = 10\log P_j + 10\log G_{ja} - 10\log P_t - 10\log G_t - 10\log \sigma + 10.99 \text{ dB} + 20\log R_{Tx} \qquad \textbf{[13]}$$

Note: To avoid having to include additional terms for these calculations, always combine any transmission line loss with antenna gain. Neither *f* nor λ terms are part of the final form of equation [11] and equation [13].

Bistatic J/S Calculations (Bistatic) Using a One Way Free Space Loss - The simplified radar equations developed in previous sections can be used to express J/S.

From the one way range equation in Section 4-3:

$10\log(P_{r1} \text{ or } J) = 10\log P_j + 10\log G_{ja} + 10\log G_r - \alpha_{Rx}$ (all factors dB) **[14]**

From the two way range equation in Section 4-4:
$10\log(P_{r2} \text{ or } S) = 10\log P_t + 10\log G_t + 10\log G_r + G_\sigma - \alpha_{Tx} - \alpha_{Rx}$ (all factors dB) **[15]**

$10\log(J/S) = 10\log P_j + 10\log G_{ja} - 10\log P_t - 10\log G_t - G_\sigma + \alpha_{Tx}$ (all factors dB) **[16]**

Note: To avoid having to include additional terms for these calculations, always combine any transmission line loss with antenna gain. The $20\log f_1$ term in $-G_\sigma$ cancels the $20\log f_1$ term in α_1.

Target gain factor, $G_\sigma = 10\log\sigma + 20\log f_1 + K_2$ (in dB)			
K_2 Values (dB)	RCS (σ) (units)	f_1 in MHz K_2 =	f_1 in GHz K_2 =
	m^2	-38.54	21.46
	ft^2	-48.86	11.14

One-way free space loss $\alpha_{Tx\text{ or }Rx} = 20\log f_1 R_{Tx\text{ or }Rx} + K_1$ (in dB)			
K_1 Values (dB)	Range (units)	f_1 in MHz K_1 =	f_1 in GHz K_1 =
	NM	37.8	97.8
	km	32.45	92.45
	m	-27.55	32.45
	yd	-28.33	31.67
	ft	-37.87	22.13

Saturated J/S (Monostatic) Example (Constant Power Jamming)

Assume that a 5 GHz radar has a 70 dBm signal fed through a 5 dB loss transmission line to an antenna that has 45 dB gain. An aircraft is flying 31 km from the radar. The aft EW antenna has -1 dB gain and a 5 dB line loss to the EW receiver (there is an additional loss due to any antenna polarization mismatch but that loss will not be addressed in this problem). The aircraft has a jammer that provides 30 dBm saturated output if the received signal is above -35 dBm. The jammer feeds a 10 dB loss transmission line which is connected to an antenna with a 5 dB gain. If the RCS of the aircraft is 9 m^2, what is the J/S level received by the tracking radar?

Answer: The received signal at the jammer is the same as the example in Section 4-3, i.e. answer (1) = -32.3 dBm @ 5 GHz. Since the received signal is above -35 dBm, the jammer will operate in the saturated mode, and equation [5] can be used. (See Section 4-10 for an example of a jammer in the linear region.)

$10\log J/S = 10\log P_j + 10\log G_{ja} - 10\log P_t - 10\log G_t - 10\log\sigma + 10.99 \text{ dB} + 20\log R$

Note: the respective transmission line losses will be combined with antenna gains,
i.e. $-5 + 45 = 40$ dB & $-10 + 5 = -5$ dB.

$10\log J/S = 30 - 5 - 70 - 40 - 9.54 + 10.99 + 89.8 = 6.25$ dB @ 5 GHz*

* The answer is still 6.25 dB if the tracking radar operates at 7 GHz provided the antenna gains and the aircraft RCS are the same at both frequencies.

In this example, there is inadequate jamming power at each frequency if the J/S needs to be 10 dB or greater to be effective. One solution would be to replace the jammer with one that has a greater power output. If the antenna of the aircraft and the radar are not the proper polarization, additional power will also be required (see Section 3-2).

BURN-THROUGH / CROSSOVER RANGE

The burn-through equations are derived in this section. These equations are most commonly used in jammer type of applications. The following is a summary of the important equations explored in this section:

J/S CROSSOVER RANGE (MONOSTATIC) (J = S)

$R_{J=S} = [\ (P_t\ G_t\ \sigma) / (P_j\ G_{ja}\ 4\pi)\ ]^{1/2}$ (dB Ratio)

or $20 \log R_{J=S} = 10\log P_t + 10\log G_t + 10\log \sigma - 10\log P_j - 10\log G_{ja} - 10.99$ dB

If simplified radar equations already converted to dB are used:

$20 \log R_{J=S} = 10\log P_t + 10\log G_t + G_\sigma - 10\log P_j - 10\log G_{ja} - K_1 - 20\log f_1$ (dB)

BURN-THROUGH RANGE (MONOSTATIC)

The radar to target range where the target return signal (S) can first be detected through the EA (J).

$R_{BT} = [\ (P_t\ G_t\ \sigma\ J_{min\ eff}) / (P_j\ G_{ja}\ 4\pi\ S)\ ]^{1/2}$ (dB Ratio)

or $20\log R_{BT} = 10\log P_t + 10\log G_t + 10\log\sigma - 10\log P_j - 10\log G_{ja} + 10\log(J_{min\ eff}/S) - 10.99$

If simplified radar equations already converted to dB are used:

$20\log R_{BT} = 10\log P_t + 10\log G_t + G_\sigma - 10\log P_j - 10\log G_{ja} - K_1 + 10\log(J_{min\ eff}/S) - 20\log f_1$(in dB)*

f_1 is MHz or GHz value of frequency

* Keep P_t & P_j in same units
Keep R and σ in same units

K_1 Values (dB):

Range (units)	f_1 in MHz K_1 =	in GHz K_1 =
m	-27.55	32.45
ft	-37.87	22.13

Target gain factor (dB)

$G_\sigma = 10\log \sigma + 20\log f_1 + K_2$

K_2 Values (dB):

RCS (σ) (units)	f_1 in MHz K_2 =	in GHz K_2 =
m^2	-38.54	21.46
ft^2	-48.86	11.14

BURN-THROUGH RANGE (BISTATIC)

R_{Tx} is the range from the radar transmitter to the target and is different from R_{Rx} which is the range from the target to the receiver. Use Monostatic equations and substitute R_{Tx} for R

CROSSOVER RANGE and BURN-THROUGH RANGE

To present the values of J and S, (or J/S) over a minimum to maximum radar to target range of interest, equation [1], Section 4-7. which has a slope of 20 log for J vs. range and equation [2], Section 4-7, which has a slope of 40 log for S vs. range are plotted. When plotted on semi-log graph paper, J and S (or J/S) vs. range are straight lines as illustrated in Figure 1.

Figure 1 is a sample graph - it cannot be used for data.

The crossing of the J and S lines (known as crossover) gives the range where J = S (about 1.29 NM), and shows that shorter ranges will produce target signals greater than the jamming signal.



Figure 1. Sample J and S Graph.

The point where the radar power overcomes the jamming signal is known as burn-through. The crossover point where J = S could be the burn-through range, but it usually isn't because normally J/S > 0 dB to be effective due to the task of differentiating the signal from the jamming noise floor (see receiver sensitivity section). For this example, the J/S required for the EA to be effective is given as 6 dB, as shown by the dotted line. This required J/S line crosses the jamming line at about 2.8 NM which, in this example, is the burn-through range.

In this particular example, we have:

P_t = 80 dBm G_t = 42 dB
P_j = 50 dBm G_{ja} = 6 dB
σ = 18 m^2 f = 5.9 GHz (not necessary for all calculations)

A radar can be designed with higher than necessary power for earlier burn-through on jamming targets. Naturally that would also have the added advantage of earlier detection of non-jamming targets as well.

Note: To avoid having to include additional terms for the following calculations, always combine any transmission line loss with antenna gain.

CROSSOVER AND BURN-THROUGH RANGE EQUATIONS (MONOSTATIC)

To calculate the crossover range or burn-through range the J/S equation must be solved for range. From equation [3], Section 4-7:

$$\frac{J}{S} = \frac{P_j\, G_{ja}\, 4\pi\, R^2}{P_t\, G_t\, \sigma} \quad \textit{(ratio form)} \qquad \text{Solving for R:} \quad R = \sqrt{\frac{P_t\, G_t\, \sigma\, J}{P_j\, G_{ja}\, 4\pi\, S}} \qquad \textbf{[1]}$$

BURN-THROUGH RANGE (MONOSTATIC) - Burn-through Range (Monostatic) is the radar to target range where the target return signal (S) can first be detected through the jamming (J). It is usually the range when the J/S just equals the minimum effective J/S.

$$R_{BT} = \sqrt{\frac{P_t\, G_t\, \sigma\, J_{\min eff}}{P_j\, G_{ja}\, 4\pi\, S}} \quad \text{(burn-through range)} \qquad \textbf{[2]}$$

or in dB form, (using 10log 4π = 10.99 dB):

$$20\log R_{BT} = 10\log P_t + 10\log G_t + 10\log \sigma - 10\log P_j - 10\log G_{ja} + 10\log (J_{\min eff}/S) - 10.99 \text{ dB} \qquad \textbf{[3]}$$

RANGE WHEN J/S CROSSOVER OCCURS (MONOSTATIC) - The crossover of the jammer's 20 dB/decade power line and the skin return signal's 40 dB/decade power line of Figure 1 occurs for the case where J = S in dB or J/S=1 in ratio. Substituting into equation [1] yields:

$$R_{(J=S)} = \sqrt{\frac{P_t\, G_t\, \sigma}{P_j\, G_{ja}\, 4\pi}} \quad \text{(Crossover range)} \qquad \textbf{[4]}$$

or in dB form:

$$20\log R_{J=S} = 10\log P_t + 10\log G_t + 10\log \sigma - 10\log P_j - 10\log G_{ja} - 10.99 \text{ dB} \qquad \textbf{[5]}$$

Note: keep R and σ in same units in all equations.

CROSSOVER AND BURN-THROUGH EQUATIONS (MONOSTATIC) USING α - ONE WAY FREE SPACE LOSS

The other crossover burn-through range formulas can be confusing because a frequency term is subtracted (equations [6], [7] and [8]), but both ranges are independent of frequency. This subtraction is necessary because when J/S is calculated directly as previously shown, λ^2 or $(c/f)^2$ terms canceled, whereas in the simplified radar equations, a frequency term is part of the G_σ term and has to be cancelled if one solves for R. From equation [8], Section 4-7:

$$10\log J/S = 10\log P_j + 10\log G_{ja} - 10\log P_t - 10\log G_t - G_\sigma + \alpha_1 \quad \text{(factors in dB)}$$

or rearranging: $\alpha_1 = 10\log P_t + 10\log G_t + G_\sigma - 10\log P_j - 10\log G_{ja} + 10\log (J/S)$

from Section 4-4: $\alpha_1 = 20\log f_1 R_1 + K_1$ or $20\log R_1 = \alpha_1 - K_1 - 20\log f_1$

then substituting for α_1:

$$20\log R_1 = 10\log P_t + 10\log G_t + G_\sigma - 10\log P_j - 10\log G_{ja} - K_1 + 10\log (J/S) - 20\log f_1 \quad \text{(in dB)} \qquad \textbf{[6]}$$

EQUATION FOR BURN-THROUGH RANGE (MONOSTATIC) - Burn-through occurs at the range when the J/S just equals the minimum effective J/S. G_σ and K_1 are as defined on page 4-8.1.

$$20\log R_{BT} = 10\log P_t + 10\log G_t + G_\sigma - 10\log P_j - 10\log G_{ja} - K_1 + 10\log (J_{min\ eff}/S) - 20\log f_1 \quad \text{(in dB)} \quad \textbf{[7]}$$

EQUATION FOR THE RANGE WHEN J/S CROSSOVER OCCURS (MONOSTATIC)

The J/S crossover range occurs for the case where J = S, substituting into equation [6] yields:

$$20\log R_{J=S} = 10\log P_t + 10\log G_t + G_\sigma - 10\log P_j - 10\log G_{ja} - K_1 - 20\log f_1 \qquad \text{(factors in dB)} \qquad \textbf{[8]}$$

BURN-THROUGH RANGE (BISTATIC)

Bistatic J/S crossover range is the radar-to-target range when the power received (S) from the radar skin return from the target equals the power received (J) from the jamming signal transmitted from the target. As shown in Figure 6, Section 4-7, the receive antenna that is receiving the same level of J and S is remotely located from the radar's transmit antenna. Bistatic equations [11], [13], and [14] in Section 4-7 show that J/S is only a function of radar to target range, therefore J/S is not a function of wherever the missile is in its flight path provided the missile is in the antenna beam of the target's jammer. The missile is closing on the target at a very much higher rate than the target is closing on the radar, so the radar to target range will change less during the missile flight.

It should be noted that for a very long range air-to-air missile shot, the radar to target range could typically decrease to 35% of the initial firing range during the missile time-of-flight, i.e. A missile shot at a target 36 NM away, may be only 12 NM away from the firing aircraft at missile impact.

Figure 2 shows both the jamming radiated from the target and the power reflected from the target as a function of radar-to-target range. In this particular example, the RCS is assumed to be smaller, 15 m^2 vice 18 m^2 in the monostatic case, since the missile will be approaching the target from a different angle. This will not, however, always be the case.

In this plot, the power reflected is:

$$P_{ref} = \frac{P_t\, G_t\, 4\,\pi\,\sigma}{(4\pi R\,)^2}$$

Substituting the values given previously in the example on page 4-8.1, we find that the crossover point is at 1.18 NM (due to the assumed reduction in RCS).



Figure 2. Bistatic Crossover and Burnthrough.

CROSSOVER AND BURN-THROUGH RANGE EQUATIONS (BISTATIC)

To calculate the radar transmitter-to-target range where J/S crossover or burn-through occurs, the J/S equation must be solved for range. From equation [11] in Section 4-7:

$$\frac{J}{S} = \frac{P_j\, G_{ja}\, 4\pi\, R_{Tx}^2}{P_t\, G_t\, \sigma} \qquad \textit{(ratio form)}$$

Solving for R_{Tx}:

$$R_{Tx} = \sqrt{\frac{P_t\, G_t\, \sigma\, J}{P_j\, G_{ja}\, 4\pi\, S}} \qquad \textbf{[9]}$$

Note:
Bistatic equation [10] is identical to monostatic equation [1] except R_{Tx} must be substituted for R and a bistatic RCS (σ) will have to be used since RCS varies with aspect angle. The common explanations will not be repeated in this section.

BURN-THROUGH RANGE (BISTATIC) - Burn-through Range (Bistatic) occurs when J/S just equals the minimum effective J/S. From equation [9]:

$$R_{Tx(BT)} = \sqrt{\frac{P_t\, G_t\, \sigma\, J_{\min eff}}{P_j\, G_{ja}\, 4\pi\, S}} \qquad \textit{(ratio form)} \qquad \textbf{[10]}$$

or in dB form:

$$20\log R_{Tx(BT)} = 10\log P_t + 10\log G_t + 10\log \sigma - 10\log P_j - 10\log G_{ja} + 10\log (J_{min\ eff}/S) - 10.99\ \text{dB} \qquad \textbf{[11]}$$

If using the simplified radar equations (factors in dB):

$$20\log R_{Tx(BT)} = 10\log P_t + 10\log G_t + G_\sigma - 10\log P_j - 10\log G_{ja} - K_1 + 10\log (J_{min\ eff}/S) - 20\log f_1 \qquad \textbf{[12]}$$

Where G_σ and K_1 are defined on page 4-8.1

RANGE WHEN J/S CROSSOVER OCCURS (BISTATIC)

The crossover occurs when J = S in dB or J/S = 1 in ratio.

$$R_{Tx(J=S)} = \sqrt{\frac{P_t\, G_t\, \sigma}{P_j\, G_{ja}\, 4\pi}} \qquad (ratio) \qquad \textbf{[13]}$$

or in log form:

$$20\log R_{Tx(J=S)} = 10\log P_t + 10\log G_t + 10\log \sigma - 10\log P_j - 10\log G_{ja} - 10.99\ \text{dB} \qquad \textbf{[14]}$$

If simplified equations are used (with G_σ and K_1 as defined on page 4-8.1) we have:

$$20\log R_{Tx(J=S)} = 10\log P_t + 10\log G_t + G_\sigma - 10\log P_j - 10\log G_{ja} - K_1 - 20\log f_1 \qquad \text{(factors in dB)} \qquad \textbf{[15]}$$

Note: keep R and σ in same units in all equations.

DETAILS OF SEMI-ACTIVE MISSILE J/S

Unless you are running a large scale computer simulation that includes maneuvering, antenna patterns, RCS, etc., you will seldom calculate the variation in J/S that occurs during a semi-active missile's flight. Missiles don't fly straight lines at constant velocity. Targets don't either - they maneuver. If the launch platform is an aircraft, it maneuvers too. A missile will accelerate to some maximum velocity above the velocity of the launch platform and then decelerate.

The calculation of the precise variation of J/S during a missile flight for it to be effective requires determination of all the appropriate velocity vectors and ranges at the time of launch, and the accelerations and changes in relative positions during the fly out. In other words, it's too much work for too little return. The following are simplified examples for four types of intercepts.

In these examples, all velocities are constant, and are all along the same straight line. The missile velocity is 800 knots greater than the launch platform velocity which is assumed to be 400 kts. The missile launch occurs at 50 NM.

	J/S (dB)	ΔJ/S (dB)
At Launch:	29	n/a
Intercept Type	At 2 sec. to Intercept:	
AAM Head-on:	23	-6
SAM Incoming Target:	25	-4
AAM Tail Chase:	29	0
SAM Outbound Target:	35	+6

For the AAM tail chase, the range from the radar to the target remains constant and so does the J/S. **In these examples** the maximum variation from launch J/S is ± 6 dB. That represents the difference in the radar to target range closing at very high speed (AAM head on) and the radar to target range opening at moderate speed (SAM outbound target). The values shown above are examples, not rules of thumb, every intercept will be different.

Even for the simplified linear examples shown, graphs of the J and S will be curves - not straight lines. Graphs could be plotted showing J and S vs. radar to target range, or J and S vs. missile to target range, or even J/S vs. time of flight. If the J/S at launch is just barely the minimum required for effectiveness, and increasing it is difficult, then a detailed graph may be warranted, but in most cases this isn't necessary.

This page intentionally left blank.

SUPPORT JAMMING

The following table contains a summary of equations developed in this section:

MAIN LOBE JAMMING TO SIGNAL (J/S) RATIO (For SOJ/SIJ)

$$J/S = (P_j\ G_{ja}\ 4\pi\ R_{Tx}^4) / (P_t\ G_t\ \sigma\ [BW_J/BW_R]\ R_{Jx}^2) \quad \text{(ratio form)*}$$

$$10\log J/S = 10\log P_j - 10\log[BW_J/BW_R] + 10\log G_{ja} - 10\log P_t - 10\log G_t - 10\log \sigma + \downarrow$$

$$10.99\text{ dB} + 40\log R_{Tx} - 20\log R_{Jx}\ ^* \qquad \leftarrow\leftarrow$$

or if simplified radar equations are used:

$$10\log J/S = 10\log P_j - BF + 10\log G_{ja} - \alpha_{jx} - 10\log P_t - 10\log G_t - G_\sigma + 2\alpha_1 \quad \text{(in dB)*}$$

Target gain factor,

$G_\sigma = 10\text{Log}\sigma + 20\text{Log}f_1 + K_2$ (in dB)

K_2 Values (dB):

RCS (σ) (units)	f_1 in MHz K_2 =	f_1 in GHz K_2 =
m^2	-38.54	21.46
ft^2	-48.86	11.14

SIDE LOBE JAMMING TO SIGNAL (J/S) RATIO (For SOJ/SIJ)

$$J/S = (P_j\ G_{ja}\ G_{r(SL)}\ 4\pi\ R_{Tx}^4) / (P_t\ G_t\ G_{r(ML)}\ \sigma\ [BW_J/BW_R]\ R_{Jx}^2) \quad \text{(ratio form)*}$$

$$10\log J/S = 10\log P_j - BF + 10\log G_{ja} + 10\log G_{r(SL)} - 10\log P_t - 10\log G_t - 10\log G_{r(ML)} + \rightarrow\downarrow$$

$$10.99\text{ dB} - 10\log \sigma + 40\log R_{Tx} - 20\log R_{Jx}\ ^* \qquad \leftarrow\leftarrow$$

or if simplified radar equations are used (in dB)*:

$$10\log J/S = 10\log P_j - BF + 10\log G_{ja} + 10\log G_{r(SL)} - \alpha_{jx} - 10\log P_t - 10\log G_t - 10\log G_{r(ML)} - G_\sigma + 2\alpha_1$$

One-way free space loss,

α_1 or $\alpha_{Tx} = 20\text{Log}(f_1 R) + K_1$ (in dB)

K_1 Values (dB):

Range (units)	f_1 in MHz K_1 =	f_1 in GHz K_1 =
NM	37.8	97.8
Km	32.45	92.45
m	-27.55	32.45
yd	-28.33	31.67
ft	-37.87	22.13

R_{Jx}	Range from the support jammer transmitter to the radar receiver
R_{Tx}	Range between the radar and the target
BF	10 Log of the ratio of BW_J of the noise jammer to BW_R of the radar receiver
$G_{r(SL)}$	Side lobe antenna gain
$G_{r(ML)}$	Main lobe antenna gain
α_{JX}	One way free space loss between SOJ transmitter and radar receiver
α_1	One way space loss between the radar and the target

* Keep R and σ in same units

Support jamming adds a few geometric complexities. A SOJ platform usually uses high gain, directional antennas. Therefore, the jamming antenna must not only be pointed at the victim radar, but there must be alignment of radar, targets, and SOJ platform for the jamming to be most effective. Two cases will be described, main lobe-jamming and side-lobe jamming.



Figure 1. Radar Antenna Pattern.

Support jamming is usually applied against search and acquisition radars which continuously scan horizontally through a volume of space. The scan could cover a sector or a full 360°. The horizontal antenna pattern of the radar will exhibit a main lobe and side lobes as illustrated in Figure 1. The target is detected when the main lobe sweeps across it. For main lobe jamming, the SOJ platform and the target(s) must be aligned with the radar's main lobe as it sweeps the target(s).

For side lobe jamming, the SOJ platform may be aligned with one or more of the radar's side lobes when the main lobe sweeps the target. The gain of a radar's side lobes are many tens of dB less (usually more than 30 dB less) than the gain of the main lobe, so calculations of side lobe jamming must use the gain of the side lobe for the radar receive antenna gain, not the gain of the main lobe. Also, because many modern radars employ some form of side lobe blanking or side lobe cancellation, some knowledge of the victim radar is required to predict the effectiveness of side lobe jamming.

All radar receivers are frequency selective. That is, they are filters that allow only a narrow range of frequencies into the receiver circuitry. Deceptive EA, by definition, creates forgeries of the real signal and, ideally, are as well matched to the radar receiver as the real signal. On the other hand, noise jamming probably **will not match** the radar receiver bandwidth characteristics. Noise jamming is either spot jamming or barrage jamming. As illustrated in Figure 2, spot jamming is simply narrowing the bandwidth of the noise jammer so that as much of the jammer power as possible is in the radar receiver bandwidth. Barrage jamming is using a wide noise bandwidth to cover several radars with one jammer or to compensate for any uncertainty in the radar frequency. In both cases some of the noise power is "wasted" because it is not in the radar receiver filter.


85% OF JAMMING IN RECEIVER
SPOT JAMMING
Reducing jamming in the receiver from 100% to 85% reduces J/S by 0.7 dB.
J/S ⬇ 0.7 dB
RADAR 3dB BANDWIDTH
JAMMER 3dB BANDWIDTH
JAMMER POWER DENSITY SPECTRUM
RADAR SIGNAL
AMPLITUDE
FREQUENCY
ω
14% OF JAMMING IN RECEIVER
BARRAGE JAMMING
Reducing jamming in the receiver from 100% to 14% reduces J/S by 8.6 dB.
J/S ⬇ 8.6 dB
JAMMER 3dB BANDWIDTH
JAMMER POWER DENSITY SPECTRUM
RADAR 3dB BANDWIDTHS
RADARS
ω

Figure 2. Noise Jamming.

In the past, noise jammers were often described as having so many "watts per MHz." This is nothing more than the power of the noise jammer divided by the noise bandwidth. That is, a 500 watt noise jammer transmitting a noise bandwidth of 200 MHz has 2.5 watts/MHz. Older noise jammers often had noise bandwidths that were difficult, or impossible, to adjust accurately. These noise jammers usually used manual tuning to set the center frequency of the noise to the radar frequency. Modern noise jammers can set on the radar frequency quite accurately and the noise bandwidth is selectable, so the noise bandwidth is more a matter of choice than it used to be, and it is possible that all of the noise is placed in the victim radar's receiver.

If, in the example above, the 500 watt noise jammer were used against a radar that had a 3 MHz receiver bandwidth, the noise jammer power applicable to that radar would be:

$$3\ MHz\ x\ 2.5\ watts/MHz = 7.5\ watts\ \_\ 38.75\ dBm \qquad \textbf{[1]}$$

The calculation must be done as shown in equation [1] - multiply the watts/MHz by the radar bandwidth first and then convert to dBm. You can't convert to dBm/MHz and then multiply. (See derivation of dB in Section 2-4)

An alternate method for dB calculations is to use the bandwidth reduction factor (BF).

The BF is: $$BF_{dB} = 10\ \text{Log}\left[\frac{BW_J}{BW_R}\right] \qquad \textbf{[2]}$$

where: BW_J is the bandwidth of the noise jammer, and BW_R is the bandwidth of the radar receiver.

The power of the jammer in the jamming equation (P_J) can be obtained by either method. If equation [1] is used then P_J is simply 38.75 dBm. If equation [2] is used then the jamming equation is written using (P_J - BF). All the following discussion uses the second method. Whichever method is used, it is required that $BW_J \geq BW_R$. If $BW_J < BW_R$, then all the available power is in the radar receiver and equation [1] does not apply and the BF = 0.

Note: To avoid having to include additional terms for the following calculations, always combine any transmission line loss with antenna gain.

MAIN LOBE STAND-OFF / STAND-IN JAMMING

The equivalent circuit shown in Figure 3 applies to main lobe jamming by a stand-off support aircraft or a stand-in RPV. Since the jammer is not on the target aircraft, only two of the three ranges and two of the three space loss factors (α's) are the same. Figure 3 differs from the J/S monostatic equivalent circuit shown in Figure 4 in Section 4-7 in that the space loss from the jammer to the radar receiver is different.


MAINLOBE STAND-OFF / STAND-IN EQUIVALENT CIRCUIT
For SOJ/SIJ
$R_{Rx} = R_{Tx} \neq R_{Jx}$
$\alpha_1 = \alpha_{Rx} = \alpha_{Tx} \neq \alpha_{Jx}$ and α_2
P_t
G_t
TRANSMITTER
RADAR ANTENNA GAIN
$\alpha_{1 or Tx}$, ONE-WAY SPACE LOSS
R_{Tx}
G_σ
GAIN OF RCS TARGET
SEPARATE LOCATIONS
COLLOCATED
$\alpha_{1 or Rx}$, ONE-WAY SPACE LOSS
R_{Rx}
RECEIVER
P_r
G_r
(TOTAL SIGNAL = J + S)
$\alpha_{2 or Jx}$, ONE-WAY SPACE LOSS
R_{Jx}
G_{JA}
P_t
JAMMER ANTENNA GAIN (G_{JA})
SOJ/SIJ
JAMMER POWER (P_J)
SIGNAL = POWER + GAINS - LOSSES (in dB)

Figure 3. Main Lobe Stand-Off / Stand-In EA Equivalent Circuit.

The equations are the same for both SOJ and SIJ. From the one way range equation in Section 4-3, and with inclusion of BF losses:

$$P_r\,1\ or\ J = \frac{P_j\,G_{ja}\,G_r\,\lambda^2\,BW_R}{(4\pi\,R_{Jx})^2\,BW_J} \qquad [3]$$

From the two way range equation in Section 4.4: $P_r\,2\ or\ S = \frac{P_t\,G_t\,G_r\,\lambda^2\,\sigma}{(4\pi)^3\,R_{Tx}^4}$ **[4]**

so

$$\frac{J}{S} = \frac{P_j\,G_{ja}\,G_r\,\lambda^2\,(4\pi)^3\,R_{Tx}^4\,BW_R}{P_t\,G_t\,G_r\,\lambda^2\,\sigma\,(4\pi\,R_{Jx})^2\,BW_J} = \frac{P_j\,G_{ja}\,4\pi\,R_{Tx}^4\,BW_R}{P_t\,G_t\,\sigma\,R_{Jx}^2\,BW_J} \qquad \textit{(ratio form)} \qquad [5]$$

Note: Keep R and σ in the same units. Converting to dB and using 10 log 4π = 10.99 dB:

$10\log J/S = 10\log P_j - 10\log [BW_j/BW_R] + 10\log G_{ja} - 10\log P_t - 10\log G_t - 10\log \sigma + 10.99\text{ dB} + 40\log R_{Tx} - 20\log R_{Jx}$ **[6]**

If the simplified radar equation is used, the free space loss from the SOJ/SIJ to the radar receiver is α_{Jx}, then equation [7] is the same as monostatic equation [6] in Section 4-7 except α_{Jx} replaces α, and the bandwidth reduction factor [BF] losses are included:

$10\log J = 10\log P_j - BF + 10\log G_{ja} + 10\log G_r - \alpha_{Jx}$ (factors in dB) **[7]**

Since the free space loss from the radar to the target and return is the same both ways, $\alpha_{Tx} = \alpha_{Rx} = \alpha_1$, equation [8] is the same as monostatic equation [7] in Section 4-7.

$10\log S = 10\log P_t + 10\log G_t + 10\log G_r + G_\sigma - 2\alpha_1$ (factors in dB) **[8]**

and $10\log J/S = 10\log P_j - BF + 10\log G_{ja} - \alpha_{Jx} - 10\log P_t - 10\log G_t - G_\sigma + 2\alpha_1$ (factors in dB) **[9]**

Notice that unlike equation [8] in Section 4-7, there are two different α's in [9] because the signal paths are different.

SIDE LOBE STAND-OFF / STAND-IN JAMMING

The equivalent circuit shown in Figure 4. It differs from Figure 3, (main lobe SOJ/SIJ) in that the radar receiver antenna gain is different for the radar signal return and the jamming.


SIDE LOBE STAND-OFF / STAND-IN
EQUIVALENT CIRCUIT
For SOJ/SIJ
$R_{Rx} = R_{Tx} \neq R_{Jx}$
$\alpha_1 = \alpha_{Rx} = \alpha_{Tx} \neq \alpha_{Jx}$ and α_2
P_t
G_t
$\alpha_{1 \text{ or } Tx}$, ONE-WAY SPACE LOSS
R_{Tx}
G_σ
SEPARATE LOCATIONS
TRANSMITTER
RADAR ANTENNA GAIN
$\alpha_{1 \text{ or } Rx}$, ONE-WAY SPACE LOSS
R_{Rx}
GAIN OF RCS TARGET
COLLOCATED
RECEIVER
P_r
$G_{r(ML)}$
$G_{r(SL)}$
$\alpha_{2 \text{ or } Jx}$, ONE-WAY SPACE LOSS
R_{Jx}
G_{JA}
P_t
(TOTAL SIGNAL = J + S)
SIGNAL = POWER + GAINS - LOSSES (in dB)
JAMMER ANTENNA GAIN (G_{JA})
SOJ/SIJ
JAMMER POWER (P_J)

Figure 4. Side Lobe Stand-Off / Stand-In EA Equivalent Circuit.

To calculate side lobe jamming, the gain of the radar antenna's side lobes must be known or estimated. The gain of each side lobe will be different than the gain of the other side lobes. If the antenna is symmetrical, the first side lobe is the one on either side of the main lobe, the second side lobe is the next one on either side of the first side lobe, and so on. The side lobe gain is G_{SLn}, where the 'n' subscript denotes side lobe number: 1, 2, ..., n.

The signal is the same as main lobe equations [4] and [8], except $G_r = G_{r(ML)}$

$$P_r 2 \text{ or } S = \frac{P_t\, G_t\, G_{r(ML)}\, \lambda^2\, \sigma}{(4\pi)^3\, R_{Tx}^4} \quad \textit{(ratio form)} \qquad \textbf{[10]}$$

If simplified radar equations are used:

$10\log S = 10\log P_t + 10\log G_t + 10\log G_{r(ML)} + G_\sigma - 2\alpha_1$ (factors in dB)

The jamming equation is the same as main lobe equations [3] and [7] except $G_r = G_{r(SL)}$:

$$J = \frac{P_j\, G_{ja}\, G_{r(SL)}\, \lambda^2\, BW_R}{(4\pi\, R_{Jx})^2\, BW_J} \qquad \textbf{[11]}$$

$10\log J = 10\log P_j - BF + 10\log G_{ja} + 10\log G_{r(SL)} - \alpha_{Jx}$ (factors in dB) **[12]**

so

$$\frac{J}{S} = \frac{P_j\, G_{ja}\, G_{r(SL)}\, 4\pi\, R_{Tx}^4\, BW_R}{P_t\, G_t\, G_{r(ML)}\, \sigma\, R_{Jx}^2\, BW_J} \quad \textit{(ratio form)} \qquad \textbf{[13]}$$

Note: keep R and σ in same units. Converting to dB and using $10\log 4\pi = 10.99$ dB:

$10\log J/S = 10\log P_j - BF + 10\log G_{ja} + 10\log G_{r(SL)} - 10\log P_t - 10\log G_t - 10\log G_{r(ML)} - 10\log\sigma + 10.99\text{ dB} + 40\log R_{Tx} - 20\log R_{Jx}$
(factors in dB) **[14]**

If simplified radar equations are used:

$10\log J/S = 10\log P_j - BF + 10\log G_{ja} + 10\log G_{r(SL)} - \alpha_{Jx} - 10\log P_t - 10\log G_t - 10\log G_{r(ML)} - G_\sigma + 2\alpha_1$ **[15]**
(in dB)

This page intentionally left blank.

JAMMING TO SIGNAL (J/S) RATIO - CONSTANT GAIN [LINEAR] JAMMING

JAMMING TO SIGNAL (J/S) RATIO (MONOSTATIC)

$$\frac{J}{S} = \frac{G_{ja(Rx)}\, G_j\, G_{ja(Tx)}\, \lambda^2}{4\pi\sigma} = \frac{G_{ja(Rx)}\, G_j\, G_{ja(Tx)}\, c^2}{4\pi\sigma\, f^2} \quad \text{(ratio form)}$$

$G_{ja(Rx)}$ = The Gain of the jammer receive antenna
G_j = The gain of the jammer
$G_{ja(Tx)}$ = The Gain of the jammer transmit antenna

or:

$10\log J/S = 10\log G_{ja(Rx)} + 10\log G_j + 10\log G_{ja(Tx)} - 10\log (4\pi\sigma/\lambda^2)$

or if simplified radar equations developed in previous sections are used:

$10\log J/S = 10\log G_{ja(Rx)} + 10\log G_j + 10\log G_{ja(Tx)} - G_\sigma$ (dB)

* Keep λ and σ in same units. Note: $\lambda = c/f$

Target gain factor,
$G_\sigma = 10\log \sigma + 20\log f_1 + K_2$ (dB)

K_2 Values (dB):

RCS (σ) (units)	f_1 in MHz K_2 =	f_1 in GHz K_2 =
m^2	-38.54	21.46
ft^2	-48.86	11.14

JAMMING TO SIGNAL (J/S) RATIO (BISTATIC)

Same as the monostatic case except G_σ will be different since RCS (σ) varies with aspect angle.

Since the jammer on the target is amplifying the received radar signal before transmitting it back to the radar, both J and S experience the two way range loss. Figure 1 shows that the range for both the signal and constant gain jamming have a slope that is 40 dB per decade. Once the jammer output reaches maximum power, that power is constant and the jamming slope changes to 20 dB per decade since it is only a function of one way space loss and the J/S equations for constant power (saturated) jamming must be used.



Figure 1. Sample Constant Gain / Constant Power Graph.

Normally the constant gain (linear) region of a repeater jammer occurs only at large distances from the radar and the constant power (saturated) region is reached rapidly as the target approaches the radar. When a constant gain jammer is involved it may be necessary to plot jamming twice - once using J from the constant power (saturated) equation [1] in Section 4-7 and once using the constant gain (linear) equation [4], as in the example shown in Figure 1.

CONSTANT GAIN SELF PROTECTION EA

Most jammers have a constant power output - that is, they always transmit the maximum available power of the transmitter (excepting desired EA modulation). Some jammers also have a constant gain (linear) region. Usually these are coherent repeaters that can amplify a low level radar signal to a power that is below the level that results in maximum available (saturated) power output. At some radar to target range, the input signal is sufficiently high that the full jammer gain would exceed the maximum available power and the jammer ceases to be constant gain and becomes constant power.

To calculate the power output of a constant gain jammer where:

S_{Rj} = The Radar signal at the jammer input (receive antenna terminals)
$G_{ja(Rx)}$ = The Gain of the jammer receive antenna
G_j = The gain of the jammer
α_{Tx} = The one-way free space loss from the radar to the target
P_{jCG} = The jammer constant gain power output
P_j = The maximum jammer power output
L_R = The jammer receiving line loss; combine with antenna gain $G_{ja(Rx)}$

From equation [10], Section 4-3, calculate the radar power received by the jammer.

$$10\log S_{Rj} = 10\log P_t + 10\log G_t - \alpha_{Tx} + 10\log G_{ja(Rx)} \qquad \text{(factors in dB)} \qquad \textbf{[1]}$$

The jammer constant gain power output is:

$$10\log P_{jCG} = 10\log S_{Rj} + 10\log G_{ja} \qquad \textbf{[2]}$$

and, by definition:

$$P_{jCG} \le P_j \qquad \textbf{[3]}$$

MONOSTATIC

The equivalent circuit shown in Figure 2 is different from the constant power equivalent circuit in Figure 4 in Section 4-7. With constant gain, the jamming signal experiences the gain of the jammer and its antennas plus the same space loss as the radar signal.


JAMMER CONSTANT GAIN (LINEAR)
EQUIVALENT CIRCUIT (MONOSTATIC)
JAMMER RECEIVER ANTENNA GAIN
$G_{ja(Rx)}$
$\alpha_{1 \text{ or } Tx}$, ONE-WAY SPACE LOSS
P_t
G_t
R_{Tx}
G_σ
S_{Rj}
G_j
TRANSMITTER
RADAR ANTENNA GAIN
$\alpha_{1 \text{ or } Rx}$, ONE-WAY SPACE LOSS
R_{Rx}
GAIN OF RCS
TARGET
JAMMER AMPLIFIER
COLLOCATED
RECEIVER
P_r
G_r
$\alpha_{1 \text{ or } Jx}$, ONE-WAY SPACE LOSS
R_{Jx}
G_{JA}
(TOTAL SIGNAL = J + S)
JAMMER TRANSMITTER ANTENNA GAIN ($G_{JA(Tx)}$)
SIGNAL POWER + GAINS - LOSSES (in dB)
For Monostatic: $R_{Rx} = R_{Tx}$ $\alpha_{Rx} = \alpha_{Jx} = \alpha_{Tx} = \alpha 1$

Figure 2. Jammer Constant Gain EA Equivalent Circuit (Monostatic).

To calculate J, the one way range equation from Section 4-3 is used twice:

$$J = \frac{P_t\, G_t\, G_{ja(Rx)}\, \lambda^2}{(4\pi R\,)^2}\; \frac{G_j\, G_{ja(Tx)}\, G_r\, \lambda^2}{(4\pi R\,)^2} \qquad \textbf{[4]}$$

From the two way range equation in Section 4-4: $S = \frac{P_t\, G_t\, G_r\, \lambda^2\, \sigma}{(4\pi\,)^3\, R^4}$ **[5]**

Terms cancel when combined: $\frac{J}{S} = \frac{G_{ja(Rx)}\, G_j\, G_{ja(Tx)}\, \lambda^2}{4\pi\sigma}$ *Keep λ and σ in same units* **[6]**

Or in dB form: $10\log J/S = 10\log G_{ja(Rx)} + 10\log G_j + 10\log G_{ja(Tx)} - 10\log (4\pi\sigma/\lambda^2)$ **[7]**

Since the last term can be recognized as minus G_σ from equation [10] in Section 4-4, where the target gain factor, $G_\sigma = 10\log (4\pi\sigma/\lambda^2) = 10\log (4\pi\sigma f^2/c^2)$, it follows that:

$10\log J/S = 10\log G_{ja(Rx)} + 10\log G_j + 10\log G_{ja(Tx)} - G_\sigma$ (factors in dB) **[8]**

Target gain factor, $G_\sigma = 10\log \sigma + 20\log f_1 + K_2$ (in dB)

K_2 Values

(dB)

RCS (σ) (units)	f_1 in MHz K_2 =	f_1 in GHz K_2 =
m^2	-38.54	21.46
ft^2	-48.86	11.14

BISTATIC

The bistatic equivalent circuit shown in Figure 3 is different from the monostatic equivalent circuit shown in Figure 2 in that the receiver is separately located from the transmitter, $R_{Tx} \neq R_{Rx}$ or R_{Jx} and G_σ will be different since the RCS (σ) varies with aspect angle.


JAMMER CONSTANT GAIN (LINEAR)
EQUIVALENT CIRCUIT (BISTATIC)
JAMMER RECEIVER ANTENNA GAIN
$G_{ja(Rx)}$
α_{Tx} , ONE-WAY SPACE LOSS
P_t
G_t
R_{Tx}
G'_σ
S_{Rj}
G_J
TRANSMITTER
RADAR ANTENNA GAIN
α_{Rx} , ONE-WAY SPACE LOSS
GAIN OF RCS
TARGET
SEPARATE LOCATIONS
R_{Rx}
JAMMER AMPLIFIER
RECEIVER
P_r
G_r
α_{Jx} , ONE-WAY SPACE LOSS
R_{Jx}
G_{JA}
(TOTAL SIGNAL = J + S)
JAMMER TRANSMITTER ANTENNA GAIN ($G_{ja(Tx)}$)
SIGNAL POWER + GAINS - LOSSES (in dB)
For Bistatic: $R_{Rx} = R_{Jx} \neq R_{Tx}$ $\alpha_{Rx} = \alpha_{Jx} \neq \alpha_{Tx}$

Figure 3. Jammer Constant Gain EA Equivalent Circuit (Bistatic).

To calculate J, the one way range equation from Section 4-3 is used twice:

$$J = \frac{P_t\, G_t\, G_{ja(Rx)}\, \lambda^2}{(4\pi\, R_{Tx})^2} \frac{G_j\, G_{ja(Tx)}\, G_r\, \lambda^2}{(4\pi\, R_{Rx})^2} \qquad (R_{Jx} = R_{Rx}) \qquad \textbf{[9]}$$

From the two way range equation in Section 4-4: $S = \dfrac{P_t\, G_t\, G_r\, \lambda^2\, \sigma'}{(4\pi)^3\, R_{Tx}^2\, R_{Rx}^2}$ (σ′ is bistatic RCS) **[10]**

Terms cancel when combined: $\dfrac{J}{S} = \dfrac{G_{ja(Rx)}\, G_j\, G_{ja(Tx)}\, \lambda^2}{4\pi\sigma'}$ *Keep λ and σ in same units* **[11]**

Or in dB form: $10\log J/S = 10\log G_{ja(Rx)} + 10\log G_j + 10\log G_{ja(Tx)} - 10\log (4\pi\sigma'/\lambda^2)$ **[12]**

Since the last term can be recognized as minus G_σ from equation [10] in Section 4-4, where the target gain factor, $G_\sigma = 10\log (4\pi\sigma'/\lambda^2) = 10\log (4\pi\sigma' f^2/c^2)$, it follows that:

$10\log = 10\log G_{ja(Rx)} + 10\log G_j + 10\log G_{ja(Tx)} - G_\sigma'$ (factors in dB) **[13]**

Target gain factor, $G_\sigma = 10\log \sigma + 20\log f_1 + K_2$ (in dB)			
K_2 Values (dB)	RCS (σ) (units)	f_1 in MHz K_2 =	f_1 in GHz K_2 =
	m^2	-38.54	21.46
	ft^2	-48.86	11.14

Linear J/S (Monostatic) Example (Linear Power Jamming)

Assume that a 5 GHz radar has a 70 dBm signal fed through a 5 dB loss transmission line to an antenna that has 45 dB gain. An aircraft that is flying 31 km from the radar has an aft EW antenna with -1 dB gain and a 5 dB line loss to the EW receiver (there is an additional loss due to any antenna polarization mismatch but that loss will not be addressed in this problem). The received signal is fed to a jammer with a gain of 60 dB, feeding a 10 dB loss transmission line which is connected to an antenna with 5 dB gain.

If the RCS of the aircraft is 9 m^2, what is the J/S level received at the input to the receiver of the tracking radar?

Answer:

$10\log J/S = 10\log G_{ja(Rx)} + 10\log G_j + 10\log G_{ja(Tx)} - G_\sigma$

$G_\sigma = 10\log \sigma + 20\log f_1 + K_2 = 10\log 9 + 20\log 5 + 21.46 = 44.98$ dB

Note: The respective transmission line losses will be combined with antenna gains, i.e. -1 -5 = -6 dB and -10 + 5 = -5 dB

$10\log J/S = -6 + 60 - 5 - 44.98 = 4.02$ dB @ 5 GHz

The answer changes to 1.1 dB if the tracking radar operates at 7 GHz provided the antenna gains and aircraft RCS are the same at both 5 and 7 GHz.

$G_\sigma = 10\log 9 + 20\log 7 + 21.46 = 47.9$ dB

$10\log J/S = -6 + 60 - 5 - 47.9 = 1.1$ dB @ 7 GHz

Separate J (-73.5 dBm @ 5 GHz and -79.34 dBm @ 7 GHz) and S (-77.52 dBm @ 5 GHz and -80.44 dBm @ 7 GHz) calculations for this problem are provided in Sections 4-3 and 4-4, respectively. A saturated gain version of this problem is provided in Section 4-7.

This page intentionally left blank.

RADAR CROSS SECTION (RCS)

Radar cross section is the measure of a target's ability to reflect radar signals in the direction of the radar receiver, i.e. it is a measure of the ratio of backscatter power per steradian (unit solid angle) in the direction of the radar (from the target) to the power density that is intercepted by the target.



Figure 1. Concept of Radar Cross Section.

The RCS of a target can be viewed as a comparison of the strength of the reflected signal from a target to the reflected signal from a perfectly smooth sphere of cross sectional area of 1 m^2 as shown in Figure 1.

The conceptual definition of RCS includes the fact that not all of the radiated energy falls on the target. A target's RCS (σ) is most easily visualized as the product of three factors:

σ = **Projected cross section** x Reflectivity x Directivity.

RCS(σ) is used in Section 4-4 for an equation representing power reradiated from the target.

Reflectivity: The percent of intercepted power reradiated (scattered) by the target.

Directivity: The ratio of the power scattered back in the radar's direction to the power that would have been backscattered had the scattering been uniform in all directions (i.e. isotropically).



* See creeping wave discussion for exception when $\lambda <<$ Range and $\lambda << r$

Figure 2. RCS vs. Physical Geometry.

Figures 2 and 3 show that RCS does not equal geometric area. For a sphere, the RCS, $\sigma = \pi r^2$, where r is the radius of the sphere.

The RCS of a sphere is independent of frequency if operating at sufficiently high frequencies where $\lambda <<$Range, and $\lambda <<$ radius (r). Experimentally, radar return reflected from a target is compared to the radar return reflected from a sphere which has a frontal or projected area of one square meter (i.e. diameter of about 44 in). Using the spherical shape aids in field or laboratory measurements since orientation or positioning of the sphere will not affect radar reflection intensity measurements as a flat plate would. If calibrated, other sources (cylinder, flat plate, or corner reflector, etc.) could be used for comparative measurements.

To reduce drag during tests, towed spheres of 6", 14", or 22" diameter may be used instead of the larger 44" sphere, and the reference size is 0.018, 0.099, or 0.245 m^2 respectively instead of 1 m^2. When smaller sized spheres are used for tests you may be operating at or near where λ~radius. If the results are then scaled to a 1 m^2 reference, there may be some perturbations due to creeping waves. See the discussion at the end of this section for further details.


SPHERE
$\sigma \max = \pi r^2$
CYLINDER
$\sigma \max = \frac{2\pi r h^2}{\lambda}$
FLAT PLATE
$\sigma \max = \frac{4\pi w^2 h^2}{\lambda^2}$
TILTED PLATE
Same as above for what reflects away from the plate and could be zero reflected to radar
CORNER
$\sigma \max = \frac{8\pi w^2 h^2}{\lambda^2}$
Dihedral Corner Reflector
$\sigma \max = \frac{4\pi L^4}{3\lambda^2}$
L
$\sigma \max = \frac{12\pi L^4}{\lambda^2}$
L
$\sigma \max = \frac{15.6\pi L^4}{3\lambda^2}$
L
Trihedral Corner Reflectors

Figure 3. Backscatter From Shapes.


RELATIVE MAGNITUDE (dBsm)
360° Pattern
± 90° Pattern
± 60° Pattern
SPHERE
FLAT PLATE
CORNER

Figure 4. RCS Patterns.

In Figure 4, RCS patterns are shown as objects are rotated about their vertical axes (the arrows indicate the direction of the radar reflections).

The sphere is essentially the same in all directions.

The flat plate has almost no RCS except when aligned directly toward the radar.

The corner reflector has an RCS almost as high as the flat plate but over a wider angle, i.e., over ±60°. The return from a corner reflector is analogous to that of a flat plate always being perpendicular to your collocated transmitter and receiver.

Targets such as ships and aircraft often have many effective corners. Corners are sometimes used as calibration targets or as decoys, i.e. corner reflectors.

An aircraft target is very complex. It has a great many reflecting elements and shapes. The RCS of real aircraft must be measured. It varies significantly depending upon the direction of the illuminating radar.

Figure 5 shows a typical RCS plot of a jet aircraft. The plot is an azimuth cut made at zero degrees elevation (on the aircraft horizon). Within the normal radar range of 3-18 GHz, the radar return of an aircraft in a given direction will vary by a few dB as frequency and polarization vary (the RCS may change by a factor of 2-5). It does not vary as much as the flat plate.



Figure 5. Typical Aircraft RCS.

As shown in Figure 5, the RCS is highest at the aircraft beam due to the large physical area observed by the radar and perpendicular aspect (increasing reflectivity). The next highest RCS area is the nose/tail area, largely because of reflections off the engines or propellers. Most self-protection jammers cover a field of view of +/- 60 degrees about the aircraft nose and tail, thus the high RCS on the beam does not have coverage. Beam coverage is frequently not provided due to inadequate power available to cover all aircraft quadrants, and the side of an aircraft is theoretically exposed to a threat 30% of the time over the average of all scenarios.

Typical radar cross sections are as follows: Missile 0.5 sq m; Tactical Jet 5 to 100 sq m; Bomber 10 to 1000 sq m; and ships 3,000 to 1,000,000 sq m. RCS can also be expressed in decibels referenced to a square meter (dBsm) which equals 10 log (RCS in m^2).

Again, Figure 5 shows that these values can vary dramatically. The strongest return depicted in the example is 100 m^2 in the beam, and the weakest is slightly more than 1 m^2 in the 135°/225° positions. These RCS values can be very misleading because other factors may affect the results. For example, phase differences, polarization, surface imperfections, and material type all greatly affect the results. In the above typical bomber example, the measured RCS may be much greater than 1000 square meters in certain circumstances (90°, 270°).

SIGNIFICANCE OF THE REDUCTION OF RCS

If each of the range or power equations that have an RCS (σ) term is evaluated for the significance of decreasing RCS, Figure 6 results. Therefore, an RCS reduction can increase aircraft survivability. The equations used in Figure 6 are as follows:

Range (radar detection):
From the 2-way range equation in Section 4-4:

$$P_r = \frac{P_t G_t G_r \lambda^2 \sigma}{(4\pi)^3 R^4} \quad \text{Therefore, } R^4 \propto \sigma \text{ or } \sigma^{1/4} \propto R$$

Range (radar burn-through):
The crossover equation in Section 4-8 has:

$$R_{BT}^2 = \frac{P_t G_t \sigma}{P_j G_j 4\pi} \quad \text{Therefore, } R_{BT}^2 \propto \sigma \text{ or } \sigma^{1/2} \propto R_{BT}$$

Power (jammer): Equating the received signal return (P_r) in the two way range equation to the received jammer signal (P_r) in the one way range equation, the following relationship results:

$$P_r = \underset{\underset{S}{\uparrow}}{\frac{P_t G_t G_r \lambda^2 \sigma}{(4\pi)^3 R^4}} = \underset{\underset{J}{\uparrow}}{\frac{P_j G_j G_r \lambda^2}{(4\pi R)^2}}$$

Therefore, $P_j \propto \sigma$ or $\sigma \propto P_j$

Note: jammer transmission line loss is combined with the jammer antenna gain to obtain G_t.



Figure 6. Reduction of RCS Affects Radar Detection, Burn-through, and Jammer Power.

Example of Effects of RCS Reduction - As shown in Figure 6, if the RCS of an aircraft is reduced to 0.75 (75%) of its original value, then (1) the jammer power required to achieve the same effectiveness would be 0.75 (75%) of the original value (or -1.25 dB). Likewise, (2) If Jammer power is held constant, then burn-through range is 0.87 (87%) of its original value (-1.25 dB), and (3) the detection range of the radar for the smaller RCS target (jamming not considered) is 0.93 (93%) of its original value (-1.25 dB).

OPTICAL / MIE / RAYLEIGH REGIONS

Figure 7 shows the different regions applicable for computing the RCS of a sphere. The optical region ("far field" counterpart) rules apply when $2\pi r/\lambda > 10$. In this region, the RCS of a sphere is independent of frequency. Here, the RCS of a sphere, $\sigma = \pi r^2$. The RCS equation breaks down primarily due to creeping waves in the area where λ~2πr. This area is known as the Mie or resonance region. If we were using a 6" diameter sphere, this frequency would be 0.6 GHz. (Any frequency ten times higher, or above 6 GHz, would give expected results). The largest positive perturbation (point A) occurs at exactly 0.6 GHz where the RCS would be 4 times higher than the RCS computed using the optical region formula. Just slightly above 0.6 GHz a minimum occurs (point B) and the actual RCS would be 0.26 times the value calculated by using the optical region formula. If we used a one meter diameter sphere, the perturbations would occur at 95 MHz, so any frequency above 950 MHz (~1 GHz) would give predicted results.

CREEPING WAVES

The initial RCS assumptions presume that we are operating in the optical region (λ<<Range and λ<<radius). There is a region where specular reflected (mirrored) waves combine with back scattered creeping waves both constructively and destructively as shown in Figure 8. Creeping waves are tangential to a smooth surface and follow the "shadow" region of the body. They occur when the circumference of the sphere ~ λ and typically add about 1 m^2 to the RCS at certain frequencies.

RAYLEIGH REGION
$\sigma = [\pi r^2][7.11(kr)^4]$

where: $k = 2\pi/\lambda$

MIE (resonance)
$\sigma = 4\pi r^2$ at Maximum (point A)
$\sigma = 0.26\pi r^2$ at Minimum (pt B)

OPTICAL REGION
$\sigma = \pi r^2$
(Region RCS of a sphere is independent of frequency)



* "RF far field" equivalent
Courtesy of Dr. Allen E. Fuhs, Ph.D.

Figure 7. Radar Cross Section of a Sphere.


ADDITION OF SPECULAR AND CREEPING WAVES
SPECULAR
CREEPING
E
Constructive interference gives maximum
SPECULAR
CREEPING
Destructive interference gives minimum
Specularly
Reflected Wave
Backscattered Creeping Wave
Courtesy of Dr. Allen E. Fuhs, Ph.D.

Figure 8. Addition of Specular and Creeping Waves.

EMISSION CONTROL (EMCON)

When EMCON is imposed, RF emissions must not exceed -110 dBm/meter^2 at one nautical mile. It is best if systems meet EMCON when in either the Standby or Receive mode versus just the Standby mode (or OFF). If one assumes antenna gain equals line loss, then emissions measured at the port of a system must not exceed -34 dBm (i.e. the stated requirement at one nautical mile is converted to a measurement at the antenna of a point source - see Figure 1). If antenna gain is greater than line loss (i.e. gain 6 dB, line loss 3 dB), then the -34 dBm value would be lowered by the difference and would be -37 dBm for the example. The opposite would be true if antenna gain is less.


Seam or
Connector
Leakage
MIL-STD-461B/C RE-02 or
MIL-STD-461D RE-102
70 dBµV/m for externally mounted systems
1 Meter
RF System
Maximum
EMCON
Emissions
1 Nautical mile
-34 dBm (at RF port)
(For Line Loss = Antenna Gain)
$\frac{P_t G_t}{4\pi R^2}$ = -110 dBm/m^2

Figure 1. EMCON Field Intensity / Power Density Measurements.

To compute the strength of emissions at the antenna port in Figure 1, we use the power density equation (see Section 4-2)

$$P_D = \frac{P_t G_t}{4\pi R^2} \quad \textbf{[1]} \qquad \text{or rearranging} \qquad P_tG_t = P_D\,(4\pi R^2) \quad \textbf{[2]}$$

Given that $P_D = -110\ \text{dBm/m}^2 = (10)^{-11}\ \text{mW/m}^2$, and R = 1 NM = 1852 meters.

$$P_tG_t = P_D\,(4\pi R^2) = (10^{-11}\text{mW/m}^2)(4\pi)(1852\text{m})^2 = 4.31(10)^{-4}\ \text{mW} = -33.65 \approx -34\ \text{dBm}$$

at the RF system antenna as given.

or, the equation can be rewritten in Log form and each term multiplied by 10:

$$10\log P_t + 10\log G_t = 10\log P_D + 10\log\,(4\pi R^2) \quad \textbf{[3]}$$

Since the m^2 terms on the right side of equation [3] cancel, then:

$$10\log P_t + 10\log G_t = -110\ \text{dBm} + 76.35\ \text{dB} = -33.65\ \text{dBm} \approx -34\ \text{dBm as given in Figure 1.}$$

If MIL-STD-461B/C RE02 (or MIL-STD-461D RE-102) measurements (see Figure 2) are made on seam/connector leakage of a system, emissions below 70 dBµV/meter which are measured at one meter will meet the EMCON requirement. Note that the airframe provides attenuation so portions of systems mounted inside an aircraft that measure 90 dBµV/meter will still meet EMCON if the airframe provides 20 dB of shielding (note that the requirement at one nm is converted to what would be measured at one meter from a point source).

The narrowband emission limit shown in Figure 2 for RE02/RE102 primarily reflect special concern for local oscillator leakage during EMCON as opposed to switching transients which would apply more to the broadband limit.



Figure 3. MIL-STD-461 Narrowband Radiated Emissions Limits.

Note that in MIL-STD-461D, the narrowband radiated emissions limits were retitled RE-102 from the previous RE-02 and the upper frequency limit was raised from 10 GHz to 18 GHz. The majority of this section will continue to reference RE02 since most systems in use today were built to MIL-STD-461B/C.

For the other calculation involving leakage (to obtain 70 dBµV/m) we again start with: $P_D = \frac{P_t G_t}{4\pi R^2}$

and use the previous fact that: 10log (P_tG_t) = -33.6 dBm = 4.37x10^{-4} mW (see Section 2-4).

The measurement is at one meter so $R^2 = 1\ m^2$

we have: $\frac{4.37x\,10^{-4}}{4\pi}\ mW/\,m^2 = .348x\,10^{-4}\ mW/\,m^2 = -\,44.6\ dBm/\,m^2 = P_D$ @ 1 meter

Using the field intensity and power density relations (see Section 4-1)

$$E = \sqrt{P_D Z} = \sqrt{3.48x\,10^{-8} \bullet 377\Omega} = 36.2x\,10^{-4}\ V/m$$

Changing to microvolts (1V = 10^6 µV) and converting to logs we have:

20 log (E) = 20 log (10^6 x 36.2x10^{-4}) = 20 log (.362x10^4) = 71.18 dBµV/m ≈ 70 dBµV/m as given in Figure 1.

Some Words of Caution

A common error is to only use the one-way free space loss coefficient α_1 directly from Figure 6, Section 4-3 to calculate what the output power would be to achieve the EMCON limits at 1 NM. This is incorrect since the last term on the right of equation [3] (10 Log($4\pi R^2$)) is simply the Log of the surface area of a sphere - **it is NOT** the one-way free space loss factor α_1. You cannot interchange power (watts or dBW) with power density (watts/m^2 or dBW/m^2).

The equation uses power density (P_D), **NOT** received power (P_r). It is independent of RF and therefore varies only with range. If the source is a transmitter and/or antenna, then the power-gain product (or EIRP) is easily measured and it's readily apparent if 10log (P_t G_t) is less than -34 dBm. If the output of the measurement system is connected to a power meter in place of the system transmission line and antenna, the -34 dBm value must be adjusted. The measurement on the power meter (dBm) minus line loss (dB) plus antenna gain (dB) must not be higher than -34 dBm.

However, many sources of radiation are through leakage, or are otherwise inaccessible to direct measurement and P_D must be measured with an antenna and a receiver. The measurements must be made at some RF(s), and received signal strength is a function of the antenna used therefore measurements must be scaled with an appropriate correction factor to obtain correct power density.

RE-02 Measurements

When RE-02 measurements are made, several different antennas are chosen dependent upon the frequency range under consideration. The voltage measured at the output terminals of an antenna is not the actual field intensity due to actual antenna gain, aperture characteristics, and loading effects. To account for this difference, the antenna factor is defined as:

$$AF = E/V \qquad \textbf{[4]}$$

where E = Unknown electric field to be determined in V/m (or µV/m)
V = Voltage measured at the output terminals of the measuring antenna

For an antenna loaded by a 50 Ω line (receiver), the theoretical antenna factor is developed as follows:

$$P_D A_e = P_r = V^2/R = V_r^2/50 \text{ or } V_r = \sqrt{50 P_D A_e}$$

From Section 4-3 we see that $A_e = G_r\lambda^2/4\pi$, and from Section 4-1, $E^2 = 377 P_D$ therefore we have:

$$AF = \frac{E}{V} = \frac{\sqrt{377\, P_D}}{\sqrt{50\, P_D (\lambda^2 G_r / 4\pi)}} = \frac{9.73}{\lambda \sqrt{G_r}} \qquad \textbf{[5]}$$

Reducing this to decibel form we have:

$$20 \log AF = 20 \log E - 20 \log V = 20 \log \left[\frac{9.73}{\lambda\sqrt{GSUBr}} \right] \quad \textit{with } \lambda \textit{ in meters and Gain numeric ratio (not dB)} \qquad \textbf{[6]}$$

This equation is plotted in Figure 3.

Since all of the equations in this section were developed using far field antenna theory, use only the indicated region.



Figure 3. Antenna Factor vs. Frequency for Indicated Antenna Gain.

In practice the electric field is measured by attaching a field intensity meter or spectrum analyzer with a narrow bandpass preselector filter to the measuring antenna, recording the actual reading in volts and applying the antenna factor.

$$20\log E = 20\log V + 20\log AF \qquad \textbf{[7]}$$

Each of the antennas used for EMI measurements normally has a calibration sheet for both gain and antenna factor over the frequency range that the antenna is expected to be used. Typical values are presented in Table 1.

Table 1. Typical Antenna Factor Values.

Frequency Range	Antenna(s) Used	Antenna Factor	Gain(dB)
14 kHz - 30 MHz	41” rod	22-58 dB	0 - 2
20 MHz - 200 MHz	Dipole or Biconical	0-18 dB	0 - 11
200 MHz - 1 GHz	Conical Log Spiral	17-26 dB	0 - 15
1 GHz - 10 GHz	Conical Log Spiral or Ridged Horn	21-48 dB	0 - 28
1 GHz - 18 GHz	Double Ridged Horn	21-47 dB	0 - 32
18 GHz - 40 GHz	Parabolic Dish	20-25 dB	27 - 35

The antenna factor can also be developed in terms of the receiving antenna's effective area. This can be shown as follows:

$$AF = \frac{E}{V} = \frac{\sqrt{377\,P_D}}{\sqrt{50\,P_D\,A_e}} = \frac{2.75}{\sqrt{A_e}} \qquad \textbf{[8]}$$

Or in log form:

$$20\log AF = 20\log E - 20\log V = 20\log\left[\frac{2.75}{\sqrt{A_e}}\right] \qquad \textbf{[9]}$$

While this relation holds for any antenna, many antennas (spiral, dipole, conical etc.) which do not have a true "frontal capture area" do not have a linear or logarithmic relation between area and gain and in that respect the parabolic dish is unique in that the antenna factor does not vary with frequency, only with effective capture area. Consequently a larger effective area results in a smaller antenna factor.

A calibrated antenna would be the first choice for making measurements, followed by use of a parabolic dish or "standard gain" horn. A standard gain horn is one which was designed such that it closely follows the rules of thumb regarding area/gain and has a constant antenna factor. If a calibrated antenna, parabolic dish, or "standard horn" is not available, a good procedure is to utilize a flat spiral antenna (such as the AN/ALR-67 high band antennas). These antennas typically have an average gain of 0 dB (typically -4 to +4 dB), consequently the antenna factor would not vary a lot and any error would be small.

EXAMPLE:

Suppose that we want to make a very general estimation regarding the ability of a system to meet EMCON requirements. We choose to use a spiral antenna for measurements and take one of our samples at 4 GHz. Since we know the gain of the spiral is relatively flat at 4 GHz and has a gain value of approximately one (0 dB) in that frequency range. The antenna is connected to a spectrum analyzer by 25 feet of RG9 cable. We want to take our measurements at 2 meters from the system so our setup is shown as follows:



Our RG9 cable has an input impedance of 50Ω, and a loss of 5 dB (from Figure 5, Section 6-1).

First, let's assume that we measure -85 dBm at the spectrum analyzer and we want to translate this into the equivalent strength at 1 NM. Our power received by the antenna is: P_r = -85 dBm + 5 dB line loss = -80 dBm

also $P_D = P_r/A_e$ and $A_e = G\lambda^2/4\pi = (G/4\pi)\bullet(c/f)^2 = (1/4\pi)\bullet(3x10^8/4x10^9)^2 = 4.47x10^{-4}$ m^2

in log form: $10 \text{ Log } P_D = 10 \text{ Log } P_r - 10 \text{ Log } A_e$ = -80 dBm + 33.5 = -46.5 dBm/m^2
at our 2 meter measuring point

To convert this to a value at 1 NM, we use

$P_t G_t = P_{D@1\ nm} 4\pi R_1^2 = P_{D@2\ m} 4\pi R_2^2$ and we solve for PD@1 $_{nm}$

in log form after cancelling the 4π terms:

$10 \text{ Log } P_{D@1\ nm} = 10 \text{ Log } P_{D@2\ m} + 10 \text{ Log } (R_{2m}/R_{1nm})^2$ = -46.5 dBm/m^2 - 59.3 dB = -105.8 dBm/m^2 which is more power than the maximum value of -110 dBm/m^2 specified.

If we are making repetitive measurement as we might do when screening an aircraft on the flight line with numerous systems installed, or when we want to improve (reduce) the leakage on a single system by changing antennas, lines, connectors, or EMI gaskets or shielding, this mathematical approach would be unnecessarily time consuming since it would have to be repeated after each measurement. A better approach would be to convert the -110 dBm/m^2 value at 1 NM to the maximum you can have at the measuring instrument (in this case a spectrum analyzer), then you could make multiple measurements and know immediately how your system(s) are doing. It should be noted that -90 to -100 dBm is about the minimum signal level that can be detected by a spectrum analyzer, so you couldn't take measurements much further away unless you used an antenna with a much higher gain.

In order not to exceed EMCON, the power density must not exceed -110 dBm/m^2 at 1 NM, which is 10^{-11} mW/m^2.

$$P_t G_t = P_{D@1\ nm} 4\pi R_1^2 = P_{D@2\ m} 4\pi R_2^2$$

we solve for $P_{D@2\ m} = 10^{-11}(1852m)^2/(2m)^2 = 8.57 \text{ x } 10^{-6}$ mW/m^2 = -50.7 dBm/m^2

We'll be using a spectrum analyzer, so we want to compute what the maximum power or voltage may be.

Method 1 - Using the Power Density Approach

Using logs/dB and the values of $P_{D@2\ m}$ and A_e determined previously:
$10 \text{ Log } P_r = 10 \text{ Log } P_D + 10 \text{ Log } A_e$ = -50.7 - 33.5 = -84.2 dBm

taking line loss into account we have: -84.2 - 5 dB = - 89.2 dBm as the maximum measurement reading.

If we wanted to calculate it in volts, and take into account our line impedance we would have the following:

$P_r = P_D A_e = V^2/R = V^2/50\Omega$ also $A_e = G\lambda^2/4\pi$ so solving for V we have:

$$V = \sqrt{P_D\left[\frac{G_r\lambda^2}{4\pi}\right]R} = \sqrt{P_D\left[\frac{G_r}{4\pi}\left(\frac{c}{f}\right)^2\right]R} = \sqrt{8.57x10^{-9}\left[\frac{1}{4\pi}\left(\frac{3x10^8}{4x10^9}\right)^2\right]50\Omega} = 1.38x10^{-5}\ volts\ \ (before\ line\ loss)$$

since our line loss is 5 dB, we have -5 dB = 20 Log V_2/V_1. Solving for V_2 we get $\underline{7.79x10^{-6}\text{ volts}}$ or -89 dBm as a maximum at our measurement device input. We can see immediately that our value of -85 dBm that we measured on the previous page would not meet specifications, and neither would any signal with more power than -89 dBm.

Method 2 - Using the Antenna Factor Approach

Starting with the same value of power density that we obtained above ($8.57x10^{-9}$ W/m^2), we find the field intensity from Table 1, Section 4-1 to be approximately 65 dBμv/m. Also from Figure 3 in this section, AF = 43 dB @ 4 GHz (by calculating with equation [6], the exact value is 42.3 dB).

From equation [6]:
20log V = 20log E - 20log AF
20log V = 65 - 43 = 22 dBμv/m.

Since dBμv/m = 20 log (V)(10^6) = 20 log V + 20 log 10^6 = 20 log V + 120, we see that to get an answer in dBv we must subtract 120 from the dBμv/m value so: V_{dB} = 22 - 120 = -98dBv. We then subtract our line loss (-5 dB) and we have:

V = -98 - 5 = -103 dBv = 17 dBμv = $\underline{7.1x10^{-6}\text{ volts}}$

using the fact that P = V^2/R and for the input line R = 50Ω, P = $1x10^{-12}$ W = -120 dBW = -90 dBm

Although this method is just as accurate as that obtained using method 1, the values obtained in Table 1, Section 4-1, and Figure 3 must be interpolated, and may not result in values which are as precise as the appropriate formulas would produce.

Sample Problem: What is the approximate transmit power from a receiver?

A. 1 nanowatt (nW)
B. 10 nW
C. 100 nW
D. 1 microwatt (μW)
E. 10 μW
F. 100 μW
G. 1 milliwatt (mW)
H. 10 mW
I. 100 mW
J. 1 watt (W)
K. 10 W
L. 100 W
M. 1 kilowatt (kW)
N. 10 kW
O. 100 kW

The question may seem inappropriate since a receiver is supposedly a passive device which only receives a signal. If the receiver was a crystal video receiver as shown in Section 5-3, it wouldn't transmit power unless a built-in-test (BIT) signal was injected after the antenna to periodically check the integrity of the microwave path and components. The potential exists for the BIT signal to leak across switches and couple back through the input path and be transmitted by the receiver's antennas.

If the receiver uses a local oscillator (LO) and a mixer to translate the signal to an intermediate frequency (IF) for processing (such as a superhet shown in Section 5-3), there is the potential for the CW LO signal to couple back through the signal input path and be transmitted by the receiver's antenna. Normally a mixer has 20 dB of rejection for the reverse direction. In addition, the LO may be further attenuated by receiver front end filters.

In both cases, the use of isolators described in Section 6-7 could be used to further attenuate any signals going in the reverse direction, i.e. back to the antenna. A good receiver design should ensure that any RF leakage radiated by the receiver will not exceed the EMCON level.

In answer to the initial question, "transmit" leakage power should be less than -34 dBm (0.4 μW) to meet EMCON. Therefore, the real answer may be "A," "B," or "C" if EMCON is met and could be "D" through possibly "G" if EMCON is not met.

EW JAMMING TECHNIQUES

INTRODUCTION

Electronic jamming is a form of Electronic Attack where jammers radiate interfering signals toward an enemy's radar, blocking the receiver with highly concentrated energy signals. The two main technique styles are noise techniques and repeater techniques. The three types of noise jamming are spot, sweep, and barrage. Repeater techniques can be further subdivided into categories as shown in Figure 1.


ECM Type
Jamming
(Concealment)
Deception
(Forgery)
ECM Generation Method
Active
(Transmitting)
Passive
(Reflection)

Figure 1. EA Repeater Technique Divisions.

ASYNCHRONOUS SWEPT WAVE MODULATION (ASWM)

ASWM is synonymous with A-SWM. Asynchronous indicates that the waveform is free running - also see SSWM. A swept wave modulation is essentially a swept amplitude modulation (SAM). It is a waveform that is swept between two frequencies that are usually chosen to bracket a radar's passive angle scanning rate. The modulation amplitude can be either down modulated or On-Off Keyed (OOK). The down modulated shape can be square wave, rectangular wave, linear (e.g. a sine wave), or a combination. The OOK modulated shape can be square wave or rectangular wave.

BARRAGE JAMMING


BARRAGE JAMMING
14% OF JAMMING IN RECEIVER
Reducing jamming in the receiver from 100% to 14% reduces J/S by 8.6 dB.
J/S ⬇ 8.6 dB
JAMMER 3dB BANDWIDTH
JAMMER POWER DENSITY SPECTRUM
RADAR 3dB BANDWIDTHS
RADARS

Figure 2. Barrage Jamming.

The jamming of multiple frequencies at once by a single jammer. The advantage is that multiple frequencies can be jammed simultaneously; however, the jamming effect can be limited because this requires the jammer to spread its full power between these frequencies. So the more frequencies being jammed, the less effectively each is jammed.

CROSS POLARIZATION (X-POL)

(1) A self-screening or support EA technique that causes angle errors in tracking radars and sensing errors in jamming suppression EP systems of surveillance radars by radiating a signal that is orthogonally polarized to the principal polarization of the victim radar. (2) A technique used against monopulse and other passive lobe tracking radars. Requires a strong jam-to-signal ratio or the skin echo will show up in the pattern nulls.

HOME ON JAM (HOJ)

A means whereby a missile guidance receiver utilizes the self-screening target jamming signal to develop angular steering information so that the missile can home on that target.

IMAGE JAMMING

Jamming at the image frequency of the radar receiver. Barrage jamming is made most effective by generating energy at both the normal operating and image frequency of the radar. Image jamming inverts the phase of the response and is thereby useful as an angle deception technique. Not effective if the radar uses image rejection.

INVERSE CON SCAN (ICS)

One method of confusing a radar operator or fire control radar system is to provide erroneous target bearings. This is accomplished by first sensing the radar antenna or antenna dipole scan rate and then modulating repeater amplifier gain so that the weapons system will fire at some bearing other than the true target bearing.


Target
Target Return - Off Boresight
A
B
C
D
A
True Error
Target Return - Tight Tracking On Boresight
Zero Error
Target
ICS ECM Signal
Real Target
Target Return Plus ICS ECM Signal
C
A
B
D
A
Error
False Target

Figure 3. Inverse Con Scan.

J/S REQUIREMENT

The jamming to signal ratio for effective coverage of the true target. Usually on the order of zero dB (J/S=1).

LINEAR MODULATION

A modulation technique in which the output varies in a straight line (linear) manner with the input (modulating) waveform. This is different from a discontinuous (On-Off) modulation. Typically the modulating waveform is a ramp or triangular wave but could also be a sine wave modulating input.

LOBE ON RECEIVE ONLY (LORO)

Predicting the future location of a target (to track) requires that the radar look at areas where the target is not located. When this scanning is accomplished with the radiated beam, large angle targets such as chaff clouds can create complete radar "white-out." RWR indications can be obtained before actual target lock-on. These problems can be overcome by scanning only the receiving antennas and using a separate transmitting antenna pointed only at the target.

In a LORO system, a transmitting antenna emits a few "exploratory" pulses along a direction obtained from an acquisition radar. These exploratory pulses are the acquisition mode of the TTR. That is, in its acquisition mode the small beamed TTR must scan the large location segment provided by the acquisition radar. In radars equipped with Fast Time Constant, the return pulse is applied to a differentiator of extremely short time constant. When the pulse is received, it is "cut-off" on the leading edge and only that portion is fed to the computer. This allows the radar to effectively track on the leading edge of the target. FTC does not improve the range resolution but it can prevent any countermeasures aft of the target which are in the same resolution cell as the target (such as chaff) from interfering with the radar receiver.

The receiving antennas scan their sector for the target return due to these exploratory pulses; as the power centroid is located, the center of the receiving pattern is brought onto the target. The transmitting antenna, which is slaved to the receiving antenna, is then pointing directly at the desired target and only that target is radiated during tracking. This approach allows a very small radiated beam, but the resolution cell of the system is still that of the receiving antenna.

NOISE JAMMING

The transmission of noise-like signals in the target system's radar receiver bandpass. At low power levels, noise jamming has the characteristics of receiver noise and can be mistaken by the radar operator as a problem with the radar. The object of noise jamming is to introduce a disturbing signal into the hostile electronic equipment so that the actual signal is obscured by the interference. The victim of this disturbance might be a radar receiver, a communications network, or a data link.

See also Barrage Jamming and Spot Jamming.



Figure 4. Noise Jamming.

ON-OFF MODULATION

On-Off Modulation is any modulation which switches rapidly between two states. This definition includes pulse radar operation.

On-Off Keying (OOK) is the envelope modulation of a jamming signal with a rectangular wave. The modulation rate and duty cycle are adjusted commensurate with the victim radar's processing time constants. These can be related to AGC time constants, logic time-outs, data sampling cycles, or any other data processing response times.

An important distinction must be made between the terms On-Off Keying and Blinking. While both terms involve envelope modulations that turn a jamming signal on and off, the term OOK is used as the envelope modulation of a single jamming signal, and the term blinking is used as the tactical application of OOK involving two or more cooperative jamming platforms.

PSEUDO RANDOM NOISE (PRN)

A controlled, noise-like, pulse pattern repeated in synchronism with the victim radar pulse repetition frequency. Synonymous with quasi-noise jamming.



Figure 5. Random Dual Line.

RANDOM DUAL LINE (RDL)

RDL is a coherent repeater technique that is essentially the same as velocity noise (VN), narrow band noise (NBN), and pseudo random noise (PRN) except that no false Doppler frequencies are stepped directly over the target return. The objective is to prevent the momentary additions of the EA signal and target signal that might highlight the presence of a coherent return.

RANDOM RANGE PROGRAM (RANRAP)

A dynamic False Target Jamming technique program to create multiple realistic targets of varying size and distance from the jamming plane.

RANGE GATE PULL OFF (RGPO)

Once a tracking radar has detected a target, it will place *range gates* to either side of it. Range gates essentially blank out all signals which originate from ranges outside a narrow window, substantially increasing the signal-to-noise ratio and protecting the radar against unsynchronized jamming pulses. The radar 'concentrates' on a short range interval which encloses the target's location, and it no longer looks out for other targets. This state is known as 'lock-on'. But range gates can be 'stolen', and it is the objective of the Range Gate Pull-Off (RGPO) technique to *break lock* and escape from out of the window.



Figure 6. Range Gate Pull Off.

RGPO works as follows:

Upon detection (or assumption) that a tracking radar has locked on, the on-board jammer is switched on and starts to work in a couple of phases:

1. First, a sample of the illuminating pulse signal is taken and the radar's pulse repetition frequency (PRF) is determined. This sample is amplified and retransmitted simultaneously when further pulses are received. The aircraft actually highlights itself on the radar screen. The jamming power is steadily increased, and this continues until the replica is much stronger than the echo from the aircraft skin return. At this time, the sensitivity of the tracking radar's receiver is usually reduced in order to avoid overload. This causes the skin echo vanishes below the noise floor.

2. *Another* replica is transmitted after each of the 'dummy' skin echoes. The power of the second replica is increased while the dummy is made weaker.

3. Next, the tracker has locked on to the *delayed replica*, whereas the skin return has decreased into the noise. With respect to each of the radar's pulses, the replica is now being delayed by small, but increasing amounts of time. The range gates, of course, follow the dummy target which appears to be receding. This continues until the range gates have been moved away from the target's real position. The result is that the radar is tracking a *phantom target* and the skin return is being blanked out by the range gates.

4. Finally, the jammer is switched off and leaves the radar with just *nothing* but noise inside the window between its range gates. Break-lock was successfully achieved and the "tracking" radar needs to

switch back into a search or acquisition mode and loses time. The whole cycle will start again if the target is still within range and is reacquired.

As described above, RGPO creates only false targets which appear at greater ranges than the real target because the deceptive signal is transmitted *after* the skin echo. However, if the victim radar's PRF is constant then the time of incidence of the next radar pulse can be calculated and jamming pulses can be placed such that false targets at closer ranges are also produced.

SCINTILLATION (SCINT)

Scintillation is not an EA technique by itself, it is an implementation of an EA technique. Scintillation is simply superimposing a small, pseudo random amplitude modulation on the EA signal to make it appear more realistic to a manual operator.

SPOT JAMMING

Occurs when a jammer focuses all of its power on a single frequency. While this would severely degrade the ability to track on the jammed frequency, a frequency agile radar would hardly be affected because the jammer can only jam one frequency. While multiple jammers could possibly jam a range of frequencies, this would consume a great deal of resources to have any effect on a frequency-agile radar, and would probably still be ineffective


SPOT JAMMING
Reducing jamming in the receiver from 100% to 85% reduces J/S by 0.7 dB.
J/S ↓ 0.7 dB
85% OF JAMMING IN RECEIVER
RADAR 3dB BANDWIDTH
JAMMER 3dB BANDWIDTH
JAMMER POWER DENSITY SPECTRUM
RADAR SIGNAL
AMPLITUDE
FREQUENCY

Figure 7. Spot Jamming.

SWEPT JAMMING

This happens when a jammer's full power is shifted from one frequency to another. While this has the advantage of being able to jam multiple frequencies in quick succession, it does not affect them all at the same time, and thus limits the effectiveness of this type of jamming. Although, depending on the error checking in the receiver(s) this can render a wide range of receivers effectively useless.

SWEPT AMPLITUDE MODULATION (SAM)

The OOK frequency is linearly varied in a sawtooth fashion between preset frequency limits while the duty factor is held constant.

SWEPT WAVE MODULATION (SWM)

A swept wave modulation.2 (SWM.2) is essentially a swept amplitude modulation (SAM). It is a waveform that is swept between two frequencies that are usually chosen to bracket a radar's passive angle scanning rate. SWM can be either Synchronous Swept Wave Modulation.2-; (S-SWM) or Asynchronous Swept Wave Modulation.2-; (A-SWM.2-;). The modulation amplitude can be either down modulated or On-Off Keyed (OOK). The down modulating shape can be square wave, rectangular wave, linear (e.g. a sine wave), or a combination. The OOK modulating shape can be square wave or rectangular wave.



Figure 8. Typical Linear SWM Modulation.



Figure 9. Rectangular SWM.

SYNCHRONOUS SWEPT WAVE MODULATION (SSWM)

SSWM is synonymous with S-SWM. S-SWM and A-SWM are essentially the same except that asynchronous means that the waveform is free running and synchronous means that when a radar scan or TWS beam can be detected, the modulation waveform is synchronized to the detected beam. For programming purposes A-SWM sets sweep limits and rate by frequency (Hz), while S-SWM sets them by period (mSec).

Active Con-Scan radars will not have a detectable modulation if the target is being tightly tracked in the center of the beam. Therefore, a SWM can "jog" the tracking sufficiently to detect the modulation and allowing subsequent synchronization of the SWM waveform.

TRACK WHILE SCAN JAMMING

The technique of shifting or "walking" EA pulses off target. Many angle jamming techniques are effective.

VELOCITY FALSE TARGETS (VFT)

VFT is a pseudo-random false Doppler target concealment technique. It is designed for use against radars that acquire Doppler targets with a bank of contiguous narrow band filters. A false Doppler target is programmed to remain in a Doppler filter long enough for the radar processing to declare it a valid target return, but not long enough for the radar processing to establish tracking.

The false Doppler target is then switched to the next pseudo-randomly selected frequency and repeated. It is intended to overload the radar processing and/or the operator's ability to identify an actual target. In the illustration, the VFTs jump around in the indicated numerical order.


Transmitted Signal
Time
Radar's Angle Gates
Tracker Boresight
ECM
Either Fixed Or Walking Pulse
Combined Signals Received by Radar
Radar's Angle Gates
Tracker Boresight (Induced Error)

Figure 10. TWS Jamming.


Nine False Targets (Number 5 Active)
Target
6
9
7
2
8
3
5
1
4
Doppler Filter Bank
- f +
Bandwidth

Figure 11. Velocity False Targets.

VELOCITY GATE PULL OFF

This is a method of capturing the velocity gate of a Doppler radar and moving it away from the skin echo. Similar to the RGPO, but used against CW or Doppler velocity tracking radar systems. The CW or pulse doppler frequency, which is amplified and retransmitted, is shifted in frequency (velocity) to provide an apparent rate change or Doppler shift.


$\frac{J}{S}$ > ~ 6dB
VGPO Motion
Target Doppler
$\frac{J}{S}$ = ∞
VGPO Motion
- Doppler Frequency +

Figure 12. Velocity Gate Pull Off.

VELOCITY NOISE (VN)

VN is a coherent repeater technique. The objective is to create noise centered on a coherent radar's RF, with a noise bandwidth that is close to, or less than, the radar's bandwidth and conceal the target, or destroy target signal coherency. VN is generated by pseudo randomly stepping a frequency over the victim radar's bandwidth. The dashed RF lines represent possible frequencies and the solid line represents the frequency currently active.


Target
Current RF
- f +
Bandwidth

Figure 13. Velocity Noise.

This page intentionally left blank.

RADAR AND RECEIVER CHARACTERISTICS & TEST

RF Atmospheric Absorption / Ducting 5-1
Receiver Sensitivity / Noise 5-2
Receiver Types and Characteristics 5-3
Radar Modes 5-4
General Radar Display Types 5-5
IFF - Identification - Friend or Foe 5-6
Receiver Tests 5-7
Signal Sorting and Direction Finding 5-8

This page intentionally left blank.

RF ATMOSPHERIC ABSORPTION / DUCTING

Signal losses are associated with each stage of signal processing in both the transmitting and receiving portions of the system. The transmitting losses include power transmission efficiency, waveguide and antenna losses, and duplexer losses. In the receiver, losses include antenna, waveguide, RF amplifier, mixer, and IF amplifier.

In addition to these losses, energy traveling through the atmosphere suffers from atmospheric attenuation caused primarily by absorption by the gasses. For lower frequencies (below 10 GHz), the attenuation is reasonably predictable. For high frequencies in the millimeter wave range, the attenuation not only increases, but becomes more dependent upon peculiar absorbing characteristics of H_2O, O_2, and the like.

Figure 1 shows the areas of peak absorption in the millimeter wave spectrum. Figure 2 shows how the intensity of precipitation can affect atmospheric attenuation.



Figure 1. Atmospheric Absorption of Millimeter Waves.



Figure 2. Atmospheric Attenuation.

Ducting is an increase in range that an electromagnetic wave will travel due to a temperature inversion of the lower atmosphere (troposphere) as shown in Figure 3. The temperature inversion forms a channel or waveguide (duct) for the waves to travel in, and they can be trapped, not attenuating as would be expected from the radar equation. Ducting may also extend range beyond what might be expected from limitations of the radar horizon (see Section 2-9).

The ducting phenomena is frequency sensitive. The thicker the duct, the lower the minimum trapped frequency.



Figure 3. Ducting.

A similar occurrence takes place with ionospheric refraction, however the greatest increase in range occurs in the lower frequencies. This is familiar to amateur radio operators who are able to contact counterparts “around the world.”

RECEIVER SENSITIVITY / NOISE

RECEIVER SENSITIVITY

Sensitivity in a receiver is normally taken as the minimum input signal (S_{min}) required to produce a specified output signal having a specified signal-to-noise (S/N) ratio and is defined as the minimum signal-to-noise ratio times the mean noise power, see equation [1]. For a signal impinging on the antenna (system level) sensitivity is known as minimum operational sensitivity (MOS), see equation [2]. Since MOS includes antenna gain, it may be expressed in dBLi (dB referenced to a linear isotropic antenna). When specifying the sensitivity of receivers intended to intercept and process pulse signals, the minimum pulse width at which the specified sensitivity applies must also be stated. See the discussion of post-detection bandwidth (B_V) in Section 5-2 for significance of minimum pulsewidth in the receiver design.

$\mathbf{S_{min} = (S/N)_{min}kT_oB(NF)}$ receiver sensitivity ("black box" performance parameter) **[1]**

or $\mathbf{MOS = (S/N)_{min}kT_oB(NF)/G}$ system sensitivity i.e. the receiver is connected to an antenna **[2]**
(transmission line loss included with antenna gain)

where: S/N_{min} = Minimum signal-to-noise ratio needed to process (vice just detect) a signal
NF = Noise figure/factor
k = Boltzmann's Constant = 1.38×10^{-23} Joule/°K
T_o = Absolute temperature of the receiver input (°Kelvin) = 290°K
B = Receiver Bandwidth (Hz)
G = Antenna/system gain

We have a lower MOS if temperature, bandwidth, NF, or S/N_{min} decreases, or if antenna gain increases. For radar, missile, and EW receivers, sensitivity is usually stated in dBm. For communications and commercial broadcasting receivers, sensitivity is usually stated in micro-volts or dBμv. See Section 4-1.

There is no standard definition of sensitivity level. The term minimum operational sensitivity (MOS) can be used in place of S_{min} at the system level where aircraft installation characteristics are included. The "black box" term minimum detectable signal (MDS) is often used for S_{min} but can cause confusion because a receiver may be able to detect a signal, but not properly process it. MDS can also be confused with minimum discernable signal, which is frequently used when a human operator is used to interpret the reception results. A human interpretation is also required with minimum visible signal (MVS) and tangential sensitivity (discussed later). To avoid confusion, the terms S_{min} for "black box" minimum sensitivity and MOS for system minimum sensitivity are used in this section. All receivers are designed for a certain sensitivity level based on requirements. One would not design a receiver with more sensitivity than required because it limits the receiver bandwidth and will require the receiver to process signals it is not interested in. In general, while processing signals, the higher the power level at which the sensitivity is set, the fewer the number of false alarms which will be processed. Simultaneously, the probability of detection of a "good" (low-noise) signal will be decreased.

Sensitivity can be defined in two opposite ways, so discussions can frequently be confusing. It can be the ratio of response to input or input to response. In using the first method (most common in receiver discussions and used herein), it will be a negative number (in dBm), with the more negative being "better" sensitivity, e.g., -60 dBm is "better" than -50 dBm sensitivity. If the second method is used, the result will be a positive number, with higher being "better." Therefore the terms low sensitivity or high sensitivity can be very confusing. The terms S_{min} and MOS avoid confusion.

SIGNAL-TO-NOISE (S/N) RATIO

The Signal-to-Noise Ratio (S/N) (a.k.a. SNR) in a receiver is the signal power in the receiver divided by the mean noise power of the receiver. All receivers require the signal to exceed the noise by some amount. Usually if the signal power is less than or just equals the noise power it is not detectable. For a signal to be detected, the signal energy plus the noise energy must exceed some threshold value. Therefore, just because N is in the denominator doesn't mean it can be increased to lower the MOS. S/N is a required minimum ratio, if N is increased, then S must also be increased to maintain that threshold. The threshold value is chosen high enough above the mean noise level so that the probability of random noise peaks exceeding the threshold, and causing false alarms, is acceptably low.

Figure 1 depicts the concept of required S/N. It can be seen that the signal at time A exceeds the S/N ratio and indicates a false alarm or target. The signal at time B is just at the threshold, and the signal at time C is clearly below it. In the sample, if the temperature is taken as room temperature (T_o = 290°K), the noise power input is -114 dBm for a one MHz bandwidth. Normally S/N_{min} may be set higher than S/N shown in Figure 1 to meet false alarm specifications.


DETECTION THRESHOLD
A
False alarm due to noise
B
TIME
C
S/N
AVERAGE NOISE POWER
k = Boltzman's Constant =1.38 x 10^-23 Joules / °K
T₀ = Temperature (°K) = 290 °K
B = Bandwidth (Hz)
P_N = -114 dBm for a 1 MHz bandwidth
P_N = -174 dBm for a 1 Hz bandwidth
• P_N = k T₀ B
• Distribution is Gaussian

Figure 1. Receiver Noise Power at Room Temperature.

The acceptable minimum Signal-to-Noise ratio (or think of it as Signal **above** Noise) for a receiver depends on the intended use of the receiver. For instance, a receiver that had to detect a single radar pulse would probably need a higher minimum S/N than a receiver that could integrate a large number of radar pulses (increasing the total signal energy) for detection with the same probability of false alarms. Receivers with human operators using a video display may function satisfactorily with low minimum S/N because a skilled operator can be very proficient at picking signals out of a noise background. As shown in Table 1, the setting of an acceptable minimum S/N is highly dependent on the required characteristics of the receiver and of the signal.

Table 1. Typical Minimum S/N Required.

Skilled Operator	Auto-Detection	Auto-detection with Amplitude, TOA, and Frequency Measurements	AOA Phase Interferometer	AOA Amplitude Comparison
3 to 8 dB	10 to 14 dB	14 to 18 dB	14 to 18 dB	16 to 24 dB

A complete discussion of the subject would require a lengthy dissertation of the probability and statistics of signal detection, which is beyond the scope of this handbook, however a simplified introduction follows. Let's assume that we have a receiver that we want a certain probability of detecting a single pulse with a specified false alarm probability. We can use Figure 2 to determine the required signal-to-noise ratio.

S/N EXAMPLE

If we are given that the desired probability of detecting a single pulse (P_d) is 98%, and we want the false alarm rate (P_n) to be no more than 10^{-3}, then we can see that S/N must be 12 dB (see Figure 2).



Figure 2. Nomograph of Signal-to-Noise (S/N) Ratio as a Function of Probability of Detection (P_d) and Probability of False Alarm Rate (P_n).

MAXIMUM DETECTION RANGE (ONE-WAY)

From Section 4-3, the one way signal strength from a transmitter to a receiver is:

$$S\ (or\ P_R) = \frac{P_t G_t G_r \lambda^2}{(4\pi)^2 R^2}$$

For calculations involving receiver sensitivity the "S" can be replaced by S_{min}. Since $S_{min} = (S/N)_{min}$ $kT_oB(NF)$, given by equation [1], the one-way radar equation can be solved for any of the other variables in terms of receiver parameters. In communication, radar, and electronic warfare applications, you might need to solve for the maximum range (R_{max}) where a given radar warning receiver could detect a radiated signal with known parameters. We would then combine and rearrange the two equations mentioned to solve for the following one-way equation:

$$R_{max} \cong \sqrt{\frac{P_t\ G_t\ G_r\ \lambda^2}{(4\pi)^2\,(S/N)_{min}\,k\,T_o\,B\,(NF)}} \quad or \quad \sqrt{\frac{P_t\ G_t\ G_r\ c^2}{(4\pi f)^2\,(S/N)_{min}\,k\,T_o\,B\,(NF)}} \quad or \quad \sqrt{\frac{P_t\ G_t\ A_e}{4\pi\,(S/N)_{min}\,k\,T_o\,B\,(NF)}} \qquad \textbf{[3]}$$

We could use standard room temperature of 290° K as T_o, but NF would have to be determined as shown later.

In this calculation for receiver R_{max} determination, P_t, G_t, and λ are radar dependent, while G_r, S/N_{min}, NF, and B are receiver dependent factors.

Equation [3] relates the maximum detection range to bandwidth (B). The effects of the measurement bandwidth can significantly reduce the energy that can be measured from the peak power applied to the receiver input. Additional bandwidth details are provided in Sections 4-4, 4-7, and in other parts of this section.

NOISE POWER, kT_oB

Thermal noise is spread more or less uniformly over the entire frequency spectrum. Therefore the amount of noise appearing in the output of an ideal receiver is proportional to the absolute temperature of the receiver input system (antenna etc) times the bandwidth of the receiver. The factor of proportionality is Boltzmann's Constant.

Mean noise power of ideal receiver = kT_oB = P_N (Watts)
Mean noise power of a real receiver = $(NF)kT_oB$ (Watts)

The convention for the temperature of T_o is set by IEEE standard to be 290°K, which is close to ordinary room temperature. So, assuming T_o = 290°K, and for a bandwidth B = 1 Hz, $kT_oB = 4\times10^{-21}$ W = -204 dBW = -174 dBm.

For any receiver bandwidth, multiply 4×10^{-21} W by the bandwidth in Hz, or if using dB;

$10 \log kT_oB$ = -174 dBm + 10 Log (actual BW in Hz) or -114 dBm + 10 Log (actual BW in MHz)

and so on, as shown by the values in Table 2.

Table 2. Sample Noise Power Values (kT_oB).

Bandwidth	Bandwidth Ratio (dB)	Watts	dBW	dBm
1 Hz	0	4×10^{-21}	-204	-174
1 kHz	30	4×10^{-18}	-174	-144
1 MHz	60	4×10^{-15}	-144	-114
1 GHz	90	4×10^{-12}	-114	-84

Typical values for maximum sensitivity of receivers would be:

RWR	-65 dBm
Pulse Radar	-94 dBm
CW Missile Seeker	-138 dBm

If antenna contributions are ignored (see note in Table 4) for a CW receiver with a 4 GHz bandwidth, the ideal mean noise power would be -174 dBm + 10 Log(4×10^9) = -174 dBm + 96 dB = -78 dBm. A skilled operator might only be able to distinguish a signal 3 dB above the noise floor (S/N=3 dB), or -75 dBm. A typical radar receiver would require a S/N of 3 to 10 dB to distinguish the signal from noise, and would require 10 to 20 dB to track. Auto tracking might require a S/N of approximately 25 dB, thus, a receiver may only have sufficient sensitivity to be able to identify targets down to -53 dBm. Actual pulse receiver detection will be further reduced due to sin x/x frequency distribution and the effect of the measurement bandwidth as discussed in Sections 4-4 and 4-7. Integration will increase the S/N since the signal is coherent and the noise is not.

Noise Bandwidth

Equivalent Noise Bandwidth (B_N) - Set by minimum pulse width or maximum modulation bandwidth needed for the system requirements. A choice which is available to the designer is the relationship of pre- and post-detection bandwidth. Pre-detection bandwidth is denoted by B_{IF}, while post-detection is denoted B_V, where V stands for video. The most affordable approach is to set the post-detection filter equal to the reciprocal of the minimum pulse width, then choose the pre-detection passband to be as wide as the background interference environment will allow. Recent studies suggest that pre-detection bandwidths in excess of 100 MHz will allow significant loss of signals due to "pulse-on-pulse" conditions. Equations [4] and [5] provide B_N relationships that don't follow the Table 3 rules of thumb.

Table 3. Rules of Thumb for B_N a.k.a. B (Doesn't apply for S/N between 0 and 10 to 30 dB).

S/N out	Linear Detector	Square Law Detector
High S/N (>15 to 20 dB)	$B_N = B_V$ (> 20 to 30 dB)	$B_N = 4 B_V$ (> 10 to 15 dB)
Low S/N (< 0 dB)	$B_N = \sqrt{(2 B_{IF} B_V - B_V^2) / 4 (S/N)_{out}}$	$B_N = \sqrt{(2 B_{IF} B_V - B_V^2) / (S/N)_{out}}$

For a square law detector: (1)

$$B_N = B_V \left[2 + \sqrt{4 + \frac{(2 B_{IF} / B_V) - 1}{(S/N)_{out}}} \right] \qquad \textbf{[4]}$$

At high $(S/N)_{out}$, the $1/(S/N_{out})$ term goes to zero and we have: $B_N = B_V [2 + \sqrt{4}] = 4 B_V$

At low $(S/N)_{out}$, the $1/(S/N_{out})$ term dominates, and we have:

$$B_N = B_V \sqrt{\frac{(2 B_{IF} / B_V) - 1}{(S/N)_{out}}} = \sqrt{\frac{2 B_{IF} B_V - B_V^2}{(S/N)_{out}}}$$

For a linear detector: (1)

$$B_N = \frac{B_V}{2} + \frac{1}{4} \bullet \sqrt{B_V \left(4 B_V + \frac{H^2 (2 B_{IF} - B_V)}{(S/N)_{out}} \right)} \qquad \textbf{[5]}$$

H is a hypergeometric (statistical) function of $(S/N)_{in}$

$H = 2$ for $(S/N)_{in} << 1$
$H = 1$ for $(S/N)_{in} >> 1$

At high $(S/N)_{out}$, the $1/(S/N_{out})$ term goes to zero and we have: $B_N = \frac{B_V}{2} + \frac{1}{4}\sqrt{B_V (4 B_V)} = B_V$

At low $(S/N)_{out}$, the $1/(S/N_{out})$ term dominates, and we have:

$$B_N = \frac{1}{4} \bullet \sqrt{\frac{B_V H^2 (2 B_{IF} - B_V)}{(S/N)_{out}}} = \sqrt{\frac{2 B_{IF} B_V - B_V^2}{4 (S/N)_{out}}}$$

Note (1): From Klipper, "Sensitivity of Crystal Video Receivers With RF Pre-amplification," *The Microwave Journal*, August 1965.

TRADITIONAL "RULE OF THUMB" FOR NARROW BANDWIDTHS (Radar Receiver Applications)
Required IF Bandwidth for Matched Filter Applications:

$$B_{IF} = \frac{1}{PW_{\min}} \quad \text{Where :} \quad \begin{array}{l} B_{IF} = \text{Pre - detection RF or IF bandwidth} \\ PW_{\min} = \text{Specified minimum pulse width} = \tau \end{array}$$

Matched filter performance gives maximum probability of detection for a given signal level, but: (1) Requires perfect centering of signal spectrum with filter bandwidth, (2) Time response of matched pulse does not stabilize at a final value, and (3) Out-of-band splatter impulse duration equals minimum pulse width. As a result, EW performance with pulses of unknown frequency and pulse width is poor.

Required Video Bandwidth Post - Detection
Traditional " Rule of Thumb"

$$B_V = \frac{0.35}{PW_{\min}} \quad \text{Where : } B_V = \text{Post - detection bandwidth}$$

Some authors define B_V in terms of the minimum rise time of the detected pulse, i.e., $B_V = (0.35 \text{ to } 0.5)/t_r$ min, where t_r = rise time.

REVISED "RULE OF THUMB" FOR WIDE BANDWIDTHS (Wideband Portion of RWRs)

$$B_{IF} = \frac{2 \text{ to } 3}{PW_{\min}} \quad \text{and} \quad B_V = \frac{1}{PW_{\min}}$$

The pre-detection bandwidth is chosen based upon interference and spurious generation concerns. The post-detection bandwidth is chosen to "match" the minimum pulse width. This allows (1) Half bandwidth mistuning between signal and filter, (2) Half of the minimum pulse width for final value stabilization, and (3) The noise bandwidth to be "matched" to the minimum pulse width. As a result, there is (1) Improved EW performance with pulses of unknown frequency and pulse width, (2) Measurement of in-band, but mistuned pulses, and (3) Rejection of out-of-band pulse splatter.

NOISE FIGURE / FACTOR (NF)

Electrical noise is defined as electrical energy of random amplitude, phase, and frequency. It is present in the output of every radio receiver. At the frequencies used by most radars, the noise is generated primarily within the input stages of the receiver system itself (Johnson Noise). These stages are not inherently noisier than others, but noise generated at the input and amplified by the receiver's full gain greatly exceeds the noise generated further along the receiver chain. The noise performance of a receiver is described by a figure of merit called the noise figure (NF). The term noise factor is synonymous, with some authors using the term "factor" for numeric and "figure" when using dB notation. (The notation "F_n" is also sometimes used instead of "NF.") The noise figure is defined as:

$$NF = \frac{Noise\ output\ of\ actual\ receiver}{Noise\ output\ of\ ideal\ receiver} = \frac{N_{out}}{GN_{in}} \quad or\ in\ dB: \quad 10\ \text{Log}\left[\frac{Noise\ output\ of\ actual\ receiver}{Noise\ output\ of\ ideal\ receiver}\right] = 10\ \log\frac{N_{out}}{GN_{in}}$$

A range of NF values is shown in Table 4.

Table 4. Typical Noise Figure / Factor Value.	Decimal	dB
Passive lossy network (RF transmission line, attenuator, etc.) Example: 20 dB attenuator (gain = 0.01)	Same as reciprocal of gain value ex: 100	Same as dB value ex: 20
Solid State Amplifier (see manufacturers specifications)	4	6
Traveling Wave Tube (see manufacturers specifications)	10 to 100	10 to 20
Antennas (Below ≈ 100 MHz, values to 12 dB higher if pointed at the sun) Note: Unless the antenna is pointed at the sun, its negligible NF can be ignored. Antenna gain is not valid for NF calculations because the noise is received in the near field.	1.012 to 1.4	0.05 to 1.5

An ideal receiver generates no noise internally. The only noise in its output is received from external sources. That noise has the same characteristics as the noise resulting from thermal agitation in a conductor. Thermal agitation noise is caused by the continuous random motion of free electrons which are present in every conductor. The amount of motion is proportional to the conductor's temperature above absolute zero. For passive lossy networks, the noise factor equals the loss value for the passive element:

$$NF = \frac{N_{out}}{G\,N_{in}} = \frac{kTB}{\frac{1}{L}kTB} = L \qquad \begin{array}{c} Where\ L = Ratio\ Value\ of\ Attenuation \\ i.e.\ For\ a\ 3\ dB\ attenuator, G = 0.5\ and\ L = 2 \\ \therefore NF = 2\ \ and\ \ 10\log NF = 3\ dB \end{array}$$

A typical series of cascaded amplifiers is shown in Figure 3.



Figure 3. Noise Factors for Cascaded Amplifiers (NF_{CA}).

Loss (negative gain) can be used for the gain value of attenuators or transmission line loss, etc to calculate the noise out of the installation as shown in the following equation:

$$N_{out} = N_{in}\,G\,NF_{CA} = k\,T\,B_1(\,G_1G_2G_3\dots)\left(NF_1 + \frac{B_2(NF_2-1)}{B_1G_1} + \frac{B_3(NF_3-1)}{B_1G_1G_2} + \frac{B_4(NF_4-1)}{B_1G_1G_2G_3} + \dots\right) \quad (ratio\ form) \qquad \textbf{[6]}$$

If the bandwidths of the amplifiers are the same, equation [6] becomes:

$$N_{out} = N_{in}\, G\, NF_{CA} = k\,T\,B\,(G_1 G_2 G_3 \ldots)\left(NF_1 + \frac{NF_2 - 1}{G_1} + \frac{NF_3 - 1}{G_1 G_2} + \frac{NF_4 - 1}{G_1 G_2 G_3} + \ldots \right) \quad \textit{(ratio form)} \qquad \textbf{[7]}$$

Pre-amplifier Location Affects Receiver Input Noise

As shown in Figure 4, if a 2 to 12 GHz receiver installation doesn't have enough sensitivity, it is best to install an additional amplifier closer to the antenna (case 1) instead of closer to the receiver (case 2). In both cases, the line loss (L) and the amplifier gain (G) are the same, so the signal level at the receiver is the same. For case 1, $S_1 = P_{in} + G - L$. In case 2, $S_2 = P_{in} - L + G$, so $S_1 = S_2$. The noise generated by the passive transmission line when measured at the receiver is the same in both cases. However, the noise generated inside the amplifier, when measured at the receiver input, is different.



Figure 4. Pre-Amp S/N.

For this example, case 2 has a noise level at the input to the receiver which is 19.7 dB higher than case 1 (calculations follow later).

Table 5a	Case 1 Gain		Case 1 NF	
	Amp	L	Amp	L
dB	25	-20	6 *	20
ratio	316.2	0.01	4 *	100

Table 5b	Case 2 Gain		Case 2 NF	
	L	Amp	L	Amp
dB	-20	25	20	6 *
ratio	0.01	316.2	100	4 *

* Amplifier NF value from Table 4.

Using equation [3] and the data in Tables 5a and 5b, the noise generated by the RF installation is shown in Tables 6a and 6b (the negligible noise contribution from the antenna is the same in both cases and is not included) (also see notes contained in Table 4):

Table 6a. Case 1	**Table 6b.** Case 2
$G(NF) = 316.2\,(0.01)\left(4 + \frac{100 - 1}{316.7}\right) = 13.64$	$G(NF) = 0.01\,(316.2)\left(100 + \frac{4 - 1}{0.01}\right) = 1264.8$
10 log G(NF) = 11.34 dB	10 log G(NF) = 31 dB
Noise at receiver:	
$N_{out\,1}$ = -74 dBm + 11.34 dB = -62.7 dBm	$N_{out\,2}$ = -74 dBm + 31 dB = -43 dBm

$N_{out\,2} - N_{out\,1}$ = 19.7 dB. The input noise of -74 dBm was calculated using 10 log (kTB), where B = 10 GHz.

Note that other tradeoffs must be considered: (1) greater line loss between the antenna and amplifier improves (decreases) VSWR as shown in Section 6-2, and (2) the more input line loss, the higher the input signal can be before causing the pre-amplifier to become saturated (mixing of signals due to a saturated amplifier is addressed in Section 5-7).

Combining Receive Paths Can Reduce Sensitivity

If a single aircraft receiver processes both forward and aft signals as shown in Figure 5, it is desirable to be able to use the receiver's full dynamic range for both directions. Therefore, one needs to balance the gain, so that a signal applied to the aft antenna will reach the receiver at the same level as if it was applied to the forward antenna.



Figure 5. Example of Pre-Amplifier Affecting Overall Gain / Sensitivity.

Common adjustable preamplifiers can be installed to account for the excessive transmission line loss. In this example, in the forward installation, the level of the signal at the receiver is the same as the level applied to the antenna. Since the aft transmission line has 5 dB less attenuation, that amount is added to the preamplifier attenuator to balance the gain. This works fine for strong signals, but not for weaker signals. Because there is less loss between the aft preamplifier and the receiver, the aft noise dominates and will limit forward sensitivity. If the bandwidth is 2-12 GHz, and if port A of the hybrid is terminated by a perfect 50Ω load, the forward noise level would be -65.3 dBm. If port B is terminated, the aft noise level would be -60.4 dBm. With both ports connected, the composite noise level would be -59.2 dBm (convert to mw, add, then convert back to dBm). For this example, if the aft preamplifier attenuation value is changed to 12 dB, the gain is no longer balanced (7 dB extra loss aft), but the noise is balanced, i.e., forward = -65.6 dBm, aft = -65.3 dBm, and composite -62.4 dBm. If there were a requirement to see the forward signals at the most sensitive level, extra attenuation could be inserted in the aft preamplifier. This would allow the forward noise level to predominate and result in greater forward sensitivity where it is needed. Calculations are provided in Tables 7 and 8.

Table 7. Summary of Gain and NF Values for Figure 5 Components.

		Aft					Fwd				
		RF Line	Amp	Attn	Amp	RF Line & hybrid	RF Line	Amp	Attn	Amp	RF Line & hybrid
Gain	dB	-7	15	-5	10	-13	-2	15	0	10	-23
	ratio	0.2	31.6	0.32	10	0.05	0.63	31.6	0	10	0.005
NF	dB	7	6	5	6	13	2	6	0	6	23
	ratio	5	4	3.16	4	20	1.585	4	0	4	200

Aft NF = 22.79 therefore 10 log NF = 13.58 dB. Input noise level = -74 dBm + 13.58 dB = -60.42 dBm ≅ -60.4 dBm
Fwd NF = 7.495 therefore 10 log NF = 8.75 dB. Input noise level = -74 dBm + 8.75 dB = -65.25 dBm ≅ -65.3 dBm
The composite noise level at the receiver = -59.187 dBm ≅ -59.2 dBm.

Table 8. Effect of Varying the Attenuation (shaded area) in the Aft Preamplifier Listed in Table 7.

Aft Attn NF	Aft Attn Gain	Aft Noise	Fwd Noise	Composite Noise	Min Signal Received ***	Aft Input	Fwd Input
0 dB	0 dB	-55.8 dBm	-65.3 dBm	-55.4 dBm	-43.4 dBm	-48.4 dBm	-43.4 dBm
5	-5	-60.4	-65.3	-59.2	-47.2 *	-47.2 *	-47.2 *
10	-10	-64.4	-65.3	-61.8	-49.8	-44.8	-49.8
12	-12	-65.6 **	-65.3 **	-62.4	-50.4	-43.4	-50.4
15	-15	-67.1	-65.3	-63.1	-51.1	-41.1	-51.1

* Gain Balanced ** Noise Balanced *** S/N was set at 12 dB

TANGENTIAL SENSITIVITY

Tangential sensitivity (TSS) is the point where the top of the noise level with no signal applied is level with the bottom of the noise level on a pulse as shown in Figure 6. It can be determined in the laboratory by varying the amplitude of the input pulse until the stated criterion is reached, or by various approximation formulas.



Figure 6. Tangential Sensitivity.

The signal power is nominally 8±1 dB above the noise level at the TSS point. TSS depends on the RF bandwidth, the video bandwidth, the noise figure, and the detector characteristic.

TSS is generally a characteristic associated with receivers (or RWRs), however the TSS does not necessarily provide a criterion for properly setting the detection threshold. If the threshold is set to TSS, then the false alarm rate is rather high. Radars do not operate at TSS. Most require a more positive S/N for track (> 10 dB) to reduce false detection on noise spikes.

SENSITIVITY CONCLUSION

When all factors effecting system sensitivity are considered, the designer has little flexibility in the choice of receiver parameters. Rather, the performance requirements dictate the limit of sensitivity which can be implemented by the EW receiver.

1. Minimum Signal-to-Noise Ratio (S/N) - Set by the accuracy which you want to measure signal parameters and by the false alarm requirements.

2. Total Receiver Noise Figure (NF) - Set by available technology and system constraints for RF front end performance.

3. Equivalent Noise Bandwidth (B_N) - Set by minimum pulse width or maximum modulation bandwidth needed to accomplish the system requirements. A choice which is available to the designer is the relationship of pre- (B_{IF}) and post-detection (B_V) bandwidth. The most affordable approach is to set the post-detection filter equal to the reciprocal of the minimum pulse width, then choose the pre-detection passband to be as wide as the background interference environment will allow. Recent studies suggest that pre-detection bandwidths in excess of 100 MHz will allow significant loss of signals due to "pulse-on-pulse" conditions.

4. Antenna Gain (G) - Set by the needed instantaneous FOV needed to support the system time to intercept requirements.

This page intentionally left blank.

RECEIVER TYPES AND CHARACTERISTICS

Besides the considerations of noise and noise figure, the capabilities of receivers are highly dependent on the type of receiver design. Most receiver designs are trade-offs of several conflicting requirements. This is especially true of the Electronic Support Measures (ESM) receivers used in Electronic Warfare.

This section consists of a figure and tables that provide a brief comparison of various common ESM receiver types. Figures 1 and 2 show block diagrams of common ESM receivers. Table 1 is a comparison of major features of receivers. Table 2 shows the receiver types best suited for various types of signals and Tables 3 and 4 compare several direction of arrival (DOA) and emitter location techniques. Table 5 shows qualitative and quantitative comparisons of receiver characteristics.


CRYSTAL VIDEO RECEIVER
RF AMPLIFIER
COMPRESSIVE VIDEO AMPLIFIER
Multiplexer
BAND 1 VIDEO
BAND 2 VIDEO
BAND 3 VIDEO
YIG TUNED NARROWBAND SUPERHET
IF AMP
YIG FILTER
IF FILTER
LOG VIDEO AMP
VIDEO
TUNING
YIG OSCILLATOR
WIDEBAND SUPERHET
WIDEBAND FILTER
IF FILTER
RECEIVED SIGNAL
FIXED FREQUENCY OSCILLATOR
INSTANTANEOUS FREQUENCY MEASUREMENT
LIMITING AMPLIFIER
SPLITTER
DELAY LINE
PHASE DETECTOR
SIN
COS
VIDEO CONVERSION
FREQUENCY INFORMATION

Figure 1. Common ESM Receiver Block Diagrams.


CHANNELIZED RECEIVER
r(t)
H_RF
BPF 1
BPF 2
BPF M
A/D
A/D
A/D
Digital Processor
ACOUSTO-OPTIC RECEIVER
BRAGG CELL
COHERENT LIGHT
T
UNDIFFRACTED LIGHT
LENS
INPUT RF
DETECTOR ARRAY
FULL BANDWIDTH
MICROSCAN (COMPRESSIVE) RECEIVER
ANTENNA
MIXER
WEIGHTED FILTER
DDL
VIDEO DETECTOR
OUTPUT
LOCAL OSCILLATOR

Figure 2. Common ESM Receiver Block Diagrams (Continued).

Table 1. Comparison of Major Features of Receivers.

Receiver	Advantages	Disadvantages	Principal Applications
Wideband crystal video	Simple, inexpensive, instantaneous, High POI in frequency range	No frequency resolution Poor sensitivity and Poor simultaneous signal performance	RWR
Tuned RF Crystal Video	Simple, Frequency measurement Higher sensitivity than wideband	Slow response time Poor POI	Option in RWR, Frequency measurement in hybrid
IFM	Relatively simple Frequency resolution Instantaneous, high POI	Cannot sort simultaneous signals Relatively poor sensitivity	Shipboard ESM, Jammer power management, SIGINT equipment
Narrow-band scanning Superhet	High sensitivity Good frequency resolution Simultaneous signals don't interfere	Slow response time Poor POI Poor against frequency agility	SIGINT equipment Air and ship ESM Analysis part of hybrid
Wide-band Superhet	Better response time and POI	Spurious signals generated Poorer sensitivity	Shipboard ESM Tactical air warning
Channelized	Wide bandwidth, Near instantaneous, Moderate frequency resolution	High complexity, cost; Lower reliability; limited sensitivity	SIGINT equipment Jammer power management
Microscan	Near instantaneous, Good resolution and dynamic range, Good simultaneous signal capability	High complexity, Limited bandwidth No pulse modulation information Critical alignment	SIGINT equipment Applications for fine freq analysis over wide range
Acousto-optic	Near instantaneous, Good resolution, Good simultaneous signal capability Good POI	High complexity; new technology	

Note: The Microscan receiver is also known as a compressive receiver

Table 2. Receiver Types vs. Signal Types.

Signal Type	Receiver Type							
	Wide-Band Crystal Video	TRF Crystal Video	IFM	Narrow-Band Superhet	Wide-Band Superhet	Channelized	Microscan	Acousto-optic
CW	Special design for CW	Special design for CW	Yes, but interferes with pulsed reception	Yes	Yes	Yes	Yes	Yes
Pulsed	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Multiple Frequency	No	No	No	Yes, but won't recognize as same source	No	Yes	Yes	Yes
Frequency Agile	Yes, doesn't measure frequency	No	Yes	No	Yes (within passband)	Yes	Yes	No/Yes, depending on readout time
PRI Agile	Yes	Yes	Yes	No/Yes, depending on scan rate	Yes	Yes	No/Yes, imprecision in TOA	No/Yes, depending on readout time
Chirped	Yes, within acceptance BW	No	Yes	No/Yes, depending on BW	Yes	Yes (reduced sensitivity)	No/Yes, depending on scan rate	Yes (reduced sensitivity)
Spread Spectrum	Yes, within acceptance BW	No	Yes	No	No/Yes, depending on BW	Yes (reduced sensitivity)	Yes (reduced sensitivity)	Yes (reduced sensitivity)

Table 3. Direction of Arrival Measurement Techniques.

	Amplitude Comparison	Phase Interferometer
Sensor Configuration	Typically 4 to 6 Equal Spaced Antenna Elements for 360° Coverage	2 or more RHC or LHC Spirals in Fixed Array
DF Accuracy	$DF_{ACC} \approx \frac{\Theta_{bW}^{2}\,\Delta C_{dB}}{24\,S}$ (Gaussian Antenna Shape)	$DF_{ACC} \approx \frac{\lambda}{2\,\pi\,d\,\cos\theta}\Delta\theta$
DF Accuracy Improvement	Decrease Antenna BW; Decrease Amplitude Mistrack; Increase Squint Angle	Increase Spacing of Outer Antennas; Decrease Phase Mistrack
Typical DF Accuracy	3° to 10° rms	0.1° to 3° rms
Sensitivity to Multipath/Reflections	High Sensitivity; Mistrack of Several dB Can Cause Large DF Errors	Relatively Insensitive; Interferometer Can be Made to Tolerate Large Phase Errors
Platform Constraints	Locate in Reflection Free Area	Reflection Free Area; Real Estate for Array; Prefers Flat Radome
Applicable Receivers	Crystal Video; Channelizer; Acousto-Optic; Compressive; Superheterodyne	Superheterodyne
ΔC_{dB}= Amplitude Monopulse Ratio in dB S= Squint Angle in degrees θ_{BW}= Antenna Beamwidth in degrees		

Table 4. Emitter Location Techniques.

Measurement Technique	Advantages	Disadvantages
Triangulation	Single Aircraft	Non-instantaneous location Inadequate accuracy for remote targeting Not forward looking
Azimuth/elevation	Single Aircraft Instantaneous location possible	Accuracy degrades rapidly at low altitude Function of range
Time Difference of Arrival (Pulsed signals)	Very high precision Can support weapon delivery position requirements Very rapid, can handle short on-time threat	Very complex, diverse systems required, at least 3 aircraft High quality receivers, DME (3 sites) very wideband data link Very high performance control processor; requires very high reliability subsystems

Table 5. Qualitative Comparison of Receivers. (From NRL Report 8737)

Feature	Receiver Type							
	Wide-Band Crystal Video	TRF Crystal Video	IFM	Narrow-Band Superhet	Wide-Band Superhet	Channelized	Microscan	Acousto-optic
Instantaneous Analysis Bandwidth	Very wide	Narrow	Very wide	Narrow	Moderate	Wide	Wide	Moderate
Frequency Resolution	Very poor	Fair	Good	Very good	Poor	Fair	Good	Good
Sensitivity	Poor (No preamp) Fair (preamp)	Fair/ good	Poor (No preamp) Fair (preamp)	Very good	Fair	Fair/ good	Very good	Good
Dynamic Range	Fair	Fair/ good	Good	Very good	Fair	Good	Fair	Poor
Speed of Acquisition	Very Fast	Slow	Very Fast	Slow	Fast	Very Fast	Very Fast	Fast
Short pulse Width Capability	Good	Good	Good	Good	Very good	Good	Fair	Fair
Retention of Signal Characteristics	Fair	Fair	Poor	Good	Fair/ good	Good	Poor	Fair/ good
Applicability to Exotic Signals	Poor/ fair	Poor	Good	Poor	Fair/ good	Good	Fair/ good	Fair/ good
High signal Density Performance	Poor (high false alarm rate from background)	Fair/ good	Good	Poor	Fair (depending on BW)	Fair/good, depending on architecture & processing	Good	Poor
Simultaneous Signal Capability	Poor	Fair/ good	Poor	Good	Fair (depending on BW)	Good	Good	Good
Processing Complexity	Moderate depending on application	Moderate depending on application	Moderate	Moderate	Moderate	Low-high depending on architecture	Complex	Simple signal processing complex data processing
Immunity to Jamming	Poor	Fair	Poor/ Fair	Good	Poor/ Fair	Good	Good	Good
Power Requirements	Low	Low/ Moderate	Moderate	Moderate	Moderate	High	Moderate	Moderate/ High
RF Range (GHz)	Multi-octave (0.5-40)	0.15-18 separate	>0.5 to 40	<0.01 to 40	0.5 to 18	0.5 to 60	<0.5 to 8	0.5-4 (0.5-18 channelized and down conversion)
Max Instantaneous Analysis Bandwidth	Multi-octave (to 17.5 GHz)	As high as desired with equivalent reduction in resolution	Multi-octave (1 octave per unit)	50 MHz	500 MHz	~2 GHz without degradation, 17.5 GHz with degradation	0.5 to 2 depending on PW limitation	1 GHz
Frequency Accuracy	Measurement accuracy no better than analysis BW	Measurement accuracy no better than analysis BW	5-10 MHz	0.5% to 1%	0.5 to 3 MHz	±1 MHz	10 KHz	±1 MHz

Feature	Receiver Type							
	Wide-Band Crystal Video	TRF Crystal Video	IFM	Narrow-Band Superhet	Wide-Band Superhet	Channelized	Microscan	Acousto-optic
Pulse Width Range	CW to 50 ns	CW to 50 ns	CW to ~20 ns (depending on resolution)	CW to 100 ns with 20 MHz resolution	CW to 4 ns with 500 MHz resolution	CW to 30 ns (depending on resolution)	CW to 250 ns	CW to 0.5 µs
Frequency Resolution	~400 MHz (no better than BW)	25 MHz	1 MHz	<0.1 MHz	100-500 MHz	10-125 MHz (less with freq vernier)	1 MHz	0.5 to 1 MHz
Sensitivity (dBm)	-40 to -50 (no preamp) -80 (with preamp)	Better than -80 with preamp	-40 (no preamp) -75 (preamp) 4 GHz BW	-90, 1 MHz BW	-80, 500 MHz BW	-70, 10-50 MHz BW	-90, 5-10 MHz BW	-70 to -80
Maximum Dynamic Range (dB)	70	70-80	80 (w/preamp) 100+ (saturated)	90	60	50-80	40-60	25-35
Tuning Time	-	50 ms	-	1.0 s (1 octave)	.12 s (200 MHz band)	-	0.3 µs LO scan time	0.5 ms (integration time)
Signal ID Time	100 ns	50 ms	2-10 ms	~0.1 s	-	2.10 ms	~1 µs	-
Minimum Weight (lb)	20 (with processor)	30	<20 (octave unit) 65-75 (full coverage)	60-75	35 (tuner only)	1309-200 for 0.5 to 18 GHz coverage	25	29-55
Size / Minimum Volume (in^3)	Small 300 (w/processor)	Small 375	Sm/Moderate 600-1000 ~100 miniaturized	Moderate 1500-3000	Moderate Several thousand	Large 4000-8000 (0.5-18 GHz coverage	Moderate 1200-2000	Small 800-1900
Minimum Power (W)	100 (with processor) <10 without processor	60 (without processor)	~50 (octave unit)	150	150 (tuner only)	350 to 1200 for 0.5 to 18 GHz coverage	70-80	200
Cost	Low	Low/ Moderate	Moderate	Moderate/ High	Moderate/ High	High	Moderate/ High	Low/ Moderate

This page intentionally left blank.

RADAR MODES

Typical Radar modes are listed below in the general functional category for which they were designed. Not all of these modes are applicable to all radars and certain radars have additional modes.

• NAVIGATION

Terrain avoidance - A mode in which the radar is set at a fixed depression angle and short range to continuously sweep the ground area directly in front of the aircraft in order to avoid mountains. This is particularly useful during flight into unfamiliar territory when clouds, haze, or darkness obscure visibility.

Ground mapping - A mode in which the radar uses a variety of techniques to enhance ground features, such as rivers, mountains, and roads. The mode is unlike air-to-air modes where ground return is rejected from the display.

Precision velocity update / Doppler navigation - A mode in which the radar again tracks ground features, using Doppler techniques, in order to precisely predict aircraft ground speed and direction of motion. Wind influences are taken into account, such that the radar can also be used to update the aircraft inertial navigation system.

• FIGHTER MISSIONS

Pulse search - Traditional pulse techniques are used to accurately determine range, angle, and speed of the target. Limitations are easy deception by enemy jamming, and less range when compared to other modes.

Velocity search - A high PRF Pulse Doppler waveform is used for long range detection primarily against nose aspect targets, giving velocity and azimuth information. Although velocity search can work against tail-on targets, the Doppler return is weaker, consequently the maximum detection range is also much less. When the target is in the beam (flying perpendicular to the fighter), the closure (Doppler) is the same as ground return and target return is almost zero.

Track While Scan (TWS) - A system that maintains an actual track on several aircraft while still searching for others. Since the radar is sharing its computing time between targets, the accuracy is less precise than for a single target track (STT) mode of operation.

Raid assessment - A mode in which the radar has an STT on a single target, but is routinely driven off by a small amount in order to determine if multiple aircraft exists in the immediate vicinity of the target aircraft.

Single-Target-Track (STT) (including air combat maneuvering modes) - Highly precise STT modes are used to provide the most accurate information to the fire control computer so that accurate missile or gun firing can be accomplished. The fire control radar continuously directs energy at the target so that the fired missile locates and tracks on the reflected energy from the target. Air combat maneuvering modes are automatic modes in which the radar has several sweep patterns fixed about the aircraft axis, such that little or no work is required of the pilot in order to lock up a target.

- **AIR-TO-GROUND MISSIONS**

Weapons delivery - A mode in which ground features are tracked, and particular emphasis is placed on determining range to the ground target, angle of dive, weapons ballistic tables, and aircraft speed.

Surveillance/tracking of ground forces/targets - Similar to the above with emphasis on multiple ground features and less on weapons delivery data.

Reconnaissance - A specific navigational mode to aid in identifying specific targets.

- **AIR-TO-SURFACE MISSIONS**

ASW - Navigational techniques specializing in specific search patterns to aid in detection of enemy submarines.

- **TECHNIQUES USED FOR MULTIPLE APPLICATIONS**

Synthetic Aperture Radar (SAR) - A form of radar that uses the relative motion between an antenna and its target region, to provide coherent-signal variations, in order to obtain finer spatial resolution than is possible with conventional beam-scanning means. SAR is usually implemented by mounting a single beam-forming antenna on a moving platform such as an aircraft from which a target scene is repeatedly illuminated with pulses of radio waves at wavelengths anywhere from a meter down to millimeters. The many echo waveforms received successively at the different antenna positions are coherently detected and stored and then post-processed together to resolve elements in an image of the target region.

Over-The-Horizon Radar (OTHR) - uses the refraction of high frequency radiation through the ionosphere in order to detect targets beyond the line-of-sight. The complexities of the ionosphere can produce multipath propagation, which may result in multiple resolved detections for a single target. When there are multipath detections, an OTHR tracker will produce several spatially separated tracks for each target. Information conveying the state of the ionosphere is required in order to determine the true location of the target and is available in the form of a set of possible propagation paths, and a transformation from measured coordinates into ground coordinates for each path. Since may be no other information as to how many targets are in the surveillance region, or which propagation path gave rise to which track, there is a joint target and propagation path association ambiguity which must be resolved using the available track and ionospheric information.

GENERAL RADAR DISPLAY TYPES

There are two types of radar displays in common use today.

RAW VIDEO

Raw video displays are simply oscilloscopes that display the detected and amplified target return signal (and the receiver noise). Raw video displays require a human operator to interpret the various target noise and clutter signals.

On the left hand display of Figure 1, an operator could readily identify three targets and a ghost (a ghost is a phony target that usually fades in and out and could be caused by birds, weather, or odd temporary reflections - also referred to as an angel). Target 3 is a weak return and hidden in the noise - an operator can identify it as a target by the “mouse under the rug” effect of raising the noise base line.

SYNTHETIC VIDEO

Synthetic video displays use a computer to clean up the display by eliminating noise and clutter and creating its own precise symbol for each target.

On the right hand display target 1 comes and goes because it is barely above the receiver noise level - notice that it is quite clear on the raw video. Target 3 wasn’t recognized by the computer because it’s too far down in the noise. The computer validated the ghost as a target. The ghost might be a real target with glint or ECM characteristics that were recognized by the computer but not the operator.



Figure 1. Radar Display Types.

SEARCH AND ACQUISITION RADARS

They generally use either a PPI or a sector PPI display as shown in Figure 2. PPI displays can be either raw video or synthetic video.

PPI scope (plan position indicator).
Polar plot of direction and distance.
Displays all targets for 360 degrees.

Sector PPI scope.
Polar plot of direction and distance.
Displays all targets within a specific sector.
Origin may be offset so that "your" radar position may be off the scope.

TRACKING RADARS

Usually use some combination of A, B, C, or E scope displays. There are many other types of displays that have been used at one time or another - including meters - but those listed here are the most common in use today.


0°
RANGE
Target
270°
90°
180°
PPI
Azimuth
0
Target
RANGE
SECTOR PPI
AMPLITUDE
Target
Noise
RANGE or VELOCITY
A-SCOPE
RANGE
Target
(-)
0
(+)
AZIMUTH / ELEVATION
B-SCOPE / E-SCOPE
ELEVATION
Target
AZIMUTH
C-SCOPE

Figure 2. Common Radar Displays.

A-SCOPE

Target signal amplitude vs. range or velocity.

Displays all targets along pencil beam for selected range limits.

Displays tracking gate. Usually raw video. Some modern radars have raw video a-scopes as an adjunct to synthetic video displays.

Must be used with a separate azimuth and elevation display of some sort.

Also called a range scope (R-Scope).

B-SCOPE

Range vs. azimuth or elevation. Displays targets within selected limits.

Displays tracking gate. May be raw or synthetic video.

Surface radars usually have two. One azimuth/one elevation which can result in confusion with multiple targets.

C-SCOPE

Azimuth vs. elevation. Displays targets within selected limits of az and el.

Displays tracking gate. May display bull's-eye or aim dot.

May have range indicator inserted typically as a marker along one side. Usually synthetic video.

Pilots eye view and very common in modern fighter aircraft heads up displays for target being tracked.

Could be used in any application where radar operator needs an "aiming" or "cross hair" view like a rifle scope.

E-SCOPE

Elevation vs. Range similar to a B-scope, with elevation replacing azimuth.

This page intentionally left blank.

IFF - IDENTIFICATION - FRIEND OR FOE

Originated in WWII for just that purpose - a way for our secondary radars to identify U.S. aircraft from enemy aircraft by assigning a unique identifier code to U.S. aircraft transponders.

The system is considered a secondary radar system since it operates completely differently and independently of the primary radar system that tracks aircraft skin returns only, although the same CRT display is frequently used for both.

The system was initially intended to distinguish between enemy and friend but has evolved such that the term “IFF” commonly refers to all modes of operation, including civil and foreign aircraft use.

There are five major modes of operation currently in use by military aircraft plus two sub-modes.

- Mode 1 is a non-secure low cost method used by ships to track aircraft and other ships.
- Mode 2 is used by aircraft to make carrier controlled approaches to ships during inclement weather.
- Mode 3 is the standard system also used by commercial aircraft to relay their position to ground controllers throughout the world for air traffic control (ATC).
- Mode 4 is secure encrypted IFF (the only true method of determining friend or foe) Military only
- Mode 5 – provides a cryptographically secured version of Mode S and ADS-B GPS position. (military only). Mode 5 is divided into two levels. Both are crypto-secure with Enhanced encryption, Spread Spectrum Modulation, and Time of Day Authentication. Level 1 is similar to Mode 4 information but enhanced with an Aircraft Unique PIN. Level 2 is the same as Mode 5 level one but includes additional information such as aircraft position and other attributes
- Mode “C” is the altitude encoder (military and civilian).
- Mode S – provides multiple information formats to a selective interrogation. Typically aircraft are assigned a unique 24-bit Mode S address. The Mode S address is partitioned and a group of address ranges are allocated to each country. Some countries change the assigned address for security reasons, and thus it might not be a unique address. (military and civilian)

The non-secure codes are manually set by the pilot but assigned by the air traffic controller.

A cross-band beacon is used, which simply means that the interrogation pulses are at one frequency and the reply pulses are at a different frequency. 1030 MHz and 1090 MHz is a popular frequency pair used in the U.S.

The secondary radar transmits a series of selectable coded pulses. The aircraft transponder receives and decodes the interrogation pulses. If the interrogation code is correct, the aircraft transponder transmits a different series of coded pulses as a reply.

The advantage of the transponder is that the coded pulses “squawked” by the aircraft transponders after being interrogated might typically be transmitted at a 10 watt ERP, which is much stronger than the microwatt skin return to the primary radar. Input power levels may be on the order of several hundred watts.

The transponder antenna is low gain so that it can receive and reply to a radar from any direction.

An adjunct to the IFF beacon is the altitude encoding transponder known as mode C - all commercial and military aircraft have them, but a fair percentage of general aviation light aircraft do not because of cost. The number of transponder installations rises around many large metropolitan areas where they are required for safety (easier identification of aircraft radar tracks).

Air traffic control primary radars are similar to the two-dimensional search radar (working in azimuth and range only) and cannot measure altitude.

The expanded display in figure 1 is typical of an air traffic control IFF response. The aircraft was told to squawk a four digit number such as “4732.” The altitude encoded transponder provides the aircraft altitude readout to the ground controllers display along with the coded response identifying that particular aircraft.



Figure 1. IFF Transponder.

In addition to systems with active electronic data interchange between airborne and ground equipment, some military surveillance systems can provide targeting in tactical applications. The development of automated techniques for use against ground targets is typically referred to as Automatic Target Recognition (ATR). When used against air targets, it is typically referred to as Non-Cooperative Target Recognition (NCTR). The requirements for radar target recognition are complex since typical targets have background clutter and often multiple targets types exist.

RECEIVER TESTS

Two tone and spurious response (single signal) receiver tests should be performed on EW and radar receivers to evaluate their spurious free dynamic range. A receiver should have three ranges of performance: (1) protection from damage, (2) degraded performance permitted in the presence of a strong interfering signal(s) and no degradation when only a strong desired signal is present, and (3) full system performance.

The original MIL-STD-461A design requirement and its companion MIL-STD-462 test requirement specified four receiver tests. These standards allowed the interfering signal(s) to be both inband and out of band, which is meaningful for design and test of EW receivers, however inband testing generally is not meaningful for narrowband communications receivers. These standards were difficult to follow and had to be tailored to properly evaluate the EW and radar system. MIL-STD-461B/C still allowed the interfering signal(s) to be both inband and out of band but deleted the single signal interference test (CS08 Conducted Susceptibility test). MIL-STD-461D/-462D leave the pass/fail criteria entirely up to what is listed in the individual procurement specification. It also places all interfering signals out of band, redesignates each test number with a number "100" higher than previously used, and combines "CS08" as part of CS104. Therefore, to provide meaningful tests for EW and radar systems, the procurement specification must specify the three ranges of performance mentioned in the beginning of this section and that the tests are to be performed with the interfering signal(s) both inband and out of band. The four tests are as follows (listed in order of likelihood to cause problems):

Test Name	MIL-STD-461A	MIL-STD-461D
Undesired, Single signal interference test	CS08	Part of CS104
Desired with undesired, two signal interference tests	CS04	CS104
Two signal intermodulation test	CS03	CS103
Two signal cross modulation test	CS05	CS105

The rest of this section explains the application of these tests and uses the names of the original MIL-STD-461A tests to separate the tests by function.

TEST SETUP



Figure 1. Receiver Test Setup When Antenna Can Be Removed.

A directional coupler used backwards (as shown here in Figure 1) is an easy way to perform two signal tests. The CW signal should be applied to the coupling arm (port B) since the maximum CW signal level is -10 dBm. The pulse signal should be applied to the straight-through path (port C) since the maximum pulse level is +10 dBm peak. These power levels are achievable with standard laboratory signal generators, therefore one doesn't have to resort to using amplifiers which may distort the signals. Always monitor the output signal to verify spectrally pure signals are being applied to the test unit. This can be accomplished by another directional coupler used in the standard configuration. Dissimilar joints or damaged or corroded microwave components can cause mixing. This can also result if the two signal generators are not isolated from one another. Therefore, even if a directional coupler is used to monitor the signal line, it is still advisable to directly measure the input to the receiver whenever there is a suspected receiver failure. This test does not need to be performed in an EMI shielded room and is more suitable for a radar or EW lab where the desired signals are readily available.

If the receiver's antenna is active or cannot be removed, a modified test as shown in Figure 2 should be performed. The monitoring antenna which is connected to the spectrum analyzer should be the same polarization as the antenna for the receiver being tested. Amplifiers may be required for the F_1 and F_2 signals. It is desirable to perform this test in an anechoic chamber or in free space.



Figure 2. Receiver Test Setup When Antenna Is Active.

In the following discussion of CS08, CS04, CS03, and CS05 tests, it is assumed that when the receive light illuminates, the receiver identifies a signal that matches parameters in the User Data File (UDF) or pre-programmed list of emitter identification parameters. If a receiver is different, the following procedures will have to be appropriately tailored. If the UDF does not have entries for very low level signals in the 10% and 90% regions of each band, complete testing is not possible. Most problems due to higher order mixing products and adjacent band leakage are only evident in these regions. In the following tests, the lowest level where the receive light is constantly on is used to identify the minimum receive level. If a receiver has a receive level hysteresis or other idiosyncrasy, then using a 50% receive light blinking indicator may be more appropriate. Whatever technique is appropriate, it should be consistently used during the remainder of the test. The maximum frequency for testing is normally 20 GHz. If a millimeter wave receiver is being tested, the maximum frequency should be 110 GHz.

CS08 - UNDESIRED, SINGLE SIGNAL INTERFERENCE TEST

MIL-STD-461B/C (EMI design requirements) deleted this test. MIL-STD-461D allows a single signal test as part of CS104 (CS04) but specifies it as an out of band test. The original CS08 inband and out of band test is still needed and is the most meaningful test for wide band EW receivers which have a bandwidth close to an octave. This test will find false identification problems due to 1) lack of RF discrimination, 2) higher order mixing problems, 3) switch or adjacent channel/band leakage, and 4) cases where the absence of a desired signal causes the receiver to search and be more susceptible. In this latter case, a CS04 two signal test could pass because the receiver is captured by the desired signal, whereas a CS08 test could fail. Examples of the first three failures are as follows.

EXAMPLE 1

A 2 to 4 GHz receiver which uses video detection (e.g., crystal video) and doesn't measure RF is used for this example. This receiver assumes that if the correct Pulse Repetition Interval (PRI) is measured, it is from a signal in the frequency band of interest. Three cases can cause false identification. Refer to Figure 3.

(1) Region A&C. The 2 to 4 GHz band pass filter will pass strong signals in regions A&C. If they have the correct PRI, they will also be identified.



Figure 3. Frequency Areas in a Sample 2-4 GHz Receiver.

(2) Region B. Any other signal besides the desired signal in the 2 to 4 GHz region that has the correct PRI will also be identified as the signal of interest.

(3) Region D. Band pass filters with poor characteristics tend to pass signals with only limited attenuation at frequencies that are three times the center frequency of the band pass filter. If these signals have the correct PRI, they will be incorrectly identified.

High duty cycle signals (CW or pulse doppler) in regions A, B, C, and D may overload the processing of signals, saturate the receiver, or desensitize the receiver. This case is really a two signal CS04 test failure and will be addressed in the CS04 section.

EXAMPLE 2

A receiver measuring the carrier frequency of each pulse (i.e., instantaneous frequency measurement (IFM)) and the PRI is used for this example. False signal identification can occur due to higher order mixing products showing up in the receiver pass bands. These unwanted signals result from harmonics of the input RF mixing with harmonics of the Local Oscillator (LO). Refer to Figures 4 and 5.



Figure 4. Low Side Mixing.

Mixers are nonlinear devices and yield the sum, difference, and the original signals. Any subsequent amplifier that is saturated will provide additional mixing products.

If a 8.5 GHz signal with a 1 kHz PRI is programmed to be identified in the UDF, measurements are made at the 2.5 GHz Intermediate Frequency (IF), i.e., RF-LO = IF = 8.5-6 = 2.5 GHz.

The same 2.5 GHz signal can result from an RF signal of 9.5 GHz due to mixing with the second harmonic of the LO i.e., 2 X 6 - 9.5 = 2.5 GHz. This signal will be substantially attenuated (approximately 35 dB) when compared to the normal IF of 9.5 - 6 = 3.5 GHz. If the receiver has filters at the IF to reduce the signal density and a filter has minimum insertion loss at 2.5 GHz and maximum insertion loss at 3.5 GHz, then only the low level 2.5 GHz signal will be measured and assumed to be due to a 8.5 GHz input signal whereas the input is really at 9.5 GHz.



Figure 5. Low Side Mixing Results.

Spurious intermodulation products can also result from high side mixing, but generally the suppression of undesired signals is greater. In this case, the LO is at a frequency higher than the RF input. This is shown in Figures 6 and 7.



Figure 6. High Side Mixing.

Table 1. Intermodulation Product Suppression.

Harmonic of		
LO	RF	Suppression
1	1	0
1	2	ΔP-41
1	3	$2\Delta P$-28
2	1	-35
2	2	ΔP-39
2	3	$2\Delta P$-44
3	1	-10
3	2	ΔP-32
3	3	$2\Delta P$-18
4	1	-35
4	2	Δ-39
5	1	-14
5	3	$2\Delta P$-14
6	1	-35
6	2	ΔP-39
7	1	-17
7	3	$2\Delta P$-11

Courtesy Watkins-Johnson

As previously mentioned, the amplitude of intermodulation products is greatly reduced from that of the original signals. Table 1 shows rule of thumb approximate suppression (reduction), where $\Delta P = P_{RF}(dBm) - P_{LO}(dBm)$. As can be seen, the strength of the LO is a factor. The higher the LO power, the more negative the suppression becomes.

If one assumes the maximum RF power for full system performance is +10 dBm and the LO power level is +20 dBm, then ΔP = -10 dB minimum. Therefore in this example, the 3RF-2LO mixing product would be $2\Delta P - 44 = -20 - 44 = -64$ dB when compared to the desired mixing product.



Figure 7. High Side Mixing Byproducts.

The use of double mixing, as shown in Figure 8, can significantly reduce unwanted signals but it is more expensive. For a 8 GHz signal in, one still generates a 2 GHz IF but by mixing up, then down, unwanted signals are not generated or significantly suppressed.


Hi Mixer
IF
Band Pass Filter
Hi Mixer
Final IF
RF
8 to 10 GHz
X
15 to 13 GHz
X
2 to 4 GHz
LO
23 GHz
LO
17 GHz
IF
15
14
13
LO = 23 GHz
Desired
IF = LO-RF
8
9
10
RF
IF
4
3
2
LO = 17 GHz
Desired
IF = LO-RF
13
14
15
RF

Figure 8. Double Mixing.

Some of these problems can be corrected by:

(1) always having LOs on the high side versus low side of the input RF (but this is more expensive),

(2) using double mixing

(3) software programming the receiver to measure for the potential stronger signal when a weak signal is measured in a certain IF region, and

(4) improved filtering of the LO input to the mixer and the output from the mixer.

EXAMPLE 3

If the same receiver discussed in example 2 had additional bands (Figure 9) and used a switch at the IF to select individual bands, a strong signal in an adjacent band could be inadvertently measured because:

(1) the switch, which may have 80 dB of isolation when measured outside the circuit, may only have 35 dB isolation when installed in a circuit because of the close proximity of input and output lines,

(2) the strong signal in one band may have the same IF value that is being sought in an adjacent band, and

(3) the additional parameters such as PRI may be the same.



* Use of low side LO was done to emphasize a CS08 problem

Figure 9. Multi Band Receiver With Common IF.

As shown in Figure 9, assume that in band 2 we are looking for a 4.5 GHz signal that has a PRI of 1 kHz. Measurements are made at an IF of 3.5 GHz since LO-RF = IF = 8-4.5 = 3.5 GHz. If a 6.5 GHz signal is applied to band 3, its IF also equals 3.5 since LO-RF = 10-6.5 = 3.5 GHz. If this is a strong signal, has a PRI of 1 kHz, and there is switch leakage, a weak signal will be measured and processed when the switch is pointed to band 2. The receiver measures an IF of 3.5 GHz and since the switch is pointed to band 2, it scales the measured IF using the LO of band 2 i.e., LO-IF = RF = 8-3.5 = 4.5 GHz. Therefore, a 4.5 GHz signal is assumed to be measured when a 6.5 GHz signal is applied. Similarly this 6.5 GHz signal would appear as a weak 3.5 GHz signal from band 1 or a 9.5 GHz signal from band 4.

In performing this test it is important to map the entries of the UDF for each band i.e., show each resulting IF, its PRI, and the sensitivity level that the receive light is supposed to illuminate, i.e., if a test in one band used a PRI corresponding to a PRI in another band where the receive threshold is programmed to not be sensitive this will negate the effectiveness of a cross coupling test. Mapping the UDF will facilitate applying a strong signal to one band using the PRI of a desired signal in an adjacent band.

CS08 TEST PROCEDURE



Figure 10. Receiver Band With Multiple UDF Entries.

Assume that the receiver band is 2 to 4 GHz as shown in Figure 10. Pick the UDF entry that has the greatest sensitivity. UDF #1 entry is for a 3±.05 GHz signal with a PRI of 1 kHz. If the test signal is set for the UDF #1 PRI, a receive light will also occur at the frequencies of UDF #2 if it also has the same PRI (this is not a test failure). If adjacent bands don't also have entries with the same PRI, then the test should be repeated for the band being tested with at least one of the adjacent band PRI values.

(1) Set the receiver or jammer to the receive mode, verify it is working for UDF #1 and record P_o, the minimum signal level where the receive light is constantly on.

(2) Raise this signal to its maximum specified level for full system performance. If a maximum level is not specified, use +10 dBm peak for a pulse signal or -10 dBm for a CW signal.

(3) Tune this strong RF signal outside the UDF #1 range and record any RF frequency where the receive light comes on. If another inband UDF has the same PRI, this is not a failure.

(4) This test is performed both inband and out of band. Out of band tests should be performed on the high end to five times the maximum inband frequency or 20 GHz, whichever is less, and on the low end to IF/5 or 0.05 F0, whichever is less, unless otherwise specified. The out of band power level is +10 dBm peak for a pulse signal or -10 dBm for a CW signal, unless otherwise specified.

(5) If a receive light comes on when it is not supposed to, record the RF and reduce the power level to where the receive light just stays on constantly. Record this level P1. The interference rejection level is P1-P0= PIR

(6) Repeat this test for each type of signal the receiver is supposed to process, i.e., pulse, PD, CW, etc.

CS04 - DESIRED WITH UNDESIRED, TWO SIGNAL INTERFERENCE TEST

The intent is for a weak desired signal to be received in the presence of an adjacent CW signal. The desired signal is kept tuned at minimal power level and a strong unmodulated signal is tuned outside the UDF region. Radar and EW receivers without preselectors are likely to experience interference when this test is performed inband. Receivers with nonlinear devices before their passive band pass filter, or filters that degrade out of band, are likely to experience susceptibility problems when this test is performed out of band.

Tests performed inband - An unmodulated CW signal is used. If the receiver is supposed to handle both pulsed and CW signals, this test is performed inband. If the pulse receiver is supposed to desensitize in order to only process pulse signals above the CW level, then only this limited function is tested inband i.e., normally the levels correspond, if a CW signal of -20 dBm is present, then the receiver should process pulse signals greater than -20 dBm.

CS04 TEST PROCEDURE

(1) As shown in Figure 11, initially the pulse signal is tuned to F_0 and the minimum receive level P_0 is recorded, i.e., minimum level where the receive light is constantly on.

(2) The pulse signal is raised to the maximum specified level for full system performance and tuned on either side of F_0 to find the frequencies on both sides (F_{High} and F_{Low}) where the receive light goes out. If a maximum pulse power level is not specified, then +10 dBm peak is used. In some receivers F_L and F_H are the band skirts.



Figure 11. CS04 Test Signals.

(3) The pulse signal is returned to the level found in step 1. A CW signal at the maximum specified CW power level for full system performance is tuned above F_H and below F_L. If a maximum CW power level is not specified, then -10 dBm is used. Anytime the receive light is lost, the tuned CW RF value is recorded. The CW signal should be turned off to verify that the pulse signal can still be received in the absence of

interference. If the pulse signal is still being received, then the interfering CW signal should be reapplied and decreased to the lowest power level where the receive light stays on constantly. Record this level P_1. The interference rejection level is $P_1 - P_0 = P_{IR}$.

(4) Out of band tests should be performed to five times the maximum inband frequency or 20 GHz, whichever is less, and on the low end to IF/5 or 0.05 F_0, whichever is less, unless otherwise specified. The out of band CW power level is -10 dBm unless otherwise specified.

Failures - Out of band test

(1) If a non-linear device such as a limiter is placed before a band pass filter, a strong out of band signal can activate the limiter and cause interference with the inband signal. The solution is to place all non-linear or active devices after a passive band pass filter.

(2) Band pass filters with poor characteristics tend to pass signals with only limited attenuation at frequencies that are three times the center frequency of the band pass filter. Passage of a CW or high duty cycle signal that is out of band may desensitize or interfere with the processing of a weak inband signal.

CS03 INTERMODULATION TEST

This two signal interference test places a pulse signal far enough away (Δf) from the desired UDF frequency (F_0) that it won't be identified. A CW signal is initially placed 2Δf away. If an amplifier is operating in the saturated region, these two signals will mix and produce sum and difference signals. Subsequent mixing will result in a signal at the desired UDF frequency F_0 since $F_1 - (F_2 - F_1) = F_0$. These two signals are raised equally to strong power levels. If no problem occurs, the CW signal is tuned to the upper inband limit and then tuned out of band. A similar test is performed below F_0.

CS03 TEST PROCEDURES

(1) Set the receiver or jammer to the receive mode. Verify it is working at a desired signal frequency, (F_0), and record the minimum signal level i.e., lowest level where the receive light is constantly on (record this level P_0).

(2) The modulated signal is raised to the maximum specified level for full system performance and tuned on either side of F_0 to find the frequency F_1 on both sides where the receive light goes out. If a maximum power level is not specified, +10 dBm peak is used. The difference between F_1 and F_0 is Δf as shown in Figure 12.



Figure 12. Initial CS03 Test Signal.

(3) As shown in Figure 13, a pulse signal is tuned to F_1 and a CW signal is tuned to F_2 where $F_2 = F_1 + \Delta f$ on the high side. The power level of the two signals is initially set to P_0 and raised together until the maximum specified levels for full system performance are reached. If maximum power levels are not specified, then +10 dBm peak is used for the pulse signal and -10 dBm is used for the CW signal. Whenever the receive light comes on, the two signals should be turned off individually to verify that the failure is due to a combination of the two signals versus (1) a single signal (CS08) type failure or (2) another inband UDF value has been matched. If the failure is due to the two signal operation, then the power level (P_1 and P_2) of F_1 and F_2 should be recorded. If $P_1=P_2$, the intermodulation rejection level is $P_1-P_0=P_{IM}$. If $P_1 \neq P_2$, it is desirable to readjust them to be equal when the receive light just comes on.



Figure 13. CS03 Testing Signal.

(4) Once the $F_1 + F_2$ signals are raised to the maximum power test levels described in step 3 without a failure, then F_2 is tuned to the upper limit of the band. F_2 should also be tuned out of band to five times the maximum inband frequency or 20 GHz whichever is less unless otherwise specified. The out of band power level is -10 dBm unless otherwise specified. Whenever the receive light comes on, F_2 should be turned off to verify that the failure is due to a two signal test. If it is, turn F_2 back on and equally drop the power levels of F_1 and F_2 to the lowest level where the receive light just comes on. Record the power levels (P_1 and P_2).

(5) Step 3 is repeated where F_1 is Δf below F_0 and $F_2=F_1-\Delta f$. Step 4 is repeated except F_2 is tuned to the lower limit of the band. F_2 should also be tuned out of band down to 0.1 F_0, unless otherwise specified.

(6) Normally if a failure is going to occur it will occur with the initial setting of F_1 and F_2. Care must be taken when performing this test to ensure that the initial placements of F_1 and F_2 do not result in either of the signals being identified directly.

As shown in Figure 14, if F_1 was placed at 3.2 GHz it would be identified directly and if F_2 was placed at 3.4 GHz it would be identified directly. Whereas, if F_1 was at 3.1 GHz and F_2 was at 3.2 GHz neither interfering signal would be identified directly but their intermodulation may result in an improper identification at F_0. Later when F_2 is tuned higher, the receive light will come on around 3.4 GHz and 3.6 GHz. This is not a test failure just a case of another inband UDF value being matched.



Figure 14. Sample UDF Entries.

CS05 - CROSS MODULATION

This two signal interference test places a weak CW signal where the receiver is programmed for a pulse signal and tunes a strong pulse signal elsewhere. As shown in Figure 15, when an amplifier is saturated, lower level signals are suppressed. When an amplifier is operated in the linear region all signals receive the rated linear gain. In this test the pulse signal will cause the amplifier to kick in and out of saturation and modulate the weak CW signal. The receiver may measure the modulation on the CW signal and incorrectly identify it as a pulse signal.


Amplifier Linear
Pulse
CW
Amplifier Saturated
High Pulse Signal
Amplifier Linear
Amplifier Linear
CW

Figure 15. Cross Modulation Example.

CS05 TEST PROCEDURE

(1) Initially the pulse signal is tuned to F_0 and the minimum power level P_0 where the receive light is constantly on is recorded.

(2) As shown in Figure 16, the signal is raised to the maximum specified level for full system performance for a pulse signal and tuned on either side of F_0 to find the frequencies on both sides, (F_{High} and F_{Low}) where the receive light goes out. If a maximum pulse power level is not specified, then +10 dBm peak is used.


F_L
F_0
F_H
0 dB
Attenuation
- dB
Strong Pulse Signal
(No response)
Weak Pulse Signal
(With Response)
2 GHz
UDF #1
4 GHz
Frequency

Figure 16. Initial CS05 Test Signals.

(3) The pulse signal from step 2 is turned off and a second signal is placed at F_0. It is a CW signal that is 10 dB stronger than the peak power level (P_0) measured is step 1. The receive light should not come on.

(4) As shown in Figure 17, the strong pulse signal of step 2 is turned back on and tuned above F_H and then tuned below F_L. Out of band tests should be performed to the maximum RF of the system + maximum IF or 20 GHz whichever is less and on the low end to the minimum RF of the system minus the maximum IF, unless otherwise specified.

(5) If a receive light occurs, turn off the weak CW signal since the “failure” may be due to the tuned pulsed signal, i.e., a CS08 failure or another inband UDF value has been matched.

If the light extinguishes when the weak CW signal is turned off, then turn the signal back on, reduce the value of the high level pulse signal until the minimum level is reached where the light stays on constantly. Record this level as P_1.

The cross modulation rejection level is P_1-P_0-10 dB = P_{CM}.


0 dB
- dB
Attenuation
F_L
F_O
F_H
Strong Pulse Signal
Weak CW Signal
(10dB greater than P_o)
UDF #1
2 GHz
4 GHz
Frequency

Figure 17. Final CS05 Test Signals.

This page intentionally left blank.

SIGNAL SORTING METHODS and DIRECTION FINDING

As shown in Figure 1, signal processing is basically a problem of signal detection, emitter parameter measurement and correlation, emitter sorting, identification, and operator notification.


TYPICAL ESM / RWR SIGNAL PROCESSING
Detect Signal Activity
De-interleave (Sort) Signals
Measure
- AOA
- Freq
- PRI etc.
Determine Signal Type and Characteristics
Determine Location (DF)
ELINT Database (Location)
Threat UDF Database (Type)
Correlate (Identification)
Action
Display
Record Results
Take Direct CM Action
Jammer
Chaff
Other

Figure 1. Signal Processing Steps.

The ultimate goal of this processing is to classify radar signals by their unique characteristics and to use this data to identify enemy radars operating in the environment, determine their location or direction, assess their threat to friendly forces, and display this information to the operator.

While not all electronic support measures (ESM) or radar warning receiver (RWR) systems perform every step in this process, each completes some of them. For example, ESM systems seldom initiate direct CM action, while RWRs sometimes do. Also ESM systems frequently record electronic data for future use, but few RWRs do. ESM systems place more emphasis on accurate emitter location and hence direction finding capabilities, while RWRs usually give a rough estimate of position/distance.

The typical emitter characteristics that an ESM system can measure for a pulse radar include the following data:

1. Radio Frequency (RF)
2. Amplitude (power)
3. Direction of Arrival (DOA) - also called Angle of Arrival (AOA)
4. Time of Arrival (TOA)
5. Pulse Repetition Interval (PRI)
6. PRI type
7. Pulse Width (PW)
8. Scan type and rate
9. Lobe duration (beam width)

However, this list is not comprehensive. Other emitter parameters are available which may be necessary to characterize the threat system.

More sophisticated ESM systems can measure additional parameters, such as PRI modulation characteristics, inter- and intra-pulse Frequency Modulation (FM), missile guidance characteristics (e.g., pattern of pulse spacing within a pulse group), and Continuous Wave (CW) signals.

Still other parameters which can describe an electromagnetic wave but are currently not commonly used for identification include polarization and phase. However, as threat emitters begin to use this data more frequently to avoid jamming the more important they may become in identifying signals.

Some of the emitter characteristics which describe an electromagnetic wave are shown in Figure 2.


Frequency
Polarization
E_Y
E_X
Time
Time
Waveshape
(Pulse width & interval)
and Amplitude
Phase
Time
DOA
A
These variables can be constant or time varying

Figure 2. Information Content of an Electromagnetic Wave.

Table 1 illustrates the relative importance of several measured parameters during various stages of signal processing.

Table 1. Importance of Emitter Parameters During Signal Processing.

Parameter	Pulse Train De-interleavement	Emitter Identification	Intercept Correlation
Frequency	2	2	2
Amplitude	1	0	1
Angle of Arrival	2	0	2
TOA	0	0	1
PRI	2	2	2
PRI type	2	2	2
PW	2	1	1
Scan rate and type	0	2	1
Lobe Duration	0	1	1
0 Not Useful 1 Some Use 2 Very Useful			

Some emitter parameters can be measured using a single pulse; these parameters are referred to as monopulse parameters. The monopulse parameters include RF, PW, DOA, amplitude and TOA. RF can be determined on a pulse-by-pulse basis by receivers that can measure frequency. Frequency is very useful for emitter identification since most radars operate at a single frequency. Most real-time systems measure pulse width instead of pulse shape because the latter is much more difficult to characterize mathematically. Unfortunately, the apparent pulse width can be severely distorted by reflections, and consequently, its usefulness for emitter identification is limited. DOA cannot be used for emitter identification, but is excellent for sorting signals. A number of ESM systems use both frequency and DOA information to distinguish the new signals from the old (that is, known) ones. Amplitude also cannot be used for emitter identification. However, it can be used for sorting and for gross distance estimation using precompiled emitter's effective radiated power. Moreover, amplitude in conjunction with TOA can be used to determine the emitter's scan characteristics.

Other emitter parameters such as PRI, guidance and scan characteristics can be determined only by analyzing a group of pulses. All these parameters are useful for emitter identification; unfortunately, they require time for data collection and analysis, and call for sophisticated signal processing algorithms.

The problem of signal recognition in real-time is complicated by two factors: modulation of the signals and the very high pulse densities expected in the environment. Complex modulations (for example, inter-pulse RF modulation, intra-pulse RF modulation and agile Pulse Repetition Frequencies (PRFs)) present a significant pattern recognition problem for a number of ESM systems. It is expected that during some missions, hundreds of emitters will be transmitting simultaneously in the same vicinity. Wide-open antenna/receiver combination systems may have to cope with up to a million PPS. Even narrow-band receivers can expect data rates up to 100,000 PPS. At these rates, a single modern computer cannot be expected to process all the pulses, derive the characteristics for all emitters and identify the emitters in real-time. Other factors which encumber signal recognition include missing pulses, atmospheric noise and multiple reflections of pulses.

Present RWRs are designed primarily to cope with stable emitters. A stable emitter is one whose frequency and pulse repetition interval (PRI) remain relatively constant from pulse to pulse. The future threat will move steadily away from the stable emitter towards agile emitters which vary their frequency and PRI characteristics. The first change in this direction is towards the patterned agile emitter which varies its pulse and frequency parameters in accordance with a specific pattern. Examples of patterned agile emitters are MTI radars which use staggered PRFs, pulse Doppler radars which change frequency and PRF on a block-to-block basis, and certain frequency-agile radars whose transmitter frequency is mechanically modulated in a systematic pattern (e.g., spin-tuned magnetron). The next step in this evolution is towards truly agile emitters which change their frequency and PRF in a random manner on a pulse-to-pulse basis. One tempering factor in this evolution is that radars which process Doppler must maintain a constant frequency for at least two consecutive pulses.

In addition to agile frequency and PRI parameters, the future threat will be composed of a number of high-PRF pulsed Doppler, burst-frequency, CW, pulse-compression, agile-beam, and LPI radars, which use pseudo-noise waveforms. This conglomeration of radar types will cause a high signal density which must be segmented into a manageable data stream by the use of both frequency and spatial filtering in the RWR. While frequency and PRI are good parameters for sorting present-day non-agile emitters, they are poor or useless parameters for sorting agile emitters.

Angle of arrival is generally regarded as the best initial sorting parameter because it cannot be varied by the emitter from pulse to pulse.

PASSIVE DIRECTION FINDING AND EMITTER LOCATION

Direction finding (DF) systems provide several important functions in modern EW systems. We have already discussed the importance of measuring the emitter's bearing, or angle of arrival (AOA), as an invariant sorting parameter in the deinterleaving of radar signals and in separating closely spaced communication emitters. In addition, the conservation of jamming power in power-managed ECM systems depends on the ability of the associated ESM system to measure the direction to the victim emitter. A function which is becoming increasingly important in defense suppression and weapon delivery systems involves locating the emitter's position passively. This can be accomplished from a single moving platform through successive measurements of the emitter's angular direction, or from multiple platforms which make simultaneous angular measurements.

The emitter identification function requires identifying and associating consecutive pulses produced by the same emitter in angle of arrival (AOA) and frequency. The AOA is a parameter which a hostile emitter cannot change on a pulse-to-pulse basis. However, to measure the AOA of pulses which overlap in the time domain first requires them to be separated in the frequency domain. The advanced ESM receivers which accomplish this function must operate over several octaves of bandwidth while providing RMS bearing accuracies on the order of at least 2 degrees with high POI and fast reaction time in dense signal environments.

There are basically three methods, depicted in Figure 3, which allow the passive location of stationary ground-based emitters from airborne platforms.

These are:

1. The azimuth triangulation method where the intersection of successive spatially displaced bearing measurements provides the emitter location.

2. The azimuth/elevation location technique, which provides a single-pulse instantaneous emitter location from the intersection of the measured azimuth/elevation line with the earth's surface.

3. The time difference of arrival (TDOA), or precision emitter location system (PELS) method, which measures the difference in time of arrival of a single pulse at three spatially remote locations.



Figure 3. Passive Emitter Location Techniques.

Additional methods include:

1. Phase rate of change, which is similar to triangulation, except it makes calculations using the phase derivative.

2. Angle distance techniques, where the distance from the emitter is derived from the signal strength (with known "threat" characteristics).

3. RF Doppler processing, which measures Doppler changes as the aircraft varies direction with respect to the "target" radar.

The relative advantages and disadvantages of each are given in Table 2.

Table 2. Emitter Location Techniques.

Measurement Technique	Advantages	Disadvantages
Triangulation	Single Aircraft	Non-Instantaneous Location; Inadequate Accuracy for Remote Targeting; Not Forward Looking
Azimuth/Elevation	Single Aircraft Instantaneous Location Possible	Accuracy Degrades Rapidly at Low Altitude; Function of Range
Time Difference of Arrival (Pulsed Signals)	Very High Precision Can Support Weapon Delivery Position Requirements Very Rapid, Can Handle Short On-Time Threat	Very Complex, At Least 3 Aircraft; High Quality Receivers; DME (3 Sites); Very Wideband Data Link; Very High Performance Control Processor; Requires Very High Reliability Subsystems. Requires common time reference and correlation operation for non-pulse signals.

The triangulation method has the advantage of using a single aircraft, and its accuracy is greatest for a long baseline and the broadside geometry. The accuracy degenerates as the aircraft heading line approaches the boresight to the emitter.

The azimuth/elevation technique also has the advantage of using a single aircraft, but suffers from the difficultness of making an accurate elevation measurement with limited vertical aperture and in the presence of multipath effects.

The TDOA technique requires multiple aircraft and is complex, but has high potential accuracy. The determination of the location of the site involves the solution of at least two simultaneous second order equations for the intersection of two hyperbolas which represent $T_2 - T_1 =$ Constant #1 and $T_3 - T_2 =$ Constant #2. This method can be used to obtain a fix for an emitter which radiates only a single pulse.

ANGLE-OF-ARRIVAL (AOA) MEASUREMENTS

Several of the above DF measurements require AOA determination. Threat AOA measurements are also required to inform the aircrew in order to position the aircraft for optimal defense.

As shown in Figure 4, angle-of-arrival measuring systems fall into three main system categories of:

1. Scanning beam
2. Amplitude comparison or Simultaneous-multiple-beam
3. Phased Interferometer techniques


▪ Scanning Beam
- Slow Response
- Low Probability of Intercept
Bearing
▪ Amplitude Comparison
- Very Common, Low Cost
- Small Size
- Relatively Low Resolution
- One RF Path per Band/Sector
A1
A2
Bearing
A2
A3
DOA = f(A2/A3)
▪ Phased Interferometer or Array
- Very High Resolution
- High Cost
- Larger Size
- 3-5 Antennas/RF Paths per Band/Sector
- Conformal Arrays Possible
or
DOA = f(Δ Phase)

Figure 4. Angle-of-Arrival Measurement Techniques.

Scanning Beam

The mechanically scanning beam, or "spinner," requires only a single receiver and also exhibits high sensitivity due to the use of a directive antenna. The disadvantage is that the "spinner" usually exhibits slow response because it must rotate through the coverage angle (e.g., 360 degrees) to ensure that it intercepts an emitter. Also, if the emitter uses a scanning directional antenna, both beams must point at each other for maximum sensitivity, which is a low probability occurrence. Both of these effects cause the mechanically scanning beam technique to have a low probability of intercept (POI).

Amplitude Comparison

The two primary techniques used for direction finding are the amplitude-comparison method and the interferometer or phase-comparison method. The phase-comparison method generally has the advantage of greater accuracy, but the amplitude-comparison method is used extensively due to its lower complexity and cost. Regardless of which technique is used, it should be emphasized that the ultimate rms angular accuracy is given by:

$$\Delta\theta = \frac{k\,\theta_B}{\sqrt{SNR}}$$

where θ_B is the antenna's angular beamwidth, or interferometer lobe width, and SNR is the signal-to-noise ratio.

Thus, phase interferometers that typically use very widebeam antennas require high signal-to-noise ratios to achieve accurate angle-of-arrival measurements. Alternately, a multi-element array antenna can be used to provide relatively narrow interferometer lobes, which require modest signal-to-noise ratios.

Virtually all currently deployed radar warning receiving (RWR) systems use amplitude-comparison direction finding (DF). A basic amplitude-comparison receiver derives a ratio, and ultimately angle-of-arrival or bearing, from a pair of independent receiving channels, which utilize squinted antenna elements that are usually equidistantly spaced to provide an instantaneous 360° coverage. Typically, four or six antenna elements and receiver channels are used in such systems, and wideband logarithmic video detectors provide the signals for bearing-angle determination. The monopulse ratio is obtained by subtraction of the detected logarithmic signals, and the bearing is computed from the value of the ratio.

Amplitude comparison RWRs typically use broadband cavity-backed spiral antenna elements whose patterns can be approximated by Gaussian-shaped beams. Gaussian-shaped beams have the property that the logarithmic output ratio slope in dB is linear as a function of angle of arrival. Thus, a digital look-up table can be used to determine the angle directly. However, both the antenna beamwidth and squint angle vary with frequency over the multi-octave bands used in RWRs. Pattern shape variations cause a larger pattern crossover loss for high frequencies and a reduced slope sensitivity at low frequencies. Partial compensation of these effects, including antenna squint, can be implemented using a look-up table if frequency information is available in the RWR. Otherwise, gross compensation can be made, depending upon the RF octave band utilized.

Typical accuracies can be expected to range from 3 to 10 degrees rms for multi-octave frequency band amplitude-comparison systems which cover 360 degrees with four to six antennas.

The four-quadrant amplitude-comparison DF systems employed in RWRs have the advantage of simplicity, reliability, and low cost. Usually, only one antenna per quadrant is employed which covers the 2 to 18 GHz band. The disadvantages are poor accuracy and sensitivity, which result from the broad-beam antennas employed. Both accuracy and sensitivity can be improved by expanding the number of antennas employed. For example, expanding to eight antennas would double the accuracy and provide 3 dB more gain. As the number of antennas increases, it becomes appropriate to consider multiple-beam-forming antennas rather than just increasing the number of individual antennas. The geometry of multiple-beam-forming antennas is such that a conformal installation aboard an aircraft is difficult. Therefore, this type of installation is typically found on naval vessels or ground vehicles where the space is available to accommodate this type of antenna.

Simultaneous-multiple-beam (amplitude comparison)

The simultaneous-multiple-beam system uses an antenna, or several antennas, forming a number of simultaneous beams (e.g., Butler matrix or Rotman lens), thereby retaining the high sensitivity of the scanning antenna approach while providing fast response. However, it requires many parallel receiving channels, each with full frequency coverage. This approach is compatible with amplitude-monopulse angular measuring techniques which are capable of providing high angular accuracy.

A typical example of a multiple-beam antenna is a 16-element circular array developed as part of a digital ESM receiver. This system covers the range from 2 to 18 GHz with two antenna arrays (2 to 7.5 GHz and 7.5 to 18 GHz), has a sensitivity of -55 to -60 dBm and provides an rms bearing accuracy of better than 1.7 degrees on pulsewidths down to 100 ns.

Phased Interferometer Techniques

The term interferometer generally refers to an array type antenna in which large element spacing occurs and grating lobes appear.

Phase interferometer DF systems are utilized when accurate angle-of-arrival information is required. They have the advantage of fast response, but require relatively complex microwave circuitry, which must maintain a precise phase match over a wide frequency band under extreme environmental conditions. When high accuracy is required (on the order of 0.1 to 1°), wide baseline interferometers are utilized with ambiguity resolving circuitry. The basic geometry is depicted in Figure 5, whereby a plane wave arriving at an angle is received by one antenna earlier than the other due to the difference in path length.

The time difference can be expressed as a phase difference:

$$\varphi = \omega\Delta\tau = 2\pi a(f/c) = 2\pi\,(d \sin\theta)/\lambda,$$

where θ is the angle of arrival,
d is the antenna separation, and
λ is the wavelength in compatible units.

The unambiguous field of view (FOV) is given by $\theta = 2 \sin^{-1} (\pi/2d)$, which for $\lambda/2$ spacing results in 180° coverage. This spacing must be established for the highest frequency to be received.

Interferometer elements typically use broad antenna beams with beamwidths on the order of 90°. This lack of directivity produces several adverse effects. First, it limits system sensitivity due to the reduced antenna gain. Secondly, it opens the system to interference signals from within the antenna's broad angular coverage. The interference signals often include multipath from strong signals which can limit the accuracy of the interferometer.



Figure 5. Phase Interferometer Principle.

In an interferometer, the locus of points that produce the same time or phase delay forms a cone. The indicated angle is the true azimuth angle multiplied by the cosine of the elevation angle. The error in assuming the incident angle to be the azimuth angle is negligible for signals near the antenna's boresight. At 45° azimuth and 10° elevation, the error is less than 1°, increasing to 15° for both at 45°. Two orthogonal arrays, one measuring the azimuth angle and the other the elevation angle can eliminate this error. For targets near the horizon, the depression angle is small, thereby requiring only horizontal arrays.

The rms angular accuracy of an interferometer in radians is given by:

$\sigma_\theta = \Delta\alpha \,/\, (\pi \bullet \sqrt{SNR}\,),$ where $\Delta\alpha = \lambda/(d\cdot\cos\theta)$ is the separation between adjacent nulls.

For a two-element interferometer, the spacing (d) must be $\lambda/2$ or less to provide unambiguous, or single lobe ± 90°, coverage. This, in effect, sets a wide interferometer (or grating) lobe which must be split by a large factor to achieve high accuracy. This, in turn, imposes a requirement for high SNR to achieve the large beam-splitting factor. For example, if 0.1° accuracy is required from an unambiguous two-element interferometer, then a SNR of about 50 dB is required to achieve this accuracy. This may be difficult to achieve considering the inherently low sensitivity of an interferometer system.

When high accuracy is required from an interferometer system, it is usual to employ separations greater than λ/2. The increased separation sets up a multi-grating-lobe structure through the coverage angle which requires less SNR to achieve a specified accuracy. For example, a two-element interferometer with 16λ spacing would set up a 33-grating-lobe structure (including the central lobe) throughout the ± 90° coverage angle. Within each of the 33 grating lobes, it would only require a SNR on the order of 20 dB to achieve 0.1° accuracy. However, there would be 33 ambiguous regions within the ± 90° angular coverage and also 32 nulls (where the phase detector output is zero), about which the system would be insensitive to an input signal. The ambiguities could be resolved by employing a third antenna element with λ/2 spacing, which would provide an accuracy on the order of 3° with 20 dB SNR. This accuracy is sufficient to identify which of the 33 lobes contains the signal. Providing coverage in the null regions requires additional antenna elements.

Interferometers employing multiple antenna elements are called multiple-baseline interferometers. In a typical design, the receiver consists of a reference antenna and a series of companion antennas. The spacing between the reference element and the first companion antenna is λ/2; other secondary elements are placed to form pairs separated by 1, 2, 4, and 8 wavelengths. The initial AOA is measured unambiguously by the shortest-spaced antenna pair. The next greatest spaced pair has a phase rate of change which is twice that of the first, but the information is ambiguous due to there being twice as many lobes as in the preceding pair. A greater phase rate of change permits higher angular accuracy while the ambiguity is resolved by the previous pair. Thus, the described multiple-baseline interferometer provides a binary AOA measurement where each bit of the measurement supplies a more accurate estimate of the emitter's AOA.

Harmonic multiple-baseline interferometers use elements which are spaced at $2^n \cdot \lambda/2$, with n = 0, 1, 2, 3. In nonharmonic interferometers, no pair of antennas provides a completely unambiguous reading over the complete field of view. For example, the initial spacing in the nonharmonic interferometer might be λ, while the next companion element spacing is 3λ/2. Ambiguities are resolved by truth tables, and hence the accuracy is set by the spacing of the widest baseline antenna pair. Nonharmonic interferometers have been implemented over 9:1 bandwidths (2 to 18 GHz) with rms accuracies from 0.1 to 1° and with no ambiguities over ± 90°. The principal advantage of the nonharmonic over the harmonic interferometer is the increased bandwidth for unambiguous coverage.

Interferometer DF accuracy is determined by the widest baseline pair. Typical cavity-backed spirals, track to 6 electrical degrees, and associated receivers track to 9°, resulting in an rms total of 11°. At a typical 16 dB SNR, the rms phase noise is approximately 9 electrical degrees. For these errors and an emitter angle of 45°, a spacing of 25λ is required for 0.1° rms accuracy while a spacing of 2.5λ is needed for 1° accuracy. For high accuracy, interferometer spacings of many feet are required. In airborne applications, this usually involves mounting interferometer antennas in the aircraft's wingtips.

The characteristics of typical airborne amplitude comparison and phase interferometer DF systems are summarized in Table 3. The phase interferometer system generally uses superheterodyne receivers which provide the necessary selectivity and sensitivity for precise phase measurements.

Table 3. Direction of Arrival Measurement Techniques.

	Amplitude Comparison	Phase Interferometer
Sensor Configuration	Typically 4 to 6 Equispaced Antenna Elements for 360° Coverage	2 or more RHC or LHC Spirals in Fixed Array
DF Accuracy	$DF_{ACC} \approx \frac{\theta_{BW}^2 \Delta C_{dB}}{24S}$ (Gaussian Shape)	$DF_{ACC} = \frac{\lambda}{2\pi d \cos\theta} \Delta\theta$
DF Accuracy Improvement	Decrease Antenna BW Decrease Amplitude Mistrack Increase Squint Angle	Increase Spacing of Outer Antennas; Decrease Phase Mistrack
Typical DF Accuracy	3° to 10° rms	0.1° to 3° rms
Sensitivity to Multipath/ Reflections	High Sensitivity Mistrack of Several dB Can Cause Large DF Errors	Relatively Insensitive; Interferometer Can Be Made to Tolerate Large Phase Errors
Platform Constraints	Locate in Reflection Free Area	Reflection Free Area; Real Estate For Array; Prefers Flat Radome
Applicable Receivers	Crystal Video; Channelizer; Acousto-Optic; Compressive; Superheterodyne	Superheterodyne

ΔC_{dB} = Amplitude Monopulse Ratio in dB
S = Squint Angle in degrees
θ_{BW} = Antenna Beamwidth in degrees

This page intentionally left blank.

MICROWAVE / RF COMPONENTS

Microwave Waveguides and Coaxial Cable 6-1
Voltage Standing Wave Ratio (VSWR) / Reflection Coefficient
    Return Loss / Mismatch Loss 6-2
Microwave Coaxial Connectors 6-3
Power Dividers and Directional Couplers 6-4
Attenuators / Filters / DC Blocks 6-5
Terminations / Dummy Loads 6-6
Circulators and Diplexers 6-7
Mixers and Frequency Discriminators 6-8
Detectors 6-9
RF / Microwave Amplifiers 6-10
Signal Generation 6-11
Digital Processing Components 6-12
Microwave Measurements 6-13

This page intentionally left blank.

MICROWAVE WAVEGUIDES and COAXIAL CABLE



Figure 1. The Rectangular Waveguide.

In general, a waveguide consists of a hollow metallic tube of arbitrary cross section uniform in extent in the direction of propagation. Common waveguide shapes are rectangular, circular, and ridged. The rectangular waveguide has a width a and height b as shown in Figure 1. Commonly used rectangular waveguides have an aspect ratio b/a of approximately 0.5. Such an aspect ratio is used to preclude generation of field variations with height and their attendant unwanted modes. Waveguides are used principally at frequencies in the microwave range; inconveniently large guides would be required to transmit radio-frequency power at longer wavelengths. In the X-Band frequency range of 8.2 to 12.4 GHz, for example, the U.S. standard rectangular waveguide, WR-90, has an inner width of 2.286 cm (0.9 in.) and an inner height of 1.016 cm (0.4 in.).

In waveguides the electric and magnetic fields are confined to the space within the guides. Thus no power is lost to radiation. Since the guides are normally filled with air, dielectric losses are negligible. However, there is some I^2R power lost to heat in the walls of the guides, but this loss is usually very small.



Figure 2. TE Modes.

It is possible to propagate several modes of electromagnetic waves within a waveguide. The physical dimensions of a waveguide determine the cutoff frequency for each mode. If the frequency of the impressed signal is above the cutoff frequency for a given mode, the electromagnetic energy can be transmitted through the guide for that particular mode with minimal attenuation. Otherwise the electromagnetic energy with a frequency below cutoff for that particular mode will be attenuated to a negligible value in a relatively short distance. This grammatical use of cutoff frequency is opposite that used for coaxial cable, where cutoff frequency is for the highest useable frequency. The dominant mode in a particular waveguide is the mode having the lowest cutoff frequency. For rectangular waveguide this is the TE_{10} mode. The TE (transverse electric) signifies that all electric fields are transverse to the direction of propagation and that no longitudinal electric field is present. There is a longitudinal component of magnetic field and for this reason the TE_{mn} waves are also called H_{mn} waves. The TE designation is usually preferred. Figure 2 shows a graphical depiction of the E field variation in a waveguide for the TE_{10}, TE_{20}, and TE_{30} modes. As can be seen, the first index indicates the number of half wave loops across the width of the guide and the second index, the number of loops across the height of the guide - which in this case is zero. It is advisable to choose the dimensions of a guide in such a way that, for a given input signal, only the energy of the dominant mode can be transmitted through the guide. For example, if for a particular frequency, the width of a rectangular guide is too large, then the TE_{20} mode can propagate causing a myriad of problems. For rectangular guides of low aspect ratio the TE_{20} mode is the next higher order mode and is harmonically related to the cutoff frequency of the TE_{10} mode. It is this relationship together with attenuation and propagation considerations that determine the normal operating range of rectangular waveguide.

The discussion on circular waveguides will not be included because they are rarely used in the EW area. Information regarding circular waveguides can be found in numerous textbooks on microwaves.

CHARACTERISTICS OF STANDARD RECTANGULAR WAVEGUIDES

Rectangular waveguides are commonly used for power transmission at microwave frequencies. Their physical dimensions are regulated by the frequency of the signal being transmitted. Table 1 tabulates the characteristics of the standard rectangular waveguides. It may be noted that the number following the EIA prefix "WR" is in inside dimension of the widest part of the waveguide (i.e., WR90 has an inner dimension of 0.90").

DOUBLE RIDGE RECTANGULAR WAVEGUIDE



Figure 3. Double Ridge Waveguide.

Another type of waveguide commonly used in EW systems is the double ridge rectangular waveguide. The ridges in this waveguide increase the bandwidth of the guide at the expense of higher attenuation and lower power-handling capability. The bandwidth can easily exceed that of two contiguous standard waveguides. Introduction of the ridges mainly lowers the cutoff frequency of the TE_{10} mode from that of the unloaded guide, which is predicated on width alone. The reason for this can easily be explained when the field configuration in the guide at cutoff is investigated. At cutoff there is no longitudinal propagation down the guide. The waves simply travel back and forth between the side walls of the guide. In fact the guide can be viewed as a composite parallel plate waveguide of infinite width where the width corresponds to the direction of propagation of the normal guide. The TE_{10} mode cutoff occurs where this composite guide has its lowest-order resonant frequency. This occurs when there is only one E field maximum across the guide which occurs at the center for a symmetrical ridge. Because of the reduced height of the guide under the ridge, the effective TE_{10} mode resonator is heavily loaded as though a shunt capacitor were placed across it. The cutoff frequency is thus lowered considerably. For the TE_{20} mode the fields in the center of the guide will be at a minimum. Therefore the loading will have a negligible effect. For guides of proper aspect ratio, ridge height, and ridge width, an exact analysis shows that the TE_{10} mode cutoff can be lowered substantially at the same time the TE_{20} and TE_{30} mode cutoffs are raised slightly. Figure 3 shows a typical double ridged waveguide shape and Table 2 shows double ridged waveguide specifications. In the case of ridged waveguides, in the EIA designation, (WRD350 D36) the first "D" stands for double ridged ("S" for single ridged), the 350 is the starting frequency (3.5 GHz), and the "D36" indicates a bandwidth of 3.6:1. The physical dimensions and characteristics of a WRD350 D24 and WRD350 D36 are radically different. A waveguide with a MIL-W-23351 dash number beginning in 2 (i.e., 2-025) is a double ridge 3.6:1 bandwidth waveguide. Likewise a 1- is a single ridge 3.6:1, a 3- is a single ridge 2.4:1, and a 4- is a double ridge 2.4:1 waveguide.

Figure 4 shows a comparison of the frequency /attenuation characteristics of various waveguides. The attenuation is based on real waveguides which is higher than the theoretical values listed in Tables 1 and 2. Figure 5 shows photographs of waveguides with some common connectors. Figure 6 shows attenuation characteristics of various RF coaxial cables.



Figure 4. Attenuation vs. Frequency for a Variety of Waveguides and Cables.

Table 1. Rectangular Waveguide Specifications.

Waveguide Size	JAN WG Desig	MIL-W-85 Dash #	Material	Freq Range (GHz)	Freq Cutoff (GHz)	Power (at 1 Atm)		Insertion Loss (dB/100ft)	Dimensions (Inches)	
						CW	Peak		Outside	Wall Thickness
WR284	RG48/U RG75/U	1-039 1-042	Copper Aluminum	2.60 - 3.95	2.08	45 36	7650	.742-.508 1.116-.764	3.000x1.500	0.08
WR229	RG340/U RG341/U	1-045 1-048	Copper Aluminum	3.30 - 4.90	2.577	30 24	5480	.946-.671 1.422-1.009	2.418x1.273	0.064
WR187	RG49/U RG95/U	1-051 1-054	Copper Aluminum	3.95 - 5.85	3.156	18 14.5	3300	1.395-.967 2.097-1.454	1.000x1.000	0.064
WR159	RG343/U RG344/U	1-057 1-060	Copper Aluminum	4.90 - 7.05	3.705	15 12	2790	1.533-1.160 2.334-1.744	1.718x0.923	0.064
WR137	RG50/U RG106/U	1-063 1-066	Copper Aluminum	5.85 - 8.20	4.285	10 8	1980	1.987-1.562 2.955-2.348	1.500x0.750	0.064
WR112	RG51/U RG68/U	1-069 1-072	Copper Aluminum	7.05 - 10.0	5.26	6 4.8	1280	2.776-2.154 4.173-3.238	1.250x0.625	0.064
WR90	RG52/U RG67/U	1-075 1-078	Copper Aluminum	8.2 - 12.4	6.56	3 2.4	760	4.238-2.995 6.506-4.502	1.000x0.500	0.05
WR75	RG346/U RG347/U	1-081 1-084	Copper Aluminum	10.0 - 15.0	7.847	2.8 2.2	620	5.121-3.577 7.698-5.377	0.850x0.475	0.05
WR62	RG91/U RG349/U	1-087 1-091	Copper Aluminum	12.4 - 18.0	9.49	1.8 1.4	460	6.451-4.743 9.700-7.131	0.702x0.391	0.04
WR51	RG352/U RG351/U	1-094 1-098	Copper Aluminum	15.0 - 22.0	11.54	1.2 1	310	8.812-6.384 13.250-9.598	0.590x0.335	0.04
WR42	RG53/U	1-100	Copper	18.0 - 26.5	14.08	0.8	170	13.80-10.13	0.500x0.250	0.04
WR34	RG354/U	1-107	Copper	2.0 - 33.0	17.28	0.6	140	16.86-11.73	0.420x0.250	0.04
WR28	RG271/U	3-007	Copper	26.5 - 40.0	21.1	0.5	100	23.02-15.77	0.360x0.220	0.04



Standard waveguide - 7 mm

Double ridge waveguide - SMA jack

Figure 5. Waveguides With Some Common Connections.

Table 2. Double Ridge Rectangular Waveguide Specifications.

Waveguide Size	MIL-W-23351 Dash #	Material	Freq Range (GHz)	Freq Cutoff (GHz)	Power (at 1 Atm)		Insertion Loss (dB/ft)	Dimensions (Inches)					
					CW	Peak		A	B	C	D	E	F
WRD250		Alum Brass Copper Silver Al	2.60 - 7.80	2.093	24	120	0.025 0.025 0.018 0.019	1.655	0.715	2	1	0.44	0.15
WRD350 D24	4-029 4-303 4-031	Alum Brass Copper	3.50 - 8.20	2.915	18	150	0.0307 0.0303 0.0204	1.48	0.688	1.608	0.816	0.37	0.292
WRD475 D24	4-033 4-034 4-035	Alum Brass Copper	4.75 - 11.00	3.961	8	85	0.0487 0.0481 0.0324	1.09	0.506	1.19	0.606	0.272	0.215
WRD500 D36	2-025 2-026 2-027	Alum Brass Copper	5.00 - 18.00	4.222	4	15	0.146 0.141 0.095	0.752	0.323	0.852	0.423	0.188	0.063
WRD650		Alum Brass Copper	6.50 - 18.00	5.348	4	25	0.106 0.105 0.07	0.720	0.321	0.820	0.421	0.173	0.101
WRD750 D24	4-037 4-038 4-039	Alum Brass Copper	7.50 - 18.00	6.239	4.8	35	0.0964 0.0951 0.0641	0.691	0.321	0.791	0.421	0.173	0.136
WRD110 D24	4-041 4-042 4-043	Alum Brass Copper	11.00 - 26.50	9.363	1.4	15	0.171 0.169 0.144	0.471	0.219	0.551	0.299	0.118	0.093
WRD180 D24	4-045 4-046 4-047	Alum Brass Copper	18.00 - 40.00	14.995	0.8	5	0.358 0.353 0.238	0.288	0.134	0.368	0.214	0.072	0.057



Figure 6. Attenuation vs. Frequency for a Variety of Coaxial Cables.

This page intentionally left blank.

VOLTAGE STANDING WAVE RATIO (VSWR) / REFLECTION COEFFICIENT RETURN LOSS / MISMATCH LOSS

When a transmission line is terminated with an impedance, Z_L, that is not equal to the characteristic impedance of the transmission line, Z_O, not all of the incident power is absorbed by the termination. Part of the power is reflected back so that phase addition and subtraction of the incident and reflected waves creates a voltage standing wave pattern on the transmission line. The ratio of the maximum to minimum voltage is known as the Voltage Standing Wave Ratio (VSWR) and successive maxima and minima are spaced by 180° ($\lambda/2$).

$$VSWR = \frac{E_{\max}}{E_{\min}} = \frac{E_i + E_r}{E_i - E_r}$$

where $E_{\max}$ = maximum voltage on the standing wave
$E_{\min}$ = minimum voltage on the standing wave
Ei = incident voltage wave amplitude
Er = reflected voltage wave amplitude

The reflection coefficient, ρ, is defined as E_r/E_i and in general, the termination is complex in value, so that ρ will be a complex number.

Additionally we define: $\Gamma = \frac{Z_L - Z_O}{Z_L + Z_O}$ The refection coefficient, ρ, is the absolute value of the magnitude of Γ. If the equation for VSWR is solved for the reflection coefficient, it is found that:

$$\begin{matrix} \textit{Reflection} \\ \textit{Coefficient} \end{matrix} = \rho = |\Gamma| = \frac{VSWR - 1}{VSWR + 1} \qquad \text{Consequently, } VSWR = \frac{1 + \rho}{1 - \rho}$$

The return loss is related through the following equations:

$$\begin{matrix} \textit{Return} \\ \textit{Loss} \end{matrix} = 10 \log \left[\frac{P_i}{P_r} \right] = -20 \log \left[\frac{E_r}{E_i} \right] = -20 \log \left[\frac{VSWR - 1}{VSWR + 1} \right] = -20 \log \rho$$

Return loss is a measure in dB of the ratio of power in the incident wave to that in the reflected wave, and as defined above always has a positive value. For example if a load has a Return Loss of 10 dB, then 1/10 of the incident power is reflected. The higher the return loss, the less power is actually lost.

Also of considerable interest is the Mismatch Loss. This is a measure of how much the transmitted power is attenuated due to reflection. It is given by the following equation:

Mismatch Loss = -10 log (1 -ρ^2)

For example, an antenna with a VSWR of 2:1 would have a reflection coefficient of 0.333, a mismatch loss of 0.51 dB, and a return loss of

VSWR	Return Loss (dB)	% Power / Voltage Loss	Reflection Coefficient	Mismatch Loss (dB)
1	∞	0 / 0	0	0.000
1.15	23.1	0.49 / 7.0	0.07	.021
1.25	19.1	1.2 / 11.1	0.111	.054
1.5	14.0	4.0 / 20.0	0.200	.177
1.75	11.3	7.4 / 27.3	0.273	.336
1.9	10.0	9.6 / 31.6	0.316	.458
2.0	9.5	11.1 / 33.3	0.333	.512
2.5	7.4	18.2 / 42.9	0.429	.880
3.0	6.0	25.1 / 50.0	0.500	1.25
3.5	5.1	30.9 / 55.5	0.555	1.6
4.0	4.4	36.3 / 60.0	0.600	1.94
4.5	3.9	40.7 / 63.6	0.636	2.25
5.0	3.5	44.7 / 66.6	0.666	2.55
10	1.7	67.6 / 81.8	0.818	4.81
20	0.87	81.9 / 90.5	0.905	7.4
100	0.17	96.2 / 98.0	0.980	14.1
∞	.000	100 / 100	1.00	∞

* Divide % Voltage loss by 100 to obtain ρ (reflection coefficient)

9.54 dB (11% of your transmitter power is reflected back). In some systems this is not a trivial amount and points to the need for components with low VSWR.

If 1000 watts (60 dBm/ 30 dBW) is applied to this antenna, the return loss would be 9.54 dB. Therefore, 111.1 watts would be reflected and 888.9 watts (59.488 dBm/29.488 dBW) would be transmitted, so the mismatch loss would be 0.512 dB.



Figure 1. Reduction of VSWR by Attenuation.

Transmission line attenuation improves the VSWR of a load or antenna. For example, a transmitting antenna with a VSWR of 10:1 (poor) and a line loss of 6 dB would measure 1.5:1 (okay) if measured at the transmitter. Figure 1 shows this effect.

Therefore, if you are interested in determining the performance of antennas, the VSWR should always be measured at the antenna connector itself rather than at the output of the transmitter. Transmit cabling will load the line and create an illusion of having a better antenna VSWR. Transmission lines should have their insertion loss (attenuation) measured in lieu of VSWR, but VSWR measurements of transmission lines are still important because connection problems usually show up as VSWR spikes.

Historically VSWR was measured by probing the transmission line. From the ratio of the maximum to minimum voltage, the reflection coefficient and terminating impedance could be calculated. This was a time consuming process since the measurement was at a single frequency and mechanical adjustments had to be made to minimize coupling into circuits. Problems with detector characteristics also made the process less accurate. The modern network analyzer system sweeps very large frequency bandwidths and measures the incident power, P_i, and the reflected power, P_r. Because of the considerable computing power in the network analyzer, the return loss is calculated from the equation given previously, and displayed in real time. Optionally, the VSWR can also be calculated from the return loss and displayed real time.

If a filter is needed on the output of a jammer, it is desirable to place it approximately half way between the jammer and antenna. This may allow the use of a less expensive filter, or a reflective filter vs. an absorptive filter.

Special cases exist when comparing open and shorted circuits. These two conditions result in the same ∞ VSWR and zero dB return loss even though there is a 180° phase difference between the reflection coefficients. These two conditions are used to calibrate a network analyzer.

MICROWAVE COAXIAL CONNECTORS

For high-frequency operation, the average circumference of a coaxial cable must be limited to about one wavelength in order to reduce multimodal propagation and eliminate erratic reflection coefficients, power losses, and signal distortion.

Except for the sexless APC-7 connector, all other connectors are identified as either male (plugs) which have a center conductor that is a probe or female (jacks) which have a center conductor that is a receptacle. Sometimes it is hard to distinguish them as some female jacks may have a hollow center "pin" which appears to be male, yet accepts a smaller male contact.

An adapter is an approximately zero loss interface between two connectors and is called a barrel when both connectors are identical. A number of common of coaxial connectors are described below, however other special purpose connectors exist, including blind mate connectors where spring fingers are used in place of threads to obtain shielding (desired connector shielding should be at least 90 dB).

APC-2.4 (2.4mm) - The 50 Ω APC-2.4 (Amphenol Precision Connector-2.4 mm) is also known as an OS-50 connector. It was designed to operate at extremely high microwave frequencies (up to 50 GHz).	 2.4 mm jack - 3.5 mm jack
APC-3.5 (3.5mm) - The APC-3.5 connector provides repeatable connections and has a very low VSWR. Either the male or female end of this 50 Ω connector can mate with the opposite type of SMA connector. The APC-3.5 connector can work at frequencies up to 34 GHz.	
APC-7 (7mm) - The APC-7 was developed by HP, but has been improved and is now manufactured by Amphenol. The connector provides a coupling mechanism without male or female distinction and is the most repeatable connecting device used for very accurate 50 Ω measurement applications. Its VSWR is extremely low up to 18 GHz. Other companies have 7mm series available.	 7mm - 3.5mm plug
BNC (OSB) - The BNC (Bayonet Neill-Concelman or Bayonet Navy Connector) was originally designed for military system applications during World War II. The connector operates best at frequencies up to about 4 GHz; beyond that it tends to radiate electromagnetic energy. The BNC can accept flexible cables with diameters of up to 6.35 mm (0.25 in.) and characteristic impedance of 50 to 75 Ω. It is now the most commonly used connector for frequencies under 1 GHz. Other names the BNC has picked up over the years include: "Baby Neill-Concelman", "Baby N connector", "British Naval Connector", and "Bayonet Nut Connector"	 BNC male plug (above) BNC female jack

C - The C (Concelman) coaxial connector is a medium size, older type constant 50 Ω impedance. It has a bayonet (twist and lock) connection. It is larger than the BNC, but about the same as Type N. It has a frequency range of 0-11 GHz	C Plug (top)  C jack (bottom)
SC (OSSC) - The SC type connector is a screw version of the "C" connector.	
SMA (OSM/3mm) - The SMA (Sub-Miniature A) connector was originally designed by Bendix Scintilla Corporation, but it has been manufactured by the Omni-Spectra division of M/ACOM (as the OSM connector) and many other electronic companies. It is a 50 Ω threaded connector. The main application of SMA connectors is on components for microwave systems. The connector normally has a frequency range to 18 GHz, but high performance varieties can be used to 26.5 GHz.	 SMA Plug (above) SMA Jack
SSMA (OSSM) - The SSMA is a microminiature version of the SMA. It is also 50 Ω and operates to 26.5 GHz with flexible cable or 40 GHz with semi-rigid cable.	 SSMA jack - BNC jack

SMC (OSMC) - The SMC (Sub-Miniature C) is a 50 Ω or 75 Ω connector that is smaller than the SMA. The connector can accept flexible cables with diameters of up to 3.17 mm (0.125 in.) for a frequency range of up to 7-10 GHz.	 SMC Plug - SMA Jack (Some call this a SMC Jack, even though it has a female connector)
SMB (OSMB) - The SMB is like the SMC except it uses quick disconnect instead of threaded fittings. It is a 50 / 75 Ω connector which operates to 4 GHz with a low reflection coefficient and is useable to 10 GHz.	 SMB Plug (above) SMB Jack
TNC (OST) - The TNC (Threaded Neill-Concelman or threaded Navy Connector) is merely a threaded BNC. The function of the thread is to stop radiation at higher frequencies, so that the connector can work at frequencies up to 12 GHz (to 18 GHz when using semi-rigid cable). It can be 50 or 75 Ω. For size comparison here is a SMA plug - TNC plug 	 TNC Plug (above) TNC Jack

Type N (OSN) - The 50 or 75 Ω Type N (Navy) connector was originally designed for military systems during World War II and is the most popular measurement connector for the frequency range of 1 to 11 GHz. The precision 50 Ω APC-N and other manufacturers high frequency versions operate to 18 GHz.

For size comparison here is a picture of Type N plug - TNC jack



N Plug (above)

N Jack

Note: Always rotate the movable coupling nut of the plug, not the cable or fixed connector, when mating connectors. Since the center pin is stationary with respect to the jack, rotating the jack puts torque on the center pin. With TNC and smaller connectors, the center pin will eventually break off.

An approximate size comparison of these connectors is depicted below (not to scale).

Large	======================	Medium	==========================	Small
SC 7mm N		TNC/BNC	3.5mm SMA 2.4mm SSMA	SMC

Figure 1 shows the frequency range of several connectors.



Note: Just because connectors can be connected together, doesn't mean they will work properly with respect to power handling and frequency.

Figure 1. Frequency Range of Microwave Connectors.

POWER DIVIDERS AND DIRECTIONAL COUPLERS



Figure 1. Directional Coupler.

A directional coupler is a passive device which couples part of the transmission power by a known amount out through another port, often by using two transmission lines set close enough together such that energy passing through one is coupled to the other. As shown in Figure 1, the device has four ports: input, transmitted, coupled, and isolated. The term "main line" refers to the section between ports 1 and 2. On some directional couplers, the main line is designed for high power operation (large connectors), while the coupled port may use a small SMA connector. Often the isolated port is terminated with an internal or external matched load (typically 50 ohms). It should be pointed out that since the directional coupler is a linear device, the notations on Figure 1 are arbitrary. Any port can be the input, (as in Figure 3) which will result in the directly connected port being the transmitted port, adjacent port being the coupled port, and the diagonal port being the isolated port.

Physical considerations such as internal load on the isolated port will limit port operation. The coupled output from the directional coupler can be used to obtain the information (i.e., frequency and power level) on the signal without interrupting the main power flow in the system (except for a power reduction - see Figure 2). When the power coupled out to port three is half the input power (i.e., 3 dB below the input power level), the power on the main transmission line is also 3 dB below the input power and equals the coupled power. Such a coupler is referred to as a 90 degree hybrid, hybrid, or 3 dB coupler. The frequency range for coaxial couplers specified by manufacturers is that of the coupling arm. The main arm response is much wider (i.e., if the spec is 2-4 GHz, the main arm could operate at 1 or 5 GHz - see Figure 3). However it should be recognized that the coupled response is periodic with frequency. For example, a λ/4 coupled line coupler will have responses at nλ/4 where n is an odd integer.

Common properties desired for all directional couplers are wide operational bandwidth, high directivity, and a good impedance match at all ports when the other ports are terminated in matched loads. These performance characteristics of hybrid or non-hybrid directional couplers are self-explanatory. Some other general characteristics will be discussed below.

COUPLING FACTOR

The coupling factor is defined as: $\mathit{Coupling\ factor\ (dB)} = -10 \log \frac{P_3}{P_1}$

where P_1 is the input power at port 1 and P3 is the output power from the coupled port (see Figure 1).

The coupling factor represents the primary property of a directional coupler. Coupling is not constant, but varies with frequency. While different designs may reduce the variance, a perfectly flat coupler theoretically cannot be built. Directional couplers are specified in terms of the coupling accuracy at the frequency band center. For example, a 10 dB coupling ± 0.5 dB means that the directional coupler can have 9.5 dB to 10.5 dB coupling at the frequency band center. The accuracy is due to dimensional tolerances that can be held for the spacing of the two coupled lines. Another coupling specification is frequency sensitivity. A larger frequency sensitivity will allow a larger frequency band of operation. Multiple quarter-wavelength coupling sections are used to obtain wide frequency bandwidth directional couplers. Typically this type of directional coupler is designed to a frequency bandwidth ratio and a maximum coupling ripple within the frequency band. For example a typical 2:1 frequency bandwidth coupler design that produces a 10 dB coupling with a ±0.1 dB ripple would, using the previous accuracy specification, be said to have 9.6 ± 0.1 dB to 10.4 ± 0.1 dB of coupling across the frequency range.

LOSS

In an ideal directional coupler, the main line loss port 1 to port 2 (P_1 - P_2) due to power coupled to the coupled output port is:

$$Insertion\ loss\ (dB) = 10 \log \left[1 - \frac{P_3}{P_1} \right]$$

The actual directional coupler loss will be a combination of coupling loss, dielectric loss, conductor loss, and VSWR loss. Depending on the frequency range, coupling loss becomes less significant above 15 dB coupling where the other losses constitute the majority of the total loss. A graph of the theoretical insertion loss (dB) vs. coupling (dB) for a dissipationless coupler is shown in Figure 2.



Coupling dB	Insertion Loss - dB
3	3.00
6	1.25
10	0.458
20	0.0436
30	0.00435

Figure 2. Coupling Insertion Loss.

ISOLATION

Isolation of a directional coupler can be defined as the difference in signal levels in dB between the input port and the isolated port when the two output ports are terminated by matched loads, or:

$$Isolation\ (dB) = -10 \log \frac{P_4}{P_1}$$

Isolation can also be defined between the two output ports. In this case, one of the output ports is used as the input; the other is considered the output port while the other two ports (input and isolated) are terminated by matched loads.

Consequently: $Isolation\ (dB) = -10 \log \frac{P_3}{P_2}$

The isolation between the input and the isolated ports may be different from the isolation between the two output ports. For example, the isolation between ports 1 and 4 can be 30 dB while the isolation between ports 2 and 3 can be a different value such as 25 dB. If both isolation measurements are not available, they can assumed to be equal. If neither are available, an estimate of the isolation is the coupling plus return loss (see VSWR section). The isolation should be as high as possible. In actual couplers the isolated port is never completely isolated. Some RF power will always be present. Waveguide directional couplers will have the best isolation.



Figure 3. Two-Tone Receiver Tests.

If isolation is high, directional couplers are excellent for combining signals to feed a single line to a receiver for two-tone receiver tests. In Figure 3, one signal enters port P_3 and one enters port P_2, while both exit port P_1. The signal from port P_3 to port P_1 will experience 10 dB of loss, and the signal from port P_2 to port P_1 will have 0.5 dB loss. The internal load on the isolated port will dissipate the signal losses from port P_3 and port P_2. If the isolators in Figure 3 are neglected, the isolation measurement (port P_2 to port P_3) determines the amount of power from the signal generator F_2 that will be injected into the signal generator F_1. As the injection level increases, it may cause modulation of signal generator F_1, or even injection phase locking. Because of the symmetry of the directional coupler, the reverse injection will happen with the same possible modulation problems of signal generator F_2 by F_1. Therefore the isolators are used in Figure 3 to effectively increase the isolation (or directivity) of the directional coupler. Consequently the injection loss will be the isolation of the directional coupler plus the reverse isolation of the isolator.

DIRECTIVITY

Directivity is directly related to Isolation. It is defined as:

$$Directivity\ (dB) = -10 \log \frac{P_4}{P_3} = -10 \log \frac{P_4}{P_1} + 10 \log \frac{P_3}{P_1}$$

where: P_3 is the output power from the coupled port and P_4 is the power output from the isolated port.

The directivity should be as high as possible. Waveguide directional couplers will have the best directivity. Directivity is not directly measurable, and is calculated from the isolation and coupling measurements as:

Directivity (dB) = Isolation (dB) - Coupling (dB)

HYBRIDS

The hybrid coupler, or 3 dB directional coupler, in which the two outputs are of equal amplitude takes many forms. Not too long ago the quadrature (90 degree) 3 dB coupler with outputs 90 degrees out of phase was what came to mind when a hybrid coupler was mentioned. Now any matched 4-port with isolated arms and equal power division is called a hybrid or hybrid coupler. Today the characterizing feature is the phase difference of the outputs. If 90 degrees, it is a 90 degree hybrid. If 180 degrees, it is a 180 degree hybrid. Even the Wilkinson power divider which has 0 degrees phase difference is actually a hybrid although the fourth arm is normally imbedded.

Applications of the hybrid include monopulse comparators, mixers, power combiners, dividers, modulators, and phased array radar antenna systems.

AMPLITUDE BALANCE

This terminology defines the power difference in dB between the two output ports of a 3 dB hybrid. In an ideal hybrid circuit, the difference should be 0 dB. However, in a practical device the amplitude balance is frequency dependent and departs from the ideal 0 dB difference.

PHASE BALANCE

The phase difference between the two output ports of a hybrid coupler should be 0, 90, or 180 degrees depending on the type used. However, like amplitude balance, the phase difference is sensitive to the input frequency and typically will vary a few degrees.

The phase properties of a 90 degree hybrid coupler can be used to great advantage in microwave circuits. For example in a balanced microwave amplifier the two input stages are fed through a hybrid coupler. The FET device normally has a very poor match and reflects much of the incident energy. However, since the devices are essentially identical the reflection coefficients from each device are equal. The reflected voltage from the FETs are in phase at the isolated port and are 180° different at the input port. Therefore, all of the reflected power from the FETs goes to the load at the isolated port and no power goes to the input port. This results in a good input match (low VSWR).

If phase matched lines are used for an antenna input to a 180° hybrid coupler as shown in Figure 4, a null will occur directly between the antennas. If you want to receive a signal in that position, you would have to either change the hybrid type or line length. If you want to reject a signal from a given direction, or create the difference pattern for a monopulse radar, this is a good approach.



Figure 4. Balanced Antenna Input.

OTHER POWER DIVIDERS



Figure 5. Power Divider.

Both in-phase (Wilkinson) and quadrature (90°) hybrid couplers may be used for coherent power divider applications. The Wilkinson's power divider has low VSWR at all ports and high isolation between output ports. The input and output impedances at each port is designed to be equal to the characteristic impedance of the microwave system. A typical power divider is shown in Figure 5. Ideally, input power would be divided equally between the output ports. Dividers are made up of multiple couplers, and like couplers, may be reversed and used as multiplexers. The drawback is that for a four channel multiplexer, the output consists of only 1/4 the power from each, and is relatively inefficient. Lossless multiplexing can only be done with filter networks.

Coherent power division was first accomplished by means of simple Tee junctions. At microwave frequencies, waveguide tees have two possible forms - the H-Plane or the E-Plane. These two junctions split power equally, but because of the different field configurations at the junction, the electric fields at the output arms are in-phase for the H-Plane tee and are anti-phase for the E-Plane tee. The combination of these two tees to form a hybrid tee allowed the realization of a four-port component which could perform the vector sum (Σ) and difference (Δ) of two coherent microwave signals. This device is known as the magic tee.

POWER COMBINERS

Since hybrid circuits are bi-directional, they can be used to split up a signal to feed multiple low power amplifiers, then recombine to feed a single antenna with high power as shown in Figure 6. This approach allows the use of numerous less expensive and lower power amplifiers in the circuitry instead of a single high power TWT. Yet another approach is to have each solid state amplifier (SSA) feed an antenna and let the power be combined in space or be used to feed a lens which is attached to an antenna. (See Section 3-4.)


TYPICAL HYBRID SIGNAL ADDITION
+40 dB SOLID STATE AMPLIFIERS (SSAs)
(Voltage Gain of 100)
90°
180°
Output 90°, 270° Signals Cancel
Output 180°, 180° Signals Add
SIGNAL INPUT
IN
0°- 3dB
90°- 3dB
0°- 6dB
90°- 6dB
90°- 6dB
180°- 6dB
0°- 9dB
90°- 9dB
90°- 9dB
180°- 9dB
90°- 9dB
180°- 9dB
180°- 9dB
270°- 9dB
0°+31dB
90°+31dB
90°+31dB
180°+31dB
90°+31dB
180°+31dB
180°+31dB
270°+31dB
90°+34dB
180°+34dB
180°+34dB
270°+34dB
180°+37dB
270°+37dB
270°+40dB
ANTENNA OUTPUT

NOTE: All isolated ports of the hybrids have matched terminations. They have signals which are out of phase and cancel

Figure 6. Combiner Network.

Sample Problem:

If two 1 watt peak unmodulated RF carrier signals at 10 GHz are received, how much peak power could one measure?

A. 0 watts

B. 0.5 watts

C. 1 watt

D. 2 watts

E. All of these

The answer is all of these as shown in Figure 7.



The phase error could be due to a hybrid being used to combine the same signal received from two aircraft antennas.

Signal A
Signal B
Signal A + B

If 180° out of phase, signals cancel and there is zero watts received

If in phase, the signals add, so there would be 2 watts received

Any other phase relationship will produce a signal somewhere between 0 and 2 watts. This shows signals that are 90° out of phase.

Figure 7. Sine Waves Combined Using Various Phase Relationships.

ATTENUATORS / FILTERS / DC BLOCKS

ATTENUATORS

An attenuator is a passive microwave component which, when inserted in the signal path of a system, reduces the signal by a specified amount. They normally possess a low VSWR which makes them ideal for reducing load VSWR in order to reduce measurement uncertainties. They are sometimes used simply to absorb power, either to reduce it to a measurable level, or in the case of receivers to establish an exact level to prevent overload of following stages.

Attenuators are classified as either fixed or variable and either reflective or non-reflective. The fixed and variable attenuators are available in both waveguide and coaxial systems. Most of the receivers under 20 GHz use coaxial type attenuators.

FIXED

The performance characteristics of a fixed attenuator are:

1. input and output impedances
2. flatness with frequency
3. average and peak power handling capability
4. temperature dependence

VARIABLE

The variable attenuator can be subdivided into two kinds: step attenuator and continuously variable attenuator. In a step attenuator, the attenuation is changed in steps such as 10 dB, 1 dB or 0.5 dB. In a continuously variable attenuator, the attenuation is changed continuously and a dial is usually available to read the attenuation either directly or indirectly from a calibration chart.

For a variable attenuator, additional characteristics should be considered, such as:

1. amount or range of attenuations
2. insertion loss in the minimum attenuation position
3. incremental attenuation for step attenuator
4. accuracy of attenuation versus attenuator setting
5. attenuator switching speed and switching noise.

REFLECTIVE

A reflective attenuator reflects some portion of the input power back to the driving source. The amount reflected is a function of the attenuation level. When PIN diodes are zero or reverse biased, they appear as open circuits when shunting a transmission line. This permits most of the RF input power to travel to the RF output. When they are forward biased, they absorb some input, but simultaneously reflect some back to the input port. At high bias current, most RF will be reflected back to the input resulting in a high input VSWR and high attenuation.

ABSORPTIVE

The VSWR of a non-reflective (absorptive) PIN diode attenuator remains good at any attenuation level (bias state). This is accomplished by configuring the diodes in the form of a Pi network that remains matched for any bias state or by use of a 90° hybrid coupler to cancel the waves reflected to the input connector.

MICROWAVE FILTERS

INTRODUCTION

Microwave filters are one of the most important components in receivers. The main functions of the filters are: (1) to reject undesirable signals outside the filter pass band and (2) to separate or combine signals according to their frequency. A good example for the latter application is the channelized receiver in which banks of filters are used to separate input signals. Sometimes filters are also used for impedance matching. Filters are almost always used before and after a mixer to reduce spurious signals due to image frequencies, local oscillator feedthrough, and out-of-frequency band noise and signals. There are many books which are devoted to filter designs. There are many kinds of filters used in microwave receivers, so it is impossible to cover all of them.

If a filter is needed on the output of a jammer, it is desirable to place it approximately half way between the jammer and antenna vs. adjacent to either. The transmission line attenuation improves the VSWR of the filter at the transmitter. This may allow use of a less expensive filter, or use of a reflective filter vs. an absorptive filter.

A filter is a two-port network which will pass and reject signals according to their frequencies. There are four kinds of filters according to their frequency selectivities. In the examples that follow, f_L = low frequency, f_M = medium frequency, and f_H = high frequency. Their names reflect their characteristics, and they are:

1. A low-pass filter which passes the low frequency signals below a predetermined value as shown in Figure 1.



Figure 1. Low-Pass Filter.

2. A high-pass filter which passes the high frequency signals above a predetermined value as in Figure 2.


Input Strength
0 dB
Attenuation
- dB
f_L f_M f_H
f_L f_M f_H
Frequency
Output Strength
f_L f_M f_H

Figure 2. High-Pass Filter.

3. A band-pass filter which passes signals between two predetermined frequencies as shown in Figure 3.


Input Strength
0 dB
Attenuation
- dB
f_L f_M f_H
f_L f_M f_H
Frequency
Output Strength
f_L f_M f_H

Figure 3. Band-Pass Filter.

A band-pass filter with different skirt slopes on the two sides of the pass band is sometimes referred to as an asymmetrical filter. In this filter the sharpness of the rejection band attenuation is significantly different above and below the center frequency. One additional note regarding band-pass filters or filters in general, their performance should always be checked in the out-of-band regions to determine whether or not they possess spurious responses. In particular they should be checked at harmonics of the operating frequency.

4. A band reject filter (sometimes referred to as a bandstop or notch filter) which rejects signals between two predetermined frequencies such as high power signals from the aircraft's own radar as shown in Figure 4.



Figure 4. Band-Reject Filter.

In general, filters at microwave frequencies are composed of resonate transmission lines or waveguide cavities that, when combined, reflect the signal power outside the filter frequency pass band and provide a good VSWR and low loss within the frequency pass band. As such, specifications for filters are maximum frequency, pass band loss, VSWR, and rejection level at a frequency outside of the pass band. The trade-offs for filters are a higher rejection for a fixed frequency pass band or a larger frequency pass band for a fixed rejection, which requires a filter with more resonators, which produce higher loss, more complexity, and larger size.

DC BLOCKS

DC Blocks are special connectors which have a capacitor (high pass filter) built into the device. There are three basic types:



Figure 5. Inside DC Block.

1. INSIDE - The high pass filter is in series with the center conductor as shown in Figure 5. DC is blocked on the center conductor.
2. OUTSIDE - The high pass filter is in series with the cable shield as shown in Figure 6.
3. INSIDE/OUTSIDE - A high pass arrangement is connected to both the inner and outer conductors.

DC Blocks are ideal for filtering DC, 60 Hz, and 400 Hz from the RF line.

In general, capacitors with a large value of capacitance do not have the least loss at microwave frequencies. Also, since capacitance is proportional to size, a large size produces more capacitance with more inductance. Because of these reasons, D.C. blocks are typically available with a high pass frequency band starting in the region of 0.1 to 1 GHz.



Figure 6. Outside DC Block.

TERMINATIONS / DUMMY LOADS

A termination is a one-port device with an impedance that matches the characteristic impedance of a given transmission line. It is attached to a certain terminal or port of a device to absorb the power transmitted to that terminal or to establish a reference impedance at that terminal. Important parameters of a termination are its VSWR and power handling capacity. In a receiver, terminations are usually placed at various unconnected ports of components such as hybrid and power dividers to keep the VSWR of the signal path low. It is extremely important that the isolated port in a directional coupler and the unused port of a power divider (i.e., only three ports of a four-way power divider are used) be properly terminated. All of the design considerations of directional couplers and power dividers are based on the fact that all ports are terminated with matched loads. If an unused port is not properly terminated, then the isolation between the output ports will be reduced which may severely degrade the performance of the receiver.

A termination is the terminology used to refer to a low power, single terminal device intended to terminate a transmission line. Similar devices designed to accommodate high power are generally termed dummy loads.

TERMINATIONS

Terminations are employed to terminate unconnected ports on devices when measurements are being performed. They are useful as dummy antennas and as terminal loads for impedance measurements of transmission devices such as filters and attenuators.

The resistive elements in most terminations are especially fabricated for use at microwave frequencies. Two types are commonly employed: (1) resistive film elements, and (2) molded resistive tapers. The resistive film is very thin compared to the skin depth and normally very short relative to wavelength at the highest operating frequency. The molded taper consists of a dissipative material evenly dispersed in a properly cured dielectric medium. Both forms of resistive elements provide compact, rugged terminations suitable for the most severe environmental conditions with laboratory stability and accuracy.

Terminations should be properly matched to the characteristic impedance of a transmission line. The termination characteristics of primary concern are:

a. operating frequency range
b. average power handling capability
c. operating temperature range
d. VSWR
e. size
f. weight

Many microwave systems employ directional couplers which require terminations on at least one port, and most have various modes of operation or test where terminations are needed on certain terminals.

A matched termination of a generalized transmission line is ideally represented by an infinite length of that line having small, but non-zero loss per unit length so that all incident energy is absorbed and none is reflected.

Standard mismatches are useful as standards of reflection in calibrating reflectometer setups and other impedance measuring equipment. They are also used during testing to simulate specific mismatches which would be encountered on the terminals of components once the component is installed in the actual system.

The following table shows common mismatches with the impedance that can provide the mismatch.

Common Mismatches ($Z_O = 50\ \Omega$)		
Ratio	Z_L (higher)	Z_L (lower)
1.0 : 1	50 Ω (matched)	50 Ω (matched)
1.25 : 1	62.5 Ω	40 Ω
1.50 : 1	75 Ω	33.3 Ω
2.00 : 1	100 Ω	25 Ω

DUMMY LOADS

A dummy load is a high power one port device intended to terminate a transmission line. They are primarily employed to test high power microwave systems at full power capacity. Low power coaxial loads are generally termed terminations and typically handle one watt or less.

Most radars or communications systems have a dummy load integrated into them to provide a non-radiating or EMCON mode of operation, or for testing (maintenance).

Three types of dissipative material are frequently employed in dummy loads: (1) lossy plastic, (2) refractory, and (3) water.

The lossy plastic consists of particles of lossy material suspended in plastic medium. This material may be designed to provide various attenuations per unit length but is limited as to operating temperature. It is employed primarily for low power applications.

The refractory material is a rugged substance that may be operated at temperatures up to 1600°F. It is virtually incapable of being machined by ordinary means but is often fabricated through diamond wheel grinding processes. Otherwise material must be fired in finished form. Such material is employed in most high power applications.

The dissipative properties of water are also employed for dummy load applications. Energy from the guide is coupled through a leaky wall to the water which flows alongside the main guide. Water loads are employed for extremely high power and calorimetric applications.

While dummy loads can operate over full waveguide bands, generally a more economical unit can be manufactured for use over narrower frequency ranges.

The power rating of a dummy load is a complex function dependent upon many parameters, including average and peak power, guide pressure, external temperature, guide size, air flow, and availability of auxiliary coolant. The average and peak powers are interrelated in that the peak power capacity is a function of the operating temperature which in turn is a function of the average power.

CIRCULATORS AND DIPLEXERS

A microwave circulator is a nonreciprocal ferrite device which contains three or more ports. The input from port n will come out at port n + 1 but not out at any other port. A three-port ferrite junction circulator, usually called the Y-junction circulator, is most commonly used. They are available in either rectangular waveguide or strip- line forms. The signal flow in the three-port circulator is assumed as 1→2, 2→3, and 3→1 as shown in Figure 1.



Figure 1. Symbolic Expression for a Y-Junction Circulator.

If port 1 is the input, then the signal will come out of port 2; in an ideal situation, no signal should come out of port 3 which is called the isolated port. The insertion loss of the circulator is the loss from 1 to 2, while the loss from 1 to 3 is referred to as isolation. A typical circulator will have a few tenths of a dB insertion loss from port 1 to 2 and 20 dB of isolation from port 1 to 3 for coaxial circulators (30 dB or more for waveguide circulators). When the input is port 2, the signal will come out of port 3 and port 1 is the isolated port. Similar discussions can be applied to port 3.

> Since circulators contain magnets, they should not be mounted near ferrous metals since the close proximity of metals like iron can change the frequency response.

As shown in Figure 2, if one port of a circulator is loaded, it becomes an isolator, i.e., power will pass from ports one to two, but power reflected back from port two will go to the load at port three versus going back to port one.



Figure 2. Isolator From A Circulator.

As shown in Figure 3 this circulator is made into a diplexer by adding a high pass filter to port two. Frequencies from port one that are below 10 GHz will be reflected by port two. Frequencies above 10 GHz will pass through port two. At the 10 GHz crossover frequency of the diplexer, a 10 GHz signal will be passed to both ports two and three but will be half power at each port. Diplexers or triplexers (one input and three output bands), must be specifically designed for the application.



Figure 3. Diplexer From A Circulator.

Another useful device is the 4-port Faraday Rotator Circulator shown symbolically in Figure 4. These waveguide devices handle very high power and provide excellent isolation properties. It is useful when measurements must be made during high power application as shown. A water load is used to absorb the high power reflections so that a reasonable power level is reflected to the receiver or measurement port.


ANTENNA
VSWR 2:1
9 kW
1 kW *
CW
POWER
INPUT
SOURCE
10 kW
1 kW
Water
Load
0.9 kW
100 W *
**
10 W *
100 W
40 dB attenuator
Receiver/Measurment Device (9 mW)

* All loads and the antenna have a 2:1 VSWR

Reflected power down 10 dB

Reflected power now down 20 dB from power input

** If reverse leakage is not attenuated by at least 20 dB, this leakage path dominates at the measurement port. Normally, a coaxial circulator will have at least 20 dB of reverse attenuation and a waveguide circulator will have at least 30 dB of reverse attenuation.

Figure 4. Faraday Rotator Circulator.

The Maximum Input Power to a Measurement Device - The ideal input to a measurement device is in the 0 to 10 dBm (1 to 10 mW) range. Check manufacturer's specification for specific maximum value.

If the RF transmission lines and their components (antenna, hybrid, etc.) can support the wider frequency range, circulators could be used to increase the number of interconnecting RF ports from two as shown in Figure 5, to four as shown in Figure 6. Figure 7 shows an alternate configuration using diplexers which could actually be made from circulators as shown previously in Figure 3.


AFT
FWD
Hybrid
Low
Rx
Low
Tx

Figure 5. Low Band Configuration.


AFT
FWD
Hybrid
* High
power
device
*
*
Low
Rx
Low
Tx
High
Rx
High
Tx

Figure 6. Low/High Band Configuration.


AFT
FWD
Hybrid
Low
power
device
High
power
device
L
H
L
H
Low
Rx
High
Rx
Low
Tx
High
Tx

Figure 7. Alternate Low/High Band Configuration.

MIXERS AND FREQUENCY DISCRIMINATORS

Mixers are used to convert a signal from one frequency to another. This is done by combining the original RF signal with a local oscillator (LO) signal in a non-linear device such as a Schottky-barrier diode.

The output spectrum includes:

- The original inputs, LO and RF
- All higher order harmonics of LO and RF
- The two primary sidebands, LO ± RF (m,n = 1)
- All higher order products of mLO ± nRF (where m,n are integers)
- A DC output level

The desired output frequency, commonly called the intermediate frequency (IF), can be either the lower (LO-RF) or upper (LO+RF) sideband. When a mixer is used as a down converter, the lower sideband is the sideband of interest.

A microwave balanced mixer makes use of the 3 dB hybrid to divide and recombine the RF and LO inputs to two mixing diodes. The 3 dB hybrid can be either the 90° or 180° type. Each has certain advantages which will be covered later. The critical requirement is that the LO and RF signals be distributed uniformly (balanced) to each mixer diode.

Figure 1 is a typical balanced mixer block diagram. The mixer diodes are reversed relative to each other; the desired frequency (IF) components of each diode are then in-phase while the DC outputs are positive and negative respectively.

The two diode outputs are summed in a tee where the DC terms cancel and only the desired IF component exists at the IF port.



Figure 1. Mixer Block Diagram.

Other types of mixers exist, including the double-balanced mixer, and the Ortho-Quad® (quadrature fed dual) mixer. The relative advantages and disadvantages of each of the four types are summarized in Table 1.

Table 1. Mixer Comparison.

Mixer Type	VSWR [1]	Conversion Loss [2]	LO/RF Isolation [3]	Harmonic Suppression [4]	Dynamic Range	IF Bandwidth
90° Hybrid	good	lowest	poor	poor-fair	high	wide
180° Hybrid	poor	low	good	good	high	wide
Double-Balanced	poor	low	Very good -excellent	very good	high	extremely wide
Ortho Quad	good	low	very good	fair	high	wide

NOTES:
(1) Poor = 2.5:1 typical; Good = 1.3:1 typical
(2) Conversion loss: lowest: 5-7 dB typical; Low 7-9 dB typical
(3) Poor: 10 dB typical; Good: 20 dB typical; Very Good: 25-30 dB typical; Excellent: 35-40 dB typical
(4) Poor: partial rejection of LO/RF even harmonics
Fair: slightly better
Good: can reject all LO even harmonics
Very Good: can reject all LO and RF even harmonics

Used in various circuits, mixers can act as modulators, phase detectors, and frequency discriminators.

The phase discriminators can serve as a signal processing network for systems designed to monitor bearing, polarization, and frequency of AM or FM radiated signals.

A frequency discriminator uses a phase discriminator and adds a power divider and delay line at the RF input as shown in Figure 2. The unknown RF signal "A" is divided between a reference and delay path. The differential delay (T) creates a phase difference (θ) between the two signals which is a linear function of frequency (f) and is given by θ = 2πfT.



Figure 2. Frequency Discriminator.

When the two output signals are fed to the horizontal and vertical input of an oscilloscope, the resultant display angle will be a direct function of frequency.

DETECTORS

A detector is used in receiver circuits to recognize the presence of signals. Typically a diode or similar device is used as a detector. Since this type of detector is unable to distinguish frequency, they may be preceded by a narrow band-pass filter.

A typical simplistic circuit is shown in Figure 1.



Figure 1. Typical Diode Detector Circuit.



Figure 2. Demodulated Envelope Output.

To integrate a pulse radar signal, we can add capacitance to the circuit in parallel with the output load R_L to store energy and decrease the bleed rate. Figure 2 shows a typical input/output waveform which detects the envelope of the pulse radar signal. From this information pulse width and PRF characteristics can be determined for the RWR UDF comparison.

When the diode is reverse biased, very little current passes through unless the reverse breakdown voltage is exceeded. When forward biased and after exceeding the cut-in voltage, the diode begins to conduct as shown in Figure 3. At low voltages, it first operates in a square law region. Detectors operating in this region are known as small signal type. If the voltage is higher, the detector operates in a linear region, and is known as the large signal type.



Figure 3. Diode Electrical Characteristics.

The power/voltage characteristics for a typical diode detector is shown in Figure 4.



Figure 4. Diode Power/Voltage Characteristic.

Square Law Detector

In the square law region, the output voltage V_o is proportional to the square of the input voltage V_i, thus V_o is proportional to the input power.

$V_o = nV_i^2 = nP_i$ or $P_i \propto V_o$
Where n is the constant of proportionality

Linear Detector

In the linear detection region, the output voltage is given by:

$V_o = mV_i$ and since $P=V^2/R$, $P_i \propto V_o^2$
Where m is the constant of proportionality

Log Detector Amplifier

Another type of detector arrangement is the Log detector amplifier circuit shown in Figure 5. It is formed by using a series of amplifiers and diode detectors. Due to the nature of the amplifier/diode characteristics, the output voltage is related to the power by:

$P_i \propto 10^{pV_o + q}$
Where p and q are constants of proportionality



Figure 5. Log Detector.

The Log detector has good range, but is hampered by large size when compared to a single diode detector.

Pulse Width Measurements

If the pulse width of a signal was specified at the one-half power point, the measurements of the detected signal on an oscilloscope would vary according to the region of diode operation. If the region of operation is unknown, a 3 dB attenuator should be inserted in the measurement line. This will cause the power to decrease by one-half. The (temporary) peak amplitude on the oscilloscope becomes the amplitude reference point for measuring the pulse width when the external 3 dB attenuator is removed.

These voltage levels for half power using the three types of detectors are shown in Table 1.

Table 1. Detector Characteristics.

	Square Law	Linear	Log
Output Voltage When Input Power is reduced by Half (3 dB)	0.5 V_{in}	0.707 V_{in}	A very small value. ~ 0.15 V_{in} for typical 5 stage log amplifier
Sensitivity & Dynamic Range	Good sensitivity Small dynamic range	Less sensitivity Greater dynamic range	Poorest sensitivity Greatest dynamic range (to 80 dB)

Also see the Microwave Measurements section subsection entitled "Half Power or 3 dB Measurement Point."

This page intentionally left blank.

RF / MICROWAVE AMPLIFIERS

An amplifier is one of the most essential and ubiquitous elements in modern RF and microwave systems. Fundamentally, an amplifier is a type of electronic circuit used to convert low-power signals into ones of significant power. The specific requirements for amplification are as varied as the systems where they are used. Amplifiers are realized using a wide range of different technologies, and are available in many form factors. While the performance of an amplifier can be measured by wide range of attributes, several important ones include: gain, power added efficiency (PAE), input and output return loss, 1-dB compression point (P_{1dB}), stability, linearity, intermodulation distortion, and noise figure.

Traveling Wave Tubes (TWTs)

A traveling-wave tube (TWT) is a specialized vacuum tube used in electronics to amplify radio frequency (RF) signals to very high power. A TWT is a component of an electronic assembly known as a traveling-wave tube amplifier (TWTA), often pronounced "Tweet-uh." While trades between these parameters exist, modern TWTAs are capable of providing very high gains (>50 dB), multiple octaves of bandwidth, high efficiency, and output powers that range from tens to thousands of watts. Pulsed TWTAs can reach even higher output powers. Figure 1 presents a simplified diagram of a helix-type TWT.



Figure 1. Cutaway view of a helix TWT.
(1) Electron gun; (2) RF input; (3) Magnets; (4) Attenuator;
(5) Helix coil; (6) RF output; (7) Vacuum tube; (8) Collector.
Reproduced from Wikipedia.

The device is an elongated vacuum tube with an electron gun (a heated cathode that emits electrons) at one end. A solenoid coil wrapped around the tube creates a magnetic field which focuses the electrons into a beam, which then passes down the middle of a wire helix that stretches the length of the tube, finally striking a collector at the other end. An input signal is coupled into the helix near the emitter, is amplified by the electron beam as it travels down the length of the tube, and the amplified signal is coupled to an external port near the collector.

The helix, which acts as a RF transmission line, delays the signal to near the same propagation speed as the electron beam. The speed at which the electromagnetic wave travels down the tube can be varied by changing the number or diameter of the turns in the helix. While propagating along the tube, the EM wave interacts with the electron beam. Since the electromagnetic wave effectively propagates slower than the electron beam, the electrons “bunch up” and modulate the input signal, giving up energy in the process - an effect known as velocity modulation. Thus, the traveling wave progressively grows in amplitude as it propagates down the tube towards the collector.

Figure 2 features a photo of a high voltage power supply and TWT.



Figure 2. TWTA Including High Voltage Power Supply (top) and TWT (bottom).

Historically, TWTAs have been used in satellite transponders, radars, and in electronic warfare and self-protection systems. Recently, with the advent of wideband, high power solid-state amplifier solutions, however, TWTAs are slowly being replaced due to the higher reliability of their solid state counterparts.

Microwave Power Modules (MPMs)

A Microwave Power Module (MPM) is a hybrid solution between solid-state and vacuum tube electronics, which aims to take advantage of the best features of both technologies. They feature a solid-state pre-amplifier, miniaturized TWTA, and a high-density power supply, all integrated into a unit much more compact and lightweight than the traditional TWTA. While MPMs generally don’t provide as much power as their larger TWTA counterparts, their lighter weight, compact form factor, and relaxed power supply requirements (often 28 VDC or 270 VDC) enable use in applications where a TWTA would not be possible.

Similar to TWTAs, MPMs are capable of providing very high gains (>50 dB), multiple octaves of bandwidth, high efficiency. Typical power levels range from tens to hundreds of watts, with ~1 kW capability for pulsed MPMs.


High-Voltage Module
Low-Voltage Board
SSA
TWT
2.9-mm Input
Control
28-Vdc Input
WRD-180 Output

Figure 3. 40W Ka-band MPM With Components Identified.
Image from *IEEE Magazine*, December 2009, page 42.

They have found applications in phased array antennas, lower-power radar transmitters, satellite communications, EW systems, and UAVs.

Solid State

Solid-state electronics, including amplifiers, are built entirely from solid materials and in which the electrons, or other charge carriers, are confined entirely within the solid material. The building material is most often a crystalline semiconductor. Solid-state power amplifiers, or SSPAs, are fabricated on many different semiconductor technologies, some of which include GaAs, GaN, InP, SiGe, CMOS. A photo of a GaN SSPA is presented in Figure 4.


RFMD
RF3927
0135
RFMD
RF3927410(1)
68761-1
0822

Figure 4. Typical SSPA. Note the GaN die and external impedance matching networks.

In general, SSPAs are heralded as having a higher reliability than TWTAs. While high power SSPAs are available on the market, achieving high efficiency has been a challenge as many amplifier stages often need to be combined to meet to achieve power levels in the tens to hundreds of watts. Multi-stage designs increase size, weight, and power (SWAP) and decrease PAE (due to ohmic losses in the combining networks), which is one reason why TWTs and MPMs still provide excellent alternatives for medium to high power applications.

Below is a table that attempts to compare and contrast different solid-state technologies in the context of microwave networks and amplifiers. It is by no means complete, but provides a general overview.

Table 1. Comparison Between Different Semiconductor Process Technologies.

Technology	**Advantages**	**Disadvantages**
Silicon variants (CMOS, SiGe)	• Cheapest substrate due to CPU industry • Can be fabricated with nanometer accuracy	• Not a good overall microwave substrate • Results in lossy, high noise figure, low power components • Crystal is fragile • Junction temperatures limited to ~110C
Indium Phosphide Variants (InP/InGaP)	• High performance at low voltage • Good thermal stability • Results in high efficiency PAs, particularly at lower operating voltage • Extremely low noise figure • Useful through W-band and beyond	• Less mature, “niche” fabrication houses • Brittle, fragile material • Higher cost than GaAs • Low breakdown voltage – not good for high power
Gallium Arsenide variants (GaAs)	• Most mature, widespread technology • Many transistor variants (MESFET, PHEMT, MHEMT, HBT, etc) • High reliability • Fairly low cost (but more than silicon) • Great microwave substrate • Low loss, high ε_r. • 16-20V breakdown possible • Junction temperatures up to 150C	• High noise figure, Noise figure and power performance • Difficult to summarize - depends on transistor type used
Gallium Nitride (GaN)	• Up to 10x the power density of GaAs • High breakdown voltage (100V possible) • Results in high efficiency, high frequency, wide bandwidth PAs • Can operate hotter than GaAs, Si, or SiGe	• Currently more expensive than GaAs, but costs are decreasing • Difficult to fabricate • High power density leads to thermal challenges

SIGNAL GENERATION

Signal generators, also known variously as function generators, RF and microwave signal generators, pitch generators, arbitrary waveform generators, digital pattern generators or frequency generators are electronic devices that generate repeating or non-repeating electronic signals (in either the analog or digital domains). They are generally used in designing, testing, troubleshooting, and repairing electronic or electro-acoustic devices; though they often have artistic uses as well.

There are many different types of signal generators, with different purposes and applications (and at varying levels of expense); in general, no device is suitable for all possible applications.

Analog Signal Generators

RF signal generators are capable of producing CW (continuous wave) tones. The output frequency can usually be tuned anywhere in their frequency range. Many models offer various types of analog modulation, either as standard equipment or as an optional capability to the base unit. This could include AM, FM, ΦM (phase modulation) and pulse modulation. Another common feature is a built-in attenuator which makes it possible to vary the signal's output power. Depending on the manufacturer and model, output powers can range from -135 to +30 dBm. A wide range of output power is desirable, since different applications require different amounts of signal power. For example, if a signal has to travel through a very long cable out to an antenna, a high output signal may be needed to overcome the losses through the cable and still have sufficient power at the antenna. But when testing receiver sensitivity, a low signal level is required to see how the receiver behaves under low signal-to-noise conditions.

RF signal generators are required for servicing and setting up analog radio receivers, and are used for professional RF applications.

Arbitrary Waveform Generator

An arbitrary waveform generator (AWG) is a piece of electronic test equipment used to generate electrical waveforms. These waveforms can be either repetitive or single-shot (once only) in which case some kind of triggering source is required (internal or external). The resulting waveforms can be injected into a device under test and analyzed as they progress through the device, confirming the proper operation of the device or pinpointing a fault in the device.

Unlike function generators, AWGs can generate any arbitrarily defined wave shape as their output. The waveform is usually defined as a series of "waypoints" (specific voltage targets occurring at specific times along the waveform) and the AWG can either jump to those levels or use any of several methods to interpolate between those levels.

Because AWGs synthesize the waveforms using (baseband) digital signal processing techniques, their maximum frequency is usually limited to no more than a few gigahertz (~10 GHz being the latest state-of-the-art in 2012).

A major difficulty in generating non-repetitive waveforms at higher frequencies with AWGs is the large amount of data required to describe high-frequency baseband signals. For example, a 20 gigasample/sec arbitrary waveform with 8 bits of resolution requires 20 GB of data to represent every 1 second of signal, regardless of that signal's nature. Generating such large digital data streams and delivering them to the DAC in the AWG is an increasingly difficult problem as DAC upper frequencies continue to grow.

AWGs, like most signal generators, may also contain an attenuator, various means of modulating the output waveform, and often contain the ability to automatically and repetitively "sweep" the frequency of the output waveform (by means of a voltage-controlled oscillator) between two operator-determined limits. This capability makes it very easy to evaluate the frequency response of a given electronic circuit.

AWGs can operate as conventional function generators. These would include standard waveforms such as sine, square, ramp, triangle, noise, and pulse. Some units include additional built-in waveforms such as exponential rise and fall times, sinx/x, cardiac. Some AWGs allow users to retrieve waveforms from a number of digital and mixed-signal oscilloscopes. Some AWGs may display a graph of the waveform on their screen - a graph mode. Some AWGs have the ability to generate a pattern of words from multiple bit output connector to simulate data transmission, combining the properties of both AWGs and digital pattern generators.

One feature of direct digital synthesizer (DDS) based arbitrary waveform generators is that their digital nature allows multiple channels to be operated with precisely controlled phase offsets or ratio-related frequencies. This allows the generation of polyphase sine waves, I-Q constellations, or simulation of signals from geared mechanical systems such as jet engines. Complex channel-channel modulations are also possible.

Vector Signal Generators

Modern vector signal generators can be seen as a hybrid of the arbitrary waveform generator and the analog signal generator, combining a lower-bandwidth AWG with analog upconversion, allowing a moderate-bandwidth (~100 MHz, circa 2012) digital signal to be upconverted to any frequency (~50 GHz typically upper frequency typically).

With the advent of digital communications systems, it is no longer possible to adequately test these systems with traditional analog signal generators. This has led to the development of vector signal generators, also known as digital signal generators. These signal generators are capable of generating digitally-modulated radio signals that may use any of a large number of digital modulation formats such as QAM, QPSK, FSK, BPSK, and OFDM. In addition, since modern commercial digital communication systems are almost all based on well-defined industry standards, many vector signal generators can generate signals based on these standards. Examples include GSM, W-CDMA (UMTS), CDMA2000, LTE, Wi-Fi (IEEE 802.11), and WiMAX (IEEE 802.16). In contrast, military communication systems such as JTRS, which place a great deal of importance on robustness and information security, typically use very proprietary methods. To test these types of communication systems, users will often create their own custom waveforms and download them into the vector signal generator to create the desired test signal.

This page intentionally left blank.

DIGITAL SIGNAL PROCESSING COMPONENTS

The goal of DSP is usually to measure, filter and/or compress continuous real-world analog signals. The first step is usually to convert the signal from an analog to a digital form, by sampling and then digitizing it using an analog-to-digital converter (ADC), which turns the analog signal into a stream of numbers. However, often, the required output signal is another analog output signal, which requires a digital-to-analog converter (DAC). Even if this process is more complex than analog processing and has a discrete value range, the application of computational power to digital signal processing allows for many advantages over analog processing in many applications, such as error detection and correction in transmission as well as data compression. With the increasing bandwidth and dynamic range of ADC and digital components, common analog RF signal processing operations such as filtering, threshold detection, and pulse compression are being carried out in the digital domain. Additionally new capabilities such as synthetic aperture radar (SAR), digital RF memory (DRFM), and space-time adaptive processing (STAP) are wholly enabled by the increasing power of digital processing components.

Analog-to-Digital Converter

An analog-to-digital converter (abbreviated ADC, A/D or A to D) is a device that converts a continuous quantity to a discrete time digital representation. An ADC may also provide an isolated measurement. The reverse operation is performed by a digital-to-analog converter (DAC).

Typically, an ADC is an electronic device that converts an input analog voltage or current to a digital number proportional to the magnitude of the voltage or current. However, some non-electronic or only partially electronic devices, such as rotary encoders, can also be considered ADCs.

Resolution

The resolution of the converter indicates the number of discrete values it can produce over the range of analog values. The values are usually stored electronically in binary form, so the resolution is usually expressed in bits. In consequence, the number of discrete values available, or “levels,” is a power of two. For example, an ADC with a resolution of 8 bits can encode an analog input to one in 256 different levels, since $2^8 = 256$. The values can represent the ranges from 0 to 255 (i.e. unsigned integer) or from −128 to 127 (i.e., signed integer), depending on the application.

Resolution can also be defined electrically, and expressed in volts. The minimum change in voltage required to guarantee a change in the output code level is called the least significant bit (LSB) voltage. The resolution Q of the ADC is equal to the LSB voltage. The voltage resolution of an ADC is equal to its overall voltage measurement range divided by the number of discrete values:

$$Q = \frac{E_{FSR}}{2^M}$$

where M is the ADC’s resolution in bits and E_{FSR} is the full scale voltage range (also called ‘span’).

E_{FSR} is given by

$$E_{FSR} = V_{RefHi} - V_{RefLow}$$

where V_{RefHi} and V_{RefLow} are the upper and lower extremes, respectively, of the voltages that can be coded.

Normally, the number of voltage intervals is given by

$$N = 2^M - 1$$

where M is the ADC's resolution in bits.

That is, one voltage interval is assigned in between two consecutive code levels.

A typical 3 bit (2^8 = 8-level) coding scheme is depicted in Figure 1.



Figure 1. An 8-level (3 bit) ADC Coding Scheme.

Example:

Assume input signal x(t) = A cos(t), A = 5V
Full scale measurement range = -5 to 5 volts
ADC resolution is 8 bits: 2^8 - 1 = 256 - 1 = 255 quantization levels (codes)
ADC voltage resolution, Q = (5 V − [-5] V) / 255 = 10 V / 255 ≈ 0.039 V ≈ 39 mV.

In practice, the useful resolution of a converter is limited by the best signal-to-noise ratio (SNR) that can be achieved for a digitized signal. An ADC can resolve a signal to only a certain number of bits of resolution, called the effective number of bits (ENOB). One effective bit of resolution changes the signal-to-noise ratio of the digitized signal by 6 dB, if the resolution is limited by the ADC. If a preamplifier has been used prior to A/D conversion, the noise introduced by the amplifier can be an important contributing factor towards the overall SNR.

Accuracy

An ADC has several sources of errors. Quantization error and (assuming the ADC is intended to be linear) non-linearity are intrinsic to any analog-to-digital conversion. There is also a so-called aperture error which is due to a clock jitter and is revealed when digitizing a time-variant signal (not a constant value).

These errors are measured in a unit called the least significant bit (LSB). In the above example of an eight-bit ADC, an error of one LSB is 1/256 of the full signal range, or about 0.4%.

Sampling Rate

The analog signal is continuous in time and it is necessary to convert this to a flow of digital values. It is therefore required to define the rate at which new digital values are sampled from the analog signal. The rate of new values is called the sampling rate or sampling frequency of the converter.

A continuously varying band limited signal can be sampled (that is, the signal values at intervals of time T, the sampling time, are measured and stored) and then the original signal can be exactly reproduced from the discrete-time values by an interpolation formula. The accuracy is limited by quantization error. However, this faithful reproduction is only possible if the sampling rate is higher than twice the highest frequency of the signal. This is essentially what is embodied in the Shannon-Nyquist sampling theorem.

Oversampling

Usually, for economy, signals are sampled at the minimum rate required, with the result that the quantization noise introduced is white noise spread over the whole pass band of the converter. If a signal is sampled at a rate much higher than the Nyquist frequency and then digitally filtered to limit it to the signal bandwidth there are the following advantages:

- Digital filters can have better properties (sharper roll-off, phase) than analog filters, so a sharper anti-aliasing filter can be realized and then the signal can be down-sampled giving a better result
- A 20-bit ADC can be made to act as a 24-bit ADC with 256× oversampling
- The signal-to-noise ratio due to quantization noise will be higher than if the whole available band had been used. With this technique, it is possible to obtain an effective resolution larger than that provided by the converter alone.
- The improvement in SNR is 3 dB (equivalent to 0.5 bits) per octave of oversampling which is not sufficient for many applications. Therefore, oversampling is usually coupled with noise shaping. With noise shaping, the improvement is 6L+3 dB per octave where L is the order of loop filter used for noise shaping. e.g. - a 2nd order loop filter will provide an improvement of 15 dB/octave.

Digital to Analog Converter (DAC)

Digital-to-analog converters (DACs) perform the inverse function of the ADC. As such, the aforementioned principles of accuracy, resolution, sampling and oversampling, etc. apply equivalently.

Field-Programmable Gate Array (FPGA)

A field-programmable gate array (FPGA) is an integrated circuit designed to be configured by the customer or designer after manufacturing—hence "field-programmable." The FPGA configuration is generally specified using a hardware description language (HDL), similar to that used for an application-specific integrated circuit (ASIC). Circuit diagrams were previously used to specify the configuration, as they were for ASICs, but this is increasingly rare. FPGAs can be used to implement any logical function that an ASIC could perform. The ability to update the functionality after shipping, partial re-configuration of a portion of the design and the low non-recurring engineering costs relative to an ASIC design (notwithstanding the generally higher unit cost), offer advantages for many applications.

FPGAs contain programmable logic components called "logic blocks," and a hierarchy of reconfigurable interconnects that allow the blocks to be "wired together"—somewhat like many (changeable) logic gates that can be inter-wired in (many) different configurations. Logic blocks can be configured to perform complex combinational functions, or merely simple logic gates like AND and XOR. In most FPGAs, the logic blocks also include memory elements, which may be simple flip-flops or more complete blocks of memory.

FPGAs are becoming increasingly more popular for implementing RF signal processing functions such as signal compression (matched filtering), channel selection, modulation / demodulation, etc.

MICROWAVE MEASUREMENTS

Measurement Procedures

Calculate your estimated power losses before attempting to perform a measurement. The ideal input to a measurement device is in the 0 to 10 dBm (1 to 10 mW) range.

Linearity Check

To verify that a spectrum measurement is accurate and signals are not due to mixing inside the receiver, a linearity check should be performed, i.e., externally insert a 10 dB attenuator - if measurements are in the linear region of the receiver, all measurements will decrease by 10 dB. If the measurements decrease by less than 10 dB, the receiver is saturated. If the measurements disappear, you are at the noise floor.

Half-Power or 3 dB Measurement Point

To verify the half power point of a pulse width measurement on an oscilloscope, externally insert a 3 dB attenuator in the measurement line, and the level that the peak power decreases to is the 3 dB measurement point (Note: you cannot just divide the peak voltage by one-half on the vertical scale of the oscilloscope).

VSWR Effect on Measurement

Try to measure VSWR (or reflection coefficient) at the antenna terminals. Measuring VSWR of an antenna through its transmission line can result in errors. Transmission lines should be measured for insertion loss not VSWR.

High Power Pulsed Transmitter Measurements

When making power measurements on a high power pulsed transmitter using a typical 40 dB directional coupler, an additional attenuator may be required in the power meter takeoff line, or the power sensor may be burnt out.

For example, assume we have a 1 megawatt transmitter, with PRF = 430 pps, and PW = 13 μs. Further assume we use a 40 dB directional coupler to tap off for the power measurements. The power at the tap would be:

$10 \log(P_p) - 10 \log(DC) - \text{Coupler reduction} =$

$10 \log(10^9 \text{mW}) - 10 \log(13\text{x}10^{-6})(430) - 40 \text{ dB} =$

$90 \text{ dBm} - 22.5 \text{ dB} - 40 \text{ dB} = 27.5 \text{ dBm}$ (too high for a power meter)

Adding a 20 dB static attenuator to the power meter input would give us a value of 7.5 dBm or 5.6 mW, a good level for the power meter.

High Power Measurements With Small Devices

When testing in the presence of a high power radar, it is normally necessary to measure the actual field intensity. The technique shown in Figure 4, in Section 6-7, may not be practical if the measurement device must be small. An alternate approach is the use of a rectangular waveguide below its cutoff frequency. In this manner, the "antenna" waveguide provides sufficient attenuation to the frequency being measured so it can be coupled directly to the measurement device or further attenuated by a low power attenuator. The attenuation of the waveguide must be accurately measured since attenuation varies significantly with frequency.

ELECTRO-OPTICS AND IR

ELECTRO-OPTICS AND IR 7-1
  Introduction 7-1.1
  Optical Spectrum 7-1.1
  Radiometric Quantities and Terminology 7-1.2
  Photometric Quantities 7-1.3
  Basic Principles 7-1.4
  Basic Radiant Power Relationships 7-1.5
  Infrared Source Characteristics 7-1.10
  Atmospheric Transmission 7-1.14
  EO Components and Sensors 7-1.16
  IR Threats to Aircraft and Their Countermeasures 7-1.30
  IRCM 7-1.36
  Lasers 7-1.38
  Fiber Optics 7-1.41

Laser Safety 7-2

This page intentionally left blank.

ELECTRO-OPTICAL SYSTEMS AND EW COUNTERMEASURES

INTRODUCTION

The development of infrared countermeasures and the evaluation of their performance against threat missiles is a broad, complex technical field. Much of the detailed information about the threats to be countered and the characteristics of the countermeasures themselves is understandably sensitive, beyond the limitations of this document. More detailed information can be requested, provided the requesting organization has the necessary clearance and need to know. Such requests will be considered on a case-by-case basis. Information will be provided only upon written concurrence of the controlling Government organization.

There are many electro-optical (EO) electronic warfare (EW) systems, which are analogous to radio frequency (RF) EW systems. These EO EW systems operate in the optical portion of the electromagnetic spectrum. Electro-optics (EO), as the name implies, is a combination of electronics and optics. By one definition EO is the science and technology of the generation, modulation, detection and measurement, or display of optical radiation by electrical means. Most infrared (IR) sensors, for example, are EO systems. In the popularly used term "EO/IR," the EO is typically used to mean visible or laser systems. The use of EO in this context is a misnomer. Actually, almost all "EO/IR" systems are EO systems as defined above. Another often-used misnomer is referring to an EO spectrum. EO systems operate in the optical spectrum, which is from 0.01 to 1000 micrometers. EO systems include, but are not limited to, lasers, photometry, infrared, and other types of visible, and UV imaging systems.

Within the broad field of Electronic Warfare, electro-optical systems are prevalent for communication systems and offensive and defensive applications. Lasers have been used extensively for weapons guidance purposes, warhead fuzing applications, targeting systems and other offensive weapons related purposes. Understanding electro-optical and radiometric principles and sensors is critical to the development of vehicle survivability systems. These principles range from signature reduction and camouflage to active countermeasure systems such as lamp-based and laser jammers to passive threat warning systems and expendable flare decoys.

Although military systems operate in many portions of the electro-optical spectrum, the infrared is of paramount importance for remote detection systems and weapons applications. Missile seekers, Forward Looking Infrared (FLIR) systems, and Infrared Search and Track Systems all operate in the infrared portion of the spectrum.

OPTICAL SPECTRUM

The optical spectrum is that portion of the electromagnetic spectrum from the extreme ultraviolet (UV) through the visible to the extreme IR. Figure 1 shows the optical spectrum in detail. The end points of the optical spectrum are somewhat arbitrary.

IR spectrum terminology has also varied through the years, with near (near visible), or short-wavelength infrared (SWIR) being on the high frequency end. Then as frequency decreases the spectrum is followed by intermediate or mid-wavelength infrared (MWIR), then far or long-wavelength IR (LWIR), and finally extreme IR.


10^{16}
10^{15}
10^{14}
10^{13}
10^{12}
Frequency
υ - sec^{-1}
10^{-2}
10^{-1}
1
10
10^{2}
10^{3}
Wavelength
λ - μm
0.37
0.75
ULTRAVIOLET
VISIBLE
INFRARED
MICRO WAVES
EXTREME
FAR
MID
NEAR
NEAR
INTER-MEDIATE
FAR
EXTREME
OLDER IR BAND TERMINOLOGY
Near
Mid
Far
Long Wave
Extreme
UV A = 315 to 400 nm
UV B = 280 to 315 nm
UV C = 100 to 280 nm
0.37
VISIBLE SPECTRUM
0.75
NEAR UV
VIOLET
BLUE
GREEN
YELLOW
ORANGE
RED
NEAR IR
0.3 μm
0.4 μm
0.5 μm
0.6 μm
0.7 μm
0.8 μm

Figure 1. Optical Spectrum.

RADIOMETRIC QUANTITIES AND TERMINOLOGY

The common terms used to describe optical radiation are the source parameters of power, radiant emittance (older term) or radiant exitance (newer term), radiance, and radiant intensity. They refer to how much radiation is given off by a body. The parameter measured by the detector (or collecting object/surface) is the irradiance. Any of these quantities can be expressed per unit wavelength in which case the subscript is changed from e (meaning energy derived units) to λ and the term is then called "Spectral ...X...", i.e. I_e is radiant intensity, while I_λ is spectral radiant intensity. These quantities in terms of currently preferred "Système International d'Unités" (SI units) are defined in Table 1.

Table 1. Radiometric SI Units.

Symbol	Name	Description	Units
Q	Radiant Energy		J (joules)
Φ_e	Radiant Power (or flux)	Rate of transfer of radiant energy	W (watts)
M_e	Radiant Exitance	Radiant power per unit area emitted from a surface	W m^{-2}
L_e	Radiance	Radiant power per unit solid angle per unit projected area	W m^{-2}sr^{-1}
I_e	Radiant Intensity	Radiant power per unit solid angle from a point source	W sr^{-1}
E_e	Irradiance	Radiant power per unit area incident upon a surface	W m^{-2}
X_λ	Spectral ...X..	(Quantity) per unit wavelength interval	(Units) nm^{-1} or **μ**m^{-1}

Where X_λ is generalized for each unit on a per wavelength basis; for example, L_λ would be called "spectral radiance" instead of radiance.

In common usage, irradiance is expressed in units of Watts per square centimeter and wavelengths are in **µ**m instead of nanometers (nm). Other radiometric definitions are shown in Table 2.

Table 2. Other Radiometric Definitions.

Symbol	Name	Description	Units
α	Absorptance[1]	α = (*) absorbed / (*) incident	numeric
ρ	Reflectance	ρ = (*) reflected / (*) incident	numeric
τ	Transmittance	τ = (*) transmitted / (*) incident	numeric
$\in$	Emissivity	$\in$ = (*) of specimen / (*) of blackbody @ same temperature	numeric

Where (*) represents the appropriate quantity Q, Φ, M, E, or L
Note (1) Radiant absorptance should not be confused with absorption coefficient.

PHOTOMETRIC QUANTITIES

Whereas the radiometric quantities Φ_e, M_e, I_e, L_e, and E_e have meaning throughout the entire electromagnetic spectrum, their photometric counterparts Φ_v, M_v, I_v, L_v, and E_v are meaningful only in the visible spectrum (0.38 **µ**m thru 0.78 **µ**m).

The "standard candle" was redefined as the new candle or candela (cd). One candela is the luminous intensity of 1/60th of 1 cm^2 of the projected area of a blackbody radiator operating at the temperature of the solidification of platinum (2045 ºK). By definition, the candela emits one lumen (lm) per steradian.

Table 3 displays the photometric quantities and units. These are used in dealing with optical systems such as aircraft television camera systems, optical trackers, or video recording.

Table 3. Photometric SI Units.

Symbol	Name	Description	Units
Q_v	Luminous energy		lumen sec (lm s)
F or Φ_v	Luminous flux or Luminous Power	Rate of transfer of luminant energy	lumen (lm)
M_v	Luminous Exitance or flux density (formerly luminous emittance)	Luminant power per unit area emitted from a surface	$lm\ m^{-2}$
L_v	Luminance (formerly brightness)	Luminous flux per unit solid angle per unit projected area	nit (nt) or candela / m^2 or $lm/sr{\cdot}m^2$
I_v	Luminous Intensity (formerly candlepower)	Luminous power per unit solid angle from a point source	candela (cd) or lm/sr
E_v	Illuminance (formerly illumination)	Luminous power per unit area incident upon a surface	lux or lx or lm/m^2
K	Luminous efficacy	$K = \Phi_v / \Phi_e$	lm / w

Table 4 displays conversion factors for commonly used illuminance quantities.

Table 4. Illuminance Conversion Units.

		Lux (lx)	Footcandle (fc)	Phot (ph)
1 lux (lm m^{-2})	=	1	0.0929	1×10^{-4}
1 footcandle (lm ft^{-2})	=	10.764	1	0.001076
1 phot (lm cm^{-2})	=	1×10^{4}	929	1

THE BASIC PRINCIPLES

The processes of absorption, reflection (including scattering), and transmission account for all incident radiation in any particular situation, and the total must add up to one in order that energy be conserved:

$\alpha + \rho + \tau = 1$, as shown in Figure 2.



Figure 2. Radiation Incident on a Body.

If a material is opaque (no transmission), then: absorption + reflection = 1

In addition to the above processes, optical (including IR) radiation interacts with matter the same as radiation in any other part of the spectrum, including:

1. **Diffraction** – around edges
2. **Emission** – from matter by conversion from another form of energy
3. **Interference** – constructive and destructive
4. **Refraction** – bends when passing between two media with different propagation speeds (Snell's Law)
5. **Scattering** – when interacts with particles whose size approaches length of the wave
6. **Polarized** - electric field is partially polarized by reflection from dielectric

STERADIAN – SOLID ANGLE

Of significance to many terms and units in radiometric calculations is the *solid angle*. Figure 3 is a pictorial depicting the relationship of area, distance, and solid angle. By definition, the ratio of area on the surface of a sphere to the square of distance (the radius) is the unit less parameter *solid angle*, or steradian in the SI system of units. Solid angle is usually abbreviated as "sr" or given the Greek letter, Ω. The steradian is a dimensionless quantity in radiometric calculations.



Figure 3. Solid Angle.

A sphere contains a solid angle of 4π steradians; a hemisphere contains 2π steradians, and so on. The area is a curved surface, but in most applications, the solid angles are sufficiently small that the area can be approximated as a plane. Also, for small angles, the solid angle in steradians is approximately equal to the product of two plane angles in radians.

CONVERSIONS

IR wavelengths are typically expressed in **μ**m, visible wavelengths in **μ**m or nm, and UV wavelengths in nm or angstroms. Table 5 lists conversion factors for converting from one unit of wavelength to another. The conversion is from column to row. For example, to convert from **μ**m to nm, multiply the value expressed in **μ**m by 10^3. IR wavelengths are also sometimes expressed in a frequency-like unit called wavenumbers or inverse centimeters. A wavenumber value can be found by dividing 10,000 by the wavelength expressed in **μ**m. For example, 2.5 **μ**m converts to a wavenumber of 4000 or 4000 inverse centimeters (cm^{-1}).

Table 5. Wavelength Conversion Units.

From ->	Angstroms - Å	Nanometers - nm	Micrometers - **μ**m
To get ↓	Multiply by		
Angstroms - Å	1	10	10^4
Nanometers - nm	10^{-1}	1	10^3
Micrometers - **μ**m	10^{-4}	10^{-3}	1

BASIC RADIANT POWER RELATIONSHIPS

Radiant intensity is the most commonly used term to describe the radiant power of a source per unit solid angle. Radiant Intensity offers the advantage of being a source term, like radiance, that is not related to the size of the radiating source. In practice, radiant intensity is a derived term and is not directly measurable. If the Instantaneous Field of View (IFOV), which represents the smallest optical resolution element of a remote sensor, subtends an angle smaller than the size of the radiating source, the sensor responds directly to *radiance*. If the IFOV of the sensor subtends an angle larger than the radiating source, the sensor responds to *irradiance*. The relationship among radiant intensity, radiance, and irradiance is shown in the following equation:

$$I = ED^2 = E\frac{A}{\Omega} = LA = L\Omega D^2$$

Where:

I = Intensity. Radiant intensity is the target source power per unit solid angle, in Watts/steradian.

E = Irradiance. Irradiance is the received power density in Watts/cm2 incident on a distant sensor. Irradiance is the quantity measured or detected by a distant sensor where the target is not spatially resolved (i.e., where the target subtends an angle smaller than the resolution or field of view of the instrument.)

L = Radiance. Radiance is the intensity per unit area of source, in W/cm^2/steradians. Radiance is the quantity measured by a camera or imaging system, where the target is optically resolved (i.e., where the target subtends an angle much greater than the resolution or instantaneous field of view of the imager.)

A = Area. Area is the cross-sectional or projected area of the target in cm^2.

D = Distance. Distance between the target and sensor in cm.

Ω = Solid angle subtended by the target in steradians. Solid angle appears directly or indirectly in many infrared quantities. The solid angle subtended by a source is the ratio of the source area to the square of distance.

All remote sensors receive energy from a source through an atmospheric path. The atmosphere attenuates the propagation of energy due to scattering, absorption, and molecular rotation and vibration, depending on the wavelengths involved. The atmosphere itself also radiates. All incident energy on a remote sensor, except as received under vacuum conditions, is detected through the atmosphere. The term *apparent* is applied to a radiometric quantity to acknowledge the presence of atmospheric effects. A remote sensor, responding the radiance of a source over an atmospheric path, responds to *apparent radiance*.

Real sensors do not respond uniformly to energy. Sensors have non-uniform spectral and spatial response due to many factors, including detector and optical characteristics. All energy received by the detector is spectrally weighted by the spectral response of the instrument. The term *effective* is applied to acknowledge the non-uniform response of the instrument.

Outside of a vacuum, all radiation incident on a remote sensor is attenuated by atmospheric effects such as scattering and absorption. Where the atmosphere absorbs, it also emits. Path radiance is the term applied to the contribution of the atmospheric path to the received radiation. The term *apparent* is applied to radiometric quantities to acknowledge the influence of the atmosphere on the received radiation.

DOMAINS, DISTRIBUTIONS, AND SENSOR RESPONSE

Radiant power that is emitted or reflected from a source is distributed across multiple dimensions or domains. The three domains that are most important to radiometric applications are spectral (Figure 4), spatial (Figure 5), and temporal (Figure 6). Knowing how the radiant power from a source is distributed across each domain is important to understanding performance of an EW system, whether it be a sensor, a weapon, or a countermeasure.



In the spectral domain, radiation is distributed as a function of wavelength (or wavenumber). Radiation from solid materials is distributed as a continuum in accordance with Planck's formula. The graph above shows the spectral distribution of radiation from a 600 degree Celsius blackbody after passage through the atmosphere. Radiation from gases appears at specific wavelength "lines" corresponding to molecular resonances.

Figure 4. Sample Spectral Distribution of a Solid Material.

Spatial Domain



In the spatial domain, radiation is distributed as a function of angle, position, size, shape, or orientation. The graph above shows the radiance of a circular target as viewed by an imaging system.

Figure 5. Sample Spatial Distribution of a Circular Target Image.

Temporal Domain



In the temporal domain, radiation is distributed as a function of time (or frequency). Most IR target sources, such as aircraft and ground vehicles, change slowly with time and can be considered steady state for measurement purposes. However, IR countermeasures systems and devices, such as jammers and decoy flares, have high frequency content that must be considered in their design and effectiveness assessment.

Figure 6. Sample Temporal Distribution of a Modulated Source.

All electro-optical sensors have some sensitivity to how radiation is distributed across the different domains. This sensitivity or response takes the following forms:

1. **Spectral response**:
    a. May be broad in the case of a radiometer or imager, or narrow in the case of a spectrometer where response takes the form of resolution.
    b. Spectral response is chosen to exploit particular spectral features of interest in a target.
    c. Non-uniformity of spectral response can have a significant effect on the performance of sensor.

2. **Spatial response**:
    a. May be broad in the case of a radiometer or spectrometer, where spatial response takes the form of sensitivity across the sensor's FOV. In the case of an imager, the spatial response may be narrow because spatial response takes the form of the resolution or IFOV.
    b. Required spatial resolution is defined by the size and radiant power of the source, the distance between the source and the target, and by the sensitivity of the sensor.
    c. Non-uniformity of spatial response can have a significant effect on the performance of sensor.
    d. Response to radiation from the background within the FOV is primarily a spatial response issue and can be significant to sensor performance.

3. **Temporal response**:
    a. Takes the form of bandwidth or, in the case of a digital system, of sampling frequency.
    b. Unlike spectral and spatial response, temporal response includes the response time of the detector and all of the electronics, data transfer time, and processing time for a sensor.
    c. Non-uniformity across a region is usually not a concern. Temporal response is usually uniform for target frequencies that fall well below the low-pass or Nyquist breakpoints.

Sensors respond to received radiant power by integrating the power distribution in each domain under the corresponding response curve. Sensors respond in multiple domains, so output is proportional to a multi-dimensional, weighted integral. Figure 7 illustrates response-weighting, or convolution, of radiation with instrument response in the spectral domain. The concept applies equally in the spatial domain.

Response Weighting in the Spectral Domain


Source Spectral Radiance (W/cm2/sr/µ)
L
$L(\lambda)$
L
λ
R
$R(\lambda)$
Instrument Spectral Response
λ
Response-Weighted Product
$\int_0^\infty R(\lambda)L(\lambda)d\lambda$
Area
Product curve
$L(\lambda)R(\lambda)$
λ

Non-uniform sensor response across a domain distorts the distribution of received radiant power by weighting the radiation at some wavelengths differently than others. Instrument output is proportional to the integral of this weighted product, which makes instrument response shape an embedded part of both the measurement and the calibration. Some consequences of non-uniform response are:

- Two different sources with identical power, but different distributions will produce different measurement values.
- If two different sources (such as the calibration and the target) have similar relative power distributions, the relative weighting by the instrument will be the same for both sources, so the shape and degree of non-uniformity has little or no effect. This will be discussed in more detail later as a key strategy in calibration to reduce measurement uncertainty.

Figure 7. Response-Weighting in the Spectral Domain.

The consequence of instrument output being proportional to multiple weighted integrals is that the characteristics of the instrument affect the measured value in ways that cannot be easily extracted or corrected. Understanding non-uniformity in sensor response is critical to understanding performance and evaluating the effectiveness of the system.

INFRARED SOURCE CHARACTERISTICS

Reflectance

Reflectance is generally categorized as either *specular* (mirror-like) or *diffuse* (scattered by reflection from a rough surface). Most surfaces exhibit both types of reflection, but one typically dominates. Reflections from smooth surfaces are specular. Reflectance is a unitless quantity between zero and one that is the ratio of reflected power to the incident power. Reflectance varies with angle from the normal and with wavelength.

Diffuse reflectors scatter incident radiation broadly. Johann Heinrich Lambert described an ideal diffuse reflector in which the intensity of reflected rays is distributed as a cosine of the angle from the normal, regardless of the angles of the arriving incident rays. Such a surface is described as *Lambertian*. The same relationship applies to a diffuse source. If the source is perfectly diffuse, the radiance is independent of the viewing angle because the projected area of the source also varies as a cosine function of the angle from normal.

While no surface is perfectly diffuse, standard paint on most aircraft, for example, is near enough for at least a first approximation. Significant effort has gone into measuring and describing surface properties of military vehicles to support modeling and simulation activities. Bidirectional Reflectance Distribution Function (BRDF) is defined as the ratio of the reflected radiance to the incident irradiance at a wavelength, λ.

The BRDF provides a complete description of the reflectance properties of a surface. Measurements of BRDF are made in specially equipped optical laboratories. For aircraft, a typical use of BRDF data is in computer models that predict the reflections of the earth and sun from the aircraft fuselage and wings.

Emissivity

Emissivity is a unitless quantity that is a measure of the efficiency of a surface as an absorber or emitter. Emissivity is expressed as a number between 0.0 and 1.0. According to Kirchoff's Law, for an opaque object in thermal equilibrium, i.e., no net heat transfer, the emissivity equals the absorptance. In other words, a perfect emitter is also a perfect absorber. This ideal emitter is known as a *blackbody*. A surface with an emissivity of 1.0 emits the maximum radiation that Planck's Law allows. A body for which the emissivity is constant with wavelength but less than 1.0 is commonly known as a *graybody*. Planck's equation is typically expressed for an ideal blackbody emitter, but multiplying the blackbody expression by the emissivity term expresses the spectral distribution of power for a graybody.

Electromagnetic (EM) radiation, including infrared radiation, can be characterized by amplitude, frequency (or wavelength), coherency, and polarization properties. Amplitude refers to the magnitude of the electromagnetic wave. Coherency refers to the degree in which the electromagnetic waves maintain a constant phase difference, both spatially and temporally. Polarization is a description of the orientation of the wave's propagation perpendicular to the direction of travel. Like all electromagnetic radiation, infrared radiation travels as an EM field with the propagation velocity of the speed of light in a vacuum, and slower through air and other dielectrics. , Infrared radiation also exhibits both wave and particle properties. Which property is used depends on the application: Waves are used for applications involving propagation and geometrical optics, while particles (photons) are used for most detector applications. The energy of a photon is inversely proportional to its wavelength (*hc*/λ) where *h* is the Planck's constant, and *c* is the speed of light.

Infrared radiation also interacts with matter in a variety of ways:

- Reflects – wave is reflected from a surface.
- Refracts – direction of wave bends when passing between two transparent media with different propagation speeds.
- Scatters – when interacts with particles whose size approaches the wavelength of the radiation.
- Diffracts – around edges of an obstruction.
- Interferes – constructively and destructively.
- Absorbs – when absorbed by matter, radiation is (usually) converted into heat energy.
- Emits – radiation is emitted from matter by conversion from another form of energy.
- Transmitted – propagates through a transparent medium (or vacuum).

Plank's Law:

Infrared is directly related to the heat radiated from matter. Anything with a temperature above absolute zero (-273.15 degrees Celsius) radiates in the infrared. Planck's Law, discovered by German Physicist Max Planck, mathematically describes the distribution of radiant power across the spectrum for a given temperature. The form presented below calculates source radiance in Watts/sr/cm^2/ μ:

$$L_\lambda = \frac{C_1}{\pi\lambda^5\left[e^{\left(\frac{C_2}{\lambda T}\right)} - 1\right]}$$

Where: $C_1 = 2\pi c^2 h = 3.7415 \times 10E{+}04$ W cm^{-2} μ^4

$C_2 = ch/k = 1.4389E{+}04$ μ K

c = speed of light; h = Plank's constant; k = Boltzmann's constant

With λ in μ and T in Kelvin (= ºC + 273.15)

The behavior of Planck's curve with temperature is fundamental to every infrared detection scenario. Figure 8 shows Planck's equation for a single temperature. The shape of this curve resembles a wave of water, with a steep rise in power on the short wavelength side of the peak and a tail off on the long wavelength side.



Figure 8. Temperature Effects and Power Distribution.

When temperature increases, two significant changes in power distribution occur and are governed by the following two relationships:

Stefan-Boltzmann Law:

The total power under the curve increases proportionally to the fourth power of the temperature. According to the Stefan-Boltzmann law, the total radiant emittance (power) of a blackbody is:

$$M = \sigma T^4 \qquad \text{Where:} \quad \sigma = \frac{2\pi^5 k^4}{15 c^2 h^3} = 5.67 \times 10^{-12}\ Watts\ cm^{-2}\ {}^\circ K^{-4}$$

and T is in Kelvin

This is Plank's radiation law integrated over all values of λ.

Wein's Displacement Law

The peak emission translates toward shorter wavelengths.

Wein's displacement law takes the derivative of the Plank's law equation to find the wavelength for maximum spectral exitance (emittance) at any given temperature:

$$\lambda_{max} = 2897.8 / \mathbf{T}$$ where T = temperature is in Kelvin

The surface of the sun radiates with a spectral distribution like that of a 5900 Kelvin source. In accordance with Wein's Law, the wavelength at which the radiation for a 5900 Kelvin source peaks is approximately 490 nanometers. The maximum sensitivity of the day-adapted human eye (photopic) occurs at about 555 nanometers, which happens to be in a highly transparent region of the atmosphere. In other words, the temperature of our sun and the transmission of our atmosphere are conveniently matched to the response of the human eye. Figure 9 shows the relationship between the response of the human eye and the spectral distribution of solar irradiance.



Figure 9. Power Distribution of the Sun Related to the Human Eye.

Unlike other electromagnetic radiation, the peak radiation from objects at the temperature of the earth, and of humans, vehicles, aircraft, etc., lies at infrared wavelengths. This makes the infrared portion of the spectrum militarily important.

For detection of an object, whether it is with the human eye or with an electro-optical sensor, it is not where the maximum emissions occur in the spectrum that is important. It is where the maximum difference between the target and background lies that is most significant.

The *absolute* signature of a source or target is the power radiated and reflected by the target without influence from background radiation. Absolute signature can be measured with an instrument such as an imaging camera at close range, producing highly resolved IR imagery. The difference between radiation from a target and its background is its *contrast*. Contrast is the target signature relative to a specific background. Contrast irradiance is the quantity detected by any remote sensor or missile. Contrast varies greatly with background conditions.

Figure 10 shows several different types of source distributions encountered by infrared sensors. Most targets of military interest are a complex combination of spectral contributions from a variety of sources. For example, the signature of an aircraft can typically be described by the contributions from airframe, hot engine parts, and plume.



NOTE: These charts show relative not absolute radiant intensity of each signature. Consequently the "amplitude" of one cannot be compared with the "amplitude" of another.

Figure 10. Spectral Distribution of Various Targets.

ATMOSPHERIC TRANSMISSION

The radiation emitted or reflected from the targets and backgrounds must pass through the intervening atmosphere before reaching the detection system. The radiation is absorbed and re-emitted by molecular constituents of the atmosphere and scattered into and out of the path by various aerosol components.

Figure 11 reveals the presence of atmospheric windows, i.e. regions of reduced atmospheric attenuation. IR detection systems are designed to operate in these windows. Combinations of detectors and spectral bandpass filters are selected to define the operating region to conform to a window to maximize performance and minimize background contributions.



Figure 11. Atmospheric Transmission Over 1 NM Sea Level Path.

The molecules that account for most of the absorption in the IR region are water, carbon dioxide, nitrous oxide, ozone, carbon monoxide, and methane. Figure 12 shows an expanded view of the infrared portion of the spectrum.



Figure 12. Transmittance of Atmosphere Over 1 NM Sea Level Path (Infrared Region).

The transmission in a window is greatly dependent on the length and characteristics of the path. As path length increases, absorption gets deeper and broader. Water vapor also has a significant effect overall on transmission through the atmosphere. High relative humidity attenuates transmission at all optical wavelengths.



Figure 13. Transmittance at Various Altitudes.

Since water vapor generally decreases with altitude, transmission generally increases and path length becomes the determining factor. However, path length does not affect transmission of all wavelengths the same.

The altitude effects on transmittance are shown in Figure 13.

A great deal of work has gone into developing high fidelity atmospheric models. One of the most commonly used tools is MODTRAN™ (MODerate Resolution Atmospheric TRANsmission). MODTRAN™ models atmospheric propagation of EM radiation from 0.2 to 100 um. MODTRAN was developed by Spectral Sciences Inc. and the United States Air Force Research Laboratory.

ELECTRO-OPTICAL COMPONENTS AND SENSORS

Almost all IR instruments, missiles, search systems, etc. have similar functional components. Basic components typically include:

- Optics - Reflective or refractive lenses to:
  - Collect radiation. Irradiance (power density) is increased by collecting radiation over a large area and focusing down to a small area.
  - Form or focus an image that will be used to extract information about the target.

- Filter(s) - Spectral and spatial filters to distinguish target from background and to extract
  - Target information.
  - Spectral filters restrict sensitive wavelength range.
  - A spatial filter separates image information by features such as size or position.

- Detector - A transducer to convert received radiation to an electrical signal for processing.

- Electronics - Used to amplify and condition the detector signal and perform some action, such as controlling a servo for tracking and guidance or recording the received information. In addition to the above, the optical head may also contain a window to protect the electronics and an output unit consisting of indicators or displays.

Windows / Domes / Lens Materials

For most applications of EO systems in EW the detection system is protected from the environment by a window or dome of optically transmissive material. The window operates both as a weather seal and, in some cases, helps to define the spectral response region of the system. In some cases the window functions as a lens.

IR energy interacts with matter in ways we associate with light (reflection, refraction, and transmission). Lower energy of IR photons results in different optical properties than light. For example:

- Glass and water are not transparent to wavelengths longer than about 3 microns.
- Silicon and germanium are highly transparent to infrared radiation, but are opaque to visible light.

Transmission bands of representative window or lens materials are shown in Figure 14. The end points depicted are for the 10% transmission wavelengths. Not shown in Figure 14 are the various UV transmissive glasses such as Pyrex, Corex, and Vycor or Amorphous Material Transmitting IR radiation (AMTIR) which are various combinations of Ge-As-Se (AMTIR-1), As-Se (AMTIR-2, 4, & 5), Ge-Sb-Se (AMTIR-3), As-S (AMTIR-6).



Figure 14. Transmission of Selected Window / Lens Materials.

Objective Lens

The objective lens is the first optical element in a lens in a typical sensor or missile seeker. The objective lens serves two main functions:

- Collect radiation (i.e., multiply irradiance (power density) by collecting over a large area and focusing onto a small area)
- Form an image of the target scene onto a filter and detector array.

Lens Types

Lenses for the IR can be either refractive or reflective. Refractive optics are "straight through" lenses, with the light never making large bends as shown in Figure 15.



Figure 15. Refractive Lens.

A common reflective design used in many missiles is the Cassegrain. The Cassegrain design shown in Figure 16 is compact in size for its focal length.


Primary mirror objective lens
Image plane
Secondary mirror
Cassegrainian telescope

Figure 16. Cassegrain Lens.

Optical Filters

Filters may be divided into two major categories: (1) spectral and (2) spatial.

Most optical radiation detectors have a wider sensitivity band than desired for the particular application. Spectral filters restrict sensitive wavelength range. Reasons for filtering include: enhancement of target-to-background contrast, avoidance of unwanted plume emissions and/or atmospheric absorption regions, and extraction and measurement of target spectral features.

To further define the system sensitivity, band interference filters or absorption filters are used. An absorption filter is a bulk material with a sharp cut-on or cut-off in its transmission characteristic. A cut-on and a cut-off filter can be combined to make a bandpass filter. By selecting absorption characteristics of absorption filters combined with the response of a detector, the desired system response can be obtained. An interference filter is composed of dielectric coatings on an appropriate substrate combined in such a way to produce cut-on, cut-off, or bandpass filters. Interference filters allow more control of the final response characteristics and smaller elements. See Figure 17.


Transmission
Region of destructive interference: no transmission
Region of constructive interference: high trans
Region of destructive interference: no transmission
Wavelength

Figure 17. Spectral Bandpass Filter.

Most spectral filters are of the thin-film interference type. Layers of dielectric material are vacuum deposited on a substrate window material. Typical substrate materials in IR are sapphire, silicon, and germanium. Thickness of deposited layers designed to have constructive interference to pass desired radiation at desired wavelengths and destructive interference to block undesired wavelengths Besides spectral filters, EO system optics often have antireflection (or AR) coatings to eliminate or greatly reduce unwanted reflections between optical elements.

A spatial filter separates information in a scene image by features such as size or position. Spatial filters take a variety of forms. Some common types and their functions include:

- Field stop: limits an instrument's field of view. Blocks unwanted sources (such as sun) outside nominal field of view.
- Mechanical modulator or "chopper."
- Reticle: A mechanical modulator used in many missile designs. Usually discriminates against extended sources (such as background) in favor of "point" target sources and provides target directional information from modulation phase.

Detector Coolers

Many IR detectors have to be cooled for proper operation. Most systems use closed-cycle coolers or thermoelectric coolers. Thermoelectric coolers use the Peltier effect, which produces a reduced temperature by passing a d-c current through a thermoelectric junction. Multi-stage coolers can cool a detector down to below 200ºK. Closed-cycle coolers typically are of the Stirling cycle design and utilize the expansion of a gas (helium) to cool a cold finger attached to the detector. These generally operate at liquid nitrogen temperature (77ºK).

Detectors

A detector is a transducer that transforms electromagnetic radiation into a form, which can be more easily detected. In the detectors of interest to EW the electromagnetic radiation is converted into an electrical signal. In some systems the signal is processed entirely within the system to perform its function. In others the signal is converted to a form to allow the human eye to be used for the final detection and signal analysis.

Detectors are transducers than convert optical radiation into electrons. The physical effects by which electromagnetic radiation is converted to electrical energy are divided into two categories: photon effects and thermal effects. EW systems primarily use detectors dependent on photon effects. These effects can be divided into internal photo effects and external photo effects.

The external photo effect is known as photoemission. In the photoemissive effect, photons impinging on a photocathode drive electrons from its surface. These electrons may then be collected by an external electrode and the photocurrent thus obtained is a measure of the intensity of the received radiation.

Internal photoeffects of interest are the photoconductive effect and the photovoltaic effect. In the photoconductive effect, absorbed photons cause an increase in the conductivity of a semiconductor. The change is detected as a decrease in the resistance in an electrical circuit. In the photovoltaic effect, absorbed photons excite electrons to produce a small potential difference across a p-n junction in the semiconductor. The photovoltage thus produced may be amplified by suitable electronics and measured directly.

Thermal detectors respond directly to heat. Examples of these devices include bolometers, thermopiles, and pyroelectric detectors. The pyroelectric effect is an example of the thermal effect. The pyroelectric effect is a change in polarization in a crystal due to changes in temperature. Radiation falling on such a crystal is detected by observing the change in polarization as a build up of surface charge due to local heating. When coated with a good black absorber, the crystal will be sensitive to a wide band of wavelengths.

Figure 18 shows the spectral sensitivity range of typical detectors using these effects.



Figure 18. Spectral Range of Various Detectors.

Detector Types

Photoconductive detectors operate as resistors in a circuit. The resistance of the detector changes as the radiation incident on its surface changes. For EW applications, the most photoconductive detector types include: Indium Antimonide (InSb), which can also be operated in photovoltaic mode; Gallium Arsenide (GaAs); Lead Sulfide (PbS); and Lead Selenide (PbSe).

Photovoltaic detectors, the most common detectors used in modern EW and military sensor applications, produce a voltage that is proportional to the incident radiation. Common examples of photovoltaic detectors are Indium Antimonide (InSb) and Mercury Cadmium Telluride (HgCdTe). Both of these detector types offer high sensitivity when cryogenically cooled.

Diode phototubes and photomultipliers are commonly used detectors for UV systems including many operational missile-warning systems. These types of tubes offer the advantage of operating uncooled which can significantly reduce the complexity of a sensor system and offer increased reliability. Most of the modern IR sensors require cooled detectors. InSb, for example, requires cooling to 77 Kelvin to achieve the necessary sensitivity. Depending on the application, HgCdTe can be operated at somewhat higher temperature conditions.

A Photoelectromagnetic (PEM) detector has a junction that generates a current when exposed to light in a magnetic field.

Some detectors (such as InSb) have multiple modes of operation, including: Photoconductive (PC), Photovoltaic (PV), or Photoelectromagnetic (PEM) modes of operation.

Detector Parameters and Figures of Merit

The important parameters in evaluating a detector are the spectral response, time constant, the sensitivity, and the noise figure.

The spectral response determines the portion of the spectrum to which the detector is sensitive.

The time constant is a measure of the speed of response of the detector. It is also indicative of the ability of the detector to respond to modulated radiation. When the modulation frequency is equal to one over the time constant, the response has fallen to 70.7 % of the maximum value. The time constant is related to the lifetime of free carriers in photoconductive and photovoltaic detectors and to the thermal coefficient of thermal detectors. The time constant in photoemissive devices is proportional to the transit time of photoelectrons between the photocathode and anode.

The sensitivity of a detector is related to its responsivity. The responsivity is the ratio of the detected signal output to the radiant power input. For photoconductive and photovoltaic detectors the responsivity is usually measured in volts per watt -- more correctly, RMS volts per RMS watt. However, the sensitivity of a detector is limited by detector noise. Responsivity, by itself, is not a measure of sensitivity. Detector sensitivity is indicated by various figures of merit, which are analogous to the minimum detectable signal in radar. Such a quantity is the noise equivalent power (NEP). The NEP is a measure of the minimum power that can be detected. It is the incident power in unit bandwidth, which will produce a signal voltage equal to the noise voltage. That is, it is the power required to produce a signal-to-noise ratio of one when detector noise is referred to unit bandwidth. The units of NEP are usually given as watts, but more correctly, are watts/$\text{Hz}^{1/2}$ or watts·$\text{sec}^{1/2}$.

Another figure of merit is the noise equivalent irradiance (NEI). The NEI is defined as the radiant power per unit area of the detector required to produce a signal-to-noise ratio of one. The units of NEI are watts per square centimeter.

Noise equivalent power (NEP) is the radiant power required to produce a signal to noise ratio of one for a detector. Detectivity (D) of a detector is defined as the reciprocal of the NEP. The units of D are watts $^{-1}\cdot$sec $^{-1/2}$. A higher value of detectivity indicates an improvement in detection capability. Since D depends on detector area, an alternate figure of merit, known as D-star (D*). D* is the detectivity measured with a bandwidth of one hertz and reduced to a responsive area of one square centimeter. The units of D* are cm·watts $^{-1}\cdot$sec $^{-1/2}$. D* is the detectivity usually given in detector specification sheets. Typical spectral detectivity characteristics for various detectors are shown in Figure 19.



Figure 19. Spectral Detectivity of Various Detectors.

Besides the NEI mentioned above, the quantum efficiency of the photocathode is also a figure of merit for photoemissive devices. Quantum efficiency is expressed as a percent -- the ratio of the number of photoelectrons emitted per quantum of received energy expressed as a percent. A quantum efficiency of 100 percent means that one photoelectron is emitted for each incident photon.

There are other figures of merit for television cameras. The picture resolution is usually described as the ability to distinguish parallel black and white lines and is expressed as the number of line pairs per millimeter or TV lines per picture height. The number of pixels in the scene also defines the quality of an image. A pixel, or picture element, is a spatial resolution element and is the smallest distinguishable and resolvable area in an image. CCD cameras with 512 x 512 elements are common.

Another resolution quantity is the gray scale, which is the number of brightness levels between black and white a pixel can have.

Noise in Detectors

The performance of a detector is limited by noise. The noise is the random currents and voltages that compete with or obscure the signal or information content of the radiation. Five types of noise are most prominent in detectors: (1) thermal, (2) temperature, (3) shot, (4) generation-recombination, and (5) 1/f noise.

Thermal noise, also known as Johnson noise or Nyquist noise, is electrical noise due to random motions of charge carriers in a resistive material.

Temperature noise arises from radiative or conductive exchange between the detector and its surroundings, the noise being produced by fluctuations in the temperature of the surroundings. Temperature noise is prominent in thermal detectors.

Shot noise occurs due to the discreetness of the electronic charge. In a photoemissive detector shot noise is due to thermionic emission from the photocathode. Shot noise also occurs in photodiodes and is due to fluctuations in the current through the junction.

Generation-recombination noise is due to the random generation and recombination of charge carriers (holes and electrons) in semiconductors. When the fluctuations are caused by the random arrival of photons impinging upon the detector, it is called photon noise. When it is due to interactions with phonons (quantized lattice vibrations), it is called generation-recombination noise. Johnson noise is predominant at high frequencies, shot noise predominates at low frequencies, and generation-recombination and photon noise are predominant at intermediate frequencies.

As the name implies, 1/f noise has a power spectrum that is inversely proportional to frequency. It is dominant at very low frequencies. In photoemissive detectors it is called flicker noise and has been attributed to variation in the emission from patches of the photocathode surface due to variation in the work function of the surface. In semiconductors 1/f noise is also called modulation noise. Here it is apparently due to surface imperfections and ohmic contacts (which are a form of surface imperfection).

Infrared Spectral Region and Features of Interest

Different portions of the infrared spectrum are common for particular applications. The reasons for the selection of a specific window are often sensitive and beyond the scope of this document, but selections are typically based on several key considerations:

- Target characteristics such as size and spectral distribution of signature.
- Background radiance and clutter.
- Atmospheric effects (transmission, path radiance, scintillation, etc.).
- Distinguishing characteristics between natural and man-made sources.

Table 6 describes some of the types of characteristics that are prevalent in the short-wavelength (SWIR) infrared (0.7 to 3.0 microns), mid-wavelength (MWIR) infrared (3.0 to 6.0 microns) and long-wavelength (LWIR) infrared (7.0 to 14.0 microns) along with some types of systems that operate in these regions.

Table 6. Infrared Features, Regions, and Types of Systems.

Near or Short Wave IR (SWIR)	**Dominant natural source:**	**Sun**
	Atmospheric:	
	Transmission:	High
	Path radiance:	Scattered sunlight
	Dominant aircraft IR component:	Sunlit airframe
	Anti-aircraft threat:	Vehicle-launched SAM
Mid-wave IR (MWIR)	**Dominant natural source:**	**Sun**
	Atmospheric:	
	Transmission:	High transmission “windows” between H_2O and CO_2 absorption
	Path radiance:	Scattered sunlight below 3 microns Thermal at longer than 3 microns
	Dominant aircraft IR component:	Engine hot parts and plume
	Anti-aircraft threat:	All AAMs and SAMs
Far or Long-wave IR (LWIR)	**Dominant natural source:**	**Earth**
	Atmospheric:	
	Transmission:	High
	Path radiance:	Low: small thermal emission from ozone
	Dominant aircraft IR component:	Airframe direct emission and terrestrial illumination
	Anti-aircraft threat:	Airborne IRST. No anti-aircraft missiles

Sensors and Detection

Figure 20 shows a generalized detection problem. On the left of the diagram are the radiation sources - the sun, background, and the target of interest. In the middle is the intervening atmosphere, which attenuates the radiation as it travels to the detection system shown on the right of the diagram.



Figure 20. Generalized Detection Problem.

Figure 21 shows the basic relationships that are critical to detection of a target in the infrared. The figure is based on a generalized aircraft, but the principles apply whether the target is in fact an aircraft against a sky background or a ground vehicle being viewed from above against a terrain background. At detection, most targets are unresolved. The sensor’s ability to detect the target against background in this case is driven primarily by noise equivalent irradiance.


Irradiance = Intensity / (Range²)
E = I / R²
where:
E = Irradiance at sensor (W/cm²)
R = sensor-to-target range (cm)
Target
Sensor
Range to target
= R (cm)
L_t
A_t
L_b
Background
Intensity = Radiance * Area
I_t = L_t * A_t
where:
A_t = target projected area (cm²)
L_t = radiance (W/sr/cm²)

Figure 21. Detection of a Target with a Remote Sensor.

Each of the equations shown in Figure 21 in reality has atmospheric effects and attenuation due to transmission losses and contributes to path radiance. Just as the power distribution of the target and background vary with wavelength, atmospheric effects are also spectrally selective.

Figure 22 shows the roll off of irradiance as a function of range for two different aircraft. Detection occurs at the point of intersection with the sensors noise equivalent irradiance. In the case of threat missiles, there is often a signal-to-noise threshold required for launch of the missile to ensure target quality prior to launch. The product of noise equivalent irradiance and the threshold for these systems is known typically as the minimum trackable irradiance (MTI). This is the figure used to calculate detection range for such systems.

In an effort to simplify calculations, band average atmospheric transmission values are often applied during analysis of detection scenarios. The target itself is non-uniformly distributed as a function of wavelength, and the atmospheric effect is non-uniform, so this approach is mathematically incorrect since it pulls a non-constant term out of an integral. The degree of error introduced by the band average approach depends on the spectral distribution of the source and the overall transmission of the band in question, but caution should be applied when applying band averages. All calculations involving atmospheric propagation should be done spectrally and then integrated to provide the in-band value.



Figure 22. Detection Range Calculation.

Sensor Characterization

As described in a previous section, the output of every sensor is proportional to an integral of the received radiation weighted by the instrument's response function in that domain. Every sensor responds to radiation in accordance with the characteristics of the sensor and its components.

Characterization quantifies the sensor's response shape. Knowledge of response shape is essential to the design of a sensor and understanding its performance in with changing ambient conditions and against various types of targets in real environments.

Normalization

Calibration of a sensor, which describes its response to known input sources, and characterization of the sensor would ideally be the same process. Ideally, the absolute instrument response would be mapped over a domain with a traceable standard laboratory source that was tunable across the range of interest. In the spectral domain, for example, this would require a tunable monochromater whose output beam provided a level of spectral irradiance traceable to a radiation standard and that also had a cryogenically-cooled background source. The result would be an absolute spectral response function in units of output reading per unit radiance (or irradiance) as a function of wavelength.

In practice, it is sufficient and more practical to separate the characterization and calibration processes, so characterization determines only the relative response shape rather than absolute. Calibration then incorporates the results of the shape characterization to determine the absolute instrument response. Both, however, are important to understanding performance of a sensor.

Characterization uses a variety of different methods and sources to map relative response shapes. The response curve is then normalized and this normalized curve is used in the later derivation of the calibration coefficients. Different normalizations, such as normalization to an average value, are possible, but the convention throughout most of the measurement community today is to normalize response curves to unity at the peak.

When the contributions of all the components are combined into one curve, the result is then peak normalized and this, now unitless, curve is used in the calibration calculations.

Calibration

Sensor calibration, which is the process of relating the known input power to the output of a sensor, requires the use of standard sources, typically National Institute of Standards and Technology (NIST) traceable blackbodies and various other laboratory equipment such as collimators which make all of the rays coming from the source parallel to each other, thus representing a source at infinity. Figure 23 is a pictorial illustration of the calibration of a sensor.


Known input radiant power (L_{calib} or E_{calib})
Sensor
Output reading (volts or digital counts)
Calibration quantifies the relationship between input radiant power and output reading.

Figure 23. Sensor Calibration Relates Input Power to Output.

Calibration of a sensor usually involves two major steps. Responsivity is the change in output of the sensor to changing input. For a sensor that responds linearly, for example, responsivity represents the slope of the curve when source radiance or incident irradiance is plotted against output voltage or counts for a digitized system. Figure 24 represents a calibration curve for a sensor that has a linear change in output over its dynamic range with changing input power. The slope of the curve is the “m” in the linear equation. Not all sensors respond linearly with power. Higher order response coefficients are common, especially for bolometers and infrared focal plane array sensors operated at short integration times. For these the process of determining the response of the instrument is the same, the curve just yields higher order terms.


+
-
0
Input Radiance, L (W/sr/cm^2)
Output reading, x (counts)
$L = mx + b$
x-intercept (-b/m) is determined by electrical offset and instrument internal radiation sources.
y-intercept, (b) is often a "negative radiance" number that varies with time and ambient temperature.

Figure 24. Calibration of a Sensor to Determine Responsivity and Offset.

For most electro-optical sensors, the responsivity does not change with ambient temperature. In other words, the non-constant terms in the calibration equation, whether it is linear or higher order, do not change with changes in temperature. Over time, however, as detectors decay, responsivity decreases. This would show itself on the Figure 24 as an increase in the slope value, i.e., higher input power is required for the same output as the detector becomes less responsive.

Offset

Offset is another important parameter for instrument calibration. For any real (non-ideal) instrument, the response curve does not pass through zero. There are several reasons for this; one being that except in a complete vacuum, zero radiance does not exist. Additionally, contributions from detector noise and radiation from the optical elements in the lens, which cause the offset to drift with changes in ambient temperature, contribute to the offset term. Some amount of offset is designed into the system as well. All electronic circuits have some amount of DC drift. To prevent clipping of the signal if this drift should go below the lower limit of the analog-to-digital converter, the "bottom end" level is adjusted up to some offset level. The consequence of this offset voltage is the addition of a y-intercept term (b), which also must be quantified by the calibration if the sensor is a laboratory instrument. For a sensor that is used for contrast detection, the intercept value is unimportant since it subtracts out in the contrast calculation.

Sensitivity

Sensitivity for a sensor is determined to a large extent by the noise level in the detector output. For focal plane array detector, pixel-to-pixel non-uniformity also limits the sensitivity of the system since detection is determined by contrast with surrounding pixels. In practice, at least for cooled infrared sensors, detection is typically limited by background and not noise limits.

Instrument Response Uniformity and Non-Uniformity Correction

In reality, all sensors exhibit non-uniform response in all of the domains referenced previously. For example, in the spatial domain, the raw output of an infrared focal plane array detector exhibits pixel-to-pixel offset differences and response differences across the field-of-view. The response change is the result of two primary factors. Since each pixel is essentially a unique detector, it exhibits unique response because of manufacturing tolerances, slight differences in crystal structure, etc. Additionally, most electro-optical sensors implement an aperture or "field stop" in the case of infrared sensors, that limits the radiation that can reach the detector outside of the sensor's desired field-of-view. Radiation entering at angles off of normal to the detector shows a cosine roll-off in incident power. The result is a reduction in responsivity for pixels that are radially separated from the center of the detector. For the majority of systems, an optical gain correction can be applied to compensate for the change in response. The typical method involves using an extended blackbody source that fills the FOV of the sensor. Reference images are collected with the source at two temperatures that are well separated across the sensor's dynamic range. This process is typically called a "2-point" correction. Actual temperature is unimportant. Slope corrections can be determined for each pixel. The result is a gain map that can be stored in the sensor electronics that can be applied to each image to correct for the non-uniform spatial response across the detector array. Pixel-to-pixel offset maps can be determined using one of the same reference images. Pixel slope and offset corrections are typically derived as normalized quantities relative to a center pixel, average of center pixels, or maximum value. The application of the correction maps to the images is commonly referred to as "non-uniformity correction." Figure 25 shows the transition from a raw image to a non-uniformity corrected image.



Figure 25. Non-Uniformity Correction of a Mid-IR Image.

Bad Pixel Replacement

Focal plane arrays have pixels that are either unresponsive or responsive outside of useful limits. Figure 25 shows some of the bad pixels that appear as small black spots in an image from an InSb IRFPA imager. Bad pixels can be identified during laboratory calibration or with a sensor mounted reference source. There are many approaches to replacement of bad pixels and the best approach often depends on the sensor characteristics and its application. One common approach is simply to replace the pixel with the average of its nearest neighbors.

INFRARED THREATS TO AIRCRAFT AND THEIR COUNTERMEASURES

IR guided missiles are the largest single cause for aircraft losses since the start of the 1991 Gulf war. All missiles designed within the last 20 years have counter-countermeasures circuitry. Every missile can be defeated with IR countermeasures given time to develop and test devices and techniques, but many missiles have not been exploited and the variety and complexity of the different designs present formidable challenges to the US countermeasure community.

The IR "signature" of any aircraft has three main components:

- Engine exhaust plumes
- Engine hot parts (tailpipe, etc)
- Airframe (aerodynamic heating & reflection from sun, earth, etc)

Infrared guided missiles modulate the signal produced by the aircraft in contrast with its background. Previous generations of missiles used reticles to produce signal waveforms that would provide spatial and temporal information from which signal processing could produce trackable information.

IR Missile Operation

Aircraft (or any other object) can be intercepted using several different types of guidance. The simplest type is pure pursuit, where the missile is always pointed directly at the target location. This is not aerodynamically efficient since the missile would follow a longer (curving) flight path when following a crossing target.

Most missile guidance systems are designed to lead the target so that intercept occurs at the point where the target will be at the time the missile arrives. This requires that the missile fly a course so the relative bearing to the target stays constant (constant "line of sight" angle). The LOS angle is determined by missile speed relative to the target (higher closing speed = smaller angle). The size of the angle isn't important; only that it be constant (zero line of sight rate) as shown in Figure 26.



Figure 26. Missile Proportional Navigation.

This intercept course ("proportional navigation") requires that the missile have two separate servo loops: (1) a target tracker and (2) a wing control servo to control direction of flight

For a missile to guide to its intended target, it needs a tracker, which contains the following elements:

- Optics to collect and focus IR from target.
- Gimbals to allow movement to point the optics.
- Gyro stabilization to isolate optics from missile body.
- Detector to convert the received IR to electrical signal.
- Stabilization (gyro) to isolate from missile body.
- A method to determine target direction to enable closed-loop tracking.
- A method to distinguish the target from natural background.

The target tracker is the "window" into the missile's guidance through which it can be deceived by countermeasures.

The problem of determining target direction with a single detector was solved by forming an image of the target scene onto the center of a reticle disk that spun with the optics. Unlike, for example, the reticle in a rifle telescope that superimposes cross hairs, the reticle in a missile acts as a kind of shutter that blocks the passage of IR through part of the reticle and allows IR to pass through the other part. A target image falling on the opaque portion is blocked and produces no detector signal. A target image falling on the transparent portion is passed on to the detector. When the reticle is spun, IR from a target off center is alternately passed and blocked, resulting in amplitude modulation (AM). The phase of this modulation relative to a spin reference is used to tell target direction from center. A closed servo loop moves the optics to keep the target centered on the reticle. This is depicted in Figure 27.


Target
Image
a
Opaque Sector
Masks Target Return
Detector
Output
a
Time
b
b
Detector
Output
Time
Detector
Output
Time

Figure 27. Basic Reticle Design.

Target trackers have another problem: The aircraft target must be distinguished from natural background sources, such as sunlit clouds and terrain. To solve this, they look for features in the spectral, spatial, and temporal domains where the target is different from background.

- Temporal: There is no difference. Neither clouds nor aircraft signature are time varying.
- Spectral: Some difference. Choice of wavelength band yields helpful differences between target and background, but this is not sufficient by itself.
- Spatial: The most viable option. Aircraft are smaller than clouds and terrain. Background radiation can be greatly reduced by spatial filtering.

If half of the reticle is made with opaque "spokes," then some irradiance from targets with small images (such as aircraft) will be modulated more completely and generate a stronger signal at a faster modulating rate than large images (clouds) as shown in Figure 28.


Cloud or Other Extended Source
Target Image
DETECTOR OUTPUT
Target Return
50% Transmissive
Cloud Return

Figure 28. IR Seeker Design for Background Discrimination.

The past figure and the following two figures (29 and 30) depict a spin-scan reticle used on the early Sidewinder designs. After the detector preamp, signal goes through a narrow bandpass filter to improve S/N. The AM waveform is then rectified and filtered. Target direction is determined from AM envelope phase.


Target Image Off-Center
Target Image at Center
50% Transmissive Reticle
Static Gain Curve
Center
Total FOV

Figure 29. Spin Scan Seeker.


Raw detector waveform
Carrier frequency (fc)
AM waveform after bandpass filtering
Target Signal Strength
100%
50%
0%
fc
Modulation envelope at spin frequency contains target direction information (phase)
Bandpass Filter

Figure 30. Spin Scan Waveforms for Off-Center Target.

Spin-scan has the following characteristics that are important to countermeasures:

- The tracker loop drives to null the signal to zero. This occurs when the target is on the optical axis and the target image is at the center of the reticle.
- If the target is off-center, an AM carrier "error signal" is generated, where the phase of the modulation envelope indicates the target direction.

With spin scan, the missile is always looking at the target. This vulnerability to jammers led to the next evolution in target trackers: conical scan.

Conical scan borrows concept from early fire-control radars, which used a nutating feed horn. A con scan tracker is shown in Figure 31. With con scan:

- The secondary mirror of the Cassegrain is canted so the field of view seen by the detector sweeps out a pattern of overlapping circles.
- A target image at boresight falls near the edge of the reticle instead of center.
- Reticle pattern is same all the way around. (Usually tapered spokes.)

- Modulation of target near boresight is FM rather than AM. This allows tighter tracking.
- For larger angles off boresight, the target image falls outside the FOV of the detector for part of the scan. The modulation then becomes AM.


Incoming
IR Rays
Primary Mirror
Fixed Reticle
Canted Rotating Secondary Mirror
Detector
Dome
Instantaneous Field of View (IFOV)
With conical scan, IFOV of tracker sweeps out a circular pattern on reticle & detector

Figure 31. Conical Scan Tracker.

In the con scan tracker, as the missile instantaneous field of view nutates about a target on boresite, (moving through positions at t_1 through t_5 shown in Figure 32), the apparent position of a target image on the reticle sweeps out the circular pattern shown.


Target image at center of nutating FOV
t_4
t_3
t_5
t_2
t_1
t_1
t_2
Apparent position of target image on reticle.
t_5
t_3
t_4

Figure 32. Image on a Con Scan Reticle: Target at Boresite.

If the target is off boresight as shown in Figure 33, the detector receives a signal of varying pulse widths.


Target image off boresite
t_4
t_3
t_2
t_5
t_1
t_1
t_2
t_3
t_4
t_5
Apparent position of target image on reticle.

Figure 33. Image on a Con Scan Reticle: Target off Boresite**.**

The waveform produced by a target on boresite is a constant amplitude carrier at the reticle chopping frequency as shown in Figure 34. A target slightly off boresite produces a constant amplitude carrier that is frequency modulated at spin frequency.


RETICLE
CENTERED TARGET
Detector Output Uniform - Constant Amplitude
OFF-CENTER TARGET
Detector Output Has Varied Pulse Width

Figure 34. Conical Scan Seeker Output.

A target further off boresite leaves the missile field of view during part of the scan, producing an amplitude-modulated waveform similar to that of a spin scan tracker. The important difference is that with a spin scan tracker, the target never leaves the missile field of view. With con scan, the target may fall outside the missile FOV at certain times during the scan. Because con-scan trackers do not necessarily view the target continuously, they can have high resistance to jammers.

Other types of seeker scan patterns now exist. The Rosette scan pattern shown in Figure 35 is one such example. It has an even higher resistance to countermeasures.



Figure 35. Rosette Scan Pattern.

Imaging arrays of detectors without reticles are newer yet. They may be classified as either staring (every pixel sees the entire scene), or scanning arrays, where the optics plays a role in determining which "pixels" are exposed to optical / IR radiation.

INFRARED COUNTERMEASURE (IRCM)

Flares

Figure 36 shows a Navy F/A-18E Super Hornet aircraft dispensing IRCM flares from its internal flare dispensers. IRCM have been the staple of countermeasures protection for military aircraft more than four decades. Flares are designed to transfer the track of an attacking infrared missile by exhibiting characteristics that confuse the tracking and guidance algorithms built into the missile. Modern missiles incorporate Counter-Countermeasures (CCM) capabilities including hardware configurations, circuitry, and logic to help identify countermeasures and reject them from processing. CCM capabilities can be based on spectral, spatial, and temporal features of the target scene. As missiles continue to improve in their sensitivity, range, maneuverability, and CCM capabilities, flares continue to evolve in order to keep pace with the evolving threat.



Figure 36. Navy F/A-18E Aircraft Dispensing IRCM Flares.

Over the years the Navy has fielded many flare types including the MJU-2/B, MJU-8, MJU-32, MJU-38, MJU-27, MJU-49, and many other improved versions of these flares and other types as well. IRCM flares continue to be the prevailing countermeasure for military aircraft protection by offering cost effective and robust protection.

Dispenser Systems

Most Navy fixed wing and rotary wing aircraft are equipped with countermeasures dispenser systems. These systems are critical to the survivability of the aircraft in a hostile threat environment. Modern dispensers such as the AN/ALE-47 offer high reliability and substantial programming capability that allows flare dispenses to be tailored for maximum protection of the host aircraft type. AN/ALE-47 is highly integrated into the aircraft over the 1553 data buses. The dispenser can incorporate information from several aircraft systems including missile-warning systems to improve its responses to threats and provide vital situational awareness to the aircrew.

Impulse Cartridges

IRCM flares are dispensed from the aircraft flare dispensers with electrically initiated impulse cartridges. Impulse cartridges incorporate energetic materials within a small confined canister. Upon application of a voltage to the electrical leads, a bridge wire in contact with the energetic materials burns through, igniting the propellant materials. The expanding gases push the flare from its case, held captive in the aircraft dispenser. Impulse cartridges for Navy use have been designed to withstand the extreme electro-magnetic environments encountered around aircraft carriers and other combat ships. Examples of impulse cartridges include the CCU-63 and CCU-136.

Infrared Jammers

Several lamp-based and mechanically modulated jammers have been developed over the years for protection of aircraft. Examples include the AN/ALQ-144 and AN/ALQ-157, predominantly used on helicopters and cargo aircraft. These jammers offer some level of protection over a broad field-of-regard and offer the advantage of continuous operation.

In principle, these jammers produce a modulated signal in the track band of the threat that corrupts the target tracking pulses in the missile seeker.

Passive Missile Warning Systems

Infrared-guided weapons provide passive attack capabilities against military vehicles. Unlike a radar-guided weapon that actively emits radiation and tracks the reflected pulses from the target, infrared weapons track radiation already being emitted from the target. Attacking missiles fly at very high speeds, and they are exceptionally maneuverable. Missile warning systems must be capable of detecting the threat, alerting the aircrew, and cueing a countermeasures response within sufficient time to counter the attacking missile. The time from launch to impact can be very short, making timely detection critical. Active warning systems have been developed in the past that use Doppler Radar capabilities to detect missiles, but passive missile warning systems have been preferred because of the desire to minimize emissions from the aircraft under attack.

Several passive missile-warning systems have been developed over the years for military aircraft. These systems operate in a variety of different parts of the electro-optical spectrum, but the most common are ultraviolet and infrared sensor systems. Examples of passive missile warning systems include AN/AAR-47, AN/AAR-54, AN/AAR-57, AN/AAQ-24 (both passive and active components), and the Joint and Allied Threat Awareness System (JATAS), currently under development by the Navy. Passive missile warning sensors continue to improve with advances in detector technologies, particularly with imaging detectors. These sensors provide excellent angle-of-arrival information, necessary to support cueing of laser based countermeasures, and advanced processing to detect and declare threat missiles in cluttered environments.

Laser Countermeasures

Laser-based infrared countermeasures have been in development for many years. Several systems have been fielded over the past fifteen years including the AN/AAQ-24 system on Air Force cargo aircraft and helicopters and a derivative system for Marine Corps helicopters.

Although configurations vary, most of these systems incorporate a single multi-band laser or several single-band lasers that produce modulated waveforms designed to corrupt a missile's guidance target tracking. The laser optics are located in a tracking gimbal that provides agile and rapid pointing over a broad field-of-regard. Laser based countermeasures require a relatively high angle of arrival accuracy from the host aircraft's missile warning sensor. Upon declaration of the threat, the missile warning system hands-off track to the tracking gimbal and cues the lasers to lase. A tracking camera in the tracking gimbal with high optical resolution helps to maintain track on the threat missile through the engagement period.

LASERS

The word laser comes from Light Amplification by Stimulated Emission of Radiation. A laser system emits light that is generated through a process of stimulated emission. The radiation produced by a laser exhibits high temporal and spatial coherence. In order to begin the process of stimulated emission, the lasing medium absorbs the energy from a pump source. The atoms in the lasing medium are excited to a higher energy state. These atoms will eventually return to their ground state. A large number of atoms that are excited to higher states create a population inversion. Population inversion describes the number of atoms in excited state versus the number of atoms in the ground state. In order for the atoms to return to their ground state, they must release energy. This energy is released in the form of photons. Energy of a photon is expressed as

$$E = \frac{hc}{\lambda}$$

Where

E = Energy, generally electron volts (eV)
h = Planck's constant = 4.136 x 10^{-15} (eV·s)
c = speed of light = 2.998 x 10^{8} (m/s)
λ = wavelength of light in meters

The energy that must be released by the atom to return to the ground state will direct the wavelength of the photon emitted since h and c are constants. If all the excited atoms released the same amount of energy to return to their ground state, the released photons would all have the same wavelength and would be considered fully monochromatic. Most lasers do not emit a single wavelength but a range of slightly differing wavelengths (Δλ).

The lasing medium may be a solid, a gas, liquid, or plasma. Some laser types include gas, chemical, dye, fiber-based, solid-state and semiconductor lasers. The laser radiation can be output in a continuous wave (CW) or in a pulsed wave. A continuous wave laser emits light that maintains a steady amplitude and frequency. A pulse wave will vary in amplitude and is also characterized by the systems pulse repetition frequency (PRF). The PRF is defined as the number of pulses emitted during a unit of time. Figure 37 shows the spectral output of several laser types.

The first laser was constructed by Theodore Maiman at Hughes Research Laboratories in Malibu, California. This laser was a pulsed, solid-state ruby laser. The ruby laser uses a synthetic ruby crystal as the lasing medium. A xenon flash lamp is used to excite the atoms in a ruby rod to higher energy levels. The highly polished and mirrored ends of the rod form a resonant cavity. One end of the rod has a slightly lower reflectivity. The lamp excitation produces an inverted population of excited atoms, which are stimulated to relax to lower energy levels releasing their extra energy as photons. Repeated reflections off the mirrored ends of the rod causes the photons to bounce back and forth through the rod stimulating further emissions at the same wavelength and phase producing a highly coherent beam, which finally passes through the lower reflectivity end.



Figure 37. Spectral Lines / Ranges of Available Lasers.

The typical laser rangefinder uses a solid-state laser with a neodymium-YAG crystal lasing at 1.06 μm.

Gas lasers can be pulsed or CW. The gas dynamic laser obtains its inverted population through a rapid temperature rise produced by accelerating the gas through a supersonic nozzle. In chemical lasers the inversion is produced by a chemical reaction. In the electric discharge laser the lasing medium is electrically pumped. The gas can also be optically pumped. In an optically pumped gas laser the lasing medium is contained in a transparent cylinder. The cylinder is in a resonant cavity formed by two highly reflective mirrors.

Many gas lasers use carbon dioxide as the lasing medium (actually a mixture of CO_2 and other gases). These are the basis for most high energy or high power lasers. The first gas laser was an optically pumped CW helium-neon laser. The common laser pointer is a helium-neon laser operating at 0.6328 µm. The lasing medium is a mixture of helium and neon gas in a gas discharge or plasma tube.

The dye laser is an example of a laser using a liquid for the lasing medium. The lasing medium is an organic dye dissolved in a solvent such as ethyl alcohol. Dye lasers operate from the near UV to the near IR, are optically pumped, and are tunable over a fairly wide wavelength range.

Another type of laser is the semiconductor or injection laser, also known as a laser diode. The junctions of most semiconductor diodes will emit some radiation if the devices are forward biased. This radiation is the result of energy released when electrons and holes recombine in the junction. There are two kinds of semiconductor diode emitters: (1) the light emitting diode (LED), which produces incoherent spontaneous emission when forward biased and which has a broad (800 angstrom) spectral output, and (2) the laser diode, which maintains a coherent emission when pulsed beyond a threshold current and which has a narrow spectral width (< 10 angstrom). In the laser diode the end faces of the junction region are polished to form mirror surfaces. They can operate CW at room temperatures, but pulsed operation is more common. Figure 38 shows a typical diode laser structure.



Figure 38. Diode Laser Construction.

Fiber lasers use fibers that are doped with rare-earth elements as the pumping medium. These rare-earth elements include elements such as Erbium (most common), Ytterbium, and Neodymium. There are other elements such as Thulium that are used for doping purposes. Erbium doped fiber lasers can emit in the 1.5 to 1.6 micron wavelength, which is important due to eye safety concerns in this part of the spectrum. Other wavelength emissions for Erbium include 2.7 and 0.55 microns.

Fiber based laser systems are beneficial in many ways. The fiber gain medium is compact compared to many other types of gain medium and is highly efficient. The fiber gain medium can also be physically manipulated to save space. Fiber based lasers are able to achieve high output powers. The gain medium of a fiber laser can extend for several kilometers to achieve these higher power outputs. The fact that the light is already propagating in a flexible fiber can also allow for system designs that implement a gain cavity in one location and then deliver the output in another location.

Q-switching is a common means of obtaining short intense pulses from lasers. The Q-switch inhibits lasing until a very large inverted population builds up. The switch can be active or passive. A passive Q-switch switches at a predetermined level. An active Q-switch is controlled by external timing circuits or mechanical motion. The switch is placed between the rod (or lasing medium) and the 100 percent mirror. Figure 39 shows an arrangement using a Pockels cell as an active Q-switch.



Figure 39. Q-Switch Arrangement.

Other methods of obtaining pulsed operation include using pump sources that are pulsed and mode-locking.

FIBER OPTICS

Fiber optic cables are the optical analog of RF waveguides. Fiber optic cables are made from transparent dielectrics. The fiber optic cable acts as an optical waveguide allowing light to propagate along the length of the fiber by using the principle of total internal reflection. This phenomenon can only occur under certain conditions relating to the material indices of refraction and the light ray's angle of incidence. Some benefits of fiber optic fiber include low losses, bandwidth, electromagnetic interference immunity, size, and weight.

Consider the physical construction of a bare optical fiber, depicted in Figure 40. A bare optical fiber is simply the inner glass core and the surrounding glass sleeve. The core must have a higher index of refraction than the cladding, $n_1 > n_2$. When $n_1 > n_2$, light impinging the boundary between the core and the cladding will totally internally reflect if the incident angle at each reflection is greater than the critical angle, θ_c. $\sin \theta_c = (n_2/n_1)$



Figure 40. Bare Fiber Optic Cable.

Incident rays on the face of the fiber must intersect at angles less than θ_{max} for the internal ray, θ_t, to intersect at θ_c. When rays intersect the front face of the fiber at angles greater than θ_c, they are only partially reflected in the core and will leak out.

There are many varieties of optical fibers. Optical fibers can either be single mode or multimode. Single mode fibers are fibers which propagate a single mode down the length of the fiber while multimode fibers can propagate many modes. Single mode fibers typically have a much smaller core diameter, typically around 8 to 10 µm. Their cladding is usually 125 µm. Multimode fibers typically have core diameters around 62.5 µm with 125 µm claddings. These diameters can vary depending on the application. Loss in multimode fibers over a 1 kilometer distance is typically around 1 dB at 1310 nm. This value will vary some with changes in wavelength. Single mode fibers can maintain the quality of a light pulse over longer distances than multimode fibers due to modal dispersion effects that occur in multimode fibers. Typical losses for a single mode fiber over 1 kilometer is approximately .3 dB at 1310 nm. Again, this value will vary some with changes in wavelength. However, multimode fiber is much less expensive than single-mode and can have a lower connection loss due to the larger core diameter. Multimode fiber is commonly used in communications.

In addition to single mode or multimode, a fiber can have a step index profile or a graded index profile. Figure 41 depicts the two profiles. The step index profile maintains a uniform index of refraction within the core. A graded index profile has a peak index of refraction at the center of the core. The index of refraction value rolls off from the center to lower values closer to the cladding interface. This profile assists with the modal dispersion issue found in multimode fiber.



Figure 41. Fiber Profiles for a Single Mode Step Index and a Multimode Graded-Index Fiber.

Most fiber is not used in a bare form and has some additional layers of protection around the cladding. These layers can include a 250 µm buffer with a 900 µm PVC tight buffer. Some fiber will also contain aramid yarn followed by a 3 mm PVC furcation tube. Buffer tubes are often used to assist with identification and provide damage protection. The outer layers can provide additional isolation from environmental factors and lower optical crosstalk.

There are also more specialized types of fiber that include polarization maintaining and photonic crystal fibers. Polarization maintaining fibers are not constructed with a cylindrical core but instead use elliptical, bow-tie styled cores or stress rods located in the cladding (PANDA style). These are shown in Figure 42.



Figure 42. Polarization Maintaining Optical Fiber Types.

Polarization maintaining fibers maintain the state of the linearly polarized light propagating through the fiber. This type of fiber is used when the polarization state of the light cannot vary within a system. Photonic crystals propagate light by an arrangement of very small and closely spaced air holes that are maintained throughout the length of the fiber. Applications of photonic crystal fibers are varying and can be used in fiber lasers, amplifiers, sensors, and telecom.

It is well known that fiber optics has many communication applications; however, improvements in fiber optic technology have lent themselves to many EO applications. Many EO components are now fiber based and can interface with the tremendous advancements in fiber-based laser systems as well as other EO systems. An example of the use of fiber optics in an EW system is the AN/ALE-50 and 55 Fiber-Optic Towed Decoy (FOTD). The FOTD uses fiber optic cabling to communicate with the jammer.

This page intentionally left blank.

LASER SAFETY

Lasers are divided into the following classes:

Class 1	Low power / non-hazardous
Class 2/2a	Low power / minor controls necessary
	Emit less than 1 mW visible CW radiation. Not considered hazardous for momentary (<0.25 sec) unintentional exposure. Class 2a lasers are those class 2 lasers not intended to be viewed, i.e. supermarket scanners.
Class 3a/3b	Medium power / direct viewing hazard / little diffuse reflection hazard.
Class 3a	Visible lasers with 1-5 mW power output, invisible lasers, and those having 1-5 times the Accessible Emission Limit (AEL) of class 1 lasers.
Class 3b	All other class 3 lasers at all wavelengths which have a power output less than 500 mW.
Class 4	High power / eye & skin hazard / potential diffuse reflection hazard or fire hazard

There are several pertinent instructions and guidelines regarding laser use. They are:

- OPNAVINST 5100.27B Navy Laser Hazards Control Program
  (which replaced OPNAVINST 5100.27A and SPAWARINST 5100.12B)
- MIL-HDBK-828B, Range Laser Safety
- ANSI Z136.1-2007, American National Standard for the Safe Use of Lasers (Parent)

Every Navy command which uses lasers must have a Laser System Safety Officer (LSSO). All LSSOs must attend a Navy LSSO course.

There are four categories of LSSOs.

- Administrative Laser Safety Officer (ALSO)
- Technical Laser Safety Officer (TLSO)
- Laser Safety Specialist (LSS)
- Range Laser Safety Specialist (RLSS)

See OPNAVINST 5100.27B for details of their qualifications and responsibilities.

The hazard ranges of interest are the NOHD for direct viewing of a beam and the $r_{1(safe)}$ or $r_{2(safe)}$ for viewing a beam reflected off an object such as a wall. These are depicted in Figure 1. The Maximum Permissible Exposure (MPE) values present laser safety levels as a function of exposure time, laser PRF, pulse duration, and wavelength. Different tables are used for eye safety while directly viewing a beam, for viewing a diffusely reflected beam, and for skin exposure.

For repeated pulses the following equation is used to calculate the maximum permissible exposure (MPE).

$$\text{MPE (repeated pulse)} = \frac{MPE(single\ pulse)}{(\,PRF\ x\ t_e\,)^{1/4}} \qquad \textbf{[1]}$$

Where PRF is the pulse repetition frequency of the laser and t_e is the exposure duration.

For visible lasers t_e is usually taken as 1/4 second and for non-visible lasers a value of 10 seconds is used.

Figure 1 depicts some laser hazard distances.


Nominal Ocular Hazard Distance (NOHD)
LASER
Φ
BEAM
NOHD
EYE
Diffuse Reflection Hazard
Reflecting Surface
LASER
BEAM
r (diffuse)
EYE
r1

Figure 1. Laser Hazard Distances.

Range laser safety specialists shall be designated for external operations. Range test plans shall specify:

- Permissible aircraft flight paths, and ship or vehicle headings.
- Hazard areas to be cleared.
- Operational personnel locations.
- Types of surveillance to be used to ensure a clear range.
- Radio / communications procedures.

During laser operations no portion of the laser beam may extend beyond the controlled target area unless adequate surveillance can prevent radiation of unprotected areas. Class 3 and class 4 lasers shall not be directed above the horizon unless coordinated with those responsible for the given airspace (FAA, Navy, Air Force, etc).

In an industrial environment, warning and hazard signs and lights will be posted, a hazard zone shall be designated when lasers are in operation, and training shall be provided to operators in the proper eye and body (skin) protection required. Interlocks to laser operation shall be provided when there is the possibility of unauthorized personnel entering the hazard area.

Fiber optic cables usually have laser power sources so appropriate warnings or labels need to be applied to connections or possible breakage points.

This page intentionally left blank.

AIRCRAFT DYNAMICS CONSIDERATIONS

Free Fall / Aircraft Drag....8-1
Mach Number and Airspeed vs. Altitude....8-2
Maneuverability 8-3
EMP / Aircraft Dimensions....8-4

This page intentionally left blank.

FREE FALL / AIRCRAFT DRAG

The purpose of this section is to get an awareness of the distance traveled by a flare or other object such as a bomb, which is jettisoned or dropped by an aircraft. This will give the reader an appreciation for the significance of aircraft tactical altitude.

From Newton's second law of motion:

$$F = m_o a$$

where: F = Force
m_o = Mass of object
a = Acceleration

and the law of gravitation:

$$F = G\frac{m_o m_e}{r^2}$$

where:		English Units	SI Units
	F = Force of attraction	lb_f	Newton
	G = universal gravitational constant	$3.44\text{x}10^{-8}\ ft^4/lb\text{-}sec^4$	$6.67\text{x}10^{-11}\ m^3/kg\text{-}sec^2$
	m_o, m_e= Masses (not weight) of object & earth	slug	kg
	r = distance between center of gravity of objects	feet	meter

Combining the two equations and solving for "a":

$$a = \frac{G\,m_e}{r^2} = g$$

, the familiar constant acceleration due to gravity.

Since G and m_e are fixed and the variation in r (the distance from the earth's center) is small except for satellites, "g" is considered fixed at 32.2 ft/sec^2.

For objects with a constant acceleration (g), it can be shown that:

$$d = v_i t + \frac{1}{2}gt^2$$

where
d = distance traveled
v_i = Initial velocity
t = time
g = acceleration

For a falling object, Figure 1 on the following page may be used to estimate time/distance values.

- The upper curve is for an object shot upward with an initial velocity of 50 ft/sec.
- The middle curve is for an object shot horizontally with an initial velocity of 50 ft/sec or one that is a free-falling object dropped with no initial vertical velocity.
- The lower curve is for an object with a downward initial velocity of 50 ft/sec.

Notes:

1) 50 ft/sec is the typical cartridge ejection velocity of a flare/chaff expendable.
2) The top curve actually goes up 39 feet before starting back down, but this is difficult to see due to the graph scale.
3) This simplification ignores the effects of air drag or tumbling effects on a falling object which will result in a maximum terminal velocity, with resultant curve straightening.



Figure 1. Object Fall Rate.

SAMPLE CALCULATIONS

Let us assume that we want to know how far a bomb or other object has fallen after 13 seconds if it had been dropped from an aircraft traveling at 450 kts which was in a 40° dive.

Our initial vertical velocity is: 450 kts (Sin 40°) (1.69 ft/sec per knot) = 489 ft/sec downward

$d = V_it + ½gt^2 = -489(13) + ½(-32.2)(13)^2 = - 6355 - 2721 = -9{,}076$ ft.

Remember to keep the signs (+/-) of your calculations in agreement with whatever convention you are using. Gravity pulls downward, so we used a minus sign for acceleration. Also the initial velocity was downward.

In reality, any object may well have reached terminal velocity before the time indicated using the above formula or Figure 1. In this example, the actual distance determined from ballistics tables would have been 8,000 ft, which is about 13% less than the above calculation would indicate. The drag characteristics of the object determine how much shorter the distance will be. In any case, it will not have dropped farther.

AIRCRAFT DRAG INDEX POINTS

Tactical aircraft carry stores in various combinations depending upon the mission. Each store has a different drag load which affects range. The pilot needs to know the total drag load in order to determine his aircraft range on a particular mission. Adding up the total drag in pounds of force for wind resistance would be cumbersome. Therefore, the drag of the stores is compared to a known reference drag (usually the aircraft), and expressed as a percentage of aircraft drag multiplied by some constant. This ratio is variously called drag count, drag index, or drag points. For instance, if a missile has 100 pounds of drag and the reference aircraft drag is 50,000 pounds, the ratio is 100/50,000 = 0.002. Multiply this by a constant of 100 (for example) and the drag index point is 0.2. The pilot only needs to look on a chart to see what the drag index points are for his stores, add up the drag points, and look on a chart to see what his aircraft range and best range (or endurance) speed will be.

This page intentionally left blank.

MACH NUMBER and AIRSPEED vs. ALTITUDE

MACH NUMBER is defined as a speed ratio, referenced to the speed of sound, i.e.

$$MACH\ NUMBER = \frac{Velocity\ of\ Interest}{Velocity\ of\ Sound} \quad (at\ the\ given\ atmospheric\ conditions) \qquad \textbf{[1]}$$

Since the temperature and density of air decreases with altitude, so does the speed of sound, hence a given true velocity results in a higher MACH number at higher altitudes.

AIRSPEED is a term that can be easily confused. The unqualified term airspeed can mean any of the following:

a. Indicated airspeed (IAS) - the airspeed shown by an airspeed indicator in an aircraft. Indicated airspeed is expressed in knots and is abbreviated KIAS.

b. Calibrated airspeed (CAS) - indicated airspeed corrected for static source error due to location of pickup sensor on aircraft. Calibrated airspeed is expressed in knots and is abbreviated KCAS. Normally it doesn't differ much from IAS.

c. True airspeed (TAS) - IAS corrected for instrument installation error, compressibility error, and errors due to variations from standard air density. TAS is expressed in knots and is abbreviated KTAS. TAS is approximately equal to CAS at sea level but increases relative to CAS as altitude increases. At 35,000 ft, 250 KIAS (or KCAS) is approximately 430 KTAS.

IAS (or CAS) is important in that aircraft dynamics (such as stall speed) responds largely to this quantity. TAS is important for use in navigation (True airspeed ± wind speed = ground speed).

Figures 1 and 2 depict relations between CAS and TAS for various altitudes and non-standard temperature conditions. The first graph depicts lower speed conditions, the second depicts higher speeds.

As an example of use, consider the chart on the next page. Assume we are in the cockpit, have read our IAS from the airspeed indicator, and have applied the aircraft specific airspeed correction to obtain 370 KCAS. We start at point "A" and go horizontally to our flight altitude at point "B" (25,000 ft in this case). To find our Mach, we go down vertically to point "C" to obtain 0.86 Mach. To get our TAS at our actual environmental conditions, we go from point "B" vertically until we hit the Sea Level (S.L.) reference line at point "D", then travel horizontally until we reach our actual outside air temperature (-20°C at altitude) at point "E", then go up vertically to read our actual TAS from the scale at point "F" (535 KTAS). If we wanted our TAS at "standard" temperature and pressure conditions, we would follow the dashed lines slanting upward from point "B" to point "G" and read 515 KTAS from the scale. Naturally, we could go into the graph at any point and go "backwards" to find CAS from true Mach or TAS.

Figure 3 shows a much wider range of Mach numbers. It contains only TAS and Mach, since aircraft generally do not fly above Mach 2, but missiles (which don't have airspeed indicators) do. The data on this graph can be obtained directly from the following formula for use at altitudes of 36,000 ft and below:

$$Speed\ of\ Sound\ (KTAS) = 29.06\sqrt{518.7 - 3.57\ A} \qquad Where\ A = altitude\ (K\ ft) \qquad \textbf{[2]}$$

The speed of sound calculated from this formula can be used with the equation on the first page to obtain Mach number. This equation uses the standard sea level temperature of 59° F and a lapse rate of -3.57°/1000 ft altitude. Temperature stabilizes at -69.7° F at 36,000 ft so the speed of sound stabilizes there at 573 knots. See the last page of this section for a derivation of equation [2].



Figure 1. TAS and CAS Relationship With Varying Altitude and Temperature.



Figure 2. TAS and CAS Relationship With Varying Altitude and Temperature (Continued).



Figure 3. Mach Number vs. TAS Variation With Altitude.

The following is a derivation of equation [2] for the speed of sound:

Given: p = pressure (lb/ft^2)
v = specific volume (ft^3/lb)
R = a constant (for air: R = 53.3)
T = absolute temperature (°Rankine) = °F + 459.7
w = specific weight (lb/ft^3) = $1/v$
ρ = density = $w/\mathrm{g} = 1/\mathrm{g}v \;\therefore\; v = 1/\mathrm{g}\rho$

From Boyle's law of gasses: $pv = \mathrm{RT}$, therefore we have: $p/\rho = \mathrm{gRT} = (32.2)(53.3)\mathrm{T} = 1718\ \mathrm{T}$ **[3]**

It can also be shown that: p/ρ^{γ} = constant; for air $\gamma = 1.4$ **[4]**

From the continuity equation applied to a sound wave: $\rho \mathrm{AV_a} = (\rho + \mathrm{d}p)\mathrm{A}(\mathrm{V_a} + \mathrm{dV_a})$ **[5]**

Expanding and dropping insignificant terms gives: $\mathrm{dV_a} = -\mathrm{V_a}\, \mathrm{d}\rho/\rho$ **[6]**

Using Newton's second law ($p + \rho \mathrm{V_a}/2$ = a constant) and taking derivatives: $\mathrm{d}p = -\rho \mathrm{V_a dV_a}$

Substituting into [6] gives: $\mathrm{V_a}^2 = \mathrm{d}p/\mathrm{d}\rho$ **[7]**

Then taking derivatives of [4] and substituting in [7] gives: $V_a = \sqrt{\dfrac{\gamma p}{\rho}}$ **[8]**

Then using [3] gives: $V_a = \sqrt{\gamma gRT} = \sqrt{1.4(1718)T} = 49\sqrt{T}$ **[9]**

Using a “Standard” atmosphere of 59° F @ Sea Level (S.L.) and a lapse rate of -3.57°/1000 ft altitude:

$$V_a = 49\sqrt{459.7+59-3.57\,A}\,\frac{ft}{\text{sec}}\left[\frac{3600\,\text{sec}}{hr}\,\frac{nm}{6076\;ft}\right] = 29.06\sqrt{518.7-3.57A} \quad \text{which is equation [2]}$$

MANEUVERABILITY

A useful function is to determine how many “G’s” an aircraft might require to make a given turn without altitude loss. From Newton’s laws, F cos φ = W, where: F = force applied to an aircraft, W = weight, and φ = bank angle. By definition “G’s” is the ratio of the force on an object to its weight, i.e., G = F/W = 1/cos φ.

Simple calculations will show the results presented in Table 1, to the right.

Given that the average structural limit of an aircraft is about 7 G’s, the maximum bank angle that can be achieved in level (non-descending) flight is 81.8°.

Table 1. G vs. Angle of Bank.
(No altitude loss)

G	φ
1.0	0
1.4	45
2.0	60
3.9	75
7.2	82
11.5	85

Figure 1 can be used to determine the turn radius and rate-of-turn for any aircraft, given speed and angle of bank (assuming the aircraft maintains level flight). It may also be used in the reverse context. It should be noted that not all aircraft can fly at the speeds depicted - they may stall beforehand or may be incapable of attaining such speeds due to power/structural limitations.

In the example shown on Figure 1, we assume an aircraft is traveling at 300 kts, and decides to make a 30° angle of bank turn. We wonder what his turn radius is so we can approximate his flight path over the ground, and what his rate of turn will be. We enter the chart at the side at 300 kts and follow the line horizontally until we intercept the 30° “bank angle for rate of turn” line. We then go down vertically to determine the 2.10°/sec rate of turn. To get radius, we continue horizontally to the 30° “bank angle for turn radius” line. We can then go down vertically to determine the radius of 13,800 ft.



Figure 1. Aircraft Turn Rate / Radius vs. Speed.

The exact formulas to use are:

$$Rate\ of\ Turn = \frac{1091 \tan(\phi)}{V} \qquad Radius\ of\ Turn = \frac{V^2}{11.26 \tan(\phi)} \qquad Where: \begin{array}{l} V = Velocity\ (Knots) \\ and\ \phi = Angle\ of\ Bank \end{array}$$

Another interesting piece of information might be to determine the distance a typical aircraft might travel during a maneuver to avoid a missile.

Figure 2 shows a birds-eye view of such a typical aircraft in a level (constant altitude) turn.



ASSUME:
Vac = 400 Kts & is pulling 7 G's in turn

From Table 1:
Angle of bank = 82°

From Figure 1:
Rate of Turn (ROT) = 18°/sec
Radius of Turn = 2100 ft

In 5 sec turning, the plane will have turned 90°, in 10 sec it will have turned 180°

In 5 sec without turning, the plane will have traveled 3333 ft, in 10 sec it will have traveled 6666 ft.

Figure 2. Maneuvering Aircraft.

To counter many air-to-air missiles the pilot might make a level turn, however in countering a SAM, altitude is usually lost for two reasons: (1) the direction of maneuvering against the missile may be downward, and (2) many aircraft are unable to maintain altitude without also losing speed. These aircraft may have insufficient thrust for their given weight or may be at too high an altitude. The lighter an aircraft is (after dropping bombs/burning fuel), the better the performance. Likewise, the higher the altitude, the poorer the thrust-to-weight ratio. Maximum afterburner is frequently required to maintain altitude at maximum "G" level.

REFERENCE AXES (Roll, Pitch, Yaw)

The rotational or oscillating movement of an aircraft, missile, or other object about a longitudinal axis is called roll, about a lateral axis is called pitch, and about a vertical axis is called yaw as shown in Figure 3.



Figure 3. Reference Axes.

SAMPLE CALCULATIONS

If we want to determine the rate of turn or turn radius more precisely than can be interpolated from the chart in Figure 1, we use the formulas. For our initial sample problem with an aircraft traveling 300 kts, in a 30° angle of bank turn, we have:

$$Rate\ of\ Turn = \frac{1091\tan(\phi)}{V} = \frac{1091\tan(30)}{300} = 2.1°/\sec$$

$$Radius\ of\ Turn = \frac{V^2}{11.26\tan(\phi)} = \frac{300^2}{11.26\tan(30)} = 13{,}844\ ft$$

These are the same results as we determined using Figure 1.

This page intentionally left blank.

EMP / AIRCRAFT DIMENSIONS

An aircraft flying in the vicinity of an electromagnetic pulse (EMP) acts like a receiving antenna and picks up EMP radiation in relation to size like a dipole (or half-wavelength dipole). The electromagnetic pulse spectrum decreases above 1 MHz as shown in Figure 1, so an F-14 aircraft that is an optimum ½ wavelength antenna at ≈8 MHz will pick up less EMP voltage than a B-52 or an aircraft with a trailing wire antenna. A rule of thumb for the voltage picked up is:

V_{EMP} = 8.1 volts/ft times the maximum dimension of the aircraft in feet

This rule of thumb was generated because a single linear relationship between voltage and aperture seemed to exist and compared favorably with more complex calculations for voltage picked up by various aircraft when subjected to EMP.

Table 1 shows various aircraft and the frequencies they would be most susceptible to, using $f = c/\lambda$, where λ matches the selected aircraft dimension for maximum "antenna reception effect." This should be a design consideration when trying to screen onboard avionics from the effects of EMP.

The following is a partial listing of aircraft types vs. identifying prefix letters (several are used in Table 1):

A	Attack	K	Tanker	T	Trainer
B	Bomber	O	Observation	U	Utility
C	Cargo	P	Patrol	V	Vertical or Short Takeoff and Landing (V/STOL)
E	Electronic Surveillance	Q	Special mission	X	Experimental
F	Fighter	R	Reconnaissance	Y	Prototype
H	Helicopter	S	Anti Sub/Ship		



Figure 1. EMP as a Function of Frequency.

Table 1. Aircraft Dimensions and Equivalent Antenna Aperture.

Mission	Aircraft Type	Height (ft.)	Frequency (MHz)		Length (ft.)	Frequency (MHz)		Wing Span (ft.)	Frequency (MHz)	
		A	f	f/2	A	f	f/2	A	f	f/2
ATTACK	A-10	14.66	67.05	33.52	53.33	18.43	9.21	57.5	17.1	8.55
ELECTRONIC WARFARE	EA-6B	16.50	59.64	29.82	59.34	16.58	8.29	53.0	18.57	9.29
	EA-18	16.0	61.47	30.74	60.17	16.35	8.17	44.67	22.02	11.01
FIGHTER	F-15	18.4	53.42	26.71	63.75	15.42	7.71	42.8	22.97	11.48
	F-16	16.66	59.00	29.5	49.25	19.96	9.98	31.0	31.71	15.85
	F/A-18C/D	15.3	64.31	32.16	56.0	17.57	8.79	40.70	24.18	12.09
	F/A-18E/F	16	61.47	30.7	60.17	16.34	8.17	44.67	22.02	11.01
	F-22	17.75	55.41	27.7	64.17	15.33	7.66	43	22.87	11.43
	F-35A	14.2	69.27	34.63	51.4	19.1	9.57	35	28.1	14.05
	F-35C	15.5	63.45	31.73	51.4	19.1	9.57	43	22.8	11.43
	F-117	12.42	79.15	39.57	65.92	14.91	7.46	43.33	22.69	11.34
ASW	P-3C	33.75	29.16	14.58	116.42	8.45	4.23	99.67	9.87	4.94
	S-3A	22.75	43.25	21.63	54.34	18.45	9.23	68.67	14.33	7.17
	P-8	42.1	23.36	11.68	129.5	7.6	3.8	123.6	7.96	3.98
AEW	E-2C	18.4	53.48	26.74	56.50	17.42	8.71	80.58	12.21	6.11
V/STOL	AV-8B	11.64	84.45	42.23	46.3	21.23	10.62	30.3	32.44	16.22
	V-22	18.1	54.3	27.2	57.3	17.17	8.58	84.5	11.64	5.82
	F-35B	15.0	65.6	32.78	51.2	19.2	9.61	35	28.1	14.05
HELICOPTERS	AH-1W	14.16	69.46	34.73	58.25	16.89	8.44	48.0	20.49	10.24
	UH-1E	12.75	71.18	35.59	52.91	18.60	9.30	44.0	22.36	11.18
	U/SH-2	15.41	63.85	31.93	52.5	18.74	9.37	44.0	22.36	11.18
	SH-3D	16.42	59.93	29.97	72.67	13.54	6.77	62.00	15.87	7.84
	CH-46D	16.75	58.75	29.38	84.34	11.67	5.84	50.0	19.68	9.84
	CH-47	18.75	52.45	26.23	99.0	9.94	4.98	60.0	16.39	8.19
	CH-53A	24.91	39.50	19.75	88.16	11.16	5.58	72.25	13.62	6.81
	SH-60	17.0	57.85	28.93	64.83	15.17	7.59	53.83	18.27	9.14
	AH-64	15.25	64.5	32.25	58.25	16.89	8.44	48.0	20.49	10.24
TRANSPORT	C-2A	15.92	61.81	30.91	56.6	17.39	8.70	80.58	12.21	6.11
TANKERS	KC-130F	38.1	25.83	12.92	97.8	10.06	5.03	132.5	7.43	3.72
SPECIAL ELECTRONICS	EC-13OQ	38.5	25.56	12.78	99.34	9.91	4.96	132.58	7.42	3.71
TRAINER	T-2B	14.8	66.49	33.25	38.7	25.43	12.72	37.85	26.00	13.0
	T-39D	16.0	61.50	30.75	43.75	22.49	11.25	44.34	22.19	11.10
	T-45	13.5	72.86	36.43	39.33	25.0	12.5	30.8	31.93	15.97

DATA TRANSFER BUSSES

Data Busses 9-1
RS-232 Interface 9-2
RS-422 Balanced Voltage Interface 9-3
RS-485 Interface 9-4
IEEE-488 Interface Bus (HP-IB/GP-IB) 9-5
MIL-STD-1553 & 1773 Data Bus 9-6
Ethernet 9-7
Transmission Control Protocol / Internet Protocol 9-8

This page intentionally left blank.

DATA BUSSES

INTRODUCTION

The avionics systems on aircraft frequently contain general purpose computer components which perform certain processing functions, then relay this information to other systems. Some common examples are the mission computers, the radar processors, RWRs, and jammers. Each system is frequently laid out as shown in Figure 1.



Figure 1. Avionics Block Diagram.

The Input/Output (I/O) modules will vary in function, but all serve the same purpose - to translate the electrical signals from one protocol to one of another in order to exchange information. I/O modules are used similarly in general purpose computers in laboratories to test equipment and/or tie computers together via a local area network (LAN) to exchange information. Some of the methodologies include a star, ring, or bus type network (see terminology at the end of this section).

A number of network "models" exist for describing the functions, interfaces and protocols involved in network data interchange. Regardless of the descriptive model used, all strive toward the same end and none actually changes the detailed implementation. Table 1 shows the layer names and the number of layers of networking models presented in Internet Engineering Task Forces (IETF) Request For Comments (RFCs) and in common use by textbooks.

Table 1. Some Common Network Architecture Models.

IETF-RFC 1122	**Kurose, Forouzan**	**Comer, Kozierok**	**Stallings**	**Cisco Academy**
Four layer Internet model	*Five-layer Internet model or TCP/IP protocol suite*	*TCP/IP 5-layer reference model*	*Five layer TCP/IP model*	*Four layer Internet model*
Application	Application	Application	Application	Application
Transport	Transport	Transport	Host-to-host or transport	Transport
Internet	Network	Internet	Internet	Internetwork
Link	Data link	Data link (Network interface)	Network access	Network interface
	Physical	(Hardware)	Physical	

These textbooks are secondary sources that may be contrary to the intent of RFC 1122 and other primary sources such as the Open Systems Interconnection (OSI) Reference Model developed by the International Organization for Standardization (ISO).

The OSI Reference Model is a more general description for layered communications and computer network protocol design. The IETF makes no effort to follow the OSI model although RFCs sometimes refer to it. The description of the OSI layers is shown in Table 2.

Table 2. OSI Reference Model.

	Name	Use	Misc Example	IP Suitte
7	APPLICATION	Meaning of data	HL7, Modbus	DHCP, DNS, FTP, Gopher, HTTP, NTP, SMTP, SNMP, Telnet
6	PRESENTATION	Building blocks of data and encryption	ASCII, EBCDIC, MIDI	MIME, XDR, SSL
5	SESSION	Opening and closing of specific communication paths	NetBIOS, SAP, Half Duplex, Simplex, SDP	NetBIOS, RTP, SAP
4	TRANSPORT	Error checking	NBF	PPTP, SCTP, TCP, UDP
3	NETWORK	Determination of data paths within the network	NBF, Q.931, IS-IS	IP, ICMP
2	DATA LINK	Data transmission, source, destination, and checksum	802.3 (Ethernet), PPP 802.11a/b/g/n MAC, FDDI	ARP, PPP, PPTP, SLIP
1	PHYSICAL	Voltage levels, signal connections, wire, or fiber	RS-232, 10Base-T, 802.11a/b/g/n Physical	

A layer is a collection of conceptually similar functions that provide services to the layer above it and receives service from the layer below it. On each layer an instance provides services to the instances at the layer above and requests service from the layer below. For example, a layer that provides error-free communications across a network provides the path needed by applications above it, while it calls the next lower layer to send and receive packets that make up the contents of the path. Conceptually two instances at one layer are connected by a horizontal protocol connection on that layer.

Most networks do not use all layers. For example, RS-232 is only a physical layer. Ethernet is only layers 1 and 2. TCP/IP is a protocol, not a network, and uses layers 3 and 4 regardless of whether layers 1 and 2 are a telephone line, wireless connection, or 10Base-T Ethernet cable.

Most of the sections in this division discuss the lowest (physical) layer of communication. There are, however, several more areas of general interest which are included in later sections such as Ethernet and TCP/IP. These are used in general purpose computers like the desktop PC or lab networks, and are not commonly used in aircraft.

The typical high-speed data busses on avionics/computers do not operate as fast as the CPU clock speed, but they are much faster than the interface busses they connect to. There are a number of interface busses (physical layer in network model) which are widely used by aircraft, avionics systems and test equipment. The most common include the RS-232, the RS-422, the RS-485, the IEEE-488 (GP-IB/HP-IB) and the MIL-STD-1553A/B. The MIL-STD-1773 bus is a fiber optic implementation of the 1553 bus and may be used in the future when technology requires it to reduce susceptibility to emissions or other reasons.

A summary of these more common types follows in Table 3, which includes a brief descriptive comparison, while a section covering each in more detail is provided later.

Table 3. Summary of Physical Bus Characteristics.

Bus	**Max Length**	**Max Number of Terminals**$^{(1)}$	**Type**	**# of Lines**$^{(2)}$	**Data Rate**	**Rise Time**$^{(3)}$	**Data Format**
RS-232C	100 feet max 50 ft at 20k bps	1	Serial	3-20	150 - 19,200 baud per sec		5- to 8- bit serial
RS-422	1.2 km$^{(4)}$	10$^{(5)}$	Serial	3	see figure in RS-232 section	$<0.1\ T_b$	unspecified
RS-485	unspecified	32	Serial	3	10 MHz	$<0.3\ T_b$	unspecified
IEEE-488 (GP-IB/HP-IB)	20 meters	14	Parallel	16	500 kHz$^{(6)}$		8-bit parallel
HP-IL	100 meters	30	Serial	2	20 k BPS		serial
MIL-STD-1553B MIL-STD-1773	300 feet N/A	32$^{(7)}$	Serial	3	1 MHz	100-300 ns	20-bit serial

NOTES FROM TABLE:

(1) Max Number of Terminals does not include the bus controller.

(2) Including ground/shield

(3) T_b = time duration of the unit interval at the applicable data signaling rate (pulse width)

(4) Length is function of data signaling rate influenced by the tolerable signal distortion, amount of longitudinally coupled noise and ground potential difference introduced between the controller and terminal circuit grounds as well as by cable balance. See RS-422 section for graph.

(5) Physical arrangement of multiple receivers involves consideration of stub line lengths, fail-safe networks, location of termination resistors, data rate, grounding, etc.

(6) Rate can go up to 1 MHz if special conventions are followed.

(7) Max Number of Terminals includes terminal reserved for broadcast commands.

BUS TERMINOLOGY

10BASE-T: Standard “Plain Vanilla” Ethernet based on Unshielded Twisted Pair wire

10BASE-F: 10Mbps fiber optic Ethernet

100BASE-T: Standard “Fast Ethernet” based on twisted pair copper wire

ADDRESS: A unique designation for the location of data or the identity of an intelligent device; allows each device on a single communications line to respond to its own message.

ASCII (American Standard Code for Information Interchange): Pronounced asky. A seven-bit-plus-parity code established by ANSI to achieve compatibility between data services.

ASYNCHRONOUS OPERATION: Asynchronous operation is the use of an independent clock source in each terminal for message transmission. Decoding is achieved in receiving terminals using clock information derived from the message.

BAUD: Unit of signaling speed. The speed in baud is the number of discrete events per second. If each event represents one bit condition, baud rate equals bits per second (BPS). When each event represents more than one bit, baud rate does not equal BPS.

BIT: Contraction of binary digit: may be either zero or one. A binary digit is equal to one binary decision or the designation of one or two possible values of states of anything used to store or convey information.

BIT RATE: The number of bits transmitted per second.

BRIDGE: A network bridge connects multiple network segments at the data link layer (layer 2) of the OSI model, and the term layer 2 switch is very often used interchangeably with bridge. Bridges are similar to repeaters or network hubs, devices that connect network segments at the physical layer; however, with bridging, traffic from one network is managed rather than simply rebroadcast to adjacent network segments.

BROADCAST: Operation of a data bus system such that information transmitted by the bus controller or a remote terminal is addressed to more than one of the remote terminals connected to the data bus.

BUS CONTROLLER: The terminal assigned the task of initiating information transfers on the data bus.

BUS MONITOR: The terminal assigned the task of receiving bus traffic and extracting selected information to be used at a later time.

BYTE: A binary element string functioning as a unit, usually shorter than a computer “word.” Eight-bits per byte are most common. Also called a “character.”

COMMAND/RESPONSE: Operation of a data bus system such that remote terminals receive and transmit data only when commanded to do so by the bus controller.

CRC: Cyclic Redundancy Check; a basic error-checking mechanism for link-level data transmissions; a characteristic link-level feature of (typically) bit-oriented data communications protocols. The data integrity of a received frame or packet is checked by an algorithm based on the content of the frame and then matched with the result that is performed by a sender and included in a (most often, 16-bit) field appended to the frame.

CROSSOVER CABLE: Cable with transmit/receive pairs reversed so one computer or hub or switch can link directly to another.

DATA BUS: Whenever a data bus or bus is referred to in MIL-STD-1553B, it shall imply all the hardware including twisted shielded pair cables, isolation resistors, transformers, etc., required to provide a single data path between the bus controller and all the associated remote terminals.

DCE (Data Communications Equipment): Devices that provide the functions required to establish, maintain, and terminate a data-transmission connection; e.g., a modem.

DHCP: Dynamic Host Configuration Protocol - permits auto-assignment of temporary IP addresses for new devices logging in

DNS: Domain Name Server - associates names with IP addresses

DTE (Data Terminal Equipment): Devices acting as data source, data sink, or both.

DUPLEX: Communication traveling between two nodes in both directions

DYNAMIC BUS CONTROL: The operation of a data bus system in which designated terminals are offered control of the data bus.

EIA (Electronic Industries Association): A standards organization in the U.S.A. specializing in the electrical and functional characteristics of interface equipment.

FDM (Frequency-Division Multiplexer: A device that divides the available transmission frequency range into narrower banks, each of which is used for a separate channel.

FDX (Full Duplex): Simultaneous, two-way, independent transmission in both directions (4-wire).

FTP: File Transfer Protocol - the most popular mechanism for bulk movement of files on TCP/IP.

GATEWAY: Device which links Ethernet to dissimilar networks and transfers data at the application layer level. Interface cards link the PC to Ethernet via the PCI, ISA, PCMCIA, PC/104, or other buses.

GPIB: General Purpose Interface Bus (see section 9-5),

HALF DUPLEX: Operation of a data transfer system in either direction over a single line, but not in both directions on that line simultaneously.

HANDSHAKING: Exchange of predetermined signals between two devices establishing a connection. Usually part of a communications protocol.

HPIB / HPIL: Hewlett-Packard Interface Bus / Hewlett-Packard Interface Loop

HUB: The simplest method of redistributing data, are "dumb," not interpreting or sorting messages that pass through them. A hub can be as simple as an electrical buffer with simple noise filtering. It isolates the impedances of multiple spokes in a star topology. Some hubs also have limited store-and-forward capability. They indiscriminately transmit data to all other devices, which are still on the same collision domain, connected to the hubs. They are not assigned MAC addresses or IP addresses.

IEEE (Institute of Electrical and Electronic Engineers): An international professional society that issues its own standards and is a member of ANSI and ISO.

IP: Internet Protocol portion of TCP/IP. It is a protocol used for communicating data across a packet-switched network.

IP ADDRESS: Address of a TCP/IP enabled device on an Intranet or Internet – in the form xxx.xxx.xxx.xxx, where xxx is an integer between 0 and 255.

LAN: Local Area Network

MAC: Media Access Control - the physical components which disassemble Ethernet message fames

MANCHESTER ENCODING: Digital encoding technique (specified for the IEEE 802.3 Ethernet baseband network standard) in which each bit period is divided into two complementary halves; a negative-to-positive (voltage) transition in the middle of the bit period designates a binary "1," while a positive-to-negative transition represents a "0." The encoding technique also allows the receiving device to recover the transmitted clock from the incoming data stream (self-clocking).

MESSAGE: A single message is the transmission of a command word, status word, and data words if they are specified. For the case of a remote terminal to remote terminal (RT to RT) transmission, the message shall include the two command words, the two status words, and data words.

MODE CODE: A means by which the bus controller can communicate with the multiplex bus related hardware, in order to assist in the management of information flow.

MODEM (Modulator-Demodulator): A device used to convert serial digital data from a transmitting terminal to a signal suitable for transmission over a telephone channel, or to reconvert the transmitted signal to serial digital data for acceptance by a receiving terminal.

MULTIPLEXOR (also Multiplexer): A device used for division of a transmission into two or more subchannels, either by splitting the frequency band into narrower bands (frequency division) or by allotting a common channel to several different transmitting devices one at a time (time division).

NETWORK: An interconnected group of nodes; a series of points, nodes, or stations connected by communications channels; the assembly of equipment through which connections are made between data stations.



NODE: A point of interconnection to a network. Normally, a point at which a number of terminals or tail circuits attach to the network.

PARALLEL TRANSMISSION: Transmission mode that sends a number of bits simultaneously over separate lines (e.g., eight bits over eight lines) to a printer. Usually unidirectional.

PHASE MODULATION: One of three ways of modifying a sine wave signal to make it "carry" information. The sine wave or "carrier" has its phase changed in accordance with the information to be transmitted.

PING: Packet Inter Net Groper - very useful utility which probes for the existence of a TCP/IP host

POLLING: A means of controlling devices on a multipoint line.

PORT: A number in TCP/IP to which services are assigned; e.g. FTP is port 21; SMTP is port 25; HTTP is port 80.

PROTOCOL: A formal set of conventions governing the formatting and relative timing of message exchange between two communicating systems.

PULSE CODE MODULATION (PCM): The form of modulation in which the modulation signal is sampled, quantized, and coded so that each element of information consists of different types or numbers of pulses and spaces.

REMOTE TERMINAL (RT): All terminals not operating as the bus controller or as a bus monitor.

REPEATER: Buffer which cleans up, strengthens and re-transmits a signal.

ROUTER: Repeater which selectively re-distributes messages based on IP address

SERIAL TRANSMISSION: The most common transmission mode; in serial, information bits are sent sequentially on a single data channel.

SNMP: Simple Network Management Protocol; allows monitoring and management of a network.

SOCKET: Specific instance of an IP address and Port number that represents a single connection between two applications.

STAR TOPOLOGY: Topology which allows only one device at each end of a wire and requires repeaters for more than two devices.

STUBBING: Stubbing is the method wherein a separate line is connected between the primary data bus line and a terminal. The direct connection of stub line causes a mismatch which appears on the waveforms. This mismatch can be reduced by filtering at the receiver and by using bi-phase modulation. Stubs are often employed not only as a convenience in bus layout but as a means of coupling a unit to the line in such a manner that a fault on the stub or terminal will not greatly affect the transmission line operation. In this case, a network is employed in the stub line to provide isolation from the fault. These networks are also used for stubs that are of such length that the mismatch and reflection degrades bus operation. The preferred method of stubbing is to use transformer coupled stubs. The method provides the benefits of DC isolation, increased common mode protection, a doubling of effective stub impedance, and fault isolation for the entire stub and terminal. Direct coupled stubs should be avoided if at all possible. Direct coupled stubs provide no DC isolation or common mode rejection for the terminal external to its subsystem. Further, any shorting fault between the subsystems' internal isolation resistors (usually on the circuit board) and the main bus junction will cause failure of that entire bus. It can be expected that when the direct stub length exceeds 1.6 feet, that it will begin to distort the main bus waveforms. Note that this length includes the cable runs internal to a given subsystem.

SUBSYSTEM: The device or functional unit receiving data transfer service from the data bus.

SWITCH: Repeater which selectively re-distributes messages based on hardware MAC address

SYNCHRONOUS TRANSMISSION: Transmission in which data bits are sent at a fixed rate, with the transmitter and receiver synchronized. Synchronized transmission eliminates the need for start and stop bits.

TCP: Transmission Control Protocol - mechanism in TCP/IP that ensures that data arrives intact and in correct order

TELNET: Standard interface through which a client may access a host as though it were local

TERMINAL: The electronic module necessary to interface the data bus with the subsystem and the subsystem with the data bus. Terminals may exist as separate units or be contained within the elements of the subsystem.

TIME DIVISION MULTIPLEXING (TDM): The transmission of information from several signal sources through one communication system with different signal samples staggered in time to form a composite pulse train.

UDP: User Datagram Protocol - lower overhead alternative to TCP protocol which does not guarantee message delivery

WORD: A set of bits or bytes comprising the smallest unit of addressable memory. In MIL-STD-1553B, a word is a sequence of 16 bits plus sync and parity.

RS-232 INTERFACE

INTRODUCTION

The RS-232 interface is the Electronic Industries Association (EIA) standard for the interchange of serial binary data between two devices. It was initially developed by the EIA to standardize the connection of computers with telephone line modems. The standard allows as many as 20 signals to be defined, but gives complete freedom to the user. Three wires are sufficient: send data, receive data, and signal ground. The remaining lines can be hardwired on or off permanently. The signal transmission is bipolar, requiring two voltages, from 5 to 25 volts, of opposite polarity.

COMMUNICATION STANDARDS

The industry custom is to use an asynchronous word consisting of: a start bit, seven or eight data bits, an optional parity bit and one or two stop bits. The baud rate at which the word sent is device-dependent. The baud rate is usually 150 times an integer power of 2, ranging from 0 to 7 (150, 300, 600, ..., 19,200). Below 150 baud, many system-unique rates are used. The standard RS-232-C connector has 25 pins, 21 pins which are used in the complete standard. Many of the modem signals are not needed when a computer terminal is connected directly to a computer, and Figure 1 illustrates how some of the “spare” pins should be linked if not needed. Figure 1 also illustrates the pin numbering used in the original DB-25 connector and that now commonly used with a DB-9 connector normally used in modern computers

Specifying compliance to RS-232 only establishes that the signal levels in two devices will be compatible and that if both devices use the suggested connector, they may be able to be connected. Compliance to RS-232 does not imply that the devices will be able to communicate or even acknowledge each other’s presence.


DB-9
DB-25
RS-232 Interface
DB-25
DB-9
COMPUTER
TERMINAL
Ground
Transmit data
Receive data
Signal Ground
Request to send
Clear to send
Carrier detect
Data set ready
Ring indicator
Data terminal ready
Transmit data
Receive data
Request to send
Clear to send
Carrier detect
Data set ready
Ring indicator
Data terminal ready
1
3 2
2 3
5 7
7 4
8 5
1 8
6 6
9 22
4 20
1
2 3
3 2
7 5
4 7
5 8
8 1
6 6
22 9
20 4

Figure 1. Direct-to-Computer RS-232 Interface.

Table 1 shows the signal names, and functions of the RS-232 serial port pinout. Table 2 shows a complete pin description.

Table 1. RS-232 Serial Port Pinout.

Name	Pin	Signal Name	Function
AA	1	PG Protective Ground	This line is connected to the chassis ground of the GPIB-232CV. Since the GPIB-232CV chassis ground is not connected to earth ground, pin 1 should be connected on both serial devices.
BA	2	TxD Transmit Data	This line carries serial data from the GPIB-232CV to the serial host.
BB	3	RxD Receive Data	This line carries serial data from the serial host to the GPIB-232CV.
CA	4	RTS Request to Send	This signal line is driven by the GPIB-232CV and when asserted indicates that the GPIB-232CV is ready to accept serial data. The GPIB-232CV un-asserts RTS when it is no longer ready to accept serial data because of a buffer full condition.
CB	5	CTS Clear to Send	This signal line is asserted by the serial host and sensed by the GPIB-232CV. When asserted, it indicates that the serial host is ready to accept serial data. When unasserted, it indicates that data transmission should be disabled.
AB	7	SG Signal Ground	This line establishes a reference point for all interface voltages.
CD	20	DTR Data Terminal Ready	This signal line is asserted by the GPIB-232CV to signal that it has been powered on, and is ready to operate.

Table 2. RS-232C Interface Signals.

Pin	Description	Pin	Description	Pin	Description
1	Protective Ground	10	(Reserved for Data Set Testing)	19	Secondary Request to Send
2	Transmitted Data	11	Unassigned	20	Data Terminal Ready
3	Received Data	12	Sec. Rec'd. Line Sig. Detector	21	Signal Quality Detector
4	Request to Send	13	Sec. Clear to Send	22	Ring Indicator
5	Clear to Send	14	Secondary Transmitted Data	23	Data Signal Rate Selector (DTE/DCE Source)
6	Data Set Ready	15	Transmission Signal Element Timing (DCE Source)	24	Transmit Signal Element Timing (DTE Source)
7	Signal Ground (Common Return)	16	Secondary Received Data	25	Unassigned
8	Received Line Signal Detector	17	Receiver Signal Element Timing (DCE Source)		
9	(Reserved for Data Set Testing)	18	Unassigned		

Electrical Characteristics: The RS-232-C specifies the signaling rate between the DTE and DCE, and a digital signal is used on all interchange circuits. The RS-232 standard specifies that logic “1” is to be sent as a voltage in the range -15 to -5 V and that logic “0” is to sent as a voltage in the range +5 to +15 V. The standard specifies that voltages of at least 3 V in amplitude will always be recognized correctly at the receiver according to their polarity, so that appreciable attenuation along the line can be tolerated. The transfer rate is rated > 20 kbps and a distance of < 15 m. Greater distance and data rates are possible with good design, but it is reasonable to assume that these limits apply in practice as well as in theory. The load impedance of the terminator side of the interface must be between 3000 and 7000 ohms, and not more than 2500 pF.

Table 3, summarizes the functional specifications of the most important circuits.

Table 3. RS-232-C Circuit Definitions.

Name	Direction to:	Function
Data Signals		
Transmitted Data (BA)	DCE	Data generated by DTE
Received Data (BB)	DTE	Data Received by DTE
Timing signals		
Transmitter Signal Element Timing (DA)	DCE	Clocking signal, transitions to ON and OFF occur at center of each signal element
Transmitter Signal Element Timing (DB)	DTE	Clocking signal, as above; both leads relate to signals on BA
Receiver Signal Element Timing (DD)	DTE	Clocking signal, as above, for circuit BB
Control Signals		
Request to Send (CA)	DCE	DTE wishes to transmit
Clear to Send (CB)	DTE	DCE is ready to transmit; response to request to send
Data Set Ready (CC)	DTE	DCE is ready to operate
Data Terminal Ready (CD)	DCE	DTE is ready to operate
Ring Indicator (CE)	DTE	Indicates that DCE is receiving a ringing signal on the communication channel
Carrier Detect (CF)	DTE	Indicates that DCE is receiving a carrier signal
Signal Quality Detector (CG)	DTE	Asserted when there is reason to believe there is an error in the received data
Data Signal Rate Selector (CH)	DCE	Asserted to select the higher of two possible data rates
Data Signal Rate Selector (CI)	DTE	Asserted to select the higher of two possible data rates
Ground		
Protective Ground (AA)	NA	Attached to machine frame and possibly external grounds
Signal Ground (AB)	NA	Establishes common ground reference for all circuits

Range: The RS-232-C standard specifies that the maximum length of cable between the transmitter and receiver should not exceed 100 feet. Although in practice many systems are used in which the distance between transmitter and receiver exceeds this rather low figure. The limited range of the RS-232C standard is one of its major shortcomings compared with other standards which offer greater ranges within their specifications. One reason why the range of the RS-232C standard is limited is the need to charge and discharge the capacitance of the cable connecting the transmitter and receiver.

Mechanical Characteristics: The connector for the RS-232-C is a 25 pin connector with a specific arrangement of wires. In theory, a 25 wire cable could be used to connect the Data Terminal Equipment (DTE) to the Data Communication Equipment (DCE). The DTE is a device that is acting as a data source, data sink, or both, e.g. a terminal, peripheral, or computer. The DCE is a device that provides the functions required to establish, maintain, and terminate a data-transmission connecting, as well as the signal conversion, and coding required for communication between data terminal equipment and data circuit; e.g. a modem. Table 4, shows the complete summary of the RS-232-C, e.g., descriptor, sponsor, data format, etc.

Table 4. Summary of the RS-232-C.

Data Format	5- to 8- bit serial
Transfer Type	Asynchronous
Error Handling	Optional Parity Bit
Connector	25-pin female connector on DCE; 25-pin male connector on DTE
Length	20 meters
Speed	20 kb/s
Remarks	RS-232 is used in the microcomputer world for communications between two DTEs. The null-modem is included into one or both connecting devices, and/or cable and is seldom documented. As a result, establishing an RS-232 connection between two DTEs is frequently a difficult task.

RS-422 BALANCED VOLTAGE INTERFACE

Specifying compliance to RS-422 only establishes that the signal between the specified devices will be compatible. It does not indicate that the signal functions or operations between the two devices are compatible. The RS-422 standard only defines the characteristic requirements for the balanced line drivers and receivers. It does not specify one specific connector, signal names, or operations. RS-422 interfaces are typically used when the data rate or distance criteria cannot be met with RS-232. The RS-422 standard allows for operation of up to 10 receivers from a single transmitter. The standard does not define operations of multiple tri-stated transmitters on a link.

The RS-422-A interfaces between the Data Terminal Equipment (DTE) and Data Communication Equipment (DCE) or in any point-to-point interconnection of signals between digital equipment. It employs the electrical characteristics of balanced-voltage digital interface circuits.

The balanced voltage digital interface circuit will normally be utilized on data, timing, or control circuits where the data signaling rate is up to 10 Mbit/s. While the balanced interface is intended for use at the higher data signaling rate, it may (in preference to the unbalanced interface circuit) generally be required if any of the following conditions prevail:

- The interconnecting cable is too long for effective unbalanced operation.
- The interconnecting cable is exposed to an extraneous noise source that may cause an unwanted voltage in excess of + 1 volt measured differentially between the signal conductor and circuit common at the load end of the cable with a 50 ohm resistor substituted for the generator.
- It is necessary to minimize interference with other signals.
- Inversion of signals may be required, i.e. plus to minus MARK may be obtained by inverting the cable pair.

Applications of the balanced voltage digital interface circuit are shown in Figure 1.


DTE
B
B
DCE
DCE
B
B
DTE
DTE
B
B
DTE
LEGEND:
DTE = Data Terminal Equipment
DCE = Data Communication Equipment
= Interface Generator
= Interface Load
B = Balanced Interface Curcuit
= Telecommunication Channel

Figure 1. Application of a RS-422 Circuit.

While a restriction on maximum cable length is not specified, guidelines are given later with respect to conservative operating distances as function of data signaling rate.

For a binary system in which the RS-422-A is designed, the data signaling rate in bit/s and the modulation in bauds are numerically equal when the unit interval used in each determination is the minimum interval.

Electrical Characteristics:

The balanced voltage digital interface circuit consists of three parts: the generator (G), the balanced interconnecting cable, and the load. The load is comprised of one or more receivers (R) and an optional cable termination resistance (RT). The balanced voltage interface circuit is shown in Figure 2.

Environmental Constraints:

Balanced voltage digital interface conforming to this standard will perform satisfactorily at data signaling rates up to 10 Mbit/s providing that the following operational constraints are satisfied:

- The interconnecting cable length is within that recommended for the applicable data signaling rate (see Figure 3) and the cable is appropriately terminated.
- The common mode voltage at the receiver is less than 7 volts (peak). The common mode voltage is defined to be any uncompensated combination of generator-receiver ground potential difference, the generator offset voltage (Vos), and longitudinally coupled peak noise voltage measured between the received circuit ground and cable within the generator ends of the cable short-circuited to ground.


BALANCED INTERCONNECTING CABLE
LOAD
CABLE TERMINATION
GENERATOR
RECEIVER
A
A1
B
B1
G
Rt
R
To additional receivers, if any
C
Vg
C1
LEGEND:
Rt = Optional Cable Termination Resistance
Vg = Ground Potential Difference
A, B = Generator Interface Points
A1, B1 = Load Interface Points
C = Generator Circuit Ground
C1 = Load Circuit Ground
Note: The physical connections of multiple receiver is not defined

Figure 2. Balanced Digital Interface Circuit.

Interconnecting Cable Guidelines:

The maximum permissible length of cable separating the generator and the load is a function of data signaling rate and is influenced by the tolerable signal distortion, the amount of coupled noise and ground potential difference introduced between the generator and load circuit as well as by cable balance. The curve of cable length versus signaling rate is given in Figure 3. This curve is based upon using 24 AWG copper, twisted-pair cable with a capacitance of 52.5 pF/meter terminated in a 100 ohm load. As data signaling rate is reduced below 90 kbit/s, the cable length has been limited at 1200 meters by the assumed maximum allowable 6 dBV signal loss.

Industry customs are not nearly as well established for RS-422 interfaces as they are for RS-232. The standard specifies use of the 37-pin "D"; the 9-pin "D" is specified for use with the secondary channel. Most data communications equipment uses the 37-pin "D"; many computer applications use a 9-pin "D" only. Some equipment applications use the 25-pin "D" defined for RS-232.

Compatibility With Other Interfaces:

Since the basic differential receivers of RS-423-A and RS-422-A are electrically identical, it is possible to interconnect an equipment using RS-423-A receivers and generators on one side of the interface with an equipment using RS-422-A generators and receivers on the other side of the interface, if the leads of the receivers and generators are properly configured to accommodate such an arrangement and the cable is not terminated.

This circuit is not intended for interoperation with other interface electrical circuits such as RS-232-C, MIL-STD-188C, or CCITT (Comite Consultatif Internationale Telegraphique et Telephonique), recommendations V.28 and V.35. Under certain conditions, the above interfaces may be possible but may require modification of the interface or equipment; therefore satisfactory operation is not assured and additional provisions not specified herein may be required.



Figure 3. Data Signaling Rate vs. Cable Length.

This page intentionally left blank.

RS-485 INTERFACE

STANDARD FOR ELECTRICAL CHARACTERISTICS OF GENERATORS AND RECEIVERS FOR USE IN BALANCED DIGITAL MULTIPOINT SYSTEMS

Introduction: The RS-485 is the recommend standard by the Electronic Industries Association (EIA) that specifies the electrical characteristics of generators and receivers that may be employed for the interchange of binary signals in multipoint interconnection of digital equipments. When implemented within the guidelines, multiple generators and receivers may be attached to a common interconnecting cable. An interchange system includes one or more generators connected by a balanced interconnecting cable to one or more receivers and terminating resistors.

Electrical Characteristics: The electrical characteristics that are specified are measured at an interconnect point supplied by the devices manufacturer. Figure 1 shows an interconnection application of generators and receivers having the electrical parameters specified. The elements in the application are: generators, receivers, transmission cables, and termination resistances (Rt). The loads on the system caused by each receiver and passive generator shall be defined in terms of unit loads. Each generator can drive up to 32 unit loads consisting of both receivers and generators in the passive state. The loading caused by receivers and passive generators on the interconnect must be considered in defining the device electrical characteristics. Two areas are of concern: the DC load and the AC load characteristics. The DC load is defined as a number or fractions of "unit loads." The AC loading is not standardized but must be considered in the design of a system using the devices meeting this standard.


Rt
Rt
A
B
G
C
A1
B1
R
C1
L
Interface Described in This Standard
A/A1
B/B1
G/R
C/C1
Balanced Interconnecting Cable
LEGEND:
G = Generator
R = Receiver
G/R = Combination Generator / Receiver
L = Length of stub: the guideline assumes length of stub to be effectively zero
Rt = Termination resistance; location and value are not specified in this standard, but a generator can drive 32 unit loads plus two termination resistances of 120 ohms each.

Figure 1. Multipoint Interconnect Application.

General System Configuration: The generators and receivers conforming to the RS-485 standard can operate with a common mode voltage between -7 volts and +7 volts (instantaneous). The common mode voltage is defined to be any uncompensated combination of generator-receiver ground potential difference and longitudinally coupled peak noise voltage measured between the receiver circuit ground and cable with the generator ends of the cable short circuited to ground, plus the generator offset voltage (Vos).

Grounding Arrangements: Proper operation of the generator and receiver circuits requires the presence of a signal return path between the circuit grounds of the equipment at each end of the interconnection. The grounding arrangements are shown in Figure 2. Where the circuit reference is provided by a third conductor, the connection between circuit common and the third conductor must contain some resistance (e.g., 100 ohms) to limit circulating currents when other ground connections are provided for safety. Some applications may require the use of shielded interconnecting cable for EMI or other purposes. The shield shall be connected to frame ground at either or both ends, depending on the application.


Balanced Interconnecting Cable Pair
R₁
R₁
No Connection
Third Conductor
No Connection
A
G
B
A₁
R
B₁
A/A₁
G/R
B/B₁
C
100 Ω
100 Ω
C₁
100 Ω
C/C₁
Logic reference
100 Ω *
1/2 W
100 Ω *
1/2 W
Optional Strap
100 Ω *
1/2 W
Chassis reference
Earth (safety) reference
* Resistor must become an open circuit when overloaded
NOTE: Third conductor not required if earth reference provided in each using equipment.

Figure 2. Grounding Arrangements.

Similarity with RS-422-A:

In certain instances, it may be possible to produce generators and receivers that meet the requirements of both RS-422-A and of RS-485. Table 1 depicts the differences in parameter specifications which exist between the two documents.

Table 1. Comparison of RS-422-A and RS-485 Characteristics.

Characteristic	RS-422-A	RS-485
Min. output voltage	2V into 100 ohm > 1/2 open circuit V	1.5 V into 54 ohms
I_{short} to ground	150 mA maximum	
I_{short} to -7, +12 volts		250 mA peak
t_{rise} time	< 0.1 t_b , 100 ohm load	< 0.3 t_b , 54 ohm, 50 pF load

Where t_b = time duration of the unit interval at the applicable data signaling rate (pulse width).

IEEE-488 INTERFACE BUS (HP-IB/GP-IB)

In the early 1970's, Hewlett-Packard came out with a standard bus (HP-IB) to help support their own laboratory measurement equipment product lines, which later was adopted by the IEEE in 1975. This is known as the IEEE Std. 488-1975. The IEEE-488 Interface Bus (HP-IB) or general purpose interface bus (GP-IB) was developed to provide a means for various instruments and devices to communicate with each other under the direction of one or more master controllers. The HP-IB was originally intended to support a wide range of instruments and devices, from the very fast to the very slow.

DESCRIPTION

The HP-IB specification permits up to 15 devices to be connected together in any given setup, including the controller if it is part of the system. A device may be capable of any other three types of functions: controller, listener, or talker. A device on the bus may have only one of the three functions active at a given time. A controller directs which devices will be talkers and listeners. The bus will allow multiple controllers, but only one may be active at a given time. Each device on the bus should have a unique address in the range of 0-30. The maximum length of the bus network is limited to 20 meters total transmission path length. It is recommended that the bus be loaded with at least one instrument or device every 2 meter length of cable (4 meters is maximum). The use of GP-IB extenders may be used to exceed the maximum permitted length of 20 meters.

ELECTRICAL INTERFACE

The GP-IB is a bus to which many similar modules can be directly connected, as is shown in Figure 1. A total of 16 wires are shown in the figure - eight data lines and eight control lines. The bus cables actually have 24 wires, providing eight additional for shielding and grounds.



Figure 1. IEEE-488 (HP-IB / GP-IB) Bus Configuration.

The GP-IB defines operation of a three-wire handshake that is used for all data transfers on the bus. The bus operation is asynchronous in nature. The data-transfer rate of the GP-IB is 500 kHz for standard applications and can go up 1 MHz if special conventions are followed. Each transaction carries 8 bits, the maximum data bandwidth is on the order of 4 to 8 megabits (1 M byte) per second. The bus is a two way communications channel and data flows in both directions. Figure 2 illustrates the structure of the GP-IB bus and identifies the 16 connections of the interconnecting cable.


GPIB Listner and / or Talker
GPIB Listner and / or Talker
GPIB Listner and / or Talker
GPIB Listner and / or Talker
DAV
NRFD
NDAC
Handshake Bus
IFC
ATN
SRQ
REN
EOI
Management Bus
DIO - 1
Data Bus
DIO - 8

Figure 2. GP-IB Instrumentation Bus Structure.

The cabling limitations make it a less-than-ideal choice for large separation between devices. These limitations can be overcome with bus extenders. Those attempting to use bus extenders should be aware that few extenders are as transparent as claimed. This is especially true in handling of continuous data and interrupts. In nonextended environments, it provides an excellent means for high-speed computer control of multiple devices.

The following table shows the various interface functions, the mnemonics and the descriptions.

Table 1. GP-IB Interface Functions.

Interface Function	Mnemonic	Description
Talker (extended talker)	T (TE)	Device must be able to transmit
Listener (Extended listener)	L (LE)	Device must receive commands and data
Source Handshake	SH	Device must properly transfer a multiline message
Acceptor Handshake	AH	Device must properly receive remote multiline messages
Remote/Local	RL	Device must be able to operate from front panel and remote information from bus
Service Request	SR	Device can asynchronously request service from the controller
Parallel Poll	PP	Upon controller request, device must uniquely identify itself if it requires service
Device Clear	DC	Device can be initialized to a predetermined state
Device Trigger	DT	A device function can be initiated by the talker on the bus
Controller	C	Device can send addresses, universal commands, address commands, and conduct polls
Drivers	E	This code describes the type of electrical drivers in a device

The cabling specifications of the GP-IB interface system permit interconnecting all devices together in a star or linear configuration. The GP-IB connector is a 24-pin ribbon-type connector.

In summary, Table 2 on this page and the next shows the complete description of the GP-IB data bus.

Table 2. GP-IB Data Bus Description.

IEEE-488, GP-IB, HP-IB, or IEC-625					
Descriptor	8-bit parallel, monodirectional, multi-master (token passing) One controller, one talker, several listeners	Arbitration	Token passing: the controller addresses the next controller SRQ Service request when the controller assigns modes	Connector	24-pin Amphenol Female connector on equipment chassis. DIO1 1 ■ ■ 13 DIO5 DIO2 2 ■ ■ 14 DIO6 DIO3 3 ■ ■ 15 DIO7 DIO4 4 ■ ■ 16 DIO8 EOI 5 ■ ■ 17 REN DAV 6 ■ ■ 18 Gnd NRFD 7 ■ ■ 19 Gnd NDAC 8 ■ ■ 20 Gnd IFC 9 ■ ■ 21 Gnd SRQ 10 ■ ■ 22 Gnd ATN 11 ■ ■ 23 Gnd Shld 2 ■ ■ 24 Gnd
Sponsor	Hewlett-Packard	Error handling	Parity bit DI07 when 7-bit ACSII characters		
Standard	IEEE 488, IEC 625	Bus length	15 m		
Address space	31 devices	Driver	Special 24 mA drivers		
Data format	8-bit parallel	Speed	1 MByte/s		
Transfer type	Write only, talker toward listener(s) or commander toward all others			Remarks	The 488 is most commonly used for data acquisition of H-P peripherals. Programmable interfaces and drivers exist and simplify the development of microprocessor interfaces.
Timing	Handshaken 3-wire broadcast transfer: DAV data valid NDAC Not data accepted NRFD Not ready for data	References	IEEE Computer Society		

HP-IL VARIATION

Since introduction of the IEEE-488, technology produced a generation of medium-speed, low-power, instrumentation which had a need to operate in an automatic test system such as the GP-IB. The HP-IL (Hewlett-Packard Interface Loop), was introduced to meet this need. The HP-IL is a low-cost, low-power alternative to the GP-IB system. The HP-IL and GP-IB provide the same basic functions in interfacing controllers, instruments, and peripherals, but they differ in many other respects. HP-IL is suitable for use in low-power, portable applications (typically used for interface of battery-power systems). The GP-IB is not practical to operate from battery power. The HP-IL maximum data rate is 20K bytes per second. This is a high rate compared to the RS-232C, but much slower than GP-IB. The HP-IL can operate over distances of up to 100 meters between any two devices. Since it is a loop environment, there is no maximum system cable restriction. The basic device-addressing scheme allows for up to 30 devices on a loop.

MIL-STD-1553 & 1773 DATA BUS

PURPOSE

In recent years, the use of digital techniques in aircraft equipment has greatly increased, as have the number of avionics subsystems and the volume of data processed by them.

Because analog point-to-point wire bundles are inefficient and cumbersome means of interconnecting the sensors, computers, actuators, indicators, and other equipment onboard the modern military vehicle, a serial digital multiplex data bus was developed. MIL-STD-1553 defines all aspects of the bus, therefore, many groups working with the military tri-services have chosen to adopt it.

The 1553 multiplex data bus provides integrated, centralized system control and a standard interface for all equipment connected to the bus. The bus concept provides a means by which all bus traffic is available to be accessed with a single connection for testing and interfacing with the system. The standard defines operation of a serial data bus that interconnects multiple devices via a twisted, shielded pair of wires. The system implements a command-response format.

MIL-STD-1553, "Aircraft Internal Time-Division Command/Response Multiplex Data Bus," has been in use since 1973 and is widely applied. MIL-STD-1553 is referred to as "1553" with the appropriate revision letter (A or B) as a suffix. The basic difference between the 1553A and the 1553B is that in the 1553B, the options are defined rather than being left for the user to define as required. It was found that when the standard did not define an item, there was no coordination in its use. Hardware and software had to be redesigned for each new application. The primary goal of the 1553B was to provide flexibility without creating new designs for each new user. This was accomplished by specifying the electrical interfaces explicitly so that compatibility between designs by different manufacturers could be electrically interchangeable.

The Department of Defense chose multiplexing because of the following advantages:

- Weight reduction
- Simplicity
- Standardization
- Flexibility

Some 1553 applications utilize more than one data bus on a vehicle. This is often done, for example, to isolate a Stores bus from a Communications bus or to construct a bus system capable of interconnecting more terminals than a single bus could accommodate. When multiple buses are used, some terminals may connect to both buses, allowing for communication between them.

MULTIPLEXING

Multiplexing facilitates the transmission of information along the data flow. It permits the transmission of several signal sources through one communications system.

BUS

The bus is made up of twisted-shielded pairs of wires to maintain message integrity. MIL-STD-1553 specifies that all devices in the system will connect to a redundant pair of buses. This provides a second path for bus traffic should one of the buses be damaged. Signals are only allowed to appear on one of the two buses at a time. If a message cannot be completed on one bus, the bus controller may switch to the other bus. In some applications more than one 1553 bus may be implemented on a given vehicle. Some terminals on the bus may actually connect to both buses.

BUS COMPONENTS

There are only three functional modes of terminals allowed on the data bus: the bus controller, the bus monitor, and the remote terminal. Devices may be capable of more than one function. Figure 1 illustrates a typical bus configuration.



Figure 1. 1553 Bus Structure.

- Bus Controller - The bus controller (BC) is the terminal that initiates information transfers on the data bus. It sends commands to the remote terminals which reply with a response. The bus will support multiple controllers, but only one may be active at a time. Other requirements, according to 1553, are: (1) it is “the key part of the data bus system,” and (2) “the sole control of information transmission on the bus shall reside with the bus controller.”

- Bus Monitor - 1553 defines the bus monitor as “the terminal assigned the task of receiving bus traffic and extracting selected information to be used at a later time.” Bus monitors are frequently used for instrumentation.

- Remote Terminal - Any terminal not operating in either the bus controller or bus monitor mode is operating in the remote terminal (RT) mode. Remote terminals are the largest group of bus components.

MODULATION

The signal is transferred over the data bus using serial digital pulse code modulation.

DATA ENCODING

The type of data encoding used by 1553 is Manchester II biphase.

- A logic one (1) is transmitted as a bipolar coded signal 1/0 (in other words, a positive pulse followed by a negative pulse).
- A logic zero (0) is a bipolar coded signal 0/1 (i.e., a negative pulse followed by a positive pulse).



Figure 2. Data Encoding.

A transition through zero occurs at the midpoint of each bit, whether the rate is a logic one or a logic zero. Figure 2 compares a commonly used Non Return to Zero (NRZ) code with the Manchester II biphase level code, in conjunction with a 1 MHz clock.

BIT TRANSMISSION RATE

The bit transmission rate on the bus is 1.0 megabit per second with a combined accuracy and long-term stability of +/- 0.1%. The short-term stability is less than 0.01%.

There are 20 1.0-microsecond bit times allocated for each word. All words include a 3 bit-time sync pattern, a 16-bit data field that is specified differently for each word type, and 1 parity check bit.

WORD FORMATS

Bus traffic or communications travels along the bus in words. A word in MIL-STD-1553 is a sequence of 20 bit times consisting of a 3 bit-time sync wave form, 16 bits of data, and 1 parity check bit. This is the word as it is transmitted on the bus; 1553 terminals add the sync and parity before transmission and remove them during reception. Therefore, the nominal word size is 16 bits, with the most significant bit (MSB) first.

There are three types of words: command, status, and data. A packet is defined to have no inter-message gaps. The time between the last word of a controller message and the return of the terminal status byte is 4-12 microseconds. The time between status byte and the next controller message is undefined. Figure 3 illustrates these three formats.


BIT Times
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
Command Word
5
1
5
5
1
Sync
Remote Terminal Address
T/R
Subaddress/Mode
Data Word Count / Mode Code
P
Data Word
16
1
Sync
Data
P
Status Word
5
1
1
1
3
1
1
1
1
1
1
Sync
Remote Terminal Address
Message Error
Instrumentation
Service Request
Resereved
Broadcast Command Received
Busy
Subsystem Flag
Dynamic Bus Control Accptance
Terminal Flag
Parity
T/R - Transmit/Receive
P - Parity

Figure 3. 1553 Word Formats.

COMMAND WORD

Command words are transmitted only by the bus controller and always consist of:

- 3 bit-time sync pattern
- 5 bit RT address field
- 1 Transmit/Receive (T/R) field
- 5 bit subaddress/mode field
- 5 bit word count/mode code field
- 1 parity check bit.

DATA WORD

Data words are transmitted either by the BC or by the RT in response to a BC request. The standard allows a maximum of 32 data words to be sent in a packet with a command word before a status response must be returned. Data words always consist of:

- 3 bit-time sync pattern (opposite in polarity from command and status words)
- 16 bit data field
- 1 parity check bit.

STATUS WORD

Status words are transmitted by the RT in response to command messages from the BC and consist of:

- 3 bit-time sync pattern (same as for a command word)
- 5 bit address of the responding RT
- 11 bit status field
- 1 parity check bit.

The 11 bits in the status field are used to notify the BC of the operating condition of the RT and subsystem.

INFORMATION TRANSFERS

Three basic types of information transfers are defined by 1553:

- Bus Controller to Remote Terminal transfers
- Remote Terminal to Bus Controller transfers
- Remote Terminal to Remote Terminal transfers

These transfers are related to the data flow and are referred to as messages. The basic formats of these messages are shown in Figure 4.


Controller to RT Transfer
From Controller
Receive Command
Data Word
Data Word
....
Data Word
**
From RT
Status Word
#
Next Sequence
Command Word
RT to Controller Transfer
From Controller
Transmit Command
**
From RT
Status Word
Data Word
Data Word
....
Data Word
#
Next Sequence
Command Word
RT to RT Transfer
From Controller
Receive Command
Transmit Command
**
From Transmitting RT
Status Word
Data Word
Data Word
....
Data Word
**
From Receiving RT
Status Word
#
RT = Remote Terminal
** = End of transmission from that unit
# = End of overall sequence

Figure 4. 1553 Data Message Formats.

The normal command/response operation involves the transmission of a command from the BC to a selected RT address. The RT either accepts or transmits data depending on the type (receive/transmit) of command issued by the BC. A status word is transmitted by the RT in response to the BC command if the transmission is received without error and is not illegal.

Figure 5 illustrates the 1553B Bus Architecture in a typical aircraft.


Fire Control Navigation Panel
Fire Control Computer
Bus Control Discrete
Inertial Navigation Unit
Heads-Up Display Unit
Stores Management
Fire Control Radar
Central Air Data Computer
Radar Display
Target Identification

Figure 5. Typical Bus Architecture.

MIL-STD-1773

MIL-STD-1773 contains the requirements for utilizing a fiber optic “cabling” system as a transmission medium for the MIL-STD-1553B bus protocol. As such, the standard repeats MIL-STD-1553 nearly word-for-word. The standard does not specify power levels, noise levels, spectral characteristics, optical wavelength, electrical/optical isolation or means of distributing optical power. These must be contained in separate specifications for each intended use.

Data encoding and word format are identical to MIL-STD-1553, with the exception that pulses are defined as transitions between 0 (off) and 1 (on) rather than between + and - voltage transitions since light cannot have a negative value.

Since the standard applies to cabling only, the bus operates at the same speed as it would utilizing wire. Additionally, data error rate requirements are unchanged.

Different environmental considerations must be given to fiber optic systems. Altitude, humidity, temperature, and age affects fiber optics differently than wire conductors. Power is divided evenly at junctions which branch and connectors have losses just as wire connectors do.

ETHERNET

HISTORY

Ethernet was originally developed by Digital, Intel, and Xerox (DIX) in the early 1970's at the Xerox Palo Alto Research Center (PARC). The two primary inventors were Robert Metcalf and David Boggs.

IEEE Project 802 was set up in February 1980 to provide standards for Local Area Network (LAN) and Metropolitan Area Network (MAN) Architecture. The following committees were established:

- IEEE 802.1: Standards related to network management.
- IEEE 802.2: General standard for the data link layer in the OSI Reference Model. The IEEE divides this layer into two sub-layers -- the logical link control (LLC) layer and the media access control (MAC) layer. The MAC layer varies for different network types and is defined by standards IEEE 802.3 through IEEE 802.5.
- IEEE 802.3: Defines the MAC layer for bus networks that use CSMA/CD. **This is the basis of what is most commonly referred to as the Ethernet standard**.
- IEEE 802.4: Defines the MAC layer for token-bus networks.
- IEEE 802.5: Defines the MAC layer for token-ring networks.
- IEEE 802.6: Standard for Metropolitan Area Networks (MANs).
- IEEE 802.7-9 Inactive Standards:
  - IEEE 802.7: Broadband local area networks. The working group is currently inactive.
  - IEEE 802.8: The Fibre Optic Technical Advisory Group was to create a LAN standard for fiber optic media used in token passing computer networks like FDDI.
  - IEEE 802.9: Integrated Services (IS) LAN Interface at the MAC and Physical Layers.
- IEEE 802.10: A standard for security functions that can be used in both LAN and MAN.
- IEEE 802.11: Wireless LAN MAC and physical layer
- IEEE 802.12: Demand Priority Access Method, Physical Layer and Repeater used in star topology, 100VG-AnyLAN, etc
- IEEE 802.16: Fixed broadband wireless LAN

Ethernet versions 1.0 and 2.0 followed after the original development until the IEEE 802.3 committee altered the structure of the Ethernet II packet to form the Ethernet 802.3 packet. You will currently see either Ethernet II (DIX) format or Ethernet 802.3 format being used.

IEEE 802.3 Ethernet uses Manchester Phase Encoding (MPE) for coding the data bits on the outgoing signal.

INTRODUCTION

Ethernet is a family of frame-based computer networking technologies for local area networks (LANs). The 'Ether' part of Ethernet denotes that the system is not meant to be restricted for use on only one medium type. Copper cables, fiber cables and even radio waves can be used.

Ethernet is standardized as IEEE 802.3. The combination of the twisted pair versions of Ethernet for connecting end systems to the network, along with the fiber optic versions for site backbones, is the most widespread wired LAN technology. It has largely replaced competing LAN standards such as token ring, FDDI, and ARCNET.

Ethernet defines a number of wiring and signaling standards for the Physical Layer of the OSI networking model, through means of network access at the Media Access Control (MAC) / Data Link Layer, and a common addressing format. Therefore, Ethernet defines the lower two layers of the OSI Reference Model (see Data Busses Section intro). Ethernet sometimes implies an attached protocol—such as TCP/IP, however TCP/IP really defines the transport and network layers, respectively, of the OSI model.

Ethernet was designed as a ‘broadcast’ system, i.e. stations on the network can send messages whenever and wherever they want. All stations may receive the messages, however only the specific station to which the message is directed responds. To handle simultaneous demands, the system uses Carrier Sense Multiple Access with Collision Detection (CSMA/CD).

CARRIER SENSE MULTIPLE ACCESS WITH COLLISION DETECTION (CSMA/CD)

When an Ethernet station is ready to transmit, it checks for the presence of a signal on the cable. If no signal is present then the station begins transmission. However, if a signal is present then the station delays transmission until the cable is not in use. If two stations detect an idle cable and at the same time transmit data, then a collision occurs. On a star-wired, unshielded twisted pair (UTP) network, if the transceiver of a sending station detects activity on both its receive and transmit pairs before it has completed transmitting, then it decides that a collision has occurred. On a coaxial system, a collision is detected when the DC signal level on the cable is the same or greater than the combined signal level of the two transmitters. Line voltage drops dramatically if two stations transmit at the same time and the first station to notice this sends a high voltage jamming signal around the network as a signal. The two stations involved with the collision quit transmitting again for a random time interval.

A Collision Domain is that part of the network where each station can ‘see’ other stations’ traffic both unicast and broadcasts. The Collision Domain is made up of one segment of Ethernet coax (with or without repeaters) or a number of UTP shared hubs. A network is segmented with bridges that create two segments, or two Collision Domains where a station on one segment cannot see traffic between stations on the other segment unless the packets are destined for itself. If it can still see all broadcasts on the segmented network(s), no matter the number of segments, it is a Broadcast Domain.

ETHERNET FRAME

Figure 1 depicts the structure of the older DIX (Ethernet II) and the now standard 802.3 Ethernet frames. The numbers above each field represent the number of bytes.



Figure 1. Ethernet Frame.

- **Preamble field:** Establishes bit synchronization and transceiver conditions so that the circuitry synchs with the received frame timing. The DIX frame has 8 bytes for the preamble rather than 7, as it does not have a Start Frame Delimiter (or Start of Frame).
- **Start Frame Delimiter:** Sequence 10101011 in a separate field, only in the 802.3 frame.
- **Destination address:** Hardware address (MAC address) of the destination station (usually 48 bits i.e. 6 bytes).
- **Source address:** Hardware address of the source station (must be of the same length as the destination address, the 802.3 standard allows for 2 or 6 byte addresses, although 2 byte addresses are never used, N.B. Ethernet II *only* uses 6 byte addresses).
- **Type:** Specifies the protocol sending the packet such as IP or IPX (only applies to DIX frame).
- **Length:** Specifies the length of the data segment, actually the number of LLC data bytes, (only applies to 802.3 frame and replaces the Type field).
- **LLC:** Logical Length Control is a data communication protocol layer which provides multiplexing and flow control mechanisms that make it possible for several network protocols (IP, IPX) to coexist within a multipoint network and to be transported over the same network media.
- **Data:** Actual data which is allowed anywhere between 46 to 1500 bytes within one frame.
- **Pad:** Zeros added to the data field to ‘Pad’ a short data field to 46 bytes (applies to 802.3 frame).
- **CRC:** Cyclic Redundancy Check to detect errors during transmission (DIX version of FCS).
- **FCS:** Frame Check Sequence to detect errors that occur during transmission (802.3 version of CRC). This 32-bit code has an algorithm applied to it, which will give the same result as the other end of the link, provided that the frame was transmitted successfully.

From the above we can see that the maximum 802.3 frame size is 1518 bytes and the minimum size is 64 bytes. Packets that have correct CRCs (or FCSs) but are smaller than 64 bytes are known as ‘Runts’.

The hardware address, or MAC address is transmitted and stored in Ethernet network devices in **Canonical** format i.e. Least Significant Bit (LSB) first. The expression **Little-Endian** is used to describe the LSB format in which Ethernet is transmitted. On the other hand, Token Ring networks and the subset, Fiber

Distributed Data Interface (FDDI) networks, transmit the MAC address with the Most Significant Bit (MSB) first, or **Big-Endian**, This is known as **Non-Canonical** format. Note that this applies on a byte-by-byte basis i.e. the bytes are transmitted in the same order, it is just the bits in each of those bytes that are reversed. The storage of the MAC addresses in Token Ring and FDDI devices however, may sometimes still be in Canonical format so this can sometimes cause confusion. The reference to, the distribution of MAC addresses and the Organizationally Unique Identifier (OUI) destinations are always in Canonical format.

The Logical Link Control (LLC) protocol data unit (PDU) is defined in IEEE 802.2 and operates with 802.3 Ethernet as seen in Figure 2.



DSAP address	SSAP address	Control	Information
8 bits	8 bits	8 or 16 bits	M*8 bits

DSAP address = Destination service access point address field

SSAP address = Source service access point address field

Control = Control field [16 bits for formats that include sequence numbering, and 8 bits for formats that do not (see 5.2)]

Information = Information field

* = Multiplication

M = An integer value equal to or greater than 0. (Upper bound of M is a function of the medium access control methodology used.)

Figure 2. LLC Format.

LLC is based on the High-Level Data Link Control (HDLC) data protocol format. Whereas Ethernet II (2.0) combines the MAC and the Data link layers restricting itself to connectionless service in the process, IEEE 802.3 separates out the MAC and Data Link layers. IEEE 802.2 is also required by Token Ring and FDDI but cannot be used with the Novell ‘Raw’ format. There are three types of LLC; Type 1, which is connectionless, Type 2 which is connection-oriented, and Type 3 for Acknowledged Connections.

The **Service Access Point (SAP)** is used to distinguish between different data exchanges on the same end station and basically replaces the Type field for the older Ethernet II frame. The **Source Service Access Point (SSAP)** indicates the service from which the LLC data unit is sent, and the **Destination Service Access Point (DSAP)** indicates the service to which the LLC data unit is being sent. As examples, NetBIOS uses the SAP address of **F0** whilst IP uses the SAP address of **06**. The following lists some common SAPs:

00 - Null LSAP
02 - Individual LLC Sublayer Management Function
03 - Group LLC Sublayer Management Function
05 - IBM SNA Path Control (group)

06 - Internet Protocol (IP)
18 - Texas Instruments
42 - IEEE 802.1 Bridge Spanning Tree Protocol
80 - Xerox Network Systems (XNS)
86 - Nestar
AA - SubNetwork Access Protocol (SNAP)
E0 - Novell NetWare
F0 - IBM NetBIOS
F5 - IBM LAN Management (group)
FE - ISO Network Layer Protocol

The **Control Field** identifies the type of LLC, of which there are three:

- **Type 1** - Data (PDUs) shall be exchanged between LLCs without the need for the establishment of a data link connection. These PDUs shall not be acknowledged, nor shall there be any flow control or error recovery. This is called **Unsequenced Information (UI)**.
- **Type 2** – Needs data link connection. Uses **Information (I)** frames and maintains the sequence numbers during an acknowledged connection-oriented transmission.
- **Type 3** – No data link connection required. Uses **Acknowledged Connection (AC)** frames in an acknowledged connectionless service.

MAC ADDRESS

With an Ethernet MAC address, the first octet uses only the lowest significant bit as the Individual/Group (I/G) bit address identifier. If it is zero it indicates the address is individual. If it is one, it indicates a group address. The Universally or Locally administered (U/L) address bit is the bit of octet 0 adjacent to the I/G address bit. This bit indicates whether the address has been assigned by a local or universal administrator. Universally administered addresses have this bit set to 0. If this bit is set to 1, the entire address (i.e., 48 bits) has been locally administered.

The first 3 octets of the MAC address form the Organizational Unique Identifier (OUI) assigned by IEEE to organizations that requires their own group of MAC addresses.

SUBNETWORK ACCESS PROTOCOL (SNAP)

The SNAP protocol was introduced to allow an easy transition to the new LLC frame format for vendors. SNAP allows older frames and protocols to be encapsulated in a Type 1 LLC header making any protocol ‘pseudo-IEEE compliant’. SNAP is described in RFC 1042. Figure 3 shows how it looks:


Destination MAC address
Source MAC address
Ethernet Type
Ethernet data
FCS
AC
FC
Destination MAC address
Source MAC address
SNAP "AA"
SNAP "AA"
UI "03"
RFC 1042 OUI 00-00-00
Ethernet Type
Ethernet data
FCS
DSAP
SSAP
CTL
Protocol Identification Field
Protocol Data Field
IEEE 802.5 MAC header
LLC PDU header
SNAP PDU

Figure 3. Ethernet Frame SNAP-encapsulated in IEEE 802.5 Frame.

It can be seen that it is an LLC data unit (sometimes called a Logical Protocol Data Unit (LPDU)) of Type 1 (indicated by 03). The DSAP and SSAP are set to AA to indicate that this is a SNAP header coming up. The SNAP header then indicates the vender via the Organizational Unique Identifier (OUI) and the protocol type via the Ethertype field. In the example above the OUI is 00-00-00 which means that there is an Ethernet frame. An ethernet type (Ethertype) of 08-00 would indicate Internet IP is the protocol. The official list of types can be found at IEEE. Although vendors tend to be are moving to LLC1 on the LAN, SNAP still remains.

TRANSMISSION MEDIA

10Base-5 - largely obsolete, but may still be in use.

Traditionally, Ethernet is used over ‘thick’ coaxial cable called 10Base-5 (the ‘10’ denotes 10Mbps, base means that the signal is baseband i.e. takes the whole bandwidth of the cable (so that only one device can transmit at one time on the same cable), and the ‘5’ denotes 500 m maximum length). The minimum length between stations is 2.5 m.

The cable is run in one long length forming a ‘Bus Topology’. Stations attach to it by way of inline N-type connections or a transceiver, which is literally screwed into the cable (by way of a ‘Vampire Tap’) providing a 15-pin Attachment Unit Interface (AUI) connection (also known as a DIX connector or a DB-15 connector) for a drop lead connection (maximum of 50 m length) to the station. The segments are terminated with 50 ohm resistors and the shield grounded at one end only.

The segment could be appended with up to a maximum of 4 repeaters; therefore 5 segments (total length of 2,460 m) can be connected together. Of the 5 segments only 3 can have devices attached (100 per segment). This is known as the 5-4-3 rule. A total of 300 devices can be attached on a Thicknet broadcast domain.

10Base-2 – dominant for many years

It was common to see the Thick coax used in Risers to connect Repeaters, which in turn provide 'Thin Ethernet' coaxial connections for runs up to 30 workstations. Thin Ethernet (Thinnet) uses RG-58 cable and is called 10Base-2 (The '2' now denoting 200 m maximum length - strictly speaking this is 185 m). The minimum length between stations is 0.5 m.

Each station connects to the thinnet by way of a Network Interface Card (NIC), which provides a BNC (British Naval Connector). At each station the thinnet terminates at a T-piece and at each end of the thinnet run (or 'Segment') a 50-ohm terminator is required to absorb stray signals, thereby preventing signal bounce. The shield is grounded at one end only.

A segment can be appended with other segments using up to 4 repeaters, i.e. 5 segments in total. Two of these segments however, cannot be tapped; they can only be used for extending the length of the broadcast domain (to 925 m). What this means is that 3 segments with a maximum of 30 stations on each can give you 90 devices on a Thinnet broadcast domain.

10Base-T – Most widespread today

The most common media used in of Ethernet today involves use of Unshielded Twisted Pair (UTP) or Shielded Twisted Pair (STP). For instance, Category 5 UTP can be installed in a 'Star-wired' format, with runs recommended at no greater than 100 m (including patch leads, cable run and flyleads) and Ethernet Hubs with UTP ports (RJ45) centrally located. It has been found though that runs of up to 150 m are feasible, the limitations being signal strength. Also, there should be no more than a 11.5 dB signal loss and the minimum distance between devices is 2.5 m. The maximum delay for the signal in a 10Mbps network is 51.2 microseconds. This comes from the fact that the bit time (time to transmit one bit) is 0.1 microseconds and that the slot time for a frame is 512 bit times.

In order to connect to Ethernet in this 'Star Topology', each station has a NIC, which contains an RJ45 socket which is used by a 4-pair droplead to connect to another nearby RJ45 socket.

Each port on the hub sends a 'Link Beat Signal' which checks the integrity of the cable and devices attached, a flickering LED on the front of the port of the hub tells you that the link is running fine. The maximum number of hubs (or, more strictly speaking, repeater counts) that you can have in one segment is four and the maximum number of stations on one broadcast domain is 1024.

The advantages of the UTP/STP technology are gained from the flexibility of the system, with respect to moves, changes, fault finding, reliability, and security. The following table shows the RJ45 pin-outs for 10Base-T:

RJ45 Pin	Function	Color
1	Transmit	White/Orange stripe
2	Transmit	Orange
3	Receive	White/Green stripe
4		Blue
5		White/Blue stripe
6	Receive	Green
7		White/Brown stripe
8		Brown

If you wish to connect hub to hub, or a NIC directly to another NIC, then the following 10Base-T crossover cable should be used:



Figure 4. 10Base-T Crossover.

The 4-repeater limit manifests itself in 10/100Base-T environments where the active hub/switch port is in fact a repeater, hence the name multi-port repeater. Generally, the hub would only have one station per port but you can cascade hubs from one another up to the 4-repeater limit. The danger here is that you will have all the traffic from a particular hub being fed into one port so care would need to be taken on noting the applications being used by the stations involved, and the likely bandwidth that the applications will use.

There is a pre-standard called Lattisnet (developed by Synoptics), which runs 10 MHz Ethernet over twisted pair but instead of bit synchronization occurring at the sending (as in 10Base-T) the synchronization occurs at the receiving end.

10Base-F

The 10Base-F standard defines the use of fiber for Ethernet. 10Base-FL describes the standards for the fiber optic links between stations and repeaters, allowing up to 2 km per segment on multi-mode fiber. It replaces the 1987 FOIRL (Fiber Optic Inter-Repeater Link), which provides the specification for a fiber optic Media Attachment Unit (MAU) and other interconnecting components. Two related standards are essentially "dead": 10Base-FB allows up to 2 km per segment (on multi-mode fiber) and is designed for backbone applications such as cascading repeaters. In addition, there is the 10Base-FP (Passive components) standard

The 10Base-F standard allows for 1024 devices per network.

Fast Ethernet - 100Base-T

Fast Ethernet is the most popular of the newer standards and is an extension to 10Base-T. The '100' denotes 100 Mbps data speed and it uses the same two pairs as 10Base-T and must only be used on Category 5 UTP cable installations with provision for it to be used on Type 1 STP. The actual data throughput increases by between 3 to 4 times that of 10Base-T.

Fast Ethernet is specified in 802.3u and uses the same frame formats and CSMA/CD technology as normal 10Mbps Ethernet. The difference is that the maximum delay for the signal across the segment is 5.12 microseconds instead of 51.2 microseconds. This stems from the fact that the bit time (time to transmit one bit) is 0.01 microseconds and that the slot time for a frame is 512 bit times. The Inter-Packet Gap (IPG) for 802.3u is 0.96 microseconds as opposed to 9.6 microseconds for 10Mbps Ethernet.

Whereas 10Base-T uses Normal Link Pulses (NLP) for testing the integrity of the connection, 100Base-T uses Fast Link Pulses (FLP) which are backwardly compatible with NLPs but contain more information. FLPs are used to detect the speed of the network (e.g. in 10/100 switchable cards and ports). The distance must not exceed 100 m.

The IEEE uses the term 100Base-X to refer to both 100Base-Tx and 100Base-Fx and the Media-Independent Interface (MII) allows a generic connector for transceivers to connect to 100Base-Tx, 100Base-Fx and 100Base-T4 LANs.

There is no such thing as the 5-4-3 rule in Fast Ethernet. All 10Base-T repeaters are considered to be functionally identical. Fast Ethernet repeaters are divided into two classes of repeater: Class I and Class II. A Class I repeater has a repeater propagation delay value of 140 bit times, whilst a Class II repeater is 92 bit times. The Class I repeater (or Translational Repeater) can support different signaling types such as 100Base-Tx and 100Base-T4. A Class I repeater transmits or repeats the incoming line signals on one port to the other ports by first translating them to digital signals and then retranslating them to line signals. The translations are necessary when connecting different physical media (media conforming to more than one physical layer specification) to the same collision domain. Any repeater with an MII port would be a Class I device. Only one Class I repeater can exist within a single collision domain, so this type of repeater cannot be cascaded.

A Class II repeater immediately transmits or repeats the incoming line signals on one port to the other ports: it does not perform any translations. This repeater type connects identical media to the same collision domain (for example, TX to TX). At most, two Class II repeaters can exist within a single collision domain.

The cable used to cascade the two devices is called and unpopulated segment or IRL (Inter-Repeater Link). The Class II repeater (or **Transparent Repeater**) can only support one type of physical signaling.

100Base-T4

100Base-T4 was an early implementation of Fast Ethernet. It requires four twisted copper pairs, but those pairs were only required to be category 3 rather than the category 5 required by TX. One pair is reserved for transmit, one for receive, and the remaining two will switch direction as negotiated. A very unusual 8B6T code is used to convert 8 data bits into 6 base-3 digits (the signal shaping is possible as there are three times as many 6-digit base-3 numbers as there are 8-digit base-2 numbers). The two resulting 3-digit base-3 symbols are sent in parallel over 3 pairs using 3-level pulse-amplitude modulation (PAM-3).

100Base-T2

This little known version of Fast Ethernet is for use over two pairs of Category 3 cable and uses PAM-5 for encoding. There is simultaneous transmission and reception of data in both pairs and the electronics uses DSP technology to handle alien signals in adjacent pairs. 100Base-T2 can run up to 100 m on Category 3 UTP.

100Base-Fx

100Base-Fx is a version of Fast Ethernet over optical fiber. It uses a 1300 nm near-infrared (NIR) light wavelength transmitted via two strands of optical fiber, one for receive (RX) and the other for transmit (TX). Maximum length is 400 meters (1,310 ft) for half-duplex connections (to ensure collisions are detected) or 2 kilometers (6,600 ft) for full-duplex over multimode optical fiber. Longer distances are possible when using single-mode optical fiber. 100Base-Fx uses the same 4B5B encoding and NRZI line code that 100Base-TX does. 100Base-Fx should use the following connectors: SC, straight tip (ST), or media independent connectors (MIC), with SC being the preferred option. 100Base-Fx is not compatible with 10Base-Fl, the 10 MBit/s version over optical fiber.

100Base-Sx

100Base-Sx is a version of Fast Ethernet over optical fiber. It uses two strands of multi-mode optical fiber for receive and transmit. It is a lower cost alternative to using 100Base-Fx, because it uses short wavelength optics (850 nm) which are significantly less expensive than the long wavelength optics used in 100Base-Fx. 100Base-Sx can operate at distances up to 300 meters (980 ft).

100Base-Sx uses the same wavelength as 10Base-Fl, the 10 MBit/s version over optical fiber. Unlike 100Base-Fx, this allows 100Base-Sx to be backwards-compatible with 10Base-Fl. Because of the shorter wavelength used and the shorter distance it can support, 100Base-Sx uses less expensive optical components (LEDs instead of lasers) which makes it an attractive option for those upgrading from 10Base-Fl and those who do not require long distances.

100Base-Bx

100Base-Bx is a version of Fast Ethernet over a single strand of optical fiber (unlike 100Base-Fx, which uses a pair of fibers). Single-mode fiber is used, along with a special multiplexer which splits the signal into transmit and receive wavelengths. The two wavelengths used for transmit and receive are either 1310/1550 nm or 1310/1490 nm. Distances can be 10, 20, or 40 km.

100VG-AnyLAN

Based on 802.12 (Hewlett Packard), 100VG-AnyLAN uses an access method called Demand Priority. The 'VG' stands for 'Voice Grade' as it is designed to be used with Category 3 cable. This is where the repeaters (hubs) carry out continuous searches around all of the nodes for those that wish to send data. If two devices cause a 'contention' by wanting to send at the same time, the highest priority request is dealt with first, unless the priorities are the same, in which case both requests are dealt with at the same time (by alternating frames). The hub only knows about connected devices and other repeaters so communication is only directed at them rather than broadcast to every device in the broadcast domain (which could mean 100's of devices!). This is a more efficient use of the bandwidth. This is the reason why the new standard was developed as it is not strictly Ethernet. Standard 802.12 is designed to better support both Ethernet and Token Ring.

The encoding techniques used are 5B/6B and NRZ. All four pairs of UTP are used. On Cat3 the longest cable run is 100 m but this increases to 200 m on Cat5. The clock rate on each wire is 30 MHz; therefore 30 Mbits per second are transmitted on each pair giving a total bit rate of 120 Mbps. Since each 6-bits of data on the line represents 5 bits of real data due to the 5B/6B encoding, the rate of real data being transmitted is 25 Mbps on each pair, giving a total real data rate of 100 Mbps. For 2-pair STP and fiber, the bit rate is 120 Mbps on the transmitting pair, for a real data transmission rate of 100 Mbps.

Gigabit Ethernet

Although the functional principles of Gigabit Ethernet are the same as Ethernet and Fast Ethernet i.e. CSMA/CD and the Framing format, the physical setup is very different. One difference is the slot time. The standard Ethernet slot time required in CSMA/CD half-duplex mode is not long enough for running over 100 m of copper, so Carrier Extension is used to guarantee a 512-bit slot time.

1000Base-X (802.3z)

The 802.3z committee is responsible for formalizing the standard for Gigabit Ethernet. The 1000 refers to 1 Gbps data speed. The existing Fiber Channel interface standard (ANSI X3T11) is used and allows up to 4.268 Gbps speeds. The Fiber Channel encoding scheme is 8B/10B.

Gigabit Ethernet can operate in half or full duplex modes and there is also a standard 802.3x which manages XON/XOFF flow control in full duplex mode. With 802.3x, a receiving station can send a packet to a sending station to stop it sending data until a specified time interval has passed.

There are three media types for 1000Base-X. 1000Base-Sx, 1000Base-Lx, and 1000Base-Cx.

1000Base-Sx (‘S’ is for Short Haul) uses short-wavelength laser (850 nm) over multi-mode fiber. 1000Base-Sx can run up to 300 m on 62.5/125 µm multimode fiber and up to 550 m on 50/125 µm multimode fiber.

1000Base-Lx (‘L’ is for Long Haul) uses long wavelength laser (1300 nm) and can run up to 550 m on 62.5/125 µm multi-mode fiber or 50/125 µm multi-mode fiber. In addition, 1000Base-Lx can run up to 5 km (originally 3 km) on single-mode fiber using 1310 nm wavelength laser.

1000Base-Cx is a standard for STP copper cable and allows operation up to 25 m over STP cable.

1000Base-T (802.3ab)

Many cable manufacturers are enhancing their cable systems to ‘enhanced Category 5’ (Cat 5e) standards in order to allow Gigabit Ethernet to run at up to 100 m on copper. The Category 6 standard has yet to be ratified, and is not being pursued very strongly.

In order to obtain the 1000 Mbps data bit rate across the UTP cable without breaking the FCC rules for emission, all 4 pairs of the cable are used. Hybrid circuits at each end of each pair are used to allow simultaneous transmission and reception of data (full-duplex) by separating the transmission signal from the receiving signal. Because some transmission signal still manages to couple itself to the receiving side there is an additional echo canceller built in, this is called a Near End Crosstalk (NEXT) canceller.

Encoding is carried out with PAM-5.

TRANSMISSION CONTROL PROTOCOL / INTERNET PROTOCOL

Transmission **C**ontrol **P**rotocol / **I**nternet **P**rotocol (TCP/IP) is the communication protocol for the Internet.

Whereas IP handles lower-level transmissions from computer to computer as a message makes its way across the Internet, TCP operates at a higher level, concerned only with the two end systems, for example a Web browser and a Web server. In particular, TCP provides ordered delivery of a stream of bytes from a program on one computer to another program on another computer. Besides the Web, other common applications of TCP include e-mail and Internet file transfer like FTP. Among its other management tasks, TCP controls message size, the rate at which messages are exchanged, and network traffic congestion. Your computer Internet address is a part of the standard TCP/IP protocol and so is your domain name.

Inside the TCP/IP standard there are several protocols for handling data communication:

- TCP (Transmission Control Protocol) communication between applications
- UDP (User Datagram Protocol) simple communication between applications
- IP (Internet Protocol) communication between computers
- ICMP (Internet Control Message Protocol) for errors and statistics
- DHCP (Dynamic Host Configuration Protocol) for dynamic addressing

TCP: If one application wants to communicate with another via TCP, it sends a communication request. This request must be sent to an exact address. TCP is responsible for breaking data down into IP packets before they are sent, and for assembling the packets when they arrive. After a "handshake" between the two applications, TCP will set up a "full-duplex" communication between the two applications. The "full-duplex" communication will occupy the communication line between the two computers until it is closed by one of the two applications. UDP is very similar to TCP, but simpler and less reliable.

IP: IP is responsible for sending the packets to the correct destination. IP does not occupy the communication line between two computers and hence reduces the need for network lines. Each line can be used for communication between many different computers at the same time. With IP, messages (or other data) are broken up into small independent "packets" and sent between computers via the Internet. IP is responsible for "routing" each packet to the correct destination.

When an IP packet is sent from a computer, it arrives at an IP router. The IP router is responsible for "routing" the packet to the correct destination, directly or via another router. The path the packet will follow might be different from other packets in the same communication chain. The router is responsible for the right addressing, depending on traffic volume, errors in the network, or other parameters.

Each computer must have a unique IP address before it can connect to the Internet. Each IP packet must also have an address before it can be sent to another computer. TCP/IP uses 32 bits (4 bytes), of four numbers between 0 and 255, separated by a period, to address a computer. A typical IP address is of the format: 192.255.30.50

Domain Names: A name is much easier to remember than a 12 digit number. The names used for TCP/IP addresses are called domain names. "**navy.mil**" is a domain name. Subdomains are identified by prefixes to the main domain name (separated by a period). When you address a web site, like **http://www.navair.navy.mil** the name is translated to a number by a Domain Name System (DNS) Server. DNS servers are connected to the Internet all over the world. When a new domain name is registered together with a TCP/IP address, all DNS servers are updated with this information.

BROWSER AND OTHER APPLICATION LAYER PROTOCOLS

DHCP - Dynamic Host Configuration Protocol. DHCP is used for allocation of dynamic IP addresses to computers in a network.

FTP - File Transfer Protocol. FTP takes care of transmission of data files between computers.

HTTP - Hyper Text Transfer Protocol - takes care of the communication between a web server and a web browser. It is used for sending requests from a web client (a browser) to a web server, returning web content (web pages) from the server back to the client.

HTTPS - Secure HTTP. HTTPS typically handles credit card transactions and other sensitive data.

IMAP - Internet Message Access Protocol. The IMAP protocol is used by email programs (like Microsoft Outlook) just like the POP protocol (discussed below). The main difference between the IMAP protocol and the POP protocol is that the IMAP protocol will not automatically download all your emails each time your email program connects to your email server. The IMAP protocol allows you to look through your email messages at the email server before you download them. With IMAP you can choose to download your messages or just delete them. This way IMAP is useful if you need to connect to your email server from different locations, but only want to download your messages when you are back in your office.

NTP - Network Time Protocol. NTP is used to synchronize the time (the clock) between computers.

POP - Post Office Protocol. The POP protocol is used by email programs (like Microsoft Outlook) to retrieve emails from an email server. If your email program (also called email client), uses POP, all your emails are downloaded to your computer each time it connects to your email server.

SMTP - Simple Mail Transfer Protocol. The SMTP protocol is used for the transmission of e-mails to another computer. Normally your email is sent to an email server (SMTP server), and then to another server or servers, and finally to its destination. SMTP can only transmit pure text. It cannot transmit binary data like pictures, sounds, or movies directly. SMTP uses the MIME protocol to send binary data across TCP/IP networks.

SNMP - Simple Network Management Protocol. SNMP is used for administration of computer networks.

PRESENTATION LAYER PROTOCOLS

MIME - Multi-purpose Internet Mail Extensions protocol. Converts binary data to pure text. The MIME protocol lets SMTP transmit multimedia files including voice, audio, and binary data.

SSL - Secure Sockets Layer. The SSL protocol is used for encryption of data for secure data transmission.

LOWER LAYER PROTOCOLS

ARP - Address Resolution Protocol. ARP is used by IP to find the hardware address of a computer network card based on the IP address.

BOOTP - Boot Protocol. BOOTP is used for booting (starting) computers from the network.

ICMP - Internet Control Message Protocol. ICMP takes care of error-handling in the network.

LDAP - Lightweight Directory Access Protocol. LDAP is used for collecting information about users and e-mail addresses from the internet.

PPTP - Point to Point Tunneling Protocol. PPTP is used for setting up a connection (tunnel) between private networks.

RARP - Reverse Address Resolution Protocol. RARP is used by IP to find the IP address based on the hardware address of a computer network card.

This page intentionally left blank.

GLOSSARY

ACCEPTABLE DEGRADATION - The allowable reduction in system performance. For a fire control radar, the acceptable degradation is usually expressed as a reduction in range; for example, the maximum lock-on range might be degraded by 25 percent without loss of essential defense capability.

ACQUISITION - A procedure by which a fire control tracking radar attains initial lock-on. Usually, the approximate target coordinates are supplied to the tracking radar and it searches a predetermined volume of space to locate the target.

AEROSOLS - Solid particles dispersed in the atmosphere having resonant size particles with a high index of refraction. The particles both scatter and absorb visual and laser directed energy so as to cut down on weapon systems directed by these techniques.

AFC (AUTOMATIC FREQUENCY CONTROL) - An arrangement whereby the frequency of an oscillator or the tuning of a circuit is automatically maintained within specified limits with respect to a reference frequency. A magnetron drifts in frequency over a period of time. The AFC of a radar makes the local oscillator shift by an equal amount so the IF frequency will remain constant.

AGC (AUTOMATIC GAIN CONTROL) - A method for automatically obtaining an essentially constant receiver output amplitude. The amplitude of the received signal in the range gate determines the AGC bias (a DC voltage) which controls the receiver gain so as to maintain a nearly constant output even though the amplitude of the input signal changes.

AMPLIFIER - An electronic device used to increase signal magnitude or power. See also GaAs FET Amplifier, Klystron Amplifier, Traveling-Wave Tube Amplifier.

AMPLITUDE MODULATION (AM) - A method of impressing a message upon a carrier signal by causing the carrier amplitude to vary proportionally to the message waveform.

AMPLITUDE SHIFT KEYING (ASK) - A method of impressing a digital signal upon a carrier signal by causing the carrier amplitude to take different values corresponding to the different values of the digital signal.

ANGLE JAMMING - ECM technique, when azimuth and elevation information from a scanning fire control radar is jammed by transmitting a jamming pulse similar to the radar pulse, but with modulation information out of phase with the returning target angle modulation information.

ANGULAR SEPARATION - This term is frequently used to indicate a protective (from EMI) zone for a missile. The interfering antenna axis must be separated, throughout the critical portion of the missile flight, from the missile by the specified angle. The vertex of the angle is at the interference source antenna.

ANTENNA BEAMWIDTH - The angle, in degrees, between the half-power points (-3 dB) of an antenna beam. This angle is also nearly that between the center of the mainlobe and the first null. The angle is given for both horizontal and vertical planes unless the beam is circular. When so indicated, the term may refer to the angular width of the mainlobe between first nulls [beamwidth between first nulls (BWFN)]. See also Antenna Pattern. The figure illustrates vertical profile for antenna displaying a 10-degree beamwidth characteristic. The values can vary dramatically with frequency.



ANTENNA CROSS TALK - A measure of undesired power transfer through space from one antenna to another. Ratio of power received by one antenna to power transmitted by the other, usually expressed in decibels.

ANTENNA ISOLATION - The ratio of the power input to one antenna to the power received by the other. It can also be viewed as the insertion loss from transmit antenna input to receive antenna output to circuitry.



ANTENNA LOBING - Two lobes are created that overlap and intercept at -1 to -3 dB. The difference between the two lobes produces much greater spatial selectivity than provided by either lobe alone. (See also Lobe, Antenna.)

ANTENNA NUTATING - An antenna, as used in automatic-tracking radar systems, consisting of a parabolic reflector combined with a radiating element which is caused to move in a small circular orbit about the focus of the antenna with or without change of polarization. The radiation pattern is in the form of a beam that traces out a cone centered on the reflector axis. The process is also known as nutating conical scanning.



ANTENNA PATTERN - A cross section of the radiating pattern (representing antenna gain or loss) in any plane that includes the origin (source reference point) of the pattern. Both horizontal and vertical polar plots are normally used to describe the pattern. Also, termed "polar diagram" and "radiation pattern."

ANTENNA, PENCIL-BEAM - A highly directional antenna designed that cross sections of the major lobe are approximately circular, with a narrow beamwidth.

ANTI-CLUTTER CIRCUITS (IN RADAR) - Circuits which attenuate undesired reflections to permit detection of targets otherwise obscured by such reflections.

APERTURE - In an antenna, that portion of the plane surface area near the antenna perpendicular to the direction of maximum radiation through which the major portion of the radiation passes. The effective and/or scattering aperture area can be computed for wire antennas which have no obvious physical area.

A-SCOPE - A cathode-ray oscilloscope used in radar systems to display vertically the signal amplitude as a function of time (range) or range rate. Sometimes referred to as Range (R)-Scope.

ASYNCHRONOUS PULSED JAMMING - An effective form of pulsed jamming. The jammer nearly matches the pulse repetition frequency (PRF) of the radar; then it transmits multiples of the PRF. It is more effective if the jammer pulsewidth is greater than that of the radar. Asynchronous pulsed jamming is similar to synchronous jamming except that the target lines tend to curve inward or outward slightly and appear fuzzy in the jammed sector of a radar scope.

ATTENUATION - Decrease in magnitude of current, voltage, or power of a signal in transmission between two points. May be expressed in decibels.

AUTOMATIC FREQUENCY CONTROL - See AFC.

AUTOMATIC GAIN CONTROL - See AGC.

BACKWARD WAVE OSCILLATOR (BWO) - A cross-field device in which an electron stream interacts with a backward wave on a nonreentrant circuit. This oscillator may be electronically tuned over a wide range of frequencies, is relatively unaffected by load variations and is stable. BWO is commonly pronounced "be woe".

BALANCED MIXERS - The two most frequently encountered mixer types are single-balanced and double-balanced. In a double-balanced mixer, four Schottky diodes and two wideband transformers are employed to provide isolation of all three ports.

BALLISTIC MISSILE - Any missile which does not rely upon aerodynamic surfaces to produce lift and consequently follows a ballistic trajectory when thrust is terminated.

BANDPASS FILTER - A type of frequency discrimination network designed to pass a band or range of frequencies and produce attenuation to all other frequencies outside of the pass region. The figure illustrates a typical bandpass filter, incorporating a bandpass region of (F_h)-(F_l), offering no rejection (0 dB) to desired signal (F_m) and much higher rejection to the adjacent undesired signals F_h, and F_l. The upper and lower frequencies are usually specified to be the half power (-3 dB) or half voltage points (-6 dB).



BANDWIDTH - An expression used to define the actual operational frequency range of a receiver when it is tuned to a certain frequency. For a radar receiver, it is the difference between the two frequencies at which the receiver response is reduced to some fraction of its maximum response (such as 3 dB, 6 dB, or some other specified level). The frequencies between which "satisfactory" performance is achieved. Two equations are used:

$$\textit{Narrowband by \%}\ \left(\frac{F_u - F_l}{F_c}\right)(100)\ \ ;\ \ \textit{Broadband by ratio}\ \frac{F_u}{F_l}$$

$$\textit{Where}\ F_u = \textit{Upper}\ ;\ F_l = \textit{lower}\ ;\ F_c = \textit{center} = (\ F_u + F_l\ ) \div 2$$

See also Receiver Bandwidth and Spectrum Width.

BARRAGE NOISE JAMMING - Noise jamming spread in frequency to deny the use of multiple radar frequencies to effectively deny range information. Although this is attractive because it enables one jammer to simultaneously jam several radars of different frequencies, it does have the inherent problem that the wider the jamming spread, the less jamming power available per radar, i.e. the watts per MHz bandwidth is low.

BATTERY, MISSILE - A missile battery consists of a missile launcher and its associated missile fire control systems (such as a MK 11 MOD 0 Missile Launcher and two MK 74 MOD 0 Missile Fire Control Systems).

BEACON - A system wherein a transponder in a missile receives coded signals from a shipboard radar guidance transmitter and transmits reply signals to a shipboard radar beacon receiver to enable a computer to determine missile position. The missile beacon transmitter and shipboard radar beacon receiver are tuned to a frequency different from that of the guidance transmitter.

BEAM - See Lobe, antenna. The beam is to the side of an aircraft or ship.

BEAM, CAPTURE - See Capture Beam.

BEAM-TO-BEAM CORRELATION (BBC) - BBC is used by frequency scan radars to reject pulse jamming and jamming at a swept frequency. Correlation is made from two adjacent beams (pulses). The receiver rejects those targets (signals) that do not occur at the same place in two adjacent beams.

BEAMWIDTH - See Antenna Beamwidth.

BEAT FREQUENCY OSCILLATOR (BFO) - Any oscillator whose output is intended to be mixed with another signal to produce a sum or difference beat frequency. Used particularly in reception of CW transmissions.

BINGO - The fuel state at which an aircraft must leave the area in order to return and land safely. Also used when chaff/flares reach a preset low quantity and automatic dispensing is inhibited.

BIPOLAR VIDEO - Unrectified (pre-detection) IF (both positive and negative portions of the RF envelope) signals that arise from the type of detection and console display employed in pulse Doppler and MTI receivers.

BISTATIC RADAR - A radar using antennas at different locations for transmission and reception.

BLANKING - The process of making a channel, or device non-effective for a certain interval. Used for retrace sweeps on CRTs or to mask unwanted signals such as blanking ones own radar from the onboard RWR.

BOGEY - Unknown air target.

BURN-THROUGH RANGE - The ability of a radar to see through jamming. Usually, described as the point when the radar's target return is a specified amount stronger than the jamming signal (typical values are 6 dB manual and 20 dB automatic). See Section 4-8.

BUTT LINE - Line used for reference in measurement of left/right location. One of several aircraft references. See also fuselage station and water line.

CAPTURE BEAM - A wide beam incorporated in capture transmitters of beam rider (command guided) missile systems to facilitate gaining initial control of a missile immediately after launch. Upon capture, the system then centers the missile in the narrow guidance beam. The figure illustrates a launched missile at point of capture.



CAPTURE TRANSMITTER - A transmitter employing a wide beam antenna to gain initial control of in-flight missile for the purpose of centering the missile in the guidance transmitter antenna beam. See also Capture Beam.


fc (Carrier Frequency)
Spectral Line Spacing = 1/PRI
Amplitude changes from + to - at every 1/PW interval
1/PRI
Frequency
-3/PW
-2/PW
-1/PW
1/PW
2/PW
3/PW

CARRIER FREQUENCY - The basic radio frequency of the wave upon which modulations are impressed. Also called “Carrier” or f_c. See figure at right.

CATCH-22 - A lose-lose situation, from the book of the same name.

CAVITY - A space enclosed by a conducting surface used as a resonant circuit at microwave frequencies. Cavity space geometry determines the resonant frequency. A storage area for oscillating electromagnetic energy.

CENTER FREQUENCY - The tuned or operating frequency. Also referred to as center operating frequency. In frequency diversity systems, the midband frequency of the operating range. See also Carrier Frequency.

CHAFF - Ribbon-like pieces of metallic materials or metalized plastic which are dispensed by aircraft or ships to mask or screen other “targets.” The radar reflections off the chaff may cause a tracking radar to break lock on the target. The foil materials are generally cut into small pieces for which the size is dependent upon the radar interrogation frequency (approximately 1/2 wave length of the victim radar frequency). Being this length, chaff acts as a resonant dipole and reflects much of the energy back to the radar. Also see rainbow, rope, stream chaff, and window.

CHANNEL - A frequency or band of frequencies. In guided missile systems, an assigned center frequency and a fixed bandwidth around it. Designates operating frequency of track radars and frequency/code assignments of X-band CW illuminators.

CHIRP - A pulse compression technique which uses frequency modulation (usually linear) on pulse transmission.

CHIRP RADAR - See PC.

CIRCULARLY POLARIZED JAMMING - The techniques of radiating jamming energy in both planes of polarization simultaneously. With this method, there is a loss of 3 dB of effective power in either linear plane, and substantial loss if the opposite sense of circular polarization is used (i.e. left vs. right). See Section 3-2.



CLUTTER, RADAR - Undesired radar returns or echoes resulting from man-made or natural objects including chaff, sea, ground, and rain, which interfere with normal radar system observations. The figure illustrates a target being masked by ground clutter

CO-CHANNEL - This term is used to indicate that two (or more) equipments are operating on the same frequency.

COHERENT - Two signals that have a set (usually fixed) phase relationship.

COINCIDENCE DETECTOR - This radar video process requires more than one hit in a range cell before a target is displayed. This prevents video interference from pulses coming from another radar, because such interference is unlikely to occur twice in the same range cell.

COLLIMATION - The procedure of aligning fire control radar system antenna axes with optical line of sight, thereby ensuring that the radars will provide for correct target illumination and guidance beam positioning.

COMMAND CODE - Modulations superimposed upon transmitter carrier signals to provide electronic instructions to an airborne guided missile or pilotless aircraft. The receiver of the remotely guided vehicle is preset to accept only a selected transmitter code to eliminate the possibility of the vehicle responding to commands of extraneous signals. Missile command codes include instructions such as arm, warhead detonate, and self destruct.

COMMAND GUIDANCE - A guidance system wherein intelligence transmitted to the missile from an outside source causes the missile to traverse a directed flight path.

CONICAL SCAN - See Antenna, Nutating.

CONTINUOUS WAVE and CONTINUOUS WAVE ILLUMINATOR - See CW and CWI.

COOPERATIVE COUNTERMEASURES - (CO-OP) Generic term for jamming the same threat radar from two or more separate platforms that are in the same radar resolution cell.

COUPLING FACTOR - A multiplying factor, expressed in dB, used to express the change in EM energy intensity from a radar transmitter to a receiver. The factor includes the antenna gains and the loss (basic transmission loss) caused by the distance between the antennas. The factor will usually be a negative dB figure (a reduction in intensity) because basic transmission loss is always a large negative value. The antenna gains may be positive (pointed toward each other) or negative (no main beam interactions).

CROSS MODULATION - Intermodulation caused by modulation of the carrier by an undesired signal wave.

CROSS POLARIZATION - or "Cross Pole," is a monopulse jamming technique where a cross-polarized signal is transmitted to give erroneous angle data to the radar. The component of the jamming signal with the same polarization as the radar must be very small.

CW (CONTINUOUS WAVE) - In radar and EW systems this term means that the transmitter is on constantly; i.e., not pulsed (100% duty cycle). These systems may frequency or phase modulate the transmitter output. A CW radar has the ability to distinguish moving targets against a stationary background while conserving spectrum bandwidth compared to pulsed radar requirements. A CW radar extracts accurate target range-rate data but cannot determine target range.

CWI (CONTINUOUS WAVE ILLUMINATOR) - A surface or aircraft-based CW transmitter employed in semiactive homing missile systems where the transmitter illuminates the target and the missile senses the reflected energy. The transmitter also provides a reference signal to the missile rear receiver to allow determination of range-rate data and target identification. CW transmitter emissions are sometimes coded corresponding to the associated missile receiver codes to reduce the possibility of the "missile accepting commands of extraneous signals.

DECIBEL (dB) - A dimensionless unit for expressing the ratio of two values of power, current, or voltage. The number of decibels being equal to: dB = 10 log P_2/P_1 = 20 log V_2/V_1 = 20 log I_2/I_1 Normally, used for expressing transmission gains, losses, levels, and similar quantities. See Section 2-4.

DECEPTION - The deliberate radiation, reradiation, alteration, absorption or reflection of electromagnetic energy in a manner intended to mislead the enemy interpretation or use of information received by his electronic systems.

dB - See Decibel, or Decibel Section 2-4.

dBc - Decibels referenced to the carrier signal.

dBi - Decibels referenced to an isotropic radiator. (dBLi indicating linear isotropic radiator is sometimes used).

dBm - Decibels relative to 1 mW. dBm is calculated by using the ratio of some power (expressed in mW) to 1 mW. For example, 1 mW is 0 dBm and 10 mW is +10 dBm.

dBsm - Decibel referenced to one square meter.

dBv / dBμv - Decibels referenced to one volt or microvolt, i.e. 0 dBv is 1 volt or 120 dBμv.

dBW / dBμW - Decibels referenced to 1 watt or one microwatt, i.e. 0 dBW is 1 watt or 30 dBm or 60 dBμW.

DEMODULATOR - A device employed to separate the modulation signal from its associated carrier, also called Second Detector. See also Detection.

DESIGNATION - The assignment of a fire control radar to a specific target by supplying target coordinate data to the radar system.

DETECTION - Usually refers to the technique of recovering the amplitude modulation signal (envelope) superimposed on a carrier. See figure at right.



DICKE FIX - This type of radar processing occurs in the IF amplifier. A limiter follows a wideband amplifier, and then the signal goes to a matched filter amplifier. This discriminates against pulses that are too long (clutter) or too short (interference). The "DICKE FIX" is a technique that is specifically designed to protect the receiver from ringing caused by noise, fast-sweep, or narrow pulse jamming. The basic configuration consists of a broadband limiting IF amplifier, followed by an IF amplifier of optimum bandwidth. The limit level is preset at approximately the peak amplitude of receiver noise, the bandwidth may vary from 10 to 20 MHz, depending on the jamming environment. This device provides excellent discrimination against fast sweep jamming (10-500 MHz), usually something on the order of 20 to 40 dB, without appreciable loss in sensitivity. However, strong CW jamming will seriously degrade the performance of the DICKE FIX because the CW signal captures the radar signal in the limiter.

DIELECTRICALLY STABILIZED OSCILLATOR - The DSO uses a dielectric resonator as the frequency determining element. When the dielectric material is properly selected and used, the variations in dielectric constant vs. temperature and the dimensions of the resonant structure vs. temperature tend to cancel out, providing relatively good frequency vs. temperature stability. The DSO offers frequency accuracy and stability, low power consumption and high reliability. Some of the commonly used materials are barium, zirconium, or tin tinates. The composition of these materials may be controlled to achieve any frequency variation with temperature with close tolerances.

DIODE - An electronic device which restricts current flow chiefly to one direction. See also Gunn diode, IMPATT diode, PIN diode, point contact diode, Schottky barrier diode, step recovery diode, tunnel diode, varactor diode.

DIODE SWITCH - PIN-diode switches provide state-of-the-art switching in most present-day microwave receivers. These switches are either reflective or nonreflective in that the former reflect incident power back to the source when in the isolated state. While both types of switches can provide high isolation and short transition times, the reflective switch offers multi octave bandwidth in the all shunt diode configuration, while the non-reflective switch offers an octave bandwidth.

DIPLEX - The simultaneous transmission or reception of two signals using a common feature such as a single antenna or carrier. Typically, two transmitters operate alternately at approximately the same RF and using a common antenna. See Section 6-7 for a discussion of diplexers.

DIRECTIONAL COUPLER - A 4-port transmission coupling device used to sample the power traveling in one direction through the main line of the device. There is considerable isolation (typically 20 dB) to signals traveling in the reverse direction. Because they are reciprocal, the directional coupler can also be used to directively combine signals with good reverse isolation. The directional coupler is implemented in waveguide and coaxial configurations. See Section 6-4.

DIRECTIVITY - For antennas, directivity is the maximum value of gain in a particular direction. (Isotropic point source has directivity = 1). For directional couplers, directivity is a measure (in dB) of how good the directional coupling is and is equal to the isolation minus the coupling. See Section 6-4.

DISH - A microwave reflector used as part of a radar antenna system. The surface is concave and is usually parabolic shaped. Also called a parabolic reflector.

DOPPLER EFFECT - The apparent change in frequency of an electromagnetic wave caused by a change in distance between the transmitter and the receiver during transmission/reception. The figure illustrates the Doppler increase that would be realized by comparing the signal received from a target approaching the radar site to the transmitted reference signal. An apparent frequency decrease would be noted for targets departing the radar location. Differences can be calibrated to provide target range-rate data.



DRY RUN - A test run with aircraft/ship armament and/or EW switches off.

DUCTING - The increase in range that an electromagnetic wave will travel due to a temperature inversion of the atmosphere. The temperature inversion forms a channel or waveguide (duct) for the waves to travel in, and they can be trapped, not attenuating as would be expected from the radar equation.

DUMMY LOAD (Radio Transmission) - A dissipative but essentially nonradiating substitute device having impedance characteristics simulating those of the antenna. This allows power to be applied to the radar transmitter without radiating into free space. Dummy loads are commonly used during EMCON conditions or when troubleshooting a transmitter at a workbench away from its normal environment.

DUPLEXER - A switching device used in radar to permit alternate use of the same antenna for both transmitting and receiving.



DUTY CYCLE - The ratio of average power to peak power, or ratio of pulse length to interpulse period for pulsed transmitter systems. Interpulse period is equal to the reciprocal of the pulse repetition rate. See Section 2-5.

The duty cycle of a radar having a pulse length of 0.3 μsec and a PRF of 2000 pulses/sec is computed as follows:

Interpulse Period, T = PRI = 1/PRF = 500 μsec

$$Duty\ Cycle = \frac{Pulse\ length}{Interpulse\ Period} = \frac{0.3\ \mu\text{sec}}{500\ musec} = 0.0006\ (or\ 0.06\%)$$ or Duty Cycle (dB) = 10log(Duty cycle) = -32.2 dB

An output tube providing an average power of only 90 watts for such a system would, therefore, provide a peak power of:

$$Peak\ Power = \frac{Average\ Power}{Duty\ Cycle} = \frac{90}{0.0006} = 150{,}000\ W\ or\ 52\ dBW\ or\ 82\ dBm$$

EFFECTIVE RADIATED POWER (ERP) - Input power to the antenna in watts times the gain ratio of the antenna. When expressed in dB, ERP is the transmitter power (P_T), in dBm (or dBW) plus the antenna gain (G_T) in dB. The term EIRP is used sometimes and reiterates that the gain is relative to an isotropic radiator.

EGRESS - Exit the target area.

ELECTROMAGNETIC COUPLING - The transfer of electromagnetic energy from one circuit or system to another circuit or system. An undesired transfer is termed EMI (electromagnetic interference).

EMC (ELECTROMAGNETIC COMPATIBILITY) - That condition in which electrical/electronic systems can perform their intended function without experiencing degradation from, or causing degradation to other electrical/electronic systems. More simply stated, EMC is that condition which exists in the absence of EMI. See also Intersystem and Intrasystem EMC tests.

EME (ELECTROMAGNETIC ENVIRONMENT) - The total electromagnetic energy in the RF spectrum that exists at any given location.

EMI (ELECTROMAGNETIC INTERFERENCE) - Any induced, radiated, or conducted electrical emission, disturbance, or transient that causes undesirable responses, degradation in performance, or malfunctions of any electrical or electronic equipment, device, or system. Also synonymously referred to as RFI (Radio Frequency Interference).

EMI MODEL - Usually a set of equations or logical concepts designed to illustrate the interactions, the detailed parameters considerations, and mathematical procedures necessary for proper analysis of a given EMI situation.

EMITTER - Any device or apparatus which emits electromagnetic energy.

EMP (ELECTROMAGNETIC PULSE) - The generation and radiation of a very narrow and very high-amplitude pulse of electromagnetic noise. It is associated with the high level pulse as a result of a nuclear detonation and with intentionally generated narrow, high-amplitude pulse for ECM applications. In the case of nuclear detonations, EMP consists of a continuous spectrum with most of its energy distributed through the low frequency band of 3 KHz to 1 MHz.

ERROR SIGNAL - In servomechanisms, the signal applied to the control circuit that indicates the degree of misalignment between the controlling and the controlled members. In tracking radar systems, a voltage dependent upon the signal received from a target whose polarity and magnitude depend on the angle between the target and the center axis of the scanning beam.

FAST TIME CONSTANT - See FTC.

FEET DRY / WET - Aircraft has crossed from water to shore / aircraft has crossed from shore to water.

FERRET - An aircraft, ship, or vehicle especially equipped for the detection, location, recording, and analyzing of electromagnetic radiations.

FIELD STRENGTH - The magnitude of a magnetic or electric field at any point, usually expressed in terms of ampere turns per meter or volts per meter. Sometimes called field intensity and is expressed in volts/meter or dBμv/meter. Above 100 MHz, power density terminology is used more often. See Section 4-1.

FIRST HARMONIC - The fundamental (original) frequency.

FREQUENCY AGILITY - A radar's ability to change frequency within its operating band, usually on a pulse-to-pulse basis. This is an ECCM technique employed to avoid spot jamming and to force the jammer to go into a less effective barrage mode.

FREQUENCY AGILITY RADAR - A radar that automatically or semiautomatically tunes through a discrete set of operating frequencies in its normal mode of operation.

FREQUENCY DIVERSITY RADAR - A radar system technique, employed primarily as an antijamming feature, where the transmitter output frequency varies randomly from pulse to pulse over a wide frequency range.

FREQUENCY RANGE - (1) A specifically designated portion of the frequency spectrum; (2) of a device, the band of frequencies over which the device may be considered useful with various circuit and operating conditions; (3) of a transmission system, the frequency band in which the system is able to transmit power without attenuating or distorting it more than a specified amount.

FREQUENCY SHIFT KEYING (FSK) - A form of FM where the carrier is shifted between two frequencies in accordance with a predetermined code. In multiple FSK, the carrier is shifted to more than two frequencies. FSK is used principally with teletype communications.

"FRUIT" - In a radar beacon system, there is a type of interference called "FRUIT," caused by beacon replies to interrogation asynchronous with the observer's interrogator. The largest amount of this interference is received through the sidelobes of the interrogating antenna, but it can become dense enough to cause false target indications.

FTC (FAST TIME CONSTANT) - An antijam feature employed in radar systems where receiver circuits may be selected to provide a short time constant to emphasize signals of short duration to produce discrimination against the low frequency components of clutter.

FUNDAMENTAL FREQUENCY - Used synonymously for tuned frequency, carrier frequency, center frequency, output frequency, or operating frequency.

FUSELAGE STATION or just STATION - A reference point (usually the nose of an aircraft) used to measure or identify fore and aft locations. One of several aircraft location designations - also see butt line and water line.

GaAs FET AMPLIFIER - Because of their low noise, field-effect transistors are often used as the input stage of wideband amplifiers. Their high input resistance makes this device particularly useful in a variety of applications. Since the FET does not employ minority current carriers, carrier storage effects are eliminated giving the device faster operating characteristics and improved radiation resistant qualities.

GAIN - For antennas, the value of power gain in a given direction relative to an isotropic point source radiating equally in all directions. Frequently expressed in dB (gain of an isotropic source = 0 dB). The formula for calculating gain is:

$$G = \frac{4\pi\, P(\theta,\phi)}{P_{in}} \quad ;\, where \quad \begin{array}{l} P(\theta,\phi) = \text{Radiation intensity in given direction} \\ P_{in} = \text{Power into lossless antenna radiating uniformly in all directions} \end{array}$$

Note: (1) If radiation efficiency is unity, then gain = directivity i.e. if directivity = 2, then gain = 3 dB, etc.
(2) Interference losses within an array also affect gain
(3) See Section 3-1 for further details

For amplifiers, gain is the ratio of the output power to input power (usually in dB).

GATE (RANGE) - A signal used to select radar echoes corresponding to a very short range increment. Range is computed by moving the range gate or marker to the target echo; an arrangement which permits radar signals to be received in a small selected fraction of the time period between radar transmitter pulses.

GATING - (1) The process of selecting those portions of a wave which exist during one or more selected time intervals; (2) the application of a square waveform of desired duration and timing to perform electronic switching; (3) the application of receiver operating voltages to one or more stages only during that portion of a cycle of operation when reception is desired. See also Gate (Range).

GCI (GROUND-CONTROLLED INTERCEPT) - Vectoring an interceptor aircraft to an airborne target by means of information relayed from a ground-based radar site which observes both the interceptor and the target.

GIGA - A prefix meaning 10^9 (times a billion). For example, gigahertz (GHz).

GLINT (In Radar) - 1. The random component of target location error caused by variations in the phase front of the target signal (as contrasted with Scintillation Error). Glint may affect angle, range of

Doppler measurements, and may have peak values corresponding to locations beyond the true target extent in the measured coordinate. 2. Electronic countermeasures that uses the scintillating, or flashing effect of shuttered or rotating reflectors to degrade tracking or seeking functions of an enemy weapons system.

GUARDBAND - A frequency band to which no other emitters are assigned as a precaution against interference to equipments susceptible to EMI in that band.

GUIDANCE, BEAM RIDER - A missile guidance technique which is dependent on the missile's ability to determine its positions with reference to the center of scan of the guidance radar beam and thus correct its trajectory on the basis of detected errors.

GUIDANCE CODE - A technique of modulating guidance transmitter carriers with coded pulses compatible with the receiver code of the missile assigned that system, thus reducing the possibility of the missile accepting erroneous commands of other transmissions.

GUIDANCE, COMMAND - A guidance system wherein intelligence transmitted to the missile from an outside source causes the missile to traverse a directed path in space.

GUIDANCE, HOMING, ACTIVE - A system of homing guidance wherein both the transmitter and receiver are carried within the missile.

GUIDANCE, HOMING, PASSIVE - A form of homing guidance, which is dependent on a missile's ability to detect energy emitted by the target. Frequently termed Home-On-Jam (HOJ).

GUIDANCE, HOMING, SEMIACTIVE - A system of homing guidance wherein the missile uses reflected signals from the target which has been illuminated by a source other than within the missile. See also CWI.

GUIDANCE, INERTIAL - A self-contained system independent of information obtained from outside the missile, usually using Newton's second law of motion.

GUNN DIODE - The Gunn diode is a transferred electron device which because of its negative resistance can be used in microwave oscillators or amplifiers. When the applied voltage exceeds a certain critical value, periodic fluctuations in current occur. The frequency of oscillation depends primarily upon the drift velocity of electrons through the effective length of the device. This frequency may be varied over a small range by means of mechanical tuning.

HARMONIC - A sinusoidal component of a periodic wave or quantity having a frequency that is an integral multiple of the fundamental frequency. For example, a component which is twice the fundamental frequency is called the second harmonic. (The fundamental is the first harmonic, which is frequently misunderstood.)

HERTZ - The unit of frequency equal to one cycle per second.

HOME-ON-JAM (HOJ) - See Guidance, Homing, Passive.

HORN ANTENNA - A flared, open-ended section of waveguide used to radiate the energy from a waveguide into space. Also termed "horn" or "horn radiator." Usually linearly polarized, it will be vertically polarized when the feed probe is vertical, or horizontally polarized if the feed is horizontal. Circular polarization can be obtained by feeding a square horn at a 45° angle and phase shifting the vertical or horizontal excitation by 90°.

HYPERABRUPT VARACTOR OSCILLATOR - Due to a non-uniform concentration of N-type material (excess electrons) in the depletion region, this varactor produces a greater capacitance change in tuning voltage and a far more linear voltage-vs.-frequency tuning curve. As a result, this device has an improved tuning linearity and low tuning voltage.

IF (INTERMEDIATE FREQUENCY) - The difference frequency resulting from mixing (beating) the received signal in a superheterodyne receiver with the signal from the local oscillator. The difference frequency product provides the advantages inherent to the processing (amplification, detection, filtering, and such) of low frequency signals. The receiver local oscillator may operate either below or above the receiver tuned frequency. A single receiver may incorporate multiple IF detection.

$IF = F_{LO} - F_O$ (for a local oscillator operating above the fundamental)

where:
F_O = Received fundamental frequency
F_{LO} = Local oscillator frequency


Antenna
Mixer
60 MHz IF
Desired received signal (1050 MHz)
Local Oscillator (1110 MHz)

The simplified block diagram illustrates a typical mixing procedure employed in radar systems to obtain desired IF frequencies. The local oscillator is tuned above the fundamental frequency in this example. It should be noted that an undesired signal received at the receiver image frequency of 1170 MHz will also produce the desired 60 MHz IF frequency; this relationship provides the receiver image. See also Image Frequency.

IFF (IDENTIFICATION FRIEND OR FOE) - A system using radar transmission to which equipment carried by friendly forces automatically responds by emitting a unique characteristic series of pulses thereby distinguishing themselves from enemy forces. It is the "Mode IV" for the aircraft transponder. See also transponder.


Desired received signal (1050 MHz)
Antenna
$F_{LO} - F_O = IF$
$F_I - F_{LO} = IF$
$F_I = F_O + 2\ IF$
Image Frequency (F_I = 1170 MHz)
Mixer
60 MHz IF
Lower Sideband
$IF = F_{LO} - F_O = \Delta f$
F_O
F_{LO}
F_I
Δf
Δf
Local Oscillator (F_{LO} = 1110 MHz)
Upper Sideband
$IF = F_O - F_{LO} = \Delta f$
F_I
F_{LO}
F_O
Δf
Δf

IMAGE FREQUENCY - That frequency to which a given superheterodyne receiver is inherently susceptible, thereby rendering such a receiver extremely vulnerable to EMI at that frequency. The image frequency is located at the same frequency difference (Δf) to one side of the local oscillator as the tuned (desired) frequency is to the other side. An undesired signal received at the image frequency by a superheterodyne receiver not having preselection would, therefore, mix (beat) with the oscillator, produce the proper receiver IF, and be processed in the same manner as a signal at the desired frequency. See also receiver selectivity.

IMAGE JAMMING - Jamming at the image frequency of the radar receiver. Barrage jamming is made most effective by generating energy at both the normal operating and image frequency of the radar.

Image jamming inverts the phase of the response and is thereby useful as an angle deception technique. Not effective if the radar uses image rejection.

IMPATT DIODE - The IMPATT (IMPact Avalanche and Transit Time) diode acts like a negative resistance at microwave frequencies. Because of this property, Impatt diodes are used in oscillators and amplifiers. Usually the frequency range is in the millimeter wave region where other solid state devices cannot compete.

INGRESS - Go into the target area.

INSERTION LOSS - The loss incurred by inserting an element, device, or apparatus in an electrical/electronic circuit. Normally expressed in decibels determined as 10 log of the ratio of power measured at the point of insertion prior to inserting the device (P_1) to the power measured after inserting the device (P_2). Insertion loss (dB) = 10 log P_1/P_2.

INTEGRATION EFFECT - Pulse radars usually obtain several echoes from a target. If these echoes are added to each other, they enhance the S/N ratio, making a weak target easier to detect. The noise and interference do not directly add from pulse to pulse, so the ratio of target strength to undesired signal strength improves making the target more detectable. Random noise increases by the square root of the number of integrations, whereas the signal totally correlates and increases directly by the number of integrations, therefore the S/N enhancement is equal to the square root of the number of integrations.

INTERFERENCE - See EMI.

INTERFERENCE PARAMETERS - Equipment and propagation characteristics necessary for the proper evaluation of a given EMI situation.

INTERFERENCE/SIGNAL RATIO - See I/S Ratio.

INTERFERENCE THRESHOLD - The level of interference normally expressed in terms of the I/S (interference/signal) ratio at which performance degradation in a system first occurs as a result of EMI.

INTERFEROMETER - When two widely spaced antennas are arrayed together, they form an interferometer. The radiation pattern consists of many lobes, each having a narrow beamwidth. This antenna can provide good spatial selectivity if the lobe-to-lobe ambiguity can be solved such as using amplitude comparison between the two elements.

INTERMODULATION - The production, in a nonlinear element (such as a receiver mixer), of frequencies corresponding to the sums and differences of the fundamentals and harmonics of two or more frequencies which are transmitted through the element; or, the modulation of the components of a complex wave by each other, producing frequencies equal to the sums and differences of integral multiples of the component frequencies of the complex wave.

INTERSYSTEM EMC - EMC between the external electromagnetic environment (EME) and an aircraft with its installed systems. Generally, only system BIT must operate properly on the carrier deck while all system functions must operate properly in the operational EME.

INTRASYSTEM EMC - EMC between systems installed on an aircraft, exclusive of an external environment.

INVERSE CON SCAN - One method of confusing a radar operator or fire control radar system is to provide erroneous target bearings. This is accomplished by first sensing the radar antenna scan rate and then modulating repeater amplifier gain so the weak portion of the radar signal is amplified by the jammer, while the strong portion is not, so the weapons systems will fire at some bearing other than the true target bearing. The angle deception technique is used to break lock on CONSCAN radars.

INVERSE GAIN - Amplification, inverse modulation, and re-radiation of a radar's pulse train at the rotation rate of the radar scan. Deceives a conical scanning radar in angle.

ISOTROPIC ANTENNA - A hypothetical antenna which radiates or receives energy equally in all directions.

I/S RATIO (INTERFERENCE-TO-SIGNAL RATIO) (ISR) - The ratio of electromagnetic interference level to desired signal level that exists at a specified point in a receiving system. The ratio, normally expressed in dB, is employed as a tool in prediction of electronic receiving system performance degradation for a wide range of interference receiver input levels. Performance evaluations compare actual I/S ratios to minimum acceptable criteria.

JAFF - Expression for the combination of electronic and chaff jamming.

JAMMING - The deliberate radiation, reradiation, or reflection of electromagnetic energy with the object of impairing the use of electronic devices, equipment, or systems by an enemy.

JATO - JAmmer Technique Optimization group -- Organization coordinates EA technique development and evaluation efforts in support of naval airborne EA (ALQ-99, USQ-113, ALQ-227, ALQ-231, ALE-43). The group is run out of PMA-234 and comprised of elements at NAWCWD-Point Mugu, Johns Hopkins University/ Applied Physics Lab, Naval Research Lab, and NSWC-Crane. Efforts include M&S, Lab test, ground test, flight test, direct fleet support, and requirements and test support to development programs.

JINK - An aircraft maneuver which sharply changes the instantaneous flight path but maintains the overall route of flight. More violent than a weave.

JITTERED PRF - An antijam feature of certain radar systems which varies the PRF consecutively, and randomly, from pulse to pulse to prevent enemy ECM equipment from locking on, and synchronizing with, the transmitted PRF. PRF is synonymous with pulse repetition rate (PRR).

JTAT - JATO Techniques Analysis and Tactics -- Analysis documents produced by JATO to advise EA systems operators on the best ways to employ their systems by region, mission and equipment configuration. Currently covering ALQ-99 and USQ-113 on EA-6B; ALQ-99 and ALQ-227 on EA-18G, and ALQ-231 on AV-8B.

KILO - A prefix meaning 10^3 (times one thousand). For example, kilohertz.

KLYSTRON AMPLIFIER - An electron beam device which achieves amplification by the conversion of periodic velocity variations into conduction-current modulation in a field-free drift region. Velocity variations are launched by the interaction of an RF signal in an input resonant cavity and are coupled out through an RF output cavity. Several variations including reflex and multi cavity klystrons are used.

KLYSTRON, MULTICAVITY - An electron tube which employs velocity modulation to generate or amplify electromagnetic energy in the microwave region. Since velocity modulation employs transit time of the electron to aid in the bunching of electrons, transient time is not a deterrent to high frequency operations as is the case in conventional electron tubes. See also Velocity Modulation.

KLYSTRON, REFLEX - A klystron which employs a reflector (repeller) electrode in place of a second resonant cavity to redirect the velocity-modulated electrons through the resonant cavity. The repeller causes one resonant circuit to serve as both input and output, which simplifies the tuning operation. This type of klystron is well adapted for use as an oscillator because the frequency is easily controlled by varying the position of the repeller. See also Velocity Modulation.

LEAKAGE - Undesired radiation or conduction of RF energy through the shielding of an enclosed area or of an electronic device.

LENS, RADAR (MICROWAVE) - The purpose of any such lens is to refract (focus) the diverging beam from an RF feed into a parallel beam (transmitting) or vice versa (receiving). The polarization is feed dependent.

LIGHT AMPLIFICATION BY STIMULATED EMISSION OF RADIATION (LASER) - A process of generating coherent light. The process utilizes a natural molecular (and atomic) phenomenon whereby molecules absorb incident electromagnetic energy at specific frequencies, store this energy for short but usable periods, and then release the stored energy in the form of light at particular frequencies in an extremely narrow frequency-band.

LIMITING - A term to describe that an amplifier has reached its point of saturation or maximum output voltage swing. Deliberate limiting of the signal is used in FM demodulation so that AM will not also be demodulated.

LITTORAL - Near a shore.

LOBE, ANTENNA - Various parts of the antenna's radiation pattern are referred to as lobes, which may be subclassified into major and minor lobes. The major lobe is the lobe of greatest gain and is also referred to as the main lobe or main beam. The minor lobes are further subclassified into side and back lobes as indicated in the figure to the right. The numbering of the side lobes are from the main lobe to the back lobe.



LOCAL OSCILLATOR FREQUENCY - An internally generated frequency in a superheterodyne receiver. This frequency differs from the receiver operating frequency by an amount equal to the IF of the receiver. The local oscillator frequency may be designed to be either above or below the incoming signal frequency.

LOG VIDEO - This receiver process, generally implemented in the IF, compresses the dynamic range of the signal so both weak and strong signals are displayed without changing the gain setting. Output voltage can be calibrated in volts/dB of input power.

LONG PULSE MODE - Many pulsed radars are capable of transmitting either long or short pulses of RF energy. When the long pulses of RF energy are selected manually (or sometimes automatically), the radar is said to be operating in the long pulse mode. In general, "long pulse mode" is used to obtain high average power for long-range search or tracking, and “short pulse mode” gives low average power for short-range, high-definition, tracking or search.

LOOSE DEUCE - General term for two aircraft working in mutual support of each other.

LORO (LOBE-ON-RECEIVE-ONLY) - A mode of operation generally consisting of transmitting on one non-scanning antenna system and receiving the reflected energy on another scanning system (The receiver could be TWS, Conical, or monopulse).

MACH NUMBER - The ratio of the velocity of a body to the speed of sound in the medium that is being considered. In the atmosphere, the speed of sound varies with temperature and atmospheric pressure, hence, so does mach number.

MAGNETIC ANOMALY DETECTOR - A means of detecting changes in the earth’s magnetic field caused by the presence of metal in ships and submarines.

MAGNETRON - A magnetron is a thermionic vacuum tube which is constructed with a permanent magnet forming a part of the tube and which generates microwave power. These devices are commonly used as the power output stage of radar transmitters operating in the frequency range above 1000 MHz and are used less commonly down to about 400 MHz. A magnetron has two concentric cylindrical electrodes. On a conventional magnetron, the inner one is the cathode and the outer one is the anode. The opposite is true for a coaxial magnetron.

MAGNETRON OSCILLATOR - A high-vacuum tube in which the interaction of an electronic space charge and a resonant system converts direct current power into ac power, usually at microwave frequencies. The magnetron has good efficiency, is capable of high power outputs, and is stable.

MATCHED FILTER - This describes the bandwidth of an IF amplifier that maximizes the signal-to-noise ratio in the receiver output. This bandwidth is a function of the pulsewidth of the signal.

MDS (MINIMUM DETECTABLE/DISCERNIBLE SIGNAL) - The receiver input power level that is just sufficient to produce a detectable/discernible signal in the receiver output. The detectable term is interchangeable with S_{min} and the discernable term is interchangeable with MVS. See Section 5-2.

MEACONING -- A system receiving radio signals and rebroadcasting them (or just transmitting) on the same frequency to confuse navigation. The meaconing station attempts to cause aircraft to receive inaccurate range or bearing information.

MEATBALL - Visual light “ball” seen in Fresnel lens optical landing system (FLOLS) by pilot during carrier or Navy field landing. Used as a reference to determine if flight path is high or low.

MEGA - A prefix meaning 10^6 (times one million). For example megahertz (MHz)

MICROVOLT PER METER - A commonly used unit of field strength at a given point. The field strength is measured by locating a standard receiving antenna at that point, and the “microvolts per meter” value is then the ratio of the antenna voltage in microvolts to the effective antenna length in meters. Usually used below 100 MHz. Above 100 MHz, power density terminology is normally used.

MICROWAVE AMPLIFICATION BY STIMULATED EMISSION OF RADIATION (MASER) - A low-noise radio-frequency amplifier. The emission of energy stored in a molecular or atomic system by a microwave power supply is stimulated by the input signal.

MISS DISTANCE - Used variously in different contexts. The distance from the missile to the geometric center of the aircraft, or the closest point of approach (CPA) of the missile to any portion of the aircraft such as the aircraft nose or telemetry pod, etc.

MISSILE SYSTEMS FUNCTIONS - Examples of missile system functions are: "acquisition" (ability to lock-on a desired target); "tracking" of a target; "guidance" of a missile toward a target; "illumination" of a target so that a homing missile can home on the reflected RF illumination; and "command" signal transmission to a missile to cause it to arm, to detonate, to commence homing, or to destroy itself.

MIXERS - See Balanced and Schottky Diode Mixers.

MODULATION - The process whereby some characteristic of one wave is varied in accordance with some characteristic of another wave. The basic types of modulation are angle modulation (including the special cases of phase and frequency modulation) and amplitude modulation. In missile radars, it is common practice to amplitude modulate the transmitted RF carrier wave of tracking and guidance transmitters by using a pulsed wave for modulating, and to frequency module the transmitted RF carrier wave of illuminator transmitters by using a sine wave.


AMPLITUDE MODULATED RF CARRIER
AMPLITUDE MODULATING PULSE WAVE
MODULATING SINE WAVE
AMPLITUDE MODULATED RF CARRIER

MODULATION, AMPLITUDE - This type of modulation changes the amplitude of a carrier wave in responses to the amplitude of a modulating wave. This modulation is used in radar and EW only as a switch to turn on or turn off the carrier wave; i.e., pulse is a special form of amplitude modulation.

MODULATION, FREQUENCY - The frequency of the modulated carrier wave is varied in proportion to the amplitude of the modulating wave and therefore, the phase of the carrier varies with the integral of the modulating wave. See also Modulation.

MODULATION, PHASE - The phase of the modulated carrier is varied in proportion to the amplitude of the modulating wave. See also Modulation.

MONOPULSE - (See figure to right) A type of tracking radar that permits the extracting of tracking error information from each received pulse and offers a reduction in tracking errors as compared to a conical-scan system of similar power and size. Multiple (commonly four) receiving antennas or feeds are placed symmetrically about the center axis and operate simultaneously to receive each RF pulse reflected from the target. A comparison of the output signal amplitude or phase among the four antennas indicates the location of the target with respect to the radar beam center line. The output


TGT ABOVE RADAR BEAM CENTER LINE
SIGNAL AMPLITUDE
A B C D
B
A
D
C
HORN ARRANGEMENT
TGT RIGHT OF RADAR BEAM CENTER LINE
SIGNAL AMPLITUDE
A B C D

of the comparison circuit controls a servo system that reduces the tracking error to zero and thereby causes the antenna to track the target.

MOS (MINIMUM OPERATIONAL SENSITIVITY) - The minimum signal which can be detected and automatically digitally processed by a radar without human discrimination.

MTI (MOVING TARGET INDICATOR) - This radar signal process shows only targets that are in motion. Signals from stationary targets are subtracted out of the return signal by a memory circuit.

MULTIPATH - The process by which a transmitted signal arrives at the receiver by at least two different paths. These paths are usually the main direct path, and at least one reflected path. The signals combine either constructively or destructively depending upon phase, and the resultant signal may be either stronger or weaker than the value computed for free space.

MULTIPLEX - Simultaneous transmission of two or more signals on a common carrier wave. The three types of multiplex are called time division, frequency division, and phase division.

MULTIBAND RADAR - A type of radar which uses simultaneous operation on more than one frequency band through a common antenna. This technique allows for many sophisticated forms of video processing and requires any jammer to jam all channels at the same time in order to be effective.

MVS (MINIMUM VISIBLE SIGNAL) - The minimum input pulse signal power level which permits visibility of the output pulse, such as on a radar A-scope display. This level is determined by initially setting the input level above the visible detection threshold, and then slowly decreasing the amplitude.

NOISE FIGURE, RECEIVER - A figure of merit (NF or F) of a system given by the ratio of the signal-to-noise ratio at the input, S_i / N_i, divided by the signal-to-noise ratio at the output, S_o/N_o. It essentially expresses the ratio of output noise power of a given receiver to that of a theoretically perfect receiver which adds no noise.

$$\textit{Noise Figure} = \frac{S_i / N_i}{S_o / N_o} = \frac{N_o}{G\,N_i}$$

Where $S_o = GS_i$ and G is the gain of the system.


SYSTEM OUTPUT
Input Power times Power Gain
GNᵢ
Perfect System
Noise Power Added By Receiver
Input Power times Power Gain
Nₒ
Actual System

Noise figure is usually expressed in dB and given for an impedance matched condition. Impedance mismatch will increase the noise figure by the amount of mismatch loss. NF is usually given at room temperature; 17°C or 290°K. See Section 5-2.

NOISE JAMMING - A continuous random signal radiated with the objective of concealing the aircraft echo from the enemy radar. In order for it to be effective, it must have an average amplitude at least as great as the average amplitude of the radar echo. There are three major categories of noise jamming which are grouped by how jamming power is concentrated: Spot, barrage, and swept jamming. (See individual definitions)

NONCOHERENT - Two signals that have no set phase relationship.

NOTCH - The portion of the radar velocity display where a target disappears due to being notched out by the zero Doppler filter. If not filtered (notched), ground clutter would also appear on the display. A notch filter is a narrow band-reject filter. A "notch maneuver" is used to place a tracking radar on the beam of the aircraft so it will be excluded.

NULL, ANTENNA PATTERN - The directions of minimum transmission (or reception) of a directional antenna. See also Lobe, Antenna.

NULL FILL - The nulls in an antenna pattern may be reduced (filled) by using a second ancillary (spoiler) antenna whose pattern is such that it fills in the nulls of the main antenna pattern.


NULL
NULL PARTIALLY FILLED
PATTERN OF MAIN ANTENNA (PRE–NULL FILL)
PATTERN OF ANCILLARY ANTENNA
COMPOSITE PATTERN OF MAIN PLUS ANCILLARY ANTENNA (NULL FILL)

NUTATION - As applied to current missile system radars, this term refers to the mechanical motion of an antenna feed to produce a conical scan (fixed polarization) by the main beam of a tracking antenna, thus providing a means of developing tracking error signals. See also Antenna, Nutating. By analogy, "Nutation" also is used to denote the electrical switching of the quadrants of a seeker antenna. See also Interferometer. The effect is similar to that of a conical scan.

NUTATOR - A motor-driven rotating antenna feed used to produce a conical scan for a tracking radar. See also Antenna, Nutating. Also, the electrical circuits necessary to effect nonmechanical conical scans. See also Nutation.

OPERATIONAL CONSTRAINTS - Limitations on operating procedures in order to prevent interference between missile systems on a ship or between missile systems in a formation of ships under operational conditions. These limitations consist of such things as limited frequency bands or channels in which the radars may be tuned, limited sectors of space into which radar beams may be pointed, limits on minimum spacing between ships, limits on what codes may be used by radars and missiles on each ship, and limits on minimum interval between firing of certain missiles.

OSCILLATORS - Devices which generate a frequency. See also Backward Wave, Dielectrically Stabilized Oscillator, Hyperabrupt Varactor Oscillator, Magnetron Oscillator, Varactor Tuned Oscillator, and YIG tuned oscillator.

OSCILLATOR, LOCAL - See Local Oscillator Frequency.

PALMER SCAN - Conical scan superimposed on another type of scan pattern - usually a spiral pattern.

PARAMETER - A quantity which may have various values, each fixed within the limits of a stated case or discussion. In the present case, some examples of parameters; would be: radar frequency, limited by the tuning range of the radar; missile range, limited by the maximum operating range of the missile; or a missile code, limited by the number of codes available and by the codes that the ship radars are set up to operate on.

PASSIVE ANGLE TRACKING - Tracking of a target using radiation from the target (such as jamming), with no radiation from the radar itself. Only angular tracking is possible under these conditions since no measurement of time of travel of radiation to the target is possible, as is required to obtain target range.

PC (PULSE COMPRESSION) - The process used in search and tracking pulse radars whereby the transmitted pulse is long, so as to obtain high average transmitter output power, and the reflected pulse is processed in the radar receiver to compress it to a fraction of the duration of the transmitted pulse to obtain high definition and signal strength enhancement. Pulse compression may be accomplished by sweeping the transmitted frequency (carrier) during the pulse. The returned signal is then passed through a frequency-dependent delay line. The leading edge of the pulse is therefore delayed so that the trailing edge catches up to the leading edge to produce effectively a shorter received pulse than that transmitted. Pulse compression radars are also referred to as CHIRP radars. Other more sophisticated pulse compression techniques are also possible and are becoming more popular.

PENCIL BEAM - A narrow circular radar beam from a highly directional antenna (such as a parabolic reflector).

PHASED ARRAY RADAR - Radar using many antenna elements which are combined in a controlled phase relationship. The direction of the beam can be changed as rapidly as the phase relationships (usually less than 20 microseconds). Thus, the antenna typically remains stationary while the beam is electronically scanned. The use of many antenna elements allows for very rapid and high directivity of the beam(s) with a large peak and/or average power. There is also a potential for greater reliability over a conventional radar since the array will fail gracefully, one element at a time.

PIN DIODE - A diode with a large intrinsic (I) region sandwiched between the P- and N- doped semiconducting regions. The most important property of the PIN diode is the fact that it appears as an almost pure resistance at RF. The value of this resistance can be varied over a range of approximately one-10,000 ohms by direct or low frequency current control. When the control current is varied continuously, the PIN diode is useful for attenuating, leveling and amplitude modulation of an RF signal. When the control current is switched on and off or in discrete steps, the device is useful in switching, pulse modulating, and phase shifting an RF signal.

POINT CONTACT DIODE - This was one of the earliest semiconductor device to be used at microwave frequencies. Consisting of a spring-loaded metal contact on a semiconducting surface, this diode can be considered an early version of the Schottky barrier diode. Generally used as a detector or mixer, the device is somewhat fragile and limited to low powers.

POLARIZATION - The direction of the electric field (E-field) vector of an electromagnetic (EM) wave. See Section 3-2. The most general case is elliptical polarization with all others being special cases. The E-field of an EM wave radiating from a vertically mounted dipole antenna will be vertical and the wave is said to be vertically polarized. In like manner, a horizontally mounted dipole will produce a horizontal electric field and is horizontally polarized. Equal vertical and horizontal E-field components produce circular polarization.

PORT - The left side of a ship or aircraft when facing the bow (forward)

POWER (AVERAGE) FOR PULSED RADARS - Average power for a pulse radar is the average power transmitted between the start of one pulse and the start of the next pulse (because the time between pulses is many times greater than the pulse duration time, the average power will be a small fraction of peak power).



For this example: Peak Power = 1 MW, Pulse Time (t) = 0.5 microsecond, and Interval Between Pulses (T) = 1000 microseconds (1000 pps).

Peak Power = Pwr during pulse time (t) = 1 MW = 10^6 Watts = 90 dBm.

Avg Power = Average Power During Time (T) = 10^6 x t/T
= 10^6 x 0.5/1000 = 0.5 x 10^3 = 0.5 kilowatt = 57 dBm or 27 dBW

POWER OUTPUT - Power output of a transmitter or transmitting antenna is commonly expressed in dBW or dBm. One megawatt would be expressed as 60 dBW or 90 dBm:

10 log (1 megawatt / 1 watt) = 10 log ($10^6/10^0$) = 10 x 6 = 60 dBW

10 log (1 megawatt / 1 milliwatt) = 10 log ($10^6/10^{-3}$) = 10 x 9 = 90 dBm

POWER (PEAK) FOR PULSED RADARS - Peak power for a pulsed radar is the power radiated during the actual pulse transmission (with zero power transmitted between pulses).

POWER FOR CW RADARS - Since the power output of CW transmitters (such as illuminator transmitters) usually have a duty cycle of one (100%), the peak and average power are the same.

POWER DENSITY - The density of power in space expressed in Watts/meter^2, dBW/m^2, etc. Generally used in measurements above 100 MHz. At lower frequencies, field intensity measurements are taken. See Section 4-1.

PPI-SCOPE - A radar display yielding range and azimuth (bearing) information via an intensity modulated display and a circular sweep of a radial line. The radar is located at the center of the display.

PRESELECTOR - A device placed ahead of the mixer in a receiver, which has bandpass characteristics such that the desired (tuned) RF signal, the target return, is allowed to pass, and other undesired signals (including the image frequency) are attenuated.



PROPAGATION - In electrical practice, the travel of waves through or along a medium. The path traveled by the wave in getting from one point to another is known as the propagation path (such as the path through the atmosphere in getting from a transmitting antenna to a receiving antenna, or the path through the waveguides and other microwave devices in getting from an antenna to a receiver).

PULSE COMPRESSION - See PC.

PULSED DOPPLER (PD) - A type of radar that combines the features of pulsed radars and CW Doppler radars. It transmits pulses (instead of CW) which permits accurate range measurement. This is an inherent advantage of pulsed radars. Also, it detects the Doppler frequency shift produced by target range rate which enables it to discriminate between targets of only slightly different range rate and also enables it to greatly reduce clutter from stationary targets. See also Doppler Effect.

PULSE LENGTH - Same meaning as Pulsewidth.

PULSE MODULATION - A special case of amplitude modulation wherein the carrier wave is varied at a pulsed rate. Pulse Modulation - The modulation of a carrier by a series of pulses generally for the purpose of transmitting data. The result is a short, powerful burst of electromagnetic radiation which can be used for measuring the distance from a radar set to a target.

PULSE REPETITION FREQUENCY (PRF) - The rate of occurrence of a series of pulses, such as 100 pulses per second. It is equal to the reciprocal of the pulse spacing (T) or PRT. (PRF = 1/T = 1/PRI). Sometimes the term pulse repetition rate (PRR) is used.

PULSE REPETITION FREQUENCY (PRF) STAGGER - The technique of switching PRF (or PRI) to different values on a pulse-to-pulse basis such that the various intervals follow a regular pattern. This is useful in compensating for blind speeds in pulsed MTI radars. Interpulse intervals which differ but follow a regular pattern.

PULSE REPETITION INTERVAL (PRI) or TIME (PRT) - Time between the beginning of one pulse and the beginning of the next.

PULSE SPACING - The interval of time between the leading edge of one pulse and the leading edge of the next pulse in a train of regularly recurring pulses. See also Pulse Repetition Frequency. Also called "the interpulse period."



PULSEWIDTH - The interval of time between the leading edge of a pulse and the trailing edge of a pulse (measured in microseconds for the short pulses used in radar). Usually measured at the 3 dB midpoint (50-percent power or 70% voltage level) of the pulse, but may be specified to be measured at any level. See Section 6-10 for measurement techniques.

QUANTIZE - The process of restricting a variable to a number of discrete values. For example, to limit varying antenna gains to three levels.

RADAR - Radio detection and ranging.

RADAR CROSS SECTION - A measure of the radar reflection characteristics of a target. It is equal to the power reflected back to the radar divided by power density of the wave striking the target. For most targets, the radar cross section is the area of the cross section of the sphere that would reflect the same energy back to the radar if the sphere were substituted. RCS of sphere is independent of frequency if operating in the far field region. See Section 4-11.

RADAR RANGE EQUATION - The radar range equation is a basic relationship which permits the calculation of received echo signal strength, if certain parameters of the radar transmitter, antenna, propagation path, and target are known.

Given: $P_r = \dfrac{P_t G_t G_r \lambda^2 \sigma}{(4\pi)^3 R^4}$ *(freespace)* as the basic two-way radar equation (see Sections 4-4 thru 4-6)

where:
P_r = Peak power at receiver input
λ = Wavelength of signal (length) = c/f

P_t = Transmitted signal level (power)
R = Range of target to radar (distance)
G_t = Gain of transmitting antenna (dimensionless ratio)
σ = Radar cross section of target
G_r = Gain of receiving antenna (dimensionless ratio)

In practical use, the radar range equation is often written in logarithmic form, all terms expressed in decibels, so that the results can be found by simple processes of addition and subtraction. Using the above equation and $\lambda = c/f$.

$$10 \log P_r = 10 \log P_t + 10 \log G_t + 10 \log G_r + 10 \log \sigma - 40 \log R - 20 \log f + 20 \log c - 30 \log 4\pi$$

where: f = Signal frequency (cycles {dimensionless}/time) c = Speed of light (length/time)

$$10 \log P_r = 10 \log P_t + 10 \log G_t + 10 \log G_r + G_\sigma - 2\alpha_1$$

where α_1 and G_σ are factors containing the constants and conversion factors to keep the equations in consistent units.

Refer to Sections 4-4 through 4-6.

RADAR TRIGGER KILL - see Trigger Kill, Radar.

RADIATION EFFICIENCY - $E = P_{radiated}/P_{in}$ (ideal=1)

RADIATION PATTERN - See Antenna Pattern.

RADIO FREQUENCY - See RF.

RADIO FREQUENCY INTERFERENCE - See RFI.

RAIL KEEPING - Ability of countermeasures to keep the missile on the launch rail, i.e., prevent launch.

RAINBOW - A technique which applies pulse-to-pulse frequency changing to identifying and discriminating against decoys and chaff.

RANGE CELL - In a radar, a range cell is the smallest range increment the radar is capable of detecting. If a radar has a range resolution of 50 yards and a total range of 30 nautical miles (60,000 yds), there are: 60000/50 = 1,200 range cells.

RANGE GATE - A gate voltage used to select radar echoes from a very short range interval.

RANGE GATE PULL OFF (RGPO) - Deception technique used against pulse tracking radars using range gates. Jammer initially repeats the skin echo with minimum time delay at a high power to capture the AGC circuitry. The delay is progressively increased, forcing the tracking gates to be pulled away (“walked off”) from the target echo. Frequency memory loops (FML’s), or transponders provide the variable delay.

RANGE RATE - The rate at which a radar target is changing its range with respect to the radar (in feet per second for example). Note that this rate is not the same as target velocity unless the target is moving straight toward or straight away from the radar.

RANGE SCOPE - See A-Scope or PPI.


F₁
F₂
Receiver Bandwidth
1.0
0.707
Voltage Gain
Gain of 0.707 corresponds to a 3 dB decrease and is also called the half power points
Center of Frequency

RECEIVER BANDWIDTH - The difference between the limiting frequencies within which receiver performance in respect to some characteristic falls within specified limits. (In most receivers this will be the difference between the two frequencies where the intermediate frequency (IF) amplifier gain falls off 3 dB from the gain at the center IF frequency.) See also Receiver Selectivity.


SELECTIVITY
Wide receiver bandwidth undesired signal will pass
Narrow receiver bandwidth increases signal rejection
Desired Signal
Undesired Signal

RECEIVER SELECTIVITY - The degree to which a receiver is capable of differentiating between the desired signal and signals or interference at other frequencies. (The narrower the receiver bandwidth, the greater the selectivity.)

REFLECTION - The turning back (or to the side) of a radio wave as a result of impinging on any conducting surface which is at least comparable in dimension to the wavelength of the radio wave.

RESOLUTION - In radar, the minimum separation in angle or in range between two targets which the radar is capable of distinguishing.

RF (RADIO FREQUENCY) - A term indicating high frequency electromagnetic energy.

RFI (RADIO FREQUENCY INTERFERENCE) - Any induced, radiated, or conducted electrical disturbance or transient that causes undesirable responses or malfunctioning in any electrical or electronic equipment, device, or system. Same as EMI. Not to be confused with the logistic term ready for issue (also RFI).

RING AROUND - A condition in which a repeater jammer's total gain, from receiver antenna to transmitter antenna, exceeds the antenna isolation resulting in the repeater amplifying its own internal noise. Akin to positive feedback in an amplifier that causes unwanted oscillations.

RING AROUND (RADAR-TO-MISSILE) - The condition where radio frequency interference signals from a transmitter of one missile radar enter the receiving circuits of a missile under the control of another missile radar.

RING AROUND (RADAR-TO-RADAR) - The condition where radio frequency interference signals from a transmitter of one radar enter the receiving circuits of another radar.

ROPE - An element of chaff consisting of a long roll of metallic foil or wire which is designed for broad, low-frequency response. See Chaff.

R-SCOPE - (RANGE SCOPE) See A-scope or PPI.

SAFETY OF FLIGHT (SOF) TEST - A flight test to verify that a new or modified subsystem will not cause a major problem with the aircraft, i.e., interference can occur, but will not be such that required navigational systems will fail or which might potentially cause the loss of an aircraft under all normally expected weather conditions.

SCAN - To transverse or sweep a sector or volume of airspace with a recurring pattern, by means of a controlled directional beam from a radar antenna. See also "Antenna, nutating."

SCHOTTKY BARRIER DIODE - The Schottky barrier diode is a simple metal-semiconductor boundary with no P-N junction. A depletion region between the metal contact and the doped semiconductor region offers little capacitance at microwave frequencies. This diode finds use as detectors, mixers, and switches.

SCHOTTKY DIODE MIXER - The mixer is a critical component in modern RF systems. Any nonlinear element can perform the mixing function, but parameters determining optimal mixing are noise figure, input admittance, and IF noise and impedance. The Schottky diode is particularly effective because of its low noise figure and nearly square law characteristics.

SCHOTTKY DIODE SWITCH - Standard P-N diodes are limited in switching ability at high frequencies because of capacitance provided by the minority carriers. The Schottky diode overcomes this problem by use of the metal-semiconductor junction with inherently low carrier lifetimes, typically less than 100 picoseconds.

SEARCH RADAR - A radar whose prime function is to scan (search) a specified volume of space and indicate the presence of any targets on some type of visual display, and, in some cases, to provide coordinates of the targets to a fire control system to assist in target acquisition and tracking.

SEEKER - The seeker consists of circuitry in a homing missile which detects, electronically examines, and tracks the target; provides data for controlling the flight path of the missile; and provides signals for destroying the missile or for detonating it at intercept. (The seeker function is similar to that of an interferometer.)

SELF-SCREENING JAMMING (SSJ) - Each aircraft carries its own jamming equipment for its own protection.

SENSITIVITY - The sensitivity of a receiver is taken as the minimum signal level required to produce an output signal having a specified signal-to-noise ratio. See also Minimum Visible Signal and Minimum Discernible Signal (MDS).

SENSITIVITY TIME CONTROL - See STC.

SENSOR - The receiver portion of a transmitter/receiver pair used to detect and process electromagnetic energy.

SHIELDING - The physical arrangement of shields for a particular component, equipment, or system, (A shield is a housing, screen, or other material, usually conducting, that substantially reduces the effect of electric or magnetic fields on one side of the shield upon devices or circuits on the other side.) Examples are tube shields, a shielded enclosure or cabinet for a radar receiver, and the screen around a screen room.

SHORT PULSE MODE - See Long Pulse Mode.



SIDEBAND - A signal either above or below the carrier frequency, produced by the modulation of the carrier wave by some other wave. See figure at right ⇒

SIDELOBE - See Lobe, Antenna.

SIGNAL STRENGTH - The magnitude of a signal at a particular location. Units are volts per meter or dBV/m.

SIGNATURE - The set of parameters which describe the characteristics of a radar target or an RF emitter and distinguish one emitter from another. Signature parameters include the radio frequency of the carrier, the modulation characteristics (typically the pulse modulation code), and the scan pattern.

SILICON CONTROLLED SWITCH - A P-N-P-N device able to operate at sub-microsecond switching speeds by the application of gate signals. Because it is a four layer device, this switch is also known as a tetrode thyristor.

SLANT POLARIZATION - Technique of rotating a linear antenna 45° so it can receive or jam both horizontal and vertical polarization although there is a 3 dB loss. See Section 3.2.

SOLID STATE STAMO - A stable master oscillator constructed using transistors and other solid state devices as opposed to vacuum tubes. See also STAMO.

SPECTRUM - The distribution of power versus frequency in an electromagnetic wave. See also Spectrum Signature Analysis and illustrations under Sideband.

SPECTRUM ANALYZER - An electronic device for automatically displaying the spectrum of the electromagnetic radiation from one or more devices. A cathode ray tube display is commonly used to display this power-versus frequency spectrum. For examples of two types of displays, see illustrations under Sideband.

SPECTRUM SIGNATURE ANALYSIS - The analysis of the electromagnetic radiation from an electronic device to determine the relative power in each sideband, harmonic, and spurious emission compared to the carrier frequency. This particular distribution (or spectrum) is peculiar to the device and can identify this type of device, thereby acting as an identifying "signature."

SPECTRUM WIDTH (TRANSMITTER) - The difference between the frequency limits of the band which contains all the spectrum frequency components of significant magnitude.

SPOILER ANTENNA - An antenna used to change (spoil) the antenna pattern of a second antenna so as to reduce the nulls in the pattern of the second antenna. See also Null Fill.

SPOKING (RADAR) - Periodic flashes of the rotating radial display. Sometimes caused by mutual interference.

"SPOOFING" - A type of deception by using an electronic device to transmit a "target" echo. The spoofing transmitter must operate at the same frequency and PRF as the radar to be deceived. The radar main pulse triggers the spoofing transmitter which, after a delay, transmits a false echo.

SPOT JAMMING - Narrow frequency band jamming concentrated against a specific radar at a particular frequency. The jamming bandwidth is comparable to the radar bandpass. Can deny range and angle information.

SPURIOUS EMISSION - Electromagnetic radiation transmitted on a frequency outside the bandwidth required for satisfactory transmission of the required waveform. Spurious emissions include harmonics, parasitic emissions, and intermodulation products, but exclude necessary modulation sidebands of the fundamental carrier frequency.



SQUINT ANGLE - The angular difference between the axis of the antenna mainlobe and the geometric axis of the antenna reflector, such as the constant angle maintained during conical scan as the mainlobe rotates around the geometric axis of the reflector.

STAGGERED PRF - Staggered PRF allows an increase in MTI blind speeds such that no zeros exist in the velocity response at lower velocities. In a two-period mode, the usual "blind speed" or occurrence of a zero in the velocity response is multiplied by a factor which is a function of the ratio of the two repetition periods.

STAMO (STABLE MASTER OSCILLATOR) - A very stable (drift free) oscillatory used to provide a precise frequency for transmission and for comparison with the reflected radar signal returned to the receiver, such as in a Doppler radar where a precise difference between transmitted and received signals must be measured to determine accurately the Doppler frequency.

STAND-FORWARD JAMMING - A method which places the jamming vehicle between the enemy sensors and attack aircraft.

STAND-IN JAMMING (SIJ) - Similar to stand-forward jamming but usually using an UAV with a lower powered jammer instead of a jammer aircraft.

STAND-OFF JAMMING (SOJ) - An ECM support aircraft orbits in the vicinity of the intended target. As the fighter-bomber pilot starts his strike penetration, the ECM aircraft directs jamming against all significant radars in the area. This technique provides broad frequency band ECM without affecting performance of the strike aircraft.

STARBOARD - The right side of a ship or airplane when facing the bow (forward).

STC (SENSITIVITY TIME CONTROL) - Gain control that reduces the radar receiver gain for nearby targets as compared to more distant targets. STC prevents receiver saturation from close-in targets.

STEP RECOVERY DIODE - A charge-controlled switch which ceases current conduction so rapidly that it can be used to produce an impulse. Cyclic operation of the diode can produce a train of impulses which when used with a resonant circuit can produce a single frequency output at any harmonic of the pulse frequency.

STERADIAN - Unit of solid angle. An entire sphere has 4π steradians.

STREAM CHAFF - Operational technique of dropping large quantities of chaff for a continuous period of time. This results in a “ribbon” or “stream” of returns many miles in lengths on radarscopes. The penetrating strike force can then use the resulting chaff corridor to mask their penetration.

SUBHARMONIC - A frequency which is an integral submultiple of another frequency. For example, a sine wave whose frequency is one-third of the frequency of another sine wave is called the third subharmonic. (3 MHz is the third subharmonic of 9 MHz).

SUPERHETERODYNE RECEIVER - A receiver that mixes the incoming signal with a locally generated signal (local oscillator) to produce a fixed, low intermediate frequency (IF) signal for amplification in the IF amplifiers.

SUPPRESSION - Elimination or reduction of any component of an emission, such as suppression of a harmonic of a transmitter frequency by band rejection filter.

SUPPRESSION OF ENEMY AIR DEFENSES (SEAD) - Activity which neutralizes, destroys, or temporarily degrades enemy air defense systems by using physical attack or electronic means (SEAD pronounced “seed” or “C add”).

SUSCEPTIBILITY - The degree to which an equipment or a system is sensitive to externally generated interference.

SWEPT JAMMING - Narrowband jamming which is swept through the desired frequency band in order to maximize power output. This technique is similar to sweeping spot noise to create barrage jamming, but at a higher power.

SWITCHES - See also Diode Switch, Silicon Controlled Switch, Schottky Diode Switch.

SYNCHRODYNE - A klystron mixer amplifier stage in a transmitter, where two signal frequencies are applied as inputs and a single amplified signal is taken out.

TARGET SIZE - A measure of the ability of a radar target to reflect energy to the radar receiving antenna. The parameter used to describe this ability is the “radar cross section” of the target. The size (or radar cross section) of a target, such as an aircraft, will vary considerably as the target maneuvers and presents different views to the radar. A side view will normally result in a much larger radar cross section than a head-on view. See also Radar Cross Section.

TERMINAL IMPEDANCE - The equivalent impedance as seen by the transmitter/receiver.

TERRAIN BOUNCE - Term for jamming that is directed at the earth’s surface where it is reflected toward the threat radar. Reflected jamming creates a virtual image of the jamming source on the earth as a target for HOJ missiles.

THERMISTOR - A resistor whose resistance varies with temperature in a defined manner. The word is formed from the two words “thermal” and “resistor,”

THRESHOLD ISR - The interference to signal ratio (ISR) at which the performance of a receiver starts undergoing degradation. It must be determined by tests.

TRACKING RADAR - A radar whose prime function is to track a radar target and determine the target coordinates (in range and angular position) so that a missile may be guided to the target, or a gun aimed at the target.

TRACKING RADAR RECEIVER - These are of two primary types: conical scan and monopulse. (1) The conical scan system directs the radar signal in a circle around the target. The radar paints this circle 15 to 40 times per second. As the target moves out of the center of this circle, the radar develops aim error voltages and re-aims the antenna. (2) The monopulse system directs four beams at the target simultaneously. The target is in the middle of the four beams. If the target is not in the center, the radar return develops an aim error voltage to re-aim the antenna.

TRACK WHILE SCAN (TWS) RADAR - Although it is not really a tracking radar in the true sense of the word, it does provide complete and accurate position information for missile guidance. In one implementation it would utilize two separate beams produced by two separate antennas on two different frequencies. The system utilizes electronic computer techniques whereby raw datum is used to track an assigned target, compute target velocity, and predict its future position, while maintaining normal sector scan. Most aircraft use only a single antenna.

TRADE-OFF TABLES - A set of tables showing the various combinations of two or more variables that are related in that making one variable better will make the other variable worse. The trade-off helps find the best solution considering all combinations. (For example, how a no-interference condition can be maintained if two emitter platforms are brought close together, if at the same time the frequency separation between their radar transmitters is increased.)

TRANSIENT - A phenomenon (such as a surge of voltage or current) caused in a system by a sudden change in conditions, and which may persist for a relatively short time after the change (sometimes called ringing).

TRANSPONDER - A transmitter-receiver capable of accepting the electronic challenge of an interrogator and automatically transmitting an appropriate reply. There are four modes of operation currently in use for military aircraft. Mode 1 is a nonsecure low cost method used by ships to track aircraft and other ships. Mode 2 is used by aircraft to make carrier controlled approaches to ships during inclement weather. Mode 3 is the standard system used by commercial aircraft to relay their position to ground controllers throughout the world. Mode 4 is IFF. See also IFF.

TRAVELING-WAVE TUBE AMPLIFIER - The TWT is a microwave amplifier capable of operation over very wide bandwidths. In operation, an electron beam interacts with a microwave signal which is traveling on a slow wave helical structure. The near synchronism of the beam and RF wave velocities results in amplification. Bandwidths of 3:1 are possible. Operation at high powers or at millimeter wavelengths is possible at reduced bandwidths.

TRIGGER KILL (RADAR) - A method employed to momentarily disable certain radar system circuits to reduce or eliminate RF emissions which may cause an EMI/EMC or RADHAZ situation such as on the deck of a ship.

TUNNEL DIODE - The tunnel diode is a heavily doped P-N junction diode that displays a negative resistance over a portion of its voltage-current characteristic curve. In the tunneling process, electrons from the p-side valence bands are able to cross the energy barrier into empty states in the N-side conduction band when a small reverse bias is applied. This diode is used as a microwave amplifier or oscillator.

UPLINK - The missile guidance signal which passes midcourse correction command guidance intelligence from the guidance radar site to the missile.

VARACTOR DIODE - A P-N junction employing an external bias to create a depletion layer containing very few charge carriers. The diode effectively acts as a variable capacitor.

VARACTOR TUNED OSCILLATOR - A varactor diode serves as a voltage-controlled capacitor in a tuned circuit to control the frequency of a negative resistance oscillator. The major feature of this oscillator is its extremely fast tuning speed. A limiting factor is the ability of the external voltage driver circuit to change the voltage across the varactor diode, which is primarily controlled by the driver impedance and the bypass capacitors in the tuning circuit.

VELOCITY GATE PULL-OFF (VGPO) - Method of capturing the velocity gate of a Doppler radar and moving it away from the skin echo. Similar to the RGPO, but used against CW or Doppler velocity tracking radar systems. The CW or pulse doppler frequency, which is amplified and retransmitted, is shifted in frequency (velocity) to provide an apparent rate change or Doppler shift.

VELOCITY MODULATION - Velocity modulation is modification of the velocity of an electron beam by alternately accelerating and decelerating the electrons at a frequency equal to the input frequency. Thus, the electrons are segregated in bunches, each bunch causing a cycle or current as it passes an output electrode. The velocity of the electrons is thus a function of the modulation voltage. See also Klystron, Multicavity and Klystron, Reflex.

VICTIM - A receiver (radar or missile) that suffers degradation due to ECM or EMI effects.

VIDEO - Receiver RF signals that have been converted (post detection) into a pulse envelope that can be seen when applied to some type of radar visual display; also used to describe the actual display itself (such as the video on an A-scope).

WARM - Acronym for Wartime Reserve Mode. Any mode of operation of a radar or ECM that is held in reserve, and never used, except in actual combat.

WATER LINE - A reference line used for vertical measurements. When used with an aircraft it is usually the ground with the landing gear extended normally. One of several aircraft location designations, also see butt line and fuselage station.

WAVEGUIDE - A transmission line consisting of a hollow conducting tube of arbitrary geometry (usually rectangular, but may be circular) within which electromagnetic waves may propagate.

WAVELENGTH (λ) - The distance traveled by a wave in one period (the period is the time required to complete one cycle). $\lambda = c/f$. In the atmosphere, electromagnetic waves travel at c, the speed of light (300 million meters per second or 30 cm/nsec). At 5 GHz, one wavelength = 6 cm. At 10 GHz, one wavelength = 3 cm.

WAVEMETER - An instrument for measuring the frequency of a radio wave. The wavemeter is a mechanically tunable resonant circuit. It must be part of a reflection of transmission measurement system to measure the maximum response of a signal. Below 20 GHz, the wavemeter has been replaced by the frequency counter with much greater accuracy and ease of use.

WEAVE - An aircraft maneuver that smoothly changes the instantaneous flight path but maintains the overall route of flight. Not as violent as a jink.

WET RUN - A test run with ship / aircraft armament and/or EW switches on.

WILD WEASEL - USAF aircraft (F-4Gs during Desert Storm) used for suppression of enemy air defense (SEAD) mission.

WINDOW - WWII name for chaff

YIG TUNED OSCILLATOR - A YIG (yttrium iron garnet) sphere, when installed in the proper magnetic environment with suitable coupling will behave like a tunable microwave cavity with Q on the order of 1,000 to 8,000. Since spectral purity is related to Q, the device has excellent AM and FM noise characteristics.

ZENER DIODE - A diode that exhibits in the avalanche-breakdown region a large change in reverse current over a very narrow range in reverse voltage. This characteristic permits a highly stable reference voltage to be maintained across the diode despite a wide range of current.

THE REALITY OF PSYCHOTRONIC WEAPONS TODAY!

by

Preston T. Bailey, PhD.

Poll: Most Americans Feel Threatened By the Government

A new survey from Pew Research Center finds more than half of Americans believe the government threatens their personal rights. The national survey marks the first time a majority of Americans have viewed the government as a threat since Pew began tracking public opinion on the subject in 1995.

Welcome to
IDAHO

ATTENTION CRIMINALS & TERRORISTS

Over 170,000 Idaho Residents Have A Permit to Legally Carry A Concealed Weapon, About 60% Of The rest of the Population Is Armed But Have Not Bothered to Purchase the License As It Is Not A Requirement To Carry A Firearm. Understand, A Substantial Portion Of The Population Is Armed And Prepared To Defend themselves And Others Against Acts of Criminal Violence.

YOU HAVE BEEN WARNED!

However, California, New York and Illinois have disarmed their citizens for your convenience.

The outgoing Homeland Security Secretary has a warning for her successor: A massive and “serious” cyber attack on the U.S. homeland is coming, and a natural disaster — the likes of which the nation has never seen — is also likely on its way.

ELECTROMAGETIC ENERGY WEAPONS


PROJECT: SOUL CATCHE
LOOK INSIDE
VOLUME TWO
Secrets of Cyber and Cybernetic Warfare Revealed
DECLASSIFIED
ROBERT DUNCAN
and The Mind Hacking Strategy Group

Project Soul Catcher: Secrets of Cyber and Cybernetic Warfare Revealed reveals the cybernetic mind control by the CIA and their use of psychotronic weapons and their pursuit to weaponize neurpsychology.

ELECTROMAGNETIC SATELLITE TECHNOLOGY

THE NEUROPHONE:US Patent # 3,393,279.
July 16th, 1968

It's a device that converts sound to electrical impulses sometimes called the “Voice of God” or makes the person think he is crazy. When the signals are sent to the brain, it makes a person think that God is speaking to him/her or even an “alien.” It targets the unique bioelectrical resonance frequency using his “vibrational pattern” in the brain called a “signature” and it acts like an audio receiver.

THE PSYCHO-ACOUSTIC PROJECTOR:

U.S. patent #3,566,347, (23/2/71)
A device/weapon which can actually deafen the target.

SILENT SUBLIMAL MESSAGES: US Patent # 5,159,703. October 27th, 1992

Non aural carriers in extreme audio frequency ranges are amplified or modulated with the desired material and propagated acoustically for direct inducement into the brain. This is an excellent method of influencing people without their knowledge and is used in advertising.

METHODS AND SYSTEMS OF ALTERING CONSICOUSNESS:

US Patent # 5,123,844. June 23rd, 1992
US Patent # 5,289,438. February 22nd, 1994
These systems stimulate the brain with different frequencies and wave forms to alter the subject's state of consciousness.

Electro Magnetic Field (EMF) monitoring/interference is one of the most insidious and secretive of all methods used by the agencies.

MICROWAVE WEAPONS: "A hearing system" U.S. patent #4,877,027, 31/10/89 & "A hearing device" U.S. patent #4,858,612, 22/8/89.

The first known experiment with microwaved voices was conducted by Sharp and Grove in the early 70's. However, the Defence Intelligence Agency and ARPA (The Advanced Research Projects Agency) are principally to blame for the abuse of such technologies since. eg Project Pandora etc. The CIA's Langley Research Center as well as numerous scientists working in Energy/Defence department labs across the U.S. are also responsible.

BRAIN WAVE MONITORS/ANALYSERS

When the brain wave pattern of an individual is detected from the use of one of numerous types of detectors such as a satellite, these brainwave signals are sent to a monitor with a computer. These brain wave patterns are interpreted through a brain wave vocabulary that records the thoughts into words. The NSA monitors the brainwaves of their targets by satellite and decode the evoked potentials (3.50Hz 5 milliwatts) that the brain emits. So, using lasers / satellites and high-powered computers, the agencies have now gained the ability to decipher human thoughts - and from a considerable distance almost instantaneously.

Psychotronic Weapons

Russian former Prime Minister Dmitry Medvedev with a psychotronic gun

Psychotronic Guns by Thor Jensen

This is still an in-development project, but the potential for mayhem is unimaginable. Russia is currently working on weapons that employ electromagnetic radiation to directly affect the central nervous system – the root of all sensory processing – in a variety of unpleasant ways. The weapon will most likely build on existing research that shows the ability of low-frequency microwaves to affect brain function, alter moods and transmit false sensory data. Although this may all seem like *X-Files* stuff, the scientific basis is there. It’s up to some unscrupulous weapons designer to put it into practice.

Long Range Acoustic Device



Sound waves have the potential to deal tremendous damage at loud enough amplitudes – think about a sonic boom, for instance. But you don’t need a jet engine to turn sound into a weapon. The Long Range Acoustic Device is a creation of the American technology Corporation that was originally designed to defend safe zones around boats. It produces an incredibly loud noise that can travel almost 1000 feet in a targeted beam, and if the frequency is amplified enough it can cause legitimate physical pain in its victims.

Dazer Laser

Of all the senses you use on the battlefield, vision is probably the most important. So disrupting that can turn the tide in war. One of the most effective sensory weapons on the market right now is the Dazer Laser, made by Laser Energetics. Using a green laser source that emits both a continuous and pulsed wave, the range on the unit can be adjusted to as far as 2400 meters. One shot of the laser targeted at the eye area can completely incapacitate the victim for several minutes, long enough for them to be subdued non-lethally.

Distributed Sound And Light Array Debilitator



The most effective sensory weapons are ones that can engage and disorient multiple methods of input as well. Colloquially known as the “puke ray,” the Distributed Sound And Light Array Debilitator generates sound and light in a specific sequence designed to overload the brain’s processors, generating feelings of unease and discomfort. Prolonged exposure can result in even more unpleasant effects, including nausea and vomiting. Some scientists are even working towards producing a portable version the size of a flashlight that can be used on an individual basis.

Pulsed Energy Projectiles

E. P. Industries, Inc./ Mission Research Corp.
04-18-2001

The sensory organ with the largest active area in the body is, of course, the sense of touch. The human body has millions of individual nerves that are used to transmit sensory data to the brain, and a new experimental weapon from the U.S. government aims to really get them going. Pulsed energy projectiles are a specially-modulated laser that generates a burst of expanding plasma when they hit a solid object. That plasma in turn emits an electromagnetic pulse that causes immediate, searing pain to nerve cells all over the target's body. They're not in use yet, but research has been very promising.

MEDUSA



One of the most interesting sensory weapons on the market uses audio to disorient and confuse targets, but it skips the ear entirely. MEDUSA, a product of the Sierra Nevada Corporation, doesn’t create sound in a conventional way. Instead, it uses pulses of microwave radiation to generate shockwaves inside the skull that are detected by the ears from within – so earplugs won’t help you at all. It can generate painful white noise and even recognizable speech that sounds like it’s coming from the inside of your brain. Scary stuff.

"The Mind Has No Firewall" Army article on psychotronic weapons (Parameters)

The human body, much like a computer, contains myriad data processors. They include, but are not limited to, the chemical-electrical activity of the brain, heart, and peripheral nervous system, the signals sent from the cortex region of the brain to other parts of our body, the tiny hair cells in the inner ear that process auditory signals, and the light-sensitive retina and cornea of the eye that process visual activity.

We are on the threshold of an era in which these data processors of the human body may be manipulated or debilitated. Examples of unplanned attacks on the body's data-processing capability are well-documented. Strobe lights have been known to cause epileptic seizures. Not long ago in Japan, children watching television cartoons were subjected to pulsating lights that caused seizures in some and made others very sick.

http://dprogram.net/2009/07/01/the-mind-has-no-firewall-army-article-on-psychotronic-weapons/

TYPES OF PSYCHOTRONIC WEAPONS

A psychotronic generator produces a powerful electromagnetic emanation capable of being sent through telephone lines, TV, radio networks, supply pipes, and incandescent lamps.

An autonomous generator is a device that operates in the 10-150 Hertz band. At the 10-20 Hertz band, it forms an infrasonic oscillation that is destructive to all living creatures.

A nervous system generator is designed to paralyze the central nervous systems of insects which could have the same applicability to humans.

Ultrasound emanation devices using ultrasound emanations are capable of carrying out bloodless internal operations without leaving a mark on the skin. They can also be used to kill people from a distance.

Noiseless cassettes is the ability to place infra-low frequency voice patterns over music, patterns that are detected by the subconscious. These messages are then stored in a person’s sub-conscious mind which they may later act upon.

MICHIGAN LAW AGAINST ELECTROMAGNETIC DEVICES

House Bill 4513 would amend the penal code (MCL 750.200h) to define “harmful electronic or electromagnetic device” as a device designed to emit or radiate an electronic or electromagnetic pulse or signal or microwave intended to cause harm to others or cause damage to, destroy, or disrupt any electronic or telecommunications system or device including a computer or computer network. The bill would also include a harmful electronic or electromagnetic device in the definition of “imitation harmful substance or device.”

The Nuremberg Code opposes all forms of human experiments

The state of Missouri has a law against involuntary chipping or implanting of a human

Many countries have laws against human experimentation and the use of electromagnetic devices to control a person either their mind or their bodies

SENATOR JOHN GLENN

Senator Glenn's publicly-expressed outrage that this government has been found to be engaging in brutal forms of involuntary human experimentation, and that any and all forms of this type of experimentation be exposed. He stated that there are experiments with non-ionizing, so-called "non-lethal," directed-energy weapons, surveillance and psychotronic systems. He opposes Microwave Harassment and Mind-Control Experimentation especially connected to Los

Alamos National Laboratory, the Department of Energy, the Department of Defense, CIA, and the National Reconnaissance Office. He stated the DOD has increased in the numbers of Ground Wave Emergency Network (GWEN) towers and satellites that qualify as directed-energy emitters, microwave towers, and antennae arrays. John Glenn is also a member of the Electronic Surveillance Project that is trying to stop these forms of harassment and human experimentation.

CITIZENS AGAINST HUMAN RIGHTS ABUSE

Scientists, many of which are Nobel Prize winners, in this Human Rights organization have documented for years the numerous abuses of electromagnetic weapons and electromagnetic radiation (EMR) mind control weapons. Most of the perpetrators of this abuse has been Russia and the United States. The International Red Cross has also verified these offenses.

http://mindjustice.org/emr13.htm

RUSSIAN DEFENSE MINISTER

In March 2012 the Russian defense minister Anatoli Serdjukov said:

“The development of weaponry based on new physics principles; direct-energy weapons, geophysical weapons, wave-energy weapons, genetic weapons, psychotronic weapons, etc., is part of the state arms procurement program for 2011-2020,”Voice of Russia

EUROPEAN PARLIAMENT

A directed energy weapon system is designed to match a radio frequency source to interfere with human brain activity at a synapse level.” Since 1999 those weapons have been upgraded and should be banned in the world.

UNITED NATIONS

The United Nations also agreed with this report and stated the “United States is the main country of the world to use directed energy weapons and electromagnetic weapons.

The former United States Secretary of Defense William Cohen stated in a press briefing, while commenting on new technological threats possibly held by terrorist organizations: *"Others are engaging in an eco-type of terrorism whereby they can alter the climate, set off earthquakes, (and) volcanoes remotely, using the use of electromagnetic waves."*

A TARGETED INDIVIDUAL

Targeted Individuals are people who are illegally and covertly stalked, tortured and harassed by the use of hi-tech, Modern-day Military type Technologies (DAARPA, NASA, CIA etc.). Targets/Victims are usually implanted with **RFID** *(Radio-Remote Frequency Identification Device)* type transmitter chips ***(PositiveID*** or VERi Chips) and sometimes miniature Nano-Biochips and Stimulators/Transmitters mostly for GPS tracking purposes. Targets can be remotely connected to via radio frequency signals sent to the chip/s thus the mind and body being in theory "wirelessly" connected.. controlled and manipulated.

There are targeted individuals, victims of Psychotronic (or Mind Control, Electronic, Electromagnetic, Directed Energy, Neurological, Non-lethal) Weapons, who are being targeted unjustly or used as human subjects in experiments without their informed consent. Victims of mind/body control detail the most extreme and totalitarian violations of human rights in human history. Criminals may implant people with microchips or nanomaterials and place them under continuous surveillance. They monitor the human brain, continuously alter consciousness and behavior, directly assault and torture mind and bodies of the human subjects.

These are some of the symptoms that targeted individuals may experience:

a). Microwave hearing, torture with loud noise.
b). Visual hallucinations, artificial dreams.
c). Reading thoughts, retrieving memories.
d). Manipulation of thoughts, will, emotions, desires and perceptions.
e). Manipulation of human behavior: forced speech, involuntary body movements, transmission of specific commands into the subconscious, compulsory execution of these commands (i.e. the Manchurian Candidate effect).

f). Debilitation of mental acuity, loss of memory.
g). Sleep deprivation or uncontrollable sleep
h). Cramps, spasms, excruciating artificial pain in any part of the body, manipulation of body systems, including heart attacks and other serious medical conditions.

TARGETED INDIVIDUAL SUPPORT GROUPS

http://www.freedomfchs.com/id19.html

http://www.stopcovertwar.com/support.html

https://www.facebook.com/victimsoforganizedstalking

http://www.targetedinamerica.com/hitlist.html

http://targetedindividualsua.weebly.com/

http://targetedindividuals.blogspot.com/2011/08/tis-support-group.html

Dennis M. Bushnell
Chief Scientist
NASA Langley Research Center

Future Strategic Issues/Future Warfare

05
MARINES
© Getty Images

CURRENTLY

- Order of 70% of Worlds Research conducted outside of U.S. (to first order, a % of GDP, U.S. produces order of 18% of worlds GDP)
- Order of 70% of U.S. Research now "Commercial" (as opposed to Government sponsored)

TYPES OF WARFARE

- **Hunter-Gatherer - "Nature Provided"**
- **Agriculture - Controlled Nature (Plants/Animals)**
- **Industrial - Mechanized Agriculture**
- **IT/BIO/Nano - Automating Industry/Agriculture**
- **Virtual - Robotization of IT/Bio/Nano/Industry/Agriculture**

Worldwide IT Revolution

- Comms/Computing/Sensors/Electronics
- U.S. Commercial IT R&D ~ $100B/yr.
- Factor of 1 Million further improvement [Silicon,Molecular,Quantum,Bio,Optical]
- Beyond Human AI?
- Automatics/Robotics “in the large”
- Immersive multi-sensory VR/”Holodecks”
- Ubiquitous multi physics/hyperspectral sensors [land/sea/air/space]
- Micro/Nano sats/GNC/sensors,etc.

Current Competitive Landscape

- U.S. produces only 18% of Worlds GDP
- ~70% of Research conducted offshore
- $300B/yr trade deficit
- 32 other nations devote a larger % of their GDP to Research
- 5th in No of R&D personnel/labor unit
- 3% savings rate vs. 30% in Asia
- Proliferation of IT,bio,nano,Space Technology etc.

Bio Revolution Applications

- **“Pharm Animals” [drugs, spare parts]**
- **Fast Growing plants on/near sea surface & sea water irrigated plants for biomass energy/closed CO2 cycle**
- **Polymer growing plants**
- **Spider genes in goats allow spider silk spinning from goat milk for “Biosteel”, 3.5X strength of aramid fibers for Armor**
- **Binary Bio-weaponry**

A Real Transgenic Spider Goat

Carbon Nanotubes

- C1,000,000, Buckminister Fullerine Carbon
- 100X strength, 1/6 weight of steel
- 8X better Armor
- Low energy Molecular/Petaflop Computing
- Ultra Capacitor/High Temperature SC
- Non-Cryo H2 storage



Some Sensor "Swarms"

- SMART DUST
  - Cubic mm or less
  - Combined sensors, comms and power supply
  - Floats in air currents for up to 2 years
- NANOTAGS
  - Placed on everything/everywhere
  - Identification and Status Info
- Co-opted INSECTS





Gathering Data on the Fly

Researchers at the University of California are developing tiny, electronic devices called "smart dust" designed to capture information about their environment while literally floating on air. Each dust "mote" packs sensors, computers and wireless communicators onto a tiny silicon chip light enough to remain airborne for hours at a time. As the motes drift, they can monitor their surroundings and beam data back to a base station.

Air Delivery

Researchers are exploring a number of methods for deploying "smart dust." One technique involves the use of tiny, unmanned aircraft that would spray motes over an area like a miniature crop duster and then relay the resulting information back to a base station.

Winged computers

Researchers are also exploring ways to prolong the time smart dust remains airborne. By adding "wings" like those on maple seeds, the researchers hope to extend that period two- or three-fold.

Short-range transmitter (hundreds of yards)
Reflects back a laser beam directed at the smart dust. Rapid tilting of one mirror causes the light to blink in a Morse code-like signal.

Long-range transmitter (several miles)
Onboard laser sends signals to base station by blinking on and off.

Sensor
Collects information such as light, sound, temperature, chemical composition and other information.

Early Prototype

Smart dust "macro-mote" made with readily available components.

Video image of San Francisco skyline taken with a camera at Berkeley. The white dot is the laser signal emitted by a smart dust device positioned at Coit Tower.

To test their concept, researchers planted golf ball-sized smart dust devices at Twin Peaks and on Coit Tower. Using a modified laser pointer, the device beamed weather information back to Berkeley.

Potential uses

- Military uses include tracking enemy troop movements from above and detecting chemical warfare agents in the air.
- Monitoring weather conditions around the globe and detecting fires and earthquakes are among the nonmilitary uses.
- Stationary motes could be used to monitor the quality of products from factory to consumer.

Source: University of California Department of Electrical Engineering and Computer Sciences.

JOHN BLANCHARD / *The Chronicle*

6 inch wingspan
Incoming laser beam
Mirrors
Outgoing laser beam
Laser
Lens
Mirror
Power capacitor
Solar cell
Thick film battery
1-2 millimeters
Smart dust
Actual size of smart dust
1 square millimeter
1 inch
Sensors: Temperature, light, pressure, humidity
Modified laser pointer
2 inches
3 inches
Panasonic
Berkeley Marina
3.2 miles
Cory Hall U.C. Berkeley campus
S.F. Bay
9.5 miles
Coit Tower
Oakland
Pacific Ocean
San Francisco
13.3 miles
Twin Peaks



IN GOD WE TRUST
LIBERTY
2001
D



“Volumetric” Weaponry

[Alternatives to HE]

- EMP
- Info/Net/Psy warfare
- Miniature brilliant sensor/mine combo’s
- Fuel/air & dust/air
- RF
- Chem/bio Antifunctionals/antifauna
- Isomers, Strained Bond Energy Release, etc.
- Carbon fibers/Acoustics etc.



EMP Area By Bursts At 30, 120, & 300 Miles

Click on the image for a larger view.

Burst Altitude 300 Miles
Burst Altitude 120 Miles
Burst Altitude 30 Miles
480 Miles
1000 Miles
1470 Miles

- **Wide area coverage**
  - -A million square miles
- **Intensity depends on:**
  - -Weapon design
  - -Height of burst
  - -Location of burst
- **Broad frequency range**
- **Threat to all electronics**

Source: Gary Smith, "Electromagnetic Pulse Threats", testimony to House National Security Committee on July 16, 1997

Copyright© Young Research & Publishing, Inc.

“Slingatron” for Global Precision Strike

- 10Kg projectiles, up to thousands/minute
- Global, or less, range
- $20M/device
- Mechanical “on-the-ground” propulsion via Gyrating Spiral Guide Tube (a multiple “hula hoop”
- “Poor Mans” Global Precision Strike/“Takedown Weapon”

SLINGATRON

A MECHANICAL HYPERVELOCITY MASS ACCELERATOR

Test Ring

Impact Physics and Space
Launch Research Facility

Global Reach Machine

Potential Future “Orders of Magnitude” Increases in Overall Weapon Effectiveness/Availability at Orders of Magnitude Reduced Cost(s)

- Bio/Chem/Molec./Nano Computing - (E6)
- Ubiquitous Optical Comms - (E4)
- Micro/Nano/Ubiquitous Sensors - (E4)
- BioWeaponry - (EN)
- Co-operative Swarms of Cheap/Small Weapons/Sensors - (E4)
- Volumetric Weaponry - (E4)
- Cyber/Artificial Life (Beyond AI) - (E?)

Chemtrails

Inside of a US Chemtrail Plane



Major U.S. Future Warfare Issues

- **“Non-explosive Warfare” (psywar, biowar IT/net war, “anti-operability war,” Beam weaponry including RF, Spoofing/Cammo**
- **Robotic Warfare “in the large”/better than human AI/“Cyber life”**

Worth1000.com

DARPA Laser Weapon



ROBOTIC SOLDIERS

Robotic soldiers are being created right now in the world to build a huge army against humans and God. The New World Order is not going to reveal their plans on the evening news!

SINGULARITY

The **technological singularity** is a theoretical moment in time when artificial intelligence will have progressed to the point of a greater-than-human intelligence that will "radically change human civilization” according to Amnon Eden. Ray Kurzweil says “revolutions in genetics, nanotechnology and robotics will usher in the beginning of the Singularity.” Robots and cybernetic organisms are developing at a very fast pace that is blurring the line between humans and robots.



Bionic Skin for a Cyborg You

Flexible electronics allow us to cover robots and humans with stretchy sensors

By Takao Someya
Posted 26 Aug 2013 | 17:30 GMT

One decade ago, my research group at the University of Tokyo created a flexible electronic mesh and wrapped it around the mechanical bones of a robotic hand. We had dreamed of making an electronic skin, embedded with temperature and pressure sensors, that could be worn by a robot. If a robotic health aide shook hands with a human patient, we thought, this sensor-clad e-skin would be able to measure some of the person's vital signs at the same time.

Today we're still working intensively on e-skin, but our focus is now on applying it directly to the human body. Such a bionic skin could be used to monitor medical conditions or to provide more sensitive and lifelike prosthetics

Photo: Someya-Sekitani Group

Gilded skin: Takao Someya's latest e-skin material is one-tenth the



Today we're still working intensively on e-skin but our focus is now on applying it directly to the human body. Such a bionic skin could be used to monitor medical conditions or to provide more sensitive and lifelike prosthetics.

Gilded skin: Takao Someya's latest e-skin material is one-tenth the thickness of plastic kitchen wrap, and it can conform to any body shape.

Thin-film transistors don't just allow electronics to be flexible—they can also help an e-skin mimic the sensitivity of real skin. Consider this: There are more than 2 million pain receptors in a person's skin, which is equivalent to the number of pixels found in a typical high-definition TV. Synthetic skin covers the circuits that looks like human skin.

http://spectrum.ieee.org/biomedical/bionics/bionic-skin-for-a-cyborg-you


GREETINGS from
CAMP
FEMA
Brought to you by KBR - a Division of Halliburton
Deesillustration.com

CAMP FEMA

Coming to your city soon!

motifake.com

FEMA CAMPS in the United States



From [redacted]
Subject **RE: Supply Questions**
To Me <support@mypatriotsupply.com>
7/29/2013 10:48 AM

Matt,

I am inquiring in regards to the following:

1. Breakdown the total possible servings available for immediately delivery. For example, "averaging 3 servings per meal, 3 times per day, per person = 9 servings per day per person" how many servings can you provide within 24 hours, 48 hours, 72 hours, etc.?
2. Number of currently available meals?
3. Can your current stock begin shipping in 24 hours?
4. Do you ship dedicated truckloads by pallet? If so, how many pallets per truck?
5. At full capacity (assuming all resources are available) how many canned/packaged servings per day can you provide in a 24 hour period?

Please let me know when you have the opportunity.

Thanks in advance,

DHS/Federal Emergency Management Agency
Patriots Plaza
395 E Street, [redacted]
Washington, DC 20472
(202) [redacted] - Office
(202) [redacted] - BlackBerry

FEMA

FM 3-39.40

There is over 600 FEMA camps

INTERNMENT AND RESETTLEMENT OPERATIONS

FEMA has divided the U.S. into 10 regions with Governors assigned over each region

February 2010


Region X
AK
Seattle
WA
OR
ID
Region VIII
MT
ND
SD
WY
UT
Denver
CO
Region VII
NE
IA
Kansas City
KS
MO
Region V
MN
WI
MI
Chicago
IL
IN
OH
Region I
ME
VT
NH
Boston
MA
RI
CT
Region II
NY
New York
NJ
PR
U.S. VIRGIN ISLANDS
PA
Philadelphia
MD
DE
Washington, D.C.
WV
VA
Region III
KY
TN
NC
SC
Atlanta
MS
AL
GA
FL
Region IV
NM
OK
AR
Denton
TX
LA
Region VI
San Francisco
NV
CA
AZ
Region IX
AMERICAN SAMOA,
GUAM,
U.S. TRUST TERRITORY OF THE PACIFIC ISLANDS
HI

10 FEDERAL REGIONS

ent: Military Internment Camps in U.S to be Used for Political Dissidents


Admin area
Interrogation rooms
Visitation rooms
Admin area
Interrogation rooms
Visitation rooms
CK
Medical
Mortuary
Water storage
Laundry
QRF/guard brief
Covered storage
Class I storage
dry
refr
Recreation area
Inprocessing
Temp holding
W
Open storage
Admin area
Visitation rooms
Interrogation rooms
Admin area
Recreation areas
100-person enclosure

FM 3-39.40

INTERNMENT AND RESETTLEMENT OPERATIONS

February 2010

Internment and Resettlement Operations

Contents

Page

PREFACE .... **viii**

INTRODUCTION .... **xi**

Chapter 1 **INTERNMENT AND RESETTLEMENT AND THE OPERATIONAL ENVIRONMENT** **1-1**

Conduct 1-1

Principles 1-3

Personnel Categories 1-5

Status Determination 1-7

Article 5 Tribunals 1-8

Appeals and Periodic Reviews of Civilian Internees 1-9

General Protection and Care of Detainees, U.S. Military Prisoners, and Dislocated Civilians 1-10

Agencies Concerned With Internment and Resettlement 1-12

Protecting Power 1-13

Planning Considerations for Internment and Resettlement Operations 1-14

Military Police Capabilities 1-16

Chapter 2 **INTERNMENT AND RESETTLEMENT IN SUPPORT OF THE SPECTRUM OF OPERATIONS** **2-1**

Support to Combat Operations 2-1

Support to Stability Operations 2-3

Support to Civil Support Operations 2-8

Army Command and Support Relationships 2-8

Considerations Within the Operational Area and the Area of Operations 2-9

Chapter 3 **COMMAND AND STAFF ROLES AND RESPONSIBILITIES** **3-1**

National and Theater Reporting Agencies 3-1

Roles and Responsibilities 3-2

Chapter 4 CAPTURE, INITIAL DETENTION, AND SCREENING 4-1
Detainee Flow 4-1
Detainee Processing 4-5
Custody and Accountability of Property, Evidence, and Intelligence Information 4-12
Detainee Movement 4-15
Methods of Transportation 4-16
Detainee Release 4-19

Chapter 5 DETAINEE OPERATIONS 5-1
Command and Control 5-1
Planning Considerations 5-2
Intelligence and Interrogation 5-3
Medical Support 5-6
Dental Support 5-8
Specific Detainee Support Requirements 5-9
Detainee Deaths 5-13
Legal Considerations 5-14

Chapter 6 DETAINEE FACILITIES 6-1
General Considerations 6-1
Detainee Collection Point 6-4
Detainee Holding Area 6-10
Fixed Detainee Internment Facilities 6-14
Theater Internment Facility 6-17
Strategic Internment Facility 6-37
Transfers or Releases 6-38

Chapter 7 CONFINEMENT OF U.S. MILITARY PRISONERS 7-1
U.S. Battlefield Confinement Operations Principles 7-1
Planning Process for U.S. Military Prisoners 7-1
Battlefield Facilities 7-2
Processing, Classification, and Identification Requirements 7-3
Clothing, Meals, and Dining Facilities 7-4
Medical Care and Sanitation 7-5
Discipline, Control, and Administration 7-6
Emergency Planning and Investigations 7-11
Rules of Interaction 7-12
Use of Force 7-12
Escape 7-12

If there are not real FEMA camps for detainment of American citizens, then why:

- Did Obama sign so many Executive Orders taking away the freedoms of American citizens?
- Did Obama say that anyone who is a threat to American security could be “detained indefinitely?”
- Does Homeland Security avoid answering a direct question about the hundreds of camps that exist?
- Are so many camps totally empty but staffed 24 hours a day?

- Why did they not house a single illegal immigrant of the 12 million that are here in any of these camps even though they say that is what they were built for?
- Why didn’t any of those effected by hurricanes go to a FEMA camp?
- Why does Homeland Security keep on building more FEMA camps?
- Why are a majority of these camps designed to hold 20,000 inmates?

- Why aren’t the people paid to station these camps informed about the purpose of the camps?
- Why are these camps hiring so many guards recently?
- Why aren’t the victims of fires, flooding, tornadoes, and hurricanes taken to any of these camps?
- Why did the sponsors of the bill years ago to build these camps even know what these camps were designed for?

LIST OF ALL OF THE CAMPS:

http://www.sianews.com/modules.php?name=News&file=article&sid=1062


Calgary
Vancouver
Washington-Okanogan County
Washington-Seattle/Tacoma
Washington Sand Point
Washington- Ft Lewis
Montana-Malmstrom AFB
NORTH DAKOTA-Minot
Ontario
Quebec
Newfoundland and Labrador
Idaho- Clearwater National Forest
North Dakota
Saint Pierre
Oregon
-Josephine County
Wyoming-East Yellowstone
WYOMING-Heart Mountain
Minnesota-Camp Ripley
MINNESOTA-Duluth
Maine-Houlton
California-Tule Lake
Idaho-Minidoka/Jerome
Michigan-Sawyer
Montreal
New Hampshire-North
VERMONT
Nova Scotia
SOUTH DAKOTA-Edgemont
Michigan-Camp Grayling
Nevada-Wells
NEBRASKA-NorthWest
New York-Ft Drum
Nevada-Winnemucca
Wyoming-Southwest
SOUTH DAKOTA-Yankton
Ashley National Forest
NEBRASKA-Scottsbluff
Wisconsin- Ft McCoy
Michigan-Bay City
Nevada-Stillwater
NEBRASKA-NorthEast
alifornia-Oakdale
Wyoming-Laramie
Illinois-Savanna
Michigan-Berrien County
Detroit
New York-Buffalo
New York-Albany
eterans Affairs Medical Center: Berryman William R MD
NEBRASKA-South Central
Illinois-Marseilles
Illinois-Sheridan
OHIO-Camp Perry
NEW YORK-Otisville
PENNSYLVANIA-Allenwood
Illinois-Galesburg
Ohio- Lima
Utah-Cedar City
PENNSYLVANIA-Camp Hill
Illinois-Menard
Illinois-Lincoln
Indiana-Ft. Benjamin Harrison
Nevada-Las Vegas AREA
Colorado-Ft. Carson
Maryland-Ft. Detrick
Colorado-Granada
Missouri-Richards-Gebaur AFB
Illinois-Greenfield
Indiana-Camp Atterbury
WEST VIRGINIA- Mill Creek
California-Ft. Irwin
ifornia-Twentynine Palms
Colorado-Trinidad
Illinois-Scott AFB
Missouri-Warsaw
Arizona-Sedona
Missouri-Ft. Leonard Wood
WEST VIRGINIA- Beckly
VIRGINIA -Petersburg
Illinois-Marion
Arkansas-Omaha
Arkansas-Berryville
Arizona-Wickenburg
Arizona-Phoenix
Texas- Amarillo
TENNESSEE -Ft. Campbell
OKLAHOMA- Tinker
Arizona-Florence
Arizona-Pinal County
TENNESSEE -Crossville
Arkansas-Ft. Chaffee
Arkansas-Blythville
NEW MEXICO-Fort Stanton
OKLAHOMA- Lawton
North Carolina-Andrews
North Carolina-Camp Lejeune / New R
OKLAHOMA-McAlester
SOUTH CAROLINA-Greenville
NEW MEXICO-Holloman
Texas- Lubbock
Arkansas-Pine Bluff Arsenal
Arkansas-Rohwer
NEW MEXICO-Ft. Bliss
Texas- Ft.Bliss
Texas -Carrolton
Arkansas-Jerome
Alabama-Talladega
Texas-Ft. Worth
Alabama-Aliceville
South Carolina-Charleston
Texas-Eden
Texas- Mexia
Georgia-Oglethorpe
Louisiana-Ft. Polk
Alabama-Montgomery
Gulf of California
Texas- Killeen
Georgia-Morgan
Louisiana-Oakdale
Louisiana-north of Interstate 12
Texas- Beaumont/Port Arthur
Florida
Florida-Avon Park
Florida-Camp Krome
Gulf of Mexico

Googles list of FEMA Camps

Complete 326 page manual

http://info.publicintelligence.net/USArmy-InternmentResettlement.pdf

Leaked Document: Military Internment Camps in U.S to be Used for Political Dissidents

http://www.youtube.com/watch?v=FfkZ1yri26s

Military ad as it appeared in Government Pub:

Correction Officer Internment / Resettlement Specialist

As an Internment/Resettlement Specialist for the Army National Guard, you will ensure the smooth running of military confinement/ correctional facility or detention/internment facility, similar to those duties conducted by civilian Corrections Officers. This will require you to know proper procedures and military law; and have the ability to think quickly in high-stress situations. Specific duties may include assisting with supervision and management operations; providing facility security; providing custody, control, supervision, and escort; and counseling individual prisoners in rehabilitative programs.

So, why is the National Guard hiring “Internment / Resettlement Specialists?”



http://intellihub.com/2013/06/13/find-the-fema-camp-nearest-you/

The White House quietly issued National Security Presidential Directive 51 (NSPD-51), to ensure "continuity of government" in the event of what the document vaguely calls a "catastrophic emergency." Should the president determine that such an emergency has occurred, he and he alone is empowered to do whatever he deems necessary to ensure "continuity of government." This could include everything from canceling elections to suspending the Constitution to launching a nuclear attack.

REX 84

The Rex 84 Program was established on the reasoning that if a mass exodus of illegal aliens crossed the Mexican/US border, they would be quickly rounded up and detained in detention centers by FEMA. Rex 84 allowed many military bases to be closed down and to be turned into prisons. With half a million entering the US every year, not one of them has been put in a FEMA camp yet! What are they waiting for?

NATIONAL DEFENSE AUTHORIZATION ACT

Sect. 1042 of the 2007 National Defense Authorization Act (NDAA), "Use of the Armed Forces in Major Public Emergencies," gives the executive the power to invoke martial law. For the first time in more than a century, the president is now authorized to use the military in response to "a natural disaster, a disease outbreak, a terrorist attack or any other condition in which the President determines that domestic violence has occurred to the extent that state officials cannot maintain public order."

If the US government spends billions of dollars on Homeland Security, they scan all of our emails, record all of our telephone calls, and watch almost everything we do; because they expect a Muslim terrorist to blow up our country any minute, then why did they allow 9 million Muslims to come into our country?

WARNING!

FEMA EXECUTIVE ORDERS

E.O. 11004 - Allows the Housing and Finance Authority to relocate communities, build new housing with public funds, designate areas to be abandoned, and establish new locations for populations.

E.O. 10990 - Allows the government to take over all models of transportation and control of highways and seaports.

E.O. 10995 - Allows the government to seize and control the communication media.

E.O. 10997 - Allows the government to take over all electrical power, gas, petroleum, fuels and minerals.

E.O. 10998 - Allows the government to take over all food resources and farms.

Etc. these are real presidential executive orders!
Not to mention these are just a few of them...
To learn more Google fema executive orders.

ARMY TRAINING MANUAL

The manual states, “These operations (camp) may be performed as domestic civil support operations,” and adds that “The authority to approve resettlement such operations within U.S. territories,” would require a “special exception” to “The Posse Comitatus Act,” which can be obtained via “the President invoking his executive authority.” The document also makes reference to identifying detainees using their “social security number.”

Mock Military Invasions

UNITED STATES ARMY

http://www.independentsentinel.com/2013/03/military-drills-armored-tanks-zombies-are-coming-to-a-city-near-you/

DRONES

- The U.S. has over 8,000 drones
- They are used by police for surveillance on Americans
- They are used along the borders
- Some states have passed laws against flying drones

CHRISTIAN PERSECUTION

Media Silent as Muslims Ethnically Cleanse 60,000 Christians in Philippines

http://frontpagemag.com/2013/dgreenfield/media-silent-as-muslims-ethnically-cleanse-60000-christians-in-philippines/

PERSECUTION AT UNPRECEDENTED LEVELS

The Body of Christ today is suffering a degree of persecution not seen previously in our lifetime. In Central African Republic a serious humanitarian crisis is unfolding as the predominantly Christian population suffers terror at the hands of Islamic rebels. Afghan converts risk death not only in Afghanistan but also in India because the Afghan media is inciting violence against them, particularly Pastor Obaid. In Somalia, al-Shabaab routinely kills Somali converts.

Mustaf (13), who has already lost two Christian relatives to al-Shabaab, was recently kidnapped by militants seeking to draw his Christian parents out of hiding. For example on 30 August eleven Laos families (50 people) were expelled from their village and sent out into the bush for refusing to renounce Christ. On 1 September nine Catholics were massacred by Fulani Muslim gunmen in Nigeria's Kaduna State. On 4 September jihadists killed eight Syrian soldiers before seizing control of the Aramaic-speaking, Christian village of Maaloula in western Syria.

"The power of the Executive to cast a man into prison without formulating any charge known to the law, and particularly to deny him the judgment of his peers, is in the highest degree odious and is the foundation of all totalitarian government whether Nazi or Communist."

- Winston Churchill, Nov. 21, 1943


HORSEY
ON THE PLUS SIDE, WE SEEM TO HAVE HIT BOTTOM.
U.S. ECONOMY



Fed downgrades its outlook for US economy

Federal Reserve sketches a gloomier outlook for US economic growth for this year and next

AP By Christopher s. Rugaber, AP Economics Writer | Associated Press – 5 hours ago

WASHINGTON (AP) -- The Federal Reserve on Wednesday downgraded its outlook for the U.S. economy for 2013 and 2014. In doing so, it underscored concerns that led it to maintain the pace of its stimulus.

The Fed predicted Wednesday that the economy will grow just 2 percent to 2.3 percent this year, down from its previous forecast in June of 2.3 percent to 2.6 percent growth.

Next year's economic growth will be a barely healthy 3 percent, the Fed predicts.

Fed officials decided to continue their $85-billion-a-month bond purchase program, surprising most economists, who had expected a slight reduction. The bond purchases have been designed to keep long-term loan rates low to encourage spending.

The Fed's policymakers expect the unemployment rate to fall to 7.1 percent to 7.3 percent by the end of 2013, slightly below its June forecast of 7.2 percent to 7.3 percent. It predicts that unemployment will fall as low as 6.4 percent next year, down from 6.5 percent in its June forecast.

The unemployment rate is now 7.3 percent.

The projections showed that 12 of the 17 officials on the Fed's policymaking committee think the Fed shouldn't begin raising rates until 2015. And two think the Fed shouldn't do so until 2016, one more than in June. Three chose 2014, the same as in June.

The Fed doesn't say which policymakers made which forecast.



Foreigners Dumping the Most Treasuries in History!

$40.8 BLN in sales is worst ever!

Data Source: US Treasury

FINANCES IN THESE DIFFICULT TIMES

IL 87266782 C
THIS NOTE IS LEGAL TENDER
FOR ALL DEBTS, PUBLIC AND PRIVATE
Treasurer of the United States.
FEDERAL RESERVE NOTE
UNITED STATES OF AMERICA
WASHINGTON, D.C.
SERIES 2006

We Are Now On The Verge Of A Historic Meltdown & Collapse

On the heels of a tremendous rally in gold and silver, today a man who has been involved in the financial markets for 50 years shocked King World News when he said that we are on the verge of a historic and catastrophic global financial "meltdown." He also spoke about events that are unfolding behind the scenes at the White House right now. This is without question one of John Embry's most powerful interviews ever.

Embry: ***"I guess I'm always unnerved as a result of what happened in April, the last time the President of the United States had a meeting with all of the bank heads, and two days later the price of gold was smashed for over $200. Now, the President is meeting with all of the heads of the various agencies, institutions, the Fed, and all of the other key money entities in the United States today. What's that all about?***

But clearly if the President is having this meeting, there is a crisis unfolding somewhere in the background, and it could very well relate to the dollar, interest rates, and the massive derivatives market associated with interest rates....

“Rising interest rates are a killer in an over-levered economy, and that’s exactly what we’ve been seeing in the United States.

This surge in interest rates may have already seriously destabilized the entire financial system, and that’s why there is this meeting taking place in the White House today. The fact is that the vast majority of derivatives in the global financial system are related to interest rates.

Now, the entire financial system may be on the precipice of some sort of catastrophic event unfolding because of what we have already seen in the bond market, and how the derivatives are so heavily intertwined. Meaning, we may be on the verge of another disastrous derivatives meltdown.

We have an unbelievable amount of interest rate derivatives in the financial system. So the winners theoretically take the profits on them, and the losers simply misprice them on their books. But as you get higher interest rates it becomes even more destabilizing.

I firmly believe the reason the President has called this meeting today is because if interest rates in the U.S. continue to rise, it could really unleash something disastrous. We are talking here about the possibility of a meltdown.
http://kingworldnews.com/kingworldnews/KWN_DailyWeb/Entries/2013/8/20_We_Are_Now_On_The_Verge_Of_A_Historic_Meltdown_%26_Collapse.html

Financial Crisis Alert: Half A Million People Drop Off Workforce In One Month, Bank of America To Cut 2100 Jobs, Shut 16 offices, HP Has Chopped 22,700 Jobs Since Last Year, Polled Unemployment Soars To March 2012 Levels!

Bank of America


9.5
9
8.5
8
7.5
7
6.5
Jun-11
Sep-11
Dec-11
Apr-12
Jul-12
Oct-12
Jan-13
May-13
Aug-13
Gallup Unemployment (%)
Government Unemployment (%)



http://investmentwatchblog.com/financial-crisis-alert-half-a-million-people-drop-off-workforce-in-one-month-bank-of-america-to-cut-2100-jobs-shut-16-offices-hp-has-chopped-22700-jobs-since-last-year-jpmorgan-exits-commodity-a/



US Pension Funding Ratios by State

(Ranked in Descending Order, All 50 States)

Source: Mauldin Economics; State Budget Solutions, September 2013; Manhattan Institute for Policy Research, August 2013

International Investors Dump $40.8 Billion in Treasuries, the Most Ever

Money and Markets

Foreign holders dumped a whopping $40.8 billion in long-term Treasuries, the biggest exodus from bonds in the history of the U.S. Worse, June was actually the third month of mass dumping in the past four, for a total of $79 billion. China, the biggest holder of our bonds, unloaded $21.5 billion, while Japan, the second-largest holder, dumped $20.3 billion.

It wasn't just government bonds, either. Foreigners dumped $116 million of bonds made up of packaged U.S. mortgages. They sold $5.2 billion of Fannie Mae, Freddie Mac and Ginnie Mae bonds, and $5 billion in corporate bonds. And they unloaded $26.8 billion of U.S. stocks. All told, more international capital flowed *out* of U.S. markets than at any time in history, worse even than at the depths of the 2008 credit crisis.



State's unfunded pension debt will grow to more than $200 billion under new reporting rules

	Unfunded liability as currently reported	Unfunded liability under Moody's
TRS	$43.5 billion	$120.6 billion
SERS	$20.2 billion	$46.2 billion
SURS	$17.6 billion	$39.3 billion
JRS	$1.3 billion	$2.6 billion
GARS	$0.2 billion	$0.4 billion
Combined	**$82.9 billion**	**$209.0 billion**

Source: Commission on Government Forecasting and Accountability; Illinois Policy Institute

Market Week Pullout Dow Falls 1.3% on Syria Fears; Time to Buy Tyson Foods Page M3

BARRON'S

The Dow Jones Business and Financial Weekly Vol. XCIII No. 35 barrons.com September 2, 2013 $5.00

Good Hands: Allstate Could Rise 50%
Page 16

THE BULL'S IN CHARGE

Despite recent stock-market declines and the possibility of an autumn correction, Wall Street's top strategists see the market headed higher over the longer term, with stocks rising 20% or more in 18 months.

RANDALL W. FORSYTH • 5
Obama's Hobson's choice on Syria

STREETWISE • 9
Investors pause but don't panic

SHOT IN THE ARM • 14
Onyx deal will give Amgen a boost

CLOUDY OUTLOOK • 17
Woes at Elon Musk-backed SolarCity

PLACE YOUR BETS • 20
Regional casino stock could rise 30%

INTERVIEW • 21
Cliff Asness sees risk everywhere

TAKEOVER BAIT? • M8
A flush Vodafone could attract AT&T

DOW JONES

Subscriptions/Customer Service: 800 544 0422


16000
15000
14000
13000
12000
11000
10000
9000
8000
7000
6000
1997
1998
1999
2000
2001
2002
2003
2004
2005
2006
2007
2008
2009
2010
2011
2012
2013
Still Bullish
DOW 17000
BARRON'S
DOW 14,000?
BARRON'S
DOW 16,000!

UNITED STATES DOLLAR

China and Japan a few weeks ago sold $48 billion worth of U.S. Treasury Bonds in one day more than ever in history. Bernanke and the Fed are printing $85 billion per month ($40 billion to buy Mortgage Backed Securities and $45 billion to buy Treasuries). All foreign countries are buying less US Treasury bonds since June of this year. This is very bad news.

WHAT TO DO TO PREPARE FOR THIS?

1. Get a job and keep it
2. Start a job on something that makes money
3. Store cash at your home
4. Buy gold and silver eagles and keep it at home
5. Pay off your bills
6. Store food
7. Store water

8. Store guns & ammunition

9. Store toilet paper

10. Store tooth brush, tooth paste, shampoo, soap, etc.

11. Have something to cook on such as an outside gas cooker, fireplace, or solar cooker.

12. Store cooking oil, condiments, bowls, cups, etc.

13. Have a water filter- Big Berkey

Preston T. Bailey, PhD., D.Min.

"That's all Folks!"

www.SaveAmerica Foundation.com

Donald Marshall On Megadeth's "The World Needs A Hero" Album Cover

Empowerment by Virtue of Golden Truth
Human Cloning: Specifically,
REM Driven Human Cloning
FULL DISCLOSURE

Donald Marshall

29 October 2015

https://www.facebook.com/donald.marshall.148
http://donaldmarshall.proboards.com/
Vincent Eastwood Interview
https://www.youtube.com/watch?v=M_1UiFeV5Jg&ab

Contents

List of Images 5

Introduction 6

Whistle Blowing: Qualifying Disclosure 6

The Serious Crime Act 2015 7

Fundamentals 8

Key Figures 9

- *Phil Schneider* 9
- *George Green* 11
- *Aaron Russo* 13
  - *Income Tax* 13
  - *Radio Frequency Identification (RFID) Microchips* 14
  - *Habeas Corpus* 15
  - *Fraudulent Manipulation of Election Results* 15
  - *The War on Terrorism is the War on Your Freedom* 16
  - *Whoever Makes the Money Makes the Rules* 16
  - *Russo's Message to Mankind* 16
  - *Let's Consolidate our Problems* 17
- *Aaron Russo: Reflections and Warnings* 17
  - *The Falsehood of September 11th 2001* 17
  - *The New World Order Agenda* 19
  - *Women's Liberation from the Perspective of the Elite* 20
  - *America is a Republic* 20
  - *Depopulation* 21
  - *Borrowing Money from Private Banks causes Inflation and Debt* 21
  - *The Deception of the Council of Foreign Relations (CFR)* 23
  - *Combining America, Mexico and Canada into one Country* 24
  - *Russo's Vision on How to Bring These People Down* 25

The Trans-humanist / Post Human Agenda 26

The Phases of Sleep and Rapid Eye Movement (R.E.M) Sleep 27

REM Sleep 28

Current Advances in Technology 28

- *Memory Suppression Technologies* 29
- *Mind-Voice Technology* 29
- *H.A.A.R.P. Technology* 29
- *H.A.A.R.P. and Weather Control* 30
- *H.A.A.R.P. and Mind Control* 31
- *RFID Technology* 32

RFID Technology and the Medical Profession 32
Further Implications of RFID Technology 33
Mind Control: MK Ultra Technology 33
Human Cloning 35
Cloning Centre and Cloning Technology 36
Drip Feed Disclosure and Evaluative Conditioning 36
Drip Feed Disclosure 36
Evaluative Conditioning 37
Consciousness Transfer 38
Disclosure: Save the Victims through your Diligence 40
Words of Inspiration: Personalized from a Theoretical Physicist –Thomas Campbell 41
The Science of Hidden Consciousness 41
Disclosure: Donald Marshall’s Message to the World 42
The Two Types of Cloning Techniques 42
The Different Grades of Clones: “Mark 1” to “Mark 4” Clones 43
Donald Marshall’s Dilemma with “Mark 2” Sleep Driven REM Clones 43
Consciousness Transfer Happens When the Original Reaches REM Sleep 43
Donald Marshall is an Original as he sits at Home Typing this Disclosure 44
When Donald Marshall’s REM Driven Cloned Experiences Began 45
The Science of REM Driven Cloning Began in 1945 46
Help Donald Marshall STOP REM Driven Cloning NOW! 47
Do Not Panic, Riot, or Cause Chaos. This is Very Important. 47
Spread this Disclosure Document until it reaches the Armed Forces 47
Donald Marshall is NOT “The New Age Saviour”. Nobody wants to be a ‘saviour’ 48
How the Nostradamus Prophecies shapes the lives of the Illuminati 49
HIV/AIDS has been cured; so have many forms of cancer 49
The Behaviour of High Profile People at the Cloning Centre 50
The Ring Leaders of the Cloning Centre 50
The Royal Family of England 53
Help Donald Marshall by Sharing this Disclosure with Your Close Friends and Family 57
The Deplorable Nature of the Illuminati 59
What Happened to Britney Spears? 60
NEVER EVER SELL YOUR SOUL 62
In This Physical World Selling Your Soul Is Selling Your REM Driven Clone 62
Fake Alien Abductions conducted through REM Driven Cloning Technology 64
I am THE Spy for Humanity against the Corruption of the Illuminati 65
The Threat to Humanity when the H.A.A.R.P Grid is Complete 66
REM Driven Cloning is the Most Terrible Nightmare Situation Ever 68

  - *The Meek Shall Inherit the Earth* 70
  - *Be Wary of: Shills; Trolls; Disinformation Agents and Double Agents* 72
- *Contact Information* 73
- *Interviews* 74
  - *Links to Donald Marshall Interviews* 76
    - *Vincent Eastwood* 76
    - *Jeanice Barcelo* 76
    - *Lisa Phillips (CFR)* 76
- *Radio Presenters –Contact Donald Marshall* 77
- *Professionals who understand "Consciousness Transfer" –Contact Donald Marshall* 77
- *Email* 77
- *How to Learn More about Donald Marshall's Whistle Blowing Disclosures* 77
- *How Much Do You Know About Post-humanism / Trans-humanism?* 78
- *This IS your ONLY chance to end these monsters. There is a deadline!* 79
- *Do NOT Be Afraid to Help. We Outnumber the Illuminati by 1,000,000:1* 80
- *Noteworthy Frequently Asked Question* 81
- *Donald Marshall's Mission and Vision on How to Bring Down The Illuminati* 81
- *Empowerment by Virtue of Golden Truth* 83
- *Appendices* 84
  - *Appendix A: Thien Thanh Thi Nguyen (Tila Tequila) Transcript* 84
  - *Appendix B: MK Ultra* 87
  - *Appendix C: The Illuminati* 89
- *References* 99
- *Legislation* 111

List of Images

Image 1: Stages of sleep.. 27
Image 2: The ionosphere's relationship to earth.. 30
Image 3: Megadeth Album Cover: *The World Needs a Hero* (2001)... 58
Image 4: Donald Marshall's original body compared with his REM Driven Duplicate Clone. 58
Image 5: Britney Spears Japanimation: Britney Spears grown as a duplicate clone.......................... 61
Image 6: Britney Spears Japanimation: Britney Spears walks into the Cloning Centre..................... 61
Image 7: Britney Spears Japanimation: The Cloning Centre depicted from an aerial view................ 61
Image 8: Possible H.A.A.R.P. Locations. 67

Introduction

Just read it. Every word in this document is true, and it is the most important document to ever reach the internet. This document is written to empower good people of the world against the tyranny which exists all around us in our world today. Effectively, the document presented here discloses concealed information about the extent to which medicine, science, and technology has advanced in our **current** era. Moreover, I am disclosing this information because I have been extensively abused, and I am victim of **current** advances in medicine, science, and technology, which I describe in detail below. There are many, many, other victims of abuse, including myself, and therefore it is our plea that you read this document with an open mind and you investigate **ALL** statements which may initially irk you and appear 'suspect' to begin with (the circumstantial evidence is available all around you); because as a victim of abuse, I can honestly say, there is nothing worse than experiencing abuse, and those who have the power to protect you from your abusers, ignore you.

I will now discuss what qualifies as whistle blowing disclosure. After detailing the criteria which qualifies for whistle blowing disclosure, I will detail aspects of the Serious Crime Act, and preface a foundation which defines, explains, and references key information for the reader to understand as well as explore the extent to which medicine, science, and technology has advanced today; all for the express purpose of compelling the reader that medicine, science, and technology, has advanced at an incredible rate; that **current** advances in medicine, science and technology are withheld from public knowledge; and finally these advancements in medicine, science, and technology, have been and are **currently** used to commit **serious unspeakable** crimes against humanity and our environment here on earth. Moreover, it is my aim to present this information as coherently as possible to assist the reader to save me, and save many, many others who experience abuse daily resulting from concealed advances in technology.

Whistle Blowing: Qualifying Disclosure

In the United Kingdom under the Public Interest Disclosure Act (1998) (PIDA) section 43B, a "qualifying disclosure" (whistle blowing disclosure) implies "any disclosure of information which in the reasonable belief of the worker, tends to show one of the following:

a) That a criminal offence has been committed, is being committed or is likely to be committed,
b) That a person has failed, is failing or is likely to fail to comply with any legal obligation to which he is subject
c) That a miscarriage of justice has occurred, is occurring or is likely to occur,
d) That the health or safety of any individual has been, is being or is likely to be endangered,
e) That the environment has been, is being, or is likely to be damaged, or
f) That information tending to show any matter falling within any one of the preceding paragraphs has been, or is likely to be deliberately concealed"

Furthermore, under the Enterprise and Regulatory Reform Act (ERRA) 2013 section 17 (*The new 'public interest' test)* is added for whistle blowing disclosures, amending section 43B of the Employment Rights Act (ERA) 1996 and therefore now reads as such (new words underlined):

"(1) In this part a 'qualifying disclosure' means any disclosure of information which, in the reasonable belief of the worker making the disclosure, *is made in the public interest and* tends to show one or more of the following-- [criminal offence, breach of legal obligation, etc]." (Halliday 2013, p. 2).

The following information is presented **with the express intent** that it is made in the public interest, and meets the all criteria set out in section 43B (a-f) of PIDA as well as the 'public interest test', ERRA section 17. Furthermore, in order for the reader to perceive the credence of my statements, so that (s)he has impetus to research the validity of my statements and not dismiss it as folly supplied by an internet troll who has nothing better to do than waste peoples' time, I will cite the Serious Crime Act 2015 here for the express purpose of convincing the reader that all statements made in this document and my original document are indeed FACTUAL! THIS IS NO HOAX. THIS IS NO JOKE. This is simply what is happening in the world today.

The Serious Crime Act 2015

The Serious Crime Act 2015 (UK) section 41, 3ZA, amends section 3A of the Computer Misuse Act 1990 which **previously** read [under Computer Misuse Offences]:

[F1 3A Making, supplying or obtaining articles for use in offence under section 1 or 3

1) [That] A person is guilty of an offence if he makes, adapts, supplies or offers to supply any article intending it to be used to commit, or to assist in the commission of, an offence under section 1 or 3.

To: [The Serious Crime Act 2015, section 41, 3ZA]

3ZA Unauthorised acts causing, or creating risk of, serious damage

(1) A person is guilty of an offence if—

(a) the person does any unauthorised act in relation to a computer;

(2) Damage is of a "material kind" for the purposes of this section if it is—

(a) damage to human welfare in any place;

(b) damage to the environment of any place;

(c) damage to the economy of any country; or

(d) damage to the national security of any country.

3) For the purposes of subsection (2)(a) an act causes damage to human welfare only if it causes—

(a) loss to human life;

(b) human illness or injury;

(4) It is immaterial for the purposes of subsection (2) whether or not an act causing damage—

(a) does so directly;

(b) is the only or main cause of the damage.

(5) In this section—

(c) a reference to a country includes a reference to a territory, and to any place in, or part or region of, a country or territory.

(6) A person guilty of an offence under this section is (unless subsection (7) applies) liable, on conviction on indictment, to imprisonment for a term not exceeding 14 years, or to a fine, or to both.

(7) Where an offence under this section is committed as a result of an act causing or creating a significant risk of—

(a) serious damage to human welfare of the kind mentioned in subsection (3)(a) or (3)(b), or

(b) serious damage to national security,

a person guilty of the offence is liable, on conviction on indictment, to imprisonment for life, or to a fine, or to both."

In laymen's terms it is a **serious crime** (Serious Crime Act 2015), punishable by imprisonment, a fine, or both, to cite hatred or spread hoaxes by use of a computer which would cause mass hysteria or public dissension. I have been condemning public figures, high profile individuals, celebrities, singers, movie stars, directors, politicians, world leaders, royalty, anti-secret society 'truthers' (who are really misinformation agents, and agents of deception) etc. –the list is long - since 2011 and **NOT** a single one of these high profile people has issued a public statement saying "I do not like how you have tarnished my name" or filed a law suit against me. Why you may ask? **Because** every word I have stated and will state again (in this document) is true.

Fundamentals

Before I describe the heinous crimes committed against me and many others (including unsuspecting civilians of the world) it is important that I explain, define, and reference:

- Key figures such as Phil Schneider, George Green and Aaron Russo, so that the reader has reference points to verify the extent to which technology has advanced in our **present** era (and continues to advance);
- Define and briefly explain the transhumanist / post human agenda (for those who may be unfamiliar with their aims).
- Define and explain rapid eye movement (R.E.M) sleep, the phases of sleep, and what happens to the (original's) body during sleep.

- Reference advances in technology, with particular attention to: Memory suppression technologies; Mind-voice technology; H.A.A.R.P technology, RFID microchip technology, and MK Ultra technology (CIA's mind control program);
- Define and explain cloning; the different types of clones; cloning centres and cloning technology;
- Define drip feed disclosure / evaluative conditioning and explain why it occurs;
- Explain what 'consciousness transfer' is to the best of my knowledge, and cite drip feed disclosure articles with the express intent to allow the reader to grasp the abuse I have suffered daily at the hands of my tormentors.

Key Figures

Phil Schneider

Phil Schneider (pictured) had 17 years experience working in government black projects carrying a level three security clearance. He was a geologist and engineer who worked in the black projects underground bases at Area 51, S-4, and Los Alamos.

He is most notable for disclosing (Schneider 1995; 1996; Open Minds 2011):

- The 'black budget' expenditure of the United States, which Schneider claims to be between 1.023 trillion U.S. dollars every 2 years (over $500 billion per year);
- Deep Underground Military Bases (also known as D.U.M.Bs -"dumbs"), and at the time of his lecture (Schneider, 1995), –that there are 131 **active** Deep Underground Military Bases present in the United States, and 1477 Deep Underground Military Bases worldwide;
- Each D.U.M.B costs on average 17-19 billion U.S. dollars; paid for by the taxpayer; and it takes approximately a year-and-a-half to 2 years to build D.U.M.Bs with sophisticated methods.
- That military technology outstrips the general public's technology at a rate of 44 to 45 years of technology for every calendar year which passes. In other words for every 12 months which passes military technology will have advanced by 44 years than what we as the general public is currently accustomed to. Therefore as a rough example if we were to take the year Facebook was founded (2004) as a base year, then the military technology since the creation of Facebook will have outstripped what the

general public is accustomed to by as much as **484 years(!)** (2015 - 2004 = 11. 11 x 44 = 484). Similarly, if we are to use the year which YouTube was founded as a base year (2005), once again, military technology would be 440 years more advanced than what the public is currently accustomed to today.

For the purpose of disclosing current advances in medicine, science and technology, and how such advances are used against me and the people of the world to commit monstrous crimes I will use 1945 as a base year. Everything will become apparent including why I use 1945 as a base year for my disclosure, but for the express purpose of compelling the reader to investigate my disclosure I must present everything, logically, sequentially, methodologically, and provide references for the reader in a coherent way to enable him or her to **pay serious attention** to my eye witness accounts. Therefore, at this present stage keep in mind the year 1945, and the fact that military technology outstrips the general public's technology at a rate of 44 years for every 12 months which passes.

George Green

George Green (pictured) was affiliated with U.S. Presidential candidates, and was once asked to be the Finance Chairman for the next President of the United States. Green would later declined the offer of Finance Chairman when a comment made by Ted Kennedy regarding sleeping with Green's 14 year old daughter caused George Green to re-evaluate his associations with this in-group.

During his 2008 interview with Project Camelot (2008a; 2008b), Green disclosed the following noteworthy information:

- U.S. presidents are "selected" and not elected. This is clearly expressed in a story Green recounts, when Green asks:
  "Who is going to be the next President of the United States [for him to overlook their finances]?"
  And the reply was: "Jimmy Carter"
  Green responds: "Jimmy who?"
  The reply Green received was: "Well, he's the Democratic Governor of Georgia."
  George Green: "But I've been voting Republican."
  Green was then confronted by a tall man, Paul Volcker (American Economist, and Chairman of Federal Reserve under Jimmy Carter and Ronald Regan), who walked over and said, "Son, don't worry about it [Republican or Democrat], we control 'em both."
- U.S. scientists learned how to make people (clones) since 1938 -walking talking ones –and the scientists call these people "synthetics" or "the others".
- Cloning technology is relatively advanced. All that has to be done is take two cells from the original, give the cells a small electrical charge (retain a fertilised egg), then all one needs is a receiver (a womb / artificial womb for the fertilised egg to grow).
- Scientist were excited by the synthetic technology because it meant that spare organ parts could be grown for an "original" human without rejection, because theoretically speaking, the DNA of the synthetic is the same as the original.
- Green gives an example of a cloned Politician: George Walker Bush. Green advices the viewer to seek old video recordings of George W. Bush, and compare the old George W. Bush, with the George W. Bush during Bush's second term,

-in terms of mannerism, speech pattern, body language etc. (old videos of George Walker Bush (Boringest 2006; Fox 4 News - Dallas-Fort Worth 2014) are presented in the References section).

- Scientist have also learned how to make these synthetic people within a few months, to the point where the synthetic can be a walking, talking duplicate of the original, intact with all the memories and experiences of the original. The only problem is that the memory, experiences, and functioning capabilities of these synthetics are like: "A DVD recorder. Sometimes you have glitches, and you have to take the synthetics to Camp David occasionally [every 6 months to a year] to get them tuned up."
- Remember these synthetics are people too, they can think and act just like you can, but they do not have a soul.
- Most of the world leaders have been bought and paid for [by men in the background] and are created to think a certain way –to meet the agendas of these men who remain in the background.
- The global elite plans on depopulating the current human population of **over 7 billion** to **500 million** people. This is corroborated by the "Georgia Guidestones" (WorldTruth 2014).
- Vladimir Putin is executing plans to bring the United States down and into a massive depression. Furthermore, China agrees with Vladimir Putin's plans; stating that the Chinese government has not been a Superpower for over 5000 years and "It is their turn to run the world."
- China has the capacity to set back / shut down all of U.S. computing and electrical systems within two days.

At this present stage, the most **salient** points to keep in mind from Green's accounts are that: U.S. presidents are selected and not elected; and **most importantly**, that scientists have been capable of creating synthetics (cloning people) since 1938. If you have kept in mind Schneider's statement (1995; 1996), (that for every 12 months which passes military technology increases by the equivalent of 44 years compared to what the general public is accustomed to) –then learning that scientists have been capable of cloning humans since 1938 should not come as much surprise. Again, everything regarding my disclosure will become apparent, and I thank these men for disclosing their information, because it helps the reader to corroborate my disclosure.

Aaron Russo

Aaron Russo (pictured) was an American businessman, director, and political activist. He is best known for directing blockbuster films such as *Trading Places*, *The Rose* and *Wise Guys.* Russo believed that a human being "Should stand for something, and do the right thing when the time calls to act". Consequently, during the latter part of his career he did his best to warn the American public by producing documentaries such as *Mad as Hell* (1996), *Freedom to Fascism* (Russo 2006), and *Reflections and Warnings* (Jones 2008).

Russo disclosed the following key information in *Freedom to Fascism* (Russo 2006):

Income Tax

- There is no law requiring Americans to pay income tax. **Although this is a truth, I DO NOT advocate Americans NOT to pay income tax (and neither did Russo).** This is simply because the Federal Reserve can imprison you and seize your possessions for not paying income tax (although there is no law requiring Americans to do so). So for the sake of avoiding hassle for the mean time –pay your income taxes.
- To further illustrate the above point, Bob Shultz speaking at "We the People Foundation" said the following: "Most people believe that the income tax system is legal and that the revenue from the tax is used in the public interest. However, there is a substantial conclusive body of evidence that proves that our income tax system represents the most pernicious form of tyranny. It is the greatest hoax ever perpetrated by government against the working men and women of America."
- Charlie Beall: "The federal government itself refuses to provide, the American people, who are coercively being subjected to this extraction of their private property, without any underlying legal justification. There is no law. There is no law that requires the average American worker in the private sector to pay a direct un-apportioned tax on their labour and compensation for services. There is no law."

- State Representative – Phil Hart –(R-Idaho): "You can look through the statutes, and look for the law that requires you to pay, and when you do that, you **cannot** identify a law that requires the average person in America who earns a wage and works in private business to pay an income tax."
- Peter Gibbons (Tax Attorney) –It's actually very simple. Congress tried to enact an income tax in 1894 –The Supreme Court said that is unconstitutional. When The Supreme Court says something is unconstitutional, it's unconstitutional. They (Congress) tried again in 1913 –and The Supreme Court said –the 16th amendment- "No new power of taxation" –so if they (Congress) didn't have it then (1913) and they didn't get it; they **DON'T** have it. There is no constitutional base for a tax on the wages for Americans living and working in the 50 States of the union. Period. End of argument.

Radio Frequency Identification (RFID) Microchips

- The latest technology for identifying people at the point of self, when they make purchases –is actually the implantable (RFID) microchip. There are microchips that can actually be imbedded directly into human flesh... It's a tiny glass capsule about the size of a grain of rice... it contains an RFID computer microchip with a coiled antenna and it can transmit information also at a distance.
- Katherine Albrecht –Author of "*Spychips*" (2005) makes the following comment: "RFID is a technology that uses tiny computer technology the size of a grain of sand or smaller; hooked up to miniature antennas to transmit information about items at a distance. Back in 1999, Procter and Gamble, Gillette, and MIT got together to find a way to commercialise this technology and make it small enough, make it efficient enough and make it low cost enough to essentially ---their dream is to put these tiny computer chips on every physical item manufactured on planet earth."
- Radio waves can travel through walls, they can travel through wood, and they can travel through things we normally rely on to protect our privacy, for example your purse, your bag-pack, your pocket, –anything you are wearing or carrying.
- One of the most worrisome applications of RFID microchips, are proposals to put them into cash, meaning that it would be able to track every bank note where it had been, who it had been issued to, and create in essence an audit trail. That would essentially take away the anonymity of cash we now enjoy today.
- Once everything you do is tied down to a single number and there is no longer the ability to pay with cash, then all it takes to render you a non citizen is to simply turn that microchip off. **You will no longer be able to participate in any function in society including buying food. Once money becomes digitised through RFID technology, the elite can deduct whatever amount of money they want out of your microchip, whenever they want. They can trace you whenever they want. You will be at their mercy.**

Habeas Corpus

- Habeas Corpus is "[A] writ [formal document] requiring a person under arrest to be brought before a judge or into court, especially to secure the person's release unless lawful grounds are shown for their detention" (Legal-dictionary 2015).
- During the Bush Presidency [2001-2009 (History 2015)], President Bush signed executive orders giving him sole authority to impose martial law, and suspend Habeas Corpus. This gives him doctorial power over the people without any 'checks and balances.'

  In other words, "The government can jail you for life without charges, without a trial, without a lawyer" (Russo 2006).
- Furthermore: "The National Defense Authorization Act [4] signed by President Obama on the 31st December 2011 authorises the indefinite detention, without trial or indictment, of any US citizens designated as enemies by the executive." See Paye (2013) for further discussion regarding the suspension of Habeas Corpus.

Fraudulent Manipulation of Election Results

- In 2004 at the "Forum of Presidential Election" Clinton Eugene Curtis, a former Computer Programmer for NASA and ExxonMobil testified under oath that election results can be rigged using electronic programs.
- In 2004 he gave the following abridged testimony (Russo 2006):

  Judge: Mr Curtis, are there programs which can be used to secretly fix elections?

  Curtis: Yes.

  Judge: How do you know that to be the case?

  Curtis: Because in October of 2000 I wrote a prototype for present congressman Tom Feeney, and the company I worked for in Oviedo Florida –it did just that.

  Judge: And when you said, "it did just that" –it would rig an election?

  Curtis: It would flip the vote 51:49 –whoever you wanted it to go to, and whichever race you wanted to win.

  Judge: And would that program that you designed be something that election officials that might be on county boards would actually, could detect?

  Curtis: They'd never see it.

  Judge: So how would such a program, a secret program that, fixes the election –how could it be detected?

  Curtis: You would have to view it either with source code, or you would have to have a receipt and then count the hard paper against the actual vote total –other than that you won't see it.
- **Judge:** Given the availability of such vote rigging software and the testimony that has been given under oath of substantial statistical anomalies and gross differences – between exit polling data and the actual tabulated results, do you have an opinion whether or not Ohio elections, the Ohio Presidential elections was hacked?

  Curtis: Yes. I would say it was.

Person in the audience: ---So in other words there is absolutely no assurance whatsoever in anything in regard to these machines?
Curtis: Absolutely none.

- See Truthstream (2006) for further details regarding the full account of Curtis' testimony on how elections can be manipulated.
- Moreover, voting machine manufactures refuse to allow anyone to see the source code. Without paper ballots, the honesty of any election cannot be verified.

The War on Terrorism is the War on Your Freedom

- It is time to wake up America. These ID cards are not about defeating terrorism, but they are **ALL** about controlling the American people.
- The (mainstream) media controls the information that a person gets in various ways. They can make sure that the average American watching T.V. or reading the newspaper is going to come out with a certain mindset. She is going to say this is good, that's bad –and that is all they (media/elites) have to do.

Whoever Makes the Money Makes the Rules

- As Mayer Rothschild said "Give me control of a nation's money supply, and I care not who makes its laws". Mayer Rothschild, private banker, –knew that he and the other bankers would now control the laws of the nation. Government gave these bankers one of its most important powers, and now had to borrow money from the bankers and pay interest to finance the government.
- America has gone from people owning their own property, owning their own businesses –to a nation in debt because all the money is created by borrowing (from private banks) and this country has become one where people just live by borrowing.

Russo's Message to Mankind

- If you are in the military or law enforcement, remember you swore an oath [to uphold the law of the land]. You did not swear an oath to promote world government, or corporations.
- Now that you do understand what happened [to America, and the monetary system based on debt slavery] and how it is leading to a tyrannical one world government – the future of mankind depends on you –will you choose freedom or slavery?
- Stop being passive liberals. Stop being passive conservatives. Stop being passive centralists. Stop being passive human beings! When the media starts telling you that the country will fall apart if this is done... Do not be fooled!!
- Remember these are sick, malevolent and twisted people we are dealing with, trying to save themselves. Squash their agendas and stay on course.
- "I believe the time for mankind is time to give all or perish. Grow up or die. Grow up and become adults. Act like adults. Take some responsibility. The world which you have perceived is childlike; –and now the curtain has been pulled back for all to see."

- Unless people get active [get fully informed, and learn how governments of the world are conspiring against their people] and say –I am going to help shut down the Federal Reserve System; I am going to shut down the powers that be –the whole human race is doomed otherwise.
- We are coming near the end game and things are starting to accelerate... –and people are looking at the world leaders to declare martial law [which in turn will rid Habeas corpus].

Let's Consolidate our Problems

- If we can all get focused on how to win the game instead of all these different objectives –such as people are fighting for a better environment; people are fighting to keep their guns/gun control; there are all these different issues which are going on around the world -and which are all important on their own –but if we can consolidate on that and focus –and take all those people –and say –hey let's shut down the Federal Reserve, then we'll deal with those issues. Let's go to the agenda, the objective, the root cause of man's problems, first, then we'll go back to the other stuff.
- That is the priority right now. You have to cut off the head of the beast. And the head of the beast is the Federal Reserve System and the people behind it. You see, and that is what will save the world, and if people understand that –and they **stop** being passive liberals, and **stop** being passive republicans, but rather become **active** human beings –that is what will save the world!

Aaron Russo: Reflections and Warnings

In this documentary Russo recalls his relationship with Nick Rockefeller. Russo shares critical information Rockefeller discussed with him.

The Falsehood of September 11th 2001

- Russo met Nick Rockefeller through a female attorney who telephoned Russo and said "One of the Rockefellers would like to meet you." Russo made a documentary called *Mad as Hell* (1996), and Rockefeller had watched the video and knew Russo was running for Governor of Nevada and wanted to meet him. Russo said "Sure I'd like to meet him", and the two met and talked. Rockefeller proved to be a very smart man and shared ideas with Russo and was the person to tell Russo 11 months before 9/11 happened "There was going to be an event..."
- Rockefeller never told Russo what the event was going to be; but, there was going to be an event –and out of that event, we [America] were going to invade Afghanistan, to run pipelines from the Caspian Sea; we were going to invade Iraq, to take over the oil fields and establish a base in the Middle East, and make it all part of the New World Order; and we would go after (Hugo) Chavez and Venezuela –and sure enough, later when 9/11 happened –and I remember he was telling me how you are going to see soldiers looking in caves for people in Afghanistan and Pakistan and all these places and there is going to be this war on terror which has no real enemy and

the whole thing is a giant HOAX, but it is a way for the government to take over the American people (and the world).

- There is no question about it [that 9/11 is a hoax]. Nick Rockefeller said to Russo: "There is going to be a "War on Terror"" and he was laughing. Who are we fighting against...? Why do you think 9/11 happened and then nothing has happened since then? Do you think that our security is so great here that these people who pulled off 9/11, who were able to lock down another plane...? Come on it is ridiculous... 9/11 was done by people in our own government and our own banking system to perpetuate the fear of the American people into subordinating themselves to anything the government wants them to do. That is what it is about and to create this endless war on terror.
- Nick Rockefeller was laughing when he said, "We are going to be sending men into caves in Afghanistan and Pakistan" –and it was just cynical, he kept laughing and saying "Look how stupid everyone is! We can do whatever we want!"
- 9/11 was the first lie; and the next lie was to go into Iraq, to get Saddam Hussein out with his weapons of mass destruction (when the real issue was control of the oil fields) –that was the next lie. 9/11 created an endless war on terror that would go on and on and you can never define a real winner. There is no one to defeat and so it goes on and on forever. And they can do whatever they want; because they scared the hell out of the American public.
- This whole war on terror is [perpetuated on] a fraud. It is a farce. It is very difficult to say it out loud because people are intimidated in saying it. Because if you say it they want to make you into a nutcase –but the truth has to be... and the truth has to come out. The fact of the matter happens to be the whole war on terror is a fraud, it is a farce. Yes. There is a war going on in Iraq, because we invaded Iraq, and people over there are fighting... but the 'war on terror' –it is a JOKE –you know, and until we discover what really happened in 9/11 and who was responsible for 9/11 –because that is where the war on terror emanates from. That is where it comes from. It was 9/11 which allowed this war on terror to begin and until we get to the bottom root of 9/11 –the truth of 9/11 we'll never know about the war on terror.
- Russo was in Tahiti when 9/11 happened and he got a call from his son – and his son said –"The twin towers, they were just attacked and they are falling down or something..." Russo was in Tahiti and had just woken up from sleep. Russo didn't realise what it was immediately (11 months after Rockefeller had told him about 9/11 and it had happened –because Rockefeller said there was going to be an event –he wasn't specific) –but after Russo saw that America was going to go to Iraq and Afghanistan, that is when he realised, and equated it to what Rockefeller had said.
- 9/11 was only a manifestation to create a fear in the American public. So that we would obey and do what they want us to do. Take for example, Richard Reed 'The shoe bomber' –now here is a guy who is 6 feet 6, ugly as can be; I heard he smelled... He sits on a plane, lights a match in a non-smoking area, to put his shoe on fire... surrounded by people... That is idiotic! If you were going to blow up a plane... you would go into the bathroom... you close the door... and you put your shoe on fire...

you are not going to sit there.... surrounded by people, lighting matches in a no smoking flight... they (elite) want you to believe this nonsense. That is ridiculous!

- The war on terrorism is to keep people in fear. It is an endless war without a real enemy ('terrorists') –so that people would submit and do whatever the government wants them to. Submit to searches, give you ID cards, put Radio Frequency Identification (RFID) chips in you etc. You become servants to the elite –that is what this is all about...
- Freedom of liberty is what people really want, and it is time to stop the duplicity of the government from lying to us. You see many people know the truth of what is happening in this country; like 9/11 but they are afraid to stand up. People have to stand up and find their courage and say "I'm not going to take this anymore, I know the truth" –and they create a situation where if you tell the truth, you are considered a lunatic.
- In other words if someone goes on a T.V. show and says that 9/11 was an inside job – immediately the person is labelled an idiot or crazy. They call you names. **You cannot be afraid of that.**
- If you do not fight the corruption and you do not stand up for what is right in life, you end up being a serf and a slave and you are leaving your children a world in which you would not want to live in yourself, so how can you in decency behave that way? You have to stand up for what is right in life, and unless you do that you are nothing.

The New World Order Agenda

- The whole agenda is to create a one world government where everyone has an RFID chip implanted in them. All the money is to be in those chips [a cashless world]. This information came straight from Nick Rockefeller himself. That is what the ultimate plans of the global elite, banking industry and Rockefeller wants to accomplish.
- The agenda is to implant everyone with RFID microchips. All money is transferred to those microchips. There is no more cash. Money would be in microchips. Instead of having cash, you would have money in your microchips, but whenever they want, they (elite) could take whatever amount out of your microchip whenever they want to. Total control. If you are a protestor they just turn off your chip; you cannot buy food; you cannot do anything; it is total control of the people.
- So they want a one world government controlled by them. Everyone being chipped, all the money in those chips, and they control the chips and they control people, and you become a slave. You become a serf to these people –that is their goal. That is their goal; that is their intentions.
- Russo did not believe in enslaving people and Rockefeller would question him in the following manner: "Why do you care about them? Why do you care about those people? What difference does it make to you [Aaron]? Take care of your own life.
  Do the best you can for you and your family. What do the rest of the people mean to you? They don't mean anything to you. They are just serfs. They are just people..."

- Rockefeller asked –"Why are you fighting for the people for, what is it all about? The people have to be ruled. The constitution, what you are standing for is only for a few people, it's only for a few individuals who can live that way and we believe that it is best for society to be ruled by an elite people who control everything." Russo told Rockefeller he does not believe that. Russo believes: "God put me on this earth to be best person I could be and put everyone on this earth to be the best they can be, and NOT to be a slave and a sheep to YOU and these people (elite) –and I do not understand why you want to control everything. What is the need for that?"
- It was just a lack of caring [from Rockefeller's part], and that is just not who Russo was. It was just sort of like cold you know, and Russo used to say to Rockefeller, "What is the point, of all this? You have all the money in the world you need; you have all the power you need, what is the point? What is the end goal? Rockefeller said "The end goal is to get everyone chipped. To control the whole society. To have the elite people [the bankers and government] controlling the world."

Women's Liberation from the Perspective of the Elite

- Women's' Liberation was founded by the Rockefellers.
- Rockefeller asked Russo: "What do you think women's liberation was about?" At the time Russo had a pretty conventional thinking about it and he said "It's about women having the right to work; get equal pay with men; just like they won the right to vote." At this point Rockefeller started to laugh and he said to Russo "You're an idiot"
- Rockefeller said –"Let me tell you what that was about. We the Rockefellers funded women's' liberation. We are the ones who got it all over the newspapers and television. The Rockefeller foundation –and you want to know why? There were two primary reasons:"
- 1) "We couldn't tax half the population before Women's Liberation and the second reason was"
- 2) "Now we get the kids at an early age [because both parents are away from home working] –we can indoctrinate the kids how to think, so it breaks up their family –the kids start looking at the state as the family, as the school as the officials as their family, not as their parents teaching them, and so those are the two primary reasons for women's liberation."
- Russo thought, up to that point, Women's Liberation was a noble thing; however when he saw the Rockefellers' intentions behind it, where they were coming from when they created Women's Liberation; the thought process of it; Russo saw the evil behind what he thought was a noble venture.

America is a Republic

- America is a constitution republic / it is supposed to be a constitution republic –and **NOT** a democracy. The majority should not rule, and nor should the majority take over the inalienable rights of the minority.

- Americans pledge allegiance to the “Flag and the **Republic** which it stands” –and **NOT** democracy.
- Democracy is the worst form of government you can have because it is majority rule. Therefore the government can tell you what to do because ‘the majority’ wants it. It is irrelevant what the majority wants. Decisions should not take away the inalienable rights of an individual.
- Russo also said “It doesn’t matter who you vote for, republican or democrat; –they are the same –neither one of them is stopping the Federal Reserve or paying income taxes.
- The elite (Federal Reserve) have taken over the American government; there is no difference between republicans and democrats. There is no difference between the two parties. The duality is manufactured. They (Federal Reserve; central banks) control both parties. It doesn’t matter to the elite which one wins, because whoever is running for President will be someone they anoint. Whoever runs for President, will do whatever the elite want them to do. The fact of the matter happens to be that you cannot win an election unless you have enough money to win; they (Federal Reserve; central banks) make sure who gets the money.

Depopulation

- Russo and Rockefeller discussed many things –and one of the things Rockefeller brought up in conversation was reducing the world population. Rockefeller felt that there are too many people in the world. In a way Russo agreed that there are too many people in the world, but he **does not** think he has the authority to say who dies and who lives; but the elite felt that they want to reduce world population and Rockefeller felt it should be reduced by half.
- Rockefeller even mentioned to Russo in conversation, that they were having a real problem trying to solve the Israel/Palestine problem –and they were playing with the idea of bringing Israel to Arizona –and taking everybody from Israel and giving everybody a million dollars, and setting up Israel in the state of Arizona –because that is a problem that they are not in charge of.

Borrowing Money from Private Banks causes Inflation and Debt

- These people (elite) control the money so they make all the rules, and therefore they put the rules in which they want into effect, and the truth is America has really become a socialist communistic country. Everyone says it is a capitalistic country, but how can it be a capitalistic country when you have a central bank? That is the first question people should ask. It can’t be. It is a planned economy, it is a phony!
- If they want to create prosperity, they just print dollars, or put digits into the economy. Now you have prosperity. You do not have real prosperity, you do not have real manufacturing, you just have money being injected in which is infusion of credit. This makes the government go into more debt.

- Whoever makes the money makes the rules. Rothschild said that. Why are we allowing these private bankers to make the money for our country? It is nonsense. Why are we paying interest to these banks to make money for us when the government can do it itself without paying interest, without all that debt? There is no answer to that question and it is a question no politician will raise. Everybody talks about America's debt... We are in debt because we borrow money... but we don't HAVE to borrow money. They designed it so that we can go into debt. We can create the money, and back it by gold so that they cannot create too many of it, so that you do not have the inflation, and do what the Founding Fathers told us.
- Why in the world does the American government borrow money from the banks when they have the ability to create it themselves without borrowing it, and paying interest on it? Why? Nobody can answer that question –not one politician ever raises that. Why does the American government ever borrow money, when they can create it without paying interest?

  –And people say that –well if the American government creates it, it will cause inflation. And that is their answer. And Russo says well let's look at it: the American government has the Federal Reserve do it, which creates the same inflation as if they did it, but also with the inflation –now you are getting massive debt –so with the Federal Reserve you have inflation and debt. Now if the American government made the money, backed by gold which would limit the amount they could make –you wouldn't have debt and you wouldn't have inflation.
- It wasn't until 1913 when the Federal Reserve came in, that America had inflation. Before then there was no inflation for 100 years. There were points and spikes, mostly during the Civil War –but basically there was no inflation other than during that short period of time. I mean a loaf of bread would cost the same thing. People could plan their lives.
- Today, they have planned inflation, and now you have two parents working, they cannot afford to take and pay for their family anymore; the kids are going to state run schools now, the kids are being indoctrinated how to think; they are being given Ritalin, they are being given all these drugs, the whole country is being dumb down, it is all because of the Federal Reserve System; and the Federal Reserve system and these bankers are responsible for the demise of America. And if we ever want to win this battle you must shut down the Federal Reserve System, and we must shut down these bankers and restore sound money to this country.
- If you analyse the situation and if you realise that since the Federal Reserve has come into being since 1913, illegally, without a constitutional amendment, by bribing a few senators during Christmas vacation, they turned over the most important power that the American government has, the creation and issuance of money to a private bank.
- Through that private bank issuing money they have destroyed this country. They have destroyed the purchasing power of money in this country; they have created social programs that are destroying this country.
- The Federal Reserve has created massive inflation in America which means the American worker has to keep on making more money to keep up with the cost of

living. The more money they make to keep up with the cost of living, the less competitive they become in the world economy. So now what happens is that we have to pay our workers so much to keep up with the cost of living; and then they (elite; government; corporations etc.) say screw the American worker; let's go overseas now to get the cheap labour.

- The inflation the Federal Reserve has created has now allowed other countries to outcompete us. Other countries do not have to pay as much money as we have to pay to our workers to survive. So now we are not competitive anymore and we have lost our manufacturing base. We have lost our competitive edge.
- "Freedom to Fascism" is a documentary that everybody should see. Russo and his team show the fraud of the income tax; they show how Judges put people into jail for no reason; they show the corruption of the justice system. They show how the Federal Reserve came into being and how it is controlling society and how all the central banks are working together through the bank of International Settlements, in Switzerland which is the central bank for all central banks and how all are working together to create this one world government; this one world order; which is what they are trying to do.

The Deception of the Council of Foreign Relations (CFR)

- Russo was interested in joining the Council of Foreign Relations, but he found out from Rockefeller himself, that part of the end goal of the CFR is to get everyone RFID chipped. To control the whole society and have the elite people (bankers, government etc.) controlling the world. Russo asked Rockefeller "Do all the people in the CFR believe the way that you do?" Rockefeller said "No, no, no. Most of them believe they are doing the right thing. A lot of them believe it is better off being socialistic. We have to convince people that socialism is really capitalism." Because America is becoming a socialistic country; it is a communist country today.
- Russo's friendship with Rockefeller became one where they would share thoughts, ideas and philosophies and Rockefeller wanted Russo to become a part of what they were doing [enslavement agenda], and for Russo to become a member of the CFR; Rockefeller offered various business opportunities for Russo to get involved in the CFR and to **not** take up the fight or the battle that Russo had been taking up in the past. Rockefeller wanted Russo to drop the idea of helping the people; because "What was the point in Russo fighting for the people?" Rockefeller would question.
- Russo asked Rockefeller do all the people of the Council of Foreign Relations feel the same way you feel? Rockefeller said "A lot of them think they are doing the right thing, they think that socialism is the best way to go (but this form of socialism involves redistributing the wealth for the elites and not to everyone), they think that they are doing the right thing." But the people at the (very) top they all know the truth of what is happening. (Therefore, the good people in the CFR are also under an illusion, and do not know that effectively they are working for evil men who have the overall goal to control the populace of the world).

- So it is compartmentalised within the elite structure as well. All the people in the CFR -2000 to 3000 people like Dan Raddler –they don't know what is going on--- they join the CFR because it is prestigious. They think it is good for business, it is good for this; they don't know what is really happening –the evil that comes out of it –that is emanating out of it.
- In terms of the CFR, in terms of compartmentalisation, there are many good people which Russo believes are part of these organisations who do not even understand what these organisations are really about. For example, when Russo was in Germany, doing cancer treatment, there was a gentleman there who was visiting a friend of his with cancer. The gentleman visiting his friend was a member of the CFR, and him and Russo were talking and Russo showed him the movie (*Freedom to Fascism* (2006)); --and he said, "Oh my god! I'm going to resign." "I had no idea this is what the CFR is about". He had no idea; he is just a nice guy, who thought he was joining a prestigious organisation.
- A lot of people join the CFR because they think it is a prestigious organisation; it will help them in business; make good business contacts etc. They do not have an understanding that the CFR is really about world domination. How they, and the Trilateral Commission, The Bilderberger [Group], the banks, all work together to control the people –a lot of them do not understand that. They do not see the big picture. They think: Oh the CFR is a prestigious organisation. I'll make this, I'll make that, and I can do business deals. It is just business to them. The CFR wants to get the people in there that have influence and power, and so they are part of that (enslavement agenda), and so they are not opposed to them. So the whole country is becoming the haves and the have not. You are getting the very, very wealthy and the middle class being destroyed and you are getting the poor people.
- In Russo's words: "You can call the CFR what you like, but it is a criminal organisation. Run by criminals. But people do not think of it as a criminal organisation, because it has 'class'; 'style'; 'prestige'; –and it is 'respected'; so people do not look at it as being a criminal organisation. That is what a great job they have done."

Combining America, Mexico and Canada into one Country

- Imagine this... here you are in America, and they (elite) are combining American, Canada and Mexico into one country. The North American union. And the American people do not know anything about it. It is not even in the press. They would rather talk about Rosy O'Donnell and Donald Trump calling each other names than discussing the fact that we are merging into one country. This isn't even reported.
- The fact of the matter happens to be, that tells you how controlled the media is. The elite control the media, and they control governments and they are all in bed together. Here you are combining American, Canada and Mexico into one country, and you do not see it in the press. You do not see it in the press. Why? This should be one of the top stories everywhere –and the elite are not worried about it. That tells you –there is the evidence that [media] it is controlled. They do not want the American people to

know what is going on, that is why they do not protect our borders. That is why we are losing our constitution, the very document that secures our freedoms.

Russo's Vision on How to Bring These People Down

- There is no question we are in tyranny, there is no question that the American citizen is no longer a free individual human being, to do the things that they wish to do. We're slaves and it is getting worse.
- We are dealing with complete evil; and until the American people wake up and say, we do not want this evil in our country anymore and we want to come back to a country of decency and goodness, integrity and honour, we are going down that road and that is what it is going to take? It is going to take people to stand up and say we do not want to live in this kind of world anymore. I believe we should pull all of our troops out of Iraq, I believe we should leave other countries alone. Let other countries live their lives the way they choose to. Stop trying to spread 'democracy' around the world, which is the worst form of government there is anyway (because 51 percent rule over 49%), restore our republic to what it is supposed to be and go back to what the founding fathers gave us. Restore the republic.
- In Russo's opinion: The populace must shut down the Federal Reserve System –and there has to be an uprising. There has to be an uprising. People have to stand up. One person cannot do it alone. You cannot do it alone. People do not seem to have the courage to do what they have to do.
- A lot of people in Hollywood know the truth, they do not want to stand up and speak about it; I know many of them have seen my movie (*Freedom to Fascism* (2006)) and they know I am right, and they want to talk about it because everybody is afraid. Everybody is afraid because they think that the money they get from the Federal Reserve is really money and they have a comfortable lifestyle and they are afraid of change. They are afraid to stand up for what is right, and until people are willing to stand up and have the courage to do what they need to do, it is not going to change; and hopefully we can affect change when people stand up and say "Hey, I've had enough".
- We (the populace) have one advantage. They (elite) need us to cooperate. See, if we do not cooperate with them, they cannot win. They always need our cooperation with them to go along with their programs. They try to "sell us". Democracy; this majority says this; believe in this; do this, do that; the war on terror; we have to be scared... They are always trying to do things to "sell to us" to go along with them, and once we learn not to cooperate with them; then we win the game.
- That is the point, do not cooperate with them, and do not go along with the program anymore. Stop it. Join forces, and bring freedom back to this country. It is going to take people who believe in freedom; The Constitution and the Founding Fathers, Thomas Jefferson, to make this country whole again, because right now it is in the grip of the evil ones, and the only way to stop that is for good men to stand up.

- We have to stop being scared. We have to do what is necessary to take back what is ours. We have to stop these bankers, these elite, full of liars, congressmen full of liars. They are destroying our borders.
- So through these bankers, attempting to take over America, knowing that America was the freest nation on this earth, it was necessary for them to takeover America, take away gun rights, freedom to bear arms, and create a country where we become slaves, because once they take over America, the rest of the world becomes a lot easier for them. And so by creating 9/11, an event to terrify the American people that we are being 'attacked by terrorist', you create a world where there is an enemy that can **never** be pinpointed. You can never win the battle. It is 100 year war – a never ending war on terrorism. So you are always fighting this war, and through the war on terrorism, through 9/11 which is the first lie, then you create the war on terrorism which is the next lie, then you create the war in Iraq through weapons of mass destruction, which is the next lie –so you get one lie, to the next lie, to the next lie, -- now it is going to be Iran the next lie –and sending more troops and insurgents into Iraq.
- Restore America's Republic back to what it is supposed to be. Get the bankers out of our government. Get government to stop borrowing money from the banks. Government should make its own money; restore the Republic. Restore individual freedoms. That is what this country is about -and until we do that we are going to be slaves.
- You have to take away the creation of money away from the private bankers and you will solve 95% of your problems.
- Americans, mobilise, stand tall, stand together, tell the government you are "Mad as hell!" Do not cooperate with the government do not accept a National ID card. Do everything in your power to restore freedom and your individuality back to America. Stop being a country run by the institutions for the institutions. Let's go back to "We the people, by the people for the people", as opposed to, we the institutions, by the institution, for the institution. Stand up for your individual rights. Stand up for the God leaders that are in each and every one of us!

The Trans-humanist / Post Human Agenda

Transhumanism is a cultural and intellectual movement that believes we can, and should, improve the human condition through the use of advanced technologies. One of the core concepts in transhumanist thinking is life extension: through genetic engineering, nanotech, cloning, and other emerging technologies, eternal life may soon be possible. Likewise, transhumanists are interested in the ever-increasing number of technologies that can boost our physical, intellectual, and psychological capabilities beyond what humans are naturally capable of (thus the term *trans*human) (Anthony 2013). Transcranial direct current stimulation (tDCS), for example, which speeds up reaction times and learning speed by running a very weak electric current through your brain, (Anthony 2012) has already been used by the US military to train snipers. On the more extreme side, transhumanism deals with the concepts of mind uploading (to a computer), and what happens when we finally craft a computer with greater-than-human intelligence (the technological singularity) (See: “How to create a mind, or die trying”, Hewitt 2012) (Anthony 2013).

Moreover, put simply, “posthumanism” can be defined as that condition in which humans and intelligent technology are becoming increasingly intertwined (TheNanoAge 2015). For readers interested in learning more about the posthuman / transhuman agenda see BT Soul Catcher 2025 (BEAMS 2007); Avatar Project 2045 (2045 Initiative 2015; Borghino 2012) and Mind Clone Robot (Bloomberg Business 2015; RT 2015) which have all been disclosed as methods of transferring the human consciousness to a computer.

The Phases of Sleep and Rapid Eye Movement (R.E.M) Sleep

Sleepers pass through five stages of sleep: 1, 2, 3, 4, and REM (rapid eye movement) sleep. These stages progress cyclically from stage 1 through REM then begin again with stage 1. A complete sleep cycle takes an average 90 to 110 minutes (Sleepdex 2015). In other words, after falling asleep, it takes approximately 90-110 minutes to enter REM sleep.



Stages

Waking	REM Sleep	NREM Sleep			
Stage 0	Stage R	Light Sleep		Deep Sleep	
		Stage 1	Stage 2	Stage 3	Stage 4
Eyes open, responsive to external stimuli, can hold intelligible conversation	Brain waves similar to waking. Most vivid dreams happen in this stage. Body does not move.	Transition between waking and sleep. If awakened, person will claim was never asleep.	Main body of light sleep. Memory consolidation. Synaptic pruning.	Slow waves on EEG readings.	Slow waves on EEG readings.
16 to 18 hours per day	90 to 120 min/night	4 to 7 hours per night			

Image 1: Stages of sleep. Source: Sleepdex: (2015)

Any sufficiently advanced technology is indistinguishable from magic.
Arthur C. Clarke

REM Sleep

Most dreaming occurs during Stage Five, known as REM. REM sleep is characterized by eye movement, increased respiration rate, and increased brain activity. REM sleep is also referred to as paradoxical sleep because, while the brain and other body systems become more active, your muscles become more relaxed, or paralyzed. Dreaming occurs because of increased brain activity, but voluntary muscles become paralyzed. Voluntary muscles are those that you need to move by choice, for example, your arms and legs. Involuntary muscles are those that include your heart and gut. They move on their own (Sleepdex 2015; Walcutt 2013).

Rapid eye movement, or REM sleep, is when you typically dream. You may have images float by in earlier stages, particularly when you are going through Alpha or Theta (brain waves), but the actual dream state occurs in REM (Walcutt 2013).

This period of paralyzation is a built-in protective measure to keep you from harming yourself. When you are paralyzed, you can't leap out of bed and run. Do you ever feel like you can't escape during a dream? Well, the truth is, you can't. You can breathe, and your heart is working, but you really can't move (Walcutt 2013).

The reader is also advised to see the Horizon documentary "Why Do We Dream?" (BBC Horizon 2009). This video is available, on YouTube, and details sleep, the phases of sleep, REM sleep, the period of paralysation and more.

Current Advances in Technology

This is a section some readers may have difficulty with, because reading about these current technologies alone, one cannot help but feel that such technologies described below sound like the stuff of science fiction and fantasy -although they have been corroborated through public drip-feed disclosure (explained below). Nevertheless, I urge the reader to keep in mind Arthur C. Clarke's quote (above), as well as Phil Schneider's testimony regarding the advancements of military technology in comparison to the general public's technology (for every 12 months, military technology outstrips the technology the public is accustomed to by a rate of 44 years). Moreover, for the reader who finds difficulty understanding the technologies described below, seek the supporting articles / videos.

Memory Suppression Technologies

Memory suppression technologies are any scientifically advanced technologies which are used to suppress memory. Examples of how memories can be suppressed can be found by reading Winter's (2014) article which details how memories can be suppressed using light; and Greenberg's (2013) article which discusses memory suppression through gene / chemical modification.

Mind-Voice Technology

Mind-voice technology is an advanced technology which is capable of reading, listening, hearing or broadcasting your inner voice / thoughts. Examples of articles which discuss mind-voice technology are: Prigg (2014) details software which can read the inner voice; and New Scientist (2014) which also discusses a brain decoder which can eavesdrop on one's inner voice.

H.A.A.R.P. Technology

The High Frequency Active Auroral Research Program (HAARP) is a radio transmitting system that can bounce signals off the ionosphere (a region of the Earth's upper atmosphere 60km (37 miles) to 1000km (620 miles) altitude) and back to earth to probe deep into the earth or sea, its proponents say. The system could locate minerals or communicate with submarines. (Begich & Manning 1997; Sheen, Begich & Robbins 2005).

HAARP can also:

- Disrupt human mental processes.
- Knock out all global communications systems.
- Manipulate global weather.
- Change weather patterns over large areas.
- Interfere with wildlife migration patterns.
- Hurt ecosystems.
- Negatively affect your health, moods, and mental states.
- Unnaturally impact the Earth's upper atmosphere.

This illustration (below) shows the ionosphere's relationship to the Earth. The illustration appeared in the HAARP Environmental Impact Statement on page 10-125 of Volume II.



Image 2: The ionosphere's relationship to earth. Source: (Begich & Manning 1997)

The ionosphere protects the earth. HAARP (High frequency Active Auroral Research Program) is made to beam more than 1.7 gigawatts (billion watts) of radiated power into the ionosphere -the electrically charged layer above Earth‘s atmosphere. Put simply, the apparatus is a reversal of a radio telescope - just transmitting instead of receiving. It will boil the upper atmosphere. After disturbing the ionosphere, the radiations will bounce back onto the earth in the form of long waves which penetrate our bodies, the ground, and the oceans.

HAARP represents a technology which could lead to a new class of weapons that could change our world profoundly - an all-purpose military tool. If misused, the tool could mess up the weather. It could be used against humanity in a way that would change what people think, believe and feel. It could be used for good or evil, just as a harp can produce the music of Mozart or the melody of a death march.

H.A.A.R.P. and Weather Control

- “The theoretical implication [of Dr. Robert Helliwell and John Katsufrakis of Stanford University in 1974] suggested by their work is that global weather control can be attained by the injection of relatively small 'signals' into the Van Allen belts (radiation belts around Earth) - something like a super-transistor effect” said Frederic Jueneman.
- Yes. The weather can be controlled using HAARP technology.

- A series of weather disasters began in 1960, according to a CIA report mentioned in the editorial, but at the time climatologists couldn‘t look ahead and see that droughts, floods and abnormal temperatures would continue beyond that decade. As if natural disasters weren‘t bad enough, the CIA reported that national governments were already able to manipulate weather for military purposes [using HAARP technology].

As far back as 1958, the chief White House advisor on weather modification, Captain Howard T. Orville, said the U.S. Department of Defence (DoD) was studying ways to manipulate the charges of the earth and sky and so affect the weather by using an electronic beam to ionize or deionize the atmosphere over a given area. In 1966, Professor Gordon J. F. MacDonald, associate director of the Institute of Geophysics and Planetary Physics at the University of California, Los Angeles, was a member of the President‘s Science Advisory Committee, and later a member of the President's Council on Environmental Quality.

Gordon J. F. MacDonald published papers on the use of environmental control technologies for military purposes. MacDonald made a revealing comment: ―The key to geophysical warfare is the identification of environmental instabilities to which the addition of a small amount of energy would release vastly greater amounts of energy. MacDonald had a number of ideas for using the environment as a weapon system and he contributed to what was, at the time, the dream of a futurist. When he wrote his chapter, ―"How to Wreck the Environment" for the book "Unless Peace Comes" he was not kidding around.

In the text MacDonald describes the use of weather manipulation, climate modification, polar ice cap melting or destabilization, ozone depletion techniques, earthquake engineering, ocean wave control and brain wave manipulation utilizing the planet‘s energy fields. He also said that these types of weapons would be developed and, when used, would be virtually undetectable by their victims. He was not some wire haired fanatic when he made these observations in 1966 -he had the credentials of a world recognized scientist. What his futuristic concepts became, are the things which projects like HAARP are made of...

H.A.A.R.P. and Mind Control

- Radio frequency radiation, acting as a carrier for extremely low frequencies (ELF), can be used to wirelessly entrain (adjust) brain waves.
- We are talking about very, very low power requirements. The trick for influencing brain activity is in the combination of frequency, power level and wave form.
- As Dr. Patrick Flanagan, one of America's most gifted inventors noted in an interview, the HAARP project could be not only the biggest ionospheric heater in the world, but also the biggest brain-entrainment (brain adjustment) device ever conceived.
- According to HAARP records, when the device is built to full power it can send very low frequency (VLF) and extremely low frequency (ELF) waves using many wave forms at energy levels sufficient to affect the mental states of entire regional populations.

- The HAARP transmitting system could be used unintentionally or intentionally to alter mental functions.
- If HAARP is tuned to the right frequency, using just the right wave forms, mental disruption throughout a region could occur intentionally or as a side effect of the radio frequency transmissions [in other words: “mind control”].

RFID Technology

Radio Frequency Identification (RFID) microchips are microchips that can be directly imbedded into human flesh. This section discusses the dangers of RFID chips. See Rense (2001) for full review.

- RFID technology links the brains of people via implanted microchips to satellites controlled by ground-based super-computers.
- Today they are small enough to be inserted into the neck or back, and also intravenously (through a vein) in different parts of the body during surgical operations, with or without the consent of the subject. It is now almost impossible to detect or remove them.
- Implanted human beings can be followed anywhere.
- Today's microchips operate by means of low-frequency radio waves that target them. With the help of satellites, the implanted person can be tracked anywhere on the globe.

RFID Technology and the Medical Profession

- One reason the dangers of implantable microchip technology has remained a state secret is the widespread prestige of the psychiatric DIAGNOSTIC STATISTICAL MANUAL IV produced by the U.S. American Psychiatric Association (APA), and printed in 18 languages. Psychiatrists working for U.S. intelligence agencies no doubt participated in writing and revising this manual. This psychiatric "bible" covers up the secret development of Mind Control technologies by labelling some of their effects as symptoms of paranoid schizophrenia.
- The Psychiatric Diagnostic Statistical Manual (DSM) for mental disorders has been a brilliant cover up operation in 18 languages to hide the atrocities of military and intelligence agencies' actions towards their targets. THE MANUAL LISTS ALL MIND CONTROL ACTIONS AS SIGNS OF PARANOID SCHIZOPHRENIA.
- If a target is under surveillance with modern technology via TV, radio, telephone, loudspeakers, lasers, microwaves, poisoned with mind altering drugs via air-ducts, giving familiar smells which cause headache, nausea and so forth, if s/he claims her/his clothes are poisoned, her/his food or tap water as well --- all medical schools teach their students that the person is paranoid, ESPECIALLY if s/he believes intelligence agencies are behind it all.
- Never is the medical profession told that these are routine actions all over the world by intelligence agencies against their targets. Thus, victims of mind control are falsely considered mentally ill and get no help since they are not believed and their suffering is doubled by misinformed health professionals.

Further Implications of RFID Technology

- How many people realize what the implications of implantable chips actually mean? It means total loss of privacy and total outside control of the person's physical body functions, mental, emotional and thought processes, including the implanted person's subconscious and dreams! For the rest of his / her life!
- It sounds like science fiction but it is secret military and intelligence agencies' mind control technology, which has been experimented with for over half a century (since 1950s). Totally without the knowledge of the general public and even the general academic population.
- Supercomputers in Maryland, Israel and elsewhere with a speed of over 20 BILLION bits/sec can monitor millions of people simultaneously. In fact, the whole world population can be totally controlled by these secret brain-computer interactions, however unbelievable it sounds for the uninformed.
- Neuro-electromagnetic involuntary human experimentation has been going on with the so-called "vulnerable population" for over 50 years, in the name of "science" or "national security" contrary to all human rights. It happens today in the **USA, Japan, and Europe**. With few exceptions, the mass media suppresses all information about the entire topic.
- Only increased public awareness of the microchip implants, their frightful consequences to privacy by influencing of individuals' thoughts and actions, causing people to become biological robots with physical and emotional pain whenever the supercomputer technician so wishes, is enough reason to refuse to take the microchip into your body for whatever reason.
- It is the biggest threat to humanity and the most sinister plan to enslave the human race forever.

If you have a choice and want to remain a normal human being with privacy, **DO NOT** have your children implanted **NOR** yourself implanted with RFID microchip(s) (or any other type of implantable microchip). Otherwise your vision, hearing, sensing, thoughts, dreams and subconscious will be influenced by an outsider, who does not have your best interests in mind. For the rest of your life!

Mind Control: MK Ultra Technology

MK Ultra today has evolved from the 1950s variation of mind control (MK Ultra Compendium 1980), whereby drugs such as LSD, and interrogation were used as methods to weaken the mind of the individual to force confessions through mind control. Today, mind control is achieved through the implantable microchip (mentioned above; Rense 2001).

- The brain functions of an implanted person can then be remotely monitored by supercomputers and even altered through the changing of frequencies.
- Once implanted, the U.S. National Security Agency's (NSA) 20 billion bits / second supercomputers could now "see and hear" what you are experiencing with a remote monitoring system (RMS).

- Every thought, reaction, hearing and visual observation causes a certain neurological potential, spikes, and patterns in the brain and its electromagnetic fields, which can now be decoded into thoughts, pictures and voices. MK Ultra technology is therefore capable of Mental Video and Audio Projection, as well as Artificial Telepathy.
- The mass media have not reported that an implanted person's privacy vanishes for the rest of his or her life. S/he can be manipulated in many ways. Using different frequencies, the secret controller of MK Ultra technology can even change a person's emotional life. S/he can be made aggressive or lethargic. Sexuality can be artificially influenced. Thought signals and subconscious thinking can be read, dreams affected and even induced, all without the knowledge or consent of the implanted person by using MK ultra technology.
- Memory suppression technologies are used in conjunction with MK Ultra technology, which enables the programmer to control certain memories the victim remembers. The use of memory suppression technologies and MK Ultra technology allows the programmer to reinforce behaviour and elicit specific conditioned responses.
- Mind control techniques, such as MK Ultra, can be used for political purposes. The goal of mind controllers today is to induce the targeted persons or groups to act against his/her own convictions and best interests. Zombified individuals can even be programmed using MK Ultra technology, to murder and remember nothing of their crime afterward.
- The goal of mind control, using MK Ultra technology is to program an individual to carry out any task against their will and self-preservation instinct and to control the absolute behaviour and thought patterns of the individual. The purpose of mind control, using MK Ultra technology is to disrupt memory, discredit people through unusual behaviour, to make them insane or to commit suicide or murder.

See Mind-Computer (2012) which discusses how artificial telepathy is achieved. Artificial telepathy, also known as ‘brain to brain communication’, is also possible using MK Ultra technology. Furthermore, review: Jim Cristea (2009); Berkeley News (2011); UC Berkeley Campus Life (2011) CTForecaster (2013); nature video (2013) and Stromberg (2013). The above mentioned articles and videos describe, demonstrate, and corroborate how audio and video projection of the brain is achieved; how dreams can be recorded and projected digitally; how the brain can be scanned to reveal hidden information personal to an individual; and what a person’s underlying intentions are, by using brain scans. Moreover, the articles and videos mentioned above confirm the functionalities of MK Ultra technology.

Furthermore, when our brain functions are connected to supercomputers by means of RFID technology, MK Ultra technology and other implantable microchips, it will be too late for protest. This threat can be defeated only by educating the public, using available literature on biotelemetry (electronic equipment that receives signals from radio transmitters) and information exchanged at international congresses.

Human Cloning

There are currently five different types of clones, concealed from public knowledge. There are Mark 1 clones; Mark 2 Clones; Mark 3 Clones; and Mark 4 clones and reanimated clones. Moreover, there are two types of cloning techniques: duplication cloning and replication cloning.

Mark 1 clones are REM sleep driven clones. However, the technology used for Mark 1 clones causes many side effects and therefore Mark 1 REM sleep driven clones are no longer a preferred choice.

Mark 2 clones are also REM sleep driven clones. Mark 2 clones have fewer side effects than Mark 1 clones, and therefore Mark 2 clones are currently the preferred method for REM sleep driven clones.

Mark 3 clones are independent clones which operate on microchip containing the entire consciousness of an individual.

Mark 4 clones are also independent clones, operating on a microchip which contains the entire consciousness of an individual and is an advanced version of a Mark 3 clone.

These independent clones (Mark 3 and Mark 4) have a lifespan of 6 months to 12 months and require adjustments after this period to run efficiently once more. Without these adjustments, their functionality weakens.

To "reanimate" means "to restore to life; resuscitate; revive". Consequently, reanimated clones are clones which are genetically identical to that of a person who once lived.

Replication cloning is what the public is most familiar with. Replication cloning involves giving birth to a genetic identical of an original where the newborn starts life off as a baby and matures. The newborn is referred to as a clone.

However, duplication cloning is a current concealed advanced from of cloning, and it involves taking as little as two cells from an individual, adding a constant electrical charge to the cells until a complete human being is formed.

Duplication cloning is similar to the process of regenerative medicine as demonstrated by Dr. Stephen Badylak's video "How to grow a New Fingertip" (CBS 2008; Science Channel 2014) where Badylak states: 'A whole human can be grown within 9 months.' On average it takes 5 months to grow a duplicate clone of an original by means of advanced scientific and technological regenerative procedures.

Cloning Centre and Cloning Technology

A cloning centre is a place where clones are produced. Cloning technology are the advancements in medicine, science and technology used to produce duplicate and replicate copies of originals.

Drip Feed Disclosure and Evaluative Conditioning

Drip Feed Disclosure

Drip feed disclosure is the process of supplying information but in small amounts overtime. Drip feed disclosure is also the process of revealing information slowly overtime, possibly telling lies to conceal certain aspects of the truth until the source administering the drip feed disclosure has adequate time to let out the truth in a slow and controlled way, thereby delaying the betrayed partner (in this disclosure, the public) from having the "complete truth" for some time.

Drip feed disclosure is also a method to gauge public reaction used by governments, the media, multinational corporations and organisations as well as high ranking officials to "test" whether the general public is acceptant of the concealed information or not. When the public reacts favourably to the drip feed disclosure, more information is revealed and made public, and it appears to the unsuspecting observer that the people involved in making the disclosure are taking positive steps towards a favourable goal for all. However, when the public reacts adversely; information contradicting the drip feed disclosure is presented, and an expert is presented to the public who voices the concerns of the general public, and therefore it appears that the opinions of the public have been noted and research and development will not continue in the initial stated direction. Nevertheless, the truth remains concealed and research and development continues despite the aversions of the public.

Examples of drip feed disclosure involve articles such as mind uploading / downloading (BEAMS 2007), Mind Clone Robots (Bloomberg Business 2015; RT 2015), The 2045 Avatar Project (2045 Initiative 2015; Borghino 2012). I am here to tell you that I have been a spy for over 30 years and such technological accomplishments which are posted under trans-humanism / post-humanism genre have been realised many years ago and are **available** today. They are just concealed from the public.

Furthermore, Dolly the sheep was announced as the first publicly cloned mammal (Animal Research 1996), but how many readers can say they know that, four years later, a monkey (BBC News 2000), our closest primate, was cloned? This is publicly disclosed knowledge, but I suspect not many people know of a cloned monkey four years after Dolly. This is because there was such a worldwide adverse reaction to genetic cloning when Dolly was made public, that the disclosure of the cloned Rhesus monkey (BBC News 2000) was not made public knowledge on a grand scale.

Evaluative Conditioning

Evaluative conditioning is defined as a change in liking, which occurs due to an association with a positive or negative stimulus (see De Houwer et al., 2001). Simply put, this means that our preferences for brands, products, people and other things can be influenced and even modified by the presence of something we like or dislike strongly (Hale 2012).

In many settings, a neutral stimulus, called a "conditioned stimulus", often coincides with some desirable or undesirable object, called the unconditioned stimulus. An unknown brand, for example, might appear in a commercial that also depicts a happy child. Over time, stimuli that often coincide with desirable objects are perceived more favourably, whereas stimuli that often coincide with undesirable objects are perceived less favourably--called evaluative conditioning (De Houwer, Thomas, & Bauyens, 2001; Walter, Nagengast, & Trassilli, 2005; Moss 2009). An "unconditioned response" is a response to a neutral stimulus we have no / little control over. It is a natural automatic response.

In other words, our preferences for liking or disliking brands, products etc. (the neutral stimulus) can be influenced by embedding (implicitly placing) the brand etc. (neutral stimulus) with positive or negative associations. Overtime our conditioned response becomes one of conditioned favourable or negative response towards the brand, product etc. (neutral stimulus) when we are faced with the brand, product etc. at a future date. Our preferences have been guided overtime. Evaluative conditioning can change our preferences when carried out subliminally or implicitly; it does not have to be explicit.

In media; music; movies; and other forms of popular culture and entertainment, images and symbols (of stimuli which cause undesirable consequences) are embedded subliminally and implicitly and are paired with positive associations as a form of evaluative conditioning. This causes individuals who have no preconceived judgements of the stimulus to be guided to have positive associations with a stimulus which causes undesirable consequences.

In popular culture; media; advertisements; movies; music and other forms of entertainment, evaluative conditioning is used as a method of hinting (that something is wrong); showing off of power (i.e. nothing can be done to stop the negative stimulus) and as a form of gloating (i.e. we've pulled off the negative stimulus / we are pulling it off). In over the 30 years I have been a spy, I have witnessed methods of evaluative conditioning used to hint, show off power, and gloat more often than not, and evaluative conditioning is not used just to guide social order.

The fortunate aspect is that once a person learns that his / her preferences are being guided by methods of evaluative conditioning, in order to influence the person to have positive associations with negative stimuli (or feel powerless towards the negative stimuli); and that the stimulus (brand / product) does in fact cause undesirable consequences –then the 'spell' is broken. The person can now choose how he or she responds to the brand etc. Usually, once all is known: a negative stimulus is associated with negative associations; despite it being portrayed as positive through evaluative conditioning.

Consciousness Transfer

Consciousness is defined as "the state of being aware of and responsive to one's surroundings; a person's awareness or perception of something" (Dictionary Reference 2015). Consciousness can also be described as: individual awareness of a person's unique thoughts, memories, feelings, sensations and environment (Cherry 2015).

John Locke (1632-1704) was an English philosopher, Oxford academic and medical researcher who argues that it is sameness of consciousness rather than sameness of substance that constitutes personal identity. Consequently, if the psychological life is transferred from the body of a prince to the body of a cobbler (shoe mender), Locke argues, the resulting person will be the prince and not the cobbler. He would be responsible for the prince's actions and not the cobbler's; those who were close to the prince could continue their relationships with him but those who had relationships with the cobbler could not, and so on (Schechtman 2012, p.334). Moreover, basic Lockean intuition has proved to be that "consciousness transfer" can be thought of as the feat in which the person moves from one body into another (Schechtman 2012, p.334).

Consciousness transfer can also be thought of as the process of transferring or copying the mental content (including long-term memory and "self") from a particular brain and copying it to a computational device; artificial body or avatar body such as that of a robot or clone version of the original. The computation device, robot or the clone, will then respond essentially the same way as the original brain (as suggested by Lockean theory on consciousness transfer) and therefore the computational device, robot or clone experiences having a conscious mind and essentially the behaviour of the computational device, robot or clone, can be attributed as belonging to that of the original.

It is **OF MONUMENTAL IMPORTANCE** that the reader understands the above statement regarding consciousness transfer is a method of **CURRENT** concealed advances in technology and not a concept relegated only to the genre of science fiction. At the very least the reader should be **open** to the possibility of consciousness transfer and the implications of consciousness transfer, in order to truly begin to understand the extent to which current concealed advances in technology are used to commit monstrous crimes.

I understand the above sounds unsettling, but there are also many wonderful concealed advances in technology (detailed in the disclosure section). The marvels in technological feats and human accomplishment will be released for the benefit of mankind once the world learns about the monstrous crimes which are committed against the them, and the earth, through the use of highly concealed technological advances and the good people of the world band together to put an end to the tyranny around us.

Now is also a good time to remind the reader that if military technology advances by a rate of 44 years for every 12 months which passes, then since 1945 military technology has advanced by a rate of more than 3000 years compared to the technology the public is currently accustomed to (44 times 70 = 3080). Now ask yourself honestly, in 3000 years from now (the year is 5015) don't you think humans will have been capable of developing a method which allows them to transfer their consciousness from one body to the next and more?

I am here to tell you that I have been a spy for over 30 years and that from the intelligence I have gathered over the years it has been illustrated to me countless times that consciousness transfer is indeed fact and currently exists. Consciousness transfer has been achieved since 1945, although this accomplishment in human advancement (and more) is concealed from public knowledge. Moreover, consciousness transfer is a highly advanced form of concealed technology used by high ranking members of society to commit unspeakable crimes against the public.

Furthermore, for the reader who wishes to understand how consciousness transfer is possible, see Petkova and Ehrsson (2008) and Ehrsson (2013). In the video Professor Henrik Ehrsson (2013) demonstrates:

1) Consciousness transfer from one body to the next (owning another body other than ones original)
2) Physiological evidence for owning the new body. In other words when consciousness has been transferred and the person perceives the new body as that of his or her own; when the new body is threatened as the mannequin (new body) was in the experiment, individuals still perceived the mannequin body as that of their own and became frightened (displayed biological and physiological responses).
3) Visual perception and stimulation causes us to perceive ownership of a new body.
4) The new body we inhabit must be similar to that of our own (it does not matter whether the new body is smaller or larger than our original so long as the measurements are proportional) for consciousness transfer to occur.

5) That it is possible for consciousness to be transferred to another person's body and have (or perceive) ownership of other person's body while being localised in your own body. In other words, dual consciousness is possible.

Petkova and Ehrsson's (2008) and Ehrsson's (2013) research gives one of the clearest publicly disclosed explanations of consciousness transfer and I urge the reader to watch the video in order to better understand my disclosure. One of the main findings from his research is that perception is not rigid; and perception does shape reality. Sight and synchronous (going on at the same time) stimulation can, and does alter the brains perception of reality. Sight and synchronous stimulation activates certain parts of the brain (the sensory parts of the brain and the motor (movement) parts of the brain). The match between the two (sight and stimulation) "convinces" the brain that 'hey, I'm no longer in this body; I'm in that one or that I have a third arm (although it is a false limp) etc. Accordingly, "perception is reality".

Disclosure: Save the Victims through your Diligence

I've done my best to preface this information as logically, sequentially and methodologically for the reader as possible. I have stated what the law is on 'whistle blowing'; I have given references and definitions where appropriate and I have provided many sources in order for the reader to research, corroborate, and better understand my disclosure, so that he or she becomes compelled to help me and victims like me, defeat tyranny and save the future of mankind; therefore if there are any areas of my disclosure which still appears suspect –and I understand, after all my efforts –things may still not appear clear to some readers because we are dealing with highly advanced concealed technologies which are not available in the world the general public lives in; and therefore it is difficult to fathom and furthermore conceive that men can be so evil to their fellow humans through the use of advances in science and technology. Nevertheless, I promise you, I have no reason to lie, I am victimised daily because of these technologies, and therefore my only option is to tell the truth, and nothing but the truth so that the people of the world can put an end to this grave injustice.

For the reader who still finds it difficult to accept my disclosure after first read, I want you to do two things:

1) **Give me the benefit of the doubt.** I am asking you to do this because as I stated earlier, one of the hardest things to do as a victim of abuse is to come forward about the abuse you have suffered. It is even more heartbreaking when nobody believes you. Consider all the victims of paedophiles you have heard about on the news. I cannot speak for their individual cases but I can attest to the fact it affects my mental psyche beyond comprehension; there is nothing worse than being ignored and that nobody believes you. So on that premise, please give me the benefit of the doubt, because I'm sure the majority of good human beings out there will feel worse when it is proven that I am a victim of severe abuse and you ignored me, when you could have done everything in your power to save me.

2) **Set out on a genuine quest to debunk my disclosure.** If my disclosure appears suspect to you to begin with, then set out on a genuine and investigative quest to debunk my disclosure because, if my disclosure initially appears circumspect to believe, then I should be proven false within minutes of your research of my disclosure, because even professionals make mistakes. There will be something about the disclosure which will just not 'add up'. However, when a person is telling the truth, then it is very difficult to debunk that person.
I promise you, it will be worth your time to know the real truth about the world, simply because the truth is liberating.

I would also like to remind you that the truth about the world has been hidden from the public for many decades, therefore when you do hear the truth of course it is going to sound absurd to begin with; but keep an open mind and pursue till you know what truth is; because "to "know" is to understand with certainty".

Words of Inspiration: Personalized from a Theoretical Physicist –Thomas Campbell

The following gives an introduction to many aspects which occur in this world behind closed doors or in plain sight depending on how familiar the reader is with the topics. Evidently, a lot of what is written predominantly affects the people of the world and it is time the people of the world stood up and reclaimed their world. I cannot stress this importance enough! The disclosure is also a basis which explains many of the anomalies which exist in the world today. I apologise in advance if the disclosure is too shocking to be believable (initially) and it shakes the foundations of your belief systems... but as I've said, rather than lash out at the information, you must question your own belief system... and probe into the mechanisms which have influenced you to adopt your current belief system... only then does the shock subside... and you can move forward with an open mind through investigation, which should lead you to either corroborate or debunk the disclosure. Keep in your heart: scepticism, optimism and open mindedness (Campbell 2008). Scepticism keeps you from believing fallacies. It keeps you from falling into that which you have not yet proven for yourself. Scepticism is a requirement for breakthroughs. Optimism gives you the ability to give merit to that which you have not yet proven for yourself and Open Mindedness gives you the ability to "see" that which has not yet been proven.

The Science of Hidden Consciousness

Furthermore, "Consciousness Science Kept Hidden" (YesEthan 2013) illustrates:

- "The heart is an electrical organ. It produces by far the strongest form of bio electricity in our body; up to 40-60 times stronger than the second most powerful source –which is the brain. This electrical energy travels through every single cell in our body and in a sense, binds the cells together. The bio-electricity field is strong enough that it can even be detected outside of the body; out into space; beyond the skin. It is very measurable electromagnetic energy, much like radio waves. What we found is that the heart produces an electromagnetic field that surrounds our entire body 360 degrees; and it can be detected about 3-4 feet with megatron meters outside of the body. Researchers at the medical facility in Kansas –say they have detected it 10-12 feet. So regardless of how far it goes, what is interesting is that we produce this electromagnetic field which can be detected; it can be measured, with sensitive mainstream medical equipment." -Howard Martin (co Author) "The Heart Math Solution""
- Scientific studies have shown: that the heart is not only the most powerful centre in the body, it is the most intelligent and has the ability to receive precognition (knowledge of a future event or situation, especially outside one's normal sense of perception). If we can create coherence with our heart and mind centre we can access our intuition more frequently.

When you read my disclosure, remember that it is the heart and NOT the brain which is the most powerful centre in the body; the heart is the most intelligent; it has the ability to receive precognition and intuition about a future event, **before it actually occurs**; therefore if you find that your heart is in resonance with the themes I disclose; do not fight it with the ego of the mind; when our egos get in the way it overrides our heart's intuition; your heart is capable of discerning the truth of an event before your brain becomes conscious of it; by all means listen to your heart, and allow your brain to naturally develop its intuition. It will be the coherence between your heart first, and then your mind centre which will allow you to access your intuition.

Make an effort and reach your own conclusions to the point where you feel comfort in the fact that you **KNOW** the information contained in this disclosure is indeed factual. This will be the point you will have become empowered with golden truth and compelled to fulfil your duty as a human being and also spread the truth far and wide. Yes, we are all living in very interesting times.

Disclosure: Donald Marshall's Message to the World

My name is Donald Marshall. I have been cloned by a large secretive cult know as "The Freemasons" and "The Vril Society" and "Scientologist" together called the Illuminati. For readers unfamiliar with The Illuminati see "The New World Order" (1990) by A. Ralph Epperson and Appendix C in this document; an introductory guide to the Illuminati and their agenda for the world is presented.

Furthermore, I have to tell you that human cloning has been done since 1945. Now is also a very good time to recall Phil Schneider's comment (Schneider was a Geologist and Engineer who worked on black projects and Deep Underground Military Bases (DUMBs)): "That for every 12 months which passes, military technology advances by a rate of 44 years compared to the technology the public is currently accustomed to" (Schneider 1995; 1996; Open Minds 2011). George Green (a former Financier affiliated with U.S. Presidential candidates) also attests to the fact that humans have been cloned since 1938 (Green 2008a; 2008b). Therefore if we take 1945 as a base year, then military technology or hidden technology has advanced by the rate equivalent to 3080 years than the technology the general public is currently accustomed to (2015 – 1945 = 70 years; 70 multiplied by 44 = 3080). So yes, humans have been cloned since 1945 and continue to be cloned today and that current hidden technology in the year 2015 is as much as 3000 years ahead of the technology the public is currently accustomed to. I'll repeat myself because it is **very important** the reader understands the above statement, even if, the rest of the disclosure is hard to fathom after first read. The two **most important** things to keep in mind are:
1) Humans have been cloned for over 70 years (since 1945);
2) **Present** hidden technology is more advanced -as much as 3080 years more advanced- than what the public is currently accustomed to and technology continues to advance at an incredible rate.

The Two Types of Cloning Techniques

Now there are two different types of cloning techniques, there is replication cloning and duplication cloning. Replication cloning is the type of cloning the public has generally heard of. Replication cloning involves taking the nucleus (the DNA) out of a donor egg, and replacing it with new DNA from the person to be cloned. After a few days the resulting embryo can be implanted for pregnancy. The newborn starts life off as a genetic copy of an original.

Duplication cloning, on the other hand, is the second hidden method and type of cloning where the DNA from the person is grown in a big thick tank full of (salty) water. It involves a method of regenerative technology where the cells are agitated and agitated and over the course of 5 months, a fully formed duplicate clone body of an original is developed. The Illuminati used to have to use a tissue sample from the original or the cells from women's pap smears because this contained rich cells to make duplicate clones; they also used children's foreskins which were discarded at the hospital that got removed. That is what happened to me. I had my foreskin removed at age 4 –and by age 5 the Illuminati grew duplicate clones of me. Now the Illuminati say they have upgraded the technology since 2000 and now all they need is blood from the original. They then agitate the blood cells over and over again through regenerative technology, until a fully formed duplicate clone body of an original is produced. For readers who are unfamiliar with regenerative procedures, see Dr Stephen Badylak's video on "How to grow a new fingertip" (Science Channel 2014) and Carmichael (2013) which discuses how scientists cloned a mouse from a blood sample (this is another example of drip-feed disclosure). Regenerative science and medicine (CBS 2008) does work; I've seen it many times.

The Different Grades of Clones: "Mark 1" to "Mark 4" Clones

There are a few different grades of clones that I know of. There are: "Mark 1" to "Mark 4" clones. Mark 1 clones were available at the end of World War II (1945). Mark 1 clones were rapid eye movement (REM) driven clones but they were primitive grades of cloning with lots of side effects caused to the original. Mark 1, REM driven clones were called "Organic Robotoids", even though there are no robotic parts to the clone at all. See Dr Peter Beter's discussion on "Organic Robotoids" (Beter 2011).

Donald Marshall's Dilemma with "Mark 2" Sleep Driven REM Clones

The problem I am having is with Mark 2 REM driven clones. "Mark 2" is a rapid eye movement (REM) driven clone. In other words, Mark 2 clones are sleep driven clones. REM sleep is the fifth stage of sleep (Sleepdex 2015). The first REM cycle usually happens 90 minutes to 110 minutes **after** we fall asleep (Sleepdex 2015). What that means is: **currently,** this is the Illuminati's main form of communication. They do not call people on the phone; they do not meet at the Bohemian Grove anymore (they only meet there once a year for traditional purposes). Since they discovered the science of sleep driven cloning, they meet at the cloning centre **WHEN THEY GO TO SLEEP** (The cloning centre is a physical location, located 5 / 6 hours radius from the Robert Pickton Farm (Port Coquitlam, British Columbia, Canada) at a nature reserve).

Consciousness Transfer Happens When the Original Reaches REM Sleep

The Illuminati can transfer the consciousness of an original once the person reaches REM sleep if there is a duplicate clone of the original at the cloning centre, once the person goes to sleep (90 minutes to 110 minutes after falling asleep). So what happens is that the consciousness of the original is transferred to the duplicated clone body (the duplicated clone body is grown within 5 months by regenerative technology) once the original reaches REM sleep. The original's consciousness is transferred from the original's body, although the original's body is still in their bed, asleep at home; to a duplicated REM driven clone body at the cloning centre and the original 'wakes up' as a cloned version of himself / herself at the cloning centre. It is a great marvel of science and one man's greatest achievements, but it is kept hidden and used for sinister purposes which I discuss below. I must address the readers at this point who are lost at the thought of duplication cloning, and consciousness transfer.

For readers who may have difficulty understanding the process of duplication cloning, see the video which features Dr Stephen Badylak (CBS 2008; Science Channel 2014). Badylak describes and illustrates how a new fingertip can be grown within 4 weeks, by the process of regenerative technology. Duplication cloning works a similar way; involving regenerative technology whereby the cells are agitated and agitated, and over the course of 5 months a fully formed duplicate clone body of an original is grown. Moreover, readers should also view the Horizon documentary "Why Do We Dream?" (2009); the documentary clearly explains the phases of sleep; particularly REM sleep. The documentary also clearly explains that during REM phase sleep the whole body shuts down, and it is only the brain which is active. The fact that the brain is still active, although the body is inactive, is a perfect opportunity for consciousness transfer; and this is usually the moment the Illuminati transfer the consciousness of a person who is asleep, to a cloned version of himself / herself. The reader should also explore Ehrsson's (2013) lecture on consciousness transfer. In the video, Ehrsson (2013) clearly explains how through the first person visual perspective (seeing through the eyes), and through synchronous (occurring at the same time) stimulation of a body part, individuals can perceive and see the world from another body different from their original. In other words, so long as people can see through the eyes, and the body is stimulated, the match between the visual perspective and feeling body sensations allows the individual to see and perceive the world through another body different from their original. The consciousness has been transferred to another body.

Ehrsson (2013) also demonstrates that consciousness is linked. Once consciousness is transferred (from the original's body to the new body), even though the new body is not the persons original body; when the new body is attacked, because the person perceives the world through the new body, everything feels "very real". When the new body (for which the person's consciousness has been transferred to) is attacked, the original still perceives the threat as "real", and therefore the person displays a biological and physiological fear response in their original body; the heart rate increases, as does respiration (breathing) rate, as well as anxiety.

Donald Marshall is an Original as he sits at Home Typing this Disclosure

This is how advanced technology is today. This is also exactly what happens to me. **I am an original as I sit at home here typing this disclosure,** but when I enter REM sleep, my entire original body shuts down, and only my brain is active. The Illuminati have linked my consciousness to a REM driven duplicate clone body of me. Therefore, as soon as I enter REM sleep, they are alerted to the fact that I have entered stage five of the sleep cycle, and in REM sleep, because they have a green and red light above duplicate clones at the cloning centre. The red light indicates that the original is awake, and the green light lets them know that original has entered REM phase sleep and it is time to transfer their consciousness to a duplicate clone version. They cannot transfer the consciousness of an original before REM phase or when the original is awake. When they try and transfer consciousness before an original is in REM phase it makes the original have intense headaches. Setting an alarm every 90 minutes to wake up and then go back to sleep also does not work in terms of avoiding REM sleep and having your consciousness transferred, because the body requires REM sleep, and therefore you become very tired, quickly, if you do not get REM sleep. If you stay awake for four days without REM sleep you begin to hallucinate; after seven days without REM sleep you will die.

When Donald Marshall's REM Driven Cloned Experiences Began

This whole sordid episode began when I was 5 years old, after going to the doctors to get my foreskin removed, at age 4. The tissues from my discarded foreskin were used to grow multiple duplicate clones of me. Within months, I was having my consciousness transferred to a REM driven, 5 year old clone version of me every time I entered REM sleep. The reason the Illuminati did this was because they wanted to use me as what they term "a diddle kid" – in other words they wanted to have sex with an REM driven, 5 year old, duplicate clone version of me. This is what they do. They clone people. They make duplicate clone bodies of people to victimise in terrible ways, and they clone children for men with undeveloped penises to have sex with.

However, I could never remember any of these REM driven clone experiences when I woke up for 25 years; because another aspect of REM driven cloning is that the Illuminati have the advantage of being able to suppress the experiences of people who have their consciousness transferred to their REM driven duplicate clone versions through advanced memory suppression technologies. For the reader who wishes to understand how memory suppression works see Winter (2014). Memories are stored and retrieved from different parts of the brain. Interactions between the cerebral cortex (the outer layer of the brain) and hippocampus need to work together in order to bring the memories out of mental storage to be re-experienced by the mind (Winter 2014). Therefore all that has to be done is for them to turn off the nerve cells which communicate with the cerebral cortex and hippocampus for the evening which you went to sleep and had your consciousness transferred to a REM driven duplicate clone version of you, and you will not remember anything. The technology is so advanced; they can, and do suppress memories at a push of a button. Therefore, the victim wakes up the next morning and will not remember a single REM driven duplicate clone experience. All that they will be aware of is that they did not have a dream the previous night.

This is what happened to me for over 25 years. I wasn't allowed to remember these REM driven duplicate clone experiences until I turned 30. My memories were suppressed for 25 years. I would wake up many days, after a night's sleep, thinking 'I didn't have a dream last night'; or I would wake up the next morning and I would be sick, although I went to sleep the previous night feeling completely healthy. Throughout the years, I thought I had terminal illness; because whenever I went to see a doctor, the diagnosis would always come back that 'there was nothing wrong with me'.

However, over the course of 25 years when I was memory suppressed, and not allowed to remember my REM sleep driven clone experiences, the Illuminati were using me to produce songs, lots and lots of songs, and whenever I could not produce a song, or did not want to, they would stab my REM driven clone body; sodomize my REM driven clone body; chain me to a crucifix and burn my REM driven clone and torture me for all kinds different reasons; and even when I was compliant and did what they told me to, I was attacked, simply because some members of the Illuminati wanted to know what it feels like to stab someone. Now because consciousness is linked (Ehrsson 2013), all these REM clone torture experiences affected me in my original body, and I have a weak heart today because of it, at the age of 39. The memories of my REM clone driven experiences also had to be released to me slowly (see Alford (2014) and FW: Thinking (2014) –for an example of how memories can be wiped and restored) over the course of many months because I had been through so much horror and torture that if the memories was released all at once, I would have had a heart attack in my real body and died.

This is one of the main reasons the Illuminati currently use REM sleep driven cloning (besides sex and torture): to plagiarise talented people under duress. There are many people including me who have been, and are plagiarised on a daily basis. Their consciousness is transferred to their REM driven clone alternates, and night after night and under duress they are forced to reveal their money making ideas or face torture or clone death; clone death after clone death. That is what the movie *Inception* (2010) is about: REM sleep driven cloning, and stealing ideas from the minds of unsuspecting individuals. The Illuminati actually made the film *Inception* (2010) as well as *The Island* (2005), *Avatar* (2009) and *The 6th Day* (2000); the films mentioned above contain references of cloning and REM driven cloning to show off the Illuminati's 'power' and throw in the world's face and laugh.

The Science of REM Driven Cloning Began in 1945

I am one of the few people fortunate, or unfortunate depending on how you look at it, who remembers all of my REM driven cloning experiences because these memories were released to me at the age of 30. I remember many people who have attended and still attend the cloning centre which they bring me to over the course of 34 years. I am currently 39 years old and was brought there since the age of 5. The science of REM sleep driven cloning was first discovered in 1945, and at first it was just a political thing which leaders of the world did. Through the science of REM sleep driven cloning, political figures, heads of state and royalty met each other as REM driven clones versions of their selves when they went to sleep and discussed worldly affairs in complete secret with each other. They also did whatever they wanted with each other as REM driven clones, which they could not do in their original bodies such as sex, fighting each other to the death, jumping off cliffs as their REM driven clones, and just about anything you can think of when one has the ability of pseudo-immortality as a sleep driven clone version of themselves hidden from the guise of the world and general public.

Well they soon got bored of each other very quickly, and started to make REM driven duplicate clones of movie stars, musicians, celebrities and public figures from all walks of life to hang with as REM driven clones and now they all get together for a disgusting time as REM driven clones when they go to sleep. Most of the G20 political leaders meet at the cloning centre as REM driven clones when they go to sleep to discuss worldly matters and watch gruesome things done to innocent and unsuspecting civilians, who are also REM sleep driven clones at the cloning centre, but civilians have their memories suppressed. This is what the films *Hostel* (2006); *Hostel: Part II* (2007); and *Hostel: Part III* (2011) (Illuminati made films) -are about: -rich people paying to torture and kill innocent people at a secluded location for sport; just that at the cloning centre, the Illuminati members torture and kill REM driven clones of innocent people.

Therefore, depending on what was done to your REM driven clone, you could wake up the next day with a very intense headache in your **original body**, if your REM clone was repeatedly punched in the head; an upset stomach in your **original body** if your internal organs were tortured; achy limbs; and worst of all, feel sick all over; although the previous evening you went to sleep feeling healthy. Remember consciousness is linked (Ehrsson 2013), therefore whatever happens to your REM driven clone will affect you in your original body. Even when they suppress your memory; the previous night's experiences still affects you in your original body. You wake up with the knowledge that you did not dream the previous evening when you went to sleep, and with certain illnesses depending on what was done to your REM driven clone.

Help Donald Marshall STOP REM Driven Cloning NOW!

Everything I discuss in this disclosure is firsthand witness accounts. I have seen and experienced horror spectacles done to innocent civilians and to me. For the sake of humanity and the innocent children brought to the cloning centres all over the world; I must tell the whole world about this and the good people of this world **MUST HELP ME TO BRING THIS TO A STOP.** My sense of duty, moral correctness, and conscience cannot allow me to stay silent about this evil. REM sleep driven cloning, and the torture of innocent civilians as REM driven clones; having REM driven clone sex with beautiful, innocent unsuspecting civilians of the world; the paedophilia of children through the process of REM driven cloning; REM driven sex slavery; the plagiarism of talented individuals through the process of REM driven cloning; and REM driven idea slavery, whereby talented individuals must produce new ideas and concepts daily (or whenever they sleep) or be stabbed or tortured in their sleep as REM clones –is the most vicious and pernicious form of tyranny ever to occur against humanity and **IT MUST BE STOPPED NOW!**

Do Not Panic, Riot, or Cause Chaos. This is Very Important.

Now I must preface this carefully, because members of the Illuminati have told me that I have to put this in an eloquent fashion, in a way which does not make people panic because people finding out about REM driven cloning, and the extent of the evil it has been used for, and continues to be used for; it could cause loss of social order, riots and anarchy in the streets. Moreover, I too **DO NOT** want riots and anarchy in the streets, despite the fact that I am vehemently angry considering the extent to which they plagiarised my talents over the years. If you are a good person reading this, and you want to help and you want social order restored for the benefit of mankind, promise yourself; me; all the innocent children they have affected through REM driven cloning, and the children of the future that you will **NOT** riot, and destroy a world for children who are going to inherit the world. **This is very important**. Remember the Illuminati have highly advanced technologies (kept hidden and secret), including weaponry, and they are just waiting for any excuse to use it on the populace. In all revolutions, the populace always win, and I want this disclosure and the end of REM driven sleep cloning to go smoothly. I want the good people of the world to keep spreading this information, keep spreading this disclosure all over social media, tell your close friends, your family, and as many people on social media platforms as you can. The internet, and radio shows with small audiences are the only forms of communication the Illuminati do not control. They own all forms of television networks, even including the Aboriginal People's Television Network (APTN), and therefore a message as important as this will never reach the average man or woman through television because it does not serve their agenda.

Spread this Disclosure Document until it reaches the Armed Forces

I want this message to reach the armed forces, because currently people in the armed forces are following orders, yet they do not know how corrupt their governments and people in high profile places are. They are unknowingly defending these corrupt people. People in the armed forces will **NOT** defend these corrupt people nor will they harm civilians when they realise that these corrupt people have been growing duplicate clone bodies of civilians, transferring civilians consciousness to their duplicate clone versions when the victim reaches REM sleep, and torturing civilians in their sleep; having sex with under-aged REM driven cloned children; having sex with innocent and unsuspecting adults as REM driven sleep clones, against their will; torturing REM driven clones for sport; and for money-making ideas to benefit their own pockets while they make innocent civilians sick and have side effects in their original bodies from REM sleep driven cloning technology. No. The armed forces will not accept that. Therefore keep spreading and sharing this information for everyone to see so that it reaches personnel in the armed forces **ASAP!** I want the armed forces to overthrow these corrupt people. The Illuminati think they are very sly and untouchable because together they hold most of the wealth in the world. We must show them that they are not untouchable. Please do all you can, to share and spread this message. It is the most important message to ever reach the internet because it affects all our liberties.

I must also address the readers who may feel afraid in spreading my message because they may want to do the right thing, but they are terrified the Illuminati may degrade or end their lives. As unbelievable as the next thing I am going to share sounds, it is a belief system which shapes the reality of the Illuminati and therefore they themselves are afraid to do anything which may degrade their lives or 'eternal soul'.

They believe that they are the 'fornicators' mentioned in The Bible, and if they were to degrade or harm the lives of anyone aiding me, they would suffer the wrath of God when they die. Notice I said **when they die**, but so long as they are still alive they can do all the evil they like, with little consequence, as they do in their REM driven clone versions at the cloning centre; worshipping Lucifer and doing all sorts of ungodly things. They even say God does not exist, only science and technology; yet they are afraid of dying. Very afraid of dying; because they believe they'll meet God's judgement. I'm just relaying what they have told me. They are weird like that. They also follow Hopi Indian Prophecy, Mayan Prophecy and Nostradamus Prophecy. They mix and match those three prophecies and come up with their own religion of what may or may not happen in the future.

Donald Marshall is NOT "The New Age Saviour". Nobody wants to be a 'saviour'

Furthermore, **THEY** believe I am a new age saviour for the end times; that I was going to save the world from something, according to the Nostradamus prophecy (quatrains); the Illuminati consider Nostradamus the greatest prophet ever to walk the earth. They are in awe of him.

I **DO NOT** endorse their claims. I just want REM driven cloning to stop and these people face punishments for their crimes against humanity. I really do not endorse such claims, but if it saves my life and yours, so be it. In reality and practicality, nobody wants to be 'the saviour'; not with such tyranny and pernicious evil such as this. We'd rather all just be living normal lives without the knowledge and practice of REM driven sleep cloning which is used for torture, clone death spectacles and sex with children. My friends on Facebook do not want to be heroes or 'saviours' either; nobody really does, but we do it out of a sense of duty, moral correctness and our conscience would never rest knowing the true extent of evil in this world, and doing nothing to end it. So all that saviour and Nostradamus prophecy talk, it is just the Illuminati; they like to quote prophecies, and make them come true to make themselves feel special.

Like I said, they are weird. I'm just relaying what they say, and I **do not** endorse the new age saviour claims. I'm just a normal guy, who was unfortunate to be cloned when he had his foreskin removed at age 4. This could have happened to anyone. Thankfully I had a very active imagination at the age of 5 and with the use of the technologies such as Mind-voice technology (that is what the Illuminati call it) it allowed me to make songs to keep the perverts off me. Mind-voice technology is just a technology which can tune into the inner voice in your head (See articles by Prigg (2014) and New Scientist (2014) –which discuss how scientist can listen to your inner voice; –it is similar to how Mind-voice technology works). Therefore, when you hear the sound of a guitar; the sound of drums; or any instrument for that matter; after hearing the sound, when you imagine the sound you heard, your REM driven clone can replicate this sound with Mind-voice technology **exactly**; and I used Mind-voice technology to make many, many songs over the years. As I've said, and I'll say it again: technology today is very advanced.

How the Nostradamus Prophecies shapes the lives of the Illuminati

Also another reason they have not killed me is because the Illuminati said "If they do, everyone is going to know I am telling the truth", -which I am with my right hand to God and I cannot lie about this stuff; the things I have seen are too sinister and diabolical. It would make me as bad as them if I did. Furthermore, because they follow the Nostradamus prophecies religiously, they have told me that they believe anyone helping me is considered part of "The Army of Light" and again, to hurt or degrade anyone helping me, considered part of The Army of Light would incur the wrath of God; and that to hurt anyone considered part of The Army of Light will degrade their lives; they will suffer misfortune and entire ruin as will their eternal soul. These are just some of the interpretations of the Nostradamus quatrains they have relayed to me. These people are beyond crazy, zealot and religious fanatics. Nevertheless, the main point to remember by all this is that **you are safe**, and **they cannot hurt you**, **they are scared to hurt you**, as well as kill me because prophecies have shaped their lives and the lives of their ancestors for hundreds of years.

Furthermore, and practically, I have told too many people that this is the extent, to which technology has developed in our current day, and it is kept secret and hidden from the public for nefarious purposes and this is what the Illuminati do: REM sleep driven cloning. I have been spreading this information **since 2011** and not one of these high profile people, government officials or celebrity figures has issued a (public) statement against me or taken me to court over libel charges because I'm telling the truth; and their statements would not hold in court.

I have also told over a million Arabs; I have appeared on radio interviews with Vinny Eastwood (Vincent Eastwood 2013); Jeanice Barcelo (Jeanice Barcelo 2013); and Lisa Phillips on the Cry Freedom Radio show (Astral 7ight 2013a – 2013h). I have reached audiences as many as 280,000 views on the Vinny Eastwood Show (Vincent Eastwood 2013) alone. However, I must stress that YouTube reduces the view count of my interviews every so often in order to suppress the truth so that my interviews do not get featured on their platform. Nevertheless, there is safety in numbers and rest assured there are new people waking up to the disclosure of REM driven sleep cloning every day; and therefore you can share and spread this information **without any worry** about facing reprisals from the Illuminati, even if you do not believe that it is in fact their beliefs in Nostradamus prophecies which is saving you and I from the Illuminati.

HIV/AIDS has been cured; so have many forms of cancer

Now is also a good time to share with the reader that this situation is not all 'doom and gloom.' In their quest to perfect technologies, science and medicine, the Illuminati discovered the cure for HIV/AIDS; cancer (except pancreatic cancer); Alzheimer's; Dementia and many more debilitating diseases which humanity suffers with. They relayed the fact that they found the cure for HIV/AIDS by stimulating the cells in an oxygenated rich environment because diseases/viruses cannot thrive in an oxygenated rich environment (in layman's terms). Magic Johnson was cured from AIDS this way and they use him as a spokesperson to sell the retrovirus pills which they know is not as effective. However, the greed these people have, knows no bounds, and because they receive too many donations for HIV/AIDS as well as cancer donations they do not announce they have cured HIV/AIDS or cancer publicly. As I've told you, and will continue to tell you: technology is far, far, FAR advanced than what you currently see around you. With the help of the good people of earth I promise to release these technologies for the benefit of mankind, and all reading this disclosure can hold me to this. You **must** hold me to this. It is time we ended corrupt governments and corrupt individuals in high positions of power in this world. Hold me to this.

I hope you are now beginning to understand why this is a **world emergency** and why these corrupt people must be ousted and overthrown. I also hope you understand why you must not riot or cause chaos because as I said at the beginning of this disclosure "I write this to empower good people of the world against the tyranny which exists all around us in our world today"; I **did NOT** write this to cause chaos, public dissension or anarchy. Good people of the world will inherit the earth once these corrupt people are overthrown. Therefore, under no circumstance must you destroy the world when you are going to inherit it. No matter how angry this disclosure makes you; no matter how angry the diabolical people who commit these crimes against humanity make you feel. Let's make sure this goes smoothly. Keep spreading and sharing this information, until this disclosure reaches the armed forces; until the armed forces bring these corrupt people to their knees. We are about to inherit the earth; by all means let's ensure everything goes smoothly. Now that you understand how important this disclosure is and that the overthrow of these corrupt individuals must progress smoothly, I'll continue.

The Behaviour of High Profile People at the Cloning Centre

The high profile individuals who attend these REM driven clone gatherings in their sleep have nothing better to do than to show off in disgusting ways. They have no shame and it seems nothing embarrasses them. Some REM sleep driven, cloning centre attendees, sit in the stands of an unused arena, smaller than a hockey rink, but it still has the capacity to seat between approximately 300 to 400 people. There is dirt in the centre of the rink where ice would be. They have frightened REM driven clones of children walk into the middle of the dirt rink to be victimised for a bizarre and disgusting spectacle. Sometimes, they have animals like dogs have sex with the REM driven clone children, while a man holds the dogs on leash so that it wouldn't bite the child on the back of the neck; which I have seen happen before. They all try to outdo each other in their levels of depravity; to be evil is to be "cool" to them.

The Ring Leaders of the Cloning Centre

I will now discuss the ring leaders, but before I name names, please understand that I am not someone who has collated stories and evidence together over the internet. I REALLY **do not** need to do this. Every time I enter REM sleep, the ring leaders at the cloning centre transfer my consciousness to a duplicate clone version of me. I have seen and talked with these monsters over the course of 34 years as REM driven clones at the cloning centre. However, I do understand that for the average reader, without understanding how far medicine, science and technology has advanced; without seeing or hearing people, other than me, discuss the crimes the ring leaders of the cloning centres commit, it is very difficult to imagine that this is what these high profile people are involved with, and do. Nevertheless, I guarantee it; this is the true extent and prevalence of evil in our world.

Their public personas, and public images is well managed by their PR teams, and therefore for the average person it is difficult to imagine these people in any other way but "positive"; but these people behind closed doors are the most evil, sick and twisted people I have ever had the misfortune of encountering. It is also difficult to take in what I am saying because I am not a public figure, nor do I have the "influence" or public image these people have; the general populace have never met, or heard of me, or known who I am; if this was the case my eye witness testimony alone will be enough; however, I do understand that we are dealing with highly advanced technologies, thousands of years advanced compared to what the general public is accustomed to, and because of this I provide references for the reader; I provide references for the reader to have something to corroborate what I am disclosing; and I provide references for the reader to see past the illusions these people have created.

Moreover, as "Consciousness Science Kept Hidden" demonstrates (YesEthan 2013):
remember that it is the heart and not the brain which is the most powerful centre in the body, the heart is the most intelligent; it has the ability to receive precognition and intuition about a future event, **before it actually occurs**, therefore if you find that your heart is in resonance with the names mentioned; do not fight it with the ego of the mind; when our egos get in the way it overrides our heart's intuition; your heart is capable of discerning the truth of an event before your brain becomes conscious of it; by all means listen to your heart, and allow your brain to naturally develop its intuition. It will be the coherence between your heart first, and then your mind centre which will allow you to access your intuition.

The references I provide for the reader to corroborate what I am about to say includes: "Appeal from Survivors of Canadian Genocide" (inifiniLor 2013); Tila Tequila –"Missing Children and Cloning Centres" (Astral 7ight 2013i); "Royal Babylon by Heathcote Williams" (MrCowshedder 2012); and "THIS MOVIE WILL BLOW YOUR F%SNG MIND" (KafkaWinstonWorld 2014).

Watch all the above videos and you will easily see all that I disclose. In Appeal from Survivors of Canadian Genocide interview (inifiniLor 2013): Listen to the indigenous people Stee-mas and Wahtsek speak about the pain and torment they have suffered under the Crown, the Vatican, the government, and churches of Canada. 50,000 to 150,000 indigenous children have gone missing because of the involvement of the Crown, the Vatican, the government, and the churches of Canada; and all these factions involved know this!

Tila Tequila is a television personality who has attended the cloning centres as a REM driven clone since childhood. In Tila Tequila's radio phone in (Astral 7ight 2013i), the audio is not very clear for the majority of her disclosure; she was also frightened and therefore she sounds most animated; however her words are clear at the following points of the audio (I also provide a transcript in the appendices section: "Appendix A"):

4.00 min: Cloning Centres and they take your children...
4.25 min: –There are these CLONING CENTRES –I'm not even talking about child molestation here...
5.40 min –They take your children –they not only molest them; men f*** them; and make them shoot each other...
7.59 min- There is a point where you cannot just turn the other way, you know this stuff is going on and you go 'oh well, you know... that's their problem; let's just turn the other cheek. How long are you going to turn the other cheek until it happens to your own freaking children?

10.34 min - Do you know why they love children? Because they are innocent souls; they are innocent... they are the most innocent, pure beings in this planet. They are not harmed by anything. They are new to the world; bright-eyed, pure innocent children. That is why these disgusting paedophile... and these clone rings, cloning centres, satanic rituals, Brownsville Texas... there are many of the of the cloning centres where they take your children that go missing.

Royal Babylon by Heathcote Williams (MrCowshedder 2012) addresses the fact that for Brits, despite their inordinate pride about their tradition, it is often revealed they know little about it than anyone. The documentary then goes on to address the fact that Prince Phillip the Duke of Edinburgh, has a lust for blood-sports which includes shooting endangered wildlife and mammals which he considers ‘culling’. The documentary is also notable for demonstrating to the viewer that Queen Elizabeth II redistributed as much as 2.1 million for her private income from 276 people from Merseyside and Lancashire. These people had no will, so their property was grabbed. The same is true for the Duchy of Cornwall. If you die without making a will, everything you possess will go to Prince Charles. Furthermore, Queen Elizabeth II is the largest land owner on earth. Queen Elizabeth II: head of state of the United Kingdom, and 31 other states and territories is the legal owner of about 6600 million acres of land; one six of the earth’s non ocean surface. She is the only person on earth who owns whole countries, and who owns countries that are not her own domestic territory. This land ownership is separate from her role as head of state; is different from other monarchies where no such claim is made –Norway, Belgium, Denmark etc. The value of her land holding is £17,600,000,000,000 (17.6 trillion Pounds) (approximately)).

In “THIS MOVIE WILL BLOW YOUR F%SNG MIND” (KafkaWinstonWorld 2014), readers with a deeper knowledge of the Illuminati and the agenda of the Illuminati will easily spot the minor inaccuracies in the documentary. However, the documentary provides a good reference and foundation for anyone new to the topic of the Illuminati and their agendas for the world. The documentary demonstrates how the world is currently a deception within a deception coated in reverse psychology. It gives widespread insight into the Royal family of England, and their lineage.

Furthermore, the documentary provides information that the world’s most popular religions have been infiltrated with Illuminati dogma, in secret. The documentary details how (some) modern Christians, Jews, and Muslims do not (yet) recognise their common enemy because that enemy is invisible (until now). The enemy hides within their own religions. The enemy also hides within the activist community (anti-Illuminati movements), it finances big budget documentaries and movements. The end game is to sell a divisive (creating strong disagreement), anti-capitalistic, atheistic message and deliver trusting followers right into the lap of a communist (one government) New World Order. The enemy is the Illuminati.

The documentary also details that: “Today, the bloodlines of this unholy alliance are on the final stages of establishing one world religion, one world government, and one world ruler [--that is **IF**, the good people of this world do nothing to stop them]. The Windsor Royals are at the control of this web of deceit. It is a known fact that Adam Weishaupt (the founder of the Illuminati) took refuge and got assistance from the German Saxe-Coburg Gotha Royal family. The Saxe-Coburg Gotha’s changed their German name to Windsor (in 1917). The Windsor’s public image is a façade, to hide the cesspool from which they operate behind the scenes; their power and control cascades out of Buckingham Palace to the elite bloodlines who run world affairs.”

For anyone who thinks they know they Royal family of England, did you know that still to this day: they have a person appointed called "Groom of the Stool"? What is a "Groom of the stool", you may ask? A Groom of the stool is responsible for stools. The kind you sit on and the kind you expel. In other words a Groom of the stool wipes Royal bottoms. The above has been confirmed to me by Prince Charles of Wales himself as REM driven clones at the cloning centre, and I quote: "It gives you the feeling of being completely taken care of" when I asked Prince Charles (as a REM driven clone) why they still have that. But don't just take my word for this; research "Groom of the stool".

The Royal Family of England

As most of readers have already guessed; and as unbelievable as it may currently sound to some readers, the ring leaders of these cloning centres includes the royal family of England. As I've said REM driven cloning started as far back as 1945, and it was just a political thing, but Queen Elizabeth II has been involved with REM driven cloning since its inception! Yes! Queen Elizabeth II; Phillip, Duke of Edinburgh and Prince Charles of Wales are the worst of them. They are unbelievable depraved perverts all showing off to the celebrities who attend these REM driven clone gatherings. Elizabeth has the REM sleep driven cloned children at the cloning centre call her "Lilli-bet" and Elizabeth as a REM driven clone herself does ungodly things to these REM driven cloned children. Some she fakes being nice to; some she is terrible to; and as a REM sleep driven clone Elizabeth cuts these REM driven clone children with swords while they scream. The decent people at these cloning centres who have had their consciousness transferred into their duplicate REM driven clones, and are there against their will, like I am; they are terrified to say anything against Elizabeth and her cronies. Most of these decent people also have their children's consciousness transferred into their REM driven duplicate clones, and Elizabeth and her cronies hold these decent peoples' children as hostage; to be torn apart; clone death after clone death if they have the slightest inkling of informing anyone, but as Elizabeth and her cohort have been torturing me as REM driven sleep clones anyway, I will disclose all that they do.

Vladimir Putin is also there, as an REM driven clone, and he loves to put the fear of torture and death into people, but he is essentially a perverted coward himself. Most of the famous people who attended the cloning centre as REM driven clones are ashamed to speak or be seen by me there very much; because they are ashamed of the perverse and disgusting gatherings. I am a decent person, even when my consciousness is transferred to my REM duplicate clone alternative, and I will not participate in these depraved acts; so they use me as an example and torture me for being a good person. They have drugged my REM driven clone, and as I've mentioned because consciousness transfer is real (Ehrsson 2013) and because consciousness is linked, therefore everything feels "real as real"; when I'm drugged as a REM driven clone, I behave exactly as any person would on hard drugs (although I have never taken any drugs in my original body); my vision is blurry and my balance affected; they have used this as method of having me do disgusting things in a blurred state, videotaping these dirty acts and editing a highlight reel which also depicts me doing disgusting things to show to the world when the world learns of their depraved natures and their public personas are shattered so that I can be despised as much as they will be when the entire world learns about this. Furthermore, because of the microchip inserted in my REM driven clone; they mind controlled me like a "Manchurian Candidate" (*The Manchurian Candidate* 2004) using MK Ultra technology, which is far more advanced than the declassified MK Ultra techniques (MK Ultra Compendium 1980) mentioned online today which references MK Ultra techniques in the 1970s. See Rense (2001) for a detailed explanation of how implanted microchips work, and how these chips allow the programmer control victims. C.S.I.S Canadian intelligence are all involved; they have REM driven clones too; including a lot of Commissionaires and Canadian Prime Minister Steven Harper himself; They do what Elizabeth says, and seem to follow her every whim without question. It doesn't matter who you are; if you have a cute child, or a talented child with imagination, creativity and moneymaking potential (such as business smarts; song making ability; literary / oratory ability etc. –you name it so long as your child has moneymaking value to them) they will send for the blood record of your child; agitate the blood cells over and over until a duplicate clone of your child is grown; they will then transfer your child's duplicate clone body from the tank they were grown onto a steel rack; the steel racks contain 5 rows and each row holds a duplicate cloned body; once your child goes to sleep in his or her original body and once they enter REM sleep (90 minutes to 110 minutes after they first fall asleep) the Illuminati are alerted to this fact by a green light above your child's duplicate clone at the cloning centre and they then transfer your child's consciousness to the REM driven duplicate clone; this is the point where the prime evils molest your children; and so your children are being molested in their sleep as REM driven clones and then they suppress the child's memory or implant false memories (see Kim (2013) and Alford (2015) –on how false memories can be implanted) so your children wake up not remembering dreams from the previous night, or if they do remember anything, the memory is false. These depraved acts very much stunt children's development; it causes them to have learning disabilities; unexplained depression; loneliness; suicidal thoughts, and all kinds of side effects.

The cloning centre is a paedophiles paradise and **it must be stopped**! Elizabeth secretly owes a few music companies too (Universal and others) with bands under contract; she forces me under a knife to compose music for them; if I can't she will stab my REM driven clone; burn my REM driven clone and have her pervert thugs smash my REM driven clone body there. As Ehrsson (2013) demonstrated, because consciousness is linked; and consciousness transfer leads the person who has had their consciousness transferred to still perceive reality as "real as real" in the new body; I have the same biological and physiological responses as I would have if these attacks were occurring to my original body. This has caused me to have heart damage and severe debilitating headaches. Because my memories were released to me; I can now also remember all my past REM driven clone memories since age 5; as well as the previous night's REM driven cloned memories (when I have my consciousness transferred to the cloning centre) which causes severe stress to my mental psyche and mental well being.

As unbelievable as the above statement sounds regarding Elizabeth's ownership of music companies, just go and listen to the song "Abadon" performed by Boondox (RainmanJhof 2011) on YouTube. There are two "Abadon" versions; the version you seek can be found in the Reference section uploaded by RainmanJhof (2011); skip to 2:46 min (or listen to the whole song; pay particular attention at 2:46 min) and you will hear loud and clearly, Elizabeth say "Drop the mother f****ing base". That is Elizabeth's voice; you can compare it to any of her Christmas speeches. That is her. Elizabeth said the above as a REM driven clone at the cloning centre. I know. I was there. They got so confident, that nobody would ever find out about their REM driven cloning shenanigans, that they even had me sing on a song I produced: "Where'd You Go" –Fort Minor (Murdok Dubstep Remix) (MurdokDubstep 2010), available on YouTube. Tila Tequila and I sing on this remixed track as REM driven clones (MurdokDubstep 2010); I start to sing from 1:44 min onwards. You can compare the voice you hear in the song with the Vinny Eastwood interview (Vincent Eastwood 2013). That is me, in both cases, and that song was recorded at the cloning centre.

One good person at the cloning centre; Bernie Mac (also as an REM clone version of himself); who was an actor and comedian, tried to stand up for me and speak up for me saying ‘Cloning and torturing people here, it’s not right to do to a human being...’ and “This place is the devil”’... Bernie Mac also tried to have others join him in speaking out against the REM driven clone torture zone while he was having his consciousness transferred to his REM clone driven version. Elizabeth and Philip tortured him for 4 to 5 hours continuously at the cloning centre as an example of their ‘power’, Bernie Mac had an aneurysm (brain bleed) the next day and died. This is one of the aspects about REM driven clone torture: if you torture a REM driven clone continuously for hours on end, you will cause the person to die in their original body from a heart attack or aneurysm (while they sleep); even if they do manage to wake up the next day; because of the constant pain their consciousness has recorded; and because consciousness is linked they will wake up only to have a heart attack or aneurysm in their original bodies the following day. If you apply a constantly electrical current to a REM driven clone, that person will either have a heart attack or die from aneurysm in their original bodies while they sleep.

This form of murder is similar to the CIA’s heart attack gun (Non Mirage Truth Vision 2015); which was declassified in the 1970s and was a weapon used for causing heart attacks in victims, undetectable as the cause of heart attack under autopsy. The difference with REM driven clone death as a form of weaponry is that hardly anyone has heard of death by REM driven clone torture. Moreover, the perpetrator can be thousands of miles away from the victim; the culprit just needs a duplicate REM driven clone of the victim to torture or apply a constant electrical current to; this is exactly what is going on in our world every day. When Elizabeth and Philip don’t like someone and they want to get rid of that person, they clone that person; torture his or her REM driven clone till that person has a heart attack or aneurysm in their original body and dies.

This is what Elizabeth and Duke Phillip did to the indigenous people in Canada. The video reference (inifiniLor 2013) provided above, regarding the genocide of the indigenous people of Canada discusses this very topic (inifiniLor 2013). As Elizabeth and Duke Phillip visited Canada as clones, when they killed the native children; they both had solid alibis of being in England at the time. They then cloned all the witnesses of the Canadian missing children’s case and had them remotely killed by applying constant electric currents to their REM driven clones; one by one and each witness either died of a heart attack or aneurysm. They just dispatched the last witness by also applying a constant electric current to the persons REM driven clone because the missing children’s case was building momentum.

After Bernie Mac’s death everyone is afraid to speak up; they all became afraid of suffering the same fate. All it will take is a few lie detector tests from an independent source; and I will volunteer for them; they cover up for themselves so carefully that lie detector tests from an independent source unconnected to them in anyway will be the only viable method. I know many know non-famous people who have also attended these clone centre gatherings as their REM driven clone duplicate versions and also remember the clone gathering experiences in their original bodies (because they were not memory suppressed) that could be given lie detector tests to prove this. When it comes to the sexual exploitation of a child, lie detectors are admissible in Canadian courts. I need decent people with integrity to speak about this filthy business; to testify about who is involved. There is much to tell about the Illuminati and I am a wealth of information about this topic.

Elizabeth also had Princess Dianna Spencer killed by having someone shine the brightest light known to mankind through the window side on her car; they served away to avoid the light and hit the divider; it was no paparazzi. I first wrote about this in my original disclosure in **2011**; this was corroborated by an article 2 years **AFTER** I had made my original disclosure. See Radar Online (2013) for the corroborating article. Furthermore, "Candle in the wind" performed by Elton John (SadSongs4You 2010) was not Dianna's 'death song'; it was "Bigger than us" performed by "White Lies" (WhiteLiesVevo 2010). The Illuminati released this song, deliberately, 13 years after Dianna's death, again as a show of their 'power'. I did not want to compose this song but Elizabeth and her thugs threatened to stab and burn my REM driven clone repeatedly if I did not. Listen to the lyrics. I'll provide some of the lyrics here for those of you who are feeling too shocked by these revelations:

White Lies Lyrics "Bigger than us"

You took the tunnel route home.
You've never taken that way with me before.
Did you feel a need for change?
Apologies on your fingernails,
Love flickered in the city of lights
Like internet and radio waves.

I don't need your tears
I don't want your love
I've just got to get home

And I feel like I'm breaking up
But I wanted to stay.
Headlights on the hillside
Don't take me this way.
I don't want you to hold me
I want you to pray,
'cause it's bigger than us.

Are you beginning to see why these people must be stopped and stopped immediately? Are you beginning to see why it is no longer okay to 'turn a blind eye' or 'bury your head in the sand', and hope it all goes away? Can you see why I need the good people of this world to keep sharing this disclosure (online); to tell your friends and family until this information reaches the armed forces so that the armed forces can bring these people to their knees. I also do not want innocent civilians to get hurt despite the monstrosities these people cause to humanity on a daily basis. I want the overthrow to progress smoothly so that the good people of the earth can inherit the world, with all technologies and medical advancements which benefit mankind, made available to all. This is why I maintain my composure and resolve, in spite of the evil I see on a daily basis, and you the reader must also maintain your composure and resolve in spite of the evil which I am disclosing, so that we do not inherit a torn down world after we have completely overthrown these malevolent, sinister and corrupt hypocrites!

Furthermore, Diana survived the car crash; and while, either on her way to hospital or in hospital, Dianna was injected with a high concentration of salt, which is near undetectable in an autopsy and she died. Elizabeth did this because Diana was going to marry an Arab named Dodi Fayed. The Illuminati hate Arabs because for the most part, Arabs have not broken their relationship with God. Dianna hated her association with these people; Dianna knew about REM driven, sleep cloning and wanted nothing to do with it; but she was afraid of being killed and so said nothing. I know a lot about this and many more deplorable things the Illuminati have done over the course of 34 years and I will be more than happy to reveal all the evil they have done; as well as all the wonderful discoveries and progresses they have made in medicine, science and technology, which they have withheld from the general public. I am very happy to disclose all, because I known once the world learns of all they have done, we truly will begin to see the end of such evil on this planet. Just make sure you keep spreading this disclosure and it reaches the armed forces soon. Soon, soon, soon!

Help Donald Marshall by Sharing this Disclosure with Your Close Friends and Family

If you are reading this, then you have to help me. I know some of you may be reading this thinking, but I am just an ordinary man or woman Donald, I know you are telling the truth; I can feel it in my heart and my head that what you say is true and that you are telling the truth (which I promise you, with my right hand to God I am) but I'm just an ordinary man / woman Donald; I don't have any power; I don't have any influence; or because of the position I am currently in I can't speak out against these people; and I am just an ordinary man / woman I cannot be expected to take on the world's problems. You are right if you are thinking and feeling this, and I do not expect or want you to take on the world's problems. All I want you to do is share this information with close friends and family initially, because when you do that, at least that is one more person who will know about the true extent of evil in this world. When your close friend or family member also shares my disclosure with another close friend, the disclosure will eventually spread exponentially. It will also be one more person who has your well being in their thoughts because I understand how scary it is to know this. Therefore remember **there is safety in numbers;** and the more people you tell in your social circle, the more you can all look out for each other. So feel free to share my disclosure with close friends and family. Do not talk about my disclosure in public (for now) if it makes you feel uncomfortable. Moreover, if you want to reach more people (other than your initial social circle) the best way, is to do it online: through social media, such as Facebook, Twitter, and YouTube etc. As I've already mentioned, the Illuminati controls all forms of media except the internet.

The Illuminati, being so 'confident' at the time with the evil they wield onto the world, put my face on a Megadeth album cover titled *The World Needs a Hero* (2001) (to mock me) when I was 23. I posed for this album cover at the cloning centre when I was 23, and the album was released with a picture of my face, as a REM driven clone, 3 years later when I was 26. They did this because they were extremely confident that nothing would ever be proven. Google image it, although I am 39 now, you can still tell that it is me. The image shows what I end up looking like after an REM driven clone gathering with a skeleton popping out from my chest. I understand most of you are going to continue reading because although it is "liberating", it is also "paralysing" at the same time (Laurence Mountford) to realise what the truth of the world is, so I will display two images below, but promise yourself, that you will Google search this image in your spare time.



Image 3: Megadeth Album Cover: ***The World Needs a Hero*** **(2001)**


Donald Marshall On Megadeth's "The World Needs A Hero" Album Cover

Image 4: My original body: top left (age 37) and bottom right (age 37); compared to my 23 year old REM driven duplicate clone body (top right and bottom left) at the cloning centre.

You can clearly see from the images that, it is in fact me. In Image 4, you can also compare what my real body (top left and bottom right) looks like compared to my duplicate clone body. Duplicate clones do not come out of the tank looking 100% like the original; it's 99% - there are always some slight variations as some have commented that the eyebrows and nose in the picture, bottom right, is not the same (as the duplicate clone on the album cover). However, to people who make such comments, I say: my eyebrows and nose is the same when you compare it to the pictures of my original body (top left and bottom right). Also, remember that the image on the album cover is a duplicate REM driven clone of me. REM duplicate clones do not come out of the tank looking 100% like the original. There are always slight variations; but the wrinkles on my 37 year old forehead (when I took the picture in my original body; top left and bottom right) is similar to my 23 year old wrinkles, the lips are the same; and the face which you see, is definitely, the same! Yes. REM duplicate cloning is real; going to sleep and waking up as a cloned version of version of you is real and **we must put a stop to it now!**

The Deplorable Nature of the Illuminati

My own family has been turned against me one by one. The Illuminati have told my family members when they were REM driven clones at the cloning centre, things such as I secretly hit or molested their children; poisoned their pets when the pets died of sickness and other such things to make my own family hate me and not want to help me. Even when my family side with me there at the cloning centre, as REM driven clones of themselves; and my family members say 'They do not believe that Donny did all those horrid things' -which they have been told; Elizabeth then says "Are you cooling me a liyah?!" in her disgusting croaking voice made as low as low and evil sounding as she can make it, complete with psychotic and malevolent glare; and as terrified REM driven clones my family say "No, no, of course [what you are saying] it's true", stuttering and afraid as REM clones. My mother Catherine McMahon sold me into this REM driven sex and torture cloning slavery when she remarried a man named Gordon Cohoon; Gordon's whole family is in this scummy secret society, his brothers Tom and Tony Cohoon; his sisters Darlene and Bernadette Cohoon; they fear the new and improved lie detector tests; and all it would take, is for an independent source, far, far removed from any association with the Illuminati to administer these lie detector tests on me **AND** the above named people to prove this unequivocally.

Half way through the making of my original disclosure document (in **2011**), when I went to sleep that evening, the Illuminati transferred my consciousness to my REM driven clone and introduced me to a man (who was also a REM driven clone) named TROY LANDRY. He is an alligator trapper from Louisiana on the TV program named "Swamp People". Troy Landry said "If I send my [original] disclosure out to the public then he would take a power drill to my shin bone at the cloning centre and suck the marrow from my [REM driven clone's] bones." It is similar to spinal tap, and one of the WORST things you can do to a REM driven clone besides burning a REM driven clone. I told Troy that I will be sending out my disclosure to the public, because I have to escape the cloning centre, and so, Troy Landry did just that. It was excruciatingly painful; all the REM driven clones that were sat in the stands of the arena just watched; slack-jawed. Troy Landry is an insatiable child molester and an extra retarded REM driven clone. A side effect of REM driven cloning is that as a REM driven clone version of yourself, your emotions are heightened and you are less smart as you are when you are experiencing the world in your original body. Nevertheless, Troy Landry is extra retarded as a REM driven clone.

In Louisiana, when Troy sees a young boy that he likes, Troy asks of the boy's name and tells the boy "He is an alligator hunter"; Troy then proceeds to shake the boy's hand; Troy then has his paedophile friends at the local cloning centre find the boy's blood records to grow duplicate clones of the boy. Five months later, there are multiple REM driven duplicate clone bodies of the boy grown for Troy Landry to victimise before the crowd of onlookers. All members of the Illuminati do this; it's just a way of life to them; they consider themselves 'the privileged people' in the world power organisation. Almost all the cast on the "Swamp People" television program attended the cloning centre as REM driven duplicate clones of themselves, **when they go to sleep**. After putting a power drill to my shin bone, Troy Landry asked me again, "Will I send my [original] disclosure out?" I said "Yes" to which he replied "I'll do the same to your pelvic bone everyday!" The pain on my pelvic bone was far worse than when Troy put the power drill to my REM driven clone shin bone. I told Troy "I have no choice but to inform the public" – and so Troy put a power drill to my REM driven pelvic bone, everyday... and it is the worst pain ever... you forget your own name; where you are; all you know is pain; and you beg God or anything to save you from it...

Another deplorable thing which the Illuminati did in real life is: The Canadian government were trying to lower the amount of prostitutes on the streets (Elizabeth hates prostitutes) so they had a man named Robert Pickton start killing the women and feeding the women to pigs on his farm. The Illuminati had a camera set up in the upper corner of a room in Pickton's house and recorded Pickton hitting these women over the head with a hammer (a ball-peen hammer). They took the recordings, all 49 of these murders, and they all watch them at the cloning centre. To be seen as 'tough' at the cloning centre is to watch all 49 of the Pickton murders without having it affect your psyche. Elizabeth loves watching the Pickton murders and she says she has a macabre fascination with death. Canadian Prime minster Steven Harper knows all about the conduct of the Pickton murders; he has seen all the recordings and cheers on as the rest of them do. If Mr. Pickton says anything about his involvement with the Illuminati, or the recordings, they will apply a constant electrical current to his REM driven clone until Pickton has a heart attack or aneurysm in his original body.

What Happened to Britney Spears?

The Pickton murders are also the reason Britney Spears 'lost it' and shaved her head bald. She had watched too many Pickton murders as a REM driven clone at the cloning centre and it drove her 'over the edge'. I'll also reference the following songs performed by Britney Spears so that the reader has more corroborating evidence to add to the ever increasing pile. Search for the video "Break the Ice" (BritneySpearsVevo 2009) on YouTube. In the Japanimation video; at the beginning of the video; that is a cloned **cartoon** version of Britney Spears being grown in a big thick thank full of water (1 second to 7 seconds); and at 1:32 min to 1:43 min Britney walks into the cloning centre. This is **EXACTLY** how the cloning tubes are in real life. They are stacked one on top of the other, each filled with salty water. Britney Spears made this video because she said a fantasy of hers is to "Blow up a cloning centre". The Illuminati allowed her to release this video because at the time they figured nobody would ever figure it out. I have provided the images on the next page.



Image 5: Britney Spears is being grown as a duplicate clone in a cloning tube. The depiction is EXACTLY how the duplicate clones are grown in the Cloning Centre... with wires extending from the body; in a big thick tank full of salty water.



Image 6: Britney Spears walks into the cloning centre. The cloning tubes are stacked one on top of another. This is EXACTLY how these cloning tubes are in real life at the Cloning Centre.



Image 7: The Cloning Centre depicted from an aerial view.

In “Hold it Against Me” (BritneySpearsVevo 2011) performed by Britney Spears; Britney is depicted fighting against her clone at 2:46 min till the end of the video. In “Mona Lisa” (SimpleGirl4ewer 2007) later remade by Britney Spears she changed the words in the song from “gone” to “cloned”. I’ll provide the lyrics to chorus here because they have not changed it on A-Z lyrics etc., but listen to the song and you will clearly hear the following:

Britney Spears Lyrics “Mona Lisa”

She’s the original (yeah, yeah)
She’s unforgettable (yeah yeah)
She wants you to know (yeah)
She’s been cloned…
It’s kind of incredible (yeah yeah)
She’s so unpredictable (yeah yeah)
She wants you to know (yeah)
She’s been cloned,
She’s been cloned,
She’s been cloned…

Yes. Britney Spears and many other celebrities want you to know they have been cloned. The celebrities are depending on you, the ordinary man / woman; the populace, as I am depending on you to spread this message fast and far. In fact Elizabeth has said that “If any public person speaks out, they will die!” Therefore, public figures cannot openly discuss this topic to warn the populace –so they hint. It is **NOW** up to the ordinary man and woman to end this. Furthermore, Elizabeth has a nuclear bomb hooked up at the cloning centre which she can press at any time to wreck havoc on the world unsuspectingly. Thankfully, I managed to convince Elizabeth not to do such a silly thing. I hope you can now understand why everyone is terrified of Elizabeth at the cloning centre, and why this is a **world emergency** and we are depending on you to share and spread my disclosure!

NEVER EVER SELL YOUR SOUL

In This Physical World Selling Your Soul Is Selling Your REM Driven Clone

Furthermore I must discuss an entrapment many up and coming ‘stars’ fall into. You have most likely heard many public figures say “I sold my soul to the devil” or some variation of “I sold my soul”. I am now going to address the aspect of “selling souls” or “selling your soul” which I am sure you have heard many of these celebrities talk about. I’ll address this as coherently as I can because the on the surface selling your soul talk is difficult to contemplate especially if you consider the soul to be a metaphysical, ethereal or mystical part separate from your earth body. Moreover, we live in a physical world, so selling a metaphysical aspect of you sounds incomprehensible (at first). For the most part we have little understanding of what the soul is. However, we are told that the soul is a part of us which never dies and it is eternal. It is all that we are, ever were, and ever will be. Now our faiths and beliefs come into question, because if you are an atheist: there is no God, selling your soul is a bunch of crazy nonsense.

From a practical perspective it also seems difficult to fathom, because if you go on what you have been told, you are selling an intangible part of yourself to be used by someone else for whatever they wish; and so if you get into the headspace of viewing your soul as something separate from you or that you are in control of your mind and your body, then again, 'selling an intangible aspect of you' again sounds like nonsense because right now nobody controls you; you are controlling you; so what are you really selling? Thin air?

Many up and coming 'stars' think this way when they are confronted with "selling their soul" aspect. The up and coming 'stars' are blinded by the prospect of being super famous and super rich; and in the moment they are confronted with "selling their soul" they believe these Illuminati people, are a group of over religious zealots and that they, -the up and coming 'stars' are taking advantage of the Illuminati because the 'soon to be 'stars'' do not believe (in that moment) it is possible to sell your soul, and only consider being super rich and super famous; so the 'stars' sign their 'soul' over.

At this point, it is usually too late for the up and coming 'star'; because what they have actually sold, in this physical world, is the use of their REM driven clone to the Illuminati. They have sold their REM driven clone to be used for REM driven sex by perverse old men and women whenever they enter REM sleep.

These celebrities are not memory suppressed either; so whenever they enter REM sleep, their consciousness is transferred to their REM driven clone, to be used for whatever the Illuminati wish: usually sex as REM driven clones with dirty and perverse old men in return for a promotion in the entertainment industry; such as movie role, advertisements, concert gigs etc. It is a very, very, sick business, and once these up and coming 'stars' get into the business they are trapped. Now you can begin to understand why so many celebrities, although on the surface it appears they have it all, are depressed; and do random and crazy things. It is a cry for help. Their illogical behaviours, (not all) for the most part, can be attributed to REM driven cloning. Furthermore, the Illuminati consider 'selling your soul' (the use of your REM clone) **a very serious business.** They do not joke about this; and there are NO RETURNS. Once you have sold the use of your REM driven clone for promotions etc., that's it. If you ever make a fuss and want your 'soul' back, in other words: you no longer wish to have your REM driven clone to be used by dirty old men for sex; the Illuminati will kill you by applying a constant electric current to your REM driven clone until you have a heart attack or aneurysm in your original body and die. It is as simple as that.

For example, Whitney Houston wanted nothing to do with the cloning centres, she said she would keep quiet; she never wants to be in the spotlight; she never wants to do radio or television. Let bygones be bygones, I'll go my way and you can go your way. The Illuminati were extremely angry! They had bank-rolled her, and now she didn't want to be their 'friend' or ever associate with them again. She was sacrificed; she was killed with a constant electric current to her REM clone. She had sold her soul, in the beginning of her career; in other words, the "use of her REM clone". Earlier in Whitney Houston's career, she had signed that they can use her REM driven clone however they wish.

I have also seen people say "No" –when confronted with 'selling their souls'. These people are then memory suppressed, and will not remember the proposal of their REM driven experience. The people who also refuse to sell the use of their REM driven clone ('sell their souls') are blacklisted secretly, and they will never receive a high paying movie role, concert gig, advertisements etc. If you have ever wondered why so many talented people have not 'made it' –they refused to sell their souls, in other words, the use of their REM driven clones in exchange for promotions. This is how the entertainment industry really works. Another aspect of selling your soul, in other words, **selling your REM driven clone** is that you are also agreeing to sell your children, and your children's children etc.; your whole lineage to the Illuminati; for the Illuminati to use your unborn children for paedophilia, torture, sex sports and other grotesque and ungodly things when they sleep. It is a nasty business. **NEVER EVER** sell your soul.

The lesson is very important. NEVER EVER, 'sell your soul'; NEVER, EVER! You will experience the worst nightmare situation ever, and in this physical world, that is the use of your REM driven clone to be used for sex sports. You'll never have a decent night's sleep ever again, and you will always retain the full memory of your REM driven clone experiences; as well as, you will be selling your unborn children into this dirty business. Even when confronted with this as a joke: never sell your soul. Never Ever! The physical aspect you are confronted with when asked to 'sell your soul' is: "YOU", and everything which makes you, "you"; your ideas, your creativity, your privacy, your biology; everything which makes you, you. Never sell your soul, which in this life is currently the use of your REM driven clone! Never, ever! I hope that is well received.

Fake Alien Abductions conducted through REM Driven Cloning Technology

I must add they grow duplicate REM driven clones of people from all walks of life and then they transfer the persons consciousness to their REM driven clone version at the cloning centre while the person's REM driven duplicate clone is chained down to stainless steel corpse tables; or they pre-inject the REM driven duplicate clones with drugs before transferring the consciousness so that once the consciousness has been transferred, the REM driven clone cannot move. This is the point when they usually send people into the room dressed as aliens. It is a fake alien abduction. It's just these Illuminati people dressed in Hollywood quality accessories and they make the REM driven duplicate clones which have either been chained to the steel corpse tables or pre-injected with drugs, believe they are having an 'alien abduction'. Members of the Illuminati even dye chicken skin grey, and stretch it over a mask for realism and perform "experiments" on the immobile REM driven clones; the perverts anally probe them; they rape their limb bodies and do not suppress the victims memories; so these victims wake up thinking they have been abducted by aliens but in reality, they had their consciousness transferred to their duplicate clone versions when they entered REM sleep and they were violated. The victims do not know where to turn and naturally, they are embarrassed. Some victims even try and do install cameras all around their bedrooms in order to videotape themselves while they sleep; to prove they have been 'taken'; but to no avail they have not been taken; they have been cloned and had their consciousness transferred to their REM driven duplicate copies once they enter REM sleep by the most disgusting perverts in the world. The scum even videotape these 'abductions' to watch later as sick demented porn. These fake abductions are conducted by the Illuminati more often than you can imagine. They just keep doing it to random people over and over and over...

I am THE Spy for Humanity against the Corruption of the Illuminati

Over the years the Illuminati have offered me: a priceless katana (samurai sword); a rigged jackpot winning lottery ticket; REM driven clone slaves to keep me quiet, any of the prettiest women I've ever seen; any girl from high school; Vladimir Putin's daughter; even children; I do the right thing and spit in their REM driven clone faces; jam my fingers into their eyes but they have the technology to turn off the pain sensors of a REM driven clone, and therefore they have their pain receptors turned off as REM clones, while my pain receptors are fully on (sometimes even beyond the threshold of what is normal pain for a human). See the online articles: Science Daily (2014) and RT (2014) which discuss how pain receptors can be turned on and off in humans. Not much will hurt their REM driven clones other than getting dirt or vomit in a wound or bleeding too much. However, they have perfected the science and technology of REM driven cloning and therefore it only takes time and approximately $30 to grow new duplicate clone bodies. I started to smear excrement in their faces as a REM driven clone at the cloning centre in an attempt to deter them; I have **never** handled faeces in my original body, but I do this as a REM driven clone at the cloning centre, and even that does not deter them from their depraved ways. I composed a song which was later performed by "One Republic" referring to it called "All the Right Moves" ("All the right friends in all the right places... All the right moves in all the right faces"). I've made so many songs with MK Ultra technology (Rense 2001; Jim Cristea 2009; Berekley News 2011; Mind-Computer 2012 nature video 2013) and Mind-voice technology (New Scientist 2014; Prigg 2014) it is ridiculous. You see it is very easy to make music using Mind-voice technology; Flo-Rida used Mind-voice technology to produce the song "Whistle" when I first made my original disclosure (in 2011). The song is a taunt at me about my "whistle blowing disclosure" i.e. 'Can Donald blow the whistle? Etc. etc.' The thing is, anyone with a talent for music can make music much easier with the technologies which they have (MK ultra technology; Mind-voice technology); however, the Illuminati made more money from the music I composed, and so over the years, they just kept using me, over and over and over again, for rock, pop, rap, country etc. There are so many people involved in this REM driven cloning business, it is staggering; the organisation is vast. The only things the Illuminati fear are nuclear war; the new and improved lie detector tests and the general populace spreading my DISCLOSURE DOCUMENTS.

For those of you thinking Queen Elizabeth II looks like a kindly little old lady and you still cannot believe that all this is true, although I have provided plenty of evidence to the contrary as well as evidence of her saying "Drop the mother f***ing base" as a REM driven clone on a song track (RainmanJhof 2011); you could not be more wrong. She is the worst human being I have ever seen or heard of. It is so sad to see these REM driven women and children having their consciousness transferred to their REM driven clone duplicates and brought to the centre of the dirt rink, sitting there naked, afraid and crying and raped and beaten for sport, for the rich and famous. REM driven cloned women and children display the most range of emotions, and it is the saddest thing to see there. Therefore, of course I cannot bring myself to be a part of this despite any riches which the Illuminati offer me.

Over the 31 years when I was having my consciousness transferred to my REM driven clone at the cloning centre; Elizabeth, Vladimir and many, many Illuminati members and cloning centre attendees discussed many topics with me. These Illuminati people, such as Elizabeth and Vladimir, as well as many others confided in me because I had composed songs since I was 5 years old.

For readers struggling with the idea that a 5 year old can compose such wonderful songs at such a young age I will remind you that, it is easier to compose songs with technologies such as MK Ultra and Mind-voice technology. One is only limited by their imagination and creativity. Moreover, research talented children. I won't provide references of talented children here because I want to protect children from the Illuminati, and not have children exploited like I was; and for the readers who are parents; I am sure you know how talented, creative, and imaginative your children are.

Accordingly, since the age of 5, Elizabeth, Vladimir and many, others confided me in me because they thought I was special, and wanted me to hang with them; some of these Illuminati people, I had composed their favourite songs; I was also memory suppressed for many years so they thought it was harmless to tell me everything that exists or is possible. They were trying to impress me and amaze me, and therefore they showed me plenty of their technologies and what they had. They wanted me to me a willing, full Illuminati member; so over the years I feigned interest and pretended to like these Illuminati people, so that I could learn what they do and how they do it. I was looking for a way to block the consciousness transfer to a clone during REM sleep, or hoping they would reveal this part to me; but they did not, and I did not find a method to block the consciousness transfer. However, I bided my time, until I knew just about everything they do; so that I could reveal to the world everything they do; to give humanity a fighting chance against everything they do and as a consequence, I became a spy for humanity against the corruption of the Illuminati.

The Threat to Humanity when the H.A.A.R.P Grid is Complete

One of the most important topics which they discussed with me that I must add to this disclosure is HAARP technology and their plans for HAARP technology. I have discussed the basics of HAARP above. HAARP radio transmitters have to be placed at certain points across earth to complete a 'HAARP grid'. Once all the installations are completed over the earth HAARP will have more functions as a grid than the basics described. The Illuminati have told me, there is a possibility the HAARP grid will be capable of time travel, although there is a 50/50 chance using HAARP for time travel could destroy the earth. They also told me that once the HAARP installations are completed, the HAARP grid will be able to bend space and make the distance between, for example, Earth and Pluto approximately 1000 miles for a few seconds, and then the distance will go back to normal.

The Illuminati also said, once the HAARP grid is completed, they would be able to mind control people like never before without the use of RFID microchips or MK Ultra. Life on earth will be much worse once all the HAARP installations are up and working together in unison. The grid has to be complete though. HAARP cannot achieve time travel manipulation and mind control if it is just located in one or a few locations around the earth. There must be a certain number of HAARP installations around the world, in certain locations around the world; and the HAARP radio transmitters must be working in unison in order to achieve time travel manipulation and mind control of the populace of earth.

This is what they told me as REM driven clones at the cloning centre. This disclosure could be false, or a half truth. I do not know. However, it is very important that I add this to the disclosure because the Illuminati are working twice as fast to complete the HAARP grid to achieve their aim of mind control over the entire population since I the time I sent out my first disclosure (in **2011**). Whether or not they will achieve their aim of total mind control once all the HAARP installations are completed is NOT something we can afford to debate. They also told me that once the HAARP installations are completed; they will have the capability to mind control anyone remotely like never before, at the push of a button. HAARP will also be capable of setting back time; which the Illuminati will use if they are ever in danger of being exposed. However, the Illuminati will remember the previous time, and the general populace will NOT remember the previous time, so that the Illuminati can correct the mistake(s) which led to their downfall. **Once the HAARP grid is completed, humanity will be slaves forever.** This is why we cannot afford to debate. Furthermore, from the book "Angels don't play this HAARP" (Begich & Manning 1997, p. 8), it is estimated that the HAARP grid will be completed by approximately 2017; others estimate by the year 2020. The important thing to note is that humanity does not have long, until the HAARP grid is completed.

I must also add the positive side of HAARP, because as I have said, there is nothing inherently evil about technology. Technology is just a tool; it depends on the person using it. HAARP used correctly, and in the hands of honest men and women, will tame the weather with no adverse effects. Therefore humanity is on a timeline and a deadline to bring the Illuminati to an end. **HAARP is one of the main reasons, this disclosure must spread, and spread fast.**

See below for possible HAARP locations around the earth (Rense 2011). The HAARP sites are located globally where the richest mineral belts are located. Sub-surface mineral exploration has been done from satellites by radio tomography that is 100% accurate.


WORLD
Political Map
EISCAT HAARP NORWAY
HAARP GAKONA ALASKA
HAARP LONG ISLAND
HAARP UK
HAARP RUSSIA
HAARP CHINA
HAARP JAPAN
HAARP AREA 51
HAARP PUERTO RICO
IRAQ
HAARP INDIA
HAARP PERU
HAARP BRAZIL
AUSTRALIA HAARP
AUSTRALIA DEFENSE RADAR
Arctic Ocean
North Pacific Ocean
North Atlantic Ocean
South Pacific Ocean
South Atlantic Ocean
Indian Ocean
Southern Ocean
ANTARCTICA
Copyright © 2008 www.mapsofworld.com
0 600 1800 3000 4200 Kms.

Image 8: Possible H.A.A.R.P. Locations. Source: Rense (2011)

REM Driven Cloning is the Most Terrible Nightmare Situation Ever

Furthermore, in terms of REM driven cloning; Fefe Dobson (singer) and Kurt Russell (actor) told me during my original disclosure (**2011**) specifically, to include in my disclosure that they do not like the cloning centre and they didn't torture me. Then they said not to mention them, but I will mention them again. Mila Kunis (actress) from "That 70s Show" stabbed in my REM driven clone body multiple times when I made my original disclosure and I was rendered immobile for saying that "She is a slimy scumbag for hanging with these people" and for also saying "She has enormous eyeballs and looks like a lemur". Mila Kunis (as a REM driven clone at the cloning centre) then begged me not to mention her (in my original disclosure, but I'll mention her again too) and then Mila Kunis said "She doesn't want to go to the clone zone anyway" and the Illuminati then deactivated her consciousness from her REM driven clone body, and she left. Her REM driven clone body went limp at the point where her consciousness was deactivated from it; her REM driven clone body looked 'dead', and she was gone. Some of the privileged people at the cloning centre are allowed **NOT** to have their consciousness transferred to their REM driven, clone duplicate versions (or they attend the cloning centre willingly when they want), but not me. I am an imprisoned slave in the worst nightmare situation. I told Nicole Leone (Madonna) also a REM driven clone at the cloning centre, that I was going to tell everyone that she coerced me to compose songs for her throughout my life (as REM driven clones). Nicole Leone (Madonna) told me VERY specifically to say in my disclosure here "She is not afraid!" and "No one will believe me and nothing will come of this". I beg you to help me prove her wrong.

Moreover, having your consciousness transferred to a REM driven clone alternative inhibits the person's ability to dream for that evening. Although your original body is immobile and asleep in your bed, when they transfer your consciousness you have actually 'woken up' as a REM driven clone version of you at a physical location here on earth; therefore you walk and talk as a clone version of you. You are not dreaming; you are just a REM driven clone for the evening. Furthermore, when the Illuminati restore your memories (as they have with me) or do not suppress the memory of your REM driven cloning experience for the evening (such as with the fake alien abductions), you will remember the experience as 'clear as daylight on a summer's day'; the experience is 'clear as a bell' as life is in your original body.

It is unlike dreaming, where dreams are fuzzy, incoherent and with random conjecture. The Illuminati know this as a fact, and therefore pre-inject the REM driven clones of random unsuspecting civilians for the evening with drugs before they transfer the person's consciousness. They tell the person who has had their consciousness transferred to their REM driven clone all sorts of nonsense: such as they are in the 5th Dimension; the astral plane; a singularity; the spiritual realm; Valhalla; quantum hopping etc. and all sorts of fallacies so that the person will not have a coherent picture of what has happened or what is happening. The truth is that person has had their consciousness transferred to their REM driven duplicate clone when they went to sleep and entered REM sleep; their original body still remains asleep in their bed; their consciousness however is now transferred to a clone duplicate alternative, and the person is 'awake', walking and talking as a cloned version of themselves in a physical location. The Illuminati allow some people to retain some of these REM driven clone experiences to affect their mental psyche.

The physical location where the populace will be able to verify these REM driven clones is somewhere within 5/6 hours drive, in a radius of the Robert Pickton farm, Port Coquitlam, British Columbia, in Canada, somewhere at a remote nature reserve. This is the cloning centre all the rich and famous attend because it is above ground and the rich and famous don't like the 'hospital smell' of underground cloning centres. The above ground cloning centre located in Canada is the cloning centre I have my consciousness transferred to when I sleep. It is guarded by military personnel. There are many cloning centres all over the world; as Phil Schneider (1995; 1996) disclosed as far back as the mid 1990s when he spoke: there were 1477 Deep Underground Military Bases (DUMBs) worldwide and 131 active DUMBs in the United States alone. Each DUMB costs on average 17 -19 billion U.S. dollars; paid for by the taxpayer; and it takes approximately a year-and-a-half to 2 years to build DUMBs with sophisticated methods. DUMBs contain cloning floors, and have an entire floor dedicated to human cloning, where duplicate clones are grown of unsuspecting civilians (remember they just need your blood / DNA); and unsuspecting civilians have their consciousness transferred to their REM driven clones at a physical location, which is usually these Deep Underground Military Bases when they sleep; unsuspecting civilians are memory suppressed, also to be used for gruesome torture and sex sports; as well as the plagiarism of talented individuals. Schneider gave the above statistics in the mid 1990s; chances are there are more DUMBS and cloning centres worldwide today.

Are you beginning to understand why this is the worst nightmare situation ever? Can you understand how: you, your friends, your family, your brothers, your sisters, aunties, uncles, children, work colleagues and anyone else you have contact with in your network, may be involved in this REM driven cloning business and will not even be fully aware of the situation or remember any experiences which they may have had once they wake up from sleep and they are back in their original bodies? I remember all of the REM driven clone experiences as clear as daylight because my memories are fully restored. Can you understand why the Illuminati must be stopped and stopped immediately? This REM driven clone business is vast, and it affects everyone, not just me.

This is why I mention that I am fortunate or unfortunate to remember all these experiences clearly depending on how you view it. I am unfortunate in the sense that I can recall all the depraved things these people do as REM driven cloned duplicates as clear as daylight and it affects my mental psyche. However, the fortunate part is: because I can recall all these experiences clearly, I can inform the world about the evil committed against humanity in a clear and logical way for the average reader to understand and verify, so that the populace can bring these people to justice for the crimes they have perpetrated against humanity and continue to inflict on humanity. For anyone who has had their intellectual property stolen by the Illuminati as a consequence of the technologies they have used on you unsuspectingly, you will be able to sue and regain monetary reward for the theft of intellectual property as well as invasion of your privacy.

I do not want to get too far ahead, because at this present moment, it is **very important** (I cannot say it enough) that this disclosure spreads (this is the stage we are currently at); it reaches the armed forces; to enable the armed forces to realise the crimes committed against humanity because of these people (the armed forces are kept 'out of the loop'; they just 'follow orders'); the armed forces will have to perform a military coup and bring this people to their knees. This is the point where the ordinary man / woman can have his REM driven cloning experiences restored, (that is if you want to) and sue / rightfully reclaim damages and legal reward for any crimes committed against him or her.

The Meek Shall Inherit the Earth

As you can see if everything goes smoothly; the meek shall inherit the earth. This is why you must maintain your composure and resolve, as I do every single day. You must not riot or cause chaos, damage property or undertake any act which will cause public dissension. The good people of this earth are about to inherit the earth; under no circumstance must you destroy anything. At the end of this currently dire and complicated situation; humanity will inherit the cure for HIV/AIDS, cancer, Alzheimer's, dementia, you name it –many debilitating diseases known to man; and other such wonderful technologies like hypersonic trains which run on magnets and are capable of doing Mach 5 (Mach 5 is the equivalent of 3806 miles per hour or 6125 kilometres per hour; Schneider (1995; 1996) also mentions the availability of Mach 5 trains in his disclosure, back in the 1990s). These trains can be used to deliver foods which are discarded in More Economically Developed Countries (MEDCs) to Less Economically Developed Countries (LEDCs) because these trains can travel thousands of miles within minutes. Yes. The Illuminati have all these wonderful technologies and more, but withhold it, and in turn withhold the progress of humanity. Yes. Plenty of man's problems can be solved when we address the root causes of our problems, and one of the root causes of humanity's problems is: REM driven human cloning which is currently in the hands of evil men. Even REM driven cloning can be used for the benefit of mankind when this tool is in the hands of righteous men. It can be used learn new skills in your sleep: such as gain extra qualifications; learn how to speak a new language; play instruments etc. –so long as memories are not suppressed, you will be able to perform the skills you learned as a REM clone in your original body when you wake up. As you see there is nothing wrong with most technologies; it all depends on the person / people using it. Nevertheless, although they may be beneficial uses to REM driven cloning not yet realised, we must be shut down REM cloning before we can even consider how REM driven cloning may benefit mankind, because at this present moment all that REM driven human cloning is used for is to commit evil, particularly against unsuspecting civilians.

It is OK to feel angry about all these crimes committed against humanity daily. But do not let these evil crimes rule you, in fact, let it motivate you; let it motivate you to the point where you will stand up and speak out to ensure that these crimes end. I think about the children and the future of the world every day; that is what motivates me and I view my situation as a God-given mission to bring these people to justice. I view things this way to maintain my sanity and composure. This is what keeps me going despite the extreme evil I experience, and it helps me to maintain my resolve and composure. The fact that I do not want a single child to grow up in a world, where they are being messed with in their sleep is what keeps me going despite this extreme evil. Some children are even kidnapped and brought to the cloning centre in their original bodies, again to be messed with. This is the root cause of why so many children go missing across the world. I'm sure any rational thinking human being feels the same way I do, and does not want their children, or any child to inherit a sick world governed by sick individuals.

I am a baptised Roman Catholic and a God fearing man. I believe there is a Creator of the universe but the Illuminati tell me there is no God, only science and technology. The Illuminati are also responsible for the death of the young beauty pageant girl Jean-Benet Ramsay; her parents are in this REM driven cloning business. Casey Anthony's daughter; as well as, Casey Anthony (before she died) AND Casey Anthony's parents also attend the cloning centre as REM driven clones. Many others; a man had his wife killed and this was mentioned on the news; it was an Asian woman whose rich husband had killed her; the husband said the wife was responsible for their son’s death. Elizabeth’s response was that “Rich people in this organisation (The Illuminati) do not go to jail, they are covered for.”

Stephen Spielberg and George Lucas are Illuminati members and they willing attend the cloning centre as REM driven clones when they sleep. George Lucas made other Illuminati members light my REM driven clone body on fire for the end of his movie *Star Wars Episode III: Revenge of the Sith* (2005).George Lucas said (as a REM driven clone) he wanted Hayden Christensen “To scream realistically”. Hayden Christensen (also a REM driven clone at the cloning centre) watched me, and listened to my screams and groans of pain and copied the sounds coming from my burning REM driven clone exactly. Hayden Christensen knows he is a REM driven clone when he goes to sleep and Hayden Christensen knows his consciousness is transferred when he reaches REM sleep. Hayden Christensen knows all about REM driven human cloning, and he is a “privileged” Illuminati member. Natalie Portman also knows all there is to know about REM driven human cloning; as does approximately a quarter of the “Star Wars” cast. Many directors have attended the cloning centre as REM driven clones too, and have used me in a similar role playing situation; they have caused me to have excruciating pain as a REM driven clone, to see what kind of squeak or screech I will make, as if I were less than a dog; and when I am a bloody mess on the floor as a REM driven clone; that is when they usually crawl on my broken REM driven clone body and sodomize me saying something like “They love me and they cannot control themselves because I made all their favourite songs and I’m so “special””.

My ribs in my REM driven clone body will be broken, I will have suffered internal bleeding and will be crying or screaming, if I am able, but they just continue to sodomize me, and videotape such a depraved act of wickedness so that they can view it again like “evil pornography”.

The REM driven cloned children, who have their consciousness transferred while they sleep at home in bed, in their original bodies, need a familiar face to talk to as REM clones or all they do is scream and cry at the cloning centre; that is where Joy Geizer comes in. Joy Geizer is married to my half brother from my father’s first marriage; Joy Geizer is a REM driven clone girl guide leader, and when the Illuminati clone young girls, Joy Geizer speaks to these REM driven cloned girls; Joy Geizer keeps the REM driven cloned girls calm and “pimps” them out for free, knowing that these young girls will have their memories suppressed, and therefore they will not remember the experience and will not talk about it when they wake up. All the Geizers are in this REM driven, human cloning business; there are many people who remember these REM driven cloning experiences in their ‘awake state’ and in their original bodies who could be polygraph tested by independent polygraph testers. The police, and polygraph testers in my City of Halifax, Nova Scotia are compromised (they attend cloning centres as REM driven clones too); they cover up for child molesters and therefore cannot be trusted to fairly administer a polygraph test; as I said, commissionaires and C.S.I.S are heavily involved. All it would take is a few polygraph tests to prove these things unequivocally, because for those of you who have ‘eyes’, you can already see that REM driven cloning is real, and that this is actually the way of the world. I will take these polygraph tests publicly too, and demand that my mother and step father submit to them. They have told me, they **wouldn’t** even attempt to lie on a polygraph.

Human cloning, particularly REM driven human cloning, is one of the absolute truths of this world; hidden from the world for over 70 years. My life and the freedoms of many, many people, including the reader (you) depend on this disclosure. The Illuminati say that the world finding out about REM driven human cloning will set the stage for the end of the world; people panicking and destroying property because of the evil these people have committed, but as I've said: prove them wrong, because we are going to inherit the earth, so there is no need to riot or cause public dissension. There will be no end of this world; just the end of the crazy Illuminati people. They always like to think and behave so negatively, don't they? *Sigh*. Furthermore, the whole talk about 2012; December 21st 2012 and the end of the world Mayan Prophecy; that was really about the world finding out REM driven human cloning, and the sick and sadistic nature it has been used for by these sick and sadistic people. Under no circumstance must you riot; you **must** prove you are better than these savage barbarians. I'll say it again, **because it is important**: we are going to inherit the earth, and therefore the smart and right thing to do, is not to destroy anything, especially the earth which you shall inherit.

Furthermore, I hope you are beginning to understand that the good people of this world must bring these people to justice and stop their wicked ways. I sincerely wrote this disclosure so that the good people of earth would be empowered to put a stop to their wicked ways. I wrote this disclosure to empower the good people of earth against tyranny and not so that the world would end. Therefore you must understand that the downfall of these Luciferians (Illuminati) must progress smoothly, because unless you have been to the cloning centre as a REM driven clone and retained the full memories of your experience, it is difficult to understand the level of depravity and sub human cruelty; it is beyond anything that has ever been heard of, and there is much more to tell.

Ignore this disclosure and you will condemn me to a horrible eventual death and you will encourage them that 'they are all 'powerful''. This is not an exaggeration. There is no need to exaggerate even President Barrack Obama is involved in the REM driven cloning business and attends the cloning centre as a REM driven clone version of himself, when he goes to sleep. He and his wife Michelle Obama attend these REM driven clone gatherings. Barrack Obama has even told me as a REM driven clone, at the cloning centre "Donny, we're all powerful. You are a slave and the people here [as REM driven clones at the cloning centre] won't speak up for you for fear of torture or death. Now make us a new song or we'll gut you like fish and leave you to writhe in agony!"

Be Wary of: Shills; Trolls; Disinformation Agents and Double Agents

There are many, many disinformation agents whose aim it is, is to denounce or debunk me. Be very wary of them. They DO NOT, and cannot debunk me, because after all, everything I have disclosed is truth. Although the truth concerns highly advanced concealed technologies, so it is a bit difficult to fathom at first, but keep reading, and you will realise that all which I have disclosed is true. Be very wary of the disinformation agents.

The most common thing these people say is that "Donald is a paranoid schizophrenic" –yet, ask them to detail the ins and outs of what a paranoid schizophrenic is and what specifically qualifies Donald to be a 'paranoid schizophrenic'; there is a high probability they will not be able to explain this to you, logically, sequentially and methodologically. Their main goal is just to make it as difficult for newcomers to understand what the real truth of this world is and as I have disclosed; and one of the root causes of man's problems is REM driven cloning.

Some disinformation agents are paid by the Illuminati, to behave this way, and are all too happy to echo empty statements (without any substantial evidence for their claims) because it provides them with a pay check. I will provide the following reference for the reader which discusses the signs and symptoms of a paranoid schizophrenic; all for the express intent for the reader to further understand paranoid schizophrenia. You can read more about paranoid schizophrenia on Medical News Today (2015). The link is provided in the reference section. You are welcome to read my Facebook wall and within days, you will realise I converse with others quite naturally. You can also ask individuals who have spoken to me through Skype or met me; but if this is not a viable option for you; all you have to do is read my Facebook wall and within days, you'll see that whoever makes such harsh and untrue remarks on my character is in fact a disinformation agent.

Furthermore, remember we live in a 3D **physical** world; and there is always a physical aspect to how something manifests. Therefore, when you hear others discussing concepts such as 'Tila Tequila demonstrated an 'energy ball' right on camera; Why didn't Donald discuss that?!' Please understand that these people are trying to deceive you with misinformation. There are also professional disinformation agents to be wary of. I do not perceive anything extra-ordinary in the world when I am awake in my original body beyond the five senses. I don't see orbs, auras or anything of the like. All I will ever discuss are practical things which have been unequivocally proven to me as fact; because in the situation the earth is currently in, I cannot afford to speculate.

Contact Information

My Facebook is: https://www.facebook.com/donald.marshall.148
You can also press Ctrl+Click (hold "Ctrl" on your keyboard and left "Click" with your mouse, on the image to your right).

I have a public wall on Facebook which starts from March 2012. In other words, all posts are made public since March 2012 and you do not have to join my friends list or subscribe me to see what I post (although you will have to have a Facebook account). I suggest that newcomers start reading from March 2012, and be patient, and read everything. You can read everything and learn the real truth of the world free of charge. I don't wish to write a book, I am not looking to turn a profit from this; I want to crush these guys and shut down the cloning centres!

It also worthwhile to add that: I am **not** asking for donations. I do not want **ANY** donations. Ever! These disclosures are far more important than any donations. This is **NOT** my job. I have a job. I am an independent contractor; carpentry is my trade and I earn a living this way. If you sincerely want to help; the best way to help is to spread and share my disclosures. That is all I ever ask for, so that eventually, the world knows about REM driven human cloning, and the armed forces can bring these people to their knees. **That is all I want; spread, spread, and spread this disclosure.** I will **never ever** ask for donations. Ever! Please keep this in mind, and anyone who asks for donations in my name or on my behalf should not be trusted. I, Donald Marshall, will **NEVER EVER** ask for any donations. I hope that is well received.

You can also view Proboards which has all my Facebook posts and have been archived by Celine O'Carroll and Astral 7ight by visiting:

http://donaldmarshall.proboards.com/
You can also press Ctrl+Click (hold "Ctrl" on your keyboard and left "Click" with your mouse, on the image to your right).

There is a search function on Proboards, and you can use this to search for and read all the disclosures I have made regarding REM driven clones, the people involved and more. I understand that it is human nature to want to know, which people have been to the cloning centre as REM driven clones; therefore, use the search function to read about any public figure which I have already covered that you have an inkling about. You can also post anonymously on Proboards and Celine and other Administrators will transfer your question onto Facebook which I'll answer.

Donald Marshall Revolution is a website which details a brief overview of the Illuminati.
http://donaldmarshallrevolution.com/
You can also press Ctrl+Click (hold "Ctrl" on your keyboard and left "Click" with your mouse, on the image to your right).

DONALD MARSHALL
REVOLUTION

Interviews

You can listen to the radio interviews I have done. Listen for consistency; particularly anything which you do not hear me, pronounce clearly for the first time; the best thing to do is to pause the recording at that particular point and replay it. You should also research the statement you do not understand. Sometimes reading helps comprehension a lot faster.

One of the main reasons you should pause and replay the recordings is because: the truth has been kept hidden for so long that a lot of what I discuss in my interviews are beyond most people's current world view; so at some points I may speak too fast for you; my audio/ microphone may not be so clear so you may miss what I say etc.

A friend has told me that when he first watched the Vinny Eastwood interview; he did not hear me say the word "scars" (When Vinny asked: 'How do I know I'm the real me?') although he replayed that particular point in the video 8 times. Everything was just beyond his current comprehension, at the time. No matter how many times he replayed that part he really could not hear me say the word "scars" –so he let that part go, and played the rest of the interview, pausing, and replaying points which he did not understand, especially to comprehend whether I was talking about my original body or my REM driven clone duplicate body. He also listened to all my interviews for consistency, to note any 'slip ups', or any parts of my testimonies which do not 'add up'. He would listen to all my interviews, pausing and replaying parts he did not understand and he would reserve his judgements until he felt everything I was saying was for example as ordinary as: 'I woke up today, brushed my teeth, and took the dog for a walk'. He was also patient to realise the truth. After listening to my interviews he would just let it 'sink in'. A week later he would come back and listen to the same interviews, to test whether his comprehension on the topics I discuss has improved, and whether he can understand what I am saying without having to pause and repeat at certain points in my interview; and soon enough he could now hear me say “scars” at that particular point of the Vinny Eastwood interview. He had reached the point where all topics I discuss sounded to him like I’m saying everyday common place stuff that people have heard, such as: ‘I woke up today, brushed my teeth, and took the dog for a walk’. For anyone who may struggle to understand the topics I discuss: I strongly recommend you take the above approach as my friend did; soon enough, you too will realise the real truth of the world like he has: REM driven cloning, kept secret and used for sinister purposes.

I cannot say the following is true for everybody, however, an unproductive venture a complete newcomer can do is to listen to my interviews first time, all the way through, without pausing or replaying parts which they do not fully understand; If you do this and if there is just a single part of my interviews which does not make sense to you; this will interfere with your understanding of the entire interview. Remember, all I am discussing is technology, thousands of years advanced compared to what you currently use; available today, hidden and secret. If things start to get too complex for you, reduce it to its bare minimums: (advanced) science and technology. I hope that helps.

Another thing which I do in my interviews, that friends have picked up on, is: -because REM driven cloning has been my reality for many years; I don’t differentiate between my original body and my REM driven clone body. I just say: I did this, I did that, and Elizabeth did this and that, therefore it can become very confusing for newcomers. Please bare with me; although I’m more emotional as a REM driven clone, and not as smart as I am in my original body (this is a side effect of cloning: REM driven clones are more emotional than normal, and dumber than they are in their original bodies) I’m still “me” when my consciousness is transferred; I have all the experiences and knowledge which makes me, “me” and therefore I naturally do not differentiate between my REM driven clone version, and my original body as an outsider discussing these concepts would. I understand it helps comprehension so I have painstakingly done this throughout this disclosure.

I hope this helps; and I hope this helps to better understand my disclosure as well as the interviews which I have done. On the next page you can find the links to my interviews. You can copy and paste the links to your web browser or press Ctrl+Click – (hold “Ctrl” on your keyboard and left “Click” with your mouse, on the images below) to direct you to the interviews.

Links to Donald Marshall Interviews

Vincent Eastwood

Copy and paste the link below to your web browser.
https://www.youtube.com/watch?v=M_1UiFeV5Jg&ab_channel=VincentEastwood
OR Press Ctrl+Click (on the image below) to follow the link.



Jeanice Barcelo

Copy and paste the link below to your web browser.
https://www.youtube.com/watch?v=3uzgu4ekT3c&ab_channel=JeaniceBarcelo
OR Press Ctrl+Click (on the image below) to follow the link.



Lisa Phillips (CFR)

Copy and paste the link below to your web browser.
https://www.youtube.com/watch?v=UonnFuHLJKc&ab_channel=Astral7ight
OR Press Ctrl+Click (on the image below) to follow the link.
Listen to parts 1 through 8.

Donald Marshall
1st Part Of Interview
April 11, 2013

Radio Presenters –Contact Donald Marshall

Anyone who sincerely wants to contact me for radio interviews on their show is welcome to do this. Please contact me through Proboards by leaving a message for me to contact you.

Professionals who understand "Consciousness Transfer" –Contact Donald Marshall

Any neuroscientists, engineers or professionals who understand how consciousness transfer works, and can provide me with a detailed methodology of how to block the consciousness transfer to my REM driven clone; please message me on Proboards, and this will be greatly appreciated.

Email

I currently do not have a contactable email address. In my original disclosure, the email address has been compromised (hacked), and so has any other email accounts I created: Yahoo, hotmail, Gmail, AOL etc. It doesn't matter; they eventually get hacked; for whatever reason, the Illuminati do not want me to have an email account.

How to Learn More about Donald Marshall's Whistle Blowing Disclosures

The best ways to learn about the truth of the world is through my Facebook page and Proboards. There is a mountain of evidence which has been collated over the years, and corroborates all that I have disclosed here. I also understand that for some people it is impractical to read three years worth of Facebook posts, especially when some post are repetitive; contain unnecessary comments from trolls, shills and other disinformation agents. Therefore, I am currently compiling 5 documents which should make it easier for others to read and understand everything quickly; as well as, for others to share and spread those 5 documents including this main disclosure document –so 6 documents about the real truth of the world. All for free!!

These documents include:

- "Frequently Asked Donald Marshall Questions" –This will contain all the general FAQs which I have been asked over the years; all in one place.
- "Experiences from the cloning centre" –This document will contain the full disclosure of my REM driven cloning experiences from the cloning centre when I go to sleep; all in chronological order.
- "List of people to avoid" This will contain a whole list of trolls, shills, and disinformation agents and double agents in alphabetical order, to avoid at all costs, in real life and online; -all complied in one place; and the reasons why they should be avoided.
- "Public Figures and their relationship with Donald Marshall as REM driven clones" – this will be a complete list of every public figure I have ever come into contact with as a REM driven clone; and you will be able to read about all the public figures I have met as REM clones, as well as the experiences, all in one place.
- "The subterranean underground colonists: The Vril" –this will be everything about the biological parasites the Illuminati harbour. Yes. The Illuminati harbour biological parasites, which they use against unsuspecting humans. I told you the Illuminati were

> the biggest depraved perverts ever to grace God's earth. REM driven human cloning, kept secret from the world for over 70 years is difficult to fathom as it is, as are these biological parasites. These parasites are also one of the main root causes of humanity's problems here on earth, and must be rendered extinct. In this document you will be able to learn everything about their, strengths, weaknesses, psychology, biology, ecology, sexuality and arm yourself with knowledge which ensures that humanity exterminates these parasites from our earth, forever. The secret of Vril; a secret no more!

I hope after reading my eye witness statements presented in this document that you have now began to understand that this is simply what is happening in our world today.

Heed my disclosure, very diligently. At the start of my disclosure I asked the reader to do two things:

1) Give me the benefit of the doubt –because there is nothing worse than being a victim of abuse, reporting it and the people who have the power to stop it, ignore you;
2) Set out on a genuine quest to debunk my disclosure. I understand that for some people, plenty of what I have disclosed will still sound 'too out there' beyond their current scope of reality to be believable. For such people, the honest thing to do is to start with the first topic which you do not fully understand and explore it, either by finding that corresponding topic on Proboards (Donald Marshall Proboards 2015), and continuing your research from there; or just Google any topic you currently do not understand and review the topic on websites such as New Scientist (2015), Gizmag (2015), Motherboard (2015), BBC News (2015a; 2015b), BBC Future (2015), The Guardian (2015a; 2015b) The Independent (2015a; 2015b), Daily Mail Online (2015) and start reading more articles in the Science and Technology columns because these people have been telling you what they have been doing for decades. Consequently, keep in mind that articles which discuss 'future' technologies and 'improvements' in medicine or science, are articles, which are **really** discussing present technologies, and achievements in science and medicine already realised; because most of these achievements have been realised decades ago. It just hasn't been fully disclosed publicly.

I have also saved and backed-up every reference (except the homepages of the websites referenced) in this document; therefore if a link or video is ever deleted let me know.

How Much Do You Know About Post-humanism / Trans-humanism?

Furthermore, you have to be honest here: because if you do not know much or anything about post-humanism / trans-humanism then I am afraid to say, -and this is no fault of yours – that you are behind in this the world; simply because these Illuminati people are Post-humanists; and that is the direction the want the rest of the world to go. They want the world to reach a destination where human cloning is common place; a world where downloading your mind / entire life experience onto a computer microchip and living on as a cloned version of you with the microchip running the consciousness to be common place; and these Illuminati Post-humanists want the world to head in a direction where it is commonplace to molest children through science and technology. No. This really is not Science-Fiction, this is the world we live in today; this is why such marvels in science, medicine and technology has been withheld from the general public and kept hidden by an 'elite' group of people because if these people honestly came forward, and said “We have invented this technology and we want to use it for this “negative” purpose” –the populace would not accept it, and these people will be lynched in the streets before lunchtime. Therefore, through concealed advancements in medicine, science and technology, the Illuminati can live out their inner depraved cravings and commit crimes against humanity and the world, for which most people will be too blind to see or even fathom, because the hidden science and technology is beyond the average person’s current comprehension.

Therefore, please attain an education in post-humanism / trans-humanism because these Illuminati people believe they can rival creation, nature and the marvels of the universe through science, medicine and technology. The Illuminati go **against** creation; they go **against** nature; and they go **against** humans. They don’t consider themselves humans. They consider themselves post-humans and believe they can become “gods” through advancements in medicine, science and technology. See LawOfIdentity (2014) and Mark Dice (2014) for Richard Seed’s comments on ‘becoming gods’ through transhumanism. Richard Seed is a Physicist with a Ph.D. from Harvard University; he is well known in the controversial cloning debate and declares his aspirations to "become god" saying 'We are going to become Gods, period. If you don't like it, get off. You don't have to contribute, you don't have to participate, but if you are going to interfere with me becoming a God, you're going to have trouble. There'll be warfare.' If you value humanity, do your best to attain an education in the trend of post-humanism / trans-humanism; otherwise the future of mankind will be bleak. We must do everything we can to stop these people.

This is of uttermost importance. REM driven cloning of is the most terrible thing in the world, especially when it involves unsuspecting civilians, and worst of all, innocent children. If you choose NOT to do anything you allow the Illuminati to continue to clone your children, sisters, wives, and sons. You allow the Illuminati to continue to hijack the minds of your children, sisters, wives, and sons while they sleep, through concealed advancements in science and technology. You allow the Illuminati to transfer the consciousness of your children, sisters, wives and sons to their REM driven duplicate clone versions while they sleep, whereby the Illuminati molest your children, sisters, wives and sons, which will cause them to have learning disabilities, unexplained depression and suicidal thoughts, as well as all kinds of side effects.

This IS your ONLY chance to end these monsters. There is a deadline!

This is your **ONLY** chance to do something to end these monsters. We are on a timeline and there is a deadline. As I have already mentioned, as well as, the top scientists in the field of physics and geophysics have mentioned: HAARP is not only capable of controlling the weather; once the HAARP grid is completed and working at full power, it will be capable of mind control over entire populations. We will all be slaves to the Illuminati FOREVER. Our freewill will be gone forever. Furthermore, if they achieve their aim of time travel with HAARP technology, future generations of humanity will never be able to stop them, because as they have told me: ‘They will always be able to go back to a previous time, and correct the mistake(s) which led to their downfall’. This is the Illuminati’s end game and what they wish to achieve. This is why this disclosure is so heavy, and so important. It goes beyond REM driven cloning; although it is important the world understands REM driven cloning. The future of humanity is at stake; and because of the 2-5 year deadline until the HAARP grid is completed, it is time humanity stood up and brought an end to the Illuminati. This REALLY is your ONLY chance to end these monsters!

The only way for evil to triumph is for good people to do nothing.
Edmund Burke

Remember for every 12 months which passes military / concealed technology outstrips the technology the general public is accustomed to by 44 years (Schneider 1995; 1996). Close your eyes and think 44 years into the future. The year is 2059. What kind of technologies do you expect mankind to have? Do it for real; don't just read the words. Close your eyes and imagine. The year is 2059. What kind of technologies does mankind have? You see. It is 'out of this world' technology, right. This is exactly what is going on today in the year 2015. It's just that it is hidden. That's all. Not so difficult to fathom now.

Do NOT Be Afraid to Help. We Outnumber the Illuminati by 1,000,000:1

Don't be afraid to help. These people are easily defeated when good people stand together as one. These Illuminati people total no more than 10,000 people. 10,000 people against 7,000,000,000 (7 billion) people –that's less than 0.000001 % of the world's population. Now can you begin to understand how prevalent evil can be when a small organised group of individuals, as little as 10,000 of the world's most evil and tyrannical people all work together in unison to exert their influence over the world? The world does not have to be this way. We outnumber the Illuminati people by a 1,000,000 to 1. For every Illuminati person there is, there are **one million** people who are not Illuminati, therefore do not to be afraid to help; all you will be doing is helping humanity rid itself of its sickness. So please feel free to share and spread my disclosure far and wide.

For those of you whom this applies to: remember the Illuminati (and I know it sounds ridiculous despite the evil they do) are deeply religious. They believe anyone aiding me is part of the "Army of Light" prophesised by Nostradamus; and to harm or degrade the life of anyone assisting me will bring them to their ultimate end and they will incur the wrath of God; they will suffer utter ruin and demise in their lives if they are to hurt you; they are very scared of people who can see through the lies and deceptions they have inflicted on the world. So please, stay calm, do not stress your heart, and know that **you are safe**, and **they cannot hurt you**. You can feel safe in the knowledge that you can do the right thing by helping me. They told me this as REM driven clones on the night of 21st of February 2014 when I went to sleep. The above is exactly what they said.

For anyone interested in understanding the interpretations of the Nostradamus Prophecies, Crystal Links (2015) provides a good source for all 942 of the quatrains. Delores Cannon is also an author who has written three volumes called "Conversations with Nostradamus" and for anyone interested you can read these online (Galactic 2012a; Galactic 2012b) as well as watch her YouTube videos (CreativeForceVideo 2014; Disclose TruthTV 2015).

Yes. This is the state of the world today: a deception within a deception coated in reverse psychology; and fact is indeed stranger than fiction. Now after everything I have said, if you are still sceptical and 'in-between' on this issue then the best thing for you to do is to pay attention to your dreams; or lack of dreams –they are your own experiences and you cannot deny your experiences.

In other words, you may be having REM driven cloned experiences too; for some people they have a ‘dream’, where they are in the same environment, over and over and over again; or the theme being discussed in their ‘dreams’ is the same over and over and over again; or the environment their ‘dreams’ take place always appear to happen in the same 3 or 4 environments over and over again –no matter what the theme is. In each scenario there is a likely probability that these are not just dreams, and in fact these people have had their consciousness transferred to the REM driven clone duplicates and the Illuminati is trying to extract something from them, once that is done they implant a false memory (See Kim (2013) and Alford (2015) for discussions on how false memories are implanted) so you wake up with the feeling of remembering something, but in actuality it is false; or you wake up with no memory of dreams from the previous evening, which means there is a high probability that you had your memories suppressed when your consciousness was transferred to your REM driven clone. This is why I say you can be sceptical about everything I have said (for now), but pay attention to your dreams, or lack of dreams, they are your own experiences, and you cannot deny your own experiences.

Noteworthy Frequently Asked Question

A Frequently Asked Question I receive, which is worth a mentioning here, is as follows: **Q:** Donald, if everything you have said is true...; in other words human clones walk among us now in a multilayered conspiracy which reaches the highest levels of government; armed with this knowledge what does one do exactly? What happens now, Donald? You obviously want to spread the word and make people aware but to what end?

DM: In short: I want to bring a complete end to the Illuminati and usher in a “Golden Age” of mankind. This question is best answered by detailing my ‘Mission and Vision’ for ending the Illuminati completely.

Donald Marshall’s Mission and Vision on How to Bring Down The Illuminati

- This disclosure must spread, and **spread FAST and FAR!**
- If you now understand everything I have disclosed in this document as truth, then do not waste any more time. Share this disclosure with your wives, husbands, brothers, sisters’ aunties, uncles, friends, co-workers, and children. We all have a part to play in saving the world from a premature doom.
- Call friends who have not heard from you in a while and tell them you have important news to share. Share this document. Share it on social media such as Facebook; Twitter; Instagram; Dropbox; Slideshare etc.
- Keep sharing this document until it comes to the attention of the Armed Forces. The Armed Forces will have to intervene. Once the Armed Forces intervene we will have reached the middle stage of this vision and will be witnessing a complete end to the Illuminati. Until then, we’re in the beginning stages, so please; spread this document faster and further. The quicker it is spread; the quicker the Illuminati are ended.
- Once the Armed Forces have intervened a Military coup can be orchestrated against these vile people.
- Cloning centres can then be shut down once these people are overthrown.

- The freeing of any missing people (children; teens; adults) trapped in the cloning centres can commence (once the Armed Forces intervene).
- HAARP (as well as other highly advanced technologies) can now be contained and not used for adverse effects against the world (once the world learns of this disclosure).
- These Illuminati people will then HAVE to appear in court for their crimes against humanity.
- Suing the Illuminati members in court (once court proceedings commence... we will be past the midpoint of my vision, and closer towards witnessing a complete end to the Illuminati).
- The populace (and it will be your choice) can then have their REM driven clone experiences restored and also sue and claim any legal reward / compensation.
- After the populace has sued the Illuminati for their crimes against humanity; the punishments can commence.
- Punishments will include: imprisonment and executions of these sick and malevolent people. The imprisonment and executions of evil Illuminati members will bring an end to the Illuminati.
- After the punishments and executions; Governments worldwide can now be replaced with incorrupt individuals, worldwide.
- The structure of Governance will also have to change. The reason for this because future generations will always be able to check their leaders and governance more appropriately; so that the depraved and subhuman acts I described can NEVER be committed against humanity again; nor will world leaders be capable of committing such monstrous crimes in such secrecy ever again.
- Ensuring that the laws of the land always progresses in line with advancements in medicine, science and technology; as well as, ensuring law progresses in the directions of Research and Development (R&D) regarding future technologies, science and medicine.
- Release of technologies, science and medicine which benefit mankind.
- Commence a “Golden Age” of mankind.

If you do not fight the corruption and you do not stand up for what is right in life, you end up being a serf and a slave and you are leaving your children a world in which you would not want to live in yourself, so how can you in decency behave that way? You have to stand up for what is right in life, and unless you do that you are nothing.

Aaron Russo

Empowerment by Virtue of Golden Truth

As you can see, despite all the horror of the world I currently present: if everything goes smoothly, the good people of this world, truly will inherit it. This is why despite any anger, sadness, or fears you may have; you must not riot, damage property or cause chaos or bring about any other form of public dissension. You cannot stay silent, or ignore the issue in the hope that the threat removes itself. You are called to act; you must take action to help bring the Illuminati to an end; you must act while at the same time, you must maintain your composure and resolve to ensure that the whole procedure goes smoothly, and we all inherit a world we want to live in.

Your life, **at this very moment**, is more important than you may have probably ever imagined. You have purpose. Through you, and other good people around the world, together we can bring an end to such unspeakable forms of tyranny in this world. It is my humble stance that you have now become truly empowered with golden truth and you are now compelled to bring this tyranny to an end.

Do not waste the knowledge you have obtained from this disclosure. It is my only hope to escape this man made living hell. It is my only hope, as well as, the hope of many REM clones imprisoned there, as well as, real people who go missing daily, and are trapped in the cloning centres.

We sincerely beg you.

Donald Marshall

Appendices

Appendix A: Thien Thanh Thi Nguyen (Tila Tequila) Transcript

Link: https://www.youtube.com/watch?v=7mRZ7ItF9ls&ab_channel=Astral7ight

00.00 – 1.10 min: You know what... since you f****** with my program darling Queen Elizabeth [II] and the paedophilia ring and the cloning centres, and the cloning centres. That's right darling the cloning centres. Parents listen to me right now, they are blocking me but that is quite alright. They are blocking me but that is quite alright. Because I have many, many other forces; I shall not say their names right now, but I have many big plans to expose all of you disgusting, sadistic f***s! Okay? That is all. I shall save that for another time. But, however, I shall REPEAT: that was just an introduction to the reptilian family, leading all the way back. They call themselves the "The Black Nobility". Now that is just one part of it; alright?

1.11 -2.47 min: The Black Nobility; the reptilian family; all the way back from ancient times; so which they think... they feel like they are the divine chosen ones... from whom may I ask? Definitely. Definitely not God. Our creator of the world. Reptilians: they feed on blood; children; the paedophilia ring; recently busted. Oh! It has been going on for centuries. Parents listen to me carefully. I don't care if I'm cutting out. I will continue this and I am not alone on this battle. Believe THAT! Believe THAT! I am not alone on this battle. I started out alone but I am marching on with MILLIONS; okay? So sit your old a** down okay. Because you are gonna roll over, but it doesn't matter anyway because you are all ancestral f***s! Who interbreed... ancestral f*****g... and then... and then... Oh! Only going to talk about cloning those children and... oh! And all those many children's parents listen to me carefully.

2.48 -4.24 min: Hundreds of missing children come up every year. You wonder... why? How? How could this be? And then there is so called CPS [Child Protection Services] or whatever they are called; they come and take your children, just, just for nothing; right? Not to discredit everybody, because not everybody is bad. I'm talking about the bad people. And they take your kids... they take them as this... they treat them like... I can't even say the word. It's disgusting, it's sadistic. They... they... they take your kids... they toss them out like little [inaudible] cause they are so f*****g... Pardon my French, but then again when I'm dealing with these evil cum-buckets I have no holy words coming out of my mouth, because these are the only words they resonate to. So therefore that's how I refer to them. Because they can only [inaudible] ...their masters whiplash on them with these [inaudible] words of cursing, vileness and slaving and that is not what the true God is; okay? The God of Hell...; Anyways...

4.25 – 5.30 min: There are these CLONING CENTRES where they take your children and do sadistic things to them. I'm not even talking about child molestation here; not to mention; uh there is one of them that got caught, flying out to Florida; to meet up with a four year old little girl, to have sex with a four year old girl. That's right. Google it because it is so highly sinful... We have commercials about... you know starving kids; you know save the starving kids and it is heartbreaking. We can have commercials about it... why? Because it is a horrible thing and people can have commercials about it. WHY do we not have commercials about... 'Daddy please don't, don't. Mommy please don't let daddy let daddy touch me?' – because it is disgusting! It is so disgusting; beyond sin that no one, NO ONE, can even make a commercial about that because that's how sinful it is.

5.31 – 7.19 min: Do you understand that? Do you understand how sinful that is? These people, I'm not even going to call them people; alright? They take your children; they not only molest them; men f*** them and make them shoot each other. They give them guns. It's either you shoot him or I'm gonna shoot you. They are... mind you, they are children. Children. Yes. I'm speaking out, because I... uh! Who else is doing this? You're all just [inaudible]... shame on you... And actually the most recent paedophilia... got taken down... WOW! How long did that take? Really?! Do you know how long this has been going on? *Sigh* Alright I'm gonna calm down... but as a parent and I love parents out there. My heart goes out to all the parents out there who have missing children. You know, we all pray for them; every day. And I put on a bold face in public every day; because there needs to be someone strong, believe that. But my strength comes from somewhere... that I have a very vulnerable emotional side where I feel very strongly for these children and innocent people. So therefore I want to speak out.

7.20 – 9.10 min: I have and I have my passion too; and in the end you shall all know why I am so passionate about exposing every single one of these scumbags; okay? The truth shall prevail and you all will know why. So, as for you parents... ah... there are no words to describe. But let me just expose because you can't just... there is a point where you CANNOT just turn the other way. You know this stuff is going on; and you go 'Oh well... that's their problem. Let's just turn the other cheek.' How long are you going to turn the other cheek, until it happens to your own freaking children? When, when, when your own child; three years old, get's run out [kidnapped] and gets blasted right in the head with a gun... yeah... there's more to that people; okay? And I'm not just saying that coming from some... I mean, actually, mothers, fathers out there... If you found out... I'm sure you would do way worse than what I am just saying. I'm just using voc. I'm just annihilating them vocally. I'm sure the parents out there who find out what their children have gone through, their missing children. I am pretty positive more than just a vocal annihilation of these scumbags that do this to your children; okay?

9.11 – 10.32 min: So keep on turning the other cheek folks. Hey, go and turn the other cheek; you are with the others. I am not. I AM NOT. Like I said you... There is only two ways to go about this: you're either with us: the good guys, or you're with the others. There is no in-between. Cause if you are in-between, hiding like cowards, turning the other cheek; doing whatever; well then you are a freaking coward and you are just a sheep. And sheep end up dying because you know what you are owned by "The Others". So pick one: you're either one of us: the good guys or you're part of the others. That is simple as that! Two choices: good guys; bad guys. In-between you're dead because the bad guys are going to suck your soul out [transfer your consciousness to your REM driven clone] and do some sadistic stuff to you and watch, and make you watch while they pretty sadistic stuff to your children as well.

10.33 – 11.33 min: Do you know why they love children? Because they are innocent souls; they're innocent... they're, they're the most innocent pure beings in this planet. They're not harmed by anything. They're new to the world; bright-eyed pure innocent children. That is why these disgusting paedophile and these clone rings; cloning centres; satanic rituals; Brownsville Texas... There are many other cloning centres where they take your children that go missing. And you wonder why? What happens to them? I'm sorry to break this to you but that is what happens. Now either do you want to know what happens to them or do you want to turn the other freaking cheek?

11.34 – 13.09 min: Tune into my next show. I'm gonna upload stuff; I have an arsenal ready to blow up! Okay. And I have reason behind this. You all should know my personal reason soon; but this has nothing to do with me right now. But know that I'm back, I'm back with a vengeance and I'm back with an army full of people around the world who are sick and tired of treated like animals; or quote, unquote "COWS". We all know what that means. For the outside world (the masses) we all know the term "sheep", sheeple. But for the insiders we know what the cows are don't we? You know what "The Others" like to do with the cows, right? They start to herd you in... and to... yeah...I'm gonna end it at that. And to all the parents, families and children out there, I love you so much. I... have to maintain composure, because that is what I do. That is all. Over and out.

Appendix B: MK Ultra

MK Ultra *-noun:* [Manufacturing Killers Utilizing Lethal Tradecraft Requiring Assassinations] The goal of mind control, using MK Ultra technology is to program an individual to carry out any task against their will and self-preservation instinct, and to control the absolute behaviour and thought patterns of the individual.

.

Modern-day MK Ultra involves an implantable microchip which is inserted into a Mark 2 clone of the victim. Every thought, reaction, hearing and visual observation causes a certain neurological potential, spikes, and patterns in the brain and its electromagnetic fields, which can now be decoded by the implantable microchip into thoughts, pictures and voices. The thoughts, pictures and voices of the implanted Mark 2 clone (victim) can now be displayed visually and heard on any system capable of converting visual images, such as a television or a computer. These images are usually displayed on a giant screen at the cloning centre.

The purpose of MK Ultra is to elicit a specific conditioned response in a victim (desired by the programmer) to an otherwise neutral stimulus. In other words, through the process of "classical conditioning" (which involves learning a new behaviour via the process of association. In simple terms two stimuli are linked together to produce a new learned response in a person) the implanted Mark 2 REM duplicate clone (victim) is placed thorough many similar recurring scenarios which are experienced (or perceived) by the victim as "real", because the programmer manipulates the victim's audio and visual field, and continuously pairs the victim with the neutral stimulus, so that either a positive or negative conditioned response is elicited in the victim towards the neutral stimulus.

In other words an implanted victim can be placed in many recurring situations deemed as frightful, where a mystery stranger saves the victim from the frightful situation over and over again. The victim will now have positive associations towards the mystery stranger and therefore the conditioned response is now one of 'positive associations' (towards the mystery stranger who did not elicit such a reaction before).

MK Ultra techniques are administered through Mark 2 (sleep driven) clones. In other words classical conditioning happens when the person sleeps. Memory suppression technologies are also used in conjunction with MK Ultra technology, which enables the programmer to control certain memories the victim remembers. The use of memory suppression technologies and MK Ultra technology allows the programmer to reinforce behaviour and elicit specific conditioned responses (in an original).

Therefore, in our example above, when the original meets the mystery stranger in real life, the original (victim) will be predisposed to the mystery stranger and automatically 'feel safe' around this person and may even believe that he / she should 'date this mystery stranger' – depending on what was programmed; because the victim was conditioned to elicit such an emotional response towards the mystery stranger in his / her sleep as a Mark 2 REM driven clone through MK Ultra functionality.

MK Ultra can also be used to create zombified individuals who are programmed to murder and remember nothing of their crime afterward. MK Ultra (technology) can also be used to disrupt the memory of the original, discredit people through unusual behaviour, make the person insane or commit suicide and murder.

MK Ultra has much functionality. Furthermore, because of its video and audio projection functionality, MK Ultra can also be used to compose music. MK Ultra is capable of relaying the Mark 2 REM driven clone's subconscious and conscious mind as visual images and audio, projected onto a screen. Therefore thoughts, pictures and voices which have been experienced consciously and subconsciously in one's life can be displayed visually and audibly on a television or computer screen. The Mark 2 clone now has the option of harmonising these thoughts, pictures, and voices into a coherent order which produces music through the thought process of his or her imagination. See Jim Cristea (2009); Berkeley News (2011); UC Berkeley Campus Life (2011) CTForecaster (2013); nature video (2013) and Stromberg (2013) for examples and discussions and the capability of MK Ultra technology.

Appendix C: The Illuminati

Illuminati *–noun:* A modern-day criminal organisation operated by reprobate (depraved, unprincipled and wicked person) criminals. Their main agenda: is to enslave the whole world through advanced concealed technologies.

Today's Illuminati trace their roots back to Professor Adam Weishaupt who found the Illuminati on 1st May 1776. Since the inception of the Illuminati the intent has always been, and remains: "to bring about a NEW World Order that writes God out of the picture and deifies (glorifies) Lucifer." This intent is still prevalent today. The following excerpt is derived from A. Ralph Epperson (1990) *The New World Order:*

> Weishaupt was a teacher of Cannon Law (law governing the affairs of a Christian Church, especially the law created or recognised by the Papal authority in the Roman Catholic Church) at the University of Ingolstadt in Bavaria, now part of Germany.
>
> He even told the world, in his writings, where he would conceal the Order: "None is fitter than the three lower degrees of Free Masonry; the public is accustomed to it, expects little from it, and therefore takes little notice of it." He felt that this secrecy would lead him to success because he felt no one would be able to break into it. He wrote: "Our secret Association works in a way that nothing can withstand ...."
>
> Weishaupt accepted the fact that all secret associations and secret orders had two doctrines, one concealed and reserved for the Masters... the other public ...." and the Illuminati was [and are to this day] a secret society with two doctrines.
>
> Professor Weishaupt, its founder, boasted of his organization's secrecy. He realized that this secrecy would enable them to decide the fate of nations and because their deliberations were secret, no outsider could interfere. He wrote: "The great strength of our Order lies in its concealment; let it never appear in its own name, but always covered by another name, and another occupation." Weishaupt later wrote about that secrecy in a letter to a fellow member of the Illuminati: "Nothing can bring this about [the new world order] but hidden societies. Hidden schools of wisdom are the means which will one day free men from their bonds [the "bonds" of religion] Princes and nations shall vanish from the earth." So the secret societies were created to bring the world to the new society known as the New World Order. The members of these organizations obviously feel that their goals are so noble that they may perform whatever tasks are required of them to bring that goal to fruition. This means that murder, plunder, and lying all become acceptable as long as these methods assist its members in obtaining their goal.
>
> Adam Weishaupt, the founder of the Illuminati, wrote over and over and over again, that "the ends justified the means." Weishaupt also told initiates to use whatever means, which included murder, to achieve the goals of the association that he was joining. And that the major goal of the Illuminati, was the destruction of all religion, including Christianity. That meant that if Christians physically stood in the way, they could be removed by simply murdering them. Weishaupt even went so far as to say that anyone not willing to take the life of another was unfit to join the Illuminati. He wrote the following in a letter to a fellow member in 1778: "No man is fit for our Order who is not ... ready to go to every length ...."
>
> Another reason, that Weishaupt felt that the Illuminati would succeed, was the fact that he was offering his members worldwide power. He felt that this inducement would enable him to draw into his organization only those who would do anything to satisfy that desire for power. He wrote: "The true purpose of the Order was to rule the world. To achieve this it was necessary for the Order to destroy all religions, overthrow all governments and abolish private property."

> But his religion had a different base than the traditional religion: his was based upon a worship of reason: "... then will Reason rule with unperceived sway." "... Reason will be the only code of Man. This is one of our greatest secrets." "When at last Reason becomes the religion of man, then will the problem be solved." Weishaupt's dedication of his organization to "reason" makes some sense when the reader recalls that "reason" has been defined as the "unbridled use of man's mind to solve man's problems without the involvement of God." The Bible calls this "the fruit of the tree of the knowledge of good and evil." It was this knowledge that God wanted man not to have, and it was the promise made to man by Lucifer that man could have it by eating of "the fruit." In addition, Weishaupt's religion offered its believers a reward not offered by any other religion: worldwide power!
>
> Weishaupt wrote: "The pupils [members of the Illuminati] are convinced that the Order will rule the world. Every member therefore becomes a ruler." Weishaupt's religion not only offered power to his believers, but he offered them something else not guaranteed by any other religion: worldly success. He said that once a candidate had achieved the exalted degree of Illuminatus Minor, the fourth of the thirteen inside his Order, his superiors would: "assist him [the member] in bringing his talents into action, and [would] place him in situations most favourable for their exertion, so that he may be assured of success." Finally, the goal of the Illuminati was "man made perfect as a god - without God."

The ideology of "man made perfect as a god –without God" still remains to this day, and it is practiced by today's Illuminati members. The above phrase is what ties in Luciferian worship and trans-humanism. Lucifer is idolised by Illuminati members as the deity who gave man 'knowledge' and therefore is worthy of worship; God, -according to Luciferians, -did not want man to have knowledge and therefore is despised by Luciferians. Ingrained in the trans-humanism doctrine is the believe that: 'man can become 'god' through science and technology and in turn overthrow the Creator of the universe: God'. See LawOfIdentity (2014) and Mark Dice (2014).

These are the basics of Luciferianism. Therefore everything which is natural or pertains to nature must be contended or destroyed by Luciferians. This is why Illuminati members endorse having sex with children, killing first born sons, and drink blood. All the above go against nature and according to the 'edicts of Lucifer': paedophilia makes the person committing the act younger (it doesn't, it is just an excuse to act perverse on children because they know children are vulnerable); killing your first born son gives you good luck and fortune in this life (so yes, some Luciferians have sacrificed their first bon sons); and Illuminati members believe drinking blood / cannibalism is a 'purifying agent' (although in reality it causes spongiform encephalitis (holes in the brain)).

Modern-day Illuminati members still retain the goal of its founder "to bring about a NEW World Order that writes God out of the picture and deifies (glorifies) Lucifer." Infiltration through secrecy, still remains their mode of operation, for the current Illuminati and therefore they have secretly infiltrated all the major religions on earth; government and education – where each successive generation is being dumb down; they have continually diminished the ability for individuals to own private property, or claim inheritance; divided people against each other to continually diminish patriotism; and have continually diminished family values.

They also compartmentalise their knowledge between members. Until I fully exposed the Illuminati, many people who have been REM clones at the cloning centre did not know they were in fact REM driven clones, and thought they were in the 5th Dimension; the astral plane; a singularity; the spiritual realm; Valhalla; quantum hopping; a time stutter etc. or whatever else the Illuminati told them.

Today's Illuminati members also meet in secret (just like the founding members) as REM driven clones, **when they go to sleep**. Furthermore, because Illuminati meetings are in secret and not many people know the exact location (because knowledge is compartmentalised) of the cloning centre; or the fact that their consciousness has been transferred to Mark 2 REM driven clone bodies at the cloning centre (and they are not in their original bodies); as well as the fact that unsuspecting civilians have their memories suppressed; the points mentioned above are the reasons the Illuminati believe 'they are all powerful and untouchable'; and as a consequence, today's Illuminati members do all the disgusting things they want, because they believe no outsider can interfere.

The ring leaders of the Illuminati today also believe "the ends justify the means". This is why they clone, torture, molest, murder, and rape unsuspecting civilians as REM driven clones in their sleep. The Illuminati of today offer their members incitements to go along with their agenda and not oppose them (or face death). Another popular method is to entice their target with many, many wonderful prospects, and have the target believe they are joining a noble and prosperous venture, so that the target fulfils the objectives of the Illuminati unknowingly; promoting the Illuminati in a positive way, because the target has been deceived to perceive the nature of the Illuminati as 'positive'; by the time the target finds out the true intent of the Illuminati, and the evil which emanates from it, it is too late. Those who rise up in the ranks of the Illuminati are the men and women who have an insatiable lust for power, and most importantly: the men and women who want to rule the world.

Modern-day Illuminati members also wish to become gods (through technology); overthrow the Creator, and achieve their overall aim of enslaving mankind. This is why they clone people, and clone people in high rank society from all walks of life (movie stars, musicians, politicians etc.; whether the person willing wants to be part of the Illuminati or not) so long as that person is in a position of power and influence, the Illuminati clone that person, and threaten that person, for example -"Hey, you're going to hang with us –or else" –through such coercion, the people in high rank society who have power and influence will not oppose the Illuminati's plans to become gods; enslave mankind forever; and rule the world. Another reason for cloning high rank society is to include these people into the Illuminati (willingly or unwillingly) to ensure the world's populace remains in ignorance (because once all the world leaders and high rank society are cloned and under the coercion of the Illuminati nobody in a position of influence or power can warn the populace against the Illuminati) until the Illuminati's plan is completed and they have enslaved the world forever.

The Illuminati’s overall aim of ‘becoming gods’ and ruling the world, as well as, mind controlling all the inhabitants of earth is also the reason the Illuminati:

- Administer drip feed disclosure through media, by telling some truths mixed with lies in order to conceal their true intentions and overall aim, and prevent the betrayed partner (the public) from ever discovering “the complete truth”;
- Administer evaluative conditioning, by placing their symbols and ideology in popular media with positive associations, so that the unknowing and unsuspecting public will eventually become predisposed to the Illuminati and unsuspectingly have a positive or neutral response towards the Illuminati;
- Because they want to become ‘gods’ is also the reason the Illuminati is promoting RFID microchips and only discussing RFID microchips positively, while at the same time placing suppression (gagging) orders on anyone who speaks negatively about RFID microchips –which implies an unsuspecting public will willingly accept the microchip; and at the point of transaction, the person will have (unknowingly) given up their privacy to a third party (the Illuminati) for the rest of his / her life;
- Their aim to become ‘gods’ is also the reason the Illuminati are hurriedly trying to complete the HAARP grid across earth –because a complete HAARP grid will allow them to achieve their goal of mind control over the entire world; which fulfils their objective of becoming gods; because a complete HAARP grid will be capable of time travel, and therefore the Illuminati will be capable of going back to a previous time to correct the mistake(s) which led to their downfall; the Illuminati members will retain the knowledge of the previous time, and the rest of humanity will have no recollection of such a memory.

The Illuminati is **not** a joke. It is **not** fiction. They are very real, and part of humanity’s reality; and through advanced concealed technologies the Illuminati aim to enslave humanity forever. The ring leaders of the present Illuminati includes Queen Elizabeth II, Prince Philip Duke of Edinburgh, Prince Charles of Wales and Vladimir Putin. I have also detailed the actions of the ringleaders in the main text in this disclosure, as well as, detailed other modern-day evil Illuminati members on my Facebook and Proboards. It is time the good people of earth, stopped being afraid, do the right thing, put a stop to this evil, and save themselves, as well as their children’s children from being slaves forever. Spread and share this disclosure.

Glossary

Aneurysm *-noun:* An excessive swelling of the wall of an artery at a fixed point in the body. A brain aneurysm is therefore a: bulge or ballooning in a blood vessel in the brain. It often looks like a berry hanging on a stem. A brain aneurysm can leak or rapture, causing bleeding into the brain.

Brain Aneurysm *-noun:* see Aneurysm.

Clone *–noun:* a cell, group of cells, an organism produced asexually from a single ancestor and is genetically identical to a single ancestor.

Concealed Technology *-noun:* hidden machinery and devices undisclosed and currently unavailable for public consumption. Concealed (or military) technology develops at a rate of 44 years for every 12 months which passes in comparison to the technology the public is currently accustomed to. Origin: Phil Schneider.

Cloning Centre *–noun:* a physical location (on earth) where duplicate and replicate clones are produced. These physical locations are usually Deep Underground Military Bases (DUMBs). DUMBs have an entire floor dedicated to cloning. It is also a place where Illuminati members meet with each other as REM driven clones. The above-ground cloning centre where many high profile people attend can be found within a radius of 5/6 hours drive from the Robert Pickton Farm Port Coquitlam, British Columbia, in Canada, somewhere at a remote nature reserve.

Cloning Technology *-noun:* the technological advancements in medicine, science and technology used to produce duplicate and replicate copies of originals.

Conditioned Response *-noun:* an automatic response established by training to an ordinarily neutral stimulus.

Conditioned Stimulus *–noun:* A previously neutral stimulus that, after repeated association with an unconditioned stimulus, elicits the response produced by the unconditioned stimulus itself.

Consciousness *–noun:* the state of being aware of and responsive to one's surroundings; a person's awareness or perception of something.

Consciousness Transfer *-noun or verb:* the process of transferring or copying the mental content (including long-term memory and "self") from a particular brain and copying it to a computational device; artificial body or avatar body such as that of a robot or clone version of the original. It is also the feat in which the person's mental content (long term memory and "self") moves from one body into another.

Depopulation *verb:* to remove or reduce the population of, as by destruction or force.

Drip Feed Disclosure *noun or verb:* is the process of supplying information but in small amounts overtime. Drip feed disclosure is also the process of revealing information slowly overtime, possibly telling lies to conceal certain aspects of the truth until the source administering the drip feed disclosure has adequate time to let out the truth in a slow and controlled way, thereby delaying the betrayed partner (in this disclosure, the public) from having the "complete truth" for some time.

DUMB *–noun:* [Deep Underground Military Base] a facility directly owned and operated by or for the military or one of its branches that shelters military equipment and personnel, and facilitates training and operations beneath the surface of the earth.

Duplicate Clone *-noun:* a fully formed human body which is a genetic copy of original developed through the process of regenerative technology. Duplicate clones are grown in a big thick tank full of (salty) water.

Duplication Cloning *-verb:* involves agitating the cells of on an original repetitively until a fully formed human body of the original is developed. Duplicate clones take an average of 5 months to form into a fully developed human body of the original through the process of regenerative medicine and technology.

Evaluative Conditioning *-noun:* is a change in liking, which occurs due to an association with a positive or negative stimulus.

H.A.A.R.P. Technology *–noun:* [High frequency Active Auroral Research Program] a radio transmitting system that can bounce signals off the Earth's upper atmosphere, (60km (37 miles) to 1000km (620 miles) high) back to probe deep into the earth or sea. HAARP is also capable of: disrupting human mental processes; knocking out all global communication systems; changing weather patterns over large areas; interfering with wildlife and migration patterns; hurting ecosystems; negatively affect human beings health, moods and mental states; and unnaturally 'boil' the earth's upper atmosphere. HAARP used correctly will control the weather without any adverse effects.

H.A.A.R.P. Grid *–noun:* a network of radio transmitters which can bounce signals off the earth's upper surface. Each transmitter is located at a specific point across earth and communicates in unison with other radio transmitters across the earth. At this present time of writing, a HAARP grid has **not** been completed, although the Illuminati are working twice as fast to complete a HAARP grid. The threat to humanity once a HAARP grid is completed includes: mind control over the entire world's inhabitants. A completed HAARP grid will also be capable of time travel, and therefore the Illuminati will always be able to go back to a pervious point in time to correct the mistake(s) which led to their downfall. Humanity will be slaves forever.

Habeas Corpus *-noun:* is [A] writ [formal document] requiring a person under arrest to be brought before a judge or into court, especially to secure the person's release unless lawful grounds are shown for their detention.

Heart Attack *-noun:* A sudden occurrence of a blockage of the flow of blood to the heart.

Human Clone *–noun:* The creation of a genetically identical copy of a human.

Ionosphere *–noun:* the layer of the earth's atmosphere which contains a high concentration of ions and free electrons and is able to reflect radio waves. It lies above the mesosphere and extends from about 60km (37 miles) to 1,000 km (620 miles) above the earth's surface.

Illuminati *–noun:* A modern-day criminal organisation operated by reprobate (depraved, unprincipled and wicked person) criminals. Their main agenda: is to enslave the whole world through advanced concealed technologies. See Appendix C for further discussion.

Mark 2 Clone *–noun:* Is a sleep driven clone; specifically, a REM sleep driven clone. A Mark 2 Clone is activated by transferring the consciousness of an original into a Mark 2 Clone **only when** the original reaches REM sleep (usually 90- 110 minutes **after** the original falls asleep). Once the consciousness of the original is transferred from the original's body to the Mark 2 Clone, the Mark 2 clone is now capable of motion: such as walking, talking etc. The Mark 2 clone 'drops limp' and becomes motionless once the original wakes up from sleep. The original's consciousness no longer resides in the Mark 2 clone (once the original is awake) and therefore the Mark 2 clone is now incapable of motion. Mark 2 Clones are also known as "REM Driven Clones" and "REM Duplicate Clones".

Memory Suppression *–noun or verb:* is the selective removal of memories or associations with the mind using memory suppression technology.

Memory Suppression Technology *–noun:* any scientifically advanced technology used selectively to remove memories from the conscious mind.

Mind-Voice Technology *–noun:* an advanced technology capable of reading, listening, hearing and broadcasting a person's inner voice or thoughts. It is capable of replicating sounds **exactly**. Therefore an individual can hear the sound of drums, a guitar or any instrument and replicate that sound exactly just by thinking about it. Consequently, Mind-voice technology has the functionality of producing music.

Military Technology *–noun:* machinery and devices developed from scientific knowledge used by the Armed Forces which advance at a rate of 44 years for every 12 months which passes, compared to the technology the public is accustomed to. Origin: Phil Schneider

MK Ultra *-noun:* [Manufacturing Killers Utilizing Lethal Tradecraft Requiring Assassinations] The goal of mind control, using MK Ultra technology is to program an individual to carry out any task against their will and self-preservation instinct and to control the absolute behaviour and thought patterns of the individual. See Appendix B for further details.

Neutral Stimulus *–noun:* is a stimulus which initially produces no specific response other than focusing attention. In classical conditioning, when used together with an unconditioned stimulus, the neutral stimulus becomes a conditioned stimulus.

Negative Association *-noun:* is an undesirable experience or perception.

Negative Stimulus *-noun:* a stimulus with undesirable consequences.

New World Order *-noun:* [NWO] Agenda. The whole NWO agenda is to turn humanity into mindless slaves forever; whereby the post-humans / trans-humans mind control the entire world's populace either through RFID microchips or a completed HAARP grid. Another aspect of the NWO agenda is to depopulate the world's current population of 7.3 billion people to 500 million people (and never exceed a world population of 500 million people afterwards); ruled by a one world government; a one world ruler; with a one world religion. See Appendix C for more details.

Original *–noun:* A person who is **not** a clone.

Pain Receptor *-noun:* Any one of the many nerve endings throughout the body that warn of harmful changes in the environment such as excessive pressure or temperature.

Positive Association *-noun:* is a desirable experience or perception.

Positive stimulus *-noun:* a stimulus with desirable consequences.

Posthumanism *–noun:* seeks to rewrite the very definition of being human. It is the condition in which humans and intelligent technology become intertwined. In the Posthuman there are no essential differences or absolute demarcations between bodily existence and computer stimulation, cybernetic mechanism and biological organism, robot technology and human goals.

Posthuman *-noun:* see Posthumanism.

Project MK Ultra *-noun:* see MK Ultra.

Regenerative Medicine *-noun:* (of a living organism) the process of re-growing new tissues after loss or damage.

Regenerative Technology *-noun:* any machinery or device developed from scientific knowledge which has the capability to re-grow new tissues after loss or damage.

REM Sleep *–noun:* [Rapid Eye Movement] is the fifth stage of sleep in the sleep cycle. It takes 90 - 110 minutes to reach REM sleep after we fall asleep. REM sleep is also known as the "period of paralysation". The involuntary muscles such as the brain become more active whereas voluntary muscles (those that you move by choice) such as your arms and legs become more relaxed or paralysed. REM sleep is a kind of sleep that occurs at intervals during sleep, and it is characterised by rapid eye movements.

REM Driven Clone *-noun:* [Rapid Eye Movement Driven Clone] a clone that can only become activated, once the original is in REM sleep. See Mark 2 Clone.

REM Duplicate Clone *-noun:* [Rapid Eye Movement Driven Clone] A clone developed by regenerative medicine and technology and is therefore an identical copy of an original. REM duplicate clones can only become activated when the original is in REM sleep. See Mark 2 Clone.

REM Driven Clone Death *–noun:* the process where an original dies because of constant torture to their REM driven clone or where a constant electrical current is applied to the REM driven clone resulting in death of an original usually in the form of an aneurysm or heart attack (because consciousness is linked) in the original's body.

REM Driven Clone Torture *—noun or verb:* the action or practice of inflicting serve pain on a REM driven clone. REM driven clone torture causes biological and physiological responses in the original's body because consciousness is linked. Intermittent REM driven clone torture (depending on what is done) causes the original to experience severe headaches, an upset stomach, achy limbs, sickness; a weakened heart. Continuous REM driven clone torture will lead to the death of the original; usually in the form of aneurysm or heart attack in the original's body.

Replication Cloning *–verb:* involves giving birth to a genetic identical of an original where the newborn starts life off as a baby and matures. The newborn is referred to as a clone.

RFID Technology [Radio Frequency Identification] *-noun:* are electronic microchips the size of a grain of sand that can be directly embedded into the human flesh. RFID microchips communicate wirelessly through the use of electromagnetic fields to transfer data. RFID microchips link the brains of people via the implanted microchip to satellites controlled by ground base super-computers. The dangers of RFID microchips to the implanted person are: total loss of privacy and total control of the person's physical body functions, mental and emotional thought processes, including the implanted person's subconscious or dreams –for the rest of that person's life! RFID microchips are also tracking devices, and the implanted person can be tracked anywhere on the globe.

Selling One's Soul *-verb:* to sell the use one's "Mark 2" REM driven clone to the Illuminati, for the Illuminati to use the individual's Mark 2 REM driven clone in whatever manner the Illuminati wishes. There are no returns once the individual has signed over his / her (soul) Mark 2 REM driven clone. When an individual sells their (soul) Mark 2 REM driven clone, the person has also entered into a contract to sell the Mark 2 REM driven clone(s) of their current children (if they have any) as well as any unborn children the person may have later in life. The person sells all their descendants (souls) Mark 2 REM driven clones to the Illuminati, once the individual sells their (soul) Mark 2 REM driven clone to the Illuminati. Selling one's (soul) Mark 2 REM driven clone is considered **a serious business transaction** to the Illuminati. There are no returns. If the person ever makes a fuss and wants their (soul) Mark 2 REM driven clone back, the Illuminati will either torture the person's Mark 2 Clone, or apply a constant electric current to the person's Mark 2 Clone until the person either has a heart attack or aneurysm in their original body. This is what public figures are hinting at when they say "They have sold their soul". They have sold the use of their Mark 2 REM driven clone to the Illuminati. Selling one's soul is not a joke. Never sell your soul.

Stimulus *–noun:* is something that causes a reaction, especially interest, excitement or energy. It is also an energy change registered by the senses. For example a stimulus can be a shinny object for a baby.

Technology *–noun:* machinery and devices developed from scientific knowledge.

Technological Advancement *–noun:* is incorporating, by means of experimental development, a characteristic or capability not previously existing or available in standard practice, into a new or existing process or product that enhances a product's performance. Novelty, uniqueness, or innovation alone does not indicate a technological advancement.

Transhumanism *–noun:* the belief or theory that the human race can evolve beyond its current physical and mental limitations, especially by means of science and technology.

Unconditioned Response *–noun:* is a response to a neutral stimulus we have no / little control over. It is a natural automatic response. For example, food is an unconditioned stimulus for a hungry animal, and salivation is the unconditioned response.

Unconditioned Stimulus *–noun:* A stimulus that elicits an unconditioned response.

All references in this document have been saved and backed-up; therefore if any link in this document, is ever deleted, modified etc. (online), let me know.

References

2045 Initiative (2015) *2045 Strategic Social Initiative* [Online] Available from: http://2045.com/ [Accessed 1st June 2015]

Albrecht, K., and McIntyre (2005) *Spychips: How Major Corporations and Government Plan to Track Your Every Move with RFID.* Plume

Alford, J., (2014) *Scientist Selectively Erase and Restore Memories* [Online] Available from: http://www.iflscience.com/brain/scientists-selectively-erase-and-restore-memories [Accessed 8th July 2015]

Alford, J., (2015) *Scientist Implant False Memories Into Sleeping Mice* [Online] Available from: http://www.iflscience.com/brain/scientists-implant-false-memories-sleeping-mice [Accessed 28th July 2015]

Animal Research (1996) *Cloning Dolly the Sheep* [Online] Available from: http://www.animalresearch.info/en/medical-advances/timeline/cloning-dolly-the-sheep/ [Accessed 28th June 2014]

Anthony, S., (2012) *GoFlow: a DIY tDCS brain-boosting kit* [Online] Available from: http://www.extremetech.com/extreme/121861-goflow-a-diy-tdcs-brain-boosting-kit [Accessed 24th May 2015]

Anthony, S., (2013) *What is transhumanism, or, what does it mean to be human?* [Online] Available from: http://www.extremetech.com/extreme/152240-what-is-transhumanism-or-what-does-it-mean-to-be-human [Accessed 24th May 2015]

Astral 7sight (2013a) *Illuminati Exposed 2013: Chemtrails, Atlantis, Clones, Drones & Vril Part 1/8.* [Online video]. June 23rd 2013. Available from: https://www.youtube.com/watch?v=UonnFuHLJKc&ab_channel=Astral7ight [Accessed 12th July 2015]

Astral 7sight (2013b) *Illuminati Exposed 2013: Chemtrails, Atlantis, Clones, Drones & Vril Part 2/8.* [Online video]. June 23rd 2013. Available from: https://www.youtube.com/watch?v=QPAXCwu5MIo&ab_channel=Astral7ight [Accessed 12th July 2015]

Astral 7sight (2013c) *Illuminati Exposed 2013: Chemtrails, Atlantis, Clones, Drones & Vril Part 3/8.* [Online video]. June 23rd 2013. Available from: https://www.youtube.com/watch?v=5zlJ0VQP444&ab_channel=Astral7ight [Accessed 12th July 2015]

Astral7sight (2013d) *Illuminati Exposed 2013: Chemtrails, Atlantis, Clones, Drones & Vril Part 4/8*. [Online video]. June 23rd 2013. Available from: https://www.youtube.com/watch?v=dCGhrDEl-q8&ab_channel=Astral7ight [Accessed 12th July 2015]

Astral7sight (2013e) *Illuminati Exposed 2013: Chemtrails, Atlantis, Clones, Drones & Vril Part 5/8*. [Online video]. June 23rd 2013. Available from: https://www.youtube.com/watch?v=EDyerA-k8Ic&ab_channel=Astral7ight [Accessed 12th July 2015]

Astral7sight (2013f) *Illuminati Exposed 2013: Chemtrails, Atlantis, Clones, Drones & Vril Part 6/8*. [Online video]. June 23rd 2013. Available from: https://www.youtube.com/watch?v=iqQZPpXl2yg&ab_channel=Astral7ight [Accessed 12th July 2015]

Astral7sight (2013g) *Illuminati Exposed 2013: Chemtrails, Atlantis, Clones, Drones & Vril Part 7/8*. [Online video]. June 23rd 2013. Available from: https://www.youtube.com/watch?v=WYZSOnyWwP8&ab_channel=Astral7ight [Accessed 12th July 2015]

Astral7sight (2013h) *Illuminati Exposed 2013: Chemtrails, Atlantis, Clones, Drones & Vril Part 8/8*. [Online video]. June 23rd 2013. Available from: https://www.youtube.com/watch?v=Y18m0gPLQhM&ab_channel=Astral7ight [Accessed 12th July 2015]

Astral7sight (2013i) *Celebrity Tila Tequila: Missing Children and Cloning Centers* [Online video]. June 7th 2013. Available from: https://www.youtube.com/watch?v=7mRZ7ItF9ls&ab_channel=Astral7ight [Accessed 12th July 2015]

Avatar (2009) Film. Directed by James Cameron. [DVD]. UK: 20th Century Fox

BBC Future (2015) *BBC Future* [Online] Available from: http://www.bbc.com/future [Accessed 28th July 2015]

BBC Horizon (2009) *Why Do We Dream BBC Horizon* [Online video]. May 15th 2013. Available from: https://www.youtube.com/watch?v=E8MZ1twv0cU&ab_channel=AHOlearning [Accessed: 7th June 2015]

BBC News (2000) *Scientist 'clone' monkey* [Online] Available from: http://news.bbc.co.uk/1/hi/sci/tech/602027.stm [Accessed: 28th June 2015]

BBC News (2015a) *BBC News* [Online] Available from: http://www.bbc.co.uk/news/science_and_environment [Accessed 28th July 2015]

BBC News (2015b) *BBC News* [Online] Available from: http://www.bbc.co.uk/news/technology [Accessed 28th July]

BEAMS (2007) *BT's 'Soul Catcher2025' Implants* [Online] Available from: http://www.beamsinvestigations.org/BT's%20'Soul%20Catcher%202025'%20Implants.htm [Accessed 1st June 2015]

Begich, N., & Manning, J., (1997) *ANGELS DON'T PLAY THIS HAARP. Advances in Tesla Technology* [Online] Available from: http://www.alachuacounty.us/Depts/epd/EPAC/Angels%20Dont%20Play%20This%20HAARP%20by%20Nick%20Begich%201997.pdf [Accessed 15th June 2015]

Berkeley News (2011) *Scientists use brain imaging to reveal the movies in our mind* [Online] Available from: http://news.berkeley.edu/2011/09/22/brain-movies/ [Accessed: 22nd July 2015]

Beter, P., (2011) *"Organic Robotoids are real" by Dr Peter Beter* [Online video]. April 15th 2011. Available from: https://www.youtube.com/watch?v=nc0m5UMPwtU&ab_channel=youlittlerocket [Accessed 6th July 2015]

Bloomberg Business (2015) *See Future of Artificial Intelligence in Mind Clones Right Now!* [Online video] Available from: https://www.youtube.com/watch?v=4bqZp9TPYVk&ab_channel=BloombergBusiness [Accessed 27th June 2015]

Borghino, D., (2012) *"Avatar" project aims for human immortality by 2045* [Online] Available from: http://www.gizmag.com/avatar-project-2045/23454/ [Accessed 3rd June 2015]

Boringest (2006) *Bush Video 10 years ago!* [Online video]. January 3rd 2006. Available from: https://www.youtube.com/watch?v=pw4Bhmm22xo&ab_channel=boringest [Accessed: 11th May 2015]

BritneySpearsVevo (2009) *Britney Spears –Break The Ice* [Online video] October 24th 2009. Available from: https://www.youtube.com/watch?v=eQFIKP9rGhQ&ab_channel=BritneySpearsVEVO [Accessed 18th July 2015]

BritneySpearsVevo (2011) *Britney Spears –Hold it Against me* [Online video] February 17th 2011. Available from: https://www.youtube.com/watch?v=-Edv8Onsrgg&ab_channel=BritneySpearsVEVO [Accessed 18th July 2015]

Campbell, T., (2008) *Physics, Metaphysics and the nature of Consciousness* [Dr Thomas Campbell –My Big TOE (1 of 18)] [Online video] May 25th 2008. Available from: https://www.youtube.com/watch?v=MxECb7zcQhQ&list=PLBFFCEB1CAEDF9E6C&ab_channel=akn0ledge [Accessed 4th July 2015]

Carmichael, J., (2013) *Mouse Cloned From A Mere Drop of Blood* [Online] Available from: http://www.popsci.com/science/article/2013-06/mouse-cloned-mere-drop-blood [Accessed 19th July 2015]

CBS (2008) *Regeneration of Cells – Regrowing finger* [Online video] May 15th 2010. Available from: https://www.youtube.com/watch?v=ITxx2sOLW2Y&ab_channel=Weltenspur2 [Accessed: 25th June 2015]

Cherry, K., (2015) *What is Consciousness* [Online] Available from: http://psychology.about.com/od/statesofconsciousness/f/consciousness.htm [Accessed 1st July 2015]

CreativeForceVideo (2014) *Speaking with Nostradamus, Quantum Hypnosis with Delores Cannon* [Online video] August 2nd 2014. Available from: https://www.youtube.com/watch?v=CBOml6LTbpM&ab_channel=CreativeForceVideo [Accessed 25th July 2015]

Crystal Links (2015) *Nostradamus* [Online] Available from: http://www.crystalinks.com/nostradamus.html [Accessed 25th July 2015]

CTForecaster (2013) *Japanese Dream Recording Machine –Update* [Online video]. April 12th 2013. Available from: https://www.youtube.com/watch?v=gQueU9a8URw&ab_channel=CTForecaster [Accessed: 22nd July 2015]

Daily Mail Online (2015) *Mail Online* [Online] Available from: http://www.dailymail.co.uk/sciencetech/index.html [Accessed 28th July 2015]

De Houwer, J., Thomas, S., & Baeyens, F. (2001) *Associative Learning of Likes and Dislikes: A Review of 25 years of Research on Human Evaluative Conditioning*. Psychological Bulletin, Vol. 127, No.6, 853-869 In Hale, J., (2012) *What influences are Food Likes and Dislikes?* [Online] Available from: http://psychcentral.com/blog/archives/2012/02/15/what-influences-our-food-likes-and-dislikes/ [Accessed 28th June 2015]

Dictionary Reference (2015) *Consciousness* [Online] Available from: http://dictionary.reference.com/browse/consciousness?s=t [Accessed 30th June 2015]

Disclose TruthTV (2015) *Delores Cannon on WW3, Antichrist Nostradamus Prophecies [Full Video]* [Online video] March 19th 2015. Available from: https://www.youtube.com/watch?v=l0aCHrY0ObI&ab_channel=DiscloseTruthTV [Accessed 26th July 2015]

Donald Marshall Proboards (2015) *Donald Marshall Proboards* [Online] Available from: http://donaldmarshall.proboards.com/ [28th July 2015]

Ehrsson, H.H., (2013) *Inspirational Lecture –Professor Henrik Ehrsson* [Online video] October 3rd 2013. Available from: https://www.youtube.com/watch?v=iR7HissYN2U&ab_channel=karolinskainstitutet [Accessed 2nd July 2013]

Epperson, A. R., (1990) *The New World Order*, Publius Press. [Online] Available from: https://ia700406.us.archive.org/27/items/TheNewWorldOrder_342/TheNewWorldOrder.pdf [Accessed 7th July 2015]

Fox 4 News –Dallas Fort Worth (2014) *Aug. 15, 1988 – George W. Bush –KDFW* [Online video]. June 23rd 2014. Available from: https://www.youtube.com/watch?v=zwrl2axvPmY&ab_channel=FOX4News-Dallas-FortWorth [Accessed: 15th May 2015]

FW: Thinking (2014) *Erase and Restore your memories* [Online video]. Jun 18th 2014. Available from: https://www.youtube.com/watch?v=PpzzD_103jc&ab_channel=FW:Thinking [Accessed 8th July 2015]

Galactic (2012a) *Conversations With Nostradamus Volume One* [Online] Available from: http://galactic.no/rune/DoloresCannon_books/Dolores-Cannon-Conversations-With-Nostradamus-Volume-1.pdf [Accessed 25th July 2015]

Galactic (2012b) *Conversations With Nostradamus Volume Two* [Online] Available from: http://galactic.no/rune/DoloresCannon_books/Dolores-Cannon-Conversations-With-Nostradamus-V2.pdf [Accessed 25th July 2015]

Gizmag (2015) *Gizmag* [Online] Available from: http://www.gizmag.com/ [Accessed 28th July 2015]

Greenberg, P., (2013) *No More Bad Flashback: Scientist Find Gene That Erases Memories* [Online] Available from: http://mashable.com/2013/09/25/erase-bad-memories/ [Accessed 11th June 2015]

Hale, J., (2012) *What influences are Food Likes and Dislikes?* [Online] Available from: http://psychcentral.com/blog/archives/2012/02/15/what-influences-our-food-likes-and-dislikes/ [Accessed 28th June 2015]

Halliday, P., (2013) *Whistleblowing: the new 'public interest' test and other developments.* [Online] Available from: http://www.11kbw.com/uploads/files/PHPaper.pdf [Accessed 8th May 2015], p. 2

Hewitt, J., (2012) *How to create a mind or die trying* [Online] Available from: http://www.extremetech.com/extreme/141507-how-to-create-a-mind-or-die-trying [Accessed 24th May 2015]

History (2015) *George W. Bush* [Online] Available from: http://www.history.com/topics/us-presidents/george-w-bush [Accessed 14th May 2015]

Hostel (2006) Film. Directed by Eli Roth. [DVD]. USA: Lionsgate

Hostel: Part II (2007) Film. Directed by Eli Roth. [DVD]. USA: Lionsgate

Hostel: Part III (2011) Film. Directed by Scott Spiegel. [DVD]. USA: Sony Pictures Home Entertainment

Inception (2010) Film. Directed by Christopher Nolan. [DVD]. UK: Warner Bros. Pictures

inifiniLor (2013) *Appeal from Survivors of Canadian Genocide* [Online video]. April 8th 2013. Available from: https://www.youtube.com/watch?v=cVYkctM1k90&ab_channel=infiniLor [Accessed 13th July 2015]

Jeanice Barcelo (2013) *BNE Radio Show w/ guest Donald Marshall* [Online video]. March 9th 2013. Available from: https://www.youtube.com/watch?v=3uzgu4ekT3c&ab_channel=JeaniceBarcelo [Accessed 11th July 2015]

Jim Cristea (2009) *Mind Reading - FMRI - Machine that Reads Your Thoughts - 60 Minutes* [Online video]. January 9th 2009. Available from: https://www.youtube.com/watch?v=Cwda7YWK0WQ&ab_channel=JimCristea [Accessed: 22nd July 2015]

Jones, A., (2008) *Reflections and Warnings: An Interview with Aaron Russo* [Online video]. June 1st 2009. Available from: https://www.youtube.com/watch?v=YGAaPjqdbgQ&ab_channel=rohstyles23 [Accessed: 12th May 2015]

KafkaWinstonWorld (2014) *IS THIS WHERE WE ARE GOING? THIS MOVIE WILL BLOW YOUR F%$NG MIND(mirrored)* [Online video]. December 11th 2014. Available from: https://www.youtube.com/watch?v=4mUII1HcsRg&ab_channel=KafkaWinstonWorld [Accessed 15th July 2015]

Kim, M., (2013) *MIT scientists implant a false memory into a mouse's brain* [Online] Available from: http://www.washingtonpost.com/national/health-science/inception-mit-scientists-implant-a-false-memory-into-a-mouses-brain/2013/07/25/47bdee7a-f49a-11e2-a2f1-a7acf9bd5d3a_story.html [Accessed 28th July 2015]

LawOfIdentity (2014) *"We Will Become Gods"* [Online video]. August 20th 2014. Available from: https://www.youtube.com/watch?v=5MmXHMaati0&ab_channel=LawOfIdentity [Accessed 23 July 2015]

Legal-dictionary (2015) *Habeas Corpus* [Online] Available from: http://legal-dictionary.thefreedictionary.com/habeas+corpus [Accessed 14th May 2015]

Mark Dice (2014) *Top Transhumanist Claims He Will Become God and Kill Anyone Who Tries to Stop Him!!!* [Online video] May 14th 2014. Available from: https://www.youtube.com/watch?v=KPJARo-5VXE&ab_channel=MarkDice [Accessed 24th July 2015]

Medical News Today (2015) *Paranoid Schizophrenia: Causes, Symptoms and Treatments* [Online] Available from: http://www.medicalnewstoday.com/articles/192621.php [Accessed 21st July 2015]

Megadeth (2001) *The World Needs a Hero* [CD] USA: Sanctuary Records Group Ltd

MK Ultra Compendium (1980) *Secret CIA Human Experiments in the United States: MK Ultra Mind Control Research Program.* [online video] May 26th 2012. Available from: https://www.youtube.com/watch?v=c4f9Hs0s1jQ&ab_channel=TheFilmArchives [Accessed: 22nd June 2015]

Mind-Computer (2012) *Synthetic telepathy "Artificial Telepathy"* [Online] Available from: http://mind-computer.com/2012/05/15/synthetic-telepathy-artificial-telepathy/ [Accessed 22nd June 2015]

Moss, S., (2009) *Evaluative conditioning* [online] Available from: http://www.psych-it.com.au/Psychlopedia/article.asp?id=312 [Accessed 28th June 2015]

Motherboard (2015) *Motherboard* [Online] Available from: http://motherboard.vice.com/en_uk [Accessed 28th July 2015]

MrCowShedder (2012) *Royal Babylon by Heathcote Williams (rough cut).* [Online video]. May 11th 2012. Available from: https://www.youtube.com/watch?v=jIukrdRhnpw&ab_channel=MrCowshedder [Accessed 14th July 2015]

MurdokDubstep (2010) *Where'd You Go – Fort Minor (Murdok Dubstep Remix)* [Online video]. July 22nd 2010. Available from: https://www.youtube.com/watch?v=7VdAvIf1Nc4&ab_channel=MurdokDubstep [Accessed 15th July 2015]

nature video (2013) *Reading minds* [Online video]. October 23rd 2013. Available from: https://www.youtube.com/watch?v=z8iEogscUl8&ab_channel=naturevideo [Accessed: 22nd July 2015]

New Scientist (2014) *Brain Decoder can eavesdrop on your inner voice* [Online] Available from: https://www.newscientist.com/article/mg22429934-000-brain-decoder-can-eavesdrop-on-your-inner-voice/ [Accessed 12th June 2015]

New Scientist (2015) *New Scientist* [Online] Available from: https://www.newscientist.com/ [Accessed 28th July 2015]

Non Mirage Truth Vision (2015) *CIA's Heart Attack Gun* [Online video]. Available from: https://www.youtube.com/watch?v=Uwy56QTV4cs&ab_channel=NonMirageTruthVision [Accessed 16th July 2015]

Open Minds (2011) *Phil Schneider's incredible ET claims.* [Online] Available from: http://www.openminds.tv/phil-schneiders-incredible-et-claims/9982 [Accessed 9th May 2015]

Paye, J-C., (2013) *The Suspension of Habeas Corpus in America* [Online] Available from: http://www.globalresearch.ca/the-suspension-of-habeas-corpus-in-america/5311701 [Accessed 20th May 2015]

Petkova, V. I., and Ehrsson, H.H., (2008) *If I Were You: Perceptual Illusion of Body Swapping*, PLoS ONE, Volume 3, Issue 12, pp. 1-9

Prigg, M., (2014) *Mindreading software could eavesdrop on your secret inner voice* [Online] Available from: *http://www.dailymail.co.uk/sciencetech/article-2814896/The-mindreading-machine-listen-voices-head-let-paralysed-speak-again.html* [Accessed 13th June 2015]

Project Camelot (2008a) *Project Camelot Interviews George Green – Part 1 of 2* [Online video]. April 16th 2008. Available from: https://www.youtube.com/watch?v=sSYXrWIA618&ab_channel=ProjectCamelot [Accessed: 11th May 2015]

Project Camelot (2008b) *Project Camelot Interviews George Green – Part 2 of 2* [Online video]. April 16th 2008. Available from: https://www.youtube.com/watch?v=6zSrg0IxHzI&ab_channel=ProjectCamelot [Accessed: 11th May 2015]

RainmanJhof (2011) *Boondox-Abadon* [Online video]. October 31st 2011. Available from: https://www.youtube.com/watch?v=C2bH4B5_83Q&ab_channel=RainmanJhof [Accessed 15th July]

Radar Online (2013) *Princess Dianna 'Killed By Bright Light Shone By Special Forces Soldiers Into Car She Was In'* [Online] Available from: http://radaronline.com/exclusives/2013/09/princess-diana-killed-died-death-forces-light-special-air-service/ [Accessed 17th July 2015]

Rense (2001) *Microchip Mind Control, Implants and Cybernetics* [Online] Available from: http://www.rense.com/general17/imp.htm [Accessed 20th June 2015]

Rense (2011) *Possible HAARP Locations Around the World* [Online] Available from: http://www.rense.com/general92/haarp.htm [Accessed 20th July 2015]

Russo, A., (1996) *Mad as Hell* [Online video]. May 10th 2011. Available from: https://www.youtube.com/watch?v=Zz4TI75MszQ&ab_channel=XRepublicTV [Accessed: 13th May 2015]

Russo, A., (2006) *Freedom to Fascism* [Online video]. May 10th 2011. Available from: https://www.youtube.com/watch?v=uNNeVu8wUak&ab_channel=RevolutionistsUnited [Accessed: 12th May 2015]

RT (2014) *Revolutionary way to 'switch off' pain discovered* [Online] Available from: http://www.rt.com/news/210031-revolutionary-painkiller-discovered-scientists/ [Accessed 19th July 2015]

RT (2015) *Living forever as a robot? Prototype lets humans upload their mind into mechanised 'heads'* [Online] Available from: http://www.rt.com/usa/229811-mind-clones-robot-afterlife/ [Accessed 27th June 2015]

SadSongs4You (2010) *Elton John –Candle In The Wind. With lyrics* [Online video]. August 23rd 2010. Available from: https://www.youtube.com/watch?v=80rHyABCb20&ab_channel=SadSongs4You [Accessed 17th July 2015]

Schechtman (2012) *The Story of my (Second) Life: Virtual Worlds and Narrative Identity,* Philosophy and Technology, Volume 25, Issue 3, pp. 329-343

Schneider, P., (1995) *Phil Schneider Documentary of truth about Aliens & UFO's & our Government*. [Online video]. September 21st 2013. Available from: https://www.youtube.com/watch?v=Oljrjxnixtw&ab_channel=AliensAmongUs [Accessed: 10th May 2015]

Schneider, P., (1996) *Phil Schneider's Last Speech ~ Two Months Before His Assassination ~ Aliens & Underground Bases* [Online video]. November 24th 2013. Available from: https://www.youtube.com/watch?v=Slgb5U-OqFM&ab_channel=FallofMedia [Accessed: 10th May 2015]

Science Channel (2014) *How to Grow a New Fingertip | World's Strangest*. [Online video] June 16th 2014. Available from: https://www.youtube.com/watch?v=DtBUM51t4iw&ab_channel=ScienceChannel [Accessed 23rd June 2015]

Science Daily (2014) *'Off switch' for pain discovered: Activating the adenosine A3 receptor subtype is key to powerful pain relief* [Online] Available from: http://www.sciencedaily.com/releases/2014/11/141126132639.htm [Accessed 19th July 2015]

Sheen, M., Begich, N., & Robbins, W., (2005) *Holes in Heaven? H.A.A.R.P. & Advances in Tesla Technology* [Online video]. October 8th 2014. Available from: https://www.youtube.com/watch?v=SWVU6DKcjyA&ab_channel=documentary2014 [Accessed: 15th June 2015]

SimpleGirl4ewer (2007) *Britney Spears – Mona Lisa* [Online video]. March 18th 2007. Available from: https://www.youtube.com/watch?v=xEecXKUxl1s&ab_channel=SimpleGirl4ewer [Accessed 18th July 2015]

Sleepdex (2015) *Stages of Sleep* [Online] Available from: http://www.sleepdex.org/stages.htm [Accessed: 5th June 2015]

Star Wars Episode III: Revenge of the Sith (2005) Film. Directed by George Lucas. [DVD]. USA: 20 Century Fox

Stromberg, J., (2013) *Scientist Figure Out What You See While You're Dreaming* [Online] Available from: http://www.smithsonianmag.com/science-nature/scientists-figure-out-what-you-see-while-youre-dreaming-15553304/?no-ist [Accessed 22nd July 2015]

The 6th Day (2000) Film. Directed by Roger Spottiswoode. [DVD]. USA: Columbia Pictures

The Guardian (2015a) *The Guardian* [Online] Available from: http://www.theguardian.com/science [Accessed 28th July 2015]

The Guardian (2015b) *The Guardian* [Online] Available from: http://www.theguardian.com/uk/technology [Accessed 28th July 2015]

The Independent (2015a) The Independent [Online] Available from: http://www.independent.co.uk/news/science/ [Accessed 28th July 2015]

The Independent (2015b) The Independent [Online] Available from: http://www.independent.co.uk/life-style/gadgets-and-tech/ [Accessed 28th July 2015]

The Island (2005) Film. Directed by Michael Bay. [DVD]. USA: DreamWorks Pictures

The Manchurian Candidate (2004) Film. Directed by Jonathan Demme. [DVD]. USA: Paramount Pictures

TheNanoAge (2015) *Transhumanism and Posthumanism: The Future of Us (Humanity Plus)* [Online] Available from: *http://www.thenanoage.com/transhumanism-posthumanism.htm#transhuman* [Accessed: 30th May 2015]

Truthstream (2006) *Rigged USA Elections Exposed.* March 2nd 2006. Available from: https://www.youtube.com/watch?v=JEzY2tnwExs&ab_channel=truthstream [Accessed: 22th May 2015]

UC Berkeley Campus Life (2011) *Vision Reconstruction* [Online video]. December 11th 2011 Available from: https://www.youtube.com/watch?v=6FsH7RK1S2E&feature=youtu.be&ab_channel=UCBerkeleyCampusLife [Accessed 22nd July 2015]

Vincent Eastwood (2013) *Illuminati Cloning Programs, Sex and Murder Cults and Reptilians! 26Feb2013* [Online video] February 26th 2013. Available from: https://www.youtube.com/watch?v=M_1UiFeV5Jg&ab_channel=VincentEastwood [10th July 2015]

Walcutt, D. L., (2013) *Stages of Sleep*. [Online] Available from: http://psychcentral.com/lib/stages-of-sleep/ [Accessed 5th June 2015]

Walther, E., Nagengast, B., & Trasselli, C., (2005). *Evaluative conditioning in social psychology: Facts and speculations.* Cognition and Emotion, 19, 175–196 In Moss, S., (2009) *Evaluative conditioning* [online] Available from: http://www.psych-it.com.au/Psychlopedia/article.asp?id=312 [Accessed 28th June 2015]

WhiteLiesVevo (2010) *White Lies – Bigger Than Us* [Online video]. November 18th 2010 Available from: https://www.youtube.com/watch?v=JW0yynlDmqQ&ab_channel=WhiteLiesVEVO [Accessed 18th July]

Winter, L., (2014) *Scientist Erase Memories with Light* [Online] Available from: http://www.iflscience.com/brain/scientists-erased-memories-light [Accessed 10th June 2015]

WorldTruth (2014) *The Georgia Guidestones* [Online] Available from: http://worldtruth.tv/the-georgia-guidestones-2/ [Accessed 16th May 2015]

YesEthan (2013) *Consciousness Science Kept Hidden* [Online Video] January 12th 2013. Available from: https://www.youtube.com/watch?v=LFSRTsLOiv0&ab_channel=YesEthan [Accessed 4th July 2015]

Legislation

Computer Misuse Act (1990) Section 3A, *Making, supplying or obtaining articles for use in offence under section 1 or 3* [Online] Available from: http://www.legislation.gov.uk/ukpga/1990/18/section/3A [Accessed 8th May 2015]

Enterprise and Regulatory Reform Act (2013) Section 17, *Disclosures not protected unless believed to be made in the public interest.* [Online] Available from: http://www.legislation.gov.uk/ukpga/2013/24/section/17/enacted [Accessed 8th May 2015]

Employment Rights Act (1996) Section 43B, *Disclosures qualifying for protection.* [Online] Available from: http://www.legislation.gov.uk/ukpga/1996/18/section/43B [Accessed 8th May 2015]

Public Interest Disclosure Act (1998) Section 43B, *Disclosures qualifying for protection.* [Online] Available from: http://www.legislation.gov.uk/ukpga/1998/23/section/1 [Accessed 8th May 2015]

Serious Crime Act (2015) Section 41 3ZA, *Unauthorised acts causing, or creating risk of, serious damage.* [Online] Available from: http://www.legislation.gov.uk/ukpga/2015/9/section/41/enacted [Accessed 8th May 2015]

Tetryonic Theory - an overview (1) 2
Tetryonic theory..... challenging and correcting the foundations of quantum th 13
tetryonics merged pdf 21
Response to an analysis of Tetryonic Chemistry by Robert J Brotherus (1) 1675
Planck mass-energy templates [Tetryonic theory] 1694

Tetryonic Theory

The unified quantum field geometry of charged EM mass-ENERGY-Matter in motion

> *"...the scientist makes use of a whole arsenal of concepts which he imbibed practically with his mother's milk; and seldom if ever is he aware of the eternally problematic character of his concepts. He uses this conceptual material, or, speaking more exactly, these conceptual tools of thought, as something obviously, immutably given; something having an objective value of truth which is hardly even, and in any case not seriously, to be doubted. ...in the interests of science it is necessary over and over again to engage in the critique of these fundamental concepts, in order that we may not unconsciously be ruled by them."* *[Albert Einstein]*

Given the range and applied scope of Quantum Physics in today's modern technologic World there remains a driving desire to rationalise our numerous disparate scientific theories into one coherent theory with a intuitive model that can be applied equally to the Quantum and Cosmological scales of our Universe.

Such a theory would need to preserve the currently observed outcomes and present established theories in a new light, offering additional testable predictions of its own, and ideally do so in a manner that is simpler than that of the established theories and hypothesises.

Many foundational properties of Quantum Mechanics remain unaddressed by scientific theory and in the following pages an overview of the key quantum properties challenging our current scientific advancement will be highlighted, including a number of assumptions that currently impede the development of a fully realised, coherent solution to all of our current scientific questions.

While Mathematics is the language of Science it remains a language that lacks a well-defined physical model on which to test it and further its many and varied solutions to Quantum & Cosmological scale physics. It is this lack of any rigid, enforceable GEOMETRY that has allowed the development of numerous disjointed statistical and probabilistic solutions to physical problems, in turn impeding our scientific understanding and advancement of quantum processes.

The Standard Model has many observed and testable components to it but more recently new theories have emerged to contest it without being rigorously testable themselves. They rely on the established foundation provided by the Standard Model but try to explain its various deficiencies ad-hoc with various suppositions without any solid footing of their own.

Often the only way to progress further in our scientific endeavours is to retrace our footsteps in science and to develop new physical models on which we can discern our known results and observations thus excluding any false or misleading assumptions (mathematical of otherwise).

In doing so there exists the promise that a simple underlying foundation can be found to the physics of our Universe, revealing new and exciting advances in Science that will allow us to usher in a new age of scientific and technological advancement for the betterment of humanity as a whole.

'Tetryonics – The charged geometry of EM mass-ENERGY-Matter' whose founding principle is that **EQUILATERAL Planck energies are** the foundation geometry for all quantum mechanical processes is presented here as just such a solution to the current quandaries of Quantum Mechanics.

ENERGY


EM mass-Energy momenta
Energy
Planck's Constant
is the 'quantum of Action'
quantised angular momenta
$\left[\frac{m\Omega v^2}{s}\right]$
E
kg
$\frac{m^2}{s}$
$\left[\frac{m^2}{s}\right]$
Ω
P
m
mass-Energy
Charge-momenta
m
mΩ
s
$\left[\frac{E}{c^2}\right]$
c^2
$\left[\frac{\Omega}{c^2}\right]$
6.629432672 x 10^-34 J.s
mass
mass momenta
charge

Energy, in Physics, is an indirectly observed quantity of a system that imbues it with the ability to exert a Force or do Work over a distance.

It has been measured and quantified through numerous methodologies over the centuries, most notably through its associated characteristics such as mass, velocity and ElectroMagnetic fields.

The most recent attempt to quantify its characteristics (with respect to heat and light) led to the discovery of Planck's constant and the development of Quantum Mechanics

The application of a simple proposition (that Energy has an equilateral geometry) opens the door on a greater understanding of the mechanics of the quantum world, a realm that will be forever beyond the reach of our physical eyes.

The myriad of perplexing properties of quantum properties (such as Charge, mass & Matter) and the astonishing outcomes of quantum experiments (Interference and Wave-Particle duality) can now all be readily modelled and explained rationally on a solid geometric footing.

Paving the way for new discoveries and a greater understanding of our Universe and its mechanics

Quantised Angular Momenta


Planck Quanta
Often defined as the "quantum of action"
h
hv
Planck's Constant
kg $\frac{m^2}{s}$
hv
hv²
m
mΩv²
Planck quanta per second
kg.$\left[\frac{m^2}{s}\right]$.$s^{-1}$
The Planck constant (denoted h), also called Planck's constant, is a geometric constant resulting from QAM in quantum mechanics
Planck's constant relates the energy in one quantum (photon) of electromagnetic radiation to the frequency of that radiation
v
v²
Planck quanta are the minimum Energy-geometry possible
(comprised of EM mass-Energies and associated momenta)
c²
hv
Charge is a result of QAM geometry
quantised angular momentum is the result of equilateral geometry
Photons have neutral quanta geometry
hf
rotational Angular momentum
≈
Quantised Angular momentum
v²

Building on the priori definition of equilateral energy quantisation it can be quickly demonstrated that any energy measurement per unit of Time results in a geometric unit of measurement that has historically be taken to represent rotational motion (specifically Angular momentum)

This unit of motion is found throughout Quantum Mechanics and is directly related to the square energy levels in nuclear processes.

The equilateral EM fields of energy quanta are constrained by its geometry and this geometry lies at the heart of understanding the quantum world in all its beauty.

It determines properties such as Electric permittivity and Magnetic permeability, the vector direction of linear momentum and relates the scalar property of electromagnetic mass directly to velocity.

CHARGE


Charged mass geometry
The symmetry of Charge geometries provides a geometric foundation for all mass-Energy-Matter particles and physical forces
mv²
v
p
E
v²
kg [m²/s²]
Classical analysis of Energy (mass velocity) does not reveal the nature of Charge
v
p
Ω
1/c²
v²
The Tetryonic geometry of Energy reveals Charge as a product of quantised angular momentum
mΩv²
v
E
v²
[kg m²/s] 1/s
Charge is the result of quantised angular momentum and can also be modelled electrically as the uni-directional rotation of inductive energies
Q
[m[Ω/c²]v²]
Q
'a un-balanced (broken) energy symmetry resulting from the nett geometry of equilateral EM mass-energy quanta'

A fundemental property of all mass-ENERGY-Matter that gives rise to the Forces of electrical Interaction has eluded physical explanation by Physicists since its discovery and led to many 'band aid' additions to the Standard model in attempts to explain its observed properties.

The most recent attempt at an explanation was Special relativity theory which in turn led to our current models of charge from contractions of Matter due to motion.

SR explains Charge as an invariant property of of electrostatic bodies and that the motion of charges creates an additional magnetic moment through the relativistic distortion of spherical bodies of Matter.

Equilateral Planck energy momenta geometries and Matter topologies offer a completely different explanation for the source of electrostatic charges and their associated magnetic moments.

Positive and Negative charges are revealed to be opposite side of the same quantum energy 'quoin', and can be modelled electrically as ideal quantum inductive loops. It is equilateral geometry that gives rise to the physical properties of quantised angular momenta, inertial mass, elemental charges and even the geometric topology of Matter itself.

In a planar 2D form they form a neutral EM energy momenta geometry but it is when they form the topology of 3D Matter they are expressed as either Positive or Negative electric charge fascia.

ODD number energy quanta [W Bosons] combine via their magnetic bases in fixed quantum steps to create the 'squared' nuclear energy levels so familiar to quantum mechanics and form the basis for ElectroMagnetic Induction.


Elementary and quantum Charges
"All known fermions have charges that are integer 1/3 multiples of the elementary charge"
ε₀
Ω
It can be shown that the "quantum of charge" is the intrinsic angular momentum of a Planck mass
It then follows that Quasi-particles [Tetryons and Quarks] have charges of 0, 4 and 8
Further, it can be shown that the "elementary charge" applied to Leptons and Baryons (12 times quantum charge) is reflective of their nett charged Matter geometries
Tπ[±q]
Opposites attract
Similars repel
Quarks
up
anti-down
down
anti-up
+2/3
+1/3
-1/3
-2/3
Charmed Top
Strange Bottom
Strange Bottom
Charmed Top
Leptons
12
Positron
Tau
anti-electron
neutrino
Tau
neutrino
Muon
Tau
e-
Baryons
+1
0
-1
Proton
Neutron
Negatron
quantised Charges
(EM energy flux rotation within a ZPF geometry)
q
quantum charges
[v]
[v]
The elementary charge, usually denoted as e, is the electric charge carried by a single proton, or equivalently, the absolute value of the electric charge carried by a single electron
[v-v]
Q
Elementary charges
Elementary Charges
are the nett charge created by mass-Energy-Matter geometries
Zero Point Fields
E
V
[1-0]
V
[0-1]
E
Q
Q
N
S
S
N
All Charged particles and their respective KEM fields can be modelled with ZPF fields reflective of their nett Charge
Tetryons
4 [4-0]
0 [2-2]
4 [0-4]
Quarks
up 8 [10-2]
down 4 [8-4]
down 4 [4-8]
up 8 [2-10]
12 [12-0] e
0 [6-6] ve
0 [6-6] ve
12 [0-12] e
Leptons
Baryons
Proton 12 [24-12]
Neutron 0 [18-18]
Negatron 12 [12-24]
All Charges seek Equilibrium

It is their rigid equilateral geometry that provides the basis for relativistic charge invariance and the quantum mechanism for photo-electron transitions in atoms while the net energy momenta quanta in charged geometries provides the electromotive force known as Voltage.

Equilateral geometry reveals an intrinsic connection between EM Energy, mass and Charge.

As separated charges seek equilibrium they provide motive energies & the quantum scaffolding for large scale Matter topologies and their force interactions throughout our Universe.

mass-ENERGY-Matter

All Energy has an EM mass equivalence and equally any object with EM mass has energy equivalence

But there has never been a formal scientific definition and associated equation to distinguish the property of EM mass from that of Matter.

Using Tetryonic geometry it can be clearly demonstrated that ElectroMagnetic mass is NOT Matter – it is the Energy content of a system per unit of time [E / c^2] in total agreement with Einstein (and all before him) however, lacking a formal definition of either the two terms have become mired with each other so much that they are often used for each other inappropriately even in scientific peer-reviewed literature.


EM mass-Energy-Matter
CHARGE
c²
m
EM mass
c²
E
ENERGY
[Ω / c²]
Charge is a measure of the quantised angular momentum of any physical system
Tetryonic Matter
EM Field
Planck quanta
Tπ [[ε₀μ₀].[mΩv²]]
3D geometry
ElectroMagnetic
2D mass
velocity
Planck quanta
[mΩv]²
mass
velocity
Bosons
n
v
v
c²
1π[[ε₀μ₀].[mΩv²]]
ODD quanta
3D Matter
2D mass-Energies
M
Matter
c⁴
4nπ[[ε₀μ₀].[mΩv²]]
TETRYONS
Photons
+ f -
c²
2π[[ε₀μ₀].[mΩv²]]
EVEN quanta

ElectroMagnetic mass is the two dimensional (planar) measurement of Energy per unit of Time whereas Matter is a measure of the tetrahedral energies found in a spherical volume of 3D space.

Mass-energy can be viewed as the paper from which 3D Matter is created when it is folded into a tetrahedral shape (the quantum canvas covering the topology of Matter)

The often used tem of 'massless' is now shown to be a misnomer that should be removed from the scientific vocabulary except where it specifically refers to empty space (devoid of any energies).

Matter is now formally defined geometrically as 4nπ tetrahedral standing wave of EM energy and it is the tetrahedral topology of Tetryons that forms the foundation for all large scale Matter in the Universe (not spherical point particles).


v
ε₀
π
v²
mass-energy
c²
'massless' is a physics mis-nomer as all Energy exhibits mass equivalence
nπ[[ε₀μ₀].[mΩv²]]
2D EM mass-energy waveforms can be combined to form 3D EM mass-Energy-Matter particles
c
v²
radiant Matter wavefunction
c²
Tetryons
4 fascia Matter quanta
ZPF
mass-Energy quanta
m
TETRYONS
Platonic tetrahedrons are the foundational geometry of all 3D Matter
Tetryon
Matter Quantum
M
A Tetryon is a standing-wave of EM energy that creates a 4π tetrahedral geometry
(2 orthagonally opposed inductive circuits)
v
ε₀
ρ
v²
4π EM mass-energies
c²
4nπ[[ε₀μ₀].[mΩv²]]
ε₀
ρ
Matter
c⁴

Charge allows EM masses to form a Tetryonic topology giving volume to Matter and its energy momenta provides the interactive forces between them imbuing motion into our Universe.

Matter at rest is comprised of EM mass-energies that are always in motion and propagating in a tetrahedral EM standing wave.

To cause at will the birth and death of matter would be man's grandest deed, which would give him the mastery of physical creation, make him fulfil his ultimate destiny."

[Nikola Tesla]

Sub-Atomic Particles

Using equilateral energy all the mass-energy geometries & mass-Matter topologies of EM fields and particles can be physically modelled revealing the known Standard Model particle sand a few more.

Bosons are shown to be transverse EM fields that facilitate EM induction and Photons are revealed as longitudinal dual-charge pairs possessing a neutral EM charge and inherent magnetic moment.

The net unidirectional momentum of Bosons then distinguishes them from Photons that possess a bi-directional momentum

Closer examination of the geometries highlights a long-standing error in the mathematical formulation of QM energy formulas, namely the mistaken interchanging of Planck's quanta [*v*] for Einstein's frequency [*f*] in relation to Energy.


Tetryonic Charge families
Deltahedrals
EM Fields
1π
1 [1-0]
1 [0-1]
Quarks & Leptons
12π
up
8 [10-2]
up
8 [2-10]
4 [4-8]
down
down
4 [8-4]
charmed
8 [10-2]
charmed
8 [2-10]
4 [4-8]
strange
strange
4 [8-4]
top
8 [10-2]
top
8 [2-10]
4 [4-8]
bottom
bottom
4 [8-4]
12 [12-0]
e+
12 [0-12]
e-
ve
ve
0 [6-6]
0 [6-6]
12 [12-0]
μ
12 [0-12]
μ
vμ
vμ
0 [6-6]
0 [6-6]
12 [12-0]
τ
12 [0-12]
τ
vτ
vτ
0 [6-6]
0 [6-6]
Tetryons
4π
4 [4-0]
0 [2-2]
4 [0-4]
Mesons
24π
4 [14-10]
π+
0 [12-12]
π0
0 [12-12]
π0
4 [10-14]
π-
Baryons
36π
12 [24-12]
P+
Proton
Neutron
N°
0 [18-18]
N̄°
anti - Neutron
anti-Proton
12 [12-24]
P⁻

2D EM masses [bosons-photons] do not have the physical property of 3D topology possessed by Matter [Fermions]

Fermions can now be defined as the standing wave energy topologies that create all the known sub-atomic particles – the building blocks of large scale Matter and structure in the macro world.

Historically these particles have been classified according to their charges and masses, Tetryonic geometry now provides a 3D physical model of all the particles highlighting the physical source of the 1/3 charges of Quarks and revealing charge to be the foundational geometry of all Matter.

Tetryons are 4π charge topologies that are the foundational quanta of Matter and surprisingly have a mass-charge ratio identical to that of Leptons explaining how these particles have remained hidden from accelerator experiments.

Quarks are 12π charge geometries where the attractive strong charge interactions between their fascia form 8π particle topologies with entirely different properties to that of Leptons

Leptons also have 12π charge geometries but with repulsive fascia that result in them forming the quantum equivalent of a 6 loop rotor

Protons and Neutrons are 36π charge geometries [that result in 20π Baryon topologies] and have identical masses (against the current model of baryonic masses which derived from an entirely different process where Neutrons are formed by Protons absorbing electrons).

The Particle Zoo

Baryons – the building blocks of atomic nuclei can be formed from many tri- quark combinations and energy levels and this is of particular note when modern accelerators are used to probe atomic structures.

The higher energies they employ when colliding particles together results in higher 2D kinetic energies (and increased energy quanta) which recombine after collisions into a plethora of similar particles called the Particle Zoo.


TETRYONIC charge
Elemental charge
8
[10-2]
12
4
[4-8]
12
+2/3
-1/3
n
d
s
b
UP
DOWN
gen 1
CHARMED
STRANGE
gen 2
TOP
BOTTOM
gen 3
Quarks form Baryons according to their respective energy levels and EM apex orientations
+8 +8 +8 [10-2] [10-2] [10-2] 24 + 2 2/3 2/3 2/3
+8 -4 +8 [10-2] [4-8] [10-2] 12 + 1 2/3 1/3 2/3
The particle Zoo is the result of all possible 36π tri-quark energy geometries
-4 +8 -4 [4-8] [10-2] [4-8] 0 0 0 1/3 2/3 1/3
-4 -4 -4 [4-8] [4-8] [4-8] 12 - 1 1/3 1/3 1/3
Same fascia quarks combinations are not stable & very short lived
Any combinations of inter-generational quarks results in differing mass-energies in the created Baryonic Matter due to energy equalisation
EM Field
Planck
quanta
36π[[ε₀μ₀].[mΩv²]]
Baryons
ElectroMagnetic
mass
velocity
Twice the number of combinations are possible with the inclusion of anti-matter geometries
The Particle Zoo
216 possible Baryon combinations [excluding anti-matter] with each combination producing differing Baryonic nett energy levels

uuu	udu	ucu	usu	utu	ubu	suu	sdu	scu	ssu	stu	sbu
uud	udd	ucd	usd	utd	ubd	sud	sdd	scd	ssd	std	sbd
uuc	udc	ucc	usc	utc	ubc	suc	sdc	scc	ssc	stc	sbc
uus	uds	ucs	uss	uts	ubs	sus	sds	scs	sss	sts	sbs
uut	udt	uct	ust	utt	ubt	sut	sdt	sct	sst	stt	sbt
uub	udb	ucb	usb	utb	ubb	sub	sdb	scb	ssb	stb	sbb
duu	ddu	dcu	dsu	dtu	dbu	tuu	tdu	tcu	tsu	ttu	tbu
dud	ddd	dcd	dsd	dtd	dbd	tud	tdd	tcd	tsd	ttd	tbd
duc	ddc	dcc	dsc	dtc	dbc	tuc	tdc	tcc	tsc	ttc	tbc
dus	dds	dcs	dss	dts	dbs	tus	tds	tcs	tss	tts	tbs
dut	ddt	dct	dst	dtt	dbt	tut	tdt	tct	tst	ttt	tbt
dub	ddb	dcb	dsb	dtb	dbb	tub	tdb	tcb	tsb	ttb	tbb
cuu	cdu	ccu	csu	ctu	cbu	buu	bdu	bcu	bsu	btu	bbu
cud	cdd	ccd	csd	ctd	cbd	bud	bdd	bcd	bsd	btd	bbd
cuc	cdc	ccc	csc	ctc	cbc	buc	bdc	bcc	bsc	btc	bbc
cus	uds	ucs	uss	uts	ubs	bus	bds	bcs	bss	bts	bbs
cut	cdt	cct	cst	ctt	cbt	but	bdt	bct	bst	btt	bbt
cub	cdb	ccb	csb	ctb	cbb	bub	bdb	bcb	bsb	btb	bbb

Quarks always form symmetrical [ΩΩΩ] or [ΩΩΩ] charged Baryonic geometries
[same charges never combine except under high energy conditions]
ie. Proton is a [udu] not [uud] as is commonly stated

A sound understanding of EM mass-energy geometries & the charged topologies of all sub-atomic Matter particles reveals the true genesis of all of the Baryons to be found in the particle zoo.

Tetryonic geometries facilitate the precise 3D modelling of all the periodic elements, allotropes and compounds enabling the development of new classes of materials and medicines providing us with many new insights into Quantum Chemistry and large scale Matter in general.

Quantum Electro-Dynamics [QED]

Adding to the mysteries of quantum mechanics is a number of well-known QED effects that have also eluded physical explanation – to date


Wave Particle Mechanics
Planck-Einstein
nhν
hf
de Broglie
h/p
HΨ
ΔxΔp ≳ h
Heisenberg
Schrodinger
ODDπ[[ε₀μ₀].[mΩv²]]
Transverse boson quanta
E=hν
ν
Λ
128
Wavenumber
Wavelength
2π[[ε₀μ₀].[mΩv²]]
Longitudinal photon frequency
E=hf
f
64
Wavefunction
EVENπ[[ε₀μ₀].[mΩv²]]
EM waveform
Probabilty
Amplitude
HΨ
EΨ
E=p²
E
Quantum Energy Levels [n²]

In 1865, James Maxwell Clerk unified the then disparate theories of Electric and Magnetic fields into a theory of Electromagnetism and related then to the velocity of light.

The exact quantum geometry for EM wave geometries (and the photons comprising them) that explains their Wavefunctions and observed inference patterns represents one of the greatest challenges to developing a concise fully realised quantum theory of EM radiation.

Wave-Particle duality dating back to the 17th century is perhaps the best known example of quantum behaviour that has defied precise modelling despite intense effort by scientists around the World for over two centuries

The application of equilateral energy momenta to the charged geometries of Photons and EM waves not only explains these long standing mysteries but also removes the quantum fuzziness introduced by Heisenberg's Uncertainty principle, in turn clearing the way for Science to develop an advanced understanding of Electricity, its role in Quantum ElectroDynamics and provide new clean forms of energy from quantum processes.

Photo-electrons and spectral lines


Quantum Electrodynamics
Δhv
Quantum differentials
emission
absorption
bound photo-electrons
Photo-electrons
Spectral lines
Lyman
Balmer
Paschen
Brackett
Pfund
Humphries
un-named
1
2
3
4
5
6
7
8
12
48
108
192
588
972
Spectral line transitions
Δv
Σv
KEM
Planck, Rydberg, Lorentz, Newton, Leibniz
uniting classical physics and relativity through equilateral geometry
Velocity
KEM Energies
Spectral Lines
hf = ΔMv = Δp
spectral lines are produced by accelerating electrons
the charged geometry of mass-ENERGY-Matter in motion

The physical relationship between Spectral lines, Rydberg's Constant and the Kinetic energies of Photo-electrons as they interact with photons and atomic nuclei is quickly revealed when equilateral energy geometries are employed

It is the rigid geometry of equilateral Planck energy momenta that gives rise to the invisible forces of Faraday's Electric and Gauss' Magnetic fields as well as Newton's Action-at-a-Distance.

Quantised Angular Momentum, a direct measure of the long hidden equilateral geometry of Energy, is revealed as the source of Charge, the physical constants and even the geometry of EM mass-energy & Matter itself.

The geometry of Nuclear Forces and Constants

Charge interactions resulting from equilateral EM energy geometries have been mistakenly developed into three disparate nuclear forces:

The EM Force is the result of $2n\pi$ charge geometries acting along transverse or longitudinal directions (or in superposition) in the forms of Bosons and Photons

The Weak Force is the inductive coupling of the magnetic permeability of adjacent energy geometries

The Strong Force is the attractive force between opposite charged fascia of Tetryonic Matter. It can also form a repulsive force between similar charged fasciae resulting in charged Leptons [electrons].

Gravitation (mathematically identical to Coulomb's Force save for strength and source) can also be modelled as the geometric mean of super-positioned EM waves.

All of which are determined by the Fine Structure Constant – the mysterious hand of GOD – setting the strength of EM interactions and determining Charge on the quantum level.

Applying equilateral geometry to energy momenta quanta, the Tetryonic model of EM mass-ENERGY-Matter quickly evolves to explain many additional electrical properties such as Voltage, Current and Power

Quantum Chemistry

Applying tetrahedral Matter topologies to quantum chemistry leads to a number of significant advances in the understanding of chemical processes most notably:

- **Accurate models for all periodic elements and their associated allotropes**
- **Advanced molecular orbitals plots**
- **Exact rest masses for all elements and**
- **A new Periodic table based on the charged topologies of Matter**

Improving upon and extending the Aufbau principle with charged geometries leads to many refinements in chemical engineering and facilitates the building of accurate 3D models of all elements, isotopes and compounds.

Every element can be analysed from the quantum level upwards revealing its exact 3D topology, quark configuration, rest mass-Matter-energies and chemical properties.

And number of misconceptions can be quickly clarified and corrected in turn advancing our understanding to the physical mechanics underlying chemical processes like chemical bonding, element family properties and the structures of complex chemical compounds.

Hydrocarbons and Carbohydrates have already been modelled using equilateral charge topology with the results matching the established chemical models of Nobel gases, Core electrons, Lewis diagrams and the most recent electron photographs of these chemical properties of atoms.



Even DNA can be modelled in 3 dimensions leading to a greater understanding of the role of quantum mechanics in biological processes and the interaction of EM radiation on organic compounds.

A highly developed quantum model of chemical elements and compounds will allow us to model chemical and biological structures in hitherto unimagined detail and facilitate the building of complex (and increasingly accurate) models of all chemical compounds and biological processes.

A Unified field equation


m
Unified Field Equation
for Tetryonic EM mass-Energy-Matter
M
All forms of mass-ENERGY-Matter
are defined by their charged geometries and
the spatial co-ordinate systems used to measure their physics
Tetryonic
EM Field
Planck quanta
Tπ [[ε₀μ₀].[mΩv²]]
geometry
ElectroMagnetic mass
velocity
nπ
2D mass
Tπ
3D Matter
[[mΩv²]]
spatial co-ordinate systems
are defined by the velocity of energy

In physics a Unified Field Theory is a type of theory that allows all that is usually thought of as a fundamental force or elementary particle to be formulated in terms of a single equation that explains all their disparate properties.

It is considered the holy grail of Science, offering the promise of advances in Technology, Energy and Medicine unparalleled in Human history.

Equilateral energy provides the foundation for the creation of a single equation that expresses EM mass-ENERGY and Matter as the result of geometric & topological charge interactions.

Applying equilateral geometry to Planck energy momenta quanta has been shown to firmly resolve many of the current mysteries plaguing the Standard model and provides a firm foundation for the development of a single unified quantum theory uniting all quantum and macroscopic forces.

It effortlessly merges all the tested features of Classical mechanics with the statistical probabilities of quantum mechanics and scales up to the cosmological scale of General Relativity.

Equilateral charged energy geometries provide a quantifiable foundation for advances in:


0.987654321
SQUARE ROOTS
80/81
ODDS
SQUARES
n
EVEN DISTRIBUTION

- **Quantum Mechanics**
- **Quantum Electrodynamics**
- **Quantum Chemistry**
- **Quantum Cosmology**

Explaining the quantum mysteries of mass & Matter, Wave-Particle duality and gravitational Singularities by challenging the very foundational assumptions of Relativity and the role of charge in our Universe.

Mathematical principles such as re-normalisation, probabilities and square roots of negative numbers can all be geometrically modelled through Tetryonics leading to further advances in fields such as biology, medicine, quantum computing and telecommunications

Through the charged geometry of Tetryonics many of the erroneous theories that have been developed during the last 1oo years can be falsified at last providing a solid foundation for further advances in science and mathematics.

Gravitation


Fields of Interaction
Gravito-Electro-Magnetic
Fields
M
M
Q
Q
G
EM
M
S
N
EM
EM
Convergent Gravity fields produce a unilateral directional attraction between two or more sources of Matter
Divergent EM fields produce bidirectional interactive forces between charged objects in motion

The force of Gravity has been long-held to be the mysterious force that holds our Universe together, shaping the Stars and holding us to the Earth as we orbit our own SUN.

Tetryonic geometry reveals its quantum mechanics to be the result of electromagnetic fields and the effect produced by the geometry of Matter in these fields.

Newton saw Gravity as a force that acts instantaneously on distant bodies of Matter while Einstein dismissed the force between the bodies and explained it as the result of the 'curvature of Spacetime'.


Gravitational geometries
G
Newton viewed Gravitation as an attractive FORCE of Matter (inverse square field)
Einstein viewed it as the curvature of 4D spacetime (PRESSURE gradient)
Einstein's formula, attempting to correct observed discrepancies maps convergent & divergent forces as a singular pressure gradient
G
F = -G M₁M₂ / r²
Force vs. Gradient
M
M
Newton's formula based on observations maps only the observed nett gravitational attraction of large-scale Matter
-8πG / c⁴
K
G_ab = K T_ab
Both Newton and Einstein failed to define and distingush between EM mass & Matter

In fact the Gravitational field is comprised of 3 separate components, each of which produces differing forces of interaction, but all combine to produce the nett Gravitational field that we observe and describe as strictly convergent Gravity.

Gravity fields are created by the topology of Matter itself as it displaces and distorts the Vacuum energies surrounding it.

Electric fields diverge radially from all Matter as it is heated, or placed in motion by other forces creating an interactive field with both divergent and convergent equatorial regions of force and acceleration.

Dipole Magnetic fields located around the Polar Regions of all Matter also create a perturbative force on bodies close to them

Although Newton's and Einstein's theories were both correct in their respective analysis of the forces at work they both failed to define and distinguish between EM masses and Matter leading to the continued debate over the true nature and physical formulation of quantum gravity.


Standing EM waves produce Gravitational Matter
Stellar mechanics
Collapsed Matter produces EM radiation
Singularities
Gravity fields obey the inverse SQUARED law
Magnetic dipoles obey the inverse CUBED law
Electric fields obey the inverse SQUARED law

These three quantum forces [G+E+M] combine to produce a field of gravitational acceleration that was so eloquently modelled by Newton back in the 16th century through his inverse square law.

And these 3 distinct forces also combine to produce the stellar mechanics that power the Stars – a Gravito-Electro-Magnetic pinch.

The force of Gravity, created by the geometry of Matter draws Matter toward the core of Stars.

And the GEM pinch singularity at the core of the Star destroys Matter (collapsing its 3D geometry), turning it into radiant 2D ElectroMagnetic radiation (Light).

Energy from the Stars

Virtual particles, Dark Energy and Dark Matter (were all developed to explain the observed mechanics of our Universe) and can now be revealed to be differing manifestations of the electromagnetic force interacting at various angles to, and with, the standing-wave topologies that create it.


Virtual Particles
In Tetryonics the Uncertainity principle has been negated with the deterministic charged geometries of mass-ENERGY-Matter
Negative Zero Point Field
Positive Zero Point Field
Weak Nuclear Force
Strong Nuclear force
Force of Gravity
Electric fields
Van der Waals Force
EM induction
Coulomb Force
Cosmic Force
Magnetic fields
Divergent Coulomb forces are interactive
Material Gravitation
EM Interactions
M
Charged Matter geometries in vacuum energy fields create Gravity
m
Superpositioned EM fields create interactive EM forces
Vacuum field Energies
m²c⁴ = E² = p²c²
Virtual Particles are not required

Quantum fields of Planck energies combine to create charged 2D geometries of radiative ElectroMagnetic fields that in turn spread out interacting with each other to give us the fundamental laws of Attraction and Repulsion.

The 3D standing-wave topologies of Matter provide a rigid structure that displaces the surrounding Vacuum energies and creates a pressure gradient which we call Gravity.

And the destruction of these Matter topologies in turn creates radiant energies that propagate out into the surrounding space to weaken and form the Vacuum energies that permeate all of Space.

The eternal cycle of Matter creation and destruction within Stars and Galaxies is what drives the Universe we see today causing it to contract as it forms gravitational Matter and to expand as it restructures the standing-wave Matter into radiant forms of Energy (Light and heat).

The same process offers us clean, limitless energy for all our needs as well as unlimited resources from the restructuring of this energy into its varied elemental and compound forms.

Our toxic stockpiles of radioactive wastes can be completely eliminated from the environment and electrical power can be safely stored as mass within large-scale models of the deuterium nuclei and distributed worldwide to any location without the need for transmission lines.

Even hydro-electric storage schemes can be eliminated, returning water courses to their natural states of flow in turn reducing conflicts stemming from the flow of this precious resource worldwide.


The geometric field equation of EM mass-ENERGY-Matter
EM Field
Planck
Clean, limitless Energy
Tπ [[ε₀μ₀].[mΩv²]]
Unlimited resources
ElectroMagnetic mass
velocity
Unifying Science and Religion

Through the geometries of equilateral Planck energies and the application of the Tetryonic unified field equation of mass-ENERGY-Matter in motion to our needs, for the first time in Humanity's history, we have the chance to advance our civilization to new pinnacles of technology and understanding in turn leaving our World a better place than we found it to be.

The age old dilemma of technological advancement versus environmental pollution is at an end

We stand on the threshold of realising one of the greatest advances in scientific understanding ever witnessed but we must also endeavour to redress our current social challenges with an equally rigorous determination to ensure all of Humanity benefits from this discovery

……………………..……. ABRAHAM [2012]

Tetryonics …. Challenging and correcting the foundations of quantum theory

Electric field permittivity has a 2pi (rhombic) field geometry while magnetic field permeability is always the result of two separate equilateral magnetic fields that form a magnetic dipole moment

Where two or more rhombic electric fields interact a Coulombic –charge force of interaction results
Where two or more equilateral magnetic fields interact a Gaussian-Ampere forces of interaction results *[opposite fields attract - same fields repel]*

The classical model of the unidirectional electrostatic force fields of point charged particles is corrected to show a bidirectional arrangement of equilateral Planck energy momenta geometries within the electrostatic field that creates the bi-directional forces of charge interactions

Where two similar coupled equilateral energy momenta fields combine an electrostatic field is created
Where two opposite coupled equilateral energy momenta fields combine a magnetic dipole is created

The arrangement and asymmetry of Planck quantum charges with in any EM field determines the motion and acceleration of charged particles within the field of electrostatic force

The classical forces of attraction should be renamed forces of interaction
(as they result from bidirectional quantum vector forces)

All electromagnetic fields are comprised of a squared number of equilateral Planck energy momenta quanta (whose asymmetrical distribution of equilateral Planck quanta results in a net divergent Force) with a convergent vector force component

When modelled with equilateral Planck geometries electromagnetic fields follow the Biot-Savart Law:

- Rhombic electric fields follow the inverse squared law of propagation
- Equilateral magnetic fields follow the inverse squared law of propagation
- Magnetic dipole fields follow an inverse cubed law of propagation

The equilateral geometry of quantised angular momentum creates chirality at the quantum level in physics (rotation does not affect the charge of plank quanta, but mirroring and/or spatial coordinate translations do)

All positive charged fields can be modelled as having a clockwise inductive flux geometry
All negative charged fields can be modelled as having an anticlockwise inductive flux geometry
(with OMEGA representing equilateral geometries per second and PI reflecting their scalar areas]

All W bosons are comprised of an odd number of equilateral Planck quanta in a trapezoidal geometry
All Z bosons are comprised of an even number of equilateral Planck quanta in a dual-trapezoidal geometry (neutral Z bosons are equivalent in terms of Planck mass energy momenta to photons save their net geometry)

All charged fascia [Higgs bosons] are comprised of squared numbers of equilateral Planck quanta in an equilateral geometry.

The odd quanta W bosons within electromagnetic fields form quantum levels of charged mass-energy momenta

The Planck equation [E=n.hv] of quantised energy is a generalised equation of Planck geometries (and applies to all energy momenta arrangements equally)

Bosons and Quantum levels are a transverse measure of mass energy momenta in EM fields
Photons are a longitudinal measure of mass energy momenta within the same electromagnetic fields

Equilateral Planck energy momenta per second [E/c^2] equates to mass geometries
Equilateral Planck energies momenta per second squared [E/c^4] equates to Matter topologies

Interactive **mass energy geometries** can combine via the weak force to form standing wave Matter topologies

Standing wave **Matter topologies** can combine via the strong force to form elementary subatomic particles

The fundamental Matter quantum of all physics is the tetryon (a tetrahedral mass-energy Matter topology) which is formed from photons of electrostatic energy and can be found as positive, neutral or negative charges topologies

These three forms of charged tetryons form the foundation of all the physical Matter of our universe as they seek a state of equilibrium, Tetryons are not spherical point charges – they are tetrahedral, likewise the subatomic particles they form are not spherical point charges - they are **[T]**π Tetryonic charge topologies

The Tetryonic topologies created by tetryons as they combine to form elementary particles creates new forms of closed volume topologies that follow Euler's characteristic [V+F-E = 2] for Platonic solids

Quarks and leptons are comprised of 12 charged mass energy geometries
- quarks form *[8π]* octahedral Matter topologies
- leptons form *[12π]* dodecahedral Matter topologies

and

Baryons are comprised of 36 charged mass energy geometries
- forming *[20π]* Icosahedral Matter topologies

Anti-UP quark's are comprised of 2 positive and 8 negative charges
creating a net charge of **-8** *[-2/3 elementary charge]*
DOWN quark's are comprised of 4 positive and 8 negative charges
creating a net charge of **-4** *[-1/3 elementary charge]*
Anti-DOWN quark's are comprised of 8 positive and 4 negative charges
creating a net charge of **4** *[1/3 elementary charge]*
UP quark's are comprised of 10 positive and 2 negative charges
creating a net charge of **8** *[2/3 elementary charge]*

Positrons are comprised of 12 positive charges
creating a net charge of **+12** *[positive integer elementary charge]*
neutrinos are comprised of 6 positive and 6 negative charges
creating a net charge of **0** *[no elementary charge]*
Electrons are comprised of 12 negative charges
creating a net charge of **-12** *[negative integer elementary charge]*

Protons are comprised of 24 positive charges and 12 negative charges
creating a net charge of **+12** *[positive integer elementary charge]*
Neutrons are comprised of 18 positive and 18 negative charges
creating a net charge of **0** *[no elementary charge]*
anti-Neutrons are comprised of 18 positive and 18 negative charges
creating a net charge of **0** *[no elementary charge]*
anti -Protons are comprised of 12 positive charges and 24 negative charges
creating a net charge of **-12** *[negative integer elementary charge]*

Rest lepton topologies have a completely neutralised magnetic dipole structure and all leptons (charged or neutral) have identical physical Matter topologies
Their rest masses are the result of the number of plank quanta comprising each Matter topology with applied forces creating additional asymmetrical KEM fields resulting in kinetic energies, magnetic moments and vector velocities of motion

As the energies of motion are added to equilateral KEM fields the Planck quanta themselves are physically WAVE-length Lorentz contracted

(Lorentz contractions apply to mass energy geometries only - NOT to Matter topologies)

Matter topologies are Lorentz invariant to velocity changes (or acceleration)
The relativistic distortion of spherical point charges in physics is no longer applicable, in turn undermining a basic tenet of special relativity as postulated by Albert Einstein

It is the equilateral secondary KEM fields of motion created by applied forces to material Matter topologies (and the asymmetrical distribution of plank charges therein) that creates the magnetic moments associated with charged particles in motion, not the relativistic distortion of spherical bodies of Matter as postulated by Einstein in special relativity

These secondary KEM fields of motion also contain the kinetic EM energies and vector [square root] linear momentum of material particles in motion - the mass energy momenta density and physical geometries of Matter topologies is unaffected by applied forces or changes to velocity-momenta

The changing Lorentz contracted mass energies of kinetic EM fields contributes to the total relativistic mass energy of Matter topologies but in no way changes the mass energy distribution of the Matter component of particles in motion itself - leading in turn to varying generations of subatomic particles with in the particle families themselves

The net asymmetric KEM field geometry of each particles in motion is reflective of the charged distribution of the Matter topology of the particle itself.

Mesons are created when quark and anti-quark particles combine via the strong force interaction between their charged fascias to create unique 14 pi Matter topologies (neutral or charged pions)

These strong interactions between opposite charge fascia of material particles and the resulting Matter topologies are evidence of the fact that Matter-antimatter combinations do not necessarily result in the explosive annihilation of the particles concerned (in fact the combining of opposite charge quarks is a necessary step in the formation of the baryons)

All Baryons are Matter topologies created from the combination of tri-quark topologies
The quark's combine via their opposite charged [Higgs] fascia to create neutral and charged elementary topologies
Due to this opposite charge interaction the charged distribution of baryonic topologies does not follow the textbook given arrangements of [UUD] & [DDU] instead they are arranged as follows:

Protons	**UP**	**+**	**DOWN**	**+**	**UP**
Neutrons	**DOWN**	**+**	**UP**	**+**	**DOWN**
anti-Neutrons	**anti-DOWN**	**+**	**anti-UP**	**+**	**anti-DOWN**
anti-Protons	**anti-UP**	**+**	**anti-DOWN**	**+**	**anti-UP**

The specific arrangement of charged fascia within these respective Matter topologies goes on to facilitate nuclear bonding via the residual strong force between atomic nuclei, following the charge arrangement given in modern textbooks does not allow the formation of baryons or their subsequent bonding to form larger scale atoms and molecules

Protons and neutrons are revealed to have quark arrangements that are mirror symmetries of each other, revealing the neutral charge neutron to have a complementary negative charge arrangement to that of protons.

The increased Planck mass energy contents of various families of quarks facilitates the creation of a huge number of possible Baryon topologies resulting in the particle zoo of subatomic elements created in particle collisions within accelerator experiments - all of these elements can be easily modelled and accounted for using Tetryonic mass-energy Matter topologies

Additionally, the particles often referred to as gluons within the standard model can be easily accounted for and explained as being neutral tetryons within Tetryonic theory - where these neutral charge Matter topologies form a neutral Matter dielectric between charged tetryons to facilitate the strong force interaction and the formation of larger particles

Neutral tetryons (gluons) can also form particles in their own right (neutrinos and glue-balls), as can charged tetryons (charge-ball particles), most of which are short lived

Tetryonics reveals the previously hidden geometry and topology of electromagnetic fields and subatomic particles and the geometric relationship and interplay between electric permittivity and magnetic permeability within all EM field that results on the speed of light in any medium.

As well as the revealing a geometric source of all physical constants within physics itself, Tetryonic charge geometries show the weak force to be a magnetic dipole [edge] interaction between mass energy geometries and Matter topologies and the strong force to be a charge [fascia] interaction between Matter topologies themselves

The equilateral [quantised angular momentum] of ***inductive*** Planck mass energy geometries within squared [HIGGS] fascia of Matter topologies is what creates ***inertial*** properties of Matter at the quantum level

The strong force between charged parallel Higgs fascia of Matter topologies results in 'hidden' partitions of mass energy with in the Matter topologies of quark's and baryons leading to the inability of mathematics online to accurately model and understand the physics of creating these particles at the quantum level

Tetryonic charged mass energy geometries allows for the accurate 2D and 3D modelling of all Matter topologies and fields of Force interactions within physics

It reveals that the deuterium atom [not the hydrogen atom] is the quantum building block of all elementary Matter - the unique charge topology of deuterium (consisting of a proton, neutron and electron) can be related to the electromechanical topology and function of quantum synchronous converters.

These quantum synchronous converters absorb and emit mass energies via the rotating electrons [quantum rotors] bound to the nuclei by way of radiant bosons and photons [heat and light]

The net charge of Deuteron nuclei facilitates their binding together to form helium and larger atoms, while stored mass energy quanta within their Matter topology results in raised quantum grounds states that can all be modelled mathematically using Schrodinger’s wavenumbers

The simpler geometric charge topology reveals visually how the mass energy content of baryons directly affects the angular momentum and energy levels of photo electrons bound to atomic nuclei, in turn revealing that larger elements be created in two ways - namely by the addition of a neutron to a Hydrogen atom (as classically modelled in modern chemical physics) or through the raising of Planck mass-energy quanta within the deuterium Matter topology itself

Deuterium nuclei without any bound photo-electrons form quantum batteries with EM mass energies can be stored indefinitely without being released.
These nuclei can be arranged atomically in either a series, parallel or empty parallel configuration each of which affects the ground energy states of the respective nuclei created.
Where photo-electrons (quantum rotors) are attracted and bind to these nuclei (quantum batteries) the stored mass energies can then be released in a controlled manner via spectral line emissions, or energy can be added via spectral line absorption.

As photo-electrons are bound to the deuteron nuclei the energy levels are affected directly by the mass energy levels of the nuclei that they bind to, in turn affecting their KEM field energies
The square root linear momentum of KEM field energies normally creates a vector motion but in the case of bound electrons this vector motion is turned into an angular motion resulting in electron spin within the nucleus.

The direction of the spin is always reference with respect to the nuclear magnetic moment resulting in up and down electron spins and their associated magnetic dipole moments

The kinematics of KEM fields provides an easy visual explanation of Newton's 2nd law of motion - namely that deceleration can be seen as the removal of odd number quanta from the squared kinetic energy fields and acceleration can be viewed as the addition of odd numbered quanta to squared kinetic energy fields.

The addition or subtraction of odd numbered Planck quanta from squared energy fields results in changing square root linear momentum for the particles that these fields are associated with - this changing linear momentum over time can be equated to acceleration leading to Newton's formulation of Force = mass x acceleration [F = ma = dp/t = dmv/t]

Using the equilateral geometry of Planck's constant we can now unify classical mechanics with quantum mechanics and reveal the underlying dynamics of relativistic mass energies of motion (as well is providing an electromechanical explanation of inertia in the physics of Matter in motion)

Newton's vector linear momentum [p=mv] forces are revealed to be the geometric square root of Leibnitz's scalar energies [E/mv^2] with their associated inertial mass being a measure of the scalar energies per second [m=E/v^2]

Linear momentum [mv] is differentiated from vector velocities [v] through the equilateral geometry of energy per second [m] in tetryonics, with the total linear momentum of any EM field or system of particles being the vector some of the square root Planck linear momentum of the quanta in the fields comprising the system

Once the equilateral field geometry of KEM fields is revealed it is easy to show that the total energy of the field [E=mv^2] is the result of the kinetic energies [$_{1/2}$Mv^2] plus the magnetic moment [$_{1/2}$Mv^2] of any material topology in motion

This in turn allows for a rigid geometric differentiation of quantised angular momentum [Ω] in Planck quanta, the linear momentum [p] of any system and the classical angular momentum [vector rotation about a point] in physics

These geometric definitions of mass energy momenta in physical systems as portrayed in Tetryonic theory reveal a differing geometric relationship to that commonly portrayed in modern physics]i.e. neutralising right angled Pythagorean triangles]

Additionally Lorentz corrections factors are restricted to planar 2-D mass energies of KEM fields associated to particles in motion where changes of velocity force result in the addition or subtraction of equilateral Planck quanta from the KEM field geometry resulting in the physical expansion or contraction of Planck geometries within the field

Tetryonic theory's geometric definition and application of quantised angular momentum with respect to mass energy momenta in physics allows for the physical modelling of mass energy and Matter at all scales of physics and their unification of classical, quantum and relativistic mechanics

The 'squared' energies of quantum mechanics and statistical distributions of the math associated with quantum mechanics is now revealed in an entirely new light facilitating the macro scale modelling of all hitherto unseen quantum particles and processes.

The geometric relationships between charge, mass geometries and Matter topologies is easily visualised and applied to all physics revealing quantised angular momenta [QAM] to be the hidden variable of Planck's constant [h].......

The modelling of quantised angular momentum as an equilateral geometry allows for the elimination of Heisenberg's uncertainty principle and Bell's inequality from the foundational tenants of quantum mechanics

Both the position and momentum of particles and fields can be now modelled at any stage of a system's spatio-temporal development and evolution using these simple equilateral charged geometries of mass energy momenta

Precise rest mass energies of any Matter topology can be calculated from 1st principles allowing for accurate modelling of all quantum systems and even periodic elements - expanding our knowledge of chemical systems and processes

The Planck-Compton frequency, de Broglie wavelength, absolute rest mass and charge Matter topology of all periodic elements, compounds and molecules can now be calculated with absolute certainty and precision and can be related back to Avogadro's number for all elements in chemistry

The exponential energy levels of atomic nuclei and atomic processes of energy release can also now be shown to be the result of an underlying geometric Planck scale geometry inherent to all mass energy Matter within physics

Einstein's mass energy equivalence formula is shown to be a geometric relationship between measurements of energy per second and inertial mass........ combined with Tetryonics new definition of Matter as energy per second squared we can now show that Einstein's famous formulation is an incomplete formulation of the mass-ENERGY-Matter relationship that applying only to specific processes within our physical universe

The Lorentz corrections on which special relativity is based are shown to be WAVE-length and QAM corrections for the changing physical geometries of scalar mass energies per unit of time in spatial co-ordinate systems (c^2) and that additional time-based dimensional analysis must be taken into account in order to define and differentiate between electromagnetic mass and Matter in physics

The application of squared (equilateral) geometries to physics in the role of quantised angular momentum has been overlooked since the inception of physics itself, but with the inclusion of this geometry a rigid geometric grammar can now be imposed upon the mathematics of physics leading to the correction of many erroneous mathematical assumptions

An exact value from first principles for Planck's constant can be calculated and Avogadro's number can be confirmed and related to the absolute rest mass of hydrogen atoms.

A geometric representation of Coulomb's charged field interactions and the impedance of free space can also be provided for all physical processes allowing for a fast and accurate visualisation of energy mechanics at all scales of physics

Tetryonics theory’s equilateral charged mass energy and polyhedral Matter topologies allow for the modelling and differentiation of energy in all its forms within any spatial coordinate system providing a vast improvement over relativity's use of stress energy tensors and non-Euclidean geometries in modelling physical systems

All fields and particles can be defined and differentiated in terms of their charged mass energy geometries and Matter topologies respectively and the differentiation of elemental families into their generations can be easily accounted for through the addition of mass energies of motion to secondary KEM fields associated with each particle grouping

Inertial resistance to force can be modelled and explained through the equilateral geometry of quantised angular momentum when viewed as an electromechanical equivalent to an inductive loop of energy

Electromagnetic inertial mass can now be clearly defined as a measure of the inductive EM energy density of any charged 2D planar Planck geometry in any spatial co-ordinate system of measurement

3D Matter can now be viewed and modelled as the closed topology created by 2D mass energies through charge interactions in any spatial co-ordinate system of measurement per second squared

Additionally physical terms such as 'mass-less' particles are shown to be a misnomer as any field or particle must by definition contain energy per unit of time - and should be more appropriately re-termed Matter-less or weightless particles

Tetryonics theory defines, differentiates and unifies energy in all its forms (mass, Matter & Force) through the equilateral geometry of quantised angular momentum at the quantum level, allowing for the development of a unified field equation that models physics on all scales and reveals a common geometric thread to all the disparate fields of physics that to date have defied unification

Equilateral (SQUARED) energy fields of Planck quanta comprised of statistical distributions of (ODD) transverse bosons and (EVEN) longitudinal photons account for all the quantum mechanical processes of physics including EM field geometries and material particle topologies and electron spin

Principle quantum levels [1st Schrodinger wave-numbers] are shown to be the result of the series addition of deuterium nuclei in atomic elements with their resulting energy levels determining the squared energy levels of bound photoelectron KEM fields – in turn forming the foundation of discrete quantum jumps of electrons bound to atomic nuclei

The bound photo-electron can only transition between allowed squared energy levels permitted by the energy levels of deuterium nuclei to which they are bound and once free from the atomic nuclei the electron can emit or absorbed a continuous spectra of light photons - but while bound to the deuterium nuclei in atoms it can only have specific [squared] KEM energy levels

The complex, asymmetric tri-quark (9 tetryon) Matter topology of baryons directly affects the magnetic moment of protons and neutrons in motion making them considerably weaker than the symmetric axial Bohr magnetron of electrons in motion

As the Bohr magneton of photo-electrons is determined by the squared energies of its secondary KEM field confusion has arisen with respect to the allocation of spins to subatomic particles, Tetryonic geometries now correct for this and suggest that the electron historically viewed as a spin 1/2 particle is in fact a spin 3 particle under the formal definitions of spin rotations i.e. rotating at 120° can bring it back to an identical quantum state as the initial state measured]

Again Tetryonic theory and its energy geometries in addition to explaining and correcting electron spins also shows that the term electron spin can now be taken literally when modelled with Tetryonic geometries to provide an accurate description of the origin of magnetic moments for electrons, in turn undermining the foundational postulate of special relativity that these magnetic moments are the result of the distortion of spherical point charges and that relativistic Lorentz contractions apply to Matter topologies

Dirack's constant, or Planck's reduced constant [h/2π], is revealed to be a measure of the electric permittivity of a relativistic electron's KEM field, and the measurement of the associated magnetic dipole of the same KEM field results in the mistaken concept of 1/2 spins in the measurement of Bohr magnetons

The magnetic vector created by the Bohr magneton [or KEM field dipole] when measured with respect to the nuclear magneton [Proton magnetic moment] produces either a higher energy [parallel] or lower energy [anti-parallel] state for all atomic nuclei

It is the arrangement of these parallel or anti-parallel magnetic dipoles within atomic nuclei that determines the exact frequency-wavelength (energy level) of emitted spectral lines with the interaction of a particle’s magnetic dipole moment with external electromagnetic fields creating Lorentz forces

As electrons and protons have identical quantum Matter topologies [elementary charges] but differing mass energy contents the electron is able to create a much larger secondary KEM field (with associated magnetic dipole moment) for the same velocity [1/2Mv^2]

The energy level differences created by the parallel or anti-parallel spin coupling of electrons with protons or deuterium nuclei within atomic elements creates the hyperfine splitting and Zeemen effects observed and spectral lines

As the electron is now shown to be a complex non-spherical particle topology when it binds with protons to form hydrogen the unique Matter topology of both the proton and the electron [Hydrogen] create a small but detectable precession in the motion of the spinning electron as compared to that of the motion of the same electron in a deuterium nuclei

Additionally, as all periodic elements, compounds and molecules are comprised of deuterium nuclei (not hydrogen as currently supposed) the orientation and spin direction of electrons bound within these nuclei results in the diamagnetic and paramagnetic properties of various macro-scale materials

Tetryonics theory reveals that the mass charge ratio is of particles are measure of the constituent mass energy geometries that go into making the particle's final Matter topology that we observe a measure

But unlike the current mathematical approach the geometric approach of Tetryonics reveals the hidden mass energy partitions within the Matter topology of all subatomic particles and that particles such as tetryons (the quantum building blocks of all Matter) are in fact hidden within the debris of current collider results.

4 quantum charge tetryons have the same1/3 partial elementary charge as some quarks, and can be measured as having the same mass charge ratio's as charged leptons such as positrons and electrons in collider experiments.

………. To be continued [QED, Chemistry, Cosmology, Mathematics, Biology and economic theory]

answers@tetryonics.com

ABRAHAM [2014]

principia geometrica [3b] - quantum chemistry 2
principia geometrica [4] - quantum cosmology 230
principia geometrica [5] - quantum mathematics 461
Principia Scientifica [5] - Quantum Mathematics 624
Principia Scientifica [3a] - Quantum Chemistry 787
principia geometrica [1] - quantum mechanics 991
principia geometrica [2] - quantum electrodynamics 1232
principia geometrica [3a] - quantum chemistry 1451

Copyright ABRAHAM [2008] - All rights reserved

TETRYONICS

The charged topology of periodic & compound Matter


Q
RE
M
KE
13 Md Tm 13
Ac La 1 1
Pa Pr 3 3
Rg Au Ag Cu 9 9
Bk Tb 9 9
Lr Lu Y Sc 1 1
Db Ta Nb V 3 3
Es Ho 11 11
Mt Ir Rh Co 7 7
Bh Re Tc Mn 5 5
Am Eu 7 7
At Uus I Br Cl F 5 5
Cs Rb Fr D K Uun Li Na 1 1
Po Lv Te Se O S 4 4
Np Pm 5 5
Tl Uut In Ga B Al 1 1
Pb Fl Sn Ge C Si 2 2
Ba Sr Ra He Ca Ub Be Mg 2 2
Bi Uup Sb As N P 3 3
Rn Uuo Xe Kr Ne Ar 6 6
Pu Sm 6 6
Hs Os Ru Fe 6 6
Ds Pt Pd Ni 8 8
Cm Gd 8 8
Fm Er 12 12
Sg W Mo Cr 4 4
Cn Hg Cd Zn 10 10
Rf Hf Zr Ti 2 2
Cf Dy 10 10
U Nd 4 4
Th Ce 2 2
No Yb 14 14

Foundational Quantum Chemistry

Abraham

ISBN 978-0-987288-3-1
[Second Edition © 2012]

Periodic element Families


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
f 7
d 5
p 3
s 1
1-14 Actinoid
1-14 Lanthanoid
9-10 Post Transition Metal
1-8 Transition Metal
6 Noble Gas
5 Halogen
1-4 Non-Metal Metaloid Poor-Metal
2 Alkaline Earth
1 Alkali Metal
Shell
Energy level
Orbitals
sub orbital
Family


f
d
s
p
PTM
PTM
Halogens
Transition Metals
Transition Metals
Semi-Metals
Semi-Metals
Alkali Metals
Alkaline Earths
Noble Gases
Actinides
Lanthanides
Actinides
Lanthanides

Atomic Shells
O
P
Q
K
R
N
L
M

5
6
7
1
8
4
2
3
Energy levels



Alkali Metals

The alkali metals are silver-colored (caesium has a golden tinge), soft, low-density metals, which react readily with halogens to form ionic salts, and with water to form strongly alkaline (basic) hydroxides.

These elements all have one electron in their outermost shell, so the energetically preferred state of achieving a filled electron shell is to lose one electron to form a singly charged positive ion.


Atomic shell
s1
Energy level
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
electron configuration


R
8
Q
7
P
6
O
5
N
4
M
3
L
2
K
1
Shell
Quantum level

S
1
Alkali Metal

s Orbital

n1-8

s1 sub-orbital


Cs
Fr
Rb
D
1
K
Li
Na
Ba
Sr
Ra
He
2
Ca
Be
Mg

8

Alkaline Metals



Quantum level

The alkali metals are all highly reactive and are never found in elemental form in nature.

As a result, in the laboratory they are stored under mineral oil. They also tarnish easily and have low melting points and densities. Potassium and rubidium possess a weak radioactive characteristic (harmless) due to the presence of long duration radioactive isotopes.

Alkaline Earths

The alkaline earth metals are silver colored, soft metals, which react readily with halogens to form ionic salts, and with water, though not as rapidly as the alkali metals, to form strong alkaline (basic) hydroxides.


Atomic shell
s2
Energy level
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
electron configuration


R
8
Q
7
P
6
O
5
N
4
M
3
L
2
K
1
Shell
Quantum level

S
2
Alkaline Earth

s Orbital

n1-8

s2 sub-orbital


Ba
Sr
Ra
He
2
Ca
Be
Mg
Rb
Fr
H
1
K
Li
Na

8

Alkaline Earths

6
5
7
1
4
8
2
3
Quantum level

All the alkaline earth metals have two electrons in their valence shell, so the energetically preferred state of achieving a filled electron shell is to lose two electrons to form doubly charged positive ions.

Metalloids

A metaloid is a material with a small overlap in the energy of the conduction band and valence bands.

Unlike a regular metal, metaloids have been described electrically as charge carriers of both types (holes and electrons), so it could be argue that they should be called 'double-metals' rather than metaloids.

As metaloids have fewer charge carriers than metals, they typically have lower electrical and thermal conductivities.


Atomic shell
Energy level
p1
p2
p3
p4
Q 7
P 6
O 5
N 4
M 3
L 2
8
1
2
electron configuration


Q 7
P 6
O 5
N 4
M 3
L 2
Shell
Energy level

p
1-4
Non-Metal
Metaloid
Poor-Metal

2 p-Orbitals

n2-7

p1-4 sub-orbitals


Po
Te
Lv
4
Se
O
S
Tl
In
1
Ga
B
Al
Pb
Sn
Fl
2
Ge
C
Si
Bi
Sb
3
As
N
P

24

Semi-Metals

6
5
7
4
2
3
Energy levels

Charge carriers typically occur in much smaller numbers than in a real metal. In this respect they resemble degenerate semiconductors more closely.
This explains why the electrical properties of metaloids are partway between those of metals and semiconductors.

Halogens

Owing to their high reactivity, the halogens are found in the environment only in compounds or as ions.

Halide ions and oxoanions such as iodate (IO3−) can be found in many minerals and in seawater.

Halogenated organic compounds can also be found as natural products in living organisms. In their elemental forms, the halogens exist as diatomic molecules, but these only have a fleeting existence in nature and are much more common in the laboratory and in industry.


Atomic shell
Energy level
R
Q
P
O
N
M
L
K
p5
1
1
1
1
1
1
8
7
6
5
4
3
2
1
electron configuration


Q
7
P
6
O
5
N
4
M
3
L
2
Shell
Quantum level

p3 Orbital

n2-7

p5 sub-orbital


At
Uus
I
5
Br
F
Cl
No
Yb
13
Tb
Ce
1
Nd
3
Rg
Au
9
Ag
Cu
Ac
La
1
Sc
Db
Ta
3
Nb
V
Mt
Ir
7
Rh
Co
Bh
Re
5
Tc
Mn
Cf
Dy
Fm
Er
11
Cm
Gd
7
Pu
Sm
5
Po
Te
Se
S
O
Cs
Rb
Fr
H
1
K
Li
Na
Pb
Sn
Ge
2
Si
C
Tl
In
Ga
1
B
Al
Ba
Sr
Ra
He
2
Ca
Be
Mg
Bi
Sb
As
3
N
P
Rn
Xe
Kr
6
Ne
Ar
Am
Eu
6
Bk
Tb
8
Os
Ru
6
Fe
Ds
Pt
Pd
8
Ni
Sg
W
Mo
4
Cr
Rf
Hf
Zr
2
Ti
Md
Tm
12
Es
Ho
10
Hg
Cd
10
Zn
Np
Pm
4
Pa
Pr
2
Lr
Lu
14

6

Halogens

6
5
7
4
2
3
Quantum level

At room temperature and pressure, fluorine and chlorine are gases, bromine is a liquid and iodine and astatine are solids.

Group 17 is therefore the only periodic table group exhibiting all three states of matter at room temperature

Nobel Gases

The properties of the noble gases can be well explained by modern theories of atomic structure: their outer shell of valence electrons is considered to be "full", giving them little tendency to participate in chemical reactions, and only a few hundred noble gas compounds have been prepared.

The melting and boiling points for each noble gas are close together, differing by less than 10 °C (18 °F); consequently, they are liquids only over a small temperature range.


Atomic shell
Energy level
R
Q
P
O
N
M
L
K
p6
1
1
1
1
1
1
8
7
6
5
4
3
2
1
electron configuration


Q
7
P
6
O
5
N
4
M
3
L
2
Shell
Quantum level

p
6
Noble Gas

completed p3 Orbital

n2-7

p6 sub-orbital


No
Yb
13
Th
Ce
1
U
Nd
3
Rg
Au
Ag
Cu
9
Ac
La
Y
Sc
1
Db
Ta
Nb
V
3
Cf
Dy
9
Mt
Ir
Rh
Co
7
Bh
Re
Tc
Mn
5
Fm
Er
11
Cm
Gd
7
At
I
Br
Cl
F
5
Po
Te
Se
S
O
4
Pu
Sm
5
Cs
Rb
Fr
H
K
Na
Li
1
Tl
In
Ga
Al
B
1
Pb
Sn
Ge
Si
C
2
Ba
Sr
Ra
He
Ca
Mg
Be
2
Am
Eu
6
Bi
Sb
As
P
N
3
Rn
Xe
Uuo
Kr
Ne
Ar
6
Bk
Tb
8
Hs
Os
Ru
Fe
6
Ds
Pt
Pd
Ni
8
Md
Tm
12
Sg
W
Mo
Cr
4
Rf
Hf
Zr
Ti
2
Es
Ho
10
Hg
Cd
Zn
10
Np
Pm
4
Pa
Pr
2
Lr
Lu
14

6

Nobel Gases

Neon, argon, krypton, and xenon are obtained from air using the methods of liquefaction of gases and fractional distillation.

Helium is typically separated from natural gas, and radon is usually isolated from the radioactive decay of dissolved radium compounds.

Quantum level

Copyright ABRAHAM [2008] - All rights reserved

Transitional Metals

In chemistry, the term transition metal commonly refers to any element in the d-block of the periodic table, including the group 12 elements zinc, cadmium and mercury.

This corresponds to groups 3 to 12 on the periodic table, which are all metals.

More strictly, IUPAC defines a transition metal as "an element whose atom has an incomplete d sub-shell, or which can give rise to cations with an incomplete d sub-shell."

The first definition is simple and has traditionally been used. However, many interesting properties of the transition elements as a group are the result of their partly filled d subshells.


Atomic shell
Energy level
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
d7
d1
d3
d5
d6
d4
d2
d8
2
electron configuration


P
6
O
5
N
4
M
3
Shell
Quantum level

d
1-8
Transition Metal

4 d-Orbitals

n3-6

d1-8 sub-orbitals


Ac
La
1
Y
Sc
Db
Ta
3
Nb
V
Bh
Re
5
Tc
Mn
Mt
Ir
7
Rh
Co
Hs
Os
6
Ru
Fe
Sg
W
4
Mo
Cr
Rf
Hf
2
Zr
Ti
Ds
Pt
8
Pd
Ni
Rg
Au
9
Ag
Cu
Hg
Cd
10
Zn

32 Transition Metals

The name transition comes from their position in the periodic table. In each of the four periods in which they occur, these elements represent the successive addition of electrons to the d atomic orbitals of the atoms.

In this way, the transition metals represent the transition between group 2 elements and group 13 elements.

6
5
4
3
Quantum level

Copyright ABRAHAM [2008] - All rights reserved

Post-Transition Metals

In chemistry, the term post-transition metal is used to describe the category of metallic elements to the right of the transition elements on the periodic table.

There are two IUPAC definitions of "transition element" that have been in apparent conflict with one another since September 2007.

According to the first definition, transition metals are elements in group 3 through group 11.
In this case, post-transition metals include all of group 12—zinc, cadmium, mercury, and ununbium

According to the second definition, transition elements either have an incomplete d-subshell or have the ability to form an incomplete d-subshell.

Post Transitional metals are normally defined as completed d orbitals

Tetryonics suggests it may be appropriate to include all the d5 orbital elements in this grouping


Atomic shell
Energy level
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
d9
2
2
2
2
d10
electron configuration


P
6
O
5
N
4
M
3
Shell
Quantum level

d 9-10 Post Transition Metal

d5 Orbital

n3-6

d9-10 sub-orbitals


No
13
Yb
Th
1
Ce
U
3
Nd
Rg
Au
9
Ag
Cu
Ac
La
1
Db
Ta
3
Cf
Dy
9
Mt
Ir
7
Rh
Sc
Nb
V
Bh
Re
5
Tc
Fm
11
Er
Cm
Gd
7
At
I
Br
Cl
Po
Te
Se
S
O
Cs
Rb
Fr
H
K
Li
Na
Pu
5
Sm
Tl
In
Ga
Al
B
Pb
Sn
Ge
Si
C
Ba
Sr
Ra
He
Ca
Be
Mg
Am
Eu
6
Os
Ru
6
Fe
Bi
Sb
As
P
N
Rn
Xe
Kr
Ar
Ne
Pt
Pd
8
Ni
Bk
Tb
8
Md
Tm
12
Sg
Mo
Cr
Rf
Hf
Zr
Ti
Es
Ho
10
Hg
Cd
10
Zn
Np
Pm
Pa
Pr
Lr
Lu
14

8 Post-transitional Metals

In 2007, mercury(IV) fluoride was synthesized.[2][3] This compound contains a mercury atom with an incomplete d-subshell, and ununbium is predicted to have the capacity to form a similar electronic configuration.

In this case, post-transition metals include only zinc and cadmium within group 12.

6
5
4
3
Quantum level

Copyright ABRAHAM [2008] - All rights reserved

Lanthanoids


Atomic shell
Energy level
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
f7 f9 f1 f13 f3 f11 f5
2 2 2 2 2 2 2
f6 f12 f4 f14 f2 f10 f8
electron configuration

All lanthanoids are f-block elements, corresponding to the filling of the 4f electron shell

The lanthanoid series (Ln) is named after Lanthanum.

The trivial name "rare earths" is sometimes used to describe all the lanthanoids together with scandium and yttrium.

These elements are in fact fairly abundant in nature, although rare as compared to the "common" earths such as lime or magnesia. Cerium is the 26th most abundant element in the Earth's crust, neodymium is more abundant than gold and even thulium (the least common naturally-occurring lanthanoid) is more abundant than iodine.

f
1-14
Lanthanoid

N
4
Shell
Quantum level

7 f-Orbitals

n4

f1-14 sub-orbitals


13 Yb
1 Ce
3 Nd
9 Dy
11 Er
7 Gd
5 Sm
6 Eu
8 Tb
12 Tm
10 Ho
4 Pm
2 Pr
14 Lu

14 Lanthanoids

The term "rare earths" arises from the minerals from which they were isolated, which were uncommon oxide-type minerals.

According to the IUPAC terminology, the lanthanoid (previously lanthanide) series comprises the fifteen elements with atomic numbers 57 through 71, from Lanthanum to Lutetium.

The use of this name is deprecated by IUPAC, as they are neither rare in abundance nor "earths" (an obsolete term for water-insoluble strongly basic oxides of electropositive metals incapable of being smelted into metal using late 18th century technology).

4
Quantum level

Copyright ABRAHAM [2008] - All rights reserved

Actinoids

According to IUPAC nomenclature, the actinoid (previously actinide) series encompasses the 15 chemical elements that lie between actinium and lawrencium included on the periodic table, with atomic numbers 89 - 103.

The actinoid series derives its name from the first element in the series, actinium, and ultimately from the Greek ακτις (aktis), "ray," reflecting the elements' radioactivity.

The actinoids display less similarity in their chemical properties than the lanthanoid series (Ln), exhibiting a wider range of oxidation states, which initially led to confusion as to whether actinium, thorium, and uranium should be considered d-block elements. All actinoids are radioactive.


Atomic shell
Energy level
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
f7 f9 f1 f13 f3 f11 f5
2 2 2 2 2 2 2
f6 f12 f4 f14 f2 f10 f8
electron configuration

f 1-14 Actinoid


o
5
Shell
Quantum level

7 f-Orbitals

n5

f1-14 sub-orbitals


No 13
Th 1
U 3
Cf 9
Fm 11
Cm 7
Pu 5
Am 6
Bk 8
Md 12
Es 10
Np 4
Pa 2
Lr 14

14 Actinoids



Quantum level

Only thorium and uranium occur naturally in the earth's crust in anything more than trace quantities. Neptunium and plutonium have been known to show up naturally in trace amounts in uranium ores as a result of decay or bombardment. The remaining actinoids were discovered in nuclear fallout, or were synthesized in particle colliders.

The latter half of the series possess exceedingly short half-lives.

Copyright ABRAHAM [2008] - All rights reserved



$$E = nhv$$

$$m = Ev^2/c^2$$

$${}^{R}_{K}\,{}^{P}\!\sum_{25}^{32}\underset{\text{Deuterium mass-energy per shell}}{\left[\overset{\text{Baryon rest masses}}{[72(n)^2]}+\overset{\text{lepton rest mass}}{[12e19]}+\overset{\text{KEM}}{[m_e v^2]}\right]_1^8}$$

Periodic summation formula

re-terming the masses of the periodic summation formula into Planck energy quanta we can derive a quadratic formulation for the mass-energies of any periodic element

Baryon energies determine electron KEMs

$$h\;{}^{R}_{K}\,{}^{P}\!\sum_{25}^{32}\underset{\text{Deuterium mass-energy per shell}}{\left[\overset{\text{Baryon rest mass-energy}}{[72(n^2)]}+\overset{\text{KEM}}{[v]}+\overset{\text{lepton rest mass-energy}}{[12e19]}\right]_1^8}$$

electron rest mass-Matter is velocity invariant

quadratic PΣ formulation

$$n = 1e19v$$

this quadratic form can be again re-organised to better reflect the specific rest mass-energy contributions of Baryons, electrons & their KEM fields to the molar mass-energy-Matter of any specific element

atomic shell energies

$${}^{R}_{K}\,{}^{P}\!\sum_{25}^{32}\underset{\text{nuclear mass-energy quanta per shell}}{\left[\overset{\text{Baryon rest quanta}}{[72(n^2)]}+\overset{\text{lepton rest quanta}}{[12e19]}+\overset{\text{KEM}}{[\Delta v]}\right]_1^8}$$

spectral line transitions

Elementary PΣ formulation

Tetryonics 52.13 - Periodic element summation formula



aufbau filling principle

The aufbau principle was developed by Neils Bohr and Wolfgang Pauli in 1920 as they applied quantum mechanics to the physical properies of chemistry

It attempted to model the properties of electrons in atoms to and led to the introduction of the n+l orbitals, and later to the development of Schrodiner's quantum numbers

"The orbitals of lower energy are filled in first with the electrons and only then the orbitals of higher energy are filled."
While succesful in describing lower numbered elements, many anomalous configurations arise from it in the d & f electron orbitals that need to be corrected

Tetryonic orbital filling

Tetryonic theory refines the aufbau principle by correcting it to follow the true quantum filling order of Deuterium nuclei in atoms

This then allows for all elementary nuclei, their atomic configurations & quantum properties to be modeled exactly

Nuclei
per level
R
Q
P
O
N
M
L
K
8s
7s 7p
6s 6p 6d
5s 5p 5d 5f
4s 4p 4d 4f
3s 3p 3d
2s 2p
1s
s1 s2 p1 p2 p3 p4 p5 p6 d1 d2 d3 d4 d5 d6 d7 d8 d9 d10 f1 f2 f3 f4 f5 f6 f7 f8 f9 f10 f11 f12 f13 f14
Azmithal & Magnetic numbers
0
1
2
3
s
p
d
f
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 52.14 - Tetryonic aufbau orbital filling

Copyright ABRAHAM [2008] - All rights reserved



Tetryonic element families

Elemental family groupings are a reflection of atomic sub-orbitals within elemental atoms

f 7
1-14 Actinoid
1-14 Lanthanoid
d 5
9-10 Post Transition Metal
1-8 Transition Metal
p 3
6 Noble Gas
5 Halogen
1-4 Non-Metal Metaloid Poor-Metal
s 1
2 Alkaline Earth
1 Alkali Metal
Orbitals
sub orbital
Family
f
Orbitals
d
p
s
0
1
2
l
Azmithal
3
7
m
orbitals
5
3
1
2
6
10
s
sub-orbitals
14
Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
Atomic Shells
8
7
6
5
4
3
2
1
Energy levels
Actinoids
Lanthanoids
Post-transition
Transition Metals
Halogens
Semi-metals
Alkali Metals
Alkaine Earths
Semi-metals
Nobel Gases
Transition Metals
Post-transition
Actinoids
Lanthanoids
f
d
p
s
p
d
f
Orbitals & sub-Orbitals

Tetryonics 52.15 - Tetryonic elemental families

Copyright ABRAHAM [2008] - All rights reserved



elemental family geometry

electron configuration

Hydrogen

Hydrogen is NOT a periodic table element

Free Radical element

Baryonic energy levels determine photo-electron KEM field energies

$$\sum_{K}^{P}{}_{25}\left[\,[72(n^{2})] + [12e19] + [\Delta v]\,\right]_{1}^{8}$$

Baryon rest quanta · lepton rest quanta · KEM

nuclear mass-energy quanta per shell

accelerating photo-electrons produce spectral lines

All electrons in elements have differing KEM field energies

H
3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
1/2
f d p s p d f
Absorption
Emission
Atomic Shells
Energy levels
1
3
5
7
9
11
13
15
12
36
60
84
108
132
156
180
13.525 eV
0.84 eV
0.54 eV
0.37 eV
0.27 eV
0.21 eV
p
d

Tetryonics 53.00 - Hydrogen atomic config


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
1
f d p s p d f
Deuterium
1s1
Alkali
Metal
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
01
1
s
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

$$_{K}{}^{p}\sum_{25}\left[\overset{\text{Baryon rest quanta}}{[72(\mathrm{m}^2)]}+\overset{\text{lepton rest quanta}}{[12e19]}+\overset{\text{KEM}}{[\Delta v]}\right]_{1}$$

nuclear mass-energy quanta per shell

Tetryonics 53.01 - Deuterium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
f d p s p d f
1
2He
Helium
Baryon rest quanta
lepton rest quanta
KEM
nuclear mass-energy quanta per shell
1s2
Alkaline
Earth
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
02
1 s 2
Atomic Shells
Orbitals & sub-Orbitals
Energy levels

$$_{K}\overset{P}{\sum}\,_{25}\Big[[72(m^2)] + [12e19] + [\Delta v]\Big]_1$$

Tetryonics 53.02 - Helium atomic config


elemental family geometry
3 2 1 0 1 2 3
electron configuration
R Q P O N M L K
8 7 6 5 4 3 2 1
1
2
f d p s p d f
Lithium
L
K
P
26
25
Baryon rest quanta
lepton rest quanta
KEM
[72(n²)] + [12e19] + [Δv]
2
1
nuclear mass-energy quanta per shell
[He] 2s1
Alkali
Metal
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
03
1
s
2
Atomic Shells
Orbitals & sub-Orbitals
Energy levels

Tetryonics 53.03 - Lithium atomic config


elemental family geometry
1
2
Be
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
2
f
d
p
s
p
d
f
electron configuration
Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
04
1
s
2
Atomic Shells
Orbitals & sub-Orbitals
Energy levels

Beryllium

$${}^{L}_{K}\sum_{P}{}^{26}_{25}\left[\overset{\text{Baryon rest quanta}}{[72(m^{2})]}+\overset{\text{lepton rest quanta}}{[12e19]}+\overset{\text{KEM}}{[\Delta v]}\right]^{2}_{1}$$

nuclear mass-energy quanta per shell

[He] 2s2

Alkaline Earth

Tetryonics 53.04 - Beryllium atomic config


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
3
2
f d p s p d f
Boron
Baryon rest quanta
lepton rest quanta
KEM
nuclear mass-energy quanta per shell
[He] 2s2 2p1
Metaloid
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
1
0
-1
05
1
p
1
s
2
Atomic Shells
Orbitals & sub-Orbitals
Energy levels

$$\sum_{K}^{L} {}_{P}\, {}_{25}^{26}\left[[72(n^2)] + [12e19] + [\Delta v] \right]_{1}^{2}$$

Tetryonics 53.05 - Boron atomic config

elemental family geometry




3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
4
2
f
d
p
s
p
d
f

electron configuration



Carbon

Baryon rest quanta · lepton rest quanta · KEM

$$\sum_{K}^{L} {}_{P}\!\sum_{25}^{26} \left[[72(m^2)] + [12e19] + [\Delta v] \right]_{1}^{2}$$

nuclear mass-energy quanta per shell

[He] 2s2 2p2

Metaloid

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
1
0
1
-1
-1
06
1
2
p
p
1
s
2

Atomic Shells

Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.06 - Carbon atomic config


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
5
2
f d p s p d f
Nitrogen
[He] 2s2 2p3
Metaloid
Baryon rest quanta
lepton rest quanta
KEM
L
K
P
26
25
[[72(m²)] + [12e19] + [Δv]]
2
1
nuclear mass-energy quanta per shell
Azmithal & Magnetic numbers
1 0 1
0 -1 -1
07
3 1 2
p s p
1 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.07 - Nitrogen atomic config

Copyright ABRAHAM [2008] - All rights reserved

elemental family geometry




3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
6
2
f
d
p
s
p
d
f

electron configuration



Oxygen

$$ {}_{K}^{L}\,{}_{P}\sum_{25}^{26}\underset{\text{nuclear mass-energy quanta per shell}}{\left[\overset{\text{Baryon rest quanta}}{[72(n^2)]} + \overset{\text{lepton rest quanta}}{[12e19]} + \overset{\text{KEM}}{[\Delta v]}\right]_{1}^{2}} $$

[He] 2s2 2p4

Metaloid

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
1
0
1
0
-1
-1
0
08
3
1
2
4
p
p
1
s
2

Atomic Shells

Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.08 - Oxygen atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
7
2
f d p s p d f
F
5 4 1 1 2 2 3
Azmithal & Magnetic numbers
1 0 1
+1 0 -1 -1 0
09
5 3 1 2 4
p s p
1 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Fluorine

$$\sideset{_{K}^{L}}{}{\overset{}{{}^{P}\sum}}{}_{25}^{26}\left[\underbrace{\overset{\text{Baryon rest quanta}}{\left[72(\mathrm{m}^2)\right]}+\overset{\text{lepton rest quanta}}{\left[12e19\right]}+\overset{\text{KEM}}{\left[\Delta v\right]}}_{\text{nuclear mass-energy quanta per shell}}\right]_1^2$$

[He] 2s2 2p5

Halogen

Tetryonics 53.09 - Fluorine atomic config

Copyright ABRAHAM [2008] - All rights reserved



elemental family geometry

electron configuration

Neon

[He] 2s2 2p6

Noble Gas

$$\sum_{K}^{L} {}_{P}\sum_{25}^{26} \left[\underbrace{\overset{\text{Baryon rest quanta}}{[72(n^2)]} + \overset{\text{lepton rest quanta}}{[12e19]} + \overset{\text{KEM}}{[\Delta v]}}_{\text{nuclear mass-energy quanta per shell}} \right]_1^2$$

Azmithal & Magnetic numbers

Atomic Shells

Energy levels

Orbitals & sub-Orbitals

3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
8
2
f
d
p
s
p
d
f
Ne
1
0
1
+1
0
-1
-1
0
+1
10
5
3
1
2
4
6
p
p
1
s
2

Tetryonics 53.10 - Neon atomic config

elemental family geometry




3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
1
8
2
f
d
p
s
p
d
f

electron configuration



Sodium

Baryon rest quanta — lepton rest quanta — KEM

$$\sum_{K}^{M} P \sum_{25}^{27} \left[[72(m^2)] + [12e19] + [\Delta v] \right]_{1}^{3}$$

nuclear mass-energy quanta per shell

[Ne] 3s1

Alkali Metal

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
+1
0
-1
1 1
-1
0
+1
5
3
1
2
4
6
p
p
1
s
2

Atomic Shells

Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.11 - Sodium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
8
2
f d p s p d f
Magnesium
[Ne] 3s2
Alkaline Earth
Baryon rest quanta
lepton rest quanta
KEM
nuclear mass-energy quanta per shell
Azmithal & Magnetic numbers
0
1
1
+1 0 -1
-1 0 +1
12
5 3 1
2 4 6
p
s
p
1 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

$$\sum_{K}^{M} {}_{p}\sum_{25}^{27}\left[\left[72\left(m^{2}\right)\right]+\left[12e19\right]+\left[\Delta v\right]\right]_{1}^{3}$$

Tetryonics 53.12 - Magnesium atomic config

Copyright ABRAHAM [2008] - All rights reserved



elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
3
8
2
f d p s p d f
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
1
1
-1
13
+1 0 -1 0 +1
5 3 1 2 4 6
p p
1 s 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Aluminium

Baryon rest quanta — lepton rest quanta — KEM

$$ {}^{M}_{K}\,{}_{P}\sum_{25}^{27}\Big[[72(\mathfrak{m}^2)] + [12e19] + [\Delta v]\Big]_{1}^{3} $$

nuclear mass-energy quanta per shell

[Ne] 3s2 3p1

Metaloid

Tetryonics 53.13 - Aluminium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Si
Silicon
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
4
8
2
f d p s p d f
M
K
P
27
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
3
1
nuclear mass-energy quanta per shell
electron configuration
[Ne] 3s2 3p2
Metaloid
Azmithal & Magnetic numbers
0
1
1
-1
-1
+1
0
0
+1
14
5 3 1 2 4 6
p
p
1 s 2
Atomic Shells
Orbitals & sub-Orbitals
Energy levels

Tetryonics 53.14 - Silicon atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
5
8
2
f d p s p d f
Phosphorus
M
K
P∑
27
25
Baryon rest quanta
lepton rest quanta
KEM
[[72(m²)] + [12e19] + [Δv]]
3
1
nuclear mass-energy quanta per shell
[Ne] 3s2 3p3
Metaloid
Azmithal & Magnetic numbers
1 0 1
0 -1 -1
+1 0 +1
15
5 3 1 2 4 6
p s p
1 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.15 - Phosphorus atomic config



elemental family geometry

electron configuration

Sulfur

Baryon rest quanta · lepton rest quanta · KEM

$$\sum_{K}^{M} P\sum_{25}^{27}\Big[[72(m^2)] + [12e19] + [\Delta v]\Big]_{1}^{3}$$

nuclear mass-energy quanta per shell

[Ne] 3s2 3p4

Metaloid

3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
6
8
2
f d p s p d f
Azmithal & Magnetic numbers
1 0 1
0 -1 -1 0
+1 +1
16
5 3 1 2 4 6
p s p
1 2
Atomic Shells
Orbitals & sub-Orbitals
Energy levels

Tetryonics 53.16 - Sulfur atomic config

elemental family geometry




3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
7
8
2
f d p s p d f

electron configuration



Chlorine

$$ {}_{K}^{M}\sum_{25}^{27} P \left[[72(n^2)] + [12e19] + [\Delta v] \right]_{1}^{3} $$

Baryon rest quanta lepton rest quanta KEM

nuclear mass-energy quanta per shell

[Ne] 3s2 3p5

Halogen

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
1 0 1
+1 0 -1 -1 0 +1
17
5 3 1 2 4 6
p s p
1 2

Atomic Shells

Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.17 - Chlorine atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
8
8
2
f d p s p d f
Ar
Argon
M
K
P
Σ
27
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
3
1
nuclear mass-energy quanta per shell
[Ne] 3s2 3p6
Noble
Gas
Azmithal & Magnetic numbers
1 0 1
+1 0 -1 -1 0 +1
18
5 3 1 2 4 6
p
s
p
1 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.18 - Argon atomic config


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
1
8
8
2
f d p s p d f
Potassium
N
K
P
28
25
Baryon rest quanta
lepton rest quanta
KEM
4
1
$\sum_{K}^{N} {}_{P}\sum_{25}^{28}\left[[72(n^2)] + [12e19] + [\Delta v]\right]_{1}^{4}$
nuclear mass-energy quanta per shell
[Ar] 4s1
Alkali
Metal
Azmithal & Magnetic numbers
0
1
1
19
+1 0 -1
-1 0 +1
5 3 1
2 4 6
p
p
1 s 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.19 - Potassium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
8
8
2
f d p s p d f
Calcium
N
K
28
25
Baryon rest quanta
lepton rest quanta
KEM
4
1
nuclear mass-energy quanta per shell
[Ar] 4s2
Alkaline
Earth
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
1
1
20
+1 0 -1 -1 0 +1
5 3 1 2 4 6
p
p
1 s 2
Atomic Shels
Energy levels
Orbitals & sub-Orbitals

$$\sum_{K}^{N} p \sum_{25}^{28} \left[\left[72(\mathrm{n}^2) \right] + \left[12e19 \right] + \left[\Delta v \right] \right]_1^4$$

Tetryonics 53.20 - Calcium atomic config

Copyright ABRAHAM [2008] - All rights reserved

elemental family geometry




3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
9
8
2
f
d
p
s
p
d
f

electron configuration



Scandium

Baryon rest quanta, lepton rest quanta, KEM

$$\sum_{K}^{N} {}_{P}\sum_{25}^{28}\left[[72(m^2)] + [12e19] + [\Delta v] \right]_{1}^{4}$$

nuclear mass-energy quanta per shell

[Ar] 3d1 4s2

Transition Metal

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
1
0
1
-2
+1
0
-1
-1
0
+1
21
1
d
5
3
1
2
4
6
p
p
1
s
2

Atomic Shells

Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.21 - Scandium atomic config

elemental family geometry




3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
10
8
2
f
d
p
s
p
d
f

electron configuration



Titanium

$$
{}^{N}_{K}\,{}_{p}\!\sum_{25}^{28}\left[\underset{\text{Baryon rest quanta}}{\left[72(\mathrm{n}^2)\right]}+\underset{\text{lepton rest quanta}}{\left[12e19\right]}+\underset{\text{KEM}}{\left[\Delta v\right]}\right]_{1}^{4}
$$

nuclear mass-energy quanta per shell

[Ar] 3d2 4s2

Transition Metal


Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
2
1
1
2
-2
+1
0
-1
-1
0
+1
-2
22
1
2
d
d
5
3
1
2
4
6
p
p
1
s
2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Copyright ABRAHAM [2008] - All rights reserved

elemental family geometry


1
3
Va
5
4
1
1
2
2
3
6
2


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
11
8
2
f
d
p
s
p
d
f

electron configuration



Vanadium

$$ {}^{N}_{K}\,{}_{P}\!\sum_{25}^{28}\underbrace{\left[\overset{\text{Baryon rest quanta}}{[72(n^{2})]} + \overset{\text{lepton rest quanta}}{[12e19]} + \overset{\text{KEM}}{[\Delta v]} \right]_{1}^{4}}_{\text{nuclear mass-energy quanta per shell}} $$

[Ar] 3d3 4s2

Transition Metal

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
1
0
1
2
-1
-2
+1
0
-1
-1
0
+1
-2
23
3
1
2
d
5
3
1
2
4
6
d
p
p
1
s
2
Atomic Shells
Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.23 - Vanadium atomic config

elemental family geometry




3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
12
8
2
f
d
p
s
p
d
f

electron configuration



Chromium

$$ {}_{K}^{N}\sum P \; {}_{25}^{28}\left[\overset{\text{Baryon rest quanta}}{[72(m^2)]} + \overset{\text{lepton rest quanta}}{[12e19]} + \overset{\text{KEM}}{[\Delta v]} \right]_{1}^{4} $$

nuclear mass-energy quanta per shell

[Ar] 3d4 4s2

Transition Metal

Azimthal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
1
0
1
2
-1
-2
+1
0
-1
-1
0
+1
-2
-1
24
3
1
2
4
5
3
1
2
4
6
d
d
p
p
s
1
2
Atomic Shells
Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.24 - Chromium atomic config


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
f d p s p d f
2
13
8
2
Mn
25
2 1 0 1 2
-1 -2 +1 0 -1 -1 0 +1 -2 -1
3 1 2 4
5 3 1 2 4 6
d p s p d
1 2

elemental family geometry

electron configuration

Manganese

$$ {}^{N}_{K}{}^{P}\sum^{28}_{25}\left[\left[72(\mathrm{m}^{2})\right]+\left[12e19\right]+\left[\Delta v\right]\right]^{4}_{1} $$

Baryon rest quanta

lepton rest quanta

KEM

nuclear mass-energy quanta per shell

[Ar] 3d5 4s2

Transition Metal

Azmithal & Magnetic numbers

Atomic Shells

Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.25 - Manganese atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Fe
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
14
8
2
f d p s p d f
electron configuration
Iron
N
K
P
28
25
Baryon rest quanta
lepton rest quanta
KEM
[72(n²)] + [12e19] + [Δv]
nuclear mass-energy quanta per shell
[Ar] 3d6 4s2
Transition Metal
Azmithal & Magnetic numbers
2 1 0 1 2
0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0
26
5 3 1 2 4 6
d
5 3 1 2 4 6
p
1 s 2
p
d
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.26 - Iron atomic config

Copyright ABRAHAM [2008] - All rights reserved

elemental family geometry


Co
1
3
7
5
5
4
1
2
1
2
6
3
6
4
2

Cobalt


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
15
8
2
f
d
p
s
p
d
f

$$\sum_{K}^{N} P\sum_{25}^{28}\left[\overset{\text{Baryon rest quanta}}{[72(m^2)]} + \overset{\text{lepton rest quanta}}{[12e19]} + \overset{\text{KEM}}{[\Delta v]}\right]_{1}^{4}$$

nuclear mass-energy quanta per shell

electron configuration



[Ar] 3d7 4s2

Transition Metal

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
1
0
1
2
+1
0
-1
-2
+1
0
-1
-1
0
+1
-2
-1
0
27
7
5
3
1
2
4
6
d
d
5
3
1
2
4
6
p
p
1
s
2
Atomic Shells
Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.27 - Cobalt atomic config

Copyright ABRAHAM [2008] - All rights reserved

elemental family geometry




3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
16
8
2
f
d
p
s
p
d
f

electron configuration



Nickel

$$\sum_{K\,25}^{N\,28}{}_{P}\left[\underbrace{\overset{\text{Baryon rest quanta}}{[72(\mathrm{m}^2)]}+\overset{\text{lepton rest quanta}}{[12e19]}+\overset{\text{KEM}}{[\Delta v]}}_{\text{nuclear mass-energy quanta per shell}}\right]_1^4$$

[Ar] 3d8 4s2

Transition Metal


Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
1
0
1
2
+1
0
-1
-2
+1
0
-1
-1
0
+1
-2
-1
0
+1
28
7
5
3
1
2
4
6
8
d
d
5
3
1
2
4
6
p
p
1
s
2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.28 - Nickel atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Cu
electron configuration
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
2
17
8
2
f d p s p d f
Azmithal & Magnetic numbers
2 1 0 1 2
+2 +1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0 +1
29
9 7 5 3 1 2 4 6 8
5 3 1 2 4 6
d
p
s
1 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Copper

$$\sum_{K}^{N} P \; {}_{25}^{28}\Big[[72(m^2)] + [12e19] + [\Delta v] \Big]_{1}^{4}$$

Baryon rest quanta · lepton rest quanta · KEM

nuclear mass-energy quanta per shell

[Ar] 3d9 4s2

Post Transition Metal

Tetryonics 53.29 - Copper atomic config


elemental family geometry
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
18
8
2
f d p s p d f
electron configuration
Zinc
N
K
28
25
Baryon rest quanta
lepton rest quanta
KEM
4
1
$\sum_{K}^{N} {}_{p}\left[[72(m^2)] + [12e19] + [\Delta v] \right]$
nuclear mass-energy quanta per shell
[Ar] 3d10 4s2
Post Transition Metal
Azmithal & Magnetic numbers
0
2 1 1 2
+2 +1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0 +1 +2
30
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.30 - Zinc atomic config


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
3
18
8
2
f d p s p d f
Gallium
N
K
P
28
25
Baryon rest quanta
lepton rest quanta
KEM
72(m²)
12e19
Δv
4
1
nuclear mass-energy quanta per shell
[Ar] 3d10 4s2 4p1
Metaloid
Azmithal & Magnetic numbers
2 1 0 1 2
+2 +1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0 +1 +2
31
9 7 5 3 1
5 3 1
1 2
2 4 6
2 4 6 8 10
d p s p d
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.31 - Gallium atomic config

Copyright ABRAHAM [2008] - All rights reserved

elemental family geometry


1
2
3
4
5
6
7
8
9
10
Ge


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
4
18
8
2
f
d
p
s
p
d
f

electron configuration



Germanium

$$ {}_{K}^{N}\,{}^{p}\!\sum_{25}^{28}\left[\left[72(\mathrm{n}^2)\right]+\left[12e19\right]+\left[\Delta v\right]\right]_1^4 $$

Baryon rest quanta

lepton rest quanta

KEM

nuclear mass-energy quanta per shell

[Ar] 3d10 4s2 4p2

Metaloid

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
2
1
1
2
-1
-1
32
+2
+1
0
-1
-2
+1
0
0
+1
-2
-1
0
+1
+2
9
7
5
3
1
2
4
6
8
10
d
d
5
3
1
2
4
6
p
p
1
s
2

Atomic Shells

Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.32 - Germanium atomic config

elemental family geometry


9
1
3
7
5
5
4
1
1
2
3
6
6
8
4
2
10


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
5
18
8
2
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f

electron configuration



Arsenic

$$ {}^{N}_{K}\,{}_{p}\sum_{25}^{28}\underset{\text{nuclear mass-energy quanta per shell}}{\left[\overset{\text{Baryon rest quanta}}{[72(n^2)]}+\overset{\text{lepton rest quanta}}{[12e19]}+\overset{\text{KEM}}{[\Delta v]}\right]_{1}^{4}} $$

[Ar] 3d10 4s2 4p3

Metaloid

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
1
0
0
-1
-1
2
1
2
+2
+1
0
-1
-2
+1
33
0
+1
-2
-1
0
+1
+2
9
7
5
3
1
2
4
6
8
10
d
d
5
3
1
2
4
6
p
p
1
s
2
Atomic Shells
Energy levels

Orbitals & sub-Orbitals


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
6
18
8
2
f d p s p d f
Azmithal & Magnetic numbers
1 0 1
0 -1 -1 0
2 2
+2 +1 0 -1 -2 +1 34 +1 -2 -1 0 +1 +2
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Selenium

$$\sum_{K}^{N} {}_{P}\left[\,[72(\mathrm{n}^2)]_{25}^{28} + [12e19] + [\Delta v]\,\right]_{1}^{4}$$

Baryon rest quanta — lepton rest quanta — KEM

nuclear mass-energy quanta per shell

[Ar] 3d10 4s2 4p4

Metaloid

Tetryonics 53.34 - Selenium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Br
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
7
18
8
2
f d p s p d f
electron configuration
Azmithal & Magnetic numbers
1 0 1
2 2
+1 0 -1 -1 0
+2 +1 0 -1 -2 +1 -2 -1 0 +1 +2
35
9 7 5 3 1 2 4 6 8 10
5 3 1 2 4 6
d p s p d
1 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Bromine

Baryon rest quanta · lepton rest quanta · KEM

$$\sum_{K}^{N} {}_{P}\sum_{25}^{28}\left[[72(m^{2})]+[12e19]+[\Delta v]\right]_{1}^{4}$$

nuclear mass-energy quanta per shell

[Ar] 3d10 4s2 4p5

Halogen

Tetryonics 53.35 - Bromine atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Kr
Krypton
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
8
18
8
2
f d p s p d f
electron configuration
[Ar] 3d10 4s2 4p6
Noble
Gas
N
K
P
28
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
4
1
nuclear mass-energy quanta per shell
Azmithal & Magnetic numbers
2 1 0 1 2
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
36
9 7 5 3 1
5 3 1
2 4 6
2 4 6 8 10
d p s p d
1 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.36 - Krypton atomic config

Copyright ABRAHAM [2008] - All rights reserved

elemental family geometry




3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
1
8
18
8
2
f
d
p
s
p
d
f

electron configuration



Rubidium

$$ {}^{O}_{K}\,{}_{P}\sum_{25}^{29}\underset{\text{nuclear mass-energy quanta per shell}}{\left[\overset{\text{Baryon rest quanta}}{[72(n^{2})]} + \overset{\text{lepton rest quanta}}{[12e19]} + \overset{\text{KEM}}{[\Delta v]}\right]_{1}^{5}} $$

[Kr] 5s1

Alkali Metal

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
2
2
37
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
9 7 5 3 1
5 3 1
1 2
2 4 6
2 4 6 8 10
d
p
s
p
d
Atomic Shells
Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.37 - Rubidium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
3 2 1 0 1 2 3
electron configuration
R Q P O N M L K
8 7 6 5 4 3 2 1
2
8
18
8
2
f d p s p d f
Strontium
O
K
P∑
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(n²)] + [12e19] + [Δv]
5
1
nuclear mass-energy quanta per shell
[Kr] 5s2
Alkaline Earth
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
38
1
1
2
2
+1 0 -1
-1 0 +1
+2 +1 0 -1 -2
-2 -1 0 +1 +2
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
d
d
p
p
1 s 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.38 - Strontium atomic config

elemental family geometry




3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
9
18
8
2
f
d
p
s
p
d
f

electron configuration



Yttrium

$$ {}^{O}_{K}\,{}_{P}\sum_{25}^{29}\left[\,[72(m^2)] + [12e19] + [\Delta v]\,\right]_{1}^{5} $$

Baryon rest quanta — lepton rest quanta — KEM

nuclear mass-energy quanta per shell

[Kr] 5s2 4d1

Transition Metal

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
2
2
-2
+1
0
-1
-1
0
+1
+2
+1
0
-1
-2
-1
0
+1
+2
39
9
7
5
3
1
2
4
6
8
10
d
d
5
3
1
2
4
6
p
p
1
s
2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.39 - Yttrium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
2
10
18
8
2
f d p s p d f
Zirconium
O
K
P
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
5
1
nuclear mass-energy quanta per shell
[Kr] 5s2 4d2
Transition Metal
Azmithal & Magnetic numbers
0
1
1
2
2
-2 +1 0 -1
-1 0 +1 -2
+2 +1 0 -1
-1 0 +1 +2
40
9 7 5 3 1
2 4 6 8 10
d
d
5 3 1
2 4 6
p
p
1 s 2
Atomic Shells
Orbitals & sub-Orbitals
Energy levels

Tetryonics 53.40 - Zirconium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Nb
electron configuration
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
f d p s p d f
2
11
18
8
2
Niobium
O
K
29
25
Baryon rest quanta
lepton rest quanta
KEM
nuclear mass-energy quanta per shell
$\sum_{K}^{O} P \left[\left[72(m^2) \right] + \left[12e19 \right] + \left[\Delta v \right] \right]_{1}^{5}$
[Kr] 5s2 4d3
Transition Metal
Azmithal & Magnetic numbers
Atomic Shells
41
0
1 1
2 2
+2 +1 0 -1 -2
-1 +1 0 -1
-1 0 +1 -2
-1 0 +1 +2
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
d p s p d
1 2
Orbitals & sub-Orbitals

Tetryonics 53.41 - Niobium atomic config


elemental family geometry
electron configuration
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3
2
1
0
1
2
3
2
12
18
8
2
f
d
p
s
p
d
f
Mo
Azmithal & Magnetic numbers
0
1
1
2
2
42
d
d
p
p
s
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Molybdenum

$${}^{O}_{K}\sum_{25}^{29} P\left[[72(\mathrm{m}^2)] + [12e19] + [\Delta v]\right]^{5}_{1}$$

Baryon rest quanta

lepton rest quanta

KEM

nuclear mass-energy quanta per shell

[Kr] 5s2 4d4

Transition Metal

Tetryonics 53.42 - Molybdenum atomic config

Copyright ABRAHAM [2008] - All rights reserved

elemental family geometry




3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
13
18
8
2
f
d
p
s
p
d
f

electron configuration



Technetium

$$\sideset{_{K}^{O}}{}{\,}{}_{P}\sum_{25}^{29}\left[[72(m^2)] + [12e19] + [\Delta v]\right]_1^5$$

Baryon rest quanta — lepton rest quanta — KEM

nuclear mass-energy quanta per shell

[Kr] 5s2 4d5

Transition Metal

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
2
2
0
-1
-2
+1
0
-1
-1
0
+1
-2
-1
+2
+1
0
+1
+2
43
9
7
5
3
1
5
3
1
2
4
6
2
4
6
8
10
d
p
s
1
2
p
d
Atomic Shells
Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.43 - Technetium atomic config


elemental family geometry
Ru
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
14
18
8
2
f d p s p d f
electron configuration
Ruthenium
O
K
p
29
25
Baryon rest quanta
lepton rest quanta
KEM
5
1
[72(n²)] + [12e19] + [Δv]
nuclear mass-energy quanta per shell
[Kr] 5s2 4d6
Transition Metal
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
2 1 1 2
0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0
+2 +1 +1 +2
44
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.44 - Ruthenium atomic config


elemental family geometry
Rh
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
15
18
8
2
f d p s p d f
electron configuration
Rhodium
Baryon rest quanta
lepton rest quanta
KEM
nuclear mass-energy quanta per shell
[Kr] 5s2 4d7
Transition Metal
Azmithal & Magnetic numbers
0
2 1 1 2
+1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0
+2 +1 +2
45
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
Atomic Shells
Orbitals & sub-Orbitals
Energy levels

$$\sum_{K}^{O} {}_{p}\left[\,[72(\mathfrak{n}^2)] + [12e19] + [\Delta v]\,\right]_{1}^{5}$$

Tetryonics 53.45 - Rhodium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Pd
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
16
18
8
2
f d p s p d f
electron configuration
Palladium
O
K
p
∑
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
5
1
nuclear mass-energy quanta per shell
[Kr] 5s2 4d8
Transition Metal
Azmithal & Magnetic numbers
2 1 0 1 2
+1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0 +1
+2
+2
46
9 7 5 3 1
5 3 1
2 4 6
2 4 6 8 10
d p s p d
1 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.46 - Palladium atomic config


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
17
18
8
2
f d p s p d f
Silver
O
K
P
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
5
1
nuclear mass-energy quanta per shell
[Kr] 5s2 4d9
Post Transition Metal
Azmithal & Magnetic numbers
0
1 1
2 2
+2 +1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0 +1 +2
47
9 7 5 3 1 5 3 1 1 2 2 4 6 2 4 6 8 10
d p s p d
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.47 - Silver atomic config


elemental family geometry
Cd
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
18
18
8
2
f d p s p d f
electron configuration
Azmithal & Magnetic numbers
2 1 0 1 2
+2 +1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0 +1 +2
48
9 7 5 3 1 5 3 1 1 2 2 4 6 2 4 6 8 10
d p s p d
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Cadmium

$$\sum_{K}^{O} P \left[\underset{\text{Baryon rest quanta}}{\left[72(\mathrm{n}^2)\right]} + \underset{\text{lepton rest quanta}}{\left[12e19\right]} + \underset{\text{KEM}}{\left[\Delta v\right]} \right]_{25\,1}^{29\,5}$$

nuclear mass-energy quanta per shell

[Kr] 5s2 4d10

Post Transition Metal

Tetryonics 53.48 - Cadmium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
3
18
18
8
2
f d p s p d f
Indium
O
K
P
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
5
1
nuclear mass-energy quanta per shell
[Kr] 5s2 4d10 5p1
Metaloid
Azmithal & Magnetic numbers
2 1 0 1 2
+2 +1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0 +1 +2
49
9 7 5 3 1 5 3 1 1 2 2 4 6 2 4 6 8 10
d p s p d
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.49 - Indium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Sn
Tin
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
4
18
18
8
2
f d p s p d f
electron configuration
[Kr] 5s2 4d10 5p2
Metaloid
O
K
P
29
25
Baryon rest quanta
lepton rest quanta
KEM
5
1
$\sum [72(m^2)] + [12e19] + [\Delta v]$
nuclear mass-energy quanta per shell
Azmithal & Magnetic numbers
0
-1 -1
1 1
2 2
50
+2 +1 0 -1 -2 +1 0 0 +1 -2 -1 0 +1 +2
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.50 - Tin atomic config


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
5
18
18
8
2
f d p s p d f
Sb
Antimony
O
P
K
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
5
1
nuclear mass-energy quanta per shell
[Kr] 5s2 4d10 5p3
Metaloid
Azmithal & Magnetic numbers
2 1 0 1 2
+2 +1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0 +1 +2
51
9 7 5 3 1 5 3 1 1 2 2 4 6 2 4 6 8 10
d p s p d
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.51 - Antimony atomic config



elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
6
18
18
8
2
f d p s p d f
Azmithal & Magnetic numbers
1 0 1
2 2
0 -1 -1 0
+2 +1 0 -1 -2 +1 +1 -2 -1 0 +1 +2
52
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tellurium

$$\sum_{K}^{O} P \sum_{25}^{29} \left[[72(n^2)] + [12e19] + [\Delta v] \right]_{1}^{5}$$

Baryon rest quanta · lepton rest quanta · KEM

nuclear mass-energy quanta per shell

[Kr] 5s2 4d10 5p4

Metaloid

Tetryonics 53.52 - Tellurium atomic config


elemental family geometry
electron configuration
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
7
18
18
8
2
f
d
p
s
p
d
f
Azmithal & Magnetic numbers
+2
+1
0
-1
-2
+1
0
-1
-1
0
+1
-2
-1
0
+1
+2
53
9
7
5
3
1
5
3
1
1
2
2
4
6
2
4
6
8
10
d
p
s
p
d
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Iodine

$$\sum_{K}^{O}{}_{P}\ {}^{29}_{25}\left[\,[72(n^2)] + [12e19] + [\Delta v]\,\right]^{5}_{1}$$

Baryon rest quanta · lepton rest quanta · KEM

nuclear mass-energy quanta per shell

[Kr] 5s2 4d10 5p5

Halogen

Tetryonics 53.53 - Iodine atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
f d p s p d f
8
18
18
8
2
Xe
Xenon
O
K
P
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
5
1
nuclear mass-energy quanta per shell
[Kr] 5s2 4d10 5p6
Noble Gas
Azmithal & Magnetic numbers
2
1
0
1
2
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
54
9 7 5 3 1
5 3 1
2 4 6
2 4 6 8 10
d
p
s
p
d
1 2
Atomic Shells
Orbitals & sub-Orbitals
Energy levels

Tetryonics 53.54 - Xenon atomic config


elemental family geometry
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
1
8
18
18
8
2
f d p s p d f
electron configuration
Caesium
P
K
29
25
Baryon rest quanta
lepton rest quanta
KEM
6
1
[72(n²)] + [12e19] + [Δv]
nuclear mass-energy quanta per shell
[Xe] 6s1
Alkali Metal
Azmithal & Magnetic numbers
0
1
1
2
2
55
+1 0 -1
-1 0 +1
+2 +1 0 -1 -2
-2 -1 0 +1 +2
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
d
p
s
p
d
1 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.55 - Caesium atomic config


elemental family geometry
electron configuration
Barium
[Xe] 6s2
Alkaline Earth
Baryon rest quanta
lepton rest quanta
KEM
nuclear mass-energy quanta per shell
$\sum_{K}^{P} {}_{25}^{29}[[72(m^2)] + [12e19] + [\Delta v]]_1^6$
R Q P O N M L K
8 7 6 5 4 3 2 1
2 8 18 18 8 2
f d p s p d f
Azmithal & Magnetic numbers
56
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.56 - Barium atomic config

elemental family geometry


La
1
9
1
3
7
5
5
6
4
1
1
2
2
3
6
6
8
4
2
10


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
8
19
18
8
2
f
d
p
s
p
d
f

electron configuration



Lanthanum

$${}_{K}^{P}\sum_{25}^{29}\left[[72(n^2)] + [12e19] + [\Delta v]\right]_{1}^{6}$$

Baryon rest quanta — lepton rest quanta — KEM

nuclear mass-energy quanta per shell

[Xe] 4f1 6s2

Lanthanoid

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
+1
0
-1
-1
0
+1
3
2
2
-3
+2
+1
0
-1
-2
-2
-1
0
+1
+2
57
1
f
9
7
5
3
1
d
2
4
6
8
10
d
5
3
1
p
2
4
6
p
1
s
2
Atomic Shells
Energy levels

Orbitals & sub-Orbitals

Copyright ABRAHAM [2008] - All rights reserved

elemental family geometry


1
9
7
3
7
5
5
6
4
1
1
2
2
3
6
6
8
4
10
2
2
Ce


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
8
20
18
8
2
f
d
p
s
p
d
f

electron configuration



Cerium

$$\sum_{K}^{P} {}_{P}\!\sum_{25}^{29}\left[\underset{\text{Baryon rest quanta}}{[72(\mathrm{n}^2)]} + \underset{\text{lepton rest quanta}}{[12e19]} + \underset{\text{KEM}}{[\Delta v]}\right]_{1}^{6}$$

nuclear mass-energy quanta per shell

[Xe] 4f2 6s2

Lanthanoid

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3
2
1
0
1
2
3
-3
+2
+1
0
-1
-2
+1
0
-1
-1
0
+1
-2
-1
0
+1
+2
-3
58
1
2
9
7
5
3
1
2
4
6
8
10
5
3
1
2
4
6
1
2
f
d
p
s
p
d
f
Atomic Shells
Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.58 - Cerium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
Praseodymium
P
K
29
25
Baryon rest quanta
lepton rest quanta
KEM
6
1
[72(m²)] + [12e19] + [Δv]
nuclear mass-energy quanta per shell
[Xe] 4f3 6s2
Lanthanoid
R Q P O N M L K
8 7 6 5 4 3 2 1
2
8
21
18
8
2
f d p s p d f
Azmithal & Magnetic numbers
59
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.59 - Praseodymium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Nd
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
2
8
22
18
8
2
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f
electron configuration
Azmithal & Magnetic numbers
0
1
1
2
2
3
3
+1
0
-1
-1
0
+1
-2
-3
+2
+1
0
-1
-2
-2
-1
0
+1
+2
-3
-2
60
3
1
2
4
9
7
5
3
1
2
4
6
8
10
5
3
1
2
4
6
1
2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Neodymium

Baryon rest quanta, lepton rest quanta, KEM

$$\sum_{K}^{P} {}_{p}\sum_{25}^{29}\Big[[72(n^{2})] + [12e19] + [\Delta v]\Big]_{1}^{6}$$

nuclear mass-energy quanta per shell

[Xe] 4f4 6s2

Lanthanoid

Tetryonics 53.60 - Neodymium atomic config

elemental family geometry




3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
8
23
18
8
2
f d p s p d f

electron configuration



Promethium

$$\sum_{K}^{P}{}_{p}\;{}^{29}_{25}\Big[[72(n^{2})]+[12e19]+[\Delta v]\Big]^{6}_{1}$$

Baryon rest quanta · lepton rest quanta · KEM

nuclear mass-energy quanta per shell

[Xe] 4f5 6s2

Lanthanoid

Azmithal & Magnetic numbers


R Q P O N M L K
8 7 6 5 4 3 2 1
0
1 1
+1 0 -1
-1 0 +1
2 2
3 3
-1 -2 -3 +2 +1 0 -1 -2
-2 -1 0 +1 +2 -3 -2
61
5 3 1
9 7 5 3 1
5 3 1
1 2
2 4 6
2 4 6 8 10
2 4
f d p s p d f
Atomic Shells
Energy levels

Orbitals & sub-Orbitals

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Sm
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
8
24
18
8
2
f d p s p d f
Samarium
P
K
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
6
1
nuclear mass-energy quanta per shell
[Xe] 4f6 6s2
Lanthanoid
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
+1 0 -1 -1 0 +1
-1 -2 -3 +2 +1 0 -1 -2 -2 -1 0 +1 +2 -3 -2 -1
62
5 3 1 2 4 6
9 7 5 3 1 2 4 6 8 10
5 3 1 2 4 6
1 2
f d p s p d f
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.62 - Samarium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Eu
electron configuration
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
2
8
25
18
8
2
f d p s p d f
Europium
[Xe] 4f7 6s2
Lanthanoid
Baryon rest quanta
lepton rest quanta
KEM
nuclear mass-energy quanta per shell
Azmithal & Magnetic numbers
63
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

$$\sum_{K}^{P} \sum_{25}^{29} \left[[72(\mathrm{m}^2)] + [12e19] + [\Delta v] \right]_{1}^{6}$$

Tetryonics 53.63 - Europium atomic config


elemental family geometry
electron configuration
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
f d p s p d f
2
8
26
18
8
2
Gadolinium
P
K
29
25
Baryon rest quanta
lepton rest quanta
KEM
6
1
$\sum_{K}^{P}\left[[72(m^2)] + [12e19] + [\Delta v]\right]$
nuclear mass-energy quanta per shell
[Xe] 4f8 6s2
Lanthanoid
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
64
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.64 - Gadolinium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Tb
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
8
27
18
8
2
f d p s p d f
electron configuration
Terbium
P
K
29
25
Baryon rest quanta
lepton rest quanta
KEM
6
1
[72(n²)] + [12e19] + [Δv]
nuclear mass-energy quanta per shell
[Xe] 4f9 6s2
Lanthanoid
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
1 1
2 2
3 3
+1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0
65
9 7 5 3 1
f
9 7 5 3 1
d
5 3 1
p
1 s 2
2 4 6
p
2 4 6 8 10
d
2 4 6 8
f
Atomic Shells
Orbitals & sub-Orbitals
Energy levels

Tetryonics 53.65 - Terbium atomic config

Copyright ABRAHAM [2008] - All rights reserved

elemental family geometry




3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
2
8
28
18
8
2
8
7
6
5
4
3
2
1
f d p s p d f

electron configuration



Dysprosium

$$\sum_{K}^{P} {}_{25}^{29}\left[[72(\mathrm{m}^2)] + [12e19] + [\Delta v] \right]_{1}^{6}$$

Baryon rest quanta · lepton rest quanta · KEM

nuclear mass-energy quanta per shell

[Xe] 4f10 6s2

Lanthanoid

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
+1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0 +1
66
9 7 5 3 1
f
9 7 5 3 1
d
5 3 1
p
1 s 2
2 4 6
p
2 4 6 8 10
d
2 4 6 8 10
f

Atomic Shells

Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.66 - Dysprosium atomic config

elemental family geometry


Ho
1
2
3
4
5
6
7
8
9
10
11


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
8
29
18
8
2
f
d
p
s
p
d
f

electron configuration



Holium

$$ {}_{K}^{P}\,{}^{P}\sum_{25}^{29}\left[[72(m^2)] + [12e19] + [\Delta v]\right]_{1}^{6} $$

Baryon rest quanta lepton rest quanta KEM

nuclear mass-energy quanta per shell

[Xe] 4f11 6s2

Lanthanoid

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
2
2
3
3
67
+1
0
-1
f
d
p
s
p
d
f

Atomic Shells

Orbitals & sub-Orbitals

Energy levels

Tetryonics 53.67 - Holium atomic config


elemental family geometry
Ho
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
2
8
29
18
8
2
f d p s p d f
electron configuration
Holmium
$\sum_{K}^{P} {}_{P}\sum_{25}^{29}\left[[72(m^2)] + [12e19] + [\Delta v]\right]_{1}^{6}$
Baryon rest quanta
lepton rest quanta
KEM
nuclear mass-energy quanta per shell
[Xe] 4f11 6s2
Lanthanoid
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
+1 0 -1
-1 0 +1
+2 +1 0 -1 -2
-2 -1 0 +1 +2
+2 +1 0 -1 -2 -3
-3 -2 -1 0 +1
67
11 9 7 5 3 1
2 4 6 8 10
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 2
f d p s p d f
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.67 - Holmium atomic config

Copyright ABRAHAM [2008] - All rights reserved



elemental family geometry

electron configuration

Erbium

$$\sum_{K}^{P} {}^{29}_{25}\left[72(m^2)\right] + \left[12e19\right] + \left[\Delta v\right]^{6}_{1}$$

Baryon rest quanta · lepton rest quanta · KEM

nuclear mass-energy quanta per shell

[Xe] 4f12 6s2

Lanthanoid

Azmithal & Magnetic numbers

Atomic Shells

Energy levels

Orbitals & sub-Orbitals

3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
8
30
18
8
2
f d p s p d f
0
1 1
2 2
3 3
+1 0 -1
-1 0 +1
+2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2
11 9 7 5 3 1
9 7 5 3 1
5 3 1
1 2
2 4 6
2 4 6 8 10
2 4 6 8 10 12
68

Tetryonics 53.68 - Erbium atomic config

elemental family geometry


Tm
13
1
3
9
11
7
5
1
2
3
4
5
6
12
10


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
8
31
18
8
2
f
d
p
s
p
d
f

electron configuration



Thullium

$$ {}_{K}^{P}\sum {}^{29}_{25}\Big[[72(\mathrm{m}^2)] + [12e19] + [\Delta v] \Big]^{6}_{1} $$

Baryon rest quanta; lepton rest quanta; KEM

nuclear mass-energy quanta per shell

[Xe] 4f13 6s2

Lanthanoid

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
2
2
3
3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2
69
13 11 9 7 5 3 1
9 7 5 3 1
5 3 1
1 2
2 4 6
2 4 6 8 10
2 4 6 8 10 12
f
d
p
s
p
d
f
Atomic Shells
Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.69 - Thulium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Yb
Ytterbium
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
8
32
18
8
2
f d p s p d f
electron configuration
[Xe] 4f14 6s2
Lanthanoid
P
K
29
25
Baryon rest quanta
lepton rest quanta
KEM
6
1
$_{P}\sum [[72(m^2)] + [12e19] + [\Delta v]]$
nuclear mass-energy quanta per shell
Azmithal & Magnetic numbers
0
1
2
3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
13 11 9 7 5 3 1
2 4 6 8 10 12 14
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 2
70
f d p s p d f
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.70 - Ytterbium atomic config


elemental family geometry
Lu
electron configuration
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
9
32
18
8
2
f
d
p
s
p
d
f
Lutetium
Baryon rest quanta
lepton rest quanta
KEM
nuclear mass-energy quanta per shell
[Xe] 4f14 5d1 6s2
Transition Metal
Azmithal & Magnetic numbers
Atomic Shells
Orbitals & sub-Orbitals
Energy levels

$$\overset{P}{\underset{K}{{}_{P}\sum}}{}^{29}_{25}\left[\left[72\left(n^{2}\right)\right]+\left[12e19\right]+\left[\Delta v\right]\right]^{6}_{1}$$

Tetryonics 53.71 - Lutetium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Hf
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
10
32
18
8
2
f d p s p d f
electron configuration
Azmithal & Magnetic numbers
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Hafnium

$$\sum_{K}^{P} {}_{25}^{29}\left[\underset{\text{Baryon rest quanta}}{[72(m^2)]} + \underset{\text{lepton rest quanta}}{[12e19]} + \underset{\text{KEM}}{[\Delta v]}\right]_{1}^{6}$$

nuclear mass-energy quanta per shell

[Xe] 4f14 5d2 6s2

Transition Metal

Tetryonics 53.72 - Hafnium atomic config


elemental family geometry
Ta
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
11
32
18
8
2
f d p s p d f
electron configuration
Tantalum
Baryon rest quanta
lepton rest quanta
KEM
P
K
29
25
6
1
$\sum_{K}^{P} \left[[72(n^2)] + [12e19] + [\Delta v] \right]$
nuclear mass-energy quanta per shell
[Xe] 4f14 5d3 6s2
Transition Metal
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
73
Atomic Shells
Energy levels
f d p s p d f
Orbitals & sub-Orbitals

Tetryonics 53.73 - Tantalum atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
2
12
32
18
8
2
f d p s p d f
Tungsten
P
K
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
6
1
nuclear mass-energy quanta per shell
[Xe] 4f14 5d4 6s2
Transition Metal
Azmithal & Magnetic numbers
74
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.74 - Tungsten atomic config



elemental family geometry
Rh
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
13
32
18
8
2
f d p s p d f
electron configuration
Azmithal & Magnetic numbers
Atomic Shells
Energy levels
Orbitals & sub-Orbitals
75

Rhenium

Baryon rest quanta — lepton rest quanta — KEM

$$\,^{P}_{K}\,{}_{P}\sum_{25}^{29}\left[\left[72(m^{2})\right]+\left[12e19\right]+\left[\Delta v\right]\right]_{1}^{6}$$

nuclear mass-energy quanta per shell

[Xe] 4f14 5d5 6s2

Transition Metal

Tetryonics 53.75 - Rhenium atomic config

elemental family geometry


13
1
3
9
11
7
1
9
3
5
7
5
5
4
6
1
1
2
2
6
3
6
8
12
6
10
4
2
8
10
4
2
14
1


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
14
32
18
8
2
f
d
p
s
p
d
f

electron configuration



Osmium

$$\sum_{K}^{P} {}^{29}_{25}\left[[72(m^2)] + [12e19] + [\Delta v] \right]^{6}_{1}$$

Baryon rest quanta — lepton rest quanta — KEM

nuclear mass-energy quanta per shell

[Xe] 4f14 5d6 6s2

Transition Metal

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
2
2
3
3
+3
+2
+1
0
-1
-2
-3
+2
+1
0
-1
-2
+1
0
-1
-1
0
+1
-2
-1
0
+1
+2
-3
-2
-1
0
+1
+2
+3
76
13
11
9
7
5
3
1
2
4
6
8
10
12
14
f
f
9
7
5
3
1
2
4
6
8
10
d
d
5
3
1
2
4
6
p
p
1
s
2

Atomic Shells

Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.76 - Osmium atomic config

elemental family geometry


13
1
3
9
9
11
1
3
7
5
7
5
1
4
1
2
1
2
6
3
6
8
6
12
8
10
4
2
10
4
2
14


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
15
32
18
8
2
f
d
p
s
p
d
f

electron configuration



Iridium

$$ {}^{P}_{K}\sum{}^{29}_{25}\,P\,\left[\,[72(m^2)] + [12e19] + [\Delta v]\,\right]^{6}_{1} $$

Baryon rest quanta · lepton rest quanta · KEM

nuclear mass-energy quanta per shell

[Xe] 4f14 5d7 6s2

Transition Metal

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
2
2
3
3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
77
13 11 9 7 5 3 1
2 4 6 8 10 12 14
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 2
f
f
d
d
p
p
s

Atomic Shells

Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.77 - Iridium atomic config

elemental family geometry




3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
16
32
18
8
2
f
d
p
s
p
d
f

electron configuration



Platinum

Baryon rest quanta

lepton rest quanta

KEM

$$\overset{P}{\underset{K}{}}\ {}^{P}\sum_{25}^{29}\left[72(m^2)\right]+\left[12e19\right]+\left[\Delta v\right]_{1}^{6}$$

nuclear mass-energy quanta per shell

[Xe] 4f14 5d8 6s2

Transition Metal

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
2
2
3
3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
78
13 11 9 7 5 3 1
9 7 5 3 1
5 3 1
1 2
2 4 6
2 4 6 8 10
2 4 6 8 10 12 14
f
d
p
s
p
d
f

Atomic Shells

Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.78 - Platinum atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Au
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
17
32
18
8
2
f d p s p d f
electron configuration
Gold
P
K
$\sum_{K}^{P} {}_{25}^{29}\left[[72(n^2)] + [12e19] + [\Delta v] \right]_{1}^{6}$
Baryon rest quanta
lepton rest quanta
KEM
nuclear mass-energy quanta per shell
[Xe] 4f14 5d9 6s2
Post Transition Metal
Azmithal & Magnetic numbers
79
+3 +2 +1 0 -1 -2 -3
13 11 9 7 5 3 1
+2 +1 0 -1 -2
9 7 5 3 1
+1 0 -1
5 3 1
0
1 s 2
-1 0 +1
2 4 6
-2 -1 0 +1 +2
2 4 6 8 10
-3 -2 -1 0 +1 +2 +3
2 4 6 8 10 12 14
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.79 - Gold atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Hg
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
2
18
32
18
8
2
f d p s p d f
electron configuration
Mercury
$\sum_{K}^{P} {}_{25}^{29}\left[[72(m^2)] + [12e19] + [\Delta v] \right]_{1}^{6}$
Baryon rest quanta
lepton rest quanta
KEM
nuclear mass-energy quanta per shell
[Xe] 4f14 5d10 6s2
Post Transition Metal
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
80
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.80 - Mercury atomic config


elemental family geometry
Tl
3 2 1 0 1 2 3
R Q P O N M L K
3 18 32 18 8 2
8 7 6 5 4 3 2 1
f d p s p d f
electron configuration
Thallium
P
K
29
25
Baryon rest quanta
lepton rest quanta
KEM
6
1
$\sum_{K}^{P} {}^{p}\sum \left[[72(n^2)] + [12e19] + [\Delta v] \right]$
nuclear mass-energy quanta per shell
[Xe] 4f14 5d10 6s2 6p1
Metaloid
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0
-1
81
-1 0
+1 -2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
13 11 9 7 5 3 1
9 7 5 3 1
5 3 1
1 2
2 4 6
2 4 6 8 10
2 4 6 8 10 12 14
f d p s p d f
Atomic Shells
Orbitals & sub-Orbitals
Energy levels

Tetryonics 53.81 - Thallium atomic config


elemental family geometry
Pb
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
4
18
32
18
8
2
f d p s p d f
electron configuration
Lead
P
K
29
25
Baryon rest quanta
lepton rest quanta
KEM
6
1
$\sum_{K}^{P} {}_{P}\left[[72(n^2)] + [12e19] + [\Delta v] \right]$
nuclear mass-energy quanta per shell
[Xe] 4f14 5d10 6s2 6p2
Metaloid
Azmithal & Magnetic numbers
0
-1 -1
82
1 1
2 2
3 3
+2 +1 0 -1 -2 +1 0 0 +1 -2 -1 0 +1 +2
+3 +2 +1 0 -1 -2 -3
-3 -2 -1 0 +1 +2 +3
13 11 9 7 5 3 1
2 4 6 8 10 12 14
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 2
f d p s p d f
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.82 - Lead atomic config


elemental family geometry
electron configuration
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
5
18
32
18
8
2
f d p s p d f
Bismuth
P
K
29
25
Baryon rest quanta
lepton rest quanta
KEM
6
1
$$\sum_{K}^{P} {}_{25}^{29}\left[\,[72(n^2)] + [12e19] + [\Delta v]\,\right]_1^6$$
nuclear mass-energy quanta per shell
[Xe] 4f14 5d10 6s2 6p3
Metaloid
Azmithal & Magnetic numbers
83
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.83 - Bismuth atomic config


elemental family geometry
Po
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
6
18
32
18
8
2
f d p s p d f
electron configuration
Polonium
P
K
29
25
Baryon rest quanta
lepton rest quanta
KEM
6
1
nuclear mass-energy quanta per shell
[Xe] 4f14 5d10 6s2 6p4
Metaloid
Azmithal & Magnetic numbers
1 0 1
2 2
3 3
84
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

$$\sum_{K}^{P} {}_{P}\left[\left[72(\mathrm{m}^2)\right] + \left[12e19\right] + \left[\Delta v\right]\right]_{1}^{6}$$

Tetryonics 53.84 - Polonium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
At
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
7
18
32
18
8
2
f d p s p d f
electron configuration
Azmithal & Magnetic numbers
1 0 1
2 2
3 3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
85
13 11 9 7 5 3 1
9 7 5 3 1
5 3 1
1 s 2
2 4 6
2 4 6 8 10
2 4 6 8 10 12 14
f d p p d f
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Astatine

$$\overset{P}{\underset{K}{\,}}{}_{P}\sum_{25}^{29}\left[\overset{\text{Baryon rest quanta}}{[72(\mathfrak{m}^2)]}+\overset{\text{lepton rest quanta}}{[12e19]}+\overset{\text{KEM}}{[\Delta v]}\right]_1^6$$

nuclear mass-energy quanta per shell

[Xe] 4f14 5d10 6s2 6p5

Halogen

Tetryonics 53.85 - Astatine atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Rn
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
8
18
32
18
8
2
f d p s p d f
electron configuration
Radon
P
K
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
6
1
nuclear mass-energy quanta per shell
[Xe] 4f14 5d10 6s2 6p6
Noble Gas
Azmithal & Magnetic numbers
3 2 1 0 1 2 3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
86
13 11 9 7 5 3 1
9 7 5 3 1
5 3 1
1 2
2 4 6
2 4 6 8 10
2 4 6 8 10 12 14
f d p s p d f
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.86 - Radon atomic config


elemental family geometry
Fr
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
1
8
18
32
18
8
2
f d p s p d f
Francium
Baryon rest quanta
lepton rest quanta
KEM
Q
K
P
29
25
[72(m²)] + [12e19] + [Δv]
7
1
nuclear mass-energy quanta per shell
[Rn] 7s1
Alkali Metal
Azmithal & Magnetic numbers
0
87
1 1
2 2
3 3
Atomic Shells
Energy levels
Orbitals & sub-Orbitals
s
p p
d d
f f

Tetryonics 53.87 - Francium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
8
18
32
18
8
2
f d p s p d f
Radium
Q
K
P
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
7
1
nuclear mass-energy quanta per shell
[Rn] 7s2
Alkaine Earth
Azmithal & Magnetic numbers
0
88
1
2
3
+3 +2 +1 0 -1 -2 -3
13 11 9 7 5 3 1
+2 +1 0 -1 -2
9 7 5 3 1
+1 0 -1
5 3 1
1 2
-1 0 +1
2 4 6
-2 -1 0 +1 +2
2 4 6 8 10
-3 -2 -1 0 +1 +2 +3
2 4 6 8 10 12 14
f d p s p d f
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.88 - Radium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
3 2 1 0 1 2 3
R Q P O N M L K
2
8
19
32
18
8
2
8 7 6 5 4 3 2 1
f d p s p d f
electron configuration
Actinium
Q
K
$\sum P$
29
25
Baryon rest quanta
lepton rest quanta
KEM
$[72(m^2)] + [12e19] + [\Delta v]$
7
1
nuclear mass-energy quanta per shell
[Rn] 5f1 7s2
Actinoid
Azmithal & Magnetic numbers
0
1 1
+1 0 -1 -1 0 +1
2 2
-3 +2 +1 0 -1 -2 -2 -1 0 +1 +2
3 3
+3 +2 +1 0 -1 -2 -3 -2 -1 0 +1 +2 +3
89
13 11 9 7 5 3 1
f
9 7 5 3 1
d
5 3 1
p
1 s 2
2 4 6
p
2 4 6 8 10
d
2 4 6 8 10 12 14
f
Atomic Shells
Orbitals & sub-Orbitals
Energy levels

Tetryonics 53.89 - Actinium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
8
20
32
18
8
2
f d p s p d f
Thorium
Q
K
P
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
7
1
nuclear mass-energy quanta per shell
[Rn] 5f2 7s2
Actinoid
Azmithal & Magnetic numbers
0
1
2
3
90
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.90 - Thorium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
2
8
21
32
18
8
2
f d p s p d f
Protactinium
Q
K
P
29
25
Baryon rest quanta
lepton rest quanta
KEM
7
1
[72(m²)] + [12e19] + [Δv]
nuclear mass-energy quanta per shell
[Rn] 5f3 7s2
Actinoid
Azmithal & Magnetic numbers
0
1
1
2
2
3
3
91
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.91 - Protactinium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
8
22
32
18
8
2
f d p s p d f
Azmithal & Magnetic numbers
Atomic Shells
Energy levels
Orbitals & sub-Orbitals
92

Uranium

$$\sum_{K}^{Q} P \;{}^{29}_{25}\left[[72(m^2)] + [12e19] + [\Delta v] \right]^{7}_{1}$$

Baryon rest quanta — lepton rest quanta — KEM

nuclear mass-energy quanta per shell

[Rn] 5f4 7s2

Actinoid

Tetryonics 53.92 - Uranium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
2
8
23
32
18
8
2
f d p s p d f
Neptunium
Q K P Σ 29 25 [72(m²)] + [12e19] + [Δv] 7 1
Baryon rest quanta
lepton rest quanta
KEM
nuclear mass-energy quanta per shell
[Rn] 5f5 7s2
Actinoid
Azmithal & Magnetic numbers
93
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.93 - Neptunium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
3 2 1 0 1 2 3
R Q P O N M L K
2
8
24
32
18
8
2
8 7 6 5 4 3 2 1
f d p s p d f
electron configuration
Plutonium
Q
K
Baryon rest quanta
lepton rest quanta
KEM
$\sum_{K}^{Q} p \sum_{25}^{29} \left[[72(n^2)] + [12e19] + [\Delta v] \right]_{1}^{7}$
nuclear mass-energy quanta per shell
[Rn] 5f6 7s2
Actinoid
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
94
13 11 9 7 5 3 1
9 7 5 3 1
5 3 1
1 s 2
2 4 6
2 4 6 8 10
2 4 6 8 10 12 14
f d p s p d f
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.94 - Plutonium atomic config


elemental family geometry
electron configuration
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
f d p s p d f
2
8
25
32
18
8
2
Azmithal & Magnetic numbers
Atomic Shells
Energy levels
Orbitals & sub-Orbitals
95
Baryon rest quanta
lepton rest quanta
KEM
nuclear mass-energy quanta per shell

Americium

$$\sum_{K}^{Q} {}^{P}\sum_{25}^{29}\Big[[72(m^2)] + [12e19] + [\Delta v] \Big]_{1}^{7}$$

[Rn] 5f7 7s2

Actinoid

Tetryonics 53.95 - Americium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Cm
R Q P O N M L K
3 2 1 0 1 2 3
8 7 6 5 4 3 2 1
2
8
26
32
18
8
2
f d p s p d f
electron configuration
Curium
Q
P
K
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
7
1
nuclear mass-energy quanta per shell
[Rn] 5f8 7s2
Actinoid
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
96
f d p s p d f
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.96 - Curium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
2
8
27
32
18
8
2
f d p s p d f
Berkelium
Q
P
K
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
7
1
nuclear mass-energy quanta per shell
[Rn] 5f9 7s2
Actinoid
Azmithal & Magnetic numbers
0
1
1
2
2
3
3
97
f
d
p
s
p
d
f
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.97 - Berkelium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
2 8 28 32 18 8 2
f d p s p d f
Californium
Q
K
$\sum_{K}^{Q} P \sum_{25}^{29} \left[[72(n^2)] + [12e19] + [\Delta v] \right]_{1}^{7}$
Baryon rest quanta
lepton rest quanta
KEM
nuclear mass-energy quanta per shell
[Rn] 5f10 7s2
Actinoid
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
98
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.98 - Californium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
2
8
29
32
18
8
2
f d p s p d f
Einsteinium
Baryon rest quanta
lepton rest quanta
KEM
nuclear mass-energy quanta per shell
[Rn] 5f11 7s2
Actinoid
Azmithal & Magnetic numbers
99
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

$$\sum_{K}^{Q} P \; {}_{25}^{29}\Big[[72(m^2)] + [12e19] + [\Delta v]\Big]_{1}^{7}$$

Tetryonics 53.99 - Einsteinium atomic config


elemental family geometry
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
8
30
32
18
8
2
f d p s p d f
electron configuration
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
+1 0 -1 -1 0 +1
+2 +1 0 -1 -2 -2 -1 0 +1 +2
+3 +2 +1 0 -1 -2 -3 -3 -2 -1 0 +1 +2 +3
100
13 11 9 7 5 3 1 2 4 6 8 10 12 14
9 7 5 3 1 2 4 6 8 10
5 3 1 2 4 6
f d p s p d f
1 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Fermium

$$\sum_{K}^{Q} P \; {}_{25}^{29}\left[[72(n^2)] + [12e19] + [\Delta v] \right]_{1}^{7}$$

Baryon rest quanta · lepton rest quanta · KEM

nuclear mass-energy quanta per shell

[Rn] 5f12 7s2

Actinoid

Tetryonics 53.100 - Fermium atomic config


elemental family geometry
Md
electron configuration
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
2
8
31
32
18
8
2
f d p s p d f
Mendelevium
Baryon rest quanta
lepton rest quanta
KEM
nuclear mass-energy quanta per shell
[Rn] 5f13 7s2
Actinoid
Azmithal & Magnetic numbers
Atomic Shells
Energy levels
Orbitals & sub-Orbitals
101
+3 +2 +1 0 -1 -2 -3
13 11 9 7 5 3 1
f
+2 +1 0 -1 -2
9 7 5 3 1
d
+1 0 -1
5 3 1
p
0
1 s 2
-1 0 +1
2 4 6
p
-2 -1 0 +1 +2
2 4 6 8 10
d
-3 -2 -1 0 +1 +2 +3
2 4 6 8 10 12 14
f

$$\sum_{K}^{Q} {}_{P} \; {}_{25}^{29}\left[[72(m^2)] + [12e19] + [\Delta v] \right]_{1}^{7}$$

Tetryonics 53.101 - Mendelevium atomic config


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
8
32
32
18
8
2
f d p s p d f
No
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
102
13 11 9 7 5 3 1
9 7 5 3 1
5 3 1
1 s 2
2 4 6
2 4 6 8 10
2 4 6 8 10 12 14
f d p s p d f
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Nobelium

$$\sum_{K}^{Q} P \; {}_{25}^{29}\left[\overset{\text{Baryon rest quanta}}{[72(m^2)]} + \overset{\text{lepton rest quanta}}{[12e19]} + \overset{\text{KEM}}{[\Delta v]} \right]_{1}^{7}$$

nuclear mass-energy quanta per shell

[Rn] 5f14 7s2

Actinoid

Tetryonics 53.102 - Nobelium atomic config


elemental family geometry
electron configuration
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
9
32
32
18
8
2
f
d
p
s
p
d
f
Azmithal & Magnetic numbers
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Lawrencium

$$\sum_{K}^{Q} {}_{P}^{\,29}_{\,25}\left[[72(n^2)] + [12e19] + [\Delta v] \right]_1^7$$

Baryon rest quanta · lepton rest quanta · KEM

nuclear mass-energy quanta per shell

[Rn] 5f14 6d1 7s2

Transition Metal

Tetryonics 53.103 - Lawrencium atomic config

Copyright ABRAHAM [2008] - All rights reserved

elemental family geometry




3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
10
32
32
18
8
2
f
d
p
s
p
d
f

electron configuration



Rutherfordium

$$\sum_{K}^{Q} {}_{P} \overset{29}{\underset{25}{}} \left[\overset{\text{Baryon rest quanta}}{[72(\mathrm{m}^2)]} + \overset{\text{lepton rest quanta}}{[12e19]} + \overset{\text{KEM}}{[\Delta v]} \right]_{1}^{7}$$

nuclear mass-energy quanta per shell

[Rn] 5f14 6d2 7s2

Transition Metal

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
2
2
3
3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1
-2 +1 0 -1
-1 0 +1
104
-1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
13 11 9 7 5 3 1
9 7 5 3 1
5 3 1
1 s 2
2 4 6
2 4 6 8 10
2 4 6 8 10 12 14
f
d
p
s
p
d
f
Atomic Shells
Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.104 - Rutherfordium atomic config


elemental family geometry
Db
electron configuration
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
2
11
32
32
18
8
2
f d p s p d f
Azmithal & Magnetic numbers
0
1
1
2
2
3
3
105
13 11 9 7 5 3 1
9 7 5 3 1
5 3 1
1 2
2 4 6
2 4 6 8 10
2 4 6 8 10 12 14
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Dubnium

Baryon rest quanta — lepton rest quanta — KEM

$$\sum_{K}^{Q} P \; {}^{29}_{25}\left[[72(\mathrm{m}^2)] + [12e19] + [\Delta v]\right]_{1}^{7}$$

nuclear mass-energy quanta per shell

[Rn] 5f14 6d3 7s2

Transition Metal

Tetryonics 53.105 - Dubnium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Sg
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2 12 32 32 18 8 2
f d p s p d f
electron configuration
Seaborgium
Q P K 29 25 Baryon rest quanta lepton rest quanta KEM 7 1
[72(m²)] + [12e19] + [Δv]
nuclear mass-energy quanta per shell
[Rn] 5f14 6d4 7s2
Transition Metal
Azmithal & Magnetic numbers
0 1 1 2 2 3 3
+3 +2 +1 0 -1 -2 -3
106
13 11 9 7 5 3 1
2 4 6 8 10 12 14
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 s 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.106 - Seaborgium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
13
32
32
18
8
2
f d p s p d f
Bohrium
Q
K
P
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(n²)] + [12e19] + [Δv]
7
1
nuclear mass-energy quanta per shell
[Rn] 5f14 6d5 7s2
Transition Metal
Azmithal & Magnetic numbers
0
1
2
3
107
Atomic Shells
Energy levels
f d p s p d f
Orbitals & sub-Orbitals

Tetryonics 53.107 - Bohrium atomic config


elemental family geometry
electron configuration
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
2
14
32
32
18
8
2
f d p s p d f
Hassium
Q
K
P
29
25
Baryon rest quanta
lepton rest quanta
KEM
$\sum_{K}^{Q} P \left[[72(\mathfrak{m}^2)] + [12e19] + [\Delta v] \right]$
7
1
nuclear mass-energy quanta per shell
[Rn] 5f14 6d6 7s2
Transition Metal
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
108
13 11 9 7 5 3 1
9 7 5 3 1
5 3 1
1 2
2 4 6
2 4 6 8 10
2 4 6 8 10 12 14
f d p s p d f
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.108 - Hassium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Mt
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
2
15
32
32
18
8
2
f d p s p d f
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
109
13 11 9 7 5 3 1
9 7 5 3 1
5 3 1
1 2
2 4 6
2 4 6 8 10
2 4 6 8 10 12 14
f d p s p d f
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Meitnerium

$$\overset{Q}{\underset{K}{}}{}_{P}\sum_{25}^{29}\left[\overset{\text{Baryon rest quanta}}{[72(n^2)]}+\overset{\text{lepton rest quanta}}{[12e19]}+\overset{\text{KEM}}{[\Delta v]}\right]_1^7$$

nuclear mass-energy quanta per shell

[Rn] 5f14 6d7 7s2

Transition Metal

Tetryonics 53.109 - Meitnerium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
2
16
32
32
18
8
2
f d p s p d f
Azmithal & Magnetic numbers
Atomic Shells
Energy levels
Orbitals & sub-Orbitals
110
Ds

Darmstadtium

$$\sum_{K}^{Q} {}_{P} \left[\overset{\text{Baryon rest quanta}}{[72(\mathrm{m}^2)]} + \overset{\text{lepton rest quanta}}{[12e19]} + \overset{\text{KEM}}{[\Delta v]} \right]_{1}^{7}$$

29 25

nuclear mass-energy quanta per shell

[Rn] 5f14 6d8 7s2

Transition Metal

Tetryonics 53.110 - Darmstadtium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Rg
3 2 1 0 1 2 3
R Q P O N M L K
2
17
32
32
18
8
2
8 7 6 5 4 3 2 1
f d p s p d f
electron configuration
Roetgenium
Q
K
P
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(n²)] + [12e19] + [Δv]
7
1
nuclear mass-energy quanta per shell
[Rn] 5f14 6d9 7s2
Post Transition Metal
Azmithal & Magnetic numbers
0
1
2
3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
111
13 11 9 7 5 3 1
9 7 5 3 1
5 3 1
1 2
2 4 6
2 4 6 8 10
2 4 6 8 10 12 14
f
d
p
s
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.111 - Roetgenium atomic config

elemental family geometry




3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
2
18
32
32
18
8
2
8
7
6
5
4
3
2
1
f d p s p d f

electron configuration



Copernicium

$$\sum_{K}^{Q} {}_{P}\!\sum_{25}^{29}\left[72(\mathrm{m}^2)\right]+\left[12e19\right]+\left[\Delta v\right]_{1}^{7}$$

Baryon rest quanta · lepton rest quanta · KEM

nuclear mass-energy quanta per shell

[Rn] 5f14 6d10 7s2

Post Transition Metal

Azmithal & Magnetic numbers


0
2 1 1 2
+2 +1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0 +1 +2
3 3
+3 +2 +1 0 -1 -2 -3 -3 -2 -1 0 +1 +2 +3
112
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
13 11 9 7 5 3 1 2 4 6 8 10 12 14
f f
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
Atomic Shells
Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.112 - Copernicium atomic config


elemental family geometry
Uut
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
3
18
32
32
18
8
2
f d p s p d f
electron configuration
Ununtrium
Q
P
K
Σ
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
7
1
nuclear mass-energy quanta per shell
[Rn] 5f14 6d10 7s2 7p1
Metaloid
Azmithal & Magnetic numbers
0
-1
113
3 2 1 1 2 3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
13 11 9 7 5 3 1
9 7 5 3 1
5 3 1
1 2
2 4 6
2 4 6 8 10
2 4 6 8 10 12 14
f d p s p d f
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.113 - Ununtrium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Fl
3 2 1 0 1 2 3
R Q P O N M L K
4
18
32
32
18
8
2
8 7 6 5 4 3 2 1
f d p s p d f
electron configuration
Flerovium
Q
P
K
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(m²)] + [12e19] + [Δv]
7
1
nuclear mass-energy quanta per shell
[Rn] 5f14 6d10 7s2 7p2
Metaloid
Azmithal & Magnetic numbers
0
1
2
3
114
Atomic Shells
Energy levels
f
d
p
s
Orbitals & sub-Orbitals

Tetryonics 53.114 - Flerovium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
electron configuration
Uup
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
5
18
32
32
18
8
2
3 2 1 0 1 2 3
f d p s p d f
Ununpentium
Q
K
P
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(n²)] + [12e19] + [Δv]
7
1
nuclear mass-energy quanta per shell
[Rn] 5f14 6d10 7s2 7p3
Metaloid
Azmithal & Magnetic numbers
115
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.115 - Ununpentium atomic config


elemental family geometry
electron configuration
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
6
18
32
32
18
8
2
3
2
1
0
1
2
3
f
d
p
s
p
d
f
Livermorium
Q
K
P
29
25
Baryon rest quanta
lepton rest quanta
ΔEM
7
1
[72(n²)] + [12e19] + [Δv]
nuclear mass-energy quanta per shell
[Rn] 5f14 6d10 7s2 7p4
Metaloid
Azmithal & Magnetic numbers
Atomic Shells
Energy levels
Orbitals & sub-Orbitals
116

Tetryonics 53.116 - Livermorium atomic config

Copyright ABRAHAM [2008] - All rights reserved


elemental family geometry
Uus
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
7
18
32
32
18
8
2
f d p s p d f
electron configuration
Azmithal & Magnetic numbers
1 0 1
2 2
3 3
+1 0 -1 -1 0
+2 +1 0 -1 -2 +1 -2 -1 0 +1 +2
+3 +2 +1 0 -1 -2 -3 -3 -2 -1 0 +1 +2 +3
13 11 9 7 5 3 1
9 7 5 3 1
5 3 1
1 s 2
2 4 6
2 4 6 8 10
2 4 6 8 10 12 14
f d p p d f
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Unbinilium

$$\overset{Q}{\underset{K}{}}\;{}_{P}\sum_{25}^{29}\left[\overset{\text{Baryon rest quanta}}{[72(m^2)]} + \overset{\text{lepton rest quanta}}{[12e19]} + \overset{\text{KEM}}{[\Delta v]}\right]_{1}^{7}$$

nuclear mass-energy quanta per shell

[Rn] 5f14 6d10 7s2 7p5

Halogen

Tetryonics 53.117 - Ununseptium atomic config


elemental family geometry
Uuo
3 2 1 0 1 2 3
R Q P O N M L K
8
18
32
32
18
8
2
8 7 6 5 4 3 2 1
f d p s p d f
electron configuration
Ununoctium
Q
K
P∑
29
25
Baryon rest quanta
lepton rest quanta
KEM
[[72(n²)] + [12e19] + [Δv]]
7
1
nuclear mass-energy quanta per shell
[Rn] 5f14 6d10 7s2 7p6
Noble Gas
Azmithal & Magnetic numbers
1 0 1
2 2
3 3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
118
13 11 9 7 5 3 1
9 7 5 3 1
5 3 1
1 2
2 4 6
2 4 6 8 10
2 4 6 8 10 12 14
f d p s p d f
Atomic Shells
Orbitals & sub-Orbitals
Energy levels

Tetryonics 53.118 - Ununoctium atomic config

elemental family geometry




3 2 1 0 1 2 3
R Q P O N M L K
1
8
18
32
32
18
8
2
8 7 6 5 4 3 2 1
f d p s p d f

electron configuration



Ununnenium

$$\sum_{K}^{R} P\,{}^{29}_{25}\left[[72(m^2)] + [12e19] + [\Delta v]\right]_{1}^{8}$$

Baryon rest quanta — lepton rest quanta — KEM

nuclear mass-energy quanta per shell

[Uuo] 8s1

Alkali Metal

Azmithal & Magnetic numbers


R Q P O N M L K
8 7 6 5 4 3 2 1
0
119
1 1
+1 0 -1 -1 0 +1
2 2
+2 +1 0 -1 -2 -2 -1 0 +1 +2
3 3
+3 +2 +1 0 -1 -2 -3 -3 -2 -1 0 +1 +2 +3
13 11 9 7 5 3 1 2 4 6 8 10 12 14
f f
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2

Atomic Shells

Energy levels

Orbitals & sub-Orbitals

Tetryonics 53.119 - Ununnenium atomic config


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
2 8 18 32 32 18 8 2
8 7 6 5 4 3 2 1
f d p s p d f
Unbinilium
R
K
P
29
25
Baryon rest quanta
lepton rest quanta
KEM
[72(n²)] + [12e19] + [Δv]
8
1
nuclear mass-energy quanta per shell
[Uuo] 8s2
Alkaline Earth
Azmithal & Magnetic numbers
0
120
1 1
2 2
3 3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
13 11 9 7 5 3 1
9 7 5 3 1
5 3 1
1 2
2 4 6
2 4 6 8 10
2 4 6 8 10 12 14
f d p s p d f
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 53.120 - Unbinilium atomic config

Copyright ABRAHAM [2008] - All rights reserved

Chemical element bonding

All Deuterium nuclei pack in hexagonal patterns
to form larger atoms & molecules



Individual chemical element topologies
are mapped using Cormier grid

Hexagonal tiling
is a regular tiling of
the Euclidean plane

Tetryonic chemistry
utilises hexagonal tiling for
modelling chemical bonds

unfilled atomic orbital
positions are indicated
by vacant hexagonal
tiles

Euclidean space is tiled with
equilateral tessellations
of Planck mass-energy
geometries

Tetryonic mass-Matter topologies
can be represented as hexagonal
cells in a Cormier grid

When seeking the most stable energy configurations
nuclei & atoms bond to create filled s&p [stable octet]
electron orbital patterns as welll as filled d & f orbitals.

Copyright ABRAHAM [2008] - All rights reserved

Periodic Table Atomic configurations


252
[126-126]
Li
6.1615
138,708
3,672
504
[252-252]
C
12.6493
284,760
14,688
672
[336-336]
O
16.9744
382,128
36,864

Allotropes are different structural forms of the same element and can exhibit quite different physical properties and chemical behaviours

Lithium


252
[126-126]
Li
6.1615
135,036
[0.99605577602 e-26 kg]

Oxygen


672
[336-336]
O
15.995
360,096
[2.656154027 e-26 kg]

Allotropes

The Periodic Table, although useful in identifying Elements via their atomic and quantum numbers, does not reflect all the charged topologes that Deuterium nuclei can form as they combine.

Various atomic configurations with the same Tetryonic charge, but differing in their final mass-Matter topologies and properties can be formed - they are the Allotropes

Some of the more plentiful chemical elements form this way

Carbon


504
[254-254]
C12
11.9968
C12
270,072

6 [Protons [24-12] ; Neutrons [18-18] ; electrons [0-12]] m1


504
[252-252]
C
11.9968
270,072

6 [Protons [24-12] ; Neutrons [18-18] ; electrons [0-12]] m1


504
[252-252]
C
12.6493
284,760
14,688

6 [Protons [24-12] ; Neutrons [18-18] ; electrons [0-12]] m1-2

Allotropes are elements created from the same number of Deuterium nuclei as periodic elements but possess a differing mass-Matter topology

Q

same component charge


336
[168-168]
Beryllium
8
2
1
1
3
2
1
183,756

different Matter geometries

M

The varying material geometries allows what is the same chemical element to possess vastly different bonding points and chemical attributes


336
[168-168]
Be
8.3241
2
1
2 Be
2
187,392
[1.38224811e-26 kg]

Allotropic geometries

[charge vs Matter]


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
2
f
d
p
s
p
d
f

Some element allotropes have different Matter topologies that persist in different phases


336
[168-168]
Beryllium
8
1
1
1
3
4
1
2
1
180,048

Allotropes vs. Isotopes

Isotopes are elementary atoms with the same number of nuclei, but with differing energy levels, resulting in different mass-energies


336
[168-168]
Beryllium
9
1
1
1
3
4
1
2
1
210,384

Copyright ABRAHAM [2008] - All rights reserved


504
[252-252]
C
12.6493
1
2
3
5
6
C
1
4
2
284,760
[2.10045764e-26 kg]
14,688
[0.6077GeV]

Carbon Allotropes

Carbon is capable of forming many allotropes due to its valency.

Well known forms of carbon include:

- Carbon
- Diamond
- Graphite
- Graphene
- Amorphous carbon
- Buckminsterfullerenes
- Carbon nanotubes
- Glassy carbon
- atomic & diatomic carbon

Tetryonic theory affords us the ability to model the charged mass-energy geometries & 3D Matter topologies of each element along with its bonding points


504
[254-254]
C
11.996
5
1
3
4
2
6
270,072
Ground energy level

It also allows for the calculation of the molar rest mass-energy geometry of any Matter topology


504
[254-254]
C
11.996
6
5
1
C12
4
2
3
1
270,072
Ground energy level

Graphene has a unique p orbital arrangement of its electrons


Q
RE
n
C12
M
KE

Electron Configuration

[n] p6

Shell			Molar meM	Nuclei per shell
R	8	446,976	19.855	6
Q	7	418,680	18.598	6
P	6	391,392	17.385	6
O	5	365,112	16.218	6
N	4	339,840	15.095	6
M	3	315,576	14.018	6
L	2	292,320	12.985	6
K	1	270,072	11.996	6

Carbon-14, a radioactive isotope of carbon with a half-life of 5,730 years, is used to find the age of formerly living things through a process known as radiocarbon dating.

In 1961 the international unions of physicists and chemists agreed to use the mass of the isotope carbon-12 as the basis for atomic weight.


504
[254-254]
C
11.996
6
1
3
4
2
5
1
270,072
Ground energy level

energy level

There are nearly ten million known carbon compounds and an entire branch of chemistry, known as organic chemistry, is devoted to their study.

Graphene



Graphene is also an allotrope of carbon.

Its structure is one-atom-thick planar sheets of sp2-bonded carbon atoms that are densely packed in a honeycomb crystal lattice

Graphite

The mineral graphite is an allotrope of carbon.

Unlike periodic table carbon [diamond], graphite is an electrical conductor, a semi-metal.

And Graphite is the most stable form of carbon under standard conditions.

Graphite has a layered, planar structure. In each layer, the carbon atoms are arranged in a hexagonal lattice





Graphite electrons can act as atomic bearings between the planar sheets of graphene





Tetryonic modelling of C12 atoms reveals two packing densities can occur between graphene atoms as they form graphite sheets

Unlike periodic carbon where electrons are tightly bound, graphite is highly conductive, with electrical energy being propagated via the electrons & their KEM fields



Graphene electrons are loosley bound to the top of the Deuterium nuclei

Carbon Nanotubes

Carbon nanotubes (CNTs) are allotropes of carbon
with a cylindrical nanostructure.



Large molecules consisting only of carbon, known as buckminsterfullerenes, or buckyballs, have recently been discovered and are currently the subject of much scientific interest.

A single buckyball consists of 60 or 70 carbon atoms (C60 or C70) linked together in a structure that looks like a soccer ball.

They can trap other atoms within their framework, appear to be capable of withstanding great pressures and have magnetic and superconductive properties.

They can be thought of as a sheet of graphite
(a hexagonal lattice of carbon) rolled into a cylinder.

C36



C12



**Carbon nanotubes are the strongest
and stiffest materials yet discovered**

Maybe the most significant spin-off product of fullerene research, leading to the discovery of the C60 "buckyball" by the 1996 Nobel Prize laureates Robert F. Curl, Harold W. Kroto, and Richard E. Smalley, are nanotubes based on carbon or other elements.

These systems consist of graphite layers seamlessly wrapped to cylinders.

Excitingly, Tetryonic theory points clearly to the possibility that organo-carbon nanotubes can be created.

Where C36 periodic carbon could be used insetad of conventional C12 graphene atoms

Carbyne

C60



Nanotubes are members of the fullerene structural family, which also includes the spherical buckyballs, and the ends of a nanotube may be capped with a hemisphere of the buckyball structure.

Diamonds

are a metastable allotrope of carbon,
where the carbon atoms are arranged in
cubic crystal structure called a diamond lattice.







Periodic [C6] Carbon

Diamonds are renowned as a material with superlative physical qualities,
most of which originate from the strong fascia bonds between its atoms.



Ionised [C6] Carbon

Most natural diamonds are formed at high temperature
and pressure at depths of 140 to 190 kilometers in the Earth's mantle
[resulting in the loss of electrons form bound positions, making
them poor conductors compared to grahphene atoms].



filled n[C7] Carbon diamond lattice



The chemical bonds that hold the carbon atoms in diamonds together
are stronger than those in graphite.

In diamonds, the bonds form an inflexible three-dimensional lattice, whereas in graphite,
the atoms are tightly bonded into sheets, which can slide easily over one another, making the overall structure weaker



Organo-Carbon
biological molecule

Copyright ABRAHAM [2008] - All rights reserved

Oxygen Allotropes

There are several known allotropes of oxygen.
The most familiar is molecular oxygen (O2), present at significant levels in Earth's atmosphere and also known as dioxygen or triplet oxygen.
Another is the highly reactive ozone (O3).

Others include:
Atomic oxygen (O1, a free radical)
Singlet oxygen (O2), either of two metastable states of molecular oxygen
Tetraoxygen (O4), another metastable form
Solid oxygen, existing in six variously colored phases, of which one is O8 and another one metallic

Atomic Oxygen also forms bonds easily with Hydrogen to create Hydroxy compounds


OH
Hydroxide
720
[360-360]


O3
Ozone
2,016
[1,008-1,008]


TetraOxygen
O4
2,688
[1,344-1,344]


O2
Oxygen
1,344
[672-672]

All charge fascia interact and bind where possible to form neutral chemical bonds


TetraOxygen
O4
2,688
[1,344-1,344]


1,344
[672-672]
O2
Oxygen


O3
Ozone
2,016
[1,008-1,008]

Tetryonics 54.08 - Oxygen allotropes

Copyright ABRAHAM [2008] - All rights reserved


1,260
P
741,996
66,816

Phosphor Allotropes

Elemental phosphorus can exist in several allotropes; the most common of which are white and red solids.

Solid violet and black allotropes are also known.

Gaseous phosphorus exists as diphosphorus and atomic phosphorus.


P_2
65.920
1,260
[630-630]
1,260
[630-630]
2,520
[1,260-1,260]

The diphosphorus allotrope (P2) can be obtained normally only under extreme conditions (for example, from P4 at 1100 kelvin).

Nevertheless, some advancements were obtained in generating the diatomic molecule in homogenous solution, under normal conditions with the use by some transition metal complexes (based on for example tungsten and niobium).


P_6
197.760
7,560
[3,780-3,780]
1,260
[630-630]
1,260
[630-630]
1,260
[630-630]
1,260
[630-630]
1,260
[630-630]
1,260
[630-630]

Black phosphorus is the thermodynamically stable form of phosphorus at room temperature and pressure. It is obtained by heating white phosphorus under high pressures (12,000 atmospheres).

In appearance, properties and structure it is very like graphite, being black and flaky, a conductor of electricity, and having puckered sheets of linked atoms

Sulfur Allotropes


2,688
[1,344-1,344]
S2
disulfur


S4
tetrasulfur
5,376
[2,688-2,688]
4,032
[2,016-2,016]
S3
trisulfur


1,344
S
794,496
74,304

Charged fascia interactions
between differing elements
result in the familiar
chemical bonds

Sulfur [like Carbon]
can form Chains
or Ring compounds

There are a large number of allotropes of sulfur.
In this respect, sulfur is second only to carbon.

cyclo-hexasulfur


8,064
[4,032-4,032]

Isotopes

In addition to forming varying allotropic elements

Atoms can also absorb energy directly and create numerous elemental isotopes as a result of their differing nuclear energy levels

Deuterium nuclei with bound photo-electrons form quantum-scale synchronous converters

n
R
8
Q
7
P
6
O
5
N
4
M
3
L
2
K
1
Shell
Level

0	Hydrogen	22,512	24,384	26,352	28,416	30,576	32,832	35,184	37,632
Element		1	2	3	4	5	6	7	8
1	**Deuterium**	45,012	48,720	52,596	56,640	60,852	65,232	69,780	74,496
2	**Helium**	90,024	97,440	105,192	113,280	121,704	130,464	139,560	148,992
3	**Lithium**	135,036	146,160	157,788	169,920	182,556	195,696	209,340	223,488
4	**Berylium**	180,048	194,880	210,384	226,560	243,408	260,928	279,120	297,984
5	**Boron**	225,060	243,600	262,980	283,200	304,260	326,160	348,900	372,480
6	**Carbon**	270,072	292,320	315,576	339,840	365,112	391,392	418,680	446,976
7	**Nitrogen**	315,084	341,040	368,172	396,480	425,964	456,624	488,460	521,472
8	**Oxygen**	360,096	389,760	420,768	453,120	486,816	521,856	558,240	595,968
9	**Fluorine**	405,108	438,480	473,364	509,760	547,668	587,088	628,020	670,464
10	**Neon**	450,120	487,200	525,960	566,400	608,520	652,320	697,800	744,960
11	**Sodium**	495,132	535,920	578,556	623,040	669,372	717,552	767,580	819,456
12	**Magnesium**	540,144	584,640	631,152	679,680	730,224	782,784	837,360	893,952
13	**Aluminium**	585,156	633,360	683,748	736,320	791,076	848,016	907,140	968,448
14	**Silicon**	630,168	682,080	736,344	792,960	851,928	913,248	976,920	1,042,944
15	**Phosphorus**	675,180	730,800	788,940	849,600	912,780	978,480	1,046,700	1,117,440
16	**Sulfur**	720,192	779,520	841,536	906,240	973,632	1,043,712	1,116,480	1,191,936
17	**Chlorine**	765,204	828,240	894,132	962,880	1,034,484	1,108,944	1,186,260	1,266,432
18	**Argon**	810,216	876,960	946,728	1,019,520	1,095,336	1,174,176	1,256,040	1,340,928
19	**Potassium**	855,228	925,680	999,324	1,076,160	1,156,188	1,239,408	1,325,820	1,415,424
20	**Calcium**	900,240	974,400	1,051,920	1,132,800	1,217,040	1,304,640	1,395,600	1,489,920

Level
R
8
Q
7
P
6
O
5
N
4
M
3
L
2
K
1
Shell

It is the increased nucleonic energy levels that creates isotopes (not extra Neutrons within an atomic nucleus)



The energy level of Baryons determines the KEM energies of photo-electrons bound to them

Most isotopes are considered
to be radioactive as a result of
the nuclei seeking to release excess
energy in the form of photons of energy
or particles with high kinetic energies

Carbon Isotopes

It is widely held in the scientific community tha: Carbon-14, 14C, or radiocarbon, is a radioactive isotope of carbon with a nucleus containing 6 protons and 8 neutrons.

It is in fact a nucleus comprised of 6 deuterium nuclei [with 6 Protons, 6 Neutrons & 6 electrons]

The mistaken belief in 'extra' neutrons being present in the nucleus stems from the fact that electrons and protons combine in equal numbers in the atomic nucleus and historically attributing the mass in excess of this as being the result of the mass contribution of 'extra' neutrons

Tetryonics finally corrects this erroneous assumption

Carbon 12-14


504
[254-254]
C12
11.996
C12
6 Deuterium nuclei
6
5
1
4
2
3
n1
1
6 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1
270,072
[1.99211542e-26 kg]
KEM

There are NO extra neutrons (in excess of the element's Z#) in the nuclei of atomic isotopes.

The measured 'excess mass' is the direct result of the raised quantum levels of the Deuterium nuclei that comprise each atomic element

And is compreletely accounted for in Tetryonic theory by calculating for the total rest mass-energies in each elementary Matter topology.

The 'extra' mass historically attrtibuted to neutron numbers above that of the elemental number are now reflected as stored kinetic 'chemical' energies as they always were.

ALL elements & isotopes have equal numbers of Protons, electrons & Neutrons


504
[254-254]
C13
12.9850
6 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n2
6
5
1
n2
4
2
3
1
292,320
[2.156220002e-26 kg]
22,248
[920 MeV]



Quantum levels of atomic nuclei contribute to the molar mass [Isotopes are higher energy nuclei]


504
[254-254]
C14
14.0181
6
5
1
n3
4
2
3
1
6 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n3
315,576
[2.127703802e-26 kg]
45,504
[1,8828 MeV]

	n1	n2	n3	n4	n5	n6	n7	n8
C12	270,072	292,320	315,576	339,840	365,112	391,392	418,680	446,976
KEM diff	0	22,248	45,504	69,768	95,040	121,320	148,608	176,904
neutron #		.98	2.0	3.1	4.2	5.4	6.6	7.8

This applies equally to all atomic nuclei



Electron Configuration
[n] p1

Atoms store mass-energies in their standing wave Matter topologies and release it via radioactive decay paths

It is increased kinetic energy level geometries that create nuclear isotopes (not extra Neutrons within a nucleus)


504
[254-254]
C12
11.996
n1
6
5
1
4
2
3
1
270,072
[1.99211542 e-26 kg]
Ground energy level


504
[254-254]
C13
12.9850
n2
6
5
1
4
2
3
1
292,320
[2.15622002 e-26 kg]
22,248
[.998 Neutrons]
[920.5 MeV]


504
[254-254]
C14
14.0181
n3
6
5
1
4
2
3
1
315,576
[2.327763802 e-26 kg]
45,504
[2.0224 Neutrons]
[1.882 GeV]


504
[254-254]
C15
15.0959
n4
6
5
1
4
2
3
1
339,840
[2.50674085 e-26 kg]
69,768
[3.1008 Neutrons]
[2.886 GeV]


504
[254-254]
C16
16.218
n5
6
5
1
4
2
3
1
365,112
[2.693153146 e-26 kg]
95,040
[4.224 Neutrons]
[3.925 GeV]


504
[254-254]
C17
17.385
n6
6
5
1
4
2
3
1
391,392
[2.88700069 e-26 kg]
121,320
[5.392 Neutrons]
[5.019 GeV]


504
[254-254]
C18
18.589
n7
6
5
1
4
2
3
1
418,680
[3.08828359 e-26 kg]
148,608
[6.6048 Neutrons]
[6.145 GeV]


504
[254-254]
C19
19.855
n8
6
5
1
4
2
3
1
446,976
[23.297000964 e-26 kg]
176,904
[7.8624 Neutrons]
[7.319 GeV]

Shell			Molar meM	Nuclei per shell
R	8	446,976	19.855	6
Q	7	418,680	18.598	6
P	6	391,392	17.385	6
O	5	365,112	16.218	6
N	4	339,840	15.095	6
M	3	315,576	14.018	6
L	2	292,320	12.985	6
K	1	270,072	11.996	6

energy level

22,500
[1 Neutron]

n

[930.97 MeV]

Kinetic mass-energy geometries stored in 3D Matter topologies is released as Chemical energies

Deuterium nuclei with bound photo-electrons fom quantum-scale synchronous converters

Copyright ABRAHAM [2008] - All rights reserved


588
[294-294]
N
14.8118
333,444
[2.4659562315 e-26 kg]
18,360
[0.759 GeV]

It is Increased Nucleonic energy levels that creates Isotopes (not extra Neutrons within any elementary Nucleus)

Nitrogen gas


1,176
[588-588]
2N
29.623
666,888
[4.919124858e-26 kg]
36,720
[1.51938 GeV]

Nitrogen Allotropes & Isotopes


588
[294-294]
N15
15.149
341,040
[2.515592424 e-26 kg]
25,959
[1.0740 GeV]

Isotopes are created by increasing the number of Planck mass-energies stored in the standing-wave geometries of chemical elements


588
[294-294]
N14
13.996
315,084
[2.324134774 e-26 kg]
Ground energy level nuclei

The charged mass-energy geometries of differing allotropic topologies create various chemical bond points

Shell			Molar meM	Nuclei per shell
R	8	521,472	23.164	7
Q	7	488,460	21.697	7
P	6	456,624	20.283	7
O	5	425,964	18.921	7
N	4	396,480	17.612	7
M	3	368,172	16.354	7
L	2	341,040	15.149	7
K	1	315,084	13.996	7
				7

energy level
7
5
3
1
2
4
6

Copyright ABRAHAM [2008] - All rights reserved


672
[336-336]
O16
15.995
360,096
[2.656153934e-26 kg]
Ground energy
level nuclei


672
[336-336]
O17
17.313
389,760
2.87496266 e-26 kg]
36,664
1 Neutron


672
[336-336]
O18
18.690
420,768
[3.10368506 e-26 kg]
60,672
2 Neutrons


672
[336-336]
O20
20.127
453,120
[3.3423283 e-26 kg]
93,024
4 Neutrons

Oxygen Allotropes & Isotopes


Electron Configuration
ɱ s2 p6
Q
RE
M
KE
p5
p4
s1
p1
p2
s2
p3
p6
1
2
1
1
1
1
2
1

This oxygen allotrope's nuclei arrangement is very stable and inert like Neon [due to its filled sp electron orbitals]


672
[336-336]
O
18.9744
382,128
[2.8866797 e-26 kg]
22,032
[0.005 GeV]

There exists an allotrope of Oxygen formed when 8 nuclei combine in a single level SP orbital arrangement

Shell			Molar meM	Nuclei per shell
R	8	595,968	26.473	8
Q	7	558,240	24.797	8
P	6	521,856	23.181	8
O	5	486,816	20.825	8
N	4	453,120	20.127	8
M	3	420,768	18.690	8
L	2	389,760	17.313	8
K	1	360,096	15.995	8


energy
level
7
5
3
1
2
4
6
8
8

It is Increased Nucleonic energy levels that creates Isotopes (not extra Neutrons within a Nucleus)


672
[336-336]
O21
20.825
468,816
[3.59087068 e-26 kg]
108,720
4 Neutrons


672
[336-336]
O23
23.181
521,856
[3.84933425 e-26 kg]
161,760
7 Neutrons


672
[336-336]
O24
24.797
558,240
[4.1177831 e-26 kg]
198,144
8 Neutrons


672
[336-336]
O26
26.473
595,968
[4.396 e-26 kg]
235,872
10 Neutrons

Tetryonics 54.15 - Oxygen isotopes

Copyright ABRAHAM [2008] - All rights reserved

Bose–Einstein condensates exist at the low energy extremes











Gaseous

Liquid



The Natural states of Matter

(room temperature)

The halogen element family provides a great example of all 4 states of Matter at room temperature

Elements appear in their natural phase at room temperature as a gas, liquid, solid or synthetic

As energy is added or removed from any element's charged Matter topology or their baryonic KEM field geometry their phase states & Brownian motion changes

Solid

Radioactive









At the high energy extremes exist the Plasma states of Matter

Chemical bonds

A chemical bond is an attraction between atoms that allows the formation of chemical substances that contain two or more atoms.

Particle charge & Inter-fascia electric interaction provides the foundation of chemical bonds







It is usually taught that based on electron sharing principles a single bond contains 2 paired electrons, a double bond has 4 electrons and a triple bond has 6 shared electrons

filled electron shells
[weak KEM'ical bonds]

single bond

Charged baryon fascia and electron sharing both play roles in facilitating chemical bonds

double bond



Lewis diagrams are not an accurate representation of chemical bonding in elements or compounds



triple bond

unfilled electron shells
[stronger KEM'ical bonds]

Tetryonic geometry provides an advanced quantum topology for all atoms and compounds that is superior to the older Lewis diagrams and even molecular orbital theory, facilitating a clear understanding of the quantum geometry of each element, its nuclear bonds and electron sharing in all compound chemical structures; along with the core & valence electron configurations & interactive electric charge fascia bonding positions for each compound created.

ethane
[C2H6]

6 valence electrons



ethene
[C2H4]

4 valence electrons



ethyne
[C2H2]

2 valence electrons



Valance electrons also play an important role in determining the strength of chemical bonds

Van der Waals Forces

Van der Waals forces include attractions between atoms, molecules, and surfaces. They differ from covalent and ionic bonding in that they are caused by correlations in the fluctuating polarizations of nearby particles

All charges seek equilibrium





Van der Walls and London forces are the geometric fields of interaction between charged Matter topologies



The Forces of interaction can be attractive or repulsive

Residual interactive bonding force between the charged fascia of atoms

Resulting in the creation of larger-scale chemical compounds and molecules



This is considered to be the only attractive intermolecular force present between neutral atoms (e.g., a noble gas configurations and charge neutral atomic topologies).



Without London forces, there would be no attractive force between noble gas atoms, and they wouldn't exist in liquid form.



Lewis Structures

The Lewis structure was named after Gilbert N. Lewis,
who introduced it in his 1916 article
The Atom and the Molecule.

Lewis structures, also called Lewis-dot diagrams,
are diagrams that show the bonding between the atoms of any molecule,
and the lone pairs of electrons that may exist in the molecule.



BeCl2



HF

Line drawings can be used to depict molecular geometry:


Beryllium dichloride
$BeCl_2$
linear


Borane
BH_3
trigonal planar


Methane
CH_4
tetrahedral


Ammonia
NH_3
trigonal pyrimidal


Water
H_2O
bent


Hydrofluoric acid
HF
linear

Also applies to molecules with multiple bonding:


methanal
(formaldehyde)
trigonal planar


Carbon dioxide
linear


ethyne
(acetylene)
linear


ethane
(ethylene)
both carbons are trigonal planar

Hydrogen is a 'free radical' atom whose energy can be changed to facilitate chemical bonding between elements

Tetryonic geometry uses the charged geometry of the element fascia themselves

to show the bonds and charge interactions between differing elements as they form larger compounds

as well as the actual final quantum topology of compound elements and molecules

They are similar to electron dot diagrams in that the valence electrons in lone pairs are represented as dots, but they also contain lines to represent shared pairs in a chemical bond (single, double, triple, etc.).



HCHO

single
fascia bond



double
fascia bonds



triple
fascia bond





C2H4

it is the electric field fascia of baryons that facilitates chemical bonds

Copyright ABRAHAM [2008] - All rights reserved

Atomic bonds

All atoms, elements and compounds seek stable core energy & configurations where their electron orbitals are filled





Hydrogen σ bonds
Outward presenting electic fascia bonds
Facilitate bonding between molecules



Molecular π bonds
Inward recieving bonds
capable of accepting Hydrogen
or extra-orbital elctric fascia bonds

Bonds fill in order of orbital filling
ie p1-6, d1-10

OH



Hydroxide bonds
Oxygen-Hydrogen compound
creates a halogen-like topology
which seeks to fill its p6 orbital
in order to reach a stable electronic
configuration

Extremely reactive



HCO3
Bi-Carbonate
ion



NO3
Nitrate
ion

Nitrate and Carbonate Ions
have equivalent electron
configurations (Isoelectronic)



Core electron configuration
Unreactive [non-valence]
electron configuration

CH4



Covalent bonds
Intra-orbital bonding between
elements and compounds where
electrons exchange is the main
mechanisium resulting in
stable electronic configurations

Ionic bonds
Extra-orbital bonding between
elements and compounds where
element charge attraction is the
predominent mechanism
with electrons sharing resulting in
stable electronic configurations



NaCl

Tetryonics 55.05 - Atomic facsia Bonds

Atomic bonds

All atoms, elements and compounds seek stable core electron configurations where their electron orbitals are filled





Hydrogen Bonds

Outward presenting electic fascia bonds
Facilitate bonding between molecules



Molecular bonds

Inward recieving bonds
capable of accepting Hydrogen
or extra-orbital elctric fascia bonds

Bonds fill in order of orbital filling
ie p1-6, d1-10

OH



Hydroxide bonds

Oxygen-Hydrogen compound
creates a halogen-like geometry
which seeks to fill its p6 orbital
in order to reach a stable electronic
configuration

Extremely reactive



HCO3
Bi-Carbonate
ion



NO3
Nitrate
ion

Nitrate and Carbonate Ions

have equivalent electron
configurations (Isoelectronic)



Core electron configuration

Unreactive [non-valence]
electron configuration

CH4



Covalent bonds

Intra-orbital bonding between
elements and compounds where
electrons exchange is the main
mechanisism resulting in
stable electronic configurations

Ionic bonds

Extra-orbital bonding between
elements and compounds where
element charge attraction is the
predominent mechanism
with electrons sharing resulting in
stable electronic configurations



NaCl

CORE ELECTRON configurations

			[He]
L	1s2	2s2 2p6	[Ne]
M	1s2 2s2 2p6	3s2 3p6	[Ar]
N	1s2 2s2 2p6 3s2 3p6 3d10	4s2 4p6	[Kr]
O	1s2 2s2 2p6 3s2 3p6 3d10 4s2 4p6 4d10	5s2 5p6	[Xe]
P	1s2 2s2 2p6 3s2 3p6 3d10 4s2 4p6 4d10 4f14 5s2 5p6 5d10	6s2 6p6	[Rn]
Q	1s2 2s2 2p6 3s2 3p6 3d10 4s2 4p6 4d10 4f14 5s2 5p6 5d10 5f14 6s2 6p6 6d10	7s2 7p6	[Uuo]

The term "core electrons" or "noble gas core" refers to the electrons within the atom which have the same electron configuration as the nearest noble gas of lower atomic number and contain filled s&p orbitals

'Nobel Gas' configuration
full s,p orbitals


p5
p4
s1
p1
p2
s2
p3
p6

'core electron' configurations are present in energy levels L [2] - [7] Q

electrons not in filled or complete atomic orbitals are valence electrons

"OCTET"
No valance

Using core electron notation greatly reduces complexity of the electron configuration notations of larger elements in the periodic table

[Ub] 1s2 2s2 2p6 3s2 3p6 3d10 4s2 4p6 5s2 4d10 5p6 4f14 5d10 6s2 6p6 5f14 6d10 7s2 7p6 8s2
120
2 8 18 32 32 18 8 2

They are the electrons in the inner part of the atom that are not valence electrons and therefore do not participate in bonding

[Uuo] 8s2
118


840
Ne
479,496
29,376

[He] 2s2 2p6
2

1,512
Ar
899,496
89,280

[Ne] 3s2 3p6
10

3,024
Kr
1,876,176
255,744

[Ar] 3d10 4s2 4p6
18

4,536
Xe
2,925,288
494,640

[Kr] 4d10 5s2 5p6
36


7,224
Rn
4,839,864
968,832

[Xe] 4f14 5d10 6s2 6p6
54

9,912
Uuo
6,889,512
1,578,096

[Rn] 5f14 6d10 7s2 7p6
86

Copyright ABRAHAM [2008] - All rights reserved

Core electron configurations

Core electrons are the electrons in an atom that are not valence electrons and therefore do not participate in bonding.

Reactive



Elements with more nuclei than the core configurations are reactive


p
s
p
Q
[118]
Ununoctium
P
[86]
Radon
O
[54]
Xenon
N
[36]
Krypton
M
[18]
Argon
L
[10]
Neon
K
[2]
Helium

Reactive elements combine with other elements seeking core electron configurations

Inert

Nobel gases are found amongst the by-products of unstable element decay



Noble Gases have stable inert electron configurations [core electrons]

Copyright ABRAHAM [2008] - All rights reserved

!

Helium is a unique noble gas in that it only has filled s-orbitals

suggesting that it be more appropriate to designate it as an alkaline earth gas


filled s elctron configuration
168
He
Helium
90,024
Alkaline Earth
2
Protons
Neutrons
electrons
n1
1s2


filled s & p elctron configuration
840
420 420
Ne
Neon
479,496
29,376
10
Protons
Neutrons
electrons
n1-2
[He] 2s2 2p6


filled s & p elctron configuration
1,512
756 756
Ar
Argon
899,496
89,280
18
Protons
Neutrons
electrons
n1-3
[Ne] 3s2 3p6



Nobel gases all have inert core sp electron configurations


filled s,p & d elctron configuration
3,024
1,512 1,512
Kr
Krypton
1,876,176
255,744
36
Protons
Neutrons
electrons
n1-4
[Ar] 3d10 4s2 4p6

The Nobel Gases

are nuclei whose electron orbitals are completely filled
(and consequently have no valence electrons for bonding)

2			[He]
10	1s2	2s2 2p6	[Ne]
18	1s2 2s2 2p6	3s2 3p6	[Ar]
36	1s2 2s2 2p6 3s2 3p6 3d10	4s2 4p6	[Kr]
54	1s2 2s2 2p6 3s2 3p6 3d10 4s2 4p6 4d10	5s2 5p6	[Xe]
86	1s2 2s2 2p6 3s2 3p6 3d10 4s2 4p6 4d10 4f14 5s2 5p6 5d10	6s2 6p6	[Rn]
118	1s2 2s2 2p6 3s2 3p6 3d10 4s2 4p6 4d10 4f14 5s2 5p6 5d10 5f14 6s2 6p6 6d10	7s2 7p6	[Uuo]

All nobel gases have filled electron orbitals creating inert, chemically un-reactive elements


filled s,p,d & f elctron configuration
7,224
3,612 3,612
Rn
Radon
4,839,864
968,832
86
Protons
Neutrons
electrons
n1-6
[Xe] 4f14 5d10 6s2 6p6


filled s,p & d elctron configuration
4,536
2,268 2,268
Xe
Xenon
2,925,288
494,640
54
Protons
Neutrons
electrons
n1-5
[Kr] 4d10 5s2 5p6

The noble gases are a group of chemical elements with very similar properties: under standard conditions, they are all odorless, colorless, monatomic gases, with a very low chemical reactivity.

Whilst some of the nobel gases are often termed core electron configurations the large elements also have filled d & f orbitals in them

The six noble gases that occur naturally are Helium (He), Neon (Ne), Argon (Ar), Krypton (Kr), Xenon (Xe), and the radioactive noble gases are Radon (Rn) and Ununioctium (Uuo).


filled s,p,d & f elctron configuration
9,912
4,956 4,956
Uuo
Ununoctium
6,889,512
1,578,096
118
Protons
Neutrons
electrons
n1-7
[Rn] 5f14 6d10 7s2 7p6

Molecular Bonds

Hydrogen bonds

A weak, primarily electrostatic, bond between a hydrogen atom bound to a highly electronegative element in a given molecule and a second highly electronegative atom in another molecule

Diatomic bonds are fascia interactions between molecules with the same nuclei number [O2, F2, I2, Cl2]

Sigma bonds


s1
s2
s1
s2
s1
s2

The residual EM force between opposite charge fascia in nuclei holds individual nuclei together in turn resulting in larger molecules and compounds

Pi bonds


p5
p4
s1
residual Strong Force
p1
p2
internalised EM charges
s2
p3
p6

Molecular bonds


p5
p4
s1
Stable inert Nobel gas config
external s&p fascia interaction
p1
p2
s2
p3
p6

A molecular bond is an attractive force between nuclei that allows two or more elements or atoms to combine into a singular, complex compound structure


Oxygen Molecule
Hydrogen Sulfate Molecule
3 bonded Water Molecules
Carbon Dioxide Molecule
Trishexane Molecule
O
S
H
C
p5
p6
1
2
3

Tetryonic mass-energy geometries & 3D Matter topologies provide for the modelling of even the most complex chemical bonding arrangements

Copyright ABRAHAM [2008] - All rights reserved

Covalent bonds are chemical links between two atoms in which electrons are shared between them.



Sigma bonds are covalent bonds formed by direct overlapping of two adjacent atom's outermost orbitals.



Note: sigma bonds can be formed by the bonding of either s-orbitals [or two adjacent p-orbitals]

Lewis electron dot diagrams fail to illustrate reality in that molecules exist as 3D objects and not as a two dimensional systems as shown by them.

Tetryonic geometry & topologies provide a polar view of 3D atomic nuclei that can be viewed as an exact representation of what a molecule & its bonds would look like when viewed from above.

Sigma & Pi covalent bonds



A pi bond is a covalent bond formed between two neighboring atom's unbonded p-orbitals.





The single electrons from each atom's p orbital combine to form an electron pair creating the sigma bond.





Double and triple bonds between atoms are usually made up of a single sigma bond and one or two pi bonds

$\pi - \sigma - \pi$





Alkali Metals


924
[462-462]
Na
23.6317
5
4
3
1
Na
1
1
2
1
2
1
2
3
1
6
531,996
[3.924129448 e-26 kg]
36,864
[1.5253 GeV]


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
1 valence electron
[Ne] 3s1
10
f
d
p
s
p
d
f

Atoms with more electrons than a closed shell are also highly reactive,
as the extra valence electrons are easily removed from that orbital
(to form a positive ion)



Valence electrons



are the highest energy electrons in an atom forming the outermost electrons of an atom, and are important in determining how the atom reacts chemically with other atoms

Historically, the number of valence electrons was reflected by the element's group number in the Mendeleev table and formed the basis of elemental families

Tetryonic topologies now replace the older, incorrect models of valence electron configurations with the full 3D modelling of all atoms, elements & compounds

[zz] are core electron configurations

providing a superior visual means of accurately determining the energies and position of any electron in chemical compounds and determining the valence numbers

Halogens


1,428
[714-714]
Cl
37.6242
2
3
2
Cl
2
2
1
6
3
2
846,996
[6.247644688 e-26 kg]
81,792
[3.6384 GeV]


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
7 valence electrons
[Ne] 3s2 3p5
10
f
d
p
s
p
d
f

Atoms one or two valence electrons short of a closed shell are highly reactive,
due to their tendency to seek to gain the missing valence electrons
(thereby forming a negative ion)

Hydro-Chloric acid



HCl

HNO3



Nitric acid

Carbonic acid



H2CO3

H2SO4



Sulfuric acid

Common Acids



The Arrhenius definition defines acids as substances which increase the concentration of hydrogen ions (H+), or more accurately, hydronium ions (H3O+), when dissolved in water.

The Brønsted-Lowry definition is the most widely used definition where acid-base reactions are assumed to involve the transfer of a proton (H+) from an acid to a base.

A Lewis acid is a substance that can accept a pair of electrons to form a covalent bond.



HC2H3O2



Acetic acid

Phosphoric acid



H3PO4

H2C2O4



Oxalic acid

Citric acid



H3C6H5O7

Copyright ABRAHAM [2008] - All rights reserved

Chemical reactions

Valence Bonds & Molecular orbitals

A chemical reaction is a process that leads to the transformation of one set of chemical substances to another.

Valence bond theory focuses on how the atomic orbitals of the dissociated atoms combine in molecular formations to give rise to individual chemical bonds.



In contrast, molecular orbital theory has orbitals that are designed to cover the whole molecule but is mathematically more complex in application



6 valence electrons
2 [n2] valence bonds available
(8 electron stable configuration)



water

Hydrogen Chloride gas



7 valence electrons
1 [n3] valence bond available
(8 electron stable configuration)

In order to form Hydro-chloric acid [HCl aq] and bond with similar water [H2O] molecules, the n2 Hydrogen atom's energy must be raised so it can migrate to the [3π6] orbital and bond

[n2] Hydrogen atom cannot bond in the [3π6] valence position so in HCl gas it forms a [n2] di-atomicbond instead and its electron migrates to the [π6] orbital



Hydrochloric acid



Aqueous Hydro-Chloric acid solution

Tetryonic theory replaces both VB & MO theories by modelling the physical quantum charge topologies and rest mass-energy geometry of all elements and compounds

Valence configurations seek to create stable filled obital configurations



Building on exisiting electron configuration nomenclature tetryonic theory provides a new bonding schema for elements and complex compounds alike that is fully reflective of the physical quantum charge interactions

Ionic Bonding



Alkaline Metal

Sodium atom develops into a nett POSITIVE charge ion





Household Salt

Sodium atom gives up an electron in order to create a stable [Ne] nobel gas configuration

Resultant salt [NaCl] molecule has a NEUTRAL charge with the n3 electron migrating to fill the 3p6 orbital



OPPOSITES ATTRACT

Chlorine atom seeks an electron to order to create a stable [Ar] nobel gas configuration



Halogen



Chlorine atom develops into a nett NEGATIVE charge ion

All atoms and molecules seek equilibrium via stable electron configurations



[Ne] electron configuration

[Ar] electron configuration

In short, it is a bond formed by the attraction between two oppositely charged ions.

An ionic bond (or electrovalent bond) is a type of chemical bond that can often form between metal and non-metal ions (or polyatomic ions such as ammonium) through electrostatic attraction.

The metal donates one or more electrons, forming a positively charged ion or cation with a stable electron configuration.
These electrons then enter the non metal, causing it to form a negatively charged ion or anion which also has a stable electron configuration.
The electrostatic attraction between the oppositely charged ions causes them to come together and form a bond.

Valence electron rules


Full s,p,d orbitals
'Nobel Gas'
p5
p4
s1
p1
p2
s2
p3
p6
Nobel gas
'inert'
electron
configuration
In any
element or compound
electrons in excess of
the sp8 config are
valence electrons
"OCTET"
No valance

sp8 - core electron orbital grouping

Tetryonic quantum charge topologies
provide the complete picture

Valence electrons are the highest quantum level electrons in elemental or compound atom nuclei in excess of the core sp8 'noble gas' electron configuration

They are located in the outer most shells (ie K-Q or Quantum 1-7) making them easily ionised from the elemental nuclei

s 1-2 [electron orbital pair]
p 1-2, 3-4, 5-6 [electron orbital pairs]
d 1-2, 3-4, 5-6, 7-8 , 9-10 [electron orbital pairs]
f 1-2, 3-4, 5-6, 7-8, 9-10, 11-12, 13-14 [electron orbital pairs]

Valance electron congigurations always include 's' orbital electrons due to their higher quantum levels

Developed from Lewis diagrams
is usually only useful for elements Z<20

Fluorine
[He] 2s2, 2p5
Valence - 7





Nickel
[Ar] 3d8, 4s2
Valence - 10

Gold
[Xe] 4f14, 5d9, 6s2
Valence - 11



Scandium
[Ar] 3d1, 4s2
Valence - 3





Indium
[Kr] 4d10, 5s2, 5p1
Valence - 3



Neon
[He] 2s2, 2p6



Sodium
[Ne] 3s1
Valence - 1



Krypton
[Ar] 4s2, 4p6



Mercury
[Xe] 4f14, 5d10, 6s2

Copyright ABRAHAM [2008] - All rights reserved

Filled electron orbitals

Once 8 valence electrons are reached a stable valence cofiguration is created

Once sub-orbit 8 (P7-8) is reached sequential valence numbering switches
to paired valence numbering (as per orbital energies)

Valence numbers can be calculated by adding the 2 highest energy orbitals together
(and subtracting 8 - if the total is higher than 8)

The octet rule is a simple chemical rule of thumb that states that atoms tend to combine in such a way that they each have eight electrons in their valence shells, giving them the same electronic configuration as a noble gas.

The rule is applicable to the main-group elements, especially carbon, nitrogen, oxygen, and the halogens, but also to metals such as sodium or magnesium. In simple terms, molecules or ions tend to be most stable when the outermost electron shells of their constituent atoms contain eight electrons.

In short, an element's valence shell is full and most stable when it contains eight electrons, corresponding to an s2p6 electron configuration.

CORE ELECTRONS

This stability is the reason that the noble gases are so unreactive, for example neon with electron configuration 1s2 2s2 2p6. (Helium is an exception as explained).

Note that a "full shell" means that there are the eight electrons in the valence shell when the next shell starts filling, even though higher subshells (d, f, etc.) have not been filled.

There can be at most eight valence electrons in a ground-state atom because p subshells are always followed by the s subshell of the next shell.

OCTET RULE

This means that once there are 8 valence electrons (when the p subshell is filled), the next additional electron goes into the next shell, which then becomes the valence shell.

A consequence of the octet rule is that atoms generally react by gaining, losing, or sharing electrons in order to achieve a complete octet of valence electrons. Reaction of atoms occurs primarily in two ways: ionically and covalently.


'S8P rule'
sub-orbit 8
[p7-8]
Transition orbit
Sequential valences
Valence Pairs

Once 8 valence electrons are reached the sub-orbits are stable and form a stable, non-reactive valence configuration.

Additionally, valence numbers proceed sequentially (1,2,3,4,5,6,7) up to sub-orbit 8 (P7-8) at which point all sub-orbit valences number in valence pairs (1-2, 3-4, 5-6, 7-8, 9-10, 11-2, 13-14)

The significance is that sub-orbit 8 is the middle sub-orbit (of 16 total sub-orbits possible)


full s-orbitals
'Nobel Gas'
Helium gas
'inert'
electron
configuration
s1
s2
2
"DIATOMIC"
No valance


full s,p orbitals
'Nobel Gas'
Nobel gas
'inert'
electron
configuration
p5
p4
s1
p1
p2
s2
p3
p6
8
"OCTET"
No valance

free
radical
atom
reactive
Hydrogen
bond
Hydrogen bond


full s,p,d-orbitals
'Transistion Metals'
d9
d1
d3
d7
d5
Noble Metal
electron
configuration
s
18
"Post-transition"
No valance
d6
d8
d4
d2
d10


f13
f1
f3
d9
f9
d1
d3
f11
d7
d5
f7
f5
s1
32
s2
full s,p,d,f-orbitals
'Radio-active'
"Actinoid/Lanthanoids"
No valance
f6
f8
d6
d8
f12
d4
d2
f10
d10
f4
f2
f14

Tetryonics 56.08 - Filled electron orbitals

Copyright ABRAHAM [2008] - All rights reserved

ACID

Hydrochloric acid is a clear, colourless solution of hydrogen chloride in water, it is a highly corrosive, strong mineral acid


Aqueous
Hydro-Chloric acid solution
[aqueous]
H2O
O
P
Cl
HCl


Proton
P
H3O
O
P
Cl
Cl –
Chlorine
Hydronium

The H(+) cation of the acid combines with the OH(-) anion of the base to form water.



+

all charges seek equilibrium

When an acid and a base are placed together, they react to neutralize the acid and base properties, producing a salt.

$\mathrm{HCl(aq)} + \mathrm{NaOH(aq)} \dashrightarrow \mathrm{NaCl(aq)} + \mathrm{H_2O(l)}$

=>

combining the free Protons & electrons


electron
P
+
=
H
Proton
Hydrogen

neutralises the ions and releases energy


O
NaOH
Na
Caustic
Soda


Hydroxide
O
OH-
Sodium
Na
Na+


Sodium Chloride
salt
Cl
Na
NaCl

The compound formed by the cation of the base and the anion of the acid is called a salt.

BASE

Sodium hydroxide, also known as caustic soda, or lye, has the molecular formula NaOH and is a highly caustic metallic base and alkali salt.

Geometric Molecular Topology

Molecules are most often held together with covalent bonds involving single, double, and/or triple bonds,
where a "bond" is a pair of electrons shared between elements as they seek equilibrium
(another method of bonding is ionic bonding and involves a positive cation and a negative anion).

Hydrogen

A Hydrogen bond is a chemical bond in which a hydrogen atom of one molecule is attracted to an electronegative atom, especially nitrogen, oxygen, or flourine atoms, usually of another molecule

The hydrogen bond is often described as an electrostatic dipole-dipole interaction.

However, it also has some features of covalent bonding: it is directional and strong, acting over interatomic distances shorter than that of van der Waals radii



Oxygen



The oxidation state of oxygen is −2 in almost all known compounds

Oxides of Oxygen & oxygen molecules are found throughout the range of Organic & inorganic compounds

All molecules seek KEM'ical charge and energy equilibrium

Geometric Molecular Topology is the overall arrangement of the atoms in a molecule, where the bonded atoms in a molecule are responsible for determining the final molecular topology of a chemical system of bonded elements.

As the numbers of atoms in molecules increases, the quantum molecular topology of a system grows increasingly complex and can only be modelled accurately using Tetryonic charged geometries

by bonding together and forming larger complex molecules

Common nitrogen functional groups include: amines, amides, nitro groups, imines, and enamines.

Compounds of Carbon form the 'backbones' of Organic & inorganic compounds

Molecular Octets

The concept of the Expanded Octet occurs in any system that has an atom with more than four electron pairs attached to it.

Most commonly, atoms will expand their octets to contain a total of five or six electron pairs, in total. In theory, it is possible to expand beyond those number.

The large amounts of negative charge concentrated in small volumes of space prevent those larger expanded octets from forming.

When an atom expands its octet, it does so by making use of empty d-orbitals that are available in the valence level of the atom doing the expanding.

The atom that expands its octet in a structure will usually be located in the center of the structure and the system will not use any multiple bonds in attaching atoms to the central atom.



Nitrogen



Carbon

48
[24-24]

Hydrogen bonds

H

96
[48-48]

1 Proton
1 electron


48
[24-24]
Hydrogen
H
H
Hydrogen
48
[24-24]


84
[42-42]
D
1
Deuterium
Deuterium
2
84
[42-42]



168
[84-84]

2 Protons
2 Neutrons
2 electrons

Hydrogen is a 'free radical' atom

H2 has a smaller s-orbital [lower energy level] compared to Helium

Deuterium is the building block of elements


H
+
H
e-
P+
+
+
Hydrogen
atom
e-
P+
+
+
Hydrogen
atom

Hydrogen atoms
→
form Covalent bonds


H_2
up
down
di-atomic
Hydrogen

Hydrogen, bound mostly to carbon and nitrogen, is part of almost every molecule in your body: DNA, proteins, sugars, fats.
Hydrogen bonds - which form between atoms that "share" a hydrogen atom, is one of the most important interactions that makes biological molecules behave as they do.


0
[48-48]
0
[24-24]
H
H
0
[24-24]
2 Protons
2 electrons

Hydrogen bonds are sigma bonds



note: n2 energy level Hydrogen is illustrative only
[Hydrogen bonds can be of any energy level]


0
[24-24]
0
[48-48]
H
H
2 Protons
2 electrons
0
[24-24]

The charged fascia of Baryonic quarks facilitates chemical [hydrogen] bonding in molecules

Copyright ABRAHAM [2008] - All rights reserved

Carbon Compounds

504

[252-252]

Carbon can bond in four places, and it can bond to itself so it's easy to make lots of different molecules.


CO
504
[252-252]
1,176
[588-588]
672
[336-336]
C
O

Carbon Monoxide Molecule


504
C
284,760
14,688

[He]$_2$ 2s2 2p2

Many carbon compounds are essential for life as we know it.
Some of the most common carbon compounds are: carbon dioxide (CO2), carbon monoxide (CO), carbon disulfide (CS2), chloroform (CHCl3), carbon tetrachloride (CCl4), methane (CH4), ethylene (C2H4), acetylene (C2H2), benzene (C6H6), ethyl alcohol (C2H5OH) and acetic acid (CH3COOH) to name just a few.

Acetylene Molecule


C2H2
504
[252-252]
504
[252-252]
48
[24-24]
48
[24-24]
1,104
[552-552]
C
C
H
H


CO2
1,848
[924-924]
672
[336-336]
504
[252-252]
672
[336-336]
C
O
O

Carbon dioxide Molecule

C

There are nearly ten million known carbon compounds and an entire branch of chemistry, known as organic chemistry, is devoted to their study.

Nitrogen Compounds


588
[294-294]
N
672
[336-336]
NO
1,260
[630-630]
588
[294-294]
48
[24-24]
48
[24-24]
684
[342-342]
H
588
[294-294]
NH3
48
[24-24]
588
N
333.444
18,360
[He] 2s2 2p3
2
672
[336-336]
588
[294-294]
N2O
1,848
[924-924]
588
[294-294]
672
[336-336]
588
[294-294]
672
[336-336]
NO2
1,932
[966-966]
O
N

Nitrogen is a component of many biological molecules including proteins, lipids, nucleic acids, and carbohydrates. Nitrogen is so important that a shortage of nitrogen will inhibit the growth of an organism.

Oxygen Compounds

672
[336-336]

O


H2O
48
[24-24]
768
[384-384]
672
[336-336]
48
[24-24]
672
[336-336]
O2
1,504
[252-252]
672
[336-336]
672
[336-336]
672
O
382,128
22,032
SO2
672
[336-336]
2,688
[1,344-1,344]
1,344
[672-672]
672
[336-336]
O3
672
[336-335]
2,016
[1,008-1,008]
672
[336-336]
672
[336-336]

$[He]_2$ 2s2 2p4

Oxygen forms oxide compounds with almost all of the known elements

As soon as the oxygen enters your blood, a passing protein molecule called hemoglobin picks it up. Each molecule of hemoglobin can transport four molecules of oxygen to almost anywhere in the body.

The hemoglobin transport the oxygen to your cells where another protein, called cytochrome C oxidase makes two molecules of water out of every molecules of oxygen delivered to it


H2
hydrogen
48
[24-24]
48
[24-24]
96
[48-48]
NH3
ammonia
48
[24-24]
48
[24-24]
780
[390-390]
48
[24-24]
588
[294-294]
48
[24-24]
804
[402-402]
756
[378-378]
48
[24-24]
HF
hydrogen fluoride
HCN
hydrogen cyanide
504
[252-252]
48
[24-24]
588
[294-294]
1,140
[570-570]
CH4
methane
48
[24-24]
48
[24-24]
696
[348-348]
48
[24-24]
504
[252-252]
48
[24-24]
672
[336-336]
1,344
[672-672]
O2
oxygen
672
[336-336]
HCl
hydrogen chloride
1,476
[738-738]
1,428
[714-714]
48
[24-24]
756
[378-378]
420
[210-210]
CO2
carbon dioxide
672
[336-336]
1,848
[924-924]
504
[252-252]
672
[336-336]
H2S
hydrogen sulfide
48
[24-24]
1,344
[672-672]
48
[24-24]
1,440
[720-720]
BF3
boron trifluoride
2,688
[1,344-1,344]
756
[378-378]
756
[378-378]


252
[126-126]
Li
lithium
1,680
[840-840]
48
[24-24]
48
[24-24]
CaH2
calcium hydride
1,776
[888-888]
H2O2
hydrogen peroxide
672
[336-336]
48
[24-24]
1,440
[720-720]
48
[24-24]
672
[336-336]
252
[126-126]
48
[24-24]
LiH
lithium hydride
300
[150-150]
756
[378-378]
1,428
[714-714]
ClF3
chlorine trifluoride
756
[378-378]
756
[378-378]
3,696
[1,848-1,848]
CaC2
calcium carbide
3,696
[1,848-1,848]
1,680
[840-840]
504
[252-252]
504
[252-252]
756
[378-378]
HF2
48
[24-24]
756
[378-378]
1,560
[780-780]
48
[24-24]
672
[336-336]
1,644
[822-822]
924
[462-462]
NaOH
sodium hydroxide
HCl
hydrogen chloride
48
[24-24]
1,428
[714-714]
1,476
[738-738]
48
[24-24]
2,316
[1,158-1,158]
KOH
potassium hydroxide
672
[336-336]
1,596
[798-798]


504
[252-252]
C
12.6493
284,760
14,688

Chemistry

is a branch of physical science, concerning the study of the composition, properties and behavior of Matter

Compounds containing bonds between carbon and a metal are called organometallic compounds.


504
[254-254]
C
11.996
270,072
Ground energy level

Inorganic compounds are produced by non-living natural processes or in the laboratory.



Inorganic compounds can form salts.



Inorganic compounds contain metal atoms.


Schrodinger's quantum numbers
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
atomic shells
Q
[v-v]
RE
2
8
18
32
Z
32
18
8
2
M0
KE
8
7
6
5
4
3
2
1
energy levels
f
d
p
C4
p
d
f
Bohr's atomic orbitals

Organic compounds are produced by living things.

Organic compounds can't form salts.



Organic compounds contain carbon-hydrogen bonds.


504
[254-254]
C
11.996
Cl2
270,072
Ground energy level

Tetryonic theory unifies and expands upon the currently disjointed physical and chemical theories through the application of 2D equilateral charged mass-energy geometries in 3D standing-wave mass-Matter topologies



Inorganic **Typically the difference is defined as being whether or not a substance contains carbon or carbon-hydrogen bonds** **Organic**

A chemical compound is a collection of elements bonded together in a way that the resultant ions, atoms or molecules form a 3D material geometric structure. Tetryonic chemical geometries, along with its firm definition and distinction between EM mass & Matter provide a clear visual path for the differentiation between both brankes of modern chemistry - as well as the source of animation in living Matter

Copyright ABRAHAM [2008] - All rights reserved

Functional Groups

A functional group is a reactive portion of a molecule.

carbonyl group





hydroxyl group

Organic molecules containing a hydroxyl group are known as alcohols.

carboxyl group



The combinations of functional groups with hydrocarbons produce a vast number of compounds.

Carbon monoxide



CO

carbonyl group is composed of a carbon atom double-bonded to an oxygen atom



HNO_3

Nitric acid

Carbonic acid



H_2CO_3

The carboxyl group is present in amino acids and carboxylic acids.

Derivatives of Hydrocarbons

An almost unlimited number of carbon compounds can be formed by the addition of a functional group to a hydrocarbon

Esters



Most esters have pleasant odors.
Esters are responsible for the fragrances of many flowers & the tastes of ripened fruits.



Ethers

The best known ether is diethyl ether.
It is a volatile, highly flammable liquid that was used as an anesthetic in the past.



Alkyl Halides - haloalkanes

Common alkyl halides include medical anesthetics, chlorofluorocarbons (CFCs), hydrochlorofluorocarbons (HCFCs) and hydrofluorocarbons (HFCs).



Carboxylic Acids

The simplest of the carboxylic acids is formic acid and is a constituent of bee stings and the bites of other insects including mosquitos.



Alcohols

Alcohols are organic compounds containing a hydroxyl group, [OH], substituted for a hydrogen atom.
Ethanol is the alcohol in alcoholic beverages and it is also widely used as a solvent.

H

hydro



Aldehydes

An aldehyde is a compound containing a carbonyl group with at least one hydrogen attached to it.
With a Hydrogen in place of the R group it forms Formaldehyde

C

carbons



Ketones

Acetone is the simplest of the ketones.
Acetone is a commonly used solvent and is the active ingredient in nail polish remover and some paint thinners.



Amines

Amines are organic compounds that contain nitrogen, they are basic compounds with strong odors, often described as "fishy"

"R's" stand for carbon substituents or hydrogen atoms.



Amides

Amides are nitrogen-containing organic compounds and are formed when amino acids react to form proteins.

Hydrocarbons

In organic chemistry, a methylene group is any part of a molecule that consists of two hydrogen atoms bound to a carbon atom, which is connected to the remainder of the molecule


600
[300-300]
48
[24-24]
2π4
504
[252-252]
2π3
48
[24-24]

CH2
Methylene

The methylene group should be distinguished from the free methylene radical, also called carbene, whose molecule is a methylene group all by itself.

H2C
Carbene


2π5
48
[24-24]
504
[252-252]
2π6
48
[24-24]
600
[300-300]


504
[252-252]
48
[24-24]
48
[24-24]
696
[348-348]
48
[24-24]
48
[24-24]

CH4
Methane


48
[24-24]
48
[24-24]
1,200
[600-600]
504
[252-252]
48
[24-24]
504
[252-252]
48
[24-24]

CH2-CH2
Ethylene

CH3-CH3
Ethane
C2H6


48
[24-24]
48
[24-24]
504
[252-252]
1,296
[648-648]
48
[24-24]
48
[24-24]
504
[252-252]
48
[24-24]
48
[24-24]

2

3


48
[24-24]
2,304
[1,152-1,152]
504
[252-252]
48
[24-24]
48
[24-24]
504
[252-252]
48
[24-24]
504
[252-252]
48
[24-24]
504
[252-252]
48
[24-24]

CH2-(CH)2-CH2
Butadine
C4H6

CH3-(CH2)-CH3
Propane
C3H8


48
[24-24]
48
[24-24]
48
[24-24]
504
[252-252]
48
[24-24]
504
[252-252]
48
[24-24]
504
[252-252]
2,404
[1,202-1,202]
48
[24-24]
48
[24-24]


2,496
[1,248-1,248]
48 [24-24]
48 [24-24]
48 [24-24]
48 [24-24]
48 [24-24]
504 [252-252]
48 [24-24]
504 [252-252]
48 [24-24]
504 [252-252]
48 [24-24]
48 [24-24]
504 [252-252]
48 [24-24]
C
C
C
C

CH3-(CH2)2-CH3

Butane

C4H10

4

Butane, also called n-butane,
is the unbranched alkane
with four carbon atoms,
CH3- [CH2]n -CH3.

Butane is also used as a collective
term for n-butane together
with its only other isomer, isobutane
(also called methylpropane), CH(CH3)3.

Butanes are highly flammable, colorless,
odorless, easily liquefied gases.


3,096
[1,548-1,548]
48 [24-24]
48 [24-24]
48 [24-24]
504 [252-252]
48 [24-24]
48 [24-24]
48 [24-24]
504 [252-252]
48 [24-24]
48 [24-24]
504 [252-252]
48 [24-24]
504 [252-252]
504 [252-252]
48 [24-24]
48 [24-24]
C
C
C
C
C

CH3-(CH2)3-CH3

Pentane

C5H12

5


48 [24-24]
48 [24-24]
48 [24-24]
504 [252-252]
48 [24-24]
48 [24-24]
48 [24-24]
504 [252-252]
48 [24-24]
504 [252-252]
48 [24-24]
504 [252-252]
48 [24-24]
504 [252-252]
48 [24-24]
504 [252-252]
48 [24-24]
48 [24-24]
3,696
[1,848-1,848]
C
C
C
C
C
C

CH3-(CH2)4-CH3

Hexane

C6H14

6


7
CH3-(CH2)5-CH3
Heptane
C7H16
4,296
[2,148-2,148]
48
[24-24]
504
[252-252]
8
CH3-(CH2)6-CH3
Octane
C8H16
4,896
[2,448-2,448]
1
2
C

Just like periodic elements,
compounds can form
allotropic compound structures


$(C_3H_6)_2$
cyclopropene
3,600
[1,800-1,800]
C_6-H_{12}
Cyclohexane
C_6H_{12}
C6
3,600
[1,800-1800]
3,600
[1,800-1,800]
CH_3-$(CH)_n$-CH_3
Hexene polymer chain backbone
1
2
3
4
5
6
48
[24-24]
504
[252-252]
H
C

Long chains of [CH] compounds form Poylmer chains
hydrocarbons, aeromatic oils, fuels, plastics etc.

Rings of atoms are also common in organic structures. You may have heard the famous story of Auguste Kekulé first realizing that benzene has a ring structure when he dreamt of snakes biting their own tails.



Carbon ring

Friedrich August Kekul

(7 September 1829 - 13 July 1896)



Organic Chemistry

In 1865, August Kekulé presented a paper at the Académie des Sciences in Paris suggesting a cyclic structure for benzene, the inspiration for which he ascribed to a dream. However, was Kekulé the first to suggest that benzene was cyclic. Some credit an Austrian schoolteacher, Josef Loschmidt with the first depiction of cyclic benzene structures.

In 1861, 4 years before Kekulé's dream, Loschmidt published a book in which he represented benzene as a set of rings. It is not certain whether Loschmidt or Kekulé—or even a Scot named Archibald Couper—got it right first

Some non-benzene-based compounds called heteroarenes, which follow Hückel's rule, are also aromatic compounds. In these compounds, at least one carbon atom is replaced by one of the heteroatoms oxygen, nitrogen, or sulfur.



Carbon-Nitrogen ring



Carbon-Oxygen ring

Copyright ABRAHAM [2008] - All rights reserved

Benzene molecules

Benzene, or benzol, is an organic chemical compound and a known carcinogen with the molecular formula C6H6.

It is sometimes abbreviated Ph–H.
Benzene is a colorless and highly flammable liquid with a sweet smell and a relatively high melting point.

Because it is a known carcinogen, its use as an additive in gasoline is now limited, but it is an important industrial solvent and precursor in the production of drugs, plastics, synthetic rubber, and dyes. Benzene is a natural constituent of crude oil, and may be synthesized from other compounds present in petroleum.

Benzene is an aromatic hydrocarbon and the second [n]-annulene ([6]-annulene), a cyclic hydrocarbon with a continuous pi bond.

Cyclic hydrocarbon compounds are often referred to as Aromatic compounds due to their sweet smell


504
[252-252]
504
[252-252]
504
[252-252]
504
[252-252]
504
[252-252]
504
[252-252]
C6H6

3,312
[1,656-1,656]

(CH)6
Benzene ring
C6H6


48
[24-24]
48
[24-24]
48
[24-24]
48
[24-24]
48
[24-24]
48
[24-24]
504
[252-252]
504
[252-252]
504
[252-252]
504
[252-252]
504
[252-252]
504
[252-252]
+
-
1
2
C

C6H6
Polymer chain backbone

Functional goups quickly interact with vacant bonding positions in (CH)n chains to form hydrocarbon compounds

A aromatic hydrocarbon is formed when CH compounds form a cyclic molecule

Many important additional chemical compounds are derived from benzene by replacing one or more of its hydrogen atoms with another functional group.

Examples of simple benzene derivatives are phenol, toluene, and aniline, abbreviated PhOH, PhMe, and PhNH2, respectively

Linear (CH)n chains are rarely found in nature as the Positive and Negative tail ends of Hydrocarbon chain interact and bond to form cyclic compounds.

Carbon-Nitrogen Chains


CN
Carbon-Nitrogen
chain backbone
1
2
3
4
5
6
-
+
504
[252-252]
504
[252-252]
504
[252-252]
504
[252-252]
504
[252-252]
588
[294-294]
Carbon
504
[252-252]
Hydrogen
48
[24-24]
48
[24-24]
Nitrogen
588
[294-294]
Oxygen
672
[336-336]
C5N
588
[294-294]
504
[252-252]
504
[252-252]
504
[252-252]
504
[252-252]
504
[252-252]

3,108
[1,554-1,554]

37 Protons
37 electrons
37 Neutrons


48
[24-24]
H
48
[24-24]
H

Hydrogen

Carbon-Oxygen Chains


1
2
3
4
5
6
C
O
C5O


672
[336-336]
O

Oxygen

Heterocyclic Rings

Tetrahydropyran is the organic compound consisting of a saturated six-membered ring containing five carbon atoms and one oxygen atom.

Carbon


C
504
[252-252]

3,192
[1,596-1,596]


672
[336-336]
504
[252-252]
504
[252-252]
504
[252-252]
504
[252-252]
504
[252-252]
6
1
2
3
4
5
C5O

38 Protons
38 electrons
38 Neutrons

Nitrogen


N
588
[294-294]

C6H2(NO2)3CH3
Trinitrotoluene


NO2
1,932
672
[336-336]
672
[336-336]
CH3
648
48
[24-24]
504
[252-252]
48
[24-24]
48
[24-24]
588
[294-294]
588
[294-294]
672
[336-336]
NO2
1,932
672
[336-336]
C6H2
48
[24-24]
3,120
48
[24-24]
588
[294-294]
672
[336-336]
NO2
1,932
672
[336-336]

2,4,6-trinitrotoluene is better known by its initials, TNT.
It is an important explosive, since it can very quickly
change from a solid into hot expanding gases.

TNT is explosive for two reasons;

First, it contains the elements carbon, oxygen and nitrogen, which means that when the material burns it produces highly stable substances (CO, CO2 and N2) with strong bonds, so releasing a great deal of energy.

Secondly, TNT is chemically unstable - the nitro groups are so closely packed that they experience a great deal of strain and hindrance to movement from their neighbouring groups.

Thus it doesn't take much of an initiating force to break some of the strained bonds, and the molecule then flies apart.

Because TNT melts at 82° C (178° F) and does not explode below 240° C (464° F), it can be melted in steam-heated vessels and poured into casings.

It is relatively insensitive to shock and cannot be exploded without a detonator.

For these reasons it is the most favoured chemical explosive, extensively used in munitions and for demolitions.

Trinitrotoluene, or more specifically, 2,4,6-trinitrotoluene,
is a chemical compound with the formula C6H2(NO2)3CH3

9,564
[4,782-4,782]

Copyright ABRAHAM [2008] - All rights reserved

(C6)4-H10

Pyrene


48
[24-24]
48
[24-24]
3,024
[1,512-1,512]
C6
48
[24-24]
48
[24-24]
3,024
[1,512-1,512]
48
[24-24]
C6
C6
48
[24-24]
3,024
[1,512-1,512]
48
[24-24]
48
[24-24]
C6
3,024
[1,512-1,512]
48
[24-24]
48
[24-24]
H



12,576
[6,288-6,288]

Pyrene highlights the failings of Lewis diagram structures

Which can be rectified using charged Tetryonic geometric Matter topologies for all elements and compound interactions & modelling

Pyrene is a polycyclic aromatic hydrocarbon (PAH) consisting of four fused benzene rings, resulting in a flat aromatic system.

Its chemcial formula as is often stated as C16H10, which tetryonic geometry shows is an error resulting from not using equilateral quantum geometries in chemical topology modelling.

Four cyclic carbon rings cannot be formed with only 16 C-atoms

Ammonium Nitrate

3,384

NH_4NO_3,

Ammonium nitrate is composed of two polyatomic ions:
1) Ammonium Ion (NH_4+)
2) Nitrate Ion (NO_3-)

The bond between these ions is an ionic bond meaning the ammonium ion transfers an electron to the nitrate ion.


672
[336-336]
588
[294-294]
672
[336-336]
-3
588
[294-294]
48
[24-24]
NO3
2,604
48
672
[336-336]
+4
NH4
780
48
[24-24]
48
[24-24]

The bonds in a polyatomic atomic ion are covalent because they take place between gases.

This means that the hydrogens of the ammonium ion are bonded to the nitrogen covalently and that the oxygens of the nitrate are bonded to the nitrogen covalently

Ammonium nitrate decomposes into the gases nitrous oxide and water vapor when heated (non-explosive reaction); however, ammonium nitrate can be induced to decompose explosively by detonation.


H2O
768
672
[336-336]
48
[24-24]
48
[24-24]

+


N2O
1,848
588
[294-294]
672
[336-336]

+


H2O
768
48
[24-24]
672
[336-336]
48
[24-24]


504
[252-252]
48
[24-24]
CH
552
OH
720
48
[24-24]
672
[336-336]

Carbohydrates

A carbohydrate is an organic compound that consists only of carbon, hydrogen, and oxygen (with a hydrogen:oxygen ratio of 2:1) in other words, with the empirical formula Cm(H2O)*n*



Ribose

Monosaccharides

Gluclose

Disaccharides

Lactose

$$\boxed{C_m(H_2O)_n}$$

Oligosaccharides

Polysaccharides

Fructose

Sucrose

Deoxyribose


1
2
3
4
5
6
C6-H22-O11
sucrose

Carbohydrates perform numerous roles in living organisms.
Polysaccharides serve for the storage of energy (e.g., starch and glycogen),
and as structural components (e.g., cellulose in plants and chitin in arthropods)

Copyright ABRAHAM [2008] - All rights reserved

Monosaccharides

Monosaccharides are the simplest carbohydrates in that they cannot be hydrolyzed to smaller carbohydrates

The Carbon nuclei in Monosaccharides join together to form chains of biologically important carbohydrates

1,272

[636-636]


504
[252-252]
48
[24-24]
CH
552
OH
720
48
[24-24]
672
[336-336]

$C(H_2O)$

The general chemical formula of an unmodified monosaccharide is $(C\cdot H_2O)$ n, literally a "carbon hydrate."

CH 552 **CH-OH** OH 720


O
H
H
OH
HO
H
H
OH
H
OH
CH₂OH

D-Glucose


O
H
HO
H
H
OH
HO
H
HO
H
CH₂OH

L-Glucose


O
672
CH
552
OH
720
1
2
CH
552
OH
720
3
CH
552
OH
720
OH
720
4
CH
552
OH
720
5
CH
552
OH
720
OH
720
6
CH2
600

$C(H_2O)_6$

D-glucose

C_6-H_{12}-O_6


CH
552
O
672
1
2
CH
552
OH
720
OH
720
3
CH
552
4
CH
552
OH
720
OH
720
5
CH
552
6
CH
552
OH
720
CH2
600

$C(H_2O)_6$

L-glucose

C_6-H_{12}-O_6


CH
552
O
672
1
2
3
4
5
CH2
600

C(H2O)5
ribose
C5-H10-O5

C(H2O)n


CH
552
OH
720


CH2
600
O
672
1
2
3
4
5
6
CH2
600

C(H2O)6
fructose
C6-H12-O6

Major Monosaccharides



ribose



fructose



mannose



glucose

D D & L sugars are chiral, mirror images of one another and have the same name. **L**


CH
552
O
672
1
2
3
4
5
6
CH2
600

C(H2O)6
mannose
C6-H12-O6


OH
720
CH
552


O
672
CH
552
1
2
3
4
5
6
CH2
600

C(H2O)6
glucose
C6-H12-O6

A monosaccharide often switches from the acyclic (open-chain) form to a cyclic form, through a nucleophilic addition reaction between the carbonyl group and one of the hydroxyls of the same molecule.

cyclic monosaccharides

For many monosaccharides (including glucose), the cyclic forms predominate, and therefore the same name commonly is used for forms of isomers.

C(H2O)6
glucose
C6-H12-O6


H
C
O
H—C—OH
HO—C—H
H—C—OH
H—C—O
H
CH2OH
CH2OH
C
O
H
H
C
H
C
HO
OH
H
C
OH
C
C
H
OH

C(H2O)6
glucopyranose
C6-H12-O6


O
672
+
CH
552
1
OH
720
2
CH
552
3
CH
552
OH
720
OH
720
4
CH
552
5
CH
552
OH
720
OH
720
6
CH2
600
-

linear saccharide chain

The Carbon nuclei in Monosaccharides chains can join together to form cyclic [Carbon-Oxygen] rings or polycarbohydrates through condensation

C6-H12-O6
7,632
[3,816-3,816]

The reaction creates a ring of carbon atoms closed by one bridging oxygen atom, which in turn can be easily broken to restore the linear monosaccharide chains

cyclic Oxygen-Carbon ring

Allotropic cyclic [Carbon-Oxygen] forms of polycarbohydrates can also be formed via other element bonding processes


OH
720
CH2
600
OH
720
C
504
CH
552
5
6
4
C50
1
OH
720
OH
720
3
2
CH
552
CH
552
CH
552
OH
720
OH
720

acyclic monosaccharides

Condensed Disaccharides

Condensed Disaccharides are formed when two monosaccharides are joined together and a molecule of water is removed

For example, milk sugar (lactose) is made from glucose and galactose
whereas cane sugar (sucrose) is made from glucose and fructose



CH-OH
1,272

monosaccharide

+

monosaccharide



CH-OH
1,272

2,544
[1,272-1,272]



Disaccharides & condensed disaccharides
can bond together and form cyclic
polysaccharides

simple disaccharide

condensed
disaccharide



C2H2O
1,776

[CH2O]12 - [H2O]

H2O
768



water molecule

The reverse of this reaction, the formation of two monosaccharides from one disaccharide, is called a hydrolysis reaction and requires one water molecule to supply the H and OH to the sugars formed.

Sucrose is used in many plants for transporting food reserves, often from the leaves to other parts of the plant.
Lactose is the sugar found in the milk of mammals and maltose is the first product of starch digestion
and is further broken down to glucose before absorption in the human gut.

14,496

[7,248-7,248]

Disaccharides

Disaccharides are one of the four basic categories of carbohydrates,
(the others are monosaccharides, oligosaccharides, and polysaccharides)

Monosaccharides, such as glucose, are the monomers out of which disaccharides are constructed.

C12-(H2O)11

Disaccharides & condensed disaccharides can bond together and form cyclic polysaccharides


C(H2O)6
fructose
C6-H12-O6
CH2
600
O
672
1
2
3
4
5
6
CH2
600
H2O
O
672
+
CH
552
1
2
3
4
5
6
C(H2O)6
glucose
C6-H12-O6
CH2
600

sucrose
C12-H22-O11


O
672
CH
552
C(H2O)6
galactose
C6-H12-O6
1
2
3
4
5
6
CH2
600
H2O
O
672
+
CH
552
1
2
3
4
5
6
C(H2O)6
glucose
C6-H12-O6
CH2
600

lactose
C12-H22-O11


O
672
CH
552
1
2
3
4
5
6
C(H2O)6
glucose
C6-H12-O6
CH2
600
H2O
O
672
+
CH
552
1
2
3
4
5
6
C(H2O)6
glucose
C6-H12-O6
CH2
600

maltose
C12-H22-O11

The general chemical formula for carbohydrates, C(H2O),
gives the relative proportions of carbon, hydrogen, and oxygen in a monosaccharide
(the proportion of these atoms are 1:2:1)-(H2O)

Copyright ABRAHAM [2008] - All rights reserved


C(H2O)6
glucose
C6-H12-O6
Glycosidic
bond
C(H2O)6
fructose
C6-H12-O6
C(H2O)6
glucose
C6-H12-O6
Glycosidic
bond
C(H2O)6
fructose
C6-H12-O6
6 5 4 3 2 1 6 5 4 3 2 1
6 5 4 3 2 1 6 5 4 3 2 1
C12-H22-O11
sucrose
+
H2O
Glycosidic
bond
(C24-H42-O21)
saccharose
+
H2O
C12-H22-O11
sucrose
+
H2O

Oligosaccharides

any carbohydrate of from three to six units of simple sugars (monosaccharides).

The nuclei that form Monosaccharides chains
can also join to form cyclic Carbohydrates
[Polysaccharides]


C(H2O)6
glucose
C6-H12-O6
H2O
C(H2O)6
fructose
C6-H12-O6
H2O
C(H2O)6
glucose
C6-H12-O6
H2O
C(H2O)6
fructose
C6-H12-O6
C12-H22-O11
sucrose
5 6 4 C5O 1 3 2
Glycosidic
bond
5 6 4 C5O 1 3 2
Glycosidic
bond
5 6 4 C5O 1 3 2
Glycosidic
bond
5 6 4 C5O 1 3 2
C12-H22-O11
sucrose

An oligosaccharide is a saccharide polymer containing a small number (typically two to ten) component sugars (monosaccharides). Oligosaccharides can have many functions; for example, they are commonly found on the plasma membrane of animal cells where they can play a role in cell–cell recognition.

Starch or amylum is a carbohydrate consisting of a large number of glucose units joined by glycosidic bonds. This polysaccharide is produced by most green plants as an energy store.


C(H2O)6
glucose
C6-H12-O6
C(H2O)6
glucose
C6-H12-O6
C(H2O)6
glucose
C6-H12-O6
C(H2O)6
glucose
C6-H12-O6
O 672
CH2 600
CH 552
6
5
4
3
2
1
+
-
Glycosidic bond
H2O

C6-H10-O5

6,864 n

[3,432-3,432]

Polysaccharides

Polysaccharides have a general formula of Cx(H2O)y where x is usually a large number between 200 and 2500.

$C_x[H2O]_y$

The repeating units in a Polysaccharide polymer backbone are often six-carbon monosaccharides, their general formula can be represented as (C6-H10-O5)n

Polysaccharides are generally comprised of chains of cyclic monosaccharides


H2O
Glycosidic bond
C5O
1
2
3
4
5
6

Cellulose is an organic compound with the formula (C6H10O5)n, a polysaccharide consisting of a linear chain of several hundred to over ten thousand linked D-glucose sugars.

Amines



Amines are organic compounds that contain Nitrogen

NH2-[HC-R]-COOH + NH2-[HC-R]-COOH

As both the amine and carboxylic acid groups of amino acids can react to form amide bonds, one amino acid molecule can react with another and become joined through an amide linkage. This polymerization of amino acids is what creates proteins.

OH + NH2 -----> NH + H2O

This yields a peptide bond and a molecule of water via a condensation reaction

Carboxylic Acids



The general formula of a carboxylic acid is R-COOH

Amino Acids

Amino acids are biologically important organic compounds made from amine and carboxylic acid functional groups, along with a side-chain specific to each amino acid



un-ionized amino acid

NH2-[HC-R]-COOH



zwitterionic amino acid

NH3-[HC-R]-COO

The α-carbon.

The α-amino acids in peptides and proteins consist of a carboxylic acid (-COOH) and an amino (-NH2) functional group attached to the same tetrahedral carbon atom







The peptide group attached to the alpha carbon distinguishes one amino acid from another (Tetryonic theory defines these compound side-chains of atoms as peptides [p])

Copyright ABRAHAM [2008] - All rights reserved



Peptide side chains

Amino acids are the structural units (monomers) that join together
to form short polymer chains called peptides;
or longer chains called either polypeptides or proteins

A A A
A A G
A A C
A A U
A G A
A G G
A G C
A G U
A C A
A C G
A C C
A C U
A U A
A U G
A U C
A U U

A
$C_5\text{-}H_5\text{-}N_5$
Adenine

C
$C_4\text{-}H_5\text{-}N_3\text{-}O$
Cytosine

C A A
C A G
C A C
C A U
C G A
C G G
C G C
C G U
C C A
C C G
C C C
C C U
C U A
C U G
C U C
C U U

3,180
Gly
$C_2H_5NO_2$

3,780
Ala
$C_3H_7NO_2$

4,452
Ser
$C_3H_7NO_3$

4,884
Pro
$C_5H_9NO_2$

4,980
Val
$C_5H_{11}NO_2$

5,052
Thr
$C_4H_9NO_3$

5,124
Cys
$C_3H_7NO_2S$

5,580
Lle
$C_6H_{13}NO_2$

5,580
Leu
$C_6H_{13}NO_2$

5,592
Asn
$C_4H_8N_2O_3$

5,628
Asp
$C_4H_7NO_4$

p
peptide side chain

current chemical theory
hypothesizes that all
peptides and proteins
are the result of codon
triplet side chains
on amino acids

Tetryonic theory reveals
serious flaws in this line
of thought

6,192
Gln
$C_5H_{10}N_2O_3$

6,216
Lys
$C_6H_{14}N_2O_2$

6,228
Glu
$C_5H_9NO_4$

6,324
Met
$C_5H_{11}NO_2S$

6,564
His
$C_6H_9N_3O_2$

6,996
Phe
$C_9H_{11}NO_2$

7,392
Arg
$C_6H_{14}N_4O_2$

7,668
Tyr
$C_9H_{11}NO_3$

8,640
Trp
$C_{11}H_{12}N_2O_2$

G A A
G A G
G A C
G A U
G G A
G G G
G G C
G G U
G C A
G C G
G C C
G C U
G U A
G U G
G U C
G U U

G
$C_5\text{-}H_5\text{-}N_5\text{-}O$
Guanine

U
$C_4\text{-}H_4\text{-}N_2\text{-}O_2$
Uracil

U A A
U A G
U A C
U A U
U G A
U G G
U G C
U G U
U C A
U C G
U C C
U C U
U U A
U U G
U U C
U U U

Tetryonics 59.10 - Peptide side chains.jpg

Copyright ABRAHAM [2008] - All rights reserved

GGU
GGC
GGA
GGG

3,180
Gly
C2H5NO2


O
OH
C
NH2
HCH

Glycine
HO2CCH2(NH2)

HCH


amino acid
amino acid
amino acid
O
O
O
peptide bond
peptide bond
NH2
C
NH
C
NH
C
OH
HC
HC
HC
peptide
p
peptide
p
peptide
p

poly-peptide chains

GCU
GCC
GCA
GCG

3,780
Ala
C3H7NO2


O
OH
C
NH2
HC
CH3
CH3

Alanine
HO2CCH(NH2)CH3

UCU
UCC
UCA
UCG
AGU
AGC

4,452
Ser
C3H7NO3


O
OH
C
NH2
HC
CH2
OH
CH2OH

Serine
HO2CCH(NH2)CH2OH

CCU
CCC
CCA
CCG

4,884
Pro
C5H9NO2


O
OH
C
NH2
HC
CH2
CH2
CH2
(CH2)3

Proline
HO2CCH(NH)(CH2)3

GUU
GUC
GUA
GUG

4,980
Val
C5H11NO2


O
OH
C
NH2
HC
CH3
CH
CH3
CH(CH3)2

Valine
HO2CCH(NH2)CH(CH3)2


ACU
ACC
ACA
ACG
5,052
Thr
C4H9NO3
O
OH
C
NH2
HC
CH
OH
CH3
Threonine
HO2CCH(NH2)CH(OH)CH3
CH(OH)CH3


UGU
UGC
5,124
Cys
C3H7NO2S
O
OH
C
NH2
HC
Cysteine
HO2CCH(NH2)CH2SH
CH2
SH
CH2SH


AUU
AUC
AUA
5,580
Lle
C6H13NO2
O
OH
C
NH2
Isoleucine
HO2CCH(NH2)CH(CH3)CH2CH3
HC
CH3
CH
CH2
CH3
CH(CH3)CH2CH3


UUA
UUG
CUU
CUC
CUA
CUG
5,580
Leu
C6H13NO2
O
OH
C
NH2
HC
Leucine
HO2CCH(NH2)CH2CH(CH3)2
CH2
CH3
CH
CH3
CH2CH(CH3)2


AAU
AAC
5,592
Asn
C4H8N2O3
O
OH
C
NH2
HC
Asparagine
HO2CCH(NH2)CH2CO(NH2)
CH2
O
C
NH2
CH2CO(NH2)


GAU
GAC
5,628
Asp
C4H7NO4
O
OH
C
NH2
HC
Aspartate
HO2CCH(NH2)CH2COO
CH2
O
C
O
CH2COO

Copyright ABRAHAM [2008] - All rights reserved


6,192
Gln
C5H10N2O3
CAA
CAG
O
OH
C
NH2
HC
Glutamine
HO2CCH(NH2)(CH2)COHN2
CH2
CH2
O
C
NH2
(CH2)2CONH2
6,216
Lys
C6H14N2O2
AAA
AAG
O
OH
C
NH2
HC
Lysine
HO2CCH(NH2)(CH2)4NH2
CH2
CH2
CH2
CH2
NH2
(CH2)4NH2
6,228
Glu
C5H9NO4
GAA
GAG
O
OH
C
NH2
HC
Glutamate
HO2CCH(NH2)(CH2)2COO
CH2
CH2
O
C
O
(CH2)2COO
6,324
Met
C5H11NO2S
AUG
O
OH
C
NH2
HC
Methionine
HO2CCH(NH2)(CH2)2SCH3
CH2
CH2
S
CH3
(CH2)2SCH3
6,564
His
C6H9N3O2
CAU
CAC
O
OH
C
NH2
HC
Histidine
HO2CCH(NH2)CH2NH(CH2)2N
CH2
NH
CH
C
CH
N
CH2NH(CH2)2N


UUU
UUC
6,996
Phe
C9H11NO2
O
OH
C
NH2
HC
Phenylalanine
HO2CCH(NH2)CH2C6H5
CH2
CH2C6
C
CH
CH
CH
CH
CH
CGU
CGC
CGA
CGG
AGA
AGG
7,392
Arg
C6H14N4O2
O
OH
C
NH2
HC
Arginine
HO2CCH(NH2)(CH2)3C(NH2)2NH
(CH2)3C(NH2)2NH
CH2
CH2
CH2
NH2
C
NH2
NH
UAU
UAC
7,668
Tyr
C9H11NO3
O
OH
C
NH2
HC
Tyrosine
HO2CCH(NH2)CH2(C6)OH
CH2(C6)OH
CH2
C
C
C
C
OH
C
C
UGG
8,640
Trp
C11H12N2O2
O
OH
C
NH2
HC
Tryptophan
HO2CCH(NH2)CH2(C2NH)C6H5
CH2(C2NH)C6
CH2
C
NH
C
C
CH
CH
CH
CH
CH

Copyright ABRAHAM [2008] - All rights reserved


O
C
NH
amine
NH2
C
OH
carboxyl
+
amine
NH2
C
OH
carboxyl
HC
HC
p
peptide
H2O
H2O
H2O
O
NH2
C
NH
C
OH
HC
+
NH2
C
NH
C
OH
HC
+
NH2
C
NH
C
OH
HC

Peptide Bonds

The four-atom functional group -CONH- is called a peptide link.

Polypeptide chains of amino acids arre held together by peptide bonds

NH2-[HC-R]-COOH + NH2-[HC-R]-COOH

A peptide bond (amide bond) is a covalent chemical bond formed between two molecules when the amine group of one molecule reacts with the carboxyl group of the other molecule, causing the release of a molecule of water (H2O),

OH + NH2 ——> NH + H2O

OH + NH2 ——> NH + H2O

Tetryonics 59.15 - Peptide bonds

amino terminus
The beginning of a polypeptide protein molecule has a free amino group.





The four-atom functional group -CONH- is called a peptide link.

carboxy terminus
The end of a polypeptide protein molecule has a free carboxyl group.



Proteins [poly-peptides] are formed by joining the -CO2H [carboxyl] end of one amino acid with the -NH2 [amine] end of another to form an amide. The -CONH- bond between amino acids is known as a peptide bond because relatively short polymers of amino acids are known as peptides.

polypeptide chains

Proteins are formed when amino acids are covalently linked together.

DNA and RNA have a deoxyribose and ribose sugar backbone, respectively, whereas PNA's backbone is composed of repeating (2-aminoethyl)-glycine units linked by peptide bonds.

Proteins (polypeptides) are chains of amino acids held together by peptide bonds which form the backbone stringers of PNA, RNA & DNA.

Proteins


amino acid
amino acid
amino acid
amino acid
amino acid
amino acid
amino acid
amino acid
peptide bond
peptide bond
peptide bond
peptide bond
peptide bond
peptide bond
peptide bond
O
NH2
C
NH
HC
OH
p
peptide

There are 20 different nucleotide side chains present in biological molecules.

Lipids

hydrophyllic



hydrophobic



Lipids are a group of naturally occurring molecules that include fats, waxes, sterols, fat-soluble vitamins (such as vitamins A, D, E, and K), mono-glycerides, di-glycerides, tri-glycerides, phospho-lipids, and others.



hydrophobic



hydrophyllic

Lipids are molecules that contain hydrocarbons and make up the building blocks of membranes, providing a semi-permeable barrier between a living cell's internal & external enviroments.

Tetryonics 59.17 - Lipids

Copyright ABRAHAM [2008] - All rights reserved

Acetylcholine

is an organic molecule that acts as a neurotransmitter in many organisms, including humans. It is an ester of acetic acid and choline

Ach

$C_7H_{16}NO_2$

$CH_3COO(CH_2)_2N^+(CH_3)_3$

Lewis chemical structure


CH3
CH3
N
CH3
CH2
CH2
O
O
C
CH3





$$H_3C-\underset{\underset{O}{\|}}{C}-O-\underset{H_2}{C}-\underset{H_2}{C}-\overset{+}{N}(CH_3)_3$$

Tetryonic charge topology


CH3
CH3
N
CH3
CH2
CH2
O
C
O
CH3

6,228

Ribose

6,360

[3,180-3,180]

C5-H10-O5

Carbohydrate compounds can form acyclic sugars

Carbohydrate compounds can also form cyclic sugars

Ribose is an organic compound
with the formula C5H10O5; specifically,
a monosaccharide (simple sugar) with
linear form H–(C=O)–(CHOH)4–H

C(H2O)5
ribose
C5-H10-O5


H
48
C
504
O
672
1
CH
552
2
OH
720
OH
720
3
CH
552
CH
552
4
OH
720
OH
720
5
CH
552
H
48


CHO
H
C
H
H
C
OH
H
C
OH
CH₂OH

H-(CO)-(CHOH)4-H


HOCH₂
O
OH
C
C
H
H
H
H
C
C
OH
H

C(H2O)5
ribose
C5-H10-O5


OH
720
H
48
O
672
C
504
5
6
H
48
CH
552
4
+
C5O
1
−
CH
552
3
2
OH
720
CH
552
OH
720
CH
552
OH
720

Ribose forms part of the backbone of RNA.
It is related to deoxyribose, which is found in DNA.

**Ribose is present within every living cell of the body and is used to manufacture ATP (the energy currency of the cell) from scratch.
Whilst the body can manufacture its own ribose from glucose, this requires energy and is a very slow process.**

As its name indicates it is a deoxygenated sugar, meaning that it is derived from the sugar ribose by loss of an oxygen atom

Deoxyribose

5,688

[2,844-2,844]

As a component of DNA, 2-deoxyribose derivatives have an important role in biology

The DNA (deoxyribonucleic acid) molecule, which is the main repository of genetic information in life, consists of a long chain of deoxyribose-containing units called nucleotides, linked via phosphate groups


O
672
H
48
C
504
O
672
1
CH2
600
2
OH
720
CH
552
3
4
CH
552
OH
720
5
OH
720
CH
552
H
48


HOCH2
O
OH
C
C
H
H
H
H
C
C
OH
H

Deoxyribose, more, precisely 2-deoxyribose, is a monosaccharide


CHO
H
C
H
H
C
OH
H
C
OH
CH2OH

$C_5\text{-}H_{10}\text{-}O_4$
deoxyribose


OH
720
H
48
O
672
504
5
6
H
48
CH
552
4
+
C5O
1
−
CH
552
OH
720
3
2
CH
552
H
48
OH
720
CH
552
O
672

$C_5\text{-}H_{10}\text{-}O_4$
deoxyribose

$H\text{-}(CO)\text{-}(CH_2)\text{-}(CHOH)_3\text{-}H$

Hermann Emil Fischer won the Nobel Prize in Chemistry (1902) for his work in determining the structure of the D-aldohexoses.

However, the linear, free-aldehyde structures that Fischer proposed represent a very minor percentage of the forms that hexose sugars adopt in solution. It was Edmund Hirst and Clifford Purves, in the research group of Walter Haworth, who conclusively determined that the hexose sugars preferentially form a pyranose, or six-membered, ring. Haworth drew the ring as a flat hexagon with groups above and below the plane of the ring – the Haworth projection


1,260
P
Phosporus
741,996
66,816


3,996
[1,998-1,998]
OH
720
1
O
672
2
O
672
4
P
1,260
3
O
672
OH
720
H
48
O
672
+
C
504
5
6
H
48
C5-H10-O4
deoxyribose
CH
552
4
C5O
1
−
CH
552
3
2
OH
720
CH
552
H
48
OH
720
CH
552

HPO_4
phosphate
group



The other repeating part of the DNA backbone is a phosphate group. A phosphate group is attached to the sugar molecule in place of the -OH group on the 5' carbon.


P
deoxy
ribose
AGCT
nucleotide



5,688
[2,844-2,844]

Radioactive Decay

The Atom releases excess energies in various forms as it seeks a lower energy, state of equilibria with its surrounding EM energy environment

Energy in all its forms seeks equilibirium

Photons, Heat, Vibration & Kinetics can all raise the energy levels of atomic nuclei

The spectral line emissions of photons from bound electrons in addition to Alpha, Beta and Gamma Particle emissions from nuclei can release KEM energies over long time spans

E

scalar equilateral

mass-ENERGY-Matter

geometries

topologies

mc^2

Mc^4


7,728
[3,864-3,864]
U
231.8998
5,220,528
[3.850786032 e-25 kg]
1,079,424
[44.663 GeV]

unstable high energy nuclei


n
D+
12
[42-30]
N°
n5
P+
+ charge nuclei
α
e+
12
[12-0]
+ charge lepton
νe
0
[6-6]
e-


0
[n-n]
neutral charge Photons
γ
12
[0-12]
- charge lepton
Neutral leptons
β


7,392
[3,696-3,696]
Ra
221.1388
4,978,272
[3.673092226 e-25 kg]
1,017,216
[42.089 GeV]

stable core electron configurations

Copyright ABRAHAM [2008] - All rights reserved

Radio-Carbon isotope dating

Radiocarbon dating (sometimes simply known as carbon dating) is a radiometric dating method that uses the naturally occurring radioisotope carbon-14 (14C) to estimate the age of carbon-bearing materials up to about 58,000 to 62,000 years


6 protons
+ 6 neutrons
electron
proton
neutron
Carbon atom

Standing-wave KE not 'excess' Neutrons

It is the stored Kinetic Energies [KE] that increase the mass of Carbon12 to create its isotopes, historically these mass-energies have been mistakenly thought to be extra Neutrons in the nuclei

**C14 half-life
5730 ± 40**


504
[254-254]
14C
14.0181
6
5
1
C14
4
2
3
315,576
[2.327763802e-26 kg]
45,504
[1.882 GeV]
[2.0224 Neutrons]

*Carbon-14, 14C, or radiocarbon,
is a radioactive isotope of carbon
with a nucleus containing
6 protons, 6 neutrons and 6 electrons
with an excess energy content
of 1.88 GeV*

[6 Deuterium nuclei]

ALL elemental Carbon atoms have an atomic configuration of 6 protons, 6 neutrons and 6 electrons


504
[254-254]
13C
12.9850
6
5
1
C13
4
2
3
292,320
[2.15622002e-26 kg]
22,248
[920.5 MeV]
[.998 Neutrons]

*Carbon-13, 13C, is a weakly
radioactive isotope of carbon
with a nucleus containing
6 protons, 6 neutrons and 6 electrons
with an excess energy content
of 920 MeV*

Radio-Carbon dating can be used to determine the age of carbonaceous materials up to about 60,000 years old


Isotopic mass-charge quotient determines an element's properties
Q
RE
Net Charges create 3D Matter topologies
Stored KE contributes to isotopic mass
M
KE


504
[254-254]
12C
11.996
6
5
1
C12
4
2
3
270,072
[1.99211542le-26 kg]
Ground energy level

Tetryonic theory corrects historical errors of atomic geometries and nuclear energies


6 protons
6 neutrons
Carbon-12
(6P + 6N)
Atomic weight = 12
6 protons
7 neutrons
Carbon-13
(6P + 7N)
Atomic weight = 13
6 protons
8 neutrons
Carbon-14
(6P + 8N)
Atomic weight = 14

The stored KE [chemical] mass-energies of the Carbon 12+ isotopes comes from various radiological [and biological] processes and its steady, predictable release through the quantum mechanics of the synchronous convertors that make up Carbon nuclei make it useful in dating objects based on their decay rates

Radioactive Isotopes

Where the elementary nuclei's Deuteron energy levels are raised from their ground levels radioactive isotopes are created


R
Q
P
O
N
M
L
K
atomic shells
8
7
6
5
4
3
2
1
energy levels
Q
RE
M
KE
2
8
18
32
32
18
8
2
$T_{\mu\nu}$
c^4
f
d
p
s
p
d
f
+3
+2
+1
0
-1
-2
-3
orbitals

Each periodic element is comprised of an EQUAL number of Protons, Neutrons & electrons that form each element's unique 2D mass-energy geometries & 3D Matter topology and contribute to its observed properties

The $\frac{\text{mass}}{c^2}$ ~ $\frac{\text{energy}}{c^4}$ content of Matter

Einstein's relativistic stress energy tensor models mass-energy-Matter as a nebulous energy-momenta density-pressure gradient



Tetryonic theory redefines the relativistic stress energy tensor [$T_{\mu\nu}$] into a geometric measure of the charged 2D electromagnetic mass-energies & 3D Matter topologies within any spatial co-ordinate system

Nuclear Decay processes

is the set of processes by which an unstable atomic nucleus emits subatomic particles

Charged Matter equivalence

Neutrogen $\underset{[6\text{-}6]}{ve} + \underset{[18\text{-}18]}{N^0} \overset{[24\text{-}24]}{\sim} \underset{[24\text{-}12]}{P^+} + \underset{[0\text{-}12]}{e^-}$ **Hydrogen**





gamma rays

$\underset{[v\text{-}v]}{KE} \longrightarrow \underset{[n\text{-}n]}{\gamma}$

gamma ray production

Charge & mass-energy momenta are conservative physical properties

Radioactivity was discovered in 1896 by the French scientist Henri Becquerel, while working on phosphorescent materials. These materials glow in the dark after exposure to light, and he suspected that the glow produced in cathode ray tubes by X-rays might be associated with phosphorescence



alpha-particles

$\underset{[42\text{-}30]}{D^+} \; \underset{[42\text{-}30]}{D^+} \longrightarrow \underset{[84\text{-}60]}{He^{+2}}$

alpha particle production

E

Energy can be released from atomic nuclei through various processes

alpha-particles
beta-particles
gamma rays
spectral lines
heat & motion

positrons
neutrinos
electrons

beta-particles

m *All nuclear decay particles are determined by Tetryonic charge topologies* M

Charge Matter particle creation follows chemical equilibrium formulae

$\underset{[18\text{-}18]}{N^0} \longrightarrow \underset{[12\text{-}0]}{e^+} + \underset{[6\text{-}6]}{ve} + \underset{[0\text{-}12]}{e^-}$

Neutron decay processes

$\underset{[18\text{-}18]}{N^0} \longrightarrow \underset{[6\text{-}6]}{ve} + \underset{[6\text{-}6]}{ve} + \underset{[6\text{-}6]}{ve}$

3D Matter topologies are not conservative

Alpha radiation

(Deuteron emissions)


He^{+2}
alpha particle
large, unstable energetic nuclei
large stable nuclei

Alpha particles are released during alpha decay processes in ultra-heavy nuclei like uranium, thorium, actinium, and radium


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
8
18
32
32
18
8
2
Z

Beta radiation - Negative charge sets (Nuclei)
Gamma radiation - Neutral Charge sets (Photons)


24
[84-60]
90,000
He^{+2}

Helium nuclei creation

D^{+} D^{+}
[42-30] [42-30]
+
[0-12] [0-12]
e^{-} e^{-}
→ He^{0}
[84-84]

charged
alpha nuclei bond
&
capture electrons
to form neutral
Helium

alpha particles


12
[42-30]
D^{+}
45,000
α
α
Deuteron
Deuteron

The radioactive isotope Americium 241 emits alpha particles which are used in smoke detectors.


24
[84-60]
D
D
He
90,024

Due to their larger masses compared to beta and gamma particles, alpha particles can be easily stopped by a piece of paper or human skin.

Beta particle decay

$$\underset{[18\text{-}18]}{N^0} \longrightarrow \underset{[12\text{-}0]}{e^+} + \underset{[6\text{-}6]}{\nu e} + \underset{[0\text{-}12]}{e^-}$$

Neutron decay paths

$$\underset{[18\text{-}18]}{N^0} \longrightarrow \underset{[6\text{-}6]}{\nu e} + \underset{[6\text{-}6]}{\nu e} + \underset{[6\text{-}6]}{\nu e}$$

(the emission of leptons from atomic nuclei)

Beta decay


Carbon-14
β⁻
Nitrogen -14
beta-minus decay
6 protons
8 neutrons
7 protons
7 neutrons
+
anti-neutrino
+
electron
Carbon-10
β⁺
Boron-10
6 protons
4 neutrons
5 protons
5 neutrons
+
neutrino
+
positron
beta-plus decay

Charge is a conserved physical property of all material objects

$$\underset{[18\text{-}18]}{N^0} + \underset{[6\text{-}6]}{\nu e} \xrightarrow{[24\text{-}24]} \underset{[24\text{-}12]}{P^+} + \underset{[0\text{-}12]}{e^-}$$

Neutron decay is not a spontaneous process

All beta decay processes are the result of neutrino interaction with Neutrons


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
8
18
32
32
18
8
2
Z
β⁺
β⁻
β⁰


e⁺
[12-0]
12
12
Beta-particles
[6-6]
0
12
12
νe
e⁻
[0-12]
12
12

Alpha radiation - Positive charge particles (Nuclei)
Gamma radiation - Neutral charge quanta (Photons)

Gamma Radiation

(high energy photon emission)

Natural sources of gamma rays on Earth include gamma decay from naturally occurring radioisotopes, and secondary radiation from atmospheric interactions with cosmic ray particles.

λ [*f*]

All ejected gamma ray photons are neutral energy quanta sets [photons / EM waves]

[*f*] λ

Gamma rays typically have frequencies above 10 exahertz (or >10^19 Hz), and therefore generally have energies above 100 keV and wavelengths less than 10 picometers (less than the diameter of an atom)



Alpha radiation - Positive charge particles (nuclei)
Beta radiation - Negative charge particles (leptons)

gamma rays

Gamma decay produces rays with energies of only a few hundred keV, and almost always less than 10MeV



0
[n-n]

EM Wave

EM Field Planck quanta

$$2\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Photons ElectroMagnetic mass velocity

Gamma rays are a form of ionizing radiation, and they have very good penetrating power. They result from the release of atomic energies and will cause biological damage to living tissue.

$$2hv = E = hf$$

Care must always be taken to distingush between charged Planck quanta [v] and photons [f]

gamma ray bursts

Baryon mass-Matter topology

N^0 [18-18] → [2.25 e23] [v-v]

$$E = 2mc^2 = hf$$

930 MeV 930 MeV

gamma ray mass-energy geometry

are the result of the stored KEM mass-energies of Matter topologies being released as mass-energy momenta geometries

neutrino-Neutron Interactions

Neutrogen

$ve + N^0 \overset{[24\text{-}24]}{\sim} P^+ + e^-$

$[6\text{-}6]$ $[18\text{-}18]$ $[24\text{-}12]$ $[0\text{-}12]$

Charged Matter equivalence

Hydrogen



neutrino capture

Neutron decay is not the spontaneous process hypothesied by modern nuclear physicists

The observed decay products are the result of solar neutrinos interacting with Neutrons (both within nuclei and free)

the neutrinos also have an equally likely probability of interacting with Protons in the nuclei

[24-24]

A Neutronium atom has an identical mass-charge quotient to that of Hydrogen

[24-24]

Neutronium decay processes

A Neutron/neutrino interaction can decay into 4 differing particle sets

$[24\text{-}24]$

$\underset{[18\text{-}18]}{N^0} + \underset{[6\text{-}6]}{ve}$

$\xrightarrow{\alpha} \underset{[12\text{-}0]}{e^+} + \underset{[12\text{-}0]}{e^+} + \underset{[0\text{-}12]}{e^-} + \underset{[0\text{-}12]}{e^-}$

$\xrightarrow{\beta} \underset{[12\text{-}0]}{e^+} + \underset{[0\text{-}12]}{e^-} + \underset{[6\text{-}6]}{ve} + \underset{[6\text{-}6]}{ve}$

$\xrightarrow{\gamma} \underset{[6\text{-}6]}{ve} + \underset{[6\text{-}6]}{ve} + \underset{[6\text{-}6]}{ve} + \underset{[6\text{-}6]}{ve}$

$\xrightarrow{\delta} [n\text{-}n]\ \gamma^0$

All paths are uni-directional high energy Matter-Energy CP decay paths only →



Excluding their nett Charge,
Neutrons have neutral particle geometries [18-18]
identical to that of a Proton [24-12]

$\underset{[18\text{-}18]}{N^0} \neq \underset{[24\text{-}12]}{P^+} + \underset{[0\text{-}12]}{e^-}$

$[24\text{-}24]$



Spontaneous Neutron decay into Proton-electron-neutrinos is not possible without the interaction of Muonic neutrinos (see Tetryonic Charge numbers)

A Neutron is NOT a Proton that has absorbed an electron

neutrino-Proton Interactions



neutrino capture

Neutron decay is not the spontaneous process hypothesied by modern nuclear physicists

The observed decay products are the result of solar neutrinos interacting with Neutrons (both within nuclei and free)

the neutrinos also have an equally likely probability of interacting with Neutrons in the nuclei

[30-18]

A Proton-neutrino atom would have an identical charge quotient to that of a Proton

[24-12]

Although very weakly interacting, neutrinos can still be attracted to and bind to Protons via their negative charge fascia



Proton decay paths

A Proton/Neutrino interaction can decay into 4 differing particle sets



[30-18]

$P^+ + ve$ [24-12] [6-6]

α $\rightarrow$ $N^0 + e^+$ [18-18] [12-0]

β $\rightarrow$ $e^+ + e^+ + e^- + ve$ [12-0] [12-0] [0-2] [6-6]

γ $\rightarrow$ $ve + ve + ve + e^+$ [6-6] [6-6] [6-6] [12-0]

δ $\rightarrow$ [n-n] $\gamma^0 + e^+$ [12-0]

All paths are uni-directional high energy Matter-Energy CP decay paths only $\rightarrow$

If they exist, Proton-neutrino particle couplings would function in a manner identical to that of Proton-electron couplings and could be detected by the anomalous spin measurements that would result

A Proton has a Positive charge geometry [24-12] equivalent to that of a Neutral Neutron [18-18]



A Proton is topologically identical to a Neutron (differing only in the net charge created)

Quantum Batteries

Atomic nuclei can be easily scaled to non-quantum sizes to offer clean, safe and portable long term Energy storage devices that can store energy indefinitely and release it on demand anywhere in the World


Quantum
Cathode
12
[42-30]
N0
n
e-
P+
45,000
Quantum
Anode

The quantum battery is unique in that in addition to storing energy indefinitely, when an electron binds to the Deuteron nuclei it has the ability to release specific energies [photons] by way of its quantum-scale synchronous converter topologies


12
[0-12]
e-
Negative charge
topology
Quantum
Rotor

12 loop quantum inductive rotor

(Atomic Nuclei)


144
[84-60]
+
-
P+
N0
n1
n1
N0
P+
45,000
45,000
-
+

anti-Parallel Configuration

+ E90
03-2013
Energizer

Synchronous quantum converter topologies can be connected in parallel or series to meet varying power requirements anywhere in the World and provides for the safe storage of nuclear energy as mass

Series Configuration

+ E90
03-2013
Energizer


144
[84-60]
-
N0
n2
P+
N0
n1
P+
90,000
+

Quantum synchronous Converters

Energy can be stored in macro-scaled quantum converters as mass

The electron has a charged Tetryonic
Matter topology that is electrically
equivalent to a 6 loop inductive rotor

Energy

$$\frac{12\pi}{c^4}\left[\left[m\Omega v^2\right]\right]_{n1}^{n8}$$

Planck quanta
mass velocity

momenta

Quantum
Cathode



Quantum
Anode

Matter is radiant EM energy
in a standing-waveform

Energy

$$\frac{72\pi}{c^4}\left[\left[m\Omega v^2\right]\right]_{n25}^{n32}$$

Nuclei
Planck quanta
mass velocity

momenta

Building on the charged topology of Deuterium nuclei,
scaled electromechanical quantum converters can be manufactured
to provide efficient electrical mass-energy storage & distribution devices

Energy

$$\frac{84\pi}{c^4}{}_{n25}^{n32}\left[\left[m\Omega v^2\right]\right]_{n1}^{n8}$$

Deuterons
Planck quanta
mass velocity

momenta

These devices can be transported any where demand requires them worldwide with their energies stored in the form of mass

Negating the need for centralised power stations and distribution lines extending vast distances to provide power to remote communities

A quantum synchronous converter
can store and release 3 forms of energy

Angular Momentum (motional energy)
square root linear momentum

Radiant Energy (emission/absorption)
of photon/boson mass-energy geometries

EM mass-Matter (stored masses in Matter topologies)
radiant EM mass-energies stored in standing wave Matter topologies

Radiant
energies in



Radiant
energies out

Leptons rotate within the
Baryonic EM fields of the Nucleus

Nuclear Fission

Fission is a currently known source of nuclear energy for human consumption with an efficiency of less than 1%

Its energy output can be easily exceeded with cold fission & EM pinch technologies without any of the harmful nuclear by-products


Uranium
Actinoid
Level
Q
P
O
N
M
L
K
Shell
7
6
5
4
3
2
1
2
9
21
32
18
8
2
[Rn] 5f3 6d1 7s2
92
92 Protons 24/12
92 Neutrons 18/18
92 Electrons 0/12
17
56
36
Barium
Alkaline Earth
P
O
N
M
L
K
6
5
4
3
2
1
2
8
18
18
8
2
[Xe] 6s2
56
Krypton
Noble Gas
N
M
L
K
4
3
2
1
8
18
8
2
[Ar] 3d10 4s2 4p6
36

1 - A Slow Neutron with >0.4eV of [K]EM energy interacts with a unstable Uranium nuclei raising its quantum levels

2 - Outer layer of alpha particles are ejected from inner Barium core electron configuration

3 - Remaining Bayonic cloud releases excess energy and recombines to form Nuclei

4 - Barium cores and recombined Krypton cores form Decay products

Energy Released

U Ba Kr

[1,079,424] - [534,240 + 255,744]

289,440

~ 12 rest energy Neutrons
~ 11.9760 GeV

Tetryonics 60.12 - Nuclear Fission



Tetryonic Geometry

7,728 = (4,708 + 3,024)
U Ba Kr

Kinetic [KEM] energies stored in charged geometries are CHEM'ical energies

In fission the outermost layer of protons/neutrons are 'ejected' leaving a core (electron) element.

Ejected baryons then recombine under residual Strong Forces to form the lighter secondary decay products

1 - A slow Neutron with >0.4eV of [K]EM energy interacts with a unstable Uranium nuclei raising its quantum levels

2 - Outer layer of Deuterons is ejected from inner Barium core electron configuration

3 - Remaining Bayonic cloud releases excess energy and recombines to form Nuclei

4 - Barium cores and recombined Krypton cores form Decay products

The linear momentum of slow neutrons fractures the weakly held outer orbital baryons from the core electron configurations in radioactive elements

The controlled release of KEM energies from the atomic nucleus is nuclear fission [heat, light & radioactive isotopes]

Energies excess to the formation of a stable atomic configuration can be released and either radiated away as light/heat, or go on to provide additional kinetic energies to free additional Neutrons that can initiate a continuing chain reaction of the remaining high energy nuclei

It is the sudden release of stored standing-wave & kinetic energies that creates the explosive power of nuclear explosions

Energy Released

U → Ba + Kr
[1,079,424] - [534,240 + 255,744]

289,440

~ 12 rest energy Neutrons
~ 11.9760 GeV

Tetryonics 60.13 - Nuclear Fission process

Copyright ABRAHAM [2008] - All rights reserved

Sonoluminescence

Sonoluminescence is the first hint at the energies that can be released from Tetryonic collapse and involves the emission of short bursts of light from imploding bubbles in a liquid when excited by sound.

The production of light as a result of the passing of sound waves through a liquid medium.

The sound waves cause the formation of bubbles that emit bright flashes of light when they collapse.

It is a key step on the road to realising technologies that can provide Humanity with clean, safe, efficient Energy production through the conversion of Matter into various forms of EM radiation

Sonoluminesence is the result of energy releases from the collapse of standing-wave Matter topologies within Fluids

Finding an efficient means of inducing and managing a controlled reaction where 3D Matter topologies are converted into 2D radiant energy is a key step on the path to creating a future energy source of all Humanity



The gauge transformation of Matter into EM radiation is the most efficient form of energy release available to us



All Matter and molecules are 3D Tetryonic charge topologies which can be collapsed into 2D radiant EM geometries [waveforms]

The energies released are seen as brief flashes of light at the centre of the surrounding medium

Stanley Pons Martin Fleischmann

(23 August 1943) (29 March 1927 – 3 August 2012)

'Nuclear fusion of the type postulated would be inconsistent with current understanding and, if verified, would require theory to be extended in an unexpected way'

Palladium's rest molar mass is 108.7867 with a stored Kinetic energy content of 15.699 Gev [16 neutron equivalence]


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
E
2
8
18
32
32
18
8
2

The reported excess energy released is often refused as being impossible as it woud require the release of massive neutron radiation bath.

Expelling the non-core atomic nuclei results in a release of stored KEM energies as the deuterium nuclei seek to reach a ground energy level state

Cold Fission



Atomic nuclei can easily release the reported energies without Neutron particle emissions when an accurate model of the atomic nuclei is used



'Fusion' is a fictious nuclear process 'cold fusion' is in fact a form of nuclear fission

Krypton's rest molar mass is 83.3412 with a stored Kinetic energy content of 10.582 Gev [11 neutron equivalence]


3,864
[1,932-21,932]
Pd
108.7857
9
1
3
7
5
5
4
1
2
1
2
3
6
6
8
Pd
4
2
10
2,448,984
[1.806429039 e-25 kg]
378,432
[15.699 GeV]
Palladium


O
Side view
N
x2
46
N
M
L
K
36
8
18
8
2


3,024
[1,512-1,512]
Kr
83.3412
9
1
3
7
5
5
4
1
1
2
2
3
6
Kr
6
8
4
2
10
1,876,176
[1.383912190 e-25kg]
255,744
[10.582 GeV]
Krypton

2 x n5
10 Deuterons
8 x n4

122,688
[5.076 GeV]

Energy equivalent to 5+ Neutrons

NO excess Neutrons are ever released
~ only stored KEM energies and alpha particles

[Kr] 4d8 5s2
36

Transition
Metal

46 Protons 24-12
46 Neutrons 18-18
46 Electrons 0-12
1 5

[Ar] 3d10 4s2 4p6
36

Noble
Gas

36 Protons 24-12
36 Neutrons 18-18
36 Electrons 0-12
1 4


ENERGY
13 Md 13 Tm
Ac 1 La 1
Pa 3 Pr 3
Rg Au 9 Ag Cu 9
MASS
MATTER
Bk 9 Tb 9
Lr Lu 1 Y Sc 1
Db Ta 3 Nb V 3
Es 11 Ho 11
Mt Ir 7 Rh Co 7
Bh Re 5 Tc Mn 5
7 Am 7 Eu
At I Uus 5 Br F Cl 5
4 Po Te Lv 4 Se O S
Np 5 Pm 5
1 Cs Rb Fr D 1 K Uun Li Na
1 Tl In Uut 1 Ga B Al
Pb Sn Fl 2 Ge C Si 2
Tetryonic
Topologies
Ba Sr Ra He 2 Ca Ub Be Mg 2
Bi Sb Uup 3 As N P 3
Rn Xe Uuo 6 Kr Ne Ar 6
Pu 6 Sm 6
6 Hs Os 6 Ru Fe
8 Ds Pt 8 Pd Ni
Cm 8 Gd 8
12 Fm 12 Er
4 Sg W 4 Mo Cr
2 Rf Hf 2 Zr Ti
10 Cn Hg 10 Cd Zn
Cf 10 Dy 10
ELEMENTS
COMPOUNDS
4 U 4 Nd
Th 2 Ce 2
No 14 Yb 14
ELECTRON CONFIGURATIONS

Tetryonic Chemistry

The charged topology of periodic and compound Matter


1
2
3
4
5
3
9
Q
RE
7
2
16
Atomic masses
Molar Matter
8
9
25
18
Z
32
32
18
Elements
Compounds
13
49
15
8
64
17
2
81
M
KE
Chemical energies

ISBN 978-0-987288-3-1
[Second Edition © 2012]

Abraham



TETRYONICS

The charged interactions of universal Gravitation

Q
RE
ε
Radiant
masses
Standing-wave
Matter
G
Gravitational
GEM fields
Interactive
KEM fields
μ
k
M
KE
Vacuum
Energies

Foundational Quantum Cosmology

Abraham

ISBN 978-0-987288-4-8
[Second Edition © 2012]

Copyright ABRAHAM [2008] - All rights reserved

Copyright ABRAHAM [2008] - All rights reserved

Laws of Force

$F = ma$

Sir Issac Newton

(25 December 1642 – 20 March 1727)

$w = mg$

Gravity



changing Magnetic lines of Force

Michael Faraday

(22 September 1791 – 25 August 1867)

create changing Electric fields of Force

Newton's Principia formulated the laws of motion and of universal gravitation

Faraday discovered the principles of electromagnetic induction, diamagnetism, and the laws of electromagnetism.

Electro-Magnetism



$$\oint \vec{E} \cdot d\vec{A} = \frac{q}{\varepsilon_0}$$

Gauss

Light is an electromagnetic wave

Faraday

$$\oint \vec{E} \cdot d\vec{s} = -\frac{d\Phi_B}{dt}$$

James Clerk Maxwell



(13 June 1831 – 5 November 1879)

$$\oint \vec{B} \cdot d\vec{A} = 0$$

Gauss

The separate works of Gauss, Ampere & Faraday were unified to create an electromagnetic wave field theory

Ampere

$$\oint \vec{B} \cdot d\vec{s} = \mu_0 i + \frac{1}{c^2}\frac{\partial}{\partial t}\int \vec{E} \cdot d\vec{A}$$





Lorentz Contraction

Lorentz proposed that moving bodies contract in the direction of motion (Lorentz–Fitzgerald contraction)

Hendrik Lorentz

(18 July 1853 – 4 February 1928)

Lorentz Transformations



Special Relativity

attempted to explain the constant speed of Light using relative motion & Lorentz contractions

Albert Einstein

(14 March 1879 – 18 April 1955)

&

later attempted to explain gravity as a curvature of spacetime caused by Matter

General Relativity

Copyright ABRAHAM [2008] - All rights reserved

Early physics of Motion

In the 4th century BC, the Greek philosopher Aristotle believed that there is no effect or motion without a cause

Greek philosopher Aristotle

(384 BC – 322 BC)

Aristotle defined space to be the boundary geometry of a body

[x,y,z]

geometry, toplogy

Aristotle defined time to be a measure of movement

the past Δ the future

'Nature abhors a vacuum'

In Book VII of his De Architectura, the Roman engineer and architect Vitruvius contends that gravity is not dependent on a substance's "weight" but rather on its "nature".

The cause of the downward motion of heavy bodies, such as the element earth, was related to their nature, which caused them to move

In the 7th Century the Indian mathematician Brahmagupta stated "Bodies fall towards the earth as it is in the nature of the earth to attract bodies, just as it is in the nature of water to flow."


Predicted motion according to Aristotle
Actual motion of projectile

Heavier things fall faster, with speed being proportional to weight.

The speed with which a body falls is inversely proportional to the density of the medium it is falling through.

Indian Mathematician Brahmagupta

(597–668 AD)

Brahmagupta dedicated a substantial portion of his work to geometry

height
base

Brahmagupta is considered the first to formulate the concept of zero

negative numbers 0 positive numbers

Brahmagupta introduced new algebric methods for solving quadratic equations

Copyright ABRAHAM [2008] - All rights reserved

Galilean Gravity

Galileo Galilei

(15 February 1564 – 8 January 1642)

Galileo claimed to have a Universal Law of Gravitation
covering both terrestrial gravity and the motion of planets
which he was afraid to discuss.

But this looks more an inspired aspiration than a reality,
as he seems not to have considered gravitational force as
decreasing with distance from its source.

He did however, definitively show that objects experience a uniform
acceleration in a gravitational field (irrespective of their masses)
which was central to Newton's later Universal Law of Gravitation

*Galileo dismissed as a "useless fiction" the idea, held by his
contemporary Johannes Kepler, that the moon caused the tides.*

*Galileo also refused to accept Kepler's elliptical orbits of the planets,
considering the circle the "perfect" shape for planetary orbits.*

The Motion of Falling Bodies



MATHEMATICAL
DISCOURSES
CONCERNING
Two New Sciences
RELATING TO
Mechanicks and Local Motion,
IN
FOUR DIALOGUES.

By GALILEO GALILEI,

LONDON:

(ca. 1590)

Galileo was the first to counter Aristotle's earlier idea's of motion by teaching that
All objects experience a uniform acceleration in a Gravitational field
(irrespective of their different mass-Matter contents)



Aristotelian physics

**In De motu Galileo proposed that in free fall bodies dropped with a characteristic
uniform speed determined not by their weight but by their specific gravity.**

**He put this theory to the test by dropping bodies from heights and
found that his experiments did not confirm his theory.**

**It is quoted in 'Galileo's Daughter' that the lighter body (i.e. that of the lower specific gravity)
will move ahead of the heavier body at the start of the fall, and
that the heavier body then overtakes it and arrives at
the bottom slightly earlier.**



Newtonian physics

Copyright ABRAHAM [2008] - All rights reserved

Sir Issac Newton

(25 December 1642 – 20 March 1727)

In the late 17th century, Robert Hooke's suggested
'that there is a gravitational force which depends on the inverse square of the distance'

Newtonian Gravitation

Newton's monograph Philosophiæ Naturalis Principia Mathematica, published in 1687, lays the foundations for most of classical mechanics. In this work, Newton described Universal gravitation and the three laws of motion, which dominated the scientific view of the physical universe for the next three centuries.

Newton showed that the motions of objects on Earth and of celestial bodies are governed by the same set of natural laws, by demonstrating the consistency between Kepler's laws of planetary motion and his theory of gravitation, thus removing the last doubts about heliocentrism and advancing the Scientific Revolution.

The Principia is generally considered to be one of the most important scientific books ever written.

Principia Mathematica



PHILOSOPHIÆ
NATURALIS
PRINCIPIA
MATHEMATICA.

AUCTORE
ISAACO NEWTONO, Eq. Aur.

Editio tertia aucta & emendata.

LONDINI:
Apud Guil. & Joh. Innys, Regiæ Societatis typographos.
MDCCXXVI.

first edition (1686/1687)

First Law of Motion

$$\sum \mathbf{F} = 0 \Rightarrow \frac{d\mathbf{v}}{dt} = 0$$

Bodies at rest - remain at rest
unless acted upon by an outside Force

Second Law of Motion

$$\sum \mathbf{F} = \frac{\mathrm{d}\mathbf{p}}{\mathrm{d}t} = m\frac{\mathrm{d}\mathbf{v}}{\mathrm{d}t} + \mathbf{v}\frac{\mathrm{d}m}{\mathrm{d}t}$$

The nett force on a particle is equal to the time
rate of change of its linear momentum [p]

Third Law of Motion

$$\sum \mathbf{F}_{a,b} = -\sum \mathbf{F}_{b,a}$$

For every action there is
an equal and opposite reaction



Newton's Law of universal Gravitation

"I deduced that the forces which keep the planets in their orbs must [be] reciprocally as the squares of their distances from the centers about which they revolve: and thereby compared the force requisite to keep the Moon in her Orb with the force of gravity at the surface of the Earth; and found them answer pretty nearly"

$$F = -G\,\frac{M_1 m_2}{r^2}$$

"hitherto I have not been able to discover the cause of those properties of gravity from the phenomena, and I frame no hypothesis"

According to Bošković's simple dynamistic atomism, Matter is not only endowed with forces (dynamic system), but it is composed of forces (dynamistic system). Forces flow out of the atom and permeate empty space.

This idea led to the concept of the field, much later formulated by M. Faraday (1844), who together with J.C. Maxwell introduced the idea of fields of force into science.

Boskovic is famous for his atomic theory and made many important contributions to astronomy, including the first geometric procedure for determining the equator of a rotating planet from three observations of a surface feature and for computing the orbit of a planet from three observations of its position.

In 1753 he also discovered the absence of atmosphere on the Moon.

Rudjer Boskovic

(18 May 1711 – 13 February 1787)

k

Boskovic proposed that attractive Gravitational fields could be explained as diminshed interactive EM fields that result in a nett converent force at great distances

G



Diminished EM waves



D E
VIRIBUS VIVIS
DISSERTATIO
AUCTORE
P. ROGERIO JOSEPHO BOSCOVICH S.J.
Matheseos Professore in Collegio Romano.

ROMÆ, MDCCXLV.
Sumtibus Venantii Monaldini Bibliopolæ in Via Cursus.
Typis Komarek
Superiorum permissu.

In 1745 Bošković published De Viribus Vivis in which he tried to find a middle way between Isaac Newton's gravitational theory and Gottfried Leibniz's metaphysical theory of monad-points

The force is repulsive when this curve lies above the line AC and attractive when it lies below it.

At very large distances (at and beyond V), it is attractive and approaches Newton's inverse-square law of force produced by gravity



nett attractive force at large distances

Copyright ABRAHAM [2008] - All rights reserved

Gaussian Gravity

Gauss's law for gravity bears the same mathematical relation to Newton's law that Gauss's law for electricity bears to Coulomb's law.

G

Gauss's law for gravity is mathematically similar in form to Gauss's law for electrostatics.

k

the striking mathematical similarity in the formulation of electrostatics and gravitation has puzzled science for centuries

$$F_{elec}\ k \propto \frac{Q_1 Q_2}{r^2}$$

$$F_{grav}\ G \propto \frac{M_1 m_2}{r^2}$$



Carl Friedrich Gauss

(30 April 1777 – 23 February 1855)



$$\oint \vec{E}\cdot d\vec{A} = \frac{q}{\varepsilon_0} = 4\pi k q$$

The electric flux through any closed surface is proportional to the enclosed electric charge.

$$\nabla \cdot E = \frac{\rho}{\varepsilon_0} = 4\pi k \rho$$

Gauss's law for gravity, also known as Gauss's flux theorem for gravity, is a law of physics which is essentially equivalent to Newton's law of universal gravitation.

Although Gauss's law for gravity is physically equivalent to Newton's law, there are many situations where Gauss' law for gravity offers a more convenient and simple way to do a calculation than Newton's law.

note: 4π spherical topologies are equivalent to 4π tetrahedral topologies
[see Euler characteristics & Gauss-Bonnet topology theorem]

$$\oint_{\partial V} \mathbf{g}\cdot d\mathbf{A} = -4\pi G M$$

The gravitational flux through any closed surface is proportional to the enclosed Matter

$$\nabla \cdot \mathbf{g} = -4\pi G \rho$$

Poisson's Gravity fields

Charges are the sources
and sinks of EM fields

Poisson recognised that charges are the sources and sinks of electrostatic fields:
positive charges emanate electric field lines, and the field lines terminate at negative charges.

Similarly, in Newton's gravitation masses are the sources of the gravity field
so that field lines terminate at objects that have mass.

Simeon Poisson

(21 June 1781 – 25 April 1840)

Matter is the source
of Gravitational fields



Poisson formalised Gauss' Law for electric fields (using the more general divergence theorem)

$$\iint \vec{E}\cdot d\vec{S} = \frac{q_e}{\epsilon_0} \Rightarrow \vec{\nabla}\cdot\vec{E} = \frac{\rho_e}{\epsilon_0}$$

and then applied the same formulation to spherical Matter for gravitation

$$\iint \vec{g}\cdot d\vec{S} = -4\pi G_c m \Rightarrow \vec{\nabla}\cdot\vec{g} = -4\pi G_c \rho_m$$

All EM field interactions are the result of superpositioned EM fields (comprising of convergent AND divergent energy momenta) whose quanta create differing field strengths,
The inverse square forces of gravity can be modelled using the same field geometry thus illustrating the reason for the geometric & mathematical similarity between Newton's & Coulomb's constants



Positive charges are
Sources of positive E fields and
Sinks for negative E fields

$$\nabla^2\Phi = 4\pi G\rho.$$

Negative Charges are
Sources of negative E fields and
Sinks for positive E fields

k

charged Matter interacts-at-a-distance
through superpositined EM fields
of energy momenta

G

gravitational Matter acts-at-a-distance
through the 3D displacement of
vacuum energy momenta

$$\nabla^2\Phi = -\frac{\rho}{\epsilon_0}$$

$$\nabla^2\Phi = -\frac{\rho}{\epsilon_0}$$

Gravitational Matter is a source of interactive EM fields and a sink for convergent Gravitational fields

Tetryonic QM & QED clearly shows that both the sink and source fields are the result of bidirectional energy momenta

Poison's field equations shows that weak KEM field geometries can be used to model the convergent forces of Gravitational fields

Copyright ABRAHAM [2008] - All rights reserved

Gravito-Electro-Magnetism

inverse squared law



nett divergent
Electric field forces

$1/r^2$

$$\oint \vec{E}\cdot d\vec{A} = \frac{q}{\varepsilon_0}$$

k

$$\oint \vec{B}\cdot d\vec{A} = 0$$

Maxwell's 1864 achievements concerning electromagnetism have been called the "second great unification in physics", following on from the first one realised by Isaac Newton.

inverse cubed law



vector
Magnetic forces

$1/r^3$

Maxwell's equations
$\nabla\cdot\mathbf{E} = \frac{\rho}{\epsilon_0}$
$\nabla\cdot\mathbf{B} = 0$
$\nabla\times\mathbf{E} = -\frac{\partial\mathbf{B}}{\partial t}$
$\nabla\times\mathbf{B} = \frac{1}{\epsilon_0 c^2}\mathbf{J} + \frac{1}{c^2}\frac{\partial\mathbf{E}}{\partial t}$

James Clerk Maxwell

(13 June 1831 – 5 November 1879)

Any opinion as to the form in which the energy of gravitation exists in space is of great importance, and whoever can make his opinion probable will have, made an enormous stride in physical speculation.

The apparent universality of gravitation, and the equality of its effects on matter of all kinds are most remarkable facts, hitherto without exception; but they are purely experimental facts, liable to be corrected by a single observed exception.

We cannot conceive of Matter with negative inertia or mass; but we see no way of accounting for the proportionality of gravitation to mass by any legitimate method of demonstration

GEM equations
$\nabla\cdot\mathbf{E}_g = -4\pi G\rho_g$
$\nabla\cdot\mathbf{B}_g = 0$
$\nabla\times\mathbf{E}_g = -\frac{\partial\mathbf{B}_g}{\partial t}$
$\nabla\times\mathbf{B}_g = 4\left(-\frac{4\pi G}{c^2}\mathbf{J}_g + \frac{1}{c^2}\frac{\partial\mathbf{E}_g}{\partial t}\right)$

$1/r^2$

strictly convergent vector force



Maxwell proposed a set of equations based on his EM field laws that created a Gravito-Electro-Magnetic field reflective of the similarities between Newton's & Coulomb's Laws

$$\nabla\times\mathbf{E}_g = -\frac{\partial\mathbf{B}_g}{\partial t}$$

G

$$\nabla\cdot\mathbf{B}_g = 0$$

giving rise to spectulation about the existence of 'gravitons'
a theorised Gravitational 'charge' carrier

$1/r^3$

gravitomagnetic dipole



Copyright ABRAHAM [2008] - All rights reserved

General Relativity

$$G_{ab} = 8\pi G\, T_{\mu\nu}$$

The General Theory of Relativity

In 1915, Einstein extended SR and proposed a new theory of gravitation to account for accelerating bodies

Einstein said that when he "was sitting in a chair in the patent office at Bern when all of a sudden a thought occurred to me: 'If a person falls freely he will not feel his own weight.' I was startled. This simple thought ... impelled me toward a theory of gravitation. ..."

$$R_{\mu\nu} - \tfrac{1}{2} R g_{\mu\nu} = \frac{8\pi G}{c^4} T_{\mu\nu}$$

The EFE is a tensor equation relating a set of symmetric 4 x 4 tensors.

the scalar curvature

Newton's gravitational constant

Ricci curvature tensor

$$R_{\mu\nu} - \tfrac{1}{2} g_{\mu\nu} R + \Lambda g_{\mu\nu} = \frac{8\pi G}{c^4} T_{\mu\nu}$$

the stress-energy tensor

the metric tensor

the speed of light in vacuum

Each tensor has 10 independent components

Spacetime

Matter

$$G_{\mu\nu} + g_{\mu\nu}\Lambda = 8\pi T_{\mu\nu}$$

the cosmological constant

General Relativity describes gravity as a warping of space itself, not as a force.
Einstein pictured space as a three-dimensional version of a thin rubber sheet

Einstein's General Theory of Relativity, which was published in 1916 had as its foundation that the laws of nature in an accelerating frame are equivalent to the laws of a gravitational field.

This is known as the Equivalence Principle.

Albert Einstein

(14 March 1879 – 18 April 1955)

$$G_{ab} = \kappa\, T_{\mu\nu}$$

curved spacetime

mass-energy tensor

where

$$\kappa = -\frac{8\pi G}{c^4}$$

Sir Issac Newton

(25 December 1642 – 20 March 1727)

GEM fields & Gravity

Gravity is one of the four fundamental interactions of nature,
along with electromagnetism and the nuclear strong and weak forces

[for centuries scientific enquiry has been aimed squarely at discerning a physical mechanism for gravitation]

$$\overset{\text{Matter}}{\frac{4n\pi}{c^4}}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\overset{\text{quanta}}{\underset{\text{velocity}}{v^2}}\right]\right]$$

Tetryonics reveals Gravity to be the result of the displacement of vacuum energies by mass-Matter topologies which is accurately modelled using GEM field geometry

Albert Einstein

(14 March 1879 – 18 April 1955)

$$F = -G\,\overset{\text{masses}}{\frac{M_1 m_2}{r^2}}$$

$$G_{ab} = \frac{8\pi G}{c^4}\,\overset{\text{energies}}{T_{\mu\nu}}$$

Gravity is responsible for keeping the Earth and the other planets in their orbits around the Sun;
for keeping the Moon in its orbit around the Earth; for the formation of tides; for natural convection,
by which fluid flow occurs under the influence of a density gradient and gravity;
for heating the interiors of forming stars and planets to very high temperatures;
and for various other phenomena observed on Earth.



instantaneous
action-at-a-distance

Gravity is a natural phenomenon by which physical bodies attract each other with a force proportional to their mass-Matter content.

Gravity is most familiar as the agent that gives weight to objects with mass and causes them to fall to the ground when dropped.

Gravity causes dispersed Matter to coalesce, and coalesced Matter to remain intact, to the creation of the SUN, the Earth, and to source of energy in the stars that light our universe.



motion in
curved spacetime

Separating Space & Time





(in the search for Gravity)

Instantaneous
'action-at-a-distance'

Relativistic
spacetime 'curvature'



DOES

The Earth pull on the moon and
the moon pull proportionally back on the Earth

OR

Does the Earth curve spacetime in its vicinity
with the moon following the geodesic path created



Tetryonic theory through its clear definitions of charged mass-ENERGY-Matter provides the long-sought answer to Gravitation

Copyright ABRAHAM [2008] - All rights reserved

Empty Space

is defined in Tetryonic & relativistic theory
by the speed of light



c^2
(0,1,1)
c^3
(1,1,1)
c
(0,0,1)
c^2
(1,0,1)
3D
space
2D
plane
c
(0,1,0)
c^2
(1,1,0)
z
y
vector direction
vector direction
2D
plane
x
vector direction
(0,0,0)
c
(1,0,0)

Energy

content of free space is Zero

A Spatial region is defined
by a co-ordinate system so as to
measure the physics and motion
of mass-ENERGY-Matter
within its confines

mass

is Energy content per unit of time

EM mass-energies can
be found in (and move through)
empty Space in various forms:
radiant energies, Matter etc

Matter

is Energy content per unit of time squared

Space can be any regular geometry
[Cubic, Spherical or polyhedral]
limited by the spatial co-ordinates
used to define the region or volume

Empty Space is defined as a geometric volume devoid of any form of Energy

Spacetime co-ordinates

The linear force vectors of divergent Energy
can form various co-ordinate systems
based on their vector directions
per unit of time

Charge radiates unilaterally
in the direction of its
vector linear momentum

Vector forces

**Euclidean
planar
space-time**



EM Light radiates bi-laterally
in the 2 directions of its
linear momentum vectors



Radiant Energies

Radial Time

c
299,792,458
linear metres
per sec

c^2
8.987551787 e16
radial square metres
per sec

c^3
2.694400242 e25
cubic metres
per sec

c^4
8.077608713 e33
spherical metres
per sec

Cartesian and Curvilinear
spatial co-ordinate systems
both measure 3D Matter

Time in Physics is a measure
of how long it takes for light to
travel 299,792,458 metres
from its source in a vacuum

$$\frac{\text{metre}}{299{,}792{,}458 \text{ sec}}$$

A metre in Physics is
the distance light travels in
1/ 299,792,458 of a second
from its source

$$\frac{299{,}792{,}458 \text{ m}}{\text{second}}$$

**Energy entropy
of a system**

**mass-energy-Matter
content of a system**

Copyright ABRAHAM [2008] - All rights reserved



Spatial co-ordinate geometries

based on the vector speed of light
form distinct spatial co-ordinate systems
for the measurement of physics

vector lines

1 Dimensional velocity

metres

Planar Circles

2 Dimensions

c^2

velocity squared

seconds

Cubic volumes

3 Dimensions velocity cubed

c^3

Cartesian co-ordinates

Spherical volumes

3 Dimensions

c^4

quarternion velocity

seconds²

Forces

mass-energies

EM energy has an equilateral geometry
and forms Tetrahedral topologies
within regions of empty space

mass-Energy-Matter
and all forces

Copyright ABRAHAM [2008] - All rights reserved

Spatial co-ordinate systems

Cubic



Spacetime (or space-time, or space time) is any mathematical model that combines space and time into a single continuum.

Spacetime is usually interpreted with space as being three-dimensional and time playing the role of a fourth dimension that is different from the spatial dimensions.

Tetryonic theory redefines as time to be a measure of the changing quantised angular momenta of Planck scale Charges In any spatial plane or volume

By combining space and time into a single manifold, we can significantly simply a large number of physical theories, and re-formulate them in a more uniform way to explain the mechanics of the Universe at all scales

Tetryonics maps radial spacetime co-ordinates through the vector momentum of Energy

Spherical



Cartesian Space-Time



3 spatial vectors

Recti-Linear energy momenta mapping

1 hidden dimension of time



The quantised angular momenta of mass-Energy and Matter are triangular geometries

The current methodologies for mapping energy densities onto Euclidean, Cartesian and Reimannian co-ordinates are inaccurate reflections of the charged mass-ENERGY-Matter geometries, introducing a mathematical complexity to a otherwise simple foundational equilateral geometry

Tetryonic Space-Time



3 spatial vectors

Tetryonic mass-ENERGY- Matter geometries

changing QAM is time

By mapping equilateral mass-energies & Matter into radial spatial co-ordinates Tetryonic theory is able to reveal the hidden 4th dimension of time

Copyright ABRAHAM [2008] - All rights reserved

Space & time separated

All equilateral mass-energies & tetrahedral Matter can be mapped with planar spatial geometries within spherical space-time co-ordinates

Space is the region of measurement defined by the vector propagation of light
time is a measure of the changing QAM within any spatial region


p
Ω
spatial field
nullspace
nullspace
nullspace
nullspace
nullspace
nullspace
nullspace
nullspace
nullspace
nullspace
nullspace
nullspace
nullspace
nullspace
γ
γ
+q
-q
W+
W-

Tπ standing-waves

c⁴ spatial regions contain mass-Matter

compounds

3D Matter
topologies

Molecules

Baryons

Elements

c² spatial regions contain mass-energies

nπ radiant geometries

weak irradiated mass-energies permeate 'empty' space
[vacuum energies]

photons

2D mass-energy
geometries

bosons

charges

photons

'nullspace' is a spatial region devoid of all forms of energy
[found only within tetrahedral Matter topologies]

Copyright ABRAHAM [2008] - All rights reserved

2D Euclidean spatial geometry

All 2D mass-energy momenta map onto **FLAT** Euclidian co-ordinates

[x,y] ΔΩ

(2D space & time)


ε_0
Recti-linear integrals

Cartesian spatial co-ordinates

fail to accurately map equilateral energy momenta



Minkowski spacetime

is a close approximation of Tetryonic energy momenta


ε_0
Equilateral integrals

Tetryonic space-time


60°
1
1
3
4
5
9
7
16
9
25
11
36
13
49
15
64
17
81
19
100
60°
60°
Bosons
ENERGY
$\frac{\text{ODD}\,\pi}{c^2}[[m\Omega v^2]]$
$n\pi[[m\Omega v^2]]$
Planck quanta
mass
velocity
π
radians
1/2 1 3/2 2 5/2 3 7/2 4 9/2 n 9/2 4 7/2 3 5/2 2 3/2 1 1/2
EM waves
$\frac{\text{EVEN}\,\pi}{c^2}[[m\Omega v^2]]$
c^2
seconds



negative curvative

angles add up to > 180°



flat Euclidean

angles = 180°



positive curvature

angles add up to < 180°

Copyright ABRAHAM [2008] - All rights reserved

Light cones space & time



The Tetrahedral fascia
of Matter reflect the
3 dimensions of space

The Three dimensions of Matter

Linear momentum
is the square root of
equialteral energy

mass-energy has an
equilateral geometry
due to its quantised
angular momenta

Energy densities
follow an
inverse square law

Charge is
velocity invariant

Polar view of Energy propagation

quantised
angular momenta
within a
radial spatial geometry

Photons are 2π bi-directional
radiant mass-Energy geometries

Given sufficient energies
a light cone is NOT
confined to the
illustrated
spatial
angles

time is the measurement of the changing quantised angular momenta in any spatial region

A light cone is the path that a flash of light, emanating from a single event
(localized to a single point in space and a single moment in time) and traveling in all directions,
would take through space & time.

Tetryonics 62.08 - Minkowski Light Cones

Copyright ABRAHAM [2008] - All rights reserved

Charge, energy momenta & time

measurements of the changing quantised angular momenta of scalar energy is the basis of measuring time

Ω

$\boxed{.0012}$

$\frac{m^2}{s}$

quantised angular momentum

$$\beta = \left[\frac{v}{c}\right]$$

Linear Lorentz factor

metres

$\frac{m^2}{s} \cdot \frac{s}{m}$

$\boxed{\frac{\Omega}{v}}$

λ



The Universe is filled with a predominantly neutral energy field

creating a pressure gradient on all standing-wave Matter

q

$\boxed{\frac{\Omega}{c^2}}$

$\frac{m^2}{s} \cdot \frac{s^2}{m^2}$

seconds

$$\left[\frac{v^2}{c^2}\right] = \beta^2$$

Scalar Lorentz factor

per second

$\frac{m^2}{s^2} \cdot \frac{s}{m^2}$

$\boxed{\frac{v^2}{\Omega}}$

f

Velocity of Light

$$c = \left[\overset{\lambda}{\underset{\text{Wavelength}}{\left[\frac{\Omega}{c}\right]}} \cdot \overset{f}{\underset{\text{Frequency}}{\left[\frac{c^2}{\Omega}\right]}} \right]$$

Copyright ABRAHAM [2008] - All rights reserved

$\vec{p}$

Spatial co-ordinate systems are defined by the vectors of their linear energy momentum

Space
[x,y,z]


v
x
y
p
changing linear momentum
F = mΔp = m.Δv/t = ma
creates acceleration

$\Delta\Omega$

Time is a measure of the changing quantised angular momenta in any defined region of space

Time
[seconds]

Spacetime Fields

are spatial geometries that contain changing Quantised Angular energy-Momenta [Planck quanta]


ε₀
[x,y]
ΔΩ
c²
mΩ
ε₀
[x,y]
ΔΩ
c²

Charge is the nett distribution of Planck quanta mass.[Quantised Angular Momenta] within any spatial co-ordintate system

EM masses are 2D planar energy waveforms

2D mass-energy quanta have linear & angular momenta

Matter has a 3D volumetric energy waveform


[2-2]
[4-0]
[0-4]
ε₀
ε₀
⁰3
ε₀
4
c²

mass Planck quanta

$$\frac{n\pi}{c^2}[[m\Omega v^2]]$$

mass velocity

Tetryonic geometry restores symmetry to Einstein's mass-energy equivalence and reveals a mass-ENERGY-Matter equivalance

radiant mass-energies can form standing-wave Matter


m
c²
=
ε₀
E
ε₀
3
ε₀
=
M
c⁴

standing-wave Matter can release radiant mass-energies

where space and time are separated



Matter Planck quanta

$$\frac{T\pi}{c^4}[[m\Omega v^2]]$$

mass velocity



The 4th dimension of Time

is charge, the angular momenta associated with any planar mass-energy

Accelerate

$\vec{p}$

increasing a systems's linear momentum

F = mΔ**p** = m.Δv/t = ma

creates acceleration

Decclerate

$\overleftarrow{p}$

decreasing a systems's linear momentum

F = mΔ**p** = m.Δv/t = ma

creates decceleration

Δ**p**

acceleration

$\Delta\Omega$

seconds


The square root vector force of Planck mass-energies createss linear momentum
Energy
QAM
The equilateral geometry of Planck mass-energy is Quantised Angular Momenta
$\frac{m^2}{s}$
$\frac{s^2}{m^2}$
p
p
ε_0
ε_0
$\frac{\Omega}{c^2}$
S
S
s
μ_0
μ_0
μ_0
μ_0

Clockwise charge is positive mass-seconds

Counter-clockwise charge is negative mass-seconds

Positive charge

Negative charge

the two 'arrows' of time in physics are a mathematical mis-interpretation of charge

Positive and Negative charges on opposite sides of Planck energy quanta,
the direct result of the equilateral geometry of all energy momenta
has been historically mis-represented in mathematics as
being two directional arrows of time

$\Delta\Omega$

Positive Time

$\Delta\Omega$

Negative Time

Time is a measure of the changing angular momenta-energy (Planck geometry) of any given spatial region

Copyright ABRAHAM [2008] - All rights reserved

CHARGE



all ideal inductive loops
resist changes to their
Energy levels

INERTIAL mass



All quantised angular momentum
is an equilateral geometry

all quantised Planck
energy momenta posses
square root vector Forces

quantum of WORK



vector velocity results from
linear momentum - the square root
of all scalar energies

$$kg\left[\frac{m^2}{s^2}\ \frac{s^2}{m^2}\right]$$

Scalar energy
per unit time

mass



Force

changing forces produce acceleration

$$kg\left[\frac{m^2}{s}\ \frac{s^2}{m^2}\right]$$

Planck quanta
per unit time

mass.seconds

Tetryonics 62.12 - Charge is mass.time

Charge is the equilateral geometry of Energy that gives form to all mass & Matter

Positive charged mass-energy


1
[1-0]
ε_0
Ω

Clockwise inductive energy flux

charge


mass
sec
0.0012
m²
Ω
c²

time

mass.seconds in physics is expressed as Coulombs [charge]

Negative charged mass-energy


1
[0-1]
ε_0
Ω

Counter clockwise energy flux

ε_0
m
Ω

t

$$\frac{\Delta\Omega}{c^2}$$

$$\frac{m^2}{s}\,\frac{s^2}{m^2}$$

$$s$$

seconds

t

ε_0
m
Ω

ElectroMagnetic Charge is a quantum property resulting from the equilateral QAM geometry of mass-energy

1.33518 e-20 s

Changes to nett quantised angular momenta [charged mass-energies] within any spatial co-ordinate system forms the basis of time



Two ElectroMagnetic charges are possible & both are created through the tesselation of EM energy momenta in ideal inductive loops

Copyright ABRAHAM [2008] - All rights reserved

The Quantum Arrow of Time

in physics is a measurement of changes to quantised angular momenta

Thermodynamic arrow of time

The Entropy of a system always increases



ε_0
mass.seconds
is charge



12
1
2
3
4
5
6
7
8
9
10
11
Q
RE
M
KE
t

Cosmological arrow of time

The Universe is evolving from a big bang to ?



ε_0
mass.seconds
is charge

Radiative arrow of time

EM mass-energies rative outward from a point source

Causal arrow of time

A cause always precedes its effect

Tetryonic theory maps QAM as equilateral Planck geometries & reveals ΔQAM to be time
Time and the spatial dimensions it creates are mapped with radial & spherical co-ordinates

$\Delta m\Omega$

Decceleration

The Arrow of Time

is our perception of changing quantum-scale angular momenta

$\Delta m\Omega$

Acceleration





12
1
2
3
4
5
6
7
8
9
10
11
12
0°
30°
60°
90°
120°
150°
180°
210°
240°
270°
300°
330°
360°



Copyright ABRAHAM [2008] - All rights reserved

Time dilation

An accurate clock at rest with respect to one observer may be measured to tick at a different rate when compared to a second observer's own equally accurate clocks.
This effect arises neither from technical aspects of the clocks nor from the fact that signals need time to propagate, but from the nature of spacetime itself.

The changing quantised angular momenta of
all mass-energy-Matter densities in any spatial region
all impact on our measurement of time [ΔΩ]

increasing the mass of Matter
increases the stress energy tensor
[mass-energy gradient]

Stronger G fields

GR

Vacuum energy-Matter
pressure gradients

Weaker G fields

gravity is proportional to
the material displacement volume of mass-Matter
in a given spatial region of vacuum energy



Gravitation
is the result of the
GEM
gravity & KEM field
interactions
of material bodies

tests of GR using
photons are erroneous
tests of SR

accelerating material objects
increases the Planck quanta
[mass.QAM] in their KEM fields

Stronger KEM fields

SR

Kinetic EM energies
of motion

Weaker KEM fields

decelerating material objects
decreases the Planck quanta
[mass.QAM] in their KEM fields

Any attempt to accurately model the full effections of Gravitation must include
a complete definition and differentiation of all mass-energy & Matter
along with the vacuum energy pressure gradient created by them

In the theory of relativity, time dilation is an actual difference of elapsed time between two events as measured by observers either moving relative to each other or differently situated from gravitational masses.

Copyright ABRAHAM [2008] - All rights reserved

Entropy in physical systems

is the result of changes to the net organisation of quantised angular momenta as it seeks equilibrium

Second law of thermodynamics

An isolated physical system, if not already in its own internal state of thermodynamic equilibrium, spontaneously evolves towards it.
In an isolated physical system, there is a tendency towards spatial homogeneity.

The Boltzmann equation was developed to describe the dynamics of an ideal gas

$$\frac{\partial f}{\partial t} + v\frac{\partial f}{\partial x} + \frac{F}{m}\frac{\partial f}{\partial v} = \frac{\partial f}{\partial t}$$

Ludwig Eduard Boltzmann

(February 20, 1844 – September 5, 1906)

$$S = k\cdot[\log(W)]$$

Boltzmann entropy formula

Tetryonic theory utilises the equilateral geometry of ideal quantum inductors to model EM energies

mass-energy radiator

normal statisitcal distribution of energies

Energy in all its forms seeks equilibrium



$E = n.hv$

Max Planck extended on the work of Stefan-Boltzman by deriving his heat law and quantum mechanics

Classical entropy formula

$$\underset{\text{entropy}}{\Delta S} = \overset{\text{heat}}{\Delta Q}/\underset{\text{temperature}}{T}$$

Energy always moves from higher energy organised systems to a lower dis-organised system

lower energy blackbody

A black body is an idealized physical body that absorbs all incident electromagnetic radiation

Jacob David Bekenstein



(born May 1, 1947)

Bekenstein-Hawking entropy formula

$$S = \frac{\pi A k c^3}{2hG}$$

still uses 3D [c^3] classical cartesian co-ordinates

Stephen William Hawking

(born 8 January 1942)

Tetryonic theory unites classical and quantum mechanics with relativity through equilateral QAM

The Aether

Aether theories in physics propose the existence of a medium, the aether
a space-filling substance or field, thought to be necessary as a transmission
medium for the propagation of electromagnetic waves.

bosons, photons and Matter are simply geometric concentrations of EM energy in regions of Space

Spacetime is the QAM geometry of any measured spatial [LT] region


Divergent EM field vectors
[with convergent component]
Convergent
G field vectors
Convergent
G field vectors
Divergent EM field vectors
[with convergent component]
Divergent EM field vectors
[with convergent component]
Convergent
G field vectors
null
space
Convergent
G field vectors
Divergent EM field vectors
[with convergent component]
Divergent EM field vectors
[with convergent component]
Convergent
G field vectors
Convergent
G field vectors
Divergent EM field vectors
[with convergent component]

Matter geometries form perfect quantum Faraday cages excluding all energies thus creating nullspaces

Vast radiant energy fields exist throughout all of Space save inside Matter topologies

The vacuum energy field acts upon the internal 'null space' volumes of all Matter creating a gravitational pressure gradient

The low level EM fields permeating the space between Matter forms a background vacuum energy density

Vacuum Energy is the EM energy that permeates and fills any spatial region

Historically refered to as the Aether (or the Ether) this vacuum energy field has been the source of much contention

Photons do not require the aether to propagate however the aether is permeated with 'weak' superpositioned EM fields

Copyright ABRAHAM [2008] - All rights reserved

The Luminiferous Aether

$$\frac{\rho}{m^2}$$

Photons are radiant 2D mass-energy geometries



Vacuum energies are very long wavelength photons

*Hendrik Lorentz created an electron/aether theory,
in which he introduced a strict separation
between Matter and the aether*

In the late 19th century, luminiferous aether or ether, meaning light-bearing aether,
was proposed as a medium for the propagation of light.

Newton's Opticks (1704) postulated an "Aethereal Medium" transmitting vibrations faster than light,
by which light, is put into "Fits of easy Reflexion and easy Transmission"

*Maxwell proposed a mechanical sea of molecular vortices
to explain the transfer of ElectroMagnetic energies*

*Einstein wrote that one can actually speak about a "new aether",
but one may not speak of motion in relation to that aether*

In Tetryonics all EM radiation & Matter
are revealed to be concentrations of geometric
Energies seeking equilibrium in regions of Spacetime



The aether does NOT facilitate the transmission of Energies
throughout the Universe, it is the result of radiated [K]EM energies

Vacuum energies can be likened to the mean atmospheric pressure,
with 2D mass-energies being HIGHER pressure 'gusts'

and

the nullspaces within 3D Matter creating a LOW pressure gradient
[providing a driving mechanism akin to to that of Storms, Cyclones or Tornados]

$$\frac{\rho}{m^3}$$

All Matter are 3D mass-energy topologies containing nullspaces



Planets, Stars and Galaxies contain high densities of mass-energies

*Michaelson and Morley sought to detect
the Relative motion between the Earth and aether
by measuring the speed of light*



Copyright ABRAHAM [2008] - All rights reserved

Vacuum Energy

Vacuum energy is an underlying background mass-energy that exists
in free space even when the space is devoid of matter

The Universe is Electric in nature and all Matter in it interacts via Gravito-Electro-magnetic [GEM] fields

Tetryonics shows that all Matter is quantised and these charged mass-energy quanta produce EM fields of varying strengths in turn radiating out from the source Matter into Space to form GEM fields

v
P
Q
t
M
λ
f
v²
m
s
E
c
c²

VE is not a 'quantum foam' as popularly depicted, it is a triangular Euclidean geometry of neutral mass-energies



The internal nullspaces of all Matter geometries creates a pressure gradient within Vacuum energies

EM fields do NOT propagate to 'infinity'

They radiate under the inverse square law until they weaken to become vacuum-energies

The Cosmic background radiation is the result of low level KEM fields radiated from all Matter

There are no 'virtual particles' in free space only varying mass-Energy density geometries [Bosons, Photons & Matter]

The field gradients are strongest closer to bodies of Matter

Coulombic fields are DIVERGENT [K]EM fields with interactive forces



Gravitational fields are CONVERGENT
Gravity is always attractive

Space is not Black [it is INDIGO]

It is filled with superpositioned EM fields

The Higgs Field

is another name for the Aether
(or vacuum energy field) that fills
free Space, its interaction with
inductive Tetryonic topologies
creates the inertial properties
observed in mass-Matter

Peter Higgs



(born 29 May 1929)

Free Space

is any spatial region
free of EM energy quanta
(nullspace within Tetryons)

The 'Higgs Boson' is
just a W boson by
another name

All Higgs vacuum fields
are equilateral mass-
Energy-momenta
fields

Vacuum Energy

is the lowest denisty [longest wavelength]
electromagnetic mass-energy that
having diverged from Matter
radiates outwards to fill space
& create a pressure gradient

'Virtual particles'
do NOT exist



All Bosons have ODDn planar electromagnetic charge geometries



Inductive resistance to changes of the energy content of charged fascia through vacuum energy fields creates inertial mass

mass Planck quanta

$$\frac{n\pi}{c^2}[[m\Omega v^2]]$$

mass velocity

Electromagnetic mass is a measure of the Energy content of a 2D geometry per unit of Time

m

mass-energy is a 2D geometric property of 3D Matter



the square root of scalar energies is linear momentum

The HIGGS boson has a squared number of Planck quanta in a equilateral π geometry

The HIGGS boson is an alternative name for the 2D charged mass-energy fascia of all Matter

[whose inductive QAM quanta create the physical property of inertial mass]

$$F = ma$$

inertial mass is a measure of a body's resistance to changes in acceleration due to external forces



Charged Planck quanta form the geometry of of all mass-ENERGY-Matter
[each charge fascia contains equilateral mass-energy momenta]



All Matter has 4n enclosed tetrahedral charge topologies



Matter Planck quanta

$$\frac{T\pi}{c^4}[[m\Omega v^2]]$$

mass velocity

3D material Matter is a EM standing-wave topology whose mass is a measure of its geometric Energy content

M

Matter is the 3D topology created by mass-energies

The energy momenta density of standing wave Matter

determines its inertial mass


1
h
linear momentum
1^2
quantised angular momentum
1
3
n2
1^2
2^2
1
3
5
n3
1^2
2^2
3^2
1
3
5
7
n4
1^2
2^2
3^2
4^2

m

mass

kg


ε_0
d
d
ρ
energy
c^4

M

Matter

KG


n5
1^2
2^2
3^2
4^2
5^2
n6
1^2
2^2
3^2
4^2
5^2
6^2
n7
1^2
2^2
3^2
4^2
5^2
6^2
7^2
n8
1^2
2^2
3^2
4^2
5^2
6^2
7^2
8^2

Spatial topology

Matter Planck quanta

$$\frac{4n\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

EM mass-energies

de Broglie Wavelengths

$$\frac{\rho}{c^2}$$

mass

m


velocity
v
bosons
energy
v
c
v^2
statistical distribution of
energy momenta

$$\frac{\rho}{c^4}$$

Matter

M

Compton Frequencies

The mass-energy content of Matter is contained entirely within its charged fascia topology

Copyright ABRAHAM [2008] - All rights reserved

3D Nullspaces

Planck mass-energy quanta clothe
only the topologies of Matter



**3D EM fields with volume
are measurements of
Energy per unit Time squared
[Matter]**

$$T\pi$$

**Nullspace is proportional to the
internal volumes of Tetryons**

**2D planar EM fields
are measurements of
Energy per unit Time
[EM mass]**

$$[m\Omega v^2]$$

**The mass-energy densities [fascia] of
Matter do NOT influence nullspaces**

**Inside the Tetrahedral topologies
of all Matter exists the only true vacuum**

Any radiant energy trying to enter
the interior volume of a Tetryon
will be absorbed into the fascia,
increasing its Tetryonic mass
(or increasing its KEM field energy)



A volume devoid of any possible energy quanta
[ie The True vacuum]

The interior volume of Tetryons has the
lowest energy density/pressure possible
and is accumulative as Matter forms
increasingly complex states, creating
regions of low energy density within
the nuclei of all Matter

*Outer space is considered a high-quality vacuum,
with the equivalent of just a few hydrogen atoms
per cubic meter on average. However even it is
permeated with superpositioned EM fields
of vacuum mass-energies*

$$\frac{\rho_0}{T}$$

*A true vacuum is a spatial volume
that is completely devoid of EM mass-energies,
such that its energy density/pressure is much lower
than of the surrounding energy density/pressure
[a nullspace]*



Positive charges in 2D space
are classically modelled as
clockwise energy fluxs



Time is the measurement of
Quantised Anguar momenta
in any spatial region



Negative charges in 2D space
are classically modelled as
anti-clockwise energy fluxs

mass Planck quanta

$$\frac{n\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

m

mass

Charged Planck mass-energies provide the scaffolding of 3D Matter

[x,y,z] ΔΩ

3D Space and Time

M

Matter

Matter Planck quanta

$$\frac{T\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

2D
mass geometries
are a property of
3D Matter

2 Dimensional mass-energies



3 Dimensions of Space

kg

radiant
2D mass-energy momenta

EM Field Planck quanta

$$T\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

impedance mass velocity

creates 3D standing-wave
Matter

KG

2D charged fascia



3D Space + Time

3D
Matter topology
is not a property of
2D mass-energy

Copyright ABRAHAM [2008] - All rights reserved

The impedance of any spatial region

is determined by its scalar energy content

4

[4-0]

Positive Matter

4

[0-4]



Negative Matter

$$\frac{m}{hv^2}$$

$$\frac{mc^2}{v^2}$$

$$\frac{mc^2}{h}$$



$$\frac{v^2}{c^2}$$

1.112650056 e-17

8.987551787 e16^{-1}

$$\frac{h}{m}$$

$$\frac{hv^2}{c^2}$$

$$\frac{hv^2}{m}$$

111.265 ohms

Neutral Matter

0

[2-2]



Neutral Matter

0

[2-2]

The impedance of any medium determines
the velocity of propagation for mass-energy momenta through it

EM mass vs. Matter

Often a source of confusion,
Tetryonics provides a rigorous
definition of both EM mass & Matter


504
254-254
C12
11.996
6
5
1
4
2
3
n1
270,072
14,688

6.022141579 e23
[Avagadros number]

**1 ton of Carbon & 1 ton of Lead
have the same mass-energies**

**But they have differing Matter topologies
that create a differing energy densities
for any spational region of measurement**


6,888
3444-3444
Pb
203.4744
4,580,516
889,632

**1 mole of Carbon atoms
[11.996 grams]**


Level
Graphite
4,321,152
Shell
Nuclei

Shell	Level	Nuclei
R	8	0
Q	7	0
P	6	0
O	5	0
N	4	0
M	3	0
L	2	0
K	1	6

*if Carbon 12's mass-energy content
was raised to n4 atomic levels
it would be close to the same weigh as lead*

Elemental Configuration
6[De]

*In terms of charged Matter topology
Carbon12 displaces 1/14th the volume of Lead*

504
Carbon12 atom
270,072

1 : 17

4,580,616
Lead atom
6,888

*In terms of mass-ENERGY-Matter densities
Lead is 17 times denser than Carbon
as a result of the mass quanta per charge fascia*

**1 mole of Lead
[203.4744 grams]**


Level
Lead
82
Shell
Nuclei

Shell	Level	Nuclei
R	8	0
Q	7	0
P	6	4
O	5	18
N	4	32
M	3	18
L	2	8
K	1	2

Elemental Configuration
[Xe] 4f14 5d10 6s2 6p2



EM mass-energy geometries

are 2D Euclidean EM fields posessing energy momenta

Charge

$$\frac{1\pi}{c^2}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

Bosons

$$\frac{\text{ODD}\,\pi}{c^2}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

Photons

$$\frac{2\pi}{c^2}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

EM waves

$$\frac{\text{EVEN}\,\pi}{c^2}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

mass

$$\frac{n\pi}{c^2}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

m

ENERGY

$$n\pi\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

M

Matter

$$\frac{T\pi}{c^4}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

Equilateral mass-energy geometries & Matter Topologies are measured in radial spatial-time co-ordinate systems



Tetryons

$$\frac{4\pi}{c^4}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

Fermions

$$\frac{12\pi}{c^4}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

Baryons

$$\frac{36\pi}{c^4}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

Deuterons

$$\frac{84\pi}{c^4}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$



Matter Topologies

are 3D standing-wave [4nπ] mass-energy geometries

Copyright ABRAHAM [2008] - All rights reserved

mass-energy-Matter quanta

are all defined by charged geometries & topologies



Bosons (v)

Bosons

$$\frac{\mathrm{ODD}\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

Planck quanta

mass velocity



Photons

Photons(f)

EM waves

$$\frac{\mathrm{EVEN}\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

Planck quanta

mass velocity





Tetryons (n)

Matter

$$\frac{4n\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

Planck quanta

mass velocity

charges

1π	ZPF	v
ODD π	boson	v

mass-energies

2π	photon	$2v^2$
EVEN π	EM wave	$2v^2$

mass-Matter

4π	tetryon	n
12π	lepton	n
24π	meson	n
36π	Baryon	n

Inductive charges



EM waves



Matter particles





Copyright ABRAHAM [2008] - All rights reserved

Differentiating mass & Matter

geometries topologies



All modern physical theories including relativity fail to define and differentiate between mass & Matter



kg



Charged Planck quanta
7.376238634 e-51 kg

Photons
1.475247727 e-50 kg

EM waves
5.900990907 e-50 kg

$n\pi$
mass

radiant mass-energies

Equilateral energy momenta

$T\pi$
Matter

standing-wave Matter

KG



Neutrino
8.851486361 e-50 kg

Lepton
8.851486361 e-31 kg

Baryon
1.6596536693 e-27 kg

geometry

Topology

Increasing a particle's speed increases its Kinetic EM mass-energies (rest Matter's EM mass-energy content is velocity invariant)

Charge
$$\frac{1\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$
Planck quanta mass velocity

Photons
$$\frac{2\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$
Planck quanta mass velocity

Bosons
$$\frac{\text{ODD}\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$
Planck quanta mass velocity

EM waves
$$\frac{\text{EVEN}\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$
Planck quanta mass velocity

All Matter has EM mass-energies not all EM mass-energies form Matter

Tetryons
$$\frac{4\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$
Planck quanta mass velocity

Fermions
$$\frac{12\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$
Planck quanta mass velocity

Baryons
$$\frac{36\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$
Planck quanta mass velocity

Deuterons
$$\frac{84\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$
Planck quanta mass velocity

Copyright ABRAHAM [2008] - All rights reserved

$$E = mv^2$$

6.629432351 e-34 J

E

Energy

$$kg\,\frac{m^2}{s^2}$$

Planck quanta

$$E = n\pi\left[\left[m\Omega v^2\right]\right]$$

Energy mass velocity


v
p
ε_0
hv
v^2
energy momenta

ENERGY

the proagation velocity of energy is determined
by the impedance of any spatial region

E=hv²


Δv
p
a
hv
v²
F
Δt

F=ma

the scalar impedance of space

$$\frac{s^2}{m^2}$$

$$\varepsilon_0 \times \mu_0$$

Electric permittivity* & *Magnetic permeability

$$1.11265\text{ e-}17\ \frac{s^2}{m^2}$$

$$\frac{1}{c^2}$$


ε_0
$\frac{1}{c^2}$
EM field
permitivity & permeability
c²

the Forces created by energy momenta in any spatial region
are related through the scalar constant of mass

EM mass

$$m = \frac{E}{c^2}$$

m

mass

kg

field impedance

Planck quanta

$$n\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

mass ElectroMagnetic mass velocity

7.376238376 e-51 kg


ε
m
EM mass
c²

Copyright ABRAHAM [2008] - All rights reserved

The energy-momenta of Matter

$$p = mv$$

Linear correction factor

$$\beta = \left[\frac{v}{c}\right]$$



The Energy comprising all KEM fields is proportional to the particle's velocity

$$\beta^2 = \left[\frac{v^2}{c^2}\right]$$

Scalar correction factor

$$p^2 = E = mv^2$$

$$p = T\pi\left[\left[\underset{\text{momenta}}{\overset{\text{Energy}}{m\Omega v}}\right]\right]$$

As the velocity of a particle increases so does its KEM field's mass-energy momentum

$$mv = p = hv$$

$$kg\,\frac{m}{s}$$

$$\sqrt{6.629432351\text{ e-}34\text{ J}}$$

$$4n\pi\left[\underset{\text{mass}\quad\text{velocity}}{\overset{\text{Planck}\quad\text{quanta}}{m\Omega v}}\right]$$

2.5476847 e-17 kg m/s

The linear momentum of mass-energies in standing-wave rest Matter topologies propagates at c

$$p_M = 4\pi[mv]$$

The rest mass of a particle with NO motion is the total EM mass-energy of the particle

Its linear four-momentum is the square root of its scalar energies



rest mass-Matter

In standing-wave Matter, where there is NO external forces acting on the particle, all internal momenta act in opposition and add to ZERO

all fascia

$$\vec{p}_0 = \sum \vec{p}$$

Copyright ABRAHAM [2008] - All rights reserved

Gravitational mass-Matter quanta

gravity pulls on things proportional to their mass-Matter content

$$F = -G\frac{M_1 M_2}{r^2}$$

Radiant mass-energy geometries



7.376238634 e-51 kg
mass-energy equivalence
6.629432672 e-34 J

All 3D Tetryonic topologies create displacement Matter volumes that in turn generate KEM fields as a result of the motion of their charge fascia



standing-wave Matter topologies
displace vacuum energies
creating a stress energy gradient

radiant mass-energy geometries
add energy momenta to spatial regions
increasing the stress energy gradient

Standing-wave Matter Topologies



8.851486051e-50 KG

Matter particles can have the same Tetryonic topologies but possess a differing charged mass-energy momenta content

8.851486051e-31 KG



Gravitational Attraction can be modelled as a dipole attraction of opposite charged mass fascia of Matter topologies through its differing energy field interactions

Gravitation attraction is a strictly UNI-DIRECTIONAL CONVERGENT FORCE



$k = 8.99\text{e}9 \frac{N m^2}{C^2}$



$G = 6.67\text{e-}11 \frac{N m^2}{KG^2}$



KEM field energy momenta produce a BI-DIRECTIONAL INTERACTION FIELD

Gravitation attraction is
20 orders of magnitude weaker

KEM field energy momenta produce a BI-DIRECTIONAL INTERACTION FIELD

Stress energy gradients

Energy's highest density form is 3D Matter [comprised of planar 2D EM mass-energies]
whilst its lowest pressure form is the vacuum energies created by radiated mass-energies filling space

ENERGY in all its forms seeks equilibrium



Where Newton's Law of Gravitation is modelled on geometric means

$$F = k\frac{Q_1 Q_2}{r^2}$$

Inverse Square Law

$$F = -G\frac{M_1 m_2}{r^2}$$





Einstein's General Relativity is modelled on energy pressure

$$PV = nRT$$

Matter tells Spacetime how to bend
Spacetime tells Mater how to move

$$R_{\mu\nu} - \frac{1}{2}Rg_{\mu\nu} = \frac{8\pi G}{c^4}T_{\mu\nu}$$

Like any pressure gradient, ENERGY always flows from areas of highest density to regions of low density seeking to reduce 'pressure' differentials and reach a state of equilibrium.

mass-Matter topologies create stress energy differentials in the vacuum energies of space

Copyright ABRAHAM [2008] - All rights reserved

Gravitational Matter & weight

is a measure of the amount of mass-energy in Matter

The gravitational mass
of a body determined by its
response to the force of gravity

mass-Matter

Matter

Planck quanta

$$\frac{4n\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

The gravitational acceleration
of a body in any gravity field is uniform
and proportional to its mass-Matter

$$w = F = M.g$$



48

[24-24]

charge topology

N_A

Avagadro

electrons

Planck quanta

$$\frac{12\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

mass-energy-Matter

8.8514586361 e-31 KG

Baryons

Planck quanta

$$\frac{36\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

mass-energy-Matter

1.659653693 e-27 KG

22,512

mass-Matter

1.660538841 e-27 KG

mass-Matter quantum

.001 KG

molar mass

w=M.g

weight

9.8 m/s²

$$F=Ma_g$$

= [.001] x [9.8]

= .0098 N

KG

g

Force

$$\frac{\left[kg\,\frac{m}{s^2}\right]}{KG}$$

Copyright ABRAHAM [2008] - All rights reserved

Zero Point Fields



ZPF quanta charges are the opposite sides of the same 'quantum coin'

ZPF quanta have unidirectional
energy momenta orientations

KEM fields



N-S magnetic moment vector





S-N magnetic moment vector

standing-wave mass-Matter

As the velocity of Matter increases
its relativistic mass-Energy quanta increase
as a result of the associated momentum,
kinetic energy and magnetic moment

standing-wave mass-Matter

in addition to their standing-wave topologies
mass-Matter also posesses

radiant mass-energies

Gravity & EM fields

All energy fields are velocity dependent
and combine to form vectorial K-EM fields

All charged Matter posseses
bi-directional interactive
radiant EM fields

EM



G



charged Matter topologies create
uni-directional convergent
energy gradiants

All mass-Matter is velocity invariant
and creates convergent G fields

Copyright ABRAHAM [2008] - All rights reserved

Matterless EM mass-energies

Photons are often termed as 'mass-less' particles in physics which is a complete mis-nomer.
Leading to many erroneous supersitions on the true nature and physics of light and gravity

$$\frac{E}{c^2} = m$$

mass geometry

$$M = \frac{E}{c^4}$$

Matter topology

mass is a measure of planar Energy per second



mass-less infers no energy momenta

Photons are weightless radiant EM energies not massless particles

photons possess 2D planar radiant EM mass-energy momenta

A Particle has a charged Matter topology

Matter is a closed tetrahedral standing-wave energy possessing volume

photons & EM waves have no 3D Matter topology, they are Matter-less geometries

$$\frac{\overset{ENERGY}{n\pi}\left[\left[\underset{mass}{\overset{Planck}{m}}\,\overset{quanta}{\Omega}\,\underset{velocity}{v^2}\right]\right]}{\underset{second}{c^2}}$$

$$\frac{\overset{mass}{n\pi}\left[\left[\underset{mass}{\overset{Planck}{m}}\,\overset{quanta}{\Omega}\,\underset{velocity}{v^2}\right]\right]}{c^2}$$

The definition and distinction between mass & Matter
is a major failing of modern physics, corrected for by Tetryonic theory

$$\frac{\overset{Matter}{T\pi}\left[\left[\underset{mass}{\overset{Planck}{m}}\,\overset{quanta}{\Omega}\,\underset{velocity}{v^2}\right]\right]}{c^4}$$

EM fields, vacuum energies and gravity

all result from radiant equilateral mass-energy momenta
and standing-wave Matter in radial space


EVEN π
STANDING-WAVE
mass-energies
Topologies
Photons
STRONG radiant
mass-energies
KEM
fields
WEAK radiated
mass-energies
Vacuum
energies
????

mass-energy momenta

EM

**Kinetic & EM fields create
bi-directional fields
of INTERACTION**

**Matter displaces vacuum eneries
in its environment to create a
CONVERGENT force**

G

Gravity

**All GEM fields
have equilateral
quantum geometries**

$$F = k\frac{Q_1 Q_2}{r^2}$$

**All G-EM fields can
be modelled with
Tetryonic geometry**


S
Moon
Earth
Van Allen
Belts
N

KEM fields are Interactive
Gravity is ALWAYS Convergent

*the proportional attraction of
material bodies towards each other
can be easily modeled with Tetryonic fields*

$$F = -G\frac{M_1 m_2}{r^2}$$

geometric mean



inverse square law

Charges vs. Gravity

both can be modelled as interactive or attractive geometric forces

Charged particles are comprised of non-neutralised Planck quanta


12
[12-0]
12
[0-12]
1.2e20


12
[24-12]
2.25e23

$$F = k\frac{Q_1Q_2}{r^2}$$

Charges produce bi-lateral interactive forces

mass

Matter

Nuclei

Elements

$$F = -G\frac{M_1M_2}{r^2}$$

Gravity is a convergent attractive force

Neutral Matter is comprised of neutralised Planck quanta




0
[18-18]
2.25e23

Charged ions


12
[60-48]
9.0000e23



Neutral nuclei


0
[84-84]
9.0024e23



$8.99 \times 10^{9}\ \frac{N\,m^2}{kg^2}$

Opposites Attract
Similars Repel

Interactive mass-energies & **Gravitational mass-Matter**

both produce inverse squared forces



$7.49 \times 10^{-11}\ \frac{N\,m^2}{KG^2}$

Gravitational Matter is always Attractive

Copyright ABRAHAM [2008] - All rights reserved

$$\nabla \times \mathbf{E} = -\frac{\partial \mathbf{B}}{\partial t}$$

GravitoElectroMagnetism, (abbreviated GEM), refers to a set of formal analogies between Maxwell's field equations and an approximation, valid under certain conditions, of the Einstein field equations for General Relativity.

$$\nabla \cdot \mathbf{B} = 0$$

$$\mathbf{F} = q\left(\frac{-1}{4\pi\varepsilon_0}\frac{Q}{r^2}\hat{\mathbf{r}}\right) = q\mathbf{E}$$

$$F = k\,\frac{Q_1 Q_2}{r^2}$$

$$k = 8.99 \times 10^{9}\,\frac{\mathrm{N\,m}^2}{\mathrm{C}^2}$$

nett Charge is a DIVERGENT field


k
μ_0
μ_0
μ_0
μ_0
$\varepsilon_0\left[\frac{\mathrm{Nm}}{\mathrm{KG}}\right]$
$\left[\frac{\mathrm{Nm}}{\mathrm{KG}}\right]^2$
$\left[\frac{\mathrm{Nm}}{\mathrm{KG}}\right]\varepsilon_0$
μ_0
μ_0
μ_0
μ_0
G

Gravity is a CONVERGENT field

$$\mathbf{F} = m\left(-G\frac{M}{r^2}\hat{\mathbf{r}}\right) = mg.$$

$$F = -G\,\frac{M_1 M_2}{r^2}$$

$$G = 6.67 \times 10^{-11}\,\frac{\mathrm{N\,m}^2}{\mathrm{kg}^2}$$

$$\nabla \times \mathbf{E}_g = -\frac{\partial \mathbf{B}_g}{\partial t}$$

GEM fields

are an accurate way of modelling Gravitational attraction between massive bodies using weak KEM field vectors

$$\nabla \cdot \mathbf{B}_g = 0$$

Gravitational fields can be modelled as weak convergent EM fields


128
36 divergent
36 divergent
[28-36]
p
16
p
[28-36]
28 convergent
28 convergent
[56-72]
attract/repel

Electrostatic fields

Charges attract or repel dependent on polarity
Neutral Matter is largely unaffected (equally repel & attract)


128
36 divergent
36 divergent
[36-28]
p
16
p
[36-28]
28 convergent
28 convergent
[72-56]
repel/attract


negative charge Matter
M


neutral charge Matter
M


positive charge Matter
M

Charged Matter INTERACTS electrically


36 divergent
36 divergent
[36-28]
g
0
g
[28-36]
28 convergent
28 convergent
64

All Matter ATTRACTS gravitationally


divergent energy momenta
k

interactive EM fields & attractive gravity
M

convergent force of gravity
G

Nett KEM field interaction is divergent from source
Gravitational attraction is the convergent mean force between two sources

Gravitational & Electric constants

are scaling constant relating Gravitational gradients to superpositioned EM fields

[1665]

Newton was the first to apply the Inverse Square law to Gravity

but was unaware of ElectroMagnetic forces

GEM

Gravito ElectroMagnetism

[1769]

Coulomb applied the Inverse Square Law to Charge Interactions

and obtained the value for the Electric Constant

Newton's convergent Gravity & Couolomb's Charge interaction
both follow inverse squared laws
(geometric means)

Attractive Gravity has the negative vector of nett Charge Interaction



Interactive EM fields are 20 orders of magnitude stronger than Gravity

'Graviton'
Gravitational 'charge' carrier



Convergent force vectors

superpositioned EM fields can be used to model the strength and direction of the weaker Graviational force vectors at any point in the fields as they are both inverse squared forces

Producing the ongoing speculation of the existence of a gravitational charge carrier

(an erroneous assumption that stems from using mathematics alone, without a solid understanding of geometric mass-energies & Matter topologies)

Photon
Electric charge carrier



Divergent force vectors

Newton's attractive Gravity & Coulomb's Charge interaction
both follow inverse square laws



Instantaneous
action-at-a-distance

The Force of Gravity

Absolute
Space & Time
(x,y,z) (t)

Gravitational action
limited to c

mass-ENERGY-Matter

Curved relativistic
Spacetime
(x,y,z,t)

Modelling Gravity with EM field geometries

while superpositioned EM fields can be used to model the strength and vector direction
of weaker Gravitational fields at any point in time within the field geometry
they DO NOT reflect the actual physicality of the fields involved

$$R_{00} = 4\pi\rho$$

The speed of Gravity is not limited to c as changes to the energy density-pressure gradient are immediately translated through the aether from one object to the other

$$R_{\mu\nu} - \tfrac{1}{2} R g_{\mu\nu} = \frac{8\pi G}{c^4} T_{\mu\nu}$$

Gravity is a the pressure gradient created by the displacement of vacuum energies though the presence of 3D mass-Matter topologies in any region of space

Fields of Interaction

All topological Matter in motion creates a interactive Kinetic EM field
in addition to its inherent convergent Gravitational field

Convergent Gravity fields produce a uni-directional attraction between two or more Matter topologies

Divergent EM fields produce a bi-directional interactive force between charged objects



interactive EM fields of force are created by geometrically superpositioned equilateral energy momenta vectors


S
Max
E
Max
p
p
0
N
Max

longitudinal energy momentaum vectors create instantaneous action-at-a-distance




M
M
G
$7.49 \times 10^{-11} \frac{N\,m^2}{kg^2}$
r^2

Gravitational fields of force are created by the displacement of vacuum energies by Matter topologies

Gravito-Electro-Magnetic
Fields


Q
Q
k
$8,99 \times 10^{9} \frac{N\,m^2}{kg^2}$
r^2

Copyright ABRAHAM [2008] - All rights reserved

GEM gradients

The gravitational field of Material objects is the result of zero energy nullspace volumes encompassed by all Matter which in turn creates a displacement energy pressure differential gradient with the surrounding Vacuum Energies

Gravitational attraction can be modelled as a CONVERGENT EM FIELD created by the nullspace differential of Matter

All Matter in motion creates an eternally dynamic system of Gravitational fields and radiative ElectroMagnetic Energies

EM radiation is a bidirectional DIVERGENT-CONVERGENT FIELD resulting from quanta imbalances

radiative EM fields are created by all Matter as it seeks equilibrium with its environment, the impedance of space creates a propagation velocity equal to the speed of light

convergent Gravitational fields



radiant interactive EM fields

Gravity and ElectroMagnetic fields



Newtonian Gravity

Gravity & Electro-Magnetic field strengths all converge to zero at the centre of the sphere

General Relativity

All EM fields and Matter are comprised of charged EM quanta

The total relativisitc energy of any object is the sum of its mass-Matter & Kinetic energies

All Matter seeks thermal equilibrium

All Matter in motion produces radiant [K]EM fields

Charges are Interactive

Gravimetric fields can be modelled as weak EM fields [space-time curvatures] created by Matter

Gravity is always attractive

Copyright ABRAHAM [2008] - All rights reserved

Electric vs Gravitational Fields

C

interactive electrostatic fields



Electrical interaction
is the result of the nett
EM geometry of [K]EM fields

Q

nett Divergent Field

In fields of charge
the nett divergent
field encloses the
convergent field



Gravitational fields are
always convergent
to the source of
the field

SR

Using Special relativity as the basis for the development of a General theory of Relativity to model Gravity is problematic

[as SR models EM interactions]

GR

strictly Convergent Field

KG



attractive gravitational fields

Gravitational attraction is
the result of the displacement
topology of Matter

M

Field	Units	Equation
Gravity	$\vec{g} = \frac{\text{newtons}}{\text{kilogram}} \left(\frac{N}{kg}\right)$	$\vec{F} = m\vec{g}$
Electricity	$\vec{E} = \frac{\text{newtons}}{\text{coulomb}} \left(\frac{N}{c}\right)$	$\vec{F} = q\vec{E}$

The similarities between Electro-Magnetic
and Gravitational fields can be shown by
modelling their effects through
EM field geometries

Tetryonics 66.01 - Electric vs. Gravitational fields

Electric fields and Gravitation





Electrostatic forces are much greater than Gravitational forces (by about 10^20 times).
The force of gravity is attractive for all Matter, whereas electrostatic forces are repulsive for like charged Matter,
There are no negative [repulsive] gravitational charges, while there are both positive and negative electric charges.

Electrostatic forces are interactive
while Gravitational forces are always attractive





Gravitational attraction has the opposite force vector of Electrostatic interaction





All ElectroMagnetic field quanta are subject to Lorentz wavelength-frequency corrections due to velocity

Gravitational Matter topologies are NOT affected by Lorentz corrections due to their velocity of motion



There are similarities between the Electric field and the Gravity field of Matter, (so sometimes Matter is refered to as "gravitational charge")

Both act in a vacuum and are central and conservative.
Both obey an inverse-square law (both are inversely proportional to square of r).
Both field types propagate at the finite speed of c, the speed of light.
Electric charges and EM mass-energies are conservative



Copyright ABRAHAM [2008] - All rights reserved

Charge vs Gravitation


[empirically determined value]
8.987551787e9 N
Q1
k
Q2
r2

"The magnitude of the electrostatic force between two charges is directly proportional to the product of the magnitudes of each charge and inversely proportional to the square of the distance between the charges."

Charge interaction can be modelled as a DIVERGENT EM FIELD

We have two fundamental laws stating that the forces between two particles are directly proportional to the product of their charges/masses and inversely proportional to the square of the distance between them

Gravitational attraction can be modelled as a CONVERGENT EM FIELD

"The magnitude of the gravitational force between two masses is directly proportional to the product of the magnitudes of each mass and inversely proportional to the square of the distance between the charges."


M1
G
M2
r2
6.67428e-11 N
[empirically determined value]

Coulombic interaction is proportional to Charge (energy geometry imbalances)

$$F = k\frac{Q_1Q_2}{r^2}$$


Q1
2.309004159 e-28 N
k
Q2
12
[12-0]
e+
1.2e20
G
k
12
[0-12]
e-
1.2e20
c4
M1
5.2259218643 e-71 N
G
M2

$$F = -G\frac{M_1M_2}{r^2}$$

Gravitational attraction is proportional to Matter (total rest EM mass-energy content)

*It can now be clearly demonstrated that **Newtonian Gravity** can be modelled as a weak convergent Electro-Magnetic Force*



$$\frac{k \quad 8.9875\ \text{e}9\ \text{N}}{G \quad 6.67384\ \text{e-}11\ \text{N}} = 1.346\ \text{e}20$$

The field strength differential is reflective of the Compton frequency of electron [1.20 e20 quanta]

Einstein's general relativity offers a different model of Gravitational attraction however

Gravito-Electro-Magnetic interaction

The ElectroMagnetic [Coulombic] field strength is proportional to an object's relativistic charge

$$F \propto \frac{Q_1Q_2}{r^2}$$

Charge interactions can be modelled as a superpositional DIVERGENT FORCE

$$F = k\frac{Q_1Q_2}{r^2}$$



equilateral mass-energy momenta quanta create the interactive fields of Force between material bodies of Matter

The attractive strength of Gravity is 20 orders of magnitude weaker than the strength of Electrostatic interaction

Gravitational attraction can be modelled as a superpositional CONVERGENT FORCE

$$F = -G\frac{M_1m_2}{r^2}$$

$$F \propto \frac{M_1m_2}{r^2}$$

Gravitational field strenth is proportional to the rest Matter topology (and can be modelled with weak coulombic fields)

Copyright ABRAHAM [2008] - All rights reserved

Charged Matter Gravitational interactions

**Electrostatic force fields dominate Gravitational fields
and can be modelled via their superpositioned
energy momenta force fields**

*Following the field symmetries
provided by Tetryonic geometry
we can now model all fields*

$$F = k\frac{Q_1 Q_2}{r^2}$$

2.30900415 e-28 Newtons

*Electromagnetic interactions
as well as the convergent
Gravitational atraction*



1.60217602 e -19 C

1.60217602 e -19 C

**Proton
Matter-charge
9.6577107 e7 C/kg**

**8.98755 e9
Nm/C²**

**7.489625 e-11
Nm/KG²**

**electron
Matter-charge
1.810820762 e11 C/kg**

1.659653693 e -27 KG

8.851486361 e -31 KG

*Reflecting all of the
geometric force interactions in terms of
EM mass-ENERGY & Matter*

1.10025594 e-67 Newtons

$$F = -G\frac{M_1 m_2}{r^2}$$

*Allowing an accurate value
of the graviationl constant
to be derived*

**Gravity [like electrostatic] fields
can be modelled as superpositioned
Energy momenta force fields**

The Gravitational Constant

The gravitational constant is a difficult physical constant to measure to high accuracy, in fact it was not measured until over seventy years after Newton's death by Henry Cavendish with his torsion beam experiment, performed in 1798

G

The gravitational constant is denoted by letter G,
it is an empirical physical constant involved in the calculation
of the gravitational force between two material bodies.

It usually appears in Sir Isaac Newton's law of universal gravity,
and in Albert Einstein's theory of general relativity.



He used a horizontal torsion beam with lead balls whose inertia (in relation to the torsion constant) he could tell by timing the beam's oscillation

The accuracy of the measured value of G has increased only modestly since the original Cavendish experiment

Henry Cavendish

(10 October 1731 – 24 February 1810)

Extreme care must be taken when attempting
to measure the strength of Gravitational attraction
to ensure that NO Electrostatic interaction
influences the experimental results

The attractive strength of Gravity
is 20 orders of magnitude weaker than
the strength of Electrostatic interaction

8.98755 e9 N

$$F = k\frac{Q_1 Q_2}{r^2}$$

It is also known as the universal gravitational constant,
Newton's constant, and colloquially as Big G.

g

It should not be confused with "little g" (g),
which is the local gravitational field
(equivalent to the free-fall acceleration),
especially that at the Earth's surface.

G

6.67384 e-11 N

$$F = -G\frac{M_1 m_2}{r^2}$$

Gravity has no established relation to other fundamental forces, so it does not appear possible to calculate it indirectly from other constants that can be measured more accurately, as is done in some other areas of physics

Fundamental field strengths

are the result of equilateral energy momenta geometries


magnetic dipole interaction
ε0
W
μ0
Weak


Bosons
1
3
5
7
9
11
13
15
1
4
16
25
36
49
64
1^2
2^2
3^2
4^2
5^2
6^2
7^2
8^2
n
Energy Levels
E
Photons


Strong
S
parallel charged fascia interaction

Force	Approximate Relative Strength	Range
Strong Nuclear	10^{38}	10^{-15}
ElectroMagnetic	10^{36}	Infinite
Weak	10^{2}	10^{-18}
Gravitational	1	infinite


Divergent Field
k
Electro Magnetic

All the field strengths of the fundamental interactions are a direct result of the interactions of their Tetryonic mass-energy goemetries and Tetryonic Matter topologies

m E M

geometries density topologies


Gravity
G
Convergent Field

(whilst Gravity can be modelled as a weak convergent Coulombic attraction its actual physics are the result of vacuum energy displacement by Matter topologies)

The Strength of the Gravitational Constant

Coulomb's Constant



[24-12]

Proton nett charge

1.60217646 e -19 C

equal (but opposite) nett Charges

[0-12]

Electron nett charge

1.60217646 e -19 C



8.987551787e9 N

CHARGED mass-energy geometries interact



Gravitational Matter topologies attract

7.489626483e-11 N



Newton's Constant

1.659653693 e -27 KG

Proton rest mass-Matter

[1.5e23-7.5e22]

1875

8.851486361 e -31 KG

electron rest mass-Matter

[1.2e20]

Although it provides a coherent and accurate model of all the motive forces & interactions present the modelling of Gravity with EM fields dces not account for the source, strength & unilateral direction of Gravitational fields

Tetryonics 66.08 - Strength of the Gravitational Constant

Tetryonic Matter interaction and Gravitation

Electrostatic convergence can serve as a model for Gravitational attraction

All Matter is comprised of EM mass-Energies

Q

Charged mass-energy geometries form Matter topologies

$$F = -G\frac{M_1 m_2}{r^2}$$

EM mass & Matter must be differentiated

Matter

$$\frac{4n\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

Planck quanta, mass, velocity

M

All Matter is gravitationally attractive

RE

All gravitational systems are comprised of Matter & KEM fields

Einstein's stress-energy tensor lumps all mass-Energy-matter together as a pressure gradient

$$F = k\frac{Q_1 Q_2}{r^2}$$

All Matter in motion posseses [K]EM fields

EM waves

$$\frac{\text{EVEN}\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

Planck quanta, mass, velocity

KE

All Matter radiates [K]EM mass-Energies



but in reality

Gravitational attraction results from the displacement of vacuum energies by Matter topologies

[The effects of stronger [K]EM fields can be excluded from the long distance attractive [gravitational] motion of material bodies to each other]

Modelling the force of Gravity

It is in many ways very similar to Coulomb's law of Interaction
between charged particles developed by Coulomb
(after Newton's Gravitation)



Gravity can be modelled as weak convergent EM field

For many people, it is easiest to picture gravity
as a kind of special invisible force,
emanating from ALL the Matter in the universe.
Newton's law of Gravity leads one to sees
it this way and it is probably the view
most of us were given when we learned
about gravity in elementary school.



However, there is another way
to model Gravity's effects.
It stems from Albert Einstein's
General theory of Relativity,
a theory that describes gravitation
as being the result of the curvature of
spacetime as a result of energy gradiant

Gravity can also be modelled as convergent pressure gradients







To understand what gravity really is you must have a clear understanding of the distinctions between radiant EM mass and standing-wave Matter and the various quantum interactions they produce.

Tetryonics provides a clear geometric definition and distinction between 2D radiant mass-energy geometries and 3D Matter topologies along with a new unified model of the mechanics of Universal Gravitation at all scales

radiant mass-energy geometries



'Action-at-a-Distance'

mass-energies

Planck quanta

$$\frac{n\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

**[K]EM mass-Energies
with QAM create interactive
divergent [and convergent]
charge geometries**

Newtonian Gravity

Toplogical mass is Matter



*All Matter contains nullspaces
and produces motional KEM fields*

standing-wave Matter toplogies



'Folded Space-Time'

Matter

Planck quanta

$$\frac{4n\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

**Tetryonic Matter creates
low pressure nullspace
resulting in convergent
Energy pressure gradients**

General Relativity

Instantaneous action-at-a-distance

Tetryonic QED theory shows that where the linear energy momentum of longitudinal waves align and act in a co-linear direction they can facilitate near instantanous action-at-a-distance

$$\sum \mathbf{F} = 0 \Rightarrow \frac{d\mathbf{v}}{dt} = 0$$

Free particles move with constant vector-velocity
(that is, with zero acceleration, unless acted upon by an outside force).

The Earth orbits the SUN where it is now about a common centre of gravity

'Action-at-a-Distance' and 'Instantaneous' forces were introduced into Physics within Newton's notion of absolute space and time

If the SUN were to vanish the Earth would cease traveling in its current elipical orbit immediately


F = ma
Instantaneous Forces
μ_0
μ_0
μ_0
μ_0
F
F
p
p
Action at a Distance
W = mad

$$\sum \mathbf{F} = \frac{d\mathbf{p}}{dt} = m\frac{d\mathbf{v}}{dt} + \mathbf{v}\frac{dm}{dt}$$

The vector-force on a particle equals the product of its mass by its vector acceleration

$$\mathbf{F} = m\mathbf{a} = \frac{\Delta \mathbf{p}}{\Delta t} = \Delta\left[\frac{m\mathbf{v}}{t}\right]$$


Δv
a
ODD number
bosons
SQUARE number
energy
Ω
m
hv
v²
c
normal distribution of photons
F
c²
Δt

The speed of gravity is limited to c

Einstein's GR theory replaces Newton's force of gravity and absolute space & time with a relativistic spacetime gradient curved by mass-energies

If the SUN were to vanish the Earth would continue traveling in its current orbit for 8⅓ minutes

The forces of action and reaction are equal and opposite;
(if a particle A exerts a force f on a particle B, then B exerts a force –f on A)

$$\sum \mathbf{F}_{a,b} = -\sum \mathbf{F}_{b,a}$$

Copyright ABRAHAM [2008] - All rights reserved

Newton's Gravitational Constant

$$F = -G \frac{M_1 m_2}{r^2}$$

According to Newton's law of universal gravitation,

the attractive force (F) between the centres of two bodies of mass-Matter, is proportional to the product of their Matter (M1 and m2), and inversely proportional to the square of the distance (r) between them

Long distance force

spacetime curvature

Newton's Gravitional Force models a motive force for gravitational acceleration



Einstein's General relativity has no motive force for gravitational accelerations

6.67384 e-11

$$\left[\frac{Nm}{kg}\right].\left[\frac{Nm}{kg}\right]$$

The gravitational force between two interacting bodies of Matter is

$4\pi G\rho$

$$\left[\frac{Nm^2}{kg^2}\right] = \left[kg\frac{m}{s^2}\frac{m^2}{kg^2}\right] = \left[\frac{m^3}{kg\,s^2}\right]$$

$8\pi G\rho$

Copyright ABRAHAM [2008] - All rights reserved

Action-at-a-Distance

All Matter creates KEM fields of energy momenta



All Matter creates a displacement of vacuum energies

radiant mass-energies INTERACT

Once established longitudinal EM fields between Matter form an 'inelastic rod' of energy momenta that can facilitate an instantaneous 'Action-at-a-Distance'

standing-wave Matter ATTRACTS



Energy momenta propagates at 'c' - ACTION moves instantaneously along established lines of longitudinal Electric Force

Any field of longitudinal energy momenta between Matter can facilitate instantaneous interactions including radiant EM fields and vacuum energies

Gravity is known as a Universal force of attraction between two objects that is proportional to their mass-Matter content

Newton's theory of gravity offered no prospect of identifying any mediator of gravitational interaction. His theory assumed that gravity acts instantaneously, regardless of distance.

Energy momenta creates universal motive forces

According to Albert Einstein's theory of special relativity, instantaneous action-at-a-distance was seen to violate the relativistic upper limit on speed of propagation of information.

If one of the interacting objects were to suddenly be displaced from its position, the other object would feel its influence instantaneously, meaning information had somehow been transmitted faster than the speed of light.

Gravity fields create a universal attractive field

Copyright ABRAHAM [2008] - All rights reserved

Gravitational Constant

The gravitational constant denoted by letter G, is an empirical physical constant involved in the calculation(s) of gravitational force between two bodies.
It appears in Sir Isaac Newton's law of universal gravitation, and in Albert Einstein's theory of general relativity.
It is also known as the universal gravitational constant, Newton's constant, and colloquially as Big G.

It should not be confused with "little g", which is the local gravitational field (equivalent to the free-fall acceleration), at the Earth's surface

Gravitational Forces
can be modelled

$6.67\ \text{e-}11\ \left[\frac{Nm}{kg}\right]^2$

linear Newton metres



$6.67\ \text{e-}11\ \left[\frac{E}{kg}\right]^2$

scalar Energy momentum

as the geometric MEAN of
superpositioned fields of gravitational energy

$$F = -G\,\frac{M_1\, m_2}{r^2}$$

The gravitational force between
two neutral interacting bodies is

N.m = Joules

$$\left[\frac{Nm}{kg}\right]\cdot\left[\frac{Nm}{kg}\right]$$

$[N.m/kg]^2 \sim [E/kg]^2$

Gravitational acceleration

Gravitational acceleration can be viewed as a reflection of the change in an object's momentum over time

$$\sum \mathbf{F} = \frac{d\mathbf{p}}{dt} = m\frac{d\mathbf{v}}{dt} + \mathbf{v}\frac{dm}{dt}$$

$$\frac{\left[\frac{m}{s}\right]}{s}$$

$$\vec{g} = \frac{\vec{F}_g}{m} = -G\frac{mM}{mr^2}\hat{r} = -\frac{GM}{r^2}\hat{r}$$

expressed vectorially the force is always ATTRACTIVE to the larger masss and acts in opposition to the KEM field's divergent momenta



F=ma

The force on a body acted upon by a Gravitational field is given by

$$g = G\frac{m}{r^2}$$

The greater the mass of a gravitating object the greater the acceleration due to the mass

The closer a body is to a the source of a Gravitational field the greater the acceleration due to the field

$$\left[\frac{N}{kg}\right] = \left[\frac{m}{s^2}\right] = \frac{\left[kg\,\frac{m}{s^2}\right]}{kg}$$

gravitational acceleration can be modelled as the convergent vector component of superpositioned EM fields

$$\left[\frac{Nm}{kg}\right]^2$$

The gravitational force between TWO neutral interacting bodies is

$$\left[\frac{Nm}{kg}\right]\cdot\left[\frac{Nm}{kg}\right]$$

Modelling Gravitational fields


convergent force
E
interactive forces
N
M
S
interactive forces
E
convergent force

The [K]EM fields of planetary bodies are the result of their mass-Matter density and motion in space

Gravity can be modelled as weak convergent force created by and acting between the mass-Matter in planetary bodies

Matter topologies displace vacuum energies creating Gravity



Weak KEM fields can accurately model Gravitational fields

Gravitational fields are the result of the displacement of vacuum energies by Matter topologies and the interactive energy momenta of their radiant KEM fields

$$F = k\,\frac{Q_1 Q_2}{r^2}$$


interactive forces
8.98755 e9
The elecinteractive orce created by two superpositioned KEM fields
$\left[\frac{Nm}{C}\right]^2$
[Nm]
k
superpositioned EM fields
G
[Nm]
$\left[\frac{Nm}{KG}\right]^2$
6.67384 e-11
The gravitational force between two neutral interacting bodies
attractive force

$$F = -G\,\frac{M_1 M_2}{r^2}$$

Copyright ABRAHAM [2008] - All rights reserved

Centres of Gravity

are determined by
the distribution of the combined
gravitational mass-Matter in a system


M
Centre of system
mass-Matter
Gravitational Matter
[The Sun]
Centre of
system Gravity
G
Gravitational Matter
[Mercury]
Centre of mass-Matter
[Mercury]
m
Centre of mass-Matter
[Sun]
c4

Any two massive bodies of Matter (be they Stars or Neutrinos) will orbit about their 'Centre of Gravity'

The term center of mass is often used interchangeably with center of gravity, but they are physically different concepts. They happen to coincide in a uniform gravitational field, but where gravity is not uniform, center of gravity refers to the mean location of the gravitational force acting on a body.

Electrostatic forces are many orders of magnitude greater than gravity & dominate nuclear interactions at the quantum scale


Q
0
[6-6]
ve
m
12
Centre of Matter
k
Centre of
Gravity
0
[6-6]
m
ve
12
Q
Electrostatic mass-Matter
[Neutrino]
Electrostatic mass-Matter
[Neutrino]
c4

Super-postioned EM fields
have c^4 geometries [c^2x c^2]

Copyright ABRAHAM [2008] - All rights reserved

$$F=ma$$

There are two quite distinct types of mass in Newton's theory of mechanics and gravitation.

(i) inertial mass, which occurs as the ratio between force and acceleration in Newton's second law
and thus measures a particle's resistance to acceleration, and

(ii) Gravitational mass, which may be regarded as the gravitational analog of electric charge,
and which occurs in Newton's Gravitational equation

$$F_g = -G\,\frac{m}{r^2}$$

Inertial mass
is a measure of the total
energy momenta geometries
of Matter topologies





All Gravitational Matter
has EM mass geometries in
its Matter topology



Inertial mass

results from constituent quanta
acting against (or with) any
Force applied to a mass

Often stated as the 'Principle of Equivalence'
on which General relativity is founded ,
it can be summarised as follows:

$$a = \frac{m}{m}\,g$$

*"Inertial mass and Gravitational mass
are equivalent"*

***whilst mass-energies contribute equally
to inertial & gravitational mass
it is Matter topologies that creates Gravity***

'Gravitational' mass

is seen as being the constituent quanta
of opposite charge polarity
attracting another particle's quanta

Discerning between the competing laws of Gravity

$$M + KE = RE$$

gravitational mass-Matter — *fields of force* — *relativisitic mass-energy densities*

At the heart of resolving the true nature of Gravity is the formal definitions of mass-Energy-Matter and the interplay between the various field interactions they produce and possess

Newton's view of gravity

Sir Isaac Newton described gravity as a force that attracts things possessing Matter

Sir Issac Newton

(25 December 1642 – 20 March 1727)

Gravity is an instantaneous 'Action-at-a-Distance' mediated by a means unknown

$$F = -G\frac{M_1 m_2}{r^2}$$

Newton taught that masses attract each other with a force inversly proportional to the distance between the masses.

Newton's idea was that planets are held in their orbits around the Sun by a force proprtional to the mass of the Sun and the planets, and that force is always pointing inwards (i.e. planets get pulled in the direction of the Sun, and the Sun gets pulled in the directions of the planets).

Newton said that a person standing on the Earth is being held to the Earth by a force due to the mass of the Earth and the mass of the person, and that force is always pointing inwards (i.e. a person gets pulled in the direction toward the center of the Earth, and the Earth gets pulled in the direction of that person).

Newton's and Einstein's view of gravity differ markedly

Einstein, on the other hand, taught that all things with mass (including the Sun, Earth, and the rest of the planets) create a energy density gradient that causes spacetime to curve and that this curvature is an alteration the geometry of spacetime.

The curvature casues Matter to move toward the center of the largest nearby mass. The closer to this mass the larger the degree of curvature in the local spacetime.

Additionally, Einstein taught that if there are no external forces acting upon an object (even those without any mass such as photons) then that object will simply follow its natural path (geodesic) through the altered geometry of the local spacetime - regardless of the degree of curvature of that local spacetime. This implies that if an object is somehow kept from following its natural path (geodesic) then a net force does exist and is measurable on that object.

Ricci curvature *scalar curvature* *Gravitational constant*

$$R_{\mu\nu} - \tfrac{1}{2}R g_{\mu\nu} = \frac{8\pi G}{c^4} T_{\mu\nu}$$

stress-energy tensor

spatial geometry

Einstein's view of gravity

Albert Einstein described gravity as a 3D curvature of spacetime caused by Matter

Albert Einstein

(14 March 1879 – 18 April 1955)

Matter and energy tell spacetime how to curve. Spacetime tells matter how to move

There is no doubt that both Sir Isaac Newton & Albert Einstein were both brilliant, their theories describing Universal Gravitation have remained at the fore for hundreds of years now.

However, a more accurate model of the Universal Gravitation is now at hand and its true nature is revealed via the Tetryonic geometry of EM mass-Energy-Matter and its associated field interactions. Tetryonic Gravitation demonstrates the validity of both approaches and reveals the true geometry behind the field interplays that result in the familiar force of Gravity

Copyright ABRAHAM [2008] - All rights reserved

The two models of Gravitation

Newtonian gravitation models the observed large-scale convergent force between all material bodies



Newtonian Gravitation
[modelled with weak KEM fields]

General Relativity
[Total EM Pressure Gradients]

General Relativity models the convergent pressure gradiant created by all forms of energy

While both models are very successful they both fail to reveal the quantum-scale geometries and topologies that give rise to universal gravitation

Theories of gravitation


G
attractive force

Newton viewed Gravitation as
an attractive FORCE of Matter
(inverse square field strength)

for the mechanics of gravitation
"I feign no Hypothesis"

"Gravity is the result of
curved spacetime"


P
pressure gradient

Einstein viewed it as the
curvature of 4D spacetime
(PRESSURE gradient)

$$F = -G\frac{M_1 M_2}{r^2}$$


G
6.67384 e-11
$\left[\frac{Nm}{KG}\right]^2$
Force
vs.
Pressure
M
M
$-\frac{8\pi G}{c^4}$
κ

$$G_{ab} = \kappa T_{\mu\nu}$$

Newton's formula based on observations maps only the observed nett force of gravitational attraction on large-scale Matter

Einstein's formula, attempted to correct observational discrepancies by mapping convergent G & divergent EM forces as a single pressure gradient

Both Newton and Einstein failed to define and distingush between mass-energy geometries & Matter topologies

Copyright ABRAHAM [2008] - All rights reserved

Newton's G vs Einstein GR

Both Newton and Einstein developed their gravitational models
from the observed motions of celestial bodies without any distinction
between mass and Matter or the quantum forces at work

Gravitational Matter

Newton maps Matter's gravitational attraction
[excluding any perturbations caused by [K]EM fields]

All mass-energies

Einstein's GR maps Newton's G & SR effects
[mass-energy momenta [K]EM interactions]

Φ | $g_{\mu\nu}$

F | $\Gamma^{\sigma}_{\mu\nu}$

$\nabla^2\Phi$ | $R_{\mu\nu}$

ρ | $T_{\mu\nu}$

Increasing accuracy in the measurements of the motions
of spacecraft interacting with planetary bodies [using EM waves]
has resulted in the need for refinement of both theories

Einstein's doubling of Newton's gravitational constant
was done to fit later observed perturbations in
Mercury's orbital mechanics

Newtonian G field

Any valid tests of the purely gravitational fields of Matter
must exclude KEM fields and not use EM masses to test it

$$[\text{Newton}] = \frac{4\pi GMm}{r^2}$$

$$\nabla^2\Phi = 4\pi G\rho$$

Poisson

$$[\text{Einstein}] = \frac{8\pi GT_{\mu\nu}}{c^4}$$

Copyright ABRAHAM [2008] - All rights reserved

Pressure gradients and GR

Tensor mathematics is utilised in General relativity to model mass-energy geometries and energy pressure gradients as curved spacetime

$$F = -G\frac{M_1}{r^2}$$

Newton's Gravitational fields are modelled on the observed motions of large-scale Matter attraction

$$G_{ab} = \kappa T_{\mu\nu}$$

Einstein's GR gradients corrects Newtonian gravity by modelling all forms of EM mass-Energy momenta



At all scales of physics
the convergent EM energy momenta of K[EM] fields
forms part of the convergent force of universal gravitation

standing-wave Matter topologies

radiant mass-energy momenta geometries

$P \ll \rho$

At the quantum level KEM mass-energy densities
overwhelm the vacuum pressure gradients
created by Matter topologies

Newtonian G field

4π

Einstein's G field

8π

G

K

Vector Force
between Matter

Pressure gradient
per unit Volume

$$n\pi\rho = \underset{\text{geometries}}{n\pi}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\underset{\text{velocity}}{\overset{\text{quanta}}{v^2}}\right]\right] = T_{\mu\nu}$$

representive of ALL the mass-energy momenta of any spatial volume

Stress energy-pressure gradiants

are the result of Tetryonic charge geometries & topologies

$$\overset{\text{mass}}{\frac{n\pi}{c^2}}\left[\left[\underset{\text{mass}}{m}\,\overset{\text{Planck}}{\Omega}\,\overset{\text{quanta}}{\underset{\text{velocity}}{v^2}}\right]\right]$$

Radiant mass-energies have planar energy geometries

$n\pi$	**Energy quanta**
EVENπ	**photons**
ODDπ	**bosons**
4π	**tetryons**
12π	**quarks**
12π	**leptons**
24π	**mesons**
36π	**Baryons**

All Matter topologies are tetrahedral standing-wave mass-energy geometries

$$\overset{\text{Matter}}{\frac{T\pi}{c^4}}\left[\left[\underset{\text{mass}}{m}\,\overset{\text{Planck}}{\Omega}\,\overset{\text{quanta}}{\underset{\text{velocity}}{v^2}}\right]\right]$$



On the non-quantum scale all Matter topologies can be generalised and mathematically modelled as SPHERICAL 4π mass-energy topologies

radiated [K]EM fields
have interactive energy momenta
[convergent & divergent]

fields of Force

KEM



M

standing-wave topologies

displace vacuum energies
creating convergent Gravity

$$\underset{\text{stress energies}}{\overset{\text{relativistic mass-energies}}{RE}} = \underset{\text{topologies}}{\overset{\text{standing-wave Matter}}{M}} + \underset{\text{geometries}}{\overset{\text{radiant mass-energies}}{KEM}}$$

Stress Energy tensor

In the Einstein field equations [EFE] of general relativity, the stress-energy tensor is the source of gravitational mass just as Matter is the source of such a field in Newtonian gravity

$$T_{\mu\nu}$$

In Einstein's general relativity,
the symmetric stress-energy tensor
acts as the source of spacetime curvature

mass *ENERGY* *Matter*

m E M

geometries *momenta* *topologies*

Matter

Planck quanta

$$\frac{4n\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

The Tetryonic unified field equation
models all mass-ENERGY geometries
& Matter topologies

A recognised problem in General Relativity is that
the stress tensor models all forms of mass-energy-Matter
in the form of a generalised stress energy pressure gradient
but fails to differentiate between either mass or Matter
and their resulting interactions within the fields



Planck quanta

$$n\pi\left[m\Omega v^2\right]$$

mass velocity

radiant mass-energies
create interactive
fields of force



$$T\pi[\rho]$$

standing-wave Matter
creates vacuum energy
pressure gradients

Gravimetric topologies

Charges create radiant mass-energy geometries & standing-wave Matter topologies

kg

2D mass geometries

EM mass is not Matter

$$\frac{\overset{\text{mass}}{n\pi}}{c^2}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

Charged energy geometries are the basis for 2D mass

Photons have mass-energy momenta geometries but no Matter topology


4
[4-0]
0
[2/2]
gluons
4
tetryons
0
[2/2]
4
[0-4]
0
[6-6]
u
8
[10-2]
12
[12-0]
neutrinos
leptons
12
quarks
dodecyons
4
[8-4]
d
u
8
[2-10]
12
[0-12]
4
[4-8]
d

2D mass-energy geometries form surface integral areas of charged Matter topologies


u
u
0
[12-12]
pions
24
mesons
d
d
12
[24-12]
P⁺
0
[18-18]
N⁰
Protons
36
Baryons
Neutrons
N̄⁰
0
[18-18]
P⁻
12
[12-24]

KG

3D Matter topologies

Matter has mass energies

$$\frac{\overset{\text{Matter}}{T\pi}}{c^4}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$


84
[42-42]
N⁰
e⁻
P⁺
M
45,012
c⁴

Charged mass-energy topologies are the basis for 3D Matter

Its topology forms a quantum Faraday cage [with a charged surface integral of mass-energies]

Copyright ABRAHAM [2008] - All rights reserved

Interactive mass-energies vs. gravitational Matter

energy in all its forms seeks equilibrium






Opposites Attract
Similars Repel





radiant mass-energy geometries


4π
ε_0
ε_0
ε_0

mass
$$\frac{n\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$
Planck quanta
mass velocity



the failure to define and differentiate between mass-energy geometries & Matter topologies is a failing of all modern physics theories

Matter
$$\frac{T\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$
Planck quanta
mass velocity

standing-wave Matter topologies

Charged Planck quanta of mass-energy momenta that form topologies displace the vacuum energies surrounding them in turn creating a mass-energy-Matter pressure gradient

Compton frequency of rest Matter is what creates inertial mass, its Gravitational Matter results from its charged topology

The integral inductive EM mass-energy momenta in Matter fascia create the physical property of inertial mass


12
[42-30]
40π
N0
P+
4.5e23


0
[42-42]
N0
e-
52π
P+
4.5024e23

$$F_z = \Delta P.\Delta A$$

Pressure is the force per unit area
applied in a direction perpendicular to the surface of an object



The theory of general relativity uses a stress-energy tensor to reflect to the pressure differentials created by Energy in ALL its forms (making no distinction between EM masses & Matter)

In Tetryonics the stress energy tensor is expanded, through geometric terms, to diferentiate between radiant mass-energy interactions and Matter topologies in radial spatial co-ordinate systems defined by the speed of light

Radiant EM masses

mass

$$\frac{n\pi}{c^2}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

Photons are often referred to as 'massless particles' are better defined as Matterless EM mass-energy momenta

Photons

$$\frac{2\pi}{c^2}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

interactive mass-energy momenta geometries

Energy Pressure gradients

The vacuum energy pressure gradient created by the charged topology of Matter is distinct from its intrinsic & radiative mass-energy geometries



Any theory of gravitation that attempts to model it on any scale must account for energy in all its forms

Standing-wave Matter

Matter

$$\frac{T\pi}{c^4}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

Tetryons, the quantum building blocks of Matter have EM mass-energy topologies that create a vaccum pressure gradient



Tetryons

$$\frac{4\pi}{c^4}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

gravitational Matter topologies

Convergent mass-energies & Gravitational Matter

m

Spacetime curvature

$$R_{\mu\nu} - \frac{1}{2}R g_{\mu\nu} = \frac{8\pi G}{c^4} T_{\mu\nu}$$

Stress-Energy Tensor

M

The concept of mass in general relativity (GR) is more complex than the concept of mass in special relativity. In fact, general relativity does not offer a single definition for the term mass, but offers several different definitions which are applicable under different circumstances.

Komar mass **Bondi mass** **ADM mass**

Under some circumstances, the mass or Matter components of a system may not even be defined



Einstein Field equation

Spacetime curvature

gravitation

constant

total mass-energy-Matter

Planck quanta

mass velocity

$$R_{\mu\nu} - \frac{1}{2}R g_{\mu\nu} = K \frac{n\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

per spatial volume

Tetryonic geometries & topologies



In contrast Tetryonic field equations explicitly differentiate all EM mass-energies and Matter via their charged geometries along with their contributions to the total energy density of any spatial region

GR models the convergent force of gravitation as a convergent energy density pressure gradient created by mass-energies

gravitational interactive stress

$$M + kEM = U$$

mass-Matter mass-energies energies

Tetryonics models gravitation as the result of mass-energy interactions AND Matter topology displacement of vacuum energies

Interactive EM force fields are subject to Lorentz velocity corrections

Faraday

$$\mathcal{E} = -\frac{d\Phi_B}{dt},$$

$$|\mathcal{E}| = N\left|\frac{d\Phi_B}{dt}\right|$$

Maxwell

$$\oint \vec{E}\cdot d\vec{s} = -\frac{d\Phi_B}{dt}$$

$$\oint \vec{E}\cdot d\vec{A} = \frac{q}{\varepsilon_0}$$

$$\oint \vec{B}\cdot d\vec{A} = 0$$

$$\oint \vec{B}\cdot d\vec{s} = \mu_0 i + \frac{1}{c^2}\frac{\partial}{\partial t}\int \vec{E}\cdot d\vec{A}$$

Special Relativity was developed from the foundation of Lorentz corrections to EM fields


E & M
EM
v
p
β
inductive EM
bosons
equilateral
energies
m
γ
γ
M
hv
v²
c
wave-length [γ]
contractions
[ΔQAM] time
dilation
β²
c⁴
SR
seconds²
GR

General Relativity was developed from Special Relativity and incorporates EM field interactions



Lorentz

$$L = L'\sqrt{1-\frac{v^2}{c^2}}$$

$$t' = \frac{t}{\sqrt{1-\frac{v^2}{c^2}}}$$



Einstein

$$G_{\mu\nu} = 8\pi G T_{\mu\nu}$$

$$E = \frac{mc^2}{\sqrt{1-\frac{v^2}{c^2}}}$$

Standing-wave Matter topologies are Lorentz invariant

the failure to differentiate between mass & Matter has lead to major misconceptions in physics

Copyright ABRAHAM [2008] - All rights reserved

Tensor Rankings

Rank 0

scalars

A tensor may consist of a single number, in which case it is referred to as a tensor of order zero, or simply a scalar

An example of a scalar would be the EM mass-energy of a particle or field

A second example of a scalar field would be the value of the gravitational potential energy as a function of position

Rank 1

The next most complicated tensor is the tensor of order one, otherwise known as a vector.

vectors

A vector can be defined as a direction between two points, its strength may vary continuously from point-to-point, thereby defining a vector field

Next above a vector are tensors of order 2, which are often referred to as matrices.

Rank 2

mass-energy momenta

A tensor of rank 2 is defined as a system that has a magnitude and two associated vector directions within the fields that it describes

Rank 3



curved spacetime

Rank 4 Tensors as used in Einstein's General Theory of Relativity, describe the curvature of spacetime [the so-called Riemann curvature tensor].

Tetryonic Matrices



EM fields can be represented by Tetryonic Matrices [Tensors] identical to current square Tensor Matrices with the only difference being the change in the geometry of the matrix to better reflect the true geometry of EM fields

This better facilitates the easy recognition of Electric & Magnetic scalar fields and their associated energy-momenta vectors

Rank 4



mass-Matter topology

the total mass-energies of Matter & fields thatcontribute to creating gravity.

Tetryonics 69.02 - Tensor rankings

ElectroMagnetic field tensor

The electromagnetic tensor or electromagnetic field tensor (sometimes called the field strength tensor, Faraday tensor or Maxwell bivector) is a mathematical object that describes the electromagnetic field of a physical system in Maxwell's theory of electromagnetism

Energy

$$2\pi\left[\frac{1}{c^2}\cdot\left[m\Omega v^2\right]\right]$$

Photons momenta

Photons

Planck quanta

$$\frac{2\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

Visualising EM waves and photons in terms of their Tetryonic geometry the scalar relationships between Electric and Magnetic fields becomes readily apparent.

$$F^{\mu\nu} = -F^{\nu\mu}$$

photons are their own anti-particles

A EM field tensor has six degrees of freedom, representing the three components of each of the electric and magnetic fields

$$c = \frac{1}{\sqrt{\mu_0\varepsilon_0}}$$

Speed of Light

EM wave factors such as Lorentz's velocity corrections arise naturally from the geometry providing a clear and concise illustration of the relationships between EM mass-energies, Charge, Electric & Magnetic fields and the speed of Light

Wavelength contraction

$$L = L'\sqrt{1-\frac{v^2}{c^2}}$$

speed of Light

$$c = \left[\left[\frac{c^2}{\Omega}\right]\cdot\left[\frac{\Omega}{c}\right]\right]$$

velocity of propagation

f Frequency

λ Wavelength



$$\vec{\nabla}\cdot\vec{B} = 0$$

$$\vec{\nabla}\cdot\vec{E} = \frac{\rho}{\epsilon_0}$$

$$\vec{\nabla}\cdot\vec{E} = \frac{\rho}{\epsilon_0}$$

$$\beta^2 = \left[\frac{v^2}{c^2}\right]$$

Scalar correction factor

Linear correction factor

$$\beta = \left[\frac{v}{c}\right]$$

$$p = \frac{h}{\lambda} = \frac{E}{c}$$

Linear Momentum

$$\varepsilon_0\mu_0 = \frac{1}{c^2}$$

EM Fields

$$\frac{\partial\vec{B}}{\partial t} + \vec{\nabla}\times\vec{E} = 0$$

the change of the magnetic field with respect to time plus the curl of the electric field is equal to zero

$$\vec{\nabla}\times\vec{B} - \frac{1}{c^2}\frac{\partial\vec{E}}{\partial t} = \mu_0\vec{J}$$

The curl of the magnetic field vector minus the change of the electric field with respect to time, is equal to the field's current density

$$\det(F) = \frac{1}{c^2}\left(\vec{B}\cdot\vec{E}\right)^2$$

the electromagnetic tensor may also be written in terms of the 4-vector potential

3D space time

$$[\Delta x, \Delta y, \Delta z] \quad \Delta\tau$$

In Tetryonics, the relativistic Four vector reflects the changing quantised angular momenta [time] of EM mass-energies & Matter in 3D space



$$M_0 + KE = E$$

Standing-wave four-vector

Lorentz corrected mass-energies

Stress energy momenta tensor

Relativistic Four-vectors

Charged Matter interacts at-a-distance through super-positioned energy momenta fields from which our force constants are derived

The electromagnetic four-potential is a potential from which electromagnetic field can be derived. It combines both the electric scalar potential and the magnetic vector potential into a single space-time four-vector



Inverse sqaured Gravity can be mathematically modeled using the same geometry explaining the similar formulations for charge interaction & gravitation

$$m^2v^4 = KE^2 = p^2v^2$$

EM mass

radiant energies

momenta

Four-vectors are reflective of the total EM mass-energy momenta of superpositioned [K]EM fields where the KE is the interactive force component

Special and General relativity

General relativity was developed by Einstein in an attempt to describe the acceleration forces experienced by graviational Matter (on the foundation of special relativity) which in turn was an extension of Lorentz corrections of EM waves developed to account for the fixed speed of light and established Newtonian mechanics

SR

Special Relativity

(describes inertial frames of reference
in flat Euclidean spacetime)

mass-energy

mass

$$\frac{n\pi}{c^2}\left[\left[\underset{\text{mass}}{m}\,\overset{\text{Planck}}{\Omega}\,\overset{\text{quanta}}{\underset{\text{velocity}}{v^2}}\right]\right]$$

geometries

GR

General Relativity

(describes accelerating frames of reference
in curved Riemannian spacetime)

Matter

Matter

$$\frac{4n\pi}{c^4}\left[\left[\underset{\text{mass}}{m}\,\overset{\text{Planck}}{\Omega}\,\overset{\text{quanta}}{\underset{\text{velocity}}{v^2}}\right]\right]$$

topologies



2D



3D



all physical theories to date have failed to explain the mechanics of gravitation at all scales of energy and distance

$$\frac{\rho}{m^2}$$

6.629432351 e-34 J

ENERGY

$$n\pi\left[\left[\underset{\text{mass}}{m}\,\overset{\text{Planck}}{\Omega}\,\overset{\text{quanta}}{\underset{\text{velocity}}{v^2}}\right]\right]$$

7.376238376 e-51 kg

$$\frac{\rho}{m^3}$$

The Weak Equivalence Principle

$$m_g . a = m_i . g$$

Newton

The uniqueness of free fall states than any two test bodies must fall with the same acceleration in a given external gravitational field

$$m_g = m_i \sum_A \eta^A \frac{E^A}{c^2}$$

Einstein

The uniqueness of free fall trajectories allows one to regard spacetime as filled being with curved energy gradients

$$F = ma$$

↑ **divergent FORCE**



convergent FORCE ↓

$$F = mg$$



acceleration vs inertial mass

'There is no way of distinguishing between the effects on an observer of a uniform gravitational field and that of constant acceleration'

Inertial and Gravitational masses are equivalent

Of particular note is the fact that the relativistic formulation of the weak equivalence principle hints at the fact that mass-energies in all their forms must be accounted for and correctly modeled for an accurate picture of the mechanics of gravitiation on all-scales to be developed



acceleration vs gravitational mass

Copyright ABRAHAM [2008] - All rights reserved

Einstein's Gravitational Constant

Newton gave a law for the behavior of objects that experienced gravitational forces:
$F = ma$, where $F = -m\nabla\phi$ for a given gravitational field ϕ

And along with Gauss & Poisson also gave a law determining how φ is generated:
$\nabla^2\phi = 4\pi G\rho$.

Einstein subsiquently re-expressed Newtonian Gravitation as a curvation of spacetime brought about by the presence of all mass-Energies

$$G_{ab} = \kappa T_{\mu\nu}$$

General Relativity

spactime curvature — *Gravitational constant* — *stress energies*

$$G_{ab} = \frac{8\pi G}{c^4} T_{\mu\nu}$$

speed of light

Einstein viewed gravitation as the result of a curvature of spacetime created by a mass-energy-pressure gradiant

EM

2D euclidean mass-energy-momenta

Rank 2 tensors

convergent & divergent forces

$$m = \frac{\rho}{c^2}$$

$$n\pi[mEM]$$

Tetryonic charged geometries

Gravitational Matter topologies — *Interactive mass-energy geometries*

$$T\pi\left[\frac{\rho}{c^4}\right] + n\pi\left[\frac{\rho}{c^2}\right]^2$$

3D spatial region — *2D spatial fields*

Tetryonics differentiates between Matter & interactive mass-energies via their charged geometries and topologies

M

3D mass-Matter topologies

Rank 4 tensors

convergent pressure gradient

$$M = \frac{\rho}{c^4}$$



$$G_{ab} = \frac{8\pi G}{c^4} T_{\mu\nu}$$

An explanation for all three formulations of Gravity must be derived from Tetryonic charge geometries

By modeling all mass-energy geometries and Matter topologies as a stress energy tensor General Relativity fails to differentiate between the interactive Forces of mass-energy momenta and gravitational Matter

mass-energy-Matter spatial interactions

**No two Fermions [3D Matter topologies]
can occupy the same physical space
at the same time - Pauli exclusion**





c^4

is a volumetric measure
of the amount of space
taken up by Matter

Fermions

Planck quanta

$$\frac{4n\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity


μ
μ
M
KE^2
M
c^4
c^4
μ
μ
$c^2 \cdot c^2$
c^4

c^4

is also a spatial measure
of two superpositioned
interactive KEM fields

Force interaction

Planck quanta

$$\frac{2\pi}{c^2}\cdot\frac{2\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity


v
Ω
RE
μ
KE
ρ
c^2
m
μ
KE
v^2
v

**All separated particles
interact with each other via 2D fields of Force
(superpositioned [K]EM fields)**


v^2
KE
m
μ
v
ρ
KE
c^2
μ
Ω
RE
v

Tetryonics 69.08 - mass-energy-Matter spatial interactions



SR

Special relativity applies
Lorentz velocity corrections to
radiant mass-energy momenta



GR

General relativity applies SR
to total energy momenta
density-pressure gradients



Otto von Guericke, (1602-1686), a German physicist, performed a famous experiment: the "Magdeburg Hemispheres".

When two halves of a large, hollow metal ball had all the air removed from the volume they created when joined, two teams of horses couldn't pull them apart, because the pressure of the Earth's atmosphere (external to the volume created) exerted a very large force on the ball as it sought to equalise the pressure gradient created.

Nullspace energy pressure gradients

mass-energy geometries

$$P = \frac{\text{Force}}{\text{Area}} = \frac{F}{A} \Rightarrow \frac{F.d}{A.d} \Leftarrow \frac{W}{V} = \frac{\text{Energy}}{\text{Volume}} = U$$

mass-Matter topologies

The scalar mass-energies of all Matter topologies are all contained in their charged fascia



$$n\pi\left[\frac{\rho}{c^2}\right]$$



$$T\pi\left[\frac{\rho}{c^4}\right]$$



A Faraday cage is a metallic enclosure that prevents the entry or escape of an electromagnetic field (EM field)

All Matter topologies are ideal Faraday cages, quantum standing-waves of EM mass-energies that in turn create regions of nullspace

An ideal quantum Faraday cage consists of an unbroken, perfectly conducting shell. (a Matter topology of scalar mass-energies)

Copyright ABRAHAM [2008] - All rights reserved

Total stress energies & Matter

The stress energy tensor can be regarded only as a provisional means of representing all of the interactive mass-energies & gravitational Matter in any physical system.

$$T_{\mu\nu}$$

GR's Stress Energy Tensor
does NOT differentiate
between EM mass & Matter

Einstein

It is only in present circumstances that we find we have insufficient knowledge of the electromagnetic field of concentrated charges that compels us, provisionally, to leave, undetermined in present theory, the true form of this tensor...

The right hand side the EFE is a formal condensation of all things whose comprehension in the sense of a field theory is still problematic.

Not for a moment... did I doubt that this formulation was merely a makeshift in order to give the general principle of relativity a preliminary closed form expression.

For it was essentially no more than a theory of the gravitational field, which was isolated somewhat artificially from a total field of as yet unknown structure.

Abraham

$$\overset{\text{mass}}{\frac{n\pi}{c^{2}}}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^{2}}\right]\right]$$

$$\overset{\text{ENERGY}}{n\pi}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^{2}}\right]\right]$$

$$\overset{\text{Matter}}{\frac{T\pi}{c^{4}}}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^{2}}\right]\right]$$


Q
All Matter is comprised of EM mass-Energies
10,080
[5,040-5,040]
All gravitational systems have Matter & KEM fields components
Ub
312.5885
RE
convergent
convergent
divergent
7,036,992
[5.1906532044e-25 KG]
M
All Matter is gravitationally attractive
1,635,552
[67.675 GeV]
All Matter radiates (K)EM mass-Energies
KE
c^4

changing quantised angular momenta creates charge~Time

3D MATTER topologies displace vacuum energies creating Gravity

Vacuum energies are formed from weak radiated mass-energies

changing linear momentum creates forces of Acceleration

radiant 2D planar mass-ENERGIES create interactive forces

KEM field energy momenta create fields of interactive Force

Tetryonics 69.10 - Total stress energies & Matter

Copyright ABRAHAM [2008] - All rights reserved

Einstein's Field Equation



"Spacetime tells Matter how to move; Matter tells spacetime how to curve"
John Archibald Wheeler

$$R_{ab} - \frac{1}{2} R g_{ab} = \frac{8\pi G}{c^4} T_{\mu\nu}$$

The solutions of the Einstein field equations are metrics of spacetime



General Relativity was developed to account for the observed perihilion precession of Mercury's orbit around the SUN
[only noticable through detailed observations after Newton developed his law of universal gravitation]

Newtonian G field

$$4\pi$$

the scalar curvature

the cosmological constant

Newton's gravitational constant

Ricci curvature tensor

$$R_{ab} - \frac{1}{2} g_{ab} R + \Lambda g_{ab} = \frac{8\pi G}{c^4} T_{\mu\nu}$$

the stress-energy tensor

the metric tensor

the spatial region of mass-energy-Matter being measured
as determined by the speed of Energy in vacuum

The EFE is a tensor equation relating a set of symmetric 4 x 4 tensors. Each tensor has 10 independent components

Einstein's G field

$$8\pi$$

The EFE (based on SR principles) reduces to Newton's law of gravitation where the radiant mass-energy fields are weak and velocities are much less than the speed of light
[highlighting the inability of GR to distingush between radiant mass-energy geometries & the standing-wave Matter topologies comprising the total energies within the stress Energy tensor]



Curved Spacetime

Einstein's gravitational constant

$$G_{ab} + \Lambda g_{ab} = K T_{\mu\nu}$$

the cosmological constant

mass-ENERGY-Matter

Despite the successes of General Relativity, the problems of quantum gravity and spacetime singularities remain open problems in its formulation of curved spacetime geometries

ZPF

All Energies are quantised

Quantum theory

m

Gravitation is Universal

Newtonian Mechanics

M

Gravity results from curved spacetime



Relativity theory

VE

Quantum gravity is the effort in theoretical physics to create a theory that includes both general relativity and the standard model of particle physics. Currently, these two theories describe different scales of nature and attempts to explore the scale where they overlap yield results that don't quite make sense, like the force of gravity (or curvature of spacetime) becoming infinite.

Euclidean quantum gravity
Scalar theories
Modified Newtonian dynamics (MOND)
Einstein-Cartan Bimetric theories
Tensor-vector-scalar
DGP model
Geometrodynamics
Loop Quantum Gravity
Lovelock theory
Kaluza-Klein theory
Induced gravity
Canonical Quantum Gravity
Jackiw-Teitelboim gravity
Liouville gravity

Quantum gravity

String theory
Composite gravity
Causal Set theory
Brans-Dicke
Massive gravity

Gravity as it is currently understood cannot be reconciled with the laws of quantum mechanics.

Causal dynamical triangulation
Teleparallelism
Scalar-tensor-vector
2+1D topological gravity
Gauss-Bonnet gravity
Supergravity
Conformal gravity
Nonsymmetric gravitation
Gauge theory gravity
f(R) gravity
Unified theory

hv
1899
Planck's law

Q
1785
Couolomb's law

G
1686
Newton's law of Gravitation

SR
1905
Special relativity

GR
1915
General relativity

Copyright ABRAHAM [2008] - All rights reserved

Without the aid of Tetryonic's charged geometries
Gravitational & EM fields point to mathematical singularities


c²
Q
RE
S
a singularity is a point in space
E
0
E Max
c
v
where all GEM fields converge to zero
N
M
KE
c⁴

Inverse squared
Electric fields produce
INTERACTIVE
fields of force

Inverse squared
Magnetic fields produce
PURTURBATIVE
fields of force

There are NO
Black Holes

There are NO
point Particles

Matter produces
CONVERGENT
inverse squared fields
of Gravity

Gravitation is the nett
convergent force
produced by all
G-E-M fields

GravitoElectroMagnetic fields

Matter topologies and gravity

the positive spatial displacements created by tetrahedral standing-wave mass-energies displace vacuum energies found in those regions to create a energy density pressure gradient

A convergent Gravity field is the result of the higher density-pressure vacuum energies in any spatial region seeking to equalise the lower pressure regions of nullspace within Matter topologies

Matter has a
Tetrahedral mass-energy
quantum topology
[non-Spherical]

M

The mass-energies
of Matter topologies
are stored in the integral
surface area geometries
of their charged fascia



Gravity itself is
the result of vacuum
energy pressure gradients
not Coloumbic fields

G

Gravitation is the
result of the convergent
gravity AND interactive
[k]EM fields that all quantum
Matter topologies create

The resultant density-pressure gradients created by the displacement of vacuum energies by Matter topologies can be modelled using equilateral EM field geometries and a reduced Coloumb constant

Spatial displacement of GEM energies by Matter topologies

The positive 4nπ displacement of vacuum eneriges by Matter topologies creates

Spatial energy density-pressure

$$F = -G\frac{M_1 m_2}{r^2}$$

Planets orbit
around the SUN

Newtonian fields models the resultant attraction as gravity

EM fields accelerate
charged Matter

$$F = k\frac{Q_1 Q_2}{r^2}$$



$$G_{ab} = 8\pi G T_{\mu\nu}$$

All EM mass & Matter
create stress energies

Einstein models the GEM energy densities as curved spacetime

Orbital precessions
must be accounted for

Newton	Einstein
4π vs.	8π
G	G+SR

Convergent Gravitational fields

Copyright ABRAHAM [2008] - All rights reserved

Newtonian Gravity

model the observed, long range attraction between two bodies of Matter
[exclusive of the close range electromagnetic interactions of each body]

A gravity field is produced by the charged topology of mass-Matter as it displaces vacuum energies and creates intrisic nullspace energy differentials

The strength of a Gravity field produced by Matter is proportional to the total EM mass-energy geometry/topology of any body and its convergent force can be modelled with equilateral Tetryonic geometries



Single Body
Gravitational Field

$$F = -G\frac{M_1}{r^2}$$

Single Body
Gravitational Field

$$F = -G\frac{m_2}{r^2}$$

Two Body
Gravitational Field

$$F = -G\frac{M_1 m_2}{r^2}$$

However, unless it is at absolute zero all Matter topologies produce interactive EM fields that contribute to gravitational forces as evidenced with the perihelion of Mercury where later observations revealed inaccuracies in Newton's formulation for the motion of material bodies subject to convergent G forces & interactive EM fields

Copyright ABRAHAM [2008] - All rights reserved

Gravitational energies as a geometric mean

the geometric mean of two numbers is the square root of their product

EM standing waves
[Matter] can be
created and destroyed

Sir Issac Newton was the first to realise that gravity could be modelled as an inverse square Force

EM mass-energies
can be neither
created or destroyed

$$F = -G \frac{M_1 m_2}{r^2}$$

M

E

The Force of Gravity
can be accurately modelled

Gravitational field of mass-Matter only

$$F_G = 4\pi G \rho$$

[ignoring EM interactions]



M_1
G^2
convergent
inverse square interaction
square root of superpositioned
mass ENERGY-Matter fields
m_2

Gravitational energy of Matter in motion

$$G_{ab} = 8\pi G T_{\mu\nu}$$

[including KEM field interactions]

$$F_G = \frac{M_1 \cdot m_2}{r^2}$$

as the convergent geometric MEAN of interactive superpositioned E-fields that represent the total mass-energies of the gravitational Matter

$$F_G = \sqrt{M_1 \cdot m_2}$$

Gravity is the result of spatial energy density differentials created by the internal null-space volumes of Matter.
Energy (in all its forms) will seek to fill areas of lower pressure in search of universal equilbrium

Newton modelled the
attractive forces between
objects of Matter

Matter topologies are non-conservative and as they are destroyed
the low pressure nullspace gradient [convergent gravitational Force] they created
is replaced with conservative forms of radiative EM energy [interactive vacuum energies-photons]

GR models the
energy density created
by mass-Matter

Gravitational Tidal Forces

The tidal force is a secondary effect of the force of gravity resulting from the geometry of massive bodies attracting each other.

Its geometric effects allow acceleration fields to be distingushed from pure graviation fields



Over a small area on the surface of a Gravitating body, gravitational attraction is often modelled as a uniform field acting downwards across the whole area.

The Gravity of a material body of mass-Matter has historically been defined as a strictly attractive force between bodies

$$F = -G\,\frac{M_1 m_2}{r^2}$$

Tetryonics reveals Gravitation to be the nett result of 3 distinct interactions:
Convergent G-fields
Interactive E-fields and
Perturbative M-fields



mass-Matter topologies displace vacuum energies to create stress energy densities

All Gravitational fields accelerate objects towards the Centre of any Gravitational field produced by mass-Matter topologies

radiated [K]EM fields create vacuum energies

The directional pull of Gravity to the centre of Matter topologies (along with the increase in g forces as the radius of attraction decreases) creates Tidal forces on the body being accelerated

In accordance with Newton's 3rd law there is an equal but opposite Force on the Earth produced by the Moon's graviational field resulting in Tides

In addition to Gravity all Matter radiates [K]EM fields that accelerate incident EM masses and Matter

Copyright ABRAHAM [2008] - All rights reserved

Tetryonic Gravitation

is the result of the combined interactions
of radiant EM geometries & Matter topologies
in any spatial region of measurement


Matter
Tπ [m Ω v²]
c²
Planck quanta
mass
velocity
G
EM mass
nπ [m Ω v²]
c⁴
Planck quanta
mass
velocity
E²

[k]EM fields & Vacuum energy gradients
create energy momenta pressure differentials
that accelerate Matter

3D mass-Matter topologies
create nullspace
vacuum energy differentials

Radiant EM mass-energy densities
create [k]EM and Vacuum Energy fields

$$F = -G\frac{M_1 m_2}{r^2}$$

All massive bodies create interactive GEM fields
through their mass-energy geometries & Matter topologies
with convergent and divergent vectors of acceleration

[k]EM energy fields INTERACT
to provide additional acceleration to
EM mass-Matter close to material bodies

Gravity
ATTRACTS Matter
over large distances

$$G_{ab} = \kappa T_{\mu\nu}$$

Copyright ABRAHAM [2008] - All rights reserved

EM masses & Gravitational Matter

$\frac{\rho}{m^2}$

The core problem preventing the unification of Classical gravitation with QM & Relativity theory is the imprecise formulation, definition and differentiation between mass & Matter

$\frac{\rho}{m^3}$



$$E = mc^2$$

radiant mass-energy geometry

mass

Energy

Planck quanta

$$\frac{n\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

mass is a geometric measure of a field's planar energy momenta content per unit Time

2D masses

bosons photons

$$F = ma$$

mass is a conserved quantity
Matter is not a conserved quantity

$$F = -G\frac{M_1 m_2}{r^2}$$

inertial mass
active gravitational mass
passive gravitational mass

$$G_{ab} = \kappa T_{\mu\nu}$$

Even GR offers no clear distinction

General relativity has been heralded as a highly successful model of gravitation and cosmology, which has so far passed every unambiguous observational and experimental test.

Even so, there are strong indications the theory is incomplete

Without a clear, concise understanding and accurate models of the relationship between mass & Matter [and their interactions] a Unified Field theory is impossible

$$mc^2 = E = Mc^4$$

Note: in both cases the amount of Energy described is identical
It is the changing spatial co-ordinate systems used to measure Energy in all it forms
that allows for the differentiation betweeen mass-energy geometries & Matter-energy topologies



$$E = Mc^4$$

standing-wave Matter topology

Matter

Energy

Planck quanta

$$\frac{T\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

Matter is a topological measure of an object's planar mass-energy content per unit of Time

3D Matter

Fermions, Baryons

mass-ENERGY-Matter equivalence

Einstein's mass-energy equivalence can be further refined and differentiated through charge geometries
[in turn creating a symetric mass-ENERGY-Matter equivalence formulation]


v
ε0
m
kg
c
[k]EM waves are
Lorentz variant
c²

mass

The mass-energies of EM waveforms is contained within its charged geometry

$$E = mc^2$$

EM mass-energy is a property of Matter

standing-wave

topologies

radiant EM mass geometry

$$\frac{m}{c^2} = M$$

standing-wave Matter topology

$$m = \frac{E}{c^2}$$

$$\frac{E}{c^4} = M$$

radiant


[v-v]
μ0
μ0
ε0
m
ε0
c
c
f

geometries

Matter is NOT a property of EM mass-energy

$$E = Mc^4$$

The mass-energies of Matter is contained entirely within its charged fascia topology


[n-n]
ε0
M
KG
Matter is
Lorentz invariant
c⁴

Matter

Tetryonic unified GEM fields

Equilateral Tetryonic geometry/topology provides a unified quantum field equation to model all Gravito-Electro-Magnetic mass-ENERGY-Matter interactions



Bosons

$$\frac{ODD\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

Planck quanta
mass velocity

All Matter is comprised of CHARGED EM mass-Energies

The total energy of any system is comprised of Matter & KEM fields

ENERGY

$$n\pi\left[\left[m\Omega v^2\right]\right]$$

Planck quanta
mass velocity

mass & Matter are distinct EM properties

The stress-Energy tensor includes all forms of energy

ENERGY

$$T\pi\left[m\Omega v^2\right]$$

Matter mass

Equilateral energy momenta are geometrically related to the square of velocity

3D Matter geometry is determined by charge

All Matter in motion produces a [k]EM field

Matter

$$\frac{T\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

Planck quanta
mass velocity

All Matter is gravitationally ATTRACTIVE

All Matter radiates INTERACTIVE [k]EM mass-Energies

EM waves

$$\frac{EVEN\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

Planck quanta
mass velocity

Matter topologies create convergent gravity & mass-energy geometries create interactive forces

Quantum Gravity

At present, one of the deepest problems of modern theoretical physics is the unification of General Relativity, which describes gravitation, and applies to large-scale structures (stars, planets, galaxies), with Quantum Mechanics, which describes the other three fundamental forces acting on the atomic scale

M

Newtonian Gravitation models observed motions of large-scale MATTER



$T_{\mu\nu}$

Einstein's GR models interactions of all mass-energy-Matter

G

The large scale Cosmos is ruled by GRAVITY

k

The Quantum world is ruled by ELECTROMAGNETISM

There are major points of tension between Quantum mechanics and General relativity.

Firstly, classical general relativity breaks down at singularities, and Quantum mechanics becomes inconsistent with general relativity in the neighborhood of singularities

Secondly, it is not clear how to determine the gravitational field of a particle, since under the Heisenberg uncertainty principle of Quantum mechanics its location and velocity at any instant of Time cannot be known with certainty.

Thirdly, there is the Problem of Time in Quantum gravity. Time has a different meanings in Quantum mechanics and General relativity and hence there are subtle issues to resolve when trying to formulate a theory which combines the two.



Gravitational attraction is a convergent Force between Matter

Newton



Gravitation results from energy density-pressure gradients

Einstein

Attempts to generalize ordinary quantum field theories, used in elementary particle physics to describe the fundamental interaction of gravity have to date led to serious problems.

Copyright ABRAHAM [2008] - All rights reserved

Gravitons

Gravitons are not required in Tetryonic theory
as gravitational attraction is a convergent force created
by the EM energy differential produced by
3D Matter topologies in a vacuum energy field

All standing-wave Matter
geometries create Gravity

G

CONVERGENT
Gravitation

Gravitons are the hypothetical
carriers of the attractive
Gravitational FORCE



Radiant EM fields are produced
by all Matter in motion

EM

DIVERGENT
ElectroMagnetism



Photons are the carriers
of the interactive
ElectroMagnetic FORCE

Gravitons were proposed as the gravitational equivalent
of the Photon in ElectroMagnetic theory but have never been detected

4πG

They were postulated because of the great success of quantum field theory (in particular, the Standard Model)
at modeling the behavior of all other known forces of nature as being mediated by elementary particles:
electromagnetism by the photon, the strong interaction by the gluons, and the weak interaction by the W and Z bosons.

8πG

The hypothesis was that the gravitational interaction is likewise mediated by a – yet undiscovered – elementary particle, dubbed the graviton.
In the classical limit the theory would allow Newton's law of gravitation in the weak-field limit to conform with Einstein's field equations of General relativity

Copyright ABRAHAM [2008] - All rights reserved

Laplacian field interactions

impedance of a medium

$$Z = \frac{\rho}{c^2} = \varepsilon_0 \mu_0$$

energy density

field geometry

electric permittivity

magnetic permeability

The planar two-dimensional Laplacian is given by

$$\Delta = \nabla^2 = \nabla \quad \nabla = \frac{\partial^2}{\partial x^2} + \frac{\partial^2}{\partial y^2}$$

This fundamental differential operator of Applied Mathematics was introduced by Laplace in his 1782 study of the force of gravitational attraction exerted by spheroids and was named after him by Maxwell in his 1873 treatise on electromagnetism.

$$G_P = K \frac{\rho}{c^4}$$

energy density pressure gradient

Einstein's constant

energy density

spatial volume

The net divergence of Positive charge fields is due to the anti-symmetry of their component Planck quanta

The net divergence of Negative charge fields is due to the anti-symmetry of their component Planck quanta


Δ
divergent field
Δ²
interactive field
Δ
divergent field
2π
2π
c². c²
μ0
μ0
μ0
μ0
ε0
ε0
2π
M
4π
M
2π
ε0
ε0
ε0
ε0
2π
c⁴
2π
convergent field
∇
convergent field
∇

superpositioned [k]EM fields produce both convergent and divergent forces depending on the charges involoved

$$E = \frac{\rho}{c^2 \mu_0}$$

$$B = \frac{\rho}{c^2 \varepsilon_0}$$



The Laplacian of any scalar field is interpreted as being the limit of the net outward flux per unit enclosed area of this field through a closed contour surrounding the point of evaluation

$$\Delta\phi = \lim_{A \to 0} \frac{1}{A} \oint_{\partial D} \frac{\partial \phi}{\partial \nu}\, dl, \quad A = \text{area}(D)$$

co-ordinate-free representation of the Laplacian

Newton's Gravitational Constant
has been shown to be a greatly
reduced version of Coulomb's
Electric interaction Constant



Newtonian Gravitation models
the observed convergent force of
GEM interactions that results in
the motion of large-scale Matter

*Any compete Unified field equation for
Gravitation must take into account both
the Nullspace gravitation resulting from
Matter topologies as well as the Coulombic
2D interaction fields that result from charge
and the motion of Matter through the aether*

Combined Interactive & Gravitational Forces

mass-energy-Matter

$$G_P = \kappa \frac{\rho}{c^4}$$

spatial volume

[24-12] KE [1-0] KE [0-1] [0-12]

Coulomb's Law $$P+ \left[\frac{2\pi\overset{\text{Energy}}{[mv^2]}}{c^2}\right] k \left[\frac{2\pi\overset{\text{Energy}}{[mv^2]}}{c^2}\right] e-$$

Q_1 c^4 Q_2

*Coulombic
[k]EM fields*

**Divergent [Interaction]
radiative EM Fields**

[k]EM interactive superpositioned EM fields of Force [k]EM

$$P+ \left[\underbrace{\frac{T\pi}{c^4}\overset{\text{Energy}}{[m]}}_{\text{Matter}} + \left[\frac{n\pi\overset{\text{Lorentz}}{[mv^2]}}{c^2} \underset{\text{Einstein's constant}}{\kappa} \frac{n\pi\overset{\text{Lorentz}}{[mv^2]}}{c^2}\right] + \underbrace{\frac{T\pi}{c^4}\overset{\text{Energy}}{[m]}}_{\text{Matter}}\right] e-$$

Matter *convergent gravitational field of Force* *Matter*



M_1 M_2

Newton's Law $$P+ \left[\frac{4n\pi\overset{\text{Energy}}{[mc^2]}}{c^2}\right] G \left[\frac{4n\pi\overset{\text{Energy}}{[mc^2]}}{c^2}\right] e-$$

[2,25e23] c^4 [1.2e20]

*Gravitational
Matter*

**Convergent [Attractive]
Gravity Field**

*The observed net convergent force between
objects of mass-Matter are the result of
convergent G & interactive EM fields*

vacuum impedance

electric permittivity

$Z = \frac{1}{c^2} = \varepsilon_0 \mu_0$

magnetic permeability

The energy density pressure gradient produced by the positive dispacement of vacuum energies by 3D standing-wave mass-Matter topologies is a strictly convergent force

mass-energy density

$G_\rho = \kappa \frac{\rho}{c^4}$

spatial region

$P = \frac{kT}{V}$

CHARGED mass-energy geometries create Matter topologies

mass-Matter-Vacuum energy displacements contributes to STRESS energies



M

All Matter is gravitationally ATTRACTIVE

m

Gravity fields produce a convergent inverse square force

mass-Matter topologies displace vacuum energies to create gravity

All Matter radiates INTERACTIVE [k]EM mass-energy momenta

$$\nabla\phi\ grav = 4\pi G\rho$$

The pressure Force of Gravity is proportional to the amount of mass-Matter in a system and can be modelled with weak superpositioned E-field geometries

c^4

$$F = -G\frac{M_1 m_2}{r^2}$$

$$G = \frac{8\pi G\, T_{\mu\nu}}{c^4}$$

Inverse squared interactive E-fields



wherever mass-energies create standing-wave topologies they also create Gravity



wherever there exists mass-energy imbalances energy will seek equilibirum via radiant EM fields

Although present, the Gravitational Attraction between quantum scale Matter particles is vastly overwhelmed by the Coulombic Interaction field resulting from the nett Charge imbalances of Matter and its fields of motion



Protons have
Stronger G fields than electrons
but weaker [k]EM fields

1.6596×10^{-27} KG
proton mass-Matter

electrons have
Weaker G fields than Protons
but stronger [k]EM fields

8.8514×10^{-31} KG
electron mass-Matter

All Matter in motion create inverse squared forces due to their divergent [K]EM fields

M

Matter 36π topology ∗ *mass-energy* 25n² *geometry*

KEM

superpositioned kEM fields create forces of attraction & repulsion

Gravity creates a strictly convergent force of attraction

G

c⁴

Matter 12π topology ∗ *mass-energy* 1n² *geometry*

[k]EM

mass-Matter topologies displace vacuum energies to form convergent gravity

Equilateral [k]EM mass-energies contribute to the total stress energies of any region

Copyright ABRAHAM [2008] - All rights reserved

vacuum impedance

electric permittivity $\varepsilon_0 = \frac{1}{c^2\,\mu_0}$ magnetic permeability

$\varepsilon_0 = 8.8541878176\,e^{-12}$ F/m

Vacuum Permittivity

The Electric fields produced by Matter produce interactive nett divergent forces

Opposites ATTRACT
Similars REPEL

$P = \frac{kT}{V}$

Electric field permittivity contributes to STRESS energies

CHARGED mass-energy geometries create Matter topologies

Q

RE



All Electric fields are nett divergent charge geometries >

< ***Electric fields follow the inverse square law***

M

KE

mass-Matter topologies displace vacuum energies to create gravity

All Matter radiates INTERACTIVE [k]EM mass-energy momenta

Equal opposing E-field energy-momenta create electrostatic fields around Matter [that produce Lorentz forces]

vacuum impedance $Z = \frac{1}{c^2} = \varepsilon_0\,\mu_0$ (electric permittivity, magnetic permeability)

c^2

electric permittivity of a spatial region

$4\pi \frac{1}{c^2\,\mu_0}\left[\left[m\Omega v^2\right]\right]$ (Planck quanta; mass, velocity)

Copyright ABRAHAM [2008] - All rights reserved

Perturbative M-forces

ElectroMagnetism is a velocity dependent vector interaction that dominates the Gravitational attraction of Matter



Inertial viewpoint

EM

Maxwells ElectroMagnetism

$$\nabla \times \mathbf{E} = -\frac{\partial \mathbf{B}}{\partial t}$$

$$\nabla \cdot \mathbf{B} = 0$$

$$\nabla \cdot \mathbf{E} = \frac{\rho}{\epsilon_0}$$

$$\nabla \times \mathbf{B} = \frac{1}{\epsilon_0 c^2}\mathbf{J} + \frac{1}{c^2}\frac{\partial \mathbf{E}}{\partial t}$$

[k]EM fields have electric and magnetic field components

The Tetryonic GEM model reveals the interplay of Convergent [Gravity], interactive [E-fields] & perturbative [M-field] forces

Gravitational Matter is ALWAYS attractive vectorial ElectroMagnetic fields are interactive

Gravity can be modelled with pseudo-electric and pseudo-magnetic field components

GravitoElectroMagnetism

$$\nabla \cdot \mathbf{E}_g = -4\pi G \rho_g$$

$$\nabla \cdot \mathbf{B}_g = 0$$

$$\nabla \times \mathbf{E}_g = -\frac{\partial \mathbf{B}_g}{\partial t}$$

$$\nabla \times \mathbf{B}_g = -\frac{4\pi G}{c^2}\mathbf{J}_g + \frac{1}{c^2}\frac{\partial \mathbf{E}_g}{\partial t}$$

G

Inertial viewpoint



The sign of the effect is different (attraction in one case, repulsion in another), but this is just because in electromagnetism the sign of the electric part of the acceleration is opposite that of gravity; electric charges of the same type repel each other, while in gravity two massive objects attract.

Apart from this sign, there is such a close analogy to magnetism that this velocity-dependent gravitational effect is often termed Gravito-magnetism

The Gravitational forces on the central particle are always equal irrespective of the inertial viewpoints

The ElectroMagnetic forces resulting from inertial motion in a different frame of reference produces different KINETIC [EM] forces

Copyright ABRAHAM [2008] - All rights reserved

vacuum impedance

magnetic permeability $\mu_0 = \dfrac{1}{c^2 \varepsilon_0}$ electric permittivity

μ_0 = 1.2566370614 e $^{-12}$ N/A^2

Vacuum Permeability

The Magnetic fields of Matter produce perturbative interactions

$P = \dfrac{kT}{V}$

Magnetic field permeability contributes to STRESS energies

CHARGED mass-energy geometries create Matter topologies

Q

RE



Magnetic dipoles follow the inverse cubed law

Magnetic fields follow the inverse square law

M

KE

mass-Matter topologies displace vacuum energies to create gravity

All Matter radiates INTERACTIVE [k]EM mass-energy momenta

Matter posesses a secondary magnetic moment that is subject to Lorentz forces

vacuum impedance $Z = \dfrac{1}{c^2} = \varepsilon_0 \mu_0$ (electric permittivity, magnetic permeability)

c^2

magnetic permeability of a spatial region

$4\pi \dfrac{1}{c^2 \varepsilon_0} \left[\left[\underset{\text{mass}}{m} \overset{\text{Planck}}{\Omega} \overset{\text{quanta}}{\underset{\text{velocity}}{v^2}} \right] \right]$

Gravitational & EM fields

Any unified Field equation that attempts to accurately model celestial scale gravitational attraction must also take into account KEM field interactions between the bodies resulting from their respective motions

Q

RE



Gravity is created by vacuum energy displacement produced by Matter topologies in vacuum energy fields

along with displaced Vacuum energy gradients

Interactive E-fields and perturbative M-fields

also contribute to the nett convergent gravitational field

M

KEM

All Matter produces a nett Gravitational [convergent] force as a direct result of its mass-Matter topologies & KEM mass-energies

mass-Matter
5.9736×10^{24} KG
Earth
2.8673e26 π
displacement topology

interactive KEM field mass-energy momenta

$$\left[\overset{\text{Matter}}{\frac{4n\pi}{c^4}}\overset{\text{Energy}}{\underset{\text{mass}}{[\rho]}} + \left[\frac{2n\pi}{c^2}\overset{\text{EM mass}}{[\rho]} \; K \; \frac{2n\pi}{c^2}\overset{\text{EM mass}}{[\rho]}\right] + \overset{\text{Matter}}{\frac{4n\pi}{c^4}}\overset{\text{Energy}}{\underset{\text{mass}}{[\rho]}}\right]$$

$$r^2$$

mass-Matter
7.3477×10^{22} KG
moon
3.526e24 π
displacement topology

Gravitational gradients can be modelled as weak KEM fields

Independently and almost simultaneously in1964 three groups of physicists proposed the proposed the Higgs mechanism thorugh which the inertial mass properties of Matter are created:
François Englert and Robert Brout; by Peter Higgs (inspired by ideas of Philip Anderson); and by Gerald Guralnik, C. R. Hagen, and Tom Kibble.

CERN
Higgs search update

The Higgs mechanism was incorporated into modern particle physics by Steven Weinberg and Abdus Salam, and is an essential part of the standard model.



The Higgs Mechanism

Finding this particle would give an insight into why particles have certain mass, and help to develop subsequent physics. The technical problem is that we do not know the mass of the Higgs boson itself, which makes it more difficult to identify. Physicists have to look for it by systematically searching a range of masses within which it is predicted to exist.. which will determine its existence.

If it turns out that we cannot find it, this will leave the field wide open for physicists to develop a completely new theory to explain the origin of a particle's mass

As the Universe cooled and the temperature fell below a critical value, an invisible force field called the 'Higgs field' was formed together with the associated 'Higgs boson'

The Higgs mechanism is a process by which vector bosons can obtain mass

M

TETRYONS / FERMIONS / BARYONS
3D tetrahedral standing-waves
[4nπ EM mass-Matter topologies]
interact with the vacuum energy aether

Matter



m

BOSONS / PHOTONS
2D planar matterless fields
[nπ EM mass-energy geometries]
'slice' through the vacuum energy aether

EM masses

Tetryonics is a full relativistic unified theory of electromagnetic mass-ENERGY & Matter and motion in which the classical properties of inertial mass and quantum mechanical quantised energy momenta are explained as being direct result of the geometric properties of inductive equilateral energies moving through external electromagnetic fields

Applying the Unified Field Equation

for ElectroMagnetic masses & Matter interactions

All Matter has a
4π standing-wave
mass-energy topology

Matter topologies

$$G_{ab} = 8\pi G T_{\mu\nu}$$

The net gravitational force is the geometric mean of all EM mass-ENERGY-Matter interactions

All kEM waves have
4π superpositioned
mass-energy geometries

mass-ENERGY geometries

$$-G\frac{M_1 m_2}{r^2} = F$$


r²
kEM field interactions
kEM field
Electric field interactions
kEM field
The alpha constant is the universal coupling constant
Tπ
2nπ
α
K
2nπ
Tπ
determined by the energy momenta In superpositioned EM fields
Matter
Magnetic field perturbations
Matter
Gravitational attraction
c⁴
E²

$$F = k\frac{Q_1 Q_2}{r^2}$$

$$G$$

$$k$$

Gravity can be modelled as a reduced negative Coloumb Constant acting over a large distance

Coloumb's Constant is a large interactive Electric constant acting over a short distance

Tetryons - 4π
Leptons - 12π
Quarks - 12π
Mesons - 24π
Baryons - 36π

Ignoring interactive [k]EM field interactions reduces GR [k] to Newtonian [G]

Charges - 1π

Photons -2π

EM Fields - 2nπ

$$G_{ab} = 4\pi G T_{\mu\nu}$$

Copyright ABRAHAM [2008] - All rights reserved

Tetryonic two body interactions

$$G_{ab} = 8\pi G T_{\mu\nu}$$

Factoring all GEM interactions
Tetryonics resolves to General relativity



hν
v²
Q
RE
ElectroMagnetic
INTERACTION
r²
4nπ
4nπ
attractive
interactive
G
k
g
interactive
attractive
g
4nπ
c²
Gravitational
ATTRACTION
M
KEM
v²
hν

In a purely gravitational field
Tetryonics resolves to Newtonian gravity

$$G_{ab} = 4\pi G T_{\mu\nu}$$

Copyright ABRAHAM [2008] - All rights reserved


CHARGED
mass-time symmetries
$\frac{1}{c^2}\left[\left[m\Omega v^2\right]\right]$
Planck quanta
mass velocity
RELATIVISTIC
mass-ENERGY-Matter
$\frac{n\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$
Planck quanta
mass velocity
c^2
mass
Coulombs
Q
Joules
RE
3D
+
Ω
time
c^2
c
divergent
convergent
0
convergent
divergent
v
ρ
space
c^4
−
2D
M
KG
KE
Newtons
Matter
c^4
$\frac{4n\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$
Planck quanta
mass velocity
mass-MATTER
topologies
$\frac{n\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$
Planck quanta
mass velocity
KINETIC EM
mass-energy geometries

Tetryonics 71.14 - Quantum GEM space-time fields

Our EM SUN

The SUN (like the Planets) is a CHARGED body moving through an EM environment

G & E fields obey the inverse SQUARED laws

The nett Charge of a body is the result of an excess of one type of energy quanta and is reflective of their charged topologies [ie ionised Matter]



Neutral Magnetic Pole

Solar wind

Solar wind

Q

Positive ions stream outward from the Sun's surface and accelerate away

Positive ions stream outward from the Sun's surface and accelerate away

Negative ions flow inward

Neutral Magnetic Pole

The charged E field [heliosphere] of our SUN interacts with other charged planetary bodies

Magnetic dipole fields follow the inverse CUBED law

Solar eclipses allow us to view

the SUN's EM corona in detail

Solar Dynamics

The SUN is a ElectroMagnetohydrodynamo

Prominences

Flares, Prominences and CMEs are the result of Electro-Magnetic geometries



Tetryonic charge geometries explain Solar EM field dynamics



When multiple charged fascia interact they flare produce and CMEs

Positive ions stream outward from the Sun's surface and accelerate away

The SUN (like the Planets) is a CHARGED body moving through an EM environment

Where Solar EM loops breakdown or interact flares result

Solar Flares

The breaking of large inductive EM loops creates CMEs [Coronal Matter Ejections]



CMEs

The Earth is located at an average distance of about 150 million kilometers [1AU] from the Sun
It takes sunlight travelling at the speed of Light [c] about 8.3 minutes to cross this distance and reach the Earth.

BUT due to the nature of Longitudinal waves emitted by the SUN mechanical momenta impulses [action-at-a-distance] can be transfered from the SUN to the planets nearly instantanteously providing the mechanism for Newton's instataneous pull of Gravity on planetary bodies

Copyright ABRAHAM [2008] - All rights reserved


Stellar E-fields dominate the planetary ecliptic
E
E
Stellar E-fields near the core are constrained by M-fields
M
M
E
E
Solar prominence
Sunspot
Sunspot
Sunspot
Sunspot
6000 Kelvin
Maximum E-field strength
1 million Kelvin
Solar minimum
Solar maxiumum

Solar Coronal Heating

is a question that has perplexed solar physicists for over half a century.

The Charged EM field [heliosphere] of our SUN interacts with the charged planetary bodies

Current solar Magnetohydrodynamics uses nanoflares and wave heating in an attempt to try to explain this temperature differential

The SUN's Corona is far hotter than the the Solar surface (the photosphere) and its atmosphere (the chromosphere) due to the flanking dipolar solar M-fields

Positive ions stream outward from the Sun's surface and accelerate away

Tetryonics explains this temperature differential as a product of the Electric permittivity of the SUN's EM field geometry

The SUN (like the Planets) is a CHARGED body moving through an EM environment

Producing cyclic variations in the energy outputs of all stars

The SUN is a electromagnetohydrodynamo

Solar cycles

On an 11 year cycle, the shape of the corona oscillates from a wide crown about the Sun's equator to a completely closed envelope surrounding the Sun



decreased Matter-Energy conversion results in smaller E-field geometries

As Matter is consumed in the GEM pinch core

a Star's radiant EM output varies

increased Matter-Energy conversion results in larger E-field geometries

Solar maximum
whole sphere
Solar minimum
Equitorial regions
0
Solar maximum
whole sphere
Solar wind
EM irradiance
Solar minimum
Solar maximum

The solar cycle is the periodic recurrence of sunspots, or darker, relatively cool regions at the Sun's surface over a period of about 11 years

Tetryonics 72.04 - Solar cycles



Sunspot cycles

This is a question that has perplexed solar physicists for over half a century.

Powered by a Electromagnetic hydro-dynamic process, it drives the inductive action of internal solar fluxes

Modulates the occurrence frequency of solar flares, coronal mass ejections, and other solar eruptive phenomena

The solar cycle has a period of about 11 years and is the result of the SUN moving through the extra-solar vacuum energy environment

Structures the Sun's atmosphere, its corona and the wind

Sunspot activity occurs in the region of the SUN dominated by E-field geometries

Modulates the solar irradiance

Sunspots are the result of ElectroMagnetic field dynamics not just magnetic fields

Modulates the flux of short-wavelength solar radiation from ultraviolet to X-ray

Indirectly modulates the flux of high-energy galactic cosmic rays entering the solar system via the heliosphere

30° N
30° N
Solar irradiance
EQ
Solar flares
Solar Filaments
EQ
Coronal Matter Ejections
30° S
30° S
1880
1890
1900
1910
1920
1930
1940
1950
1960
1970
1980
1990
2000
Solar minimum
Solar maximum

Spots from multiple cycles can co-exist for some time and the sun reverses magnetic polarity one solar half cycle to the next, so spots from different cycles can be told apart over time

Tetryonics 72.05 - Sunspot cycles

Solar irradiance





The total solar irradiance (TSI) is
the amount of solar radiative energy
incident on the Earth's upper atmosphere

The SUN is an ElectroMagnetic pinch reactor

Solar EM mass-energy irradiation

is a measure of the total incident levels of solar EM radiation
recieved by the Earth's upper atmosphere in a given unit of time.

It is not the same as measuring the amount of EM radiation
emitted from the surface of the SUN.

It can be stated that solar irradiation is the amount of EM energy
transmitted from the SUN to the Earth's outer atmosphere.

This measurement is normally done in
square units per units of time.

Solar irradiance [W/m^2]

The set amount of solar energy recieved by the Earth's atmosphere
is called the solar constant.

The most recent value measured for the Solar Constant is
1368 Watts per meter squared.

The Solar constant has an inverse relationship to the
solar irradiance of the SUN's surface
reflective of Earth's distance from the SUN.

It shows how the massive amouts of EM energies
emitted by the sun is scaled down
to what is used by every biosystem on the planet.

The Sun emits longitudinal EM radiation across
most of the electromagnetic spectrum.

**The basic causes of the solar variability and solar cycles are still under debate,
Tetryonics dictates a EM mechanism for the energies produced at the core of Stars
and that the variability of the stellar outputs may be due to changes in the
ElectroMagnetic environment that Stars [and their planetary systems] move through**

The spectrum of the Sun's solar radiation is close to that of a
black body with a temperature of about 5,800 K.

Changes in the SUN's EM output
can have a direct effect on the
weather and electrical activity
of the Earth and other planets

Solar irradiation produces Carbon 14



An extremely long stretch of low activity in recent years has left scientists baffled
and searching for a better model of the SUN's interal processes and how to forcast its output
in order to establish a better link between the solar cycle and global climate flucuations

Stellar refraction of EM waves

Any test of General Relativity using photons (or EM waves) will only measure SR interactions
[ie Gravitational red-shifting is a SR effect on EM masses not graviational Matter]

G

The motion of Matter is affected by gravitational attraction and EM interactions

Photons are NOT 'bent' by Gravitational fields they are refracted by propagation velocity changes resulting from their EM interactions with the solar corona

$$\alpha[\text{einstein}] = \frac{8\pi GM}{c^2}$$

EM

The motion of EM masses is affected by EM interactions and creates refraction


Stellar light spectra
α
Distant Star
RF transmissions
Mars
Velocity propagation delays caused by the Solar Plasma environment
μ
ε
Solar Corona
ω
ω
Earth
EM interaction of coronal plasma is 10^38 times greater than that of gravity

According to Einstein's general theory of relativity published in 1916 light coming from a star far away from the Earth and passing near the Sun will be deflected by the Sun's gravitational field by an amount that is inversely proportional to the star's radial distance from the Sun

1.745" at the Sun's limb
(this is the result of EM refraction NOT Matter gravitation)

$$\alpha[\text{newton}] = \frac{4\pi GM}{r}$$

Photons are not massless they are 2D radiant EM mass-energy momenta geometries

r

The additional 'bending' of light rays as they pass by a Gravitational body as predicited in Einstein's general relativity is caused by refractive EM interactions not by the force of gravity

4π

4π

c^2

Gravitation in General relativity is Newton's Gravity with SR corrections

The Solar Heliosphere

The planetary obits, often hypothesised as being created by the SUN's accreation disk during its formation and 'spun up' to their current orbital momenta can now be visualised as having been formed by the SUN's constant interactive Gravito-Electro-Magnetic fields

The eight planets (plus Pluto and all those other dwarf planets) orbit within a very small volume of the heliosphere (the volume of space dominated by the E field influence of the Sun)

Comets go around the Sun in a highly elliptical orbits.

They can spend hundreds and thousands of years out in the depths of the solar system before they return to the Sun at their perihelion


The planets possess only 2% of the Matter
but posses 98% of the angular momentum
of the solar system
Outer Jovian gaseous Planets
Inner Terrestrial rocky Planets
Pluto
Kuiper Belt
Comets
Asteroids
Uranus
Saturn
Earth
Mercury
asteroid belt
asteroid belt
Neptune
Jupiter
Mars
Venus
The Sun
(99.8% of total Matter)
Dwarf Planets

convergent force

The SUN's gravitational field attracts Matter in the solar system towards it

The SUN's electroMagnetic field Interacts with charged Matter in the solar system accelerating it Into stable elliptical orbits

interactive forces

The SUN's electromagnetic field pushes Matter in the solar system away from it

Planetary Orbits are NOT to scale

The SUN is the Solar system's dominant charged electromagnetic mass-Matter body

Planetary solar Orbits, though technically ellipses, are nearly circular

Tetryonics 72.08 - The Solar Heliosphere

Stellar mechanics



Standing-wave energy momenta topologies produce gravitational Matter

Radiant energy momenta geometries produce interactive EM waves

charged
geometries
Q
RE
Relativisitic
energies
convergent
gravity
interactive
EM fields
Solar
winds
Spectral
lines
GEM field point
0
singularities
mass-Matter
topologies
M
KE
Kinetic EM
energies

The current mathematical modelling of all G & EM field energy momenta leads to

Tetryonic charge geometry provides a foundational solution

Gravity fields obey the inverse SQUARED law

Magnetic dipoles obey the inverse CUBED law

Electric fields obey the inverse SQUARED law

Tetryonics 73.01 - Stellar mechanics

Anti-Matter Stars




$\bar{N}^0$ = dud
anti-Neutron
positron
Negatron
18-18
12-0
[42-42]
12-24
+
−
P^- = udu

anti-Matter stars have
the opposite charge topology
to Matter stars


μ_0
μ_0
ε_0
ε_0
μ_0
μ_0



Neutron Stars

Colours used are illustrative of Matter types only


N^0 = dud
Neutron
neutrino
anti-Neutron
18-18
6-6
[42-42]
18-18
−
+
$\bar{N}^0$ = dud

All stars types emit Neutral Photons


μ_0
μ_0
ε_0
ε_0
μ_0
μ_0

Matter Stars


N^0 = dud
18-18
Neutron
[42-42]
0-12
electron
24-12
Proton
−
+
P^+ = udu

Matter stars have
the opposite charge topology
to anti-Matter stars


μ_0
μ_0
ε_0
ε_0
μ_0
μ_0

Star classifications





The greater the EM mass-energies radiated in a given volume of space the higher the Temperatures

White dwarves

Average Matter in Small volumes

The greater the voume for a given amount of radiated EM mass-energy the 'cooler' the Frequency of light produced from stellar processes

Blue giants

Greater mass-Matter in Larger volumes

O

≥ 16 M



B

2.1–16 M



A

1.4–2.1 M



Red giants

Less mass-Matter in Larger volumes

M

≤ 0.45 M



K

0.45–0.8 M



G

0.8–1.04 M



F

1.04–1.4 M



Main sequence

Average mass-Matter in medium volumes

Nucleosynthesis

The goal of nucleosynthesis is to understand the vastly differing abundances of the chemical elements and their several isotopes as being a result of natural history



Nucleosynthesis is the process of creating new atomic nuclei from pre-existing nucleons (protons and neutrons)

All Stars have a dominant spectral colour and emit a multitude of spectral lines



All Stars emit various colour spectra that combine to form spectral lines reflective of the star's energy output

The CNO cycle describing element creation inside Stars is erroneous ....

All spectral lines can be produced by the excitation of stellar nuclei by photons released by GEM pinch Matter-Energy conversion

In 1920, Arthur Eddington was the first to suggest that stars obtained their energy from nuclear fusion of hydrogen to form helium.

The P-P Chain describing the FUSION of elements to release energy is erroneous ....

All Matter-Energy conversion inside Stars is the result of ElectroMagnetic Pinches

Elements in the Sun

Element	% of total atoms	% of total mass
Hydrogen	91.2	71.0
Helium	8.7	27.1
Oxygen	0.078	0.97
Carbon	0.043	0.40
Nitrogen	0.0088	0.096
Silicon	0.0045	0.099
Magnesium	0.0038	0.076
Neon	0.0035	0.058
Iron	0.030	0.014
Sulfur	0.015	0.040

Nucleosynthesis problems such as the abundances of observed elements & low mass element synthesis remain open problems for the current theory

Despite intense efforts to create suitable conditions, FUSION as described in nuclear theory, remains an ellusive source of Energy

The CNO cycle and P-P reactions are incorrect theorical models, developed to explain the SUN's GEM pinch dynamics and broad spectral line emissions



Solar Arc lamp spectra

spectral lines are produced by accelerating electrons

Energy-momentum relationship

$$E = mv^2$$


Q
RE
Elemental Spectra
Stellar
1
2
3
4
5
6
7
8
9
0
core
Ni
Fe
Si
Mg
O
N
C
He
H
Quantum Energy levels [layers]
M
KE

$$\Delta hf = \Delta Mv = \Delta p$$

Spectral line transitions


v
Δv
Σv
12
36
3
36
60
5
96
84
7
180
108
9
288
132
11
420
156
13
576
180
15
756
hv
v
c
Mv²
E

hv, R, β, p, KE
Planck, Rydberg, Lorentz, Newton, Leibniz

Spectral lines

KEM	
48	*Lyman*
108	*Balmer*
192	*Paschen*
300	*Brackett*
432	*Pfund*
586	*Humphries*
768	*un-named*

classical physics and relativity united through equilateral geometry

Astrophysicists and astronomers use arc lamps as spectral line reference sources for many elemental emission and absorption lines



Tetryonic QED explains Planck's heat law along with all the observed spectral lines from first principles

Planck's quantum radiation Law gives a energy distribution that peaks at a certain wavelength, Wien's Law explains the peak shifts to shorter wavelengths for higher temperatures, and the Stefan-Boltzman law explains the growth in the height [the area under] the curve with increasing temperatures

Stellar spectral lines


Q
RE
M
KE
Quantum Energy levels [layers]
n
0
Elemental Spectra

$$E = Mc^4$$

Energy-mass-Matter equivalence

Z#
All elements have equal number nuclei components
[P-e-N]

$\Delta mv = \Delta hf$
Excitation of photo-electrons in atomic nuclei produces spectral line emissions

Energies released from the collapse of mass-Matter topologies in stellar cores is radiated as spectral mass-energies
[GEM pinch]

mass-Energy equivalance

$$E = mc^2$$

The emissions from GEM pinch processes produce broad spectral lines that range from UV to IR rays
[& include white light]

The spectral lines of all elements can be mimicked by Deuterium nuclei with rasied energy levels undergoing energy transitions

Tetryonic Electrodynamics

Δhv
Quantum differentials


Lyman
Balmer
Paschen
Brackett
Pfund
Humphries
1
2
3
4
5
6
7
8
n
972

$$hf = \Delta Mv = \Delta p$$

spectral lines are produced by accelerating electrons

As energy is 'released'by the collapse of mass-Matter topologies in the stellar core they radiate outward raising the nuclear energies of the surrounding Matter which in turn radiate spectral series photons


standing-wave
radiant
radiant
n8
n7
n6
n5
M
Spectral energies
Spectral energies
mass-Matter topologies
n2
n1
mass-energy geometries
mass-energy geometries

Joseph von Fraunhofer

(6 March 1787 – 7 June 1826)


n1
standing-wave
n2
n3
n4
n5
n6
mass-Matter topologies
n7
n8
Quantum levels
Spectral energies
radiant
radiant
mass-energy geometries
mass-energy geometries
>

Annie Jump Cannon

(December 11, 1863 – April 13, 1941)

SPECTRAL SERIES

Lyman
Balmer
Paschen
Brackett
Pfund
Humphries

Stellar spectroscopy

Astronomical spectroscopy is the technique of spectroscopy used in astronomy. The object of study is the spectrum of electromagnetic radiation, including visible light, which radiates from stars and other celestial objects.

ATOMIC SHELLS

K
L
M
N
O
P

Spectral absorption lines are often referred to as Fraunhofer lines

QUANTUM LEVELS


v
M5
M0
K5
K0
G5
G0
F5
F0
A5
A0
B5
B0
O5
E
hv
v²
M5
M0
K5
K0
G5
G0
F5
F0
A5
A0
B5
B0
O5

In 1901 Annie Cannon improved upon the 1897 work of Harvard associate Antonia Maury to produce the Harvard spectral class

STELLAR CLASSIFICATIONS

Spectroscopy can be used to derive many properties of distant stars and galaxies, such as their chemical composition, and motion through Doppler shift measurements.

Tetryonics 73.07 - Stellar spectroscopy

Radiant electromagnetic waves propagate

at the speed of light in a vacuum [c]
taking 8.3 minutes to reach Earth

$$E = hf$$


X-rays, visible light, heat
GEM pinch core
E
ENERGY
MOMENTUM
action-at-a-distance

$$p = mc$$

Square root linear momenta present in
all longitudinal EM waveforms from rigid rods

and once established propagate impulses of momenta
near-instantaneously along the longitudinal waves
arriving 8.3 minutes before visible light

mass-ENERGY-Matter

Energy from the SUN

EM energies released by the collapse of standing-wave Matter topologies in the SUN radiate through space as mass-energy momenta and interact with Matter

All atoms are comprised of Deuterium nuclei


Azmithal & Magnetic numbers
+3
+2
+1
0
-1
-2
-3
R
Q
P
O
N
M
L
K
atomic shells
Shell
8
7
6
5
4
3
2
1
Quantum levels
Nuclei
2
8
18
32
32
18
8
2
Z
f
d
p
s
p
d
f
electron Orbitals & sub-orbitals

The Earth receives a broad spectrum of energies from the SUN
[with visible light falling into the Balmer spectral series]

$$hf = \underset{366.859\text{ nm}}{kEM} = \frac{hcR}{n^2}$$

By inductively coupling to the raised quantum KEM fields of the bound electrons their energies can be extracted and utilised

Deuterium nuclei are quantum synchronous convertors of electromagnetic energies

$$kEM = Mv^2$$

As energy momenta is recieved the energy levels of the Baryons increases in turn affecting and raising the KEM field energies of bound electrons


Q
O
[42-42]
RE
d
d
u
u
M
Deuterium
c^2
KE

spectral lines, atomic transitions, photo-electric effect


v
Δv
Σv
KEM
48
108
192
300
432
588
768
36
60
84
108
132
156
180
3
5
7
9
11
13
15
36
96
180
288
420
576
756
hv
v
c
v²
Mv²
hv, R, γ, p, KE
Planck, Rydberg, Lorentz, Newton, Leibniz

changing spectral emissions $\Delta hf = \Delta Mv = \Delta p$ accelerate photo-electrons

Stellar Energies


4He
1H
1H
12C
γ
13N
15N
ν
ν
Incorrect atomic models lead to erroneous theories of stellar energy release
15O
13C
14N
γ
γ
1H
1H
The CNO cycle


84
[48-48]
D
1.9995
45,012
[3.320192418e-27 kg]


Q
RE
mass-energy equivalence
E = mc²
Tetryonic theory restores symmetry to Einstein's mass-energy equivalence
E = m/c²
M
KE
Matter-energy equivalence

$$\underset{mass}{mc^2} = \overset{ENERGY}{E} = \underset{Matter}{Mc^4}$$

mass-ENERGY-Matter equivalence shows that a tiny amount of mass-Matter can be converted into a tremendous amount of radiant EM mass-energy

The energy released hypothesised by 'Fusion' is 1/200th that of the Tetryonic collapse of Matter into radiant EM mass-energies

All mass-ENERGY-Matter topologies are modelled in Tetryonic theory and Baryon decay is instigated by neutrinos


48
[24-24]
H
1.0000
22,512
[1.660538783 e-27 kg]

Neutrons are NOT Protons with an absorbed electron inside their charge topology

High pressure tunneling through the Coulomb barrier does NOT occur


1H
1H
1H
1H
P-P chain rection
ν
ν
2H
1H
1H
2H
nuclear 'fusion'
γ
γ
3He
3He
1H
1H
4He

The P-P fusion chain of Hydrogen->Helium is completely erroneous

The neutrino production of Proton-Proton chain reactions is 1/3 of what is detected


168
[84-84]
He
3.9989
90,024
[6.640384835e-27 kg]

The SUN's energy comes from Tetryonic Matter collapse NOT the fusion of atomic nuclei

Copyright ABRAHAM [2008] - All rights reserved



Stellar Nuclear Fusion

is the process of fusing of light atomic nuclei in order to facilitate energy releases

'COLD fusion'

can be realised through the fragmenting of large atomic nuclei thus releasing stored nuclear [K]EM waveform energies

Long sought after, but never realised, Fusion energies remain an ellusive source of clean limitless energy.

'HOT fusion'

is a fallacy, Stars release energy by collapsing standing-wave Matter into radiant EM mass-energy geometries in electromagnetic pinches

As Matter is consumed in the stellar core
GEM
PINCH
a Star radiates EM mass-energies
c
c

The much-maligned 'COLD fusion' of Palladium is in fact a form of atomic fission that releases the stored chemical [kEM] energies of atomic nuclei and is 12-13% efficient

Tetryonics reveals the true mechanics behind the cold 'fusion' observed by Drs. Pons & Fleischmann and corrects the model of stellar processes to reveal new energy sources for the future

The hypothesised 'HOT fusion' of elements in stars is the Tetryonic conversion of mass-Matter within the star into radiant mass-energies requiring an electromagnetic pinch reaction but is 100% efficient

Where Fusion went Wrong

The conversion of standing-wave Matter into radiant mass-energy constitutes a sustainable, virtually unlimited environmentally compatible long-term source of energy that can meet all of Humanity's needs.

The toriodal design of Tokamak reactors does not allow for the formation of plasma pinches at their cores

Tokamak design

Among a small number of approaches, the concept of toroidal magnetic confinement of fusion plasmas has achieved the most impressive scientific and technical progress towards energy release by thermonuclear burn of deuterium-tritium fuels.

The plasma consists of charged nuclei and electrons, which move in tight spirals around the lines of force of strong magnetic fields.

Of the two designs only inertial confinement offered the best chance of creating the conditions required to effectively collapse Matter topologies in order to release the EM energies it contains.

However a far superior approach would be the electromagnetic pinching of Matter (as present in all stellar cores)

The basic problems in attaining useful nuclear fusion conditions are

(1) to heat the gas to these very high temperatures and

(2) to confine a sufficient quantity of the reacting nuclei for a long enough time to permit the release of more energy than is needed to heat and confine the gas.

A subsequent major problem is the capture of this energy and its conversion to electrical energy for work

Inertial confinement fusion produces brief shockwaves, excessive heating and no sustained EM field



Inertial confinement

In inertia confinement the fuel—tritium or deuterium is contained within a tiny glass sphere that is then bombarded on several sides by a pulsed laser or heavy ion beam.

This causes an implosion of the glass sphere, setting off a thermonuclear reaction that ignites the fuel but offer no self-regualation and relase of radiant mass-energies.

E_{in}

In any useful fusion device, the energy output must exceed the energy required to confine and heat the plasma

E_{out}

Copyright ABRAHAM [2008] - All rights reserved

ElectroMagnetic Pinch technology

can serve as the gateway to realising new forms of clean, safe, efficient Energy production through the conversion of any Matter into various forms of EM radiation utilising electromagnetic pinch geometries developed from Tetryonic theory

Charged Matter topologies are standing wave EM mass-energies



mass-Matter-ENERGY conversion

$$Mc^2 = E = hv^2$$

is the collapse of mass-Matter topoplogies into radiant mass-energy geometries

Radiant mass-energies form kEM wave geometries

An electromagnetic pulse (sometimes abbreviated EMP) is a burst of electromagnetic radiation that results from an explosion (usually from the detonation of a nuclear weapon) and/or a suddenly fluctuating magnetic field. The resulting rapidly changing electric fields or magnetic fields may couple with electrical/electronic systems to produce damaging current and voltage surges.

Copyright ABRAHAM [2008] - All rights reserved

Stellar GEM Pinches

M

The century old theoretical mechanism of FUSION
from which the SUN generates its broad radiative EM energies
must be replaced with Gravito-Electro-Magnetic pinches

E

Gravity fields obey the inverse SQUARE law

Polar Magnetic fields obey the inverse SQUARED law
Magnetic dipoles obey the inverse CUBED law

Electric fields obey the inverse SQUARE law



Gamma rays produced by EM Pinches are absorbed by nuclei in the Sun, and then re-emitted over the course of 200,000 years

They then make their way through the radiative zones of the Sun and out into space

3D standing-wave topologies

$E = Mc^4$

Energy-mass-Matter equivalence

mass-Matter creates Gravity

2D radiant geometries

$E = mc^2$

mass-Energy equivalance

mass-energies create kEM fields

Vaccum energies are displaced by Matter topologies to form convergent gravity

KEM waves created by stellar pinches create interactive action-at-a-distance

The conversion of Matter to Energy in stellar GEM pinches is 100% efficient

The Fusion of elements is NOT the energy source of Stars

mass-Matter-ENERGY conversion

Stars emit broad spectra LONGITUDINAL electromagnetic waves

Tetryonics 73.13 - GEM Pinches

Copyright ABRAHAM [2008] - All rights reserved

GEM Pinch efficiency

GEM Matter-Energy conversion is the 100% efficient dimensional transformation of 3D Matter into 2D mass-energy

M

Theorised Proton-Proton chain reactions of Stellar fusion release <1% of the total Matter as EM energies

m

Matter to energy conversion by EM pinches releases 100% of the total Tetryonic Matter as radiant EM mass-energies



Q
RE
M
KE
n1
n2
n3
GEM
0
pinch
n5
n6
n7
n8
Spectral energies
Spectral energies

3D mass-Matter topologies

c^4

2D mass-energy geometries

c^2

The collapse and conversion of 3D mass-Matter topologies into radiant mass-energies releases as much energy as



12
[42-30]
12
[30-42]
γ
Matter
anti-Matter

annihilation



e^-
12
[0-12]
dud
N^0
0
[18-18]
p^+
12
[24-12]
udu



12
[12-0]
e^+
0
[18-18]
$\overline{N}^0$
dud
12
[12-24]
N
udu

Tetryonics 73.14 - Matter-Energy collapse

Copyright ABRAHAM [2008] - All rights reserved

EM Pinch reactors

The technology required to create clean, limitless energy and meet all of humanity's future energy requirements has existed since the 1900's.

The basic steps to build a EM Pinch reactor are

(1) design and build a EM pinch field into which a fuel pellet can be injected

(2) the fuel can be any form of Matter that exhibits both Electric & Magnetic dipoles to facilitate the automatic positioning of the material fuel into the pinch core [the EM fields interact untill they equalise]

(3) enclose the EM Pinch core in a containment casing that can both capture and absorb the radiant EM energies produced by the collapse of Matter at the core and convert these energies into electricity

Th efficiency of the containment vessel along with energy storage and distribution can all be improved through the use of various Tetryonic field geometries to capture and re-circulate all EM energies produced

There are no moving parts to wear out or require extensive maintenance regimes

Upon any loss of Power to the system the EM pinch will be unsustainable and shutdown automatically preventing any possibility of runaway reactions

Photons

$$\frac{2\pi}{c^2}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\underset{\text{velocity}}{\overset{\text{quanta}}{v^2}}\right]\right]$$



EM waves

$$\frac{2n\pi}{c^2}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\underset{\text{velocity}}{\overset{\text{quanta}}{v^2}}\right]\right]$$

No preheating of Plasma is required as the EM pinch generates energy by collapsing' 3D Matter topologies into 2D EM mass-energy geometries by way of EM compression

Once initiated a secondary 'circuit' could be placed in circuit to bleed off and return suficient energy to the EM pinch field circuit in order to make the reaction self-sustaining

EM pinches are fuelled

by any form of Matter

The electromagnetic pinching of Matter (as utilised in Nature in all stellar cores) produces only EM radiation [light & heat] as a by-product - there are no harmful wastes - as the Matter is converted with 100% efficiency

and release mass-energy

as radiative KEM fields

Tetryonics 73.15 - The EM Pinch reactor

EM Pinch reactor containment vessel



A resilient material is required for the containment sphere

Fuel for the EM pinch reactor is any form of Matter

EM pinch technologies can provide clean limitless energy to meet the all needs of all Humanity

To handle high temperatures, the extreme radiant energies along with the EM energy momenta forces created

However radioactive waste is an obvious choice so as to destroy existing stockpiles & to release the most energy per KG of waste

With clean, limitless energy

We can create unlimited resources

The released EM energies can be bled off electrically as demand requires or confined for later use

In the equatorial region doping metals may be added to enhance the conduction of EM energies into electrical circuits

Matter-ENERGY conversion in EM Pinch reactors is 100% efficient

The reactor and its containment vessel can be scaled to meet energy requirements of different locales

There are no moving parts in contact to wear out or require extensive maintenance regimes

Tetryonics 73.16 - EM Pinch reactor containment

Copyright ABRAHAM [2008] - All rights reserved

The Earth has finite resources and an ever increasing human population puts pressure on its ability to supply resources to meet our needs

Unlimited material Resources

Tetryonics offers a solution to human problems that have plagued civilization from its beginnings leading to wars, disease and famines

With clean, limitless energy sources

Unlimited resources can be created



mass-energy geometries
cannot be created or destroyed



mass-Matter topologies
can be created and destroyed

Resources

Health

With this new understanding of the charged mass-energy geometries of Matter excess energies generated from the destruction of Matter topologies can be reformed into any desired element or compound, and all harmful waste can be removed from our environment

Food

Water

Tetryonics 73.17 - Unlimited resources

Copyright ABRAHAM [2008] - All rights reserved



The Solar System

the strength of divergent EM solar radiation
acts on convergent, gravitating Matter to accelerate it
forming stable orbits relative to the individual
densities of the planetary bodies

Classical Gravity models the observed motion of Planetary bodies

[without explaining its motivating force]

Denser, rocky
planets are
strongly attracted
to the SUN

Newtonian Gravity

G

Denser, rocky
planets orbit
closer to the SUN
where radiant EM
energies are stronger

Light measurement	AU	KM travelled
1 light-second	0.0020	299,792.458
1 light-minute	0.1202	17.98 million
1 light-hour	7.2143	1.08 billion
1 light-day	173.14	25.9 billion
1 light-week	1212.0	181.3 billion
1 light-month	5194.3	777.06 billion
1 light-year	9.46 trillion	5.89 trillion

The PULL of gravity

*Convergent gravity
attracts all Matter
towards stars*

is counter-balanced by

*Divergent EM fields
accelerates Matter to
create stable orbits*

the PUSH of EM fields

Longitudinal EM energy momenta
produced in the cores of stars provides the mechanics for
instantaneous interaction -at-a-distance
between stars and their planets

General Relativity corrects for fine purturbations caused by EM interactions

[without distinction between its various forms]

Lighter, gaseous
planets are less
strongly attracted
to the SUN

Special Relativity

EM

Lighter, gaseous
planets orbit further
from the SUN
where radiant EM
energies are weaker

Planet	Distance from Sun
Mercury	192 light-seconds
Venus	361 light-seconds
Earth	500 light-seconds
Mars	762 light-seconds
Jupiter	2,598 light-seconds
Saturn	4,752 light-seconds
Uranus	9,576 light-seconds
Nepture	14,976 light-seconds

Tetryonics 74.01 - The Solar System

Kepler's Laws

Kepler's three laws of planetary motion can be described as follows:

The path of the planets about the sun is elliptical in shape,
with the center of the sun being located at one focus.
(The Law of Ellipses)

An imaginary line drawn from the center of the sun to the center of
the planet will sweep out equal areas in equal intervals of time.
(The Law of Equal Areas)

The ratio of the squares of the periods of any two planets is equal to
the ratio of the cubes of their average distances from the sun.
(The Law of Harmonies)

$$T^2 = k\,a^3$$

The square of the orbital period of a planet is directly proportional to the cube of the semi-major axis of its orbit.

The divergent energy momenta of kEM fields create an acceleration FORCE on material bodies



The orbit of every planet is an ellipse
with the Sun at one of the two foci.

A line joining a planet and the Sun sweeps
out equal areas during equal intervals of time.

Gravity attracts Matter towards stars

An Elipse circumsribed,
onto the Apex points of
an Equilateral triangle
has the form
of a Circle

A Star's kEM field accelerates Matter away from it creating stable ellipical orbits

With an equilateral triangle, draw lines from the center of the circle to each vertex and each midpoint, creating six right triangles, as shown with six different colored triangles. Each right triangle has a radius of the circle for one leg, and half of a side of the original triangle for another. Any two right triangles sharing one of the radial lines must therefore be congruent, and that implies that the hypotenuses of the triangles are all equal. This in turn shows that the six right triangles are all congruent, and so the large triangle they combine to form is equilateral

The Major celestial bodies

All planetary orbits are the result of a balance between gravitation Matter and interactive kEM fields

The sun is a rotating charged mass-Matter object, and it creates a solar system-wide kEM field.

The solar mass is large enough to produce a EM field with lines of Force reaching the orbit of Pluto.

Planet	Object Axial tilt (°)	Axial tilt (radians)
Mercury	~0.01	0.00
Venus	177.4	3.10
Earth	23.44	0.41
Moon	1.5424	0.03
Mars	25.19	0.44
Jupiter	3.13	0.06
Saturn	26.73	0.47
Uranus	97.77	1.71
Neptune	28.32	0.49
Pluto	119.61	2.09



The charged planets move at right angles to the Sun's magnetic lines of force and describe the usual circular motion to which moving charged bodies are subject to in an electromagnetic field.

Venus and Uranus are unique in that their orbital motions about the SUN are retro-grade motions

Satellites, in turn, revolve in the smaller magnetic fields produced by the rotation of the planets. Mercury and Venus have no satellites as they produce extremely weak electromagnetic fields in addition to their Gravitational fields.



"In comparing the masses of the Earth, Jupiter and Saturn to their volumes, one remarks that the densities of these planets are, to some degree, inverse to their mean distances from the Sun. This rule is not true for Venus and Uranus"

Urbain Le Verrier

Copyright ABRAHAM [2008] - All rights reserved

Solar orbit Inclinations

Inclination to Sun's equator (°)

Rocky Planets	
Mercury	3.38
Venus	3.86
Earth	7.15
Mars	5.65

Gas giants	
Jupiter	6.09
Saturn	5.51
Uranus	6.48
Neptune	6.43


Solar
Magnetosphere
Pluto-Cometary
inclinations
Solar Heliosphere
Earth
Mars
Solar Heliosphere
Jupiter
Saturn
Uranus
Neptune
Inclination to Sun's equator
Solar
Magnetosphere

Orbital inclination is one of the six orbital parameters describing the shape and orientation of a celestial orbit.

It is the angular distance of the orbital plane from the plane of reference (usually the primary's equator or the ecliptic), normally stated in degrees.

Copyright ABRAHAM [2008] - All rights reserved

Gravity is a strictly convergent Force

← ← ↔

GR = G + EM

Einstein Newton Lorentz

General Relativity models Newtonian Gravity with SR interactions

The Lagrange Points

are the five positions in an orbital configuration where a small object affected only by gravity can be stationary relative to two larger material bodies of mass-Matter



GEM forces between two bodies can be modelled with super-positioned equilateral energy geometries

Gravitational forces from the two massive bodies are in the same ratio as the material masses of the two bodies



Gravitational attraction of M partially cancels the gravity of m

This point lies on the line defined by the two large masses, beyond the larger of the two

Gravitational forces of the two large masses baance the centrifugal effect on a body at L2.

L4 and L5 are sometimes called triangular Lagrange points or Trojan points after the Trojan ateroids found in the L4-L5 points of the Jupiter-Saturn system.

Newtonian Gravitation models the observed attractive force between Matter

The Lagrange points mark positions where the combined gravitational pull of the two large masses provides precisely the right centripetal force required to rotate with them

Lagrange found his points of stabilty by subtracting the gravitational potential energy from the object's kinetic energy.

Copyright ABRAHAM [2008] - All rights reserved

Earth-Moon Gravito-Electro-Magnetic fields



$F = mv^2/r$
Orbital motion

The Moon's orbit is the result of the balance between Earth's gravitational attraction and the Moon's orbital velocity

1,023 m/s
[3,680 km/hr]

$F_g = -G\frac{M_1}{r^2}$

sqrt[GM/r]

strictly convergent gravity does not explain why the Moon is slowly moving away from the Earth at the rate of 3.8 cm per year

Gravitational tests in the region of any material body using Photons must also take into account EM interactions

Convergent gravity attracts 3D Material bodies towards each other

5.9736e24 kg
mass

These geometries reflect simple calculations. However, it assumes something we now accept without second thought:

That the pull of the Earth would be the same if all the mass of the Earth were concentrated in its center

6,371 km
radius

$\frac{6.67\,e{-11}\,N^2}{KG^2}$

1,738 m
radius

363,301 km
Gravitational fields are 1/r^2 fields

Earth's gravitational field on the Moon's surface is 1/3600 that of the field on the Earth's surface
$[1/60^2]$

The origin of the Earth's magnetic field has so far defied all attempts at a satisfactory solution.

$F = -G\frac{M_1 m_2}{r^2}$

Gravity is not what gives the Moon its velocity.

It has been theorised that whatever velocity the Moon has was probably acquired when it was created.

Gravity prevents the Moon from breaking out of Earth orbit and flying away, confining it to its known orbit

Tetryonics illustrates that along with the gravitational force the Earth's [k]EM field provides a interactive force to accelerate any bodies in its gravitational embrace.

It is this balance between Gravitational attraction interactive E-field forces & Magnetic perturbations that creates stable orbits over long periods of time

Divergent 2D kEM fields accelerate charged bodies creating stable orbits

The Gravitational field of the Earth is the result of its mass-Matter and can be modelled as a weak EM field

moon's orbital period
27.32 days . 24hr/day . 3600s/hr = 2,360,448 s

The Sun's gravitational effect on the Moon is over twice as great as the Earth's on the Moon

Tetryonics 74.06 - Earth-Moon EM interaction field

Copyright ABRAHAM [2008] - All rights reserved

The Earth's ElectroMagnetic field

Earth's magnetic field (also known as the geomagnetic field) is the magnetic field that extends from the Earth's inner core to where it meets the solar wind,


Solar particle ions attracted
Solar particle ions repelled
Solar particle ions repelled
Solar particle ions repelled
Solar particle ions attracted
S
S
W
E
N
N

It is the magnetic dipole field tilted at an angle of 11 degrees with respect to the rotational axis

The Earth's magnetic field is really generated by the motion of the Earth through solar & vacuum energies and it is enhanced by the molten alloys in the Earth's core

The magnetic poles precess and even flip over time

It protects the Earth from cosmic rays that would strip away the upper atmosphere leaving us exposed to UV & cosmic rays

At random intervals (several hundred thousand years) the Earth's field reverses (the north and south geomagnetic poles change places with each other)

Tetryonics 74.07 - The Earth's Magnetic field

The Earth's molten core

The Earth has an outer silicate solid crust, a highly viscous mantle, a liquid outer core that is much less viscous than the mantle, and a solid inner core.
Scientific understanding of Earth's internal structure is based on observations of topography and bathymetry.



Q

The SUN and planetary bodies are all charged Matter moving in, displacing and interacting with solar and vacuum energies

Dynamo theory suggests that convection in the outer core, combined with the Coriolis effect, gives rise to Earth's magnetic field.

KE

The energy that creates the Earth's magnetic field is supplied by the SUN via longitudinal waves of energy momenta

The solid inner core is too hot to hold a permanent magnetic field but acts to stabilize the magnetic field generated by the Earth's motion through the Stellar EM environment as it orbits the SUN

The Earth's molten core does not produce the Earth's magnetic field it enhances it

The force exerted by Earth's gravity can be used to calculate its mass, and by estimating the volume of the planet, its average density can be calculated.

Astronomers can also calculate Earth's mass from its orbit and effects on nearby planetary bodies.

Terrestrial Aurora

result from the interaction of the Earth's magnetic field and the energetic solar wind, which provides energised ions and photons to the polar regions of Planets




Solar particle ions attracted
Nitrogen [red]
Oxygen [green]
Northern lights [aurora borealis]
Nitrogen [blue]
Solar particle ions repelled
Solar particle ions repelled
Van Allen belt
Van Allen belt
Solar particle ions repelled
Nitrogen [blue]
Southern lights [aurora australis]
Oxygen [green]
Solar particle ions attracted
Nitrogen [red]

Aurora result from ionized atmospheric atoms gaining an excited electron, and subsequently returning it from its excited state to ground state [see T-QED]

The Van Allen radiation belt is a torus of energetic charged particles (plasma) around Earth, which is held in place by Earth's magnetic field



Aurora occur on many planets throughout the Solar system

Copyright ABRAHAM [2008] - All rights reserved

Absolute Rest Frames

Absolute Rest is intrinsically linked to the concepts of absolute time and space originally introduced by Sir Isaac Newton in the Philosophiæ Naturalis Principia Mathematica, which provided a theoretical foundation that facilitated Newtonian mechanics.

According to Newton, absolute time and space respectively are independent aspects of objective reality.

Rest in physics refers to an object being stationary relative to a particular frame of reference or another object



In Tetryonics an Inertial Rest frame can be determined by the absence of a Kinetic EM field & its Magnetic moment

The concepts of space and time were separate in physical theory prior to the advent of special relativity theory, which connected the two and showed both to be dependent upon the observer's inertial state of motion relative to other inertial frames.

In Einstein's theories, the ideas of absolute time and space were superseded by the notion of spacetime in special relativity, and by dynamically curved spacetime in general relativity.

$$p^2 = E = mv^2$$



$$\frac{p^2}{2} = KE = \frac{1}{2}Mv^2$$

In some of his later paper (especially in 1920 and 1924), Einstein gave a new definition of the aether by identifying it with "properties of space", and this aether can be called absolute, as long as its state cannot be influenced by Matter.

So he argued that Newton's absolute space can be considered as an "absolute aether". Also the four-dimensional spacetime of special relativity (which replaces the absolute space of Newton) would be some sort of "absolute aether", as its states cannot be influenced by Matter.

Tetryonics clearly establishes free space as a 3D volume filled with a interactive vacuum [aether] and EM energies against which any relative motion can be deduced by the presence (or absence) of divergent [K]EM fields produced as a direct result of Matter in motion additionally, 3D mass-Matter topologies displace the aether [vacuum energy field] producing convergent differential energy gradients [gravity fields]

Red-shifted Photonic Energies

Energy is ALWAYS conserved... longer wavelength [red-shifted] photon energies are a reflection of the time specific measurement of photonic energies at a particular distance from the source of the light

Photons

$$\frac{2\pi}{c^2}\left[\left[\overset{\text{Planck}}{m}\,\overset{\text{quanta}}{\Omega}\,v^2\right]\right]$$

mass velocity

EM waves

$$\frac{\text{EVEN}\,\pi}{c^2}\left[\left[\overset{\text{Planck}}{m}\,\overset{\text{quanta}}{\Omega}\,v^2\right]\right]$$

mass velocity

Photons are neutral, coupled charge equilateral mass-energy momenta geometries that radiate bilaterally at the speed of light in a vacuum



As photons radiate from a point source at 'c'

their EM energies diminsh as per the inverse square law



producing the familiar red-shifting of spectral lines



The red shift of Photons

$d\lambda$ df

According to special relativity, as something approaches the speed of light, the passage of time slows.
A twin moving at the speed of light would not age or change relative to the stationary twin.

General relativity additionally states that the cosmological red shift is the result of a photon traveling through an expanding space time field which causes the photon to loose energy and it's wavelength correspondingly increases.

A photon travels at the speed of light; therefore it will not experience the passage of time, therefore it will not change; yet it does.

The divergent spreading of EM energy over time from a source creates the spacetime aether

The Quantised Angular Momentum and Energy content are directly related through the geometry of Photons

Blue-shifted photon travelling towards observer

The EM mass-energy content of photons reveals photons to be a quantised electromotive field



All EM Energy waveforms (save Matter) radiate outward following the inverse square law & reducing their energy content over time

Red-shifted photon moving away from observer

The wavelength of a photon is related directly to its quantised mass-energy momenta geometry per unit of time



Tetryonic geometry relates photon mass-energy momenta to the constant velocity of light in a vacuum and its intrinsic quantised angular momenta

$$\frac{mc^2}{c^2} = KE = \frac{hv^2}{c^2}$$




s
8
7
6
5
4
3
2
1
E
m²
Ω
sec
hv
≠
hf
v
h
v
v²
c²
m
Ω
v
v²
c²
1/1
4
1/4
9
1/9
16
1/16
25
1/25
36
1/36
49
1/49
64
1/64
hv
v²

As EM energy radiates away from any point source

its wave-length increases

and it's lorentz contracted

in its direction of motion wrt the observer

QAM has the dimensions of Area/time [m²/s]

QAM is a hidden geometry within Planck's constant

Planck's constant is equilateral mass-energy momenta per second

2 charged Planck quanta form a EM photon of mass-energy momenta

postive Planck quanta

negative Planck quanta

We measure received photons of energy momenta as sinusodial waves of charged, equilateral mass-energy momenta per second

As the elapsed time period is increased
the equilateral mass-energy momenta geometry
is spread over a greater area creating longer wavelengths

Tetryonics 75.04 - Doppler wavelengths

The Doppler shifting of EM waves

Photons

$$\frac{2\pi}{c^2}[[m\Omega v^2]]$$

Planck quanta
mass velocity

General relativity incorrectly holds that the cosmological red shift is the result of a photon traveling through an expanding space time field which causes the photon to loose energy and it's wavelength correspondingly increases

EM waves

$$\frac{EVEN\,\pi}{c^2}[[m\Omega v^2]]$$

Planck quanta
mass velocity

Photonic energies form
infitie energy loops
[quantum transformers]

It is the Photon's intrinsic geometry that increases the further it travels from the source due to the inverse square law resulting in less energy (per unit of time) being recieved at increasing distances from the source as the Photon's specific QAM [m²/s] has increased over time

All EM waves are comprised
of Photons of specific energies
[Light is superpositioned EM waves]

All Photons are quantum harmonic oscillators
and create sinusoidal EM waveforms
are they radiate and are detected



Photons are 2π
divergent bi-directional
mass-energy momenta
geometries

Photonic mass-energies
always propagate at
c

Radiating geometric EM mass-energies
from a source (over Distance-Time)
creates the spatial vacuum aether



Blue-shifted

observer moves towards source *or* source moves towards observer

*Any relative motion between the source & observer
that reduces the distance between them
produces a Blue-shift in the measured
quanta-frequency/ energy of the EM wave*

observer moves away from source *or* source moves away from observer

Red-shifted

Red-shifted

source moves away from observer *or* observer moves away from source

*Any relative motion between the source and observer
that increases the distance bewteen them
produces a Red-shift in the measured
quanta-frequency/ energy of the EM wave*

source moves towards observer *or* observer moves towards source

Blue-shifted



Tetryonics clearly shows and relates
Time to quantised angular momentum
and Planck energy momenta to velocity

The energy of indiviudal photons is
invariant until they interact with Matter
and transfer their mass-energy momenta

*motion toward the source
increases the number of
quanta per sec measured*

[v+v]



*Poor definintions of Energy per unit of Time
along with the interchange of quanta and frequency
have led to the mistaken concept of photons losing energy*

$$mv^2 = E = hv^2$$

*Photons DO NOT lose energy as they travel.
the group energy [per unit of time] of the EM wave
they form spreads out over time as a direct result
of the inverse square law*



*motion away from the source
decreases the number of
quanta per sec measured*

[v-v]

**Cosmological doppler-shifting of Light
is the direct result of the motion
of Matter in the Universe**

**Gravitational Red-shifting
is an EM effect
not gravitational**

Copyright ABRAHAM [2008] - All rights reserved



Relativistic Corrections

are applied to only [kinetic]EM mass-energy geometries

$$\frac{Mv^2}{c^2} = KEM = \frac{hv^2}{c^2}$$

$d\lambda$

Wave-length contraction

linear
Lorentz corrections

$$\beta = \left[\frac{v}{c}\right]$$

SR - measuring rods in differing interial frames have different contracted lengths

GR - lengths measured in curved spacetime are different to straight lines in flat spacetime

$$\frac{\Delta\Omega}{c}$$

dt

Time Dilation

scalar
Lorentz corrections

$$\beta^2 = \left[\frac{v^2}{c^2}\right]$$

SR - clocks in differing inertial frames experience time dilation

GR - clocks in differing Gravitational fields experience time dilation

$$\frac{\Delta\Omega}{c^2}$$

kEM mass-energy geometries
are subject to Lorentz corrections

scalar energy momenta

$$\frac{T\pi}{c^4}\left[\left[m\Omega v\right]^2\right]$$

linear momentum

The mass-energies of standing-wave Matter topologies are Lorentz invariant

Tetryonics 75.06 - Relativistic corrections

GPS relativistic corrections

Claims that the Global Positioning System (GPS) provides a valid test of General relativity are erroneous
[GR provides Lorentzian [SR] correcttions under the guise of Gravitational effects]

Photons are mass-energy momenta quanta
[they are Matter-less NOT mass-less]
and are subect to Lorentz Forces and corrections

Newton G + SR = GR *Einstein*
Lorentz

Graviational Matter

M

All Matter topologies produce a Gravitational field

Newtonian Gravity
is universal

The gravitational effects caused by Matter can only be accurately modelled [or tested] through the exclusion of all EM fields interactions



Interactive masses

m

All Matter in motion produces interactive mass-energies



General Relativity
is limted to c

Any test of GR using Photons as a testing mechanism by definition is affected by and subject to Special relativity [ElectroMagnetic effects]

The 'gravitational' frequency shifting [Red-Blue shifting of EM waves] is in fact an electromagnetic effect



The Bending of Light

The 'Gravitational bending' of light as it passes close to Matter
is a scientific misnomer

EM waves of light are refracted by the
EM plasma enviroment
of any star

*Like the Perihelion of Mercury,
the bending of Light due to Gravity
as it passes near the limb of the Sun is a
flawed test of GR that fails to distingush between
Gravitational Matter and EM mass interactions
due to GR's use of a Stress Energy Tensor that
is reflective of all EM mass-ENERGY-Matter
in the system being measured.*

*According to General relativity,
a light ray arriving from the left
would be bent inwards such that its
apparent direction of origin, when viewed
from below would differ by an angle (a),
whose size is inversely proportional to
the distance (d) of the closest approach
of the ray path to the center of mass.*

**All Light and EM waves
are 2D ElectroMagnetic masses
and are unaffected by gravity**

**All Light and EM waves
are deflected and dispersed
by ElectroMagnetic interactions**

$$4\pi G + 4\pi SR = 8\pi GR$$

**3D standing-wave
gravitational
mass-Matter**

**2D radiant
electromagnetic
mass-energies**

Light waves passing close to Massive objects
experience a measureable DEFLECTION in their paths
due to the ElectroMagnetic interaction of EM mass-energies

Gravitation is a result of convergent vacuum energy densities
produced by toplogical EM mass-energies of Matter
& their interactive mass-energy geometries

Q
RE
mass-energy momenta
KE
geometry
Apparent position
θa
Newton
Einstein
Lorentz
correction
M
KE
c4
n1
n2
n3
n4
n6
n7
n8
Atomic
shells
Quantum
levels
M
topology
KEM
geometry

Tetryonics 75.08 - The Bending of Light

The Perihelion of Mercury

is the result of EM interactions in addition to gravitational attraction

The perihelion of Mercury's orbit precesses at a measurable rate, but even after accounting for gravitational perturbations caused all other planets in the solar system, Newton's theory (assuming a precise inverse-square relationship for distance) predicts a rate of precession that differs from the measured rate by approximately 43 arcseconds per century.



Both Newton and Einstein saw Gravity as a singular force of attraction between objects and developed their math accordingly from the observed motions without any physical distinction between mass & Matter

$4\pi G$

$8\pi G$

Newton modelled only the observed nett attractive force of Matter in the system

Einstein modelled the nett convergent force of all energies without differentiation

$$F = -G\frac{M_1 m_2}{r^2}$$

$$G_{ab} = \kappa T_{ab}$$

Universal gravitation is the result of the convergent gravity AND interactive EM fields in any spatial region

c^4

Newton

G

Einstein

G+EM

Newton Lorentz

General relativity was developed in part to provide an estimate for this rate of precession that better matches observations.

Newton's theory can also be 'incorrectly modified' to explain this perihelion by factoring in the gravitational pull due to other planets or making tiny adjustments to parameters in the gravitational equation to reflect the effect of ElectroMagnetic interactions between the Sun and Mercury.

By modelling the quantum interactions of ALL GEM mass-ENERGIES and their distinct geometries Tetryonic theory explains recently measured discrepancies in both Newtonian & GR formulations of Gravity

Copyright ABRAHAM [2008] - All rights reserved



Gravity
Gravity + M-field pertubations
μ
μ
η
η
Gravity + E-field interactions
Gravity + E-field interactions
Gravity + M-field pertubations
Gravity
GEM pinches power all Stars
S
8πG
Mercury
Venus
Earth
Mars
Asteroid Belt
Jupiter
Saturn
Neptune
Uranus
4πG

Universal Gravitation

Close to gravitational Matter sources 4π Newtonian gravity has to be modified with SR corrections to account for [K]EM field interactions

At larger distances 8π GR reduces to 4π Newtonian gravity

Perturbative M fields have inverse squared geometries

The SUN's longitudinal wave emissions creates interaction-at-a-distance

All the major solar bodies orbit within the interactive Stellar E-field

Perturbative M -dipole fields have inverse cubed geometries

Convergent Gravitational fields and interactive Electric fields are inverse squared fields of differing strengths

The SUN's GEM field

Tetryonics 76.01 - The SUN's GEM field

Copyright ABRAHAM [2008] - All rights reserved



SUN-Earth-Moon GEM fields

Using equilateral [Tetryonic] GEM field geometries, a visual representation of the SUN-Earth-moon GEM interactions can be created

The interactive Magnetic dipole force is a inverse cubed force whereas the interactive Electric force is an inverse squared force [as is Gravity]

$$F = k\frac{Q_1 Q_2}{r^2}$$

$$F = k\frac{Q_1 Q_2}{r^2}$$

$$F = -G\frac{M_1 m_2}{r^2}$$

The Gravitational force of Matter is co-incidental to [and weaker than] the divergent interactive forces of E fields

$$F = -G\frac{M_1 m_2}{r^2}$$

Note: the SUN-Earth GEM field interactions [coupling strengths] are not to scale.

In reality they are all the same size with differing energy densities/c^4 [as illustrated in Earth-moon system]

Tetryonics 76.02 - SUN-Earth-moon GEM fields



GEM field accelerations

All GEM fields are comprised of:

Convergent G fields
Interactive E fields
Perturbative M fields

Measurements of any GEM field using photons or EM waves is a SR correction of E field interactions

Interactive KE fields are geometrically co-incidental with the convergent Gravity fields of Matter

The position of the Moon in its orbit will either increase or decrease the EM field accelerations of the SUN-Earth-moon system

Convergent G fields & Interactive E fields are inverse squared field geometries

Perturbative dipolar M fields have inverse cubed field geometries

Spacecraft entering the Earth-moon system will experience accelerations due to the interactive GEM fields of the system

Tetryonics 76.03 - GEM fields [Polar]

Copyright ABRAHAM [2008] - All rights reserved

GEM field accelerations

All GEM fields are comprised of:
Convergent G fields
Interactive E fields
Perturbative M fields

Interactive KE field vectors are geometrically co-incidental with the strictly convergent vector of Gravity

The Electric field forces of GEM fields are produced by Longitudinal EM waveforms



The angle of incidence with any interactive EM field has an impact on the acceleration experienced

The position of the Moon in its orbit will either increase or decrease the EM field accelerations of the SUN Earth-moon system

0-30 degree [Equator-Tropic] E-field interactions create inverse squared accelerations

30-90 degree [Tropic-Polar] M-field interactions create inverse cubed purturbations

The combined interactions of GEM fields create the nett convergent motional force we have historically observed and modelled as gravity

Strictly Newtonian Gravity fields are the result of the spatial energy differential created by Matter as it topologically displaces the surrounding Vacuum Energies

Convergent G fields & interactive E fields are inverse squared geometries

Perturbative dipolar M fields have inverse cubed geometries

Side elevation

Tetryonics 76.04 - GEM fields [Side]



Gravitational flyby accelerations

All Material bodies
[Matter] are comprised
of charged fascia
mass-energies

All Material bodies
[Matter] in motion create
KEM fields in addition to
their Gravitational fields

*The E-field acceleration of Matter
due to interactive co-linear momenta is
evidenced with the acceleration of
the moon away from the Earth over time
[against the strictly convergent force of Gravity]*

*Additional to the velocity changes
acheived due to the spacecraft's
angle to the planet's equator and
the assymmetry of the flyby will
affect its KEM interactions*

*As Gravity pulls
the Moon towards to Earth*

*The position of the Moon
in its orbit wrt spacecraft flybys
will create minute increases or
decreases in its osberved velocity
in addition to that calculated
from purely G-field calculations*

*The Earth's EM field
provides a constant outward force
to create a stable orbit*

*Spacecraft entering the Earth-moon system
will experience accelerations due to the
interactive GEM fields of the system
[Gravito-Electro-Magnetic assists]*

*The Lorentz force satisfies all of the known effects of the Earth
flyby anomaly. It is physical, nonconservative, bidirectional,
distance-dependent, and affected by orbital declinations
[ie E-field accelerations of charged Matter]*

Measurements of any Gravitational
field using photons or EM waves is
a SR correction measurement of the
EM field component of GEM fields

Gravity & EM field forces at work

The motion of all Matter
requires Lorentz corrections
for velocities obtained from
the flybys of planetary systems

Tetryonics 76.05 - Gravitational flyby accelerations

Flyby anomalies



ALL Matter creates GravitoElectoMagnetic fields

The flyby anomaly is an unexpected velocity increase that occurs during Earth-flybys of spacecraft.

This anomaly has been observed as shifts in the S-Band and X-Band Doppler and ranging telemetry.

Taken together it causes a significant, unaccounted velocity increase of spacecraft during flybys.

SR is a Lorentz correction of photons within EM fields

Any measurement of GEM fields must take into account:

E-field accelerations

M-field perturbances

and the position of ALL Matter wrt other bodies in the system that contribute to GEM field interactions

Spacecraft flybys in this region of GEM fields experience E-field interactions

$$F = k\frac{Q_1 Q_2}{r^2}$$

$$F = -G\frac{M_1 m_2}{r^2}$$

Measurements of 'Gravitational shifts' obtained through the measurement of EM energy transmissions is erroneous.

The changing wavelength-velocity-frequency is the result of interactive E-field accelerations [NOT Gravity fields]

Spacecraft at great distances from material bodies are affected by convergent Gravitational fields [Newtonian gravity]

Spacecraft travelling closer to material bodies are affected by interactive E-fields as well as G-fields [General Relativity]

Tetryonics 76.06 - Flyby anomalies

Newtonian Gravitation

$$F = -G\frac{M_1 m_2}{r^2}$$

measures the nett gravitational attraction
of Matter towards other Matter
[using weak [K]EM fields]

Pioneer anomaly

Despite many proposed solutions,
there is not yet an accepted explanation
for the cause of the Pioneer velocity anomaly


Viewed down from north ecliptic pole
Pioneer 10
'92
'90
'88
'86
'84
'82
'80
'78
'76
'74
'75
'77
'73
Jupiter
Mars
Saturn
Uranus
Neptune
Pluto
Earth
Sun
'79
'81
'82
'83
'84
'85
'86
'87
'88
'89
'90
'91
'94
'92
Voyager 2
Pioneer 11
Voyager 1

Many proposals
have been put forward to
explain this unexpected
acceleration towards the Sun

The modelling of solar
Spacecraft motions using
either Newtonian Gravitation
or Einstein's General relativity is
problematic as neither model
accurately reflects the true, dynamic
GravitoElectroMagnetic interacitons
of our Solar system and its environment

Tetryonic GEM interactions shows
that the measured acceleration is
the result of a weakening, inverse
squared stellar EM interaction
throughout the Solar heliopause

This would result in
a decrease in divergent
acceleration away from the Sun
which has been mis-interpretted as
an acceleration toward the Sun

General Relativity

$$G_{ab} = \kappa T_{ab}$$

calculates for the total Gravitational and
EM interactions for energy in all its forms
[using Energy pressure gradients]

"Both Pioneer spacecraft are escaping the Solar System, and are slowing under the influence of the Sun's nett gravitational [GEM] field.

Upon very close examination of navigational data, the spacecraft were found to be slowing slightly more than expected.
The effect is an extremely small but unexplained acceleration towards the Sun, of 8.74±1.33×10−10 m/s2"

Tetryonics 76.07 - Pioneer anomaly



co-linear momentum forms an inflexible path for the propagation of linear forces between separated objects of mass-Matter

The SUN radiates longitudinal mass-energy momenta from the collapse of Matter in its GEM pinch core

instantaneous interaction-at-any-distance

electrostatic field co-linear momentum

as the energy field density increases so does the physical force one object can exert on another

as Matter radiates longitudinal waves of energy momentum - the co-linear momentum vectors form 'rigid rods' that can facilitate the transfer of instantaneous impulses of physical force bilaterally in real time between objects of mass-Matter irrespective of time and distance between the objects

EM waves propagate at the speed of light - co-linear momentum impulses can propagate instantly for as long as the field exists between the objects

Tetryonics 76.08 - Co-linear momentum [interaction-at-a-distance]

Copyright ABRAHAM [2008] - All rights reserved

Instantaneous interaction-at-a-distance

One of the major points of disagreement between Newtonian Graviation and General Relativity concerns Einstein's limiting of information and energy momenta propagation to the speed of light whereas the Newtonian physics for Gravitation acts instantly between Matter irrespective of distance and time

particles interact with others in real time irrespective of distance


The SUN's electrostatic field
The Earth's ElectroMagnetic field
Coulomb
EM waves propagate at c
SR
charged
Q
M
mass-Matter
charged
Q
M
mass-Matter
electromagnetic waves & co-linear momentum transfer
Newton
Gravity acts instantly
GR

the flow of energy and information is limited to the speed of light

Where electrostatic and/or electromagnetic fields overlap they form fields of interaction between bodies of Matter

the 'quantum rods' of co-linear momentum in their EM fields facilitate 'FTL spooky interaction-at-a-distance' facilitating near instantaneous [real time] impulses of linear momentum to convey physical forces over vast distances without loss for as long as the fields exist between the objects

Tetryonics 76.09 - Instantaneous interaction-at-a-distance

The efficient wireless transmission of electrical energy requires the creation of a large electrostatic field of longitudinal energy momenta



The key to wireless energy is the use of LONGITUDINAL EM voltages such as those produced by spark gaps

Nikola Tesla was the first to promote the use of Longitudinal EM waves as a source of wireless energy

Once generated by EM pinch [or other spark gap technologies] real electrical power can be transmitted wirelessly through the air without loss using LONGITUDINAL waves of energy momenta

where upon its reciept at distant locations near instanteous impulses of linear momentum can be utilised to produce electrical work for any number of devices utilising an earth return

Since the discovery of the photo-electric effect at the turn of the 19th century electrical engineering and physics theory has focused on transverse Hertzian waveforms to the exclusion of longitudinal waves

For the efficient generation, production and storage of electrical energy to met ALL of Humanities growing energy needs, electrical engineering practices must move from transverse wave technologies to longitudinal waves

Transverse EM waves are in-efficient for transmitting energy over distances as their linear energy momentum is not co-linear with their direction of proagation

The lossless transmission of power over any distance, including to and from orbital platforms & remote locations on Earth, can at last be made into a physical reality

Copyright ABRAHAM [2008] - All rights reserved

Super-luminal communications

Creating a near instantaneous real-time communications network



Once established the linear energy momenta of a scalar electric field

acts as a rigid rod along which impulses of momentum can be instantaneous transmitted

Utilising Tesla's spark gap technology we can establish a longitudinal communications link with distant points that we wish to talk to

Distance and Time will become irrelevant to information telecommunications

Information would need to be encoded in a digital impulse form akin to Morse code



Once recieved at the end station the information could be decoded and rebroadcast as transverse waves to the local stations

Orthagonal electromagnetic waves can also propagate along the rigid rod of momentum but only at the speed of Light

Tetryonics 76.11 - FTL Communications

Copyright ABRAHAM [2008] - All rights reserved



Having already shown how to transmit and recieve information in real time over vast distances.

All that remains is to establish a communications network between different stars and galaxies

Interstellar communications

Establishing a real-time interstellar communications network

Sending spacecraft to each star in order to establish longitudinal wave communications is simply impractical, however a solution to this problem is apparent

Instead of 'beaming' transverse radiowaves into space or searching for the same arriving from other planets

Any advanced technological civilisation becoming aware of longitudinal waves should look to their local star for signs of life in the Universe and use it to communicate with other lifeforms

All Stars emit continuous longitudinal energy momenta in the form of radiant EM waves and have done so since they formed providing a natural backbone for a real-time interstellar communications network

Tetryonics 76.12 - Interstellar communication

Copyright ABRAHAM [2008] - All rights reserved

Mercurial anomalies

Mercury has a weak magnetic field


Mercury
Bow Shock
One Solar Day = 176 Earth Days
Thin Mantle
Large Core
2439 km
Temperature up to 360°C
SUN
Heat up to 10 times more intense than at Earth
Magnetic Field
Magnetotail
Temperature down to minus 140°C

Mercury has heat of its own, not just reflected heat of the Sun;

Mercury has still an atmosphere of Hydrogen, possibly the last vestiges of a more extensive halo and trail (caduceus)

Mercury rotates because it is in its present orbit it is strongly affected by the EM field of the SUN,

Because the ElectroMagnetic forces near the Sun need to be accounted for in the motion of any satellite about a more massive body [ie Satellite-Planet or Planet- Sun], the stronger E & perturbative M forces are responsible for the observed precession of the perihelion of Mercury, and Leverrier's discovery of this precession can be modelled with Einsteins' General relativity through Tetryonic geometries

Laplace showed that should a celestial body attracted by its primary as inverse square of distance be subject to another attraction that changes as the inverse cube of distance, a precession by that body would result.


P1
P2
P3
Sun
Mercury

Einstein corrected Newton's gravitational results by calculating for ALL the energies in a system but failed to realise that his 'graviational correction' was in fact a Lorentz correction for EM interactions

Copyright ABRAHAM [2008] - All rights reserved

Venusian anomalies

is sometimes referrd to as Earth's "twin" owing to their similar size, gravity, and bulk composition.



Venus has the densest atmosphere of all the terrestrial planets
in the Solar System, consisting of mostly carbon dioxide.
The atmospheric pressure at the planet's surface is 92 times that of the Earth.



Galileo's discovery that Venus showed phases
(while being never very far from the Sun in our sky)
proved that it orbits the Sun and not the Earth

**Venus is the hottest world in the solar system.
Although Venus is not the planet closest to the sun,
its dense atmosphere traps heat in a runaway version
of the greenhouse effect that warms up the Earth.**

As a result, temperatures on Venus reach 465 degrees C

The lack of an intrinsic magnetic field at Venus was surprising
given it is similar to Earth in size, and was expected also to
contain a dynamo at its core

Venus has no moons or rings

The Venusian year is about 225 Earth days long.

Venus takes 243 Earth days to rotate on its axis,
which means that days on Venus would be longer
than years. However, because of Venus' curious
retrograde rotation, the time from one sunrise
to the next is only about 117 Earth days

The very top layer of Venus' clouds zip around the planet
every four Earth days, propelled by hurricane-force winds
traveling roughly 224 miles (360 kilometers) per hour.

This super-rotation of the planet's atmosphere, some 60 times faster
than Venus itself rotates, may be one of Venus' biggest mysteries.

Earth-Moon anomalies

The Moon is slowly accelerating away from the Earth

Athough it is attracted gravitationally to the Earth the Moon is moving away from the Earth at about 4cm per year as a result of the Earth's EM field interactions with Matter in its vicinity.

The Moon's Origin

Most scientists think the moon was born from a gargantuan collision, when a young, 30-million-year-old Earth was sideswiped by an embryonic planet the size of Mars some 4.5 billion years ago, with debris from our planet and this impactor eventually coalescing from the ejecta to form our Moon.

The Lunar a lunar day is a month long,
the same as the Moon's orbital period



The Earth's EM field accelerates the moon against the pull of gravity stabilising its orbit
its current field strength forces the moon to slowly accelerate away from the Earth over time

The Moon only shows one face to the Earth

it is gravitational locked in its orbit with one side
always facing the Earth when viewed from the Earthat night.
There is no such thing as the "dark side of the moon".
The sun shines on all sides

The Moon is 400 times smaller than the SUN
The SUN is 400 times more distant

The Moon looks exactly the same size as the Sun

"There is no astronomical reason why the moon and the sun should fit so well. It is the sheerest of coincidences, and only the Earth among all the planets is blessed in this fashion." ....Isaac Asimov

A striking coincidence that has had astronomers thinking since ancient times is why the Sun and the Moon appear to be the same size during an eclipse. It's known that the Sun's diameter is 400 times that of the Moon, but, then again, the Moon is 400 times further away from the Sun.

This creates the optical illusion that the two are actually the same size, allowing us to observe the Solar corona and its EM field lines

Our moon is the only moon in the solar system that has a stationary, near-perfect circular orbit. Stranger still, the moon's center of mass is about 6000 feet closer to the Earth than its geometric center (which should cause wobbling), but the moon's bulge is on the far side of the moon, away from the Earth. "Something" had to put the moon in orbit with its precise altitude, course, and speed.

Martian anomalies

Phobos

There is no completely satisfactory theory as to how Deimos and Phobos came to be in orbit around Mars

With a dametre of 6 km Deimos
is one of the smallest known moons
in the solar system

Deimos

Although Mars is much smaller than Earth, [approx 1/4 the size]
its surface area is about the same as the land surface area of Earth

Deimos and Phobos are probably asteroids perturbed
by Jupiter into orbits that allowed them to be captured by Mars

The southern hemisphere of Mars
is predominantly ancient
cratered highlands somewhat
similar to the Moon.

In contrast, the northern hemisphere
consists of plains which are much younger,
lower in elevation and have a much
more complex history.

Mars orbits about
1.5au from the SUN

An abrupt elevation change of several kilometers seems to occur at the boundary

Copyright ABRAHAM [2008] - All rights reserved

Jupiters' anomalies

Jupiter has an intense and far-reaching magnetic field.
Exactly what drives the magnetic powerhouse and
how deep inside the planet it originates, however, is unknown

Jupiter's diameter is approx
1/10 that of the SUN and
10 times the size of Earth

Jupiter has twelve satellites.

The five inner moons revolve around their planet in orbits only slightly inclined to the planet's equator at distances from about 110,000 miles for the innermost to about 640,000 miles for the outermost.

Jupiter's mass is 2.5 times that of all the other planets in our Solar System combined



Tetryonic EM geometry
offers answers to many of the dynamic
mysteries of Jupiter and its moons

Then there is a group of three moons whose orbits are inclined to the planet's equator by almost 30° at distances of about 7 million miles from Jupiter.

These three moons also revolve around the planet in the predicted direction.

The four outer moons, however, move around the planet in retrograde motion, or opposite to that of the other eight satellites, at distances from about 12 to 13 million miles from the planet



Its Great Red Spot
has a circumference
about the same as the Earth

Jupiter also has the most energetic auroras in the solar system at both of its poles

Copyright ABRAHAM [2008] - All rights reserved

Saturnian anomalies

In addition to the planet's giant rings, Saturn has nine major moons and more than 60 known satellites.

The motion of the outermost, Phoebe, is retrograde, moving in a direction opposite to the other eight moons and opposite to that predicted from an evolutionary origin.

Tetryonic theory suggests that this retrograde motion is the result of it being a gravitationally captured body whose motion over time will be slowed, eventually forcing it into the same motion as the others

TITAN
is the only moon that
possesses a thick atmosphere, and
it's the only place beyond Earth to have
stable bodies of liquid Methane on its surface

The rings of Saturn occasionally exhibit ghostly radial spokes that seemingly defy the laws of gravity

The Saturnian rings, like many others, are formed by the electric field of the planet and subject to seasonal fluctuations of the SUN's heliosheric E-field

Tetryonic GEM interactions shows that these features are the result of electric forces additional to gravity

Strange features abound within the rings of Saturn. These include hundreds of "record grooves" or narrow fluctuations in the B ring, the most massive ring.



These also include "plateaus" in the C ring, the innermost main ring—broad, dark, sharp-edged features thicker than elsewhere in the ring.

Copyright ABRAHAM [2008] - All rights reserved

Neptunes' anomalies

Neptune was the first planet found by mathematical prediction
rather than by empirical observation

Neptune has two satellites.

Nereid, a small moon, moves around Neptune in the predicted direction, but Triton, one of the larger satellites in the solar system with a mass almost twice that of the earth's moon.

Of Neptune's 13 moons, Triton is by far the biggest and the only one massive enough to be spheroidal.

Weirdly, Triton has a "retrograde" orbit, revolving in the opposite direction of the planet and other moons.

Plus, the orbit is at an angle rather than in the plane around the equator like typical satellites

The magnetic field of Neptune, like that of Uranus,
is highly tilted at 47 degrees from the rotation axis and offset
at least 0.55 radii (about 13,500 kilometers or 8,500 miles) from the physical center

Copyright ABRAHAM [2008] - All rights reserved

Uranus' anomalies

Uranus is remarkable, even though it rotates around the sun in the same direction as the other planets in an orbit inclined less than a degree (46') from the ecliptic (the plane of the earth's orbit around the sun), the axis of rotation of Uranus is nearly in the plane of its orbit.

Accordingly, the inclination of the equator of Uranus to the plane of its orbit is 98°, and its axial rotation is retrograde.

The five moons or satellites of Uranus move exactly in the equatorial plane of the planet and they revolve in the same direction as the planet rotates.

Their motion, with respect to the remainder of the solar system, is, therefore, also retrograde.

Tetryonic theory dictates that Uranus' peculiar planetary mechanics may be the result of the EM interactions of Uranus itself with its satellites rather than the current evolutionary explanation

The direction of the axial rotation of Uranus and the motion of its satellites is opposite to that predicted on the basis of an evolutionary origin.

Pluto's anomalies

Pluto is much smaller than any of the official planets
and due to its size and orbital inclination
is now classified as a "dwarf planet"


P4
Hydra
Charon
Nix
Pluto
50,000 miles
80,500 kilometers
N
E

Pluto rotates in the opposite direction
to that of most of the other planets

Pluto is locked in a 3:2 resonance with Neptune;
i.e. Pluto's orbital period is exactly 1.5 times longer than Neptune's.
Its orbital inclination is also much higher than the other planets

Pluto's orbit is highly eccentric.
At times it is closer to the Sun than Neptune

Charon is unusual in that it is
the largest moon with respect to its
primary planet in the Solar System
(a distinction once held by Earth's moon)


PLUTO
NEPTUNE
JUPITER
SATURN
URANUS

The Pluto–Charon system is noteworthy
for being one of the Solar System's
few binary system

Pluto
Nix
Hydra
Charon

Copyright ABRAHAM [2008] - All rights reserved

Cometary anomalies

Comets provide some of the clearest evidence of Electromagnetic interactions between the SUN and other planetary bodies

While the solid nucleus of comets is generally less than 50 km across, the coma may be larger than the Sun, and Ion tails have been observed to extend 3-4 astronomical units (5-600 million km)

Cometary discharging may also occur due to any disturbances of its electrical plasma sheath as it passes through regions of varying electric potential.

This seems to have occurred in the recent "totally surprising" outburst of Comet Holmes 17P as it moved away from the Sun's domain.

In 2000 the explosive break up of Comet Linear provoked great amazement as the event occurred well over a hundred million kilometers from the Sun

Other anomalies that can be explained by a CHARGED model of cometary nuclei are: Unexpectedly high temperatures and X-ray emissions from cometary comas

The sharply carved relief of comets [the exact opposite of what is expected under the "dirty snowball" model]

The unexplained ability of a relatively minuscule comet nucleus to hold in place a highly spherical coma, up to millions of miles in diamater, against the force of the solar wind;

Ejection of larger particles and "gravel" that was never anticipated under the idea that comets accreted from primordial clouds of ice, gas, and dust;

A short supply or complete absence of water and other volatiles on comets' nuclei;

The Electric Universe's model of charged solar bodies predicted the occurrence of an electrical flash in advance to the impact of a projectile into the nucleus of Comet Tempel 1 (Deep Impact.)

Comets have two tails:
A Dust tail and
A Ion tail
most recently observed
in comet Hale-Bopp

The Dust tail is the result of reflective ejected Matter following the comet's path throught solar system while the Ion tail is the result of ejected charged particles of Matter and is heavily influenced by the SUN's radiated E fields



In deep space comets are subject to only convergent gravity

deceleration

Comets move in highly ellipical obits compared to the planets

Comets like planetary bodies are subject to EM interactions from the SUN on their orbits

acceleration

the radiant EM field of the SUN forces the comet's tail to always point away from it

close to the SUN EM interactions take place and comets are accelerated into their elliptical orbits

As they decelerate they are attracted back toward the SUN

The tails of comets always point away from the Sun, so after a comet has passed the Sun it actually travels tail first

Copyright ABRAHAM [2008] - All rights reserved



The Plasma universe

Plasma in space consists of
energetic ions and electrons
[accelerated charged particles]

Ionised plasma is the fourth & most common
state of ordinary Matter, most of which
is found in the rarefied intergalactic
medium and in stars

*Charged electromagnetic fields
are the unseen purveyors of Force and creators of structure
in our Universe*

Only when mass-energies form standing-wave
topologies does it create the states of Matter
we are familiar with here on Earth:
solids, liquids, and gases

Where there are Magnetic fields there are Electric fields,
modern radio-astronomers often map the magnetic lines
of force to the exclusion of electric currents in the mistaken
belief that electric fields do not exist in space

Copyright ABRAHAM [2008] - All rights reserved



Cosmic GEM pinches

Black Holes do not exist

radiant
E
2D mass-energy geometries
standing-wave
M
3D mass-Matter topologies
Magnetic fields
Electric fields
Galactic
GEM
θ
pinch
singularity
Electric fields
Magnetic fields

Galaxies are held together
and structured by EM fields

Dark Matter & Dark Energy
are manifestation of EM forces

The conversion of Matter to Energy
in GEM pinches on all-scales
is 100% efficient

Tetryonics 78.02 - GEM pinches

Copyright ABRAHAM [2008] - All rights reserved



PLASMA FIELDS

The Cosmos is
electromagnetic
in nature

Plasma fields create the most tenous forms of a pure Electrical field, and being a EM field they are also exceptional conductors of energy and accelerators of charged Ions

Magnetised Plasma fields
neutral electric charge EM fields
(with a magnetic magneton)

Charged Plasma fields
charged electrostatic EM fields
(with no magnetic magneton)

Neutron stars

Matter

antiMatter

Accretion discs

Gamma rays

Magnetars

Pulsars

Tetryonics 78.03 - Plasma Fields

Copyright ABRAHAM [2008] - All rights reserved

Neutron Stars

All Gravitational fields
are comprised of quantum
GEM fields

In current astrophysical theories in order to create a

Neutron star

the central region of the star collapses under gravity.

It collapses so much that protons and electrons
combine to form neutrons. and neutrogenic Matter

Hence the name "neutron star".



Typical Neutron stars have
very strong M-fields

Contrary to current theories
any star with strong dipolar M-fields
must also possess neutral E-fields

"A neutron star is a type of remnant that can result from the
gravitational collapse of a massive star during a Type II,
Type Ib or Type Ic supernova event.

Such stars are composed almost entirely of neutrogenic Matter,
[Neutrons, antiNeutrons and neutrinos] which against
current theory act in exactly the same manner as
ordinary Matter in producing spectral lines.

*"Neutron stars are very hot and are supported against further
collapse because of the Pauli exclusion principle.*

*This principle states that no two neutrons (or any other fermionic
particle) can occupy the same place and quantum state simultaneously""*

As shown throughout Tetryonic theory
Neutron stars can be formed
comprised completely of 'Neutral Matter'

Neutral Matter is comprised of
Neutron - anti-Neutron - Neutrino
atomic nuclei

Neutral matter atoms function identically to
normal matter-antimatter particle topologies
and releases energy in the form of photons

The gravitational collapse of any
stellar material must overcome
the radiant EM energies that it
releases

Pulsars are non-neutral stellar
objects that have weak M-fields
but emit extremely strong E-field
radiation as they collapse

Neutral matter in Neutron stars experience the same ElectroMagnetic forces as
normal matter and anti-matter stars but have differing charge arrangements



Magnastars produce
extreme magnetic fields

Neutrons &

Neutronium formation

neutrinos

Neutronium is a proposed name for a substance composed entirely of Neutrons & neutrinos

Neutron degeneracy

As a star collapses, the Fermi energy of the electrons increases to the point where it is energetically favorable for them to combine with protons to produce neutrons (via inverse beta decay, also termed "neutralization" and electron capture)

This, as shown through Tetryonic geometry, is incorrect

Neutrons are NOT comprised of Protons with electrons fused into them under pressure

Gravitational fields are comprised of convergent gravity and interactive EM fields



"The gravitational field at the star's surface is about 2×10^11 times stronger than on Earth.

Such a strong gravitational field acts as a gravitational lens and bends the radiation emitted by the star such that parts of the normally invisible rear surface become visible"

Photons and EM waves are REFACTED by EM fields NOT bent by gravity as currently hypothesized

Neutronium

$$\frac{T\pi}{c^4}\left[\left[\underset{\text{mass}}{m}\,\overset{\text{Planck quanta}}{\Omega}\,\underset{\text{velocity}}{v^2}\right]\right]$$

The neutral nuclei of neutron stars emit exactly the same light as normal stars do

Neutron stars are made of neutronium nuclei

A neutron star is a type of stellar remnant that can result from the gravitational collapse of a massive star during a Type II, Type Ib or Type Ic supernova event.

Such stars are composed almost entirely of neutrons, which are subatomic particles without electrical charge and with the same mass-Matter as protons. Neutron stars are very hot and are supported against further collapse by quantum degeneracy pressure due to the Pauli exclusion principle.

This principle states that no two neutrons (or any other fermionic particles) can occupy the same place and quantum state simultaneously

N^0 ν^0



Equilateral Planck geometries create elementary charge topologies

Neutron star types

Neutron stars comprise one of the possible evolutionary end-points for stars,
they are compact stellar objects measuring between 10 and 20 km across
with intense magnetic fields around 10^12 times that of the Earth

Like all forms of Matter, neutron stars are formed from 3 distinct charge flavours of Matter

E
N
S
h
ε
Matter
anti-Matter
positrons
neutrinos
electrons
0
Protons
Neutrons
Negatrons

Neutron stars are neutral charge pulsars

Positive charge pulsars
Neutron Stars
Negative charge pulsars
Strong E-fields
Strong dipolar M-fields
Strong E-fields

Tetryonics 78.06 - Neutron star types

Copyright ABRAHAM [2008] - All rights reserved

Pulsars

A pulsar is a rotating neutron star that emits a beam of electromagnetic radiation.

This radiation can only be observed when the beam of emission is pointing towards the Earth,
much the way a lighthouse can only be seen when the light is pointed in the direction of an observer,
and is responsible for the pulsed appearance of emission.


Number of pulses per Second
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21
generated by rotating Electric field geometries

Pulsars are electrially charged versions of neutron stars that have weak M-fields in comparision to Neutron stars themselves


Number of pulses per Second
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21
generated by rotating Electric field geometries

Pulsars are very dense, and have short, regular rotational periods.
This produces a very precise interval between pulses that range from
milliseconds to several seconds for individual pulsars

E-field waves accelerate charged particles M-fields do no work

Ampere

$$\vec{F} = q\vec{E} + q\vec{v} \times \vec{B}$$

Electric force

Magnetic field

Lorentz



Current models of pulsars illustrating radio emissions being produced by a pulsar's magnetic fields are erroneous and must be corrected

Radio wave astomony detects E-field waves of energy momenta not magnetic waves

Maxwell

Because a magnetic force is always perpendicular to the motion,
the magnetic field can do no work on an isolated charge.

It can only do work indirectly, via the electric field
generated by a changing magnetic field

Faraday

Pulsars

Are compact Matter bodies with strong GEM fields



Like all Stellar bodies their GEM fields
resolve to a point at their core

The gravitational collapse of Matter produces radiative electromagnetic waves

A millisecond pulsar (MSP) is a pulsar with a rotational period in the range of about 1-10 milliseconds.

Millisecond pulsars have been detected in the radio, X-ray, and gamma ray portions of the electromagnetic spectrum.

The origin of millisecond pulsars is still unknown.

The leading theory is that they begin life as longer period pulsars but are spun up or "recycled" through accretion. For this reason, millisecond pulsars are often called recycled pulsars.



This model much better explains extreme millisecond pulsars EM emissions against the current rotating magnetic dipole models where the high angular momentum involved would result in the star tearing itself apart

Number of Pulses per Second

Radio wave astomony detects E-field energy momenta impulses not magnetic waves

Millisecond Pulsars are best explained as the detection of polarised Electric fields originating from a non-charged Neutron star rotating with high angular momentum

Applying Tetryonic geometries to the question of millisecond pulsars reveals that they are the formative form of all Pulsars and that over time they slow down to become the observed longer period pulsars [obeying the conservation of Angular momentum law]

Tetryonics 78.08 - Pulsar rotations

Copyright ABRAHAM [2008] - All rights reserved



X-ray pulsars or accretion-powered pulsars are a class of astronomical objects that are X-ray sources displaying strict periodic variations in X-ray intensity

Like all Stellar bodies their GEM fields resolve to a point at their core

Accretion X-ray Pulsars

An X-ray pulsar consists of a magnetized neutron star in orbit with a normal stellar companion and are a type of binary star system.

Charged Matter topologies from the companion star are attracted onto the surface of the Pulsar

Where it is ionised before the particles are accelerated to extreme velocities by the radiative energies created from the collapse of Matter at the core and emitted as X-rays

The gravitational collapse of Matter produces EM waves

<<<<<< Negative pulsars accelerate electrons - Positive pulsars accelerate positrons >>>>>>

Radio wave astomony detects E field waves not magnetic waves

Tetryonics 78.09 - Accretion X-ray Pulsars

Stellar Novae

Novae are cataclysmic nuclear explosions in a white dwarf star.

*It is caused by the accretion of hydrogen on to the surface of the star,
which ignites and starts a runaway nuclear 'fusion' process*



Novae are cataclysmic stellar phenomena that take place in binary systems
consisting of a compact stellar object and a low-mass star.

*All stellar 'fusion' processes are in fact GEM pinches
that convert standing wave Matter into radiant mass-energy*



the size of a planet
but with a mass of up to
1.4 times that of the Sun

The stars must be close enough for the intense gravitational field of the white dwarf to tear material away from the outer layers of its companion.

photons of energy momenta
form kEM fields that accelerate
ions and electrons



all elemental spectral lines
are the result of accelerating
photo-electrons



Novae break accreted Matter into its constituent Deuterium nuclei
and then irradiate the nuclei to higher energy levels
with radiant EM energies produced by their EMP cores

producing the characteristic
spectral lines of Helium, Carbon, Nitrogen,
Oxygen, Calcium, Iron etc

runaway
Matter-energy conversion
within the supernova

12	*Lyman*
48	*Balmer*
108	*Paschen*
192	*Brackett*
300	*Pfund*
432	*Humphries*
588	*un-named*
768	*ionised leptons*

accelerates ions & photo-electrons
producing spectral line emissions
and creates gamma ray bursts

An enigma that has puzzled experts for over 50 years is the origin of the irregular, inhomogeneous distribution of nova ejecta

The material transferred by the companion star is often of solar composition (i.e., close to 98% hydrogen and helium by mass).

Elements, in the range between carbon (C) and calcium (Ca) on the periodic table, can account for 30% to 50% of the material ejected during a nova explosion.

Supernovae explosions

Supernovae are extremely luminous and cause a burst of radiation that often briefly outshines an entire galaxy,

The GEM pinching [collapse of Matter waveforms]
always results in divergent neutral charge
KEM mass-energies



All Matter particles
are standing wave
mass-energy topologies

The gravitational attraction of Matter
is many orders of magnitude weaker
than that of divergent KEM energies
and ceases upon Matter's collapse into
radiant mass-energy geometries

If the EM pinch at the core of a Star
rapidly increases its efficiency or
loses its ability to confine the
resultant KEM energies the
star will be blasted apart

Black holes, hypothesied in physics
as a solution to the math of Einstein's
General relativity since it was was first
formulated in 1915, do NOT exist

All their physics are provided for
by GEM pinch field mechanics

A star moving in a ElectroMagnetic
vacuum energy environment will be subject
to changes in the energy density of the
surrounding vacuum energies

The energy released as a result of the
collapse of Matter topologies in the
core of a supernova is as efficient as
Matter-antiMatter annihilation

Supernovae are created by the sudden disruption of the counter balanced convergent and radiative
mass-ENERGY-Matter output of GEM pinch singularities at the core of compact stellar objects
which results in the sudden release of massive amounts of divergent mass-energy
all at once from the stellar core blasting away the remaining stellar Matter

Tetryonics 79.02 - Supernovae explosions

Singularities

A gravitational singularity or spacetime singularity is a location where the quantities that are used to measure the gravitational electromagnetic fields become infinite in a way that does not depend on the spatial co-ordinate system

Just as the radiative KEM fields of Matter in motion and charged EM fields gives rise to the modern physics misconceptions of spherical point particles and String theories

Tetryonic theory precludes point particles and black holes through analytic mass-energy geometries & Gaussian Matter topologies that result from equilateral Planck energy momenta interactions

The collapse of 3D Matter releases its standing-wave energies as radiant 2D mass-energies foms the basis for all Stellar energy releases

Current theories based on mathematical modelling of General relativity without accurate quantum mechanical models predicts that at densities greater than those supported by fermion degeneracy, gravity overwhelms all other forces collapsing the 3D material body of a large star to create a singularity and the eventual formation of a black hole.

Equilateral Planck charge geometries are the key to understanding stellar processes



The smallest quanta of 3D Matter is a Tetryon

(any attempt to reduce its 3 spatial dimensions results in its collapse into 2D divergent mass-energy waveforms)

Tracing the GravitoElectroMagnetic fields of Matter back to their origin point can give rise to the misconception of a EM field singularity leading to a black hole

Quasi-stellar objects

As standing-wave Matter is converted to radiant EM masses and pure energy the outputs of GEM pinches can increase dramatically over short periods

Black holes do not exist


Blazar
Relativistic jet
Accretion disk
Quasar
Supermassive black hole
Accretion disk
Relativistic jet

A quasi-stellar radio source ("quasar") is a very energetic and distant active galactic nucleus.

Quasars and Blazars are extremely luminous and were first identified as being high redshift sources of electromagnetic energy, including radio waves and visible light, that were point-like, similar to stars, rather than extended sources similar to galaxies


SDSS J0919+2720
30,000 light-years
7.7kpc
5″6
SDSS J1005+4016
F814W I
F475W B
N
E
50,000 light-years
15.3kpc
8″9
SDSS J0827+5224
50,000 light-years
15.3kpc
5″8



Long hypothesised as having supermassive Blackholes at their cores Tetryonics reveals Matter~Energy GEM pinches to be the source of the observed, distant large-scale stellar dynamics

All Matter (comprised of charged Planck quanta) will accelerate according to their charge distributions as they interact with the divergent energies of EM pinches

The central 'core' point singularity of any GEM pinch is completely invisible and is revealed only by its effects on Matter through its interactive EM fields

mass geometries are energy per c^2

$$E = mc^2$$

mass-energy equivalence

Stellar GEM pinches convert Matter topologies into radiant mass-energy geometries with 100% efficiency

Matter topologies are energy per c^4

Matter-energy equivalence

$$E = \frac{m}{c^2}$$

Active Galaxies



In addition to the E-field acceleration of charged particles GEM pinches can also release energies along their Magnetic axis

An active galactic nucleus (AGN) is a compact region at the centre of a galaxy that has a much higher than normal luminosity over at least some portion, and possibly all, of the electromagnetic spectrum.

The motion of stars about a central point in a galaxy's core is the result of a GEM pinch's radiated interactive forces



GR uses stress tensors to model the gravitational effects of ALL energy in a system in its various forms without distinction or differentiation between mass-energy geometries and Matter topologies

EM PINCHES ARE 100% EFFICIENT CONVERTERS OF MATTER INTO ENERGY

Using Tetryonic geometry the Universe is revealed as being completely dominated by ElectroMagnetic forces, with Gravity aiding at the larger scales to help shape the differing forms of Galaxies that we see

EM PINCHES REDUCE TO SINGULARITIES AT THE FOCUS OF THEIR DIVERGENT FIELDS

Tetryonic geometry reveals divergent interactive EM masses & convegent gravitational Matter all contribute to the nett force of Gravitational fields

The current astrophysical models of active galaxies propose supermassive Blackholes as the only mechanism possible to produce the observed large-scale dynamics



E-fields hold Matter in a disc and M-fields release highly polarised energies

Tetryonics reveals the Galactic EM Pinches are also capable of fitting the observed data and explaining many of the current mysteries surrounding how active galaxies generate their power.

The energies released by the conversion of Matter into energy in GEM pinches is the most energetic process in the Universe



Black holes

[Garbage IN - Garbage OUT]

Computer-based modelling of GR
mathematics without charge geometries
leads to paradoxial & erroneous outcomes

Tetryonics allows for Supermassive Matter to form but does NOT allow for the classically defined Black holes

Matter topology collapse
radiant mass-energies

The centres of Galaxies & Quasars hypothesised as being powered by supermassive blackholes are in fact the foci of ElectroMagnetic pinches

In General relativity, a black hole is a region of space in which the gravitational field is so powerful that nothing, including light, can escape its gravitational pull.

The black hole has a one-way surface, called an event horizon, into which objects can fall, but out of which nothing can come. It is called "black" because it absorbs all the light that hits it, reflecting nothing, just like a perfect blackbody in thermodynamics.

'Standard Model' quantum analysis of black holes shows them to possess a temperature and emit Hawking radiation.

In Standard Model Quantum Mechanics
a problem arises in that Charge and Gravity equations
break down and produce infinities and
other impossible results

Very large non-radiating 'Dark Matter'
would be the closest thing possible to
the currently theorised black-holes.

However the 3D volume of such an object
would be limited to the space taken up by its
constituent Tetryonic charge Matter topologies.
(ie Tetryons face-to face without Space
present between any facsias)

This is similar to the current models of
Neutron Stars , WIMPs and MACHOs



The Universe has
only 3 spatial
dimensions

Dark Matter &
Dark Energy are
EM vector forces

Black holes, Worm holes &
other passable singularities
do NOT exist

The collapse of standing-wave Matter topologies results in the release of divergent radiative mass-energy geometries



Vacuum Field geometry

radiated weak neutral EM energies that permeate all of space

All mass-energy geometries & Matter topologies are created from Planck quanta

Relativistic stress energy tensors model mass & Matter as a density-pressure gradient

Matter standing wave topologies make up a small faction of the energy in the Universe

EM mass-energy geometries radiate, permeating all of Free Space

Newtonian

Gravity fields

Relativistic

EM corrections

Gravitation

Interaction

Quantum field theory states that all fundamental fields, such as the electromagnetic field, must be quantized at each and every point in space.

A field in physics may be envisioned as if space were filled with interconnected vibrating balls and springs, and the strength of the field were like the displacement of a ball from its rest position.

The theory requires 'Vibrations' in, or more accurately changes in the strength of such a field to propagate as per the appropriate wave equation for the particular field in question.

Electric ***Magnetic***

The second quantization of quantum field theory requires that each such ball-springcombination be quantized, that is, that the strength of the field be quantized at each point in space.

Canonically, if the field at each point in space is a simple harmonic oscillator, its quantization places a quantum harmonic oscillator at each point.

Excitations of the field correspond to the elementary particles of particle physics.

Thus, according to the theory, even the vacuum has a vastly complex structure and all calculations of quantum field theory must be made in relation to this model of the vacuum.

Wikipedia

Gravitational Matter is always Attractive

ElectroMagnetic masses are interactive

Matter topologies displace vacuum energies to create gravity

kEM geometries radiate to create vacuum energies of all wavelengths

convergent gravitational mass-Matter topologies

divergent interactive mass-energy geometries

All radiative EM fields weaken as they diverge from their sources to create the vacuum energy aether

Tetryonics 79.07 - Vacuum Field geometry

Copyright ABRAHAM [2008] - All rights reserved

The Big Bang theory

The Big Bang is a considered to be a well-tested scientific theory which is widely accepted within the scientific community because it is the most accurate and comprehensive explanation for the full range of phenomena astronomers observe.





The framework for the Big Bang model relies on Albert Einstein's general relativity and on simplifying assumptions such as homogeneity and isotropy of space.

Primodial Atom

According to the Big Bang theory, the Universe was once in an extremely hot and dense state which expanded rapidly

The Big Crunch

If the mass density of the Universe were greater than the critical density, then the Universe would reach a maximum size and then begin to collapse.

It would become denser and hotter again, ending with a state similar to that in which it started



The equations of classical General relativity indicate a singularity at the origin of cosmic time, and while the Big Bang model is well accepted in modern cosmology, Tetryonics provides a clear causal model for the origin of all mass-energy-Matter and fields of force in our Universe, offering a unified, determinsitic explaination of all its field interactions and ultimate energy fate.

Tetryonics relates Time to changing equilateral QAM [Planck] geometries in a dynamic evolving Universe. Moreover, general relativity must break down before the Universe reaches the Planck temperature while Tetryonics provides a unified explanation for the mechanics of the Universe

Big Bang

Extrapolation of the expansion of the Universe backwards in time using general relativity yields an infinite density and temperature at a finite time in the past, which it is proposed underwent a explosive birth and a period of rapid expansion in order to produce the homognetity currently observed.

Inflation

The Big Chill

The heat death of the universe is a suggested ultimate fate of the universe, in which the universe has diminished to a state of no thermodynamic free energy and therefore can no longer sustain motion or life.

The Big Bang theory is the prevailing cosmological model that attempts to explain the early development of the Universe

Energy death

Tetryonics 79.08 - The Big Bang


Positive discharge point
Negative discharge point
c⁴
Q
M
RE
KE
+
−
the observable Universe
N
E
S
Planck's constant
c²

Positive and negative charges are opposing sides of the same Planck energy quoin

All the mass-ENERGY-Matter & forces of motion in our Universe are the result of charge interaction between a finite number of equilateral Planck quanta

Empty space

that were released at a distant point in space and time to expand and fill a region of empty space in the form of a

Big electrical Discharge

Time is a measure of changing charge arrangements

mass-energy geometries & Matter topologies

the mass-ENERGY-Matter density of our Universe is constant

Fields of Force result from [k]EM field interactions

Upon their release these Planck scale energies created all the mass-energy-Matter and forces of interaction within our Universe as it sought, and continues to seek a state of eternal, dynamic equilibrium



The Dynamic Universe

Like a living breathing Organism, the Universe can now be seen as an eternally dynamic system that is constantly evolving through Matter creation, EM interactions & Matter destruction

Gravitational contraction

Singularities

arise from the vector modelling of convergent EM fields of force without an understanding of the EM energy momenta geometries

The formation of Matter creates regions of attractive low vacuum energy pressure

[Convergent Gravity]

Dark Matter

results from modern modelling of convergent EM interactions without an understanding of the EM energy momenta geometries

All mass-ENERGY -Matter arises from equilateral Planck energy quanta

Flat Euclidean geometries and Platonic topologies create everything

The Cosmos is a dynamic eternally evolving GEM energy environment

Radiant expansion

Inflation

arises from an attempt to explain the observed homogenity of the Universe without an understanding of kEM energy momenta geometries

The collapse of standing-wave Matter releases interactive EM mass-energies

[Divergent EM Radiation]

Dark Energy

results from modern modelling of divergent EM interactions without an understanding of the EM energy momenta geometries

The energetic 'space-time fabric' of our Universe is not curved, it is created from flat Euclidean Planck quanta in a finely tuned state of dynamic equilibrium between gravitational Matter & radiant EM mass-energies

Tetryonics 79.10 - The Dynamic Universe

Copyright ABRAHAM [2008] - All rights reserved



Galactic GEM interactions

GEM field interactions
determine the overall shapes
of Galaxies

All Matter throughout the Universe
is shaped by the volumetric energy gradients
of Gravity and planar interactions of EM fields

DARK MATTER

Convergent energy momenta
EM field interactions

DARK ENERGY

Divergent energy momenta
EM field interactions

Convergent
gravitational Matter

$$\frac{T\pi\rho}{c^4}$$

topologies

Divergent interactive
EM mass-energy

$$\frac{n\pi\rho}{c^4}$$

geometries

Tetryonic GEM fields reveals that Gravitational fields to be
the result of gravitational Matter, interactive E-fields
and perturbative M-fields

*The Tetryonic solution to problematic 'Dark Matter & Energy'
is to differentiate between all Matter & EM mass-energy
geometries within the same spatial co-ordinate system*

Tetryonics 79.11 - Universal GEM interactions

The Dark Forces

Gravitational attraction is the result of the nullspace of Matter.
It is many orders of magnitude weaker than ElectroMagnetic forces
(Gravity does not hold the whole galaxy together)

charged energy geometries

energy momenta quanta

$$n\pi\left[m\Omega v\right]^2$$

mass velocity

$$G_{ab} + \Lambda g_{ab} = \frac{8\pi G}{c^4} T_{\mu\nu}$$

Newtonian Gravity
models the motion resulting
from the attractive force
between Matter

General Relativity
models perturbative force
resulting from the total energy
of any system



charged energy geometries
create Bosons & Photons
and Matter topologies

the radiated [K]EM energies
of Matter diverge to create
Vacuum Energies

Convergent EM field interactions
Divergent EM field interactions

standing wave mass-energies
[Matter topologies]
contain nullspaces
that create Gravity

the K/EM fields of Matter are
convergent and divergent
energy momenta
geometries

All [K]EM radiation has
a CONVERGENT component in its
interactive field that increases
when Matter is in motion

DARK MATTER

or when its standing-wave Matter
topology is destroyed

$$E \xrightarrow[\text{energy momenta}]{\text{convergent}} M$$

All [K]EM radiation has
a DIVERGENT omponent in its
interactive field that increases
when Matter is in motion

DARK ENERGY

or when its standing-wave Matter
topology is destroyed

$$M \xrightarrow[\text{energy momenta}]{\text{divergent}} E$$

$$F = -G\frac{M_1 m_2}{r^2}$$

$$F = k\frac{Q_1 Q_2}{r^2}$$

Gravitational
Matter
is attractive

G

Tetryonics dictates that in order to correct for measured Gravitational accelerations
we must distingush between EM mass and Matter and take into account
all the EM forces as well as that of Gravity produced by Matter

k

ElectroMagnetic
mass-energies
are interactive

Tetryonics 80.01 - The Dark Forces

Vacuum Energies

Vacuum energy is an underlying background energy that exists in space even when it is devoid of Matter (free space) and results from the introduction of the Cosmological constant [Λ] by Albert Einstein as a modification of his original theory of General relativity in order to achieve a static universe.

Dark Matter is a measure of CONVERGENT KEM interactions additional to that of Gravity



Dark Energy is a measure of DIVERGENT KEM interactions opposing that of Gravity



He later abandoned this concept after observations of the Hubble redshift indicated that the universe might not be stationary

Gravitational Matter is always attractive

ElectroMagnetic masses are always interactive

$$G_{ab} + \Lambda g_{ab} = \frac{8\pi G}{c^4} T_{\mu\nu}$$

total system energy

Matter

M

topologies

mass

m

geometries

Unlike Einstein's Special and General theories of Relativity that utilizes a scalar energy density tensor, Tetryonics utilizes analytical geometry & topology to differentiate between EM mass & Matter and model all energy interactions in any spatial region

Gravity results from standing-wave Matter

Gravito-Electro-magnetic interactions

Total energy geometries

quantised energy momenta

$$\mathrm{GEM} = \frac{n\pi[m\Omega v]^2}{c^4}$$

of all EM mass-ENERGY-Matter in the Universe can be defined as

spatial volume of mass-energy-Matter interactions

EM interactions result from superpositioned EM masses

Copyright ABRAHAM [2008] - All rights reserved



$E_\gamma = 2mv^2$

Vacuum Energy Wavelengths

$2hv = E = hf$

Vacuum energies account for all energy in the Universe that is not standing-wave Matter or its associated [K]EM wave

λ/2
V
volts
Longitudinal Waves
f
frequency
Transverse Waves
λ/72
λ/8
λ/98
λ18
λ/32
λ/50
λ/128

Radiated [K]EM energies that permeate the Universe
are comprised of photons of predominately longer wavelengths

These radiated EM waves interact and superposition
over time to create a uniform vacuum energy density field
that is displaced by Matter topologies in turn creating Gravity

Tetryonics 80.03 - Vacuum Energy Wavelengths



Dark Matter is a nett attractive force that results when the ElectroMagnetic interactions of Matter in motion are not included in calculations

In addition to Gravity the [K]EM waves of all Matter in motion possess a convergent component which in turn creates a unidirectional 'force'

The convergent EM force component can be modelled as being the result of an 'invisible' form of Matter or additional gravitational force

DARK MATTER

Convergent EM field vector momenta

All Matter emits divergent EM radiation photons comprised of bidirectional vector momenta

Matter produces Gravity
EM waves are interactive

Dark Matter is matter that neither emits nor scatters light or other electromagnetic radiation, and so cannot be directly detected via optical or radio astronomy.

Gravity is the result of the displacement of vacuum energies by 3D Matter topologies

All [K]EM radiation has a convergent component in its interactive field that increases when Matter is in motion or created in the form of EM standing-wave topologies

DARK MATTER

As Matter is destroyed and energy is released the attractive force of Gravity decreases but the convergent acceleration due to Dark Matter increases

Dark Matter

Dark matter is estimated to constitute 84% of the Matter in the universe and 23% of the total mass-energies



Dark Matter created by KEM field convergence contributes to the total energies of the cyclic Universe



Much of the evidence for dark matter comes from the study of the motions of galaxies

Dark matter plays a central role in the modeling of galactic structure formation and evolution

Dark Matter's existence is inferred from its gravitational effects on visible Matter and the convergent lensing of background radiation

Copyright ABRAHAM [2008] - All rights reserved

Galaxy Rotations

In 1986, Nobel laureate Hannes Alfven
postulated at an electrical model
for the solar system

The rotation curve of a galaxy (also called a velocity curve)
can be represented by a graph that plots the orbital speed (in km/s) of the stars or gas
in the galaxy on the y-axis against the distance from the center of the galaxy on the x-axis

The dynamic modelling
of large scale Matter must take
into account all forces present

Based on Newtonian mechanics and assuming, as was originally thought, that most of the Matter of the galaxy had to be in the galactic bulge near the center, Matter (such as stars and gas) in the disk portion of a spiral should orbit the center of the galaxy similar to the way in which planets in the solar system orbit the sun, i.e. where the average orbital speed of an object any distance away from the majority of the Matter would decrease inversely with the square root of the radius of the orbit

G

**Gravitational
Matter
is attractive**

Newtonian gravity
models convergent
Gravity only



Gravity alone produces
spheres or ellipsoids

Matter is comprised of charged quanta
ALL charged quanta experience
Lorentz forces

EM forces produce
dynamic spiral shapes

$F = q[E+v.B]$

SR

**ElectroMagnetic
mass-Energy
is interactive**

General relativity
models interactive
GEM energies

$$F = -G\frac{M_1}{r^2}$$

The curves of the rotational velocities of stars within Galaxies do not decrease in the expected inverse square root relationship but are "flat", i.e. outside of the central bulge their speed is nearly constant from the centre out ot the edge of the galaxy [identical to the forces produced by homopolar motors]

$$F = k\frac{Q_1}{r^2}$$

*Tetryonics dictates that we must take into account EM forces as well as Gravity
in order to account for any perturbations that convergent Gravitation alone cannot account for*

Observations have shown there is not sufficient visible Matter in the Universe to account for the apparent strength of gravitational forces within and between galaxies leading to the hypothesis that up to 90% of the Matter in the Universe is

Dark Matter

***Gravity alone does not hold the whole galaxy together
It is many orders of magnitude weaker than ElectroMagnetic forces***

To account for the redshift-magnitude relation of type Ia supernovae General relativity requires that much of the energy in the Universe consists of a component with large negative pressure, this negative-gravity has been dubbed

Dark Energy

Gravitational attraction is the nett convergent force resulting from three distinct quantum forces

Dark Energy

Dark energy is a hypothetical form of energy that permeates all of space
and tends to increase the rate of expansion of the universe.

EM mass-energies are conservative

Dark Energy is a nett
repulsive force that results when
Gravitational Matter topologies
are destroyed by stellar GEM
pinch processes

Matter is not conservative

*All [K]EM radiation has
a divergent component in its
interactive field that increases
when Matter is in motion*

DARK ENERGY

*or its standing-wave topology
is destroyed*

*As Matter is destroyed and energy is released
the attractive force of Gravity decreases
and the divergent acceleration
due to Dark Energy
increases*



*Independent from its actual nature, dark energy would need to have a strong negative pressure
(repulsive force or divergent energy opposite that of gravitational attraction)
in order to explain the observed acceleration in the expansion rate of the universe.*

The [K]EM fields of Matter
are comprised of
KEM fields contributes to the total energies
of the cyclic Universe

DARK ENERGY

Divergent EM field interactions

**Dark Energy is the divergent scalar field
created by [K]EM field energies**

2D [K]EM fields
create interactive forces
between Matter

**The cosmological constant is physically
equivalent to vacuum energy**

DARK MATTER

Convergent EM field interactions

*A major outstanding problem is that most quantum field theories
predict a huge energy value for the quantum vacuum,
more than 100 orders of magnitude too large.*

*This would need to be cancelled almost, but not exactly,
by an equally large term of the opposite sign.*

DARK ENERGY

Divergent EM field interactions

In fact a negative pressure does not influence the gravitational interaction between Matter [which remains attractive]
but rather alters the overall evolution of the universe at the cosmological scale, typically resulting in the localised accelerating
expansion of the universe despite the attraction between Matter present throughout the Universe.

Copyright ABRAHAM [2008] - All rights reserved

Energy-momenta geometry

The super-positioned EM fields of free space is comprised of Planck energy momenta

A major outstanding problem is that most quantum field theories predict a huge cosmological constant from the energy of the quantum vacuum, more than 100 orders of magnitude too large.

If the Higgs field does exist, another field with an unknown negative energy is needed to reduce the total energy in the vacuum to a slightly positive value to correspond with the current accelerated rate of expansion

Summing over all possible Energy quanta at all points in space gives a large but NOT infinite quantity of energy-momenta

Due to the equilateral asymmetry of all the energy momenta quanta in charged electromagnetic fields

Dark Energy is Divergent Vacuum Energy momenta in free Space



Convergent Vacuum Energy momenta in free Space is Dark Matter



E Field Coulombic forces

convergent momenta ↓

divergent momenta ↑

Vacuum charge momentum

1	1		1
2	3		0.666667
3	5		0.6
4	7		0.571429
5	9		0.555556
6	11		0.545455
7	13		0.538462
8	15		0.533333
9	17		0.529412
10	19		0.526316
11	21		0.52381
12	23		0.521739
13	25		0.52
14	27		0.518519
15	29		0.517241
16	31		0.516129
17	33		0.515152
18	35		0.514286
19	37		0.513514
20	39		0.512821
21	41		0.512195
22	43		0.511628
23	45		0.511111
24	47		0.510638
25	49		0.510204
26	51		0.509804
27	53		0.509434
28	55		0.509091
29	57		0.508772
30	59		0.508475

The total Vacuum Energy in any spatial region contains fields of Planck energy-momenta seeking an equalised, homgenous state

Divergent energy momenta always dominates over Convergent energy momenta

Tetryonics 80.07 - Vacuum Energy-momenta

Copyright ABRAHAM [2008] - All rights reserved

Charged electrostatic fields

E Field Coulombic forces

convergent momenta

divergent momenta

Charge interaction

DIVERGENT CHARGE FIELDS
are external Energy momenta

momenta

CONVERGENT CHARGE FIELDS
are internal Energy momenta

Energy-momenta forces

Forward velocity

downward Thrust

Momenta acceleration

1	1		1
2	3		0.666667
3	5		0.6
4	7		0.571429
5	9		0.555556
6	11		0.545455
7	13		0.538462
8	15		0.533333
9	17		0.529412
10	19		0.526316
11	21		0.52381
12	23		0.521739
13	25		0.52
14	27		0.518519
15	29		0.517241
16	31		0.516129
17	33		0.515152
18	35		0.514286
19	37		0.513514
20	39		0.512821
21	41		0.512195
22	43		0.511628
23	45		0.511111
24	47		0.510638
25	49		0.510204
26	51		0.509804
27	53		0.509434
28	55		0.509091
29	57		0.508772
30	59		0.508475



Electrostatic fields can provide a source of thrust

The greater the EM charge field strength the greater the divergent force

a source of cost effective space launches

1	0
3	.25
2	.333
1,666	.375
1.5	.4
1.4	.4166
1.333	.4375
1,2857	.4375

7/15

#		Pos	Neg		Charge		Pos %	Neg %		Pos Split	Neg Split		Power		SQRT
1000		1000	999		1		0.50025	0.49975		500500	499500		1000000		1000

Launch Pad

Momentum splits are reversed
for Negative charges

Electric Charge divergence is always superior to Charge convergence

Momentum trends to 50/50 split
(but never reaches it)

Launch Pad

Tetryonics 80.08 - Electro-Gravitic Charge lauches

Copyright ABRAHAM [2008] - All rights reserved

Electrostatic lifters

Electrostatic levitation is the process of using an electric field to levitate a charged object and counteract the effects of gravity

Tetryonic geometries and Coulombic forces offers an alternative means of propulsion for space lauches and frictionless transports



Charged voltage fields contain nett divergent energy momenta [Planck quanta] that can do work over distances

Electrostatic charges are always divergent from their sources



Interactive electromagnetic forces are vastly stronger than convergent gravity

Static electricity is the result of electrostatic charges

Electrostatic charges are comprised of divergent energy momenta

Electrostatic levitation



forces should not be confused with



Magnetic levitation

Copyright ABRAHAM [2008] - All rights reserved

The Light speed barrier

BOSONS/PHOTONS
2D Planar massless particles
[EM mass-Energies]
'slice' throught the
vacuum energy aether

**The 'speed of Light'
is the limiting speed of
transverse EM accelerations
[it is not THE limit]**

TETRYONS/BARYONS
3D Tetrahedral EM Matter
[4nπ EM mass-Energies]
interact at various angles with the
vacuum energy aether

CHARGED
particle or massive body

$$E = Mv^2$$

REST MATTER
remains invariant
(but accelerates)



ENERGY-MOMENTA
of populsion field

KEM FIELD
induces motion
in a charged body

**The Compton frequency of quanta
in any EM field is directly proportional
to the field's velocity of propagation**

$$KE = \frac{1}{2}Mv^2$$

MOTION VECTOR
direction of propulsion
of a charged body

**Tetryonic geometry clearly shows that here is NO limit to the
energy content that can be released into any spatial region,
negating the long held belief of a Light speed barrier**

V

According to special relativity, c is the maximum speed at which all EM mass-Energy and information in the universe can travel. It is predicted by General relativity to be the absolute velocity of all 'massless particles' and associated fields - Including ElectroMagnetic radiation such as Light in a vacuum.

Such particles and waves travel at c regardless of the motion of the source or the inertial frame of reference of the observer. In the theory of relativity, c interrelates space and time, and appears in the famous equation of mass–energy equivalence E = mc2.

C

The speed at which light waves propagate in vacuum
is independent both of the motion of the wave source
and of the inertial frame of reference of the observer

$$E = n\pi\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

The speed of light in vacuum, usually denoted by c,
is a physical constant important in many areas of physics
and is determined by the impedance of the medium

Tetryonics 80.10 - The Light Speed Barrier

Copyright ABRAHAM [2008] - All rights reserved

Inflation

While the detailed particle physics mechanisms responsible for inflation are not known, the basic picture makes a number of predictions that have been confirmed by observation.

Inflation is thus now considered part of the standard hot Big Bang cosmology

$$\underset{\text{momentum}}{\overset{\text{ENERGY}}{n\pi}}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\underset{\text{velocity}}{\overset{\text{quanta}}{v}}\right]^2\right]$$

Tetryonics now provides a detailed physical model of ALL ponderable Matter and its kinetics through the charged geometry of mass-ENERGY-Matter



All mass-energy propagates
at a velocity directly related to
the impedance of the medium



The energy in any spatial region
possesses a related mass-velocity
[linear momentum] component

GIVEN SUFFICIENT ENERGIES ANY REGION OF SPACE-TIME
WILL UNDERGO SUPERLUMINAL EXPANSION [INFLATION]


72 million light years
v²
ρ
p
p
c⁴
with sufficient energy per spatial region
FTL velocities can be easily achieved

UNTIL IT REACHES A CRITICAL ENERGY DENSITY THAT RESULTS IN
THE OBSERVED SPEED OF LIGHT THAT WE NOW MEASURE

The observable Universe
could have originated from a
region of pure energy in it's past.

This point would have contained all
the Energy that ultimately formed all the
mass-Matter of the Universe and Forces
that we now observe and measure
in two 2D planar fields

"And God said,
Let there be light:
and there was light"

The planar EM Energies released
at that point would have resulted
in faster-than-light divergence from
that point as dictated by the
geometric energy-momenta
velocity relationship

$$\frac{\overset{\text{mass}}{n\pi}}{c^2}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\underset{\text{velocity}}{\overset{\text{quanta}}{v^2}}\right]\right]$$

It prescribes a dynamical EM Universe evolving over time
into a state of equilibrium between gravitational mass-Matter topologies
and radiant, interactive mass-energy momenta geometries

$$\frac{\overset{\text{Matter}}{T\pi}}{c^4}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\underset{\text{velocity}}{\overset{\text{quanta}}{v^2}}\right]\right]$$



Superluminal velocities

Any velocity is obtainable by Matter providing
sufficient energy is released in very short durations
to a region of space containing a charged body

$$\Sigma F = \frac{\Delta p}{dt} = m.\frac{dv}{dt}$$

W bosons $[hv]-$ **E** $+[hv]$ W bosons

decelerate accelerate

Every quantum energy level change requires a related change in the number of quanta compared to the previous energy level (ad infinitum)

Note: Inertial considerations still apply
Instanteous release of energy to acheive
superluminal velocities is not advised

REQUIRED VELOCITY

$$\beta = \left[\frac{v}{c}\right]$$

Linear correction factor

The speed of light is a limiting velocity
for accelerations due to transverse wave
electromagnetic energies

Providing the KEM geometry contains enough
energy per c^2 geometry the long held belief of
'the speed of light' being an ultimate speed barrier
is shown to be invalid

KEM fields contain energy-momenta

$$p^2 = KEM = mv^2$$

Any mass-energy field moving
at superluminal velocities is still
subject to Lorentz contractions

Any Matter held within, and moving along
with, a superluminal EM field remains
Lorentz invariant

$$\frac{mv^2}{c^2} = \frac{KEM}{c^2} = \frac{hv^2}{c^2}$$

The mass-energy of Kinetic EM
fields is velocity dependent and
subject to Lorentz corrections

The rest mass of Matter
is Lorentz invariant

ENERGY REQUIRED

$$\beta^2 = \left[\frac{v^2}{c^2}\right]$$

Scalar correction factor

Tetryonics 80.12 - Superluminial velocities

Faster than Light Travel

It has been well established by Tetryonic geometry that the speed of light 'c' is not a insurmountable barrier as long expounded by Relativity theory

The natural speed of Light is easily surpassed given the right technologies (and sources of energy)


Any charged object in an Electric field will undergo acceleration
v
KE
Charged spaceship
(2v²)-1
v²

Velocity changes are additive as per Newtonian mechanics

The energy requirements to accelerate Matter to increasing velocities are exponental and follow equilateral geometries


20c
KE
Charged spaceship
(20c²)-1
20c²
kg

As the Spaceship's Velocity increases the wavelength of Kinetic Energies decreases and the Compton Frequency increases

Warp Speed Scotty

Proposed explanation for GAMMA RAY BURSTS (GRB)

Any massive body using KEM fields as a motive force for faster-than-Light travel would produce an extremely bright release of Gamma rays at their point of acceleration (as only 1/2 of the photonic energy would be used to accelerate the craft in any one direction). additionally anybody noticing the burst of required Energy would not find a 'source' for the Gamma ray burst when they looked as the craft would have accelerated away from that point in free space

Copyright ABRAHAM [2008] - All rights reserved



The finely tuned Universe

ħ
v
n
π
ε0
m
Ω
μ0
hv
v²
p
KE
N
S
hv
v²
c²
p
KE
S
N
hv
v²
c²
Q²
Q
k
Q
E²
M
G
M
M²
divergent forces
convergent forces

Physical Constant geometries

Long considered a source of mystery, equilateral Planck geometry reveals itself as the geometric basis for

all the invisible force constants of Nature

Tetryonics 80.14 - Physical Constant geometries

Conservation symmetry

A conservation law states that some quantity X
(describing any physical system)
remains constant throughout its motion

$$\frac{\Delta x}{dt} = 0$$

Rotation symmetry gives
conservation of angular momentum

conservation of
angular momenta

$$\left[\frac{\Omega}{c^2}\right]$$

QAM / second

conservation of
linear momentum


velocity
Δv
CPT
a
mass
quantised
angular
momentum
square root
linear
momentum
m
Ω
Charge
Energy
hv
v²
Electro
Force
Magnetic
c²

Equilateral geometries provide the foundational symmetry for all the physical conservation laws

Matter topologies are not conservative

Noether's Symmetry

The action of a physical system
is the integral over time
of a Lagrangian function

The invariance of physical systems
with respect to spatial translation
(the laws of physics do not
vary with locations in space)

Amalie Emmy Noether

(23 March 1882 – 14 April 1935)

Time translation symmetry
gives conservation of energy

conservation of
energy

v
ε_0
E
hv
hv
v²

6.629432672 e-34 J

Planck quanta

$$\left[m\Omega v^2\right]$$

mass velocity

7.376238634 e-51 kg

mass-ENERGY quanta

conservation of
mass

Tetryonics 80.15 - Conservation symmetry

Copyright ABRAHAM [2008] - All rights reserved

Virtual Particles

In physics, a virtual particle is a particle that exists for a limited time and space.
The energy and momentum of a virtual particle are uncertain according to the uncertainty principle.
The degree of uncertainty of each is inversely proportional to
time duration (for energy) or to position span (for momentum).

In Tetryonics the Uncertainty principle
has been negated with deterministic, re-normalisable
charged mass-ENERGY geometries & Matter topologies


q
P
+
N
S
$+\frac{1}{2}hf$

Positive Zero Point Field
energy momenta


$-\frac{1}{2}hf$
P
-
S
N
q

Negative Zero Point Field
energy momenta

Longitudinal waves facilitate
action-at-a-distance

Energy propagates at the
speed of light

Convergent Gravitation
is attractive

Divergent Coulomb forces
are interactive

Material Gravitation


Weak Nuclear Force
Force of Gravity
Electric fields
Strong Nuclear force
η
η
renormalisable energy field
renormalisable energy field
$\mathcal{E}^2$
Van der Waals Force
EM induction
μ
μ
Coulomb Force
Casmir Force
Magnetic fields
All Matter interacts through super-positioned EM fields
from which our force constants are derived
c^4

EM Interactions

M

Charged Matter topologies
in vacuum energy fields
create Gravity

Vacuum field Energies

$$\underset{\text{EM mass}}{m^2c^4} = E^2 = \underset{\text{momenta}}{p^2c^2}$$

m

Superpositioned EM fields
create interactive
EM forces

virtual Particles are not a required part of tetryonic theory

Tetryonics 80.16 - Virtual Particles

Copyright ABRAHAM [2008] - All rights reserved


anti-Matter topologies
12
[12-0]
e+
0
[6-6]
ν0
neutral Matter topologies
0
[6-6]
ν0
Matter topologies
e-
12
[0-12]
0
[18-18]
dud
N̄0
18-18
24-12
12
[12-24]
P-
udu
12
[30-42]
0
[18-18]
dud
N0
18-18
18-18
0
[18-18]
N̄0
dud
0
[36-36]
12
[42-30]
N0
dud
18-18
12-24
0
[18-18]
p+
udu
12
[24-12]
[4-0]
[0-4]
E
ε0
h
N
S
ε0
μ0
μ0
E
ε0
h
S
N

A long-standing symmetry question of Physics is "why do we live in a Matter dominated Universe ?"

Matter~antiMatter asymetry

It is the EXTERNALLY expressed fascia topologies of Matter that determines observed charges

Anti-Matter can be viewed as an inverted Matter topology (and vice-versa)

Matter

inverted antiMatter charge topologies

Anti-Matter

inverted Matter charge topologies

equilateral ZPF geometry

Matter & antiMatter are opposing sides of the same Quantum coin

When negative charges are expressed on the external fascai of Matter topologies - the internal geometry of Matter contains a nett positive charge

When nett positive charges are expressed on the external fascia of Matter topologies - the internal geometry of Matter contains a nett negative charge

Tetryonics 80.17 - Charged fascia chirality

Copyright ABRAHAM [2008] - All rights reserved



Types of Matter

In addition to the established Matter-antiMatter forms of mass
there exists a third form of Matter

Anti-Matter

anti-Neutron
positron
anti-Proton

0
[24-24]
48
udu
anti-Hydrogen

dud
0
[42-42]
84
anti-Deuterium

0
[48-48]
96
di-atomic
anti-Hydrogen

Neutral Matter

Neutron
Neutrino
anti-Neutron

0
[24-24]
Neutrogen
48
dud
dud

0
[42-42]
Neutronium
84

0
[48-48]
di-atomic Neutronium
96

Matter

Neutron
electron
Proton

0
[24-24]
48
udu
Hydrogen

dud
0
[42-42]
84
Deuterium

0
[48-48]
96
di-atomic
Hydrogen

The Universe is filled with Matter - Neutronium - antiMatter star Galaxies
and their emitted photons of light are identical

12-0
12-24
18-18
12-0
12-24
12-0
12-24
12-24
12-0
6-6
18-18
6-6
18-18
18-18
6-6
18-18
18-18
6-6
18-18
6-6
18-18
18-18
6-6
0-12
24-12
18-18
0-12
24-12
0-12
24-12
24-12
0-12

Tetryonics 80.18 - Types of Matter



Matter - Antimatter

symmetry

Negative and Positive charges are opposite sides of the same equialteral Planck energy triangle

Symmetry breaking is no longer required to explain the Matter bias of our observable region of the Universe as all Tetryons comprising Matter have opposite charge internal fascia within their Teryonic geometries (Matter has antimatter internals ~ Antimatter has matter internals)

1
[0-1]
ZPF
L
R
1
[1-0]
ZPF
tetryons
4
[0-4]
0
[2-2]
gluons
tetryons
0
[2-2]
gluons
4
[4-0]
leptons
quarks
anti-quarks
anti-leptons
12
[0-12]
e
0
[6-6]
νe
12
[0-12]
μ
0
[6-6]
νμ
12
[0-12]
τ
0
[6-6]
ντ
8
[10-2]
up
4
[4-8]
down
8
[10-2]
charmed
4
[4-8]
strange
8
[10-2]
top
4
[4-8]
bottom
up
8
[2-10]
4
[8-4]
down
charmed
8
[2-10]
4
[8-4]
strange
top
8
[2-10]
4
[8-4]
botom
e+
12
[12-0]
νe
0
[6-6]
μ
12
[12-0]
νμ
0
[6-6]
τ
12
[12-0]
ντ
0
[6-6]
UP SPIN
DOWN SPIN
DOWN SPIN
UP SPIN
DOWN SPIN
UP SPIN
UP SPIN
DOWN SPIN
e-
e+
KE
μB
N
S
L
R
External magnetic dipole
Parallel magnetons
Opposing Nuclei momentum
Same as Nuclei momentum
μN
12
[24-12]
Baryons
0
[18-18]
P+
N⁰
22,500
22,500
0
[18-18]
AntiBaryons
12
[12-24]
N̄⁰
P-
22,500
22,500

Tetryonics 80.19 - Matter - Antimatter symmetry

Anti-Matter

Baryon asymmetry

Matter

The Big Bang should have produced equal amounts of Matter and antiMatter,
as such, there should have been total cancellation of both.



anti-Deuterium

It is not yet understood why the Universe has more matter than antimatter.
It is generally assumed that when the Universe was young and very hot,
it was in equilibrium and contained equal numbers of baryons and antibaryons.

Protons should have cancelled with antiprotons, electrons with antielectrons (positrons),
neutrons with antineutrons, and so on for all elementary particles.
This would have resulted in a sea of photons in the universe with no matter.

However, observations suggest that the Universe, including its most distant parts,
is made almost entirely of normal matter.



Deuterium

anti-Neutron
positron
anti-Proton



Neutron
electron
Proton

antiMatter dominated Galaxy

Neutral Matter

Neutron Neutrino anti-Neutron

Matter dominated Galaxy

nett positive
GEM
interactions

Tetryonics dictates that the Universe is filled with
Matter - Neutronium - Antimatter star Galaxies
and their emitted light photons are identical

Tetryonics also demonstrates that the charge topologies of each Matter type prevalent in the formation of each Galaxy determines the overall resultant EM field geometries that shapes their large-scale evolution

It is hypothesised that the rotation direction of galaxies is also influenced by how each galaxy was formed
in particular the predominance of Matter over antiMatter interactions and
the electrodynamic fields of each Galaxy's GEM pinch core

nett negative
GEM
interactions

Clockwise rotation

Counter-clockwise rotation

Copyright ABRAHAM [2008] - All rights reserved



Opposites attract - Similars repel
even on the galactic-scale

Galactic Matter distributions

Tetryonics dictates that the Universe is filled with 3 forms of
Matter - Neutronium - Antimatter stars and Galaxies
their light is identical and cannot be used to distingush them



false colour image of the universe showing galaxy distributions

Matter

Neutron
Electron
Proton

Neutronium

Neutron
Neutrino
anti-Neutron

Neutronium is found predominantly in Neutron stars and Pulsars
spread throughout Matter and antiMatter galaxies
however it is conceivable that neutral galaxies may exist

Anti-Matter

anti-Neutron
Positron
anti-Proton

Tetryonics 80.21 - Galactic Matter distribution

E

scalar Energy

$\mathrm{kg}\,\frac{\mathrm{m}^2}{\mathrm{s}^2}$

Planck

$$h = m.\Omega$$

quantised angular momentum is equilateral geometry

$$E = hv^2$$

h

Planck's constant

$\mathrm{kg}\,\frac{\mathrm{m}^2}{\mathrm{s}}$

Leibniz-Newton

linear momentum

$$E = mv^2$$

mass-energy momenta relationship

square root equilateral energy is linear momentum


v
p
ODD number
bosons
SQUARED
energies
m
Ω
hv
v²
c
normal distribution of energies
F
c²
seconds

Lorentz-Einstein

scalar energies

$$E = \frac{mv^2}{c^2}$$

mass-energy equivalence

Energy per second is mass

p

linear momentum

$\mathrm{kg}\,\frac{\mathrm{m}}{\mathrm{s}}$

$$F = ma$$

mass is a scalar constant relating Force to acceleration

$$F = m\frac{\Delta v}{\Delta t}$$

m

scalar mass

kg

Tetryonic Theory

The charged geometry of ElectroMagnetic mass-ENERGY
& Matter in motion

Charged geometries

Bosons

$$\frac{\mathrm{ODD}\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

Planck quanta mass velocity

Total Relativistic Energies

ENERGY

$$n\pi\left[\left[m\Omega v^2\right]\right]$$

Planck quanta mass velocity

Quantum Mechanics

Chemistry



Cosmology

ElectroDynamics

Matter

$$\frac{T\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

Planck quanta mass velocity

EM waves

$$\frac{\mathrm{EVEN}\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

Planck quanta mass velocity

mass/Matter topologies

Unifying QM, QED, Chemistry and Cosmology
through charged equilateral Planck mass-energy momenta

Kinetic Energies of motion



Tetryonic Cosmology

The quantum geometry of universal Gravitation

Q
ε
RE
Radiant masses
Standing-wave Matter
G
0
Gravitation
Interaction
μ
γ
M
Vacuum Energies
KE
Abraham

ISBN 978-0-987288-4-8
[Second Edition © 2012]

Tetryonics 80.24 - Quantum Cosmology

Copyright ABRAHAM [2008] - All rights reserved

TETRYONICS

The equilateral geometry underpinning the mathematics of Physics



Foundational physics Mathematics

Abraham

ISBN 978-0-987288-5-5
[Second Edition © 2012]

Copyright ABRAHAM [2008] - All rights reserved

Geometry and the Theory of Everything

Plato

(c.428-348 BC)

DIFFERENT TYPE OF GEOMETRIES



2D PLANE | **3D** SPHERE | **3D** SADDLE

Zero Curvature *Euclidian geometry*

Positive Curvature *Elliptic geometry*

Negative Curvature *Hyperbolic geometry*

(studied by Omar Khayyam, Girolamo Saccheri, Bernhard Riemann, ...)

Euclid

(c.330-275 BC, fl. c.300 BC)

The Socratic tradition was not particularly congenial to mathematics, as may be gathered from Socrates' inability to convince himself that 1 plus 1 equals 2, but it seems that his student Plato gained an appreciation for mathematics after a series of conversations with his friend Archytas in 388 BC.

One of the things that most caught Plato's imagination was the existence and uniqueness of what are now called the five "Platonic solids".

It's uncertain who first described all five of these shapes - it may have been the early Pythagoreans - but some sources (including Euclid) indicate that Theaetetus (another friend of Plato's) wrote the first complete account of the five regular solids.

Presumably this formed the basis of the constructions of the Platonic solids that constitute the concluding Book XIII of Euclid's Elements.

In any case, Plato was mightily impressed by these five definite shapes that constitute the only perfectly symmetrical arrangements of a set of (non-planar) points in space, and late in life he expounded a complete "theory of everything", in the treatise called Timaeus, based explicitly on these five solids.

Interestingly, almost 2000 years later, Johannes Kepler was similarly fascinated by these five shapes, and developed his own cosmology from them





Tetractys

The Tetractys historically symbolized the four elements
[Earth, Air, Fire, and Water]
and the relationship between Humanity
and the cosmos created by GOD

The Greek Tetractys is a
triangular figure consisting of ten points
arranged in four rows:

one, two, three, and four points in each row,
which is the geometrical representation of the
fourth triangular number.

As a mystical symbol, it was very important to
the secret worship of the Pythagoreans.



Sacred numbers

A



The Tetractys can be re-organised to represent the
space-time geometries of
all EM mass-ENERGY-Matter

The tetrad was the name given to
the number four -
in Pythagorean philosophy
there were four seasons
and four elements,
and the number was also associated
with planetary motions and music

As a mystical symbol, it was very important to
the secret worship of the Pythagoreans.



The Cosmos

Ω

The single triangle in the first row represents zero-dimensions (a point)
A vector direction in one-dimension can be represented as a line between any two points
The second row represents a Boson (two-dimensions in a plane defined by a rhombus of three triangles)
The whole figure folded represents three-dimensions (a tetrahedron defined by four apex points)
Photons of ElectroMagnetic mass-Energy quanta are represented by two opposing triangles

The Greek Zodiac






12
Aries
1
20 March – 19 April
Taurus
19 April – 20 May
2
Gemini
20 May – 20 June
3
Cancer
20 June – 22 July
4
Leo
22 July – 22 August
5
Virgo
22 August – 22 September
6
Libra
22 September – 23 October
7
Scorpio
23 October – 21 November
8
Sagittarius
21 November – 21 December
9
Capricorn
21 December – 19 January
10
Aquarius
19 January – 18 February
11
Pisces
18 February – 20 March
Neptune
Mars
Uranus
Mercury
Saturn
Earth
Jupiter
Moon
Pluto
SUN
Venus
Mercury





The Greek Elements

Equilateral Triangles

An equilateral triangle is a triangle in which all three sides are equal



Equilateral triangles are
symmetrical in
many different ways



Any six equilateral triangles
joined can make a hexagon.

It is unique in that it is the only polygon
that can be tiled [or divided] and produce
only identical geometries and squares numbers

The equilateral triangle
is eminently suited for
the construction of fractals


v
ε_0
Square numbered geometries
μ_0
N
S
Equilateral triangles are scalable geometries
ε_0
Fractals
Religious icons
μ_0
hv
v^2

The
tesselation of
odd numbered
equilateral triangles
creates square numbers

That is,

1
1+3 = 4
1+3+5 = 9
1+3+5+7 = 16
1+3+5+7+9 = 25
1+3+5+7+9+11 = 36
1+3+5+7+9+11+13 = 49
1+3+5+7+7+9+11+13+15 = 64
etc

An equilateral triangle is simply a specific case of a regular polygon with 3 sides

The Pythagorean Theorem

Though attributed to Pythagoras, it is not certain that he was the first person to prove it.

The first clear proof came from Euclid, and it is possible the concept was known
1000 years before Pythoragas by the Babylonians

$$a^2 + b^2 = c^2$$

The square of the hypotenuse of a triangle is equal to the sum of the squares of its sides.

*In any right triangle,
the area of the square whose side is the hypotenuse
(the side opposite the right angle) is equal to
the sum of the areas of the squares
whose sides are the two legs
(the two sides that meet at a right angle)*





**In Physics
SQUARED numbers are
EQUILATERAL geometries**

Pythagoras of Samos



about (570 – 495 BC)



Pythagorean Tetractys

Since Greek times
squared numbers
have incorrectly
been identified with
square geometries

Equilateral triangles are also
squared number geometries

The Pythagorean equation is at the core of much of geometry,
its links geometry with algebra,
and is the foundation of trigonometry.

Without it, accurate surveying, mapmaking, and navigation
would be impossible,

but its application to the energy-momenta geometries
of ElectroMagnetic fields and Matter in motion in Physics
is erroneous and must be corrected for science to advance

Copyright ABRAHAM [2008] - All rights reserved

Hexagons

A regular hexagon can be subdivided into six equilateral triangles



Energy geometries

Atomic nuclei geometries



Hexagons can be tiled or tessellated in a regular pattern on a flat two-dimensional plane

Hexagons are the only regular polygon that can be subdivided into another regular polygon



Hexagons are the unique regular polygon such that the distance between the center and each vertex is equal to the length of each side

Six is a highly composite number,
the second-smallest composite number,
and the first perfect number.

That is, 1*2*3=1+2+3=6

An interesting relationship between circular and hexagonal geometry is that hexagonal patterns often appear spontaneously when natural forces are trying to approximate circles



Hexagonal tessellation is topologically identical to the close packing of circles on a plane

Platonic Solids

The Pythagoreans knew that there were only five regular convex solids,
the tetrahedon, cube, octahedron, icosohedron and dodecahedron
and each one could be accurately circumscribed by a sphere.

FIRE

4 triangles meet to form
a Tetrahedron

EARTH

6 squares meet to form
a Cube

AIR



8 triangles meet to form
a Octahedron

tetryons **4**

regular deltahedrons

leptons **12**

$$F - E + V = 2$$

faces edges vertexs

8 ***quarks***

regular deltahedrons

20 ***Baryons***

12 pentagons meet to form
a Dodecahedron

THE HEAVENS

Plato

(c.428-348 BC)

The philosopher Plato concluded that they must be the fundamental building blocks
– the atoms – of nature, and assigned to them what he believed to be
the essential elements of the universe.

20 triangles meet to form
a Icosahedron

WATER

Copyright ABRAHAM [2008] - All rights reserved

Tetryonic Solids

Despite their unique topologies Tetryonic solids are not unlike Platonic solids save that their toplogies are comprised entirely from complex hitherto undescribed **4nπ equilateral Planck mass-energy momenta geometries** that also match the **Euler numbers of Platonic solids**

+ tetryon



4 faces
6 edges
4 vertices

2

- tetryon

up quark



2

8 faces
12 edges
6 vertices

down quark

mass geometries

4π *tetryons* **4π**

regular deltahedrons

12π *leptons* **12π**

Matter topologies



Matter topologies

8π *quarks* **12π**

regular deltahedrons

20π *Baryons* **36π**

mass geometries



neutrino

12 faces
18 edges
8 vertices

2

electron



Their equilateral topologies are best described as regular topologic-deltahedrons:

tetra-delta-hedrals	**tetryons**	4π external charge fascia
octa-delta-hedrals	**quarks**	8π external charge fascia
dodeca-delta-hedrals	**leptons**	12π external charge fascia
icoso-delta-hedrals	**Baryons**	20π external charge fascia

note:
Charged mass-energy fascia geometries and edges become "hidden" upon the meshing of delta-hedra to form Matter topologies



Neutron

2

20 faces
30 edges
12 vertices

Proton



Copyright ABRAHAM [2008] - All rights reserved

Euclidean geometry

Euclid

(c.330-275 BC, fl. c.300 BC)

Arguably the most influential Mathematics book ever written is Euclid's 'The Elements'



In all, it contains 465 theorems and proofs, described in a clear, logical and elegant style, and using only a compass and a straight edge.

The Elements - Book 1 - Definition 20

Of the trilateral figures, an equilateral triangle is that which has its three EQUAL sides



Euclid's Elements - Book 1 - Proposition 1
Method of constructing an Equialteral triangle

Euclid's five general axioms were:

Things which are equal to the same thing are equal to each other.

If equals are added to equals, the wholes (sums) are equal.

If equals are subtracted from equals, the remainders (differences) are equal.

Things that coincide with one another are equal to one another.

The whole is greater than the part

Copyright ABRAHAM [2008] - All rights reserved

Archimedes



c. (287 BC – c. 212 BC)

As its definition relates to the circle,
π is found in many formulae in trigonometry and geometry,
especially those concerning circles, ellipses, or spheres.

It is also found in formulae from other branches of science,
such as cosmology, number theory, statistics, fractals,
thermodynamics, mechanics, and electromagnetism

Incorrect identification of Pi [c/d] as opposed to Pi radians
in Physics has led to the inappropriate association
of spherical particles to the physical sciences
whereas equilateral triangles & tetrahedra
form its true geometry

The number π is a mathematical constant that is
the ratio of a circle's circumference to its diameter.

Pi



π is an irrational number
its decimal representation
never ends and never repeats.

$\pi = c/d$

The ratio C/d is constant,
regardless of the circle's size

3.141592654.......

Proof of the fact that C=2πr and how Archimedes proved it



Draw any circle.

Make a point anywhere on the circumference of the [green] circle.

Use that point as the center of a second [blue] circle with the same radius as the green circle.

The edge of the blue circle should touch the center of the green circle.

Draw the line segment connecting the centers of the two circles.

That forms the radius of both of the circles.

Now draw the line connecting the center of the blue circle to where it crosses the green circle
on both sides, and complete the triangles.

You should have two equilateral triangles whose sides are equal to the radius of the green circle

Now extend all of the radius lines so they become diameter lines,
all the way across the circle, and finish drawing all of the triangles to connect them.

You've got six equilateral triangles now, that make an orange hexagon.

So the perimeter of your hexagon is the same as six times the radius of your circle.

But your circumference is a little bigger than the perimeter of your hexagon,
because the shortest distance between two points is always a straight line.

This shows you that the circumference of the blue circle has to be more than 6r,
so if C=2πr then π (pi) has to be a little bigger than 3, which it is.

The more sides we draw on our polygon, the closer we will get to the real value of pi (3.14159 etc.).
Using a polygon with 96 sides, Archimedes was able to calculate that π was a little bigger than 3.1408

The Golden Ratio

Two quantities are in the golden ratio (φ) if the ratio of the sum of the quantities to the larger quantity is equal to the ratio of the larger quantity to the smaller one.

The figure to the right illustrates the geometric relationship

[1.61803]



Interior line length [LM] of the bisector line is equal to 1/2 the side of the original triangle [BC] [AB] or [CA]

Φ

Golden ratio phi

$$\hbar = \frac{h}{2\pi}$$

Tetryonic geometry reveals the maximum E-field amplitude of the reduced Planck constant to be an example of the Golden ratio in physics

velocity vectors

The height of the triangle [ALM] produced by the bisecting line is 1/2 the height of the height of [ABC]



Kinetic energies

The area of the E-field permittivity diamond [ALDM] produced by the golden ratio bisector is 1/2 the area of the original equilateral Planck energy triangle [ABC]

Planck's constant [h]



$a+b$ is to a as a is to b

An intriguing showing of φ in an equilateral triangle was observed by George Odom, a resident of the Hudson River Psychiatric Center, in the early 1980s



The exterior lines [My] and [Lx] are Phi ratios of the interior line [LM]

Let L and M be the midpoints of the sides AB and AC of an equilateral triangle ABC

By measurement and the Intersecting Chords Theorem

MX·MY = AM·MC.

which is of the form

(a + b)·b = a·a.

Denoting a/b = x, we see that

$1 + x = x^2$,

George Odom



The Golden Rhombus

Applying the golden ratio (φ) to quantum scale
electrodynamic geometry we can quickly determine that
the linear momentum and magnetic moment vectors of photons
& EM waves can also be expressed as a golden ratio

vector velocities
vs
magnetic vector


μ
μ_0
μ_0
ε_0
Φ
ε_0
μ_0
μ_0
>
<
μ
$\frac{c^2}{sec}$

Φ

Golden ratio phi
[1.61803]

magnetic Force
vs
electric Force

photons
of
EM energy



The 3 planes of Cartesian co-ordinates


A
v
Z
mass
Energy
2r
Musical Notes
Planetary Orbits
.5r
r
Matter topologies
Conservation Laws
hv
X
Y
v^2
B
C


inverse space
3D space

An equilateral [square] triangle divided into 12 equal semitones

Pythagoras is credited with the discovery that the intervals between harmonious musical notes always have whole number ratios.

An equilateral [square] triangle
divided into 6 equal semitones
and 6 equal quarter tones

With an Equilateral triangle, draw lines from the center of the circle to each vertex and each midpoint, creating six right triangles, as shown with six different colored triangles.
Each right triangle has a radius of the circle for one leg, and half of a side of the original triangle for another.
Any two right triangles sharing one of the radial lines must therefore be congruent, and that implies that the hypotenuses of the triangles are all equal.
This in turn shows that the six right triangles are all congruent, and so the large triangle they combine to form is equilateral

Copyright ABRAHAM [2008] - All rights reserved

Equilateral Fifths


8
7
6
5
4
3
2
1
Do
Re
Mi
Fa
So
La
Ti
do
B
B flat
C
15:8
9:5
13/1
A
D flat
5:3
12
11
1
16:15
10
2
A flat
8:5
9
CDEFGABC
do re mi fa so la ti do
3
9:8
D
8
4
7
5
6
3:2
6:5
G
E flat
45:32
4:3
5:4
G flat
E
F
1
2
3
4
5
6
7
8
C
B
A
G
F
E
D
C

Musical Notes

Tetryonics 81.14- Equilateral Fifths

2D radiated mass-energies

ODD numbers

SQUARED numbers


1
3
5
7
9
11
13
15
17
19
21
23
25
27
29
31
33
35
37
39
41
43
45
47
hν
1^2
2^2
3^2
4^2
5^2
6^2
7^2
8^2
9^2
10^2
11^2
12^2
13^2
14^2
15^2
16^2
17^2
18^2
19^2
20^2
21^2
22^2
23^2
24^2
v^2
48, 44, 40, 36, 32, 28, 24, 20, 16, 12, 8, 4
1,
4, 8, 12, 16, 20, 24, 28, 32, 36, 40, 44, 48
8
16
24
32
40
48
56
64
72
80
88
96

Equilateral Octaves

Copyright ABRAHAM [2008] - All rights reserved

Ternary Diagrams

Viviani's Theorem implies that lines parallel to the sides of an equilateral triangle provide (homogeneous/barycentric/areal/trilinear) coordinates for ternary diagrams for representing three quantities A,B,C whose sum is a constant (which can be normalized to unity).



Ternary diagrams should NOT be used to model EM field strengths



In a ternary plot, of EM energy the Electric field [E] and the Magnetic dipole [N-S] must renormalise to 1

A ternary diagram is simply a triangular coordinate system in which the 3 edges correspond to the axes.



Trilinear charts are commonly used for finding the result of mixing three components (such as gases, chemical compounds, soil, color, etc.) that add to 100% of a quantity.

Copyright ABRAHAM [2008] - All rights reserved

Whilst the Pythagorean Theorem boasts a slightly greater economy of terms than the Eutrigon Theorem (Wayne Roberts 2003), the latter contains an important area not included in the former:

the area enclosed or swept out by the three points of the triangle in question

$$ab = a^2 + b^2 - c^2$$

the area of any eutrigon is equal to the combined areas of the equilateral triangles on legs 'a' and 'b', minus the area of the equilateral triangle on its hypotenuse 'c'.

The Pythagorean theorem

$$a^2 + b^2 = c^2$$

The square of the hypotenuse of a triangle is equal to the sum of the squares of its sides.



Since Greek times square numbers have been incorrectly identified with square geometries

Equilateral triangles also form square number geometries

Eutrigons

are an important new class of triangle (mathematically defined by Wayne Roberts), as the analogue of the right-triangle in orthogonal (Cartesian) coordinate geometry

Kepler's Second Law of planetary motion



The orbit of every planet is an ellipse with the Sun at one of the two foci.

A line joining a planet and the Sun sweeps out equal areas during equal intervals of time.

The algebraic form of the Eutrigon Theorem, (like the algebraic form of Pythagoras' Theorem), is proven to be special case of the Cosine Rule...

Tetryonic theory reveals the equilateral [square] energy geometry that reveals the 'harmonics at play' in physical laws such as the second law of Kepler, and in many other phenomena in physics, chemistry, cosmology, biochemistry and number theory thus providing the foundation for the mathematics of quantum mechanics

Number theory


Real
Real Algebraic
Rational
Integer
Natural
0
1
2
3
ℕ
−1
−2
−3
ℤ
1/2
−2/3
2.25
ℚ
√2
−√3
(1+√5)/2
𝔸ℝ
π
e
−2π
Transcen-dental
Irrational
ℝ

The Pythagoreans also established the foundations of number theory, with their investigations of triangular, square and also perfect numbers (numbers that are the sum of their divisors).

They discovered several new properties of square numbers, such as that the square of a number n is equal to the sum of the first n odd numbers (e.g. 1 + 3 + 5 + 7 = 16).





It has only been in recent centuries that mathematics has begun to explore the higher order irrational numbers

Tetryonics takes this investigation to new levels with the identification of equilateral geometries as the foundation of transcendental numbers and the physics of fields and particles in motion

What mathematics has failed to appreciate is the significance application of equilateral geometries to the 'square' numbers of physics and science in general

Copyright ABRAHAM [2008] - All rights reserved



TETRYONICS



COUNTING POLYGONS



Copyright ABRAHAM [2008] - All rights reserved

SQUARED energies in quantum mechanics are EQUILATERAL geometries



Square

area = s^2 = [100]

Circles


r= 5.642m
area = pi * r²

= pi *$[5.642]^2$
= 100


10
10
100 m²
5.642
Squared Areas
13.160
15.197

can be created by a number of planar geometries

For a long time it has been assumed by scientists (and mathematicians) that circular [and squared] geometries are the geometric foundation of all physics, leading to a serioulsy flawed model of particles and forces in quantum mechanics

Tetryonic theory now reveals that quantised equilateral angular momenta creates the foundational geometry of all the mass-Energy-Matter & forces of physics


15.197m
s
a = √3/4 * s²

Equilateral

area = $(\frac{1}{2} * b) * h$

Triangles


h = 13.160m
s
15.197m
b

$$\overset{b}{[.5 \times 15.197]} \times \overset{h}{13.160}$$
= 100

0.987654321

SQUARE ROOTS

80/81


1
2
3
4
5
6
7
8
9
•
n
1
3
5
7
9
11
13
15
17
19
1
4
9
16
25
36
49
64
81
100
1/2 1 3/2 2 5/2 3 7/2 4 9/2 5 9/2 4 7/2 3 5/2 2 3/2 1 1/2

ODDS

SQUARES

EVEN DISTRIBUTIONS

Copyright ABRAHAM [2008] - All rights reserved

Integers

The integers (from the Latin integer), literally "untouched", hence "whole"
in Tetryonics it is the basis for the Planck charge quantum

$$2n-1$$

$$\left[[n] + [n-1]\right]$$

Triangular numbered geometries are NOT equialteral geometries

0, 1, 3, 6, 10, 15, 21, 28, 36, 45, 55, ...


1
2 3 4
5 6 7 8 9
10 11 12 13 14 15 16
17 18 19 20 21 22 23 24 25
26 27 28 29 30 31 32 33 34 35 36
37 38 39 40 41 42 43 44 45 46 47 48 49
50 51 52 53 54 55 56 57 58 59 60 61 62 63 64
65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81
1 2 3 4 5 6 7 8 9 8 7 6 5 4 3 2 1



$$\sum_{1}^{n} [2n-1]$$

Equilateral geometries form **SQUARE** number geometries

1, 4, 9, 16, 25, 49, 64, 81, 100, 121, 144, ...

Equilateral energy quanta form a normal longitudinal distribution

Viewed as a subset of the real numbers, they are numbers that can be written without a fractional or decimal component

Copyright ABRAHAM [2008] - All rights reserved

ε_0
π
μ_0
μ_0

Bosons are a transverse measure of scalar energy momenta

ODD numbers

An odd number is an integer which is not a multiple of two.

E
μ_0
n
3
μ_0
E
ε_0
+
ε_0
−
N
μ_0
S
S
μ_0
N


1
1 2 3
1 2 3 4 5
1 2 3 4 5 6 7
1 2 3 4 5 6 7 8 9
1 2 3 4 5 6 7 8 9 10 11
1 2 3 4 5 6 7 8 9 10 11 12 13
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17
1
3
5
7
9
11
13
15
17
hv

Quantum

Bosons have ODD number quanta

Quantum Levels

An odd number, when divided by two, will result in a fraction

Copyright ABRAHAM [2008] - All rights reserved

Tau radians

Around the whole outside of a circle,
there are about 6.283 radians - or, Tau radians

3.141592654



π/2
90
2π/3
120
π/3
60
π/4
45
π/6
30
π, 180
0,2π
2π
D
270
3π/2



1/4
1/3
1/6
1/8
1/12
1/2
0,1
radians
r
2/3
3/4

6.283185307



τ/4
90
τ/3
120
τ/6
60
τ/8
45
τ/12
30
τ/2
180
τ
0
270
3/4τ

τ is a more 'natural' radian system for geometric physics than π
Tau = 2π = 360 degree rotation about a point



π

historically defined as the
ratio of a circle's circumference to its DIAMETER
should be redefined in physics to

τ

the ratio of its circumference to its RADIUS

in doing so many of the π/2 terms common to physics
will re automatically rationalised and will better reflect
the Tetryonic geometry of mass-ENERGY-Matter in motion



Photons are a longitudinal measure of scalar energy momenta

E
ε_0
+
2
N
N
S
S
−
μ_0
E

Photons are EVEN number quantums

EVEN numbers

An integer that is not an odd number is an even number


1
2 3 4
5 6 7 8 9
10 11 12 13 14 15 16
17 18 19 20 21 22 23 24 25
26 27 28 29 30 31 32 33 34 35 36
37 38 39 40 41 42 43 44 45 46 47 48 49
50 51 52 53 54 55 56 57 58 59 60 61 62 63 64
65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81



EM waves are comprised of EVEN numbered quanta

If an even number is divided by two, the result is another whole number

1/2 **1** 3/2 **2** 5/2 **3** 7/2 **4** 9/2 **4** 7/2 **3** 5/2 **2** 3/2 **1** 1/2

If an odd number is divided by two, the result is a fractional number

Copyright ABRAHAM [2008] - All rights reserved

Triangular numbers

Historically, a triangular number counts quanta that can pack together to form an equilateral triangle

1, 3, 6, 10, 15, 21, 28, 36, 45, 55, ...

this form of geometric counting of same charges over-complicated the simpler physical reality


1
3
5
7
9
11
13
15
ν
odd

$$2\nu - 1$$

$$[[\nu] + [\nu - 1]]$$

Equilateral chords or quantum levels are ODD numbers

1, 3, 5, 7, 9, 11, 13, 15, 17, 19, 21,....


1 1 0
2 2 1 3 1
3 4 2 5 3 6 2
4 7 4 8 5 9 6 10 3
5 11 7 12 8 13 9 14 10 15 4
6 16 11 17 12 18 13 19 14 20 15 21 5
7 22 16 23 17 24 18 25 19 26 20 27 21 28 6
8 29 22 30 23 31 24 32 25 33 26 34 27 35 28 36 7
9 37 29 38 30 39 31 40 32 41 33 42 34 43 35 44 36 45 8
1/2 1 3/2 2 5/2 3 7/2 4 9/2 4 7/2 3 5/2 2 3/2 1 1/2

Triangular energy quanta form normal distributions


1
4
9
16
25
36
49
81
n²

$$\sum_{1}^{n} [2n-1]$$

Equilateral geometries form SQUARE numbered geometries

1, 4, 9, 16, 25, 49, 64, 81, 100, 121, 144, ...

Copyright ABRAHAM [2008] - All rights reserved

Squared numbers

A square number, sometimes also called a perfect square,
is the result of an integer multiplied by itself



1
+
3
+
5
+
7
+
9
+
11
+
13
+
15
+
17

Square numbers result from
the summing of consecutive
ODD numbers

ODDS

$2n-1$

$[[n]+[n-1]]$


1
3
2 4
6 8
5 7 9
11 13 15
10 12 14 16
18 20 22 24
17 19 21 23 25
27 29 31 33 35
26 28 30 32 34 36
38 40 42 44 46 48
37 39 41 43 45 47 49
51 53 55 57 59 61 63
50 52 54 56 58 60 62 64
66 68 70 72 74 76 78 80
65 67 69 71 73 75 77 79 81
v²

Quantum Energies

$$\sum_{1}^{n}[2n-1]$$

Energy levels have
SQUARE number
quanta

Compton Frequency

In Tetryonics Square numbers produce equilateral geometries

Copyright ABRAHAM [2008] - All rights reserved

Square roots

A square root of a number is a number that, when it is multiplied by itself (squared) , gives the first number again.



Root of positive one

-*i* and +*i*



Root of negative one

Square roots of negative numbers have a basis in physical reality



They reflect the real non-negative linear momentum of a system

A whole number with a square root that is also a whole number is called a perfect square in Tetryonic theory they are actually equilateral geometries

Copyright ABRAHAM [2008] - All rights reserved

Real Numbers

In mathematics, a real number is a value that represents a quantity along a continuous line. The real numbers include all the rational numbers,


Quantum levels
n
-n
9
8
7
6
5
4
3
2
1
0
1
2
3
4
5
6
7
8
9
+n
Ψ
Wave probabilities

Copyright ABRAHAM [2008] - All rights reserved

ONE to ∞^2

Quantum levels

ODD numbers

[2n-1]

1, 3, 5, 7, 9......


v
1
2
3
4
3
5
9
4
7
16
5
9
25
6
11
36
7
13
49
8
15
64
9
17
81
n
hv
v²
1 2 3 4 5 6 7 8 9 8 7 6 5 4 3 2 1
[n-1]
N
[n-1]

SQUARE numbers

the sum of consecutive ODD numbers

1+3+5+7+9+......

Scalar Energies

Linear energy momentum

NORMAL DISTRIBUTION

Tetryonics 82.13 - One to Infinity squared

Copyright ABRAHAM [2008] - All rights reserved

Basic Properties of nested scribed Equilateral Triangles

Given an equilateral triangle of side s

altitude

$\sqrt{3/2}\,S$

$3S$

perimeter

$\sqrt{3/4}\,S^2$

area



$\sqrt{3/6}\,S$

in-radius

$\sqrt{\pi/12}\,S^2$

in-circle area

circum-radius

$\sqrt{3/3}\,S$

circum-circle area

$\sqrt{\pi/3}\,S^2$

Copyright ABRAHAM [2008] - All rights reserved

Tetryonic [equilateral] geometry



The equilateral triangle exhibits 'square symmetry'
it can always be divided into n^2 [number]
of smaller self-similar parts



All triangles are
flat euclidean
π radian
geometries
[180°]





An equilateral triangle is the most symmetrical triangle,
having 3 lines of reflection and rotational symmetry of order 3 about its center

Copyright ABRAHAM [2008] - All rights reserved

CHARGE

Scribed equilateral geometries

reflect space-time's geometric relationship with charged mass-energy

Energy



Energy per spatial unit

mass


v
Inscribed Triangles
hv
v²
c
c²

The triangle of largest area of all those inscribed in any given circle is equilateral

QAM



QAM per spatial unit

seconds

$$m = \frac{E}{c^2}$$

$$\frac{\Omega}{c^2} = s$$

Copyright ABRAHAM [2008] - All rights reserved

Circumscribed Triangles

reflect Energy's relationship with Time


E
$\mathcal{E}_0$
+
μ_0
μ_0
N
S

Positive Planck Charge

E
$\mathcal{E}_0$
−
μ_0
μ_0
S
N

Negative Planck Charge

v
$\mathcal{E}_0$
Inscribed circles
μ_0
μ_0
hv
v²

The perimiter of an equilateral triangle is

$$p = 3a$$

The radius of the circumscribed circle is

$$R = \frac{\sqrt{3}}{3}a$$

The equilateral triangle has the smallest area of all those circumscribed around a given circle

Copyright ABRAHAM [2008] - All rights reserved

Circumscribed circles

By Euler's inequality, the equilateral triangle has the smallest ratio R/r of the circumradius to the inradius of any triangle: specifically, R/r = 2

The ratio of the area to the square of the perimeter of an equilateral triangle

$$\frac{1}{12\sqrt{3}}$$

The ratio of the area of the incircle to the area of an equilateral triangle

$$\frac{\pi}{3\sqrt{3}}$$


v
ε_0
r
R
Inscribed circle
μ_0
μ_0
hv
v²
circumscribed circle
c²


Bosons
ε_0


Photons
ε_0

Equilateral triangles and Tetrahedrons will scale at exactly the same proportion as Circles and Spheres scribing them

Charged mass-ENERGIES

Charge is the result of quantised angular momenta
[the inscribed circular flux of energy in equilateral geometries]

Time is a measure of changing quantised angular momenta
[the circumscribed spatial co-ordinate of equilateral energy geometries]

inscribed



charge

It is the equilateral geometry of energy not a classical vector rotation that creates QAM



circumscribed



time

Scalar EM mass is a measure of equilateral Planck energy per spatial co-ordinate system

m

Charged mass-energies can be described as
a vector measure of scalar Energy momenta per unit of time
[inscribed circular fluxes of equilateral energy per circumscribed temporal geometry]

E

Copyright ABRAHAM [2008] - All rights reserved

Trigometric functions

$$\sin\theta = \frac{\text{opposite}}{\text{hypotenuse}}$$

$$\cos\theta = \frac{\text{adjacent}}{\text{hypotenuse}}$$

$$\tan\theta = \frac{\text{opposite}}{\text{adjacent}}$$


hypotenuse
opposite
θ
adjacent


45°
sin
tan
cos
45°

The most familiar trigonometric functions are the sine, cosine, and tangent.

In the context of the standard unit circle with radius 1,
where a triangle is formed by a ray originating at the origin and
making some angle with the x-axis,

the SINE of the angle gives the length of the y-component (rise) of the triangle,
the COSINE gives the length of the x-component (run), and
the TANGENT function gives the slope
(y-component divided by the x-component)

Standard trigometric functions must be carefully applied to
measurements of equilateral Planck mass-energy geometries
in scribed circular space-time co-ordinate systems


30°
ε0
2
2
sqr [3] b
r
μ0
μ0
60°
a
b

In most cases it is in fact easier to
ignore the trigonomteric functions and math
and simpy draw their related equilateral geometries


Linear momentum
S
O
H
C
A
H
Magnetic vector
T
O
A
Equialteral edge

The roots of scribed equilateral triangles

Scalar equilateral energies map directly onto circular space-time co-ordinates
through their square root linear momentum

r

The ratio of the
circumscribed circle of
an equilateral triangle
to its inscribed circle
is 2:1

d


60°
cosine
tangent
2
b
sine
a
r
d
sqr [3]
30°
v
b
2
60°
v²

0.866 r

The ratio of the
side of an equilateral triangle
to the radius of
its incribed circle
is sqr [3]/2

a

The ratio of the
side of an equilateral triangle
to the radius of
its circumscribed circle
is sqr [3]

1.732 d


scribed circles
r
radius
2:1
diameter
d
Sqr[3]
linear momentum
equilateral triangle
a
equilateral side
2:1
right angle base
b

Copyright ABRAHAM [2008] - All rights reserved

Equilateral triangles and scribed circles

$$\gamma = \frac{1}{\sqrt{1 - v^2/c^2}} = \frac{1}{\sqrt{1-\beta^2}} = \frac{dt}{d\tau}$$

$$\gamma(\beta) = 1 + \frac{1}{2}\beta^2 + \frac{3}{8}\beta^4 + \frac{5}{16}\beta^6 + \frac{35}{128}\beta^8 + \ldots$$

$$L = L'\sqrt{1 - \frac{v^2}{c^2}}$$


60°
2r
2b
b
magnetic
μ
a
$\sqrt{1-\beta^2}$
r
q
KE
30°
θ
$\beta = \frac{v}{c}$
pc
μ_0
moment
m_0c^2
E (= mc²)
K
φ
$E^2 = p^2c^2 + m_0^2c^4$
E = m₀c² + K

$$E_k = \frac{mc^2}{\sqrt{1-(v/c)^2}} - mc^2$$





$$mc^2\left\{\frac{1}{\sqrt{1-v^2/c^2}} - 1\right\}$$

$$p = \frac{m_0 v}{\sqrt{1 - \frac{v^2}{c^2}}} = \gamma m_0 v$$

$$E = \frac{mc^2}{\sqrt{1 - \frac{v^2}{c^2}}}$$

All the relativistic relationships historically attributed to circularised energies and modelled through the use of the math of right angled triangles are in fact the result of equilateral, scalar geometries

$$\sqrt{1 - \left(\frac{v}{c}\right)^2}$$

Copyright ABRAHAM [2008] - All rights reserved

Finite sequences and series have defined first and last terms,

$$\sum a_n = a_0 + a_1 + a_2$$



$$\sum_{n=1}^{\infty} \frac{1}{n^2} = \lim_{n \to +\infty} \left(\frac{1}{1^2} + \frac{1}{2^2} + \cdots + \frac{1}{n^2} \right).$$

whereas infinite sequences and series continue indefinitely

The Basel problem is a famous problem in mathematical analysis with relevance to number theory, first posed by Pietro Mengoli in 1644 and solved by Leonhard Euler in 1735.

$$\frac{1}{1^2} + \frac{1}{2^2} + \frac{1}{3^2} + \frac{1}{4^2} + \frac{1}{5^2} + \ldots = \frac{\pi^2}{6}$$

Tetryonics now provides a geometric solution to visualising and solving the Basel problem

$$\zeta(2) = 1 + \frac{1}{2^2} + \frac{1}{3^2} + \cdots = \frac{\pi^2}{6} \approx 1.645;$$

Tetryonic Infinite Series

is a infinite sequence of square numbers,
the result of adding all those terms together
[or their geometric inverse]



$$\sum_{n \geq 1} \frac{1}{n^2}$$

The entire sum of the series is equal to
twice the size of the radius of the largest inscribed circle
which is equal to the largest circle circumscribing the triangular series.

Inverting the Circle

Electric
Permittivity

ε_o

Magnetic
Permeability

μ_o



c^2

$\frac{1}{c^2}$

2D spatial
co-ordinates

ElectroMagnetic
fields

Irrational numbers

an irrational number cannot be represented as a simple fraction.
Irrational numbers are those real numbers that cannot be represented as terminating or repeating decimals

sin(x)=-square root of (3)/2

0.866025403.......


2
$\sqrt{3}$
1
30°
2
2
$\sqrt{3/2}$
60°
1
1
linear momentum
vector forces

Pythagφras’ theoreom
and irratiφnal numbers expressed in terms of right-angled triangles in Physics
offer a ‘half truth’ regarding the equilateral geometry of Energy

Leibniz

Leibniz introduced the concept of vis viva (living force) which attempted to quantify life force



Newton

Newton focused his work on linear momentum which he developed into his famous laws of motion

Newton and Leibniz disagreed about what the world is made of and how its physics shaped our scientific concepts of force, energy, and momentum

Tetryonics reveals the physical relationships they both described mathematically as geometric properties of equilateral Planck energy momenta

$$E=mv^2$$

$$p=mv$$

Copyright ABRAHAM [2008] - All rights reserved

Geometric Square Roots

In geometrical terms, the square root function maps the area of a square to its side length.



Square root of 1

"In mathematics, as in any scientific research, we find two tendencies present. On the one hand, the tendency toward abstraction seeks to crystallize the logical relations inherent in the maze of material that is being studied, and to correlate the material in a systematic and orderly manner. On the other hand, the tendency toward intuitive understanding fosters a more immediate grasp of the objects one studies, a live rapport with them, so to speak, which stresses the concrete meaning of their relations"



"As to geometry, in particular, the abstract tendency has here led to the magnificent systematic theories of Algebraic Geometry, of Riemannian Geometry, and of Topology; these theories make extensive use of abstract reasoning and symbolic calculation in the sense of algebra.

Notwithstanding this, it is still as true today as it ever was that intuitive understanding plays a major role in geometry. And such concrete intuition is of great value not only for the research worker, but also for anyone who wishes to study and appreciate the results of research in geometry"

David Hilbert [Geometry and the Imagination]

Copyright ABRAHAM [2008] - All rights reserved

Square Roots in Physics

In mathematics, a square root of a number a is a number [n] such that [n]2 = x,
or, in other words, a number [n] whose square (the result of multiplying the number by itself, or [n × n]) is x.

Modern calculators use the
Square Root Algorithm
to calculate the value

It is an approximate numerical value



Tetryonics uses the
geometric Square Root
to calculate the value

It is an exact geometric value



$$E = mv^2$$

In classical geometry,
the square root function maps the
area of a square to its side length.

$$p = \sqrt{E}$$



Geometry can easily map irrational numbers



$$p^2 = E$$

In physics,
the square root function maps
ENERGY [E] to momentum [mv]

The Square roots of n

Historically, any number raised to the power of 2 has been modeled using a polygon--the square
That's why we call raising a number to the second power "squaring the number."





note: scalar
linear momentum
[mv]

is distinct
from vector
[v]elocity

$\sqrt{1} = 1$
$\sqrt{4} = 2$
$\sqrt{9} = 3$
$\sqrt{16} = 4$
$\sqrt{25} = 5$

$1^2 = 1$
$2^2 = 4$
$3^2 = 9$
$4^2 = 16$
$5^2 = 25$



[In physics square numbers are in fact equilateral geometries]
The perfect squares are squares of whole numbers.
Here are the first eight perfect squares

The Square root of Negative 1



Positive fields are out of phase with Negative fields



Magnetic fields are out of phase with Electric fields

P
COS
SIN
SIN

Euler's Formula

Euler's formula is often considered to be the basis of the complex number system. In deriving this formula, Euler established a relationship between the trigonometric functions, sine and cosine, and e raised to a power

$$e^{ix} = \cos(x) + i\sin(x)$$

a mathematical description of EM-Energy waveforms

Leonhard Euler

(15 April 1707 – 18 September 1783)

$$\sin x = x - \frac{x^3}{3!} + \frac{x^5}{5!} - \dots$$

$$\cos x = 1 - \frac{x^2}{2!} + \frac{x^4}{4!} - \dots$$

$$e^x = 1 + x + \frac{x^2}{2!} + \frac{x^3}{3!} + \frac{x^4}{4!} + \frac{x^5}{5!} + \dots$$

$$\sin x + \cos x = 1 + x - \frac{x^2}{2!} - \frac{x^3}{3!} + \frac{x^4}{4!} + \frac{x^5}{5!} + \dots$$



$$e^{i\pi} = -1$$

$$e^{i\pi} + 1 = 0$$



Copyright ABRAHAM [2008] - All rights reserved

Geometric means

The geometric mean of two numbers, is the square root of their product

geometric square root of positive one





$$F = k\frac{Q_1 Q_2}{r^2}$$

geometric square root of negative one



In physics, the geometric mean of two superpositioned fields produces a vector square root Force

It is generally stated that
the geometric mean applies
only to positive numbers.



$$F = -G\frac{m_1 m_2}{r^2}$$

In Tetryonic geometry
the geometric mean applies
to positive & negative fields.

Superpositioning

When two or more waves traverse the same space,
the net amplitude at each point is the
sum of the amplitudes of the individual waves.



constructive interference

In phase

Additive


1/2
1
3/2
2
5/2
3
7/2
4
7/2
3
5/2
2
3/2
1
1/2


+
1
2
3
4
5
6
7
8
7
6
5
4
3
2
1
10
12
14
16
−


1/2
1
3/2
2
5/2
3
7/2
4
7/2
3
5/2
2
3/2
1
1/2

Subtractive

Out of phase

destructive interference



When two or more waves traverse the same space,
if the summed variation has a smaller amplitude
than the constiuent component variations.

The lines of Force

Copyright ABRAHAM [2008] - All rights reserved

Tetryonic Multiplication table

A multiplication table is a mathematical grid used to define a multiplication operation and its results



Multiplication Table

	1	2	3	4	5	6	7	8	9	10	11	12
1	1	2	3	4	5	6	7	8	9	10	11	12
2	2	4	6	8	10	12	14	16	18	20	22	24
3	3	6	9	12	15	18	21	24	27	30	33	36
4	4	8	12	16	20	24	28	32	36	40	44	48
5	5	10	15	20	25	30	35	40	45	50	55	60
6	6	12	18	24	30	36	42	48	54	60	66	72
7	7	14	21	28	35	42	49	56	63	70	77	84
8	8	16	24	32	40	48	56	64	72	80	88	96
9	9	18	27	36	45	54	63	72	81	90	99	108
10	10	20	30	40	50	60	70	80	90	100	110	120

Historically Multiplication tables
have been based on Square geometries

In Tetryonics multiplication tables can
also be based on EQUILATERAL geometries


1
1
2
2 4 6
3
3 6 9 12 15
4
4 8 12 16 20 24 28
5
5 10 15 20 25 30 35 40 45
6
6 12 18 24 30 36 42 48 54 60 66
7
7 14 21 28 35 42 49 56 63 70 77 84 91
8
8 16 24 32 40 48 56 64 72 80 88 96 104 112 120
9
9 18 27 36 45 54 63 72 81 90 99 108 117 126 135 144 153
10
10 20 30 40 50 60 70 80 90 100 110 120 130 140 150 160 170 180 190
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19

The integer multiplicitors are colour coded

Rhombic Multiplication Tables

1	2	3	4	5	6	7	8	9	10
2	**4**	6	8	10	12	14	16	18	20
3	6	**9**	12	15	18	21	24	27	30
4	8	12	**16**	20	24	28	32	36	40
5	10	15	20	**25**	30	35	40	45	50
6	12	18	24	30	**36**	42	48	54	60
7	14	21	28	35	42	**49**	56	63	70
8	16	24	32	40	48	56	**64**	72	80
9	18	27	36	45	54	63	72	**81**	90
10	20	30	40	50	60	70	80	90	**100**









Tetryonics 85.03 - Rhombic multiplication tables

Copyright ABRAHAM [2008] - All rights reserved

Photonic Root Tables

Tetryonic multiplication table can take a number of geometric forms

Square root median



Table read diagonally



1	2	3	4	5	6	7	8	9	10
2	**4**	6	8	10	12	14	16	18	20
3	6	**9**	12	15	18	21	24	27	30
4	8	12	**16**	20	24	28	32	36	40
5	10	15	20	**25**	30	35	40	45	50
6	12	18	24	30	**36**	42	48	54	60
7	14	21	28	35	42	**49**	56	63	70
8	16	24	32	40	48	56	**64**	72	80
9	18	27	36	45	54	63	72	**81**	90
10	20	30	40	50	60	70	80	90	**100**

Integer median



Table read from centre
to outside edge then down

Copyright ABRAHAM [2008] - All rights reserved


1
1
1
4
2
2
9
3
3
16
4
4
25
5
5

Divide [division] tables

Minus [subtraction] tables



Times [multiplication] tables

Plus [addition] tables


36
6
6
49
7
7
64
8
8
81
9
9
100
10
10



1 1 1	2 1 2	3 1 3	4 1 4	5 1 5	6 1 6	7 1 7	8 1 8	9 1 9	10 1 10
2 2 1	4 2 2	6 2 3	8 2 4	10 2 5	12 2 6	14 2 7	16 2 8	18 2 9	20 2 10
3 3 1	6 3 2	9 3 3	12 3 4	15 3 5	18 3 6	21 3 7	24 3 8	27 3 9	30 3 10
4 4 1	8 4 2	12 4 3	16 4 4	20 4 5	24 4 6	28 4 7	32 4 8	36 4 9	40 4 10
5 5 1	10 5 2	15 5 3	20 5 4	25 5 5	30 5 6	35 5 7	40 5 8	45 5 9	50 5 10
6 6 1	12 6 2	18 6 3	24 6 4	30 6 5	36 6 6	42 6 7	48 6 8	54 6 9	60 6 10
7 7 1	14 7 2	21 7 3	28 7 4	35 7 5	42 7 6	49 7 7	56 7 8	63 7 9	70 7 10
8 8 1	16 8 2	24 8 3	32 8 4	40 8 5	48 8 6	56 8 7	64 8 8	72 8 9	80 8 10
9 9 1	18 9 2	27 9 3	36 9 4	45 9 5	54 9 6	63 9 7	72 9 8	81 9 9	90 9 10
10 10 1	20 10 2	30 10 3	40 10 4	50 10 5	60 10 6	70 10 7	80 10 8	90 10 9	100 10 10


tetryons
quarks
leptons
Matter
Neutronium
anti-Matter
1
2 3 4
5 6 7 8 9
2
4 6 8
10 12 14 16 18
3
6 9 12
15 18 21 24 27
4
8 12 16
20 24 28 32 36
5
10 15 20
25 30 35 40 45
6
12 18 24
30 36 42 48 54
7
14 21 28
35 42 49 56 63
8
16 24 32
40 48 56 64 72
9
18 27 36
45 54 63 72 81
10
20 30 40
50 60 70 80 90

Irrational Numbers

An irrational number is defined to be any number that is the part of the real number system that cannot be written as a complete ratio of two integers


Sin π/3
60
v
hv
60
60
v²
Sin 60
.866025403
√3/2
c²

One well known irrational number is π

Irrational numbers can be easily represented geometrically

Copyright ABRAHAM [2008] - All rights reserved

Exponentials & Logarithms

e and the Natural Log are inverse functions of each other:

e ^{x} is the amount of continuous GROWTH after a certain amount of time.
Natural Log (ln) is the amount of TIME of continuous growth to reach a certain level

1	0
10	1
100	2
1,000	3

$10{,}000 = 10^4$

$\log(10{,}000) = 4$



e

How much growth after x units of time
(and 100% continuous growth)

$$e^x = \lim_{n\to\infty} (1 + x/n)^n,$$

GROWTH

ln

ln(x) lets us plug in continuous growth
and get the time it would take.

$$\ln(x) = \lim_{n\to\infty} n(x^{1/n} - 1).$$

PERIOD

Exponential growth

$$\text{growth} = e = \lim_{n \to \infty}\left(1 + \frac{r}{n}\right)^{t}$$

e represents the idea that all continually growing systems
are scaled versions of a common rate

GEOMETRIC

3.141592654

π

Pi is the ratio between
circumference and diameter
shared by all circles.

It is a fundamental ratio inherent in all circles
and therefore impacts any calculation of
circumference, area, volume, and surface areas

Pi radians are equally important and show
all quantised equilateral energy geometries
are related to their scribed circles



GROWTH

2.718281828

e

e is the base rate of growth
shared by all continually growing processes.

e lets you take a simple growth rate
(where all the change happens all at once
at the end of a period of time - ie quantised growth)

e shows up whenever systems grow
exponentially and continuously.....
radioactive decay, interest calculations
and populations

tetryons

EM fields

quarks

**e can be applied to the equilateral energy geometries of physical systems
only where the rate of increase is a integer factor of a squared number**

leptons

Baryons

Copyright ABRAHAM [2008] - All rights reserved

Nuclear Energy levels


400000
350000
300000
250000
200000
150000
100000
50000
0
Energy
Baryons
Leptons
Particle families
Quantum Levels
12000
10000
8000
6000
4000
2000
0
Energy
n
Quantum Levels
Baryons
400000
350000
300000
250000
200000
150000
100000
50000
0
Baryonic Energy
36v²
Quantum Levels
12
[24-12]
0
[18-18]
12
[12-24]
12
[12-0]
Quarks and Leptons
140000
120000
100000
80000
60000
40000
20000
0
Leptonic Energy
12v²
Quantum Levels
12
[0-12]
0
[6-6]
8
[10-2]
4
[4-8]
Tetryons
45000
40000
35000
30000
25000
20000
15000
10000
5000
0
Tetryonic Energy
4v²
Quantum Levels
4
[4-0]
0
[2-2]
4
[0-4]

The emission and absorption of bosons and Photons within sub-atomic nuclei

Increase and decrease in integer amounts according to the charged Tetryonic topologies of the particles involved

Exponential energy levels

Radioactive decays follow exponential curves determined by the Tetryonic topology of the sub-atomic particle families

Proton
Neutron

antiNeutron
antiProton

EM Field · Planck · quanta

$$36\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Baryons · ElectroMagnetic · mass · velocity

Electron
Positron

Neutrino

Up
Down
Strange
Charmed
Top
Bottom

EM Field · Planck · quanta

$$12\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

quarks · leptons · ElectroMagnetic · mass · velocity

Positive
Negative
Neutral

EM Field · Planck · quanta

$$4\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

tetryons · ElectroMagnetic · mass · velocity

Series addition & the Riemann Zeta Function

The second series addition of the Reimann Zeta function is where x=2: (pi^2)/6=1+1/2^2+1/3^2+1/4^2+...
(the sum of the reciprocals of the squares)

$$\zeta(s) = \sum_{n} \frac{1}{n^s}$$

$$\zeta(2) = \frac{1}{1^2} + \frac{1}{2^2} + \frac{1}{3^2} + \frac{1}{4^2} + \cdots = \frac{\pi^2}{6}$$

$$f(n) = 1/n^2$$

$$\sum_{n=1}^{\infty} \frac{1}{n^x}$$



In mathematics, the Riemann zeta function, is a prominent function of great significance in number theory. It is a named after German mathematician Bernhard Riemann. It is so important because of its relation to the distribution of prime numbers. It also has applications in other areas such as physics, probability theory, and applied statistics



The mystery of prime numbers

Question: which natural numbers are prime? how are they distributed among natural numbers?

Primes are basic building blocks for natural numbers:

- any natural number is a product of prime numbers
- a prime number is only divisible by itself and by 1:
  (it cannot be further simplified)

We don't know how to predict where the prime numbers are:

"Prime numbers grow like weeds among the natural numbers, seeming to obey no other law than that of chance but also exhibit stunning regularity" (Don Zagier, number theorist)

Copyright ABRAHAM [2008] - All rights reserved

Adding the odd numbers in order produces the square numbers

Apart from 2, all primes are odd numbers;
the difference between two consecutive squares being odd,
every prime can be expressed as the difference between two squares

SPECTRAL LINES

Primes can be modelled as Bosons
[ODD number energy momenta geometries]

[2n-1]

KEM ENERGIES

Primes can be expressed as Bosons
[the difference of two squared energies]

$n^2 - [n-1]^2$


0
[1+0] 1 1 1 $[1^2-0^2]$
[2+1] 3 2 4 $[2^2-1^2]$
[3+2] 5 3 9 $[3^2-2^2]$
[3+4] 7 4 16 $[4^2-3^2]$
9 5 25
[6+5] 11 6 36 $[6^2-5^2]$
[7+6] 13 7 49 $[7^2-6^2]$
15 8 64
[9+8] 17 9 81 $[9^2-8^2]$
[10+9] 19 10 100 $[10^2-9^2]$
21 11 121
[12+11] 23 12 144 $[12^2-11^2]$
25 13 169
27 14 196
[15+14] 29 15 225 $[15^2-14^2]$
[16+15] 31 16 256 $[16^2-15^2]$
33 17 289
35 18 324
[18+19] 37 19 361 $[18^2-19^2]$
39 20 400
[21+20] 41 21 441 $[21^2-20^2]$
[22+21] 43 22 484 $[22^2-21^2]$
45 23 529
[24+23] 47 24 576 $[24^2-23^2]$
49 25 625
51 26 676
[27+26] 53 27 729 $[27^2-27^2]$
55 28 784
57 29 841
[30+29] 59 30 900 $[30^2-29^2]$
[31+30] 61 31 961 $[31^2-30^2]$
63 32 1024
65 33 1089
[34+33] 67 34 1156 $[34^2-33^2]$
69 35 1225
[36+35] 71 36 1296 $[36^2-35^2]$
[37+36] 73 37 1369 $[37^2-36^2]$
75 38 1444
77 39 1521
[40+39] 79 40 1600 $[40^2-39^2]$
81 41 1681
[42+41] 83 42 1764 $[42^2-41^2]$
85 43 1849
87 44 1936
[45+44] 89 45 2025 $[45^2-44^2]$
91 46 2116
93 2209
95 48 2304
[49+48] 97 49 2401 $[49^2-48^2]$
99 50 2500

The difference of two squares is $(n+1)^2 - n^2 = (n^2 + 2n + 1) - n^2 = 2n + 1$

[n-1] **all energy quanta create normal distributions** **[n-1]**

Copyright ABRAHAM [2008] - All rights reserved

Prime number Distributions

A twin prime is a prime number that differs from another prime number by two, for example the twin prime pair (41, 43). Sometimes the term twin prime is used for a pair of twin primes; an alternative name for this is prime twin or prime pair.

Twin primes appear despite the general tendency of gaps between adjacent primes to become larger as the numbers themselves get larger due to the prime number theorem (the "average gap" between primes less than n is log(n)).

$$p_2 - p_1 = 2$$

Every twin prime pair except (3, 5) is of the form (6n – 1, 6n + 1) for some natural number n, and with the exception of n = 1, n must end in 0, 2, 3, 5, 7, or 8

What Yitang Zhang just proved is that there are infinitely many pairs of primes that differ by at most 70,000,000. In other words, that the gap between one prime and the next is bounded by 70,000,000 infinitely often—thus, the "bounded gaps" conjecture.

On first glance, this might seem a miraculous phenomenon. If the primes are tending to be farther and farther apart, what's causing there to be so many pairs that are close together?

It is the geometry of Numbers themselves that causes a natural geometric convergence



An isolated prime is a prime number p such that neither p – 2 nor p + 2 is prime
2, 23, 37, 47, 53, 67, 79, 83, 89, 97

Copyright ABRAHAM [2008] - All rights reserved

The Digital roots of Prime numbers

The digital root (also repeated digital sum) of a number is the (single digit) value obtained by an iterative process of summing digits, on each iteration using the result from the previous iteration to compute a digit sum.

The process continues until a single-digit number is reached.



1	2	3	4	5	6	7	8	9	10
11	12	13	14	15	16	17	18	19	20
21	22	23	24	25	26	27	28	29	30
31	32	33	34	35	36	37	38	39	40
41	42	43	44	45	46	47	48	49	50
51	52	53	54	55	56	57	58	59	60
61	62	63	64	65	66	67	68	69	70
71	72	73	74	75	76	77	78	79	80
81	82	83	84	85	86	87	88	89	90
91	92	93	94	95	96	97	98	99	100

Archimedes is given credit for the first calculus.

Archimedes infinite series

Today's calculus was published by Newton.

1 + 3/4 + 3/16 + 3/64 + 3/256 + 3/1024 + ...

1 + .75 + .1875 + .046875 + .01171875 + ...

$$3\left(\frac{1}{4}+\frac{1}{4^2}+\frac{1}{4^3}+\frac{1}{4^4}+\cdots\right)=1.$$

$$\frac{3}{4}+\frac{3}{4^2}+\frac{3}{4^3}+\frac{3}{4^4}+\cdots=1.$$


1/4
1/16
1/64
1/16
1/256
1/256
1/64
1/256
1/64
1/4
1/16
1/4

Nested convergent infinite series

Summing a convergent infinite series


0
1/256
1/64
1/16
1/4
hv
n²
1/4⁵
1/1024
1/1024
1/4⁴
1/256
1/256
1/4³
1/64
1/64
1/4²
1/16
1/16
1/4
1/4
1/4
0
1
hv
n²

$1/4 + 1/4^2 + 1/4^3 + 1/4^4 + 1/4^5 + \ldots\ldots\ldots\ldots$

$$\sum_{n=0}^{\infty} a_n = a_0 + a_1 + a_2 + \cdots$$

$1/2 + 1/2^2 + 1/2^3 + 1/2^4 + 1/2^5 + \ldots\ldots\ldots\ldots$

$$\sum_{n=1}^{\infty} \frac{1}{2^n} = \frac{1}{2} + \frac{1}{4} + \frac{1}{8} + \cdots.$$

ODDS = 2n-1

$$\sum_{1}^{n} 2n-1 = n^2$$

Summing the dissimilar coloured equilateral triangles gives unity

1/3 1/3 1/3

1/3 1/3 1/3

Summing the dissimilar coloured equilateral triangles gives unity


4096
4096
4^6
1024
1024
4^5
256
256
4^4
64
64
4^3
4^2
0
256
64
16
0
1
0

$1/4 + 1/4^2 + 1/4^3 + 1/4^4 + 1/4^5 + \dots\dots\dots$

$$\sum_{n=0}^{\infty} a_n = a_0 + a_1 + a_2 + \cdots$$

$1/2 + 1/2^2 + 1/2^3 + 1/2^4 + 1/2^5 + \dots\dots\dots$

$$\sum_{n=1}^{\infty} \frac{1}{2^n} = \frac{1}{2} + \frac{1}{4} + \frac{1}{8} + \cdots.$$

Summing a divergent infinite series

Copyright ABRAHAM [2008] - All rights reserved

Pietro Mengoli

(1626 – June 7, 1686)

The Basel Problem

The Basel problem is a famous problem in mathematical analysis with relevance to number theory, first posed by Pietro Mengoli in 1644 and solved by Leonhard Euler in 1735.

Leonhard Euler

(15 April 1707 – 18 Sept 1783)

$$\zeta(2) = \frac{1}{1^2} + \frac{1}{2^2} + \frac{1}{3^2} + \frac{1}{4^2} + \cdots = \frac{\pi^2}{6} \approx 1.644934$$



The Basel problem asks for the precise summation of the reciprocals of the squares of the natural numbers, i.e. the precise sum of the infinite series

$$f(n) = 1/n^2$$



Integrals of mass-energy

is a means of finding scalar areas using summation and limits.

Integration is a micro adding of ***CONTINUOUS*** quantities.

$$\int_{n}^{\infty} f(x)$$

Integration is a special case of summation.

Integration is defined as the limit of a summation as the number of elements approches infinity while a part of their respective value approaches zero.

Summation is the finite sum of multiple, fixed values.

$$\sum_{n}^{\infty} x$$

Summation is a macro adding of ***DISCRETE*** quantities.

The summation of equilateral energy momenta quanta with respect to their linear vector components



Integrating the energy quanta contained within equilateral charge geometry gives the variable Force required to acheive changes in motion [Energy, work, acceleration]



The Integral of the continuous area under the curve is the summation of an infinte number of disctrete rectangular measurements made to a specified limit

An integration isn't a simple summation, but the limit of a sequence of summations

All Planck energies are discrete equilateral geometries



mass is the surface integral of EM energy geometries per unit of time

Copyright ABRAHAM [2008] - All rights reserved

"The calculus of infinitesimals"

The fundamental theorem of calculus
simply states that the sum of infinitesimal changes in a quantity over time
adds up to the net change in the quantity.

Scalar Energy



$E = mv^2$

Leibniz's vis viva
(Latin for living force)
is mv2,

[2 x kinetic energy]

Gottfried Wilhelm von Leibniz

(July 1, 1646 – November 14, 1716)

vector Force



Much of Newton's work
centred around momentum
and changes to it

[mass.velocity]

$F = m[dv/dt]$

Sir Isaac Newton

(1643-1727)





integral calculus

The founders of calculus thought
of the integral as an infinite sum of
rectangles of infinitesimal width

differential calculus



In calculus, a branch of mathematics,
the derivative is a measure of how
a function changes as its input changes

The fundamental theorem of calculus is a theorem that links
the concept of the integral with the derivative of a function.

Copyright ABRAHAM [2008] - All rights reserved

Energy momentum geometries

Leibniz

scalar energies

linear momentum is the square root vector force
of the scalar energy required to do a set amount of work



$$E = p^2$$

Energy momentum

$$kg\left[\frac{m}{s}\right]^2$$

print out this page

then cut out the 10
Planck energy momenta triangles
shown

Newton

linear momentum

$$d[mv]/dt = dp/dt = ma$$



slice fine lines along the pink linear momentum arrows
with a razor blade or similar as highlighted
under the Newtonian acceleration curve


5.9
E
35
4.6
E
21
3.1
E
10
7.2
E
52
6.7
E
45
v
1
2
3
4
5
7
9
16
25
36
49
11
13
7
m
hv
v²
c²
seconds
3.1
E
10
4.6
E
21
5.9
E
35
6.7
E
45
7.2
E
52

mass is energy per second

slide the cut-out triangles
into the slots created

rotate the assembled model
to show the real force momenta
geometry at work

Tetryonics 87.07 - Physically modeling the geometric forces of acceleration in calculus

Copyright ABRAHAM [2008] - All rights reserved

linear momentum is the square root vector force
of the scalar energy required to do a set amount of work



p

linear momentum

$\mathrm{kg}\,\frac{\mathrm{m}}{\mathrm{s}}$

print out this page

$d[mv]/dt = dp/dt = ma$



Leibniz

scalar energies

$$E = mv^2$$

mass-energy momenta relationship

square root equilateral energy
is linear momentum


v
p
ODD number
bosons
SQUARED
energies
m
Ω
hv
v²
c
normal distribution of energies
F
c²
seconds

Planck quanta and their vector linear momentum
lie at 90 degrees to the angle use in the graphs of motion in calculus

Newton

linear momentum

$$F = ma$$

mass is a scalar constant relating Force to acceleration

$$F = m\frac{\Delta v}{\Delta t}$$

Differentiation

Differentiation is concerned with things like speeds and accelerations, slopes and curves etc.
These are Rates of Change, they are things that are defined locally.


d.v
1
a
2
3
4
5
6
1
3
5
7
9
1²
2²
3²
4²
5²
hv
v²
F

An increase in a force
opposing an object's
vector velocity results in
DECCELERATION


d.v
a
ε_0
E
m
ONCE ENERGY IS ADDED TO AN INDUCTIVE LOOP
THE LOOP RESISTS ANY CHANGES
μ_0
v^2
time

A body in uniform motion remains in motion
unless acted upon by **F** an outside Force


d.v
1
a
2
3
4
5
6
7
8
1
3
5
7
9
11
13
1²
2²
3²
4²
5²
6²
7²
hv
v²
F

An increase in a force
in line with an object's
vector velocity results in
ACCELERATION

A linear measure of Forces acting on physical systems resulting in changes to distance covered per unit of time

A scalar measure of Forces acting on physical systems resulting in changes to their rate of motion

$$v = \frac{\Delta d}{\Delta t}$$

$$= m/s$$

$$F = ma$$

In physics, the derivative of the displacement of a moving body with respect to time is the velocity of the body, and the derivative of velocity with respect to time is acceleration.

$$\sum \mathbf{F} = \frac{d\mathbf{p}}{dt} = m\frac{d\mathbf{v}}{dt} + \mathbf{v}\frac{dm}{dt}$$

Newton's second law of motion states that the derivative of the momentum of a body equals the force applied to the body.

$$a = \frac{\Delta v}{\Delta t}$$

$$= m/s^2$$

Visualising the geometric half-truths of relativistic physics

The source of all the physical relationships of mass-energy momenta and the constants in Physics is the Equilateral Triangle (and all texts must be corrected)



Energy geometries within Physics including Special Relativity with its Lorentz corrections have historically been incorrectly illustrated through the geometry of right angled triangles



F

$$\sum \mathbf{F} = \frac{d\mathbf{P}}{dt} = m\frac{d\mathbf{v}}{dt} = m\mathbf{a}$$

$$\mathbf{F} = m\mathbf{a}\,.$$

Physics is geometry,
one cannot be separated from the other

Equilateral geomtries lead to a intuitive understandings of Physics, Chemistry, Electrodynamics and Gravitation along with all the other apsects of Nature.

$$mv^2 = E = hv^2$$

ENERGY

6.629432673 e-34 J

Planck
quanta
mΩv²
mass
velocity

7.376238634 e-51 kg

momentum

$$p^2 = mv^2$$



$$E^2 = p^2c^2 + m_0^2c^4$$

Generalizing, we see that the square of the total energy, mass, or distance in spacetime is the sum of the components squared.

We can see an origin of distance in spacetime relating to velocity in pc in which Energy is subject to Lorentz corrections [v/c]

$$E = pc.$$

Additionally, EM mass can be directly related tot the Energy content of a body by the velocity of Energy

$$E = mc^2$$

Copyright ABRAHAM [2008] - All rights reserved

Velocity

In physics, velocity is the measurement of the rate and direction of change in the position of an object.

It is a vector physical quantity; both magnitude and direction are required to define it.

The scalar absolute value (magnitude) of velocity is speed, a quantity that is measured in metres per second (m/s or ms–1) when using the SI (metric) system.

$$\frac{m}{s}$$

Speed is the scalar value of the
Distance traveled per unit of TIme

$$\bar{\mathbf{v}} = \frac{\Delta \mathbf{x}}{\Delta t}.$$

Velocity is the vector value of the
Distance traveled per unit of Time

$$\frac{\vec{m}}{s}$$

Velocity squared is the scalar value of the
Distance traveled per unit of Time squared
(Energy of a given spatial volume)

$$\frac{m^2}{s^2}$$

v Velocity $\frac{m}{s}$

sec

is a 2D
radial Space-time
MEASUREMENT



*All divergent Energy possesses a vector direction
and an associated scalar area
whose energy content is quantised*

Velocity squared

$$\frac{m^2}{s^2}$$

Copyright ABRAHAM [2008] - All rights reserved


sec²
is a 3D
Spherical Space-time
MEASUREMENT
a
Acceleration
m/s²
m
+a
m/s²
Deceleration
[2n]-1
[2n]+1
Acceleration
-a
hv
v²
Force
acceleration is a measure of
a vector Force acting along a line
in a spatial volume
c⁴
seconds²

Acceleration

In physics, acceleration is the rate of change of velocity over time [dt]

In one dimension, acceleration is the rate at which something speeds up or slows down.

However, since velocity is a vector, acceleration describes the rate of change of both the magnitude and the direction of velocity.

Acceleration has the dimensions [Length]/[Time Squared]
In SI units, acceleration is measured in meters per second squared (m/s^2).

$$a = \frac{\Delta y}{\Delta x} = \frac{\Delta v}{\Delta t}.$$

In classical mechanics, for a body with constant mass,
the acceleration of the body is proportional to the net force acting on it
(Newton's second law)

$$F=ma \longrightarrow a=F/m$$

Force

$$kg\,\frac{m}{s^2}$$

Additionally, for a mass with constant velocity,
(ie in an inertial frame)
the energy of motion is expressed as its momentum
(acceleration causes changes in Energy-momentum)

$$p = kg\,\frac{m}{s}$$

$kg\frac{m}{s}$

linear
momentum

p



Linear momentum is the vector square root
of the mass-energy in any [K]EM field geometry
and produces a vector velocity

Momentum

In classical mechanics, momentum (pl. momenta; SI unit kg·m/s, or, equivalently, N·s) is the product of the mass and velocity of an object (p).

Like velocity, momentum is a vector quantity, possessing a direction as well as a magnitude.

Momentum is a conserved quantity (law of conservation of linear momentum), meaning that if a closed system is not affected by external forces, its total momentum cannot change.

Momentum should be referred to in its specific forms to distinguish it in its various forms [Quantised Angular, Linear, Rotational and quantum/nuclear momentum]

$$\boxed{p = \frac{hv^2}{v} = mv}$$

Although originally expressed in Newton's Second Law, the conservation of momentum also holds in special relativity and, with appropriate definitions, a (generalized) momentum conservation law holds in electrodynamics, quantum mechanics, quantum field theory, and general relativity.

In relativistic mechanics, non-relativistic momentum is further multiplied by the Lorentz factor.

$$p^2 = E = mv^2$$

Energy can be expressed as
the square of linear momentum

$$kg\frac{m^2}{s^2}$$

equilateral Planck energy momenta

$$m\Omega v^2$$

Energy-momentum relationship

The total number of equilateral Planck quanta [quantised mass-energy momenta]
is directly related to the square of its linear momentum [mass-velocity]

Quantum Mechanics

$$h = \frac{E}{v^2}$$



Quantised energy
equilateral momenta

hv^2



Quantised Energy momenta is related to
Scalar mass energy momenta through
the equilateral geometry of Planck's constant

Newtonian physics

$$m = \frac{E}{v^2}$$



Scalar energy
linear momentum

pv

$$m\Omega v^2 = E = mv^2$$

Inertial resistance to Force

Inertia is the resistance of any physical object
to a change in its state of motion.



*Changes to mass-velocity
require a corresponding
change to boson quanta*



*Changes to mass-velocity
produces a change in an
object's Kinetic Energies*



$$E = mc^2$$

***The total intrinsic momenta of
all energy waveforms is the
sum of their constituent
Quantised Angular momenta
(mass-energy momenta)***

$$M_0 = m/c^2$$

$$KEM = Mv^2$$

***Matter in motion
has Kinetic Energies
in addition to invariant
rest mass-Energy***

KE = RE - rest Matter

Any change in motion results in changes to
the Charge geometries creating in turn proportional
changes to KEM mass and momenta components

$$F = ma$$

**The 'inductive resistance' of Charge quanta fields to
changes in their mass-energy momenta content
is what we term Inertia**



quantised moment of inertia

**Any change to an object's velocity results in a corresponding
change to its mass-Energy momenta which is reflected by its inertia**

$$p^2 = E = mv^2$$

Inertial mass can be related to Charge through inductive Planck quanta



quantised moment of inertia

Quantised Angular momentum

As it is a physical [equilateral] geometry QAM is conservative in any system where there are no external Forces and serves as the foundational geometric source for all the conservation laws of physics


m
ε_0
$\frac{m^2}{s}$
m^2
Quantised Angular Momenta
1 second

Angular momentum is sometimes described as the rotational analog of linear momentum, in Tetryonics it is revealed to be the equilateral geometry of quantised mass-energy momenta within any defined space-time co-ordinate system

A major re-definition of quantised angular momentum in physics is revealed


$\frac{m^2}{s}$
classical rotational angular momentum
≈
[v-v]
1
1
3
4
5
9
7
16
9
25
11
36
13
49
15
64
$\frac{m^2}{s}$
Quantised Angular momentum

In quantum mechanics, angular momentum is quantised – that is, it cannot vary continuously, but only in ODD number "quantum steps" between the allowed SQUARE nuclear Energy levels

In physics, angular momentum, moment of momentum, or rotational momentum is a conserved vector quantity that can be used to describe the overall state of a physical system.

When applied to specific mass-Energy-Matter systems QAM reveals the true quantum geometry and nature of Energy in our universe


h
$kg \frac{m^2}{s}$
m
mΩ
mass x QAM

Planck's Constant

Normally viewed as an expression of rotational momentum Quantised Angular Momentum [QAM] is in fact a result of the equilateral geometric quantization of mass-energy

Copyright ABRAHAM [2008] - All rights reserved

Charged geometries

All charge geometries are nett divergent


Q
[v-v]
1
3
5
7
9
11
13
15
1
4
9
16
25
36
49
64
1
2
3
4
5
6
7
8

Divergent energy momenta	Convergent energy momenta
1	0
3	1
6	3
10	6
15	10
21	15
28	21
36	28

All charge geometries are comprised of finite equilateral energy momenta quanta

Renormalisation

Renormalization was first developed in quantum electrodynamics (QED) to make sense of infinite integrals in perturbation theory.
The problem of infinities first arose in the classical electrodynamics of point particles in the19th and
later in the calculation of Gravitational fields in General Relativity in the early 20th century.

In QED Infinities must be cancelled





In Tetryonics Infinities do not exist



The mass of a charged particle should include the mass-energy in its electrostatic field (Electromagnetic mass) which in turn would approach infinity as the electron radius decreases.

Tetryonics solves the problem by clearly differentiating between EM mass and Matter and using finite equilateral geometries for all Matter in motion

Initially viewed as a suspicious provisional procedure by some of its originators, renormalization was eventually embraced as an important and self-consistent tool in several fields of physics and mathematics.

Copyright ABRAHAM [2008] - All rights reserved

2D space [c²]

The adjective Cartesian refers to the French mathematician and philosopher René Descartes who developed the coordinate system in 1637

Since then many other coordinate systems have been developed such as the polar coordinates for the plane, and the spherical and cylindrical coordinates for three-dimensional space.



Cartesian coordinates are the foundation of analytic geometry, and provide enlightening geometric interpretations for many other branches of mathematics, such as linear algebra, complex analysis, differential geometry, multivariate calculus, group theory, and more

Mapping 3D spaces using Recti-linear co-ordinates

Cartesian coordinates can be defined as the positions of the perpendicular projections of a point onto the two or more axes, expressed as signed distances from the origin.



3D Cartesian co-ordinate [c³] systems are distinct from spherical co-ordinate [c⁴] systems

Polar co-ordinates

In mathematics, the polar coordinate system is a two-dimensional co-ordinate system in which each point on a plane is determined by a distance from a fixed point and an angle from a fixed direction.



In geometry, curvilinear coordinates are a coordinate system for Euclidean space in which the co-ordinate lines may be curved.

Action Dynamics

Curvilinear co-ordinates may be derived from a set of rectilinear Cartesian coordinates by using a locally invertible transformation that maps one point to another in both systems

Metric Tensors



Gravitational acceleration

Polar or curvilinear co-ordinate systems are used extensively by Einstein in his theory of General Relavtivity

Reimannian curved space-time

Copyright ABRAHAM [2008] - All rights reserved

Co-ordinate transformations

There are many different possible coordinate systems for describing geometrical figures and they can all be related to one another.

Such relations are described by coordinate transformations which give formulas for the coordinates in one system in terms of the coordinates in another system



Converting between Polar and Cartesian coordinates



$$\tan\theta = \frac{\text{opposite}}{\text{adjacent}}$$

$$= \tan^{-1}(5/12)$$

$$= 22.619$$



$$r^2 = 12^2 + 5^2$$

$$= \sqrt{169}$$

$$= 13$$

solving for the triangle using trigometric functions

Spatial co-ordinates systems

Cubic



Spacetime is any mathematical co-ordinate system or model that combines space and time into a single continuum.

Spacetime is usually interpreted with space as being three-dimensional with time playing the role of a fourth dimension that is different from the spatial dimensions.

From a Euclidean space perspective, the universe has three spatial dimensions and one dimension of time [reflected by quantised angular momentum].

Spherical



Tetryonics maps spatial co-ordinates through the momenta vectors of equilateral Energy

Cartesian Space-Time





EM mass-ENERGY momenta are equilateral geometries

Mapping equilateral Energy geometries onto recti or curvi-linear spatial co-ordinate systems introduces mathematical complexity to a otherwise simplistic geometry for all EM mass-Energy-Matter interactions

Tetryonic Space-Time



In physics spatial co-ordinates to date have been based on Cartesian co-ordinates when in fact Energy momenta follow a Tri-Linear co-ordinate geometry

vectors

1 Dimensional velocity

Euclidean


c
ε_0
c^2
μ_0
seconds
c

2 Dimensions velocity squared

$$m = \frac{E}{c^2}$$

mass-energy equivalence

mass-Matter

$$\frac{m}{c^2} = M$$

equivalence

$$T_{\mu\nu}$$

energy-Matter equivalence

$$M = \frac{E}{c^4}$$

GR fails differentiate betweem EM mass-ENERGY-Matter unlike Tetryonic theory

Cartesian co-ordinates


z
c
$T_{\mu\nu}$
c^3
c
x
c
y

3 Dimensions velocity cubed

Spherical


0
c
270
c
c^4
c
90
seconds squared
c
180

3 Dimensions quadrature velocity

Space-time co-ordinates

The propagation of Energy momenta forms distinct spatial co-ordinate systems

Where angles are typically measured in degrees (°) or radians (rad), where 360° = 2π rad = τ radians.

Tetryonic co-ordinate systems

Energy per second

m



2D mass-energy geometries




z
planar
[x,z]
planar
[y,z]
volumes
[x,y,z]
x
y
[x,y]
planar
time

Planar mass-energy geometries have no z-components

Differentiation between 2D mass-energy & 3D Matter is key to extending our understanding of physics

Matter topologies have z-components

Energy per second squared

M



Proton

3D Matter topologies

Neutron



Copyright ABRAHAM [2008] - All rights reserved


1
1
1
1
1
1
1
2
3
4
1 2 1
1
1
1
2
3
4
3
5
9
1 2 3 2 1
1
1
1
2
3
4
5
9
3
4
7
16
1 2 3 4 3 2 1


ν
square roots
ODD numbers
SQUARE numbers
Ψ
hν
ν²
1 2 3 4 5 6 … n … 6 5 4 3 2 1
normal distributions


1 1
1 2
3 4
5 9
3 4
7 16
9 25
5
1 2 3 4 5 4 3 2 1
1 1
1 2
3 4
5 9
3 4
7 16
9 25
5
11 36
6
1 2 3 4 5 6 5 4 3 2 1
1 1
1 2
3 4
5 9
3 4
7 16
9 25
5 6
11 36
13 49
7
1 2 3 4 5 6 7 6 5 4 3 2 1
1 1
1 2
3 4
5 9
3 4
7 16
9 25
5 6
11 36
13 49
7 8
15 64
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1

Quantum probability distributions

The equilateral geometry and distribution of quantised Energy momenta provides the basis for all statistical probabilities in Quantum mechanics, thermodynamic & information entropy - including a solution to Heisenberg's Uncertainty Principle thus paving the way forward for a new understanding, and manipulation of physical phenomena at the quantum level

1
1 2 1
1 2 3 2 1
1 2 3 4 3 2 1
1 2 3 4 5 4 3 2 1
1 2 3 4 5 6 5 4 3 2 1
1 2 3 4 5 6 7 6 5 4 3 2 1
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1

Normal distributions are extremely important in statistics, and are often used in the natural and social sciences for real-valued random variables whose distributions are not known

Copyright ABRAHAM [2008] - All rights reserved

Quantum Probability Distributions

The normal distribution is a probability distribution.
It is also called Gaussian distribution because it was discovered by Carl Friedrich Gauss.

x/n^2

Probabilities are
the square of the
Amplitude

n

$\Sigma x/n^2$

All probabilities
are re-normalisable
and sum to Unity

1

square root momenta

v



ODD
transverse
Bosons

EVEN
Longitudinal
Photons

Planck
quanta

hv

v^2

Square
energies

Normal Distribution

c^2

Quanta Distributions

$$2h\nu = E = hf$$

Quantum Levels

transverse bosons

Quantum Probabilities

longitudinal photons


W+
W-
E
N
S
+
−
64
64
64
γ
1
3
5
7
9
11
13
15
1
2
3
4
5
6
7
8
1/64
2/64
3/64
4/64
5/64
6/64
7/64
8/64

Wavefunctions


Quantum Levels
h
KEM fields
Transverse Bosons
Longitudinal Photons
Quantised Angular Momenta
ElectroMagnetic Waves
v
1 2 3 4 5 6 7
c
7 6 5 4 3 2 1
v
Velocity
Amplitude Probabilities
Linear momentum
Squared energies
Vector Forces
$\frac{v^2}{c^2}$
Energy momenta

EM waveforms



All EM waveforms can be measured by either their Transverse EM masses [Bosons] or their Longitudinal EM masses [Photons]

BOSONS

Bosons Planck quanta

$\frac{\text{ODD}\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$

mass velocity

vs.

PHOTONS

EM waves Planck quanta

$\frac{\text{EVEN}\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$

mass velocity


Longitudinal wave Amplitude
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1
64
Longitudinal Frequency (*f*)
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1

Photons are longitudinal quanta


1 3 5 7 9 11 13 15 15 13 11 9 7 5 3 1
Transverse wave Amplitude
128
Transverse Frequency (v)
1 3 5 7 9 11 13 15 15 13 11 9 7 5 3 1
EM Wavelengths
λ
KE
Wave Amplitude
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1
64
Photon Frequency (*f*)
c
c
Group Phase Velocity

$2hv = hf$

Bosons are transverse quanta

Copyright ABRAHAM [2008] - All rights reserved

Quantum Energy distributions



$E = h\nu$

$E = hf$

Quanta

Quantum

Medium dependent
Group Phase Velocity

ν

f

Transverse Boson quanta

Longitudinal Photon Frequency

Quantum
Energy
Levels
[n²]

Wavefunction

Levels

Waveforms

Bosons

Planck quanta

$$\frac{\mathrm{ODD}\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

EM waves

Planck quanta

$$\frac{\mathrm{EVEN}\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

$E = p^2$

Normal Distributions

The Gaussian distribution sometimes informally called the bell curve.

Pierre de Fermat

Pierre de Fermat is given credit for early developments that led to infinitesimal calculus.

$$\frac{1}{\sqrt{2\pi\sigma^2}}\,e^{-\frac{(x-\mu)^2}{2\sigma^2}}$$


mean
-2.58σ
-1.96σ
-1.69σ
-1.0σ
-.67σ
+.67σ
+1.0σ
+1.69σ
+1.9σ
+2.58σ
50% of the area
68% of the area
90% of the area
95% of the area
99% of the area
S.L.

$$\frac{1}{2}\left[1+\operatorname{erf}\left(\frac{x-\mu}{\sqrt{2\sigma^2}}\right)\right]$$

Leonhard Euler

Leonhard Euler developed a formula which links complex exponentiation with trigonometric functions

all ODD numbers are

$$a^2 - b^2 = [a-b].[a+b]$$

the difference of two squares

A bell shaped curve defines the standard normal distribution, in which the probability of observing a point is greatest near the average, and declines rapidly as one moves away from the mean.

$$e^{i\pi} = -1$$


v
p
SQUARE roots
Transverse
Bosons
[ODD numbers]
Scalar Energy
EM waves
[SQUARE numbers]
hv
v²
n-1
n
n-1
[normal distribution]



The Normal Distribution

$\Pr(x) = \frac{1}{\sqrt{2\pi}}\, e^{-x^2/2}$

The Binomial Theorem

$\Pr(k) = (n!/(n-k)!\,k!)\,p^{(n-k)}q^{k}$

$p = q = ½ ,\ n = 13$

36 Random Events

The "Law" of Errors

σ = standard deviation

$\Pr(x) = \frac{1}{\sqrt{2\pi\sigma}}\, e^{-x^2/2\sigma}$

Central Limit Theorem

In the limit of large numbers, the sum of independent random variables will be normally distributed.


-1
odd no.
bosons
squared
energies
Ω
1
2
3
4
5
6
5
4
3
2
1
longitudinal photon distributions

In probability theory, the normal (or Gaussian) distribution is a continuous probability distribution that has a bell-shaped probability density function, known as the Gaussian function

Fundamental theorem of Energy momenta

A nth level scalar energy momenta waveform has exactly n linear momentum in unit circle co-ordinate systems
(with Longitudinal and Transverse equilateral Planck waveforms being orthogonal to each other)

scalar energies

E

mv^2


+1
90°
1/4τ
3π/4
π/4
transverse
frequency
Q
180°
-1
1/2τ
Maxwell
Q
Tesla
tau
+1
0°
emf
voltage
Q
5π/4
Hertz
7π/4
3/4τ
270°
-1

Longitudinal EM waveforms are the waves produced by spark gap discharges

Their energy momenta are co-linear with the wave's direction of propagation

p

mv

linear momentum

Transverse EM waveforms are the waves produced by accelerating charges

Their energy momenta are orthogonal to the direction of wave propagation

[Mathematics] *i or j* *[Electrical theory]*

square root of negative one

Velocity and Time dependent EM fields



Quantum levels


v
1
2
3
4
3
5
9
4
7
16
5
9
25
6
11
36
13
49
15
64
17
9
81
hv
v²
c²
Matter
Tπ
topologies
EM Field
ε₀μ₀
Planck quanta
mΩv²
ElectroMagnetic mass
velocity

$$T\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

SQUARE ROOT
momenta

EVEN number
PHOTONS

ODD number
BOSONS

SQUARE number
ENERGIES



Wave probabilities

All EM geometries are comprised of Transverse quantum levels and Longitudinal wave probabilities

Matrices

Matrices are a key tool in linear algebra.
One use of matrices is to represent linear transformations,
which are higher-dimensional analogs of linear functions
of the form f(x) = cx, where c is a constant; matrix multiplication
corresponds to composition of linear transformations.

Further developing equilateral Matrices and tensor mathematics to
reflect the 2D geometry of EM , KEM and GEM quantum fields,
along with the geometric quantisation of mass-energiy momenta
and their energy distributions allows for field interactions
to be accurately visualised and modelled


n1
1x1
n2
2x2
n3
3x3
n4
4x4
v
E
KE
M
M
hv
v²
c²
Positive Fields
v
E
KE
M
M
hv
v²
c²
Negative Fields
v
p
1
2
3
4
5
6
7
8
n5
5x5
n6
6x6
n7
7x7
n8
8x8

Tensors are geometric entities introduced into mathematics and physics to extend the notion of scalars, geometric vectors, and matrices to increasingly higher orders.

Modifying Square matrices to reflect the equialteral geometries of Tetryonic fields allows for the accurate geometric modelling of all Scalar & Vector fields along with their varied intrinsic quantum energies and physical properties

Energy momenta Tensors

momenta
(a property of Energy)
is converative



$$p_M \longrightarrow (E, p1, p2, p3, p4).$$

All standing-wave Matter topologies can be modelled using its Tetryonic charge energy momenta Tensors

with an additional Kinetic EM energy-momenta tensor required for Matter in motion

$$p_{KEM} \longrightarrow (E, p5).$$

Matter
(a geometric property)
is NOT conservative



2D+1 [SR] mass-energy momenta can be folded into 3D+1 [GR] Matter
that can be modelled using 4 Energy-momenta tensors



Positive standing-wave
Matter

$$E = \sum_{\text{all fascia}} E$$

Energy of a massive particle
is the total of all Planck quanta
(compton frequency) in a 3D geometry



$$\vec{p} = \sum_{\text{all fascia}} \vec{p}$$

Total Momentum
is the total of all quanta
linear Momenta in a 3D particle



Negative standing-wave
Matter

Relativistic Matter
in motion



$$I = \sum_{\text{all fascia}} I$$

Inertial mass
is the total of all inertia
in a 3D particle



Photons have
null
energy-momentum
tensors

Note that both
2D mass-energies [Special Relativity]
and 3D Matter [General Relativity]
have distinct Energy momenta

It is the 3D Tetrahedral topologies that
provides a definative basis for Matter

Relativistic Matter
in motion



Tetryonic Energy momenta tensors should not be confused with Four vector tensors
which map energy-momenta vectors in 3D spatial[cartesian] co-ordinate systems



Relativistic Lorentz correction factor

The Lorentz factor or Lorentz term is an expression which appears in several equations in special relativity
It is often incorrectly graphed [as pictured to the right] as an increasing function of velocity approaching but never reaching c

'c' is the maximum velocity acheivable through the electrical acceleration of particles is NOT the maximum velocity possible for Matter in motion



Linear correction factor

$$\beta = \left[\frac{v}{c}\right]$$





Scalar correction factor

$$\beta^2 = \left[\frac{v^2}{c^2}\right]$$

Lorentz factors are LINEAR and SCALAR velocity related corrections to the relativistic mass-energy momenta content of any physical system accelerated by EM Forces

$$\frac{\Delta\gamma}{c^2}$$ Wavelength contraction

Time Dilation $$\frac{\Delta\Omega}{c^2}$$

$$\frac{\Delta mv}{c^2}$$ Relativistic momentum

$$\frac{\Gamma}{c^2}$$ Lorentz corrections

Relativistic mass-energy $$\frac{\Delta hv}{c^2}$$

Equilateral energies

Any measurements of mass without a Space-Time co-ordinate system are measurements of Energy


v
Bosons
Energy
E
momentum
hv
v²
Photons

form the basis for all charged energy geometries and their associated quanta distributions




1 3
1 4
1 2
1/2 1 1/2


1 3 5
1 4 9
1 2 3
1/2 1 3/2 1 1/2


1 3 5 7
1 4 9 16
1 2 3 4
1/2 1 3/2 2 3/2 1 1/2


1 3 5 7 9
1 4 9 16 25
1 2 3 4 5
1/2 1 3/2 2 5/2 2 3/2 1 1/2


1 3 5 7 9 11
1 4 9 16 25 36
1 2 3 4 5 6
1/2 1 3/2 2 5/2 3 5/2 2 3/2 1 1/2


1 3 5 7 9 11 13
1 4 9 16 25 36 49
1 2 3 4 5 6 7
1/2 1 3/2 2 5/2 3 7/2 3 5/2 2 3/2 1 1/2


1 3 5 7 9 11 13 15
1 4 9 16 25 36 49 64
1 2 3 4 5 6 7 8
1/2 1 3/2 2 5/2 3 7/2 4 7/2 3 5/2 2 3/2 1 1/2


1 3 5 7 9 11 13 15 17
1 4 9 16 25 36 49 64 81
1 2 3 4 5 6 7 8 9
1/2 1 3/2 2 5/2 3 7/2 4 9/2 4 7/2 3 5/2 2 3/2 1 1/2

Copyright ABRAHAM [2008] - All rights reserved

Electromagnetic mass

2D mass-energy is the surface integral of 3D Matter


v
Bosons
Energy
m
hv
v²
Photons
c²

Time specific measurements of equilateral ENERGY momenta geometries forms the basis for EM mass




1
1
1
2
3
4
1/2
1
1/2
c²


1
1
1
2
3
3
4
5
9
1/2
1
3/2
1
1/2
c²


1
1
1
2
3
3
4
5
9
4
7
16
1/2 1 3/2 2 3/2 1 1/2
c²


1
1
1
2
3
4
3
4
5
9
7
16
5
9
25
1/2 1 3/2 2 5/2 2 3/2 1 1/2
c²


1
1
1
2
3
4
5
9
3
4
7
16
5
9
25
6
11
36
1/2 1 3/2 2 5/2 3 5/2 2 3/2 1 1/2
c²


1
1
1
2
3
4
5
3
9
4
7
16
9
5
25
11
6
36
13
7
49
1/2 1 3/2 2 5/2 3 7/2 3 5/2 2 3/2 1 1/2
c²


1
1
1
3
2
4
5
3
9
7
4
16
9
5
25
11
6
36
13
7
49
15
8
64
1/2 1 3/2 2 5/2 3 7/2 4 7/2 3 5/2 2 3/2 1 1/2
c²


1
1
1
3
2
4
5
3
9
7
4
16
9
5
25
11
6
36
13
7
49
15
8
64
17
9
81
1 2 3 4 4 3 2 1
c²

mass-less particles
is a physical misnomer

All measurements of energy
in spatial co-ordinate systems
are measurements of mass

Matter-less is the appropriate terminology

Standing-wave Matter

Matter is a higher order 3D topology created by standing wave mass-energies


v
momentum
Bosons
Energy
M
hν
v²
Photons
c⁴

The equilateral mass-ENERGY content of 4nπ Tetrahedral standing-wave topologies forms the basis of Matter




1
1
1
2
3
4
1/2
1
1/2
c⁴


1
1
1
2
3
3
4
5
9
1/2
1
3/2
1
1/2
c⁴


1 3 5 7
1 4 9 16
1 2 3 4
1/2 1 3/2 2 3/2 1 1/2
c⁴


1 3 5 7 9
1 4 9 16 25
1 2 3 4 5
1/2 1 3/2 2 5/2 2 3/2 1 1/2
c⁴


1 3 5 7 9 11
1 4 9 16 25 36
1 2 3 4 5 6
1/2 1 3/2 2 5/2 3 5/2 2 3/2 1 1/2
c⁴


1 3 5 7 9 11 13
1 4 9 16 25 36 49
1 2 3 4 5 6 7
1/2 1 3/2 2 5/2 3 7/2 3 5/2 2 3/2 1 1/2
c⁴


1 3 5 7 9 11 13 15
1 4 9 16 25 36 49 64
1 2 3 4 5 6 7 8
1/2 1 3/2 2 5/2 3 7/2 4 7/2 3 5/2 2 3/2 1 1/2
c⁴


1 3 5 7 9 11 13 15 17
1 4 9 16 25 36 49 64 81
1 2 3 4 5 6 7 8 9
1/2 1 3/2 2 5/2 3 7/2 4 9/2 4 7/2 3 5/2 2 3/2 1 1/2
c⁴

Only
mass-ENERGIES contained in
the tetryonic fascia of
standing-wave topologies
contribute to weight

Copyright ABRAHAM [2008] - All rights reserved

Periodic element nuclei


v
Bosons
Energy
momentum
M
v
v²
Photons
c4

The mass-ENERGY content of
4nπ Tetrahedral standing-wave topologies
forms the basis of all periodic elements






c4
n
0
42-42
45,012

ALL
periodic elements are
comprised of
n level deuterium
nuclei



μ_0
ε_0
p
d



2D radiant EM mass-Energies
μ_0
ε_0

n1 - Charged Tetryon Templates



3D standing-wave Matter



μ_0
ε_0
p
d





2D radiant EM mass-Energies

n1 - Neutral Tetryon Templates



3D standing-wave Matter







2D radiant EM mass-Energies

n2 - Charged Tetryon Templates



3D standing-wave Matter




p
d
ε_0
μ_0


ε_0
μ_0

2D radiant EM mass-Energies

n2 - Neutral Tetryon Templates



3D standing-wave Matter


p
d
ε_0
μ_0




2D radiant EM mass-Energies

n3 - Charged Tetryon Templates


3D standing-wave Matter







2D radiant EM mass-Energies

n3 - Neutral Tetryon Templates



3D standing-wave Matter







2D radiant EM mass-Energies

n4 - Charged Tetryon Templates



3D standing-wave Matter






2D radiant EM mass-Energies
ε0
μ0

n4 - Neutral Tetryon Templates


3D standing-wave Matter




p
d
ε_0
μ_0


ε_0
μ_0

2D radiant EM mass-Energies

n5 - Charged Tetryon Templates



3D standing-wave Matter


p
d
ε_0
μ_0


p
d
μ_0
ε_0


2D radiant EM mass-Energies
μ_0
ε_0

n5 - Neutral Tetryon Templates


3D standing-wave Matter


p
d
μ_0
ε_0




2D radiant EM mass-Energies
ε0
μ0

n6 - Charged Tetryon Templates


3D standing-wave Matter



Copyright ABRAHAM [2008] - All rights reserved


p
d
ε_0
μ_0


μ_0
ε_0

2D radiant EM mass-Energies

n6 - Neutral Tetryon Templates



3D standing-wave Matter


p
d
ε_0
μ_0




2D radiant EM mass-Energies
ε0
μ0

n7 - Charged Tetryon Templates


3D standing-wave Matter






2D radiant EM mass-Energies
ε0
μ0

n7 - Neutral Tetryon Templates


3D standing-wave Matter






2D radiant EM mass-Energies
μ0
ε0

n8 - Charged Tetryon Templates


3D standing-wave Matter



Copyright ABRAHAM [2008] - All rights reserved





2D radiant EM mass-Energies

n8 - Neutral Tetryon Templates



3D standing-wave Matter





Each shell consists of one or more subshells, and
each subshell consists of one or more atomic orbitals.

Periodic element geometries

An electron shell may be thought of as an orbit followed by electrons around an atom's nucleus.
The closest shell to the nucleus is called the "1 shell" (also called "K shell"), followed by the
"2 shell" (or "L shell"), then the "3 shell" (or "M shell"), and so on further and further from the nucleus.
The shell letters K, L, M, ... are alphabetical


0
42-42
N°
n
e-
P+
45,012

Each shell can contain only an integer
number of whole deuterium nuclei
[Proton, Neutron & electron]


Electron Shells
R
Q
P
O
N
M
L
K
Q
[v-v]
RE
2
8
18
Z
32
32
18
8
2
M₀
KE
8
7
6
5
4
3
2
1
Principal Quantum Numbers
f
+3
d
+2
p
+1
s
0
p
-1
d
-2
f
-3
Sub-orbitals

VALENCE SHELLS
The electrons in the partially filled
outermost [or highest energy]
shell determine the chemical
properties of the atom

Each atomic shell equates to a specific
Energy level for the dueterium nuclei
that comprise it, in turn affecting the
angular momentum of electrons in that shell

Copyright ABRAHAM [2008] - All rights reserved

Periodic Harmonic motions

$x = A\cos(\omega t + \varphi)$

Circular motion

Much of the math in of modern physics is predicated on the assumption that π [where it appears] is related to the properties of a circle

$F = -kx$

Linear motion


96°
96°
32
32
Z
18
18
54°
54°
8
2 2
8
24°
24°
6° 6°

$$P\sum 2(n^2)$$


2
8
18
32
32
18
8
2
Z

Simple harmonic motion can be visualized as the projection of uniform circular motion onto one axis

circular harmonic motion

simple harmonic motion

Principal Quantum Numbers


3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
Q
RE
M₀
KE
2
8
18
32
32
18
8
2
Z
8
7
6
5
4
3
2
1
electron shells
energy levels
f d p s p d f

Sub-orbitals

Circular motions describe the motion of a body with a changing velocity vector [the result of an acceleration force].

Nuclei per shell in elements follows a 'periodic summation rule' that is reflective of photonic energies

Copyright ABRAHAM [2008] - All rights reserved

E

The quantum level mass-energies of Baryons determines the kinetic energies of electrons

1n - 1 e19v



Baryon mass-energies n			electron KEM field hv^2
73,728	n32	v8	3.268969693 e15
69,192	n31	v7	2.502804921 e15
64,800	n30	v6	1.838795452 e15
60,552	n29	v5	1.276941286 e15
56,448	n28	v4	8.172424232 e14
52,488	n27	v3	4.596988631 e14
48,672	n26	v2	2.043106058 e14
45,000	n25	v1	5.107765145 e13

Compton frequencies
930 MeV

1.2 e20
electron rest Matter is velocity invariant
496 keV

spectral frequencies
13.6 eV

Atomic nuclei mass-energies

Each element's weight [mass-Matter in a gravitational field] is the result of the total quanta comprising that element



The nuclei forming each atomic shell have specific mass-energy quanta

$$\overset{8}{\underset{1}{\mathrm{n}}}\Big[\overset{\text{Baryon rest masses}}{[72(n)^2]}+\overset{\text{lepton rest mass}}{[12e19]}+\overset{\text{KEM}}{[m_e v^2]}\Big]$$

Deuterium mass-energy per shell

Despite having differing mass-energies each Deuterium nuclei has the same velocity invariant Matter geometry [84π]

spin orbital coupling in synchronous quantum convertors

Electrons act as quantum scale rotating armatures in atomic nuclei and can only have specific energies reflective of the electron orbital energy level of the Baryons in which they are found

They acheive these energy levels by absorbing or emitting photons to acheive the specific angular momentum required

$$\overset{\text{Baryons}}{930.947\text{ MeV}} + \overset{\text{KEM fields}}{13.525\text{ ev}} + \overset{\text{electrons}}{496.519\text{ keV}}$$

Mapping Planck mass-energy contributions to elementary Matter and isotopes


Schrodinger's quantum numbers
3 2 1 0 1 2 3
electron shells
R
Q
P
O
N
M
L
K
energy levels
8
7
6
5
4
3
2
1
Q
[v-v]
RE
M₀
KE
Z
2
8
18
32
32
18
8
2
f d p c4 p d f
Bohr's atomic orbitals

$$E = hv^2$$

$$n^2 + v^2 + e = Z$$

general form quatratic equation

$$ax^2 + bx + c = Z$$

$$E = nhv$$


E
polar aufbau

polar energy spirals courtesy of Rene Cormier

Identifying electron rest Matter topologies as velocity invariant we can re-arrange the component Planck mass-energy geometry formulation of periodic elements to

$$h\left[\underset{\text{Deuteron rest mass}}{72[v^2]} + \underset{\text{Spectral lines}}{v} + \underset{\text{electron rest mass}}{1.20\text{ e}20\ v}\right]$$

reveal a quadratic formulation for all Z numbers

$$\sum_{K}^{R}$$

nuclei per shell

$$ {}^{R}_{K}P\sum Z$$

Periodic Summation

Periodic summation is a notation developed for Tetryonic theory
to model the geometric series addtion of Z[n²] energy level
Deuterium nuclei that form the periodic elements

$$\sum_{1}^{120} Z$$

element number

STEP ONE

Periodic summation follows the atomic shell electron config

STEP TWO

Periodic elements build up following the aufbau sequence

1 R
2
3
4
4
3
2
1 K

$$ {}^{R}_{K}P\sum 2(x^{2}) =$$



$^{P}\sum R = 2$	2 nuclei [74,496 ea]	+	120	Unbinilium
$^{P}\sum Q = 8$	8 nuclei [69,780 ea]	+	118	Ununoctium
$^{P}\sum P = 18$	18 nuclei [65,232 ea]	+	110	Darmstadtium
$^{P}\sum O = 32$	32 nuclei [60,852 ea]	+	92	Uranium
$^{P}\sum N = 32$	32 nuclei [56,640 ea]	+	60	Neodymuim
$^{P}\sum M = 18$	18 nuclei [52,596 ea]	+	28	Argon
$^{P}\sum L = 8$	8 nuclei [48,720 ea]	+	10	Neon
$^{P}\sum K = 2$	2 nuclei [45,012 ea]		2	Helium
			0	Hydrogen

Each atomic shell can hold only a fixed number of deuterium nuclei

THe LHS of the notation determine the number of nuclei in each atomic shell, from the periodic mass-energy levels for atoms, and the RHS follows the aufbau building principle to determine the rest mass-Matter of any specific element

Aufbau

Each periodic element is made of Z [n² energy] deuterium nuclei

$$Z\#\left[\begin{array}{ll} z\ \text{Protons} & [24\text{-}12] \\ z\ \text{Neutrons} & [18\text{-}18] \\ z\ \text{electrons} & [0\text{-}12] \end{array}\right] n1\text{-}8$$

Planck mass-energies form the surface integral of rest Matter topologies for each periodic element

Copyright ABRAHAM [2008] - All rights reserved

Proton - Neutron Curve

The graph below is a plot of neutron number against proton number.
It is used as rule to determine which nuclei are stable or unstable.



Plot of Baryon numbers based on excess Neutron model of periodic elements

Deviation from Tetryonic plot is the result of the intrinsic mass-energies of each particle comprising the atomic nucleus

Plot of Baryonic nuclei numbers based on Tetryonic topologies of periodic elements

Historically, Proton-electron numbers are viewed as being equivalent in neutral elementary matter with the excess molar mass measured being the result of 'excess or extra' Neutrons in the atom

Atomic Nuclei Numbers

All periodic elements have an EQUAL number of Protons, Neutrons & Electrons with their molar mass-Matter being determined by their quantum level mass-energies



Tetryonic modelling of the charged mass-ENERGY-Matter topologies of elementary atoms and the nuclei that comprise them, reveals a DIRECT LINEAR relationship for the number of Protons-electrons-Neutrons in all periodic elements and nuclear isotopes

Copyright ABRAHAM [2008] - All rights reserved

Planck mass-energy contributions to elementary Matter and isotopes

The mass-energy content of Deuterium nuclei creates the molar mass of elements
[not extra neutrons in excess of the elemental number]


Deuteron
electron
eV
KEM
Z
32
3,050.6 MeV
8
En = -13.52 eV
291,166
31
2,5862.9 MeV
7
En = -10.35 eV
285,065
30
2,6811 MeV
6
En = -7.60 eV
262,158
29
2,505.4 MeV
5
En = -5.28 eV
213,887
28
2,335.6 MeV
4
En = -3.38 eV
133,697
27
2,171.8 MeV
3
En = -1.90 eV
58,940
26
2,013.9 MeV
2
En = -0.84 eV
19,840
25
1,861.9 MeV
1
En = -0.21 eV
3,725
496.519 keV
n
Quantum levels
v^2
2H+
291,107 MeV
Elemental mass-Matter
[in MeV]
59,580 keV
e
3,724 MeV
993 keV
En = -0.42 eV
16,111 MeV
3,972 keV
En = -6.72 eV
39,092 MeV
8,937 keV
En = -34.2 eV
74,740 MeV
15,888 keV
En = -108.16 eV
80,174 MeV
15,888 keV
En = -168.96 eV
48,262 MeV
8,937 keV
En = -136.8 eV
22,903 MeV
3,972 keV
En = -82.8 eV
6,101 MeV
993 keV
En = -27.05 eV
565.11 keV
KEM field mass-energies
[in eV]
KE
2 + 8 + 18 + 32 + 32 + 18 + 8 + 2
nuclei number per shell
electron shells
R
Q
P
O
N
M
L
K
Schrodinger's quantum numbers
3
2
1
0
1
2
3
Q
[v-v]
RE
2
8
18
32
Z
32
18
8
2
M0
KE
c4
f
d
p
p
d
f
Bohr's atomic orbitals
8
7
6
5
4
3
2
1
energy levels

n1
Elementary nuclei

are comprised of equal numbers of
Protons, Neutrons & electrons
with varying energy levels

Baryons		electrons		KEM fields
930.947 MeV	+	**496.519 keV**	+	**13.525 ev**

The mass-energy content of Matter topologies is velocity invariant

The mass-energy content of Baryons determines the KEM field of electrons

Copyright ABRAHAM [2008] - All rights reserved

All elements are comprised of n level Duetrium nuclei

Baryons **KEM fields** **electrons**

$$Z\,[[72n^2] + [12v^2] + [1.2e20]]$$

1,861,949 MeV **13.525 eV** **496,519 keV**

The atomic shell energy levels of Deuterium nuclei in elements

Deuteron **electron eV** **KEM**


32
3,050.6 MeV
8
En = -13.52 eV
31
2,5862.9 MeV
7
En = -10.35 eV
30
2,6811 MeV
6
En = -7.60 eV
29
2,505.4 MeV
5
En = -5.28 eV
28
2,335.6 MeV
4
En = -3.38 eV
27
2,171.8 MeV
3
En = -1.90 eV
26
2,013.9 MeV
2
En = -0.84 eV
25
1,861.9 MeV
1
En = -0.21 eV
496.519 keV
n
v²


atomic shells
nuclei per shell
p
Σ
c²

Shell	Baryons	KEM fields	electrons		nuclei per shell
R	3,050.6 MeV	13.525 eV	496,519 keV	Z [[72*32n²] + [12*8v²] + [1.2e20]]	2
Q	2,862.9 MeV	10.35 eV	496,519 keV	Z [[72*31n²] + [12*7v²] + [1.2e20]]	+ 8
P	2,681.2 MeV	7.60 eV	496,519 keV	Z [[72*30n²] + [12*6v²] + [1.2e20]]	+ 18
O	2,505.4 MeV	5.28 eV	496,519 keV	Z [[72*29n²] + [12*5v²] + [1.2e20]]	+ 32
N	2,335.6 MeV	3.38 eV	496,519 keV	Z [[72*28n²] + [12*4v²] + [1.2e20]]	+ 32
M	2,171.7 MeV	1.90 eV	496,519 keV	Z [[72*27n²] + [12*3v²] + [1.2e20]]	+ 18
L	2,013.8 MeV	0.84 eV	496,519 keV	Z [[72*26n²] + [12*2v²] + [1.2e20]]	+ 8
K	1861.9 MeV	0.21 eV	496,519 keV	Z [[72*25n²] + [12*1v²] + [1.2e20]]	+ 2

$2H^+$ $[72n^2]$ **Z** γ $[M_e v^2]$

Elemental mass-Matter
[in MeV]

6,101 MeV
993 keV
En = -27.05 eV
+
22,903 MeV
3,972 keV
En = -82.8 eV
+
48,262 MeV
8,937 keV
En = -316.8 eV
+
80,174 MeV
15,888 keV
En = -168.96 eV
+
74,740 MeV
15,888 keV
En = -108.16 eV
+
39,092 MeV
8,937 keV
En = -34.2 eV
+
16,111 MeV
3,972 keV
En = -6.72 eV
+
3,724 MeV
993 keV
En = -0.42 eV

[1.2e20]]

e

Determines the spectral line [KEM field energies] of electrons bound to them

The relativistic rest mass-energy-Matter of all periodic elements
is the sum of the mass-energies of all atomic nuclei and spectral lines that comprise its mass-Matter topology as measured in any spatial co-ordinate system per unit of time

the rest mass-Matter of bound photo-electrons is velocity invariant

Ionisation energies

Fractional quantum differentials


RE
M+KE
h
e
Mv^2 = KEM = p^2
R
R
180
156
132
108
84
60
36
Lyman
Balmer
Paschen
Brackett
Pfund
Humphries
un-named
12
48
108
192
300
432
588
768
972
KEM energies
1
2
3
4
5
6
7
8
ε_0
n

$$hf = \Delta Mv = \Delta p$$

spectral lines are produced by accelerating electrons

Note: this is an Illustrative schema for modelling KEM field energies
All KEM fields possess the same physical spatial geometry
in radial-time defined spatial co-ordinate systems

c^2 c^4




Higher energies
S up
e⁻
S down
Lower Energies

Photo-electrons absorb/emit spectral energies

$$E = eV = \frac{1}{4\pi\epsilon_0}\frac{ne^2}{a}$$

photo-electronic energy momenta


v
RE
KE
1
4
9
16
25
36
49
64
12
48
108
192
300
432
588
768
Spectral Lines
KEM Energies
p
KE
hv
v^2
M
12
[0-12]
1.2e20
Q
M

Mapping photo-electron transition energies
to Tetryonic energy momenta geometries
reveals many key facts about the
ionisation energies of nuclei

$$E = -\frac{Z^2}{n^2}\frac{ke^2}{2a_0} = -\frac{13.6Z^2}{n^2}eV$$

The differing fractional KEM field energy momenta of electrons
that results from their transitions to specific energy nuclei
in elements results in differing QAM quanta and
produces spectral lines and fine line splitting

Spectral line transitions


Δv
Σv
KEM
Quantum differentials
36
60
84
108
132
156
180
3
5
7
9
11
13
15
1
2
3
4
5
6
7
8
1^2
2^2
3^2
4^2
5^2
6^2
7^2
8^2
36
96
180
288
420
576
756
48
108
192
300
432
588
768
hv
v
c
v^2
Mv^2

*h*v, R, β, p, KE
Planck, Rydberg, Lorentz, Newton, Leibniz

uniting classical physics and relativity
through equilateral geometry

Element numbers

Nuclei per shell in elements follow
a 'periodic summation rule'
that is reflective of
photonic energies

1 R
2
3
4
4
3
2
1 K

$$\sum_{K}^{R} {}^{P}\, 2(x^2) = 2 + 8 + 18 + 32 + 32 + 18 + 8 + 2$$

Z

120	Unbinilium	n8
119	Ununennium	
118	Ununoctium	n7
87	Francium	
112	Copernicium	n6
55	Caesium	
102	Nobelium	n5
37	Rubidium	
70	Ytterbuim	n4
19	Potassium	
30	Zinc	n3
11	Sodium	
10	Neon	n2
3	Lithium	
2	Helium	n1
1	Deuterium	
Hydrogen	0	


Principal Quantum Numbers
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
electron shells
Q
[v-v]
RE
M₀
KE
2
8
18
32
Z
32
18
8
2
8
7
6
5
4
3
2
1
energy levels
f
d
p
s
p
d
f
Sub-orbitals

Periodic mass-ENERGY-Matter

Following periodic summation rules for shell filling
n[1-8] quantum energy deuterium nuclei
combine to form elementary Matter

$$\boxed{\sum_{K}^{R} {}^{P} {}_{25}^{32}\left[\overset{\text{Baryon rest masses}}{\left[72(n)^2\right]} + \overset{\text{lepton rest mass}}{\left[12e19\right]} + \overset{\text{KEM}}{\left[m_e v^2\right]}\right]_{1}^{8}}$$

Deuterium mass-energy per shell

The measured weight of Matter in gravitational fields is the result of
planar mass-energies in tetryonic standing-wave geometries

The periodicity of all the elements,
along with their exact molar rest mass-energies and
quantum wavefunctions can be described with Tetryonic geometries

Ionisation energies

γ


Un-named series
Humphries series
Pfund series
Brackett series
Paschen series
Balmer series
Lyman series
Spectral Lines

$$\boxed{Mv^2 = \text{KEM} = hcR_H}$$

Photon emission/absorption

Spectral line differentials

$$\Delta hv = \Delta Mv = \Delta p$$

changes to energy momenta

accelerate photo-electrons

$$\frac{1}{\lambda} = \frac{R_H}{hc}\left(\frac{1}{n_1^2} - \frac{1}{n_2^2}\right)$$

Ryberg's formula is
a mathematical description
of Tetryonic energy geometry


v
p
KE
ε0
M
hv
v²
3

& produces spectral lines

Δhf


v
c
bosons
KE
R
1 3 5 7 9 11 13 15
1² 2² 3² 4² 5² 6² 7² 8²
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64
absorption
$\frac{n_i^2}{n_f^2}$
$\frac{n_f^2}{n_i^2}$
emission
3/4
5/9
8/9
7/16
12/16
15/16
9/25
16/25
21/25
24/25
11/36
20/36
27/36
32/36
35/36
13/49
24/49
33/49
40/49
45/49
48/49
15/64
28/64
39/64
48/64
55/64
60/64
63/64
Un-named
Humphries
Pfund
Brackett
Paschen
Balmer
Lyman

Fractional energy level transitions

Photo-electrons

Ryberg's constant reflects the changing
energy momentum of a transitioning electron

$$Mv^2 = KEM = hcR$$

*All of the transitions of photo-electrons
bound to Hydrogen atoms can now be
revealed in the fractional geometry
of KEM field energies*

KEM field energies

Fermat's method of Factoring

also known as 'the difference of two squares' is used to factorise large numbers


1
1
1
3
4
1
3
5
9
1
3
5
7
16



$[x-y].[x+y]$

$x^2 - y^2$

All
spectral
lines transitions
are an example of

Fermat's
difference of two squares
in action at the quantum level

leading in turn to Ryberg's formula


1
3
5
7
9
25
1
3
5
7
9
11
36
1
3
5
7
9
11
13
49
1
3
5
7
9
11
13
15
64

Fermat knew that every odd number could be written as the difference of two squares
or as revealed geometrically through Tetryonic theory's equilateral geometry,
every 'SQUARE' number is the sequential sum of ODD numbers

Fractions

A fraction is a number that shows how many equal parts there are

In quantum mechanics fractions appear in quantum steps
as a result of the equilateral geometry of Planck energy momenta

3/4



24/25





40/49



48/64

80/81

.987654321


v
n²
hv
n²
R
R
1
2 3 4
5 6 3 8 9
4 10 11 12 14 15 16
5 17 18 19 20 22 23 24 25
6 26 27 28 29 30 32 33 34 35 36
7 37 38 39 40 41 42 44 45 46 47 48 49
8 50 51 52 53 54 55 56 58 59 60 61 62 63 64
9 65 66 67 68 69 70 71 72 74 75 76 77 78 79 80 81

$$\frac{1}{\lambda} = R\left(\frac{1}{1} - \frac{1}{81}\right)$$

.987654321

Cos 60

.5

1/2

Sin 60

.866025403

$\sqrt{3}/2$

Tetryonic geometry explains the fractional mathematics of Rydberg's formula

Lyman spectral transitions

$$\Delta h\nu = \text{KEM} = hcR$$

Planck
13.525 eV
Rydberg


n1 8
756
η
R
768
7 quantum level jump
n1 7
576
ζ
R
588
6 quantum level jump
n1 6
420
ε
R
432
5 quantum level jump
n1 5
288
δ
R
300
4 quantum level jump
n1 4
180
γ
R
192
3 quantum level jump
n1 3
96
β
R
108
2 quantum level jump
n1 2
36
α
R
48
1 quantum level jump



Emission

768

180 15 [n1-8] 756 [n8-1] 15

+ − 588

156 13 [n1-7] 576 [n7-1] 13

+ − 432

132 11 [n1-6] 420 [n6-1] 11

+ − 300

108 9 [n1-5] 288 [n5-1] 9

+ − 192

84 7 [n1-4] 180 [n4-1] 7

+ − 108

60 5 [n1-3] 96 [n3-1] 5

+ − 48

36 3 [n1-2] 36 [n2-1] 3

12

Absorption

		λ (nm)	$\tilde{\nu}$ (m-1)	f (Hz)	E (eV)	Ω (m²/s)	
63/64	.9843	93.17075598	10,732,981.5	$3.217666905 \times 10^{15}$	13.31395504	27.93188995	$R\left(\frac{1}{1}-\frac{1}{64}\right)$ .984375
48/49	.9795	93.62569132	10,680,829.01	$3.202031983 \times 10^{15}$	13.24926138	28.06822613	$R\left(\frac{1}{1}-\frac{1}{49}\right)$ .9795
35/36	.9722	94.33539043	10,600,475.55	$3.177942622 \times 10^{15}$	13.14958523	28.28103857	$R\left(\frac{1}{1}-\frac{1}{36}\right)$ .9722
24/25	.9600	95.53641971	10,467,212.43	$3.137991343 \times 10^{15}$	12.98427616	28.64109809	$R\left(\frac{1}{1}-\frac{1}{25}\right)$ .96
15/16	.9375	97.82929378	10,221,5587.14	$3.064444671 \times 10^{15}$	12.67995718	29.32848443	$R\left(\frac{1}{1}-\frac{1}{16}\right)$ .9375
8/9	.8888	103.1793333	9,691,863.362	$2.90554754 \times 10^{15}$	12.02247792	30.93238594	$R\left(\frac{1}{1}-\frac{1}{9}\right)$ .888
3/4	.7500	122.2866172	8,177,509.712	$2.451555737 \times 10^{15}$	10.14396575	36.60060556	$R\left(\frac{1}{1}-\frac{1}{4}\right)$ .75

$$\Delta M v^2$$

Balmer spectral transitions

$\Delta h\nu$ = KEM = hcR

Planck · 3.381 eV · Rydberg

720

768

6 quantum level jump

540

588

5 quantum level jump

384

432

4 quantum level jump

252

300

3 quantum level jump

144

192

2 quantum level jump

60

108

1 quantum level jump



Emission

						768
180	15	[n2-8]	720	[n8-2]	15	
		+		−		588
156	13	[n2-7]	540	[n7-2]	13	
		+		−		432
132	11	[n2-6]	384	[n6-2]	11	
		+		−		300
108	9	[n2-5]	252	[n5-2]	9	
		+		−		192
84	7	[n2-4]	144	[n4-2]	7	
		+		−		108
60	5	[n2-3]	60	[n3-2]	5	
		+		−		48

Absorption

768	60/64 .2343	λ 391.3171751 nm	ṽ 2,555,471.1785 m-1	f 7.661111677 x 10^{14} Hz	E 3.169989296 eV	Ω 103.1079531 m^2/s	$R\left(\frac{1}{4}-\frac{1}{64}\right)$ .2343
588	45/49 .2295	λ 399.4696163 nm	ṽ 2,5033,319.299 m-1	f 7.50476246 x 10^{14} Hz	E 3.105295637 eV	Ω 101.0037092 m^2/s	$R\left(\frac{1}{4}-\frac{1}{49}\right)$ .2295
432	32/36 .2222	λ 412.7173331 nm	ṽ 2,422,965.84 m-1	f 7.26386885 x 10^{14} Hz	E 3.00561948 eV	Ω 97.76161483 m^2/s	$R\left(\frac{1}{4}-\frac{1}{36}\right)$ .2222
300	21/25 .2100	λ 436.7379187 nm	ṽ 2,289,702.719 m-1	f 6.864356063 x 10^{14} Hz	E 2.840310409 eV	Ω 92.38472601 m^2/s	$R\left(\frac{1}{4}-\frac{1}{25}\right)$ .21
192	12/16 .1875	λ 489.1464689 nm	ṽ 2,044,377.428 m-1	f 6.128889342 x 10^{14} Hz	E 2.535991437 eV	Ω 82.48636251 m^2/s	$R\left(\frac{1}{4}-\frac{1}{16}\right)$ .1875
108	5/9 .138	λ 660.347733 nm	ṽ 1,514,353.65 m-1	f 4.539918031 x 10^{14} Hz	E 1.878512175 eV	Ω 61.10100927 m^2/s	$R\left(\frac{1}{4}-\frac{1}{9}\right)$ .138

ΔMv^2

Copyright ABRAHAM [2008] - All rights reserved

Paschen spectral transitions

$$\Delta h\nu = \text{KEM} = hcR$$

Planck

1.502 eV

Rydberg

660

768

5 quantum level jump

480

588

4 quantum level jump

324

432

3 quantum level jump

192

300

2 quantum level jump

84

192

1 quantum level jump



Emission
768
180
15
[n3-8]
660
[n8-3]
15
+
-
588
156
13
[n3-7]
480
[n7-3]
13
+
-
432
132
11
[n3-6]
324
[n6-3]
11
+
-
300
108
9
[n3-5]
192
[n5-3]
9
+
-
192
84
7
[n3-4]
84
[n4-3]
7
+
-
108
Absorption

55/64

.0954

λ	960.5057935	nm
$\tilde{\nu}$	1,041,118.135	m-1
f	$3.121193646 \times 10^{14}$	Hz
E	**1.29147712**	**eV**
Ω	287.9523928	m^2/s

$R\left(\frac{1}{9}-\frac{1}{64}\right)$

.09548

40/49

.0907

λ	1,011.157466	nm
$\tilde{\nu}$	988,965.6492	m-1
f	$2.9464844428 \times 10^{14}$	Hz
E	**1.226783461**	**eV**
Ω	303.1373822	m^2/s

$R\left(\frac{1}{9}-\frac{1}{49}\right)$

.0907

27/36

.8033

λ	1,100.579555	nm
$\tilde{\nu}$	908,612.1902	m-1
f	$2.723950819 \times 10^{14}$	Hz
E	**1.127107305**	**eV**
Ω	329.94545	m^2/s

$R\left(\frac{1}{9}-\frac{1}{36}\right)$

.0833

16/25

.0711

λ	1,289.741666	nm
$\tilde{\nu}$	775,349.069	m-1
f	$2.324438032 \times 10^{14}$	Hz
E	**0.961798233**	**eV**
Ω	386.6548243	m^2/s

$R\left(\frac{1}{9}-\frac{1}{25}\right)$

.0711

7/16

.0486

λ	1,886.707809	nm
$\tilde{\nu}$	530,023.7776	m-1
f	$1.588971311 \times 10^{14}$	Hz
E	**0.657479261**	**eV**
Ω	365.6207715	m^2/s

$R\left(\frac{1}{9}-\frac{1}{16}\right)$

.0486

$\Delta M v^2$

Brackett spectral transitions

$$\Delta h\nu = \mathrm{KEM} = hcR$$

Planck — 0.8451 eV — Rydberg



576
768
4 quantum level jump

396
588
3 quantum level jump

240
432
2 quantum level jump

108
300
1 quantum level jump



Emission

768

180 15 [n4-8] 576 [n8-4] 15

588

156 13 [n4-7] 396 [n7-4] 13

432

132 11 [n4-6] 240 [n6-4] 11

300

108 9 [n4-5] 108 [n5-4] 9

192

Absorption

48/64
.0468

λ	1,956.585876	nm
ṽ	511,094.357	m-1
f	1.532222335 x 10 ^{14}	Hz
E	**0.634001085**	**eV**
Ω	586.569689	m²/s

$R\left(\frac{1}{16}-\frac{1}{64}\right)$
.0468

33/49
.04209

λ	2,178.92518	nm
ṽ	458,941.8716	m-1
f	1.375873118 x 10 ^{14}	Hz
E	**0.569307096**	**eV**
Ω	653.2253354	m²/s

$R\left(\frac{1}{16}-\frac{1}{49}\right)$
.04209

20/36
.0347

λ	2,641.390932	nm
ṽ	378,588.4126	m-1
f	1.134979508 x 10 ^{14}	Hz
E	**0.469630433**	**eV**
Ω	791.8690801	m²/s

$R\left(\frac{1}{16}-\frac{1}{36}\right)$
.0347

9/25
.0225

λ	4,076.220574	nm
ṽ	245,325.2914	m-1
f	7.35466721x 10 ^{13}	Hz
E	**0.30432052**	**eV**
Ω	1,222.020185	m²/s

$R\left(\frac{1}{16}-\frac{1}{25}\right)$
.0225

ΔMv^2

Copyright ABRAHAM [2008] - All rights reserved

Pfund spectral transitions

$$\Delta h\nu \;=\; \mathrm{KEM} \;=\; hcR$$

Planck — 0.541 eV — Rydberg



n5~8
γ
468
768
3 quantum level jump
n5~7
β
288
588
2 quantum level jump
n5~6
α
132
432
1 quantum level jump



Emission
768
180
15
[n5-8]
468
[n8-5]
15
588
156
13
[n5-7]
288
[n7-5]
13
432
132
11
[n5-6]
132
[n6-5]
11
300
Absorption

39/64
.0243

λ	3,762.665146	nm
$\tilde{\nu}$	265,769.0656	m-1
f	7.967556145 x 10^{13}	Hz
E	**0.329678886**	**eV**
Ω	1,128.018633	m^2/s

$$R\left(\frac{1}{25}-\frac{1}{64}\right)$$
.0243

24/49
.0195

λ	4,681.284566	nm
$\tilde{\nu}$	213,616.5802	m-1
f	6.404063965 x 10^{13}	Hz
E	**0.264985227**	**eV**
Ω	1,403.413807	m^2/s

$$R\left(\frac{1}{25}-\frac{1}{49}\right)$$
.01959

11/36
.0122

λ	7,503.951512	nm
$\tilde{\nu}$	133,263.1212	m-1
f	3.995127867 x 10^{13}	Hz
E	**0.165309071**	**eV**
Ω	2,249.628068	m^2/s

$$R\left(\frac{1}{25}-\frac{1}{36}\right)$$
.0122

$$\Delta M v^2$$

Copyright ABRAHAM [2008] - All rights reserved

Humphreys spectral transitions

$\Delta h\nu$ = KEM = hcR

Planck 0.375 eV Rydberg

588

1 quantum level jump

768

2 quantum level jump


Emission
768
588
432
180
15
[n6-8]
336
[n8-6]
15
+
−
156
13
[n6-7]
156
[n7-6]
13
+
−
Absorption

28/64

.01215

λ	7,546.831235	nm
ṽ	132,505.9444	m-1
ƒ	3.972428277 x 10^{13}	Hz
E	**0.164369815**	**eV**
Ω	1,128.018633	m^2/s

$R\left(\frac{1}{36}-\frac{1}{64}\right)$

.01215

13/49

.00733

λ	12,445.01497	nm
ṽ	80,353.459	m-1
ƒ	2.4089936098x 10^{13}	Hz
E	**0.099676156**	**eV**
Ω	1,403.413807	m^2/s

$R\left(\frac{1}{36}-\frac{1}{49}\right)$

.0073

$\Delta M v^2$

Copyright ABRAHAM [2008] - All rights reserved

Un-named spectral transition

$\Delta h\nu$ = KEM = hcR

Planck — 0.276 eV — Rydberg

$\Delta\nu$ $\Sigma\nu$ Mv^2


n7~8
α
180
768
1 quantum level jump


Emission
768
180
15
p
[n7-8]
180
[n8-5]
15
d
+
-
588
Absorption

15/64
.0047

λ	19,174.54158	nm
$\tilde{\nu}$	52,152.48541	m-1
f	$1.563492179 \times 10^{13}$	Hz
E	**0.064693658**	**eV**
Ω	5,748.382952	m^2/s

$R\left(\frac{1}{49} - \frac{1}{64}\right)$

.0047

ΔMv^2

Quantum Electrodynamics

Δhv

quantum energy momenta differentials


emission
absorption
[n-u]
0
Schrödinger's wavefunctions
Rydberg's constant & wavenumbers
R
R
bound
photo-electrons
μ
KE
η
v²
hv
180
156
132
108
84
60
36
12
48
108
192
300
432
588
768
972
p
2
3
4
5
6
7
8
n
quantised Planck mass-energy momenta
α
β
γ
δ
ε
ζ
η
Velocity
v
KEM
Energies
v²
1.2e20
Spectral
Lines
M
12
[φ-12]
hv
Spectral
line transitions
v
Δv
Σv
12
36
3
2
2²
36
60
5
3
3²
96
84
7
4
4²
180
108
9
5
5²
288
132
11
6
6²
420
156
13
7
7²
576
180
15
8
8²
756
hv
v
c
v²
Mv²
KEM
48
108
192
300
432
588
768

Spectral lines

Lyman

Balmer

Paschen

Brackett

Pfund

Humphries

un-named

Photo-electrons

hv, R, β, p, KE
Planck, Rydberg, Lorentz, Newton, Leibniz

uniting classical physics and relativity
through equilateral geometry

$$\Delta hv = \Delta Mv = \Delta p$$

all spectral lines are produced by accelerating photo-electrons

the charged geometry of mass-ENERGY-Matter
in motion

Tetryonics 96.11 - Atomic spectral series transitions

Copyright ABRAHAM [2008] - All rights reserved



ninths



eigteenths



Eighteenths



Twenty-fourths



Fractionals and fractals

White light
[EM radiation]
is comprised of many
superpositioned
frequencies



Fractal antennas
are tuned to specific
wavelength-frequencies
to match the equilateral
geometry of photons



Sizteenths



Twenty-sevenths



Twenty-sevenths



Thirty-seconds

Polygons and Angles


rev
0
1
1/8
1/4
3/8
1/2
5/8
3/4
7/8
deg
0°
360°
45°
90°
135°
180°
225°
270°
315°
rad
0
2π
π/4
π/2
3π/4
π
5π/4
3π/2
7π/4

polygon exterior and interior angles


rev
1/6
1/3
1/4
1/4
3/10
1/5
1/3
1/6
deg
60°
120°
90°
90°
144°
72°
120°
60°
rad
π/3
2π/3
π/2
π/2
3π/5
2π/5
2π/3
π/3

dividing the circle


rev
1/3
1/4
1/5
1/6
1/8
deg
120°
90°
72°
60°
45°
rad
2π/3
π/2
2π/5
π/3
π/4

supplementary angles

complementary angles

triangles


rev
3/8
1/8
sum = 1/2 rev
1/6
1/12
sum = 1/4 rev
1/8
1/4
1/8
1/6
1/4
1/12
sum = 1/2 rev
deg
135°
45°
sum = 180°
60°
30°
sum = 90°
45°
90°
45°
60°
90°
30°
sum = 180°
rad
3π/4
π/4
sum = π rad
π/3
π/6
sum = π/2 rad
π/4
π/2
π/4
π/3
π/2
π/6
sum = π rad

Copyright ABRAHAM [2008] - All rights reserved

Pi vs Tau


π
bosons
180°
τ/2
π/3
π/3
π/2
π/3
60°
60°
90°
60°
τ/6
τ/6
τ/4
τ/6
2π
360°
photons
τ

Copyright ABRAHAM [2008] - All rights reserved

Triangular dissection of an equilateral triangle

is a way of dividing up a original triangle into smaller equilateral triangles,
such that none of the smaller triangles overlap











lowest order perfect equilateral triangle dissected by equilateral triangles





lowest order perfect dissected equilateral triangle, an isomer of the first

Golden mean Spirals

Golden Mean Spiral – This spiral is derived via the golden rectangle, a unique rectangle which has the golden ratio.
This form is found everywhere in nature: the Nautilus Shell, the face of a Sunflower, fingerprints, our DNA, and the shape of the Milky Way

Golden spiral



$0,\ 1,\ 1,\ 2,\ 3,\ 5,\ 8,\ 13,\ 21,\ 34,\ 55,\ 89,\ 144,\ \ldots$



Golden spirals







Continued fractions and the Fibonacci sequence

The convergence of the continued fractions

$$1+\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\ldots$$

are:

$$\frac{2}{1},\ \frac{3}{2},\ \frac{5}{3},\ \frac{8}{5},\ \frac{13}{8},\ \frac{21}{13},\ \frac{34}{21},\ \frac{55}{34},\ \frac{89}{55},\ \frac{144}{89},\ \frac{233}{144},\ \frac{377}{233},\ \frac{610}{377},$$

The Golden Ratio (Golden Mean, Golden Section)
is defined mathematically as:

$$\varphi=\frac{1+\sqrt{5}}{2}=1.6180339887\ldots.$$

Koch fractal Curve

Niels Fabian Helge von Koch (January 25, 1870 – March 11, 1924) was a Swedish mathematician
who gave his name to one of the earliest fractal curves ever known

He described the Koch curve, or Koch snowflakes as it popularly known, in a 1904 paper entitled
“On a continuous curve without tangents constructible from elementary geometry”

Von Koch wrote several papers on number theory .
One of his results was a 1901 theorem proving that
the Riemann hypothesis is equivalent to a strengthened
form of the prime number theorem.

Three Koch curves form the snowflake.



The Koch snowflake (or Koch star) is a mathematical curve
and one of the earliest fractal curves to have been described.

Actually Koch described what is now known as the Koch curve,
which is the same as the now popular snowflake, except it starts
with a line segment instead of an equilateral triangle.



$$a = \frac{1}{2} + \frac{i}{\sqrt{12}}$$

The Koch curve is a special case of the Cesaro curve where:



which is in turn a special case of the de Rham curve.





vesica piscis

$$\frac{1351}{780} > \sqrt{3} > \frac{265}{153}.$$

Koch snowflake



space-time

star tetrahedron



Flower of Life



The Flower of Life is a name for a geometrical figure composed of multiple evenly-spaced, overlapping circles.

Copyright ABRAHAM [2008] - All rights reserved

Unit circles - SINE WAVES - Photons



Classic model of a photon

Maxwell's Equations

$$\nabla \times \vec{E} = -\frac{\partial \vec{B}}{\partial t}$$

$$\nabla \cdot \vec{D} = \rho$$

$$\nabla \times \vec{H} = \frac{\partial \vec{D}}{\partial t} + \vec{J}$$

$$\nabla \cdot \vec{B} = 0$$

electric fields

magnetic fields

Tetryonic model of a photon

Magnetic component
Electric field
Magnetic field
Direction of propagation
Electric component
$e^{i\tau/4}$
$e^{i\tau/3}$
$e^{i\tau/6}$
$e^{i\tau/8}$
$e^{i\tau/12}$
$e^{i\tau/2}$
$e^{i\cdot 0}, e^{i\tau}$
$e^{i\pi} = -1$
$i \equiv \sqrt{-1}$
$e^{i\cdot(3\tau/4)}$
N
N
S
S
v
sin(x)
1
0
−1
1 2 3 4 5 6 7 8 9
x (in decimal radians)
cos(x)
1
0
−1
1 2 3 4 5 6 7 8 9
x (in decimal radians)

Magnetic waveforms are 90 degrees out of phase with Electric waveforms

Copyright ABRAHAM [2008] - All rights reserved

Boson distributions in monochromatic EM waves


1/64 2/64 3/64 4/64 5/64 6/64 7/64 8/64 7/64 6/64 5/64 4/64 3/64 2/64 1/64
hν
v²
μ_0
ε_0
KE
p
boson-photon distribution in KEM field waveform
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1
normal distribution of Planck energy momenta
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1
detected interference pattern produced by quantum distributions
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1
.015 .031 .046 .062 .078 .093 .109 .125 .109 .093 .078 .062 .046 .031 .015

Probability distributions of monochromatic EM waves

Tetryonics 98.02 - Boson distributions in monochromatic EM waves

Wave interference patterns

The double-slit experiment, sometimes called Young's experiment, is a demonstration that matter and energy can display characteristics of both waves and particles, and demonstrates the fundamentally probabilistic nature of quantum mechanical phenomena and Establishes the quantum interference principle known as wave–particle duality.

Matter particles are stopped by the barrier but the [K]EM wave passes through both slits and is diffracted by them producing weaker EM waves that then superposition with each other to produce interference patterns



photo-electron KEM wave photon intensities

It is not the Particle passing through both slits that produces an interference pattern it is the particle's associated K[EM] wave

The Compton frequency of any [K]EM wave is comprised of identical wavelength Photons which can combine to produce interference patterns

Equilateral superpositioned KEM waves produce constructive and destructive interference waves that have historically been interpreted as being circular wavefronts

electrons will be stopped by the material barrier but their associated KEM field energy momenta will be absorbed by the screen and 'tunnel through' the barrier to contribute to the interference pattern

final interference pattern produced will depend on phase relationships of the two super-postioned wavefronts

Any detctor placed after the primary screen will remove energy from the secondaryKEM fields and affect the interference patterns produced

In the basic version of the experiment, a coherent light source such as a laser beam illuminates a thin plate pierced by two parallel slits, and the light passing through the slits is observed on a screen behind the plate. The wave nature of light causes the light waves passing through the two slits to interfere, producing bright and dark bands on the screen — a result that would not be expected if light consisted strictly of particles. However, on the screen, the light is always found to be absorbed as though it were composed of discrete particles or photons.

If one slit is observed for the passage of the electron in order to determine its physical state then the its KEM field wave will be absorbed by the detector resulting in only one wave remaining, enforcing a classical particle outcome

Quantum computing via EM wave super-positioning

BY superpositioning two beams
of EM radiation the resultant 'colours'
will perform quantum level computations
that can be read via the resultant
interference patterns produced

constructive interference

additive in-phase EM waves



In phase

Additive


1/2
1
3/2
2
5/2
3
7/2
4
7/2
3
5/2
2
3/2
1
1/2


+
−
square root
1
2
3
4
5
6
7
8
7
6
5
4
3
2
1
10
12
14
16
square root


1/2
1
3/2
2
5/2
3
7/2
4
7/2
3
5/2
2
3/2
1
1/2

Subtractive

Out of phase



destructive interference

subtractive out-of-phase EM waves

Various basic operations, such as
ADDITION, SUBTRACTION and
SQUARE ROOTS etc
are all easily computed using
EM wave super-positioning

The lines of Force

By utilising the statiscal distribution of equilateral Planck energy momenta quanta in EM waves
Tetryonic theory provides a practical geometric solution to quantum computing problems

q

bosons

P vs. NP

The set of all decision problems for which an algorithm exists which can be carried out by a deterministic Turing machine in polynomial time

the set of all decision problems for which an algorithm exists which can be carried out by a non-deterministic Turing machine in polynomial time

E

photons

An algorithm of time complexity ***O****(n)* is one which increases in time linearly as the "size of the problem" (whatever n stands for) increases.



2n+1
[n-n]
2n-1
POSITIVE numbers
NEGATIVE numbers
ODD numbers
SQUARE numbers
n
n
f
1 2 3 4 5 6 7 8
8 7 6 5 4 3 2 1
1 4 9 16 25 36 49 64
15 13 11 9 7 5 3
3 5 7 9 11 13 15
4 9 16 25 36 49 64
quanta intensities
1/64
2/64
3/64
4/64
5/64
6/64
7/64
8/64
7/64
6/64
5/64
4/64
3/64
2/64
1/64
linear momentum provides square roots of normal distributions of quanta
wave interference parterns provide information about normal distributions of quanta
quantum probabilites
0.0156
0.0312
0.0468
0.0625
0.0781
0.093
0.109
0.125
0.109
0.093
0.0781
0.0625
0.0468
0.0312
0.0156

2^n

n^2

An algorithm of complexity ***O****(2^n)* utlises exponential quanta; increasing n by 1 will double the quanta required

$2n^2$

An algorithm of complexity ***O****(n^2)* utilises quadratic quanta, meaning that if you double n it will use four times as many quanta.

n^o

Unlike Math treatise on P vs Np that require exponential polynomial time ***O****(n^k)* Tetryonic geometry of EM fields utilise exponential energies per second

2*h*v

1 second

hf

By relating p to the number of equilateral wave fields in any EM wave very large [pn^2] data sets can be modelled and processed every second

Copyright ABRAHAM [2008] - All rights reserved

Quantum Cryptography

If the numerical sequences were applied to amplitude modulation
their non-repeating numerical sequences would appear
to be purely random noise

Using Tetryonic geometry
advanced non-repeating cyphers
of any complexity
can be easily developed

The level of encryption can
be easily increased (without limit)
by increasing the dimensions
of the cypher geometry

eg: number of quanta
2D vs 3D geometries


1
A 2 B
C Z 3 Y D
E X A 4 B W F
G V C Z 5 F D U H
I T A B C 6 D E F S J
K Q G H I J 7 K L M N R L
M O P O P Q R 8 S T U V W P N
O N X Y Z J A T 9 P G V S C X M P
Q L R K S J T I U 0 V H W G X F Y E Z

eg: quantum encryption 1024
[38 60 02 64 72 90 50 10 47 05 94 08 48 52 27 26 51 66 01 91 03 20]

I T W A S T H E B E S T O F T
I M E S I T W A S T H E W
O R S T O F T I M E S
A T A L E O F T W
O C I T I E S
C . D I C
K E N S

They can be based on known letter sources
(books, pages of magazines etc)
and can be further encrypted
through rotations, double encrypting
or pictogram substitutions

Copyright ABRAHAM [2008] - All rights reserved

Quantum Computing

The Proton/Neutron geometries of atomic nuclei can be built at the quantum scale
to create an atomic nuclei that can operate as a Opto-memory-transistive computing element,
many elements can then be combined in lattices to create super computers no larger than bacterium

Spin UP

Energy can be gated through individual nuclei
using the centre Baryon as the base transistor element,
in turn effecting the energies of bound photo-electrons

Spin DOWN







Q-bits

photo-electronic transitions can be used to directly recieve
or emit memory states through the absorption and emission
of spectral photons of specific energy momenta

1

0

Scalar mass-energies


v
p
ε0
ENERGY
[mΩv]²
momentum
Bosons
Energy
hv
v²
Photons
c²

Quantum distributions


v
p
Boson
Quantum levels
Scalar
Energies
Planck quanta
[mΩv²]
mass
velocity
hv
v²
Photon
Distributions
c²

EM mass

Planck quanta

$$\frac{n\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

2D mass

EM mass

Planck quanta

$$\frac{n\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity


v
Bosons
Energy
ε_0
m
p
hv
v²
Photons
c²
seconds

Measure of planar energies
in a nπ radiant wave
geometry
[per second]

mass quantum
7.376238634 e-51 kg

ENERGY

ENERGY

$$n\pi\left[\left[m\Omega v^2\right]\right]$$

momenta

Equilateral energy momenta
has a mass equivalence
per unit of Time


v
p
ε_0
E
hv
v²

c² is the radial geometry
created by radiant energy
in 1 second

Planck Constant
6.629432672 e-34 J.s

3D Matter

Matter

Planck quanta

$$\frac{T\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

Measure of mass-energy
in a 4nπ standing wave
topology
[per second squared]


c
Quarks
Baryons
ε_0
M
hv
v²
Leptons
c⁴
seconds squared

Matter quantum
2.9504955454 e-50 kg

Planck's constant - the quantum of Action


E
ε_0
$\hbar$
μ_0
μ_0
N
S

all ideal quantum inductive loops
resist changes to their
energy levels

INERTIAL mass



all equilateral energy momenta
produce square root vector
Forces

quantum of WORK


E
ε_0
$\hbar$
μ_0
μ_0
S
N

Quantised angular momentum is equilateral geometry

The two sides of Planck's Constant

The square root of all Energy is linear momentum

Equilateral energy quanta per second

mass


Δv
a
ε_0
E
Planck
Einstein
μ_0
μ_0
hv
v²
Force
Newton
c²
seconds

Quantised angular momenta per second

time

Copyright ABRAHAM [2008] - All rights reserved

CHARGE

bosons

tetryons

EM fields

quarks

leptons

photons

Baryons


v
p
ε_0
Q
RE
E
m
Ω
μ_0
hv
v^2
c
M
KE
FORCE
c^2

mass geometries

Matter Topologies

Electric fields

Magnetic fields

Law of Attraction

Interaction-at-a-Distance

second

MASS ENERGY MATTER

Tetryonics 99.04 - Charged Planck mass-ENERGY-Matter


E
ε
+
N
S
μ
−
Q
RE
M
KE
v
hv
v²
interaction
gravitation
opposites charges attract
same charges repel
Proton
Neutron

All squared energies have equilateral geometries

2D
radiant
mass-energy
geometries

Energy in all its forms
seeks equilibrium

3D
standing-wave
Matter
topologies

There are NO infinities

only Eternity

Copyright ABRAHAM [2008] - All rights reserved



Clean, limitless Energy

Unlimited resources

The geometric field equation of mass-ENERGY-Matter

$$T\pi\left[\left[\varepsilon_0\mu_0\right]\cdot\left[m\Omega v^2\right]\right]$$

Matter
topology
spatial
impedance
Planck
quanta
mass
velocity

Unifying Science and Religion



Tetryonic Theory

All EM mass, energy momenta & Matter can be measured and geometrised with respect to equilateral Quantised Angular Momenta

charged Planck quanta

$$\overset{\text{Bosons}}{\frac{\text{ODD}\,\pi}{c^2}}\left[\overset{\text{Planck quanta}}{\left[\underset{\text{mass}}{m}\,\Omega\,\underset{\text{velocity}}{v^2}\right]}\right]$$

Total Relativistic energies

$$\overset{\text{ENERGY}}{n\pi}\left[\overset{\text{Planck quanta}}{\left[\underset{\text{mass}}{m}\,\Omega\,\underset{\text{velocity}}{v^2}\right]}\right]$$

Quantum Mechanics

Quantum Cosmology

standing-wave mass-Matter

radiant EM mass-energies

Quantum Chemistry

$$\overset{\text{Matter}}{\frac{T\pi}{c^4}}\left[\overset{\text{Planck quanta}}{\left[\underset{\text{mass}}{m}\,\Omega\,\underset{\text{velocity}}{v^2}\right]}\right]$$

3D standing-wave mass/Matter topologies

Electrodynamics

$$\overset{\text{EM waves}}{\frac{\text{EVEN}\,\pi}{c^2}}\left[\overset{\text{Planck quanta}}{\left[\underset{\text{mass}}{m}\,\Omega\,\underset{\text{velocity}}{v^2}\right]}\right]$$

2D radiant mass-energy geometries

The application of equilateral QAM geometries covers all of the Physical disciplines



Tetryonic Geometrics

The equilateral geometry underpinning the mathematics of Physics

ISBN 978-0-987288-5-5
[Second Edition © 2012]

Abraham

Copyright ABRAHAM [2008] - All rights reserved

TETRYONICS

The equilateral geometry underpinning the mathematics of Physics



Foundational physics Mathematics

Abraham

ISBN 978-0-987288-5-5
[Second Edition © 2012]

Copyright ABRAHAM [2008] - All rights reserved

Geometry and the Theory of Everything

Plato

(c.428-348 BC)



DIFFERENT TYPE OF GEOMETRIES

Zero Curvature
Euclidian geometry

Positive Curvature
Elliptic geometry

Negative Curvature
Hyperbolic geometry

(studied by Omar Khayyam, Girolamo Saccheri, Bernhard Riemann, ...)

Euclid

(c.330-275 BC, fl. c.300 BC)

The Socratic tradition was not particularly congenial to mathematics, as may be gathered from Socrates' inability to convince himself that 1 plus 1 equals 2, but it seems that his student Plato gained an appreciation for mathematics after a series of conversations with his friend Archytas in 388 BC.

One of the things that most caught Plato's imagination was the existence and uniqueness of what are now called the five "Platonic solids".

It's uncertain who first described all five of these shapes - it may have been the early Pythagoreans - but some sources (including Euclid) indicate that Theaetetus (another friend of Plato's) wrote the first complete account of the five regular solids.

Presumably this formed the basis of the constructions of the Platonic solids that constitute the concluding Book XIII of Euclid's Elements.

In any case, Plato was mightily impressed by these five definite shapes that constitute the only perfectly symmetrical arrangements of a set of (non-planar) points in space, and late in life he expounded a complete "theory of everything", in the treatise called Timaeus, based explicitly on these five solids.

Interestingly, almost 2000 years later, Johannes Kepler was similarly fascinated by these five shapes, and developed his own cosmology from them





Tetractys

The Tetractys historically symbolized the four elements
[Earth, Air, Fire, and Water]
and the relationship between Humanity
and the cosmos created by GOD

The Greek Tetractys is a
triangular figure consisting of ten points
arranged in four rows:

one, two, three, and four points in each row,
which is the geometrical representation of the
fourth triangular number.

As a mystical symbol, it was very important to
the secret worship of the Pythagoreans.



Sacred numbers

A



*The Tetractys can be re-organised to represent the
space-time geometries of
all EM mass-ENERGY-Matter*

The tetrad was the name given to
the number four -
in Pythagorean philosophy
there were four seasons
and four elements,
and the number was also associated
with planetary motions and music

As a mystical symbol, it was very important to
the secret worship of the Pythagoreans.



The Cosmos

Ω

The single triangle in the first row represents zero-dimensions (a point)
A vector direction in one-dimension can be represented as a line between any two points
The second row represents a Boson (two-dimensions in a plane defined by a rhombus of three triangles)
The whole figure folded represents three-dimensions (a tetrahedron defined by four apex points)
Photons of ElectroMagnetic mass-Energy quanta are represented by two opposing triangles

The Greek Zodiac






12
Aries
20 March – 19 April
1
Mars
Taurus
19 April – 20 May
2
Mercury
Gemini
20 May – 20 June
Earth
3
Moon
Cancer
20 June – 22 July
4
SUN
Leo
22 July – 22 August
5
Mercury
Virgo
22 August – 22 September
6
Venus
Libra
22 September – 23 October
7
Scorpio
23 October – 21 November
8
Pluto
Sagittarius
21 November – 21 December
Jupiter
9
Capricorn
21 December – 19 January
Saturn
10
Uranus
Aquarius
19 January – 18 February
11
Pisces
18 February – 20 March
Neptune





The Greek Elements

Copyright ABRAHAM [2008] - All rights reserved

Equilateral Triangles

An equilateral triangle is a triangle in which all three sides are equal



Equilateral triangles are symmetrical in many different ways



Any six equilateral triangles joined can make a hexagon.

It is unique in that it is the only polygon
that can be tiled [or divided] and produce
only identical geometries and squares numbers

The equilateral triangle
is eminently suited for
the construction of fractals


v
E
ε_0
Square numbered geometries
μ_0
N
S
μ_0
N
S
μ_0
μ_0
ε_0
ε_0
Equilateral triangles are scalable geometries
ε_0
Fractals
Religious icons
E
μ_0
μ_0
μ_0
μ_0
hv
v²

The
tesselation of
odd numbered
equilateral triangles
creates square numbers

That is,

1
1+3 = 4
1+3+5 = 9
1+3+5+7 = 16
1+3+5+7+9 = 25
1+3+5+7+9+11 = 36
1+3+5+7+9+11+13 = 49
1+3+5+7+7+9+11+13+15 = 64
etc

An equilateral triangle is simply a specific case of a regular polygon with 3 sides

The Pythagorean Theorem

Though attributed to Pythagoras, it is not certain that he was the first person to prove it.

The first clear proof came from Euclid, and it is possible the concept was known
1000 years before Pythoragas by the Babylonians

$$a^2 + b^2 = c^2$$

The square of the hypotenuse of a triangle is equal to the sum of the squares of its sides.

In any right triangle,
the area of the square whose side is the hypotenuse
(the side opposite the right angle) is equal to
the sum of the areas of the squares
whose sides are the two legs
(the two sides that meet at a right angle)

Pythagoras of Samos



about (570 – 495 BC)





In Physics
SQUARED numbers are
EQUILATERAL geometries



Pythagorean Tetractys

Since Greek times
squared numbers
have incorrectly
been identified with
square geometries

Equilateral triangles are also
squared number geometries

The Pythagorean equation is at the core of much of geometry,
its links geometry with algebra,
and is the foundation of trigonometry.

Without it, accurate surveying, mapmaking, and navigation
would be impossible,

but its application to the energy-momenta geometries
of ElectroMagnetic fields and Matter in motion in Physics
is erroneous and must be corrected for science to advance

Copyright ABRAHAM [2008] - All rights reserved

Hexagons

A regular hexagon can be subdivided into six equilateral triangles



Energy geometries

Atomic nuclei geometries



Hexagons can be tiled or tessellated in a regular pattern on a flat two-dimensional plane

Hexagons are the only regular polygon that can be subdivided into another regular polygon



Hexagons are the unique regular polygon such that the distance between the center and each vertex is equal to the length of each side

Six is a highly composite number,
the second-smallest composite number,
and the first perfect number.

That is, 1*2*3=1+2+3=6

An interesting relationship between circular and hexagonal geometry is that hexagonal patterns often appear spontaneously when natural forces are trying to approximate circles



Hexagonal tessellation is topologically identical to the close packing of circles on a plane

Copyright ABRAHAM [2008] - All rights reserved

Platonic Solids

The Pythagoreans knew that there were only five regular convex solids,
the tetrahedon, cube, octahedron, icosohedron and dodecahedron
and each one could be accurately circumscribed by a sphere.

FIRE

4 triangles meet to form
a Tetrahedron

EARTH

6 squares meet to form
a Cube

AIR



8 triangles meet to form
a Octahedron

tetryons **4**

regular deltahedrons

leptons **12**

$$F - E + V = 2$$

faces edges vertexs

8 ***quarks***

regular deltahedrons

20 ***Baryons***

12 pentagons meet to form
a Dodecahedron

THE HEAVENS

Plato

(c.428-348 BC)

The philosopher Plato concluded that they must be the fundamental building blocks
– the atoms – of nature, and assigned to them what he believed to be
the essential elements of the universe.

20 triangles meet to form
a Icosahedron

WATER

Tetryonic Solids

Despite their unique topologies Tetryonic solids are not unlike Platonic solids save that their toplogies are comprised entirely from complex hitherto undescribed **4nπ equilateral Planck mass-energy momenta geometries** that also match the Euler numbers of Platonic solids

+ tetryon



4 faces
6 edges
4 vertices

2

- tetryon

up quark



2

8 faces
12 edges
6 vertices

down quark



mass geometries

4π ***tetryons*** **4π**

regular
deltahedrons

12π ***leptons*** **12π**

Matter topologies

Matter topologies

8π ***quarks*** **12π**

regular
deltahedrons

20π ***Baryons*** **36π**

mass geometries



12 faces
18 edges
8 vertices

neutrino

electron

2



Their equilateral topologies are best described as regular topologic-deltahedrons:

tetra-delta-hedrals	**tetryons**	4π external charge fascia
octa-delta-hedrals	**quarks**	8π external charge fascia
dodeca-delta-hedrals	**leptons**	12π external charge fascia
icoso-delta-hedrals	**Baryons**	20π external charge fascia

note:
Charged mass-energy fascia geometries and edges become "hidden" upon the meshing of delta-hedra to form Matter topologies



Neutron

2

20 faces
30 edges
12 vertices

Proton



Copyright ABRAHAM [2008] - All rights reserved

Euclidean geometry

Euclid

(c.330-275 BC, fl. c.300 BC)

Arguably the most influential Mathematics book ever written is Euclid's 'The Elements'



In all, it contains 465 theorems and proofs, described in a clear, logical and elegant style, and using only a compass and a straight edge.

The Elements - Book 1 - Definition 20

Of the trilateral figures, an equilateral triangle is that which has its three EQUAL sides



Euclid's Elements - Book 1 - Proposition 1
Method of constructing an Equialteral triangle

Euclid's five general axioms were:

Things which are equal to the same thing are equal to each other.

If equals are added to equals, the wholes (sums) are equal.

If equals are subtracted from equals, the remainders (differences) are equal.

Things that coincide with one another are equal to one another.

The whole is greater than the part

Copyright ABRAHAM [2008] - All rights reserved

Archimedes



c. (287 BC – c. 212 BC)

As its definition relates to the circle,
π is found in many formulae in trigonometry and geometry,
especially those concerning circles, ellipses, or spheres.

It is also found in formulae from other branches of science,
such as cosmology, number theory, statistics, fractals,
thermodynamics, mechanics, and electromagnetism

Incorrect identification of Pi [c/d] as opposed to Pi radians
in Physics has led to the inappropriate association
of spherical particles to the physical sciences
whereas equilateral triangles & tetrahedra
form its true geometry

The number π is a mathematical constant that is
the ratio of a circle's circumference to its diameter.



Pi

π is an irrational number
its decimal representation
never ends and never repeats.

$\pi = c/d$

The ratio C/d is constant,
regardless of the circle's size

3.141592654.......

Proof of the fact that C=2πr and how Archimedes proved it



Draw any circle.

Make a point anywhere on the circumference of the [green] circle.

Use that point as the center of a second [blue] circle with the same radius as the green circle.

The edge of the blue circle should touch the center of the green circle.

Draw the line segment connecting the centers of the two circles.

That forms the radius of both of the circles.

Now draw the line connecting the center of the blue circle to where it crosses the green circle
on both sides, and complete the triangles.

You should have two equilateral triangles whose sides are equal to the radius of the green circle

Now extend all of the radius lines so they become diameter lines,
all the way across the circle, and finish drawing all of the triangles to connect them.

You've got six equilateral triangles now, that make an orange hexagon.

So the perimeter of your hexagon is the same as six times the radius of your circle.

But your circumference is a little bigger than the perimeter of your hexagon,
because the shortest distance between two points is always a straight line.

This shows you that the circumference of the blue circle has to be more than 6r,
so if C=2πr then π (pi) has to be a little bigger than 3, which it is.

The more sides we draw on our polygon, the closer we will get to the real value of pi (3.14159 etc.).
Using a polygon with 96 sides, Archimedes was able to calculate that π was a little bigger than 3.1408

Copyright ABRAHAM [2008] - All rights reserved

The Golden Ratio

Two quantities are in the golden ratio (φ) if the ratio of the sum of the quantities to the larger quantity is equal to the ratio of the larger quantity to the smaller one.

The figure to the right illustrates the geometric relationship

[1.61803]



Interior line length [LM]
of the bisector line
is equal to 1/2 the side
of the original triangle [BC]
[AB] or [CA]

Φ

Golden ratio phi

$$\hbar = \frac{h}{2\pi}$$

Tetryonic geometry reveals
the maximum E-field amplitude
of the reduced Planck constant
to be an example of the
Golden ratio in physics

velocity vectors

The height of the triangle [ALM] produced by
the bisecting line is 1/2 the height of the height of [ABC]



Kinetic energies

The area of the E-field permittivity diamond [ALDM]
produced by the golden ratio bisector is 1/2
the area of the original equilateral
Planck energy triangle [ABC]

Planck's constant [h]



$a+b$ is to a as a is to b

An intriguing showing of φ in an equilateral triangle was observed by George Odom, a resident of the Hudson River Psychiatric Center, in the early 1980s



The exterior lines
[My] and [Lx] are
Phi ratios of the
interior line [LM]

Let L and M be the midpoints of the sides
AB and AC of an equilateral triangle ABC

By measurement and
the Intersecting Chords Theorem

$$MX \cdot MY = AM \cdot MC.$$

which is of the form

$$(a + b) \cdot b = a \cdot a.$$

Denoting a/b = x, we see that

$$1 + x = x^2,$$

George Odom

Copyright ABRAHAM [2008] - All rights reserved



The Golden Rhombus

Applying the golden ratio (φ) to quantum scale
electrodynamic geometry we can quickly determine that
the linear momentum and magnetic moment vectors of photons
& EM waves can also be expressed as a golden ratio

vector velocities
vs
magnetic vector

Φ
Golden ratio phi
[1.61803]



magnetic Force
vs
electric Force

photons
of
EM energy

Copyright ABRAHAM [2008] - All rights reserved



The 3 planes of Cartesian co-ordinates


inverse
space
3D space

An equilateral [square] triangle divided into 12 equal semitones


A
v
Z
mass
Energy
2r
Musical Notes
Planetary Orbits
.5r
r
Matter topologies
Conservation Laws
hv
X
Y
v²
B
C

Pythagoras is credited with the discovery that the intervals between harmonious musical notes always have whole number ratios.

An equilateral [square] triangle divided into 6 equal semitones and 6 equal quarter tones

With an Equilateral triangle, draw lines from the center of the circle to each vertex and each midpoint, creating six right triangles, as shown with six different colored triangles.
Each right triangle has a radius of the circle for one leg, and half of a side of the original triangle for another.
Any two right triangles sharing one of the radial lines must therefore be congruent, and that implies that the hypotenuses of the triangles are all equal.
This in turn shows that the six right triangles are all congruent, and so the large triangle they combine to form is equilateral

Copyright ABRAHAM [2008] - All rights reserved

Equilateral Fifths


8
7
6
5
4
3
2
1
Do
Re
Mi
Fa
So
La
Ti
do
B
B flat
C
15:8
9:5
13/1
A
D flat
5:3
12
11
1
16:15
10
2
A flat
8:5
9
CDEFGABC
do re mi fa so la ti do
3
9:8
D
8
4
7
5
3:2
6
6:5
G
E flat
45:32
4:3
5:4
G flat
E
F
1
2
3
4
5
6
7
8
C
B
A
G
F
E
D
C

Musical Notes

2D radiated mass-energies


1
3
5
7
9
11
13
15
17
19
21
23
25
27
29
31
33
35
37
39
41
43
45
47
ODD numbers
1^2
2^2
3^2
4^2
5^2
6^2
7^2
8^2
9^2
10^2
11^2
12^2
13^2
14^2
15^2
16^2
17^2
18^2
19^2
20^2
21^2
22^2
23^2
24^2
SQUARED numbers
hv
v^2
48, 44, 40, 36, 32, 28, 24, 20, 16, 12, 8, 4
1,
4, 8, 12, 16, 20, 24, 28, 32, 36, 40, 44, 48
8
16
24
32
40
48
56
64
72
80
88
96

Equilateral Octaves

Copyright ABRAHAM [2008] - All rights reserved

Ternary Diagrams

Viviani's Theorem implies that lines parallel to the sides of an equilateral triangle
provide (homogeneous/barycentric/areal/trilinear) coordinates for ternary diagrams
for representing three quantities A,B,C whose sum is a constant
(which can be normalized to unity).



Ternary diagrams
should NOT be used
to model EM field
strengths



In a ternary plot, of EM energy
the Electric field [E] and the
Magnetic dipole [N-S]
must renormalise
to 1

A ternary diagram is simply a triangular coordinate system in which the 3 edges correspond to the axes.



Trilinear charts are commonly used for finding the result of mixing three components (such as gases, chemical compounds, soil, color, etc.) that add to 100% of a quantity.

Copyright ABRAHAM [2008] - All rights reserved

Whilst the Pythagorean Theorem boasts a slightly greater economy of terms than the Eutrigon Theorem (Wayne Roberts 2003), the latter contains an important area not included in the former:

the area enclosed or swept out by the three points of the triangle in question

$$ab = a^2 + b^2 - c^2$$

the area of any eutrigon is equal to the combined areas of the equilateral triangles on legs 'a' and 'b', minus the area of the equilateral triangle on its hypotenuse 'c'.

The Pythagorean theorem

$$a^2 + b^2 = c^2$$

The square of the hypotenuse of a triangle is equal to the sum of the squares of its sides.



Since Greek times square numbers have been incorrectly identified with square geometries

Equilateral triangles also form square number geometries

Eutrigons

are an important new class of triangle (mathematically defined by Wayne Roberts), as the analogue of the right-triangle in orthogonal (Cartesian) coordinate geometry

Kepler's Second Law of planetary motion



The orbit of every planet is an ellipse with the Sun at one of the two foci.

A line joining a planet and the Sun sweeps out equal areas during equal intervals of time.

The algebraic form of the Eutrigon Theorem, (like the algebraic form of Pythagoras' Theorem), is proven to be special case of the Cosine Rule...

Tetryonic theory reveals the equilateral [square] energy geometry that reveals the 'harmonics at play' in physical laws such as the second law of Kepler, and in many other phenomena in physics, chemistry, cosmology, biochemistry and number theory thus providing the foundation for the mathematics of quantum mechanics

Copyright ABRAHAM [2008] - All rights reserved

Number theory


Real
Real Algebraic
Rational
Integer
Natural
0
1
2
3
ℕ
−1
−2
−3
ℤ
$^1/_2$
$-^2/_3$
2.25
ℚ
√2
−√3
$\frac{1+\sqrt{5}}{2}$
$\mathbb{A}_\mathbb{R}$
π
e
−2π
Transcen-dental
Irrational
ℝ

The Pythagoreans also established the foundations of number theory, with their investigations of triangular, square and also perfect numbers (numbers that are the sum of their divisors).

They discovered several new properties of square numbers, such as that the square of a number n is equal to the sum of the first n odd numbers (e.g. 1 + 3 + 5 + 7 = 16).



It has only been in recent centuries that mathematics has begun to explore the higher order irrational numbers

Tetryonics takes this investigation to new levels with the identification of equilateral geometries as the foundation of transcendental numbers and the physics of fields and particles in motion



What mathematics has failed to appreciate is the significance application of equilateral geometries to the 'square' numbers of physics and science in general

Copyright ABRAHAM [2008] - All rights reserved



TETRYONICS



COUNTING POLYGONS



SQUARED energies in quantum mechanics are EQUILATERAL geometries



Square

area = s² = [100]

Circles


r= 5.642m
area = pi * r²

= pi *[5.642]^2
= 100


10
10
100 m²
Squared Areas
5.642
13.160
15.197

can be created by a number of planar geometries

For a long time it has been assumed by scientists (and mathematicians)
that circular [and squared] geometries are the geometric foundation of all physics,
leading to a serioulsy flawed model of particles and forces in quantum mechanics

Tetryonic theory now reveals that quantised equilateral angular momenta creates the foundational geometry of all the mass-Energy-Matter & forces of physics


15.197m
s
a = √3/4 * s²

Equilateral

area = $(\frac{1}{2}*b)*h$

Triangles


h = 13.160m
s
15.197m
b

b h
[.5x15.197] x 13.160
= 100

0.987654321

SQUARE ROOTS

80/81


1
1
2
3
4
5
6
7
8
9
•
n
1
3
5
7
9
11
13
15
17
19
1
4
9
16
25
36
49
64
81
100
1/2 1 3/2 2 5/2 3 7/2 4 9/2 5 9/2 4 7/2 3 5/2 2 3/2 1 1/2

ODDS

SQUARES

EVEN DISTRIBUTIONS

Copyright ABRAHAM [2008] - All rights reserved

Integers

The integers (from the Latin integer), literally "untouched", hence "whole"
in Tetryonics it is the basis for the Planck charge quantum

$$2n-1$$

$$[[n]+[n-1]]$$

Triangular numbered geometries are NOT equialteral geometries

0, 1, 3, 6, 10, 15, 21, 28, 36, 45, 55, ...


1
2 3 4
5 6 7 8 9
10 11 12 13 14 15 16
17 18 19 20 21 22 23 24 25
26 27 28 29 30 31 32 33 34 35 36
37 38 39 40 41 42 43 44 45 46 47 48 49
50 51 52 53 54 55 56 57 58 59 60 61 62 63 64
65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81
1 2 3 4 5 6 7 8 9 8 7 6 5 4 3 2 1



$$\sum_{1}^{n}[2n-1]$$

Equilateral geometries form **SQUARE** number geometries

1, 4, 9, 16, 25, 49, 64, 81, 100, 121, 144, ...

Equilateral energy quanta form a normal longitudinal distribution

Viewed as a subset of the real numbers, they are numbers that can be written without a fractional or decimal component

Copyright ABRAHAM [2008] - All rights reserved

ε_0
π
μ_0
μ_0

Bosons are a transverse measure of scalar energy momenta

ODD numbers

An odd number is an integer which is not a multiple of two.

E
μ_0
n
3
μ_0
E
ε_0
ε_0
+
−
N
S
S
N

Quantum

Bosons have ODD number quanta

Quantum Levels

hν


1
1 2 3
1 2 3 4 5
1 2 3 4 5 6 7
1 2 3 4 5 6 7 8 9
1 2 3 4 5 6 7 8 9 10 11
1 2 3 4 5 6 7 8 9 10 11 12 13
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17

1
3
5
7
9
11
13
15
17

An odd number, when divided by two, will result in a fraction

Tau radians

Around the whole outside of a circle,
there are about 6.283 radians - or, Tau radians

3.141592654


π/2
90
2π/3
120
π/3
60
π/4
45
π/6
30
π,180
0,2π
2π
D
270
3π/2


1/4
1/3
1/6
1/8
1/12
1/2
0,1
τ
radians
r
2/3
3/4

6.283185307


τ/4
90
τ/3
120
τ/6
60
τ/8
45
τ/12
30
τ/2
180
τ
0
π
π
270
3/4τ

τ is a more 'natural' radian system for geometric physics than π
Tau = 2π = 360 degree rotation about a point



π

historically defined as the
ratio of a circle's circumference to its DIAMETER
should be redefined in physics to

τ

the ratio of its circumference to its RADIUS

in doing so many of the π/2 terms common to physics
will re automatically rationalised and will better reflect
the Tetryonic geometry of mass-ENERGY-Matter in motion



Photons are a longitudinal measure of scalar energy momenta


E
ε_0
+
2
N
N
S
S
−
μ_0
E

Photons are
EVEN number
quantums

EVEN numbers

An integer that is not an odd number is an even number


1
2 3 4
5 6 7 8 9
10 11 12 13 14 15 16
17 18 19 20 21 22 23 24 25
26 27 28 29 30 31 32 33 34 35 36
37 38 39 40 41 42 43 44 45 46 47 48 49
50 51 52 53 54 55 56 57 58 59 60 61 62 63 64
65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81



EM waves are
comprised of EVEN
numbered quanta

If an even number is divided by two, the result is another whole number

1/2 **1** 3/2 **2** 5/2 **3** 7/2 **4** 9/2 **4** 7/2 **3** 5/2 **2** 3/2 **1** 1/2

If an odd number is divided by two, the result is a fractional number

Triangular numbers

Historically, a triangular number counts quanta that can pack together to form an equilateral triangle

1, 3, 6, 10, 15, 21, 28, 36, 45, 55, ...

this form of geometric counting of same charges over-complicated the simpler physical reality


1
3
5
7
9
11
13
15
ν
odd

$$2\nu - 1$$

$$[\nu] + [\nu - 1]$$

Equilateral chords or quantum levels are ODD numbers

1, 3, 5, 7, 9, 11, 13, 15, 17, 19, 21,....


1 2 3 4 5 6 7 8 9
0 1 2 3 4 5 6 7 8
1
2 1 3
4 2 5 3 6
7 4 8 5 9 6 10
11 7 12 8 13 9 14 10 15
16 11 17 12 18 13 19 14 20 15 21
22 16 23 17 24 18 25 19 26 20 27 21 28
29 22 30 23 31 24 32 25 33 26 34 27 35 28 36
37 29 38 30 39 31 40 32 41 33 42 34 43 35 44 36 45
1/2 1 3/2 2 5/2 3 7/2 4 9/2 4 7/2 3 5/2 2 3/2 1 1/2


n²
1
4
9
16
25
36
49
81

$$\sum_{1}^{n} [2n-1]$$

Equilateral geometries form SQUARE numbered geometries

1, 4, 9, 16, 25, 49, 64, 81, 100, 121, 144, ...

Triangular energy quanta form normal distributions

Squared numbers

A square number, sometimes also called a perfect square,
is the result of an integer multiplied by itself



1
+
3
+
5
+
7
+
9
+
11
+
13
+
15
+
17

Square numbers result from
the summing of consecutive
ODD numbers

ODDS

2n-1

[[n] + [n-1]]


1
2 3 4
5 6 7 8 9
10 11 12 13 14 15 16
17 18 19 20 21 22 23 24 25
26 27 28 29 30 31 32 33 34 35 36
37 38 39 40 41 42 43 44 45 46 47 48 49
50 51 52 53 54 55 56 57 58 59 60 61 62 63 64
65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81
v²

Quantum Energies

$$\sum_{1}^{n} [2n-1]$$

Energy levels have
SQUARE number
quanta

Compton Frequency

In Tetryonics Square numbers produce equilateral geometries

Square roots

A square root of a number is a number that, when it is multiplied by itself (squared) , gives the first number again.



Root of positive one

-*i* and +*i*



Root of negative one

Square roots of negative numbers have a basis in physical reality



They reflect the real non-negative linear momentum of a system

A whole number with a square root that is also a whole number is called a perfect square in Tetryonic theory they are actually equilateral geometries

Real Numbers

In mathematics, a real number is a value that represents a quantity along a continuous line. The real numbers include all the rational numbers,


Quantum levels
n
-n
9
8
7
6
5
4
3
2
1
0
1
2
3
4
5
6
7
8
9
+n
Ψ

Wave probabilities

ONE to ∞^2

Quantum levels

ODD numbers

[2n-1]

1, 3, 5, 7, 9......

SQUARE numbers

the sum of consecutive ODD numbers

1+3+5+7+9+......

Scalar Energies


v
1
2
3
4
5
3
9
7
4
16
9
5
25
11
6
36
13
7
49
15
8
64
17
9
81
n
hv
v²
1 2 3 4 5 6 7 8 9 8 7 6 5 4 3 2 1
[n-1]
N
[n-1]

Linear energy momentum

NORMAL DISTRIBUTION

Tetryonics 82.13 - One to Infinity squared

Copyright ABRAHAM [2008] - All rights reserved

Basic Properties of nested scribed Equilateral Triangles

Given an equilateral triangle of side s

altitude

$\sqrt{3/2}\,S$

3S

perimeter

$\sqrt{3/4}\,S^2$

area



$\sqrt{3/6}\,S$

in-radius

$\sqrt{\pi/12}\,S^2$

in-circle area

circum-radius

$\sqrt{3/3}\,S$

circum-circle area

$\sqrt{\pi/3}\,S^2$

Copyright ABRAHAM [2008] - All rights reserved

Tetryonic [equilateral] geometry





The equilateral triangle exhibits 'square symmetry'
it can always be divided into n^2 [number]
of smaller self-similar parts

**All triangles are
flat euclidean
π radian
geometries
[180°]**





An equilateral triangle is the most symmetrical triangle,
having 3 lines of reflection and rotational symmetry of order 3 about its center

Copyright ABRAHAM [2008] - All rights reserved

CHARGE

Scribed equilateral geometries

reflect space-time's geometric relationship with charged mass-energy

Energy



Energy per spatial unit

mass

$$m = \frac{E}{c^2}$$


v
Inscribed
Triangles
hv
v²
c
c²

The triangle of largest area of all those inscribed in any given circle is equilateral

QAM



QAM per spatial unit

seconds

$$\frac{\Omega}{c^2} = s$$

Copyright ABRAHAM [2008] - All rights reserved

Circumscribed Triangles

reflect Energy's relationship with Time


E
ε_0
+
μ_0
μ_0
N
S

Positive Planck Charge


E
ε_0
–
μ_0
μ_0
S
N

Negative Planck Charge


v
ε_0
Inscribed circles
μ_0
μ_0
hv
v^2

The perimiter of an equilateral triangle is

$$p = 3a$$

The radius of the circumscribed circle is

$$R = \frac{\sqrt{3}}{3}a$$

The equilateral triangle has the smallest area of all those circumscribed around a given circle

Circumscribed circles

By Euler's inequality, the equilateral triangle has the smallest ratio R/r
of the circumradius to the inradius of any triangle: specifically, R/r = 2

The ratio of the area to the square of the perimeter of an equilateral triangle

$$\frac{1}{12\sqrt{3}}$$

The ratio of the area of the incircle to the area of an equilateral triangle

$$\frac{\pi}{3\sqrt{3}}$$


v
ε_0
r
R
Inscribed circle
μ_0
μ_0
hv
v²
circumscribed circle
c²


Bosons
ε_0


Photons
ε_0

Equilateral triangles and Tetrahedrons will scale at exactly the same proportion as Circles and Spheres scribing them

Charged mass-ENERGIES

Charge is the result of quantised angular momenta
[the inscribed circular flux of energy in equilateral geometries]

Time is a measure of changing quantised angular momenta
[the circumscribed spatial co-ordinate of equilateral energy geometries]







It is the equilateral geometry of energy not a classical vector rotation that creates QAM

Scalar EM mass is a measure of equilateral Planck energy per spatial co-ordinate system

m

Charged mass-energies can be described as a vector measure of scalar Energy momenta per unit of time
[inscribed circular fluxes of equilateral energy per circumscribed temporal geometry]

E

Trigometric functions

$$\sin\theta = \frac{\text{opposite}}{\text{hypotenuse}}$$

$$\cos\theta = \frac{\text{adjacent}}{\text{hypotenuse}}$$

$$\tan\theta = \frac{\text{opposite}}{\text{adjacent}}$$


opposite
hypotenuse
θ
adjacent


45°
sin
tan
cos
45°

The most familiar trigonometric functions are the sine, cosine, and tangent.

In the context of the standard unit circle with radius 1,
where a triangle is formed by a ray originating at the origin and
making some angle with the x-axis,

the SINE of the angle gives the length of the y-component (rise) of the triangle,
the COSINE gives the length of the x-component (run), and
the TANGENT function gives the slope
(y-component divided by the x-component)

Standard trigometric functions must be carefully applied to
measurements of equilateral Planck mass-energy geometries
in scribed circular space-time co-ordinate systems


30°
ε0
sqr [3] b
2
2
r
μ0
μ0
60°
a
b

In most cases it is in fact easier to
ignore the trigonomteric functions and math
and simpy draw their related equilateral geometries


Linear momentum
S
O
H
C
A
H
Magnetic vector
T
O
A
Equilateral edge

The roots of scribed equilateral triangles

Scalar equilateral energies map directly onto circular space-time co-ordinates
through their square root linear momentum

r

The ratio of the
circumscribed circle of
an equilateral triangle
to its inscribed circle
is 2:1

d


60°
cosine
tangent
2
b
a
r
sine
d
sqr [3]
30°
v
b
2
60°
v²

0.866 r

The ratio of the
side of an equilateral triangle
to the radius of
its incribed circle
is sqr [3]/2

a

The ratio of the
side of an equilateral triangle
to the radius of
its circumscribed circle
is sqr [3]

1.732 d


scribed circles
r
radius
2:1
diameter
d
Sqr[3]
linear momentum
equilateral triangle
a
equilateral side
2:1
right angle base
b

Equilateral triangles and scribed circles

$$\gamma = \frac{1}{\sqrt{1 - v^2/c^2}} = \frac{1}{\sqrt{1-\beta^2}} = \frac{\mathrm{d}t}{\mathrm{d}\tau}$$

$$\gamma(\beta) = 1 + \frac{1}{2}\beta^2 + \frac{3}{8}\beta^4 + \frac{5}{16}\beta^6 + \frac{35}{128}\beta^8 + \ldots$$

$$L = L'\sqrt{1 - \frac{v^2}{c^2}}$$

$$E_k = \frac{mc^2}{\sqrt{1-(v/c)^2}} - mc^2$$


60°
2r
b
magnetic
2b
E² = p²c² + m0²c⁴
KE
a
r
q
30°
θ
β = v/c
√1-β²
pc
μ0
moment
m0c²
E (=mc²)
φ
K
E = m0c² + K





$$mc^2\left\{\frac{1}{\sqrt{1-v^2/c^2}} - 1\right\}$$

$$p = \frac{m_0 v}{\sqrt{1 - \frac{v^2}{c^2}}} = \gamma m_0 v$$

$$E = \frac{mc^2}{\sqrt{1 - \frac{v^2}{c^2}}}$$

$$\sqrt{1 - \left(\frac{v}{c}\right)^2}$$

All the relativistic relationships historically attributed to circularised energies and modelled through the use of the math of right angled triangles are in fact the result of equilateral, scalar geometries

Copyright ABRAHAM [2008] - All rights reserved

Finite sequences and series have defined first and last terms,

$$\sum a_n = a_0 + a_1 + a_2$$



$$\sum_{n=1}^{\infty} \frac{1}{n^2} = \lim_{n\to+\infty} \left(\frac{1}{1^2} + \frac{1}{2^2} + \cdots + \frac{1}{n^2} \right).$$

whereas infinite sequences and series continue indefinitely

The Basel problem is a famous problem in mathematical analysis with relevance to number theory, first posed by Pietro Mengoli in 1644 and solved by Leonhard Euler in 1735.

$$\frac{1}{1^2} + \frac{1}{2^2} + \frac{1}{3^2} + \frac{1}{4^2} + \frac{1}{5^2} + \ldots = \frac{\pi^2}{6}$$

Tetryonics now provides a geometric solution to visualising and solving the Basel problem

$$\zeta(2) = 1 + \frac{1}{2^2} + \frac{1}{3^2} + \cdots = \frac{\pi^2}{6} \approx 1.645;$$

Tetryonic Infinite Series

is a infinite sequence of square numbers,
the result of adding all those terms together
[or their geometric inverse]



$$\sum_{n\geq 1} \frac{1}{n^2}$$

The entire sum of the series is equal to
twice the size of the radius of the largest inscribed circle
which is equal to the largest circle circumscribing the triangular series.

Copyright ABRAHAM [2008] - All rights reserved

Inverting the Circle

Electric
Permittivity

ε_o

Magnetic
Permeability

μ_o



c^2

2D spatial
co-ordinates

$\frac{1}{c^2}$

ElectroMagnetic
fields

Tetryonics 83.11 - Inverting the Circle

Irrational numbers

an irrational number cannot be represented as a simple fraction.
Irrational numbers are those real numbers that cannot be represented as terminating or repeating decimals

sin(x)=-square root of (3)/2

0.866025403.......


2
$\sqrt{3}$
1
30°
2
2
$\sqrt{3/2}$
60°
1
1
linear momentum
vector forces

Pythagφras' theoreom
and irratiφnal numbers expressed in terms of right-angled triangles in Physics
offer a 'half truth' regarding the equilateral geometry of Energy

Leibniz

Newton



Newton focused his work on linear momentum which he developed into his famous laws of motion

Leibniz introduced the concept of vis viva (living force) which attempted to quantify life force

Newton and Leibniz disagreed about what the world is made of and how its physics shaped our scientific concepts of force, energy, and momentum

Tetryonics reveals the physical relationships they both described mathematically as geometric properties of equilateral Planck energy momenta

$$E=mv^2$$

$$p=mv$$

Geometric Square Roots

In geometrical terms, the square root function maps the area of a square to its side length.



"In mathematics, as in any scientific research, we find two tendencies present. On the one hand, the tendency toward abstraction seeks to crystallize the logical relations inherent in the maze of material that is being studied, and to correlate the material in a systematic and orderly manner. On the other hand, the tendency toward intuitive understanding fosters a more immediate grasp of the objects one studies, a live rapport with them, so to speak, which stresses the concrete meaning of their relations"



"As to geometry, in particular, the abstract tendency has here led to the magnificent systematic theories of Algebraic Geometry, of Riemannian Geometry, and of Topology; these theories make extensive use of abstract reasoning and symbolic calculation in the sense of algebra.

Notwithstanding this, it is still as true today as it ever was that intuitive understanding plays a major role in geometry. And such concrete intuition is of great value not only for the research worker, but also for anyone who wishes to study and appreciate the results of research in geometry"

David Hilbert [Geometry and the Imagination]

Copyright ABRAHAM [2008] - All rights reserved

Square Roots in Physics

In mathematics, a square root of a number a is a number [n] such that [n]2 = x,
or, in other words, a number [n] whose square (the result of multiplying the number by itself, or [n × n]) is x.

Modern calculators use the
Square Root Algorithm
to calculate the value

It is an approximate numerical value



Tetryonics uses the
geometric Square Root
to calculate the value

It is an exact geometric value



$$E = mv^2$$

In classical geometry,
the square root function maps the
area of a square to its side length.

$$p = \sqrt{E}$$



Geometry can easily map irrational numbers



$$p^2 = E$$

In physics,
the square root function maps
ENERGY [E] to momentum [mv]

The Square roots of n

Historically, any number raised to the power of 2 has been modeled using a polygon--the square
That's why we call raising a number to the second power "squaring the number."


1
1
1
2
1
3
4
1
2
1
1
2
3
1
3
5
9
1
2
3
2
1
1
2
3
4
1
3
5
7
16
1
2
3
4
3
2
1


v
1
2
3
4
5
6
7
8
$\sqrt{1}=1$
$\sqrt{4}=2$
$\sqrt{9}=3$
$\sqrt{16}=4$
$\sqrt{25}=5$
$1^2=1$
$2^2=4$
$3^2=9$
$4^2=16$
$5^2=25$

note: scalar linear momentum [mv]

is distinct from vector [v]elocity



[In physics square numbers are in fact equilateral geometries]
The perfect squares are squares of whole numbers.
Here are the first eight perfect squares

The Square root of Negative 1



Positive fields are out of phase with Negative fields



Magnetic fields are out of phase with Electric fields

P
COS
π
SIN
SIN

Euler's Formula

Euler's formula is often considered to be the basis of the complex number system. In deriving this formula, Euler established a relationship between the trigonometric functions, sine and cosine, and e raised to a power

$$e^{ix} = \cos(x) + i\sin(x)$$

a mathematical description of EM-Energy waveforms

Leonhard Euler

(15 April 1707 – 18 September 1783)

$$\sin x = x - \frac{x^3}{3!} + \frac{x^5}{5!} - \dots$$

$$\cos x = 1 - \frac{x^2}{2!} + \frac{x^4}{4!} - \dots$$

$$e^x = 1 + x + \frac{x^2}{2!} + \frac{x^3}{3!} + \frac{x^4}{4!} + \frac{x^5}{5!} + \dots$$

$$\sin x + \cos x = 1 + x - \frac{x^2}{2!} - \frac{x^3}{3!} + \frac{x^4}{4!} + \frac{x^5}{5!} + \dots$$



$$e^{i\pi} = -1$$

$$e^{i\pi} + 1 = 0$$



Geometric means

The geometric mean of two numbers, is the square root of their product

geometric square root
of positive one



geometric square root
of negative one



$$F = k\frac{Q_1 Q_2}{r^2}$$



In physics, the geometric mean of two superpositioned fields produces a vector square root Force



$$F = -G\frac{m_1 m_2}{r^2}$$

It is generally stated that
the geometric mean applies
only to positive numbers.

In Tetryonic geometry
the geometric mean applies
to positive & negative fields.

Superpositioning

When two or more waves traverse the same space,
the net amplitude at each point is the
sum of the amplitudes of the individual waves.



constructive interference

In phase

Additive


1/2
1
3/2
2
5/2
3
7/2
4
7/2
3
5/2
2
3/2
1
1/2


+
1
2
3
4
5
6
7
8
7
6
5
4
3
2
1
10
12
14
16
−


1/2
1
3/2
2
5/2
3
7/2
4
7/2
3
5/2
2
3/2
1
1/2

Subtractive

Out of phase



destructive interference

When two or more waves traverse the same space,
if the summed variation has a smaller amplitude
than the constiuent component variations.

The lines of Force

Tetryonic Multiplication table

A multiplication table is a mathematical grid used to define a multiplication operation and its results



Multiplication Table

	1	2	3	4	5	6	7	8	9	10	11	12
1	1	2	3	4	5	6	7	8	9	10	11	12
2	2	4	6	8	10	12	14	16	18	20	22	24
3	3	6	9	12	15	18	21	24	27	30	33	36
4	4	8	12	16	20	24	28	32	36	40	44	48
5	5	10	15	20	25	30	35	40	45	50	55	60
6	6	12	18	24	30	36	42	48	54	60	66	72
7	7	14	21	28	35	42	49	56	63	70	77	84
8	8	16	24	32	40	48	56	64	72	80	88	96
9	9	18	27	36	45	54	63	72	81	90	99	108
10	10	20	30	40	50	60	70	80	90	100	110	120

Historically Multiplication tables
have been based on Square geometries

In Tetryonics multiplication tables can
also be based on EQUILATERAL geometries


1
1
2
2 4 6
3
3 6 9 12 15
4
4 8 12 16 20 24 28
5
5 10 15 20 25 30 35 40 45
6
6 12 18 24 30 36 42 48 54 60 66
7
7 14 21 28 35 42 49 56 63 70 77 84 91
8
8 16 24 32 40 48 56 64 72 80 88 96 104 112 120
9
9 18 27 36 45 54 63 72 81 90 99 108 117 126 135 144 153
10
10 20 30 40 50 60 70 80 90 100 110 120 130 140 150 160 170 180 190
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19

The integer multiplicitors are colour coded

Rhombic Multiplication Tables

1	2	3	4	5	6	7	8	9	10
2	**4**	6	8	10	12	14	16	18	20
3	6	**9**	12	15	18	21	24	27	30
4	8	12	**16**	20	24	28	32	36	40
5	10	15	20	**25**	30	35	40	45	50
6	12	18	24	30	**36**	42	48	54	60
7	14	21	28	35	42	**49**	56	63	70
8	16	24	32	40	48	56	**64**	72	80
9	18	27	36	45	54	63	72	**81**	90
10	20	30	40	50	60	70	80	90	**100**


1
2
3
4
5
6
7
8
9
10
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19




1 2 3 4 5 6 7 8 9 10
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20
1 2 3 4 5 6 7 8 9 10


1 2 3 4 5 6 7 8 9 10
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20
1 2 3 4 5 6 7 8 9 10

Tetryonics 85.03 - Rhombic multiplication tables

Copyright ABRAHAM [2008] - All rights reserved

Photonic Root Tables

Tetryonic multiplication table can take a number of geometric forms

Square root median



Table read diagonally



1	2	3	4	5	6	7	8	9	10
2	**4**	6	8	10	12	14	16	18	20
3	6	**9**	12	15	18	21	24	27	30
4	8	12	**16**	20	24	28	32	36	40
5	10	15	20	**25**	30	35	40	45	50
6	12	18	24	30	**36**	42	48	54	60
7	14	21	28	35	42	**49**	56	63	70
8	16	24	32	40	48	56	**64**	72	80
9	18	27	36	45	54	63	72	**81**	90
10	20	30	40	50	60	70	80	90	**100**

Integer median



Table read from centre
to outside edge then down


1
1 1
4
2 2
9
3 3
16
4 4
25
5 5

Divide [division] tables

Minus [subtraction] tables



Times [multiplication] tables

Plus [addition] tables


36
6 6
49
7 7
64
8 8
81
9 9
100
10 10

Copyright ABRAHAM [2008] - All rights reserved



1 1 1	2 1 2	3 1 3	4 1 4	5 1 5	6 1 6	7 1 7	8 1 8	9 1 9	10 1 10
2 2 1	4 2 2	6 2 3	8 2 4	10 2 5	12 2 6	14 2 7	16 2 8	18 2 9	20 2 10
3 3 1	6 3 2	9 3 3	12 3 4	15 3 5	18 3 6	21 3 7	24 3 8	27 3 9	30 3 10
4 4 1	8 4 2	12 4 3	16 4 4	20 4 5	24 4 6	28 4 7	32 4 8	36 4 9	40 4 10
5 5 1	10 5 2	15 5 3	20 5 4	25 5 5	30 5 6	35 5 7	40 5 8	45 5 9	50 5 10
6 6 1	12 6 2	18 6 3	24 6 4	30 6 5	36 6 6	42 6 7	48 6 8	54 6 9	60 6 10
7 7 1	14 7 2	21 7 3	28 7 4	35 7 5	42 7 6	49 7 7	56 7 8	63 7 9	70 7 10
8 8 1	16 8 2	24 8 3	32 8 4	40 8 5	48 8 6	56 8 7	64 8 8	72 8 9	80 8 10
9 9 1	18 9 2	27 9 3	36 9 4	45 9 5	54 9 6	63 9 7	72 9 8	81 9 9	90 9 10
10 10 1	20 10 2	30 10 3	40 10 4	50 10 5	60 10 6	70 10 7	80 10 8	90 10 9	100 10 10


1
2 3 4
5 6 7 8 9
2
4 6 8
10 12 14 16 18
tetryons
3
6 9 12
15 18 21 24 27
4
8 12 16
20 24 28 32 36
quarks
5
10 15 20
25 30 35 40 45
leptons
6
12 18 24
30 36 42 48 54
7
14 21 28
35 42 49 56 63
Matter
8
16 24 32
40 48 56 64 72
Neutronium
9
18 27 36
45 54 63 72 81
anti-Matter
10
20 30 40
50 60 70 80 90

Copyright ABRAHAM [2008] - All rights reserved

Irrational Numbers

An irrational number is defined to be any number that is the part of the real number system that cannot be written as a complete ratio of two integers

One well known irrational number is π

Irrational numbers can be easily represented geometrically


Sin π/3
60
v
hv
60
Sin 60
60
v²
.866025403
$\frac{\sqrt{3}}{2}$
c²

Exponentials & Logarithms

e and the Natural Log are inverse functions of each other:

e^x is the amount of continuous GROWTH after a certain amount of time.
Natural Log (ln) is the amount of TIME of continuous growth to reach a certain level

1	0
10	1
100	2
1,000	3

$10{,}000 = 10^4$

$\log(10{,}000) = 4$



e

How much growth after x units of time
(and 100% continuous growth)

$$e^x = \lim_{n\to\infty} (1 + x/n)^n,$$

GROWTH

ln

ln(x) lets us plug in continuous growth
and get the time it would take.

$$\ln(x) = \lim_{n\to\infty} n(x^{1/n} - 1).$$

PERIOD

Copyright ABRAHAM [2008] - All rights reserved

Exponential growth

$$\text{growth} = e = \lim_{n \to \infty}\left(1 + \frac{r}{n}\right)^t$$

e represents the idea that all continually growing systems are scaled versions of a common rate

GEOMETRIC

3.141592654

π

Pi is the ratio between circumference and diameter shared by all circles.

It is a fundamental ratio inherent in all circles and therefore impacts any calculation of circumference, area, volume, and surface areas

Pi radians are equally important and show all quantised equilateral energy geometries are related to their scribed circles



GROWTH

2.718281828

e

e is the base rate of growth shared by all continually growing processes.

e lets you take a simple growth rate (where all the change happens all at once at the end of a period of time - ie quantised growth)

e shows up whenever systems grow exponentially and continuously..... radioactive decay, interest calculations and populations

tetryons

EM fields

quarks

e can be applied to the equilateral energy geometries of physical systems only where the rate of increase is a integer factor of a squared number

leptons

Baryons



Nuclear Energy levels

The emission and absorption of bosons and Photons within sub-atomic nuclei

Increase and decrease in integer amounts according to the charged Tetryonic topologies of the particles involved

Exponential energy levels

Radioactive decays follow exponential curves determined by the Tetryonic topology of the sub-atomic particle families

Proton
Neutron

antiNeutron
antiProton

$36\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$

Baryons

EM Field ElectroMagnetic · Planck quanta · mass · velocity

Baryons
400000
350000
300000
250000
200000
150000
100000
50000
0
Baryonic Energy
Quantum Levels
36v²
12
[24-12]
0
[18-18]
12
[12-24]

Electron
Positron

Neutrino

Up
Down
Strange
Charmed
Top
Bottom

quarks
$12\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$
leptons

EM Field ElectroMagnetic · Planck quanta · mass · velocity

12
[12-0]
Quarks and Leptons
12
[0-12]
140000
120000
100000
80000
60000
40000
20000
0
Leptonic Energy
Quantum Levels
12v²
0
[6-6]
8
[10-2]
4
[4-8]

Positive
Negative
Neutral

$4\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$

tetryons

EM Field ElectroMagnetic · Planck quanta · mass · velocity

Tetryons
45000
40000
35000
30000
25000
20000
15000
10000
5000
0
Tetryonic Energy
Quantum Levels
4v²
4
[4-0]
0
[2-2]
4
[0-4]

Series addition & the Riemann Zeta Function

The second series addition of the Reimann Zeta function is where x=2: (pi^2)/6=1+1/2^2+1/3^2+1/4^2+...
(the sum of the reciprocals of the squares)

$$\zeta(s) = \sum_{n} \frac{1}{n^s}$$

$$\zeta(2) = \frac{1}{1^2} + \frac{1}{2^2} + \frac{1}{3^2} + \frac{1}{4^2} + \cdots = \frac{\pi^2}{6}$$

$$f(n) = 1/n^2$$

$$\sum_{n=1}^{\infty} \frac{1}{n^x}$$



In mathematics, the Riemann zeta function, is a prominent function of great significance in number theory. It is a named after German mathematician Bernhard Riemann. It is so important because of its relation to the distribution of prime numbers. It also has applications in other areas such as physics, probability theory, and applied statistics



The mystery of prime numbers
Question: which natural numbers are prime? how are they distributed among natural numbers?

Primes are basic building blocks for natural numbers:

- any natural number is a product of prime numbers
- a prime number is only divisible by itself and by 1:
  (it cannot be further simplified)

We don't know how to predict where the prime numbers are:

“Prime numbers grow like weeds among the natural numbers, seeming to obey no other law than that of chance but also exhibit stunning regularity" (Don Zagier, number theorist)

Adding the odd numbers in order produces the square numbers

Apart from 2, all primes are odd numbers;
the difference between two consecutive squares being odd,
every prime can be expressed as the difference between two squares

SPECTRAL LINES

Primes can be modelled as Bosons
[ODD number energy momenta geometries]

[2n-1]

KEM ENERGIES

Primes can be expressed as Bosons
[the difference of two squared energies]

$n^2 - [n-1]^2$


0
[1+0] 1 1 1 [1²-0²]
[2+1] 3 2 4 [2²-1²]
[3+2] 5 3 9 [3²-2²]
[3+4] 7 4 16 [4²-3²]
9 5 25
[6+5] 11 6 36 [6²-5²]
[7+6] 13 7 49 [7²-6²]
15 8 64
[9+8] 17 9 81 [9²-8²]
[10+9] 19 10 100 [10²-9²]
21 11 121
[12+11] 23 12 144 [12²-11²]
25 13 169
27 14 196
[15+14] 29 15 225 [15²-14²]
[16+15] 31 16 256 [16²-15²]
33 17 289
35 18 324
[18+19] 37 19 361 [18²-19²]
39 20 400
[21+20] 41 21 441 [21²-20²]
[22+21] 43 22 484 [22²-21²]
45 23 529
[24+23] 47 24 576 [24²-23²]
49 25 625
51 26 676
[27+26] 53 27 729 [27²-27²]
55 28 784
57 29 841
[30+29] 59 30 900 [30²-29²]
[31+30] 61 31 961 [31²-30²]
63 32 1024
65 33 1089
[34+33] 67 34 1156 [34²-33²]
69 35 1225
[36+35] 71 36 1296 [36²-35²]
[37+36] 73 37 1369 [37²-36²]
75 38 1444
77 39 1521
[40+39] 79 40 1600 [40²-39²]
81 41 1681
[42+41] 83 42 1764 [42²-41²]
85 43 1849
87 44 1936
[45+44] 89 45 2025 [45²-44²]
91 46 2116
93 2209
95 48 2304
[49+48] 97 49 2401 [49²-48²]
99 50 2500
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 49 48 47 46 45 44 43 42 41 40 39 38 37 36 35 34 33 32 31 30 29 28 27 26 25 24 23 22 21 20 19 18 17 16 15 14 13 12 11 10 9 8 7 6 5 4 3 2 1

The difference of two squares is $(n+1)^2 - n^2 = (n^2 + 2n + 1) - n^2 = 2n + 1$

[n-1] **all energy quanta create normal distributions** **[n-1]**

Copyright ABRAHAM [2008] - All rights reserved

Prime number Distributions

A twin prime is a prime number that differs from another prime number by two, for example the twin prime pair (41, 43). Sometimes the term twin prime is used for a pair of twin primes; an alternative name for this is prime twin or prime pair.

Twin primes appear despite the general tendency of gaps between adjacent primes to become larger as the numbers themselves get larger due to the prime number theorem (the "average gap" between primes less than n is log(n)).

$$p_2 - p_1 = 2$$

Every twin prime pair except (3, 5) is of the form (6n – 1, 6n + 1)
for some natural number n, and with the exception of n = 1,
n must end in 0, 2, 3, 5, 7, or 8



An isolated prime is a prime number p such that neither p – 2 nor p + 2 is prime
2, 23, 37, 47, 53, 67, 79, 83, 89, 97

What Yitang Zhang just proved is that there are infinitely many pairs of primes that differ by at most 70,000,000. In other words, that the gap between one prime and the next is bounded by 70,000,000 infinitely often—thus, the "bounded gaps" conjecture.

On first glance, this might seem a miraculous phenomenon.
If the primes are tending to be farther and farther apart,
what's causing there to be so many pairs that are close together?

It is the geometry of Numbers themselves that causes a natural geometric convergence

The Digital roots of Prime numbers

The digital root (also repeated digital sum) of a number is the (single digit) value obtained by an iterative process of summing digits, on each iteration using the result from the previous iteration to compute a digit sum.

The process continues until a single-digit number is reached.



1	2	3	4	5	6	7	8	9	10
11	12	13	14	15	16	17	18	19	20
21	22	23	24	25	26	27	28	29	30
31	32	33	34	35	36	37	38	39	40
41	42	43	44	45	46	47	48	49	50
51	52	53	54	55	56	57	58	59	60
61	62	63	64	65	66	67	68	69	70
71	72	73	74	75	76	77	78	79	80
81	82	83	84	85	86	87	88	89	90
91	92	93	94	95	96	97	98	99	100

Copyright ABRAHAM [2008] - All rights reserved

Archimedes is given credit for the first calculus.

Archimedes infinite series

Today's calculus was published by Newton.

1 + 3/4 + 3/16 + 3/64 + 3/256 + 3/1024 + ...

1 + .75 + .1875 + .046875 + .01171875 + ...

$$3\left(\frac{1}{4}+\frac{1}{4^2}+\frac{1}{4^3}+\frac{1}{4^4}+\cdots\right)=1.$$

$$\frac{3}{4}+\frac{3}{4^2}+\frac{3}{4^3}+\frac{3}{4^4}+\cdots=1.$$


1/4
1/16
1/64
1/16
1/256
1/256
1/64
1/256
1/64
1/4
1/16
1/4

Nested convergent infinite series

Summing a convergent infinite series


0
1/256
1/64
1/16
1/4
hv
n²
0
1/4⁵
1/1024
1/1024
1/4⁴
1/256
1/256
1/4³
1/64
1/64
1/4²
1/16
1/16
1/4
1/4
1/4
0
1
hv
n²

$1/4 + 1/4^2 + 1/4^3 + 1/4^4 + 1/4^5 + \ldots\ldots\ldots\ldots$

$$\sum_{n=0}^{\infty} a_n = a_0 + a_1 + a_2 + \cdots$$

$1/2 + 1/2^2 + 1/2^3 + 1/2^4 + 1/2^5 + \ldots\ldots\ldots\ldots$

$$\sum_{n=1}^{\infty} \frac{1}{2^n} = \frac{1}{2} + \frac{1}{4} + \frac{1}{8} + \cdots.$$

ODDS = 2n-1

$$\sum_{1}^{n} 2n-1 = n^2$$

Summing the dissimilar coloured equilateral triangles gives unity

1/3 1/3 1/3

Copyright ABRAHAM [2008] - All rights reserved

1/3 1/3 1/3

Summing the dissimilar coloured equilateral triangles gives unity


4096
4096
4^6
1024
1024
4^5
256
256
4^4
64
64
4^3
4^2
0

$1/4 + 1/4^2 + 1/4^3 + 1/4^4 + 1/4^5 + \ldots\ldots\ldots\ldots$

$$\sum_{n=0}^{\infty} a_n = a_0 + a_1 + a_2 + \cdots$$



$1/2 + 1/2^2 + 1/2^3 + 1/2^4 + 1/2^5 + \ldots\ldots\ldots\ldots$

$$\sum_{n=1}^{\infty} \frac{1}{2^n} = \frac{1}{2} + \frac{1}{4} + \frac{1}{8} + \cdots.$$



Summing a divergent infinite series

Copyright ABRAHAM [2008] - All rights reserved

Pietro Mengoli

(1626 – June 7, 1686)

The Basel Problem

The Basel problem is a famous problem in mathematical analysis with relevance to number theory, first posed by Pietro Mengoli in 1644 and solved by Leonhard Euler in 1735.

$$\zeta(2) = \frac{1}{1^2} + \frac{1}{2^2} + \frac{1}{3^2} + \frac{1}{4^2} + \cdots = \frac{\pi^2}{6} \approx 1.644934$$

Leonhard Euler

(15 April 1707 – 18 Sept 1783)



The Basel problem asks for the precise summation of the reciprocals of the squares of the natural numbers, i.e. the precise sum of the infinite series

$$f(n) = 1/n^2$$



Copyright ABRAHAM [2008] - All rights reserved

Integrals of mass-energy

is a means of finding scalar areas using summation and limits.

The summation of equilateral energy momenta quanta
with respect to their linear vector components

Integration is a micro adding of ***CONTINUOUS*** quantities.

$$\int_{n}^{\infty} f(x)$$

Integration is a special case of summation.

*Integration is defined as the limit of a summation
as the number of elements approches infinity while
a part of their respective value approaches zero.*

Summation is the finite sum of multiple, fixed values.

$$\sum_{n}^{\infty} x$$

Summation is a macro adding of ***DISCRETE*** quantities.



Integrating the energy quanta contained within equilateral charge geometry
gives the variable Force required to acheive changes in motion
[Energy, work, acceleration]



The Integral of the continuous area under the curve
is the summation of an infinte number of disctrete
rectangular measurements made to a specified limit

An integration isn't a simple summation,
but the limit of a sequence of summations

All Planck energies are discrete
equilateral geometries



mass is the surface integral of
EM energy geometries
per unit of time

"The calculus of infinitesimals"

The fundamental theorem of calculus
simply states that the sum of infinitesimal changes in a quantity over time
adds up to the net change in the quantity.

Scalar Energy



$E = mv^2$

Leibniz's vis viva
(Latin for living force)
is mv2,

[2 x kinetic energy]

Much of Newton's work
centred around momentum
and changes to it

[mass.velocity]

vector Force



$F = m[dv/dt]$



Gottfried Wilhelm von Leibniz

(July 1, 1646 – November 14, 1716)

Sir Isaac Newton

(1643-1727)



integral calculus

differential calculus



The founders of calculus thought
of the integral as an infinite sum of
rectangles of infinitesimal width

The fundamental theorem of calculus is a theorem that links
the concept of the integral with the derivative of a function.

In calculus, a branch of mathematics,
the derivative is a measure of how
a function changes as its input changes

Leibniz

scalar energies

linear momentum is the square root vector force of the scalar energy required to do a set amount of work



Energy momentum geometries

$$E = p^2$$

Energy momentum

$$kg\left[\frac{m}{s}\right]^2$$

print out this page

then cut out the 10 Planck energy momenta triangles shown

slice fine lines along the pink linear momentum arrows with a razor blade or similar as highlighted under the Newtonian acceleration curve

Newton

linear momentum

d[mv]/dt = dp/dt = ma




5.9
E
35
4.6
E
21
3.1
E
10
7.2
E
52
6.7
E
45


v
1
2
3
4
7
m
hv
v²
mass is energy per second
c²
seconds


3.1
E
10
4.6
E
21
5.9
E
35
6.7
E
45
7.2
E
52

slide the cut-out triangles into the slots created

rotate the assembled model to show the real force momenta geometry at work

Tetryonics 87.07 - Physically modeling the geometric forces of acceleration in calculus

Copyright ABRAHAM [2008] - All rights reserved

linear momentum is the square root vector force of the scalar energy required to do a set amount of work



p

linear momentum

$\mathrm{kg}\,\frac{\mathrm{m}}{\mathrm{s}}$

print out this page

$d[mv]/dt = dp/dt = ma$



Leibniz

scalar energies

$$E = mv^2$$

mass-energy momenta relationship

square root equilateral energy is linear momentum


v
p
ODD number
bosons
SQUARED
energies
m
Ω
hv
v²
c
normal distribution of energies
F
c²
seconds

Newton

linear momentum

$$F = ma$$

mass is a scalar constant relating Force to acceleration

$$F = m\frac{\Delta v}{\Delta t}$$

Planck quanta and their vector linear momentum lie at 90 degrees to the angle use in the graphs of motion in calculus

Copyright ABRAHAM [2008] - All rights reserved

Differentiation

Differentiation is concerned with things like speeds and accelerations, slopes and curves etc.
These are Rates of Change, they are things that are defined locally.


d.v
1
a
2
3
4
5
6
1²
2²
3²
4²
5²
1
3
5
7
9
hv
v²
F


d.v
a
ε_0
m
ONCE ENERGY IS ADDED TO AN INDUCTIVE LOOP
THE LOOP RESISTS ANY CHANGES
v²
F
time


d.v
1
a
2
3
4
5
6
7
8
1²
2²
3²
4²
5²
6²
7²
1
3
5
7
9
11
13
hv
v²
F

An increase in a force
opposing an object's
vector velocity results in
DECCELERATION

An increase in a force
in line with an object's
vector velocity results in
ACCELERATION

A body in uniform motion unless acted upon by F remains in motion an outside Force

A linear measure of Forces acting on physical systems resulting in changes to distance covered per unit of time

A scalar measure of Forces acting on physical systems resulting in changes to their rate of motion

$$v = \frac{\Delta d}{\Delta t}$$

$$= m/s$$

$$F = ma$$

In physics, the derivative of the displacement of a moving body with respect to time is the velocity of the body, and the derivative of velocity with respect to time is acceleration.

$$\sum \mathbf{F} = \frac{\mathrm{d}\mathbf{p}}{\mathrm{d}t} = m\frac{\mathrm{d}\mathbf{v}}{\mathrm{d}t} + \mathbf{v}\frac{\mathrm{d}m}{\mathrm{d}t}$$

Newton's second law of motion states that the derivative of the momentum of a body equals the force applied to the body.

$$a = \frac{\Delta v}{\Delta t}$$

$$= m/s^2$$

Copyright ABRAHAM [2008] - All rights reserved

Visualising the geometric half-truths of relativistic physics

The source of all the physical relationships of mass-energy momenta and the constants in Physics is the Equilateral Triangle (and all texts must be corrected)



Energy geometries within Physics including Special Relativity with its Lorentz corrections have historically been incorrectly illustrated through the geometry of right angled triangles



F

$$\sum \mathbf{F} = \frac{d\mathbf{P}}{dt} = m\frac{d\mathbf{v}}{dt} = m\mathbf{a}$$

$$\mathbf{F} = m\mathbf{a}\,.$$

Physics is geometry,
one cannot be separated from the other

Equilateral geomtries lead to a intuitive understandings of Physics, Chemistry, Electrodynamics and Gravitation along with all the other apsects of Nature.

$$mv^2 = E = hv^2$$

ENERGY

6.629432673 e-34 J

Planck quanta

$$[m\Omega v^2]$$

mass velocity

7.376238634 e-51 kg

momentum

$$p^2 = mv^2$$



$$E^2 = p^2c^2 + m_0^2c^4$$

Generalizing, we see that the square of the total energy, mass, or distance in spacetime is the sum of the components squared.

We can see an origin of distance in spacetime relating to velocity in pc in which Energy is subject to Lorentz corrections [v/c]

$$E = pc.$$

Additionally, EM mass can be directly related tot the Energy content of a body by the velocity of Energy

$$E = mc^2$$

Copyright ABRAHAM [2008] - All rights reserved

Velocity

In physics, velocity is the measurement of the rate and direction of change in the position of an object.

It is a vector physical quantity; both magnitude and direction are required to define it.

The scalar absolute value (magnitude) of velocity is speed, a quantity that is measured in metres per second (m/s or ms–1) when using the SI (metric) system.

$$\frac{m}{s}$$

Speed is the scalar value of the
Distance traveled per unit of TIme

$$\bar{\mathbf{v}} = \frac{\Delta \mathbf{x}}{\Delta t}.$$

Velocity is the vector value of the
Distance traveled per unit of Time

$$\frac{\vec{m}}{s}$$

Velocity squared is the scalar value of the
Distance traveled per unit of Time squared
(Energy of a given spatial volume)

$$\frac{m^2}{s^2}$$

v Velocity $\frac{m}{s}$

sec

is a 2D
radial Space-time
MEASUREMENT



*All divergent Energy possesses a vector direction
and an associated scalar area
whose energy content is quantised*

Velocity squared

$$\frac{m^2}{s^2}$$

is a 3D
Spherical Space-time
MEASUREMENT



acceleration is a measure of a vector Force acting along a line in a spatial volume

Acceleration

In physics, acceleration is the rate of change of velocity over time [dt]

In one dimension, acceleration is the rate at which something speeds up or slows down.

However, since velocity is a vector, acceleration describes the rate of change of both the magnitude and the direction of velocity.

Acceleration has the dimensions [Length]/[Time Squared]
In SI units, acceleration is measured in meters per second squared (m/s^2).

$$a = \frac{\Delta y}{\Delta x} = \frac{\Delta v}{\Delta t}.$$

In classical mechanics, for a body with constant mass, the acceleration of the body is proportional to the net force acting on it (Newton's second law)

$$F=ma \longrightarrow a=F/m$$

Force

$$kg\,\frac{m}{s^2}$$

Additionally, for a mass with constant velocity,
(ie in an inertial frame)
the energy of motion is expressed as its momentum
(acceleration causes changes in Energy-momentum)

$$p = kg\,\frac{m}{s}$$

Copyright ABRAHAM [2008] - All rights reserved

$kg\frac{m}{s}$ linear momentum **p**



Linear momentum is the vector square root of the mass-energy in any [K]EM field geometry and produces a vector velocity

Momentum

In classical mechanics, momentum (pl. momenta; SI unit kg·m/s, or, equivalently, N·s) is the product of the mass and velocity of an object (p).

Like velocity, momentum is a vector quantity, possessing a direction as well as a magnitude.

Momentum is a conserved quantity (law of conservation of linear momentum), meaning that if a closed system is not affected by external forces, its total momentum cannot change.

Momentum should be referred to in its specific forms to distinguish it in its various forms [Quantised Angular, Linear, Rotational and quantum/nuclear momentum]

$$\boxed{p = \frac{hv^2}{v} = mv}$$

Although originally expressed in Newton's Second Law, the conservation of momentum also holds in special relativity and, with appropriate definitions, a (generalized) momentum conservation law holds in electrodynamics, quantum mechanics, quantum field theory, and general relativity.

In relativistic mechanics, non-relativistic momentum is further multiplied by the Lorentz factor.

$$p^2 = E = mv^2$$

Energy can be expressed as the square of linear momentum

$$kg\frac{m^2}{s^2}$$

equilateral Planck energy momenta

$$m\Omega v^2$$

Copyright ABRAHAM [2008] - All rights reserved

Energy-momentum relationship

The total number of equilateral Planck quanta [quantised mass-energy momenta]
is directly related to the square of its linear momentum [mass-velocity]

Quantum Mechanics

$$h = \frac{E}{v^2}$$



Quantised energy equilateral momenta

$$hv^2$$



Quantised Energy momenta is related to
Scalar mass energy momenta through
the equilateral geometry of Planck's constant

Newtonian physics

$$m = \frac{E}{v^2}$$



Scalar energy linear momentum

$$pv$$

$$m\Omega v^2 = E = mv^2$$

Copyright ABRAHAM [2008] - All rights reserved

Inertial resistance to Force

Inertia is the resistance of any physical object
to a change in its state of motion.


v
a
1
2
3
4
5
6
1
3
5
7
9
1²
2²
3²
4²
5²
hv
v²
F

Changes to mass-velocity require a corresponding change to boson quanta


v
Q
[v-v]
p
KE
ε_0
m
μ
μ
second

Changes to mass-velocity produces a change in an object's Kinetic Energies


v
a
1
2
3
4
5
6
7
8
1
3
5
7
9
11
13
1²
2²
3²
4²
5²
6²
7²
hv
v²
F

$$E = mc^2$$

The total intrinsic momenta of all energy waveforms is the sum of their constituent Quantised Angular momenta (mass-energy momenta)

$$M_0 = m/c^2$$

$$KEM = Mv^2$$

Matter in motion has Kinetic Energies in addition to invariant rest mass-Energy

KE = RE - rest Matter

Any change in motion results in changes to the Charge geometries creating in turn proportional changes to KEM mass and momenta components

$$F = ma$$

The 'inductive resistance' of Charge quanta fields to changes in their mass-energy momenta content is what we term Inertia


q
[v-v]
v
p
ε_0
I
μ
μ
N
S
v²

quantised moment of inertia

Any change to an object's velocity results in a corresponding change to its mass-Energy momenta which is reflected by its inertia

$$p^2 = E = mv^2$$

Inertial mass can be related to Charge through inductive Planck quanta


v
q
[v-v]
p
ε_0
I
μ
μ
S
N
v²

quantised moment of inertia

Quantised Angular momentum

As it is a physical [equilateral] geometry QAM is conservative in any system where there are no external Forces and serves as the foundational geometric source for all the conservation laws of physics



Angular momentum is sometimes described as the rotational analog of linear momentum, in Tetryonics it is revealed to be the equilateral geometry of quantised mass-energy momenta within any defined space-time co-ordinate system

A major re-definition of quantised angular momentum in physics is revealed



classical rotational angular momentum



Quantised Angular momentum

In quantum mechanics, angular momentum is quantised – that is, it cannot vary continuously, but only in ODD number "quantum steps" between the allowed SQUARE nuclear Energy levels

In physics, angular momentum, moment of momentum, or rotational momentum is a conserved vector quantity that can be used to describe the overall state of a physical system.

When applied to specific mass-Energy-Matter systems QAM reveals the true quantum geometry and nature of Energy in our universe



Planck's Constant

Normally viewed as an expression of rotational momentum Quantised Angular Momentum [QAM] is in fact a result of the equilateral geometric quantization of mass-energy

Copyright ABRAHAM [2008] - All rights reserved

Charged geometries

All charge geometries are nett divergent


Q
[v-v]
1
1
1
2
3
4
3
5
9
4
7
16
5
9
25
6
11
36
7
13
49
8
15
64

Divergent energy momenta	Convergent energy momenta
1	0
3	1
6	3
10	6
15	10
21	15
28	21
36	28

All charge geometries are comprised of finite equilateral energy momenta quanta

Renormalisation

Renormalization was first developed in quantum electrodynamics (QED) to make sense of infinite integrals in perturbation theory.
The problem of infinities first arose in the classical electrodynamics of point particles in the19th and
later in the calculation of Gravitational fields in General Relativity in the early 20th century.

In QED Infinities must be cancelled



The mass of a charged particle should include the mass-energy in its electrostatic field (Electromagnetic mass) which in turn would approach infinity as the electron radius decreases.



In Tetryonics Infinities do not exist



Tetryonics solves the problem by clearly differentiating between EM mass and Matter and using finite equilateral geometries for all Matter in motion

Initially viewed as a suspicious provisional procedure by some of its originators, renormalization was eventually embraced as an important and self-consistent tool in several fields of physics and mathematics.

Copyright ABRAHAM [2008] - All rights reserved

2D space [c^2]

The adjective Cartesian refers to the French mathematician and philosopher René Descartes who developed the coordinate system in 1637

Since then many other coordinate systems have been developed such as the polar coordinates for the plane, and the spherical and cylindrical coordinates for three-dimensional space.



Cartesian coordinates are the foundation of analytic geometry, and provide enlightening geometric interpretations for many other branches of mathematics, such as linear algebra, complex analysis, differential geometry, multivariate calculus, group theory, and more

Mapping 3D spaces using Recti-linear co-ordinates

Cartesian coordinates can be defined as the positions of the perpendicular projections of a point onto the two or more axes, expressed as signed distances from the origin.



3D Cartesian co-ordinate [c^3] systems are distinct from spherical co-ordinate [c^4] systems

Copyright ABRAHAM [2008] - All rights reserved

Polar co-ordinates

In mathematics, the polar coordinate system is a two-dimensional co-ordinate system in which each point on a plane is determined by a distance from a fixed point and an angle from a fixed direction.



In geometry, curvilinear coordinates are a coordinate system for Euclidean space in which the co-ordinate lines may be curved.

Action Dynamics

Curvilinear co-ordinates may be derived from a set of rectilinear Cartesian coordinates by using a locally invertible transformation that maps one point to another in both systems

Metric Tensors



Gravitational acceleration

Polar or curvilinear co-ordinate systems are used extensively by Einstein in his theory of General Relavtivity

Reimannian curved space-time

Co-ordinate transformations

There are many different possible coordinate systems for describing geometrical figures and they can all be related to one another.

Such relations are described by coordinate transformations which give formulas for the coordinates in one system in terms of the coordinates in another system



Converting between Polar and Cartesian coordinates



$$\tan\theta = \frac{\text{opposite}}{\text{adjacent}}$$

$$= \tan^{-1}(5/12)$$

$$= 22.619$$



$$r^2 = 12^2 + 5^2$$

$$= \sqrt{169}$$

$$= 13$$

solving for the triangle using trigometric functions

Copyright ABRAHAM [2008] - All rights reserved

Spatial co-ordinates systems

Cubic



Spacetime is any mathematical co-ordinate system or model that combines space and time into a single continuum.

Spacetime is usually interpreted with space as being three-dimensional with time playing the role of a fourth dimension that is different from the spatial dimensions.

From a Euclidean space perspective, the universe has three spatial dimensions and one dimension of time [reflected by quantised angular momentum].

Spherical



Tetryonics maps spatial co-ordinates through the momenta vectors of equilateral Energy

Cartesian Space-Time





EM mass-ENERGY momenta are equilateral geometries

Mapping equilateral Energy geometries onto recti or curvi-linear spatial co-ordinate systems introduces mathematical complexity to a otherwise simplistic geometry for all EM mass-Energy-Matter interactions

Tetryonic Space-Time



In physics spatial co-ordinates to date have been based on Cartesian co-ordinates when in fact Energy momenta follow a Tri-Linear co-ordinate geometry

vectors

1 Dimensional velocity

Euclidean



2 Dimensions velocity squared

$$m = \frac{E}{c^2}$$

mass-energy equivalence

mass-Matter

$$\frac{m}{c^2} = M$$

equivalence

Cartesian co-ordinates



3 Dimensions velocity cubed

$T_{\mu\nu}$

energy-Matter equivalence

$$M = \frac{E}{c^4}$$

GR fails differentiate betweem EM mass-ENERGY-Matter unlike Tetryonic theory

Spherical



3 Dimensions quadrature velocity

Space-time co-ordinates

The propagation of Energy momenta forms distinct spatial co-ordinate systems

Where angles are typically measured in degrees (°) or radians (rad), where 360° = 2π rad = τ radians.

Tetryonic co-ordinate systems

Energy per second

m



2D mass-energy geometries




z
planar
[x,z]
planar
[y,z]
volumes
[x,y,z]
x
y
[x,y]
planar
time

Planar mass-energy geometries have no z-components

Differentiation between 2D mass-energy & 3D Matter is key to extending our understanding of physics

Matter topologies have z-components

Energy per second squared

M



Proton

3D Matter topologies

Neutron



Copyright ABRAHAM [2008] - All rights reserved


1
1
1
1
1
1
1
2
3
4
1
2
1
1
1
1
2
3
4
5
9
3
1
2
3
2
1
1
1
1
2
3
4
3
4
5
9
7
16
1 2 3 4 3 2 1


v
square roots
ODD
numbers
SQUARE
numbers
Ψ
hv
v^2
1 2 3 4 5 6 ... n ... 6 5 4 3 2 1
normal distributions

Quantum probability distributions

The equilateral geometry and distribution of quantised Energy momenta provides the basis for all statistical probabilities in Quantum mechanics, thermodynamic & information entropy - including a solution to Heisenberg's Uncertainty Principle thus paving the way forward for a new understanding, and manipulation of physical phenomena at the quantum level

1

1 2 1

1 2 3 2 1

1 2 3 4 3 2 1

1 2 3 4 5 4 3 2 1

1 2 3 4 5 6 5 4 3 2 1

1 2 3 4 5 6 7 6 5 4 3 2 1

1 2 3 4 5 6 7 8 7 6 5 4 3 2 1

Normal distributions are extremely important in statistics, and are often used in the natural and social sciences for real-valued random variables whose distributions are not known


1
1
1
2
3
4
3
4
5
9
7
16
9
5
25
1 2 3 4 5 4 3 2 1
1
1
1
2
3
4
5
9
3
4
7
16
9
5
25
11
6
36
1 2 3 4 5 6 5 4 3 2 1
1
1
1
2
3
4
5
9
3
4
7
16
9
25
5
6
11
36
13
7
49
1 2 3 4 5 6 7 6 5 4 3 2 1
1
1
1
2
3
4
5
9
3
4
7
16
9
25
5
6
11
36
13
49
7
8
15
64
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1

Quantum Probability Distributions

The normal distribution is a probability distribution.
It is also called Gaussian distribution because it was discovered by Carl Friedrich Gauss.

x/n^2

Probabilities are the square of the Amplitude

n

$\Sigma\ x/n^2$

All probabilities are re-normalisable and sum to Unity

1

square root momenta

v


1
2
1 1
1 2 3 2 1
1 2 3 4 3 2 1
1 2 3 4 5 4 3 2 1
1 2 3 4 5 6 5 4 3 2 1
1 2 3 4 5 6 7 6 5 4 3 2 1
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1
1 2 3 4 5 6 7 8 9 8 7 6 5 4 3 2 1
1
1 2 3 4 5 6 7 8 9 8 7 6 5 4 3 2 1
[n-1]
[n-1]

ODD transverse Bosons

EVEN Longitudinal Photons

Planck quanta

hv

v^2

Square energies

Normal Distribution

c^2

Quanta Distributions

$$2h\nu = E = hf$$

Quantum Levels

transverse bosons

Quantum Probabilities

longitudinal photons



W+


1
3
5
7
9
11
13
15
15
13
11
9
7
5
3
1
1
2
3
4
5
6
7
8
8
7
6
5
4
3
2
1






4
7
7
3
3
5
5
2
2
3
3
1
1
1
1
γ
1
1
1
1
3
3
2
2
5
5
3
3
3
7
4
1/64
2/64
3/64
4/64
5/64
6/64
7/64
8/64

W−





Copyright ABRAHAM [2008] - All rights reserved

Wavefunctions



Quantum Levels

KEM fields

Transverse Bosons

Longitudinal Photons

Quantised Angular Momenta

ElectroMagnetic Waves

Velocity

Amplitude Probabilities

Linear momentum

Squared energies

Vector Forces

Energy momenta

EM waveforms



All EM waveforms can be measured by either their Transverse EM masses [Bosons] or their Longitudinal EM masses [Photons]

BOSONS

Bosons Planck quanta

$$\frac{\text{ODD}\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

vs.

PHOTONS

EM waves Planck quanta

$$\frac{\text{EVEN}\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity



Longitudinal wave Amplitude
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1
64
Longitudinal Frequency (f)
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1
Transverse wave Amplitude
1 3 5 7 9 11 13 15 15 13 11 9 7 5 3 1
128
Transverse Frequency (v)
1 3 5 7 9 11 13 15 15 13 11 9 7 5 3 1
EM Wavelengths
KE
Wave Amplitude
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1
λ
64
Photon Frequency (f)
Group Phase Velocity
c
c

$$2h\nu = hf$$

Photons are longitudinal quanta

Bosons are transverse quanta

Copyright ABRAHAM [2008] - All rights reserved

Quantum Energy distributions


E = hν
128
ν
Quanta
Transverse Boson quanta
E
Quantum
E = hf
64
f
Longitudinal Photon Frequency
Medium dependent
Group Phase Velocity
v
c
Quantum
Energy
Levels
[n²]
2x8²
n
E = p²
Levels
Bosons
Planck quanta
ODD π / c² [[mΩv²]]
mass velocity
EM waves
Planck quanta
EVEN π / c² [[mΩv²]]
mass velocity
Waveforms
Wavefunction
Ψ
HΨ

Normal Distributions

The Gaussian distribution sometimes informally called the bell curve.

Pierre de Fermat

Pierre de Fermat is given credit for early developments that led to infinitesimal calculus.

$$\frac{1}{\sqrt{2\pi\sigma^2}}\, e^{-\frac{(x-\mu)^2}{2\sigma^2}}$$



$$\frac{1}{2}\left[1+\operatorname{erf}\left(\frac{x-\mu}{\sqrt{2\sigma^2}}\right)\right]$$

Leonhard Euler

Leonhard Euler developed a formula which links complex exponentiation with trigonometric functions

A bell shaped curve defines the standard normal distribution, in which the probability of observing a point is greatest near the average, and declines rapidly as one moves away from the mean.

all ODD numbers are

$$a^2 - b^2 = [a-b].[a+b]$$

the difference of two squares

$$e^{i\pi} = -1$$


v
p
SQUARE roots
Transverse Bosons [ODD numbers]
Scalar Energy EM waves [SQUARE numbers]
hv
v²
n-1
n
n-1

[normal distribution]



$\Pr(x) = \frac{1}{\sqrt{2\pi}} e^{-x^2/2}$

$\Pr(k) = (n!/(n-k)!\,k!)p^{(n-k)}q^k$

$p = q = ½, n = 13$

σ = standard deviation

$\Pr(x) = \frac{1}{\sqrt{2\pi\sigma}} e^{-x^2/2\sigma}$

In the limit of large numbers, the sum of independent random variables will be normally distributed.


-1
odd no. bosons
squared energies
Ω
1
2
3
4
5
6
5
4
3
2
1

longitudinal photon distributions

In probability theory, the normal (or Gaussian) distribution is a continuous probability distribution that has a bell-shaped probability density function, known as the Gaussian function

Copyright ABRAHAM [2008] - All rights reserved

Fundamental theorem of Energy momenta

A nth level scalar energy momenta waveform has exactly n linear momentum in unit circle co-ordinate systems
(with Longitudinal and Transverse equilateral Planck waveforms being orthogonal to each other)

scalar energies

E

mv^2


+1
90°
1/4τ
3π/4
π/4
transverse
frequency
Q
180°
-1
1/2τ
Maxwell
Tesla
Hertz
Q
tau
+1
0°
emf
voltage
Q
5π/4
7π/4
3/4τ
270°
-1

Longitudinal EM waveforms are the waves produced by spark gap discharges

Their energy momenta are co-linear with the wave's direction of propagation

p

mv

linear momentum

Transverse EM waveforms are the waves produced by accelerating charges

Their energy momenta are orthogonal to the direction of wave propagation

[Mathematics] *i or j* *[Electrical theory]*

square root of negative one

Velocity and Time dependent EM fields


n
Ψ
v
1
2
3
4
3
5
9
4
7
16
5
9
25
6
11
36
13
49
15
64
9
17
81
hv
v^2
Matter
$T\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$
topologies
EM Field
ElectroMagnetic mass
velocity
c^2

Quantum levels

Wave probabilities

SQUARE ROOT momenta

EVEN number PHOTONS

ODD number BOSONS

SQUARE number ENERGIES

All EM geometries are comprised of Transverse quantum levels and Longitudinal wave probabilities

Matrices

Matrices are a key tool in linear algebra.
One use of matrices is to represent linear transformations,
which are higher-dimensional analogs of linear functions
of the form f(x) = cx, where c is a constant; matrix multiplication
corresponds to composition of linear transformations.

Further developing equilateral Matrices and tensor mathematics to
reflect the 2D geometry of EM , KEM and GEM quantum fields,
along with the geometric quantisation of mass-energiy momenta
and their energy distributions allows for field interactions
to be accurately visualised and modelled



n1
1
1x1
n2
1
2
1 1
2x2
n3
1
2
1 1
2 2
1 3 1
3x3
n4
1
2
1 1
2 2
1 3 1
2 4 2
1 3 3 1
4x4



v
E
KE
M
M
hv
v²
c²
Positive Fields
v
1
p
2
3
4
6
8
5
3
9
11
4
15
10
12
14
16
18
20
22
24
17
19
5
23
25
27
29
33
35
26
28
30
6
32
34
36
38
40
42
44
46
48
37
39
41
7
45
47
49
51
53
55
8
59
61
63
50
52
54
56
58
60
62
64
v
E
KE
M
M
hv
v²
c²
Negative Fields



n5
5x5
n6
6x6
n7
7x7
n8
8x8

Tensors are geometric entities introduced into mathematics and physics to extend the notion of scalars, geometric vectors, and matrices to increasingly higher orders.

Modifying Square matrices to reflect the equialteral geometries of Tetryonic fields allows for the accurate geometric modelling of all Scalar & Vector fields along with their varied intrinsic quantum energies and physical properties

Copyright ABRAHAM [2008] - All rights reserved

Energy momenta Tensors

momenta
(a property of Energy)
is converative



$$p_M \longrightarrow (E, p1, p2, p3, p4).$$

All standing-wave Matter topologies can be modelled using its Tetryonic charge energy momenta Tensors

with an additional Kinetic EM energy-momenta tensor required for Matter in motion

$$p_{KEM} \longrightarrow (E, p5).$$

Matter
(a geometric property)
is NOT conservative



2D+1 [SR] mass-energy momenta can be folded into 3D+1 [GR] Matter
that can be modelled using 4 Energy-momenta tensors

Positive standing-wave Matter

$$E = \sum_{\text{all fascia}} E$$

Energy of a massive particle is the total of all Planck quanta (compton frequency) in a 3D geometry



$$\vec{p} = \sum_{\text{all fascia}} \vec{p}$$

Total Momentum is the total of all quanta linear Momenta in a 3D particle



Negative standing-wave Matter

Relativistic Matter in motion



$$I = \sum_{\text{all fascia}} I$$

Inertial mass is the total of all inertia in a 3D particle

Photons have null energy-momentum tensors

Note that both 2D mass-energies [Special Relativity] and 3D Matter [General Relativity] have distinct Energy momenta

It is the 3D Tetrahedral topologies that provides a definative basis for Matter

Relativistic Matter in motion



Tetryonic Energy momenta tensors should not be confused with Four vector tensors which map energy-momenta vectors in 3D spatial[cartesian] co-ordinate systems



Relativistic Lorentz correction factor

The Lorentz factor or Lorentz term is an expression which appears in several equations in special relativity
It is often incorrectly graphed [as pictured to the right] as an increasing function of velocity approaching but never reaching c

**'c' is the maximum velocity acheivable through the electrical acceleration of particles
is NOT the maximum velocity possible for Matter in motion**



Linear correction factor

$$\beta = \left[\frac{v}{c}\right]$$



Scalar correction factor

$$\beta^2 = \left[\frac{v^2}{c^2}\right]$$

*Lorentz factors are LINEAR and SCALAR velocity related corrections
to the relativistic mass-energy momenta content of any
physical system accelerated by EM Forces*

$$\frac{\Delta\gamma}{c^2}$$

Wavelength contraction

Time Dilation

$$\frac{\Delta\Omega}{c^2}$$

$$\frac{\Delta mv}{c^2}$$

Relativistic momentum

$$\frac{\Gamma}{c^2}$$

Lorentz corrections

Relativistic mass-energy

$$\frac{\Delta h\nu}{c^2}$$


v
Bosons
Energy
E
momentum
hv
v²
Photons

form the basis for all charged energy geometries and their associated quanta distributions

Equilateral energies

Any measurements of mass without a Space-Time co-ordinate system are measurements of Energy




1
1
3
4
1
2
1/2 1 1/2


1
1
3
4
5
9
1
2
3
1/2 1 3/2 1 1/2


1
1
3
4
5
9
7
16
1
2
3
4
1/2 1 3/2 2 3/2 1 1/2


1
1
3
4
5
9
7
16
9
25
1
2
3
4
5
1/2 1 3/2 2 5/2 2 3/2 1 1/2


1
1
3
4
5
9
7
16
9
25
11
36
1
2
3
4
5
6
1/2 1 3/2 2 5/2 3 5/2 2 3/2 1 1/2


1
1
3
4
5
9
7
16
9
25
11
36
13
49
1
2
3
4
5
6
7
1/2 1 3/2 2 5/2 3 7/2 3 5/2 2 3/2 1 1/2


1
1
3
4
5
9
7
16
9
25
11
36
13
49
15
64
1
2
3
4
5
6
7
8
1/2 1 3/2 2 5/2 3 7/2 4 7/2 3 5/2 2 3/2 1 1/2


1
1
3
4
5
9
7
16
9
25
11
36
13
49
15
64
17
81
1
2
3
4
5
6
7
8
9
1/2 1 3/2 2 5/2 3 7/2 4 9/2 4 7/2 3 5/2 2 3/2 1 1/2


v
Bosons
Energy
m
hv
v²
Photons
c²

Time specific measurements of
equilateral ENERGY momenta geometries
forms the basis for EM mass

Electromagnetic mass

2D mass-energy is the surface integral of 3D Matter


1
1
1
1/2
c²
1
1
1
2
3
4
1/2 1 1/2
c²
1
1
1
2
3
4
3
5
9
1/2 1 3/2 1 1/2
c²


1
1
1
2
3
4
3
5
9
4
7
16
1/2 1 3/2 2 3/2 1 1/2
c²
1
1
1
2
3
4
3
5
9
4
7
16
5
9
25
1/2 1 3/2 2 5/2 2 3/2 1 1/2
c²
1
1
1
2
3
4
3
5
9
4
7
16
5
9
25
6
11
36
1/2 1 3/2 2 5/2 3 5/2 2 3/2 1 1/2
c²


1 1 1
3 2 4
5 3 9
7 4 16
9 5 25
11 6 36
13 7 49
1/2 1 3/2 2 5/2 3 7/2 3 5/2 2 3/2 1 1/2
c²
1 1 1
3 2 4
5 3 9
7 4 16
9 5 25
11 6 36
13 7 49
15 8 64
1/2 1 3/2 2 5/2 3 7/2 4 7/2 3 5/2 2 3/2 1 1/2
c²
1 1 1
3 2 4
5 3 9
7 4 16
9 5 25
11 6 36
13 7 49
15 8 64
17 9 81
1/2 1 3/2 2 5/2 3 7/2 4 9/2 4 7/2 3 5/2 2 3/2 1 1/2
c²

mass-less particles
is a physical misnomer

All measurements of energy
in spatial co-ordinate systems
are measurements of mass

Matter-less is the appropriate terminology

Standing-wave Matter

Matter is a higher order 3D topology created by standing wave mass-energies


v
Bosons
Energy
momentum
M
hv
v²
Photons
c⁴

The equilateral mass-ENERGY content of 4nπ Tetrahedral standing-wave topologies forms the basis of Matter


1
1
1
1/2
c⁴
1
1
1
2
3
4
1/2
1
1/2
c⁴
1
1
1
2
3
5
4
9
3
1/2
1
3/2
1
1/2
c⁴



Only mass-ENERGIES contained in the tetryonic fascia of standing-wave topologies contribute to weight

Periodic element nuclei


v
Bosons
Energy
momentum
M
v
v²
Photons
c4

The mass-ENERGY content of
4nπ Tetrahedral standing-wave topologies
forms the basis of all periodic elements


−
+
c4
n
0
42-42
45,012

ALL
periodic elements are
comprised of
n level deuterium
nuclei

Copyright ABRAHAM [2008] - All rights reserved




2D radiant EM mass-Energies
μ0
ε0

n1 - Charged Tetryon Templates


3D standing-wave Matter



Copyright ABRAHAM [2008] - All rights reserved




2D radiant EM mass-Energies
μ0
ε0

n1 - Neutral Tetryon Templates


3D standing-wave Matter



Copyright ABRAHAM [2008] - All rights reserved


μ_0
ε_0
p
d


2D radiant EM mass-Energies
μ_0
ε_0

n2 - Charged Tetryon Templates


3D standing-wave Matter


μ_0
ε_0
p
d

Copyright ABRAHAM [2008] - All rights reserved




2D radiant EM mass-Energies
ε0
μ0

n2 - Neutral Tetryon Templates


3D standing-wave Matter





2D radiant EM mass-Energies

n3 - Charged Tetryon Templates


3D standing-wave Matter




p
d
μ_0
ε_0


2D radiant EM mass-Energies
μ_0
ε_0

n3 - Neutral Tetryon Templates


3D standing-wave Matter


p
d
μ_0
ε_0





2D radiant EM mass-Energies

n4 - Charged Tetryon Templates



3D standing-wave Matter




p
d
ε_0
μ_0


ε_0
μ_0

2D radiant EM mass-Energies

n4 - Neutral Tetryon Templates



3D standing-wave Matter


p
d
ε_0
μ_0




2D radiant EM mass-Energies

n5 - Charged Tetryon Templates


3D standing-wave Matter




p
d
μ_0
ε_0

n5 - Neutral Tetryon Templates


2D radiant EM mass-Energies
μ_0
ε_0


3D standing-wave Matter


p
d
μ_0
ε_0




2D radiant EM mass-Energies
ε0
μ0

n6 - Charged Tetryon Templates


3D standing-wave Matter




p
d
ε_0
μ_0


2D radiant EM mass-Energies
ε_0
μ_0

n6 - Neutral Tetryon Templates


3D standing-wave Matter


p
d
ε_0
μ_0

Copyright ABRAHAM [2008] - All rights reserved



2D radiant EM mass-Energies



n7 - Charged Tetryon Templates



3D standing-wave Matter






2D radiant EM mass-Energies
ε0
μ0

n7 - Neutral Tetryon Templates


3D standing-wave Matter



Copyright ABRAHAM [2008] - All rights reserved





2D radiant EM mass-Energies

n8 - Charged Tetryon Templates



3D standing-wave Matter




p
d
μ_0
ε_0


μ_0
ε_0

2D radiant EM mass-Energies

n8 - Neutral Tetryon Templates



3D standing-wave Matter


p
d
μ_0
ε_0

Periodic element geometries

An electron shell may be thought of as an orbit followed by electrons around an atom's nucleus.
The closest shell to the nucleus is called the "1 shell" (also called "K shell"), followed by the
"2 shell" (or "L shell"), then the "3 shell" (or "M shell"), and so on further and further from the nucleus.
The shell letters K, L, M, ... are alphabetical



Each shell consists of one or more subshells, and
each subshell consists of one or more atomic orbitals.


0
42-42
N⁰
e⁻
P⁺
n
45,012

Each shell can contain only an integer
number of whole deuterium nuclei
[Proton, Neutron & electron]


R
Q
P
O
N
M
L
K
Electron Shells
Q
[v-v]
RE
M₀
KE
Z
2
8
18
32
32
18
8
2
8
7
6
5
4
3
2
1
Principal Quantum Numbers
f
+3
d
+2
p
+1
s
0
p
-1
d
-2
f
-3
Sub-orbitals

VALENCE SHELLS
The electrons in the partially filled
outermost [or highest energy]
shell determine the chemical
properties of the atom

Each atomic shell equates to a specific
Energy level for the dueterium nuclei
that comprise it, in turn affecting the
angular momentum of electrons in that shell

Copyright ABRAHAM [2008] - All rights reserved

Periodic Harmonic motions

$x = A \cos(\omega t + \varphi)$

Circular motion

Much of the math in of modern physics
is predicated on the assumption that
π [where it appears] is related to
the properties of a circle

$F = -kx$

Linear motion


96°
96°
32
32
Z
18
18
54°
54°
8
2
2
8
24°
24°
6° 6°


1
2
3
4
4
3
2
p∑2(n²)


2
8
18
32
Z
32
18
8
2

Simple harmonic motion can be visualized as the projection of uniform circular motion onto one axis

circular harmonic motion


Principal Quantum Numbers
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
2
8
18
Z
32
32
18
8
2
M₀
KE
8
7
6
5
4
3
2
1
electron shells
energy levels
f
d
p
s
p
d
f
Sub-orbitals

simple harmonic motion

**Circular motions describe
the motion of a body
with a changing velocity vector
[the result of an acceleration force].**

**Nuclei per shell in elements follows
a 'periodic summation rule'
that is reflective of
photonic energies**

The quantum level mass-energies of Baryons determines the kinetic energies of electrons

1n - 1 e19v



Baryon mass-energies n		E		electron KEM field hv^2
73,728	n32	8	v8	3.268969693 e15
69,192	n31	7	v7	2.502804921 e15
64,800	n30	6	v6	1.838795452 e15
60,552	n29	5	v5	1.276941286 e15
56,448	n28	4	v4	8.172424232 e14
52,488	n27	3	v3	4.596988631 e14
48,672	n26	2	v2	2.043106058 e14
45,000	n25	1	v1	5.107765145 e13
Compton frequencies		**1.2 e20** **electron rest Matter is velocity invariant**		**spectral frequencies**
930 MeV		**496 keV**		**13.6 eV**

Atomic nuclei mass-energies

Each element's weight [mass-Matter in a gravitational field] is the result of the total quanta comprising that element



The nuclei forming each atomic shell have specific mass-energy quanta

Baryon rest masses · lepton rest mass · KEM

$$\overset{8}{\underset{1}{n}}\left[\left[72(n)^{2}\right]+\left[12e19\right]+\left[m_{e}v^{2}\right]\right]$$

Deuterium mass-energy per shell

Despite having differing mass-energies each Deuterium nuclei has the same velocity invariant Matter geometry [84π]

spin orbital coupling in synchronous quantum convertors

Electrons act as quantum scale rotating armatures in atomic nuclei and can only have specific energies reflective of the electron orbital energy level of the Baryons in which they are found

They acheive these energy levels by absorbing or emitting photons to acheive the specific angular momentum required

Copyright ABRAHAM [2008] - All rights reserved

Baryons **930.947 MeV** + **KEM fields** **13.525 ev** + **electrons** **496.519 keV**

Mapping Planck mass-energy contributions to elementary Matter and isotopes


Schrodinger's quantum numbers
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
electron shells
8
7
6
5
4
3
2
1
energy levels
Q
[v-v]
RE
M_0
KE
2
8
18
32
Z
32
18
8
2
f
d
p
c^4
p
d
f
Bohr's atomic orbitals

$$E = hv^2$$

$$n^2 + v^2 + e = Z$$

general form quatratic equation

$$ax^2 + bx + c = Z$$

$$E = nhv$$


E
polar aufbau

polar energy spirals courtesy of Rene Cormier

Identifying electron rest Matter topologies as velocity invariant we can re-arrange the component Planck mass-energy geometry formulation of periodic elements to

$$h\left[\underset{\text{Deuteron rest mass}}{72[v^2]} + \underset{\text{Spectral lines}}{v} + \underset{\text{electron rest mass}}{1.20\ \text{e}20\ v}\right]$$

reveal a quadratic formulation for all Z numbers

Copyright ABRAHAM [2008] - All rights reserved

$$\sum_{K}^{R}$$

nuclei per shell

STEP ONE

Periodic summation follows the atomic shell electron config

$${}_{P}\sum_{K}^{R} Z$$

Periodic Summation

Periodic summation is a notation developed for Tetryonic theory to model the geometric series addtion of Z[n²] energy level Deuterium nuclei that form the periodic elements

$$\sum_{1}^{120} Z$$

element number

STEP TWO

Periodic elements build up following the aufbau sequence

1 2 3 4 4 3 2 1

$${}_{P}\sum_{K}^{R} 2(x^2) =$$



Each atomic shell can hold only a fixed number of deuterium nuclei

$_{P}\sum R = 2$	2 nuclei [74.496 ea]	**120**	Unbinilium
	+		
$_{P}\sum Q = 8$	8 nuclei [69,780 ea]	**118**	Ununoctium
	+		
$_{P}\sum P = 18$	18 nuclei [65,232 ea]	**110**	Darmstadtium
	+		
$_{P}\sum O = 32$	32 nuclei [60,852 ea]	**92**	Uranium
	+		
$_{P}\sum N = 32$	32 nuclei [56,640 ea]	**60**	Neodymuim
	+		
$_{P}\sum M = 18$	18 nuclei [52,596 ea]	**28**	Argon
	+		
$_{P}\sum L = 8$	8 nuclei [48,720 ea]	**10**	Neon
	+		
$_{P}\sum K = 2$	2 nuclei [45,012 ea]	**2**	Helium
		0	Hydrogen

THe LHS of the notation determine the number of nuclei in each atomic shell, from the periodic mass-energy levels for atoms, and the RHS follows the aufbau building principle to determine the rest mass-Matter of any specific element

Aufbau

Each periodic element is made of Z [n² energy] deuterium nuclei

Z# [
z Protons [24-12]
z Neutrons [18-18]
z electrons [0-12]
] n1-8

Planck mass-energies form the surface integral of rest Matter topologies for each periodic element

Proton - Neutron Curve

The graph below is a plot of neutron number against proton number.
It is used as rule to determine which nuclei are stable or unstable.



Plot of Baryon numbers based on excess Neutron model of periodic elements

Deviation from Tetryonic plot is the result of the intrinsic mass-energies of each particle comprising the atomic nucleus

Plot of Baryonic nuclei numbers based on Tetryonic topologies of periodic elements

Historically, Proton-electron numbers are viewed as being equivalent in neutral elementary matter with the excess molar mass measured being the result of 'excess or extra' Neutrons in the atom

Atomic Nuclei Numbers

All periodic elements have an EQUAL number of Protons, Neutrons & Electrons with their molar mass-Matter being determined by their quantum level mass-energies



Tetryonic modelling of the charged mass-ENERGY-Matter topologies of elementary atoms and the nuclei that comprise them, reveals a DIRECT LINEAR relationship for the number of Protons-electrons-Neutrons in all periodic elements and nuclear isotopes

Copyright ABRAHAM [2008] - All rights reserved

Planck mass-energy contributions to elementary Matter and isotopes

The mass-energy content of Deuterium nuclei creates the molar mass of elements
[not extra neutrons in excess of the elemental number]


Deuteron
electron
eV
KEM
Z
32
3,050.6 MeV
8
En = -13.52 eV
291,166
31
2,5862.9 MeV
7
En = -10.35 eV
285,065
30
2,6811 MeV
6
En = -7.60 eV
262,158
29
2,505.4 MeV
5
En = -5.28 eV
213,887
28
2,335.6 MeV
4
En = -3.38 eV
133,697
27
2,171.8 MeV
3
En = -1.90 eV
58,940
26
2,013.9 MeV
2
En = -0.84 eV
19,840
25
1,861.9 MeV
1
En = -0.21 eV
3,725
496.519 keV
n
Quantum levels
V²
2H+
291,107 MeV
Elemental mass-Matter
[in MeV]
59,580 keV
e
6,101 MeV
993 keV
En = -27.05 eV
22,903 MeV
3,972 keV
En = -82.8 eV
48,262 MeV
8,937 keV
En = -136.8 eV
80,174 MeV
15,888 keV
En = -168.96 eV
74,740 MeV
15,888 keV
En = -108.16 eV
39,092 MeV
8,937 keV
En = -34.2 eV
16,111 MeV
3,972 keV
En = -6.72 eV
3,724 MeV
993 keV
En = -0.42 eV
565.11 keV
KEM field mass-energies
[in eV]
KE
2 + 8 + 18 + 32 + 32 + 18 + 8 + 2
nuclei number per shell
electron shells
R
Q
P
O
N
M
L
K
Schrodinger's quantum numbers
3
2
1
0
1
2
3
Q
[v-v]
RE
Z
2
8
18
32
32
18
8
2
M₀
KE
8
7
6
5
4
3
2
1
energy levels
f
d
p
c4
p
d
f
Bohr's atomic orbitals

n1
Elementary nuclei

are comprised of equal numbers of
Protons, Neutrons & electrons
with varying energy levels

Baryons		electrons		KEM fields
930.947 MeV	+	496.519 keV	+	13.525 ev

The mass-energy content of Matter topologies is velocity invariant

The mass-energy content of Baryons determines the KEM field of electrons

All elements are comprised of n level Duetrium nuclei

Baryons	**KEM fields**	**electrons**
Z [[72n²]	+ [12v²]	+ [1.2e20]]
1,861,949 MeV	13.525 eV	496,519 keV

$2H^{+}$ $[72n^2]$ **Z** γ $[M_e v^2]$

Elemental mass-Matter
[in MeV]

The atomic shell energy levels of Deuterium nuclei in elements



Deuteron	electron eV	KEM
32 3,050.6 MeV		En = -13.52 eV
31 2,5862.9 MeV		En = -10.35 eV
30 2,6811 MeV		En = -7.60 eV
29 2,505.4 MeV		En = -5.28 eV
28 2,335.6 MeV		En = -3.38 eV
27 2,171.8 MeV		En = -1.90 eV
26 2,013.9 MeV		En = -0.84 eV
25 1,861.9 MeV		En = -0.21 eV

496.519 keV

n v²

Determines the spectral line [KEM field energies] of electrons bound to them



R	3,050.6 MeV	13.525 eV	496,519 keV	Z [[72*32n²] + [12*8v²] + [1.2e20]]	2
					+
Q	2,862.9 MeV	10.35 eV	496,519 keV	Z [[72*31n²] + [12*7v²] + [1.2e20]]	8
					+
P	2,681.2 MeV	7.60 eV	496,519 keV	Z [[72*30n²] + [12*6v²] + [1.2e20]]	18
					+
O	2,505.4 MeV	5.28 eV	496,519 keV	Z [[72*29n²] + [12*5v²] + [1.2e20]]	32
					+
N	2,335.6 MeV	3.38 eV	496,519 keV	Z [[72*28n²] + [12*4v²] + [1.2e20]]	32
					+
M	2,171.7 MeV	1.90 eV	496,519 keV	Z [[72*27n²] + [12*3v²] + [1.2e20]]	18
					+
L	2,013.8 MeV	0.84 eV	496,519 keV	Z [[72*26n²] + [12*2v²] + [1.2e20]]	8
					+
K	1861.9 MeV	0.21 eV	496,519 keV	Z [[72*25n²] + [12*1v²] + [1.2e20]]	2

6,101 MeV
993 keV
En = -27.05 eV
+
22,903 MeV
3,972 keV
En = -82.8 eV
+
48,262 MeV
8,937 keV
En = -316.8 eV
+
80,174 MeV
15,888 keV
En = -168.96 eV
+
74,740 MeV
15,888 keV
En = -108.16 eV
+
39,092 MeV
8,937 keV
En = -34.2 eV
+
16,111 MeV
3,972 keV
En = -6.72 eV
+
3,724 MeV
993 keV
En = -0.42 eV

[1.2e20]]

e

the rest mass-Matter of bound photo-electrons is velocity invariant

The relativistic rest mass-energy-Matter of all periodic elements

is the sum of the mass-energies of all atomic nuclei and spectral lines that comprise its mass-Matter topology as measured in any spatial co-ordinate system per unit of time

Ionisation energies

Fractional quantum differentials


RE
M+KE
180
156
132
108
84
60
36
Lyman
Balmer
Paschen
Brackett
Pfund
Humphries
un-named
12
48
108
192
300
432
588
768
972
KEM energies
$p^2 = KEM = Mv^2$
1
2
3
4
5
6
7
8
ε_0
n
Higher energies
S up
e⁻
S down
Lower Energies

$$hf = \Delta Mv = \Delta p$$

spectral lines are produced by accelerating electrons

Note: this is an Illustrative schema for modelling KEM field energies
All KEM fields possess the same physical spatial geometry
in radial-time defined spatial co-ordinate systems

c^2 c^4



Photo-electrons absorb/emit spectral energies

$$E = eV = \frac{1}{4\pi\epsilon_0}\frac{ne^2}{a}$$

photo-electronic energy momenta


v
RE
KE
1
4
9
16
25
36
49
64
12
48
108
192
300
432
588
768
Spectral Lines
KEM Energies
p
KE
M
hv
v^2
12
[0-12]
1.2e20
Q
M

Mapping photo-electron transition energies
to Tetryonic energy momenta geometries
reveals many key facts about the
ionisation energies of nuclei

$$E = -\frac{Z^2}{n^2}\frac{ke^2}{2a_0} = -\frac{13.6Z^2}{n^2}eV$$

The differing fractional KEM field energy momenta of electrons that results from their transitions to specific energy nuclei in elements results in differing QAM quanta and produces spectral lines and fine line splitting

Spectral line transitions


Δv
Σv
KEM
Quantum differentials
36
60
84
108
132
156
180
3
5
7
9
11
13
15
1^2
2^2
3^2
4^2
5^2
6^2
7^2
8^2
36
96
180
288
420
576
756
48
108
192
300
432
588
768
1
2
3
4
5
6
7
8
hv
v
c
v^2
Mv^2

hv, R, β, p, KE
Planck, Rydberg, Lorentz, Newton, Leibniz

uniting classical physics and relativity
through equilateral geometry

Element numbers

Nuclei per shell in elements follow
a 'periodic summation rule'
that is reflective of
photonic energies

1 R
2
3
4
4
3
2
1 K

$$\sum_{K}^{R} P\, 2(x^2) = 2 + 8 + 18 + 32 + 32 + 18 + 8 + 2$$

Z

120	Unbinilium	n8
119	Ununennium	
118	Ununoctium	n7
87	Francium	
112	Copernicium	n6
55	Caesium	
102	Nobelium	n5
37	Rubidium	
70	Ytterbuim	n4
19	Potassium	
30	Zinc	n3
11	Sodium	
10	Neon	n2
3	Lithium	
2	Helium	n1
1	Deuterium	
0	Hydrogen	


Principal Quantum Numbers
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
electron shells
energy levels
Q
[v-v]
RE
M0
KE
Z
2
8
18
32
32
18
8
2
f
d
p
s
p
d
f
Sub-orbitals

Periodic mass-ENERGY-Matter

Following periodic summation rules for shell filling
n[1-8] quantum energy deuterium nuclei
combine to form elementary Matter

Baryon rest masses — lepton rest mass — KEM

$$\sum_{K}^{R} P \sum_{25}^{32} \left[[72(n)^2] + [12e19] + [m_e v^2] \right]_1^8$$

Deuterium mass-energy per shell

The measured weight of Matter in gravitational fields is the result of
planar mass-energies in tetryonic standing-wave geometries

The periodicity of all the elements,
along with their exact molar rest mass-energies and
quantum wavefunctions can be described with Tetryonic geometries

Ionisation energies



γ


Un-named series
Humphries series
Pfund series
Brackett series
Paschen series
Balmer series
Lyman series
Spectral Lines

$Mv^2 = KEM = hcR_H$

Photon emission/absorption

Copyright ABRAHAM [2008] - All rights reserved

Spectral line differentials

$$\Delta hv = \Delta Mv = \Delta p$$

changes to energy momenta

accelerate photo-electrons

$$\frac{1}{\lambda} = \frac{R_H}{hc}\left(\frac{1}{n_1^2} - \frac{1}{n_2^2}\right)$$

Ryberg's formula is
a mathematical description
of Tetryonic energy geometry


v
p
KE
ε_0
M
hv
v^2
3

& produces spectral lines

Δhf


V
bosons
KE
R
1
3
5
7
9
11
13
15
1^2
2^2
3^2
4^2
5^2
6^2
7^2
8^2
1
4
9
16
25
36
49
64
C
3/4
5/9
8/9
7/16
12/16
15/16
9/25
16/25
21/25
24/25
11/36
20/36
27/36
32/36
35/36
13/49
24/49
33/49
40/49
45/49
48/49
15/64
28/64
39/64
48/64
55/64
60/64
63/64
Un-named
Humphries
Pfund
Brackett
Paschen
Balmer
Lyman

absorption $\frac{n_i^2}{n_f^2}$ **Fractional energy level transitions** $\frac{n_f^2}{n_i^2}$ emission

Photo-electrons

Ryberg's constant reflects the changing
energy momentum of a transitioning electron

$$Mv^2 = KEM = hcR$$

*All of the transitions of photo-electrons
bound to Hydrogen atoms can now be
revealed in the fractional geometry
of KEM field energies*

KEM field energies

Copyright ABRAHAM [2008] - All rights reserved

Fermat's method of Factoring

also known as 'the difference of two squares' is used to factorise large numbers


1
1
1
3
4
1
3
5
9
1
3
5
7
16

$[x-y].[x+y]$

$x^2 - y^2$



All
spectral
lines transitions
are an example of

Fermat's
difference of two squares
in action at the quantum level

leading in turn to Ryberg's formula


1
3
5
7
9
25
1
3
5
7
9
11
36
1
3
5
7
9
11
13
49
1
3
5
7
9
11
13
15
64

Fermat knew that every odd number could be written as the difference of two squares
or as revealed geometrically through Tetryonic theory's equilateral geometry,
every 'SQUARE' number is the sequential sum of ODD numbers

Fractions

A fraction is a number that shows how many equal parts there are

In quantum mechanics fractions appear in quantum steps
as a result of the equilateral geometry of Planck energy momenta

3/4

24/25



40/49



48/64

80/81

.987654321



$$\frac{1}{\lambda} = R\left(\frac{1}{1} - \frac{1}{81}\right)$$

.987654321

Cos 60

.5

1/2

Sin 60

.866025403

$\sqrt{3}/2$

Tetryonic geometry explains the fractional mathematics of Rydberg's formula



Lyman spectral transitions

$$\Delta h\nu = \mathrm{KEM} = hcR$$

Planck

13.525 eV

Rydberg

n1 8
756
768
7 quantum level jump

n1 7
576
588
6 quantum level jump

n1 6
420
432
5 quantum level jump

n1 5
288
300
4 quantum level jump

n1 4
180
192
3 quantum level jump

n1 3
96
108
2 quantum level jump

n1 2
36
48
1 quantum level jump

Emission

Absorption

						768
180	15	[n1-8]	756	[n8-1]	15	
		+		–		588
156	13	[n1-7]	576	[n7-1]	13	
		+		–		432
132	11	[n1-6]	420	[n6-1]	11	
		+		–		300
108	9	[n1-5]	288	[n5-1]	9	
		+		–		192
84	7	[n1-4]	180	[n4-1]	7	
		+		–		108
60	5	[n1-3]	96	[n3-1]	5	
		+		–		48
36	3	[n1-2]	36	[n2-1]	3	
						12

		λ (nm)	$\tilde{\nu}$ (m-1)	f (Hz)	E (eV)	Ω (m^2/s)	
63/64	.9843	93.17075598	10,732,981.5	$3.217666905 \times 10^{15}$	13.31395504	27.93188995	$R\left(\frac{1}{1} - \frac{1}{64}\right)$ .984375
48/49	.9795	93.62569132	10,680,829.01	$3.202031983 \times 10^{15}$	13.24926138	28.06827613	$R\left(\frac{1}{1} - \frac{1}{49}\right)$ .9795
35/36	.9722	94.33539043	10,600,475.55	$3.177942622 \times 10^{15}$	13.14958523	28.28103857	$R\left(\frac{1}{1} - \frac{1}{36}\right)$ .9722
24/25	.9600	95.53641971	10,467,212.43	$3.137991343 \times 10^{15}$	12.98427616	28.64109809	$R\left(\frac{1}{1} - \frac{1}{25}\right)$ .96
15/16	.9375	97.82929378	10,221,5587.14	$3.064444671 \times 10^{15}$	12.67995718	29.32848443	$R\left(\frac{1}{1} - \frac{1}{16}\right)$ .9375
8/9	.8888	103.1793333	9,691,863.362	$2.90554754 \times 10^{15}$	12.02247792	30.93238594	$R\left(\frac{1}{1} - \frac{1}{9}\right)$ .888
3/4	.7500	122.2866172	8,177,509.712	$2.451555737 \times 10^{15}$	10.14396575	36.66060556	$R\left(\frac{1}{1} - \frac{1}{4}\right)$ .75

$$\Delta M v^2$$

Copyright ABRAHAM [2008] - All rights reserved

Balmer spectral transitions

$\Delta h\nu$ = KEM = hcR

Planck — 3.381 eV — Rydberg


n2~8
ζ
768
720
6 quantum level jump
n2~7
ε
588
540
5 quantum level jump
n2~6
δ
432
384
4 quantum level jump
n2~5
γ
300
252
3 quantum level jump
n2~4
β
192
144
2 quantum level jump
n2~3
α
108
60
1 quantum level jump


Emission
768
180
15
[n2-8]
720
[n8-2]
15
p
+
−
588
156
13
[n2-7]
540
[n7-2]
13
+
−
432
132
11
[n2-6]
384
[n6-2]
11
+
−
300
108
9
[n2-5]
252
[n5-2]
9
+
−
192
84
7
[n2-4]
144
[n4-2]
7
+
−
d
108
60
5
[n2-3]
60
[n3-2]
5
+
−
48
Absorption

Level	Ratio	λ (nm)	$\tilde{\nu}$ (m-1)	f (Hz)	E (eV)	Ω (m²/s)	Rydberg
768	60/64 .2343	391.3171751	2,555,471.1785	$7.661111677 \times 10^{14}$	3.169989296	103.1079531	$R\left(\frac{1}{4}-\frac{1}{64}\right)$ .2343
588	45/49 .2295	399.4696163	2,5033,319.299	$7.50476246 \times 10^{14}$	3.105295637	101.0057092	$R\left(\frac{1}{4}-\frac{1}{49}\right)$ .2295
432	32/36 .2222	412.7173331	2,422,965.84	$7.26386885 \times 10^{14}$	3.00561948	97.76161483	$R\left(\frac{1}{4}-\frac{1}{36}\right)$ .2222
300	21/25 .2100	436.7379187	2,289,702.719	$6.864356063 \times 10^{14}$	2.840310409	92.38472601	$R\left(\frac{1}{4}-\frac{1}{25}\right)$ .21
192	12/16 .1875	489.1464689	2,044,377.428	$6.128889342 \times 10^{14}$	2.535991437	82.48636251	$R\left(\frac{1}{4}-\frac{1}{16}\right)$ .1875
108	5/9 .138	660.347733	1,514,353.65	$4.539918031 \times 10^{14}$	1.878512175	61.10100927	$R\left(\frac{1}{4}-\frac{1}{9}\right)$ .138

$\Delta M v^2$

Copyright ABRAHAM [2008] - All rights reserved

Paschen spectral transitions

Δhv = KEM = hcR

Planck 1.502 eV Rydberg


n3~8
660
768
5 quantum level jump
n3~7
480
588
4 quantum level jump
n3~6
324
432
3 quantum level jump
n3~5
192
300
2 quantum level jump
n3~4
84
192
1 quantum level jump



Emission

768

180 *15* [n3-8] 660 [n8-3] *15*

+ − 588

156 *13* [n3-7] 480 [n7-3] *13*

+ − 432

132 *11* [n3-6] 324 [n6-3] *11*

+ − 300

108 *9* [n3-5] 192 [n5-3] *9*

+ − 192

84 *7* [n3-4] 84 [n4-3] *7*

+ − 108

Absorption

55/64
.0954

λ	960.5057935	nm
ṽ	1,041,118.135	m-1
f	3.121193646 x 10^{14}	Hz
E	**1.29147712**	**eV**
Ω	287.9523928	m^2/s

$R\left(\frac{1}{9}-\frac{1}{64}\right)$
.09548

40/49
.0907

λ	1,011.157466	nm
ṽ	988,965.6492	m-1
f	2.9464844428 x 10^{14}	Hz
E	**1.226783461**	**eV**
Ω	303.1373822	m^2/s

$R\left(\frac{1}{9}-\frac{1}{49}\right)$
.0907

27/36
.8033

λ	1,100.579555	nm
ṽ	908,612.1902	m-1
f	2.723950819 x 10^{14}	Hz
E	**1.127107305**	**eV**
Ω	329.94545	m^2/s

$R\left(\frac{1}{9}-\frac{1}{36}\right)$
.0833

16/25
.0711

λ	1,289.741666	nm
ṽ	775,349.069	m-1
f	2.324438032 x 10^{14}	Hz
E	**0.961798233**	**eV**
Ω	386.6548243	m^2/s

$R\left(\frac{1}{9}-\frac{1}{25}\right)$
.0711

7/16
.0486

λ	1,886.707809	nm
ṽ	530,023.7776	m-1
f	1.588971311 x 10^{14}	Hz
E	**0.657479261**	**eV**
Ω	565.6207715	m^2/s

$R\left(\frac{1}{9}-\frac{1}{16}\right)$
.0486

ΔMv^2

Copyright ABRAHAM [2008] - All rights reserved

Brackett spectral transitions

$$\Delta h\nu \;=\; \text{KEM} \;=\; hcR$$

Planck — 0.8451 eV — Rydberg



n4~8
δ
576
768
4 quantum level jump
n4~7
γ
396
588
3 quantum level jump
n4~6
β
240
432
2 quantum level jump
n4~5
α
108
300
1 quantum level jump



Emission
768
180
15
[n4-8]
576
[n8-4]
15
p
588
156
13
[n4-7]
396
[n7-4]
13
432
132
11
[n4-6]
240
[n6-4]
11
300
108
9
[n4-5]
108
[n5-4]
9
d
192
+
−
Absorption

48/64
.0468

λ	1,956.585876	nm
ṽ	511,094.357	m-1
ƒ	$1.532222335 \times 10^{14}$	Hz
E	**0.634001085**	**eV**
Ω	586.569689	m²/s

$R\left(\frac{1}{16} - \frac{1}{64}\right)$ .0468

33/49
.04209

λ	2,178.92518	nm
ṽ	458,941.8716	m-1
ƒ	$1.375873118 \times 10^{14}$	Hz
E	**0.569307096**	**eV**
Ω	653.2253354	m²/s

$R\left(\frac{1}{16} - \frac{1}{49}\right)$ .04209

20/36
.0347

λ	2,641.390932	nm
ṽ	378,588.4126	m-1
ƒ	$1.134979508 \times 10^{14}$	Hz
E	**0.469630433**	**eV**
Ω	791.8690801	m²/s

$R\left(\frac{1}{16} - \frac{1}{36}\right)$ .0347

9/25
.0225

λ	4,076.220574	nm
ṽ	245,325.2914	m-1
ƒ	$7.35466721 \times 10^{13}$	Hz
E	**0.30432052**	**eV**
Ω	1,222.020185	m²/s

$R\left(\frac{1}{16} - \frac{1}{25}\right)$ .0225

ΔMv^2

Pfund spectral transitions

$$\Delta h\nu = \text{KEM} = hcR$$

Planck P

0.541 eV

Rydberg


n5~8
γ
468
768
3 quantum level jump
n5~7
β
288
588
2 quantum level jump
n5~6
α
132
432
1 quantum level jump


Emission
768
180
15
[n5-8]
468
[n8-5]
15
588
156
13
[n5-7]
288
[n7-5]
13
432
132
11
[n5-6]
132
[n6-5]
11
300
Absorption

39/64

.0243

λ	3,762.665146	nm
$\tilde{\nu}$	265,769.0656	m-1
f	$7.967556145 \times 10^{13}$	Hz
E	**0.329678886**	**eV**
Ω	1,128.018633	m^2/s

$R\left(\frac{1}{25} - \frac{1}{64}\right)$

.0243

24/49

.0195

λ	4,681.284566	nm
$\tilde{\nu}$	213,616.5802	m-1
f	$6.404063965 \times 10^{13}$	Hz
E	**0.264985227**	**eV**
Ω	1,403.413807	m^2/s

$R\left(\frac{1}{25} - \frac{1}{49}\right)$

.01959

11/36

.0122

λ	7,503.951512	nm
$\tilde{\nu}$	133,263.1212	m-1
f	$3.995127867 \times 10^{13}$	Hz
E	**0.165309071**	**eV**
Ω	2,249.628068	m^2/s

$R\left(\frac{1}{25} - \frac{1}{36}\right)$

.0122

$\Delta M v^2$

Humphreys spectral transitions

$$\Delta h\nu \quad = \quad \text{KEM} \quad = \quad hcR$$

Planck   0.375 eV   Rydberg


n6~8
β
336
768
2 quantum level jump
n6~7
α
156
588
1 quantum level jump
Emission
768
180
15
[n6-8]
336
[n8-6]
15
+
−
588
156
13
[n6-7]
156
[n7-6]
13
+
−
432
Absorption

28/64

.01215

λ	7,546.831235	nm
ν̃	132,505.9444	m-1
ƒ	3.972428277 x 10^{13}	Hz
E	**0.164369815**	**eV**
Ω	1,128.018633	m^2/s

$$R\left(\frac{1}{36}-\frac{1}{64}\right)$$

.01215

13/49

.00733

λ	12,445.01497	nm
ν̃	80,353.459	m-1
ƒ	2.4089936098x 10^{13}	Hz
E	**0.099676156**	**eV**
Ω	1,403.413807	m^2/s

$$R\left(\frac{1}{36}-\frac{1}{49}\right)$$

.0073

$$\Delta M v^2$$

Un-named spectral transition

$$\Delta h\nu \quad = \quad \text{KEM} \quad = \quad hcR$$

Planck

0.276 eV

Rydberg

$\Delta\nu$ $\quad$ $\Sigma\nu$ $\quad$ $M\nu^2$


n7~8
α
180
768
1 quantum level jump


Emission
768
180
15
p
[n7-8]
180
[n8-5]
15
d
+
−
588
Absorption

15/64

.0047

λ	19,174.54158	nm
$\tilde{\nu}$	52,152.48541	m-1
ƒ	1.563492179 x 10^{13}	Hz
E	**0.064693658**	**eV**
Ω	5,748.382952	m²/s

$$R\left(\frac{1}{49}-\frac{1}{64}\right)$$

.0047

$\Delta M\nu^2$

Quantum Electrodynamics

$\Delta h\nu$

quantum energy momenta differentials


emission
absorption
[n-n]
0
Schrodinger's wavefunctions
180
156
132
108
84
60
36
Rydberg's constant & wavenumbers
R
R
bound photo-electrons
μ
KE
ɳ
hv
v
v²
Photo-electrons
Spectral lines
Lyman
Balmer
Paschen
Brackett
Pfund
Humphries
un-named
α
β
γ
δ
ε
ζ
η
p
2
3
4
5
6
7
8
n
quantised Planck mass-energy momenta
12
48
108
192
300
432
588
768
972
Velocity
v
KEM Energies
v²
1.2e20
Spectral Lines
KE
M
12
[φ-12]
hv
Spectral line transitions
Δv
Σv
v
12
1²
36
3
2
2²
36
60
5
3
3²
96
84
7
4
4²
180
108
9
5
5²
288
132
11
6
6²
420
156
13
7
7²
576
180
15
8
8²
756
hv
v
c
v²
Mv²
KEM
48
108
192
300
432
588
768
hv, R, β, p, KE
Planck, Rydberg, Lorentz, Newton, Leibniz
uniting classical physics and relativity through equilateral geometry
the charged geometry of mass-ENERGY-Matter in motion

$$\Delta h\nu = \Delta M\nu = \Delta p$$

all spectral lines are produced by accelerating photo-electrons

Tetryonics 96.11 - Atomic spectral series transitions



ninths



eigteenths



Eighteenths



Twenty-fourths



Fractionals and fractals

White light
[EM radiation]
is comprised of many
superpositioned
frequencies



Fractal antennas
are tuned to specific
wavelength-frequencies
to match the equilateral
geometry of photons



Sizteenths



Twenty-sevenths



Twenty-sevenths



Thirty-seconds

Polygons and Angles


rev
0
1
1/8
1/4
3/8
1/2
5/8
3/4
7/8
deg
0°
360°
45°
90°
135°
180°
225°
270°
315°
rad
0
2π
π/4
π/2
3π/4
π
5π/4
3π/2
7π/4

polygon exterior and interior angles


rev
1/6
1/3
1/4
1/4
3/10
1/5
1/3
1/6
deg
60°
120°
90°
90°
144°
72°
120°
60°
rad
π/3
2π/3
π/2
π/2
3π/5
2π/5
2π/3
π/3

dividing the circle


rev
1/3
1/4
1/5
1/6
1/8
deg
120°
90°
72°
60°
45°
rad
2π/3
π/2
2π/5
π/3
π/4


supplementary angles
complementary angles
triangles
rev
3/8
1/8
sum = 1/2 rev
1/6
1/12
sum = 1/4 rev
1/8
1/4
1/8
1/6
1/4
1/12
sum = 1/2 rev
deg
135°
45°
sum = 180°
60°
30°
sum = 90°
45°
90°
45°
60°
90°
30°
sum = 180°
rad
3π/4
π/4
sum = π rad
π/3
π/6
sum = π/2 rad
π/4
π/2
π/4
π/3
π/2
π/6
sum = π rad

Copyright ABRAHAM [2008] - All rights reserved

Pi vs Tau


π
bosons
180°
τ/2
π/3
π/3
π/2
π/3
60°
60°
90°
60°
τ/6
τ/6
τ/4
τ/6
2π
360°
photons
τ

Copyright ABRAHAM [2008] - All rights reserved

Triangular dissection of an equilateral triangle

is a way of dividing up a original triangle into smaller equilateral triangles,
such that none of the smaller triangles overlap













lowest order perfect equilateral triangle dissected by equilateral triangles



lowest order perfect dissected equilateral triangle, an isomer of the first

Copyright ABRAHAM [2008] - All rights reserved

Golden mean Spirals

Golden Mean Spiral – This spiral is derived via the golden rectangle, a unique rectangle which has the golden ratio.
This form is found everywhere in nature: the Nautilus Shell, the face of a Sunflower, fingerprints, our DNA, and the shape of the Milky Way

Golden spiral



$0,\ 1,\ 1,\ 2,\ 3,\ 5,\ 8,\ 13,\ 21,\ 34,\ 55,\ 89,\ 144,\ \ldots$



Golden spirals







Continued fractions and the Fibonacci sequence

The convergence of the continued fractions

$$1 + \frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\,\frac{1}{1+}\ \cdots$$

are:

$$\frac{2}{1},\ \frac{3}{2},\ \frac{5}{3},\ \frac{8}{5},\ \frac{13}{8},\ \frac{21}{13},\ \frac{34}{21},\ \frac{55}{34},\ \frac{89}{55},\ \frac{144}{89},\ \frac{233}{144},\ \frac{377}{233},\ \frac{610}{377},$$

The Golden Ratio (Golden Mean, Golden Section)
is defined mathematically as:

$$\varphi = \frac{1+\sqrt{5}}{2} = 1.6180339887\ldots.$$

Copyright ABRAHAM [2008] - All rights reserved

Koch fractal Curve

Niels Fabian Helge von Koch (January 25, 1870 – March 11, 1924) was a Swedish mathematician
who gave his name to one of the earliest fractal curves ever known

He described the Koch curve, or Koch snowflakes as it popularly known, in a 1904 paper entitled
“On a continuous curve without tangents constructible from elementary geometry”

Von Koch wrote several papers on number theory . One of his results was a 1901 theorem proving that the Riemann hypothesis is equivalent to a strengthened form of the prime number theorem.

Three Koch curves form the snowflake.



The Koch snowflake (or Koch star) is a mathematical curve and one of the earliest fractal curves to have been described.

Actually Koch described what is now known as the Koch curve, which is the same as the now popular snowflake, except it starts with a line segment instead of an equilateral triangle.



$$a = \frac{1}{2} + \frac{i}{\sqrt{12}}$$

The Koch curve is a special case of the Cesaro curve where:



which is in turn a special case of the de Rham curve.





vesica piscis

$$\frac{1351}{780} > \sqrt{3} > \frac{265}{153}\,.$$

Koch snowflake



space-time

star tetrahedron



Flower of Life



The Flower of Life is a name for a geometrical figure composed of multiple evenly-spaced, overlapping circles.

Unit circles - SINE WAVES - Photons


Classic model of a photon
Maxwell's Equations
$\nabla \times \vec{E} = -\frac{\partial \vec{B}}{\partial t}$
$\nabla \cdot \vec{D} = \rho$
$\nabla \times \vec{H} = \frac{\partial \vec{D}}{\partial t} + \vec{J}$
$\nabla \cdot \vec{B} = 0$
Magnetic component
Electric component
sin(x)
x (in decimal radians)
electric fields
$e^{i\tau/4}$
$e^{i\tau/3}$
$e^{i\tau/6}$
$e^{i\tau/8}$
$e^{i\tau/12}$
$e^{i\tau/2}$
$e^{i\cdot 0}, e^{i\tau}$
$e^{i\pi} = -1$
$i \equiv \sqrt{-1}$
N
N
S
S
v
$e^{i\cdot(3\tau/4)}$
magnetic fields
cos(x)
x (in decimal radians)
Tetryonic model of a photon

Magnetic waveforms are 90 degrees out of phase with Electric waveforms

Boson distributions in monochromatic EM waves


1/64 2/64 3/64 4/64 5/64 6/64 7/64 8/64 7/64 6/64 5/64 4/64 3/64 2/64 1/64
hν
v²
μ0
ε0
KE
p
boson-photon distribution in KEM field waveform
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1
normal distribution of Planck energy momenta
detected interference pattern produced by quantum distributions
.015 .031 .046 .062 .078 .093 .109 .125 .109 .093 .078 .062 .046 .031 .015

Probability distributions of monochromatic EM waves

Tetryonics 98.02 - Boson distributions in monochromatic EM waves

Wave interference patterns

The double-slit experiment, sometimes called Young's experiment, is a demonstration that matter and energy can display characteristics of both waves and particles, and demonstrates the fundamentally probabilistic nature of quantum mechanical phenomena and Establishes the quantum interference principle known as wave–particle duality.

Matter particles are stopped by the barrier but the [K]EM wave passes through both slits and is diffracted by them producing weaker EM waves that then superposition with each other to produce interference patterns



It is not the Particle passing through both slits that produces an interference pattern it is the particle's associated K[EM] wave

Equilateral superpositioned KEM waves produce constructive and destructive interference waves that have historically been interpreted as being circular wavefronts

electrons will be stopped by the material barrier but their associated KEM field energy momenta will be absorbed by the screen and 'tunnel through' the barrier to contribute to the interference pattern

final interference pattern produced will depend on phase relationships of the two super-postioned wavefronts

The Compton frequency of any [K]EM wave is comprised of identical wavelength Photons which can combine to produce interference patterns

Any detctor placed after the primary screen will remove energy from the secondaryKEM fields and affect the interference patterns produced

In the basic version of the experiment, a coherent light source such as a laser beam illuminates a thin plate pierced by two parallel slits, and the light passing through the slits is observed on a screen behind the plate. The wave nature of light causes the light waves passing through the two slits to interfere, producing bright and dark bands on the screen — a result that would not be expected if light consisted strictly of particles. However, on the screen, the light is always found to be absorbed as though it were composed of discrete particles or photons.

If one slit is observed for the passage of the electron in order to determine its physical state then the its KEM field wave will be absorbed by the detector resulting in only one wave remaining, enforcing a classical particle outcome

Quantum computing via EM wave super-positioning

BY superpositioning two beams
of EM radiation the resultant 'colours'
will perform quantum level computations
that can be read via the resultant
interference patterns produced



In phase

constructive interference

additive in-phase EM waves


1/2
1
3/2
2
5/2
3
7/2
4
7/2
3
5/2
2
3/2
1
1/2

Additive


+
1
2
3
4
5
6
7
8
7
6
5
4
3
2
1
square root
10
12
14
16
−

Subtractive


1/2
1
3/2
2
5/2
3
7/2
4
7/2
3
5/2
2
3/2
1
1/2

Out of phase



destructive interference

subtractive out-of-phase EM waves

Various basic operations, such as
ADDITION, SUBTRACTION and
SQUARE ROOTS etc
are all easily computed using
EM wave super-positioning

The lines of Force

**By utilising the statiscal distribution of equilateral Planck energy momenta quanta in EM waves
Tetryonic theory provides a practical geometric solution to quantum computing problems**

q

bosons

P vs. NP

*The set of all decision problems for which an algorithm exists which can be carried out by a deterministic Turing machine in **polynomial** time*

*the set of all decision problems for which an algorithm exists which can be carried out by a **non-deterministic** Turing machine in **polynomial** time*

E

photons

An algorithm of time complexity ***O**(n)* is one which increases in time linearly as the "size of the problem" (whatever n stands for) increases.

quanta intensities

1/64	🟥	1
2/64	🟧	2
3/64	🟨	3
4/64	🟩	4
5/64	●	5
6/64	🟦	6
7/64	●	7
8/64	🟪	8
7/64	●	7
6/64	🟦	6
5/64	●	5
4/64	🟩	4
3/64	🟨	3
2/64	🟧	2
1/64	🟥	1

linear momentum provides square roots of normal distributions of quanta



wave interference parterns provide information about normal distributions of quanta

1	🟥	0.0156
2	🟧	0.0312
3	🟨	0.0468
4	🟩	0.0625
5	●	0.0781
6	🟦	0.093
7	●	0.109
8	🟪	0.125
7	●	0.109
6	🟦	0.093
5	●	0.0781
4	🟩	0.0625
3	🟨	0.0468
2	🟧	0.0312
1	🟥	0.0156

quantum probabilites

An algorithm of complexity ***O**(2^n)* utlises exponential quanta; increasing n by 1 will double the quanta required

An algorithm of complexity ***O**(n^2)* utilises quadratic quanta, meaning that if you double n it will use four times as many quanta.

n^o

Unlike Math treatise on P vs Np that require exponential polynomial time ***O**(n^k)* Tetryonic geometry of EM fields utilise exponential energies per second

2*h*v

1 second

hf

By relating p to the number of equilateral wave fields in any EM wave very large [pn^2] data sets can be modelled and processed every second

Quantum Cryptography

If the numerical sequences were applied to amplitude modulation
their non-repeating numerical sequences would appear
to be purely random noise

Using Tetryonic geometry
advanced non-repeating cyphers
of any complexity
can be easily developed

The level of encryption can
be easily increased (without limit)
by increasing the dimensions
of the cypher geometry

eg: number of quanta
2D vs 3D geometries


1
A 2 B
C Z 3 Y D
E X A 4 B W F
G V C Z 5 F D U H
I T A B C 6 D E F S J
K Q G H I J 7 K L M N R L
M O P O P Q R 8 S T U V W P N
O N X Y Z J A T 9 P G V S C X M P
Q L R K S J T I U 0 V H W G X F Y E Z

eg: quantum encryption 1024
[38 60 02 64 72 90 50 10 47 05 94 08 48 52 27 26 51 66 01 91 03 20]
I T W A S T H E B E S T O F T
I M E S I T W A S T H E W
O R S T O F T I M E S
A T A L E O F T W
O C I T I E S
C . D I C
K E N
S

They can be based on known letter sources
(books, pages of magazines etc)
and can be further encrypted
through rotations, double encrypting
or pictogram substitutions

Copyright ABRAHAM [2008] - All rights reserved

Quantum Computing

The Proton/Neutron geometries of atomic nuclei can be built at the quantum scale
to create an atomic nuclei that can operate as a Opto-memory-transistive computing element,
many elements can then be combined in lattices to create super computers no larger than bacterium

Spin UP

Energy can be gated through individual nuclei
using the centre Baryon as the base transistor element,
in turn effecting the energies of bound photo-electrons

Spin DOWN







Q-bits

1

photo-electronic transitions can be used to directly recieve
or emit memory states through the absorption and emission
of spectral photons of specific energy momenta

0

Copyright ABRAHAM [2008] - All rights reserved


Scalar mass-energies
v
p
Bosons
Energy
$\mathcal{E}_0$
ENERGY
$[m\Omega v]^2$
momentum
hv
v²
Photons
c²
Quantum distributions
v
p
Boson
Quantum levels
Scalar
Energies
Planck quanta
$[m\Omega v^2]$
mass
velocity
hv
v²
Photon
Distributions
c²
EM mass
Planck quanta
$\frac{n\pi}{c^2}[[m\Omega v^2]]$
mass
velocity

2D mass

EM mass Planck quanta

$$\frac{n\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity


v
p
ε0
m
Bosons
Energy
hv
v²
Photons
c²
seconds

Measure of planar energies
in a nπ radiant wave
geometry
[per second]

mass quantum
7.376238634 e-51 kg

ENERGY

ENERGY

$$n\pi\left[\left[m\Omega v^2\right]\right]$$

momenta

Equilateral energy momenta
has a mass equivalence
per unit of Time



c^2 is the radial geometry
created by radiant energy
in 1 second

Planck Constant
6.629432672 e-34 J.s

3D Matter

Matter Planck quanta

$$\frac{T\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

Measure of mass-energy
in a 4nπ standing wave
topology
[per second squared]


c
ε0
M
Quarks
Baryons
hv
v²
Leptons
c⁴
seconds squared

Matter quantum
2.9504955454 e-50 kg

Copyright ABRAHAM [2008] - All rights reserved

Planck's constant - the quantum of Action

all ideal quantum inductive loops
resist changes to their
energy levels

INERTIAL mass

all equilateral energy momenta
produce square root vector
Forces

quantum of WORK


E
ε_0
$\hbar$
μ_0
μ_0
N
S




E
ε_0
$\hbar$
μ_0
μ_0
S
N

Quantised angular momentum is equilateral geometry

The two sides of Planck's Constant

The square root of all Energy is linear momentum

Equilateral energy quanta per second

mass


Δv
a
ε_0
E
Planck
Einstein
μ_0
μ_0
$h\nu$
v^2
Force
Newton
c^2
seconds

Quantised angular momenta per second

time

Copyright ABRAHAM [2008] - All rights reserved


CHARGE
bosons
tetryons
v
EM fields
quarks
p
leptons
ε_0
photons
Q
RE
Baryons
E
m
Ω
mass geometries
Matter Topologies
μ_0
μ_0
Electric fields
hv
v^2
Magnetic fields
c
M
KE
FORCE
Law of Attraction
Interaction-at-a-Distance
c^2
second
MASS
ENERGY
MATTER

Tetryonics 99.04 - Charged Planck mass-ENERGY-Matter



All squared energies have equilateral geometries

E
ε
+
N
μ
S
Q
RE
ν
Proton
opposites charges attract
interaction
gravitation
hν
ν²
same charges repel
M
KE
Neutron
−

2D
radiant
mass-energy
geometries

Energy in all its forms
seeks equilibrium

3D
standing-wave
Matter
topologies

There are NO infinities

only Eternity

Copyright ABRAHAM [2008] - All rights reserved



Clean, limitless Energy

Unlimited resources

The geometric field equation of mass-ENERGY-Matter

Matter

spatial

Planck

quanta

$$T\pi \left[[\varepsilon_0 \mu_0] \cdot [m \Omega v^2] \right]$$

topology

impedance

mass

velocity

Unifying Science and Religion

Tetryonic Theory

All EM mass, energy momenta & Matter can be measured and geometrised with respect to equilateral Quantised Angular Momenta

charged Planck quanta

Bosons

Planck quanta

$$\frac{\text{ODD}\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

Total Relativistic energies

ENERGY

Planck quanta

$$n\pi\left[\left[m\Omega v^2\right]\right]$$

mass velocity

Quantum Mechanics

Quantum Cosmology

standing-wave mass-Matter



radiant EM mass-energies

Quantum Chemistry

Electrodynamics

Matter

Planck quanta

$$\frac{T\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

EM waves

Planck quanta

$$\frac{\text{EVEN}\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

3D standing-wave mass/Matter topologies

The application of equilateral QAM geometries covers all of the Physical disciplines

2D radiant mass-energy geometries



Tetryonic Geometrics

The equilateral geometry underpinning the mathematics of Physics

Abraham

ISBN 978-0-987288-5-5
[Second Edition © 2012]

Copyright ABRAHAM [2008] - All rights reserved

TETRYONICS

The charged topology of periodic & compound Matter


Q
RE
3
2
1
0
1
2
3
Atomic masses
Molar Matter
R
Q
P
O
N
M
L
K
atomic shells
energy levels
8
7
6
5
4
3
2
1
2
8
18
32
32
18
8
2
Z
f
d
p
s
p
d
f
Chemical Energies
M
KE

Foundational Quantum Chemistry

Abraham

ISBN 978-0-987288-3-1

[Second Edition © 2012]

Copyright ABRAHAM [2008] - All rights reserved

Residual Electro-Magnetic Forces

allow Neutrons and Protons to attract via the opposite Electric charge points created by their constituent Quarks in order to create Elementary Nuclei

Protons + *Neutrons*

u+d+u d+u+d

All electrons, quarks and Baryons are made up of 4n+ (Tetryonic) standing-wave EM fields.

As well as having nett Tetryonic charged topologies ranging between [+24] ~ [-12] they all posses distinct ELECTRIC FIELDS that are concentrated in 3 apex points as indicated in the illustrations

These points result from the orientation of Electric apexes and orthagonal Magnetic dipole field edges that make up each particle's externalised EM fields.

The Positive and Negative electric apex points, obey the Law of Interaction forcing separated nuceli to combine due to their individual nett Tetryonic charges and provide a means of orienting nuclei to each other to create larger particles [elements, allotropes and compounds]

External Magnetic (H) fields can interact with the integral magnetic (B) dipoles of Tetryonic particles forcing them to orientate in specific directions to facilite chemical bonding [nuclear forces]

Additionally, external Electric fields can interact with the integral electric fields attracting or repelling them depending on the polarity of the external electric field [Electrostatics]

External energies can be induced into these integral EM fields via inductive coupling or the absorption of spectral photons in turn leading to an increase in the strengthes of the integral EM apexes in turn increasing the Strong Nuclear Force.



The orientation of the component Electric fields within 3D Matter creates macroscopic force apexes via externalised 'E-points'



The Strong Nuclear force binds Matter together





The orientation of the component Magnetic fields within 3D Matter creates macroscopic force apexes via externalised 'M-dipoles'

Nucleonic residual EM force

Neutrons

Protons

The attraction between Baryonic E&M field apexs, a result of their component Quark arrangements, results in the formation of heavier and more complex Nuclei

The residual e-field apexes and m-field dipoles form two rings of residual EM fields around the circumference of atomic nuclei







Elements & compounds follow Hexagonal packing rules

3D CAD modeling of elements courtesy of Ilene Cormier





E-field apexes and their polarities highlight the quark alignment of all atomic nuclei and elements

UP Quark
Positive Electric field apex

DOWN Quark
Negative Electric field apex

Insulators and Conductors

The position of electrons in Nuclei within Atomic Elements results in the properties of Insulators or Conductors


0
[24-24]
e-
P+
22,500
Hydrogen

Coloumbic forces

Electrons are attracted to the residual EM net (+12) positive charge of Protons or n[+12] unbalanced Ionic charges of nuclei

Conductor

Electrical energies move around the material via boson exchanges and electron movement


0
84
Deuterium
[42-42]
0
120
Tritium
[60-60]

≈

Insulator

Electrical energy is fixed within the nucleus as electrostatic charges & released upon demand via electron rotation/motion within the nucleus


84
Deuterium
[42-42]
0
120
Tritium
[60-60]
0

Insulator atomic configurations are equivalent to Quantum convertors

Ions

Charge (energy) is moved around material via electron movement


72
Deuterium
[42-30]
12
108
Tritium
[60-48]
12

Conductive materials contain 'free' electrons that can be readily or easily moved within the material

Insulator materials have electrons that are 'bound' tightly to the atoms and store charges locally where they are applied

Materials that have been ionised are more likely to become Conductors as they easily attract and bind free electrons to them

Nucleon Quark Arrangement

The nuclei arrangement of each atomic shell [quantum level] is the result of quark EM field interactions


Quantum levels
n8
n7
n6
n5
n4
n3
n2
n1
Atomic shells
R
Q
P
O
N
M
L
K
u
d
+
−
1
2
3
4
5
6
7
8
9
10
11
12
13
14

Nucleon Charges and Bonding


quark charges
nucleon charges

(Strong force - topological Electric Points)



residual EM forces



(Strong force - topological Magnetic dipoles)

Copyright ABRAHAM [2008] - All rights reserved

Bound electron arrangements

Externally bound electrons produce sub-orbital patterns different to the electron orbitals of internally bound electrons



Deuterium

electrons are externally bound to the Deuteron nuclei



Deuterium

electrons are internally bound in the Deuteron nuclei







Conductors

Charges are free to move and equalise

electrons require less energy to 'break free' from Nuclei

Insulators

Charges are bound to specific locations

electrons require more energy to 'break free' from Nuclei

The electron orbitals of conductors are lower energies than those of insulators

Tetryonics 41.06 - External electron configuration

2D mass-energy geometries form the fabric of 3D Matter topologies







Proton

12

[24-12]

nett Charge

component charges



charged mass-energy geometry

20π

Matter topology

12

[42-30]



40π

Deuteron

nett Charge

component charges

0

[18-18]

charged mass-energy geometry



Matter topology

20π

Neutron







Charge provides the framework for the mass-energy geometry of Matter

Copyright ABRAHAM [2008] - All rights reserved


0
[18-18]
36
Neutron
c^4
12
[42-30]
u
d
u
72
d
u
d
c^4
12
[24-12]
36
Proton
c^4
ε
p
d
μ

All Matter topologies are the result of charged EM mass-energy geometries

Matter

Baryons Planck quanta

$$\frac{36\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

mass-energy

Matter

Baryons Planck quanta

$$\frac{36\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

mass-energy

Deuterons

are the building blocks of all periodic elements and compounds

Tetryonics 42.02 - Nuclei formation

Strong Forces and Nuclear Bonding

How do Baryons with Positive and Neutral charges
attract each other and bind to form stable elements ?


P
Charged EM fascia
Electric fields & Magnetic dipoles
N
u
10-2
u
10-2
+
-
d
4-8
d
4-8
d
4-8
u
10-2

Protons & Neutrons are attracted to each other through their equal but opposite charge fascia of their Matter topologies


36
0
[18-18]
+
=
72
12
[42-30]
36
12
[24-12]

The attraction and binding of Protons and Neutrons through their electric charge imbalances creates Deuterons which have +12 charges

The residual Z[+12] charge is what attracts electrons to form neutral atomic nuclei via Coulombic attraction


[10-2]
[4-8]
[10-2]
12
[42-30]
72
P
N
[4-8]
[10-2]
[4-8]
N
P
[4-8]
[10-2]
[4-8]
72
12
[42-30]
[10-2]
[4-8]
[10-2]

Once nuclei have been created their external electric fields & magnetic dipoles continue to attract and bind individual nuclei together via the Residual EM Force as nuclei seek charge equilibrium by combining with each other and electrons to form neutral elements


84
84
84
84
84
84
84
d
u
1
2
3
4
5
6
0
[42-42]
Z

Copyright ABRAHAM [2008] - All rights reserved

Strong Nucleonic Bonding





+

In addition to the Strong colour force
a separate residual binding force arises
from the external apexes formed by
Positive and Negative Electric points of quarks
in each Baryon [nuclear-chemical bonds]

-



All energy seeks equilibrium

Strong E-force
nuclear linkages

External Electric field points
bind via Charge fascia interactions
with Plus and Minus Electric points
combining and sharing energy
throughout the resultant nuclei



● Positive Electric field apex

Negative Electric field apex ●

Copyright ABRAHAM [2008] - All rights reserved

Hydrogenic vs Nucleonic electron binding

If a unbound Proton attracts an Electron
the Electron can be bound to the nuclei
in a number of differing orientations
[each with differing spin energies]


12
[24-12]
N
S
Proton
+
12
[0-12]
S
N
electron
=
nuclear spin coupled
Bohr magneton
0
[24-24]
S
N
Hydrogen

The energy levels of Baryons determines the KEM field energy of bound electrons

All atomic nuclei (and elements) are Deuteron'ic nuclei with a mixture of *orthagonal*, parallel and anti-paralllel spin orientations

(this is why Rydberg is less accurate for elemental nuclei compared to Hydrogenic atoms - see QM spin)


12
[42-30]
N
S
Deuteron
+
12
[0-12]
S
N
electron
=
Spin DOWN electron coupling
[anti-parallel moments]
0
[42-42]
Deuterium

Bohr magnetons are always referenced wrt the Nuclear magneton


12
[42-30]
N
S
Deuteron
+
12
[0-12]
N
S
electron
=
Spin UP electron coupling
[parallel moments]
0
[42-42]
Deuterium

electrons produce stronger magnetic moments due to their mass-charge quotient

Electrons can be bound to deuteron nuclei
in four distinct orientations [2 horizontal & 2 vertical]
with each spin coupling orientation producing
differing energy electron orbitals
[wrt to the nuclear magnetic moments]

Ejecting electrons from atomic nuclei
by adding energies to their KEM fields
[the Photoelectric effect]
creates Positive Ions

Vertically orientated electrons
within Proton-Neutron Nuclei [Deuterons]
create quantum synchronous convertor geometries

Atomic Nucleus Master Template


Nucleon Number
Z
1 Proton [24-12]
1 electron [0-12]
1 Neutron [18-18]
R 8
Q 7
P 6
O 5
N 4
M 3
L 2
K 1
f 7
1-14 Actinoid
1-14 Lanthanoid
d 5
9-10 Post Transition Metal
1-8 Transition Metal
p 3
6 Noble Gas
5 Halogen
1-4 Non-Metal Metaloid Poor-Metal
s 1
2 Alkaline Earth
1 Alkali Metal
Shell
Energy level
Orbitals
sub orbital
Family

- s 1 sub-Orbital (2 electrons max)
- p 3 sub-Orbitals (6 electrons max)
- d 5 sub-Orbitals (10 electrons max)
- f 7 sub-Orbitals (14 electrons max)


Neutrons
Protons
u
d
Md Tm 13
Ac La 1
Pa Pr 3
Rg Au Ag Cu 9
Lr Lu Y Sc 1
Db Ta Nb V 3
Bk Tb 9
Es Ho 11
Mt Ir Rh Co 7
Bh Re Tc Mn 5
Am Eu 7
Np Pm 5
At I Uus Br Cl F 5
Po Te Lv Se S O 4
Cs Rb Fr D K Uun Na Li 1
Tl In Uut Ga Al B 1
Pb Sn Fl Ge Si C 2
Ba Sr Ra He Ca Ub Be Mg 2
Bi Sb Uup As P N 3
Rn Xe Uuo Kr Ne Ar 6
Pu Sm 6
Cm Gd 8
Hs Os Ru Fe 6
Ds Pt Pd Ni 8
Fm Er 12
Cf Dy 10
Sg W Mo Cr 4
Rf Hf Zr Ti 2
Cn Hg Cd Zn 10
U Nd 4
Th Ce 2
No Yb 14
Spin 1/2
electrons
e-
S
N
μB
Bohr magnetons are referenced to the Nuclear magneton
μN
electrons
-e
Spin 1/2



The Chemical elements

Elemental family groupings are a reflection of atomic sub-orbitals within elemental atoms

Orbitals	sub orbital	Family
f 7	1-14	Actinoid
	1-14	Lanthanoid
d 5	9-10	Post Transition Metal
	1-8	Transition Metal
p 3	6	Noble Gas
	5	Halogen
	1-4	Non-Metal Metaloid Poor-Metal
s 1	2	Alkaline Earth
	1	Alkali Metal

Quantum numbers

	3							2					1			0		1			2					3							
	+3	+2	+1	0	-1	-2	-3	+2	+1	0	-1	-2	+1	0	-1			-1	0	+1	-2	-1	0	+1	+2	-3	-2	-1	0	+1	+2	+3	
R																119	120																8
Q													117	115	113	87	88	114	116	118													7
P								111	109	107	105	103	85	83	81	55	56	82	84	86	104	106	108	110	112								6
O	101	99	97	95	93	91	89	79	77	75	73	71	53	51	49	37	38	50	52	54	72	74	76	78	80	90	92	94	96	98	100	102	5
N	69	67	65	63	61	59	57	47	45	43	41	39	35	33	31	19	20	32	34	36	40	42	44	46	48	58	60	62	64	66	68	70	4
M	13	11	9	7	5	3	1	29	27	25	23	21	17	15	13	11	12	14	16	18	22	24	26	28	30	2	4	6	8	10	12	14	3
				f				9	7	5	3	1									2	4	6	8	10				f				
L										d			9	7	5	3	4	6	8	10			d										2
K													5	3	1	1	2	2	4	6													1
														p		1	2		p														
																s																	

Atomic Shells

Energy levels

Orbitals & sub-Orbitals

Tetryonics 43.02 - The Chemical Elements

Element Numbers

Z *
1 Proton [24-12]
1 Neutron [18-18]
1 electron [0-12]

Each elemental nuclei is made from Deuterium


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
f 7
d 5
p 3
s 1
1-14 Actinoid
1-14 Lanthanoid
9-10 Post Transition Metal
1-8 Transition Metal
6 Noble Gas
5 Halogen
1-4 Non-Metal Metaloid Poor Metal
2 Alkaline Earth
1 Alkali Metal
Shell
Energy level
Orbitals
sub orbital
Family

○ **s** *1 sub-Orbital (2 electrons max)*

○ **p** *3 sub-Orbitals (6 electrons max)*

○ **d** *5 sub-Orbitals (10 electrons max)*

○ **f** *7 sub-Orbitals (14 electrons max)*

Atomic shells
P
O
K
Q
N
R
L
M



There are a maximum of 120 elements possible

6
5
7
1
4
8
2
3
Energy levels

Element Names


Z
*
1 Proton [24-12]
1 Neutron [18-18]
1 electron [0-12]
R 8
Q 7
P 6
O 5
N 4
M 3
L 2
K 1
f 7
1-14 Actinoid
1-14 Lanthanoid
d 5
9-10 Post Transition Metal
1-8 Transition Metal
p 3
6 Noble Gas
5 Halogen
1-4 Non-Metal Metaloid Poor-Metal
s 1
2 Alkaline Earth
1 Alkali Metal
Shell
Energy level
Orbitals
sub orbital
Family

There are a maximum of 120 elements possible


Atomic shells
P Q O K N R L M
13 Md 13 Tm
1 Ac 1 La
Pa 3 Pr 3
Rg Au 9 Ag Cu 9
Bk 9 Tb 9
Lr Lu 1 Y Sc 1
Db Ta 3 Nb V 3
Es 11 Ho 11
Mt Ir 7 Rh Co 7
Bh Re 5 Tc Mn 5
7 Am 7 Eu
Np 5 Pm 5
At I Uus 5 Br F Cl 5
Po Te Lv 4 Se O S 4
1 Cs Rb Fr D 1 K Uun Li Na
1 Tl In Uut 1 Ga B Al
Pb Sn Fl 2 Ge C Si 2
Ba Sr Ra He 2 Ca Ub Be Mg 2
Bi Sb Uup 3 As N P 3
Rn Xe Uuo 6 Kr Ne Ar 6
Pu 6 Sm 6
6 Hs Os 6 Ru Fe
8 Ds Pt Pd 8 Ni
Cm Gd 8 8
12 Fm 12 Er
Sg W 4 Mo Cr 4
10 Cn Hg 10 Cd Zn
2 Rf Hf 2 Zr Ti
Cf 10 Dy 10
4 U 4 Nd
Th 2 Ce 2
No 14 Yb 14
5 6 7 1 4 8 2 3
Energy levels

o s *1 sub-Orbital (2 electrons max)*

O p *3 sub-Orbitals (6 electrons max)*

O d *5 sub-Orbitals (10 electrons max)*

O f *7 sub-Orbitals (14 electrons max)*

They were originally named according to their properties by their discoverer but have recently been named after famous scientists

Copyright ABRAHAM [2008] - All rights reserved

Electron orbital configurations

A huge number of differing d and f orbital configurations are possible given the number of nuclei and bond points created by elemental topologies


85
53
5
35
9
17
84
52
4
34
8
16
55
37
87
1
19
11
81
49
1
31
5
13
82
50
2
32
6
14
56
38
88
2
20
4
12
83
51
3
33
7
15
86
54
6
36
10
18

As the number of nucleons increases so does the complexity of the electron orbitals possible

quantum snowflakes

However all have a stable 'core' grouping of nuclei comprised of s and p electron orbitals


At
I
5
Br
F
Cl
Po
Te
4
Se
O
S
Cs
Rb
Fr
D
1
K
Li
Na
Tl
In
1
Ga
B
Al
Pb
Sn
2
Ge
C
Si
Ba
Sr
Ra
He
2
Ca
Be
Mg
Bi
Sb
3
As
N
P
Rn
Xe
6
Kr
Ne
Ar


d
f
s
p
5
4
1
1
2
2
3
6

All nuclei bonding closely follows hexagonal packing rules

Atomic Nucleus Exploded view

1 Proton [24-12]
1 electron [0-12]
1 Neutron [18-18]


R
8
Q
7
P
6
O
5
N
4
M
3
L
2
K
1
f 7
1-14
Actinoid
1-14
Lanthanoid
d 5
9-10
Post Transition Metal
1-8
Transition Metal
p 3
6
Noble Gas
5
Halogen
1-4
Non-Metal Metaloid Poor-Metal
s 1
2
Alkaline Earth
1
Alkali Metal
Shell
Energy level
Orbitals
sub orbital
Family

○ s *1 sub-Orbital (2 electrons max)*
○ p *3 sub-Orbitals (6 electrons max)*
○ d *5 sub-Orbitals (10 electrons max)*
○ f *7 sub-Orbitals (14 electrons max)*


Atomic shells
P
O
Q
K
N
R
L
M
Md 31 Tm
Ac 19 La
Pa 21 Pr
Rg Au 17 Ag Cu
Lr Lu 9 Y Sc
Db Ta 11 Nb V
Mt Ir 15 Rh Co
Bh Re 13 Tc Mn
Bk 27 Tb
Es 29 Ho
Am 25 Eu
Np 23 Pm
At I Uus 7 Br F Cl
Po Te Lv 6 Se O S
Cs Rb Fr H 1 K Uun Li Na
Tl In Uut 3 Ga B Al
Pb Sn Fl 4 Ge C Si
Ba Sr Ra He 2 Ca Ub Be Mg
Bi Sb Uup 5 As N P
Rn Xe Uuo 8 Kr Ne Ar
Pu 24 Sm
Cm 26 Gd
Fm 30 Er
Cf 28 Dy
Hs Os 14 Ru Fe
Ds Pt 16 Pd Ni
Sg W 12 Mo Cr
Rf Hf 10 Zr Ti
Cn Hg 18 Cd Zn
U 22 Nd
Th 20 Ce
No 32 Yb
6
5
1
7
8
4
2
3
Energy levels

Copyright ABRAHAM [2008] - All rights reserved



Atomic radii of elements

The Mendeleev block arrangement of periodic elements presents a number of problems in representing the true topologies and properties of all the periodic elements:

Questions are raised over Hydrogen's appropriate position in the table

The table correctly positions elements according to their elemental properties but offers no insight into the individual geometries of the periodic elements themselves

The table does not reflect the charged quantum geometries of nuclei in each atomic shell

The table is unable to accurately reflect the electron orbitals or other elemental properties described by the Bohr & Schrodinger models

The table maps the atomic number (the number of protons in an atom), not atomic weight in determining the order of the elements in the table resulting in a number of errors in periodic element placements

'f' orbitals elements are not normally presented in their true atomic number positions

Tetryonic charge geometry rectifies all of these deficiencies

Tetryonics 43.07 - Atomic radii of elements



PERIODIC TABLE OF ELEMENTS

modelled on the polar view of the charge topologies of periodic elements

Deuterium [not Hydrogen] is the building block of all elements

Periodic element families

3D quantum charge geometry of periodic element nuclei

84
[42-42]
Energy levels
P 6
O 5
Q 7
K 1
R 8
N 4
L 2
M 3
Atomic shells
electron orbitals
f
d
p
s
2
6
10
14
electron sub-orbitals
Md Tm 13
Ac La 1
Pa Pr 3
Rg Au Ag Cu 9
Lr Lu Y Sc 1
Db Ta Nb V 3
Bk Tb 9
Es Ho 11
Mt Ir Rh Co 7
Bh Re Tc Mn 5
Am Eu 7
Np Pm 5
At Uus I Br Cl F 5
Cs Rb Fr D K Uun Li Na 1
Po Lv Te Se O S 4
Tl Uut In Ga B Al 1
Pb Fl Sn Ge C Si 2
Ba Sr Ra He Ca Ub Be Mg 2
Bi Uup Sb As N P 3
Rn Uuo Xe Kr Ne Ar 6
Pu Sm 6
Cm Gd 8
Hs Os Ru Fe 6
Ds Pt Pd Ni 8
Fm Er 12
Cf Dy 10
Sg W Mo Cr 4
Cn Hg Cd Zn 10
Rf Hf Zr Ti 2
U Nd 4
Th Ce 2
No Yb 14
R 8
Q 7
P 6
O 5
N 4
M 3
L 2
K 1
f 7
d 5
p 3
s 1
1-14 Actinoid
1-14 Lanthanoid
9-10 Post Transition Metal
1-8 Transition Metal
6 Noble Gas
5 Halogen
1-4 Non-Metal Metaloid Poor-Metal
2 Alkaline Earth
1 Alkali Metal
Shell
Energy level
Orbitals
sub orbitlas
Family
quantum numbers
3 2 1 0 1 2 3
2
8
18
32
32
18
8
2
Z
Atomic Shells
Energy levels
8 7 6 5 4 3 2 1
d p s p d f
Sub-orbitals



THE ATOMIC NUCLEUS

the charged quantum mass-energy geometry of periodic element topologies

Neils Bohr
(7 October 1885 – 18 November 1962)
NEILS BOHR
Erwin Schrödinger
[12 August 1887 – 4 January 1961]
SCHRÖDINGER
quantum numbers
3
2
1
0
1
2
3
Atomic Shells
R
Q
P
O
N
M
L
K
2
8
18
32
32
18
8
2
Z
8
7
6
5
4
3
2
1
Energy levels
f
d
p
s
p
d
f
electron orbitals

The Bohr model gives us a basic conceptual model of electrons orbits and energies, along with the idea of quantum jumps.

The Schrondinger wave equation gives precise details of spectra and electron position and motions within the nuclei

The uncertainty principle erroneously dictates that position and momentum cannot be simultaneously determined.

Copyright ABRAHAM [2008] - All rights reserved

Periodicity of atomic elements

An electron shell may be thought of as an orbit followed by electrons around an atom's nucleus.
The closest shell to the nucleus is called the "1 shell" (also called "K shell"), followed by the
"2 shell" (or "L shell"), then the "3 shell" (or "M shell"), and so on further and further from the nucleus.
The shell letters K, L, M, ... are alphabetical

Each shell can contain only a fixed number of deuterium nuclei [Protons, Neutrons & electrons]

Each shell consists of one or more electron orbitals, and each orbital consists of one or more sub-orbitals.



8 atomic energy shells with electrons

120 periodic elements in total

The number of deuterium nuclei that form each atomic shell in an elemental atom number is double that of Photon energy levels

Each atomic shell equates to a specific energy level for the Deuterium nuclei that comprise it with in turn affect the angular momentum of electrons in that shell

The electrons in the partially filled outermost atomic shell [or highest energy level] determine the chemical properties of the atom; they are called valence shell electrons.

Copyright ABRAHAM [2008] - All rights reserved


Side View
Quantum numbers
0
1
1
2
2
3
3
R
Q
P
O
N
M
L
K
atomic shells
2
8
18
32
32
18
8
2
n
8
7
6
5
4
3
2
1
energy levels
f
f
d
d
p
p
s
electron orbitals
Top View
ℓ
m
f d p s p d f
7 + 5 + 3 + 2 + 3 + 5 + 7
5, 11, 3, 13, 1, 9, 7
8, 2, 10, 4, 6
5, 1, 3
1-2
6, 2, 4
7, 1, 9, 3, 5
6, 12, 4, 14, 2, 10, 8
Quantum numbers
0
1 1
+1 0 -1
-1 0 +1
2 2
+2 +1 0 -1 -2
-2 -1 0 +1 +2
3 3
+3 +2 +1 0 -1 -2 -3
-3 -2 -1 0 +1 +2 +3
R
Q
P
O
N
M
L
K
2
8
18
32
32
18
8
2
Z
8
7
6
5
4
3
2
1
13 11 9 7 5 3 1
2 4 6 8 10 12 14
f
f
9 7 5 3 1
2 4 6 8 10
d
d
5 3 1
2 4 6
p
p
1 s 2
Atomic Shells
Orbitals & sub-Orbitals
Energy levels

Atomic shells & energy levels

Using the charge geometries of equilateral
mass-energies in Matter topologies
all period elements can be
accurately modelled

Tetryonics 44.03 - Shells & energy levels

Copyright ABRAHAM [2008] - All rights reserved

atomic Shells


s
s + p
s + p + d
s + p + d + f
s + p + d + f
s + p + d
s + p
s

energy levels


Azmithal quantum number
3 2 1 0 1 2 3
R Q P O N M L K
atomic shell
8 7 6 5 4 3 2 1
energy level
ℓ
f d p s p d f

Electron orbitals



quantum numbers

Each electron's location in an elemental nuclei is defined by its quantum numbers

All atoms have shells comprised of concentric s, p, d & f electron orbitals

electron orbitals

each electron orbital can hold a maximum of two spin opposed electrons

a core s-orbital surrounded by 3 p-orbitals 5 d-orbitals and 7 f-orbitals


Azmithal & Magnetic numbers
0
1 1
+1 0 -1
-1 0 +1
2 2
+2 +1 0 -1 -2
-2 -1 0 +1 +2
3 3
+3 +2 +1 -1 -2 -3
-3 -2 -1 +1 +2 +3
f d p s p d f
1 4 9 16 16 9 4 1
13 11 9 7 5 3 1
2 4 6 8 10 12 14
f f
9 7 5 3 1
2 4 6 8 10
d d
5 3 1
2 4 6
p p
1 s 2
R Q P O N M L K
8 7 6 5 4 3 2 1
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Tetryonics 44.04 - Electron Orbitals

magnetic quantum numbers


m
s
p
d
f
14
10
6
2


Azmithal & Magnetic numbers
+3
+2
+1
0
-1
-2
-3
atomic shells
R
Q
P
O
N
M
L
K
Shell
2
3 2 3
5 3 2 3 5
7 5 3 2 3 5 7
7 5 3 2 3 5 7
5 3 2 3 5
3 2 3
2
electrons per shell
2
8
18
32
32
18
8
2
Nuclei
1,3,5,7,9,11,13
1,3,5,7,9
1,3,5
1,2
2,4,6
2,4,6,8,10
2,4,6,8,10,12,14
f
d
p
s
p
d
f
electron Orbitals & sub-orbitals

electron sub-orbitals

each eatomic orbital can hold two spin opposed electrons


H
D
s
K
2
He
s+p
2+6
F
O
Li
B
L
C
Be
8
N
Ne
s+p+d
2+6+10
Cu
Sc
V
Co
Mn
Cl
S
Na
Al
M
Si
Mg
18
P
Ar
Fe
Ni
Cr
Ti
Zn
s+p+d+f
2+6+10+14
Tm
La
Pr
Ag
Bk
Y
Nb
Ho
Rh
Tc
Eu
Br
Se
Pm
K
Ga
N
Ge
Ca
32
Sm
As
Kr
Gd
Ru
Pd
Er
Mo
Zr
Dy
Cd
Nd
Ce
Yb
Md
Ac
Pa
Au
Bk
Lu
Ta
Es
Ir
Re
Am
I
Te
Np
Rb
In
O
Sn
Sr
32
Pu
Sb
Xe
Cm
Os
Pt
Fm
W
Hf
Cf
Hg
U
Th
No
s+p+d+f
2+6+10+14
Rg
Lr
Db
Mt
Bh
At
Po
Cs
s+p+d
2+6+10
Tl
P
Pb
18
Ba
Bi
Rn
Hs
Ds
Sg
Rf
Uub
Uus
Uuh
Fr
s+p
2+6
Uut
Q
Uuq
8
Ra
Uup
Uuo
Uun
s
R
2
Ub

120 elements in 8 quantum levels

[+ Hydrogen as a free radical]

Electron SPIN in atoms

1 sub-Orbit	s	*2 electrons*
3 sub-Orbits	p	*6 electrons*
5 sub-Orbits	d	*10 electrons*
7 sub-Orbits	f	*14 electrons*

Hund's Rule
Each electron sub-orbital (Azimuthal number)
can not have electrons with the same spin direction



S
s p d
f
14
10 6 2



f 14
1,3,5,7,10,12,14
2,4,6,8,9,11,13
d 10
1,3,6,8,10
2,4,5,7,9
p 6
2,3,6
1,4,5
s 2
1
2

electron spin is always referenced to the Nuclear magneton



azmithal & magnetic quantum numbers
+3
+2
+1
0
-1
-2
-3
Atomic shells
R
Q
P
O
N
M
L
K
2
8
18
32
32
18
8
2
Z
8
7
6
5
4
3
2
1
energy levels
f
d
p
s
p
d
f
electron orbitals & sub-orbitals



KE
α
Spin down
Spin up
β
α
β
μ z
N
S
α
Spin up
Spin down
β
KE

Tetryonics 44.06 - Electron spin

Quantum numbers


Energy levels
0
R
1
1
8
Q
2
8
2
7
P
3
18
3
6
O
32
n
5
N
32
4
M
f
18
f
3
L
d
8
d
2
K
p
2
p
1
s
Atomic Shells
3
2
1
0
1
2
3
+3, +2, +1, 0-1, -2, -3
+2, +1, 0, -1, -2
+1, 0, -1
0
-1, 0, +1
-2, -1, 0, +1, +2
-3, -2, -1, 0+1, +2, +3
Electron SPINS

The properties of every atom's specific electron configuration can be described by four quantum numbers:

n (1-8)
Principal
(n = 1, 2, 3, 4 ...)

ℓ (0-3)
Azimuthal
(l = 0, 1 ... n−1)

m (2ℓ+1)
Magnetic
(ml = −l, −l+1 ... 0 ... l−1, l)

s ± ½
electron Spin
(ms = −1/2 or +1/2),

The Bohr model was a one-dimensional model that used one quantum number to describe the distribution of electrons


ℓ
0 1 2
3
14
10 6 2
ms

The three coordinates that come from Schrödinger's wave equations are the principal (n), angular (l), and magnetic (m) quantum numbers.

These quantum numbers describe the size, shape, and orientation in space of the orbitals of any particular atom mathematically.

Each electron's quantum numbers are unique and cannot be shared by another electron in that atom.

These four numbers, n, ℓ, m and s can be used to describe any electron in a stable atom [and can be mapped back to the classical terminology of Shells and electron orbitals].


Azmithal & Magnetic numbers
Energy levels
0
1
1
+1 0 -1
-1 0 +1
2
2
+2 +1 0 -1 -2
-2 -1 0 +1 +2
3
3
+3 +2 +1 0 -1 -2 -3
-3 -2 -1 0 +1 +2 +3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
8
18
32
Z
32
18
8
2
13 11 9 7 5 3 1
f
2 4 6 8 10 12 14
f
9 7 5 3 1
d
2 4 6 8 10
d
5 3 1
p
2 4 6
p
1
s
2
Atomic Shells
Orbitals & sub-Orbitals

A stable atom has equal numebrs of Protons, electrons [and Neutrons], all following the Pauli Exclusion Principle thus orientating their spins so that each element has a unique electron configuration

PRINCIPAL quantum number

The first describes the electron shell, or energy level, of an atom.

This is the only quantum number
introduced by the Bohr model

atomic shells

n(1-8)

(n = 1, 2, 3, 4 ...)

The principal quantum number
can only have positive integer values

energy levels



As energies of the Baryons comprising the atomic nuclei increases,
the electron bound to each nuclei also possesses more KEM field energies
and is therefore less tightly bound to the nucleus

Atomic Shells



(K, L, M, N, O, P, Q, R)

Atomic shells relate directly to Principal quantum numbers

(1, 2, 3, 4, 5, 6, 7, 8)

Energy levels



AZMITHAL quantum number


orbitals
Shells
N
4
s+p+d+f
M
s+p+d
L
2
s+p
K
1
s
Principal Quantum Number
(1,2,3,4)

The azimuthal quantum number is a quantum number assigned to any atomic orbital that describes its orbital angular momentum and determines the shape of the electron orbital

s p d f

electron orbitals

(l = 0, 1 ... n−1)

ℓ (0-7)
Azimuthal


Shells
S
8
R
s+p
7
Q
s+p+d
6
P
s+p+d+f
5
O
orbitals
Principal Quantum Number
(5,6,7,8)


Azimuthal Quantum number (l)
n 1-4
l = (n-1)
0
1
2
3


Azimuthal Quantum number (l)
n 5-8
l = (n-1)
4
5
6
7

Care must always be taken
to never confuse
Orbital Angular Momentum
[rotation about a point in atoms]
with
Quantised Angular Momenta
[equilateral Planck energy geometries]

MAGNETIC quantum number


Shells
orbitals
electrons per shell
N
4
s+p+d+f
32
M
3
s+p+d
18
L
2
s+p
8
K
1
s
2
Principal Quantum Number
(1,2,3,4)

The magnetic quantum number denotes the energy levels available within any subshell

Magnetic numbers do not continue to increase as the Principal numbers increase instead they reverse after n4 to reflect the charged quanutm geometry of Elements and do not follow the current computer models in popular use


electrons per shell
Shells
2
S
8
R
8
s+p
7
Q
18
s+p+d
6
P
32
s+p+d+f
5
O
orbitals
Principal Quantum Number
(5,6,7,8)

s p d f

electron sub-orbitals

(ml = −l, −l+1 ... 0 ... l−1, l)

ml (2ℓ+1)

Magnetic


Magentic Quantum number (l)
n 1-4
l = (n-1)


Magentic Quantum number (l)
n 5-8
l = (n-1)

Z

120 is the maximum elemental number possible

parallel magnetic moments

Spin UP

higher coupling energies

SPIN quantum number

The spin quantum number is a quantum number that parameterizes
the intrinsic angular momentum (or spin angular momentum),
of any given electron anywhere in an atomic nucleus

anti-parallel magnetic moments

Spin DOWN

lower coupling energies



**Electron spin can orientate in either direction within Nuclei,
providing the nett spins follow the Hund rule and Pauli exclusion principle**


Spin +1/2
KE
μ_B
e-
KE
(ms = −1/2 or +1/2)
Spin -1/2
KE
μ_B
d
p
μ_B
μ_N
(ms = −1/2 or +1/2)
-e
Spin -1/2
Spin +1/2

electron Spin is
referenced to the
Nuclear magneton


n8
n7
n6
n5
n4
n3
n2
n1
−
+

**The nuclear energy levels of the Baryons comprising Elemental nuclei
determine the energy-momenta of electrons bound to them**

Copyright ABRAHAM [2008] - All rights reserved

Modifying Hund's Rule

Electrons fill orbitals in an alternating sequential numbering pattern due to nucleon placement creating opposed direction electron spins

The increased stability of the atom, most commonly manifested in a lower energy state, arises because the high-spin state forces the unpaired electrons to reside in different spatial orbitals.

A commonly given reason for the increased stability of high multiplicity states is that the different occupied spatial orbitals create a larger average distance between electrons, reducing electron-electron repulsion energy. In reality, it has been shown that the actual reason behind the increased stability is a decrease in the screening of electron-nuclear attractions[1].

The total spin state is calculated as the total number of unpaired electrons + 1, or twice the total spin + 1 written as 2s+1.

As a result of Hund's rule, constraints are placed on the way atomic orbitals are filled using the Aufbau principle.

Before any two electrons occupy an orbital in a subshell, other orbitals in the same subshell must first each contain one electron. Also, the electrons filling a subshell will have parallel spin before the shell starts filling up with the opposite spin electrons (after the first orbital gains a second electron).

As a result, when filling up atomic orbitals, the maximum number of unpaired electrons (and hence maximum total spin state) is assured

s	p	d	f
▲ 1 1 2 ▼	▼ 1 1 2 ▲	▲ 1 1 2 ▼	▲ 1 1 2 ▼
	▲ 3 2 4 ▼	▲ 3 2 4 ▼	▲ 3 2 4 ▼
	▼ 5 3 6 ▲	▼ 5 3 6 ▲	▲ 5 3 6 ▼
		▼ 7 4 8 ▲	▲ 7 4 8 ▼
		▼ 9 5 10 ▲	▼ 9 5 10 ▲
			▼ 11 6 12 ▲
			▼ 13 7 14 ▲

▲

Hund's rule of orbital filling
must be modified to reflect
the true orbital filling order

▼



Sub-orbitals fill in order of numbering

Electrons spins pair
before next orbital
is filled

ie.
p1 [DOWN] and p2 [UP] fill
before
p3 [UP] and p4 [DOWN]
before
p5 [DOWN] and p6 [UP] etc

Copyright ABRAHAM [2008] - All rights reserved

Principle quantum Energies



In an atom - electron energies are proportional to their intrinsic Kinetic Energies - which in turn are directly proportional to the quantum energy level of the nuclei which the electron binds to in their respective atomic shells

In a nucleus, lower energy orbits have less 'paired' nuclei supplying energy. The more energy you give a nuclei the faster it casuses the bound electron to rotate. If you give the nuclei enough energy, it will impart eneough energy to its electron for it to leave the system entirely.

The same is true for an electron orbital. Higher values of n mean more energy for the electron and the corresponding KEM field enegies of the electron is larger, resulting in increased angular momentum.

Values of n start at 1 and go up by integer amounts.

If enough energy is added to the system by incident Photons a electron will leave the atom creating a positively charged nuclei [ionisation].





s orbits	n1-8
p orbits	n2-7
d orbits	n3-6
f orbits	n4-5

Eigenstate value

KEM field energy [per n] required to exceed 13.525 eV at which point the photo-electron has sufficient KE to break free of the Nucleus

$$E_n = \frac{E_1}{n^2} = \frac{-13.6eV}{n^2}, n = 1, 2, 3...$$

The possible Kinetic Energies (quantum levels) of an electron are directly related to the energy level of the Nuclei in each Quantum Level

Copyright ABRAHAM [2008] - All rights reserved

Quantum Level 1

K shell

n1

Ground State electron


v
P
KE
c
hv
v^2
1.2e20
0.28 eV

$iE = -13.313\ eV$

The energy levels of bound electrons is determined by Baryons

Z#	Name		Protons	electrons	Neutrons
1	1s1	Deuterium	1	1	1
2	1s2	Helium	2	2	2

2

Deuterium [not Hydrogen] is the building block of elements


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
f
d
p
s
p
d
f




Energy level
1

Z#	Name		Protons	electrons	Neutrons
1	1s1	Hydrogen	1	1	0

Hydrogen is a free radical element



Copyright ABRAHAM [2008] - All rights reserved

Quantum Level 2

L shell

n2

Ground State electron


v
KE
hv
v²
1.2e20
0.8453 eV

$iE = -12.679\ eV$

The energy levels of bound electrons is determined by Baryons

Z #		Name	Protons	electrons	Neutrons
3	2s1	Lithium	3	3	3
4	2s2	Beryllium	4	4	4
5	1p1	Boron	5	5	5
6	1p2	Carbon	6	6	6
7	1p3	Nitrogen	7	7	7
8	1p4	Oxygen	8	8	8
9	1p5	Fluorine	9	9	9
10	1p6	Neon	10	10	10

8

Deuterium [not Hydrogen] is the building block of elements


5
F
2
1
4
O
1
1
Li
1
1
B
2
C
1
2
Be
3
N
2
1
6
Ne
1

Energy level


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
8
f
d
p
s
p
d
f



Copyright ABRAHAM [2008] - All rights reserved

Quantum Level 3

The energy levels of bound electrons is determined by Baryons

Z #		Name	Protons	electrons	Neutrons
11	3s1	Sodium	11	11	11
12	3s2	Magnesium	12	12	12
13	2p1	Aluminium	13	13	13
14	2p2	Silicon	14	14	14
15	2p3	Phosphorus	15	15	15
16	2p4	Sulfur	16	16	16
17	2p5	Chlorine	17	17	17
18	2p6	Argon	18	18	18
21	3d1	Scandium	21	21	21
22	3d2	Titanium	22	22	22
23	3d3	Vanadium	23	23	23
24	3d4	Chromium	24	24	24
25	3d5	Manganese	25	25	25
26	3d6	Iron	26	26	26
27	3d7	Cobalt	27	27	27
28	3d8	Nickel	28	28	28
29	3d9	Copper	29	29	29
30	3d10	Zinc	30	30	30

18

Deuterium [not Hydrogen] is the building block of elements


9
Cu
1
Sc
3
V
7
Co
5
Mn
5
Cl
4
S
1
Na
1
Al
2
Si
2
Mg
3
P
6
Ar
6
Fe
8
Ni
4
Cr
2
Ti
10
Zn

M shell

n3

Ground State electron


v
KE
hv
v²
1.2e20
1.9019 eV

$iE = -11.623\ eV$

Energy level


3
2
1
0
1
2
3
R
8
Q
7
P
6
O
5
N
4
M
18
3
L
2
K
1
f
d
p
s
p
d
f



Copyright ABRAHAM [2008] - All rights reserved

Quantum Level 4

The energy levels of bound electrons is determined by Baryons

Z #		Name	Protons	electrons	Neutrons
19	4s1	Potassium	19	19	19
20	4s2	Calcium	20	20	20
31	4p1	Gallium	31	31	31
32	4p2	Germanium	32	32	32
33	4p3	Arsenic	33	33	33
34	4p4	Selenium	34	34	34
35	4p5	Bromine	35	35	35
36	4p6	Krypton	36	36	36
39	4d1	Yttrium	39	39	39
40	4d2	Zirconium	40	40	40
41	4d3	Niobium	41	41	41
42	4d4	Molybdenum	42	42	42
43	4d5	Technetium	43	43	43
44	4d6	Ruthenium	44	44	44
45	4d7	Rhodium	45	45	45
46	4d8	Palladium	46	46	46
47	4d9	Silver	47	47	47
48	4d10	Cadmium	48	48	48
57	4f1	Lanthanum	57	57	57
58	4f2	Cerium	58	58	58
59	4f3	Praseodymium	59	59	59
60	4f4	Neodymium	60	60	60
61	4f5	Promethium	61	61	61
62	4f6	Samarium	62	62	62
63	4f7	Europium	63	63	63
64	4f8	Gadolinium	64	64	64
65	4f9	Terbium	65	65	65
66	4f10	Dysprosium	66	66	66
67	4f11	Holium	67	67	67
68	4f12	Erbium	68	68	68
69	4f13	Thulium	69	69	69
70	4f14	Ytterbium	70	70	70

32

Deuterium [not Hydrogen] is the building block of elements



3 2 1 0 1 2 3
R 8
Q 7
P 6
O 5
N 32 4
M 3
L 2
K 1
f d p s p d f



1
13
Tm
1
La
3
Pr
1
9
Ag
9
Bk
1
11
Ho
1
1
Y
2
2
3
Nb
2
7
Rh
5
Tc
1
7
Eu
2
5
Br
3
4
3
4
Se
2
1
5
Pm
1
K
3
1
Ga
2
Ge
3
2
Ca
6
Sm
1
2
3
As
3
4
6
Kr
3
2
8
Gd
1
6
Ru
8
Pd
1
12
Er
4
Mo
2
2
2
2
Zr
10
Dy
1
10
Cd
1
4
Nd
2
Ce
1
14
Yb
1

N shell

n4

Ground State electron



v
KE
hv
v²
1.2e20
3.3812 eV

$iE = -10.143\ eV$

Energy level
4



Quantum Level 5

The energy levels of bound electrons is determined by Baryons

Z #		Name	Protons	electrons	Neutrons
37	5s1	Rubidium	37	37	37
38	5s2	Strontium	38	38	38
49	5p1	Indium	49	49	49
50	5p2	Tin	50	50	50
51	5p3	Antimony	51	51	51
52	5p4	Tellurium	52	52	52
53	5p5	Iodine	53	53	53
54	5p6	Xenon	54	54	54
71	5d1	Lutetium	71	71	71
72	5d2	Hafnium	72	72	72
73	5d3	Tantalum	73	73	73
74	5d4	Tungsten	74	74	74
75	5d5	Rhenium	75	75	75
76	5d6	Osmium	76	76	76
77	5d7	Iridium	77	77	77
78	5d8	Platinum	78	78	78
79	5d9	Gold	79	79	79
80	5d10	Mercury	80	80	80
89	5f1	Actinium	89	89	89
90	5f2	Thorium	90	90	90
91	5f3	Protactium	91	91	91
92	5f4	Uranium	92	92	92
93	5f5	Neptunium	93	93	93
94	5f6	Plutonium	94	94	94
95	5f7	Americium	95	95	95
96	5f8	Curium	96	96	96
97	5f9	Berkelium	97	97	97
98	5f10	Californium	98	98	98
99	5f11	Einsteinium	99	99	99
100	5f12	Fermium	100	100	100
101	5f13	Mendelevium	101	101	101
102	5f14	Nobelium	102	102	102

32

Deuterium [not Hydrogen] is the building block of elements


3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
32
f d p s p d f


Md 13
Ac 1
Pa 3
Au 9
Bk 9
Lu 1
Ta 3
Es 11
Ir 7
Re 5
Am 7
I 5
Te 4
Np 5
Rb 1
In 1
Sn 2
Sr 2
Pu 6
Sb 3
Xe 6
Cm 8
Os 6
Pt 8
Fm 12
W 4
Hf 2
Cf 10
Hg 10
U 4
Th 2
No 14

O shell

n5

Ground State electron


v
P
KE
hv
v²
1.2e20
5.5282 eV

$iE = -8.241\ eV$

Energy level




n5
n4
n3
n2
n1

Quantum Level 6

The energy levels of bound electrons is determined by Baryons

Z #		Name	Protons	electrons	Neutrons
55	6s1	Caesium	55	55	55
56	6s2	Barium	56	56	56
81	6p1	Thallium	81	81	81
82	6p2	Lead	82	82	82
83	6p3	Bismuth	83	83	83
84	6p4	Polonium	84	84	84
85	6p5	Astatine	85	85	85
86	6p6	Radon	86	86	86
103	6d1	Lawrencium	103	103	103
104	6d2	Rutherfordium	104	104	104
105	6d3	Dubnium	105	105	105
106	6d4	Seaborgium	106	106	106
107	6d5	Bohrium	107	107	107
108	6d6	Hassium	108	108	108
109	6d7	Meitnerium	109	109	109
110	6d8	Darmstadtium	110	110	110
111	6d9	Roetgenium	111	111	111
112	6d10	Copernicium	112	112	112

18

Deuterium [not Hydrogen] is the building block of elements


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
18
f
d
p
s
p
d
f

Energy level
6


Rg
9
Lr
1
Db
3
Mt
7
Bh
5
At
5
Po
4
Cs
1
Tl
1
Pb
2
Ba
2
Bi
3
Rn
6
Hs
6
Ds
8
Sg
4
Rf
2
Cn
10

P shell

n6

Ground State electron


v
P
KE
hv
v²
1.2e20
7.607 eV

iE = -5.917 eV


n6
n5
n4
n3
n2
n1

Copyright ABRAHAM [2008] - All rights reserved

Quantum Level 7

The energy levels of bound electrons is determined by Baryons

Z #		Name	Protons	electrons	Neutrons
87	7s1	Francium	87	87	87
88	7s2	Radium	88	88	88
113	7p1	Ununtrium	113	113	113
114	7p2	Flerovium	114	114	114
115	7p3	Ununpentium	115	115	115
116	7p4	Livermorium	116	116	116
117	7p5	Ununseptium	117	117	117
118	7p6	Ununoctium	118	118	118

8

Deuterium [not Hydrogen] is the building block of elements

Q shell

n7

Ground State electron


v
p
KE
hv
v²
1.2e20
10.355 eV

$iE = -3.169\ eV$


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f


Uus
5
Lv
4
Fr
1
Uut
1
Fl
2
Ra
2
Uup
3
Uuo
6
7
7
6
6
6
6
6
6


n7
n6
n5
n4
n3
n2
n1

Energy level
7

Copyright ABRAHAM [2008] - All rights reserved

Quantum Level 8

The energy levels of bound electrons is determined by Baryons

Z #		Name	Protons	electrons	Neutrons
119	8s1	Ununnonium	119	119	119
120	8s2	Unbinilium	120	120	120

2

Deuterium [not Hydrogen] is the building block of elements


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
2
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f



Energy level
8

R shell

n8

Ground State electron


v
p
KE
hv
v²
1.2e20
13.525 eV


n8
n7
n6
n5
n4
n3
n2
n1
−
+

Quantum Level Jumps

Photon Absorption and Release


Emission
s p d
f
3
2
1 0


Absorption
s p d
f
3
2
1 0

Photo-electrons can only transition between principal energy Baryons in the atomic nuclei in discrete steps [or quantum jumps] because Baryons determine the KEM energy levels of electrons in nuclei

[see Tetryonic QED for full details on spectral line mechanics]

Initial Quantum level

8	768	756	720	660	576	468	336	180	0
7	588	576	540	480	396	288	156	0	
6	432	420	384	324	240	132	0		
5	300	288	252	192	108	0			
4	192	180	144	84	0				
3	108	96	60	0					
2	48	36	0						
1	12	0							
		12	48	108	192	300	432	588	768
		1	2	3	4	5	6	7	8

Final Quantum level

$$\Delta p = \Delta M v = hf$$

accelerating photo-electrons produce spectral lines

Spectral line transitions


8
un-named
7
Humphries
6
Pfund
5
Brackett
4
Paschen
3
Balmer
2
Lyman
1

Quantum level jumps

Spectral line transitions


v
Δv
Σv
KEM
48
108
192
300
432
588
768
36
60
84
108
132
156
180
36
96
180
288
420
576
756
2
3
4
5
6
hv
c
Mv²

Quantum differentials

hv, R, β, p, KE
Planck, Rydberg, Lorentz, Newton, Leibniz

uniting classical physics and relativity through equilateral geometry

Nuclear energy emission~absorption

If atoms are left undisturbed, their electrons usually fill the lowest available energy levels and stay there, in their "ground state."

Occasionally, however, they may also be pushed up to some higher energy ("become excited") e.g. by a collision with a fast atom or electron, one which got extra speed from an electric voltage or from some source of heat.

An atom/electron elevated to one of its higher "excited levels" soon falls back to a lower level ("undergoes a quantum jump"), emitting a photon whose energy corresponds to the difference between the levels.

That need not be the ground state: the atom/electron might descend to that state in several steps, emitting a photon at each step on the way.


Velocity
v
p
Spectral Lines
KEM Energies
KE
M
hv
v²
12
[0-12]
1.2e20

Quantum transitions

(Orbital Shells - Bound energy states)


Quantum differentials
Lyman
Balmer
Paschen
Brackett
Pfund
Humphries
un-named
12
48
108
192
300
432
588
768
768+
KEM energies
1
2
3
4
5
6
7
8
n
$hf = \Delta Mv = \Delta p$
spectral lines are produced by accelerating electrons
Energy levels
Atomic Shells
n1
hv
KE
1.2e20
0.211 eV
iE= -13.358 eV
1
n2
1.2e20
0.276 eV
iE = -12.679 eV
2
n3
1.2e20
0.375 eV
iE = -11.623 eV
3
n4
1.2e20
0.541eV
iE = -10.143 eV
4
n5
1.2e20
0.845 eV
iE = -8.2417 eV
5
n6
1.2e20
1.502 eV
iE = -5.917 eV
6
n7
1.2e20
3.381 eV
iE = -3.1699 eV
7
n8
1.2e20
13.525 eV
iE = -any eV
8
Quantum level
1 K
2 L
3 M
4 N
5 O
6 P
7 Q
8 R

Quantum levels 1-8
are also referred to as
Atomic Shells K-R

Photo-electrons can only transition in discrete steps [or quantum jumps] within atomic nuclei shells because Baryons determine the KEM energy levels of electrons in nuclei

Any photo-electron bound in a Deuterium nuclei will have specific quantised KEM field energies and angular momenta

Copyright ABRAHAM [2008] - All rights reserved


AZMITHAL
MAGNETIC
electron orbitals
f
d
p
s
magnetic
7
m
5
3
1
Z
2
6
10
s
14
spins
0
1
2
l
3
azmithal
ORBITALS
SUB-ORBITALS

Tetryonics 47.01 - Elemental Orbits

Atomic Orbitals


Energy level
n
Quantum numbers
0
1 1
2 2
3 3
8 R s
7 Q s+p
6 P s+p+d
5 O s+p+d+f
4 N s+p+d+f
3 M s+p+d
2 L s+p
1 K s
l
f f
d d
p p
s
Atomic Shell
electron orbitals


S 2 6 10 14
7 5 3 1 m

An atomic orbital is a mathematical function that describes the wave-like behavior of either one electron or a pair of electrons in an atom

Atomic orbitals are typically categorized by n, l, and m quantum numbers, which correspond to the electron's energy, angular momentum, and an angular momentum vector component, respectively.

Historically used to define the pedagogical electron cloud model of an atom Tetryonics reveals the true geometry of atomic nuclei

Each orbital is defined by a different set of quantum numbers and contains a maximum of two spin opposed electrons.

Aufbau

Azmithal & Magnetic numbers


Energy levels
R 8
Q 7
P 6
O 5
N 4
M 3
L 2
K 1
0
1 1
+1 0 -1 -1 0 +1
2 2
+2 +1 0 -1 -2 -2 -1 0 +1 +2
3 3
+3 +2 +1 0 -1 -2 -3 -3 -2 -1 0 +1 +2 +3
2 8 18 32 32 18 8 2
7 5 3 1 1 3 5 7
13 11 9 7 5 3 1
2 4 6 8 10 12 14
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 2
f f
d d
p p
s
Atomic Shells

Orbitals & sub-Orbitals

Electron Spins can be either up or down providing they obey the Pauli exclusion principle

s Orbital

1 Orbit (2 electrons max)

Alkali Metals & Alkali Earths


Quantum numbers
0
Energy level
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
f
d
p
Atomic shell
s
electron orbitals


Cs
Rb
Fr
D
1
K
Uun
Li
Na
s
1
Ba
Sr
Ra
He
2
Ca
Ub
Be
Mg

		n
azmithal number	0	l
magnetic numbers	0	m
spins	-1/2 +1/2	s



erroneous computer model of 's' electron orbitals


Energy levels
6
5
7
1
8
4
2
3

p Orbital

3 Orbits (6 electrons max)

Non-Metals, Halogens & Nobel gases


Quantum numbers
Energy level
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
-1
0
+1
p
p
p
s
d
f
Atomic shell
electron orbitals


p
At
I
Uus
5
Br
F
Cl
Po
Te
Lv
4
Se
O
S
Tl
In
Uut
1
Ga
B
Al
Pb
Sn
Fl
2
Ge
C
Si
Bi
Sb
Uup
3
As
N
P
Rn
Xe
Uuo
6
Kr
Ne
Ar
1
2
3

				n
azmithal number		1		l
magnetic numbers	-1	0	+1	m
spins	-1/2 +1/2	-1/2 +1/2	-1/2 +1/2	S


z
y
x
p_{-1}
z
y
x
p_0
z
y
x
p_1

erroneous computer model of 'p' electron orbitals

Quantum levels
6
5
7
4
2
3

d Orbital

5 Orbits (10 electrons max)

Transition & post-Transition Metals


Quantum numbers
Energy level
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
-2
-1
0
+1
+2
d
d
d
d
d
f
f
p
p
s
Atomic shell
electron orbitals

						n
azimthal number			2			l
magnetic numbers	-2	-1	0	+1	+2	m
spins	-1/2 +1/2	-1/2 +1/2	-1/2 +1/2	-1/2 +1/2	-1/2 +1/2	s


Rg
Au
9
Ag
Cu
Lr
Lu
1
Y
Sc
Db
Ta
3
Nb
V
Mt
Ir
7
Rh
Co
Bh
Re
5
Tc
Mn
d
1 2 3 4 5
erroneous computer model of 'd' electron orbitals
Hs
Os
6
Ru
Fe
Sg
W
4
Mo
Cr
Cn
Hg
10
Cd
Zn
Rf
Hf
2
Zr
Ti
Ds
Pt
8
Pd
Ni
Quantum levels
5
6
4
3

f Orbital

7 Orbits (14 electrons max)


Quantum numbers
Energy level
R 8
Q 7
P 6
O 5
N 4
M 3
L 2
K 1
-3 -2 -1 0 +1 +2 +3
f f f f f f f
d d
p p
s
Atomic shell
electron orbitals

								n
azmithal number				3				ℓ
magnetic numbers	-3	-2	-1	0	+1	+2	+3	m
spins	-1/2 +1/2	-1/2 +1/2	-1/2 +1/2	-1/2 +1/2	-1/2 +1/2	-1/2 +1/2	-1/2 +1/2	s

Lanthanoids & Actinoids


Md 13 Tm
Ac 1 La
Pa 3 Pr
Bk 9 Tb
Es 11 Ho
Am 7 Eu
Np 5 Pm
f
1 2 3 4 5 6 7
Pu 6 Sm
Cm 8 Gd
Fm 12 Er
Cf 10 Dy
U 4 Nd
Th 2 Ce
No 14 Yb
N μ S
Quantum levels
5
4

erroneous computer model of 'f' electron orbitals

Copyright ABRAHAM [2008] - All rights reserved

Orbital energy variations

All Elements have stable core electron configurations of s & p orbitals for each energy level as revealed through diffraction studies




f
n
d
p
s
orbital energies
l
azimthal
Σ
magnetic
m
electrons per orbital
2
6
10
s
14

As additional nuclei bind to form d & f orbitals they can do so by bonding in many positions, with each location producing different orbital energies for each electron that binds to nuclei in that position



The final energy levels of each orbital is the result of the energy of the Baryons in the nuclei and the spin coupling energies of the photo-electrons bound to them

Electrons per shell



Each energy shell of a periodic element can hold only a fixed number of electrons



Atomic Orbitals

f	d	p	s	p	d	f
5, 11, 3, 13, 1, 9, 7	8, 2, 10, 4, 6	5, 1, 3	1-2	6, 2, 4	7, 1, 9, 3, 5	6, 12, 4, 14, 2, 10, 8

7 + 5 + 3 + 2 + 3 + 5 + 7

Rules governing the allowed combinations of Quantum Numbers

The three quantum numbers (n, l, and m)
that describe an orbital are integers: 0, 1, 2, 3, and so on

n (1-8) Principal (n = 1, 2, 3, 4 ...)	The principal quantum number (n) cannot be zero.
ℓ (0-3) Azimuthal (l = 0, 1 ... n-1)	The angular quantum number (l) can be any integer between 0 and n - 1.
mℓ (2ℓ+1) Magnetic (mℓ = -ℓ, -ℓ+1 ... 0 ... ℓ-1, ℓ)	The magnetic quantum number (m) can be any integer between -l and +l.
ms $\pm\frac{1}{2}$ Spin Projection (ms = -1/2 or +1/2)	The Spin of electrons in any nuclear sub-orbital can only be +1/2 (Spin UP) or -1.2 (Spin DOWN).

Z

1, 2, 3, 4, 5, 6, 7, 8

s, p, d, f

1	2
1, 3, 5	2, 4, 6
1, 3, 5, 7, 9	2, 4, 6, 8, 10
1, 3, 5, 7, 9, 11, 13	2, 4, 6, 8, 10, 12, 14
down up	up down

Quantum Numbers

n	4-5	3-6	2-7	1-8	2-7	3-6	4-5
ℓ	3	2	1	0	1	2	3
m	-3	-2	-1	1	+1	+2	+3
s	+1/2 -1/2	+1/2 -1/2	+1/2 -1/2	+1/2 -1/2	+1/2 -1/2	+1/2 -1/2	+1/2 -1/2

Copyright ABRAHAM [2008] - All rights reserved

Using Tetryonic charged geometries for mass-ENERGY-Matter,
an electron's position and velocity CAN be modelled simultaneously
(but any attempt to measure or interact with it, will affect its component energy-momenta)

Electron Position Uncertainty

Atomic orbitals are typically described as "hydrogen-like" (meaning one-electron) wave functions over any spatial region of measurement, categorized by n, l, and m quantum numbers, which correspond to the electron's energy, angular momentum, and a vector momentum component, respectively

Erwin Schrödinger

(12 August 1887 – 4 January 1961)

Werner Heisenberg

(5 December 1901 – 1 February 1976)

Lepton's are physically Spin 1 fermion particles
that can easily be misconstrued as having entirely different
spin numbers without the correct physical topologies
to base the observed measurements on



The energies of photo-electrons are determined by the Baryons they bind to & incident photons

Quantum Mechanics is a mathematical representation of equilateral energy momenta interactions and the charged geometries of mass-ENERGY-Matter

Determining the motion of electrons bound to atomic nuclei is akin to measuring the motion of variable speed electric fan blades mounted at various heights within a rotating carousel

Leptons are 12 loop quantum rotors



an identical fascia is presented with every 120 degree rotation

their spin number is a measure ment of their magnetic moment

The unique 12 faceted topology of leptons results in an identical EM geometry being oberved for every 120° rotation of the particle

Leading to the interpretation that the Lepton disappears and re-appears when being 'observed' or measured



Every charged radial arm of a Lepton's Matter topology is identical to every other

Making accurate measurement and mathematical modelling of its rotational dynamics & mechanics incorrect without the correct physical topologies

Electron modelling & probability calculations

12
[0-12]
RE
S
KE

Electron positional measurements have proven to be historically difficult to accurately model due to the charged 12π rotating topologies of leptons


2s
6p
p_{-1}
p_0
p_1
10d
d_{-2}
d_{-1}
d_0
d_1
d_2
14f
f_{-3}
f_{-2}
f_{-1}
f_0
f_1
f_2
f_3
x
y
z

Computer generated plots of 'clouds' of electron probabilites are inaccurate mis-representations and should be abandoned in favour of realistic atomic models reflective of the charged geometry of each periodic element

v
RE
KE
P
KE
hv
Q
M
M
v²
c²

Every elemental atom can be viewed as a quantum carousel with a unique number of oscillating fans positioned around it.

Each fan has 3 blades and a fixed speed n[1-8] related to its height above ground level, AND the carousel is turning around on its axis

All periodic elements are made form Deuterium nuclei


0
[42-42]
N⁰
n
e⁻
M
P⁺

The baryonic energies of nuclei determines the energies of bound photo-electrons


Azmithal quantum number
3
2
1
0
1
2
3
8
7
6
5
4
3
2
1
nuclear energy level
2
8
16
32
32
16
8
2
electrons in level
Z
f
d
p
s
p
d
f

The current computer generated electron probability diagrams in popular use at present can now be show to be a misrepresentative model of mathematical modelling of electron sub-orbital energies

The nuclear quantum levels [n], intrinsic quantised angular momentum [h] and orbital angular momentum [l] of each electron bound within atomic nuclei are all the direct result of the Baryonic energies of the nuclei they are bound to

Each level of the quantum carousel can contain only a limited number of fans each running at a specific speed

Imagine trying to measure (or model) the motion of any 1 quantum scale blade while the carousel rotates

Copyright ABRAHAM [2008] - All rights reserved


AUFBAU
FILLING
quantum numbers
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Atomic Shells
8
7
6
5
4
3
2
1
Energy levels
2
8
18
32
32
18
8
2
Z
f
d
p
s
p
d
f
electron orbitals
BUILDING THE ELEMENTS

Tetryonics 48.01 - aufbau geometry

Quantum Topologies




0
2
1
8
1
2
18
2
3
32
3
32
f
f
18
d
d
Z
8
p
p
2
s


Electron
Neutron
Nucleus
Proton

Dalton Model

Quantum Model

Thomson Model

Rutherford Model



Historically viewed as a spherical object
Tetryonic charge geometry has finally revealed the
true quantum topology of all atoms


proton
neutron

Element numbers

The rule dictating how many nuclei form each Atomic shell is known as the Aufbau principle.

The physical and chemical properties of elements is determined by the atomic structure.
The atomic structure is, in turn, determined by the electrons and
which shells, subshells and orbitals they reside in.

The maximum periodic elemental number is 120

$$Z = \sum^{1\,2\,3\,4}_{4\,3\,2\,1} 2(n^2) = 2 + 8 + 18 + 32 + 32 + 18 + 8 + 2$$

Number of nuclei per level	Element #
2	120 119
8	118 111
18	110 93
32	92 61
32	60 29
18	28 11
8	10 3
2	2 1

The number of nuclei per quantum level is reflective of photonic energy levels and provides the foundational geometry for all of the periodic elements

The number of possible nuclei in each Quantum level follows aufbau principle 'numbers' which can be determined using the following summation formula


Element Number
Level
Nuclei
R 8 s 2 2
Q 7 s + p 2+6 8
P 6 s + p + d 2+6+10 18
O 5 s + p + d + f 2+6+10+14 32
N 4 s + p + d + f 2+6+10+14 32
M 3 s + p + d 2+6+10 18
L 2 s + p 2+6 8
K 1 s 2 2
Z
Shell
orbitals
sub-orbitals

Deuterium is the building block of all elements

Each element has equal numbers of Protons, electron & Neutrons with their stored mass-energies making up the molar masses of elements not excess neutron as currently modelled

Copyright ABRAHAM [2008] - All rights reserved

Aufbau Principle

(Nuclei number and position)

1 Sub-Orbit (2 electrons max) ○ s

3 Sub-Orbits (6 electrons max) ○ p

○ d *5 Sub-Orbits (10 electrons max)*

○ f *7 Sub-Orbits (14 electrons max)*


Azmithal quantum number
3 2 1 0 1 2 3
atomic shells
R 2
Q 2+6
P 2+6+10
O 2+6+10+14
N 2+6+10+14
M 2+6+10
L 2+6
K 2
8s
s+p 7s 7p
s+p+d 6s 6p 6d
s+p+d+f 5s 5p 5d 5f
s+p+d+f 4s 4p 4d 4f
s+p+d 3s 3p 3d
s+p 2s 2p
1s
2 8
8 7
18 6
32 5
32 4
18 3
8 2
2 1
energy level
f d p s p d f
7 + 5 + 3 + 2 + 3 + 5 + 7

2 6 10 14

Nuclei	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	Quantum number	per level
R	119	120																															8	2
Q	87	88	113	114	115	116	117	118																									7	8
P	55	56	81	82	83	84	85	86	103	104	105	106	107	108	109	110	111	112															6	18
O	37	38	49	50	51	52	53	54	71	72	73	74	75	76	77	78	79	80	89	90	91	92	93	94	95	96	97	98	99	100	101	102	5	32
N	19	20	31	32	33	34	35	36	39	40	41	42	43	44	45	46	47	48	57	58	59	60	61	62	63	64	65	66	67	68	69	70	4	32
M	11	12	13	14	15	16	17	18	21	22	23	24	25	26	27	28	29	30															3	18
L	3	4	5	6	7	8	9	10																									2	8
K	1	2																															1	2
Shells	*s1*	*s2*	*p1*	*p2*	*p3*	*p4*	*p5*	*p6*	*d1*	*d2*	*d3*	*d4*	*d5*	*d6*	*d7*	*d8*	*d9*	*d10*	*f1*	*f2*	*f3*	*f4*	*f5*	*f6*	*f7*	*f8*	*f9*	*f10*	*f11*	*f12*	*f13*	*f14*		

sub-orbitals

A specific nuclear energy is associated with each electron configuration and, upon certain conditions, bound electrons are able to move from one orbital to another by emission or absorption of a quantum of energy, in the form of a photon.

The Aufbau principle can also be used to model the binding configuration of Protons and Neutrons in an atomic nucleus, according to their specific Baryonic Energy levels, in turn revealing the quantum geometry of all periodic Elements

Wolfgang Pauli

(25 April 1900 – 15 December 1958)


Azmithal quantum number
3 2 1 0 1 2 3
R Q P O N M L K
8s
7s 7p
6s 6p 6d
5s 5p 5d 5f
4s 4p 4d 4f
3s 3p 3d
2s 2p
1s
8 7 6 5 4 3 2 1
energy level
f d p s p d f

Friedrich Hermann Hund

(4 February 1896 - 31 March 1997)

The orbitals of lower energy are filled in first with the electrons and only then are the higher energy orbitals filled.

aufbau electron orbital filling

Orbitals of equal energy are each occupied by one electron before any orbital is occupied by a second electron, and all electrons in singly occupied orbitals must have the same spin state


Azmithal & Magnetic numbers
Energy levels
3 2 1 0 1 2 3
+3 +2 +1 0 -1 -2 -3 +2 +1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0 +1 +2 -3 -2 -1 0 +1 +2 +3
R 60 60 8
Q 59 58 57 44 44 57 58 59 7
P 56 55 54 53 52 43 42 41 28 28 41 42 43 52 53 54 55 56 6
O 51 50 49 48 47 46 45 40 39 38 37 36 27 26 25 19 19 25 26 27 36 37 38 39 40 45 46 47 48 49 50 51 5
N 35 34 33 32 31 30 29 24 23 22 21 20 18 17 16 10 10 16 17 18 20 21 22 23 24 29 30 31 32 33 34 35 4
M 15 14 13 12 11 9 8 7 6 6 7 8 9 11 12 13 14 15 3
L 5 4 3 2 2 3 4 5 2
K 1 1 1
13 11 9 7 5 3 1 2 4 6 8 10 12 14
f f
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
Atomic Shells
Orbitals & sub-Orbitals

Aufbau construction


60
7
5
4
14
f
5
6
5
4
3
20
d
3
7
6
5
4
3
2
18
p
1
8
7
6
5
4
3
2
1
8
s

Proton
base
Hemisphere


3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
2
8
18
32
32
18
8
2
α
8
7
6
5
4
3
2
1
f d p s p d f


Azmithal & Magnetic numbers
Energy levels
0
1
1
2
2
3
3
R
Q
P
O
N
M
L
K
2
8
18
32
32
18
8
2
Z
8
7
6
5
4
3
2
1
13 11 9 7 5 3 1
f
9 7 5 3 1
d
5 4 1
p
1 s 2
2 3 6
p
2 4 6 8 10
d
2 4 6 8 10 12 14
f
α Hemisphere Orbitals
β Hemisphere Orbitals
Atomic Shells
Orbitals & sub-Orbitals


3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
2
8
18
32
32
18
8
2
β
8
7
6
5
4
3
2
1
f d p s p d f

Neutron
base
Hemisphere


1
8
7
6
5
4
3
2
1
8
s
3
7
6
5
4
3
2
18
p
5
6
5
4
3
20
d
7
14
5
4
f
60



Atomic Weights

[Molar mass-energies]

The table does not illustrate the quark compositions of the baryonic nuclei in elements

The Mendeleev table incorrectly positions Hydrogen as Element 1 in the table and does not show Deuterium [the building block of all Elements]

The Mendeleev block arrangement of periodic elements presents a number of problems in representing the true topologies and properties of all the periodic elements:

It provides no insight into the individual topologies of the periodic elements themselves

The physical dimensions of periodic elements and the electron orbitals of each element are not represented by the table

The table does not reflect elemental quantum numbers as defined by Schrodinger's wave equation

The table provides no additional insights or information on nuclei packing, aufbau element building processes or how nuclei energies contribute to total molar mass

Tetryonic charge geometry can rectify all of these deficiencies

Tetryonics 49.01 - Atomic Weight

Copyright ABRAHAM [2008] - All rights reserved

Atomic nuclei mass-energies

Each element's weight [mass-Matter in a gravitational field] is the result of the total quanta comprising that element

Baryon mass-energies

n

E

The quantum level mass-energies of Baryons determines the kinetic energies of electrons

1n - 1 e19v

electron KEM field

hv^2



73,728	n32	v8	3.268969693 e15
69,192	n31	v7	2.502804921 e15
64,800	n30	v6	1.838795452 e15
60,552	n29	v5	1.276941286 e15
56,448	n28	v4	8.172424232 e14
52,488	n27	v3	4.596988631 e14
48,672	n26	v2	2.043106058 e14
45,000	n25	v1	5.107765145 e13

Compton frequencies

930 MeV

1.2 e20
electron rest Matter is velocity invariant

496 keV

spectral frequencies

13.6 eV



The nuclei forming each atomic shell have specific mass-energy quanta

Baryon rest masses — lepton rest mass — KEM

$$\overset{8}{\underset{1}{n}}\left[\,[72(n)^2]+[12e19]+[m_e v^2]\,\right]$$

Deuterium mass-energy per shell

Despite having differing mass-energies each Deuterium nuclei has the same velocity invariant Matter geometry [84π]

spin orbital coupling in synchronous quantum convertors

Electrons act as quantum scale rotating armatures in atomic nuclei and can only have specific energies reflective of the electron orbital energy level of the Baryons in which they are found

They acheive these energy levels by absorbing or emitting photons to acheive the specific angular momentum required

Hydrogen Ionisation Energies [/n^2]


free electron
>13.525 eV
K.E
n8+
Quantum numbers
0
1
1
2
2
3
3
f
f
d
d
p
p
s
electron orbitals
atomic shells
energy levels
emission
absorption
hv
n
n0
R
Q
P
O
N
M
L
K
768
588
432
300
192
108
48
12
0.21 eV
0.27 eV
0.37 eV
0.54 eV
0.84 eV
1.50 eV
3.38 eV
13.5 eV
8
7
6
5
4
3
2
1

13.6eV
Free electron

768	R	0.21 eV	8	5.107765145 e13
588	Q	0.27 eV	7	6.671366720 e13
432	P	0.37 eV	6	9.078047137 e13
300	O	0.54 eV	5	1.307587877 e14
192	N	0.84 eV	4	2.043106058 e14
108	M	1.50 eV	3	3.632188548 e14
48	L	3.38 eV	2	8.172424234 e14
12	K	13.5 eV	1	3.268969693 e15

Planck quanta

Spectral line series frequencies
[Hydrogen]

accelerating electrons $Mv^2 = KEM = hv^2$ produce spectral lines

Copyright ABRAHAM [2008] - All rights reserved

Redefining Atomic weights

Atomic weight (symbol: Ar) is a dimensionless physical quantity,
the ratio of the average mass of atoms of an element (from a given source) to
1/12 of the mass of an atom of carbon-12 (known as the unified atomic mass unit)

Carbon 12



6 Protons [24-12]
6 Neutrons [18-18] n1
6 electrons [0-12]

The 'unified atomic mass unit' currently in use
is known to be inaccurate and must be corrected
in order to bring clarity & increased accuracy
to the atomic weights of all elements

$$\boxed{A_r = 22{,}512 \quad \text{Hydrogen}}$$

Defining Hydrogen as having an exact
atomic Planck mass of 22512n quanta
provides uniformity with Tetryonics

$1/12\ C_{12}$

$A_r = 22{,}506$



1.660096209e-27 kg

1 Proton [24-12]
n1
.5 electron 0-6

Unified atomic Matter unit



1.660538783e-27 kg

1 Proton [24-12]
n1
1 electron [0-12]

Deuterium is the building block of all elements in the period table

$$\boxed{A_r = 45{,}012 \quad \text{Deuterium}}$$

Defining Deuterium as having an exact
atomic Planck mass of 45012n quanta
reflects the true charged geometries
of all Elements & their topologies

D

1/6 C



3.320192418e-27 kg

1 Proton [24-12]
1 Neutron [18-18] n1
1 electron [0-12]

Planck mass-energy units

NAu = 0.001 kg


48
[24-24]
22,512
e-
P+
^{1}H

1.660538841 e-27 kg

One Da is approximately equal to the mass of one proton or one neutron


36
[18-18]
22,500
N^0
0.499866702 H

1.659653693 e-27 kg


36
[24-12]
22,500
P^+
0.499866702 H

Deuterium is the building block of all elements


84
[42-42]
45,012
N^0
e-
P+
^{2}H

3.320192534 e-27 kg

The unified atomic mass unit (symbol: u) or Dalton (symbol: Da)
is a unit that is used for indicating mass on an atomic or molecular scale

270,072

1/12 the mass of a C12 graphene atom at rest in its electronic ground state

1.660538782(83)×10−27 kg

22,506

is an inaccurate means of determining the exact rest mass of a Hydrogen atom

22,512

Carbon 12 has 270,072n planck quanta
(270,072 / 12 = 22,506)

Hydrogen has a mass of 22,512n (22,500+12) requiring all mass to be calculated directly using the Planck mass-energy quantum (.001kg / N_A / 22,512) & Tetryonic charge geometries

Using Tetryonic theory to define
n Planck mass = $7.376238634 \times 10^{-32}$ Kg
(see Tetryonics QM 15.04)

exact atomic rest masses for all particles, elements and compounds can be determined directly from atomic theory

N_A = 6.02214179 e23

The mole is the amount of substance of a system which contains as many elementary entities as there are atoms in 0.012 kilogram of carbon 12; its symbol is "mol".

NA(12u) = 0.012 kg


504
[254-254]
12
C
11.996
C_{12}
270,072
6 [s1]

6 Protons	[24-12]	n1
6 Neutrons	[18-18]	
6 electrons	[0-12]	

Carbon has a number of differing atomic configurations (allotropes)

6 Protons	[24-12]	n1-2
6 Neutrons	[18-18]	
6 electrons	[0-12]	


504
[252-252]
6
C
12.6493
284,760
[He] 2s2 2p2

Copyright ABRAHAM [2008] - All rights reserved

Planck mass-energy contributions to the measured weights of periodic, elementary mass-Matter topologies



1.659653693 e-27 kg



8.851486361 e-31 kg



2.411109611 e-35 kg



Baryons have 2,25e23 Planck quanta comprising their rest Matter topologies

[930.974 MeV]

Δ 1875 x

[496.5 keV]

Leptons have 1.2 e20 Planck quanta comprising their rest Matter topologies

[496.5 keV]

Δ 36,711 x

[13.6 eV]

Photons are planar geometries [Matter-less]
(purely Kinetic mass-Energy and momenta)

The Lyman alpha spectral line mass-energy contribution to the mass of a Deuterium nucleus is negligible

Electron quantum level energies are determined by the energy of the Nuclei they bind to in elements



Photons contribute spectral mass-energies to the nuclei mass but are themselves Matterless [2D zero rest mass-energies]

Photons are 2π charge mass-energy geometries

Tetryonics 49.06 - Planck mass contributions in Elements

Ionisation energies

Fractional quantum differentials


RE
M+KE
$Mv^2 = KEM = p^2$
Lyman
Balmer
Paschen
Brackett
Pfund
Humphries
un-named
12
48
108
192
300
432
588
768
972
KEM energies
1
2
3
4
5
6
7
8
ε_0
n

$$hf = \Delta M v = \Delta p$$

spectral lines are produced by accelerating electrons

Note: this is an Illustrative schema for modelling KEM field energies
All KEM fields possess the same physical spatial geometry
in radial-time defined spatial co-ordinate systems

c^2 c^4




Higher energies
S up
e
S down
Lower Energies

Photo-electrons absorb/emit spectral energies

$$E = eV = \frac{1}{4\pi\epsilon_0}\frac{ne^2}{a}$$

photo-electronic energy momenta


RE
KE
v
p
Spectral Lines
KEM Energies
KE
M
hv
v^2
Q
M
12
[0-12]
1.2e20
1
4
9
16
25
36
49
64
12
48
108
192
300
432
588
768

Mapping photo-electron transition energies to Tetryonic energy momenta geometries reveals many key facts about the ionisation energies of nuclei

$$E = -\frac{Z^2}{n^2}\frac{ke^2}{2a_0} = -\frac{13.6Z^2}{n^2}eV$$

The differing fractional KEM field energy momenta of electrons that results from their transitions to specific energy nuclei in elements results in differing QAM quanta and produces spectral lines and fine line splitting

Spectral line transitions


Δv
Σv
KEM
Quantum differentials
36
60
84
108
132
156
180
36
96
180
288
420
576
756
48
108
192
300
432
588
768
hv
v
c
v²
Mv²

hv, R, β, p, KE
Planck, Rydberg, Lorentz, Newton, Leibniz

uniting classical physics and relativity
through equilateral geometry

Elementary ionisation energies



The term ionization energy (EI) of an atom or molecule is the minimal KEM field energy required to remove (or unbind) one mole of electrons from one mole of gaseous atoms isolated in in any spatial region and in its ground energy state.

The term "ionization energy" is sometimes used as a name for the work needed to remove (or un-bind) the highest energy photoelectron from an atom or molecule.

However, due to interactions with surfaces, this value differs from the ionization energy of the atom or molecule in question when it is located by itself in free space.

So, in the case of surface-adsorbed atoms and molecules, it may be better to use the more general term "electron binding energy", in order to avoid confusion.

Both these names are also sometimes used to describe the work needed to remove an electron from a "lower" orbital (i.e., not the topmost orbital) for both free and adsorbed atoms; in such cases it is necessary to specify the orbital from which the electron has been removed

$$E = -\frac{Z^2}{n^2}\frac{ke^2}{2a_0} = -\frac{13.6Z^2}{n^2}eV$$

Every electron in each elementary orbit has a unique ionisation energy



Element number

Nuclei	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	Energy level	per shell
R	119	120																															8	2
Q	87	88	113	114	115	116	117	118																									7	8
P	55	56	81	82	83	84	85	86	103	104	105	106	107	108	109	110	111	112															6	18
O	37	38	49	50	51	52	53	54	71	72	73	74	75	76	77	78	79	80	89	90	91	92	93	94	95	96	97	98	99	100	101	102	5	32
N	19	20	31	32	33	34	35	36	39	40	41	42	43	44	45	46	47	48	57	58	59	60	61	62	63	64	65	66	67	68	69	70	4	32
M	11	12	13	14	15	16	17	18	21	22	23	24	25	26	27	28	29	30															3	18
L	3	4	5	6	7	8	9	10																									2	8
K	1	2																															1	2
Shells	s		p						d										f															
	s1	s2	p1	p2	p3	p4	p5	p6	d1	d2	d3	d4	d5	d6	d7	d8	d9	d10	f1	f2	f3	f4	f5	f6	f7	f8	f9	f10	f11	f12	f13	f14		

Orbitals

sub-orbitals

Copyright ABRAHAM [2008] - All rights reserved

Hyperfine splitting and Lamb Shifts

When the spectral lines of the hydrogen spectrum are examined at very high resolution, they are found to be closely-spaced doublets.
This splitting is called fine structure and was one of the first experimental evidences for electron spin.

The fine structure describes the splitting of the spectral lines of atoms due to first order relativistic corrections [principal quantum energies]

n

Differing electron spins within shells & quantum levels produces Hyperfine splitting


f13
f1
f3
d9
d1
d3
f9
f11
f7
f5
p4
d7
d5
s1
p5
s p d
f
p1
n
lms
14
10 6 2
p2
p6
s2
d6
d8
p3
f6
f8
d4
d2
d10
f12
f10
f4
f2
f14

The electron energy levels of Hydrogen should depend only on the principal quantum number n.

In 1951 it was discovered that this was not so, the $2p_{(1/2)}$ state is slightly less than the $2s_{(1/2)}$ state resulting in the Lamb shift

ℓ m s

Differing electron sub-Orbtial energies create Lamb Shifts


R
Q
P
O
N
M
L
K
8s
1s
8
7
6
5
4
3
2
1

atomic shell energies result from Series addition of baryonic energies

If you measure the atomic energy levels of photo-electrons at an extremely high resolution, you'll find small deviations of individual KEM field energies of electrons in sub-orbitals which are primarily the result of parallel and anti-parallel electron spins


Spin UP
μB
KE
μN
N Nuclear Magneton S
KE
μB
Spin DOWN

Higher energy
Parallel
Magnetic moments

Lower energy
Anti-parallel
Magnetic moments

All electron spins are referenced to the Nuclear magneton


3
2
1
0
1
2
3
2p
2s
2p
f
d
p
s
p
d
f

electron sub-orbital energies are Parallel energy configurations

Copyright ABRAHAM [2008] - All rights reserved

M_0

3D Matter topologies are comprised of charged 2D mass-energies

Energy per second²


E
ρ
c⁴
seconds²

$$\overset{\text{Matter}}{\frac{T\pi}{c^4}}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

mass-Matter

standing wave mass-energiescreate
the material substance of all chemical elements

RE

Relativistic mass-ENERGY-Matter

Relativity fails at the foundational level to explain and differentiate between mass-ENERGY and Matter in physical systems


Schrodinger's quantum numbers
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
electron shells
Q
[v-v]
RE
M₀
KE
2
8
18
32
32
18
8
2
8
7
6
5
4
3
2
1
energy levels
f
d
p
c⁴
p
d
f
Bohr's atomic orbitals

Einstein's relativistic [Lorentz corrected] stress energy tensor aggregates all forms of energy into a single energy density gradient

$$\text{atomic energies}\quad Tm\frac{n}{c^4} + m\frac{v^2}{c^2}\quad\text{electron spins}$$

3D rest Matter + Lorentz corrected 2D Kinetic Energies = total Relativistic Energies

KE

2D equilateral mass-energies are euclidean geometries

Energy per second

E
ρ
c²
seconds

$$\overset{\text{mass}}{\frac{n\pi}{c^2}}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

mass-energies

radiant planar mass-energies create
EM fields, spectral lines & chemical interactions

Deuterium is the building block of all Elements (save Hydrogen)

The geometry of any Element is determined by its Charge

The Molar Weight of any Element is a measure of its standing wave mass-energies



The rest mass-Matter of any Element is determined by the total number of quanta making up the Protons, Neutrons and electrons that comprise them (in their respective energy levels)

Any mass-energies in excess of the molar [n1] weight is a measurement of a element's CHEMICAL energies

Important point to note:

The Kinetic Energy difference between any Element's total [n1] Deuteron mass-energies and its Molar mass has historically been incorrectly explained as resulting from an excess number of Neutrons in the atom it is not. Z# = (number of Protons = number of electrons = number of Neutrons)

Elementary mass-Matter

R

∑

K

	n per nuclei 1e19v = n	
2	2 nuclei [74,496 ea]	120 Unbinilium 119 Ununennium
	+	
8	8 nuclei [69,780 ea]	118 Ununoctium 87 Francium
	+	
18	18 nuclei [65,232 ea]	112 Copernicium 55 Caesium
	+	
32	32 nuclei [60,852 ea]	102 Nobelium 37 Rubidium
	+	
32	32 nuclei [56,640 ea]	70 Ytterbuim 19 Potassium
	+	
18	18 nuclei [52,596 ea]	30 Zinc 11 Sodium
	+	
8	8 nuclei [48,720 ea]	10 Neon 3 Lithium
	+	
2	2 nuclei [45,012 ea]	2 Helium 1 Deuterium

The rest mass-Matter of any Element is the sum total of its constituent Z[n²] energy level Deuterium nuclei

Aufbau

$$Z\#\left[\begin{array}{ll} z \text{ Protons} & [24\text{-}12] \\ z \text{ Neutrons} & [18\text{-}18] \\ z \text{ electrons} & [0\text{-}12] \end{array}\right] n1\text{-}8$$

(ie Calcium [20] = 2+8+10 n level Deuterium nuclei)

Copyright ABRAHAM [2008] - All rights reserved

Periodic Harmonic motions

$x = A\cos(\omega t + \varphi)$

Circular motion


96°
96°
32
32
Z
18
18
54°
54°
8
2 2
8
24°
24°
6° 6°

circular harmonic motion

Circular motions describe the motion of a body with a changing velocity vector [the result of an acceleration force].

Much of the math in of modern physics is predicated on the assumption that π [where it appears] is related to the properties of a circle



$$P\sum 2(n^2)$$

Simple harmonic motion can be visualized as the projection of uniform circular motion onto one axis

Principal Quantum Numbers


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
2
8
18
32
Z
32
18
8
2
M₀
KE
8
7
6
5
4
3
2
1
electron shells
energy levels
f
d
p
s
p
d
f

Sub-orbitals

$F = -kx$

Linear motion


2
8
18
32
Z
32
18
8
2

simple harmonic motion

Nuclei per shell in elements follows a 'periodic summation rule' that is reflective of photonic energies

Copyright ABRAHAM [2008] - All rights reserved

$$\sum_{K}^{R}$$

nuclei per shell

$$\sideset{_{K}^{R}}{}{\text{P}}\sum Z$$

Periodic Summation

Periodic summation is a notation developed for Tetryonic theory to model the geometric series addtion of Z[n²] energy level Deuterium nuclei that form the periodic elements

$$\sum_{1}^{120} Z$$

element number

STEP ONE

Periodic summation follows the atomic shell electron config

STEP TWO

Periodic elements build up following the aufbau sequence

$$\text{P}\sum_{K}^{R} 2(x^2) =$$

1 2 3 4 4 3 2 1



$\text{P}\sum R = 2$	2 nuclei [74,496 ea]	120	Unbinilium
+			
$\text{P}\sum Q = 8$	8 nuclei [69,780 ea]	118	Ununoctium
+			
$\text{P}\sum P = 18$	18 nuclei [65,232 ea]	110	Darmstadtium
+			
$\text{P}\sum O = 32$	32 nuclei [60,852 ea]	92	Uranium
+			
$\text{P}\sum N = 32$	32 nuclei [56,640 ea]	60	Neodymuim
+			
$\text{P}\sum M = 18$	18 nuclei [52,596 ea]	28	Argon
+			
$\text{P}\sum L = 8$	8 nuclei [48,720 ea]	10	Neon
+			
$\text{P}\sum K = 2$	2 nuclei [45,012 ea]	2	Helium
		0	Hydrogen

Each atomic shell can hold only a fixed number of deuterium nuclei

THe LHS of the notation determine the number of nuclei in each atomic shell, from the periodic mass-energy levels for atoms, and the RHS follows the aufbau building principle to determine the rest mass-Matter of any specific element

Aufbau

Each periodic element is made of Z [n²energy] deuterium nuclei

$$Z\# \left[\begin{array}{ll} z \text{ Protons} & [24\text{-}12] \\ z \text{ Neutrons} & [18\text{-}18] \\ z \text{ electrons} & [0\text{-}12] \end{array}\right] n1\text{-}8$$

Planck mass-energies form the surface integral of rest Matter topologies for each periodic element

Copyright ABRAHAM [2008] - All rights reserved

Element numbers

Nuclei per shell in elements follow
a 'periodic summation rule'
that is reflective of
photonic energies

1 2 3 4 4 3 2 1

$$P\sum_{K}^{R} 2(x^2) = 2 + 8 + 18 + 32 + 32 + 18 + 8 + 2$$

Z

120	Unbinilium	n8
119	Ununennium	
118	Ununoctium	n7
87	Francium	
112	Copernicium	n6
55	Caesium	
102	Nobelium	n5
37	Rubidium	
70	Ytterbuim	n4
19	Potassium	
30	Zinc	n3
11	Sodium	
10	Neon	n2
3	Lithium	
2	Helium	n1
1	Deuterium	
0	Hydrogen	


Principal Quantum Numbers
3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
electron shells
Q
[v-Y]
RE
M0
KE
2
8
18
32
Z
32
18
8
2
8
7
6
5
4
3
2
1
energy levels
f d p s p d f
Sub-orbitals

Periodic mass-ENERGY-Matter

Following periodic summation rules for shell filling
n[1-8] quantum energy deuterium nuclei
combine to form elementary Matter

$$P\sum_{K\;25}^{R\;32}\left[\overset{\text{Baryon rest masses}}{[72(n)^2]}+\overset{\text{lepton rest mass}}{[12e19]}+\overset{\text{KEM}}{[m_e v^2]}\right]_1^8$$

Deuterium mass-energy per shell

The measured weight of Matter in gravitational fields is the result of
planar mass-energies in tetryonic standing-wave geometries

The periodicity of all the elements,
along with their exact molar rest mass-energies and
quantum wavefunctions can be described with Tetryonic geometries

Ionisation energies

γ


Un-named series
Humphries series
Pfund series
Brackett series
Paschen series
Balmer series
Lyman series
Spectral Lines

$$Mv^2 = KEM = hcR_H$$

Photon emission/absorption

Photo-electron ionisation energies


n
unbound photo-electron
Continuous spectrum
v²/c²
8
7
6
5
4
3
2
1
η 756
ζ 576
ε 420
δ 288
γ 180
β 96
α 36
-13.525 eV
Lyman
ζ 720
ε 540
δ 384
γ 252
β 144
α 60
-3.381 eV
Balmer
ε 660
δ 480
γ 324
β 192
α 84
-1.502 eV
Paschen
δ 576
γ 396
β 240
α 108
-0.845 eV
Brackett
γ 468
β 288
α 132
-0.541 eV
Pfund
β 336
α 156
-0.375 eV
Humphries
α 180
-0.276 eV
Un-named
-0.211 eV
Full levels
180
+
156
+
132
+
108
+
84
+
60
+
36
768
588
432
300
192
108
48
12
K
L
M
N
O
P
Q
R


3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
α
8
7
6
5
4
3
2
1
2
8
18
32
32
18
8
2
f d p s p d f

Opposed electron spins results in Hyperfine splitting & Lamb shifts


3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
β
8
7
6
5
4
3
2
1
2
8
18
32
32
18
8
2
f d p s p d f


Azmithal & Magnetic numbers
Energy levels
0
1
+1 0 -1
-1 0 +1
2
+2 +1 0 -1 -2
-2 -1 0 +1 +2
3
+3 +2 +1 0 -1 -2 -3
-3 -2 -1 0 +1 +2 +3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
8
18
32
32
18
8
2
Z
13 11 9 7 5 3 1
2 4 6 8 10 12 14
f
f
9 7 5 3 1
2 4 6 8 10
d
d
5 3 1
2 4 6
p
p
1 2
s
Atomic Shells
Orbitals & sub-Orbitals

Eigenstate - Ionisation energies


Atomic shells
P
O
Q
K
N
R
L
M
n
s1
s2
p1
p2
p3
p4
p5
p6
d1
d2
d3
d4
d5
d6
d7
d8
d9
d10
f1
f2
f3
f4
f5
f6
f7
f8
f9
f10
f11
f12
f13
f14
6
5
7
1
4
8
2
3
Quantum numbers


Azmithal & magnetic numbers
3
2
1
0
1
2
3
2
+
8
+
18
+
32
+
32
+
18
+
8
+
2
nuclei per shell
atomic shells
R
Q
P
O
N
M
L
K
8s
7s
7p
6s
6p
6d
5s
5p
5d
5f
4s
4p
4d
4f
3s
3p
3d
2s
2p
1s
f
d
p
s
p
d
f
8
7
6
5
4
3
2
1
energy level
120
119
118
111
110
93
92
61
60
29
28
11
10
3
2
1
element number

The ionisation energies of individual atoms varies due to many factors, namely:
electron spin-orbital coupling with Baryons of specific energies,
the relativistic energies of photo-electrons bound in nuclei
and Zitterbewegung effects on bound electrons

First ionisation energies for all periodic elements

$$E = -\frac{Z^2}{n^2}\frac{ke^2}{2a_0} = -\frac{13.6Z^2}{n^2}eV$$



Copyright ABRAHAM [2008] - All rights reserved

Proton - Neutron Curve

The graph below is a plot of neutron number against proton number.
It is used as rule to determine which nuclei are stable or unstable.



Plot of Baryon numbers based on excess Neutron model of periodic elements

Deviation from Tetryonic plot is the result of the intrinsic mass-energies of each particle comprising the atomic nucleus

Plot of Baryonic nuclei numbers based on Tetryonic topologies of periodic elements

Historically, Proton-electron numbers are viewed as being equivalent in neutral elementary matter with the excess molar mass measured being the result of 'excess or extra' Neutrons in the atom

Atomic Nuclei Numbers

All periodic elements have an EQUAL number of Protons, Neutrons & Electrons with their molar mass-Matter being determined by their quantum level mass-energies



Tetryonic modelling of the charged mass-ENERGY-Matter topologies of elementary atoms and the nuclei that comprise them, reveals a DIRECT LINEAR relationship for the number of Protons-electrons-Neutrons in all periodic elements and nuclear isotopes

Planck mass-energy contributions to elementary Matter and isotopes

The mass-energy content of Deuterium nuclei creates the molar mass of elements
[not extra neutrons in excess of the elemental number]


Deuteron
electron
eV
KEM
Z
32
3,050.6 MeV
31
2,5862.9 MeV
30
2,6811 MeV
29
2,505.4 MeV
28
2,335.6 MeV
27
2,171.8 MeV
26
2,013.9 MeV
25
1,861.9 MeV
8
7
6
5
4
3
2
1
En = -13.52 eV
En = -10.35 eV
En = -7.60 eV
En = -5.28 eV
En = -3.38 eV
En = -1.90 eV
En = -0.84 eV
En = -0.21 eV
291,166
285,065
262,158
213,887
133,697
58,940
19,840
3,725
496.519 keV
n
Quantum levels
v²
2H⁺
291,107 MeV
Elemental mass-Matter
[in MeV]
59,580 keV
e
6,101 MeV
993 keV
En = -27.05 eV
22,903 MeV
3,972 keV
En = -82.8 eV
48,262 MeV
8,937 keV
En = -136.8 eV
80,174 MeV
15,888 keV
En = -168.96 eV
74,740 MeV
15,888 keV
En = -108.16 eV
39,092 MeV
8,937 keV
En = -340 eV
16,111 MeV
3,972 keV
En = -6.72 eV
3,724 MeV
993 keV
En = -0.42 eV
565.11 keV
KEM field mass-energies
[in eV]
KE
2 + 8 + 18 + 32 + 32 + 18 + 8 + 2
nuclei number per shell
electron shells
R
Q
P
O
N
M
L
K
Schrodinger's quantum numbers
3
2
1
0
1
2
3
Q
[v·v]
RE
Z
2
8
18
32
32
18
8
2
M₀
KE
c⁴
8
7
6
5
4
3
2
1
energy levels
f
d
p
p
d
f
Bohr's atomic orbitals

n1
Elementary nuclei

are comprised of equal numbers of
Protons, Neutrons & electrons
with varying energy levels

Baryons		electrons		KEM fields
930.947 MeV	+	496.519 keV	+	13.525 ev

The mass-energy content of Matter topologies is velocity invariant

The mass-energy content of Baryons determines the KEM field of electrons

Baryons **930.947 MeV** + **KEM fields** **13.525 ev** + **electrons** **496.519 keV**

Mapping Planck mass-energy contributions to elementary Matter and isotopes


Schrodinger's quantum numbers
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
electron shells
Q
[v-v]
RE
2
8
18
32
Z
32
18
8
2
M_0
KE
8
7
6
5
4
3
2
1
energy levels
f
d
p
c^4
p
d
f
Bohr's atomic orbitals

$$E = hv^2$$

$$n^2 + v^2 + e = Z$$

general form quatratic equation

$$ax^2 + bx + c = Z$$

$$E = nhv$$


E
polar aufbau

polar energy spirals courtesy of Rene Cormier

Identifying electron rest Matter topologies as velocity invariant we can re-arrange the component Planck mass-energy geometry formulation of periodic elements to

$$h\left[\underset{\text{Deuteron rest mass}}{72[v^2]} + \underset{\text{Spectral lines}}{v} + \underset{\text{electron rest mass}}{1.20\text{ e}20\text{ }v}\right]$$

reveal a quadratic formulation for all Z numbers

Copyright ABRAHAM [2008] - All rights reserved

All elements are comprised of n level Duetrium nuclei

Baryons **KEM fields** **electrons**

Z [[72n²] + [12v²] + [1.2e20]]

1,861,949 MeV **13.525 eV** **496,519 keV**

The atomic shell energy levels of Deuterium nuclei in elements



Deuteron	electron eV	KEM
32 3,050.6 MeV	8	En = -13.52 eV
31 2,5862.9 MeV	7	En = -10.35 eV
30 2,6811 MeV	6	En = -7.60 eV
29 2,505.4 MeV	5	En = -5.28 eV
28 2,335.6 MeV	4	En = -3.38 eV
27 2,171.8 MeV	3	En = -1.90 eV
26 2,013.9 MeV	2	En = -0.84 eV
25 1,861.9 MeV	1	En = -0.21 eV

496.519 keV

m v²

Determines the spectral line [KEM field energies] of electrons bound to them



atomic shells					nuclei per shell
R	**3,050.6 MeV**	13.525 eV	Z [[72*32n²] + [12*8v²] + [1.2e20]]	496,519 keV	2
					+
Q	**2,862.9 MeV**	10.35 eV	Z [[72*31n²] + [12*7v²] + [1.2e20]]	496,519 keV	8
					+
P	**2,681.2 MeV**	7.60 eV	Z [[72*30n²] + [12*6v²] + [1.2e20]]	496,519 keV	18
					+
O	**2,505.4 MeV**	5.28 eV	Z [[72*29n²] + [12*5v²] + [1.2e20]]	496,519 keV	32
					+
N	**2,335.6 MeV**	3.38 eV	Z [[72*28n²] + [12*4v²] + [1.2e20]]	496,519 keV	32
					+
M	**2,171.7 MeV**	1.90 eV	Z [[72*27n²] + [12*3v²] + [1.2e20]]	496,519 keV	18
					+
L	**2,013.8 MeV**	0.84 eV	Z [[72*26n²] + [12*2v²] + [1.2e20]]	496,519 keV	8
					+
K	**1861.9 MeV**	0.21 eV	Z [[72*25n²] + [12*1v²] + [1.2e20]]	496,519 keV	2

The relativistic rest mass-energy-Matter of all periodic elements

is the sum of the mass-energies of all atomic nuclei and spectral lines that comprise its mass-Matter topology as measured in any spatial co-ordinate system per unit of time

$2H^+$ Z γ

[72n²] $[M_e v^2]$

Elemental mass-Matter [in MeV]

6,101 MeV
993 keV
En = -27.05 eV
+
22,903 MeV
3,972 keV
En = -82.8 eV
+
48,262 MeV
8,937 keV
En = -316.8 eV
+
80,174 MeV
15,888 keV
En = -168.96 eV
+
74,740 MeV
15,888 keV
En = -108.16 eV
+
39,092 MeV
8,937 keV
En = -34.2 eV
+
16,111 MeV
3,972 keV
En = -6.72 eV
+
3,724 MeV
993 keV
En = -0.42 eV

[1.2e20]]

e

the rest mass-Matter of bound photo-electrons is velocity invariant

Tetryonics 50.10 - rest masses in atomic Matter

Copyright ABRAHAM [2008] - All rights reserved

48
H
1.0000
22,512

Avagadro's number

6.022141579 e26
atoms in 1KG of Matter

1 KG mass
[of Matter]

1.660538841 e-27 kg
atomic rest mass-Matter

Hydrogen

01

using SI units Avagadro's number can be expressed exactly as the inverse rest mass of Hydrogen

504
C
11.996
C12
270,072

Carbon

12

Weighted atomic mass

5.019789213 e25
atoms in 1KG of Matter

6.02214078 e 23

1.99211552 e-26 kg
atomic rest mass-Matter

Tetryonic charge geometries make weighted atomic mass measurements and calculations obsolete

22,506 1/12 of Carbon 12 [Graphene] is not equal to 1 Hydrogen atom 22,512
(Deuterium is the building block of all atomic elements]



Silicon



28

International Avagadro project

1.966225348 e25
atoms in 1KG of Matter

5.085887033 e-26 kg
atomic rest mass-Matter

The gram was originally defined in 1795 as the mass of one cubic centimeter of water at 4°C,
making the kilogram equal to the mass of one liter of water.

The prototype kilogram, manufactured in 1799 and from which the current kilogram is based
has a mass equal to the mass of 1.000025 liters of water

In recent years two major experiments, namely the Watt balance & Avagadro projects, have been attempting to
measure and define 1KG of mass-Matter in terms of electrical force and the number of atoms respectively
in order to better define 1KG of mass-Matter precisely for all future physical references

Platinum

191

6,552
Pt
4,329,864
818,028

La Grande K

2.817950081 e24 atoms in 1KG of Matter	90%	Pt	3.1893811012 e-25 kg atomic rest mass-Matter
3.181804449 e23	10%	Ir	3.142870708 e-25 kg

The La grande K is an alloy of 90% Platinum & 10% Iridium
that has been slowly losing mass since its manufacture

All atomic rest masses are for atoms at absolute zero and any deviation is a measure of
the topological Matter's Kinetic energy content [chemical energy, KEM fields and/or spectral lines]

Copyright ABRAHAM [2008] - All rights reserved


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
f 7
d 5
p 3
s 1
1-14 Actinoid
1-14 Lanthanoid
9-10 Post Transition Metal
1-8 Transition Metal
6 Noble Gas
5 Halogen
1-4 Non-Metal Metaloid Poor-Metal
2 Alkaline Earth
1 Alkali Metal
Shells
Energy levels
Orbitals
sub orbital
Family

Incorporating

- *Quark configurations*
- *Nuclei geometries*
- *Chemical bond points*
- *Atomic Orbitals*
- *Hund Rule*
- *Pauli exclusion*
- *Aufbau filling principle*
- *Element names, numbers and*
- *Elementary families*

Element placements that reflects the true quantum geometries of periodic elements

● UP Quark

● DOWN Quark


azmithal & magnetic quantum numbers
+3
+2
+1
0
-1
-2
-3
Atomic shells
R
Q
P
O
N
M
L
K
energy levels
8
7
6
5
4
3
2
1
2
8
18
32
32
18
8
2
Z
1,3,5,7,9,11,13
1,3,5,7,9
1,3,5
1-2
2,4,6
2,4,6,8,10
2,4,6,8,10,12,14
f
d
p
s
p
d
f
electron orbitals & sub-orbitals


n
ℓ spd f
ms
14 10 6 2
Md Tm 13
Ac La 1
Pa Pr 3
Rg Au Ag Cu 9
Lr Lu Y Sc 1
Db Ta Nb V 3
Bk Tb 9
Es Ho 11
Mt Ir Rh Co 7
Bh Re Tc Mn 5
Am Eu 7
Np Pm 5
At I Uus Br Cl F 5
Po Te Uuh Se S O 4
Cs Rb Fr K Uun Na Li D 1
Tl In Uut Ga Al B 1
Pb Sn Uuq Ge Si C 2
Ba Sr Ra Ca Ub Mg He Be 2
Bi Sb Uup As P N 3
Rn Xe Uuo Kr Ar Ne 6
Pu Sm 6
Cm Gd 8
Hs Os Ru Fe 6
Ds Pt Pd Ni 8
Fm Er 12
Cf Dy 10
Sg W Mo Cr 4
Rf Hf Zr Ti 2
Cn Hg Cd Zn 10
U Nd 4
Th Ce 2
No Yb 14

6
7
8
3
2
1
5
4
Energy levels

Periodic Table 2.0

(the quantum geometry of periodic elements)


P
Q
R
M
L
K
O
N
Atomic shells


48
[24-24]
H
1.0000
22,512
[1.660538841 e-27 kg]
KE
Hydrogen
0
R
Q
P
O
N
M
L
K
1/2
8
7
6
5
4
3
2
1
Shell
Nuclei
h
Humphries series
Pfund series
Brackett series
Paschen series
Balmer series
Lyman series
Orbitals & sub-orbitals
atomic shell
energy level

Baryonic energies
and photon interactions
determine Lepton energies

electron configuration
1s1

Hydrogen is NOT a periodic element
[Deuterium is the building block of elements]

Aufbau

R	5.107765145 e13	8
Q	6.671366720 e13	7
P	9.078047137 e13	6
O	1.307587877 e14	5
N	2.043106058 e14	4
M	3.632188548 e14	3
L	8.172424234 e14	2
K	3.268969693 e15	1

13.525 eV
photo-electron
ionisation energy

Tetryonics 51.00 - Hydrogen atom


84
[42-42]
D
1.9995
45,012
[3.320192534 e-27 kg]
electron configuration
1s1
Deuterium
01
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
1
f d p s p d f
01
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
n1
Alkali Metal
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
1
s
atomic shell
Orbital & sub-orbitals
energy level

Tetryonics 51.01 - Deuterium atom

Copyright ABRAHAM [2008] - All rights reserved


168
[84-84]
He
3.9989
1
1
He
2
1
90,024
[6.640385068 e-27 kg]
Helium
02
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
2
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f
electron configuration
1s2
Aufbau
02
Potons [24-12]
Neutrons [18-18]
electrons [0-12]
m1
Alkaline
Earth
Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
2
1
s
2
atomic shell
Orbital & sub-orbitals
energy level

Tetryonics 51.02 - Helium atom

Copyright ABRAHAM [2008] - All rights reserved


252
[126-126]
Li
6.1615
1
2
Li
138,708
[1.023143308 e-26 kg]
3,672
[0.1519 GeV]
electron configuration
[He] 2s1
2
Lithium
03
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
3
f d p s p d f
03 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-2
Alkali Metal
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
1
2
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.03 - Lithium atom

Copyright ABRAHAM [2008] - All rights reserved


336
[168-168]
Be
8.3241
2
1
2
Be
2
187,392
[1.3822481e-26 kg]
7,344
[0..303 GeV]
electron configuration
[He] 2s2
Aufbau
Beryllium
04
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
4
KE
f d p s p d f
04
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-2
Alkaline Earth
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
2
2
1 s 2
Orbital & sub-orbitals
atomic shell
energy level

Tetryonics 51.04 - Beryllium atom

Copyright ABRAHAM [2008] - All rights reserved


420
[210-210]
B
10.4867
1
1
B
2
2
1
2
236,076
[1.741352851 e-26 kg]
11,016
[0.455 GeV]
electron configuration
[He] 2s2 2p1
Aufbau
Boron
05
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
5
f d p s p d f
05
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-2
Metaloid
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
1
0
-1
1
3
2
p
1
s
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.05 - Boron atom

Copyright ABRAHAM [2008] - All rights reserved


504
[252-252]
C
12.6493
1
2
284,760
[2.100457713 e-26 kg]
14,688
[0.6077 GeV]
electron configuration
[He] 2s2 2p2
2
Aufbau
Carbon
06
3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
6
f d p s p d f
06
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-2
Metaloid
Azmithal & Magnetic numbers
1 0 1
-1
-1
4
2
p
s
p
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.06 - Carbon atom


588
[294-294]
N
14.8118
333.444
[2.4659562515 e-26 kg]
18,360
[0.759 GeV]
Nitrogen
07
electron configuration
[He] 2s2 2p3
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
7
f d p s p d f
07 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-2
Metaloid
Azmithal & Magnetic numbers
1 0 1
0 -1 -1
5
2
3 1 2
p p
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.07 - Nitrogen atom

Copyright ABRAHAM [2008] - All rights reserved


672
[336-336]
O
16.9744
382,128
[2.818667317 e-26 kg]
22,032
[0.9116 GeV]
Oxygen
08
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
8
f d p s p d f
electron configuration
[He] 2s2 2p4
2
Aufbau
08 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-2
Metaloid
Azmithal & Magnetic numbers
1 0 1
0 -1 -1 0
6
2
3 1 2 4
p p
1 s 2
Orbitals & sub-orbitals
atomic shell
energy level

Tetryonics 51.08 - Oxygen atom

Copyright ABRAHAM [2008] - All rights reserved


756
[378-378]
F
19.1370
430,812
[3.177772119 e-26 kg]
25,704
[1.063 GeV]
Fluorine
09
electron configuration
Aufbau
[He] 2s2 2p5
2
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
9
f d p s p d f
09
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-2
Halogen
Azmithal & Magnetic numbers
1 0 1
+1 0 -1 -1 0
7
2
5 3 1 2 4
p s p
1 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.09 - Fluorine atom


840
[420-420]
Ne
21.2996
5
4
1
2
1
2
3
6
Ne
479,496
[3.53687692 e-26 kg]
29,376
[1.2155 GeV]
electron configuration
[He] 2s2 2p6
Aufbau
Neon
10
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
10
f d p s p d f
10 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-2
Noble Gas
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
1 0 1
+1 0 -1 -1 0 +1
8
2
5 3 1 2 4 6
p
1 s 2
p
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.10 - Neon atom

Copyright ABRAHAM [2008] - All rights reserved


924
[462-462]
Na
23.6317
5
4
3
1
Na
1
2
2
3
6
531,996
[3.924129448 e-26 kg]
36,864
[1.5253 GeV]
electron configuration
Aufbau
[Ne] 3s1
10
Sodium
11
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
11 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-3
Alkali Metal
Azmithal & Magnetic numbers
0
1
1
+1 0 -1
-1 0 +1
1
8
2
5 3 1
2 4 6
p
p
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.11 - Sodium atom


1,008
[504-504]
Mg
25.9838
5
4
3
1
2
1
2
Mg
3
6
584,496
[4.31138l977 e-26 kg]
44,352
[1.835 GeV]
Magnesium
12
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
12
f d p s p d f
electron configuration
[Ne] 3s2
10
Aufbau
12
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-3
Alkaline Earth
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
1
1
+1 0 -1
-1 0 +1
2
8
2
5 3 1
2 4 6
p
p
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.12 - Magnesium atom


1,092
[546-546]
Al
28.2958
636,996
[4.698634505 e-26 kg]
51,840
[2.3450 GeV]
Aluminium
13
electron configuration
[Ne] 3s2 3p1
10
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
13
f d p s p d f
13 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-3
Metaloid
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
-1
1
1
+1 0 -1 0 +1
3
8
2
5 3 1 2 4 6
p
p
1 s 2
Orbitals & sub-orbitals
atomic shell
energy level

Tetryonics 51.13 - Aluminium atom


1,176
[588-588]
Si
30.6279
Si
689,496
[5.085887033 e -26 kg]
59,328
[2.4548 GeV]
Silicon
14
electron configuration
[Ne] 3s2 3p2
10
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
14
f d p s p d f
14 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-3
Metaloid
Azmithal & Magnetic numbers
0
1 1
-1 -1
+1 0 0 +1
4
8
2
5 3 1 2 4 6
p p
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.14 - Silicon atom


1,260
[630-630]
P
32.9600
741,996
[5.473139562 e-26 kg]
66,816
[2.7646 GeV]
electron configuration
[Ne] 3s2 3p3
10
Phosphorus
15
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
15
f d p s p d f
15 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-3
Metaloid
Aufbau
Azmithal & Magnetic numbers
1 0 1
0 -1 -1 0
+1 +1
5
8
2
5 3 1 2 4 6
p p
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.15 - Phosphorus atom

Copyright ABRAHAM [2008] - All rights reserved


1,344
[672-672]
S
35.2821
5
4
S
3
2
1
1
2
2
3
6
3
2
1
2
1
2
3
2
1
794,496
[5.86039209 e-26 kg]
74,304
[3.074 GeV]
Sulfur
16
3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
16
f d p s p d f
electron configuration
[Ne] 3s2 3p4
10
16
Potons [24-12]
Neutrons [18-18]
electons [0-12]
m1-3
Metaloid
Aufbau
Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
1 0 1
0 -1 -1 0
+1 +1
6
8
2
5 3 1 2 4 6
p p
1 s 2
Orbitals & sub-orbitals
atomic shell
energy level

Tetryonics 51.16 - Sulfur atom

Copyright ABRAHAM [2008] - All rights reserved


1,428
[714-714]
Cl
37.6242
5
Cl
4
1
1
2
2
3
6
846,996
[6.247644618 e-26 kg]
81,792
[3.6384 GeV]
Chlorine
17
3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
17
f d p s p d f
electron configuration
[Ne] 3s2 3p5
10
Aufbau
17 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-3
Halogen
Azmithal & Magnetic numbers
1 0 1
+1 0 -1 -1 0 +1
7
8
2
5 3 1 2 4 6
p p
1 s 2
Orbitals & sub-orbitals
atomic shell
energy level

Tetryonics 51.17 - Chlorine atom


1,512
[756-756]
Ar
39.9563
1
2
3
4
5
6
Ar
899,496
[6.634897147 e-26 kg]
89,280
[3.694 GeV]
Argon
18
electron configuration
[Ne] 3s2 3p6
10
Aufbau
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
8
7
6
5
4
3
2
1
18
f
d
p
s
p
d
f
18
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
n1-3
Noble Gas
Azmithal & Magnetic numbers
1
0
1
+1
0
-1
-1
0
+1
8
8
2
5
3
1
2
4
6
p
p
1
s
2
Orbitals & sub-orbitals
atomic shell
energy level

Tetryonics 51.18 - Argon atom

Copyright ABRAHAM [2008] - All rights reserved


1,596
[798-798]
K
42.4643
955,956
[7.05135958 e-26 kg]
100,728
[4.167 GeV]
Potassium
19
electron configuration
[Ar] 4s1
18
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
19 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-4
Alkali Metal
Azmithal & Magnetic numbers
0
1
1
+1 0 -1
-1 0 +1
1
8
8
2
5 3 1
2 4 6
p
p
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.19 - Potassium atom


1,680
[840-840]
Ca
44.9723
5
4
1
1
2
Ca
2
3
6
2
4
1,012,416
[7.467822013 e-26 kg]
112,176
[4.641 GeV]
Calcium
20
3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
M
KE
20
8 7 6 5 4 3 2 1
f d p s p d f
electron configuration
[Ar] 4s2
18
Aufbau
20 Protons [24-12] Neutrons [18-18] electrons [0-12] m1-4
Alkaline Earth
Azmithal & Magnetic numbers
R Q P O N M L K
0
1
+1 0 -1
2
8
8
2
1
-1 0 +1
5 3 1
p
2 4 6
p
1 2
s
8 7 6 5 4 3 2 1
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.20 - Calcium atom


1,764
[882-882]
Sc
47.3044
1
Sc
5
4
1
2
3
6
1,064,916
[7.855074541 e-26 kg]
119,664
[4.951 GeV]
Scandium
21
electron configuration
[Ar] 3d1 4s2
18
Aufbau
3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
21
8
7
6
5
4
3
2
1
f d p s p d f
21
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-4
Transition
Metal
Azmithal & Magnetic numbers
0
1
1
-2 +1 0 -1 -1 0 +1
2
2
9
8
2
d
5 3 1 2 4 6
p
p
1 s 2
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.21 - Scandium atom


1,848
[924-924]
Ti
49.6365
1,117,416
[8.242327069 e-26 kg]
127,152
[5.261 GeV]
Titanium
22
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
22
f d p s p d f
22
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-4
Transition Metal
electron configuration
[Ar] 3d2 4s2
18
Aufbau
Azmithal & Magnetic numbers
0
1
1
2
2
2
10
8
2
-2 +1 0 -1 -1 0 +1 -2
d
d
p
p
s
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.22 - Titanium atom

Copyright ABRAHAM [2008] - All rights reserved


1,932
[966-966]
Va
51.9886
1,169,916
[8.629579598 e-26 kg]
134,640
[5.570 GeV]
Vanadium
23
electron configuration
[Ar] 3d3 4s2
18
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
23 Protons [24-12] Neutrons [18-18] electrons [0-12] m1-4
Transition Metal
Azmithal & Magnetic numbers
0
2 1 1 2
-1 -2 +1 0 -1 -1 0 +1 -2
2
11
8
2
d p s p d
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.23 - Vanadium atom


2,016
[1,008-1,008]
Cr
54.3008
1,222,416
[9.016832126 e-26 kg]
142,128
[5.880 GeV]
Chromium
24
electron configuration
[Ar] 3d4 4s2
18
Aufbau
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f
24
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-4
Transition Metal
Azmithal & Magnetic numbers
0
2
1
1
2
-2
+1
0
-1
-1
0
+1
-2
-1
2
12
8
2
d
p
s
p
d
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.24 - Chromium atom

Copyright ABRAHAM [2008] - All rights reserved


2,100
[1,050-1,050]
Mn
56.6327
Mn
1,274,916
[9.404084654 e-26 kg]
149,616
[6.190 GeV]
Manganese
25
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
25
f d p s p d f
electron configuration
[Ar] 3d5 4s2
18
Aufbau
25 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4
Transition Metal
Azmithal & Magnetic numbers
0
2 1 1 2
2
13
8
2
d p s p d
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.25 - Manganese atom


2,184
[1,092-1,092]
Fe
58.9648
1,327,416
[9.791337183 e-26 kg]
157,104
[6,500 GeV]
Iron
26
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
[Ar] 3d6 4s2
18
Aufbau
26 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4
Transition Metal
Azmithal & Magnetic numbers
0
2 1 1 2
2
14
8
2
d p s p d
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.26 - Iron atom


2,268
[1,134-1,134]
Co
61.2969
7
Co
1.379,916
[1.017858971 e-25 kg]
164,592
[6.810 GeV]

Cobalt

27


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
8
7
6
5
4
3
2
1
27
f
d
p
s
p
d
f

electron configuration

[Ar] 3d7 4s2
18

27 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4

Transition Metal

Aufbau

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
2
1
1
2
+1
0
-1
-2
+1
0
-1
-1
0
+1
-2
-1
0
2
15
8
2
7
5
3
1
2
4
6
d
d
5
3
1
2
4
6
p
p
1
s
2
atomic shell
energy level

Orbital & sub-orbitals

Tetryonics 51.27 - Cobalt atom


2,352
[1,176-1,176]
Ni
63.6290
1,432,416
[1.056584224 e-25 kg]
172,080
[7,110 GeV]
Nickel
28
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
[Ar] 3d8 4s2
18
Aufbau
28 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-4
Transition Metal
Azmithal & Magnetic numbers
0
2
16
8
2
d
p
s
Orbital & sub-orbitals
atomic shell
energy level

Tetryonics 51.28 - Nickel atom

Copyright ABRAHAM [2008] - All rights reserved


2,436
[1,218-1,218]
Cu
65.9811
1,484,916
[1.095309477 e-25 kg]
179,568
[7.429 GeV]
Copper
29
electron configuration
[Ar] 3d9 4s2
18
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
29 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-4
Post Transition Metal
Azmithal & Magnetic numbers
2 17 8 2
d p s p d
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.29 - Copper atom


2,520
[1,260-1,260]
Zn
68.2932
9
1
3
7
5
5
4
1
1
2
2
3
6
6
8
4
2
10
Zn
1,537,416
[1.13403473 e-25 kg]
187,056
[7.739 GeV]

Zinc

30


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
30
f
d
p
s
p
d
f

electron configuration

[Ar] 3d10 4s2
18

30 [Protons [24-12] / Neutrons [18-18] / electrons [0-12]] m1-4

Post Transition Metal

Aufbau


Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
2
1
1
2
+2
+1
0
-1
-2
+1
0
-1
-1
0
+1
-2
-1
0
+1
+2
2
18
8
2
9
7
5
3
1
2
4
6
8
10
d
d
5
3
1
2
4
6
p
p
1
s
2
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.30 - Zinc atom


2,604
[1,302-1,302]
Ga
70.8012
1,593,876
[1.175680973 e-25 kg]
198,504
[8.213 GeV]
Ga
9
1
3
7
5
5
4
1
1
2
2
6
3
6
8
4
2
10

electron configuration

[Ar] 3d10 4s2 4p1
18

Gallium

31


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
31
f
d
p
s
p
d
f

31 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4

Metaloid

Aufbau


Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
-1
2
1
1
2
+2
+1
0
-1
-2
+1
0
-1
0
+1
-2
-1
0
+1
+2
3
18
8
2
9
7
5
3
1
2
4
6
8
10
d
d
5
3
1
2
4
6
p
p
1
2
s
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.31 - Gallium atom

Copyright ABRAHAM [2008] - All rights reserved


2,688
[1,344-1,344]
Ge
73.3092
Ge
1,650,336
[1.217327216 e-25 kg]
209,952
[8,687 GeV]
Germanium
32
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
f d p s p d f
Q
RE
M
KE
32
electron configuration
[Ar] 3d10 4s2 4p2
18
Aufbau
32 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4
Metaloid
Azmithal & Magnetic numbers
0
2
1
1
2
4
18
8
2
d
p
s
p
d
atomic shell
Orbital & sub-orbitals
energy level

Tetryonics 51.32 - Germanium atom


2,772
[1,386-1,386]
As
75.8172
1,706,796
[1.258973460 e-25 kg]
221,400
[9.160 GeV]
Arsenic
33
Q
RE
M
KE
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
f d p s p d f
electron configuration
Aufbau
[Ar] 3d10 4s2 4p3
18
33 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4
Metaloid
Azmithal & Magnetic numbers
5
18
8
2
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.33 - Arsenic atom


2,856
[1,428-1,428]
Se
78.3252
1,763,256
[1.30069703 e-25 kg]
232,848
[9.634 GeV]
Selenium
34
electron configuration
[Ar] 3d10 4s2 4p4
18
Aufbau
R
Q
P
O
N
M
L
K
3 2 1 0 1 2 3
8
7
6
5
4
3
2
1
Q
RE
M
KE
f d p s p d f
34 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4
Metaloid
Azmithal & Magnetic numbers
6
18
8
2
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.34 - Selenium atom

Copyright ABRAHAM [2008] - All rights reserved


2,940
[1,470-1,470]
Br
80.8332
1,819,716
[1.342265946 e-25 kg]
244,296
[10.108 GeV]
Bromine
35
electron configuration
[Ar] 3d10 4s2 4p5
36
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
35
35 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4
Halogen
Azmithal & Magnetic numbers
2 1 0 1 2
+2 +1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0 +1 +2
7
18
8
2
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.35 - Bromine atom


3,024
[1,512-1,512]
Kr
83.3412
1,876,176
[1.383912190 e-25kg]
255,744
[10.582 GeV]
Krypton
36
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
36
f d p s p d f
electron configuration
[Ar] 3d10 4s2 4p6
36
Aufbau
36 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4
Noble Gas
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
2 1 0 1 2
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
8
18
8
2
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
d
d
p
p
1 s 2
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.36 - Krypton atom


3,108
[1,554-1,554]
Rb
86.0315
Rb
1,936,740
[1.428585641 e-25 kg]
271,296
[11.225 GeV]
Rubidium
37
electron configuration
[Kr] 5s1
36
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
37
f d p s p d f
37
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-5
Alkali
Metal
Azmithal & Magnetic numbers
0
1
1
2
2
+1 0 -1
-1 0 +1
+2 +1 0 -1 -2
-2 -1 0 +1 +2
1
8
18
8
2
9 7 5 3 1
2 4 6 8 10
d
d
5 3 1
2 4 6
p
p
1 s 2
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.37 - Rubidium atom

Copyright ABRAHAM [2008] - All rights reserved


3,192
[1,596-1,596]
Sr
88.7218
Sr
1,997,304
[1.473259093 e-25 kg]
286,848
[11.868 GeV]
Strontium
38
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
38
f d p s p d f
electron configuration
[Kr] 5s2
36
Aufbau
38 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-5
Alkaline Earth
Azmithal & Magnetic numbers
0
1 1
2 2
+1 0 -1 -1 0 +1
+2 +1 0 -1 -2 -2 -1 0 +1 +2
2
8
18
8
2
9 7 5 3 1 2 4 6 8 10
5 3 1 2 4 6
1 2
d d
p p
s
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.38 - Strontium atom


3,276
[1,638-1,638]
Yt
91.2297
2,053,764
[1.514905336 e-25 kg]
298,296
[12.342 GeV]
electron configuration
[Kr] 4d1 5s2
36
Aufbau
Yttrium
39
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
39 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5
Transition Metal
Azmithal & Magnetic numbers
0
1 1
2 2
-2 +1 0 -1
-1 0 +1
+2 +1 0 -1
-2 -1 0 +1 +2
2
9
18
8
2
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 2
d d
p p
s
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.39 - Yttrium atom

Copyright ABRAHAM [2008] - All rights reserved


3,360
[1,680-1,680]
Zr
93.7377
9
1
3
7
5
2
1
1
5
5
4
3
1
3
1
1
2
3
3
2
3
6
5
3
1
3
1
6
8
4
2
1
1
2
10
Zr
2,110,224
[1.556551580 e-25 kg]
309,744
[12.816 GeV]

Zirconium

40


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
40
f
d
p
s
p
d
f

electron configuration

[Kr] 4d2 5s2
36

40 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5

Transition Metal

Aufbau

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
2
2
-2
+1
0
-1
-1
0
+1
-2
+2
+1
0
-1
-1
0
+1
+2
2
10
18
8
2
9
7
5
3
1
2
4
6
8
10
5
3
1
2
4
6
1
2
d
d
p
p
s
atomic shell
energy level

Orbital & sub-orbitals

Tetryonics 51.40 - Zirconium atom


3,444
[1,722-1,722]
Nb
92.2457
9
1
3
Nb
7
5
5
4
1
1
2
2
3
6
8
4
10
2
2,166,684
[1.598197823 e-25 kg]
321,192
[13.289 GeV]

Niobium

41


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
41
f
d
p
s
p
d
f

electron configuration

[Kr] 4d3 5s2

36

41 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5

Transition Metal

Aufbau

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
2
2
-1
-2
+1
0
-1
-1
0
+1
-2
+2
+1
0
-1
0
+1
+2
2
11
18
8
2
9
7
5
3
1
2
4
6
8
10
d
d
5
3
1
2
4
6
p
p
1
s
2
atomic shell
energy level

Orbitals & sub-orbitals

Tetryonics 51.41 - Niobium atom

Copyright ABRAHAM [2008] - All rights reserved


3,528
[1,764-1,764]
Mo
98.7537
2,223,144
[1.639844066 e-25 kg]
332,640
[13.763 GeV]
Molybdenum
42
electron configuration
[Kr] 4d4 5s2
36
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
42 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5
Transition Metal
Azmithal & Magnetic numbers
0
1
1
2
2
2
12
18
8
2
d
d
p
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.42 - Molybdenum atom


3,612
[1,806-1,806]
Tc
101.2617
2,279,604
[11.6814903 e-25 kg]
344,088
[14.237 GeV]
Technetium
43
R
Q
P
O
N
M
L
K
Q
RE
M
KE
3 2 1 0 1 2 3
8 7 6 5 4 3 2 1
f d p s p d f
electron configuration
[Kr] 4d5 5s2
36
Aufbau
43 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5
Transition Metal
Azmithal & Magnetic numbers
2
13
18
8
2
d
p
s
atomic shell
Orbitals & sub-orbitals
energy level

Tetryonics 51.43 - Technetium atom

Copyright ABRAHAM [2008] - All rights reserved


3,696
[1,848-1,848]
Ru
103.7697
Ru
2,336,064
[1.72326553 e-25 kg]
355,536
[14.710 GeV]
Ruthenium
44
3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
M
KE
8 7 6 5 4 3 2 1
44
f d p s p d f
44
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-5
Transition Metal
electron configuration
[Kr] 4d6 5s2
36
Aufbau
Azmithal & Magnetic numbers
R Q P O N M L K
0
2
14
18
8
2
d
p
s
p
d
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.44 - Ruthenium atom


3,780
[1,890-1,890]
Rh
106.2777
Rh
9
1
3
7
5
5
4
1
1
2
2
3
6
6
8
4
2
10
2,392,524
[1.764782796 e-25 kg]
366,984
[15.184 GeV]
Rhodium
45
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
45
f d p s p d f
electron configuration
[Kr] 4d7 5s2
36
Aufbau
45 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5
Transition Metal
Azmithal & Magnetic numbers
0
2 1 1 2
+1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0
+2 +1 +2
2
15
18
8
2
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.45 - Rhodium atom

Copyright ABRAHAM [2008] - All rights reserved


3,864
[1,932-21,932]
Pd
108.7857
2,448,984
[1.806429039 e-25 kg]
378,432
[15.699 GeV]
Palladium
46
electron configuration
[Kr] 4d8 5s2
36
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
46
f d p s p d f
46 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5
Transition Metal
Azmithal & Magnetic numbers
0
2 1 1 2
2
16
18
8
2
d
d
p
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.46 - Palladium atom


3,948
[1,974-1,974]
Ag
111.2937
Ag
9
1
3
7
5
5
4
1
1
2
2
5
5
3
6
6
8
4
2
10
2
3
1
2,505,444
[1.848075283 e-25 kg]
389,880
[16.121 GeV]

Silver

47

electron configuration

[Kr] 4d9 5s2
36

Aufbau


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
47
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f

47 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5

Post Transition Metal

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
0
2
1
1
2
+2
+1
0
-1
-2
+1
0
-1
-1
0
+1
-2
-1
0
+1
+2
2
17
18
8
2
9
7
5
3
1
2
4
6
8
10
d
d
5
3
1
2
4
6
p
p
1
s
2
8
7
6
5
4
3
2
1
atomic shell
energy level

Orbitals & sub-orbitals

Tetryonics 51.47 - Silver atom


4,032
[2,016-2,016]
Cd
113.8017
9
1
3
7
5
5
4
1
1
2
2
3
6
6
8
4
2
10
Cd
2,561,904
[1.889721526 e-25 kg]
401,328
[16.605 GeV]
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f
48
0
2
1
1
2
+2
+1
0
-1
-2
+1
0
-1
-1
0
+1
-2
-1
0
+1
+2
2
18
18
8
2
9
7
5
3
1
2
4
6
8
10
d
d
5
3
1
2
4
6
p
p
1
2
s
atomic shell
energy level
Post Transition Metal

Cadmium

48

electron configuration

[Kr] 4d10 5s2
36

48 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5

Aufbau

Azmithal & Magnetic numbers

Orbitals & sub-orbitals

Tetryonics 51.48 - Cadmium atom


4,116
[2,058-1,058]
In
116.4920
2,622,468
[1.934394978 e-25 kg]
416,880
[17.249 GeV]
Indium
49
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
49
f d p s p d f
electron configuration
[Kr] 4d10 5s2 5p1
36
49 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5
Aufbau
Azmithal & Magnetic numbers
0
2 1 1 2
+2 +1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0 +1 +2
3
18
18
8
2
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.49 - Indium atom


4,200
[2,100-2,100]
Sn
119.1823
Sn
2,683,032
[1.979068429 e-25 kg]
432,432
[17.392 GeV]

Tin

50


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
50
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f

50 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5

Metaloid

electron configuration

$[Kr]_{36}$ 4d10 5s2 5p2

Aufbau


Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
-1
-1
2
1
1
2
+2
+1
0
-1
-2
+1
0
0
+1
-2
-1
0
+1
+2
4
18
18
8
2
9
7
5
3
1
2
4
6
8
10
d
d
5
3
1
2
4
6
p
p
1
s
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.50 - Tin atom

Copyright ABRAHAM [2008] - All rights reserved


4,284
[2,142-2,142]
At
121.8726
2,743,596
[2.02374188i e-25 kg]
447,984
[18.536 GeV]
Antimony
51
electron configuration
[Kr] 4d10 5s2 5p3
36
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
51 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5
Metaloid
Azmithal & Magnetic numbers
5
18
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.51 - Antimony atom


4,368
[2,184-2,184]
Te
124.5629
2,804,160
[2.068415333 e-25 kg]
463,536
[19.179 GeV]
Tellurium
52
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
[Kr] 4d10 5s2 5p4
36
Aufbau
52
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-5
Metaloid
Azmithal & Magnetic numbers
6
18
18
8
2
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.52 - Tellurium atom



4,452
[2,226-2,226]

I
127.2532

2,864,724
[2.113088784 e-25 kg]

479,088
[19,823 GeV]

Iodine

53


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
53
M
KE
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f

53 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-5

Halogen

electron configuration

[Kr] 4d10 5s2 5p5
36

Aufbau


Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
1
0
1
+1
0
-1
-1
0
2
2
+2
+1
0
-1
-2
+1
-2
-1
0
+1
+2
7
18
18
8
2
9
7
5
3
1
2
4
6
8
10
d
d
5
3
1
2
4
6
p
p
1
s
2
Orbitals & sub-orbitals
atomic shell
energy level
8
7
6
5
4
3
2
1

Tetryonics 51.53 - Iodine atom


4,536
[2,3268-2,268]
Xe
129.9435
2,925,288
[2.157762236 e-25 kg]
494,640
[20.466 GeV]
Xenon
54
electron configuration
[Kr] 4d10 5s2 5p6
36
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
54 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5
Noble Gas
Azmithal & Magnetic numbers
2 1 0 1 2
+2 +1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0 +1 +2
8
18
18
8
2
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 2
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.54 - Xenon atom


4,620
[2,310-2,310]
Cs
132.8225
2,990,100
[2.205569114 e-25 kg]
514,440
[21.285 GeV]
Caesium
55
electron configuration
[Xe] 6s1
54
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
55 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Alkali Metal
Azmithal & Magnetic numbers
0
1 1
2 2
+1 0 -1 -1 0 +1
+2 +1 0 -1 -2 -2 -1 0 +1 +2
1
8
18
18
8
2
9 7 5 3 1 2 4 6 8 10
5 3 1 2 4 6
1 2
d d
p p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.55 - Caesium atom


4,704
[2,352-2,352]
Ba
135.7015
9
1
3
7
5
2
5
4
6
1
1
2
Ba
2
3
6
6
8
4
2
10
3,054,912
[2.253375992 e-25 kg]
534,240
[22.105 GeV]

Barium

56


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
56
M
KE
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f

electron configuration

[Xe] 6s2
54

56 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6

Alkaline Earth

Aufbau


Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
0
1
1
2
2
+1
0
-1
-1
0
+1
+2
+1
0
-1
-2
-2
-1
0
+1
+2
2
8
18
18
8
2
9
7
5
3
1
2
4
6
8
10
d
d
5
3
1
2
4
6
p
p
1
s
2
Orbitals & sub-orbitals
atomic shell
8
7
6
5
4
3
2
1
energy level

Tetryonics 51.56 - Barium atom


4,788
[2.394-2.394]
La
138.2095
3,111,372
[2.295022235 e-25 kg]
545,688
[22.578 GeV]

Lanthanum

57


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
57
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f

Aufbau

electron configuration

[Xe] 4f1 6s2
54

57 [Protons [24-12]
Neutrons [18-18]
electrons [0-12]] m1-6

Lanthanoid


Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
0
1
1
2
2
3
+1
0
-1
-1
0
+1
-3
+2
+1
0
-1
-2
-2
-1
0
+1
+2
2
8
19
18
8
2
1
9
7
5
3
1
2
4
6
8
10
f
d
d
5
3
1
2
4
6
p
p
1
s
2
Orbitals & sub-orbitals
8
7
6
5
4
3
2
1
atomic shell
energy level

Tetryonics 51.57 - Lanthanum atom

Copyright ABRAHAM [2008] - All rights reserved


4,872
[2,436-2,436]
Ce
140.7175
3,167,832
[2.336668478 e-25 kg]
557,136
[23.052 GeV]
Cerium
58
Q
RE
M
KE
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
f d p s p d f
58
58 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Lanthanoid
electron configuration
[Xe] 4f2 6s2
54
Aufbau
Azmithal & Magnetic numbers
0
1
1
2
2
3
3
2
8
20
18
8
2
f
f
d
d
p
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.58 - Cerium atom


4,956
[2,478-2,478]
Pr
143.2255
3,224,292
[2.378314722 e-25 kg]
568,584
[23.526 GeV]
Praseodymium
59
R
Q
P
O
N
M
L
K
Q
RE
M
KE
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
f d p s p d f
59
electron configuration
[Xe] 4f3 6s2
54
59 [Potons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Lanthanoid
Aufbau
Azmithal & Magnetic numbers
0
2
8
21
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.59 - Praseodymium atom


5,040
[2,520-2,520]
Nd
145.7335
Nd
3,280,752
[2.49960965 e-25 kg]
580,032
[23.999 GeV]

Neodymium

60


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
60
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f

60 [Protons [24-12] neutrons [18-18] electrons [0-12]] n1-6

Lanthanoid

electron configuration

[Xe]$_{54}$ 4f4 6s2

Aufbau

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
0
1
1
2
3
2
2
3
+1
0
-1
-1
0
+1
-2
-3
+2
+1
0
-1
-2
-2
-1
0
+1
+2
-3
-2
2
8
22
18
8
2
3
1
9
7
5
3
1
2
4
6
8
10
2
4
5
3
1
2
4
6
1
2
f
d
p
s
p
d
f
8
7
6
5
4
3
2
1
atomic shell
energy level

Orbitals & sub-orbitals

Tetryonics 51.60 - Neodymium atom


5,124
[2,562-2,562]
Pm
148.2415
Pm
3,337,212
[2.461607208 e-25 kg]
591,480
[24.473 GeV]

Promethium

61


3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
61
8
7
6
5
4
3
2
1
f d p s p d f

electron configuration

[Xe] 4f5 6s2

54

61 [Potons [24-12]
Neutrons [18-18]
electrons [0-12]] n1-6

Lanthanoid

Aufbau

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
0
1
1
2
8
23
18
8
2
3
2
2
3
f
d
p
s
p
d
f
8
7
6
5
4
3
2
1
atomic shell
energy level

Orbitals & sub-orbitals

Tetryonics 51.61 - Promethium atom


5,208
[2,604-2,604]
Sm
150.7495
3,393,672
[2.503253452 e-25 kg]
602,928
[24.947 GeV]
Samarium
62
electron configuration
[Xe] 4f6 6s2
54
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
62 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Lanthanoid
Azmithal & Magnetic numbers
2
8
24
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.62 - Samarium atom


5,292
[2,646-2,646]
Eu
153.2575
Eu
3,450,132
[2.544899695 e-25 kg]
614,376
[25.421 GeV]
Europium
63
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
63
f d p s p d f
electron configuration
Aufbau
[Xe] 4f7 6s2
54
63 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Lanthanoid
Azimuthal & Magnetic numbers
0
1 1
2 2
3 3
2
8
25
18
8
2
f d p s p d f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.63 - Europium atom

Copyright ABRAHAM [2008] - All rights reserved


5,376
[2,688-2,688]
Gd
155.7655
3,506,592
[2.586545938 e-25 kg]
625,824
[25.894 GeV]
Gadolinium
64
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
64
f d p s p d f
electron configuration
[Xe] 4f8 6s2
54
64 Potons [24-12] Neutrons [18-18] electrons [0-12] m1-6
Lanthanoid
Aufbau
Azmithal & Magnetic numbers
0
2
8
26
18
8
2
f d p s p d f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.64 - Gadolinium atom

Copyright ABRAHAM [2008] - All rights reserved


5,460
[2,730-2,730]
Tb
158.2735
3,563,052
[2.628192182 e-25 kg]
637,272
[26,368 GeV]
Terbium
65
electron configuration
[Xe] 4f9 6s2
54
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
65
f d p s p d f
65 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Lanthanoid
Azmithal & Magnetic numbers
0
1
2
3
2
8
27
18
8
2
f
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.65 -Terbium atom


5,544
[2,772-2,772]
Dy
160.7815
3,619,512
[2.669838425 e-25 kg]
648,720
[26.842 GeV]
Dysprosium
66
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
66
f d p s p d f
electron configuration
[Xe] 4f10 6s2
54
66 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Lanthanoid
Aufbau
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
2
8
28
18
8
2
f d p s p d f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.66 - Dysprosium atom


5,628
[2,814-2,814]
Ho
163.2895
3,675,972
[2.711484668 e-25 kg]
660,168
[27.316 GeV]
Holmium
67
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
Aufbau
electron configuration
[Xe] 4f11 6s2
54
67
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-6
Lanthanoid
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
2
8
29
18
8
2
f d p s p d f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.67 - Holmium atom


5,712
[2,856-2,856]
Er
165.7974
3,732,432
[2.753130912 e-25 kg]
671,616
[27.789 GeV]

Erbium

68


3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
68
f d p s p d f

electron configuration

[Xe] 4f12 6s2
54

68 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6

Lanthanoid

Aufbau


Azmithal & Magnetic numbers
R Q P O N M L K
atomic shell
8 7 6 5 4 3 2 1
energy level
0
2
1 1
+1 0 -1 -1 0 +1
8
3 2 2 3
+2 +1 0 -1 -2 -3 +2 +1 0 -1 -2 -2 -1 0 +1 +2 -3 -2 -1 0 +1 +2
30
11 9 7 5 3 1 2 4 6 8 10 12
f f
18
9 7 5 3 1 2 4 6 8 10
d d
8
5 3 1 2 4 6
p p
2
1 s 2
Orbitals & sub-orbitals

Tetryonics 51.68 - Erbium atom

Copyright ABRAHAM [2008] - All rights reserved


5,796
[2,898-2,898]
Tm
168.3054
3,788,892
[2.794777155 e-25 kg]
683,064
[28.263 GeV]
Thulium
69
R
Q
P
O
N
M
L
K
3 2 1 0 1 2 3
Q
RE
M
KE
8
7
6
5
4
3
2
1
f d p s p d f
electron configuration
[Xe] 4f13 6s2
54
69 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Lanthanoid
Aufbau
Azmithal & Magnetic numbers
0
1
2
3
2
8
31
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.69 - Thulium atom


5,880
[2,940-2,940]
Yb
170.8134
3,845,352
[2.836423398 e-25 kg]
694,512
[28.737 GeV]
Ytterbium
70
electron configuration
[Xe] 4f14 6s2
54
Aufbau
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
3 2 1 0 1 2 3
f d p s p d f
70 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Lanthanoid
Azmithal & Magnetic numbers
0
1
2
3
2
8
32
18
8
2
f
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.70 - Ytterbium atom


5,964
[2,982-2,982]
Lu
173.5037
13
1
3
9
Lu 1
3
9
7
11
5
7
5
5
4
6
1
1
2
2
6
3
6
6
8
6
8
12
4
2
10
10
4
2
14
3,905,916
[2.881096850 e-25 kg]
710,064
[29.380 GeV]

Lutetium

71


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
71
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f

electron configuration

[Xe] 4f14 5d1 6s2
54

71 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6

Lanthanoid

Aufbau


Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
2
3
2
3
2
9
32
18
8
2
f
d
p
s
p
d
f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.71 - Lutetium atom

Copyright ABRAHAM [2008] - All rights reserved


6,048
[3,024-3,024]
Hf
176.1940
3,966,480
[2.925770302 e-25 kg]
725,616
[30.024 GeV]
Hafnium
72
electron configuration
[Xe] 4f14 5d2 6s2
54
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
72
f d p s p d f
72
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-6
Transition Metal
Aufbau
Azmithal & Magnetic numbers
0
2
10
32
18
8
2
s
p
d
f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.72 - Hafnium atom


6,132
[3,066-3,066]
Ta
178.8843
4,027,044
[2.970443753 e-25 kg]
741,168
[30.667 GeV]

Tantalum

73


3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
73
f d p s p d f

electron configuration
[Xe] 4f14 5d3 6s2
54

73 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-6

Transition Metal

Aufbau


Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
1 1
2 2
3 3
2
11
32
18
8
2
f f
d d
p p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.73 - Tantalum atom


6,216
[3,108-3,108]
W
181.5746
4,087,608
[3.015117205 e-25 kg]
756,720
[31.311 GeV]
electron configuration
[Xe] 4f14 5d4 6s2
54
Tungsten
74
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
74 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Transition Metal
Aufbau
Azmithal & Magnetic numbers
2
12
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.74 - Tungsten atom


6,300
[3.150-3.150]
Re
184.2849
4,148,172
[3.059790657 e-25 kg]
772,272
[31.954 GeV]
Rhenium
75
electron configuration
[Xe] 4f14 5d5 6s2
54
Aufbau
Q
RE
M
KE
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
f d p s p d f
75 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Transition Metal
Azmithal & Magnetic numbers
2
13
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.75 - Rhenium atom


6,384
[3,192-3,192]
Os
186.9552
4,208,736
[3.104464108 e-25 kg]
787,824
[32.598 GeV]
Osmium
76
3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
M
KE
8 7 6 5 4 3 2 1
f d p s p d f
electron configuration
[Xe] 4f14 5d6 6s2
54
Aufbau
76 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Transition Metal
Azmithal & Magnetic numbers
0
2
14
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.76 - Osmium atom

Copyright ABRAHAM [2008] - All rights reserved


6,468
[3.234-3.234]
Ir
189.6455
4,269,300
[3.149137560 e-25 kg]
803,376
[33.241 GeV]
Iridium
77
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
[Xe] 4f14 5d7 6s2
54
Aufbau
77 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Transition Metal
Azmithal & Magnetic numbers
2
15
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.77 - Iridium atom

Copyright ABRAHAM [2008] - All rights reserved


6,552
[3,276-3,276]
Pt
192.3358
4,329,864
[3.19381012 e-25 kg]
818,928
[33.884 GeV]
Platinum
78
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
Aufbau
[Xe] 4f14 5d8 6s2
54
78 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-6
Transition Metal
Azmithal & Magnetic numbers
0
2 16 32 18 8 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.78 - Platinum atom


6,636
[3.318-3.318]
Au
195.0261
4,390,428
[3.238484463 e-25 kg]
834,480
[34.528 GeV]
Gold
79
electron configuration
[Xe] 4f14 5d9 6s2
54
Aufbau
Q
RE
M
KE
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
f d p s p d f
79 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Post Transition Metal
Azmithal & Magnetic numbers
2
17
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.79 - Gold atom

Copyright ABRAHAM [2008] - All rights reserved


6,720
[3,360-3,360]
Hg
197.7164
4,450,992
[3.283157915 e-25 kg]
850,032
[35.171 GeV]
Mercury
80
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
80
f d p s p d f
electron configuration
[Xe] 4f14 5d10 6s2
54
80 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-6
Post Transition Metal
Aufbau
Azmithal & Magnetic numbers
0
2
18
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals
s
p
d
f

Tetryonics 51.80 - Mercury atom

Copyright ABRAHAM [2008] - All rights reserved


6,804
[3,402-3,402]
Tl
200.5954
4,515,804
[3.330964793 e-25 kg]
869,832
[35.991 GeV]
Thallium
81
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
Q
RE
M
KE
81
f d p s p d f
electron configuration
Aufbau
[Xe] 4f14 5d10 6s2 6p1
54
81
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
n1-6
Metaloid
Azmithal & Magnetic numbers
3
18
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.81 - Thallium atom


6,888
[3.444-3.444]
Pb
203.4744
4,580,616
[3.37877167l e-25 kg]
889,632
[36.810 GeV]
Lead
82
electron configuration
Aufbau
[Xe] 4f14 5d10 6s2 6p2
54
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
82
f d p s p d f
82 Protons [24-12] Neutrons [18-18] electrons [0-12] m1-6
Metaloid
Azmithal & Magnetic numbers
4
18
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.82 - Lead atom


6,972
[3,486-3,486]
Bi
208.3534
Bi
4,624,188
[3.426578549 e-25 kg]
909,432
[37.269 GeV]

Bismuth

83


3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
83
f d p s p d f

electron configuration

[Xe] 4f14 5d10 6s2 6p3

54

83 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6

Metaloid

Aufbau


Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
5
18
32
18
8
2
f d p s p d f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.83 - Bismuth atom


7,056
[3.528-3.528]
Po
209.2324
4,710,240
[3.474385426 e-25 kg]
929,232
[38.449 GeV]
Polonium
84
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
f
d
p
s
p
d
f
electron configuration
Aufbau
[Xe] 4f14 5d10 6s2 6p4
54
84
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-6
Metaloid
Azmithal & Magnetic numbers
6
18
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.84 - Polonium atom

Copyright ABRAHAM [2008] - All rights reserved


7,140
[3.570-3.570]
At
212.1114
4,775,052
[3.522192304 e-25 kg]
949,032
[39.268 GeV]
Astatine
85
Q
RE
M
KE
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
f d p s p d f
electron configuration
Aufbau
[Xe] 4f14 5d10 6s2 6p5
54
85 Protons [24-12] Neutrons [18-18] electrons [0-12] m1-6
Halogen
Azmithal & Magnetic numbers
7
18
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.85 - Astatine atom


7,224
[3,612-3,612]
Rn
214.9904
13
1
3
9
1
3
9
11
7
5
7
5
6
5
4
1
2
1
2
3
Rn
6
6
8
6
8
12
10
4
2
10
4
2
14
4,839,864
[3.569999182 e-25 kg]
968,832
[40.087 GeV]

Radon

86


3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
86
8
7
6
5
4
3
2
1
f d p s p d f

electron configuration

Aufbau

[Xe] 4f14 5d10 6s2 6p6
54

86 [Protons [24-12] / Neutrons [18-18] / electrons [0-12]] m1-6

Noble Gas


Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
1 0 1
+1 0 -1 -1 0 +1
2 2
+2 +1 0 -1 -2 -2 -1 0 +1 +2
3 3
+3 +2 +1 0 -1 -2 -3 -3 -2 -1 0 +1 +2 +3
8
18
32
18
8
2
13 11 9 7 5 3 1
2 4 6 8 10 12 14
f f
9 7 5 3 1
2 4 6 8 10
d d
5 3 1
2 4 6
p p
1 2
s
atomic shell
energy level
Orbitals & sub-orbitals

Copyright ABRAHAM [2008] - All rights reserved


7,308
[3,654-3,654]
Fr
218.0845
4,909,068
[3.62]045704 e-25 kg]
993,024
[41.088 GeV]
Francium
87
R
Q
P
O
N
M
L
K
3 2 1 0 1 2 3
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
[Rn] 7s1
86
87
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
n1-7
Alkali Metal
Aufbau
Azmithal & Magnetic numbers
1
8
18
32
18
8
2
s
p
d
f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.87 - Francium atom


7,392
[3,696-3,696]
Ra
221.1386
4,978,272
[3.672092226 e-25 kg]
1,017,216
[42.089 GeV]
Radium
88
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
[Rn] 7s2
86
88
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-7
Alkaline Earth
Aufbau
Azmithal & Magnetic numbers
2
8
18
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.88 - Radium atom



7,476
[3.738-3.738]
Ac
223.8289
5,038,836
[3.716765677 e-25 kg]
1,032,768
[42.732 GeV]
electron configuration
[Rn] 5f1 7s2
86
Actinium
89
R
Q
P
O
N
M
L
K
3 2 1 0 1 2 3
8 7 6 5 4 3 2 1
Q
RE
M
KE
89
f d p s p d f
89
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-7
Actinoid
Aufbau
Amzithal & Magnetic numbers
0
1 1
2 2
3 3
+1 0 -1 -1 0 +1
-3 +2 +1 0 -1 -2 -2 -1 0 +1 +2
+3 +2 +1 0 -1 -2 -3 -2 -1 0 +1 +2 +3
2
8
19
32
18
8
2
13 11 9 7 5 3 1 2 4 6 8 10 12 14
f f
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 2
s
atomic shell
Orbitals & sub-orbitals
energy level

Tetryonics 51.89 - Actinium atom


7,560
[3,780-3,780]
Th
226.5192
5,099,400
[3.761439129 e-25 kg]
1,048,320
[43.376 GeV]
Thorium
90
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
90
f d p s p d f
electron configuration
[Rn] 5f2 7s2
86
90
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-7
Actinoid
Aufbau
Azmithal & Magnetic numbers
0
2
8
20
32
18
8
2
f
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.90 - Thorium atom

Copyright ABRAHAM [2008] - All rights reserved


7,644
[3,822-3,822]
Pa
229.2095
5,159,964
[3.80611258 e-25 kg]
1,063,872
[44.019 GeV]
Protactinium
91
3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
M
KE
8 7 6 5 4 3 2 1
f d p s p d f
Aufbau
electron configuration
[Rn] 5f3 7s2
86
91 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-7
Actinoid
Azmithal & Magnetic numbers
2
8
21
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.91 - Protactinium atom

Copyright ABRAHAM [2008] - All rights reserved


7,728
[3.864-3.864]
U
231.8998
5,220,528
[3.850786032 e-25 kg]
1,079,424
[14.663 GeV]
electron configuration
Uranium
92
3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
M
KE
8 7 6 5 4 3 2 1
f d p s p d f
92 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-7
Actinoid
Aufbau
[Rn] 5f4 7s2
86
Azmithal & Magnetic numbers
0
2
8
22
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.92 - Uranium atom

Copyright ABRAHAM [2008] - All rights reserved


7,812
[3,906-3,906]
Np
234.5901
5,281,092
[3.895459484 e-25 kg]
1,094,976
[45.306 GeV]
Neptunium
93
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
f d p s p d f
Q
RE
M
KE
electron configuration
Aufbau
[Rn] 5f5 7s2
86
93 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Actinoid
Azmithal & Magnetic numbers
2
8
23
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.93 - Neptunium atom

Copyright ABRAHAM [2008] - All rights reserved


7,896
[3,948-3,948]
Pu
237.2804
5,341,656
[3.940132936 e-25 kg]
1,110,528
[45.950 GeV]
Pu

Plutonium


3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
94
f d p s p d f

94

electron configuration

Aufbau

[Rn] 5f6 7s2

86

94 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7

Actinoid


Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
1 1
2 2
3 3
2
8
24
32
18
8
2
f f
d d
p p
s
atomic shell
energy level
Orbitals & sub-orbitals


7,980
[3,990-3,990]
Am
239.9707
Am
5,402,220
[3.984806387 e-25 kg]
1,126,080
[46,593 GeV]
Americium
95
3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
M
KE
95
8 7 6 5 4 3 2 1
f d p s p d f
Aufbau
electron configuration
[Rn] 5f7 7s2
86
95 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-7
Actinoid
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
+1 0 -1 -1 0 +1
+2 +1 0 -1 -2 -2 -1 0 +1 +2
0 -1 -2 -3 -3 -2 -1 0
+3 +2 +1 +1 +2 +3
2
8
25
32
18
8
2
13 11 9 7 5 3 1 2 4 6 8 10 12 14
f f
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.95 - Americium atom


8,064
[4,032-4,032]
Cm
242.6810
5,462,784
[4.029479839 e-25 kg]
1,141,632
[47.237 GeV]
Curium
96
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
Aufbau
[Rn] 5f8 7s2
86
96 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-7
Actinoid
Azmithal & Magnetic numbers
2
8
26
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.96 - Curium atom


8,148
[4,074-4,074]
Bk
245.3513
5,523,348
[4.07415329I e-25 kg]
1,157,184
[47,880 GeV]
Berkelium
97
R
Q
P
O
N
M
L
K
Q
RE
M
KE
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f
electron configuration
Aufbau
[Rn] 5f9 7s2
86
97
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-7
Actinoid
Azmithal & Magnetic numbers
2
8
27
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.97 - Berkelium atom


8,232
[4,116-4,116]
Cf
248.0416
5,583,912
[4.118826742 e-25 kg]
1,172,736
[48.524 GeV]
Californium
98
R
Q
P
O
N
M
L
K
3 2 1 0 1 2 3
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
Aufbau
[Rn] 5f10 7s2
86
98 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Actinoid
Azmithal & Magnetic numbers
0
1
3
2
2
8
28
32
18
8
2
+1 0 -1
-1 0 +1
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
13 11 9 7 5 3 1
2 4 6 8 10 12 14
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 2
f
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.98 - Californium atom


8,316
[4.158-4.158]
Es
250.7319
5,644,476
[4.163500194 e-25 kg]
1,188,288
[49.167 GeV]
Einsteinium
99
Q
RE
M
KE
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
f d p s p d f
electron configuration
Aufbau
[Rn] 5f11 7s2
86
99 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Actinoid
Azmithal & Magnetic numbers
2
8
29
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.99 - Einsteinium atom

Copyright ABRAHAM [2008] - All rights reserved


8,400
[4,200-4,200]
Fm
253.4222
5,705,040
[4.208173646 e-25 kg]
1,203,840
[49.811 GeV]
Fm
Fermium
100
electron configuration
Aufbau
[Rn] 5f12 7s2
86
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
100
f d p s p d f
100
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-7
Actinoid
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
+1 0 -1
-1 0 +1
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
2
8
30
32
18
8
2
13 11 9 7 5 3 1
2 4 6 8 10 12 14
f
9 7 5 3 1
2 4 6 8 10
d
5 3 1
2 4 6
p
1 2
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.100 - Fermium atom

Copyright ABRAHAM [2008] - All rights reserved


8,484
[4,242-4,242]
Md
256.1125
5,765,604
[4.252847097 e-25 kg]
1,219,392
[50.454 GeV]
Mendelevium
101
electron configuration
Aufbau
[Rn] 5f13 7s2
86
R
Q
P
O
N
M
L
K
3 2 1 0 1 2 3
8
7
6
5
4
3
2
1
Q
RE
M
KE
f d p s p d f
101 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Actinoid
Azmithal & Magnetic numbers
0
1
1
2
2
3
3
2
8
31
32
18
8
2
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
13 11 9 7 5 3 1
2 4 6 8 10 12 14
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 2
f
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.101 - Mendelevium atom

Copyright ABRAHAM [2008] - All rights reserved


8,568
[4,284-4,284]
No
258.8028
5,826,168
[4.297520549 e-25 kg]
1,234,944
[51.098 GeV]
Nobelium
102
electron configuration
Aufbau
[Rn] 5f14 7s2
86
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
102 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Actinoid
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
+1 0 -1 -1 0 +1
+3 +2 +1 0 -1 -2 -3 +2 +1 0 -1 -2 -2 -1 0 +1 +2 -3 -2 -1 0 +1 +2 +3
2
8
32
32
18
8
2
13 11 9 7 5 3 1 2 4 6 8 10 12 14
f f
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.102 - Nobelium atom


8,652
[4,326-4,326]
Lr
281.6818
5,890,980
[4.345327427 e-25 kg]
1,254,744
[51.917 GeV]
electron configuration
Aufbau
[Rn] 5f14 6d1 7s2
86
Lawrencium
103
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
103 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Actinoid
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1
-2 +1 0 -1
-1 0 +1
-2 -1 0 +1 +2
-3 -2 -1 0 +1 +2 +3
2
9
32
32
18
8
2
13 11 9 7 5 3 1
2 4 6 8 10 12 14
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 2
f d p s p d f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.103 - Lawrencium atom

Copyright ABRAHAM [2008] - All rights reserved


8,736
[4,368-4,368]
Rf
264.5608
5,955,792
[4.393134305 e-25 kg]
1,274,544
[52.736 GeV]
Rutherfordium
104
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
Aufbau
[Rn] 5f14 6d2 7s2
86
104
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
n1-7
Transition Metal
Azmithal & Magnetic numbers
2
10
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.104 - Rutherfordium atom


8,820
[4,410-4,410]
Db
287.4398
6,020,604
[4.44094182 e-25 kg]
1,294,344
[53.556 GeV]

Dubnium

105


3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
105
8
7
6
5
4
3
2
1
f d p s p d f

electron configuration

Aufbau

[Rn] 5f14 6d3 7s2

86

105 [Protons [24-12] / Neutrons [18-18] / electrons [0-12]] m1-7

Transition Metal


Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
11
32
32
18
8
2
f
d
p
s
p
d
f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.105 - Dubnium atom

Copyright ABRAHAM [2008] - All rights reserved


8,904
[4,452-4,452]
Sg
270.3188
6,085,416
[4.488748060 e-25 kg]
1,314,144
[54.375 GeV]
Seaborgium
106
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
Aufbau
[Rn] 5f14 6d4 7s2
86
106 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Transition Metal
Azmithal & Magnetic numbers
2
12
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.106 - Seaborgium atom


8,988
[4.494-4.494]
Bh
273.1978
6,150,228
[4.536554938 e-25 kg]
1,333,944
[55.194 GeV]
Bohrium
107
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
Aufbau
[Rn] 5f14 6d5 7s2
86
107 Protons [24-12] Neutrons [18-18] electrons [0-12] n1-7
Transition Metal
Azmithal & Magnetic numbers
2
13
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.107 - Bohrium atom


9,072
[4.536-4.563]
Hs
276.0768
6,215,040
[4.584361816 e-25 kg]
1,353,744
[56.013 GeV]
Hs
Hassium
108
R
Q
P
O
N
M
L
K
3 2 1 0 1 2 3
Q
RE
M
KE
8
7
6
5
4
3
2
1
f d p s p d f
electron configuration
Aufbau
[Rn] 5f14 6d6 7s2
86
108 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Transition Metal
Azmithal & Magnetic numbers
0
2
14
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals
s
p
d
f

Tetryonics 51.108 - Hassium atom


9,156
[4.578-4.578]
Mt
278.9558
6,279,852
[4.632168604 e-25 kg]
1,373,544
[56.833 GeV]
Meitnerium
109
R
Q
P
O
N
M
L
K
Q
RE
M
KE
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
f d p s p d f
electron configuration
Aufbau
[Rn] 5f14 6d7 7s2
86
109 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-7
Transition Metal
Azmithal & Magnetic numbers
2
15
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.109 - Meitnerium atom


9,240
[4,620-4,620]
Ds
281.8348
6,344,664
[4.679975572 e-25 kg]
1,393,344
[57.652 GeV]
Darmstadtium
110
R
Q
P
O
N
M
L
K
3
2
1
0
1
2
3
8
7
6
5
4
3
2
1
Q
RE
M
KE
110
f
d
p
s
p
d
f
electron configuration
Aufbau
[Rn] 5f14 6d8 7s2
86
110
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-7
Transition Metal
Azmithal & Magnetic numbers
0
2
16
32
32
18
8
2
+3
+2
+1
0
-1
-2
-3
13
11
9
7
5
3
1
2
4
6
8
10
12
14
f
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.110 - Darmstadtium atom

Copyright ABRAHAM [2008] - All rights reserved


9,324
[4,662-4,662]
Rg
284.7138
Rg
6,409,476
[4.727782449 e-25 kg]
1,413,144
[58.471 GeV]

Roetgenium

111


3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
111
f d p s p d f

electron configuration

Aufbau

[Rn] 5f14 6d9 7s2
86

111 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7

Post Transition Metal

Azmithal & Magnetic numbers


R Q P O N M L K
8 7 6 5 4 3 2 1
0
2
1
1
2
3
3
+2 +1 0 -1 -2
+1 0 -1
-1 0 +1
-2 -1 0 +1 +2
+3 +2 +1 0 -1 -2 -3
-3 -2 -1 0 +1 +2 +3
2
17
32
32
18
8
2
13 11 9 7 5 3 1
2 4 6 8 10 12 14
f
f
9 7 5 3 1
2 4 6 8 10
d
d
5 3 1
2 4 6
p
p
1 2
s
atomic shell
energy level

Orbitals & sub-orbitals

Tetryonics 51.111 - Roetgenium atom

Copyright ABRAHAM [2008] - All rights reserved


9,408
[4,704-4,704]
Cn
287.5928
Cn
6,474,288
[4.775589327 e-25 kg]
1,432,944
[59.290 GeV]
Copernicium
112
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
112
f d p s p d f
electron configuration
Aufbau
[Rn] 5f14 6d10 7s2
86
112 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-7
Post transition Metal
Azmithal & Magnetic numbers
0
2 1 1 2
3 3
+2 +1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0 +1 +2
+3 +2 +1 0 -1 -2 -3 -3 -2 -1 0 +1 +2 +3
2
18
32
32
18
8
2
13 11 9 7 5 3 1 2 4 6 8 10 12 14
f f
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.112 - Copernicium atom


9,492
[4,746-4,746]
Uut
290.6669
6,543,492
[4.826535849 e-25 kg]
1,457,136
[60.292 GeV]
Ununtrium
113
electron configuration
Aufbau
[Rn] 5f14 6d10 7s2 7p1
86
3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
113 Protons [24-12]
Neutrons [18-18]
electrons [0-12]
n1-7
Metalloid
Azmithal & Magnetic numbers
0
3
18
32
32
18
8
2
f
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.113 - Ununtrium atom


9,576
[4,788-4,788]
Fl
293.7409
6,612,696
[4.877682371 e-25 kg]
1,481,328
[61.293 GeV]
Flerovium
114
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
Aufbau
[Rn] 5f14 6d10 7s2 7p2
86
114 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Metalloid
Azmithal & Magnetic numbers
4
18
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.114 - Flerovium atom


9,660
[4,830-4,830]
Uup
298.8150
6,681,900
[4.9287288893 e-25 kg]
1,505,520
[62.294 GeV]
electron configuration
Ununpentium
115
Q
RE
M
KE
R
Q
P
O
N
M
L
K
3
2
1
0
1
2
3
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f
115 [Protons [24-12]
Neutrons [18-18]
electrons [0-12]] n1-7
Metaloid
Aufbau
[Rn] 5f14 6d10 7s2 7p3
86
Azmithal & Magnetic numbers
5
18
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.115 - Ununpentium atom

Copyright ABRAHAM [2008] - All rights reserved


9,744
[4,872-4,872]
Uh
289.8891
Lv
6,751,104
[4.979775415 e-25 kg]
1,529,712
[63.295 GeV]
Livermorium
116
R
Q
P
O
N
M
L
K
3 2 1 0 1 2 3
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
Aufbau
[Rn] 5f14 6d10 7s2 7p4
86
116 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-7
Metaloid
Azmithal & Magnetic numbers
6
18
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.116 - Livermorium atom


9,828
[4.914-4.914]
Uus
302.9832
Ununseptium
6,820,308
[5.030821937 e-25 kg]
1,553,904
[64.296 GeV]
117
electron configuration
Aufbau
[Rn] 5f14 6d10 7s2 7p5
86
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
f d p s p d f
Q
RE
M
KE
117 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Halogen
Azmithal & Magnetic numbers
7
18
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.117 - Ununseptium atom

Copyright ABRAHAM [2008] - All rights reserved


9,912
[4.956-4.956]
Uuo
308.0373
6,889,512
[5.0818684 59 e-25 kg]
1,578,096
[65.297 GeV]
Uuo
electron configuration
Ununoctium
118
R
Q
P
O
N
M
L
K
3
2
1
0
1
2
3
Q
RE
M
KE
118
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f
Aufbau
[Rn] 5f14 6d10 7s2 7p6
86
118 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-7
Noble Gas
Azmithal & Magnetic numbers
8
18
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.118 - Ununoctium atom


9,996
[4,998-4,998]
Uun
309.3129
Uun
6,963,252
[5.136260842 e-25 kg]
1,606,824
[66.486 GeV]
Ununnenium
119
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
119
f d p s p d f
Aufbau
electron configuration
[Uuo] 8s1
118
Azmithal & Magnetic numbers
119 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-8
Alkali Metal
1
8
18
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.119 - Ununnenium atom


10,080
[5,040-5,040]
Ub
312.5885
7,036,992
[5.190653044 e-25 kg]
1,635,552
[67.675 GeV]
Unbinilium
120
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
Aufbau
[Uuo] 8s2
118
Azmithal & Magnetic numbers
120 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-8
Alkaline Earth
2
8
18
32
32
18
8
2
s
p
d
f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.120 - Unbinilium atom


Atomic shell
Energy level
K 2 1
L 8 2
M 18 3
N 32 4
O 32 5
P 18 6
Q 8 7
R 2 8
electron configuration
Periodic
Elements
H
D 1
He 2
Li 3
Be 4
B 5
C 6
N 7
O 8
F 9
Ne 10
Na 11
Mg 12
Al 13
Si 14
P 15
S 16
Cl 17
Ar 18
K 19
Ca 20
Sc 21
Ti 22
V 23
Cr 24
Mn 25
Fe 26
Co 27
Ni 28
Cu 29
Zn 30
Ga 31
Ge 32
As 33
Se 34
Br 35
Kr 36
Rb 37
Sr 38
Y 39
Zr 40
Nb 41
Mo 42
Tc 43
Ru 44
Rh 45
Pd 46
Ag 47
Cd 48
In 49
Sn 50
Sb 51
Te 52
I 53
Xe 54
Cs 55
Ba 56
La 57
Ce 58
Pr 59
Nd 60
Pm 61
Sm 62
Eu 63
Gd 64
Tb 65
Dy 66
Ho 67
Er 68
Tm 69
Yb 70
Lu 71
Hf 72
Ta 73
W 74
Re 75
Os 76
Ir 77
Pt 78
Hg 79
Au 80
Tl 81
Pb 82
Bi 83
Po 84
At 85
Rn 86
Fr 87
Ra 88
Ac 89
Th 90
Pa 91
U 92
Np 93
Pu 94
Am 95
Cm 96
Bk 97
Cf 98
Es 99
Fm 100
Md 101
No 102
Lr 103
Rf 104
Db 105
Sg 106
Bh 107
Hs 108
Mt 109
Ds 110
Rg 111
Cn 112
Uut 113
Fl 114
Uup 115
Lv 116
Uus 117
Uuo 118
Uun 119
Uub 120
Z
D nuclei

Tetryonics 52.01 - Tetryonic Element Table

Copyright ABRAHAM [2008] - All rights reserved


PERIODIC
ELEMENTS
13 Md Tm 13
1 Ac La 1
3 Pa Pr 3
9 Au Rg Ag Cu 9
1 Lr Lu Y Sc 1
3 Db Ta Nb V 3
9 Bk Tb 9
11 Es Ho 11
7 Mt Ir Rh Co 7
5 Bh Re Tc Mn 5
7 Am Eu 7
5 Np Pm 5
5 At I Uus Br Cl F 5
1 Cs Rb Fr D K Uun Li Na
4 Po Te Lv Se S O 4
1 Tl In Uut Ga Al B 1
2 Pb Sn Fl Ge Si C 2
2 Ba Sr Ra He Ca Ub Be Mg 2
3 Bi Sb Uup As P N 3
6 Rn Xe Uuo Kr Ar Ne 6
6 Pu Sm 6
8 Cm Gd 8
6 Hs Os Ru Fe 6
8 Ds Pt Pd Ni 8
12 Fm Er 12
10 Cf Dy 10
4 Sg W Mo Cr 4
2 Rf Hf Zr Ti 2
10 Cn Hg Cd Zn 10
4 U Nd 4
2 Th Ce 2
14 No Yb 14

Tetryonics 52.02 - Periodic Table [Elements]

Copyright ABRAHAM [2008] - all rights reserved

TETRYONICS

The charged geometry of mass-ENERGY-Matter


Q
RE
3
4
5
9
2D mass
geometries
3D Matter
topologies
7
16
9
25
11
6
36
Bosons
Fermions
13
7
49
15
8
64
17
9
h
M
scalar
energies
KE

Foundational Quantum Mechanics

Abraham

ISBN 978-0-9872884-1-7
[Second Edition © 2012]

Copyright ABRAHAM [2008] - all rights reserved

FUNDAMENTUM QUANTUM MECHANICA

questions **Q**

A answers

[TETRYONICS]

A fundamental re-interpretation of the geometry of quantised angular momentum is required to complete the physics of 'The Standard model'



Everyone is entitled to their own opinions
but NO-ONE is entitled to their own facts

Mathematics is the language of Physics,
and Geometry is its grammar

Philosophiae Naturalis Principia geometricae



For ANY physical model to be valid
it must demonstrate the known facts

Having removed the impossible,
anything that remains, however improbable,
must be the truth

"...the scientist makes use of a whole arsenal of concepts which he imbibed practically with his mother's milk; and seldom if ever is he aware of the eternally problematic character of his concepts. He uses this conceptual material, or, speaking more exactly, these conceptual tools of thought, as something obviously, immutably given; something having an objective value of truth which is hardly even, and in any case not seriously, to be doubted. ...in the interests of science it is necessary over and over again to engage in the critique of these fundamental concepts, in order that we may not unconsciously be ruled by them."

[Albert Einstein]

Science is born from observation,
and the reasoning of known facts
in search of underlying truths

In the following pages the true geometry of quantum mechanics is revealed, leading scientific endeavour into new realms of understanding

mass-ENERGY-Matter

The a-priori revelation of Tetryonic theory is that all square mass-energies possess equilateral momenta geometries



The equilateral Quantised Angular Momentum intrinsic to Planck mass-energy momenta produces charged geometries


v
p
ε0
kg
m²
S
m
v
v²
mΩ
mass QAM
time



The quantum mechanics of velocity, quanta, EM fields and mass-Energy-Matter can be fully revealed through their equilateral geometries


m
kg
mass-ENERGY
geometry
c²

A long hidden topology is revealed

Equilateral triangles are the foundational geometry for all mass-ENERGY-Matter topologies and physical Force interactions


M
KG
mass-MATTER
topology
c⁴

Copyright ABRAHAM [2008] - all rights reserved

SQUARED energies in quantum mechanics are EQUILATERAL geometries



Square

area = s^2 = [100]

Circles


r=5.642m
area = pi * r^2

= pi *$[5.642]^2$
= 100


10
10
100 m²
5.642
Squared Areas
13.160
15.197

can be created by a number of planar geometries

For a long time it has been assumed by scientists (and mathematicians)
that circular [and squared] geometries are the geometric foundation of all physics,
leading to a serioulsy flawed model of particles and forces in quantum mechanics

Tetryonic theory now reveals that quantised equilateral angular momenta creates the foundational geometry of all the mass-Energy-Matter & forces of physics


$a = \frac{\sqrt{3}}{4} * s^2$
s
15.197m

Equilateral

area = $(\frac{1}{2}*b)*h$

Triangles


h = 13.160m
s
15.197m
b

b h
[.5x15.197] x 13.160
= 100

Integers

The integers (from the Latin integer), literally "untouched", hence "whole"
in Tetryonics it is the basis for the quantum


1
2 3 4
5 6 7 8 9
10 11 12 13 14 15 16
17 18 19 20 21 22 23 24 25
26 27 28 29 30 31 32 33 34 35 36
37 38 39 40 41 42 41 44 45 46 47 48 49
50 51 52 53 54 55 56 57 58 59 60 61 62 63 64
65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81
n

Viewed as a subset of the real numbers, they are numbers that can be written without a fractional or decimal component

ODD numbers

An odd number is an integer which is not a multiple of two.

2n-1

2n+1


n
1
1
3
1 2 3
5
1 2 3 4 5
7
1 2 3 4 5 6 7
9
1 2 3 4 5 6 7 8 9
11
1 2 3 4 5 6 7 8 9 10 11
13
1 2 3 4 5 6 7 8 9 10 11 12 13
15
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15
17
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17

ODD numbers
in each level

Bosons have
ODD number
quanta

An odd number, when divided by two, will result in a fraction

Copyright ABRAHAM [2008] - all rights reserved

EVEN numbers

An integer that is not an odd number is an even number.

2

Photons have
EVEN number
quanta


1
3
2
4
6
8
5
7
9
11
13
15
10
12
14
16
18
20
22
24
17
19
21
23
25
27
29
31
33
35
26
28
30
32
34
36
38
40
42
44
46
48
37
39
41
41
45
47
49
51
53
55
57
59
61
63
50
52
54
56
58
60
62
64
66
68
70
72
74
76
78
80
65
67
69
71
73
75
77
79
81

2n

EM waves are
comprised of EVEN
numbered quanta

An even number is defined as a whole number that is a multiple of two.
If an even number is divided by two, the result is another whole number.

Square numbers

A square number, sometimes also called a perfect square,
is the result of an integer multiplied by itself

2n-1

Quantum levels
have ODD number
geometries

Σ 2n-1

SQUARE numbers
are the sum of successive
ODD numbers


1
1
3
2 3 4
5
5 6 7 8 9
7
10 11 12 13 14 15 16
9
17 18 19 20 21 22 23 24 25
11
26 27 28 29 30 31 32 33 34 35 36
13
37 38 39 40 41 42 43 44 45 46 47 48 49
15
50 51 52 53 54 55 56 57 58 59 60 61 62 63 64
17
65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81
n²
Square
numbers

In Tetryonics SQUARE numbers are EQUILATERAL geometries

Square roots

A square root of a number is a number that, when it is multiplied by itself (squared) , gives the first number again.

-i and +i

Against Mathematical convention,
square roots of negative numbers
are real numbers

In Physics
every complex number
except 0 has 2 square roots.



2n-1

n^2

A whole number with a square root that is also a whole number is called a perfect square

Copyright ABRAHAM [2008] - all rights reserved

Real Numbers

A real number is a value that represents a quantity along a continuous line.

The real numbers include all the rational numbers,


n
-n
9
8
7
6
5
4
3
2
1
0
1
2
3
4
5
6
7
8
9
+n
-n to +n

Copyright ABRAHAM [2008] - all rights reserved

Irrational Numbers

An irrational number is defined to be any real number that cannot be written as a complete ratio of two integers

$+i$ and $-i$

Well known irrational & imanginary numbers in Math are π and i

π


$i^2 = -1$
60°
0.866025403
17 18
26 27 28 30 33 34 35 36
37 38 39 40 42 45 46 47 48 49
50 51 52 53 56 59 60 61 62 63 64
66 67 68 69 71 72 77 78 79 80
60°
60°
Sin 60
Sin π/3
$\sqrt{3/2}$

$\sqrt{n}$

in Tetryonics the SQR of a negative number is the linear momentum of a negative charge EM field

$\sqrt{-n}$

Irrational numbers often occur in mathematics

$\sqrt{-n}$

Copyright ABRAHAM [2008] - all rights reserved


infra-red
ultra-violet

0	Brown
1	Red
2	Orange
3	Yellow
4	Green
5	Aqua
6	Blue
7	Indigo
8	Violet
9	Black

A colour code is used to indicate the varying quantum levels of the numerous forms of mass-ENERGY-Matter and serves to illustrate relationships between various Physical properties.

Tetryonic Colour Code



Tetryonics uses a colour code that is based on the spectral colours of dispersed White Light


v
1
2
3
4
5
6
7
8
9
3
5
7
9
11
13
15
17
4
9
16
25
36
49
64
81
n
ODD Numbers
SQUARE Numbers
hv
v²

Copyright ABRAHAM [2008] - all rights reserved

Free Space

A contiguous volume or area
of any regular geometry
that is free, available, or unoccupied

$$E = 0$$

in any form



*There is NO aether for the
transmission of Light
in empty space*

*2D space has
Flat 'Euclidean'
geometries*

A Spatial region
is defined so as to
measure the physics
of mass-ENERGY-Matter
within its confines

Energy moves through Space
in various forms:
radiant energies, Matter etc

Space can be
Cubic, Spherical or
Tetrahedral as defined by
the spatial co-ordinates
used to define the region

Empty Space is defined as a topology whose volume is devoid of Energy

Copyright ABRAHAM [2008] - all rights reserved

Space-Time co-ordinates

Charge radiates unilaterally
in line with its
vector linear momentum

Vector forces



The linear vector of divergent Energy
forms various co-ordinate systems
based on its vector directions
per unit of Time

Radiant Energies

Radial Time

c
299,792,458
linear metres
per sec

c²
8.987551787 e16
radial square metres
per sec

c³
2.694400242 e25
cubic metres
per sec

c⁴
8.077608713 e33
spherical metres
per sec

Cartesian and Curvilinear
spatial co-ordinate systems
both measure 3D Matter

**Euclidean
planar
space-time**



EM Light radiates bi-laterally
co-linear with its two
linear momentum vectors

Time in Physics is a measure
of how long it takes for light to
travel 299,792,458 metres
from its source in a vacuum

$$\frac{299{,}792{,}458\ \text{m}}{\text{second}}$$

$$\frac{\text{metre}}{299{,}792{,}458\ \text{sec}}$$

A metre in Physics is
the distance light travels in
1/ 299,792,458 of a second
from its source

**Cartesian
rectilinear
space time**

**Riemannian
curvilinear
space-time**

Spatial geometries

based on the vector speed of Light
form distinct spatial co-ordinate systems
for the measurement of physics



vector lines

1 Dimensional velocity

linear metres

Planar Circles

2 Dimensions

c^2

velocity squared

radial seconds

Cubic volumes

3 Dimensions

velocity cubed

c^3

Cartesian co-ordinates

Spherical volumes

3 Dimensions

c^4

quarternion velocity

radial seconds²

Forces

2D planar radiant geometry

mass-energies

Energy has an equilateral geometry and forms
Tetrahedral topologies within any
spatial region

3D standing-wave topology

mass-Energy-Matter
and all forces

Copyright ABRAHAM [2008] - all rights reserved

c is the natural velocity of light

Energy has a 2D equilateral geometry [Euclidian]

Time - as a measure of divergent energies has a radial geometry


v
$\frac{1}{c^2}$
Impedance of Space
Permittivity
and
Permeability
hv
v²
c²
seconds

Equilateral geometry is the inverse of radial geometry

3D Matter has a tetrahedral mass-energy topology

The scalar spatial geometry of Energy

Copyright ABRAHAM [2008] - all rights reserved

Velocity

Velocity is the measurement of the rate and direction of change in the position of an object.

It is a vector physical quantity; both magnitude and direction are required to define it.

The absolute scalar value (magnitude) of velocity is speed, a quantity that is measured in metres per second (m/s or ms−1) when using the SI (metric) system.

$$\frac{m}{s}$$

Speed is the scalar value of the Distance traveled per unit of TIme

$$\bar{\mathbf{v}} = \frac{\Delta x}{\Delta t}.$$

Velocity is the vector value of the Distance traveled per unit of Time

$$\overrightarrow{\frac{m}{s}}$$

v Velocity $\frac{m}{s}$

sec

c^2

is a 2D RADIAL
SPACE-TIME
co-ordinate system



*All divergent Energy possesses a vector direction
and an associated scalar area
whose energy content is quantised*

Acceleration

sec^2

c^4

is a 3D SPHERICAL
SPACE-TIME
co-ordinate system

a acceleration $\frac{m}{s^2}$



In physics, acceleration is the rate of change of velocity [dv] over time [dt]

In one dimension, acceleration is the rate at which something speeds up or slows down.

However, since velocity is a vector, acceleration describes the rate of change of both the magnitude and the direction of velocity.

Acceleration has the dimensions [Length]/[Time Squared]
In SI units, acceleration is measured in meters per second squared (m/s^2).

$$a = \frac{\Delta y}{\Delta x} = \frac{\Delta v}{\Delta t}.$$

In classical mechanics, for a body with constant mass,
the acceleration of the body is proportional to the net force acting on it
(Newton's second law)

$$F=ma \longrightarrow a=F/m$$

Force

$$\mathrm{kg}\,\frac{m}{s^2}$$

Additionally, for a mass with constant velocity,
(ie in an inertial frame)
the energy of motion is expressed as its momentum
(acceleration causes changes in Energy-momentum)

$$p = \mathrm{kg}\,\frac{m}{s}$$

Quantised Angular momentum

As it is a physical [equilateral] geometry QAM is conservative in any system where there are no external Forces and serves as the foundational geometric source for all the conservation laws of physics


m
ε_0
Ω
$\frac{m^2}{s}$
m²
Quantised
Angular Momenta
1 second

Conservation of Quantised Angular momenta

In QFT, angular momentum is is considered to be the rotational analog of linear momentum, in Tetryonics it is revealed to be the equilateral geometry of mass-energy within any defined spatial co-ordinate system

A major re-definition of
quantised angular momenta
in physics is revealed


$\frac{m^2}{s}$
≈
[v-v]
1
3
5
7
9
11
13
15
1
4
9
16
25
36
49
64
$\frac{m^2}{s}$
Tetryonic
quantised angular momenta

classical rotational angular momenta

Tetryonic quantum mechanics

In quantum mechanics, angular momenta is quantised – that is, it cannot vary continuously, but only in ODD number "quantum steps" between the allowed SQUARE nuclear Energy levels

In physics, angular momentum, moment of momentum, or rotational momentum is a conserved vector quantity that can be used to describe the overall state of a physical system.

When applied to specific mass-energy-Matter systems QAM reveals the true quantum geometry and nature of Energy in our universe


h
$kg\frac{m^2}{s}$
m
mΩ
mass x QAM

Planck's Constant

Normally viewed as an expression of rotational momentum Quantised Angular Momentum [QAM] is in fact a result of the equilateral geometric quantization of mass-energy



mass - Energy geometry

Newton developed his
Laws using Force
$p = mv$
(linear momentum)

Gottfried Leibniz first described Scalar Energy as the square of velocity

Planck developed his Heat
Law using quantised mass
$h = m\Omega$
(Planck Constant)

Planck's equation for heat energy describes transverse masses [Bosons]

Transverse
Bosons
$[hv]$

Scalar
ENERGY
$[hv^2]$

$$E = mv^2$$

Leibnitz mass-energy equivalence

$$E = nhv$$

Planck mass-energy equivalence

mass velocity squared

quantised mass per second

$$kg\,\frac{m^2}{s^2}$$

Planck quanta per second

$$\left[kg\,\frac{m^2}{s}\,\frac{1}{s}\right]$$

$$mv^2 = E = hv^2$$

Leibniz-Planck mass-Energy equivalence

scalar energies can be related to velocity-momenta through mass geometries

scalar | *quantised*

mv^2 Leibniz-Newton mass-Energy equivalence $m\Omega v^2$ Tetryonic-Planck mass-Energy equivalence hv^2

mass-Energy Forms

Scalar/Linear forms



mass x velocity squared

$$kg.\left[\frac{m}{s}\right]^2$$

Energy momentum

Leibniz [and Newton] showed that the Energy of a system can be viewed as a product of its mass x velocity squared or [equally as linear momentum squared], forever linking Energy to velocity through the scalar property of mass

$$mv^2 = E = p^2$$

Energy is the ability to do work in varying forms such as potential, kinetic, & mechanical energies, work, heat, and chemical or electrical energies.



$$\boxed{mv^2 = E = hv^2}$$

The total energy contained in an object is identified with its EM mass, and Energy (like mass), cannot be created or destroyed

Tetryonic reveals mass to be a scalar measurement of quantised [equilateral] energy per unit of Time

$$m[\Omega]v^2$$

Energy is subject to the law of conservation

Quantised form



Planck quanta per second

$$\left[kg.\frac{m^2}{s}\right].s^{-1}$$

mass-Energy quanta

Max Planck reveealed that energy was not continuous, it was quantized – only certain energies are allowed. Continuous energy is a scalar propertyo of mass-energy and its quantisation is the result of its equilateral geometry

$$E = hv^2$$

In quantum mechanics energy is defined in terms of the energy operator as a time derivative of the wave function



Energy is mass-velocity squared

$E = mv^2$



Planck quanta

$$\left[\left[m \Omega v \right]^2 \right]$$

mass velocity

linear momentum squared

Everything in our Universe results from the equilateral geometry of quantised mass-energies



Energy is Planck-quanta squared

$E = hv^2$

Quantised Energy

scalar mass

kg

$m = \frac{E}{v^2}$

Planck quanta per second

$$\left[\left[kg \frac{m^2}{s} \right] \frac{1}{s} \right]$$

mass velocity squared

Scalar Energy

Note: There is a direct correspondence between Velocity and Planck quanta numbers (ie as velocity varies, the energy quanta varies as well by the square of the linear change)

quantised mass

$kg \frac{m^2}{s}$

$h = \frac{E}{v^2}$

Copyright ABRAHAM [2008] - all rights reserved

Linear Momentum

p Momentum $kg\frac{m}{s}$



Linear momentum is the vector square root of any equilateral mass-energy field

In classical mechanics, momentum (pl. momenta; SI unit kg·m/s, or, equivalently, N·s) is the product of the mass and velocity of an object (p).

Like velocity, momentum is a vector quantity, possessing a direction as well as a magnitude.

Momentum is a conserved quantity (law of conservation of linear momentum), meaning that if a closed system is not affected by external forces, its total momentum cannot change.

Momentum should be referred to in its specific forms to distinguish it in its various forms [Quantised Angular, Linear, Rotational and quantum/nuclear momentum]

$$\boxed{p = \frac{hv^2}{v} = mv}$$

Although originally expressed in Newton's Second Law, the conservation of momentum also holds in special relativity and, with appropriate definitions, a (generalized) momentum conservation law holds in electrodynamics, quantum mechanics, quantum field theory, and general relativity.

In relativistic mechanics, non-relativistic momentum is further multiplied by the Lorentz factor.

$$p^2 = E = mv^2$$

Energy can be expressed as the square of linear momentum

$$kg\frac{m^2}{s^2}$$

Just as Tetyonic geometry distingushes between angular momenta and linear momentum it also distingushes between linear momentum and the vector velocities it produces

Linear Momentum

$p = mv$

Velocity



$E = pv$

$E = p^2$



SCALAR square root

Scalars are quantities that are fully described by only their magnitude

$E = mv^2$

VECTOR square root

Vectors fully describe both the magnitude and direction.

linear momentum is a scalar component of all equilateral mass-energies that produce vector velocities

Copyright ABRAHAM [2008] - all rights reserved

Velocity-Quanta equivalence

Classically, the Energy of massive bodies was determined using the Newtonian mass-velocity relationship

but most recently Quantum mechanics was developed utilising the Planck's quantised Energy relationship





classical vector force

$$mv^2$$

mass
linear velocity
squared

$$kg\left[\frac{m}{s}\right]^2$$



quantised energy momenta

$$hv^2$$

mass
angular momenta
per second

$$kg\left[\frac{m^2}{s}\,\frac{1}{s}\right]$$

The EM mass-Energy relationship can be revealed either by linear or angular momentum analysis

Energy-momentum relationship

The total number of Planck quanta [mass-angular momenta] in any physical system is directly related to the square of its linear momentum [mass-velocity]

$$h = \frac{E}{v^2}$$

$$m = \frac{E}{v^2}$$



Quantised Energy-momentum





Linear Energy-momentum

mass-energy momenta

The omega geometry of Energy produces the direct relationships between Planck's constant-quanta and mass-Energy-momentum of any spatio-temporal co-ordinate system

$$E = m\Omega v^2$$

Quantised Angular Momenta is an equilateral geometry

$$E = pc$$

Linear momentum is a vector Force

$$m\Omega v^2 = E = mv^2$$

mass is a derived physical property relating Energy momenta to Velocity

Copyright ABRAHAM [2008] - all rights reserved

CHARGE

Charge is a measure of mass.QAM/second
[the equilateral geometry of Energy]
that gives form to all physics

ElectroMagnetic Charge
is a quantum property
resulting from the equilateral
QAM geometry of mass-Energy



The two ElectroMagnetic charge
geometries possible can be modelled
by the flux of electrical energy
in ideal inductive loops

It is a measure of the arrangment of Planck quanta
geometries/topologies within any specific
space-time co-ordinate system

q

Clockwise inductive
energy flux



Positive charged
mass-energy momenta

$$\frac{hv}{c^2}$$

$$kg\,\frac{m^2}{s}\,\frac{s^2}{m^2}$$

$$kg.s$$

1.33518 e-20 s

Counter clockwise
energy flux



Negative charged
mass-energy momenta

q

Copyright ABRAHAM [2008] - all rights reserved

Measuring charge geometries

Charge comes in two types, called Negative and Positive
which create the Law of Interaction (historically, the Law of Attraction)

q

quantised Charge

[v] [v]

Q

nett Charge

[v-v]

All charged masses seek equilibrium

Charge geometry is velocity invariant



Clockwise Energy flux



Charge is the geometric source of all

EM forces



anti-Clockwise Energy flux

Historically defined as a physical property of mass-Matter that causes it to experience a force
charge is actually the result of the equilateral geometry of qantised mass angular momenta
which provides the physical mechanics of mass-ENERGY-Matter differentiation and interaction

The SI unit of quantity of charge is the Coulomb, C ≈ mass seconds ≈ kg.s which can also be expressed as Amp-seconds

Copyright ABRAHAM [2008] - all rights reserved

EM Field Geometry


v
c²
c⁴
N
S
c²
v


ρ/m²
v
kg
E
m
hv
v²
ElectroMagnetic mass-energies
c²


v
c²
c⁴
N
S
c²
v

mass-energies are 2D radiant EM field geometries

[299,792,458 m/s]

'c' forms a CONSTANT of proportionality for different spatio-temporal co-ordinate systems used to measure mass-ENERGY-Matter

All Matter are 3D EM standing wave topologies



EM fields create 'interaction-at-a-distance'


ρ/m³
0
KG
ε₀
M
hv
v²
Matter
c⁴


v
KE
M
KE
v
N S
S N
c⁴

Electrostatic Matter has opposing 2D KEM fields

Copyright ABRAHAM [2008] - all rights reserved

Energy quantisation

All mass-Energy-Matter can only have certain integer Energy-momenta,
[mass-Energy in all its forms is QUANTISED]

q

Net quanitised angular momenta
[inductive energy flux]
determines Charge

$$m\left[\frac{\Omega}{c^2}\right]$$

$$kg\,\frac{m^2}{s}\cdot\frac{s^2}{m^2}$$

seconds

Transverse quanta
create Quantum Levels



E = $h\nu$

Bosons

E = mv^2

Joules

$$kg.\frac{m^2}{s}$$

Planck's Constant

q

Net quanitised angular momenta
[inductive energy flux]
determines Charge

$$m\left[\frac{\Omega}{c^2}\right]$$

$$kg\,\frac{m^2}{s}\cdot\frac{s^2}{m^2}$$

seconds

Scalar (nett) quanta
create Square Energies

The equilateral geometry of
quantised angular momentum
creates charged masses

Planck's Constant is in fact
mass x equilateral QAM

$$kg.\frac{m^2}{s}$$

n.Planck quanta per second is Energy

Planck's Constant
can be described in
a number of differing ways

Scalar Energy x Time $kg.\frac{m^2}{s^2}.\,s$

Linear momentum x Distance $kg.\frac{m}{s}.\,m$

Copyright ABRAHAM [2008] - all rights reserved

Tetryonic Mnemonics



Energy momentum


v
p
m
Ω
hv
c
v²
c²



Electrical flow



velocity of propagation

Many physical relationships are can be represented with DELTA mnemonics



Inertial Force



UNITS OF PHYSICS

λ	Wavelength	m
v	Velocity	$\frac{m}{s}$
Ω	Quantised Angular Momentum	$\frac{m^2}{s}$
$\frac{1}{c^2}$	2D radiant mass-energies	$\frac{s^2}{m^2}$
C	Coulombs As	$kg\ s$
ε_0	Electric Constant	$\frac{F}{m}$
p	Momentum	$kg\frac{m}{s}$
m	*mass-energy geometries*	kg

$\frac{1}{s}$	Frequency	f
$\frac{m}{s^2}$	Acceleration	a
$kg\frac{m^2}{s}$	Planck's Constant	h
$\frac{s^4}{m^4}$	3D standing-wave mass-Matter	$\frac{1}{c^4}$
KG	Amperes $\frac{C}{s}$	A
$\frac{H}{m}$	Magnetic Constant	μ_0
$kg\frac{m}{s^2}$	Force	F
KG	*mass-Matter topologies*	M

$N\frac{m^2}{C^2}$

Coloumb's Constant

k

mass

Matter

G

Newton's Constant

$N\frac{m^2}{KG^2}$

Physics is filled with numerous units of measurement comprised of various inter-related components of physical measurement

Tetryonic geometry offers a complete geometric understanding of physical terms such as Charge, mass geometries, Energy densities, Matter topologies and spatial impedance along with their roles in physical mechanics

Scalar mass-energies

have an EQUILATERAL geometry
(60°- 60°- 60°)


v
p
ε_0
m
E
v
v^2
F

$$\sin\frac{\pi}{3} = \sin 60^\circ = \frac{\sqrt{3}}{2}$$


a
60°
s1
s2
b
60°
60°
c
s3

ac = ac = bc

cos 60° = sin 30 ° = 1/2

sin 60° = cos 30 ° = √3/2

$$\cos\frac{\pi}{3} = \cos 60^\circ = \frac{1}{2}$$

$\frac{\sqrt{3}}{2}$ **s**

The Area of an Equilateral triangle

½ base x height



$$\tan\frac{\pi}{3} = \tan 60^\circ = \sqrt{3}$$

Copyright ABRAHAM [2008] - all rights reserved

Pythagorian geometry

Energy geometries within Physics including Special Relativity and Lorentz corrections have historically been incorrectly illustrated as having the geometry of right angled triangles



$$E^2 = p^2c^2 + m_0^2c^4$$

Generalizing, we see that the square of the total mass-energies is the sum of the components squared.
[shown incrorectly formulated in this above equation]

We can see an origin of distance in spacetime relating to velocity in pc in which Energy is subject to Lorentz corrections [v/c]

$$E = pc.$$

Additionally, EM mass can be directly related to the energy content of a body by the velocity of Energy

$$E = mc^2$$

Physics is geometry,
one cannot be separated from the other



$$mv^2 = E = hv^2$$

There are three ways to look at geometry
– mathematically, verbally, and visually,

Of the three, Visually will be shown to be superior leading to intuitive understandings of Physics, Chemistry, Electrodynamics and Gravitation along with all their related physical attributes

6.629432672 e-34 J

Planck quanta

$$[m\Omega v]^2$$

mass velocity

7.376238634 e-51 kg

$$mv = p$$

Tetryonic geometry

The source of all the physical relationships of mass-Energy momenta & their constants is the geometry of equilateral Planck Triangles (and all texts must be corrected)



F

$$\sum \mathbf{F} = \frac{d\mathbf{P}}{dt} = m\frac{d\mathbf{v}}{dt} = m\mathbf{a}$$

Newton's Second law of Motion
is based on changes to linear momentum

$$\mathbf{F} = m\mathbf{a}\,.$$

Copyright ABRAHAM [2008] - all rights reserved

Tetryonics and Pi radians

Although not historically considered a physical constant, π appears routinely in equations describing fundamental principles of the Universe, due in no small part to its relationship to the nature of the circle and, correspondingly, spherical coordinate systems.

The quantised equilateral geometry of mass-energy momenta is measured in π radians

Using units such as Planck units can sometimes eliminate π from formulae.

Heisenberg's uncertainty principle, which shows that the uncertainty in the measurement of a particle's position (Δx) and momentum (Δp) can not both be arbitrarily small at the same time:

$$\Delta x\,\Delta p \geq \frac{h}{4\pi} = \frac{\hbar}{2}$$

Einstein's field equation of general relativity:

$$R_{ik} - \frac{g_{ik}R}{2} + \Lambda g_{ik} = \frac{8\pi G}{c^4}T_{ik}$$

The cosmological constant Λ from Einstein's field equation is related to the intrinsic energy density of the vacuum ρvac via the gravitational constant G as follows:

$$\Lambda = 8\pi G\ \rho_{vac}$$

Coulomb's law for the electric force, describing the force between two electric charges (q1 and q2) separated by distance r:

$$F = \frac{|q_1 q_2|}{4\pi\varepsilon_0 r^2}$$

Magnetic permeability of free space relates the production of a magnetic field in a vacuum by an electric current in units of Newtons (N) and Amperes (A):

$$\mu_0 = 4\pi \cdot 10^{-7}\,\mathrm{N/A}^2$$

Kepler's third law constant, relating the orbital period (P) and the semimajor axis (a) to the masses (M and m) of two co-orbiting bodies:

$$(\frac{2\pi}{P})^2 a^3 = \omega^2 a^3 = G(M+m)$$

and the Gaussian formula for a Normal Distribution:

$$f(x) = \frac{1}{\sigma\sqrt{2\pi}}\, e^{-(x-\mu)^2/(2\sigma^2)}$$

$$\pi = \frac{C}{d}.$$



$$\pi = \frac{A}{r^2}.$$



Pi radian mass-energy fascia geometries



All Equilateral triangles have internal angles that add up to 180°

Equilateral Triangles can be tessellated in turn forming larger equilateral geometries

SQUARED numbers in physics are EQUILATERAL geometries


π/6
30°
a
a
radians
degrees
π
π/3
π/2
90°
60°
a
180°


arc length = radius
a
a
π
radian
hν
radius
a


2π
360°
60
a
a
π
3π/2
270°
2π
90°
π/2
60
a
a
60
180°
π

nπ mass-energy geometries

180° π An equilateral triangle of mass-energy momenta has a geometry of π radians 2π **360°**




2π
a
5π/3
π/3
a
a
360°
300
60
6π
240
120
180
4π/3
2π/3
a
a
a
π



Copyright ABRAHAM [2008] - all rights reserved

Tetryonic Cardinal Angles

equilateral mass-energy geometries form tetrahedral mass-Matter topologies

EM Charge

Equilateral energies

Q

E

Space

Time


360°
330°
30°
300°
60°
270°
90°
N
N
S
S
240°
120°
210°
150°
180°

M

m

Matter topologies

mass geometries

radiant light

in radial spatial co-ordinate systems defined by the speed of light

Copyright ABRAHAM [2008] - all rights reserved

Charge EM Field Planck quanta

$\text{ODD}\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$

Bosons & quantum levels ElectroMagnetic mass velocity

Kinetic Energies EM Field Planck quanta

$\text{EVEN}\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$

Photons & EM waves ElectroMagnetic mass velocity



ALL Matter topologies stem from tessellated equilateral mass-energies

Matter EM Field Planck quanta

$4n\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$

Fermions ElectroMagnetic mass velocity

Matter's 4π mass-Energies
ares Lorentz invariant to accelerations

mass-energy geometries


360°
60°
2D planar radiant mass-energies
120°
120°
3D standing-wave Matter topologies
60°
60°
60°
60°
60°
60°
60°
60°
60°
60°
hv
v²
180°

Matter topologies

Copyright ABRAHAM [2008] - all rights reserved

Tetryonic geometry


Electric Flux
Permittivity Field
1
[1-0]
E
ε_0
Ω
+
N
S
Magnetic Permeability
Dipole field
Electric
field
ε_0
π
μ_0
μ_0
Magnetic
pole
Magnetic
pole
Electric Flux
Permittivity Field
1
[0-1]
E
ε_0
Ω
–
S
N
Magnetic Permeability
Dipole field

equilateral quantised angular momenta
is the foundational geometry of all mass-ENERGY-Matter

Copyright ABRAHAM [2008] - all rights reserved

The Golden Triangle

Planck's formulation for Energy is imprecise for use in Tetryonics
and does not reflect the velocity-momenta relationship
inherent in the equilateral geometry of Energy

Planck quantum levels

Energy is gained or lost in
whole number multiples of the quantity hv

$$E = n[hv]$$

ODD

Charge EM Field Planck quanta

$$\text{ODD}\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$$

Bosons & quantum levels ElectroMagnetic mass velocity

$$3 = 3.[1]$$

$$9 = 9.[1]$$

$$25 = 25.[1]$$

$$hv$$

The generalise formulation of Plank's heat law
E = nhv is now changed to a specific formulation of
E = [ODD] hv for transverse quantum levels [Bosons]


v
1
1^2
3
2^2
5
3^2
7
4^2
9
5^2
11
6^2
13
7^2
h
v^2
1
2
3
4
6
7
8
2
4
6
8
5
9
11
15
10
12
14
16
18
20
22
24
17
23
25
27
35
26
28
34
36
38
40
46
48
37
39
43
47
49
51
53
55
59
61
63
50
52
54
56
58
60
62
64

mass-energy momenta are geometrically related to velocity

Scalar energy quanta

Energy is gained or lost in equilateral geometries
as whole number multiples of the quantity hv²

$$E = n[hv]$$

SQUARED

Planck quanta

$$E = n\pi\left[[m\Omega v^2]\right]$$

mass velocity

$$3 = 3.[1^2]$$

$$9 = 1.[3^2]$$

$$25 = 1.[5^2]$$

$$hv^2$$

The general formulation of Plank's heat law
is also changed to a specific formulation of
E = hv² for scalar EM waveforms [ENERGY]

Tetryonic geometry [nπ] redefines Planck's quantum formulation for heat energies from a generalised equation for 2D energy momenta into a geometric formulation for all mass-energy momenta in Matter

[all equilateral [π] geometries contain square number quanta]

Copyright ABRAHAM [2008] - all rights reserved

Scalar field geometries

All scalar fields are comprised of Transverse and Longitudinal mass-energy momenta all of which are formed from equilateral quantum geometries

Charge is a conserved force

Bosons are transverse ODD planck geometries

$$E = n\pi\left[\left[h\nu\right]\right]$$

Planck quanta

Energy is a conserved quantity

Energy is scalar SQUARE planck quanta

$$E = n\pi\left[\left[h\nu^2\right]\right]$$

Planck quanta squared



Energy is a scalar field

Photons are 2π Planck quanta

E = hf

Charge is a measurement of QAM per unit of Time

EM mass is a measurement of scalar Energy per unit of Time

Planck quanta

Energy is gained or lost in whole number multiples of the quantity hν

Scalar energies

Energy is gained or lost in equilateral quanta containing whole number multiples of $h\nu^2$

All energy is comprised of EM fields

All squared energy geometries have component quantum levels

Squared energy levels in quantum physics

are in fact equilateral Planck mass-energy geometries


linear
momentum
[square roots]
v
hv
ODD
number
quanta
2n-1
[n] + [n-1]
hv^2
SQUARED
number
quanta
n
1
+
3
+
5
+
7
+
9
+
11
+
13
+
hv
1^2
2^2
3^2
4^2
5^2
6^2
7^2
v^2
1
4
$\sum_{1}^{n}$ [2n-1]
9
16
25
36
49
64
$\int_{1}^{n}$ [2n-1]
Energy Levels
Charged bosons form scalar energies
Energy is the scalar Integral of Bosons
1
2 3 4
5 6 7 8 9
10 11 12 13 14 15 16
17 18 19 20 21 22 23 24 25
26 27 28 29 30 31 32 33 34 35 36
37 38 39 40 41 42 43 44 45 46 47 48 49
50 51 52 53 54 55 56 57 58 59 60 61 62 63 64
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1
E
(n-1)
N
(n-1)

Cumulative Distribution

NORMAL DISTRIBUTION

['Bell Curve']

Probability Distribution

Energy quanta defined

Quantum levels

Charge is gained or lost in odd number multiples of the quantity hv

$$E = n\pi[[hv]]$$

Planck quanta

transverse

ODD quanta

Quantum

The **number** of Planck quanta in any physical system

$$v = f/2$$

Scalar Energies

Energy is gained or lost in equilateral geometries containing whole number multiples of the quantity hv^2

$$E = n\pi[[hv^2]]$$

Planck quanta squared

scalar

SQUARE quanta


v
1
3
5
7
9
11
13
hv
1^2
2^2
3^2
4^2
5^2
6^2
7^2
v^2
1
2
3
4
5
6
7
8
1/2 1 3/2 2 5/2 3 7/2 4 7/2 3 5/2 2 3/2 1 1/2

Longitudinal

Transverse

Quantum Levels

The number of repeating waveform **cycles** in a system

$$2v = f$$

Frequency

EVEN quanta

Tetryonic field equation

E

$$E = n\pi\left[\left[\underset{\text{mass}}{\overset{\text{Planck}}{m}}\,\Omega\,\underset{\text{velocity}}{\overset{\text{quanta}}{v^2}}\right]\right]$$

electromagnetic energy is a scalar

m

$$\underset{\text{mass}}{n\pi}\left[\underset{\text{ElectroMagnetic}}{\overset{\text{EM Field}}{\left[\varepsilon_0\mu_0\right]}}.\left[\underset{\text{mass}}{\overset{\text{Planck}}{m}}\,\Omega\,\underset{\text{velocity}}{\overset{\text{quanta}}{v^2}}\right]\right]$$

mass is an inertial constant
that relates Force to acceleration

[v-v]
Q

$$\underset{\text{Bosons \& quantum levels}}{\overset{\text{Charge}}{ODD\pi}}\left[\underset{\text{ElectroMagnetic}}{\overset{\text{EM Field}}{\left[\varepsilon_0\mu_0\right]}}.\left[\underset{\text{mass}}{\overset{\text{Planck}}{m}}\,\Omega\,\underset{\text{velocity}}{\overset{\text{quanta}}{v^2}}\right]\right]$$

equilateral charge geometry
is Lorentz invariant

KE

$$\underset{\text{Photons \& EM waves}}{\overset{\text{Kinetic Energies}}{EVEN\pi}}\left[\underset{\text{ElectroMagnetic}}{\overset{\text{EM Field}}{\left[\varepsilon_0\mu_0\right]}}.\left[\underset{\text{mass}}{\overset{\text{Planck}}{m}}\,\Omega\,\underset{\text{velocity}}{\overset{\text{quanta}}{v^2}}\right]\right]$$

KEM fields mass-energy geometries
are Lorentz variant to accelerations

M

$$\underset{\text{Fermions}}{\overset{\text{Matter}}{4n\pi}}\left[\underset{\text{ElectroMagnetic}}{\overset{\text{EM Field}}{\left[\varepsilon_0\mu_0\right]}}.\left[\underset{\text{mass}}{\overset{\text{Planck}}{m}}\,\Omega\,\underset{\text{velocity}}{\overset{\text{quanta}}{v^2}}\right]\right]$$

Matter's 4π mass-energy topologies
are Lorentz invariant to accelerations

$$E$$

$$\frac{E}{c^2}$$

$$\frac{\Omega}{c^2}$$

$$\tfrac{1}{2}m\left[\frac{v^2}{c^2}\right]$$

$$4n\pi\left[\frac{E}{c^4}\right]$$

Energy momenta geometry



Energy is the total Planck quanta per second



EM mass is scalar energy per unit of Time



Charge is the nett Angular momentum per spatial co-ordinate system



Kinetic Energy is the Electric field
mass-energy of Matter moving at v



mass-energy geometry



Matter topology

mass-Energy equivalence


$kg\frac{m}{s}$
m
sec
v
kg
E
[mΩv²]
$\frac{m^2}{s}$
v²
$kg\frac{m^2}{s}$
h
sec
v
p
m
v²
kg
v
m
Ω
v²

$$m = \frac{E}{v^2}$$

$$mv^2 = hv^2$$

$$h = \frac{E}{v^2}$$

The relationship between scalar mass-energy, linear momentum and quantised angular momenta is the result of equilateral geometry

linear momentum
mass velocity

quantised
angular momenta

mass-Energy geometries


v
P
E
c^2
v^2
v
P
m
v^2
v
m
v^2
v
ε_0
m
μ_0
μ_0
v^2
v
ε_0
μ_0
μ_0
v^2
v
m
Ω
v^2

Leibniz - Newton

Planck - Einstein

$p=mv$

$mv^2 = E$

EM mass

Energy

$m=\frac{E}{v^2}$

h

Planck's Constant

$kg\frac{m^2}{s}$

$\frac{E}{v^2} = h$

velocity

quanta

$mv^2 =$

$kg\frac{m^2}{s^2}$

$kg\frac{m^2}{s}\frac{1}{s}$

$= hv^2$

velocity squared

quanta squared

There exists an intrinsic geometric relationship between mass-velocity and the quantisation of Energy momenta

Copyright ABRAHAM [2008] - all rights reserved


c
p
ε_0
m
μ_0
μ_0
v^2
c^2

Electro-Magnetic mass

EM mass-energy

$$E = mc^2$$

EM mass is related to Matter
throught the square of the velocity of light
of 8.987551787 e16 m²/s² [c²]

EM mass-Matter

$$E = Mc^4$$


c
E
m
ε_0
v^2
c^2

Matter's energy quanta

scalar EM mass



$$M = \frac{E}{c^4}$$


0
ε_0
E
M
μ_0
μ_0
v^2
c^4

3D Matter has 2D mass-energies moving at c
in a 4π standing wave topology
creating a closed volume

quantised mass



$$h = \frac{E}{v^2}$$

Kinetic Electro-Magnetic fields

[The energies of Motion]


v
ε_0
mass-energy
geometry
M
v^2
Matter topology
c^4

Matter in motion produces secondary Kinetic energies and a Magnetic moment

$$\mu_B = \frac{1}{2}Mv^2$$


magnetic moment
μ_0
KE
ε_0
p
v
c^2
v^2

$$KE = \frac{1}{2}Mv^2$$

All Matter in motion possess momenta and kinetic mass-energies in extrinsic KEM fields


v^2
μ_0
μ_0
KE
KE
ε_0
ε_0
p
p
v
v
v^2
c^2

$$E_\gamma = 2\frac{mv^2}{c^2}$$

These 2D planar fields are subject to Lorentz factor corrections that apply to the KEM field mass-energies of Matter in motion

$$p^2 = E = Mv^2$$

The Electric field energy in any EM field is equal and orthogonal to the Magnetic field energy

$$p^2 = KEM = Mv^2$$

Charge & Kinetic EM fields



Charges are the result of quantised angular momenta

Kinetic Energies result from Matter in motion

$$mv^2 = E = hv^2$$

$$p^2 = E = m\Omega \mathbf{v}^2$$



$$KEM = M\mathbf{v}^2$$

$$KE = \frac{1}{2}M\mathbf{v}^2$$

EM field energies externalised on the fascia of 3D Matter geometries form the physical property known as elementary Charge

[k]EM energies in amy region of free space are viewed as either
a Kinetic energy field with an associated Magnetic moment
or
a neutral charge Photon of ElectroMagnetic mass-energy


ε_0
μ_0
μ_0

$$m_0 = \frac{E}{c^2}$$

Rest mass is equivalent to the total quantity of Energy in a body or system (divided by c^2)



2D fields propagate at c
3D Matter moves at v



inertial mass

$$m = \frac{F}{a}$$


v
mass geometries
ρ/sec
kg/m²
Matter topologies
ρ/sec^2
KG/m³
ε_0
m
E
Longitudinal mass
μ_0
μ_0
Transverse mass
$h\nu$
v^2
c^2

Inscribed equialteral triangles
are the inverse of any radial-circular
spatial geometry circumscribing them

mass must be distinguished from Matter in physics,
because Matter is a poorly-defined concept in modern science,
and although all types of agreed-upon Matter exhibit properties of mass,
it is also the case that there many types of Energy that posses NO Matter topology,
such as potential energy, kinetic energies and electromagnetic radiation (photons)

$$\underset{\text{mass}}{n\pi}\left[\overset{\text{EM Field}}{\underset{\text{ElectroMagnetic}}{[\varepsilon_0\mu_0]}}.\left[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\overset{\text{quanta}}{\underset{\text{velocity}}{v^2}}\right]\right]$$

The term 'massless' must be re-termed 'Matterless'
to reflect true physical attributes of mass-energy-momenta

EM mass is a planar measurement of 2D energy per unit of time

Thus, all 3D Matter topologies have charged fascia comprised of 2D scalar of mass-energies,
but closed volume 3D topology is not a property of 2D EM mass-energy geometries

mass

$$\rho$$

EM mass is a measure of planar energy density per second

$$\frac{mv^2}{c^2} \quad \boxed{\frac{m\Omega v^2}{c^2}} \quad \frac{h\nu^2}{c^2}$$

per unit of time

EM mass geometries are subject to Lorentz corrections

velocity

QAM
quanta

$$\frac{mv^2}{c^2} = \frac{m\Omega v^2}{c^2}$$

per unit of time

Gravitational Matter

$$g = G\frac{M}{r^2}$$

Copyright ABRAHAM [2008] - all rights reserved

Electromagnetic mass-energy



In physics, EM mass–energy equivalence is the concept that the EM mass of a body is a measure of its energy content

Using this concept, EM mass is a property of all Energy, and Energy is a property of all EM mass, and the two properties are connected by a constant.

Using Tetryonic geometry it can be shown that the constant is the equilateral geometry of QAM thus unifying Classical mechanics and Relativisic mechanics



2D mass-ENERGY geometry is NOT **3D Matter topology**

$$m = \frac{E}{v^2}$$

Classical mass

$$m = \frac{E}{c^2}$$

Relativistic mass



radiant 2D mass-energies
are planar equilateral
energy geometries



ElectroMagnetic mass
is a measure of the scalar energy momenta
in any spatial co-ordinate system

Relativity shows that rest mass and rest energy are essentially equivalent, via the well-known relationship ($E=mc^2$)



standing-wave 3d mass-Matter
are tetrahedral energy
momenta topologies

EM mass-Energy-Matter





$$\left[\frac{\Omega}{c^2}\right]$$

Charge is a measure of the quantised angular momentum of any physical system

Tetryonic Matter

planar spatial Impedance

Planck quanta

$$T\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

3D topology

ElectroMagnetic

2D mass

velocity

Planck quanta

$$\left[m\Omega v\right]^2$$

mass velocity


Bosons
v
n
v
c²

$$1\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

ODD quanta


2D mass-energies
3D Matter
M
Matter
c⁴

$$4n\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

TETRYONS


Photons
+
f
−
c²

$$2\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

EVEN quanta

EM mass-Energy momenta

Energy

$$\left[\frac{m\Omega v^2}{s}\right]$$

E

6.629432672 e-34 J

mass-Energy

7.376238634 e-51 kg

m

$$\left[\frac{E}{c^2}\right]$$

mass

Planck's Constant

is the 'quantum of Action'



$$6.629432672 \times 10^{-34}\ \mathrm{J.s}$$

mass momenta

quantised angular momenta

$$\left[\frac{m^2}{s}\right]$$

Ω

0.0012 m2/s

Charge-momenta

1.33518 e-20 s

s

$$\left[\frac{\Omega}{c^2}\right]$$

charge

Copyright ABRAHAM [2008] - all rights reserved


v
n1
1
c²
v
n2
4
c²
v
n3
9
c²
v
n4
16
c²
ε₀
c²
ρ
2D
EM mass-energy geometry
per square metre
c²
ε₀
c²
mass
m
kg/s
c²
ρ
Energy density
per spatial region
Tπ [[ε₀μ₀].[mΩv²]]
3D Matter
EM Field
ElectroMagnetic
Planck
quanta
2D mass
velocity
c⁴
ρ
c⁴
3D
EM mass-Matter topology
per cubic metre
c⁴
Matter
M
KG/s²
c⁴
v
n5
25
c²
v
n6
36
c²
v
n7
49
c²
v
n8
64
c²

Copyright ABRAHAM [2008] - all rights reserved

Zero Point Fields [ZPFs]

IDEAL QUANTUM INDUCTORS
(equilateral triangle Energy geometry)



ZPFs are quantum inductive tank circuits
(Short-circuited 'IDEAL' inductors with energy)
ZPFs charge energies do NOT oscillate
[The magnetic dipole vector determines charge]

The EM FIELD

Electric flux fields can propagate in any direction
Magnetic fields are always at 90 degrees to Electric fields

Magnetic dipole fields propagate in 2 directions at
180 degrees to each other (bi-directionally)
forming North and South poles

Electric flux field energy is directly proportional to
the resultant Magnetic dipole field energy
and vice versa



The linear Electric field strength is directly
proportional to its associated transverse
Magnetic field which propagates bi-directionally
from & into the bloch wall of the Zero point field



h

Positive Charge ZPF

Nett positive Planck quanta
with North-South m-dipole vector



Zero Point Fields consist of
Electric and Magnetic (EM) fields
propagating at 90 degrees
to each other

Magnetic MONOPLES do NOT exist

Energy quanta always form charged Electric fields and dipole Magnetic fields

As localised energy quanta increases
(number of ZPFs per time unit)
the charge geometry remains the same



h

Negative Charge ZPF

Nett negative Planck quanta
with South-North m-dipole vector



$mv^2 = E$

Quantised Angular Momentum

is the equilateral geometry of scalar energy momenta per unit of time

$E = hv^2$

$$\frac{m^2}{s}$$



m/s
v
p
ε0
m
E
kg m/s
v²
m²/s²
vector linear momentum
1 second



mΩ
mass-QAM
6.629432672 e-34 J.s
Planck
quanta
[mΩv]²
mass
velocity
7.376238634 e-51 kg
mass
m



v
m
Ω
E
kg m²/s
v²
m²/s²
quantised Energy momenta
1 second

p

linear momentum

$kg\,\frac{m^2}{s}$



Normally percieved as vector rotation about a point
quantised angular momentum is actually
an equilateral gaussian flux geometry

(there is no physical vector rotation component)

h

Planck's Constant

$kg\,\frac{m^2}{s}$

Charged mass & Matter in motion

produce differing but related measurments of EM force





Charged masses per second $\frac{C}{s} \approx kg \approx A$ Charged Matter in motion

Amperes

By definition in Tetryonics the quantised angular momentum of mass in any defined spatial co-ordinate system provides the quantum basis for

$$\boxed{kg\,\frac{m^2}{s}}$$

charged mass-energies

Quantised angular momenta creates CHARGE

Vector linear momentum creates CURRENT



charged mass

$$C \approx kg.s \approx As$$

Coulombs

Amp.sec



Charge, through its energy interactions, creates the geometric scaffolding for ALL 3D EM mass-Energy-Matter geometries

Charged mass geometry

The symmetry of Charge geometries provides a geometric foundation
for all mass-Energy-Matter particles and physical forces


mv^2
v
p
E
v^2
$kg\left[\frac{m^2}{s^2}\right]$
v
p
Ω
$\frac{1}{c^2}$
v^2
$m\Omega v^2$
v
E
v^2
$\left[kg\frac{m^2}{s}\right]\frac{1}{s}$
E
ε_0
Ω
+
N
S
c^2
Q
Q
E
ε_0
Ω
-
S
N
c^2

Classical analysis of Energy
[mass velocity] does not
reveal the nature of Charge

The Tetryonic geometry of Energy
reveals Charge as a product
of quantised angular momentum

Charge is the result of quantised angular momentum
and can also be modelled electrically as the
uni-directional rotation of inductive energies

$$\left[m\left[\frac{\Omega}{c^2}\right]v^2\right]$$

'a un-balanced (broken) energy symmetry resulting from
the nett geometry of equilateral EM mass-energy quanta'



electrically modelled as anti-clockwise inductive energy flux

Negative Charge Zero Point Field

Positive Charge Zero Point Field

electrically modelled as clockwise inductive energy flux

Electric Field Apex
E
Q
+
N
S
North Magnetic Apex
South Magnetic Apex
Electric Flux Permittivity Field
ε0
Ω
μ0
Magnetic Permeability Dipole field
½f
hν
N
S
m
μ0
μ0
ε0
E
E
m
N
S
ε0
μ0
μ0
hν
½f
Electric Flux Apex
E
Q
-
S
N
South Magnetic Field Apex
North Magnetic Field Apex
Electric Flux Permittivity Field
ε0
Ω
μ0
Magnetic Permeability Dipole field

Copyright ABRAHAM [2008] - all rights reserved

Elementary and quantum Charges

" All known Fermions have charge topologies that are integer 1/3 multiples of the elementary charge "

ε_0
Ω
μ_0
μ_0

It can be shown that the "quantum of charge"
Is the intrinsic angular momentum of a Planck mass

It then follows that Quasi-particles
[Tetryons and Quarks]
have charge topologies with nett charges of 0, 4 and 8

Further, it can be shown that the "elementary charge"
applied to Leptons and Baryons (12 times quantum charge)
Is reflective of their nett charged Matter topologies

topology *charge*

$$T\pi[\pm q]$$

geometry



All Charged particles and their respective KEM fields
can be modelled with ZPF field geometries
reflective of their nett Charge topologies

Opposites attract
Similars repel

Quarks

up	anti-down	down	anti-up
+2/3	+1/3	-1/3	-2/3
Charmed Top	Strange Bottom	Strange Bottom	Charmed Top

Leptons

Positron	neutrino	Muon
Tau anti-electron	Tau neutrino	Tau

Baryons

+1	0	-1
Proton	**Neutron**	**Negatron**

quantised Charges
(EM energy flux rotation
within a ZPF geometry)

q
quantum charges

[v] [v]

The elementary charge, usually denoted as e,
is the electric charge carried by a single proton,
or equivalently,
the absolute value of the electric charge
carried by a single electron

[v-v]

Q
Elementary charges

Elementary Charges
are the nett charge created
by mass-energy-Matter
topologies

Tetryons

4	0	4
[4-0]	[2-2]	[0-4]

Quarks

up	down	down	up
8	4	4	8
[10-2]	[8-4]	[4-8]	[2-10]

12	0	0	12
[12-0]	[6-6]	[6-6]	[0-12]
e	νe	νe	e

Leptons

Baryons

Proton	Neutron	Negatron
12	0	12
[24-12]	[18-18]	[12-24]

All Charges seek Equilibrium

Copyright ABRAHAM [2008] - all rights reserved

Sir Issac Newton

(25 December 1642 – 20 March 1727)



Any changes to velocity
result in changes to Energy-momenta
within a charged geometry

$$\sum \mathbf{F} = 0 \Rightarrow \frac{d\mathbf{v}}{dt} = 0$$

Newton's first law of motion says:
"A body maintains the current state of motion unless acted upon by an external force."

$$F = ma$$

Inertia is the resistance of any physical object to a change in its state of motion or rest, or the tendency of an object to resist any change in its motion.

It is proportional to an object's mass.



Ideal Inductive loops (ZPF quanta) will oppose ANY changes to their energy levels and consequently, Inertia can be viewed as an outcome of quantum ZPF self-Inductance

Inertia

The moment of inertia plays much the same role in rotational dynamics as mass does in linear dynamics, describing the relationship between angular momentum and angular velocity, torque and angular acceleration, and several other quantities

The difference between the impeding (inertial) linear momenta and the co-linear (supportive) momenta is a result of the nett Planck mass-energy momenta within the charged geometries of Matter & its KEM fields



Planck Quanta

are often defined as the "quantum of action"

h

Planck's Constant

$$kg\,\frac{m^2}{s}$$

The Planck constant (denoted h), is a geometric constant resulting from QAM in quantum mechanics


BOSONS
hv
ENERGY
hv^2
ε_0
m
μ_0
μ_0
v
v^2
c^2

Planck quanta are the minimum energy geometry possible (equilateral mass-energy momenta)

hv

$m\Omega v^2$

Planck quanta per second

$$kg.\left[\frac{m^2}{s}\right].s^{-1}$$

Planck's constant relates the energy in one quantum (photon) of electromagnetic radiation to the frequency of that radiation

Charge is a result of QAM geometry

quantised angular momentum is the result of equilateral geometry


rotational Angular momentum
≈
Quantised Angular momentum
v^2

Photons have neutral quanta geometry

$E = n.h\nu$

Planck Number


+8
[36–28]
ν
1
3
5
7
9
11
13
15
ε_0
m
Ω
64
hν
ν^2
nett positive EM mass-energies
c^2

hν
tranverse
Bosons

Max Planck



(April 23, 1858 – October 4, 1947)

hf
longitudinal
Photons


ν
–8
[28–36]
1
3
5
7
9
11
13
15
ε_0
m
Ω
64
hν
ν^2
nett negative EM mass-energies
c^2

$1e19\nu = n = 5e18f$

quantum number

BOSONS
are the quanta of Charge

$$\underset{\text{Boson}}{1\pi}\left[\overset{\text{EM Field}}{\underset{\text{ElectroMagnetic}}{[\varepsilon_0\mu_0]}}.\left[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\underset{\text{velocity}}{\overset{\text{quanta}}{\nu^2}}\right]\right]$$

Equating nu̲mber of quanta
is the source of a number

$h\nu \neq hf$

Planck Einstein

$$\underset{\text{Photon}}{2\pi}\left[\overset{\text{EM Field}}{\underset{\text{ElectroMagnetic}}{[\varepsilon_0\mu_0]}}.\left[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\underset{\text{velocity}}{\overset{\text{quanta}}{\nu^2}}\right]\right]$$

to photon f̲requency
of quantum misconceptions

PHOTONS
are the neutral quanta of EM waves


E
h
ν
N
S
$\frac{1}{2}f$


E
h
ν
S
N
$\frac{1}{2}f$

The Planck constant was first described as the proportionality constant between the energy (E) of a photon and the frequency (ν) of its associated electromagnetic wave.
[it in fact describes the energy of bosons]

The zero-point energy for a simple harmonic oscillator of frequency f is ½ hf

The relation between the energy and frequency is called the Planck–Einstein relationship.

2ν
S
S
E
+
h
-
E
N
N
f

Copyright ABRAHAM [2008] - all rights reserved

Quantum Inductors

+ ZPF

A positive ZPF can
be viewed as a quantun quoin
or an quantum 'ideal' inductor
with an internalised energy flux
that is the opposite of
a negative ZPF

Clockwise current flow



POSITIVE

Quantum L circuit

[quantum inductive circuit]

An "ideal inductor" has inductance,
but no resistance or capacitance, and will not dissipate energy
(until it interacts with other ZPFs or Matter) and forms the basis for
all Charge-Parity-Time [CPT] interactions

A ZPF is fixed in either a + or - state
[Quantum Inductor circuit]

Its energy flux direction as modelled electrically] is relative
to the observer's view or the direction of measurement

Charge polarity is opposed on opposite faces
of the same quoin [quantum coin]

The direction of inherent energy flux
from the presective of the observer
determines ZPF charge polarity

The Quantum Inductor (L) circuit stores
energy as EM mass in π geometries,
it does not oscillate



Energy received is stored indefinitely
until its release via weak interaction

[Inductive Magnetic coupling]

The quantum Inductive circuit
is a SINGLE charge tri-field inductive energy loop

It does not oscillate energy between two opposing charges
its differing energy fields are the reuslt of its equilateral QAM geometry
storing Electric energy in its E field, and Magnetic energy in its M field

The direction of the QAM flux that models inertia is relative
to the observer

- ZPF

A negative ZPF can
be viewed as a quantum quoin
or an quantum 'ideal' inductor
with an internalised energy flux
that is the opposite of
a positive ZPF

Counter-Clockwise Current Flow



NEGATIVE

Quantum L circuit

[quantum inductive circuit]

Quantum Inductors and EM energy Levels


v
ε_0
ρ
v
v^2
$\frac{1}{c^2}$

coupled ODD# mass-energies
form SQUARE energy geometries

quantum Inductors

Scalar Energies


E
1
N
S
Coupled Inductance
E
2
E
3
4
Ǝ
N
S
Coupled Inductance
Coupled Inductance
E
E
E
5
6
7
8
9
Ǝ
Ǝ
1
3
5
1^2
2^2
3^2
Series Inductance
Series Inductance
Series Inductance

[ZPFs]

[Bosons]

[1]
Single Quantum Inductor

[1+2]
Coupled
Quantum Oscillator

[1+2]
A Coupled Inductance
in Parallel with
Two Series Inductors
[3+4]

E

[1+2] [3+5] [4+6]
Three coupled Inductances
in Parallel with
Three Series Inductors
[7+8+9]

All quantum levels form inductive magnetic dipole bases
[Weak Force]

Quantum energy levels
can be viewed as
various combinations
of:

Coupled Inductances


Prim
U_p
I_p
Sec
U_s
I_s

Parallel Inductances

$$L_{total} = \frac{1}{\frac{1}{L_1} + \frac{1}{L_2} + \ldots \frac{1}{L_n}}$$

Series Inductances

$$L_{total} = L_1 + L_2 + \ldots L_n$$

The Golden Triangle

Charged mass-energy geometries


v
n
π
1
2
3
4
5
6
7
8
ε_0
hv
v^2
1^2 2^2 3^2 4^2 5^2 6^2 7^2 8^2 9^2 10^2 11^2 12^2 13^2 14^2 15^2 16^2 17^2 18^2 19^2 20^2 21^2 22^2 23^2 24^2 25^2
1 3 5 7 9 11 13 15 17 19 21 23 25 27 29 31 33 35 37 39 41 43 45 47 49
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 24 23 22 21 20 19 18 17 16 15 14 13 12 11 10 9 8 7 6 5 4 3 2 1
Transverse Energies
Integral of Transverse Energies

Number of ZPFs per quantum level

ZPFs

All scalar mass-energies [integral quantum levels] have square number quanta in each radian spatial field

Photons

ODD NUMBER GEOMETRIES

SQUARE NUMBER GEOMETRIES

Bosons

EM waves

Probabilities **NORMAL DISTRIBUTIONS** Wavefunctions



Quantum Energy Levels

Within any spatial co-ordinate system the energy density of a region can increase or decrease geometrically creating the familiar squared quantum energy levels of quantum physics

Individual equilateral Planck quanta combine to form larger EM mass-energy geometries with the nett Charge being determined by the scalar arrangement of Positive and Negative quanta within the resulting Tetryonic geometry or topology

$E = n_{\text{ODD}}\pi[[m\Omega v]]$

$E = n_{\text{SQUARED}}\pi[[m\Omega v^2]]$

v
ε_0
h
hv
v²
c²
n1
n2
n3
n4
n5
n6
n7
n8
E
ρ
q
charge carriers
Bosons
1 3 5 7 9 11 13
1² 2² 3² 4² 5² 6² 7²
1 2 3 4 5 6 7 8
equilateral scalar energy field density

Tetryonics 03.13 - Quantum Energy levels

Magnetic Vectors

Intrinsic Magnetic vectors are transverse to E fields



Magnetic Permeability
Dipole field

External Magnetic fields are termed B fields

Opposite charges moving in opposing directions
produce co-directional Magnetic vectors



Magnetic vectors can be modelled geometrically or electrically through energy field fluxes
[quantised angular momenta]

Within a Magnetic dipole

Magnetic Vector A

energy 'flows' South to North

External to a Magnetic dipole
energy 'flows' North to South



Opposite charges moving in the same direction
produce Magnetic vectors in opposition

Charge Fields


1
[1-0]
E
ε0
Electro-Magnetic
Flux field
μ0
μ0
M

EM energy fluxes in a Positive ZPF flows
are electrically modelled as Clockwise
(from North to South)



The EM flux directions of Charges
can be modelled vectorially with
Electric and Magnetic vectors


1
[0-1]
E
ε0
Electro-Magnetic
Flux field
μ0
μ0
M

EM energy fluxes in a Negative ZPF
are electrically modelled as counter-Clockwise
(from North to South)


Q
[v-v]
E
ε0
m
μ0
μ0

All rotational planck energy fluxes can serve as models for the nett quantised angular momenta of any mass-energy geometry

Polarised
Electric and Magnetic fluxes
in ElectroMagnetic fields arise from
intrinsic quantised angular momentum


Q
[v-v]
E
ε0
m
μ0
μ0

Copyright ABRAHAM [2008] - all rights reserved

EM fields

are the combined Electric & Magnetic fields
resulting from the quantised angular momentum
of mass-energy in any region of free space



$$\varepsilon_0 \mu_0 = \frac{1}{c^2}$$

EM Permittivity-Permeability is a measure of how much resistance
is encountered when the quantised angular momenta of
EM energies form an electro-magnetic field in a vacuum

Celeritas = 299,792,458 $\frac{m}{s}$

$$c_0 = \frac{1}{\sqrt{\mu_0 \varepsilon_0}}.$$

EM field Permittivity-Permeability

$$\varepsilon_0 \mu_0 = 1.112650056e\text{-}17 \ \frac{s^2}{m^2}$$

$$\left[\frac{A^2\ s^4}{kg\ m^3} \cdot \frac{kg\ m}{A^2\ s^2}\right]$$



Equilateral triangles
are the inverse geometries
of circles

m		nπ	$[\varepsilon_0 \mu_0]$	$[m\Omega v^2]$
mass	=	charged	Spatial geometry	Energy density

Electric Constant

$$\varepsilon_0 = \frac{1}{\mu_0 c^2}$$

$$= 8.85418785\ e\text{-}12\ \frac{F}{m} \qquad \frac{A^2\ s^4}{kg\ m^3}$$

The permittivity of empty space, equal to 1 in centimeter-gram-second electrostatic units and numerically, to 8.854 × 10-12 farad per meter in International System units, where c is the speed of light in meters per second. Symbolized ε0.

Magnetic Constant

$$k_0 = \frac{1}{4\pi\varepsilon_0}$$

$$= 1.25663706\ e\text{-}6\ \frac{H}{m} \qquad \frac{kg\ m}{A^2\ s^2}$$

A measure of the degree to which molecules of some material polarize (align) under the influence of an electric field; symbol k0, units F/m (farads per metre).



$$\vec{\mathbf{S}} = \mathbf{E} \times \mathbf{H},$$

The Energy-momenta
of ZPFs form
natural Poynting vectors

Copyright ABRAHAM [2008] - all rights reserved

EM field Permittivity

The Electric constant, commonly called
the vacuum permittivity, or permittivity of free space,
relates the units for electric charge to
mechanical quantities such as
length and force.

The name Vacuum Permittivty is a misnomer and should be
replaced with the correct term EM field Permittivity

**The strength of Electric fields
is determined by the
Electrical Permittivity Constant**

$$E = \frac{1}{4\pi\varepsilon_0}\frac{Q}{r^2}$$



$\frac{F}{m}$

$\frac{A^2\,s^4}{kg\,m^3}$

8.85418785 e-12

$$\varepsilon_0 = \frac{1}{\mu_0 c^2}$$

ε_0
Ω
μ_0
μ_0

"Ampere's Law states that for any closed
loop path, the sum of the quantities (B.ds)
for all path elements into which the complete
loop has been divided is equal to the product
of µ0 and the total current enclosed by the
loop."

$$k = \frac{1}{4\pi\varepsilon_0}$$



Positive Charge Electric Field

The permittivity of empty space, equal to 1 in centimeter-gram-second
electrostatic units and to 107/4πc2 farads per meter or, numerically, to
8.854 × 10-12 farad per meter in International System units,
where c is the speed of light in meters per second.

Gauss' Law:

**"The total of the electric flux out of a closed surface
is equal to the charge enclosed divided by the permittivity"**

This applies equally to any geometry chosen to
tessellate a surface area

Superpostioned E fields
gives rise to Coulomb Forces



Negative Charge Electric Field

Electric permittivity Fields

Negative externalised Planck quanta
(Counter-clockwise energy fluxs)



Positive externalised Planck quanta
(Clockwise energy fluxs)



Coupled same charge ZPFs
have **neutralised** Magnetic fields

In Electro-statics superpositioned E fields
with interactive energy momenta
are the interactive mechanism
for Coulombic forces

Electrostatic Particles
in motion have Kinetic energies
resulting in Magnetic moments

Polar view

Negative
E-fields





Polar view



Positive
E-fields

NEGATIVE electrostatic E fields
attract positive charges and
repel negative charges

ε_0

POSITIVE electrostatic E fields
attract negative charges and
repel positive charges



Opposites Attract
Similars Repel



Vectorial momenta forces in EM fields are bi-directional
due to the energy-momenta quanta comprising them

The currently stated 'standard' premise of Electrical Energy flowing from Positive to Negative is misleading (as Energy also flows from Negative to Positive at the same time)

EM field Permeability

The permeability of free space,
also called absolute permeability.

The name Vacuum Permeability is a misnomer and should be replaced with the correct term EM field Permeability

The magnetic constant has the value of 4π × 10-7 henry per meter.

The strength of Magnetic fields is determined by the Magnetic Permeability Constant

F

The magnetic field is most commonly defined in terms of the Lorentz force it exerts on moving electric charges.

The magnetic field generated by a steady current (a constant flow of electric charges in which charge is neither accumulating nor depleting at any point) is described by the Biot–Savart law

μ_0

$B = \mu_0 H$



Magnetic Constant
1.25663706 e-6

A measure of the degree to which molecules of some material polarize (align) under the influence of an electric field.

Measured in units of units H/m (Henries per metre).

There are NO magnetic monopoles [not under any condition]



Positive Magnetic Moment



Negative Magnetic Moment

Magnetic permeability Fields



Coupled opposite charge ZPFs
produce **neutralised** Electric fields

In Magneto statics superpositioned M fields
with interactive energy momenta
are the interactive mechanism
for Lorentz forces

Magneto-static Particles
have enhanced Magnetic moments





Amperes law

Current flowing through a wire
will create a magnetic field



magnetic field forces are
orthagonal to electric Coulomb forces

Lorentz forces

charged particles in motion are subject
to forces due to external EM fields



Vectorial momenta forces in EM fields are bi-directional
due to the energy-momenta quanta comprising them

Opposites Attract
Similars Repel

NORTH M- fields
attract south M-fields and
repel north M-fields

μ_0

SOUTH M- fields
attract north M-fields and
repel south M-fields



Magentic fields can only exist in conjuction with Electric fields & Electric fields can only exist in conjunction with Magnetic fields





Electro-static fields

Similar charge electric dipole pairings
create 'neutralised' Magnetic dipoles

There are no such things as purely
Electric or Magnetic fields

v=0



Where Energy couples
with equal and opposite vectors

static KEM fields are created
otherwise know as EM fields

Fields of Force





All energy fields are Electro-Magnetic in nature
a direct product of their equilateral geometry

'Neutralised' electric dipole pairings
create Magnetic dipole fields

Magneto-static fields

Tetryonics 04.08 - Electro-Static & Magneto-static fields

Copyright ABRAHAM [2008] - all rights reserved

Charged EM field geometries

Opposite charge fields
can produce neutral E-fields
(with magnetic moments)



Electrostatic charged matter generate
charged energy fields around them

Moving charged particles generate
Kinetic energy & Magnetic moments



Charged electrostatic fields

accelerate charged particles
vectorally dependent on their quantum
charge mass-energy momenta field geometries



Positive charge electrostatic fields
attract Negative charges
repel Positive charges





Negative charge electrostatic fields
attract Positive charges
repel Negative charges

Copyright ABRAHAM [2008] - all rights reserved

E field acceleration of charged particles

Electric fields can accelerate charged particles within their field geometry
dependent on the particle's nett charged mass-Matter topology

Opposites ATTRACT

Similars REPEL



Positive E fields accelerate
Negative charges
towards their source

Particle acceleration
increases as it approaches
the E field source

Negative E fields accelerate
Negative charges
away from their source

Positive E fields accelerate
Positive charges
away from their source

Negative E fields accelerate
Positive charges
towards their source

Similars REPEL

Opposites ATTRACT

The charge quanta within Neutral particles are affected equally by Electric fields

Tetryonics 04.10 - E field acceleration of charged particles

ZPFs can combine to form
4 distinct static EM fields



Electro-static fields

ElectroMagnetic fields

Magneto-static fields



Similars REPEL
[QAM momenta vectors in opposition]

Opposites ATTRACT
[QAM momenta vectors in same direction]

'THE LAW OF INTERACTION'



Flux momenta in opposition

Electro-static fields
$1/r^2$



Flux momenta in the same direction

'FORCES OF INTERACTION'



Parallel

Flux momenta in the same direction

Magneto-static fields
$1/r^2$

Flux momenta in opposition



Anti-parallel

Positive electrostatic fields

divergent
positive
momenta

convergent
negative
momenta



$$\mathbf{E} = \frac{1}{4\pi\varepsilon_0}\frac{Q}{r^2}\hat{\mathbf{r}}$$

Coulomb's Force Law

$$E = \frac{F}{q} = \frac{kQ_{source}q}{qr^2} = \frac{kQ_{source}}{r^2}$$

Negative electrostatic fields

convergent
positive
momenta

divergent
negative
momenta



$$\nabla \cdot E = \frac{\rho}{\varepsilon_0} = 4\pi k\rho$$

Forces of Interaction

"The force of electrical attraction or repulsion between two point charges is directly proportional to the product of magnitude of each charge and inversely proportional to the square of distance between them"

attract Negative charged masses
repel Positive charged masses


ε_0
μ
ε^2
ε_0

attract Positive charged masses
repel Negative charged masses


Q
K
Q
K
Q
K
Q
Similars
Repel
Opposites
Attract
Similars
Repel

Electro-Magnetic field Lines

The magnetic field at any given point is specified by both its direction and magnitude

Magnetic dipoles can be produced by the coupling of opposite electric charge fields



or

by accelerating charged bodies of Matter which in turn produce associated Kinetic energies
[Neutral Electric field and equal strength Magnetic moment]

Magnetic South Poles have divergent south vectors and convergent north vectors



Magnetic North Poles have divergent north vectors and convergent south vectors

Interaction between vectorally opposed (convergent and divergent) vectors within Electric and Magnetic fields produces the familar lines of force and and interactions of Electro-Magnetic fields

3D Magnetic lines of Force are made up of 2D fields of Planck energy momenta

Every particle of Matter in motion possesses intrinsic Planck M-field dipoles becasue of their nett charged quanta which combine to produce a nuclear magneton.



The magnetic field lines of permanent bar magnets are the result of the equilateral charge [QAM] geometry of neutralised quanta that form their electrostatic fields

Magnetic field Forces

attractive magnetic forces

$$\frac{m^2\cdot kg}{s^2\cdot A^2} = \frac{J}{A^2} = \frac{Wb}{A} = \frac{s^2}{F} = \frac{V\cdot s}{A} = \frac{J/C\cdot s}{C/s} = \frac{J\cdot s^2}{C^2} = \frac{m^2\cdot kg}{C^2}$$

In physics superpositioned M fields with interactive energy momenta produce Lorentz forces

repulsive magnetic forces

Magnetic moments of same charges moving in the same direction




ε0
Ω
N
I
S
F
S
I
N
ε0

$4\pi\ e\text{-}7\ \frac{N}{A^2}$

$\frac{1}{\varepsilon_0 c^2} = \mu_0$

Magnetic moments of same charges moving in opposite directions



magnetostatic fields

ε0
magnetic dipole
Q
μ0
μ0
ε0

$$H = \frac{B}{\mu_0}$$

Coupled opposite charge EM fields produce Magnetic dipole fields

Joseph Henry

(17 December 1797 – 13 May 1878)

μ_B

Electrostatic charged particles in motion create magnetic moments

KE
magnetic moments
Q
KE

kinetic EM fields

Magnetic field lines

Magnetostatic Dipole

Magnetic field lines were introduced by
Michael Faraday (1791-1867) who named them
"lines of force"

Michael Faraday

(22 September 1791 – 25 August 1867)

*Magnetic South Poles have
divergent south vectors and
convergent north vectors*

External to the dipole
field lines run from
North to South



**Positive Electric fields have
divergent positive E vectors and
convergent negative E vectors**

**Negative Electric fields have
divergent negative E vectors and
convergent positive E vectors**

Internal to the dipole
field lines run from
South to North

Tetryonic geometry reveals
the true source of all
EM field lines of force

*Magnetic North Poles have
divergent north vectors and
convergent south vectors*

Permanent Magnets can be viewed as
neutral charge Electrostatic
EM fields

Similar to conventional vs electron current flows
Magnetic field vectors can be modelled with
two directions of 'magnetic flux'

Parallel Magnetic Dipoles

Michael Faraday

(22 September 1791 – 25 August 1867)

James Clerk Maxwell



(13 June 1831 – 5 November 1879)



Magnetic lines of force are continuous and will always form closed loops.

Magnetic lines of force will never cross one another.

Parallel magnetic lines of force traveling in the same direction repel one another.

Parallel magnetic lines of force traveling in opposite directions tend to unite with each other and form into single lines traveling in a direction determined by the magnetic poles creating the lines of force.

Magnetic lines of force tend to shorten themselves.

Therefore, the magnetic lines of force existing between two unlike poles cause the poles to be pulled together.

Magnetic lines of force pass through all materials, both magnetic and nonmagnetic.

Magnetic lines of force always enter or leave a magnetic material at right angles to the surface

Maxwell had studied and commented on the field of electricity and magnetism as early as 1855/6 when "On Faraday's lines of force" was read to the Cambridge Philosophical Society.

The paper presented a simplified model of Faraday's work, and how the two phenomena were related. He reduced all of the current knowledge into a linked set of differential equations with 20 equations in 20 variables. [Quarterions]

This work was later published as "On physical lines of force" in March 1861.

In his 1864 paper "A dynamical theory of the electromagnetic field", Maxwell wrote, "The agreement of the results seems to show that light and magnetism are affections of the same substance, and that light is an electromagnetic disturbance propagated through the field according to electromagnetic laws

Maxwell showed that the equations predict the existence of waves of oscillating electric and magnetic fields that travel through empty space at a speed of 310,740,000m/s.

His famous equations, in their modern form of four partial differential equations, first appeared in fully developed form in his textbook A Treatise on Electricity and Magnetism in 1873.

The specific features of Faraday's field concept, in its 'favourite' and most complete form, are that force is a substance, that it is the only substance and that all forces are interconvertible through various motions of the lines of force. These features of Faraday's 'favourite notion' were not carried on by Maxwell in his approach to the problem of finding a mathematical representation for the continuous transmission of electric and magnetic forces. Maxwell considered these electric and magnetic forces to be states of stress and strain in a mechanical aether, a notion further advanced by relativity theory with its 'stress energy' tensor math.

Tetryonics reveals lines of Force to be a direct result of the various superpositioned EM field geometries of equilateral mass-energy momenta

Anti-Parallel Magnetic Dipoles


E
ε_0
μ_0
μ_0
S
N
S
N
S
N
+
+
N
S
N
S
N
S
μ_0
μ_0
ε_0
E

Tetryonics 04.17 - Anti-Parallel Magnetic dipoles

Copyright ABRAHAM [2008] - all rights reserved

Magnetic Moments



Single ZPFs are
'ideal quantum inductor elements'

1

Electro-static Energies
Charges


E
ε
+
+
'Neutralised' dipole
N
S
E
ε
–
–
'Neutralised' dipole
N
S

All Matter in motion possesses kinetic energies
which are stored as Planck quanta in their KEM fields

The charge geometry of KEM fields are reflective
of the interactive component of the charged topology
of the particle in motion

Each charge geometry
has distinct Magnetic dipole
alignments


E
ε
KE
N
S
μZ
E
ε
KE
S
N
μZ

which in turn can only create
2 distinct orientations [spins] of
magnetic moments

2

Magneto-static Energies
Kinetic Energies


E
ε
N
S
'Re-inforced' dipole
N
S
ε
E

ZPF sets can form inductively coupled
quantum Harmonic Oscillators


1
4
9
16
n1
n2
n3
n4
n5
n6
n7
n8
25
36
49
64
v
ε0
n
μ0
μ0
hv
v²
c²

EM field strengths

All Energies are 'square' quanta scalar fields made up of quantised Electric & Magnetic fields

All EM fields have the same equilateral geometries [v^2]
Electric fields are inverse squared fields [1/r^2]
Magnetic dipoles are inverse cubed fields [1/r^3]

As the mass-energy quanta in EM fields change their geometries are subject to Lorentz contractions

Electrostatic particle modeling

m

EM mass-energy
Tetryonic field geometry

Tetryonic [4np] standing wave charge fields
form electrostatic Particle topologies
[Charged and Neutral Matter]

Matter
tetryonic Matter topology

M



Non-neutral
nett
Tetryonic quanta

12π geometries
12π topologies

Positive
Charge
Particles

Equal numbers
of opposite
Tetryonic quanta

12π EM field geometries

12π particle topologies

12π EM field geometries

12π particle topologies

Neutral
Charge
Particles

Non-neutral
nett
Tetryonic quanta

12π geometries
12π topologies

Negative
Charge
Particles

All particles in motion create secondary KEM field geometries
[Kinetic energies and Magnetic moments]

Electro-static Fields

Momenta
acting in oppose directions
results in zero velocity



Zero Velocity
equates to
Zero nett Momentum



Stationary Charges
have neutralised
magnetic dipoles



The Kinetic Electric
& Magnetic energies
are contained in an
KEM field extending
from a charged
particle in motion


v
CHARGE
ENERGY
Neutral E field
hv
v²
Magnetic moment

Charged particles
in motion produce a
Magnetic moment

Kinetic EM Fields





Moving Charges have
neutral KE fields and
Magnetic moments





Motion in any direction
produces
Kinetic & Magnetic energies


v
KE
S
N
hv
v²
Q
N
S
KE
v

The Strength of the
Kinetic Electric field & Magnetic moment
is directly proportional to
the square of the particle's Velocity

Electric & Kinetic Fields


v
[1-0]
ε0
Ω
N
S
c²

Positive charge field



$p = Mv$ $KE = \frac{1}{2}Mv^2$

$m = \frac{E}{v^2}$ $E = p^2$

The combined Kinetic & Magnetic moment energies total mv^2


v
[0-1]
ε0
Ω
S
N
c²

Negative charge field

Kinetic Energy field

KEM field created by a Positive charged body

KEM field created by a Negative charged body


KE
Q
N
S
KE
Q
S
N
+
ε0
KE
μ0
μ0
−


v
p
KE
N
S
hv
v²

Positive charges repelled
Negative charges attracted


v
p
KE
S
N
hv
v²

Negative charges repelled
Positive charges attracted

Neutralised Electric fields
Enhanced Magnetic moments

EM & KEM force vectors

All mass-energy quanta are ideal quantum Inductors

The E&M force vectors create orthogonal equilateral EM Fields

Electric fields propogate orthogonally to the Magnetic dipole field



Magnetic flux external to the Magnetic dipole flows from North to South

&

Internal to a Magnetic dipole it flows South to North

When ZFFs combine to form a Magnetostatic dipole they form orthogonal magnetic vectors

Positive charge can be modelled electrically with clockwise EM fluxes [omegas]

Negative charge can be modelled electrically with anti-clockwise EM fluxes [omegas]



Positive charge fields of interaction result from an excess of divergent positive energy momenta

Equal energy-momenta in opposition create static fields

Negative charge fields of interaction result from an excess of divergent negative energy momenta



The opposing E-field energy momenta creates the Coulombic Law of Interaction

When E field is at Maximum - B field is at Minimum
when B field is at Maximum - E field is at Minimum

The opposing M-field energy momenta creates the Lorentz Force

EM Forces and ZPFs

ZPF quanta can combine in differing combinations
to produce 3 distinct charged sets



Positive Charges

Magnetic dipole moment

Negative Charges

'Neutralised'
Magnetic dipole moment

Neutral Charges

'Neutralised'
Magnetic dipole moment

All EM mass-Energy-Matter & forces can be modelled using Tetryonic geometries



Positive charge particle KE field and magnetic moment

Zero Point Field EM geometry is the foundation for all the EM forces comprising, and acting between particles of Matter

Lorentz force, Lenz's Law, Right/Left Hand rules, etc can all be easily replaced with this simple geometric model



Negative charge particle KE field and magnetic moment

Kinetic EM fields

All Kinetic EM fields resulting from motion have charge field geometries
resulting from the charged Matter geometry of the particle in motion


Q
12
[12-0]
+
+
+
ε0
ε0
ε0


N
N
N
S
S
S
S
N
KE
KE
M


Q
12
[0-12]
ε0
ε0
ε0

Positive charge particle
topologies produce
positive KEM fields

**KEM field charge geometries
do not contribute to the nett charge**

Negative charge particle
topologies produce
negative KEM fields


+
−
−
+
μ0
μ0
ε0
ε0
ε0
Q

Negative KEM field geometries
viewed from different angles
are positive KEM fields

Positive KEM field geometries
viewed from different angles
are negative KEM fields


S
KE
N
Magnetic moment

***As a direct result of the KEM field being a EM field permeating free space
the symmetry of EM fields results in KEM field geometries being
viewed as having neutral KE fields with a magnetic moment***


S
KE
N
Magnetic moment

Point Particles and KEM fields




12
12n
ε_0
μ_0



Charged rest mass-Matter topology

Quarks T[8π]
Leptons T[12π]

velocity invariant rest mass-Matter has a standing wave topology

Baryons T[20π]

Charged Leptons at rest are Electric field standing waves
(with neutral Magnetic poles)
KE from motion generates a Magnetic Moment

Bosons nπ [ODD]

Kinetic EM field geometry is divergent from a particle's rest Matter topology

Photons nπ [EVEN]


v
KE
ε_0
μ_0


Charge
Q
[v-v]
[nπ]
rest mass-Matter
+
Kinetic Energies
μ_B
ε_0
μ_0
KE
v
[12π]
rest Matter topology
[1π]
Kinetic Energy geometry


ε_0
μ_0
KE
v

KEM fields of Matter in motion


Electron Flow
Conventional Current Flow
+
KE
N
S
N
KE
S
−

ZPFs geometries can be used
to model the KEM fields
of charged particles

2D charged EM field geometries create Matter topologies

tetryons	[4π]	tetryons	[4π]
quarks	[12π]	quarks	[8π]
leptons	[12π]	leptons	[12π]
Baryons	[36π]	Baryons	[20π]
Elements	[84π]	Elements	[54π]

*The mass-energy content of all charged fascia constituting
massive particles have momenta that is proportional
to the intrinsic velocity [c] of the standing wave*

Relativistic mass


rest Matter
Q
M

Electro-static particles
have neutralised
magnetic dipoles



Kinetic motion
produces
Magnetic moments

Spherical point charges do NOT exist


positron
Q
RE
M
KE
μB


12
[12-0]
e+
12n
+1
Q
-1
e-
12
[0-12]
12n

*3D Matter is a standing-wave topology resulting from radiant 2D EM geometries
All leptons and quarks both have 12 charged fasica geometries.
[but differing mass-Matter-particle topologies]*


electron
Q
RE
M
KE
μB

**All EM fields resulting from Kinetic Energy (motion) radiate outwards
(the intrinsic KEM fields contain both Negative and Positive Energy momenta quanta)**


Conventional Current Flow
Electron Flow
+
−

Magnetic field
around a
current carrying
conductor

Magnetic field
produced
by a
Solenoid


Electron Flow
S
N
Conventional Current Flow
+
−

Biot-Savart Law

is an equation in electromagnetism that describes the magnetic field B generated by an electric current.

μ_0 There is an inverse cube relationship between magnetic field strength and magnetic field force with respect to distance from the magnet. ε_0

The interaction between Magnetostatic fields for which a Magentic dipole exists obeys the inverse CUBED law of attraction and repulsion



The interaction between Electrostatic fields for which an Electric field exists obeys the inverse SQUARE law of attraction and repulsion

The Biot–Savart law is used to compute the magnetic field generated by a steady current, i.e. a continual flow of charges, through a wire, which is constant in time and in which charge is neither building up nor depleting at any point

$$\mathbf{B} = \int \frac{\mu_0}{4\pi} \frac{I d\mathbf{l} \times \mathbf{r}}{|r|^3},$$

The radial distance between Magnetic dipoles is less than the distance between Electric dipoles

$$\mathbf{B} = \int \frac{\mu_0}{4\pi} \frac{I d\mathbf{l} \times \hat{\mathbf{r}}}{|r|^2},$$



Close to one pole of a magnet, B field strength resembles the inverse square of Electric force. This is because it behaves as a "unipolar magnetic field"



Electric field drops off as the square of the distance from the source (for a monopole).

Magnetic field drops off as the cube of the distance from the source (for a dipole).

Copyright ABRAHAM [2008] - all rights reserved

Quantum Chirality

Its the equilateral geometry of quantised angular momenta that creates chirality in physics

Mirror imaged Planck quanta
are NOT
identical to each other



A reflection of Horizontal or Vertical axis results in a changed EM dipole orientation in turn signifying an opposite charge ZPF


Q
[v-v]
C
coulombs
mass.seconds
[v-v]
Q
charge
quantised angular momenta
Q
[v-v]
C
coulombs
mass.seconds

The equilateral geometry of any EM field or Matter particle is determined by its nett Coulombic charge


0°
60°
120°
180°
240°
300°
N
S
E
ε

Any nominal rotation about an axis results in a re-orientation of the electromagnetic vectors but does not affect any change to charge etc.

Irrespective of orientation or rotation:

Positive charge fields have clockwise inductive flux geometries

Negative charge fields have counter-clockwise inductive flux geometries

Pi radian - energy momenta geometries


1
[1-0]
E
ε₀
Ω
+
μ₀
N
S


1
[0-1]
E
ε₀
Ω
−
μ₀
S
N

mass-energy momenta

Q

nett charge

[v-v]


1
+
3
+
5
+
7
+
9
+
11
+
13
+
hv
1²
2²
3²
4²
5²
6²
7²
v²
π
Ω
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1
N

π

pi radian energy geometries

Ω

quantised angular momentum

Planck quanta

$n\pi[m\Omega v]^2$

energy mass velocity



π radian geometries are comprised of equilateral mass momenta Ω

Copyright ABRAHAM [2008] - all rights reserved

ZPFs and Bosons

ZPFs are Planck energy quantum elements



Bosons are transverse Quantum levels



Quantised angular momentum is the foundation for all Tetryonic mass-ENERGY-Matter geometries



Bosons are the exchange particles for the EM force



ZPFs are the quanta geometry for Charge, Bosons and Energy

Each Quantum level is an ODD number of quanta (Bosons)

Each 'squared' energy field is the sum of the preceeding Bosons


[square root]
v
Charge
Energy
n
ODD numbers
SQUARED numbers
2n-1
hv
[1-0] 1 + 1^2 [1-0] 1
[2-1] 3 + 2^2 [3-1] 4
[3-2] 5 + 3^2 [6-3] 9
[4-3] 7 + 4^2 [10-6] 16
[5-4] 9 + 5^2 [15-10] 25
[6-5] 11 + 6^2 [21-15] 36
[7-6] 13 + 7^2 [28-21] 49
v^2 [36-28] 64
(n-1) N (n-1)

The charged quanta in all mass-Energy geometries create a NORMAL Distributions


[v-v]
1
3
5
7
9
11
13
15
Q

$$\mathrm{ODD}\,\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

EM Field
Planck
quanta
Bosons
ElectroMagnetic
mass
velocity


[v-v]
1
3
5
7
9
11
13
15
Q

Bosons form the geometry of Quantum Levels



$$W^{+} = \underset{\text{ODD}}{n\pi}\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Force carrier for Positive charge particles

W⁺ Boson

EM field, Planck, quanta

$$\underset{\text{Bosons}}{\text{ODD}\,\pi}\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

ElectroMagnetic, mass, velocity

CHARGE carrier Bosons
are ODD number quanta

Bosons

form unit charge Quantum levels
that facilitate EM induction between
mass-Energy-Matter

Neutral Z Bosons and Photons
are EVEN quanta Bosons

EMField, Planck, quanta

$$\underset{\text{Photons}}{\text{EVEN}\,\pi}\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

ElectroMagnetic, mass, velocity

Neutral charge parallelogram geometry EM force carriers



Z⁰ Boson

Neutral Z Bosons can be formed by combining EVEN numbers of W Bosons

They are EVEN numbered alternate geometry Photons



Photons are alternate (diamond) EM geometries formed from Z Bosons

W⁻ Boson

Force carrier for Negative charge particles

$$W^{-} = \underset{\text{ODD}}{n\pi}\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$



Copyright ABRAHAM [2008] - all rights reserved

Bosons are charge carriers

[the geometric foundation of quantum levels]


v
[1-0]
E
Ω
+
N
S
1
W+
Positive charge carrier
1
[1-0]
–
+
+
3
hv
ODD
hv =1,3,5,7,9,11,13,15,17,19,21, ...
E = n.hv
Planck's Heat Law
c²
v
[0-1]
1
Negative charge carrier
W-
+
1
[0-1]
–
–
3

All Bosons have ODD quanta trapazoidal charged EM mass-energy geometries


λ/2
mΩv / c²μ₀
ε₀
π
ELECTRIC FIELDS
μ₀
MAGNETIC DIPOLE FIELDS
mΩv / c²ε₀
c

Tetryonics 05.03 - Boson EM field geometry

Boson Frequencies

All Bosons are 1/2 wavelength EM fields with ODD number quanta
They are the geometric basis for transverse EM field Quantum levels

EM Field Planck quanta

$\text{ODD}\,\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$

Bosons ElectroMagnetic mass velocity

W Bosons are comprised of
ODD number quanta

Bosons are TRANSVERSE Charge carriers

ODD #

Q

Planck quanta

$n\pi\left[[m\Omega v^2]\right]$

mass velocity


W Bosons
1
[8-7]
v = 15
c
½
ε₀
ɜ
f
f/2
15
f = 7.5
W+



Neutral Z BOSONS and PHOTONS
have differing EM geometries

EVEN #

Q

Planck quanta

$2n\pi\left[[m\Omega v^2]\right]$

mass velocity


Photons
c
Wavelength decreases as Frequency increases
16
λ
0
[8-8]
γ
f = 8



Photons are LONGITUDINAL
neutral EM force carriers
resulting from Bosons

ODD #

Q

Planck quanta

$n\pi\left[[m\Omega v^2]\right]$

mass velocity


f = 7.5
f
f/2
c
½
15
1
[7-8]
v = 15
W Bosons
W-

EM waves are comprised of
EVEN number quanta [Photons]

EM Field Planck quanta

$\text{EVEN}\,\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$

EM waves ElectroMagnetic mass velocity

Copyright ABRAHAM [2008] - all rights reserved

Boson Waveforms

All ODD Ω geometries [bosons] create a quantum of charge



W

The Electro-weak force is the result of Bosons interacting along their edge of Permeability



Boson exchange
is the basis of
Electro-Magnetic Induction
& Charge transfer

S



The Strong Colour Force is the result of Bosons interacting via their their Electric charge fascia

Positive charge carrier

W+



ODD number quanta

All charges are comprised of odd numbered Bosons

[each Boson is a Quantum level]

ODD number quanta

W–



Negative charge carrier


[v-v]
Ω
1
3
5
7
9
11
13
15
1 [1-0] Quantum level 1
1 [2-1] Quantum level 2
1 [3-2] Quantum level 3
1 [4-3] Quantum level 4
1 [5-4] Quantum level 5
1 [6-5] Quantum level 6
1 [7-5] Quantum level 7
1 [8-7] Quantum level 8
E
Q
+
N
S

Integral W Bosons form square Energy geometries

Separated energy geometries create an electromotive force


15
13
11
9
7
5
3
1
1 [7-8] Quantum level 8
1 [6-7] Quantum level 7
1 [5-6] Quantum level 6
1 [4-5] Quantum level 5
1 [3-4] Quantum level 4
1 [2-3] Quantum level 3
1 [1-2] Quantum level 2
1 [0-1] Quantum level 1
℧
–
E
N
S
[Λ-Λ]

Bosons



Positive Charges have nett
positive quantised angular momenta

Positive Bosons


1
3
5
7
9
11
13
15
1
2
3
5
6
7
8
Ω

EM Field Planck quanta

$$\text{ODD}\,\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Bosons

ElectroMagnetic mass velocity


1
3
5
7
9
11
13
15
1
2
3
5
6
7
8
Ω

Bosons are the geometry of Quantum Levels

Negative Bosons

Negative Charges have nett
negative quantised angular momenta



Bosons are TRANSVERSE EM fields [levels]

Each quantum Level is
a unit of Charge

nett Charge is a SCALAR EM field property

Charge


[v-v]
1
3
5
7
9
11
13
15
+1
+1
+1
+1
+1
+1
+1
+1
Q

Positive Charge field

Charge is a measure of the nett quantised angular momenta - energy geometry of any given region of Space-time


[v-v]
1
3
5
7
9
11
13
15
-1
-1
-1
-1
-1
-1
-1
-1
Q

Negative Charge field

bosons

photon



Electromagnetic induction results from the coupling of ODD quanta [charge boson] mass-energy momenta geometries

Photons are coupled dual charge mass-energy momenta geometries

The vector linear momentum of all bosons & photons determines their directions of propagation

ODD π

2nπ


Q
[v-v]
1
1
3
4
5
9
7
16
9
25
11
36
13
49
64
m
Ω
hv
v²
positive Charge field
c²

mass geometries

$$m \qquad \underset{\text{energy}}{\overset{\text{mass}}{n\pi}}\left[\underset{\text{impedance}}{\overset{\text{spatial field}}{[\varepsilon_0\mu_0]}}.\overset{\text{Planck} \quad \text{quanta}}{[\underset{\text{mass}}{m}\Omega \underset{\text{velocity}}{v^2}]}\right] \qquad E$$

mass-energy

the distribution of energy momenta in EM fields creates charged fascia


Q
[v-v]
1
1
3
4
5
9
7
16
9
25
11
36
13
49
64
m
Ω
hv
v²
negative Charge field
c²

charged planar mass-energy momenta form

radiant 2D equilateral geometries

ρ

mass-energy geometries

m

kg/m²

energy momenta per second

$$\frac{E}{c^2} = \underset{\text{mass}}{m} \qquad E \qquad \underset{\text{Matter}}{M} = \frac{E}{c^4}$$

ENERGY

energy momenta per second squared

ρ

mass-Matter topologies

M

KG/m³

charged mass-energy geometries form

standing-wave 3D tetrahedral topologies

Matter displacement topologies have internalised strong force fascia partitions


4
[4-0]
ε
M
4π
positive mass-Matter
c⁴

mass-Matter

$$m \qquad \underset{\text{Matter}}{4n\pi}\left[\underset{\text{impedance}}{\overset{\text{spatial field}}{[\varepsilon_0\mu_0]}}.\overset{\text{Planck} \quad \text{quanta}}{[\underset{\text{mass}}{m}\Omega \underset{\text{velocity}}{v^2}]}\right] \qquad M$$

Matter topologies


4
[0-4]
ε
M
4π
negative mass-Matter
c⁴

Tetryonics 05.08 - geometric mass-ENERGY-Matter topologies

Matter





EM mass-energies have
2D planar geometries

$E = mv^2$

2D EM mass-Energy
forms
3D Matter

EM Matter has a
3D Tetrahedral topology

$E = Mc^4$

3D Matter
is comprised of
2D EM mass-Energies



2D

ρ/sec

EM mass-energy per square metre

EM mass geometries

m

kg/m²

Matter is comprised of
4nπ mass-energy geometries
forming a 3D standing wave topology

3D

ρ/sec^2

EM mass-energy per cubic metre

Matter topologies

M

kg/m³

Tetryons EM Field Planck quanta

$$4n\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Matter quanta ElectroMagnetic mass velocity

Matter is anything that has a closed mass-energy topology and displaces a volume
(the 3D massive building blocks of quantum particles and atomic elements)

The EM mass-energy quanta of Matter can be measured transversely and longitudinally
allowing them to exhibit a number of wave-like and particle-like properties
(de Broglie wavelength & Compton frequency)





Tetryons - the quanta of Matter


v
ε_0
π
hv
v²
charged mass-energy
c²

'massless' is a physics mis-nomer as all energy exhibits mass equivalence

ZPF

mass-Energy quanta

m


v
ε_0
ρ
d
3
hv
v²
4π EM mass-energies
c²

$$m = n\pi\left[\left[\overset{spatial}{\underset{impedance}{1/c^2}}\right].\overset{Energy}{\underset{momenta}{\left[\overset{Planck}{\underset{mass}{m}}\,\Omega\,\overset{quanta}{\underset{velocity}{v^2}}\right]}}\right]$$

TETRYONS

Platonic tetrahedrons are the foundational topologies of all 3D Matter

$$T\pi\left[\left[\overset{spatial}{\underset{impedance}{1/c^4}}\right].\overset{Energy}{\underset{momenta}{\left[\overset{Planck}{\underset{mass}{m}}\,\Omega\,\overset{quanta}{\underset{velocity}{v^2}}\right]}}\right] = \underset{Matter}{M}$$


c
ε
π
3
hv
v²
radiant mass-energy wavefunction
c²

Tetryon

Matter Quantum

M

2D mass-energy geometries can be combined to form 3D mass-ENERGY-Matter particles


ε_0
d
ρ
d
ρ
Matter
c⁴

Standing wave mass-energy geometries and Matter topologies







As each charged fascia's E field tries to propagate outwards it interacts with a M field dipole at each apex

$$\underset{\text{Matter}}{M} = T\pi\left[\left[\overset{\text{spatial}}{\underset{\text{impedance}}{1/c^4}}\right].\overset{\text{Energy}}{\underset{\text{momenta}}{\left[\overset{\text{Planck}}{\underset{\text{mass}}{m}}\Omega\overset{\text{quanta}}{\underset{\text{velocity}}{v^2}}\right]}}\right]$$

In turn energised M fields supply energy to the E Fields creating a EM standing wave [the EM topology of Matter]







Matter stores EM mass-energies geometries in its 3D Tetrahedral topology

All mass-energy propagate at the speed of light creating linear energy momentum

Copyright ABRAHAM [2008] - all rights reserved

Tetryonic charge topologies


v
p
ε_0
μ_0
d
hv
v^2

Positive Tetryon

The 3D Tetryonic volume of Matter
is what distingushes it from
2D EM mass-energies

Negative Tetryon


v^2
hv
p
ε_0
μ_0
d
v

TETRYONS



[MATTER]



The four EM mass-energy momenta
produced by Tetryonic collapse
must not be confused with
the classical 4 Energy-momenta
(which refers to x,y,z co-ordinates & v)

v
ε_0
m

4pi radiant mass-energies

Four 2D mass-energy geometries
can combine to form via charge interactions
3D tetrahedral Matter topologies


v
p
ε_0
μ_0
d
hv
v^2

Neutral Tetryon

A 3D Tetryon can be 'collapsed' into a 2D waveform
radiant four energy momenta EM waveform
that conserves all of its 2D mass-energy-momenta

Neutral Tetryon


v^2
hv
p
ε_0
μ_0
d
v

Copyright ABRAHAM [2008] - all rights reserved

Tetryon Genesis

1. WEAK interaction
Mutual Inductive Coupling
[Magnetic dipoles interact]

ODDπ
charged mass-energies

Non-Zero
nett mass-Energy-momenta
result in Linear momentum

EVENπ
radiant mass-energies

2. *2D EM mass-energies*
interact to form
3D Matter topologies

EM wave momenta
can form standing waves
[Matter geometries]

3. STRONG interaction
Electrostatic Matter attract
via Electric charges and
Magnetic dipoles

4nπ
mass-Matter geometries


Electro-static field
[2 - 0]
[1 - 1]
Magneto-static field
WEAK force
[1 - 1]
Magneto-static field
Electro-static field
[0 - 2]
[4 - 0]
[2 - 2]
[2 - 2]
[0 - 4]
Q
Q
Q
Positive Tetryon
Neutral Tetryon
Neutral Tetryon
Negative Tetryon
STRONG force
STRONG force
STRONG force

Opposing momenta
result in static EM fields

All Tetryonic charges seek equilibrium

Copyright ABRAHAM [2008] - all rights reserved

Positive Tetryon


[4-0]
ε0
ε0
ε0
ε0
4




4
ε0
ε0
ε0
ε0
4

charged boson geometry

standing-wave Matter topology

radiant mass-energy geometries


4
ε0
ε0
ε0
ε0
[0-4]




4
ε0
ε0
ε0
ε0
4

Negative Tetryon

Copyright ABRAHAM [2008] - all rights reserved

Neutral Tetryons


[2-2]
ε0
ε0
ε0
ε0
4




0
ε0
ε0
ε0
ε0
4

charged boson geometry

standing-wave Matter topology

radiant mass-energy geometries


4
ε0
ε0
ε0
ε0
[2-2]




4
ε0
ε0
ε0
ε0
0

mass



$$\underset{\text{mass}}{m} = n\pi\left[\left[\underset{\text{impedance}}{\overset{\text{spatial}}{1/c^2}}\right].\underset{\text{momenta}}{\overset{\text{Energy}}{\left[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\underset{\text{velocity}}{\overset{\text{quanta}}{v^2}}\right]}}\right]$$

radiant mass-energy geometries



$$E = mc^2$$

Energy per second



energy

$$n\pi\left[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\underset{\text{velocity}}{\overset{\text{quanta}}{v^2}}\right]$$



Energy per second ^{2}

$$E = Mc^4$$



Matter



$$\underset{\text{Matter}}{M} = T\pi\left[\left[\underset{\text{impedance}}{\overset{\text{spatial}}{1/c^4}}\right].\underset{\text{momenta}}{\overset{\text{Energy}}{\left[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\underset{\text{velocity}}{\overset{\text{quanta}}{v^2}}\right]}}\right]$$

standing wave Matter topologies





Tetryons





mass-ENERGY-Matter

geometries topologies

mass
geometry
EM Field
ElectroMagnetic
Planck
quanta
mass
velocity

$n\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$



2D mass-energy geometries
are a property of
3D Matter topologies



Tetryonic Matter
is the building block
of all Fermions,
elements and
compounds

Matter
topology
EM Field
ElectroMagnetic
Planck
quanta
mass
velocity

$T\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$


12
144
1
1
2
4
3
9
4
16
5
25
6
36
7
49
8
64
9
81
10
100
11
121
hv
v²
1
1
1²
1
1²
3
2²
1
3
5
1²
2²
3²

ALL EM masss-energies
have equilateral geometry

Transverse
EM mass-energies
form bosons
[Quantum levels]

Longitudinal
EM mass-Energies
form Photons

Bosons combine
to form SQUARED
scalar EM energies

massless is a scientific
misnomer

2D [non-Topolgical]
EM mass-ENERGY is
'Matterless'

ALL Matter
has a 3D topology

Tetryonics 06.09 - Tetryonic mass-Energy-Matter

Tetryonic Matter

All quantum Matter has a foundational tetrahedral topology as a result of their equilateral mass-energy geometries [not spherical as has been assumed from the math]




Ex-sphere
Mid-sphere
In-sphere
r_I
r_M
r_E
$\frac{a}{\sqrt{24}}$
$\frac{a}{\sqrt{8}}$
$\frac{a}{\sqrt{6}}$

Sphere



Area sphere= $4\pi r^2$

Surface curvature = $1/r^2$

Total curvature = 4π


Tetryonic mass geometries
Surface Area
Spherical Point
Surface Area
Diameter
Altitude
Charged
fascia
edges
Canonical
Radius
M
Centroid
Centre of mass-Matter topology

Spheres & Tetrahedra are both 3D Platonic solids with 4π scalar integral Gaussian topologies and physical displacement volumes [Gauss-Bonnet theorem]



area = $\sqrt{3/4} * a^2$

ZPF fascia


$\sqrt{3/2} * a$
60
Altitude
Sin 60
Ω
60
60
Side/Base
Cos 60



Area Tetryon

$$A = 4\,A_0 = \sqrt{3}a^2$$

Vertex curvature = π

Total curvature = 4π

Dodecyons

while quarks & leptons are comprised of
12π mass-energy geometries
they have differing final Matter topologies

+1/3

up quark



positron



e +1

anti-strange quark

+2/3

top quark

charmed quark

8π

anti-τ neutrino

anti-μ neutrino

tau

12π

0

anti-down quark



anti-charmed quark

quarks

electron neutrino



neutrinos

anti-top quark



down quark



positron neutrino

strange quark

-1/3

bottom quark

anti-bottom quark

muon

muon neutrino

tau neutrino

-2/3



anti-up quark



e -1

electron

EM Field Planck quanta

$$12\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

ElectroMagnetic mass velocity

Quarks have octahedral topologies

Leptons have dodecahedral topologies

Copyright ABRAHAM [2008] - all rights reserved

anti-up quark


-2/3
quark octahedral topology
0
4
4
0-4
2-2
0-4
attractive dodecyon geometry

EM Field Planck quanta

$$12\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

dodecyon

ElectroMagnetic mass velocity

as mass-energy momenta is added to
Matter topologies & KEM fields of motion
different generations of particles are created

1. **anti-up** quark
2. **anti-charmed** quark
3. **anti-top** quark

u


nett charge
8
[2-10]
μ_0
ε_0
+
+
3
u
charged
mass-Matter
topology
8π

Quarks have 12 charged fascia - mass-energy geometries

2 Positive 10 Negative

Quarks have octahedral mass-Matter topologies

[-2/3 elementary charge]

down quark

-1/3

quark octahedral topology



attractive dodecyon geometry

EM Field Planck quanta

$$12\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

docdecyon ElectroMagnetic mass velocity

as mass-energy momenta is added to
Matter topologies & KEM fields of motion
different generations of particles are created

1. **down** quark
2. **strange** quark
3. **bottom** quark

d

nett charge

4

[4-8]



charged
mass-Matter
topology

8π

Quarks have 12 charged fascia - mass-energy geometries

4 Positive 8 Negative

Quarks have octahedral mass-Matter topologies

[-1/3 elementary charge]

anti-down quark

+1/3

quark octahedral topology



attractive dodecyon geometry

EM Field Planck quanta

$$12\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$$

dodecyon ElectroMagnetic mass velocity

as mass-energy momenta is added to
Matter topologies & KEM fields of motion
different generations of particles are created

1. **anti-down** quark
2. **anti-strange** quark
3. **anti-bottom** quark

d

nett charge

4

[8-4]



charged
mass-Matter
topology

8π

Quarks have 12 charged fascia - mass-energy geometries

8 Positive 4 Negative

Quarks have octahedral mass-Matter topologies

[+1/3 elementary charge]

up quark

+2/3

quark octahedral topology



attractive dodecyon geometry

EM Field   Planck quanta

$$12\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$$

dodecyon   ElectroMagnetic   mass   velocity

as mass-energy momenta is added to
Matter topologies & KEM fields of motion
different generations of particles are created

1. **up** quark
2. **charmed** quark
3. **top** quark

u

nett charge

8

[10-2]



charged
mass-Matter
topology

8π

Quarks have 12 charged fascia - mass-energy geometries

10 Positive   2 Negative

Quarks have octahedral mass-Matter topologies

[+2/3 elementary charge]

Copyright ABRAHAM [2008] - all rights reserved



Charged mass geometries & Matter topologies
are the physical basis for differentiating particles

hv

BOSONS

ZPFs are single quanta Bosons

PHOTONS

Photons are dual quanta Bosons

2D mass

[radiant energies]

All mass-energy-Matter geometries are comprised of Bosons containing quantised angular momenta

TETRAHEDRALS

Tetryons are the [4π] tetrahedral quanta of Matter

OCTAHEDRALS

DODECAHEDRALS

Quarks and Leptons are both 12π [dodecadeltahedral] mass geometries [differentiated by their final nett charged Matter topologies]

3D Matter Fermions

[standing-wave energies]

v
[1-0]
+1/12
1
ZPF
1
-1/12
v
[0-1]
1
[2-1]
n
W+ boson
n
1
[1-2]
W- boson
tetryon
4
[4-0]
+1/3
0
[2-2]
4
0
[2-2]
4
[0-4]
-1/3
tetryon
quark
8
[10-2]
+2/3
u
c
t
4
[8-4]
+1/3
d
s
b
anti-quark
8
quark
4
[4-8]
-1/3
d
s
b
8
[2-10]
-2/3
u
c
t
anti-quark
Lepton
12
[12-0]
1
e+
μ
τ
+1
2/3
νe
νμ
ντ
1/3
0
[6-6]
12
0
0
[6-6]
νe
νμ
ντ
0
neutrino
1/3
2/3
e-
μ
τ
-1
12
[0-12]
1
Lepton
Elementary Charges

Tetryonics 07.06 - Bosons & Fermions

divergent negative E-fields

electron

convergent negative E-fields


12
[0-12]
e-
12n
μ
ε_0


0
[6-6]
ν−
12
μ
ε_0

divergent negative E-fields

electron neutrino

convergent positive E-fields

Leptons have 12 charged mass-energy fascia geometries

Repulsive STRONG force creates Lepton topologies

12π

Tetryonic charged fascias creates the Matter topologies of all Leptons

Repulsive STRONG force creates Neutrino topologies

Leptons have dodecadeltahedral mass-Matter topologies

divergent positive E-fields

positron

convergent positive E-fields


12
[12-0]
e+
12n
μ
ε_0


0
[6-6]
ν+
12
μ
ε_0

divergent positive E-fields

positron neutrino

convergent negative E-fields

Copyright ABRAHAM [2008] - all rights reserved

Charged Leptons

EM Field Planck quanta

$$12\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$$

Dodecyon ElectroMagnetic mass velocity

e+

12


positron
net charge
12
[12-0]
+
+
+
+
+
ε_0
μ_0
charged mass-Matter topology
12π

1. **positron**
2. **anti-muon**
3. **anti-tau**

Leptons have 12 charged mass-energy fascia geometries

12 positive charge fascia or 12 Negative charge fascia

repulsive dodecyon geometries

lepton topologies

Charged Leptons have dodecadeltahedral mass-Matter topologies

[1 elementary charge]

e-

12


net charge
12
[0-12]
–
–
–
–
–
ε_0
μ_0
charged mass-Matter topology
12π
electron

1. **electron**
2. **muon**
3. **tau**

as mass-energy momenta is added to Matter topologies & KEM fields of motion different generations of particles are created repulsive charge dodecyon geometry



lepton mass-Matter topology

positron




12
[12-0]
+1
μ_0
ε_0
+
12n



EM Field Planck quanta

$$12\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Dodecyon ElectroMagnetic mass velocity

1. **positron**
2. **anti-muon**
3. **anti-tau**

Copyright ABRAHAM [2008] - all rights reserved

Neutral Leptons

EM Field Planck quanta

$12\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$

Dodecyon ElectroMagnetic mass velocity



ν-
0

nett charge
0
[6 6]

charged mass-Matter topology
12π

1. electron neutrino
2. muon neutrino
3. tau neutrino

Neutrinos have 12 charged mass-energy fascia geometries

6 Positive & 6 Negative

repulsive dodecyon geometries

lepton topologies

Neutrinos have neutral dodecadeltahedral mass-Matter topologies

[0 elementary charge]



ν+
0

nett charge
0
[6-6]

charged mass-Matter topology
12π

1. positron neutrino
2. anti- muon neutrino
3. anti-tau neutrino

as mass-energy momenta is added to
Matter topologies & KEM fields of motion
different generations of particles are created

electron



repulsive charge dodecyon geometry

lepton mass-Matter topology







EM Field Planck quanta

$12\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$

Dodecyon ElectroMagnetic mass velocity

1. electron
2. muon
3. tau

Leptronic Quantum levels

[KEM field mass-energy geometry]


v
CHARGE
ENERGY
n
hν
v^2
c

v^2 Total quanta		n Electron quantum level
1.2e20	1e19	1
4.8e20		4
1.08e21		9
1.92e21		16
3.00e21		25
4.32e21		36
5.88e21		49
7.68e21		64






1
3
5
n3
1^2
2^2
3^2


1
3
5
7
n4
1^2
2^2
3^2
4^2


Quantum Levels
n8
n7
n6
n5
n4
n3
n2
n1
Q
[ν-ν]
RE
M+KE
μ0
ε0
v
Compton Frequencies
Photon Frequencies
36
60
84
108
132
156
180
108
M
KE
Energy level differential per Electron level
769+
Free Electron

Leptronic KEM field mass-energies

$$p^2 = KEM = Mv^2$$









Illustrative schema only: All Leptonic quantum levels have the same equilateral KEM geometry as the compton frequency of the KEM field increases the wavelengths of the quanta decrease

$P^2 = KEM = Mv^2$

Electron energy levels

As the total Energy content of particles increase
the Quantum levels of their KEM fields increase as well,
in turn this is reflected in their associated
Compton Frequencies and deBroglie wavelengths


n1
12
[0-12]
12n+
v
12n
KE
n2
12
[0-12]
12n+
v
12n
KE
n3
12
[0-12]
12n+
v
12n
KE
n4
12
[0-12]
12n+
v
12n
KE


Charge
12
[0-12]
Quantum Levels
n8
n7
n6
n5
n4
n3
n2
n1
Relativistic mass-Energies
Velocity
Photon Frequencies
Compton Frequencies
M
1.2e20
rest Matter
KE
Kinetic Energies

All Tetryonic geometries [EM fields & Matter]
absorb and release energy exponentially
in equilateral Quantum steps


12
[0-12]
12n+
v
12n
KE
n5
12
[0-12]
12n+
v
12n
KE
n6
12
[0-12]
12n+
v
12n
KE
n7
12
[0-12]
12n+
v
12n
KE
n8

The ratio of the area of a sphere

$$A = 4\pi r^2 = \pi d^2.$$

to

the area of a 3 Tetryhedron Lepton shape

$$A = 4\,A_0 = \sqrt{3}a^2$$

is

2.418399152



The spherical model of an electron's topology is wrong

Tetryonics 08.07 - Electron energy levels

Copyright ABRAHAM [2008] - all rights reserved

Leptronic Kinetic EM Fields


1
12.5%
12
[0-12]
n1
12n
12
2
25%
12
[0-12]
n2
12n
24
3
37.5%
12
[0-12]
n3
12n
48
4
50%
12
[0-12]
n4
12n
192
v
Electric Field
Any moving charge can be modelled with its associated ZPF geometry
All Leptons have 12 quantum inductive loop rotating topologies
KE
hv
S
N
M
v²
Magnetic Moment
Invariant rest Matter
EM fields are c² spatial geometries
Charge
12
[0-12]
Quantum Levels
Relativistic mass-Energies
n8
n7
n6
n5
n4
n3
n2
n1
μ₀
ε₀
Velocity
Compton Frequencies
Photon Frequencies
M
1.2e20
rest Matter
KE
Kinetic Energies
Leptronic KEM field energy
5
62.5%
12
[0-12]
n5
12n
300
6
75%
12
[0-12]
n6
12n
432
7
87.5%
12
[0-12]
n7
12n
588
8
100%
12
[0-12]
n8
12n
768

$$P^2 = KEM = Mv^2$$

The motion of an Electron's Matter topology through any external EM fields creates a proportional KE field and Magnetic Moment as a direct result of the 'quantum inductive loops' formed by the Leptronic EM field geometries

Tetryonics 08.08 - Leptronic KEM fields

Kinetic field modelling

RE

Mv^2

2D

Kinetic Energy field

$E = mc^2$

3D

rest mass-Matter topology

Tetryonic
Positive Charge
KEM field geometry



Positron



Similar charges moving
in the same direction
produce attractive
magnetic dipoles

Opposite charges moving
in the same direction
produce repulsive
magnetic dipoles

F_A

Opposite charges moving
in different directions
produce attractive
magnetic dipoles

Similar charges moving
in opposing directions
produce repulsive
magnetic dipoles

Tetryonic
Negative Charge
KEM field geometry



Electron

RE

Mv^2

2D

Kinetic Energy field

$E = mc^2$

3D

rest mass-Matter topology

The KEM fields of all
Matter particles in motion
can be modelled using
ZPF EM geometries

Kinetic EM field geometry determines the Magnetic Moments of all particles in motion

The KEM E-field is reflective
of the nett particle charge
and forms a directional
vector of motion

Lepton Families & Generations

v
KE
M
hv
v²
rest Matter is invariant
c

Charged Matter topologies in motion creates Kinetic EM field geometries

Charged mass-energy geometries form elementary particle topologies

12π

$$KEM = Mv^2$$

Total relativistic mass-energies
[rest Matter + KEM]

All high mass-energy particles 'decay' into low mass-energy particles by emitting photons


anti-Lepton
Neutrino
Lepton
e
12
[12-0]
RE
12
KE
0
[6-6]
RE
12
KE
νe
νe
12
[0-12]
RE
12
KE
e
μ
νμ
νμ
μ
τ
ντ
ντ
τ
increasing
increasing
KE
KE


Generation 1
Electron
Generation 2
Muon
Generation 3
Tau

Note: All Lepton geometries are the same size - only the energy density of the EM field changes

Copyright ABRAHAM [2008] - all rights reserved

Lepton Helicity and Chirality

Particle Spin and Handedness is always referenced
with respect to the direction of nett total system linear Momentum

Particle Spin


12
[0-12]
Spin
UP
Spin
DOWN
Spin
DOWN
Spin
UP
12
[12-0]

Particle Chirality


Parallel spin
Creates higher energy
magnetic moment
Anti-Parallel spin
Creates lower energy
magnetic moment
L
L
µ UP
µ DOWN
L
R
system momentum direction
system momentum direction
µ DOWN
µ UP
L
L
Anti-Parallel spin
Creates lower energy
magnetic moment
Parallel spin
Creates higher energy
magnetic moment
N
Nuclear Magneton dipole
S
All Lepton SPINs are relative to the Nuclear Magneton

Particle Chirality


PARTICLE
L
12
[0-12]
0
[6-6]
12
[12-0]
0
[6-6]
R
ANTI-PARTICLE

Particles and Anti-particles are mirror images of each other

Particle Helicity


12
[0-12]
q < 0
q-
Left handed particles
$F_{mag} = q(\mathbf{v} \times \mathbf{B})$
q
v
B
q0
12
[12-0]
q > 0
q+
Right handed particles

Lorentz Force and Transformation


Left handed
PARTICLE
UP
spin
DOWN
spin
System direction of Momentum
DOWN
spin
UP
spin
Right handed
ANTI-PARTICLE

Moving charges create Magnetic Moments

The Kinetic EM field of moving charges is subject to Lorentz transformations

Charged particles moving in external E fields are subject to Lorentz Forces

$$\sqrt{1-\beta^2}$$

‘Point Charges’

The only true ‘point charges’ are Zero Point Fields



Positive Particles


v
KE
N
S
M
v²
KEM
12
[12-0]
e⁺
1.2e20

Relativistic mass-energy Model

Kinetic Energies

velocity related mass-energy geometry

Magnetic moment

Invariant rest Matter topology


+
ε_0
Ω
μ_0
μ_0
−

Static charge particles have neutral M Fields
Charges in motion have magnetic moments


12
[0-12]
μ_0
ε_0
μ_0
ε_0
μ_B
ε_0
v
RE
KEM
M
[Mv²]

Relativistic mass-Energy Model

It is the Kinetic EM field geometry of charged Matter topologies in motion that produces Magnetic Moments

[not a relativistic distortion of speherical charge topologies]



Negative Particles


v
KE
S
N
M
v²
KEM
12
[0-12]
e⁻
1.2e20

Relativistic mass-energy Model

Kinetic Energies

velocity related mass-energy geometry

Magnetic moment

Invariant rest Matter topology

Copyright ABRAHAM [2008] - all rights reserved


8π octahedral particle family
8π quark topology
8π anti-quark topology
12π lepton topology
12π neutrino topology
12π dodecahedral particle family
Generation 1
up - down
up
8 [10-2]
4 [4-8]
down
up
8 [2-10]
4 [8-4]
down
12 [0-12]
e
ve
0 [6-6]
12 [12-0]
e
ve
0 [6-6]
Generation 1
electron
Generation 2
charmed - strange
charmed
8 [10-2]
4 [4-8]
strange
charmed
8 [2-10]
4 [8-4]
strange
Kinetic Energy content
Kinetic Energy content
12 [0-12]
μ
νμ
0 [6-6]
12 [12-0]
μ
νμ
0 [6-6]
Generation 2
muon
Generation 3
top - bottom
top
8 [10-2]
4 [4-8]
bottom
top
8 [2-10]
4 [8-4]
bottom
12 [0-12]
τ
ντ
0 [6-6]
12 [12-0]
τ
ντ
0 [6-6]
Generation 3
tau

Charge topologies determines particle families - Kinetic Energies determine particle generations

Tetryonics 08.13 - Quark & Lepton families

Copyright ABRAHAM [2008] - all rights reserved

Mesons

are 24π subatomic mass-Matter particles composed of one quark and one antiquark

$$24\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

EM Field · Planck · quanta · Mesons · ElectroMagnetic · mass · velocity


12
++
8π
12
8π
12
++
8π
12
8π
12
++
8π
12
8π

+16 [20-4]

+12 [18-6]

+8 [16-8]

prevented by strong repulsive forces

24π charged mass-energy fascia geometries

Pions


14π
14π
14π
14π

π+	24	+4	[14-10]
πo	24	0	[12-12]
πo	24	0	[12-12]
π-	24	-4	[10-14]

Short lived combinations

14π final mass-Matter topologies


12
--
8π
12
8π
12
--
8π
12
8π
12
--
8π
12
8π

-8 [8-16]

-12 [6-18]

-16 [4-20]

prevented by strong repulsive forces

PION decay

24π dual -quark mass-energy geometries

12π lepton mass-energy geometries


π+
8
[10-2]
4
[8-4]
24π
12
[18-6]
e+
12
[12-0]
12π
0
[6-6]
νe
12π
π0
8
[0-2]
8
[2-10]
24π
0
[24-24]
π0
4
[4-8]
4
[8-4]
24π
e+
12
[12-0]
12π
[2x]
0
[6-6]
νe
12π
[[2x]]
[[4x]]
e-
12
[0-12]
12π
[2x]
0
[6-6]
νe
12π
π-
4
[4-8]
8
[2-10]
24π
12
[6-18]
e-
12
[0-12]
12π
0
[6-6]
νe
12π

24π neutral Pions can decay into a number of different 12π lepton particles

2 [neutrino]+electron+positron
2 [electron+positron]
4 [neutrino]

EM Field Planck quanta

$$24\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Mesons ElectroMagnetic mass velocity

24π dual dodecyon geometries

Despite having 24π geometries Mesons have same nett Charges as 36π Baryons

36π tri-dodecyon geometries

$$12\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right] + 12\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Lepton - Neutrino generational pairing produced is dependent on the mass-energy levels of the interacting Pions

Copyright ABRAHAM [2008] - all rights reserved



$$24\pi + 12\pi = 36\pi$$

mesons *charged mass-energy geometries* **Baryons**

Short-lived Particles

All particles seek charge equilibrium

Stable Particles

+16 [20-4]
++
+12 [18-6]
++
+8 [16-8]
++
+4 [14-10]
π+
0 [12-12]
πo
0 [12-12]
πo
-4 [10-14]
π-
Pions
-8 [8-16]
--
-12 [6-18]
--
-16 [4-20]
--
8 [10-2]
4 [8-4]
quarks
4 [4-8]
8 [2-10]
P+
12 [24-12]
Proton
Neutron
N°
0 [18-18]
N°
0 [18-18]
anti - Neutron
anti-Proton
P−
12 [12-24]

Nuclear strong force fascia bonds
create Baryonic Matter topologies

All Matter topologies have internalised mass-energy fascia

mesons *mass-Matter topologies* **Baryons**

$$14\pi + 8\pi = 20\pi$$

Copyright ABRAHAM [2008] - all rights reserved

Baryons

Baryons are 36π mass-energy geometries

EM Field Planck quanta

$$36\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$$

Baryons ElectroMagnetic mass velocity

Double Charmed Xi

Charmed Sigma

Lambda

P⁺



12
[24-12]

Proton

Double Bottom Xi

-1





Bottom Xi

Charmed Bottom Omega

Bottom Omega

-2

Bottom Lambda

Neutron

N⁰



0
[18-18]

+1



Bottom Sigma

Charmed Omega



+2

Charmed Bottom Omega Prime

0
[18-18]



N̄⁰

Anti - Neutron

0

Charmed Xi Prime

Charmed Lambda

Double Charmed Omega

Xi



Anti-Proton

Bottom Xi Prime

12
[12-24]



P⁻



Sigma

Double Bottom Omega

that result in 20π mass-Matter topologies

Copyright ABRAHAM [2008] - all rights reserved

Proton


nett charge
12
[24-12]
p+
d
u
u
charged mass-energy geometries
36π

Tri-quark mass-energy geometry

EM Field Planck quanta

$$36\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Baryons ElectroMagnetic mass velocity

Baryon mass-Matter topology




12
[24-12]
+
+
+
+
+
+
20π
charged mass-Matter topology

Proton



Copyright ABRAHAM [2008] - all rights reserved

Neutron


nett charge
0
[18-18]
N°
d
d
u
charged mass-energy geometries
36π

Tri-quark mass-energy geometry

EM Field Planck quanta

$$36\pi\left[\left[\varepsilon_0 \mu_0\right].\left[m \Omega v^2\right]\right]$$

Baryons ElectroMagnetic mass velocity

Baryon mass-Matter topology


up
down
down


0
[18-18]
Neutron
20π
charged mass-Matter topology


up
down
down

anti-Neutron


net charge
0
[18-18]
N⁰
d
d
u
charged mass-energy geometries
36π

Tri-quark mass-energy geometry

EM Field Planck quanta

$$36\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Baryons ElectroMagnetic mass velocity

Baryon mass-Matter topology


anti-up
anti-down
anti-down


0
[18-18]
anti-Neutron
20π
charged mass-Matter topology


anti-up
anti-down
anti-down

anti-Proton


nett charge
12
[12-24]
P⁻
d
u
u
charged mass-energy geometries
36π

Tri-quark mass-energy geometry

EM Field Planck quanta

$$36\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Baryons ElectroMagnetic mass velocity

Baryon mass-Matter topology


anti-down
anti-up
anti-up


12
[12-24]
charged mass-Matter topology
20π

anti-Proton


anti-down
anti-up
anti-up

Copyright ABRAHAM [2008] - all rights reserved

Baryon geometry

Proton

12
Tetryonic Charge
[24-12]



[36] Linear - Tri-quark geometries - prior to Strong force interaction

+1
elementary charge
Proton

Protons are
GEOMETRIC MIRROR IMAGES
of Neutrons

0
elementary charge
Neutron

[18-18]
Tetryonic Charge
0

Neutron

Copyright ABRAHAM [2008] - all rights reserved


Chared particle families
[charged mass geometries & Matter topologies]
EM Fields
1π
1
[1-0]
ε₀
μ₀
1
[0-1]
Tetryons
4π mass geometries
4π Matter topologies
4π
4
[4-0]
0
[2-2]
4
[0-4]
4π
Quarks
12π mass geometries
8π Matter topologies
12π
Leptons
12π mass geometries
12π Matter topologies
8 [10-2] up
up 8 [2-10]
4 [4-8] down
down 4 [8-4]
8 [10-2] charmed
charmed 8 [2-10]
4 [4-8] strange
strange 4 [8-4]
8 [10-2] top
top 8 [2-10]
4 [4-8] bottom
bottom 4 [8-4]
8π
12 [12-0] e+
12 [0-12] e-
νe 0 [6-6]
νe 0 [6-6]
12 [12-0] μ
12 [0-12] μ
νμ 0 [6-6]
νμ 0 [6-6]
12 [12-0] τ
12 [0-12] τ
ντ 0 [6-6]
ντ 0 [6-6]
12π
Mesons
24π mass geometries
14π Matter topologies
24π
14π
4 [14-10] π+
0 [12-12] π0
0 [12-12] π0
4 [10-14] π-
Baryons
36π mass geometries
20π Matter topologies
12 [24-12] P+
Proton
Neutron
N°
36π
0 [18-18]
N̄°
anti - Neutron
anti-Proton
12 [12-24] P⁻
20π

Tetryonics 10.07 - Tetryonic Charged particle families

Copyright ABRAHAM [2008] - all rights reserved

Tetryonic Energy levels

$$\underset{\text{momentum}}{\overset{\text{Energy}}{E = n\pi\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]}}$$

Energy levels

𝔪

1e19 $hv = n$


v
1
p
3
4
5
6
7
8
1^2
2^2
3^2
4^2
5^2
6^2
7^2
1
3
5
7
9
11
13
hv
v^2
1
2
3
4
5
6
7
8

charged field quantisation

Every charged fascia of a Field or Particle holds squared energy levels
[equilateral EM mass-energy geometries & Matter topologies]

The Tetryonic KEM Colour code

As the energy levels of atomic nuclei increase/decrease
the KEM fields of leptons bound to them change accordingly


12
[0-12]
e-
RE
12n
KE

Electron

1	2	3	4	5	6	7	8
▲	▲	▲	▲	▲	▲	▲	▲
1	4	9	16	25	36	49	64

All energy levels are Tetryonic square number quantas
ie 1, 4 , 9, 16, 25 etc (1,2,3,4,5)

rest mass-Matter


0
[18-18]
N^0
22,500n
RE
KE


1875
rest Matter
differential
12
[0-12]
12n
RE
KE
e-


12
[24-2]
P^+
22,500n
RE
KE

The total mass-energy for any particle is its rest mass-Matter + Kinetic Energies

The mass-energies of its charge geometry determines its rest mass-Matter

An electron's nuclear kinetic energy level is determined by the Baryons it binds to (or by incident photons)


N^0
e^-
P^+
45,012n

Nuclei



Nuclear Quantum Level	electron Kinetic Energy Level
8	768
7	588
6	432
5	300
4	192
3	108
2	48
1	12

As the Nuclei quanutm level increases - so does the electron's energy and tmomenta

$$\underset{\text{Kinetic energies}}{KEM} = 4\pi\left[\underset{\text{ElectroMagnetic}}{\overset{\text{EM Field}}{[\varepsilon_0\mu_0]}}.\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]$$

tri-quark charged toplogy combinations



Quarks seek charge equilibrium by
forming Baryonic Matter topologies
as a result of charge interactions
[STRONG nuclear Force]

UP **DOWN**	gen 1
CHARMED **STRANGE**	gen 2
TOP **BOTTOM**	gen 3

[+8 +8 +8] [10-2] [10-2] [10-2]	24	+	2	2/3 2/3 2/3
[+8 -4 +8] [10-2] [4-8] [10-2]	12	+	1	2/3 1/3 2/3

The particle Zoo is the result of tri-quark mass-energy topologies

[-4 +8 -4] [4-8] [10-2] [4-8]	0	0	0	1/3 2/3 1/3
[-4 -4 -4] [4-8] [4-8] [4-8]	12	-	1	1/3 1/3 1/3

Twice the number of combinations are possible with the inclusion of anti-matter topologies

EM Field
Planck quanta

$$36\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Baryons
ElectroMagnetic
mass
velocity

Any combinations of inter-generational quarks
results in differing final mass-energies
in the created Baryonic Matter
due to energy equalisation

The Particle Zoo



uuu	udu	ucu	usu	utu	ubu	suu	sdu	scu	ssu	stu	sbu
uud	udd	ucd	usd	utd	ubd	sud	sdd	scd	ssd	std	sbd
uuc	udc	ucc	usc	utc	ubc	suc	sdc	scc	ssc	stc	sbc
uus	uds	ucs	uss	uts	ubs	sus	sds	scs	sss	sts	sbs
uut	udt	uct	ust	utt	ubt	sut	sdt	sct	sst	stt	sbt
uub	udb	ucb	usb	utb	ubb	sub	sdb	scb	ssb	stb	sbb
duu	ddu	dcu	dsu	dtu	dbu	tuu	tdu	tcu	tsu	ttu	tbu
dud	ddd	dcd	dsd	dtd	dbd	tud	tdd	tcd	tsd	ttd	tbd
duc	ddc	dcc	dsc	dtc	dbc	tuc	tdc	tcc	tsc	ttc	tbc
dus	dds	dcs	dss	dts	dbs	tus	tds	tcs	tss	tts	tbs
dut	ddt	dct	dst	dtt	dbt	tut	tdt	tct	tst	ttt	tbt
dub	ddb	dcb	dsb	dtb	dbb	tub	tdb	tcb	tsb	ttb	tbb
cuu	cdu	ccu	csu	ctu	cbu	buu	bdu	bcu	bsu	btu	bbu
cud	cdd	ccd	csd	ctd	cbd	bud	bdd	bcd	bsd	btd	bbd
cuc	cdc	ccc	csc	ctc	cbc	buc	bdc	bcc	bsc	btc	bbc
cus	uds	ucs	uss	uts	ubs	bus	bds	bcs	bss	bts	bbs
cut	cdt	cct	cst	ctt	cbt	but	bdt	bct	bst	btt	bbt
cub	cdb	ccb	csb	ctb	cbb	bub	bdb	bcb	bsb	btb	bbb

216 possible Baryon topologies [excluding anti-matter] with each combination producing differing Baryonic nett energy levels

Quarks always form symmetrical [udu] or [dud] charged Baryonic topologies
[same charges never combine except under high energy conditions]
ie. Proton is a [udu] not [uud] as is commonly stated


Baryons
12 [24-12]
udu
Proton
0 [18-18]
dud
Neutron
12 [24-12]
ssd
Charmed Lambda
0 [18-18]
sud
Lambda
0 [18-18]
bud
Bottom Lambda
12 [24-12]
usu
Sigma+
0 [18-18]
dus
Sigma0
12 [12-24]
dsd
Sigma-
Unstable High energy particle (extremely short lived)

Tetryonics 10.10 - Proton to Sigma-


Baryons
24
[30·06]
ucu
Charmed Sigma
12
[24·12]
udc
Charmed Sigma
0
[18·18]
dcd
Charmed Sigma
12
[24·12]
ubu
Bottom Sigma
0
[18·18]
dub
Bottom Sigma
12
[12·24]
dbd
Bottom Sigma
Unstable High energy particle (extremely short lived)
Unstable High energy particle (extremely short lived)
2-2
4-0
0-4

Tetryonics 10.11 - Charmed to Bottom Sigma

Baryons

0
[18-18]



Xi


2-2
2-2
2-2
2-2
2-2
s
s
0-4
4-0
4-0
0-4

12
[12-24]



Xi


2-2
2-2
0-4
2-2
2-2
s
p
s
0-4
2-2
2-2
0-4

Unstable High energy particle (extremely short lived)

Charmed Xi Prime

12
[24-12]




2-2
2-2
2-2
2-2
s
4-0
4-0
0-4
4-0
4-0

Charmed Xi Prime

0
[18-18]




2-2
2-2
2-2
2-2
2-2
s
d
0-4
4-0
4-0
0-4

Double Charmed Xi

24
[30-06]



Unstable High energy particle (extremely short lived)


2-2
4-0
4-0
2-2
4-0
4-0
2-2
4-0
4-0

Double Charmed Xi

12
[24-12]




2-2
2-2
2-2
2-2
d
0-4
4-0
0-4
4-0
0-4

Copyright ABRAHAM [2008] - all rights reserved

Copyright ABRAHAM [2008] - all rights reserved

Baryons



Bottom Xi
(Cascade B)


2-2
2-2
2-2
2-2
2-2
0-4
4-0
4-0
0-4



Bottom Xi
(Cascade B)


2-2
2-2
0-4
2-2
2-2
0-4
2-2
2-2
0-4

Unstable High energy particle (extremely short lived)



Double
Bottom Xi


2-2
2-2
2-2
2-2
2-2
0-4
4-0
4-0
0-4



Double
Bottom Xi


2-2
2-2
0-4
2-2
2-2
0-4
2-2
2-2
0-4

Unstable High energy particle (extremely short lived)



Charmed
Bottom Xi


2-2
2-2
2-2
2-2
4-0
4-0
0-4
4-0
4-0



Charmed
Bottom Xi


2-2
2-2
2-2
2-2
2-2
0-4
4-0
4-0
0-4

Copyright ABRAHAM [2008] - all rights reserved

Baryons

0
[18-18]



Charmed
Omega


2-2
2-2
2-2
2-2
2-2
0-4
4-0
4-0
0-4

12
[12-24]



Bottom
Omega


2-2
2-2
0-4
2-2
2-2
0-4
2-2
2-2
0-4

Unstable Highenergy particle (extremely short lived)

12
[24-12]



Double
Charmed
Omega


2-2
2-2
2-2
2-2
4-0
4-0
0-4
4-0
4-0

0
[18-18]



Charmed
Bottom
Omega


2-2
2-2
2-2
2-2
2-2
0-4
4-0
4-0
0-4

12
[12-24]



Double
Bottom
Omega


2-2
2-2
4-0
2-2
2-2
0-4
2-2
2-2
0-4

12
[24-12]



Double
Charmed
Bottom
Omega


2-2
2-2
2-2
2-2
4-0
4-0
0-4
4-0
4-0

0
[18-18]



Charmed
Double
Bottom
Omega


2-2
2-2
2-2
2-2
2-2
0-4
4-0
4-0
0-4

ZPF **Photons** **Bosons** **Tetryons**

$n\pi$ charged mass-Energy-Matter geometries


Ω
1
[1-0]
π
1
1
1
[0-1]
℧
2
ε0
2π
3
0
[1-1]
Q
1
Q
1
[2-1]
ε0
3π
ε0
3
3
3
3
1
[1-2]
Q
4
[4-0]
4π
4n
0
[2-2]
4π
4n
4π
4n
4π
4n
4
[0-4]

ZPFs are the quantum of Bosons

All energies seek equilibrium

Energy momenta

$n\pi[[m\Omega v]^2]$

Energy, Planck quanta, mass, velocity

EM mass-Energies

EVEN $\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$

mass-energy, EM Field, ElectroMagnetic, Planck quanta, mass, velocity

Charges

ODD $\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$

Charge, EM Field, ElectroMagnetic, Planck quanta, mass, velocity

Matter

$4n\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$

Matter, EM Field, ElectroMagnetic, Planck quanta, mass, velocity

Tetryonics 11.01 - Charged Energy-Matter geometries

Gluons

The gluon can be considered to be the fundamental exchange particle facilitating the strong interaction between protons and neutrons in a nucleus.

Gluons are the exchange particles for the 'colour' strong force between quarks, analogous to the exchange of photons in the electromagnetic force between two charged particles.


0
[2-2]
ε_0
$^0 3$
ε_0
ε_0


'Attractive' Colour Force
Opposite charge Tetryonfascias
Colour Force fascias
θ
0°
Same direction QAM flux
Colour force Interaction angle

The interaction between neutral Tetryons (Gluons) and all charged Tetryons is the Strong Colour force


0
[18-18]
2-2
2-2
2-2
2-2
2-2
1
2
3
4
5
N^0
d
u
d



Ω

Gluons are considered to be bi-coloured, carrying a unit of colour and a unit of anti-colour

℧



Q

Gluons are the neutral Tetryons inside all fermionic Matter topologies

nett charge of Gluons is same as a Neutron


0
[42-42]
9 neutral
[18-18]
tetryons
45,012
9
N^0
e-
p^+

Electrons contain no Gluons


12
[24-12]
2-2
2-2
2-2
2-2
1
2
3
4
P^+
u
d
u


$^0 3$
ε_0
$^0 3$
$^0 3$
0
[2-2]

They are the neutral charge [di-electric] Tetryons located between charged Tetryons in Matter topologies

[attractive coulombic forces between their opposite charged fascia create the 'colour force]


d
d
e-
p-
u
p+
ν^0
u
N^0
e+

Neutral Tetryons combine with charged Tetryons to form all Particles



Gluons in Fermions

In the Standard model Gluons have no mass and no electric charge.
They carry a special 'colour charge' property that hold quarks together to form Baryons

'Gluons' are neutral tetryons

Neutrinos are 3 Gluon sets

Tetryonics reveals that gluons are neutral charge tetryons comprised of equal positive & negative mass-energies & are elementary Matter particles

up Quarks have 1 Gluon
[Neutral Tetryon]

anti-down Quarks have 2 Gluons
[Neutral Tetryons]

GLUONS
are the neutral tetryons in Matter topologies acting as a di-electric between charged tetryons

down Quarks have 2 Gluons
[Neutral Tetryons]

anti-up Quarks have 1 Gluon
[Neutral Tetryon]

$4\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$ Gluons

$12\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$ Glueballs

u
8
[10-2]
2-2
1
4-0
4-0
8
d
4
[8-4]
4-0
1
2
2-2
2-2
8
EM Field
Planck
quanta
ElectroMagnetic
mass
velocity
d
4
[4-8]
2-2
2-2
1
2
0-4
8
u
8
[2-10]
0-4
0-4
1
2-2
8
0
[6-6]
2-2
2
+
3
2-2
ve
+
+
1
12
2-2
EM Field
Planck
quanta
ElectroMagnetic
mass
velocity
2-2
1
0
[6-6]
—
—
ve
2-2
2
—
3
2-2
12

Copyright ABRAHAM [2008] - all rights reserved

Baryonic Gluons

In 'the Standard Model', Gluons are vector gauge bosons that mediate strong interactions of quarks in quantum chromodynamics (QCD). Unlike the electrically neutral photon of quantum electrodynamics (QED), gluons themselves carry colour charge and therefore participate in the strong interaction in addition to mediating it, making QCD significantly harder to analyze than QED.

They are considered to be elementary particles which act as the exchange particles (or gauge bosons) for the colour force between quarks, analogous to the exchange of photons in the electromagnetic force between two charged particles

Tetryonics simplifies the current definition of Gluons and clearly identifies their geometric properties, along with their role in particle genesis



Neutrons have 5 Gluons

[Neutral Tetryons]

0

[18-18]

Deuterium nuclei (being the constituent quanta of all Elements) have 9 neutral Tetryons (Gluons) which in turn contribute to their gravitational mass along with the charged Tetryons



12

[24-12]

Protons have 4 Gluons

[Neutral Tetryons]



'Glueballs'

In particle physics, a glueball is a hypothetical composite particle.
It solely consists of gluon particles, without valence quarks.



Neutral Tetryons
are the result of equal number
charged EM fields combining to form
neutral charge Tetryonic topologies



It is conceivable that given the right conditions (ie a cloud of neutral Tetryons), that in the absence of charged Tetryons to interact with, a Glueball topology can be formed entirely from neutral Tetryons

Note: Despite their total neutral charge
Glueball topologies are polarised

Neutrinos and some exotic neutral charge Baryons
can be considered to be 'Gluon topologies'





It is possible to create a family
of Baryonic particles comprised
entirely of neutral Tetryons





Neutrons are not considered to be Glueballs
as they contain charged Tetryons

OMEGA Particle
Icosahedron Glueball



20 Neutral Teryons





The 3 internalised planes formed by
the external apex points correspond with
the 3 spatial dimensions of Cartesian geometry

Non-gluonic Baryon formation

Non-neutral 'UP' quark has +4 charge as opposed to +8 charge of UP quark


8
[10-2]
+2/3
2-2
4-0
u
4-0


0-4
4
[4-8]
-1/3
2-2
d
2-2

Non-neutral 'DOWN' quark has +4 charge as opposed to -4 charge of DOWN quark


4
[8-4]
+1/3
0-4
4-0
4-0
?

Baryonic Particles can be formed with non-neutral dielectric Tetryons in lieu of the usual neutral Tetyrons [Gluons] - altering the nett charges of the quarks formed


4-0
4
[4-8]
-1/3
0-4
0-4
?


+4
+4
+4
+12
[24-12]
0-4
4-0
4-0
0-4
+1
36
4-0
4-0
0-4
4-0
4-0


+4
-4
+4
0-4
0-4
0-4
0-4
+4
[20-16]
+1/3
4-0
4-0
4-0
4-0
4-0
36

Un-stable form

[rapidly decays into constituent Quarks]

Resulting in another family of Baryons [CHARGEBALLS]

Stable Form

[possibly mistakenly viewed as Bottom Quarks]


0-4
0-4
4-0
0-4
0-4
-12
[12-24]
-1
36
4-0
0-4
0-4
4-0
-4
-4
-4


0-4
0-4
0-4
0-4
0-4
-4
[16-20]
-1/3
4-0
4-0
4-0
4-0
36
-4
+4
-4

Electro-Magnetic fields

Quantised Charge
is the nett geometry of mass-Energy-Matter formed
by equilateral ElectroMagnetic fields and can be
modelled with classical vector flux rotations



Positive Charge ZPF

Magnetic Monopoles do NOT exist

Negative Charge ZPF





Charge

All mass-Energy-Matter EM field interactions can be modelled using ZPFgeometries

Current

ε_0 Q μ_0

The charge geometry of all
EM fields determines their
Electric Permittivity and
Magnetic Permeability

**The 'zero point' field
has scalar EM energies**



velocity
vector momentum
Charge geometry
Electric Flux Permittivity Field
angular momenta
p
ε0
m
hν
v²
Magnetic Permeability Dipole field
c²

**The EM field is a equilateral waveform with the
Magnetic field always orthogonal to the Electric**

**The Magnetic fields propogate bi-directionally
and the Electric field is responsible for
producing linear momentum**

**The Electric field and Magnetic fields
are equal to each other
and directly proportional
to the velocity of propagation**

Photons
are the neutral quanta of EM waves
they are comprised of two opposite charge
EM field quanta



Electro-Magnetic fields are the source of all physical Forces

Zero Point fields are polarised
and are the sources of



**Electro-static and Magneto-static
fields and particles**

Copyright ABRAHAM [2008] - all rights reserved

The Weak Force


12
[0-12]
e-
12
W
ε₀

6 Inductive 'Weak' edges
(3 internalised)
(3 externalised)

Quantum Energy is stored or released, and distributed throughout Tetryonic geometries in ODD number quanta [Bosons]

Quantum Inductive loops

Quantum Tank circuit

Energy received is stored in quantum inductive loops (until its release via weak interaction - Boson exchange)


v
ε₀
L
W
hv
v²
c²

All ElectroMagnetic fields are ideal quantum inductive loops of EM energy momenta

Each has a Magnetic edge (base) which acts as a quantum inductor through which energy can be absorbed or released in EM quanta via electro**Magnetic** induction [exchange Bosons]

Leptons and Quarks have the same Tetryonic numbers but differing Matter topologies



6 Inductive 'Weak' edges


12
4
[4-8]
down
d


12
[24-12]
Proton
P+
36
W
d

18 Inductive 'Weak' edges


36
0
[18-18]
N⁰
Neutron
W
d

The Strong Force

The force resulting from the interaction of 2 Tetryons along their parallel planar (Electric charge) surfaces



Leptons Repulsive colour Force

Leptons are 'held together' by a radial Weak Force axis





'Attractive' Colour Force
Opposite charge Tetryon fascias

Same direction
QAM flux

Colour Force fascias

θ
0°

Colour force Interaction angle

'Repulsive' Colour Force
Same charge Tetryon fascias

Opposing direction
Electric flux
rotation

Strong Force strength is directly proportional to the nett mass-energy quanta involved
(Increases/decreases as total Tetryon mass-energy quanta increases/decreases)

Leptons and Quarks result from the Strong 'colour' force interactions in dodeca-deltahedrons

(In Quarks the attractive strong force produces Octahedral topologies)
(In Leptons the repulsive strong force produces Dodecahedral topologies)



Quarks
4 Fascia 'Colour' Attraction

Quarks Attractive colour Force





Baryons Attractive colour Forces

Baryon formation
16 Fascia 'Colour' Attraction



The Strong Colour Force is the binding force that holds Nuclei together

Tetryonic Fascia (Planar Electric Charge) interaction



It interacts through oppositely charged Tetryon Fascias in contact with each other in all Matter (save Leptons)



Strong Force Interaction

On the smallest scale (less than about 0.8 fm), it is the Electric force (mediated by gluons in nuclei) that holds Tetryons together in order to form Quarks, Protons and Neutrons


0
[18-18]
Neutron
36π
20π


Nuclei
12
[42-30]
72π
40π


12
[24-12]
Proton
36π
20π

The residual Electric field force produced by the Strong Force is also facilitates the binding of Protons and Neutrons together to form the nucleus of an atom

Attractive Colour Charge Force holding Quarks and Nuclei together

Atomic Nucleus


0
[18-18]
36π
N⁰

36 charged mass-energy fascia geometries


12
[24-12]
36π
P+

12
[42-30]

creates an external Baryons topology with 20 charge fascia

Copyright ABRAHAM [2008] - all rights reserved

Proton Hydrogen ion

36

1 Proton	24-12	
Total Charge	24-12	[+12]

H^+

F+ n=25



Proton - Hydrogen ion

The Proton is a Baryon with a Positive Tetryonic charge geometry of +12 [24-12] [and a final Matter topology of 20π]

It attracts electrons [0-12] and Neutrons [13-18] through their opposite charged facia in order to reach charge equilibrium

The Proton's opposite charge particle is the electron
If it binds with one or more Neutrons it will still attract electrons in order to acheive Tetryonic charge equilibrium.

As a Hydrogen nuclei it is highly reactive

Neutral Hydrogen

48

1 Proton	24-12	
1 electron	0-12	
Total Charge	24-24	[0]

H^0

F+ n=25
e- n=1



Neutral Hydrogen

Hydrogen is the Second Neutral Tetryonic geometry [Baryon] formed in the creation of Matter

It is a [24-24] NEUTRAL [balanced] Tetryonic charge geometry

The Neutral Hydrogen Atom interacts with Deuterium and other Elements via its external nucleon fascia charges (residual EM Interactions)

Deuterium

84

1 Proton	24-12	
1 Neutron	18-18	
1 electron	0-12	
Total Charge	42-42	[0]

D 1

N^0 n=25
F+ n=25
e- n=1



Deuterium

Deuterium has the same nett charge as Neutral Hydrogen but has an increased Tetryonic mass- Matter topology

It has an additional 9 Tetryons in its nucleus (due to the Neutron) and consequently is larger than the Hydrojon nucleus

It has a [42-42] NEUTRAL Tetryonic charge geometry
Deuterium nuclei combine to form all other elements

Tritium

84

1 Proton	24-12	
1 Neutron	18-18	
1 electron	0-12	
Total Charge	42-42	[0]

D 7

N^0 n=31
F+ n=31
e- n=7
Radioactive Isotope



Tritium

(Radioactive Deuterium)

Tritium has the same nett Tetryonic charge as Neutral Hydrogen and Deuterium (D) but due to its higher quantum energy levels it has additional mass-energy quanta in its charged geometry

It has the same 84 charged fascia in its nucleus as Deuterium but its increased mass-energy is equivalent to that of 1 Neutron.

This extra nuclear energy is the source of its radioactivity and ongoing confusion in chemistry where it is released as a variety of decay particles over time

Copyright ABRAHAM [2008] - all rights reserved


Hydrogen - Helium genesis
0
Hydrogen
[24-24]
0-12
24-12
H
22,512
+12
[24-12]
(ionised)
Additional charged Baryon
+ Neutron
[18-18]
0
Deuterium
[42-42]
18-18
0-12
24-12
²H
45,012
+12
[42-30]
(ionised)
Increased Energy quanta
[n-n]
Elemental nuclei formation
0
Tritium
³H
[42-42]
18-18
n7
0-12
24-12
69,780
+12
[42-30]
(ionised)
Helium
0
[84-84]
18-18
0-12
24-12
24-12
0-12
18-18
He
90,024
+24
[84-60]
(ionised)

Tetryonics 13.02 - Hydrogen-Helium genesis

Hydrogen Family


12
[24-12]
22,500
+
12
[0-12]
12
=
0
[24-24]
22,512

Proton	electron	Hydrogen
36π	12π	48π


0
[24-24]
22,512
+
0
[18-18]
22,500
=
0
[42-42]
45,012

Hydrogen	Neutron	Deuterium
48π	36π	84π


0
[42-42]
n1
45,012
+
=
0
[42-42]
n7
69,780

Tritium is Radioactive

6 quantum level
Energy increase
(24,768 n quanta)

1.1008 Neutron mass-Matter

Deuterium	Tritium
84π	84π

Copyright ABRAHAM [2008] - all rights reserved

Copyright ABRAHAM [2008] - all rights reserved

Hydrogen-Helium3 genesis

Elemental Form

Positive Ions


0
[24-24]
48
22,512
e-
P+

Hydrogen


12
[24-12]
36
22,500
P+

Proton


0
[42-42]
84
45,012
N0
e-
P+

Deuterium


12
[42-30]
72
45,000
N0
P+

Deuterium$^+$

Radioactive


0
[42-42]
84
69,780
N0
e-
n7
P+

Tritium


12
[42-30]
72
69,192
N0
P+

Tritium$^+$

Tritium 0


0
[60-60]
120
67,512
N0
e-
n1
P+
N0

Tritium 0$^+$


12
[60-48]
108
67,500
N0
P+
N0

Tritium 0
is a non-radioactive allotrope of Tritium,
it has the same Tetryonic charge and mass-Energy as Helium 3
(but is ionically 1 elemental charge less than Helium 3)


12
[66-54]
+1
120
67,512
P+
N0
e-
n1
P+

Helium 3


24
[66-42]
+2
108
67,500
P+
N0
P+

Helium 3

Quantum Batteries

Atomic nuclei can be easily scaled to non-quantum sizes to offer clean, safe and portable long term energy storage devices that can store energy indefinitely and release it on demand anywhere in the World



Negative charge topology

Quantum Rotor

12 loop quantum inductive rotor

The quantum battery is unique in that in addition to storing energy indefinitely, when the nuclei combine with a lepton it has the ability to release specific energies [photons] by way of its synchronous quantum convertor topology


Quantum Cathode
12
[42-30]
N 0
n
e-
P+
45,000
Quantum Anode

Energy stored in quantum batteries is measured as mass

(Atomic Nuclei)


24
[84-60]
+
-
P+
N 0
n1
n1
N 0
P+
45,000
45,000
-
+

anti-Parallel Configuration

The non-neutral charge of atomic nuclei attract free leptons into 'bound' states within the various **n** levels of atomic shells releasing energy as spectral photons

Series Configuration


24
[84-60]
-
N 0
n2
P+
N 0
n1
P+
90,000
+

Quantum synchronous Converters

The electron can be viewed as
a rotating inductor consisting of
3 negative Tetryons

EM Field Planck quanta

$$12\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]^{n8}_{n1}$$

Leptons ElectroMagnetic mass velocity

The electron has a charged
Matter topology that is electrically
equivalent to a quantum 6 loop inductive rotor

Quantum
Cathode



Quantum
Anode

EM Field Planck quanta

$$72\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]^{n32}_{n25}$$

Nuclei ElectroMagnetic mass velocity

With the addition of a quantum rotor (lepton) a quantum battery can
be converted from a storage device into a energy distribution device.

And just like the quantum battery, the quantum convertor can be scaled
to any size in order to provide tailor-made energy efficient delivery devices

EM Field Planck quanta

$$84\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]^{n32}_{n25}$$

Deuterons ElectroMagnetic mass velocity

***Where varying levels and frequencies of Energy
are transmitted long distances and
need to be stored for later release on demand
the 'ideal' mechanical device is
the rotating (or synchronous) convertor***

Changes in energy-momenta results in photon emission/absorption lines
photon emission/absorption produces changes in leptronic energy-QAM
and results in the quantum transition of electrons in atomic orbitals

Changes in Baryonic energy levels induces a directly
proportional change in electron energy levels

3 forms of mass-energy momenta
are possessed by quantum convertors

Angular Momentum (motional energy)
linear momentum of Baryons & leptons

Photonic spectral energies (emission/absorption)
KEM fields geometries of photo-electrons

Nuclear mass-energies (stored energy quanta)
standing wave mass-energies of Matter topologies



QAM of KEM field
creates angular momentum

A change in any 1 of the 3 types
of energy in a atom results
in a proportional change in the other 2

*External EM fields and incident photons can all
affect the quantum energy levels of the atomic nuclei*

Hydrogen Ionisation Energies

$$Mv^2 = KEM = hv^2$$


n8
En = -0.21 eV
768
n7
En = -0.27 eV
588
n6
En = -0.37 eV
432
n5
En = -0.54 eV
300
n4
En = -0.84 eV
192
n3
En = -1.50 eV
108
n2
En = -3.4 eV
48
n1
0
[24-24]
En = -13.6 eV
12
22,512
Hydrogen

The KEM Planck quanta
required to ionise
a photo-electron

The ionisation energy level for each quantum level
is proportional to the square of the
quantum number


Electron energy
$E = \frac{-13.6eV}{n^2}$
Orbit Radius
$r = n^2 a_0$
Electron
Wavelength
$\lambda = 2\pi n a_0$
Ionization
energy
n=5
n=4
n=3
-1.5 eV
n=2
-3.4 eV
n=1
-13.6 eV
n=1
n=2
n=3
n=4
n=5
$a_0 = 0.0529nm$ = Bohr radius

**In Hydrogen nuclei electrons
remain in the same position
close to the Proton due to
Coulombic attraction.**

**The established model of electron orbitals
having circular radii of increasing size
in proportion to their energies
is incorrect**


N
S
Nuclear Magnetic moment
N
S
KE
$m = -½; "\beta"$
$+½\ \hbar\gamma B$
$\Delta E = \hbar\gamma B$
$m = +½; "\alpha"$
$-½\ \hbar\gamma B$
B
BOHR magneton
BOHR magneton
N
S
KE
S
N
KE

Spin UP
Parallel magnetic moments
(higher energy)

Spin DOWN
Anti-parallel magnetic moments
(lower energy)



The intrinsic magnetic moment of the rotating electron
couples wrt the nuclear magnetic moment to
produce a split in the resulting spectral lines
produced by quantum level transitions

Copyright ABRAHAM [2008] - all rights reserved



Hydrogen Energy Levels

KEM field energy in each electron's energy level

$Mv^2 = KEM = hv^2$

The rest mass-energy content of Matter topologies in motion is INVARIANT to changes of velocity-momentum

M_0

$M\left[\frac{v}{c}\right]^2$

The mass-energy geometries of all KEM fields are subject to Lorentz corrections

$M[\beta]^2$

rest Matter Electrons have zero velocity and no KEM field

13.6 eV
Free Electron

n8+
Free Electrons have Kinetic Energies of 13.6 eV+

n0
n1
n2
n3
n4
n5
n6
n7
n8
12
0-12
1.2e20
0 eV
v
1
12
p
[0.845 eV]
3
48
5
[1.901 eV]
108
7
[3.381 eV]
192
9
[5.283 eV]
300
11
[7.607 eV]
432
13
[10.355 eV]
588
15
[13.5259 eV]
768
hv
v²
c²
KEM
n1
0.211 eV
n2
0.845 eV
n3
1.901 eV
n4
3.381 eV
n5
5.283 eV
n6
7.607 eV
n7
10.3551 eV
n8
13.525 eV

Tetryonics 13.08 - Hydrogen Energy Levels

Kinematics

An inertial frame of reference is one in which the motion of a particle not subject to forces and results in motion in a straight line at constant velocity

Deceleration

[Inertial Frame MINUS odd quanta]



Newton's First Law

$$\sum \mathbf{F} = 0 \Rightarrow \frac{d\mathbf{v}}{dt} = 0$$

Every body persists in its state of being at rest or of moving uniformly straight forward, except insofar as it is compelled to change its state by force impressed



Newton's Second Law

$$\sum \mathbf{F} = \frac{\mathrm{d}\mathbf{p}}{\mathrm{d}t} = m\frac{\mathrm{d}\mathbf{v}_{cm}}{\mathrm{d}t} = m\mathbf{a}_{cm}$$

Force creates a change in Momentum over Time

A body of [m]ass subject to a net [F]orce undergoes an [a]cceleration that has the same direction as the force and a magnitude that is directly proportional to the force and inversely proportional to the mass, i.e., F = ma.

Alternatively, the total force applied on a body is equal to the time derivative of linear momentum of the body.

Sir Issac Newton

(25 December 1642 – 20 March 1727)

$$a = \frac{\Delta y}{\Delta x} = \frac{\Delta v}{\Delta t}.$$

$$\mathbf{F} = ma \quad \rightarrow \quad \mathbf{a} = \mathbf{F}/m$$

Acceleration

[Inertial Frame PLUS odd quanta]





PHILOSOPHIÆ
NATURALIS
PRINCIPIA
MATHEMATICA.

AUCTORE
ISAACO NEWTONO, Eq. Aur.

Editio tertia aucta & emendata.

LONDINI:
Apud Guil. & Joh. Innys, Regiæ Societatis typographos.
MDCCXXVI.

Copyright ABRAHAM [2008] - all rights reserved

Inertia and Force

Any change to the energy-momenta content of a closed inductive loop requires a proportional change to the loop's energy density

momentum

The classical definition of Momentum
relates the mass of a material body
at given velocity (v) to its Momentum (p);
it is a proportionality factor in the formula

$$p = mv$$

Force

This meaning of a body's inertia therefore is altered
from the classsical definition of "a tendency to maintain
momentum" to a description of the measure of how
difficult it is to change the momentum of a body

$$F = ma$$

linear quanta forces

divergent ↑ $[v - v]$ ↓ convergent

Transverse Bosons

Any change to energy-momenta
levels in Tetryonic geometry
requires specific number quanta

Scalar mass-energy

Inertia is resistance to change
of energy momenta vectors
within spatial geometries



[all inductive loops resist changes to their energy levels]

Inertia is the resistance of any physical object to a change in its state of motion or rest, or the tendency of an object to resist any change in its motion.

The principle of inertia is one of the fundamental principles of classical physics which is used to describe the motion of matter and how it is affected by applied forces



Linear momentum is the nett square root of mass-energy quanta

p

$$E = mv^2$$

Any change in the energy-momenta content of a body of mass-Matter results in a proportional change in its momentum-velocity



Force is the sum of the linear mass-energy momenta quanta

F

Gottfried Wilhelm von Leibniz

(July 1, 1646 – November 14, 1716)



Scalar Energy

Leibniz's vis viva (Latin for living force) is mv^2, twice the modern kinetic energy.

He realized that the total energy would be conserved in certain mechanical systems, so he considered it an innate motive characteristic of Matter.

His thinking gave rise to another regrettable nationalistic dispute. His vis viva was seen as rivaling the conservation of linear momentum championed by Newton in England and by Descartes in France; hence academics in those countries tended to neglect Leibniz's idea.

In reality, both energy and momentum are conserved, so the two approaches are equally valid.

Newtons

of force

The nett direction of Force within energy geometry is UNIDIRECTIONAL
ie the force exerted is the result of the nett linear momenta irrespective of charge



[Joule seconds] per second

mass x velocity squared $kg.\left[\frac{m}{s}\right]^2$

$$\boxed{\text{Energy} \quad kg.\frac{m^2}{s^2}}$$

$$J = \frac{kg \cdot m^2}{s^2} = N \cdot m = Pa \cdot m^3 = W \cdot s$$

A Joule is equal to the energy expended (or work done) in applying
a force of one newton through a distance of one metre
(1 newton metre or N·m)

momentum x velocity $\left[kg.\frac{m}{s}\right].\frac{m}{s}$

Planck's quanta per second $\left[kg.\frac{m^2}{s}\right].s^{-1}$



[Joule seconds] per second

Copyright ABRAHAM [2008] - all rights reserved

Linear Momentum

Linear momentum is the SQUARE ROOT of equilateral Planck mass-energy geometries and produces a undirectional vector force

The Energy-momentum relationship is a fundamental physical property used to determine the mass of a body

Using the formula for mass-Energy equivalence as it relates to Photons moving at 'c'

$$E = h\nu = \frac{hc}{\lambda} = mc^2$$

Noting that the rest mass in the case of EM fields (Bosons and Photons) is to equal Zero

we can derive a relationship for Momentum - Energy - Wavelength showing that

$$p = E/c$$

Thus momentum in Photons is directly related to the EM energy content of the photon and the mass-energy content of any massive 3D body

$$p = \hbar k = \frac{h\nu}{c} = \frac{h}{\lambda}.$$

and momentum in Particles is related to the total EM Energies of an object (its rest Matter + KE) and the wavelengths associated with those distinct energy levels

$$p = \frac{E}{c} = \frac{h\nu}{c} = \frac{h}{\lambda}$$



Longitudinal [linear] momentum

$$p = n\pi\overset{\text{Energy}}{\underset{\text{momentum}}{\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v}\right]\right]}}$$

Momentum is a conserved quantity, meaning that the total momentum of any closed system (one not affected by external forces) cannot change.

Linear Momentum is the intrinsic sqare root vector component of Force

$$p = mv$$

In classical mechanics, momentum is the product of the mass and velocity of an object.

$$\sum \mathbf{F} = \frac{d\mathbf{p}}{dt} = m\frac{d\mathbf{v}}{dt} + \mathbf{v}\frac{dm}{dt}$$

In relativistic mechanics, this quantity is multiplied by the Lorentz factor.

$$p = \frac{n\pi\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]}{v} = mv$$

EM field momentum is a function of its energy density, and is directly proportional to the group velocity

$$\left[\sqrt{\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v}\right]^2}\right]$$

Vector linear momentum

is the square root of the KEM field energies produced by Matter in motion

Energy

$$n\pi\left[\left[m\Omega v\right]\right]$$

momenta

Classical formulation

$$p = mv$$

Linear Momentum
is the vector force of
mass times its velocity

Quantum formulation

$$p = \frac{E}{v}$$

Linear Momentum is
Energy divided by the
square root of its quanta

INERTIAL FRAME
[m/s]



Energy required to change
the velocity of a mass

Energy content
for a specific velocity

$$\mathbf{p} = \sum_{i=1}^{n} m_i \mathbf{v}_i = m_1\mathbf{v}_1 + m_2\mathbf{v}_2 + m_3\mathbf{v}_3 + \cdots + m_n\mathbf{v}_n\,,$$

The linear momentum of a EM field or system of particles is
the vector sum of the linear momenta in the KEM fields
of individual particles in any spatial co-ordinate system

$$\frac{E}{c^2}.v$$

$$\frac{hv^2}{v}$$

Kinetic Energy
is the Electric field energy of Matter in motion

$$1/2\left[\underset{\text{Matter}}{4n\pi}\left[\overset{\text{EM Field}}{\underset{\text{ElectroMagnetic}}{[\varepsilon_0\mu_0]}}.\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]\right]$$

Kinetic Energy is the diamond electric field extending from charged Matter topologies as a result of its motion, it follows Tetryonic omega geometry and is proportional to an object's mass-Matter and its vector velocity

Charge
Q
[v-v]


Quantum Levels
n8
n7
n6
n5
n4
n3
n2
μ_0
μ_0
ε_0
ε_0
μ_0
μ_0
ε_0
μ_0
μ_0
Leptons absorb/emit Kinetic Energies
v
Velocity
Photon frequencies
Compton frequencies
Leptonic field energy

12n
rest Matter

Relativitic
mass-Energies
M+KE

[n-n]
Kinetic Energies

Kinetic Energy is
1/2 of the secondary KEM
field energies created when
Matter particles are in motion

$$\frac{2\pi\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]}{\underset{\text{EM Field}}{c^2}}$$

and is shown to be subject to
Lorentz corrections






v
p
KE
μ_0
μ_0
Magnetic moment
M
v²





Kinetic Energies
create
Magnetic Moments

$$KE = \frac{1}{2}Mv^2$$

Kinetic energy is a scalar quantity;
it does not have a direction.

The Kinetic Energy of an object is the energy which it possesses due to its motion.

It consists of Neutral Electric fields and an associated Magnetic moment

Kinetic Energies are subject
to Lorentz corrections

$$E_k = mc^2 - m_0c^2.$$

rest Matter is not









Tetryonics 14.06 - Kinetic Energy

Copyright ABRAHAM [2008] - all rights reserved

Kinetic Energy and Magnetic moments

$$Mv^2 = KEM = p^2$$

Unlike charged fields KEM fields have neutralised Electric Fields


v
E
ε_0
Ω
+
hv
N
S
v²

KEM field geometry of positive charged Matter in motion

$$KE = \frac{1}{2}Mv^2$$


v
E
ε_0
Ω
−
hv
S
N
v²

KEM field geometry of negative charged Matter in motion

Often noted as being two distinct EM energies [Kinetic Energy and Magnetic moments] are shown to be orthogonal aspects of the same KEM field of motion


v
p
ε_0
KE
ε_0
μ_0
M
hv
v²
Magnetic
Dipole
Moment
c²

As the velocity of a particle increases so does its Kinetic Energy and Magnetic moment creating Lorentz variable KEM fields



$$\mu_B = \frac{1}{2}Mv^2$$



$$\mu_B = \frac{1}{2}Mv^2$$

Types of Momentum

Ω

quantised angular momenta

[m²/s]

The quantised 'angular momentum' of each Planck mass-energy geometry, gives rise to the two quantum Charges

p

Linear momentum

[kg·m/s]

The square root (v) of each Planck quanta's mass-energy geometry (v^2) is vector Linear Momentum

ℓ

Angular momentum

[kg·m²/s]

The orbital angular momentum of electrons in atoms associated with a given quantum state

. . . [n-1] [n] [n+1] . . .

There are 3 forms of momenta in physics

equilateral charge geometry



h

[kg·m²/s]

$m\Omega$



vector momentum



mv

[kg·m/s]

p



vector rotation about a point



$$L^2 = L_x^2 + L_y^2 + L_z^2$$

Copyright ABRAHAM [2008] - all rights reserved

Kinetic Energy vs Momentum

An important difference is that Kinetic energy is a scalar quantity - it has no direction in space
momentum is a vector quantity - it has a direction in space, momenta combine like forces do.

$$p = Mv$$

$$KE = 1/2\,[Mv^2]$$



Energy momenta





KEM field

$$p = \sqrt{E}$$

$$KEM = Mv^2$$

In Tetryonic geometry, the square root maps the linear momenta [mv] of a field to its ENERGY

$$p^2/_{2m} = KE$$

In Tetryonic geometry, E-field geometry maps the kinetic energy [1/2 mv] of a field to its ENERGY

Linear momentum has a different geometric ENERGY relationship to that of Electric fields

Copyright ABRAHAM [2008] - all rights reserved



mass-Energy-momentum

$p=mv$
[vector force]

$m=\frac{F}{a}$
[inertial mass]

Like velocity, linear momentum
is a vector quantity,
possessing a direction
as well as a magnitude

The intrinsic mass-Energy
of a massive body is a result
of its nett Energy
per unit of Time

$KEM=mv^2$
[Kinetic Energy & magnetic moment]

$KE=\frac{1}{2}mv^2$
[scalar E-field]

$$E = m_0c^2 + K$$

$$E^2 = p^2c^2 + m_0^2c^4$$

Often generalised as having the geometry of
right angled triangles the mass-energy momenta
relationship is fully revealed using
Equilateral geometry

The Energy of a system
is the square of
its linear momentum

The Kinetic energy
of Matter in motion is
directly related to its
velocity

E^2
**is the energy content
of a superpositioned
EM field**

$E=mv^2$
[scalar KEM field energies
of Matter in motion]

$E=p^2$
[Energy momenta]

$[m\Omega v]$
Planck quanta
mass velocity

Linear momentum is the square root
of the Energy of a system.

It is the nett linear Force
resulting from Matter in motion
and was used by Newton
as the foundation for
his Laws of motion

acceleration results in
changes to momenta

$F=ma$

Newton's
Second law of Motion

Linear momentum is also a conserved quantity, meaning that
if a closed system is not affected by external forces, its total
linear momentum cannot change. Although originally expressed
in Newton's second law, the conservation of linear momentum
also holds in special relativity and, with appropriate definitions,
a (generalized) linear momentum conservation law holds in
electrodynamics, quantum mechanics, quantum field theory,
and general relativity. In relativistic mechanics, non-relativistic
linear momentum is further multiplied by the Lorentz factor

Lorentz Factor

Tetryonics 14.10 - mass-Energy momentum

Copyright ABRAHAM [2008] - all rights reserved

Lorentz velocity correction Factor

The Lorentz factor or Lorentz term is an expression which appears in several equations in special relativity. It arises from deriving the Lorentz transformations. The name originates from its earlier appearance in Lorentzian electrodynamics - named after the Dutch physicist Hendrik Lorentz.

Wavelength, momentum

mass-ENERGY



$$\beta = \left[\frac{v}{c}\right]$$



$$\left[\frac{v^2}{c^2}\right] = \beta^2$$



Classically modelled as an infinite series approaching c
Tetryonics reveals it to be a physical property
of equilateral energy-momenta geometries



A vector measure of the Energy content of a waveform

$$\gamma \equiv \frac{c}{\sqrt{c^2 - v^2}} = \frac{1}{\sqrt{1 - \beta^2}} = \frac{dt}{d\tau}$$

A scalar measure of a KEM waveform's energies

$$\gamma = 1/\sqrt{1 - v^2/c^2}$$

Importantly - Newton's classical velocity addition remains correct, but the energy-momenta required to accelerate Matter to higher velocities increases exponentially in line with the equilateral [Tetryonic] geometry of mass-energies

γ

Γ

Tetryonics 14.11 - Lorentz velocity correction Factor

Copyright ABRAHAM [2008] - all rights reserved

Unified Energy momenta geometry



$$m = n\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$$

$$p = n\pi\,[m\Omega v]$$

$$E = n\pi\left[[m\Omega v]^2\right]$$

$$mv = p$$

$$p^2 = E$$

$$\beta = \left[\frac{v}{c}\right]$$

Linear Lorentz factor

$$\beta^2 = \left[\frac{v^2}{c^2}\right]$$

Scalar Lorentz factor

$$E_\gamma = 2\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$$

$$m = 4n\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$$

Tetryonic's equilateral geometries model EM mass-ENERGY momenta in all its forms

EM Field
Planck quanta
mass
Electromagnetic
mass
velocity
linear momentum
quantised angular momentum
energy
mass
velocity
linear momentum
quantised angular momentum
v
ε_0
m
v^2
mass
c^2
c
ε_0
E
v^2
Energy
c
ε_0
γ
v^2
μ_0
c
Photons
c
m
v^2
Collapsed waveform
Matter
c^2
v
1
p
2
3
4
5
6
7
1 2 3 4 5 6 7 9 10 12 13 14 15 16 17 19 20 21 22 24 25 26 27 29 30 31 32 34 35 36 49
1^2
2^2
3^2
4^2
5^2
6^2
v^2
3
5
7
9
11
+
hv
c
c^2
E
ε_0

Copyright ABRAHAM [2008] - all rights reserved

Squared Energy distributions


v
n
1e19
v
v²
c²

Bosons

Transverse EM mass-Energies

Odd number sequence

Number of quanta per geometry

n = (2n-1)

v
v²
n
1 2 3 4 5 6 7 8
1 3 5 7 9 11 13 15 17 19 21 23 25 27 29 31 33 35 37 39 41 43 45 47 49
1² 2² 3² 4² 5² 6² 7² 8² 9² 10² 11² 12² 13² 14² 15² 16² 17² 18² 19² 20² 21² 22² 23² 24² 25²
1 4 9 16 25 36 49 64
1 2 3 4 5 6 7 8
ε0
n
hv
v²
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 24 23 22 21 20 19 18 17 16 15 14 13 12 11 10 9 8 7 6 5 4 3 2 1

Squared quantum numbers are the integral sum of the preceeding Boson levels' odd quanta numbers

[n-1] Transverse Quanta Distributions [n-1]

EM mass-energy

Quantum numbers are *not* TRIANGULAR NUMBERS

TRI n = (n/2) x (n+1)

Quantum numbers are *not* TETRAHEDRAL NUMBERS

TETRA n = (n/6) (n+1) (n+2)

Scalar energy levels have SQUARED quanta

Photons

Longitudinal EM mass-Energies

Even number sequence

Number of quanta per geometry

n = (2n)

Tetryonic Energy and Charge relationships





Quantised angular momenta is the geometric source of all mass-Energy-Matter relationships



Scalar energies
(are 'squared' numbers)


n
hv
1
3
5
7
9
11
13
15
1^2
2^2
3^2
4^2
5^2
6^2
7^2
8^2
1
2
3
4
5
6
7
8

The Energy density of a particle's charged fascia geometry determines its mass

m

Charged mass-energy geometry & Matter topology determines a particle's physical characteristics (Type, Family, generation, mass etc)

M

Charge

-12

electron

12
[0-12]



1.2 e20

mass-Matter

e-

8.851486 e-31 KG

1875x
(differential)

Opposite nett elementary charge geometries

differing Matter topologies

Proton

12
[24-12]



2.25 e23

1.65965 e-27 KG

P+

+12

[v-v]


ε0
7.376238634 x 10[illegible] Kg
6.62943267 x 10[illegible] J [kg.m²s⁻²]
41,3766 ev
1.33518 x 10[illegible] C
[1/12 elementary charge]
1

Planck mass-energy

Copyright ABRAHAM [2008] - all rights reserved

Planck's energy momenta quantum

$$\frac{E}{c^2}$$

m



$$mv^2 = E = hv^2$$

q

Planck mass	m	m - mass quantum
Planck Charge quantised angular momentum / spatial co-ordinate system	Ω	v - quanta of Charge elemental charge / 12
Planck Energy	E	E - Energy quantum

q

v^2 Compton Frequency	$\frac{mc^2}{h}$	1×10^{19} quanta per second
λ de Broglie wavelength	$\frac{h}{mc}$	$2.99792458 \times 10^{-11}$ meters
p Momentum	mc	2.21134×10^{-23} Ns

Planck's constant is the equilateral geometry of rest mass-energy momenta in standing wave Matter topologies

Currently the Atomic masses are calculated using 1/12 of a Molar Carbon12 atom's mass as the reference mass.

Tq [Carbon] - [252-252]
Tm [Carbon] - 270,072



[270,072] / 12
22,506

If we calculated for the molar mass of C12 in 12 grams we would get
(.012/N/270072) $7.378205107 \times 10^{-32}$ kgrams
this is in error by 1/2 of the mass of an electron



Tetryonic mass [Hydrogen] - 2.2512 e23 v

Using Tetryonic geometry we can solve for an exact Compton frequency of any mass-Matter topology and account exactly for all quantum energy contributions to the rest Matter of all electrons and Baryons in any element thus determining exact molar masses exclusive of blackbody radiation, kinetic energies and energies of measurement and avoiding 'weighted' masses

Defining [N] as the number of rest mass Hydrogen atoms in 1gram exactly and makes Avagadro's number the inverse of this number

$$\text{Molar mass} = \frac{H_1\ \text{Atomic mass}}{\text{Avagadro's No.}}$$

$$\text{mass } H_{mol}/Av = \frac{.001}{6.022141579 \times 10^{23}}$$

$$\textbf{rest mass Hydrogen} = 1.660538841 \times 10^{-27}\ \text{g/mol}$$

$$H_{mole}/m[H] = \frac{1.660738412 \times 10^{-27}}{22{,}512}$$

$$\textbf{n Planck mass} = 7.376238634 \times 10^{-32}\ \text{Kg}$$

This is an exact Atomic rest mass as opposed to the current weighted molar Atomic mass estimates (which is incorrect by **1/2** the mass of an electron)

Planck's constant is the 'quantum of action' and also contributes to the mass-energies of radiant EM wave geometries

Tetryonics 15.04 - Planck's energy momenta quantum

Copyright ABRAHAM [2008] - all rights reserved

Nuclear Energy levels



Exponential energy levels

$1e19v = n = 5e18f$

Radioactive Decays follow exponential curves determined by the Tetryonic topology of the particle families

$\mathrm{T}\pi\,[[m\Omega n]]$

Energy
mass QAM quanta

12 [24-12]
0 [18-18]
12 [12-24]

Proton
Neutron

antiNeutron
antiProton

Electron
Positron

12 [12-0]
12 [0-12]
0 [6-6]
8 [10-2]
4 [4-8]

Neutrino

Up
Down
Strange
Charmed
Top
Bottom

4 [4-0]
0 [2-2]
4 [0-4]

Positive
Negative
Neutral

Bosons

EM Field Planck quanta

$\mathrm{ODD}\,\pi\,[[\varepsilon_0\mu_0].[m\Omega v^2]]$

Bosons
ElectroMagnetic mass velocity

EM Field Planck quanta

$2\pi\,[[\varepsilon_0\mu_0].[m\Omega v^2]]$

Photons
ElectroMagnetic mass velocity

Linear energy levels

1 [1-0]
0 [1-1]
1 [0-1]

Emission and Absorption of Bosons and Photons within Atomic Nuclei

Increase and decrease in integer amounts according to the Tetryonic geometries and topologies of the particles involved

Tetryonics 15.05 - Nuclear energy levels

Copyright ABRAHAM [2008] - all rights reserved

Energy momenta geometry

m

All mass-energies have equilateral geometries

E

mass-Energy

$kg\frac{m^2}{s^2}$


v
RE
p
ε0
m/s
Q
[v-v]
m²/s
m
Ω
m
m
hv
v²
m²/s²
m
KE
planck
quanta
[mΩv²]
mass
velocity
1 second²

Ω

Quantised angular momenta facilitates EM interactions

h

Planck's Constant

$kg\frac{m^2}{s}$



scalar mass velocity squared

$$mv^2 = E = hv^2$$



quantised angular momenta per second

Tetryonics 15.06 - Energy momenta geometry

Copyright ABRAHAM [2008] - all rights reserved

m

mass

E

Energy

Bosons are transverse EM masses

Photons are longitudinal EM masses


Velocity
Square root
Momentum
v
Quantum
Energy
p
Charge
Volts
Bosons
Current
Ω
mass
Velocity squared
hv
v²
c²

quantised angular momentum is the equilateral geometry of scalar mass-energies

mass is a measure of Energy per spatial co-ordinate system

mass-Energy momenta

Electromagnetic energy is a scalar measurement of mass

Tetryonics 15.07 - EM mass-energy relationships

Copyright ABRAHAM [2008] - all rights reserved

Bosons are Transverse masses


v
ε_0
m
v^2
c^2

Planck mass

EM Field Planck quanta

$$\text{ODD}\,\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Bosons ElectroMagnetic mass velocity


v
1
3
4
5
9
7
16
9
25
11
36
13
49
15
64
m
7.376238634e-51 kg
E
6.629432672 e-34 j
hv
v²

Photons are Longitudinal masses

Photons



EM Field Planck quanta

$$\text{EVEN}\,\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Photons ElectroMagnetic mass velocity

mass-ENERGY-Matter equivalence


12
LEPTONS
[0-12]
e-
12n
12
ε_0

Tetryonic Matter of Electron - 8.851486361 x 10^{-31} Kg
mass-Energy of Electron - 7.955319207x 10^{-14} J

EM Field Planck quanta

$$12\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Fermions ElectroMagnetic mass velocity


0
[18-18]
N°
P+
36n
N0
22,500
22,500
12
[24-12]
P+

Tetryonic Matter of Proton - 1.659653693 x 10^{-27} Kg
mass-Energy of Proton - 1.491622351 x 10^{-10} J

EM Field Planck quanta

$$36\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Baryons ElectroMagnetic mass velocity


ELEMENTS
0
[42-42]
D
n0
$36n^2$
$12n^2$
$36n^2$
84n
45,012

Tetryonic Matter of Deuterium - 3.320192534 x 10^{-27} Kg
mass-Energy of Deuterium - 2.984040234 x 10^{-10} J

EM Field Planck quanta

$$84\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Deuterons ElectroMagnetic mass velocity

Tetryonics 15.08 - mass-Energy-Matter equivalence

Copyright ABRAHAM [2008] - all rights reserved

EM mass quanta in Matter


kg
ε_0
m
7.376238634 e-31 kg
c^2
q
KG
ε_0
m
1.475247727 e-50 kg
c^2
f
mass
1
¼ M
½ M
v
ε_0
M
v
v^2
c^4
ODDπ
EVENπ
3 m
4 m
4
Matter
Q
ε_0
m
2.2287159 e-50 kg
c^2
M
ε_0
m
2.95049545 e-50 kg
c^2

EM Field · Planck · quanta

$$n\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

mass · ElectroMagnetic · mass · velocity

EM Field · Planck · quanta

$$\mathrm{ODD}\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Bosons · ElectroMagnetic · mass · velocity

EM Field · Planck · quanta

$$\mathrm{EVEN}\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

EM waves · ElectroMagnetic · mass · velocity

EM Field · Planck · quanta

$$4n\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Matter · ElectroMagnetic · mass · velocity

Tetryonics 15.09 - EM mass quanta in Matter

Copyright ABRAHAM [2008] - all rights reserved



Lorentz velocity corrections

[result from the measurement of EM mass-energy quanta in a planar spatial co-ordinate system]

$$\beta = m\left[\frac{v}{c}\right]$$

[Linear momentum corrections are linear]

$$\beta^2 = m\left[\frac{v^2}{c^2}\right]$$

[EM mass-Energy corrections are Scalar]

$$m \qquad \frac{E}{c^2} = \frac{\overset{\text{Energy}}{\left[\underset{\text{mass}}{m}\,\underset{\text{quanta}}{\Omega}\,v^2\right]}}{\underset{\text{EM Field}}{c^2}} = \underset{\text{mass}}{n\pi}\left[\underset{\text{ElectroMagnetic}}{[\varepsilon_0\mu_0]}.\left[\overset{\text{planck}}{\underset{\text{mass}}{m}}\,\overset{\text{quanta}}{\Omega}\,\underset{\text{velocity}}{v^2}\right]\right] \qquad \left[\frac{1}{c^2}\right]E$$

$$p \qquad mv = \left[\frac{E}{v^2}\right].v = \underset{\text{linear momentum}}{n\pi}\left[\overset{\text{EM Field}}{\underset{\text{ElectroMagnetic}}{[\varepsilon_0\mu_0]}}.\overset{\text{Planck quanta}}{[\underset{\text{mass}}{m}\,\underset{\text{velocity}}{v}]}\right] \qquad \frac{E}{v}$$

$$E \qquad mv^2 = \frac{mv^2}{\underset{\text{EM Field}}{c^2}} = \underset{\text{Matter}}{4n\pi}\left[\overset{\text{EM Field}}{\underset{\text{ElectroMagnetic}}{[\varepsilon_0\mu_0]}}.\overset{\text{Energy}}{[\underset{\text{mass}}{m}\,\underset{\text{velocity}}{c^2}]}\right] \qquad m\left[\frac{c^2}{c^2}\right]$$

mass-energy in Matter propagates at c

$$KE \qquad 1/2\,Mv^2 = 1/2\left[4\left[\frac{\overset{\text{Energy}}{\left[\underset{\text{mass}}{m}\,\underset{\text{quanta}}{\Omega}\,v^2\right]}}{\underset{\text{EM Field}}{c^2}}\right]\right] = \underset{\text{Photons}}{2\pi}\left[\underset{\text{ElectroMagnetic}}{[\varepsilon_0\mu_0]}.\left[\overset{\text{planck}}{\underset{\text{mass}}{m}}\,\overset{\text{quanta}}{\Omega}\,\underset{\text{velocity}}{v^2}\right]\right] \qquad 2m\left[\frac{v^2}{c^2}\right]$$

Tetryonics 15.10 - Lorentz velocity corrections

The geometry of Constants

Quantised angular momentum is the source of all physical Constants


R_H
c
Q
k
Q
ε_0
μ_0
c^4


v
1
4
9
Ω
6
25
36
hv
v²
c
c²


h
v²
M
G
M
n
π
c^4

A physical constant is a physical quantity that is generally believed to be both universal in nature and constant in time.

It can be contrasted with a mathematical constant, which is a fixed numerical value but does not directly involve any physical measurement







Copyright ABRAHAM [2008] - all rights reserved


q
[1-0]
E
ε_0
m
N
S
hv
7.376238634 e-51 kg

"To interpret the vibrational energy of N oscillators not as a continuous, infinitely divisible quantity, but as a discrete quantity composed of an integral number of finite equal parts.

Max Planck



(April 23, 1858 – October 4, 1947)

$$\varepsilon = nh\nu$$

"Let us call each such part of the energy element h "


q
[0-1]
E
ε_0
m
S
N
hv
7.376238634 e-51 kg

Planck's Constant

[quantised mass-energy angular momenta]

N_A

1 mole of Hydrogen atoms has a rest-mass of 1 gram

Solving for Planck's Constant using the inverse of Avogadros number & Tetryonic geometry we obtain an exact corrected value of :

$$\pm\ 6.629432672 \times 10^{-34}\ \mathrm{J.s}$$

$$4.137664546 \times 10^{-15}\ \mathrm{eV.s}$$

$$mv^2 = E = hv^2$$

A rest mass Hydrogen atom has a Compton frequency of 2.2512 e23 Planck quanta


0
[24-24]
e-
P+
2.2512 e23
Hydrogen


v
ε_0
m
hv
v^2
All Matter waveforms can be collapsed into radiant mass-energies
c^2


EM Field
Planck
quanta
$T\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$
Matter
ElectroMagnetic
mass
velocity

Planck's constant is the relationship between EM mass-energy and quantised angular momenta that provides the basis for EM charge in Tetryonic geometries

Copyright ABRAHAM [2008] - all rights reserved

Amedeo Avogadro

(9 August 1776 – 9 July 1856)

Avogadro's Number

The number of rest mass Hydrogen atoms in 1 gram (and the rest molar mass of any element or compound) can be determined directly from tetryonic theory

[exclusive of any measurement, blackbody or kinetic energies]

Using a Compton frequency of 2.2512 e23 Planck quanta for a rest mass-Matter Hydrogen atom

atomic mass unit

$$1\ \text{u} = \frac{M_\text{u}}{N_\text{A}} = 1.660\,538\,782(83)\times 10^{-24}\ \text{g}$$

Avogadro N = 6.022141579 x 10^{23}

$$N^{-1} = \frac{2.2512\ \text{e}23\ \text{v}}{\overset{\text{[Hydrogen mass]}}{1.660538841\times 10^{-24}\ \text{g}}}$$



n0 *1 mol = 1 g*

Hydrogen = 1.660538841 x 10^{-27} Kg

n1 *1 mol = 1.000533 g*

n0 *1 mol = 11.996801 g*

Carbon 12 = 1.99211552 x 10^{-26} Kg

n1 *1 mol = 12 g*

Hydrogen's rest Tetryonic mass is 22,512 n Planck quanta [Proton - 22,500n + electron 12n]

$$\left[22{,}512\left[\underset{\text{ElectroMagnetic}}{\overset{\text{EM Field}}{[\varepsilon_0\mu_0]}}.\overset{\text{Planck}\quad\text{quanta}}{\left[\underset{\text{mass}}{m}\,\Omega\,\underset{\text{velocity}}{v^{2}}\right]}\right]\right]^{-1}$$

The inverse mass of Hydrogen is equal to Avogadro's number

Coulomb's Constant

$$k = \frac{1}{4\pi\varepsilon_0}$$

The proportionality constant ke, called the Coulomb constant (sometimes called the Coulomb force constant), is related to defined properties of EM Energy-momenta and is used to define Electric field forces

$$c = \frac{1}{\sqrt{\mu_0\varepsilon_0}}$$

$$8.987\text{ e}9\ \frac{\text{Nm}^2}{\text{C}^2}$$

$$\varepsilon_0 = \frac{1}{\mu_0 c^2}$$


[0-12]
Same charge repulsion field
[0-12]


μ0
μ0
Q
k
Q
ε0
ε0

$$\mu_0 = \frac{1}{\epsilon_0 c^2}$$


[12-0]
Same charge repulsion field
[12-0]

Similars repel

Opposites attract

Similars repel

Linear Coulombic force interactions are a result of charged E field linear momenta

$$\mathbf{E} = \frac{\mathbf{F}}{q_t}$$

The Electric field can be defined as the longitudinal Force exerted by charged masses


[12-0]
Couloumbic Interaction field
[0-12]

It is a measure of the interactive force produced by the Electric field energy-momenta of two superpositioned charge KEM fields

Longitudinal E field forces between Charged particles are mediated by Photons

$$\mathbf{E} = \frac{1}{4\pi\varepsilon_0}\frac{Q}{r^2}\hat{\mathbf{r}}$$

The Electric field can also be derived from Coulomb's Law

Copyright ABRAHAM [2008] - all rights reserved

The Speed of ElectroMagnetic energies

The classical behaviour of the electromagnetic field is described by Maxwell's equations, which predict that the speed c with which electromagnetic waves (such as light) propagate through the vacuum is related to the electric constant ε_0 and the magnetic constant μ_0 by the equation $c = 1/\sqrt{\varepsilon_0\mu_0}$.

c

Celeritas is a Latin word for "swiftness" or "speed". It is often given as the origin of the symbol c, the universal notation for the speed of light in a vacuum



The distance energy travels in 1 second from its source

EM waves and energy momenta can be measured as either Transverse or Longitudinal waveforms with respect to their velocity vector

All EM waves and energy are symmetrical waveforms whose quanta contain ElectroMagnetic mass-energy and momenta



The equilateral geometry of EM energy is the inverse of the spatial geometry of 1 second

The square root of equilateral energies [scalar speed] is a vector velocity

velocity is a vector direction of the energies of motion

speed is a scalar property of the energies of motion

The maximum velocity possible due to electrical accelerations or the impedance of any spatial region that energy propagates through it is often referenced in physics as 'the speed of Light' IT IS NOT AN ABSOLUTE LIMIT or BARRIER

All EM waves radiate outwards in accord with Biot-Savart's law

C^2

The velocity vectors of EM energies form the geometries of spatial co-ordinate systems

The speed of EM energies in a vacuum is defined as 299,792,458 meters per second (1,079,252,848.8 km/h).

$$\frac{K_E}{K_M} = 9e16 \, \frac{\frac{N\,m^2}{c^2}}{\frac{N\,s^2}{c^2}}$$

$$C^2 = 9e16 \, \frac{m^2}{s^2}$$

$$c = 299{,}792{,}458 \, \frac{m}{s}$$

The natural velocity of EM energies can be calculated from the field's EM permittivity & permeability and is affected by the medium it is propagating through

EM waveforms are bidirectional radiant emissions of 2D energy



with velocity [Lorentz] variable energy contents

Copyright ABRAHAM [2008] - all rights reserved

Quantum masses

$$h\nu^2 = E = m\nu^2$$

$$kg\,\frac{m^2}{s}\,\frac{1}{s} \qquad kg\,\frac{m^2}{s^2} \qquad kg\,\frac{m^2}{s^2}$$

The quantum of mass-energy can be derived with several methodolgies using Tetryonic Geometry

mass quanta



EM mass-energy quanta

Matter is a KEM standing wave propagating at c

EM Field planck quanta

$$[\varepsilon_0\mu_0]\,[m\Omega v^2]$$

mass velocity

1.112650056 e-17 s2 m-2

6.629432672 e-34 kg m2 s-2

Permittivity x Energy density

$$\frac{E}{c^2} = m$$



mass = 7.376238634 x 10^{-51} Kg

Planck-Einstein

Planck mass-energy geometries

quantised energy momenta

h

$$kg\,\frac{m^2}{s}$$

6.629432672 e-34 J

Planck quanta

$$[m\Omega v^2]$$

mass velocity

7.376238634 e-51 kg

$$kg\,\frac{m^2}{s^2}$$

m

scalar mass-energy

Charged mass-Matter topologies

The mass Tπ *of Matter*

EM Field Planck quanta

$$T\pi\,[[\varepsilon_0\mu_0].[m\Omega v^2]]$$

ElectroMagnetic mass velocity

Matter Quanta

Tetryonic molar mass [Hydrogen] - 1 g



$$\text{Molar mass} = \frac{H_1\text{ Atomic mass}}{\text{Avagadro's No.}}$$

$$\text{mass } H_{mol}/Av = \frac{.001}{6.022141579 \times 10^{23}}$$

$$= 1.660538841 \times 10^{-27}\ \text{g/mol}$$

$$H_{mole}\,/\,\boxed{m}\,[H] = \frac{1.660538841 \times 10^{-27}}{22{,}512}$$

mass = 7.376238634 x 10^{-32} KG

Avogadro - Mandeleev

Copyright ABRAHAM [2008] - all rights reserved

2D mass-Energy equivalence

'The Speed of Light' is the Natural velocity of Energy propagation

Energy

$$mv^2 = hv^2$$

EM mass

$$\frac{mv^2}{c^2}$$

$$\frac{mv^2}{h}$$

$$\frac{c^2}{v^2}$$

8.987551787 e16


E_0
h
v^2
Ω
n_0
m
v^2
equilateral quanta
$1/c^2$

1.112650056 e-17

$$\frac{m}{h}$$

$$\frac{hv^2}{c^2}$$

$$\frac{hv^2}{m}$$

$$\frac{m}{hv^2}$$

Photons

Matter

Tetryonics 16.07 - 2D mass-Energy equivalence

Copyright ABRAHAM [2008] - all rights reserved

Zero Point Fields

EM Field Planck quanta

$n\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$

Quanta ElectroMagnetic mass velocity



mass-energy

m=1π

radiant 4π mass-energy geometries



in standing wave topologies
are 3D MATTER quanta

Photons

EM Field Planck quanta

$2n\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$

Photons ElectroMagnetic mass velocity



m=2π

EM energy carriers

[1, 2, 3, 4, 5, 6, 7, 8, 9,10......]

[2D EM masses are planar energy momenta]

[2, 8,18, 32, 50, 72, 98,128......]

The geometry of mass and Matter

[1, 3, 5, 7, 9, 11, 13,15, 17, 19........]

[3D Matter has mass-energy momenta and volume]

[4, 8,12, 24, 36, 48, 72, 84, 168......]

Charge Carriers



m=3π



m=4π



EM Field Planck quanta

$ODDn\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$

Bosons ElectroMagnetic mass velocity

Bosons

3D Matter topologies are standing waves of
2D mass-energies propagating at c

EM Field Planck quanta

$4n\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$

Matter ElectroMagnetic mass velocity

mass-Matter

Tetryonics 17.01 - The geometry of mass and Matter

mass geometries & rest Matter topology

2D

m

mass

kg


v
ε0
m
hv
v²
mass-energy
c²

M

Matter

KG

3D

Quanta number

1e19 v

Compton frequency

Matter is a three dimensional charged mass-energy topology

EM Field Planck quanta

$$M = 4n\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Matter ElectroMagnetic mass velocity

Energy density is mass - the term 'massless particle' is a misnomer

Quantum number

n

Nuclear Level


v
ε0
m
ω
hv
v²
2D 4π masses form KEM fields
c²

Kinetic Energies

RE = Matter + KE

Relativistic mass is the total EM energy content of a massive body (or system) in motion

The relativistic rest mass-energies of Matter are velocity invariant as 3D Matter is a EM standing wave with 2D mass- energy fascia whose velocity of propagation is the speed of Light


M
hv
v²
3D 4π tetrahedral shape masses form Matter
c⁴

Matter

Copyright ABRAHAM [2008] - all rights reserved

Charge topologies and rest mass-energies

mass-Matter topologies

mass-energy geometries

12
[0-12]



1.2 e20

Electron

n=0
Q

0.00000053 g
molar mass

Tm Electron = 12n

electron Charge	$-1.602216081 \times 10^{-19}$ C
electron rest mass	$8.851486361 \times 10^{-31}$ kg
electron rest energy	$7.955319207 \times 10^{-14}$ J 496,519.7 eV [.496519 MeV]

Proton

12
[24-12]



2.25 e23

Q
n=25²

0.000999 g
molar mass

Tm Proton = 22,500n

Proton Charge	$+1.602216081 \times 10^{-19}$ C
Proton rest mass	$1.659653693 \times 10^{-27}$ kg
Proton rest energy	$1.491622351 \times 10^{-10}$ J 930,974,522.8 eV [930.9 MeV]

Protons and Neutrons have identical masses to each other and equivalent topologies but differing charges

0
[18-18]



2.25 e23

Neutron

Q
n=25²

0.000999 g
molar mass

Tm Neutron = 22,500n

Neutron Charge	0
Neutron rest mass	$1.659653693 \times 10^{-27}$ kg
Neutron rest energy	$1.491622351 \times 10^{-10}$ J 930,974,522.8 eV [930.9 MeV]

Hydrogen

When Protons and electrons interact to form neutral Hydrogen the electron's KEM quantum field energies increase in direct proportion to the Proton's energy levels

0
[24-24]



2.2512 e23

n=0
Q
n=25²

1.000533 g
molar mass

Tm Hydrogen = 22,512n

Hydrogen = Proton + electron

H Charge	0
H rest mass	$1.660538841 \times 10^{-27}$ kg
H rest energy	$1.492417883 \times 10^{-10}$ J 931,967,562.3 eV [931.9MeV]

0
[42-42]



4.5012 e23

quantum synchronous converters

n=0
Q
n=25²

1.999466 g
molar mass

Tm Deuterium = 22,512n

Hydrogen = Proton + electron

H Charge	0
H rest mass	$3.320192534 \times 10^{-27}$ kg
H rest energy	$2.984040234 \times 10^{-10}$ J 1,862,445,565 eV [1,862MeV]

Tetryonics 17.03 - Charge topologies and rest mass-energies

In order to make an exact 1kg reference mass-Matter topology


c
ε0
1kg
hv
v²
Collapsed Matter standing waveforms
form radiant mass-energies
c²

mass

Planck quanta

$$\frac{n\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

mass-energy

Energy per second

$$\boxed{mc^2 = E = hv^2}$$

$$m = E/c^2$$

mass is the scalar integral surface area of Matter topologies



which is equivalent to exactly 1,000 molar Hydrogen masses


0
[24-24]
1,000 N_A
1.00000
H°
2.2512e23

whose Tetryonic Matter topology can be modelled using charged Planck mass-energy geometries

grams per kg

6.629432672 e-34 J

Energy

$$M = 1{,}000 \times N_A.\, T\pi\left[\left[m\Omega v^2\right]\right]$$

1kg

6.022141579 e23
Avogadro's number

revealing that there are exactly

1.355704512 e50

Planck quanta in standing wave Matter


0
6.629432672 e-34 J.s
Planck Constant
1.355704512 e50
Planck quanta
E
m
hv
v²
8.987551787 e16 J
Energy
c⁴

Matter

Planck quanta

$$\frac{T\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

Matter-energy

Energy per second squared

$$\boxed{hv^2 = E = Mc^4}$$

$$M = E/c^4$$

Matter topologies are standing-waves of mass-energy

you need to create a standing-EM wave with a specific compton frequency

Copyright ABRAHAM [2008] - all rights reserved

EM mass and Matter defined

There remains a lot of confusion over the exact definition of EM mass and Matter resulting in the frequent interchanging of one term for the other in physical processes

This must be clarified and the two terms must be properly defined in a manner that explains their derivation and physical properties in detail.



$$m = \frac{E}{c^2}$$

EM mass

3D Matter is comprised of 2D mass-energies
2D mass-energy cannot contain 3D Matter

Matter

$$M = \frac{4\pi E}{c^4}$$



$$n\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

EM Field Planck quanta
mass ElectroMagnetic mass velocity



$$n\pi\left[\left[m\Omega v^2\right]\right]$$

Planck quanta
Energy mass velocity

2D mass-Energies

EM mass is a measure of equilateral scalar energy per unit of Time

$$\beta = \left[\frac{v}{c}\right]$$

mass is the Lorentzian velocity corrected energy content of Tetryonic geometries

All forms of EM mass-Energy are subject to Lorentz factor relationships

$$\beta^2 = \left[\frac{v}{c}\right]^2$$

Matter is Lorentz invariant as its mass-energies propagate in a 4π standing wave geometry

Bosons and Photons are not 'massless' they are 'Matterless' [2D waveforms]

Bosons

$$m_p = \frac{hv}{c^2}$$

Planck masses



Photons

$$m_\gamma = \frac{hf}{c^2}$$

Photon mass

$$\text{ODD}\,\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

EM Field Planck quanta
Bosons ElectroMagnetic mass velocity

$$\text{EVEN}\,\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

EM Field Planck quanta
EM waves ElectroMagnetic mass velocity

$$4n\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

EM Field Planck quanta
Matter ElectroMagnetic mass velocity



$$84\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

EM Field Planck quanta
Deuterium ElectroMagnetic mass velocity

Matter is the 3D topology of standing wave 2D mass-energies



$$12\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]\ e^-$$

EM Field Planck quanta
electrons

+

$$72\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Deuteron
Nuclei ElectroMagnetic mass velocity



Copyright ABRAHAM [2008] - all rights reserved

Charged mass-Matter geometries



Differing nett Charges

$T = 12\pi$

Same Tetryonic Number
Same topology

Matter Topology is determined by the geometry of charged Planck T[q] quanta

Any measurement of a system's mass is subject to velocity corrections

mass = EM energy density

Planck quanta

$$\frac{n\pi\,[m\Omega v^2]}{c^2}$$

mass quanta — mass — velocity — Spatial geometry

n [7.376238634 e-51] kg

EM mass is a measure of 2D planar energies comprising the fascia of charged topologies

ENERGY

Planck quanta

m $\quad n\pi[[m\Omega v^2]]\quad$ **M**

mass — velocity

c^2
2D space

The mass - ENERGY - Matter contents of any physical system are all related through the spatial co-ordinate system used [which in turn is determined by the speed of light]

c^4
3D space

mass

$$\frac{n\pi}{c^2}[[m\Omega v^2]]$$

E

Matter

$$\frac{T\pi}{c^4}[[m\Omega v^2]]$$

The Energy content of any physical system remains the same irrespective of the spatial co-ordinates used

Matter and Charge are velocity invariant properties

Differing Tetryonic charge numbers produce differing particle topologies



Photons
$$\frac{2\pi}{c^2}[[m\Omega v^2]]$$

$$\frac{12\pi}{c^4}[[m\Omega v^2]]$$

Baryons
$$\frac{36\pi}{c^4}[[m\Omega v^2]]$$

As the energy content [levels] of particles and fields increase their intrinsic Planck quanta and EM mass increases but their charge geometries remain the same

Charged mass-Energies

All 3D Matter particles are comprised of charged fascia whose energy content determines their 2D mass


1
ZPFs
4
Tetryons
Quarks
12
Dodecadeltahedrons
e+
e-
Leptons
N0
36
Baryons
P+


4
[4-0]
4
Positive Tetryon
0
[2-2]
4
0
[2-2]
4
Neutral Tetryon
4
[0-4]
4
Negative Tetryon
8
[10-2]
7.5e22
up quark
4
[4-8]
7.5e22
down quark
12
[12-0]
e+
1.2e20
Positron
0
[6-6]
12
Neutrino
0
[6-6]
12
12
[0-12]
e-
1.2e20
Electron
0
[18-18]
2.25e23
N0
Neutron
12
[24-12]
2.25e23
P+
Proton

3D Matter geometries

Matter Planck quanta

$$\frac{T\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

Tetryons
4 charge fascia

4π $2.651773069 \times 10^{-33}$ J
$2.950495454 \times 10^{-50}$ kg
4 quanta

Quarks
12 charge fascia

12π $4.97207450 \times 10^{-11}$ J
$5.532178976 \times 10^{-28}$ kg
7.5×10^{22} quanta

Neutrinos
12 charge fascia

12π $7.955319207 \times 10^{-33}$ J
$8.851486361 \times 10^{-50}$ kg
12 quanta

Leptons
12 charge fascia

12π $7.955319207 \times 10^{-14}$ J
$8.851486361 \times 10^{-31}$ kg
1.2×10^{20} quanta

Baryons
36 charge fascia

36π $1.491622351 \times 10^{-10}$ J
$1.659653693 \times 10^{-27}$ kg
2.250×10^{23} quanta

Deuterium
72 charge fascia
ion

72π $2.984040234 \times 10^{-10}$ J
$3.320192534 \times 10^{-27}$ kg
4.5012×10^{23} quanta


q
[v-v]
v
E
h
hv
N
S
v
inertial mass-energy quanta

In physics there exists
2 forms of energy momenta
[linear momenta &
quantised angular]

MOMENTA



The nett scalar
energy momenta
required to effect
changes in velocity

ENERGY


v
q
[v-v]
E
h
hv
S
N
v
inertial mass-energy quanta

Net Charge is reflective of the total energy momenta
of any EM field or Matter subjected to acceleration
[inertial mass]


v
1
3
5
7
9
1²
2²
3²
4²
5²
p
ε0
m
hv
v²
F
S

Inertial resistance to Force

Any change in motion results in changes to
the Charge geometries creating in turn proportional
changes to the nett KEM mass-energy momenta components

$$F=ma$$

The inductive resistance of quanta in charged EM fields
to any changes to their nett mass-energy geometry
is the source ofwhat we term inertial mass


v
1
3
5
7
9
11
13
1²
2²
3²
4²
5²
6²
7²
p
ε0
m
hv
v²
F
S

**Inertia is the resistance of any physical object
to a change in its state of motion.**

Force does work when it results in movement

$$\boxed{W = F.d = ma.d = E}$$

$$kg\,\frac{m}{s^2}\,m$$

classical mechanics

quantum mechanics

$$\Delta mv = \overset{\text{scalar}}{\underset{\text{energies}}{\Delta E}} = \Delta m\Omega v$$

linear momenta

angular momenta

$$kg\,\frac{m^2}{s^2}$$

The Planck constant is the quantum of Action

$$\boxed{E = m\Omega v^2 = h\nu^2}$$

$$kg\,\frac{m^2}{s}\,\frac{1}{s}$$

Changing an object's velocity results in a corresponding energy momenta change which relate to each other through its inertial mass

Tetryonics 17.08 - Inertial resistance to Force

EM field densities



EM mass is a measure of the energy content of any spatial co-ordinate system

$$\beta^2 = \left[\frac{v}{c}\right]^2$$

and is subject to Lorentz velocity corrections in 2D EM fields

6.629432672 e-34 J
1 planck quantum has a
EM mass-Energy of
7.376238634 e-51 kg
and
Quantised Angular Momentum
which creates Charge
1.33518 e-20 C

mass-Energy equivalence

mass velocity



7.376238634 e-51 kg

6.629432672e-34 j.s

$$mv^2 = E = hv^2$$

8.987551787 e16 [m/s]²

6.629432672 e-34 j

quanta/sec

Matter is only mass-energy in Tetrahedral topologies [T4π+]
[else it is nπ EM mass-energies that propagate away at c]



planck quanta

6.629432672 e-34 J



7.376238634 e-51 kg
radiant mass-energies

If reduced to a flat Euclidean space geometry
Matter topologies become radiant mass-energies

m
mass

$$\left[\frac{n\pi}{c^2}\rho\right]$$

E
ENERGY

Planck quanta

$$\left[m\Omega v^2\right]$$

mass velocity

M
Matter

$$\left[\frac{4n\pi}{c^4}\rho\right]$$

The inertial properties of electromagnetic mass - ENERGY & Matter
[can all be differentiated as energy densities per unit of time]
in any spatial co-ordinate system

2.984040234 e-10 J



3.320192534 e-27 kg
rest mass-Matter

m

[oddπ]hv



EM Field Planck quanta

$$1\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Charge ElectroMagnetic mass velocity

Bosons

2D

Photons

m

[evenπ]hv



EM Field Planck quanta

$$2\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Photons ElectroMagnetic mass velocity

EM Field geometries & Matter topologies

M

[4nπ]hv



EM Field Planck quanta

$$12\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Dodecyon ElectroMagnetic mass velocity

Leptons

3D

Baryons

M

[4nπ]hv



EM Field Planck quanta

$$36\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Baryons ElectroMagnetic mass velocity

2D planar Euclidean electromagnetic mass-energies propagate through the vacuum energy aether without interaction

EM Field Planck quanta

$$n\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

mass ElectroMagnetic mass velocity

2D Fields

3D Matter



Tetryonic charged geometries provides a clear mechanism for providing all particles with their distinct properties of 2D inertial EM mass-energy and 3D Matter.

EM Field Planck quanta

$$T\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Matter ElectroMagnetic mass velocity

3D standing wave topologies of electromagnetic mass-energies interact with the vacuum energy aether at various angles through their charged [inductive] fascia

Tetryonics 17.10 - EM Field geometries and Matter topologies

Copyright ABRAHAM [2008] - all rights reserved

Velocity invariant rest Matter

The Relativistic EM mass-energies of a system in motion is the sum of its invariant rest Matter and Kinetic Energies

Electrostatic charges have no Magnetic Moments


12
[0-12]
1.2 e20
rest Matter
0
KE
c⁴

All Matter are 3D standing wave topologies

$$M = \frac{E}{c^4}$$



$E = Mc^4$

rest mass-Matter is composed of 4nπ standing wave topologies and is INVARIANT to velociy changes

Electron rest Matter

Kinetic Energy field

$$RE = \underset{\text{Fermions}}{12\pi}\left[\left[\frac{m\Omega v^2}{c^4}\right]\right] + \underset{\text{Photons}}{2\pi}\left[\left[\frac{m\Omega v^2}{c^2}\right]\right]$$

EM fields resulting from motion are subject to Lorentz correction

Kinetic mass-energies are divergent from invariant rest Matter topologies as a result of a particle's motion

At zero velocity the relativistic mass is equal to the invariant mass.


hv
Q
12
[0-12]
c⁴
1.2 e20
M
v²
S
N
KE
v
RE
1.20003268 e20
[1.2 e20+3.268 e15]
KE
3.268 e15

The energy which an object has due to its motion will not add mass into the invariant rest Matter of the particle in motion (it increases the total Planck quanta [EM mass-enegies] of its extended KEM field)

Wavelengths are proportional to EM energy content


0
[v/v]
RE
c
c
KE
KE
Magnetic moment
0
rest Matter
3.268e15
KE
hf
c²

Photons are bidirectional Kinetic EM Fields

$$\frac{E}{c^2} = m$$

Matter in motion has a resultant velocity related Energy field that posseses the physical properties of Kinetic energy and Magnetic moments

$KEM = Mv^2$

KEM field Energy is directly relaıed to the Velocity changes of massive particles

Tetryonics 17.11 - Velocity invariant rest Matter

mass geometries and Matter Topologies

All 2D EM fields and 3D Matter particles have ElectroMagnetic fields, inertial mass-energies & momenta resulting from their constituent equilateral Planck quanta which possess the additional physical properties of Compton Frequency and De Broglie Wavelength



EM mass is a measure of the inertial energy density of any 2D [EM field] or 3D [Matter] energy geometry

$$m\Omega v^2 = E = mv^2$$

EM mass-energy momenta

The EM mass of an object is a fundamental property of the object; a numerical measure of its inertia; a fundamental measure of the energy density of an object.

All 3D Matter topologies contain 2D EM mass-energy geometries
not all 2D EM mass-energy geometries form 3D Matter topologies

EM mass can be clearly defined as a measure of the energy density of any charged geometry

$$\underset{\text{Matter}}{T\pi}\left[\overset{\text{EM Field}}{\left[\varepsilon_0\mu_0\right]}.\left[m\overset{\text{Planck quanta}}{\Omega}v^2\right]\right]$$

ElectroMagnetic mass velocity

3D Matter is any mass-energy geometry that creates a closed volume Topology (4nπ Tetryonic geometry)

ε_0
m
c²

EM waves [FIELDS] are distinguishable from Material Particles [MATTER] through their non-Tetrahedral topologies

$$\frac{E}{c^2} = m$$



mass-energy is a conserved property
Matter is not conservative

$$M = \frac{E}{c^4}$$

The term 'massless' is a misnomer and should be discontinued in its use as all EM fields and Particles have EM mass [Energy quanta per second] geometries [other alternatives could be 2D, EM field, or Matterless]



$$\frac{E}{c^2} = m$$

$$M = \frac{E}{c^4}$$

[7.376238634 e-51 kg]

[6.629432672 e-34 kg.m²/s²]

[2.95049545 e-50 kg]

EM mass

ENERGY

All attempts to clearly differentiate between planar EM mass-energy & 3D Matter in physics have met with limited success until the introduction of charged geometries

Collapsed Matter

mv mass-velocity squared is Energy

$n\pi$

Planck quanta is Energy content $m\Omega$

mass-ENERGY-Matter equivalence

Newton and Leibniz measured Energy as a velocity related function of mass

Planck and Einstein viewed mass-energies as quantised particles with momenta

Energy momenta

$$mv^2 = E = hv^2$$

EM masses are subject to velocity related Lorentz corrections

Matter is a standing-wave of electromagentic energies and is Lorentz invariant

EM mass quantum

$$\frac{n\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

$$n\pi\left[\left[m\Omega v^2\right]\right]$$

Matter quantum

$$\frac{T\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

Tetryonics 17.13 - EM mass-Energy-Matter equivalence

Copyright ABRAHAM [2008] - all rights reserved

m

mass geometries

mass Planck quanta

$$\frac{n\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

All forms of mass-ENERGY-Matter
are defined by their charged geometries and
the spatial co-ordinate systems used to measure their physics

Unified Field Equation

for Tetryonic EM mass-Energy-Matter

M

Matter topologies

Matter Planck quanta

$$\frac{T\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

Tetryonic EM Field Planck quanta

$$T\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

geometry ElectroMagnetic mass velocity

EM Field Planck quanta

$$n\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

mass ElectroMagnetic mass velocity

EM Field Planck quanta

$$\mathrm{ODD}\,\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Bosons ElectroMagnetic mass velocity

EM Field Planck quanta

$$2\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Photons ElectroMagnetic mass velocity

EM Field Planck quanta

$$\mathrm{EVEN}\,\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

EM waves ElectroMagnetic mass velocity

bosons & photons

nπ

EM waves forms



spatial co-ordinate systems
are defined by the velocity of energy

Fermions

Tπ

Particles

EM Field Planck quanta

$$4\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Tetryons ElectroMagnetic mass velocity

EM Field Planck quanta

$$12\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Dodecyons ElectroMagnetic mass velocity

EM Field Planck quanta

$$24\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Mesons ElectroMagnetic mass velocity

EM Field Planck quanta

$$36\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Baryons ElectroMagnetic mass velocity

Tetryonics 17.14 - Unified Field Equation

Copyright ABRAHAM [2008] - all rights reserved

EM mass

Matter



m

M

mass

Planck quanta

$$\frac{n\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

Planck quanta

$$n\pi\left[m\Omega v\right]^2$$

energy mass velocity

Matter

Planck quanta

$$\frac{T\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

Classical Mechanics

Quantum Mechanics

Tetryonic unified field Geometry

p

mass velocity

7.376238634 e-51 kg

6.629432672e-34 j.s

$$mv^2 = E = hv^2$$

8.987551787 e16 [m/s]^2 6.629432672 e-34 j quanta/sec

mass-Energy momenta equivalence

planck quanta

h

The equilateral geometry of quantised angular momentum is the key to understanding Energy

$$kg\,\frac{m}{s}$$

$$mv$$

linear momentum

charge

$$m\Omega$$

$$kg\,\frac{m^2}{s}$$

quantised angular momentum

Tetryonics 17.15 - Unified field geometries

$kg\frac{m^2}{s}\frac{1}{s}$

Planck quanta

$[m\Omega v^2]$

mass velocity

$kg\frac{m^2}{s^2}$

m

EM Field Planck quanta

$n\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$

mass ElectroMagnetic mass velocity

kg

ElectroMagnetic field

$[\varepsilon_0\mu_0]$ $\frac{s^2}{m^2}$

$\frac{1}{c^2}$

E

Energy

Classical Field Theory


v
Quantised Angular momentum
p
vector Linear momentum
ε0
Transverse Bosons
Squared Energies
nπ
[[ε0μ0].[mΩv²]]
hv
v²
Longitudinal Photons
c²

All energy in c squared spatial co-ordinates are defined as EM mass equivalents

Quantum Field Theory

$\frac{s^2}{m^2}$ $\frac{m}{s^2}$

Q

Charge

Charge

$\frac{[\varepsilon_0\mu_0\Omega]}{s}$

ElectroMagnetic QAM

h

$[m\Omega]$

mass QAM

$kg\frac{m^2}{s}$

Unified Field Components

The Unified field equation can be re-arranged to reveal a multitude of physical properties and relationships previously poorly understood.

Highlighting the fact that all of the constants and properties of both Classical and Quantum Mechanics are in fact geometric properties of Energy

QAM

$\frac{m^2}{s}$ Ω

v^2

velocity squared

Velocity - quanta

v^2

quanta/sec

Tetryonics 17.16 - UFE components

EM mass Relationships

v	Velocity	$\frac{m}{s}$
a	Acceleration	$\frac{m}{s^2}$

m

p	Momentum	$kg\frac{m}{s}$
F	Force	$kg\frac{m}{s^2}$


v
E
m
hv
v²
mass angular momenta
per second
c²

$kg\ \frac{m^2}{s}\ \frac{1}{s}$

EM mass is revealed to be the scalar property of 2D Energy waveforms that is at the core of many important physical processes and measurements

Ω	Quantum Angular Momentum	$\frac{m^2}{s}$
v^2	Celeritas squared	$\frac{m^2}{s^2}$

m

h	Planck's Constant	$kg\frac{m^2}{s}$
E	Energy	$kg\frac{m^2}{s^2}$

E/second


ε0
m
kg
EM mass
c²

f	Frequency	$\frac{1}{s}$
T	Period	s

m

I	Current	$\frac{kg}{s}$
C	Charge	$\frac{s}{kg}$

E/second²


ε0
M
μ0
KG
Matter
c⁴

2D mass geometries should never be confused with 3D Matter topoplogies; nor should the terms be used in exchange for each other

Tetryonics 17.17 - EM mass relationships



Relativistic mass-Matter

Rest Matter

$$T\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

mass-Matter

3D rest mass-Matter topolgy = closed volume of 2D mass-energies

3D Electrostatic particle No Magnetic Moment

rest mass of a particle is dependent on its Energy level

All Matter is a Tetryonic standing-wave charged geometry occupying a volume in 3D spherical space

Matter

$$\frac{T\pi}{c^4}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\overset{\text{quanta}}{\underset{\text{velocity}}{v^2}}\right]\right]$$

$$\downarrow$$

Dodecyon

$$\frac{12\pi}{c^4}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\overset{\text{quanta}}{\underset{\text{velocity}}{v^2}}\right]\right]$$

rest mass-Matter is velocity invariant (not subject to Lorentz corrections)

The property of Matter cannot be measured using a planar [c squared] spatial co-ordinate system

Magnetic Moment

$$\frac{KE + \mu_B}{c^2}$$

A KEM field has Electric and Magnetic quanta whose total energy quanta is directly related to the square of the particle's velocity

$$4\pi\left[\frac{\overset{\text{mass}}{m}\Omega\overset{\text{velocity}}{v^2}}{c^2}\right]$$

All KEM fields are subject to Lorentz corrections

Kinetic Energies

$$4n\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

KEM field

Matter-Energy

electron KEM model

Relativistic mass Energy = rest Matter + Kinetic EM Energies

Electron rest Matter

Lepton

$$\frac{12\pi}{c^4}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\overset{\text{quanta}}{\underset{\text{velocity}}{v^2}}\right]\right]$$

$$+$$

KEM wave

$$\frac{4\pi}{c^2}\left[\left[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\overset{\text{quanta}}{\underset{\text{velocity}}{v^2}}\right]\right]$$

Kinetic Energies

KEM mass-energies are velocity dependent (subject to Lorentz corrections)

Tetryonics 17.18 - Relativistic mass-Matter

Copyright ABRAHAM [2008] - all rights reserved

Tetryonic mass & Matter

m

Historically interchanged due to the lack of proper definitions the physical properties of EM mass & Matter can now be firmly defined with respect to their energy equivalence and spatial geometries

M

mass is a measure of the 2D planar energy content of any physical system

mass Planck quanta

$$\frac{n\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity



Matter is a measure of the 3D volumetric energy content of any physical system

Matter Planck quanta

$$\frac{T\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity



EM mass should replace the generic term mass with reference to ElectroMagnetic energy densities



MATTER is a geometric 4nπ standing wave topology of EM mass-energy geometries

E/second

2D
radiant equilateral geometry
of EM mass-ENERGY momenta
EM mass

The electromagnetic energies of rest Matter is never 'at rest' as the electromagnetic field energies creating mass-Matter topologies alway propagate at c

E/second²

3D
standing-wave topology
of EM mass-ENERGY momenta
rest Matter

Copyright ABRAHAM [2008] - all rights reserved

Photoelectron KEM fields

The linear momenta produced
as a result of energy momenta in KEM
fields is converted into angular momentum
when leptons are bound to atomic nuclei

EM mass-energy-momenta

The motion of leptons
within atomic nuclei produces
Magnetic moments at various orientations
to the nuclear magneton


v
KE
Transverse bosons
Longitudinal photons
μ
μ
hv
v²

SPIN UP

Changes in the momenta of bound Leptons
[linear & quantised angular]


v
Ω
p
ε₀
KEM
Transverse bosons
Longitudinal photons
hv
v²
v²
hv
λ
f
v

prouduces spectral lines of varying frequencies

SPIN DOWN


v²
hv
μ
μ
Longitudinal photons
Transverse bosons
KE
v

The EM mass-energy content of Baryons directly influence the KEM field energy levels of bound Leptons

and Spin are always conserved

If an electron is 'ejected' from the
Nuclei it will obey conservation of
EM mass-energy momentum

ie Its ejected energy-momentum equals
the absorbed photon's energy-momenta
[minus the work energy required to free it]



UP
spin



Parallel
Magnetic Moments

Nuclear magneton
p
KE

DOWN
spin



Antiparallel
Magnetic moments



Copyright ABRAHAM [2008] - all rights reserved


12
[12-0]
e+
12n
0
[6-6]
ν0
12
0
[6-6]
ν0
12
12
[0-12]
e-
12n
accelerating electrons
n1
0.211 eV
n2
0.276 eV
n3
0.375 eV
n4
0.541eV
n5
0.845 eV
n6
1.502 eV
n7
3.381 eV
n8
13.525 eV
v
1/2c
c
12
e+
μ+
T+
0
ν0
μν0
Tν0
0
ν0
μν0
Tν0
12
e-
μ-
T-

EM energies released through atomic level transitions are released as photons

negative

Energy

$$12\pi\left[\left[m\Omega v^2\right]\right]$$

Leptons

A moving Lepton generates an additional axial magnetic dipole along its central axis of rotation (due to the 'inductive loops' of mass-energy created by charged geometries)

Energy

$$\frac{\left[m\Omega v^2\right]}{n^2}$$

A Lepton's quantum energy level is a result of the Baryonic energy contained in atomic nuclei or incident Protons

KEM fields have Energy and momenta

Stationary leptons have neutralised Magnetic dipoles (Electrostatic fields)

$$KEM \approx \frac{E_1}{n^2} = \frac{-13.6\ \text{eV}}{n^2}$$

Energy created by moving a Lepton though a magnetic field is stored as EM field energy within the Lepton's Kinetic EM field

Creating the various flavours (families) of Leptons

Neutrino oscillations are the result of energy level changes of KEM fields produced by motion within Neutrino families

KEM energy required to ionise bound electron in Hydrogen atom

Tetryonics 18.02 - accelerating electrons

Copyright ABRAHAM [2008] - all rights reserved

Leptronic Oscillations


v
1/2c
c
positron
anti-muon
anti-tau
Q
12
e^+
μ^+
τ^+
12
ν^0
$\mu\nu^0$
$\tau\nu^0$
0
0
Q
0
0
ν^0
$\mu\nu^0$
$\tau\nu^0$
Q
12
e^-
μ^-
τ^-
12
electron
muon
tau
N
S
+
−

Antimatter

$$12\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Leptons · EM Field · ElectroMagnetic · Planck · quanta · mass · velocity

All Leptronic generations, oscillations and types can be accounted for through Tetryonic geometries & energy levels

Matter

Tetryonics 18.03 - Leptronic oscillations


Eigenstate bound energy states
v
P
KE
hv
v²
Q
M
c⁴
n0
0
0 eV
12
[0-12]
1.2e20
rest Matter
n1
5.10 e13
0.211 eV
1
n2
2.04 e14
0.845 eV
2
n3
4.59 e14
1.901 eV
3
n4
8.17 e14
3.381 eV
4
n5
1.27 e15
5.283 eV
5
n6
1.83 e15
7.607 eV
6
n7
2.50 e15
10.355 eV
7
n8
3.27 e15
13.525 eV
8
1 K
2 L
3 M
4 N
5 O
6 P
7 Q
8 R

Principal Quantum levels

$$Mv^2 = KEM = hv^2$$

Bound electron Eigenstate values

In order to ionise any photo-electron from its bound position within a Hydrogen atom the KEM field energy of the electron must be increased from its Eigenstate value to more than 13.525ev

The mass-energy content of Baryons comprising atomic nuclei directly determines the Kinetic energy levels of bound Leptons [forming quantum synchronous convertors]
(incident Bosons/Photons can increase these levels if they contain the exact quanta required to increase the level to the next square number)

Bohr radius

As the Electron's angular velocity increases the measureable Bohr magnetic moment strength increases and its associated KEM field Planck wavelengths decrease (due to the increased Planck quanta).


O
[42-42]
RE
n
$h\nu$
v^2
μ_B
KE
ε
+
+
45,012
KE

The highest quantum number level produces the strongest Magnetic Moment


n=8
n=7
n=6
n=5
n=4
n=3
n=2
n=1
rest Matter is velocity invariant
Charge like rest Matter is velocity invariant
KE
KE
Q
Atom emits Energy
Atom absorbs Energy

Model is for illustrative purposes only - actual quanta illustrated are stored in radial KEM fields

All massive particles asbsorb and release energy in discrete quantum steps according to their respective Tetryonic geometries and changes in velocities


n8
3.27063 e15
13.525 eV
P
KE
ε
$h\nu$
v^2
1.2e20


n7
2.50382 e15
10.355 eV
P
KE
ε
$h\nu$
v^2
1.2e20


n6
1.83939 e15
7.607 eV
P
KE
ε
$h\nu$
v^2
1.2e20

Kinetic Energies


n1
5.10943 e13
0.211 eV
P
KE
ε
$h\nu$
v^2
12
[0-12]
1.2e20


n2
2.04377 e14
0.845 eV
P
KE
ε
$h\nu$
v^2
1.2e20


n3
4.59848 e14
1.901 eV
P
KE
ε
$h\nu$
v^2
1.2e20


n4
8.17509 e14
3.381 eV
P
KE
ε
$h\nu$
v^2
1.2e20


n5
1.27735 e15
5.283 eV
P
KE
ε
$h\nu$
v^2
1.2e20

Copyright ABRAHAM [2008] - all rights reserved

Nuclear Magnetons

are weaker than Bohr magnetons
due to differing mass-charge ratios
and non-parallel Quark magnetons

Baryons

are tri-Dodecyon geometries

EM Field Planck quanta

$36\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$

Baryons ElectroMagnetic mass velocity


Tetryonic Charge
d
u
μ_N
u
Proton
μ_d
μ_u
μ_u
p^+
12
[24-12]
Q
36
Nuclear magneton
u
d
μ_N
d
μ_u
μ_d
anti-Neutron
μ_d
$\overline{N}^0$
0
[18-18]
Q
36
Nuclear magneton
u
d
μ_N
d
μ_d
Neutron
μ_d
μ_u
N^0
0
[18-18]
Q
36
Nuclear magneton
d
u
μ_N
u
μ_u
anti-Proton
μ_u
μ_d
p^-
12
[12-24]
Q
36
Nuclear magneton
Matter geometry

Copyright ABRAHAM [2008] - all rights reserved

Baryonic Magnetic Moments


0
[18-18]
N⁰
N
μN
S
P+
12
[24-12]

A Baryon's Magnetic Moment
is a result of the combined non-parallel
Magnetic moments of its Quarks


0
[18-18]
μd
μd
μu
N⁰
P+
μd
μu
μu
12
[24-12]

As a result of the 3 non-aligned Quark magnetic moments
resulting from their Tetryonic geometry,
the Nuclear Magneton is considerably weaker than the Bohr Magneton

Nuclear Quantum Energies

[Principal Quantum Numbers]


Ionisation Energy
n1
n2
n3
n4
n5
n6
n7
n8
hv
ionisation
(free electron)
v
P
KE
ε0
M
μ0
v²
Kinetic Energies
n1
hv
0.211 eV
5.10 e13
0 eV
1.2e20
-13.389 eV
rest Matter
n2
0.845 eV
2.04 e14
-12.755 eV
n3
1.901 eV
4.59 e14
-11.699 eV
n4
3.381 eV
8.17 e14
-10.219 eV
n5
5.283 eV
1.27 e15
-8.317 eV
n6
7.607 eV
1.83 e15
-5.993 eV
n7
10.355 eV
2.50 e15
-3.245 eV
n8
13.525 eV
3.27 e15
-0.075 eV
n=8
n=7
n=6
n=5
n=4
n=3
n=2
n=1
Q
Atom emits Energy
Atom absorbs Energy

All electron energy levels are reflective of the KEM field of a electron in a specific quantum level (The rest Matter of each electron is invariant)

Higher Quantum Level electrons already have high Kinetic energies and thus require lower frequency photons (low additional KE) in order to be ejected from their bound nuclear positions

-13.6 eV Hydrogen ionisation Energy

An Electron's energy can only increase in steps that reflect the Tetryonic Matter geometry of Leptons and their square mass-energies

Principal Quantum numbers reflect an electron's energy level

Energy may be absorbed or released from any lepton in Quantum steps reflecting the energy difference between the electron 'orbitals'

Energy required to ionise electron with an existing KEM field

$$\frac{1}{\lambda} = \frac{R_H}{hc}\left[\frac{1}{n_i^2} - \frac{1}{n_f^2}\right]$$

Transitions between electron energy levels is the basis for emission and absorption spectra

$$KEM = \frac{E_i}{n^2} = \frac{-13.525\ \text{eV}}{n^2}$$

Eigenstate energy levels

Any electron that has in excess of 13.525 eV of Kinetic Energy has sufficent KE to escape the Nucleus

Leptons are historically classified as Spin 1/2 particles (by the spin-statistics theorem and the Pauli exclusion principle) as determined by their magnetic moments

Quantum Spin Numbers

(rotations about an axis)

Spin 1/2

720°

Rotating a spin-1/2 particle by 360 degrees does not bring it back to the same quantum state it needs a 720 degree rotation



Planck bar relates to the electric field content of KEM fields resulting from Matter in motion (as reference to the Nuclear magneton or external Magnetic field)

Spin 0

any°

A spin-zero particle can only have a single quantum state, even after torque is applied.

Spherical 'point particles' of charge do not exist

Spin 1

360°

Rotating a spin-1 particle 360 degrees can bring it back to the same quantum state



SPIN must not to be confused with Chirality (reflections)



Spin 2

180°

Rotating a spin-2 particle 180 degrees can bring it back to the same quantum state

Photons are their own anti-particle



Spin 3

120°

Rotating a spin-3 particle 120 degrees can bring it back to the same quantum state



On a geometric basis all Leptons are in fact spin 3 particles

Tetryonics 19.01 - Quantum spin numbers



Magnetic moments are determined by the KEM fields created by vector linear momentum

Nuclear Magnetic moments are complicated by the tri-quark magnetons within all Matter topologies

The KEM field of any charged particle in motion is reflective of the particle's nett charge topology

S
Spin UP
KE
e-
N
S
Bohr magneton
Nuclear magneton
P+
Spin DOWN
μB
Parallel
μN
anti-Parallel
μB
μB
anti-Parallel
μN
Parallel
μB
clockwise
anticlockwise
S_z
$+\frac{1}{2}\hbar$
$\frac{\sqrt{3}}{2}\hbar$
$-\frac{1}{2}\hbar$

electron spins

720°

Rotating a spin-1/2 particle by 360 degrees does not bring it back to the same quantum state it needs a 720 degree rotation

Spin 1/2

120°

Rotating a spin-3 particle 120 degrees can bring it back to the same quantum state

Spin 3

All atomic particles have a particular "spin" analogous to the Earth's rotation on its axis.

$$\mu_B = \left[\frac{Q}{2mv}\right]/\ell$$

An isolated electron has an angular momentum and a magnetic moment resulting from its spin. While an electron's spin is sometimes visualized as a literal rotation about an axis, it is in fact a fundamentally different, quantum-mechanical phenomenon with no true analogue in classical physics.

The quantum mechanical reality underlying spin is complex and still poorly understood Consequently, there is no reason to expect the above classical relation to hold.

$$\mu_B = g\left[\frac{e-}{2mv}\right]S$$

Tetryonic KEM field geometries reveals the source and orientation of all atomic magnetic moments

Generating Magnetons

A static Electron has a negative Tetryonic charge [0-12] topology with neutralised magnetic dipoles



Leptons are
12 loop inductive
charge rotors

Tetryonic geometry
fully explains Leptronic 'spins'



Einstein's Special Relativity model of distorted moving charges producing magnetic moments is incorrect

*BOHR Magneton
produced by Lorentzian
distortion of charges due to
relativistic velocities*

$$\mu_B = \frac{e\hbar}{2m_e}$$



The term "electron spin" can now be taken literally (when modelled with Tetryonic geometries) as an accurate description of the origin of Magnetic moments for all Leptonic [BOHR] magnetons.

The previously held model of the electron as a spinning sphere of charge must be abandoned in favour of the true Tetryonic charge geometries of EM mass-Energy-Matter

Ampere Force



$$B = \frac{\mu_0 I}{4\pi}\int \frac{d\ell \times \hat{r}}{r^2},$$

$$F = 2k_A \frac{I_1 I_2}{r}$$

$$\mathbf{F} = q[\mathbf{E} + (\mathbf{v} \times \mathbf{B})].$$

Lorentz Force



A moving Electron has a KEM field with an Electric field and a Magnetic Moment



The gyromagnetic ratio of a particle or system is the ratio of its magnetic dipole moment to its angular momentum



The KEM field energy of an Electron in motion is subject to relativistic corrections due to energy changes resulting from its acceleration

$$\lambda = L'\sqrt{1 - \frac{v^2}{c^2}}$$

WAVE-length contraction
of mass-energy quanta of KEM field

Stern Gerlach Experiment

In 1922 O. Stern and W. Gerlach measured the intrinsic spin angular momentum
of silver atoms and found it to take only two discrete values.
+ h / 2 and - h / 2 commonly called "spin up" and "spin down


Oven
Magnet pole
N
Beam of silver atoms
S
Magnet pole
Inhomogeneous magnetic field
Photographic plate
Zero field pattern
Field on
Classical expectation
Experimental result
S_z
$+\frac{1}{2}h$
$\frac{\sqrt{3}}{2}h$
$-\frac{1}{2}h$
Spin can take only two orientations

The Stern-Gerlach experiment
to determine electron SPIN

The results were interpreted to show that particles possess an intrinsic angular momentum that is most closely analogous to the angular momentum of a classically spinning charged sphere, that takes on only certain quantized values of angular momentum

Tetryonics shows the results are a product of the KEM field produced by charge particles in motion, with all charged particles being able to produce 2 distinct magneton orientations as a result of the real motion of their intrinsic quantum inductive loop [Matter]geometries through external E fields & as referenced to external M moments.

This along with the Lorentz force produced by an external Magnetic field acting on the KEM magnetons produces the two results obtained

Any increase in electron energies results in an increase in quantised angular momenta and its vector linear momentum


hv
12
[0 12]
M
μ
KE
p
v
v²
Negative charged in motion produce negative charge KEM field geometries

Any change in the KEM energy level of an electron results in Photon emission or absorption

Electron Spins based on the measured Bohr Magnetons of moving electrons are reflected with KEM field geometries

Electrons bound in atomic nuclei increase of decrease their energy levels dependent on the energy level of the nuclei in which they are bound

Bound and unbound electrons can rotate in one of two directions influenced only by external magnetic and electric fields or incident Photons


S_z
N
S
μ
$+\frac{1}{2}h$
$\frac{\sqrt{3}}{2}h$
$-\frac{1}{2}h$


N
Parallel magnetic moment
S
μ_B
S
Antiparallel magnetic moment
N
$\frac{h}{2\pi}$
μ
M
$\frac{h}{2\pi}$
μ
M

The BOHR magneton dipole is measured against either the Nuclear Magneton or external magnetic fields

The two separated beams of electrons produced are defined as having differing SPINS [UP or DOWN]


L
v
z
z
$\frac{\partial B_z}{\partial z}$

$$z=\frac{1}{2}at^2=\frac{1}{2}\frac{F}{m}\left[\frac{L}{v}\right]^2=\pm\frac{\mu_B L^2}{4KE}\frac{\partial B_z}{\partial z}$$

The orientation of the BOHR magneton wrt the NUCLEAR magneton determines the 'direction' of electron SPIN

Tetryonics 19.04 - Stern Gerlach experiment

Copyright ABRAHAM [2008] - all rights reserved



Bohr Magnetons

A moving electron is a 12 loop rotating inductor

Energy created by moving a Lepton though an external EM field is stored as Planck quanta within the Lepton's extended KEM field

Leptronic 'spin' is always determined by the Leptronic Magnetic moment as referenced against the Nuclear Magnetic Moment

Electro-static particles have neutralised Magnetic moments

A moving Lepton creates a secondary stronger intrinsic magnetic dipole moment within its KEM field which interacts with external magnetic fields

Velocity creates Kinetic Energy and Magnetic moments

Reversing the vector direction of the particle's linear momentum creates a reversed dipole Magnetic moment

Left handed and right handed fermions are mirror images of each other

Leptons are not point particles

All Leptronic macro-KEM fields and interactions with external fields can be modelled using Tetryonic geometries

Magnetic moment 'spin orientations' are reversed for opposite charge particles

12
[0-12]
μ
$\frac{h}{2\pi}$
η
12
[0-12]
μ
$\frac{h}{2\pi}$
η
Bohr Magneton
Parallel Magnetic Moments
Anti-Parallel Magnetic Moments
Spin UP
Spin DOWN
Nuclear Magneton
Spin DOWN
Spin UP
Anti-Parallel Magnetic Moments
Parallel Magnetic Moments
Bohr Magneton

Tetryonics 19.05 - Bohr Magnetons

Copyright ABRAHAM [2008] - all rights reserved

Electron Spin orientation

The Bohr magneton dipole produced by Kinetic Energies
is located axially about the centre of rotation



Spin UP


0
[24-24]
H⁰
22,512

Higher energy

Parallel spin


KE
e-
N
S
S
e-
KE
N

All Leptons have 12 intrinsic neutralised dipole moments
and a polarised KEM field Magnetic moment
created by the energies of its motion



Spin DOWN


0
[24-24]
H⁰
22,512

Lower energy

Anti-parallel spin

N
External H field
S

Spin UP



Magnetic field is Parallel to
Nuclear Magnetic moment
or external Magentic H field

Lepton
Magnetic moment



[Bohr Magneton]

$$\mu_B = \frac{e\hbar}{2m_e}$$

Spin DOWN



Magnetic field is Antiparallel to
Nuclear Magnetic moment
or external Magnetic H field


Nuclear Magneton
N
P+
KE
S

Nuclear magnetons
are weaker than
Bohr magnetons

All Leptronic spin directions are referenced to external Magnetic fields [either Nuclear Magnetons or H fields]

Tetryonics 19.06 - Electron Spin orientation

Nuclear Spins

are determined by the orientation of Bohr Magneton
with respect to the Nuclear Magneton
[or an external Magnetic field]

election Matter geoemtries
are negative charged fascia
which create neutral intrinsic
magnetic dipole configurations



MAGNETIC MOMENT

In a moving electron
Kinetic energy produces
an axial Magnetic moment

In a static electron
all intrinsic dipoles are
neutralised through
their orientations



Quantum Inductive Loops
In motion produce Kinetic Energies
In turn creating Magnetic Moments

Electron

PARALLEL
Magnetic moments

UP ▲

BOHR
Magneton

ANTIPARALLEL
Magnetic moments

DOWN ▼



▼ DOWN
ANTIPARALLEL
Magnetic moments

μB

Positron

▲ UP
PARALLEL
Magnetic moments

▲

Spin UP



Spin UP
is a higher energy state
resulting in a **(Parallel)**
Bohr Magneton

Nuclear magneton or external Magnetic field



Spin DOWN
is a lower energy state
resulting in a **(antiParallel)**
Bohr Magneton

Spin DOWN

▼

Lorentz Force

When moving in an
external magnetic field

The axial dipole
moment of an
electron will experience
torque force
proportional to
its velocity



Opposites attract
Similars repel

Nuclear magnetic Moment

[Nuclear magneton]


12
[24-12]
P+
22,500
>
h/2π
μ
ε


12
[24-12]
P+
22,500
<
h/2π
μ
ε

NUCLEAR magnetons are much weaker than BOHR magnetons due to the higher charge to mass ratio of electrons

$$\frac{M_p}{M_e} = \frac{1}{1875}$$


12
[0-12]
e-
12
>
h/2π
μ
ε


12
[0-12]
e-
12
<
h/2π
μ
ε

The nuclear spins for individual protons and neutrons parallels the treatment of electron spin, with spin 1/2 and an associated magnetic moment.

For the combination of electron, neutrons and protons in periodic elements, the situation is even more complicated.



Spin UP

Parallel Magnetons

Spin DOWN

Antiparallel Magnetons

Bohr Magnetons

Nuclear Magnetons

Bohr Magnetons

Antiparallel Magnetons

Spin DOWN

Parallel Magnetons

Spin UP

Direction of total nuclei momentum

0
[24-24]
H°
0
[24-24]
H°
0
[42-42]
N°
e-
P+
0
[42-42]
N°
e-
P+
e-
KE
N
S
P+

Tetryonics 19.08 - Nuclear Magnetic moments

Spin orbital coupling mechanics

The induced magnetic moment of electrons in atomic nuclei combine vectorally with the magnetic moment of the nuclei

anti-parallel moments

Spin DOWN


electron momenta
μB
μ
e
h/2π
P
+
μZ
Proton momenta

μB

Bohr magnetons



parallel moments

Spin UP


electron momenta
μB
μ
e
h/2π
P
+
μZ
Proton momenta

The energy level differences created are manifested in Hyperfine-line splitting Zeeman effects etc.


electron momenta
μB
h/2π
e
P
+
μZ
Proton momenta

Spin DOWN

anti-parallel moments



Nuclear magnetons

μZ


electron momenta
μB
μ
e
h/2π
P
+
μZ
Proton momenta

Spin UP

parallel moments

The alignment of electron spins in nuclei results in diamagnetic, para-magnetic Matter

Copyright ABRAHAM [2008] - all rights reserved

Gyromagnetic Ratio

The electron is a 12 charge quantum rotor
with a uniform charge to mass density ratio,
the ratio of its magnetic moment to
its orbital angular momentum,
also known as gyromagnetic ratio



This implies that a more massive
assembly of charges spinning with the
same angular momentum will have a
proportionately weaker magnetic moment,
compared to its lighter counterpart.

12
[0-12]
1.2 e20

1
electron
12π

The Bohr Magneton is determined by the
charged KEM field geometry of Leptons

1875
charged mass-Matter differential

The combined Kinetic energy of Motion [KEM field]
and Electron Spin coupling with Nuclear Magnetons
will effect any measured Gyromagnetic ratios

22,550
Proton
36π



12
[24-12]
2.25 e23

-1

9.1 e-31 kg

Classical electron model
[rotating sphere]

4π

An electron is
NOT
a spherical particle

12π

12
[0-12]



8.85 e-31 kg

Tetryonic electron
[rotating tri-tetryon topology]

In physics, the gyromagnetic ratio
(also sometimes known as the magnetogyric ratio in other disciplines)
of a particle or system is the ratio of its magnetic dipole moment to
its angular momentum, and it is often denoted by the symbol γ, gamma.

An isolated electron has an angular momentum and
a magnetic moment resulting from its spin.

Its SI units are radian per second per tesla (s−1·T −1) or,
equivalently, coulomb per kilogram (C·kg−1).

Tetryonic quantum mass to Charge ratio

$1.810109642 \times 10^{11}$

The 2006 CODATA
– e / me = -1.758 820 150(44) x 10[11]

Nuclear Magnetons

$$\frac{e-}{e_m} = \frac{\text{Tetryonic elementary charge } 1.602216081\text{ e-19 coulombs}}{\text{Tetryonic electron mass } 8.851486361\text{ e-31}} = \frac{12q}{1.2\text{ e20}}$$

[q/m]

181,010,964,200 C/kg

Spin UP

K.E.



Lower energy

Electron Spin
[Orbital Angular Momentum]

N
Nuclear Magneton
S

Spin DOWN

K.E.



Higher energy

$$\frac{12q}{2.25\text{ e23}} = \frac{\text{Tetryonic elementary charge } 1.602216081\text{ e-19 coulombs}}{\text{Tetryonic Proton mass } 1.659653693\text{ e-27}} = \frac{e+}{P_m}$$

[q/m]

96,539,180.9 C/kg

Tetryonics 19.10 - Gyromagnetic ratio

Copyright ABRAHAM [2008] - all rights reserved


DIA-magnetic [opposed SPINS]
μZ
SPIN UP
μB
Bohr magnetons
Nuclear magnetons
SPIN DOWN
PARA-magnetic [aligned SPINS]
h/2π
ε₀
μ

Tetryonics 19.11 - DIA & PARA-magnetic fields

12
[12-0]
1.2e20



Positron

Leptons

181,010,964,200 C/kg

12
[0-12]
1.2e20



Electron

12
[24-12]
2.25e23



Proton

Baryons

96,539,180.9 C/kg

0
[18-18]
2.25e23



Neutron

All mass-Matter have distinct charge geometries
and once in motion are subject to EM forces
as a result of their geometries & KEM field



Lorentz force Law

$$\vec{F} = q\vec{E} + q\vec{v} \times \vec{B}$$

LORENTZ force | Electric force | charge velocity | Magnetic force

all Matter in motion is subject to
NEWTON'S SECOND LAW OF MOTION

$$F = ma$$

Combining
Lorentz's force law & Newton's Third Law
we obtain a EM mass-charge quotient
for any particle of mass-Matter in motion

$$(M/Q)a = E + v \times B$$

mass-charge ratios

1.335180067 e-20 C

1.810109642 e11 $\left[\frac{q}{m}\right]$m 1e19 V

7.376238634 e-51 kg

are the basis for mass spectroscopy



$$F = ma$$

$$\mathbf{a} \times \mathbf{b} = ab\sin\theta\ \hat{\mathbf{n}}$$

For every action there is an equal and opposite reaction
(NEWTON'S THIRD LAW OF MOTION)

Q *Any two particles with the same EM mass-to-charge ratio follow the same path in a vacuum when subjected to the same external electric field* **M**

Dependent on their generations

Charge/mass

$\left(\frac{q_t}{m_t}\right)$ 4:4 181,010,964,200 C/kg 12:12 $\left(\frac{q_e}{m_e}\right)$

Tetryons and Leptons can have identical mass-charge ratios

96,487,720.78 C/kg

Elements

48,256,721.99 C/kg

0
[24-24]
2.2512e23



Hydrogen

Deuterium



0
[42-42]
4.5012e23

Tetryonic theory shows mass-charge ratios are a measure of mass-energy geometries in Matter topologies

E

Collider particle track physics

A collider is a type of a particle accelerator involving directed beams of particles.



Colliders may either be ring accelerators or linear accelerators,
and may collide a single beam of elementary particles against a stationary target or two beams head-on.

t 4 [0-4]

4 [4-0] t

Tetryons have the same 1/3 elementary charge as some Quarks

d 4 [4-8]

4 [8-4] d

m

2D bosons & photons are radiant mass-enery geometries



3D Matter Fermions are standing wave mass-energy topologies

Analysis of the by-products of these collisions without a clear definition of, and distinction between, EM mass-energy geometries & Matter topologies through the charged geometrics of Tetryonics ceates a misleading and erroneous picture of the particles created in high energy collisions within particle physics accelerator experiments



Q



181,010,964,200 C/Kg



Tetryons can have the same mass-charge ratios as Leptons

12
[0-12]
1.2e20
e-

181,010,964,200 C/Kg

12
[12-0]
1.2e20
e+

M

Copyright ABRAHAM [2008] - all rights reserved

Radiant EM mass-energy geometries

mass Planck quanta

$$\frac{n\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity



E
ε_0
Ω +
N
S
positive charged mass
c^2



E
ε_0
Ω –
S
N
negative charged mass
c^2

Charge Planck quanta

$$\frac{1\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

Bosons Planck quanta

$$\frac{\text{ODD}\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity



Photons Planck quanta

$$\frac{2\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

EM waves Planck quanta

$$\frac{\text{EVEN}\,\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

2D space-time measurements of
equilateral energies form the geometric basis
for electromagnetic mass



S
S
E
ε_0
Ω +
f
Ω –
ε
E
N
N

2D Planar divergent EM mass-energies form radiant Electromagnetic waves

ElectroMagnetic mass is a property of Matter
[being the energy content of its charged geometry per unit time]



Copyright ABRAHAM [2008] - all rights reserved

ENERGY

2D Equilateral scalar energy-momenta



Quantised angular momenta are energy geometries

Squared numbers in physics create equilateral geometries

Planck's constant of mass-energy momenta is the source of all physical constants and force relationships

Separated fields of charge create electromotive forces accelerating Material bodies within them

ENERGY

Planck quanta

$$n\pi\left[\left[m\Omega v^{2}\right]\right]$$

mass velocity

Equilateral energy-momenta form the foundation of all Forces, EM masses & Matter

All energy seeks equilibrium

Positive charge energy momenta fields

Negative charge energy momenta fields

3D Matter topology is NOT a property of 2D ElectroMagnetic mass-energies

it is a measure of the closed 3D standing-wave spatial topology of all fermionic particles created by their charged equilateral mass-energy momenta geometries

Matter displaces vacuum energies to create convergent gravity fields around it



Tetryons are the quantum of Matter

Tetryons
$$\frac{4\pi}{c^4}\left[\left[\overset{\text{Planck}}{m}\,\Omega\,\overset{\text{quanta}}{v^2}\right]\right]$$
mass velocity

Fermions
$$\frac{12\pi}{c^4}\left[\left[\overset{\text{Planck}}{m}\,\Omega\,\overset{\text{quanta}}{v^2}\right]\right]$$
mass velocity

Mesons
$$\frac{24\pi}{c^4}\left[\left[\overset{\text{Planck}}{m}\,\Omega\,\overset{\text{quanta}}{v^2}\right]\right]$$
mass velocity



3D Matter particles are Z component second squared mass-energy topologies & created closed volumes

c^4

Matter
$$\frac{T\pi}{c^4}\left[\left[\overset{\text{Planck}}{m}\,\Omega\,\overset{\text{quanta}}{v^2}\right]\right]$$
mass velocity

The mass-energies of Matter are Lorentz invariant to velocity changes

All Matter is comprised of [and radiates divergent] kEM mass-energies



Deuterium is the quantum of all Elements

Baryons
$$\frac{36\pi}{c^4}\left[\left[\overset{\text{Planck}}{m}\,\Omega\,\overset{\text{quanta}}{v^2}\right]\right]$$
mass velocity

Nuclei
$$\frac{72\pi}{c^4}\left[\left[\overset{\text{Planck}}{m}\,\Omega\,\overset{\text{quanta}}{v^2}\right]\right]$$
mass velocity

Deuterons
$$\frac{84\pi}{c^4}\left[\left[\overset{\text{Planck}}{m}\,\Omega\,\overset{\text{quanta}}{v^2}\right]\right]$$
mass velocity

Tetryonics 20.05 - Standing-wave Matter topologies



Tetryonic Mechanics

The charged geometry of mass-ENERGY-Matter

Q
RE
M
KE
2D mass geometries
3D Matter topologies
scalar energies
Bosons
Fermions
h
3
2
4
5
3
9
7
16
9
5
25
11
6
36
13
7
49
15
8
64
9
81

Abraham

ISBN 978-0-9872884-1-7
[Second Edition © 2012]



TETRYONICS

The charged geometry of mass-ENERGY-Matter in motion

Foundational Quantum Electrodynamics

Abraham

ISBN 978-0-987288-2-4
[Second Edition © 2012]

RE
KE
Q
M
3D Matter
2D mass
KEM energies
Particles Waves
Spectral lines
1
2
3
4
5
6
7
8
3
5
7
9
11
13
15
17
4
9
16
25
36
49
64
81
1/2
1
3/2
2
5/2
3
7/2
4

Tetryonics 21.00 - Tetryonic Electrodynamics title page

Copyright ABRAHAM [2008] - all rights reserved

James Clerk Maxwell



(13 June 1831 – 5 November 1879)

Maxwell's equations describe how Electric and Magnetic fields are generated and altered by each other and by charges and currents.

Q
[v-v]

Net Electric charge is the result of quanta imbalances in equilateral geometry

EM Planck Energy



ORTHOGONAL MAGNETIC DIPOLE FIELD

E

Electric charge polarity is determined by the magnetic dipole vector

$$\oint \overline{E}\cdot d\overline{A} = \frac{q}{\varepsilon_0}$$

Gauss's Law for Electricity

$$\oint \overline{B}\cdot d\overline{A} = 0$$

Gauss's Law for Magnetism

$$\oint \overline{E}\cdot d\overline{s} = \frac{-d\Phi_B}{dt}$$

Faraday's Law

$$\oint \overline{B}\cdot d\overline{s} = \mu_0 i + \frac{\mu_0\varepsilon_0 d\Phi_E}{dt}$$

Ampere's Law

E = electric field
A = area
q = charge
ε_0 = permittivity of free space (a constant)
B = magnetic field intensity
s = path length
Φ_B = magnetic flux
Φ_E = electric flux
t = time
μ_0 = permeability of free space (a constant)
i = current electric charge
$\mu_0\varepsilon_0$ = $1/c^2$, where c=speed of light

ElectroMagnetic fields in turn provide the foundation of our modern electrical and communications technologies.

Maxwell's Equations

Maxwell's equations are a set of partial differential equations that, together with the Lorentz force law, form the foundation of classical electrodynamics, classical optics, and electric circuits.

q
[1-0]

POSITIVE [Ω] CHARGE



Q

Gauss' Law of Electric Flux

Electric fields diverge from Electric charge, and produce the Coulomb force,

Q

N

Gauss' Law of Zero Nett Magnetism

there are no isolated Magnetic poles, but the Henry force acts between the poles of a magnet,

S

ε_0

Faraday's Law of Inductance

Electric fields are produced by changing Magnetic fields,

μ_0

Ampere's Circuital Law

circulating Magnetic fields are produced by moving Electric fields and by electric currents.

NEGATIVE [Ω] CHARGE

q
[0-1]



Copyright ABRAHAM [2008] - all rights reserved

Gauss' Laws

- Gauss' Law of Electric Flux and
- Gauss' Law of Magnetic dipoles

The laws were formulated by Carl Friedrich Gauss in 1835, but was not published until 1867.

They form two of Maxwell's equations which are the basis of classical electrodynamics.

The other two being:
- Faraday's law of induction, and
- Ampère's law with Maxwell's correction.

Gauss's law can be used to derive Coulomb's law, and vice versa.

Equilateral triangles are the foundational charge geometry of EM mass-Energy and Matter


[v-v]
Bosons
1
2 3 4
5 6 7 8 9
10 11 12 13 14 15 16
17 18 19 20 21 22 23 24 25
26 27 28 29 30 31 32 33 34 35 36
37 38 39 40 41 42 43 44 45 46 47 48 49
50 51 52 53 54 55 56 57 58 59 60 61 62 63 64
Q

Electric Charge

results from an imbalance of Energy momenta quanta in v² geometries


[v-v]
Bosons
1
2 3 4
5 6 7 8 9
10 11 12 13 14 15 16
17 18 19 20 21 22 23 24 25
26 27 28 29 30 31 32 33 34 35 36
37 38 39 40 41 42 43 44 45 46 47 48 49
50 51 52 53 54 55 56 57 58 59 60 61 62 63 64
Q

Carl Friedrich Gauss

(30 April 1777 – 23 February 1855)

Integral form

$$\oint \vec{E}\cdot d\vec{A} = \frac{q}{\varepsilon_0} = 4\pi k q$$

Differential form

$$\nabla \cdot E = \frac{\rho}{\varepsilon_0} = 4\pi k \rho$$

Electric fields are divergent from their source

Although originally envisaged as a property applied to spherical geometries and usually illustrated with square sectional boundaries integrating a surface area

$$\Phi = EA = E4\pi r^2 = \frac{Q}{\varepsilon_0}$$

Charge is shown to be the result of the symmetry of equilateral quantised angular momenta

Integral form

$$\oint \vec{B}\cdot d\vec{A} = 0$$

Differential form

$$\nabla \cdot B = 0$$

There are NO Magnetic Monopoles


Electric Constant

$$\varepsilon_0 = 8.85418785\text{e-}12 \ \frac{F}{m}$$

$$\oint \vec{E}\cdot d\vec{A} = \frac{q}{\varepsilon_0}$$


[v-v]
ε0
Q
Ω
μ0
μ0
v²

$$\oint \vec{B}\cdot d\vec{A} = 0$$

The electric flux through any closed surface is proportional to the enclosed electric charge


Magnetic
Constant

$$\mu_0 = 1.25663706\text{e-}6 \ \frac{H}{m}$$

The Divergent force of Charge






[v-v]
Q
DIVERGENT
forces
CONVERGENT
forces





Charged EM fields create a net DIVERGENT force
as a result of their outward radiant energy momenta

but still possess CONVERGENT forces as a result of
their inherent equilateral energy momentum symmetries

Where these radiant charged fields diverge from their source
and overlap their superpositional energy momenta
create the forces of the Law of Interaction

Copyright ABRAHAM [2008] - all rights reserved

Coulomb's Law


12
[24-12]
22,500n
KE
Proton


F
q_1
q_2
F
Like charges repel
Unlike charges attract
q_1
F
F
q_2

$$F = \frac{kq_1q_2}{r^2} = \frac{q_1q_2}{4\pi\varepsilon_0 r^2}$$

Coulomb's Law


12
[0-12]
12n
KE
Electron

The magnitude of the electrostatic force between two point electric charges is directly proportional to the product of the magnitudes of each of the charges and inversely proportional to the square of the distance between the two charges.



opposing energy momenta directions

co-linear energy momenta directions

opposing energy momenta directions


Q
k
Q
k
Q
k
Q
Similars Repel
Opposites Attract
Similars Repel

The law of Interaction

Copyright ABRAHAM [2008] - all rights reserved

Changing Electric Fields produce changing Magnetic fields


t
Zero + E field
No Magnetic dipole
t=1
Observes South
Magnetic field
Maximum + E field
Minimum Magnetic dipole
t=2
Zero + E field
Maximum Magnetic dipole
t=3
Maximum - E field
Minimum Magnetic dipole
t=4
Zero - E field
No Magnetic dipole
t=5
Observes North
Magnetic field
t
+
N
−
S

Photons are chiral EM fields

The geometry of EM fields is invariant to the energy levels that produces them

The quantum harmonic oscillator is the quantum mechanical analog of the classical harmonic oscillator.

It is one of the few quantum mechanical systems for which a simple exact solution is known.

Photons are shown to be Quadrature waves with multiple Electric and Magnetic components 90 degrees out of phase

As viewed from the Right-hand side (a LHS oberserver sees opposite Magnetic poles)

Changing Magnetic fields produce changing Electric fields

The symmetric EM field geometry of photons and EM waves

The symmetric ElectroMagnetic field strengths measured

Michael Faraday

(22 September 1791 – 25 August 1867)

EM field symmetry

" It is proposed that if a changing magnetic field can make an oscillating electric field, then

a changing electric field (from a oscillating electric charge) should make a changing magnetic field "



Any change in the magnetic environment of a coil of wire will cause a voltage (emf) to be "induced" in the coil.

No matter how the motional change is produced, a changing electromotive force will be generated.

The change could be produced by changing the magnetic field strength, moving a magnet toward or away from the coil, moving the coil into or out of the magnetic field, rotating the coil relative to the magnet.

All the resulting changes to the E & M fields and the vector strengths etc are the result of the inherent equilateral geometries of EM fields

Electromagnetic Induction

All ElectroMagnetic circuits are comprised of quantum inductive fields [ZPFs] and energies that obey Newton's third law and the conservation of energy

Electromagnetic induction is the production of an electric current across a conductor moving through a magnetic field.
It underlies the operation of generators, transformers, induction motors, electric motors, synchronous motors, and solenoids.

EM field coupling



$$|\mathcal{E}| = \left|\frac{d\Phi_B}{dt}\right|$$

Michael Faraday formulated that electromotive force (EMF) produced around a closed path is proportional to the rate of change of the magnetic flux through any surface bounded by that path.

$$\nabla \times \mathbf{E} = -\frac{\partial \mathrm{B}}{\partial t}$$

$$V_\mathrm{p} = N_\mathrm{p}\frac{\mathrm{d}\Phi}{\mathrm{d}t}.$$

For the special case of a coil of wire, or a transformer circuit composed of N loops with the same area, Faraday's general equation becomes

$$V_\mathrm{s} = N_\mathrm{s}\frac{\mathrm{d}\Phi}{\mathrm{d}t},$$

Inductive Coupling



A corollary of Faraday's Law, together with Ampère's law and Ohm's law is Lenz's law:
The EMF induced in an electric circuit always acts in such a direction that the current
it drives around the circuit opposes the change in magnetic flux which produces the EMF



Flemings left hand rule
(for electric motors)

Coil moves UP



$$\mathcal{E} = -N\frac{d\Phi_B}{dt}.$$



Coil moves DOWN

An electric current passes through a solenoid, resulting in a magnetic field. When you wrap your right hand around the solenoid with your fingers in the direction of the conventional current, your thumb points in the direction of the magnetic north pole.

An electric current passes through a straight wire. Here, the thumb points in the direction of the conventional current (from positive to negative), and the fingers point in the direction of the magnetic lines of flux.


N
S
Thumb points in direction of the North Pole.
conventional current

Fleming's right hand rule
(for EM induction)

Faraday's Law of Induction

Electromagnetic induction is the production of a potential difference (voltage) across a conductor when it is exposed to a varying magnetic field.

In the frame of a conductor moving relative to the magnet, charged particles in the conductor experience a coulombic force due to the neutralised electric fields of the permanent magnet.

Michael Faraday

(22 September 1791 – 25 August 1867)

Faraday's law states that:
The induced electromotive force (emf) in any closed circuit is equal to the time rate of change of the magnetic flux through the circuit.

$$\boxed{\oint \vec{E} \cdot d\vec{s} = -\frac{d\Phi_B}{dt}}$$

The motion of EM fields creates an induced motion in external fields and particles



The linear energy momenta of the neutralised E-fields produces differing directions of induced emf (current flow)

A permanent magnet has a static Magnetic dipole field and neutralised Electric field geometries

Charged particles in the conductor are subject to voltage emfs

Charged particles in the conductor are subject to voltage emfs

Magnets and Conductors moving together (in the same inertial reference frame) experience NO changing EM fields

Any motion of the conductor relative to the Tetryonic field geometry produces changing force vectors in both the Electric fields and Magnetic fields

An Electrostatic (charged) particle has Electric fields of a particular polarity and neutralised Magnetic fields

Electric Constant

It is impossible (due to the geometry of EM fields) to move either the permanent Magnet or the Conductor without producing variations in the Electric and Magnetic fields



A Magneto-static body of Matter has a dipolar Magnetic field and neutralised Electric fields

Copyright ABRAHAM [2008] - all rights reserved

Ampere's Law

In classical electromagnetism, Ampère's circuital law, relates the integrated magnetic field around a closed loop to the electric current passing through the loop.

Q

[v-v]

All energy momenta quanta have equilateral geometries, [quantised angular momenta [Ω]] that can be modelled as a continuous steady current within a closed inductive loop

$$\oint \vec{B}\cdot d\vec{s} = \mu_0 i + \frac{1}{c^2}\frac{\partial}{\partial t}\int \vec{E}\cdot d\vec{A}$$

The nett Charge of any particle or surface is the result of the quantised equilateral energy momenta symmetries of its integral surface area


Conventional
Current Flow
I
S
N
KE
v
E
separated charge symmetries [emf]
v
Positive Charge
Magnetic field

$1\ \mathrm{A} = 1\frac{\mathrm{C}}{\mathrm{s}}$

All charged bodies in motion posses a Magnetic moment in addition to their kinetic energy

As the velocity of a charged body increases so does its energy momenta


v
p
ε0
Ω
μ0
μ0
hv
v²

$$\oint_C \mathbf{B}\cdot \mathrm{d}\boldsymbol{\ell} = \mu_0 I_{\mathrm{enc}}$$

$$\mathbf{J}_{\mathrm{f}} + \mathbf{J}_{\mathrm{D}} + \mathbf{J}_{\mathrm{M}} = \mathbf{J}_{\mathrm{f}} + \mathbf{J}_{\mathrm{P}} + \mathbf{J}_{\mathrm{M}} + \varepsilon_0\frac{\partial \mathbf{E}}{\partial t} = \mathbf{J} + \varepsilon_0\frac{\partial \mathbf{E}}{\partial t}\ ,$$

With the addition of Maxwell's Displacement current to account for time varying electric fields without a physical flow of charged Matter the way forward is paved for Planck, Lorentz and Tetryonics

The Closed circuit or loop can be any geometric shape with Tetryonics dictating equilateral [triangular] Planck energies & quantum charge geometries with Tetrahedral geometries for Matter quanta

Andre Ampere

(20 January 1775 – 10 June 1836)

Ampere's law relates magnetic fields to the electric currents that produce them.


Electron
Current Flow
I
v
E
separated charge symmetries [emf]
v
KE
Q
S
N
Negative Charge
Magnetic field

$1\ \mathrm{A} = 1\frac{\mathrm{C}}{\mathrm{s}}$

Interactive force between Conductors





$$F = 2k_A \frac{I_1 I_2}{r}$$

Ampère's force law states that there is an interactive force between two parallel wires carrying an electric current.



$$\mu_0 \overset{\text{def}}{=} 4\pi\ e\text{-}7\ \frac{N}{A^2}$$



This force is used in the formal definition of the ampere which states that it is "the constant current which will produce an attractive force of 2 × 10−7 newtons per metre of length between two straight, parallel conductors of infinite length and negligible circular cross section placed one metre apart in a vacuum"



These attractions and repulsions between electric currents differ fundamentally from the effects produced by electricity in repose. First, they cease, as chemical decompositions do, as soon as we break the circuit. Second, in ordinary electric attractions and repulsions, opposite charges attract, and like charges repel; in the attractions and repulsions of electric currents, we have precisely the contrary; it is when the two conducting wires are placed parallel in such a way that their ends of the same sign are next to each other that there is attraction, and there is repulsion when the ends of the same sign are as far apart as possible. Third, in the case of attraction, when it is sufficiently strong to bring the movable conductor into contact with the fixed conductor, they remain attached to one another like two magnets, and do not separate after a while, as happens when two conducting bodies, oppositely electrified, come to touch.

André Marie Ampère (1775 - 1836)


Thumb Pointing in Direction of Current Flow
Fingers Point in Direction of Magnetic Field

Figure 3

$$1\ \mathrm{A} = 1 \frac{\mathrm{C}}{\mathrm{s}}$$


Similar charges moving in the opposite directions REPEL
Similar charges moving in the same direction ATTRACT
KE
E
F
12
[0-12]
Repulsive Force
Attractive Force
r
I1
I2
Opposite charges moving in the same direction REPEL
Opposite charges moving in the opposite directions ATTRACT
12
[12-0]
S
N

Copyright ABRAHAM [2008] - all rights reserved



ElectroMotive exchange particles

W

All four of the fundamental forces involve the exchange of ODD numbers of electromagnetic charge bosons so as to transfer discrete energy momenta between separated Matter

In ElectroMagnetic field or circuits, when charged Matter moves along electric field lines, electrical work is done on them by the electromotive force, whether it involves storing potential energy (negative work) or increasing kinetic energy (positive work)

γ

The EM exchange force denotes a force produced by the exchange of force carrier particles, such as the electromagnetic force produced by the exchange of photons between electrons

KEM field energy momenta attracts opposite charges

In accordance with Newton's 3rd Law Q2 can also act on Q1 via the superpositioning of energy fields and their momenta

This layered interaction of EM force quanta [EM charge carriers - Z bosons & Photons] is what constitutes the electromotive inductive force [emf]

The closer that Q1 and Q2 are, the greater the effect.

KEM field energy momenta repels same charge particles

Bosons

$$\underset{\text{Charge}}{1\pi}\left[\overset{\text{EM Field}}{\underset{\text{ElectroMagnetic}}{[\varepsilon_0\mu_0]}}.[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}]\right]$$

Photons

$$\underset{\text{Photons}}{2\pi}\left[\overset{\text{EM Field}}{\underset{\text{ElectroMagnetic}}{[\varepsilon_0\mu_0]}}.[\underset{\text{mass}}{m}\overset{\text{Planck quanta}}{\Omega}\underset{\text{velocity}}{v^2}]\right]$$

v
KE
Q
hv
v²
F
v
KE
Q
hv
v²
F
hv
W
hv
W
hf
γ
hf
γ
n1
EM
0.211 eV
1.2e20
n3
KE
0.375 eV
1.2e20
n2
KE
0.276 eV
1.2e20
n2
EM
0.276 eV
1.2e20
v
[1-0]
E
1.33570456 x 10⁻¹⁹ C
1
1
1.33570456 x 10⁻¹⁹ C
E
[0-1]
v
KE
hv
v²
M
Magnetic Moment
c
0
[1-1]
N
S
c

Tetryonics 21.10 - EM Exchange Particles

Lorentz Force


conventional current
I
F
Lorentz Force
A
α
−
+
magnetic vector

In physics, the Lorentz force is the force on a point charge due to electromagnetic fields.

It is given by the following equation in terms of the electric and magnetic fields

The magnetic force component of the Lorentz force manifests itself as the force that acts on a current-carrying wire in a magnetic field.

In that context, it is also called the Laplace force.


Magnetic moment
μ0
Electric Field
ε0
v
μ0

Hendrik Lorentz



(18 July 1853 – 4 February 1928)

$$\vec{F} = q\vec{E} + q\vec{v} \times \vec{B}$$

LORENTZ force *Electric force* *charge velocity* *Magnetic force*

Magnetic fields created by moving charges are perpendicular to the direction of motion (and can do NO work)


Moving Away
KE
Q
S
N
S
N
Q
Negative Charges
S
N
Moving Towards


Q+
Q-
Q0
Q+
Q-
Cyclotron Motion
Q-
Q+
Q0
Q-
Q+


Moving Away
S
N
KE
Q
Positive Charges
Q
S
N
Moving Towards

Up out of page ◎ Magnetic Field ⊗ Down into page

Copyright ABRAHAM [2008] - all rights reserved

Work - Force - Energy

Work is the result of energy-momenta transfer (by means other than Matter-transfer), and produces changes in the second system's nett energy-momenta

Work

refers to an activity involving a force and movement in the directon of the force



ε_0
m
μ_0
μ_0
v^2

Work

$$W = F.d = ma.d = E$$

The Planck constant is the quantum of Action

$$kg\frac{m}{s^2}\,m$$

Mechanical work is a scalar quantity that can be described as the product of a force times the distance through which it acts

[Force per meter]

Force $\boxed{ma = \frac{\Delta p}{\Delta t} = \Delta\left[\frac{mv}{t}\right]}$ $kg\frac{m}{s^2}$

Momentum is the quantum of Force



v
p
ε_0
$kg\frac{m}{s}$
K E
m
μ_0
μ_0
hv
v^2
$\left[m\Omega v\right]^2$
planck
quanta
mass
velocity
c^4

nett linear momentum (like Charge) is the sum of the linear energy-momenta of the quanta

Power is defined as the rate of using Energy or the rate of doing work

Energy

is the scalar capacity to do work You must have energy to accomplish work



ε_0
E
μ_0
μ_0
v^2

Energy

$$E = mv^2 = hv^2$$

Energy is the square of Momentum

$$kg\frac{m^2}{s^2}$$

Energy is always equivalent to the ability to exert pulls or pushes against the basic forces of nature, along a path of a certain length.

[mass-energy momentum squared]

Tetryonics 22.01 - Work, Force & Energy

Copyright ABRAHAM [2008] - all rights reserved

WORK

Force per second

In Classical Mechanics

One watt is the rate at which work is done when an object's velocity is held constant at one meter per second against constant opposing force of one newton.

Work in physics is measured in Joules

Nm/s



Watts

[Joules per second]

James Watt

(19 January 1736 – 25 August 1819)

The watt second is a unit of energy, equal to the joule

$$W = \frac{J}{s} = \frac{N \cdot m}{s} = \frac{kg \cdot m^2}{s^3}$$

One Watt, defined as one joule per second, measures the rate of energy conversion.

W=V.A

Energy / second
[Joules/sec]

POWER

Energy per second

In ElectroDynamics

One watt is the rate at which work is done when one ampere (A) of current flows through an electrical potential difference of one volt (V).

Electrical power is measured in Watts

J/s



Copyright ABRAHAM [2008] - all rights reserved

The electromotive Force

The electromotive force, or most commonly emf (seldom capitalized), or (occasionally) electromotance is "that which tends to cause current (actual electrons and ions) to flow.

Electric Fields contain bi-directional energy-momenta



The electromotive Force is the nett force resulting from the separation of electrical charges (potential difference)



All Charges seek Equilibrium



Separated charges produce an electromotive force

A conductor creates a circuit between the 'Quantum potentials' allowing charges to seek an eqilibrium (current flow)



$$\mathcal{E} = -\frac{d\Phi_B}{dt},$$

"A source emf can be thought of as a kind of charge pump that acts to move charge from a point of high potential through its interior to a point of opposite potential. …

By chemical, mechanical or other means, the source of emf performs work dW on that charge to move it to the high potential terminal. The emf of the source is defined as the work dW done per charge dq: = dW/dq."

A Magnet stores charge quanta (bosons) in static Electro-Magnetic fields that in turn produce a Magnetic dipole

emf is shown to be the nett force resulting from the linear momenta quanta in every Electric 'voltage' field

These momenta accelerate charged particles in one of two directions dependent of the particle's nett charge



A Magnet can be viewed as a neutralised quantum emf source

Copyright ABRAHAM [2008] - all rights reserved

Poynting Vectors


[v-v]
Positive Voltage
SINK
hv
Separated Charges create an emf
hv
Negative Voltage
SOURCE
[^-^]



Energy is the sum of all Electric and Magnetic fields created in a circuit

Poynting Field


V
Electron Flow
2hv
hf
Conventional Current Flow
^

An test charge placed in an Electric field will experience an acceleration in a direction dependent on the sign of the charge

John Henry Poynting



(9 September 1852 – 30 March 1914)

Electrical energy is transferred along a conductive path in an electrical circuit accelerating charged particles and ions in turn imbuing them with Kinetic Energy [voltage leads current]

There is an electric field running down the middle of the wire, which extends to just beyond its surface.

This electric field pushes the charges along against the resistance and adds to the electric field caused by the surface charges. The resultant electric field changes its direction around the circuit as the wires form a loop back to the battery.

Moving charged topologies inside the wire create a secondary magnetic field geometry around the wire



Electric fields

Energy

$$\mathbf{S} = \mathbf{E} \times \mathbf{H}$$

momenta

Magnetic fields

Electrons form a conductive path for Energy to flow along

The Electron drift velocity is much less than the speed of electricity(c)


V
μ_0
KE
ε_0
μ_0
KE
ε_0
μ_0
KE
ε_0
V

Despite the very low 'drift' velocity of the Electrons they generate a large Magnetic field as a result of their motion

Energy is transferred through empty space around (and NOT in) the wires of an electric circuit via an electromagnetic field called the Poynting field

It's important to remember that the current doesn't flow in both directions, only the energy does

Copyright ABRAHAM [2008] - all rights reserved

Coulomb's Electric Interactions

$$k = \frac{1}{4\pi\varepsilon_0}$$

The proportionality constant ke, called the Coulomb constant (sometimes called the Coulomb force constant), is related to defined properties of linear EM energy momentum and is used to define Electric field forces

$$c = \frac{1}{\sqrt{\mu_0\varepsilon_0}}$$

$$8.987\text{ e9 } \frac{\text{Nm}^2}{\text{C}^2}$$



$$\varepsilon_0 = \frac{1}{\mu_0 c^2}$$

Similars repel



Opposites attract



$$\mu_0 = \frac{1}{\epsilon_0 c^2}$$

Similars repel

Linear Coulombic force interactions are a result of charged E field linear momenta

$$\mathbf{E} = \frac{\mathbf{F}}{q_t}$$

The Electric field can be defined by the Force exerted by a Charge



It is a measure of the interactive force produced by the Electric field energy-momenta of two superpositioned charge KEM fields

Longitudinal E field forces between Charged particles are mediated by Photons

$$\mathbf{E} = \frac{1}{4\pi\varepsilon_0}\frac{Q}{r^2}\hat{\mathbf{r}}$$

The Electric field can also be derived from Coulomb's Law

Copyright ABRAHAM [2008] - all rights reserved

Coulomb Force

Electric fields produce Coulombic forces

$$F = k\,\frac{Q_1 Q_2}{r^2}$$

It is defined as the nett Charge transported by a steady current of one Ampere in one second.

C

1 Coulomb of nett charge is comprised of

$(12 \times 1.335180067\ e\text{-}20)^{-1}$

6.240355408 e18 electrons

kg.s



$$k = \frac{1}{4\pi\varepsilon_0}$$

12
[24-12]
1.602176487e-19C
2.25e23
+
k
1.602176487e-19 C
12
[0-12]
1.2e20

$$\alpha = e^2/4\pi\epsilon_0\hbar c$$

Charles-Augustin de Coulomb

(14 September 1736 – 23 August 1806)

Coulomb's Law is a law of physics describing the electric interaction between any two charged particles (and forms the basis for Ampere's Law)

F
q_1
q_2
F
Like charges repel
Unlike charges attract
q_1
F
F
q_2

$$F = \frac{kq_1q_2}{r^2} = \frac{q_1q_2}{4\pi\varepsilon_0 r^2}$$ *Coulomb's Law*

The interactive linear momenta of super-positioned E-fields creates Coulombic forces

Coulombs

As

$$1\text{C} = 1\text{A} \cdot 1\text{s}$$



$\frac{\text{Nm}^2}{\text{C}^2}$
La Place Force
La Place Force
La Place Force
La Place Force
μ_0
μ_0
μ_0
μ_0
F
F
F
α
α
α
+
-

Same charge repulsion field

Opposite charge attraction field

Same charge repulsion field

Amperes

$$\frac{C}{s}$$

$$1\,\text{A} = 1\frac{\text{C}}{\text{s}}$$

Copyright ABRAHAM [2008] - all rights reserved

Charles-Augustin de Coulomb

(14 September 1736 – 23 August 1806)

Coulomb force

$$k_c \frac{Q_1 Q_2}{r^2}$$

As


v
C
Max
A
Max
Max
hv
v²

Ampere force

$$2k_A \frac{I_1 \; I_2}{r}$$

$$\frac{C}{s}$$

Andre Ampere

(20 January 1775 – 10 June 1836)

Lorentz Forces

are the forces on a point charge due to external electromagnetic fields

$$\vec{F} = q[\vec{E} + (\vec{v} \times B)]$$

electric force velocity

magnetic forces do not accelerate charged particles

Linear acceleration
Electric force
between charged particles

Q

Same charges

Q

Opposite charges

Q

Same charges

Q


F
r
repulsive force
F
r
attractive force
F
r
repulsive force

I

The amount of charged mass-Matter topologies moving passing a point per unit time

Current


vector momentum
P
Charge geometry
Electric Permittivity
ε
m
Magnetic Permeability
Dipole field
c²

Charge

The angular mass momenta possessed by a steady current of one ampere in one second.

Q

Transverse perturbative
Magnetic force
between charged particles


KE
Q
S
N
I
KE
Q
S
N
KE
Q
S
N
I
KE
Q
S
N
r
F
r

Same charge
same direction
attractive M fields

Same charge
opposite direction
repulsive M fields

$$F_m = \frac{\mu_0 I^2}{2\pi r}.$$

Copyright ABRAHAM [2008] - all rights reserved

Capacitance

Any two electrical conductors separated by a non-conducting (or very high resistance) medium is a capacitor
[these can be plates, conductive wires or coaxial cables etc]

Capacitance is a function only of the physical dimensions (geometry) of conductors and the permittivity of the dielectric separating them

Plate capacitors



separated conductive cables

In general any separated charges will create a emf voltage



should a current flow in the conductors the capacitive field will be dominated by perpendicular, superpositioned amperian M-fields of greater strength

Coaxial cables



The SI unit of capacitance is the farad (symbol: F) named after the English physicist Michael Faraday;

Capacitance is the ability of a body to store an electrical charge.

$$C = \frac{Q}{V}$$

Any object that can be electrically charged exhibits capacitance

A 1 farad capacitor when charged with1 coulomb of electrical charge will have a potential difference of 1 volt between its plates.

Copyright ABRAHAM [2008] - all rights reserved

Amperian Forces

Currents produce magnetic field forces

$$F = 2k_A \frac{I_1 I_2}{r}$$

6.241335 e18 electrons passing a given point per second constitutes one Ampere.

Coulombs are charged masses

m

that produce accelerations

Andre Ampere

(20 January 1775 – 10 June 1836)

Current is charged Matter in motion

M

that produce magnetic fields

A

1 Amp of electrons has a EM mass of

6.241355408 e18 x 8.851486361 e-31

5.524527227 e-12 kg

kg

An Ampere is a Coulomb per second.
a measure of the rate at which charged Matter moves.

A coulomb is the quantity of charge transported by one amp in one second

1.60221681 e-19 1.60221681 e-19 1.60221681 e-19 1.60221681 e-19 1.60221681 e-19 1.60221681 e-19

C

$1C = 1A \cdot 1s$

As



A

$1\,A = 1\frac{C}{s}$

$\frac{C}{S}$

8.851486 e-31 kg 8.851486 e-31 kg 8.851486 e-31 kg 8.851486 e-31 kg 8.851486 e-31 kg 8.851486 e-31 kg

An ampere is one coulomb per second

Copyright ABRAHAM [2008] - all rights reserved

Ampere's Magnetic Interactions

the force of attraction or repulsion between two current-carrying wires (see first figure below) is often called Ampère's force law.

The best-known and simplest example of Ampère's force law, which underlies the definition of the ampere, the SI unit of current, states that the force per unit length between two straight parallel conductors is



$$F = 2k_A \frac{I_1 I_2}{r}$$

Opposites attract

Opposite charges moving in opposite directions

Opposite charges moving in the same direction

Same charges moving in opposite directions

Same charges moving in the same direction

Similars repel

It is a measure of the interactive force produced by the Magnetic field energy-momenta of two superpositioned KEM field geometries

2D Electric field geometries accelerate charged particles

Lorentz Forces

If a particle of charge q moves with velocity v in the presence of an electric field E and a magnetic field B, then it will experience a force

3D Matter topologies in motion create magnetic moments


F
torque force
electric vector
E
A
magnetic vector

charged particles in motion produce KEM fields with magnetic moments


magnetic pertrubation
A
magnetic dipole vector
N
M
E
S
E-field acceleration
S
M
E
A
magnetic dipole vector
N
Amps
Magnetic forces
Perturbative
m
Coulombs
Electric
acceleration forces

$$\vec{F} = q\vec{E} + q\vec{v} \times B$$

LORENTZ force · Electric force · charge velocity · Magnetic force


conventional current
I
F
torque force
magnetic vector
A
α
-
+

external magnetic fields create torque forces on the M dipoles of KEM fields

The Lorentz force is the force on a charged particle due to external electromagnetic fields.

Charles-Augustin de Coulomb

(14 September 1736 – 23 August 1806)

Magnetic field upwards through paper ⊙


DRIFT
Weaker field
Stronger field
grad |H|
DRIFT
D
DRIFT
F
DRIFT
C
DRIFT
E
DRIFT
B
positive charges
cyclotron motion
negative charges
A

Andre Ampere

(20 January 1775 – 10 June 1836)

All charges in motion are subject to external EM forces on their KEM fields

Copyright ABRAHAM [2008] - all rights reserved

Neutral Particle interactions

Opposites Attract

Classical Forces of interaction
are unable to explain
how Neutral particles
are attracted to other particles

Similars Repel


0
[42-42]
+
−
ε
84
ε
Max
45,012

Tetryonic charge geometry



reveals the equilateral field mechanics behind
EM induction and all the physical forces

All Matter topologies are comprised of charged mass-energy quanta
that effect atomic interactions via their KEM field energy momenta


12
[42-30]
−
72
+
45,000


22,500
0
[18-18]
−
36
d
ε²
12
[24-12]
+
36
22,500

Coulombic Interactions


eν
0
[6-6]
12
S
N
KE
eν
0
[6-6]
12
S
N
KE

Magnetic Interactions

Amperian Forces

All Matter in motion produces a secondary interactive KEM field

Copyright ABRAHAM [2008] - all rights reserved

Charged mass-Matter

All particles and fields have charged mass-energy geometries

Coulombs

C

kg.s

mass seconds

$$1\text{C} = 1\text{A} \cdot 1\text{s}$$

An elementary charge is 1.602216081 e-19 C

Amperes

A

KG

mass-Matter per second

$$1\,\text{A} = 1\frac{\text{C}}{\text{s}}$$

6.241355408 e18 electrons /sec constitutes one ampere.



Charge is measured by the linear forces produced by the 2D equilateral geometry of mass-energy momenta

2D kEM angular mass-energy momenta

It is defined as the charge provided by a steady current of one ampere in one second.



Current is measured by the transverse forces produced by mass-energy momenta of Matter topologies in motion per unit of time

3D mass-Matter momentum

The amount of charged mass- Matter passing a point per unit time

CHARGE

One coulomb of charge flowing per second equals one ampere of current.

CURRENT

$$Q = I \,.\, t$$

Charge and Current are related to each other through time

Charge

Q

Current

I



C As Charge kg.s

$C \approx kg.s \approx A$

KG $\frac{C}{s}$ Current A

q

1.355180067 e-20 s/kg

Planck Charge

quantised angular momenta
per scalar mass

$\frac{\Omega}{c^2}$

kg Planck's constant $\frac{m^2}{s}$

m

6.629432672 e-34

c^2

$\frac{E}{c^2}$

m

7.376238634 e-51 kg/s

Planck mass

scalar EM energies
per second

1.602216081 e-19 C

elemental charge

Inverse Planck mass momenta

1.810109642 e30 C/kg

There exists an inverse spatial relationship between mass & charge that supports an earlier determination that quantised angular momentum [equilateral geometry] creates Charged mass-Energy-Matter

8.851486361 e-31 kg

electron mass

scalar mass per
quantised angular momenta

q^{-1}

7.489626489 e19 kg/s

$\frac{c^2}{\Omega}$

n

1.015372043 e70 v^2

Compton frequency

$\frac{c^2}{E}$

seconds per
scalar EM energies

m^{-1}

1.355704512 e50 s/kg

KG A

C kg.s

Fine-tuning this relationship of Planck mass-energies to quantised angular momenta at the quantum scale to equilibrium
will provide an exact determination of all macroscale physical properties of mass-energy, charge, physical constants etc directly from theory

Electricity



"There exits Negative and Positive electrical quanta"



Electromagnetism: a fundamental interaction between the magnetic field and the presence and motion of an electric charge topology.

Electric charge: the geometry of EM energy momenta, also detemines their electromagnetic interactions.



Electrically charged Matter topologies are influenced by, and produce, electromagnetic fields when in motion



Electric potential: the capacity of an electric field to do work on an electric charge, typically measured in volts..

Benjamin Franklin

(January 17, 1706 – April 17, 1790)

Charles-Augustin_de_Coulomb
(14 September 1736 – 23 August 1806)

Andre Ampere
(20 January 1775 – 10 June 1836)

Georg Simon Ohm
(16 March 1789 – 6 July 1854)

Carl Friedrich Gauss
(30 April 1777 – 23 February 1855)

Heinrich Lenz
(February 12, 1804 – February 10, 1865)

Michael Faraday
(22 September 1791 – 25 August 1867)

James Clerk Maxwell
(13 June 1831 – 5 November 1879)

James Prescott Joule
(24 December 1818 – 11 October 1889)

John Henry Poynting
(9 September 1852 – 30 March 1914)

Nikola Tesla
(10 July 1856 – 7 January 1943)



Electric field: an influence produced by one electric charge on other charges in its vicinity.



Electricity is the flow of Energy between separated Charge potentials when an electric circuit is formed measured in Volts [Joules/C]



Electric current: is a secondary effect resulting from electrical energy in a circuit It is the movement or flow of electrically charged particles, typically measured in amperes.

Electricity is a general term encompassing a variety of phenomena resulting from the presence and flow of electric charge. These include many easily recognizable phenomena, such as lightning, static electricity, and the flow of electrical current in an electrical wire. In addition, electricity encompasses less familiar concepts such as the electromagnetic field and electromagnetic induction.

Copyright ABRAHAM [2008] - all rights reserved

EM field Permittivity

The Electric constant, commonly called
the vacuum permittivity, or permittivity of free space,
relates the units for electric charge to
mechanical quantities such as
length and force.

The name Vacuum Permittivty is a misnomer and should be
replaced with the correct term EM field Permittivity

**The strength of Electric fields
is determined by the
Electrical Permittivity Constant**

$$E = \frac{1}{4\pi\varepsilon_0}\frac{Q}{r^2}$$



8.85418785 e-12

$$\varepsilon_0 = \frac{1}{\mu_0 c^2}$$



"Ampere's Law states that for any closed
loop path, the sum of the quantities (B.ds)
for all path elements into which the complete
loop has been divided is equal to the product
of μ0 and the total current enclosed by the loop."

$$k = \frac{1}{4\pi\varepsilon_0}$$

The permittivity of empty space, equal to 1 in centimeter-gram-second
electrostatic units and to 107/4πc2 farads per meter or, numerically, to
8.854 × 10-12 farad per meter in International System units,
where c is the speed of light in meters per second.



Positive Charge Electric Field

Gauss' Law:
**"The total of the electric flux out of a closed surface
is equal to the charge enclosed divided by the permittivity"**

This applies equally to any integral geometry chosen to
tessellate a surface area

Superpostioned E fields
gives rise to Coulomb Forces



Negative Charge Electric Field

Copyright ABRAHAM [2008] - all rights reserved

EM field Permeability

The permeability of free space,
also called absolute permeability.

The name Vacuum Permeability is a misnomer and should be replaced with the correct term EM field Permeability

The magnetic constant has the value of
4π × 10-7 henry per meter.

The strength of Magnetic fields is determined by the Magnetic Permeability Constant



Magnetic Constant

1.25663706 e-6

$$\mu_0$$

The magnetic field is most commonly defined in terms of the Lorentz force it exerts on moving electric charges.

$$F$$

The magnetic field generated by a steady current (a constant flow of electric charges in which charge is neither accumulating nor depleting at any point) as described by the Biot–Savart law

$$B=\mu_0 H$$



Positive Magnetic Moment

Magnetic monopoles do NOT exist

they are a mathematical identity and not physically possible due to the equilateral geometry of Planck energies



Negative Magnetic Moment

Copyright ABRAHAM [2008] - all rights reserved

James Prescott Joule



(24 December 1818 – 11 October 1889)


1m
1 Coulomb creates a linear accelrations
F
ε0
1N
μ0
1 Joule
v²
1 Ampere creates orthogonal magnetic fields

Joule

A measure of the equilateral charged
mass-energy momenta that can to do work

... the mechanical power exerted in turning a magneto-electric machine is converted into the heat evolved by the passage of the currents of induction through its coils; and, on the other hand, that the motive power of the electro-magnetic engine is obtained at the expense of the heat due to the chemical reactions of the battery by which it is worked (1845)

EM Field Planck quanta

$$n\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$$

mass ElectroMagnetic mass velocity

It is equal to the energy expended (or work done) in applying a force of one newton through a distance of one meter (1 newton metre or N·m), or in passing an electric current of one ampere through a resistance of one ohm for one second


Q
[v-v]
Positive Charge energy
1N.m
F
m
hv
v²
c²
second

[Joule seconds] per second

$$\boxed{\text{Energy}\quad kg.\frac{m^2}{s^2}}$$

$$J = \frac{kg\cdot m^2}{s^2} = N\cdot m = Pa\cdot m^3 = W\cdot s$$

Planck's Constant x frequency $[kg.\frac{m^2}{s}].s^{-1}$

mass x velocity squared $kg.[\frac{m}{s}]^2$

Momentum x velocity $[kg.\frac{m}{s}].\frac{m}{s}$


1N.m
Q
[v-v]
Negative Charge energy
F
m
hv
v²
c²
second

[Joule seconds] per second

Volts

[Joules per Coulomb]

The volt is the unit for electric potential (voltage), electric potential difference, and electromotive force.

$$V = \frac{W}{A} = \frac{J}{A \cdot s} = \frac{N \cdot m}{A \cdot s} = \frac{kg\,m^2}{A\,s^3} = \frac{kg \cdot m^2}{C \cdot s^2} = \frac{N \cdot m}{C} = \frac{J}{C}$$

A single volt is defined as the difference in electric potential across a wire when an electric current of one ampere dissipates one watt of power.
It is also equal to the potential difference between two parallel, infinite planes spaced 1 meter apart that create an magnetic field of 1 newton per coulomb.
Additionally, it is the potential difference between two points that will impart one joule of energy per coulomb of charge that passes through it

Positive charge



1V = 1J/C

One Volt is defined as energy consumption of
one joule per electric charge of one coulomb

Negative charge



1V = 1A · 1ohm

One volt is equal to current of 1 amp
times resistance of 1 ohm

Positive voltage

Negative voltage




V
[v-v]
V
E
1-0
3-1
6-3
10-6
15-10
21-15
28-21
36-28
1 Joule
4 Joules
9 Joules
16 Joules
25 Joules
36 Joules
49 Joule
64 Joules

[Joules per Coulomb]

Any separation of electrostatic charges, results in a voltage.
[Potential Difference]

Voltage is a scalar measure of linear electromotive forces of separated charges seeking potential equilibrium


V
[v-v]
V
E
0-1
1-3
3-6
6-10
10-15
15-21
21-28
28-36
1 Joule
4 Joules
9 Joules
16 Joules
25 Joules
36 Joules
49 Joule
64 Joules

[Joules per Coulomb]

Positive charged mass-energy



Clockwise inductive energy flux

charge

Charge is the equilateral geometry of Energy that gives form to all mass & Matter



time

Negative charged mass-energy



Counter clockwise energy flux

q

q

t

$$\frac{\Omega}{c^2}$$

$$\frac{m^2}{s}\ \frac{s^2}{m^2}$$

$$s$$

seconds

t

1.33518 e-20 s

Changes to nett quantised angular momenta [charged mass-energies] within any space-time co-ordinate system forms the basis of time

ElectroMagnetic Charge is a quantum property resulting from the equilateral QAM geometry of mass-Energy



The two ElectroMagnetic charge geometries possible can be created through tesselation of electrical energy in ideal inductive loops

Coulombs

are a measure of 2D charged mass geometries
and the electromagnetic forces they produce per unit time

W+ boson integrals
nett positive charged
mass momenta



Q
[v-v]

Charles-Augustin de Coulomb

(14 September 1736 – 23 August 1806)

Derived in 1785 Coulomb's Law is a law of physics describing the electrostatic interaction between any two charged particles (and forms the basis for Ampere's Law)

Q
[v-v]

W- boson integrals
nett negative charged
mass momenta



Electric forces

$$m\frac{\Omega}{c^2}$$

Magnetic forces

Coulombs

The coulomb (unit symbol: C) is the SI derived unit of electric charge (symbol: Q or q).
It is defined as the charge transported by a steady current of one ampere in one second:

Amperes

As



$$\frac{C}{s}$$

Interactive linear momenta of super-positioned E-fields creates Coulomb's force law

1A.1s

1F.1V

Copyright ABRAHAM [2008] - all rights reserved

$1\text{C} = 1\text{A} \cdot 1\text{s}$

1 COULOMB is a measure of linear 2D electric field energy momenta in EM field geometries

1 AMPERE is a measure of orthogonal 2D magnetic field forces produced by Matter topologies in motion

$1\,\text{A} = 1\frac{\text{C}}{\text{s}}$

quantised electrical energy momenta

1C is the quantity of charged masses which pass any point in a circuit in which a current of 1A flows for 1s

C

Coulombs

kg.s

linear acceleration energy momenta

Q

Charge



Amperes are tranverse M-field forces

Coulombs measure longitudinal E-field forces

Amperes are tranverse M-field forces

A

Amperes

KG

magnetic perturbation energy momenta

I

Current

CHARGE is a measure of 2D quantised angular momenta [mass -Matter geometries]

$$Q = I.t$$

quantity of charge = rate of flow of charge × time

CURRENT is a measure of charged mass-Matter geometries in motion

Copyright ABRAHAM [2008] - all rights reserved

Current

is a measure of charged Matter in motion in a circuit per unit of Time

An elementary charge is
1.602216081 e-19 C

C

It is defined as the charge transported by a steady current of one ampere in one second.

Coulombs



Amperes

The amount of electric charge passing a point per unit time

A

6.2413354 e18 electrons passing a given point each second constitutes one ampere.

charged **masses**

kg.s

1.33518 e-20 kg.s

7.489626 e19 kg

Matter

KG

The 2D linear mass-energy momenta capable of accelerating charged particles

The transverse magnetic forces produced by Matter in motion

The ampere is a measure of the amount of charge topologies passing a point in an electric circuit per unit time with 6.241 x 10^18 electrons, or one coulomb per second constituting one ampere

$$1C = 1A \cdot 1s$$

$$1\,A = 1\frac{C}{s}$$

Electric current is a measure of the flow of electrically charged mass-Matter in a circuit as a result of an electrical Voltage potential

5.524527227 e-12 kg

Charged mass

1 second

Matter in motion

6.241355408 e18 electrons

As

$$\frac{C}{S}$$

Voltage [emf] is a measure of the energy momenta per coulomb available to exert a force on charged Matter in a circuit

Copyright ABRAHAM [2008] - all rights reserved



DC

Charges flow in ONE direction

$$I = \frac{V}{R}$$

CURRENT [Charged mass-Matter flow]

VOLTAGE [Energy momenta pressure]

RESISTANCE [electrical conductivity]

Positive charges moving in one direction produce the same magnetic B fields as negative charges moving in the opposite direction

AC

Charges change direction periodically

Current flow

Current is a measure of the charged mass-Matter in motion in an electrical circuit

Electrostatic charges

Current is a measure of the acceleration of charged Matter topologies in any electrical circuit

[it is an indirect measure of electrical energy]

Charges in motion

The velocity of the charges in a circuit is proportional to the value of electric current

Current flow produces magnetic fields around conductive wires

kg.s

Conventional current flow

6.241355408 e18 electrons per sec

Amperes

Electron current flow

KG

Charge

1C = As

coulomb

1C is defined as one amp second

5.524527227 e-12 kg/s

Current

$\frac{C}{s} = 1A$

amperes

1A is defined as 1 Coulomb per second

Tetryonics 23.10 - Current [Matter in motion]

Copyright ABRAHAM [2008] - all rights reserved

The electrical resistance of a conductor is a measure of how much it opposes the passage of an electric current through it

OHM's Law

Georg Simon Ohm

(16 March 1789 – 6 July 1854)

resistivity

$$\mathcal{E} = \rho J$$

Electric field

Current density

General vector equation



$\frac{V}{R} = I$

$R = \frac{V}{I}$

$V = I.R$

$$P = I.V = I^2.R$$

Power is the amount of current times the voltage level at a given point measured in watts.

Current is the flow of charged mass-Matter resulting from an electromotive force

Resistance determines how much current will flow through a conductor

Current [I.V] Voltage
POWER
Current squared [I^2R] Resistance

Ohm's law states that the current through a conductor between two points is directly proportional to the potential difference across the two points.



By introducing the constant of proportionality, Resistance, one arrives at the usual mathematical equation that describes this relationship

Voltage is the force motivating charges to "flow" in a circuit, it is measured as the difference in electrical potential between two points in a circuit

Electrical Resistance



Electron
current flow

Electro-Magnetic energy
can travel through free space or be guided along conductors
and propagates at the 'speed of light' in that medium

Conventional
current flow

The 'drfit' velocity of charged bodies is considerably less
than the velocity of Energy propagation in an electrical circuit

Resistive current flows should be avoided at all costs
to facilitate the efficient transfer of energy

The Polarised Electric fields induce
motion into charged bodies in an attempt to
equalise the charge imbalances at the emf sources

Whenever a current exists,
there MUST be a Magnetic field and
there MUST be Energy present in that field

The acceleration [change in velocity] of electrons in motion
requires the release [or absorption] of Bosons of energy
from [or to] the equilateral KEM field geometry
[[spectriaaline emission~absorption]

Voltage produces a linear force that motivates
charged Matter topologies into motion in a circuit
as electrical energy geometries seek equilibrium

Power is a measure of the total charge geometry
(electrons) moving past a point along with the energy each
charge geometry (electron) possesses (KE expressed as eV)
V.I = P = i.R.I

James Prescott Joule verified Ohm's Law and determined that the heat delivered by a conductor is directly proportional to its resistance and to the square of the current through it.



All energy is comprised of 2D charged masses

He defined Power physically to be the rate at which electrical energies are created or transferred in an electric circuit

Electrical Power

Power is the integral of the cross-product of all electrical and magnetic field vectors produced by scalar energy momenta within a specific area defined by time



The scalar surface integral of the Poynting vector.

The SI unit of power is the watt, one joule per second.



Electrical power flows wherever Electric and Magnetic fields exist together and change over time

emf Voltage



The potential to do work

$$P = V.I$$



Charge geometry Q

RE Relativistic mass-energies densities

3D mass-Matter topologies M

KE Kinetic mass-energies of motion

$$I^2.R = \frac{V^2}{R}$$

Resistance

[0-12]

1.2e 20

The Inertial mass of Matter

Electrical power propagates at the speed of light in an electrical circuit [dependent on the voltage source] electrons have a vastly slower 'drift' velocity resulting from their inertial interaction with energy momenta of the Voltage [emf] field

Copyright ABRAHAM [2008] - all rights reserved



Source

Positive charges are repelled

Negative charges are attracted

Sink

The movement of positive charges is conventional current

separated charges [emf]

Electricity is the flow of energy momenta in a ciruit

A source or a sink is defined by which which charge type is under observation

Upon closure of the circuit separated Charges seek Equilibrium

The transfer of force from electrical energy-momenta quanta to charged Matter in a circuit results in Current

The directional 'flow' of Electricity can be modelled by the movement of Positive or Negative charges in a circuit as separated charges seek equilibrium via any conductive path

Sink

Positive charges are attracted

Negative charges are repelled

Source

The movement of negative charges is electron current

Tetryonics 24.01 - Sources and Sinks

EM Inductive circuits


V
E
I
V
N
S
KE
KE
S
N
S
N
Magnetic dipole moment produced by Inductive turns of wire
Electric current with Circular Magnetic field

Electricity is the flow of Energy between separated Charge potentials when an electric circuit is formed measured in Volts [Joules/C]

Neutral Electric field with Magnetic dipole

Current is produced in a conductor when it is moved through a magnetic field because the neutralised Electric field lines are applying a emf on the free electrons in the conductor and causing them to move.

The process of generating current in a conductor by placing the conductor in a changing magnetic field is called induction

The stronger the Magnetic dipole the greater the potential emf

The Electrical emf created by the energy momenta comprising the neutral EM field will cause electrons to flow in a conductor

If electrical current is flowing in a conductor, there is an associated magnetic field created around the wire.

In a similar manner, if we move a wire inside a magnetic field an electrical current will be generated in the wire.

$$|\mathcal{E}| = N\left|\frac{d\Phi_B}{dt}\right|$$

Magnetic Dipole stength is dependent on:

The total Number of turns in the inductor
& the current flowing through the circuit

Magnets can be considered to be static stores of potential [emf fields]

Magnetic Dipole with Neutral Electric field

Copyright ABRAHAM [2008] - all rights reserved

Electron Volts

The electron volt can also be used
as a unit of mass-energy by applying
Einstein's relation $E = mc^2$.

For example, the rest mass-energy of electron
topologies if 496,532 eV (496.532 MeV).

Chemically, for 1 mole of electrons
1 eV ~ 100 kJ mol-1 (96.49 kJ mol-1)



A Free electron is attracted to
Positive anode of an emf source



EM Field Planck quanta

$$12\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Fermions ElectroMagnetic mass velocity

eV

A unit of energy
equal to the work required to move
one electron through a potential
difference of 1 volt.



hv +

Separated Charges produce electro-motive forces [emf]

− *hv*

Negative charges are
accelerated to the Anode

emf generator

Positive charges are
accelerated to the Cathode

sink

source

The application of UFE to Kinetic energy
calculations reveals the underlying processes
of the Photo-electric effect and
Light-Energy interactions
with respect to Kinetic energy

$$\frac{p^2}{2m} = KE = \frac{1}{2}Mv^2$$

By definition, it is equal to the amount of
kinetic energy momenta
gained by a single unbound electron
when it accelerates through an
electric potential difference of one volt.

An Electron Volt is also
a measure of Electrical Kinetic Energy

EM Field Planck quanta

$$\frac{1}{2}\left[4\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]\right]$$

Tetryons ElectroMagnetic mass velocity

As distinct from Matter's ENERGY
Kinetic Energy is 'extended from the
Tetryonic geometry of all Matter in motion
in a separate 2D KEM field



Accelerated electrons have increased
KE, Magnetic moments & momentum



(Total Energy = Absolute rest Matter + Kinetic energy)
additionally the Lorentz relativistic correction factor (β)
presents itself naturally from the UFE when velocity is applied

All electro-statically charged
particles in Motion have
Kinetic EM fields

Direct Currents result in atttractive co-linear Magnetic fields

KEM fields facilitate
EM interactions between
charges in motion


S
S
N
N
KE
KE
KE
KE
KE
KE

12
[0-12]
e-
mc²
1.2 e20
rest Matter

The Skin Effect

Skin effect is the tendency of an alternating electric current (AC) to distribute itself within a conductor with the current density being largest near the surface of the conductor, decreasing at greater depths

Total Energy
$mc^2 + Mv^2$
KE
magnetic moment


S
S
N
N
KE
KE
KE
Alternating Currents generate repulsive internalised Magnetic fields
N
N
S
S
KE
KE
KE

As the electromotove force
[Electric field energy momenta
driving the charged masses]
alternates so does the resultant
electron direction of motion
and their KEM fields

As the electric Current alternates
[changing direction of charge movement]
the external Magnetic field vector
produced by the electronic KEM fields
aslo alternate

Stationary Charged particles have
neutralised Magnetic fields

EM fields of particles in Motion

Positive changed quanta traveling anti-clockwise in a solonoid creates a North-South magnetic field orientated in the direction shown

positive ion flow

Negative charged quanta create a reversed Magnetic dipole field and reversing the direction of particle motion also reverses the magnetic vector

electron flow

Solenoidal Motion



Charged particles moving in a spiral produce a Circular Magnetic field



Toroidal Motion

A toroidally wound conductor produces a Circular Magnetic field

Helical Motion



Motion in a Magnetic field

Inductors

An inductor (also choke, coil, or reactor) is a passive two-terminal electrical component that stores energy in its magnetic field.

For comparison, a capacitor stores energy in an electric field, and a resistor does not store energy but rather dissipates energy as heat

An inductor with an inductance of 1 henry produces an EMF of 1 volt when the current through the inductor changes at the rate of 1 ampere per second.


Tetryonics reveals the Magnetic fields of Inductors to be neutral Electro-Magnetic fields
L
Magneto-static fields

When the current flowing through an inductor changes, a time-varying electromagnetic field is created around the coil, and a changing emf voltage is formed



Inductors are DC electrical components typically made of a wire or other conductor wound into a coil, to increase the magnetic field.

The number of loops, the size of each loop, and the material it is wrapped around all affect the inductance.

note: the electric field quanta that create an electromotive force in inductors are neutralised voltage fields leading to the mistaken belief that inductors store electrical energy in a magnetic field

Copyright ABRAHAM [2008] - all rights reserved

Charges moving in an Inductive winding



Counter-clockwise winding produces South-North Magnetic field dipole

Similar charges moving in the same direction ATTRACT

Clockwise winding produces North - South Magnetic field dipole

Reversing the direction of current flux reverses the Magnetic dipole field produced

Counter-clockwise winding produces South-North Magnetic field dipole

Similar charges moving in opposite directions REPEL

Clockwise winding produces North - South Magnetic field dipole



Opposite charge ZPFs have opposite inherent magnetic dipole orientations

Opposite direction windings produce reverse dipole orientations

Opposite direction currents produce opposite polarity magnetic dipoles

Opposite direction currents with opposite direction windings produce similar polarity magnetic dipoles

This is best viewed using physical models

Tetryonics 24.07 - Moving charges in an Inductor

Capacitors

Changing Electric fields
create
changing Magnetic fields

A capacitor is a passive two-terminal AC electrical component
used to store alternating electrical energy in an electric field.
It blocks the block of direct currents.

Changing Magnetic fields
create
changing Electric fields

Capacitors store & pass electrical energy as charged 2D masses

Capacitors store EM Energy
as transverse Bosons

Capacitors store charged
masses between their plates

E

Capacitors store
Energy as Charges



Voltage is
Joules per Coulomb

V

Charged Matter [current] does not
flow between the plates
of a Capacitor

ODD.hv

charge

A common form of energy storage device is a parallel-plate capacitor whose
capacitance is directly proportional to the surface area of the conductor plates
and inversely proportional to the separation distance between the plates.

volts

hv^2

Capacitance

Copyright ABRAHAM [2008] - all rights reserved

Capacitance

The SI unit of capacitance is the farad (symbol: F), named after the English physicist Michael Faraday

In general any separated charges will create a emf voltage



Any two electrical conductors separated by a non-conducting (or very high resistance) medium is a capacitor
[these can be plates, conductive wires or coaxial cables etc]

Plate capacitors



Coaxial cables



Capacitance is the ability of a body to store an electrical charge.

$$C = \frac{Q}{V}$$

Any object that can be electrically charged exhibits capacitance

A 1 farad capacitor when charged with1 coulomb of electrical charge will have a potential difference of 1 volt between its plates.

should a current flow in the conductors the capacitive field will be dominated by orthogonal, superpositioned Amperian M-fields of greater strength



Capacitance is a function only of the physical dimensions (spatial geometry) of conductors and the permittivity of the dielectric separating them

Inductive and Capacitive energy storage



Inductors store energy as Magnetostatic fields

It is customary to use the symbol L for inductance, in honour of the physicist Heinrich Lenz.

In the SI system the unit of inductance is the Henry,
named in honor of the scientist who discovered inductance,
Joseph Henry.

If the rate of change of current in a circuit is one ampere per second and the resulting electromotive force is one volt, then the inductance of the circuit is one henry

$$v_m = \sum_{n=1}^{K} L_{m,n} \frac{di_n}{dt}.$$

The voltage across an inductor
is equal to the product of its
inductance and the time
rate of change of the current through it

Joseph Henry

[17 December 1797 – 13 May 1878]

Michael Faraday

[22 September 1791 – 25 August 1867]

The SI unit of capacitance is the farad (symbol: F),
named after the English physicist Michael Faraday

a 1 farad capacitor when charged with 1 coulomb of electrical charge will have a potential difference of 1 volt between its plates.

$$W_{\text{stored}} = \frac{1}{2}CV^2 = \frac{1}{2}\varepsilon_r\varepsilon_0\frac{A}{d}V^2.$$

Capacitance is the ability of a body to store an electrical charge.
Any object that can be electrically charged exhibits capacitance.



Capacitors store energy in Electrostatic charge fields

Copyright ABRAHAM [2008] - all rights reserved

Inductive - Capacitive circuits

An LC circuit, also called a resonant circuit, tank circuit, or tuned circuit,
consists of an inductor, represented by the letter L,
and a capacitor, represented by the letter C.

LC

When connected together, they can act as an electrical resonator,
an electrical analogue of a tuning fork, storing energy
oscillating at the circuit's resonant frequency

These LC circuits are idealised models
assuming there is no dissipation of energy due to resistance over time,
with the circular EM vectors representing electron current flow in the circuit
and its translation between inductive and capacitive forms of energy storage.



**If a charged capacitor is connected across an inductor,
charge will start to flow through the inductor,
building up a magnetic field around it and
reducing the voltage on the capacitor.**

**Eventually all the charge on the capacitor will be gone
and the voltage across it will reach zero.**

**However, the current will continue,
because inductors resist changes in current.**

**The energy to keep it flowing is extracted from the magnetic field,
which will begin to decline.**

**The current will begin to charge the capacitor
with a voltage of opposite polarity to its original charge.**

**When the magnetic field is completely dissipated the current will stop
and the charge will again be stored in the capacitor,
with the opposite polarity as before.**

**Then the cycle will begin again,
with the current flowing in the
opposite direction through the inductor.**



Capacitors store EM Energy as transverse Bosons



Ampere's current is charged Matter in motion

Current does not flow between the plates of a Capacitor

Capacitors store Energy as Joules per charge

Capacitors store & pass energy as charged masses



Ampere's force is produced by M-fields

Voltage is Joules per Coulomb

Changing Magnetic fields create changing Electric fields

Changing Electric fields create changing Magnetic fields

Capacitors store charged masses between their plates

Displacement Current

Maxwell's displacement current is better termed a 'displacement voltage' in light of the fact the charged Matter does not move/flow between the charged plates of a capacitor only the charged mass-energies.

Changing Electric fields produce changing Magnetic fields and vice versa as a direct result of their respective E&M field geometries within the Planck quanta of EM fields

$$\nabla \times \mathbf{B} = \epsilon_0 \mu_0 \frac{\partial \mathbf{E}}{\partial t} + \mu_0 \mathbf{J},$$



As the energy content of a charge increases so does its voltage

As opposed to Maxwell's view of a 'stretching ether' that stores energy between the capacitive plates

Equilateral energy momenta is stored compressively in the inductive quantum fields [ZPF] as it increases, and is released via charged exchange W-Bosons

Producing a capacitive region of ElectroMagnetic fields and stress energies



Bosons are transverse stores of energy momenta

$$\mathbf{J}_D = \epsilon_0 \frac{\partial \mathbf{E}}{\partial t}$$

'Displacement Currents' between charged surfaces are produced by a increasing Electric Field component that seeks equilibrium

It must be carefully borne in mind that we have made only one step in the theory of the action of the medium. We have supposed it to be in a state of stress, but we have not in any way accounted for this stress, or explained how it is maintained. This step, however, seems to me to be an important one, as it explains, by the action of the consecutive parts of the medium, phenomena which were formerly supposed to be explicable only by direct action at a distance.

Maxwell - On Physical Lines of Force (1861)

$$mc^2 = E = Mc^4$$

A clear geometric distinction can now be made between **EM mass geometries** and standing wave **Matter topologies**

mass



$$\frac{E}{c^2} = m$$

mass-energy momenta in a 2D equilateral geometry

Radiant waveform
EM mass-energies

Matter

$$M = \frac{E}{c^4}$$



Four mass-energy momenta in a 3D tetrahedral topology

Standing waveform
EM energies



Photons are dual EM mass-energies

Photons are Matterless

2D EM mass is NOT 3D Matter

3D Matter is comprised of 2D EM mass-energies

radiant mass-energies
of collapsed Matter geometry

$$n\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$$

mass · EM Field · ElectroMagnetic · Planck · quanta · mass · velocity

$$T\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$$

Matter · EM Field · ElectroMagnetic · Planck · quanta · mass · velocity

$$\rho/\text{second}$$

$$\rho/\text{second}^2$$



$$= m\Omega\left[\frac{v^2}{c^2}\right]$$

kg

Radiant EM masses

$$\frac{4\pi m}{c^2} = M$$

Standing-wave mass-Matter

$$m\Omega\left[\frac{v^2}{c^4}\right] =$$



KG

massless particles are a scientific misnomer
and massless must now be re-termed Matterless

de Broglie Matter-waves

EM CHARGE
provides the foundational interaction geometry for all mass & Matter

In quantum mechanics, a Matter wave or de Broglie wave is the probabilistic electromagnetic quantum wave-form created by the Planck elements constituting Matter

Relativistic mass-energy is the total sum of all Planck energy momenta in any spatial co-ordinate system



Q
Charged Planck quanta

RE
M+KE
Relativistic mass-energies

hv

hv^2

M
rest mass-Matter topologies

mv^2

KE
Kinetic mass-energy geometries

All EM waves and Matter are made up of integral Planck quanta [any imbalance results in Charge] as the number of Planck quanta increases their associated wavelengths decrease

The relativistic stress tensor mass-energies of Matter in motion is the sum of its standing-wave mass-Matter topology and its Lorentz corrected kEM field mass-energy geometries

3D MATTER
is the charged topology created by standing-waves of 2D mass-energies

Kinetic EM mass-energy levels depend on the velocity of the Matter particle in motion
[in Matter energy travels in a standing wave at the speed of Light]

Kinetic EM fields are the mass-energy fields created by Matter in motion

P
KE
N
S
magnetic moment

The rest mass-energy geometries comprising all Matter topologies are velocity invariant

Copyright ABRAHAM [2008] - all rights reserved



Material EM masses

deBroglie wavelength & Compton frequency



λ

Any increase in Energy quanta results in
a decrease in EM mass quanta wavelengths

v^2

In Matter all energy propagates at c

$$mv^2 = E = hv^2$$

in Standing wave Matter
v=c

Number of Quanta comprising rest Matter



Compton Frequency

$$\frac{mc^2}{h} = 1 \times 10^{19}$$

Electron Compton Frequency

$= 1.2 \times 10^{20}$ quanta



v^2

Wavelength of Quanta comprising rest Matter



de Broglie wavelength

$$\frac{h}{mc} = 2.99792456 \times 10^{-11} \text{ m}$$

Electron de Broglie wavelength

$= 4.002769142 \times 10^{-11}$ m



λ

Linear momentum of standing wave Energy comprising Matter



Intrinsic Particle Momenta

$$mc = 2.211340633 \times 10^{-23} \text{ Ns}$$

Intrinsic Electron momenta

$= 2.95253793 \times 10^{-30}$ Ns



p

The Compton frequency, deBroglie wavelength
and Energy momenta of any physical system
are all related through the speed of Energy [c]

**The examples above are for stationary Electrons
any motion will NOT affect the results for the electron itself
(however a extended KEM field will be produced by the motion
and its properties will be affected by changes in velocity)**

In Lorentz invariant Matter the standing wave
Energy always propagates at the speed of Light [c]
(with the KEM field subject to Lorentz corrections)

Tetryonics 25.03 - Material deBroglie-Compton properties

Copyright ABRAHAM [2008] - all rights reserved

KEM Quantum levels


Free electron
n9
769+
n8
768
n7
588
n6
432
n5
300
n4
192
n3
108
n2
48
n1
12
Electron rest Matter
Kinetic Energies
8
7
6
5
4
3
2
1
v
p
KE
hv
v²
magnetic moment
$\frac{Mv^2}{c^2}$

Electron energy external to Nuclei is continuous as there are no Nuclei to determine electron energies

Photons are Kinetic energy momenta EM force carriers

Quantum levels are the result of Nucleons and electrons interacting as synchronous quantum convertors

$$\frac{p^2}{2m} = KE = \frac{1}{2}Mv^2$$

Photo-electron mass-energies within Nuclei are determined by the quantum energy levels of the Nucleons themselves

EM mass-energy is exchanged via W-bosons [with varying energy momenta]

The Photoelectric effect and spectral lines are examples of changes in Kinetic field energy-momenta

Tetryonics 25.04 - KEM quantum levels

deBroglie relationships



Quantum levels
8
7
6
5
4
3
2
1
Q
RE
M+KE
v^2
n^2
v
1.2 e20
ε_0
c^2
M
KE
12
48
108
192
300
432
588
768

rest mass-Matter is velocity invariant

" The electron which is moving in a sine wave circular path, will repeat the same sine wave path in each successive orbit. The sine wave paths in consecutive orbits will exactly overlap. The electron wave reconnects with itself and is in phase with itself. "

An electron bound in a atomic nuclei will trace a toroidal path around the nuclei mapped by the sine wave motion of any point on its charged geometric surface

$$\lambda = \frac{h}{p}$$



$$f = \frac{E}{h}$$

Louis de Broglie

(15 August 1892 – 19 March 1987)

The relativistic energy of Matter in motion is a measure of its standing wave mass-energies, and the object's velocity related kinetic energy and magnetic moment in the form of a KEM wave geometry

$$p = \frac{h}{\lambda} = \frac{h}{2\pi}\frac{2\pi}{\lambda} = \hbar k$$

Although Mathematically correct the illustrative model commonly used to depict the deBroglie relationships is incorrect



RE
M+KE
KE
v
v^2
Q
M



n1
1
KE
1
magnetic moment
M
n2
KE
4
n3
KE
9
n4
KE
16

The greater the KEM field energy level the smaller the quantum wavelength of the KEM field's EM mass

All mass-Matter topologies are Lorentz velocity invariant, only the EM mass-energy content and quantised angular momentum of the Kinetic EM fields vary



n5
KE
25
n6
KE
36
n7
KE
49
n8
KE
64
magnetic moment
M

Copyright ABRAHAM [2008] - all rights reserved

Werner Heisenberg

(5 December 1901 – 1 February 1976)

Electron Positions in Atomic Orbitals

Atomic orbitals are typically described as "hydrogen-like" (meaning one-electron) wave functions over space, categorized by n, l, and m quantum numbers, [as covered in Tetryonic Chemistry] which correspond to the electron's energy, angular momentum, and an angular momentum vector component, respectively

Using Tetryonics as a EM field model, an electron's position and velocity CAN be modelled simultaneously (but any attempt to measure or interact with it, will affect its energy levels)

Quantum Mechanics is a statistical [mathematical] representation of equilateral, charged geometries and EM energy interactions

Erwin Schrödinger

(12 August 1887 – 4 January 1961)

The unique 12 facet topology of Leptons results in the same geometry being presented every 120° rotation of the particle

Leacing to the interpretation that the Lepton disappears and re-appears when being measured

Making accurate measurement of its rotational dynamics incorrect without correct models



Additionally, every radial arm of the Lepton's topology is identical to every other

Including Electric fields and Magnetic dipole orientations

Tetryonics resolves these issues with an accurate 3D model of Leptons

And Quantum Levels thus providing a solid foundation for explaining Electro-Dynamics





Leptons are 6 loop quantum loop inductive rotors

Lepton's are Spin 1 particles that can easily be misinterpreted as 1/2 or 3 quantum spin numbers without the correct physical models to interpret physcical observations on



The charged facia presented changes continously, with a complete fascia change occuring in every 30 degrees of rotation

The magnetic moments created by KEM fields as a result of Matter in motion can be mistaken for a quantum spin

Copyright ABRAHAM [2008] - all rights reserved

Distributions and Uncertainty

A Bell Curve (Normal Distribution) is a mathematical reflection of the integral Planck mass-energy momenta quanta distributions found in all equilateral charge geometries

Probabilities are the square of the Amplitude


Velocity
v
Transverse Bosons [ODD numbers]
Scalar Energy EM waves [SQUARE numbers]
P
E
$\frac{h}{2\pi}$
hv
v²
n-1
n
n-1
[normal distribution]
c²
seconds



All probabilities are re-normalisable and sum to Unity


Momentum
v
ODD transverse Bosons
EVEN longitudinal Photons
1
hv
v²
1 2 3 4 4 3 2 1
boson & photon distribution
c²
seconds

All Matter and EM fields are comprised of equilateral mass-energy momenta and any attempt to measure the system involves the introduction of additional Planck EM quanta into the systems

John Stewart Bell

(28 June 1928 – 1 October 1990)

No physical theory of local hidden variables can reproduce all of the predictions of quantum mechanics.

WRONG

$$\Delta p \; \Delta x \geq \frac{1}{2} \hbar$$

Quantum uncertainty formulation

$$\Delta E \; \Delta t \geq \frac{1}{2} \hbar$$

The more precisely the position is determined, the less precisely the momentum is known in this instant, and vice versa.

Heisenberg, uncertainty paper, 1927

WRONG

Werner Heisenberg

(5 December 1901 – 1 February 1976)

Chance is closely related to the ideas of uncertainty and indeterminacy.
Uncertainty today is best known from Werner Heisenberg's principle in quantum mechanics.
It states that the exact position and momentum of an atomic particle can only be known within certain limits.
The product of the position error and the momentum error is equal to a multiple of Planck's constant of action.
This irreducible randomness in physical processes established the existence of chance and indeterminism in physics

Copyright ABRAHAM [2008] - all rights reserved

Leptronic Self-energies

As the velocity of a charged particle increases
the energy level of its KEM field increases

$$\frac{\overset{\text{KEM field}}{4n\pi}}{c^2}\overset{\text{Energy}}{\underset{\text{momenta}}{\left[\left[\overset{\text{Planck}}{\underset{\text{mass}}{m}}\overset{\text{quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]}}$$

mass

radiant energy per second

$$E/c^2$$

KEM field geometries generated as a product of Matter in motion are Lorentz variant


v
mass
Matter
ε_0
m
π
π
hv
v^2
c

Quantum inductive loops resist changes to energies contained in their equilateral energy fields [inertial mass]

$$\frac{\overset{\text{Matter}}{4n\pi}}{c^4}\overset{\text{Energy}}{\underset{\text{momenta}}{\left[\left[\overset{\text{Planck}}{\underset{\text{mass}}{m}}\overset{\text{quanta}}{\Omega}\underset{\text{velocity}}{v^2}\right]\right]}}$$

Matter

standing-wave energy per second squared

$$E/c^4$$

rest mass-Matter topologies are not affect by changes in velocity [Matter is Lorentz invariant]


Standing-wave energy
12
[12-0]
+
+
+
ε_0
ε_0
ε_0
Matter


magnetic moment
M
KEM
Divergent radiant energy
[KEM field]

The Law of Interaction

The Energy momenta of an electron's KEM field polarises the region surrounding its Matter and creates fields of interaction through the super-positioning of these fields


Divergent radiant energy
[KEM field]
KEM
M
magnetic moment


Standing-wave energy
12
[0-12]
ε_0
ε_0
ε_0
Matter

a particle's self-energy represents the contribution to the particle's energy, or effective mass, due to interactions between the particle and the system it is part of.

$$KEM = Mv^2$$

All Matter topologies are made up of quantum inductive loops which extract energy from any EM field they move through

Matter stores energy in its 3D planar facsia as charged mass-energy

additional to creating the familiar laws of interaction
[opposite attract - similars repel]
the KEM fields of leptons can act as tuned antennas
extracting energy from their environment

KEM fields store energy in their 2D planar EM field as neutral divergent mass-energies

$$E = Mc^4$$

All Matter contains EM energy propagating in a standing wave topology at the speed of light (the source of inertial mass)

Resonant EM fields



Transmitting in order to efficiently recieve
via resonant inductive coupling
of EM fields

1:1
[or other harmonics]



Tuned KEM waves

Quantum inductive antenna fields

Historically, all recieiving antennas have been mechanically tuned to match the sought EM wavelength
But if power is applied to a small wavelength electrostatic topology it creates a KEM field
that produces a much larger, tuned rhombic antenna field

EM waves are hf geometries



Electron's rest Matter stores EM mass-energy in a standing wave



EM bosons have hv geometries



Electrostatic particles of Matter have dual KEM energy fields that can act as resonant antennas

Bosons

All Light is made of transverse EM energy Quanta

EM Field Planck quanta

$$1\pi\,[[\varepsilon_0\mu_0].[m\Omega v^2]]$$

Bosons ElectroMagnetic mass velocity

Energy is quantised

Max Planck

$$E = n.hv$$

All Photons have mass-Energy and momentum

$$\lambda = \frac{h}{p} = \frac{h}{mv}\sqrt{1-\frac{v^2}{c^2}}$$



James Clerk Maxwell

$$\nabla\cdot \mathbf{D} = 4\pi\rho$$

$$\nabla\times \mathbf{H} = \frac{4\pi}{c}\mathbf{J} + \frac{1}{c}\frac{\partial \mathbf{D}}{\partial t}$$

$$\nabla\times \mathbf{E} + \frac{1}{c}\frac{\partial \mathbf{B}}{\partial t} = 0$$

$$\nabla\cdot \mathbf{B} = 0$$

ElectroMagnetic waveforms propagate at the speed of light



Matter is a probabilistic wave of EM particles

p

Louis de Broglie

Erwin Schrodinger

Ψ

Photons

All Light consists of longitudinal harmonic oscillators

EM Field Planck quanta

$$2\pi\,[[\varepsilon_0\mu_0].[m\Omega v^2]]$$

Photons ElectroMagnetic mass velocity

Photons are particles



Albert Einstein

$$E = hf$$

All EM waves and Matter exhibit a Wave-Particle duality

$$i\hbar\frac{\partial}{\partial t}\Psi = \hat{H}\Psi$$

Photonic EM fields

In 1865, James Clerk Maxwell's prediction that light was an electromagnetic wave, [which was confirmed experimentally in 1888 by Heinrich Hertz's detection of radio waves], seemed to be the final blow to particle models of light.

James Clerk Maxwell



(13 June 1831 – 5 November 1879)

EM Field · Planck · quanta

$$2\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Photons · ElectroMagnetic · mass · velocity

All EM mass-energy momenta propagates bi-directionally at c [the speed of light] in a vacuum





$$E = \frac{1}{4\pi\varepsilon_0}\frac{Q}{r^2}$$

$$\frac{K_E}{K_M} = 9e16 \;\frac{\frac{N\,m^2}{C^2}}{\frac{N\,s^2}{C^2}}$$

$$c^2 = 9e16\;\frac{m^2}{s^2}$$

$$c = 299{,}792{,}458\;\frac{m}{s}$$

The speed of light can be calculated using the Electric and Magnetic constants

8.8541e-12

$$\frac{F}{m} \qquad \varepsilon_0 \qquad \frac{A^2\,s^4}{kg\,m^3}$$



$$\frac{H}{m} \qquad \mu_0 \qquad \frac{kg\,m}{A^2\,s^2}$$

[4π]e-7

Electric field strength

The strength of Electric fields is determined by the Electrical Permittivity Constant

$$\varepsilon_0\mu_0 = \frac{1}{c^2}$$

The strength of Magnetic fields is determined by the Magnetic Permeability Constant

$$B = \mu_0 H$$

Copyright ABRAHAM [2008] - all rights reserved

The ElectroMagnetic field geometry of Photons

$$2mv^2 = KE = hf$$



EM Field Energy

$$2\pi\left[\left[\varepsilon_0\mu_0\right].\left[hv^2\right]\right]$$

Photons momenta

Matter is comprised entirely of equilateral electromagnetic energies

EM Field Planck quanta

$$4n\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Matter ElectroMagnetic mass velocity

Matter topologies contain standing-wave EM mass-energies moving at the speed of light



v
p
ε_0
μ_0
c
ε_0
p
v

A photon's momentum is the Square root of its EM waveform energies its velocity of propagation is dependent on the medium through which it is moving

The Speed of Light is the 'maximum' velocity of propagation possible by electrical energies and remains a Universal constant (but it is not a Limit)

Photons are diamond geometry ElectroMagnetic mass-energies

EM Field Planck quanta

$$2\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega 0^2\right]\right]$$

Photons ElectroMagnetic mass velocity

Light cannot have zero velocity or stand still but it is possible (against Einstein's thought experiment) to catch up to a photon and observe its waveform

linear Lorentz contractions

$$\beta = \left[\frac{v}{c}\right]$$

scalar Lorentz corrections

$$\beta^2 = \left[\frac{v^2}{c^2}\right]$$

Any addition of energy quanta to an existing photonic waveform is subject to relativistic Lorentz velocitycorrections to the Photon's KEM waveforms



S
S
μ_0
μ_0
E
ε_0
+
Linear Electric Field propagation
-
ε_0
E
μ_0
μ_0
N
N

ELECTRIC
Flux Fields

EM Field Planck quanta

$$2\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Photons ElectroMagnetic mass velocity



S
S
μ_0
μ_0
E
ε_0
+
Transverse photomagneton
-
ε_0
E
μ_0
μ_0
N
N

MAGNETIC
Dipole fields

Copyright ABRAHAM [2008] - all rights reserved

Photons and Charge bosons

Photons are dual [2π]
neutral charge quanta

$$\underset{\text{Photons}}{2\pi}\Big[\overset{\text{EM Field}}{\underset{\text{ElectroMagnetic}}{[\varepsilon_0\mu_0]}}.\big[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\overset{\text{quanta}}{\underset{\text{velocity}}{v^2}}\big]\Big]$$

Their Electric and Magnetic
fields are orthogonal to each other

**Bosons are transverse charge carriers
they combine to create ElectroMagnetic
photons which are longitudinal charge carriers**

They propagate
in differing mediums
at v/c

$$\underset{\text{EM waves}}{\text{EVEN}\,\pi}\Big[\overset{\text{EM Field}}{\underset{\text{ElectroMagnetic}}{[\varepsilon_0\mu_0]}}.\big[\underset{\text{mass}}{m}\overset{\text{Planck}}{\Omega}\overset{\text{quanta}}{\underset{\text{velocity}}{v^2}}\big]\Big]$$

nπ electromagnetic waves are comprised of
numerous 2π photons of the same wavelength
(save in superpositioned states - White light)

Photons are dual Boson waveforms

$$E = 2h\nu$$



$$E = hf$$

**A moving charge creates a magnetic field throughout space
that is perpendicular to the direction of motion.**



**Photons require NO ether to propagate
they are discrete bundles of EM energy-momenta**



**Similarly, a magnet has an intrinsic neutral electric field
that is perpendicular to its Magnetic Dipole.**

Photon EM strength vectors

Electric field force vectors



When E field flux is at Maximum
B field flux is at Minimum



Electric and Magnetic Fields propogate orthagonally


1
[1-0]
W+
ε0
γ 0
[1-1]
0ε
W-
[1-0]
1

All Photons are comprised of Two W Bosons

Magnetic field force vectors


0
Max
0
0
Max
Max
Max
Max
0
0
Max
0

When B field flux is at Maximum
E field flux is at Minimum

Copyright ABRAHAM [2008] - all rights reserved

Photons are
2π electromagentic masses
possessing:

Frequency
Wavelength
Energy
Momentum
Kinetic Energy
Magnetic Moment
Probabilistic Properties

and can

Refract
Deflect and
Disperse

ZPFs [Bosons] are
1/2 wavelength photons


E
+
N
S
$\frac{hf}{2}$
N
S
E
-
E

$$2v = f$$

2π Planck Constants
Photon energy density


μ_0
μ_0
ε_0
ε_0
μ_0
μ_0

hf



Photon sizes (wavelengths)
change in direct proportion
to the energy content of any
electro-magnetic wave

Wavelength
decreases as total
EM wave Frequency increases

Photons

v
2
ε_0
μ_0
γ
ε_0
μ_0
1
f

$E = hf$

The energy content of any
Electro-Magnetic wave
is directly proportional to
Plancks constant x Frequency

Photons interact with other
photons via their photomagnetons
to form Electro-Magnetic waves

64
Frequency
Number of Cycles per time unit

Bosons in a EM wave

EM waves are comprised of transverse W Bosons

Odd numbers
totaling to a
Square number

$$E = h\nu$$

$$\boxed{2\nu = f}$$

$$E = hf$$

Even numbers
totaling to a
Square number

EM waves are also comprised of longitudinal Photons


Group Phase Velocity
(with respect to E field)
c
c
128
W Boson Frequency (v)
1
3
5
7
9
11
13
15
15
13
11
9
7
5
3
1
1
2
3
4
5
6
7
8
7
6
5
4
3
2
1
Photon Frequency (f)
64
c
c
Group Phase Velocity
(with respect to E field)

$$2h\nu = E = hf$$

[Bosons]

ODD π

(1,3,5,7,9, ...)

Z BOSONS are
1/2 wavelength
quantum levels

$E = h\nu$



vs.

1:1



PHOTONS are
integer wavelength
frequencies

$E = hf$

[Photons]

EVEN π

(2,4,6,8,10, ...)

EM Field Planck quanta

$$1\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Bosons ElectroMagnetic mass velocity

ZPFs are Boson quantums



EM Field Planck quanta

$$\text{ODD}\,\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Bosons ElectroMagnetic mass velocity

Charges are comprised of transverse Bosons

Bosons and Photons have differing EM geometries

EM Field Planck quanta

$$2\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Photons ElectroMagnetic mass velocity

Photons are comprised of Bosons

Photons are EVEN number
Planck geometries



EM Field Planck quanta

$$\text{EVEN}\,\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

EM waves ElectroMagnetic mass velocity

EM waves are comprised of longitudinal Photons


ZPF
Wavelet
f/2
1
[1-0]
Wavelength
λ/2
E
ν
N
S
Frequency
[0-1]
1
Wavelength
λ/2
f/2

Bosons

Charge Carriers
$E = h\nu$

W+ boson

Bosons are half wavelength - non-Integer frequency waveforms due to their odd ZPF numbers


1
[5-4]
Wavelength
λ/2
ν f ν ν f ν ν f ν ν f ν ν
Frequency
c
Group Phase Velocity

$$mv^2 = E = h\nu^2$$

All Bosons are transverse ODD quanta EM masses



$E = h\nu$

$_{ODD}\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$

The interchanging of Quantum number [ν]

$$2\nu = f$$

with Photon Frequency [f] is a cause of confusion

$E = hf$



$_{EVEN}\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$

All Photons are longitudinal EVEN quanta EM masses

Transverse Bosons



8

Boson quanta [ν]

Linear Length

$$2h\nu = E = hf$$

EM Force Carriers
$E = hf$

Photons

Longitudinal Photons



4

Photon Frequency [f]

c **Group Phase Velocity** c

Photonic Energies

$$2p^2 = KE = 2mv^2$$

The equilateral geometries of Quantised Angular Momentum of Planck energy quanta is the source of linear Momentum



Photons are their own 'anti-particles'

$$2hv = E = hf$$

$$E_\gamma = 2mc^2$$

As Photons are 2D EM energy waveforms they should always be referred to as having EM mass-energy equivalence

γ

$$2\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

EM Field Planck quanta

Photons ElectroMagnetic mass velocity

$$2\pi\left[m\Omega v^2\right]$$

Planck quanta

mass velocity

Photons are kinetic energy [KE] wave packets:

KE = (1/2) * m_γ* v²
= 1/2 * (E/c²) * c²
= E/2

KE

Frequency
Number of repeating cycles of energy momenta per time unit



Wavelength decreases as Photon internal Frequency increases

They have momentum [p]:

p = m_γ*v
=(E/c²)*c
= E*c

0
[v-v]

Photons are 2n neutral charge waveforms

Photons are divergent kinetic waveforms

$$KE = \frac{E_{KEM}}{2}$$



$$KE = \frac{1}{2}Mv^2$$



Quantum Harmonic Motion

$$2\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

EM Field
Planck
quanta
Photons
ElectroMagnetic
mass
velocity

The quantum harmonic oscillator is the quantum mechanical analog of the classical harmonic oscillator.

It is one of the few quantum mechanical systems for which a simple exact solution is known.

Single Photons sread out from point sources bi-directionally

Only as part of an EM wave do Photons move past detectors without spreading out over time

The geometry of EM fields is invariant to the energy levels that produces them

Photons are revealed to be quadrature waves with multiple Electric and Magnetic components 90 degrees out of phase

As viewed from the Right-hand side (a LHS oberserver sees opposite Magnetic poles)

The Quantum Harmonic motion of a Photon

ε_0
μ_0
μ_0
μ_0
μ_0
ε_0
Zero + E field
Maximum + E field
Minimum Magnetic dipole
Zero + E field
Maximum Magnetic dipole
Maximum - E field
Minimum Magnetic dipole
Zero - E field
Observes South Magnetic field
Observes North Magnetic field
+
N
−
S

Tetryonics 26.11 - Quantum Harmonic Motion

Copyright ABRAHAM [2008] - all rights reserved



Photonic EM fields

alternating

Electric fields

oscillating

Magnetic fields

c
c
S
+
N
-
270
180
90
0
S
-
N
+

Euler's formula is a natural geometric expression of electromagnetic waves

$$e^{ix} = \cos x + i \sin x$$

$$e^{i\pi} = -1$$

magnetic fields

cos

270
180
90
360
270
180
90
0
90
180
270
360
90
180
270

sin

electric fields

$$e^{i\pi} + 1 = 0$$

1
+
-1
0

Every field geometry in a EM wave
is 90 degrees out of phase
with the E or M field adjacent to it

Tetryonics 26.12 - Photonic EM field phases

Euler's Formula

Euler's formula is often considered to be the basis of the complex number system. In deriving this formula, Euler established a relationship between the trigonometric functions, sine and cosine, and e raised to a power

$$e^{ix} = \cos(x) + i\sin(x)$$

a mathematical description of EM-Energy waveforms

adjacent EM fields are 90-180° out of phase

$$e^{i\pi} = -1$$

$$e^{i\pi} + 1 = 0$$

Leonhard Euler

(15 April 1707 – 18 September 1783)

Positive E-fields are out of phase with Negative fields



$$\sin x = x - \frac{x^3}{3!} + \frac{x^5}{5!} - \ldots$$

$$e^x = 1 + x + \frac{x^2}{2!} + \frac{x^3}{3!} + \frac{x^4}{4!} + \frac{x^5}{5!} + \ldots$$



Magnetic fields are out of phase with Electric fields



$$\cos x = 1 - \frac{x^2}{2!} + \frac{x^4}{4!} - \ldots$$

$$\sin x + \cos x = 1 + x - \frac{x^2}{2!} - \frac{x^3}{3!} + \frac{x^4}{4!} + \frac{x^5}{5!} + \ldots$$



The above geometry is reflective of negative charge energy momenta Planck geometries

the momentum of the nett charged geometry is the Square root of Negative 1





Inverse Square Law

Squared numbers are equilateral geometries

Any point source which spreads its influence equally in all directions
without a limit to its range will obey the inverse square law

0
[v·v]
c
c
KEM
KEM
γ
μ₀
μ₀
ε₀
ε₀
v²
c²
S
r
2r
3r
A
A
A
c
c
p
p
KE
ε₀
ε₀
μ₀
μ₀
μ₀
μ₀
Strength
1/64
1/49
1/36
1/25
1/16
1/9
1/4
1/4
1/9
1/16
1/25
1/36
1/49
1/64
8
7
6
5
4
3
2
1
γ
1
2
3
4
5
6
7
8
Radius

Copyright ABRAHAM [2008] - all rights reserved

mass-Energy momenta

EM Field Planck quanta

$$n\pi\,[[\varepsilon_0\mu_0].[m\Omega v^2]]$$

mass ElectroMagnetic mass velocity

Throughout history Physicists have sought relationships between EM mass-Energy and momenta in an attempt to discern the true Nature of these physical properties



quantised equilateral energy momenta is the key to understandings physics

E

Energy

$$kg\,\frac{m^2}{s^2}$$

$E = mv$

Newton

$E = mv^2$

Leibnitz

$v = \frac{1}{\sqrt{\varepsilon_0\mu_0}}$

Maxwell

de Broglie wavelength

$$\left[\frac{E}{p}\right]$$

Wavelength

Velocity of Light

$$v = \left[\left[\frac{c^2}{\Omega}\right]\cdot\left[\frac{\Omega}{c}\right]\right]$$

f λ

Scalar Frequency

Linear Wavelength

p

Linear momentum

$$kg\,\frac{m}{s}$$

Planck

$E = hv$

Einstein

$E = hf$

de Broglie

h/p

Compton Frequency

$$\left[\frac{E}{h}\right]$$

Planck's Constant

$$kg\,\frac{m^2}{s}$$

Ryberg wavenumber

$$\left[\frac{p}{E}\right]$$

Tetryonics 26.15 - Photonic mass-ENERGY momenta



$$mv^2 = KE = hv^2$$

All Photons contain Energy momenta
and therefore have electromagnetic mass
but they are 'Matterless' geometries

Light cannot have zero velocity
[stand still] but it is possible
to catch up to a photon
and observe its waveform

The Speed of Light is
the maximum speed of Electrical energy
and remains a Universal constant
(but it is not a Limit)



$$hf = E \qquad E = h\frac{c}{\lambda}$$

Frequency
[number of cycles per unit time]

c^2

Celeritas

[Frequency x Wavelength]

EM waves are typically described
through any of their following
three physical properties:

frequency f,
wavelength λ, or
photon energy E

Wavenumber

$$\frac{m}{s}\cdot\frac{s}{m^2}\left[\frac{c}{\Omega}\right]\frac{1}{m}$$

ElectroMagnetic Fields

$$\varepsilon_0\mu_0 = \frac{1}{c^2}$$

$$1.112650056\text{ e-}17\ \frac{s^2}{m^2}$$

Frequency, momentum, and Wavelength
are all related through the geometries of c & c²

λ

$$m\left[\frac{\Omega}{c}\right]\frac{m^2}{s}\cdot\frac{s}{m}$$

Wavelength

Velocity of Light

$$c = \left[\left[\frac{c^2}{\Omega}\right]\cdot\left[\frac{\Omega}{c}\right]\right]$$

$$v = \frac{1}{\sqrt{\varepsilon_0\mu_0}}$$

f λ

Frequency Wavelength

f

$$\frac{m^2}{s^2}\cdot\frac{s}{m^2}\left[\frac{c^2}{\Omega}\right]\frac{1}{s}$$

Frequency

Frequency is the number of neutral quanta sets
repeating per unit time in a EM wave



EM waves frequencies [photon number] change in direct proportion to the energy content of any electromagnetic wave

Irrespective of whether its measured as a transverse or longitudinal electromagnetic wave

Frequency is the inverse
of Charge

$2v = f$

The specific wavelengths and frequencies of energy momenta
in KEM fields form the basis for Spectral emission/absorption lines
[care must be always taken to specify if quanta or photons are being measured]

Bosons are charged transverse energy momenta quanta

$E = hv$

2 charge quanta



Photons are neutral longitudinal energy momenta waveforms

1 Photon

$$E = hf$$

$$f$$

$$\left[\frac{c^2}{\Omega}\right]$$

Frequency

c^2



Frequency
[Number of Neutral ZPF sets per unit of time]

is directly related to the nett
quantised angular momentum
of any space time geometry

λ

Wavelength

Wavelength is a measure of the distance between repetitions of geometric features such as maximums, minimums, or zero-points of Electric and Magnetic fields

$$\lambda$$

$$\left[\frac{\Omega}{c}\right]$$

Wavelength

In physics, the wavelength of a sinusoidal wave is the spatial period of the wave – the distance over which the wave's shape repeats. It is usually determined by considering the distance between consecutive corresponding points of the same phase, such as crests, troughs, or zero crossings, and is a characteristic of both traveling waves and standing waves, as well as other spatial wave patterns.

The concept can also be applied to periodic complex or non-sinusoidal waves



$\tilde{\nu}$

Wavelengths are the inverse of Wavenumbers

λ

For additional quantised energy momenta to be added to any spatial geometry their physical wavelengths must decrease

Lorentz velocity dependent length contractions must be correctly retermed electromagnetic WAVE-length contractions


hf
c
c
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64

λ

Wavelength decreases as total Photon Frequency Increases

$\tilde{\nu}$

Wavelength decreases as the wavenumber Increases


λ
λ
λ
λ
λ
λ
λ
λ
N
S
+
−
c
c

299,792,458
linear metres per second

Copyright ABRAHAM [2008] - all rights reserved



Wavenumbers

Wavenumbers are the spatial equivalent of Frequency

$$\left[\frac{c}{\Omega}\right]$$

ṽ

Wavenumbers are the inverse of Wavelengths

λ

λ

$$\left[\frac{\Omega}{c}\right]$$

Wavelength and Frequency are related to the group velocity of quanta in an EM wave

$$\tilde{\nu} = 1/\lambda$$

Wavenumbers are inversely proportional to Wavelengths

Wavelength decreases as Frequency increases

Wavenumbers decrease as the wavelengths increase

299,792,458

linear metres per second

Tetryonics 26.19 - Wavenumbers


EM Field
Planck
quanta
Bosons
ElectroMagnetic
mass
velocity
EM Field
Planck
quanta
Photons
ElectroMagnetic
mass
velocity
v
p
λ
f
Wavelength
Frequency
Wavenumber
quanta
ν̃
q
KE
d
M
c

$1\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$

Bosons are EM charges

$2\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$

Photons are EM force carriers

$\lambda = {}^{v}/_{f}$

$f = {}^{v}/_{\lambda}$

W

γ

Wavelength decreases as Photon wavenumbers increases

Frequency is the number oscillations per measured timeframe

Transverse energy momenta

$2hv$

$$\left[\left[\frac{\Omega}{c}\right].\left[\frac{c^2}{\Omega}\right]\right]$$

hf

Longitudinal energy momentum

$KE = \frac{E}{2}$

$\frac{1}{2}Mv^2 = KE$

Wavenumbers are inversely proportional to Wavelengths

Wavelength and Frequency are related through Celeritas

$\tilde{\nu} = {}^{1}/_{\lambda}$

$v = f\lambda$

mv

hv^2

linear momentum

scalar energies

Kinetic energy-momenta geometry is 1/2 the equilateral scalar

Tetryonics 26.20 - Kinetic energy-momenta

Copyright ABRAHAM [2008] - all rights reserved

Faraday Rotation

The Faraday effect or Faraday rotation is a Magneto-optical phenomenon, that is, an interaction between light and a magnetic field in a medium. The Faraday effect causes a rotation of the plane of polarization which is linearly proportional to the component of the magnetic field in the direction of propagation.



Discovered by Michael Faraday in 1845,
the Faraday effect was the first experimental
evidence that light and electromagnetism are related

Michael Faraday

(22 September 1791 – 25 August 1867)

Faraday summarized the entire effect as follows:

"Magnetic lines, then, in passing through silicated borate of lead, and a great number of other substances, cause these bodies to act upon a polarized ray of light when the lines are parallel to the ray, or in proportion as they are parallel to it: if they are perpendicular to the ray, they have no action upon it.

They give the diamagnetic the power of rotating the ray; and the law of this action on light is, that if a magnetic line of force be going from a north pole, or coming from a south pole, along the path of a polarized ray coming to the observer, it will rotate that ray to the right-hand; or, that if such a line of force be coming from a north pole, or going from a south pole, it will rotate such a ray to the left hand."

Evan's Photomagneton

A photon has a magnetic dipole.
It is an elementary magnet.
Evans discovery of the photon's
longitudinal magnetic field in
1992 is as significant, as Einstein's
discovery of relativity.

It helps in giving a physical
interpretation of wave mechanics,
two-slit interference
and the Faraday effect,

all accounted for in Tetryonic Theory.

**This experiment determined that
light was affected by magnetic force.
This "magneto-optical effect" was later
termed the Faraday effect.**

**Faraday experimented with other substances
that yielded similar results.**

**The resultant effect he termed "diamagnetism"
concluding that magnetism was an inherent property
of all EM mass-ENERGY-Matter**





Reversing the direction
of Wave propgation
reverses the rotation
effected by the external
magnetic field



Every Photon and EM wave has polarised magnetic
apexes as a result of the Planck quanta constituing them
(creating Magnetic moments)

These Photo-Magnetic Moments allow for the interaction
of Photons with external magnetic fields resulting in
Faraday rotation of Photons and EM fields

Tetryonics 26.21 - Faraday rotation of Photons



Isaac Newton allowed sunlight from a small, circular hole to fall on a prism, producing a rainbow of color. Although the production of a rainbow by a clear crystal was known to the ancients, it was Newton who showed that the colors did not originate in the crystal, but rather were components of sunlight.

Spectral colours

William Herschel:
The Discovery of Infrared Light

White Light is comprised of many coloured corpusles

Refracting Prism

White Light

This array of colors he called a spectrum.

White Light is the result of superpositioned EM waves of differing wavelength Photons

Johann Ritter:
The Discovery of Ultraviolet Light

Thomas Young discovered interference patterns caused by light passing through a narrow slit. Up until this point, the wave theory of light (Huygens) had had nothing convincing to offer in opposition to the particle theory of light (Newton). Now it did, because you cannot explain interference using particles.

The term "light" is often extended to wavelength ranges that the eye cannot detect - to infrared radiation, which has a frequency less than that of visible light, and to ultraviolet radiation, which have a frequency greater than that of visible light.



Light has:

Velocity
Angular momenta
Frequency
Wavelength
Relativistic Energy
Linear momentum
Kinetic Energies
Magnetic Moment

and can

Refract
Reflect
Defract
and
Disperse

All EM waves possess Wavefunctions describing their probabilistic energy properties

Tetryonics 27.01 - EM wavefunctions


Transverse wave Amplitude
1 3 5 7 9 11 13 15 15 13 11 9 7 5 3 1
transverse Boson quanta (v)
1 3 5 7 9 11 13 15 15 13 11 9 7 5 3 1
128
λ λ λ λ λ λ λ λ
γ
64
Photon Frequency (f)
ODD π [[ε0μ0].[mΩv²]]
Bosons
EM Field
Planck quanta
ElectroMagnetic
mass
velocity
W
15 13 11 9 7 5 3 1
1 4 9 16 25 36 49 64
½ 1 1½ 2 2½ 3 3½ 4 3½ 3 2½ 2 1½ 1 ½
Ψ
E
distributions
E = mv²
EVEN π [[ε0μ0].[mΩv²]]
EM waves
EM Field
Planck quanta
ElectroMagnetic
mass
velocity
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1
longitudinal Photon Frequency (f)
Longitudinal wave Amplitude

Bosons are transverse quanta

$E = hv$

BOSONS

ElectroMagnetic waveforms can be measured as either;

transverse EM mass-energies [Bosons] or longitudinal EM mass-energies [Photons]

PHOTONS

EM waveforms

$2v = f$

Group Phase Velocity

$E = hf$

Photons are longitudinal quanta

Copyright ABRAHAM [2008] - all rights reserved

Wavefunction probabilites



Wave Amplitude

Amplitude = bi-directional Momentum

Probability = [Amplitude]^2

In his 1926 paper, Max Born suggested that the wave function
of Schrödinger's wave equation represents
the probability density of finding a particle

Probability of finding a Photon in a electromagnetic wave is the Square of its Amplitude

The de Broglie-Schrodinger wave fields should not to be interpreted as a mathematical descripion of how an event actually takes place in time and space, though, of course, they have reference to such an event.

Rather they are a mathematical description of what we can actually know about the system. They serve only to make statistical statements and predictions of the results of all measurements which we can carry out upon the system.

(Albert Einstein, on Quantum Physics, 1940)


1/1
1
100
1/4
2/4
1/4
2
0.25
0.5
0.25
1/9
2/9
3/9
2/9
1/9
3
0.11
0.22
0.33
0.22
0.11
1/16
2/16
3/16
4/16
3/16
2/16
1/16
4
0.0625
0.125
0.1875
0.25
0.1875
0.125
0.0625
1/25
2/25
3/25
4/25
5/25
4/25
3/25
2/25
1/25
5
0.04
0.08
0.12
0.16
0.20
0.16
0.12
0.08
0.04
1/36
2/36
3/36
4/36
5/36
6/36
5/36
4/36
3/36
2/36
1/36
6
0.027
0.055
0.083
0.111
0.138
0.166
0.20
0.20
0.20
0.20
0.20
1/49
2/49
3/49
4/49
5/49
6/49
7/49
6/49
5/49
4/49
3/49
2/49
1/49
7
0.020
0.040
0.061
0.081
0.102
0.122
0.142
0.122
0.102
0.081
0.061
0.040
0.020
1/64
2/64
3/64
4/64
5/64
6/64
7/64
8/64
7/64
6/64
5/64
4/64
3/64
2/64
1/64
8
0.0156
0.0312
0.0468
0.0625
0.0781
0.093
0.109
0.125
0.109
0.093
0.0781
0.0625
0.0468
0.0312
0.0156

EM radiation patterns

Quantum wavefunctions mathematically model the statistical probability distributions of electromagnetic mass-energy within EM waves


n1
S S
E
+
-
E
N N
1
n2
4
n3
9
n4
16
n5
25
n6
36
n7
49
n8
64
Polar Plot
Electric Field strength
$1/r^2$
$E = h\nu$
$E = hf$
c
c
Rotating radiant EM field geometries produce torodial E fields
$E = mv^2$

EM waves radiate outward at the speed of light along their E fields within scribed radial time dependent spatial co-ordinates

As the energy of an EM wave increases so does its frequency

As the Energy and frequency increase, the Wavelengths of the Photons in a EM wave decreases

Copyright ABRAHAM [2008] - all rights reserved

EM wave geometry



Electromagnetic waves transport energy through empty space, stored in the propagating electric and magnetic fields.

Magnetic field variation is perpendicular to electric field.

A single-frequency electromagnetic wave exhibits a sinusoidal variation of electric and magnetic fields in space.

λ
Electric vector field variation
Magnetic vector field variation

Bosons

$E = \hbar v$

transverse mass-energies

When E fields are at Maximum the B fields are at Minimum (and Vice-a-versa)

Photons

$E = hf$

longitudinal mass-energy frequency

$2v = f$

S
E
N
Max
Max
Max
0
ε₀
μ₀

As the E field reverses polarity the M field reverses its vector dipole

S
S
+
−
E
E
N
N
magnetic vector

E Field oscillations

EM waves are comprised of relativistic photons of mass-energy

$$RE = 2m\frac{v^2}{c^2}$$

EM waves have orthogonal transverse and longitudinal mass-energies

Tetryonics 27.05 - EM wave geometry

Copyright ABRAHAM [2008] - all rights reserved


measured Electrical waveform
E
E
Electric Fields
N
+
S
-
LHS
RHS
electromagnetic waves
and photons
measured Magnetic waveform
A
A
A
Magnetic Fields

ALL EM waves are
comprised of Photons

E-field propagation

**All EM waves
can be modelled
with neutral
charge quanta**

M-field propagation

All Photons travelling in groups
interact via their photomagnetons
to form & maintain EM waveforms

Copyright ABRAHAM [2008] - all rights reserved

Energy momenta in EM waveforms



Linear energy momentum creates physical vector forces

Tesla invested considerable effort into
trying to draw attention to the distinctions
between these 2 forms of EM radiation

Longitudinal EM waveforms are the waves produced by spark gap discharges

Their energy momenta are co-linear with the wave's direction of propagation

Transverse EM waveforms are the waves produced by accelerating charges

Their energy momenta are orthagonal to the direction of wave propagation

Longitudinal emf 'impulses' voltages
provide a mechanical basis for creating
Newton's 'action-at-a-distance' force

Producing Longitudinal EM waves



The short circuiting of voltage potentials or spark gap discharges of electrical energy are two ways to produce longitudinal EM waves

After inventing AC electricity
Nikola Tesla began to investigate
disruptive DC discharges

He noted the deadly power
of the spark discharges and
how they 'stung his face'



Orthagonal Magnetic fields produce reactive inductance fields

Longitudinal Electric fields produce lines of force

and he was convinced that this
form of EM energy would replace his
AC system and provide wireless
energy to the World without losses

He strove to point out that
the load circuits must be
inductively coupled to the
transmission circuits

or a combination of the two

Very large Voltage

High frequency



disruptive discharges

Longitudinal energy momenta

Maxwell's equations lead to the prediction of transverse electromagnetic waves as a means of transefering electrical power (where the wave's Electric fields and Magnetic fields vary perpendicularly to their direction of propagation).

Longitudinal Photons & EM waves are 2D electromagnetic waveforms with co-planar energy momenta that is co-linear with their directions of propagation and that can 'cut like a knife'

Longitudinal energy momenta waves [created by the use of spark gap technologies] are the EM energy forms created and radiated by Stars


v
v
Horizontally Polarized
Vertically Polarized
p
p
Horizontally Polarized
Horizontally Polarized
Vertically Polarized
Vertically Polarized
p
p
Vertically Polarized
Horizontally Polarized
v
v

All photons have 2D planar Electric and Magnetic fields

unpolarised longitudinal EM waves produce concentric diffraction patterns

The longitudinal alignment of E field momenta with their direction of propagation produces 'action-at-a-distance' and can produce material 'faster than light' velocities, if sufficient energies are inputted

Copyright ABRAHAM [2008] - all rights reserved

The velocity of Electrical energy momenta

The velocity of light is the limit for electrical energy acceleration

(the induced velocity of charged particles resulting from electric field energy-momenta interactions)

c

Transverse EM waves
propagate at energy at
the speed of light

Γ

Longitudinal EM waves
can propagate energies & information
in excess of the speed of light

470,912,891 m/s

463,491,072 km/second

288,000 miles/second

$v = [\pi/2]c$

Longitudinal electrical fields
can create near-instantaneous
'action-at-a-distance' EM fields



once established, these fields can
transfer momentum and information
at speeds faster than light through
co-linear impulses of momentum

Wheatstone achieved renown by a great experiment
The measurement of the velocity of electrical Energy in a wire.

He cut the wire at the middle, to form a gap which a spark might leap across, and connected its ends to the poles of a Leyden jar filled with electricity. Three sparks were thus produced, one at either end of the wire, and another at the middle. He mounted a tiny mirror on the works of a watch, so that it revolved at a high velocity, and observed the reflections of his three sparks in it.

The points of the wire were so arranged that if the sparks were instantaneous, their reflections would appear in one straight line; but the middle one was seen to lag behind the others, because it was an instant later. The electricity had taken a certain time to travel from the ends of the wire to the middle.

This time was found by measuring the amount of lag, and comparing it with the known velocity of the mirror. Having got the time, he had only to compare that with the length of half the wire, and he could find the velocity of electricity.

His results gave a calculated velocity of 288,000 miles per second,
i.e. faster than what we now know to be the speed of light

Charles Wheatstone

(6 February 1802 – 19 October 1875)



Wheatstone measured the velocity of LONGITUDINAL electrical energy using spark gaps
[as opposed to transverse waveforms produced by oscillating voltages]

Copyright ABRAHAM [2008] - all rights reserved



'Action at a Distance'

a source of mystery since it was first proposed by Newton
as the basis for Gravitational attraction can be
explained with Teslian Longitudinal waves

Positive longitudinal energy momenta

The ability of one source
to affect the other depends
on their respective potentials

Increasing the Voltage of
the discharges in the same
time duration increases the
total Momenta of the wave

Bi-directional 'action at a distance'

'equal & opposite reactions'

Longitudinal waves are
produced by DC discharges
and are unidirectional

Once established bi-directional
Longitudinal waves act as a 'instantaneous
'rigid conductor' of energy and information
along their entire momenta length

Negative longitudal energy momenta

Tetryonics 27.11 - Longitudinal 'action at a distance'

Copyright ABRAHAM [2008] - all rights reserved

Longitudinal EM waves have their E-fields co-linear with their direction of propagation

Longitudinal Photons & EM waves are produced by disruptive spark gap discharges



M field has NO preferential axial alignment (and can arrive at any angle)

Un-Polarised



M field has an alignment that follows a circular pattern (Clockwise or Counter-clockwise)

Circularly (or Elliptically) Polarised

Longitudinal wave polarisations

emf
Q
voltage

As a convention, the polarization of longitudinal EM waves must be described by specifying the orientation of the wave's magnetic field at a point in space over one period of the oscillation

Longitudinal waves have their linear momenta aligned along their direction of propagation and are extremely efficient at accelerating charges they interact with, creating co-linear accelerations [parallel to their direction of field propagation] - they do not produce charge oscillations along their vector direction of propagation like transverse waves.

Examples of transverse waves include seismic P (primary) waves, and Tesla's longitudinal 'stinging' rays, whose electric fields and energy momenta are both co-linear with each other and parallel to the direction of energy transfer.



M field alignment is along the Vertical axis

Vertically Polarised



M field alignment is along the Horizontal axis

Horizontally Polarised

Tetryonics 27.12 - Longitudinal wave polarisation

Copyright ABRAHAM [2008] - all rights reserved

ElectroMagnetic waveforms

In Teslian longitudinal waves, produced by disruptive EM discharges, the E fields are co-linear with the direction of propagation



After inventing AC electricity Tesla investigated transferring energy through the air via electrostatic longitudinal waves to receiving devices, and noted the differing 'lethality' of the forces produced by these waves



Although comprised of the same energy momenta quanta
EM waves can be formed with Electric fields perpendicular to each other
thus leading to conflicting theories of EM wave propagation



Hertzian transverse waveforms have their EM fields perpendicular to the direction of propagation

In 1887, Heinrich Hertz demonstrated the reality of Maxwell's electromagnetic waves by experimentally generating radio waves in his laboratory

T

Teslian waves transmit Energy in a LONGITUDINAL waveform producing 'action-at-a-distance'

Nikola Tesla

(10 July 1856 - 7 January 1943)

Volt Seconds [per metre²]



108 Mx = 1 J/A = 1 V·s = 1 Wb = 1 T·m2

Heinrich Hertz

(22 Feburary 1857 - January 1 1894)

Hz

Hertzian waves transmit Energy in a TRANSVERSE waveform producing 'radio waves'

Cycles per Second

Soon after Hertz's claim of discovering Maxwell's transverse EM waves Tesla visited him and personally demonstrated the experimental error to him.
Hertz agreed with Tesla and had planned to withdraw his claim, but varying agendas intervened and set the stage for a major rift in the 'accepted' theories

Tetryonics 27.13 - Tesla vs Hertz

Copyright ABRAHAM [2008] - all rights reserved

Transverse EM waves have their E&M fields orthogonal with their direction of propagation



E field has NO
preferential axial alignment
(and can arrive at any angle)

Un-Polarised

Transverse Photons & EM waves are produced by accelerating/oscillating charges



E field has an alignment that
follows a circular pattern
(Clockwise or Counter-clockwise)

Circularly (or Elliptically) Polarised

transverse
Q
frequency

Transverse wave polarisations

By convention, the polarization of EM waves is described by specifying the orientation of the wave's electric field at a point in space over one period of the oscillation

Transverse waves are inefficient propagators of EM energy as they apply their linear momenta tangentially to the charges they interact with, creating lateral accelerations [orthogonal to their direction of field propagation] - they do not accelerate charges along their vector direction of propagation like longitudinal waves.

Examples of transverse waves include seismic S (secondary) waves, and electromagnetic plane wave, whose electric (E) and magnetic (M) fields both oscillate perpendicular to each other and orthogonal to the direction of energy transfer.



E field alignment is
along the Vertical axis

Vertically Polarised



E field alignment is
along the Horizontal axis

Horizontally Polarised

Tetryonics 27.14 - Transverse wave polarisation

EM wave modulations

In telecommunications, modulation is the process of varying one or more properties of a periodic waveform, called the carrier signal, with a modulating signal which typically contains information to be transmitted

Amplitude modulation


Amplitude Modulation

the amplitude of the carrier signal is varied


transverse
waves

the frequency of the carrier signal is varied


Frequency Modulation

Frequency modulation

In addition to planar Hertzian waves
there exists Longitudinal EM waves

Impulse propagation

linear force transfer

As the voltage [energy/coulomb] of longitudinal waves increases their co-linear energy-momenta increase and these forces provide a mechanical basis for near instantaneous 'action-at-a-distance'

Impulse propagation is distinct from pulse modulations


longitudinal
waves

a narrowband analog signal is pulsed over an analog baseband channel


Pulse Modulation

PCM Pulsed modulation **TDM**

Transverse EM wave production

Alternating the Voltage potentials in an electrical circuit produces an Alternating Current
of electrons with Kinetic EM energies reflective of the Time-Energy duration of the AC circuit

Kinetic Energies from motion
(diverge from rest Matter)

**Alternating Voltages provide an electromotive force to Electrically charged Particles
producing tranverse Kinetic Energy fields with orthagonal Magnetic fields**

F=ma

$$\sum \mathbf{F} = \frac{\mathrm{d}\mathbf{p}}{\mathrm{d}t} = m\frac{\mathrm{d}\mathbf{v}}{\mathrm{d}t} + \mathbf{v}\frac{\mathrm{d}m}{\mathrm{d}t}$$



Changes in velocity produce
changes in momentum
which is radiated as Photons

All Stationary charged particles have
NO extrinsic Magnetic moment
ie. They are Electro-static

Charges with constant velocities
produce
REACTIVE [K]EM FIELDS

**Any change to the momentum of a charged particle in motion
requires a corresponding quantum level energy-momentum change through the
emission/absorption of quantised EM mass-ENERGY momenta in the form of W bosons**

Accelerating Charges
produce
RADIANT EM WAVES

Modelling of planar transverse waves

(of varying amplitudes)


Varying signal
Carrier

AM waveform

Amplitude Modulation (AM) works by varying the strength of the transmitted signal in relation to the information being sent.


Upper Side Band
Carrier
Lower Side band

Note: In amplitude modulation each colour planar wave contains differing energy momenta [n1-red to n8-violet]

Tetryonics 27.17 - Amplitude Modulation

Modelling of planar transverse waves
(of the same frequencies)



FM waveform

Frequency modulation (FM) is a form of modulation which conveys information over a carrier wave by varying its frequency (in contrast with amplitude modulation, in which the amplitude of the carrier is varied while its frequency remains constant).

In analog applications, the instantaneous frequency of the carrier is directly proportional to the instantaneous value of the input signal



Note: In Frequency modulation all the planar waves have the same energy momenta [only the number of waves per sec varies]

Copyright ABRAHAM [2008] - all rights reserved

ElectroMagnetic waves

Mathematics alone [without a correct foundational geometry] is insufficent to describe EM radiation
EM waves can be Longitudinal or Transverse with respect to their direction of propagation



Tesla



Maxwell - Hertz

It is now clear [using Tetryonic geometry] that both Tela and Maxwell were correct in their opposing theories of EM waveforms with Tesla proposing Longitudinal waves [from experiment] and Maxwell proposing Transverse waves [from his equations].

The differing opinions on the EM waveforms is shown to be a direct result of the sources of EM wave generation employed in their creation.
After the discovery of the photo-electric effect Hertz and others moved to oscillating charges to produce Transverse [planar] waves
while Tesla continued to investigate and utilise the older spark gap technology to produce Longitudinal waves

Spark Gaps & Plasma discharges
produce
longitudinal EM radiation

Accelerating charges
produce
transverse EM radiation



Action-at-a-Distance

Radio waves

In order to explain and advance our understanding of all EM phenomena we must return to, and utilise, the older discharge technologies

Planar electromagnetic waves

In the physics of wave propagation, a plane wave (also spelled planewave) is a wave whose wavefronts are infinite parallel planes of peak-to-peak amplitude normal to the phase velocity vector.



transverse Radio waves

longitudinal Spectral lines

E
p
E
p
v
E
M
M
E
v
E
p

The phase relationships of their EM energy momenta can all be finally visualised and drawn through Tetryonic theory geometries

[with appropriate radian units]



π/2
90
2π/3
120
π/3
60
π/4
45
π/6
30
π,180
D
0,2π
270
3π/2

bosons $2\pi[h\nu] = hf$ photons



τ/4
90
τ/3
120
τ/6
60
τ/8
45
τ/12
30
τ/2
180
0
τ
270
3/4τ

τ is a more 'natural' radian unit for describing EM waves than π
tau = 2π = 360 degree rotation about a point

Lorentz co-ordinate transforms

In physics, the Lorentz transformation (or transformations) are named after the Dutch physicist Hendrik Lorentz.

The transformations describe how measurements of mass-energies in space and time by two observers are related through mathematics

It was the result of attempts by Lorentz and others to explain how the speed of light was observed to be independent of the reference frame, and to understand the symmetries of the laws of electromagnetism.



All photons are comprised of two dual-sided equilateral Planck quanta



All EM waves are comprised of neutral charge quanta called Photons

Photons are comprised of mass-energies and the term 'mass-less' is not appropriate

Forces add mass-energies to KEM fields resulting in WAVElength changes



Lorentz corrections only apply to velocity related mass-energy changes in EM fields

Linear correction factor

$$\beta = \left[\frac{v}{c}\right]$$

Linear Lorentz boosts produce changes to the velocity and momenta of a system

Scalar correction factor

$$\beta^2 = \left[\frac{v^2}{c^2}\right]$$

As the velocity and momenta of a system changes so does its scalar energies



The Lorentz transformation is a linear transformation

It may include a rotation of space;
a rotation-free Lorentz transformation is called a Lorentz boost.

bosons $2\pi[hv] = hf$ photons

π

As photons are neutral charge mass-energy geometries care must alway be taken in identifying and specifying the planar wavefront polarities and direction of wave propagation when developing co-ordinate systems to describe their motions and resulting electromagnetic properites

τ



The Lorentz transformation is in accordance with special relativity, but was derived well before special relativity, its mathematical development in relativity theory has resulted in erroneous assumptions being accepted as foundational facts.

Copyright ABRAHAM [2008] - all rights reserved

Photoelectron KEM fields

As electrons bound to nuclei are accelerated by external forces their energies of motion are stored in their KEM fields


n1
1
1
1/2
n2
1
1
3
4
1/2
1
1/2
n3
n4

Transverse

quantum level jumps of photoelectrons are created by the ODD quanta geometries of bosons

Longitudinal

linear energy momentum of photoelectrons are stored as EVEN quanta geometries of photons


v
p
KE
hv
v²
c
ε₀
μ₀
M
magnetic
moment
1
3
5
7
9
11
13
15
17
1
4
9
16
25
36
49
64
81
1/2
1
3/2
2
5/2
3
7/2



KEM mass-energies are subject to velocity related Lorentz corrections and produce magnetic moments

Copyright ABRAHAM [2008] - all rights reserved

Kinetics & Photons

The photon has several properties that distinguish it from all other subatomic particles.

It is the only elementary particle wherein a high-energy photon can transform/split into two or more low-energy photons.

A photon is a magnetic dipole. It is an elementary magnet. Evans discovery of the photon's longitudinal magnetic field in 1992 is considered as significant as Einstein's discovery of Relativity.





The Evans photomagneton or the photon's transverse magnetic moment has to be conserved.



Photons can form super-position EM waves



Photons are their own Anti-particle

PAIR PRODUCTION
A photon with sufficient energy can be transformed into a real electron-positron pair.

The EM mass-energy is conserved as per Einstein's equivalence of mass and energy.

The photon's magnetic charge is conserved in the magnetic moments of the created electron-positron pair.



Raised Quantum Level

Absorption

The emission (or absorption) of a photon by an electron, results in a decrease (or increase) in the EM mass-energy [KE & magnetic moment] of the photo-electron's KEM field



Option a
Photon 'spontaneously generates' a pair + anti-particle pair

Option b
Two Photons combine

Compton Scattering

Arthur Compton



(September 10, 1892 - March 15, 1962)

The in-elastic scattering of photons in matter results in a decrease in energy (increase in wavelength) of an X-ray or gamma ray photon and is called the Compton effect.

Part of the energy of the X/gamma ray is transferred to a scattering electron, which recoils and is ejected from its atom (which becomes ionized), and the rest of the energy is taken by the scattered, "degraded" photon.

Compton frequency of photons

$$E = hf = \frac{hc}{\lambda} = mc^2$$

where v = c

Lorentz corrected energies of EM masses in motion

$$n\pi\frac{\left[m\Omega v^2\right]}{c^2}$$



$$p_e = \frac{\sqrt{E^2 - (m_e c^2)^2}}{c}$$

$$p_i = \frac{E_i}{c} = \frac{h\upsilon_i}{c} = \frac{h}{\lambda_i}$$

$$p_f = \frac{E_f}{c} = \frac{h\upsilon_f}{c} = \frac{h}{\lambda_f}$$

Compton frequencies should never be calculated from the total relativistic energies of Matter in motion without proper consideration of the invariant rest Matter

Total relativistic energies of Matter in motion

$$n\pi\frac{\left[m\Omega v^2\right]}{c^4}$$

$$\lambda_f - \lambda_i = \Delta\lambda = \frac{h}{m_0 c}(1 - \cos\theta)$$

deBroglie wavelength formula

Degraded Photon

Pair Production

$$mv^2 = E = \tfrac{1}{2}hf$$

A photon with sufficient energy can be transformed into a real, material electron-positron pair.

The EM mass-energies of the system are conserved as per the equivalence of mass and Energy.


W^0
v
v
$2v = f$
f
+
γ

The photon's magnetic dipole and charges are also conserved (but in differing charge geometries)

Option a

Photon produces 2 particles


n=2.4e20+
[n-n]
E=1.59106e-13+ j.s
f=1.2e20+Hz
E=7.9553e-14+ j
[0-12]
m=8.851e-31 kg
[12-0]
m=8.851e-31 kg
E=7.9553e-14+ j

Photon of sufficently high energy 'spontaneously generates' a pair + anti-particle pair

Option b

Two Photons combine


E=7.9553e-14+ j
n=1.2e20+
f=6e19+ Hz
[n-n]
[0-12]
m=8.851e-31 kg
+ Kinetic Energies
m=8.851e-31 kg
n=1.2e20+
[n-n]
[12-0]
f=6e19+ Hz
E=7.9553e-14+ j

Planck's constant	Energy	electron rest mass-Matter
6.62432672 e-34 kgm^2/s	7.9553 e-14 j	8.8514860 e-31 kg

$$\boxed{n\pi[\overset{\text{Planck}}{\underset{\text{mass}}{m}}\overset{\text{quanta}}{\Omega}\underset{\text{velocity}}{v^2}] = E = T\pi[\overset{\text{Planck}}{\underset{\text{mass}}{m}}\overset{\text{quanta}}{\Omega}\underset{\text{velocity}}{v^2}]}$$

6 e19
photon frequency

1.2 e20
Compton frequency

All pair production - annihilations must follow the mass-Energy-Matter equivalency formula

$$\text{mass} \quad c^2 \xleftarrow{\text{per second}} E \xrightarrow{\text{per second squared}} c^4 \quad \text{Matter}$$

Kinetic Energies

$$KE = \frac{1}{2}Mv^2$$

As velocity increases so does the number of energy momenta quanta per spatial geometry



Photons contain Kinetic energies and momentum

Photonic Energy

$$E_\gamma = 2\pi\overset{\text{Planck quanta}}{\Big[\big[\underset{\text{mass}}{m}\Omega\underset{\text{velocity}}{v^2}\big]\Big]}$$

Kinetic Energy and momenta are all related through Tetryonic geometry

Photons

$$p = \frac{h}{\lambda} = \frac{E}{c}$$




EM field
Planck quanta
2π[[ε₀μ₀][mΩv²]]
Photons
ElectroMagnetic
mass
velocity
μ₀
μ₀
ε₀
ε₀
γ
p
p
v
v
c²


c
c
p
p
KE
ε₀
ε₀
μ₀
μ₀

$$E = hf$$

Momentum

$$\frac{p^2}{2m} = KE = \frac{1}{2}Mv^2$$

As the number of Photons increases so does the Momentum

$$p = n\pi\frac{\overset{\text{Planck quanta}}{\Big[\big[\underset{\text{mass}}{m}\Omega\underset{\text{velocity}}{v^2}\big]\Big]}}{v} = E/v$$

All Photons travel at the 'speed of light' in their medium of transmission

$$p = \frac{E}{c} = \frac{h\nu}{c} = \frac{h}{\lambda}$$

$$p = n\pi\overset{\text{Planck quanta}}{\Big[\big[\underset{\text{mass}}{m}\Omega\underset{\text{velocity}}{v}\big]\Big]}$$

linear energy-momentum

Copyright ABRAHAM [2008] - all rights reserved

Electronic Kinetic Energies

have discrete energy levels within the nucleus and
continuous energy levels in unbound electrons


hv
μ_0
ε_0
Magnetic moment
c^2
v^2
n8
13.525 eV
n7
3.381 eV
Un-named
n6
1.502 eV
Humphreys
n5
0.845 eV
Pfund
n4
0.541eV
Brackett
n3
0.375 eV
Paschen
n2
0.276 eV
Balmer
n1
0.211 eV
Lyman
12
n0
[0-12]
1.2e20
0 eV
Rest Matter
12
[0-12]
RE
12n
hf
0 eV
M_ev^2
[12π m]
n
12
48
108
192
300
432
588
768
p
KE
hv
13.6 eV
v^2

Boson exchanges between quantum levels provides the basis for all electron - photon interactions

0.211 eV / n^2

Relativistic KEM formula must always remove invariant rest Matter PRIOR to Lorentz correction being applied

$$KEM = RE - mc^2$$

As rest Matter is invariant and the Lorentz factor applies to EM waves only

EM Field Planck quanta

$$KEM = 4\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

ElectroMagnetic mass velocity

Electric & Magnetic energies are contained in the KEM field geometry extending from all Matter topologies in motion

$$p/h = \tilde{\nu}$$

Wave numbers are the inverse of Wavelengths

$$h/p = \lambda$$

Frequency and Wavelength are inversely related via the Speed of Light

$$m\Omega v^2/h = f$$

$$2m\Omega v = hf$$

$$M\frac{v^2}{c^2} = KEM = h\frac{v^2}{c^2}$$

Copyright ABRAHAM [2008] - all rights reserved

Photonic energy
momenta of KEM fields


v
R
KE
bosons
photons
ε₀
hv
v²
Mv² =
= hv²
3
Matter
topology

Rydberg's formula is a wavenumber equivalent re-expression of Lorentz's velocity correction formula as it applies to the quantised energy momentum of Photo-electrons bound in atomic nuclei

$$\frac{1}{\lambda} = \frac{R_H}{hc}\left(\frac{1}{n_1^2} - \frac{1}{n_2^2}\right)$$

The difference of two inverse squared KEM energies

Rydberg		Tetryonic
$R\left(\frac{1}{1} - \frac{1}{4}\right)$ .75	=	$R(36 \diagup 48)$ .75

n1 and n2 are integers greater than or equal to 1 such that n1< n2

$$\frac{1}{2}Mv^2 = KE = hcR$$

Whereas Rydberg calculated for wavenumbers using the difference of two inverse squared KEM energies. (inverse wavelengths)

$$\left(\frac{1}{1} - \frac{1}{4}\right)$$

.75

A mathematical solution that works but whose physical mechanics has eluded explanation

Tetryonics obtains the same answers geometrically using the difference of the two KEM energies. (quanta differentials)


1
1
1
α
3
4
36
48
n_1
n_2

(36/48)

.75


n
8
7
6
5
4
3
2
1
Spectral Lines
Lyman
Balmer
Paschen
Brackett
Pfund
Humphries
Un-named
Tetryonic Energy - n squared
n²
Rydberg constant / n²
LEPTONS - 12Δ Tetryonic geometry
Photon Wave number
Rydberg wavenumber
12
48
108
192
300
432
588
768
769+ Free Electron
36
60
84
108
132
156
180
Δ difference per electron level
Tπn²
Kinetic mass-energies
Mv²
KEM
[v-v]
[n-n]
Ψ
Electron Wavefunction

Any changes to the Energy momenta of the electron's KEM field must be reflected in the Energy momenta of the Photo-electrons emitted [absorbed]

$$\pm\Delta hv = KEM_i - KEM_f$$

The difference of two KEM energies

Kinetic Energies of Photoelectrons


12
[0-12]
e⁻
M
12n

rest Matter

Kinetic energies are DIVERGENT from Matter topologies


RE
[n-n]
M
12
[0-12]
12n

Relativistic mass-energies

rest Matter + Kinetic Energies

The total energy of a photon is absorbed into the electron's KEM field geometry



All velocity changes produce changes to mass-energies, momenta and wavefunction relationships

$$\mathrm{KEM} = Mv^2$$

rest Matter is velocity invariant


RE
ℳ
KEM
[n-n]
M
12
[0-12]
12n

$1e19\nu = ℳ$


p
All the mass -energy momenta of Matter in motion is stored in divergent KEM field

$2\nu = f$

6.62943 e -34 J.s

13.5252 eV
2.1669 e -18 J

$$E = h\nu^2$$

3.26874 e15 quanta

KEM fields are velocity variant


v
p
n8
v
1 2 3 4 3 2 1
v²

Δp


1²
n₁
n1
3
5
7
9
11
13
15
R
756
63/64
64
8²
n₂
n8
768

$$4\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

KEM field — EM Field — ElectroMagnetic — Planck quanta — mass — velocity

Electron KEM Quantum levels


v
n1 Ground State
1
3
5
7
9
11
13
15
1²
2²
3²
4²
5²
6²
7²
8²
12
36
60
84
108
132
156
180
R
n
1
6
7
8
hν
c
±Δhν


KEM field energies
1²
α
β
γ
δ
ε
ζ
η
R
spectral lines
12
48
108
192
300
432
588
768

Rydberg spectral transition jumps

Rydberg

$$R_H\left(\frac{1}{1}-\frac{1}{64}\right) = \frac{1}{\lambda} = \mathrm{KEM}\left(\frac{63 \diagup 64}{1}\right)$$

.984375

Tetryonic

.984375

Copyright ABRAHAM [2008] - all rights reserved

Spectral line energies

$1\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$

Charge · EM Field · Planck quanta · ElectroMagnetic · mass · velocity


ZPF
1
+1
[1-0]
ZPF
1
-1
[0-1]

n.hv

Bosons are

Odd number Charge carriers

$\text{ODD}\,\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$

Bosons · EM Field · Planck quanta · ElectroMagnetic · mass · velocity


W+
3
+1
[2-1]
W-
3
-1
[1-2]

Each quantum level transition requires kinetic energies with an ODD number of EM mass-energy momenta quanta [bosons - charge carriers]

In order to transistion between levels for each emission and absorption leptons must release or absorb specific W bosons (neutral Z bosons - photons) for each KEM field change

Pairs of charged W bosons combine to form neutral bosons / photons [EM induction]



γ $2\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$

Photons · EM Field · Planck quanta · ElectroMagnetic · mass · velocity

Photons are

Even number EM force carriers

n.hf



W^0 $\text{EVEN}\,\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$

EM waves · EM Field · Planck quanta · ElectroMagnetic · mass · velocity

KEM field Differentials

Bosonic quantum level changes


Mv²
Absorption
Lyman
36
96
180
288
420
576
756
Balmer
60
144
252
384
540
720
Paschen
84
192
324
480
660
Brackett
108
240
396
576
Pfund
132
288
468
Humphries
156
336
Un-named
180
bosons x12
KEM energies
1
0
12
3
36
48
5
60
108
7
84
192
9
108
300
11
132
432
13
156
588
15
180
768
Mv²
756
720
660
576
468
336
180
576
540
480
396
288
156
Un-named
420
384
324
240
132
Humphries
288
252
192
108
Pfund
180
144
84
Brackett
96
60
Paschen
36
Balmer
Lyman
Emission

All quantum level changes are the result of boson increases or decreases

Copyright ABRAHAM [2008] - all rights reserved

Quantum level differentials

The exact number of Kinetic energy quanta (ZPFs)
required for each bound electron transition within a nucleus

$$\frac{1}{\lambda} = \frac{R_H}{hc}\left(\frac{1}{n_1^2} - \frac{1}{n_2^2}\right)$$

Ryberg calculated this as the wavenumber differerential of two inverse squared energies

$$n_f^2 \qquad \overset{\text{Rydberg}}{\underset{.75}{R_H\left(\frac{1}{1} - \frac{1}{4}\right)}} = \overset{\text{Tetryonic}}{\underset{.75}{R_H\left(36 \diagup 48\right)}} \qquad n_i^2$$

Tetryonic geometry reveals it to be sum of ODD Integer bosons between two squared KEM energies


v
P
KE
Charge
quanta
KEM
energies
ε_0
μ_0
μ_0
M
hv
v²
magnetic moment
3
Matter
topology

Each Quantum level jump within an Atomic Nuclei is discrete and requires an exact number of EM mass-energy quanta

The calculation of the quanta required is historically done utilising Rydberg's Constant and its associated formula

The quantum level [boson] differential equates it to the release or absorption of consecutive ODD number Planck quanta from squared KEM field energy geometries Δ[hv]


hcR_H
hf
v
c
E
R
1
3
5
7
9
11
13
15
1
4
9
16
25
36
49
64

Rydberg's constant is a LINEAR measurement of wavenumbers which can be related to squared KEM energies through the velocity-frequency-wavelength relationship


n
8
7
6
5
4
3
2
1
Lyman
Balmer
Paschen
Brackett
Pfund
Humphreys
Un-named
n²
1
4
9
16
25
36
49
64
Tπn²
12
48
108
192
300
432
588
768
36
60
84
108
132
156
180
Rydberg wavenumbers
KEM
± Δ hv

$R_H = 10{,}903{,}346.28$

$$\left[\frac{c}{\text{SQRT}(756) = 27.4954}\right]$$



$$R_H\left(\frac{1}{n_1^2}-\frac{1}{n_2^2}\right)$$

Rydberg

Spectral Emission/Absorption lines are the result of Boson exchanges due to quantum level changes (resulting from EM quanta emissions or absorption by Leptons)

The differing kinetic mass-energies momenta of each spectral line series can be found using either Rydberg's constant or Tetryonic geometries

Tetryonics

$$\pm\left[\frac{\Delta hv}{KEM}\right]$$

W⁰
KE
ε₀
γ
μ₀
c²
12
±
36
±
60
±
84
±
108
±
132
±
156
±
180
Quanta differential
n1
n2
n3
n4
n5
n6
n7
α 36 48
β 96 108
γ 180 192
δ 288 300
ε 420 432
ζ 576 588
η 756 768
α 60 108
β 144 192
γ 252 300
δ 384 432
ε 540 588
ζ 720 768
α 84 192
β 192 300
γ 324 432
δ 480 588
ε 660 768
α 108 300
β 312 432
γ 468 588
δ 648 768
α 132 432
β 288 588
γ 468 768
α 156 588
β 336 768
α 180 768
Lyman
Balmer
Paschen
Brackett
Pfund
Humphreys
Un-named

Tetryonics 28.11 - Boson differentials

Absorption~Emission lines

Spectral line series

$$E = hf = \frac{hc}{\lambda} = mc^2$$


Non-Nuclear emission/absorption
Non-nuclear Electrons can absorb and release in continuous amounts
24
23
22
21
20
19
18
17
16
15
14
13
12
11
10
9
6,912
Unbound electrons
972
Nuclear Lines
8
7
6
5
4
3
2
1
768
588
432
300
192
108
48
12
Rest Mass electron
E
E
n
Unbound Continuous Spectra
Un-named Series
Humphries Series
Brackett Series
Pfund Series
Paschen Series
Balmer Series
Lyman Series
η
ζ
ε
δ
γ
β
α
Base level electron
v
p
ODD quanta
SQUARED quanta
Quantum levels
KEM field energies
KE
hv
v²
mass-energy
distribution
Matter topology

A photon imparts momentum, Kinetic and Magnetic energies to a bound photo-electron

An electron transition imparts momentum, Kinetic and Magnetic energies to a photon

$$\frac{1}{\lambda} = \frac{R_H}{hc}\left(\frac{1}{n_1^2} - \frac{1}{n_2^2}\right)$$

Ryberg Constant - $1.0903 \times 10^7\ m^{-1}$

Any changes to the energy momenta of bound photo-electrons in atomic nulcei must be reflected in the energy momenta of emitted/absorbed Bosons/Photons

Tetryonics 29.01 - Absorption~Emission Lines

Copyright ABRAHAM [2008] - all rights reserved

Spectral Lines

Spectral lines are the result of interaction between a quantum system (usually atoms, but sometimes molecules or atomic nuclei) and a single photon. When a photon has exactly the right amount of energy to allow a change in the energy state of the system (in the case of an atom this is usually an electron changing orbitals), the photon is absorbed. Then it will be spontaneously re-emitted, either in the same frequency as the original or in a cascade, where the sum of the energies of the photons emitted will be equal to the energy of the one absorbed (assuming the system returns to its original state). The direction and polarization of the new photons will, in general, correlate with those of the original photon.



Planck
quanta
Q
[ν-ν]
ν̃
p
Rybergs constant
n8
n7
n6
n5
n4
n3
n2
n1
Spectral Lines
RE
M+KE
Compton
frequencies
769+
Free Electron
Velocity
12
48
108
192
300
432
588
768
36
60
84
108
132
156
180
Relativisitic Energy differential
per quantum level
KEM Energy differential
per quantum level
Photon
Frequencies
Lyman
Balmer
Paschen
Brackett
Pfund
Humphries
Un-named
M
mass-energy
momenta
Rest Matter
is invariant
KEM fields are
velocity dependent
KE
ε₀
μ₀
de broglie
wavelengths
Quantum Transitions

Spectral lines are highly atom-specific, and can be used to identify the chemical composition of any medium capable of letting light pass through it (typically gas is used). Several elements were discovered by spectroscopic means, such as Helium [04], Rubidium [37], Cerium [58] and Thallium [81]

Spectral lines also depend on the physical conditions of the gas, so they are widely used to determine the chemical composition of stars and other celestial bodies that cannot be analyzed by other means, as well as many other of their physical properties.

Tetryonics 29.02 - Spectral line production

Copyright ABRAHAM [2008] - all rights reserved


Absorption
n²
Tn²
KEM
±Δhv


n1
1²
1
n₁
n2
n3
n4
n5
n1-5
288
25
5²
n₂
300

4 quantum level jump

$$\frac{1}{\lambda} = R\left(\frac{1}{n_1^2} - \frac{1}{n_2^2}\right)$$

.96 KEM


Emission
n²
Tn²
KEM
±Δhv

Photoelectron KEM field changes

The absorption (or emission) of a photon by an electron results in a increase (or decrease) in the Kinetic EM mass-energies of the electron

In the 1880s, Rydberg developed a formula describing the relation between the wavelengths in spectral lines of alkali metals, in turn finding the Rydberg Constant.

The Rydberg constant represents the limiting value of the highest wavenumber (the inverse wavelength) of any photon that can be emitted from the hydrogen atom, or, alternatively, the wavenumber of the lowest-energy photon capable of ionizing the hydrogen atom from its ground state.


v=6.3164 e15
[n-n]
KE=2.093 e-18 j.s
f=3.1582 e15 Hz


v=6.3164 e15
[n-n]
f=3.1582 e15 Hz
KE=2.093 e-18 j.s


Absorption
Raised KEM energies
Emission
12
[0-12]
KE=1.988 e-12 j.s
12n
300n
M=8.851 e-31 kg
KE=7.9553 e-14 j.s
12
[0-12]
12n
12n
M=8.851 e-31 kg
12
[0-12]
M=8.851 e-31 kg
12n
KE=7.9553 e-14 j.s
12n

Kinetic energies of Matter in motion $Mv^2 = \text{KEM} = hv^2$ Spectral line energies of Atomic transitions

Tetryonics 29.03 - Photolectron KEM changes

Copyright ABRAHAM [2008] - all rights reserved

Revealing Rydberg Formula's geometry

The Rydberg formula is used in atomic physics to determine the wavenumber of spectral lines of many chemical elements.

$$\frac{h}{Mv} = \lambda$$

Wavelength is inversely related to Frequency

$$1/\lambda = \frac{R_H}{hc}\left(\frac{1}{n_1^2} - \frac{1}{n_2^2}\right)$$

$$p/h = \tilde{v}$$

Wavenumbers are a inverse measure of Wavelengths

$$p^2 = E = Mv^2$$

Tetryonic geometry can be applied to Kinetic EM field variations produced by the emission and absorption of Photons by electrons in Nuclear orbits to reveal the geometry behind Rydberg's formula

$$p = \frac{E}{v} = hv$$



EM Field — Planck quanta

$$12\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

Photoelectron KEM fields — ElectroMagnetic — mass — velocity



13.525 eV

$$\boxed{Mv = \frac{KEM}{v} = hv}$$

linear momentum — longitudinal quanta

Compton frequency

$$\frac{Mv^2}{h} = f$$

Spectral line emissions reveals Rydberg's formula to be a measure of longitudinal KEM momenta

$$KEM = hcR$$

Wavelengths and Frequency are related through the velocity of propagation

$$\lambda_{KEM} = \frac{f}{v}$$

Hydrogen spectral lines



As the energy of a KEM field increases so does the velocity of its associated Matter

As the KEM field energy increases the KEM wavelength decreases

KEM field mass-energies are subject to Lorentz corrections

KE
c
0 eV
12
1.2e20
n0
hf
eV
12
1.2e20
v
[.2133 eV]
[0.2760 eV]
[0.3757 eV]
[0.5410 eV]
[0.84533 eV]
[1.5028 eV]
[3.3813 eV]
[13.5259 eV]
KE
K shell
n1
L shell
n2
M shell
n3
N shell
n4
O shell
n5
P shell
n6
Q shell
n7
R shell
n8
$\frac{Mv^2}{c^2}$
$\frac{hv^2}{c^2}$
KEM quanta
KEM energies
hv
v^2
c
5.109431785 e13
2.043772714 e14
4.598488607 e14
8.175090856 e14
1.277357946 e15
1.839395443 e15
2.503621575 e15
3.270036343 e15
Hydrogen Spectral Frequencies
Free Electron
13.6eV

Tetryonics 29.05 - Hydrogen Spectral Frequencies

Absorption lines

Increase in photo-electronic energies


hv
Number of quanta per quantum level
Quantum Levels (follow Square rule)
e⁻
36
60
84
108
132
156
180
204
Free electron - continuous spectra
±Δhv

$$\Delta 2hv = E = hf$$

When an electron 'absorbs' a photon of energy momenta it 'jumps' from one energy level to another, dependent on the energy and frequency of the incident photon

$$f = R_H \left(\frac{1}{n_1^2} - \frac{1}{n_2^2} \right)$$


Absorption
n²
Tn²
nf
Lyman
Balmer
Paschen
Brackett
Pfund
Humphries
Un-named
±Δhv

The quantum level of the nuclei determines the ground quantum level of electrons within the nucleus
All transitions within the nulceus are discrete quantum jumps - outside the nucleus all spectra are continuous

KEM A Hydrogen photo-electron can only exist in specific energy levels below 13.525eV within the nucleus (any excess KE results in a unbound electron with KE - velocity)

KE in excess of 13.525 eV results in unbound electron


±Δhv
15 n8 180
13 n7 156
11 n6 132
9 n5 108
7 n4 84
5 n3 60
3 n2 36
1 n1
η 756
φ 576
ε 420
δ 288
γ 180
β 96
α 36
12
φ 720
ε 540
δ 384
γ 252
β 144
α 60
48
ε 660
δ 480
γ 324
β 192
α 84
108
δ 576
γ 396
β 240
α 108
192
γ 468
β 288
α 132
300
β 336
α 156
432
α 180
588
768
-13.525 eV
-10.355 eV
-7.607 eV
-5.283 eV
-3.381 eV
-1.902 eV
-0.845 eV
-0.211 eV
n²
1 K
Lyman
10,903,346
UV spectrum
2 L
Balmer
2,725,836
Visible Spectrum
3 M
Paschen
1,211,482
IR spectrum
4 N
Brackett
681,459
IR spectrum
5 O
Pfund
436,133
IR spectrum
6 P
Humphries
302,870
IR spectrum
7 Q
Un-named
222,517
IR spectrum
8 R
Full atomic levels



KEM fields & quantum jumps

$$Mv^2 = KEM = hv^2$$

$$f = R_H\left(\frac{1}{n_1^2} - \frac{1}{n_2^2}\right)$$

Absorbing a photon of a specific energy momenta frequency results in a jump from one energy level to another

Once 13.525+ eV is reached the electron is ionised and escapes the nucleus

Dropping down from one energy level to another results in a photon of specific energy momenta frequency being emitted producing distinct elemental emission lines

Kinetic Energy

eV/n^2

n9
n8
n7
n6
n5
n4
n3
n2
n1
Free electron
768+
-13.525+ eV
768
-13.525 eV
588
-10.355 eV
432
-7.607 eV
300
-5.283 eV
192
-3.381 eV
108
-1.902 eV
48
-0.845 eV
12
-0.211 eV
Energy absorbed
Hydrogen Absorption
c^2
xM
1
12
3
36
5
60
7
84
9
108
11
132
13
156
15
180
13.525 eV
3.38 eV
1.50 eV
0.84 eV
0.54 eV
0.37 eV
0.27 eV
0.21 eV
Hydrogen Emission
Energy emitted
η
ζ
ε
δ
γ
β
α
Lyman
Spectral Line
Quantum Level

Copyright ABRAHAM [2008] - all rights reserved

Emission lines

Decrease in photo-electronic energies


hv
Number of quanta per quantaum level
Quantum Levels (follow Square rule)
e⁻
36
60
84
108
132
156
180
204
1
3
5
7
9
11
13
15
17
Free electron - continuous spectra
±Δhv

$$\Delta 2hv = E = hf$$

When an electron 'emits' a photon of energy momenta it 'drops' from one energy level to another dependent on the energy and frequency of the ejected photon

$$f = R_H\left(\frac{1}{n_1^2} - \frac{1}{n_2^2}\right)$$


Emission
n²
Tn²
nᵢ
Lyman
Balmer
Paschen
Brackett
Pfund
Humphries
Un-named
±Δhv

The quantum level of the nuclei determines the ground quantum level of electrons within the nucleus
All transitions within the nulceus are discrete quantum jumps - outside the nucleus all spectra are continuous

KEM A Hydrogen electron can only exist in specific energy levels below 13.525eV within the nucleus (any excess KE must be shed as Photons)

KE in excess of 13.525 eV results in unbound electron


±Δhv
15 n8 180
13 n7 156
11 n6 132
9 n5 108
7 n4 84
5 n3 60
3 n2 36
1 n1
η 756
φ 576
ε 420
δ 288
γ 180
β 96
α 36
12
φ 720
ε 540
δ 384
γ 252
β 144
α 60
48
ε 660
δ 480
γ 324
β 192
α 84
108
δ 576
γ 396
β 240
α 108
192
γ 468
β 288
α 132
300
β 336
α 156
432
α 180
588
768
-13.525 eV
-10.355 eV
-7.607 eV
-5.283 eV
-3.381 eV
-1.902 eV
-0.845 eV
-0.211 eV
n²
1 K
2 L
3 M
4 N
5 O
6 P
7 Q
8 R
Lyman
10,903,346
UV spectrum
Balmer
2,725,836
Visible Spectrum
Paschen
1,211,482
IR spectrum
Brackett
681,459
IR spectrum
Pfund
436,133
IR spectrum
Humphries
302,870
IR spectrum
Un-named
222,517
IR spectrum
Full atomic levels

Copyright ABRAHAM [2008] - all rights reserved

Spectral line series

(are produced by changes in linear momentum in photo-electric KEM fields due to atomic transitions of electrons between squared energy levels)


n1
12
1
α
β
γ
δ
ε
ζ
η
7 quantum transitions
12
[0-12]
12n
Lyman
n1-8

Lyman	27.49545417
Balmer	109.9818167
Paschen	247.4590875
Brackett	439.9272667
Pfund	687.3863542
Humphries	989.8363501
Un-named	1,347.277254


n7
49
588
1 quantum transition
12
[0-12]
12n
Un-named
n7-8


n2
4
48
α
β
γ
δ
ε
ζ
6 quantum transitions
12
[0-12]
12n
Balmer
n2-8

Square root of Energy required to transition nuclear quantum levels

$$\left[\sqrt{756}\right].n^2$$


n6
36
432
α
β
2 quantum transitions
12
[0-12]
12n
Humphries
n6-8


n3
9
108
α
β
γ
δ
ε
5 quantum transitions
12
[0-12]
12n
Paschen
n3-8


n4
16
192
α
β
γ
δ
4 quantum transitions
12
[0-12]
12n
Brackett
n4-8


n5
25
300
α
β
γ
3 quantum transitions
12
[0-12]
12n
Pfund
n5-8

Rydberg's Constant

Johannes Robert Rydberg

(November 8, 1854 – December 28, 1919)

$$\tilde{\nu} = \frac{c}{27.49545}$$

$$f = \frac{c^2}{27.49545}$$

$$\lambda = \frac{27.49545}{c}$$

$$p = 27.49545$$


Quantum
Levels
n8
n7
n6
n5
n4
n3
n2
n1
Photon
Wave number
Spectral
Lines
Q
[ν-ν]
$\tilde{\nu}$
p
Rydbergs constant
RE
M+KE
Energy
momenta
Compton
Frequencies
Velocity
Photon
quanta
Boson differential
per Electron KEM field
12
36
48
60
84
108
132
156
180
192
300
432
588
768
Lyman
Balmer
Paschen
Brackett
Pfund
Humphries
Un-named
M
KEM
769+
Free Electron
Leptronic field energy

$$R_H = \frac{c}{27.49545}$$

$1.0903346.28 \times 10^{7}$ m-1

$$\lambda = v/f$$

Using the Tetryonic model of a photo-electron and its associated quantum KEM energy levels we see that Rydberg's constant is a linear measure of the photo-electronic KEM field - and in turn directly related to its scalar energy-momenta through 'c'

$$R_H\left(\frac{1}{n_1^2} - \frac{1}{n_2^2}\right)$$

Currently accepted value - 10,973,731 m^{-1}

Rydberg's Constant can be shown to be the square root of the total number of quanta required to transition a n1 electron to n8
(the highest quantum level possible in elemental nuclei)
as per Planck's heat law

Tetryonic theory value - 10,903,346 m^{-1}

$$p^2 = KEM = Mv^2$$

Quantum Jump

The energy momenta of emitted photons is a function of the photo-electron's KEM wavefunction

27.49545

KE
Photons

$$Mv^2 = KEM = hcR_H$$

Wavenumbers and Planck's Law

Wavenumbers are revealed to be the number of quanta [nhv] required for a photo-electron to transition between specific quantum levels divided by the speed of light [c]



Balmer spectral lines
[absorption]



Max Karl Ernst Ludwig Planck

[April 23, 1858 – October 4, 1947]

Balmer spectral lines
[emission]





$$E = n[h\nu]$$

Wavenumbers are the number of Planck quanta required to reach a specific energy level

$$E = hc\tilde{\nu}$$

Photo-electrons emit and absorb photons to create blackbody radiation



Planck's law describes the electromagnetic radiation emitted by a black body in thermal equilibrium at a specific temperature



$$\Delta[nh\nu]$$

SQUARED energy levels have ODD numbered quanta in each energy level [bosons]



$$Mv^2 = \mathbf{KEM} = hf$$

As KEM energies increase wavenumbers also increase and the wavelengths decrease





Spectral lines can be understood in quantum theory as differences between energy levels and proportional to wavenumber, frequency or wavelengths

Copyright ABRAHAM [2008] - all rights reserved

Kinetic mass-energy momenta relationships

Photons are comprised of dual EM masses

Photons are KEM energy-momenta propagating at the speed of Light

EM Field Planck quanta

$2\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$

Photons ElectroMagnetic mass velocity

kg **m**

p $kg\frac{m}{s}$

f

Q

Photons have neutral charge

[ν-ν]

RE

Photons are Lorentz variant

$\frac{1}{s}$ *f*

v $\frac{m}{s}$



Frequency and Wavelength are related by the natural speed of Energy

c

c

'c' is the natural speed of Energy in free space

m λ

c $\frac{m}{s}$

M

Photons have zero EM rest mass

KE

Photons are all Kinetic Energy

KG **0**

E $kg\frac{m^2}{s^2}$

$$\Delta 2h\nu = E = hf$$

Planck Einstein

c^2

1 second

Photons are 'Matterless' 2D neutral charge mass-energy geometries

Kinetic Energy is 1/2 the energy created by Matter topologies in motion

Tetryonics 29.12 - Kinetic mass-energy relationships

Copyright ABRAHAM [2008] - all rights reserved

Relativistic Lorentz corrections

Hendrik Lorentz

(18 July 1853 – 4 February 1928)

$$\sqrt{1-\beta^2}$$

$$E=\frac{mc^2}{\sqrt{1-\frac{v^2}{c^2}}}$$

$$\sqrt{1-\left(\frac{v}{c}\right)^2}$$

The Lorentz transformation was originally the result of attempts by Lorentz and others to explain how the speed of light was observed to be independent of the reference frame and later expanded upon in an attempt to understand the creation of emfs in magnets and symmetries in electromagnetic forces

Einstein inlcuded the transformation in his theory of Special relativity [SR].

The Lorentz transformation supersedes the Galilean transformation of Newtonian physics, which assumes an absolute space and time.

According to special relativity, the Galilean transformation is a good approximation only at relative speeds much smaller than the speed of light.

Tetryonics expands upon all of this revealing this relationship as a result of the geometry of electromagnetic mass-energies in motion

rest mass-Matter

Energy

Planck quanta

$$\frac{4n\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

momentum

spatial co-ordinate system

Matter is EM energy propagating at the 'speed of Light' In a standing wave energy topology

One of the greatest mistakes in relativistic mechanics is the application of Lorentz corrections to Matter.

It stems from there being no definition and enforced differentiation between EM mass and Matter



$$m = \frac{E}{c^2}$$

2D planar fields are relativisitic

radiant EM mass geometry

$$\frac{m}{c^2} = M$$

standing-wave Matter topology

3D standing-waves are velocity invariant

$$\frac{E}{c^4} = M$$

mass is a property of Matter - Matter is not a property of mass [they are directly related throught the velocity of light]

$$\beta = \left[\frac{v}{c}\right]$$

velocity is a result of vector forces

All 2D energy waveforms propagate at the 'speed of Light'



$$\beta^2 = \left[\frac{v^2}{c^2}\right]$$

The Kinetic Energy of Matter in motion is directly related to the square of the velocity

$$\gamma \equiv \frac{c}{\sqrt{c^2-v^2}} = \frac{1}{\sqrt{1-\beta^2}} = \frac{dt}{d\tau}$$

The 'speed of Light' is a EM constant and is the limiting velocity acheivable by the electrical acceleration of Matter

Spectral Energy relationships

$$kg\frac{m^2}{s^2} \quad E = p^2$$


p²
p
Ω
m
hv²
Mv²

Scalar EM mass -energy momenta


v
1
n1
n2
n3
n4
n5
n6
n7
n8
36
96
180
288
420
576
756
R
β
c

Lorentz corrected EM mass-energies

$$KEM = \frac{mv^2}{c^2}$$


v
KE
hv
magnetic
moment
v²

$$\boxed{Mv^2 = \underset{13.525\ eV}{KEM} = hcR_H}$$

All Spectral line emissions and absorptions produce changes in KEM energies, Angular momentum, Linear momentum, Frequency and Wavelengths

Linear

$$\left[\frac{\Omega}{c}\right] = \lambda$$

de Broglie wavelengths



The 'speed of Light' is the maximum velocity acheivable by electrical energies

Scalar

$$f = \left[\frac{c^2}{\Omega}\right]$$

Compton frequencies

Spectral line photon production



At no time does the 3D rest Matter-energy content of the electron change


12
[0-12]
e-
n8
1.2e20

An electron transitioning from n8 to n7


12
[0-12]
e-
n7
1.2e20


v
1
0.21 eV
12
3
0.84 eV
36
5
1.9 eV
60
7
3.38 eV
84
9
5.28 eV
108
11
7.60 eV
132
13
156
15
180
spectral bosons
KEM field energies
KE
$h\nu_f$
$h\nu_i$
$h\nu^2_f$
$h\nu^2_i$
1
2
3
4
3
2
1
c²

Exchange quanta $Mv^2 = \text{KEM} = hv^2$ Spectral lines

$$E = hf$$

As the 3D rest Matter of any particle in motion is Lorentz invariant any changes in velocity-momentum produces changes to the mass-energy momenta content of the 2D KEM field [boson changes are the difference of two squares]

Spectral line wavenumbers

Tetryonic
$$\left(\frac{15 \diagup 49}{64}\right)$$
.0047

$$1/\lambda$$

Rydberg
$$R\left(\frac{1}{49}-\frac{1}{64}\right)$$
.0047



Does so by emitting Kinetic Energy quanta



λ	19,174.54158	nm
ṽ	52,152.48541	m-1
f	1.563492179 x 10 ¹³	Hz
E	0.064693658	eV
Ω	5,748.382952	m²/s

Which are released as photons of specific energy-momenta

un-named

of specific wavelengths (Spectral Lines)

Tetryonics 29.15 - Spectral photon production

Copyright ABRAHAM [2008] - all rights reserved

Wavenumbers

are the number of energy momenta wavelengths per unit distance

m

n1 2



48

1 quantum level jump

α

n1 3



108

2 quantum level jump

β

n1 4



192

3 quantum level jump

γ

m

$\tilde{\nu}$

the wavenumber (also wave number) is the spatial frequency of a wave, either in quanta per distance or nπ radians per unit distance.
It can be envisaged as the number of specific wavesets that exist over a specified distance

$1/\lambda$

n1 5



300

4 quantum level jump

δ

n1 6



432

5 quantum level jump

ε

m^{-1}

n1 7



588

6 quantum level jump

ζ

n1 8



768

7 quantum level jump

η

For electromagnetic radiation in vacuum, wavenumber is proportional to frequency and to photon energy

Bosons, Photons and quantums of energy momenta

$\tilde{\nu}$ WAVENUMBERS

$E = \Sigma h\nu$


RE
n
KEM
[n-n]
M
12
[0-12]
12n

$KEM = Mv^2$

LINEAR MOMETNUM **p**

γ Spectral lines are produced $\Delta m\Omega v = \Delta mv = \Delta p$ by accelerating electrons **a**

equilateral energy momenta is the foundation of all quantum EM wave-functions

ODD distribution $2\nu = f$ **SQUARED distribution**


n²
α
β
γ
δ
ε
ζ
η
n
n²

Spectral lines

Bosons

$h\nu$


v
Δhν
p
3
2
2²
36
5
3
3²
60
7
4
4²
84
9
5
5²
108
11
6
6²
132
13
7
7²
156
15
8
8²
180
m
hν
1
2
3
c
3
2
1
Mv²

EVEN distribution

hf

Photons

Kinetic energies

$h\nu^2$


v²
12
KEM
p
48
108
192
KE
300
432
588
768
v²
F

energy momenta

Copyright ABRAHAM [2008] - all rights reserved

Spectral Energy - Planck relationships

$$\frac{E}{v^2} = m\Omega = \frac{E}{c^2}$$

deBroglie wavelength λ

p MOMENTUM

Wave number $\tilde{\nu}$

f Frequency

ENERGY E

v^2 Compton Frequency


Planck quanta differential
spectral mass-energies
h
m
v
1
3
5
7
9
11
13
15
12
36
60
84
108
132
156
180
p
0.21 eV
0.84 eV
1.9 eV
3.38 eV
5.28 eV
7.60 eV
10.35 eV
13.52 eV
KE
v
v²
1 2 3 4 3 2 1
quantum distributions
c²

Applying mass to spectral energy relationships reveals the familiar quantum mechanical wave-particle relationships and properties

	2D waves						3D Matter	
EM wave wavelength	Ω / c	=	planck constant	h / p	linear momentum	=	$m\Omega / mc$	deBroglie wavelength
EM wavenumber	c / Ω	=	linear momentum	p / h	planck constant	=	$mc / m\Omega$	Matter waves
EM wave Frequency	c^2 / Ω	=	kinetic energy	E / h	planck constant	=	$mc^2 / m\Omega$	Compton Frequency

Thus reinforcing the geometric role of quantised angular momenta in Planck's constant

Tetryonics 29.18 - Spectral energy relationships

White Light

White light is radiated by our SUN and all the stars throughout the Universe.
In fact, most of the energy radiated by the sun is within the visible spectrum, which is most likely why we see this range.

Incandescence is the greatest known generator of white light. The verb incandesce means to glow white. This is also referred to as black-body radiation.

The color of a black body object at high temperatures causes it to glow, and the waves emitted include visible light.
In addition to the sun and common light bulb, molten materials such as metal or glass also glow incandescently.

Hydrogen
Oxygen
Sulfur

Spectroscopy



Planck's Heat Law



Most light sources are thermal, meaning the type of radiation
they emit is a characteristic of the source's temperature.



White light can be
decomposed or reconstituted
by passing it through
a Prism

[Spectroscopy]

White light is comprised
of many photons of varying
frequencies and wavelengths

Each colour of light has
a specific frequency
and wavelength





Until Newton's work proved otherwise, most scientists believed that white was the fundamental color of light; and that other colors were formed only by adding something to light.
Newton demonstrated this was not true by passing white light through a prism, then through another prism. If the colors were added by the prism, the second prism should have added further colors to the single-colored beam. Since the single-colored beam remained a single color, Newton concluded that the prism merely separated the colors already present in the light.

White light is the result of superpositioning of the visible colors [varying frequencies] of EM waves

Copyright ABRAHAM [2008] - all rights reserved

Max Karl Ernst Ludwig Planck



(April 23, 1858 – October 4, 1947)

White light



complex fourier waveform

is comprised of superpositioned differing spectral wavelength photons

Johannes (Janne) Robert Rydberg

(November 8, 1854 – December 28, 1919)

spectral lines & colour

bosons

photons


Lyman
Balmer
Paschen
Brackett
Pfund
Humphreys
un-named
continuous

Instantaneous measurement of energy momenta released

Time measurement of released waveforms [photons]

created by the fractional release of equilateral KEM field energy momenta

Tetryonics 29.20 - White light & spectral Colours

Lyman spectral lines


free electron
>13.525 eV
KE
S
N
n8⁺
Δv
Σv
Mv²
Emission
n8
η
768
180
15
[n1-8]
756
[n8-1]
15
n7
ζ
588
156
13
[n1-7]
576
[n7-1]
13
n6
ε
432
132
11
[n1-6]
420
[n6-1]
11
n5
δ
300
108
9
[n1-5]
288
[n5-1]
9
n4
γ
192
84
7
[n1-4]
180
[n4-1]
7
n3
β
108
60
5
[n1-3]
96
[n3-1]
5
n2
α
48
36
3
[n1-2]
36
[n2-1]
3
n1
12
p
d
+
−
Absorption
Lyman
spectral line
ground energy level

n1
Ground State


Lyman
α
β
γ
δ
ε
ζ
η
v
Δv
Σv
KEM
48
108
192
300
432
588
768
36
60
84
108
132
156
180
36
96
180
288
420
576
756
2
3
4
5
6
7
8
hv
c
v²
Mv²
hv,
R,
β,
p,
KE
Planck, Rydberg, Lorentz, Newton, Leibniz

-13.5252 eV

$$KEM = \frac{hf}{n^2}$$

v
nl
KEM
S
N
12
[0-12]
1.2e20

K shell

91.714 nm

$$KEM = \frac{hcR}{n^2}$$

$$m.\begin{bmatrix} \Omega/v \\ v/\Omega \\ c^2/\Omega \\ v^2/c^2 \end{bmatrix}$$

λ	91.71496292	nm	h/p
ṽ	10,903,346.28	m-1	p/h
f	$3.268740982 \times 10^{15}$	Hz	E/h
E	13.52528	eV	hf
Ω	27.49545417	m²/s	

ground KEM energies

equilateral energy momenta is the foundation of all quantum EM wave-functions

Copyright ABRAHAM [2008] - all rights reserved

As photo-electrons transition between Mv squared KEM field energy levels in atomic nuclei they release specific [Δhv] W bosons


-13.5252 eV
v
nl
KE
S
N
12
[0-12]
1.2e20
91.714 nm


λ
n
Absorption
n²
Mv²
KEM
Lyman
Δv
v
f

Lyman spectral series

α	122.28	n1-2
β	103.18	n1-3
γ	97.83	n1-4
δ	95.53	n1-5
ε	94.33	n1-6
ζ	93.62	n1-7
η	93.17	n1-8

UV spectrum


λ
n
Emission
n²
Mv²
KEM
Lyman
Δv
v
f

K shell

Δν

KEM

n1~2



48

1 quantum level jump

n1~3



108

2 quantum level jump

n1~4



192

3 quantum level jump

n1~5



300

4 quantum level jump

n1~6



432

5 quantum level jump

n1~7



588

6 quantum level jump

n1~8



768

7 quantum level jump

Lyman series energy momenta



M
3/4
n1~2
36
48
α
nl
3
[0.75]

M
8/9
n1~3
96
108
β
nl
3
5
[0.88888]

M
15/16
n1~4
180
192
γ
nl
3
5
7
[0.9375]

M
24/25
n1~5
288
300
δ
nl
3
5
7
9
[0.96]

nl
Ground State

Lyman
α
β
γ
δ
ε
ζ
η
v
Δv
Σv
KEM
12
2
3
4
5
6
7
8
36
60
84
108
132
156
180
3
5
7
9
11
13
15
2^2
3^2
4^2
5^2
6^2
7^2
8^2
36
96
180
288
420
576
756
48
108
192
300
432
588
768
hv
v
c
v^2
Mv^2

Planck quanta	Free electron 13.525 eV /n^2 ionsation energy		KEM field
	n8	η	768
756			
	n7	ζ	588
576			
	n6	ε	432
420			
	n5	δ	300
288			
	n4	γ	192
180			
	n3	β	108
96			
	n2	α	
36			
	n1	Lyman Spectral Line ground level	12

M
35/36
n1~6
420
432
ε
nl
3
5
7
9
11
[0.972222222]

M
48/49
n1~7
576
588
ζ
nl
3
5
7
9
11
13
[0.979591836]

M
63/64
n1~8
756
768
η
nl
3
5
7
9
11
13
15
[0.984375]

accelerating electrons $\Delta p = \Delta Mv = hf$ produce spectral lines

Tetryonics 30.03 - Lyman series energy momenta

Copyright ABRAHAM [2008] - all rights reserved

Lyman Series

$\Delta h\nu$ = KEM = hcR

Tetryonic — 13.525 eV — Rydberg



63/64

.9843

λ	93.17075598	nm
$\tilde{\nu}$	10,732,981.5	m-1
ƒ	$3.217666905 \times 10^{15}$	Hz
E	13.31395504	eV
Ω	27.93188995	m²/s

$R\left(\frac{1}{1}-\frac{1}{64}\right)$ .984375

48/49

.9795

λ	93.62569132	nm
$\tilde{\nu}$	10,680,829.01	m-1
ƒ	$3.202031983 \times 10^{15}$	Hz
E	13.24926138	eV
Ω	28.06827615	m²/s

$R\left(\frac{1}{1}-\frac{1}{49}\right)$ .9795

35/36

.9722

λ	94.33539043	nm
$\tilde{\nu}$	10,600,475.55	m-1
ƒ	$3.177942822 \times 10^{15}$	Hz
E	13.14958523	eV
Ω	28.28103857	m²/s

$R\left(\frac{1}{1}-\frac{1}{36}\right)$ .9722

24/25

.9600

λ	95.53641971	nm
$\tilde{\nu}$	10,467,212.43	m-1
ƒ	$3.137991343 \times 10^{15}$	Hz
E	12.98427616	eV
Ω	28.64199809	m²/s

$R\left(\frac{1}{1}-\frac{1}{25}\right)$ .96

15/16

.9375

λ	97.82929378	nm
$\tilde{\nu}$	10,221,5587.14	m-1
ƒ	$3.064444671 \times 10^{15}$	Hz
E	12.67995718	eV
Ω	29.32544445	m²/s

$R\left(\frac{1}{1}-\frac{1}{16}\right)$ .9375

8/9

.8888

λ	103.1793333	nm
$\tilde{\nu}$	9,691,863.362	m-1
ƒ	$2.90554754 \times 10^{15}$	Hz
E	12.02247792	eV
Ω	30.93228594	m²/s

$R\left(\frac{1}{1}-\frac{1}{9}\right)$ .888

3/4

.7500

λ	122.2866172	nm
$\tilde{\nu}$	8,177,509.712	m-1
ƒ	$2.451555737 \times 10^{15}$	Hz
E	10.14396575	eV
Ω	36.66060536	m²/s

$R\left(\frac{1}{1}-\frac{1}{4}\right)$ .75

ground KEM energies

$$m.\begin{bmatrix} \Omega/v \\ v/\Omega \\ c^2/\Omega \\ v^2/c^2 \end{bmatrix}$$

λ	91.71496292	nm	h/p
$\tilde{\nu}$	10,903,346.28	m-1	p/h
ƒ	$3.268740982 \times 10^{15}$	Hz	E/h
E	13.52528	eV	hf
Ω	27.49545417	m²/s	

changing energy momenta produces specific frequency spectral lines

Copyright ABRAHAM [2008] - all rights reserved

Balmer spectral lines



free electron

>13.525 eV

$n8^+$

n8	ζ
n7	ε
n6	δ
n5	γ
n4	β
n3	α
n2	Balmer spectral line ground energy level
n1	



Δv			Σv			Mv²
						768
180	15	[n2-8]	720	[n8-2]	15	
						588
156	13	[n2-7]	540	[n7-2]	13	
						432
132	11	[n2-6]	384	[n6-2]	11	
						300
108	9	[n2-5]	252	[n5-2]	9	
						192
84	7	[n2-4]	144	[n4-2]	7	
						108
60	5	[n2-3]	60	[n3-2]	5	
						48

Emission

Absorption

n2

Ground State



Balmer

	Δv		Σv	KEM
		48		
α	60	3	60	108
β	84	4	144	192
γ	108	5	252	300
δ	132	6	384	432
ε	156	7	540	588
ζ	180	8	720	768

hv, R, β, p, KE

Planck, Rydberg, Lorentz, Newton, Leibniz

-3.38125 eV

$$KEM = \frac{hf}{n^2}$$

V
n2
KE
S
N
12
1.2e20

L shell

366.859 nm

$$KEM = \frac{hcR}{n^2}$$

$$m.\begin{bmatrix} \Omega/v \\ v/\Omega \\ c^2/\Omega \\ v^2/c^2 \end{bmatrix}$$

λ	366.8598517	nm	h/p
ṽ	2,725,836.571	m-1	p/h
f	$8.171852456 \times 10^{14}$	Hz	E/h
E	3.381321915	eV	hf
Ω	109.9818167	m²/s	

ground KEM energies

equilateral energy momenta is the foundation of all quantum EM wave-functions

As photo-electrons transition between Mv squared KEM field energy levels in atomic nuclei they release specific [Δhv] W bosons


-3.38125 eV
v
n2
KE
S
N
12
(0-12)
1.2e20
366.859 nm


λ
n
8
7
6
5
4
3
Absorption
n²
Mv²
KEM
Δv
v
f

Balmer spectral series

α	660.34	n2-3
β	489.14	n2-4
γ	436.73	n2-5
δ	412.71	n2-6
ε	399.46	n2-7
ϕ	391.31	n2-8

Visible Spectrum


λ
n
8
7
6
5
4
3
Emission
n²
Mv²
KEM
Δv
v
f

L shell

Δv

KEM



60

108

1 quantum level jump


n2~4
β
R
5
9
7
16

144

192

2 quantum level jump


n2~5
γ
R
5
9
7
16
25

252

300

3 quantum level jump



384

432

4 quantum level jump



540

588

5 quantum level jump



720

768

6 quantum level jump

Tetryonics 31.02 - Balmer quantum transitions

Balmer series energy momenta


M
5/9
n2
n2~3
5
[0.5555]
60
108
α


M
12/16
n2
n2~4
5
7
[0.75]
144
192
β


M
21/25
n2
n2~5
5
7
9
[0.84]
252
300
γ


n2
Ground State
Balmer
Δv
Σv
KEM
α
β
γ
δ
ε
ζ
3
4
5
6
60
84
108
132
156
180
60
144
252
384
540
720
108
192
300
432
588
768
hv
c
Mv²
Planck quanta
Free electron
3.381 eV/n²
ionsation energy
KEM field
n8
ζ
720
768
n7
ε
540
588
n6
δ
384
432
n5
γ
252
300
n4
β
144
192
n3
α
60
108
n2
Balmer Spectral Line ground level
48
n1


M
32/36
n2
n2~6
5
7
9
11
[0.88888888]
384
432
δ


M
45/49
n2
n2~7
5
7
9
11
13
[0.918367346]
540
588
ε


M
60/64
n2
n2~8
5
7
9
11
13
15
[0.9375]
720
768
ζ

accelerating electrons $\Delta p = \Delta M v = hf$ produce spectral lines

Copyright ABRAHAM [2008] - all rights reserved



Balmer Series

$$\Delta h\nu = \mathrm{KEM} = hcR$$

Tetryonic — 3.381 eV — Rydberg

60/64

.2343

λ	391.3171751	nm
ṽ	2,555,471.1785	m-1
f	7.661111677 x 10¹⁴	Hz
E	3.169989296	eV
Ω	101.1879511	m²/s

$R\left(\frac{1}{4}-\frac{1}{64}\right)$ .2343

45/49

.2295

λ	399.4696163	nm
ṽ	2,5033,319.299	m-1
f	7.50476246 x 10¹⁴	Hz
E	3.105295637	eV
Ω	101.0027092	m²/s

$R\left(\frac{1}{4}-\frac{1}{49}\right)$ .2295

32/36

.2222

λ	412.7173331	nm
ṽ	2,422,965.84	m-1
f	7.26386885 x 10¹⁴	Hz
E	3.00561948	eV
Ω	97.76161853	m²/s

$R\left(\frac{1}{4}-\frac{1}{36}\right)$ .2222

21/25

.2100

λ	436.7379187	nm
ṽ	2,289,702.719	m-1
f	6.864356063 x 10¹⁴	Hz
E	2.840310409	eV
Ω	92.38472601	m²/s

$R\left(\frac{1}{4}-\frac{1}{25}\right)$ .21

12/16

.1875

λ	489.1464689	nm
ṽ	2,044,377.428	m-1
f	6.128889542 x 10¹⁴	Hz
E	2.535991437	eV
Ω	82.48636251	m²/s

$R\left(\frac{1}{4}-\frac{1}{16}\right)$ .1875

5/9

.138

λ	660.347733	nm
ṽ	1,514,353.65	m-1
f	4.539918031 x 10¹⁴	Hz
E	1.878512175	eV
Ω	61.10100927	m²/s

$R\left(\frac{1}{4}-\frac{1}{9}\right)$ .138

m.	Ω/v	λ	366.8598517	nm	h/p
	v/Ω	ṽ	2,725,836.571	m-1	p/h
	c²/Ω	f	8.171852456 x 10¹⁴	Hz	E/h
	v²/c²	E	3.381321915	eV	hf
		Ω	109.9818167	m²/s	

ground KEM energies

changing energy momenta produces specific frequency spectral lines

Paschen spectral lines


free electron
>13.525 eV
KE
n8⁺
n8
ε
n7
δ
n6
γ
n5
β
n4
α
n3
Paschen
spectral line
ground energy level
n2
n1


Δv
Σv
Mv²
Emission
768
180
15
[n3-8]
660
[n8-3]
15
588
156
13
[n3-7]
480
[n7-3]
13
432
132
11
[n3-6]
324
[n6-3]
11
300
108
9
[n3-5]
192
[n5-3]
9
192
84
7
[n3-4]
84
[n4-3]
7
108
Absorption


n3
Ground State
Paschen
α
β
γ
δ
ε
Δv
108
Σv
KEM
84
108
132
156
180
84
192
324
480
660
192
300
432
588
768
hv
v
c
v²
Mv²
hv, R, β, p, KE
Planck, Rydberg, Lorentz, Newton, Leibniz

-1.50280974 eV

$$KEM = \frac{hf}{n^2}$$

v
n3
KE
12
1.2e20

M shell

825.434 nm

$$KEM = \frac{hcR}{n^2}$$

m.

Ω/v	λ	825.4346663	nm	h/p
v/Ω	ṽ	1,211,482.92	m-1	p/h
c²/Ω	ƒ	3.631934425 x 10¹⁴	Hz	E/h
v²/c²	E	1.50280974	eV	hƒ
	Ω	247.4590875	m²/s	

ground KEM energies

equilateral energy momenta is the foundation of all quantum EM wave-functions

Tetryonics 32.01 - Paschen spectral lines

As photo-electrons transition between Mv squared KEM field energy levels in atomic nuclei they release specific [Δhv] W bosons

Paschen spectral series



-1.50280974 eV
v
n3
KE
12
1.2e20
825.434 nm



λ
n
Absorption
n²
Mv²
Paschen
KEM
v
Δν
f

α	1,886	n3-4
β	1,289	n3-5
γ	1,100	n3-6
δ	1,011	n3-7
ε	960	n3-8

IR spectrum



λ
n
Emission
n²
Mv²
Paschen
KEM
v
Δν
f

M shell

Δν

KEM



192

1 quantum level jump



300

2 quantum level jump



432

3 quantum level jump



588

4 quantum level jump



768

5 quantum level jump

Tetryonics 32.02 - Paschen quantum transitions

Paschen series energy momenta


M
7/16
n3
n3~4
84
α
192
M
16/25
n3
n3~5
192
β
300
n3
Ground State
Δv
108
Σv
KEM
α
β
γ
δ
ε
84
108
132
156
180
84
192
324
480
660
192
300
432
588
768
Planck
quanta
Free electron
1.502 eV/n²
ionsation energy
KEM
field
n8
ε
768
660
n7
δ
588
480
n6
γ
432
324
n5
β
300
192
n4
α
192
84
n3
Paschen
Spectral Line
ground level
108
M
27/36
n3
n3~6
324
γ
432
M
40/49
n3
n3~7
480
δ
588
M
55/64
n3
n3~8
660
ε
768

accelerating electrons $\Delta p = \Delta M v = hf$ produce spectral lines

Tetryonics 32.03 - Paschen series energy momenta

Paschen Series



$$\Delta h v = \text{KEM} = hcR$$

Tetryonic 1.502 eV Rydberg

55/64
.0954

λ	960.5057935	nm
$\tilde{v}$	1,041,118.135	m-1
f	$3.121193646 \times 10^{14}$	Hz
E	1.29147712	eV
Ω	287.9523928	m^2/s

$$R\left(\frac{1}{9}-\frac{1}{64}\right)$$

.09548

40/49
.0907

λ	1,011.157466	nm
$\tilde{v}$	988,965.6492	m-1
f	$2.9464844428 \times 10^{14}$	Hz
E	1.226783461	eV
Ω	303.1373822	m^2/s

$$R\left(\frac{1}{9}-\frac{1}{49}\right)$$

.0907

27/36
.8033

λ	1,100.579555	nm
$\tilde{v}$	908,612.1902	m-1
f	$2.723950819 \times 10^{14}$	Hz
E	1.127107305	eV
Ω	329.94545	m^2/s

$$R\left(\frac{1}{9}-\frac{1}{36}\right)$$

.0833

16/25
.0711

λ	1,289.741666	nm
$\tilde{v}$	775,349.069	m-1
f	$2.324438032 \times 10^{14}$	Hz
E	0.961798233	eV
Ω	386.6548241	m^2/s

$$R\left(\frac{1}{9}-\frac{1}{25}\right)$$

.0711

7/16
.0486

λ	1,886.707809	nm
$\tilde{v}$	530,023.7776	m-1
f	$1.588971311 \times 10^{14}$	Hz
E	0.657479261	eV
Ω	565.6207715	m^2/s

$$R\left(\frac{1}{9}-\frac{1}{16}\right)$$

.0486

m.

Ω/v	λ	825.4346663	nm	h/p
v/Ω	$\tilde{v}$	1,211,482.92	m-1	p/h
c^2/Ω	f	$3.631934425 \times 10^{14}$	Hz	E/h
v^2/c^2	E	1.50280974	eV	hf
	Ω	247.4590875	m^2/s	

ground KEM energies

changing energy momenta produces specific frequency spectral lines

Copyright ABRAHAM [2008] - all rights reserved

Brackett spectral lines


free electron
>13.525 eV
KE
n8⁺
n8
δ
n7
γ
n6
β
n5
α
n4
Brackett
spectral line
ground energy level
n3
n2
n1


Δv
Σv
Mv²
Emission
768
180
15
[n4-8]
576
[n8-4]
15
588
156
13
[n4-7]
396
[n7-4]
13
432
132
11
[n4-6]
240
[n6-4]
11
300
108
9
[n4-5]
108
[n5-4]
9
192
p
d
Absorption


n4
Ground State
Brackett
α
β
γ
δ
192
Δv
Σv
KEM
108
132
156
180
108
240
396
576
300
432
588
768
5
6
7
8
hv
Mv²
hv, R, β, p, KE
Planck, Rydberg, Lorentz, Newton, Leibniz

-0.84533478 eV

$$KEM = \frac{hf}{n^2}$$

v
n4
KE
S
N
12
1.2e20

N shell

1,467.43 nm

$$KEM = \frac{hcR}{n^2}$$

$$m.\begin{bmatrix} \Omega/v \\ v/\Omega \\ c^2/\Omega \\ v^2/c^2 \end{bmatrix}$$

λ	1,467.439407	nm	h/p
ṽ	681,459.1426	m-1	p/h
f	2.042963114 x 10¹⁴	Hz	E/h
E	0.84533478	eV	hf
Ω	[illegible]	m²/s	

ground KEM energies

equilateral energy momenta is the foundation of all quantum EM wave-functions

Tetryonics 33.01 - Brackett spectral lines

As photo-electrons transition between Mv squared KEM field energy levels in atomic nuclei they release specific [Δhv] W bosons


-0.84533478 eV
v
n4
KE
S
N
12
1.2e20
1,467.43 nm


λ
n
Absorption
n²
Mv²
Brackett
KEM
v
Δv
f

Brackett spectral series

α	4,076	n4-5
β	2,641	n4-6
γ	2,178	n4-7
δ	1,956	n4-8

IR spectrum


λ
n
Emission
n²
Mv²
Brackett
KEM
v
Δv
f

N shell

$$\frac{\Delta\nu}{\text{KEM}}$$



108

300

1 quantum level jump



240

432

2 quantum level jump



396

588

3 quantum level jump



576

768

4 quantum level jump

Tetryonics 33.02 - Brackett quantum transitions

Brackett series energy momenta


M
9/25
n4
[0.36]
n4~5
9
108
300
α
M
20/36
n4
[0.555555]
n4~6
9
11
240
432
β
n4
Ground State
Brackett
α
β
γ
δ
Δv
Σv
108
132
156
180
9
11
13
15
5
6
108
240
396
576
KEM
300
432
588
768
Free electron
0.845 eV/n²
ionsation energy
Planck
quanta
KEM
field
n8
δ
576
768
n7
γ
396
588
n6
β
240
432
n5
α
108
300
Brackett
Spectral Line
ground level
192
M
33/49
n4
[0.673469387]
n4~7
9
11
13
396
588
γ
M
48/64
n4
[0.75]
n4~8
9
11
13
15
576
768
δ

accelerating electrons $\Delta \mathbf{p} = \Delta M \mathbf{v} = hf$ produce spectral lines

Copyright ABRAHAM [2008] - all rights reserved



Brackett Series

$$\Delta h\nu = \text{KEM} = hcR$$

Tetryonic 0.845 eV Rydberg

48/64

.0468

λ	1,956.585876	nm
$\bar{\nu}$	511,094.357	m-1
f	$1.532222335 \times 10^{14}$	Hz
E	0.634001085	eV
Ω	586.569689	m²/s

$R\left(\frac{1}{16}-\frac{1}{64}\right)$ .0468

33/49

.04209

λ	2,178.92518	nm
$\bar{\nu}$	458,941.8716	m-1
f	$1.375873118 \times 10^{14}$	Hz
E	0.569307096	eV
Ω	653.2253354	m²/s

$R\left(\frac{1}{16}-\frac{1}{49}\right)$ .04209

20/36

.0347

λ	2,641.390932	nm
$\bar{\nu}$	378,588.4126	m-1
f	$1.134979508 \times 10^{14}$	Hz
E	0.469630433	eV
Ω	791.3690801	m²/s

$R\left(\frac{1}{16}-\frac{1}{36}\right)$ .0347

9/25

.0225

λ	4,076.220574	nm
$\bar{\nu}$	245,325.2914	m-1
f	$7.35466721 \times 10^{13}$	Hz
E	0.30432052	eV
Ω	1,222.020185	m²/s

$R\left(\frac{1}{16}-\frac{1}{25}\right)$ .0225

$$m.\begin{bmatrix} \Omega/v \\ v/\Omega \\ c^2/\Omega \\ v^2/c^2 \end{bmatrix}$$

λ	1,467.439407	nm	h/p
$\bar{\nu}$	681,459.1426	m-1	p/h
f	$2.042963114 \times 10^{14}$	Hz	E/h
E	0.84533478	eV	hf
Ω	439.9272667	m²/s	

ground KEM energies

changing energy momenta produces specific frequency spectral lines


free electron
>13.525 eV
KE
n8⁺
n8
γ
n7
β
n6
α
n5
n4
n3
n2
n1

Pfund
spectral line
ground energy level

Pfund spectral lines


Δv
Σv
Mv²
Emission
768
180
15
p
[n5-8]
468
[n8-5]
15
588
156
13
[n5-7]
288
[n7-5]
13
432
132
11
[n5-6]
132
[n6-5]
d
11
300
Absorption

n5

Ground State


v
300
Pfund
α
β
γ
Δv
Σv
KEM
132
11
6
6²
132
432
156
13
7²
288
588
180
15
8²
468
768
hv
v
c
v²
Mv²

hv, R, β, p, KE
Planck, Rydberg, Lorentz, Newton, Leibniz

-0.5410115 eV

$$\text{KEM} = \frac{hf}{n^2}$$

v
n5
KE
S
N
12
1.2e20

O shell

2,292.87 nm

$$\text{KEM} = \frac{hcR}{n^2}$$

$$m.\begin{bmatrix}\Omega/v \\ v/\Omega \\ c^2/\Omega \\ v^2/c^2\end{bmatrix}$$

λ	2,292.874073	nm	h/p
ṽ	436,133.8513	m-1	p/h
ƒ	$1.307496393 \times 10^{14}$	Hz	E/h
E	0.541011506	eV	hƒ
Ω	687.3863542	m²/s	

ground KEM energies

equilateral energy momenta is the foundation of all quantum EM wave-functions

Tetryonics 34.01 - Pfund spectral lines

Copyright ABRAHAM [2008] - all rights reserved

As photo-electrons transition between Mv squared KEM field energy levels in atomic nuclei they release specific [Δhv] W bosons

2,292.87 nm
v
n5
KE
12
[0-12]
1.2e20
-0.5410115 eV


Absorption
λ
n
n²
Mv²
KEM
Pfund
v
Δv
f

Pfund spectral series

α	7,503	n5-6
β	4,681	n5-7
γ	3,762	n5-8

IR spectrum


Emission
λ
n
n²
Mv²
KEM
Pfund
v
Δv
f

O shell

Δv
KEM


n5~6
α
1
2
3
4
5
7
8
9
10
11

132

432

1 quantum level jump



288

588

2 quantum level jump



468

768

3 quantum level jump

Tetryonics 34.02 - Pfund quantum transitions

Pfund series energy momenta


n5
Ground State
Pfund
300
α
β
γ
Δv
Σv
KEM
132
156
180
11
13
15
6
7
8
132
288
468
432
588
768
hv
v
c
v²
Mv²
Planck
quanta
Free electron
0.541 eV /n²
ionsation energy
KEM
field
n8
γ
768
468
n7
β
588
288
n6
α
432
132
n5
Pfund
Spectral Line
ground level
300


M
11/36
n5
n5~6
11
[0.3055555]
132
432
α
M
24/36
n5
n5~7
11
13
[0.4897959181]
288
432
β
M
39/64
n5
n5~8
11
13
15
[0.609375]
468
432
γ

accelerating electrons $\Delta p = \Delta Mv = hf$ produce spectral lines

Tetryonics 34.03 - Pfund series energy momenta



Pfund Series

Δhv = KEM = hcR

Tetryonic · 0.541 eV · Rydberg

39/64
.0243

λ	3,762.665146	nm
ṽ	265,769.0656	m-1
f	7.967556145 x 10^{13}	Hz
E	0.329678886	eV
Ω	1,128.018633	m^2/s

$R\left(\frac{1}{25}-\frac{1}{64}\right)$
.0243

24/49
.0195

λ	4,681.284566	nm
ṽ	213,616.5802	m-1
f	6.404063965 x 10^{13}	Hz
E	0.264985227	eV
Ω	1,403.413807	m^2/s

$R\left(\frac{1}{25}-\frac{1}{49}\right)$
.01959

11/36
.0122

λ	7,503.951512	nm
ṽ	133,263.1212	m-1
f	3.995127867 x 10^{13}	Hz
E	0.165309071	eV
Ω	2,249.628068	m^2/s

$R\left(\frac{1}{25}-\frac{1}{36}\right)$
.0122

$m.\begin{bmatrix}\Omega/v \\ v/\Omega \\ c^2/\Omega \\ v^2/c^2\end{bmatrix}$

λ	2,292.874073	nm	h/p
ṽ	436,133.8513	m-1	p/h
f	1.307496393 x 10^{14}	Hz	E/h
E	0.541011506	eV	hf
Ω	687.3863542	m^2/s	

ground KEM energies

changing energy momenta produces specific frequency spectral lines

Copyright ABRAHAM [2008] - all rights reserved

Copyright ABRAHAM [2008] - all rights reserved

Humphreys spectral lines


free electron
-13.525 eV
KE
n8+
n8
β
n7
α
n6
Humphreys
spectral line
ground energy level
n5
n4
n3
n2
n1


Δv
Σv
Mv²
Emission
768
180
15
[n6-8]
336
[n8-6]
15
588
156
13
[n6-7]
156
[n7-6]
13
432
Absorption

n6

Ground State


v
432
Humphreys
α
β
Δv
Σv
KEM
156
180
588
768
c
Mv²
hv, R, β, p, KE
Planck, Rydberg, Lorentz, Newton, Leibniz

-0.375702435 eV

$$KEM = \frac{hf}{n^2}$$

v
n6
KE
12
1.2e20

P shell

3,301.73 nm

$$KEM = \frac{hcR}{n^2}$$

$$m.\begin{bmatrix}\Omega/v\\ v/\Omega\\ c^2/\Omega\\ v^2/c^2\end{bmatrix}$$

λ	3,301.738665	nm	h/p
ṽ	302,870.7301	m-1	p/h
f	9.079836062 x 10^{13}	Hz	E/h
E	0.375702435	eV	hf
Ω	989.8363501	m^2/s	

ground KEM energies

equilateral energy momenta is the foundation of all quantum EM wave functions

Tetryonics 35.01 - Humphreys spectral lines

Copyright ABRAHAM [2008] - all rights reserved

As photo-electrons transition between Mv squared KEM field energy levels in atomic nuclei they release specific [Δhv] W bosons


-0.375702435 eV
v
n6
KE
12
1.2e20
3,301.73 nm


λ
n
Absorption
n²
Mv²
KEM
Humphries
v
Δv
f

Humphries spectral series

α	12,445	n6-7
β	7,546	n6-8
	IR spectrum	


λ
n
Emission
n²
Mv²
KEM
Humphries
v
Δv
f

P shell

Δv

KEM


n6~7
α
156
588

1 quantum level jump


n6~8
β
336
768

2 quantum level jump

Tetryonics 35.02 - Humphreys quantum transitions

Humphreys series energy momenta


n6
Ground State
432
Humphreys
α
β
156
180
Δv
Σv
KEM
156
336
588
768
Free electron
0.375 eV/n²
ionsation energy
Planck
quanta
KEM
field
n8
β
336
768
n7
α
156
588
n6
Humphreys
Spectral Line
ground level
432


M
13/49
n6
n6~7
13
[0.265306122]
156
588
α


M
28/64
n6
n6~8
13
15
[0.4375]
336
768
β

accelerating electrons $\Delta p = \Delta Mv = hf$ produce spectral lines

Tetryonics 35.03 - Humphreys series energy momenta

Copyright ABRAHAM [2008] - all rights reserved



Humphreys Series

$\Delta h\nu$ = KEM = hcR

Tetryonic

0.375 eV

Rydberg

28/64

.01215

λ	7,546.831235	nm
ṽ	132,505.9444	m-1
f	3.972428277 x 10^{13}	Hz
E	0.164369815	eV
Ω	1,128.018633	m²/s

$R\left(\frac{1}{36}-\frac{1}{64}\right)$

.01215

13/49

.00733

λ	12,445.01497	nm
ṽ	80,353.459	m-1
f	2.408993609x 10^{13}	Hz
E	0.099676156	eV
Ω	1,403.413807	m²/s

$R\left(\frac{1}{36}-\frac{1}{49}\right)$

.0073

$m.\begin{bmatrix}\Omega/v\\ v/\Omega\\ c^2/\Omega\\ v^2/c^2\end{bmatrix}$

λ	3,301.738665	nm
ṽ	302,870.7301	m-1
f	9.079836062 x 10^{13}	Hz
E	0.375702435	eV
Ω	889.8363501	m²/s

h/p
p/h
E/h
hf

ground KEM energies

changing energy momenta produces specific frequency spectral lines

Un-named spectral line


free electron
>13.525 eV
KE
n8+
n8
α
n7
Un-named
spectral line
ground energy level
n6
n5
n4
n3
n2
n1


Δv
Σv
Mv²
Emission
768
180
t5
[n7-8]
180
[n8-5]
t5
588
Absorption

n7

Ground State


un-named
α
588
Δv
Σv
KEM
180
180
768
Mv²
hv, R, β, p, KE
Planck, Rydberg, Lorentz, Newton, Leibniz

-0.276026782 eV

$$KEM = \frac{hf}{n^2}$$

Q shell

4,494.03 nm

$$KEM = \frac{hcR}{n^2}$$

m.				
Ω/v	λ	4,494.033183	nm	h/p
v/Ω	$\tilde{v}$	222,517.2711	m-1	p/h
c^2/Ω	f	$6.67089964 \times 10^{13}$	Hz	E/h
v^2/c^2	E	0.276026278	eV	hf
	Ω	1,347.277254	m^2/s	

ground KEM energies

equilateral energy momenta is the foundation of all quantum EM wave functions

Tetryonics 36.01 - Un-named spectral line

This spectral line photo electrons transition can only release ***one*** *specific [Δhv] W boson of energy*

Un-named spectral series

Q shell


-0.276026782 eV
v
n7
KE
S
N
12
f.2e20
4,494.03 nm


λ
n
Absorption
n²
Mv²
KEM
Un-named
v
Δv
f

α **19,174** n1-8

IR spectrum


λ
n
Emission
n²
Mv²
KEM
Un-named
v
Δv
f

Δv

KEM


n7~8
α
180
768
1 quantum level jump

Copyright ABRAHAM [2008] - all rights reserved

Un-named series energy momenta


n7
Ground State
588
un-named
α
Δv
Σv
KEM
180
180
768
c
Mv
Planck
quanta
KEM
field
n8
α
768
180
n7
588

This is a single un-named atomic spectral series line

Free electron
0.276 eV /n²
ionsation energy

Un-named Spectral Line ground level


M
15/64
n7
n7~8
15
[0.234375]
180
768
α

accelerating electrons $\Delta p = \Delta Mv = hf$ produce spectral lines



Un-named Series

$$\Delta h\nu = \text{KEM} = hcR$$

Tetryonic

0.276 eV

Rydberg

15/64
.0047

λ	19,174.54158	nm
$\bar{\nu}$	52,152.48541	m-1
f	1.563492179 x 10^{13}	Hz
E	0.064693658	eV
Ω	5.748.382952	m²/s

$$R\left(\frac{1}{49}-\frac{1}{64}\right)$$

.0047

$$m.\begin{bmatrix}\omega/v\\ v/\Omega\\ c^2/\Omega\\ v^2/c^2\end{bmatrix}$$

λ	4,494.033183	nm
$\bar{\nu}$	222,517.2711	m-1
f	6.67089964 x 10^{13}	Hz
E	0.276026278	eV
Ω	1,347.277254	m²/s

h/p
p/h
E/h
hf

ground KEM energies

changing energy momenta produces a specific frequency spectral line

KEM field geometry

Q
RE
v
P
KE
ε₀
M
μ₀
3
hv
v²

The Lorentz corrected velocity of electron resulting from atomic energy level transitions

Bosons differential required to effect energy level transition

Energy differential for energy level transition


v
R
KE
Lyman
Balmer
Paschen
Brackett
Pfund
Humphries
Un-named
1
3
5
7
9
11
13
15
1²
2²
3²
4²
5²
6²
7²
8²
hv
c
V²

Mv^2

12x1
12x4
12x9
12x16
12x25
12x36
12x49
12x64

All of the quantum jumps of electrons bound in a Hydrogen atom can be summerised in the Tetryonic geometry reflecting the energy level transitions

Ryberg's constant is reflective of the wavelengths and linear momentum of a transitioning electron's KEM field

Ryberg's formula is a mathematical description of Tetryonic energy geometry

$$Mv^2 = KEM = hcR_H$$

KEM field quanta



Photoelectron transitions

Ground State
Δv
Σv
ΔKE
KEM
48
108
192
300
432
588
768
36
60
84
108
132
156
180
1
2
3
4
5
6
7
8
hv
Mv
Nuclear Quantum Levels
n
8
7
6
5
4
3
2
1
Lyman
Balmer
Paschen
Brackett
Pfund
Humphries
un-named
Rydberg constant / n²
LEPTONS - 12Δ Tetryonic shape
Tetryonic Energy - n squared
64
49
36
25
16
9
4
1
Photon Wave number
ν̃
222,517.27
436,133.85
1,211,482.92
10,903,146.28
302,870.73
681,459.14
2,725,836.57
27.495
109.981
247.459
439.927
687.386
989.836
1,347.277
1,759.709
Ψ
Photo-electron Wavefunction
12
48
108
192
300
432
588
768
972
KEM
Free Electron
Δ difference per Electron level
36
60
84
108
132
156
180
Δhv
photo-electrons
KE
RE
12
photons
0
[n-n]

The kinetic energy levels of bound nuclear photon-electrons is determined by the energy levels of their Baryons

Spectral Lines

Transition				Spectral series
n1~	n2	91.29	α	Lyman UV spectra
	n3	91.30	β	
	n4	91.32	γ	
	n5	91.33	δ	
	n6	91.36	ε	
	n7	91.38	ϕ	
	n8	91.41	η	
n2~	n3	367.08	α	Balmer Visible Spectra
	n4	367.23	β	
	n5	367.28	γ	
	n6	367.54	δ	
	n7	368.19	ε	
	n8	368.59	ϕ	
n3~	n4	833.16	α	Paschen IR spectra
	n5	834.34	β	
	n6	835.68	γ	
	n7	837.23	δ	
	n8	839.02	ε	
n4~	n5	1499.69	α	Brackett
	n6	1503.50	β	
	n7	1507.87	γ	
	n8	1512.92	δ	
n5~	n6	2381.53	α	Pfund
	n7	2391.17	β	
	n8	2402.25	γ	
n6~	n7	3499.27	α	Humphreys
	n8	3520.12	β	
n7~	n8	4880.38	α	Un-named

Spectral lines are produced by

The energy and wavelength of emitted photons is a function of the photo-electron's KEM field quantum wavenumber

Quantum Transitions

$$hf = \Delta Mv = \Delta p$$

27.49545

accelerating photo-electrons

Changes to the energy momenta of KEM fields produce changes to the linear momenta of photo-electrons

Tetryonics 37.02 - Photoelectron transitions

Photoelectric energy level transitions


1
1
1
2
4
4
3
9
9
4
16
16
5
25
25
6
36
36
7
49
49
8
64
64
12
48
108
192
300
432
588
768
12
[0-12]
1.2e20

Lyman	Balmer	Paschen	Brackett	Pfund	Humphries	un-named
91.29	367.06	833.16	1499.69	2381.53	3499.27	1917.4
91.3	367.23	834.34	1503.5	2391.17	3520.12	
91.32	367.28	835.68	1507.87	2402.25		
91.33	367.54	837.23	1512.92			
91.36	368.19	839.02				
91.38	368.59					
91.41						
UV spectrum	*Visible Spectrum*	*IR spectrum*				

Applying any extra Kinetic Energy to leptons in this energy level results in unbound photo-leptons


v
Q
RE
p
KE
M
hv
v²

$$Mv^2 = KEM = hcR_H$$

These specific quantum level steps create the Photoelectric effect

$$\Delta h\nu = \phi = hf$$

Photo-electrons bound to atomic nuclei can only transition between Mv squared KEM energies as a direct result of the energy levels of Baryons


v
KEM
1
1²
3
2²
5
3²
7
4²
9
5²
11
6²
13
7²
15
8²
R
KE
Δv
Σv
hv
c
v²
Mv²
12 x 1
12 x 4
12 x 9
12 x 16
12 x 25
12 x 36
12 x 49
12 x 64

The Photoelectric effect

The photoelectric effect was first observed in 1887 by Heinrich Hertz (1857-1894) during experiments with a spark-gap generator — the earliest form of radio receiver


$E_{\gamma} = hf$
Photoelectrons with higher Kinetic energies ejected
Minimal energy Photoelectrons ejected
No Photoelectrons ejected
M
Ground State
L
Ground State
K
Ground State
n3 M
n2 L
n1 K
1
8
2
11

There are specific frequencies of light that are more efficient at exciting photo-electrons from atoms

$$p^2 = KEM = Mv^2$$

The energies of the emitted electrons are independent of the intensity of the incident radiation but are dependent on the photon frequency

n2-4 specific transitions can release 8 times the number of electrons that n3-4 can release & 4 times the number of electrons that n1-4 can release

Any photon with EM energies in excess of a specific frequency produces a 'free' electron with higher Kinetic energies and linear momentum

Soon after the discovery of Planck's Heat law and the quantisation of energy at the quantum level experiments by others, most notably Robert Millikan (1865-1953), found that light with frequencies below a certain cutoff value, called the threshold frequency, ould not eject photoelectrons from the metal surface no matter how bright the source

Photonic mass-energy momenta

Bosons

EM Field Planck quanta

$$\text{ODD}\,\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$$

Bosons ElectroMagnetic mass velocity

$$2m\Omega v^2 = E = n.hf$$

All 2D EM waveforms possess mass-energy and momenta

Photons

EM Field Planck quanta

$$2\pi\left[[\varepsilon_0\mu_0].[m\Omega v^2]\right]$$

Photons ElectroMagnetic mass velocity

charged mass-energy-momentum

$$E = mv^2$$



radiant mass-energy momenta

$$E = hv^2$$

Planck energies

All 2D EM waveforms propagate at the speed of light

Velocity of Light

$$v = \left[\left[\frac{c^2}{\Omega}\right]\cdot\left[\frac{\Omega}{c}\right]\right] = c$$

f scalar frequency

λ linear wavelength

Speed of Light

Tetryonics 37.05 - Photonic mass-Energy equivalence

Copyright ABRAHAM [2008] - all rights reserved

Wave~Particle duality

First proposed by Christian Huygens in the 1600's, it wasn't until the 1800's
that Thomas Young proved this wave-particle duality with the classic double-slit experiment.

Sir Isaac Newton



(1643-1727)

Particles

In 1678, Dutch physicist, Christiaan Huygens, believed that light was made up of waves vibrating up and down perpendicular to the direction of the light travels, and therefore formulated a way of visualising wave propagation.

This became known as 'Huygens' Principle' and was the successful theory of light wave motion in three dimensions

Sir Isaac Newton, held the theory based on his spetral observations that light was made up of tiny particles or 'corpusles of colour'

English physicist Thomas Young argued that Isaac Newton's theory of particle light was incorrect, and instead argued that light is a transverse wave.

In 1803, Thomas Young studied the interference of light waves by shining light through a screen with two slits equally separated, the light emerging from the two slits, spread out and produced wave-like interference patterns.

Waves

Thomas Young

(1773-1829)

In 1900
Max Planck proposed the existence of a light quantum, [n.hv] a finite packet of energy which depends on the frequency and spectral energy of the radiation

Light - a Wave, or a Particle?

In 1905
Albert Einstein, suggested that light is composed of tiny particles called photons, and that each photon has energy related to its frequency [hf].

Max Karl Ernst Ludwig Planck

(April 23, 1858 – October 4, 1947)

Bosons

$$nhv = E = hf$$

Mathematically directly relating the number of Planck quanta [n.hv] with Photon frequencies [hf] and the frequent interchanging of one term for the other in physics is the source of considerable quantum confusion

$$2hv = hf$$

Photons

Albert Einstein



(14 March 1879 – 18 April 1955)

The quantum idea was soon seized upon to explain the photoelectric effect, and became part of the Bohr theory of discrete atomic spectra, quickly becoming part of the foundation of modern quantum theory in turn this led to the quantum wierdness of wave-particle dualty, Heisenberg's Uncertainty principle and Schrodinger's quantum wave equation & wavefunctions.

Wave Particle Mechanics


Planck
Einstein
nhv
hf
de Broglie
h/p
HΨ
$\Delta x \Delta p \geq \frac{\hbar}{2}$
Heisenberg
Schrodinger
p
d
ODDπ[[ε₀μ₀].[mΩv²]]
E = hv
128
Wavenumber
Transverse boson quanta
Wavelength
Longitudinal photon frequency
2π[[ε₀μ₀].[mΩv²]]
E = hf
64
Relativistic zLorentz corrections
EM energy momenta
EM Wavefunctions
EVENπ[[ε₀μ₀].[mΩv²]]
E=mv²
E=p²
1 4 9 16 25 36 49 64 64 49 36 25 16 9 4 1
Quantum Energy Levels [n²]
EΨ
HΨ
Probabilty
Amplitudes
Statistical
Distributions

Tetryonics 38.01 - Wave~Particle Mechanics

Copyright ABRAHAM [2008] - all rights reserved

Blackbody Radiation


Wien's displacement law
E1
E2
E3
E4
E5
E6
E7
E8
Rayleigh–Jeans law

Max Planck

(April 23, 1858 – October 4, 1947)

In physics, Planck's law describes the amount of electromagnetic energy with a certain wavelength radiated by a black body in thermal equilibrium (i.e. the spectral radiance of a black body).

The law is named after Max Planck, who originally proposed it in 1900. The law was the first to accurately describe black body radiation, and resolved the ultraviolet catastrophe by introducing Planck's Constant.

It is a pioneer result of modern physics and quantum theory leading to mass.QAM being termed Planck's constant.



$$m\Omega = 6.62943244\ \text{e-34 J.s} = h$$

$nh\nu$

All EM waves are comprised of discrete energy quanta

As their frequency increases the wavelength of emitted Photons decreases


f
λ
n1
n2
n3
n4
n5
n6
n7
n8
2
8
18
32
50
74
98
128
1
4
9
16
25
36
49
64

$$2h\nu = hf = hc\tilde{\nu}$$

Tetryonics 38.02 - Blackbody Radiation curves

EM field energies

Planck quanta

$$E = n\pi\left[\left[m\Omega v^2\right]\right]$$

mass velocity



All quantum energy waveforms are geometrically coupled Electric and Magnetic fields that produce time-varying electro-magnetic fields




Electric Fields
1/r²

Charge

$$1\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

EM Field Planck quanta

ElectroMagnetic mass velocity

$$E = h\nu$$

EM waves are subject to Lorentz co-ordinate transformations


c
S
+
N
-
S
+
N
-
270
180
90
0
270
180
90
0
270
180
90
0
S
-
N
+
S
-
N
+
c

EM waves are a quadrature waveform of bi-directional electromagnetic oscillations

$$E = hf$$

Photons

$$2\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

EM Field Planck quanta

ElectroMagnetic mass velocity




1/r²
Magnetic Fields



EM Field Planck quanta

$$\text{EVEN}\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

EM waves ElectroMagnetic mass velocity

Bosons and Photons in EM waves

EM Field Planck quanta

$\text{ODD}\,\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$

Bosons ElectroMagnetic mass velocity

Transverse charge Quanta






λ λ λ λ λ λ λ λ λ λ λ λ λ λ λ λ
c

quanta wavenumber

quanta wavenumber


1
3
5
7
9
11
13
15
15
13
11
9
7
5
3
1
1
2
3
4
5
6
7
8
7
6
5
4
3
2
1

EM Field Planck quanta

$$n\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

mass ElectroMagnetic mass velocity

photon frequency

photon frequency

$E = h\nu$

All EM waves are comprised of transverse Bosons

$E = hf$

All EM waves are comprised of longitudinal Photons


λ λ λ λ λ λ λ λ
f f f f f f f f
c





Longitudinal neutral Photons

EM Field Planck quanta

$\text{EVEN}\,\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$

Photons ElectroMagnetic mass velocity

EM wave energy quanta

All EM waves are composed of Bosons



ODDπ $[[\varepsilon_0\mu_0].[m\Omega v^2]]$

Bosons
EM Field
ElectroMagnetic
mass
Planck quanta
velocity

Boson

E = n.hn

Tranverse Bosons in EM wave energies should be modelled using [n] Planck quanta

Wavefunction

$$i\hbar\frac{\partial}{\partial t}\Psi \quad \Psi \quad \hat{H}\Psi$$

Probability = |Amplitude| ²

The Longitudinal EM wave energies should be modelled using [f] Photon frequencies



Transverse neutral W Boson quanta [ν]

Bosons and Photons with the same energies have different wavelengths

Longitudinal Photon frequency [f]

$$E = n\pi[m\Omega v^2]$$

Planck quanta
mass
velocity

All Wave~Particle geometries and mass-energies can be calculated from and modelled with the Tetryonic Unified Field Equation



Probability = |Amplitude| ²

$|4|^2 = 16$

E =hf

Photon

EVENπ $[[\varepsilon_0\mu_0].[m\Omega v^2]]$

EM waves
EM Field
Planck quanta
ElectroMagnetic
mass
velocity

All EM waves are composed of Square number Photons



Probability = |Amplitude| ²

$|8|^2 = 64$

EM wave properties

Linear momentum is the square root of scalar mass-energies

EM waves are comprised of Photons with Kinetic energies, momenta and a photo-magnetic moment

$$\left[\sqrt{[m\Omega v^2]}\right]$$

Energy

mass quanta

EM waveform geometries



Energy

$$p_\gamma = 2\pi[[m\Omega v]]$$

momenta

Photonic energy-momentum

Transverse waveforms

Longitudinal waveforms


Quantum Levels
Bosons
1
4
9
16
25
36
49
64
15
13
11
9
7
5
3
1
8/64
7/64
6/64
5/64
4/64
3/64
2/64
1/64
Probabilities
1
2
3
4
5
6
7
8
Frequency
p
p
m
m
photo-magnetons

Ω m

Scalar Planck quanta per second is the scalar source of all linear energy-momenta

p^2


d
λ
s
monochromatic planar waves
screen with two slits
photo detector

Interference is the result of KEM waveform superpositioning

Conservation of Energy momenta

Energy momenta a conserved quantity in physical systems (laws of conservation), meaning that if a closed system is not affected by external forces, its total momentum cannot change

Copyright ABRAHAM [2008] - all rights reserved

Statistical probabilities of energy distributions

form the basis for quantum mechanical probabilities and wavefunctions

$$E = 2mv$$



$$E = Mc^4$$



All ENERGY in motion has probabilistic distribtutions of energy quanta resulting from the equilateral Tetryonic geometries of electromagnetic mass-ENERGY-Matter



$$p^2 = E = mv^2$$


Magnetic moment
KE
Kinetic Energies
KEM fields

$$KE = \frac{1}{2}Mv^2$$

$$Mv^2 = KEM$$

Copyright ABRAHAM [2008] - all rights reserved



Transverse

Bosons

$\text{ODD}\,\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$

Boson quanta (ν)

$\nu=128$

$E=h\nu$

EM waves

$\text{EVEN}\,\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$

Planck quanta

$\nu=128$

EM wavefunction

Group Phase Velocity
(with respect to E field)

$f=64$

Photon frequency

Waveform probability distribution

[Amplitude]²

$n/64 = n/[8^2]$

$E=hf$

Longitudinal

Photons

$2\pi[[\varepsilon_0\mu_0].[m\Omega v^2]]$

64

Photon Frequency (f)

128
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1
1 4 9 16 25 36 49 64
1 3 5 7 9 11 13 15
EM Field
Planck quanta
EM waves
ElectroMagnetic
mass
velocity
1/64 2/64 3/64 4/64 5/64 6/64 7/64 8/64
0.0156 0.0312 0.0468 0.0625 0.0781 0.093 0.109 0.125
ψ
c
P
64
f

Tetryonics 38.08 - EM wavefunctions

Wave functions

All EM waves and Photons exhibit quantum levels of mass-energy momenta determined by their constituent bosons

Transverse EM Waveforms


Quantum Levels
1
4
9
16
25
36
49
64
Boson quanta
15
13
11
9
7
5
3
1
v
8/64
7/64
6/64
5/64
4/64
3/64
2/64
1/64
Amplitude Probabilities
1
2
3
4
5
6
7
8
Photon Frequency

Longitudinal EM waveforms

All electromagnetic waves exhibit wave probabilities and amplitude functions determined by their constituent photons

Bosons


128
Bosons
v = 128

$E = h\nu$

[Planck quanta are single-quanta Bosons]

All EM waves are comprised of Longitudinal Photons which in turn are made up of Transverse Bosons

[Photons are neutral dual-quanta Bosons]

$E = hf$


1
2
3
4
5
6
7
8
Photons
64
f = 64

Photons

Energy levels

1
4
9
16
25
36
49
64

Squared numbers

Wave-particle duality holds that light and matter simultaneously exhibit properties of waves as well as particle-like properties (photons).

This concept is a consequence of the mathematical treament of mass-energy physics in quantum mechanics and a comprehensive explanation of this duality has been elusive to Physics since its discovery.

Any attmpt to develop an unified quantum theory must explain the root cause and processes behind Wave-Particle duality and must also explain:

Diffraction, Deflection and Reflection along with Bosons, Photons, EM radiation, energy quantisation and mass-Matter.

Probabilities


1/64
2/64
3/64
4/64
5/64
6/64
7/64
8/64
0.0156
0.0312
0.0468
0.0625
0.0781
0.093
0.109
0.125
64

Waves

EM Wavefunctions

Transverse mass-energy distrbutions


n8
0.234
0.203
0.171
0.0140
0.109
0.0781
0.0468
0.0156
1/64
3/64
5/64
7/64
9/64
11/64
13/64
15/64
15/64
13/64
11/64
9/64
7/64
5/64
3/64
1/64
0.0156
0.0468
0.0781
0.109
0.0140
0.171
0.203
0.234
1
2
3
4
5
v
7
8
8
7
v
5
4
3
2
1
v = 128

The wavefunction for a system contains all the information about the quantum state that a particle/system is in and gives a complete description of that part of the world at any one particular instant in time.



Longitudinal mass-energy distributions


n8
1/64
2/64
3/64
4/64
5/64
6/64
7/64
8/64
0.0156
0.0312
0.0468
0.0625
0.0781
0.093
0.109
0.125
0.109
0.093
0.0781
0.0625
0.0468
0.0312
0.0156
7/64
6/64
5/64
4/64
3/64
2/64
1/64
f
f = 64

Q
[v-v]

RE

Ψ

rest
Matter

KE


e
12
[0-12]
RE
E = hv
1.2 e20
rest Matter
KE


e
12
[0-12]
RE
E = hf
1.2 e20
rest Matter
KE

The wavefunction of an EM wave (KEM) geometry is distinct from that of rest mass-Matter toplogies due to the number of Planck quanta contained in it but both can be modelled using Tetryonic geometry

Quantum Energy Levels

The wavefunction itself is often said to be un-observable. In fact, it can modelled as it is a reflection of the quantas making up the quantum state of any particle and is complex-valued.

As the system evolves over time, the wavefunction also changes, so it can be written as a function of time Ψ(t).

$$\int_{-\infty}^{\infty} |\Psi|^2 \mathrm{d}x = 1.$$

The absolute square of the function must be normalizable

Wave-Particle Probabilities

The absolute square of the wavefunction is a probability density (the area of highest probability for a measurement to take place.

For example, if the wavefunction is expressed in real space and our system is a particle, the absolute square gives a probability density for the position of the system. Integrating this probability density between some bounds will give the probability that the particle will be found in that region when its position is measured

Wave~Particle energies

Equilateral energy is the foundational geometry
of Kinetic EM Waveforms [WAVES]
and standing wave Matter [PARTICLES]

**All Matter in motion exhibits
a Wave-Particle duality**

Everything is made up of
***charged mass-energy
quanta***



ZPFs combine in ODD
numbers to form
Bosons



Bosons combine to form
Quantum Levels


128
Transverse
EM mass-Energy
hν


Wavelength
Frequency
hf
Longitudinal
EM mass-Energy
64

The quantum Planck quanta tesslation
of Matter can be accurately modelled with
Wave Probability mechanics


1.2e20
Transverse
Bosons
ODD π
E = hν


12
0-12
7.95553 e-14 J
1.2e20
3.2e15
c


E = hf
6.0e19
Photons
EVEN π
Longitudinal

A n8 Electron is a massive particle
which has a Kinetic EM energy field
[6.4e15 planck quanta]

*2D EM field geometries
can combine to form
3D Tetryonic Matter topologies*


ν
Number of ZPFs
per Boson
n
Number of ZPFs
per quantum level
1 2 3 4 5 6 7 8
1 3 5 7 9 11 13 15
12 36 60 84 108 132 156 180
|8|² x12
[768]
64

Quantum levels are a transverse measurements of energy

Equivalently, all Matter & EM waves can be viewed either in terms of their transverse boson or longitudinal photon content and/ or their associated mass-energy momenta geometries


Square of
Wave function
is
Normalizable
[1]
Probability is
Square of Amplitude
|8|²
[64]
1/64 2/64 3/64 4/64 5/64 6/64 7/64 8/64
.125 .109 .093 .078 .062 .046 .031 .015
32
2 4 6 8 6 4 2

Wave functions are a linear measurement of photonic energy

Wave-particle Probabilities

All Particles in motion exhibit a Wave-Particle duality due to the 2D waveform geometry of its KEM wave and the lorentz velcoity invariant 3D standing wave geometry of its Matter


v
Transverse Bosons
Longitudinal Photons
KEM
M
hv
v²
1 2 3 4 5 6 5 4 3 2 1
Matter Particle
KEM wave

Equilateral energy tessellation provides the basis for the probabilistic statisical mechanics and math for all of Quantum Mechanics


12
[0-12]
RE
e-
Particle
Wave
M
KEM


E = hf
c
Energy
Frequency
Amplitude
1 2 3 4 5 6 7 8 8 7 6 5 4 3 2 1
p
1 2 3 4 5 6 7 8 7 6 5 4 3 2 1
d
Quantum levels
Quanta
Probabilities
c
E = hv

Schrodinger Wavefunction
The Wavefunction of a Particle equates to its Amplitude

The Square of a Wave function is Normalizable

Probability = $[\text{Amplitude}]^2$

Born Probability Rule
The Probability of finding a Particle is the Square of its Amplitude

White Light mass-energy momenta waveforms


Bosons
Transverse Bosons
Quantum levels
ml-8
Scalar EM mass-energies
E
Frequency
64
Linear energy momenta
f
Photons
1
2
3
4
5
6
7
8
7
6
5
4
3
2
1
/64
Amplitudes
White light is comprised of superpositioned EM waves
1
4
9
16
25
36
49
64
Ψ
γ1
γ2
γ3
γ4
γ5
γ6
γ7
γ8

EM Field Planck quanta

EVEN π $[[\varepsilon_0\mu_0].[m\Omega v^2]]$

EM waves ElectroMagnetic mass velocity

Bosons and Photons

EM waves are comprised of longitudinal [E=hf] Photons which in turn can also be measured as transverse [E=nhv] Bosons

Electro-Magnetic Fields



As described by Lorentz co-ordinate transforms the neutral quantum coin [quoin] geometry of all photons and EM waves have mirror E-field charges on each of their opposing fascia



2D planar mass-energy momenta waveforms

$$\underset{\text{Photons}}{2\pi}\left[\left[\overset{\text{EM Field}}{\underset{\text{ElectroMagnetic}}{\varepsilon_0\mu_0}}\right].\left[\overset{\text{Planck quanta}}{\underset{\text{mass}}{m}\Omega\underset{\text{velocity}}{v^2}}\right]\right]$$

Photons and EM waves have dual c² space-time geometries
(8.987551787 e16 m/s)



Photons and EM waves propagate outwards from their source at 'c'
(299,792,458 m/s)

$$\underset{\text{EM waves}}{\text{EVEN}\pi}\left[\left[\overset{\text{EM Field}}{\underset{\text{ElectroMagnetic}}{\varepsilon_0\mu_0}}\right].\left[\overset{\text{Planck quanta}}{\underset{\text{mass}}{m}\Omega\underset{\text{velocity}}{v^2}}\right]\right]$$

EM waves are detected as alternating radial electric E-wave radiation fields



EM wave radiation



The Magnetic vector of EM energy momenta propagate orthagonally to their E-fields


1/64
2/64
3/64
4/64
5/64
6/64
7/64
8/64
0.0156
0.0312
0.0468
0.0625
0.0781
0.093
0.109
0.125

EM wave patterns

Polarised Photons and EM waves produce linear interference patterns


1
2
3
4
5
6
7
8
7
6
5
4
3
2
1



Diffraction occurs whenever propagating waves
appear to bend around small obstacles in their path
and spread out as smaller waves waves past any openings,
its effects are generally most pronounced for
waves whose wavelength is roughly
similar to the dimensions of the diffracting objects.

If the obstructing object provides multiple, closely spaced openings,
a complex pattern of varying intensity can result.

This is due to the superposition, or interference, of different parts of a wave
that travels to the observer by different paths


Cu.25Ni.75Al2O4
NiO
Ni
(531)
(333)
(242)
(240)
(331)
(311)
(531)
(311)
(220)
(440)
(220)
(200)
(400)
(200)
(111)
(311)
(111)

atomic diffraction
spectroscopy of matter
plays an important role
in the chemical analysis
of elements and compounds

Diffraction occurs with all waves, including sound waves, water waves,
as well as with electromagnetic waves such as visible light, X-rays and radio waves.

Un-Polarised Photons and EM waves produce circular diffraction patterns


f
d
p
s
2
8
10
14

Richard Feynman once commented that:
"No-one has ever been able to define the difference between interference and diffraction satisfactorily.
It is just a question of usage, and there is no specific, important physical difference between them."

Copyright ABRAHAM [2008] - all rights reserved

Light waves

Thomas Young

(13 June 1773 – 10 May 1829)

$$E = mv^2$$

"The term energy may be applied, with great propriety, to the product of mass or weight of a body, into the square of the number expressing its velocity.

Thus, if the weight of one ounce moves with a velocity of a foot in a second, we call its energy 1; if a second body of two ounces has a velocity of three feet in a second, its energy will be twice the square of three, or 18."

$$KE = \frac{1}{2}Mv^2$$



All Light propagates at the speed of EM ENERGY

In order to establish his wave theory of light Young had to overcome the century-old view, expressed by Sir Isaac Newton' in his treatise "Optics", that light is a particle of colour.



Thomas Young studied the interference of light waves by shining light through a screen with two slits equally separated, where the light emerging from the two slits would spread out and eventually superposition [overlap] each other to produce a distinct interference pattern



All EM waves have energy momenta geometries whose physical properties can be modeled with statisical probabilities due to their equilateral wavefunctions

Tetryonics reveals the true geometry of Light

and dispels the misconceptions surrounding its physical properties of wave-length, energy momenta, frequency and associated wave-function



$$E_\gamma = 2mv^2$$

Photons are radiative Kinetic EM mass-energies

$$p^2 = KEM = Mv^2$$



Photon-EM Wave Superpositioning

In physics, the Superposition principle, also known as superposition property, states that, for all linear systems, the net response at a given place and time caused by two or more stimuli is the sum of the responses which would have been caused by each stimulus individually.

$$F(\psi_1+\psi_2)= F(\psi_1) + F(\psi_2)$$

Positive quantum charge state
is one side of the quantum
energy momenta quoin

Negative quantum charge state
is the other side of the quantum
energy momenta quoin



The linear momenta of transverse waves is orthagonal to the direction of wave propagation

Photons are neutral EM wavepackets

whose chiral quantum charges can be determined through Lorentz co-ordinate transformations



The linear momenta of longitudinal waves is co-linear to the direction of wave propagation



transverse Radio waves

longitudinal Spectral lines

mc^{2^2} *Superpositioned EM waves can be likened to the cells of a chemical battery* mv^4

E^2



p^4

It is the superpositioning of longitudinal EM waveforms that creates white light and linear interaction-at-a-distance forces

Copyright ABRAHAM [2008] - all rights reserved



Wave Interference

In Phase
In Phase
Linear Displacement
Out of Phase
Out of Phase
In Phase
In Phase
In Phase
Out of Phase
Out of Phase
Out of Phase

Constructive Interference

Bosons and Photons are geometric 2D EM mass-energy waveforms that can be superpositioned

Destructive Interference

Transverse Displacement

Tetryonics 39.05 - Wave Interference - EM waves

Wave phase interference

The interference patterns produced by the photon intensities of superpositioned EM waveforms have been historically interpretted as being the result of transverse radial wave fronts

Radial modelling of the E-field propagation of EM waves and photons does not reflect their true equilateral energy momenta geometries

This is now shown to be incorrect

Constructive



In Phase waveforms

The Photon intensities resulting from superpositioned EM waves (and photons alike) result in a distribution of equilateral energy momenta that in turn produces a 'wave-like' interference pattern when measured with respect to their resulting Electric field intensities over time.

Numerous factors can effect the resultant energy momenta intensities namely: Transverse and Longitudinal phase differences & the wavelength-frequencies of the photons comprising each EM wave

Destructive



Out of Phase waveforms

Tetryonics 39.06 - Wave phase interference

Transverse EM mass-energies

Matter in motion

Longitudinal EM mass-energies

$E = h\nu$

Historically modeled through relativistic stress energy tensors
all Matter in motion is possessive of distinct energy waveforms:
a standing wave mass-energy geometry [Matter particle] &
a divergent kinetic mass-energy field [KEM wave]

$E = hf$


1
4
9
16
25
36
49
64
15
13
11
9
7
5
3
1
1 2 3 4 5 6 7 8
8 7 6 5 4 3 2 1
v
v
n8




1/64
2/64
3/64
4/64
5/64
6/64
7/54
8/64
7/64
6/64
5/64
4/64
3/64
2/64
1/64
0.0156
0.0312
0.0468
0.0625
0.0781
0.093
0.109
0.125
0.109
0.093
0.0781
0.0625
0.0468
0.0312
0.0156
f
f=64

Negative charges in motion

EM induction and forces are effected by
neutral bi-directional KEM mass-energy fields
with interactive energy momenta

Positive charges in motion


Δhν - spectral lines - Δhf
Energy
Quanta
v
v²
v
KE
M
Q
Δhν - acceleration force - ΔMν




Δhν - acceleration force - ΔMν
v
v²
Q
M
KE
Quanta
Energy
v
Δhν - spectral lines - Δhf

unidrectional negative KEM fields
with interactive energy momenta

electromagnetic waves

[neutral bosons and/or photons]

unidirectional positive KEM fields
with interactive energy momenta

Copyright ABRAHAM [2008] - all rights reserved

**All Matter in motion [or not]
has both an intrinsic Matter-wave function
and an extrinsic KEM mass-energy wave function**

Transverse boson wavefunction

EM Field Planck quanta

$$\text{ODD}\,\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right] \qquad E = n.h\nu$$

Bosons

ElectroMagnetic mass velocity

128



EVEN π
EM waves

EM Field Planck quanta

$$\text{EVEN}\,\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right]$$

ElectroMagnetic mass velocity

64

EM Field Planck quanta

$$2\pi\left[\left[\varepsilon_0\mu_0\right].\left[m\Omega v^2\right]\right] \qquad E = hf$$

Photons

ElectroMagnetic mass velocity

Longitudinal photon wavefunction

Photon Intensity

*Photon Intensity is a result of the geometry of EM waves
[which in turn is directly proprtional to the velocity of the mass-Matter]
and can be measured in a number of vaying ways related to
the mass-energy momenta of the EM wave*

*Wavenumbers, frequency or wavelength
Transverse EM masses [BOSONS]
Longitudinal EM masses [PHOTONS]
Wavefunction probabilities [WAVE-FUNCTIONS]*

*The wave~particle nature of mass-Matter in motion
has been the subject of much debate since Lucretius in 55BC with the
debate intensitying with Newton's and Young's differing views and the
development of Planck-Einstein quantum mechanics of the photo-electric effect*



Intensity [number] of Photons
during any specified time interval of measurement
affects the interference pattern produced

*The measurement of Photons with the use
of Photo-multipliers and Charge coupled Devices
results in the measurement of the E field properties
of EM waves (producing the long confusing wave-particle
results obtained by diffraction gratings)*

*In turn these results have been historically misinterpreted
as a waveform property that cannot be attributed to
the particle properties of a Photon.*

Tetryonic geometry clears this matter up once and for all.

Interference Patterns

ε_0

When EM waves pass through the slits they are detected via their E-fields as photons of varying strength energy momenta producing the impression of a interference pattern

μ_0

$E = h\nu$


128
1/64
2/64
3/64
4/64
5/64
6/64
7/64
8/64
7/64
6/64
5/64
4/64
3/64
2/64
1/64
0.0156
0.0312
0.0468
0.0625
0.0781
0.093
0.109
0.125
0.109
0.093
0.0781
0.0625
0.0468
0.0312
0.0156
64

$E = hf$

Every EM wave is comprised of identical, specific wavelength photons which are arranged in a Normal distribution resulting from the electromagnetic Wavefunction with a peak value equal to the wave's amplitude

[the square root of the EM wave's Wavefunction/Probability amplitude]


1 2 3 4 5 6 7 8 7 6 5 4 3 2 1

Photons impact screens and photo-detectors with intensities that are determined by their energy momenta distributions


Superpositioned waves
Mid-Range peak of 8+

The resultant amplitudes are a direct result of the Phase of the Superpositioned photons within EM waves

Superpositioned wavefunctions


Superpositioned Mid-Range peak of 8
Superpositioned Mid-Range peak of [6-12]
Superpositioned Mid-Range peak of [4-14]



ALL EM mass-ENERGY Matter geometries being comprised of energy-momenta quanta are capable of producing interference patterns

The amplitudes of the detected photons in the resultant interference patterns are determined by their constructive/destructive superpositioning in each wave explaining the interference patterns currently accounted for by Young's wave theory

Copyright ABRAHAM [2008] - all rights reserved

Single slit experiment

If light consisted strictly of ordinary or classical particles, and these particles were fired in a straight line through a slit and allowed to strike a screen on the other side, we would expect to see a pattern corresponding to the size and shape of the slit. However, when this "single-slit experiment" is actually performed, the pattern on the screen is a diffraction pattern with a fairly narrow central band with ever diminishing bands parallel to it on either side



All matter in motion produces an associated velocity related KEM field

Any energy momenta added to or removed from a EM field geometry changes its related frequency & wavelengths

In the Single slit experiment the electron may pass through the slit and contribute to the resultant interference pattern

The equilateral energy distribution of the associated KEM wave photons, created by the linear momentum of the electron, produces the parallel, weaker amplitude side lines of the interference pattern

All EM fields always form v² geometries

All KEM fields are comprised of transverse Bosons and longitudinal Photons producing its associated wavefunctions and properties

Δ*hv* - *acceleration force* - Δ*Mv*

any interaction between the KEM field and the barrier will affect the energy content of the KEM field and result in velocity changes to the electron

Δ*hv* - *spectral lines* - Δ*hf*

Tetryonics 39.10 - Single slit experiment

Double slit experiments

The double-slit experiment, sometimes called Young's experiment, is a demonstration that matter and energy can display characteristics of both waves and particles, and demonstrates the fundamentally probabilistic nature of quantum mechanical phenomena and Establishes the quantum interference principle known as wave–particle duality.

Matter particles are stopped by the barrier but the [K]EM wave passes through both slits and is diffracted by them producing weaker EM waves that then superposition with each other to produce interference patterns



hv
v²
photo-electron KEM wave photon intensities
1 2 3 4 5 6 7 7 6 5 4 3 2 1
μ0
ε0
KE
p
γ1
γ2
t=1
t=2
t=1
t=2
1 2 3 4 3 2 1
1 2 3 4 3 2 1
1 2 3 4 4 4 4 4 3 2 1
final interference pattern produced will depend on phase relationships of the two super-positioned wavefronts

It is not the Particle passing through both slits that produces an interference pattern it is the particle's associated K[EM] wave

Equilateral superpositioned KEM waves produce constructive and destructive interference waves that have historically been interpreted as being circular wavefronts

electrons will be stopped by the material barrier but their associated KEM field energy momenta will be absorbed by the screen and 'tunnel through' the barrier to contribute to the interference pattern

The Compton frequency of any [K]EM wave is comprised of identical wavelength Photons which can combine to produce interference patterns

Any detector placed after the primary screen will remove energy from the secondary KEM fields and affect the interference patterns produced

In the basic version of the experiment, a coherent light source such as a laser beam illuminates a thin plate pierced by two parallel slits, and the light passing through the slits is observed on a screen behind the plate. The wave nature of light causes the light waves passing through the two slits to interfere, producing bright and dark bands on the screen — a result that would not be expected if light consisted strictly of particles. However, on the screen, the light is always found to be absorbed as though it were composed of discrete particles or photons.

If one slit is observed for the passage of the electron in order to determine its physical state then the its KEM field wave will be absorbed by the detector resulting in only one wave remaining, enforcing a classical particle outcome

Tetryonics 39.11 - Double slit experiment

Copyright ABRAHAM [2008] - all rights reserved

Light wave Reflection

Excited (or higher energy) Atoms and Molecules can emit light and energy via Electro-dynamics


0
[42-42]
N^0
e$^-$
P$^+$
45,012n


Heat
Spectral Lines
X Rays
Gamma Rays
Photo-electrons

The emitted photon/particle can go in any direction so this is the mechanism for diffuse reflection/radiation.

All Atoms and Molecules have ANGULAR charged fascia in their topologies

Incoming light interacts with a surface and may be absorbed, refelected, and/or transmitted.

Materials have a reflectance spectrum which is a function of the angle of incidence of the incoming light.

The color of an object is a function of the color spectrum of the incident light and the reflectance spectrum of the object's surface.


Angle of Incidence
equals
Angle of Reflection
Incident light
θi
θr
Absorbed
Reflected
Re-transmitted

For specular reflection the photons actually "bounce" off of the surface and are not absorbed and then re-radiated

Photon Re-Transmission


E = hν
3.2e15
E = hf
0
[42-42]
n1
4.5012e23
N^0
e$^-$
P$^+$
45,012n
Photon absorption
0
[42-42]
n8
4.501200032e23
N^0
e$^-$
P$^+$
4.5012n
3.2e15
Photon emission
E = hν
3.2e15
E = hf
0
[42-42]
n1
4.5012e23
N^0
e$^-$
P$^+$
45,012n

When a photon strikes a atom or molecule it generally imparts EM energy as heat and the photon is absorbed

For some photons their EM energy is equal to the resonance energy of the molecule.

When this happens the photon is absorbed and the molecule is put into an excited state

The molecule relaxes from the excited state back to the ground state by emitting a photon with EM energy equal to that of the original photon so the photon appears to have been reflected (but is actually absorbed then emitted)

Copyright ABRAHAM [2008] - all rights reserved

Lightwave Refraction

The refraction of light when it passes from a fast medium to a slow medium bends the light ray toward the normal at the boundaries between any two media.

The amount of bending depends on the indices of refraction of the two media and is described quantitatively by Snell's Law.

White light can be refracted into its component spectral colours



or be re-combined back into white light through superpositioning



The Fresnel equations, deduced by Augustin-Jean Fresnel describe the behaviour of light when moving between media of differing refractive indices

White Light is comprised of superpositioned waves with differing EM wavelengths

Refraction is the bending of a wave when it enters a medium where it's velocity differs to that in a vacuum

Varying refractive indices (n) of differing materials produces slower velocities of light in those materials

$c = \lambda . f$

Its wavelength increases or decreases but its frequency remains constant

$v = \lambda . f$

E
v
n2
θi
θr
n1 c
c n1
interference pattern
vphoto-dector
IR heat
n1
n2
n3
n4
n5
n6
n7
n8
Gamma rays
Microwaves
Visible Light
UV rays
visible light spectra comprise only a small percenatage of the EM spectrum

Copyright ABRAHAM [2008] - all rights reserved

Ball Lightning

An alternative radiant geometry for electromagnetic waves exists



The EM energies in radiant 'ball' lightning are transformer-couplings of energy momenta & self-sustaining until any interaction with Matter topologies occurs

Descriptions of ball lightning vary wildly. It has been described as moving up and down, sideways or in unpredictable trajectories, hovering and moving with or against the wind; attracted to, unaffected by, or repelled from buildings, people, cars and other objects.

Ball lightning has been described as transparent, translucent, multicolored, evenly lit, radiating flames, filaments or sparks, with shapes that vary between spheres, ovals, tear-drops, rods, or disks

Any interaction with a 'ball' of EM energies will result in an explosive discharge of it's EM energy momenta

Nikola Tesla was reportedly able to artificially produce 1.5" (3.8 cm) balls using spark gap technologies

Ball lightning creates a strong Magnetic moment and divergent E fields [similar to a bar magnet without the Matter] creating a "Ball' of light with varying EM energies that is sensitive to external M fields

Wave~Particle interaction-at-a-distance

All Matter in motion has both:

a standing wave energy topology [Particle] and

a divergent relativistic, Lorentz velocity corrected geometric field of mass-energy momenta [KEM Wave]


v
p
transverse bosons
longitudinal photons
KE
hv
v²
M
1 2 3 4 5 6 7 7 6 5 4 3 2 1

photo-electron KEM wave photon intensities

Whether it is Light itself or the KEM field of Matter in motion all EM fields are comprised of transverse bosons and longitudinal photons with probabillistic wave geometries

$$RE = M + KEM$$

relativistic energies *Matter* *kinetic energies*


Matter Particle
Interactive superpositioned [K]EM Waves
Matter Particle
KE
Max
p
v
KE
Max
p
v

Similar charge particles moving in the same direction experience an attractive force [Ampere]


Similarly charged particles will repel each other via their E-field interactions [Coulomb]

Matter Particle
KE
Max
p
Matter Particle
Interactive superpositioned [K]EM waves


Matter Particle
KE
Max
p
v
Matter Particle
KE
Max
p
v

Simialr charge particles moving in opposite directions experience an attractive force [Ampere]

Force fields and interaction-at-a-distance

All Matter in motion produces an associated Lorentz velocity corrected KEM field of interactive energy momenta photons

Copyright ABRAHAM [2008] - all rights reserved

Quantum Tunnelling

Charged
12
[0-12]
1.2 e20
Matter

Particles attempting to travel between potential barriers can be compared to a ball trying to roll over a hill; quantum mechanics and classical mechanics differ in their treatment of this scenario.

Classical mechanics predicts that particles that do not have enough energy to classically surmount a barrier will not be able to reach the other side. Thus, a ball without sufficient energy to surmount the hill would roll back down.

Or, lacking the energy to penetrate a wall it would bounce back (reflection) or in the extreme case, bury itself inside the wall (absorption).

In quantum mechanics, these particles can, with a very small probability, tunnel to the other side, thus crossing the barrier.

Kinetic EM energies
v
v
v²
KE
p

The quantum magician's slight of hand trick is where the incident electron is swapped another

All electrons are IDENTICAL

It is practically impossible to identify a particular electron and track it

even using spin orientations only eliminates half of the total electrons in the barrier



Absorption of Particle

When the electron is captured by an atom its KEM energies will continue to propagate until it is absorbed or makes its way out through re-emission

Reflection of Particle

KEM field 'tunnels' out

If the collision is inelastic the KEM field energy will be reduced along with the particle's velocity

Quantum KEM field tunnelling is an example of conservation of energy momenta on the atomic scale & can be likened to a unidirectional version of Newton's cradle

Removal of all electrons but the one under measurement is impractical as it would result in an attractive coloumbic force that would trap the electron in the barrier

The most probable explanation of quantum tunneling is that the original electron was bound to atoms in the material barrier and its KEM field propagated through the barrier along its original direction of momentum.

Upon reaching the opposite side/edge of the barrier its remaining energies are able to accelerate any weakly bound electron found there

Quantum 'tunnelling' is revealed to be the result of an electron's KEM wave propagation through the barrier not the electron itself


ODD hv quanta form the basis of EM induction and energy transfer
photo-electron wavefunction
mass-energy and momenta are conserved at all times in physics
μ0
μ0

The Schrodinger wavefunction of photo-electrons is comprised of 3D mass-Matter topologies and 2D KEM field mass-energy geometries

the KEM field wavefunction continues to propagate in line with its original linear momentum vector

The collapse of Matter topologies is the source of radiant stellar mass-energies not quantum tunnelling to overcome repulsive Coloumbic forces

statistical probabilities applied to quanutm tunneling processes relate to the distribution of EM Planck energy momenta quanta in the KEM field

Matter-energy conversion via GEM pinches is the source of stellar energies released in stars

photo-electron is absorbed or reflected by the material or energy potential barrier

As Planck energy momenta quanta interact or are absorbed the KEM field's wavefunction will entropy accordingly, in turn affecting the wavelength-frequency-velocity of the KEM field

$$\Delta hf = \Delta Mv = \Delta p$$


Velocity
v
p
Spectral Lines
KEM Energies
KE
hv
v²
M
12
[0-12]
1.2e20


Spectral line transitions
v
EM induction
Δv
Σv
squared energies
KEM
1
2
3
4
5
6
7
8
36
60
84
108
132
156
180
3
5
7
9
11
13
15
1²
2²
3²
4²
5²
6²
7²
8²
36
96
180
288
420
576
756
48
108
192
300
432
588
768
hv
v
c
v²
Mv²
hv,
R,
β,
p,
KE
Planck, Rydberg, Lorentz, Newton, Leibniz
uniting classical physics and relativity through equilateral geometry

Quantum tunneling plays no role in the 'fusion' of lighter elements into heavier elements in stars (which is itself an erroneous process)

Tetryonics 39.17 - mass-energy momenta induction & conservation

All Matter in motion is comprised of:

a mass-Matter standing-wave topology,
and
a KEM mass-energy field geometry

whose quantised energy momenta is reflective of the particle's vector velocity


v
1
2
3
4
5
6
7
8
3
4
5
9
7
16
9
25
11
36
13
49
15
64
Q
RE
M
KE
hv
v^2
Spectral lines
KEM wave & Particle
½ 1 3/2 2 5/2 3 7/2 7/2 3 5/2 2 3/2 1 ½
photo-electron wavefunction

The normal distribution of Planck energy momenta in any KEM field is the quantum foundation for the statistical probability mechanics of quanutm mechanics and quantum electrodynamics

Quantum Tunneling

it makes no difference
if the barrier is a EM field or material object

electrons are NOT spherical point particles


e-
Classical Picture
electron
electric field
3D
Matter
topology
Quantum Picture
electron
wave
KEM field amplitude
probability
wave
2D
mass-energy
field
1/n^2

in classical physics, the electron is repelled by an electric field as long as energy of electron is below energy level of the field

the topological Matter component of a particle's relativisitic quantum wavefunction is distinct from its Lorentz corrected KEM field mass-energy geometry

in quantum physics, the wave function of the electron encounters the electric field, but has some finite probability of tunneling through

this is the basis for transistors

quantum tunnelling is often also utilised in modern physics
as a means of overcoming Coulombic charge barriers of Protons in stars
in order to explain 'fusion' as the source of stellar energy

Tetryonics 39.17 - Quantum Tunnelling wavefunctions

Copyright ABRAHAM [2008] - all rights reserved

Relativistic Kinetic Energies

The relativistic Kinetic mass-energies of all Matter topologies in motion are contained in their KEM fields and are subject to Lorentz velocity corrections

$$KE = \frac{1}{2}M\frac{v^2}{c^2}$$

$$p^2 = E = m\frac{v^2}{c^2}$$




v
$[\frac{v}{c}]$
β
P
ε_0
μ_0
μ_0
c
v²
β²
$[\frac{v^2}{c^2}]$
c²




Charge
12
[0-12]
Leptronic field energies
Relativitic
mass-Energy
M+KE
Ψ
μ_0
ε_0
e-
Velocity
Quantum Levels
Compton Frequencies
12n
Rest Matter
Mv²
Kinetic Energies

Lorentz contractions only apply to the KEM fields of Matter in motion

The Kinetic Energies of a particle in motion can be expressed in terms of its linear momentum

$$\frac{p^2}{2m} = KE = \frac{1}{2}Mv^2$$

or equally as 1/2 the total relativistic EM mass-energies [exclusive of its invariant rest mass-Matter]

Charge and Matter topologies are Lorentz invariant


Charge
12
[12-0]
Leptronic field energies
Relativitic
mass-Energy
M+KE
Quantum Levels
Compton Frequencies
μ_0
ε_0
Ψ
e+
Velocity
12n
Rest Matter
Mv²
Kinetic Energies

Relativistic Lorentz Corrections

ges their name from their earliest appearance, in Lorentzian electrodynamics
as velocity increases the wavelengths and physical scalar geometries of Planck quanta decreases




3
1
1
1
3
4
2
5
9
n3
c


4
1
1
1
3
4
2
5
9
7
16
n4
c

Linear correction factor

$$\beta = \left[\frac{v}{c}\right]$$

Equilateral QAM contractions

$$t' = \frac{t}{\sqrt{1-\frac{v^2}{c^2}}}$$


v
p
β
ODD number transverse bosons
SQUARED number scalar energies
hv
v²
c
v-1
v-1

normal proabability distributions

Scalar correction factor

$$\beta^2 = \left[\frac{v^2}{c^2}\right]$$

'WAVE-length' contractions

$$L = L'\sqrt{1-\frac{v^2}{c^2}}$$

c^2

Matter topologies are Lorentz invariant

KEM geometries are relativistic fields

The poor definitions of EM mass & Matter has led to the incorrect application of Lorentz corrections to Matter

v v^2

all the quantum energy momenta probabilites of wavefunction distributions re-normalise [or sum] to

c c^2

Lorentz contractions apply to [K]EM waveforms only

c is the limiting velocity for the electrical acceleration of Matter

$$\sqrt{1-\beta^2}$$

Incorrectly applied to Matter topologies in motion,
The Lorentz factor or Lorentz term appears in
several equations in special relativity.

$$\sqrt{1-\left(\frac{v}{c}\right)^2}$$

The Energy of a Magnet

It is known that Maxwell's electrodynamics--as usually understood at the present time--when applied to moving bodies, leads to asymmetries which do not appear to be inherent in the phenomena. Take, for example, the reciprocci electrodynamic action of a magnet and a conductor. The observable phenomenon here depends only on the relative motionof the conductor and the magnet, whereas the customary view draws a sharp distinction between the two cases in which either the one or the other of these bodies is in motion. For if the magnet is in motion and the conductor at rest, there arises in theneighborhood of the magnet an electric field with a certain definite energy, producing a current at the places where parts of the conductor are situated. But if the magnet is stationary and the conductor in motion, no electric field arises in the neighborhood of the magnet.

In the conductor, however, we fied an electromotive force, to which in itself there is no corresponding energy, but which gives rise--assuming equality of relative motion in the two cases discussed--to electric currents of the same path and intensity as those produced by the electric forces in the former case. [On the electrodynamics of moving bodies, A. Einstein, 1905]

V

Energy can be removed by placing a conductive loop between
any Positive and Negative quanta the EM field thus creating
a potential difference & an electro-motive force

ε_0

The neutralised [K]EM fields are divergent
from a permanent magnet and create
a Magneto-static EM field with
neutral Electro-static energies

Investigation of the source of the emf produced
by magnets in conductive loops placed around them
led to the development of relativity theory



The energy of a permanent magnet is stored in
quanta of equilateral energy momenta fields that
diverge from the Magnetic moment formed
by neutralised [Positive & Negative] E-fields

Magnetic fields are produced by moving electric charges and the intrinsic magnetic moments of elementary particles associated with a fundamental quantum property, their spin. In special relativity, electric and magnetic fields are two interrelated aspects of a single object, caled the electromagnetic field tensor; the aspect of the electromagnetic field that is seen as a magnetic field is dependent on the reference frame of the observer. In QED, the electro-magnetic field is quantized and electromagnetic interactions result from the exchange of photons.

Ω

Classically, the energy of a permanent magnet
'circulates in endless loops' from North to South
in 3 dimensions around the magnetic moment

$E = h\nu$

BOSONS are
transverse EM waves
[charge carriers]

PHOTONS are
longitudinal EM waves
[neutral charge carriers]

$E = hf$







*The equilateral geometry of
ALL EM fields in relative motion
to a conductor produces a
time varying emf*

$$B = -\frac{d\phi_{\varepsilon}}{dt}$$

**A changing Electric field
produces
a changing Magnetic field**

*The is no such entity as a purely Electric field
[all fields are Electro-Magnetic in their geometric foundations]*

$$\mathcal{E} = -\frac{d\phi_{B}}{dt}$$

**A changing Magnetic field
produces
a changing Electric field**

*The is no such entity as a purely Magnetic field
[all fields are Electro-Magnetic in their geometric foundations]*

inductors

***Any two separated charge bosons
contain charged energy momenta
that once connected via a
conductive circuit will produce an emf***

*All magnetic fields store
neutral electrostatic
potentials*



permanent magnets

Copyright ABRAHAM [2008] - all rights reserved

The moving magnet - conductor problem

All permanent magnets are electromagnetic fields comprised of
transverse bosons and longitudinal photons

$$B = -\frac{d\phi_{\varepsilon}}{dt}$$

$$\varepsilon = -\frac{d\phi_{B}}{dt}$$

Observer 1 says:

The conductive loop is stationary and the magnet is moving toward it. The electrons in the loop are stationary and have no magnetic moments There is a magnetic field, but it can't produce any force on the electrons since they are stationary within the loop.

Instead, the magnetic field is changing, growing stronger as the magnet gets closer, and this changing magnetic field produces an electric field which causes forces on the electrons, and drives them around the loop producing the current in the galvanometer.

Conductor Frame of Reference
(Moving Magnet)

Charged boson field geometries contain equilateral energy momenta with transverse magnetic dipoles

We see two observers both moving, approaching each other.



Neutral photon field geometries produce electromotive forces as a result of the charged bosons that make them

Magnet Frame of Reference
(Moving Conductor)

Observer 2 says:

The magnet is stationary and the loop is moving toward it. The electrons in the loop, since they are moving with the loop, generate their own magnetic moments and experience Lorentz forces as a result of the external magnetic field [F = q v X B], which drives them around the loop and produces the current in the galvanometer.

There is no electric field.



Special relativity postulates that electric fields in one reference frame become magnetic fields in another frame

Tetryonic theory shows geometrically that the Electric and Magnetic fields are discrete, invariant geometries resulting from the equilateral 'inductive' mass-energy [Planck quanta] geometries that comprise all EM fields.

It is the relative motion of these geometries wrt a conductor that creates changing E&M field flux strengths in turn producing an emf.
When there is no relative motion in either the EM field or the conductor, no emf is produced

Copyright ABRAHAM [2008] - all rights reserved

The Electromotive Force

The electromotive force, [or emf]
or electromotance
is "that which tends to cause
a current (electrons and ions)
to flow in a conductor.



Opposite voltage emfs create
opposite forces on the same
charged particles

Transverse energy momenta
OSCILLATE CHARGES
[wrt direction of EM wave propagation]
Longitudinal energy momenta
ACCELERATE CHARGES

Opposite charged particles
experience opposing forces
due to the emf

"A source of emf can be thought of as a kind of charge pump
that acts to move a charge from a point of low potential
through its interior to a point of high potential. …
The emf of the source is defined as the work done per charge
dq: = dW/dq."



THe magneto-static fields of all Magnets are
comprised of electromagnetic fields of discrete
Planck energy momenta quanta, which
in turn are capable of accelerating
charged particles

All ElectroMagnetic fields have
distinct equilateral electric and
magnetic field geometries that produce
velocity related sinusodal waveforms

$$B = -\frac{d\phi_\varepsilon}{dt}$$



$$\varepsilon = -\frac{d\phi_B}{dt}$$



**Charged boson field geometries
can be viewed as transverse
quantum capacitors**

Lenz's law:
*"The emf induced in an electric circuit always acts
in such a direction that the current it drives around
the circuit opposes the change in magnetic flux
which produces the emf."*

**Neutral photon field geometries
can be viewed as longitudinal
quantum batteries**



The Moving Magnet problem

An electromotive Force results from
the motion of a conductor
relative to a magnetic field

A Magnet is really an electrostatic
store of neutralised emf potential differences
[creating an orthagonal Magnetic moment]

The moving magnet and conductor problem
is a famous 19th century thought experiment,
and provides the intersection for classical
and relativistic electromagnetism.

The moving magnet and conductor problem,
along with Michelson-Morley experiment,
formed the basis of Einstein's theory of
special relativity.

Relativistic theory explanation

In the frame of a conductor moving relative to the magnet, the conductor experiences a force due to an electric field.

A Magnetic field is an Electric field viewed in a differing inertial frame


N
S
In the frame of the magnet,
a conductor experiences a magnetic force.

Tetryonic theory explanation

The conductor moves through continuously changing electric and magnetic field geometries experiencing sinuodal E/M forces that are directly related to each other at all times

Electric and Magnetic fields are discrete geometrically related energies

SR requires that all observers
in inertial frames arrive at the
same form for Maxwell's equations

SR seeks to modify space and time
in a manner such that the forces
and fields transform consistently.

producing expressions that
differ from Newton's law of
motion by a factor of γ



the relativistic distortion of
accelerating spherical point charges
creates magnetic moments

Electrostatic particles have no magnetic moment

$$\vec{F} = \underbrace{q\vec{E}}_{\text{Electric force}} + \underbrace{q\vec{v} \times \vec{B}}_{\text{Magnetic force}}$$

*Once in motion it posseses a magnetic moment and kinetic energies
and is subject to Lorentz forces when it moves throuhg an external EM field*

magnetic moments are
the result of secondary KEM
fields of Matter in motion



Lorentz corrections
only all to KEM field
mass-energies

the relative motion of
geometric ElectroMagnetic fields
creates changing EM forces

Tetryonics 40.07 - The Moving Magnet problem

Copyright ABRAHAM [2008] - all rights reserved

Einstein's Error of perception

rest mass-Matter



v=0

In its rest frame the electric field of a point charge has the same strength in all directions and diverges away from the charge.

Electric fields are distorted due to relativistic speed effects to create Magnetic fields
The faster the velocity the greater the Magnetic field
At rest the Magnetic field becomes an Electric field

> What led me more or less directly to the special theory of relativity was the convicion that the electromotive force acting on a body in motion in a magnetic field was nothing else but an electric field
>
> Albert Einstein 1953



v=.6c

The SR theoretical model of a spherical charged body being relativisitically distorted as the the source of the Magnetic moments for charges in motion is incorrect

Lorentz velocity dependent factors relate only to Kinetic EM mass-energies of motion

M + *It is the KEM field mass-energies that produce Magnetic moments in relativistic partices due to the motion of ElectroStatic Matter (12 + loop inductive geometries)* = RE

Stationary Leptons are 12pi charged standing waves [Matter] topologies with NO secondary Kinetic EM mass-energies geometries

Matter is Lorentz invariant





Moving Leptons are 12pi charged standing waves [Matter] topologies with Kinetic EM mass-energies geometries



Stationary charges have Electric Fields and neutralised Magnetic fields

*The speed of light in a vacuum [c] is the limit for electrically accelerated particles
Tetryonic geometry reveals it is NOT the limit of acheivable velocities*

Moving charges have Electric fields and Magnetic moments

Tetryonics 40.08 - Einstein's Error (of perception)

Copyright ABRAHAM [2008] - all rights reserved

Tetryonic relativistic motion

The [K]EM mass-energy content of a particle in motion is velocity dependent
its rest Matter toplogy & charge geometries are velocity invariant

ε_0

μ_0 μ_0

In a frame in which the particle is at rest, we can detect only electric field



rest Matter

all Magnetic dipoles are neutral dipole pairs



Charge is a velocity invariant measure of the quantised angular momenta iof any spatial co-ordinate system

The total EM mass-energy momenta of any particle in motion is velocity dependent and is specific to particular spatial co-ordinate systems



Matter topologies are velocity invariant and their mass-energy content can only be measured in c^4 spatial co-ordinates

The [K]EM field mass-energies of any topology in motion is velocity dependent and subject to Lorentz correction within in its c^2 spatial co-ordinates

It is well demonstrated that the fields of charged particles appear different in different inertial frames

In a frame in which the particle is moving, we also see a magnetic field.



rest Matter+KEM

relativistic KEM fields produce a secondary magnetic moment



$$Mv^2 = \text{KEM} = hv^2$$

Tetryonics has revealed that the Kinetic Electro-Magnetic [KEM] field of a particle in motion has a distinct geometric identity of its own rather than being the relativistic distortion of a charged EM particle

Virtual particles and action-at-a-distance are negatived by Tetryonic KEM field mass-energy momenta and the problem of simultanity is avoided because a second particle responds not directly to the first particle, but rather to the first particle's extended, velocity related [K]EM field generated by its motion at its own position.

Copyright ABRAHAM [2008] - all rights reserved



James Clerk Maxwell



(13 June 1831 – 5 November 1879)



All quantum charge arrangements of EM mass-energy and force fields can be viewed as an arrangement of 'quantum idler wheels

"As early as 1857 Maxwell began to develop the idea of orienting molecular vortices along magnetic field lines, culminating in the publication of his paper 'On physical lines of force'…

He posited a honeycomb of vortices in which each vortex cell was separated from its neighbour by a layer of spherical particles, revolving in the opposite direction to the vortices.

These 'idler wheel' particles communicated the rotatory velocity of the vortices from one part of the field to another. In this ether model, the most famous image in nineteenth-century physics, the analogy provides mechanical correlates for electromagnetic quantities. The angular velocity of the vortices corresponds to the magnetic field intensity, and the translational flow of the idle wheel particles to the flow of an electric current; the field equations are based on the rotation of molecular vortices in the ether.

He emphasized that while the theory was mechanically conceivable, the model itself was provisional and temporary, even awkward, hardly 'a model of connexion existing in nature'



Equating Equilateral geometries to Quantised Angular Momentum reveals a classical mechanical model closely resembling Maxwell's hypothesised idler wheels that be be applied to any EM field of force

Virtual Particles

In physics, a virtual particle is a particle that exists for a limited time and space, it has become a commonplace mechanism in current Physical theories to provide a basis for the Force interactions between particles

The energy and momentum of a virtual particle are uncertain according to the uncertainty principle.

$$m^2v^4 = E^2 = p^4$$

The degree of uncertainty of each is inversely proportional to time duration (for energy) or to position span (for momentum).

Original Feymar diagram illustrating the exchange of a quantum between 2 electrons



$$mv^2 = E = pv$$

Bohr understood that if you are going to try to be mechanical, you have to show some convincing mechanics.

If you can't show some convincing mechanics, you might as well dodge all mechanics from the beginning, staying with the math.

He had learned this from Maxwell, who had done the same thing 60 years earlier.

In the 1860's, Maxwell had tried to create vortices to explain the field mechanics, but, finding himself under heavy fire from Lord Kelvin and others, he decided to give it up and go to other mathematical alternatives like quaternions instead.

ε
M
μ
ε
KE
p
KE
ε
M
μ
ε

$$m^2c^4 = E^2 - p^2c^2$$

is in-correct for superpositioned 2D KEM fields the real interaction geometry is illustrated below:

$$\frac{m\Omega^2 v^4}{2} = KE^2 = \frac{p^2v^2}{2}$$

$$KEM = mv^2$$

Superpostioned EM interaction fields



$$\frac{p^2}{2m} = KE = \frac{1}{2}Mv^2$$

$$KE = \frac{1}{2}Mv^2$$

The Force is the geometric mean of the superpositioned [KE] fields



$$KEM = pv$$

The equilateral energy geometry of Tetryonics clears up this issue once and for all, virutal particles do NOT exist. The Force interactions between all Matter in relative motion is mediated by the equilateral geometries of [K]EM mass-ENERGY momenta that spread out from their source Matter through Space-time

Equilateral geometry - the Hidden Constant



$$\overset{kg}{m}\,\Omega\,\frac{m^2}{s} = h \quad kg\,\frac{m^2}{s}$$

Quantised Angular Momenta
has an equilateral geometry



The Alpha Constant

Tetryonics has revealed
the equilateral relationships between
Charge, Planck energies and the Constants
showing quantised angular momentum to be the
'hidden' geometric constant driving the physics
of our Universe on all scales

$$\underset{\text{Charge}}{1\pi}\left[\overset{\text{EM Field}}{\underset{\text{ElectroMagnetic}}{[\varepsilon_0\mu_0]}}\cdot\overset{\text{Planck quanta}}{\left[\underset{\text{mass}}{m}\,\Omega\,\underset{\text{velocity}}{v^2}\right]}\right]$$

Alpha is the geometric coupling constant
between Magnetic and Electrical energies
that acts as a scaling constant between
Kinetic and Potential quantum energies

It is the source of the quantum charges of
all EM mass-energy momentum & inertia

Classically modelled as a 'rotational' vector Quantised Angular Momentum is in fact an Equilateral geometry



Photons are dual equilateral geometries creating a neutral charge with two opposed coupling constants

c²



Quantised Angular Momenta
creates charged EM mass-energies





.0012

2π

.007539822

$$\alpha = \frac{e^2}{\hbar c}$$



$$\alpha = \frac{e^2}{\hbar c\, 4\pi\varepsilon_0}$$

$7.297\,352\,5376(50) \times 10^{-3}$



$$= \frac{1}{137.035\,999\,679}$$

132.6291192^{-1}

The ALPHA Constant is the scalar coupling field of quantised energy momenta in superpositioned EM fields that facilitates Force (linear energy momenta) exchanges, resulting in the familiar Laws of Attraction/Interaction

In physics, the fine-structure constant is a fundamental physical constant, namely the coupling constant characterizing the strength of the electromagnetic interaction.

The numerical value of α is the same in all systems of units, because α is a dimensionless quantity.

There is a most profound and beautiful question associated with the observed coupling constant,
e the amplitude for a real electron to emit or absorb a real photon.
It is a simple number that has been experimentally determined to be close to 0.08542455.

It has been a mystery ever since it was discovered more than fifty years ago,
and all good theoretical physicists put this number up on their wall and worry about it.

Immediately you would like to know where this number for a coupling comes from:
is it related to pi or perhaps to the base of natural logarithms? Nobody knows.
It's one of the greatest damn mysteries of physics: a magic number that comes to us with no understanding by man.

We know what kind of a dance to do experimentally to measure this number very accurately,
but we don't know what kind of dance to do on the computer to make this number come out, without putting it in secretly

Richard Feynman



(May 11, 1918 - February 15, 1988)

Superpositioned Fields

equilateral energies

.0012 m²/s







0.007539822



132.6291192^{-1}

Alpha coupling Constant

You might say the "Hand of GOD" wrote that number, but "we don't know how HE pushed his pencil."

The Fine Structure Constant

$2\pi[\text{QAM}]_{.0012} = 0.007539822$

Arnold Sommerfeld introduced the fine-structure constant in 1916 as a fundamental physical constant, namely the coupling constant characterizing the strength of the electromagnetic interaction.

$2\pi[\text{QAM}]^{-1}_{.00119997} = 132.6291192$

In quantum electrodynamics, α is the coupling constant determining the strength of the interaction between electrons and their exchange photons



Similar Charges REPEL

10^{-6}

weak force



It is a dimensionless quantity that has a constant numerical value in all systems of units that is the direct result of its equilateral geometry.

1

strong force



Opposite Charges ATTRACT

$$\alpha = .007539822$$

It can now be revealed to be a measure of the forces produced by, or contained in, the geometry of two superpositioned KEM [E^2] field energies



the energy needed to overcome the electrostatic repulsion between two electrons separated by a distance of d

10^{-39}

gravity

The alpha constant applies equally to the coupling of Electric and Gravitational superpositioned fields



Gravitational Matter is always ATTRACTIVE

$7.5e^{-3}$

EM forces



the energy of a single photon of wavelength λ that provides the energy momenta required to create a force between particles

Coupling Constants

*Coulomb's [k], the Fine structure constant [α] and Newton's [G]
are all reflections of the same coupling constant geometries differing only
by the strength of their respective superpositioned energy field densities*

$$k\frac{Q_1Q_2}{r^2}=F$$

$$F=-G\frac{M_1M_2}{r^2}$$


8.99 e9
e-
k
e+
N m²
C²




Coulomb's constant
force
E²
energy momenta
d
Newton's constant


6.67 e-11
M1
G
M2
N m²
KG²

$$\beta=\left[\frac{v}{c}\right]$$

Linear force coupling constant

Coupling Constants
are dimensionless
numbers

$$\beta^2=\left[\frac{v^2}{c^2}\right]$$

Scalar energy coupling constant

They are reflective of the linear &
scalar forces produced by
2D mass-energies

In physics, a coupling constant is a number that determines the strength of an interaction
for superpositioned Electrical or Gravitational fields between material objects



$$\frac{m}{s}\cdot\frac{s}{m}$$

electric charge coupling



gravitational coupling


ε₀
KE
μ₀
μ₀
v²
c²

$$\frac{m^2}{s^2}\cdot\frac{s^2}{m^2}$$

Usually the Lagrangian or the Hamiltonian of a system can be separated into a kinetic part and an interaction part.
[For example, the electric charge of a particle is an Electrical coupling constant]

Opposites
ATTRACT

ElectroMagnetic Charge

[the universal coupling constant]

Similars
REPEL

1.33518 e-20 C

Q

1.33518 e-20 C

Electric charge is a physical property of matter that causes it to experience a force when near other electrically charged matter.
Electric charge comes in two types, called positive and negative



ElectroMagnetic CHARGE
is the equilateral foundation to
all the quantum geometries of
mass-ENERGY-Matter

$$\frac{m\,\Omega\,v^2}{c^2}$$



seconds   Changing charge geometries are equivalent to TIME in relativity   seconds

The electric charge is a fundamental conserved property of all subatomic particles, which determines their electromagnetic interaction.
The interaction between a moving charge and an electromagnetic field is the source of the electromagnetic force, which is one of the four fundamental forces

The equilateral geometry of Planck energies creates CPT symmetries in physics,
and provides the foundation for all Matter geometries and their fields of interaction

Copyright ABRAHAM [2008] - all rights reserved

Einstein–Podolsky–Rosen paradox

was a thought experiment that attempted to challenge the Copenhagen interpretation of Quantum physics

Tetryonics provides a complete model of all Energy forms and Wave-Particle interactions, allowing a clear understanding of previously mysterious actions and processes in Quantum Mechanics

Albert Einstein

(14 March 1879 – 18 April 1955)

Showing that it is possible to know the both Position and Momenta of Particles and to model EM wave geometries and interactions in Quantum Physics

Boris Yakovlevich Podolsky

(1896–1966)

Δx

Δp

Nathan Rosen

(March 22, 1909 – December 18, 1995)

The EPR experiment involved two systems that initially interact with each other and are then allowed to separate before being measured.



Measuring the Position of the Electron determines the Position of the Positron

Measuring the Momentum of the Positron determines the Momentum of the Electron

Quantum entanglement occurs when particles such as photons, electrons, etc interact physically and then become separated; this type of interaction is such that each resulting member of a pair is properly described by the same quantum mechanical state, which is indefinite in terms of important factors such as position, momentum, spin, polarization, etc

The EPR paper shows that measuring one feature of a entangled system, e.g., the momentum of one of the pair of particles, will reveal the same feature of the other particle - thus providing a mechanism for determining both the momentum and position of both particles simultaneously

Thus providing a theoretical indication that either the Uncertainty Principle was incorrect or that our understanding of Quantum Mechanics was incomplete

Spooky interactions-at-a-distance & the transfer of information

Quantum entanglement is sasid to occur when particles such as photons, electrons, and other forms of EM mass-energies interact physically and then become separated;
the type of interaction is such that each resulting member of a pair is properly described by the same quantum mechanical description (state),
which is indefinite in terms of important factors such as position, momentum, spin, polarization, etc.

Through the equilateral geomtry of Tetryonics the mass-energy-Matter of any system of particles
can be modelled in order to reveal the true EM mechanics of their quantum interactions



All EM fields have amplitude probabilies 'wavefunctions'

Longitudinal waves can facilitate instantaneous 'action-at-a-distance'

Any particles that move apart after interacting contain shared energies of motion

As these particles move apart the KEM energies present at the instant of separation remain in the systems as part of their total energies of motion

The separation of any two Charges or particles requires work to be done demanding the input of energy momentum

The separation energies form a specific energy [K]EM field geometry between (and linking) the two particles that diminishes as the particles move apart, but can still be used to predict each particle's properties and to facilitate instantaneous information flow between the particles

Information can be communicated instantaneously between vastly separated particles but their physical quantum properties are never indeterminant as dictated by the Uncertainty Principle

When two entangled particles are separated using longitudinal energies, the energy momenta of separation provides a mechanism for the establishment and near-instantaneous communication of the physical wavefunction/properties of one particle to the other, irrespective of the spatial or temporal [space-time] separation of the two 'entangled' partner particles

Spectral line differentials

$$\Delta hv = \Delta Mv = \Delta p$$

changes to energy momenta

accelerate photo-electrons

$$\frac{1}{\lambda} = \frac{R_H}{hc}\left(\frac{1}{n_1^2} - \frac{1}{n_2^2}\right)$$

Ryberg's formula is
a mathematical description
of Tetryonic energy geometry


RE
v
P
KE
ε_0
M
v
v^2
3


v
c
Bosons
R
KE
R
1
3
5
7
9
11
13
15
1^2
2^2
3^2
4^2
5^2
6^2
7^2
8^2
& produces spectral lines
Δhf
absorption
$\frac{n_i^2}{n_f^2}$
Fractional energy level transitions
$\frac{n_f^2}{n_i^2}$
emission
Photo-electrons
3/4
5/9
8/9
7/16
12/16
15/16
9/25
16/25
21/25
24/25
11/36
20/36
27/36
32/36
35/36
13/49
24/49
33/49
40/49
45/49
48/49
15/64
28/64
39/64
48/64
55/64
60/64
63/64
Un-named
Humphries
Pfund
Brackett
Paschen
Balmer
Lyman

Ryberg's constant reflects the changing
energy momentum of a transitioning electron

$$Mv^2 = KEM = hcR$$

*All of the transitions of photo-electrons
bound into a Hydrogen atom can be
revealed in the fractional geometry
of KEM field energies*

KEM field energies

Tetryonics 40.19 - Spectral line differentials



Quantum Electrodynamics

Δhv

quantum energy momenta differentials

emission
absorption
Schrodinger's wavefunctions
Rydberg constant & wavenumbers
bound photo-electrons
Photo-electrons
Spectral lines
Lyman
Balmer
Paschen
Brackett
Pfund
Humphries
un-named
180
156
132
108
84
60
36
12
48
108
192
300
432
588
768
972
p 2 3 4 5 6 7 8
quantised Planck mass-energy momenta
Spectral line transitions
Δv
Σv
KEM
48
108
192
300
432
588
768
hv, R, β, p, KE
Planck, Rydberg, Lorentz, Newton, Leibniz
Velocity
KEM Energies
Spectral Lines
hv
12
Mv²

uniting classical physics and relativity through equilateral geometry

$$hf = \Delta Mv = \Delta p$$

all spectral lines are produced by accelerating photo-electrons

the charged geometry of mass-ENERGY-Matter in motion



Tetryonic Electrodynamics

The charged geometry of mass-ENERGY-Matter in motion

Q
RE
2D
mass
3D
Matter
Spectral
lines
Waves
Particles
M
KE
KEM
energies
1
2
3
4
5
6
7
8
3
4
5
9
7
16
9
25
11
36
13
49
15
64
17
81
1/2
1
3/2
2
5/2
3
7/2
4
4
7/2
3
5/2
2
3/2
1
1/2

ISBN 978-0-987288-2-4
[Second © Edition]

Abraham

Tetryonics 40.21 - Quantum Electro-Dynamics

TETRYONICS

The charged topology of periodic & compound Matter


Q
RE
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Atomic masses
atomic shells
Molar Matter
energy levels
8
7
6
5
4
3
2
1
2
8
18
32
32
18
8
2
Z
f
d
p
s
p
d
f
M
KE
Chemical Energies

Foundational Quantum Chemistry

Abraham

ISBN 978-0-987288-3-1

[Second Edition © 2012]

Residual Electro-Magnetic Forces

allow Neutrons and Protons to attract via the opposite Electric charge points created by their constituent Quarks in order to create Elementary Nuclei

Protons + *Neutrons*

u+d+u d+u+d

All electrons, quarks and Baryons are made up of 4n+ (Tetryonic) standing-wave EM fields.

As well as having nett Tetryonic charged topologies ranging between [+24] ~ [-12] they all posses distinct ELECTRIC FIELDS that are concentrated in 3 apex points as indicated in the illustrations

These points result from the orientation of Electric apexes and orthagonal Magnetic dipole field edges that make up each particle's externalised EM fields.

The Positive and Negative electric apex points, obey the Law of Interaction forcing separated nuceli to combine due to their individual nett Tetryonic charges and provide a means of orienting nuclei to each other to create larger particles [elements, allotropes and compounds]

External Magnetic (H) fields can interact with the integral magnetic (B) dipoles of Tetryonic particles forcing them to orientate in specific directions to facilite chemical bonding [nuclear forces]

Additionally, external Electric fields can interact with the integral electric fields attracting or repelling them depending on the polarity of the external electric field [Electrostatics]

External energies can be induced into these integral EM fields via inductive coupling or the absorption of spectral photons in turn leading to an increase in the strengthes of the integral EM apexes in turn increasing the Strong Nuclear Force.





Hydrogen







Deuterium



The Strong Nuclear force binds Matter together



The orientation of the component Electric fields within 3D Matter creates macroscopic force apexes via externalised 'E-points'



Tritium



The orientation of the component Magnetic fields within 3D Matter creates macroscopic force apexes via externalised 'M-dipoles'

Nucleonic residual EM force

Neutrons

Protons

The attraction between Baryonic E&M field apexs, a result of their component Quark arrangements, results in the formation of heavier and more complex Nuclei

The residual e-field apexes and m-field dipoles form two rings of residual EM fields around the circumference of atomic nuclei







Elements & compounds follow Hexagonal packing rules

3D CAD modeling of elements courtesy of Ilene Cormier





E-field apexes and their polarities highlight the quark alignment of all atomic nuclei and elements

UP Quark
Positive Electric field apex

DOWN Quark
Negative Electric field apex

Insulators and Conductors

The position of electrons in Nuclei within Atomic Elements
results in the properties of Insulators or Conductors


0
[24-24]
e-
P+
22,500
Hydrogen

Coloumbic forces

Electrons are attracted to the residual EM net (+12) positive charge of Protons or n[+12] unbalanced Ionic charges of nuclei

Conductor

Electrical energies move around the material via boson exchanges and electron movement

0


84
Deuterium
[42-42]
120
Tritium
[60-60]

0

≈

Insulator

Electrical energy is fixed within the nucleus as electrostatic charges & released upon demand via electron rotation/motion within the nucleus


84
Deuterium
[42-42]
120
Tritium
[60-60]

Insulator atomic configurations are equivalent to Quantum convertors

0

0

Ions

Charge (energy) is moved around material via electron movement


72
Deuterium
[42-30]
108
Tritium
[60-48]

12

12

Conductive materials contain 'free' electrons that can be readily or easily moved within the material

Insulator materials have electrons that are 'bound' tightly to the atoms and store charges locally where they are applied

Materials that have been ionised are more likely to become Conductors as they easily attract and bind free electrons to them

Copyright ABRAHAM [2008] - All rights reserved

Nucleon Quark Arrangement

The nuclei arrangement of each atomic shell [quantum level] is the result of quark EM field interactions

Quantum levels

Atomic shells


n8
n7
n6
n5
n4
n3
n2
n1
R
Q
P
O
N
M
L
K
13
1
9
3
1
3
9
11
7
5
7
5
4
5
1
1
2
2
6
8
6
3
6
8
12
4
2
10
10
4
2
14
u
d
+
–

Nucleon Charges and Bonding


quark
charges
nucleon
charges

(Strong force - topological Electric Points)



residual EM forces



(Strong force - topological Magnetic dipoles)

Bound electron arrangements

Externally bound electrons produce sub-orbital patterns different to the electron orbitals of internally bound electrons



Deuterium

electrons are externally bound to the Deuteron nuclei



Deuterium

electrons are internally bound in the Deuteron nuclei







Conductors

Charges are free to move and equalise

electrons require less energy to 'break free' from Nuclei

The electron orbitals of conductors are lower energies than those of insulators

Insulators

Charges are bound to specific locations

electrons require more energy to 'break free' from Nuclei

Copyright ABRAHAM [2008] - All rights reserved

2D mass-energy geometries form the fabric of 3D Matter topologies







Proton

12
[24-12]

nett Charge
component charges



charged mass-energy geometry

20π

Matter topology

12
[42-30]



40π

Deuteron

nett Charge
component charges

0
[18-18]

charged mass-energy geometry



Matter topology

20π

Neutron



Charge provides the framework for the mass-energy geometry of Matter

Copyright ABRAHAM [2008] - All rights reserved



Neutron

All Matter topologies are the result of charged EM mass-energy geometries

Matter

Baryons Planck quanta

$$\frac{36\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

mass-energy

Matter

Baryons Planck quanta

$$\frac{36\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

mass-energy

Deuterons

are the building blocks of
all periodic elements and compounds

Proton

Tetryonics 42.02 - Nuclei formation

Copyright ABRAHAM [2008] - All rights reserved

Strong Forces and Nuclear Bonding

How do Baryons with Positive and Neutral charges
attract each other and bind to form stable elements ?


P
N
u
10-2
u
10-2
d
4-8
+
-
d
4-8
d
4-8
u
10-2

Charged EM fascia
Electric fields & Magnetic dipoles

Protons & Neutrons are attracted to each other through their equal but opposite charge fascia of their Matter topologies


[10-2]
[4-8]
[10-2]
12
[42-30]
72
P
N
[4-8]
[10-2]
[4-8]
[4-8]
[10-2]
[4-8]
N
P
72
12
[42-30]
[10-2]
[4-8]
[10-2]

Once nuclei have been created their external electric fields & magnetic dipoles continue to attract and bind individual nuclei together via the Residual EM Force as nuclei seek charge equilibrium by combining with each other and electrons to form neutral elements


36
0
[18-18]
+
=
72
12
[42-30]
36
12
[24-12]


84
84
84
84
84
84
84
84
d
u
1
2
3
4
5
6
0
[42-42]
Z

The attraction and binding of Protons and Neutrons
through their electric charge imbalances
creates Deuterons which have +12 charges

The residual Z[+12] charge is what attracts electrons
to form neutral atomic nuclei via Coulombic attraction

Copyright ABRAHAM [2008] - All rights reserved

Strong Nucleonic Bonding





+

In addition to the Strong colour force
a separate residual binding force arises
from the external apexes formed by
Positive and Negative Electric points of quarks
in each Baryon [nuclear-chemical bonds]

-



All energy seeks equilibrium

Strong E-force
nuclear linkages

External Electric field points
bind via Charge fascia interactions
with Plus and Minus Electric points
combining and sharing energy
throughout the resultant nuclei



● Positive Electric field apex

Negative Electric field apex ●

Hydrogenic vs Nucleonic electron binding

If a unbound Proton attracts an Electron
the Electron can be bound to the nuclei
in a number of differing orientations
[each with differing spin energies]


12
[24-12]
N
S
+
Proton
+
12
[0-12]
S
N
electron
=
nuclear spin coupled
Bohr magneton
0
[24-24]
S
N
+
Hydrogen

The energy levels of Baryons determines the KEM field energy of bound electrons

All atomic nuclei (and elements) are Deuteron'ic nuclei with a mixture of *orthagonal*, parallel and anti-paralllel spin orientations

(this is why Rydberg is less accurate for elemental nuclei compared to Hydrogenic atoms - see QM spin)


12
[42-30]
N
S
−
+
Deuteron
+
12
[0-12]
S
N
electron
=
Spin DOWN electron coupling
[anti-parallel moments]
0
[42-42]
Deuterium

Bohr magnetons are always referenced wrt the Nuclear magneton


12
[42-30]
N
S
−
+
Deuteron
+
12
[0-12]
N
S
electron
=
Spin UP electron coupling
[parallel moments]
0
[42-42]
Deuterium

Electrons can be bound to deuteron nuclei
in four distinct orientations [2 horizontal & 2 vertical]
with each spin coupling orientation producing
differing energy electron orbitals
[wrt to the nuclear magnetic moments]

Ejecting electrons from atomic nuclei
by adding energies to their KEM fields
[the Photoelectric effect]
creates Positive Ions

Vertically orientated electrons
within Proton-Neutron Nuclei [Deuterons]
create quantum synchronous convertor geometries

electrons produce stronger magnetic moments due to their mass-charge quotient

Copyright ABRAHAM [2008] - All rights reserved

Atomic Nucleus Master Template

Nucleon Number Z

1 Proton [24-12]
1 electron [0-12]
1 Neutron [18-18]


R 8
Q 7
P 6
O 5
N 4
M 3
L 2
K 1
f 7
1-14 Actinoid
1-14 Lanthanoid
d 5
9-10 Post Transition Metal
1-8 Transition Metal
p 3
6 Noble Gas
5 Halogen
1-4 Non-Metal Metaloid Poor-Metal
s 1
2 Alkaline Earth
1 Alkali Metal
Shell
Energy level
Orbitals
sub orbital
Family


Neutrons
Protons
u
d
Md Tm 13
Ac La 1
Pa Pr 3
Rg Au Ag Cu 9
Bk Tb 9
Lr Lu Y Sc 1
Db Ta Nb V 3
Es Ho 11
Mt Ir Rh Co 7
Bh Re Tc Mn 5
Am Eu 7
At I Uus Br Cl F 5
Po Te Lv Se S O 4
Np Pm 5
Cs Rb Fr D K Uun Li Na 1
Tl In Uut Ga B Al 1
Pb Sn Fl Ge C Si 2
Ba Sr Ra He Ca Ub Be Mg 2
Pu Sm 6
Hs Os Ru Fe 6
Bi Sb Uup As N P 3
Rn Xe Uuo Kr Ne Ar 6
Ds Pt Pd Ni 8
Cm Gd 8
Fm Er 12
Sg W Mo Cr 4
Rf Hf Zr Ti 2
Cf Dy 10
Cn Hg Cd Zn 10
U Nd 4
Th Ce 2
No Yb 14


Spin 1/2
electrons
μ_B
Bohr magnetons are referenced to the Nuclear magneton
μ_N
S
N
electrons
Spin 1/2

○ **s** *1 sub-Orbital (2 electrons max)*
○ **p** *3 sub-Orbitals (6 electrons max)*
○ **d** *5 sub-Orbitals (10 electrons max)*
○ **f** *7 sub-Orbitals (14 electrons max)*

Copyright ABRAHAM [2008] - All rights reserved

The Chemical elements

Elemental family groupings are a reflection of atomic sub-orbitals within elemental atoms


f 7
1-14 Actinoid
1-14 Lanthanoid
d 5
9-10 Post Transition Metal
1-8 Transition Metal
p 3
6 Noble Gas
5 Halogen
1-4 Non-Metal Metaloid Poor-Metal
s 1
2 Alkaline Earth
1 Alkali Metal
Orbitals
sub orbital
Family
Quantum numbers
l Azmithal
Orbitals
m orbitals
s sub-orbitals
R Q P O N M L K
Atomic Shells
8 7 6 5 4 3 2 1
Energy levels
s p d f
Orbitals & sub-Orbitals

Tetryonics 43.02 - The Chemical Elements

Copyright ABRAHAM [2008] - All rights reserved

Element Numbers

Z * 1 Proton [24-12]
1 Neutron [18-18]
1 electron [0-12]

Each elemental nuclei is made from Deuterium


R
8
Q
7
P
6
O
5
N
4
M
3
L
2
K
1
f 7
1-14
Actinoid
1-14
Lanthanoid
d 5
9-10
Post Transition Metal
1-8
Transition Metal
p 3
6
Noble Gas
5
Halogen
1-4
Non-Metal Metaloid Poor Metal
s 1
2
Alkaline Earth
1
Alkali Metal
Shell
Energy level
Orbitals
sub orbital
Family

○ **s** *1 sub-Orbital (2 electrons max)*

○ **p** *3 sub-Orbitals (6 electrons max)*

○ **d** *5 sub-Orbitals (10 electrons max)*

○ **f** *7 sub-Orbitals (14 electrons max)*


101 13 69
13
89 1 57
1
91 3 59
3
111 79 9 47 29
9
103 71 1 39 21
1
105 73 3 41 23
3
97 9 65
9
99 11 67
11
109 77 7 45 27
7
107 75 5 43 25
5
95 7 63
7
93 5 61
5
85 53 117 5 35 17 9
5
84 52 116 4 34 16 8
55 37 87 1 19 119 11 3
1
81 49 113 1 31 13 5
1
82 50 114 2 32 14 6
2
56 38 88 2 20 120 12 4
2
83 51 115 3 33 15 7
3
86 54 118 6 36 18 10
6
94 6 62
6
96 8 64
8
108 76 6 44 26
6
110 78 8 46 28
8
100 12 68
12
98 10 66
10
106 74 4 42 24
4
104 72 2 40 22
2
112 80 10 48 30
10
92 4 60
4
90 2 58
2
102 14 70
14

Atomic shells

There are a maximum of 120 elements possible



Energy levels

Element Names

Z * 1 Proton [24-12]
1 Neutron [18-18]
1 electron [0-12]


R
8
Q
7
P
6
O
5
N
4
M
3
L
2
K
1
f 7
1-14
Actinoid
1-14
Lanthanoid
d 5
9-10
Post Transition Metal
1-8
Transition Metal
p 3
6
Noble Gas
5
Halogen
1-4
Non-Metal Metaloid Poor-Metal
s 1
2
Alkaline Earth
1
Alkali Metal
Shell
Energy level
Orbitals
sub orbital
Family

○ s 1 sub-Orbital (2 electrons max)

○ p 3 sub-Orbitals (6 electrons max)

○ d 5 sub-Orbitals (10 electrons max)

○ f 7 sub-Orbitals (14 electrons max)

There are a maximum of 120 elements possible


13
Md
13
Tm
Ac
1
La
1
Pa
3
Pr
3
Rg
Au
9
Ag
Cu
9
Bk
9
Tb
9
Lr
Lu
1
Y
Sc
1
Db
Ta
3
Nb
V
3
Es
11
Ho
11
Mt
Ir
7
Rh
Co
7
Bh
Re
5
Tc
Mn
5
Am
7
Eu
7
At
I
Uus
5
Br
Cl
F
5
4
Po
Te
Lv
4
Se
O
S
Np
5
Pm
5
1
Cs
Rb
Fr
D
1
K
Uun
Li
Na
1
Tl
In
Uut
1
Ga
B
Al
Pb
Sn
Fl
2
Ge
C
Si
2
Ba
Sr
Ra
He
2
Ca
Ub
Be
Mg
2
Pu
6
Sm
6
Hs
6
Os
6
Ru
Fe
Bi
Sb
Uup
3
As
N
P
3
Rn
Xe
Uuo
6
Kr
Ne
Ar
6
8
Ds
Pt
8
Pd
Ni
Cm
8
Gd
8
12
Fm
12
Er
Sg
4
W
4
Mo
Cr
10
Cn
Hg
10
Cd
Zn
2
Rf
Hf
2
Zr
Ti
Cf
10
Dy
10
4
U
4
Nd
Th
2
Ce
2
No
14
Yb
14

Atomic shells
P
O
Q
K
N
R
L
M

They were originally named according to their properties by their discoverer but have recently been named after famous scientists

6
5
7
1
4
8
2
3
Energy levels

Electron orbital configurations

A huge number of differing d and f orbital configurations are possible given the number of nuclei and bond points created by elemental topologies


85 53 117 5 35 9 17
55 37 87 1 19 119 11 3
84 52 116 4 34 8 16
81 49 113 1 31 5 13
56 38 88 2 20 120 4 12
82 50 114 2 32 6 14
83 51 115 3 33 7 15
86 54 118 6 36 10 18

As the number of nucleons increases so does the complexity of the electron orbitals possible

quantum snowflakes

However all have a stable 'core' grouping of nuclei comprised of s and p electron orbitals


At I Uus 5 Br F Cl
Cs Rb Fr D 1 K Uue Li Na
Po Te Uuh 4 Se O S
Tl In Uut 1 Ga B Al
Ba Sr Ra He 2 Ca Ubn Be Mg
Pb Sn Uuq 2 Ge C Si
Bi Sb Uup 3 As N P
Rn Xe Uuo 6 Kr Ne Ar


d
f
s
p
1
2
3
4
5
6

All nuclei bonding closely follows hexagonal packing rules

Atomic Nucleus
Exploded view

1 Proton	[24-12]
1 electron	[0-12]
1 Neutron	[18-18]


R
8
Q
7
P
6
O
5
N
4
M
3
L
2
K
1
f 7
1-14
Actinoid
1-14
Lanthanoid
d 5
9-10
Post Transition Metal
1-8
Transition Metal
p 3
6
Noble Gas
5
Halogen
1-4
Non-Metal Metaloid Poor-Metal
s 1
2
Alkaline Earth
1
Alkali Metal
Shell
Energy level
Orbitals
sub orbital
Family

○	s	1 sub-Orbital	(2 electrons max)
○	p	3 sub-Orbitals	(6 electrons max)
○	d	5 sub-Orbitals	(10 electrons max)
○	f	7 sub-Orbitals	(14 electrons max)


Atomic shells
P O Q K N R L M
1 Cs Rb Fr H K Uun Li Na
2 Ba Sr Ra He Ca Ub Be Mg
3 Tl In Uut Ga B Al
4 Pb Sn Fl Ge C Si
5 Bi Sb Uup As N P
6 Po Te Lv Se O S
7 At I Uus Br F Cl
8 Rn Xe Uuo Kr Ne Ar
9 Lr Lu Y Sc
10 Rf Hf Zr Ti
11 Db Ta Nb V
12 Sg W Mo Cr
13 Bh Re Tc Mn
14 Hs Os Ru Fe
15 Mt Ir Rh Co
16 Ds Pt Pd Ni
17 Rg Au Ag Cu
18 Cn Hg Cd Zn
19 Ac La
20 Th Ce
21 Pa Pr
22 U Nd
23 Np Pm
24 Pu Sm
25 Am Eu
26 Cm Gd
27 Bk Tb
28 Cf Dy
29 Es Ho
30 Fm Er
31 Md Tm
32 No Yb
6 5 7 1 4 8 2 3
Energy levels

Copyright ABRAHAM [2008] - All rights reserved



Atomic radii of elements

The Mendeleev block arrangement of periodic elements
presents a number of problems in representing
the true topologies and properties of
all the periodic elements:

Questions are raised over Hydrogen's appropriate position in the table

The table correctly positions elements according to their elemental properties but offers no insight into the individual geometries of the periodic elements themselves

The table does not reflect the charged quantum geometries of nuclei in each atomic shell

The table is unable to accurately reflect the electron orbitals or other elemental properties described by the Bohr & Schrodinger models

The table maps the atomic number (the number of protons in an atom), not atomic weight in determining the order of the elements in the table resulting in a number of errors in periodic element placements

'f' orbitals elements are not normally presented in their true atomic number positions

Tetryonic charge geometry rectifies all of these deficiencies

Tetryonics 43.07 - Atomic radii of elements

PERIODIC TABLE OF ELEMENTS

modelled on the polar view of the charge topologies of periodic elements

84
[42-42]



Deuterium [not Hydrogen] is the building block of all elements


Energy levels
P
6
O
5
Q
7
K
1
R
8
N
4
2
L
3
M
Atomic shells


electron orbitals
f
d
p
s
2
6
10
14
electron sub-orbitals


Md 13 Tm 13
Ac La 1 1
Pa Pr 3 3
Rg Au Ag Cu 9 9
Bk Tb 9 9
Lr Lu Y Sc 1 1
Db Ta Nb V 3 3
Es Ho 11 11
Mt Ir Rh Co 7 7
Bh Re Tc Mn 5 5
Am Eu 7 7
At I Uus Br Cl F 5 5
Cs Rb Fr D K Uun Li Na 1 1
Po Te Lv Se O S 4 4
Np Pm 5 5
Tl In Uut Ga B Al 1 1
Ba Sr Ra He Ca Ub Be Mg 2 2
Pb Sn Fl Ge C Si 2 2
Pu Sm 6 6
Hs Os Ru Fe 6 6
Bi Sb Uup As N P 3 3
Rn Xe Uuo Kr Ne Ar 6 6
Ds Pt Pd Ni 8 8
Cm Gd 8 8
Fm Er 12 12
Sg W Mo Cr 4 4
Cn Hg Cd Zn 10 10
Rf Hf Zr Ti 2 2
Cf Dy 10 10
U Nd 4 4
Th Ce 2 2
No Yb 14 14

Periodic element families


R 8
Q 7
P 6
O 5
N 4
M 3
L 2
K 1
f 7
1-14 Actinoid
1-14 Lanthanoid
d 5
9-10 Post Transition Metal
1-8 Transition Metal
p 3
6 Noble Gas
5 Halogen
1-4 Non-Metal Metaloid Poor-Metal
s 1
2 Alkaline Earth
1 Alkali Metal
Shell
Energy level
Orbitals
sub orbitlas
Family

3D quantum charge geometry of periodic element nuclei


quantum numbers
3 2 1 0 1 2 3
R Q P O N M L K
Atomic Shells
2 8 18 32 32 18 8 2
Z
8 7 6 5 4 3 2 1
Energy levels
d p s p d f
Sub-orbitals



THE ATOMIC NUCLEUS

the charged quantum mass-energy geometry of periodic element topologies

Neils Bohr
(7 October 1885 – 18 November 1962)
NEILS BOHR
Erwin Schrödinger
[12 August 1887 – 4 January 1961]
SCHRÖDINGER
quantum numbers
3
2
1
0
1
2
3
Atomic Shells
R
Q
P
O
N
M
L
K
2
8
18
32
32
18
8
2
Z
8
7
6
5
4
3
2
1
Energy levels
f
d
p
s
p
d
f
electron orbitals

The Bohr model gives us a basic conceptual model of electrons orbits and energies, along with the idea of quantum jumps.

The Schrondinger wave equation gives precise details of spectra and electron position and motions within the nuclei

The uncertainty principle erroneously dictates that position and momentum cannot be simultaneously determined.

Copyright ABRAHAM [2008] - All rights reserved

Periodicity of atomic elements

An electron shell may be thought of as an orbit followed by electrons around an atom's nucleus.
The closest shell to the nucleus is called the "1 shell" (also called "K shell"), followed by the
"2 shell" (or "L shell"), then the "3 shell" (or "M shell"), and so on further and further from the nucleus.
The shell letters K, L, M, ... are alphabetical

Each shell can contain only a
fixed number of deuterium nuclei
[Protons, Neutrons & electrons]

Each shell consists of one or more
electron orbitals, and each orbital consists
of one or more sub-orbitals.

8
atomic
energy shells
with electrons



120
periodic
elements
in total

The number of deuterium nuclei that form each atomic shell in an
elemental atom number is double that of Photon energy levels

Each atomic shell equates to a specific
energy level for the Deuterium nuclei
that comprise it with in turn affect the
angular momentum of electrons in that shell

The electrons in the partially filled
outermost atomic shell [or highest energy level]
determine the chemical properties of the atom;
they are called valence shell electrons.

Tetryonics 44.02 - Periodicity of atomic elements

Copyright ABRAHAM [2008] - All rights reserved


Side View
Quantum numbers
0
1
1
2
2
3
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
8
18
32
32
18
8
2
n
atomic shells
energy levels
f
f
d
d
p
p
s
electron orbitals
Top View
ℓ
m
f d p s p d f
7 + 5 + 3 + 2 + 3 + 5 + 7
5, 11, 3, 13, 1, 9, 7 8, 2, 10, 4, 6 5, 1, 3 1-2 6, 2, 4 7, 1, 9, 3, 5 6, 12, 4, 14, 2, 10, 8
Quantum numbers
0
1
1
+1 0 -1
-1 0 +1
2
2
+2 +1 0 -1 -2
-2 -1 0 +1 +2
3
3
+3 +2 +1 0 -1 -2 -3
-3 -2 -1 0 +1 +2 +3
Z
13 11 9 7 5 3 1
2 4 6 8 10 12 14
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 2
Atomic Shells
Energy levels
Orbitals & sub-Orbitals

Atomic shells & energy levels

Using the charge geometries of equilateral mass-energies in Matter topologies all period elements can be accurately modelled

Tetryonics 44.03 - Shells & energy levels

atomic Shells


s
s + p
s + p + d
s + p + d + f
s + p + d + f
s + p + d
s + p
s

energy levels


Azmithal quantum number
3 2 1 0 1 2 3
R Q P O N M L K
atomic shell
8 7 6 5 4 3 2 1
energy level
ℓ
f d p s p d f

Electron orbitals



quantum numbers

Each electron's location in
an elemental nuclei is defined
by its quantum numbers

All atoms have shells comprised of concentric s, p, d & f electron orbitals

electron orbitals

each electron orbital can hold a maximum of two spin opposed electrons

a core s-orbital
surrounded by
3 p-orbitals
5 d-orbitals and
7 f-orbitals

Azmithal & Magnetic numbers


0
1 1
+1 0 -1 -1 0 +1
2 2
+2 +1 0 -1 -2 -2 -1 0 +1 +2
3 3
+3 +2 +1 -1 -2 -3 -3 -2 -1 +1 +2 +3
f d p s p d f
1 4 9 16 16 9 4 1
13 11 9 7 5 3 1 2 4 6 8 10 12 14
f f
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
R Q P O N M L K
8 7 6 5 4 3 2 1

Atomic Shells

Energy levels

Orbitals & sub-Orbitals


magnetic quantum numbers
m
s p d f
14 10 6 2
Azmithal & Magnetic numbers
+3 +2 +1 0 -1 -2 -3
R Q P O N M L K
Shell
atomic shells
2 8 18 32 32 18 8 2
electrons per shell
Nuclei
f d p s p d f
electron Orbitals & sub-orbitals
electron sub-orbitals
each eatomic orbital can hold two spin opposed electrons
s K 2
H D He
s+p 2+6 L 8
Li Be B C N O F Ne
s+p+d 2+6+10 M 18
Na Mg Al Si P S Cl Ar K Ca Sc Ti V Cr Mn Fe Co Ni Cu Zn
s+p+d+f 2+6+10+14 N 32
s+p+d+f 2+6+10+14 O 32
s+p+d 2+6+10 P 18
s+p 2+6 Q 8
s R 2
Uun Ub
120 elements in 8 quantum levels
[+ Hydrogen as a free radical]

Tetryonics 44.05 - Electron sub-Obitals

Electron SPIN in atoms

1 sub-Orbit	s	*2 electrons*
3 sub-Orbits	p	*6 electrons*
5 sub-Orbits	d	*10 electrons*
7 sub-Orbits	f	*14 electrons*

Hund's Rule

Each electron sub-orbital (Azimuthal number)
can not have electrons with the same spin direction


S
s
p
d
f
14
10
6
2


f 14
1,3,5,7,10,12,14
2,4,6,8,9,11,13
d 10
1,3,6,8,10
2,4,5,7,9
p 6
2,3,6
1,4,5
s 2
1
2

electron spin is always referenced to the Nuclear magneton


azmithal & magnetic quantum numbers
+3
+2
+1
0
-1
-2
-3
Atomic shells
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
energy levels
Z
2
8
18
32
32
18
8
2
1,3,5,7,9,11,13
1,3,5,7,9
1,3,5
1-2
2,4,6
2,4,6,8,10
2,4,6,8,10,12,14
f
d
p
s
p
d
f
electron orbitals & sub-orbitals


KE
S
N
α
Spin down
Spin up
β
KE
α
β
N
S
μ z
α
Spin up
Spin down
β
KE
KE

Tetryonics 44.06 - Electron spin

Copyright ABRAHAM [2008] - All rights reserved

Quantum numbers


Energy levels
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
2
2
3
3
2
8
18
32
n
32
18
8
2
f
f
d
d
p
p
s
Atomic Shells
3
2
1
0
1
2
3
+3, +2, +1, 0 -1, -2, -3
+2, +1, 0, -1, -2
+1, 0, -1
0
-1, 0, +1
-2, -1, 0, +1, +2
-3, -2, -1, 0 +1, +2, +3
Electron SPINS

These four numbers, n, ℓ, m and s can be used to describe any electron in a stable atom [and can be mapped back to the classical terminology of Shells and electron orbitals].

The properties of every atom's specific electron configuration can be described by four quantum numbers:

n (1-8)
Principal
(n = 1, 2, 3, 4 ...)

ℓ (0-3)
Azimuthal
(l = 0, 1 ... n−1)

m (2ℓ+1)
Magnetic
(ml = −l, −l+1 ... 0 ... l−1, l)

S ±½
electron Spin
(ms = −1/2 or +1/2),

The Bohr model was a one-dimensional model that used one quantum number to describe the distribution of electrons


ℓ
0
1
2
3
14
10
6
2
ms

The three coordinates that come from Schrödinger's wave equations are the principal (n), angular (l), and magnetic (m) quantum numbers.

These quantum numbers describe the size, shape, and orientation in space of the orbitals of any particular atom mathematically.

Each electron's quantum numbers are unique and cannot be shared by another electron in that atom.


Azmithal & Magnetic numbers
Energy levels
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
2
2
3
3
+1
0
-1
-1
0
+1
+2
+1
0
-1
-2
-2
-1
0
+1
+2
+3
+2
+1
0
-1
-2
-3
-3
-2
-1
0
+1
+2
+3
2
8
18
32
Z
32
18
8
2
13
11
9
7
5
3
1
2
4
6
8
10
12
14
f
f
9
7
5
3
1
2
4
6
8
10
d
d
5
3
1
2
4
6
p
p
1
s
2
Atomic Shells
Orbitals & sub-Orbitals

A stable atom has equal numebrs of Protons, electrons [and Neutrons], all following the Pauli Exclusion Principle thus orientating their spins so that each element has a unique electron configuration

Copyright ABRAHAM [2008] - All rights reserved

PRINCIPAL quantum number

The first describes the electron shell, or energy level, of an atom.

This is the only quantum number
introduced by the Bohr model

n(1-8)

(n = 1, 2, 3, 4 ...)

The principal quantum number
can only have positive integer values

atomic shells

energy levels



As energies of the Baryons comprising the atomic nuclei increases,
the electron bound to each nuclei also possesses more KEM field energies
and is therefore less tightly bound to the nucleus

Atomic Shells



(K, L, M, N, O, P, Q, R)

Atomic shells relate directly to Principal quantum numbers

(1, 2, 3, 4, 5, 6, 7, 8)

Energy levels



AZMITHAL quantum number

The azimuthal quantum number is a quantum number assigned to any atomic orbital that describes its orbital angular momentum and determines the shape of the electron orbital


orbitals
Shells
N
4
s+p+d+f
M
3
s+p+d
L
2
s+p
K
1
s
Principal Quantum Number
(1,2,3,4)


Shells
S
8
R
s+p
7
Q
s+p+d
6
P
s+p+d+f
5
O
orbitals
Principal Quantum Number
(5,6,7,8)

s p d f

electron orbitals

(l = 0, 1 ... n−1)

ℓ (0-7)
Azimuthal


3
3
3
2
3
2
2
3
2
2
3
1
1
0
Azimuthal Quantum number (l)
1
1
n 1-4
l = (n-1)
0
3
1
1
3
2
2
2
2
3
3
2
3
3
3


4
4
4
5
4
5
5
4
5
5
4
6
6
4
7
Azimuthal Quantum number (l)
6
6
n 5-8
l = (n-1)
7
4
6
6
4
5
5
4
5
5
4
4
4
5
4

Care must always be taken
to never confuse
Orbital Angular Momentum
[rotation about a point in atoms]
with
Quantised Angular Momenta
[equilateral Planck energy geometries]

MAGNETIC quantum number


Shells
N
M
L
K
4
3
2
1
s+p+d+f
s+p+d
s+p
s
orbitals
electrons per shell
32
18
8
2
Principal Quantum Number
(1,2,3,4)

The magnetic quantum number denotes the energy levels available within any subshell

Magnetic numbers do not continue to increase as the Principal numbers increase instead they reverse after n4 to reflect the charged quanutm geometry of Elements and do not follow the current computer models in popular use


electrons per shell
2
8
18
32
Shells
S
8
R
s+p
7
Q
s+p+d
6
P
s+p+d+f
5
O
orbitals
Principal Quantum Number
(5,6,7,8)

s p d f

electron sub-orbitals

(ml = –l, –l+1 ... 0 ... l–1, l)

$m\ell\,(2\ell+1)$

Magnetic


Magentic Quantum number (l)
n 1-4
l = (n-1)


Magentic Quantum number (l)
n 5-8
l = (n-1)

Z

120 is the maximum elemental number possible

Copyright ABRAHAM [2008] - All rights reserved

parallel magnetic moments

Spin UP

higher coupling energies

SPIN quantum number

The spin quantum number is a quantum number that parameterizes
the intrinsic angular momentum (or spin angular momentum),
of any given electron anywhere in an atomic nucleus

anti-parallel magnetic moments

Spin DOWN

lower coupling energies

Electron spin can orientate in either direction within Nuclei, providing the nett spins follow the Hund rule and Pauli exclusion principle




Spin +1/2
KE
μ_B
e-
(ms = −1/2 or +1/2)
Spin -1/2
KE
μ_B
d
μ_B
μ_N
p
KE
μ_B
(ms = −1/2 or +1/2)
e-
KE
μ_B
KE
Spin -1/2
Spin +1/2

electron Spin is referenced to the Nuclear magneton


n8
n7
n6
n5
n4
n3
n2
n1
−
+

The nuclear energy levels of the Baryons comprising Elemental nuclei determine the energy-momenta of electrons bound to them

Copyright ABRAHAM [2008] - All rights reserved

Modifying Hund's Rule

Electrons fill orbitals in an alternating sequential numbering pattern due to nucleon placement creating opposed direction electron spins

The increased stability of the atom, most commonly manifested in a lower energy state, arises because the high-spin state forces the unpaired electrons to reside in different spatial orbitals.

A commonly given reason for the increased stability of high multiplicity states is that the different occupied spatial orbitals create a larger average distance between electrons, reducing electron-electron repulsion energy. In reality, it has been shown that the actual reason behind the increased stability is a decrease in the screening of electron-nuclear attractions[1].

The total spin state is calculated as the total number of unpaired electrons + 1, or twice the total spin + 1 written as 2s+1.

As a result of Hund's rule, constraints are placed on the way atomic orbitals are filled using the Aufbau principle.

Before any two electrons occupy an orbital in a subshell, other orbitals in the same subshell must first each contain one electron. Also, the electrons filling a subshell will have parallel spin before the shell starts filling up with the opposite spin electrons (after the first orbital gains a second electron).

As a result, when filling up atomic orbitals, the maximum number of unpaired electrons (and hence maximum total spin state) is assured

Sub-orbitals fill in order of numbering

Electrons spins pair before next orbital is filled

ie.

p1 [DOWN] and p2 [UP] fill
before
p3 [UP] and p4 [DOWN]
before
p5 [DOWN] and p6 [UP] etc

s	p	d	f
▲ 1 1 2 ▼	▼ 1 1 2 ▲	▲ 1 1 2 ▼	▲ 1 1 2 ▼
	▲ 3 2 4 ▼	▲ 3 2 4 ▼	▲ 3 2 4 ▼
	▼ 5 3 6 ▲	▼ 5 3 6 ▲	▲ 5 3 6 ▼
		▼ 7 4 8 ▲	▲ 7 4 8 ▼
		▼ 9 5 10 ▲	▼ 9 5 10 ▲
			▼ 11 6 12 ▲
			▼ 13 7 14 ▲

▲

Hund's rule of orbital filling
must be modified to reflect
the true orbital filling order

▼



Copyright ABRAHAM [2008] - All rights reserved

Principle quantum Energies



In an atom - electron energies are proportional to their intrinsic Kinetic Energies - which in turn are directly proportional to the quantum energy level of the nuclei which the electron binds to in their respective atomic shells

In a nucleus, lower energy orbits have less 'paired' nuclei supplying energy. The more energy you give a nuclei the faster it casuses the bound electron to rotate. If you give the nuclei enough energy, it will impart eneough energy to its electron for it to leave the system entirely.

The same is true for an electron orbital. Higher values of n mean more energy for the electron and the corresponding KEM field enegies of the electron is larger, resulting in increased angular momentum.

Values of n start at 1 and go up by integer amounts.

If enough energy is added to the system by incident Photons a electron will leave the atom creating a positively charged nuclei [ionisation].





s orbits n1-8
p orbits n2-7
d orbits n3-6
f orbits n4-5

Eigenstate value

KEM field energy [per n] required to exceed 13.525 eV at which point the photo-electron has sufficient KE to break free of the Nucleus

$$E_n = \frac{E_1}{n^2} = \frac{-13.6eV}{n^2}, n = 1, 2, 3...$$

The possible Kinetic Energies (quantum levels) of an electron are directly related to the energy level of the Nuclei in each Quantum Level

Quantum Level 1

K shell

n1

Ground State electron


v
P
KE
hv
v²
1.2e20
0.28 eV

$iE = -13.313\ eV$

The energy levels of bound electrons is determined by Baryons

Z#		Name	Protons	electrons	Neutrons
1	1s1	Deuterium	1	1	1
2	1s2	Helium	2	2	2

2

Deuterium [not Hydrogen] is the building block of elements


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
f
d
p
s
p
d
f




Energy level
1

Z#		Name	Protons	electrons	Neutrons
1	1s1	Hydrogen	1	1	0

Hydrogen is a free radical element

n1



Copyright ABRAHAM [2008] - All rights reserved

Quantum Level 2

The energy levels of bound electrons is determined by Baryons

Z #		Name	Protons	electrons	Neutrons
3	2s1	Lithium	3	3	3
4	2s2	Berylium	4	4	4
5	1p1	Boron	5	5	5
6	1p2	Carbon	6	6	6
7	1p3	Nitrogen	7	7	7
8	1p4	Oxygen	8	8	8
9	1p5	Fluorine	9	9	9
10	1p6	Neon	10	10	10

8

Deuterium [not Hydrogen] is the building block of elements

L shell

n2

Ground State electron


v
KE
hv
v²
1.2e20
0.8453 eV

$iE = -12.679\ eV$


5 F
2
1
4 O
1
1 Li
1
1 B
2 C
1
2 Be
1
3 N
2
1
6 Ne

Energy level


3 2 1 0 1 2 3
R 8
Q 7
P 6
O 5
N 4
M 3
L 8 2
K 1
f d p s p d f



Copyright ABRAHAM [2008] - All rights reserved

Quantum Level 3

The energy levels of bound electrons is determined by Baryons

Z #		Name	Protons	electrons	Neutrons
11	3s1	Sodium	11	11	11
12	3s2	Magnesium	12	12	12
13	2p1	Aluminium	13	13	13
14	2p2	Silicon	14	14	14
15	2p3	Phosphorus	15	15	15
16	2p4	Sulfur	16	16	16
17	2p5	Chlorine	17	17	17
18	2p6	Argon	18	18	18
21	3d1	Scandium	21	21	21
22	3d2	Titanium	22	22	22
23	3d3	Vanadium	23	23	23
24	3d4	Chromium	24	24	24
25	3d5	Manganese	25	25	25
26	3d6	Iron	26	26	26
27	3d7	Cobalt	27	27	27
28	3d8	Nickel	28	28	28
29	3d9	Copper	29	29	29
30	3d10	Zinc	30	30	30

18

Deuterium [not Hydrogen] is the building block of elements


9
Cu
1
Sc
3
V
7
Co
5
Mn
5
Cl
4
S
1
Na
1
Al
2
Si
2
Mg
3
P
6
Ar
6
Fe
8
Ni
4
Cr
2
Ti
10
Zn


3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
18
f d p s p d f

M shell

n3

Ground State electron


v
KE
hv
v²
1.2e20
1.9019 eV

$iE = -11.623\ eV$

Energy level
3



Quantum Level 4

The energy levels of bound electrons is determined by Baryons

32

Z #		Name	Protons	electrons	Neutrons
19	4s1	Potassium	19	19	19
20	4s2	Calcium	20	20	20
31	4p1	Gallium	31	31	31
32	4p2	Germanium	32	32	32
33	4p3	Arsenic	33	33	33
34	4p4	Selenium	34	34	34
35	4p5	Bromine	35	35	35
36	4p6	Krypton	36	36	36
39	4d1	Yttrium	39	39	39
40	4d2	Zirconium	40	40	40
41	4d3	Niobium	41	41	41
42	4d4	Molybdenum	42	42	42
43	4d5	Technetium	43	43	43
44	4d6	Ruthenium	44	44	44
45	4d7	Rhodium	45	45	45
46	4d8	Palladium	46	46	46
47	4d9	Silver	47	47	47
48	4d10	Cadmium	48	48	48
57	4f1	Lanthanum	57	57	57
58	4f2	Cerium	58	58	58
59	4f3	Praseodymium	59	59	59
60	4f4	Neodymium	60	60	60
61	4f5	Promethium	61	61	61
62	4f6	Samarium	62	62	62
63	4f7	Europium	63	63	63
64	4f8	Gadolinium	64	64	64
65	4f9	Terbium	65	65	65
66	4f10	Dysprosium	66	66	66
67	4f11	Holium	67	67	67
68	4f12	Erbium	68	68	68
69	4f13	Thulium	69	69	69
70	4f14	Ytterbium	70	70	70

Deuterium [not Hydrogen] is the building block of elements


3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
32
f d p s p d f


13 Tm
1 La
3 Pr
9 Ag
1 Y
3 Nb
9 Bk
7 Rh
5 Tc
11 Ho
7 Eu
5 Br
4 Se
5 Pm
1 K
1 Ga
2 Ge
2 Ca
6 Sm
3 As
6 Kr
8 Gd
6 Ru
8 Pd
12 Er
4 Mo
2 Zr
10 Dy
10 Cd
4 Nd
2 Ce
14 Yb

N shell

n4

Ground State electron


v
KE
hv
v²
1.2e20
3.3812 eV

iE = -10.143 eV

Energy level



Quantum Level 5

The energy levels of bound electrons is determined by Baryons

Z #		Name	Protons	electrons	Neutrons
37	5s1	Rubidium	37	37	37
38	5s2	Strontium	38	38	38
49	5p1	Indium	49	49	49
50	5p2	Tin	50	50	50
51	5p3	Antimony	51	51	51
52	5p4	Tellurium	52	52	52
53	5p5	Iodine	53	53	53
54	5p6	Xenon	54	54	54
71	5d1	Lutetium	71	71	71
72	5d2	Hafnium	72	72	72
73	5d3	Tantalum	73	73	73
74	5d4	Tungsten	74	74	74
75	5d5	Rhenium	75	75	75
76	5d6	Osmium	76	76	76
77	5d7	Iridium	77	77	77
78	5d8	Platinum	78	78	78
79	5d9	Gold	79	79	79
80	5d10	Mercury	80	80	80
89	5f1	Actinium	89	89	89
90	5f2	Thorium	90	90	90
91	5f3	Protactium	91	91	91
92	5f4	Uranium	92	92	92
93	5f5	Neptunium	93	93	93
94	5f6	Plutonium	94	94	94
95	5f7	Americium	95	95	95
96	5f8	Curium	96	96	96
97	5f9	Berkelium	97	97	97
98	5f10	Californium	98	98	98
99	5f11	Einsteinium	99	99	99
100	5f12	Fermium	100	100	100
101	5f13	Mendelevium	101	101	101
102	5f14	Nobelium	102	102	102

32

Deuterium [not Hydrogen] is the building block of elements


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
32
f
d
p
s
p
d
f


Md 13
Ac 1
Pa 3
Au 9
Bk 9
Lu 1
Ta 3
Es 11
Ir 7
Re 5
Am 7
I 5
Te 4
Np 5
Rb 1
In 1
Sn 2
Sr 2
Pu 6
Sb 3
Xe 6
Cm 8
Os 6
Pt 8
Fm 12
W 4
Hf 2
Cf 10
Hg 10
U 4
Th 2
No 14

O shell

n5

Ground State electron

v
KE
hv
v²
1.2e20
5.5282 eV

$iE = -8.241\ eV$

Energy level
5

n5
n4
n3
n2
n1

Copyright ABRAHAM [2008] - All rights reserved

Quantum Level 6

The energy levels of bound electrons is determined by Baryons

Z #		Name	Protons	electrons	Neutrons
55	6s1	Caesium	55	55	55
56	6s2	Barium	56	56	56
81	6p1	Thallium	81	81	81
82	6p2	Lead	82	82	82
83	6p3	Bismuth	83	83	83
84	6p4	Polonium	84	84	84
85	6p5	Astatine	85	85	85
86	6p6	Radon	86	86	86
103	6d1	Lawrencium	103	103	103
104	6d2	Rutherfordium	104	104	104
105	6d3	Dubnium	105	105	105
106	6d4	Seaborgium	106	106	106
107	6d5	Bohrium	107	107	107
108	6d6	Hassium	108	108	108
109	6d7	Meitnerium	109	109	109
110	6d8	Darmstadtium	110	110	110
111	6d9	Roetgenium	111	111	111
112	6d10	Copernicium	112	112	112

18

Deuterium [not Hydrogen] is the building block of elements


3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
18
f d p s p d f

Energy level
6


Rg 9
Lr 1
Db 3
Mt 7
Bh 5
At 5
Po 4
Cs 1
Tl 1
Pb 2
Ba 2
Bi 3
Rn 6
Hs 6
Ds 8
Sg 4
Rf 2
Cn 10
4
5
6

P shell

n6

Ground State electron


v
P
KE
hv
v²
1.2e20
7.607 eV

$iE = -5.917\ eV$


n6
n5
n4
n3
n2
n1

Copyright ABRAHAM [2008] - All rights reserved

Quantum Level 7

The energy levels of bound electrons is determined by Baryons

Z #		Name	Protons	electrons	Neutrons
87	7s1	Francium	87	87	87
88	7s2	Radium	88	88	88
113	7p1	Ununtrium	113	113	113
114	7p2	Flerovium	114	114	114
115	7p3	Ununpentium	115	115	115
116	7p4	Livermorium	116	116	116
117	7p5	Ununseptium	117	117	117
118	7p6	Ununoctium	118	118	118

8

Deuterium [not Hydrogen] is the building block of elements


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f


Uus
5
Lv
4
Fr
1
Uut
1
Fl
2
Ra
2
Uup
3
Uuo
6
7
7
6
6
6
6
6
6

Energy level

Q shell

n7

Ground State electron


v
p
KE
c
hv
v²
1.2e20
10.355 eV

$iE = -3.169\ eV$


n7
n6
n5
n4
n3
n2
n1

Quantum Level 8

The energy levels of bound electrons is determined by Baryons

Z #		Name	Protons	electrons	Neutrons
119	8s1	Ununnonium	119	119	119
120	8s2	Unbinilium	120	120	120

2

Deuterium [not Hydrogen] is the building block of elements

R shell

n8

Ground State electron


v
P
KE
hv
v²
1.2e20
13.525 eV


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
2
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f




n8
n7
n6
n5
n4
n3
n2
n1
−
+

Energy level
8

Quantum Level Jumps

Photon Absorption and Release


Emission
s p d
f
3
2 1 0


Absorption
s p d
f
3
2 1 0

Photo-electrons can only transition between principal energy Baryons in the atomic nuclei in discrete steps [or quantum jumps] because Baryons determine the KEM energy levels of electrons in nuclei

[see Tetryonic QED for full details on spectral line mechanics]

Initial Quantum level

8	768	756	720	660	576	468	336	180	0
7	588	576	540	480	396	288	156	0	
6	432	420	384	324	240	132	0		
5	300	288	252	192	108	0			
4	192	180	144	84	0				
3	108	96	60	0					
2	48	36	0						
1	12	0							
		12	48	108	192	300	432	588	768
		1	2	3	4	5	6	7	8

Final Quantum level

$$\Delta p = \Delta M v = hf$$

accelerating photo-electrons produce spectral lines

Spectral line transitions


8
un-named
7
Humphries
6
Pfund
5
Brackett
4
Paschen
3
Balmer
2
Lyman
1

Quantum level jumps


Spectral
line transitions
v
Δv
Σv
KEM
48
108
192
300
432
588
768
36
60
84
108
132
156
180
36
96
180
288
420
576
756
2
3
4
5
6
hv
c
Quantum
differentials
hv, R, β, p, KE
Planck, Rydberg, Lorentz, Newton, Leibniz
uniting classical physics and relativity
through equilateral geometry

Nuclear energy emission~absorption

If atoms are left undisturbed, their electrons usually fill the lowest available energy levels and stay there, in their "ground state."

Occasionally, however, they may also be pushed up to some higher energy ("become excited") e.g. by a collision with a fast atom or electron, one which got extra speed from an electric voltage or from some source of heat.

An atom/electron elevated to one of its higher "excited levels" soon falls back to a lower level ("undergoes a quantum jump"), emitting a photon whose energy corresponds to the difference between the levels.

That need not be the ground state: the atom/electron might descend to that state in several steps, emitting a photon at each step on the way.


Velocity
v
p
Spectral
Lines
KE
KEM
Energies
hv
v^2
M
12
[0-12]
1.2e20

Quantum transitions

(Orbital Shells - Bound energy states)



Quantum levels 1-8 are also referred to as Atomic Shells K-R

Photo-electrons can only transition in discrete steps [or quantum jumps] within atomic nuclei shells because Baryons determine the KEM energy levels of electrons in nuclei

Any photo-electron bound in a Deuterium nuclei will have specific quantised KEM field energies and angular momenta

$hf = \Delta Mv = \Delta p$

spectral lines are produced by accelerating electrons

Energy levels
5 6 7 8 4 3 2 1
Atomic Shells
O P Q R N M L K
Quantum differentials
Lyman
Balmer
Paschen
Brackett
Pfund
Humphries
un-named
1 2 3 4 5 6 7 8
n
12 48 108 192 300 432 588 768 768+
KEM energies
n1
v
P
KE
hv
v²
1.2e20
0.211 eV
iE= -13.358 eV
1
Quantum level
1 K
n2
1.2e20
0.276 eV
iE = -12.679 eV
2
Quantum level
2 L
n3
1.2e20
0.375 eV
iE = -11.623 eV
3
Quantum level
3 M
n4
1.2e20
0.541eV
iE = -10.143 eV
4
Quantum level
4 N
n5
1.2e20
0.845 eV
iE = -8.2417 eV
5
Quantum level
5 O
n6
1.2e20
1.502 eV
iE = -5.917 eV
6
Quantum level
6 P
n7
1.2e20
3.381 eV
iE = -3.1699 eV
7
Quantum level
7 Q
n8
1.2e20
13.525 eV
iE = -any eV
8
Quantum level
8 R


AZMITHAL
MAGNETIC
electron orbitals
f
d
p
s
magnetic
7
m
5
3
1
Z
2
6
10
s
14
spins
0
1
2
ℓ
3
azmithal
ORBITALS
SUB-ORBITALS

Atomic Orbitals


Energy level
n
Quantum numbers
0
1
1
2
2
3
3
ℓ
8
7
6
5
4
3
2
1
R
Q
P
O
N
M
L
K
s
s+p
s+p+d
s+p+d+f
s+p+d+f
s+p+d
s+p
s
f
f
d
d
p
p
s
electron orbitals
Atomic Shell


S
2
6
10
14
7
5
3
1
m

An atomic orbital is a mathematical function that describes the wave-like behavior of either one electron or a pair of electrons in an atom

Atomic orbitals are typically categorized by n, l, and m quantum numbers, which correspond to the electron's energy, angular momentum, and an angular momentum vector component, respectively.

Historically used to define the pedagogical electron cloud model of an atom Tetryonics reveals the true geometry of atomic nuclei

Each orbital is defined by a different set of quantum numbers and contains a maximum of two spin opposed electrons.

Aufbau

Azmithal & Magnetic numbers


Energy levels
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
2
2
3
3
+1
0
-1
-1
0
+1
+2
+1
0
-1
-2
-2
-1
0
+1
+2
+3
+2
+1
0
-1
-2
-3
-3
-2
-1
0
+1
+2
+3
2
8
18
32
32
18
8
2
7
5
3
1
1
3
5
7
13
11
9
7
5
3
1
2
4
6
8
10
12
14
9
7
5
3
1
2
4
6
8
10
5
3
1
2
4
6
1
2
f
f
d
d
p
p
s
Atomic Shells

Orbitals & sub-Orbitals

Electron Spins can be either up or down providing they obey the Pauli exclusion principle

Copyright ABRAHAM [2008] - All rights reserved

s Orbital

1 Orbit (2 electrons max)

Alkali Metals & Alkali Earths


Quantum numbers
0
Energy level
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
f
d
p
Atomic shell
s
electron orbitals


Cs
Rb
Fr
D
1
K
Uun
Li
Na
Ba
Sr
Ra
He
2
Ca
Ub
Be
Mg
s
1

		n
azmithal number	0	l
magnetic numbers	0	m
spins	-1/2 +1/2	s



erroneous computer model of 's' electron orbitals


Energy levels
6
5
7
1
8
4
2
3

Copyright ABRAHAM [2008] - All rights reserved

p Orbital

3 Orbits (6 electrons max)


Quantum numbers
Energy level
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
-1
0
+1
f
d
p
p
p
s
Atomic shell
electron orbitals

n

ℓ

m

S

azmithal number		1	
magnetic numbers	-1	0	+1
spins	-1/2	-1/2	-1/2
	+1/2	+1/2	+1/2

Non-Metals, Halogens & Nobel gases


p
At
I
Uus
5
Br
F
Cl
Po
Te
Lv
4
Se
O
S
Tl
In
Uut
1
Ga
B
Al
Pb
Sn
Fl
2
Ge
C
Si
Bi
Sb
Uup
3
As
N
P
Rn
Xe
Uuo
6
Kr
Ne
Ar
1
2
3


z
y
x
p_{-1}
z
y
x
p_0
z
y
x
p_1

erroneous computer model of 'p' electron orbitals

Quantum levels
6
5
7
4
2
3

d Orbital

5 Orbits (10 electrons max)


Quantum numbers
Energy level
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
-2
-1
0
+1
+2
3
f
d
d
d
d
d
p
p
s
Atomic shell
electron orbitals

Transition & post-Transition Metals


Rg
Au
9
Ag
Cu
Lr
Lu
1
Y
Sc
Db
Ta
3
Nb
V
Mt
Ir
7
Rh
Co
Bh
Re
5
Tc
Mn
d
1 2 3 4 5
erroneous computer model of 'd' electron orbitals
Hs
Os
6
Ru
Fe
Sg
W
4
Mo
Cr
Cn
Hg
10
Cd
Zn
Rf
Hf
2
Zr
Ti
Ds
Pt
8
Pd
Ni

						n
azimthal number			2			l
magnetic numbers	-2	-1	0	+1	+2	m
spins	-1/2 +1/2	-1/2 +1/2	-1/2 +1/2	-1/2 +1/2	-1/2 +1/2	s


Quantum levels
6
5
4
3

f Orbital

7 Orbits (14 electrons max)


Quantum numbers
Energy level
R 8
Q 7
P 6
O 5
N 4
M 3
L 2
K 1
-3 -2 -1 0 +1 +2 +3
f f f f f f f
d d
p p
s
Atomic shell
electron orbitals

n

azmithal number				3				l
magnetic numbers	-3	-2	-1	0	+1	+2	+3	m
spins	-1/2 +1/2	-1/2 +1/2	-1/2 +1/2	-1/2 +1/2	-1/2 +1/2	-1/2 +1/2	-1/2 +1/2	S

Lanthanoids & Actinoids


Md 13 Tm
Ac 1 La
Pa 3 Pr
Bk 9 Tb
Es 11 Ho
Am 7 Eu
Np 5 Pm
f
1 2 3 4 5 6 7
erroneous computer model of 'f' electron orbitals
Pu 6 Sm
Cm 8 Gd
Fm 12 Er
Cf 10 Dy
U 4 Nd
Th 2 Ce
No 14 Yb
N μ S
Quantum levels
5
4

Copyright ABRAHAM [2008] - All rights reserved

Orbital energy variations

All Elements have stable core electron configurations of s & p orbitals for each energy level as revealed through diffraction studies




f
n
d
p
s
orbital energies
azimuthal
magnetic
electrons per orbital
2
6
10
l
m
s
14

As additional nuclei bind to form d & f orbitals they can do so by bonding in many positions, with each location producing different orbital energies for each electron that binds to nuclei in that position



The final energy levels of each orbital is the result of the energy of the Baryons in the nuclei and the spin coupling energies of the photo-electrons bound to them

Copyright ABRAHAM [2008] - All rights reserved

Electrons per shell



Each energy shell of a periodic element can hold only a fixed number of electrons



Atomic Orbitals

f	d	p	s	p	d	f
5, 11, 3, 13, 1, 9, 7	8, 2, 10, 4, 6	5, 1, 3	1-2	6, 2, 4	7, 1, 9, 3, 5	6, 12, 4, 14, 2, 10, 8

7 + 5 + 3 + 2 + 3 + 5 + 7

Rules governing the allowed combinations of Quantum Numbers

The three quantum numbers (n, l, and m)
that describe an orbital are integers: 0, 1, 2, 3, and so on

n (1-8) Principal (n = 1, 2, 3, 4 ...)	The principal quantum number (n) cannot be zero.
ℓ (0-3) Azimuthal (l = 0, 1 ... n-1)	The angular quantum number (l) can be any integer between 0 and n - 1.
$m\ell(2\ell+1)$ Magnetic [illegible]	The magnetic quantum number (m) can be any integer between -l and +l.
m_s $\pm\frac{1}{2}$ Spin Projection (ms = -1/2 or +1/2)	The Spin of electrons in any nuclear sub-orbital can only be +1/2 (Spin UP) or -1.2 (Spin DOWN).

Z

1, 2, 3, 4, 5, 6, 7, 8

s, p, d, f

1	2
1, 3, 5	2, 4, 6
1, 3, 5, 7, 9	2, 4, 6, 8, 10
1, 3, 5, 7, 9, 11, 13	2, 4, 6, 8, 10, 12, 14
down up	up down

Quantum Numbers

n	4-5	3-6	2-7	1-8	2-7	3-6	4-5
ℓ	3	2	1	0	1	2	3
m	-3	-2	-1	1	+1	+2	+3
s	+1/2 -1/2	+1/2 -1/2	+1/2 -1/2	+1/2 -1/2	+1/2 -1/2	+1/2 -1/2	+1/2 -1/2

Erwin Schrödinger

(12 August 1887 – 4 January 1961)

Using Tetryonic charged geometries for mass-ENERGY-Matter,
an electron's position and velocity CAN be modelled simultaneously
(but any attempt to measure or interact with it, will affect its component energy-momenta)

Electron Position Uncertainty

Atomic orbitals are typically described as "hydrogen-like" (meaning one-electron) wave functions over any spatial region of measurement, categorized by n, l, and m quantum numbers, which correspond to the electron's energy, angular momentum, and a vector momentum component, respectively

Werner Heisenberg

(5 December 1901 – 1 February 1976)

Lepton's are physically Spin 1 fermion particles that can easily be misconstrued as having entirely different spin numbers without the correct physical topologies to base the observed measurements on



The energies of photo-electrons are determined by the Baryons they bind to & incident photons

Quantum Mechanics is a mathematical representation of equilateral energy momenta interactions and the charged geometries of mass-ENERGY-Matter

Determining the motion of electrons bound to atomic nuclei is akin to measuring the motion of variable speed electric fan blades mounted at various heights within a rotating carousel

Leptons are 12 loop quantum rotors



an identical fascia is presented with every 120 degree rotation

their spin number is a measure ment of their magnetic moment

The unique 12 faceted topology of leptons results in an identical EM geometry being oberved for every 120° rotation of the particle

Leading to the interpretation that the Lepton disappears and re-appears when being 'observed' or measured



Every charged radial arm of a Lepton's Matter topology is identical to every other

Making accurate measurement and mathematical modelling of its rotational dynamics & mechanics incorrect without the correct physical topologies

Electron modelling & probability calculations

12
[0-12]
RE
S
KE

Electron positional measurements have proven to be historically difficult to accurately model due to the charged 12π rotating topologies of leptons



Computer generated plots of 'clouds' of electron probabilites are inaccurate mis-representations and should be abandoned in favour of realistic atomic models reflective of the charged geometry of each periodic element

v
RE
KE
P
KE
hv
Q
M
M
v²
c²

Every elemental atom can be viewed as a quantum carousel with a unique number of oscillating fans positioned around it.

Each fan has 3 blades and a fixed speed n[1-8] related to its height above ground level, AND the carousel is turning around on its axis

All periodic elements are made form Deuterium nuclei



The baryonic energies of nuclei determines the energies of bound photo-electrons



The current computer generated electron probability diagrams in popular use at present can now be show to be a misrepresentative model of mathematical modelling of electron sub-orbital energies

The nuclear quantum levels [n], intrinsic quantised angular momentum [h] and orbital angular momentum [l] of each electron bound within atomic nuclei are all the direct result of the Baryonic energies of the nuclei they are bound to

Each level of the quantum carousel can contain only a limited number of fans each running at a specific speed

Imagine trying to measure (or model) the motion of any 1 quantum scale blade while the carousel rotates


AUFBAU
FILLING
quantum numbers
3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
Atomic Shells
8
7
6
5
4
3
2
1
Energy levels
2
8
18
32
32
18
8
2
Z
f d p s p d f
electron orbitals
BUILDING THE ELEMENTS

Tetryonics 48.01 - aufbau geometry

Quantum Topologies




Electron
Neutron
Nucleus
Proton
N
N
N
N


0
1
1
2
2
3
3
2
8
18
32
32
18
8
2
Z
f
f
d
d
p
p
s

Dalton Model

Quantum Model

Thomson Model

Rutherford Model




proton
neutron

Historically viewed as a spherical object
Tetryonic charge geometry has finally revealed the
true quantum topology of all atoms

Copyright ABRAHAM [2008] - All rights reserved

Element numbers

The rule dictating how many nuclei form each Atomic shell is known as the Aufbau principle.

The physical and chemical properties of elements is determined by the atomic structure.
The atomic structure is, in turn, determined by the electrons and
which shells, subshells and orbitals they reside in.

The maximum periodic elemental number is 120

$$Z = \sum_{1,2,3,4}^{4,3,2,1} 2(n^2) = 2 + 8 + 18 + 32 + 32 + 18 + 8 + 2$$

Number of nuclei per level	Element #
2	120 119
8	118 111
18	110 93
32	92 61
32	60 29
18	28 11
8	10 3
2	2 1

The number of nuclei per quantum level is reflective of photonic energy levels and provides the foundational geometry for all of the periodic elements

The number of possible nuclei in each Quantum level follows aufbau principle 'numbers' which can be determined using the following summation formula


Element Number
Level
Nuclei
R
8
s
2
2
Q
7
s + p
2+6
8
P
6
s + p + d
2+6+10
18
O
5
s + p + d + f
2+6+10+14
32
N
4
s + p + d + f
2+6+10+14
32
M
3
s + p + d
2+6+10
18
L
2
s + p
2+6
8
K
1
s
2
2
Z
Shell
orbitals
sub-orbitals

Deuterium is the building block of all elements

Each element has equal numbers of Protons, electron & Neutrons with their stored mass-energies making up the molar masses of elements not excess neutron as currently modelled

Copyright ABRAHAM [2008] - All rights reserved

Aufbau Principle

(Nuclei number and position)

1 Sub-Orbit (2 electrons max) ○ s

3 Sub-Orbits (6 electrons max) ○ p

○ d *5 Sub-Orbits (10 electrons max)*

○ f *7 Sub-Orbits (14 electrons max)*


Azmithal quantum number
3 2 1 0 1 2 3
atomic shells
R 2
Q 2+6
P 2+6+10
O 2+6+10+14
N 2+6+10+14
M 2+6+10
L 2+6
K 2
8s
s+p 7s 7p
s+p+d 6s 6p 6d
s+p+d+f 5s 5p 5d 5f
s+p+d+f 4s 4p 4d 4f
s+p+d 3s 3p 3d
s+p 2s 2p
1s
2 8
8 7
18 6
32 5
32 4
18 3
8 2
2 1
energy level
f d p s p d f
7 + 5 + 3 + 2 + 3 + 5 + 7

2 6 10 14

Nuclei	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	Quantum number	per level
R	119	120																															8	2
Q	87	88	113	114	115	116	117	118																									7	8
P	55	56	81	82	83	84	85	86	103	104	105	106	107	108	109	110	111	112															6	18
O	37	38	49	50	51	52	53	54	71	72	73	74	75	76	77	78	79	80	89	90	91	92	93	94	95	96	97	98	99	100	101	102	5	32
N	19	20	31	32	33	34	35	36	39	40	41	42	43	44	45	46	47	48	57	58	59	60	61	62	63	64	65	66	67	68	69	70	4	32
M	11	12	13	14	15	16	17	18	21	22	23	24	25	26	27	28	29	30															3	18
L	3	4	5	6	7	8	9	10																									2	8
K	1	2																															1	2
Shells																																		
sub-orbitals	s1	s2	p1	p2	p3	p4	p5	p6	d1	d2	d3	d4	d5	d6	d7	d8	d9	d10	f1	f2	f3	f4	f5	f6	f7	f8	f9	f10	f11	f12	f13	f14		

A specific nuclear energy is associated with each electron configuration and, upon certain conditions, bound electrons are able to move from one orbital to another by emission or absorption of a quantum of energy, in the form of a photon.

The Aufbau principle can also be used to model the binding configuration of Protons and Neutrons in an atomic nucleus, according to their specific Baryonic Energy levels, in turn revealing the quantum geometry of all periodic Elements

Wolfgang Pauli

(25 April 1900 – 15 December 1958)


Azmithal quantum number
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8s
7s
7p
6s
6p
6d
5s
5p
5d
5f
4s
4p
4d
4f
3s
3p
3d
2s
2p
1s
8
7
6
5
4
3
2
1
energy level
f
d
p
s
p
d
f

Friedrich Hermann Hund

(4 February 1896 - 31 March 1997)

The orbitals of lower energy are filled in first with the electrons and only then are the higher energy orbitals filled.

aufbau electron orbital filling

Orbitals of equal energy are each occupied by one electron before any orbital is occupied by a second electron, and all electrons in singly occupied orbitals must have the same spin state


Azmithal & Magnetic numbers
Energy levels
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
2
3
f
d
p
s
p
d
f
Atomic Shells
Orbitals & sub-Orbitals

Aufbau construction


60
7
5
4
14
f
5
6
5
4
3
20
d
3
7
6
5
4
3
2
18
p
1
8
7
6
5
4
3
2
1
8
s

Proton base Hemisphere


3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
8
18
32
32
18
8
2
α
f d p s p d f


Azmithal & Magnetic numbers
Energy levels
0
1
1
2
2
3
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
8
18
32
32
18
8
2
Z
13 11 9 7 5 3 1
f
9 7 5 3 1
d
5 4 1
p
1 s 2
2 3 6
p
2 4 6 8 10
d
2 4 6 8 10 12 14
f
α Hemisphere Orbitals
β Hemisphere Orbitals
Atomic Shells
Orbitals & sub-Orbitals


3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
8
18
32
32
18
8
2
β
f d p s p d f

Neutron base Hemisphere


1
8
7
6
5
4
3
2
1
8
s
3
7
6
5
4
3
2
18
p
5
6
5
4
3
20
d
7
5
4
14
f
60



Atomic Weights

[Molar mass-energies]

The table does not illustrate the quark compositions of the baryonic nuclei in elements

The Mendeleev table incorrectly positions Hydrogen as Element 1 in the table and does not show Deuterium [the building block of all Elements]

The Mendeleev block arrangement of periodic elements presents a number of problems in representing the true topologies and properties of all the periodic elements:

It provides no insight into the individual topologies of the periodic elements themselves

The physical dimensions of periodic elements and the electron orbitals of each element are not represented by the table

The table does not reflect elemental quantum numbers as defined by Schrodinger's wave equation

The table provides no additional insights or information on nuclei packing, aufbau element building processes or how nuclei energies contribute to total molar mass

Tetryonic charge geometry can rectify all of these deficiencies

Tetryonics 49.01 - Atomic Weight

Copyright ABRAHAM [2008] - All rights reserved



Baryon mass-energies n	E *The quantum level mass-energies of Baryons determines the kinetic energies of electrons* 1n - 1 e19v		electron KEM field hv²
73,728	n32	v8	3.268969693 e15
69,192	n31	v7	2.502804921 e15
64,800	n30	v6	1.838795452 e15
60,552	n29	v5	1.276941286 e15
56,448	n28	v4	8.172424232 e14
52,488	n27	v3	4.596988631 e14
48,672	n26	v2	2.043106058 e14
45,000	n25	v1	5.107765145 e13
Compton frequencies 930 MeV	1.2e20 **electron rest Matter is velocity invariant** 496 keV		**spectral frequencies** 13.6 eV

Atomic nuclei mass-energies

Each element's weight [mass-Matter in a gravitational field] is the result of the total quanta comprising that element



The nuclei forming each atomic shell have specific mass-energy quanta

$$\overset{8}{\underset{1}{n}}\left[\overset{\text{Baryon rest masses}}{[72(n)^2]}+\overset{\text{lepton rest mass}}{[12e19]}+\overset{\text{KEM}}{[m_e v^2]}\right]$$

Deuterium mass-energy per shell

Despite having differing mass-energies each Deuterium nuclei has the same velocity invariant Matter geometry [84π]

spin orbital coupling in synchronous quantum convertors

Electrons act as quantum scale rotating armatures in atomic nuclei and can only have specific energies reflective of the electron orbital energy level of the Baryons in which they are found

They acheive these energy levels by absorbing or emitting photons to acheive the specific angular momentum required

Hydrogen Ionisation Energies $[/n^2]$


free electron
>13.525 eV
K.E
n8+
768
588
432
300
192
108
48
12
n0
12
R
Q
P
O
N
M
L
K
atomic shells
Quantum numbers
0
1
1
2
2
3
3
0.21 eV
0.27 eV
0.37 eV
0.54 eV
0.84 eV
1.50 eV
3.38 eV
13.5 eV
n
f
f
d
d
p
p
s
electron orbitals
emission
absorption
8
7
6
5
4
3
2
1
energy levels

13.6eV
Free electron

5.107765145 e13
6.671366720 e13
9.078047137 e13
1.307587877 e14
2.043106058 e14
3.632188548 e14
8.172424234 e14
3.268969693 e15

Planck quanta

Spectral line series frequencies
[Hydrogen]

accelerating electrons $Mv^2 = KEM = hv^2$ produce spectral lines

Redefining Atomic weights

Atomic weight (symbol: Ar) is a dimensionless physical quantity,
the ratio of the average mass of atoms of an element (from a given source) to
1/12 of the mass of an atom of carbon-12 (known as the unified atomic mass unit)

Carbon 12



6 Protons	[24-12]	n1
6 Neutrons	[18-18]	
6 electrons	[0-12]	

The 'unified atomic mass unit' currently in use
is known to be inaccurate and must be corrected
in order to bring clarity & increased accuracy
to the atomic weights of all elements

$$\boxed{A_r = 22{,}512 \quad \text{Hydrogen}}$$

Defining Hydrogen as having an exact
atomic Planck mass of 22512_n quanta
provides uniformity with Tetryonics

1/12 C_{12}

$A_r = 22{,}506$



1.660096209e-27 kg

1 Proton	[24-12]	n1
.5 electron	0-6	

Deuterium is the building block of all elements in the period table

Unified atomic Matter unit



1.660538783e-27 kg

1 Proton	[24-12]	n1
1 electron	[0-12]	

$$\boxed{A_r = 45{,}012 \quad \text{Deuterium}}$$

Defining Deuterium as having an exact
atomic Planck mass of 45012_n quanta
reflects the true charged geometries
of all Elements & their topologies

D

1/6 C



3.320192418e-27 kg

1 Proton	[24-12]	n1
1 Neutron	[18-18]	
1 electron	[0-12]	

Copyright ABRAHAM [2008] - All rights reserved

Planck mass-energy units

NAu = 0.001 kg



1.660538841 e-27 kg

One Da is approximately equal to the mass of one proton or one neutron



0.499866702 H

1.659653693 e-27 kg



0.499866702 H

Deuterium is the building block of all elements



3.320192534 e-27 kg

The unified atomic mass unit (symbol: u) or Dalton (symbol: Da)
is a unit that is used for indicating mass on an atomic or molecular scale

270,072

1/12 the mass of a C12 graphene atom at rest in its electronic ground state

1.660538782(83)x10–27 kg

22,506

is an inaccurate means of determining the exact rest mass of a Hydrogen atom

22,512

Carbon 12 has 270,072n planck quanta
(270,072 / 12 = 22,506)

Hydrogen has a mass of 22,512n (22,500+12) requiring all mass to be calculated directly using the Planck mass-energy quantum (.001kg / N_A / 22,512) & Tetryonic charge geometries

Using Tetryonic theory to define
n Planck mass = $7.376238634 \times 10^{-32}$ Kg
(see Tetryonics QM 15.04)

exact atomic rest masses for all particles, elements and compounds can be determined directly from atomic theory

N_A = 6.02214179 e23

The mole is the amount of substance of a system which contains as many elementary entities as there are atoms in 0.012 kilogram of carbon 12; its symbol is "mol".

NA(12u) = 0.012 kg



6 Protons [24-12]
6 Neutrons [18-18] n1
6 electrons [0-12]

Carbon has a number of differing atomic configurations (allotropes)

6 Protons [24-12]
6 Neutrons [18-18] n1-2
6 electrons [0-12]



Planck mass-energy contributions to the measured weights of periodic, elementary mass-Matter topologies



1.659653693 e-27 kg



8.851486361 e-31 kg



2.41110961 e-35 kg



Baryons have 2,25e23 Planck quanta comprising their rest Matter topologies

[930.974 MeV]

Δ 1875 x

[496.5 keV]

Leptons have 1.2 e20 Planck quanta comprising their rest Matter topologies

[496.5 keV]

Δ 36,711 x

[13.6 eV]

Photons are planar geometries [Matter-less]
(purely Kinetic mass-Energy and momenta)

The Lyman alpha spectral line mass-energy contribution to the mass of a Deuterium nucleus is negligible

Electron quantum level energies are determined by the energy of the Nuclei they bind to in elements



Photons contribute spectral mass-energies to the nuclei mass but are themselves Matterless [2D zero rest mass-energies]

Photons are 2π charge mass-energy geometries

Ionisation energies

Fractional quantum differentials


RE
M+KE
Lyman
Balmer
Paschen
Brackett
Pfund
Humphries
un-named
p² = KEM = Mv²
180
156
132
108
1
2
3
4
5
6
7
8
ε₀
n
12
48
108
192
300
432
588
768
972
KEM energies

$$hf = \Delta M v = \Delta p$$

spectral lines are produced by accelerating electrons

Note: this is an Illustrative schema for modelling KEM field energies
All KEM fields possess the same physical spatial geometry
in radial-time defined spatial co-ordinate systems

c^2 c^4




Higher energies
S up
e⁻
S down
Lower Energies

Photo-electrons absorb/emit spectral energies

$$E = eV = \frac{1}{4\pi\epsilon_0}\frac{ne^2}{a}$$

photo-electronic energy momenta


v
RE
KE
p
Spectral Lines
KEM Energies
KE
M
hv
v²
12
[0-12]
1.2e20
Q
M
1
4
9
16
25
36
49
64
12
48
108
192
300
432
588
768

Mapping photo-electron transition energies
to Tetryonic energy momenta geometries
reveals many key facts about the
ionisation energies of nuclei

$$E = -\frac{Z^2}{n^2}\frac{ke^2}{2a_0} = -\frac{13.6Z^2}{n^2}eV$$

The differing fractional KEM field energy momenta of electrons
that results from their transitions to specific energy nuclei
in elements results in differing QAM quanta and
produces spectral lines and fine line splitting

Spectral line transitions


Δv
Σv
KEM
Quantum differentials
36
60
84
108
132
156
180
36
96
180
288
420
576
756
48
108
192
300
432
588
768
hv
v
c
v²
Mv²

hv, R, β, p, KE
Planck, Rydberg, Lorentz, Newton, Leibniz

uniting classical physics and relativity
through equilateral geometry

Elementary ionisation energies



The term ionization energy (EI) of an atom or molecule is the minimal KEM field energy required to remove (or unbind) one mole of electrons from one mole of gaseous atoms isolated in in any spatial region and in its ground energy state.

The term "ionization energy" is sometimes used as a name for the work needed to remove (or un-bind) the highest energy photoelectron from an atom or molecule.

However, due to interactions with surfaces, this value differs from the ionization energy of the atom or molecule in question when it is located by itself in free space.

So, in the case of surface-adsorbed atoms and molecules, it may be better to use the more general term "electron binding energy", in order to avoid confusion.

Both these names are also sometimes used to describe the work needed to remove an electron from a "lower" orbital (i.e., not the topmost orbital) for both free and adsorbed atoms; in such cases it is necessary to specify the orbital from which the electron has been removed

$$E = -\frac{Z^2}{n^2}\frac{ke^2}{2a_0} = -\frac{13.6Z^2}{n^2}eV$$

Every electron in each elementary orbit has a unique ionisation energy




Element number
s
p
d
f
Orbitals
sub-orbitals

Nuclei	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32		per shell
R	119	120																															8	2
Q	87	88	113	114	115	116	117	118																									7	8
P	55	56	81	82	83	84	85	86	103	104	105	106	107	108	109	110	111	112															6	18
O	37	38	49	50	51	52	53	54	71	72	73	74	75	76	77	78	79	80	89	90	91	92	93	94	95	96	97	98	99	100	101	102	5	32
N	19	20	31	32	33	34	35	36	39	40	41	42	43	44	45	46	47	48	57	58	59	60	61	62	63	64	65	66	67	68	69	70	4	32
M	11	12	13	14	15	16	17	18	21	22	23	24	25	26	27	28	29	30															3	18
L	3	4	5	6	7	8	9	10																									2	8
K	1	2																															1	2
Shells	s1	s2	p1	p2	p3	p4	p5	p6	d1	d2	d3	d4	d5	d6	d7	d8	d9	d10	f1	f2	f3	f4	f5	f6	f7	f8	f9	f10	f11	f12	f13	f14	Energy level	

Hyperfine splitting and Lamb Shifts

When the spectral lines of the hydrogen spectrum are examined at very high resolution, they are found to be closely-spaced doublets.
This splitting is called fine structure and was one of the first experimental evidences for electron spin.

The fine structure describes the splitting of the spectral lines of atoms due to first order relativistic corrections [principal quantum energies]

n

Differing electron spins within shells & quantum levels produces Hyperfine splitting


R
Q
P
O
N
M
L
K
8s
1s
8
7
6
5
4
3
2
1

atomic shell energies result from Series addition of baryonic energies


f13
f1
f3
f9
f11
f7
f5
d9
d1
d3
d7
d5
p4
p5
s1
p1
s p d
f
n
lms
14
10 6 2
p2
p6
s2
p3
d6
d8
f6
f8
f12
f10
d4
d2
d10
f4
f2
f14

The electron energy levels of Hydrogen should depend only on the principal quantum number n.

In 1951 it was discovered that this was not so, the $2p_{1/2}$ state is slightly less than the $2s_{1/2}$ state resulting in the Lamb shift

ℓ m s

Differing electron sub-Orbtial energies create Lamb Shifts


3
2
1
0
1
2
3
2p
2s
2p
f
d
p
s
p
d
f

electron sub-orbital energies are Parallel energy configurations

If you measure the atomic energy levels of photo-electrons at an extremely high resolution, you'll find small deviations of individual KEM field energies of electrons in sub-orbitals which are primarily the result of parallel and anti-parallel electron spins


Spin UP
KE
μB
μN
N Nuclear Magneton S
μB
KE
Spin DOWN

Higher energy
Parallel
Magnetic moments

Lower energy
Anti-parallel
Magnetic moments

All electron spins are referenced to the Nuclear magneton

Tetryonics 49.09 - Hyperfine splitting and Lamb Shifts

M_0

3D Matter topologies are comprised of charged 2D mass-energies

Energy per second²


E
ρ
c^4
seconds²

Matter Planck quanta

$$\frac{T\pi}{c^4}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

mass-Matter

standing wave mass-energiescreate
the material substance of all chemical elements

RE

Relativistic mass-ENERGY-Matter

Relativity fails at the foundational level to explain and differentiate between mass-ENERGY and Matter in physical systems


Schrodinger's quantum numbers
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
electron shells
Q
[v-v]
RE
2
8
18
32
32
18
8
2
M_0
KE
8
7
6
5
4
3
2
1
energy levels
f
d
p
c^4
p
d
f
Bohr's atomic orbitals

Einstein's relativistic [Lorentz corrected] stress energy tensor aggregates all forms of energy into a single energy density gradient

atomic energies

$$\frac{Tmn}{c^4} + \frac{mv^2}{c^2}$$

electron spins

3D rest Matter + Lorentz corrected 2D Kinetic Energies = total Relativistic Energies

KE

2D equilateral mass-energies are euclidean geometries

Energy per second

E
ρ
c^2
seconds

mass Planck quanta

$$\frac{n\pi}{c^2}\left[\left[m\Omega v^2\right]\right]$$

mass velocity

mass-energies

radiant planar mass-energies create
EM fields, spectral lines & chemical interactions

Deuterium is the building block of all Elements (save Hydrogen)

The geometry of any Element is determined by its Charge

The Molar Weight of any Element is a measure of its standing wave mass-energies



The rest mass-Matter of any Element is determined by the total number of quanta making up the Protons, Neutrons and electrons that comprise them (in their respective energy levels)

Any mass-energies in excess of the molar [n1] weight is a measurement of a element's CHEMICAL energies

Important point to note:

The Kinetic Energy difference between any Element's total [n1] Deuteron mass-energies and its Molar mass has historically been incorrectly explained as resulting from an excess number of Neutrons in the atom it is not. Z# = (number of Protons = number of electrons = number of Neutrons)

Elementary mass-Matter

R–K		n per nuclei 1e19v = n		
Σ	2	2 nuclei [74,496 ea]	120 119	Unbinilium Ununennium
		+		
	8	8 nuclei [69,780 ea]	118 87	Ununoctium Francium
		+		
	18	18 nuclei [65,232 ea]	112 55	Copernicium Caesium
		+		
	32	32 nuclei [60,852 ea]	102 37	Nobelium Rubidium
		+		
	32	32 nuclei [56,640 ea]	70 19	Ytterbuim Potassium
		+		
	18	18 nuclei [52,596 ea]	30 11	Zinc Sodium
		+		
	8	8 nuclei [48,720 ea]	10 3	Neon Lithium
		+		
	2	2 nuclei [45,012 ea]	2 1	Helium Deuterium

The rest mass-Matter of any Element is the sum total of its constituent Z[n²] energy level Deuterium nuclei

Aufbau

$$Z\#\left[\begin{array}{ll} z\ \text{Protons} & [24\text{-}12] \\ z\ \text{Neutrons} & [18\text{-}18] \\ z\ \text{electrons} & [0\text{-}12] \end{array}\right] n1\text{-}8$$

(ie Calcium [20] = 2+8+10 n level Deuterium nuclei)

Copyright ABRAHAM [2008] - All rights reserved

Periodic Harmonic motions

$x = A \cos(\omega t + \varphi)$

Circular motion


96°
32
32
96°
Z
18
18
54°
54°
8
2 2
8
24°
24°
6° 6°

circular harmonic motion

Circular motions describe the motion of a body with a changing velocity vector [the result of an acceleration force].

Much of the math in of modern physics is predicated on the assumption that π [where it appears] is related to the properties of a circle


1
2
3
4
4
3
2
$P\sum 2(n^2)$

Simple harmonic motion can be visualized as the projection of uniform circular motion onto one axis


Principal Quantum Numbers
3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
electron shells
Q
RE
M₀
KE
2
8
18
32
32
18
8
2
Z
8
7
6
5
4
3
2
1
energy levels
f d p s p d f
Sub-orbitals

$F = -kx$

Linear motion


2
8
18
32
32
18
8
2
Z

simple harmonic motion

Nuclei per shell in elements follows a 'periodic summation rule' that is reflective of photonic energies

$$\sum_{K}^{R}$$

nuclei per shell

$${}_{P}\sum_{K}^{R} Z$$

Periodic Summation

Periodic summation is a notation developed for Tetryonic theory to model the geometric series addtion of Z[n²] energy level Deuterium nuclei that form the periodic elements

$$\sum_{1}^{120} Z$$

element number

STEP ONE

Periodic summation follows the atomic shell electron config

STEP TWO

Periodic elements build up following the aufbau sequence

$${}_{P}\sum_{K}^{R} 2(x^2) =$$

1 2 3 4 4 3 2 1



Each atomic shell can hold only a fixed number of deuterium nuclei

${}_{P}\sum R = 2$	2 nuclei [74,496 ea]	120	Unbinilium
	+		
${}_{P}\sum Q = 8$	8 nuclei [69,780 ea]	118	Ununoctium
	+		
${}_{P}\sum P = 18$	18 nuclei [65,232 ea]	110	Darmstadtium
	+		
${}_{P}\sum O = 32$	32 nuclei [60,852 ea]	92	Uranium
	+		
${}_{P}\sum N = 32$	32 nuclei [56,640 ea]	60	Neodymuim
	+		
${}_{P}\sum M = 18$	18 nuclei [52,596 ea]	28	Argon
	+		
${}_{P}\sum L = 8$	8 nuclei [48,720 ea]	10	Neon
	+		
${}_{P}\sum K = 2$	2 nuclei [45,012 ea]	2	Helium
		0	Hydrogen

THe LHS of the notation determine the number of nuclei in each atomic shell, from the periodic mass-energy levels for atoms, and the RHS follows the aufbau building principle to determine the rest mass-Matter of any specific element

Aufbau

Each periodic element is made of Z [n² energy] deuterium nuclei

$$Z\# \left[\begin{array}{ll} z \text{ Protons} & [24\text{-}12] \\ z \text{ Neutrons} & [18\text{-}18] \\ z \text{ electrons} & [0\text{-}12] \end{array} \right] n1\text{-}8$$

Planck mass-energies form the surface integral of rest Matter topologies for each periodic element

Element numbers

Nuclei per shell in elements follow
a 'periodic summation rule'
that is reflective of
photonic energies

1 2 3 4 4 3 2 1

$$ {}^{P}\sum_{K}^{R} 2(x^2) = 2 + 8 + 18 + 32 + 32 + 18 + 8 + 2 $$

Z

120	Unbinilium	n8
119	Ununennium	
118	Ununoctium	n7
87	Francium	
112	Copernicium	n6
55	Caesium	
102	Nobelium	n5
37	Rubidium	
70	Ytterbuim	n4
19	Potassium	
30	Zinc	n3
11	Sodium	
10	Neon	n2
3	Lithium	
2	Helium	n1
1	Deuterium	
Hydrogen	0	


Principal Quantum Numbers
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
[γ-γ]
RE
M0
KE
2
8
18
32
Z
32
18
8
2
8
7
6
5
4
3
2
1
electron shells
energy levels
f
d
p
s
p
d
f
Sub-orbitals

Periodic mass-ENERGY-Matter

Following periodic summation rules for shell filling
n[1-8] quantum energy deuterium nuclei
combine to form elementary Matter

$$ \boxed{ {}^{P}\sum_{K\;25}^{R\;32} \left[\overset{\text{Baryon rest masses}}{[72(n)^{2}]} + \overset{\text{lepton rest mass}}{[12e19]} + \overset{\text{KEM}}{[m_{e}v^{2}]} \right]_{1}^{8} } $$

Deuterium mass-energy per shell

The measured weight of Matter in gravitational fields is the result of
planar mass-energies in tetryonic standing-wave geometries

The periodicity of all the elements,
along with their exact molar rest mass-energies and
quantum wavefunctions can be described with Tetryonic geometries

Ionisation energies



γ


Un-named series
Humphries series
Pfund series
Brackett series
Paschen series
Balmer series
Lyman series
Spectral Lines

$$ \boxed{Mv^{2} = KEM = \hbar c R_{H}} $$

Photon emission/absorption

Copyright ABRAHAM [2008] - All rights reserved

Photo-electron ionisation energies


n
unbound photo-electron
Continuous spectrum
v^2/c^2
8
7
6
5
4
3
2
1
η 756
ζ 576
ε 420
δ 288
γ 180
β 96
α 36
-13.525 eV
Lyman
K
ζ 720
ε 540
δ 384
γ 252
β 144
α 60
-3.381 eV
Balmer
L
ε 660
δ 480
γ 324
β 192
α 84
-1.502 eV
Paschen
M
δ 576
γ 396
β 240
α 108
-0.845 eV
Brackett
N
γ 468
β 288
α 132
-0.541 eV
Pfund
O
β 336
α 156
-0.375 eV
Humphries
P
α 180
-0.276 eV
Un-named
Q
-0.211 eV
Full levels
R
180
156
132
108
84
60
36
+
768
588
432
300
192
108
48
12
R
Q
P
O
N
M
L
K
3 2 1 0 1 2 3
8 2
7 8
6 18
5 32
4 32
3 18
2 8
1 2
α
f d p s p d f
Opposed electron spins results in Hyperfine splitting & Lamb shifts
β
Azmithal & Magnetic numbers
Energy levels
Atomic Shells
Orbitals & sub-Orbitals
0
1
2
3
+1 0 -1
-1 0 +1
+2 +1 0 -1 -2
-2 -1 0 +1 +2
+3 +2 +1 0 -1 -2 -3
-3 -2 -1 0 +1 +2 +3
2
8
18
32
32
18
8
2
Z
13 11 9 7 5 3 1
2 4 6 8 10 12 14
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 2
s
p
d
f

Eigenstate - Ionisation energies


Atomic shells
P
Q
R
M
O
N
K
L
n
s1
s2
p1
p2
p3
p4
p5
p6
d1
d2
d3
d4
d5
d6
d7
d8
d9
d10
f1
f2
f3
f4
f5
f6
f7
f8
f9
f10
f11
f12
f13
f14
6
7
8
3
5
4
1
2
Quantum numbers


Azmithal & magnetic numbers
3
2
1
0
1
2
3
2
+
8
+
18
+
32
+
32
+
18
+
8
+
2
nuclei per shell
atomic shells
R
Q
P
O
N
M
L
K
8s
7s
7p
6s
6p
6d
5s
5p
5d
5f
4s
4p
4d
4f
3s
3p
3d
2s
2p
1s
f
d
p
s
p
d
f
8
7
6
5
4
3
2
1
energy level
120
119
118
111
110
93
92
61
60
29
28
11
10
3
2
1
element number

The ionisation energies of individual atoms varies due to many factors, namely:
electron spin-orbital coupling with Baryons of specific energies,
the relativistic energies of photo-electrons bound in nuclei
and Zitterbewegung effects on bound electrons

First ionisation energies for all periodic elements

$$E = -\frac{Z^2}{n^2}\frac{ke^2}{2a_0} = -\frac{13.6Z^2}{n^2}eV$$



Proton - Neutron Curve

The graph below is a plot of neutron number against proton number.
It is used as rule to determine which nuclei are stable or unstable.



Deviation from Tetryonic plot is the result of the intrinsic mass-energies of each particle comprising the atomic nucleus

Historically, Proton-electron numbers are viewed as being equivalent in neutral elementary matter with the excess molar mass measured being the result of 'excess or extra' Neutrons in the atom

Atomic Nuclei Numbers

All periodic elements have an EQUAL number of Protons, Neutrons & Electrons with their molar mass-Matter being determined by their quantum level mass-energies



Tetryonic modelling of the charged mass-ENERGY-Matter topologies of elementary atoms and the nuclei that comprise them, reveals a DIRECT LINEAR relationship for the number of Protons-electrons-Neutrons in all periodic elements and nuclear isotopes

Copyright ABRAHAM [2008] - All rights reserved

Planck mass-energy contributions to elementary Matter and isotopes


Deuteron
electron
eV
KEM
Z
32
3,050.6 MeV
31
2,5862.9 MeV
30
2,6811 MeV
29
2,505.4 MeV
28
2,335.6 MeV
27
2,171.8 MeV
26
2,013.9 MeV
25
1,861.9 MeV
8
7
6
5
4
3
2
1
En = -13.52 eV
En = -10.35 eV
En = -7.60 eV
En = -5.28 eV
En = -3.38 eV
En = -1.90 eV
En = -0.84 eV
En = -0.21 eV
291,166
285,065
262,158
213,887
133,697
58,940
19,840
3,725
496.519 keV
n
Quantum levels
v²
2H+
291,107 MeV
Elemental mass-Matter [in MeV]
59,580 keV
e
6,101 MeV
993 keV
En = -27.05 eV
22,903 MeV
3,972 keV
En = -82.8 eV
48,262 MeV
8,937 keV
En = -136.8 eV
80,174 MeV
15,888 keV
En = -168.96 eV
74,740 MeV
15,888 keV
En = -108.16 eV
39,092 MeV
8,937 keV
En = -340 eV
16,111 MeV
3,972 keV
En = -6.72 eV
3,724 MeV
993 keV
En = -0.42 eV
565.11 keV
KEM field mass-energies [in eV]
KE
2 + 8 + 18 + 32 + 32 + 18 + 8 + 2
nuclei number per shell
electron shells
R
Q
P
O
N
M
L
K
Schrodinger's quantum numbers
3
2
1
0
1
2
3
Q
[v·v]
RE
M₀
KE
Z
2
8
18
32
32
18
8
2
c⁴
8
7
6
5
4
3
2
1
energy levels
f
d
p
p
d
f
Bohr's atomic orbitals

The mass-energy content of Deuterium nuclei creates the molar mass of elements
[not extra neutrons in excess of the elemental number]

n1 Elementary nuclei

are comprised of equal numbers of
Protons, Neutrons & electrons
with varying energy levels

Baryons		electrons		KEM fields
930.947 MeV	+	**496.519 keV**	+	**13.525 ev**

The mass-energy content of Matter topologies is velocity invariant

The mass-energy content of Baryons determines the KEM field of electrons

Copyright ABRAHAM [2008] - All rights reserved

$$\overset{\text{Baryons}}{930.947\text{ MeV}} + \overset{\text{KEM fields}}{13.525\text{ ev}} + \overset{\text{electrons}}{496.519\text{ keV}}$$

Mapping Planck mass-energy contributions to elementary Matter and isotopes


Schrodinger's quantum numbers
3
2
1
0
1
2
3
electron shells
R
Q
P
O
N
M
L
K
Q
[v-v]
RE
2
8
18
32
Z
32
18
8
2
M₀
KE
8
7
6
5
4
3
2
1
energy levels
f
d
p
c⁴
p
d
f
Bohr's atomic orbitals

$$E = hv^2$$

$$n^2 + v^2 + e = Z$$

general form quatratic equation

$$ax^2 + bx + c = Z$$

$$E = nhv$$


E
polar aufbau

polar energy spirals courtesy of Rene Cormier

Identifying electron rest Matter topologies as velocity invariant we can re-arrange the component Planck mass-energy geometry formulation of periodic elements to

$$h\left[\underset{\text{Deuteron rest mass}}{72[v^2]} + \underset{\text{Spectral lines}}{v} + \underset{\text{electron rest mass}}{1.20\text{ e}20\text{ v}}\right]$$

reveal a quadratic formulation for all Z numbers

Copyright ABRAHAM [2008] - All rights reserved

All elements are comprised of n level Duetrium nuclei

Baryons **KEM fields** **electrons**

$$Z\,[[72n^2] + [12v^2] + [1.2e20]]$$

1,861,949 MeV **13.525 eV** **496,519 keV**

$2H^+$ Z γ

$[72n^2]$ $[M_e v^2]$

Elemental mass-Matter [in MeV]

The atomic shell energy levels of Deuterium nuclei in elements



Deuteron	electron eV	KEM
32 3,050.6 MeV	8	En = -13.52 eV
31 2,5862.9 MeV	7	En = -10.35 eV
30 2,6811 MeV	6	En = -7.60 eV
29 2,505.4 MeV	5	En = -5.28 eV
28 2,335.6 MeV	4	En = -3.38 eV
27 2,171.8 MeV	3	En = -1.90 eV
26 2,013.9 MeV	2	En = -0.84 eV
25 1,861.9 MeV	1	En = -0.21 eV

496.519 keV

m v^2

Determines the spectral line [KEM field energies] of electrons bound to them



atomic shells					nuclei per shell
R	3,050.6 MeV	13.525 eV	$Z\,[[72{*}32n^2] + [12{*}8v^2] + [1.2e20]]$	496,519 keV	2
					+
Q	2,862.9 MeV	10.35 eV	$Z\,[[72{*}31n^2] + [12{*}7v^2] + [1.2e20]]$	496,519 keV	8
					+
P	2,681.2 MeV	7.60 eV	$Z\,[[72{*}30n^2] + [12{*}6v^2] + [1.2e20]]$	496,519 keV	18
					+
O	2,505.4 MeV	5.28 eV	$Z\,[[72{*}29n^2] + [12{*}5v^2] + [1.2e20]]$	496,519 keV	32
					+
N	2,335.6 MeV	3.38 eV	$Z\,[[72{*}28n^2] + [12{*}4v^2] + [1.2e20]]$	496,519 keV	32
					+
M	2,171.7 MeV	1.90 eV	$Z\,[[72{*}27n^2] + [12{*}3v^2] + [1.2e20]]$	496,519 keV	18
					+
L	2,013.8 MeV	0.84 eV	$Z\,[[72{*}26n^2] + [12{*}2v^2] + [1.2e20]]$	496,519 keV	8
					+
K	1861.9 MeV	0.21 eV	$Z\,[[72{*}25n^2] + [12{*}1v^2] + [1.2e20]]$	496,519 keV	2

6,101 MeV
993 keV
En = -27.05 eV
+
22,903 MeV
3,972 keV
En = -82.8 eV
+
48,262 MeV
8,937 keV
En = -316.8 eV
+
80,174 MeV
15,888 keV
En = -168.96 eV
+
74,740 MeV
15,888 keV
En = -108.16 eV
+
39,092 MeV
8,937 keV
En = -34.2 eV
+
16,111 MeV
3,972 keV
En = -6.72 eV
+
3,724 MeV
993 keV
En = -0.42 eV

[1.2e20]]

e

the rest mass-Matter of bound photo-electrons is velocity invariant

The relativistic rest mass-energy-Matter of all periodic elements

is the sum of the mass-energies of all atomic nuclei and spectral lines that comprise its mass-Matter topology as measured in any spatial co-ordinate system per unit of time

Copyright ABRAHAM [2008] - All rights reserved



Avagadro's number

6.022141579 e26
atoms in 1KG of Matter

1 KG mass
[of Matter]

1.660538841 e-27 kg
atomic rest mass-Matter

Hydrogen

01

using SI units Avagadro's number can be expressed exactly as the inverse rest mass of Hydrogen

Carbon

12

Weighted atomic mass

5.019789213 e25
atoms in 1KG of Matter

6.02214078 e 23

1.99211552 e-26 kg
atomic rest mass-Matter



Tetryonic charge geometries make weighted atomic mass measurements and calculations obsolete

22,506 1/12 of Carbon 12 [Graphene] is not equal to 1 Hydrogen atom 22,512
(Deuterium is the building block of all atomic elements]



1.966225348 e25
atoms in 1KG of Matter

International Avagadro project

5.085887033 e-26 kg
atomic rest mass-Matter

Silicon



28

The gram was originally defined in 1795 as the mass of one cubic centimeter of water at 4°C,
making the kilogram equal to the mass of one liter of water.

The prototype kilogram, manufactured in 1799 and from which the current kilogram is based
has a mass equal to the mass of 1.000025 liters of water

In recent years two major experiments, namely the Watt balance & Avagadro projects, have been attempting to
measure and define 1KG of mass-Matter in terms of electrical force and the number of atoms respectively
in order to better define 1KG of mass-Matter precisely for all future physical references

Platinum

191

La Grande K

2.817950081 e24
atoms in 1KG of Matter
3.181804449 e23

90% Pt
10% Ir

The La grande K is an alloy of 90% Platinum & 10% Iridium that has been slowly losing mass since its manufacture

3.1893811012 e-25 kg
atomic rest mass-Matter
3.142870708 e-25 kg



All atomic rest masses are for atoms at absolute zero and any deviation is a measure of the topological Matter's Kinetic energy content [chemical energy, KEM fields and/or spectral lines]



Incorporating

- *Quark configurations*
- *Nuclei geometries*
- *Chemical bond points*
- *Atomic Orbitals*
- *Hund Rule*
- *Pauli exclusion*
- *Aufbau filling principle*
- *Element names, numbers and*
- *Elementary families*

Element placements that reflects the true quantum geometries of periodic elements

● UP Quark

● DOWN Quark

Periodic Table 2.0

(the quantum geometry of periodic elements)

R Q P O N M L K
8 7 6 5 4 3 2 1
f 7
1-14 Actinoid
1-14 Lanthanoid
d 5
9-10 Post Transition Metal
1-8 Transition Metal
p 3
6 Noble Gas
5 Halogen
1-4 Non-Metal Metaloid Poor-Metal
s 1
2 Alkaline Earth
1 Alkali Metal
Shells
Energy levels
Orbitals
sub orbital
Family
azmithal & magnetic quantum numbers
+3 +2 +1 0 -1 -2 -3
Atomic shells
energy levels
Z
2 8 18 32 32 18 8 2
f d p s p d f
electron orbitals & sub-orbitals
n
Energy levels
Atomic shells

Copyright ABRAHAM [2008] - All rights reserved


48
[24-24]
H
1.0000
H
22,512
[1.660538841 e-27 kg]
KE
Hydrogen
0
Baryonic energies
and photon interactions
determine Lepton energies
R
Q
P
O
N
M
L
K
1/2
8
7
6
5
4
3
2
1
Shell
Nuclei
electron configuration
1s1
h
13.525 eV
photo-electron
ionisation energy
Humphries series
Pfund series
Brackett series
Paschen series
Balmer series
Lyman series
atomic shell
Orbitals & sub-orbitals
energy level

Hydrogen is NOT a periodic element
[Deuterium is the building block of elements]

Aufbau

atomic shell		energy level
R	5.107765145 e13	8
Q	6.671366720 e13	7
P	9.078047137 e13	6
O	1.307587877 e14	5
N	2.043106058 e14	4
M	3.632188548 e14	3
L	8.172424234 e14	2
K	3.268969693 e15	1

Tetryonics 51.00 - Hydrogen atom

Copyright ABRAHAM [2008] - All rights reserved


84
[42-42]
D
1.9995
45,012
[3.320192534 e-27 kg]
electron configuration
1s1
Aufbau
Deuterium
01
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
1
f d p s p d f
01
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
n1
Alkali
Metal
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
1
1
s
atomic shell
Orbital & sub-orbitals
energy level

Tetryonics 51.01 - Deuterium atom


168
[84-84]
He
3.9989
1
1
He
2
1
90,024
[6.640385068 e-27 kg]
electron configuration
1s2
Helium
02
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
2
f d p s p d f
02
Potons [24-12]
Neutrons [18-18]
electrons [0-12]
m1
Alkaline Earth
Aufbau
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
2
1 s 2
atomic shell
Orbital & sub-orbitals
energy level

Tetryonics 51.02 - Helium atom


252
[126-126]
Li
6.1615
1
2
2
1
Li
138,708
[1.023143308 e-26 kg]
3,672
[0.1519 GeV]
electron configuration
[He] 2s1
2
Aufbau
Lithium
03
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
3
f d p s p d f
03
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-2
Alkali
Metal
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
1
2
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.03 - Lithium atom

Copyright ABRAHAM [2008] - All rights reserved


336
[168-168]
Be
8.3241
1
2
2
2
Be
187,392
[1.3822481e-26 kg]
7,344
[0..303 GeV]
electron configuration
[He] 2s2
2
Aufbau
Beryllium
04
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
4
f d p s p d f
Azmithal & Magnetic numbers
04 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-2
Alkaline Earth
R Q P O N M L K
8 7 6 5 4 3 2 1
0
2
2
1 s 2
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.04 - Beryllium atom

Copyright ABRAHAM [2008] - All rights reserved


420
[210-210]
B
10.4867
236,076
[1.741352851 e-26 kg]
11,016
[0.455 GeV]
electron configuration
[He] 2s2 2p1
Aufbau
Boron
05
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
5
f d p s p d f
05 Protons [24-12] Neutrons [18-18] electrons [0-12] n1-2
Metaloid
Azmithal & Magnetic numbers
1 0
-1
1
3
2
p
s
1 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.05 - Boron atom


504
[252-252]
C
12.6493
1
2
1
2
2
1
2
284,760
[2.100457713 e-26 kg]
14,688
[0.6077 GeV]
Carbon
06
3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
6
f d p s p d f
06 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-2
Metaloid
electron configuration
[He] 2s2 2p2
2
Aufbau
Azmithal & Magnetic numbers
1 0 1
-1 -1
4
1 2
2
p p
1 s 2
Orbitals & sub-orbitals
atomic shell
energy level

Tetryonics 51.06 - Carbon atom


588
[294-294]
N
14.8118
1
1
2
2
2
1
2
3
2
1
N
333,444
[2.4659562515 e-26 kg]
18,360
[0.759 GeV]

Nitrogen

07


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
7
f
d
p
s
p
d
f

electron configuration

[He] 2s2 2p3

2

Aufbau

07 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-2

Metaloid

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
1
0
1
0
-1
-1
5
2
3
1
2
p
p
1
s
2
atomic shell
energy level

Orbitals & sub-orbitals


672
[336-336]
O
16.9744
382,128
[2.818667317 e-26 kg]
22,032
[0.9116 GeV]
Oxygen
08
electron configuration
[He] 2s2 2p4
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
8
f d p s p d f
08 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-2
Metaloid
Azmithal & Magnetic numbers
1 0 1
0 -1 -1 0
6
2
3 1 2 4
p s p
1 2
Orbitals & sub-orbitals
atomic shell
energy level

Tetryonics 51.08 - Oxygen atom

Copyright ABRAHAM [2008] - All rights reserved


756
[378-378]
F
19.1370
430,812
[3.17777119 e-26 kg]
25,704
[1.063 GeV]
Fluorine
09
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
9
f d p s p d f
electron configuration
Aufbau
[He] 2s2 2p5
09 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-2
Halogen
Azmithal & Magnetic numbers
1 0 1
+1 0 -1 -1 0
7
2
5 3 1 2 4
p s p
1 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.09 - Fluorine atom


840
[420-420]
Ne
21.2996
479,496
[3.53687692 e-26 kg]
29,376
[1.2155 GeV]
Neon
10
electron configuration
[He] 2s2 2p6
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
10
f d p s p d f
10 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-2
Noble Gas
Azmithal & Magnetic numbers
1 0 1
+1 0 -1 -1 0 +1
8
2
5 3 1 2 4 6
p s p
1 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.10 - Neon atom

Copyright ABRAHAM [2008] - All rights reserved


924
[462-462]
Na
23.6317
531,996
[3.924129448 e-26 kg]
36,864
[15253 GeV]
1
Na
2
3
4
5
6
electron configuration
Aufbau
[Ne] 3s1
10
Sodium
11
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
11
f d p s p d f
11 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-3
Alkali Metal
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
1
1
+1 0 -1
-1 0 +1
1
8
2
5 3 1
2 4 6
p
p
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.11 - Sodium atom

Copyright ABRAHAM [2008] - All rights reserved


1,008
[504-504]
Mg
25.9638
5
4
1
1
2
2
Mg
3
6
3
3
1
584,496
[4.31138197 e-26 kg]
44,352
[1.835 GeV]
electron configuration
[Ne] 3s2
10
Aufbau
Magnesium
12
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
8
7
6
5
4
3
2
1
12
f
d
p
s
p
d
f
12
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-3
Alkaline
Earth
Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
+1
0
-1
-1
0
+1
2
8
2
5
3
1
2
4
6
p
p
1
s
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.12 - Magnesium atom


1,092
[546-546]
Al
28.2958
5
4
3
1
2
1
2
1
Al
2
3
6
636,996
[4.698634505 e-26 kg]
51,840
[2.3450 GeV]
Aluminium
13
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
13
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f
electron configuration
[Ne] 3s2 3p1
10
Aufbau
Azmithal & Magnetic numbers
13
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-3
Metaloid
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
-1
1
1
+1
0
-1
0
+1
3
8
2
5
3
1
2
4
6
p
p
1
s
2
atomic shell
Orbitals & sub-orbitals
energy level

Tetryonics 51.13 - Aluminium atom


1,176
[588-588]
Si
30.6279
1
2
3
4
5
6
Si
689,496
[5.085887033 e -26 kg]
59,328
[2.4548 GeV]
Silicon
14
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
14
f d p s p d f
electron configuration
[Ne] 3s2 3p2
10
Aufbau
14
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-3
Metaloid
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
1
1
-1
-1
+1
0
0
+1
4
8
2
5
3
1
2
4
6
p
p
1
s
2
atomic shell
Orbitals & sub-orbitals
energy level

Tetryonics 51.14 - Silicon atom

Copyright ABRAHAM [2008] - All rights reserved



1,260
[630-630]

P
32.9600

741,996
[5.473139562 e-26 kg]

66,816
[2.7646 GeV]

Phosphorus

15

electron configuration
[Ne] 3s2 3p3
10

Aufbau

15 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-3

Metaloid

Azmithal & Magnetic numbers

Orbitals & sub-orbitals

atomic shell

energy level

3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
1 0
0 -1 -1
+1 1 0 +1
5
8
2
5 3 1 2 4 6
p p
1 s 2

Tetryonics 51.15 - Phosphorus atom

Copyright ABRAHAM [2008] - All rights reserved


1,344
[672-672]
S
35.2821
794,496
[5.86039209 e-26 kg]
74,304
[3.074 GeV]
Sulfur
16
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
16
f d p s p d f
electron configuration
[Ne] 3s2 3p4
10
Aufbau
16 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-3
Metaloid
Azmithal & Magnetic numbers
1 0 1
0 -1 -1 0
+1 +1
6
8
2
5 3 1 2 4 6
p p
1 s 2
Orbitals & sub-orbitals
atomic shell
energy level

Tetryonics 51.16 - Sulfur atom


1,428
[714-714]
Cl
37.6242
846,996
[6.247644618 e-26 kg]
81,792
[3.6384 GeV]
Chlorine
17
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
17 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-3
Halogen
electron configuration
[Ne] 3s2 3p5
10
Aufbau
Azmithal & Magnetic numbers
1 0 1
+1 0 -1 -1 0 +1
7
8
2
5 3 1 2 4 6
p s p
1 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.17 - Chlorine atom

Copyright ABRAHAM [2008] - All rights reserved


1,512
[756-756]
Ar
39.9563
5
4
3
1
2
2
2
1
2
3
2
6
Ar
3
2
899,496
[6.634897147 e-26 kg]
89,280
[3.694 GeV]
Argon
18
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
18
f d p s p d f
electron configuration
[Ne] 3s2 3p6
10
Aufbau
18
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-3
Noble Gas
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
1 0 1
+1 0 -1 -1 0 +1
8
8
2
5 3 1 2 4 6
p p
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.18 - Argon atom


1,596
[798-798]
K
42.4643
955,956
[7.05135958 e-26 kg]
100,728
[4.167 GeV]
Potassium
19
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
19
f d p s p d f
electron configuration
[Ar] 4s1
18
Aufbau
19 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-4
Alkali Metal
Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
1 1
+1 0 -1 -1 0 +1
1
8
8
2
5 3 1 2 4 6
p p
1 s 2
atomic shell
Orbitals & sub-orbitals
energy level

Tetryonics 51.19 - Potassium atom

Copyright ABRAHAM [2008] - All rights reserved

1,680
[840-840]

Ca
44.9723


5
4
1
1
2
2
Ca
3
6
2
2
2
2
2
2
4
4

1,012,416
[7.467822013 e-26 kg]

112,176
[4.641 GeV]

Calcium

20


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
20
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f

20 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4

Alkaline Earth

electron configuration

[Ar] 4s2
18

Aufbau

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
+1
0
-1
-1
0
+1
2
8
8
2
5
3
1
2
4
6
p
p
1
s
2
atomic shell
energy level

Orbitals & sub-orbitals

Tetryonics 51.20 - Calcium atom


1,764
[882-882]
Sc
47.3044
1,064,916
[7.855074541 e-26 kg]
119,664
[4.951 GeV]
Scandium
21
electron configuration
[Ar] 3d1 4s2
18
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
21
f d p s p d f
21
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-4
Transition Metal
Azmithal & Magnetic numbers
0
1
1
2
d
-2 +1 0 -1 -1 0 +1
2
9
8
2
p
p
s
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.21 - Scandium atom


1,848
[924-924]
Ti
49.6365
1,117,416
[8.242327069 e-26 kg]
127,152
[5.261 GeV]
Ti
Titanium
22
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
22
f d p s p d f
22
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-4
Transition Metal
electron configuration
[Ar] 3d2 4s2
18
Aufbau
Azmithal & Magnetic numbers
0
2
10
8
2
d
p
s
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.22 - Titanium atom

Copyright ABRAHAM [2008] - All rights reserved


1,932
[966-966]
Va
51.9888
1,169,916
[8.629579598 e-26 kg]
134,640
[5.570 GeV]
Vanadium
23
electron configuration
[Ar] 3d3 4s2
18
Aufbau
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
Q
RE
M
KE
f d p s p d f
23 Protons [24-12] Neutrons [18-18] electrons [0-12] m1-4
Transition Metal
Azmithal & Magnetic numbers
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.23 - Vanadium atom

Copyright ABRAHAM [2008] - All rights reserved


2,016
[1,008-1,008]
Cr
54.3008
1,222,416
[9.016832126 e-26 kg]
142,128
[5.880 GeV]
Chromium
24
electron configuration
[Ar] 3d4 4s2
18
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
24 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4
Transition Metal
Azmithal & Magnetic numbers
0
2 1 1 2
12
8
d p s p d
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.24 - Chromium atom

Copyright ABRAHAM [2008] - All rights reserved


2,100
[1,050-1,050]
Mn
56.6327
1,274,916
[9.404084654 e-26 kg]
149,616
[6.190 GeV]
Manganese
25
electron configuration
[Ar] 3d5 4s2
18
Aufbau
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
Q
RE
M
KE
f d p s p d f
25
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
n1-4
Transition
Metal
Azmithal & Magnetic numbers
0
2 1 1 2
2
13
8
2
d p s p d
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.25 - Manganese atom

Copyright ABRAHAM [2008] - All rights reserved


2,184
[1,092-1,092]
Fe
58.9648
1,327,416
[9.791337183 e-26 kg]
157,104
[6,500 GeV]
Iron
26
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
[Ar] 3d6 4s2
18
Aufbau
26 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4
Transition Metal
Azmithal & Magnetic numbers
0
2 1 1 2
0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0
2
14
8
2
5 3 1 2 4 6
d d
5 3 1 2 4 6
p p
1 2
s
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.26 - Iron atom


2,268
[1,134-1,134]
Co
61.2969
1,379,916
[1.017858971 e-25 kg]
164,592
[6.810 GeV]
Cobalt
27
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
[Ar] 3d7 4s2
18
Aufbau
Azmithal & Magnetic numbers
27 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4
Transition Metal
2 1 0 1 2
+1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0
2
15
8
2
7 5 3 1 2 4 6
d d
5 3 1 2 4 6
p p
1 s 2
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.27 - Cobalt atom

Copyright ABRAHAM [2008] - All rights reserved


2,352
[1,176-1,176]
Ni
63.6290
1,432,416
[1.056584224 e-25 kg]
172,080
[7,150 GeV]
Nickel
28
electron configuration
[Ar] 3d8 4s2
18
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
28 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4
Transition Metal
Azmithal & Magnetic numbers
0
2 1 1 2
2
16
8
2
d p s p d
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.28 - Nickel atom

Copyright ABRAHAM [2008] - All rights reserved


2,436
[1,218-1,218]
Cu
65.9811
1,484,916
[1.095309477 e-25 kg]
179,568
[7.429 GeV]
Copper
29
electron configuration
[Ar] 3d9 4s2
18
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
29 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-4
Post Transition Metal
Azmithal & Magnetic numbers
0
2 1 1 2
+2 +1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0 +1
2
17
8
2
9 7 5 3 1 2 4 6 8
d d
5 3 1 2 4 6
p p
1 s 2
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.29 - Copper atom


2,520
[1,260-1,260]
Zn
68.2932
1,537,416
[1.13403473 e-25 kg]
187,056
[7.739 GeV]
Zinc
30
electron configuration
[Ar] 3d10 4s2
18
Aufbau
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
f d p s p d f
Q
RE
M
KE
30 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4
Post Transition Metal
Azmithal & Magnetic numbers
0
2 1 1 2
+2 +1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0 +1 +2
2
18
8
2
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.30 - Zinc atom

Copyright ABRAHAM [2008] - All rights reserved


2,604
[1,302-1,302]
Ga
70.8012
1,593,876
[1.175680973 e-25 kg]
198,504
[8.213 GeV]
Gallium
31
electron configuration
[Ar] 3d10 4s2 4p1
18
Aufbau
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
f d p s p d f
Q
RE
M
KE
31
31
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-4
Metaloid
Azmithal & Magnetic numbers
0
2 1 1 2
3
18
8
2
d d p p s
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.31 - Gallium atom


2,688
[1,344-1,344]
Ge
73.3092
Ge
1,650,336
[1.217327216 e-25 kg]
209,952
[8.687 GeV]
Germanium
32
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
32
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f
electron configuration
Aufbau
[Ar] 3d10 4s2 4p2
18
32
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-4
Metaloid
Azmithal & Magnetic numbers
0
2
1
1
2
-1
-1
+2
+1
0
-1
-2
+1
0
0
+1
-2
-1
0
+1
+2
4
18
8
2
9
7
5
3
1
2
4
6
8
10
5
3
1
2
4
6
1
2
d
d
p
p
s
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.32 - Germanium atom


2,772
[1,386-1,386]
As
75.8172
As
1,706,796
[1.258973460 e-25 kg]
221,400
[9.160 GeV]

Arsenic

33


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
33
f
d
p
s
p
d
f

electron configuration

Aufbau

[Ar] 3d10 4s2 4p3
18

33 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4

Metaloid


Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
2
1
2
5
18
8
2
d
d
p
p
s
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.33 - Arsenic atom

Copyright ABRAHAM [2008] - All rights reserved


2,856
[1,428-1,428]
Se
78.3252
1,763,256
[1.30069703 e-25 kg]
232,848
[9,634 GeV]
Selenium
34
electron configuration
[Ar] 3d10 4s2 4p4
18
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
34 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4
Metaloid
Azmithal & Magnetic numbers
6
18
8
2
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.34 - Selenium atom


2,940
[1,470-1,470]
Br
80.8332
1,819,716
[1.342265946 e-25 kg]
244,296
[10.108 GeV]
Bromine
35
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
35
f d p s p d f
35 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4
Halogen
electron configuration
[Ar] 3d10 4s2 4p5
36
Aufbau
Azmithal & Magnetic numbers
1 0 1
2 2
7
18
8
2
d d
p p
s
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.35 - Bromine atom


3,024
[1,512-1,512]
Kr
83.3412
1,876,176
[1.383912190 e-25kg]
255,744
[10.582 GeV]
Krypton
36
electron configuration
[Ar] 3d10 4s2 4p6
36
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
36 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-4
Noble Gas
Azmithal & Magnetic numbers
8
18
8
2
d
p
s
d
p
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.36 - Krypton atom


3,108
[1.554-1.554]
Rb
86.0315
1,936,740
[1.428585641 e-25 kg]
271,296
[11.225 GeV]
Rubidium
37
electron configuration
[Kr] 5s1
36
Aufbau
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
f d p s p d f
Q
RE
M
KE
37
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-5
Alkali Metal
Azmithal & Magnetic numbers
0
1
1
2
2
1
8
18
8
2
d
d
p
p
s
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.37 - Rubidium atom


3,192
[1,596-1,596]
Sr
88.7218
1,997,304
[1.473259093 e-25 kg]
286,848
[11.868 GeV]
Strontium
38
electron configuration
[Kr] 5s2
36
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
38
f d p s p d f
38 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5
Alkaline Earth
Azmithal & Magnetic numbers
0
1
1
2
2
+1 0 -1
-1 0 +1
+2 +1 0 -1 -2
-2 -1 0 +1 +2
2
8
18
8
2
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 2
d
d
p
p
s
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.38 - Strontium atom

Copyright ABRAHAM [2008] - All rights reserved


3,276
[1,638-1,638]
Yt
91.2297
Yt
2,053,764
[1.514905336 e-25 kg]
298,296
[12.342 GeV]
electron configuration
[Kr] 4d1 5s2
36
Aufbau
Yttrium
39
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
39
f d p s p d f
39 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5
Transition Metal
Azmithal & Magnetic numbers
0
1
1
2
2
-2 +1 0 -1
-1 0 +1
+2 +1 0 -1
-2 -1 0 +1 +2
2
9
18
8
2
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 2
d
d
p
p
s
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.39 - Yttrium atom

Copyright ABRAHAM [2008] - All rights reserved


3,360
[1,680-1,680]
Zr
93.7377
2,110,224
[1.556551580 e-25 kg]
309,744
[12.816 GeV]
Zirconium
40
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
40
f d p s p d f
electron configuration
[Kr] 4d2 5s2
36
Aufbau
40 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5
Transition Metal
Azmithal & Magnetic numbers
0
1
1
2
2
-2 +1 0 -1
-1 0 +1 -2
+2 +1 0 -1
-1 0 +1 +2
2
10
18
8
2
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 2
d
d
p
p
s
atomic shell
energy level
Orbital & sub-orbitals

Tetryonics 51.40 - Zirconium atom

Copyright ABRAHAM [2008] - All rights reserved


3,444
[1,722-1,722]
Nb
98.2457
9
1
3
7
5
Nb
5
4
1
1
2
2
3
6
6
8
4
2
10
2,166,684
[1.598197823 e-25 kg]
321,192
[13.289 GeV]

Niobium

41

electron configuration

[Kr] 4d3 5s2
36


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
41
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f

41 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5

Transition Metal

Aufbau

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
0
2
1
1
11
2
2
18
8
2
-1
-2
+1
0
-1
-1
0
+1
-2
+2
+1
0
-1
0
+1
+2
9
7
5
3
1
2
4
6
8
10
d
d
5
3
1
2
4
6
p
p
1
s
2
8
7
6
5
4
3
2
1
atomic shell
energy level

Orbitals & sub-orbitals

Tetryonics 51.41 - Niobium atom

Copyright ABRAHAM [2008] - All rights reserved


3,528
[1,764-1,764]
Mo
98.7537
2,223,144
[1.639844066 e-25 kg]
332,640
[13.763 GeV]
Molybdenum
42
electron configuration
[Kr] 4d4 5s2
36
Aufbau
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
f d p s p d f
Q
RE
M
KE
42
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-5
Transition
Metal
Azmithal & Magnetic numbers
2
12
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.42 - Molybdenum atom

Copyright ABRAHAM [2008] - All rights reserved


3,612
[1,806-1,806]
Tc
101.2617
2,279,604
[11.681490310 e-25 kg]
344,088
[14.237 GeV]
Technetium
43
electron configuration
[Kr] 4d5 5s2
36
Aufbau
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
Q
RE
M
KE
f d p s p d f
43 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5
Transition Metal
Azmithal & Magnetic numbers
0
2
13
18
8
2
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.43 - Technetium atom

Copyright ABRAHAM [2008] - All rights reserved



3,696
[1,848-1,848]
Ru
103.7697
9
1
3
7
5
2
5
4
1
2
6
8
10
Ru
2,336,064
[1.72336553 e-25 kg]
355,536
[14.710 GeV]
Ruthenium
44
3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
8
7
6
5
4
3
2
1
44
f
d
p
s
p
d
f
electron configuration
[Kr] 4d6 5s2
36
44
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-5
Transition Metal
Aufbau
Azmithal & Magnetic numbers
0
2
14
18
8
2
+2
+1
0
-1
-2
d
p
s
1
2
3
4
5
6
7
9
10
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.44 - Ruthenium atom


3,780
[1,890-1,890]
Rh
106.2777
Rh
2,392,524
[1.764782796 e-25 kg]
366,984
[15.184 GeV]
Rhodium
45
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
45
f d p s p d f
electron configuration
[Kr] 4d7 5s2
36
Aufbau
45 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5
Transition Metal
Azmithal & Magnetic numbers
0
2 1 1 2
+1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0
+2 +1 +2
2
15
18
8
2
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
atomic shell
Orbitals & sub-orbitals
energy level

Tetryonics 51.45 - Rhodium atom


3,864
[1,932-21,932]
Pd
108.7857
2,448,984
[1.806429039 e-25 kg]
378,432
[15.699 GeV]
Palladium
46
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
46
f d p s p d f
electron configuration
[Kr] 4d8 5s2
36
Aufbau
46 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5
Transition Metal
Azmithal & Magnetic numbers
0
2 1 1 2
2
16
18
8
2
d d
p p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.46 - Palladium atom


3,948
[1,974-1,974]
Ag
111.2937
2,505,444
[1.848075283 e-25 kg]
389,880
[16.121 GeV]
Silver
47
R
Q
P
O
N
M
L
K
3
2
1
0
1
2
3
Q
RE
M
KE
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f
electron configuration
[Kr] 4d9 5s2
36
47
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-5
Post Transition Metal
Aufbau
Azmithal & Magnetic numbers
2
17
18
8
2
d
p
s
p
d
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.47 - Silver atom

Copyright ABRAHAM [2008] - All rights reserved


4,032
[2,016-2,016]
Cd
113.8017
Cd
10
2,561,904
[1.889721526 e-25 kg]
401,328
[16.605 GeV]
Cadmium
48
electron configuration
[Kr] 4d10 5s2
36
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
M
KE
48
8 7 6 5 4 3 2 1
f d p s p d f
48 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5
Post Transition Metal
Azmithal & Magnetic numbers
0
2 1 1 2
+2 +1 0 -1 -2 +1 0 -1 -1 0 +1 -2 -1 0 +1 +2
2
18
18
8
2
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.48 - Cadmium atom


4,116
[2,058-1,058]
In
116.4920
9
1
3
7
5
5
4
1
In
1
2
2
3
6
6
8
4
2
10
2,622,468
[1.934394978 e-25 kg]
416,880
[17.249 GeV]

Indium

49


3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
M
KE
49
8 7 6 5 4 3 2 1
f d p s p d f

electron configuration

[Kr] 4d10 5s2 5p1

36

49 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-5

Aufbau

Azmithal & Magnetic numbers


R Q P O N M L K
8 7 6 5 4 3 2 1
0
-1
2
1
1
2
+2 +1 0 -1 -2 +1 0 -1 0 +1 -2 -1 0 +1 +2
3
18
18
8
2
9 7 5 3 1
2 4 6 8 10
d
d
5 3 1
2 4 6
p
p
1 2
s
atomic shell
energy level

Orbitals & sub-orbitals

Tetryonics 51.49 - Indium atom

Copyright ABRAHAM [2008] - All rights reserved


4,200
[2,100-2,100]
Sn
119.1823
2,683,032
[1.979068429 e-25 kg]
432,432
[17.392 GeV]
Sn
electron configuration
[Kr] 4d10 5s2 5p2
36
Aufbau
Tin
50
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
50
f d p s p d f
50 Protons [24-12] Neutrons [18-18] electrons [0-12] m1-5
Metaloid
Azmithal & Magnetic numbers
0
1
2
4
18
18
8
2
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.50 - Tin atom


9
1
3
7
5
5
4
1
1
2
2
At
3
6
6
8
4
2
10

4,284
[2,142-2,142]

At
121.8726

2,743,596
[2.02374188 e-25 kg]

447,984
[18.536 GeV]

Antimony

51


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
51
M
KE
f
d
p
s
p
d
f

electron configuration

Aufbau

[Kr] 4d10 5s2 5p3
36

51 [Protons [24-12]
Neutrons [18-18]
electrons [0-12]] m1-5

Metaloid

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
+2 +1 0 -1 -2
1
0 -1
0
-1 +1
1
0 +1
2
-2 -1 0 +1 +2
5
18
18
8
2
9 7 5 3 1
d
5 3 1
p
1 s 2
2 4 6
p
2 4 6 8 10
d

atomic shell

energy level

Orbitals & sub-orbitals

Tetryonics 51.51 - Antimony atom


4,368
[2,184-2,184]
Te
124.5629
2,804,160
[2.068415333 e-25 kg]
463,536
[19.179 GeV]
Tellurium
52
R
Q
P
O
N
M
L
K
3
2
1
0
1
2
3
Q
RE
M
KE
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f
electron configuration
[Kr] 4d10 5s2 5p4
36
52 [Protons [24-12]
Neutrons [18-18]
electrons [0-12]] m1-5
Metaloid
Aufbau
Azmithal & Magnetic numbers
6
18
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.52 - Tellurium atom

Copyright ABRAHAM [2008] - All rights reserved


4,452
[2,226-2,226]
I
127.2532
9
1
3
7
5
1
5
4
1
2
3
6
6
8
4
2
10
2,864,724
[2.113088784 e-25 kg]
479,088
[19.823 GeV]

Iodine

53


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
53
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f

electron configuration

[Kr] 4d10 5s2 5p5
36

53 [Protons [24-12]
Neutrons [18-18]
electrons [0-12]] m1-5

Halogen

Aufbau

Azmithal & Magnetic numbers


R
Q
P
O
N
M
L
K
1
0
1
+1
0
-1
-1
0
2
2
+2
+1
0
-1
-2
+1
-2
-1
0
+1
+2
7
18
18
8
2
9
7
5
3
1
2
4
6
8
10
d
d
5
3
1
2
4
6
p
p
1
s
2
8
7
6
5
4
3
2
1
atomic shell
energy level

Orbitals & sub-orbitals

Tetryonics 51.53 - Iodine atom

Copyright ABRAHAM [2008] - All rights reserved


4,536
[2,3268-2,268]
Xe
129.9435
2,925,288
[2.157762236 e-25 kg]
494,640
[20.466 GeV]
Xenon
54
3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
M
KE
8 7 6 5 4 3 2 1
f d p s p d f
electron configuration
[Kr] 4d10 5s2 5p6
36
Aufbau
54 Protons [24-12] Neutrons [18-18] electrons [0-12] m1-5
Noble Gas
Azmithal & Magnetic numbers
8
18
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.54 - Xenon atom


4,620
[2,310-2,310]
Cs
132.8225
2,990,100
[2.205569114 e-25 kg]
514,440
[21.285 GeV]
Caesium
55
electron configuration
[Xe] 6s1
54
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
55
f d p s p d f
55 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Alkali Metal
Azmithal & Magnetic numbers
0
1
8
18
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.55 - Caesium atom

Copyright ABRAHAM [2008] - All rights reserved


4,704
[2,352-2,352]
Ba
135.7015
Ba
3,054,912
[2.253375992 e-25 kg]
534,240
[22.105 GeV]

Barium

56


3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
56
M
KE
8 7 6 5 4 3 2 1
f d p s p d f

56 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6

Alkaline Earth

electron configuration

[Xe] 6s2
54

Aufbau

Azmithal & Magnetic numbers


R Q P O N M L K
0
1 1
+1 0 -1 -1 0 +1
2 2
+2 +1 0 -1 -2 -2 -1 0 +1 +2
2
8
18
18
8
2
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
8 7 6 5 4 3 2 1
atomic shell
energy level

Orbitals & sub-orbitals

Tetryonics 51.56 - Barium atom


4,788
[2,394-2,394]
La
138.2095
3,111,372
[2.295022235 e-25 kg]
545,688
[22.578 GeV]
Lanthanum
57
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
[Xe] 4f1 6s2
54
Aufbau
57 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Lanthanoid
Azmithal & Magnetic numbers
0
2
8
19
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.57 - Lanthanum atom


4,872
[2,436-2,436]
Ce
140.7175
3,167,832
[2.336668478 e-25 kg]
557,136
[23.052 GeV]
Cerium
58
3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
M
KE
8 7 6 5 4 3 2 1
f d p s p d f
electron configuration
[Xe] 4f2 6s2
54
58 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Lanthanoid
Aufbau
Azimuthal & Magnetic numbers
2
8
20
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.58 - Cerium atom


4,956
[2,478-2,478]
Pr
143.2255
3,224,292
[2.378314722 e-25 kg]
568,584
[23.526 GeV]

Praseodymium

59


3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
59
f d p s p d f

59 [Potons [24-12] Neutrons [18-18] electrons [0-12]] n1-6

Lanthanoid

electron configuration

[Xe] 4f3 6s2
54

Aufbau


Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
1 1
3 2 2 3
2
8
21
18
8
2
f d p s p d f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.59 - Praseodymium atom

Copyright ABRAHAM [2008] - All rights reserved


5,040
[2,520-2,520]
Nd
145.7335
3,280,752
[2.419960965 e-25 kg]
580,032
[23.999 GeV]
Neodymium
60
R
Q
P
O
N
M
L
K
3 2 1 0 1 2 3
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
60 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-6
Lanthanoid
electron configuration
[Xe] 4f4 6s2
54
Aufbau
Azmithal & Magnetic numbers
2
8
22
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.60 - Neodymium atom


5,124
[2,562-2,562]
Pm
148.2415
3,337,212
[2.461607208 e-25 kg]
591,480
[24.473 GeV]
Pm

electron configuration

[Xe] 4f5 6s2
54

Promethium

61


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
61
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f

61 [Potons [24-12] Neutrons [18-18] eectrons [0-12]] m1-6

Lanthanoid

Aufbau


Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
0
1
1
2
8
23
18
8
2
3
2
2
3
+1
0
-1
-1
0
+1
-1
-2
-3
+2
+1
0
-1
-2
-2
-1
0
+1
+2
-3
-2
5
3
1
2
4
9
7
5
3
1
2
4
6
8
10
5
3
1
2
4
6
1
2
f
d
p
s
p
d
f
8
7
6
5
4
3
2
1
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.61 - Promethium atom


5,208
[2,604-2,604]
Sm
150.7495
3,393,672
[2.503253452 e-25 kg]
602,928
[24.947 GeV]
Samarium
62
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
62
f d p s p d f
electron configuration
[Xe] 4f6 6s2
54
Aufbau
62 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Lanthanoid
Azmithal & Magnetic numbers
0
1 1
+1 0 -1 -1 0 +1
3 2 2 3
-1 -2 -3 +2 +1 0 -1 -2 -2 -1 0 +1 +2 -3 -2 -1
2
8
24
18
8
2
5 3 1 2 4 6
9 7 5 3 1 2 4 6 8 10
5 3 1 2 4 6
1 2
f d p s p d f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.62 - Samarium atom


5,292
[2,646-2,646]
Eu
153.2575
3,450,132
[2.544899695 e-25 kg]
614,376
[25.421 GeV]
Europium
63
3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
M
KE
8 7 6 5 4 3 2 1
f d p s p d f
electron configuration
Aufbau
[Xe] 4f7 6s2
54
63 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Lanthanoid
Azmithal & Magnetic numbers
2
8
25
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.63 - Europium atom


5,376
[2,688-2,688]
Gd
155.7655
3,506,592
[2.586545938 e-25 kg]
625,824
[25.894 GeV]
Gadolinium
64
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
[Xe] 4f8 6s2
54
Aufbau
64 [Potons [24-12] Neutrons [18-18] electrons [0-12]] n1-6
Lanthanoid
Azmithal & Magnetic numbers
2
8
26
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.64 - Gadolinium atom


5,460
[2,730-2,730]
Tb
158.2735
3,563,052
[2.628192182 e-25 kg]
637,272
[26.368 GeV]
Terbium
65
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
[Xe] 4f9 6s2
54
65 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Lanthanoid
Aufbau
Azmithal & Magnetic numbers
0
2
8
27
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.65 -Terbium atom

Copyright ABRAHAM [2008] - All rights reserved


5,544
[2,772-2,772]
Dy
160.7815
3,619,512
[2.669838425 e-25 kg]
648,720
[26.842 GeV]
Dysprosium
66
Q
RE
M
KE
66
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
f d p s p d f
66 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Lanthanoid
electron configuration
[Xe] 4f10 6s2
54
Aufbau
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
2
8
28
18
8
2
f d p s p d f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.66 - Dysprosium atom


5,628
[2,814-2,814]
Ho
163.2895
1
3
9
9
1
3
11
Ho
7
5
7
5
5
4
6
1
1
2
2
3
6
6
6
6
8
4
2
10
10
4
2
3,675,972
[2.711484668 e-25 kg]
660,168
[27.316 GeV]

Holmium

67


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
67
f
d
p
s
p
d
f

Aufbau

electron configuration

[Xe] 4f11 6s2

54

67 [Protons [24-12]
Neutrons [18-18]
electrons [0-12]] m1-6

Lanthanoid


Azmithal & Magnetic numbers
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
0
1
1
2
2
3
3
2
8
29
18
8
2
f
f
d
d
p
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.67 - Holmium atom

Copyright ABRAHAM [2008] - All rights reserved


5,712
[2,856-2,856]
Er
165.7974
3,732,432
[2.753130912 e-25 kg]
671,616
[27.789 GeV]
Erbium
68
R
Q
P
O
N
M
L
K
3 2 1 0 1 2 3
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
[Xe] 4f12 6s2
54
68 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Lanthanoid
Aufbau
Azmithal & Magnetic numbers
0
1 1
2 2 3 3
2
8
30
18
8
2
f d p s p d f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.68 - Erbium atom

Copyright ABRAHAM [2008] - All rights reserved


5,796
[2,898-2,898]
Tm
168.3054
3,788,892
[2.794777155 e-25 kg]
683,064
[28.263 GeV]
Thulium
69
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
[Xe] 4f13 6s2
54
Aufbau
69
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-6
Lanthanoid
Azmithal & Magnetic numbers
0
1
2
3
2
8
31
18
8
2
f
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.69 - Thulium atom

Copyright ABRAHAM [2008] - All rights reserved


5,880
[2,940-2,940]
Yb
170.8134
3,845,352
[2.836423398 e-25 kg]
694,512
[28.737 GeV]
Ytterbium
70
electron configuration
[Xe] 4f14 6s2
54
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
70 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Lanthanoid
Azmithal & Magnetic numbers
0
2
8
32
18
8
2
f
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.70 - Ytterbium atom


5,964
[2,982-2,982]
Lu
173.5037
3,905,916
[2.881096850 e-25 kg]
710,064
[29.380 GeV]
Lutetium
71
3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
f d p s p d f
electron configuration
[Xe] 4f14 5d1 6s2
54
Aufbau
71 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Lanthanoid
Azmithal & Magnetic numbers
0
2
9
32
18
8
2
s
p
d
f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.71 - Lutetium atom


6,048
[3,024-3,024]
Hf
176.1940
3,966,480
[2.925770302 e-25 kg]
725,616
[30.024 GeV]
Hafnium
72
electron configuration
[Xe] 4f14 5d2 6s2
54
3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
M
KE
8 7 6 5 4 3 2 1
f d p s p d f
72
72 Protons [24-12] Neutrons [18-18] electrons [0-12] m1-6
Transition Metal
Aufbau
Azmithal & Magnetic numbers
0
2
10
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.72 - Hafnium atom

Copyright ABRAHAM [2008] - All rights reserved


6,132
[3,066-3,066]
Ta
178.8843
4,027,044
[2.970443753 e-25 kg]
741,168
[30.667 GeV]

Tantalum

73


3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
73
f d p s p d f

electron configuration

[Xe] 4f14 5d3 6s2
54

73 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6

Transition Metal

Aufbau


Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
2
11
32
18
8
2
1
3
2
f
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.73 - Tantalum atom


6,216
[3,108-3,108]
W
181.5746
4,087,608
[3.015117205 e-25 kg]
756,720
[31.311 GeV]

Tungsten

74


3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
74
f d p s p d f

electron configuration

[Xe] 4f14 5d4 6s2
54

74 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6

Transition Metal

Aufbau


Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
1
1
2
2
3
3
2
12
32
18
8
2
f
f
d
d
p
p
s
atomic shell
energy level
Orbitals & sub-orbitals


6,300
[3,150-3,150]
Re
184.2849
4,148,172
[3.059790657 e-25 kg]
772,272
[31.954 GeV]
Rhenium
75
R
Q
P
O
N
M
L
K
Q
RE
M
KE
8
7
6
5
4
3
2
1
3
2
1
0
1
2
3
f
d
p
s
p
d
f
75 Protons [24-12] Neutrons [18-18] electrons [0-12] m1-6
Transition Metal
electron configuration
[Xe] 4f14 5d5 6s2
54
Aufbau
Azmithal & Magnetic numbers
2
13
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.75 - Rhenium atom

Copyright ABRAHAM [2008] - All rights reserved


6,384
[3,192-3,192]
Os
188.9552
4,208,736
[3.104464108 e-25 kg]
787,824
[32.598 GeV]
electron configuration
[Xe] 4f14 5d6 6s2
54
Aufbau
Osmium
76
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
f d p s p d f
Q
RE
M
KE
76 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Transition Metal
Azmithal & Magnetic numbers
2
14
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.76 - Osmium atom

Copyright ABRAHAM [2008] - All rights reserved


6,468
[3.234-3.234]
Ir
189.6455
4,269,300
[3.149137560 e-25 kg]
803,376
[33.241 GeV]
Iridium
77
electron configuration
[Xe] 4f14 5d7 6s2
54
Aufbau
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
Q
RE
M
KE
77
f d p s p d f
77
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-6
Transition Metal
Azmithal & Magnetic numbers
0
2
15
32
18
8
2
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
13 11 9 7 5 3 1
2 4 6 8 10 12 14
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 2
s p d f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.77 - Iridium atom

Copyright ABRAHAM [2008] - All rights reserved


6,552
[3,276-3,276]
Pt
192.3358
4,329,864
[3.19381012 e-25 kg]
818,928
[33.884 GeV]
Platinum
78
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
3 2 1 0 1 2 3
f d p s p d f
electron configuration
Aufbau
[Xe] 4f14 5d8 6s2
54
78 [Potons [24-12] Neutrons [18-18] electrons [0-12]] n1-6
Transition Metal
Azmithal & Magnetic numbers
0
2
16
32
18
8
2
s
p
d
f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.78 - Platinum atom


6,636
[3.318-3.318]
Au
195.0281
4,390,428
[3.238484463 e-25 kg]
834,480
[34.528 GeV]
electron configuration
[Xe] 4f14 5d9 6s2
54
Aufbau
Gold
79
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
79
f d p s p d f
79 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Post Transition Metal
Azmithal & Magnetic numbers
2
17
32
18
8
2
f
d
p
s
Orbitals & sub-orbitals
atomic shell
energy level

Tetryonics 51.79 - Gold atom



6,720
[3,360-3,360]
Hg
197.7164
4,450,992
[3.283157915 e-25 kg]
850,032
[35.171 GeV]
Mercury
80
electron configuration
[Xe] 4f14 5d10 6s2
54
Aufbau
3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
M
KE
8 7 6 5 4 3 2 1
f d p s p d f
80 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-6
Post Transition Metal
Azmithal & Magnetic numbers
2
18
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.80 - Mercury atom

Copyright ABRAHAM [2008] - All rights reserved


6,804
[3,402-3,402]
Tl
200.5954
Tl
4,515,804
[3.330964793 e-25 kg]
869,832
[35.991 GeV]

Thallium

81


3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
81
f d p s p d f

81 [Protons [24-12] / Neutrons [18-18] / electrons [0-12]] n1-6

Metaloid

electron configuration

Aufbau

[Xe] 4f14 5d10 6s2 6p1
54


Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
3
18
32
18
8
2
3 2 1 1 2 3
f d p s p d f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.81 - Thallium atom

Copyright ABRAHAM [2008] - All rights reserved


6,888
[3.444-3.444]
Pb
203.4744
4,580,616
[3.37877167l e-25 kg]
889,632
[36.810 GeV]
electron configuration
Aufbau
[Xe] 4f14 5d10 6s2 6p2
54
Lead
82
3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
8
7
6
5
4
3
2
1
f d p s p d f
82
82
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-6
Metaloid
Azmithal & Magnetic numbers
0
4
18
32
18
8
2
f
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.82 - Lead atom

Copyright ABRAHAM [2008] - All rights reserved


6,972
[3,486-3,486]
Bi
208.3534
4,624,188
[3.426578549 e-25 kg]
909,432
[37.269 GeV]
Bismuth
83
3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
M
KE
8 7 6 5 4 3 2 1
f d p s p d f
83
83 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Metaloid
electron configuration
[Xe] 4f14 5d10 6s2 6p3
54
Aufbau
Azmithal & Magnetic numbers
5
18
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.83 - Bismuth atom

Copyright ABRAHAM [2008] - All rights reserved


7,056
[3,528-3,528]
Po
209.2324
4,710,240
[3.474385426 e-25 kg]
929,232
[38.449 GeV]
Polonium
84
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
f
d
p
s
p
d
f
electron configuration
Aufbau
[Xe] 4f14 5d10 6s2 6p4
54
84
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-6
Metaloid
Azmithal & Magnetic numbers
6
18
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.84 - Polonium atom


7,140
[3.570-3.570]
At
212.1114
4,775,052
[3.522192304 e-25 kg]
949,032
[39.268 GeV]
Astatine
85
electron configuration
Aufbau
[Xe] 4f14 5d10 6s2 6p5
54
Q
RE
M
KE
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
f d p s p d f
85 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Halogen
Azmithal & Magnetic numbers
7
18
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.85 - Astatine atom


7,224
[3,612-3,612]
Rn
214.9904
4,839,864
[3.569999182 e-25 kg]
968,832
[40.087 GeV]
Radon
86
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3 2 1 0 1 2 3
Q
RE
M
KE
f d p s p d f
electron configuration
Aufbau
[Xe] 4f14 5d10 6s2 6p6
54
86 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-6
Noble Gas
Azmithal & Magnetic numbers
Orbitals & sub-orbitals
atomic shell
energy level
8
18
32
18
8
2

Tetryonics 51.86 - Radon atom


7,308
[3,654-3,654]
Fr
218.0845
4,909,068
[3.621045704 e-25 kg]
993,024
[41.088 GeV]
Francium
87
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
[Rn] 7s1
86
Aufbau
87
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-7
Alkali
Metal
Azmithal & Magnetic numbers
1
8
18
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.87 - Francium atom


7,392
[3,696-3,696]
Ra
221.1386
4,978,272
[3.672392226 e-25 kg]
1,017,216
[42.089 GeV]
Radium
88
3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
M
KE
8 7 6 5 4 3 2 1
f d p s p d f
electron configuration
[Rn] 7s2
86
88
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-7
Alkaline Earth
Aufbau
Azmithal & Magnetic numbers
0
1
2
3
2
8
18
32
18
8
2
f
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.88 - Radium atom


7,476
[3.738-3.738]
Ac
223.8289
5,038,836
[3.716765677 e-25 kg]
1,032,768
[42.732 GeV]
Actinium
89
R
Q
P
O
N
M
L
K
Q
RE
M
KE
8
7
6
5
4
3
2
1
f
d
p
s
p
d
f
electron configuration
[Rn] 5f1 7s2
86
89
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-7
Actinoid
Aufbau
Amzithal & Magnetic numbers
2
8
19
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.89 - Actinium atom


7,560
[3.780-3.780]
Th
226.5192
5,099,400
[3.761439129 e-25 kg]
1,048,320
[43.376 GeV]
Thorium
90
R
Q
P
O
N
M
L
K
3 2 1 0 1 2 3
Q
RE
M
KE
90
8
7
6
5
4
3
2
1
f d p s p d f
electron configuration
[Rn] 5f2 7s2
86
90 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Actinoid
Aufbau
Azmithal & Magnetic numbers
0
2
8
20
32
18
8
2
f
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.90 - Thorium atom



Protactinium

91

Pa 229.2095

7,644 [3,822-3,822]

5,159,964 [3.806112581 e-25 kg]

1,063,872 [44.019 GeV]

Aufbau

electron configuration

[Rn] 5f3 7s2

86

91 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7

Actinoid

3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
Azmithal & Magnetic numbers
2
8
21
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.91 - Protactinium atom


7,728
[3,864-3,864]
U
231.8998
5,220,528
[3.850786032 e-25 kg]
1,079,424
[14.663 GeV]
electron configuration
Uranium
92
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
92
f d p s p d f
92 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Actinoid
Aufbau
[Rn] 5f4 7s2
86
Azmithal & Magnetic numbers
0
1
2
3
2
8
22
32
18
8
2
f
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.92 - Uranium atom


7,812
[3,906-3,906]
Np
234.5901
5,281,092
[3.895459484 e-25 kg]
1,094,976
[45.306 GeV]
Neptunium
93
R
Q
P
O
N
M
L
K
3 2 1 0 1 2 3
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
Aufbau
[Rn] 5f5 7s2
86
93 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Actinoid
Azmithal & Magnetic numbers
0
2
8
23
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals
s
p
d
f

Tetryonics 51.93 - Neptunium atom

Copyright ABRAHAM [2008] - All rights reserved


7,896
[3,948-3,948]
Pu
237.2804
5,341,656
[3.940132936 e-25 kg]
1,110,528
[45.950 GeV]
Plutonium
94
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
Q
RE
M
KE
f d p s p d f
electron configuration
Aufbau
[Rn] 5f6 7s2
86
94 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Actinoid
Azmithal & Magnetic numbers
2
8
24
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.94 - Plutonium atom

Copyright ABRAHAM [2008] - All rights reserved


7,980
[3,990-3,990]
Am
239.9707
Am
5,402,220
[3.984806387 e-25 kg]
1,126,080
[46.593 GeV]
Americium
95
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
95
f d p s p d f
electron configuration
[Rn] 5f7 7s2
86
Aufbau
95
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-7
Actinoid
Azmithal & Magnetic numbers
0
1
1
2
2
3
3
2
8
25
32
18
8
2
f
d
p
s
p
d
f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.95 - Americium atom


8,064
[4,032-4,032]
Cm
242.6810
5,462,784
[4.029479839 e-25 kg]
1,141,632
[47.237 GeV]
Curium
96
3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
M
KE
8 7 6 5 4 3 2 1
f d p s p d f
electron configuration
Aufbau
[Rn] 5f8 7s2
86
96 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-7
Actinoid
Azmithal & Magnetic numbers
2
8
26
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.96 - Curium atom


8,148
[4.074-4.074]
Bk
245.3513
5,523,348
[4.07415329I e-25 kg]
1,157,184
[47.880 GeV]
Berkelium
97
R
Q
P
O
N
M
L
K
3
2
1
0
1
2
3
8
7
6
5
4
3
2
1
Q
RE
M
KE
f
d
p
s
p
d
f
electron configuration
Aufbau
[Rn] 5f9 7s2
86
97
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-7
Actinoid
Azmithal & Magnetic numbers
2
8
27
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.97 - Berkelium atom

Copyright ABRAHAM [2008] - All rights reserved


8,232
[4,116-4,116]
Cf
248.0416
5,583,912
[4.118826742 e-25 kg]
1,172,736
[48.524 GeV]
Californium
98
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
Aufbau
[Rn] 5f10 7s2
86
98 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Actinoid
Azimuthal & Magnetic numbers
0
2
8
28
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals
s
p
d
f

Tetryonics 51.98 - Californium atom


8,316
[4.158-4.158]
Es
250.7319
5,644,476
[4.163500194 e-25 kg]
1,188,288
[49.167 GeV]
Einsteinium
99
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
99
f d p s p d f
electron configuration
Aufbau
[Rn] 5f11 7s2
86
99
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-7
Actinoid
Azmithal & Magnetic numbers
0
1
1
3
2
2
3
+1 0 -1
-1 0 +1
+2 +1 0 -1 -2 -3 +2 +1 0 -1 -2
-2 -1 0 +1 +2 -3 -2 -1 0 +1
+3
+2 +3
2
8
29
32
18
8
2
13 11 9 7 5 3 1
2 4 6 8 10 12 14
f
f
9 7 5 3 1
2 4 6 8 10
d
d
5 3 1
2 4 6
p
p
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.99 - Einsteinium atom

Copyright ABRAHAM [2008] - All rights reserved


8,400
[4,200-4,200]
Fm
253.4222
5,705,040
[4.208173646 e-25 kg]
1,203,840
[49.811 GeV]

Fermium

100


3
2
1
0
1
2
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
100
f
d
p
s
p
d
f

electron configuration

Aufbau

[Rn] 5f12 7s2
86

100 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7

Actinoid


Azmithal & Magnetic numbers
0
1
1
2
2
3
3
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
2
8
30
32
18
8
2
f
f
d
d
p
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.100 - Fermium atom

Copyright ABRAHAM [2008] - All rights reserved


8,484
[4,242-4,242]
Md
256.1125
5,765,604
[4.252847097 e-25 kg]
1,219,392
[50.454 GeV]
Mendelevium
101
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
Aufbau
[Rn] 5f13 7s2
86
101 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Actinoid
Azmithal & Magnetic numbers
0
1
1
2
3
2
3
2
8
31
32
18
8
2
f
d
p
s
p
d
f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.101 - Mendelevium atom


8,568
[4,284-4,284]
No
258.8028
5,826,168
[4.297520549 e-25 kg]
1,234,944
[51.098 GeV]
Nobelium
102
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
f d p s p d f
Q
RE
M
KE
electron configuration
[Rn] 5f14 7s2
86
Aufbau
102 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Actinoid
Azmithal & Magnetic numbers
0 1 1 2 2 3 3
2 8 32 32 18 8 2
+3 +2 +1 0 -1 -2 -3
f d p s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.102 - Nobelium atom


8,652
[4.326-4.326]
Lr
281.6818
5,890,980
[4.345327427 e-25 kg]
1,254,744
[51.917 GeV]
Lawrencium
103
R
Q
P
O
N
M
L
K
3
2
1
0
1
2
3
8
7
6
5
4
3
2
1
Q
RE
M
KE
103
f
d
p
s
p
d
f
electron configuration
Aufbau
[Rn] 5f14 6d1 7s2
86
103
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
n1-7
Actinoid
Azmithal & Magnetic numbers
0
2
9
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.103 - Lawrencium atom


8,736
[4.368-4.368]
Rf
264.5608
5,955,792
[4.393134305 e-25 kg]
1,274,544
[52.736 GeV]
Rutherfordium
104
electron configuration
Aufbau
[Rn] 5f14 6d2 7s2
86
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
104
f d p s p d f
104 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-7
Transition Metal
Azmithal & Magnetic numbers
2
10
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.104 - Rutherfordium atom


8,820
[4,410-4,410]
Db
287.4398
6,020,604
[4.44094182 e-25 kg]
1,294,344
[53.556 GeV]
Dubnium
105
R
Q
P
O
N
M
L
K
Q
RE
M
KE
8
7
6
5
4
3
2
1
3
2
1
0
1
2
3
f
d
p
s
p
d
f
105 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Transition Metal
electron configuration
Aufbau
[Rn] 5f14 6d3 7s2
86
Azmithal & Magnetic numbers
2
11
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.105 - Dubnium atom

Copyright ABRAHAM [2008] - All rights reserved


8,904
[4,452-4,452]
Sg
270.3188
6,085,416
[4.488748060 e-25 kg]
1,314,144
[54.375 GeV]
Seaborgium
106
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
Q
RE
M
KE
106
f
d
p
s
p
d
f
electron configuration
Aufbau
[Rn] 5f14 6d4 7s2
86
106
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-7
Transition Metal
Azmithal & Magnetic numbers
2
12
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.106 - Seaborgium atom

Copyright ABRAHAM [2008] - All rights reserved


8,988
[4.494-4.494]
Bh
273.1978
6,150,228
[4.536554938 e-25 kg]
1,333,944
[55.194 GeV]

Bohrium

107


3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
107
f d p s p d f

electron configuration

Aufbau

[Rn] 5f14 6d5 7s2
86

107 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7

Transition Metal


Azmithal & Magnetic numbers
R Q P O N M L K
8 7 6 5 4 3 2 1
0
2
13
32
32
18
8
2
3 2 1 1 2 3
f d p s p d f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.107 - Bohrium atom


9,072
[4.536-4.563]
Hs
276.0768
6,215,040
[4.584361816 e-25 kg]
1,353,744
[56.013 GeV]
Hassium
108
3 2 1 0 1 2 3
R
Q
P
O
N
M
L
K
Q
RE
M
KE
8
7
6
5
4
3
2
1
f d p s p d f
electron configuration
Aufbau
[Rn] 5f14 6d6 7s2
86
108 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Transition Metal
Azmithal & Magnetic numbers
2
14
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.108 - Hassium atom


9,156
[4.578-4.578]
Mt
278.9558
6,279,852
[4.632168604 e-25 kg]
1,373,544
[56.833 GeV]
Meitnerium
109
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
f d p s p d f
Q
RE
M
KE
electron configuration
Aufbau
[Rn] 5f14 6d7 7s2
86
109 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-7
Transition Metal
Azmithal & Magnetic numbers
2 15 32 32 18 8 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.109 - Meitnerium atom

Copyright ABRAHAM [2008] - All rights reserved


9,240
[4,620-4,620]
Ds
281.8348
6,344,664
[4.679975572 e-25 kg]
1,393,344
[57.652 GeV]
Darmstadtium
110
Q
RE
M
KE
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
f d p s p d f
electron configuration
Aufbau
[Rn] 5f14 6d8 7s2
86
110
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-7
Transition Metal
Azmithal & Magnetic numbers
2
16
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.110 - Darmstadtium atom


9,324
[4,662-4,662]
Rg
284.7138
6,409,476
[4.727782449 e-25 kg]
1,413,144
[58.471 GeV]
Roetgenium
111
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
111
Protons [24-12]
Neutrons [18-18]
electrons [0-12]
m1-7
Post Transition Metal
electron configuration
Aufbau
[Rn] 5f14 6d9 7s2
86
Azmithal & Magnetic numbers
0
2
17
32
32
18
8
2
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
13 11 9 7 5 3 1
2 4 6 8 10 12 14
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 2
f
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.111 - Roetgenium atom


9,408
[4,704-4,704]
Cn
287.5928
6,474,288
[4.775589327 e-25 kg]
1,432,944
[59.290 GeV]
Copernicium
112
R Q P O N M L K
Q
RE
M
KE
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
f d p s p d f
electron configuration
Aufbau
[Rn] 5f14 6d10 7s2
86
112 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-7
Post transition Metal
Azmithal & Magnetic numbers
0
2 1 1 2
3 3
+3 +2 +1 0 -1 -2 -3
+2 +1 0 -1 -2
+1 0 -1
2 18 32 32 18 8 2
13 11 9 7 5 3 1
2 4 6 8 10 12 14
9 7 5 3 1
2 4 6 8 10
5 3 1
2 4 6
1 2
f d p s p d f
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.112 - Copernicium atom


9,492
[4,746-4,746]
Uut
290.6669
6,543,492
[4.826535849 e-25 kg]
1,457,136
[60.292 GeV]
electron configuration
Ununtrium
113
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
113
f d p s p d f
113 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-7
Metaloid
Aufbau
[Rn] 5f14 6d10 7s2 7p1
86
Azmithal & Magnetic numbers
0
1 1
2 2
3 3
3
18
32
32
18
8
2
f f
d d
p p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.113 - Ununtrium atom

Copyright ABRAHAM [2008] - All rights reserved


9,576
[4,788-4,788]
Fl
293.7409
6,612,696
[4.877682371 e-25 kg]
1,481,328
[61.293 GeV]
Flerovium
114
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
Q
RE
M
KE
f d p s p d f
electron configuration
Aufbau
[Rn] 5f14 6d10 7s2 7p2
86
114 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Metaloid
Azmithal & Magnetic numbers
4
18
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.114 - Flerovium atom


9,660
[4,830-4,830]
Uup
296.8150
Uup
6,681,900
[4.9287288893 e-25 kg]
1,505,520
[62.294 GeV]
electron configuration
Ununpentium
115
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
115
f d p s p d f
115 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-7
Metaloid
Aufbau
[Rn] 5f14 6d10 7s2 7p3
86
Azmithal & Magnetic numbers
5
18
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.115 - Ununpentium atom


9,744
[4,872-4,872]
Uuh
289.8891
Lv
6,751,104
[4.979775415 e-25 kg]
1,529,712
[63.295 GeV]
electron configuration
Livermorium
116
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
116
f d p s p d f
Aufbau
[Rn] 5f14 6d10 7s2 7p4
86
116 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-7
Metaloid
Azmithal & Magnetic numbers
1 0 1
0 -1 -1 0
2 2
+2 +1 0 -1 -2 +1 +1 -2 -1 0 +1 +2
3 3
+3 +2 +1 0 -1 -2 -3 -3 -2 -1 0 +1 +2 +3
6
18
32
32
18
8
2
13 11 9 7 5 3 1 2 4 6 8 10 12 14
f f
9 7 5 3 1 2 4 6 8 10
d d
5 3 1 2 4 6
p p
1 s 2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.116 - Livermorium atom


9,828
[4.914-4.914]
Uus
302.9832
6,820,308
[5.030821937 e-25 kg]
1,553,904
[64.296 GeV]
Ununseptium
117
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
Q
RE
M
KE
f d p s p d f
electron configuration
Aufbau
[Rn] 5f14 6d10 7s2 7p5
86
117 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Halogen
Azmithal & Magnetic numbers
7
18
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.117 - Ununseptium atom

Copyright ABRAHAM [2008] - All rights reserved


9,912
[4.956-4.956]
Uuo
308.0373
6,889,512
[5.081868459 e-25 kg]
1,578,096
[65.297 GeV]
Uuo
Ununoctium
118
R Q P O N M L K
8 7 6 5 4 3 2 1
3 2 1 0 1 2 3
f d p s p d f
Q
RE
M
KE
electron configuration
Aufbau
[Rn] 5f14 6d10 7s2 7p6
86
118 [Protons [24-12] Neutrons [18-18] electrons [0-12]] m1-7
Noble Gas
Azmithal & Magnetic numbers
8
18
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.118 - Ununoctium atom

Copyright ABRAHAM [2008] - All rights reserved


9,996
[4,998-4,998]
Uun
309.3129
Uun
6,963,252
[5.136260842 e-25 kg]
1,606,824
[66.486 GeV]
Ununnenium
119
3 2 1 0 1 2 3
R Q P O N M L K
Q
RE
M
KE
119
8 7 6 5 4 3 2 1
f d p s p d f
electron configuration
Aufbau
[Uuo] 8s1
118
Azmithal & Magnetic numbers
0
1
8
18
32
32
18
8
2
119 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-8
Alkali Metal
f
d
p
s
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.119 - Ununnenium atom

Copyright ABRAHAM [2008] - All rights reserved


10,080
[5,040-5,040]
Ub
312.5885
7,036,992
[5.490653044 e-25 kg]
1,635,552
[67.675 GeV]
Unbinilium
120
R
Q
P
O
N
M
L
K
3 2 1 0 1 2 3
Q
RE
M
KE
8 7 6 5 4 3 2 1
f d p s p d f
electron configuration
Aufbau
[Uuo] 8s2
118
Azmithal & Magnetic numbers
120 [Protons [24-12] Neutrons [18-18] electrons [0-12]] n1-8
Alkaline Earth
2
8
18
32
32
18
8
2
atomic shell
energy level
Orbitals & sub-orbitals

Tetryonics 51.120 - Unbinilium atom


Atomic shell
Energy level
K 2 1
L 8 2
M 18 3
N 32 4
O 32 5
P 18 6
Q 8 7
R 2 8
electron configuration
Periodic
Elements
H
D 1
He 2
Li 3
Be 4
B 5
C 6
N 7
O 8
F 9
Ne 10
Na 11
Mg 12
Al 13
Si 14
P 15
S 16
Cl 17
Ar 18
K 19
Ca 20
Sc 21
Ti 22
V 23
Cr 24
Mn 25
Fe 26
Co 27
Ni 28
Cu 29
Zn 30
Ga 31
Ge 32
As 33
Se 34
Br 35
Kr 36
Rb 37
Sr 38
Y 39
Zr 40
Nb 41
Mo 42
Tc 43
Ru 44
Rh 45
Pd 46
Ag 47
Cd 48
In 49
Sn 50
Sb 51
Te 52
I 53
Xe 54
Cs 55
Ba 56
La 57
Ce 58
Pr 59
Nd 60
Pm 61
Sm 62
Eu 63
Gd 64
Tb 65
Dy 66
Ho 67
Er 68
Tm 69
Yb 70
Lu 71
Hf 72
Ta 73
W 74
Re 75
Os 76
Ir 77
Pt 78
Hg 79
Au 80
Tl 81
Pb 82
Bi 83
Po 84
At 85
Rn 86
Fr 87
Ra 88
Ac 89
Th 90
Pa 91
U 92
Np 93
Pu 94
Am 95
Cm 96
Bk 97
Cf 98
Es 99
Fm 100
Md 101
No 102
Lr 103
Rf 104
Db 105
Sg 106
Bh 107
Hs 108
Mt 109
Ds 110
Rg 111
Cn 112
Uut 113
Fl 114
Uup 115
Lv 116
Uus 117
Uuo 118
Uun 119
Uub 120
Z
D nuclei

Tetryonics 52.01 - Tetryonic Element Table

Copyright ABRAHAM [2008] - All rights reserved


PERIODIC
ELEMENTS
13 Md 13 Tm
1 Ac 1 La
3 Pa 3 Pr
Rg Au 9 Ag Cu 9
Lr Lu 1 Y Sc 1
Db Ta 3 Nb V 3
9 Bk 9 Tb
11 Es 11 Ho
Mt Ir 7 Rh Co 7
Bh Re 5 Tc Mn 5
7 Am 7 Eu
5 Np 5 Pm
At I Uus 5 Br F Cl 5
1 Cs Rb Fr D 1 K Uun Li Na
4 Po Te Lv 4 Se O S
1 Tl In Uut 1 Ga B Al
Pb Sn Fl 2 Ge C Si 2
Ba Sr Ra He 2 Ca Ub Be Mg 2
Bi Sb Uup 3 As N P 3
Rn Xe Uuo 6 Kr Ne Ar 6
Pu 6 Sm 6
Cm 8 Gd 8
6 Hs Os 6 Ru Fe
8 Ds Pt 8 Pd Ni
12 Fm 12 Er
10 Cf 10 Dy
Sg W 4 Mo Cr 4
2 Rf Hf 2 Zr Ti
10 Cn Hg 10 Cd Zn
4 U 4 Nd
2 Th 2 Ce
No 14 Yb 14

Tetryonics 52.02 - Periodic Table [Elements]

Response to an analysis of Tetryonic Chemistry by Robert J Brotherus [July 2015]

In reply to a paper outlining Mr Robert Brotherus' examination and *mis*-understanding of Tetryonic theory and in particular how it applies to the modern understanding of Chemistry as it currently taught…..

Point by point I'll firstly address the particular points of concern raised wrt modern chemical theory and physics in general:

Tetryonics paper on quantum chemistry is very scarce on making any predictions about atomic properties or comparing such predictions to experimental results.

Tetryonic theory provides many predictions regarding the physical 2d planar **geometrie**s of bosons [radiant mass-energies] and the 3D material **Topologies** of Fermions [Matter and their associated physical properties]. Inclusive in these are many predictions and repeated statements and illustrations of specific particle shapes and the values of mass-energy momenta attributed to each… as well as how these values stem from the equilateral tessellation of Planck energy momenta and why they differ from the established values of modern scientific theory….

In many cases there are similarities to be found with existing observations but where Tetryonic theory differs from modern theory it is not by choice but rather dictated by the equilateral mass-energies within charged Matter topologies themselves and all too often led to much effort in order to reconcile the differences, leading to further insights and extensions of the theory over time…. Where differences exist it is deliberate not by error.


The quantum building blocks of Everything
[mass - ENERGY - Matter]
and the forces of motion
Fermions
photons
bosons
forces
Gravity
strong
weak
EM
E
ε₀
+
N
S
μ₀
a positive charge
Planck quantum of equilateral
mass-energy momenta
E
ε₀
−
S
N
μ₀
a negative charge
Planck quantum of equilateral
mass-energy momenta
our Universe is a dynamic energy system
eternally seeking charge equilibrium
opposite sides of the same quantum quoin
the energy currency of nature

Tetryonics is a BOTTOM-UP physical theory that unifies many currently disparate theories of science into a coherent unified model of the same – but not without its own set of mental challenges to those who are first becoming acquainted with it. As such it must be recognised that Tetryonic theory should not be studied without a sound understanding of the foundation upon with it is built…. Many have approached analysis of my work in such a way only to find that their analysis was limited by modern science's lack of precise detail of the foundations of the physics that they attempt to explain [to wit modern theory is a top-down explanation of the science build up over many generations with an equal number of varying interpretations and assumptions]

Tetryonics plays down importance of "mathematics" and instead emphasizes "geometry".

Arguably I place a lot of emphasis on geometry over that of mathematics in Tetryonic theory, but only so as it offers insights into physical theory that maths alone has not been able to provide since its wholesale incorporation into the science in the 1600’s. This is not to downplay the importance and productiveness that maths has provided us a scientific tool, but rather to ‘illustrate’ and draw attention to the advances that a purely geometric model has to offer us in advancing our understanding of the same…. To wit, Tetryonic geometries are based on the postulate that all physical theory is founded on equilateral Planck quanta of energy momenta and as such these physical entities afford no room for speculative ideas or mathematical manipulations beyond what is physically possible to be constructed.





To help elucidate my work and thoughts on the differentiation of 2d planar mass-energy geometries from 3D Material topologies I recorded a detailed YouTube video titled “Tetryonics 101” where I show HOW to use the existing Tetryonic templates [of Planck mass-energy momenta] to construct all the fields [boson & photons] of the Standard model along with the 3D Mater topologies of all the known fermions [and them some]… I do hope you’ll take the time to review this detailed instruction on the creation of quantum fields and Matter and try to replicate them same yourself – it is THE most informative thing students of Tetryonics and science in general can do when trying to increase their understanding of the hitherto unseen constituents that make up quantum theory and our macro-scale Universe and the laws of Nature we observe….

Tetryonics paper on physical chemistry is scarce on such numerical predictions and where it does make such predictions they are often in contradiction to observed experimental facts.

In addition to the maths found within Tetryonic illustrations there are also many spreadsheets developed from those very same equations over time to provide the numerical detail found in the illustrations – particular wrt periodic elements and theory rest atomic masses and kinetic elements etc. – It is by no means exhaustive on every topic imaginable but they do address the information provided on particles & elements etc. along with their kinetic and relativistic energies of motion.

Tetryonic Problem: Missing hydrogen element

Hydrogen is not missing from Tetryonic theory – in fact it is extensively detailed and modelled in Tetryonics [1] – Quantum Mechanics eBook [again highlight the need not to jump into one's preferred field of expertise and study but rather learn Tetryonic theory as you would any modern physical theory in order of presentation]


48
H
1.0000
Hydrogen
22.512
KE
0
Hydrogen is NOT a periodic element
[Deuterium is the building block of elements]
electron configuration
1s1
Aufbau
5.107765145 e13
6.671366720 e13
9.078047137 e13
1.307587877 e14
2.043106058 e14
3.632188548 e14
8.172424234 e14
3.268969693 e15
13.525 eV
photo-electron
ionisation energy


elemental family geometry
electron configuration
Hydrogen is NOT a periodic table element
Hydrogen
Free Radical element
Baryonic energy levels determine photo-electron KEM field energies
accelerating photo-electrons produce spectral lines
Absorption
Emission
All electrons in elements have differing KEM field energies

Hydrogen is designated as element 00 in Tetryonic theory as it is **NOT** the building block of periodic elements as is currently understood but rather a sub-unit of Deuterium the real building block of all elements…. This is not an arbitrary decision but one forced on anybody who attempts to build physical models of all elements in order to match and explain many of the current established aspects of chemical and quantum theory wrt the quantum electrodynamics of elements themselves wrt molar mass, the Aufbau principle, Schrodinger and Bohr numbers for each element and how Deuterium nuclei [or any other] may bind together in order to form all the elements of the periodic table and their respective spectral emissions lines.

Attempting to build heavy elements utilising Z number Hydrogen nuclei as a foundation with the excess molar masses being accounted for by way of 'extra or excess' Neutrons [as is the established model of modern chemistry] runs into a number of problems immediately – namely:

The lack of residual strong Force binding points on nuclei to facilitate the binding of Neutrons to the nuclei in order to form the elements [particularly elements 60+]

The incorrectness of ‘reserve beta decay’ to explain and model Neutron particle formation and the mechanics of electron binding to periodic elements in accordance with Schrodinger’s wave equation and Bohr’s atomic model of the same in order to produce observed spectral line emissions of each element in the PT.

There is no uncertainty or indeterminacy in Tetryonic theory as there is in modern theory to explain away such inconsistencies between various aspects of physical theory – each attribute MUST be modelled and explained from first principles & invariably leads to new insights into quantum chemical theory that are at odds with established lines of thought.

To wit I stand by the claims and statements made in my eBooks :

> Each elemental nuclei is made from Deuterium" (p. 12)
> “120 elements in 8 quantum levels *and hydrogen as a free radical*.” (p. 26)
> “Deuterium (not hydrogen) is the building block of all elements." (p. 21)
> “Hydrogen is NOT a periodic element” (p. 83)



Proton - Neutron Curve

The graph below is a plot of neutron number against proton number. It is used as rule to determine which nuclei are stable or unstable.

Historically, Proton-electron numbers are viewed as being equivalent in neutral elementary matter with the excess molar mass measured being the result of ‘excess or extra’ Neutrons in the atom

Atomic Nuclei Numbers

All periodic elements have an EQUAL number of Protons, Neutrons & Electrons with their molar mass-Matter being determined by their quantum level mass-energies

Tetryonic modelling of the charged mass-ENERGY-Matter topologies of elementary atoms and the nuclei that comprise them, reveals a DIRECT LINEAR relationship for the number of Protons-electrons-Neutrons in all periodic elements and nuclear isotopes

Neutron Number [Z]
Proton Number [Z]
0
10
20
30
40
50
60
70
80
90
100
110
120
130
140
Plot of Baryon numbers based on excess Neutron model of periodic elements
stability line
unstable nuclides
Deviation from Tetryonic plot is the result of the intrinsic mass-energies of each particle comprising the atomic nucleus
E = mc²
Plot of Baryonic nuclei numbers based on Tetryonic topologies of periodic elements
Neutrons = Protons
Q
[v-v]
RE
NA
R
Q
P
O
N
M
L
K
atomic shells
2
8
18
32
32
18
8
2
Z
M0
KE
8
7
6
5
4
3
2
1
energy levels
f
d
p
s
p
d
f
+3
+2
+1
0
-1
-2
-3
orbitals

As it is the ONLY way to model and explain how all the periodic elements are created from equilateral Planck energy momenta that is in accord with the known observables… they are not in agreement with some aspects of established theory BUT they do closely mirror the observables and once KEM fields of thermal heat, kinetic motion etc. are taken into account provide a very accurate quantum model of chemical processes at the quantum scale.

Tetryonics does not throw all these facts out of the window just because hydrogen does not fit neatly into my [or other] pre-conceived set of boxes and triangles and hexagons, they are calculated from the Material models and immaterial fields associated with each element that MUST grow from first principles… not from assumptions elaborated upon over time.


Aufbau Principle
(Nuclei number and position)
s
p
d
f
1 Sub-Orbit (2 electrons max)
3 Sub-Orbits (6 electrons max)
5 Sub-Orbits (10 electrons max)
7 Sub-Orbits (14 electrons max)
R
Q
P
O
N
M
L
K
2
2+6
2+6+10
2+6+10+14
2+6+10+14
2+6+10
2+6
2
2
8
18
32
32
18
8
2
8
7
6
5
4
3
2
1
7 + 5 + 3 + 2 + 3 + 5 + 7
2
6
10
14

In fact the Aufbau table is shown in Tetryonic theory to be a table that has been ‘right justified’ to match the nomenclature of mathematics rather than the geometric topology of reality [which is centred about the principle quantum numbers and shells of Schrodinger and Bohr respectively]… it is only our skewed perspective of maths that prevents most from seeing the real symmetry present in atomic nuclei as detailed in the quantum numbers of Schrodinger’s wave equation for the same … ie there are no g,h,I,j, shells as supposed and all the quantum numbers of Schrodinger’s wave equations match the symmetric topology of elements as geometric portrayed in Tetryonics [and are in agreeance with Bohr’s shells and orbitals as well, thus unifying all 3 theories]


Planck mass-energy contributions to elementary Matter and isotopes
Z
The mass-energy content of Deuterium nuclei creates the molar mass of elements
[not extra neutrons in excess of the elemental number]
Schrodinger's quantum numbers
32
31
30
29
28
27
26
25
291,166
285,065
262,158
213,887
133,697
58,940
19,840
3,725
291,107 MeV
Elemental mass-Matter
[in MeV]
565.11 keV
KEM field mass energies
[in eV]
2 · 8 · 18 · 32 · 32 · 18 · 8 · 2
nuclei number per shell
RE
KE
Bohr's atomic orbitals
n1
Elementary nuclei
are comprised of equal numbers of Protons, Neutrons & electrons with varying energy levels
Baryons
930.947 MeV
electrons
496.519 keV
KEM fields
13.525 ev
The mass-energy content of Matter topologies is velocity invariant
The mass-energy content of Baryons determines the KEM field of electrons

The material topologies of Tetryonic theory then also lead to the necessity to correct ‘weighted’ values for all known particles and elements [and then some] in light of the quantum mechanics of the same – ie their identical 3D charge topologies and the mechanics of the quantum rotating synchronous convertors [Deuterium nuclei] that they form in deference to the accepted theory of mini-solar systems and Neutrons that are heavier than their identical charged counterparts [Protons and anti-Protons]



Redefining Atomic weights

Atomic weight (symbol: Ar) is a dimensionless physical quantity, the ratio of the average mass of atoms of an element (from a given source) to 1/12 of the mass of an atom of carbon-12 (known as the unified atomic mass unit)

The 'unified atomic mass unit' currently in use is known to be inaccurate and must be corrected in order to bring clarity & increased accuracy to the atomic weights of all elements

A_r = 22,512
Hydrogen

Defining Hydrogen as having an exact atomic Planck mass of 22512n quanta provides uniformity with Tetryonics

Deuterium is the building block of all elements in the period table

A_r = 45,012
Deuterium

Defining Deuterium as having an exact atomic Planck mass of 45012n quanta reflects the true charged geometries of all Elements & their topologies

Carbon 12
504
[254-254]
12
C
11.996
C12
270,072
6s1
6 Protons [24-12]
6 Neutrons [18-18] n1
6 electrons [0-12]
Unified atomic Matter unit
48
[24-24]
H
P+
22,512
1.660538783e-27 kg
1 Proton [24-12]
1 electron [0-12] n1
1/12 C12
Ar = 22,506
42
[24-18]
1/2 electron
P+
22,506
1.660096209e-27 kg
1 Proton [24-12]
.5 electron 0-6 n1
D
1/6 C
84
[42-42]
N0
e-
P+
45,012
3.320192418e-27 kg
1 Proton [24-12]
1 Neutron [18-18] n1
1 electron [0-12]

Point in case being **Tetryonic Problem: Incorrect Proton and Neutron masses**
As detailed in illustration 49.04 & 49.05 respectively in my eBook… Tetryonics demands an exact mass for Planck quanta and the molar masses [at absolute zero] for each and every particle in our Universe for modelling and any additional energy momenta [by way of thermal, spectral, kinetic or observational energies etc.] are accounted for in the KEM fields of each respective element or particle.



Planck mass-energy units

The unified atomic mass unit (symbol: u) or Dalton (symbol: Da) is a unit that is used for indicating mass on an atomic or molecular scale

270,072
1/12 the mass of a C12 graphene atom at rest in its electronic ground state
1.660538782(83)x10−27 kg
22,506
is an inaccurate means of determining the exact rest mass of a Hydrogen atom
22,512

Carbon 12 has 270,072n planck quanta (270,072 / 12 = 22,506)

Hydrogen has a mass of 22,512n (22,500+12) requiring all mass to be calculated directly using the Planck mass-energy quantum (.001kg / N_A / 22,512) & Tetryonic charge geometries

Using Tetryonic theory to define
n Planck mass = $7.376238634 \times 10^{-32}$ Kg
(see Tetryonics QM 15.04)

exact atomic rest masses for all particles, elements and compounds can be determined directly from atomic theory

N_A = 6.02214179 e23

The mole is the amount of substance of a system which contains as many elementary entities as there are atoms in 0.012 kilogram of carbon 12; its symbol is "mol".

NAu = 0.001 kg
48
[24-24]
e-
1H
P+
22,512
1.660538841 e-27 kg
One Da is approximately equal to the mass of one proton or one neutron
36
[18-18]
N0
0.499866702 H
22,500
1.659653693 e-27 kg
36
[24-12]
P+
0.499866702 H
22,500
Deuterium is the building block of all elements
84
[42-42]
N0
e-
2H
P+
45,012
3.320192534 e-27 kg
NA(12u) = 0.012 kg
504
[254-254]
12
C
11.996
C12
270,072
6 [s1]
6 Protons [24-12]
6 Neutrons [18-18] n1
6 electrons [0-12]
Carbon has a number of differing atomic configurations (allotropes)
6 Protons [24-12]
6 Neutrons [18-18] n1-2
6 electrons [0-12]
504
[252-252]
6
C
12.6493
284,760
[He] 2s2 2p2

There is NO room for a 'weighted' atomic mass as utilised in modern chemistry which conveniently ignores the mass and motional energies of the electrons in the elements or which ignores the KEM field energies noted above for 'most' situations and calculations – Tetryonic theory MUST account for all of these energies even if it does so at the risk of disagreeing with modern theory at times…

The Proton and Neutron MUST have identical atomic masses as they are identical – both are 36π Baryon Matter topologies differing only in the net charges of +12 [24-12] vs 0 [18-18] they possess as a result of their constituent quarks [UDU vs DUD] as extensively detailed in my QM eBook… Neutrons are NOT created through the process of 'reverse' beta-decay as is supposed presently supposed in modern theory and accordingly do NOT have a slightly higher mass than Protons which in turn affects the molar mass calculations for all periodic elements and isotopes as outlined in my Chemistry eBook as well at length.


Baryon geometry
Proton
12
Tetryonic Charge
[24-12]
u
d
u
+1
elementary charge
Proton
P+
[36]
Linear - Tri-quark geometries - prior to Strong force interaction
Protons are
GEOMETRIC MIRROR IMAGES
of Neutrons
N⁰
0
elementary charge
Neutron
[18-18]
Tetryonic Charge
0
d
u
d
Neutron

Ie Carbon 13, 14 and upwards are not the result of 'extra' Neutrons being bound to the Carbon nuclei – such a nuclei if possible would be stable and not decay as observed – but rather they are simply the result of the inherent 'squared' equilateral mass-energies of each Baryon in the nuclei being increased from n1 to n2 to n3 …. Resulting in a net mass increase that 'appears' to be the result of a number of 'extra' Neutrons in the nuclei [again this is detailed in my Chemistry eBook and spreadsheets of the calculations be easily created from the formulae found in chapter 53 on my Chemistry eBook….


Q
RE
C
M
KE
Electron Configuration
[n] p1
Atoms store mass-energies
in their standing wave Matter topologies
and release it via radioactive decay paths
It is increased kinetic energy level
geometries that create nuclear isotopes
(not extra Neutrons within a nucleus)
504
[254-254]
C12
11.996
n1
270,072
Ground
energy level
504
[254-254]
C13
12.9850
n2
292,320
22,248
[.998 Neutrons]
504
[254-254]
C14
14.0181
n3
315,576
45,504
[2.0224 Neutrons]
504
[254-254]
C15
15.0959
n4
339,840
69,768
[3.1008 Neutrons]
504
[254-254]
C16
16.218
n5
365,112
95,040
[4.224 Neutrons]
504
[254-254]
C17
17.385
n6
391,392
121,320
[5.392 Neutrons]
504
[254-254]
C18
18.589
n7
418,680
148,608
[6.6048 Neutrons]
504
[254-254]
C19
19.855
n8
446,976
176,904
[7.8624 Neutrons]
Shell
Molar meM
R 8 446,976 19.855 6
Q 7 418,680 18.598 6
P 6 391,392 17.385 6
O 5 365,112 16.218 6
N 4 339,840 15.095 6
M 3 315,576 14.018 6
L 2 292,320 12.985 6
K 1 270,072 11.996 6
Nuclei per shell
energy level
22,500
[1 Neutron]
n
[930.97 MeV]
Kinetic mass-energy geometries
stored in 3D Matter topologies
is released as Chemical energies
Deuterium nuclei with bound photo-electrons form quantum-scale synchronous converters

This 'significant discrepancy' with Tetryonics prediction of Proton and Neutron masses from observed ones alone will be enough to prove Tetryonic theory a worthy successor to modern quantum chemistry theory – unless you can explain all of the above using 'excess' Neutrons.

I am neither ignorant of the basic masses of basic particles nor do I think that Tetryonic theory and observed facts of nature disagree, but rather the established theoretical 'facts' of modern chemical theory must be in error

I agree that in reality Matter has **3D structure** (including **volume**) hence the terminology of Matter **topologies** throughout my work. To portray my planar illustration of elements and particles in my PDF eBooks as not reflecting their true material topologies is grossly inaccurate and reflects that fact that **YOU have NOT read all my work** including Tetryonics 101, the Google sketch warehouse of 3D CAD models of each and every particle [kindly developed by Rene Cormier over many months of effort] and extensive list of all elements and their charged 3D topologies and electronic wave function properties and numbers which are freely available to all – only planar 2 d mass-energy **geometries** [bosons and photons] are portrayed as being like thin 2D sheets in Tetryonic theory, something I am sure you will become more familiar with as your understanding of T-theory advances,[and your distain for its predictions and values not in accord with modern theory wains over time].


anti-Matter
W⁺ bosons
bosons
π
photons
photons
2π
W⁻ bosons
Matter
4π
tetryons
Tetrahedrons
4π
Octahedrons
8π
12π
quarks
leptons
Dodecahedrons
12π
Baryons
36π
Icosahedrons
20π
radiant mass-energy geometries
Deuterium nuclei
are the atomic building blocks of all
Periodic elements
standing-wave Matter Topologies

Regarding the ‘separation ‘ of electrons from the atomic nucleus – this is an antiquated model of quantum electrodynamics that is fashioned on planets and their satellites [ie the mini-solar system Bohr model] and which has been extended to a fuzzy electron orbital model to incorporate the Schrodinger quantum model and the ‘inherent’ quantum uncertainly/indeterminacy of statistical probabilities intrinsic to quantum theory as the theories developed over time…. Tetryonics makes it quite clear in T[1] – QM that the atomic nucleus is in fact a quantum synchronous convertor [ala Tesla/Westinghouse] that can store and release mass-energies in a controlled and predictable manner [ala isotopic decay and spectral line emissions] and that quantum mechanics is NOT quantum inherently uncertain nor in determinant as it is often portrayed – in fact quantum theory as explained by Tetryonic theory is very much deterministic in every way – it was only our top-down view of the mechanics that led modern science to this erroneous conclusion, which I have attempted to correct through Tetryonic theory.



Quantum Batteries

Atomic nuclei can be easily scaled to non-quantum sizes to offer clean, safe and portable long term energy storage devices that can store energy indefinitely and release it on demand anywhere in the World

12 loop quantum inductive rotor

The quantum battery is unique in that in addition to storing energy indefinitely, when the nuclei combine with a lepton it has the ability to release specific energies [photons] by way of its synchronous quantum convertor topology

Energy stored in quantum batteries is measured as mass

The non-neutral charge of atomic nuclei attract free leptons into ‘bound’ states within the various **n** levels of atomic shells releasing energy as spectral photons

12
[0-12]
e-
Negative charge topology
Quantum Rotor
12
[42-30]
Quantum Cathode
N0
n
e-
P+
45,000
Quantum Anode
(Atomic Nuclei)
24
[84-60]
+
-
P+
N0
n1
n1
N0
P+
45,000
45,000
-
+
anti-Parallel Configuration
Series Configuration
24
[84-60]
-
N0
n2
P+
N0
n1
P+
90,000
+

The electron does not orbit the atomic nucleus of any element but rather is bound via its magnetic dipole moment to the positively charged nucleus and spins akin to the rotating rotor of quantum convertor partially within the 3D Matter topology of Deuterium nuclei….



Using Tetryonic charged geometries for mass-ENERGY-Matter,
an electron's position and velocity CAN be modelled simultaneously
(but any attempt to measure or interact with it, will affect its component energy-momenta)

Electron Position Uncertainty

Atomic orbitals are typically described as "hydrogen-like" (meaning one-electron) wave functions over any spatial region of measurement, categorized by n, l, and m quantum numbers, which correspond to the electron's energy, angular momentum, and a vector momentum component, respectively

Lepton's are physically Spin 1 fermion particles that can easily be misconstrued as having entirely different spin numbers without the correct physical topologies to base the observed measurements on

Quantum Mechanics is a mathematical representation of equilateral energy momenta interactions and the charged geometries of mass-ENERGY-Matter

Determining the motion of electrons bound to atomic nuclei is akin to measuring the motion of variable speed electric fan blades mounted at various heights within a rotating carousel

The energies of photo-electrons are determined by the Baryons they bind to & incident photons

Leptons are 12 loop quantum rotors

an identical fascia is presented with every 120 degree rotation

their spin number is a measure ment of their magnetic moment

The unique 12 faceted topology of leptons results in an identical EM geometry being oberved for every 120° rotation of the particle

Leading to the interpretation that the Lepton disappears and re-appears when being 'observed' or measured

Every charged radial arm of a Lepton's Matter topology is identical to every other

Making accurate measurement and mathematical modelling of its rotational dynamics & mechanics incorrect without the correct physical topologies

Erwin Schrödinger
(12 August 1887 – 4 January 1961)
Werner Heisenberg
(5 December 1901 – 1 February 1976)
12
(0-12)
Spin UP
Spin DOWN
0 degrees
60 degrees
120 degrees
180 degrees
240 degrees
300 degrees
360 degrees

Again these models have all been built and operate according to established electrodynamic theory and their operation is well understood in the macro sense [but obviously the acceptance of such a model strains the thoughts of most who have grown up a mental picture of fuzzy electrons orbiting a spherical nuclei]



Quantum synchronous Converters

Energy can be stored in macro-scaled quantum converters as mass

The electron has a charged Tetryonic Matter topology that is electrically equivalent to a 6 loop inductive rotor

Matter is radiant EM energy in a standing-waveform

Building on the charged topology of Deuterium nuclei, scaled electromechanical quantum converters can be manufactured to provide efficient electrical mass-energy storage & distribution devices

These devices can be transported any where demand requires them worldwide with their energies stored in the form of mass

Negating the need for centralised power stations and distribution lines extending vast distances to provide power to remote communities

A quantum synchronous converter can store and release 3 forms of energy

Angular Momentum (motional energy)
square root linear momentum

Radiant Energy (emission/absorption)
of photon/boson mass-energy geometries

EM mass-Matter (stored masses in Matter topologies)
radiant EM mass-energies stored in standing wave Matter topologies

Leptons rotate within the Baryonic EM fields of the Nucleus

Quantum
Cathode
Quantum
Anode
Energy
$\frac{12\pi}{c^4}[[m\Omega v^2]]$
Planck
quanta
mass
velocity
n8
n1
momenta
Nuclei
$\frac{72\pi}{c^4}[[m\Omega v^2]]$
n32
n25
Deuterons
$\frac{84\pi}{c^4}[[m\Omega v^2]]$
Radiant
energies in
Radiant
energies out

Again the electronic structure of each and every one of the 120 possible periodic elements is well detailed wrt Bohr shells & orbitals and unified wrt their respective Schrodinger numbers for the same in my Chemistry eBook for all to view…. Unlike modern texts which normally stop at element 20 and claim that it is just too difficult to show the quantum models of larger elements with their evermore complex electron configurations and Schrodinger numbers



Periodic Topology of Elements

electron Orbitals
7
5
3
1
quantum
numbering
3
2
1
0
s
p
d
f
atomic
orbitals
2
6
10
14
electron
Sub-Orbitals

The s.p.d & f orbitals of electrons 'around' any elementary nuclei is the result of the atomic nuclei rotating about is centre of mass/gravity [classical angular momentum] and the electrons tracing out easily determined and well defined concentric orbits about the same centre [as illustrated] …. A close examination of the Schrodinger numbers [or in fact Bohr orbits] of heavier/larger Z number atomic nuclei reveals the there are no g,h I orbits etc as often postulated but in fact there is a reversal of electron orbital distance as the element number and principal energy levels increases….. Resulting in the periodic symmetry depicted in Tetryonic theory of an atomic nucleus resembling a child's spinning top, which could be mistaken for a spherical topology from our macro view of the quantum scale.


Periodic
element number
Topology
R
2
8
Q
8
7
P
18
6
atomic shells
O
32
5
quantum levels
N
32
4
M
18
3
Z
L
8
2
K
2
1
3
2 10
s p d
f
2
6
10
14
f
d
p
s
p
d
f
electron orbitals
of Elements

With each element's Z number reflecting the number of **Deuterium** atoms in each nuclei, *not the number of Hydrogen atoms with an ever increasing number of Neutrons to account for observed molar masses*


Planck mass-energy contributions to the measured weights of periodic, elementary mass-Matter topologies

Baryons have 2,25e23 Planck quanta comprising their rest Matter topologies

Leptons have 1.2 e20 Planck quanta comprising their rest Matter topologies

Photons are planar geometries [Matter-less] (purely Kinetic mass-Energy and momenta)

The Lyman alpha spectral line mass-energy contribution to the mass of a Deuterium nucleus is negligible

Electron quantum level energies are determined by the energy of the Nuclei they bind to in elements

Photons contribute spectral mass-energies to the nuclei mass but are themselves Matterless [2D zero rest mass-energies]

Photons are 2π charge mass-energy geometries
36
[18-18]
N0
45,000n
1.659653693 e-27 kg
36
[24-12]
P+
45,000n
12
[0-12]
e-
12n
8.851486361 e-31 kg
n
[v-v]
2.4111096111 e-35 kg
γ
KE
0
KEM
[930.974 MeV]
Δ 1875 x
[496.5 keV]
[496.5 keV]
Δ 36,711 x
[13.6 eV]
D+
[1.862 GeV]
84
[42-42]
N0
e-
P+
n
90,012n+

The electrons associated with each atomic element's structure in fact have an important and direct bearing on the spectral emissions of each particular element. Even though their mass-energies of their electronic topologies are only 0.000533' % of the mass-energies of each Baryon in any atomic nuclei this mass-Matter differential along with the energy momenta of the electron's KEM field is key to facilitating the absorption and release of spectral line emissions particular to each and every element known… again, it is not simple good enough to conveniently ignore electrons ad hoc in scientific theory to suit a particular point or theory just because they are or 'insignificant' mass compared to the whole nucleus. Any successful model of science and physics in general must be able to account for ALL the known aspects of modern observations not just a select few that suit their purposes in order to unify physics on all energy scales. Ie a new model of the quantum structure, topology and mechanics of atomic nuclei must account for charge, atomic and chemical interactions, spectral line series and all known elements and compound creation in the ONE physical model.

Clarifying question about Tetryonics nuclear vs. atomic size wrt the Zenon atom

I humbly submit that illustrations 51.49


4.536
[2.3268-2.268]
Xe
129.9435
2,925,288
494,640
Xenon
54
Q
RE
M
KE
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
f d p s p d f
electron configuration
[Kr] 4d10 5s2 5p6
54
Noble Gas
Aufbau
Azmithal & Magnetic numbers
8
18
18
8
2
atomic shell
Orbitals & sub-orbitals
energy level

And 53.49 respectively along with the 3D CAD illustrations of the same


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
3
18
18
8
2
f d p s p d f
Indium
[72(m²)] + [12e19] + [Δv]
[Kr] 5s2 4d10 5p1
Metaloid
Azmithal & Magnetic numbers
49
Atomic Shells
Orbitals & sub-Orbitals
Energy levels

Should be sufficient to explain and illustrate all properties of the Zenon atom [or any other you chose] including their rest mass-Matter energies [at absolute zero], their charged Matter topology in accord with Bohr shells/orbitals and Schrodinger numbers and the kinetic mass-energies of their bound electrons.

Clarifying question 2 about Tetryonics nuclear vs. atomic size

According to Tetryonics the proton and neutron in Deuterium nuclei touch one another at the point son their respective charge topologies where the e-field components of their constituent quarks are located - this is indicated on all Tetryonic element illustrations via red [for positive] focus points and black [for negative] focus points.


Nucleonic residual EM force
Neutrons
Protons
The attraction between Baryonic E&M field apexs, a result of their component Quark arrangements, results in the formation of heavier and more complex Nuclei
The residual e-field apexes and m-field dipoles form two rings of residual EM fields around the circumference of atomic nuclei
Elements & compounds follow Hexagonal packing rules
u
d
N⁰
P+
E-field apexes and their polarities highlight the quark alignment of all atomic nuclei and elements
UP Quark
Positive Electric field apex
DOWN Quark
Negative Electric field apex

But since Tetryonics does not include any separate strong nuclear force but just electromagnetics, all particles of Tetryonic nucleus would fly apart in a nanosecond.

Again, this misunderstanding and erroneous statement about Tetryonic theory seems to stem from you having failed to read Tetryonics [1] – Quantum Mechanics, viewed my Tetryonics 101 instruction video or even attempted to build and understand how atomic nuclei are formed and come together to form larger elements and compounds alike prior to commenting ….

In my first eBook I have gone to great lengths to show that the STRONG force does indeed exist and in fact plays a crucial role in bringing tetryons [the tetrahedral quantum of Matter topologies themselves] together to form leptons, quarks, mesons & Baryons – it is the parallel opposite charge interaction present between the planar charge faces of each tetryon within each and every Baryon [not to be mistaken for the residual strong force]


The Strong Force
The force resulting from the interaction of 2 Tetryons along their parallel planar (Electric charge) surfaces
12
[12-0]
e+
12π
Leptons
Repulsive colour Force
Leptons are 'held together' by a radial Weak Force axis
12
[0-12]
e-
12π
Leptons and Quarks result from the Strong 'colour' force interactions in dodeca-deltahedrons
(In Quarks the attractive strong force produces Octahedral topologies)
(In Leptons the repulsive strong force produces Dodecahedral topologies)
up
8
[10-2]
8π
12π
Quarks
4 Fascia 'Colour' Attraction
Quarks
Attractive colour Force
4
[4-8]
down
12π
8π
'Attractive' Colour Force
Opposite charge Tetryon fascias
Colour Force fascias
θ
0°
Colour force Interaction angle
'Repulsive' Colour Force
Same charge Tetryon fascias
Same direction QAM flux
Opposing direction Electric flux rotation
Strong Force strength is directly proportional to the nett mass-energy quanta involved
(Increases/decreases as total Tetryon mass-energy quanta increases/decreases)
Proton
12
[24-12]
36π
P+
20π
Baryons
Attractive colour Forces
Baryon formation
16 Fascia 'Colour' Attraction
0
[18-18]
36π
N⁰
20π
Neutron
The Strong Colour Force is the binding force that holds Nuclei together
Tetryonic Fascia (Planar Electric Charge) interaction
It interacts through oppositely charged Tetryon Fascias in contact with each other in all Matter (save Leptons)
12
[42-30]
72π
N⁰
Nuclei
P+
40π

Obviously this co-planar opposite charge interaction holds all atomic nuclei together and your claim of Tetryonic particles flying away in a nanosecond just doesn't hold water…

In fact just place two sheets of glass together with a thin film of water between them and see how easy it is to pull those sheets apart by applying a force orthogonal to the co-planar sheets of glass and you'll soon understand the STRONG force much better that you do presently.

This charge interaction between the e-fields of quarks in Baryons serves to not only bring positive charge Protons together with neutral Neutrons [something modern theory cannot explain] but also serve to orientate each baryon to the other so as to facilitate electron bonding and the creation of ever larger atomic elements and compounds [the residual strong or EM force as it is often termed or the London force]


Strong Forces and Nuclear Bonding
How do Baryons with Positive and Neutral charges attract each other and bind to form stable elements ?
P
Charged EM fascia
Electric fields & Magnetic dipoles
N
u
10-2
d
4-8
+
-
Protons & Neutrons are attracted to each other through their equal but opposite charge fascia of their Matter topologies
12
[42-30]
72
P
N
N
P
72
12
[42-30]
Once nuclei have been created their external electric fields & magnetic dipoles continue to attract and bind individual nuclei together via the Residual EM Force as nuclei seek charge equilibrium by combining with each other and electrons to form neutral elements
36
0
[18-18]
+
=
72
12
[42-30]
36
12
[24-12]
84
1
2
3
4
5
6
0
[42-42]
Z
The attraction and binding of Protons and Neutrons through their electric charge imbalances creates Deuterons which have +12 charges
The residual Z[+12] charge is what attracts electrons to form neutral atomic nuclei via Coulombic attraction

Yes I have an ‘obsession’ with all atomic nuclei have equal numbers of Protons, electron AND Neutrons in accord with their Z number, just as you have an obsession with them being Hydrogen atoms with excess Neutrons ‘bound’ to them – but for the reasons highlighted above, and many others – as for the quantum structure of Protium (regular hydrogen), Deuterium and Tritium being ‘missing’ - again my T[1] - QM eBook holds the answers


Hydrogen Family
12
[24-12]
22,500
+
12
[0-12]
12
=
0
[24-24]
22,512
Proton
36π
electron
12π
Hydrogen
48π
0
[24-24]
22,512
+
0
[18-18]
22,500
=
0
[42-42]
45,012
Hydrogen
48π
Neutron
36π
Deuterium
84π
0
[42-42]
45,012
n1
+
Tritium is Radioactive
6 quantum level
Energy increase
(24,768 n quanta)
1.1008 Neutron mass Matter
=
0
[42-42]
69,780
n7
Deuterium
84π
Tritium
84π

With additional space being made to highlight the Tetryonic genesis of Tritium & Helium 3


Hydrogen-Helium3 genesis
Elemental Form
Positive Ions
Radioactive
n7
n1
+1
+2
24

All isotopes are simply Z number nuclei with the energy levels of their Baryons raised to the next quantum energy level [n1-n8] in accord with the 3D material symmetry of the atomic nuclei themselves and the Bohr shells/Schrodinger principal quantum numbers, which can occur either through natural energy absorption or the artificial increase of their mass-energy content in the lab….



Obviously with all Deuterium nuclei being quantum synchronous convectors as the energy levels of their Baryons are increased [or decreased] the electrons bound to them respond in kind [hence synchronous] via spectral line emissions [or absorption] ….all covered in Tetryonics [2] – Quantum Electrodynamics.


Spectral line differentials
Δhv = ΔMv = Δp
changes to energy momenta
accelerate photo-electrons
1/λ = R_H/hc (1/n₁² - 1/n₂²)
Ryberg's formula is a mathematical description of Tetryonic energy geometry
RE
KE
M
Δhf
Bosons
v
c
R
KE
1²
2²
3²
4²
5²
6²
7²
8²
absorption
n₁²/n₂²
Fractional energy level transitions
n₂²/n₁²
emission
Photo-electrons
& produces spectral lines
Un-named
Humphries
Pfund
Brackett
Paschen
Balmer
Lyman
Ryberg's constant reflects the changing energy momentum of a transitioning electron
Mv² = KEM = hcR
All of the transitions of photo-electrons bound into a Hydrogen atom can be revealed in the fractional geometry of KEM field energies
KEM field energies

There is NO explanation in modern chemical or quantum theory that accounts for the Proton-Neutron 'curve' of atomic isotopes nor for the islands of stability that exist for various elements, however Tetryonic theory accounts for all of this firstly by 'straightening' out the curved Z line of Protons and Neutrons underpinning atomic elements [by showing that all atomic nuclei are comprised of D nuclei not H atoms with excess neutrons] and then showing that the observed isotopic masses of each are the result of increased principal energy levels of their constituent baryons with the D nuclei comprising each element…. It is no error or 'false notion' as you put it, rather it is the current explanation of these facts by modern theory that is in error


672
[336-336]
O16
15.995
360,096
Ground energy level nuclei
O17
17.313
389,760
36,664
1 Neutron
O18
18.690
420,768
60,672
2 Neutrons
O20
20.127
453,120
93,024
4 Neutrons
Electron Configuration
s2 p6
Q
RE
M
KE
p5
p4
s1
p1
p2
s2
p3
p6
This oxygen allotrope's nuclei arrangement is very stable and inert like Neon [due to its filled sp electron orbitals]
Oxygen Allotropes
& Isotopes
O
382,128
22,032
There exists an allotrope of Oxygen formed when 8 nuclei combine in a single level SP orbital arrangement
Shell
Molar meM
R 8
595,968
26.473
Q 7
558,240
24.797
P 6
521,856
23.181
O 5
486,816
20.825
N 4
453,120
20.127
M 3
420,768
18.690
L 2
389,760
17.313
K 1
360,096
15.995
Nuclei per shell
8
energy level
It is increased Nucleonic energy levels that creates Isotopes (not extra Neutrons within a Nucleus)
O21
20.825
468,816
108,720
4 Neutrons
O23
23.181
521,856
161,760
7 Neutrons
O24
24.797
558,240
198,144
8 Neutrons
O26
26.473
595,968
235,872
10 Neutrons

You have chosen Lithium to make your point I chose Carbon, Nitrogen and Oxygen to make mine, but the explanation for Lithium remains the same….. an increase in the mass-energies of the baryons making up the element concerned… btw I have done spreadsheets for each and all the elements as a matter of course during the development of my theory.


588
[294-294]
N
14.8118
333,444
18,360
It is increased Nucleonic energy levels that creates Isotopes (not extra Neutrons within any elementary Nucleus)
Nitrogen gas
1,176
[588-588]
2N
29.623
666,888
36,720
Nitrogen Allotropes
& Isotopes
N15
15.149
341,040
25,959
Isotopes are created by increasing the number of Planck mass-energies stored in the standing-wave geometries of chemical elements
N14
13.996
315,084
Ground energy level nuclei
The charged mass-energy geometries of differing allotropic topologies create various chemical bond points
Shell
Molar meM
R 8
521,472
23.164
Q 7
488,460
21.697
P 6
456,624
20.283
O 5
425,964
18.921
N 4
396,480
17.612
M 3
368,172
16.354
L 2
341,040
15.149
K 1
315,084
13.996
Nuclei per shell
7
energy level


252
[126-126]
Li
6.1615
138,708
3,672
electron configuration
[He] 2s1
Lithium
03
Q
RE
M
KE
R
Q
P
O
N
M
L
K
8
7
6
5
4
3
2
1
3
2
1
0
1
2
3
f
d
p
s
p
d
f
03
Protons
Neutrons
electrons
Alkali Metal
Azimuthal & Magnetic numbers
Aufbau
atomic shell
energy level
Orbitals & sub-orbitals

Element 3 – Lithium [ground state atomic topology and electronic configuration]


elemental family geometry
electron configuration
3 2 1 0 1 2 3
R Q P O N M L K
8 7 6 5 4 3 2 1
1
2
f d p s p d f
Lithium
[72(m²)] + [12e19] + [Δv]
nuclear mass-energy quanta per shell
[He] 2s1
Alkali Metal
Azmithal & Magnetic numbers
0
03
s
Atomic Shells
Orbitals & sub-Orbitals
Energy levels

Regarding your comment of “but in reality **only electrons are on these shells** and the structure of the nucleus is completely separate from these shells”, - that is only the current opinion/consensus explanation of quantum chemistry at this stage and is obviously at odds with Tetryonic theory *built from the ground up from equilateral Planck energies not the top-down through supposition*….. I am confident that over time this consensus will change.

1. Explaining the extra (neutron) weight as higher energy-levels of the Deuterium nuclei seems *ad hoc* explanation with no supporting evidence – *simply nonsense*…..
2. No calculation is presented to *derive a prediction* for the excess mass (or energy) from the Tetryonics model – *have you even read my work in detail – calculations and mass-energies are provided everywhere throughout it*.
3. The excess mass of, say, Lithium 7 (one excess neutron compared to 3x deuterium) *– again a number based on your erroneous viewpoint – not y given explanation and illustrations of the same.*
4. This is inconsistent with the fact that there are **multiple** isotopes of each element.- *how so?*

   The energy level of Baryons of each and every illustrated element in Tetryonic can be increased resulting in isotopes of that element – with NO extra Neutrons present, again you seem to have failed to read and/or comprehend what was presented before you in the Tetryonics chemistry eBook.

5. See above for Hydrogen family [please]

All the ‘observed’ masses you have provided in that table are firstly just that, weighted [averaged] measurements of particles with kinetic energies [heat, spectral, motion etc.] not the absolute rest masses I have provided and clearly stated as such…… you must account for observational and inherent kinetic energies for your stated values to even begin reflecting the quantum values of particles at absolute zero.

Again, ‘isotopes’ is NOT what you think and proclaim – there are no extra Neutrons in the nuclei – only Baryonic energy above that of the res/ground state of such an element at absolute zero – unless you can account for those KEM field energies [as should be done]

Tetryonic Problem: Helium as Alkaline Earth metal

- And Hydrogen is element 1 which no-one can agree on which position it truly belongs in on the current periodic table.

Tetryonics problem: 120 possible maximum elements

- That is what is dictated by the charge topology of particles and elements themselves, perhaps you'd care to share what your spherical [or other] model for element 93 is, and how all the 'extra' Neutrons bind to each other to create that particular model?

Tetryonics shows quite clearly the reasons for there being only 120 possible periodic elements and it agrees with the math and equations of both Bohr and Schrodinger's models despite the differing quantum topologies.

Perhaps, you can produce element 121 and prove me wrong on this.


R
Q
P
O
N
M
L
K
electron shells
Q
[v-v]
Z_{N_A}
M_0
KE
2
8
18
32
32
18
8
2
8
7
6
5
4
3
2
1
energy levels
f +3
d +2
p +1
s 0
p -1
d -2
f -3
orbitals
Elementary mass-Matter
R
K
$\sum$
2
8
18
32
32
18
8
2
2 nuclei
8 nuclei
18 nuclei
32 nuclei
32 nuclei
18 nuclei
8 nuclei
2 nuclei
+
120 Unbinilium
119 Ununennium
118 Ununoctium
87 Francium
112 Copernicium
55 Caesium
102 Nobelium
37 Rubidium
70 Ytterbuim
19 Potassium
30 Zinc
11 Sodium
10 Neon
3 Lithium
2 Helium
1 Deuterium
Aufbau
Z#
z Protons [24-12]
z Neutrons [18-18]
z electrons [0-12]
n1-8

Deuterium is the building block of all Elements (save Hydrogen)

The geometry of any Element is determined by its Charge

The Molar Weight of any Element is a measure of its standing wave mass-energies

The rest mass-Matter of any Element is determined by the total number of quanta making up the Protons, Neutrons and electrons that comprise them (in their respective energy levels)

Any mass-energies in excess of the molar [n1] weight is a measurement of a element's CHEMICAL energies

Important point to note:
The Kinetic Energy difference between any Element's total [n1] Deuteron mass-energies and its Molar mass has historically been incorrectly explained as resulting from an excess number of Neutrons in the atom it is not. Z# = (number of Protons = number of electrons = number of Neutrons)

The rest mass-Matter of any Element is the sum total of its constituent $Z[n^2]$ energy level Deuterium nuclei

(ie Calcium [20] = 2+8+10 n level Deuterium nuclei)

Additional random quotes - the uncertainty principle erroneously dictates that position and momentum cannot be simultaneously determined

- There's nothing random about this comment/quote - Tetryonic theory is founded on the SINGLE postulate that Planck mass-energy momenta has an quantum equilateral geometry [ie quantised angular momenta (m^2/s) is equilateral/triangular not circular as it is the macro sense of angular momentum] - from that flows the fact that the probabilistic nature of quantum theory and the maths used to describe it are in fact not 'fuzzy' or indeterminate as supposed presently but in fact an emergent property of the tessellation of mass-energy momenta at the quantum level.

The inherent indeterminacy of quantum theory is a crutch used my mathematicians and scientists alike to explain many of the puzzling aspects of quantum theory like the inherent statically probabilities of quantum fields themselves or the wave-particle duality of photons or particles in motion….. Again it is them and modern theory that have simply failed to grasp the geometric reality of energy momenta that underpins these phenomena and how they build to form the familiar laws of Nature at our scale of observation.

Tetryonic theory is all about correcting these erroneous assumptions and established viewpoints – but any change of perspective is not without birth pangs of angst and misunderstanding from those who first encounter it [like Newton, Planck and Einstein with their theories of Gravity, Quantum mechanics & Relativity theories before it]


Scalar
mass-energies
Probability
distributions
v
p
Bosons
Energy
ε0
Energy
[mΩv²]
momentum
hv
v²
Photons
c²
Quantum level
Bosons
Scalar
Energies
Planck quanta
mΩv²
mass
velocity
Photon
Distributions
EM Field
Planck quanta
nπ [[ε0μ0].[mΩv²]]
mass
ElectroMagnetic
mass
velocity

That it is the transverse bosons Max Planck described using E=n.hv when resolving the ultraviolet catastrophe and spectral line emissions


0.987654321
SQUARE ROOTS
80/81
ODDS
SQUARES
1 3 5 7 9 11 13 15 17 19
1 4 9 16 25 36 49 64 81 100
1 2 3 4 5 6 7 8 9
n
1/2 1 3/2 2 5/2 3 7/2 4 9/2 5 9/2 4 7/2 3 5/2 2 3/2 1 1/2
NORMAL DISTRIBUTION

And which subsequent theorists incorrectly applied directly to Einstein's formulation of E= hf to describe neutral PHOTONS of energy momenta [dual charge bosons – quantum transformers]


0.987654321
SQUARE ROOT
LINEAR MOMENTUM - VECTOR VELOCITY
80/81
TRANSVERSE
BOSONS
SCALAR EM
ENERGIES
1 3 5 7 9 11 13 15 17 19
1 4 9 16 25 36 49 64 81 100
Ψ
1/2 1 3/2 2 5/2 3 7/2 4 9/2 5 9/2 4 7/2 3 5/2 2 3/2 1 1/2
PHOTON DISTRIBUTIONS

And then erroneously attributed to an inherent uncertainly in quantum field dynamics etc. that does NOT and never existed in Nature itself or in Tetryonics....

I do look forward to further elaborating Tetryonic theory in detail with you – but also strongly suggest that you become more familiar with my Tetryonics [1] – Quantum Mechanics and & Tetryonics [2] - Quantum Electrodynamics eBooks beforehand as a lot of your suspicions of, and reaction to Tetryonic theory seem to stem from a lack of understanding of the basics of the theory….

And as I mentioned in previous communications, I remain open to an online discussion so we may discuss these points in far more detail than possible herein.

There is also lots more additional information and explanation of Tetryonic theory to be found on YouTube and Otto’s Science of Life web- blog & the detailed 3D CAD models developed by Rene Cormier in the Google sketchup warehouse.





2D radiant EM mass-Energies

n1 - Charged Tetryon Templates



3D standing-wave Matter







2D radiant EM mass-Energies

n1 - Neutral Tetryon Templates



3D standing-wave Matter







2D radiant EM mass-Energies
μ0
ε0

n2 - Charged Tetryon Templates



3D standing-wave Matter







2D radiant EM mass-Energies

n2 - Neutral Tetryon Templates



3D standing-wave Matter







2D radiant EM mass-Energies

n3 - Charged Tetryon Templates


3D standing-wave Matter




p
d
μ_0
ε_0


μ_0
ε_0

2D radiant EM mass-Energies

n3 - Neutral Tetryon Templates



3D standing-wave Matter


p
d
μ_0
ε_0

n4 - Charged Tetryon Templates





2D radiant EM mass-Energies


3D standing-wave Matter







2D radiant EM mass-Energies

n4 - Neutral Tetryon Templates


3D standing-wave Matter







2D radiant EM mass-Energies

n5 - Charged Tetryon Templates



3D standing-wave Matter





p
d
μ_0
ε_0



μ_0
ε_0

2D radiant EM mass-Energies

n5 - Neutral Tetryon Templates



3D standing-wave Matter



p
d
μ_0
ε_0





2D radiant EM mass-Energies

n6 - Charged Tetryon Templates



3D standing-wave Matter






2D radiant EM mass-Energies
μ0
ε0

n6 - Neutral Tetryon Templates


3D standing-wave Matter







2D radiant EM mass-Energies

n7 - Charged Tetryon Templates



3D standing-wave Matter







2D radiant EM mass-Energies

n7 - Neutral Tetryon Templates



3D standing-wave Matter






2D radiant EM mass-Energies
μ0
ε0

n8 - Charged Tetryon Templates


3D standing-wave Matter







2D radiant EM mass-Energies

n8 - Neutral Tetryon Templates



3D standing-wave Matter



The Universal Order of Creation of MATTERS


MATTER
ANTIMATTER
DARK
MATTER

by Nuclear Engineer M.T. KESHE

Kt
Editions

本电子书不是官方正版，

而是使用从官方购买的正版电子书，

截屏＋拼接＋OCR文字识别＋重新拼版制作。

因此难免出现错误的字或符号，

如果您希望获得原始的官方版本，

请购买正版，支持KESHE。

QQ群：30137653

Stichting
THE KESHE FOUNDATION
(The Netherlands)

ISBN 978-94-6087-002-6.

The Universal Order Of Creation Of Matters

ITNOTGOG

… a Reflection

Mans intelligence has reached levels that through the use of modern technologies that anyone can peer the knowledge he reads to verify its logic and validity.

I firmly believe that this work has to be understood by all Men and not judged by a few whose self-interest might, and has been, obstructing the release of such a knowledge as disclosed in this book.

This book is written in such a way that anyone from any background field of science, and interest in the workings of all Matters of the universe, can understand the full new knowledge and be their own peers in receiving such a disclosure, which is at the edge of science and technology.

In this book a synthesis is given of the *understanding of new first principles in physics* that are gathered for over more than thirty years of independent research and development, where several working prototypes and numerous tests with different loadings have confirmed their correctness and operativeness.

Mehran Tavakoli Keshe
2009

Copyright notice: © Mehran Tavakoli Keshe 2009. All rights reserved.

Nothing of this e-book may be replicated, simplified, translated and/or made public by means of print, microfilm, tape, audio-recording systems, electronics, optical and solid-state media, electronic storage systems, by network publishing or by any other ways without prior written authorization of the publisher or the author.

ISBN 978-94-6087-002-6

Illustrations and Layout: Dirk Laureyssens

Publisher: Stichting The Keshe Foundation
Registered Office: Jubileumplein 3, NL-6161 SR Geleen,
The Netherlands
Registration Number: KVK 14089728.
Web site: www.keshefoundation.com
E-mail contact: info@keshefoundation.com

Forewords

In Mans technological and scientific evolution over thousands of years, conversion of the Earthly state of matters and energies from one state to another has been the key to his progressive success.

For man to progress further in the path of this evolution, man has to learn, understand, and unravel the powers of the initial fundamental particles of the Matters.

In the following pages, simple new theoretical principles and results of tests done to unleash the powers of the initial fundamental particles forces will be released and discussed.

In my writings, the simplest form of language is used so that every man, from all corners of the world, can read and will be able to comprehend the fundamental orders of their physical creation.

Therefore, every man on Earth will have the same groundwork knowledge and opportunity to build his own environment and so be in control of his future and destiny.

This simple transfer of knowledge gives every man, by understanding the principles of his world of creation, the possibility to utilise and enhance the fundamental powers of creation for his advancement in his path of evolution.

Through appropriate use of this new knowledge, one can generate as much clean power as one needs for survival at any location in the universe.

This is energy production capability, without the production of any further new wastes to damage the environment and to endanger the future generations' chances' of survival.

This new knowledge allows man to produce food and medicine through the natural process of the construction of his cells' initial fundamental plasmas.

Therefore, no child, woman or man should go hungry and rely-upon others for his survival.

This new knowledge gives man the opportunity to produce all his materials' needs, without him being tied-up to the Earthly resources, or environmental conditions, or the place or a position in the universe, wherever that might be.

This new knowledge brings about the capability for man to be able to move and travel in his environment and in the universe with universal magnetic fields protection, in any atmospheric or space conditions.

This new knowledge, gives man the freedom of motion irrespective of the medium whatever his medium, and wherever he might be in the universe. For man to be able to use systems for travel that is at all time in protected magnetic fields levels and gravitational field levels as on the Earth. As his physical body has become accustom to the atmospheric condition around his home planet.

Which up to now, this has been a dream and unattainable in all dimensions, with his present level of scientific development and knowledge.

Men will build on this new knowledge, and they will add their own scientific and technological flavours and unique additions and discoveries to overcome their present natural problems and limitations.

Our hope is that, Men, irrespective of their race, colour of skin, creed or religion, will use this new knowledge collectively and in unity, for advancement of the human race. We pray that, Man uses' these new knowledge and information's for creation of peace and justice among their fellow men and other of Gods' creations and creatures, whom they will come to be in touch with, irrespective of their appearance, technological progress and intelligence.

Mehran Tavakoli Keshe

Table of Contents

… A REFLECTION 3

FOREWORDS 5

TABLE OF CONTENTS 7

INTRODUCTION 11

Rays and plasmatic magnetic fields 11
Magnetic and gravitational fields (Magravs) 13
Plasmas 14
Matter and matter 14
Initial Gravitational Fields 14
Reactor technology 14
Fission and Fusion by Plasma Dilution 15
Lift and Motion by Magravs positioning 17

CHAPTER 1 20

HISTORICALLY UNEXPLAINED PRINCIPLES 20
1. The creation of Magnetic Fields of the Earth 21
2. Creation of the Gravitational Fields of the Earth 23
3. The source of the Heat in the Earth Cores 27
4. What causes the Rotation of the planet Earth? 28
5. The difference between Matter and matter 30
6. How motion of matters and Matters are created? 31
7. How Light is created? 32

CHAPTER 2 34

INTERACTION OF PLASMATIC MAGNETIC FIELDS (PMTICS) 34

CHAPTER 3 37

THE INITIAL FUNDAMENTAL PARTICLES OF THE PLASMA 37
Creation of Matter of plasma through interaction of pmtics. 38
Creation of the Antimatter of plasma 41
Creation of the Dark Matter of plasma 43
Creation of the torus field force 45
Initial structure of Matters of plasma 47
Transition-zone pmtics 48
Initial Fundamental Plasma 49
Decay of initial fundamental plasma 50

CHAPTER 4 53
MATTERS' OF PLASMA AND THEIR TRANSITION OF STATES 53
CHAPTER 5 60
DEFINITION OF ENERGY THROUGH PMTICS 60
Measure of a mass 62
CHAPTER 6 67
THE TOTAL ENERGY BALANCE EQUATION OF PLASMA 67
CHAPTER 7 73
THE CREATION AND SPEED OF LIGHT 73
CHAPTER 8 83
DARK LIGHT PHENOMENA 83
CHAPTER 9 84
RELATION BETWEEN GRAVITY AND LIGHT 84
CHAPTER 10 90
THE ANTIMATTER 90
CHAPTER 11 92
THE ANTIMATTER ENERGY 92
CHAPTER 12 93
THE DARK ENERGY 93
Steps in the creation of Dark Energy 94
CHAPTER 13 98
THE DARK MATTER 98
Dark spots on the Sun and Black Holes 100
CHAPTER 14 104
VIRTUAL PARTICLES (VIRTUAL MATTERS) 104
The Casimir effect 105
Van der Waals forces 106
CHAPTER 15 107
INTERACTION BETWEEN MATTERS 107
Interaction of Matter with Antimatter 107
Interaction of Matter with Dark Matter 108
The interaction of Antimatter and Dark Matter 109
1) Scenario 1 109

2) Scenario 2 111
Interaction of plasma with plasma *115*
Electron interaction: 115
CHAPTER 16 122
THE FUNDAMENTAL DIFFERENCE BETWEEN INERTIA AND GRAVITY 122
CHAPTER 17 129
PLASMA’S AND NUCLEAR DECAY 129
CHAPTER 18 132
NEUTRON-PROTON, ELECTRON-ATOM 132
The decay of the neutron *133*
CHAPTER 19 140
MOTION OF THE ELECTRON AROUND THE PROTON 140
Universal Magravs positioning principle *143*
Universal method of motion *143*
CHAPTER 20 146
MOLECULES 146
CHAPTER 21 148
PLASMA DILUTION TECHNOLOGY 148
A soup of weak plasmatic magnetic fields *148*
Disentanglement *150*
CHAPTER 22 154
MATTERS AND MAGRAVS SYSTEMS 154
matter propulsion technology *154*
Matter gravitational technology *154*
CHAPTER 23 159
MATTER PMTICS IN REACTORS FOR LIFT AND MOTION 159
Principle concept of upward or separation motion *159*
CHAPTER 24 163
PASSIVE MAGNETIC FIELDS 163
CHAPTER 25 164
NEW UNDERSTANDINGS AND NEW TECHNOLOGIES 164
Pmtics reactors for production of energy *168*
New type of Generators *169*
Seed of thought *174*

CHAPTER 26 176

MATTERS EXPERIMENTAL RESULTS AND OBSERVATIONS 176
Radiation 177
Weight reduction, motion and lift 177
Production of matters 181
Dark Matter technology 182

CHAPTER 27 183

DISCUSSIONS AND CONCLUSIONS 183
Mass of the Matters and Mass of the plasma 185

CHAPTER 28 191

INSIGHT INTO THE FUTURE 191

REFERENCES 197

PUBLISHED AND UNPUBLISHED WORKS BY M. T. KESHE ... 200

INTERNET LINKS 211

INDEX 212

Introduction

In the progressive path of mans' technological achievement, it has been proven that the human race has not been able to create and produce fundamental energy systems similar to the ones which are operating in the spans' of the universe.

Nevertheless, he has managed simply to convert one form of energy to another and he has made use of the small surplus energies released by these methods to his advantage.

In the universe, the structure, operation, appearance and existence of the plasma and an atom, does not so much differ from the relationships and interactions of their larger counter parts as the molecules, solar systems and galaxies.

Where, as in the ***present*** science and state-of-the-art technology, the lower orders of particles of construction of an atom in its nucleus are considered to be made of quarks and gluons.

The world of science has never looked at and into the ***progressive construction of a plasma*** (Chapter 3) on the same basis and principles' as other larger matters and fields in universal orders of creation and motion.

What this simply means, is that scientists over centuries have made some limited and un-necessary self-imposed conditions in looking at the physical realities of Matters and matters in their surrounding environment, for them to be able to compare and draw parallels from these phenomena and principles to understand the criterions by which the initial seeds of plasmas are set in the universe and to understand the methods by which different forces operate within them.

From the basic knowledge of what is in hand in the world of science at the present, it is not too hard to discover what are the real elementary particles in the universe, and find an *alternative and realistic way* of how these fundamental particles of plasma come together to create ***the initial seed of plasma***.

It is important to note that the existence of dynamic and different strengths, speed, velocity and densities of ***magnetic fields***, and their interactions, are the **cause** and the **foundation** of the existence of different **Matters** within the universe. In the universe, *collections* of *loose and weak magnetic fields* have initiated the creation of, and finally become the initial components of the Matters of plasma.

Rays and plasmatic magnetic fields

At the same time, we consider "rays" as individual and directional magnetic forces. We consider "fields" as the same ray's magnetic force as it is influenced by other rays and magnetic field forces, which the ray makes a dynamic zone of influence in its path.

We consider the same phenomena in principle with respect to plasma and ***plasmatic***

magnetic fields, where, a plasma of magnetic fields is considered to be a collection of such rays and fields of rays.

The collective interactions of weak plasmatic magnetic fields in the universe are considered to become the foundation and the cornerstone of the creation of initial fundamental particles.

In the universe, the same and regular specific sequential and consequential interactions of lower orders of magnitude plasmatic magnetic fields strength are always considered to lead to the formation of the plasma and its sub-Matters' components.

Throughout this book a clear distinction has been tried and been made between the magnetic field and plasmatic magnetic fields.

The **Plasmatic magnetic fields** are considered to be of *collection* of near *similar dynamic rays of* magnetic fields *strength*. We refer to the Plasmatic Magnetic Fields as "***pmtics***", *as Magnetic fields, which were detached from their source of creation*, hence, the use of the term "plasmatic" for these magnetic fields. For clarity: In this book the term "**plasmatic**" refers to a "collection" of dynamic magnetic fields, and **NOT** to the ***state of a plasma*** in its common term use that refers to a *state of dynamic protons*.

At the same time, pmtics interactions with other pmtics are considered to create effects the likes of gravitational fields and Magnetic fields of Matters, plasmas, planets and so on.

These magnetic rays or fields and their collection as plasmatic magnetic fields, become known as the **Initial Fundamental Particles.** Therefore we consider that magnetic fields to be the **"real" fundamental particles**.

The present science considers that the 'elementary particles' to be of 'quarks' and others. With the new understanding of creation of Matters and forces within the universal order of creation, in this book when the term **'elementary particles'** is used, this means that the **'magnetic fields'** are considered to be the **new** *'elementary particles'* and their forces. The existence and interaction of these magnetic fields leads to and creates all other effects that one sees and observes in the universe, like creation of Magnetic and gravitational fields which leads to creation of what I call different ***Matters*** *(Matter, Antimatter and Dark Matter)* of the plasma, or what presently is known as quarks and so on of the plasma. Where, we consider the Dark Matter as an integral and part of the same normal Matters of existence and as an important part of the construction of the initial fundamental plasma in the universe, and we do not consider the Dark Matter as an exotic and distant hidden Matter.

From this point on in this book, we refer to 'magnetic fields' as the ***'elementary particles'*** and *not consider quarks and others as elementary particles any further*, I consider that these quarks of different colour, with up and down notation and spin are all created as the outcome and consequences of different interactions and attraction of these 'magnetic fields' or 'plasmatic magnetic fields'. As quarks themselves are now known to be made of simpler particles of 'magnetic fields', then quarks cannot be considered to be the elementary particles.

In this book will be explained how 'magnetic fields' become to be the creators of quarks and other effects and forces within the plasma of proton, then the **'magnetic fields'** become the '**new elementary particles'** in the science of physics.

Further in this book it is explained how *different strength of these fields* leads to the creation of different **Matters and their forces** as has been observed by world of science.

Furthermore, these weak collections of pmtics and their interactions with magnetic fields and turbulent magnetic fields forces in different parts of galaxies manifest themselves as the seeds of atoms, stars, galaxies and so on.

Magnetic and gravitational fields (Magravs)

When we write **M**agnetic field (with capital M), we considered that these fields refer to the Magnetic field of celestial objects, like a Star, planet, etc. Where this Magnetic field is always accompanied with gravitational fields of the object.

Where we consider that ***gravitational fields and Magnetic fields*** cannot exist in the universe without each other, and that they are produced simultaneously. Through the same dynamic materials and Matters in the same region. Due to the construction of other Matters in their catchments area, these entities could have a different value than the other. As the Matter/matter content of the object dictates which will be stronger in strength and value than the other in that given position. The only known and possible objects that its gravitational and Magnetic fields could be equal in value strength, in majority of the cases in the universe, are objects of mono-material (like some stars), with pure hydrogen content. There are cases in the universe(s) that mono-matter of objects can be like uranium or heavier elements. These objects of heavier mono-matters are usually the producers of stronger gravitational fields and Magnetic fields, by several orders of magnitudes than the hydrogen mono-matter objects. It is assumed that each universe cannot possess more than one heavy material mono-magnetic star.

It has to be noted that the co-existence of these two fields always in interaction with any other magnetic fields or plasma of fields always lead to the creation of a ***magnetosphere***, which the boundary of the magnetosphere is the maximum point of balance or equality between the two field forces. Any variation in strength of one of the two fields in respect to the other will create different effects, for example such unbalance field between the two fields can be seen in Mercury, which has no atmosphere, and such a misbalance can also be observed in most moons of planetary systems.

In this book, as one field cannot exist without the other, for representation of the **MA***gneti*c and **GRAV***itational field***S** we use the term: "**MAGRAVS**".

Plasmas

We consider that " The **Plasma** in its **collective existence** is a combination of different initial fundamental Matters, which these Matters are created through the interaction of at least two or more of the same strength plasmatic magnetic fields (the initial fundamental particles)".

Plasmas (Chapter 3) are considered to be collection of combination of interaction of pmtics forces of Matters', Antimatters' and Dark Matters' and other magnetic fields forces, all at the same time and within an overall sphere of the confines of the plasma.

Further, in the process of interactions and collections of these initial pmtics with each other, in specific combinations, these leads to creation of atoms, molecules, matters and so on.

In this disclosure, simple connections between *Initial Fundamental* ***Particles*** and *initial Fundamental* ***Plasmas*** are explained and discussed.

These specific collections and interaction of initial fundamental *particles* and initial fundamental *plasmas* and their interaction with other magnetic fields manifest themselves as **states of matters**, these are purely magnetic fields densities and compactness environment dependent, and they present themselves as different states of matter (gases, liquids and solids).

Matter and matter

In the following sections, we clearly distinguish between *states of matter* (gases, liquids and solids), denoted as "**matter**", and *state of the Matters* (Matter, Antimatter and Dark Matter) denoted as "**Matter" or "Matters**".

Initial Gravitational Fields

The interaction of different magnetic fields of different strengths, upon each other, is considered to be the creator of initial gravitational fields for the start of the creation of the initial seeds of the Matters of the plasma (Fig. 8 B).

We consider that pmtics interact to create the attraction field or gravitational field.

Reactor technology

With the new knowledge and new first principles which are disclosed in this book about the creation of Matters' and plasmas', techniques acquired and reactor systems have been designed, developed and tested, it has become possible to replicate the pmtics of plasmas' environment that allows different Matters of plasma to be released from their interlocking magnetic fields forces within the confines of a reactor.

Further on, it has become possible within the structure of these reactors, to manage and control, these unlocked fields and Matters of the plasma, for specific predetermined functions and applications.

In these new reactors, in being able to weaken the Magravs of the plasmas (Coulomb magnetic or energy barrier) and by allowing the Matters of the plasma to be more free to move within the environment of the reactor. Where, these reactors were designed to facilitate the reduction in plasma magnetic fields forces and eventually to create an environment that Matters of the plasma can freely move in a soup of Matters, pmtics and rays. Where, through the operation of these types of reactors the famous Coulomb barrier becomes irrelevant in the overall structure of the soups of Matters binding magnetic fields of the plasma.

With these new methods of the manipulation of the structure of the Matters' of the plasma it has become possible for the pmtics forces of the plasma within these reactors to be unleashed, and with plasmas' constituent substructure loosen, it has become possible to manage to attain new powerful effects and properties from these rather weak initial fundamental magnetic fields of the plasma. Where up to the present time, these have been the unknown knowledge and methods in the world of science.

Within the structure of simple nuclear-based systems that have been developed, ***conditions*** *are created in which simple weak ambient dynamic pmtics, similar to the internal construction of plasmas, are generated.* The technology for creation of conditions similar to the internal structure of the plasma and methods which have been specially developed, that allows the loosening of the magnetic fields structure of the plasma, this will change the course of present nuclear fusion, and allows scientists in this field to achieve their goals *rapidly* and *at the fraction of cost* of present systems.

In the new state-of-the-art technology much simpler, softer and more practical ways, very similar to conditions as in the universe, are employed to attain fission and fusion of different Matters and plasmas.

During the reading of this book the reader will discover various future applications of this technology, so it will not surprise the reader that we have applied for several international patents to cover all aspects of the topics, principles, methods and systems mentioned in this book and the ones to follow.

Fission and Fusion by Plasma Dilution

The present methods of fusion and the Antimatter production technologies apply strong magnetic fields forces or high-speed rotation of the plasma, with low or limited success. As the real principle of the construction and structure of these sub-plasma Matters have never been understood correctly.

In our new state-of-the-art science and technology, one creates a control-conditioned environment within the confines of a multi-core reactor, which facilitates and allows the plasmas' Matters to ***disentangle*** themselves into their sub-Matters and pmtics components.

In these reactors the effects of the newly freed principal Matters of plasma's interactions with each other are utilised to create new and more powerful internal and external Magravs' forces, within and in respect to other plasmas and Matters in multi-core reactors system environments'.

In the new state-of-the-art technology reactors, after achieving desired goals, the system parameters can be changed so that the system can allow the same separated parts of plasmas' Matters to return to their original properties and regroup as the original plasmas.

This new method of loosening and the use of plasmas' Matters within the confines of a reactor is to be called the ***Keshe Theory*** of the "**Plasma Dilution**" and the art to achieve this "Plasma Dilution Technology"(Chapter 21).

This technology means that it is now possible to create an environment of weak magnetic fields within the cores' of a reactor, where the plasma is allowed to be opened-up and be released of the interlocking magnetic fields forces between its different constituent Matters.

The new dilution method in opening-up the plasma is a more practical and gentler methods for fission or fusion of the plasmas and/or its sub-Matters' components, for utilisation of their effects and properties.

In the present state-of-the-art technology in physics, scientists have chosen harsh method systems in fission industry. For fusion, they have chosen high speed and by compression of plasma, utilising giant magnetic fields induced technology to achieve their goals.

They use accelerators to slam the plasma on to a surface, to extract the sub-plasmatic components like the Antimatter component of the plasma (6, 7, and 8).

In the new state-of-the-art plasma dilution technology, within the confines of the reactors, environments and conditions are created, which are like a soup of weak pmtics, similar to the internal structure of plasma's own environment.

In this new approach, any new introduced plasma into the reactor, new **plasma's *binding* magnetic fields forces** come into an environment and ***interact*** *with fields* ***similar to their own plasmatic magnetic fields strength*** to allow their more condensed fields of interlocking Matter, Antimatter and others, to loosen and operate more freely in the environment of the pmtics soup of the reactor cores.

Using this new state-of-the-art science and technology, achievements of astonishing effects has been reported over the past few years. Where, with the current state-of-the-art technology, to achieve these effects, is considered to be nearly impossible and literally a dream and against the present known laws' of physics.

These effects reported, like being able to lift a reactor system weighing several kilograms by the use of a few grams of gasses, utilises the properties of the Antimatter components of the plasma's interactions with each other within the cores of these reactors.

This new technology makes it possible to produce in a very fast and easy manner nanomaterials and their constituent pmtics, like nano atomic layers known as graphene (sp2), diamond atomic structure (sp3) and nano-oxides, at room temperatures and atmospheric conditions, as has been independently confirmed by reputable organisation in the west.

In fact, all that has been achieved is the application of the understanding of how to use the soup principle to undo the tangles of magnetic fields of the plasma, and release of its substructure Matters, like Antimatter, in a reactor.

Lift and Motion by Magravs positioning

By utilising the properties of the interaction of forces of the collection of pmtics, interlocking between the Matters of the plasma and/or their sub-magnetic fields, which are part of the structure of the Antimatter and the Dark Matter, it has become possible to create stronger Magnetic fields, or gravitational fields' forces within the confines of and in respect to the surrounding environment of multiple-core reactors'.

These Magravs, if strong enough to interact with similar fields in their environment and with other fields of the same components of plasma in other parts of the same reactors, these Magravs interactions' of the system and the planet can cause lift and motion of the mass of the system, which the reactor is attached to.

Scientists at the Fermilab (6) in the USA state that small amounts of Antimatter, as little as a spoon-full, can release enough energy equivalent for the launch of several shuttle flights. This laboratory has confirmed that they have managed to collect some of this Antimatter in the past forty years, using special plasma separation and containment methods.

Utilising the new plasma dilution simple methods', not only are the Antimatter components of the plasma separated but, at the same time the interaction of the magnetic fields of these Matters are used within the system for the creation of strong Magravs within and in respect to their environment, for creation of lift and motion.

The newly created Magravs in these reactor cores, in interacting with the surrounding planetary Magravs and in trying to find a new Magravs balance, for example, in respect to the Earth fields, causes the system to move.

This method of achieving system motion due to interaction of Magravs forces is to be known as the ***Keshe principle of Magravs positioning*** *(Chapter 19)*. This position is, the point where the combined gravitational and Magnetic fields strength of the reactor system and the Earth, find a new position, where they are in balance strength in respect to each other.

After achieving the required Magravs positioning, this being the new height and/or distance, in respect to another Magravs force like that of the Earths Magravs, the systems' internal parameters can be changed again to create a new Magravs strength within the reactor. At this point, a new Magravs positioning balance needs to be attained by the system in respect to the planet. This, forces the system to find a new Magravs balance in respect to the planet Magravs' strength, and consequently for the need for the system to achieve the new Magravs positioning in respect to Magravs of the planet.

In attaining a new Magravs positioning balance, this leads to the movement of one system, in respect to another.

Thus through this new Magravs positioning method, motion of crafts, cars and systems for energy production can be attained *without burning* any fuel or using the present propulsion technology for lift of relatively small payload into space.

Through Magravs positioning principles, this is how ***motions*** *of atoms, planets, and stars and so on, are created and achieved in the universe (Chapter 19).*

Through tests, we can confirm that, the motion of any mass for any Magravs positioning system is not size dependent, but mass dependent, where the smaller mass always tends to move in respect of the larger mass in the universe. There are some exceptions in respect to this rule of the thumb. As in Magravs positioning reactor systems, where gravitational field strength control within the cores of the reactors plays a major roll to achieve lift, motion and Magnetic field protection of the system.

As I have said before "no one has ever seen a rocket in the back of the Earth that has been causing its motion for billions of years".

Subsequently, if necessary, through the same changes in internal parameters of these new reactors, the components of the Matters' of the plasma are and can be allowed and be facilitated to regroup and return back to their original structural state of pmtics levels of Matters and composition, once the desired affects are achieved.

Through new understanding and new state-of-the-art technology and by simply following the methods and universal orders of creation of Matters, the components of plasmas' Matter, Antimatter and Dark Matter can be manipulated and utilised for effective lift and motion of objects, creation of energy, production of new Matters and so on.

By the release of this new knowledge, this does not mean that the paths chosen up to now by other scientists have been wrong; this is by no means so. Nevertheless, their achievements have been and are limited because of the focus on the use of the **matter**; it's state of gases, liquids and solids, and even a limited view on plasma (as the fourth state-of matter) rather than our approach in use of the **Matters;** it's state of Matters, Antimatters, Dark Matters with their different pmtics strength components of the plasma.

With the use of the matter, one has to burn fuel to overcome gravitational field forces to attain a new position in respect to the planet. However, "with *Magravs positioning systems* one uses the pmtics of the Matters of plasma (Matmags) to create Magravs forces within the reactor, for the reactor system to *move within* the Magravs forces of another object, like the Earth, for the system to attain a position in respect to the Earth Magravs forces."

We consider that as much as there are Magravs forces between Matters, the same is true for the existence of Magravs forces between the Antimatter and the Dark Matter components of the plasmas too. This principle applies the same in respect to the inertia of Matter as much as to inertia of the Antimatter and the Dark Matter components of the plasma.

That is to say, in the universe there are Antimatter Magravs forces and Dark Matter Magravs forces as well as inertia for all three Matters.

All Matters and their effects can be used for the creation of motion and energy production in conjunction with other matters and Matters of the plasma.

Our newly released knowledge is for achieving and reaching the same target as other scientists and institutes, but with new knowledge about the construction of Matters of the plasma, we are achieving more profound and stronger effects, in simpler and less complicated ways than have been chosen in the past.

We see this release of new knowledge and technologies as an addition to the rest of the past and present scientific works, and a breakaway from the complicated ways and harsher methods.

In this disclosure, one comes to understand how Matters and matters are made from the start of time (Chapter 3). Where, the method of creation of plasma and atoms in the universe is explained in a simple form.

Then one can see how to use the inner construction of Matters' pmtics to generate vast amounts of energy and learn to use magnetic fields principles of interaction that are the fundamental principles' in the universal method for creation of motion.

We have tested the Magravs positioning systems for motion, and the results confirm the correctness of the theoretical aspects of the approach. The future of space technology will be based on simple safe portable Magravs positioning nuclear-based reactors, which have been developed and tested.

CHAPTER 1

Historically unexplained principles

The main reason for the lack of understanding of simple processes of creation and control of Matters of the plasma is not so much the lack of knowledge in the scientific world in the past or present. Rather the lack of progress is by large due to, the peer review obstruction mechanism, which has been put-up, for some scientists, to protect their individual financial interests and titles, in their schools of thoughts in their field of science.

For example, despite having huge research budgets and human resources, the world of science in respect to understanding of the simple structure of the plasma and its fusion, has not reached substantial results in the past sixty years. Where, nuclear physicists and industry have been trying to cause fusion of plasmas of hydrogen atoms, in fusion reactors, which have been built, and are being built at costs of billions of dollars.

The structure and working of these state-of-the-art fusion reactors are built against the natural laws of physics and opposite to the way, that fusion of plasmas takes place in the universe. Where, these reactors operate with near zero-gravitational field forces within their structure in trying to achieve fusion. Where in these systems, the natural internal gravitational field forces needed for a simple fusion is missing.

What they miss as the natural gravitational field forces needed for fusion, they try to replace this with the use of strong external electro-magnetic fields, by the use of large massive coils and huge amount of energy to operate these systems, and then the they try to achieve fusion. This is like as they are trying to bake bread with only water, salt and heat, without having its main ingredient, the flour. The question to ask from these scientists, is simply that, where are the gravitational fields essential for fusion in these reactors, and where is it suppose to come from, if there is going to be a successful fusion chain process as in the middle of the Sun, which, these forces are in thousands of G‘s.

In fact, with the use of giant external magnetic coils, they squeeze plasmas into tighter balls and then they try to fuse two hard balls of plasmas together. This is the reason why, they have and will achieve very little, if the present misguided path of fusion technology is to continue.

Another point is that the present twenty-first century advanced world of science is lead to believe and to accept the outdated 19th century principles of creation of Magnetic fields through convection principles in the centre of the Earth. Even, when scientific seismological data’s (1, 2, 3, 42A, 42B) indicate that another explanation is needed.

For example, some peers consider that man in the 21st century is not intelligent enough to discover how gravitational fields of planets are created. According to these peers, the principle of creation of gravitational field forces and their control at present is beyond comprehension of other scientists.

Where, as new Magnetic and gravitational fields positioning systems, which have been developed and tested, confirms the ability to create lift and motion by just using the effects of Matters magnetic fields (Matmags), without burning any fuel or use of propulsion technology.

Within the present 21st century knowledge and proven science, there are a number of unacceptable points from these earlier centuries accepted principles like the creation of the magnetic fields of planet through convection principles.

New theories and principles for these misassumptions, unexplained and out-of-the-hat principles are explained and discussed in the following sections and chapters.

In the following four sections in this chapter, it is important to note that:

Information that have been obtained through the earth-quakes seismological data over past thirty years from around the world, these data points to the fact, that what has been assumed to be the ***solid inner core*** *of the planet* and to be made of one piece solid metallic matter (Fig. 1), this core in fact has *a **cavity** in its centre* (Fig. 1) (1, 2, 3, 4, 5, 41A, 41B). This newly discovered cavity in the solid core of the planet has been called by geologists the 'inner-inner' core of the planet and is assumed to be about at least over 500 km in radius in the centre of the inner solid core of the planet.

I have called this new core, "***The Caroline Core***" (Fig. 1, 2 and 3), to distinguish it from other presently known cores' of the planet (12).

1. The creation of Magnetic Fields of the Earth

The assumption of the creation of the Magnetic fields of the Earth by scientific world has been based on the understanding of the working of the dynamo principle of earlier centuries. Where, the process of the production of the current was accepted to start-off with the motion of high temperature fluid of matters in the outer core (Fig. 1), in the centre of the Earth by heating and liquidity of matters in this core.

Where electrons of atoms of matters are considered to be released or loosened from their atoms to be free to vibrate or float in this region, and as the rotation of the solid metal inner core (Fig. 1) of the planet interacts with these free electrons in the outer core of the planet, this leading to the creation of Magnetic field of the planet (Fig. 1 Field M).

If this assumption is totally correct, then how do other planets and stars create their Magnetic fields?

Stars like the Sun, possess Magnetic fields and yet do not have solid inner cores as the Earth does. The Sun definitely generates Magnetic fields, which does span beyond the

Earth and the Saturn.

The first flaw with this convection theory of electrons motion is that, we know now **that plasma of an atom** is a charged entity **and possesses much stronger charges** by several orders of magnitude ***than its smaller counterpart electron***.

Thus, the main Magnetic field force of the planet is more feasible to be created by the plasma charges rather than electrons charges. With the knowledge we now know, that even the electron is a plasma condition similar to the proton construction (Chapter 3, 17, 18 and 19).


First magnetic field
Second magnetic field
OC1
OC2
M1
M2
CC1
CC2
M
Magnetic field of the Planet
CAROLINE CORE
(Inner inner Core)
Geo-Reactor
INNER CORE
(Solid metallic inner Core)
OUTER CORE
(Liquid Core)
CRUST

Fig. 1: Two interacting plasmatic magnetic fields in the inner cores of the Earth lead to the creation of the Magnetic field of the planet.

Note: The Caroline Core, can contain plasmas, atoms (nanomaterial), molecules, different matters, hydrogen, potassium, uranium and plutonium due to nuclear decay, fission, possible fusion, ionisation of matters, leading to the creation of heat in this core, which is transferred through the solid inner core to keep the materials content of outer core in fluid state.

Through current knowledge in plasma physics and studies in the nuclear fusion industry, it is a known fact that dynamic protons (plasmas) of atoms are positively charged entities and do generate their own currents, through what is known as the Birkeland current principle. It is through this principle of creation of current and the dynamism of plasma in the centre of stars that main solar Magnetic and gravitational fields forces of stars are created, and not the convection principle.

Secondly, if we have plasma in the centre of the planet, which is possible, then the convection theory for the production of Earth's Magnetic field has limited validity, and it is possible that some of the Magnetic fields of the planet are partially created by the convection principles method too.

2. Creation of the Gravitational Fields of the Earth

The other major concept, which is an obstacle to the development of new knowledge, is to understand how gravitational fields of planets are created. This is a concept that has not been understood until now. Where, the creation and maintenance of gravitational field's forces in stars and planets have unnecessarily made been by the scientific world into the holy grail of science.

In fact, the creation of the gravitational fields of planets and stars in the universe is as simple as the creation of their Magnetic fields.

The hypocrisy with this is that the scientific world and an infant child (at school age) agree on one principle, that, two dissimilar poles of solid magnets, gets attracted to each other and pulls one magnet to the other, or they have gravitation in respect to each other. It is an accepted fact that, opposite poles of magnetic fields forces can interact to create attraction field forces or the gravitational fields forces in respect to each other and other matters around them.

Thus, it is correct, to assume that, to have a gravitational field in a planetary system, the gravitational field forces must be made similarly by the same principles of attraction and interaction of at least two magnetic fields, in the centre of the planet in respect to each other. Therefore, the gravitational fields of the planet must have been made by interaction of two or more sources of magnetic fields in respect to each other in the centre of planets or stars that can span beyond the physical boundaries of these objects.

By the reality of the existence of the Magnetic and Gravitational field forces around the Earth, this leads to the confirmation and understanding of a need for two independent regions that can create magnetic fields forces within the structure of the planet inner cores, that, their interaction leads to the existence of the gravitational field forces of the planet.

Consequently the Earth, being in possession of gravitational fields, this confirms and indicates to the existence and operation of at least two independent magnetic fields forces regions in the centre cores of the planet (Fig. 2, fields G1 and G2).

Where, the interaction of the two magnetic fields (Fig. 2, fields G1 and G2), which are generated in the centre cores of the planet, upon each other, leads to the creation of attraction or gravitational field forces of the planet, similar to the attraction fields of opposing poles with solid magnets.

It is a known fact that, planets and stars are made of different layers of different materials. Similarly stars are made of the same material (Hydrogen), which, due to variation in the compression and temperatures, layers are created in these objects, where the same matters in different layers create and behaves and show slightly different properties and effects; These different layers produce their own slightly different in strength magnetic fields force, compared to their adjacent layer magnetic fields strength. Thus, the layers of plasmatic or fluid materials in different depth of stars and planets, each layer create their own independent magnetic fields in the centre of planets or stars.

The magnetic fields created in each dynamic layer in the cores of these celestial bodies, due to the proximity have no alternative, but to interact with the magnetic fields generated in ascending or descending layers from them. The interactions between these magnetic fields in different layers are considered to be as or similar to a solid magnets state magnetic fields interactions.

In the case of stars and planets' inner cores, magnetic fields are created by and in plasmatic states or fluid states of Matters. Where, these flowing dynamic materials in the inner layers of celestial objects cannot physically lock to each other through the magnetic fields generated by each layer, as it happens with solid-state magnets. This being due to fact that atoms and molecules in these layers are continuously in motion and are pushed around by other forces and the rest of the Matters in their given layers or by other layers effects and forces.

Nevertheless, the magnetic fields created by each dynamic layer interact with the magnetic fields of the adjacent dynamic layer or layers. These interactions of magnetic fields in different layers creates attraction magnetic fields, as much as, repulsion Magnetic fields forces, in between the materials in the different layers.

Therefore in the same regions and by the same matters, **similar magnetic fields polarities** in different layers interact and two similar polarities magnetic fields forces (Fig. 1 field M1 and M2) repel each other. This repulsion magnetic fields forces (Fig. 1 field M1 and M2) becomes' the ***outwards field force pushing*** and what is known as the ***Magnetic field force*** of the planet (Fig. 1 field M).

Further, the *opposite polarities magnetic fields* in these layers at the same time, interact simultaneously and in a similar way, and the interaction of **opposite magnetic fields** polarities of matters in these layers (Fig. 2 field G1 and G2), leads to the creation of the different layers magnetic fields pulling or attraction in respect to each other. This attraction magnetic fields force (Fig. 2 field G1 and G2) becomes the ***inward field forces pulling*** field force and what is known as the ***Gravitational field force*** of the planet (Fig. 2 field G)(18).

Through tests done over several years with the construction of similar set-ups as in the inner cores of the planet, the ***Keshe Theory of creation of gravitational field*** of dynamic objects in possession of dynamic cores states that:

"***The dynamic outward' Magnetic fields forces of planets and stars are created by interaction of the same materials and in the same layers, as their dynamic***

gravitational fields forces”.


Second magnetic field
First magnetic field
G1
CC1
CC2
OC1
OC2
G2
G
Gravitational field of the Planet
CRUST
CAROLINE CORE
(Inner inner Core)
Geo-Reactor
INNER CORE
(Solid metallic inner Core)
OUTER CORE
(Liquid Core)

Fig. 2: Two interacting plasmatic magnetic fields in the inner cores of the Earth lead to the creation of the Gravitational field’s forces of the planet.

The ***Magnetic fields forces*** of the planets are made from the interaction of similar polarities of plasmatic magnetic fields of Matters in the dynamic layers of its inner cores (Fig. 1 field M) and these radiate themselves ***outward***. The ***Gravitational fields forces*** (Fig. 2 field G) are created by the interaction of the opposite plasmatic magnetic fields polarities of the same Matters in the same layers in the cores of planet, creating the pull or ***inward*** attraction in these celestial objects”.

This new understanding of interaction of multi-magnetic fields in the planets inner cores brings about a new definition, new understanding and new explanation of how gravitational field forces are created in centrally dynamic multi-inner-cores celestial objects in the universe the like of the Earth and the Sun.

Gravity can now be defined on the real basis and what leads to its manifestation, strength, existence and control.

Therefore, Gravitational field forces are magnetically based fields, and thus according to ***the Keshe Theory of Gravity***, Gravity is defined as:

“***The Gravity is, the measure of the interaction and attraction of two or more, magnetic fields forces or dynamic plasmatic*** strength created within the second system”(18).

This is the same as Newton's definition of gravity, with the extension however, that two Matters or matters cannot possess pulling forces nor have gravitation in respect to each other position, without the existence of magnetism.

Certainly, the attraction and interaction of pmtics forces changes with respect to position of two objects and they are distance and fields' strength dependent.

If the celestial objects do not possess magnetic fields strength that can interact with each other, then, how could they be attracted to each other?

Thus, gravitational field now can be understood and explained in its real terms of what creates it, and this is due to interaction and attraction of pmtics created within dynamic cores of celestial objects in respect to each other.

Secondly, as the gravitational fields of these planets or stars are magnetic fields strength dependent, one can now understand why their attraction is position dependent.

Therefore, *gravity in a simple form can be defined as; that gravity or gravitational fields forces are the measure of the interaction and attraction of two or more magnetic rays or magnetic fields systems of two or more entities in respect to each other's strength and position at any point in the Matter, plasma, matters, planets, solar systems, galaxies and universe.*

This new definition of gravitational fields is an extension to the present knowledge and due to new understanding of the plasmatic magnetic fields interactions between components of Matters (see Chapter 3).

Another proposition can be that: We further can assume that the cell of a human or matters of other objects, which all are made of atoms and plasmas and of magnetic fields can/are/or behave as the possessor of the second magnetic field in respect to any other plasmatic magnetic fields in their environment. Therefore, it is possible that pmtics of these cells and matters in their interaction with the dynamic pmtics of the planet can behave and replace the interacting double magnetic fields system principles necessary for the creation of gravitational phenomenon principle to operate.

Further it can be said, that any substance in possession of plasma or nuclei has gravitational attraction in respect to the planet.

If this is correct and applicable, then, this can be another reason why, a singular Magnetic field of a planet can be enough to create the gravitational field pull in respect to any object within the catchments zone of the Magnetic field of the planet's. That is to say, a single Magnetic field would be sufficient for the gravitation of plasma to the planet to be created and exist.

Nevertheless, there could be a flaw with this concept, as one need the gravitational and magnetic fields (Magravs) together to be able to have a constant free motion and position option of the two objects too.

In this book, we try to make a distinction between *magnetic fields of matters* and *Magnetic fields created by* dynamic interaction of two magnetic *rays*, two *magnetic fields* or *two pmtics*. Where, in the case of like **plasmas** and planets *Magnetic field* and *gravitational fields*, which they always accompany each other we use **capital M** as **Magnetic field**. In these references instead of writing **Ma**gnetic and **grav**itational field**s** we write in short as "**Magravs**" ***magnetic fields forces in respect to each others position***".

"Where, the Gravitational field force of one celestial body in respect to the other is a measure of the attraction and of the interaction of one plasmatic magnetic fields strength created within one system in respect to another plasmatic magnetic fields.

3. The source of the Heat in the Earth Cores

Another unanswered question in geophysics is that, where does exactly the heating of the inner solid core of the planet Earth comes' from that can keep the outer core materials in their fluid state? Secondly, how and through what method is heat generated in the inner cores of the planet?

These questions have not been addressed fully with clarity up to the present time in the science of the planet.

In general, it is an accepted fact that the Earth maintains heating of its inner cores. I consider that the Caroline core is a Geo-nuclear reactor (Fig. 1, 2 and 3) to be known as the **Geo-Reactor** (Fig. 2). It is not hard to assume that there are radioactive matters (41C) in this new central core of the planet (12), which leads to the heating of the inner cores of the planet. In general, nuclear geophysicists and myself agree upon this, up to certain degree, with difference in the content of the matter types and the process by which this heating is generated.

Where, geophysicists mainly consider that the heat in the Caroline core is generated through the nuclear decay of heavy elements, which have sunk into the centre of the planet due to their weight.

As a nuclear engineer having built several simple nuclear reactors replicating the structure of the inner cores of the planet Earth and achieving the same effects of creating Magravs similar to of the Earth, I believe, Matters, plasmas, hydrogen atoms, carbon atoms, radioactive matters and other matters collectively are parts of the mixture of the matters content of the Caroline's core (12).

One can now clearly explain that the major contributor to the generation of heat in the inner cores of the planet are, or can be due to nuclear decays, operation of plasmas, nuclear fission (41C) and possible nuclear fusion of materials in the Caroline core of the planet.

Materials in this region of such a high temperature are, and can be, considered to be in the fluid state (12) as has been considered by present geophysics scientists in respect to the condition in the outer core materials of the planet.

Matters in this region, due to their fluidity, can be considered to be able to produce their own dynamic magnetic fields (Fig. 1 field M2 and Fig. 2 field G2), due to the *dynamic motion of fluid matters* in this section of the planet and these fields can/and interact with the dynamic solid inner core of the planet (Fig. 2). This being in principle similar to what has been assumed by geophysicists, that to be happening in between the **inner core** and the **outer core** regions of the planet matters leading to production of Magnetic field forces of the planet at the present time. Secondly due to the *charged plasmas and charged electrons and their motion in this core, these could be partially responsible for the creation of the second magnetic field force of the planet.*

By the discovery of the second cavity, the Caroline core, in the inner cores of the planet, it becomes clear that the **second magnetic fields** (Fig. 1 field M2 and G2) can be, and are created in the very centre of the planet. Where, the solid core of the planet will act as a separating partition wall, between the two dynamic matter regions in the centre of the planet, namely the fluid matters in the Caroline core and the fluid matters in the outer core.

So, the holy grail of the gravity (18) can be explained by the principle of interaction of two dynamic magnetic fields sources in the centre of the planet as was discussed in the above section. Therefore, the interaction between two pmtics on either side of the solid core is the source of the plasmatic Magravs of the planet.

4. What causes the Rotation of the planet Earth?

Another unexplained and daily-accepted phenomenon is the rotation of the planet Earth. How is the rotation of the planet Earth created and maintained? What causes and dictates its constant speed of rotation of the planet, irrespective of where the planet is in its solar system?

The way and how the rotation of a planet is created, has never been explained in the past by world of science.

The existence of two independent pmtics forces (Fig. 1 field forces of M1 and M2, and Fig. 2 field forces of G1 and G2) on either side of the inner solid core of the planet (Fig. 3) can help to explain the next mystery in the world of geophysics, through the ***Keshe Theory of "The principle of the rotation of the planet"***.

Magnetic fields are known to possess *field forces* that can exert pressure on an object, and are capable of causing its motion.

The existence of, and the continuously maintaining and interplay of the two dynamic pmtics forces (Fig. 1 fields M1 and M2 and Fig. 2 fields G1 and G2) on either side of the inner solid core of the planet, partially goes to answer the sources of the fields that exert forces on the inner solid core of the planet that causes the motion of the inner solid core.

It has been explained that the interaction of two dynamic magnetic fields on either side of the inner solid core, leads to the creation of Magravs forces of the planet. At the same time the interaction and exertion of the same magnetic fields forces on the inner solid core of the planet put magnetic pressure on the inner solid core of the planet, causing the motion of the inner solid core of the planet (Fig. 3 fields G1 and G2). In the figure 3 the total and overall effect of Magnetic field and Gravitational field forces of each core on the inner solid core are denoted as G1 and G2.


Second magnetic field
First magnetic field
G1
G2
CC1
CC2
OC1
OC2
Magnetic Force
Magnetic Force
Rotation
CRUST
CAROLINE CORE
(Inner inner Core)
Geo-Reactor
INNER CORE
(Solid metallic inner Core)
OUTER CORE
(Liquid Core)

Fig. 3: Interacting plasmatic magnetic fields in the inner cores of the Earth leads to the creation of the rotation of the planet.

As the solid inner core confines' the materials in the Caroline core (Fig. 3) and the outer cores materials are confined by other matters at the outer boundaries of this core (Fig. 3), these two cores are considered to be holding a constant volume and weight of matters. Thus, it is possible to assume that the magnetic fields forces created by each core will be constant and these magnetic fields forces will be maintained on either side of the inner solid core of the planet for a long period of time (billions of years).

Hence, the *balance of magnetic fields forces* exerted on the metallic inner solid core, by both magnetic fields on either side of the inner solid core, will determine the speed of rotation of the solid core of the planet.

Consequently, through the principle of viscosity and friction of the matters inside the planet, the final speed of the rotation of the whole planet is considered to be set and be due to the motion of the inner solid core of the planet. Which is carried out to the outer layers of the planet and becomes the final rotational speed of the planet.

Therefore, the speed of the rotational motion of the planet is determined by the planet's internal cores magnetic interactions upon the inner solid core of the planet and by large, this speed of rotation is **irrespective** of the position of the planet in its solar system and overall effect of the external Magravs forces, which are exerted by other planets, and the star of the solar system, on the planet.

So the twenty-four hour speed of rotation of the Earth is totally dictated by the exertion of the magnetic fields of the other cores on the solid inner cores of the planet as has just been explained, and not necessarily by any other factors.

This principle of constant speed of rotation of celestial object should hold true for the all-dynamic celestial objects that are in possession of dynamic thermal central materials cores and this rotation is irrespective of the temperature of the inner cores or temperature of the outer layers and surrounding environment of these objects.

Through tests in laboratory of similar reactors as the construction of Earth inner cores, we have concluded that the **speed of rotation of celestial objects and Matters** and the **creation of Magravs strength** are **temperature independent**.

The motional rotation of a planet is created through the same principle as the linear motion that is attained in the present Maglev magnetic railway system of Japan, with the difference that, due to *spherical shape* of the inner solid core of the planet (Fig. 3), the motion created in this case will be a rotational one (12) rather than linear. We can consider that this principle is universal.

5. The difference between Matter and matter

Another unexplained phenomenon in the world of physics has been the understanding and the difference between the Matter and the matter, one in respect to the other.

In this book we make a clear distinction between **the Matters** and **the matters** in all levels of universal orders of materials, where;

The **Matters** are understood to be as the like of the Matter, the Antimatter and the Dark Matter. These three Matters are all made of ***different*** *plasmatic magnetic fields strength* and are ***field strength*** dependent in respect to each other. The three Matters are the three major components of a plasma. Each of the three Matters have pmtics of another strength, where the constituent strength of the pmtics creates different Magravs, different magnetosphere field strength and different mass for each Matter, and these independent of the other two Matters within the plasma, and independent of the environment that surrounds the plasma.

Whereas:

The **matter** refers to the Matter component of the plasma. Matter becomes matter, when the Matter comes to levels that **plasmatic magnetic fields forces** and the ***motion*** *of these forces* in their environment can determine the compactness of the components of the Matter pmtics appearance in the plasma that make the matter appears as a gas, a liquid or a solid ***state-of-matter***. These forces being created due to interactions of Magravs, dynamism of the environment, and so on.

At the same time, Matters are pmtics strength, contact friction dependent. Where, the friction of pmtics in matter usually leads to the change of the state of the matter through the change of plasmatic magnetic fields forces to the likes of light, heat and other's.

It is the **external field forces** and ***not the field strength*** of the environment that dictate the compactness of any of the plasmas' Matters so that the pmtics becomes matter and visible or tangible to human senses, like odours or appearance of Matter as solid, gas or liquid, it is then that the ***Matter*** comes to be called the ***matter***.

The principle of ***strength*** of the magnetic fields of Matters is very different than the strength of magnetic fields in matters.

When we consider to work with Matter(s) for space technology, the term "**fuel**" is not applicable, therefore the use of the term "**MAT***ter* **MAG***netic* **S***upply*", abbreviated to "MATMAGS". This is a Matter (Matter, Dark Matter, Antimatter) ***source of pmtics*** used in reactors for the production of Magravs for the operation of gravitational positioning reactors, where one can state the Matter needed and the strength of the Magnetic fields of the Matter needed to achieve desired effects from the reactor.

Since "fuels" only refer to the *matter level*, where fuels are usually *burned through ignition of matters*, whereas ***magnetic fields of Matters***, in the form of Magravs, are manipulated to create a preferred effect, and where the magnetic fields can be reversed back to any other state of Matter, and they are never lost. The only difference would be that with the Matter supply the magnetic fields strength can differ after processing, but in reality one would be left still having magnetic fields of varying degrees in strength.

6. How motion of matters and Matters are created?

The question to be asked first is, that, how the Matter, the Antimatter, and the Dark Matter are created in the universe.

Secondly, how are the regular independent motion of **Matters** (Matter, Dark Matter and Antimatter) and **matters** (electrons, atoms, matters, planets, stars and galaxies) in the universe without burning of any fuel created and maintained?

No explanation has been put forward by the scientific world that is realistic, fundamental and applicable in all levels and to all sizes of objects and in any position in the universe.

In the following chapters of this book, I will disclose how **matters** (gasses, liquids and solids) and **Matters** (Matter, Antimatter and Dark Matter) as part of fundamental elements of creation, move in the universe. In addition, it will be explained, how the plasmas, electrons, planets and stars attain and maintain their motion in the span of the universe. (Chapters 19)

Motion in the universe is achieved by understanding in full that how the construction of Matters happens at their simplest form, from the inception of the initial fundamental particles how they come together, and how they respond to each other's magnetic fields forces, that the interactions of all constituents Magnetic field forces in Matter and plasma of Matters, leads to the creation of motion of plasmas, electrons, planets, stars, and so on.

7. How Light is created?

The present science of physics accepts that the light is created through the drop in energy of an electron from one energy level to a lower, or its ground energy level.

Further, in this book we will explain how light is created in the universe, where actually there are *no electrons present* in the plasma-saturated environment.

The other unanswered question is whether the speed of light (C) is the ultimate speed in the world of Matters.

The speed of light is in the world of science thought to be the ultimate speed that any Matter can travel.

I consider this assumption to be **incorrect** for all states of Matters (Matter, Dark Matter and Antimatter).

The assumption that the speed of light is the ultimate speed can be correct **only** for *interactions between matter and Matter component* of the three basic Matters (Matter, Antimatter, and Dark Matter).

I consider that the **plasma** is to be in **possession of all three states of Matters,** these being **the Matter, the Dark Matter and the Antimatter.** (See the cover image of the book)

Secondly, the assumption that the speed of light to be the ultimate speed, can at the same time be partially correct and applicable, only for a limited fraction of time for specific conditions of **matter** (and not necessarily only in vacuum conditions). Where **matte**r itself is only a small part of bigger components of Matters of plasma in the universe.

There are too many physical facts that are present in the mechanism of the universe's daily operation that rejects that the speed of the light being the ultimate speed. These new theories will be discussed further in Chapter 7, titled "Speed of light". A large numbers of physicists around the world do not accept such a limitation on the speed of matters in the universe.

CHAPTER 2

Interaction of Plasmatic Magnetic Fields (pmtics)

In the Matters the strength of the magnetic fields goes back to the origin of the creation of magnetic fields. Where, the strength of the magnetic fields is in terms of reference, the power of the magnetic fields. Where magnetic fields in essence are created out of the potential difference in position from their source and the rate of the flow of the magnetic fields from their source becomes the current of the magnetic fields. Thus, as the position is closer and the rate of the flow is higher, the stronger the strength of the fields. This principle of creation of magnetic fields and magnetic fields strength are explained in full in the paper titled "The creation of magnetic fields".

In understanding the ways and the simplicity with which the gravitational field force of plasmatic conditions are generated and maintained in planetary and stars systems, we can now state that the method of creation and production of the Magnetic fields and gravitational field forces of galaxies, stars, planets, molecules, atoms and plasma are all considered to be through the same method, irrespective of their physical size.

At the same time, it is important to appreciate that this applies to all scales of the universal order of creation. That is to say, stars are made of the denser, larger and stronger by order magnitudes of plasmatic magnetic fields strength forces in the universe. Compared to the plasmas and the electrons, which are made of a weaker order of magnitude of plasmatic magnetic fields strength forces.

Nevertheless, the same principle of structural formation applies to the Magravs structure of stars as to the structure of an atom, the plasma and the electron.

In the physically big state order of matter, large scale, stronger and denser magnetic fields can be easily observed and detected, like the magnetic fields of the Earth, the Sun or the Galaxies.

By the same measure and the same order of the scale and magnitude, plasmas and electrons possess and are made of and follow the same principles of Magravs interaction and attraction, and hold on to their different Matters and forces, as a star or a galaxy does.

Whereas, the existence of the lower order of the magnitude pmtics that make the physical structure of plasma due to their very weak magnetic fields strength, can mainly be confirmed through the physical existence of the plasma itself, its behaviour, and its properties.

Through our own tests, which have been done over several years, it is apparent that the plasmas possess their own Magravs forces, which are made from the interactions of combinations of different pmtics forces within their structure.

The fact is that, if the plasma did not create and maintained Magravs forces internally, it would not have been able to hold on to its fundamental particles, for the plasma to exist. By the ***Keshe Theory of the Gravity***, the existence of Magravs forces as the existence of a magnetosphere of the plasma confirms the existence and interaction of at least two plasmatic magnetic fields forces within this structure.

Secondly, if the plasma did not possess Magnetic field, it would get stock to other plasmas in its environment, these environments being for example the like of the other plasmas in the nucleus of heavier atoms. Then as the plasma is a free motion entity, which keeps distance from other plasmas in its environment, this confirms the existence of Magnetic as well as gravitational field's, which is internally maintained and emanated from the plasma itself.

Unless it can be proven to the contrary, we can assume that all plasmas are made of the same types of pmtics, and the same structural Matters and the same structural configuration. Then, we can say with confidence that all plasmas are made of identical Matters and create the identical Magravs forces within their structure.

We consider neutrons, protons and *especially* electrons as being of plasma structure with only difference in their pmtics content level. Thus, different atoms of different matters have different energy and physical pmtics properties from other atoms purely due to the level of total pmtics of their total plasmas that they can hold onto.

From this point on, in this book, it is considered that all **hydrogen atoms** have and will always be in ***possession of the same properties***, be of ***the same construction*** and be made ***of the same similar internal pmtics and Matters***.

Therefore, it is assumed from this point in this book that what we call initial fundamental plasmas, or what is called neutron, must always be made of the same composition and of the same specific pmtics at all times, for all such plasmas of all atoms.

Furthermore, it can be said that all initial fundamental plasmas create the same and similar plasmatic Magravs forces.

Until contrary to this fact is proven, then it is correct to assume that majority of plasmas have the same characteristics, the same properties, and have the same dimensions, and the same measurement of Magravs density and field strength.

Therefore, it is right to assume that the *majority of plasmas* in the universe are all made of the same collection of pmtics interactions.

Hence, it is correct to assume that to have plasma of specific characteristics and specific Magravs strengths; the plasma is made of and must be able to attain a Specific Magnetic Configurations for all initial fundamental plasmas.

From observation of motion of plasmas in the universe, it is clear that not all packs of pmtics are connected to a specific source. They are mainly free floating in space and are made of different magnetic fields strength.

Where, some of these pmtics interact with others of the *same strength*. Which, these interactions lead to the creation of the plasmatic Magravs, in their space and in respect to other floating pmtics in their given environments.

Initially, when pmtics of similar strength get close to each other, the interacting fields get entangled with each other and set-off a new cycle of Magravs in respect to other pmtics and magnetic fields in their given environment.

Further on as more pmtics of different field strength are gathered together due to their initial magnetic fields strength the new seeds for creation of new and different Matters are set to start. Where, the collection of these different Matters and fields and their interactions leads to the creation of initial fundamental plasma, in a specific given position in space.

Plasmas are always considered to be made in the same manner, by the same process, by the collection of the same pmtics force strength and the same interaction procedure of the fields within their structure.

Hence, plasmas are said to be made of **S***pecific* **E***ntangled* **P***lasmatic* **MA***gnetic* **F***ields* (SEPMAF) and this is considered to be the same for composition of all plasmas in general.

CHAPTER 3

The Initial Fundamental Particles of the plasma

The **initial fundamental particles** components of plasma are considered to be ***a collection*** *of weak* **plasmatic magnetic fields** (in short: pmtics) originally existing in the spans of galaxies.

These are **residuals** of different plasmatic magnetic fields activities of matters and Matters, which are released by the interaction of different magnetic fields by/and through for example processes like fission and fusion within stars and so on. It is considered that some of these ***weaker*** plasmatic magnetic fields are *released into the environment* by the nuclear decay of atoms themselves.

Where some of the pmtics (Fig. 4) are *continuously created in the* ***denser*** *environments* by the **interaction and friction** of two or denser ***or stronger*** *pmtics* and some ***weaker pmtics*** are generated through the **collision or friction** of *matters and Matters* in the universe.

South
North
South
North

Fig. A

Fig. B

Fig. 4: Graphic presentation of plasmatic magnetic fields.

Note: The figure 4 A: represents the collection of plasmatic magnetic fields of different strength. The figure 4 B: represents a graphical representation of dynamic pmtics in motion.

The pmtics due to their very weak strength are usually considered to exist and be in motion in **packs** within the different parts of universe (Fig. 5). Where, each pack can be made of number of different orders of magnitude of pmtics strength.

For ease of understanding in trying to explain that how plasmas are created initially, we will consider three packs of pmtics. Where, for our purposes, each pack of plasmatic magnetic fields is denoted by one capital letter. Then each strength sub-constituent magnetic fields forces is number denoted. The different strength fields denoted with different numbers (Fig. 5).

For simplicity of explanation, we will consider three packs of A, B and C with constituents of different dynamic pmtics (considering that fields are in motion in their environment).

Furthermore we consider that each pack of magnetic fields contains five different sets of fields strength called (**Pack A**) as A1, A2, A3, A4 and A5, (**Pack B**) as B1, B2, B3, B4 and B5 and (**Pack C**) as C1, C2, C3, C4 and C5 respectively (Fig. 5).



Fig. 5: Initial fundamental particles of plastic magnetic fields.

It is important to remember in this section, that when we talk about the *gravitational field forces (Magravs)*, this means the **gravitational fields** and the **Magnetic fields** of any entity in possession of these magnetic fields, which are generated simultaneously by the interaction of the same two or more plasmatic magnetic fields.

It is crucial to remember that there cannot be a situation where, there are gravitational fields and no Magnetic fields within a system and vice-versa. Even where, the Magnetic field comes to be placed in the boundary of the gravitational field zone.

In principle, the gravitational fields and the Magnetic fields of the plasma are represented in the same region in our diagram(s), and for simplicity, these are shown with the doted line and this single line is representing both the Magravs zone of a Matter.

Creation of Matter of plasma through interaction of pmtics.

Initially considering interactions between, the pack A and the pack B and ***at least one pmtics of each pack***, which are to match with each other strength ***of the other pack***, where these two pmtics are allowed to interact and interlock into each other.



Fig. 6: Dynamic plasmatic magnetic fields A1 and B1 making the initial magnetic interaction of two packs.

Note: Only pmtics of similar or near similar pmtics strength can interlock into each other, where pmtics of different strength are attracted to each other but cannot interlock in the majority of the cases.

For the pmtics of packs A and B, which are similar or equal in magnetic fields strength, and they are in motion, and able to interact with each other or to interlock into each other (Fig. 6 and Fig. 7 a), it is considered that the North Pole of pmtics A1 and the South Pole of the pmtics B1, (Fig. 7 b) start the ***attraction*** of the two pmtics to each other.



Fig. 7: Interacting plasmatic magnetic fields making pmtics of Matter.

Note: It is considered at all times in the universe all magnetic fields and plasmatic magnetic fields are in dynamic and in the state of motion, as magnetic fields in essence are always attracted or interacting with other magnetic entities, thus they are always on the move towards or repulsing from one magnetic field to another. This is how the motion of Matters and fields are maintained in the universe. This continuous dynamic mixture of different magnetic fields strength become part of a localized or universal pmtic soup(s).

This interaction and interlocking of these pmtics initiates and creates the ***first step*** of interactions between two packs A and B plasmatic magnetic fields (Fig. 7 c). This ***interlocking***, leads to the creation of the very first *initial fundamental magnetic fields set*, or the first initial Magravs, what is called the initial configuration of pmtics needed for initial seed of the plasma (Fig. 7 d and e).

The interaction of at least one plasmatic magnetic fields of each pack that is initiating, and starting the initial weak Magravs forces of a Matter of a plasma, this is the **first step** *for the interlocking of the two packs* of A and B, of pmtics forces in respect to each other.

From this point on, the first plasmatic Magravs force, essential for the seed of the first Matter of the plasma, is set to start and operate (Fig. 7 e). That is to say, the first gravitational field (G1 in Fig. 8 B) and the Magnetic field (M1 in Fig. 8 B) forces can be considered to be created in between these weak pmtics packs.

It is appropriate to consider that the interlocking of the two dynamic fields, due to their interaction and attraction, are bent inward or become overall to be ***spherical*** in shape (Fig. 7e and Fig. 8 A).



Fig. 8: The creation of the seed of the plasma.

For ease of explanation, all the initial plasmatic gravitational fields (Fig. 9 field G1), and all the plasmatic Magnetic fields (Fig. 9 field M1) from now on in this disclosure are denoted as G1 fields (Fig. 10), or what we call **Magnetic and gravitational fields** or **Magravs** and considered these to be the seed of the pmtics of the **Matter** components' of the plasma.



Fig. 9: Initial gravitational fields and Magnetic fields (Magravs) of the Matter components of the plasma.

At the same time, the ***remaining*** pmtics in each pack of A and B, due to the dynamism and Magravs in the vicinity of this seed, these will be kept around the seed G1 as one dynamic pack SET P1.

The collective Magravs force of the seed of Matter will be known as G1 (Fig. 10) and the remaining pmtics magnetic fields of Pack A and B as initial set of the Matter component of the plasma is denote as **SET P1** (Fig. 10).



Fig. 10: **Set P1**, the initial pmtics of the Matters Magravs' components of the plasma.

*Note: It has to be remembered that the pmtics in G1 are not produced and connected to a source of a solid magnet, but these **forces** were made by magnetic fields and were detached from their source of creation, some times before, hence, the use of the term "plasmatic" for these magnetic fields. The term "plasmatic" refers in this book to a "collection" of dynamic magnetic fields, and **not** to the state of a plasma in its common term use, which for example refers to a state of dynamic protons.*

Nevertheless, the remaining plasmatic magnetic fields of the two packs A and B are ***not matching in strength*** and hence they cannot lock into each other, *these being* pmtics A2, A3, A4, A5, and pmtics B2, B3, B4, B5.

Therefore, the initial dynamic pmtics interaction of the two packs making up the G1, possessing dynamic Magravs force, become the **Matter** component's of the *upcoming plasma*.

In the open spaces of the universe, the SET P1 due to its dynamism and motion, naturally and eventually will come across another pack of pmtics, like the **pack C**.

The interaction between magnetic fields of the SET P1 and pmtics of the pack C will be different in respect to the initial interaction of the packs A and B.

In this set of interactions between all the fields and initial Magravs force of the SET P1 and the pack C, several steps can take place instantaneously, simultaneously or over a length of time.
The first step is that, some of the magnetic fields strength in the pack C (C1, C2, C3, C4 or C5) could be **similar** to certain magnetic fields strength as in the G1 of the SET P1.

The *addition of **new** plasmatic magnetic fields* does not necessarily increase the strength of the fields of the G1, but it just adds to the density of the compact pmtics in the G1, and hence **increases of the mass** of the G1 only.

Creation of the Antimatter of plasma

The **second step** is that the stronger field of the SET P1 interacts with similar fields as in the pack C and as they are ***stronger***, they would create a much stronger Magravs strength set. This, leading to the creation of a new Magravs zone, **near** the initial Magravs forces of the G1.

Due to its ***higher*** *pmtics strength*, this new Magravs system denoted as the G2 (Fig. 11) and it would have a separate distinctive characteristic. The new Magravs set possesses **a much stronger field** due to its stronger pmtics, which initiated its creation. This new and stronger Magravs will ***exert forces on the G1*** (Fig. 10), this making the pmtics constituent of the G1 a denser environment as the seat of the Matter (solid, liquid, gas) components of the plasma.



Fig. 11: The pmtics of the second Magravs.

Hence, this new interaction of fields creates a separate and stronger Magravs zone G2 (Fig. 13) adjacent to the G1 (Fig. 13) and in the same environmental plasma condition as G1. This new Magravs G2 (Fig. 11) is independent and interlocked to the initial Magravs of Matters of G1 but it will not interfere with the operation of the G1.

In fact, the Magravs forces within the G2 (Fig. 12) and its surroundings become the seed of another Matter in the same environment.



Fig. 12: The Antimatter Pmtics and Antimatter pmtics Magravs.

This new and stronger Magravs force, due to its stronger plasmatic Magravs interactions and its transparency, become what is known as the Antimatter part of the plasma (Fig. 12 G2).

For clarity, the new stronger magnetic fields interaction between the SET P1 and the pack C, and creation of the Magravs force of G2 (Fig. 11), becomes part of the **SET P2** (Fig. 13).

Where, now this new set includes the G1 the Matter and the G2 the Antimatter and the remaining pmtics of the three original packs. Where, the weaker Magravs of the G1 and the stronger Magravs of the G2 co-exist next to each other, and are interlocked to each other by the original three pmtics fields in the original packs, which they originally shared (Fig. 13). Through overall Magravs of the two Matters in respect to each other, these two Matters' Magravs keep the rest of pmtics of the original three packs together and around them.



Fig. 13: Set P 2. This set includes pmtics and the Magravs of the Matter, the Antimatter and residual pmtics of 3 original packs.

This interaction of two different plasmatic Magravs sets of different strengths is similar to the plasmatic Magravs set forces operating in independent celestial bodies of the solar systems the like of the Earth and the Sun, where, the Earth can be considered to be the G1 pmtics Magravs and the Sun the G2 pmtics Magravs of the set.

Creation of the Dark Matter of plasma

The **third step** of the same interaction of the pack A, B and C pmtics, is from the other residual fields of these packs. Where some of the *residual* magnetic fields will generate a new Magravs force environment, the like of the G3 (Fig. 14). The G3 gravitational field force is a part of the same set of the same plasma environment as the G1 and the G2.

This new Magravs force zone of the G3 is created through the same process as the other two Magravs, with a difference that the outward Magravs strength created by G3 are in magnetic fields strength balance with the overall pmtics strength created by the G1 and the G2 and other pmtics within the environment of the original three packs of pmtics.

This G3 is independent from the magnetic fields of other two Matters of the plasma. But these sets overall Magravs are ***near equal*** or are ***in balance***, in respect to the pmtics of the overall enclosure of the plasma and of all the three original packs and the two gravitational sets of G1 and G2.



Fig. 14: The schematic and pmtics representation of Dark Matter.

Hence, even though this region of the plasma possesses Magravs forces, but it appears to be void of external magnetic fields, or this region appears to be void of a magnetosphere. Where, in the interaction of the G3 Magnetic fields with its surrounding magnetic and Magravs of the G1 and the G2 of the same environment, these fields of the G3 fail to create a visible and distinguishable magnetosphere for the G3 set with other magnetic fields in its surrounding environment. Therefore, as there are no interaction between the overall balance of the Magravs of the G3 with its surrounding pmtics, thus no visible or may be very little detectable light due to the interaction magnetic fields of the G3 with its surrounding pmtics are produced, that these could create light that could make this new gravitational centre to be detectable. Which this light can confirm the existence of another internal gravitational fields of another Matter in this region of the plasma.

Even though there would be a gravitational field force in this region of the plasma, which confirms the existence of another Matter in this region of plasma. However, the G3, due to the balance external Magravs interaction with other fields around this region with the lack of stronger external magnetic fields to create more profound detectable light in comparison to the G1 and the G2 magnetospheres within the plasma, makes this region around the G3 darker in respect to the rest of the plasma environment (Chapter 7).

Nevertheless, this region possesses pulling field forces or gravitational field forces but will not be as visible or detectable as the rest of the plasma, or will be darker in comparison, due to a lack of the stronger magnetospheric interface (Fig. 15 **SET P3**).

The G3 gravitational field force region, due to its dark appearance, becomes the Dark Matter component of the plasma (Chapter 14).



Fig. 15: Set P3 interactive gravitational fields of a Matter, Antimatter and Dark Matter.

In the past papers (36) and the Dark Matter chapter, ***Keshe Theory of creation of Dark Matter*** considers' and explains' that "Matter which possesses both Magravs, but where the overall Magravs strength are *in balance or near balance* in respect to its environments pmtics strength, so much so, that these regions do not create any or create only a very little magnetospheric visible light zone through the interaction of their pmtics (Chapter 7), that the Matter cannot become detectable or become visible in respect to its surrounding environment at specific given time and position, hence the Matter Magravs magnetosphere appears to be darker in that part of given environment, hence the term **Dark Matter**" is used.

These interactions and principles of how Dark Matters are generated have been explained and discussed in detail in the paper titled "The creation of Black Hole" (13), "Creation of Dark Matter" (36), "The rings of Saturn" (39) and further in different following chapters in this book.

We consider the creation and appearance of the Dark Matters, Black Holes, Dark Spots on the surface of the Sun and Dark sections of the rings of the Saturn, are all to be due to and through the same fundamental principle of the interaction of equal plasmatic Magravs strength forces in their given specific environment at a specific duration of time as in the G3 (13, 14, 17, 18, 24, 36).

Nevertheless, the Magravs forces of the G3 will be interacting with the rest of the plasma Matter's field's forces. The G3 pmtics released partially will feed the plasma's of other components of Matters for their motional energy and in keeping the gravitational field forces of the G1 and the G2 intact and overall to keep the plasma as one integrated system (Fig. 15).

Creation of the torus field force

The **fourth step**: Further on in this process of interaction of three original packs of pmtics, and due to the dynamic characteristics of the other three Matters Magravs, soon ***some of free pmtics*** left in the overall initial three packs will come to be positioned in the centre of three Magravs forces of the G1, the G2 and the G3, and becomes the **interlocking force** between the three. The free pmtics become a dynamic swirling compact of residual of *un-matching pmtics* field strength and behave as a partial sphere of rotating magnetic fields forces to be known as the **F1** (Fig. 16) part of the plasma.

C1 A3
F1
C1 A3
F1

Fig. 16: The spherical torus field force.

These free F1 pmtics, due to not being able to find equal magnetic fields strength partners to establish themselves as a Matter condition phenomenon, this portion of the interacting fields become void of central gravitational field forces.

As the G1, the G2 and the G3 are in continuous motion, and as these three Matters lose their energies and momentums, due to their long-term dynamic activities, they come close to this inner field force region of the F1 and in contact with its pmtics forces. This is the point where, the three Matters of plasma gain momentum from their interactions and encounter with the dynamic magnetic fields forces of the F1 (Fig. 17).

This dynamic pmtics region in between three dynamic Matters can be compared to an empty spherical torus shaped field force effect (F1) (Fig. 17), as the field forces turn inwards, without any central gravitational field forces strength, and without any matching pmtics to generate any viable internal gravitational field force for the creation of any Magravs to lead to the creation of any Matter types.

In practice, the conversion of the pmtics of the F1 into energy, partially allows the balanced dynamism of the whole plasma to be maintained.



Fig. 17: Spherical torus shaped pmtics made by interaction of different strength residual pmtics of the three original packs.

F1's are considered as a natural process and phenomenon in the plasma and in the universe, with the content of larger order of magnitude difference in pmtics strength in their constituents.

This dynamic spherical magnetic fields force region of the F1 in plasma or in space, void of central gravitational field forces, is commonly called a ***Wormhole***, and its operation of its field's forces in motion as Wormhole effect.

It has been hypothesized in the past by scientists that such a Wormhole can be used for inter-space travel with extreme speeds of motions near the speed of light.

We consider that these dynamic magnetic fields regions can be used to increase the speed of any object, which comes in touch with their dynamic magnetic fields. In fact the fast journey of the object through the F1, will not necessarily lead the Matter to anywhere rather than giving a turbulent fast ride within the structure of the plasma.

In case of wormhole in a galaxy, the object will have a fast speed travel without much control in speed and dictating the point of final destination of where the object might end up.

These are points in space that acceleration for motion for other Matters of the plasma or physical matters can be obtained, by using the dynamic pmtics forces of the F1 in plasma or space, where these forces happen to exist. Finding these points in space are much easier than ever thought before (Future publication).

Initial structure of Matters of plasma



Fig. 18: Set of interaction between the three Matters and the F1.

Even though each of the three Matters are separate and operates independently from other Matters within the plasma, it is possible that from time to time the magnetospheric envelop of each Matter comes in touch with other magnetospheres of Matters of the plasma and creates a common ***interface*** in the region for the window of time of the interaction (Fig. 18 shaded areas).

It is important to note that plasmas can possess several G3's and F1's of different pmtics strengths in its overall entity for some time, individually or simultaneously, at different time in its life cycle.

Transition-zone pmtics

The new overall interaction of all three Matters and all fields of all pmtics of all three Packs, as one entity, leads to the creation of the initial Matters and Forces of the plasma (Fig. 19).

At this point, there could be other pmtics of the three original packs within the structure of plasma that could not link or be part of the components of the three Matters and the F1, these free leftover pmtics literally float in the plasma and over time, they become the feeding pmtics for one Matter or another and the interlocking magnetic fields forces of part of the other Matters of the plasma.

These loose pmtics in-between interfaces of Matters are the dynamic plasmatic magnetic fields transition zones, which we call "***the energy transition zones***" (Fig. 20, the field arrows), in the overall structure of plasma. The magnetic fields in these intervening gaps among the Matters are fields that are mutually shared by all Matters in the plasma, when there pmtics strength comes to their level; these residual pmtics are considered more as a mixture of magnetic rays than pmtics.



Fig. 19: Initial Matters and forces of the envelope of plasma.

They are in the plasma, like intermediating or interface zones in between two or more

Matters of the plasma at the same time.

Now that all the plasmatic magnetic fields of the three original packs are considered and counted for and used up, now we consider that the full set of the G1, the G2 and the G3, loose pmtics in the transition zones and F1, create an overall **integrated** independent Magnetic field and gravitational field of their own to keep the integrate of all pmtics of the three Packs A, B and C, together as on entity. Where this new entity becomes to be known as the "Initial Fundamental Plasma".

Initial Fundamental Plasma



Fig. 20: Keshe Model of the Initial fundamental plasma.

I call this dynamic concept the **Keshe Model of *"The Universal order of creation of Matter"***.

We consider the Initial Fundamental Plasma to be similar to **the construction of the Neutron** (Fig. 20).

Figure 21 gives the conceptual presentation of complete plasmatic magnetic fields of plasma, of "**The universal order of creation of Matters**". This model represents the pmtics structure of the **Initial Fundamental Plasma**, where the G1 is the Magravs of Matter, the G2 is the Magravs of the Antimatter and the G3 is the Magravs of the Dark Matter.

It is considered that Initial Fundamental Plasmas always have an internally balanced magnetic fields environment, as one observes in the plasma as in the solar systems.



Fig. 21: Keshe Model of the pmtics of Matters of plasma.

At the same time initial fundamental plasma maintains an overall and external Magravs created by Matters and all pmtics, which are within the confine of the plasma too. Thus the internal balance magnetic fields of the neutron does not mean that it does not possess Magravs in respect to its outside environment. But due to the existence of Magravs of its component structure the initial fundamental plasma maintains an independent magnetosphere in respect to its surrounding environment.

When, contemplating on discussing about the proton or the neutron as a plasma, one has to talk about the whole of the plasmas' components, namely, the *Matter* part (what has been considered as the matter part of the nucleus of the atom), the *Antimatter* part, the *Dark Matter* part, the *spherical torus magnetic fields* and the *transition magnetic fields parts.* These are all together ***the components of one plasma*** and have to be considered as one package and entity.

There cannot be a plasma condition, where all three Matters do not participate in the existence of the plasma.

Decay of initial fundamental plasma

At the point in the cycle of the life of an initial fundamental plasma, when the shared magnetic fields of the transition zones, or pmtics of one of the Matters of plasma are partly exhausted and the Magravs balance among or in the Matter fields are disturbed and the Magravs binding forces are unbalanced, then the initial fundamental plasma disintegrates to its substructure of new balanced Magravs of the same Matters for the initial fundamental plasma to find a new balanced combination within its own Matters and fields within their given environment.

This process of splitting of the initial fundamental plasma to find new and smaller balanced plasmas for Magravs of Matters and fields balance, I call this process the **decay of the Initial fundamental plasma.**

The decay of the initial fundamental plasma always leads to the creation of at least two new balanced and smaller initial plasmatic magnetic fields plasmas of the same configuration, with, one plasma which possess more of the Matters and is larger, and one plasma which is a smaller and holds less of the Matters and pmtics of the original initial fundamental plasma. Nevertheless, the two new plasmas and their contents have to keep the overall balanced structure of the initial fundamental plasma. This happens so that both plasmas can survive within their environment as one entity.

The outcome of the **decay** of the **initial fundamental plasma** into two new components is considered to become the creator of the new ***proton*** and the ***electron*** of an atom. This new balanced pmtics entity, or so-called atom; itself has to have an overall balanced Magravs forces operating within it, for the atom to keep the integrity of the original initial fundamental plasma.

The decay of the initial fundamental plasma leads to the splitting of its content into a proton and an electron simultaneously (Fig. 46 diagrams 1 to 8). Nevertheless, at the same time as the new plasmas' component reposition and rebalance during this process of decay, this leads to the release of some residual pmtics or magnetic fields, which are not needed for or by the two new entities for their respective parts of their Magravs positioning (Chapter 18).

The release of the unwanted fields for the balance interaction between the two new plasmas, leads to the release of the magnetic fields packs as different rays or energies from the splitting of the initial fundamental plasma. This release can be in any form like a mixture of rays, pmtics, sound energy packs and so on.

I consider this ***process of the decay*** of the initial fundamental plasma of the contents of its three Matters and fields to be a **new** fundamental universal principle, where in larger scales of order of magnitude; it is called the nuclear decay of atoms.

In science at the present, scientists consider that elementary particles are quarks and so on, but now we know that ***quarks*** *themselves are further* ***made-up of basic magnetic fields and their interactions***. Where, ***collections*** of magnetic fields in a group, as dynamic plasmatic magnetic fields, and their interactions with other dynamic plasmatic magnetic fields, leads to the creation of the Matter(s). Where, the mass of the "quark" is produced by the interaction of these plasmatic magnetic fields through the principle of the creation of gravity as has been explained in Chapter 1.

Secondly, what is at the present called the spin of the quarks now we understand is the natural dynamic motion of the Matters created in the plasmas' environment, through the interaction and Magravs positioning of the dynamic Matters of the plasma.

Thirdly, what is considered by the present science, as the *colours of the quarks*, are in reality the different contents, of different plasmatic magnetic fields strength interactions leading to the creation of gravity and Magnetic fields with their overall interaction effect in respect to their environment pmtics, which leads to the creation of the magnetosphere of each Matter of the plasma, these being the magnetosphere of the Matter, the Dark Matter and the Antimatter in the magnetic environment of the plasma or the neutron, the proton or the electron.

This means that the quark cannot be considered as an "elementary particle" as it has sub-components and is made of magnetic fields itself.

Thus, ***I consider the new "elementary particle" to be of the "magnetic fields" origin,*** which this itself explains why one sees all sorts of effects, like the present quarks, bosons and the spin of the dynamic Matters of the plasma, and so forth. Where, these all can now simply be explained as being due to the interaction of different magnetic fields strengths, which makes up the structure of the Matters of the plasma and the other magnetic fields, which are within the structure of the plasma.

Even in the largest scale, this initial fundamental plasma decay model is what cosmologists see in the galaxies as the collapse of stars (which the star is and can be considered to be the initial fundamental plasma) and its re-emergence as new smaller components of star or solar systems. By the same principle, the release of energies for the star to find its new balance through its star decay always leads to releases of vast amounts of unwanted matters, Matters and energies and creation of sub-components but still with its Magravs forces.

This decay of initial fundamental plasma is discussed in more detail in Chapter 15.

CHAPTER 4

Matters' of plasma and their transition of states

There is conclusive evidence to show that plasma possesses energy, and maintains specific magnetic behaviour, and that plasmas can and do generate their own Magnetic fields and gravitational field forces.

Research done by a number of institutes around the world indicates that the plasma of Matter is accompanied by a second Matter constituent called the Antimatter. Some institutes (6, 7, 8) claim that they have separated and have managed to contain the Antimatter.

In other sections of science, scientists refer to what is called the **Dark Matter**, and observations of virtual matters.

The world of science has failed to consider the creation of all these three states' of Matters (Matter, Antimatter and Dark Matter) as constituents, and as of one process, in the chain of initial progressive process of creation of the three Matters and as the content of one plasma in the universe.

This failure has been due to the lack of understanding that the Matter, the Antimatter and the Dark Matter components of plasmas are all created simultaneously and as one integrated dynamic plasmatic magnetic entity.

It is fundamental to understand that one of these Matters' does not exist without the others within the overall structure of the plasma. Then through this process, it becomes easier to understand the operation of Matters, matter and fields, plasmas, atoms, molecules, solar systems and galaxies.

One can now translate this new understanding of how plasmas are created and operate into how larger celestial objects are created, and operate in their given environment collectively. In other words, we translate the knowledge of the operation of electrons around the nucleus to the operation of planets around their stars.

To understand the relationship and construction of the plasma with more clarity, every effort in this book have been made to go through stage by stage, how **Matters** of plasmas are considered to be connected, and *appear* **to inter-transit from one state of Matter to another** within different environments without loss or gain of any of their plasmatic magnetic fields strength.

In the matter world this is like the inter-change between states of matters, from solid-to-liquid, liquid-to-gas, and vise-versa.

Where in the matter world the ***state-of-matter*** is *magnetic fields'* **forces** dependent, and in the ***state-of-Matter*** it is *magnetic fields'* **strength** dependent.

The phenomenon of transition from one state of Matter to another is a regular occurrence in dynamic pmtics processes in the spans of the universe (Fig. 21).

All components of Matters of the plasma or any Matter or matters in the universe are connected to each other through the interaction of their pmtics, and their pmtics strength, which are the constituent and the creator of their Magravs.

Thus, as each Matter gains or losses some of its pmtics, one Matter component of the plasma will become or can become the component of another Matter of another plasma or field at “a given point in motion of pmtics” (time) and at a given point in its space.

For example, Matters of plasma can interchange from one Matter to another due to their motion of dynamic pmtics or what is called energy levels changes in respect to a given environment pmtics strength.

All Matters can appear as different Matter by just changes of the environmental pmtics strength too. For example the same plasma or Matter by just passing through another region of different pmtics strength. This is the process what we call *transmutation*, but in this case the transmutation is done by the environmental condition and not by the internal Matter pmtics strength change.

Matter can appear as different Matter, for example Dark Matter can appears as Matter by *simply entering into a new pmtics environmental condition*. This is how Dark Matter suddenly appears as virtual matter.

For example, **Dark Matter** in a given environment of plasmatic magnetic fields strength by entering into a new and stronger or weaker pmtics strength configuration, instantaneously, becomes **visible Matter** in respect to its newly entered environment (Dark Matter to Virtual matter). I call this the ***phase of transmutation of Matter(s)***, so this is the unveiling or occurrence of a new state of Matter from the same old Matter in a different outfit.

Secondly, Matters can change their status and behaviour from Matter to another for example from Dark Matter to Antimatter or Matter, by simply ***gaining from*** or ***losing to*** a part of their plasmatic magnetic fields strength to other Matter(s) or pmtics in respect to their given environment.

If Antimatter Magravs strength reaches an environment pmtics strength that its overall Magravs strength becomes equal and in balance with its new environment pmtics strength level, then the Antimatter can become and behave as the Dark Matter entity in respect to its new given environment (Fig. 22).

On the other hand, for example as the pmtics strength of the components of Antimatter reduces or as Antimatters interact with other Antimatters of different Magravs strength, these Antimatters lose enough of their Magravs strength that one or both Antimatters come to a new balance of plasmatic magnetic fields strength. Where, these balances can be in their internal and external Magravs, then these Antimatters Magravs strength can come to a level that the new strength of the former Antimatter become to be in the pmtics strength level of the Matter, or change to the Dark Matter field strength level status in respect to the same environmental condition.


MATTER
(H, He, Ar...)
Visible - emitting EM
(detectable SEPMF's)
ANTIMATTER
invisible
(detectable SEPMF's)
DARK
MATTER
transparent/tangible
neutralized EMF
(balanced superimposed SEPMF's)
magnetic fields
boundary

Fig. 22: Schematic Keshe model of interconnection relation between different states of Matters.

This is what we call the ***Keshe Theory and principle of the transition of Matters***, that is to say "***the transition from the Matter to the Antimatter or the Dark Matter and in reverse, and the transition of the Dark Matter to the Antimatter and in reverse, is a normal condition of transition of the Matters"*** (Fig. 22 and Fig. 23). These figures showing in a simple and new way how and the connections by which interchange(s) between the states of Matters in the universe are achieved.

Keshe principle of transition of the Matter states' that, "the plasmatic magnetic fields strength of the environment in which the Matters operate in, ***dictates*** what the Matter appears as or presents itself as, in that given environment" or on the other hand "when one Matter gains or losses enough of its plasmatic magnetic fields strength that the Matter Status, characteristic or behaviour becomes of other Matters of the plasma status and behaviour or characteristics within the same given environment".

Therefore, Matters can change from one Matter to another by increase or decrease in their pmtics strength or they can appear as different Matter as they enter different plasmatic strength environment and conditions.

That is to say, the Matter can become to have the characteristic of the Dark Matter in a given environment pmtics strength, and by the same measure, the Antimatter can lose enough of its pmtics to become Matter, and so one. The schematic transitions of state of the Matters are shown in figure 22 and figure 23 of the ***Keshe model of transition of Matters.***



Fig. 23: Keshe universal Model of the plasma transition of plasmatic magnetic fields and Matters.

With the use of simple pmtics plasma dilution reactors, which have been developed by Keshe Foundation through its Keshe Technology development sector, the principle of transition of Matters have been tested and results have proven to be in line with the theoretical consideration.

Where, in these nuclear-based reactors, Matters can be allowed to go from one state of Matter to another and then allowed to return to their original state of Matter. This new method of transition of Matters brings about a new way and technology of producing all man's material needs for motion, energy, creation of new matters and so on.

For example, effects and properties of transition of Matters (Fig. 23) can be used to make physical Matter to have no magnetospheric boundary as Dark Matters do in a given environment, so that the Matter behaves like the Dark Matter in characteristics. In these environments, the Matter will become translucent dark or the centre core behaves as becoming invisible in respect to its surrounding environment, without any change in the property of the physical Matter or change in its gravitational field strength or position in space of the Matter.

As the Matter with this property presents no effective magnetospheric condition in respect to its surrounding environment due to the lack of /or little interaction between the pmtics of the Matter and its environment, then the Matter now can behave as Dark

Matter and move without friction and freely within the same environment.

Utilizing this state of the Dark Matter effects around an aircraft or spacecraft, this condition will give the craft frictionless motion and higher speeds and possible invisibility in the same environment (Chapters 13).

The technology of transition of Matters has been tested-out over years by the Keshe Foundation, and several systems were designed, developed and manufactured and used to achieve the formation of original magnetic fields plasmas to prove the correctness of these principles, and indeed the effect of transition of Matters were proven to be correct.

The implication and application of the use of transition of the states of Matters are so immense and profound, that one needs to know, for example, where the Matter will end-up in, and in what state of Matter in respect to its environment, one will appear as.

That is to say, one has to know if for example, going from Matter to Antimatter, where in the strength fields of Antimatter, one will end-up in. Vice-versa, when one can go from Dark Matter into a Matter condition zone, one has to know in what state of matter (gas, solid, and liquid) one will come to ends up in.

Through the operation and control of these reactors, one needs to know where the system state of matter and magnetic condition will end-up. This could be in liquid seas, or in the middle of a solid Matter or in the middle of deserts. Without being prepared for these parameters through the operation of systems, which can facilitate such a transition behaviour and characteristic, the use of Matter transition can have catastrophic consequence, not only for the system, which produces it, but also for the occupants of possible crafts using this type of transportation in the spans of the universe.

By the understanding of the principles of creation of the initial fundamental Matters within the initial fundamental plasma, through the interaction of the initial fundamental particles, a number of unanswered questions in the world of science can be answered.

For example, in the universe the total quantity of plasmatic magnetic fields and the related energies are to be considered ***constant***. Therefore, *in the **totality***, no matter, Matters or magnetic fields will ever be lost or gained in the universe. Pmtics of different strength start existence at one strength level and they consolidate to become stronger, or lose their field strength through division and collision to become weaker in strength. Nevertheless, pmtics in their different strength fields can never be destroyed or lost.

Therefore, pmtics simply interact, divide, and interlock to produce different Matters and conditions like forces, motions, heat and compactness for them to be matters to be visible to the eye of creatures, according to their positions, and so on.

Pmtics in their interactions with others of the same can only move from one state of Matter to another depending upon the condition(s), which prevails at a given point in a given time in space. Thus, the Matter can go from the Dark Matter to the Antimatter and vice-versa, and the Matters to the Dark Matters and vice-versa and so on.

Therefore, the theory and the discussion that universe one day will run out of matters and energy and then there will be nothing as has been promoted by some scientists in the recent past is anything but a fallacy.

By the same principle, we call the **pmtics in motion as** the **energy** of the pmtics**.** These pmtics in motion can release and can lead to creation of the same Matters as they were created-out of, and can have the same capability. That is to say, for example, the energy of the Dark Matter can change into energy of Matter, or part of the matter, and the same applies for other states of Matters.

In understanding, the principles of "**the universal order of creation of Matters**", one can utilise the transition of states of Matters and matters to take full advantage of universal Matters and matters pmtics and their energies.

Through the permanent interaction of all dynamic pmtics of different scales of strength, there will be no end to the universe, as the universe moves through its different pmtics strengths field interactions and repulsions. Where, these will lead to eternal motion of the universal pmtics forces and creation of new Matters, matters, forces and new condition for them to cooperate within the universe. Thus, there never has been a Big Bang and there will never be a doomsday scenario for the universe as a whole, the universe will be forever in equilibrium in its overall universal order of pmtics.

The pmtics of Matters will ***transit*** from one state of **Matter** (Matter, Dark Matter, and Antimatter) to another state of **Matter**. In addition, from one state of **matter** (solid, liquid, gas) to another state of **matter.**

Where, these changes will depend on the properties and forces of the states of plasmatic Magravs and their strength in respect to each other. Similarly, pmtics from strength of fields of Matter will transit to pmtics of different pmtics strength of Matter, in these ***processes of transition***, plasma releasing dynamic pmtics in motion as **energy**.

The real size of the universe will never change; that is to say, the universe cannot expand into a space if the space for its expansion was not there to begin with. Where, from our point of view we only observe a small fraction of the whole, which we observe that fraction expanding. The observed expansion is relative to the position of the observer in respect to a given position in the universe, for example what will be a red shift observation of one at one end of the universe, this will be blue shift to an observer on the opposite direction of the motion of the same entity. In the paper titled "Creation of magnetic fields" it has been explained that the ***blue shift of light*** is created when ***pmtics are compressed***, and the ***red shift is created*** when the ***pmtics move away*** from each other, or ***when pmtics are opened up***.

In the real world of the universal order of creation there is no room for the principle of singularity. Except, if, we would call, a large pmtics, that covered the whole of the universe singularly by itself. Then all that has happened, is that the original single plasma has gradually disintegrated to smaller and weaker strength fields, which their interaction has lead to the creation of what has been seen and is in the present in the short time of the life of man on the Earth. Then, such original singular plasma, which covered the whole of the universe, had to gradually to disintegrate to smaller strength fields, which their interactions have lead to the creation of all events, Matters and matters in the Universe.

The transition of state of Matters principles will be discussed in full in future disclosures.

CHAPTER 5

Definition of Energy Through pmtics

The initial components and construction of plasma are due to the existence of initial dynamic plasmatic magnetic fields.

For a magnetic field to be able to be detected or its existence to be confirmed, the pmtics has to *leave the confines of the boundaries* of its containments, this being the boundary of Magravs of the Matter or the plasma.

It is important to keep in mind that the pmtics do not possess or show **field force** unless they are in motion.

The energy possessed by a plasma can be define as "the total plasmatic magnetic fields forces of all its constituent Matters *and fields in motion,* in respect to the original position of the plasma in a full three hundred and sixty degree spherical direction''.

This is an important factor, as up to this point, scientists have measured and calculated the energy of the Matter component of the Matters of the plasma. Where, in calculating the true energy of the plasma, *one has to calculate the energy of* ***all Matters*** (Matter, Antimatter and Dark Matter) and the other components of the dynamic plasma.

When the magnetic field has left the Matters' or the plasmas' boundary, at this point its existence and the content of the pmtics strength of all Matters pmtics' released can then be confirmed as energy. This is shown in (Fig. 24), the magnetic fields in the Matters.

The pmtics constituent constructions of individuals Matters of plasma are not energies in respect to other Matters while they are within the boundary of the plasmas Magravs' forces. These are shown as the magnetic fields inside the Matters on the left of image (Fig. 24) but are *only forces* (these being the like of Magnetic field or gravitational field forces) in respect to other Matters and pmtics.

When the field leaves the environment of its Matter or the plasma, it is at this point that it can release its domain pmtics to other plasmas in regions or combinations of field interaction zones. These are shown as field forces A at the boundary of the plasma in figure 24.

As the plasmatic magnetic fields, moves further from its original plasmas' boundary (field B in Fig. 24), the plasmatic magnetic fields uses' its energy to overcome other Magravs in its environment. Hence, as the plasmatic magnetic fields moves further away from its mother plasma, the less energy it will have to transfer to other plasmas as it comes into contact with their pmtics.

Thus, energy transfers from one Matter to another Matter through one pmtics strength and the measure of the pmtics possessed at the point of the contact with the second Matter, this is position and distance dependent, from the point of departure to the point of arrival.



Matter Energy Level

Antimatter Energy Level

Dark Matter Energy Level

Fig. 24: Schematic presentation of relationship of pmtics and energy in respect to their Matters.

The total Energy released by the Matter or plasma is the total of pmtics forces that the plasma can release and transfer, and that and what measure of the pmtics can be absorbed by all components of other plasmas in its environment.

That is to say, the same proportion of magnetic fields forces by Matter, Antimatter and Dark Matter and other fields of plasma are released and the same proportion of all energy fields are transferred to the all recipient plasmas and Matters and pmtics.

The total energy of Matter is said to be the total pmtics that Matter can release as it disentangles all the components of its **initial fundamental magnetic fields**, or what is known as its' "**initial fundamental particles**", which the plasma and of the Matters of plasma were made up of, at the point of their inception.

Thus energies released by the plasma or the total energy possessed by the plasma is in fact, the total collection of initial fundamental magnetic fields of all the component constituents of the plasma, which disentangles from their Matters or plasmas and are in motion in the direction of the encountering other pmtics components.

Pmtics absorbed by some plasma's can be only a part of the total pmtics in motion, or energies that have been released by the initial fundamental plasma, and are not necessarily considered to be the total energies that a plasma possessed or has released.

Energies released by plasma are said to be "**the total initial fundamental pmtics released by all components of that plasma" passing its Magravs boundary.**

Multi-plasma atoms' release more plasmatic magnetic fields, due to their total sum of the plasmatic magnetic fields released by all their participating plasmas (protons plus neutrons, and electrons).

The principles of creation of Magravs forces, gives us an insight that "**energy**" can simply be defined as "pmtics, once released, through the dynamic Magravs characteristic boundary from the plasma or Matters, that these released pmtics can ***exert or pass a part of their released pmtics to another plasma,*** for the new Matter or plasma to maintain its existence and/or maintain constant normal magnetic fields strength and/or increase its magnetic density of the same pmtics strength condition to their ground base levels, in their given environment" (Fig. 24).

Measure of a mass

One of the central unsolved questions in the world of physics is how the mass of the Matters or of matters are created, and how they can be calculated.

Through the ***Keshe theory of Mass***, the creation and the measure of the mass of an entity can be defined to be:

"Due to the interaction of at least two magnetic rays, magnetic fields, or plasmatic magnetic fields, which the outcome of their interactions leads to and creates two field forces of a ***pulling*** field forces called *the gravitational fields force* and a ***pushing*** field force called *Magnetic fields force*, whereby the interaction of the gravitational and the Magnetic field forces with each other, this interaction of two field leads to the creation of a given magnetic fields strength **balance** between the two field forces, where, the measure of the magnetic fields difference of the interaction of these two field forces of the gravitational and the Magnetic field forces, is the measure of the Mass of the entity which the two original magnetic fields have created."

The outcome of the interaction of the fields balance is creation of the mass of the Matter, components' of the plasma (Fig. 25), or mass of the matter (solid, liquid or gas).


MAGNETOSPHERE
MAGNETIC FIELD
GRAVITATIONAL FIELD
MASS
A4
C4
C2
A1
B1
A2
B2
C1
A3
F1
G1
G2
A5
B4
C3
B3
G3
C5
B5

Fig. 25: Mass

That is to say by the ***Keshe law of measure of the mass*** of any entity, this being Matter, plasma, atom, matter, planet, star, etc states that:

" **M**ass of any entity =

M*easure of the total gravitational fields strength forces of the entity*

- (minus)

M*easure of the total Magnetic fields strength forces of the entity*"

Through this definition and understanding it becomes clear that the gravitational field forces are always predominate and stronger as all entities possess mass, otherwise their mass would be negative.

Thus ***mass** is the measure of the **difference between two or more magnetic fields after their interaction***, and **NOT** the measure of strength **before interaction**.

Where, the measure of the magnetic fields *before interaction* is their "forces" of their fields, and *after the interaction* of the magnetic fields the outcome of the balance between the gravitational and Magnetic fields that is generated, becomes the mass in respect to a given fixed position of the central Magravs.

The creation of Magravs always is accompanied by the creation of a ***Magnetosphere*** and the creation of the mass of any entity in the universe, and all these four forces are created instantaneously and simultaneously.

That is to say, "the **Initial Fundamental four forces** of existence of an entity that are, the ***Magnetic fields***, the ***Gravitational fields***, the ***Magnetosphere field*** and the ***Mass field*** forces, are *all the outcome of the interaction and interlocking of two or more mainly matching in strength magnetic field*s or plasmatic magnetic fields, irrespective of the size of the entity, this being Matter, matter, an atom or a star.

This is the reason why the mass of any object, which is created by any two magnetic fields strength, is *independent of any external forces and factors*, like gravitational fields forces of other objects or entities. The instance the two magnetic rays or magnetic fields interlock, to generate the first Gravitational fields as an entity, at that moment the span of the Magravs of the two fields forces involved in the original fields are not as individual fields, but they become an *independent entity* in respect to their environments' fields forces. That is the reason why the **Mass of any entity**, like the Matters, are *constant and independent and irrespective of the environmental Magravs forces* which the entity exists and operates within.

That is the reason why the Mass of spacecrafts of the future, or the Mass of planets like the Earth are independent of their environmental conditions. That is to say, the **strength** of the interaction of the two **original** magnetic fields and the span of the fields they produces that created the Magravs *decide how much mass the interaction of the two fields will carry* and no other factors.

This is the reason why, Man will be able to make crafts that can carry any payload by the use of Grapos nuclear reactors Magravs strength, as the payload of these systems and the strength of Magravs that these systems generate, creates independent environment Magravs forces *as long as the boundary of the magnetosphere of the Grapos can cover the physical boundary of these crafts*. Figure 25, in its design, explains' this concept fully. That is why the two magnetic fields have to be equal in strength before they can create the initial four field forces.

If two unequal magnetic fields in strength interact, the two create the gravitational, the Magnetic, the magnetosphere and the Mass, and the lowest strength field, which dictates the maximum level of the strength of the four fields that the Matter can have. The stronger magnetic field residuals of these types of unequal magnetic field strength encounters and creation of matters become the ***tail* magnetic field of the entity**, and this tail is the cause of the creation of the coiling effect of these kinds of masses. Where and if the two unequal magnetic fields strength ***cannot*** create a mass, the same interaction leads to the creation of the coiling of the two fields and to what is known as the ***coiling of the magnetic fields***, this effect is partially the cause of the *swirling of the F1* torus field zones in the plasmas, and its larger counterpart, the rotation of Wormholes, as these regions in the universe are created out of unbalance Magnetic field strength interactions and interlocking, this be it in the plasma or in the universe. In so many ways in knowing the strength of two magnetic rays, magnetic fields, plasmatic magnetic fields and so on, which are about to interact and to create the initial Magnetic and gravitational fields of an entity, one can tell what would be the outcome measure of the mass of the entity they will create.

Einstein has related the mass of matter to its energy through the general equation of relativity.

As explained above, the mass of an atom or plasma itself is made of a collection of dense pmtics strength and their interaction with each other.

Thus initial fundamental plasmas always have the same mass irrespective of the Magravs of their environment.

By the same measure, the Atoms of the same elements are always made of the same number of initial plasmatic magnetic field's sub-components, of neutrons, protons and electrons.

Atoms of the same elements always have the same total plasmatic magnetic gravitational fields **pull** and Magnetic field **push** in respect to all their internal components, irrespective of the environmental plasmatic Magravs that the atoms might be in. This becomes the total mass of an atom, as mass is an expression of measurement of the total enclosed pmtics interaction within the fields of confinement of the plasma.

In considering the general equation of relativity

$$E = m \cdot c^2$$

The energy for the mass of Matters of the plasma, accordingly will be

$$E = m(M) \cdot c^2$$

That is to say "the total pmtics released in motion by the Matter of plasma (once they have left the boundary of the plasma) (Energy), is equal to, the total balance after interacting pmtics strength of the Matter components of the plasma (Mass) which the plasma is made of, multiplied by the square of the maximum speed that pmtics can travel in the matter environment (speed of light)".

Considering that, pmtics of different strength can travel different distance from their point of release with ***different speeds*** in *different Matters,* Matter *and* matter mediums.

Then it is correct to say that the pmtics of the Matter, once it has left the Matter

Magravs of the plasma, this pmtics of the Matter will travel with a different speed than the plasmatic magnetic fields of the Antimatter of the same plasma, or be it the pmtics of the Dark Matter component of the same plasma, in the matter environment.

The Antimatter has and is made of different pmtics strengths, by virtue that it has been created initially by stronger fields, then its speed will be different and higher than that of the pmtics of its Matter component of the same plasma in the same environment.

By the same principle, the faster field of the Antimatter carry more energy or more powerful energies than the slower pmtics in motion of the Matter component of the same of plasma.

Alternatively, in reverse, as the Antimatter possesses more power or energy than the Matter, then for the same volume of Antimatter as Matter in the plasma; the Antimatter pmtics must move faster than the pmtics' of the Matter, in the matter medium.

The Fermi National Accelerator Laboratory - or Fermilab, in USA (6, 7) - considers a small amount of the Antimatter, once released from the Matter of plasma; it can deliver more energy than its Matter parts of the same plasma. They are considering and working on the principle as; they can burn the Antimatter to release its energy so that by the time the Antimatter reaches the state of matter energy, that they can harvest its surpluses energy.

Through the ***Keshe principle of conversion of energy***, the fundamental universal conversion principle follows the path that the Matters convert to matters through their **dynamic pmtics in motion and forces,** or what is refer to as the **energy of the Matter magnetic fields forces, as these energies are transferred to the constituent pmtics' of matter**.

From what I call "The fundamental ***universal conversion principle***" follows that "the pmtics of the Matters' like of Antimatter slow down, through interaction with other magnetic fields, so that their energy can be absorbed and converted to Matters' pmtics strength levels, that become useable in matter environment and appears as the matter (solid, liquid and gas)".

By the same principle, the matter can be converted to Antimatter through the same method in reverse. Where, these processes are not much different for both paths of conversions.

Only the state of pmtics strength and the effects of the environment, which dominates at a given point and at a given motional position (time), that will dictate what state the dynamic pmtics in which the state of Matters, the matter manifest itself as, and what matter will appears in the line of sight by given tools of detection at a given point in the universe. This dictates if pmtics strength will appear in state of matter as solid, liquid or gas, or will manifest itself in one of the state of Matters, as Matter, Dark Matter or Antimatter.

CHAPTER 6

The total energy balance equation of Plasma

The energy balance equation or general equation of relativity ($E = m.c^2$) gives the relation between the *tangible part* of Matter of the plasma and its constituent energy.

The mass of an atom or collection of plasmas of its components, themselves are made of a collection of densities of pmtics strength of different Matters and their interactions, in respect to each other within their respective initial fundamental plasma.



Fig. 26: Schematic of the fields of all components and of the initial fundamental plasma.

In considering the plasma, the general equation of relativity can be written in its real terms of its constituent components and their interactions and effects. Thus, this equation as has been said can be defined in respect to the Matter components of the plasma in the following manner.

That is to say "the total pmtics released in motion by the Matter of the plasma (once they have left the boundary of the plasma) (Energy), is equal to, the total balance after interacting pmtics strength of the Matter components of the plasma (Mass) which the plasma is made of, multiplied by the square of the maximum speed that pmtics can travel *in the **matter** environment* (speed of light)".

Knowing the new composition of the plasma, then the ***total energy of the plasma*** has to be in its ***totality of all its masses of all its Matters*** and not just its Matter component.

Therefore:

K (the total energy of plasma) = [energy of the Matter + energy of the Antimatter + energy of the Dark Matter + energy of the spherical torus-shaped field force effect + the energy in the inter binding between the other parts in the transition zones of the plasma].

K= [E (Matter) + E (Antimatter) + E (Dark Matter) + Ecf (centre spherical torus pmtics) + Etr (pmtics within transition zones)].

Where, total general equation of relativity for the whole of the components of the plasma can be written in the following form.

$$\mathbf{K = EM + EAm + EDm + Ecf + Etr}$$

Or:

K = [(The total components of constituent pmtics of the **Matter**) x (the square of the **speed** of pmtics in the **Matter medium** or the speed of light) + (The total components of constituent pmtics of the Antimatter) x (the square of the **speed** of pmtics of the Antimatter in the Antimatter **medium**) + (The total components of constituent pmtics of the Dark Matter) x (the square of the **speed** of pmtics of the Dark Matter in the **Dark Matter medium**) + The total energy components of constituent pmtics of spherical torus-shaped field force effect + The total components of constituent pmtics of the inter binding between the four other parts in the transition zones of the plasma].

$$K=M\ (M)\ .\ c^2(M) + M\ (Am)\ .\ c^2\ (Am) + M\ (Dm)\ .\ c^2\ (Dm) + E(cf) + E(tr)$$

Note: Capital M indicates here a mass of Matter.

When for example an apple is measured using the present measuring tools and methods, the figure attained is only for the mass or the weight of the Matter part of all the plasmas' of atoms of the whole apple.

As a representation, one initial plasma of an atom in the whole construction of an **apple** with it's Matter, Antimatter, Dark Matter, and other pmtics are shown on the right hand side picture of figure 28. Where, the *tangible apple **as matter*** represents the total Matter components of all the pmtics of an apple is shown on the left picture of figure 28.



Fig. 27: The pmtics of all components and of initial fundamental plasma.

The total weight or mass of the plasma has to be the total weight and the total mass of all the components pmtics and all of all the plasmas of Matters of the initial fundamental plasma.



Fig. 28: Newton's apple has different types of pmtics and Matters.

*Note: When the Matter is part of the plasma, this is denoted as **Matter** (G1 in Fig. 26, Fig. 27 and Fig. 28) and when the same is considered as tangible matter, it is noted **as matter** (Apple in Fig. 28), of an atom or an object.*

By the same measure, if one has managed to separate the Antimatter of the plasma from its other constituents of the Matter and the Dark Matter of the plasma to confine the Antimatter in separate container as the Fermilab has claimed. The question to ask is that, what is the weight or the mass of the balanced leftovers of the Matters, (or Matter, Dark Matter and residual pmtics) of the plasma? By the laws of physics, one cannot have something (Matters/Energy) out of nothing. One cannot have mass of Antimatter component of the plasma, when its mass is not calculated in the overall mass of the plasma, or the leftover mass of the Matter and the Dark Matter of the same plasma must be less than before the Antimatter was taken out.

On the other hand, the question is that, is the present used methods of measuring the weight and mass of the plasma, measuring the ***total mass*** of ***all** the Matters* of the plasma? Alternatively, does one has to break the present numbers of mass and weight of each Matter, up to its sub-weights and sub-mass of the Matter (Fig. 26 and Fig. 27 G1), the Antimatter (Fig. 26 and Fig. 27 G2) and the Dark Matter (Fig. 26 and Fig. 27 G3) of the plasma. Further, the Magravs of the Matters of the plasma in conjunction with their own Magravs and other pmtics in the plasma create their own additional gravitational and Magnetic field forces, their own additional mass, as well as the individual masses of the Matters of the plasma. Thus the total mass of the plasma has to be more than the total mass of individual Matters of the plasma.

As Fermilab has separated the Antimatter components of the plasma, then, the question to ask from them, is that, if the mass of the matter of the plasma they hold still has the same mass as before without the Antimatter in it? So, what is the mass or the weight of the Antimatter that has been separated?

This applies the same to the Dark Matter components of the initial fundamental plasma too.

As has been said before, the total weight or total mass of the plasma is and has to be the total weight and total mass of all components of the Matters of plasma. This includes the masses or energies of the magnetic fields force of the F1 and the residual fields in the initial fundamental plasma.

Thus, there is a *fundamental error* in the present methods and technologies of measuring the weight and the mass of the plasma systems as a whole.

That is why suddenly one can see strange results from the Antimatter component of the plasma of the same mass or weight in the matter environment.

If, the total dynamic pmtics of the initial fundamental plasma, would have been, measured correctly from the beginning, then there would have not been such an ambiguity and mystery arising from the sudden hidden energy sources called the Antimatter, or the powers of the Dark Matter of the plasma.

The fact is that, the Antimatter and the Dark Matter possess plasmatic Magravs forces and that is why, they are called the **Matters**, as they possess mass and energy.

Hence, if there is a gravitational field's force of the Antimatter or the Dark Matter components of the plasma, then these Antimatter and Dark Matter have to have mass and they have to have weight in respect to the other Matters in the plasma and in respect to their environments pmtics, which the plasma is in, at given time. Therefore one needs the measurement of both of the mass and the weight of the plasma as whole as an entity as well as all the individual masses of each Matter too.

Then, the same as with the atomic mass and atomic weight of an atom measurement phenomenon of today's science, **there is a need for a new scale of measurements**, and new measuring tools to be brought about and developed for the true and total pmtics measurements of the constituent Matters and fields of the Initial fundamental plasma.

By this new total weight measurement, then the ambiguities in the present plasma physics and nuclear physics will be sorted.

That is to say then, where and when one gives the measure of the mass or the weight of the plasma, then at this point, one has to give the mass or the weight of the Matter, the Antimatter, the Dark Matter and the rest of components of the plasma in a given motional position, and the position in the life of the plasmas independently, for all components of the plasma, and one measurement for the plasma collectively as the whole needs to be given too.

The reason for stating the position and motions of the plasma is due to the fact that, the plasmas having dynamic characteristic components, plasma itself as a whole is a dynamic system too and continually gains or losses pmtics from or to its surrounding pmtics environment respectively. Therefore, the total pmtics of plasma, in different frame of motion (time), will be different, from one point to another in a given space.

In the future measurements, one has to be clear about all measurements of the Dark Matters as well as the Matter as well as the Antimatter components, as well as all magnetic field components, the likes of the F1 or maybe several F1 configurations in any given pmtics of the initial fundamental plasma. Therefore, there is a need for correct figures for the mass, the weight and the energy of the initial fundamental plasma, because such data are needed for in-depth research and developments of various kinds of applications in Magravs positioning systems using components of Matters of plasmas as the Matmags, for future space travel.

Another point to consider is the Matters environment in which the weight or mass of the plasma is carried out. That is if, this is carried-out in the Matter plasmatic magnetic fields, Antimatter pmtics strength, or Dark Matter pmtics strength environment.

Similarly, the plasmatic magnetic fields' strength in which the measurements are taken should be considered. This being, in what fields strength in the Matter, the Antimatter or the Dark Matter field strength or their respective pmtics energies measurements are taken place.

This is the true nature of the complexity of the relationship with the mass, weight, energy and their interactions in the world of Matters. These cannot be so simplified with one equation of relativity with three simple denotations, if in the future scientists strive to achieve the universal method of producing energy and motion.

The space travellers of the future will come truly to understand that a small error in the measurement of all matters and Matters components, the environmental magnetic plasmatic strength and so forth, can land them in strange and peculiar environments, which these were not planned for or expected. These small errors can end them up in new conditions and positions in the galaxies, which could be nice for experimental purposes, but not necessarily good for the health or the life of the passengers of these future crafts using Matters *Magravs positioning systems* (Chapters 22 and 23).

It is possible that due to miss-calculations, one part of the systems of the future crafts, or even the reactors of crafts, which are creating the conditions for motion or energy, will experience different environmental and Matter conditions than the rest, of the craft or the reactor. As, for example, the same system can land in the border of two different pmtics strength environments, or, in a different plasmatic condition than was originally planned, because of the miscalculation of the Dark Matter Magravs strength.

A physical comparison of the two state of Matters can be for example, considering a cube of sugar, half-submerged in a hot liquid, like tea, where, half of matter of sugar is in the solution of the hot liquid and the other end of the cube being between the fingers of the dipper, in solid state.

Therefore, the question emerges, of how does or can one put the original components of the sugar cube together to get back to the first state of the solid cube, in its original solid state and shape.

The rearranging Matters through the understanding of the Matter energy balance will be the solutions for these kinds of mistakes.

The misunderstanding and potential pitfalls with space technology of the future will be with the miss-calculation of the loading of matters as the "Matmags", and the control in the reactors of crafts of the state of Matters transitions will be interesting.

Nevertheless, the travels and space ventures of the future through miss-calculation of energy balance and wrong Matter Matmags loading will not be without its problems and sorrows, as have been experienced in the short lifetime of the space explorations of today for men whom have dared to test the limits of space explorations.

Who dares, in the space traveller of future, may succeed to have a taste of the pleasure of the unseen in the universe! Our hope is that they come out of these journeys much wiser, but not necessarily less darer than before.

CHAPTER 7

The creation and speed of light

One of the possible ways that light in the universe is created can be through interaction of pmtics' of the plasmas. The speed of light is not considered to be the ultimate speed of Matters. We will discuss how, the interaction of pmtics of the flight systems using Magravs positioning reactors would lead to the creation of light around such a system in the atmospheric conditions like that of the Earth.

Understanding the basic structure of the initial fundamental plasmas, the rationale that the speed of light is the ultimate speed of travel of any Matter becomes questionable.

The phenomenon that the speed of light is the ultimate speed of travel of any Matter(s) or matter(s) is an assumption that has a clear flaw in its concept and cannot be correct for all states of Matters in the universe.

In the iron-based magnets of the solid state of matter, the magnetic fields flow is in one direction, out off the North Pole and their return through the opposite South Pole.

The question that needs to be asked is that, what is the ***speed of the flow*** of the magnetic fields force from one pole to another in solid state of matter?

For ease of understanding let us consider two packs of dynamic plasmatic magnetic fields strength of the pack A and the pack B (Fig. 29), in the path of collision with each other.

The pack A and the pack B can be considered to be of the plasmatic magnetic fields of the plasmas, solar systems or galaxies. The other assumption is that the pmtics strength of these two sets considered not being equal. These two sets of pmtics are supposed to be the mixture of the pmtics of gravitational and Magnetic fields of their respective Matters or objects in each pack.

In considering three snapshots a), b) and c), the motion of the two packs A and B in a given space of time and pmtics strength of the environment area of the D in respect to each other.

a) As the pack A and the Pack B are in motion in space and heading towards each other and these two fields are set to collide with each other (Fig. 29).



Fig. 29: Two unequal pmtics packs heading for collision.

b) Further, in the process of their motion, the two pmtics collide with each other (Fig. 30).



Fig. 30: Two unequal pmtics packs colliding and releasing lower order of pmtics strength as light (C).

c) Further, in the process of the interaction of two original pmtics of A and B, the two fields separate (Fig. 31) and carry on in the universe with some of their fields being released during the collision.



Fig. 31: Two unequal pmtics packs after collision moving away from each other.

Considering the point (b) of impact and collision as in figure 30, as there is no physical matter in these zones, only the pmtics forces can collide and interact.

The collision of the two plasmatic magnetic fields due to their frictions with each other, this leads to separation and production of fragments of pmtics, which some will be of slower plasmatic magnetic fields strength than the two original pmtics of the two original packs.

In case of physical matter, it is normal that when two matters collide head-on, they slow down and some parts of their matter are sheared off and released as fragments.

Through the collision and the interaction of these two packs of pmtics with each other, and the friction between them, these cause separation and fragmentation of some of the same pmtics from the two original pmtics of the two packs. The collision in between two sets of magnetic fields causes some of the pmtics to slow down. In the case of pmtics collision, these slowed down fragments of original two packs of pmtics are slower, and possesses weaker strength pmtics compared to their original two pmtics strength, which were involved in the collision.

We can assume that the original two pmtics plasmas speeds of travel have to be much higher by order of magnitude than the fragments that are created by the collision and interaction of the two packs of magnetic fields forces.

In other word, when two pmtics are colliding with each other, the outcome is partly slowed down fragments of pmtics as the residuals of this collision. These slowed down plasmatic magnetic fields fragments of the collision of the two stronger plasmatic magnetic fields, are slowed enough to appear as, and to be of light magnetic spectrum within the matter magnetic fields strength spectrum of the matter detection zone.

Nevertheless, one can say that, when the two pmtics of A and B collide, the outcome are residual pmtics fragments of the collision, which some of their slowed down magnetic fields fragments created due to their friction and collision, leads to the creation of slower pmtics strength in the range of visible light (Fig. 30 field zone C). Where, this visible range of the magnetic wavelength is part of the overall universal order of magnitude of the magnetic wavelength spectrum fields.

In the universe, when two or more plasmatic magnetic rays, fields, plasmas, of Magravs collide with each other, some of the residual pmtics fragments produced by their collision will be slowed down to magnetic rays or plasmatic magnetic fields strength levels, which the strength of these magnetic rays or magnetic fields are in the range of magnetic fields strength spectrum of the visible light. In other word, the outcome of the interaction of two or more magnetic rays, magnetic fields or plasmas of Magnetic and gravitational fields (Magravs) is the production of light.

This being considered as "one of the prime methods by which visible light is created in the universe. These being the residual of slowed down weaker magnetic fields strength fragments of pmtics released by the collision of two or more pmtics of Margraves of plasmas with each other".

The speed of pmtics fragments, which has slowed down due to a head on collision of two pmtics plasmas, cannot be faster than the original two pmtics plasmas themselves that have caused it to be produced.

Thus, the ***speed of the light***, which is created by interaction of two faster fields' head-on collision, as a fragment and slowed down field, cannot have a faster speed and more pmtics strength than the fields that have caused its creation due to their collision.

For example, by the slowing down of the two faster pmtics of the Earth and the Sun that have not been visible, after collision with each other, and slowing down, they create the slower plasmatic magnetic fields' strength and slower speed magnetic fields in the range of the speed of visible pmtics as of the daylight.

It is correct to accept that "the pmtics, through their collision, have to slow down so that they became slow enough that they become in the range of the slower wavelength in the visible light pmtics wavelength spectrum".

It is obvious that a slower fragment cannot be faster than the fields that have caused its creation. Therefore, "The speed of the light is not and cannot be the ultimate speed of motion" when itself is created by interaction of faster or stronger plasmatic magnetic fields.

In universal order of magnitude of the speed of motion, I consider "the speed of light to be somewhere in the lower end of the overall universal magnetic fields speed spectrum".

Thus, the speed of the light is only the fastest to human methods of detection and not necessarily true in other levels of universal order of motion.

It can be said that the speed of the light is “the ultimate speed that can be attained by pmtics in the Matter components of the plasma”.

Another, fundamental point to realise is that “the speed of travel of light is **different** in a Matter environment than the Antimatter environment and even in the Dark Matter environment”.

Similarly, it is correct to say that “the light created by the interaction of the Antimatter pmtics plasmas and the Dark Matter pmtics plasmas, they have **different** speeds than the light created by the interaction of Matters’ pmtics plasmas”. These faster speeds of magnetic fields than the pmtics of the light spectrum are not detectable by the present tools in the scientific state-of-the-art technology. But their effects and power and strength has been seen and observed in the reactors, which have been built and tested for lift and motion in the past years.

Considering the collision of two pmtics like those of the Earth and the Sun, where the Earth’s Magnetic and gravitational pmtics (Fig. 32 field B) being made through interaction of magnetic fields of Matters in the inner cores of the Earth (Chapter 1), and the Sun’s Magnetic and gravitational pmtics (Fig. 32 fields A) being made by the matters, in the cores of the Star. (In this case, we do not consider the pmtics of Matter, which are released by interaction of matters pmtics on the surface of the Sun).

An example of the creation of the light through the interaction of pmtics:

As the pmtics of Magravs produced and released by the Sun, reach’s’ the boundaries of the Earth pmtic of Magravs, these two pmtics of Magravs collide with each other at the edges of the Earth’s upper atmospheric levels.



Fig. 32: Interaction of three different types of pmtics strength (A, B, C) and the resulting three residual fragment pmtics (D, E, and F).

Where, these interactions leads' to the creation of the pmtics interface, or the **magnetosphere** of the planet. Where, this magnetosphere of the Earth is partially produced at the same time in respect to the other surrounding pmtics of Matters and other plasmatic magnetic fields (Fig. 32 field C) in the solar system as well as the pmtics of the Sun.

Through the pmtics plasma interaction principles, the pmtics of the Magravs of the Sun interaction with pmtics of Magravs of the Earth leads to the creation of new residual ***slower rays and pmtics strength in the light spectrum*** (Fig. 32 field D), where, the overall effect of these pmtics fragments of light generated, leads to the creation of the *daylight* on the Earth, in the interfacing sector of the Earth with Sun's pmtics only.

The light generated in the sector of the planet, facing away from the pmtics of Magravs of the Sun, in interacting with the weaker pmtics of the Dark energy of space around it, due to the weaker plasmatic magnetic fields' strength of these pmtics of Dark energies in space (Fig. 32 field C) and the same constant pmtics strength of the Earth (Fig. 32 field B), in this sector, **weaker strength pmtics residuals** (Fig. 32 fields E and F) are created and released, thus, the appearance of the darker sky or the *night light*.

Thus, the interaction of the *same pmtics* of Magravs strength of the Earth (Fig. 32 field B) with the *stronger* plasmatic magnetic fields of the Sun (Fig. 32 field A) leads to the creation and release of more powerful pmtics strength residual fragments in the light spectrum (Fig. 32 field D), hence **the daylight**. Similarly, the interaction of the *same pmtics* of Magravs of the planet (Fig. 32 field B) with the *weaker pmtics* of the Dark energy (Fig. 32 field C) in space, away from the Sun's plasmatic magnetic fields, leads to the creation of weaker pmtics strength residual fragments, hence weaker lights or dark night light and creation of the translucent plasmatic darkness (Fig. 32 field E and F) light of the night.

As the Earth's reach a more Magravs pmtics strength balance and equilibrium with its environment's plasmatic magnetic fields' strength, thus the darker that part of the atmosphere it appears to be (This principle is described in Chapters 12 and 13).

Through the same principle of interaction of and collision of solid matters of the cosmic dust and the pmtics of the Earth, the northern lights in different colours are created. Where in this case, the light created is due to collision of the matter pmtics and pmtics of Magravs of the Earth.

It is not correct to consider the speed of light to be the ultimate speed of motion, for any pmtics of Matters environments existing within the universe. Similarly, it is conceivable that pmtics can fuse and that their pmtics can increase in strength and consequently they can increase their speed too. (Paper: Creation of magnetic fields).

In principle, the speed of light is not only achievable by the reduction in pmtics of higher order of magnitude pmtics strength, but conversely it can be achieved from the addition or adhesion of the strength of lower order of magnitude pmtics strength too. By the same measure, the pmtics of the light can be integrated, to create their stronger and faster speed of motion, with new and faster pmtics from their interactions too.

The **pmtics strength** and **the speed of plasmatic magnetic fields** is environment dependent and there are no limits in its lower or higher orders of magnitude. Generally, as long as plasmatic magnetic fields can interact, they can add to pmtics speed or lose their speed.

The limitation of speed of travel to plasmatic magnetic wavelength of light is the restriction that Man has forced upon himself, purely due to lack of his understanding of the true construction of Matters of his universe.

The present limitation of the speed of the light for motion is very much similar to the earlier century's hypocrisy and lack of knowledge of Man, with the belief that the Earth was flat and at the centre of the universe.

The pmtics become visible light to the human eye, purely due to the fact that human eyes are adapted through their protein molecular pmtics strength chain, for them to be able to interact and recognise them. This range of the plasmatic magnetic wavelength is translated for the human brain to be the visible light for humans to be able to see and function. Where, this visible range of the magnetic wavelength is part of the overall universal order of magnitude of the plasmatic magnetic wavelength field's strength and not necessarily its ultimate speed.

Thus, "if the human proteins pmtics strength had a different chemical chain, that is to say, if the protein chain did not have hydrogen, oxygen, carbon and nitrogen in its composition, then man would have had different overall pmtics strength in his protein and the universe would have been visible to man in a different range of plasmatic magnetic wavelength field's strength spectrum".

This phenomenon of the protein chain pmtics strength of creation is explained in more detail in the book to be published, titled "The universal order of existence (9)".

Further, in this book we will talk about new nuclear-based systems, which have been developed for them to be able to make use of the creation and control of pmtics of Magravs strength for motion. We have called these systems ***GRA**vitational **PO**sitioning **S**ystems* (**GRAPOS**). From, tests and what we have seen and observed in the past years in proof of pmtics creation and control, the following can be discussed in respect to the interaction of the pmtics of the Grapos Magravs and the pmtics of Magravs of the Earth.

Using Magravs positioning reactors, the interaction of the Magravs generated by these reactors with Earths' Magravs, these interactions of the two of Magravs, by their natural phenomenon of creation and interaction of pmtics, these Magravs interaction of the Grapos reactor and the planet, always leads to the creation of light around these systems in planets' atmospheric environment.

Crafts using **Grapos for lift and motion** in their movement and travel in pmtics plasma of Magravs environments, like the Earth's atmosphere, **these systems generate pmtics fragments of rays of light and appear** to be like **moving *bright lights* in the skies** (Fig. 33 disk 3 and 4).



Fig. 33: Visualisation of Magravs positioning systems (1, 2, 3 and 4) within Earth atmosphere.

The effects of the interaction of the *four different Grapos and their different* pmtics strength and lights they produce around these systems, due to their of Magravs strength in respect to the Earths' pmtics are demonstrated in the figure 33 disks 1, 2, 3 and 4.

The **brightness** of these lights in sky is due to the pmtics of Magravs strength of Grapos' in respect to their environment pmtics of Magravs of plasma strength of the Earth, and these *lights are balance pmtics strength dependent*. Lights around these crafts are produced by the same principles and are similar to the way light is created by stars.

Another example of the Magravs positioning reactors to be used in future craft systems' is, in creating a balanced Magravs strength in respect to the Earth atmospheric plasmatic magnetic fields' strength, so that there would be not much field strength difference and hence nearly no interaction between the pmtics of the system and the Earth. Thus, no or very little light created around these systems as is shown in figure 33, with disks lights 1 and 2. So the system or spacecraft in a given position and time in the Earth atmospheric condition can become dark translucent in respect to the Earth pmtics strength. This giving the impression that, the system has disappeared from the sky, in fact, the system has created its own balance plasmatic magnetic fields' strength condition of dark light in its environment in respect to its environments Magravs strength, while the system still is/or can be keeping the same position in atmosphere. By being able to adjust the Magnetic and gravitational field's strength of Grapos reactor(s), these crafts can change their visual appearance in the Earth atmosphere, from dark to bright light and deemed-light and so one. Four different Magravs strength of Grapos in Magravs of the Earth are shown in figure 33 and figure 55 in disks 1, 2, 3 and 4.

Man can and will travel several times faster than the speed of the light in the future. This will be of his own choosing and limited by his technological advancement and the limitation of understanding of his own tangible existence.

The speed of motion, due to the interaction or gravitational pull of the planets and stars of destination, in pulling the crafts equipped with Grapos towards them is beyond the present technological ability and comprehension of the scientific world, but in time this will be as easily and manageable as daily atmospheric flights of today. Which these crafts can travel several times faster than the speed of light.

The other scenario of collision of pmtics around the Earth could be that when the two field Magravs of the Earth and the Sun collide, and their overall field interactions can lead to the creation of faster pmtics than that of visible light. This again is the result of the amalgamation of two pmtics strength forces from two celestial objects.

Theoretically this is not possible around the Earth as most of the fields of the Earth are outward going and crossing the path of the pmtics of the Sun, and these fields would be carried away and out from Earth's atmosphere and not inwards. Therefore, any amalgamation of two pmtics of the Sun and Earth has to be inward so that Earth's atmospheres can generate the daylight.

This phenomenon of the addition of two fields to create light in the case of the high speed of the plasmatic magnetic fields of the Sun and the Earth is not a common possibility, or there is so very little of it.

By the pmtics theory, in the case of an atom's structure, pmtics of Magravs of the constituent Matters of the electron interact with the pmtics of Magravs of the proton. This creates the fuzzy light around the electron fields in motion, which makes it dimensionally easier to detect the presence of the electron than its nucleus. This fuzzy light being similar and created through the same principle as to the interaction of the pmtics of Magravs of the Sun and the Earth, as was explained.

Considering the interaction of the pmtics of matters on the surface of the Sun: The lights which can be observed from the surface of the stars is primarily due to the interaction of the pmtics of the gravitational and Magnetic field from the centre of the star and their interaction with the Magravs of the plasmas on the surface of the star, where this interaction of the two fields leads to the release of pmtics in the visible light spectrum. The intensity of the light of the stars is in principle due the strength of the gravitational and Magnetic fields generated in the centre of the star, as the pmtics of the hydrogen plasmas on the surface of the Sun are considered to be constant.

We consider the pmtics received by the fields of the Earth from the pmtics from the matters from the surface of the Sun to be small and to be a fraction of the power of the pmtics released due to the gravitational and Magnetic fields from the centre of the star which reaches the planet Earth. The only time when the pmtics of the materials on the surface of the Sun has any effect on the interaction with the Earths' gravitational and Magnetic fields is when there is a surge in the volcanic eruptive activities on the top layers of the materials on the surface of the Sun. These eruptions cause the release of large quantities of physical material of plasmas into the solar system.

CHAPTER 8

Dark Light phenomena

In the previous Chapter we explained that the *visible light* is created through the interaction of Magravs and the *light* created due to the difference in strength of Magravs. Opposite to this, must be the interaction of balanced Magravs strength where the weak or balanced Magravs fields strength, which leads to the creation of a type of night light or dark light at nights.

The point has reached in physics, that these balanced pmtics Magravs strength conditions needs to be considered on their own, where the **Dark light phenomena** can be introduced as part of the science of physics.

"**This Dark light phenomenon**, with Dark light intensity, can be said to be created and be due to the near to, or balanced, equilibrium in pmtics strength reached, or that can be achieved, through the interaction of two or more pmtics forces in respect to each others in a given environment". Where, the intensity of the darkness is pmtics strength balance dependent (Fig. 36 zone C).

The level of measurement of this darkness is not field strength dependent, but *plasmatic magnetic fields strength balance dependent of one pmtics in respect to another pmtics.* That is to say, the interacting pmtics environments can possess any magnetic strength, but in all cases, when the two pmtics strength are ***near equal***, then the darkness phenomenon of the same dark intensity prevails and the same type of dark light phenomenon occurs, irrespective of the original pmtics strength involved.

If this phenomenon is fully understood, just as man has developed night-vision tools, equipment can be produced that can view Dark light plasmatic magnetic fields strength balance in respect to different pmtics strength. Then the universe would be full of new objects that have never been seen in light energy matter conditions.

What a wonderful world would one be in and see, through these tools and machines, Men of vision would take pleasure and treasure by looking through from such a machine.

CHAPTER 9

Relation between Gravity and Light

Through the pmtics theory principles, as gravitational fields are made of interaction of pmtics, and the light being itself made of pmtics, it is inevitable that entities made of the same, will interact with each other.

From previous chapters, it is clear that the light is made of the lower order of magnitude pmtics strength in the overall pmtics strength spectrum in the universe. The light in essence is itself moving dynamic pmtics and that by the principle of this definition **light is energy**. Alternatively, it can be said that the light possesses energy.

We consider that light is a made of pmtics strength of a lower order of magnitude in the overall pmtics strength spectrum in the universe.

At the same time as has been explained, "Gravity and gravitational fields' (Chapter 1) are themselves made of interaction of at least *two **similar** pmtics* or at least *two **similar** magnetic rays*".

It is understandable that, any gravitational field's forces, as an entity, in essence are made of interactions of pmtics. Thus, gravity can and will effect any other entity in possession of pmtics, or entities being made of pmtics, like light. The light and the Magravs (known as gravitational fields) are both made of the same magnetic entities; it is normal that they have interactions and attractions in respect to each other's position.

Fundamentally, it is **not correct** to say that **light is gravitational dependent.**

But, it **is correct** to say that, "the attraction and interaction of **the light rays** in respect to, and from, another collection of plasmatic magnetic fields like **gravitational fields (Magravs) are position dependent".**

In classic physics, the behaviour of the light has been said to be gravity dependent. Through the new understanding of the creation of Magravs, this cannot be correct. As the light and gravity are made of the same magnetic fields of different strength, thus they can have near enough the same speed of motion in matter magnetic field strength medium.

In the case of light rays, when the ray comes in the vicinity of, or in position in space that it can be within a field of, or be near to or in the catchments area of a collection of Magnetic fields or gravitational fields (Magravs), these two entities' magnetic fields interact.

Thus, light is not gravitationally dependent, but in fact the attraction of light is position dependent from a pmtics of any Magravs area.

Thus, the stronger the Magravs of an object are, the stronger the pull.

Following the new principles of magnetic field interactions, the stronger pmtics of Magravs strength of the Matter, the Antimatter or the Dark Matter will exert their gravitational magnetic field forces on the weaker magnetic field strength of the light rays. Hence, the stronger pmtics of heavy matters and the stronger pmtics of stars, the Antimatter and the Dark Matter, pull weaker magnetic fields like light pmtics towards themselves.

So that the visible light will move slower as it will be pulled towards the gravitational force of these stronger, Magravs like stars and Antimatter zones and as it interacts with their pmtics forces.

Light has a different speeds in the Antimatter, the Matter and the Dark Matter due to their magnetic fields strength, very much like as it has slower speed in liquid than in air in the matter environment.

The difference between matter environment and the Antimatter and the Dark Matter environment is very much in that the former is pmtics compactness and density dependent, as in the latter it is pmtics strength dependent.

Thus, light, by the principle of its construction from pmtics, will be pulled and travel slower in other state of Matters and near large and stronger plasmatic Magravs strength of objects like stars, through the magnetic fields interaction principles or the gravitational pull of one stronger magnetic fields in respect to the weaker magnetic fields of the light.

In physics, this has been said to be like the effect of the bending of light when it passes a planet or star in possession of gravitational field forces. The principle of bending of the light, or gravitational lensing in vicinity of, for example, stars is purely due to the interaction of the pmtics of the light with the plasmatic Magravs forces of the star.

It is important to notice that in positions in space, where the Magnetic fields of the star supersede the gravitational fields' strength in respect to any given ray of light, the light ray as well as being able to bend inward due to the gravitational pulls, it can also be reflect away from Magnetic fields forces too.

By the same principle, it is now understandable, why and how for example in strong gravitational fields like black holes areas, even light appears as to get absorbed into them. This being due to the fact that Magravs strength in the centre of the black holes in these regions are so strong, that due to their magnetic fields strength they gravitate the magnetic fields of the light inwards or what they call in common terms "absorb" the light. This attraction is simply a gravitational pull of stronger Magravs strength of Matters and matters in the centre of a black hole in respect to the much weaker magnetic fields of the light.

Most certainly, ***gravity and its field strength is not warp dependent*** or gravity is not caused and is not created because of a warping of the matter in the plane of time and space, as has been discussed in some fields of present physics.


GRAVITATIONAL SYSTEM
LIKE A EARTH
M1
d
A
B
C
G1
G.
M.
W
GRAVITATIONAL SYSTEM
LIKE A STAR/PLANET
OR A BLACK HOLE
M2
d
A
B
C
G2

Fig. 34: Warping path of a weaker Magravs system towards the stronger Magravs system.

Note: Definitely the warping is not the creator of the gravitational fields, but the warping shows the path of the motion of the one gravitational field downward or toward onto another gravitational field.

That is to say, one weaker gravitational field can be attracted towards another stronger gravitational field G2 (Fig. 34), so that the path of the direction of the motion of the weaker gravitational fields G1, towards the stronger, could make the warp like path (Fig. 34 path W) in a given plane of time. This is the warping effect of a ***weaker*** *gravitational field* in respect of a ***stronger*** *gravitational field* and this is the warping path of attraction.

Therefore, warping of the matter is not the cause of the creation of gravity in the matter of the weaker gravitational field strength object, but in fact the warping is only an indication of the path of the attraction and motion of the weaker gravitational fields towards the stronger gravitational fields.

Celestial matters in possession of Magravs, through their internal pmtics and their attractions and interaction and nothing else, can generate the majority of their own gravitational fields in the universe. At the same time, the motion of two objects in the possession of their own gravitational fields can set and start different gravitational fields of one object in respect to the other. That is to say, when two stars in the universe come into each other's catchments zone, the catchments envelope creates its own gravitational pull, separate from the internal gravitational pull of the stars themselves. That is in fact the operation of two original pmtics Magravs being cascaded by the bigger one outside them. The interaction of the two stars, in trying to find their position, causes the swirling effect first and then the warping effect type of motion of the weaker stars' gravitational fields towards the stronger pmtics gravitational field.

External motion of matter does not necessary create gravitational fields inside an object, but the path and speed of the motion of matter indicates the strength of the pull of one field towards another and the direction of the path of the attraction.

There are no planes of references for this warping, as the original point of the reference of the interaction of the two pmtics magnetic fields in respect to each other comes from where, *they first come into touch* and start the first fields interactions; this becomes the plane reference point for the path of the attraction of one gravitational field towards another (Fig. 34)

In fact, the theory of warping creating gravity is as far from reality, as gravity being time dependent.

Maybe it is right to say, "In time, once two Magravs come in contact with each other and stay interlocked, the two fields might merge into one, this time of merger is then pmtics Magravs strength dependent".

As has been explained, Matter is one of the three parts of the Matters of the plasma. Thus, the same interaction between the three gravitational pulls of three Matters within the structure of the Matter (see Chapter 18 and 19) causes the warping and motion of Matters in respect to each other within the plasma.

In fact, any magnetic and pmtics entity, at all times of its existence, is gravitating or will have gravitation towards one or another magnetic ray or pmtics or Magravs in its regions and is warping towards one point or another in space at any given frame of time. That is to say, there are ***no regions in space in the universe, which are void of magnetic rays or pmtics***, and their gravitational interactions and attractions in respect to one field or one Magravs or other.

Nevertheless, there are different magnetic fields strengths, which in one form or another, are gravitated to one or another magnetic fields regions in the universe, in respect to their proximity of distance from a ray or a pmtics.

Maybe we can say "that gravitation in respect to time, is dependent on the position in space and pmtics strength of the any two entities, and that in time, for example light being in essence a magnetic field in origin, it will be effected or attracted or gravitated to another magnetic field or collection of fields, and that these magnetic fields can already possess gravitation in respect to each other.

Thus light rays in given point in space will come in touch with other magnetic fields, which they will gravitate towards each other, for them to merge, where this merger will take a certain given duration.

Thus, the light rays and other pmtics strength have a direct effect on the rate of attraction of one field to another. Thus, speed of attraction is pmtics strength dependent".

In real physical terms, the light itself can be or become one-half of a gravitational field set, so not only is the light getting attracted towards another Magravs system, but also in this process, the light becomes part of a second magnetic field of a gravitational set itself in respect to the first gravitational field. Then this light pmtics becomes part of a plasma magnetic field, which this is, a new set of a light field and the first gravitational field interaction, and this itself becomes another Magravs system like.

The other important point to consider, is the time it takes for the light ray to reach or be attracted into or by a gravitational field, zone or area. This interaction and attraction, is both gravitational field strength, and the light ray's magnetic fields strength, dependent.

That is to say, stronger gravitational magnetic fields, ***pulls*** rays faster to themselves than a weaker gravitational magnetic fields.
Thus, *the time, that it takes for a light ray to get attracted into the gravitational field zone is gravitational field strength dependent and not time dependent,* as the strength of the pmtics of the light of the matter is considered to be constant for all states of Matters.

Then for different Matters (Matter, Antimatters and Dark Matters) in the universe, there should be different *frames-of-reference* of duration or time. As the light created in the matter environment will have different speed in the Antimatter and Dark Matter magnetic fields spectrum environments of stronger pmtics strength regions. While the light created by the Antimatters and the Dark Matters pmtics, interactions have very **different speed** than the light created by Matter pmtics interaction. Secondly, the speed of the light from Dark Matters and Antimatters are much faster than the speed of the light of the Matter state or in matter state pmtics' strength levels.

Some notes about light

1. The frequency of the light wave is created on the same basis and due to the same principles as the change of the polarity in the stars, for example the Suns' eleven years half shift in polarity change (12, 18).

2. By the same principles, the alteration in the extreme points known as maximum and minimum points of return of the waves are Magravs positioning balance dependent,

and not as what has been assumed, electromagnetic field based, as electrons themselves are made of plasmatic magnetic fields.

3. The pmtics as rays, as they enter or come in touch with an atom or an object that they can move or cause motion in the penetrated atoms, electrons of matter or Matter or in their initial fundamental particles, because the matters or Matters components are similarly made of dynamic pmtics, thus, when a pmtics comes in touch with another pmtics, these pmtics interact and collide with each other. Thus, the outcome is a transition of pmtics from one entity to another.

4. The transition of pmtics takes place when the plasmas of Matters come into contact with the initial fundamental plasma of the Matter and they transfer their plasmatic magnetic fields strength from one to another. Usually this transfer is from the stronger to the weaker field strength directional of flow.

CHAPTER 10

The Antimatter



In the world of science, the Antimatter has been considered and said to be the largest source of energy for the future of the energy, space and motion technology.

In the structure of the initial fundamental plasma, I consider that "the Antimatter is the *main component* of the whole structure of the plasma and it is the carrier of the *largest amount and strongest* of dynamic pmtics strength in the plasma, which Antimatter can release the maximum and the larger amount of pmtics strength in the full spectrum of pmtics of energies from the plasma".

To understand what the role of the Antimatter is in the overall construction of plasma, we can simply look at the larger scale of the same type of entity and its effect in the universe. In the universe, the large-scale plasma conditions are said to be the like of the Stars, or the Suns' in their solar systems.

Where, the **Antimatter** part of the plasma is the same as the Star of a solar system, and it is the ***holder of the main quality and quantity*** and the possessor of the ***strongest pmtics strength*** of all Matters of the initial fundamental plasma.

I consider that, the Antimatter is the **source of the energy** and **the central gravitational point of the plasma** as a whole. The Antimatter is in fact the Star of the plasma, thus it is as the Sun to the solar system. In fact, there is nothing "anti" about this Matter component of plasma in the universe.

This is the reason why, in being able to free them from the sub-components of the Matter and the Dark Matter of the plasma, the Antimatter appear to be such a fantastic new source of energy.

As the Antimatter was made initially from the stronger magnetic fields strength in the plasma to start with, hence it holds the real fundamental source and the supplier of pmtics to all matters in the plasma. It can be said that pmtics released by the Antimatter are the platform for the change for almost everything that is made in the matter world.

That is to say, "that Antimatter is the source, where pmtics are positioned to start the change from stronger pmtics strength level in the plasma components, and transfer more of pmtics strength of Matters to matters".

It is the pmtics of the Antimatters, which are transferred in most parts', from one plasma to another, which, causes energy transfer from one molecule to another or one cell to another.

We have used these Antimatters pmtics strength effects in the recent past in our reactors, the pmtics interactions of Antimatters were utilised to create the Magravs forces needed for the Magravs positioning of these systems in respect to another plasmatic Magravs of another object, this being like the Earth's Magravs.

Through tests, it has been proven that the presence of the **Antimatters** and its strong plasmatic magnetic fields that it provides for the creation of Magravs in the reactors is the main reason why, we have managed to lift and move large masses through the gravitationally positioned principle.

In Grapos test reactors, which have been developed and tested for lift and motion, the operativeness of pmtics strength of the Antimatters have been proven to be in line with our theories, where if the pmtics of the Matter were used in these reactors, the Magravs created by pmtics of this Matter would not haven been strong enough to cause the motion or lift of the system.

The scientific world is using accelerators (6, 7, and 8) to slam the plasma into a wall of matter, for the plasma to open and to release its Antimatter sub-components.

In present technology, scientists are trying to understand how to gather and harvest the power of this Matter. It is however crucial to understand that, "**one does not burn the Antimatter as fuel,** as it is assumed by the present scientific world in this field and as Fermilab (6, 7) is considering".

Nevertheless, there is an easier and smoother way to achieve this separation, and that is just to dilute the plasma (Chapter 21), through this method, it will be easy to release the Antimatter from its plasma.

Once the scientific world has a full understanding of how to separate this Antimatter from its plasma, then they will understand that one does not need to burn this Matter as fuel to create motion and energy. But, they simply have to learn **to use the effects of the interactions of the constituent pmtics of this Antimatter** in conjunction with other Antimatters pmtics of other plasmas or Matters pmtics to achieve lift, motion, and for creation of energy, as has been done in the universal order of motion and creation of energy for billions of years.

CHAPTER 11

The Antimatter energy

Antimatters are known to be the sources of vast amount of the **strong pmtics**. The strong fields of the Antimatter are considered to be the major sources of the energy supplied into their respective environment for Matter-to-Matter, and from Matter-to-matter through their pmtics. The ***strong** pmtics*, once released by the Antimatter, and these pmtics in being *in motion* in their environment, they become to be called the **energy of the Antimatter**.

These pmtics by essence of their origin and strength they are, and become, ***strong** energy field sources* and reservoirs of energy in their environment. Where, some of the pmtics within the Antimatter are used to maintain the integrity of the Matter and the plasma itself.

At the same time, some of the pmtics of the Antimatter are equally reduced in strength, and these changes and reductions in their strength of some of the pmtics strength of the Antimatter overall constituent pmtics, these pmtics are allowed then to escape the gravitational fields of their Antimatter pmtics Magravs.

These released pmtics from the Antimatter, become the Antimatter pmtics in motion (energies) due to the strength of their plasmatic magnetic fields' forces. These pmtics can travel *much further* from the Matters and plasma, to transfer their energies to other pmtics in their environment.

These released fields become the Antimatter pmtics in motion (energies), which, due to the strength of their plasmatic magnetic fields' forces, these pmtics can travel *much further* from the Matters and the plasma, for them to transfer their energies to other pmtics in their environment.

Due to the fact that the Antimatter itself is originally made of the stronger pmtics, the Antimatter will let go of pmtics in stronger and wider spectrum of magnetic fields strength. Thus, the Antimatter releases a full spectrum of pmtics strength forces. That is why they are more powerful and covering a wider range spectrum of energy levels as they slow down.

In essence, the **Antimatter** itself starts from a combination of interactions of stronger pmtics bases, and hence has more to lose of its slowed down fields and it has more to attract due to its stronger Magravs too. At the same time, it covers a larger domain as its pmtics can spread further.

In fact, the energies that are released by the Antimatter look to be, and basically are stronger than other energy fields around them, purely due to the fact that they start their life from stronger pmtics strength base in their environments.

CHAPTER 12

The Dark Energy

The principles of creation of the Dark energy as an outcome of normal interaction of pmtics are discussed. The similarities of the Dark energy and force, which are created around Black holes, are in principle of the same origin.

In the dynamic environments of the universe, changes happen due to various conditional factors like motion, compression, turbulence, temperature, and so on, that can individually or collectively lead to concentration or motion of pmtics (energy). These changes in environmental conditions can lead to the manifestation of Matters like the Matter, the Antimatter, the Dark Matter, atoms, stars and galaxies and so on. This is the common fundamental base for the creation of Dark energy and creation of Dark Matters (36) and any dark objects like the Dark Matters, the regular appearance of dark spots on the surface of the Sun and stars (12, 13, 14), the appearance of Dark spots in the galaxies known as Black holes (13), the Dark Rings around Saturn (17) and so on. The creation of these conditions and matters can all be explained through the following interaction of normal dynamic pmtics in the universe.

By pmtics theory, the Dark energy is said to be the ***collection of balanced and equilibrium pmtics strength forces in motion*** in respect to their environments pmtics strength, this being in any given environment, in deep space in the universe or in the centre of an atom and so on.

The universe always possesses equilibrium pmtics strength in its total energy balance, hence the universe possesses more environments which are in pmtics balance strength and hence the existence of vast-spans of the universe which energies are in motion, but due to their balance magnetic fields strength in these regions of the universe, no light through the interaction of various magnetic fields are produced to confirm the motion of the pmtics in that region.

It is important to note, that in the universe only the difference in magnetic fields strength is the cause of creation of visible light from the human observation point of view. Where there is balance and equilibrium in the environment, no lights through interaction of magnetic fields or pmtics are produced. This doesn’t mean that there are no magnetic fields or pmtics in motion (energies) and that nothing is present in that region of the universe. In fact the darkness of dynamic environment of the universe confirms the existence of the balanced magnetic fields strength. Beholding the truth, the darkness of the universe confirms the existence and motion of balance and equilibrium of magnetic fields strength, and not the lack of the existence of magnetic fields in motion (energy).

We have defined Energy as: “**pmtics forces in motion**”. Therefore the Dark energy has the same definition, where in this case, these are **balanced or near balanced pmtics**

strength forces in respect to their environment pmtics field forces in motion.

The universe always possesses equilibrium pmtics strength in its total energy balance, hence it possesses more environments which are pmtics balance strength and hence the darkness of the universe.

Steps in the creation of Dark Energy

To explain the phenomenon of creation of the Dark energy in more detail, let us consider two equal pmtics environment zone A and B in figure 35. These two fields' zones can be for example pmtics from two galaxies in motion in the universe or two pmtics in the span of a plasma.

Before the interaction of the two field zones, pmtics of each zone are interacting with their respective environment, which creates their own boundaries of their field strengths through their magnetosphere boundaries, in respect to their environmental pmtics (zone A with zone D, and zone B with zone D).



Fig. 35: Two equal pmtics strength entities moving in each other path.

Lets assume; a) The universal magnetic fields are always in rotational motion as of D (Fig. 35), and b) The two pmtics of the A and the B are in motion in directions shown. Through their motion and the environmental forces, the two fields zones come to be partially in contact and interact with each other. (Fig. 36)

As segments of pmtics of the zones A and B collide (Fig. 36), and as their interacting pmtics are similar in strength, then there are no differences in field strength for the two pmtics to create the magnetospheres condition (14) or no residual pmtics or very little pmtics fragments are produced from the interaction of these two pmtics zones. Thus in the interaction of two fields and due to balance in their pmtics strength, this interaction **zone C** of fields does not lead to creation of pmtics fragments in the light magnetic field spectrum leading to the creation of pmtics of light (Chapter 7), to make this region light to show the existence and occurrence of collision between two equal magnetic fields strength zones.



Fig. 36: Two equal pmtics strength entities moving in each other path colliding and creating a temporary Dark energy zone (zone C) due to their interaction.

Thus in respect to the surrounding environment the colliding of two pmtics in motion and the lack of production of pmtics fragments strength in the bandwidth of the light in this section of colliding pmtics, this creates the appearance of being dimmer or darker zone (Fig. 36 zone C) compared to its two original zones magnetospheric condition in respect and in comparison with their surrounding pmtics.

In the region of C of figure 36, due to the balance in pmtics strength and the creation of very little residual pmtics fragments, this area has a darker appearance in comparison to the rest of the region which one can observe with the rest of the two zones of A and B in the overall region of the D environment. Nevertheless, the energy of the pmtics in motion of the two pmtics zone of A and B exist and they can be measured, as the two pmtics of A and B move on, this confirms the existence of energy in the dark zone C, where in fact there are no sources for such an energy field to justify their existence in this darker appearing region.

Thus, in the case of the Dark energies zones in the universe, most of the time, one has to look at the overall picture of the interactions of the package and area, rather than to the local zone where the darkness and dark energies appears to be and where pmtics in motion as energy fields are present.

Further on, as the two fields zones A and B are dynamic entities and they are pushed by the forces in the bigger picture of the zone D, the Dark zone C, figure 36 disappears as two zones of A and B move away from each other.

Thus, the interaction and creation of the zone C, figure 36 is a **temporary phase** as the two field zones separate and carry on in their own path and the Dark energy zone C in figure 36 disappears, as there never was a Dark energy zone in that part of the zone D as whole (Fig. 37 fields A and B).



Fig. 37: Two equal pmtics strength entities moving away from each other after their collision.

Therefore, Dark energy zones in the universe are not necessarily a place where there are void of Matters or magnetic fields, but the darkness itself confirms the existence of the balanced pmtics strength in motion in respect to the majority of pmtics strength forces in that given environment, which pmtics in these areas are in balance and in equilibrium in strength with each other in a given point and a given window of motion of fields called time in the span of the universe.

At the same time, these sudden Dark energy regions in space are temporary conditions in a given specific time and specific position from a specific point of observation.

On the other hand if one is inside such a zone not necessarily means that one is in the Dark energy zone. In some cases of dynamic solid gravitational fields of matters in the centre of these energy zones, due to the interaction of the Magravs of the Matters and in level of Dark intensity translucent, inside these Dark energy zones one can have bright zones as being near a star zone.

It is obvious that most of the universe appears as dark, even though pmtics always exist in these areas of the universe and are essential components of its structure. This by itself means that the universe is in pmtics strength balance and equilibrium within itself.

The Dark Matters do not all possess the same pmtics strength and therefore the Dark energies are not all of the same magnetic or Magravs strength, in respect to other pmtics strength environment.

By the same measure, the Dark Energies in the universe do not all possess the same pmtics strength, as their strength is pmtics strength dependent in respect to the environment pmtics strength of their appearance.

In the case of the Dark Matters as sources of the Dark energies, these Dark energies are produced through the initial pmtics interactions in the centre of the Matter, and hence the energy they produce as their overall outward Magnetic fields and inwards gravitational fields, are always in balance in respect to other pmtics in their given environment. Where this balance of pmtics strength gives the Matter the appearance of **darkness**, or darker looking in respect to its overall given environment.

Some of the Dark energies have a Magravs source in their centre in the universe. Thus, these types of Dark energies are part of a Dark Matter source, which are part of the overall magnetospheric environment of the Dark Matter pmtics. These sources of the Dark energies are the Magravs of a matter which in respect to its environment from a given position in space, and due to the equilibrium of the pmtics of the Matter and the environment, cause the Dark energy zone, from that specific point of observation, as that given zone of pmtics interaction appear to be darker than the rest of the environment surrounding it.

CHAPTER 13

The Dark Matter



According to the ***Keshe pmtics Theory of Dark Matters*** "*for an entity to be considered as a Matter, the entity has to possess both Magravs pmtics forces, so that not only the Matter can maintain its Magnetic and gravitational fields, but at the same time the Matter can maintain a balanced pmtics magnetosphere magnetic fields forces strength zone and a magnetic fields mass, for the Matter hold on to its constituent pmtics for it to exist, with the difference with the Dark Matter that the magnetosphere created through the* ***overall*** *interaction of its Magnetic and gravitational fields forces strength of the Matter and the environment pmtics force strength that these two forces are in equilibrium in strength, where the interaction of the pmtics of Magravs of the Dark Matters' magnetosphere and the environment pmtics field force in interacting with each other, they do not create residual fragments pmtics that is in the light magnetic fields strength spectrum level, that makes this Matter visible or detectable, hence the term Dark Matter (Fig. 38 G3)* (36).

At the same time the Magravs forces created by the same Dark Matter appears to create a magnetospheric fields forces' zone around the central Matter, which gives an impression of an energy source that comes from a dark space in a given environment without a visible material source and hence the use of the term **Dark Energy** (Fig. 38 C)."

The Matter is said "to be dark, as its effects can be seen or felt, but, it, is not made observable to the line of vision or is undetectable through detection systems, which are looking for signs of light as means of confirmation of the existence of the Matter"(36).

The Dark Matter can be defined in another way, that is to say:

"The Dark Matter (Fig. 38 Matter G3 field C) is the Matter that, by the interaction of its internal initial pmtics strength, creates the Magravs effects and its external plasmatic Magravs as the magnetospheric field effect for the Matter to exist. Nevertheless, it is due to the overall balanced Magravs strength that are created by the Matter as the magnetosphere of the Matter, being in balanced magnetic fields strength with respect to its given environment pmtics strength, so that the interaction of the two magnetic fields does not creates pmtics fragments in the light spectrum, where the Matter cannot create detectable magnetospheric light."

That is to say, the interaction between two plasmatic magnetic fields strength of the Dark Matter and the second pmtics strength of environment does not create a **visible or detectable magnetosphere** effect, which would be needed to confirm the presence of the Matter in that given environment and in a given position, at a given point in time.

The Dark Matters effect of Magravs energies can confirm its existence, as the Matter that *appears* as Dark or translucent Darker Matter, in respect to its given environment, to the line vision appearance of the Matter, in a given position and time.



Fig. 38: The Dark Matter (G3), the Dark energy (C)

The Dark Matters can be, or, are made of stronger or weaker plasmatic magnetic fields than the Matter, and the Antimatters components of the plasma.

The Dark Matters are Matters which appear as areas in the universe in possession of Magravs forces but no or a very weak, detectable external magnetosphere in respect to their environment at given point and **a given window of transition of time**, where the confirmation of the existence of the Dark Matter is environmental pmtics strength and position dependent.

If one could create the fundamental principles of the Dark Matter, by the use of Grapos, with the production of balanced pmtics strength around the system, then one can travel the spans of the universe with pmtics Magnetic field protection and more or less without any friction, or resistance in the direction of the motion of the system, this allows the system to achieve speeds far beyond the present knowledge of Man in the space and aircraft industries (36).

The same effects of the creation of balanced pmtics strength in respect to the environment can be used to make systems, that without moving; such system becomes invisible to the line of vision at any point in atmospheric condition or in deep space.

The larger entities like of the Dark Matters in scale of magnitude are the black holes in the galaxies, where a large gravitational fields zone is observed and no physical tangible source for the large and strong pulling forces in that region of the galaxy can be seen. These areas, which are usually and mainly in the centre of galaxies or on the edges of turbulent boundaries of galaxies, as there are more Matters, matters, magnetic fields and plasmatic magnetic fields on the move. Where the total balance of these fields, in respect to their given environment, gives these regions an impression to have the appearance of the **darkness**.

These dark regions with strong gravitational pulls are overall temporary events in the bigger cycle of life of galaxies bigger picture of motion of pmtics and Matters (12, 13).

Sudden appearance of Dark Matter as Matter due to changes in fields forces in the environment can be analogised like having a wet cloth that is dry looking. However, by twisting and squeezing the cloth, out of nowhere, drops of water start dripping out of the cloth. The appearance of the water drop does not mean that water was not in the cloth, but in fact it means that the condition were not there to force the water to manifest itself within the cloth.

The Dark Matter can become visible as Matters around their environment pmtics strength changes. On the other hand, the Dark Matter can become visible Matter when there is a change in the internal pmtics strengths of the Dark Matter, which the change in magnetospheric strength of the Dark Matter, changes the magnetosphere pmtics strength in respect to its environment pmtics strength and the Matter becomes visible. That is why the Dark Matters are environmental pmtics strength dependent. The appearance of Dark Matters, due to changes of their pmtics strength or environment pmtics strength changes have been seen in the universe by scientists and they call these, the Virtual matters or the Virtual particles (Chapter 14).

Dark spots on the Sun and Black Holes

The Dark spots on the surface of the Sun; These effects are usually seen on the dynamic surface of stars, where large numbers of similar pmtics strength materials in motion interact with each other, and hence there are more possibilities of having balanced pmtics strength regions, as most of the matters are of the same structure of hydrogen plasmas.

The main reason for the increase in the levels of the dark areas and dark spots on the surface of the Sun, about every eleven years, is due to change of polarities of the Magravs created by magnetic fields in the centre of the Sun. This increase is purely and only due to one factor, this being that the creation of dark spots on the Sun is primarily due to the interaction of pmtics of the matters on the surface of the star and the pmtics of the Magravs from the centre of the star. As at time of polarity change of the star, there are more chances of the interaction between two pmtics, which are made by the components of the same matters (Hydrogen). Thus, there are more chances of reaching Magnetic strength equilibrium conditions between the surface pmtics strength of the matters on the surface and the internal Magravs' fields strength created in the centre of the star. Where at these points of balance zones of pmtics strength, no or very little pmtics fragments in the spectrum of light are created, hence the reason why appearance of the increase in the number of dark spots on the surface of the Sun during the polarity changes of the star (12,13).

Thus, the dark spots of the Sun are natural outcomes of the balance interaction of the pmtics strength of the overall Magravs created by the centre of the Sun in respect to the pmtics strength of the plasmas of the materials on the surface of the Sun. Thus, as there are more balance pmtics areas produced, a higher number of darker zones can be observed on the surface of the Sun.

The darkness of Black holes in galaxies, and the Dark energy fields they produce in their environment, are due to the same process (12, 13). Similarly, all Dark energies are not necessarily connected to the central Magravs of the Dark Matters.

The Dark Matter and the Dark Energies appear and behave as dark regions, in respect to a given magnetic fields strength environment, at a specific point in time and space, and specific conditions from the point of observation. By the same principle, the Dark Matter and the Dark energy will be a visible or tangible Matters or matters in a different pmtics strength environment and even from another point of observation.

Therefore, state of the Matters, this being the Matter, the Antimatter, the Dark Matter appearance and detection of their energies are totally pmtics environmental respective dependent.

That is to say, "what is **the *Matter and the energy*** *in one given plasmatic magnetic fields' strength environment* can become *the* ***Dark Matter*** *or the* ***Dark Energy*** *in another pmtics strength environment* to the human point of observation".

In the universe, the Matters and the Matter energies or the Dark Matters, the Dark energies, the Antimatter and the Antimatter energies **change from one state of Matter to another**, or one **state of Matter energy to another**, purely due to *the respective Magnetic fields or gravitational field* strength as of their environments pmtics strength as these Matters and energies pass *through them*.

In the micro and macro universe, suddenly Matters and energies ***appear*** **out of nowhere** and **Matters and energies suddenly *disappear* into nothing**. These appearances are all pmtics strength respective environment dependent as the Matter or energies pass through a given field at a given time in their immediate environment.

The universe is considered by us to be covered with the Dark Matters and the Dark Energies. In general it can be said, where there are no faster or slower pmtics, or differences in pmtics strength, interacting or for other pmtics of the same or different strength to collide with, through these balanced pmtics strength regions, there are no unbalance fields to create friction or to have an interface or to have residual pmtics between the environmental and the moving pmtics, these regions in the universe give the appearance of lack of *Matter,* or the Dark Matter or the existence of Dark energy in respect to the given point and position in the universe. This means that the dark regions of the universe are balanced in pmtics strength, and *not void of pmtics*. Hence as the universe is magnetically strength balanced, therefore the universe, in general, appears dark and empty, even though the universe has no regions without magnetic fields.

These types of darkness can be see-through and can be transparent through their pmtics energies; I call these areas the "***translucent Dark energy zones***".

This translucence state of position in a given environment is a state where, there is total darkness but at the same time, there are pmtics strength field interactions that allow enough light, in respect to vision and detection for one to confirm the lack of light.

This being the reason why, one can see or detect, other Matters or matters through this universal Translucent Darkness light.

This light in the span of the universe is due to the interaction of very weak pmtics in motion (energies) in the constituent universal pmtics soup. In fact, these dark regions of their environment are where the pmtics are in balance within these regions.

As was discusses in the previous chapter, to the human eye protein pmtics balance set, these residual fields of the two pmtics interactions, due to their pmtics strength balance, appears as the Dark Matter and is like Dark energy zones in space. If humans would possess another chemical pmtics protein chain, what are the Dark Matters and the Dark energies by present means of detection, by viewing through different tools of vision, then these areas will be as visible light regions of the universe, and may be in different colour, for example in the Antimatter colours spectrum of the universe, or even in the Dark Matter colours' spectrum of the universe. Through the use of such tools, the importance of the use and function of the Dark energy (Fig. 36) and the Dark Matter (Fig. 38) will be soon grasped by men of vision, to see the true darkness. Where in the colour spectrum of the Antimatter the colours are magnetic fields strength dependent and these colours are not noticed by the human eye matter-based protein pmtics. The same applies to the Dark Matter colour spectrum.

In the universal order of containment for Matters and energies, it is not far from the truth to say that the state of Dark Matter is the same as gasses in matter state, that the Dark Matters and Dark energies do not have self-containment.

That is to say, "As with gasses in a state of matter, Dark Matter fills all the environment and space that is given to it, as it creates no effective magnetospheric interface boundary resistance in respect to its environments' pmtics strength forces.

The boundaries of the Dark Matters and Dark energies are dictated by the boundaries occupied by stronger or weaker pmtics strength regions around them in their given points in the universe."

The forces of Dark energies can be confirmed only through their interaction with other plasmatic magnetic fields in motion, in respect to the field of the Dark energies motion themselves.

That is to say that the dark lights generated by the Dark Matters and Dark Energies cover the whole of their given spaces, this being the space in-between different Matters in the atoms structure or solar system or even galaxies, I call this ***principle of creation of dark light*** strength difference of pmtics magnitude needed for creation of light, the **principle of pmtics magnitude**.

It is very correct to assume that one atom of Dark Matter and its Dark energies can be and/or is enough to span its balanced pmtics to cover the whole of a solar system, or its bigger counter part galaxies or smaller spaces as the space in the pmtics Matters of one tangible atom.

CHAPTER 14

Virtual Particles (Virtual Matters)

The existence of virtual particles, *which appear out of nowhere*, and have the characteristics of real particles in essence, has been described in the Dark Matter section of this book. The method by which these particles appear within their environment is exactly how the Dark Matters do exist and appear in their environment, after their overall Magravs, magnetosphere strength changes' or due to changes in the pmtics strength of the environment.

In fact the virtual particles are individual atoms' or plasmas, or any Matters, of the Dark Matters behaviour' (Chapter 13, and reference 12), which when they come into new pmtics strength environment *which is **different** than their previous balance condition* pmtics strength environment with their Magnetic field and gravitational fields, then these particles generate a new magnetosphere in respect to their new condition pmtics strength environment, thus they create light due to their interaction of their plasmas (Chapter 7) and so they appear *as **new matters or virtual Matter***.

There is nothing new about virtual particles; these are like loose plasmas or a single atom in the soup of the universal Magnetic and gravitational fields.

Thus, in simple way according to ***Keshe Theory of creation of Matters***, virtual particles are Matters and behave like Dark Matters. They are created from the interaction of at least two pmtics, which leads to the creation of Magravs of the Matter, therefore what scientists call virtual particles, these are real Matters, which due to the change in their environmental magnetic fields strength condition, they suddenly ***appears as matter(s)*** for *a very short time*, until they lose their pmtics strength or their environment pmtics strength changes or as they move out of the environmental pmtics strength level or they seem to disappear.

Virtual particles possess a magnetosphere and the light they create in their new environment is due to the interaction of their pmtics of their magnetosphere with the pmtics of this new environment, which makes them visible in that given point and given time.

Note: When the (virtual) particle(s), Matter(s) or matter(s) is moving towards the observer due to it's ***compacting of pmtics***, this creates the blue shift colour of magnetic wavelength spectrum (Chapter 7). If the virtual particles are moving away from the point of observer, due to ***opening of the pmtics*** of the environment, they create light in red shift colour of magnetic wavelength spectrum. (This is described in the paper: Creation of Magnetic field).

The virtual particles are actually individual nano-atom or plasmas or sub-Matters of plasmas.

The Casimir effect

In present physics, virtual particles are related to Casimir effects.

First of all, the Casimir effect and the photon energy appearance in its setup of its confirmation is always considered to be in a **vacuum condition** between two conductive plates where, photons in between two plates are observed and electrical charges are measured.

In fact, it is not important what vacuum condition level can be achieved in test laboratory conditions, nevertheless still a number of pmtics, Matters, plasmas (electrons and protons) and atoms could be left in the space between the two plates, which are under observation.

As matters are made of plasmas of interacting magnetic fields of Matters, when the space in between the plates is freed and void of most of its atoms and Matters, at this point the leftover matters or Matters between the two plates are more free to move in the newly created condition environment. Hence it is natural that these residual atoms, electron plasmas, proton, can move really in empty space and can collide with the walls of the matter of the two plates and due to their interaction fragments of pmtics strength are released which these are in the range of the pmtics strength of photons.

So vacuuming the gap between the plates creates a new environmental plasmatic magnetic fields force condition that allows a more free motion of leftover Matters and atoms in between the two plates, where in fact the boundary of the magnetosphere of one atom can occupy or expand the full span of the gap between the two plates.

Casimir effect measurement is a good tool to measure how many atoms and/or what Matters are left in the gap between the two plates at a given vacuum level.

We have done experiments in plasma dilution reactors, which we have developed and have seen the Casimir effects. In these tests, we have seen some serious voltages and currents, but never photons. Which indicates that these voltages can only be from Antimatter source in-between plates, as matter cannot produce these levels of voltage and amperages.

In a number of tests we have created 30 mm gap between plates and the results have been the clear indication that Casimir effect testing is good to find nearly the number of Matters in between the gaps, and types of Matter which are left in between the gaps. As **Matter and matter** create *different charge levels* than the **Antimatter** components of the plasma.

We have created environments of 10 (-9, -10, -11, and -12) bar in our tests, and in tests over 10 (-8) bars there was not much difference in voltage and current measurements from both plates' terminals. This indicating that it does not make much difference how far one can vacuum the gap in between the plates, there are still some components of Matters or matters will be present in the gap, which can move with more freedom than before. Where this small number of matters or Matters in-between the plates can transfer energy through the free motion of their plasmas in collision with plasmas' of matters of the wall and lead to the release of pmtics fragments in the strength of the light magnetic field spectrum or a photon.

Van der Waals forces

In respect to the Van der Waals effect, this **push and pull effect** is now very clear and easy to explain, this is to say as plasmas contains all Matters (Matter, Antimatter and Dark Matter) and these Matters are all made from the interaction of plasmatic magnetic fields, which leads to the creation of their Magravs, so that each Matter is *like a* ***independent entity*** within the structure of the plasma, at the same time plasma possesses its own Magnetic and gravitational field forces.

By the same measure, the atom, as an independent system, possesses its own Magravs in respect to other atoms in molecules. The same, the molecules have their own Magravs in respect to each other.

Therefore, what has been considered as Van der Waals forces of push and pull of molecules, these are simply Magnetic and Gravitational field forces or Magravs forces of one molecule in respect to any other molecule.

The Van der Waals force is in fact the pull (gravitational effect) and the push (Magnetic effect) of the individual molecules in respect to any entity (atom, molecule) around them.

CHAPTER 15

Interaction between Matters

Different Matters in their environment interact and create different conditions, and state of Matters are similar to the state of matter, as one can mix liquid with solid and gas with liquid in state of matter, the same can be done with different states of Matters, like allowing the pmtics of the Matter to interact with the Antimatter and further the Antimatter with the Dark Matter. As in the case of Matters, they are all pmtics strength dependent, where these kinds of mixings of states of Matters allow more profound effects to be developed. This kind of mixing between the state of Matters will open new world of science to mans' encyclopaedia of knowledge ***Matteorology*** *(knowledge of Matters).*

The process by which, Matters are created and operate in respect to each other within the construction of the plasma has been explained in previous chapters. These Matters individually possess their own properties and create their own effects in respect to their environment, both individually and in conjunction with each other.

What is important to understand is: *What happens when these Matters interact or come to collide with each other within the plasma or their environment?*

What is the outcome of the amalgamation of the plasmatic magnetic fields strength of different Matters with each other?

Let us consider some of the variations between interactions of different Matters.

Interaction of Matter with Antimatter

The Matter is composed of ***weaker*** Magravs strength than the **Antimatter**. In this case, the Matter always gets attracted towards the Antimatter.

In the case of the plasmatic magnetic fields of the Matter ***colliding*** with the plasmatic magnetic fields of the Antimatter, the Matters components will **get *absorbed* into** the larger and stronger pmtics strength, by order of magnitude, of Antimatter.

What can be observed from this impact is the release of some plasmatic magnetic fields residual as pmtics, like release of some lights or rays or magnetic residual. The content of the dynamic plasmatic magnetic fields of the Matter or its energy is *absorbed into the environment of the Antimatter* and gets mixed in within its structural magnetic fields strength. At this point there will be no more signs of the Matters past existence.

Where, most of the rays released in this interaction are mostly due to the coming close of the two Magravs of the two Matters, rather than the splashing of the pmtics from the surface of the Antimatter.

This is like when a drop of water falls into a cup of tea, in this case, the drop of water becomes part of the larger teas' liquid.

Majority of scientists working in this field, are lead to believe, as the Matter and the Antimatter collide, due to their charge balance after the impact, the content of the two Matters ***disappear into nothing***, except some residuals released as energy, gamma rays or photons, then, in their opinion, there is nothingness left as these two Matters' charges balance each other out.

Such a belief and concept is against any natural laws of existence. That is to say, there cannot be a position of total annihilation of both Matters, where there can be nothing left at all after the two actual Matters in possession of Magravs collide with each other. This nothingness of the two Matters after the collision of the Matter and the Antimatter is a rash assumption and incorrect.

In fact, the Matter and so-called the Antimatter by their pmtics strength order of magnitude in the matter world, is like the Earth slamming into the Sun, and then saying that after this collision there is nothing left of the Sun and the Earth, except some outwards splashing fragments of plasmas from the surface of the Sun. This is illogic attempt at a scientific explanation for such a real physical event.

The Matters of the Earth would cause a small splash on the Suns' surface. This splash then releases some plasmas or gamma rays or photons from the surface of the Sun. Then the plasmatic magnetic fields components of the Earth become part of the plasmatic magnetic fields of the plasmas of the Sun. This is exactly the same incident as when pmtics of the Matter collides with pmtics of the Antimatter.

In view of this principle in physics of the conservation for energy, ***nothing in the universe is lost or can disappear***. They just change their magnetic fields strength and their compactness from one form and level to another.

Thus, collision of the Matter and the Antimatter create nothing but the Antimatter, with more content of different plasmatic magnetic field's strength of the Matter components inside it. Therefore the outcome of this collision is mainly the Antimatter balance remaining.

Interaction of Matter with Dark Matter

This follows the same principle as the previous states of the Matter and the Antimatter. The content of the Matter then becomes the constituent Matter of the gravitational centre of the Dark Matter. With the difference, that in this case the Matter will not have to overcome any magnetosphere of the Dark Matter.

This interaction will be the same as seen in the universe matter dimension, where for example Stars and cosmic matters disappear into a Black hole in the universe.

In some instances, this process can disturb the overall Magravs' strength balance of the Dark Matter in respect to its surrounding plasmatic magnetic fields strength. This change can induce the production of slightly stronger or weaker magnetic fields strength magnetospheric conditions of the Dark Matter in respect to its surrounding field's environment.

In these rare cases, due to the change and unbalance of the magnetic fields strength between the new content and new Magravs strength of the Dark Matter, this new stronger or weaker plasmatic Magravs strength, allows the creation of a new magnetosphere field strength of the Dark Matter in respect to its environments pmtics strength to take hold. Then, what was the Dark Matter in a given environment, can in the same given environment, with a different and new plasmatic magnetic fields strength, now create and possess a new magnetospheric field strength zone in respect to the same environment's pmtics strength and then the Dark Matter can become like the Matter that is more visible.

This incident has been recorded by cosmologists a number of times. Where, *out of nowhere*, Matters appear in the Dark spaces of the universe.

In fact, even changes in the tightness of plasmatic magnetic fields in the span of universe, can unbalance the Dark Matter environment pmtics strength and make the Matter visible.

This magnetic unbalance of the environment causes different balance condition around the Dark Matter pmtics, and then out of nowhere stars appears in the Dark spans of universe.

The interaction of Antimatter and Dark Matter

In the case of the interaction of the Dark Matter and the Antimatter, there are clearly several scenarios, which are possible.

1) Scenario 1

This case is the most probable and is considered to be the norm. This interaction is a collision of the giants of the Matters of the plasmas‘.

Assuming that this scenario of interaction takes place within the environment of an initial fundamental plasma.

Considering the construction of pmtics strength of the Dark Matter and the Antimatter, when, these two Matters of the plasma collide, the outcome is normally production and release of new and balanced plasmatic magnetic fields environments. In this case, it is considered that each of the Matter's components of the plasmas keeps their pmtics strength plasma status.

Due to the enormity of the quantity of the amounts of the two plasmatic magnetic fields of the ***Antimatter and the Dark Matter amalgamation*** (denoted as **A-D Matter**), new supersized, unstable giant plasma is initially created. This new plasma needs to reach stability over the entity of the plasma as a whole for it to survive. Thus, the new super giant plasmatic magnetic field has to find a new Magnetic and gravitational balance and equilibrium within itself.

For the new giant plasma to reach the new equilibrium condition, the new plasma has to, and always does, release its excess plasmatic magnetic fields into its surrounding environment. The new released plasmatic magnetic fields have to be in balance by themselves too, for them to exist and stay within the gravitational fields of the A-D Matter.

This new release of excess plasmatic magnetic fields near to A-D will contain some of the Antimatter, some of the Dark Matter and some other newly balanced interacting and attracting weaker plasmatic magnetic fields of different strength in the Matter pmtics strength level. These *weaker fields* are mainly from the leftover weaker fragments of the collision of the two giant Matters. These new released small bundles of weaker plasmatic magnetic fields strength themselves due to their proximity and their source of origin, these usually bunch-up and become a new *miniature plasma version of the original initial fundamental plasma within the A-D Matter.*

At the same time, this newly created mini-plasma still has to keep it's own balance and the balance of the whole of the original Matters pmtics and stays' within the Magravs hold of the giant A-D Matter mixture. This mini-plasma creates its own Magravs and then this mini-plasma has to have a Magravs positioning in respect to its original initial fundamental plasma. Thus the new mini-plasma is forced to take a new position and new gravitational positioning in respect to its larger neighbour of A-D and it is at this point that it is forced out of the A-D Matter plasma environment, but still in A-D Matter Magravs catchments' area, therefore this mini-plasma attempts to stay in the orbit of its mother seed, and becomes the **initial fundamental satellite plasmas'** of the original A-D Matter.

Further on with the same process, the A-D Matter mixture has constituents of two unbalanced and un-matching plasmatic magnetic fields strengths of the Dark Matter and the Antimatter within it, at some point, the two Matters plasmatic magnetic strength fields separate and the balance returns' to a new central plasma. By this time the central plasma due to this interaction, finds itself with a new rotating satelliteing smaller plasma.

It should be noted that pmtics of different strength ***never mix*** with each other, however they can be ***influenced*** by each other.

The collision of the Dark Matter and the Antimatter, and creation of new satelliteing mini-plasmatic Magravs rotating around the central plasma is the ***creation of the electron*** from the interaction and collapse of theses two Matters of the initial fundamental plasma. The interaction of the Antimatter and the Dark Matter of the Initial

Fundamental plasma leading, to the creation of a new central plasma and its satellite mini-plasma, lead to creation of **Initial Fundamental Atom** (hydrogen atom). This is what I call the initial fundamental decay of the initial fundamental plasma, or decay of the neutron.

The collision of the Dark Matter and the Antimatter is usually due to unbalance or some deviation in the plasmatic magnetic fields' strength of one Matter or other within the confine of structure of the plasma itself.

2) Scenario 2

This scenario happens usually when the F1 collapses altogether, sending the two giants Matters of the plasma, the Antimatter and the Dark Matter, to collide head on.

In this case, there are two possibilities, which remains open to the new A-D Matter plasmatic magnetic fields.

A) The first possibility is that the plasmatic magnetic fields of the Dark Matter superimposes the Antimatter plasmatic magnetic fields.

By this process, the outcome will be a giant size plasmatic region of the Dark Matter and energy in the plasma.

This new giant Matter, due to the interaction and amalgamation of the two sets of plasmatic magnetic fields strength and their Magravs of its two separate Matters will have large-scale gravitational pull system, with no clear magnetospheric zone boundary in respect to interaction with its outside plasmatic magnetic fields strength environment as before.

This will be a giant gravitational region that will have massive pulling effects, but its core cannot be seen due to the lack of interaction of its magnetospheric condition with its environment's pmtics. Therefore, this region even possessing enormous amount of gravitational field pull has no balance interacting Magnetic field strength or a balance Magravs strength in respect to its surrounding pmtics strength. This Matter seems as if it does not exist, or appears to be Darker than it's surrounding. Around this area, enormous gravitational pulls' can be detected, but the cause of all the pulling and where the gravitational pulls is coming from are not clear and obvious. Where, this darkness is purely due to the balance magnetic fields strength of the magnetosphere of this Dark Matter and being too similar in strength in respect to its surrounding environment pmtics strength to be able to generate the magnetospheric light.

Thus, this area is and looks like as a giant eating machine, which has a lot of energy and gravitational pull, but no visible source to show for its Dark energy as was explained before (36) and the Dark Matter. This condition is usually referred to as the ***Black Hole effects*** (13).

In fact, the only way that one can say that the Antimatter is cascading in this case by the

Dark Matter, is by observation of the appearances of the interaction of the Matters Magravs patterns of the magnetosphere of the whole structure from the outside of the structure.

In these cases of cascading, where the two pmtics strength at the point of separation between the Antimatter Magravs strength and the Dark Matter Magravs strength, internal layers cannot mix due to their different magnetic fields strength, this interaction between two different pmtics field strength at this magnetic interface, creates an ***internal pmtics-interface zone***. Where, this pmtics strength interface zone creates a different zone gravitational and Magnetic field strength on the outside of the magnetosphere surrounding environment of the cascading Dark Matter, and the position of this zone on the outer regions of the Magnetosphere of the Dark Matters are in position and in-line with its physical position of the pmtics interface in the infrastructure in the centre of the cascaded Material.

This internal interface plasmatic magnetic fields zone can create ring-like zones around the outer boundaries of the Dark Matter magnetosphere, where these rings are like different colour or light intensity rings around the whole of the outer boundary of the Dark Matter in respect to their environment pmtics. Where, the thickness and the width of such a ring is equal to the thickness of the embedded Antimatter component.

The physical observation of these effects of the pmtics-interface strength can be seen in the gaseous planets which have initial solid core centre, and where different pmtics strength zones interfaces of different Matter layers are created internally due to their internal pmtics interfaces, as each interface is seen as one ring in the extended magnetosphere of the giant gaseous planets.

These type of magnetospheric rings are usually seen around the gaseous planets with a embedded and initiated solid matter centre cores, and as a number of different layers of the same or different gases are superimposed on top of each other over the life time of the planet. Where the solid matter due to temperatures of its blanketing of gases has become to be in the fluid state-of-matter and creates its own plasmatic Magravs forces. Which the Magravs of matters core interact with the Magravs of the gases in different layers, and/or gas-to-gas of different layers. Where, at the interface of each layer of matters, different Magravs strength are generated and their regions and position of pmtics Magravs strength balance are observed, as one ring related to that specific interface, around the outside of these planets magnetosphere environment in their solar systems. This is exactly how the rings of the Saturn and the Jupiter are created (17, 18). In fact if one could count all the numbers of the dark rings of the Saturn, one should be able to say how many layers of gasses the planets has in its constituent inner structure. This is like counting the rings across cutting of the trunk of a tree to establish its age. How these rings have come to be made and how layering of different gas layers have been achieved by the planet Saturn has been explained in full in the papers under reference 17 and 18.

These multi-layer gas rings actually can bee seen around some stars too, but these are hidden within the intense light from the surface of the star.

The application of multi-solid core and rings in Magravs positioning reactor

When this principle is used in a Grapos reactor, this gives the system and craft a major impenetrable multilayer magnetic shielding ring for protection from cosmic dusts or in defence technology for maximum shielding from incoming asteroids on the path of high-speed crafts (17, 18, 29, 33). Or these types of magnetic multiple ringing can be used around a craft for submerging in deep ***liquid environments*** (29, 33). Where, the craft using these systems become liquid-sealed and Magnetic field and gravitational depth positioning, and temperature independent.

B) The second possibility, with this interaction is that the Dark Matter's plasmatic magnetic fields moves to the centre of the Antimatter's plasmatic magnetic fields region.

In this case, the Dark Matter plasmatic magnetic fields are superimposed and they are cascaded by the Antimatter plasmatic magnetic fields.

Considering that this scenario happens in the environment of the initial fundamental plasma and between its Dark Matter and the Antimatter components. In this case, again, giant plasma of double layers of the Antimatter and the Dark Matter is created and the new plasma will suck-in the Matter components and the electron or another pmtics around it into itself as before.

Nevertheless, this interaction gives the impression of a sudden expansion of the Antimatter as a bright Matter. That is to say that the magnetospheric zone of the Antimatter becomes the total magnetospheric zone of the central plasma. Thus, this new combination of interactions will have a new plasmatic Magravs strength of the three Matters. These being the contents of plasmatic magnetic fields' strength of the Matter, then the Dark Matter and then the plasmatic magnetic fields of the Antimatter.

All these Matters again as previous scenario being cascaded this time by the pmtics of the Antimatter. Where, the weakest pmtics strength of the Matter will be in the centre, superimposed by the plasmatic magnetic fields of the Dark Matter. Then, these two Matters are superimposed by the pmtics strength of the Antimatter on the outside.

The new giant combination of three Matters at this stage is a super plasma size, and this is a temporary condition and is called the Nova state of the three layers Antimatter cascading of the plasma.

Where, the Antimatter's strong plasmatic magnetic fields strength are on the *outside* and create enormous amount of light compared to when there was a balance state of the initial fundamental plasma. This sudden expansion of the Antimatter due to ballooning of the other Matters inside the cascade gives the impression of a sudden expansion of the bright plasma, or what is called a ***Nova condition***.

Sometimes in stars, due to the internal interacting dynamic plasmatic magnetic fields of the plasmas, and through natural process of interaction like fusion or fission or nuclear decay and generation of weaker fields in the centre of these objects, Dark Matters and

Matters pmtics strength conditions are generated and held in the centre of the star.

This generation of new Matters *internally* will cause the expansion and ballooning of the volume of the star initially for a short time. Further on, at this point, as the content of the new-cascaded plasma of Matters can push its boundary to limits beyond the internal central gravitational strength pulls of its three different Matters, then the star explodes in its environment.

This explosion leads to the total release of the internal plasmatic magnetic fields of all its constituent Matters and pmtics inside the cascade. Therefore, these Matters and plasmatic magnetic fields can again start new interacting conditions and environments. Henceforth, the whole cycle of the creation of fundamental particles, then initial fundamental Matters, plasmas, atoms and matters starts again.

This is in fact the normal cycle of the process of interaction and attraction of plasmatic magnetic fields strength in their confined of their environment. There is nothing more and nothing less to this natural cycle of regurgitation of plasmatic magnetic fields of different strength and conditions that these create for themselves and the effects they create to secure their existence.

That is to say, in the case of the plasma, this becomes the release of some particles, which gets absorbed by the other atomic plastic structures around the plasma.

In the case of a star, this becomes an exploding star, which its constituent plasma after disintegration becomes part of the soup of the galaxy and the content of the star gets absorbed in, for regeneration of new stars and so on. In the case of galaxies, this is the same; further on the same happens to universes and so on.

There is the possibility of another scenario for the same new cascaded materials, and that is:

Once the Nova is created and it is not allowed by the external field force in its environment to expand its boundaries beyond its combined internal Magravs' strength, it is at this point that, the *internal* gravitational fields of its three Matters interactions starts to lock into each other and create one overall Magravs force in respect to their outside environment.

This new overall plasmatic Magravs force, which is created due to the interaction of plasmatic magnetic fields of the three layering and three different pmtics strength of the three Matters (the Matter, the Dark Matter and the Antimatter) in conjunction with each other [This is a similar principle to the systems of three internal layers for creation of gravitational field forces of the planet Earth as explained in Chapter 1 (12, 18)], once this new gravitational fields forces takes place and takes hold, and becomes operational, then purely due to its interacting layering gravitational strength magnitude, and the span of its coverage the Matters of the cascade will start pulling all three plasmatic magnetic fields components of three Matters tightly to itself. This causing the retraction of the matters of the Nova and hence contraction of the Nova. The Nova volume shrinks, in response to the new created three layers interactions' Magravs strength.

Thus, by the time all the Matters settle down to their new position, this new plasma will be a condensed Matter of all sorts. As each Matter layer, due to their plasmatic magnetic fields strength will hold onto their position within the construction of the cascaded plasma. Once, the new matters settle into their new positions from the previous giant Nova condition, this new plasma state of the three Matters will be a fraction of its Nova size. Nevertheless, its size will not be equal to the total size of the collection of all three previous Matters and its initial fundamental plasma size, but its overall internal gravitational fields strength will be enormous compared to its past when it was the whole initial fundamental plasma.

By the this stage the content of the outer layer is still active plasma with bright lights of the Antimatter, but due to the new strong internal gravitational pull of the Matters, even the light that is created through the interaction of plasmatic magnetic fields in the outer regions of the Antimatters, interacts with the strong internal field of the cascaded materials and converges inwards (Chapter 9). This giving the impression that the plasma or the Star is dormant or dying, but in fact the systems has never been as powerful and active internally as this in its whole existence even as plasma or as a star.

Interaction of plasma with plasma

Another possible scenario in interaction of collection of Matters as a plasma, is in collision with another collection of Matters as a plasma.

Electron interaction:

i) For example, there is the possibility that the plasma of the electron can be fused into the plasma of the central nucleus of its proton.

“I have called this interaction and fusing of the electron to its proton plasma the ***inter-atomic fusion principle*** (37). I consider this method to be a simpler and more practical to achieve fusion for production of energy, than the path being followed by the present scientific world in fusion reactors technology in trying to fuse two large plasmas of the proton, without any tangible success up to now after over fifty years of research and development to attain any sustainable fusion cycle to produce usable energy for domestic market. These systems being like of the Jet project (Tokamak) in UK and the present upcoming ITER (Tokamak) project being built in the South of France at the cost of over ten-billion US dollars investment with the final goals of only to produce for a few milliseconds of energy within 10 year’s time.

The process of the inter-atomic fusion is shown step by step in figure 39.


A1
B1
G1
C2
A2
B2
G2
C1 A3
F1
C3
B3
G3
1
AN ATOM
2
PROTON
ELECTRON
3
4
5
6
7
G1+ G1E
8
INTER-ATOMIC FUSION

Fig. 39: Schematic process of the inter-atomic fusion.

Where, initially by using Dilution plasma reactors (Chapter 23, Fig. 57), by feeding the atom of hydrogen into this reactor cores (Chapter 21, Fig. 54), and then in allowing the magnetic atomic structure to dilute and to open up in the soup of the plasma of the reactor (Fig. 39 diagram 1) into its sub-components of electron and proton. At this point the magnetic fields' strength of the soup of the reactor is brought to the levels, which now can be matching with the plasma of the proton pmtics level, for the reactor fields strength to match the overall Magnetic and gravitational pmtics of the protons' plasma. This is the magnetic field strength level of the binding of the plasma, which is called the Coulomb charge barrier of the plasma. Which at this point, the Matters' of the electron are more free and can be gently Magravs positioned to join up in to the Matter components of the proton.

This is the natural method of fusion in its basic form, where there is no need for the huge magnetic fields forces to achieve what happens naturally in the universe to fuse an electron of atom to its proton. The same process of fusion in the plasma dilution reactors' technology can be used for fusing Matters, plasmas or even atoms.

This inter-atomic fusion is done in a magnetic field environment of ***soft*** plasmatic magnetic fields forces and at the same time in a similar magnetic fields forces strength of the same atom environment of the two similar plasmas of the proton and the electron of the same atom, where, in fact the magnetic fields of the outer cores of the reactor performs a similar job as the magnetic rings of the Tokamak systems in providing the containment magnetic fields. Where as in the plasma dilution reactors, at the same time natural gravitational and Magnetic fields needed for fusion criterion is provided by the operation of the fields in two cores of the reactor fields' interactions with each other.

If scientists use this method of creation of Magnetic and gravitational fields forces in the present Tokamak reactors', to replace the solid coil electric magnetic rings, they will achieve fusion in real universal conditions, fusion within natural gravitational fields forces environment necessary to accommodate the fusing of any plasma at a fraction of the present costs and in a very short time-frame.

With these soft magnetic fields in plasma dilution reactors, one can achieve more rapidly fusion than using current induced enforcing magnetic fields rings. These types of magnetic fields strength in dilution plasma reactors are similar to the magnetic fields strength of the plasmas and atoms, and hence they can be manipulated much easier, than, trying to force the plasmas' of two protons.

In comparison, that is to say, to make *an omelette*, it is easier to mix the contents of two uncooked eggs homogeneously as happens in plasma dilution reactors, whereas in trying to make the same omelette, this time by boiling the content of two eggs first into two hard boiled eggs, as Tokamak scientists have been trying to do for past fifty years to make the fusion in reactors by hard balling the content of plasmas (by squeezing the plasma with the use of external magnetic fields to a tighter, harder, smaller entity) and then trying to fuse the two hard balls of plasmas to achieve the fusion process. Then hoping, with increasing the speed of the two hard balls, that they can smash and fuse the two smaller hard balls together. That is why the present path of Tokamak technology in trying to achieve fusion is a sweet dream that will never come true.

In this inter-atomic fusion technology, smaller and weaker plasmas of electrons, which are already within the structure of an atom, are fused into the Matters' component of the proton of its central plasma (Fig. 40). This is a more realistic and practical method of fusion than the present, fusion technology in trying to fuse two large plasmas of hydrogen's protons together, and creating unmanageable heat, of several billions of degrees. Where, the tools and materials to control and harvest the energy of such huge temperatures, on the long term bases in small Tokamak reactors, does not exist within the known galaxies in the universe.



Fig. 40: Schematic diagram of the fused proton and electron plasmas.

In these processes of dilution plasma technologies, when the electron plasma is gravitationally positioned or encouraged to amalgamate its contents with the content of the plasma of the proton, as the two plasmas approach each other, the interaction of two plasmatic magnetic fields of the two plasmas will and can produce several scenarios, which their effects can be harvested for production of different energy levels or production of new materials and so many other purposes.

In brief two cases are discussed here:

a) If the strength of the pmtics of these plasma dilution reactors is set at a level, to be just below that of the total balance of the pmtics strength (Coulombs barrier) of the plasma of the proton, in this case, as the two plasmas approach each other, the initial stages' of the process of fusion starts, which this process begins and will be accompanied with light and heat emission as in figure 39 - diagrams 1 to 5. This light or heat from this process can be used for example for present state of art technology turbine power generators directly. Where, the temperature of the interaction of the systems can be set at the optimum efficiency temperature of the turbine. Hence, operating these reactors in the same configurations as is done in the present fission reactor technology power generators to generate steam to run turbines. With the difference that these dilution technology reactors leave and produce no nuclear waste, and heat can be generated at any level as per demand of the system.

In these reactors, the Magravs strength similar to the plasmas' **Coulombs barriers** charges can be created and controlled. In the dilution plasma reactors' the magnetic fields created through the soup of the plasma will create and maintain pmtics strength, which can be similar to the magnetic fields barrier strength of the plasma of the proton. Where, the strength of the pmtics field in the reactor will decide the strength of the pmtics in comparison to the protons' plasma Magravs strength. As the pmtics strength of the reactor reaches more to the level of the Magravs strength of the plasma, then there is ***less resistance*** *and* ***less friction*** *between the plasmas of the proton and the electron*, when, they are brought together to fuse. Thus as the strength of the magnetic fields of the plasma can be reached by the reactor operation, this allows less friction and hence *less heat* to be produced by the interaction and by the gravitation of the two plasmas of the proton and the electron to fuse. By being able to control the pmtics strength of the plasma dilution reactors Matters' soup of plasma, one can dictate the amount and the rate of the heat release from the interaction of the two plasmas, thus one can control the heat output of the reactor, if the production of heat is the primary objective of the use of such a system.

In general, in being able to control the ***Coulombs barrier strength*** in respect to the given environment of the reactor, one can **vary** this barrier magnetic fields strength in the soup of Matters in the plasma dilution reactors.

Therefore there is no need even to fuse the plasma of the proton with the plasma of the electron, and by just bringing them close to each there to create the right friction when the Coulomb barrier is at the right strength, between the two plasmas, then the reactor can generate a controlled heat-output, or any other rays that is demanded from the systems' operations.

Therefore by *bringing the reactor magnetic fields strength to the level of Coulomb barriers*, one can bring into balance the magnetic strength barrier changes in the overall mixture of the reactor to any level from, or to the Coulombs barrier magnetic fields levels.

Where, the ***difference*** between the two, the **reactor** and the **plasmas' magnetic fields strength**, will decided the ***temperature output of the reactor*** when, the plasma of the electron is gravitated to the plasma of the proton to fuse. The outcome of the bringing of the two plasmas into each other proximity and the interaction of their Magravs, leads to the friction between the two plasmas, and the release of pmtics in form of heat. Where, the temperature of the heat released by this attempted fusion is directly controlled by the pmtics field strength within the reactor and in respect to the variation level from the

Coulomb barriers' pmtics strength level.

An example of this controlled heating of interaction pmtics in the natural world is the like of when the pmtics of the sunlight in atmospheric condition becoming in touch with pmtics of the cell of the human body. Where, as the pmtics of the proteins of the cell are always constant, by varying pmtics strength of the direct sunlight, the heat released from the interaction of these two pmtics, the human feels the increase in the pmtics strength as heat of different degrees. The stronger the pmtics of the sunlight, the more heat is produced from the interaction of two pmtics, thus the warmer one feels. This is like walking from the shadow into the sunlight.

The phenomenon of heating during illness, happens due to the interaction of pmtics of a bacteria within the blood protein pmtics, where as a blood cell comes in touch with a stronger pmtics of the bacteria, the level of the interaction of the extra pmtics from the structure of infection, in ***interaction*** with the blood cell, manifests itself as heat or the increase in the body temperature (this is explained in detail in the paper: Universal order of creation, to be published as a book), where the interaction and possible ***fusion*** of two pmtics of the bacteria and the body cell leads to a release of heat, called "an infection" temperature. This being the reason why the same pmtics of bacteria can have no affect on some human bodies and the same infection can create high temperatures like 41°C +. The reason being that the cell of the one with the high temperature has a lower pmtics strength, thus the interaction of the two infection and the body Magravs pmtics creates more release of fragments of pmtics as heat. When the temperature reaches a level that the Magnetosphere of the human protein reaches its dilution point then the cell is de-structured.

b) When the neutron is needed to be produced from the atom of hydrogen in space for production of heavier atoms, one can follow the process from stage 1 to stage 8 of the Fig 38. In this process the pmtics strength of the reactor are set to be nearer to the binding Magravs strength of the boundary of the protons of the plasma, so that the electrons' plasma literally melts into the protons Matter structure and the matching pmtics of both plasmas of the proton and the electron. Which these plasmas and their pmtics were all of the same origin; this is amalgamation to produce new neutron type initial fundamental plasma. This is the process of the decay of the initial fundamental plasma in reverse, using the same original components of Matters pmtics of all three matters of the plasma. Such a neutron can be added to the construction of the atomic structure of lighter atoms to create **gap(s)** needed for Magravs positioning for the protons of the nucleus to accommodate an extra proton and its accompanying electron for production of even heavier atoms, for example for the production of carbon, oxygen and nitrogen to produce protein base nutrition in deep space travels. Alternatively, one can produce atoms of any matter from initial hydrogen atoms, through the use of the same method of progressive accumulations of protons and neutrons in fusion in plasma dilution reactors.

ii) The other condition is, when the plasma of an electron is attracted to the protons' plasma, ***but does not get absorbed*** within its pmtics, due to their Matters strength friction at the zones of contact of the two plasmas.

As has been explained in previous chapters, the electron is itself a plasma condition and a collection of dynamic pmtics of Matters. Where through the method of its construction and motion around its nucleus, this electron is always in proximity of other electrons of the similar construction or it is in the proximity of larger plasmas such as the neutrons or the protons of the nucleus of its atom.

The ***Motion*** *of the electron* around the proton is created due to the construction of its internal Matters (Chapter 19). Similarly, it has been explained that the interaction of two pmtics due to their friction lead to release of pmtics strength fragments of lower strength of pmtics or rays in the electro-magnetic field spectrum of the light.

Now it is very simple to understand how light is released due to external factors. When the electron of the atom is forced to come close enough to another electron or the components of the plasma of its nucleus or a nucleus of another atom. So that, the interaction of the two plasmas Magravs of the electron and the proton leads to the release of lower magnitude pmtics strength fragments that, its pmtics strength are in the light electromagnetic spectrum (It has been explained that when two plasmas interact and collide; the pmtics fragments of their collisions always releases pmtics in the light bandwidth)(Chapter 7).

This interaction and collision of the pmtics of the two plasmas does not mean amalgamation of the two, but in coming too closed to each other, the two pmtics strength touch and bounce off due to their dynamism.

Hence, as the electron has lost some of its pmtics due to the interaction and collision, with the pmtics of the proton, so now being in possession of different Magravs strength, the electron accepts a new Magravs positioning (Chapter 19) in respect to its proton plasmas.

This interaction of the two plasmas creating the closeness or distance of the electron to its systems' central Magravs point, or what is called that the electron finds a new *ground energy level* position after releasing some of its energies as light, this is then a new Magravs positioning of the electron in respect its protons' Magravs strength forces, which is acceptable by both plasmas Magravs within the atoms structure after collision between the two pmtics of the plasma of the electron and the proton or other plasmas in its vicinity.

Thus when plasmas interact like the plasma of the electron and proton, this leads to the creation of light in the majority of case.

CHAPTER 16

The fundamental difference between Inertia and Gravity

Inertia is said to be due to the total interaction of pmtics of Matter(s) of a solid object without the central dynamic cores that can create Magnetic and gravitational fields forces.

Inertia, through the new understanding of the structure of the plasma, can be simply defined as "the pmtics and gravitational fields due to the Matter in the matter (solid, liquid, gases) components of the plasma (Fig. 41 link F)"



Fig. 41: Interaction and connection between inertia of Matter pmtics of an entity (I and J) in respect to another entity and their interaction (F and H) with magnetic field (C) and gravitational field (D) of systems respectively.

Gravity is simply defined as ”the total pmtics Magravs created by all components of the Matters (Matter, Antimatter, and Dark Matter) of the plasma (Fig. 41 link D and G, and Fig. 42 Link G).”

Inertia is said to be due to a *total collection of pmtics* of the constituent Matter(s) of atoms and molecules of an object, interacting and attracted with each other and any other Matter(s) or matter(s) or Magravs.

The principle of inertia is applicable to the Dark Matters and the Antimatters as well as the Matter components of the plasma in the universe.

As each atom is made of and possesses specific pmtics strength, these fields, in interacting with each other in the state of matter (solid, liquid and gas), create their own total Magravs by addition of the overall magnetic fields of all the atoms of the structure of any matter. The structure of the matter could be made of molecules or an asteroid or any physical object, which is void of gravitational pull, but in possession of pmtics Magravs’ pull of Matter component of plasma, due to the construction of components of its neutrons, protons and electrons of matters. These pmtics, in being interlocked with each other, cannot create a dynamic Magnetic and gravitational pull or interactions between the constituent pmtics of all the Matters of an object. Nevertheless, they create gravitation in between the Matter components of the Matters of plasmas of the object.

In other words they have or create gravitation in respect to Matter-to-Matter components of plasma, or this singularity Matter attraction or gravitation of the total Matter of plasma, is called the **Inertia**.

As the **Gravity** is due to the overall dynamic pmtics strength of all Matters of an object, which is in possession of at least two **sets** of dynamic pmtics in respect to other pmtics, where, the interaction between two sets of dynamic pmtics, leads to the creation of gravitational field forces and simultaneously Magnetic field forces for plasmatic magnetic fields, or rays of magnetic fields, or the whole Matters of an object, this being a planet or a star or others.”

In the case of larger objects with multi-core configurations like Earth, the multiple pmtics forces of dynamic multiple-core objects are loose from each other. Hence, the overall dynamic pmtics of their Matters can interact, creating much more active fields to be brought into play. These being, the stronger magnetic fields constituent components of the plasma; Matter, Antimatter, and Dark Matter, F1 zone fields and all other transition zone fields to interact with each other within the plasma.

That is to say, that the collective **free Matters** of the plasma create a stronger pull or gravitational forces than when the same independent are compacted and cannot be free in a dynamic condition in matter (solid, liquid and gas).

Gravitational fields, due to their free motion and strength of interaction of their Matters with others of the same, can span and reach further a field in the environment.

Gravitational field forces are always stronger and span wider in their given environment, than their inertia of individual Matter counterparts, simply because gravitational field forces of planets or stars are mainly created by all components of pmtics of Matters of the plasma (Fig. 42), rather than the collective plasmatic magnetic fields of individual types of Matters' components of the plasma or the matter.

Planets' and stars' total pull is a combination of the gravitational fields and inertia pull of all their constituent Matters and matters. These composite pulls are created due to the dynamic plasmatic materials of their constituent Matters in the inner cores of these objects in respect to each other, plus the total pmtics interaction of their matters.

Through tests, it has been proven; that the Magravs force strength of a dynamic object is independent of temperature and pressure of their cores. Where, we do not consider this to be the same for the inertia of the matter (solid, liquid and gas).

At the same time, Magravs of a dynamic object can vary as the strength of its Matters pmtics constituent changes. Where, the inertia of the solid matter is always constant, both in respects to the same initial given position.

It is considered that Matters, in general, possess Magravs forces due to their dynamic construction of their pmtics.

As much as the universe has inertia field forces, in respect to Matter components of the plasma, there is ***Antimatter inertia*** in respect to the Antimatters components of and ***Dark Matter inertia*** in respect to the Dark Matter components of the plasma or the universe (Fig. 41). In fact, a collection of the Antimatter and the Dark Matter can possess inertia similar to the physical Matter conditioning of their environment. Therefore, the same matter possesses separate Dark Matter and Antimatters inertias too.

By the same measure, it is to realise that there are Matter Magravs systems as are Antimatter and Dark Matter Magravs systems in the universe. In understanding this clarification, in the systems of attraction of Matters, reactors can be build which are inertia dependent and not gravitational dependent.

It is important to note that; gravitational fields of planets and stars are all created by the Matters components of plasma. This means gravitational fields affect all Matters of plasma (Fig. 42), where inertias of certain Matters affect only that particular Matter component of the Plasma. At the same time, it is clear that gravitational field reactors can be produced in such a way that their gravitational fields *can attract certain Matters only*.

These systems will be like laser systems with the advantage that the laser operation can work ***in reverse***, that is to say the system can send rays of a given pmtics strength as well as attraction or gravitating the same rays and collection of pmtics towards or into the system too.

These systems can or will have, single or multi-molecules pmtics gravitational settings, that can be attracted to, or repelled by only specific pmtics strength, to or from their environment.



Fig. 42: Interaction between the pmtics Magnetic fields (I) and gravitational fields (G) of two Magravs systems.

Note: In fact the term used as "gravity" has to be explained as gravitational and Magnetic field forces, as when an object is attracted by gravitational fields of a matter, like the Earth, at the same time it is repelled by the Magnetic field forces of the object too. Thus, when talking about gravity it is correct to talk about the overall Magnetic and gravitational fields (Magravs).

These simple mono- or multiple-setting gravitational or inertia systems (Fig. 41 and Fig. 42) can be used for specific *extraction* of certain Matters, matters or materials from the universal Matters or matters soup.

Such systems, will change the present industrial systems thinking that magnetic attraction is only *limited to ferrite metallic objects*. Man has now the possibility to make systems *that can attract* ***any matter*** through the development of these systems."

These systems for example can be used, once set to appropriate pmtics gravitational field strength levels, so that they can extract only the CO_2 from air, or specific poison from water, or rare metals from the Earth and space and so forth (31).

These reactor systems can be used for production of proteins for human consumption and so forth in the future space travels (32, 34, and 38). The production of proteins like matters, through gravitational plasma dilution mixing has been tested and different matters were collected in several tests in summer of 2008. In these tests, the proteins produced and extracted from the reactor cores caused the damage to the ancillary systems of the reactor set-ups. These proteins layers were physically visible and tangible.

Using the mono-Magravs systems (38), new matters can be extracted from other environments, like nano-materials of all sorts. These systems can be used to produce specifics matters too, matters like, uranium, hydrogen and so forth from the plasma of the universe as the needs for their use arises.

Thus through the understanding of the principle of mono- or multi-gravitational and inertia systems, reactors can be evolved that are gravitational to one object or one matter or one Matter only. Through understanding of the interaction of the plasmatic magnetic gravitational principles, reactors have been built, that have a Magnetic or gravitation to plastic at one point, and by resetting its configuration becomes magnetic to carbon and so on. Thus, mono-gravitational and inertia systems can be developed that have specific magnetic attraction or repulsion to one Matter, matters or any Matters of the plasma that can be expected of them through their pmtics strength operation setting.

On the other hand, the repulsion technology of the same Grapos can be used to send the Dark Matter and/or its pmtics energy as the Dark energy of the same plasma of specific pmtics strength into deep space for specific applications.

These types of gravitational lasers type reactors can be used for example in communication systems, where the information packs, using mono-pmtics strength of the Dark Matter and Dark energy can be sent through the system, so that the information can be packaged in the Dark Matter-envelop and sent without resistance or loss of energy, for it to travel with speeds beyond the speed of light to its destination anywhere in cosmos. The speed of communication through mono-Magravs systems are speeds which can be several times faster by order of magnitude than the present used state-of-the-art communication systems with satellites and microwave technologies. These speeds of transfer of information will be, by order of magnitude, faster than the speed of light.

These **GR***avitational l***ASERS** systems, that can be called “**Grasers**”, can be used for example to avoid a head-on collision and destruction of crafts by an asteroid in the path of the motion of crafts in deep space (33), or within atmospheric condition. The present missile technology due to its slowness through development of these reactors are obsolete, as once fired to protect the craft in space, for example from asteroids by the time the missile will arrive at the point of destined collision between the spacecraft and the asteroid, maybe it will be years after the craft has past that point.

These mono-gravitational or mono-inertia systems will bring to Man the realisation that the time of making war-machines has come to its end.

As Man will come to understand, soon enough that using these mono-gravitational or inertia systems against one another as tools of war will mean and will have only one outcome, and that is a total wipe-out of the human race from the face of the Earth. The men of war through this technology will come to accept peace not out of their pleasure but out of the fear of their own demise.

The use and capability of the use of this knowledge and of the effectiveness of these *mono-Magravs system*s lethality, has been the cause and the keeper of the peace in the universe. No chance, will be given to the Man, to change the tranquillity of universal peace by use of this technology.

Man through the lethal powers of these mono-Magravs systems will be taught an unforgiving and painful lesson, if he ever tries to use this technology and knowledge to carry on with his aggressive behaviours, as has been his habit for centuries on his own planet. Then this will be the coming of the end of the term of the Man in the universe.

It is clear that any celestial object as the planets, stars and galaxies, are all created through the attraction and interaction of these Matters and matters, their interactions and their constituent plasmatic magnetic fields. These interactions and collections of Matters and matters in respect to the plasmatic magnetic fields strength, which larger objects possess by their order of magnitude, decides' what will be in their part of their environment. That is to say, the plasmatic Magravs created by the plasmatic magnetic fields of Matters in the inner cores of the stars in principle will decide on the size and the span of the dominion of its field in its environment. Then these Magravs strength and their balances dictate what matters or Matters will be attracted to the atom, molecule, planet or the solar system.

This principle of mono-gravitational plasmatic magnetic fields strength forces is the main reason in the universe that why certain planets only retain one element in their structure. For example, this is one of the reasons why the planet Saturn is mainly made of helium on its outer layers as its main constituent matter (17). The reason being that the initial Magravs of the interaction of pmtics of Matters and matters in the inner cores of the planet has been set to be equal to the helium plasmatic magnetic fields strength of matters in that part of solar system in the early life of the planet.

This mono-Magravs positioning field strength of the Saturn is one of the reasons, why this planet, with its strong gravitational field forces, does not pull in and absorbs a large number of asteroids from the Astor-belts. The other reason is that, mono-Magravs systems possess very strong Magnetic fields too, which this is one of the reasons why this planet can keep the matters of asteroids in check.

Alternatively, certain galaxies have more of one matter like hydrogen than the others having nitrogen and so on. Thus, the pmtics of Magravs forces and their mixture with the inertia of a planet dictates what matters are extracted from their part of their environment, like the solar system or galaxies.

Thus, Magravs positioning reactors are not only for creation of motion and for protection, but they will be the main tool for cleaning environments, collecting preferred Matters, matters, etc.

CHAPTER 17

Plasma's and Nuclear decay

The nuclear decay principles of an atom, is in general, considered to be on "the same principles and methods and as the simple decay explained previously for the initial fundamental plasma into a proton and an electron (Fig. 43)".

For the initial fundamental plasma to reach the ground-level plasmatic magnetic fields content condition, the plasma divides itself into two new and exactly similar structures with different amount of mass of the same constituent plasmatic magnetic fields Matters for the creation of a proton and an electron, and releases its unwanted pmtics as residual pmtics or as rays (gamma or x-rays, etc)(Fig. 42). I call this process of the neutrons decay "***The initial fundamental plasmatic decay***."

Through the process of releasing of the exact amount of plasmatic magnetic fields from the **neutron** necessary for the creation of a **proton**, an **electron** and the **release of energy or other rays** from the initial fundamental plasmatic magnetic fields, this, in a way, confirms that *all initial fundamental particles of plasmas are always make exactly of the same and similar plasmatic magnetic fields and the same configurationally structure*. This being another proof that initial fundamental plasmas in the ***universal order of Matter*** are always made through and by the same Specific Entangled Plasmatic MAgnetic Fields (SEPMAF) strength criterion and procedure, as has been previously explained.

The principles of the nuclear decay of initial fundamental multi-plasmas of an atom, is considered to be solely due to the re-balancing of the overall plasmatic Magravs strength components for Matters of plasmas of the atom ***to maintain an overall Magravs forces balance of all participating plasmas***, in the construction of the atom. These being the plasmatic magnetic fields of neutrons, protons, electrons and their constituent Matters, their plasmatic magnetic fields of their Matter, Antimatter and Dark Matter and their magnetic fields forces of each plasma.

For the plasmas of an atom to stay together and hold onto its constituent structure plasmatic magnetic fields, some of these *plasmatic magnetic fields in motion* (energy) are ***transferred to*** *other plasmas*, and in term, these plasmatic magnetic fields are said to be used. At the same time, part of the initial fundamental particles fields of plasmas are used for the upkeep of the integrity of the nucleus positioning and dynamism; As part of the binding energy is consumed for holding the fundamental plasmas together. As in this cycle of consuming pmtics reaches that enough pmtics have been used, that the initial fundamental plasmatic Magravs of the plasma cannot hold onto their initial gravitational positions in respect to each other. The plasmas making up the part of participating neutrons or protons in the centre nucleus of atom, gravitationally reposition themselves within the nucleus for the nucleus to find a new Magravs *balance and equilibrium positioning* in respect to other plasmas.

At this point of magnetically repositioning of the plasma of the heavy nucleus, the nuclei of heavier atoms split into exactly the same configurations of two or more new Magnetic fields and gravitationally positioned balanced plasmatic strength configurations (Fig. 43) of the plasma's of neutrons to protons and electrons, and hence split into two new atoms. This regular splitting pattern of heavier atom to two or more light atoms is known as a ***controlled fission*** of atoms.

As the initial fundamental plasmas were all made of the same initial fundamental particles of the same specific magnetic fields strength and interactions, in their disintegration of denser nucleus atoms, they split and gather into two or more new less denser atoms and of Magravs' configuration, and their need for the new equilibrium of collective plasmas of new atoms.

That is how the atoms are always spilt into exactly the same lower order of numbers of neutrons, protons and electrons in the new nuclei for the overall new balance pmtics of the two new atomic structures to be able to be kept.



Fig. 43: Schematic of a decay of pmtics and Matters of the Initial Fundamental Plasma (NEUTRON), "the initial fundamental plasmatic decay".

In principle the overall disintegration of all atoms heavier than Hydrogen, involved in the collective pmtics of a given matter, the collective pmtics of the residual matters is always constant, and of the same end-structure of new and lighter atoms.

The overall numbers of the plasmas involved in a structure of a given matter is said to be constant, purely due to the fact that the overall rate of interactions and disintegration of plasmatic magnetic fields are considered to take place at a constant rate. Hence, the phenomenon that takes about the same time for the plasmas to reach a point of using a given amount of dynamic plasmatic magnetic fields (energy), before they reorganise themselves to a new balance condition. This reorganisation or rebalancing of overall plasmatic magnetic fields of the components of nuclei, leads to the fundamental principle of the nuclear decay nuclear of an atom.

This reorganisation of the new plasmatic magnetic fields balance in mass of matters is in so many ways dependent on all of the atoms participating in the total structure of the mass of the matter. This is irrespective of the number of atoms in the matter, these being in the solid, liquid or gaseous state of matter.

The nuclear decay in some plasmas can be triggered and be due to internal changes in the plasmatic magnetic field's structural balance, or can occur due to changes in the external environment of the initial fundamental plasma. These changes can be due to the ***changes*** in the external equilibrium of magnetic fields forces or field strength of other initial fundamental plasmas, or surrounding plasmatic magnetic fields adjacent or near to the initial fundamental plasma.

This being why different atoms of a given matter decay at different rates depending on their position within the overall structure of tangible matter. That is to say ***the decay of atoms is environmental pmtics strength dependent.*** Which the environment can be within the same matter construction of atoms, or the interface between the matter and for example matters of air. Where each environment enforces different rates of use of internal pmtics of different matters within the nucleus of that atom. This being the reason why different rate of decay of atoms within matters are considered to have a **half-life** principle. Where the half-life is, and can be pmtics strength environmental dependent.

Interesting point to consider:

Does the reorganisation take place in the same position first and the same number, which initiates the course of the decay in the rest of the mass?

Is the decay of an atom in a mass happening faster in the inner positions of the mass of matter, or on the edges of the mass?

CHAPTER 18

Neutron-Proton, Electron-Atom

Through the new understanding of the method by which the initial fundamental particles and their subsequent plasmatic magnetic fields interaction, leads to the creation of the initial fundamental Matters (Matter, Dark Matter and Antimatter) leading to the creation of initial fundamental plasmas or the Neutrons, the subsequent degeneration of initial fundamental plasmas through decays further leads to creation of protons and electrons of an atom, and their interactions and collections into molecules and matters (solid, liquid and gas).

Fundamentally, *initial fundamental particles* ***interactions***, leading to the creation of different states of Matters and the creation of initial fundamental plasmas, where these plasmas are considered to be in a ***total plasmatic magnetic equilibrium state*** (Fig. 44 and Fig. 45).

The Initial Fundamental Plasmas are **neutrons** in characteristic. Neutrons (Fig. 44 and Fig. 45), in their construction, are considered as ***balanced*** dynamic plasmatic magnetic fields environments.



Fig. 44: Schematic presentation of the overall Magravs of Matters and the fields of the Neutron.

Neutrons, due to **the *larger content* of the three Matters and their F1**, they create a ***stronger gravitational pull*** between the Matters of the plasma, consequently their overall Magravs of the initial fundamental plasmas are considered to possess more mass, than the total sum of the masses of the individual proton and electron, from the same plasma after its decay.



Fig. 45: Matters schematic diagram of the Neutron.

For the ***initial fundamental plasma*** to find its final balanced equilibrium plasmatic magnetic fields force strength condition, due to different effects, the initial fundamental plasma ***reduces*** *its plasmatic magnetic fields balance* to its **ground-level** magnetic fields mass level (Fig. 46 diagram 7) for it to survive, hence the initial fundamental plasma disintegrates or decays' to its sub-Matter levels and fields.

The decay of the neutron

This process has been explained in previous chapters where, now we look at this process in more detail.

The release and division of components of the initial fundamental plasma leads to the release of two independent, yet at the same time interlocked, balanced plasmatic magnetic fields environments plasmas (Fig. 46 diagram 8). Of these two new plasmatic magnetic fields plasmas, one would retain more of the initial fundamental plasmas' mass and be the larger of the two balanced plasmatic magnetic fields (Fig. 46 diagram 7). The second plasma will contain less of the pmtics of the initial fundamental plasma and mass and would be smaller (Fig. 46 diagram 6). The *larger of the two plasmas', would* ***stay in the centre,*** due to its mass and Magravs strength would become ***the proton*** of the atom (Fig. 46 diagram 8). The new smaller balanced plasmatic magnetic fields released can be said to manifest itself as ***an electron*** (Fig. 46 diagram 8) of the same atom.


START OF THE DECAY OF AN INITIAL FUNDAMENTAL PLASMA

1
2
3
4
5
6
7
8
A1
B1
G1
C1
A3
F1
C2
A2
B2
G2
C3
B3
G3
G1p
G2p
G3p
G1e
G2e
G3e
PROTON
ELECTRON
AN ATOM

Fig. 46: The eight steps of the Neutron decay cycle to a proton and an electron and then an atom.

It is considered that the ***pmtics of the Antimatter components*** *of the* ***neutron*** **start the process of the decay** of the neutron. As the Antimatter is the main and the strongest of the Matters' of the initial fundamental plasma (Fig. 46 diagram 1), in comparison the Antimatter is the star in a solar system. Then the pmtics of the Dark Matter part of the neutron plasma splits simultaneously as the total balance of the Magravs forces of the plasma is disturbed (Fig. 46 diagram 1). This process is continued up to the point that, due to the cycle of separation of more and more of the two pmtics of the Antimatter and the Dark Matter, leads to splitting of the Matter part of the plasma (Fig. 46 diagram 4) as the plasma tries to keep its overall stability and equilibrium.

At this point, the pmtics fragments of the Antimatter, the Dark Matter, the Matter, and other pmtics within the plasma, through the dynamism of the plasma internal environment, are brought close to each other and then merge to produce a small and independent **mini-plasma** within the structure of the initial plasma.

Where this new embedded mini-plasma in the overall structure of the initial fundamental plasma becomes the structure of the initial fundamental plasma of the **electron** of the atom.

The plasma of the electron by this time is formed internally and has establishes its own balance Magravs zone and hence its own magnetosphere (Fig. 46 diagram 5 and 6). At this stage, the Magravs of the electron plasma tries to find and reach its own Magravs positioning balance in respect to the leftover pmtics and Matters Magravs of the initial fundamental plasma. At this point, as the two plasmas try to find their Magravs positioning in respect to each other, the electron plasma is pushed out-off the boundaries of the initial fundamental plasma (Fig. 46 diagram 7) environment.

At this point where the two plasmas find their Magravs positioning balance, this becomes **the gap** *between the proton and the electron*, or the ground energy level for the electron in respect to the proton' of the plasma. From this point on, the foundation for the final step of the making of an atom with contents of a proton and an electron is reached (Fig. 46 diagram 8).

Therefore the new balanced fields of the original initial fundamental plasma now becomes the components of the two newly balanced plasmatic magnetic fields plasmas of the proton and the electron of an atom (Fig. 48).

From this point on, the motion and rotation of the electron around the proton is set to follow, according to what is described in Chapter 19.

The similarities between the construction of the protons' plasma and the electron plasmas components of Matters, as both have started together quasi-independent life, from the same initial fundamental plasma mother (Fig. 47).


MATTER
G1
ANTIMATTER
G2
F1
Transition region
DARK
MATTER
G3
PROTON
G1
G2
F1
G3
ELECTRON

Fig. 47: Schematic similarities between construction of a proton and an electron (components of Matters).


A1
B1
G1
C1
A3
F1
C2
A2
B2
G2
C3
B3
G3

Fig. 48: Pmtics presentation of Initial Fundamental Atom (hydrogen).

As the initial fundamental plasma splits into two balanced plasmas (Fig. 46 diagram 1 to 8), this guaranties the total balance of the integrity of the complete original initial fundamental plasmatic Magravs configuration.

Thus, the splitting and decay of the initial fundamental plasma into the proton and the electron (Fig. 48), called the ***initial fundamental decay***, is a natural decay process as is the ***nuclear decay*** of heavier atomic structures into lighter atoms. Where as the plasma uses some of its pmtics to keep its position, motion and magnetosphere boundary, it needs to break up to smaller atomic substructures that can guaranty its overall magnetic and gravitational field structure, thus the term "*decay of the atom"*. This neutron division, to the substructures of a proton and an electron, is for guaranteeing the survival overall of what was achieved before for the creation of initial fundamental plasma (Fig. 48).

This method of the Initial Fundamental Plasma Decay to the proton and the electron is the reason why in atomic structures the number of the electrons and the protons have always been seen to be in ***matching numbers,*** as there is no alternative way in nature for the creation of proton and electron in the universe in general, however individual electrons can be produced from the pmtics in plasma dilution reactors.

In the construction of higher atomic number elements (Fig. 49), for the total balance in both Magravs of the nuclei and their respective electrons, these heavier atoms need to have more of the balanced plasma components of neutrons.



Fig. 49: Schematic of pmtics of a complex atom (like Helium).

Note: Through this simple configuration (Fig. 49), one can understand why certain chemical bindings and structure of some atoms and molecules of certain proton combination interactions in a given environment become possible.

In fact, the neutron, due to its balanced magnetic plasma or neutrality, and at the same time possessing its own Magravs magnetosphere, becomes the space gaps and space(s) needed for Magravs positioning of protons, in respect to each other, as much as magnetic fields equalisers or balancers in the construction of the nucleus of atoms with more than one proton (Fig. 49).

In the heavier elements, due to the tightness of packing, if there were not so many neutrons to create some magnetic and Magravs positioning balance gap, or what we call **gaps**, then due to the protons gravitational pulls, part of the nucleus would most probably clog-up, this being due to the interlocking of the Magravs of protons in the nucleus of the atom. In the majority of cases, this ***clogging-up*** would most probably lead to the explosion of the nucleus, due to *repulsion* of the fields or Magnetic fields of Magravs within the construction of the nucleus in being too close to each other's proximity. On the other hand without the existence of neutrons as a gap the nucleus would not be a gravitationally positioned stable configuration.

A configuration of the complex structure of the initial fundamental plasmas like an atom of the Helium and the positioning of its neutrons, protons and electrons are shown in figure 49. This shows the overall gravitational fields and Magnetic fields generated by interaction of these individual parts, in respect to the dynamic Matters and the fields each part produces both internally, and in their overall external boundary interaction of the plasmatic Magravs of the atom.

By a close observation of the proton and electron's Magravs balance, it is now clear how the *different* ***electron orbits*** *of heavier atoms* come to be created. That is to say, as the number of protons increases, the boundary of the Magravs of all protons in the centre of the nucleus increases, thus allowing and accommodating the next orbit for the motion and Magravs positioning of the next layers orbits of electrons. It has to be remembered that protons are *dynamic* entities, thus not more than certain numbers can revolve in the compact zone of a nucleus. So as the number of protons and their equivalent electrons are added to the nucleus, *more room is needed* for the *free* motion of these protons. Hence the only way a neutral zone can be created for the free motion of these additional protons for the structure of nucleus to be Magnetically and gravitationally in balance, is to add more balance neutrons to create an environment for the free motion of the protons and their Magravs positioning.

Thus as proton number increases, and the volume of the nucleus increases to keep all protons in motion, and hence more numbers of neutrons are needed. This is the reason why one sees a larger number of neutrons in the nucleus of heavy atoms. The more neutrons and protons are in the centre, the *larger the magnetosphere of the nucleus* boundaries. Hence, the accommodation of more electrons in *further distances locations* from the centre nucleus. Where all these electrons, protons and neutrons overall pmtics Magnetic field and gravitational field have to be at all times in balance.

It is fundamental to understand that " the negative field charge of any magnetic fields is due to its Gravitational field strength or pull, and the positive charge of the fields due to the Magnetic fields strength or push of the Magravs of the Matter, like a planet.

In electric field charge and current flow, its to be understand that the **positive charge** is the flow of the Magnetic field push of the Magravs, and the **negative charge** is the gravitational pull of the flow of the gravitational fields of the Magravs of the plasma and its Matters content. This in a way explains the ***Resistance*** and the ***Impedance*** respectively of the matters in the electrical section of physics. Where the impedance is the measure of the gravitational pull of the flow of the pmtics in respect to the matters' atoms and where the resistance is the measure of the Magnetic push of the flow of the pmtics in respect to the matters' atoms.

CHAPTER 19

Motion of the Electron around the Proton

The constant rotation of the electron around the nucleus of an atom indicates that the electron and the nucleus of the atom constantly maintain an overall balanced Magravs forces between and Magravs positioning, in respect to each other.

Within the structure of the initial fundamental plasma (the neutron), and through its sub-dynamic Matters (Matter, Antimatter, and Dark Matter) and at the same time, with all Matters of the plasma being in possession of their own independent internal dynamic plasmatic Magravs forces, they all exert dynamic and varying levels of Magravs on different constituent of Matters of plasma internally, which these field forces span beyond the boundaries of the nucleus plasma itself individually and collectively.

The total effect of these dynamic forces, from the nucleus plasma (proton) (Fig. 50), will affect the *path* of the *rotation* of the satelliteing electron around the nucleus.

Similarly, the *plasma of the* ***electron*** (Fig. 50) itself is *made of the* ***same three dynamic plasmatic magnetic fields structures*** *of Matters as of the proton in its nucleus.*

The effect of these **dynamic** plasmatic Magravs of different Matters in the centre plasma **(proton)** of an atom on the **dynamic** plasmatic Magravs of different Matters of the plasma of its **electron,** and their collective effect of each plasma on each other, is the reason why the electron does not have a constant and a defined path of motion around the nucleus.

That is to say, the electron plasma by itself is in possession of its own individual Matters' (the Matter, the Antimatters and the Dark Matter) Magravs forces' as well as their collective plasmatic Magravs forces of all the Matters of the electron, and the same applies to the Matters and the plasma of the proton.

As the Magravs of different Matters of the electron passes different Matter components of the proton, each of the facing Matters' Magravs forces within the proton and the electron have to interact with each other, plus the electrons' and protons' overall Magravs positioning in respect to that particular Matter in the proton and electron. Which, this type of interactions and Magravs repositioning between the two involved Matters of each plasma will keep on repeating on continuous bases as both the proton and the electron are independent dynamic entities. As the ever-continuous Magravs positioning between the two dynamic entities leads to the ever changing in position of the lighter by mass (the electron) of the two entities, to move around the proton, hence this chasing-up of the ever-repositioning movement becomes the "uncertain" position or erratic motion of the electron around its proton.

This giving the electron in that given configuration of interactions of the Magravs its *pulled* ***closer*** *to* ***or pushed*** *further away* from the nucleus. Then, immediately, the electron has to finds its new overall Magravs balance positioning, in respect to the proton.

Then, due to the dynamism of both plasmatic Magravs of proton and electron, other Matters' fields in the two plasmas come into play and face each other and their Magravs of these two new Matters and overall Magravs have to interact again.

Therefore, the new facing Matter of the plasma of the electron Magravs have to find a new Magravs positioning in respect to the new Matter of the proton's Magravs and the overall Magravs of the two plasmas.

Further on, again, as both the proton and electron are dynamic, the electron has to find a *new Magravs positioning*, in respect to these new Matters facing each other from each entity interactions, this change of Matters facing each other takes place on a continuous basis, as different Matters and Magravs of both components and the overall structure of each atom come to exert their forces on each other and the overall balance distance of both the electron and proton position is to be maintained as every time new Matters in each entity come to face each other. We call this the ***Magravs positioning principle*** (or Magravs positioning).

The result of this continuous change of the Magravs positioning of the Matters of the electron in respect to the Matters of proton and their overall Magravs, causes and creates the motion of the electron around its nucleus.

The behaviour and interaction of the ever-changing of Magravs positioning of the proton and the electron Magravs in respect to each other, leads to the creation of an erratic, never duplicated path, and is the cause of the motion of the electron around the proton.

That is to say, as the electron rotates around the proton, its position and distance in respect to the proton changes, according to the overall position and balance of the gravitational pull forces and Magnetic field push forces of all three components of its Matters and their respective plasmas, in respect to the position of all three Matters Magravs of the protons' and overall Magravs of the proton.

Nevertheless, as the Matters, in the proton and the electron are both dynamic themselves, the rotation of the electron around the nucleus is changing by the principle of the Magravs positioning of the Magravs balancing. Where, this leads to the ever motion of the electron around the proton of an atom (Fig. 50).

As the overall strength of the Magravs of both components of the atom are the same, this leads to a minimum and maximum distance that can be attained by the electron field strength, in its position in respect to and from its proton. This explains why an electron appears to be moving erratically around the centre point, with a given minimum and maximum distance from the centre proton. This minimum and maximum is to be known as the amplitude (minus and maximum) of the distance of the electron from its proton.

In fact, as the Matters dynamic components Magravs of the electron interact with the combined dynamic Magravs of the proton, the electron, which is the less magnetically dense of the two, has to try to find its position, in respect to all the components of the denser magnetic fields plasma of the proton.


MATTER
G1
ANTIMATTER
G2
F1
Transition region
DARK
MATTER
G3
PROTON
ATOM
ELECTRON
G3
DARK
MATTER
G2
ANTIMATTER
G1
MATTER
F1
Transition region

Fig. 50: Schematic of dynamic pmtics of Matters and fields of the proton and the electron and their interaction of individual Matters and their overall plasma and Magravs, leading to Magravs positioning and motion of electron in respect to its nucleus.

This continuous change in the Magravs positioning of the electron, in respect to the proton, leads to the continuous rotational motion of the electron around the proton (Fig. 50)

In fact, one can conclude “the proton and the electron are made up of composite Magravs of several different Matters by simply observing the erratic path of the motion of the electron around the proton”.

In principle it can be said that the magnetic fields strength of any magnetic fields or Matter is ***position dependent*** of the two parts of the fields from each other, which the field has been released from. This is how magnetic fields strength in principle are determined and created. (Paper: Creation of Magnetic fields).

For example, the interaction of the Magravs of the Dark Matter’s in the plasma of the electron interacting with the Antimatter’s Magravs in the plasma of the proton and their overall Magravs of the electron and proton plasmas in respect to each other, decides the position and the distance of the Dark Matter of the electron in respect to the proton.

Universal Magravs positioning principle

The effect of the composite components of the proton and the electron's Magnetic fields and gravitational fields strength, changes the path of the electron as it approaches each Matter of the proton. In composite nucleus, the overall fields' strength of all the protons of the nucleus dictates the distance of the electron from the nucleus.

All motions of objects and fields in the universe are due to the ***overall*** *Magravs positioning of one pmtics of one object or ray*, and so on, *in respect to another*.

I call this dictation of position of an entity in respect to another entity, due to their Magravs positioning distance, the "**universal Magravs positioning principle"** for motion in the universe.

This Magravs positioning of Matter takes place within the constraints of Matters' possessing their own composite pmtics Matters fields‘ strength.

Universal method of motion

In principle, "the **continuous dynamic Magravs positioning** of one dynamic single ray or multiple Matters of multi-cores plasmas of an object in respect to another dynamic single or multi-Matters of a multi-cores plasmas of another objects, **leading to and/or can lead to and cause the motion** Matters, matters in the universe in respect to each other".

I call this method of **continuous change in Magravs positioning** of one entity in respect to another causing motion in one of the two entities, "**The Universal method of motion "**.

Motions of atoms and their components interactions, the molecules, solar systems and galaxies in the universe, are all based on the ***same*** *simple universal method of motion*.

The dynamic plasmatic Magravs of Matters within the constituent structure of one entity dictates the position and direction and the path of the motion of one object in respect to another dynamic plasmatic Magravs of Matters within the constituent structure of the entity. Motion of components of atoms, motion of planets of solar systems and physical contents of motion of galaxies in the universe are all based on this principle.

The universal method of motion of any two gravitated objects in respect to each other is based on the dynamic plasmatic Magravs strength interaction and attraction of all of its complete composite components of Matters and forces within the object, ***irrespective*** *of the physical size* of the system. All universal gravitational objects follow the same principle of motion as an electron around its proton, the same as is for the motion of Matters in the initial fundamental plasmas.

It is correct to say, "**motion in the universe** is totally and exclusively caused and is due to **Magravs strength positioning** of rays, fields, matters, Matters electron, planet, stars and galaxies in **respect** to each other".

Thus from this point on it is clear that **one does not need to burn fuel** to create **motion, but use Matmags**. However, one only needs to create the right Magravs strength within any system to attain dynamic Magravs positioning in respect to another object, this being, a planet, a star, a solar system or a galaxy for the system to be in motion.

This method of utilising the plasmatic Magravs interaction for the creation of Magravs forces within a system, that brings about the motion of one object in respect to another due to Magravs positioning, is to be known as the "**Magravs positioning methods and universal principle of gravitational motion".**

Thus, the Magravs positioning principles of motion are the future for the creation of motion for automotive, marine, air and space industry.

Through this method of Magravs positioning, there is no need for the burning of fuel in engines to move cars or use liquid fuelled jet propulsion systems to fly rockets into space.

When speaking about gravitational or Magravs positioning, this means the collective effect of gravitational field and Magnetic fields of one system in respect to another object or plasmas, Magravs of planets or stars.

It is important to remember that in the universal order of motion, the ***plasmatic gravitational field*** and ***plasmatic Magnetic fields***, are *integrated*, thus simultaneously they co-exist and one cannot exist and operate without the other.

In the universe the **Magravs positioning of Antimatters** in respect to each other and their plasmatic magnetic fields does exist. Further, there exists the **Magravs positioning of the Dark Matter** in respect to each other and their plasmatic magnetic fields too.

The way the Magravs systems of the future will be set-up and operate will dictate in which gravitational fields strength and dimensions the crafts of future will travel in.

In man-made systems using the plasmatic magnetic fields of the Matters that, through their interaction with each other, create the Magravs needed for positioning*: simply by creating Magravs* ***within a reactor***, and these systems will, by trying to find its new Magravs positioning balance in respect to the Magravs, for an example, in atmospheric area of the planet, cause the motion of the reactor system in respect to the surface of the planet.

The creation of motion through Magravs *positioning* can be used in an aircraft equipped with gravitational reactors in respect to Earth, or with a spacecraft in respect to a planet(s), solar system or galaxy.

Methods based on the Grapos principle for motions are the future for the creation of motion in space, according and in parallel to the way the universe is operating for millions of years for its dynamic existence.

CHAPTER 20

Molecules

The creation of plasma and the way its plasmatic Magravs interact to bring about a balance in its overall plasmatic Magravs and their effect on each other, leading to further interactions and balances in different atoms and their components in different dimensions in atoms has been explained. This balancing and positioning of plasmatic Magravs in between different atoms of different Matters brings about how the final Matters, plasmas and atoms can be brought together, leading to how molecules are come to be generated.

That is to say, for the creation of a molecule, it is necessary that the plasmas of protons and neutrons of any nucleus of an atom, and atoms of different elements, need to have a total plasmatic Magnetic field forces and gravitational field forces positioning balance in a given environment so that these atoms can hold onto their total structure, for the molecules to be created.

Thus, by the same principle a molecule or a cell can only be created where, the Magnetic fields and gravitational fields positioning are in equilibrium in all its participant atoms plasmatic magnetic fields (Fig. 51).

At the same time, the whole of the structure of the molecules' plasmatic Magravs have to find plasmatic Magravs balance in respect to their surrounding environments Magravs for the molecules to be able to exist as an entity in a given environment. This in fact, explains why certain atoms and molecules, in certain configurations, can never exist in one environment, while they are prevalent in other environments, like planets, or galaxies and why different pmtics forces and conditions can apply to the same Matter, and Matter manifest itself as a matter in state of solid, liquid and gas.

Likewise, the same can explain why proteins of specific characteristics are created or maintained by certain cells in one part of the human body and not in other parts of the body (9).

In fact, if the same conditions of plasmatic magnetic fields are, or can be, maintained in any part of the universe, one can reproduce exactly all the Matters known to Man anywhere in the universe.

That is to say, when one can create the required balance and equilibrium environment in the total and overall Magravs of the atoms participating in the construction of a molecule, one can replicate and maintain any molecule. Therefore this explains that Van der Waals forces of **pull** and **push**, merely can be known as the **gravitational** fields forces and **Magnetic** field forces respectively operating between different molecules, irrespective of their binding structure with other molecules or atoms.


NEUTRON
PROTON
ELECTRON
MATTER
NORMAL
G1
ANTIMATTER
G2
DARK
MATTER
G3
F1
Transition region

Fig. 51: Schematic pmtics of atoms gravitational (Magravs) positioning to form a molecule.

In the industrial Magravs reactors of the future, one can produce as many atoms as one needs by just absorbing the plasma from space or the environment, for any application and purpose like the production of the hydrogen molecules, carbon, nitrogen, oxygen for the production of proteins for food, air, water and so forth, by simply replicating the Magravs of the preferred molecules and allowing their positioning and interactions.

In the future, by giving a standard chart of Magravs strength and prevailing magnetic fields forces, temperature and pressure of plasma, atoms and molecules, one can produce and maintain any atom and molecule anywhere in the universe.

CHAPTER 21

Plasma Dilution Technology

The Plasma Dilution Technology is the new approach for the use of new gained knowledge for creation and control of plasma and its sub-Matters constituents Matters and their fundamental elementary particles.

The new understanding and insight into the construction and the structure of plasma and its constituent Matters and their magnetic fields, opens up new opportunities for the creation of energy and motion, production of new materials, for medical uses and so many other applications.

The plasma dilution technology allows the plasmas' Matters components to be diluted within a soup of Matters and their pmtics made up of exactly of the plasmas' own composite structure.

Through the specially designed ***nuclear reactors***, conditions are created within the structure of the reactor that the plasma is contained in a safe and secure way in reactors cores configuration.

The operation of these reactors can be controlled so that they do not release any radiation into the environment and they create no waste of any kind, this being the likes of radioactive materials or CO_2 waste, as has been the trend in the current nuclear and energy production industry.

Through the understanding and creation of a parallel environments, similar to the internal environment of the same weak plasmatic magnetic fields of the plasma itself, plasmatic magnetic soup environments are produced in these types of reactors, so that the plasmatic magnetic fields condition within the reactor cores matches the plasmatic magnetic fields of the binding forces (Coulomb Barrier) of the initial fundamental plasma, as the components of this plasma soup, this barrier is magnetically diluted and soften, allowing the plasma to open through the operation of the reactors, for the Matters of the plasma to become part of the dilution soup of Matters and fields forces of the reactor.

A soup of weak plasmatic magnetic fields

These plasmatic magnetic fields saturated reactors will allow components of any plasma introduced into the reactor to be loosened and, the Matter, the Antimatter and the Dark Matter of the plasma, to be free to move within the structure of the plasma soup, which has been created through specific setting and Matter combination. Matters once loosen from other Matters within the soup of the plasma, these are then free for their fundamental particles effects to be utilised to achieve any desired effects, like for fusion and production of new matters, lift and motion.

Reactors that facilitate such a dilution of plasma I call **Plasma Dilution Reactors** (Fig. 56) and their process of dilution as the **Plasma dilution principle** and their knowledge as the ***plasma dilution technology*** (Fig. 52).


D1
K2
A1
B1
G1-A
H3
C2
A2
B2
G2-A
A1
B1
G1-B
C3
B3
G3-A
F2
C1 A3
F1-A
C3
B3
G3-B
H1
H2
E3
E1
E2
F3
C2
A2
B2
G2-B
A1
B1
G1-C
C1 A3
F1-B
K1
C2
A2
B2
G2-C
D3
D2
C1 A3
F1-C
C3
B3
G3-C
F1

Fig. 52: Plasma dilution concept and technology.

Further interaction of the constituent principle plasmatic magnetic fields of the Matters of the plasma inside the cores of these reactors can create effects that can be used to achieve desired outcomes from their interactions with other Matters or matters and fields outside or inside the reactor's structural environment and this is exactly the way and the method that different entities in the universe function and operate to achieve certain desired effects and production of Materials.

Diluting the plasma in the larger pmtics environment of the reactor is another option in the nuclear world for achieving fission, fusion, production of new Matters, matters, for generation of energy and motion.

Disentanglement

Through the Plasma dilution process, once the new plasma soup is produced in the reactor cores, the weak interacting plasmatic magnetic fields soup interacts with the binding fields of the components of the Matters of the plasmas which are further introduced into the reactor cores, this allows the Matters of new plasma to disentangle themselves from each other (Fig. 53), if this level of dilution of new plasma is required.

In this process of plasma dilution, the sub-components of the plasma are allowed to loosen up from each other and not necessarily allowing the separation of all the Matters of the plasma from each other.


INITIAL FUNDAMENTAL PLASMA
MATTER
ANTIMATTER
M1
N1
G1-F
P1
M3
F1-F
M2
P2
N2
G2-F
P3
N3
G3-F
A1
B1
G1-A
H3
A1
B1
G1-B
F2
C2
A2
B2
G2-A
C1
A3
F1-B
E1
E2
C3
B3
G3-B
H1
H2
E3
A1
B1
G1-C
C1
A3
F1-A
C3
B3
G3-A
K1
C2
A2
B2
G2-C
C2
A2
B2
G2-B
C1
A3
F1-C
D2
C3
B3
G3-C
DARK MATTER
FUNNEL
LOOSE PLASMATIC MAGNETIC FIELDS

Fig. 53: Dilution process of initial fundamental plasma within a soup of Matters.

Through this method, different components of the Matters and fields of the plasma can be used for any purpose that the operator decides or that the system is pre-set to.

Hence, each sub-component Matter of the plasmas in the reactor can be separated from the plasma in any quantities of individual Matter within the soup.


LOOSE PLASMATIC MAGNETIC FIELDS
MATTER
ANTIMATTER
INITIAL FUNDAMENTAL PLASMA
A1
B1
G1-A
H3
C2
A2
B2
G2-A
M1
N1
P2
M2
N2
G1-F
P1
M3
F1-F
G2-F
G1-B
F2
P3
N3
G3-F
C1
A3
F1-B
C3
B3
G3-B
E1
E2
H1
H2
E3
F1-A
G2-B
K1
G3-A
G2-C
G3-C
D2
MATTER
NORMAL
G1
ANTI-MATTER
G2
DARK
G3
F1
Transition region
ATOM
PROTON
ELECTRON
NEUTRON
F1-C
G1-C
DARK MATTER
ATOM
INITIAL FUNDAMENTAL PLASMA
FUNNEL

Fig. 54: Dilution process of initial fundamental plasma and atoms and molecules within a soup of Matters and pmtics.

The plasma dilution technology (Fig. 54) replaces the present state-of-the-art technology *accelerators* used for the separation of different components of plasma or an atom.

The plasma dilution reactors for example can be used for the extraction of Antimatter, instead of the presently used methods of slamming plasma at high speeds in accelerators into specific pure solid metal matters to extract its Antimatter, by chance, every once in while (6, 7 and 8).

In the same way, the plasma dilution reactors can be used in the fusion industry where, present technology uses huge enforcing magnetic fields to force the fusion of plasmas.

With the plasma dilution method, the components of the plasma are opened up, in a soft way, loosened, and then are allowed to be separated from other Matters in their surroundings, and into their specific sub-components, interacting collectively in the soup of the Matters for their use for any given specific purpose (Fig. 54), like for fusion of Matters or matter.

These reactors even can be used for fusing components of two plasmas together. If the Antimatter is needed to be separated from the Matter, this can be easily done, as by creating a weak plasmatic magnetic field, around the plasma, then, the Antimatter components of the plasma can be separated for the use of their plasmatic magnetic fields properties and effects for example for the production of powerful Magravs forces. Where, the rest of plasmas' components are then *left in the* ***dilution soup***.

When one has used these freed Antimatter plasmatic magnetic fields for their effects they create, for the purposes that one needs, then the system-loading Magravs configuration and parameters can be altered to *change the dynamism of the reactor*, and gradually disassemble the dilution fields. Then the Matters of the plasma are allowed to return to their original Matters' components state of the plasma, and for the plasma to return its atomic structure and so forth.

All these reactions can be created and controlled without the creation of unstable or high temperature environments as is seen in the universal order of creation of Matters, energy and motion.

At the same time, there is no need to hold on to certain Matters and to run expensive holding systems for Antimatter as done for example by Fermilab at the present.

All these processes are carried out without any release of radiation or the production of new radioactive waste.

These effects can be created at room temperature and within portable safe nuclear reactors, which have been designed, developed and tested in the past few years.

There is conclusive evidence from tests, that the principle of the untangling of plasmas' magnetic fields binding forces through plasma dilution technology is a proven fundamental principle for the future of energy production and creation of motion for space travel.

That is to say, that we have seen the effects that Antimatter in being loose in the cores of the reactors to possess stronger fields and create stronger Magravs forces than the Matter components of the same plasma. We have managed to lift and reduce weight of reactor systems in respect to its environment, and we have create new matters, all at room temperature, in the recent past through the operation of plasma dilution reactors, as we have reported and applied patents for.

This stronger characteristics and effects of Antimatter are purely due to the fact “that at the inception of the plasma, the Antimatter components of the plasma were created by the stronger plasmatic magnetic fields to start with”.

Similarly, gravitational field forces of the Dark Matter components of the plasma can be used through the plasma dilution technology for the creation of high-speed motion without friction for crafts of the future in space technology, or these reactors can be used for the extraction of poison from a substance like water or air.

In testing for the production of the Dark Matter principle, systems have been twisted in their axel and damaged, confirming the enormous power of invisible, powerful, Magravs of the Dark Matter.

In general, it can be said, “The future is **bright**, the future is plasmatic magnetic fields based, through the production of controlled plasmatic dilution technology reactors”

CHAPTER 22

Matters and Magravs systems

The technology that uses the properties of the Matters of plasma to create motion and energy, instead of the present use of matter, I have called ***the Magravs positioning Systems Technology***.

The fundamental difference between the **Matter** gravitational technology and **matter** propulsion and energy systems can be explained in simple way.

matter propulsion technology

The present **matter** propulsion systems in burning fuels have **to fight and to overcome** Magravs of the planet for **lift and motion.** This we see in the rocket propulsion space technology of today.

In the matter systems, like the propulsions systems, power stations and cars use the fundamental principles of ***burning matter*** to release its energy and convert this energy from one form to another to create motion and energy. This technology has always delivered *limited energy*, and due to its bulkiness of mass and weight of the fuel that have to be carried by systems to achieve their objectives, these systems are payload dependent.

The matter system uses the ***Matter part*** *of plasma*, the **weakest** and **least energetic** part of the plasma. By their nature as has been seen in the past, matter systems create different type of waste, like CO_2, nuclear waste, and so on.

Matter gravitational technology

The **Matters** Magravs system uses the *properties of the all Matters* in the plasma to create motion, lift and energy without destroying the characteristic of the Matters, and the system works **within** and through the **Magnetic field** and **gravitational field** of its environment to **attain position and motion,** one can achieve more working ***within*** *than* ***fighting against*** the Magravs of the planet.

In the present state-of-art technologies, always the matter components are considered for their physical ***action and reaction***, and not their Matters field's components.

Matters used in the Magravs systems, uses the properties and interaction of all the initial fundamental particles properties of all Matters within the components of the fundamental plasma, "Matter, Antimatter and Dark Matter". There is no need to "react" as in the matter processes, since the system works' within and is part of the same magnetic fields base system and works through the universal natural forces. Therefore there is never a need for reaction for motion, as the system always magnetically balances itself in respect to other magnetic fields forces.

These reactor systems are developed to function in the same way as the interaction of the initial fundamental particles leads to the creation of Magravs for the motion of Matters through the Magravs positioning principle in the universe.

In these systems, there is no destruction of Matter, since the system can use Matters pmtics properties for the enhancement of Magravs positioning, for the creation of motion and energy and so forth.

This method of the use of Matters creates heat, if it is needed from a system.

As it has been observed, stars create massive heat to create vast amount of energy and Magravs forces, through tests it have been proven that the creation of motion and energy by the use of Magravs forces, these systems creating effects which are ***temperature independent***.

Used in the atmospheric conditions, the Grapos, through the principles of the creation of plasmatic Magravs within the cores of the reactor and their interaction with the plasmatic Magravs of the planet, this interaction of these two Magravs, leads to creation of a *magnetosphere* around the systems. Where, the interaction of plasmatic Magravs of the system and the planets Magravs always lead to ***the creation of light*** around the system. This light being created through the principle of interaction of two plasmatic magnetic fields as was explained in Chapters 7 (Fig. 29 and Fig. 31). This is exactly how the magnetosphere of the Earth is created in respect to the Magravs interaction of the Earth and the Sun, and the same principle as for the creation of the daylight as seen around the Earth.

The magnetosphere created around the Magravs system, can be a spherical or oval bright light in shape depending upon the speed of motion and protection chosen by the operator.

In the **Universal systems** like stars**, their Magravs forces** are *fixed* by their initial matters' contents in their inner cores at the point of the inception of the star, and the magnetic fields strength they generate for the production of their Magravs strength, once the strength of the Magravs is set for the stars, these cannot be changed arbitrarily to achieve different Magravs strengths for the stars.

Whereas in the **Grapos reactors'** developed for the motion of crafts, the **Magravs** parameters of these reactor systems *can be changed and manipulated* according to the position, speed, energy and so forth, as is desired of the system by their operators.

In these systems, the reactor-operator dictates the Magravs strength of the system, therefore he decides the speed and the position of the craft at any position in space in respect to another Magravs system, the like of the Earth surface or a given distance from the moon or galaxies.

Interesting enough, all these effects of motion are achieved even though the system uses the same fundamental methods and Matters as in the cores of the planet or star that the systems is operating within or aiming for.



Fig. 55: Representation of interaction of four different pmtics strength of gravitational (Magravs) positioning systems (Grapos) in respect to Earth pmtics Magravs (1, 2, 3 and 4).

Note: Figure 55, numbers 5, 6, 7 and 8 show that the position of clouds in respect to Earth are pmtics Magravs strength dependent, and not size or volume dependent.

Thus, wherever the Magravs principles reactors are used for flight in a system, like in atmospheric condition of the planets', the natural outcome of the interaction of the two pmtics Magravs of the environment and the reactors Magravs is the appearance of and creation of natural light around these flying systems (Fig. 55 light regions of 1, 2, 3 and 4). Thus, the same Magravs positioning systems can be used, to produce lamps that can create light for years without needing to burn any fuel or consuming electricity.

Simultaneously, in a dense plasmatic magnetic fields environment, like the Earth, when the Grapos are used for motion and lift, due to the interaction pmtics Magravs, of the Earth and the system, these systems will produce their own magnetosphere around them. This magnetospheric light intensity is reactor Magravs' ***strength*** *dependent* and through the principle of interaction of two pmtics of plasmas as was discussed before, these magnetospheres will cause the creation of bright light around these systems in the

Earth atmospheric condition. As the brightness of the magnetosphere around the system in respect to its surrounding pmtics strength will be dependent on the strength of the plasmatic magnetic fields that are created by the Magravs positioning reactors, and in respect to the systems' position, considering that the plasmatic magnetic fields of the Earth is constant.

Thus, the confirmation of systems using Magravs positioning technology for motion in dense atmospheric condition like the Earth will be the appearance of bright moving lights (Fig. 55 lights 3 and 4) in the Earth atmosphere or any given atmosphere or medium in the universe. In dense atmospheric conditions, these Magravs systems will be appear to be a shining bright light floating in air, either with high speeds or seated stationary.

In some literatures, systems that use Grapos for motion and appear as bright lights from an unknown source in the skies have been called, the Unidentified Flying Objects, also called ***UFO's*** (Fig. 55 lights 1, 2, 3 and 4). Now that the method by which these bright lights in the sky are produced, their operation understood, and known, these crafts are not Unidentified Flying Objects no longer.

Nevertheless, in reality, it is now interesting to see who are the users of these systems. Whoever are the users' of these Magravs systems, this does not necessarily means that they are more advanced in scientific level than the human race in its present scientific and technological evolution. However, this simply means that they have managed to harvest the principles of the plasmatic magnetic fields, and the constituents of Matters, some time before the human race.

Now that the technology and the principles behind the plasmatic Magravs positioning fields are open to the human race, it is not hard to see that interaction with users of these bright lights will be inevitable and will only be to the Mans advantage, to help man to reach new levels of understanding about his universe.

In tests, the effects and bright light created by use of these reactor systems, which have been developed and tested for weight reduction and lift, has been noted.

The operation and interference with the radar and radio frequencies, through tests running of these Magravs positioning reactors have been videoed and recorded in August 2008. This confirms the origin of the motion of these systems to be on a plasmatic magnetic fields basis, as the system's Magnetic field operation interferes with radio waves, which radio waves are magnetic fields based entities.

NASA has done tests on these types of magnetospheric condition and motion system, on a miniature scale, in advance concept projects known as MINI-magnetospheric plasma propulsion project called M2P2 (40). They have achieved this by using the argon gas up to this stage. They hope to be able to finance the project to reach helium and then the use of hydrogen as base-material in years to come. They may then use plasma of hydrogen atoms later as they progress in gaining knowledge in 30 to 50 years and having the budget. However this is still one of the theoretical approaches for NASA.

Fermilab (6, 7, and 8) is looking for the Antimatter as the “fuel” for propulsion systems of the future space programs for NASA. If they redirect their attention into the properties and the effects of the Antimatters that they have gathered by now, they can achieve the same results as have been seen and tested in the recent Magravs systems reported on our Foundation web site and patents that have been applied for.

Through the understanding of the real forces in operation of the universe, the Magravs positioning reactors are simply years ahead of their time.

Our Magravs positioning reactors are not in a mini-scale dimension as NASA’s project has tested and envisages at this moment in time, but these are in several sizes, which can create controllable size magnetospheric conditions, as the operator of these simple systems sees fit the purpose.

In the near future, these Magravs systems will replace the propulsion systems that have been used for space explorations and air travel.

The advantage with the Matters powered Grapos is that these systems create a magnetosphere around the reactor system. This is the same natural magnetic protection barrier for the future spacecrafts as the magnetosphere around the Earth has been, protecting man from space debris and cosmic radiations for billions of years.

These systems’ magnetosphere protection capabilities can be used to protect the craft in deep oceans from water and the crafts to be used like the submarines of today, with the difference that these systems magnetosphere will allow these crafts to reach the deepest parts of oceans floors without any problem, as they can reach any depth in liquid planets in the universe.

The magnetosphere generated by Grapos will create *magnetic shielding* at Matters’ level of the plasmas that can be used to pass through materials like ice without melting their matter(s). But simply by diluting the ice Matter(s) at plasma levels as in the plasma dilution reactors. In these conditions the crafts will appears as the craft will come out of nowhere and with no holes indicating the position of the exit from the ice by the spacecraft. If observed from the distance these crafts will be like bright lights shining and jumping out from the ice-covered sea-surface.

These plasma dilution Magravs positioning systems, by the use of Matters, will be the only solution for plasmatic saturation, once these crafts will pass and go through cosmic dusts as they temporarily disentangle the Magravs of atoms and plasmas of these cosmic dusts by just diluting the components of the Magravs of the Matters of cosmic dusts with the Magravs of the craft protection magnetosphere, and the craft passes through the dust matters as if they were not there.

CHAPTER 23

Matter Pmtics in reactors for lift and motion

The utilisation of the Magravs forces of dynamic multi-core systems, in respect to each other, for the purpose of the creation of lift and motion is discussed in this chapter.

In multiple cores *dynamic plasmatic dilution Grapos* that have been developed and tested at room temperature, these systems have proven to have the capability to produce different plasmatic Magravs forces strength as strong as those of a hot centre core object, like the Earth.

Using the principle of the creation of dynamic plasmatic Magravs forces within the structure of a multi-core reactor, the system can be caused to find its own position in respect to the environment of a planet or any Magnetic field and gravitational field forces in space.

In developing and achieving the Magravs positioning of these systems, in respect to the planet's Magravs forces, on the surface of the planet, leads to the reduction of the weight of the system to start with. Once the two plasmatic magnetic fields of the planet and the system reach **the total balance or equilibrium**, the ***zero weight*** of the system, in respect to the planets gravitational fields at a given point and the position, is achieved.

From this point of ***total equilibrium*** any further change(s) in Magravs force strength of the reactor in the same direction and configuration as before, this leading to and causing the ***free lift*** and **motion** of the reactor system, in respect to the planet.

Principle concept of upward or separation motion

The upward motion of the systems in respect to the planetary fields or any other Magravs systems is simply due to the fact that the **Magnetic field of the planet** and the Magnetic field of the system is of the *same polarity*. Thus, the two similar Magnetic polarities ***repel*** each other, hence causing the upward or separation motion of the system.

It is fundamental to understand that: In the Magravs positioning reactors **"The repulsion of two objects or moving away from each other, like moving away form the surface of the Earth, is totally due to interaction of the two pmtics of Magnetic fields forces of the systems and of the planet.**

Whereas**, any closeness or gravitation of the reactor system in respect to the planet is controlled by the pmtics of the gravitational fields between the system and the planet in respect to each other."**

This is how Magravs positioning reactors, in possession of dynamic cores, create up or down (lift and descend) motion in respect to another Magravs of an object, like the Earth.

In these systems by changing the strength of any of the gravitational or Magnetic fields strength within the reactors of a system, this system, necessitates the finding of a new balance position between the system and the planet's Magnetic and gravitational fields.

By changing the parameters of the reactors and for the reactor to find a new balance between the systems' own Magravs and the planetary Magravs, this causes the motion of the system as it tries to reach the newly desired balanced Magravs force position, in respect to the planet Magravs.

This is the universal method of **creation of motion** ***without burning an atom*** of any matter, and this is exactly how all the celestial objects find their position and motion in the ever-dynamic environment of plasma of an electron in an atom, solar systems, galaxy and universes.

The motion of the system is purely due to the phenomenon of **Magravs positioning**, of one system in respect to the other(s).

Simple, portable, plasma dilution nuclear reactor systems, can produce the required Magravs forces within its reactor cores on a continuous repositioning criterion bases that can cause the motion of the Magravs positioning system (Fig. 56).

In these Grapos, the individual pmtics released in the central core (Fig. 56) in their interaction with the compatible and matching pmtics' strength of other pmtics *in the same core* can then collectively interact with the same collection of pmtics created in the other cores of the reactor (Fig. 56), and interactions and interlocking of the same pmtics strength in *different cores* of the system leads to the creation of Magravs within and around these types of reactors simultaneously.

By referring to figure 1, 2 and 3 in the early chapters, then it can be realised that, what has been achieved in these dilution plasmatic Magravs positioning reactors (Fig. 56), is exactly what has been going on in inner cores of planetary systems such as the Earth, to create their Magravs for them to hold on to their components through their gravitational fields, and at the same time to protect their matters from other celestial objects through their Magnetic fields, and at the same time create positioning in respect to other Magravs, at the same leading to creation of motion of the reactor. These reactors are truly an all ***integrated system for flight and motion.***

At the same time, these reactors during their operation within a craft system creates' and maintains' an independent internal gravitational field forces within the reactor cores fields catchments' zone. For example these properties and effects can be used to maintain an earth, one-G gravitational field force within the confine of any spacecraft, independent of the position and speed of the craft where, this position in the universe might be.

These reactors in collaboration and simultaneous production of the Magnetic fields and gravitational fields leads to the creation of a distinctive and separate magnetosphere around the reactor or the craft which, uses such reactor technology, similar to the Earth atmospheric magnetic field.


C1 A3
F1-H
C3 B3
G3-B
A1 B1
G1-B
A1 B1
G1-D
E3
C1 A3
F1-A
C3 B3
G3-H
C3 B3
G3-C
K2
C2 A2 B2
G2-C
C1 A3
F1-C
H3
C2 A2 B2
G2-B
C3 B3
G3-A
C2 A2 B2
G2-D
C2 A2 B2
G2-H
D1
C1 A3
F1-B
A1 B1
G1-C
A1 B1
G1-F
C2 A2 B2
G2-A
A1 B1
G1-E
C2 A2 B2
G2-E
F3
F2
D3
D2
C1 A3
F1-D
A1 B1
G1-H
C3 B3
G3-F
H1
H2
F1
C1 A3
F1-E
A1 B1
G1-A
C3 B3
G3-E
C2 A2 B2
G2-F
C3 B3
G3-D
E1
E2
C1 A3
F1-F
K1

Fig. 56: The Keshe Model of Plasma Dilution and Magravs positioning reactor.

Thus, the Grapos are exact copies of the planetary Magravs producing systems. Similarly, they utilise the same Matters inside them, and the same principle of interaction to create Magravs between the systems and a planet. This being the same principle as, between the Earth and the Sun field forces and the Earth, and the rest of planets in the solar system and the same system principle as between electrons and protons. (Fig. 57)

Therefore, by changing the strength of the Magravs strength of Grapos, these systems can be positioned in any orbit or position around the Earth (Fig. 55, Fig. 56 and Fig. 57 c), in the solar systems or galaxies, with the use of Matters, rather than matters in the system.

In other words, the balancing of two Magravs' forces of the system, in respect to the planetary Magravs forces, leads to lift or descend of the systems. This separation only leads to a vertical up or down motion of one-system field in respect to the other systems' field. This means lift or descend of the system in a craft takes place vertically and not a 360-degree directional motion of the system.

In current physics, scientists call this the anti-gravitational field forces needed for lift and these systems are called anti-gravitational systems.

In reality, any motion of a system is not due to anti-gravitational field forces, but in fact is due to the total balancing of the gravitational field and Magnetic fields of the two systems of the planet and the Magravs positioning of a reactor, in respect to each other in a given position.

For directional motion, the same principle as vertical lift is used with the difference that in the directional case, the ratio of change between Magnetic fields and gravitational field created within the system are utilised, as the two field forces in the reactor of such a system have an opposite gradient of scale of strength with each other. That is to say, the control of the creation of gravitational fields increases with the same increment as the decrease in Magnetic field strength, within the interaction of the fields of the cores of the system, in respect to the planetary field forces.

The same principle of Magravs positioning can be used in space for motion, in a direction of motion towards or away from a planet, star or galaxy.

There is an alternative *method of motion*, which is by *compartmenting* each core of the reactor. This is a highly advanced technology and needs a full understanding of the creation and control of the magnetic fields' strength of magnetic rays and Matters mixtures and full control of the motion of dynamic Matters in a dynamic environment of the reactor cores.

As motioned before, reactors have been designed, built, and tested to confirm the effects of weight reduction and lift, and the results have proven the correctness of the principle of Magravs positioning reactors, rather than the anti-gravitational field assumptions.

It has been shown that the **system gravitational field and Magnetic field strength** are **independent** of the **size of the system for the mass that** they can lift.

In tests carried-out in 2008, a ten-kilogram reactor system was used to lift a 100-kilogram weight.

In early 2009, the system combination was used to reduce weight from 9 kg by increments of 100 grams. Then another system was use to reduce the weight of the system from 7 kg to 6.5, 6.3 and 6.1 kg and so on in increments of 100 grams. In some tests, the weight of the same system was increased by 100-gram increments also.

These tests were done to show the correctness of the theoretical principles and its practical applications in reduction or increase in Magravs forces of one system in respect to another like the planetary system.

CHAPTER 24

Passive Magnetic Fields

In the universe, there are two types of interaction in respect to plasmatic magnetic fields forces.

One pmtics force is called ***active*** magnetic fields force and the other ***passive*** magnetic fields force.

The *active magnetic fields forces* are the pmtics forces that can exert forces on other fields and components of other pmtics of plasmas causing them to move or vibrate, or receive motion or vibration from the pmtics. This is usually matter-based motion and creates tangible or physical motion of matter.

Active magnetic fields forces usually cause dislocation of the electrons in a cell or vibration of electron in conductive material, etc.

Matters of the plasma mainly produce the **passive** plasmatic magnetic fields.

Passive pmtics can deliver their magnetic fields forces as energies to another plasma of the atom, for them to increase their magnetic fields density or energy without dislocating any Matters plasma's.

Through passive magnetic fields strength, if the plasma is in need of the extra pmtics strength, it can receive the quantity that it needs *of the **same** pmtics strength* for it to return to its ground level pmtics strength level. Otherwise, the pmtics will pass the plasma without transferring any of its pmtics to the second plasma. At the same time the second plasma, if it has extra pmtics which it does not need, it gives the extra pmtics *to the **passing** pmtics,* if it needs the extra pmtics for both pmtics to return to ground levels of their original pmtics strength.

The passive magnetic fields do not cause the atom to move or be dislocated from its position but also cannot cause vibration of the electron of the atom as such.

Passive magnetic fields are pmtics used for delivering the energy levels of vitamins and minerals to atoms and molecules of protein chains and are ***Matter pmtics orientated*** and based.

It is important to note that each plasma carries' one pmtics strength pack in the majority of cases. Thus for human body to receive all its pmtics strength spectrum, the body need to consume different minerals and vitamins and proteins that can deliver certain specific passive plasmatic magnetic fields strength to cover all his cells' needs.

Where the ***active pmtics*** are **matter orientated** and create heat, motion, and vibration in the matter components of the plasma.

CHAPTER 25

New understandings and New Technologies

From the new explanation and understanding of the creation and control of initial fundamental particles (magnetic fields), and further in having access to the new knowledge and the technologies that to be able to replicate the same in small reactors and their systems, the production and the control of MATTERS and the initial fundamental plasma as in **the universal order of the creation of Matters** in these reactors have become simple and practically possible.

The world of science and technology can find new solutions and new sources of Matters for the production of energy, the creation of motion and other applications within the confines of these reactors and this technology will be developed further for these purposes.

In understanding the principles of the working of these reactors, one can make use of, and manipulate, the Matters and energies embedded in the initial fundamental plasmas for the production of new materials, motion and energy. One would be able to use the new understandings of the Matters sub-plasmatic structure for the release of magnetic fields and energies from these Matters.

Through progressive development of this technology, new and simpler methods are devised and developed further for the fission and fusion of Matters and their relevant technologies. Through these new understandings and developments of reactors, new ways and opportunities for the production of energy in the world of nuclear physics has become possible.

For energy production in nuclear fission of today, the state-of-the-art technologies use the ***collision effect*** of neutrons and atoms to break up an atomic structure and release its energy. On the other hand, in the world of nuclear fusion, the reverse methods are in use. Scientists in nuclear and physics laboratories use as ***much force*** as possible to fuse plasmas, and harvest the residual released energies from this process.

Through our technology new and simple reactors are in the reach of the scientific world for the disintegration of an atom, or for the fusing of plasmas through plasma dilution technology. This new approach is less energy consuming, much simpler, more practical and the resulting energies produced are easy to harvest.

The same is seen in the world of aircraft and space industry where, jet engines and propulsion systems are in use to force and displace matters like air to create lift and motion.

With this new knowledge and approach to plasma dilution technology as one integrated system, much simpler and more effective methods based on the universal methods for creation of motion are made available to the aircraft and space industry to move crafts within atmospheric or outer space (Fig. 57 C). Magravs positioning principle of an electron in respect to its proton (Fig. 57 A) and Magravs positioning of the planet Earth in respect to Magravs system of its Sun (Fig. 57 B), these shows similarities between the principle of the use of the new Magravs positioning reactors and their universal parallel systems.


ELECTRON
MATTER
NORMAL
G1
ANTIMATTER
G2
F1
Transition region
MATTER
DARK
G3
PROTON
ATOM
A.
EARTH
SUN
B.
CRAFT
EARTH
C.
GANYMEDE
JUPITER
D.

Fig. 57: Similarities between four different Magravs positioning principles
and systems for motion and position.

Note: Figure 57 D. shows that an independent plasmatic Magravs system can exist within another Magravs system, and have Magravs positioning in respect to each other, as the ***Ganymede****, a moon of the planet Jupiter, has been functioning for millions of years within Jupiter's Magravs. To cosmologists the case of the Ganymede is the only known condition of an inter-gravitational planetary system positioning, and its operation within the Jupiter's magnetosphere could never be explained with present scientific knowledge. Similarly, Grapos reactors can be used in crafts for motion and Magravs positioning within the magnetosphere of the planet Earth, as shown in figure 57 C using the same fundamental principle as the Ganymede.*

Through the fundamentals of this new understanding of the creation and control of plasmatic magnetic fields reactors (Grapos), **craft systems** *do not need to burn Matmags* to create **lift and motion, but where, the reactor uses the Magnetic fields strength of the Matter (the Matmags) to create gravitational positioning.**

In the **Magravs positioning Technology reactors**, by the simple creation of the acquired plasmatic Magravs levels of the desired point in space, within the reactor's systems, the system is forced by its' internally produced Magravs, the need *to reach a new plasmatic Magravs balance* position between the system and the planet Magravs forces‘, this causing the motion of the system in respect to the Earth **without burning any fuel.**

The Magravs positioning technology once used in a craft, unusually these crafts become weight independent. That is to say, the systems payload compared to the power of the gravitational positioning forces of these reactors are so insignificant, that the payload mass becomes irrelevant.

This is how small cores size of matters in comparison, in the centre of the planet Earth, can create such strong plasmatic magnetic fields, that their interactions can keep and cause continuous motion of the heavy loads of matters of the planet, at ease, for billions of years.

The important point about using Grapos in aircraft systems is that the plasmatic Magravs and Magnetosphere fields' catchments area of the system has to pass the physical boundary of the craft itself during motion, in-flight and stationary floating mode or protection mode.

During the operation of plasmatic Grapos, magnetospheres are created around the system interface between system and the planet. At the interface of the magnetosphere of the system, due to the friction between two plasmatic Magravs of the system and the planet, only at the point of the magnetospheric interface of the system, this leads to the creation of visible light (Chapter 7).

In respect to plasmatic gravitational field systems, once the fields are allowed to pass beyond the physical boundary of the craft, this gives the craft being in possession and the advantage of having a dynamic magnetically based magnetospheric protection environment around the system. This magnetic magnetospheric zone around these crafts operates and functions exactly and similar to magnetosphere possessed by the Earth, which, the Earth has generated around itself by the interaction of its own plasmatic gravitational and Magnetic fields with that of its star and the pmtics around its environment in space.

This production of plasmatic magnetospheric shielding is a *natural protection* system offered by all celestial objects in possession of dynamic plasmatic Magravs for the entrapped matters within their systems.

Thus, by the use of Grapos in crafts nothing less than that is natural in the universe and a normal phenomenon for protection of internal matters and structure of the planet are offered.

Using this magnetospheric protection capability of Grapos, crafts of future will travel at speeds beyond the capability of the present technology in the aircraft and space industry. These crafts will travel without their outer-surface ever getting heated-up, or ever being in a position to be hit for example by birds in Earths atmospheric conditions or in space by space debris. The reason for this is due to the fact that the outer surfaces of these crafts *never come to be in contact with other matters*, except its own internally created plasmatic Magravs.

The ***interface*** between the crafts' dynamic Magravs and planets plasmatic dynamic Magravs can be extended through the design and control of the Matters within the reactor cores of these systems, that their interface to be far enough away from the physical body of the craft, that there will be no contact or interface with other Matters and matters of physical body of the craft system. These matters outside the boundary of the system can be Dark Matter, air, liquid or others. These Magravs are needed for the protection of a system like this in space, as the systems cannot be hit or damaged by any cosmic dust or asteroid in the path of motion of the system.

The magnetosphere created around these systems, due to the dynamic characteristics of their nature, create plasmatic magnetic fields that will act and is a magnetic shield for the embedded craft within it. These dynamic magnetospheres around these crafts are naturally watertight systems.

If the plasmatic magnetic fields generated by the system, do not reach and pass the physical outer boundaries of the craft, these crafts can have the gravitational shearing gradient forces fields effects, enforced on it, half-way within its structure, rather than around its outer physical boundary; which partial structural cover of Magravs on the middle of the structure of the craft will end-up in the physical damage or in extreme cases the breaking-off of parts or the whole section of the craft at the point of interface between the system and the planet pmtics Magravs. This shearing-off zone is possible and can happen purely due to a difference in the two Magravs forces strength levels at the magnetospheric boundary of the reactor system in the middle of the structure of the craft.

At the same time the passengers of the future, using the Magravs positioning systems, will travel in gravitational field forces within the boundary structure of the craft in similar conditions as on the Earth. The passengers of these crafts can travel without the need for the present compression systems, in use, in the state-of-the-art aircraft industry. There will be no G-force changes inside these crafts during their flight due to the sudden changes in directional motion or at high-speed capabilities of these crafts. Using Grapos, in spacecrafts, this allows normal life and motion within the craft without the effect of weightlessness as is experienced by the space travels of today.

These crafts through their natural plasmatic magnetic fields interaction will always be rotating, as all celestial objects in possession of Magravs positioning field force do. This rotational effect can be facilitated through the design of the craft that the rotational motion can be transferred and be connected to the outer physical boundaries of these crafts, without affecting the working of the internal structure or passengers of these types of crafts.

This method of travel using plasmatic Magravs protection for motion for the future space systems is to be called the **M***agnetically* **O***riginated* **J***oint* **H***abitation* **A***nd* **N***utrition* (MOJHAN) system. The passengers of this **M***an* **O***riginated* **Z***one* **H***abitation* **A***nd* **N***utrition* to be known as "MOZHAN".

These new names unify the human race by the use of the name of the technology and the method of its travel, through the Men's collective effort to reach this point of scientific achievement over thousands of years, through their progressive evolution in science and technology. This takes away the national dependent names, like Cosmo- or Astro- and the rest from the unique and individual nations, for the collective effort and contribution by all of the inhabitants of the planet in different measures over the times to reach this point in Mans scientific evolution.

The use of Grapos will make national boundaries irrelevant except for tax and local laws. The Grapos will not need airports to land near too. These systems know no national or planetary boundaries and they have no need for fuel as such.

Thus, in the near future the nations will have to devise new ways of dealing with the Mozhans as they can land anywhere, without a need for a specific plot or landing strip. In reality however, these crafts will never even need to touch the ground.

Nevertheless, these systems can reach ground level, when their total reactor Magravs sizes are reduced to a safe planetary level, within a specific spherical zones cavity, allocated just out-side the boundary of the reactor systems but within the craft environment.

Pmtics reactors for production of energy

The creation of energy in the universe and utilisation of Grapos technology for production of energy in essence are based on the same principles.

In the universal order of production of energy like in stars, in these units, the principle of the production of current and energy is not on the base of electrons and their vibration movement. In fact, current and voltages on massive scales in these celestial objects are produce through their only ingredients, which are the plasmas and their creation of the pmtics of Magravs of their Matters within their inner natural cores.

In current state-of-the-art power production units like power stations generators, the rotational motion of magnets, and the magnetic fields forces within the confines of the copper windings, is used to create a continuous vibration of the electrons in the solid matters of the copper wire, to generate a flow of current.

We consider the flow of pmtics in materials like that of the ***wind flow of pmtics*** or what is commonly called the ***current*** *flowing through matters* like in copper wires. Where the plasmatic magnetic fields flow in matters like copper, the strength of the magnetic wind decides the rate of the vibration of the electrons of the atoms of the copper.

In understanding the new concept of the internal structure of an atom there are two fundamental points to consider.

First, the electron is the smaller and the weaker of the two components of an atom. Secondly, **the proton by order of mass is much heavier** and is made itself of greater amounts of the ***same*** plasmatic magnetic fields as **the electron**.

Thus in utilising the power of the plasma of the proton rather than the plasma of the electron, it becomes easier to produce the same levels of power with the use of a fraction of the material compared with the present power units.

This is to say; the new dilution plasma technology will bring into to play the ***use of magnetic characteristic of Matters of the plasma of the proton*** rather *than the vibration of the electron.*

To be able to separate the Matters of plasma of proton within the plasma dilution reactors, one needs to release enough dynamic plasmatic magnetic fields, in motion (energy), in the field strength level of the plasma of proton. These plasmatic magnetic fields can move the plasma of the matters of atoms with profound effects, rather than the electron of an atom.

This new capability and control of magnetic fields strength that can be released by the plasmatic reactors, brings into play totally new methods for energy production for any purpose.

The important point to note is that the production of energy through this method does not mean a change in the common use of electrical equipments. The beauty of this method is that the generators of the future will not be limited in their power production capabilities because of the material and size of the system. This means that even pmtics of plastics, nanolayers or any sort of matters can be used for current production and flow of current.

This changes the present power production capability, and gives the possibility of any generator's construction or any power levels at the point-of-demand, this being nano-amps or megawatts of power, through the operation of the same reactor, simultaneously and separately.

The other advantage is that the plasmatic magnetic fields strength of these reactors can be changed through the operation of the system. This capability of the plasma reactors gives a new insight into the power production capability of these new generators using the present equipments and tool.

New type of Generators

Through the control and power of the plasmatic magnetic fields strength **DY***namic* **P***lasmatic* **M***agnetic* **F***lux* **S***trength*, abbreviated to: **"DYPMFS"** that can be released by these new plasmatic dilution reactors, future electric power generators only need to change their Dypmfs, or the dimensions of the **VO***lume of the* **MA***gnetospheric* **F***ield* **S***trength*, abbreviated to "**VOMAFS**" of the reactor, to envelop the generators' winding using the coil winding method for power production.

Where, the Vomafs of the reactor can cover more of the same copper winding, to produce larger amounts of currents or the strength of Dypmfs of the reactor can be increased or decreased to change the levels of the current out-put of the same winding.

With these new types of plasma magnetic fields system there is no need for transformers, since the exact power input to the motor or engine can be produced by the plasmatic magnetic fields release at the point-of-demand.

For example: considering the present Power Station generating units (Fig. 58), it can be seen that, what has been used as fuel (coal, oil, gas, nuclear) to boil water, to generate steam, to turn the turbine and for the turbine to cause the rotation of the rotor, which is mounted with fixed flux strength magnets, for the motion of these magnetic fields cutting with the matter of the copper coil windings, to generate power, for this power to feed into a power grid.



Fig. 58: Schema of actual electricity production

With the present power station generating units *one losses a vast amount of energy through each step of conversion* from solid or liquid or gas to steam to rotation, by all sorts of channels like different types of frictions, heat lost, losses through the grid. These systems usually need hundreds of kilometres of **transmission lines** to transfer the generated powers to the point-of-demand usually into cities. At the same time these types of generating systems using matter components of plasma, these always produce wastes like CO_2 or nuclear wastes.

In understanding the principle of the rotation of the Earth, through the interaction of two magnetic fields (Fig. 3) and the capability of the planet to create simultaneously the external dynamic Magnetic field (Fig. 1, similarly Fig. 61), with the new knowledge of the use of the plasma dilution Magravs positioning reactors with the ability to produce **a controllable, continuous, dynamic rotational flexible Magnetic field strength**, within the cores of such reactors, it is now easy to construct and produced new strong and powerful generators that do not need to burn any fuel (Fig. 59), to create rotating Magnetic fields, but, just by using Grapos nuclear reactor one can achieve the same and even more power than the present matter-based frictional systems. Even it becomes possible to produce varying frequencies of current output of the system from the same generator.

Grapos generators can produce power from kilowatts to megawatts in seconds, by just increasing the strength of the Magravs for the **Dypmfs** of the reactor or by increasing the **Vomafs** coverage of the Magravs. We have called this new generation of power generators the ***Keshe reactor generators*** (Fig. 60).


Nuclear Waste
Short Term
~~Nuclear Waste~~
~~Long Term~~
NUCLEAR
~~COAL~~
~~OIL~~
~~GAS~~
~~HYDRO POWER~~
~~CO$_2$~~
~~STEAM~~
~~TURBINE~~
COILS
ROTOR
SOLID
MAGNETS
~~TRADITIONAL GENERATOR~~
BECOMES A
SELF-ROTATIONING
MAGNET
NEW TYPE OF ELECTRICITY PRODUCTION

Fig. 59: New approach to generate electricity

The use of plasma dilution Magravs positioning reactor brings to an end the need for burning of fuel (Fig. 59), to create rotational motion of the rotors' for production of electricity as it happens in the present generators.

Our new approach puts an end to the production of greenhouse gasses (like CO_2) through the burning of fuels (coal, oil, gas) and finally an end to the habitual burning of matters to generate motion and energy. This also bringing to an end the current production of dangerous nuclear waste by running the present nuclear power stations.

By purely using the effects of interaction of the Magravs of the Matters, within the cores of these reactors, motion and Magnetic fields, for production of any amount of electric power can be achieved in one all-integrated nuclear-based unit without creating any waste of any sorts.

In a way this is how all plasmas, atoms, planetary systems, stars and galaxies create their own motion and Magnetic fields (Fig. 60 and Fig. 61). Why not for the man to take advantage of this new knowledge of clean source of supply of Matters for new energy production technology through the real universal method of workings of magnetic fields of Matters?


COILS
MF2
MF1
MF1: magnetic fields created by solid magnets
MF2: magnetic fields created by the materials inside the dynamic cores
KESHE GENERATOR

Fig. 60: The Keshe generator, which rotates for years in a coil structure.


COILS
MF2
MF1
EARTH GENERATOR

Fig. 61: The virtual Earth generator, which rotates and generates Magnetic fields (MF1 and MF2) for millions years, and could generate electricity if there was a copper coil around it.

Similarly, using the plasmatic magnetic fields reactors can **eliminate** the need for generators and **transmission lines**, due to the fact that the pmtics needed for production of a given current and voltage level can be created at the point-of-contact of the system. Even the structure of the matters electrons or plasmas can be used to create current for their use in the same equipment. This means that one can produce current from the atoms and plasmas of a silicon or plastic cover of a microchip, to meet the components energy needs.

One possible use for a small reactor is to produce the right plasmatic vibration of electrons or the plasma of matter, within any given environment to generate light and power.

Prototype reactors have already been made and can be further refined that only need to generate plasmatic magnetic fields within their cores, that the interaction of the pmtics generated by these reactors with its surrounding matters, creates a *magnetosphere* at the point of the interface of the two pmtics of the system and atmosphere, that leads to the release of pmtics in the range of visible light of any colour and ray. This will be how future light producing units will be manufactured.

Similarly, in a given environment, in such as a craft, the operation of reactors can produce Magravs, that the interior of such crafts would always be lit due to the principle of the interaction of the surrounding Vomafs of the reactor and the dynamic plasmatic magnetic fields of the particle content of the air within the confines of these crafts.

The strength of these Dypmfs generated by the reactors can be set to produce any colour rays of any magnetic wavelength, be this red or orange light, and X-rays or gamma rays. We have seen this effect in laboratory tests and have measured the radiation fields.

The power generating units of the future, using the plasmatic magnetic dilution technology, will be a departure from the present power and light production technology.

Grapos, due to their ability can create rays at any frequency, can be used for example for disinfection of any give environment and materials, by the production of Ultra Violet lights for matter and Extreme Ultra Violet for Matter in space.

The same principle, for generating matching plasmatic magnetic fields for the production of proteins in these reactors have been tested and proven to be correct. These tests were carried out in 2008 and the production of proteins by the use of nitrogen from air through this technology was proven to be simple and achievable.

In separate tests conditions, the hydrogen atoms of water were used to transfer the right plasmatic magnetic fields to the right pmtics strength of plants and human cells for the pmtics of the cell to gain nourishment or recover to their original level of plasmatic magnetic fields' strength.

This technology has been used in trial cases for helping volunteers with different vitamin deficiencies, or cell plasmatic deficiencies, to recover from the disorders produced by the deficiency, and people to live a normal life after years of suffering.

Alternatively, this technology can be used for production of new materials for coating or new processes of coating.

At the same time, through simple magnetic plasmatic reactors, the lattice structure of matter can be changed so that the nano-components of the matter can be realigned to change their lattice formation to another. The change of characteristics and properties of one element to another has been tested and confirmed to be correct by independent organisations. In these tests, the nano-matter of an element was captured and then its lattice formation, through the right plasmatic magnetic fields conditions, was changed to attain new properties from the same matter. This was carried out through several tests, at room temperature and pressure, where ***atomic carbon*** was initially released from a C-H bound matter. The carbon was then allowed to deposit itself on a layer of copper. This deposition was dependant on the presentation of the right plasmatic magnetic fields at different points on the same copper Matter. This copper surface was then tested and proven to have sections of nanolayer coating in the form of sp2, and on the same layers and same condition the lattice structure changes the same material to a diamond lattice structure, or what is known as sp3. Where, sp2 is a two-dimensional nanolayer, and sp3 is a three-dimensional diamond-lattice nanostructure.

The plasmatic magnetic fields' of reactors can be tuned to similar frequencies' as the plants pmtics, to generate certain vitamins and minerals. These single or multi-plasmatic magnetic fields producing reactor sources can and will replace the fertiliser industries of today's technologies in space for food production, once scientists grasp the method of their use.

In tests, seeds of herbs were grown by being feed using water treated in these reactors, the parallel seeds, which were grown normally with rainwater, died in early October. The herbs that were watered from reactor system were still green till March of the following year, because the molecules of the water were structured through the reactor system to act as fertilisers. Similar tests are in progress.

In this section, it has been shown and explained some of what has been tested and achieved through this new understanding. Scientists and users of this new technology will find their own ways to expand and will add their own new knowledge to our disclosures.

Seed of thought

Where, in the present time the majority of the nations in the third world due to the lack of funds to purchase fuel even in having power stations, or being able to afford to build generators at the cost of tens of million of dollars, they cannot afforded to run these generators to provide power for their nationals. Secondly, there is not enough production capacity to build new power stations and power grids. Therefore local alternatives can be in the range of windmills and solar cells, but these will not solve the incredible lack of electricity in next decades.

Now, through the use of **Keshe generators reactors**, which can cost as little as a new car, these governments can provide electricity and clean water for their nationals.

Where, these governments do not need to pay for fuel as these reactors run on hydrogen extracted from their environment. These reactors can be placed at the ***point-of-demand*** in a village or in the cities without the need for transmission lines or for any expertise to operate these reactors. Where through the production of electricity, purification systems which are part of these reactors integral operations will allow fresh clean water supply to every child, woman and man on this planet. This new energy source and clean source of water, given opportunities to third world nations to rise above and from poverty and reliance upon foreign aids and charities organisations. Where these nations can produce food and warmth for their nation as the rest of developing world without the backbreaking debt to other nations.

According to a ***United Nations report*** (Energy Challenge for Achieving the Millennium Development Goals 2006), "*Currently****, at least 1.6 billion people do not have access to electricity*** *for lighting, refrigeration, mechanical power, telecommunications and other beneficial uses. ... Moreover under today's policies and investment trends in energy infrastructure*, **1.5 billion people will still lack access to electricity in 2030**". (42)

Of course this is not acceptable. It is clear that humanity is not capable to deliver fundamental care to all of its members, even not within next twenty years!

Man is not complete and healthy if parts of it human structure suffers from paint of self-inflicting disability, this is the same for the human race as whole. This race is not complete until all its members have and can exists and have the privilege to live the same standard of the development as the rest.

"The future is bright, the future is plasmatic magnetic fields based, through the production and control of plasmatic dilution technology reactors to bring peace and comfort to the human race."

CHAPTER 26

Matters Experimental results and observations

Tests for the proof of all the concepts have been carried out over some years. The direct results and observations made in some of these tests have already been mentioned in some other parts of this book and now will be brought under one chapter collectively and will be discussed in general.

The reason for writing this book is to disclose the theoretical new first principles of our technology; because most of our test results are so groundbreaking that they cannot be explained by actual knowledge. Actual science is partly based on a number of mainstream accepted assumptions about fundamental interactions and particles and matters, where these assumptions have become almost "laws", and do not consider the true occurrences of real events in the universal order of creation of particles, plasmas, matters, energy, gravity and motion as they take place in the universe.

Where, the major processes in the universe are based on fusion and fission of Matters and plasmas, and the transformations and conversions of matters from one form to another. In this book we explain how such conversions and transformations can be reached in plasma reactors, and by this insight we were able to attain such amazing results. Where some people don't feel comfortable with them, or a priori reject them because these new findings and their applications counter their school of thought and their financial gains.

For example, one of the major obstacles in the world of nuclear fusion has been to overcome the Coulomb barrier for fusing two plasmas, and this problem has not been solved for the past sixty years by all scientists in this industry, even though billions of US Dollars and more has been spent by different nations in laboratories and fusion reactors testing to overcome ***the weakest of the weakest of magnetic fields interactions*** in the world of creation, which this is a magnetic barrier, also known as the Coulomb barrier, where this barrier is exactly the Magravs of the plasma, and as now we know how it is created, we have found the solution not to fight and force to cross this magnetic magnetosphere barrier, but the solution is how to create an environment matching the magnetic fields strength of this magnetosphere of the plasma for it to open-up and unveil its real constituent Matters. As the environment of the whole reactor becomes in magnetic fields strength equal to the magnetic fields strength environment of the plasma. Therefore, through this method, there are no barriers to overcome, and fusion of matters of plasmas or the use of the Magravs of the Matters of the plasma becomes a child's play.

For the first time in the world of energy and motion, we offer through dilution reactor technology, at low costs, to open the plasma and dictate the strength and the resistance of this Coulomb barrier to realize the dream of fusion.

Similarly, to achieve lift and motion where, the present space agencies are only able to deliver a limited payload into space, and the burden and the costs of such launches of crafts and personnel, cannot be met by one nation easily. Where, Magravs Grapos reactors can lift much larger payloads at low costs, without limitation on passengers and no weightlessness conditions in space.

Radiation

During tests in 2008, radiation detectors in the surrounding environment of a test reactor detected high levels of magnetic fields radiation. These high-energy magnetic fields have been measured more than 1.5 meters away from the plasma reactors. Where, there were ***no neutron sources*** in the laboratory or in the building. Through known physics or theories, these radiations should have not been in the environment.

These strong radiation fields were tested and looked for and were not present in the laboratory at any other times with other different testing configurations with the same reactors, using the same radiation measuring detectors.

Such high levels of magnetic fields radiations could have only been due to the release of the magnetic fields that had been entrapped in the Matters of the plasmas, which the system was set to produce. These releases of components of the plasma were achieved during the specific pre-set configurations of loadings of reactors. These strong magnetic fields were released by the operation of multi-core plasmatic dilution environment reactors and at no other time they were detected in the laboratory.

Most of the reactors, mainly built and tested for lift and weight reductions, are made of different simple parts, which some part have materials like plastic rings, and PVC, thus these systems do not and could not have been operating at high temperatures.

In other tests in 2008, and in repeats of the same tests in January and February of 2009, the same results have been achieved, all of which have been recorded on video.

In these tests with the use of a less than *one **gram** of mixture of matters* in the similar multi-core dilution magnetic fields systems, fundamental plasma separations were created through the same method as before. These tests were done using five different reactors, each having a different set of internal configurations.

In all test settings of the reactors, different loadings of materials and different dynamics for the reactors were used.

Weight reduction, motion and lift

In all cases, when the dilution of the plasma and the subsequent untangling of its Matters in the reactors were achieved, then the effects of the disassociations of Matters were observed through the effects they created internally in the reactor and externally through lift and motion, and jamming of radio-frequencies and so on.

In the early original reactor tests, full lift was achieved so fast that the effects of free motion were noticed a while after it was clearly apparent and were in progress, through the replay of the video recorded sessions of the sessions of tests. Through video replay of the recordings of tests, the motion of the system freely on the floor of the laboratory could clearly be seen prior to physical observation of the lift of the reactor system. These reactors have no protrusions, are not equipped with propellers, or portholes, which could cause the lift of the reactor by air repositioning means.

In one configuration and loading of the system, control of the system was lost, so the reactor had to be caught by hand in mid-air, that it could be brought under control before it was damaged.

In one configuration, two reactors with different external bodies and two different internal settings were used next to each other. These systems were kept about thirty centimetres apart from each other. These reactors were entirely different in design and had different settings and loadings. In the two-system loadings that were adjacent to each other, the systems' interacting fields pushed one reactor away from the stronger Magnetic fields of the two systems. With the same systems and different configurations of loading one system was attracted by and was pulled by the stronger gravitational fields strength system, where physical force was used to keep the two systems away from colliding with each other.

"These systems have no portholes, and no physical means of interaction with the outside environment and no aerodynamic systems to cause them to propel up or move side-ways through the air, and they have been no solid magnets or electro-magnets for repositioning or for motion, for them to move the total collective weight of 15 kg of the two systems. There are no external systems and tracts used to help causing the lift or motion of the system in the laboratory. Thus the motion is ***not due to*** **propulsion** ***or*** **aerodynamic** ***design and movement***". This is the conclusion of independent expert appointed as observer for the validation of the results of the tests.

During other tests systems weighting several kilograms, their weight were reduced in a controlled manner at increments of one hundred grams and two hundred grams per setting of a reactor and these tests were all videoed and recorded. For reduction of weight in these increments, the systems needed less than one thousand^{ths} of a gram of a new material combination as Matmags, even in some tests no new material was introduced and by just adjusting some internal parameters of the reactors reductions were achieved.

With the use of such a small amount of physical mass of matters used, creation of such lift and the reduction of system weight seven kilograms, has been said to be impossible without any external energy or equipment.

Through the understanding of the principles of the plasma dilution methods of disassembling the plasma components to utilise its sub-components, systems were designed to achieve these effects in simple ways. With the interaction of the disassociated Matters components of plasmas in different parts of the system, then the scene was set for creation of profound effects such as a *reduction in weight* with respect to the Magravs forces of the planet.

The interaction of the strong Antimatters' of the plasmas components, which were released in the different cores of the ***plasma dilution reactors*** and the interaction of the fundamental magnetic fields of Antimatter upon each other, was observed during different tests. The interaction of pmtics of Antimatter leads to the creation of the strong Magravs in the vicinity of, and within, the reactor cores.

Through the control of plasmas and by being able to separate the components of Antimatters and utilising their constituent magnetic fields in reactor cores, this led to the creation of Magravs forces that initially led to a reduction in the weight of the whole system. In following on with this process there was a detachment of the system from the ground as the system found a new Magravs positioning in respect to the Earth's Magravs force strength.

When looking at the effects and results achieved, there is no doubt about the powers of the interaction of the magnetic fields of Matters, which were diluted and their fields were allowed to interact in these reactors' cores. These effects were attained by allowing a number of the pmtics of the Antimatters of the plasmas *to integrate* ***in one core***, and allowing these fields of Antimatters to interact with the same and similar fields *integrated* through the same principles in ***other parts*** *of the reactor*. Where, the interaction of the pmtics of the components' of Antimatters in different parts of the system with each other, led to the generation of strong specific plasmatic Magravs. The reactor facilitates for these stronger Magnetic fields to interact and generate strong plasmatic Magravs in the reactor cores, with allowing these Magravs created in the reactor cores to interact with the Magravs forces of the planet, and due to the strength of the fields produced in the reactor, this causes' reduction or increase in the weight of the system in respect to the planet's Magravs.

The new Magravs created within the system, pushing against the Magravs of the planet at the boundary of the systems fields, causes the variations in the weight according to the combination and configuration of the Grapos loading. The produced Magravs forces *within the confines of the system* are independent of the external planetary gravitational fields. In numerous tests, it was observed and recorded that the changes in the *internal* gravitational field forces of the system, did not necessarily change the weight of the system in respect to the Magravs of the planet. The interacting internal pmtics forces clearly showed to be generated independently by increase and decrease through internal electrical measuring components set in the system for the detection of these types of changes.

It has become clear that it is the interaction of the Magravs of the planet and the system that have brought about the reduction or increase in the weight and lift or descend of the system in respect to the planet. In some tests, these increases or decreases in the weight of the system have been without any addition or withdrawal of physical matters from the system.

In continuing with the same processes of creation of varying Magravs in the system, weight reduction was managed and followed to such an extent that the total balance of the interaction of Magravs of the system and the planet, in respect to each other, eventually zero reading on the measuring scale system. The point was reached where there was total physical detachment of the system from the table or floor first, and then the upward motion of the system, away from the surface was achieved.

Some call this the anti-gravity principle but in fact, this interaction and new balance in Magravs forces in between the system and planet, is due to both gravitational and Magnetic positioning of the reactor system in respect to the planet, as both objects are in possession of ***active*** *dynamic plasmatic Magravs forces*.

In a specific reactor, set for weight reduction, internal gravitational field reduction and zero-gravitational field force were disturbed, where the human touch was applied causing the change in the magnetic interface between the fields of the system and planet. This gave a tingling feeling on the tip of fingers after repeated tests.

In numerous tests over years, where the equilibrium state of internal Magravs strength between cores were achieved, the whole system, including internal physical dynamic parts, came to halt, sometimes for up to thirty minutes or more. Then, the dynamic motion of the systems re-set by itself and the system restarted. This ***re-setting*** has been due to losses and reduction of one Magnetic and/or gravitational field strength in respect to another within the cores of the reactor.

A number of times, *external power sources* were used to try to restart the system. In some cases measured energy of up to three, four and eight times the normal operational energy was continuously applied to the internal systems to try to push-start the system, but to no avail.

This shows that the power generated by a countable number of Matters of molecules, was so powerful that additional systems built in the reactor cores could not overcome the kinds of powers produced by so few Matters magnetic fields interactions.

These tests have shown the creation of independent Magravs in separate cores of the reactor. They show the creation of independent plasmatic Magravs within the system boundary, and then the combination of the same Magravs prevailing around the outside or beyond physical boundary of the reactor as magnetospheric or cosmic radiations were produced, which these types of fields are prevalent as have been observed in space around stars and planets.

Indications are that these radiations created in these system, due to their characteristics, do not shown any side effects in the human tissue of the operator up to this moment, years after having been involved with these fields tests.

These fields around the cores are considered to be due to the interaction of plasmatic magnetic fields' of Matters of plasma and environments' Matter or matter, and are independently created in different parts of the cores of the system.

This technology opens up new opportunities for the industrial development and manufacturing of systems that have different gravitational conditions inside the system for living, and have different gravitational conditions compared to the outside and around the physical boundary of the craft. This allows for having a one-G gravitational field force for the normal habitation of Man inside spacecrafts, or in a dome outside and around the crafts for habitation. While the conditions outside the craft can be zero G to tens of G's. The passengers of crafts using Grapos can walk around the craft, or in and around the dome created by the extension of Magravs of the systems, on any planet surface, as if they were in Earth's gravitational field force environment.

No high temperature core environments or sudden surges of heat were recorded in any tests. The reactors were in some cases opened immediately after operation for new settings, in a normal lab environment. There was no physical damage ever noticed to the internal parts of the system. This includes melting and twisting or destruction of any parts due to the presence of Matters.

Even though we lost a full system by pure enthusiasm to catch, lift upwards, which the jumping on the systems after several times cracked the structure and the systems was lost. We have kept the reactor casing for further analyses of matter lattice changes, and another reactor was damaged when a Black hole condition was replicated.

On only one occasion, where a specific setting was used, a black spot was noted on one of the external sides of the reactor core wall. This is supposedly was due to an energy surge during the test. The effect of the black burn was not removed for further analysis.

Production of matters

In different tests, a new orange and gold coloured material was noticed on two occasions in a reactor, and samples were collected for further testing to show the material production capability of the system.

This method of the production of Matter can be used by manipulating and changing the plasma's and rearranging them for the production of oxygen, hydrogen and water from collections of initial fundamental particles found in space, for human deep-space travel and colonisation. Where, the components of plasma absorbed from the cosmos are loosened by producing the right pmtics strength in the reactor for production of the first two atoms of hydrogen. Using further plasmas from space, in the matching gravitational fields as of the atoms of oxygen in the same reactor, this element can be produced. Then through the same reactor's operation, this allows the combination of the two elements, of hydrogen and oxygen, which was produced from the space plasma, this allowing the ***production of drinking water***.

In the future tests, one can attempt to combine the gravitational effects of the systems for production of energy, material production and other capabilities of the technology all simultaneously in ***one reactor***. We have achieved this much but there is a lot more to learn.

These reactors are truly an integrated system, which can produce and attain several effects and properties, like production of Magravs, creation of matters and so on simultaneously.

Dark Matter technology

The system using the Dark Matter in travelling through the Magravs of the planet creates no magnetospheric conditions, friction, or pmtics force resistance, between its pmtics Magravs and the planet pmtics Magravs. Thus, zones around a craft can be created that there is no magnetospheric field between the craft's magnetic interface and the planetary system's. Hence, a craft using the Dark Matter ***cascading*** can travel within a stronger pmtics, like that of the Earth, *without detection* since the system can create no interface magnetosphere, as there would be no visible light to be seen with this method of motion.

Through this method of using the Dark Matter for transportation, high-speed motions can be attained for spacecraft in planetary systems, solar systems and galaxies.

Using the ***Dark Matter principle for transportation***, the environment between the systems and the planet is **saturated** with the dynamic plasmatic magnetic fields of the system and the planet. This zone appears to possess energies but they cannot be linked to any source. Even though the source of the dynamic pmtics, in motion around the system or so-called energies of the pmtics, is set in the centre of a strong plasmatic Magravs systems inside the crafts and centre of the planet. Such Dark energy fields give the appearance and confirm the existence of dynamic energies, which have no explicit source of origin. Where, the source of energy or the dynamic pmtics is the hidden gravitational source in the centre of the Matters reactors and the planet.

This new technology is a radical breakaway from the hold that physical matter have had on the destiny of Man on the Earth.

With this new understanding of the methods of how Matters are created in the universe, it is possible for Man to use the real Matter sources for energies and powers available to him in the universe for his future scientific evolution.

CHAPTER 27

Discussions and Conclusions

With this new understanding, the elementary particles have become to be the 'magnetic fields' and their interaction leading to the creation of Magravs, this leading to the creation of Matters, as the state of each Matter depending upon the strength of the magnetic fields which have led to its creation in respect to their environment fields strength, which the Matter appears as the Matter, the Dark Matter or the Antimatter, where the collective interaction of the Matters Magravs, leads to the creation of the Initial fundamental Plasma (the Neutron), where the environmental magnetic fields forces conditions, around the Plasma, dictates the physical appearance states of the Matter part of the plasma as matter, this being solid, liquid or gas.

It is obvious that the universe will never stop creating new Matters and matters and their effects, and their interactions, as the universe is a soup of dynamic and ever-changing conditions, created by the Magravs positioning of plasmas, dynamic Matters, matters and their components and effects.

Man can learn how to create the same conditions as the universal order, and to rearrange these fundamental particles for his use, in a much simpler way than he has chosen up to this point in his path of technological and scientific evolution by the use of matter(s).

In the present state-of-art technologies for the production of energy, scientists have chosen the path of force and *destruction of atoms and molecules* to overcome barriers. In the universal order of creation, one works within the magnetic fields forces to achieve the same and even better results.

This ethos of ***burning and destruction*** has been the fundamental focal point for Man's survival in his environment, due to what he has been conditioned to in his evolutional path on Earth. He has seen the power of fire, from fires in forests, and he has used this knowledge to keep himself warm and so he has learned to do the same using the same methods and materials. By perfecting this art, through the burning of wood and oil and so on, he has managed to create energies for cooking and warmth and running industries.

Then he saw the birds and understood the concept of motion in air and so he used the concept of fire to create propulsion and jet engines, still burning one form of fuel or another to achieve flight, still based on the principle of ***matters repositioning and conversion***.

He has seen death through disease, so he has produced other elements to destroy the germs that can cause and bring an end to his uncertain and fragile physical life.

If man would learn to work within the structure of **the universal order of creation of**

Matters and the method and principle of their use, he will learn that he does not need to burn or destroy anything to keep himself warm or feed himself, or even to overcome diseases.

He can very simply change the characteristics of the plasmatic magnetic fields of the elements that caused the misbalance in the first place, leading to his ailment, without swallowing a single tablet in his lifetime.

We have developed and tested such simple systems in the past years and have seen their amazing results.

For example people suffering from Fibromyalgia for thirty years or more, within 3 months of drinking water through these systems, have started living a normal life without any signs of their disease. Follow-up over 18 months has shown a total eradication of the ailment.

We have tested this technology on other forms of illnesses and viruses and the results are amazing. However, this is what is to be expected with the use of the true knowledge of the creation as has been disclosed in this and future books.

With this new disclosure, man in the future will learn to live and operate in the real universal order of creation of Matters and their existence in the universe for his life. He will never destroy any Matter or matter, but he will learn to work within their structure. He will learn to achieve more, with less use of the resources in his environment. This is an improvement on the past, whereby at the present by the use of destructive methods, he has brought himself to the point that the abuse of the matters is now endangering his future on his own home planet.

Man has to learn to work with the real elementary particles and elements and their functions in the universe, such as magnetic fields and their interactions, for him to be able to produce what he needs irrespective of where in space he might be or would want to be.

Maybe this knowledge and the proof of its pleasures will change the ingrained ethos of destruction for the survival for man. One could even hope for a change in his animal instinct of killing other people and other creatures of god to survive.

Additionally he can change his habits and the instinct to want more since through the understanding of this technology he can have whatever he desires from his materialistic world.

In this disclosure, some theoretical nature of the universe has been spoken about, but the real physical aspects can be created to achieve the same conditions as in the universe as we have shown through our tests.

Man will be able to carry on with his life, but at the same time will be able to live in a balanced environment.

The reactors we have developed, which in real terms are ***miniature universes***, that can provide man with all his needs, such as water, food and medicine for him to survive and enjoy the beauties of creation.

The conditions in these reactors are soft and gentle environments and the methods of their use for control and creation of mans' needs are based on working within the universal structure, and not destroying to achieve, as has been the principle of the past for the Man.

For example, when the principles of the creation of Magravs are applied to the lower orders of creation, like the interlocking of atoms to make molecules, there are explanations as to why certain types of Matters are attracted to the reactor, and why certain molecules are, or can be, produced in certain ways and combinations, in certain parts of the universe.

The same applies in the even lower orders of creation, that one can explain and produce certain magnetic fields and their interactions that can lead to the creation of present fundamental elements in the centre of the proton, plasma, an atom and finally the man himself.

The world of science has to understand the conditions by which the interactions of initial magnetic fields can lead to the creation of an initial state, for the creation of the Matter, matter, plasma and finally atom.

Then there is a need to understand and demonstrate as is done in this book the way Matters and matters are created in vast spans of the galaxies.

Scientists have studied over centuries the structure of matters and the atom, and their interactions, in their material and tangible *states of matter*. However, the structure and method by which the atom is created, maintains and guaranties it's existence has not been fundamentally fully understood, due to the lack of overall overview of workings of the universal order of Matters. Even the construction of protons with its sub-components (quarks, gluons), up to today, is based on assumptions and indications by the use of particle accelerators and plasma reactors, by *only looking at* ***matter*** *components* of the proton and some Antimatter parts. So the present scientific world looks for an answer in the construction of the proton on the ***matter-to-matter*** level.

By the present science, the existence of the Matter, the Antimatter and the Dark Matter are largely considered to be independent entities in different points in space, and have never been considered to be as ***one collective*** *and all being* ***integrated parts of one system*** making up the plasma, up to this disclosure.

Mass of the Matters and Mass of the plasma

In the new knowledge we consider the three different quarks of a proton, ***as the three different Matters*** (Matter, Antimatter and Dark Matter) ***of the plasma***.

Where each Matter is *created* through the interaction of at least two different magnetic fields or pmtics, where through the interaction of these two plasmatic magnetic fields of different strength, initial gravitational and Magnetic field for creation of different Matters of the fundamental plasma are set to start.

So that the interaction of *at least two pmtics of* ***each*** *Matter* creates it's own Magravs forces. What we call the interaction of the Magravs strength forces between and in respect to each other of these three different Matters of the proton.

Where, through the understanding of the method of creation of different Matters of the plasma, due to interaction of at least two magnetic fields and the creation of gravitational and Magnetic fields, this confirms that ***each Matter*** irrespective of its environment Magravs *possesses an independent* ***mass*** *of its own*. In the present science this is called the mass of the quark. In fact each Matter, Dark Matter, Antimatter and Matter, has its own individual mass in the plasma. As each Matter is created by the interaction of at least two different magnetic fields strength, the ***total mass of the plasma*** is the mass of the three Matters plus the total interaction of Magravs interaction of the overall plasmatic magnetic fields within the plasma. Consequently the *total mass of the plasma* is always considered to be ***larger*** than the *total mass of its three Matters'* components.

Due to the dynamism of the interaction of the two initial pmtics, leading to the progressive creation of the Magravs of each Matter, *each Matter* is always in a ***dynamic rotational state*** within the plasma. Where the **speeds'** of the dynamic rotation of the different Matters in the plasma are not the same and they are independent from each other, since their speed of rotation is set by the strength of their initial magnetic fields interactions. Where in the present science the observation of this natural phenomenon of rotation is called the ***spin of each quark***. One can compare this, in cosmological sense, as the ***independent*** *speed of rotation* of the Sun and Earth, in spite of that they are within the same solar system. Where the initial plasmatic magnetic fields strength, which leads to the creation of different Matter(s) in it's interaction with it's environment pmtics strength, leads to the creation of an individual magnetosphere of a specific field strength for each of the Matters. Where the intensity of each magnetosphere creates *different light intensity* in its environment.

Now we understand that the interaction between the pmtics of the magnetosphere of each Matter of the initial fundamental plasma leads to the release of different pmtics strength fragments in the range of visible light (Fig. 18).

Due to the interaction of the plasma of each of the three Matters with each other and the release of light or energy, these interactions in parts reduces their strength and the pmtics content of each Matter, where due to these reductions in Matters quantity and strength of pmtics, different colours are attained by these interactions for each Matter during the cycle of the life of each Matter.

It has become clear that all states of Matters are the same in their nature of their creation with only differences in their field strength. What does differentiate these Matters from one another is in principle the strength of their fields and their position(s) and interaction(s) with other pmtics in their environment and in respect to each other.

Thus, Matters are Antimatters and Dark Matters depending on the point-of-observation and the field strength of the environment of the appearance at a given point and position, but they are all made of the same entity at source, which is the magnetic field.

The front-cover image of this book has been chosen specifically to emphasise for the scientific world to reconsider their assumptions.

The Matter can change to, or appears as the Antimatter and the Dark Matter and vice-versa, if the right conditions and the right plasmatic magnetic fields forces are given or taken away from the pmtics of the Matter.

In this disclosure, we have explained in a simple way that magnetic fields are the *new* initial fundamental particles, and the **magnetic fields** are the new elementary particles ***instead*** of what has been assumed at present as *quarks*. So, the magnetic fields and their interactions are the **creators** of these quarks and so on, in the plasmas.

Then we have explained how the Matter, the Antimatter and the Dark Matter, and the relevant energies of the Matter, the Antimatter and the Dark Matter, are all decided, dictated and created at the inception of the creation of the first stages of the creation of the initial fundamental plasmas of these Matters.

In this disclosure, we have discussed the results and shown how the three states of the Matter, the Antimatter and the Dark Matter are created, but through ***real tests conditions***, we have confirmed the co-existence of these three Matters and their respective energies.

For example, in tests there have been the very strong magnetic wavelengths of cosmic gamma-like radiations levels, which have been detected ***for meters*** around the system, *where there has been* ***no physical source*** *of such radioactive materials ever being present*. Whereas, it is a known fact that alpha and beta rays cannot travel that far in room condition environment. These levels of radiations could only be created through the interaction and the creation of strong magnetic fields in the reactors cores, which in their interaction with the pmtics of matters in the room environment have led to the release of these gamma-like radiations. This is exactly by the same principle as the Magravs generated in the centre of the stars in their interaction with the plasmas of matters on their surface, generate lights and high-level cosmic radiations.

An **atom** is considered to be "a collection of different densities and strengths of magnetic fields interacting with each other, in different magnetic mixtures and levels, in, and under, the same physical rules of the existence as the rest of the Matters, matters and bodies in the universe". The atom is nothing more than a collection of the lower order energy magnetic fields strength in motion in the universe, that always come together in the same specific pattern of dynamic pmtics and strength.

The question is, that, is it the collections of magnetism, which created the MATTERS' of the plasma, or did the existence of the MATTERS of plasma create the magnetism?

At this point, the existence and understanding of the Dark Matter becomes important, since the human eye and the physical machines of today can only observe what is in possession of visible and detectable energy fields.

The **Dark Matter** is created by interaction of magnetic fields which create and are in possession of intense fields of gravity and magnetism, and at the same time, and it is void of visible light in respect to their given environment magnetic fields strength. On the other hand, the existence of the Dark Matter is position dependent and pmtics strength balance dependent, in respect to its environments pmtics' strength.

Through the operation of hundreds of static and dynamic tests we have very strong indications that the universe is indeed made in the normal conditions and of packages of dynamic pmtics.

From our observations, we can say with a large degree of certainty, that the dynamism of the whole universe is constantly maintained through the principle of the interaction and attraction of different pmtics, according to their strength and positioning in respect to their neighbouring rays, fields and plasmas. Where magnetic fields of different strengths are locked to each other by the principle of their ***Plasmatic Magnetic Energy*** (PME) and ***polarity***. These causing the first stage of the creation of the magnetic attraction or what is called the ***Magravs force*** for the creation of the first Matters and plasma and further on of the first atoms, molecules, matter, stars and galaxies.

Through the above disclosures, it is clear that these components of plasma themselves have no solid parts, but are merely *a collection of energy and fields, trapped or interlocked in different magnetic fields strength of the other parts*, according to their strength where, they can appear as the smaller components of these parts or near to visible as the physical state of matter.

These dynamic pmtics or energies on their own in the universe are not that influential, but as they *gather with other collections* of dynamic pmtics or energies of the same levels, they appear as part of Matter, the energy constituents of an electron or the Matter parts of matters, that they show and exert their influence.

When the pmtics binding principles are fully understood, the world of creation and the understandings of the origin and working of the universe will become much easier to work with.
Why, only a part of the pmtics levels is visible to Man is not a mystery, but the reality is that Man has the habit of only looking at things in physical terms. If Man looks for the real existence of the effects of the energy levels, he will open his eyes to a new horizon in the world of creation.

The question is if one can develop the ***pmtics*** as in the universe and manage to release part of these plasmatic magnetic fields from initial plasma as energy, then, one can manage to control the level of these pmtics and their interactions that are needed to create and replicate energy combinations that can lead to the creation of the Matter and then matters. This in time will be done and depending upon the openness of Man to accept the realities of his owns creation and his existence in the midst of others.

In developing reactors, which have been openly disclosed, and in understanding their modes of operation, which are discussed, these reactors will not only be used as future sources of energy for Mans energy needs, further, these reactors will become the incubator for the creation of the energy levels, which can lead to the creation of the pmtics, which will lead to the creation of Matter and matters, like oxygen, food, water and so on.

Through the use of the plasma dilution and gravitational reactors systems of the future, one can and will experience the Black Hole concept and the reversibility of the polarity of planets (12), as we have done in our lab tests and become aware of their pleasure and dangers.

In these plasma dilution technology reactors it is not only the fusion of Matters that is possible, but also the fusion of Antimatters and Dark Matters and their real application in the production of Antimatter and Dark Matters atoms and molecules that will become part of daily use. Where, these will be used for the production of energies and effects, which are above the levels of the Matter components strength.

The beauty of the application of these universal reactors will be the opportunity for the creation and manipulation of the much weaker and smaller energy levels that can lead to the creation of electrons and protons.

These weaker strength magnetic fields for the creation of Matters will be noticed and can be collected at the *outer boundary of the plasma*, but not on the edge of the plasma in the reactor. This is due to the fact that the edges of these reactors are dynamic and are violent areas in which temperature interfaces will not be so suitable, but can allow creating the conditions for weak energy levels to be maintained and to manifest themselves. These zones are good to create the conditions for the creation of electrons' plasma, where loose plasma conditions are needed for fine-tuning of the fields in these reactors. This is due to the fact that electrons, in their foundation, are made of low energy levels bindings and interacting with each other, largely in a dynamic volume as compared to the protons, and in possession of weaker binding energy than protons.

To create conditions for the production of the protons, there is a need for the same energy levels, but tighter and stronger magnetic fields plasma conditions are essential and the size of the plasma and the mixture of energies available in both conditions are important.

The techniques for the use of the ambient temperature reactors to perform fusion or the production of new and heavier atoms can be learnt through the development of initial fundamental plasma dilution technology, which is very much different from the mode of operation of the present fission or fusion reactor technologies.

In the present nuclear fusion industry, the most important point in the world of creation, the *presence of controllable gravitational field forces*, has been absent and totally ignored by scientists.

In **dilution plasma technology**, as in the universe, **gravitational field forces** within the systems are the ***cornerstones*** of the operation of the reactor.

This is a unique method of the creation of new Matter and the creation of energy, which has been explained in the operation of dilution plasma technology. This is exactly how Matters are created in the universe.

In the right conditions and mixture of initial fundamental particles, the use of plasma dilution technology will lead to the transformation of the *initial fundamental plasma* into protons' and electrons' to create the basic matter and simple atoms like ***hydrogen***. With the right method of application of the plasma dilution technology, hydrogen atoms can be used for the production of the heavier elements.

It is important to note that, in an atom, "The interaction between the two pmtics of neutrons and protons Magravs are in fact the source of the **double magnetic fields** of the atom and consequently the creation of the Magravs of the whole atom.

Even though **neutrons** are supposed to be ***balanced*** *pmtics entities*, the magnetic energy of the nucleus can be ***increased*** up to a limit *without the disintegration* of the inner gravitational forces of its constituent parts for its components Matters field strength to attain the plasmatic magnetic energy of a higher strength or new pmtics element.

In his progressive evolution, Man has learnt to use what has been available to him, like wood to create fire, steam to create power, the use of oil for engines to create motion, and in the recent past the breaking of the atom and joining of plasma in nuclear reactors for energy.

Through the understanding of the creation of the initial fundamental plasma, the energies of not only the Matter parts of the plasma are used, but this technology allows the utilisation of all Matters of the plasma, that is the Matter, the Antimatter and the Dark Matter and their energies that these possess and can produce, that come into play and can be used.

In the other words, we welcome the Man to ***the real world of creation***.

CHAPTER 28

Insight into the Future

Using the new acquired knowledge from above chapters, one can look into the future and say that the struggles of the past will bring beautiful fruits of creation for the future of the man.

From understanding of the operation and relation between magnetic fields within any structure, this being an atom, molecules, and even a star, different types of life in all corners of the universe can exist in all forms, and through other matters then the nitrogen based protein chain of the human race, which other lives through their different pmtics can operate through the same principles as the human protein chain. These creatures through the balance of their pmtics criterion do and can exist in the spans of universe. In fact, their protein chains with different matters than nitrogen could be more efficient in its use of passive pmtics than the humans' protein chain in using pmtics from the soup of the universe.

These Beings might have different colour of liquid distribution medium than Mans' red blood, but not necessarily this mean that they are any different from the Man in essence.

For example, if the liquid of life for these creatures of god have the potassium as the base element instead of nitrogen or mixture of the potassium and the nitrogen, then this liquid can function as good as, and even better than nitrogen-based protein of the human blood for converting and the use of Matters and matters in the universal soup of supplies. Even these Beings' protein-based cell can be more efficient for the conversion and the use of the passive pmtics of the Matters of universe. This efficiency can mean more and different comprehension, intelligence, and brain structure, etc.

Thus difference in these creatures and the Man will, and could be only the colour of their medium liquid system in their bodies.

The Potassium, in combination with pmtics of matters like the hydrogen and the oxygen mixture, in vacuum condition of systems in the Earth atmosphere, creates a silver greenish pmtics magnetospheric interface colour. Which, to mans' protein mixture, in the light absorption spectrum, these creatures with potassium-base proteins can be different in colour. Thus the liquid of life of these creatures in its interaction with Earth's atmosphere pmtics will create blood of different colour than the human red blood. Even in their external appearance they might be, or having to be reflecting the colour of their blood (9).

In reality as different planets have acquired different matters due to their Matters Magravs strength as their base materials, at their inception in their galaxies, rather than nitrogen or potassium as the base for what is called their protein for cell production to sustain life in their medium, in mans' journeys into deep space to these planets and zones, he will come across different intelligence, colour, sizes, transparency and shapes creatures.

Man has to understand that the level of intelligence, colours of skin or blood and shapes of these beings in the universe, can and is, intriguing as is in his home base with his red blood of the Earth to them.

What is important is that these creatures, with their pmtics balance protein chain could have a different viruses tolerance passive magnetic fields levels than to the Man in the Earth atmosphere pmtics condition too.

From this point on in the journey of the Man in the universe, the prejudices of colour of skin, and the nationhood will have no meaning. From this point on the colour of the blood is only the means of indication of the origin of point of life reference and nothing more and nothing less.

In the short-term for the future one can envisage:

The implications and applications of the transition of Matters will be the key to the survival of Man in the hostile environments of the universe. If this technology is understood fully, Man will be able to conquer the control of most of the forces within the universe and use them to his advantage. The use of the *transition states of Matters* are such a powerful tools for science for the future, that if their applications are harvested in full, most of diseases of the present and future can be eradicated. Through the appropriate use of this knowledge, Man can use the pmtics strength to free himself from most ailments, by producing the right pmtics strength equal to his protein level configuration, to ***reset** the cells in his body* to their right and original pmtics strength of operation without swallowing a single tablet.

For example, Man can produce ***enough food*** from the initial plasmas of the universe, without the need for soil, by simply converting the initial plasma to the atoms and molecules of the proteins and vitamins that he requires, at the point-of-demand, anywhere in the universe. As the food, itself is made of and is from the conversion of different dynamic pmtics strength. Where, the planets and animals do the conversion for man, for them by absorbing the pmtics strength of the Sun, and converting these different pmtics strength to vitamins and proteins for mans consumption for his survival. Where plasma dilution reactors can do the ***direct conversion*** of what animals and plants do for production of pmtics strength in levels that can be used by humans, and have the same effect and gives the same pmtics amount and strength needed by the different cells in the human body.

At the same time by the use of plasma dilution reactors, there will be no need to carry all of Man's physical needs with him into space, like oxygen, water, food or matters for his colonisation of planets, and space. Man will be able to convert *Matters-to-matters* through the fusion technology using plasma dilution reactors in space as he travels, and produce what he needs at any given point in space (Fig. 56).

Man can produce ***any** material* from the initial plasmas absorbed from the environment of space, he can produce any Matter or matters at the point-of-demand, this being an atom of hydrogen, oxygen, water, protein molecules, leafs' of gold or sheets of steel. The crafts of the future will not need to carry any raw basic materials for the production of parts into space. Man can produce materials for the construction of permanent habitation zones at any point in space and any planetary environment, through the use of dilution plasma and Grapos reactors.

Systems can be developed, which even in possession of the Dark Matter gravitational field forces, the same system can produce balanced pmtics strength in respect to its environment, for the system to appear as the source of Dark energy.

Systems can be developed, which have the ability to produce internal Magravs forces that can be tolerated by the human body. However, at the same time, the same system is being able to generate a balanced external pmtics strength in respect to its surrounding environment, these pmtics created by the system can be matching to the environment so that they do not have to interact with other systems pmtics forces (like those of the planetary systems' magnetic fields forces), so the pmtics around this region of the craft can have the appearance of systems that can produce Dark Matters and Dark energy.

However in one instance, by creating the balanced pmtics in respect to its environment, the systems that have been physically visible in one position in the given space, without a change of position, suddenly become dark or translucent in respect to their environment. In these systems and condition of operation the interaction between the balanced pmtics strength of the system and the fields of the planetary system can be brought to be matching without the system ever moving, this giving the impression that the system has moved to another position.

New systems can be developed that can produce ***instantly*** as much *energy-on-demand*, at temperature and pressure independent conditions, anywhere in the universe.

In possession of this new knowledge and Technology: ***Man can free himself from the shackles of the Earths gravitational field forces.***

Through the understanding of the ***methods of creation and control of pmtics***, Man can produce its own controlled *protection Magravs* magnetospheric conditions within and around the crafts, with the use of the plasma dilution Magravs positioning reactors, these magnetospheric field forces strength will be similar to the Earth Magnetic field strength (Fig. 62) or similar to the magnetosphere of an electron around its proton (Fig. 63). Where, the Matmags of transport for the crafts of the future can be gathered from the plasmatic magnetic environment of the universe.

The Magravs positioning systems (Grapos) can be used as much in a plasma, on Earth, in Space as they can be used in deep liquid environments, and galaxies, irrespective of the pressures and temperature around the craft.


"GRAPOS"
GRAVITATIONAL
POSITIONING
REACTOR
MAGNETOSPHERE
OF THE CRAFT
CRAFT
MAGNETIC FIELDS
INTERFACE
LIGHT EFFECT
Earth
Atmosphere
G1
G2
G3
INNER CORES
EARTH

Fig. 62: The plasma dilution Magravs positioning reactors used in a craft due to the interaction of their plasmatic magnetic fields can lead to the creation of shining silver light in the atmosphere of the Earth.


A1
B1
G1
C1
A3
F1
C2
A2
B2
G2
C3
B3
G3

Fig. 63: Initial fusion process for the production of matters and creation of bright magnetosphere of the electron as it approaches' and is amalgamated into the plasma of the proton of the atom.

Our hope, is that this technology cannot and will not be allowed to be utilised for destruction, killing and damage to any environment or against any of God's created

Matters and creatures, whether in possession of intelligence or not.

God help Man with this knowledge so that Man will find peace within himself and others.

As Mans weakness, his greed and his hunger for power and control, soon he will come to be thought the lesson that there is no forgiveness for the ones' whom misuse this knowledge and the technology for harming others.

By understanding in totality this new knowledge and what it can bring, maybe now Man will understand the meaning of that there are balances in the overall construction of his initial fundamental materials and that their lives always have to be within their limitations, of these balances.

Mans' fundamental construction of his initial state magnetic field structure, is always the same in force and energy and specific in its initial components, as the initial fundamental components of Matters, or matters of the universe ***cannot take more than what they need*** to be constructed of the pmtics of the universe and balance enough to share their inner constituents pmtics to pass on what is needed by others' configurations for them to exist, even if this giving can mean and can bring about their own demise.

Thus every creation, in its essence, has the attributes of its creator. Therefore, with this new knowledge and the reality of its existence, maybe Man can strive to understand the truth about himself and purpose of his creation in the universe.


MATTER
weak pmtics
ANTIMATTER
strong pmtics
F1
DARK MATTER
balanced G + M pmtics
in respect to the environment pmtics

Fig. 64: The fundamental insight.

In general, I can say,

“God has been the creator of All,

and Man the converter of some”.

References

1: **The inner-inner core of Earth**
Don L. Anderson*
Seismological Laboratory, California Institute of Technology, Pasadena, CA 91125
http://www.pnas.org/content/99/22/13966.full.pdf

2: Researchers confirm discovery of Earth's inner, innermost core
Public release date: 10-Mar-2008
James E. Kloeppel
kloeppel@uiuc.edu
University of Illinois at Urbana-Champaign
The work was funded by the National Science Foundation

3: The innermost inner core of the Earth: Evidence for a change in anisotropic behavior at the radius of about 300 km
Miaki Ishii* and
Adam M. Dziewo□ski *Department of Earth and Planetary Sciences, Harvard University, 20 Oxford Street, Cambridge, MA 02138*
The National Academy of Sciences

4: The inner inner core of Earth
D. L. Anderson
Proc. Natl. Acad. Sci. USA 2002 99:13966-13968

5: Robust Normal Mode Constraints on Inner-Core Anisotropy from Model Space
C. Beghein and J. Trampert
Search*Science 2003 299:552-555*

6: Fermilab
http://www.fnal.gov/

7: Fermilab Finds Antimatter Clues in Quick-Change Particle
http://www.particlephysics.ac.uk/news/news-archive/2006/new-clues-in-Antimatter-mystery.html

8: Fermilab probes Matter- Antimatter transitions
http://physicsworld.com/cws/article/news/24639

9: The universal order of creation. (Written 5.7.2006)

10: **Cosmic Rays** (Release date 24.3.2004)

11: **The Airborne reactor** (Release date 25.3.2004)

12: The seed of the Earth (Release date 25.3.2004)

13: **The creation of Black Hole** (Release date 25.3.2004)

14: **Magnetosphere** (Release date 9.6.2004)

15: Correction to the Einstein equation of Relativity (Release date 15.6.2004)

16: Introduction to the new system (Release date 2.7.2004)

17: The rings of Saturn (Release date 2.7.2004)

18: The creation of gravity (Release date 11.7.2004)

19: Death of a star (Release date 26.7.2004)

20: Fusion (Release date 28.7.2004)

21: Life of a Cell (Release date 28.11.2004)

22:The Atom (Release date 19.12.2004)

23: Magnetism (Release date 8.1.2005)

24: The creation of the magneto-gravitational force (Release date 5.2.2005)

25: The core of the Earth (Release date 20.4.2005)

26: The electron-atomic welding (Release date 3.5.2005)

27: Shutdown and safety of the reactor core (Release date 6.6.2005)

28: Reactor Start-up (Release date 9.6.2005)

29: The energy balance of the reactor (Release date 29.6.2005)

30: Nuclear decay or half-life (Release date 20.7.2005)

31: The decontamination system (Release date 10.10.2005)

**32: The difference in atomic and molecular structure
under gravitational force and pressurised conditions.** (Release date 15.8.2005)

33: The Defence and shielding system (Release date 4.9.2005)

34: Method of creation of an atom or nano Matter (Release date 11.10.2005)

35: The relationship between Gravity and Mass (Release date 21.1.2006)

36: The Dark Matter The Fifth state of Matter (Release date 21.1.2006)

37: The inter-atomic fusion (Release date 3. 5. 2006)

38: The conductivity of the Matter in the vacuum of the interplanetary mediums
(Release date 21.1.2006)

39: The production of Graphene (Release date 25.7.2006)

40: **Mini-magnetospheric plasma propulsion (M2P2)**
(http://en.wikipedia.org/wiki/Mini-magnetospheric_plasma_propulsion

41: Inner-inner core articles:

A: Professor Guy Masters Scripps institute of Oceanography
(http://www.solstation.com/stars/earth.htm)

B: BBC Earth inner inner core
(http://www.news.bbc.co.uk/2/hi/science/nature/2290551.stm)

C: Radioactive potassium may be major heat source in Earth core
Work founded by National science Foundation and department of energy
http://www.physlink.com/News/121103Potassiumcore.cfm

Published and unpublished works by M. T. Keshe

There are a number of unfinished articles that are to be converted to full disclosures when completed, like Antimatter method of energy releases, Nano space technology, relation between the creator and the created, space communication system, deep space defence technology, dynamic magnetic fields force regions (wormholes) construction and control, creation of magnetic fields, and so on.

Some of these works have already been published through different channels and some have not yet been released.

In the following section some of the works done by the same author are mentioned, with a brief disclosure of their contents.

Some of these papers can be purchased and obtained through direct request and access through specific links.

A number of papers with * and ** marks are not for public release due to their sensitivity of information and only available to relevant commercial and governmental organisations for peaceful applications of the technology.

The universal order of creation

(5.7.2006)

In this disclosure the main construction principles and the method of the link and control in the universal order of the existence of living cells, like the function and operational method of any matter based on so called proteins chains, as for example in human cell are explained in detail.

REF 9

The author considers this paper as one of his most important and fundamental works to be published and to be added to the sets of disclosures written by him.

Cosmic Rays

(Release date 24.3.2004)

This paper explains the source and the origin of cosmic rays and the way these work within our cosmos, their function and their benefits.

REF 10

----

*The Airborne reactor

(Release date 25.3.2004)

This paper covers the total design of airborne reactors for space technology. This covers all aspects of operation, design and control of such reactors.

REF 11

The seed of the Earth

(Release date 25.3.2004)

Some extracts from this paper:
The theory that the heat of the core of the Earth is due to inertia of the material pilled on top of each other is completely dismissed through this new disclosure.
The author M T Keshe believes that this centre core is made of hydrogen, other gases and a mixture of liquid and solid Matters, which were in the vicinity of the centre of the core of the Earth at the time of its inception in the solar system.
Through this new understanding of the new inner cores of the planet, this brings to play the fact that the old inner core of the Earth that is already assumed to be made of a solid piece itself becomes a sealed container for the new inner core.
The author through design of a parallel system has set to confirm the validity of this assumption, that the centre of the Earth possesses a *semi- fusion atomic reactor* and not a fission reactor as has been assumed by other scientists.
This theory of hydrogen in the centre of the planet is in line with the physical reality of the creation and the present situation in the physical construction of the solar system.
By the laws of physics all the gases in the solar system should have been in the giant gas planets at the outer layers of the solar system, like in Jupiter and Saturn.
The physical reality in the solar system, is that the lightest of all these gasses, the Hydrogen, has taken its place right in the centre of the solar system in its star, the Sun.
It has to be recognised that the centre of all planets in possession of gravity due to the centre cores heating, are always in possession of two Magnetic Field Forces in their inner sanctum (M. T. Keshe " The creation of gravity").
In the case of the Earth up to now and with the present knowledge there has been acceptance of only one inner core and one magnetic force.
As it is explained in the paper titled "the creation of gravity", there is an inner core in the inner core. This inner core, due to it physical content, motion and position in the centre of the Earth, creates and maintains its own magnetic field force, independent of the magnetic force which has been known to be created by the interaction of the inner core and the outer core of the planet.
These two magnetic fields interact to create the planet's own double magnetic fields in its centre. The interaction of these two magnetic fields forces upon each other leads to the new concept of the "DOUBLE MAGNETIC FIELD EFFECT", where the interaction between these two field forces in the centre of the planet leads to the creation of the gravity and the magnetic forces of the planet (Paper: The creation of gravity).
This new second core is the seed core of the planet, the mother seed of the planet

positioned in this new inner core.

REF 12

The creation of Black Hole

(Release date 25.3.2004)

In this paper it is explained that the Black Hole is created out of a natural sequence of events, and that the existence of the Black Hole in a galaxy is a normal event. Further it is explained that a Black hole is created in similar ways to the Dark Spots on the surface of the Sun. In this paper for the first time, it is explained how the Black Hole is physically created and what function it plays in its galaxy.

REF 13

Magnetosphere

(Release date 9.6.2004)

"The shape and the strength of the magnetosphere of a planet is exactly what a fingerprint is to a man. It is unique to each planet, star and galaxy. It is a tell tale of all its attributes, and it reveals the hidden mysteries of the internal materials' structure".

REF 14

Correction to the Einstein equation of Relativity

(Release date 15.6.2004)

In this paper the physical reality of the Einstein equation is considered, and efforts are made to bring this equation to the real conditions. Even Einstein considers this equation applicable for very small mass, and not in real three-dimensional multi-Magnetic and gravitational conditions, which are external and have nothing to do with the theoretical object's mass and speed, but have effect on the speed and the mass of the object under consideration.

REF 15

----

*Introduction to the new system

(Release date 2.7.2004)

In this paper it is written "It is essential to understand that, with the application of this system of motion, one cannot bring into play the solid, liquid and gas fuel method to create motion, as is used today. What is offered in this system is in simple words a fully integrated plasmatic magnetic energy system. Which creates within and around the core environmental conditions as known to man in the universe, like creation of gravity and magnetic field protection the same as the magnetospheric protection condition of planets and motion through interaction of magnetic fields as planets and stars do in their given environment".

REF 16

The rings of Saturn

(Release date 2.7.2004)

One of the oldest puzzles in the world of astronomy has been the existence of the rings around Saturn. How did these rings come to exist the way they are now? How did they come to appear and behave the way they do? These questions and much more about the creation of these rings are all answered in this paper.

REF 17

The creation of gravity

(Release date 11.7.2004)

In this paper it is explained that "the source and the creator of the magnetic forces and the gravitational forces are due to the interaction between the same materials in the same region of the planet."

Further it is explained how the gravitational field force can be created, replicated and controlled within a nuclear reactor. Further it is explained how this property can be used for the motion of a system within a planetary or solar system.

Now by understanding the principal of the creation of gravity, in this paper it is further explained that "the gravity in reality is the effect of the interaction of **two plasmatic magnetic energy fields** of any two object in respect to each other."

REF 18

Death of a star

(Release date 26.7.2004)

In this paper the death of stars is explained, "The death of a star and the creation of a supernova is in reality the same as the half-life cycle energy step-down of an atom. With the difference that this show is in a larger scale, and more spectacular, in all aspects of its dimensions".

REF 19

Fusion

(Release date 28.7.2004)

In this paper the physical and scientific problems with present fusion technology is considered. Where it is written, "nuclear Scientists, with the fusion reactors of today, are trying to create fusion in the opposite way to the known laws of physics and their parallels in the universe”. Further in this paper it is written, "if the present path for creation of fusion is followed, with the present scientific knowledge of physical materials for construction of such system, then following the present path of development to create energy from current fusion systems *will be a distant dream*".

REF 20

Life of a Cell

(Release date 28.11.2004)

Extracts from this paper; "The reality of the transportation and transmutation of a cell is not far from the reality of the life of an atom or a star. Where the life cycle of the cells are slightly more complicated, as they contain other Matters like acids, which have their own magnetic characteristic of their on chemical structure. For this reason the control and replication of the energy of the cell is very much complex, but very simple to achieve".

REF 21

The Atom

(Release date 19.12.2004)

The content of this paper explains how and where atoms in the universe are originated from and how the construction of atoms in a cold plasmatic nuclear reactor can be replicated.

REF 22

Magnetism

(Release date 8.1.2005)

In this paper it is written, "The question is where did the Magnetism come from? This is the Secret of creation. The world is made of one thing and only one thing and that is Magnetism. Its combination and interaction with its own different strength fields makes it appear as different Matter. The rest of creations are the outcome of these interactions of different strength of this thing called magnetism and the forces it creates. Magnetism is the origin of existence and the real singularity in its full meaning".

REF 23

----

*The creation of the magneto-gravitational force

(Release date 5.2.2005)

The creation of magneto-gravitational field force is and will be fundamentally independent of temperature and pressure, proviso to the fact that as long as a homogenous free floating PMF within a Matter is created.

REF 24

The core of the Earth

(Release date 20.4.2005)

One of the original assumptions in developing the new Magravs system some thirty years ago by M.T. Keshe was on the basis that the centre of the Earth possesses addition cores, which create the necessary gravitational conditions of the planet. After some twenty years of space technology and through Earthquake seismological data's this assumption has been shown to be correct and after over twenty years, it has been scientifically proven that the inner core of the Earth has an inner core of 600 km. Professor Guy Master in 2002 ref 24 nuclear planet. The centre of this core is assumed to have an inner core of 8 Km, this he thought to be made of the plutonium or other nuclear materials

But the developer of this new plasma reactor technology has proven through physical dynamic cores that these cores possess a mixture of hydrogen plasmas and the process of the heating of the centre of the Earth are due to a semi-fusion chain of events.

REF 25

----

*The electron-atomic welding

(Release date 3.5.2005)

Some extracts from this paper:
"The electron atomic welding or atomic welding principle is the phenomenon that atoms of the same material, through a common shared electron, become a magnetically balanced molecule of the same Matter, with the difference that the shared electron will create a balanced PMF in the molecule".

REF 26

----

*Shutdown and safety of the reactor core

(Release date 6.6.2005)

In this paper the safety parameters in the operation of the gravitational and energy reactors are simply explained to avoid the loss of plasma and gravitational field forces created within its cores.

REF 27

----

*Reactor Start-up

(Release date 9.6.2005)

In this paper the systematic start-up of the dynamic reactors for the creation of gravitational field forces and the production of energy are set out. The start up of these systems are totally different then the prior arts known in the nuclear industry.

REF 28

----

*The energy balance of the reactor

(Release date 29.6.2005)

Some extracts from this paper:

The energy balance of these types of reactors is not as simple as might look in the first instance. The energy creation is simple. But the heat leakage and dissipation through the deliberate inherent material design are and can be zero. That is to say the system not only can hold on the heat it creates. At the same time due to the close circuit feed operation will become self-sufficient but long lasting.

In planets, the loss of heat through their surface creates the variation in the central core condition over several billions of years. In this reactor as losses can be literally negligible, the system can operate at low energy loss temperatures. Even the boundary of the body could be made through the right combination of material in the chambers, so that the body of the reactor will be colder then its surrounding boundary. So the system will not only lose energy to its surrounding, but it can be made to absorb heat in the negative temperature gradient from its surrounding, so that there are no losses.

REF 29

Nuclear decay or half-life

(Release date 20.7.2005)

Extracts from the paper:

"The nuclear decay always has the same or near the same time duration. This is due to the fact that the all neutrons and protons, from their inception, carry a predetermined level of plasmatic magnetic energy. This energy is continually used for the motion and vibration of different elements of the nucleus in respect to each other and the surrounding Matters of the atom. As the space and dimensions of a nucleus of an atom always obeys the same principal of the magnetic separation and magnetic attraction. Protons or neutrons can and will need to use or consume the same energy before they become weak enough that the splitting or decay becomes a clockwork job. The nuclear decay is the natural levelling done of a nucleus' energy, due to the energy consumption and heat dissipation for the motion of the elements of the nucleus for its remaining plasmatic magnetic fields energy necessarily needed for them to hold one together".

REF 30

----

*The decontamination system

(Release date 10.10.2005)

"What this means is that, for example in trying to recycle the CO_2, by the use of the right Matter in one of the cores of the reactor, the system will then use the O_2 to produce H_2O, in the form of pure water, and C in the form of atomic or molecular carbon, or even by feeding this back through certain operational compressions and gravitational interactions within a small core, to create industrial diamond or graphite, for different industries."

The use of the reactor for this purpose has been proven to be correct and Raman spectroscopy has proven the concept and physical reality of the separation of Matter in atomic level after separation in the same system from a composite Matter.

(See the graphene on the technology web site)

REF 31

The difference in atomic and molecular structure under gravitational force and pressurised conditions.

(Release date 15.8.2005)

In this paper is written that "the atomic and molecular structure of Matter is totally aligned and positioned in a fundamentally different configuration where it has come together due to gravitational forces, than when Matter has been brought together by the means of pressure. This has a fundamental effect on the behaviour of the structure and properties of the Matter which is created in either way". Where this is explained and utilised to develop a new method in creating graphene and Sp3 atoms and walls in a simple core made of a coca- cola bottle.

REF 32

**The Defence and shielding system

(Release date 4.9.2005)

Some extract from this paper:

The design of the side open system for lunch of high saturation magnetic plasma package is one of the most effective technologies for defence of the reactor and the craft, which is in possession of such a system.

It is essential for any space technology in the open environment of the universe, if the craft is to keep a straight line of motion and to be able to protect itself from any solids or Matters in its path in the cosmos.

This technology can destroy any object by the principal of plasmatic magnetic energy saturation of the incoming object at a molecular level, that object will disintegrate in the form of magnetic vapour and not atomic level destruction, before Matter can damage the craft as debris, and before the craft ever becomes in touch or near these space Matters.

This technology can also be used to protect Earth from the collision risk of NEO's (Near Earth Objects), like comets and asteroids.

REF 33

Method of creation of an atom or nano Matter

(Release date 11.10.2005)

The manufacture of an atom of any density, this being of the simplest form of nucleus or a full atom of hydrogen, or even heavier elements in the universe, all follow the same principal.

Atoms are created in the soup of the cosmos from collections of very weak plasmatic magnetic fields, which for their existence cluster and share their energies with the magnetic fields that are not far from their own plasmatic magnetic field strength.

REF 34

The relationship between Gravity and Mass

(Release date 21.1.2006)

Extracts from text of this paper:

"A planet like Earth possesses a combination of both gravity and inertia. Where the gravity comes from the interaction of plasmatic magnetic energy fields from the processes within its core, and the inertia comes purely from the collection molecules PMF of Matters which has built the physical body of the planet.

Any object, being an electron, atom, molecule or even a human body, is a collection of plasmatic magnetic energy fields of different strengths and their interactions between each other, which in total decides the total or collective magnetic field possessed by that object where this is the mass of the object.

Where the mass of an object is a collective package of plasmatic magnetic energy field tightness of a given object and will not change as long as the object is intact as one entity in its overall atomic or molecular or collective molecular appearance.

Which plasmatic magnetic energy of a physical body (so called the mass of the body) in interaction with molecular or atomic magnetic field (this being gravitational or inertia) of another object will determine the weight of the two object in respect to each other in each others environment".

REF 35

The Dark Matter

The Fifth state of Matter

(Release date 21.1.2006)

Extracts from text of this paper:
The existence of Dark Matter is not questionable,
Proving its existence, and its effect on the energy balance of the universe, in all Matters as small as in the heart of an electron or in a solar system needs to be created, replicated and its effect measured.
The theory of Dark Matter does not and needs not to be considered as complicated, if one understands in real terms the plasmatic magnetic energy of the Matter in the visible and invisible dimensions of the universal work.
The Dark Matter has two distinctive characteristics, which makes it totally apart from the visible Matter.
The Dark Matter possess mass but not visible light, where its existence can only be determined by the weight of the its hidden mass, which could be substantial due to its internal gravitational field.

REF 36

----

*The inter-atomic fusion

(Release date 3. 5. 2006)

Extract from this paper:
"The fusion of two or more atoms has been the pre-occupation of nuclear physicists for past years.
Conditions to achieve fusion of two hydrogen plasmas in the TOKAMAK reactors have taken years to teach scientists a lot about the behaviour of plasma and their fusing.
The reality about the fusion in someway has to be reconsidered as, if the scientific world is trying to amalgamate the contents of two plasmas to release energy. There must be a simpler way to achieve releases of similar energies.

The fundamental principal of the inter-atomic fusion is a much simpler way to achieve fusion. If this principal is applied to the atomic condition of fusion, then fusion will be attained in a simple but in a much more physically realistic environment.

The explanation for the inter- atomic fusion is very simple and direct.
In the fusion of two plasma of proton of hydrogen atom, the physicists try to fuse two large plasmas, and by doing so, they try to release a large amount of energy. Where in this process enormous amount of magnetic field forces and currents are needed to bring two plasma in close proximity, so that the energy barriers in between them can be overcome for them to amalgamate or fuse.

In the inter-atomic fusion the overcoming of energy barriers does not exist, as in this method of fusion, the electron of the atom which is circulating the nucleus of the atom and is of the same origin will be encouraged to return into and fuse with the nucleus of its atom".

Where this is a more practical way to create and release manageable energies and there is no need for elaborate systems where even if the energy release will be small compared to dreamed up fusion systems of today.

With inter-atomic fusion method at least small and practical systems can be developed to handle low temperatures of the fusion process.

REF 37

The conductivity of the Matter in the vacuum of the interplanetary mediums

(Release date 21.1.2006)

Some extracts form this short paper "Therefore plasmatic magnetic energy field of elements within the interplanetary medium will cover the space given to them in their environment. Where due to their motion and their electric charges even in eV levels, they become perfect conductor, and in turn, due to their motion on their environment, they become plasmatic electromagnetic generators.

REF 38

The production of Graphene

(Release date 25.7.2006)

Repeated experiments and tests in simple static reactors, and tests in more complex dynamic reactors, prove that atomic separation and recombination of Matter like carbon and hydrogen can be reached at room temperature and at atmospheric conditions.
We have now indications - through static and dynamic tests in our reactors - that the universe was made in normal condition, which was originally nothing but packages of plasmatic magnetic fields of different strength, which were themselves nothing but areas of plasma or collections of loose magnetic fields energies. Where magnetic fields of different strength in locking to each other, by the principle of their **plasmatic magnetic energy (PME),** have caused in the first stage the creation of fundamental particles, secondly atoms, then molecules and then Matter, clouds and asteroids and then stars and galaxy's".

The big bang theory conditions have no room in the reality of the creation of the universe.

REF 39

INTERNET LINKS

Web site: www.keshefoundation.com

Large images of this book on the web site:
http://www.keshefoundation.com/book/images/

Links on the web site to YouTube movies: http://www.keshefoundation.com/youtube/

Forum: http://www.keshefoundation.com/forum/

INDEX

1

1.5 billion people 175

A

accelerators 16, 91, 151, 185
action and reaction 154
A-D Matter 110
aircraft 57, 99, 144, 164
amplitude 141
annihilation 108
anti-gravitational 162
anti-gravity 180
Antimatter 14, 32, 66, 92
  energy 92
  strongest pmtics **90**
apple 68
argon 157
asteroids 113, 126, 127
atom 11, 20, 24, 35, 50, 51, 65, 68, 81, 89, 106, 111, 115, 123, 129, 130, 132, 140, 158
  mass 67
atomic carbon 174
atoms 14
attraction **85**
attraction field **14**, 23

B

bacteria 120
Big Bang 58
Black Hole 45, 85, 93, 100, 101, 111, 181, 189
blood **120**, **192**
  red **191**
blue shift **58**, 104
bread 20

C

carbon 27, 79, 120, 126
Caroline Core **21**, 27, 29
cascade 87, 113
cascading 111, 182
Casimir effect **105**
catchments **13**, 26, 84, 87, 110, 160, 166
charge
  negative 139
  positive 138
CO_2 126, 148, 154, 170
coiling 65
collection 12
  weak **13**
collective existence 14
collision **37**, 57, 73, 75, 76, 81, 95, 106, 115, 121, 126, **164**
colonisation of planets 192
colours 51
controlled fission 130
convection principle 22
conversion principle 66
copper 174
cosmic dusts 158
Coulomb barrier **15**, 117, 119, 148, 176
cube of sugar 72
cup of tea 108
current 105
current flow 138

D

Dark Energy **98**
dark light 80, 83, 102, **103**
Dark Matter **12**, 14, 32
Dark Rings 93
Dark Spots 45, 93, 100
darker zone 95
darkness 83, **96**, 97, 100
daylight 78
decay 51, 130
  natural 137
  neutron 129
decay of the neutron 111
dense pmtics 65
dependent
  balance 83
  density 85
  distance 60
  environment 14, 79, 99
  forces 53
  friction 31
  gravitational 84
  inertia **124**

  mass ... 18
  payload ... 154
  position ... 26, 84, 99, 142, 188
  size ... 18
  strength ... 26, 53, 80, 88
diamond lattice ... 174
dictation of position ... 143
different speed ... 66
dilution ... 177
  Grapos ... 159
  process ... 150
  reactors ... 152, 158, 169, 177, 189
  soup ... 148, 152
  technology ... 151, 164, 176, 189
direct conversion ... 192
disentangle ... 15, 62, 150, 158
dislocation ... 163
domain pmtics ... 60
drinking water ... 181
DYPMFS ... **169**, 171, 173

E

Einstein ... 65
electricity ... 175
electromagnetic ... 89
electron ... 51, 65, 89, 132, **134**, 135, 140
  enegry ... 32
  motion ... 121, 141
  path ... 141
  plasmas ... 118
elementary particle ... 52
energy ... 58, **93**
energy of the pmtics ... **58**
enough food ... 192
equation of relativity ... 65, 71
equilibrium ... 58, **94**, 159
Extreme Ultra Violet ... 173

F

faster
  than light ... 81
Fermilab ... 17, 66, 91, 158
field force ... 60
field strength ... 31
fields ... **11**
fission ... **15**, 16, 37
food ... 5
fragments ... 78
  pmtics ... 75, 105
  residual ... 78
frames-of-reference ... 88
free lift ... 159
friction ... 29, 31, 37, 57, 75, 99, 119, 153, 166, 170, 182
fundamental source ... 90
fused into ... 115
fusion ... **15**, 16, 37, 117

G

galaxies ... 52
gamma rays ... 173
Ganymede ... **165**
gap ... **120**, **135**, 138
Geo-Reactor ... 27
gluons ... 185
graphene ... 17
Grapos ... **79**, 99, 126, 155, 156, 158, 160, 161, 166, 173
  crafts ... 167, 181
  lift and motion ... 79
  nuclear reactor ... 171
  reactors ... 64, 79, 80, 165, 177, 193
  test-reactors ... 91
Grasers ... **126**
gravitational field ... 14
gravitational fields ... **12**
gravitational lensing ... 85
Gravity ... **25**, 28
greenhouse gasses ... 171
ground energy level ... 121
ground level ... 32

H

half-life ... **131**
hard ball ... 20
heating ... 27
heavier elements ... 190
heavy atoms ... 138
Helium ... 138, 157
hydrogen ... **13**, 81, 147, 157, 190

I

illnesses ... 184
impedance ... 139
independent pmtics ... 28
inertia ... 19, 123
initial

  fundamental Particle...................... **12**
  fundamental particles............5, **12**, **37**
  fundamental plasma................. 14, 51
  fundamental plasmas **35**
  gravitational field **14**
  pmtics... 14
  seeds of plasma 11
  set.. 39
initial pmtics..................................... 14
inner core.. 27
interaction... 14
inter-atomic fusion......................... 115
interface.. 167
interface colour............................... 191
interlocked...................................... 123
interlocking 39
inter-transit..................................... 53
invisibility 57
irrespective 30

K

Keshe principle
  conversion energy.......................... 66
  Magravs positioning....................... 17
  transition 55
Keshe Theory
  creation of Matters....................... 104
  Dark Matter.................................. 45
  Dilution.. 16
  Earth Rotation 28
  gravitational field 24
  Gravity.. 25
  Mass... 62
  Transition 55

L

lift... 162
lift and motion ...17, 18, 21, 77, 91, 148, 154, **159**, 164, 166, 176, 177
light **32**, **84**
  Antimatter **88**
  bright................ **79**, **81**, 115, **155**, **156**
  dark 83
  Dark Matter.................................. **88**
  day 76, **78**, 81, 155
  fuzzy 81
  matter... **88**
  night... 78
  rays... 88
  spectrum 81, 121
  sun.. 120
  UV 173

M

M2P2 157
magnetic **12**, **13**
  field 5
magnetic field.......................**11**, **12**, **13**
  plasmatic 34
  weak **16**
magnetic interface........................... 112
magnetic ray 87
magnetosphere **13**, 94, 99, 104, 138, 155, 158, 166, 173, 176, 186
  independent 50
magnitude difference 47
Magravs.................................... **13**, 15
  balance 17, 18, 78
  balanced 51
  collective 40
  overall 44
  plasmatic 28, 35
  positioning..... 17, 141, 143, 154, 156, 157, 159, 164, **171**
  reactors 162
  strong 17, 179
  weak 39
Magravs positioning........................ 141
mass... 51
  independent 186
  plasma 186
mass of matter.................................. 65
matching numbers **137**
Matmags........................19, **31**, 72, 144
matter 14, **31**, 32, 99
Matters **12**, **14**, **30**, **53**
Matters-to-matters 192
Matter-to-Matter 92, 123, 185
medicine 5
Mercury **13**
method of motion 143
minerals 163, 174
mini-plasma 110, 135
MOJHAN 168
molecules...........................14, 143, 146
mono-Magravs................................ 126

mono-material **13**
MOZHAN 168

N

nanolayer 174
nano-oxides 17
nanostructure 174
NASA 157
neutron 35, 49, 65, 120, 190
Newton 26
nitrogen 120
nothing 101
nothingness 108
Nova condition 113
nuclear
  -based 15, 19
  decay 27, 37, 51
  fission 27
  reactor 27, 56
nuclear decay 129, 137
nuclear waste 171
nucleus 50, 129, 130, 138, 143

O

omelette 117
out of nowhere 109
oxygen 120

P

photon 105, 106, 108
Plasma **14**, **32**, 157
Plasma Dilution 16
plasmas 53
plasmatic **12**, **14**, **39**
Plasmatic Magnetic Field **12**
plasmatic strength 55
pmtic **12**
  environment 54
  soup 16, 102
  strength 66
  strong 92
pmtics **12**, **37**
  active 163
  magnitude 103
  passive 163
  remaining 40
  slower 66
  spectrum 163
  strength 54
  stronger 37, 92
  weak **12**, 16
  weaker 37
pmtics in motion **58**
pmtics strength 42
polarity 88, 188
  change 100
  planets 189
  same 159
Potassium 191
poverty 175
processes of transition 58
protection system 166
proteins 79, 147, 163, 173, 191, 192
proton 13, 22, 35, 51, 52, 62, 65, 115, 118, 120, 132, **133**, 140, 141, 189, 193
  accumulations 120
purification 175
push and pull 106

Q

quark 52
quarks 12, 51, 185

R

radio waves 157
rays **11**
reactor
  multi-core **15**
red shift **58**, 104
replicating 147
residual pmtics 46, 48
residuals 37
resistance 139
rings 112
rotation 140

S

saturated 182
Saturn 22
  rings 93
seed of plasma 39
SEPMAF **36**, 129
SET P1 40
SET P2 .... **43**
SET P3 .... **44**
shielding 158
singularity 58

solar system ... 82, 186
solid core ... 28
solid magnet ... 23
soup ... 104, 150, 183
  atomic plasma ... 117
  environments ... 148
  galaxy ... 114
  Matters ... 148, 152
  plasma ... 119, 148
  pmtics ... 39
  principle ... 17
  universal ... 125
sp2 ... 174
sp3 ... 174
space in-between ... 103
space technology ... 19
spacecraft ... 57
spectrum ... 79, 84, 88, 191
  colours ... 102
  electromagnetic ... 121
  light ... 99, 101
speed of attraction ... 88
speed of rotation ... 30, **186**
spin ... 51, 186
squeezing ... 117
states of matters ... 14, 32
step
  first ... 39
  fourth ... 45
  second ... 41
  third ... 43
strength
  same ... 14
  stronger ... 42, 85, 107
  unequal ... 64
  weaker ... 57
sub-plasmatic ... **16**
swirling ... 65
swirling effect ... 87

T

tail ... 64
tests ... 91
the Antimatter ... 30
the Dark Matter ... 30
the **F1** ... 46, 65, 70, 71, 111
the Matter ... 30
the Sun ... 20, 34, 45, 76, 77, 78, 90, 100, 108, 155, **186**, 192
Theory
  Gravity ... 25
time ... **54**, 71, 88
Tokamak ... 117
transformation ... 190
transition ... **54**, 58
transition of Matters ... 55
translucent ... 56
Translucent Darkness ... 102
transmission lines ... 173
transmutation ... **54**

U

UFO ... **157**
uncertain ... 140
UN-report ... 175

V

Van der Waals ... 106
virtual Matter ... 104
virtual particles ... 104
viruses ... 184
vitamins ... 163, 174
voltage ... 105
VOMAFS ... **170**, 171

W

warp ... 85
warping ... **86**
warping effect ... 86
weak
  magnetic fields ... 11
weaker binding ... 189
Wormhole ... 47

X

X-rays ... 173

Z

zero weight ... 159

In this book nuclear engineer Mehran Keshe discloses in a very logical way that the initial fundamental building blocks of the universe find their origin in a cosmic magnetic soup that contains an uncountable number of magnetic fields of different strengths. In this soup magnetic fields of similar or equal strength can meet, interact and entangle into a larger dynamic spherical pack. The interaction between different dynamic packs, leads to the creation of Gravitational and Magnetic field effects and properties in their given environments. Due to the differences in their magnetic field strength each spherical pack will possess a different strength, which each magnetic field strength will be in the order of magnitude of the three basic types of Matters (Dark Matter, Antimatter and Matter).

As these three Matters being made of magnetic fields, they also interact, inter-balance and can interlock with each other, these interactions of three Matters results in a larger integrated dynamic system, called the Initial Fundamental Plasma, or the Neutron. By the natural decay of this plasma, the proton and the electron come to be generated and to co-exist, where plasma of each proton and each electron still contains the Trinity of the three Matters of the original plasma.

The discovery of these new first principles in physics will open for mankind a large number of benefits, since the various type of interactions of the three basic Matters and their field forces in their environment leads to the creation and control of matters (solid, liquid and gas).

In this book, new first principles and criterions for the creation of Gravitational and Magnetic field forces of the planet Earth are explained. Similarly it is explained how safe, simple, nuclear reactors, which have been build to replicate the structure of the planet inner cores, confirm the Keshe theory of creation of gravitational fields of the planet, as these reactors can produce fields which can cause reduction in weight, cause motion and lift of the reactor system, and produce an independent magnetosphere around such reactors. The interaction of the dynamic plasmatic magnetic fields of the magnetosphere around these reactors with the planetary magnetic fields creates light around the reactor. These light-effects confirm the Keshe's theory of creation of light through the interactions of plasmatic magnetic fields. These systems will open new ways of Space Travel.

By this knowledge it became possible to design, develop and test new low cost reactors that can dilute plasma and achieve fusion of plasmas in a simple and affordable way. So it now becomes possible to create vast amount of energies (like electricity and heat) and motion without the need of burning any fuel and without creating any waste. These reactors can create at any point-of-demand matters like air, water, food, medicine, and new materials, also at nano-level.

This new revolutionary technology can help to solve a number of global problems, like of the climate change, since Keshe reactors can be build to attract greenhouse gasses like CO2, or the global issue of water shortage and water pollution since it becomes now possible to create water and to attract hazardous elements out of the polluted and contaminated waters.

Kt
The Keshe
Foundation

The Keshe Foundation is an independent non-profit and a non-religious organization founded by nuclear engineer M.T. Keshe, aiming to bring new scientific knowledge and new technologies to mankind, and to bring new solutions for the major global problems, like famine, water shortage, shortage of electrical power supply, climate change, illnesses, by the use of new types of plasma reactors, and to give Man the real freedom to travel in Space.

ISBN 978-94-6087-002-6

The Structure
# of the
Light


MATTER
PRINCIPAL MATTER
TRANSITION MATTER
MATTER
PRINCIPAL MATTER
TRANSITION MATTER

Kf
Editions

Nuclear Engineer M.T. KESHE

本电子书不是官方正版，

而是使用从官方购买的正版电子书，

截屏＋拼接＋OCR文字识别＋重新拼版制作。

因此难免出现错误的字或符号，

如果您希望获得原始的官方版本，

请购买正版，支持KESHE。

QQ群：30137653

Stichting
THE KESHE FOUNDATION
(The Netherlands)

The Structure
Of The
Light

ITNOTGOG

Reflection

The light has plasmatic structure the same as the plasma of the proton and electron and it is made of mixture of magnetic fields strength with difference that the light has dynamic composite magnetic field strength spiral helixial cylindrical composite matter mafs plasma structure rather than the dynamic composite mafs spherical structure of the matters the like of the plasma of the neutrons.

Copyright notice: © Mehran Tavakoli Keshe 2011. All rights reserved.
Nothing of this book may be replicated, simplified, translated and/or made public by means of print, microfilm, tape, audio-recording systems, electronics, optical and solid-state media, electronic storage systems, by network publishing or by any other ways without prior written authorization of the publisher or the author.

ISBN 978-94-6087-003-3
Version 2 – April 27, 2011

Illustrations and Layout: Dirk Laureyssens

Publisher: Stichting The Keshe Foundation
Registered Office: Jubileumplein 3, NL-6161 SR Geleen, The Netherlands
Registration Number: KVK 14089728.
Web site: www.keshefoundation.com
E-mail contact: info@keshefoundation.com

Forwords

All knowledge gathered and learned in every fields of science by man in his cycle of scientific evolution from his beginning of time and up to this point, these are like of the speck of dust of the universal wisdom in comparison to what man will enjoy from the knowledge which is to be revealed in this disclosure.

This shall not be all that the man has to know about his creation and the creator but through this new knowledge man will become close to realise how much more he needs to discovered and learn more about the created bigger universe, and our hope is that we have managed to bring man to his ultimate point of maturity about his world and the world of other creatures of universe through what is to be disclosed in this book.

In these new series of disclosures including this we will open the world of science into the realisation of the real working of the universe and how man can advance his intelligence and that this new and up to now unknown science can clear the way for bringing peace to the Man’s own wondering life and other intelligent beings in the universe.

TABLE OF CONTENT

Reflection ... *6*
Forwords ... *9*
Introduction ... *13*
The re-naming of matters and conditions ... *14*

CHAPTER 1 ... 16

THE LIGHT ... 16

CHAPTER 2 ... 19

THE STRUCTURE OF THE LIGHT ... 19

CHAPTER 3 ... 41

THE CONVERSION OF LIGHT RAYS TO THE GANS OF THE MATTER ... 41

CHAPTER 4 ... 54

CO2 IN GANS STATE (PAPER 2009) ... 54
Abstract ... *54*
Discussion ... *54*
The CO2 absorption ... *57*
The methane CH4 absorption ... *68*
Observations and notes. ... *76*
New state of matter ... *77*
Implication and applications of this new technology ... *79*
Conclusion ... *81*
Additional pictures ... *82*

CHAPTER 5 ... 85

THE LIGHT AND ITS INTERACTION WITH THE PRINCIPAL STAR ... 85

CHAPTER 6 ... 90

THE LIGHT AND ITS PLANETARY INTERACTION ... 90

CHAPTER 7 ... 92

THE USE OF THE PROPERTIES OF THE STRUCTURE OF THE PMF OF THE LIGHT FOR SPACE TECHNOLOGY ... 92

CHAPTER 8 ... 98

INSIGHT INTO THE FUTURE USE OF THE STRUCTURE OF THE LIGHT ... 98
DEFINITIONS ... 106
Reference ... *107*
Published and unpublished works by M. T. Keshe ... *108*
INTERNET LINKS ... *120*

APPENDIX 1 ... 121

The unifying field Theory ... *121*
Abstract ... *121*
Discussions ... *121*
Electromagnetism ... *122*
Permanent magnets ... *125*
The difference between conductors and superconductors ... *125*
Experimental point's observation ... *128*
Conclusion ... *128*
Reference: ... *129*
Index ... *130*

Introduction

With the present knowledge in the plasma technology and the new understanding of the internal structure of the plasma, the light is and can be considered to be a cylindrical version of the spherical plasma like of the proton and the plasma of the light is in possession of all three magnetic fields of the matters of the plasma (1).

The ray of light is in possession of Magravs and hence its own gravity, mass and Magnetosphere, and due to its dynamism this plasma of the light possesses momentum and hence can carry and transfer this momentum as energy to other light rays, tangible and non-tangible entities.

As the plasma of the light is moving from one dynamic magnetic field strength spherical in shape plasma to another and as each matter's mafs of the plasma of the light interacts with its surrounding environment's plasmatic magnetic fields in any matter environment, then the appropriate matter mafs components of the light and its ever present environment come to interact with the same and different matters and matter mafs in strength of its environment, this leads to less losses of the plasmatic magnetic field (pmf) contents of the mafs of the matters of the ray of light and hence allowing the light to travel in any environment at the speed of its given environment plasmatic magnetic fields strength with less friction and maximum speed in that given pmf strength. Then in matter mafs and matter magnetic fields strength environment, this property allowing the ray of light to have a speed of light in matter environment strength as is observed by man, and where in antimatter environment the antimatter light travels at antimatter magnetic field strength environment, which the speed of antimatter light is far higher than the speed of light in the man's matter plasmatic magnetic field strength environment.

Thus the speed of the light in the matter environment is not the ultimate speed of matters in the universe, but the speed of light is dictated and controlled by the environmental magnetic field strength which the light operates in.

It is possible to attain faster speeds than the speed of light in a matter magnetic field strength environment by using the magnetic fields properties of the antimatter plasmatic fields.

Once understanding this criterion and concept then at this stage one will face the magnetic strength barriers to overcome as one does in the matter environment with sound barrier.

Therefore: One has to understand the truth about the real construction of the light and its movement in each plasmatic magnetic field strength environment for the man to be able to travel the spans of the universe with pleasures of being able to observe and learn all the truth about the creation in all pmf strengths which operate in the universe.

The re-naming of matters and conditions

(Advice: Skip this section unless you need to refresh or reading for the first time or read it after you have read the chapter 1, 2 and 3 as this section can be confusing and distracting you from the main body of the book).

(Point of reference: The following section is and to be added to all disclosures for the ease of understanding as most of these have been disclosed in the book (1), and it is added here for the ones who have not read the book and are not familiar with terminologies in the works of the author).

In this literature, when using the term "mafs" for example in form of the antimatter mafs this means and refers to the magnetic fields (mafs) which this entity is made of and it is considered to be as a plasma of magnetic fields, and where the term "antimatter" is used on its own this meaning the physical tangible or detectable entity of the same. This usage of mafs similarly applies to physical matter and Dark matter too.

Further, the difference with Antimatter and matter is only in their plasmatic magnetic fields (pmf) strength and compactness of their fields. Thus, what is the magnetic fields (mafs) of antimatter they become magnetic fields of the matter as antimatter magnetic fields unwinds, loosens up, weaken in their field strength through their interaction with other magnetic fields and matters and become matter mafs and in plasmatic magnetic field strength of matter environment the matter mafs becomes tangible and become matter.

Therefore the antimatters are a more compact strength magnetic fields entities of the same of the magnetic fields of the matter, and due to their tightness of their fields, these magnetic fields of these mafs of matters they create stronger gravitational and Magnetic fields and hence they have stronger Magravs and hence upon their unwinding, they release magnetic fields and pmf which are faster, higher in strength and hence they look as to be strange strong and fascinating matters.

This means that antimatter entity of for example ten centimetres in diameter once unwinds in structure it becomes a matter of several thousands of meters in diameter entity in matter magnetic field strength environment.

Inevitably one should call the term antimatter the start matter and therefore antimatters should be renamed the Principal matter. Therefore there is nothing anti about these matters mafs and matters at their pmf strength as has been assumed in the world of science.

The Principle mafs matter itself has different degrees of strength by itself and not all magnetic fields of the Principal matters have the same magnetic field strength. Where, the principal mafs plasmatic magnetic fields strength has a spectrum of field's strength too.

As the magnetic fields of the principal mafs unwinds, it releases and loosen in its environment these magnetic fields (mafs) of the principal matters disperses into their environment, then they lose their strength through contact or interaction and friction with mafs' of matter and matters, and hence these principal mafs matters pmfs go for through magnetic fields strength of the Dark mafs matter strength first before through further reduction in strength, the dynamic pmf of mafs of the dark matter in motion reaches the pmf strength of the matter mafs level and hence becomes visible in matter pmf strength environment and becomes matter.

Now that the essence of existence of dark energy or dark matter can be explained in its realistic manner, and that is what has been called dark matter is in fact this is a magnetic field in transit from the principal mafs matter and matter strength to matter mafs strength and matter.

Then as energy has been defined as “magnetic fields in motion” then the dark energy in fact is transition mafs matters in motion, or what is called the transition energy.
Then the dark energy can be called the Transition energy instead of the Dark energy, as the pmf in motion as this magnetic fields from the mafs strength of the principal matter in motion to reach to mafs strength of the matter level, this is only a Transition pmf condition, and transition mafs matter phase only.

Where, the interaction of mafs of transition matters with other of the same leads to and creates the Transition gravitational and Magnetic fields of their own or create what is called the Transition Magravs and in some cases this condition leads to creation the transition matter (dark matter) and consequently sometime interaction of mafs of transition energy leads to appearance and become transition matter (dark matter) in the cosmos.

Therefore, the magnetic fields strength which makes the **dark matter** is to be renamed as the mafs of the transition mafs matter and the dark matter as tangible matter becomes the transition matter, the dark energy to be renamed to transition energy.

The plasma of the principal mafs matters exists everywhere in the universe. This being in the centre of the universes, galaxies, stars, planets, plasma of proton and even in the centre of the plasma of the electron and in the lower order pmf strength environments which have been undetected up to now by man.

In reality in the centre of what is called a black hole in the universe, there exist and is the home of the principal mafs matters and principal matter. Therefore the *black holes should be called* ***the principal stars*** in the centre of galaxies, stars, plasma of protons and other entities like these.

The choice of the term star for principal centres of matters is correct as these principal matter concentration centres are like a star in the centre for the matter world like solar system, and the Principal stars are the place for the mafs of the Principal matters and the principal matters which their fields radiate outward into their surrounding as it does with the stars. Thus from this point on in this disclosure we call the black holes the Principal stars in the universe now that we understand the real source of their mafs of this matter(s) and its principal matters.

It can be understood now that where the intensity and the strength of stars and planets come partially from the existence of the principal mafs pmf strength which has been released by the Principal stars in the galaxies. This is to say that the seed of the pmf of the galaxies and matters needed for the creation of stars in principle are from pmf of the mafs of the Principal matter. Where, *the interaction of the pmf of these mafs' of the Principal matters* leads to *creation of initial strong Magnetic and gravitational fields* needed for the creation and attraction of mafs of matters of plasmas of matters, the mafs of the transition matter and transition matters of the same region of the galaxies, plasma of stars, plasma of the proton and other entities of the same structure in the universe.
At the same time when using Magnetic with capital “M” this means the like of the Magnetic field of the earth, which itself is the plasmatic environment created by the interaction of at least two magnetic rays and indicates the outward flow of the magnetic fields from a plasmatic environment the like of the earth.

Similarly, when using magnetic field with small “m” this simply means the magnetic fields as in what we observe at the end of a solid magnet as magnetic fields of the object without its interaction with other fields.

Chapter 1

The light

The initial assumption which has been made by Einstein that the light is energy and travels with the ultimate speed of acceleration in the world is nothing but short of the lack of the understanding of the scientist about the real truth about the real different composition of dynamic Magnetic fields strength which the light is made of.

It is really unthinkable that the light in matter environment can be considered as energy as has been done by Einstein, as he has even proven that the light tends to bend when it passes near large objects like stars.

This bending of the light should have indicated to Einstein that, when energy tends to bend in and around any objects like a star, this by itself indicates that the light is and possesses both a Magnetic and gravitational entity structure. He should have understood that only Magnetic fields or the gravitational fields, which both are magnetic fields based, that these two entities can only attract or interact with other magnetic fields based Magravs entities and then in finding their position in respect to each other, this causing the positioning and not bending of the light in respect to the star and hence light bypasses such large objects by manoeuvring around them and gets or give the appearance of bending near the object as it position's itself in respect to large objects Magravs.

Hence light is not energy but a physical plasma entity like the plasma of a proton or an electron. Therefore, the interaction and Magravs positioning of two physical dynamic entities, which leads to observation of what is called the bending or lensing of the light near large objects the like of the star.

Whereas this was not so and light was an energy, and as has been explained before energy is when plasmatic fields (pmf) are in motion, then light would have been absorbed by the Magravs of most stars into their magnetic fields based atmosphere on the way of them passing through cosmos and as has been observed the light would have been absorbed by the other entities in the cosmos, and the light ray would not find its position in respect to star and bend around stars and large dynamic entities in the universe and the light ray would have never been able to cross the universe that one can now see the emitted light of stars from far corners of the universe.

Therefore as light tends to react and bend near objects like stars this by itself indicates important points that the light is a composite magnetic field based entity and if one can attract and interact with any composite magnetically based entity, then the entity has to have both Magnetic and Gravitational field forces.

When two or more plasmatic spherical magnetic fields Magravs interact then this can lead to release and creation of cylindrical Magravs of the light, which ***this transitional Magravs entity*** possesses both **mass and gravity**. Therefore, as the plasma of the light possesses gravity and Magnetic fields, hence this entity due to its structure possesses its **own mass** and its **own magnetospheric environment** too.
Where, this magnetosphere which is created by the interaction of the two the Magnetic fields and gravitational fields of the light in its interaction with other pmf of Magravs of a given environment, this leads to and creates the visible light in matter mafs and matter environment when the outer matter content of the light is in matter environment.

Hence the interaction of the plasma of the light and its environment's magnetosphere leads to release of pmf in the human protein Magravs strength, which manifestation itself as the visible light.

That is to say as the magnetosphere of the light interacts with the magnetosphere of its given environment, due to friction of the two fields*, residual magnetic fields leftover* are created, which they are manifested as visible light or other wavelength of magnetic fields according to the human eyes protein cells plasmatic magnetic fields strength levels in earth environment Magnetic fields condition and in comparable environments.

Chapter 2

The structure of the light

As an entity in possession of Magnetic and gravitational fields moves from one spherical plasmatic magnetic fields environment (for example the plasma of the proton) to another plasma, the plasma Magravs motion in between these two spherically dynamic plasmatic entities (transition plasma magnetic fields (pmf) stretches' to and takes the shape of elongated cylindrical Magravs entity rather than a spherical shape.

It can be considered that the tangible or detectable pmf are of dynamic spherical in shape entities and they possess the pmf Magravs of their own and as the pmf moves from one dynamic spherical entity to another dynamic spherical pmfs Magravs environment then the plasmatic magnetic field Magravs in transit between the two spherical Magravs due to interaction and its composite Magravs configuration and the Magravs composite of its environment becomes elongated pmf in shape from the Magravs of the spherical plasma and takes and become narrow and elongated and hence spiral cylindrical in shape.

It has been explained in detail that the plasma of dynamic spherical entities like plasma of the protons' is made of three main components of mafs of the matters, the mafs of the principal matter and the mafs of the transition matter and mafs of the matter (1).
Therefore the elongated plasma of the same must contain the same mafs and matters but in a different structural positioning configuration.

Hence the dynamic cylindrical shape plasma of the mafs of the matters in transit from one plasma to another will have the same quantity mafs of all matters of the dynamic spherical plasma and therefore the plasma in transit possesses and it is made of the same mafs of the principal matter (Fig.1, 2), mafs of the transition matter (Fig.1, 2), and the mafs of the matter (Fig.1, 2), hence the plasma of the light contains the same mafs of the matters as the plasma which is manifested from.

This dynamic elongated cylindrical plasma once in motion due to its new shape it can penetrate and move faster in its environment as it has less frontal interface and creates a lesser friction as if it was spherical in shape, this allowing faster speed to be attained by the plasma of the light in transit from one matter mafs environment to another irrespective of the plasma matter mafs of the light being in the principal mafs, transition mafs or matter mafs mediums pmf strength environment.



Fig.1 The schematic mafs of the matters components' of the light

This internally dynamic cylindrical plasma of the light in its motion creates friction between itself and the Magravs of its environment, which this friction at the point of their interaction and due to friction of the two pmf Magravs at this point of interface releases plasmatic magnetic fields, which are in the man's protein pmf strength detectable magnetic spectrum. Through biological structure of the humans protein pmfs strength visionary sensors' which can detect this interface interaction pmf strength then these sensors become aware of different pmf strength, its position and condition and this information is passed to the brain, where this method of interface interaction of two Magravs of the rays of the light and the protein has become the method for man to be aware of his physical surrounding in his environment pmf strength and the man has called this matter interaction conditioned wave length the light ray.

The light ray in its interaction with the surrounding magnetic fields in their environment leads to creation of magnetic field in range to man visible light according to the human protein pmf strength of the universal Magravs spectrum, where the shine or the visibility of the light observed become and it is at the boundary of the magnetosphere of the plasma of the light.

The structure of this dynamic cylindrical plasma of the light ray, which creates its own Magravs, is initially consisted of, in the centre, the content of mafs of the principal matter, then the next layer to the principal mafs is the mafs of the transition matter and then the layer surrounding this, is the matter mafs strength magnetic fields components of the light.



Fig. 2 The mafs of the matters components' of the light

These dynamic plasmatic magnetic fields due to their proximity to each other, they have to interact with each other as all magnetic fields in close proximity with each other do and by the same universal principle laws of physics these magnetic interactions leads to creation of gravity (1) and creation of Magnetic fields within and around this dynamic cylindrical plasma, where these magnetic fields interactions leads to creation of internal and inward magnetically initiated gravitational fields force of the light and the outbound Magnetic fields forces of the light. Therefore due to interaction of different constituent magnetic fields of different mafs' of the matters of the light, the light must create and does possess its own Magnetic and gravitational fields, and due to the interaction of these two plasmas of the fields of the gravity and Magnetic fields, this leading to creation of the mass and the magnetosphere of the ray of light (1).

Hence the light by natural laws of magnetism possesses mass and magnetosphere and similarly not all lights have the same mass and by the same laws and principles lights of different intensity and lights which can travel longer distances possess a larger mass. Where, their mass is primarily dictated by the strength of the pmf of mafs of the principal mafs of the light components'.

The interaction of the mass of the light and the environment of the medium that the light is traveling through, then the light acquires weight in respect to its given environment fields strength.

The mass of the light has different weights according to the gravitational environment which it is passing through or being produced or arrive at. In understanding the construction of the ray of the light then the mass of the light has to be measured along its total length and not across its width.

Most rays of light possess anticlockwise spiral longitudinal rotational motion for their constituent fields and not spherical rotation of the fields as for example in spherical dynamic entities the like of plasma of the proton.

Rays of light as in the case of matter plasma of protons the light rays mainly possesses and maintains a clockwise directional motion.

Due to composite structure of the light's mafs, if one looks' at the cross-section of the light (Fig. 3), one should be able to observe a tighter magnetic fields strength region of the principal mafs in the centre, leading to creation of the strong light in the principal spectrum level and stronger gravitational fields of this sections' structure that creates its own magnetosphere region, then this section is covered with the transition mafs region structure of the light, and then when the transitions mafs have reduced in their strength, then they become in the level of the matter mafs strength and at this zone the matter mafs and matter of the light are established and maintained (Fig. 3).



Fig. 3 The cross section of the ray of light

The lights' structure is similar to the structure of inner sanctum of the Sun and principal star in the centre of the galaxies, where for example the Principal Star takes its position in the centre of the galaxy and due to its higher inner magnetic field's strength of the principal star, this creates what appears as the principal stars strong gravitational field forces that all matters around it are pulled inward and at the same directional motion of the galaxy is set by their principal star too, where simultaneous this central matter radiates outward its own light in the principal mafs strength (3 and 4).

The straight helixal cylindrical shape of the light ray has polarities the same as any straight solid magnet, where the outer magnetic fields lines of the light ray converge inwards and the inner magnetic lines of fields diverge outwards, this creating an inward (South-Pole) and outward (North-Pole) directional motion of fields (Fig. 4).



Fig. 4 The polarity of the ray of light

Due to the structure of magnetic fields of the light, it can be said that the matter mafs fields components of the light will be interacting and be attracted and drawn inwards' through the centre of the structure of light's magnetic fields at the ends of their pmf length (South -Pole of the light) and then as they go through or in proximity of the mafs of the principal mafs of the light in the centre they absorb some of the pmf, which has been unwinded by the mafs of the principal mafs fields and then these matter mafs fields, now energized, then due to their rapid motion are ejected and appearing from the other end (North-Pole) of the light ray.

This inward revolving motional central rotation of the outer matter mafs fields at the same time gives the light its property of high speed forward motion, where the conversion and the overall and total gravitational field strength and the helixial cylindrical rotation of Magnetic fields of the lights' principal mafs' dictates the length of the light ray and hence where the beginning and the end of the light ray would be.

This process of matter of light going inwards and then ejecting from other point, is very much like the process what some consider as the imaginary phenomenon commonly called and known as a wormhole principle. The continues rotation of the mafs of the matter's fields concaving-in and will go through the inner Principal Star like system of fields in the centre of the ray and then the pmf of the mafs of the matters emerges from the opposite-end as it has entered with new and higher pmf strength.



Fig. 5 The first conversion. The spherical plasma structure converts to the cylindrical plasma structure of the light (The first metamorphoses of the light)

When, the spherical plasma first changes to cylindrical plasma that is the point when the ray of light is created and becomes straight line directional in motion entity, and the spherical entity goes through the first metamorphoses (Fig. 5).

Then as and when this dynamic cylindrical entity reach's its destination point, this being of any mafs or matters plasmatic fields strength environment, then at the point of arrival then this cylindrical entity goes through the second metamorphoses and reverts back and spherical rotational fields entity (Fig. 6).



Fig. 6 The second conversion. The cylindrical plasma structure of Light converts back to a spherical plasma structure (The second metamorphoses of the light)

Where, the plasma of the light gets gravitated and absorbed then it takes the shape of the matters in the target entity environment as the content matter of the plasma of the lights gets added to the plasma of the target environment and the target entity receives an additional dynamic plasmatic magnetic field of all mafs of the matters of the light or what is called the target plasma receives an additional energy from the plasma of the light.

Therefore the plasma of the matter to hold on to its maximum pmfs and transfer its pmfs from one point in the universe to another as fast as possible, then the plasma of mafs uses and goes through double metamorphoses process of spherical to cylindrical and then to spherical entity (Fig. 7).

In reality the light ray due to its mass possesses momentum rather than light being a ray which only transfers' it magnetic fields and energy upon interaction with other entities in the universe.

Therefore, IFF the light was a ray and not a plasma composite of different mafs strength, then only one of the matters' mafs of the plasma of the targeted entity would increase in mass and this creates unbalance in the inner structure of the targeted plasma and only in that matter's content, which in the case of the matter environment this energy is so low compared to the principal mafs contents' of the targeted plasma, that this increase in matter pmf would not have shown any increase in its content and increase in the energy as the whole.



Fig. 7 The double conversion of the plasma from spherical to cylindrical, and on its arrival back to spherical plasma entity
(The double metamorphoses process of the plasma of the mafs)

But as the light transfers all its mafs of all its matters content to the targeted plasma, then the whole pmfs matters of the plasma of the target plasma increases and then the whole plasma shows signs of increase in the plasma content and for example the whole atom structure gets energised.

This being the like of when plasma of an atom receives injection of a ray of light that the whole proton and electron gets excited and energized and not only the matter components of the plasma (note: the term plasma of an atom as the whole structure of an atom including its neutron, proton and electron create its own magnetosphere and it can be considered as one plasma containing plasmas of these particles). Where, the electron due to its lesser mass shows a more rapid motion and excitation, whereas the plasma of the nucleus absorbs most of the light mafs and adds this to its total mass of all its matters.
If! The protons of the nucleus magnetosphere are measured before and after interaction of the light with its atoms magnetosphere, then it can be observed that there is a marked increase in the magnetosphere size of the plasma of the proton too, this indicating that the whole atom absorbs all matters mafs of the light and not only the plasma of the electron, which moves and takes new position in respect to the protons Magravs.

In comparison, in earth condition as meteoroids enters its magnetospheric zone, the facing side of the meteoroid on entry into pmf of the earth, its interface surface matter curves' backward, where the same happens in the case of dynamic plasma of the light in entry into a new pmf strength environment, then the same types of curvature and convergence of the mafs of outer matter mafs layer of the light due to the speed of the transition and obstruction and friction of the new environment, then the outer mafs of the light take their position on the outer layer and the rest of the mafs of other matters' of the light follow the same process and take their position within the new plasma and the cylindrical structure of the light converts into spherical plasma and hence the light converts into a tangible spherical matter, and all its matters content fuses and amalgamates with all matters of the same in the new target plasma environment (Fig. 6).

The reversal of the helixal motion and cylindrical plasma of the light to spherical and rotational mode of matter is entirely dependent on and due to the environmental plasmatic magnetic fields strength, which the light arrives at and it is dependent on the tightness or strength of the magnetic fields of the destination environment.

In this process pmf traveling from one point to another in the universe, as the fields of the mafs of the transition matters have faster speeds than the matter mafs fields of the light then, when the light arrives at the point of its destination, where is to release and converts its fields to the given environments' of other plasmas, then the conversion in the matter mafs to matter fields strength leads to creation or release of plasmatic fields in the soft x-ray which is the essence of creation of life (6) and other magnetic fields strength of magnetic spectrum levels.

In the matter environment the slowing down from the principal mafs components of the ray to matter mafs fields strength leads to release of magnetic fields plasmas in the gamma rays strength levels and similarly the beta plasmatic magnetic fields strength is due to fields strength from principal mafs to mafs of the transition matter and transition matter mafs to matter mafs and matter pmf strength this become to release alpha rays in the magnetic field spectrum.

The production of gamma ray through such similar process can be observed, when the star in the supernova state releases gamma burst, where this gamma burst is due to the rapid expansion of the principal mafs of the star converting into the matter mafs magnetic field strength or the rate of the change of the principal maf to matter and matter maf leads to release of gamma rays.

As the matter mafs composition and the construction of the plasma of the electron has been understood to be of the same as the plasma of the proton and neutron (1), then gamma rays are and can be produced by the mafs of the matters of electron the same way as done by the neutron or protons, when and where the right condition for the release of the fields strength equal to the gamma rays are made available for this ray pmf strength to be released. Where these rays released by the electron can appear in the inner structure of the plasma of the protons of the nucleus and be manifest as the incoming and mysterious energies which are moving within the plasma of proton or neutron and their source unknown.

There are lights rays which are created by the electron in the same process of spherical to cylindrical structure conversion between the pmf of the electrons and the proton or an atom.

It has been explained (2) that there is current of magnetic fields flowing within the different mafs of the matters magnetic fields strength of any plasma as it does between the plasmas themselves. Where the current of magnetic fluxes in the case of the light rays is in the light plasma magnetic fields strength and not electron levels of magnetic fields strength of the spectrum of the magnetic fields, when magnetic fields moving from one matter mafs to another within the layers of the mafs of the matters of the light. This current of pmf within the mafs of the matters' of the light is to be called the **light Magnetism**, "***ligmagnetism***" instead of electromagnetism as their mass of the mafs are totally in different scale of measurement.

It has to be said that as there are electromagnetic fields so there are *protomagnetic* field as well in the operation of universe, these are a more powerful current follow of magnetic fields package, which the world of science is not so much aware of these at the present, but in the construction of space reactors for the future of space technology the use of protomagnetic fields and their currents are much easier systems to produce and this gives opportunities for the development and production of a much smaller but more powerful by factor of several orders of magnitude than electromagnetic based plasma space reactors, where huge masses can be lifted with few grams of fuel. This concept of light to neutron and lift and motion is the main corner stone of knowledge and principle that allows the stars to create such a powerful gravitational and Magnetic fields, which the scientific world at the moment has not understood as of yet and has been entangled in the smaller component of the atom, rather than understanding the real power house of the atom and utilise this for their benefit to achieve some wonderful and interesting results.

The pmf current within the mafs of the matters of light structure magnetic field in strength has a different spectrum due to its length and rotational motion than the electromagnetism measurement. This ligmagnetisem has more powerful current flow and by size have stronger field's strength as it has more field contents in the principal mafs fields' spectrum than the electromagnetism which is in matter fields' strength spectrum.

Electromagnetism or electromagnetic flow (2) is said to be the electron magnetic fields strength equal to the strength of the magnetic fields of the plasma of an electron and the current is explained as the rate of the flow of the magnetic fields from one magnetic field strength to another (1 and 2).



Fig. 8 Conversion of the ray of light into the fundamental plasma
or what is known as neutron

In most cases when the lights have enough mixture of mafs of different strength, these rays upon their arrival to a given environment, they directly convert into the complex plasma of fundamental plasma or what is known as the plasma of neutron (Fig. 8)(1).

At the same time collection of smaller and fragments of lights plasmatic magnetic fields upon arrives at the point of destination, due to the vacuum level of the environment go through the process of accretion and they create or lead to creation of the fundamental plasma (neutron) in their new environment.

In cases the light ray carries more mass contents of all three mafs of matters compared to the its environmental mafs need for production of fundamental plasma in this new environment, then in these cases the large in mass light rays has enough mass of mafs that the light ray in this new environment goes directly into the structure of the fundamental atom or what is known as atom of hydrogen, that once this ray. That is to say in certain conditions, the structure of atom is due to total conversion of the light rays components and the ray of the light does not go through neutron decay conversion (1) for the light to become an atom (Fig. 9).



Fig. 9 Production of an atom direct from the ray of light

Some light rays due to their internal dynamism and different mafs strength in their structure, these lights rays create and contain entities moving internally and these internal structures keep the plasma of the lights' mafs in order and under control. These internal entities are the like of the electrons, which are externally positioned in the overall structure of the atom, these internal entities have specific position and purpose and they mostly convert to electrons' of the plasma of an atom in given specific conditions once the plasma of the light converts into matter of an atom, where with this process there is no conversion into neutron and then the nuclear decay of the neutron that leads to creation atom, in this process the light converts directly into atomic structure in one step. These internal entities are usually observed in the lower order environment medium which the light is traveling through, where the low speed of the entry of the outer layers fields, in-going through the faster speed principal mafs, these create small vortexes between the two fields in the transition mafs environment of the palms of the light, which these vortexes start operating independently and gradually fiend a fix position in the internal structure of the plasma of the light and when the light transfers to structure of an atom, these mafs entrapped in these vortexes become the electron of the matter of the atom (Fig. 10A).



Fig. 10A The conversion of light containing vortexes into the structure of an atom direct.

The reason why the plasma of the light takes the spiral helixial cylindrical motion and shape is simply due to the fact that plasmas' with this type of structure does not have a need for additional external plasma(s) around them for coherence and a balanced plasma the like of electron in the spherical plasma structures of an atom.

In principle rays of light get their strength from their inner plasma of the principal mafs' strength rather than any other part. This being the reason, ***why light look as to be an energy rather than entity with the mass***. Therefore the light is a composite of plasmatic magnetic fields of different mafs of the matters fields' strength and **light is not a single magnetic field structure**.

The lack of understanding of the structure of the light and the inability in scientific world to be able to split the structure of the inner components of a light ray has led the scientific world to consider the light rays as an energy rather than a dynamic structural plasma as of the same as the electron or proton.



Fig. 10B Ray of light travelling through and interacting with outer mafs and initial fundamental particles of pmfs.

Due to the cylindrical structure of the light plasmatic magnetic fields and their interactions, light has the wonderful capability to be able to change its outer mafs cover as/and depending upon the matter mafs or matter medium that it is traveling through or where it arrives at.

In choosing and using helixial cylindrical motion the light does away with the need for external rotating plasmas like as the electron(s) with the atomic and planets with solar system.

This, meaning that all rotational spherical objects the like of the solar systems and atoms need to have two or more parts that their centrifugal magnetic forces can keep their matters and mafs content of dynamic magnetic fields in an encircled and enclosed loop for them not to lose too much of their magnetic fields through leakage to other plasmas in their environment.

In reality helixial cylindrical rotation partially can be seen in structure of some of galaxial structures too, primarily due to this phenomenon.

Where, for faster and simpler speed, the layers can move inside-out and vice-versa according the mediums' magnetic fields strength of the environment of travel. This meaning that due to dynamic cylindrical helixial motional and composite matters mafs structure of the light, the mafs of the transition matter plasmatic magnetic fields can become and take its position on the outer shell of the light rays in a mafs of the transition matter mafs and medium strength and similarly the principal mafs components of the light can take their place on the outer fields layers' of the light rays in principal mafs and matter fields strength environment.

The light is energized from the central magnetic fields strength region of its structure in a matter medium and this being the reason why the light seems to be able to travel long distances and behave as energy and not an entity. This change of cover allows less losses' of the mafs of all matters of the light ray due to friction in any medium magnetic field strength.

Now it becomes clear, how and why spherical rotational shape of the movement of the dynamic plasmatic magnetic fields leads to creation of matters and at the same time longitudinal cylindrical helixial rotation of the same dynamic plasmatic magnetic fields lead to creation of light rays. Therefore the method of transport of pmf and Magravs in space is through the Light Magravs, where at the point of interaction and slowing down the lights' pmfs are transformed and transferred to matters fields strength of plasma of the new environment.

Hence, in the universe mafs of the matters are transferred and transported through the mechanism and the use of plasma of the light and when for example the Magravs of the light reaches matter environment it becomes and slowed down enough to reach's all content matters Magravs strength levels, then what is released in by the light pmf, this surplus or released pmf then becomes the pmf which targeted pmf receives as addition pmf or what is commonly called ***it receives energy from the*** pmf of ***the light***.

When, the light ray reaches the principal matter environment then its principal mafs pmf will have the same interaction as delivery to its given environment as mafs of matter have in the matter environment.

The reason matters can feel forces of rays of light are primarily due to the momentum of the motion of the mass of the light itself and not through absorption of its energy.

In the solar-sail transportation the motion of these would not be due to energy of rays of light absorbed by the sail, but in real term the created motion is due to the motion of the mass of the light and its momentum that once it comes to rest at the point of interaction with the material of the sail, the light transfers its momentum to the fabric of the sails' matters and hence the increase in the momentum of the sail and hence the motion of the sail.

It is essential to realize that as there are gamma rays, beta, and alpha rays and so on in the matter world so do the same types of rays of the same in equivalent and in proportion in strength exist in the environments of the Transition and the Principal Matters too.

Therefore one has equivalents' of the gamma ray in the principal mafs environment and the same as x-ray in the mafs of the transition matter environment in magnetic fields strength too. This meaning that the sub-division and spectrum of pmf strength of the light is not the exclusivity of the matter environment only and it has parallels' in other matters' pmf strength environments.

At the same time the interaction of the Magravs of the lights surrounding with Magravs of the light leads to release of magnetic wave's rays in the visible light spectrum in these matter mafs environments depends up on the observes pmf strength visibly tools of observation.

The inter matter's mafs cover exchangeability of the light rays is the reason why light has the capability to travel long distances in mafs of the transition matter environment of the universe, as the similar in strength mafs of the transition matters creates no loses or interactions in this level that can lead to minimum losses of light's plasmatic magnetic fields and its strength. The reason being that visible light is only released, when two different Magravs in strength collide and not when two pmf of the same interact or very little pmf are released in these compatible pmf strength entities and environments encounters as in the interaction of the similar pmf lead to and creates very little friction between the pmfs of the light and the environment and hence these interactions releases very little light and this being the reason why in the universe, the interaction of the transition mafs of the light rays with the transition matters of the universe creates very little light or a dark light or what can be called the Transition Translucent light (1) and not a bright visible light, when one looks into the deep cosmos.

The invisibility of travel path of the ray of light through the deep space is in fact ***due to its***

capability to change its outer layers according to the environment that it travels through.

That is to say as the light goes through the Transition fields regions of the universe, then the transition mafs and matters of the light will come to take their position on the outer layer of the ray, then through this process less pmf are used in interaction with these fields and matters and hence less friction and less loses of mafs of the light, and in these interactions there are very little loses through the Magravs of the mafs of the transition mafs of the light, these faint lights produced in the interaction of light's outer mafs of its transition matter and of the same and/or transition matters in the universe, where these very few interfaces of the collision between the light and the environment Magravs gives the universe a dark but translucent effect that one can see through the universe. In a way this interaction of lights' transition mafs and universe's transition mafs is the cause and the reason for the invisible transparent structure which allows the production of universes discreet light that one can see through this universe but blocks opportunity that one cannot see the lights from and the universes outside this universe (3).

It can be said that the light due to its interaction and helixial rotational characteristics is like a **chameleon** and ***it has the ability to changes its cover matter and mafs according to its environmental Magravs strength***, which it travels though and when and where the fields strength changes are too great then the light changes its cylindrical to spherical shape structure and its outer skin matter and mafs take's strength of its environment mafs or the matters' plasmatic magnetic field strength. Or it can be said that the light has **surface** Magravs strength matching characteristics and capabilities. As the Magravs of the light reaches or tries to enter another spherical Magravs or cylindrical Magravs then part of the released Magravs due to friction of two Magravs with each other lead to transfer of pmf to spherical pmf and release of some pmf in the form of magnetic rays' strength spectrum.

The light as it enters or comes in contact with plasmatic magnetic environment the likes of the earth, then the interaction of their two dynamic cylindrical and spherical Magravs creates fragments of plasmatic magnetic fields that are in the range of the man's protein Magravs strength that to man's sensory detection tool called the eyes can recognise the interface of the interaction of the two Magravs as the visible light.

In reality the light is created and operates through and from different pmfs strength and it is not as simple as an energy as if one define the true meaning of the energy, which is "the plasmatic magnetic fields (pmf) is motion" (1), then taking the motion or speed of the ray of light's movement in a different matters and mafs environment then one can see that the light in truth is no one magnetic ray but it is made of a complex plasmatic magnetic fields of different strength.

Whereas, in the light's principal mafs (3) the stronger and tighter of its fields seats in the centre of the structure (Fig.1) and as this mafs of the matters field's unwinds, these newly made available which are lower in strength and are going from one strength to another, then these mafs in motion to be known as ***transition energy*** (dark energy) and when these mafs slow down enough to their transition matter and mafs environmental strength, then these appear as mafs of the transition matters (dark matter), and then when the transition mafs pmf strength reduces or unwinds enough that this mafs reach's the matter mafs pmf strength levels environment then it become tangible or detectable the matter at this strength (Fig. 11).



Fig. 11 The magnetic field structure of the plasma of the light

Where, the visibility of the light at this point the like as in the earth and human body, then this light is human protein chain mafs strength dependent, then it became visible light to the human eye in the Magravs strength of the planet gravitational field strength and then the light appears in matter pmfs strength and as tangible or detectable matter.

Light in its visibility and tangibility has different strength and what is visible light in one matter mafs and matter environment strength, this it is not necessarily visible and tangible matter mafs and matter's pmf strength in another environment and vice-versa. The visibility of the light or its transparency is ***environment and target magnetic field strength dependent.***

The structure of the light prevail that in general in matter environments the stronger or the principal fields take its position that as it unwinds it become the source of the magnetic fields to the lower field's strength and it can be divided into the lower field's strength of the plasmatic and magnetic fields.

At the same time the tightness of the fields of the mafs of the principal matters and their content of the principle fields in their interactions with other principal strength fields of the same strength mafs and matters creates visibility in their level of strength too that these lights are not visible for example in matter mafs or matter environment to human eyes even though in the matter environment the existence of the principal fields and mafs of the matters can be felt or even their affects can be seen.

It has to be said that if the light was not in possession of its own Magravs, the light would have been attracted and absorbed into and by the first magnetic fields or the first object in possession of Magravs in its travel in the universe, whereas the light being in possession of its own Magravs (the dotted line around the mafs of the light in the figure 11) (1) this allows the light to find its position according to its Magravs strength in respect to other objects Magravs and magnetic fields in the universe and this giving the light the ability to travel the length of the universe without being absorbed into or by other objects Magravs and magnetic fields. Thus the light has the ability to establish and maintain its own Magravs positioning criterion in respect to other entities in its environment.

The light rays with higher mass of the mafs of the principal matters, these rays can travel further in space compared with rays of lower mass. Therefore what one can observe as light from far corners of the universe in general these are some of the lights which possess the more mass of the mafs of the principal matters at the point of their inception, as the rays with lower mass have already been absorbed by the other entities in the universe over the life of the universe from the time that these rays were created and have been in travel in cosmos that they could not be observed by man at this point in the life of this universe.

The light observed from far corners of the universe are some of and not all the lights from the whole of the universal light from the point of creation of this universe as most lights by now have interacted and been absorbed or are interacting and getting absorbed by the other fields in the universe, then this can indicate that lights of lower mafs of the principal matters strength and content of principal matters from the origin of the time of the birth of this universe have mostly already been absorbed or been attracted by other pmf and entities in the universe.

The absorption of different rays of light in the universe are environmental dependent and it can be said that the lower mafs strength of the principal matters of the mass of a light ray can become the **seeds of neutrons** or it can be said that the principal mafs of the light as it arrives in a matter magnetic fields strength environment, then this principal mafs of pmf of the light becomes dynamically spherical in structure and then become the seed of the creation of neutron. Hence one can understand how energies which are defined as "the plasmatic magnetic field in motion" convert to matter in a given Magravs environment. Where, each mafs of the matters field's strength components of the light then can become in its arrival at a given environment the seed of one of the components of mafs of the matters of different plasmas too.
Therefore it can be said that the initial seeds of the creation are in motion in the universe at all levels and all time and once they reach given an appropriate environment mafs pmf strength, then in that environment depending on theirs plasmatic magnetic fields strength and the given environment plasmatic magnetic fields strength then light rays manifest themselves or can become tangible and detectable in that environment.

For example the light which has the plasmatic magnetic fields strength of a neutron then can upon its arrival in a given environment changes to a tangible and detectable neutron and then through the losses of some of its magnetic fields to its environment this neutron goes through the nuclear decay (1), which this lead to creation of plasma of an electron and a proton and the light ray becomes the seed of the fundamental atom (1) or the atom of the hydrogen in matter environment plasmatic magnetic fields strength of for example of the Earth.

Thus; "the present assumptions that the first atoms in the universe were created when the universe cooled, **this theory is not and cannot be correct** and in reality atoms are created through change in the plasmatic fields strength of the mafs of the light, secondly at the point of creation of the universe, the universe was not hot and there were never high temperatures that the cooling of the universe has led to creation of the first atoms as presently commonly stated. The first atoms and universally all first atoms' the like the atom of hydrogen in all mafs strength in the universe ***are created through the magnetic field strength reduction*** and through no other means.



Fig. 12 The universe heat distribution map (W-MAP of the universe)

This concept of creation of heat and high temperatures at the birth of the universe is not observed in the plasmas of electron and proton, when the plasma of neutron decays and divides into an atomic structure, and in the universe there are always continuity and parallels, thus the universe has never been hot that has cooled down to create atoms, and this is the reason why W-MAP (8) shows present balance heat distribution of the universe (Fig.12).

In truth the current assumptions of initial heating of the universe at time of its birth cannot be true as the initial atoms of the universe and presently atoms were and are created from the original principal mafs strength which radiated out as principal lights rays of the universe in the centre of the universe and the initial atoms and matters of this universe were not created through cooling of the universe at the point of inception of this universe, which this universe itself is created from the decay and division of bigger mass of another universe as it happens in the division and decay of plasma of neutron to plasmas of proton and electron (3). One does not observe heating in the plasma of electron or proton in this division and so be it the same when the bigger universe divided and led to creation of this universe of the humans (3).

In fact, if! The universe was created by the present scientific assumption then the WMAP should have shown cooler region in its outer boundaries than the present near homogenous heat distribution which has been physical observed and from collated data by the publishers of the universal heat distribution map of the universe.

The heat distribution and the heat concentration on the central line of the WMAP confirms that the universe started from a central line in the middle and as the principal mafs of the universe unwinds then the transition mafs and the matter mafs were released and as were spreading outwards into the space of a larger universe (Fig. 13), then as the Magravs of the principal mafs in the central line region are converted and are reducing, then the overall unified oval-spherical shape explanation of the WMAP come to exist, and then as the total margrave of the central principal matters reach a point where they cannot hold on to all the mafs and matter expansion of the universal-magnetosphere, then at this point the universe will go through a division and all the matters and mafs at this point rearranged and regroup as and in the principal strength mafs and the universe then divides into two principal mafs of lesser masses of universes, which these new universe are magnetically interconnected and then these new universe go through the same principle of the principal light unwinding and the same process as creation of new universe carries as before (3).



Original WMAP-image from commons.wikimedia.com

Fig. 13 The microwave heat distribution of the universe shows a concentrated heat in the centre disk of the universe

That is to say that the principal matters are the way that universes divided and arrive form another universe and as the light in the principal mafs strength unwinds' in its new environment then the new envelop of the new universe starts to be created (3). The same process occurs when the neutron decays and divides into the plasma of the proton and electron.

Thus, the universe is not created as a big-ball of fire which has been cooling down as has been promoted, but in fact the universe is created the like of as an ejected principal mafs is injected into new a universe environment and as the principal mafs radiate outward as light of stronger mafs, then they create the other matters mafs and matters depending on the given pmtics strength of a given region in the larger process of this unwinding of the principal maf and matters and its lights (3) in this new expanding universe.

Therefore this universe is in fact created inside out than what has been assumed up to now that as it cools down to what it is, which this explains why even the universe is observed to be expanding, as the reason for expansion of the universe is being due to the presence of principal mafs in the centre of the universe and as principal lights of the principal mafs radiate outward, these light rays of the principal mafs while traveling in their new environment they reduce in strength and this creates new matter mafs and matters according to given environments magnetic fields strength and in a given point pmtics hence the creation of new mafs and matters and so forth, which this leads to creation of atoms and molecules and stars and so forth.
Thus there has never been a big-bang and the current appearance of the expansion of the universe is due to the principal maf which as unwinds it creates the sphere of this universe (3).

This method of the creation of the universe now explains' why there is a central gravitational matter concentration in the universe as this pull is centred in the dynamic central line of the injected principal maf of the universe at the time of its inception, which this can be seen as the red line in the W-MAP (Fig.13), which the more concentration of the mass of the principal matter seats in the central disk of the W-MAP and as these principal mafs create their own magnetic interactions, hence these create their own gravitational and Magnetic fields of their own and thus the central gravitational of the universe is in the centre of the denser point of principal mafs of the centre universal heliosphere of this universe is created and solving the present mystery in scientific world that, where the gravitational pulls of the universe come from.

This is how even the plasma of the neutron decays and divides into plasma of the proton and electron too, where the matters mafs of different quantities and masses of different strength from neutron are divided and injected in the new area in their environment, where the original in their overall Magravs of all their mafs as original components concurrently maintained that the plasma of the electron and proton(Fig. 14) and then as the matter mafs ***unwind*** and interact they reach given Magravs level and position ***that new plasmas of the sub-components of the atom are created***.

Where this process of division due to micro -level of masses involved it appears as an instantaneous process of creation of proton and electron.



Fig. 14A The conversion of the plasma of neutron to plasmas of the electron and proton
The same process is considered to occur when the universe divides (3).

This being the reason why the proton does not get heated as a big-bang theory suggests but as portion of principal mafs of the neutron which become part of the plasma of the proton **expand centrally** and as the principal maf unwind to the transition matter and matter maf of the plasma of the proton and all other fragment of pmtics and magnetic fields, hence the protons' plasma is created from the division of the principal plasma and the fragments of the fields as different constituent mafs, matters and fields in the plasma of the proton.

The structure of the plasma can be compared to ***the winding spring of a mechanical clock***, were as the main spring is winded up using a key and then as it unwinds.

Where as the winded spring is *tighten in the centre* this tightened spring becomes like the ***principal matter*** of the plasma, a compact entity full of energy in the centre (figure 14b-1) and as the spring unwinds it releases its magnetic fields in lower strength that this unwinding of the fields and reduction in their strength further down the line of unwinding of the spring becomes the magnetic field strength in the ***transition*** (dark matter) ***field strength*** (Fig 14b-2).


PRINCIPAL MAF's
14B-1
TRANSITION MAF's
14B-2
gamma rays
X- rays
visual light
matter
lower matter
MATTER MAF's
14B-3

Fig. 14B The visualization of the universal spectrum of magnetic fields.

Further as the magnetic field strength and as this field opens up in it's environment and slows down and reduces in strength, these fields in this region become in the visible light and lower magnetic fields strength in the unwinding cycle of the principal magnetic fields reaches the ***matter*** magnetic field strength (Fig 14b-3) and further on this field reduces in strength to even lower fields strength magnetic fields.


gamma rays
X- rays
visual light
matter
lower matter
UNIVERSAL MAGNETIC FIELD SPECTRUM
14C

Fig. 14C The visualization of the universal magnetic field spectrum.

Then as one puts the whole magnetic fields spectrum of the principal mafs, transition mafs and the matter magnetic fields as one continuous magnetic field strength spring or then the true sense of the unifying magnetic field spectrum which connects all creation of fields and matters as can be observed in the universe, that this can be called the universal magnetic field spectrum (Fig 14C).



Fig. 14D The universal plasma magnetic fields structure

Where in the plasma of a proton for example, as the fields unwind and divide in the lower scale of the maf strength these lower fields as themselves unwind they interact with other fragments of the fields of the same in the Magravs of the principals matters of the plasma and hence they create the division and sub fields which one observes within the structure of the plasma, these being like what they call quarks and bosons and so forth. Where this total interaction within the capture zone of the Magravs of all the fields is called the universal plasma magnetic fields structure 14D.

The same process can happen with the ray of the light originated from principal mafs strength (what is called the principal light), when this principal light arrives in the principal mafs strength environment and hence the first fundamental principal atoms' can be created in that given environment through the same principle as principal atoms are created in the principal matter environment (1).

In reality: if! one could follow and observe the rays of the light which arrives at the boundary of the heliosphere of a solar system, one should be able to observe that some of these light rays of varying in mafs strength, which can reach this point in the Oort clouds region, these due to the balancing of their pmf and their environment vacuum condition and mafs strength, then these light rays individually or as collection of fields will become particles, plasmas of neutron, atoms and matters, and over the life of the solar system then they rain inward towards planets and the star of the solar system (Fig. 15)(4).

These light's rays which have slowed down in the Oort clouds layers or other inner sectors of the solar system can and do become as neutrons or other particles, then some of these become like of what is commonly known as neutrinos and get attracted back to the star.



Fig. 15 Conversion of the light ray to neutron, atoms and gans in the Oort cloud

Thus as the stars of solar systems through their light emission continuously feeds their planets and moons with light rays in form of heat and further the sae light rays in slowing down in form of matter, then the same principle continues as the solar systems themselves get feed by the principal stars in the galaxies through their principle lights which these lights at the moment due to the man's lack scientific tools these lights have been invisible for detection to the man of science.

The neutrinos are on the other hand produced by and through the same process from the fragments of principal mafs of the light rays of the Sun or the principal matters in the centre of the earth inner cores too. At the same time and by the same measure neutrinos, which are released by the principal matters and mafs content of the inner-inner core of the earth which are detectable leaving the earth surface their existence and the exit from the surface of the earth is the confirmation of the presence of the principal matters and principal mafs in matter environment of the cores of the earth, as the light emitted by these principal entities lose their pmf strength within the centre cores of the earth (4) and as they move outward from the centre of the planet they appear as neutrinos exiting the earth surface.

Some of these light rays due to their Magravs strength get attracted and in a process known as the fusion of light rays and produce the initial molecules of the matters in the solar system too.

In understanding the concept that lights' rays from the Sun converts into atoms and molecules, then this make obsolete the theory that the ice particles left from the time of the creation of the solar system are the ones observed in the Oort clouds, the Kuiper belt, in the rings of the Saturn and so forth in the solar system.

That is to say most and even all matters in the solar system like the fuzzy material in the Oort clouds layers are mainly the product of the slowing down of the light rays of the star of the system and not the hypothetic present assumption that the meteoroids and all particles in the outer edges of the heliosphere of this solar systems are the residual materials from time of the creation of the star and the solar system.

This recycling of the light rays and production of for example particles is comparable and it is in fact the same process as one observes in systems which have dynamic magnetosphere the like of the earth, where the molecules of the vapours of water rise-up to upper and further regions of the earth magnetosphere and when they reach a given temperature and environmental condition then they gather and when they are heavy and enough of these entities then they rain down on the earth. This is the exact process as it happens with light rays of the Sun as these rays reach to the outer boundaries of the solar system in this process due to magnetic field strength difference instead of temperature difference as in a planetary system, they slow down and become matter mafs and matters and then they rain back towards their star due to its magnetic field interaction and gravitational field strength (4).

In attraction and motion of these lighter atoms and molecules solar winds in the outer region of the solar system are created and as they move in the Kuiper belt of the solar system these matters become part of the constituent matters of the outer giant planets and these light rays become part of and the creators of comets, asteroids and meteoroids as different densities of matters are released and created in this process and collected in these so called belts of the solar system.

Where, the existence of the meteoroids and their pattern of motion confirms the change of the mass of the light to the molecules of gans of the hydrogen as these comets and meteoroids go back in the Oort clouds layers, then meteoroids attract the newly produced molecules of the hydrogen and oxygen and at the same time they carry on mixing the soup of the Oort clouds matters(Fig. 16), this leading to collisions of new produced gas and gans of matters needed for the production of heavier matters and molecules like water in the solar system.

In reality the light rays becoming part of comets and meteoroids, these themselves become like a mixing spoon of the solar system and the cause of the mixing and displacement of the matter mafs and matters needed for having an active and dynamic matter environment in all parts of the solar system.



Fig. 16 The light rays become water molecules and get attached to comets and meteoroids and then return back into the inner parts of the solar system.

Therefore the reason, why giant planets exist and possess most of the gasses at the outer boundaries of the solar system, this is due to the fact that these gas planets *continuously absorb all the freshly* *atoms and the molecules of the gasses and gans* which are produced by the ***transformation of the light rays to these atoms***, and hence these gas and gans atoms and molecules get gravitated and pulled around and held or get captured by gravitational, Magnetic fields and get positioned, for example, ***in the rings*** of giant gas planets according to these ice **gans** particles Magravs strength and Magravs positioning.

The collection of ice particles and solids in different rings in the planetary or solar system is primarily due to magnetic fields of static inertia of these objects the like of asteroids and on the other hand due to and Magravs positioning through the Magravs of the gans matters their interaction with the planet or solar system Magravs strength and due to their of these planet's fields nearest to the Kuiper belt and Oort clouds.

Thus, light rays of the star are the feeder of the star, planets, meteoroids and asteroid as they rain back inwards into the star heliosphere over time as the Star's strong gravitational fields pulls' every matter and matter mafs in its system back to itself.

Therefore the light emitted by the star partially become the sources of the materials which are returned to the star matter for it to carry on with its everlasting existence.

Chapter 3

The conversion of light rays to the Gans of the matter

Considering the transition of the light into matter in the outer boundaries in the Oort clouds environment of the heliosphere of the Sun, there is a further process which occurs to these newly created tangible mafs from light rays of the Sun as these newly born neutron goes through its nuclear decay (1) and become an elementary atom of the hydrogen in possession of an electron and the proton. This atomic matter in the coldness and in low gravitational and Magnetic fields of the Oort clouds and Kuiper belt become in atomic or nano state of matter of hydrogen rather than atomic hydrogen and hence sometimes due to the weak gravitational field forces in these zone these lights become the gans (5) of the same element.

The **gans of the matter** is the ***state of matter, where the atomic gas of matter becomes the single solid atom of itself*** or what we have called “the gas in nano state of matter” in short or “gans” of the same element (5). Where, the gans of the matter is *internal gravitational and Magnetic field strength dependent* and at the same *time where the gravitational and Magnetic fields of the matter* ***is stronger*** *than its environments ‘Magnetic and gravitational fields strength.*

The difference between the atomic gans or a nano gas material is in the fact that gans of an atom is its solid three dimensional free state of matter due to its internal gravitational field interaction.

As the Gans is the solid state of atom of gas in its natural three dimensional structures that its mafs of this matters are interlocks due to their internal Magravs strength of its own and their internal mafs loose bindings, and not rigid binding as in solid atomic state of matter as in the form of ice state of matter of the same entity of the same atom, which ice state of matter is due to and dependent upon external magnetic fields’ strength of the environment which are exerted up on the binding structure of atoms that become creates the state of the ice of the same atom.



Fig. 17 The structure of gans of neutron

Where, at the same time it has to be noted that the light in becoming in ***state of gans*** it can create the fundamental plasma of the gans (Fig. 17); in the same region as it does create the fundamental plasma (of neutron) too.


MATTER
TRANSITION ENERGY
TRANSITION MATTER
PRINCIPAL MATTER
MATTER
TRANSITION ENERGY
TRANSITION MATTER
PRINCIPAL MATTER

Fig. 18 The structure of gans of an atom

The gans of elements (Fig. 18) are created through the same process as of known atom directly from the rays of light or through the decay of the neutron of the gans going through its nuclear decay and creation of its own gans of the same elements in atomic state.

It can be said that the gans state of an neutron or atom is internal magnetic and gravitational fields strength dependent, where atom or nano of matter of the same element is environmental magnetic fields strength the like of heat and pressure dependent (Fig.19).

In this illustration the difference between the internal and external magnetic fields forces and processes which lead to creation of gans of matter structure of neutron respectively are shown.


MATTER
TRANSITION ENERGY
TRANSITION MATTER
PRINCIPAL MATTER
pressure
heat
MATTER
PRINCIPAL MATTER
F1
TRANSITION MATTER

Fig. 19 The comparison between the gans of neutron on the left and the fundamental plasma (neutron) on the right

The gans state of matter is the reasons why for example the molecule of gans of the amino acid (Fig. 20) in the structure of protein and other cell structures the like of in the leaves of plants have tangible, flexible, soft characteristics that they can be manipulated and not being rigid hard.



Fig. 20 The structure of a molecule of gans of amino acid

May be it can be said that gans is the solid state of matter of living entities. That is to say the structure of the protein is one of the molecular states of the gans in matter magnetic fields strength environment. Where, through the gans state of matter as part of the cell of the living beings this makes the transition of pmfs needed for rapid transfer of given mafs much easier as by the availability of the gans of an atom rather than nano of atom, this makes it possible to transfer the information of the matters as magnetic fields and not the whole of the atom from one atom or molecule to another as has been assumed by the world of science up to now, and hence once the right measure of the mafs are transferred to a cell then through accretion of mafs in the vacuum of the body then a new gans cell is produced.

Where, for example, if one pinches oneself flesh or skin, what one holds within its fingers are gases of oxygen, nitrogen, carbon and hydrogen in state of gans of the matter, otherwise the body of the man would been a balloon of gases and not in the state of matter as one finds between ones fingers.

At the same time the energy transfer to the already existing cell is due the transfer of pmf of mafs from one cell of gans of lymph to the existing cell. By the same measure as the cell uses its appropriate mafs and is left with wrong or mis-measured amount of mafs for its use, then the cell transfers these pmf of mafs to the blood cells for their removal from the body's systems. This being the reason why for example one does not finds residual of urine in the blood, but as the blood passes through a different dynamic gans molecular structure of the kidney, then the mis-measured mafs in the gans blood cells are reconstituted as liquid and appear as urine in the walls of the bladder.

This applies the same for the transfer of the molecules and atoms of the minerals and vitamins which in fact are mafs of different combinations.

In reality, the world of science and humanity always have known this state of matter as part of the structure their own body but they always have considered it as molecules of the same element and not as another state of matter, thus gans can be considered as the **fifth state of matter**.

This condition of gans of matter is to be explained as the gases when their physic-chemical at ambient temperature and pressure and due to internal gravitational and Magnetic field's strength of the atom the atom physical appearance the atomic structure of the gas ***changes to a compact configuration of the solid*** and as the atom of the same gas become and behave like solid but ***with totally new properties and characteristics*** which has never been known as when the atom was in its other three initial known states (gas, liquid and solid).

This ***conversion of the light rays to solid state*** occurs in the **outer regions of the solar system**(s) where the gravitational field forces (vacuum) are low and the temperature has no effect on the internal motion of magnetic fields that create this solid state of matter. Then, as the ray becomes and appears as gas and in a given conditions manifest itself as the nano structure of gas or what is called "GANS" in the same environment *due to atom's own internal Magnetic and gravitational fields configuration* and ***not due to*** *its environmental magnetic fields.*

This state of gans and gas of an atom is being the *same difference as between* ***the mass*** *and* ***the weight*** *of an atom* respectively, where **mass** is due to internal atomic interaction of fields of the atom and irrespective of external field forces and where the **weight** is due to environmental magnetic fields effect on the outside appearance of the same mass.

Humans are familiar with the gans of the molecules and atoms as integral constituent of their own tangible body, where ***gases at low internal vacuum condition*** *of the body convert* ***gases into gans or soft individual solid atom state***, but up to now the scientific world has never considered this state of matter as they just say for example the carbon of protein chain or matter of a cell or a carbon as part of the structure of a sugar of a leaf of a plant and so one. That is to say for example, when an atom or molecule of a hydrogen gas, which was created from the ray of light as this gas is absorbed by the human body then this gas of the atom changes to the gans of the same atom and then through the accretion process in vacuum condition of the human internal operation, then this gans particle according to its Magravs strength becomes part of the molecular ganses of the **N-C-O-H protein chain** of the human and that is why human body becomes tangible entity. Where, the creation of the solid gans in the atom of the gas of the atom, this process by itself is due to the accretion process of all the fields of the mafs of the gas atom itself.

If this change of state of light to gans does not take place, then the human body should have been a balloon of gasses and not in the solid tangible arms and legs and so forth.

Further, it has to be said that as the light ray changes to the atomic gas of the hydrogen and as it reaches the planetary condition and natural Magravs state of planets this matter changes to gans atom of the same matter in the atmosphere of the planetary entities too.

The confirmation of the production and existence of the gans in the Oort clouds and Kuiper belt is and can confirmed by the existence of the hexagonal rings on the top of atmosphere of the poles of the Planet Saturn. Where the composite dynamic layers of nano gans of material(s) in this part of the planet leads to creation of the hexagonal shape solid clouds as has been recorded by pictures taken the scientific world from the pole region of the planet (4).

The only reason that one sees these types of structures in the universe is primarily due to existence of gans state of matters like hydrogen, methane ganses and others in these layers, as the Magravs of the planet interact with dynamic metallic characteristic structure of the hydrogen gans and other matters ganses and this nano state of matter in dynamic magnetic fields of the poles of the planet leads to creation of current in between these layers and consequently for example in the poles of the Saturn the formation of hexagonal shape rings of the clouds which is the consequence of these interaction , which are natural positioning for the gans in dynamic mixed and composite magnetic and nano structures.

To create the hexagonal shapes of the clouds in the north-pole of the Saturn one needs at least three layers or mixture of three different ganses of different or the same elements to be able to create these shape features in the upper atmosphere clouds of this planet (4).

In reality gans's of matters behave as semiconductors do in the matter environment, with the difference that the gans of matters are *always as they are in a* ***semiconductor state*** *and at the same* ***time they create current*** *in any environment* due to their internal dynamic magnetic fields structure.

On the other hand, the conversation of the light into gans and its absorption and their interactions with the strong Magravs producing planets like Saturn is the cause and producer of the internal Auroras that are commonly observed at the poles of the gas planets. Where these auroras are due to the fact that as the gans of the elements from Kuiper belt gets absorbed into the giants planet atmosphere and as these ganses are in solid atomic matters state the like of the cosmic dusts and in their interaction with the magnetic fields of the planet, these interactions of the gans and the magnetic fields of the planet leads to creation of the Aurora at the poles of these giant gas planets.

It is essential to understand the fundamental effect of the light rays mafs of the matters' in the solar system and even in the creation of the solar systems and planets themselves that one can understand why the rays of light are the transporters of creation in the universe as in their conversion they become the created entities the like of atoms, cells and so forth due to their pmf strength of their environment. Where, in fact the lights in becoming the gas of the matter, then they become the source and the cornerstone of the creation in all matters levels of the universe. Thus as light changes to atom and gans then in the right environment of for example one G (gravitational field strength of the earth) as on earth then the collection of atoms as the molecules of ganses state of matters leads to creation of the beings, the like of single cells and complex combination as of the human's body.

Light ray from the Principal Star (black holes) as it loses its strength and becomes to matter mafs state strength and then it becomes to the nano and atomic level of the matter strength of the fundamental element of atom of hydrogen, it is at this point, where this matter generates the first external gravitational and magnetic fields or what is called the Magravs of itself in matter environment that this tangible entity due to its Magravs positioning and strength in respect to other Magravs that it can be attracted by or attract to itself the same and others elements in the same environment. Then it is at this point that the light becomes physical entity and the seed of the stars and planets and the essence of the tangible entity in the all matters environments of the universe.

In the spans of the solar systems, galaxies and cosmos as the gans and atomic of the hydrogen interact, they create the first seeds of creation of more powerful Magravs that leads to attraction and conversion of other light rays in the universe into liquid and solids, which these interactions leads to creation of galaxies, stars and planets, where the light itself in different strength becomes the tools of the division of the hydrogen for it to start the cycle of creation of intelligence and creation of the lives in all corners of the universe (6).

The gas and gans of hydrogen becomes the dynamic fuel source of creation of the magnetic fields necessary for the creation and establishment of the stars and solar systems and their planets, as the interaction of different magnetic fields of gases and ganses lead to the creation of the initial

Magnetic and the gravitational fields needed for these celestial bodies to be created in the universe. The existence of nano materials in the core of the planets like earth has been initially disclosed (1), now it can fully be understood that how these nano materials in state of nano matter, gas and gans become to exist in the centre of these celestial entities and be the initial seeds of their creation.

It is important to realise that due to internal structure of the nano material in layers and in gans state, these materials by large keep their structural integrity, where high external environmental matter conditions like pressure and temperatures cannot affect the total structural integrity ***once they are in individual matter gans compound state***.

This meaning that internal structure and molecular binding of gans and nano materials in nano layers or composite structures will not be affected by the matter environment's the likes of temperature and pressure condition of the environment. But the gans will be changing in its structure when conditioned to high level dosage of radiation.

For example, this is one of the reasons, why the DNA of the human being is venerable to changes and absorption of radioactive energy and in the radioactive environment or to burst of radiation, as the real structure of the amino acid of the protein of the DNA chain is made of gans of matters and not solid matter of the same gases (6).

In these conditions the gans of the matter receives radiation in the upper levels of the matter mafs strength and hence it has to accommodate this extra pmf of radiation hence the gans reaches a new magnetosphere pmf strength and consequently the gans of the atoms of the protein which has absorbed the additional pmf has to accept a new positioning in respect to other ganses in the chain, hence new positioning means new additions or new configuration in the setup of the DNA and hence new changes and hence slightly new chain configuration or alteration (6).

The property of the light in gans state make the gans venerable and receptive to changes due to the magnetic fields spectrum in all levels of mafs of the matters strength, this be it from the higher order mafs of the principal matters fields to lower pmf strength of below matter environment. This being the reason why DNA due to absorption of for example high level radiation or strong ray can change its configuration this leading to new permutation and change in the characteristic and change in parts of the being characteristics of the living matter.

Through this process of Magravs positioning and that all Magravs needing to be in their given position in the DNA chain that one observes the consistency with structure of the DNA for every living entity in the universe, which these chains of protein positioning become entities exclusive to that of a given being or entity. Now one can understand how light and its process of conversion, fusion and amalgamation lead to creation of exclusive structure of DNA and creation of beings (6).

Scientists due to old understanding of creation of magnetic field consider that the earth has an iron metallic core which due to its motion through convection theory leads to creation of Magnetic fields of the earth. The fact that the Sun does not possess a metallic iron core but it has large and powerful Magnetic and gravitational field forces; hence the existence of iron in the centre of all dynamic rotational bodies is not a common and acceptable principle and natural order of creation of Magnetic and gravitational fields in the universe.

In truth the plasma of neutron does not possess iron core, but it goes through the decay and division to make plasma of electron and proton and in this process of decay neutron does not go through iron energy balance condition as has been claimed by the cosmologist that this is how they consider stars reach the point of no return due to the creation and solidification of iron matter in their central core. And at the same time geologist consider iron core of the earth is reason for the planet possessing

Magnetic fields.

The method by which the Magnetic field's (repulsion of fields) and gravitation field's (attraction of fields) are generated exponentially increased in all planetary, solar and galaxial object are initially and primarily through the magnetic properties of the plasmas, nano and gans materials within the centre and internal structure of all celestial objects. As in the inner cores of celestial objects the ganses of the matters due to their mafs and through nano layers or different composition of collective crystal and magnetic fields structure they become or behave as the best insulator and conductor simultaneously in their environment, where the gans and nano matters, and their mafs and their properties ***changes from conductor to insulators*** as these matters behave as semiconductors and metals and at the same time due to their dynamism of their pmfs this leads to the initial and then partially continues production of the Magnetic fields and gravitational fields of the star or planets respectively (2, 3, 4 and 5). It is at this point that magnetic properties of the nano and gans materials in their interaction lead to creation of Magnetic and gravitational field's forces, this leading to creation of the independent mass and magnetosphere of the new entity.

Through the gans internal disassociation of its mafs structure as the internal principal mafs of the structure unwinds rapidly and when this transition to matter level strength is very rapid, then this lead to release of the high temperatures and strong rays of light in man's protein and the visible magnetic fields spectrum strength and hence detection of the release of spectrum of magnetic fields of the light rays.

The gravitational properties of nano materials and the creation and attraction and absorption of matters from the environment have been explained in the paper published in detail (5), at the same time matter cannot attract or gravitated towards another matter if both are not in possession of magnetic fields, where at the same time it has been confirmed (5) that nano materials possess magnetic properties and as magnetic fields interact then nano and gans materials create their own gravitational field zones and environments; and in having nano and gans materials in the centre of planets and stars this indicates how the gravitation fields (6, 7) of all dynamic systems and objects in the universe are created.

Ganses being in the right magnetic fields strength environment due to their Magravs strength these materials ***will convert into gravitational zones in their environment and attract light and in turn absorb, create and release energy***, where this energy leads to creation and attraction of gases and their conversion as for example the same process in the human body to solid state of matter at room temperatures, where in test it has been shown that this process of absorption or conversion of the gas to gans leads to creation and release of energy and similarly vice-versa. As for example in absorbing CO2 from its environment the plant releases energy into its internal structure to be used for conversion of minerals to food for the plant to assist with its survival and growth.

Thus the truth about how even the heat of the body is created is far from the present assumptions which the scientific world has led the man to believe, as they themselves never understood the real working of universe and the process by which matters behave and operate in its low vacuum conditions.

This concept and process has been tested, explained and published in detail in Chapter 4 of this book, where for example in capturing gases of CO2 from the environment and collecting it as gans as a tangible entity at room temperatures and pressures, the energy released through this process is use to light and run lights and motors respectively in the lab by independent scientists as has been published in the journals in May 2010.

Whereas, in this case energy is released is in a similar way as it happens in the human body, when the light or magnetic fields of the light enters in the micro vacuum condition of system or the body and in receiving the light rays and in trying to entangle or go through the process of atomic-entanglement in gans level and then accretion, this process leads to release of the surpluses energy and then accumulation (accretion) of solid ganses which appear as cloud of matters in tests and in human body which then this become tangible structure of matters of the body and the surplus energy is released as the heat of the body or it is used for the communication system of the body.

This process of accretion is one of the sources of energy release in the living body entities and in experimental testing this released dynamic energy in the level of plasmatic magnetic field strength of an electron produced through this process become the source of power and is enough to light a LED for several months, as this process is a natural process as long as the light or other rays can penetrate the liquid, jell or soft tissue condition of the system this process can continue.

The other important reason that one finds water in this solar system is primarily due to the fact that pmf and Magravs strength of this solar system and the ones like this encourage and enforce initially the production of gans of magnetic matters the likes of oxygen, which leads to creation of liquid state of matter of water.

At the same time it is curtail to understand the structure of three and two dimensional properties and characteristics of the same atoms in layering and physical positioning. The gans of the matter is captured and held in three dimensional states, where gans of matters gravitate and make dynamic clusters of ganses around themselves and become dynamic entities, whereas, in the linked version of the same atom clustered the same matters in solid state makes layer and gives and possess totally different properties and appearance.

The light in its conversion to atom of gas or atom of gans according to its given environment then will take and enforces its preference estate of its manifestation, and with slight change in level of its internal vacuum (defined as availability of Magravs and their strength) then the light will appear as the gas of an atom or a gans of the same.
It is interesting that scientists and scientific organizations are not in possession of tools at this moment to identify these two separate states of matters of the light in visible entity of matter and hence always consider all matters as the atoms and in presently considered four states' of matters as has been tradition.

The same ray of light when changes to gans of the hydrogen atom, this change's its dynamic diamond crystal structure of the same matter and hence this gives the same matter insulating properties and hence allows the creation of conductive and isolative properties of the same element in its layering and clustering structure and its dynamic properties in between the same elements of atoms of the gas and gans.

The gans in specific condition has diamond crystal structure of the hydrogen atom and with slight change in its environmental condition become a conductor for short or on a long term. Where this has been experimental prove and demonstrated and then clustering of this structure mixture of gas and gans of the same atom leads to creation of multi-layers of conductive and isolative matters of the same matter and hence in the dynamic magnetic environment of the universe this leads to creation of different and stronger Magravs, and start of attraction and positioning of different matters towards these initial seeds of gravity and Magnetic fields and hence start of creation of initial celestial entities like plasmas of neutron, atoms, stars and galaxies.

This is the reason, for example why the same matter of carbon becomes to be the best conductor as nano layer Sp2 and the best insulator as the diamond crystal insulator structure known as Sp3 across the same layers or through its layers respectively where the production of such a mixture has been independently confirmed by Ramon spectroscopy of these structures produces as layers on a given surface. Therefore all elements and molecules or their combinations can have both Sp3 or Sp2 structure and property at the same time and in the same environmental condition.

This being the like of the protein chain, where each gans of each element exist individually and collectively in the amino acid as molecule of gans as each element plays its individual role which can affect collectively the operation and existence of the acid in its given environment (6).

In understanding the concept of the conversion of light rays to gans and gas and creation of nano materials, this discredits the present philosophy of the planets needing solid iron cores which enables them to create their Magnetic fields that they can operate in the universe or even the human race could be brought to the earth from other places from far corners of the universe. The life on earth is the natural product of lights' motion and its conversion in the internal activity of this planet and solar system.

By the same measure light plays in different environments different roles which can lead to creation of the same and similar or totally difference combination of creation of molecules of gans, which these manifestations of difference appearance of the light are environmental pmf mafs strength dependent. This is to say that life is not and shall not be the exclusivity of this planet and this solar system once on understand the principle of creation and motion of the light rays in the universe.

Thus the centre of the earth does not need to have solid iron core for it to possess Magnetic and gravitational field's forces leading to creation of life on the planet too. Whereas, composite elements of nano materials, gases and ganses crystal structure of the same element in the inner cores of the planet can lead to creation of the same Magnetic fields and gravitational fields of the planet.

This explaining why even some planets like Saturn possess Magnetic fields, even though these planets could possess some solid matter as their constituent materials as part of their inner structure.

In reality as layers and layers of dynamic gas and gans are piled-up in the centre of the planet the effects of dynamic magnetic layers exponential strength that they make as the Magravs of the planet take hold and this phenomenon lead to creation of stronger fields that can span billion of kilometres in the solar, galaxial heliosphere in the environment of these entities.

Thus the transition dynamic helixial cylindrical ray of light in slowing down in a given environment Magravs strength, this lead to creation of specific matter in that given Magravs strength environment.

The scientific world has to understand that the state of gans of matter is a natural phenomenon in the world of creation, this meaning as man has learned about the solid, liquid and gas state of matter, as these states of matters are due to temperature and pressure difference in the environment of these matters, but there is another state of the same matter even though as it's like a gas and behaves and exists as matter in form of liquid and solid but due to its internal gravitation fields forces of its atomic structure this matter for its appearance and properties is ***not external environmental dependent***.

The gans or the gas in nano state of solid state of matter will play an important part in the future of the science and technology. That is where the same atom behaves like a gas, liquid and solid at the same time depending on its own internal magnetic fields interaction in its plasma and not of the external environment conditions around the plasma the same matter will be in dynamic solid state at room temperature at all-time irrespective of the environmental condition.

That is to say the plasma of an atom of gans receives or coordinates its own Margravs and its own Magravs positioning in respect to its own electron and proton and other gans structure.

Thus, gans is the state of the structure of the light which has changed from dynamic cylindrical plasma of magnetic fields to a dynamic spherical entity of the same matter mafs, which its state of manifestation in matter environment is internal gravitational dependent and not environmental condition dependent. That is why one can observe the same element in coldest and hottest regions of the universe and still misreads them as atomic matter rather than nano-atomic or gans of the same matter.

This is how some of the plasmas and rays ejected by the Sun, depending on how they arrive at the Oort clouds and Kuiper belts then become nano materials of gas or gans and in clustering with other matters and ganses become part of the meteoroids or asteroids and look as they have been there from the time of the creation of the solar system.

In the universe and solar systems of the right Magravs strength, the light changes into the nano hydrogen and through internal magnetic fields of the solar system through the principle of magnetic balancing and accretions this matter elevates to the next magnetic material, which one of these materials' is the gans of the oxygen. This element due to its Magravs positioning and balancing in the Magravs of some solar systems lead to creation and production of water molecules in the Oort clouds belt and then these water nano particles gets pulled back into the inner parts of the solar system as nano ice particles of gans of this material which for example one observes them in the rings of Saturn.

The ice particles in the ring of the Saturn are there and for ever are produced by the return of the rays of light which were released by the Sun itself, on their way back to the Sun as gans and ice particles and they are temporarily trapped and positioned in these rings, and the present assumption that these ice particles exist in these rings are not by the crash and splitting of meteoroids or asteroids into smaller pieces that afterwards have stock in these rings of the Saturn as can be observed at the present time.

Thus as the light reaches the outer boundaries of the solar system, its becomes nano material, which due to their magnetic properties, this leads to creation of a nano magnetic material which is oxygen and then this matter of nano particles gans of oxygen to find stability for its Magravs, this attracts two atoms of gas or gans of the hydrogen nano particles, which this leads to production of gans of ice looking particles of water in the Oort clouds belt of the solar system, which they move inward and become the liquid magnetic substance and the source of the life in this solar system.

Thus the water in the solar system is generated by the rays of the light of the Sun itself mainly and by no other source and hence water is produced in the solar system by the recycling of the light rays of the Sun itself.

The mixture of these ice nano materials with solids matters of the solar system leads to creation of meteoroids, whereas these dynamic objects in traveling between the Oort clouds and Kuiper belt, these objects attract nano water molecules and then they return to the inner regions of the solar system. This being one of the reasons why the meteoroids are seen on regular basses and their size never changes, but their vapour trail tells the existence of the water residuals in their structure's as forever these objects gets replenished with the Sun rays in the form of gans of water in these outer regions of the solar system and return back into the inner parts of the solar system.

Therefore the theory that water is brought to planets like earth by meteoroids as has been assumed is partially correct, but Magravs of planets like earth in the Magravs of its Sun have the ability to convert light to nano matters and nano matters which have been produced into hydrogen and molecules of water through accretion process in the vacuum of the solar system and in the upper layers of the earth atmosphere itself. Hence water is the creation of the combination of atoms created by the rays of light and in different magnetic fields conditions in the Margraves environment of this solar and planet system.

This process of conversion of the light can happen anywhere in the universe as the nano particles of the hydrogen is one of the first and weakest Magravs strength that light can change to matter anywhere in the Magravs strength of this universe.

Thus water is not exclusivity of this solar system and is product of the light rays of the universe in matter environment.

There are waters like substances in other matter mafs and matter strength environments in the universe too.

It is important to realize that all gans have the magnetic properties with the difference that oxygen is the one of few common magnetic materials in the solar system and in most of the universe needed for braking of the light itself to lower level strength, which can lead to creation of intelligent life. In some solar systems and galaxies pmf strength of the gans of the matter of the oxygen is the common magnetic elements and the reason why all maters existence dependent upon availability of this matter in the pmf of the environment.

In the living bodies in possession of systems the like of the lungs and gills in fish, the light in changing to molecule of oxygen and in being inhaled for their existence, in these systems contrary to present belief the atoms and molecules of the oxygen will never cross the boundary of the structure of the lung or being absorbed by the blood as has been thought and promoted by scientific world (6). The fact is that in the process of inhaling or in case of fish by passing the water through its gills, the atoms of oxygen simply passes limited value of their matching plasmatic magnetic fields strength to its matching oxygen atom of protein of the blood cell that the blood cell as commonly called gets oxygenated in the lung (6). In reality no oxygen atom or molecules ever passes the walls of the lung as has been assumed, but the oxygen atom transfers its pmf to the bloods oxygen atom in its protein and then this pmf is carried through and by the same principle as the pmf from the oxygen of the blood protein cell is passed on to other oxygen atoms ganses in the protein chain of other cells in the human body (6) as they come across their corresponding mafs strength protein in the blood.

The oxygenation of the red blood cell is primarily another quantum-entanglement of the same matching matters strength or entanglement transfer of adequate amount of pmfs of specific cell of the matters of blood.

The fallacy that oxygen atoms cross the walls of the lung is so far from the reality of existence that as saying a man can walk through a solid wall. This hypocrisy has been the consequence and through the lack of understanding of the real structure of the oxygen and its origin being laying in the structure of the light that matching plasma of light and atoms can/and frequently entangle and transfer their pmf up to level of their mutual strength that existence can be guaranteed in one form or sub-structure of the same and without the plasma of actual solid atom crossing the boundaries (6) of the lung.

In fact the energisation of the red cell is through transfer of the pmf of the atom of oxygen and not the actual transfer of the crossing of oxygen into the blood stream and the brightening of the red cell passing through the lung is like the variable light switch, that as one increase the current through the

light the light shines brighter, this is the same process and in the same way as the red blood cells receive the pmf of the oxygen, then the blood become brighter or richer in pmf, then the blood cell after transferring its pmf to appointed cell in the body then pmf strength of the blood cell is reduced in energy and illumines less, dimmer or looks darker as it returns to the lung to be recharged (6). Man has a lot to learn first about his own body before he can conquer the universes.
In understanding the function and the fundamental properties of the gans and molecular gans then computing systems can be produced that not only they think the same ways as humans do but due to their dynamic energy and singular directional rotation, then at this point the first quantum computing systems can be produced that these computers will be exact copy of the human brain and muscles in structure with the same multi-neuron-cross linkage and communication channel, as these channels are created as gans molecular Magravs linkage will allow them to have the same simultaneous multi-cross connection that these quantum gans of molecules structures will be exact parallel systems as do the human brain in all aspects of a real working structure of logical system, which even they can carry emotions as well as control and logic. Where, in fact the binary gans and twin gans sets will be the future of fast thinking units needed for the high speed control logic system for space systems travels of the future.

As there are gans in the matter environment mafs strength then there are gans in pmf strength of principal matter and transition matter too, and at the same time the gans of matter in all mafs strength will operate in all levels of pmfs strength. Thus it is possible to produce molecular gans unites which work at high speeds and with same emotion and logical systems as human brain, but with speeds that are far exciding speeds of the human brain processing capabilities.

Therefore it can be said that for the first time the man has the capability and the knowledge of not only producing solid gans of gas at room temperature, but it can go one step further than present conceptual nano matters and nano matter based computers and start working on real brain based matter structure logical systems by using the gans of the gases which are the building block of the human amino acids.

But the question is that would we as far as building the first human operational brain and body using these matters as we have already decoded the DNA of the human genome, and as we know the full chain of the DNA sequence and we have already unravelled the mechanism that the RNA produces it energy and current for its internal communication and control of the internal systems of the DNA, then would man become the creator of new beings bases on human structure and would the discovery of the gans and simple method of its production will allow the ethical question of mass replication without the need for stem cell or even egg and sperm, which are memory banks of human survival on this planet. Would man will make one of his own with a clean DNA memory. OR is the human being to become the god of new generation of beings.

This is not the first time in the universe that one created has the ability to reproduce another of the same, but at the same time this discovery of structure and properties of the gans would have become apparent to man of science in due time as he would have progressed in his scientific conquests.

Some scientists believe that solid iron is the main magnetic matter in the universe and this matter in the centre of the stars and its energy balance conversion between its fission and fusion is the point when stars goes through their slowing down process or reduction or what is known as their nova state. The truth is that the plasma of mafs of the simplest structure of the plasma is the common and the fundamental and elementary magnetic entity in the universe. Thus the plasma of the light is the basic and common magnetic matter in the universe and one does not need iron to reach this point, as the plasma of matters in given position can lead to unbalancing of their total environment pmf mafs and Magravs, this leading to total disassociation of the all matters in any matter or object in the span of the universe, and once the process of the chain reaction of disintegration and disassociation starts then the whole entity disassociation from each other begins and in the case of plasma of neutron and star at this point disintegrates to re-association in a different as plasma of proton and electron and new star and planets in their form in difference point and place in their given environment.

By the same measure the plasma of neutron which is created by the conversion of the light ray is the common magnetic matter of the solar system and not atoms of iron, and in reality the light of the Sun and its Magravs dictates this property of this mafs of the matter and the present assumption that energy balance conversion of iron is the cause of their nova cannot be correct and as most of matters in the universe are created because and through the existence and the operation of principal matters in the centre of the stars and their rapid unwinding and balancing of their Magravs in the centre of the star leads to the expansion and disintegration of the star and not as has been assumed at this point by some cosmologists due to the iron fission-fusion balance (3,4 and 5) phenomenon.

What has been explained above, this is the process of creation and recycling of the light through its full circle of its existence from matter to light and from light back to matter(s).

The detailed information and explanation about the existence of the gans of the matter has been possible due to through series of tests which has been carried out and absorption of the physical solid CO2 at room temperature has been confirmed. The procedures and tests results in confirming the existence of this new state of matter was originally published in 23.12.2009 by the Keshe Foundation on its website. For those whom have not been able to read this paper a copy of the same is published in this chapter.

The state of gans of matter can now explain about the truth of life in the universe and this opens new horizons in the world of energy, new materials, production of more natural components of the human body parts, production of new medicine, new types of food processing technology, which this eliminate the need for present farming processes to feed the populations, as protein can be produced from the content of the light or the mixture of composition of lights mafs in gans state of matter that can lead to production of solid matter the like of fresh meat and or composition of dairy milk and so forth. Thus through production of gans dependence on the extensive farming in the space becomes irrelevant, where in deep space by absorbing weak residual mafs of the light and in bringing them together and through accretion, then producing the gans of the fundamental plasma, then producing the gans of fundamental atom and then through accretion creating composition of ganses of protein, then one can produce any food in the span of the universe directly using the matters of the light. Originally this concept of producing protein through gans from the gases of environment was considered and successfully tested in Tehran in the summer of 2008, and through simple process the first gans of protein in small quantities by using the natural air at room temperature was produced.

In the appendix section of this book, attached is the paper titled “The unifying field theory” published in the 28.10.2009, in this publication it is discussed and can be concluded that the origin of all entities, tangible or not are magnetic fields and the interaction of at least any two of any magnetic fields of any strength can lead to creation of all other effects and matters which are observed in the universe.

Thus the magnetic field is the unifying field and the mother and the seed of all created and creation in the universe, thus the magnetic field is the Holy Grail, which the scientific world had been searching for in the universe strength to connecting all fields and effects observed in the universe.

Chapter 4

CO2 in Gans State (paper 2009)

Direct absorption of carbon dioxide CO2 and methane CH4 gases from the environment and their conversion into nano solution and nano solid matters and production of energy and oxygen by the use of nano compound at ambient temperature and pressure.

Abstract

In this paper, results of processes will be introduced for the absorption of carbon dioxide CO2 and methane CH4 gases direct from environment and their conversion into nano materials of the same suspended in solution or dried as powder. Where, concurrently within the processes of extraction of these gases in a simple reactor, we have managed to produce energy and oxygen.

Discussion

New methods for absorption of CO2, CH4, and others gases and further conversion and preservation of these elements in their nano solid state of matters at room temperature and pressure has been developed and achieved.

We have developed simple processes by which carbon dioxide CO2 and methane CH4 gases can be extracted from their environment where no additional heat or pressure to achieve this has been applied.

At the same time conditions can be created within these systems that CO2 in conversion without going through any chemical process, can lead to creation of methyl, oxygen and methane gas and vice versa.

Where during these processes of CO2 and methane gas extraction or conversion we have managed to produce usable energy and oxygen molecules in sustainable way.

Production and extraction of CO2 by applying energy is a known technology in the present science, what is new with our technology is, that not only CO2 is extracted in a simple system at room temperature and pressure, at the same time, energy released through absorption and conversion of the captured CO2 to formic acid, we have developed simple techniques to capture the energy release from this transition process to produce useful power.

The novelty with this new technology is that in previous state of art technologies, engineers and scientists had to add energy to extract CO2 the environment or to produces O2, where through our technology, not only we generate useful energy while absorbing these gases from the environment, but also at the same time, the system can produce molecules of oxygen.

Thus, this simple system has the ability to replicate the processes as in a natural way as plants achieve in their conversion of CO2 into oxygen.

With this technology, CO2 and CH4 gases are absorbed and attracted into and within the solution in their nano state, and then they are allowed to amalgamate to produce gel like residual solution and then form nano sediment.

Where, nano CO2 can be extracted or removed from the solution as solid matter at room temperature.

The CO2 stays in state of gel as nano materials in the solution due to their diamond crystals structure (sp3), or due to their crystal lattice structure, this creating a non-adhesion molecular bound like diamond crystals. Which, this does not allow more than certain number of molecular structures to adhere to each other. Where, CO2 nano matters once reaching a certain molecular gravitational level, as crystal, then they do not attach or cannot hold on to more than single or certain numbers of nano molecules of CO2 and form independent or nano cell of matter. Thus, all clusters of CO2 in solution have certain dimensions and that is why they stay like clouds or gel within the solution.

We have to explain that it is known tested fact to us that nano-coated materials and nano materials in sp2/sp3-state due to their characteristic of diamond crystal behaviour, they cannot be soldered to each other or soldered to another material. However, at the same time in a peculiar way the outer electron of these materials allows conductivity of matter. What this means, is that, even through they do not or cannot be attached to any other material from their outer structural boundaries, but in being connected with each, these materials allow flow of current and voltage through their outer boundary.

In a way, these behave like quartz materials, but at the same time after a number of layers, they do not or would have the gravitational pull or adhesion capability to allow more layers to be added to their layers.

Where, these layers along their grain and layer, they behave as a superconductor, but across layers in PN junction, depending on the position of PN cavity within the layers, they become best resistors. Where, we have measured the resistance of these layers and this have been confirmed by other scientists whom have tested our material of sp2/sp3, that these materials have shown to have 20 M Ohms resistance threshold barrier. On the other hand, this material on the surface has as good as resistance capacity as air and diamond.

We have further managed to obtain solid matters of CO2 from the system or dry the nano-saturated nano CO2 dilution into nano CO2 powder. Thus for the first time in the world of science we have managed to generate at room temperature and pressure nano matters of CO2 and methane through the same process.

To confirm that solutions obtained in our tests to contain CO2 and CH4 matters and these matters are in nano form, we had to under take laboratory tests of the solution with infrared spectroscopy and XRD respectively.

Further, as we know through our previous developments in nano technology, that nano materials are by principle sp2/sp3 in their character. Thus from results obtained from infrared spectroscopes and XRDs of matters during our process of absorption and nanolisation, we have concluded that the extracted CO2 and CH4 materials in solution and dry are both in nano state of matters of these gases.

At the same time parallel researches which we have found on the internet since the publication of the first addition of this paper on the 23.12.2009 done by other scientists, Dr Omar M Yaghi of the university of California released on 7.12.2009, which extracts of this has published in article by The New York Times published 4 on the 8.12.2009, this article refers to "metal-organic frameworks (MOFs) material promise of carbon capture and release, and that these materials being crystalline sponge hybrid lattices of organic compound and metal atoms that has a huge internal area where gas molecules can be absorbed."

Where we have reported these characteristics of metal-organic sponge effect and capture of CO2 in 2006, and this has been confirmed by indecent testing by major nuclear testing centre in Europe in their report in 2007.

Further, in the paper Dr Yaghi states, "***MOF used in the study contained magnetism atoms***"

Where in our previous disclosures and patents applied, we have declared that the absorption of these atom of CO2 and CH4 are Magravs (Magnetic gravitational fields) based. Which this independent scientific paper confirms our finding that CO2 and CH4 are gravitated to the water as nano molecules, and they do not have any interaction with the medium of the water, but the water *is the container and tool or catalyst to keep these captured molecules in their singular or nano state and sp3 floating condition or as a solution.*

In the same paper, Dr Yaghi refers to how material separated out CO2, which allows methane to pass.

Where, our system not only captures the CO2, but also at the same time it can capture CH4 as we have reported before. That these captured carbon dioxide CO2 and methane CH4, produce diamond structure nano matters or crystals, with metallic behaviour like, which they have a superconductor characteristics and behave like conductors.

Thus, our findings are inline with other scientists and their scientific research works, which have been reported. Where now we can clearly state these captured gases can be converted to solid nano materials, which behave like metals, and are superconductors, but in reality, their superconductivity of the matter is due to their sp3 nano characteristics and not their metallic condition.

Further Dr Yaghi states that 87 percent of the CO2 captured, at 13-degree temperature are released back by the MOF matter to the environment.

Where this is inline with our reported behaviour, that as the CO2 are extracted by these materials we have developed, which our capturing materials are metallic and organic in their real structures, these materials then release their captured CO2 in the water at room temperature in Gans (Gas-Nano-Solid) state.

Further, he states that to release the balance 13 percent of the captured gas, one-need temperatures of 175 Fahrenheit.

Where, we release all captured CO2 as nano-material into the basic solution of the system, this all at room temperatures without any heat being applied.

Further more, the Canadian company Mantra-Venture-Group has announced on Business News Network that in conjunction with 3M using electro reduction of carbon dioxide, they confirm that ***they need 6Mw of energy to extract one tonne of CO2***, which this is considered to be at the edge of technology of CO2 extraction.

Where, with our new technology we produce energy rather than consuming energy.

Where, further MantraEnergy in conjunction with use of the CO2 they capture, they can produce formic acid, using the technique developed by Dr Gabor Laurenczy. Where, he has confirmed that he can generate hydrogen from formic acid. (Video-interview:

http://www.mantraenergy.com/mantra-in-the-news/squeezeplay-zapping-carbon.html).

We clearly have shown and absorbed CH4 not only from the environment, as similarly we have reported the production of formic acid through the natural gravitational forces of our system as has been shown by laboratory tests results which are discussed below.

We have reported the production of CH3 in our system late last year as we managed to separate the CH3 and its capture in nano state of matter in our system. The production of radical CH3 from the H2O molecule of the water as the magnetic and gravitational catalyst of the system, subsequently this leading to existence of two radicals in the systems at the same time, one of the CH3 and one of an atom of Hydrogen leading to release of molecules of oxygen.

Scientists at a nuclear centre have confirmed the production of hydrogen radical through our technology in 2007 in their independent (not yet published) report.

Therefore, it has become a simpler method through our development to extract CO2 and CH4 and released it in nano solid matter in water, and at the same time have the ability to produce energy and oxygen as we have demonstrate it to independent engineers in December 2009.

Further on in this paper we show and present pictures of both matters of CO2 and CH4 in solution and solid state for the first time (Fig. 29 for solution and Fig. 30 for powder of CO2, and Fig. 31A-B for solution and Fig. 32 for powder of the CH4). The CO2 in solution and dry state has a white milky appearance and methane CH4 has a blue greenish colour.

We have mentioned Dr Yaghis' paper in this section as the findings in his paper is near to our finding and is one of the latest in this field.

The CO2 capture is well documented subject on internet and we are not here to list them to support our claim, one can refer to these on the internet to find that our claims our inline with main stream physics community, with the difference that we reported the capture of CO2 in early 2005 in nano materials on our web site and now we are reporting the first solid nano material of the gas as in Gans-state. We call a Gas-Nano- Solid state the GANS-state, which is a state or phase of transition of matters, which has bee unknown in actual science up to the release of this paper.
Meanwhile in light of our latest discovery and disclosure of the capture of CO2 as solid or in solution, our foundation will ask the nuclear centre which has done the independent test for our system in 2006-2007, that if we can release part of this report confirming the CO2 capability capture of our materials.

The CO2 absorption

In our tests and development phase, we have managed to produce a special material for the production of a new and a simple system for absorption of CO2 through the principle of Magravs field forces, rather than the chemical method of absorption of these gases. Where, the absorption principles through gravitational systems have been disclosed in full in the book, which we have published in July 2009 (titled: The Universal Order of the Creation of Matter; ISBN 978-94-6087-001-9). In this book, I have, explained in detail, the principle of gravitational and Magnetic field positioning and attraction and repulsion of matters from these systems respectively.

Through the development of these new composite materials of organic and metallic nano layers, we have managed to create specific static gravitational field forces which can be in the magnetic wave length of the CO2 molecules, or we have developed condition(s) that as the gravitational field attracted the CO2 to the material, the Magnetic field(s) within these layers cause the repulsion or the release of the captured molecules of the CO2 from the layers. Thus causing the creation of nano molecules of CO2 in the water, and as we use the magnetic fields of the water for stability and as a magnetic catalyst, they come to allow the formation of clusters of Gans of CO2 and create a solution of these nano matters, which these latter manifest themselves as a sediment in the liquid of the system at the bottom of the holding container (Fig 30E).



Fig. 21 Infrared spectroscopy of the CO2 solution.

The solution of nano carbon dioxide CO2 and has been subjected to infrared spectroscopy by independent laboratory confirming the production of the first nano CO2 in a solution or as gel at 2630 cm-1 wavelength of the spectrum (Fig. 21).

This is actually the best observe data as calculated and predicted figure is said to be at 2640 cm-1 (Fig. 22). (Source: http://science.widener.edu)

The closeness of the figure of 2630 showing the purity of the CO2 solid matters within the solution obtained during our test.

Where even the predicted matter has a multiple peaks, where these captured matters due to their singularity in the measured sample has a sharp and clear single peak as has been shown in Fig. 21.

This sharp peak can confirm the possible nano sp3 structure of the suspended capture matters of CO2 in this solution, once XRD test was carried out for the same sample.
For further confirmation of nano structure of the matters captured within the solution and then the solution was allowed to dry and then as a film was subjected to XRD testing.

The results of this test showed a clear match only as superconductor characteristics for this material. Further analysis with the data from XRD, a superconductor material characteristics perfect match was not found for this matter.



Fig. 22 Standard CO2 infrared spectroscopy graph.

With this test, and from our pervious developments and testing, clearly it is shown that the matter within the solution has superconductivity property (Fig. 23), which has new non matching data in the present collected reference data, and this is the characteristics of nano materials in sp3 state of matter.

This matter as superconductors known or ever been recorded for observation.

Thus the XRD of the CO2 data as solid and its graphs have become the new base knowledge and fundamental basic data for any future capture of these gases, once they are absorbed as a nano material in solid state.

From our previous developments and tests, we know that all nano materials show and have superconductive characteristics. Now with this test, now we have further proof that the captured CO2 in the solution is in a nano state of matter.


Powder Diffraction Database Search
File Card View Search ?
Search/Match Criteria
Search/Match Result
Intensity
105
100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
6.0
8.0
10.0
12.0
14.0
16.0
18.0
20.0
22.0
24.0
26.0
28.0
30.0
32.0
34.0
36.0
38.0
40.0
42.0
44.0
46.0
48.0
50.0
52.0
54.0
56.0
58.0
60.0
62.0
64.0
66.0
68.0
70.0
72.0
74.0
76.0
78.0
80.0
82.0
84.0
86.0
88.0
90
start
WinXRD
Powder Diffraction D...

	FOM	Card #	ID	Routings	Compound	Formula
1	0.835/10/10	81-0808	C	I	Strontium Lanthanum Iron Tin Oxide	(Sr La) (Fe Sn) O6
2	0.825/5/5	89-3113	C	I	Strontium Nickel Niobium Oxide	Sr (Ni Nb2)0.333 O3
3	0.643/5/6	80-2497	C	I	Strontium Niobium Oxide	Sr0.72 Nb O3
4	0.631/5/6	26-1414	I	I	Europium Magnesium Tantalum Oxide	Eu (Mg0.33 Ta0.67) O3
5	0.621/14/17	84-1867	C	I	Barium Lanthanum Zinc Ruthenium Oxide	Ba La Zn (Ru O6)
6	0.610/5/6	18-0225	C	I, A	Beryllium Palladium	Be Pd
7	0.593/5/6	89-8212	C	I	Barium Strontium Zirconium Titanium Oxide	(Ba0.25 Sr0.749) (Zr0.283 Ti0.715) O3
8	0.587/10/13	83-0953	C	I	Strontium Antimony Nickel Oxide	Sr4 (Sb2.8 Ni1.2) O12
9	0.585/5/7	47-0035	S	I	Calcium Strontium Niobium Oxide	Ca0.6 Sr0.4 Nb O3
10	0.563/5/7	77-2064	C	I	Sodium Chloride	Na Cl
11	0.561/5/7	05-0628	S	I, M	Sodium Chloride, Halite, Syn	Na Cl
12	0.557/5/8	84-2452	C	I, A	Molybdenum Thallium Telluride	Mo Tl4 Te3

Record count:9274

Angle: 37.30 Intensity: 85.8

Fig. 23 XRD of the CO2 nano material

The closest match as superconductor characteristics to CO2 in the solution or in dry state of matter, this was found to be an exotic mixture of five different materials, as can be seen in the table at the bottom of the graph, with the best match reference data figures to be about 80%-90% superconductivity properties of this matter.

With the discovery of this new state of matters and the simplicity of their production and their high superconductivity properties, we predict that gans (GAs Nano Solid) of gases are going to be the next-best purest superconductor and resistor materials of the future.

Further more: in confirming the matter of solution being carbon dioxide and at the same time confirming that this matter within the structure of the solution and the system set-up has the capability of conversion to formic acid in presence of CO2 captured in the solution of water, a further test was carried out with **infrared spectroscopy** to confirm this conversion principle of the confirmed nano CO2 capture to formic acid within the solution.

For confirmation of absorption capability of nano CO2 by the solution and its conversion into formic acid, the chamber of the infrared spectrometer system was field with pure CO2 and measurement were taken. This measurement is shown as line A on graph Fig. 24.

Then the solution of nano CO2 from our test was then injected into the chamber and the graph line B in Fig. 24 was obtained.

The peak region NC in the Fig. 24 shows an increase in carbon dioxide in the solution was once it was introduced into the chamber.

This showing that the CO2 solution is extracting carbon from the chamber or causes reduction in carbon content of the chamber.

This in away showing the absorption capability of the solution of nano CO2 of more CO2 on its own independently, and confirming further from previous results that nano materials are CO2 absorber by their nature of construction, even though these matters are themselves part of the original solution.



Fig. 24 The comparison graph of injection of the solution of CO2 into CO2 gas environment.

In this graph the peak NC showing absorption of CO2 from the chamber and this followed by formation of formic acid as shown in the CF region of this graph through infrared spectroscopy test Fig. 24.

The graph of the CO2 from the solution and its conversion is independently shown in Fig. 26.

It is at this point of gravitation attraction and subsequent Magnetic field repulsion that the magnetic fields strength equal to the strength of the Magravs of the proton and the electron are made available to the system, which these fields are absorbed by the electrodes within the system and then these are past to cooper wire atoms', which are the constituent matters of electrodes and cause the vibration of electrons within the copper wire leading to creation of current in them.



Fig. 25 The graph of the conversion of the CO2 into the formic acid within the chamber.

In the actual physics they call these released packages of magnetic fields or energies as photons as they are released which are then these are absorbed by electrodes placed within the system and used for example to light diodes.

Through development of this technology, production of power without burning fuel and at levels that can meet the demand of a household or a car, is achievable.

Where, for separation of CO2 from environment, in present state of art technologies, energy is used to be able to first separate the CO2 and then cause the formation of formic acid reaction chain, this leading to production CH4 or hydrogen.

Where, through our simple technology, in opposite to the norm, we ***generate energy while extracting CO2 from the environment.*** The method we use is the principle of gravitational positioning and is exactly the way by which matters are extracted and separated in the universe as has been explained in this book.

Our approach is totally different than the present state of art technology, where they use and follow the fundamentals of chemistry, hence the need for their system for energy input to achieve the separation or extraction and we follow the universal method of extraction and holding where magnetic fields as energies are made available through the process.
The example of energy production during the process of CO2 extraction is shown by lighting the diodes as can be seen in Fig. 26.

Where, this set of three LED lights being powered by CO2 capture process. These lights have being on contentiously from 7 pm Saturday 11.12.2009 until this report is release 05.01.2010. Further we expect that these lights will be on for months to come, if we allow the set-up to be running as it is. The intensity of the lights from these LEDs has not diminished and in fact, sometimes they are brighter.

Through development of this technology, production of power without burning fuel and at levels, which can meet the demand of a household or a car, is comfortable achievable.



Fig. 26: Group LED's light

For further investigation into confirmation of CO2 capture and its conversion in their interaction with water to form formic acid, the standard reference infrared spectroscopy graph and data of formic acid was obtained as shown in Fig 27.

To confirm further the conversion of the CO2 into formic acid from the CO2 nano solution from our test, the following procedures were carried out.

To begin with, formic acid liquid with 95% purity was introduced as film on the sample disc of infrared spectroscopy system and the graph FA in Fig. 28 was obtained.

Then a drop of solution of nano CO2 was placed on the film the formic acid and the graph CO2+FA in Fig. 28 was obtained.

When the three graphs are superimposed, that is the original infrared graph of the nano solution of CO2, on the graph of the formic acid and then the graph of the mixture of formic acid with CO2 solution, these clearly showing the absorption of CO2 in the zone 1 in Fig. 28, and then presence and formation of formic acid as shown in the zone 2 of the Fig. 28.



Fig. 27 The standard reference of IR spectroscopy of the formic acid.

This showing the same pattern of presence of Formic acid in the solution of nano CO2, hence not only confirmation of existence of CO2 in the nano CO2 solution, but at the same time the absorption capacity of nano CO2 solution of CO2 from the environment and conversion of these additional CO2 in conjunction with water into formic acid.

Having established the characteristic of the matter within the solution from testes and results shown in Figures 21, 23, 24, 25 and 28, without the shadow of a doubt, the white material is CO2 in nano state, and from Fig. 23, we have the confirmation that this matter is a nano structure in sp3 and behaves as a superconductor.

Further, as the process of the energy production from the system has been extended to days and weeks, the following characteristics and materials have been detected and collected from the system.

In the process of the running the system, the area around the electrodes, which have been specially treated, start gathering a white cloud around them after subjecting the electrodes to certain conditions. From this point on the environment around the electrodes start creating a mist of white material around them, and then gradually the whole containment becomes like milky colour liquid, and then white sediment is established in the container.

Through the infrared spectroscopy shown in Fig. 21, we can confirm that the material in the solution is carbon dioxide and the nano state of this material is very much confirmed by the second test of XRD, as the only match for the dried solid residual of this milky substance shows' superconductivity behaviour of this material. This confirming the nano characteristics of the CO2 as white powder, or in its solid state of matter.



Fig. 28 The superimposed graph of CO2 and conversion o Formic acid and formic acid and mixture of formic acid and solution of nano CO2.

This is for the first time in the world of science that CO2 as gas not only can be captured without use of any pressure, temperature, or energy, but this matter can be extracted and held as a solid at room temperature.

The picture of concentrated nano carbon in solution used for infrared spectroscopy leading to graph in Fig. 21 is shown in Fig 29.



Fig. 29 Solution of nano-CO2

To our knowledge, this is the first picture of nano CO2 solution produced and maintained at room temperature and pressure ever been recorded.

Photographs of dried powder of nano CO2 are shown in Figures 30 A, B, C, and D. These are the first pictures taken of nano CO2 in solid state in atmospheric condition.

This is important as nano CO2 or **CO2 has *never* been observed in solid state at room temperature** and the only solid state of this gas known has been in frozen state of this matter as like of ice blocks (Dry ice).



Fig. 30 A, B: Solid nano-CO2 on a knife and in a vial



Fig. 30 C: Solid and gel nano-CO2

The important point to note is that, there is no content ratio between the CO2 absorbed in the liquid and the water, as is the usual procedure to state in most tests like these content ratios between sediments or gel and the water of the solution.

With this method of CO2 absorption technology, as long as one can extract nano CO2 from the environment or surrounding environment of water, the CO2 absorbed can be removed without ever a need for the change of the water.



Fig. 30 D: The Solid CO2 material in the Gans-state being held in hand at room temperature. This solid CO2 is not a ‘dry ice’, but a mastic-like matter.

In practice, we have a number of times collected Gans of CO2 from the same water within the container. The only reduction in the water is due to vaporisation or when it is part of the gel.

This is a very important and crucial point, and this is where this technology departs from present science of chemistry, and stands on its own merit as a nuclear gravitational system.

That is where if the system were a chemically based system, the CO2 content of the water would have been fixed and hence there would have been a ratio balance and final content for CO2 in the water and this value would have been fixed.

Due to the new understanding of the gravitational systems, as has been explained in the book (The universal order of creation of Matters), these specifically designed systems, with specifically placed and produced electrodes, these systems can create a strong but invisible gravitational and Magnetic fields within the layers zone of the electrodes, that these electrodes, as gravitational positioning elements, can create ***the gravitational pull*** *that can absorb CO2 molecules from the water and beyond the boundaries of the water*, without the CO2 as a nano molecule ever chemically interacting with the water molecules content of the system and going through the normal chemical processes.

Thus; if this was not so, how could electrodes deep submerged in liquid would have been able to extract CO2 from the air above the liquid and bring them into the material of the electrode for them to be separated as individual CO2 molecules on a continues bases, as we have been collecting these materials from the same container over period of weeks.

Where in this processes, as the materials like CO2 become in nano structure of their own state, then they are sealed like the diamond and hence they achieve a self sustained gravitational system, like a planet, that does not interact gravitational or magnetically with any other matter and attain the state of singularity or nano state.

This solution of CO2 material feels like mercury as gel, and to touch it feels cold, but does not stick to its container that much.

After extracting the water from the CO2 gans solution, the matter takes the form of gel and is cream whitish in colour.

Thus, this is a **static nuclear gravitational and magnetic field extraction process**, which has never been recorded or known up to this point.

With this method of CO2 extraction, there are no ratios between the matters collected as nano matters and the water content of the system, as the residual of gans of the gases can continuously be extracted from the environment of the system, without change in the volume of the water of the system.

The point to note is that, the volume of the water content of the system stays the same. Where, the system caries on gravitating to itself gases of CO2 and other gases from its environment indefinitely. But the total mass and the volume of the system increases as gases are absorbed into the system by the gravitational principle.

In fact, the system gains weight, mass, and volume as it absorbs more gases. This phenomenon was observed after the test was completed in Holland in the lab, and the increase in volume of the content of the system was noted at the end of that meeting, that we have more liquid in the bottle than when we started the test after about four hours of testing and running the system for energy production trail.

This is normal phenomenon, as extra gases from the environment of the system have been absorbed in the system and converted to gans, which settled at the bottom of the bottle of liquid.

The snap shot from video of the matters content of gans of CO2 as misty residual matter collected after the test in master bottle is shown in Fig. 30E.



Fig. 30E A misty residue at the bottom of the bottle.

The principle and the technology used for the extraction of CO2 and its containment as a nano matter can be used for making and allowing the production and development of vacuum systems or singular atomic weight extraction systems, which can attain high purity vacuum condition needed for space technologies of the future or in room laboratories for extracting certain molecules or germs.

This vacuuming technique can be achieved without use of any suction system or high-vacuumed pressure pumps as is the norm in today's technologies for production of interstellar space level conditions that are hard to achieve. These systems do not even needs to be adjacent to the system or near the space where the extraction is needed to take place.

In the universe, this singular Magravs strength principle is the exact method used by certain planets or stars and solar systems in managing to extract only certain materials from their solar or galaxy environment respectively. An example of mainly mono Magravs system is few elements material content, being the like Saturn with mainly helium content matter.

In fact in this system we have shown, a micro universal selective gravitational, which in this scale we only absorb CO2 gases from the environment. Where the operation of these systems can be changed and modified to extract any material from any environment without the use of suction or chemical process and so on.

The methane CH4 absorption

During the process of running the system for extraction of CO2 and production of useful current, due to specific configuration setting of the system, specific section of system starts the absorption of methane gas from the environment.

At this point, the water content of these sections of the power system starts to become blue greenish or violet blue in colour, similar to reported colours of the methane in solid state.

Further to confirm the nature of this new material, the same tests as for the CO2 gas extraction was undertaken and results obtained were as follows.

Through infrared spectroscopy test, it is has become clear that this solution has the ability to facilitate the CH4 capture and the release of the residuals of CH4 as solid in the in the dilution of the liquid through the same principles as described above for CO2 gas.

This effect of separation of CH4 as solution shown in Fig. 31 A and B as blue-greenish water and the same colour sediments in the tube.



Fig. 31A. Solution of nano Methane (from two different angles)

Fig. 31B. Solution of nano Methane

The solid dry residual nano CH4 powder is shown in Fig. 32.

Fig.: 32. Solid nano CH4 (gans of Methane)

The process of creation of current and the observation of appearance of residual of solid matter indicates two clear processes:

Firstly, the system starts to absorb methane gas from the environment through the same principle as described through mainly Magravs process as for gas of carbon dioxide CO2.

With the difference that in this case different and specific conditions Magravs strength level by the layers of matters' of electrodes are generated, that this new Magravs strength level facilitates the extraction or absorption of the new material by the system and within and through the system.

As the gravitational and Magnetic fields needed for extraction of the CH4 Magravs are slightly different than the Magravs fields for CO2, hence different combination of Magravs is needed to extract the CH4 from the environment.

Hence, in being able to collect and further test the new material from the solution to confirm the extraction of CH4 from its environment, this proves that, the system has the ability according to its pre-set conditions, to create different Magravs strength within the layers of the electrodes, that can absorb or gravitated different materials to the system such as CO2 or CH4, through operation of the same system concurrently.

Secondly, another process can take place within the system, where the CO2 absorbed in the system goes through process of interaction with water and initiates the production of CH4 and release of molecules of oxygen.

To achieve the production of methane gas through this process, one molecule of CO2 and two molecules of water H2O are required, that by using the energy absorbed by the material within the system leads to production of CH3 radical and then CH4 as molecule.

Where, this process is not a chemically binding rather is Hydrogen plasma gravitated and it is sustained through magnetic field strength within the layers of coating or matters and energies within the system facilitate such a process.

In conventional chemistry, it is assumed at least energies equivalent to eight photons are needed to achieve such a conversion from CO2 to CH4.

Through this method of using our new system, the material of the systems acts as catalyst and magnetic field provider, that such energy (eight photons) are not required, but in fact gravitational and magnetic fields of the plasma of the oxygen and hydrogen of the water become the magnetic field binder for this chain of events.

This being the reason why in similar cases and in theoretical chemistry one needs energy to trigger such conversion, where as through our system the hydrogen and it sister radicals in presence of the free magnetic oxygen, the solution becomes the magnetic bridge, allowing the system to release energy in larger quantities than eight photons, rather than in parallel chemical process in needing energy for the same process to take place in these systems.

In this second path of production of CH4, one needs catalytic effect of the material used in the set-up of the system. In the nature, this catalytic effect needs eight photons of energy for it to take place, which this is usually provided through sunrays.

In the case of our system the conversion of CO2 to production of CH4 and O2 takes place through the layers structural materials and the localised gravitational fields which they generate. As these materials have the ability to absorb infrareds rays too as well as sunrays in the environment and hence these new materials can facilitate the production of the methane and oxygen gases and release of energy twenty-four hours a day.

Thus in fact with the development of this new system, we have clearly shown that for process of photosynthesis, one needs the Magravs strength in the infrared spectrum. Through this process we have clearly shown why plant do their CO2 to CH4 and O2 conversation mainly during the night time, where the infrared radiation from the planet is high, as the sun magnetic field can not suppress their emission upwards from the earth surface. Where, it is known fact that the earth is the best suppler of infrared rays.

Further on, to show the correctness of our technology and that we do not require energy to extract CH4, where in fact we produce energy as power supplier through our technology, the engineers at the lab proposed to connected our system to an electric fan, to see if the poser produce can run mechanical devices like this on a long term. As can be see in Fig. 33. Where we ran the fan for over an hour.



Fig. 33: Turning fan powered by CH4 extraction system.

This test was done in presence of a journalist and engineers from the magazine that we cooperate with and all has been videoed. The test happened in the basement of their premises, in the absence of any sunlight.

Energy release by the process of gravitation and extraction of CH4 creates more energy and stronger current than the same process of absorbing CO2 from the environment. Where, this process leads to creation of strong current rather than stronger voltage output from the system.

The absorption of CO2 from the environment and conversion of it into formic acid and release of energy needed for the photosynthesis and where at the same time the CH3 stage of methane gas as methyl becomes first stage for the production of sugar bases in organic materials has been observed and videoed with operation of one of systems.

Thus for the first time the process of photosynthesis can be shown to take place exactly as happens in a nature like in a tree through these systems can be demonstrated.

These systems not only absorb CO2 from environment, but through their process of conversion, they can lead to production and released of oxygen as molecular structure.

To confirm and be able to show such a process takes place within the process of the production of methane and oxygen and hydrogen from our system, it is essential to show that methane in nano state of matter as we have collected in our system is or has a superconductivity behaviour, as was shown for CO2 nano material.

For the confirmation that the captured CH4 solid material is or has a ***super-conductive*** behaviour, we subjected the solid residual of the blue-greenish matter to XRD testing in the laboratory.



Fig. 34 The XRD of the superconductor characteristic of nano Methane solid

The result of this test has to be noted that CH4 as CO2 in nano state has superconductivity behaviour detected seen in XRD is shown in the graph of Fig. 34.

The nearest material composite match to this material characteristic of our solid matter is beryllium palladium, which matches by 95% as a superconductor behaviour only. The list of near enough matches as superconductor to CH4 in nano state can be seen in the table shown in Fig. 35.



```
Comment:
Scan Type: 2Theta Scan
Start Angle: 5 deg.
Stop Angle: 90 deg.
Num Points: 4251
Step Size: 0.02 deg.

Name=Beryllium Palladium / Be Pd
FOM: 0.950      Total Matches: 6      Total Lines: 6(11)      Card: 65-3196

Name=Beryllium Palladium / Be Pd
FOM: 0.946      Total Matches: 6      Total Lines: 6(11)      Card: 18-0225

Name=Sodium Silver Chloride / Na.903 Ag.097 Cl
FOM: 0.942      Total Matches: 6      Total Lines: 6(9)       Card: 77-2065

Name=Sodium Chloride; Halite / Na Cl
FOM: 0.936      Total Matches: 7      Total Lines: 7(9)       Card: 75-0306

Name=Sodium Chloride; Halite, Syn / Na Cl
FOM: 0.905      Total Matches: 7      Total Lines: 7(17)      Card: 05-0628

Name=Sodium Chloride / Na Cl
FOM: 0.866      Total Matches: 7      Total Lines: 7(9)       Card: 77-2064

Name=Strontium Nickel Niobium Oxide / Sr ( Ni Nb2 )0.333 O3
FOM: 0.860      Total Matches: 5      Total Lines: 5(12)      Card: 89-3113

Name=Manganese Tellurium Selenide / Mn Se0.8 Te0.2
FOM: 0.837      Total Matches: 7      Total Lines: 7(9)       Card: 89-4969

Name=Strontium Niobium Oxide / Sr0.72 Nb O3
FOM: 0.827      Total Matches: 5      Total Lines: 6(12)      Card: 80-2497

Name=Barium Strontium Zirconium Titanium Oxide / ( Ba0.25 Sr0.749 ) ( Zr0.283 Ti0.715
) O3
FOM: 0.785      Total Matches: 5      Total Lines: 6(12)      Card: 89-8212
```

Fig. 35 The nearest data of matching materials available that match the green blue powder superconductivity characteristic to the extracted nano methane solid from the solution.

The comparison of superconductivity characteristics of the CO2 and of the CH4 nano materials obtained by XRD and matching and similarity in behaviour of carbon dioxide CO2 and methane CH4 as super-conductive nano materials are shown in Fig. 36.



Fig. 36 The XRD superconductivity characteristic comparison of nano CO2 and nano CH4.

The common behaviour between the CH4 and CO2 nano matters have been observed and shown by superimposing their infrared spectroscopy graphs as shown in Fig. 37.



Fig. 37 The IR spectroscopy comparison between nano CO2 and nano CH4 in solution

In this graph the CO2 in zone 1, shows extraction of CO2 gas from its environment and then forms formic acid as seen in zone Z2. Similarly methane (Me) releases increase the availability of CO2 in the environment of the chamber of the spectrum machine as seen in zone Z1, and then the same releases' of formic acid as the same as CO2 as can be seen in the zone Z2 through this process.



Fig. 38 the enlarged section of the CO2 and CH4 in infrared from Fig. 37.

This explaining two factors, one that the solution is processing both CO2 and CH4 extraction simultaneously and or it is has the ability to produce CH4 through CO2 absorption and the water chain interaction as was discussed before.

Enlarged section of the zone Z1 in Fig. 37 are shown in Fig. 38.

Superimposed graphs of these nano materials of the same region in graph 37 are shown in Fig. 39.



Fig. 39 The superimposed and enlarged section of carbon sector of the Fig. 37.

Observations and notes.

In the development discussed above, one has shown how by absorbing CO2 from the environment, this being on earth or as the content of craft, this gas can be used to generate energy and oxygen to sustain life without the need for additions reserves of these gases using the man himself as the supplier of the main ingredient matter, the CO2.

What this new technology offers for the planet earth is a survival line that in the present environment of the global warming with the CO2 generated by burning of fossil fuels and production of methane gases produced by extensive cattle farming, through the utilisation of this new technology for the first time ***these gases can be extracted from the atmosphere and simultaneously be converted to solid matters or solution, this process can be used to lead to, and cause the release of energy, and through the use of specially developed composite materials, this leading to separation and generation of oxygen.***

Where some of methane and carbon dioxide in the form of nano materials of the same gases can, all be suspended in the solution or dried as solid and reburied or returned to earth as topsoil.
Where this new technology shows for the first time and make it possible to achieve creation and holding of carbon dioxide or methane gases in solid state at room temperatures and pressures. Through evaporation of water from solutions, solid of carbon dioxide CO2 and methane CH4 gases in the form of powder nano materials of these gases are produced.

This new system and technology completes the circle of life for maintenance and existence in the future while it can clean up the mess man has created by the use of fossil fuels on earth in the past centuries.

Where these new systems will behave as trees on earth and for the passengers of space systems of the future, by simple converting CO2 into oxygen, and where the man himself becomes the supplier of CO2 for the system to keep the cycles functioning.

Through the development of the technology that has been disclosed in this paper the initial steps to conclude this process for application in our space technology is considered to be completed. In the space technology of the future, one has to be able to use all matters available within a spacecraft to attain continues and sustainable existence of man in deep space travels.

This technology of direct extraction of CO2 and CH4 from the environment can happen in reactors of small and large dimensions. Thus the technology can be used to tackle the Climate Change problem. For example large installations can be connected to exhaust systems of heavy industry, and small extraction devices can be made for households or be built in cars. None of these installations will need powering, as they will deliver themselves electricity. On the other hand we don’t have a sequestering problem since the CO2 and CH4 are already in a solid state, which make storage easy. However our liquid and solid CO2 combined with limonene oxide can also be used to make new type of polymers and plastics.

We have developed and attained a fully integrated system that is able to sustainable life in space.

In letting the process of CO2 absorption and production of energy to continue, some cells of the system start the process of production of methyl CH3. This is a significant process as this shows organic process as CO2 is in progress within the system.

Further, this process in conjunction with its water content, and nitrogen from the environment, can itself lead to production of natural sugars, starch and proteins, using our simple static gravitational system.

This simple system can be used not only to clean up the environment from CO2, but at the same time the same CO2 can be used in conjunction with specific matters of the system, to release energy, oxygen. Further at the same time producing CH3 and methane and formic acid and by use of nitrogen this leading to production of protein(s) that can be the food supply for the humans' passengers of spacecraft's of the future while they inhale oxygen and exhale CO2.

Thus through this new technology mans' existence on board of the spacecraft's of the future, the man becomes the container and supplier of carbon dioxide and hence the provider of oxygen for his own existence.
Thus, man himself becomes the conversion system to maintain his own survival in deep space or on earth during shortages of food or natural disasters.

The property of this system has allowed us to submit a full patent for the first full day and night energy panels.

New state of matter

When considering this new technology and understanding the potential of its physical ability to convert gases into solid state of the same, where up to present knowledge the gas from being able to take the shape of its container, for the same atom or molecule becoming the container of itself as a nano matter, then this new state of matter or the solid state of the gas at ambient conditions like the room temperature and pressure, ***itself becomes the nano matter of the gas*** and this state of matter has never been known in the world of science and has to be considered to be a new state of Matter or the fifth state of matter.

Where, through our development of matters in our technology we consider solid, liquid, gas, plasma, and dark matter as the first five known states of matters up to this point in our technological development.

This being due to the fact that this new nano matter of the gas in solid state, it does not behave and looks as any of its old states of matters or any other state of matter as we have known and what we have seen before from these matters.

The infrared and XRD testing of these carbon dioxide CO2 and Methane CH4 gases in nano state showing that this matters behaves like a ***superconductor material***, where nor hydrogen or hydrogen and the carbon in there matters are considered as super-conductive materials in the present world of science known knowledge in their gas state of their molecules.

To our present knowledge superconductors at these levels are by principle of matter in diamond structure or sp3 state of matter. Where, their physical gas equivalent of these matters known to science and are classed as odours.

Thus as in this new state of matter molecule of GAs which becomes Nano of itself and become and appears as Solid state of matter as we have seen from our testes and shown as solid of the matter in this paper, this new state of matter needs a new name, for it to show the source of the matter, that is from GAs to Nano of Solid and to be called **GANS** for short.

This new name in fact clearly not only indicating the source of the matter, which is the gas, but at the same time it clearly explains what to be expected and describes the characteristic of these matters too.

Where these new characteristics being like superconductivity, lightness, singularity of grains and so on, of the same molecule as it become nano of itself and become solid of itself but having full molecular structure of a gas, but self gravitationally and magnetically closed and singular, but it still can be in a gas state of itself, but as it becomes singular atom or molecule of itself it behaves as solid matters do.

Thus from this point on, we do not call these solids of nano of gas or nano CO2, but **GANS** of CO2.

First ever pictures of these matters in Gans or solid state are shown in Fig. 30(A-D) for CO2 solution and dry state.

Pictures in Fig. 31A and 32B shows the first ever solutions of methane and dry or gans of CH4 respectively.

Through experiments and deliberate mixing of different gans in one solution, it is clear that these materials do not mix or do not chemical interact with each other. Where each gans of each matter stays separated from the other matters within the solution, and stays the original gans. Fig. 40 shows a mixture of three gans in a solution, where they stay without any chemical binding, where for example the green residue settles can be seen at bottom of the tube.

Similarly for the first time in the world of science, through understanding of this technology, we can capture odours as solid? But the question is that, would they smell the same as their sp3 counterpart as gases? This is the question to be answered and explored in the times to come.

Parallel with development and extraction of gans, these systems produce energy, which are not due to burning of fuel or chemical conversion like in a battery. The energy produced during the process of gans from any system, which this energy can be used for any purpose, this being creation of gravitational field force to create static sources for creation of Magravs, power to run a motor or light-up a lamp, this new source of energy needs a clear and new name classification.





Fig. 40 Different Gans do not mix or chemically bind, and stay separate in the solution.

We call this new method of production of clean energy, this being in magnetic field force strength or electric energy, the **GAs Nano Solid Energy** or GANSE for short or Gas Energy Solid for short **GES**.

Implication and applications of this new technology

In the development of the technology discussed above, we have shown how by absorbing CO2 from the environment, this being on earth or as the content of craft, this gas can be used to generate energy and oxygen to sustain life without the need for additions reserves of these gases using the man himself as the supplier of the main ingredient matter, the CO2.

What this new technology offers for the planet earth is a survival line that in the present environment of the global warming, with the CO2 generated by burning of fossil fuels and production of methane gases produced by extensive cattle farming, through the utilisation of this new technology for the first time these gases can be extracted from the atmosphere and simultaneously be converted to solid matters or solution and return of this matter as solid into the ground,

The development of this new technology shows and makes it possible, for the first time in world of science to achieve absorption and containment of carbon dioxide or methane gases in solid state at room temperatures and pressures.

Through evaporation of water from solutions, solid of carbon dioxide CO2 and methane CH4 gases in the form of powders nano materials of these gases can be produced, where in later stages in different applications like manufacturing processes, these materials can be added to effect the physical or the property of different matters or produce new types of matters with these new materials.

These new matters of gans can be used for example as new biological nano filters, where their purity or the molecular size of gans can determine the matters to be filters, this being cancer cells, germs or other matters.

Through the use of this new technology the circle of life for maintaining a clean environment in the future, while it can clean up the mess man has created by the use of fossil fuels on earth in the past centuries.

Where these new systems will behave as trees on earth and for the passengers of space systems of the future, these systems by simple converting CO2 into oxygen, guaranteeing ever supply of life essential need, where the man himself becomes the supplier of CO2 for the system to keep the cycle functioning and guaranty his own survival.

In our tests, in letting the process of CO2 absorption and production of energy to continue, some cells of the system start the process of production of methyl. This is a significant process as this shows organic process in progress within the system.

Further, this process in conjunction with its water content, and nitrogen from the environment, can itself be used to lead to production of natural sugars, starch and proteins, using our simple static gravitational system.

This simple system can be used not only to clean up the environment from CO2, but at the same time the same CO2 can be used in conjunction with specific matters of the system, to release energy and oxygen. Further at the same time producing CH3 and methane and formic acid and by use of nitrogen this leading to production of protein(s), that can be the food supply for the humans' passengers of spacecraft's of the future while they inhale oxygen and exhale CO2.

Through the development of this technology that has been disclosed in this paper, the final steps to conclude the process for application of these systems in our space technology is considered to be completed.

Where, these CO2 extraction systems, by their nature of operation as described above, they can become the natural backup energy systems and vacuum systems for spacecrafts of the future.

With the completion of this sector of our technology, we have developed and attained a fully integrated system that is able to sustainable life in space. Where we have shown through other sectors of technology, systems for motion with gravitational positioning through our nano materials we have shown how to produce matters in the universe and materials to manufacture for what man needs for food and habitation, then we have shown how to develop the system to feed and produces systems to cure ailments through our medical application section, and in the energy production system we have shown how to generate energy through simple natural process, and finally now with this technology we have shown how to create a self sufficient environment to sustain life with extraction of CO2 and use of the same to create oxygen for man to survive in space.

Thus through this new technology mans' existence on board of the spacecrafts of the future, where the man himself becomes the container and supplier of carbon dioxide and hence the provider of oxygen for his own existence is complete.

Thus, man himself becomes the conversion system to maintain his own survival in deep space or on earth during shortages of food or natural disasters.

The property of this system has allowed us to submit a full patent for the first full day and night energy panels and all other points which has raised as new science in this paper.

Conclusion

Through new and simple methods which has been developed and explained and production of new materials with some new properties which has been confirmed, we have managed to create and establish clearly how gases can be made to be contained, extract and converted into solid state of matter, without the use of any chemical reaction, temperature or pressure, and simply through creation of condition of mini and localised Magnetic and gravitational fields within the system, as is done in the universe.

Where, these fields are hidden within the static layers of different matters within the system, as they have been chosen as the electrodes within the structure of these systems.

Where clearly in picture Fig. 40, one can see that these matters are normal solid and can be handled like any other solid matter.

Clearly from the infrared spectroscopy and XRD graphs of these matters and solution it is clear that the matter absorbed or extracted from the environment, as gans are so pure and in nano state that their spectroscopy recorded data is as close as to perfect theoretical for CO2 gas. This purity of the matter, showing itself in such clear and single perfect lines of graphs shown from the test of the actual sample of the solutions of these ganses.

At the same time, it is confirmed that nano gases do behave as their metallic and semi metallic matters in the universe and they become or attain the behaviour of conductors and superconductors and super resistors. Where this finding of the behaviour of these gans solves and answers a number of unanswered questions in the world of physics, chemistry and biological binding, movement and motion of planets, stars and matters in cosmos.

This paper in its simplicity of its presentation and the knowledge it has put forward, it will in due course bring about fundamental new ways that a number of problems in the scientific world concerning gases and solids are to be considered.

For example we can think of ways to solve the mystery of the ***a-biogenesis*** (the study of how life on Earth could have arisen from inanimate matter.) or how proteins could have been created in Space by local super-conductive conditions.

With the knowledge gained with the operation of these simple power cells, new systems in production of vacuum, creation of matter, extraction of matters and conversion of matters can be developed, and in a way this paper opens a new an unbelievable horizon to the man for science and space technology of tomorrow.

We have shown and clearly proven not only one dose not need all sorts of machines to create or extract matters from the environment but simply following the laws of universal gravitational and magnetic field forces, one can achieve the same in a much simpler ways, and instead of using energy to achieve production of a matter, one can extract energy from the same system and achieve better results in doing the same process.

Additional pictures

Some pictures of different matter, which have been gravitated to the system, are shown in the picture below.

Up to this point we have managed to attain six different elements in gans-state, which each one has it's own colour as can be seen in sample tubes as they have been extracted from the system during it operation, while producing energy. Some of the materials shown have not been subjected to IR and XRD spectroscopy to confirm the composition of the original gas before they were converted to their gans-state.



Fig. 41. Six different materials in gans-state which have been gravitated by the system up to today (05.01.2010).



Fig. 42. Two different materials in gans-state, which have been gravitated by the system, which we think these, are organic gases in Gans-state. They have different orange colours.



Fig. 43. CO2 in gans-state , which have been gravitated by the system. It contains solid flakes within the solution



Fig. 44. Different angle of show from the same solution as figure 23. CO2 in gans-state, which have been gravitated by the system. It contains solid flakes within the solution.



Fig. 45. Unknown composite material in gans-state which have been gravitated by the system.

Chapter 5

The light and its interaction with the Principal star

The Principal Star is what has been commonly called the Black Hole (3) and it is understood that these entities are places, where the principal mafs and matters are create and collected.

The pmf of principal star being covered by dense layers of the transition mafs, this being the reason as why they look to be dark or where there are no lights are transparent in these regions in the specific parts of galaxies in the cosmos (Fig. 46).



Fig. 46 Structure of the principal star

The light being in possession of the gravitational and Magnetic fields of its own and consequently the light having the Magravs of its own, these fields forces' of the light in matter magnetic field strength environment of the universe take their positions in respect to the Magravs of these principal stars in the centre or any other part of the galaxies.

In these environments in the universe one can observe that as the light rays come close to the principal star the light in majority of cases will not be absorbed by the extensive gravitational fields forces of the principal star, but the light ray finds its way by going around the principal matter star instead of as it being absorbed by this entity. This ability of bending of the light is commonly called the lensing of the light near large objects, and this is the process by which currently scientific world can confirm the existence of the principal star in the universe.

The reason for the bending of the light being due to the fact that as the light possess its own mafs of the principal matter, then the light's principal mafs Magravs take their Magravs positioning in respect to the principal star mafs' and matters' and this positioning of the two Magravs of the principal mafs of the light and the star from the point of an observes from a distance looks as the light bends around these objects or what is called lensing phenomenon of the light around the Principal star occurs (Fig. 47).



Fig. 47 Bending phenomenon (lensing) of the light around the Principal star due to Magravs positioning

The theory that even the light will not escape the Principal star gravitational field forces once passes the event horizon, this shows the lack of the understanding of the scientists in this respect too, as if the scientists had the tools to observe and could detect the principal mafs magnetic field spectrum, then they could observe that as in matter mafs stars like the Sun of the earth's solar system, these Principal stars will radiate pmfs in the principal mafs strength spectrum and the Principal stars are like bright shining stars in their environment, and as they absorb light in matter's spectrum strength, they at the same time release light in principal mafs and transition mafs pmf strength simultaneously.

In time the scientific world would produce tools that with these tools they will be able to observe the motion and emission of the Principal and transition lights rays from these dark spots in the universe. Then one can observe that light in principal mafs strength are emitted from these stars in the galaxies as light are emitted from the Sun of the solar systems and the disappearance of the light in even horizon is only illusion and not a reality as the pmf of the light mafs get diluted in the stronger pmf fields of principal and transition mafs rays.

The concept that how principal stars are created, how they operate and how they absorb and emits some light has been disclosed in detail in the paper written in 2002 and published in 2006 titled "The creation of Back Hole".

Principal stars if they absorb mafs and of the matters, stars and visible light as it appears to human eyes' vision spectrum, then they can and they do at the same time emit light in the mafs of the principal matters spectrum into the environment of their galaxies too, as this was not the case then the conservation of principal mafs and matters in the cosmos will not hold and this is against all the laws of physics.

In reality the dynamism of the mafs of the principal matters in these stars and the light they emit is the cause and deliverer of pmf needed for the creation of matters and stars in the galaxies.

In a simple way, as the light from the Sun feeds its own solar system mafs of the matters and matters the like of its planets, the same is done by the Principal star through its light emission in the Principal mafs pmf strength feeds all mafs and matters in its captured Magravs sphere or so called its galaxy.

At the same time the Magravs of the Principal star dictates the position and attraction of other matters, stars and galaxies' in respect to itself as the total mass of the matter mafs and transition mafs of the matters in galaxies are about less than five present of the total mass of the galaxies (3).

Thus the positioning and directional motion of the galaxies in the universe, the same as in the solar systems is dictated by the mass of the principal mafs and matters of the principal star of the galaxy and no other factor (3). Therefore the mass of the galaxy is the measure of the interaction of the Magnetic and gravitational fields' forces that the principal mafs contents of the principal matter can produce and maintain.

Once these principal stars are formed in the universe then the Principal stars and the lights which are releases form them become the means of the supplier of pmfs and nourishment of to the environment of these galaxies" (3).

The concept of the structure of the principal's star lights as the source of pmf into its heliosphere zone is applicable the same but in much smaller quantity of mafs of in the operation of plasma of an electron, proton and stars too.

In the modern science the source of the creation of matters in the plasma of electron and proton are mysterious entity, which lead to creation of quarks, bosons and other names content of the plasma, in fact for example so called the bosons are the pmf of lights released by the principal mafs of the plasma, which as this dynamic light reaches a given point and given pmf strength in the plasma of the proton or electron due to reduction in its pmfs strength in motion in the plasma, this leads to appearance of matter mafs and matter of different pmfs strength in all regions of these plasmas.

The mysterious forces which the scientific world has been observing in the plasma of the proton, these are released by the principal star of the plasma itself as lights in the principal mafs strength unwinds and as these lights reduce in strength to different mafs and matters pmf levels strength. Then these slowed down pmfs lead to appearance of different weaker matter pmf strength in the content of the plasma, where and when two matching field's strength and matters strength can interact that they can create a given gravitational fields forces within the plasma then these points of gravitational field appears as bosons and other named entities within the plasma. At the same time these entities create their own Magravs which the operation of fields forces of these Magravs appear as mysterious filed forces within the plasma of the proton or electron.

Theory of Higgs and Higgs boson concept: In fact if these scientists would have understood that the interaction of at least two magnetic fields (bosons) leads to creation of gravity (attraction) and Magnetic fields (repulsion), which further interaction of these two fields of Gravity and Magnetic fields leads to creation of the mass of the matter (Higgs), then Higgs would have understood that interaction of magnetic fields not only in plasma but in any level of magnitude in the universe leads to creation of matter which this matter always possess its own mass and magnetosphere, or in other word when two magnetic fields interact they lead to creation of mass which is the maximum strength of the gravitational strength less the Magnetic fields strength created by the interaction of these two secondary fields (1). Thus Higgs theory is correct and in reality one does not need to smash an atom in accelerators to observe and prove his theory, but it would be easier to the same behaviour of production of matter ***if two rays of light are fused*** that **they lead to creation of matter** and thus the Higgs theory would be proven to be correct in a simpler way.

This is process of the production of bosons, Higgs and other entities in the plasma of proton is the replication of the same process as the operation of light rays in the solar system changes to matter in different pmf strength regions in the heliosphere of the star, where in the case of plasma of proton ***the same process takes place in micro/nano level*** of the mass of the principal star and principal mafs and matter in size.

Stars in the centre of the galaxies in motion near the Principal stars even though they release rays of light but not all these rays get absorbed into the principal star or the stars themselves and in reality the Principal stars do not absorb all lights from the matter stars (the sun is a matter star) into themselves as the plasmas of the lights in the matter mafs pmf strength contain their own principal mafs and matter and these principal mafs of the light create their own pmf Magravs, which this Margrave allows the light to take its position in respect to the Principal star which is so close to, and this Magravs positioning of the light allows the light from the star in the matter strength to move away from the principal star as is observed by the astronomers. In fact the speeds and the distance of the star from the principal star is dictated by their own principal's mafs content and the Magravs strength.

The matter stars in their inner sanctum contain and hold on to large quantities of the principal mafs and matters (1), This meaning that even the Sun in its process of feeding light into its heliosphere, at the same time in this process the Sun *releases a large quantity of the magnetic fields of the principal mafs and matters as the* ***principal light rays strength of magnetic spectrum*** in this environment.

It has to be said that in galaxies, the high speed of the rotation of matter stars near principal stars has to be extremely high, this being due to the fact that as the matter star itself contains principal mafs and matters and at the same time these mafs of the principal matters interact within the structure of matter star that they create their own gravitational and Magnetic fields that the matter star takes it principal mafs Magravs strength positioning in respect to the mafs of the principal star matters and mafs Magravs. Thus the only way that matter star can hold on to its pmf structure is to attain a high speed as its mafs of the principal matters of the matter star content have to find a constant continues renewing its new position in respect to the principal stars matter's and mafs' content. These high speeds of the stars near the principal star has been puzzling the cosmologist, but if they look close enough and as they could understand the principal of the rotation of an electron in respect to the proton of an atom (1), then the speed of the matter's star with composite matter and mafs content near the principal star shows and is flowing the same path and the same principle of motion as an electron does in respect to the proton in the nucleus of the atom as electron moves fast around its nucleus to maintain its position and hold on to its content matter (1). Thus now may be the high speed of the matter stars near principal stars can be explains and the single directional orbit of the star matter in these regions confirms content of the Principal star as to be mainly as of the Principal mafs and matters, that this singular mafs and matters contents' of the principal star allowing the more circular motion or elliptical motion of matter stars with their large mass near the Principal stars.

This is the same process as to replacing the proton with the principal star and the electron with the matter star, with parallel high speed dynamic motion of the matter star with controlled Magravs positioning around it nucleus. The reason that the motions of the matter star around the principal star is not as unpredictable as of motion of electron around proton (1); this is primarily due to mono content matters and mafs of the principal star. In fact in these cases the light observed by the cosmologists created by the matter star is mainly due to the interaction of Magravs of the two matter and principal stars, and at this point the Magravs of the matter star has to find rapidly its position in respect to the Magravs of the principal star, and this is how the matter star become to attain speeds' in the region of the speed of light in matter pmf strength. Thus the majority of the visible light of the matter star in close proximity of the principal star is not of the star itself but it's due to the interaction of the Magravs of the two stars. Now one can see another marvel of the universe, where matter mafs in creating light which itself is the light of itself.

This concept of mass moving at speed of light in matter pmf strength environment due to interaction of principal mafs strength will have such a profound effect on the man’s scientific progress and in man being able to travel the depth of universe and this will be the point of and the tool of detection of future space crafts in motion at speeds beyond the speed of light in matter mafs strength and above in the cosmos, once the concept of the light rays in the pmf strength of principal mafs strength are understood fully.

Chapter 6

The light and its planetary interaction

The interaction of different lights of different matters (principal, transition and matter) can be utilized to create the appropriate magnetic fields and currents and gravitational fields' forces as it is needed for any purpose, then this concept of interacting lights is the way that food and energies from the right light mafs levels can and will be produced in deep space travels of the future, as one can take the right components and amounts of the mafs in matter field strength needed of any required levels of mafs as/and for nourishment of the mans' physical body, without man actually eating tangible food.

This conversion and absorption of light rays is in fact what plants and animals do in the earth environment as they absorb specific plasmatic magnetic field strength of light spectrum and due to their atomic and molecular Magravs field's strength they create measured vacuumed condition within their structure to and for transformation of a given pmfs' strength of the light to be converted this to gans of that mafs in the structure of the plants or animals. Which, these ganses have Magravs equal to Magravs strength of vitamins or minerals levels as the planet produces or the animal needs for existence in a given environment. The process of production of minerals and vitamins in understanding how light is and can be converted to gans in earth atmospheric condition will allow the production of the same matters and vitamins by use of the light matters' structure in conjunction with the using a simple dilution Magravs positioning reactor anywhere in the universe (1).

For example man by eating a given plant, he absorbs that spectrum of the fields transmitted and absorbed from the spectrum of the light mafs of the matters fields for specific use in specific protein in man's body, and now man has the knowledge to produce the same proteins and minerals from the light rays without the need for plants or animals as an intermediary conversion toll for this process.

In earth atmospheric Magravs condition herbs absorb pmf of the higher strength of the same light as normal plants do and the meat can absorb the complex strength magnetic fields of the light. The structure of herbs pmfs attraction and storage is more dependent on the pmf emitted by the light spectrum from the earth fields as the fruits store most of the light spectrum which are entered into the atmosphere from above and that is why each entity has different mafs strength storage and conversion capacity and capability. Where, the same light from space in different distance and interaction with the magnetic fields strength of the light of the earth leads to creation, storage and production of different pmf spectrum of the light by the same plant and animal DNA.

The ray of light in its entry into the magnetosphere of the earth and the interaction of the two Magravs lead to release of specific characteristic rays of specific magnetic fields strength, that this ray through a special process with the hydrogen atom lead to creation specific division of energy that can sustain life on this planet. This ray and its process of creation, which is not known in the world of science presently has been fully explained in the book "the universal order of creation" to be published in the future. We see that in time man of knowledge would be able to comprehend this process, and once this process used then the wisdom of all creations in the universe will be understood and can be replicated anywhere in the universe.

The rays of light at any strength of its mafs at their entry into any dynamic plasmatic environment have the ability to lead to or through conversion process cause the initial chain of reactions needed for the start of life and then the matters produced use the light itself to further create more cell like beings and then through the ray of light conversion in these cells this leading to final step that the light ray in becoming the creature like man, then using light rays and its product main gains intelligence and the intelligent body at this stage acquires its magnetosphere and Magravs or what is known its ***soul***.

Chapter 7

The use of the properties of the structure of the pmf of the light for space technology

As the man's knowledge reaches and becomes in line with realities of creation; in the future the mafs of all components of the light and the phenomenon of light rays entanglement will be used for space technology in an efficient way and in manners which are not even comprehendible at the present.

The helixial cylindrical motion and reversibility capabilities of the outer-magnetic mafs of the shell of the light in space reactors of the future will be the key in control of the motion and the directional motion which these crafts can travel and the same time the control of the speed of the motion of the space crafts of the future can be set by using the matters' components of the light.

The gravitational fields' forces of the light and the reactors using and producing light gravitational properties that can be used for control of the directional motion are much easier systems to produce in a fully integrated combination space reactors setup that using different mafs' strength of the light makes take-off and landing possible in every environment and pmf fields strength in the universe, without putting the craft and its passengers ever in any danger. Where, with the use of the lights' mafs Magravs technology one can reach the deepest part of the universe in time spans that are within the fraction of the life of humans, rather than the present assumptions of thousands of the light years. In comprehending the concept of the structure of the light in full; this will the time, when the Man understands the truth about the world of creation in the universe, and how universe was created and real universal motions are created and maintained.

How, different rays of lights get entangled and leads to creation of conditions of mafs of matters is due to Magravs positioning of one light ray in respect to another of the same. The Magravs positioning of two rays of lights or what is known as the light–entanglement is the condition for example, where and when the light rays can converts from mafs of matters to characteristics of tangible or detectable matter in a given plasmatic magnetic field strength environment.

It has to be noted that there is fundamental difference in light entanglement and fusion of light rays. The ***fusion of the light*** is more fundamental process in production of matters and mafs and this process can be used for production of stronger light rays or for the production of heavier elements without going through the process of the matter state fusion. This being the like of the production of oxygen molecules through the fusion of light rays, rather than multiple fusion processes of the rays of the light's once the neutron to an atom of hydrogen is reached, and then through multiple fusions processes to reach the production of oxygen molecules.

In fact fusion of the matters of the light does not require energy and in reality does not lead to release of vast amount of energy. Whereas, in the present process of fusion of the matter of hydrogen the present fusion scientists have got themselves tied up with the wrong concept and technologies and they are in the dream of achieving fusion of matters through the use of present laborious fusion reactor technology with very little success.

By the same default in understanding the real process of the fusion in the universe, there has been a misconception by nuclear scientists in production of the heavier matters through fusion of matters in the centre of stars and in their nova process. Where, the **present assumption** that matters are created in the centre of the stars through process of fusion of matter **is not in reality correct**, whereas the process of fusion and production of all matters in the universe primarily takes place at the *point of the fusion of the light rays* ***first,*** then as the light rays become to the point of matter mafs strength they first *all convert to gans of the neutron* and then through process of the Magravs positioning and collective balancing of these forces of the total light rays in a given environmental pmf strength, then some of the light rays once converted to neutrons some stay as neutrons and others of the weaker strength in the collection go through the process of the neutron decay (1) and become proton and electron of the collection of the light rays and hence in a given pmf strength, the physical matter with given number of neutrons and protons and electrons are created. Therefore, it is the collection of fused light rays which changes to collection of neutrons and then as some neutrons go through neutron decay and become proton and electron, this is *how* ***atoms of different matters are created*** *in the universe*. Where, further this process of the light pmf strength matching through light-entanglement process is a much easier process than the matching and fusing physical plasma of atom or molecules and solids.

In fact this is how neutrons are found to take their place in the centre of atoms to start with and this is how fusion takes place in the ***real universal cosmos*** (unicos). This being one of the reasons why the present science have problem to produce fusion as they try to fuse matter as in real term in the universe and in the centre of the stars fused light rays lead to creation of matters of different mass.

Fusion light **ray reactors** are simple practical systems which do not need very much energy for them to run and operate, but they can create and facilitate *directional motion of the space crafts of the future* using their capability to split the plasma content of the light to its sub structure matters and fields and create Magravs of different strength and in a cylindrical reactor of the same to stack the light rays gravitational and Magnetic fields forces for creation of the directional change and at the same time these reactors can be used for the production of the matters for the use in the space environment of the future.

For the space technology of the future there is a need for multiple light reactors that an instantaneous three hundred and sixty degree spherical motion of space crafts can be achieved and the at the same time the shielding magnetic fields can be interchanged from matter mafs to principal mafs and change of the dynamism of the same fields can be used for rapid deployment and penetration in dangerous and denser matter and mafs parts of the universe.

The same entanglement or interconnection process exists between light rays as does and prevails in the atomic and matter environment. At the present time the scientific world is considering ***quantum entanglement*** and its use in transportation of matters and other uses within and across the boundaries of the universe. In reality if scientists comprehend the concept of the light–entanglement and understands the principle use of this phenomenon, then one can use the matching structure plasmas of light rays before they become matter to achieve high speed transportation in the range of and beyond the speed of principal light rather than limited speed of the light in matter environment as man is considering to be the ultimate speed of motion at the present.

In entanglement process one can/and have the capability of use of different mafs of the lights for crossing the universe, and without change of physicality of the plasma and change of its state and then at this stage one can even copy and lock the same plasma of the light that in Magravs positioning of one plasma in keeping its connection with the same plasma of the light of the same strength or length in other parts of the universe.

If this concept of light interconnection and complex light-entanglement of Magravs of light balancing is understood and replicated then feeling, like touch, loving and hate and so forth can be transported across the universe without actually the matter or being ever crossing it physical boundaries. Thus coping atoms and interaction of the atoms and even the emotions of the matter (which complex, vibrational and rotational based) of one atom or light to another can be transported across the universe using light entanglement technology.

In fact this is how dreams in the inner sanctum of the human brains are created and take shape and give the man the image of seeing and communicating even with people which they have never physically met or to other Magravs of other beings which in their time of living in that give environment their Magravs of the dreamer and dreamed of have been exposed too.

The light entanglement is a real and correct physical process, where certain cells within the inner brain or thought control systems of the living being has the capability to operate within these pmf mafs strength and this is the natural part of the operation of the brain of the human beings that scientific world has not mastered to unravel.

In fact the light entanglement communication method called telepathy is the easier way of communication than using the ears or other method of listing and talking and the place for this system seats in the inner parts of the man's original main brain structure.

The light entanglement technology will allow collective entanglement and different strength molecular light entanglement allows the full structure transportation and even continuous motion replication of the molecules. This meaning the transportation through the light plasma entanglements of let say heart, brain and all tissues at the same time, with the same heart beat and the same liquid with emotion of the entity across vast points of the universe becomes a possibility of the use of this process. Where, the light in all its pmfs of all its mafs of all matters and strength are available in all corners of the universe and all needs to be done, is to re-produces the same strength and combination mafs of different matters to replicated and reproduce the copy of the original entangled light for the two lights entanglement across the universe to interact and communicate and transfer their knowledge without acutely the matters of the light ever leaving their original environment.

Using this technology one can even transmute the same from one mafs of the matters' strength to another to speed up or reduce the transportation and trans-crossing time from one field strength and matter mafs to matter strength variation and principal mafs to matter mafs and matters strength. This needing and leading to change of light's mafs to the appropriate measure and sizes and conversion from matter mafs to matter like the mafs of food or oxygen and so forth for human consumption in crossing the universe without relying on and physically carrying food or power supply or even transporting human beings across the universal physical boundaries.

This concept of transmutation which is commonly used in the universal method of transportation will be thought in detail in future disclosure and partly has been disclosed in the book the universal order of creation of Matters (1) papers references 11, 16, 21, 29, 34 and 37.

In the matter environment of the earth, this can be achieved in plasma reactors of simple structure using complex combination pmf of mafs of the light and matters and plasmas in the dynamic nuclear supported reactors.

This concept of light entanglement is one of the easy solutions for transportation in the future without physically moving matter across the universe. This concept has been tested in medical application of the technology and results confirm the correctness of the technology. Where, copy of the correct cell information is translated to cells that the cell makes the copy of the right cell and uses this knowledge to cure or replace damaged cells or by allowing the process to be moved to another part of the body while one part of the brain recovers from damage (the coma case).

The concept of the atomic-entanglement and the binding between two atoms is a natural process of interaction in the universe and if one understands the similarity of this interaction and the light–entanglement then one can see that in the physical world twin stars and the atomic entanglements are of the same in principle interaction and in concept, with difference in their magnitude and the size of the entities involved. Taking note that there are differences in between the twin and binary connection of atoms and stars and their process of entanglements criterion are totally different. Where, the twin atoms and stars are matching in matter contest and, where the binary stars and atoms are matching in magnetic and field contents.

Where, in the binary system the overall Magravs is matching that entities can magnetically polarity interlock. Whereas with twin entities every matter matches in mass and position as well as Magravs and their pole positioning.

The reason that a pair of atoms in receiving additional pmfs of rays of light is elevated to create a mysterious binding between them, is due to one of the fundamental principles of the reversibility in the magnetic polarity of one atom in respect to the other, even though both atoms having the same directional motional rotation. That is to say, *one of the plasmas involved in the entanglement get its magnetic polarities reversed in respect to the other atom*. This meaning, if the first atoms' proton and electron have their North-Pole on the top, in receiving additional mafs of the light, then the second atom receives enough mafs that causes or initiates the change polarity in this second atom, that at this point the North and South poles of each atom interlock with each other and the sudden atomic binding due to the lock of magnetic fields flow between the atoms takes place.

The same principle of atomic entanglement and attraction of reverse pole attraction holds true, when one observes the rotation of twin and binary stars entanglement. Whereas one star reverses its magnetic polarity, automatically the twin star polarity changes too, that the magnetic lock between the two stars to be maintained that the entanglement and twining and binary system can be sustained.

Star, atomic and plasma twining and binary process locking is the safest and common occurrence in the universe as this gives the stars a total magnetic balancing and guaranty's the survival of the both entities. This phenomenon of reverse polarity entanglement holds true and exists for all the twin system in the universe, this being for atoms, stars, galaxies and even universes.

The reason that the light injection or absorption of additional energy by two atoms in some cases leads to creation of entanglement is primarily due to the fact that additional energy received from the ray of the light leads to increase in the magnetosphere dimension of the atoms and this in turn allows two atoms in proximity of each other two magnetically interact and entangle and at the same time in coming close to each other, one atom changes polarity and the two atoms pmf lock and gets gravitated to each other but at the same time each atom is holding on to their Magravs positioning strength gap which is dictated by their internal pmf maf contents. Once the mafs of one star and atom changes due to whatever reason, then one will observe the disconnection of the entanglement or the coupling between the two entities, where at this point the higher Magravs strength partner will pull the weaker Magravs entity to itself.

This is a crucial phenomenon to understand, especially when using light entanglement reactor process in reaching any destination and requiring the change of the plasma of the light from principal mafs to matter mafs strength condition. Thus atom entanglement is a natural phenomenon and at the same time once an atom is created the content of two atoms' plasmas are hardly ever the same, this is to say, to find matching content of pmf of two plasmas of electrons and protons are as rare as finding two completely matching structure of two snow flacks.

The injection of the light into the plasma of two atoms allows some of the atoms, which are near enough in pmf mass to reach the same point of mass or Magravs strength equality at the same time and hence have the capability of coupling. But there are points that additional pmfs of the light can induce enough energy that one atom can come near to another atom pmf balance and being able to interlock too.

The atomic–entanglement is not and cannot be used for transmutation of elements as easily as has been suggested by some scientifically advanced schools of thoughts.

In the present scientific world, scientists have been observing and detecting regular pulses of for example gamma radiation in the upper atmosphere of the earth, which they consider that these radiations all originate from the cosmos and for example they are from the time when a star explodes through the nova principle in the universe. These types of radiations are not the only types of radiations that arrive towards the inner part of the solar system from the cosmos. In reality there is spectrum of radiations and magnetic fluxes of different strength that go through the solar which are originated in the cosmos. In comparison, the radiation that arrives in the inner-most part of the solar system and at the boundaries of the earth atmosphere, these cosmic origin based rays are nothing compared to the gamma rays and other rays which are created within the heliosphere of the solar system itself.

The truth about the main source of these background radiations which has been considered to be from the cosmos and are released, when stars in the universe go through supernova, this concept that these explosions are the main source of these gamma rays and other background radiation which are detected, this shows the lack of the understanding of the process of the conversion of the light into matter and movement and collision of these new matters and mafs in the Oort clouds and Kuiper belt of the solar system. The main source of the gamma radiation bursts detected are originated and created through the motion of the charged particles of the new matters mafs and matters and their collision with each other in the Oort clouds and Kuiper belt region of the solar system and these gamma bursts have nothing to do with supernova and release of gamma bursts that they produce.

That is to say as/and, when newly born charged particles of mafs of the matter and matter as gases, nano matters and ganses move in outer regions of the solar system and ***as they collide with each other***, they release magnetic fields in the gamma, other radiations and noises in magnetic field spectrum levels in these regions of the solar system, which these radiations find their way into the inner parts of the solar system due to the strong magnetic fields interactions pull of their star.

The way these radiations and noises are generated and released is exactly the same way as the lighting and thunder are created and how light and sounds are released through the collision of clouds on earth and in other active atmospheric conditions or in other planets and moons in the solar system and similarly as it happens on the surface of the Sun, when matters mafs of the Sun collided in its upper atmosphere.

Thus the space travellers of the future have to consider all components of the all rays of the magnetic spectrum in the matters' mafs, matters, light, sounds, the principal mafs and matter and its sound and all their light radiation spectrum strength levels too, which these are all free and in motion in the space of this solar system and in the cosmos.

The radiation danger and damages from the light in the principal mafs strength levels are more predominant, stronger and profound than the matter mafs light ray spectrum strength and these radiations and their motion in space will play a crucial role in the future of space travel as these rays will be lethal and fatal if protection from these are not facilitated into cosmos excursion systems and scientific world has to have a viable protection technology for the passengers in the space crafts of the future before they contemplate on such excursions into cosmos and specially traveling in the centre of the galaxies and near principal stars.

Whereas, for example one of these problems will occur, when strong mafs of the principal matters radiations will interfere with matter mafs dilution Margraves positioning reactors used for motion of the craft in space and these principal mafs upon them reaching inside the reactor, they can create Magnetic field surges that can lead to surges in these reactors gravitational and Magnetic fields, which this can lead to the loss of the system and the total inhalation of the system, or the change in the Magravs strength leans the craft in totally different part of cosmos than where the craft was originally destined for.

Therefore, before the men of science contemplate on traveling beyond the boundaries of this solar system, they have to master the knowledge of the mafs of the principal matters spectrum's magnetic field strength and the light transportation mechanism in this spectrum.

If one could understand the structure of the light and how it changes from spherical shape plasma to cylindrical in shape for it to be able to travel with less friction and high speed from one dynamic environment of spherical or cylindrical entity to another spherical environment, then in the future the man of knowledge can develop elongated cylindrical three matters mafs strength spherical and cylindrical composite mafs fuelled combination setting and reactors and crafts, which these elongated crafts will have the benefit of possessing spherical or cylindrical plasmatic magnetic shielding of higher order magnitude pmf strength of the principal mafs and matters for fast and protected space travel in the universe, then at this point one can travel the spans of the universe in times which are not even imaginable at the present by the man of science by use of these types of composite setting and fuelling reactors.

The use of light for purpose of transportation technology and communication through the understanding of the relationship and interaction of mafs of plasma and plasmas of the light(s) in each and every mafs strength of the matters of the light structure is the key to final and ultimate intellectual growth of the human race and point of maturity of the coming of the age of the man as has been promised. This technology will be at the edge of man's enlightenment in the knowledge of creation and control of light and its mafs and matters in the universe.

Chapter 8

Insight into the future use of the structure of the light

From the new understanding of the structure of the light, can easily and readily be concluded that if the light did not and was not made of the structure of three mafs of the matters then the light would have not possessed its own gravitational and Magnetic field forces and for example the light from other stars in the universe would have never been able to reach the earth as an individual magnetic field due to the characteristic and properties of the magnetic fields interactions and gravitations, as through magnetic interactions all these rays' of lights would have been absorbed by other magnetic fields and gravitational fields in the universe and the light would have never reached the far distances of the universe. Hence the light as a physical entity which is similar to other physical entities the like of proton, electron, earth and the Sun and the light being in possession of both Magnetic and gravitational fields, the light ray has to find its position in respect to any other object and pmf in the universe as it passes these entities in the universe, and hence in its travels in cosmos light ray has to find it's Magravs positioning in respect to them that this allows the light ray not to be absorbed but to go around these objects. Hence, the reason for the physical observation of the lensing or the bending of the light near these object as the light passing large and strong gravitational object is purely due to its Magravs and its positioning in respect to these entities in the universe.

Therefore the lensing of the light is the confirmation of its existence as dynamic composite magnetic field strength fields physical and tangible entity in position of Magravs, and the light is not a ray of magnetic field in motion or what has been called that the light to be an energy. Whereas, the plasma of the light ray in motion can transfer it Magravs to other matters and thus has the ability to transfer its momentum to other matters and mafs as energy.

Hence due to the fact that the light possess both Magnetic fields and gravitational fields and in line with laws of physics, when the gravity and the Magnetic fields interact (1 and 2), their interaction lead to the creation of entity in possession of its own mass and its own magnetosphere. Where, the interaction of the lights magnetosphere with the magnetosphere of other objects due to their friction leading to release of residual magnetic fields in the matter magnetic field strength level of the human protein, which this makes the point of interaction of two Magravs detectable pmf field or what is called the visible light to human eye and his tools and methods of detection of pmfs in this ranges of filed strength, out of the full magnetic fields spectrum of the universe.

Where, the motion of the dynamic spherical plasma of magnetic field in its travel from one point in the universe to another causes and leads to elongation of the dynamic spherical pmf, hence the restructuring into a dynamic cylindrical plasma ray of the light, and as this plasma of the ray of light reaches the right pmf environment strength that slows down enough or losses its strength, at this point the cylindrical plasma restructures back to its spherical structure and leads to the creation of pmf of matter mafs and matter in given matter pmf strength environment (Fig. 48) The book cover image. Hence light has the same structure as the pmf of any other plasma known to man like the plasma of electron and proton but in elongated form rather than presently known dynamic spherical shape of tangible matters.



Fig. 48 The conversation of dynamic spherical pmf into dynamic helixial cylindrical ray of light and its conversation back to dynamic spherical (Cover image).

Where, at the same time the plasma of the light in its travels in space can become visible according to the plasmatic magnetic fields of the environment which it travels through and according to the observers' plasmatic magnetic fields strength which in the case of human living Magravs protein molecules structure.

Different proteins have different pmf strength for different creatures in the span of the universe, hence what is visible light to one creature in one point pmf strength in one part of universe this does not mean that to another protein Magravs strength in the same environment this can be visible light too. Hence what is visible light in principal matter or mafs strength, in transition mafs and matter and in matter mafs world in a given matters' magnetic fields environment respectively these light rays are detectible or visible according to the environment and of each mafs and matter in the binding Magravs of the structure of the observer.

The plasma of the light has the capability to present the magnetosphere around itself according to the pmf strength which it is passing through, thus it is the environmental pmf strength which decides the outcome of the mafs of the matter of external layer of the plasma of the light and the final presentation of the light in a given environment.

The plasma of the light to reduces its losses in its pmf of its matters and at the same time allowing it to encounter less resistance for it to be able to travels through the same pmf strength that have less or faces no losses, thus the light ray has the capability of the change of cover mafs and matters of its structure. Thus it is inevitable to consider and conclude that the light like its larger combinations has its own intelligence and its own internal logical magnetic processing that allows it to survive and exist in every dimension in the universe that it might travel through or be part of. This giving the light the capability of being able to travel long distances, and at the same time, this allowing the light not to have fixed maximum speed in all universal magnetic field strength spectrum opposite to what has been assumed by scientific world at the present.

At the same time, the light becomes more visible or detectable as it travels from stronger matter mafs fields strength to a lower matter fields strength environment.

Two rays of lights with different mafs of the principal matter strength can pass through the same medium and they can create different brightness intensity and therefore all lights rays do not have the same intensity primarily and their strength and intensity is internal initial principal mass and strength dependent. Therefore a ray of light can be dimmer or slower compared to another ray primarily due to their mafs of the principal matters content and their strength.

Lights have speed according to their lowest common denominator of it environment pmf strength. Therefore, speed of light in Principal environment due to the stronger field strength of the principal mafs pmf is much faster than the speed of the same plasma in the matter environment, hence the present assumption that the speed of the light as observed by man is the maximum speed of the plasma of the light is ***incorrect***, and hence the plasma of the light has speeds in the Principal matter environment far beyond the present assumptions in the matter environment of the earth and this universes matters' pmfs strength.

Even though the formulas used for conversion of main connection of mass and energy looks as to be balancing and to be correct, in fact this equation is only correct for small and minute amount of plasma and only in the matter environment and not in other plasmatic fields environment of principal mafs and mafs of the transition matter or combination and composite plasmatic magnetic fields strength of principal mafs and matters environments and where only individual rays are considered.

Now that one knows that mass is created through secondary effects and interaction of the effects of the interaction and connection of at least two dynamic plasmatic magnetic fields of the gravity and Magnetic fields (1), which these Gravitational and Magnetic fields both themselves are created and are products of interaction of at least two initial magnetic fields, then in fact mass itself is product of interaction of four fields of two initial fields and two effects of these two fields and hence the formula of relativity now is totally incorrect and has to be rewritten as now one of the factor of the four of the magnetic fields and their combination of their products with each field in position of its own speed of its mafs strength, as energy which is define as magnetic fields in motion, then multiple of speeds of the light in their initial matters mafs strength times the matters mafs of their effect strength in a given mafs strength is the realistic method of the measuring the energy in respect to the mass of the same matter.

Using this knowledge and understanding the structure of the light and applying these in the space technology and in the space reactors crafts of the future for travel in deep space, then by knowing the mass and the strength of the fields which one needs to be traveling to and by the same principle the strength of the original mafs of pmf can be calculated and measured by using the fundamental application and implication in production of light Magravs strength of the system and of the same of the destination point, then one can estimate the power of the crafts Magravs need to be and at the same time what the speed of the travel of the craft shall have, and using the mafs of the light at that given matter environment, one can calculate what mass of the light the system needs to have and be loaded that the system can travel at a given speed in a given environment, or what speed the craft might have once one uses the certain amount of mass of the light in any combination in any of multiple combined fuelled integrated multiple Magravs positioning reactors of the space crafts of the future (1, reference 24,18 and 11).

In understanding the strength of the principal mafs fields strength and using this phenomenon for creation of speed of motion of the systems and crafts, then one can calculate and understand that travels with speeds hundreds and thousands of times and millions of time faster than the speed of the light in matter environment in the near future will become as conventional as jet liner travels of today. The assumption that the speed of light in the matter world is the ultimate speed in the universe cannot be correct. This assumption, when using the principal mafs fields as source of fuel in dynamic plasma dilution gravitational positioning space reactors, which have been developed and tested can be used to achieve higher speed than the speed of light in the matter environment.

Through this technology of the use of light gravitational positioning systems, speeds of travel in Principal and Transition mafs strength environments, which are beyond the present understanding of the man in the matter universe are faster than the speed of light in matter environment.

Now one can understand, that once by not using the principal matters as fuel as has been discussed and promoted by some organisation to burn, as has been the habit of the man to burn to attain motion and height in the past centuries, then in using the mafs of the principal matters in creating gravitational fields and Magnetic fields within a gravitational system, then one can travel the length of the universe in times which are not acceptable to man at the present time due to restrictions which has been forced on the humanity by the less knowledgeable scientists of the time and due to their lack of understanding of the creation and control and structure of the light itself.

Then now one has to make new concepts and measuring tools for local time and universal times as these will be different according to the light mafs strength of the space crafts and environment of measurement and new conventional translation for time has to be employed, otherwise traveling in one speed of the light mafs strength and then entering another to live in, this will create untold problems for the future universal travellers of this universe and for the inter-universes travellers of the future (3, 6 and 7). Invariably in the near future one can use the principal mafs and matters magnetic fields for the purpose of transportation in the universe, where from this point on travel with speeds beyond the matter pmf strength environment for travel in the universe and between universes become a natural means of transportation.

At the same time the speed of light in the principal mafs and matters strength is visible light to the man too, with the difference that in this environment as the protein chain of the man contains and is consisted of plasma of electrons and protons, and these plasmas themselves are made of and operating and consisted of the composition of principal mafs and transition mafs and matters (1) too, then the principle mafs strength of the protein will come into operation and the life will be as normal as one living in the present matter mafs and matter environment of the universe. With a slight difference that he needs to learn about control of the operation of his physical body and his tools of detection in the speed and light configuration.

The parallel world of different pmf strength of matter mafs and mafs of the principal matters are the faster and stronger in pmf strength of life which the Man has come to comprehend and live with and soon he will be able to transmute from one pmf strength of mafs to another and use this knowledge for the advancement of his race and connection and communication in and with the other creature of the universes.

The gravitational field forces of the mafs of the matters of the structure of the light will be the smartest and fastest method for creation and control of space reactors of the future. At the same time speed of the separation of mafs of the matters of the light will be the best directional controller and magnetic shielding protection system for the space crafts of the future as the lights' mafs and matters separation and control in different mafs of the matters and matters of the universe this make the plasma of the light the safest and quickest methods to generate parallel speed of the light in different mafs of the matters environment and at the same time the directional motion of the Magravs transportation system can utilize the mafs of the matters of the light interaction for smooth transition from one matter mafs field strength to another or from matter mafs to matter environment and vice-versa.

This light matter mafs structure division and utilization will be the technology which needs a full understanding of the world of creation and once mastered as has been done by other inhabitants of the universe, then the man will be of the same strength and capability of the understanding of the universe of universes operation, interaction and universal organisation.

When, the intelligence of the man reaches the full understanding of the potentials of the use of the light mafs of the matters, then one will be able to travel in different mafs of the matters environment with use of the mafs of the principal matters magnetic fields strength as the protection magnetosphere created around the crafts in possession of the multiple Magravs positioning reactors.

The dynamic twin reversal of directional motional shielding system made of and through the use of mafs of the principal magnetic fields' strength of the light guaranties the total non-penetrable protection for travel in all mafs and matters environment in the universe, without leaving any traces of direction of motion and without being visible to the human eyes and any other tools and means of detection of any other creatures in the universe.

Where, this technology can be used for fast speed travel in crossing boundaries of universes and for travel across one universe without spending thousands of light years in traveling time as is currently calculated by human scientists. Thus one can travel with full safety using the highest lights Principal Magnetic field strength for every aspects of the motion in the universe.

Once the concept and the principle structure of the principal mafs and matters and other mafs of matters and lights are fully understood then one can use the knowledge of the light structure in full and the scientific world will be able to use the structure and mafs of the light for creating new matters and production of food and nourishment for the life of the passengers and for the space machineries of the future and food producing reactors for the man in deep space where the light is the only available matter for use and at his disposal.

The mafs of the matters of the light can be brought to levels that one needs for the body to absorb for it to survive a pleasurable and comfortable life. Where, different strength mafs of the matters and of the light can be used as vitamins and minerals and proteins for the Man's needs to live. Where, the light mafs of the matters can be used directly without the need for the plant and animal conversion systems of the light mafs of the matters to minerals and nourishment for the human consumption.

One has to understand that there are lives in the lower pmf strength of the universe too; where in reality the matter universe is not the lowest level pmf strength in the universe. The light in this universe is the same and operates in the same way.

In the future one can *use the light mafs of the matters to produce and lower their strength mafs of the matters to pmf for example of the sodium or vitamin A or B*. Therefore from this point on one can even produce composition of matters or what has been the dream of producing energy and new matters through fusion. Now one can use the Principle matter mafs field's strength of the light to fuse the elements in the matter environment. In fact fusion is more practical and achievable if one uses the principal mafs and matter's field's strength of light and their division to create environment of matter mafs for the matters to be created. Fusion of pmf of the light mafs is in so many ways easier than physical matter fusion once the light is transferred into neutron or an atom. The lights' mafs of the matters fusion is a way for the re-production of heavier elements or their pmfs without creating enormous amount of heat that one cannot and has no tools and means to control and contain such matter fusion technology.

Once the man learns the use of the construction of mafs of the matters of the light, then one will learn that source of mafs of the matters are available in all corners of universe and on the other hand one does not need to create the physical matter to have the properties of the physical matter, but one can use pmf strength properties of the given matter in its fusion of the light mafs of the matters to achieve the same effect, the likes of the production of energy and food without ever using fusion of physical matter to achieve the same goal and actually without ever needing physically to eat and to digest food. Then in the near future man's body will do with the digestion system and in the further times man will learn and will do with the physical body for it to exist and for it to travel the spans of the universe(s).

Using the mafs of the matters of the structure of the light rays for **communication purposes**, in the matter environment, then the communication system can be set to transfer the information in the Principal matter mafs strength and once the information arrives at the point of destination the receiving system can decode the information from the principal mafs strength to matter mafs strength and then the information can become available for whatever purpose it was transmitted for, this being audible, visual or computable information or transfer of matters. This method of use of mafs of the matters of the light field's strength will eliminate any time delay in communication across the spans of the universe, the delay time which has been observed in the present cosmos communication systems will not exist once using principal mafs strength and then communication become instantaneous anywhere in the universe.

Thus by switching from one matter mafs strength to another matter mafs strength of the same light, this will bring into play a totally new technology and facilitates new approaches in the production of tangible matters too. That is to say one can strip the light from one of its mafs of the matters for one purpose and use its residual mafs of the matters for other purposes. That is to say, by striping the light off its principal mafs for the communication purposes, then one can use the mafs of its transition matters and mafs of the matters of the same plasma of the light for production of increase in other matters and matters growth or expansion in their given environment or use these for production of energy for human existence in space.

The universal language using mafs of the matters of light and using the same mafs of the matters of the light for their transportation will be the cornerstone of the future transmutation of matter and matters and communication in the universe among other intelligent creatures of the universe(s).

The positrons are created at the point of the creation of the plasma of the atoms from the ray of the light and the clockwise motion of these particles is totally and primarily internal magnetic fields position dependent. This meaning that the directional rotational motion of all matters are dependent on the speed of the rotation and position of the mafs of the principal matters and matters in respect to each other, this plasma be it of the plasma of electron, proton, atoms even stars and galaxies.

The clockwise or anticlockwise rotation of electrons, protons, planets and stars is determined by the principal mafs matters speed of rotation and its distance in respect to the matter mafs and distance between different layers mafs components of the plasma of the entity after the light ray is converted to matter of the electron or the proton and star and its matter content.

In conclusion one has to be aware that visible light magnetic fields spectrum, which makes man to see its universe is the same in all pmf strength levels. This means that in every pmf strength environments there are visibility criterions to all created life, but the visibility is pmfs field strength dependent. Therefore, what is not visible to one being is visible environment to another using different pmf strength for point reference as tool for vision and this applies to all pmf strength mafs of the matters and matter universes and environment.

At the same time vision is not through the vision tools like the eyes, but vision is the openness to receive knowledge through the real means of the operation of the universe in the pmf strength of the level of intelligence of the structure of the beings.

The reality of the existence has been measured by the strength of the light, which a matter can emit, and the duration and the depth the Magravs of the created light can penetrate in its environment. Then the question for the Man to ask of his existence, is that how does the matter like him, who is the user and the producer of the same physical entities as stars, how does his existence will shine and operate in the span of the universe after the demise of his physical life on this matter strength environment?

May be it is the time for the Man to come to understand the true meaning of the light, as all beings in the universe announce their existence through the emission of the light into and onto their surroundings.

This technology of the light ray's protection gives the man the ultimate knowledge for survival and brings the man knowledge and intelligence in par with and equal to the knowledge known to the rest of the universal manifestations and the same we have served our purpose in bringing the same to all men of progress.

Thus would be correct for the Man to consider his connection beyond his physical existence and through the light of his presence during its time, and hence would the soul of the man be of the light of the confirmation of his existence.

Be wise to the truth of the creation of the man, if the light of wisdom is the light of the soul from the time of beginning to the end of time. This light will exist and will be the source of the confirmation of everlasting existence of his soul, as the light of far distance star after billions of years are shining in the deepest part of the universe, this has been and shall be destined for the soul of the Man throughout all times of the existence of the universe.

Thus it can be said

The man has come from,
He exists, operates through and
He shall return to
the Light

Definitions

Below is a list of the new terms and their definition that used in this book. A number of these words and terms have been used in the previous book and scientific papers, which have been published by the foundation and most readers, are familiar with these terms and reference. In this book a different approach and language and terminologies is used, therefore has become necessary to create a new terminology and words that can explain the real term application and processes in the world of physics.

Mafs: magnetic fields

Magnetic: with **capital M** refers to the plasma of magnetic fields created by a dynamic entity as for example this refers to the magnetic field of the earth.

Magravs: Magnetic and gravitational fields (Magnetic referring to the plasma of magnetic fields created by a dynamic entity as for example this refers to the magnetic field of the earth)

Pmf: plasmatic magnetic fields

Principal matter: This matter in conventional physics is called the ***anti-matter***, as now the real structure of this matter is fully understood and is said to be source of all matters from the dark matter to matter, thus it has been called the original matter or the principal.

Principal mafs: These are magnetic fields, which are in the principal strength levels and considered to be I order magnitude several hundreds of times stronger than the magnetic fields which make up the tangible and visible matters.

Principal star: This entity in the conventional physics is called the Black hole

Transition energy: This energy in conventional physics is called the dark energy. This is the pmfs that are in motion from principal to matter magnetic fields strength so called the transition energy as energy is defined as the pmfs in motion.

Transition matter: This matter in conventional physics is called the Dark matter, as now the real structure of this matter is fully understood and is said to be when plasmatic magnetic fields are in transition state from the principal matter to tangible matter thus the term transition matter is used.

Transition mafs: These are magnetic fields which are in strength level between the principal and matter magnetic fields strength, and are in transit from the principal mafs to matter mafs strength levels.

Gans: a new state of matter; a molecule of a gas (GAs) which becomes Nano of itself and appears as Solid state of matter. **GA**s to **N**ano of **S**olid and to be called **GANS** for short.

Reference

1. The book, “The universal order of creation of the Matters”, M T Keshe, published July 2009 ISBN 978 46 6087 001 9

2. The unifying theory of the fields M T Keshe 2009

3. The origin of the Universe M T Keshe 2010

4. The creation of the solar systems M T Keshe 2010

5. The CO2 capture paper by MT Keshe Published 23.12.2009

6. “The universal order of existence” finalized and to be published in 2010-2011 by M T Keshe

7. The Magravs positioning M T Keshe 2010

8. NASA WMAP common.wikimedia.com

Published and unpublished works by M. T. Keshe

There are a number of unfinished articles that are to be converted to full disclosures when completed, like antimatter mafs method of energy releases, Nano space technology, relation between the creator and the created, space communication system, deep space defence technology, dynamic magnetic fields force regions (wormholes) construction and control, creation of magnetic fields, and so on.

Some of these works have already been published through different channels and some have not yet been released.

In the following section some of the works done by the same author are mentioned, with a brief disclosure of their contents.

Some of these papers can be purchased and obtained through direct request and access through specific links.

A number of papers with * and ** marks **are not for public release** due to their sensitivity of information and only available to relevant commercial and governmental organisations for peaceful applications of the technology.

The universal order of creation
(5.7.2006)

In this disclosure the main construction principles and the method of the link and control in the universal order of the existence of living cells, like the function and operational method of any matter based on so called proteins chains, as for example in human cell are explained in detail.

REF 9

The author considers this paper as one of his most important and fundamental works to be published and to be added to the sets of disclosures written by him.

Cosmic Rays
(Release date 24.3.2004)
This paper explains the source and the origin of cosmic rays and the way these work within our cosmos, their function and their benefits.

REF 10

----

*The Airborne reactor

(Release date 25.3.2004)

This paper covers the total design of airborne reactors for space technology. This covers all aspects of operation, design and control of such reactors.

REF 11

The seed of the Earth
(Release date 25.3.2004)

Some extracts from this paper:
The theory that the heat of the core of the Earth is due to inertia of the material piled on top of each other is completely dismissed through this new disclosure.

The author M T Keshe believes that this centre core is made of hydrogen, other gases and a mixture of liquid and solid matters mafs, which were in the vicinity of the centre of the core of the Earth at the time of its inception in the solar system.

Through this new understanding of the new inner cores of the planet, this brings to play the fact that the old inner core of the Earth that is already assumed to be made of a solid piece itself becomes a sealed container for the new inner core.

The author through design of a parallel system has set to confirm the validity of this assumption, that the centre of the Earth possesses a semi- fusion atomic reactor and not a fission reactor as has been assumed by other scientists.

This theory of hydrogen in the centre of the planet is in line with the physical reality of the creation and the present situation in the physical construction of the solar system.

By the laws of physics all the gases in the solar system should have been in the giant gas planets at the outer layers of the solar system, like in Jupiter and Saturn.

The physical reality in the solar system, is that the lightest of all these gasses, the Hydrogen, has taken its place right in the centre of the solar system in its star, the Sun.

It has to be recognised that the centre of all planets in possession of gravity due to the centre cores heating, are always in possession of two Magnetic Field Forces in their inner sanctum (M. T. Keshe “The creation of gravity").

In the case of the Earth up to now and with the present knowledge there has been acceptance of only one inner core and one magnetic force.

As it is explained in the paper titled "the creation of gravity", there is an inner core in the inner core. This inner core, due to it physical content, motion and position in the centre of the Earth, creates and maintains its own magnetic field force, independent of the magnetic force which has been known to be created by the interaction of the inner core and the outer core of the planet.

These two magnetic fields interact to create the planet's own double magnetic fields in its centre. The interaction of these two magnetic fields forces upon each other leads to the new concept of the "DOUBLE MAGNETIC FIELD EFFECT", where the interaction between these two field forces in the centre of the planet leads to the creation of the gravity and the magnetic forces of the planet

(Paper: The creation of gravity).

This new second core is the seed core of the planet, the mother seed of the planet positioned in this new inner core.

REF 12

The creation of Black Hole

(Release date 25.3.2004)

In this paper it is explained that the Black Hole is created out of a natural sequence of events, and that the existence of the Black Hole in a galaxy is a normal event. Further it is explained that a Black hole is created in similar ways to the Dark Spots on the surface of the Sun. In this paper for the first time, it is explained how the Black Hole is physically created and what function it plays in its galaxy.

REF 13

Magnetosphere

(Release date 9.6.2004)

"The shape and the strength of the magnetosphere of a planet is exactly what a fingerprint is to a man. It is unique to each planet, star and galaxy. It is a tell-tale of all its attributes, and it reveals the hidden mysteries of the internal materials' structure".

REF 14

Correction to the Einstein equation of Relativity

(Release date 15.6.2004)

In this paper the physical reality of the Einstein equation is considered, and efforts are made to bring this equation to the real conditions. Even Einstein considers this equation applicable for very small mass, and not in real three-dimensional multi-Magnetic and gravitational conditions, which are external and have nothing to do with the theoretical object's mass and speed, but have effect on the speed and the mass of the object under consideration.

REF 15

----

*Introduction to the new system
(Release date 2.7.2004)

In this paper it is written "It is essential to understand that, with the application of this system of motion, one cannot bring into play the solid, liquid and gas fuel method to create motion, as is used today. What is offered in this system is in simple words a fully integrated plasmatic magnetic energy system. Which, creates within and around the core environmental conditions as known to man in the universe like creation of gravity and magnetic field protection and the same as the magnetospheric protection condition of planets and motion through interaction of magnetic fields as planets and stars do in their given environment".

REF 16

The rings of Saturn
(Release date 2.7.2004)

One of the oldest puzzles in the world of astronomy has been the existence of the rings around Saturn. How did these rings come to exist the way they are now? How did they come to appear and behave the way they do? These questions and much more about the creation of these rings are all answered in this paper.

REF 17

The creation of gravity
(Release date 11.7.2004)

In this paper it is explained that "the source and the creator of the magnetic forces and the gravitational forces are due to the interaction between the same materials in the same region of the planet."

Further it is explained how the gravitational field force can be created, replicated and controlled within a nuclear reactor. Further it is explained how this property can be used for the motion of a system within a planetary or solar system.

Now by understanding the principle of the creation of gravity, in this paper it is further explained that "the gravity in reality is the effect of the interaction of two plasmatic magnetic energy fields of any two object in respect to each other."

REF 18

Death of a star
(Release date 26.7.2004)

In this paper the death of stars is explained, "The death of a star and the creation of a supernova is in reality the same as the half-life cycle energy step-down of an atom, with the difference that this show is in a larger scale, and more spectacular, in all aspects of its dimensions".

REF 19

Fusion

(Release date 28.7.2004)

In this paper the physical and scientific problems with present fusion technology is considered. Where, it is written, "nuclear Scientists, with the fusion reactors of today, are trying to create fusion in the opposite way to the known laws of physics and their parallels in the universe”. Further in this paper it is written, "If the present path for creation of fusion is followed, with the present scientific knowledge of physical materials for construction of such system, then following the present path of development to create energy from current fusion systems will be a distant dream".

REF 20

Life of a Cell

(Release date 28.11.2004)

Extracts from this paper; "The reality of the transportation and transmutation of a cell is not far from the reality of the life of an atom or a star. Where the life cycle of the cells are slightly more complicated, as they contain other matters mafs like acids, which have their own magnetic characteristic of their own chemical structure. For this reason the control and replication of the energy of the cell is very much complex, but very simple to achieve".

REF 21

The Atom

(Release date 19.12.2004)

The content of this paper explains how and where atoms in the universe are originated from and how the construction of atoms in a cold plasmatic nuclear reactor can be replicated.

REF 22

Magnetism

(Release date 8.1.2005)

In this paper it is written, "The question is where did the Magnetism come from? This is the Secret of creation. The world is made of one thing and only one thing and that is Magnetism. Its combination and interaction with its own different strength fields makes it appear as different matter mafs. The rest of creations are the outcome of these interactions of different strength of this thing called magnetism and the forces it creates. Magnetism is the origin of existence and the real singularity in its full meaning".

REF 23

----

*The creation of the magneto-gravitational force
(Release date 5.2.2005)

The creation of magneto-gravitational field force is and will be fundamentally independent of temperature and pressure, proviso to the fact that as long as a homogenous free floating PMF within a matter mafs is created.

REF 24

The core of the Earth
(Release date 20.4.2005)

One of the original assumptions in developing the new Magravs system some thirty years ago by M.T. Keshe was on the basis that the centre of the Earth possesses addition cores, which create the necessary gravitational conditions of the planet. After some twenty years of space technology and through Earthquake seismological data's this assumption has been shown to be correct and after over twenty years, it has been scientifically proven that the inner core of the Earth has an inner core of 600 km. Professor Guy Master in 2002 ref 24 nuclear planet. The centre of this core is assumed to have an inner core of 8 Km, this he thought to be made of the plutonium or other nuclear materials

But the developer of this new plasma reactor technology has proven through physical dynamic cores that these cores possess a mixture of hydrogen plasmas and the process of the heating of the centre of the Earth are due to a semi-fusion chain of events.

REF 25
----

*The electron-atomic welding
(Release date 3.5.2005)

Some extracts from this paper:
"The electron atomic welding or atomic welding principle is the phenomenon that atoms of the same material, through a common shared electron, become a magnetically balanced molecule of the same matter mafs, with the difference that the shared electron will create a balanced PMF in the molecule".

REF 26
----

*Shutdown and safety of the reactor core
(Release date 6.6.2005)

In this paper the safety parameters in the operation of the gravitational and energy reactors are simply explained to avoid the loss of plasma and gravitational field forces created within its cores.

REF 27
----

*Reactor Start-up

(Release date 9.6.2005)

In this paper the systematic start-up of the dynamic reactors for the creation of gravitational field forces and the production of energy are set out. The start-up of these systems is totally different than the prior arts known in the nuclear industry.

REF 28

----

*The energy balance of the reactor

(Release date 29.6.2005)

Some extracts from this paper:

The energy balance of these types of reactors is not as simple as might look in the first instance. The energy creation is simple. But the heat leakage and dissipation through the deliberate inherent material design are and can be zero. That is to say the system not only can hold on the heat it creates. At the same time due to the close circuit feed operation will become self-sufficient but long lasting.

In planets, the loss of heat through their surface creates the variation in the central core condition over several billions of years. In this reactor as losses can be literally negligible, the system can operate at low energy loss temperatures. Even the boundary of the body could be made through the right combination of material in the chambers, so that the body of the reactor will be colder than its surrounding boundary. So the system will not only lose energy to its surrounding, but it can be made to absorb heat in the negative temperature gradient from its surrounding, so that there are no losses.

REF 29

Nuclear decay or half-life

(Release date 20.7.2005)

Extracts from the paper:

"The nuclear decay always has the same or near the same time duration. This is due to the fact that the all neutrons and protons, from their inception, carry a predetermined level of plasmatic magnetic energy. This energy is continually used for the motion and vibration of different elements of the nucleus in respect to each other and the surrounding matters mafs of the atom. As the space and dimensions of a nucleus of an atom always obeys the same principles of the magnetic separation and magnetic attraction. Protons or neutrons can and will need to use or consume the same energy before they become weak enough that the splitting or decay becomes a clockwork job. The nuclear decay is the natural levelling done of a nucleus' energy, due to the energy consumption and heat dissipation for the motion of the elements of the nucleus for its remaining plasmatic magnetic fields energy necessarily needed for them to hold one together".

REF 30

----

*The decontamination system
(Release date 10.10.2005)

"What this means is that, for example in trying to recycle the CO2, by the use of the right matter mafs in one of the cores of the reactor, the system will then use the O2 to produce H2O, in the form of pure water, and C in the form of atomic or molecular carbon, or even by feeding this back through certain operational compressions and gravitational interactions within a small core, to create industrial diamond or graphite, for different industries."

The use of the reactor for this purpose has been proven to be correct and Raman spectroscopy has proven the concept and physical reality of the separation of matter mafs in atomic level after separation in the same system from a composite matter mafs.
(See the graphene on the technology web site)

REF 31

The difference in atomic and molecular structure
under gravitational force and pressurised conditions.
(Release date 15.8.2005)

In this paper is written that "the atomic and molecular structure of matter mafs is totally aligned and positioned in a fundamentally different configuration where it has come together due to gravitational forces, than when matter mafs has been brought together by the means of pressure. This has a fundamental effect on the behaviour of the structure and properties of the matter mafs which is created in either way". Where this is explained and utilised to develop a new method in creating graphene and Sp3 atoms and walls in a simple core made of a coca- cola bottle.

REF 32

**The Defence and shielding system
(Release date 4.9.2005)

Some extract from this paper:
The design of the side open system for lunch of high saturation magnetic plasma package is one of the most effective technologies for defence of the reactor and the craft, which is in possession of such a system.

It is essential for any space technology in the open environment of the universe, if the craft is to keep a straight line of motion and to be able to protect itself from any solids or matters mafs in its path in the cosmos.

This technology can destroy any object by the principle of plasmatic magnetic energy saturation of the incoming object at a molecular level, that object will disintegrate in the form of magnetic vapour and not atomic level destruction, before matter mafs can damage the craft as debris, and before the craft ever becomes in touch or near these space matters mafs.

This technology can also be used to protect Earth from the collision risk of NEO's (Near Earth Objects), like comets and asteroids.

REF 33

Method of creation of an atom or nano matter mafs

(Release date 11.10.2005)

The manufacture of an atom of any density, this being of the simplest form of nucleus or a full atom of hydrogen, or even heavier elements in the universe, all follow the same principle.

Atoms are created in the soup of the cosmos from collections of very weak plasmatic magnetic fields, which for their existence cluster and share their energies with the magnetic fields that are not far from their own plasmatic magnetic field strength.

REF 34

The relationship between Gravity and Mass

(Release date 21.1.2006)

Extracts from text of this paper:
"A planet like Earth possesses a combination of both gravity and inertia. Where the gravity comes from the interaction of plasmatic magnetic energy fields from the processes within its core, and the inertia comes purely from the collection molecules PMF of matters mafs which has built the physical body of the planet.

Any object, being an electron, atom, molecule or even a human body, is a collection of plasmatic magnetic energy fields of different strengths and their interactions between each other, which in total decides the total or collective magnetic field possessed by that object where this is the mass of the object.

Where the mass of an object is a collective package of plasmatic magnetic energy field tightness of a given object and will not change as long as the object is intact as one entity in its overall atomic or molecular or collective molecular appearance.

Which plasmatic magnetic energy of a physical body (so called the mass of the body) in interaction with molecular or atomic magnetic field (this being gravitational or inertia) of another object will determine the weight of the two object in respect to each other in each other’s environment".

REF 35

The Dark matter mafs
The Fifth state of matter mafs

(Release date 21.1.2006)

Extracts from text of this paper:

The existence of dark matter mafs is not questionable, Proving its existence, and its effect on the energy balance of the universe, in all matters mafs as small as in the heart of an electron or in a solar system needs to be created, replicated and its effect measured.

The theory of dark matter mafs does not and needs not to be considered as complicated, if one understands in real terms the plasmatic magnetic energy of the matter mafs in the visible and invisible dimensions of the universal work.

The dark matter mafs has two distinctive characteristics, which makes it totally apart from the visible matter mafs. The dark matter mafs possess mass but not visible light, where its existence can only be determined by the weight of the it's hidden mass, which could be substantial due to its internal gravitational field.

REF 36
----

*The inter-atomic fusion
(Release date 3. 5. 2006)

Extract from this paper:
"The fusion of two or more atoms has been the pre-occupation of nuclear physicists for past years. Conditions to achieve fusion of two hydrogen plasmas in the TOKAMAK reactors have taken years to teach scientists a lot about the behaviour of plasma and their fusing.

The reality about the fusion in some way has to be reconsidered as, if the scientific world is trying to amalgamate the contents of two plasmas to release energy. There must be a simpler way to achieve releases of similar energies.

The fundamental principle of the inter-atomic fusion is a much simpler way to achieve fusion. If this principle is applied to the atomic condition of fusion, then fusion will be attained in a simple but in a much more physically realistic environment.

The explanation for inter- atomic fusion is very simple and direct.
In the fusion of two plasma of proton of hydrogen atom, the physicists try to fuse two large plasmas, and by doing so, they try to release a large amount of energy. Where in this process enormous amount of magnetic field forces and currents are needed to bring two plasmas in close proximity, so that the energy barriers in between them can be overcome for them to amalgamate or fuse.

In the inter-atomic fusion the overcoming of energy barriers does not exist, as in this method of fusion, the electron of the atom which is circulating the nucleus of the atom and is of the same origin will be encouraged to return into and fuse with the nucleus of its atom".

Where this is a more practical way to create and release manageable energies and there is no need for elaborate systems where even if the energy release will be small compared to dreamed up fusion systems of today.

With inter-atomic fusion method at least small and practical systems can be developed to handle low temperatures of the fusion process.

REF 37

The conductivity of the matter mafs in the vacuum of the interplanetary mediums
(Release date 21.1.2006)

Some extracts form this short paper "Therefore plasmatic magnetic energy field of elements within the interplanetary medium will cover the space given to them in their environment. Where due to their motion and their electric charges even in eV levels, they become perfect conductor, and in turn, due to their motion on their environment, they become plasmatic electromagnetic generators.

REF 38

The production of Graphene
(Release date 25.7.2006)

Repeated experiments and tests in simple static reactors, and tests in more complex dynamic reactors, prove that atomic separation and recombination of matter mafs like carbon and hydrogen can be reached at room temperature and at atmospheric conditions.

We have now indications - through static and dynamic tests in our reactors - that the universe was made in normal condition, which was originally nothing but packages of plasmatic magnetic fields of different strength, which were themselves nothing but areas of plasma or collections of loose magnetic fields energies. Where magnetic fields of different strength in locking to each other, by the principle of their plasmatic magnetic energy (PME), have caused in the first stage the creation of fundamental particles, secondly atoms, then molecules and then matter mafs, clouds and asteroids and then stars and galaxy's".

The big bang theory conditions have no room in the reality of the creation of the universe.

REF 39

Further works on medical research and developments have been written and completed, and will be published on the Foundation medical site in due course.

The process of the reversal of coma: Published in December 2010

Multiple Sclerosis: Published in December 2010

Epilepsy: Published in December 2010

Fibromyalgia: Published in December 2010

INTERNET LINKS

Web site: www.keshefoundation.com

YouTube Channel: http://www.youtube.com/user/keshefoundation

Forum: http://www.keshefoundation.com/forum/

Appendix 1

The unifying field Theory

© M T Keshe 2000-2009, all rights reserved

Date of release of paper 28.10.2009

Abstract

In this paper the origin of electromagnetic fields or electromagnetism and how they are created within the existence of the other magnetic fields are simply explained.

Discussions

The creation of magnetic field and its interaction with physical matter or other fields always leads to release of electromagnetic fields or energy equal to the energy of an electron.

In the universe, energy equal to energy of an electron, where there are no matters for magnetic fields to interact with, for electromagnetism to be created or to be released, in these environments electromagnetic fields do still exists and function.

Electromagnetic fields or electron energy does not need to be created by interaction of magnetic fields and matters as like in generators of present time, as in the universe electromagnetism is constantly produced due to the difference of the magnetic field strength between two fields and without presence of any matter or physical interaction of fields or fields and matters.

Due to the development of gravitational systems and having the ability to create different strength plasmatic magnetic fields within gravitational reactors cores, with the capability of being able to create and maintain different magnetic field strength in different part of reactors, where these fields are continuous and can be kept at a given constant strength level, that their difference in strength in fields can be equal to the magnetic field strength of an electron, where electromagnetic current flow can be maintained from one magnetic field to another due to their field strengths difference, this has enabled us to create and maintain energy field or elect magnetic fields strength of an electron in a plasma reactor without an electron being present or in motion within these reactors.

Where production of electromagnetic fields can be achieved by the simple creation of two magnetic fields with different magnetic field strength of an electron, that as fields are down levelled, from one magnetic fields strength to another, one can creates a flow of magnetic field equal to magnetic field strength of the an electron, thus the creation of electromagnetic current, or production of flow of electromagnetism can be achieved.

Where electromagnetism or current of magnetic fields of an electron can be created at any level of magnetic fields strength, as long as a strength level difference between two fields in magnetic fields exist, and where, in plasmatic magnetic fields the strength level difference of the fields causes the flow of magnetic fields from one field strength to another can be caused or what is called commonly electromagnetic field flow can be maintained.

Therefore, one can have electromagnetic fields of any strength, this being Matter, Antimatter or

Dark Matter, as long as their magnetic field strength difference between to field strength is equal to the magnetic field strength of an electron or magnetic fields of Matters of an electron. Or the magnetic field strength that can affect the motion of other fields to be equal to the magnetic fields strength of an electron. Then at this stage one achieves the electromagnetic current thought flow of magnetic fields, from one stronger to the weaker field, which the magnetic field strength of the flow is equal to magnetic field of an electron (see Fig. 1).

Electromagnetism

In the real world of existence, all Matters do not have boundaries as tangible matters do, but their boundaries are dictated and created through the space they cover through and by their dynamic magnetic field effects. Where, this space of effect of their magnetic field is called the environment of plasma of these fields.

Thus when we speak of plasma or plasma of an electron, proton or neutron, what we talk about here, is the space and environment where the effect of these magnetic fields of the total structure and the entity of for example an electron can cover.

Thus an electron is in fact nothing but a space in an environment, which the total effects of all magnetic fields of all Matters and fields, can be detected or be contained in.

Thus to this end, when an entity possesses magnetic field strength equal to total magnetic fields strength of an environment within the plasma of an electron, then this entity is in possession of mixture of dynamic magnetic fields of an electron or this entity has magnetic field strength measure of an electron or what is called possesses electromagnetic field.

Where this space being in possession of magnetic fields, by its nature has to interact with other magnetic fields and entities made of magnetic fields in it's surrounding, where these interaction can be attraction (gravitation) or repulsion (Magnetic).

Hence and direction of motion of this space of fields (Fig. 1) or electromagnetic fields is totally dependent on other magnetic fields within its environment, which their environments total strength in gravitation and repulsion dictates the direction of the motion of the plasma of an electrons magnetic fields.



plasma of an electron Flow of pmtics

Fig. 1 Magnetic fields concept of an electron and a flow of plasmatic magnetic fields equal in strength to that of an electron.

As I have explained in the book, The Universal Order of Creation of Matters (2009, ISBN 978-94-6087-001-9) the magnetic field strength decay of the plasma of a neutron (Fig. 2) leads to creation of two plasmas of the same structure of a proton and an electron.


MATTER
G1
ANTIMATTER
G2
F1
Transition region
DARK
MATTER
G3
NEUTRON
RELEASE OF PMTICS
ELECTRON
MATTER
G1
ANTIMATTER
G2
F1
Transition region
DARK
MATTER
G3
PROTON

Fig. 2 Decay of plasma of Neutron into two plasmas of proton and an electron.

It is an important to understand that the structure of an electron in fact is plasma and it is like the plasma of proton but in a smaller scale in the mass compared to the proton (Fig. 3).


MATTER
ANTIMATTER
F1
DARK MATTER
PROTON
MATTER
ANTI-
MATTER
F1
DARK MATTER
electron
fragments
(light,...)

Fig. 3 This showing that proton and electron both possess the same electromagnetic field strength of different Matters, with each entity having different mass of each matter.

Thus the electron is and has the structure of a proton and similarly possesses all its three states of Matters (Matter, Anti-Matter and Dark Matter), and its content is proportion to its neutron plasma prior to its decay into two plasmas of the proton and an electron. As electron is made of electromagnetic field strength of varying strength, this being the reason, why its current and its flow can be influenced by other magnetic fields, as magnetic fields of different strength do influence each other’s path of motion and speed of motion in different Matters and matters environment.

Where, at the same time and by the same principle the dynamics (orbits) of the electron around its proton is due to the continuous repositioning (alternating attraction and repulsion) of the smaller Matters parts of the electron in respect to the large Matters magnetic fields of the proton. This is the reason why that the trajectory of the electron is said to be uncertain.

Where, by the same principle, the Magnetic field source of all Matters and matters and their different magnetic fields strength, is the cause and the sources of all effects and matters we observe in the universe.

In the book I have explained how the gravity is created through interaction of two or more magnetic fields, and how mass is the measure of difference between gravitational fields and Magnetic* fields created by the interaction of the same two or more magnetic fields. Thus even mass is magnetic field strength dependent too.

Further the relation between mass and energy, which both are magnetic field strength dependent (1), and as has been explained, energy is the measure of the mass and the rate of it's the speed of transfer in its own Matters medium (this being Matter, Antimatter or Dark Matter medium) from one magnetic fields strength to another depending upon attraction or gravitational strength from one magnetic field to another. Where, this speed is magnetic fields order of magnitudes strength dependent.

Where, transmutation from one magnetic field strength of Matter to another, like from Matter to Antimatters can lead to creation of current or electromagnetism within the given environment of the same plasma itself too.

In fact in the universe one has proton magnetic field current flows or **protomagnetism** (proton-magnetism) too. This current is the flow of magnetic fields to another, which are equal to magnetic fields strength of one proton. These magnetic fields are bases of the cosmic magnetic field storms and have more profound effects on the structural integrity of the galaxies than their weaker counter parts electromagnetic fields.

Further more as now we understand the concept of plasma of an electron and even by the same principle one can understand the principle structure of the plasma of the proton and by the same measure of the plasma of the neutron, hence in the universe we have observed plasmas of neutrons in motion, which these have the same ability as electromagnetism and protomagnetism in motion and these are called the **neutromagnetism (neutron-magnetism).** Where, these are the space in universe, which carry magnetic field strength equal to the strength of magnetic fields of all Matters, and fields, which make the structure of an entity a neutron.

In fact what is called a neutron star, these in reality do not possess neutrons, but these stars emitted magnetic fields strength in the range of Magravs of neutron. Hence tangibility of the neutron becomes later on as they disassociate themselves from the other fields in their environment, and at this point, they create dynamic space or environment or what we call the plasma of the neutron, where these magnetic fields can exercise their influences on other fields within their surrounding.

Further to this explanation, one can simply understand that in the matter world or in the magnetic field strength of matter, the gravitation and repulsion between these magnetic fields are in the level of matter magnetic field strength of electron, proton or neutron.

Hence in the matter world like in solid magnets, magnetic or magnetism or attraction or gravitation, is the attraction between the magnetic fields strength of Matter components of the plasma of electron, proton or neutron of that matter.

Thus is the reason, why in the physical world certain matters are attracted to each other, which they make certain types of molecules or physical matters. Where, the attraction of atoms to make up any matter it is entirely Magravs strength dependent and no other factor.

Where these attractions or gravitation of atoms or molecules in respect to each other, on other hand is environmental magnetic field dependent too. This is the reason why we can observe certain matters in one environment and not in the others. This being due to the fact that environments themselves are made or created or are conditioned due to interaction and Magravs (Magnetic and gravitational fields) of other magnetic fields.

Permanent magnets

Sometimes in the future I will release a book which initial basic work for it already has been set. The book will be titled "The universal origin of magnetic fields". In this book I will explain how magnetic fields are generated and how plasmatic and specific Matters magnetic fields exist in different dimensions.

In simple terms, the Matter magnetic field or what we call permanent solid magnets are mono magnetic fields strength which are at the levels of the Matter components of the plasma of an electron, which are in sequence with the plasmatic magnetic field Matters' of the proton of their element.

What this means is that when plasmatic magnetic field of the Matter components of an atoms' proton and electron field strength become interconnected and in field balance, then a continuous field between the Matter fields of the proton and electron is set to operate, where in the case of for example Iron at earth magnetic and gravitational field strength, this connection is set to be holding and hence creating a permanent magnet.

Hence as one establishes inter-connection between electron and proton internal field strength, then due to the more of supply from the proton, then the matter stays in one field strength for indefinite time.

This being the reason for example why magnetic fields in level of the water molecules, do not have strength to attract for example cooper atoms gravitational level, but can attract other water molecules'.

In fact iron will not be magnetic as it is on earth in most of positions in the universe. This being due to the fact that even permanent magnetic properties or characteristic of all matters are their environmental Magravs dependent. Hence what is permanent magnetic in solar system, its no similarly the same in other solar systems or galaxies.

Secondly magnetic fields or plasmatic magnetic fields are independent of Matter, but dependent of Magnetic field of Magravs of the Matter, Antimatter and Dark Matter of plasma of electron and proton too.

But at the same time it is important to understand that to have long term or permanent magnets, the Antimatter components of the plasmas have to and are positioned that they establish a continues field between the other antimatter component of the atoms of the same matters too.

The difference between conductors and superconductors

The present world of physics has a dilemma with the fundamental principles of conductors and

superconductors. Where this should not be so, if, scientists could understand the real term difference between the current flow of electron and current flow of magnetic field flux equal to the magnetic field strength of an electron.
What this means is that in conductors, the motion of or vibration equal to vibration of an electron causes the flow of current in the matter.

Where as in superconductor it is not the flow of the electron or the vibration of an electron that causes the flow of the current, but current flow is caused by the flow of electromagnetic field strength equal to magnetic fields strength of an electron, which flows through the material.

Where in the case of superconductors' there is no need for vibration or motion of matter, as with superconductors the same magnetic field strength equal to the magnetic field of the an electron flows through the superconductor materials.

Where in the case of superconductors the lattice boundary of molecules or atoms are so closely and perfectly packed that the electromagnetic flows through the lattice structure without a need for vibration of the electrons of the atoms or molecules of that structure.

In fact one can say that the same electromagnetic field, which starts from one end of the superconductor, itself will be traveling out of the other end of the superconductor, irrespective of the length of the material of the superconductor.

In the case of conductors vibration of electron needs kinetic energy and hence loses, where in the case of superconductors the structure of the material is so that no electron moves, but the material has the ability to transfer the electromagnetic fields strength equal to an electron magnetic fields strength, hence literally no kinetic move, no resistance and no loses.

The superconductivity of the matter is lattice position structure dependent and this is usually better observed in sp3 or diamond-structured materials.

Thus in conductors, electrons have to move and in superconductors magnetic field strength equal to magnetic field strength of an electron needs to be transmitted, and as there are no physical motion of matters within a superconductor, thus there are no loses, this resulting in faster transmission of magnetic fields without losses.

Current and impedance

The origin of all motions in any material or environment is always magnetic field strength dependent. Where in the case of transfer of current in any conductive material for electrons to be moving forward or being capable to transfer current, the material or the atoms of it have in respect to their adjacent atoms two behaviours, one is attraction or gravitation and one is repulsion or outward motion.

In the connection of let say a power source to a energy consuming unit like a light bulb, the light bulb creates a position that has lower gravitational and magnetic field strength in respect to the sources' electrons magnetic field strength. Thus this negative gradient in the magnetic field strength causes the flow of the Magnetic field motion of the electron in the direction of the lower strength magnetic field, from the source to the component.

At the same time, as electron vibration is in the forward direction of the magnetic field strength of an electron towards the component and has to be maintained, there is a similar and opposite pull for the electrons of the conductive matter between the power supply and the components too. Where, this pull is the same as the gravitational field force between the power supply and the light bulb too.

Thus for the connecting wire to be able to keep its constituent atoms together, the atoms of the wire need to have equal repulsion and attraction in respect to each other and at the same time maintain the negative gradient in magnetic field strength between the component and the power supply too.

Thus for supply and component to be interacting that flow of the electromagnetic fields are maintain in between them and due to gravitation of one field to another, the reverse field flow or reverse attraction flow of the fields leads to gravitation field or equal to the field strength of the an electron magnetic field or what is call the impedance flow.

Where, the flow of the current equal to the strength of an electron magnetic field outward is the electromagnetic fields and the gravitational pull between two fields or the current of flow of attraction between the two fields, which create the pull of electromagnetism of the fields, is the impedance of the field.

Thus in fact we can compare the current and impedance to two Magnetic and gravitational field of the planetary system, one can say that the outward flow field of the planet or its Magnetic fields are the current or electromagnetism field and attraction or gravitational flow of the planet is the impedance fields in the matter, where the flow of magnetic fields are restricted within boundaries of a copper wire or an electric light bulb.

Note; At the point where the impedance or the current in a wire increase in one or the other, that is the point, where for example the wire separates and magnetic fields of the atoms of the matters can not hold on to their atomic balance Magravs as the increase in repulsion between the atoms of the wire causes the separation of atoms, and in the case large numbers of repulsion between atoms, then the separation or what is called in common language the melting of the wire occurs.

Where in fact the melting is not due to the heat, but in physical terms, the melting is due to repulsion of atoms of the copper due to not being able to maintain constant gravitational fields of atoms of the wire.

Experimental point's observation

In our reactors we a have the ability able to release the energy of protons which has magnetic field strength by order of magnitude of about 2000 times of an electron magnetic field forces.

Thus one can see how small amount of plasma can create and release vast amount of magnetic fields that one can use these magnetic fields in their dynamic state for the production of electric currents or Magravs in a confined of a small reactor, that these can be utilised for motion and production of vast amount of electric current in conjunction with other field within or within the vicinity of these type of reactors.

Further the interaction of these magnetic fields for example with physical copper winding outside the reactor in a generator structure configuration can lead to creation of energy as we are use to in present generators, without single movement or vibration of an electron within the cores of the reactor and only is presence of plasma of fields equal to the field strength of an electron.

Conclusion

The electric charges, magnetic field and gravitational fields are all of the same and of one origin. Where the gravity is due to pulling effect of two dissimilar poles of the same plasmatic magnetic fields interactions and Magnetic field is due to repulsion of two similar magnetic poles, and electric current is due magnitude of the flow of magnetic field from one field to another.

Thus the ***grand Unifying field*** is the magnetic field, and the missing link has been to understand that gravity is the product of interaction of two plasmatic magnetic fields, mass is the difference between the magnetic fields strength of similar and dissimilar field strength (gravity and magnetosphere forces strength Fig. 25 of the book), and the energy is the measure of the magnetic field that is transferred between magnetic fields at the speed that magnetic field can travel within a given matters' medium, for it to be able to move from one magnetic field strength to another, and the electromagnetic current is the rate of movement of the magnetic field from one field to another and where the electromagnetic field is due to magnetic field strength difference and is the equal to the magnetic field strength of an electron.

Thus the unified and common field is the magnetic field, between the gravity, mass, energy, and electromagnetic field.

Thus the unifying theory for the first time is complete and it is fully understood.

Where *magnetic field interaction* makes **the gravitational fields** and the *flow magnetic field from one field to another* creates **the electromagnetic current**. Energies can be created, from any ambient, depending on what one wants to produce or obtain from these currents or fields.

Electromagnetism is created *as magnetic fields strength are transferred from one field strength to another* and in the process of the flow of magnetic fields this leads to creation measurable field movement or measurable current from what is called "electromagnetic fields".

This simple sentence brings the whole of understanding between magnetic fields and its flow from one magnetic field strength to another and is the grand link between the gravity, the mass and energy and this finalises the long lasting missing link of the unifying field.

Now that one can understands that current is the rate of flow of magnetic field from one strength to other, and "the connection between electromagnetism, gravity, mass and energy" is finally understood. Thus the origin of all things tangible and their effects is magnetic field based and magnetic fields are the origin of all and unifying field in the world of creation.

Reference:

1; The Universal Order of Creation of Matters by M.T. Keshe (2009, ISBN 978-94-6087-001-9) Chapter 5.

*Magnetic field with capital M is the plasmatic magnetic fields created by systems like earth, which this spans beyond the boundary of their physical matter.

Index

A

- ***a-biogenesis*** 81
- animals 90
- anticlockwise **20**
- atom
  - hydrogen **31**
- atomic structure 32

B

- big-bang 33
- black holes 15
- Black-Hole 85

C

- CH4
  - absorption 68
- clockwise **21**
- CO2
  - extraction 67
- *CO2 molecules*
  - absorb 66
- communication system 103
- conversion 24
- cross-section of the light **21**
- current
  - creation 124
- cylindrical plasma 20, **22**
- cylindrical structure **27**

D

- dark energy 15
- dark matter 15
- dilution
  - reactor 90
- DNA **52**, 90
- dreams 94

E

- electro reduction 56
- electron **23**, 24
  - plasma 32
- energy
  - dark **29**
- energy of protons 128
- energy panels 81
- environment **22**
- **extraction process**, 67

F

- fields
  - tightness **30**
- fifth state of matter. 44
- first atoms 31
- food 90
- formic acid 62
- friction **24**
- Fusion
  - of light' pmf 102

G

- galaxial structures **27**
- gamma rays 96
- gamma rays strength 24
- Gans 41
  - definition 77, 106
- GANSE 79
- giant planets 38
- gravitational environment **20**
- ***gravitational pull*** 66

H

- heliosphere 37
- helixal **24**
- helixial **27**, **29**, 92
- Higgs boson 87
- Hydrogen
  - plasma 70

I

- ice particles 39
- increase in mass **23**
- infrared spectroscopes 55
- inner structure **23**
- interlock
  - polarity 95

K

- Kuiper belt 39, 96

L

- LED lights 62
- light
  - dark **28**
  - principal 36
  - surface **29**
  - transition translucent 28
  - visible **28**, **29**
- light bulb 127
- light Magnetisem **24**
- light-entanglement 93

M

- mafs **14**, **106**
  - of matters 28
- **Magnetic** **106**
- magnetosphere **20**, 23
  - universal 32
- Magravs **14**, 52, **106**
  - light 28
  - of the light 28
- MantraEnergy 56
- matter
  - dark **29**
- matters
  - principal 28
  - transition **24**, 28
- medical application 94
- metamorphoses

  - first 22
  - second 22
- meteoroids **23**, 39
- minerals 90
- MOFs 55

N

- nano CH4 74
- nano CO2 powder 55
- neutrinos 37
- neutron 24
  - plasma 32
- new position 23
- new state of matter 77
- North-Pole **21**
- nuclear decay **31**

O

- observes
  - pmf strength **28**
- Omar M Yaghi 55
- Oort cloud 37
- Oort clouds 96
- outer layer **29**

P

- plants 90
- plasmatic structure ***6***
- **Pmf** **106**
- pmtics 33
- PN junction 55
- **Principal mafs** **106**
- principal matter 20, **106**
- Principal matters **14**
- principal star **21**, **22**, **106**
- protein 99
- protein chain **30**
- proteins 81
- protomagnetic fields **25**
- **protomagnetism** 124
- proton **23**, 24
  - plasma 32

Q

- ***quantum entanglement*** 93

R

- ray of light 13
- **ray reactors** 93
- rays
  - alpha 28
  - beta 28
  - gamma 28
- red cell 51
- resistance capacity 55
- rotational motion **20**

S

- seeds of neutrons **31**
- solid magnet **21**
- South-Pole **21**
- sp2/sp3 55
- space technology 93
- spectrum **25**
- speed of the light *13*, 100
- speed of the transition **24**
- spherical plasma **22**
- ***superconductor*** 77
- superconductors. 126

T

- **Transition energy** **106**
- **Transition mafs** **106**
- **Transition matter** **106**
- translucent effect **29**
- twin stars 95

U

- unicos 93
- unwind 34
- unwinded **22**

V

- vitamins 90

W

- water 38, 56
- weight **20**
- WMAP 32
- wormhole **22**

X

- XRD testing 77

M.T.KESHE

THE ORIGIN OF THE UNIVERSE

The Origin of the Universe


Sister Universe
Man's Universe

Kf
The Keshe Foundation

Kf
Editions

Nuclear Engineer M.T. KESHE

本电子书不是官方正版，

而是使用从官方购买的正版电子书，

截屏＋拼接＋OCR文字识别＋重新拼版制作。

因此难免出现错误的字或符号，

如果您希望获得原始的官方版本，

请购买正版，支持KESHE。

QQ群：30137653

Stichting

THE KESHE FOUNDATION

(The Netherlands)

The Origin of the Universe

ITNOTGOG

Reflection

The creation of a new universe(s) is as simple as creation of an atom from the division of the neutrons, thus universes are made from division of bigger universes and the same shall be the future of this universe of the Man.

Copyright notice: © Mehran Tavakoli Keshe 2011. All rights reserved.
Nothing of this book may be replicated, simplified, translated and/or made public by means of print, microfilm, tape, audio-recording systems, electronics, optical and solid-state media, electronic storage systems, by network publishing or by any other ways without prior written authorization of the publisher or the author.

ISBN 978-94-6087-005-5

Illustrations and Layout: Dirk Laureyssens

Publisher: Stichting The Keshe Foundation
Registered Office: Jubileumplein 3, NL-6161 SR Geleen, The Netherlands
Registration Number: KVK 14089728.
Web site: www.keshefoundation.com
E-mail contact: info@keshefoundation.com

Forewords

In the past centuries so much discussion has been about the origin of this universe, where in the recent times the groundless concept of the Big Bang theory has taken hold in the scientific world and been considered to the norm accepted fact.

It will be explained in this disclosure that there has been start to this universe, but not necessarily in the way as it has been thought and promoted by the present scientific world due to their lack of the understanding of the universal processes of the magnetic field division and plasma decay as it is the norm in the nuclear structure.

The origin of this universe has to be on the physical realities and in parallel with the rest of the cycles of creations and developments of matters and field as we have seen and observed around us in daily life and the creation of this universe cannot be an exception to rest of universal order of creations and operations.

Introduction

The present visible universe to man is a larger scale in matters and fields of what have been seen by man of science in the structure of the plasma of the neutron, and universes division occurs in the same manner and by the same principle as decay of plasma of neutron to plasmas of an electron and a proton.

The creation of this universe is the replica of the same process as decay structure of neutron but in a larger scale in quantities of magnetic fields strength and matters. This universe is not the only universe in existence and this universe is created through the same natural processes as other elements and entities in the unicos and through decays, division and amalgamation of other fields and elements in the inner sanctum of their mother universe.

Thus in truth there are as many physical universes as there are galaxies and solar systems and man's universe is one of the units in this overall structure of the greater mother universes.

TABLE OF CONTENT

THE ORIGIN OF THE UNIVERSE 3
Reflection *5*
Forewords *9*
Introduction *11*
TABLE OF CONTENT *13*

CHAPTER 1 15

The Universe *15*

CHAPTER 2 19

Theory of Expansion of the Universe *19*

CHAPTER 3 31

The method of transportation of mafs in different mafs strength in the universe *31*

CHAPTER 4 33

How matters are created in the universe *33*

CHAPTER 5 35

The theory of decay and division of the universe(s) *35*

CHAPTER 6 41

The Man and his soul and their connection *41*
to the universe *41*

CHAPTER 7 45

The creation of gravity in the universe *45*

CHAPTER 8 47

Insight into the realities of the working of the Universe *47*
and what they bring about *47*

CHAPTER 9 77

The creation of Gravity *77*
Abstract 77
Hypothesis 77
Prototypes 77
Discussions 78
Magravs measuring system 86
Elaborations: 87
Conclusion 91

CHAPTER 10 93

The creation of Black Hole *93*
Abstract 94
Hypothesis 94
Discussion 94
Creation of the Black Hole 95
Conclusions 104
Elaborations 104

CHAPTER 11 109

The relationship between gravity, mass and weight *109*
  Abstract 109
  Hypothesis 109
  Discussion 110
  Conclusion 112
Parallel worlds *113*
  References 115

CHAPTER 13 .... **117**

The universal principle of division of pervious universe(s) and their decay leading to creation of new universe(s) *117*

CHAPTER 14 .... **121**

How would it end? *121*
Definitions *123*
The re-naming of matters and conditions *125*
Reference *127*
INTERNET LINKS *139*
  Internet radio interviews: 139
LIST OF ILLUSTRATIONS. *141*
INDEX *143*

CHAPTER 1

The Universe

The term Universe to me as a nuclear physicist's has one meaning, and that is the more of the same magnetic fields of different strength as it is in the plasma of an electron or proton. Where, the total behaviour and operation of all magnetic fields and matters created by fields within the operation of stronger fields' strength catchment's in the centre of each entity is considered to be of the same and through the same and similar processes.

Where in the smaller scale entity the like of the plasma of proton we call the bigger and stronger entity to be is the Principal mafs and matter, or what is commonly is called the up or down quark in the present physics, where in the universal scales we call these the central the principal mafs line, where the other components within the plasma of the universe are exactly created and operate as the galaxies, solar and plasma of electron systems within these universes are created and operate.

Thus, the difference between the plasma of a neutron and the plasma of the universe is the size of the mafs of the fields which has come together to create that entity and otherwise all self-contained gravitational-spherical and magneto-spherical entities this being the plasma of proton to the plasma of solar system, the plasma of a galaxy or the plasma of the universe, they are all created through the same principle and operate through the same physical conditions and restrictions.

Where, under certain conditions of magnetic field or gravitational fields strength and positioning in certain parts of the these plasmas, whatever they could be, conditions can be created that allows the growth and suitability condition that clusters of fields can become active and sustain a rhythmic and coherent field interactions that these can lead to creation of certain types of repetition of the same fields in these plasmas.

Where, the repetition of Magravs of these types' fields within these plasmas of different scale can lead to creation and sustainability of continuity of being able to absorb mafs in motion from their environment that these clusters of fields can sustain long-term durability and exist-ability, or what we call to attain the process of life.

Where, different versions of life can exist in the plasma of proton as it does in the plasma of the solar systems as is on earth and different forms of lives exists in the plasma of the universe and universes within the unicos of the creation of the bigger structures of universes.

Thus, this universe or other universes, which have led to creation of this universe and the cycle of the life of this universe in time it will lead to creation of smaller universes, where these in time have all come from one essence of a larger fields entity(s) and in time as they divide and they become weaker, then in time these fields will gather together to create a different universe(s) with different field(s) strength properties (Fig. 1).

Thus, this universe is not unique and there are others, which are created through the same process(s) and there is remote chance that there could be another universe similar to this universe in the ***unicos*** (Fig. 3) of the creation, but not necessarily it will have the exact combination and structure of mafs and positioning of its fields and matters in its internal structure as man's universe.



Fig. 1. Creation of new universes out of the division of a larger universe
through the process of decay similar to the decay of the neutron in proton and electron.

In truth the universes are created with a long whisper as one sees and hears gases leaking out of cylinder or a balloon (Fig. 18 C an D), and more like trajectory line depending on the magnetic and gravitational balances of their mother universe and outside environment, which they are getting released into and as the release gases try to find their new position in the new environment, which they have been released into.

Thus the creation of universes are not made with huge sound and explosion but very much with a long whisper as the plasma of the larger universe is dividing and ejecting its matters into two or more environments to guaranty the survival of its overall Margrave strength structure. Very much as the neutron divides and creates the proton and the electron plasmas.

Then as each universe reaches it's own Magravs balancing positioning then it again divides and creates further universes (Fig. 2).

This has been the truth about the creation of this universe in the unicos and in time man will come to understand that the creation of unicos, universes, atoms and plasma are nothing but natural dynamic processes of the interaction of different amount and strength of magnetic fields at different time and position in the overall world of the creation.

Then the question becomes, where did it begin to start with (ref 23), then one needs to understand the truth about the levels and position differences of the origin of the magnetic fields.

This in time will be revealed to the men of real insight in the world of creation as the man at this moment is not mature enough to understand and comprehend the totality of creation of the universe.

If one reads all the writings' of the author, and if! and that is a big if, then the reader will understand the truth about the essence of creation and the origin of the creation. One will come to see its creator way of operation and purpose of creating such an intriguing mesh of unify principles in all levels of creation in all of unicos's.


SISTER UNIVERSE
Galaxy
Galaxy
MAN'S UNIVERSE
Galaxy
gamma rays
X-rays
visual light
MATTER MAF's
matter
lower matter
MOTHER UNIVERSE

Fig. 2. The creation of Man’s Universe after the decay of it’s Mother Universe Magravs’ maf’s.

This shall be the point of maturity of the man to understand how feeble he has been created according to his understanding, where in fact he carries the whole of the world of creation within himself

CHAPTER 2

Theory of Expansion of the Universe

There have been theories and observational data, which support the concept of the expansion of this universe at the present time.

There are two aspects to this expansion theory of this universe, which each one has to be considered on the real terms of expansion of the universe that both can be scientifically acceptable.

In principle, it can be said that this universe cannot expand in to space in bigger unicos's space, if this space was not there for Man's Universe to expand into and to begin with. Thus this universe cannot be the only universal system that exists in the bigger **UNI**versal **COS**mology (unicos).


Man's Universe
Man's Universe within the Unicos (Universal Cosmos)

Fig. 3. The Unicos

The Man's Universe is a small fraction part of the unicos universes (Fig. 3).

This Man's universe is expanding due to two factors, ***firstly*** as the principal mafs of the central fields of this universe are unwinding they make available more mafs in the strength of different matters (Book 2) that as these fields open up they lead to creation of new galaxies and other entities, and ***the other factor*** is that the stronger gravitational fields environments which are outside the boundary of this universe's at the same time are pulling on this structure and keep it dynamic (on the same principle of motion of electron around it proton (Book 1, Chapter 19)), and the expansion of this universe in reality is part of the motion of the unicos as in the direction of the motion of all the universes in respect to unicos's internal central Magnetic and gravitational field forces interactions.

This meaning that if one looks at the overall directional motion of all the galaxies in this universe, it will be noted that not all galaxies in this universe are following the rest of this universe's galaxies on a straight overall spherical one line motion of expansion, but in fact part of this universe's galaxies overall line of motion is curvature and is following in the direction of the pull of an outside sister's universe gravitational field force, which this is necessary as this universe is to find its balance and position in respect to other external fields forces of the same of other universes in the unicos (Fig. 4).


position of
sister universe
Indication of the position of sister universe
in respect to Man's Universe in the Unicos

Fig. 4 The position of the sister universe in respect to the Man's Universe.

At the same time each universe possesses a central principal mafs and matter point and or central principal matter line, where these mafs strength and quantity of in this centre point or the centre line dictates the size of any universe and at the same time the Magravs created by this is like a Principal star and line in the centre of the universe that this dictates the position of the universe in respect to other universes in the unicos and this Magravs strength of the central line dictates the matters which are attracted and created in that universe and the matter and content of Galaxies' in respect to itself and no other matter in that universe.

Where, the total mass of the mafs and transition mafs in a galaxies are about less than five percent of the total mass of the universe principal matters and mafs in its central line and its principal star.

Thus the positioning and directional motion of the galaxies in the universe, the same as in the solar systems is dictated by the mass of the Principal mafs and mafs in that universe central principal mafs and star in the centre of that universe but in larger order of magnitude of contents and due to no other factor.

At the same time as the universe is created out of the ejection of the large quantity of principal mafs and matters and have motion in their time of creation, thus it is more feasible to consider an stretched line of principal matters and mafs across a central line of the universe rather than a centre point universe star of principal mafs and matters in the central line of universes.

Therefore the mass of the universes are measure of their principal mafs and matter content, which their Magnetic and gravitational field forces dictates every motion of matters in galaxies in that universe, hence strength of the principal matters and mafs in the central line and central principal star dictates that universe's-magnetosphere, gravitational pull sphere and the mass of that universe.

To understand the process of creation of mafs and matter and elements in the universe, one needs to look at the smaller scale universe, which are similar to the constituents' plasmas and the structure of an atom, its creation from division of the neutron to a simple hydrogen atom with it's plasma of electron and proton, the way they are created from neutrons division and the mafs which are released in the process of decay of the neutron into its environment, leading to creation of the simplest atomic system of Hydrogen.

Where, any mafs realised through and during the process of the division is not necessarily transferred to the newly created plasmas that lead to heating of the two new plasmas of the proton and electron.

Thus there could be some heating of the plasma of the electron and proton during and due to decay of its mother neutron, but this energy may and possibly and do *not necessarily is transferred totally that leads to heating up of the plasma* of the proton and electron.

Therefore the same applies to the division of this universe, when it was created ***from the decay of it mother neutron universe.*** Hence there are no logical reasons that the universe was heated and was hot and it has cooled for elements in this universe to be created due to creation of gravitational field forces.

As in the production of two parts of the plasmas of an atom (1) from the division of the plasma of neutron, the present assumptions in physics that the first atoms in the universe were created ***when the universe cooled***, this theory is not and cannot be correct and in reality *atoms are created through change* ***in the plasmatic fields strength of the mafs of the light***, secondly at the point of creation of the universe, the universe was not hot and there were never high temperatures that the cooling of the universe has led to creation of the first atoms as presently commonly stated. The first atoms and universally all first atoms' the like the atom of hydrogen in all mafs strength in the universe are created through the magnetic field strength reduction of the principal mafs and through no other means.

The concept of creation of heat and high temperatures at the birth of the universe is not observed in the creation of plasmas of electron and proton, when the plasma of neutron decays and divides into an atomic structure, and in the universe there are always continuity and parallels, thus the universe has never been hot that has cooled down to create atoms, and this is the reason why W-MAP (1) shows at present balance heat distribution in this universe (Fig.5).



Original WMAP-image from commons.wikimedia.com

Fig. 5 The universe heat distribution map (W-MAP of the universe)

In truth the current assumptions of initial heating of the universe at time of its birth cannot be true as the initial atoms of the universe and present atoms were and are created from the original principal mafs strength, ***which radiated out as principal lights rays of the universe*** in the centre of the universe and the initial atoms and matters of this universe were not created through cooling of the universe at the point of inception of this universe, which this universe itself is created from the decay and division of bigger mass of another universe as it happens in the division and decay of plasma of neutron in two plasmas of proton and electron. One does not observe heating in the plasma of electron or proton in this division and so be it the same, when the bigger universe divided and led to creation of this universe of the humans. (Fig. 18).

In fact, if! The universe was created by the present scientific assumption then the W-MAP should have shown cooler region in its outer boundaries than the present near homogenous heat distribution, which has been physical observed and from collected data by the publishers of the universal heat distribution map of the universe.

The heat distribution and the heat concentration on the central line of the WMAP confirms that the universe started from a central line in the middle and as the principal mafs of the universe unwinds and reduced in strength (Book 2) then the ***transition mafs*** and the ***matter mafs*** were released and created, and as these were spreading outwards into the space of a larger universe (Fig. 1) from its central line ejected mafs into unicos, then as the Magravs of the principal mafs in this central line region are converted and are reducing in strength, then the overall unified oval-spherical shape explanation of the WMAP come to exist.

Then as the total Magravs of the central principal matters reaches the point of the equilibrium of its forces, then at that point, this becomes the boundary of the universes boundary or becomes the plasma of the universe. At this point where they Magnetic and gravitational field forces cannot hold on to all the mafs and matter of that universe and this become the point of the limit of the expansion and the boundary of the universe and the envelop of the mafs at the given point in time, which are under control of these forces from the central lines principal mafs of that universe, where this expansion line becomes that universe’s magnetosphere boundary line.

Then, When a point in the cycle of the life this universe reaches that the overall strength of the Magnetic fields and gravitational fields of the central line principal mafs and matters cannot hold to their overall fields balance, then at this point this universe will go through a division the same as the division of neutron decay and all the matters and mafs at this point rearranged and regroup as and in the principal strength mafs and the universe then divides into two principal mafs of lesser masses of universes, which these new universes are magnetically interconnected as proton and electron do after the division of neutron and then these new universes go through the same principle of the principal mafs light unwinding and the same process as creation of new universe carries and central line as before.



Original WMAP-image from commons.wikimedia.com

Fig. 6 The microwave heat distribution of the universe shows a concentrated heat in the centre disc of the universe

That is to say through the principal mafs and matters are the way that universes divided and arrive form another universe to start a new universe and as the light in the principal mafs strength unwinds' in its new environment then the new envelop of the new universe starts to be created.

The same and similar process occurs, when the neutron decays and divides into the plasma of the proton and electron.

Thus, the universe is not created as a big-ball of fire which has been cooling down as has been promoted, but in fact the universe is created the like of as ***an ejected principal mafs*** is injected into a new area in the unicos and as the new universe environment and as the principal mafs radiate outward as light of stronger mafs, then as the weaken and radiate outwards in their new environment, then they create the other matters mafs and matters in this new envelop depending on the given pmtics strength of a given region in the larger process of this unwinding of the principal maf and matters and its lights (3) in this newly born and expanding universe.

Therefore: this universe is in fact created inside out rather than what has been assumed up to now that as it cools down to what it is, which this explains why even the universe is observed to be expanding, as the reason for expansion of the universe is being due to the presence of principal mafs in the centre of the universe and as principal lights of the principal mafs radiate outward, these light rays of the principal mafs strength while traveling in their new environment they reduce in strength and this leads to creation and transition mafs and matters, which further on losing its strength creates new matter mafs and matters according to given environments magnetic fields strength and in a given point pmtics, hence the creation of new mafs and matters and so forth, which this leads to creation of atoms and molecules and stars and so forth in this universe and its galaxies and solar system through the same principle.

Thus there has never been a Big Bang and the current appearance of the expansion of the universe is due to the principal maf, which as unwinds, it creates the expansion of the universal-sphere of this universe (3).

This method of the creation of the universe now explains' why there is a central gravitational matter concentration in the universe and as this pull is centred in the dynamic principal central line, which the original principle mafs were ejected out of the mother universe when it divided, where the injected principal maf of the universe at the time of its inception can be seen as the red line in the W-MAP (Fig. 6) which the more concentration of the mass of the principal matter sets in the central disc of the W-MAP and as these principal mafs create their own magnetic interactions, hence these create their own sphere of gravitational and Magnetic fields and thus the central gravitational of the universe is in the centre of the denser point of principal mafs of the centre universal heliosphere of this universe and as the more principal mafs are unwinding and spread outward are reduced in their strength they principal mafs become transition mafs and further as they reduce in strength they become the matter in the unisphere of the universe and as the principal mafs open up and reduce in their environment this leads to creation and expansion of the balloon of this universe in the unicos, and this explanation resolves the present mystery in the scientific world that, how and where the central gravitational pulls and the expansion of this universe which has been observed by scientists of the universe comes from.

This is how the plasma of the neutron decays and divides into plasma of the a proton and an electron too, where the different quantities of matters and mafs of different strength of the neutron are divided and injected in two new areas in their environment, that their overall Magravs of all their mafs are as original components that the plasma of the electron and proton concurrently maintain their overall Magravs of the original neutron Magravs (Fig. 7) and then as the matter and mafs unwinds and interact they reach given overall Magravs level and position as the new plasmas of the sub-components of the atom are created.

Where, this process of division of neutron due to micro-level of masses involved, these appear as an instantaneous process of creation of proton and electron, where the same applies to creation of universe and larger universes divide to guaranty their overall existence in the unicos.


MATTER
PRINCIPAL MATTER
F1
TRANSITION MATTER
MATTER
PRINCIPAL MATTER
F1
TRANSITION MATTER
NEUTRON
PROTON + ELECTRON

Fig. 7 The conversion of the plasma of neutron to plasmas of the proton and the electron.
The same process is considered to occur when the universe divides (3).

This being the reason why the proton and electron in their process of creation ***do not get heated*** as a Big Bang theory suggests but as different portions of principal mafs of the neutron which become parts of the plasma of the proton and electron unwinds and expand from the central line of their centrally disc which they are rejected into their environment by the division of the neutron, and as *their principal maf unwind* in this disc to the ***transition matter*** and then, as they weaken further, they create ***maf and matters in tangible mafs levels***, the like of the plasma of the proton and ***all other fragments of pmtics and magnetic fields*** in these new plasmas (Book 2, Chapter 1 and 2), in these processes of creation of new smaller plasmas of there is no Big Bang and there is not heating of the plasma of the neutron and electron (Fig. 8).


RELEASE OF PMTICS
ELECTRON
MATTER
G1
PRINCIPAL MATTER
G2
F1
G3
TRANSITION MATTER
NEUTRON
MATTER
G1
G2
PRINCIPAL MATTER
F1
G3
TRANSITION MATTER
PROTON

Fig.8 Decay of plasma of neutron in plasma of proton and plasma of electron.

Hence the theory of Big Bang is not correct and has no meaning in the real world of creation.

The same process can happen with the ***ray of the light*** originated from principal mafs strength (what is called the **principal light**), when this principal light arrives in the principal mafs strength environment and hence the first fundamental neutron principal plasmas and principal atoms' can be created in that given environment through the same principle as atoms are created in the matter strength environment (1).

At the same time the Magravs strength of the **P**rincipal **U**niversal **L**ine **M**afs (PULM, the central line of the universe)(Fig. 9) dictates the position and attraction of other matters, stars and galaxies' in that universe in respect to itself.


gamma rays
X-rays
B
A
C
D
E
A
B
visual light
MATTER MAF's
matter
lower matter

Fig. 9. The Principal Universal Line of Maf's.

The total mass of the matter mafs is about five percent and transition mafs of the matters about fifteen percent in any universe and is the same as with galaxies, solar and plasma of proton systems in the universe. The reason for this is due to the principal mafs (Fig. 10) and mass conversion and conservation and motion as they move within the plasma of the universe and lose their strength and reduce to transition, and matter mafs. Secondly if any mass more than this ratio of principal mafs is converted and stays within these systems, these can lead to unbalance and faster division of the entity, this be it plasma of the proton, neutron, solar system or universe.


Opening of the
principal Maf's of the Universe

Fig. 10. The principal maf's of the Universe.

Thus, the positioning and directional motion of the galaxies in the universe, the same as in the solar systems is dictated by the mass of the principal mafs and matters of the principal mafs of the universal line star mafs (pulm) of the galaxy and no other factor.

Therefore the mass of the universe is the measure of the difference in the interaction of the Magnetic and gravitational fields' forces that the principal mafs contents of the principal matter in the universe can produce and maintain. The same measurement principle applies with the galaxial and solar system.

Once these principal stars are formed in the universe then the Principal stars and the lights which are releases and radiate outward from the pulm becomes the means and the supplier of pmfs and nourishment source to all entities in the internal plasma environment of that universe, these be it galaxies, solar system atoms and so forth (Fig. 11).


Opening of the
principal Maf's of the Universe

Fig. 11. The unwinding of Magravs in an entity.

The same applies as to the galaxies, solar systems and plasma of proton systems too, where in fact in the centre of each galaxy, solar system and plasma there is the principal star (Fig. 12) with a plasma of principal mafs and matters and as these unwind, expand and spread within the Magnetic and gravitational fields which they create, these releasing, opening's and loosening of principal mafs in the pulm leads to creation of transition and then matter strength mafs and matters in the envelop of the magnetosphere of the universe leading appearance and creation of principal matter in the galaxies, solar and plasma systems, exactly the same as it has happened and has led to the creation of the plasma of a neutrons, stars, galaxy's.


gamma rays
X- rays
A
B
C
D
E
A
B
visual light
MATTER MAF's
matter
lower matter

Fig. 12 Plasma of the Universe: any entity can be created anywhere in the Universe as long as the appropriate maf's strength of that entity is reached through reduction or interaction of maf's of the Universe

Where, A(s) are the universal magnetic fields oceans in the form of fields forces or light, where sea of lights are created by the interaction of the fields which these can be in any light strength of matter, transition or principal magnetic fields strength, B(s) are universal matter oceans, C (s) are the transition matter and mafs oceans, D(s) are galaxies, E(s) are sub-matter mafs and matters oceans in the plasma of the universe, where all these entities they are created due to and through the interaction of the residual fields which are released by and through the release and separation of fields from principal mafs and transition mafs and matter mafs of the main or the subsequent divisions of these mafs as the principal mafs of the universe open up and divided and expand in the structure of the plasma of the universes' Magravs (Fig. 13).


gamma rays
X- rays
A
B
C
D
E
A
B
visual light
MATTER MAF's
matter
lower matter

Fig. 13 Plasma of galaxy: any entity can be created anywhere in the galaxy as long as the appropriate maf's strength of that entity is reached through reduction or interaction of maf's of the galaxy itself or its Universe's maf's

Where, the same principle applies to the structure of the creation of stars and planets in the galaxies and solar systems, and where the same process of creation of matters and fields is applied in the creation of entities in the plasma of neutron, proton and electron.

Where, A can be the point of creation of a star, a B the black hole, C the creation of planet in the solar system, D the cloud dusts and E the magnetic fields ocean of the galaxy.



Fig. 14 Plasma of Neutron: any entity can be created anywhere in the neutron as long as the appropriate maf's strength of that entity is reached through reduction or interaction of mafs of the neutron and it's galaxy itself or it's Universe's maf's.

Where, A can be the principal matter, B the transition matter, C the matter, D are the fields in motion, E are dust of matters in creation and motion within the plasma of the neutron (Fig. 14). Where even the creation of the X-rays and gamma rays are normal features of the plasma of the neutron as one observes in the process of the existence and operation of the galaxies (Fig. 15) and universes plasmas.

The universe as the plasma of the proton can expand according to the amount of the transition matters which can travel away from the principal matter line, and hence the expansion of the universe or plasma is dictated by the amount of the transition matter and mafs and speed of by which the principal mafs and matters can release which the pulm can hold on to the total Magravs of its structure. Now this can explain why this universe through WMAP (Fig. 5 and 6) shows to be more oval than sphere in shape.

On the other-hand the shape of the WMAP being oval can explain the same characteristics as one observes in the major composite gas planets in the solar system as they are not fully sphere in shape, but have more flat poles.

The oval shape of this universe confirms the existence of a central principal disc point in the centre of the universe and the flat disc spread shape of the principal mafs distribution in the central line disc of the universe.

At the same time the uniformity of the speed of the objects in the universe and galaxies shows the connection between the principal mafs release in the pulm.

This confirming the real process by which plasma and atoms are created and appear across the universe, where their accumulation leads to the creation of cosmic dust, stars and planets.

Fig.15 Galaxy (Source: Hubble)

Where, the concept of the cooling of the universe leading to creation of the atom becomes to be meaningless, as the creation of plasma and atoms is totally due to reduction in the mafs strength of the principal mafs to matter mafs strength and has no connection with heat or cooling inside or in any position in the plasma of the universe.

Where, the heat in different points in the plasma of the universe has only have the effect once the plasma of matter is created, then the environmental temperature in any point in the universe ***only dictates if the plasma in matter state will manifest itself as gas, liquid or solid.***

Then in fact this brings a question mark on the theory of time and space as then time will have no meaning as a new plasmas of atom can be created in the far corners of the universe from high speed mafs of the principal mafs which left the pulm, where some mafs go through the mafs strength reduction before arriving in the same point in the plasma of universe.

Thus; the theory that the whole parts of the universe are created about the same time and the more ancient galaxies are in the centre of the universe in some extent ***is not correct***. As matters in the universe move as their Magravs positioning dictates and hence some components of the universe move in such a rapid way which are not visible to the present technology available to the man.

CHAPTER 3

The method of transportation of mafs in different mafs strength in the universe

In all dimensions of the universal mafs strength, these be it principal matter, transition matter or matter environment, for the plasma of these matters to travel with the maximum speed and minimum loss of mafs to their environment, in all dimension of the universal mafs levels, the spherical shape plasma of the matter transforms itself to elongated plasma of itself or what is commonly is called as a ray of light (Fig. 16) (Book 2).



Fig. 16. Conversion of the spherical plasma of a neutron in a cylindrical ray of light.

That is to say for example as the principal light goes through the Transition fields regions of the universe, then the transition mafs and matters of the ray will come to take their position ***on the outer layer of the ray***, then through this process less pmf are used in interaction with these fields and matters of their environment and hence less friction and less loses of mafs of the ray, and in these interactions there are very little loses through the Magravs of the mafs of the transition mafs of the light.

Then any faint lights produced in the interaction of these rays outer mafs transition matter and of the same transition matters in the universe, where there are very few interfaces of the collision between the ray and the environment Magravs this gives the universe a dark but translucent effect that one can see through the universe.

In a way this interaction of rays transition mafs and universe's transition mafs is the cause and the reason for the invisible transparent structure which allows the production of universes discreet light that one can see through this universe but blocks the opportunity that one cannot see the lights from the universes outside this universe.

The most important point to understand is that light exists in all mafs strength levels in the universe, that is to say *there are lights in the principal mafs strength* as much *as light in the transition mafs strength* and *as man observe there is light in the matter world of the man*.

It has to be point out, that as one hears sound boom in the matter world when one reaches the speed of sound in the matter environment, or what is called the sound barrier, the same applies when the systems developed by man reach's and passes the ultimate speed of the light in the matter environment too.

That is to say when rays go from lower level strength to higher level strength mafs, one will hear audibly and will feel the vibration of the passing the light barrier.

This sound will not be a one of boom as when the sound barrier is broken, but due to the spectrum of the light transition forces, this noise will be more like a continues varying and long boom and roars. Therefore one will hear a long term tunes and not just one of noise.

This applies the same as one passes the transition mafs environment into principal mafs strength too.

Thus light speed barrier will always be the speed of the light according to man's mafs of his amino-acid and the visible light in all mafs strengths, which are the universes' creature's structures' mafs strength dependent.

When, the man become habitual to travel with the speeds faster than the mafs of matter strength, then on frequent bases man will hear a roar of a noise as passing the light barrier limit.

There are lights in all levels of the matter and mafs strength in the universe, that is to say there are lights in the principal mafs strength specific to that mafs strength environment, which is not necessarily the same as the white light as one observes in the man's matter world and at the same time each light has its own speed which is dependent on the mafs strength of its environment.

Therefore there are lights in the transition mafs strength as much as there are in the man's matter levels.

There are rainbows (Fig. 17) in all levels of the mafs strength in the universe as there are in the matter mafs strength of the earth. The light in all mafs can diffract according to the Magravs strength of the mafs of the given environment.

Fig. 17 The colour of rainbow according to the Man's pmtics strength in Earth Magravs strength.

CHAPTER 4

How matters are created in the universe

In the spans of the solar systems, galaxies and cosmos as the **gans** and **atom of the hydrogen** interact, ***they create the first seeds of creation of more powerful Magravs*** that leads to ***attraction and conversion of other light rays*** *in the universe* into gas, liquid and solids, which these interactions leads to creation of galaxies, stars and planets, where the light itself in different strength becomes the tools of the division elements the like of the hydrogen for it to start the cycle of creation of lives and the creation of intelligence in all corners of the universe (6).

The ***gas and gans of hydrogen*** becomes the dynamic fuel source of creation of the magnetic fields necessary for the creation and establishment of the stars and solar systems and their planets in some parts of this universe, as the interaction of different magnetic fields of gases and ganses lead to the creation of the initial Magnetic and the gravitational fields needed for these celestial bodies to be created in the universe.

The existence of nano materials in the core of the planets like earth has been initially disclosed (1), now it can fully be understood that how these nano materials in state of nano matter, gas and gans become to exist in the centre of these celestial entities and be the initial seeds of their creation once the mafs of the principal matter is reduced to the mafs of the matter strength.

It is important to realise that due to internal structure of the nano materials in ***layers*** and in ***gans state***, these materials by large keep their structural integrity, where high external environmental matter conditions like pressure and temperatures cannot affect the total structural integrity once they are in individual matter gans compound state. This meaning that internal structure and molecular binding of gans and nano materials in nano layers or composite structures ***will not be affected by the matter environment's the likes of temperature and pressure condition of the environment***. But the gans will be changing in its structure when conditioned to high-level dosage of radiation. Thus such entities have monoid characteristics.

For example, this is one of the reasons, why the DNA of the human being is venerable to changes and absorption of radioactive energy and in the radioactive environment or to burst of radiation, as the real structure of the amino-acid of ***the protein of the DNA chain is made of gans of matters*** and not solid matter of the same gases (6).

Thus, gans is the state of the structure of the light which has changed from dynamic cylindrical plasma of magnetic fields to a dynamic spherical entity of the same matter mafs, which its state of manifestation in matter environment is internal gravitational dependent and not environmental condition dependent. That is why one can observe the same element in coldest and hottest regions of the universe and still misreads them as atomic matter rather than nano-atomic or gans of the same matter.

Thus as mafs strength of the universe changes according to mafs available in any given part of the universe, this allowing the production or appearance of plasma of any matter which the mafs strength allows it become in that point in the universe.

Thus this why in one part of the universe one observes the hydrogen as in some parts helium or even gold can be observed without actual existence of any hydrogen atom any other matters.
In some part of the universe the matter take up their nano crystal structure, that the same matters looks to be the diamond structure of its parallel matter in another environment in the same galaxy or universe's environment.

Thus matters are created and to be part of the structure of star and planets or being in the universe according to the mafs strength of the environment and then they become appear in state of gas or solid according to the pressures and temperatures of that same given environment.

CHAPTER 5

The theory of decay and division of the universe(s)

In reality all theories which have been put forward up to present time have no parallel in the universe as has been observed by scientists.

In the universe everything and every process has parallel. In the universe there are always parallels due to the magnetic fields laws of interaction, and hence there cannot be any divisions from these laws.

At the present the scientific world has been intrigued and encouraged to understand the phenomenon of the creation of this universe and scientists have to unravel the mysteries of the creation of this visible universe.

In fact the creation of this universe as is visible to the world of science cannot be any different than any other process in the world of creation, and this universe has been created through the same principles as the rest of the magnetic plasmatic nuclear and atomic additions and divisions of entities in the universe.

This meaning that the present universe is created though the same method as has been observes in the division of the neutron's plasma into plasma's of electron and proton or smaller and/or bigger components of the same Matters.

Hence to follow the principle of the universal order of matters, this universe is created from the division of a larger universe that the man's visible universe is or can be the smaller part of the division.

The reason for it being the smaller part is that in the present cosmological term, this universe is following the attraction of the bigger part and hence it is always in the motion to follow the Magravs of the bigger sister .

This being the reason why it looks as the universe is always expanding as the external field forces pull and pushes the boundary of this universe mafs and as part of the universe has been noted to be collectively following different path of motion than the rest of the universe.

The portion of the independent motion of this universe is the indicator that where the bigger portion of the division of the pervious universe is in respect to the man's universe.

It has to be said that the original universe through the same principle of decay of neutron to plasma of electron and proton (1) and similarly as the decay of heavier atoms to two or more lighter atoms, through the same principle as the mother universe of the man's universe as itself has been created and was created from the division of a larger universe through the same method of decay and division.

The difference in the universe creation and decay is in principle merely is the size of the plasmatic field content in comparison to plasma of electron or proton after nuclear decay and division of the neutron.

Thus in fact this present universe itself is and was created some billion of years back from the division of a larger universe (Fig. 18). Where in Fig. 18 A to G, step by step the phases of the unbalance of the Mother Universe, it's opening and as the fields disperse in to two different zones in the unicos, where these fields interactions and Magravs positioning with Magravs of the Mother universe leads to the establishment of position and placement of two new universe entities, where the same process of decay of neutron and creation of Hydrogen atom occurs.

Hence every time as it is the same with division of the plasma of neutron to plasma of electron and proton, in this division the new universe carries the characteristics of its mother's universe, but due to reorganisation of magnetic fields and their strength the new universe will have a new and fresh cycle of time, which this shows as the age of the new universe.

In fact this being the like of giving birth to a child, where the age of the mother is irrelevant once the new seed of life is created and once the child is born, even though; the new child carries some of the same DNA fingerprint of the parents. The new life has its own cycle of life and its own timing.

Therefore the theories of Big Bang and M-11 as has been proposed in the past and present have no meaning and have no parallel principles in the physical world of creation of universe. One does not see the same Big Bang , when the atoms and neutron go through division or decay, hence this cannot be the same in the division of universes too.

Then if this was so, then every time an electron is created from the division of neutron there must be a Big Bang , This proposed principle is nothing, but showing the man's and scientific worlds lack of knowledge and ignorance of the real terms and parallel entities existence of all units in the universe.

In fact once the division is created and the universes are created, then the rest of the materials and matter content and how they organise themselves in that universe is more or less follows the same principle as before and once the fields are released within a given Magravs which the fields can created in interaction with each other, then the size of galaxies, stars and planets and even creatures within that given Margraves strength of the newly produced universe are determined.

The mafs and matters as arrive directly into the new universe are mafs first which can change to matter then divide between the two universes and then new matters are created in the new universes independently according to the Magnetic fields and gravitational fields in interaction with each other these mafs can achieve to maintain and create. Thus all universes in content are not and cannot be the same in material and mafs strength, and content of each universe are dependent upon the internal interaction of fields which are transferred into the new universes.

The new structure is dependent on the fields within the new universe and their internal motion of the new universe is internally determined by the total mass which the interaction of the Magnetic fields and gravitational fields of the universe can master.

This new universe has all the attributes and mafs of its mother's universe, where the subsequent production of mafs and matters like Principal matter and Principal Matter, planets, solar systems and galaxies and so forth, are nothing but the consequential outcome of all other effects in a given universe.

Thus in other universes there could be ***no physical matter*** the like of hydrogen and where for example hydrogen can be *only in nano or gans state only*, thus the life in these universes will be in order of fields and mafs strength rather than matters in this visible section of this Mans' universe.

But if this universe has the same structure as its mother's universe and co-birth universe, then this universes can be a micro replication of a bigger version, where these universes are macro version of the total universe in the greater universe.

Phases of the decay of the plasma of a Universe



A. Mother Universe


gamma rays
X-rays
visual light
MATTER MAF's
14B-3
matter
lower matter

B. Initial Magravs unbalancing


gamma rays
X-rays
MATTER MAF's
matter
lower matter

C. Loss of structure



D. Dispersion of fields of the plasma of the Mother Universe in the unicos.


Seed of Sister Universe
Seed of Man's Universe

E. The creation of the seeds of the new universes from the decay of the Mother Universe, where the two new universes have to maintain a magravs positioning in respect to the Mother's and each others magravs.



E. Full splitting of the Mother's Universe plasma into two new plasma's



F. Initial stage of creation of gravity and magneto-sphere of the two universes due to unwinding and interaction of the fields


Sister Universe
Soul of the Mother Universe
Man's Universe

G. The final physical parameters of the Mother Universe, the Sister Universe and the Man's Universe. Where the same process applies to decay of neutron and it's division in proton and electron, where Man's Universe is the like of the electron after the division.

Fig. 18 (A to G). The process of the division of the Mother's Universe in to Man's Universe and it's Sister Universe

Thus, in fact in the bigger portion of the original mother universe which the man' universe is partly created out of it is bigger or smaller mass portion of the original mafs of the mother fields, then the bigger portion or co-birth universe of this universe, due to the larger mass of its content, this universe's galaxies and stars can be much larger in proportion in comparison to the galaxies in mans universe and conversely due to larger Magravs of the internal structure of the larger portions, the beings within these universes can be smaller or they be totally different in operation than the beings in the mans universe.

It has to be said that life in any form is not exclusivity of the Earth, if this is the mind-set of some, this shows their lack of understanding of universe and how it is created and not the real truth and how fields and matters operated and function in the universe.

CHAPTER 6

The Man and his soul and their connection to the universe

In the structure of the Principal mafs centres or the Principal star or what is so called the Principal stars in the centre of galaxies and mafs and matters in the centre of stars and in giant planets and even in the centre of some planets, the Magravs of these objects seems to possess a stronger or larger than the mass ratio for such an object, that the object possess and covers a stronger Magravs forces than usually a matter in these regions by the present in the world of science knowledge become apparent. The reason for the stronger Magravs of these objects comes from the multiplicity in the Nano magnetic mafs' and matters' and layers in the inner structure layers in the sanctum of these objects.

In understanding the operation of different mafs of matters in the universe and the process of the reduction in strength of these mafs to reach the lower levels light, visible light and tangible structure's like atoms, then one should understand that the structure of the man's body will not change as the physical structure of the man goes through and from matter to transition matter or from transition matter to principle mafs and matters strength's environments.

The reality about this, is that the plasmas of the atom of the structure of the man, like the individual atoms, which are active in the structure of fundamental amino-acid molecule of the human body, these are all made of plasma of mafs of universe and for the proton or the electron of let say carbon atom in the amino-acid, this plasma of the proton has in its centre principal mafs and maters as well the transition mafs and matters and finally the matter mafs, which is its tangibility state which make matter visible to for example the eye of the human.

But once these plasmas of the tangible matter structure of let say proton and electrons of the carbon atom cross the barrier from the light mafs strength and matter fields to transition mafs and matters field strength, or even the body of the man crosses the principal mafs and matter strength, then at each point of field strength crossing, that part and components transition or principal mafs and matters of the plasma of the proton of the carbon will come to operate and interact in that entered field strength zone, and hence the integrity of the structure of the human being physical body will be maintained, but indifferent mafs strength level.

This meaning that the man will be still intelligent and will have the use of all its faculties, but the body will operate through the principal mafs of its plasma rather than present matters mafs strength of it material world strength.

Thus the man is not restricted to life in matter world only, but life in all dimension of strength of the mafs of the universe.

The reason for the plasma of the human body having the ability to operate in any mafs strength, is due to the fact that the atoms of each cell of the human body operate in the gans state of matter and not solid state of matter, which this gives the plasma of all the elements of the human body to cross mafs strength barriers by calling up on their mafs components of their environment.

That is to say the gans of the carbon in the amino-acid of the human beings' will bring forth and operate through it transition mafs strength in the transition mafs environment. Then the same gans of atom will operate with its principal mafs components in the principal mafs strength environment.

Thus the body of human will not be destroyed or evaporate in different plasmatic magnetic fields strength environments as it orderly crosses them.

But the body of the man will be destroyed if the mafs of principal mafs strength is applied to it in the matter strength environment, where in this case the mafs and the matters of the atoms of the man become diluted as a minor part in the mafs and matters of the applied fields.

Therefore man is part of an inclusive pattern of field’s in motions in the universe and nothing more or less can be attached to the existence of the man.

The man in physical term is an entity and in and through his soul the connection of the field between himself and the other fields in the universe.

The physical body of the man is the like of the planet earth, where it has mass and its magnetosphere which expands beyond the physical body, but its total magnetic fields and gravitational fields determines its position and relation with other matters in its solar system and in a small way it determines the position of its star in its galaxy and, then the position of star determines in a small way the position of the milky-way in the universe and so forth.

Thus the soul of the man is the external connection of the operation of the physical body of the man in the universe, it is part of one and inclusive realty of interaction of the whole.

Therefore the soul is part of the operation of the universe and every creation which can extent the effects of its overall magnetic field to others which can affect their position and existence is in possession of a soul.

Thus soul which magnetic fields created and expand beyond the physical body of the man is not exclusivity of the creature but it is the common denominator and common link between the man and other creatures of the God and has direct effect on the operation of the rest of the universe.

Therefore the man’s body due to the interaction of its atoms protons and electron and neutrons magnetic fields, this object creates its own magnetosphere and its own mass and this body is and has to be in possession of magnetosphere which shows the working of the magnetic fields of its constituent matters and its subcomponents and fields.

Where, in the physical worlds as the same as the solar systems possessing magnetosphere as so do the star and planet, so does the body of the human through the same physical principle possess the magnetosphere, which is so called aurora of the human body, the field of the aurora is part of the soul of the man, but is fact the total effect of the internal interaction of all fields of the body which creates the Magnetic field and gravitational fields of the body and their interaction on each other which leads to the interaction with their fields in the universe, this overall output of the fields of the body of the man is the soul of the man.

Thus; all dynamic plasmatic matters in the universe possesses a soul. But the man has the intelligence to allow the interaction of its soul with others. Therefore through this principle the man is responsible for all his actions and he stands answerable to other souls in the universe. As he decides how these fields which partial and fully control through the Magravs of the matters of his brain how and what happens in its interaction with other souls during its physical existence.

Hence the man has to understand, that universe and others, whom this universe has been created from and the universes which will be created from the division of this universe in the future are all interconnected and operate through the same fundamental principle magnetic fields.

Therefore there are parallel universes to this universe, with the difference in the measure of their magnetic fields and their position in their given environment.

Thus as we have the same and similar electrons structure's and protons structures in the same structure of an atom, this structure of positioning of electrons and protons is the same for all known atoms, then the same applies to the universe and the souls within them too. This meaning that there are similar universe as this universe in the greater universe and other universes which this universe has been created from or it shall create.

It has to be said that at the same time the matters in the universe have the same universal language of communication, where in the universe the common language is the basic plasmatic magnetic fields, based on the first plasmatic magnetic field strength of plasma or the simplest atom of matter of their environment.

This language is universal and once the man on earth understands this phenomenon and can fully measure the magnetic fields strength of the electron Magravs and uses this as the base strength, then man will be able to understand and communicate with rest of soul possessing creature of the universe. Until then, the search in the sound waves to look and try to communicate with other creatures of the universe is a primitive picture and shows the lack of mans understanding of the world of the Creation.

Therefore the gravitation, magnetic, radiation and other similar properties and interactions of the field(s) on each other in this and other universe(s) decides on how and the way the creatures in the different universes and in the man's universe would look and behave.

But in a essences they are all made of the same building block of *MAGNETIC FIELDS AND IN ITS AND THEIR INTERACTION OF DIFFERENT STRENGTH AND TIGHTNESS OF IT IN THEIR ENVIRONMENT*; This determining how tall and short and if one has eye or uses the interaction of fields to interact and communicates with other creatures of its environment, universe(s) with or without physical tangible or visible so called body.

May be now it can be understood what has been said that in the universe,

I have made man in the image of myself

CHAPTER 7

The creation of gravity in the universe

At the present time the scientific world uses the terminology that when the gravity took hold then that was time when the matters in the universe began to be created.

The reality is that as when the universe is created from the magnetic fields of the previous universe(s), then the content of the new universe is nothing but a soup of different strength plasmatic magnetic fields, then as these magnetic fields interact with each other usually laws of magnetism they attract or repel each other, where at this point the attraction fields of these plasmatic magnetic fields become the ***gravitational fields*** forces of the universe and the repulsion field forces of the magnetic fields become the Magnetic fields forces which the same fields create.

This interaction of fields in the plasmatic fields always enclose itself in the form of an envelope, which this always in the universe leads to creation of the spherical shapes of all entitles, this be it plasma of a neutron, earth, or universe?

The interaction of field and attraction fields which leads to creation of a circular motion of the gravitational fields as the fields in respect t the matter have keep their gravitational positioning too.
Thus the spherical shape of the fields is primarily due to the gravitational field and positioning combined together which this causes the magnetic fields in the universe to close and created a full circular; and hence the creation of spherical objects in the universe.

Therefore the gravitational filed forces of the new universe is created by the interaction of its content magnetic fields and in fact gravity is created by the natural laws due to interaction of two opposite polarities of two magnetic fields, which as these opposite fields interact they create attraction fields or what commonly called the gravitational field, where the strength the outcome field from this interaction of fields expands beyond the boundaries of the two original fields, this leading to the creation of an envelope or area of the effect of this new field that attracts other fields to itself and the strength and compactness of this new field leads to creation of gravity which in the universe this leads to creation of Principal matters, transition matters and then visible matter of galaxies , stars and planet and so forth.

The creation of gravitational fields forces in the for example the plasma of neutron, its strength and contest by large measure is dictated by the universal gravitational fields forces and not in full by the field which leads to creation of the neutron to start with. In the universe the creation of the neutrons are dependent on their universal gravitational fields forces. To this effect not all neutrons are all the same and not all neutrons in the different universes have the same gravitation a magnetic fields forces and dimension.

In fact the human race has to learn that what it is observed by them as the physical matter in fact is only a fraction of overall content of matters of the universe created through creation of gravitational forces and what he sees are not all of its matters.

This meaning that the universe has other matters and mafs contents and as the man's technological and intellectual capabilities expands and increased then man will come to see more of the realities of the universe.

CHAPTER 8

Insight into the realities of the working of the Universe and what they bring about

In the recent past scientists have talk about the term dark energy and anti-matter, where these covers the part of knowledge which they cannot find explanation for within the present understanding in the scientific world. For example the term dark energy is used to understand the forces, which is nor explainable and neither does fall within the conventional present world of physics too.

In this disclosure the terms like the matter, transition matter and Principal matter are used, where these terms are and have become recent addition to man's scientific vocabulary, where these can more precisely explain the rang and the medium, where each magnetic field in respect to their fields and its own magnetic fields strength is and would behave.

In the universe the same as in the physical matter world there are sources of magnetic fields, which are stronger in magnetic fields strength and some which are in the transition and there are some which are in between the strong and the weaker field strength.

In the physical world one called the stronger fields source the star, where in the plasmatic fields of the universe, the stronger fields' plasmatic regions or fields are easier to be called the **Principal fields**, which their interaction leads to creation so called **principal matters** (anti-matter), which these are real physical entities, which have been unknown to man up the recent times.

There are **transition fields,** which are in between the Principal matter fields in strength and the matter field's strength, and as these are in balance in between the both fields of Principal matter and matter world, and then these do not create visible light when they interact with Principal matter or matter fields strengths. Hence they tend to be like ***transparent*** and ***translucent*** in their environment and hence they give the appearance of the darkness to their environment.

When, magnetic fields are in motion they are called energies (Book1), where these translucent fields as they are in motion from one state of mafs to another they create what is called the Transition energy (commonly called the dark energy) which this explains the Transition energy mystery of today's science.

Then there are in the universe fields, which are the weaker plasmatic fields region in strength, which these fields are in the human protein plasmatic Magravs strength that they become detectable or what is called the visible or tangible matter.

Therefore in simple term, the Principal matter is the like of the sun and sources of energy in the universe, the transition matter is the magnetic fields strength fields travelling from the stronger field to weaker field, and the matter fields are the like of the planets of the solar system.

There are no mysteries about these fields, energies and matters, except in the lack of knowledge in the man's progressive and advancing science about his universe and living environment.

- Where, in the universe one sees the effect of the stronger Principal matter's fields as in the centre of the galaxies as the star do in the solar systems. The present world of science will come to realise the order of fields are all time kept and all followed the same rules and principles in all levels of the universal creation and created.

- This meaning that in the centre of the galaxies the entity which recently called as the Principal star of the galaxies, this entity in its centre have nothing but Principal matter magnetic fields, which their interaction leads to creation of strong gravitational fields. Where, this centre of Principal matter is covered by the transition fields as they are on their way to visible matter fields strength or what one observes as the dark environment around the central Principal matter region, hence the term black hole (Fig. 19) or Principal star, which this darkness region is only due to the balance transition between fields in motion and the fields which the rays are travelling through.


In the center of a black hole in a galaxy there exist the principal visible Light

Fig. 19 The Principal Light inside a black hole.

- The existence of the principle fields and matters in the centre of the universe with its strong gravitational fields is the reason as it seems that the Principal star is eating everything and absorbing everything this being rays or matters, where in fact it is the gravitational field forces of the Principal matter in the centre of this dark spot which are creating these large pulling fields.

- The size of the Principal star in the centre of the pulm is the combination of gravitational fields and Magnetic fields forces or the field's strength of the Magravs of the Principal matter content of the Principal star.

- In a sense as the Principal star extracts more material from its environment in the universe, then a position is reached that the total Principal matter absorbed by the Principal star from the objects, the like of stars, planets, plasmas and so forth, a point of criticality is reached that the gravity of the Principal matter fields exceeds the Magnetic fields of the Principal matter and that these forces cannot sustain their balance, hence the Principal star has to release enough material and fields that it can reach equilibrium between its two fields, and that is the point where the principal stars release vast amount of fields and matters without actually causing the division of the universe (Fig. 20).

- Where, these massive fields and matters of massive principle fields released will disturb the equilibrium of the universe as they travel the spans of the universe and in case can lead to creation of new galaxies and even stars and new mattes suddenly out of nowhere in the universe. These principal storms are very much like the sun storm one observes on the surface of the sun. In this process of rebalancing, it can observed in the universe, like as in galaxies that their Principal star has sodden volcanic eruptions in the rest of universal galaxies central principal stars as they absorb some of the principle matters and fields which they receive through the universes principal field eruption and the Principal star spewing of the surplus mafs and matters in to its surrounding environment.



Fig. 20 The absorption of matters and fields by principal stars of the universe or galaxies.

- The principal star of the galaxies as much as the same with the principal mafs and matters of the stars of the solar systems or their sun have observed this process in smaller scale. Where up to now man has not have had the tolls to observe that when the star of its solar system not only release the visible matters and releases huge amount of magnetic field into its heliosphere, but at the same time through and amongst these eruption of the Sun huge amount of principle fields and matters are released into the plasma of the solar system, which these have not be observed by the scientific world due to the lack of appropriate tools.

- The ejection of principal mafs and matters from the surface and right from the centre of the sun is an essential part of sustainability of the fields and matters within the solar system and essential part of the creation of new atoms and matters on the surface of the planets of the solar system. Where at the same time the solar systems as the whole on continues bases receives large amount of principal mafs and matters from principle star of its galaxy and principal stars disc in the pulm centre of the universe.

- It will observed that Principal star in the central disc of the universe even absorb principal light, in fact as light is an entity which possesses both gravity and Magnetic fields and its own mass, thus Principal star is extracting another object from its environment due to its stronger fields strength (2) is a normal occurrence. (Fig. 21)

- Where, the same has been assumed in the present science that black holes even absorb light, but the truth is that principle stars be it in the centre of the universe, or galaxies are created from the principle mafs, which are of the higher order of magnitude in mafs strength and the mafs than of the light mafs in the matter mafs strength. Thus in fact it is normal for weaker field's strength to be attracted by much larger and stronger mafs of Magravs of the principal stars in the centre of the universe or galaxies.


Principal Light in the center of the Principal star (black hole)

Fig. 21 Principal Light in the centre of the universe.

- But at the same time it is normal to see that the principal stars in the centre of the universe and galaxies spew stronger lights in the order of magnitude of principal mafs which are not visible to human eyes, where the light in the matter mafs strength is visible to him, hence man see one way traffic and not the real truth about the world of creation of duality and equilibrium.

- Thus in the universe it should be possible to observe points where the light lenses the Principal star if it is far enough that Magravs of the Principal star cannot overwhelm the Magravs of the light, but strong enough that Magravs of the light find their position in respect to the Magravs of the Principal star and creates their own Magravs positioning. As this can be observed in respect to the light and star of a system so as the star is made of mafs of principal mafs and matters too and has the same effect of the lensing for the lights rays too.

- Lensing of the transition light when passing the principal mafs regions of the universe should be observed the same way in the future as one observes the lensing in the matter light mafs strength. Where even the lensing of principal light should be observable in the specific cases and some regions in the universe.

- The matter, Transition Matter, Principal stars, the dark spots on the surface of the sun all are created through the same concept and principle that when plasmatic magnetic fields of the any field or matter is equal to the plasmatic magnetic fields of its environment, then there are no collisions between the matters fields which can leave or release any surplus or residual magnetic fields in the light spectrum of the mafs strength or lead to creation of magnetic wave in the visible light balance of the human protein pmf strength or that specific mafs spectrum anywhere in the universe. Thus these areas in the universe, the galaxies and stars surface looks as creating not too much light or what is called to be looking as to be darker than the rest of their surrounding environment(1).

- Thus the assumption that even light cannot escape the gravitational fields of the Principal star is position and the lights itself Magravs strength dependent.

- In truth if and when the Principal matter magnetic fields over time are reduces in strength and they unwind and transfer their fields to their environment, which as these fields slowdown, they become transition matter energies and then transition matter and finally they slow enough that they reach the plasmatic magnetic fields of the mafs strength, which at this point they become energies observable and absorbable and tangible to human field touch and visible to it virtual magnetic fields sensors.

- It has to be said that there is a great misunderstanding in the operation of the fields and mafs in the universe, this misunderstanding over time has reason due to the man's concept of heat in the *MATTER WORLD, WHICH THIS NEEDS SOME CORRECTION THAT CAN BE APPLICABLE IN THE UNIVERSE* as whole (The full explanation of the magnetic fields, plasmatic magnetic fields, matter and mafs is explained in the reference 1).

- The universe will never run out of energy and get cold, the universe will not expand to nothingness, but universe will decay to smaller universes as universal gravitation will never disappears as long as there are two or more magnetic fields remain in the universe that they can interact and attract and repel each other that they can create gravitational and Magnetic field forces that the whole process can restart again.

- In the nuclear decay one does not observe temperature increases and one sees uniform temperature gradients across the newly divided plasmas and the temperature distribution will be constant, this is the same with division of mother universes to smaller universes. Thus the concept of universe was hot and as cooled down matters are created is fallacy and not in parallel with the rest of the universal laws and processes.

- This observation is parallel with the W-MAP, which has been planned out by present scientific world, where one does not observe huge heated areas and points in the universal map. Here the equal heat distributions parallel with the nuclear decay and heat balance in the divided components of electron and proton after their division and long term motion in their environment is observed.

- The individual heat spots observed across the universe, these points are due to newly arrived mafs and matter movements in that given region of the universe and they are temporally condition.

- The central heat line across the W-MAP is due to dynamism of the principal mafs and matter in the centre of the universe and this is due to concentration and dynamism of the mafs and matters and their reduction to transition energies within this region.

- The creation of gravity in the beginning of time of the universe(s) was and will be primarily due to the interaction of combination of different plasmas of mafs within the plasma of each universe which have arrived from the mother universe and as the magnetic fields interacted, they create gravitational fields and Magnetic fields of the new universe, which these in turn as there are made of many mafs strength, which have arrived in the new universe from the division of the old universe, then different gravitational fields and magnetic fields due to their interaction are created, this leading to creation of different galaxies and matters. Thus, the universe never been cooled but pmfs from one strength meets-up with another and leads to creation of central gravitational fields of the universe and these interactions in the future will lead to creation of specific new matters in that universe, which these matters existence and appearance are closely related to the gravitational fields which the pulm mafs and matters have stared and maintain during the life of that universe and will allow to be created and be held in that universe. Thus all universes do not contain the same matter and all their basic matter is not based on the plasma of the hydrogen as is in the man's universe.

- The internal and initial gravity created in the plasma of any universe is on the same principle as the one created in the plasma of proton and electrons mafs and matters and from the interaction of their mafs of matters, transition matters and their principal matters once they arrived from the decay and division of the neutron. Thus the gravity of the universe is established from the interaction of different mafs and matters strength once the mother universe is divided and they are created in respect and relation to the original Magravs of the mother universe as these fields are separated from their mother universe into two or more universes like the one visible to the man. Therefore it can be said that man's universe is part of the multiples of universes which all have been created from one mother universe, which this present visible universe to man is a fraction and part of operation of bigger and more active universal order of the Grand universe.

- In reality one can say that this universe is nothing but like an electron in the structure of a uranium atom which this atom is part of a large mass of a large block of uranium atoms.

- This visible universe is part of a total universe and man's universe which looks so large to him is only due to his lack of understanding of the real terms of the world of creation and existence and is dependent up on his openness and understanding of levels of his own existence.

- The principal concept of creation of the principal matter and transition matter strength from mafs and matters in matter mafs strength can be achieved through the process of fusion of mafs, when these mafs and matters of lower order strength enter into the principal star regions of the universe and their fields become and are squashed and tightened in intensity of the fields within the mafs and Magravs of the principal star that the entered fields into the Magravs catchment's of the principal star merge different field strength magnetic rays and fuse these rays that they become and reach mafs equal to the strength and density of the principal mafs and matter strength.

  Thus Principal stars are, where the process of fusion of mafs and matters occurs to amalgamate and increasing the mafs strength of loose and incoming lights and matters from weaker strength mafs is set to take place. This is to say that Principal stars of different size and intensity in galaxies of the universe are the places where the principal mafs and matter are cooked up and separated and processed and manipulated into their given strength and then through conditions become to be known the like of quasars these new recycled stronger fields are released into their given environment, leading these principal mafs and matter to become the centre point for the creation of the stars and planets in their galaxies and as some become to be in the centre of the plasma of proton and electrons and so forth.

- Where, at the same time the Principal stars are the points in the universe that by and due to their high gravitational fields of their environment, this is the place in the universe, up on entry of different mafs and matters, these matters strength can be increased to higher level magnetic fields strength. Thus the Principal star are the points in the universe where the mafs and matters can increase their strength to transition matter levels or to the principal matter magnetic fields strength and where the transition mafs matters fields can be increased to the principal matter field's strength

- In the centre of the stars as the same as the in the centre of galaxy and universes, where the fusion process of fields and matters are considered to take place and heat to be generated due to fast movement of the pmfs. In reality in movement of the stronger and weaker mafs and reduction in strength of the mafs, which these changes disturbs the plasmatic magnetic fields of the Magravs of plasma of the components of atom, this be it the plasma of electron and plasma of proton in principal matter, transition matter or matter strength, this leads to release of mafs fragments, which these can manifest themselves as heat or radiation in their given environment mafs strength. This movement of plasmatic magnetic fields leads to weakening of the magnetosphere of plasma of the all atoms, this be it plasma of principal, transition or matter atoms, hence this weakening allowing the process of entry and amalgamations or fusion of different plasmatic fields into another magnetosphere of any other plasma or an atom or increase and amalgamation of lose mafs of different strength within the environment of a principal star.

- By creating and using the higher strength mafs than the gravitational and magnetic fields strength any entity this be it atom or rays, one can create conditions, where one can cause fusion of atoms, plasmas and rays without creating heat and any need for accelerating particles and in colliding them to create fusion as has become the tradition in the present plasma of matter fusion technology on earth in the recent times.

- If the full concept of fusion in matter level is to be achieved in much easier way, then it will more appropriate to separate the different components of the plasma's mafs and matters, amalgamate the same together and then allow the re-amalgamation of different mafs strength to take place. This is how fusion of field's and matters are attained the span of the universe.

- In the universe the principal mafs and matters are the sources of the energy and supplier of the pmfs of the universe, thus when the plasma of principal mafs or matters interacts or collides with the lower strength mafs in order of magnitude of any matter then mafs and magnetic field content of matter becomes part of the principal matter spectrum and their content is added to the mafs of the plasma of principal matter.

  Hence the current fallacy that when matter and principal matter interact nothing is left of the two, except some release of magnetic fields or energies, this is hypocrisy and man lack understanding of its own world and the world of the creation. This is like saying that if earth gets attracted and absorbed into the Sun of the solar system as a lot do on frequent bases in the universe, then there will be nothing left of the Sun.

  The principal mafs and matters are the source and stars of the universe and by order of magnitude and strength and the mass the principal matters and stars mafs are by far stronger and possess denser fields than their by-products the transition matter and matter fields strength which are created and released originally by the principal mafs and matters itself to begin with (1) which has led to creation of the planets and stars. Then how can the weaker and insignificant part in matter strength level destroy the larger entity?

  Thus nothing happens when matter entity comes to contact with principal matter (antimatter as is known at the present time) entity. There will be only principal matters left with addition into it the content of matters mafs and matters, which have collided with it.

- Thus the physical structure of the plasma of principal stars in the universe is as follows the principal mafs and matters in the centre, transition mafs and matters and the then mafs and matters in the matter mafs strength.

  This entity what man calls the universe follows the rest of the universe orders of linking the magnetic fields polarities of north and south poles together as has been observed in the man's planet. This universe is near spherical in shape in general and dynamic and rotational anticlockwise in direction of motion. But the principal star can pull into itself due to its strong Magravs and gravitational field's matters as well as matters to itself from its content plasma as well as from the unicos of it outside environment, where in the process it can separate their sub-Matters for these to be added to its principal matter too.

  Looked from outside this universe surly will possess rings as planet Saturn's does, as this universe has the same construction as the gaseous planets, but; with the difference that its rings will be colourful and much more dynamic than Saturn's rings.

- In universe(s) principal stars can be found which have anticlockwise motion and some, which have vertical rotation and may be some, which have combination of both clockwise and vertical rotation too. These motions are primarily matter and fields' strength and position dependent as has been seen in the man's solar system (1, 2).

In the principal mafs state of matter all matter more operate in the gans state of matter than the gas or plasma of the matter, where with the gans of the matter the mafs of the environment decided the appearance of the element in a given condition and in all cases tangibility of matter is the consequence outcome of these conditions.

Hence all matters in the universe are not matter atoms, but gans of matters, as gans of matter can take all lattice structural combination of elements, where for the matter of same element to converse from one lattice structure to another high temperatures and pressures are needed. Where, in the universe majority and nearly all conversion of lattice are done through gans of the matter and not atom of the matter.

To achieve the gans state of matter the environment of the atom of the gas needs low and continues flow of mafs in transition for the atom of the gas to be converted and its Magravs changes from magnetosphere of a gas to a magnetosphere of tangible matter of the gans (4) state of matter, and in fact this happens when the gravitational field of the gas is made more powerful than the Magnetic field of the gas and hence the plasma of the gas gravity contracts or tightens and hence the gas changes from gas to gans and becomes what is called solid nano state of matter in the atmospheric condition.

- Multi-layering of mafs and matters increases and exacerbates the initial magnetic fields strength of the matters and the fields they can create. This causing an increase in the strength of the Margraves of these objects and even Magravs strength can be further increased if the mafs and matters are in gans state of matter or in combination of different mafs strength in different layers.

- Ganses as gases once reach the state of certain structural lattice as in the gases on the earth atmospheric pressures, these ganses change their characteristics and take the properties of non-dimensional plasma or they become what is known as odder or what can be detected of their existence in their environment. This principle applies the same to the gans of the matter too, that the ganses of all elements have odder and hence the universe outside the earth atmosphere has an specific odder of its own, which in fact each galaxy has the same properties and different odder and each universe has its own odder primarily due to the structures of the gans(s) of the elements they create or they can hold on to, and the same element does not have the same odder in all corners of the universe. As odder is the mafs strength dimension dependent the gans of smelling entity mafs combination and/or of the gans's mafs strength itself.

- At the birth of the universe there has never been and in the future there will never been creation of heat, as in the same process of decay and division of neutron in to plasma of proton and electron. Thus the theory which has been created and been followed in the world of cosmology that universe at the beginning was hot and then as it cooled down and gravity took hold and then matters are created are false, The hot universe and cooling and production matter through cooling, this is an understanding of creation of matter and based on the matter world condition structure is base of old centuries and understanding of matter from cooling of gases and liquid into solids.

  The heat distribution of the universe is the same as the heat distribution in the plasma of the proton after the division from the neutron. This balance distribution of the heat has been observed and recorded by the W-map. This pattern of no heat and creation of gravity due to interaction of pmf fields in the universe leading to creation galaxies and stars are the normal process. Where in the universe matters operate through mafs and their environmental mafs and no other factors. This being the reason why one can observe matter in all corners of universe independent of temperatures and pressures which prevail in that part of the universe.

Matters in the universe are brought to the state of conductivity and connection through their Magravs and not heat and pressure and that is the reason why life exists in all dimensions and structures and intelligence in all corners of universe and life is not the exclusivity of water and oxygen based entities and environments the like the earth and its citizens.

- The present concept that the production of iron atoms are the limits of fusion in the universe and the point where the fusion of matters leading to production of iron and absorption of all energies of the star this leading to collapse of the star and that the star go through the final cycle of life as an active star, this again shows the man's lack understanding of the full science of creation and motion of mafs and maters in the universe.

  In fact due to presence of principal matter in the centre of stars, the process of fusion will go on and all heavy elements are produced through the process of fusion in the centre of the star and not as has been assumed when the process of red dwarf and white dwarf are initiated.

  Stars produce the heavier elements in a rapid process when the Principal mafs of the star releases part of its pmf, facilitating and making available pmf necessary for the fusion of the matters to heavier elements. All heavy matters in the universe are created in the fusion centres of the stars and most of very heavy material like uranium and heavier principal mafs are created in the principal star regions of the universe.

  The point to realise and which has been overlooked is that most of the universal objects like stars and planets, and principal stars they all carry in their centre a large amount of nano materials in all mafs and matter forms and it is correct to understand that in these areas there is a large amount of gans of matters too. The reason for the existence of these nano matters in the form of individual or specially in the form of layers and sheets in the layer boundaries or interfaces of one or different state of mafs or matters, the existence of gans and nano mafs and matters in these large objects leads to creation and production and enhancement of gravitational, and Magnetic fields of the these entities through the principle of interaction of dynamic motion of mafs and matters with magnetic matter or matter of these objects. As this interaction are the main source of increase in mafs and their effects in all matters accelerations in the universe and scientific world by large has not understood this concept in full, as if they would have understood this, they would have understood that there are no limitation within the structure of the planets and stars for them to create conditions that through fusion all elements in the universe can be produced within their sanctum during their cycle of existence, and not when they are at the their latter stages of their cycle of existence.

  In the centre of planets and stars always through interaction of plasmas and their capability to unwind and open up and release all their components of mafs and matters, then it is possible for the centre of planet to reach a point that they can release the content of the plasma of their gas, gans and matters that this leads to release of the principal matter of the plasma, that this high strength mafs through rapid reduction in strength can lead to rapid creation of new atoms and due to its localised strong Magravs in the centre of stars and even planet, this allowing the production and help with the fusion of large number of plasmas of proton and electrons separately, that further on by interaction of large quantities of these plasmas this can lead to production of any element in the centre of the planet or a star. This be it the atom of uranium or copper or even fusion hydrogen to produce helium.

  Fusion is not action, which is exclusivity of the centre of stars or universes. Fusion can take place in simple environment of universe, where there are no confinement matters like the core of the earth or where there are no high temperature regions the like of the centre of stars.

Fusion of elements can and do take place in the open spans of the universe, when the right mafs strength environment are created without even existence of no tangible matter.

Thus the creation of iron in the centre of stars being its doomsday has no meaning, and has no truth in the realities of world of production of matter in the universe, the reality is that if the centre of the star cannot create new heavier matters than iron during its working concentrated fields how can it do so when most of its matter are in process of disintegrating and diffusing in the environment of the star. Thus this is another fallacy about the doomsday of star and creation of iron atoms in the centre of the stars.

- In the process of the movement of pmf one has to understand that the interaction of magnetic fields and the repulsion of the similar magnetic field poles of the pmf of matters of the universe leads to creation of the repulsion forces of the universe, thus leading to its so called separation of its matters and what is called the expansion of the universe.

  While the interaction of opposite polarities of the same magnetic fields leads to creation of the gravitational field forces of the universe and universe cannot exceed its magnetospheric interaction size, where this is the maximum fields balance between the gravitational and Magnetic fields of the universe, and at the same time the mass of universe will remain the same as the mass is the balance fields between the gravitational fields and Magnetic field strength of the universe.

  Thus the mass and the content mafs and matters of the universe are set to be the same at the beginning of its creation less what pmf are transferred to it surrounding universe(s) during its life for this universe to keep its distance and Magravs positioning in respect its contents and in respect to others universes in the grater universal scale of existence in the unicos.

- When, the pmf of matters transferred by this universe to it neighbouring universes is more than what this universe needs to sustain its existence, then this universe cannot hold its present universal magnetosphere and gravitational balance, once this balance is disturbed then this universe like its previous universe(s) will go through division to find its new balance and this leads to creation of new universe(s).

  Thus, the concept that this universe will expand to point of running out of energy and go through crunch and/or dies as a cold entity or go through the contraction and go through a singularity point again, these are nothing but fallacy of the misunderstood and short-slightness of a few to realities of the operation of the universe and not in line with real world of existence as has been observed in the universe, and why in truth the creation of this universe should and division, but never ending process of the cycle life of this universe of its matters and fields be any different than the rest of universal methods of creation of fields and matters in their birth, fusion and decay.
  Therefore the limit of the expansion of the universe is dictated by the total Magravs strength of this universe itself and at the same time the space which is accommodate by and for this universe by the mother universe and the space given to this universe to expand into and the expansion of the universe observed presently is not dependent on no other factors.

  It is possible some times in the future this universe itself will merger and fuses with another universe and make a larger in mass universal unit too as much as it can divided into two or more universes.

- It has been considered that the noise which has been detected by scientist in the 1960's, that this noise goes back to origin of the universe, when this universe was made, this has no truth as the noise which is constantly can be detected from the cosmos is the constant noise of interactions of pmf of mafs of different matters and mafs in the universe and these are created continuously and constantly.

Thus is the same as when mafs of different field in the universe interact and create visible light, thus the noise from the universe shows that it active and living universe as different parts of it interact with each other, as one can hear the noise from the Sun in the solar system when it matters and field interact with each other.

In fact if there were any noise left from the time of the creation of the universe, by now it would have escaped from this universe through its magnetosphere into the mother universe, the way strong radiation pointed upward from the earth escapes from earth atmosphere.

- In the universal levels, the energy is defined by the term, that when the pmf are moving from one point in the universe to another, and as they transfer or they carry pmf of the principal matter for it to be slowed down to matter levels, hence this transportation of pmf of the principal matter to slowdown to matter level strength, this is called the energy of the universe or what commonly called the Transition energy (dark energy) of the universe.

- The universal energy is the one which the pmf in motion is carrying that is balanced in mafs strength with the environment in which they are travelling through which due to their balance field strength the two field create near to no resistance to each other that this condition creates near no interaction with pmf of its environment that leads to release of pmf that become visible, thus the pmf of the universe travels in the soup of its own field and hence less losses and hence the lack interaction, which this condition of travel does not create collision and hence no residual release of mafs of any significant and hence not much of the visibility of the travel of the mafs of the universe, but this transition energy is translucence and as one can see through it so much so that one can see through it stars billions of kilometres away as their light travels in the balance Transition energy of the universe.

  This concept of travel of pmf or Transition energy in the transitions matter is explained in the book “The structure of the Light” (2).

- The universal energy does not need to cool to create matter, to reach matter mafs pmf strength level, but the energy reduces in strength to pmf strength of the matter that matter can be formed, this being the reason why there is a homogeneous heat distribution is observation of the W-MAP as heat is not created during the early seconds of the creation of the universe. Thus the cooling phenomenon of the universe is a fallacy.

- The reality of the operation of the universal system is that the universe is made of pmf which their mafs and matters in motion become energies and that is where the cosmologist says that at the point of birth the universe there was only energy and as it is known now energy is defined (1, 2) is nothing but magnetic fields or plasmatic magnetic fields in motion.

  At the present some consider that there are more Transition energy than transition matters, which is not a correct assumption, where if this was correct then this means that the principal mafs and matters are unwinding much faster and in a rapid manner, which if this state has or to be achieved in the universe, then this means that the losses are more than expected and this can indicate that universe is losing too much too fast and this can be an indication that the universe is getting ready for a further division into two or more universes.

- At the same time it is possible as the universe was created from the splitting of the mother universe, then the separation of the pmf of that neutron universe due to separation of its mafs and matters have released some pmf, which might have created some localised heating in some parts at the point separation and division of the neutron mother universe, which this separation leading to creation of hot spots or small heating of the new universe in sporadic positions and conditions within the plasma of the universe.

- The plasmatic magnetic fields strength that are released from the Principal matter to matter levels and during their process of the strength level reduction from principal matter to matter level, what is known as the Transition energy, as the plasmatic fields need space and matter in the universe to release and lose some of their strength to their environment to reach the plasmatic magnetic matter mafs strength level, which is mafs in motion from one level to another strength level is known as the Transition energy or universal energy or what is called the universal energy in motion.

  The speed of travel in the universe has only relation in respect to its mafs and matter strength environment, hence one can travel at the speed of light of environment strength in any mafs strength, this meaning that in the matter environment on can go faster than the speed of the light if one travels with the Magravs of the plasmatic magnetic field strength of the transition matter or Principal matter plasmatic strength level.

  Therefore one can only travel with a faster speed than speed of light in matter environment only if one has the capability to create and/or captures Principal matter or transition matter plasmatic magnetic field strength in a Margrave positioning reactors (1).

  Hence the limitation of the speed of travel limited to speed of the light in matter environment is applicable if one use matter and mater mafs for transportation otherwise there are no speed limitation in this environment as one can travel faster than the speed of the light in matter environment when using principal mafs strength in the cores of the Magravs systems, where the speed of the light in principal matter environment is millions of times faster than the speed of light in the matter environment.

  One has the ability to travel any speed in the universe and with any mafs and matter plasmatic fields strength in but there are hazards to consider prior to taking such a travel.

  The theory, that the speed of the light to be the ultimate speed of travel is only applicable in the matter environment using matter plasmatic magnetic field strength and it is not true if using stronger mafs strength, thus one can travel the spans of the universe by using higher order mafs with speeds millions of times faster than the speed of light in matter mafs strength like on the surface of the earth.

  The body of the man will not feel any difference and will behave as one is in the jetliners of the last centuries as the pmf of the mafs of the human body cells contains within their structure mafs of principal matter, then the man will not feel that much difference travelling with speed of light or thousands of times faster than speed of the light in the universe.

- It has to be noted that as in the matter and mafs universe and environment, in the principal mafs and transition matter environment, these environment possess their own shock waves and speeds of sound and as said before even smells and odour of themselves, which these are different than the ones in the matter universe. One can smell the Principal matter and hear the noise of the transition matter interactions, once one is trained and developed the senses for the observation of the transition matters and principal matter which are part of the structure of every living thing as these matters and mafs are part of the structure of the plasma of every proton and electron in the matter environment of the universe.

- Once understanding the structure of the universe, it can be conclude that universe will never end, there are no singularities and no cold ends to it and no crunch, and only for ever the universe(s) will divide in plasmatic magnetic fields strength and from one mafs to another and then in fusing together they repeat the same process, and as the universal structure never can lose any of its fields through by its natural laws of conservation in physics, then only matters and matters converts from one matter or mafs to another form of mafs or matters and order of preservation of fields and matters is obeyed even in the bigger universal order as has been in the matter world as has been studied in details over centuries. Thus preservation of energy and conversion from one form to another is the essence of creation in every levels of the bigger universe too.

- In the matter universe for example smell is only diamond structure of the or SP3 structure of the same atom in the gas state, thus in the principal matter environment the principal matter possesses and have different states of matter like the gas, liquid and solid state of Principal matter too.

  The same there are molecules and atoms and plasma of the Principal matter too, therefore principal matter have smells and odours and they frieze and they boil and they create clouds and become all thing as one has observed in the matter environment of the universe too.

  Then one can ask the questions that are the cold and warmth the same as the matter universe as in the principal matter universe. And the answer to this is most certainly is yes, with the difference that the temperatures are beyond the levels of man's understanding as the strength levels of plasmatic magnetic field in these environments are off the scale of comprehension of the human at the present time.

- Then the point arises that are there lives in the Principal matter and transition matter scale of plasmatic magnetic field strength of the environments of the universes, and the answer to this is most certainly yes, as the same structure of interaction and creation of cells and life exists in the these environments in the universe as are these conditions available and possible in the matter environment in the larger scale of the working of the greater the universes.

- The matter made available to the matter universe by the down levelling of the plasmatic magnetic fields strength from the Principal matter levels is what allows the creation of the matter, where these new matters have to find physical Magravs positioning in respect to each other, this need for new positioning in cases can lead to movement of the matter and increase in spacing of matters in respect to each other, hence this new increase in the spacing looks as the universe is expanding. Thus the increase in the spacing or expansion is limited as the matters and the rate of conversion from the principal mafs to matter has a limit and hence the universe cannot explode and only thing which can happen to the universe, is that as the Margrave of the universe is reached a point that cannot be sustained in its present mafs levels needed for the creation and sustaining its Magravs level, then the universe in a gentle way divides to guaranty its overall survival in two parts, rather than losing everything in the mother universe to other universes all together.

- The universal Magnetic fields within the transition matter is the force which pushes the universe apart and the gravitational fields within the transition matter is what brings the matters of the universe together and is the glue of the universe. Where both these forces are created by the principal mafs and matters field's interactions of the universe and the transition matter is the medium which they use without interfering with to a large extend for these forces to keep the universe in its dynamic condition.

- If the rate of the conversion of the principal mafs reaches to the point that there are more energies in transition mafs strength levels that the rate of conversion cannot lead to creation of matter mafs of magnetic fields strength, then the transitions energies fields interact and this will lead to creation transition matter, which this condition is abnormal and this ultimately in some cases can lead to creation unbalanced Magnetic fields and gravitational fields within the universe, and this is the trigger point for sudden expansion of the universal magnetosphere in certain point and as this cannot be sustained, then the universe goes through division and the universe and creation of two or more fragment of this universe are the consequences of such condition.

- It has to be clearly understood that the neutron division to electron and proton, usually is caused due to sudden expansion of the neutron magnetosphere, which is caused through the same process of the rapid change of the principal mafs to transition energy, which this leads to temporarily creation of transition matter that this creates a new magnetosphere condition which cannot be sustained, hence the neutron goes through the process of division to electron and proton too.

- As the pmf of the transition energy slows and reduces in strength once reaching the boundaries of the universe as it happens in the planetary upper atmosphere and solar systems heliosphere, in the same way and by the same principle these transition mafs will rain inwards into the interior of the universe, where they started their lives from and at the edge of the universe boundary the same as cloudy earth in its upper levels will have showers of matters in the form of small plasmatic matters and mafs and this looks as universe is raining inward. Thus once one look at the boundary of the universe one will see cloudy or a hazy shell, in fact this haziness it is nothing but the weak mafs and matters which are lingering around as clouds do or dust particles do in the planter systems upper atmosphere.

- The same cloud systems do exist in the solar systems heliosphere too, where this zone where most of meteoroids and asteroids of the solar systems find their seeds and receive their regular matters and mafs from.

  It has to be said that once man learns to cross the boundaries of the heliosphere of the solar system, the travellers of the crafts as is done when man leave for the travel to the moon at the present time, these crafts as they enter the heliosphere of the solar system they will encounter the same misty cloudy space at the edges of the solar system too and still they have to deal with solar heliosphere re-entry and cloud dusts and so forth as one encounters in the re-entry into the earth atmosphere.

  On the edges of this universe one will see weak pmf of matter and transition matter and transition energy plasmas and even one will observe the entry of other mafs and maters and plasmas in all mafs strengths and entry of universal meteoroid from other universes and unicos, as one sees meteoroid and radiation entries into the earth atmosphere from the solar system and cosmos. There are universal lightings and universal meteoroid too, in fact if the W-map observers look for this they will see another storm and lightings as these vast energies and large matter enters this universe at the edges of the universe, but they simply have registered these as hot spots in this map’s outer boundaries.

  The existence of these short lived hot spots will show that they are dynamic, live a short life and their energy is fast moving, as it happens when one has meteoroids entering into the earth atmosphere.

  In reality the existence of these hot spots on the edges of the W-map should give a clear indication to the man the existence of other universes and the greater universe as earth is part of a solar system and a galaxy, the same is with this visible universe of the man, and all one sees in this universe as the same is repeated in the greater universe too.

- One of the fundamental principal concepts of the universal energy is what the scientific world of today to a large extent has not understood fully and has up to now ignored this fundamental principle of the pmf magnification using the pmf of the mafs and matter and energies and specially the universal energy.

-

If the scientific world understand how universe uses its dynamism and its inner content dynamic universal energies layering to magnify its power in its operation of this universe, then men of wisdom will come to realise that one does not need principal matter that much and in truth any matter so much all to operate this vast universe and transfer energy to all its far distance corners.

The world of science of today has been by large ignorant to this fact and has not managed to understand the magnetic layering and dynamic universal energy principle and in turn this has put man in disadvantage in comparison to the technological advance with other travellers of the universe.

Man of wisdom should look within to see the creation of their own being, then they will come to understand how small amount of matters and mafs and magnetic fields has been creating conduction and energy transfer in their own structure without utilising or using very little mafs or matters, then they find the power of creation and its application and manipulation for untold usages.

Then they will realise that one does not need wormholes and all that fancy words to travel within the universe with the speed of their own creator. This shall and will remain the mystery of existence upon the time when man learns not to trespass the boundary of others and he learns the existence of balance and true peace within himself and its people and it's surrounding.

- One should understand the concept of multiple principal stars operation in one galaxies system and the role they play to create disc like or spiral galaxies. The operation of visible and invisible principal stars in the universe will play the same role as the twined solar systems and twin galaxies, where in this cases the twined principal matter centres are and have the capability to discharging different pmf strength according to their anti-martial gravitational pull and the measure of the mafs that they might release to control their field of domain. The multi- principal matter centres are and can be used in the space travel in a fascinating way, where once creates multiple jumping steps, with differential and opposite dynamic direction of motion of these Matters. The speed and protection created from and through these manipulations will give the man the chance to travel the length of galaxies and universes in the minutes, but one has to be aware of the destruction power of these technologies as there will nothing left but pmf of the creatures travels of these universal craft if things goes wrong at these mafs levels.

- It should be noted that the shapes of the galaxies and their physical appearances, should teach one the power of the effect of the other matters and entities around them as they will allow and pull an push these objects toward or away from one point or other and hence allowing the appearance and the physical visible structure of these celestial bodies to obey and have a given shape, this is important in the understanding that one has not to look at an entity but look at the surrounding area of the entity to understand the limitation of the operation and the shape of the matter and mafs internally and externally as it is allowed by the environment of the entity for it to exist within a given point and time of a system, this being a planet, solar system, galaxies or universal entity.

- The uniformity of the pmf within the plasma of a proton, an atom or a universe these all show the equilibrium and balance condition between all the participating magnetic fields forces which have been designated to the entity at the point of its inception and creation. Thus, if one sees a fast moving object the like of the Plasma of an electron in an atom or in a larger part the universe, then this does not mean that the universe is expanding and it will be chaos internally in these entities. Thus the fast movement of the internal matters and mafs of the universe does not mean that the universe is expanding, on the other hand this means that the universe is internally controlling its mafs as repositioning to guaranty its existence as an entity and at the same time the universe is holding its position or what is called universal Magravs positioning in respect to other universes in the unicos.

Thus this universe will have matters and mafs which will be moving away in one position but at the same time other fields in the universe will be moving in the opposite way to, but it has to be said that the conversion of mafs to matters creates a visible expansion, but overall gravitational field forces of the universe cannot be changed and the universal order of preservation of fields will be maintained, does not matter what is converted to what fields and matters and the internal universal gravitational fields strength will be maintained and preserved.

- The universe has laws and conditions and has primary atoms and particles, at the present man has managed to understand the structure of atom and plasma of proton and other particles and through this understanding and his vision of his universe thinks that the atom of the hydrogen is the simplest structure as he can see and understand, in time this will become apparent not to be the same for all creature of the universes, but up on and until then man has to learn that the fundamental particles and unifying fields and the fundamental fields of universe are the simple magnetic fields of the universe and the whole operation of the universe is based up on their interaction and operation.

  But at the same time man has to learn that all created entities in the grater universe have achieved a common method of communication or what is known as the universal fields communication, all created being which have managed to influence their environment and have managed to interact with other intelligent being individually or as unified groups and have managed to accept one universal communication language that is acceptable to all, this language is known as the universes language and is bases on the strength of the pmf of the different strength and not based on the voice or sound or physical alphabets and shapes.

  The man will have to learn this language and will be able to communicate with the other intelligent created entities in the universe once man learn to find peace within himself and reaches the understanding that they cannot trespass and cannot create division in the universe as they have been accustom to on earth to get their way and in achieving and attaining physical possessions and that in the universe martial possession are nothing but the lack of man's understanding of his position and short slightness of use of his intelligence.

  The universal language is transparent and clear language and works on the pmf waves strength and has standard forms and accepted levels for communication depending upon the creatures of different environments which creatures are initiated from.

  Where, one should understand that not all created intelligent beings in the universe need or needed the physical planetary structure as human do for their existence for them to be created or to survive.

  Life is created in the universe in and within the fields of the universe and it does not necessarily need physical tangible, food and land for it to exist and collaborate and operate with others in the universe.

Whereas, and as long as the Man tries to contact others through pictures and voices using the present technological advancement, man will find in general he will have a long time to wait for the response, as the other created intelligent beings of the universe have been and are and will be visitors to man's home from the time of its creation and to its demise, but the universal language will be established and communications will be opened when man learns that he does not need to take more than he needs to and at the same time man does not need to create division to get what he desires and cause conflict.

The cause of isolations of the man from the universal community has been his lack of understanding that in the universal language the other creature do not need to use words but they can and do understand and communicated at pmf fields levels, thus the thoughts of the man which is pmf based in his operation in the brain of the man, these pmf are detected and are like visible light to these creatures and as what is said they can see and understand the real intentions of the man's deeds without man uttering a single word.

Thus man isolation from the universal community has been in forced up on it out of protection of the universal peace, rather than man's inability to find the other creatures to communicate with.

- The Universe in general is a peaceful place and wars and conflict has been things of the past and a long-long time in the past, hence once the man learns the advantage of peaceful living, then man will learn the universal language and then man will be allowed to learn more and join the universal community of Beings, irrespective of these being physical or field appearance to the eye of the man.
- One does not need eye to see but the intelligence to understand, and then the real sight is the real will of the observer of the beauty of the creation in all levels of universes.
- In the material world for example the neutron always divides into balancing masses that the overall gravitational positioning of two new masses can guaranty the existence and continuation of the life of the neutron in the same material world. This applies to the universe too, that universe will divide in mass and as in the neutron the lighter mass will have to follow the graters mass fields forces Magravs motion and hence the universe of the smaller mass will be more agile than the heavier mass. Whereas, the smaller mass universe will be and has to follow the internal motion of its own mafs and matters and at the same time the overall Magravs of the smaller universe has to find its position in respect to overall Magravs of the larger universe and the overall dynamic motion of the mafs and matters which the bigger universe creates.

  Thus, the smaller universe can be in **a** snapshot or in the case of man life time over a million years, this universe be looking as it is stationary in its internal space, but in fact this universe is following another larger universe at very high speeds itself to keep its position and at the same time the universal centrifugal force of motion allowing the universe to hold on to its content of its own mafs and matters.

  All universes the like of the galaxies and solar systems are all in motion not only internally but at the same time they are in motion in respect to their the other half of the their mother universe, which it was originated from. The overall direction of the motion of the universe in its bigger universe can easily be detected and realised. The direction of motion of the universe is shown by the directional motion of the mass of universe, which is moving out of normal direction of the whole content of the universe itself. This meaning that, if! The full matter motion of the universe is planned out; one should see a region, which is moving as a whole in totally arbitrary and independent direction.

The reason for this envelope of the mass following an independent directional motion is due to the fact that this mass of the universe is connected Magnetically and gravitationally is locked to the direction of the interaction of the Magravs of this universe in respect to the Magravs of it co-birth sister Universe (Fig. 22).


Sister Universe
Envelope of mass of galaxies moving with different speed within each Universe
Man's Universe
Indication of the position of sister universes in respect to each other through the separate mass movements in their plasmas

Fig. 22 Envelope of galaxies in each Universe indicating the position of the Sister Universe.

The mass of the matters involved in this motion should indicate the extent and power of the Magravs interaction between the two universes.

This mass moves in all three hundred and sixty degrees direction as the co-birth universe is dynamic and has its own dynamic Magravs motion too.

This independent zone in motion in the universe has already been detected by the cosmologist for this universe, but they could not understand the reason for this independent part motion in the plasma of the universe.

Thus the direction, which this mass in the universe is moving and is positioned, this shows the position of the co-birth universe in respect to this universe.

Therefore if and when the man's scientific and technological achievements reached the level in the future that man can see through the universal magnetosphere, then the position to look for the co-birth universe, would be the direction where this internal mass is in motion and at the same time the distance of the this internal mass from the edge of the universe will show the distance of this universe in respect to its co-birth universe.

- In the universe the heat and cold is not measured in the way, which has been accustomed in the world of physics of today. In the universe heat is measured to the extent that the matters pmf can be loosened to allow the bridge of what is known as the atomic or molecular magnetosphere.

  Thus what is commonly known, as the coulomb barrier, in the atomic physics is only the extent of the resistance or the tightness of the Magravs of the atom. In fact man has to realise that if he unifies the terminology then he will solve most of the problems in the world of the science of physics. For example, by unifying the word of the magnetosphere and coulombs barriers, which in fact these are both the same properties and principles; where one shows the tightness of the Magravs of the planter system and the second show the same for the atomic structure. If this discrepancy in language is resolved and man understood all phenomenon of the creation of magnetosphere in all levels universal mafs strength which has been discussed above, then the nuclear and theoretical physics would not have the problem in creating and maintain fusion of all matters and mafs in the universe.

  Thus for fusion one does not heat or speed to create and achieve fusion, but the loosening of the Magravs or dilution of the Magravs of the mafs and matters will lead to fusion and creation heavier elements without the need for the elaborate accelerators and others gadgets which has become the tools of the advance science of today.

  The use of the accelerators are nothing but to show the true lack of understanding of the scientific world in the what these scientists are trying to achieve and their misunderstanding of the operation of the universe.

  The heat created by the fusion processes within the stars or the principal stars is the by-product and in fact the heat assist with the operation to loosen the Magravs and loosening the Coulomb's barrier that fusion or mixing of different plasmas of mafs and matters are accommodated, but not the cause or the outcome of the fusion.

  Where in the world of the fusion of today scientists try to speed up and accelerate plasma and make them to collide and hope for the fusion, but in the universe the reverse process happens, whereas in the universe fusion takes place in condense centre of the principal stars and matter stars, where there are no rooms for the plasmas to speed-up, but due to loosening of the pmf forces magnetosphere of the plasma or coulomb barrier, then matter mix and fuse and what is not necessary from the amalgamation of two plasmas fusion, then these appears and are released as surplus unwinding pmfs of mafs which as in this process of higher to lower mafs strength is so rapid that this process shows itself as the heat in these environment of the universe as part of the process.

  Thus heat can be explained in its real term as the pmf which is unwinding from one state of matter to unwind that the pmf field released allows the other matters to open their magnetosphere that they can receive the pmf in transit from other plasma.

  Then the cold can be explained as the when the pmf of the matters are reduced to beyond the magnetosphere of the matter that matter cannot transmit any pmf to another matter.

  At the point, where the total transfer is zero, this is known as the Absolute zero point at the present time. Where, the scientists say that at this point there are no molecular movement. In fact the plasma of the matters or ***the atoms is still at this point active*** and maintains their internal dynamic condition and environment. If this was not so then magnetic fields creating the mafs and matters would have ceased to interact and the matter or mafs would have lost their gravitational fields and magnetic field and hence the matter and mafs would not have been able to maintain the magnetosphere and the mass of the atom, and hence nothing would have existed; But as one still sees the matter at absolute temperatures, then the condition is inter plasma magnetosphere connection and not internal magnetic connection;

In fact magnetic fields, which are the principal particles or are known as the fundamental matters can never come to a point that they do not exist or interact with other fields and at the same time due to ever existence of other magnetic fields and fundamental elements in the universe, then all fields and matters at all times are attracted or repelled by one matter or other and hence a total non-dynamic universe never can exist and in truth the creation of the universe and creation and origin of the magnetic fields is due to and through the fundamental of difference in the universes differential waves. Thus the magnetic fields are themselves created out of strength level difference in the universe and thus the origin of the magnetic fields is the cause of the existence of the universe and the existence the universe is the cause of the existence of the condition differential which is the creation of fields to compensate for this difference and hence the creation of entity to cover the difference in position and hence the creation of the magnetic fields. Thus one in a simple language now knows even how magnetic fields, which their variation leads to the world of the creation of universe has come from and how the real essence of all creation become to exist.

- It can be said that at the Absolute temperature the time stops for the matter and material world but not for the mafs and mafs dimension and hence if the universe were made only of matter and mafs then the physical matter would have never existed in the deepest part of the universe if the temperature were at absolute temperature.

- The measure of the cold in the universe is dependent upon the slowing down of the movement of given pmf in a given direction and strength, hence the measure of the coolness is the external strength dependent and not plasma internal fields motion dependent. This being the reason why like in the planetary systems planets can and do produce their own independent temperatures irrespective of where in the universe they are and how cold or warm the environment of their surrounding planets and stars could be. Therefore *THE ABSOLUTE ZERO IN RESPECT TO* mafs and matter environment is only applicable to the earth position and environment and not to all universal condition. This being the reason why, one can see and observe life in all kinds of pressure and magnetic field strength in the universe.

  Therefore the Absolute zero for mafs and matter environment is not applicable true for principal, transition and matter mafs and matter strength and environment.

  This being the reason why that internal atomic structures can exist and atoms mafs can hold on to its structure and its existence, while the molecular structure in the matter environment can be cold that no external motion within the atoms of the molecule can be observed at absolute temperature.

  The absolute temperature in a given environment can be said to be when the Magravs of the constituent matters environment come to be in total balance; and that is the point that the total losses and gains from the surrounding environments are said to be balance out that the total magnetosphere of the environment will compensate for the losses that the environment can keep on holding on to the zero motion of the total environmental Magravs.

  On other hand the environmental Magravs can be reduced that there is no interaction between atoms that the motion of the atoms in respect to each other ceased to exist and motion in respect to each other become frozen. This is known as balance Magravs criterion and to produce this within the structure of reactor is an art not known to man. Where, the balance Magravs positioning is the key to establishment of colonies in the universe, where there are no planets and stars as point of reference, but the condition of balance allows the station to be permanently positioned in that spot that all passengers of space can come to meet.

Production of an absolute balance give man the ability of what is known as hovering, where there are no propellers and no vertical jets of today to stay stationary in mid-air.

Absolute Magravs balance allows crafts of the future to keep a constant position and this can create fantastic composition for gate-thing, which is needed for movement from one Magravs system environment to another without actually needing to handle re-entry problem in either direction.

The operation and the use of the absolute balance Magravs technology systems are as for the physical doors of today, when used in the future, when one moves from Magravs plasma environment to another.

- In the operation of the universe, the distance of pmfs and the speed of the rotation of one pmf in respect to another is the criterion by which the speed and directional rotation of one matter or plasma in respect to another plasma is dictated.

  Where, the positioning of mafs in respect to each other in the universe has a direct effect on how fast, when and where an entity will position itself and even this dictates the measure of the cold or heat of two entities in respect to each other and to other environments. This concept is seen in the universe in respect to the rotational direction of planets, stars and galaxies, where their direction of the rotation if different to the one other entities in their surroundings.

  The criterion of mafs positioning is the reason, why for example the Vinous rotates in different direction than the rest of planetary systems in the solar system of the man, as its internal pmfs speed of rotation and their position in respect to others of the same within the internal structure of this planet are as such that the outer layers of this planet are forced by the configuration of the combination positioning of different cores and their pmf strength, forcing the planet to rotate in the clockwise direction rather than the anticlockwise direction as the rest of the planetary entities in this solar system.

  This principal of the mafs positioning and speed in way can explain even why all matters in the universe rotate anti-clockwise or what is commonly called the electro negativity of the hydrogen atom directional motion.

  Hence it can be said that the anti-clockwise directional movement of the plasma of proton and electron are due to the mafs strength within their plasma and the position of different mafs in respect to each other within the plasma.

  Then this puts a closure to present theory of electron and positrons, where in fact electrons and positrons only difference is that one's internal magnetic fields are slightly differently positioned than the other and as their mafs contents of fields is the same, then only the positioning of the fields in respect to each other dictates the direction of the rotation of the plasma of these entities. This directional motion variation can even affect the absolute temperature of the operation for the positrons and electron in different environments too.

- Time as man is accustomed to on earth, this time in the universal language does not exist; time is a manmade phenomenon to measure the course of his life. In reality the time is the measure of the pmf of given strength to pass a given predetermined strength, thus time in the universal language is magnetic field strength and environment dependent. Where in the principal mafs world the time of reduction is much faster than the time of reduction in the same matter environment. Thus time or measure of reaching from one level of strength to higher or lower by the same order of magnitude is the measure of the time in the universe.

Where, the universal positioning time will be measured according to the central position of the universe and considered to be zero at this point and then to make an appointment to be at a given time then the motion of all mafs and matters in the universe in respect to this point needs to be considered, Where this position is and has a three dimensional three hundred and sixty degree reference. Where, in fact time in the universe needs point of reference and that is earthly time, solar time, galaxial time and universal time.

Time is unchangeable and it is the same in the same gravitational and Magnetic field strength environment. This is important, as at the present there is a fallacy, which has been accepted to convince the scientific world that time goes faster in the universe as one moves away from the earth.

This is nothing but hypocrisy and lack of the understanding of how gravitational fields are created. This fallacy has come to a point that in the satellite systems of today an error time has been allocated that the satellite timing is adjusted in respect to position location of a matter or entity on earth. Where in fact if the scientific world would understood the full principles of the creation of matters, and if scientists can create the same g strength forces in the environment of the operation of the electric and mechanical processing of these satellite does not matter where they are positioned, what is called the environment of what is called one g, then these satellites do not need correction factor which they are using.

Where, in fact the time correction factor is due to the fact that matters in the different Margraves and gravitational position around the earth have and operate under different magnetic and gravitational field strength and this is the reason why there is a difference.
Thus for the correction of time in these systems only one needs to consider creating the same Magravs strength at on the surface of the earth and then there will be no difference in time.

This concept is important for the future travels of the man into space and his excursions in the universe if he wants to keep to his habitual twenty four hour clock and earth gravitational magnetic field strength of his planet.

Man soon will find and realise a simpler way and then the hypocrisy of time travel and wormhole and going to the past and to the futures and so-called granddad theory will come to an end.

One point to remember that light which itself is plasma entity moves out in a spherical three hundred and sixty degree environment of the universe and for example the feature of a the face of the man will create man lights for it to be seen as a whole, but in time as light travels in the ever rotating sphere of the universe and these rays some get absorbed and some get distorted, then one cannot bring all the lights of all the matters of the one human face together to see that entity as it was so many time lapses before.

Thus if one hopes think that one can see the past of one person on a revolving dynamic environment through one light or making a machine to go backward to see the face of its forefathers, this shows nothing but the lack of the understanding of the science of creation and motion of light through the haze of dynamic universe by these men of science.

One can see the structure of matters like stars and fields in the far points of the universe primarily due to the fact that the light is and has plasmatic environment and like a telescope can pass the information to the point of arrival. But the light cannot bring the past of its source, but shows the pattern of its source like a move at the time it left the object.

In fact it can be said that light is composite matter and entity with active complex pmf of different mafs.

Thus, for example one as one enters the principal matter environment, where the principal matters is the creator and controller of Magravs of the environment, then in these environments one travels at the speed of the pmf of the principal matter and not pmf of tangible matter. Then if considering the principal matter environment in the centre of galaxies, then time for the matter world will be looking as being much faster or matter seems to be travelling thousands of times faster than what has become to be as the speed of light in the matter world in these environments.

Thus in reality the accepted time and speed of light as the maximum limit is only applicable for and to human understanding of the universe and not considered to be the truth in the real working of the universe.

When, the race of the man understands the concept of the use of the principal matter in the travel systems of their creation, then the man will be able to travel into the universe with much faster speeds than the speed of light of the mafs in the matter world and then one can travel the spans of the universe in seconds in human term and then one can travel the length and the breadth of the greater universe as one travels the earth glob with the toy systems of the jetliners of today.

Then the point arises that why some mattes and entities in the universe can last for a long time, where for example the human life is limited, the answer to this is very simple, and that is the body of the man is made of composites of mafs and matters and the more one adds to the composite the more Magravs are available to be lost to the surrounding Magravs, and be effected by the surrounding Magravs too.

Thus the life of the man is environment conditioned and in time as the DNA of the man learns to preserve more, then this will be adding to the life of the man and then the man will live longer, but eternal life is and belongs to no one entity in the universe, but the entity is the total facet and attribute of the whole as a whole. Thus man has been and shall ever be, not in the physical form but rather in the attributes of its physical existence in all universes of the god. Where, god is part of whole and fraction of none.

Where, the universe possess mafs and matters which their difference only is in their strength and nothing more and nothing less, thus time is faster in the stronger field for the weaker matter created entities and time is slower for the stronger mafs field strength in slower in weaker matter field strength. Thus time in the universe in reality does not exist and is a creation man’s state of position and possession. Thus if one is in universe, where the strength of the mafs are one thousands time stronger than the other mafs, then the time is one thousands time faster and this applies to all mafs and matters in the world of creation.

One point to realise is that the magnetic rays which are released and are prevalent in the environment of the man are the time setters for the degeneration and division of the man’s cells and have direct effect on the life span of the man in the universe, this be it a word of wisdom for the ones who come to comprehend and look for the eternal time life.

- What holds the universe together are the attraction and repulsion force of the pmf content of the universe. Thus the tightness of and the position that matters appear in the universe are totally pmf strength dependent.

  Therefore as the pmf strength of the matters are attained at any point in the universe then that matter becomes to manifest itself in the given point and time in that part of the universe. Thus the glue of the universe is a combination of the interaction of all the mafs and matters, which their interaction makes the Magnetic and gravitational fields Magravs of the universe.

Thus in fact what is called the bosons theory has its truth in the position of and their interaction of the magnetic fields of different pmfs, plasmas, matters in a given position in the universe as these interaction dictates what and how pmf are given or taken from the universal soup of magnetic fields, and what the outcome entity shall be and how the matter manifest itself at given point and for what period of the time.

- Thus once a given pmf strength in the universe is achieved which can be initiated combination of the interactions of several conditions, plasmas, and environmental magnetic fields, then at that point in the universe a specific given mafs or matters comes to exist, this being mafs or tangible matter magnetic fields strength and so forth. This is the secrete of universal existence and manifestation of the all mafs and matters and the observation of one mafs or another matter is totally dependent on the observers pmf Magravs strength that one matter or another can be tangible or visible.

- As in the solid state magnets in the plasma state of the magnetic fields regions of the universe, these plasma poses and operate through the North and the South poles and the same goes with their attraction and interactions in respect to other magnetic fields of all plasmas too, that is to say that plasmatic magnetic fields position themselves as solid magnets do in respect to strength and position of other plasmatic magnetic fields near to and in their environment. Thus the North-pole of the plasma attracts the south-pole of other plasmas and at the same time the South-poles of the plasma keep and make distance from the South-poles of other plasmas as it happens in the solid state magnets.

In the physical matter one can see the motion of the magnetic fields and motion of magnets in respect to each other as magnets move and find their position in respect to each other in their given environment once they are brought into the proximity of each other. The same positioning and movements are applicable and are created and maintained in the magnetic environment of the plasma two plasmas once they are brought within the mafs field interaction of each other too.

The plasmatic magnetic fields of all entities can recombine to allow the circulation of their fields and in general determine the point at which the fields can re-enter the plasmatic magnetic fields to complete a full spherical plasma of the fields. Where, this point of re-entry of the fields is primarily dictated and decided according to the environment, which the mafs of the entity operates in and, not necessarily by the mafs strength of the field of the entity itself. Thus, the point of termination and re-entry of the fields of the plasma of mafs of even solid matters is dictated by the environmental mafs strength and not by the matter. That is to say the termination point for the magnetic field lines for a plasma and solid matters (the beginning and end of a field line) is decides mainly by the environmental mafs strength and not necessarily the strength of the fields of the matter.

This being the reason why the magnetic fields can reconnect anywhere in the universe irrespective of their physical distance, as the environment which the fields enter and carried to their full destination is supported and facilitated through the mafs of the environment and not the strength of the fields of the entity. Where, this phenomenon is well explained in the interaction of the change of polarity of two atoms, which as one changes its polarity, the second one does the same instantaneously. This is what one observes in the change of polarity of plasmatic field's entities, that for example as one plasma changes polarity, the other does the same parallel changes automatically that one never observes any changes in the structures of either entity.

This being like the change of the polarity of the earth and the synchronized change of the polarities of the cells of all beings on earth, that no physical change can be detected by the inhabitancies of the planet as the physical polarity of the earth changes.

Even though the same cannot be said about the change of the polarity of the moon of the earth as it does not changes as the earth polarity changes in majority of the cases.

In understanding the principle of this phenomenon, then man of science can make any matter anywhere in the universe as the need of the time be, this be it production gold or production of amino-acid needed for production of proteins of chain of fibres of heart of man anywhere in the space for the travellers of the future.

Thus, one can control the point where what appears as the magnetic fields can draw in fields (as called conventionally called the exit pole) and where the field exits to release the fields (the north-pole of the mafs. Then size and the length of the magnetic field and the gravitational fields and Magnetic fields, which any entity creates, can be controlled and hence the size of plasma of an electron or proton can be predetermined. That is to say the total field strength of the Magnetic field and the magnetosphere which an entity creates and can hold on to, this determines the exact and precise dimension of the plasma of be it this be the plasma of the proton and electron.

Thus, in principle one can have field zone of the same length, which upon their interaction they create a given magnetosphere, but one can have the same spherical dimension of magnetosphere with a different magnetic fields strength, which this creates different Magravs field zone. Thus, the length of the magnetic fields determines in what entity is to be created, this being the plasma of proton or an electron, and so forth.

Complex magnetic fields create different field lines, hence different Magravs. This being the reason why in the plasma of the proton different pmf and matters entities are observed and detected.

- In the bigger picture of universal works, scientists will come soon to realise that all parameters are the same, all plasmas do and behave within a given procedure and sequence. Thus, what one sees in the plasma of this universe is the same as what goes on in the plasma of the proton and electron too. That is to say what has been puzzling the theoretical physicists about the content of the plasma of the proton, as one can see in the operation of the universe then one should have been expecting the existence of different matters, fields and fields strength in the plasma of the proton and even the same in the plasma of the electron as one sees in the plasma of the universe.

- Interesting enough scientists soon will start wondering about the creation and control of these magnetic fields that how they lead to creation of different plasmas of magnetic fields too, and how plasma of the magnetic fields become to become units of the same fields and how a magnetic fields can be attracting one plasma while the same end of the matter can repel another of the same from the same end or exit port of the magnetic fields. That is to say how can a solid magnet at the same time as can attract the opposite polarity and then at the same time and simultaneously the same pole can attract another dissimilar polarity. The fact is that magnetic fields of plasma of fields do not bunch all to north and south or all exit and entry port, but they arrange themselves as one of entry and one of exist and or one north pole and on the south pole adjacent to each other, but they do not set end to end with each other. Thus for example looking at the section cut across cluster of the magnets, the fields are arranged like mosaic of north and south in correct sequence and order. Where, in the case of the dynamic plasmas like protons the top view shape of the magnetic fields are the likes of a whirlpool and not straight-line fields of the same mosaic.

  Then one should understand how the structure of nucleus of atoms are arranged in a similar manner too, as one exit port sets next to an entry port, then when a nucleuses has two protons then the in and out ports are matching and the magnetic fields of the atoms internal magnetosphere is complete and the atom is stable, but when the atom possess two of the same ports and one of the other ports in its nucleus then the extra port is sharing its fields and or is looking for the an extra port that can receive its pmf or it receives pmf from, and hence the odd number protons nucleuses always are more receptive in receiving or dividing for them to have matching pairs pmf ports of entry and exit, that they can make their own matching magnetic plasma. In fact single magnetic fields do not exists in the world of plasma, and in a way the theory string shows nothing but lack of understanding of operation of the fields in the universe. This explains why odd number proton numbers go through decay or they are more receptive to make polymers of themselves or join up to make molecules.

Where, the entry port of the fields can take magnetic fields from the other ports or from the soup of the Magnetic fields of its environment, and thus the size of the entry port of the fields in principle determine the matter and mafs condition in a given environment.

The reality is that the entry point consumes more energy than the fields, which are coming out of the exit port of the plasma of the fields. The fact is that whenever fields interact they create minute contact points that at these contact points fields are divided into smaller length and strength, this is like when two bodies collide and due to their friction some heat or fragments are created; This happens the same when two magnetic fields interact to create their own magnetosphere and mass. Then due to this friction between fields the magnetic fields entry of south-pole are slightly weaker and less in mass than the total mass which originally entered the magnetosphere of the two fields in the south-pole. Where, in fact the slight difference in the mass and fields strength between the entry and exist of the ports, leads to ever reconnection and closing of the loop of the fields between the North–pole and the South-pole, and the motion of the fields within the structure of the matter and the entity.

Where, the South-pole or entry port is the feeder and the North-pole or exit point is the provider, where at the same time the due to miniature and micro size of the magnetosphere of the fields, there are too many magnetospheres which are connected and arranged in the mosaic of the one cross section, thus the entries and the exists or the north and south poles set next to each other and where the entries poles are more stronger the matter attracts and where two facing section the south pole are stronger the matter repel and hence the sequence of pulling and attraction of mafs and matters in the universe.

Where, the entry points both need to attract as much as possible so they move to guaranty their own continues supply of fields and this being the reason why similar poles move away from each other, that is simply to allow the entry or exit of the same floor of the fields to have the maximum chance of attracting fields to guaranty their field supply.

The dissimilar poles gravitate, as the entry-pole try's to absorb all that it needs from the supply of exit-pole of the other entity.

Further on the minute fields which are released from the interaction of the two fields, in them separating and being able to travel a given distance away from the original two fields and their interaction, these fragments travelling distance capabilities determine the magnetosphere region of the two interacting magnetic fields too.

The interaction of fields in creating plasma of fields needs a constant supply of fields from its environment, and that is why the fields can and do regurgitate some of the fields which was released by their own interactions and this being the reason why the Plasma of magnetic fields can last for a long time in the given environment.

In a way the attraction or the gravitational fields forces is created out of the necessity of the need for the two interacting fields to keep locked to each other, and hence the need for a constant sources of supply of magnetic fields in the universe, which this need is meet in large from a stronger source of fields and their unwinding of the principal mafs sources which are scattered around the universe. Where for example the larger plasma's the likes of the stars needs are meet by the cosmoses principal fields as they unwind and in the micro levels the need of weaker fields magnetic fields of atoms are meet by their lower level strength fields of their environment.

Where, at the same time the magnetic fields can enter a centrifugal region where their strength can be tightened and thus fields as much as they can lose their strength through unwinding, and then through the same process of rewinding they can increase their strength too. That is to say that if the mafs fields are entered into a winding region or in a tighter pact region fields strength of the universe, their magnetic fields can be winded up that the mafs strength increases to principal mafs field strength. Or what is said in the common language of present science the mafs can become of principal mafs strength and the centre of the tightening mafs is the principal centre of what is called at the present science the principal region of the environment, this being in the centres of the cell, galaxies or universes.

Thus as long as the environment can supply surplus amount of the pmf for a given system for its north and south poles to be maintained, then there will always be an entity existing, does not matter what word in the vocabulary is used to confirm its existence.

The mass is created when the field at the entry port and the exit port are linked and it is independent of any other entities of the same or there scale of mafs entities in the environment. Where, the mass is the amount of the fields needed from the environment for the interaction between two fields or plasma of its fields to exist.

- The magnetosphere is the limit of the field's exertion in a given environment created by the interaction of the gravitational and Magnetic fields of the two original fields. Where the magnetic fields are the cause and the gravitational and Magnetic fields are effects their interaction and the Magnetic fields interaction now becomes the cause of the creation of the mass and magnetosphere of the entity as the latter become the effect of the interaction of gravity and the Magnetic fields.

This being the reason why, that the mass is independent of the environmental conditions and effects, as the mass is the indication of the given internal interactions itself and is due to internal processes of interaction of the same internal magnetic fields. Thus when the environmental magnetic fields, gravitational and Magnetic fields are considered and applied to the given mass system, then the weight or the measure of the mass in respect to the environmental fields forces can be measured.

As the puzzle of creation of gravity is solved, this should open new horizon in the world of science and make life easier for scientists to understand the working of the universe. Where the whole world of creation can be said to start from the difference in condition in position, where this leads to creation of field that the different position can interact and be connected to each other, This known to be the origin of creation and origin of the creation of magnetic fields in the universe.

Where, this movement of and need for interaction of fields to cross the space of their environment leads to creation of what is come to be known as magnetic fields flow, and the extent of the flow to cover the strength difference and the proximity to each other trying to cross the gap to guaranty continuity of flow of fields in the environment become the current or the strength of the magnetic fields.

Where, the interaction of magnetic fields leads to creation of Magnetic (repulsion) or gravity (attraction), where the interaction of the created Magnetic fields and gravitational fields leads to creation of mass and Magnetosphere (1) for the magnetic fields concerned. Where the interaction of magnetic fields depending upon their strength leads to creation of stronger fields to be connected to each other, thus the stronger fields become the principal fields or feeders of mafs and the weaker fields become the matter mafs fields of the universe.

In the man's range of Magravs strength of his protein, the weaker mafs become tangible and visible or detectible and part of his own being's structure and his matter world is created and where in other levels due to stronger fields the principal mafs create a visible world for the one's whom their protein Magravs strength is set to a level beyond the man's mafs strength level.

Thus, the universe is the collection of and the creator of magnetic fields in different length and strength and their interactions to create different magnetosphere in size and strength in Magravs, and whenever and wherever there are fields to interact then they coagulate and linkup and create mafs and matters of different strength.

In the universe there are no empty places, which are void of magnetic, Magnetic and gravitational, mass and magnetosphere fields or not being in the path of the movement of fields. In general what is tangible and visible magnetic fields collection has been and it can be called matter and what is fields in the motion which are not yet attached to any matter to become part of given environment of matters or mafs are called energies of the universe.

The universe will never cease to exist as long as there are fields to attract and repel each other. Universe has no dark and black unknown phenomenon about it, it has principles and how they are applied and enforce themselves or it is enforced upon them, then a given condition and fields and mafs are created for given span of duration of fields interaction so called time.

The earth is not the unique environment which can provide and sustain life and intelligence, but life starts from fields and their interactions and upon their complex interactions and order they choose to be a club of plasmas, matter mafs, atoms, molecules, Magravsly to be bind (chemically), combination orderly repetitively Magravsly bind (biological) and creating communication in the biological Magravs repetitive order to guaranty the survival of their overall Magravs which these interactions lead to creation of intelligence.

Thus the man is not the only being with intelligence in the universe, as given the environment of interaction of fields entanglement is the facets of progression interaction of the fields which can be sustained everywhere in the unicos.

What is interesting is that one does not need the intelligence to have the soul, the same as one does not need to see the star in the far corners of the universe to know of its existence, but the plasmatic magnetic fields which it released during its existence it has travelled and nourished the universe to reach the position of the observes. This is the same for the soul of the man and the manner of it's creation and movement in all dimensions of existence, wise one now can understand the mystery of nothingness and of the creation of the soul of the man and the essence of its meagre existence in the world of universes.

The survival of the soul of the created being is the beauty of it, for it to give and to receive and not to be an outcast, then man of wisdom will enlighten the man of possession that there is nothing to possess if one uses what one needs and no more. Be wise on what has been said and open to be received and receive what is in your path of life in its different levels of interaction and attractions.

The ultimate point of understanding for the man who is one of the created entities in the universe and through what has been revealed on to man in the verities of disclosures in the recent past is that in the universe among its created whom have attained intelligence and have managed to take into spaces of transition environment of universes, that in the universe there are no animosities and no wars and nor this rule shall be changed as war and acts of aggression has been the habit of the passengers of the planet earth during their technological progress and their short lives on this planet.

The reason for the universal peace is not the lack of technology among its inhabitancies, but the truth is that the intelligence of the beings of the universe is so advanced that they have no reason to fight for what they can attain in and achieve and obtain from the universe.

Thus the universe is ruled by peace and justice and the ones whom have the habit of the like of the blue blood from the blue planet will be thought soon a lesson that unless unity takes over the thoughts of the creatures of this planet, then these shall be thought a lesson that they will soon fall and follow the rules of the universe and not the old habits of the feeble man.

Not forgetting that the everlasting habitant of the universe have attained the knowledge that can wipe-out any type of life from the universe, thus the peace in the universal order is not due to the weakness of its inhabitants, but their strength to be able to see any short sightedness from the newly joined members of the universal community that they cannot and shall not be allowed or even think they can carry on with their old habits of war and division and injustice and exploitation of the other habitants of the universe as they has become accustom to on the blue planet.

The laws of the universe shall be in the hand of the land of the lion as they have been graceful and has been just and as has been promised, the knowledge of universe shall come from the land of the lion and the Sun where it will shine upon the rest of humanity in equal measure and with true powers of grace and justice. This has been the command of the created and shall be attained.

CHAPTER 9

The creation of Gravity

© M.T. Keshe/The Keshe Foundation 2004/2006. All rights reserved.
Author: Ing. Mehran Tavakoli Keshe
Date of Internet release: October 8, 2006
Revised 1.9.2011

Abstract

The universe is built and held together and operates on the basis of two forces. One cannot work and exist without the other and when one of these two forces dominates the affects can be interesting, drastic or/and at times dramatic for the entity, this be it the universe, solar system, planet, atom or plasma. These two universal principal dynamically plasmaticaly magnetic field forces one being the Gravitational fields forces (attraction field forces of the entity) and the other the Magnetic fields forces (the repulsion or magnetosphere fields forces of the entity), which both have their origin within its centre these operating entities.

Hypothesis

The source of creation and sustainer of the gravitational field force and the Magnetic field forces of for example planets are the same elements and the same conditions in the centre of the planet.

Prototypes

To prove this concept, several static and dynamic prototypes over span of five years have been made and tested (Fig. 23), which the outcome of these tests shown system on the bases of this concept can be made that the system creates both gravitational and Magnetic fields forces, which in the operation of the system allows the system to reduce its weight first and then the system separates from its ground base and hovers within its environment. This proving that the concept of production of dual Magnetic and gravitational fields through the same elements and conditions to be correct, and the results and observation from these tests are summarized in general in this and other papers to be published.



Fig. 23. Some of the prototypes used for creation of Magravs.

Discussions

In this paper for ease of understanding the structure of planet earth is considered as vast amount of information about the inner-structure of this planet are available. In fact this principle of creation of gravity through interacting magnetic fields can be scaled up to structure of universe or scaled down to structure of the plasma of proton and electron and the principle will still applies and be correct.

If scientists would have discovered both magnetic field forces and the gravitational field forces of the planet at the same time, they would have probably had a totally different understanding of their principles, their capabilities and their connections and most probably the human race would have taken a different course in its intellectual and scientific world. It seems this miscomprehension has been purely due to the physical time gap between the discovery and understanding of these two forces of creation.

Working on a real basis for gravitational field's forces production at the centre of the planet, the author set out in early 1980's to design and has produce several real and practical reactors (Fig. 23), which these reactors could replicate the universal order for generating magnetism and finally their interaction lead to the creation of Magnetic and gravitational field forces within the same system to prove the correctness of the principle of above hypothesis.

A fundamental assumption to achieve the proof of the creation and control of a gravitational force within a system has been that the Earth in its inner part has and maintains a semi-fusion and fission nuclear chain of reactions, also called a geo-nuclear reactor.

The interaction between materials and magnetic fields of semi-fusion and fission chain of events in the Caroline core (Fig. 24) of the planet (*This being the core within the inner-inner-core of the Earth, "The seed of the Earth"* (12)) always leads to creation and maintenance of planets physical forces of Magnetic field (MF) and gravitational fields (GF).



Fig. 24. The structure of inner cores of the Earth (12).

This semi-fusion and fission sequences of processes and existence of plasmas, nano-materials, gases and other materials in the containment of Caroline's' core and the convection process due to the heat transferred from the Caroline core to the Outer core of the planet once being passed through to the inner-core has been considered to be the principle operation of the inner cores of the planet, where, due to dynamic characteristic of the materials, which are charged and rotating within in vacuum condition of inside of the Caroline core, leads to independent creation of current and plasmatic magnetic field within this core, irrespective of the already assumed second and already known magnetic field, created between rotation of the inner-core and the outer-core of the planet.

These two independent dynamic plasmatic magnetic fields which are separated by means of the physical barrier made by the existence of the known solid inner-core.

The interaction of these two dissimilar poles if the these two dynamic plasmatic magnetic fields due to their proximity within the centre of the planet leads to the creation of the central gravitation field force of the planet, which this force spreads out to cover the whole of the structure of the planet.

Hence it is clear that the source of the Gravitational field force of the Earth and all planets are due to the interaction of two dynamic plasmatic magnetic energy fields, which are created independently in the centre of the planets.

The Caroline core of the Earth creates its own spherical dynamic plasmatic magnetic energy field, and the already known second field, comes from the dynamic spherical plasmatic magnetic field, which is created in the outer-core of the planet at the same time.

In trying to lock onto each other, these fields forces create the condition of double spherical magnetic fields, which both possess their own North-pole and the South-pole, where due to dynamic and loose atomic, molecular structure of the matters and fields in these two cores, the dissimilar poles of the two cores can never quite reach the point of total locking into each other, and as they try to reach this point of full lock, the field forces they create lead to creation and maintenance of the perpetual motion of the two fields in the centre of the planet.

These separated dynamic fields forces on either side of the solid-inner core exert their forces on the solid inner-core of the planet and cause it to rotate, and this leading to creation of the rotational movement of the planet (12)

At this point the interaction of the fields created by atoms and molecular elements, which cannot lock to each other due to their similarity of magnetic poles, will create the outward plasmatic magnetic field between the two cores, or they create what is known as the Magnetic field force of the planet (this being created by the environment and the behaviour of two similar poles of a solid magnet which they repel each other).

.

Where, at the same time the interaction of the magnetic fields created by atoms and molecular elements which cannot lock into each other due to their dissimilarity of magnetic poles, these interaction of the magnetic fields will create the pulling power effect between the fields, atoms and molecules contents of the two cores and this creates the dynamic attraction plasmatic magnetic fields of the planet or what is called the gravitational (Pulling) field force of the planet

Thus; Gravity or gravitational field force does not and cannot exist with existence of only one plasmatic magnetic field force as has been assumed to be so up to now in respect to the creation of the magnetic fields of the planet.

The gravity and gravitational field forces manifest themselves upon the creation and existence and maintenance of the second dynamic plasmatic magnetic field within the structure of any dynamic plasmatic field entity, that in the case of the earth fluid matter in the outer-core is source of this second field and may be generated through the assumed convection theory by the convection of the matter in the outer-core, and the interaction of fields in this core with the plasmatic magnetic field which was originally created in the Caroline core of the planet through the fluidity of the fields, plasmas and matters in this core.

Therefore the gravity is an outcome of the interaction at plasmatic, atomic or molecular levels between two dynamic plasmatic magnetic fields created and maintained by the two inner-cores of the planet upon each other.

Ultimately for creation and maintenance of gravitational field force, for all stars and planets or any dynamic maintain plasmatic magnetic fields system, and to maintain a gravitational fields forces in any celestial entity there is a need for existence and establishment of two independent dynamically, molecularly or/and combination of the two independent plasmatic magnetic fields forces, which these can be created by any mixture of matters and fields, in any combination of magnetic fields, liquid, gas, plasma or other state of matters within the confined of specific condition and entity, this leading to generation of loosely interlocking plasmatic magnetic fields, which these two fields are separated and maintained by any physical supranational means, in any state of matter or function, separately and independent from each other, even though one magnetic field could be the cause of the creation and maintenance of the second pmf.

Where, the separation of the plasmatic magnetic fields could be established by the means of solid, liquid and gases, plasma and energy directly in adjacent layers to each other as has been observed to be in the structure of the inner-core of the Sun material layers.

Once the strength of the plasmatic magnetic fields of the inner-inner-core (Caroline) and the outer-core in a system, by controlling the creation of the plasmatic magnetic fields in the Caroline core or the outer-core is attained by the system, consequently the strength of the gravitational field forces of the system like the earth is set.

Looking at overall view of the centre of the Earth magnetic fields and it their near spherical shapes structure and with the new understanding of its' physical inner construction and material composition, one will come to understand that at least the two magnetic fields generated within the inner cores structure of the Earth are spherical in shape and they generate dynamic spherical plasmatic magnetic fields. Where, one field being superimposed on top the other are in operation within the centre of the planet.

Whereas, one of the fields being the spherical magnetic fields maintained by the inner-inner-core due to existence of plasmas, hydrogen atoms, other gases, nano, gans, nuclear and non-nuclear materials in presences of second magnetic field generated by spherically dynamic plasmatic magnetic the outer-core in the centre of the Earth (Fig. 25).

Which, this creates and brings about the phenomenon of the dynamic magnetic confinement for the materials in the Caroline core, which this brings about the conditions for the fusion process to be attained in this core of the earth. This explaining why the planet can exist for a long time with its matters and motion intact, as matters through fission and fusion use a very little matter in the close capsule environment of the Caroline core.

The second spherical dynamic plasmatic magnetic field in the outer core of the earth possibly is created through convection, due to its materials in motion in the outer core.

There are strong indications and possibilities that the outer core could be operating in the same matter mixture composition as the Caroline core, which this eliminate and invalidates the concept of the convection theory.



Fig. 25. Existence of minimum two separate magnetic fields in two cores of Earth.

It has to be said and it can be proven that the Caroline core maintains and through nuclear decay of its matter content produces plasma of matters, then by the understanding of the concept of generation of current through motion of the plasma itself, this proves that one does not need the convection principle to create the current and magnetic fields in the Caroline core or even in the outer core of the planet.

Therefore the existence convection theory and motion of the solid inner-core to create the magnetic fields of the earth losses its credibility, as in plasma technology, it is well understood that plasma in motions create their own current and in turn the interaction of this current with matters and other fields in their environment this can lead to they creation their own magnetic fields.

Thus, the theory of convection has to large extent no validity in the present understanding of nuclear science as one observes these operations of plasmas' phenomenon at the solar, galaxial and universal systems levels.

The convection theory was he understanding of the eighteenth century and the understanding of the working of dynamo of bicycles and this has no room in the integral working of the universal motion of plasma and magnetic fields of today.

Secondly entities like stars do not have solid core that leads to creation of their strong magnetic fields and gravitational field, as they only operate on the principle of plasma layers and some helium matter in, nano, atomic and molecular level.

Therefore in reality the physical positioning of the matter in the cavity of the once presumed solid sphere of the inner-core is the catalyst and contributor and the creation of both plasmatic magnetic fields of the planet, which both fields are independent of each other, but at the same time interconnecting or magnetically reconnecting tool for both spherically plasmatic magnetic fields on either side of the solid inner core of the earth to produce the Magnetic field and gravitational field of the Earth.

Where the interaction between these two dynamic plasmatic magnetic fields in the physical body of the inner-core of the earth leads to creation of the double spherical plasmatic magnetic fields' phenomenon needed for creation and control of the strength of the plastically magnetically based gravitational field forces and plasmatic Magnetic field forces necessary for the creation of the mass of and the atmosphere or magnetosphere around the planet.

These reconnections' of plasmatic magnetic field generated in two cores of the planet are totally on atomic and molecular levels, this leading to a creation of loose plasmatic magnetic field forces that operate at weak levels, but strong enough to cover a vast area in their surroundings.

That is why a small Caroline core in the centre of the Earth can create a strong magnetic fields effect of up to outer boundary of the magnetosphere and gravitational field of the Earth and beyond.

As the plasmatic magnetic fields could be created by use of any elements in both cores of the planets that they can generate any amount of heat and a given gravitational fields forces and for example with the Earth operating at central temperatures of several thousands of degrees centigrade at its core with surface gravitational force of one g at its surface, and similarly the Sun physically possessing several of thousands of times larger mass and volume than the Earth with central temperatures of several millions of degrees centigrade, which has only the surface gravitational force of about twenty eight times more than the Earth, therefore the following statement can be made that "*the strength of gravitational field force of any system is largely independent of temperature, and is primarily dependent on, the composition of its dynamic inner structure mafs and matters, and the fields they created or maintained and the physical condition and are positioned in respect to each other, which through their interactions these leads to creation of the two dynamic plasmatic magnetic fields strength of the gravitational fields and magnetic fields of the system within its inner sanctum*",

In relation to the physical data's available, the present gravitational field system which has been assumed to be created by the single magnetic system due to motion of matter and the inner-cores and the outer-core in the centre of the planet is not scientifically acceptable and cannot stand the present physical knowledge about the inner construction of the planet from seismological data's of the past twenty five years.

The concept of single plasmatic magnetic field of the planet, which has up to now been assumed does not stand scrutiny of present knowledge and the present expanded laws of physics, as for the planet to be able to create gravity and Magnetism (for magnetosphere) that can span a vast area of the solar system irrespective of its position and the material carried in its outer shells and on its surface, then the planet has to have two active plasmatic magnetic field forces in its centre cores, that the interaction between these two plasmatic magnetic fields can create the fields that affect the behaviour other entities' with dynamic plasmatic fields elements in the vicinity of these fields, and the interaction of the fields of the planet and the fields of the entities allows for the entities' to position themselves in respect to and within the plasmatic magnetic field strength of the planet to be attracted by the effective plasmatic magnetic field of the planet. This is what we have called Magnetic and gravitational position or for short Magravs positioning of one entity in respect to the other entity, where both entities possess internal dynamic plasmatic magnetic fields.

The reality is that, if Earth has had only one magnetic field as has been assumed until now, then all elements on the planet would have been firmly attached to it, due to principle of attraction or repulsion of two magnets, and as it is observed on the planets all systems have been able to freely positioned themselves and being able to be mobile.

Without the shadow of a doubt the centre of the planet maintains two independent plasmatic magnetic fields, that the interaction between these two plasmatic magnetic fields at the plasmatic, atomic or molecular level leads to creation of an environment in which the matters in the surrounding area of the two plasmatic magnetic field will have the power to attract and repel mafs and matter within this created field. By the same law as the atomic matter, itself is made of magnetic energy fields, which possesses polarity hence why the attachment of the man to the earth as his being is made of these entities.

Therefore the matter will only by finding its Magravs position within the plasmatic magnetic field of the planet, if it can be attracted and be kept as part of the matter of the planet, or if its plasmatic magnetic field is too weak or too strong to be kept within a given field. Thus now it can be clearly understood how and why different planets can manage to hold on to certain matters and not the others and now one can understand why different matters take their positions in different layers of the planet too, where this positioning, like of the gases and solids, are totally related to the strength of the plasmatic magnetic energy of the atom in respect to the plasmatic magnetic energy of the planet or in other word, in respect to the total interaction between the pmf of mafs of the matter and the Magnetism and gravity of the planet.

The plasmatic magnetic field force created on these levels in the physical inner cores body of the planet these creates the condition, where all magnetic forces within these fields will be influenced through their magnetic reconnection, this being in atomic or molecular level, this creating pulling inwards forces for the two plasmatic magnetic fields of the matter and the planet to be locked into each other. This interlocking and the strength of it bind creates the effect of the gravitation field force, as the matters' magnetic force and the planet plasmatic magnetic field created by the double plasmatic magnetic energy field, reconnect to keep each other at a physical interactive but loose distance.

In reality gravity is the strength of the plasmatic magnetic field created by the interaction of the double dynamic magnetic force fields of the planet that can influence to pull the matters around these field to stay within its strength, or what is called its gravitational field force.

The interlocking of these forces are the same as with two bars of magnets when they are brought close to each other, but their binding of forces is in planetary plasmatic levels, which are at a loose atomic or molecular level rather than electrons' realignment or what is called are energy equal to the collective plasmatic magnetic energy of the electrons of Iron atoms interlocking plasmatic magnetic field level.

With the difference that in the planetary or astronomical, cosmological and universal levels these so called magnets are in the form of closed loop spherical shape and may be in possession of internal heating in respect to their surrounding temperature and system, where their plasmatic magnetic field force can vary and they can change their strength due to the compression and other factors in their centre cores, as in solid magnet the strength of the magnet is constant and permanent.

In the closed loop spherical plasmatic magnets, the system of the plasmatic magnetic field lines has to find their magnetic reconnection line for the loop to be completed. Where, this plasmatic magnetic field's reconnection leads to the directional polarity leading to the creation of the North and South Pole phenomenon of the planet.

Through replication and production of such a system as the structure of the inner-cores of the earth, in being able to control the amount of matter and fields within the structure of these systems, the strength of the plasmatic magnetic fields of the cores of the system can be controlled and adjusted, so that, this will allow the creation and control of the measured gravitational fields forces by the systems in respect to the environment in which the system is operating in.

In the case of motion of an object like a manmade system, in possession of its own gravitational power production, in the gravitational pull of another object like a planet, the use of the phenomenon of the creation and control of the gravity in the centre of any system can be treated in the same manner as in the planetary system.

Where, the gravity created in the centre of manmade system needs to be slightly changed in the positive or negative direction in respect to its previous position for the object to be repelled or be attracted towards the planet or an object.

This Magravs positioning of a system in respect to planets plasmatic magnetic fields, can be achieved through several means, like by the change of characteristic of the dynamic of the one core in respect to the other, or changes configurations of the parameters, materials or physical structure aspects of one core or both core of the system.

The magnetic and gravitational forces of a Star are to some extent dictated by the position of planets within the system as much as the constituent content matters of the Star itself. On these bases, this being the gravitational forces of the system and its position within its galaxy is to a large extent dictated and controlled by its' planets and the gravitational force they create independently on their own.

This is very much like the rotational plasmatic magnetic fields of the electrons circulating around the nucleus of an atom. Where, the magnetic rotational spin of the electron decides the plasmatic magnetic field strength of the nucleus and the position which the element occupies and the number of other electrons it can carry, so this dictates the properties and its characteristics in respect to other elements around it, even though the plasmatic magnetic field of the nucleus is much more powerful than the plasmatic magnetic field of the electrons around it, or in other word the gravitational forces of the nucleus is needed for the electrons to be kept in their orbit and vice versa.

Thus the gravitational forces of a system or a galaxy is not only dependent on the plasmatic magnetic energy forces of its centre or its star, but it is fully controlled and determined by a bigger scale by its constituent planets and stars in that system too.

From the topography of the Earth gravitational field pattern provided by space agencies, Earth plasmatic magnetic field does not keep a constant pattern and there are constant changes in the strength of these fields in different parts of the planet, where these are dictated by the activities within the centre cores of the planet at the point of observation. These variations in gravitational field's patterns confirming that the planet has composite and not necessarily spherical shape cores.

These variations in these forces in the cores of the planet could be due to the variation between the interaction of the inner and the outer plasmatic magnetic fields, where for example at point where these forces vary drastically in respect to each other, then one gets distortion of the fields and reduction or increase in the gravitational field force in that region of the planet by small factor. Then where, for example one force field, like the fields created in the Caroline core is more powerful due to sudden short burst of ionization in the core, at that point and that moment, the plasmatic magnetic fields interaction of the centre field is more powerful, then the gravitational field force can be more powerful at that given point, but these changes due to close confinement of the centre cores are usually not so large.

For example by observing the pattern of the gravitation field of the Earth, a constant depression in the plasmatic magnetic field in the region of the southern eastern hemisphere in respect to the rotation of the planet usually can be observed. Where, this phenomenon now can be easily be explained, and this is what I so call the washing machine effect and that is, where the material within the inner-core has loose plasma area of rotation, as in the drum of washing machine filled up with clothes, the inner-core of the Earth does not possess the blades as in the drum of the washing machine, then the more dense matters in the Caroline core as they cannot role all the way up against the internal wall of the cores, and then due to toroidal and interaction with poloidal motion of the Earth, these materials pull up the wall of the core and due to their viscosity they roll back over in this area, this whirlpool effect due to slower motion and less available field in this region effects the gravitational field in the south American continent area too.

This washing machine effect of the materials in the Caroline core directly affect the plasmatic magnetic field production in this core, and consequently its interaction with the plasmatic magnetic field of the outer core, and in turn this creates the disturbance in the gravitation field of the planets in these two regions as has been noted in the overall pictures of these regions gravitational field forces effect, where dents in the gravitational field forces patterns are observed on continues bases.

Even thou Newton did note the effect of interaction of two forces between the matters and the planet and he measured its strength and called it gravitational field's forces of the planet, but he could never establish the source and method of its creation. He speaks about the effects of the gravity in relationship between two objects in respect to each other's position, and not the effect created by two plasmatic magnetic forces in respect to each other and their position in respect to each other, where he could not understand that gravity was magnetic field bases entity and magnetic field strength and it effect are magnetic fields position dependent. Newton never could relate and understand the connection between Magnetism and the gravity as both to be created by the same matters and conditions which manifesting itself as two different forces in respect to other magnetic field forces.

Scientists explain the gravity as the relationship of attraction between position of two bodies in respect to each other, and not the reality that gravity manifest itself in relation to interaction and attraction of two bodies in possession of dynamic plasmatic magnetic field forces created and maintained in respect to each other position.

In understanding the real method by which the gravitational field forces of planetary systems are created then systems can be made to replicate the same process and by being able to create and control gravity as done in the planets one is able to observe the effect of this natural phenomenon within operation of a manmade system.

In manmade reactors as the concept of gravity has been replicated, now the concept of the gravity has to be redefined as the " attraction between two bodies, where at least one body possesses a double spherical dynamic plasmatic magnetic field force, where one field is superimposed by the other plasmatic magnetic field forces within an object, where their overall plasmatic magnetic field strength interaction upon each other can create an overall plasmatic magnetic field, that other matters in possession of their own dynamic plasmatic magnetic field or static plasmatic magnetic field, within their catchments area can position themselves according to their internal plasmatic magnetic fields strength".

The interaction of these double dynamic spherical superimposed plasmatic magnetic fields in the centre of the planet separated by the physical matter of the inner-core upon each other is the cause of the rotational motion of the inner solid core of the Earth and where the motion of the inner solid core itself is the containment body of the centrifuge system for the gases in the Caroline core for the atomic fusion chain of events in this chamber, for it to sustain the ionization process in the this chamber. Where, at the same time the inner-core plays the effective mixing machine for the matter in the outer-core of the planet, where the interaction of plasmatic magnetic field of the Caroline core with interaction with the plasmatic magnetic field of the outer-core would change the combined plasmatic magnetic field effect of the whole planet, which in reality would have changed the gravitational field strength of the planet.

The rotation in the gas layers of the Caroline core in conjunction with turbulence, which leads to convection in the materials in the cores of the planet, this effecting the generation of current and plasmatic magnetic field in the core of the planet and consequently the gravitational forces created by the core of the system.

Now one can explain that the change of the polarity of the earth and any other entity the like of the Sun is only due to change direction of flow of the current in one core or layer of these dynamic magnetic fields based star and hence the change of direction of the flow of the current for example in the plasma of the Sun layer leads to change of the polarity of the star, as one can sees the same change of polarity in the production solid magnets, where the change of direction of the flow of current changes the polarity of the metal, as is the same for the plasmatic magnetic field entities too.

Thus change of polarity of the earth is only due to the change of direction of the current within the core(s) of the earth and would not affect the gravitation field or Magnetic field strength of the earth when it will happens.

Now that the method of the creation and control of gravitational field forces of planet is understood and can be replicated, it becomes easy to understand how systems can be produced that can create magnetic field structure of any element or matter in the universe, this being magnet for hydrogen atom or uranium atom or magnetic machines can be produced that can gravitated to themselves molecular structure like water or protein.

Where, the system gravitational field can be created to match for example only the plasmatic magnetic field of atom of gold, so that the system becomes a gold magnet or the system will generate only or gravitates towards the plasmatic magnetic energy of the gold atom, so one can separate gold or any other matter which the system is present to generate the Plasmatic magnetic energy of. This system will then can replace the present centrifuge system of the present time.

Magravs measuring system

In the gravitational systems, where only magnetic fields forces are considered and measured, the present earthly measurement tolls of gravity has no meaning and room. Space scientists of the future have to learn to measure magnetic field force in respect to each other and not kilogram per centimetre per Seconds Square.

Thus the measuring gravitational systems to be developed have to be first of all three dimensional, as field forces of all matters and fields in space have to be considered and balanced against or with.

The gravitational tools of the space technology is fixed magnetic fields shear against the magnetic fields of the system against the total magnetic fields forces in the overall sphere of the systems fields.

In fact the gravitational fields of the space technology are like a magnetic fields sphere positioned around the gravitational reactors, as these measuring tools of the gravitational systems will measure the Magravs of the all fields of all forces internally and externally in respect to their position in respect to the reactor Magravs.

The Magravs measuring tools are to be called **Universal Magravs Measuring System** (UMMS) and position of Magravs of the system in respect to another Magravs are called **Magravs positioning System** (MPS).

Elaborations:

Through understanding the real term concepts of the creation of the gravitational field forces and design and production of specific nuclear-based reactors of the function of matters within static and dynamic reactors, the principle of the hypothesis of creation of gravity has been proven to be correct.

The difference between inertia and gravity is said to be the gravity is an attribute of a body in possession of two dynamic plasmatic magnetic field forces interacting upon each other, where the inertia is the attribute of collective molecular magnetic force of an object which does not possess a double magnetic field structure as whole, even though both behave the same and due to their plasmatic magnetic fields appear to be the same thing.

Where, in case of planets like Earth, the total pulling power of the planet in respect to other objects in, on, or about it are due to collective forces created by the gravity and its constituent's matters inertia.

The creation and maintenance of gravity is dependent on two dynamic regions being in possession of two independent dynamic plasmatic magnetic field forces and gravity is totally independent of the mass of the object as mass itself is the by-product of the interaction of the Magnetic fields and gravitational fields of the entity, but dependent on the position of their plasmatic magnetic forces in respect to their plasmatic magnetic field strength from the centre entity.

The centre of planets, does not matter what their inner layers are made of do not need a metallic matter or metallic behaviour conditioned matter for the creation and maintenance of their own electromagnetic effect due to motion of electrons and charged plasmas in their core as these entities generate current and potential difference levels for the core to maintain independent plasmatic magnetic field forces leading to the creation of plasmatic magnetic field and finally by interaction of two such dynamic plasmatic field forces upon each other, leading to creation of gravitational field forces within the entity and in its surrounding area.

The interaction of these two plasmatic magnetic field forces upon each other, or the concept of *"DOUBLE DYNAMIC SPHERICAL PLASMATIC MAGNETIC ENERGY FIELD EFFECT",* in the centre of any dynamic plasmatic entity will lead to creation of the gravitational field force and the magnetic field forces of that entity in respect to other entities with the catchments fields force of the entity.

Therefore, the gravitational field strength of a system manifest itself and can be explained as the relation to interaction and attraction of two bodies in possession of dynamic plasmatic magnetic field forces created in respect to each other plasmatic magnetic field position and strength. Even, further it has been proven through prototype reactor tests that the speed of the rotation of the planet is determined by the speed of the solid inner-core of the planet, where the speed of the rotation of the planet is set and dictated by the interaction between the dynamic plasmatic magnetic fields of the Caroline core and the outer-core of the planet, as the motion induced by the strength of the two fields in the centre cores, upon and interacting within the solid inner core, determines the speed of the rotation of the inner core, and in turn this will determine the speed of the rotation of the whole planet.

Whereas, if the speed of the rotation of the planet were not set by the planet by this principle, then the planet would have had different speeds at different points in its daily axial rotation and it would have had different speeds in its annual path in circling its star, where the effect of the other objects in the system would have dictated different speed of the rotation of the planet, therefore it is correct to assume that the speed of the planet is controlled by the speed of the solid inner-core of the planet, and the same applies with other entities like the star as the speed of the internal fields interaction dictates their speed of rotation.

The motion of the inner solid core is very much like the motion of the trains on magnetic tracks, where by not allowing the two dissimilar magnetic poles to be aliened, the train moves forward. Where, in the case of the spherical solid metallic inner-core of the Earth, this motion is rotational rather than linear.

Through tests, it has been proven and understood for the first time, that the magnetic polarity change of planet or the system occurs when the direction of the flow of current this being due to motion of electron or charged plasma in the cores in the whole of the system changes from one direction to the other, or in some cases one field change of direction of internal current can causes the half reversal of the polarity of the whole system. This is understandable, as the plasmatic magnetic fields are created due to directional motion of electrons, plasmas or charged plasmatic current within the matters of any entity, thus as the direction of the flow of the current changes, this will change the direction of the polarity of the planet.

Understanding the direct relationship between the magnetism and gravitational forces within a system, in the manmade systems the change of polarity in the reactors of a system has to be avoided, as, if this happens during the operation of the reactor, this can and would lead to the overturning of any platform which is equipped with such a system. This being one of the fundamental reasons why the reactors which have been developed and tested up to now for space technology, always are preferred to be constructed in a half spherical shape, simply to avoid the flipping of the polarity in the cores of the reactor, where the speed of the rate of the polarity change is very dependent on the components and conditions created within of the centre of a planet or a star.

If a planet is made of near enough similar material on both side of the inner core, the flips of polarity will be much faster and on a shorter time lapse, like in the Sun.

If the planet is made of a composite core, and made of two or more different materials in its Caroline core (the real centre core), for the two fields to re-align, then this will take a longer time for the magnetic flip of polarity to occur, like in the core of Earth. In any case, as the materials in both cores are always constant and cannot change that much, therefore the time laps between the changes of polarity stays on the same time intervals.

In the case of the Sun, due to its more uniform and singularity or only composite of three matters of plasma, hydrogen and helium in its core, the change of polarity takes eleven years, and the full polarity change has the predetermined time of twenty-two or three years.

In the case of smaller planets' like the Earth, which is made of composite mixtures cores, the time lapse in change of polarity will be longer. Where, the switching of polarity is a natural outcome of the direction of the flow of current created by the electrons and primarily by the charged plasma and due to dynamic characteristic of the core, and is an inherent characteristic of the atomic structure of each element and environment which they are condition to within the cores of the planet.

It has been observed in tests, that the plasmatic magnetic field of the core increases by the principle of extraction of the electron from the core, where electrons are facilitated to be absorbed by the walls of the reactor core. Where, the majority of the field created is primarily due to the motion of charged plasmas. Where, at the same time for weaker magnetic fields test the reactors have present to absorb the plasma of the proton that only the lesser mass of mafs available in the plasma of the electron can be used for a given test condition.

Therefore according to need of the use, reactors can be set to utilize any components of an atom or the mafs of their constituent plasmas without in fact destroying any structure of the mafs or the matter, which the mafs was used for that given exercise.

In principle it is observed that the plasmatic magnetic energy of the planet is primarily due to the motion of the charged plasma in the core and not electrons, where in reality the motion of charged dynamic nuclease of an atom has/ and indeed, possess a much larger electrical charge then its counterpart the electron by factor of 2000 times. Thus now it is apparent and clear why such a small core in planets can master such large magnetic field forces within and around them, and now it is understood how planets can carry the burden of such large mass in their journey through their system for such long period of time of billions of years in their solar systems.

In tests plasmatic magnetic field created by these type of cold condition plasma using a 20 cm dynamic core, has been noted to create a 4-meter radius dynamic spherical plasmatic magnetic field span, which can last up to several minutes after the switching off the whole system.

The dynamic plasmatic magnetic fields created within the double cores of the planets, determines the magnetic or gravitation fields, which the planet will possess and consequently the material, which the planet will hold on to. This explaining why planets behave like magnets, which only have the characteristic of one element or several materials plasmatic magnetic band(s) which covers some and not the other elements, which this dictates the material composition of the planet within, on the surface and around the planetary system. Where, the same applies to the solar system and galaxies and so forth. Where, the gravitational field forces created by the balance of the two interacting dynamic plasmatic magnetic fields is the principal factor in determining the constituent material of a plasma, planet, star or a system.

The creation of the gravitational field forces of a solar system and even the gravitational field force of the galaxies are not far from the gravitational system and method's used in the atomic and planetary systems. That is to say, that solar system’s possess and generate plasmatic magnetic fields like planets and they possess gravitational forces according to their stars constituent materials. If one could stand on the edges of the solar systems, one should be able to see and detect the gravitational forces of this system, by it simply absorbing and attracting with the entry of cosmic meteoroids and asteroids into its gravitational and solar heliosphere region of its solar system.

Solar systems, like planets, possess and create magnetospheres of their own which is specific to their composition materials. The entry and exit from these solar Magnetic and gravitational fields uses the same method as the entry into or exit out of planetary systems.

This also holds true for a solid magnet, where if a piece of magnet could be cut into two halves or four quarters, each piece of the material will still carry the same north and south poles and each piece will have the same magnetic powers as the original piece. That is to say, that if one uses the same volume ratio of the same mafs or matters and proportional physical conditions in the core of a system; one will attain the same magnetism and gravitational field force from the system as its bigger dimension system with the same mass ratios.

In astrophysical terms, the Magnetic field forces of any entities are what keeps the entities apart from each other, and at the same and opposite to this, the gravitation filed forces are what keeps them together.

Where, the pattern of distribution of Magnetic and gravitational fields forces of the entity interacting with another Magnetic and gravitational field force shows itself as the magnetosphere of the entity.

This Magnetic and gravitational field force (Magravs) of dynamic plasmatic fields force is known passive magnetic field (PMF) and has no relation with the magnetism as known in a solid-state magnet. This is so called passive plasmatic magnetism due to the fact that, this type of magnetism cannot magnetize an entity otherwise all the materials in the universe would have stuck to each other. But this mixture of Magnetic and gravitational fields are used to position one entity in respect to each other that they not necessarily collide or move too far from each other once they established inter-magnetic connection.

The reason the Magravs are called passive plasmatic magnetic field is due to their capability of passing through human tissue without in majority of the cases affecting the function of their atomic and molecular magnetic field, which human cell possess on their own for their structural bindings.

In the past, magnetism and gravity have been explained according to the physical understanding of a solid magnet and not according to the planetary magnetic forces, this new understanding of creation of magnetism and gravity, is one of the corner stones of the creation of plasmas, planets, solar systems and galaxies. By not appreciating the connection between the magnetic field force and gravitational field force of a system like Earth, it has become a challenge for the scientific world even to overcome the weak gravitational field forces of small planet like earth in just trying to send a small rocket into the Earth's orbit.

Through development and tests on double core type of cold condition plasma reactors creating the same conditions as it has been assumed to exist in the centre of planets, it has been observed and physically been proven, that the source of the three dimensional spherical gravitational field and three dimensional spherical magnetic field of the planets are the same materials and the dynamic interaction of plasmatic magnetic fields created individually and independently in each core of these reactors and their effects upon each other creates and maintains both forces of the creation Magnetic field and gravitational fields forces simultaneously.

If one were able to create the right condition and material in a simple core, as has been done in our tests with core developments, then one can create and control magnetism and then the gravitational field forces within that object, and then in the environment which the object is positioned in respect to other external plasmatic magnetic fields around it, where, the plasmatic magnetic fields created within and by the object will becomes its Magnetic field around it, very much like the magnetosphere of the planets, this providing a magnetic shielding like Earth atmosphere around the object and due to the spherical shape of objects in possession of both forces, this creates a magnetic loop, where they create the two poles of the magnet as the North and the South Poles.

If a system can take advantage of this phenomenon, for it to move within forces of a planet, rather than trying to overcome them, or to resist them for its motion, then not much energy or effort is needed to create the right gravitational forces and magnetic field protection within and around a system for it to move inside or outside the atmosphere of a planet or a system without burning a single atom as a fuel, which this puts an end to the propulsion technology for rapid and protected motion anywhere in the universe.

Due to the spherical shape of most of celestial entities and their rotational motions in the universe, the gravitational force created by the dynamic plasmatic magnetic effect has a pulling force, which has the tendency to encircle and reconnect within the interior of the entities fields of the same dynamic structure. This being the reason why the gravitational forces increase as one moves closer to these objects and as one moves' towards the centre of these matters.

The difference between the solid magnetism and plasmatic geomagnetism are two clear factors, in this particular order, first is Dynamism of the magnetic fields which creates the geomagnetism, and second the need for the interaction of two independent fields upon each other to maintain the plasmatic magnetise, where plasmatic magnetism for it to exist the plasma needs to create and maintain a full gravitational and Magnetic fields system of its own, which can absorb and feed other plasmatic magnetic fields within its environment to guaranty its survival in that environment at the same time, whereas in solid magnet, the order of continuity is within the structure of the matter and not mafs of the matter.

Conclusion

The gravity is the product of interactions of fields and wherever in the universe fields will interact their interactions will gravitates some fields or matters to them, or caused these fields to be attracted and gravitate towards another setup of the same or stronger and by laws of nature the stronger attract and gravitates more to itself and the heavier mass as they are made of more magnetic fields tend to dominate the seen when it comes to gravitational pull. Through tests it is apparent that the power of Magnetism and gravity of all entities in the universe are independent of the physical size of the entity and more dependent on the strength of mafs, which have led to the creation of the entity.

Through design and test of double core reactors we have proven that the origin of the gravitational force and magnetic force of a planet or any celestial systems in the universe are the same mafs and materials and conditions, where they are created out of the interaction of two independent and dynamic plasmatic magnetic fields.

Note; this revised version of the creation of gravity paper has included extracts from collection of three other papers published by the author, which these were, the gravitation measurement system, the relation between Magnetisem and gravity (35) and the original paper of the creation of the gravity.

CHAPTER 10

The creation of Black Hole

© M.T. Keshe/The Keshe Foundation 2004/2006. All rights reserved.
Author: Nuc Ir. Mehran Tavakoli Keshe
Date of Internet release: December 3, 2006
Up dated version for this book publication 2.9.2011

Note:

The original version of this paper, which explains how black holes are created and how they do leak matters and rays into the environment of the universe, was submitted to the Royal Astronomical Society of United Kingdom in London in April of 2004 for peer review and publication. The author after three months received on the 8.7.2004 a letter (Fig. 29) from the Society dated 7.7.2004 that this paper will not be published and will be kept in the library of the Society.

Interesting enough on the same day 8.7.2004 (check the press) Mr Steven Hawking, the imminent Black hole scientist and expert in this field of science announced that he, after thirty years has changed his mind and he says that indeed the black holes do leak rays out and that he announce this in a conference in Dublin later that month (see the press), as now he has lost a bit of shirt.

We have wondered for years how coincidental of the topic, the date of letter from the institute, the date of announcement, and the change of mind of a scientist!

This is the reason why the Keshe Foundation does not believe in the scandals and process of peer review and the foundation publishes its own scientific papers on its website and its own books for the reader to peer review the newly gain knowledge. As with this process the knowledge is passed on first hand and in some cases in matters of hours of the discovery to the public and not waiting for month and years until there is gap in some journal that the paper can be published. The Keshe Foundation firmly believes that 'as if a man, has reached the age of maturity and intelligence that he can read, then he can independently investigate and judge the correctness of the knowledge he receives according to his own level of intelligence for himself", unless he is an innocent, then he needs to accept the enforced control system of peer reviewing to tell him what to think, that this peer reviewing can suit the self-interest of the peer reviewer, or organisation which supports him financially or the nation which has promoted the peer reviewer for their own clandestine purposes, as we have seen the same process of control through peer review systems in different occasions in different countries around the world in this recent times.

A copy of the letter from the Royal Institute of Astronomical Society is enclosed at the back of this chapter for reference. (Fig. 29).

Abstract

Since first disclosures of this phenomenon, scientists and the rest of academic world have tried to understand and explain the reasons for the existence of these mysterious Black spots in the universe.

Hypothesis

The object of this paper is to prove that Black Holes are created out of a natural sequence of events in the universe and to prove that existence of a Black Holes in the galaxies and in the universe is a normal event as the appearance of the Dark Spots on the surface of the Sun. Black holes are simply a creation or an outcome of natural interaction between two or more mafs, passive magnetic fields and matters in motion within any dynamic plasmatic magnetic field entity in the universe (Fig. 26).



Fig. 26 Interaction of two plasmatic energy fields creating the effect of a Black Hole.

Discussion

In this paper for the first time, it will be explained how the Black Hole is physically created and in this disclosure it will be explained

1) The conditions, which this physical object is created in the universe naturally.

2) How this body of the mass appears as a dark spot in the galaxy?

3) What purpose it serves in the universe?

4) Parallel example of the Black Hole condition in our solar system.

5) The use of this phenomenon for Man to enable him to travel in space.

When, one could fully understand the concepts of the creation of galaxies, stars and planets and plasmas, and then one could be able to understand the creation and existence of the Black Hole in the universe in its different scale of dimension, where the creation of these entities in the universe all follow the same principle.

In understanding the fundamental principle that galaxies like solar systems and planets are given their inner mass and energy at the point of their birth in the universe, so they cannot create additional new masses and new source of energy on their own. Then it is understandable that Galaxies can only recycle what they have been given at the start of their lives, to create different new objects like stars or planets within themselves. In universal terms they have a finite mass and energy available to them and nothing more. But at the same time as a part of bigger picture galaxies have to obey the universal laws of physics. Consequently, all galaxies follow the same rules and so do their physical contents like solar systems and atoms within them.

A Black Hole is created primarily and only under-one condition in the Universe and as the consequences of other acts in a galaxy. They are not created as a deliberate act and as predetermined plan in and by a galaxy. But in their way, they make an enormous contribution in keeping the matters in check in their surrounding environment during their relatively short life.

At the same time they redistribute fresh materials throughout the galaxy during their cycle of existence. This is done through and as the consequent of them being the source for the creation of cosmic rays in their galaxies, as this is very much like natural fertilizers production systems of galaxies. Where, the old matters give its energy in an indirect way, for the existing other planets, to keep them healthy and for them to receive sustenance from their galaxy.

Black Holes in the universe are nothing but the centre for collection and re-cycle waste bin of cosmic debris of different sizes, this being giant meteoroids to specs of cosmic dust.

As the black hole grows bigger and their gravitational forces take over, then a Black Hole becomes a predator for parts of this galaxy. They become vast eating machines of the debris and stars and planets and this is exactly what is to be expected of them.

The Black Hole is originally created totally by chance. There are no patterns in their creation. They are simply a creation or an outcome of natural interaction between two or more passive magnetic fields or matters in motion within the galaxy or the universe.

Creation of the Black Hole

To explain the concept of creation of black holes, phenomenon's that are normal and familiar are used and will be relied upon in this paper. Then a parallel for the creation of the Black Hole type of incidents will be drawn with the same process in the solar systems, galaxies and universe.

Black Holes are created according to the rules of physics in galaxies to collect and then replenish the galaxies with fresh recycled materials, where this recycling is the vital factor in sustaining and making sure that as the galaxy moves that there are new materials available to start new systems within the galaxies. At the same time for them to nourish the other planets within the galaxy with fresh supply of materials. Where, for example the Earth receives several thousands of tons of cosmic dust from the solar system through the similar method through its atmosphere per year from the black hole within its galaxy and from the universe.

The parallel similarities between the Black Hole and presentation of new material in the universe and on Earth can be compared to the effect of collision of Earth's tectonic plates. When, two sources of solid materials interact with each other. In the long run stars and planets in the galaxy, as the same with Earth submerged tectonic plates; these become the source of the supply of new materials in the galaxy, similar to, as lava becomes the new continents, or mountains on the Earth.

Let's explain this in the following manner. The continental plates and stars systems are forever on the move, they move slowly, but surly they are on the move. On the Earth, when two or more continental plates move in random manners, over centuries and millions of years, at some point they come on each other's path so as do the stars and their systems, like solar system and others in our galaxy.

When on Earth the two or more continental plates come together. Several things can happen, this happens in galaxies but in a different form too. Where, the continental plates in galaxies are replaced by cosmic spherical or flat oval magnetic fields of the stars or systems.

The next steps in the procedure are very familiar on Earth as the continental plates push against each other, if, they are of similar strength, they rise together to create the mountains over millions of years as these plates are still pushing and moving while they are exerting their strength on each other. So, large mountain ranges on the surface of planets are created.

Other things can happen too and that is if, one of the continental plates has weaker energy strength the weaker plate will slide under the other, where the continental plate which sub-merges in the long run becomes the material in the lower levels inside the planet, which later this becomes the base material for the magma of the planet, then over millions of years this matter again appears on the surface of the Earth through volcanic eruption. Then some times in the future these too become the source of materials for new continents or an island and so on through volcanic eruptions.

The material drawn into centre of the planet does not disappear but for the time being is hidden from the view and parallel to this scenario happens in the galaxies, when two or more systems in the galaxy reach each other, where an area in the space is created that the two passive magnetic fields and or entities have to interact with each other. Where, their passive magnetic fields push against each other like continental plates (Fig. 27).



Fig. 27. Plasma of passive magnetic fields pushing each other creating
a balanced magnetic field region, called Black Hole

As they are on a collision path with each other and as at the same time the surrounding systems forces are pushing for their position, they do not allow any other course of motion but path of the collision of the two systems on the move. Then, a point is reached that as there are solid materials in motion from both systems and they have no choice but to collide and interact with each other. Where, in this process being thrown at each other by their systems, pieces of inter-planetary garbage, parts of moons or meteoroids and other bits of the two systems in this region are in the same pot too and all are mixed up and get entangled with each other.

In this area and at the same time as the two systems physical materials are pushed and thrown at each other, so do their mafs and passive magnetic fields are exerting their powers and authority too as in the like of in the planetary the hidden forces pushing the continental plates into each other. Then a point is reached, where these two magnetic force fields' of the two set of entities forces become to near enough to cancel each other out and create a condition of magnetic field equilibrium, where one field force cannot dominate the other passive magnetic field force, and inevitably an area of no or very week passive magnetic fields force in this region of the universe is established, where during all this processes materials from both systems are still being pile-up in this part of space. Where, the two systems materials are brought together due to pure forces of the Passive Magnetic Field forces of the systems and their surrounding systems in the galaxy.

Even stars themselves in the latter stages of the development of the Black Hole could become the victims of the Black Hole, which their system themselves were partially the cause of creation of. At this point the new mass of the Black Hole may even be a larger mass than any of the individual systems that created the Black Hole in the first instance.

One cannot forget that these masses are still in motion and rotating at very high speeds.

This new mass in the centre of this is pile all together creates a very large gravitational force within its region due to sheer weight of the mass which is collected and primarily these could become inertial pull rather than gravitational pull of the matter in these Black Holes too.

By laws of physics, one knows that the only reason that stars shine or cosmic rays glow is the phenomenon of the motion of charged particles passing through a magnetic field. In this region where the magnetic fields are very weak, this region lacks the main component that could make it shine or to be bright and that is the lack of the passive magnetic field in this region, due to the equilibrium and / or cancelling out of the two interacting magnetic field forces of the two systems.

Or for a time in the motion of the two magnetic fields of the systems passing each other in some parts there are no or there will be very little magnetic field force available, even thou there are charged particles in the area, but there are no magnetic fields strong enough for them to interact with to create the visible light. Consequently, in these areas of galaxy there are No glows and No shine.

Reason why this is called the Black Hole, is due to the fact that in these parts of the galaxy, which two or matters and their magnetic fields meet and interact, and can balance each other out, there will be very little visible light emission due to the lack of interaction between charge particles and non-existence of magnetic fields or existence of weak magnetic fields, that cannot produce bright light enough to be visible from the Earth.

This is the reason, why if one look's at these areas of the galaxy these areas seem to be darker compared to their surrounding areas, as the light not only is emitted from the mass of the black hole, but at the same time these matters due to their physical dimensions and their magnetic fields forces strength will not allow and block lights coming from other sources behind them in the galaxy too.

This is why, these regions of the space seem to be black, but from an outsider point of view looking over the area it looks as everything and all materials are thrown in to this dark spot from one side and nothing is coming out of the same side and consequently the physical term of The BLACK HOLE was invented.

This area appears as to be a Dark part of the universe, but in reality some rays of light should be observed being produced in this zone, as some charged particles still interact with the some weak PMF of the systems or what is left of them before they enter and interact and in this part of the galaxy there are visible light but matters are disappearing too.

So, in this region of the galaxy astronomers observe a large gravitational force due to the large amount of mass thrown in to this area by the two systems as they pass each other. But, they have no explanation as what is happening to all this mass. Now one understands the reason for this false assumption and appearance. This is the region where the gravitational forces are in reality mixture of gravity and inertia pull of two systems.

One has to remember that as these two or more systems are passing each other, several scenarios can happen again, which every one of these will have and has drastic and profound effect in that region of the galaxy. Where, at the same time these events can generate a vast amount of new recycled material for other entities within the galaxy.

At the same time one has to take into account the time factor and that one is dealing with a three dimensional picture, as in some cases the Black Hole exists for millions of years during the crossing of the two systems crossing each other's path at a slow speeds. The truth is that the Black Holes are a temporally condition, so to speak, in the bigger picture of cycle of the life of a galaxy, but they surly look like being there forever.

Some of the residual of these interactions will be some cosmic rays (10) or the outcome could be the birth of a new system with a new mass from the mixture of the masses of the two old systems after the system parameters balances each other out. In this case the overall masses of elements within the black hole are present as they were in their original systems. Where, now the new Black Hole could possess slightly less than the combined mass of two old systems. With lose of the some of its matter in the process of the interaction of the two systems into the galaxy.

One cannot forget that the centre mass of the Black Hole is still rotating most probably in the same direction as the systems were rotating which created it. At the same time, as the centre mass is void of the Passive Magnetic Field (PMF), the usual interaction between the passive magnetic force and gravitational force do not take place that usually creates the first basses of heating and sustaining that heat, so that the temperature gradient could take hold, that this in turn could create the scenario conditions for the mass to become a large star or a system.
So that the centre mass have enough material but not the right condition to create the necessary heat, for the time being to make the jump to become the source for a new system or a new star in possession of gravitational forces.
This is one of the ways that the Black Holes become the creator of new stars and systems. Therefore the mass relies upon the heat that is produced mainly by the natural friction of the elements pilling on top of each other in the centre of the black hole.

But at the same time these places become the centre of the mafs of principal matters of the entities within the collision zone. Where at this point the principal mafs and matters of the constituent matters within the collision can take hole and star t the process of creation of the principal star with its strong magnetic and gravitational field forces, which this condition can lead to creation of principal star and hence through realises of mafs of at principal level and through its slowing down and through production of transition mafs, these parts of the universe can again appear to be dark than the rest of their immediate surroundings, and hence the creation of balance mafs of created and the surrounding environment field, then again due to lack of creation of interaction sufficient to create mafs at the mafs of visible light, then these areas of the universe again look darker than the neighbouring regions, and as the centre of this region is covered with the seed of principal mafs and matters then one observes the strong pull of matters to this region without being able to see its origin which is the principal star in the centre of the dark zone.

These interactions between passive magnetic fields occur on regular basses in our galaxy, as systems are at all times on the move in a confined space of their Galaxies and if one had enough time to look out into the space, one will observe the creation of so called black hole the way one observes passing of dark clouds in the sky of the earth during stormy times.

The motions in this specific part of galaxy are in progress over thousands of years, the Black Hole's due to other systems magnetic fields surrounding it and their influence and interface with passive magnetic fields of these systems making and allowing the black hole to leak cosmic rays into the galaxy like a fountain in its surrounding area.

Then it should be understandable now that why the scientific world finds materials from the Universe that is not nor have not the same age as the original component of the galaxy. As like supernovas, the Black Holes are the source of the new material for the galaxy primarily because of the way they are created and the way their life cycle finishes.

The other scenario of the interaction of the two systems could be totally different with an interesting outcome. This is the most horrendous way that the two systems could come into contact with each other and in this case as the two magnetic fields come too close to each other, at the same time other systems around them push these Passive Magnetic Fields themselves together.

The two fields interact and the first stage of creation of the Black Hole is reached very rapidly, but as the two systems surrender more and more of their debris and planets to the Black Hole, the central mass of the Black Hole increases and as the Black Hole is receiving its contents from two different systems simultaneously, then a point reached that the weight and the gravitational force of the new centre mass of the Black Hole super-passes the mass weight of one of the systems, which created it in the first place.

Systems which have already lost some of their mass to the Black Hole at the outset of the creation of it, now losses control of its magnetic fields too. To an outsider looking at this event, it seems as the Black Hole is consuming everything around it. Where, this process can take over thousands of years, until a temperature gradient or a dynamic principal mafs and matters of in the centre of the mass is established.

As the centre mass of the Black Hole has consumed the entirety of two systems, and it is operating in a no magnetic field zone for a period of time, where its internal dynamic plasmatic magnetic field cannot pass its physical boundary (see the paper "The creation of dark matter" M T Keshe for clarity), the system will still can absorb or attract other masses from its surrounding into itself.

In this scenario, if mafs and materials are held for long enough time within the centre mass! That new magnetic field force could be produced and maintained, where at this moment of its life cycle this giant of a mass of the Black Hole will be nothing but a huge Gravity and Magnetic field producing machine. Where, by the end of this process a new system or several systems will come to be born and new materials will be scattered in the galaxy, and this Black Hole will be a Dark place but not necessarily cold.

If the centre mass during its creation does not manage to heat up, then the third phase of the Black Hole syndrome takes hold. This being that, the centre mass at this stage becomes so big and as it never had a chance to heat up due to total absence or lack of strong magnetic force at the same time where the new large centre of the mass is rotating, this new mass will be inherits a huge natural inertia force from its collective mass with no or little magnetic field beyond its physical boundary to keep it at bay, so, this massive large body will start pulling smaller objects near to it into its trap.

The same phenomenon applies when two galaxies come to pass each other's path too, with the most horrendous outcome for the galaxies in that part of the cosmos, where the outcome of such encounter is beyond imagination. This has happened before and astronomers forecast it for The Milky Way galaxy in the future as it passes the nearest galaxy to it in the next few billion years. Where, the surrounding areas near the newly created Black Hole will not be safe from the onslaught as this new mass at all time of its existence has the same fundamental problem as of all other systems, and that it tries to hold onto all its elements. At the same time like other systems the lighter elements and weaker mafs in the mass move to the outer layers and to the edges of the mass.

Where, weaker mafs as lighter gasses and particles move to the outer region of the mass, they become better candidates for them to be pulled away from the centre mass by any opening in the adjacent Magravs systems near to the Black hole. When the centre mass reaches a point that Magravs or its inertia force become weak on its edges, that lighter elements can manage to loosen themselves and escape from its grip into the space of its neighbouring environment.

These freed elements will become part of matter that can be attracted by adjacent systems to the black hole or due to the rapid motion of the Black hole released as cosmic dust in the galaxy. Therefore objects can and do leak out of the Black holes into their respective galaxy even during the time of their creation.

If these elements are pulled out of the power of the centre mass, through the strength or gap in the adjacent systems or weakness in the power of the black hole, then they become the cosmic rays this being due to the fact that during extraction most atoms get striped of their electrons, and some heavier atoms in this scenario lose their electrons in the same way and so they appear as plasma and as part of the cosmic dust in the galaxy too. Black Holes are the source of most of cosmic rays and dust in the galaxies due to this effect (10).

In the galaxies Black Hole's while are in process of being created and during their existence at all times are still surrounded by other systems and are under the influence of their Magravs.

The powers of these Black Holes are usually kept at bay by other systems around them with their larger magnetic field forces and gravitational forces, which the black hole is still encapsulate amongst.

Black Holes are normally observed close to the centre of the galaxies and the universe, as there are more systems clustered together in these regions as this increases the chances of different systems to come in the path of each other and in turn increasing the chance of the collision of solar systems in the and galaxies in the universe and hence increase in the chance of the creation of numbers of the Black Holes.

The stronger mafs and the heavier elements of the universe and galaxies are largely concentrated in and near the centre of these entities, thus the passive magnetic fields and gravitational forces of the systems in these central regions are many times more powerful near the centre of galaxies then what is experience in the outer edges of them.

Consequently, the gravitational forces and passive magnetic forces in the centre regions of the galaxy will soon bring and keep the size and the power of these giants Black Holes under control.

What these collisions of systems and creation of Black Holes achieve is the fundamental principle of regeneration of new systems out of the old matters, and at the same time unclogging of the galaxy of all the loose debris.

If one looks at a three dimensional overview of these areas in space, surely due to the movement of stars and planets and the interaction of their forces, one should be able to predict, where the next Black Hole in that part of galaxy could be produced.

In time, a point will be reached, where the passive magnetic fields systems in one of the immediate systems' neighbours to the Black hole will move on, and at this point the feeding frenzy of the Black Hole will come to an end.

Like volcanic eruptions on Earth, where the mantle is thin enough that pressure of the lava can takeover, and that it can to pure out, pushing its way out into the atmosphere as a volcanic eruption.

This is exactly what happens when one of the passive magnetic fields in this area moves or weakens.

This creates a gap in the fields containing and controlling the black hole parameters, where the materials in the centre of the Black hole, which has been pushed previously into the Black Hole from one direction, for these materials to be released or scattered in to the galaxy.

In this process, part of these materials will manage to cluster together and generate the conditions essential for creation of one or more systems or stars.

Where the rest of the materials of the centre mass of the black hole becomes cosmic dusts, some become comets and some become cosmic rays and so on.

Thus Black holes are not gigantic eating machines compared to the size of their galaxy. In reality, they are nothing but a temporary condition created in the galaxies due to movement of plasmatic magnetic field systems as they are crossing each other.

Very much like two masses of clouds crossing each other path colliding with each other. Where, this interaction of clouds upon each other creates abnormal conditions in that area of the planet, where, their thickness can block the rays of the Sun behind them and the sky looks darker, but in reality these are temporary conditions for the viewer from Earth.

Contrary to common belief, Black holes always release matters and release new recycled material into their surroundings; they are not bottomless pits, where everything disappears into them. They are like a funnel, that if one looks at one end it seems that they are taking everything in, but exactly like a funnel, they have a hole on the other end, that what goes in has to come out, with a difference that the end of this funnel is connected to a kitchen-waste unit of the universe, where that on one end it crunches everything up and mixes whatever goes in before spewing the waste out through the waste pipe.

So the behaviour of the Black Hole is very much dependent on the position of the observer. If one looks from one end they are massive eating machines and from the other end they are the supplier and feeder of new life in the Galaxy.

In real term this dark part of the galaxy is at all times emitting electromagnetic waves of varying levels and strength from all the activities which is happing within, around and because of it. Black holes can easily be identified in their environment and their position can clearly be pinpointed by using much simpler method of detection than by just guessing and look for their effects in a given region of the universe.

In principle the Black hole has all the attribute of any system, but in fact as the internal plasmatic magnetic energy field of the systems creating it, in the given region of the galaxy, cannot create outward plasmatic magnetic energy field, that can interact with other plasmatic magnetic energy fields in its immediate given environment, for it to create outward visible magnetosphere at boundary of the black hole to manifest itself as a visible space in its region, this leads to creation of lack visible light in the man's Magravs amino-acids matter mafs strength.

The phenomenon of Black Hole occurs on the continuous bases on the surface of stars of any Solar system. The principle of the creation of Black hole happens on a smaller scale on the surface of the Sun in the solar system, where these are called the Dark Spots of the Sun.

These are where dynamic plasmatic magnetic fields systems on the surface of the Sun go through the same cycle of interaction of fields with each other as it happens for the creation of the Black Hole in the galaxies, where these plasmatic magnetic fields come across each other in the atmosphere and on the surface of the Sun, consequently they have to interact or pass each other, with the difference that these plasmatic magnetic fields systems on the surface of the Sun, even thou they are so powerful, they in one way or other meet-up with each other, and as their energies have to interact, then sometimes these energies cancel each other out and reach a balance magnetic energy condition.

At these points then, the same cycle as the creation of a Black Hole, on the surface of the Sun in much smaller scale repeats itself as there are no magnetic fields interaction because of similarities and identical mafs strength of the interacting fields, then there very little friction of fields that residual fields in the strength of the man's mafs of amino-acid strength are released, and hence or a very little light in the region and hence the appearance of the Dark Spots on the surface on the Sun is observed. In some instances the same is created as there are no interactions or balanced pmfs strength of the matters and mafs between the charged particles and mafs from the surface temporally are produced and consequently there is no or very little emission of light from the surface of the Sun in these regions.

On the surface of the Sun the same scenario of retraction and absorption of matter as the of the Black Hole starts occurs with a slight variation, which in this case the gravitational fields force of the Sun is so powerful and very close by that as the gravitational forces of the Sun are (in proportion) many times stronger than the gravitational force of the particles captured within the Dark spot region on its surface, that once the magnetic fields have interacted their energies and the content within the catchments of their forces have reached the equilibrium level, then the mass of particles in these regions are sometimes pulled back inward onto the surface of the Sun instantaneously after the collapse magnetic fields which created the dark spot regions, then at this point the physical matter of plasma in this region of the dark spot are pulled back into and is literally missile back into the liquid surface of the Sun, this creating a secondary dispersion of matter in the atmosphere of the Sun and into the solar system and hence the increase in the Sun flairs during the creation and as sequence of the collapse of dark spots on the surface of the Sun.

In reality the persona of dark spot is created mainly through interaction of mafs fields of the Sun and these are created very high above the surface of the Sun, that the dark image observed is not in reality mainly on the surface but much further up in the atmosphere above the real solid surface of the Sun.

In other instances as the plasmatic magnetic energy fields interact to create the Dark spot, the surface tension of the Dark spot becomes weaker on its face away from the Sun and all sorts of mafs and matters in the full spectrum mafs of the universe directly gets ejected into the solar system with much more power and matter then normal dispersion.

Once the temporally condition of creation of dark spot of the Sun is created, By this time, most of the other plasmatic magnetic fields of the Sun physically push and cajole the plasmatic passive magnetic fields (PMF) that created the Dark spot, so that, these external forces in the surrounding environment of the dark spot move and shift them from their position, where by this movement there are no more active plasmatic magnetic fields in the region to interact with each other in these regions and then the normal process of the charged particles interacting with the plasmatic magnetic fields around them start again as before, then everything goes back to normal and the light or the shine on the surface of the Sun returns to normality.

When too many dynamic plasmatic magnetic energy fields start cancelling each other out, the surface of the Sun become congested with many different plasmatic magnetic energy fields and they clog up the surface of the Sun, like congestion in traffic jams, hence the number of the Dark Spots starts increasing.

It is important to remember that Objects (these being solid, gas, plasmas or etc.) possesses their own plasmatic magnetic energy field and all these plasmatic magnetic energy fields on the surface are dynamic and respond to other dynamic plasmatic magnetic energy fields, which are created internally in the inner cores of the star. Where, these internal magnetic fields are the creators' of the gravitational field and the overall magnetic field of the star itself. Where, The stronger plasmatic magnetic energy field (the gravitational field) usually dictates and plays apart in the position and level of freedom of the weaker plasmatic magnetic energy field (the object) in respective to each other.

Thus, when the inner cores of the stars due to their near mono atomic structure go through their internal current realignment (12, 18) this in turn leads to change in the direction of the gravitational field and thus the polarity of the whole star.

Consequently the rotation of the gravitational field which itself is originated and created magnetically interacts with the dynamic plasmatic magnetic energy field areas on its surface and in its atmosphere causing them to move in respect to the internal dynamic plasmatic magnetic energy field movements of the star.

Therefore main reason for sudden periodic increase in the movement of the plasmatic magnetic energy field on the surface of the star and sudden increase in the creation of black spot in their environment can be clearly be identified, to be due to the interaction of the dynamic plasmatic magnetic field created by the matters and mafs on the surface and the inner Magravs fields force of the stars.

Where, the inner dynamic plasmatic magnetic field of the star is by order of magnitude several millions of times much stronger than the isolated single or packages of dynamic plasmatic magnetic fields on the surface. Thus the stronger inner fields force of the star, dictating the direction of the motion of the weaker fields of the Dark spot. This being the very reason why the eleven-year cycle of change of polarity of the Sun brings about an increase in the number of the Dark spots of the surface on the Sun on regular bases. This being due to Sun's internal plasmatic magnetic energy fields' changes which brings about the polarity changes, every eleven years. Where, at these cycles there are more of these surface and atmospheric dynamic plasmatic magnetic energy fields in motion and available to interact with each other and the internal mafs of the Sun.

In fact, as the polarities of the Sun changes, so more dynamic plasmatic magnetic fields start moving from one pole to the other to accommodate the physical practicality of the plasmatic magnetic energy field polar change. Thus, a larger number of the dynamic plasmatic magnetic fields become to cross each other's path and consequently there are more chances of two or more dynamic plasmatic magnetic fields to meet and to balance out each other's field. Inevitably, as at these areas, there are no effective plasmatic magnetic energy fields for the charged matter to interact with, thus there is less light emission from these areas of the Sun. Henceforth the appearance of darker areas or dark spots in these areas on the same principle as the creation of the Black Hole phenomenon re-occurrence.

The increase in the number of dark spots of the surface of the Sun is always in sequence with the period when the Sun internal dynamic plasmatic magnetic fields activities go through their repositioning.

The number of these Dark spots increases and as they move, suddenly a vast number of dynamic plasmatic magnetic fields cancel each other out and as the change of polarity of the Sun completes itself and settles down.

The whole cycle of collapse of the Black hole re-occurs', that is, where a Dark Spot collapses, and their new plasmatic magnetic energy fields fines its total balance, and the matters which where gravitationally trapped under the influence of the dark spots, which are mainly plasmas, are retracted by the gravitational pull of the star and are ejected back onto the surface of the Sun is large quantities and numbers. This is the time, where there are massive activities and strong Sun flares scattering outwards from the surface of the Sun, where, large quantities of the Sun matters are plashed outward in the solar system.

Sometimes, as the mass of particles collected in a Dark Spot is pulled back into the surface of the Sun, due to their mass and speed, these become like meteorites hitting the surface of the Sun. This act causes more than usual charged particles to be leaving the Sun surface into surrounding space.

The darkness on the surface of the Sun is not due to what is commonly thought to be due to cooler temperature in these regions, as the Dark Spots are purely due to the fact that there are no or very little dynamic plasmatic magnetic fields available in these regions to interact with the charged particles to create light.

So underneath the Dark Spots on the surface of the Sun the temperature of the surface is still the same as the rest of its surface.

Conclusions

Black holes are natural physical by-products of the motion of forces and matters like every other object in the universe. The only difference for this body to appear is the fundamental shortage or total lack of one of the three main ingredients of the creation, namely the lack of the Passive Magnetic Force Fields in the region, where these black holes manifest themselves.

Black holes are another creation of universe like the uniqueness of the Blue planet and once one has understood the methods of universe's powers of creation within all its physical parameters, then every aspect of the appearance of objects and fields can only be explained with understanding of the interactions of these with each other.

The most beautiful part of this phenomenon will be! How Man will use this knowledge now for the advancement of its race?

Understanding of the method of creation, existence and the behaviour of the Black Hole in space opens new doors for the Man to plan his future excursions in space and the appropriate name for this object should not be a Black Hole.

These regions of Black hole in the galaxies cover areas as large as several solar systems, with them possessing all the physical attribute of solar system. With the difference that they do not shine due to the lack of appropriate dynamic plasmatic magnetic fields strength within their construction or during the time of their existence in the environment of their operation.

The appropriate name for this object as has one body and two distinctive characterizes behaviours and appearance, by first characteristic being a gigantic eating machine, and the second characteristic by allowing new systems to start from what it has digested. There is an old Aryan name for an arrow with two heads as the Black Hole with two characters and this object is called ZHUBEEN.

I call this unpredictable object in the galaxy with this name, as now it is a known object and not a mysterious scientific phenomenon.

Elaborations

The helio-seismology is the study of the internal structure and dynamic of the Sun using Sun-quakes, and the Sun oscillates continuously by varying degrees and directions. These oscillations are caused mainly by turbulent convection just below the surface. The data from spherical-symmetrical solar model of the same condition shows close correlation to physical collected data through inversion. This showing that the data simulation is close to the physical reality of what is happening in the inner sanctum of the Sun.

For our testes in dynamic cores and data's attained through them, it can be confirmed that the rotation and the turbulence have direct effect on the heating of the matter within the confined of the reactor build on the same principles, where in the reactor and consequently in the creation of the current through convection and magnetic fields production within it, where the turbulence of the matter in the core of the reactor creates the dynamic and the dynamo effects which this has a direct effect in and on the production of the dynamic plasmatic magnetic field in the reactor.

Turbulent convection and differential rotation in the Sun are thought to be the cause of the creation of the solar magnetic fields and the directions in which these magnetic fields appear to flow out of the surface of the Sun according to their direction of rotation their tightness are known as helicity of the magnetic field in the region. Where, Helicity simply describes the handedness of this field and as the field literally opens up like a cone as it moves away from the centre towards outer region. As Magnetic and Magravs helicity is in fact a measure of the knottiness and the twistedness of these fields within a region, where this closely related to the turbulent dynamo effect. Where, from all observation in the past, large-scale poloidal magnetic fields the helicity have a direct linkage with strong toroidal field leading to finite helicity.

As, in the reactor tested on the same bases as turbulence of the mafs of matters where the reactor cores having a finite parameters and the rotation and turbulence are predetermined, therefore the helicity of the magnetic fields has to be the same at different points but equal for all distance from the centre. Where, due to the small size of the core, a mean or average strength or tightness of the magnetic field could be assumed.

Thus a point of interaction of two magnetic forces in the cores will create condition similar to the dark spot on the surface of the plasma. Which if the collapse can go through plasma towards the boundary of the core, this can create a sudden surge of dynamic plasmatic magnetic field or which this can alter the system operation mode. The reason for writing this paper has been due to the fact that in the reactor designed, if the condition of Black Hole is created, this can lead to the shutdown of the system or unstable condition of the operation of reactor. As this has happened in two occasions during testing of the spherical core, where the second magnetic field was deliberately created and positioned to interact with the internal magnetic field created by the core.

In both cases the whole system did go through magnetic poles trying to bypass each other.

In the second test in trying to prove the point of the interaction of two magnetic fields and creation of black hole condition, the whole system was twisted and the axial pines of the core were off centred.

The core axels had to be realigned, but the damage to the core weld and axel proven to be too much to repair, and more or less this test of creation of black holes caused the loss of the first steel prototype core (Fig. 28).

At the same time in the same reactor the creation of the dark spots due to interaction of the matters were deliberately created for specific use of the system, where investigation in the creation of dark spots, and where the use of transition matter condition for the creation of dark matter, for the fuel needed for deep space travel was tested and confirmed.

This is how these above phenomenons clearly can be explained, and the principle for the creation of the Black Hole can easily be demonstrated.



Fig. 28 Test reactor

In the future papers the writer will explain how the Black Hole’s effects can be useful in helping to travel through galaxies and in the Universe. These are at this moment of time beyond understanding at the present level of scientific achievements.



Advancing
Astronomy and
Geophysics

ROYAL ASTRONOMICAL SOCIETY
Burlington House, Piccadilly
London W1J 0BQ, UK
T: 020 7734 4582/ 3307
F: 020 7494 0166
Info@ras.org.uk
www.ras.org.uk
Registered Charity 226545

Mr T. Keshe

7th July 2004

Dear Mr Keshe,

Thank you for your recent submission.

I am sorry but your paper is not in a suitable form to be considered for any of our journals and so I have placed it in the Society's library, where Fellows may read it. I have included your contact details so that they may approach you directly if they wish to comment.

I am sorry to disappoint you on this occasion but we cannot give your submission any further consideration.

Yours sincerely,

David Elliott
Executive Secretary

Fig. 29 . Letter of Royal Astronomical Society

CHAPTER 11

The relationship between gravity, mass and weight

© M.T. Keshe/The Keshe Foundation2004/2006. All rights reserved.
Author: Ing. Mehran Tavakoli Keshe
Date of release 21.12.2005
Date of Internet release: October 15, 2006

This paper is written for clarification by the encouragement from Mr Dirk Laureyssens.

Abstract

With the new understanding of the creation of the double dynamic plasmatic magnetic field of planets and understanding the new principle and method of the creation of gravitational forces, further on the balanced fields outcome of the collective and internal interaction of Magnetic and gravitational fields up on each other of any entity within the structure of mafs, plasmas, atoms or molecules this leads to creation of so called the mass effect of an object, it is now simple and apparent that what the mass is, how it is created and why the same mass possess different weights in different gravitational field forces environment.

Hypothesis

The mass of an entity is created from the outcome of the deduction of the interaction of the gravitational fields and Magnetic fields forces of an entity and has nothing to do with external field's interaction and strength of the environment of that entity. The variation in the numerical difference in the weight of the same mass of an object in different dynamic plasmatic Magravs field forces of different environments or different planets, is totally due to the interaction of the total collective dynamic plasmatic Magravs fields forces, including the inertia effect of the environment which the entity is weight measured and of the collective internal dynamic plasmatic Magravs fields strength of the mafs of the entity which create the mass of the objects upon each other.

Where, the magnetosphere of the same entity is the total sum of the magnetic field and gravitational field forces catchments zone of the same two internal fields which make the Mangroves fields of the entity that they can attain in their given Magravs fields strength environment.

Discussion

Planet like the Earth possesses a combination of two magnetic field forces. First the gravity, created due to the interaction of the two independent dynamic plasmatic magnetic fields in its centre cores upon each other. Second the inertia, which is the collective dynamic plasmatic magnetic field of its atoms and molecules of its constituent matters, which has the physical body of the planet.

Any object, this being plasma, an electron, an atom, a molecule or even a human body is created from a collection of the plasmatic magnetic Magravs energy fields of different strength and their continues interaction between and up on each other, which in total decides the total or collective magnetic field possessed by that object or the mass of an object and the total interaction within molecular or atomic dynamic plasmatic magnetic field of a given object is always constant irrespective of the other dynamic plasmatic magnetic field fields around it. The mass of an object has a collective package of plasmatic magnetic field tightness of all its constituent elements, and this will not change as long as the object is intact as one entity in its overall atomic or molecular or collective molecular appearance.

Which the interaction of the one object dynamic plasmatic magnetic fields with molecular or atomic magnetic field of another object Magravs in its vicinity or it environment will determine the weight of the two objects in respect to each other or in a given environment.

The mass of a body in relation to another molecular magnetic field, like gravity is dictated by the strength of the magnetic fields which creates the gravity, which in the planetary system like earth, this is maintained by the planet according to its inner molecular construction and conditions in and by which the Magravs strength of the planet manifest itself to the body.

The interaction between two or more dynamic plasmatic magnetic fields created by a planet to create and determine the gravitational strength of the planet are due to conditions and in conjunction with its elements.

Usually these types magnetic fields created by planets are very strong, so an object like a human body which possess a weaker collective dynamic plasmatic Magravs and in reality possesses its own gravitational field forces due to its combined electromagnetic fields of its elements which it is composed of, which for a given body this is constant, these will be attracted and be operating in a much more stronger dynamic plasmatic magnetic field environment of the planet. Which, this gives the body due to its interaction of the Magravs and the planet dynamic plasmatic Magravs interaction, where the strength of the Magravs force of the planet and the body in respect to each other, this determines the attraction force between the two fields of two entities of the body and the planet and consequently the mass of the weaker force or the object in respected to and within the stronger Magravs forces of planet or Magravs forces of the body dictated the weight of the body in respect to the planet.

In reality the reverse of the same criterion is true too, for the mass of the planet, and its weight in respect to the dynamic plasmatic magnetic field of the body.

Thus, it is easy to explain, when a body interacts with two planets of the same size and when the two planets are made of the same materials, where one for example has lower temperatures, or internal speed of rotation or lower rate of ionization of the prime materials within its Caroline core, which all these can affect the strength of the Magravs of the planet for it to possess a weaker dynamic plasmatic Magravs strength, then planet which has a more inertia power, which is of the weakest order than gravity, but always constant, for a planets like moons, then the magnetic attraction, or pulling, between the same object and the second

Magravs force will be weaker, this by the same principle as above giving the body in the second environment a lesser weight value.

This is the very essence, why man's body appears to have less mass on the moon than on the Earth. Where, this is simply due to the fact that the dynamic plasmatic Magravs of the moon, which creates its gravitational force, and even this could be the inertia effect of the moon, have weaker Magravs strength power to interact with same given human body's dynamic plasmatic Magravs than the Earth dynamic plasmatic Magravs strength on the same body.

Therefore, the weight of a body is position dependent in its relation to its counter interacting planet or object inner Magravs forces, which create the Magravs or/and the inertia, or static Magravs of atones of that planet.

That is to say, if one could replicate the same Magravs field as on the moon, within a given position in the Earth atmosphere, one will have the same weight as the body will have on the moon within the Magravs force of the Earth.

This is why in propulsion technology there is an absents of the Magravs within the system objects always float and have less mass, as first of all the propulsion systems do not create Magravs that the object can position itself in respective to and lock to the position that the object become motionally stable and this and the secondly for example in respect to the body of space users of the propulsion system, the body's collective dynamic plasmatic Magravs strength, has been positioned far enough away from and within the dynamic plasmatic - Magravs strength of the Earth, that the mass dynamic plasmatic magnetic field strength of body in that position within the Earth gravitational field, due to the speed of the rotation or motion and conditions created within of the craft, will have a weaker interaction upon the body, allow the body a more freedom of movement.

Using the principle of the Margrave positioning for vertical take-off or choosing stationery or fixed position orbit for an object, like for satellites, within any atmospheric condition, where the magnetic fields created within the reactor of a craft can lead to creation and control of the Magravs within the craft, allowing the mass of the body of the object in a given position within the atmosphere of the planet to reach the equilibrium in relation to the Magravs of the planet, then in that particular point within the fields that are created by the planet the body will have the same mass as the earth and the time delay lapse of free float satellites to tune with earth gravity become irrelevant and there will not be a need time delay or adjustment.

This is the fundamental principle and criterion for any system that is used in any spacecraft's technology to replace the present jet propulsion or rocket technology.

Therefore the mass of an object is the representation of the effect of the Magravs of a body in respect to the Magravs of the second body.

The Magravs positioning is the reason why atoms of the same element fuse to create molecules, as their weight in respect to each other is zero, or equilibrium, even thou they both possess the same mass.

At the same time, if this is understood in full, then most of the chemical and biological interaction of atoms to create molecules can be comprehended and replicated in an easier manner.

Where, the collective mass of atoms in respect to other atoms within a molecule Magravs will dictate the number of, position of and the composition of atoms of different elements within that molecule.

Then this explains why it is easier to create certain material in absence of gravity in space labs, that in the presence of lesser dynamic plasmatic Magravs strength of the planet in high altitude then only the weaker Magravs forces of the elements come in to play as they are in a much weaker dynamic plasmatic Magravs strength levels from the centre of the planet and they can combine to produce materials, which under Magravs forces of the Earth are impossible.

Conclusion

Therefore the mass of an object possess different numerical weight values in two different Magravs force environments purely due to the interaction of the double dynamic plasmatic magnetic field of the planet and the constant collective dynamic plasmatic Magravs of the object.

The gravity itself is created by the interaction of magnetic fields of the matter and as the mass is the product of interaction of gravitational force and Magnetic fields forces of the same matter magnetic fields based generated phenomenon and as any environment in the universe possess magnetic fields irrespective of their strength and interaction of these fields in that given environment creates a new Magnetic and gravitational fields or Magravs in that environment that the outcome the interaction the two Magravs of the matter and it environment become the weight of the matter in that environment.

That is to say the variation in weight of an object in different environments is totally due to the interaction between the dynamic plasmatic Magravs strength of the two of entities upon each other, in respect to each other's position, in their respective environment.

Where Magnetospheres of the entities are the outcome of the sum of the interaction of Magnetic fields and gravitational fields forces that the entity can master for it to be able to protect and hold on to all its mafs and matters which the difference field forces of the same Magnetic fields and gravitational or Magravs of the same entity has managed to attract and accumulate within its given environment.

In short the interaction of the two or more dynamic plasmatic magnetic fields lead to creation of Magnetic and gravitational field (Magravs) of the entity, and then the balance of interaction of the Magnetic and gravitational fields forces leads to creation of the mass of the same entity which the mass is entirely dependent on the strength of the two original magnetic fields of the entity, and then when the Magravs of entity interact with the Magravs of another entity which itself magnetic fields origin based, then difference or the influence of one Magravs of one entity in respect to the second entity Magravs make the weight of the two entities in respect to each other, where as much as the first entity has weight in respect to the Magravs of the second entity at the same time second entity has a weight in respect to the first entity too.

CHAPTER 12

Parallel worlds

Mysteries of existence about parallel worlds, the questions to ask are or can be as follows:

1. How do they become to exist?
2. How can we interact or be aware of their existence?
3. What can we do or have done to get there?

Let us consider the structure of simplest entity of plasma of an electron in overall structure of let say an atom of hydrogen (or atom of sodium which is part of piece of stone or metal, gas and etc.).

The plasma once created and maintained from interaction and down levelling in strength of different mafs of which this plasma in its division leads to creation of an atom which at this point the plasma of the electron of the atom has an independent existence from plasma of its proton and electron decides about its own motion and its own position in its environment in respect to its proton. Even though, this is conditioned on the position and strength of the proton of its atom. Where, electron itself is made up of collection of different magnetic fields strength and their interactions and as the electron of an atom is not aware of the its larger counterparts of proton(s) and other electron(s) in a larger elemental or molecular structures and it is not aware of any state of matter and at the same time that the electron is not aware of the part of heat and cold in its environment are playing in its position and motion in respect to its proton and other entities of the same which it is connect to.

Where, this electron physical appearance as any physical matter is dependent on its environmental condition. Where, let say this electron can be an electron of atom which is part of atoms of a piece of stone and at this point the electron is not aware of the existence of a stone in larger scale levels of its existence. But the electron exists within the existence of an atom, which the atom exist in existence of the stone.

But now let’s say the stone is parts of a salt stone grain which is consumed by an animal.

Now the sodium atom by making its Magravs available to protein of a cell of the animal it becomes and takes part in the bigger scale and larger Magravs of a protein chain connection, where sodium on its own could not achieve.

Let’s say that now the protein and in conjunction with sodium this creates the condition of neuro-connection and the cell becomes part of living being, this being part of neuro system a shrimp, dog or a man.

Where, for example the combination of different protein and different atoms and the interaction of their Magravs and balancing act within their mangroves lead to need for interaction and new balancing Magravs, where this new interaction of proteins and their different Magravs, leads to a need for cohesive and balancing line of magnetic fields line of transfer of fields. Where, an accumulation of different fields and Magravs and their interaction brings about feelings and intelligence and so forth in the animal.

Now as the different Magravs and their interaction takes place, this being in the level of an atom, a solid, protein, combination of proteins and their attachment to other atoms, these new entities create two distinctive levels of individual compacted fields one for their tangible state of existence and one they facilitates their fields and positioning for the use by and to other parts which are related to them but not connected to their existence in the line of communication of other atoms.

What this means, is that the entity gives life to existence of two levels, one is the physical tangible of itself and one is the fields and energy which it is part of, but once it is created the new entities has enough field that is an accumulation of the interaction of another interaction that this new entity does not need a physical entity to manifest itself in the tangible world, but the fields strength is sufficient enough that the new entity can easily exist on its own right in the universe and make decision about all others whom have become part of and operate through the new entity.

Now as the more and more fields and matters interact and creates a certain fields levels, that let say they lead to tangible matter existence of an entity, the accumulated physical matters have a parallel acuminated non tangible levels too which are its fields which allows it to be part of bigger entity.

Where in complexity of previous interactions to reach a point, these interactions have released or will release new complex fields that these fields perform and exist as the matter part do.

But sometimes the matter and associated fields interlocked, but exists and operate into different levels. Even though the tangible matter is aware of its own existence, but it is not aware of the existence of the associated counter interlocked fields within it, this be it the same as the plasma of electron of a piece of stone, which the electron is part of.

Thus now it becomes clear how a man has physical body and a soul. Where, the physical body is conditioned of the matter world and its environment, where the soul has no such a conditioning.

Thus the soul is aware of the existence of the physical body, but independent of its existence, but it receives the changes in the condition of the physical Magravs of the body.

Thus the soul of a man is a parallel world to the physical world of its associated plasmas, which has created it.

But as soul has no need for the physical body to sustain its existence once it is created, as it operates in a different field zone non tangibility, hence the physical body can die, but the soul will be left in tacked and carries on without its detached physical counterpart in the world of creation.

At the same time, the fields of the soul will carry-on with its interaction with other fields and Magravs of its own level and it will keep on attaining more and keep on and interacting as it physical counterpart did and combining with more and creating more the same and different.

The soul, itself is the balancer of the physical matter of the body, but from point of detachment, does not need the physical body for it to exist. As the physical interaction has led to its existence, but by now it is independent enough to carry on with its own operation.

This is like giving of a birth, even though the baby has been in need of the mother for it to start and become entity, up on the departure from the mothers body, the two entities can live two independent lives, without a need for each other existence.

Thus the soul of an entity, this being stone, animal or a man has the same method of operation and existence as any other matter or fields in the universe, and that as once it is established and sets its frame work, it does not need its physical counterpart which led to its existence.

Now one can understand how different levels of existence do operate and exist in conjunction and in parallel with each other.

Take this one step further and let say fields of the souls have established the same methods of interaction and communication as their physical counterpart plasmas of atoms did with each other and souls through their fields of existence interact with each other and lead to a more dynamic parallel non tangible world of existence in the dimension no need for the actually physical dimension of existence.

In the universe there creatures, which are made from the interaction of principle mafs and matters strength as man is made of matter mafs and matter fields strength and they can operate in a non-tangible level of existence rather than the physical tangibility to the eye of the man

This does not mean that they creatures do not have a soul or they are more intelligent than the man, but the only difference is that they operate in different mafs strength, which these lives can be strange to the mans' travels of the futures as they have the ability to transmute between different levels of mafs strength and be able to visible or detectable in their spectrum of mafs strengths

The soul of the man ids the like of the light from the star in distance universe, where the physical star could have been exploded and destroyed billions of years ago, but still at night the man observes the soul of the stars as the shining light in the dark of the night.

Parallel world exist even within the and during the life of the man himself, but they need the eye of the wisdom for the beings to see them and recognise them in their environment.

References

1 The book by M T Keshe (The universal order of creation of matters by M T Keshe)

2. The light Paper written and not yet published by M Keshe

3. The creation of Black hole By M T Keshe published in 2005

4. The production nano gans M T Keshe published in 2009

CHAPTER 13

The universal principle of division of pervious universe(s) and their decay leading to creation of new universe(s)

Written in 2009
© M T Keshe 2000-2010, All right reserved
ITNOGOG

In the universe there are always parallels due to the magnetic fields laws of interactions and hence there cannot be any deviations from these laws.

At the present the scientific world has been intrigued and encouraged to understand the phenomenon of the creation of this universe and scientists have tried to unravel the mysteries of the creation of this visible universe.

In fact the creation of this universe as is visible to the world of science, it cannot be any different than any other process in the world of creation and this universe has been created through the same principles as the rest of the magnetic plasmatic nuclear and atomic interactions, addition and division.

This meaning that the present universe is created though the same method as has been observes in the division of the neutron into electron and proton or smaller and/or bigger components of the same Matters.

Hence to follow the principle of the universal order of matters, this universe is created from the division of a larger universe that the man's visible universe is the smaller part of the division.

The reason for it being the part of a system is that in the present cosmological term, this universe is following the attraction of the bigger part and hence it is always in the motion to follow the Magravs of the bigger sister.

This being the reason why it looks as the universe is always expanding and as part of the universe has been noted to be collectively following different path of motion than the rest of the universe.

Where, the portion of the independent motion of the universe is the indicator that where the bigger portion of the division of the pervious universe is in respect to the man's universe. (Fig. 30).

It has to be said through the same principle of decay of neutron to plasma of electron and proton (1) and similarly as the decay of heavier atoms to two or more lighter atoms, the original universe through the same principle the mother universe of the man's universe, itself has been created and was created from the division of a larger universes through the same method decay and division during the time of the life of the unicos.

The difference in the universe's creation and decay is in principle merely the size and amount of the plasmatic field content plasma of each universe in comparison to plasma of electron or proton after nuclear decay and division of the neutron.


position of
sister universe
Indication of the position of sister universe
in respect to Man's Universe in the Unicos

Fig. 30 The position of the sister universe in respect to Man's Universe

Thus in fact our present universe itself is and was created some thirteen billion years back from the division of a larger universe. Hence every time as it is the same with division of the plasma of neutron to plasma of electron and proton, this division the new universe(s) will carries the characteristics of its mother universe, but due to reorganisation of magnetic field strength the new universe will have a new and fresh time, which this shows as the age of the new universe.

In fact this being the like of given birth to a child, where the age of the mother is irrelevant once the new seed of life is created and once the child is born, even though; the new child carries some of the same DNA fingerprint of the parents. The new life has its own cycle of life and its own timing.

Therefore the theory of Big Bang and M-11 as have been proposed in the recent past has no meaning and has no principle parallels in the physical world of creation of universe, a child or plasma of the proton or an electron. These two proposed principles are nothing, but showing the man's and scientific worlds lack of knowledge and ignorance of the real terms and parallel entities existence of all units in the universe.

In fact once the division is created and the universe is created the rest of the material and matter content and how they organise themselves in that universe is more or less follows the same principle as before and once the field are released within a given Magravs which the fields can created in interaction with each other, then the size of universe, galaxies, stars and planets and even creatures within that given Margraves strength of the newly produced universe are determined by the entity itself and without interference from its previous part.

Where, the new structure is dependent on the fields within the new universe and the internal motion of the new universe is internally determined by the total mass, which the interaction of the Magnetic fields and gravitational fields of the universe can master on its own.

Thus in fact in the bigger or smaller portion of the original mother universe which the man' universe is partly created of, in the bigger or smaller portion due to the larger mass the galaxies can be much larger in portion to the galaxies in this universe and conversely due to larger or smaller strength Magravs of the internal structure of the larger or smaller portion, the being's within these universes can be smaller or bigger or totally different in operation than the beings in this universe.

It has to be said that life in any form is not the exclusivity of the earth, if this is the mind-set of some men, thus this shows their lack of understanding of universe and how it is created, not the real truth and how matter's operated and function in the universe.

Therefore man is part of an inclusive pattern of field's motions in the universe and nothing more or less can be attached to the existence of the man.

The man in physical term is the entity and in the soul the connection of the field between himself and the other fields in the universe.

The physical body of the man is the like of the planet earth, where it has mass and its magnetosphere expands beyond its physical boy, but its total Magnetic fields and gravitational fields determines its position and relation in respect with other matters in the solar system and in a small way it determine the position of its star in its galaxy and souls which are created within it in their course their operation in the universe, as then the position of star determines in a small way the position of the milky-way in the universe and so forth.

Thus the soul of the man is the external connection of the operation of the physical body of the man in the universe, it is part of one and inclusive realty of interaction of the whole.

Thus the soul is part of the operation of the universe and every creation can extent the effects of its magnetic field to others which can affect their position and existence of any in possession of a soul.

Thus the soul, which is magnetic fields created and expands beyond the physical body of the man is not exclusivity of the creatures but it is the common denominator and common link between the man and other creatures of the God and has direct effect on the operation of the rest of the universe.

Therefore the man's body due to the interaction of its atoms protons and electron and neutrons magnetic fields, this object creates its own magnetosphere and its own mass and this body is and has to be in possession of magnetosphere which shows the working of the magnetic fields of its constituent matters and its subcomponents and fields this being including thoughts.

Where, in the physical worlds as the same as the solar system possess magnetosphere and so does the star and planet, then the body of the human through the same physical principle possesses the magnetosphere, which is so called aurora of the human's body. The field of the aurora are part of outer appearance as the soul of the man, but is fact the total effect of the internal interaction of all fields of the body which creates the Magnetic field and gravitational fields of the body and their interaction on each other which leads to the interaction with their fields in the universe, this overall output of the fields of the body of the man is the soul of the man.

Thus, all dynamic plasmatic matters in the universe possess a soul. But the man has the intelligence to allow the interaction of its soul with others; therefore through this principle the man is responsible for all his actions and he stands answerable to other souls in the universe. As he decides how these fields which partial and fully controlled through the Magravs of the matters of his brain, in how and what happens in its interaction with other souls effects their operation in the larger universe.

Hence man has to understand, that universe and others, which has the use of this universe all have been created from and the universe, which has been created from the division other universe and will be created from the division of this universe and in the future are all interconnected and operate through the same fundamental principle.

Therefore there are parallel universes to this universe, with the difference in the measure of their magnetic fields and strength and their position in their given environment.

Thus as we have the same and similar electrons structure's and protons structures in the same structure of an atom, which this structure of positioning of electrons and protons is the same for all known atoms, then the same applies to the universe too. This meaning that there are similar universe as this universe in the greater universe and other universe which this universe has been created from it and those that we will shell create through he operation of our souls and bodies mafs and matters.

It has to said that at the same time all beings in the universe use one and the same universal language of communication, where in the universe the common language is the basic plasmatic magnetic fields of basic field's. This is based on the first plasmatic magnetic field strength of existence of the simplest plasma of atom of the universe, and is similar to what we call in this universe neutron and its division and collections as atoms the like of the Hydrogen atom, which the mystery of this has been kept from the man and not apparent through his own misunderstanding of the operation of the universe.

This language is universal and once the man on earth understands this phenomenon and can fully measure the magnetic fields strength of the electron Magravs of it and he uses this as the base strength, then man will be able to understand and communicate with rest of soul possessing creatures of the universe.

Until then, the search in the sound waves to look and try to communicate with other creatures of the universe is a fantasy and shows the lack of his understanding of the world of the Creation by the man of ignorant intelligence.

Therefore the gravitation, magnetic, radiation and other similar properties and interactions of the field(s) on each other in this and other universe(s) decides on how and the way the creatures in the different universes and in the man's unicos and universe would look and behave.

But in essences they are all made of the same building block of *MAGNETIC FIELDS AND IN ITS AND THEIR INTERACTION OF DIFFERENT STRENGTH AND TIGHTNESS OF IT IN THEIR ENVIRONMENT*; This determining how tall and short and if one has eye or uses the interaction of fields to interact and communicates with other creatures of its environment, universe(s).

CHAPTER 14

How would it end?

The end of this universe will be the same as it started.

What this means is that as the magnetic field balances of the universe reduces to a level that the universe has to re-organize itself that it can keep its constituent field forces together, the whole universe will, like as with neutron plasma will decay and divide into two constituents of smaller universes, which these universes are still connected to each other through their original magnetic field forces (book 1 - chapter 17).

Hence this universe will be divided in to a smaller universe and larger universe parts of a set. This being the same process as the like of the process as neutron decays and the rest of the known nuclear decay of atoms do as there are no other known processes of division process in the universe, and there has to be uniformity in all dimensions of creation.

There is no end in the universes but conversion and amalgamation of fields and matters, which are created out of fields themselves.

Thus, this universe will divide into two active fully operational of lesser universe and bigger universe masses (fig. 31). But in total the overall balance of the matters and fields in both universes will be near equal of what was in this universe, with a little leakage of fields into the Universal Cosmos (unicos).



Fig 31. In time the decay of Man's Universe.

Where, the lesser mass part of the division of this universe will rotate around the larger mass universe. Where, the whole of the two new universes both will be rotating around larger universe mechanisms, which this universe on its own was rotating around.

Thus, if one is in the lesser universe, and looks into its motion, it looks as their universe is expanding, as they always seems that matters and fields in this universe to be running away from them as their universe is looking as being expanding.

Where, in fact being in the smaller universe, the gravitational field of the larger universe is continuously pulling or holding onto the lesser universe that the lesser universe stays within its orbit, as the electron does with its proton in atomic structure. As there can be no difference in all levels of creation of larger universe, as it is with the structure of decay of all atoms known to man.

Therefore this is how this universe was created and how future universe will be created out of this universe.

Thus there has never been a big bang, and there will never be a dooms day or the big rift. All it will happen is that this universe will go through a division, which is the norm in all-universal orders of creations.

The original universe has divided itself to smaller universes, which our universe is one of its offspring's and the same will happen over and over again to this universe and its offspring's.

Thus this universe is not the original universe, but part of a fraction of a fraction of fraction of a bigger picture.

May be now it can be understood that in the universe, as has been said that "I have made man in the image of myself" and now the reality of operation of different and all entities of the universe understood and are set in motion for the man to have the full understanding of method of creation and control and the way he has come to be on this planet at this moment in time and if he understood the purpose of his creation, then it can be said that:

The universe exists and operates within the structure of the man

and

the man exists and operates within the structure of universe

Definitions

Below is a list of the new terms and their definition that used in this book. A number of these words and terms have been used in the previous book and scientific papers, which have been published by the foundation and most readers, are familiar with these terms and reference. In this book a different approach and language and terminologies is used, therefore has become necessary to create a new terminology and words that can explain the real term application and processes in the world of physics.

Mafs: magnetic fields

Magnetic: with capital M refers to the plasma of magnetic fields created by a dynamic entity as for example this refers to the magnetic field of the earth.

Magravs: Magnetic and gravitational fields (Magnetic referring to the plasma of magnetic fields created by a dynamic entity as for example this refers to the magnetic field of the earth)

Pmf: plasmatic magnetic fields

Principal matter: This matter in conventional physics is called the anti-matter, as now the real structure of this matter is fully understood and is said to be source of all matters from the dark matter to matter, thus it has been called the original matter or the principal.

Principal mafs: These are magnetic fields, which are in the principal strength levels and considered to be I order magnitude several hundreds of times stronger than the magnetic fields which make up the tangible and visible matters.

Principal star: This entity in the conventional physics is called the Black hole

Transition energy: This energy in conventional physics is called the dark energy. This is the pmfs that are in motion from principal to matter magnetic fields strength so called the transition energy as energy is defined as the pmfs in motion.

Transition matter: This matter in conventional physics is called the Dark matter, as now the real structure of this matter is fully understood and is said to be when plasmatic magnetic fields are in transition state from the principal matter to tangible matter thus the term transition matter is used.

Transition mafs: These are magnetic fields which are in strength level between the principal and matter magnetic fields strength, and are in transit from the principal mafs to matter mafs strength levels.

Gans: a new state of matter; a molecule of a gas (GAs), which becomes Nano of itself and appears as Solid state of matter (Gas to Nano of Solid and to be called GANS for short).

The re-naming of matters and conditions

(*Advice: Skip this section unless you need to refresh or reading for the first time or read it after you have read the chapter 1, 2 and 3 as this section can be confusing and distracting you from the main body of the book*).

(Point of reference: The following section is and to be added to all disclosures for the ease of understanding as most of these have been disclosed in the book (1), and it is added here for the ones who have not read the book and are not familiar with terminologies in the works of the author).

In this literature, when using the term "**mafs**" for example in form of the antimatter mafs this means and refers to the magnetic fields (mafs) which this entity is made of and it is considered to be as a plasma of magnetic fields, and where the term "**antimatter**" is used on its own this meaning the physical tangible or detectable entity of the same. This usage of mafs similarly applies to physical matter and Dark matter too.

Further, the difference with Antimatter and matter is only in their plasmatic magnetic fields (**pmf**) strength and compactness of their fields. Thus, what is the magnetic fields (mafs) of antimatter they become magnetic fields of the matter as antimatter magnetic fields unwinds, loosens up, weaken in their field strength through their interaction with other magnetic fields and matters and become matter mafs and in plasmatic magnetic field strength of matter environment the matter mafs becomes tangible and become matter.

Therefore the antimatters are a more compact strength magnetic fields entities of the same of the magnetic fields of the matter, and due to their tightness of their fields, these magnetic fields of these mafs of matters they create stronger gravitational and Magnetic fields and hence they have stronger Magravs and hence upon their unwinding, they release magnetic fields and pmf which are faster, higher in strength and hence they look as to be strange strong and fascinating matters.

This means that antimatter entity of for example ten centimetres in diameter once ***unwinds*** in structure it becomes a matter of several thousands of meters in diameter entity in matter magnetic field strength environment.

Inevitably one should call the term antimatter the start matter and therefore antimatters should be renamed the Principal matter. Therefore there is nothing anti about these matters mafs and matters at their pmf strength as has been actually assumed in the world of science.

The ***Principal mafs matter*** itself has *different degrees of strength* by itself and *not all* magnetic fields of the Principal matters *have the same magnetic field strength*. Where, the principal mafs plasmatic magnetic fields strength has a spectrum of field's strength too.

As the magnetic fields of the principal mafs unwinds, it releases and loosen in its environment these magnetic fields (mafs) of the principal matters disperses into their environment, then they lose their strength through contact or interaction and friction with mafs' of matter and matters, and hence these principal mafs matters pmfs go for through magnetic fields strength of the Dark mafs matter strength first before through further reduction in strength, the dynamic pmf of mafs of the dark matter in motion reaches the pmf strength of the matter mafs level and hence becomes visible in matter pmf strength environment and becomes matter.

Now that the essence of existence of dark energy or dark matter can be explained in its realistic manner, and that is what has been called dark matter is in fact this is ***a magnetic field in transit from the principal mafs matter and matter strength to matter mafs strength and matter***.

Then as energy has been defined as “magnetic fields in motion” then the dark energy in fact is transition mafs matters in motion, or what is called the transition energy.

Then the dark energy can be called the Transition energy instead of the Dark energy, as the pmf in motion as this magnetic fields from the mafs strength of the principal matter in motion to reach to mafs strength of the matter level, this is only a Transition pmf condition, and transition mafs matter phase only.

Where, the interaction of mafs of transition matters with other of the same leads to and creates the Transition gravitational and Magnetic fields of their own or create what is called the Transition Magravs and in some cases this condition leads to creation the transition matter (dark matter) and consequently sometime interaction of mafs of transition energy leads to appearance and become transition matter (dark matter) in the cosmos.

Therefore, the magnetic fields strength, which makes the dark matter, is to be renamed as the mafs of the transition mafs matter and the dark matter as tangible matter becomes the transition matter, the dark energy to be renamed to transition energy.

The plasma of the principal mafs matters exists everywhere in the universe. This being in the centre of the universes, galaxies, stars, planets, plasma of proton and even in the centre of the plasma of the electron and in the lower order pmf strength environments which have been undetected up to now by man.

In reality in the centre of what is called a black hole in the universe, there exist and is the home of the principal mafs matters and principal matter. Therefore the black holes should be called the principal stars in the centre of galaxies, stars, plasma of protons and other entities like these.

The choice of the term star for principal centres of matters is correct as these principal matter concentration centres are like a star in the centre for the matter world like solar system, and the Principal stars are the place for the mafs of the Principal matters and the principal matters which their fields radiate outward into their surrounding as it does with the stars. Thus from this point on in this disclosure we call the black holes the Principal stars in the universe now that we understand the real source of their mafs of this matter(s) and its principal matters.

It can be understood now that where the intensity and the strength of stars and planets come partially from the existence of the principal mafs pmf strength, which has been released by the Principal, stars in the galaxies. This is to say that the seed of the pmf of the galaxies and matters needed for the creation of stars in principle are from pmf of the mafs of the Principal matter. Where, the interaction of the pmf of these mafs’ of the Principal matters leads to creation of initial strong Magnetic and gravitational fields needed for the creation and attraction of mafs of matters of plasmas of matters, the mafs of the transition matter and transition matters of the same region of the galaxies, plasma of stars, plasma of the proton and other entities of the same structure in the universe.
At the same time when using Magnetic with capital “M” this means the like of the Magnetic field of the earth, which itself is the plasmatic environment created by the interaction of at least two magnetic rays and indicates the outward flow of the magnetic fields from a plasmatic environment the like of the earth.

Similarly, when using magnetic field with small “m” this simply means the magnetic fields as in what we observe at the end of a solid magnet as magnetic fields of the object without its interaction with other fields.

Reference

1. Book 1, “The universal order of creation of the Matters”, M T Keshe, published July 2009
ISBN 978 46 6087 001 9

Book 2, “The structure of the Light” M T Keshe, published January 2011.
ISBN 978 94 6087 003 3

2. The unifying theory of the fields M T Keshe 2009

3. The origin of the Universe M T Keshe 2010

4. The creation of the solar systems M T Keshe 2010

5. The CO2 capture paper by MT Keshe Published 23.12.2009

6. “The universal order of existence” finalized and to be published in 2010-2011 by M T Keshe

7. The Magravs positioning M T Keshe 2010

8. NASA WMAP common.wikimedia.com

Published and unpublished works by M. T. Keshe

There are a number of unfinished articles that are to be converted to full disclosures when completed, like antimatter mafs method of energy releases, Nano space technology, relation between the creator and the created, space communication system, deep space defence technology, dynamic magnetic fields force regions (wormholes) construction and control, creation of magnetic fields, and so on.

Some of these works have already been published through different channels and some have not yet been released.

In the following section some of the works done by the same author are mentioned, with a brief disclosure of their contents.

Some of these papers can be purchased and obtained through direct request and access through specific links.

A number of papers with * and ** marks are not for public release due to their sensitivity of information and only available to relevant commercial and governmental organisations for peaceful applications of the technology.

The universal order of creation
(5.7.2006)

In this disclosure the main construction principles and the method of the link and control in the universal order of the existence of living cells, like the function and operational method of any matter based on so called proteins chains, as for example in human cell are explained in detail.

REF 9

The author considers this paper as one of his most important and fundamental works to be published and to be added to the sets of disclosures written by him.

Cosmic Rays
(Release date 24.3.2004)
This paper explains the source and the origin of cosmic rays and the way these work within our cosmos, their function and their benefits.

REF 10
----

*The Airborne reactor
(Release date 25.3.2004)

This paper covers the total design of airborne reactors for space technology. This covers all aspects of operation, design and control of such reactors.

REF 11

The seed of the Earth
(Release date 25.3.2004)

Some extracts from this paper:
The theory that the heat of the core of the Earth is due to inertia of the material piled on top of each other is completely dismissed through this new disclosure.

The author M T Keshe believes that this centre core is made of hydrogen, other gases and a mixture of liquid and solid matters mafs, which were in the vicinity of the centre of the core of the Earth at the time of its inception in the solar system.

Through this new understanding of the new inner cores of the planet, this brings to play the fact that the old inner-core of the Earth that is already assumed to be made of a solid piece itself becomes a sealed container for the new inner core.

The author through design of a parallel system has set to confirm the validity of this assumption, that the centre of the Earth possesses a semi- fusion atomic reactor and not a fission reactor as has been assumed by other scientists.

This theory of hydrogen in the centre of the planet is in line with the physical reality of the creation and the present situation in the physical construction of the solar system.

By the laws of physics all the gases in the solar system should have been in the giant gas planets at the outer layers of the solar system, like in Jupiter and Saturn.

The physical reality in the solar system is that the lightest of all these gasses, the Hydrogen, has taken its place right in the centre of the solar system in its star, the Sun.

It has to be recognised that the centre of all planets in possession of gravity due to the centre cores heating, are always in possession of two Magnetic Field Forces in their inner sanctum (M. T. Keshe “The creation of gravity").

In the case of the Earth up to now and with the present knowledge there has been acceptance of only one inner-core and one magnetic force.

As it is explained in the paper titled "the creation of gravity", there is an inner-core in the inner core. This inner core, due to it physical content, motion and position in the centre of the Earth, creates and maintains its own magnetic field force, independent of the magnetic force which has been known to be created by the interaction of the inner-core and the outer-core of the planet.

These two magnetic fields interact to create the planet's own double magnetic fields in its centre. The interaction of these two magnetic fields forces upon each other leads to the new concept of the "DOUBLE MAGNETIC FIELD EFFECT", where the interaction between these two field forces in the centre of the planet leads to the creation of the gravity and the magnetic forces of the planet (Paper: The creation of gravity).

This new second core is the seed core of the planet, the mother seed of the planet positioned in this new inner core.

REF 12

The creation of Black Hole

(Release date 25.3.2004)

In this paper it is explained that the Black Hole is created out of a natural sequence of events, and that the existence of the Black Hole in a galaxy is a normal event. Further it is explained that a Black hole is created in similar ways to the Dark Spots on the surface of the Sun. In this paper for the first time, it is explained how the Black Hole is physically created and what function it plays in its galaxy.

REF 13

Magnetosphere

(Release date 9.6.2004)

"The shape and the strength of the magnetosphere of a planet is exactly what a fingerprint is to a man. It is unique to each planet, star and galaxy. It is a tell-tale of all its attributes, and it reveals the hidden mysteries of the internal materials’ structure".

REF 14

Correction to the Einstein equation of Relativity

(Release date 15.6.2004)

In this paper the physical reality of the Einstein equation is considered, and efforts are made to bring this equation to the real conditions. Even Einstein considers this equation applicable for very small mass, and not in real three-dimensional multi-Magnetic and gravitational conditions, which are external and have nothing to do with the theoretical object's mass and speed, but have effect on the speed and the mass of the object under consideration.

REF 15

----

*Introduction to the new system
(Release date 2.7.2004)

In this paper it is written "It is essential to understand that, with the application of this system of motion, one cannot bring into play the solid, liquid and gas fuel method to create motion, as is used today. What is offered in this system is in simple words a fully integrated plasmatic magnetic energy system. Which, creates within and around the core environmental conditions as known to man in the universe like creation of gravity and magnetic field protection and the same as the magnetospheric protection condition of planets and motion through interaction of magnetic fields as planets and stars do in their given environment".

REF 16

The rings of Saturn
(Release date 2.7.2004)

One of the oldest puzzles in the world of astronomy has been the existence of the rings around Saturn. How did these rings come to exist the way they are now? How did they come to appear and behave the way they do? These questions and much more about the creation of these rings are all answered in this paper.

REF 17

The creation of gravity
(Release date 11.7.2004)

In this paper it is explained, "the source and the creator of the magnetic forces and the gravitational forces are due to the interaction between the same materials in the same region of the planet."

Further it is explained how the gravitational field force can be created, replicated and controlled within a nuclear reactor. Further it is explained how this property can be used for the motion of a system within a planetary or solar system.

Now by understanding the principle of the creation of gravity, in this paper it is further explained, "the gravity in reality is the effect of the interaction of two plasmatic magnetic fields of any two object in respect to each other."

REF 18

Death of a star
(Release date 26.7.2004)

In this paper the death of stars is explained, "The death of a star and the creation of a supernova is in reality the same as the half-life cycle energy step-down of an atom, with the difference that this show is in a larger scale, and more spectacular, in all aspects of its dimensions".

REF 19

Fusion
(Release date 28.7.2004)

In this paper the physical and scientific problems with present fusion technology is considered. Where, it is written, "nuclear Scientists, with the fusion reactors of today, are trying to create fusion in the opposite way to the known laws of physics and their parallels in the universe”. Further in this paper it is written, "If the present path for creation of fusion is followed, with the present scientific knowledge of physical materials for construction of such system, then following the present path of development to create energy from current fusion systems will be a distant dream".

REF 20

Life of a Cell
(Release date 28.11.2004)

Extracts from this paper; "The reality of the transportation and transmutation of a cell is not far from the reality of the life of an atom or a star. Where the life cycle of the cells are slightly more complicated, as they contain other matters mafs like acids, which have their own magnetic characteristic of their own chemical structure. For this reason the control and replication of the energy of the cell is very much complex, but very simple to achieve".

REF 21

The Atom
(Release date 19.12.2004)

The content of this paper explains how and where atoms in the universe are originated from and how the construction of atoms in a cold plasmatic nuclear reactor can be replicated.

REF 22

Magnetism
(Release date 8.1.2005)

In this paper it is written, "The question is where did the Magnetism come from? This is the Secret of creation. The world is made of one thing and only one thing and that is Magnetism. Its combination and interaction with its own different strength fields makes it appear as different matter mafs. The rest of creations are the outcome of these interactions of different strength of this thing called magnetism and the forces it creates. Magnetism is the origin of existence and the real singularity in its full meaning".

REF 23

----

*The creation of the magneto-gravitational force
(Release date 5.2.2005)

The creation of magneto-gravitational field force is and will be fundamentally independent of temperature and pressure, proviso to the fact that as long as a homogenous free floating pmf within a matter mafs is created.

REF 24

The core of the Earth

(Release date 20.4.2005)

One of the original assumptions in developing the new Magravs system some thirty years ago by M.T. Keshe was on the basis that the centre of the Earth possesses addition cores, which create the necessary gravitational conditions of the planet. After some twenty years of space technology and through Earthquake seismological data's this assumption has been shown to be correct and after over twenty years, it has been scientifically proven that the inner-core of the Earth has an inner-core of 600 km. Professor Guy Master in 2002 ref 24 nuclear planet. The centre of this core is assumed to have an inner-core of 8 Km, this he thought to be made of the plutonium or other nuclear materials

But the developer of this new plasma reactor technology has proven through physical dynamic cores that these cores possess a mixture of hydrogen plasmas and the process of the heating of the centre of the Earth are due to a semi-fusion chain of events.

REF 25

----

*The electron-atomic welding

(Release date 3.5.2005)

Some extracts from this paper:

"The electron atomic welding or atomic welding principle is the phenomenon that atoms of the same material, through a common shared electron, become a magnetically balanced molecule of the same matter mafs, with the difference that the shared electron will create a balanced pmf in the molecule".

REF 26

----

*Shutdown and safety of the reactor core

(Release date 6.6.2005)

In this paper the safety parameters in the operation of the gravitational and energy reactors are simply explained to avoid the loss of plasma and gravitational field forces created within its cores.

REF 27

----

*Reactor Start-up

(Release date 9.6.2005)

In this paper the systematic start-up of the dynamic reactors for the creation of gravitational field forces and the production of energy are set out. The start-up of these systems is totally different than the prior arts known in the nuclear industry.

REF 28

----

*The energy balance of the reactor
(Release date 29.6.2005)

Some extracts from this paper:
The energy balance of these types of reactors is not as simple as might look in the first instance. The energy creation is simple. But the heat leakage and dissipation through the deliberate inherent material design are and can be zero. That is to say the system not only can hold on the heat it creates. At the same time due to the close circuit feed operation will become self-sufficient but long lasting.

In planets, the loss of heat through their surface creates the variation in the central core condition over several billions of years. In this reactor as losses can be literally negligible, the system can operate at low energy loss temperatures. Even the boundary of the body could be made through the right combination of material in the chambers, so that the body of the reactor will be colder than its surrounding boundary. So the system will not only lose energy to its surrounding, but it can be made to absorb heat in the negative temperature gradient from its surrounding, so that there are no losses.

REF 29

Nuclear decay or half-life
(Release date 20.7.2005)

Extracts from the paper:
"The nuclear decay always has the same or near the same time duration. This is due to the fact that the all neutrons and protons, from their inception, carry a predetermined level of plasmatic magnetic energy. This energy is continually used for the motion and vibration of different elements of the nucleus in respect to each other and the surrounding matters mafs of the atom. As the space and dimensions of a nucleus of an atom always obeys the same principles of the magnetic separation and magnetic attraction. Protons or neutrons can and will need to use or consume the same energy before they become weak enough that the splitting or decay becomes a clockwork job. The nuclear decay is the natural levelling done of a nucleus' energy, due to the energy consumption and heat dissipation for the motion of the elements of the nucleus for its remaining plasmatic magnetic fields energy necessarily needed for them to hold one together".

REF 30
----

*The decontamination system
(Release date 10.10.2005)

"What this means is that, for example in trying to recycle the CO2, by the use of the right matter mafs in one of the cores of the reactor, the system will then use the O2 to produce H2O, in the form of pure water, and C in the form of atomic or molecular carbon, or even by feeding this back through certain operational compressions and gravitational interactions within a small core, to create industrial diamond or graphite, for different industries."

The use of the reactor for this purpose has been proven to be correct and Raman spectroscopy has proven the concept and physical reality of the separation of matter mafs in atomic level after separation in the same system from a composite matter mafs.
(See the graphene on the technology web site)

REF 31

The difference in atomic and molecular structure
under gravitational force and pressurised conditions.
(Release date 15.8.2005)

In this paper is written that "the atomic and molecular structure of matter mafs is totally aligned and positioned in a fundamentally different configuration where it has come together due to gravitational forces, than when matter mafs has been brought together by the means of pressure. This has a fundamental effect on the behaviour of the structure and properties of the matter mafs which is created in either way". Where this is explained and utilised to develop a new method in creating graphene and Sp3 atoms and walls in a simple core made of a coca- cola bottle.

REF 32

**The Defence and shielding system
(Release date 4.9.2005)

Some extract from this paper:
The design of the side open system for lunch of high saturation magnetic plasma package is one of the most effective technologies for defence of the reactor and the craft, which is in possession of such a system.

It is essential for any space technology in the open environment of the universe, if the craft is to keep a straight line of motion and to be able to protect itself from any solids or matters mafs in its path in the cosmos.

This technology can destroy any object by the principle of plasmatic magnetic energy saturation of the incoming object at a molecular level, that object will disintegrate in the form of magnetic vapour and not atomic level destruction, before matter mafs can damage the craft as debris, and before the craft ever becomes in touch or near these space matters mafs.

This technology can also be used to protect Earth from the collision risk of NEO's (Near Earth Objects), like comets and asteroids.

REF 33

Method of creation of an atom or nano matter mafs
(Release date 11.10.2005)

The manufacture of an atom of any density, this being of the simplest form of nucleus or a full atom of hydrogen, or even heavier elements in the universe, all follow the same principle.

Atoms are created in the soup of the cosmos from collections of very weak plasmatic magnetic fields, which for their existence cluster and share their energies with the magnetic fields that are not far from their own plasmatic magnetic field strength.

REF 34

The relationship between Gravity and Mass
(Release date 21.1.2006)

Extracts from text of this paper:
"A planet like Earth possesses a combination of both gravity and inertia. Where the gravity comes from the interaction of plasmatic magnetic fields from the processes within its core, and the inertia comes purely from the collection molecules pmf of matters mafs which has built the physical body of the planet.

Any object, being an electron, atom, molecule or even a human body, is a collection of plasmatic magnetic fields of different strengths and their interactions between each other, which in total decides the total or collective magnetic field possessed by that object where this is the mass of the object.

Where the mass of an object is a collective package of plasmatic magnetic field tightness of a given object and will not change as long as the object is intact as one entity in its overall atomic or molecular or collective molecular appearance.

Which plasmatic magnetic energy of a physical body (so called the mass of the body) in interaction with molecular or atomic magnetic field (this being gravitational or inertia) of another object will determine the weight of the two object in respect to each other in each other's environment".

REF 35

The Dark matter mafs
The Fifth state of matter mafs
(Release date 21.1.2006)

Extracts from text of this paper:

The existence of dark matter mafs is not questionable,

Proving its existence, and its effect on the energy balance of the universe, in all matters mafs as small as in the heart of an electron or in a solar system needs to be created, replicated and its effect measured.

The theory of dark matter mafs does not and needs not to be considered as complicated, if one understands in real terms the plasmatic magnetic energy of the matter mafs in the visible and invisible dimensions of the universal work.

The dark matter mafs has two distinctive characteristics, which makes it totally apart from the visible matter mafs. The dark matter mafs possess mass but not visible light, where its existence can only be determined by the weight of the it's hidden mass, which could be substantial due to its internal gravitational field.

REF 36
----

*The inter-atomic fusion
(Release date 3. 5. 2006)

Extract from this paper:
"The fusion of two or more atoms has been the pre-occupation of nuclear physicists for past years. Conditions to achieve fusion of two hydrogen plasmas in the TOKAMAK reactors have taken years to teach scientists a lot about the behaviour of plasma and their fusing.

The reality about the fusion in some way has to be reconsidered as, if the scientific world is trying to amalgamate the contents of two plasmas to release energy. There must be a simpler way to achieve releases of similar energies.

The fundamental principle of the inter-atomic fusion is a much simpler way to achieve fusion. If this principle is applied to the atomic condition of fusion, then fusion will be attained in a simple but in a much more physically realistic environment.

The explanation for inter- atomic fusion is very simple and direct.
In the fusion of two plasma of proton of hydrogen atom, the physicists try to fuse two large plasmas, and by doing so, they try to release a large amount of energy. Where in this process enormous amount of magnetic field forces and currents are needed to bring two plasmas in close proximity, so that the energy barriers in between them can be overcome for them to amalgamate or fuse.

In the inter-atomic fusion the overcoming of energy barriers does not exist, as in this method of fusion, the electron of the atom which is circulating the nucleus of the atom and is of the same origin will be encouraged to return into and fuse with the nucleus of its atom".

Where this is a more practical way to create and release manageable energies and there is no need for elaborate systems where even if the energy release will be small compared to dreamed up fusion systems of today.

With inter-atomic fusion method at least small and practical systems can be developed to handle low temperatures of the fusion process.

REF 37

The conductivity of the matter mafs in the vacuum of the interplanetary mediums

(Release date 21.1.2006)

Some extracts form this short paper "Therefore plasmatic magnetic field of elements within the interplanetary medium will cover the space given to them in their environment. Where due to their motion and their electric charges even in eV levels, they become perfect conductor, and in turn, due to their motion on their environment, they become plasmatic electromagnetic generators.

REF 38

The production of Graphene

(Release date 25.7.2006)

Repeated experiments and tests in simple static reactors, and tests in more complex dynamic reactors, prove that atomic separation and recombination of matter mafs like carbon and hydrogen can be reached at room temperature and at atmospheric conditions.

We have now indications - through static and dynamic tests in our reactors - that the universe was made in normal condition, which was originally nothing but packages of plasmatic magnetic fields of different strength, which were themselves nothing but areas of plasma or collections of loose magnetic fields energies. Where magnetic fields of different strength in locking to each other, by the principle of their plasmatic magnetic energy (PME), have caused in the first stage the creation of fundamental particles, secondly atoms, then molecules and then matter mafs, clouds and asteroids and then stars and galaxy's".

The Big Bang theory conditions have no room in the reality of the creation of the universe.

REF 39

Further works on medical research and developments have been written and completed, and will be published on the Foundation medical site in December of 2011

The process of the reversal of coma: Published in December 2010

Multiple Sclerosis: Published in December 2010

Epilepsy: Published in December 2010

Fibromyalgia: Published in December 2010

INTERNET LINKS

Web site: www.keshefoundation.com

YouTube Channel: http://www.youtube.com/user/keshefoundation

Forum: http://www.keshefoundation.com/forum/

Internet radio interviews:

Interview 06-09-2011 with Red Ice Creations (hour one):
http://www.redicecreations.com/radio/2011/06/RIR-110609.php

Interview 06-09-2011 with Red Ice Creations (hour two - need for simple registration):
http://www.redicecreations.com/radio/2011/06/RIR-110609.php

Interview 05-09-2011 radio interview with Alienshift:
http://www.livestream.com/alienshift/video?clipId=pla_8251665e-ac74-4d77-a785-443bbca65bf6

Interview 04-27-2011 with Mrs. Kim Greenhouse of Its RainmakingTime:
http://itsrainmakingtime.com/_radioshows/110427Keshe.mp3

Interview 04-20-2011 with Mr. Redneck Radioman of blogtalkradio.com:
http://www.blogtalkradio.com/paranormalpalace/2011/04/20/gravitational-technology-with-nuclear-scientist-mehran-keshe
----
Interview 04-17-2011 radio interview with Mrs. Aurora and Mr. Bill Alek of vortexnetworksnews.:
http://intalek.com/AV/VNN/VortexNetworkNewsHour/04-17-2011-VNN.mp3

Interview 04-09-2011 second radio interview with Mr. Bill Alek of vortexnetworksnews.:
http://intalek.com/AV/VNN/ProgressiveTechnologyHour/04-09-2011-Technology.mp3

Interview 04-02-2011 first radio interview with Mr. Bill Alek of vortexnetworksnews:
http://www.intalek.com/AV/VNN/ProgressiveTechnologyHour/04-02-2011-Technology.mp3

Interview 12-18-2009 radio interview with Mr. Allan Sterling of Peswiki:
http://www.mevio.com/episode/205187/fen-12-18-09-interview-with-mehran
----

LIST OF ILLUSTRATIONS.

FIG. 1. CREATION OF NEW UNIVERSES OUT OF THE DIVISION OF A LARGER UNIVERSE 16
THROUGH THE PROCESS OF DECAY SIMILAR TO THE DECAY OF THE NEUTRON IN PROTON AND ELECTRON. 16
FIG. 2. THE CREATION OF MAN'S UNIVERSE AFTER THE DECAY OF IT'S MOTHER UNIVERSE MAGRAVS' MAF'S...17
FIG. 3. THE UNICOS 19
FIG. 4 THE POSITION OF THE SISTER UNIVERSE IN RESPECT TO THE MAN'S UNIVERSE..20
FIG. 5 THE UNIVERSE HEAT DISTRIBUTION MAP (W-MAP OF THE UNIVERSE)...21
FIG. 6 THE MICROWAVE HEAT DISTRIBUTION OF THE UNIVERSE SHOWS A CONCENTRATED HEAT..........................22
IN THE CENTRE DISC OF THE UNIVERSE 22
FIG. 7 THE CONVERSION OF THE PLASMA OF NEUTRON TO PLASMAS OF THE PROTON AND THE ELECTRON. 24
THE SAME PROCESS IS CONSIDERED TO OCCUR WHEN THE UNIVERSE DIVIDES (3). 24
FIG.8 DECAY OF PLASMA OF NEUTRON IN PLASMA OF PROTON AND PLASMA OF ELECTRON. 24
FIG. 9. THE PRINCIPAL UNIVERSAL LINE OF MAF'S. 25
FIG. 10. THE PRINCIPAL MAF'S OF THE UNIVERSE. 25
FIG. 11. THE UNWINDING OF MAGRAVS IN AN ENTITY. 26
FIG. 12 PLASMA OF THE UNIVERSE: ANY ENTITY CAN BE CREATED ANYWHERE IN THE UNIVERSE AS LONG AS 27
THE APPROPRIATE MAF'S STRENGTH OF THAT ENTITY IS REACHED THROUGH REDUCTION OR INTERACTION OF MAF'S OF THE UNIVERSE 27
FIG. 13 PLASMA OF GALAXY: ANY ENTITY CAN BE CREATED ANYWHERE IN THE GALAXY AS LONG AS THE APPROPRIATE MAF'S STRENGTH 27
OF THAT ENTITY IS REACHED THROUGH REDUCTION OR INTERACTION OF MAF'S OF THE GALAXY ITSELF OR ITS UNIVERSE'S MAF'S 27
FIG. 14 PLASMA OF NEUTRON: ANY ENTITY CAN BE CREATED ANYWHERE IN THE NEUTRON AS LONG..................28
AS THE APPROPRIATE MAF'S STRENGTH OF THAT ENTITY IS REACHED THROUGH REDUCTION OR INTERACTION.....28
OF MAFS OF THE NEUTRON AND IT'S GALAXY ITSELF OR IT'S UNIVERSE'S MAF'S..28
FIG.15 GALAXY (SOURCE: HUBBLE)..29
FIG. 16. CONVERSION OF THE SPHERICAL PLASMA OF A NEUTRON IN A CYLINDRICAL RAY OF LIGHT. 31
FIG. 17 THE COLOUR OF RAINBOW ACCORDING TO THE MAN'S PMTICS STRENGTH IN EARTH MAGRAVS STRENGTH. 32
FIG. 18 (A TO G). THE PROCESS OF THE DIVISION OF THE MOTHER'S UNIVERSE IN TO MAN'S UNIVERSE 39
AND IT'S SISTER UNIVERSE 39
FIG. 19 THE PRINCIPAL LIGHT INSIDE A BLACK HOLE
48
FIG. 20 THE ABSORPTION OF MATTERS AND FIELDS BY PRINCIPAL STARS OF THE UNIVERSE OR GALAXIES. 49
50
FIG. 21 PRINCIPAL LIGHT IN THE CENTRE OF THE UNIVERSE..50
FIG. 22 ENVELOPE OF GALAXIES IN EACH UNIVERSE INDICATING THE POSITION OF THE SISTER UNIVERSE...........64
FIG. 23. SOME OF THE PROTOTYPES USED FOR CREATION OF MAGRAVS. 78
FIG. 24. THE STRUCTURE OF INNER CORES OF THE EARTH (12). 79
FIG. 25. EXISTENCE OF MINIMUM TWO SEPARATE MAGNETIC FIELDS IN TWO CORES OF EARTH.............................81
FIG. 26 INTERACTION OF TWO PLASMATIC ENERGY FIELDS CREATING THE EFFECT OF A BLACK HOLE. 94
FIG. 27. PLASMA OF PASSIVE MAGNETIC FIELDS PUSHING EACH OTHER CREATING 96
A BALANCED MAGNETIC FIELD REGION, CALLED BLACK HOLE 96
FIG. 28 TEST REACTOR 106
FIG. 29 . LETTER OF ROYAL ASTRONOMICAL SOCIETY...107
FIG. 30 THE POSITION OF THE SISTER UNIVERSE IN RESPECT TO MAN'S UNIVERSE 118
FIG 31. IN TIME THE DECAY OF MAN'S UNIVERSE. 121

INDEX

A

antimatter 127

B

black hole 128

C

centre of the Earth 134
CO2 135

D

dark matter 127

E

Earth 89, 90, 91, 92
energy 128

F

fusion 133, 137

G

gans 32, 125
Graphene 138
gravity 132

L

light barrier 31
light speed barrier 31

M

Mafs 125, 127
Magnetic 125
magnetic shielding 92
magnetism 133
Magravs 15, 16, 19, 21, 125
Magravs positioning 85
MPS 89

N

nano materials 32
Nuclear decay 135
nucleus 135

P

Pmf 125, 127
Principal mafs 125
Principal matter 125, 127
Principal star 125
PULM 24, 25, 27

R

rainbow 31

S

Saturn 132
shielding 136
solid magnet 72, 73, 82, 86, 88, 128
sound barrier 30
space technology 89
supernova 132

T

Transition energy 125, 128
Transition mafs 125
Transition Magravs 128
Transition matter 125

U

UMMS 89
unicos 16, 22
unisphere 22

THE ORIGIN OF THE UNIVERSE

M.T. KESHE

As we are helping with series of books which have been published and to be released, to build the full knowledge of the structure of the operation of the magnetic fields and their interactions in the world of creation for man to understand the entire process, one comes to the point that one has to explained different proportion of this entity in different levels of creation of the greater universe and not the man's universe. In the first book the creation of of matter, the operation and interaction of smaller fields, which leads to creation of matters was explained. In the second book we merely explained the method of travel of the collection of fields in the form of so called light. In this third book, it is further I have explained the operation and interaction of a bigger cells of the same fields, which these leads to creation of the mans universe and more and what is too much for the man to understand with his present scientific knowledge and he calls it his universe.

Where, the so called this universe in this book is explained itself is to be a part of natural process of creation and it has been created from the division of bigger quantities of fields and in time this universe will itself will be divided into and will create smaller universes or part of it will amalgamate with other universes and their fragments' to create bigger universes in the overall structure of the unicos, the universal cosmos.



Man's Universe within the Unicos (Universal Cosmos)

This process is being the like of the division of the plasma of the neutron to plasma of the electron and proton to create an atom and/or the fusion of two proton to create a heavier bodies of plasmas.

Thus this universe is not the centre of creation and itself is part of the bigger structure.

That is the same dilemma as man had as he tough the earth was the centre of the universe and as he understood more, he realised that he, his planet and himself are the smallest part of solar system and his solar system was in fact smaller part of a galaxy and so forth, and this is the same with operation and existence of the of the mans' universe in the bigger operation and structure of universes in the cosmos of universes: the Unicos.

The Keshe Foundation

The Keshe Foundation is an independent non-profit and a non-religious organization founded by nuclear engineer M.T. Keshe, aiming to bring new scientific knowledge and new technologies to mankind, and to bring new solutions for the major global problems, like famine, water shortage, shortage of electrical power supply, climate change, illnesses, by the use of new types of plasma reactors, and to give Man the real freedom to travel in Space.

90000 >
978-94-6087-000-2

The Keshe Foundation



BEARDEN

FER DE LANCE

BRIEFING ON SOVIET SCALAR
ELECTROMAGNETIC WEAPONS

FER DE LANCE

Lieutenant Colonel Thomas E. Bearden (U.S. Army, Retired) PhD, is the author of numerous books, papers, briefings, and presentations dealing with anomalous phenomena, scalar electromagnetics, free energy devices, Soviet Tesla weapons, and Soviet scalar electromagnetic weather warfare.

Lt. Col. Bearden was previously a senior scientist and department manager with the Alabama division of a major aerospace company where he directed the company's design and production of expert systems (artificial intelligence) applications for the U.S. Army command control systems. He has more than 29 years experience in air defense systems, tactics, and operations; technical intelligence; nuclear weapons employment; computerized wargames; anti-radiation missile countermeasures; and military systems requirements.

Bearden obtained a Master of Science degree in nuclear engineering from the Georgia Institute of Technology and a Bachelor of Science degree in Mathematics from Northeast Louisiana University. He is a graduate of the U.S. Army Command and General Staff College.

When Fer De Lance was originally written, Tom was a member of Mensa, Society for the Investigation of the Unexplained, International Tesla Society, American Association for the Advancement of Science, Association of American Physics Teachers, the Air Force Association, the Association of the U.S. Army, the American Nuclear Society, and the American Defense Preparedness Association. He is currently the Director of the Association of Distinguished American Scientists (ADAS), Fellow Emeritus of the Alpha Foundation's Institute for Advanced Study, and is CEO of CTEC, Inc.

In private life, Tom has two sons and two daughters, and lives in Huntsville, Alabama with his wife, Doris.

"...In 1999, the Earth's first strategic sub-space war
was silently fought and won..."

ISBN 0-9725146-1-9

Sweating done by red_gonzo.

Note: sometimes formatting of the text may be a little fuzzy. It's all because the OCR process didn't go as smoothly as I expected. Also there may be some errors inside text so be vigilant. In any case share this book, send emails to people about knowledge contained in it. Since this book talks about the most terrifying weapons present today the information in it is even more of value. But knowing an old saying »the knife cuts both ways« one can also use the same knowledge in order to heal ourselves since it seems that our body already does it using the physics described inside. Hopefully the latter will prove to be the most useful way to use this old but forgotten / supressed knowledge.

The contents include the 2002 update and the older 1986 briefing with slides.

TABLE OF CONTENTS

2002 OVERVIEW AND BACKGROUND........4

Mad Scramble of Soviet Science After the End of WWII........5

One Institute Had 2,000 PhDs and a Full Support Staff........7

Situation in the Early 1950s........8

1963 Deployment and Immediate Use of Scalar Interferometers........11

An Example of Russian Technology Astonishing Western Scientists........12

Softening of Metal at a Distance Was One Effect Used Against the Challenger 13

Energetics: Three Branches and a Strategic Deception Plan........14

Strategic Attacks Scheduled and Why We Were Not Destroyed........15

Attempts to Alert the Nation........18

The Responses........20

Effective Survival Treatment of Mass Casualties Could Be Developed........20

The Official Silence Was Deafening........22

The Long Dry Spell in Correcting Electrodynamics May Be Slowly Ending... 24

Engineerable Unified Field Theory Is Now Clearly Appearing........24

Examples of Some Major Non Sequiturs in Conventional Electrodynamics 25

Wide Confusion of Cause and Effect........26

CSRs: Engineering the Unobserved Causal Side To Create Functional Systems 27

Making the First CSR is Extremely Difficult; Making a Million Copies Is Easy 28

In 1999 The KGB Deployed Massive Numbers of CSRs for a Strategic Attack29

How the Asymmetrically Deployed Strategic Attack Was Stopped in Its Tracks 31

The Mostly-Ignored Time-Energy Interaction........32

Development of Threats and Scheduled Attacks Aborted........35

Live Destructive Tests Over and Near the U.S. Have Continued........38

The Scientific Basis For Energetics Weapons Is Established........39

Our Situation Here In the U.S. Is Precarious........39

The Dominant Weapons Are Quantum Potential Weapons 41
Cellular Time Reversal: Revolutionary Healing by a Team of French Scientists 43
Becker's Study of the Cellular Regeneration System 46
Need to Correct and Extend Classical Electrodynamics 48
The Situation Is Serious 48
A New Manhattan Project Is Warranted 49
2002 ENERGETICS WEAPONS THREAT TO THE U.S 51
The U.S. Narrowly Escaped Energetics Destruction Twice in 1997 51
Initiation of the Brazilian Energetics Weapon Program 52
Related Phenomena 54
Stalin *Personally* Initiated the Soviet Energetics Program with the Greatest Urgency 55
A Great Technical Breakthrough in Physics Can Always be Had in Four Years 55
A Typical Example: The Suppression of Cold Fusion 57
Revolutionary New Processes Are Hidden in the Cold Fusion Experimental Results 59
Stalin's Dictatorial Impact on Soviet Scientific Management's Response 62
Our Own Science Community's Progress During These Decades 63
U.S. Scientists Have Committed Monstrous Crimes and Gone Unpunished 66
Energetics: New Principles of Physics and How the Soviets Found Them 67
Longitudinal EM Wave Interferometry Energetics Was Almost Immediately Uncovered 68
By 1950 Russian Energetics Was Off and Running 69
Deployment of the Soviet Energetics Weapons and Their Quick Use 71
Why the Soviets Could Continue to Attack and Kill U.S. Targets with Impunity 73
The Science Behind the Soviet Energetics Weapons 77
The Importance of Scalar Photons and Time-Density Waves 80
Psychoenergetics: Engineering the Mind-Matter Interaction by Engineering Mind 81
Quantum Potential Weapons Are Utilized in All Three Energetics Branches... 84

The Importance of Longitudinal EM Waves 84
Energy, Wave Energy, and Wave Speed are All Dramatically Altered 86
A Process for Creating Longitudinal and Time-Density EM Waves 87
Quantum Potentials and Multiply Connected Spacetime 87
Need for Caution with QPs Used Against Biological Organisms 89
A Hypothetical Example 89
The QP Weapon Is a Superb Energy Amplifier "For Free" 91
Other Novel Uses of QP Weapons 93
The U.S. Narrowly Escaped Destruction Twice in 1997 Alone 95
Purpose of the Novel Attack on Captain Button 96
Rogue Japanese (Yakuza and Aum Shinrikyo) Have a Role 100
Inducing the Gulf War Disease 100
40-Years of Russian Induction of Diseases In U.S. Embassy Personnel 104
Western Electrodynamics Is in Sad Shape 105
Toward a Deeper Electrodynamics 108
Time Is Highly Compacted Energy 109
The New Transduction Model Explains the Cold Fusion Results and Mechanisms 109
Why There Is a Time Delay in the Onset of Cold Fusion Phenomena 1ll
The Early Soviet Longitudinal Wave Interferometers 112
Khrushchev Killed the Thresher to Prevent His Own Dismissal 112
Khrushchev Demonstrated the Powerful Blast Capability of Strategic Interferometry 114
Weather Engineering Over North America 115
Earthquakes to Order 117
Readying the Weapons for the 1985 Readiness Demonstration Tests 119
Meeting the 1985 Schedule for Readiness 121
KGB Crews Regularly Practiced Against U.S. Rocket Launches from Cape Canaveral 122
Kill of the Arrow DC: Practice Turned into Performance 123
The Arrow Pilot Sensed the Lack of Power, But the Aircraft Was Immediately Hit 124

Elements of the U.S. Government Deliberately Suppressed Vital Evidence... 125
Other Direct Energetics Signatures on the Arrow DC-8 126
Other Acts of War Completed the Milestone 127
Kill of the Titan Missile Over Vandenberg Air Force Base 128
Dead-Man Fuzing and Outside Assistance Deterred a Full Strategic Attack in 1986 129
What Really Happened in the Chernobyl Disaster 129
The High Side Risk Factor 131
The Low Side Risk Factor 132
Consequences of Not Taking Counterfire Action 132
My Recommendation to the Counterfire Group 132
The Group Fired and Took Out a Transmitter 133
Results at the Transmitter and at Chernobyl 133
Kill of the Challenger Included Use of Metal-Softening 135
Cold Molding: An Epilog to the Metal-Softening Donnybrook 136
Additional Update from Year 1998 to Year 2,000 Has Been Given 137
There is Also a Severe Bioenergetics (EM Biological Warfare) Threat 139
National Institute of Health Reaction 141
How the New Revolution in Medical Healing Works 142
What the French Researchers Showed 145
How the Regeneration Mechanism Was Finally Deciphered 147
Cellular and Body Rejuvenation are Possible, Once the Technology is Developed 149
How Many Americans Could Be Saved? 149
There Are No Resistant Strains to the New Technology, and There Cannot Be Any 150
Results of the Priore' Treatments Are Well-Documented and Independently Supported 151
The Present Threat Is Urgent, and Our Strategic Destruction is Still at Issue .151
Desperately Needed Defensive Capabilities Can be Provided by a QP Solution 152
In Conclusion 153

1986 FER DE LANCE INTRODUCTION & BRIEFING ON SOVIET SCALAR ELECTROMAGNETIC WEAPONS 157

Scalar Electromagnetics is Electrogravitation 157

Fer-de-Lance 157

Energetics and Directed-Energy Weapons (DEWs) 158

The Soviets Use a Deception Plan 158

Destruction of the Challenger in January 1986 161

Technological Surprise and a New Hiroshima 164

We Have Given Up Defense in the Larger Sense 164

1986—THE BRIEFING 167

Slide 001: Characterization 169

Slide 002: Outline 171

Slide 003: Elements of the Emerging Theory 172

Slide 004: Three Kinds of Electromagnetics 174

Slide 005: Bohm-Aharonov Effect 176

Slide 006: A-Field is Real 177

Slide 007: Quantum Non-Locality 179

Slide 008: Vector Mathematics has a Fundamental Problem 180

Slide 009: The Zero-Vector Axiom 182

Slide 010: Are These Systems Equal? 184

Slide 011: Infolded Systems are Excluded by Physics 185

Slide 012: Kaluza Geometry 186

Slide 013: A Potential is a Change in the Stress of Vacuum 187

Slide 014: Type of Potential Depends on the Particle(s) 190

Slide 015: A Potential Extends to Infinity & Involves the Entire Universe 192

Slide 016: A Natural Potential 194

Slide 017: An Artificial Potential 195

Slide 018: Producing an Artificial Potential 197

Slide 019: If No Observable Mass Flows: 199

Slide 020: Gravitational Potential: A Conglomerate of Stress Types 201

Slide 021: What Gravitational Field Is 202

Slide 022: EM Force Fields are Releases of Gravitational Potential via Observable Mass Flows 204

Slide 021: Scalar O-Wave Production 206

Slide 024: Scalar Electromagnetics 208

Slide 025: Rogers' Undersea & Underground Communications Systems 211

Slide 026: How does the Rogers System Work? 213

Slide 027: Scalar EM Waves are Emitted & Absorbed by the Nucleus 214

Slide 028: Nuclei of the Universe Continually Exchange Scalar EM Waves.. 216

Slide 029: Converting EM Field Energy to G-Field Energy & Vice-Versa 217

Slide 030: Normal EM Bleeds-Off G-Field 219

Slide 031: Scalar EM Forces 4-D G-Field 220

Slide 032: Detection of Electro-Gravitation 221

Slide 033: Scalar Wave Detector 226

Slide 034: Scalar Resonance 229

Slide 035: Scalar Resonance 231

Slide 036: Scalar Resonance Currents 234

Slide 037: Transverse Wave Interference 235

Slide 038: Transverse Wave Interference 236

Slide 039: Creating Energy at a Distance 239

Slide 040: Exothermic Mode (Scalar Interferometer) 240

Slide 041: Endothermic Mode (Scalar Interferometer) 242

Slide 042: Tesla's "Big Eye" for Remote Viewing 244

Slide 043: Site of Mystery Cloud 247

Slide 044: Mushroom Cloud from Sea off Japan near Russian Test Area 248

Slide 045: Mushroom Cloud Rising from Sea 249

Slide 046: Mushroom Cloud from Sea off Japan 251

Slide 047: Not a Known Natural Phenomenon 252

Slide 048: Explosive Events seen on Soviet Island 253

Slide 049: Explosive Events seen on Soviet Island 255

Slide 050: Explosive Events seen on Soviet Islands 256

Slide 051: Creating a Spatial 0-Field Pattern 257

Slide 052: Tesla Shield 258
Slide 053: Expanding Dome-like Phenomenon 260
Slide 054: Hemisphere & Globes 1977 261
Slide 055: Saryshagan Direction, September 1979 263
Slide 056: Continuous Tesla EMP Globe 266
Slide 057: Mysterious Light over North Pacific 268
Slide 058: White Sphere seen in North Atlantic 1976 269
Slide 059: Continuous Tesla Fireball 270
Slide 060: Terminal ABM System 272
Slide 062: ABM Defenses 275
Slide 063: Network of Virtual Transmitters 278
Slide 064: Network of Virtual Transmitters 281
Slide 065: Launch Phase ABM System 285
Slide 066: Soviet Command & Control Concept 287
Slide 067: Launch Phase ABM System (Anti-SLBM) 290
Slide 068: Detecting & Marking Missile Launch 291
Slide 069: Destroying the Launched Missiles 292
Slide 070: Shift to Anti-Sub Mode 293
Slide 071: Shifting to Earthquake Mode 295
Slide 072: Suppression Attack—MARVs (without defenses) 297
Slide 073: Suppression Attack—MARVs (with defenses) 298
Slide 074: Response to Counterforce Strike with No Defense 300
Slide 075: Response to Counterforce Strike with Defense 302
Slide 076: Clear Communications 305
Slide 077: Unique Communications 306
Slide 078: Mine Countermeasures—Orthodox System 308
Slide 079: Mine Countermeasures—Scalar EM Systems 309
Slide 080: Scalar Anti-Personnel Weapon 311
Slide 081 Afghanistan 312
Slide 082: Scalar Anti-Tank Weapon 314

Slide 083: Scalar Anti-Aircraft Weapon 315
Slide 084: Scalar Anti-Aircraft Weapon 316
Slide 085: An Effective Penetration Aid 318
Slide 086: Unique Capabilities: ATM/AD/AARTY 319
Slide 087: Unique Capabilities 320
Slide 088: Unique Capabilities 321
Slide 089: Unique Capabilities 322
Slide 090: Unique Capabilities: Penetrate Shielding 323
Slide 091: Multi-Purpose Weaponry 324
Slide 092: Multi-Purpose Weaponry 325
Slide 093: Multi-Purpose Weaponry 326
Slide 094: Unique Capabilities: Heat Extraction 327
Slide 095: Unique Capabilities: Cold Explosions 328
Slide 096: The Transmitter is the Major Weapon 330
Slide 097: Star Wars—The Final Frontier? 331
Slide 098: Comparison of EM Concepts (Chart) 333
Slide 099: Comparison of EM Concepts (Chart) 334
Slide 100: Comparison of EM Concepts (Chart) 335
Slide 101: Summary (1) 336
Slide 102: Summary (1) 337
Slide 103: Summary (2) 338
Slide 104: Summary (3) 339
Slide 105: Summary (4) 340
Slide 106: Soviet Defense Against Missiles 341
Slide 107: Surprise by Using Secret Weapons 342
Slide 108: Something Russia Doesn't Want the U.S. to Know 343
1986 SLIDE REFERENCES 344
1986 ADDITIONAL SLIDE NOTES 345
1986 APPENDIX I 371
SOME IMPORTANT INDICATORS AND DESTRUCTIVE TESTING.. 373

- INDICATORS AND SUCH 373
- FINAL DRESS REHEARSAL BEFORE THE BIG SHOW 384
- THE SHOW BEGINS 400
- MORE FRIGHTENING THAN THE MIND OF MAN HAS EVER IMAGINED 403
- SCALAR EM INOCULATION AND ITS IMPLICATIONS 408

1986 APPENDIX II 413

- COMPUTER WORMS AND VIRUSES, AND THE IMPACT OF SCALAR EM 415
- LARCENISTS 416
- ARSONISTS 418
- TERRORISM 419
- ANTIBODIES 419
- NATIONAL DEFENSE 419
- THE WEST'S VULNERABILITY 421
- CORE WARS REVISITED 424
- A COMMERCIAL WORM 424
- ADAM OSBORNE'S WARNING 425
- "NOW YOU'VE DONE IT!" 426
- TEEN CHALLENGE 427
- "PEOPLE ARE BASICALLY GOOD" 429
- FEDERAL FUNDS 430
- SCALAR EM INNOCULATION AND ITS IMPLICATIONS 431

1986 APPENDIX III 437

- CONTINUING THE SCENARIO 439

2002 TABLE OF FIGURES 443

2002 ENDNOTES 447

The Russians have sustained the largest weapons development program ever launched by any nation, and they have kept it effectively hidden from prying Western eyes. I have called this program "Fer-de-Lance," after the deadly South American pit viper of that name.

The dreaded fer-de-lance is a snake of great agility and lethal effect. It often ambushes its hapless prey, striking unexpectedly and without warning. Its first sudden strike is usually lethal to its victim, which promptly expires in writhing agony. Since the Soviet development of scalar EM weapons has been designed for the same purpose, the name seems appropriate.

2002

Overview[1] and Background of the Energetics[2] Weapons Threat

T. *E.* Bearden, Ph.D.
LTC, U.S. Army (Retired)
Director, ADAS

September 15, 1998
Update

Note: We have placed this update as a section in front of the original paper. This leads to some redundancy, which remains to insure clarity.

---

[1] This is an updated and slightly sanitized version of a paper originally prepared for and transmitted to selected Senators and Congresspersons.

[2] The present name of the old KGB is the Federal Security Services. The leopard's spots remain the same, regardless of its new name—at least for a die-hard old communist faction of it. Presently the helm of Russia has been turned over to a new Premier who has an extensive KGB background. However, Putin has chosen to differ from the traditional KGB outlook and seems intent on becoming America's trusted cheap oil partner and supplier, in a bid to help his economy and pump much-needed funds into it. His friendship with George Bush may be one of the turning **points** of this new century He at least has achieved sufficient control over much of the KGB to get on with trying to solve his economic problems and break the old "die-hard communist" mold a **bit**

2002 OVERVIEW AND BACKGROUND

For some time, Russia and several other nations have possessed highly advanced "extended-electromagnetics" *(energetics)* weapons of a very novel kind, using a dramatically extended electrodynamics theory {1}. To comprehend these weapons requires a combination of non-Abelian electrodynamics in at least the 0(3) gauge symmetry {2}, general relativity, Bohm's interpretation of quantum mechanics {3}, and the use of time-domain (scalar) energy, fields, and potentials to directly enter distant 3-spatial points without propagating energy through 3-space. It also requires correcting many of the serious errors in classical electrodynamics. Probably the most elegant and applicable extant model to deal with these phenomena and weapons is Sachs' {4} unification of general relativity and extended electrodynamics, particularly as implemented in O(3) electrodynamics. O(3) allows direct engineering by modified EM means.

Most of these energetics weapons are more advanced than what has previously been known to the U.S. military, intelligence, and scientific communities, although parts of the communities are finally making real progress in understanding such "revolutionary" areas. For example, every major weapons lab on earth seems to have discovered longitudinal EM waves and longitudinal EM wave weapons—the scalar interferometry we have been discussing for so long {5}. A major contributing factor holding back U.S. catch-up is that the flawed foundations of Maxwell's 1865 theory {6} have not been changed by the Western scientific community.

Historically, the scientific community exerts resistance to substantial innovation. Often 40 to 50 years are required to do what can be done with a concerted effort in four years. The Manhattan Project in WW II is a notable example of where the scientific community made a maximum effort and did a difficult job in four years. Also, "skunk works" efforts continue to be utilized for very rapid development when something really advanced is to be done and done quickly.

With the U.S. substantially behind in these "new" strategic superweapons, a new Manhattan Project would appear to be advisable and warranted. There are at least some indications that such may actually be going on at last. We hope the indications are true.

A sobering development that occurred early this year (2002) was China's deployment of both quantum potential (QP) weapons {7} and *negative energy* electromagnetic pulse (EMP) weapons (a type which we originally called the *MindSnapper* to disguise its true nature) {8,9}. The QP weapons are the dominant weapons on Earth today, followed closely by negative energy EMP weapons in second place. We have not been able to ascertain exactly how many nations have the negative energy EMP weapons, but it is at least five at the time of this writing.

The U.S. is still well behind in the use of special "engines" (special curvatures of spacetime and their dynamics, but achieved with higher group symmetry electrodynamics) for directly engineering the mind itself, and for producing *nonmaterial* robot systems made totally of such engines—"causal system robots" which we will mention later. Several of the Western nations do accomplish work in the mind control area, but use a sort of "brute force" method oriented on frequency and frequency changes, etc. where the true active mode is the unsuspected transformations of the U(1) electrodynamics to a higher group symmetry unified field theory electrodynamics, accomplished by the human body tissues and structures themselves.

Western scientists have not realized that all EM energy in 3-space actually comes from the time domain *to* each point in 3-space and *returns from* that 3-space point back to the time domain.[3] Hence "propagation" of 3-space EM energy is actually the propagation of a "circulation" of EM energy between the time domain and 3-space, involving each 3-space point presently said to be "occupied" by the energy. Unfortunately, Western science is still unaware that *no observable exists in time,* a priori, since by definition it has no extension in the time dimension at all {10}. Instead, an observable *continually recurs* as a frozen 3-space snapshot of an ongoing dynamic 4-space interaction, due to the continual repetition of the observation process which is the application of a *d/dt* operator to the ongoing 4-interaction. Hence, we "see" physical reality (3-space reality) similarly to the way we view a "motion picture" series of successive frozen frames. The major result of this flaw (mistaking a 3-space observable as a 4-spatial cause) in Western science is that Western science still extensively substitutes effect for cause—e.g., in the notion of a separate 3-force acting on a separate 3-mass. No such situation exists in nature, and nothing "moves" or "changes" in 3-space alone. For an entity to exist in time, it requires at least 4-space because a time length is required. Nonetheless, the West is making progress. If some of its scientific dogma can be overcome, the younger scientists will break free and readily do the job required for the defense of this nation.

Mad Scramble of Soviet Science After the End of WWII

During WW II the West produced a great technical breakthrough and obtained the atom bomb as a decisive new weapon. While speeding up his own atomic

---

[3] Specifically, energy comes from the time domain to the negative 3-charge, thence to the positive 3-charge, thence back to the time domain in a *4-circulation* of EM energy. With extra energy *appearing* and present at the negative charge due to entering 3-space there, and with less energy present at the positive charge due to the energy *leaving* 3-space there, there is a delta in energy density (pressure) across a dipolarity, oriented from negative to positive. That is the exact basis of the T. T. Brown unilateral thrust force, and the force used in the "lifters" experiments today. To calculate the **force, th**e long-unaccounted Heaviside energy flow component must also be accounted— not just the weak Poynting flow component.

weapons program[4] as a result, Stalin also ordered his own Academy of Sciences to quickly derive the next great new technical breakthrough, and he held the top scientific leaders themselves personally accountable to him, to see that it was done at all speed (Figure 1).


The Communists starved millions of Russian Kulaks to collectivize Soviet farming
Assembled Academy
Stalin

"The destiny of communism has been frustrated by the U S development of the atomic bomb That is not the last great technical breakthrough The next one WILL be Soviet! You will provide me with that great new technical breakthrough at all speed, or I will have your heads Do I make myself dear, comrades?"

Figure 1 Stalin's dictum removed any resistance from his scientific community.

Simply put, Stalin placed the heads of the Soviet scientific leaders on the chopping block, since he was an absolute dictator and often killed or imprisoned those who opposed his instructions. To survive, the leaders of the Soviet Academy had to demand the utmost of their subordinates, because they themselves had to report their progress or lack of it to a dictator who would and did take swift action if they did not produce results. Thus, Stalin simply bypassed the usual scientific posturing and protracted delay so typical of our Western scientific bureaucracies.[5] If the Directors of the Russian scientific community dragged their feet and did not push his desired program to the limit, their heads would roll—and some did.

---

[4] At the Potsdam conference, after Truman informed him the U.S. had just exploded a great new explosive weapon, Stalin secretly called the head of his nuclear weapons program and ordered him to accelerate the Soviet nuclear weapons program.

[5] As a simple example, the U.S. National Academy of Sciences, National Research Council, National Academy of Engineering, and the National Science Foundation—and all the electrical engineering departments at all the universities in the U.S.—have not yet recognized that all EM circuits and systems are in fact powered by EM energy extracted directly from the seething local vacuum by the source charges and dipoles in the circuit or system, and particularly by the broken symmetry of the source dipole in the generator or other primary power source. They also have not yet solved the more than a century-old source charge problem, but continue to support engineering models assuming that the charge *freely creates* real EM energy out of nothing at all, in total violation of the conservation of energy law, and pours that created energy out, freely and continuously, to establish its associated fields and potentials and their energy reaching across the universe. The agencies thus unwittingly advocate perpetual motion machines on a scale unparalleled in history. They continue to support an electrical engineering model and a classical

As a result of Stalin's forceful intervention, the entire Soviet scientific community was galvanized into a most intensive review of all of physics. The scientists desperately sought to quickly uncover potential breakthrough areas that could be developed into the great leap forward that Stalin demanded. They had to have progress, and they had to have it rapidly.

One Institute Had 2,000 PhDs and a Full Support Staff

Large review institutions were quickly set up, staffed with the best Soviet scientists and support translators and teams. One such search institute involved some 2,000 Ph.Ds along with their support staffs. Soviet ships brought in shiploads of copies of all the scientific journals of the West—from the beginning—, and they were reviewed paper-by-paper, page-by-page. Anything novel and implying new scientific possibilities, or anything that had not been adequately followed up, was laid aside in a "select" pile for further review and decision by the best Soviet theoreticians available {11}.

One gets a new physics by discovering shortcomings and flaws in the old one. This intensive Russian search almost immediately uncovered the deep flaws in classical electrodynamics—flaws that have been propagated throughout most other branches of science. Classical electrodynamics (and electrical engineering) is particularly beset by hoary flawed foundations problems, dating from at least 1865. As an example, the equations did and still do assume a material ether, and they have since the beginning! Not a single equation was changed when the

electrodynamics model which *do not even model* the active vacuum and its exchange with every charge, much less a *broken symmetry* in that exchange. So none of those agencies even knows what powers an electrical circuit, 45 years after the proof of broken symmetry was accomplished by Wu and her colleagues in 1957, and the Nobel Prize was then quickly awarded to Lee and Yang *the very same year* (1957) for predicting that broken symmetry revolution. In the modern view a charge is a dipolarity, when its vacuum interaction is considered. As a dipolarity, every charge exhibits the proven asymmetry of opposite charges, in its interaction with the active vacuum. The charge thus extracts and outpours real observable EM energy from the vacuum, freely and continuously, and it exhibits COP = oo. Those agencies—along with nearly all the rest of the U.S. scientific community—still naively assume that a COP>1.0 EM system (i) is impossible, (ii) is against the laws of nature, and (iii) is a forbidden perpetual motion machine. In nearly half a century since the discovery of the broken symmetry of opposite charges, those agencies have yet to apply that finding to electrical engineering and engineering curricula. Frankly, since they have dragged their collective feet for nearly a half century on extracting EM energy from the vacuum, what is needed is a Stalin to put his iron boot firmly to their posteriors and call their attention to it in language they cannot ignore. *The pollution of the planet for energy purposes and the imminent oil and energy wars that will ravish the earth are directly due (i) to this inexplicable dogma upheld by the scientific community and (ii) to the community's continued falsehoods equating EM COP>1.0 to perpetual motion machines.* The continuing failure to **incorporate** the **active vactnun** exchange—and its broken symmetry—into electrical engineering and classical **electromagetics a**lso poses an unacceptable threat to the continued survival of this nation.

Michelson-Morley experiments in the 1880s destroyed the material ether itself. The classical EM model also assumes a flat local spacetime (falsified by general relativity since 1915) and an inert vacuum (falsified in particle physics for several decades). It still assumes the same EM field in mass-free space as exists in mass—a non sequitur of major impact. Just to make the Maxwell-Heaviside equations easier to solve and avoid numerical methods, the *totally arbitrary* Lorentz symmetrical regauging[6] discards all EM systems far from equilibrium with their active vacuum environment. In fact, there is no "active vacuum environment" in the model, much less a broken symmetry in that exchange. Yet that very broken symmetry is exhibited by every charge and dipole {12}, and thus by every EM circuit and system. That asymmetry is involved in the continuously increasing giant negentropy poured out by every charge in the universe, thereby generating all EM fields and potentials and their energy, eventually reaching even across the universe, *and with perfect macroscopic order and time duration as long as one wishes*. Indeed, all electrodynamics is in total violation of the second law of thermodynamics, to any *macroscopic* size level and time duration desired.[7]

The terribly flawed electrodynamics model was completely overhauled by the Russian scientists *very* quickly, and the work was accomplished by some of the best nonlinear scientists in the world. Already present at the time were many things available to assist in dramatically extending {13} the hoary 1865 Maxwellian electrodynamics {6}. Gauge field theory was available since the turn of the 20th century, and the top theoreticians could readily see that something more than Abelian electrodynamics was firmly required in particle physics. The Yang-Mills {14} theory met that need in 1954 by originating non-Abelian gauge theory.

Situation in the Early 1950s

By 1950, Stalin's scientists had the beginnings of what they dubbed "energetics" {15,16}, which we would dub an "engineerable unified field theory" {17,18,19}. Longitudinal EM waves were primary {20,5} in that more fundamental approach. By the mid 1950s, one can pick out of the open literature {21} increasing incidences of prototype Russian energetics weapon testing around the world. In 1960, Khrushchev {22} spoke obliquely of these "fantastic new weapons" that were "just within the portfolio of the Soviet scientists," so to speak. Commercial aircraft sightings (Figure 2) and the reports of their captains and crews are also a particularly significant source of sightings of Russian energetics weapons tests, as are sightings by ships' crews (Figure 3) and ground observers (Figure 4).

---

[6] Actually a version of this symmetrical regauging was first performed by Ludwig Valentin Lorenz, "Ueberr die Identitat der Schwingungen des Lichts mit den elektrischen Stromen," *Ann. Phys. Chem.*, Vol. 131, 1867, p. 243-263—only two years after Maxwell published his seminal theory in 1865. The paper is also published in English, as Ludwig Valentin Lorenz, "On the identity of the vibrations of light with electrical currents," *Phil. Mag.*, Ser. 4, Vol. 34, 1867, p. 287-301. Unfortunately not much attention was paid to Lorenz's effort, since he independently derived electrodynamics. Decades later, when H. A. Lorentz also published symmetrical regauging of the Maxwell-Heaviside equations, he was given credit for it with no further mention of Lorenz. A proper historical summary of this has been given by J. D. Jackson and L. B. Okun, "Historical roots of gauge invariance," *Rev. Mod. Phys.*, Vol. 73, July 2001, p. 663-680. This is an excellent coverage of the history of who actually did what and when, and who got credit for it.

[7] This dramatically extends the size regions (microscopic through colloidal) and the time durations (momentary to two seconds) where the second law is known and proven not to necessarily apply.


18-27 km diameter
Asahi Evening News, Tokyo
June 22, 1982
Multiple tests seen per month, for years.
Pilots simply ceased reporting them.

Figure 2 Typical shield test, northern route to Japan, seen by passing airliner.


Mar. 20, 1969
Caribbean and Western North Atlantic
MOON
• Semicircle
• Milky white light
• Small, intense at first
• Dimmed as enlarged
• Grew to enormous size
• Lasted 10 minutes, then faded
50 degrees
70 degrees
Marine Observer 40:17, 1970

Figure 3 Giant missile shield test seen by passing ship's crew.


Missile Shield at Sary Shagan
London Sunday Times, 17 Aug 80
Sept. 1979
Seen twice from Afghanistan
20°
Toward Sary Shagan Missile Test Range over 100 miles away

Figure 4 Nick Downie's sighting from the ground of distant Soviet missile shield tests.

1963 Deployment and Immediate Use of Scalar Interferometers

The first huge scalar potential interferometers {23,24} of strategic range and power (Figure 5) were deployed by the Soviets in 1963, and one was used to kill the U.S.S. Thresher nuclear attack submarine (Figure 6), leaving clearly recognizable signatures {25}.

Since 1963, the Russians have had the equivalent of more than seven additional Manhattan Projects (using the Russian 5-year program instead of the 4-year Manhattan Project), back-to-back, in development of energetics weaponry. The energetics weapons have never been given to the regular Russian forces. Instead, all research, production, siting, manning, and employment are by the KGB and still under ruthless KGB control by die-hard communist factions {26}.


XMTR
BEAM OF LONGITUDINAL EM WAVES
• Energy effect in distant zone may be either heating or cooling, and slow (rising) or fast (explosive).
• Specific patterns of local spacetime curvature and dynamics (engines) may also be produced.
• Beams easily pass through Earth or ocean.
INTERFERENCE ZONE
BEAM OF LONGITUDINAL EM WAVES
XMTR

Figure 5 Scalar (longitudinal EM wave) interferometer.


APRIL 1963
© Hal Crawford 1978.
Used by permission.

Figure 6 Kill of the U.S.S. Thresher. With her controls jammed, the hull of the doomed submarine implodes when she reaches crush depth

An Example of Russian Technology Astonishing Western Scientists

Some years ago, coordinating with a Western but non-US aerospace firm, I furnished the firm with the names and addresses of some Russian scientists in Moscow, since it was clear from their internet site that the scientists were on the fringes of the KGB energetics weapons program. An excellent European engineer fluent in Russian was sent in, several times. Several unusual things were demonstrated to him, including (i) transmitting enormous energy down a very thin wire, and (ii) cold molding, or turning metal into a liquid at room temperature, pouring it into a mold, and then letting it sit and harden. All without heating.

The engineer also closely questioned the Russian scientists about Russian . energetics weaponry, a subject the scientists were most reluctant to discuss. Finally they admitted the energetics weapons existed, and they actually obtained a meeting between the engineer and the KGB General who had directed the Soviet energetics weapon program for more than 20 years. In the meeting, the General coldly admitted the weapons, stated that "Of course you are not going to be allowed to see *those!"* and confirmed that somehow the Russians obtained everything the present author writes, as soon as he writes it {27}.

The engineer then brought the Russian scientists to his aerospace firm in that Western nation, where the scientists demonstrated cold molding to assembled scientists and some U.S. personnel. I forwarded a written explanation to the Western scientists of how the cold molding was performed technically. Later, on calling the engineer again, I discovered that the foreign authorities of that country had suddenly classified everything over there, and the engineer could no longer even talk to me without filing a Foreign Intelligence Contact Report. My own part in all this was completely open-source, pro bono, and I had already written of it openly and publicly.

Softening of Metal at a Distance Was One Effect Used Against the Challenger

At any rate, earlier I had openly advanced (and printed) the same mechanism, since it was the metal softening mechanism used by the KGB to kill the U.S. Challenger spacecraft in 1986. Publicly I had been resoundingly called a lunatic for advancing such a "preposterous" thesis. Nonetheless, metal softening by a distant LWI (longitudinal wave interferometer) was definitely utilized as part of the kill of the Challenger, as a close colleague here in the U.S. proved *experimentally,* detecting and demonstrating that metal-softening Russian signal prior to the kill of the Challenger. He amplified the signal and demonstrated on the bench its nearly instant softening of nails, rendering the nails momentarily as limp as wet noodles (Figure 7). Nails from the same box, not exposed to the signal, remained hard and could be hammered into a board. Not so the nails from the box that were exposed to the amplified Soviet signal! Those nails folded up like a wet noodle when tapped with a hammer, and could not be driven into a board.

Working unpaid with the foreign scientists, we had in fact obtained the "smoking gun" proving that this cold molding capability rigorously existed in the KGB inventory. Further, it had existed so long that the KGB had essentially *declassified* it so that the civilian Russian scientists seeking employment funds from the West could utilize it.



Figure 7 Proof of metal-softening signal: Golden softens nails with amplified Woodpecker signal.

Energetics: Three Branches and a Strategic Deception Plan

The *energetics* weapons use exotic polarizations of EM waves, quantum potentials, and the "infolded" LW electrodynamics (both scalar and longitudinal photons) inside and comprising every "ordinary" transverse EM field and wave. The KGB energetic weapons are categorized (Figure 8) according to what they are targeted against:

(1) against inert matter, fields, and potentials etc., that branch of weapons is called by the same name, *energetics* weapons.

(2) Against living tissue, bodies, cells, biofields, biopotentials, etc., they are known as *bioenergetic* weapons. Disease-induction electrodynamics such as used to irradiate the U.S. Embassy in Moscow are examples of bioenergetic weapons.

(3) Against the mind, thought, memory, behavior, and the mind-body coupling mechanism, they are known as *psychoenergetic* weapons. Particularly in the latter mode, these weapons also use time-polarized (scalar) EM waves and time-polarized (scalar) photons as well {28}.


NONLIVING SYSTEMS
Energetics
• Nonliving systems
• Scalar Interferometry
• Action-at-a-Distance
• Quantum Potential
• Vacuum Engines
• Spacetime Structuring
• Material, Field Effects
• Nuclei, Lattice Changes
• Hidden EM Variables
• SWZ Effects
LIVING SYSTEMS
Bioenergetics
• Living Systems (Bodies)
• Cells, cellular changes
• Master Cell Control (Popp)
• Spacetime Structuring
• Disease Induction, Remission
• Action-at-a-Distance
• Quantum Potentials
• Scalar Interferometry
• Hidden EM Variables
• SWZ Effects
Psychoenergetics
• Living Systems (Minds)
• Thoughts, Memories, Emotions
• Conscious/Unconscious Minds
• Spacetime Structuring
• Species, Biospheric Minds
• Action-at-a-Distance
• Quantum Potentials
• Scalar Interferometry
• Hidden EM Variables
• SWZ Effects
expansion

Figure 8 Three branches of Russian energetics weapons.

The KGB also implemented an elaborate and continuing deception plan, as is standard military practice for any great strategic attack plan. The KGB deception plan has been highly successful {29} in keeping the United States convinced that these weapons do not exist, and convinced that the standard strategic nuclear weapons possessed by the West are "leading" and "superior."

Strategic Attacks Scheduled and Why We Were Not Destroyed

Indeed, the West's nuclear weapons are inferior to Russian energetics weapons, particularly to the quantum potential weapons (Figure 9) deployed at the end of 1989 and to the newer "causal system" weapons deployed since the first of 1999, where *functional robot systems* (Figure 10) are made of nonmaterial spacetime curvatures and their dynamics only! In the event of a full strategic Russian energetics strike, an opening strike with quantum potential weapons {30} will dud all nuclear weapons on earth, all nuclear power systems, and all nuclear propulsion systems in about 10 minutes. This takes care of most of the U.S. strategic armament, *within the first 10 minutes*. The publicized strategic weapons of this nation have in my opinion been almost defenseless now for at least a full decade {31,32}, but I also believe that situation may be rapidly changing for the better.

A friendly little foreign nation *does* have such weapons including QP weapons that operate in multiply connected spacetime (MCS). That little nation has been responsible for our continued survival and has continued to deter the planned KGB strategic energetics strikes upon the West. There are indications (though still not certain) that at least one—and possibly two—other friendly Western nation also possesses such weapons.


N_6
N_7
N_3
N_1
N_4
N_2
N_5
Any Depth

Figure 9 Quantum potential instantly attacking widely separated targets.


Internested patterns of spacetime curvatures
Highly Structured Einsteinian spacetime
Maxwellian Demons are EM hidden variables organized into dynamic ST curvature structures acting at all levels
Demons work at all levels
Exact ST curvature dynamics exists for any and all mass and EM system dynamics. For any mass system there is an exact ST curvature system that interacts with it to cause its functions and actions.

Figure 10 Causal system robots (CSRs). These are sets of ST curvature engines, with functions organized into a single complex weapon system with communication, propagation, weapons effects, and command and control functions incorporated. When the CSR interacts with mass, the mass performs those system functions.

Twice in 1997 alone *we were within days of the scheduled total strategic destruction of the U.S. by die-hard KGB energetic weapons,* with all-out strategic attacks actually scheduled in each case. The first attack was scheduled in latter February but was quickly countered. The attack was immediately rescheduled for May 1. The U.S. intelligence and scientific communities were apparently unaware of what was happening, and still do not believe it. However, as this author previously informed appropriate government agencies a few days prior to the attack scheduled for May 1, 1997, U.S. intelligence agencies certainly intercepted my urgent personal fax directly to the prime minister of the friendly little nation, urgently requesting that the "sane" command and control of the countering MCS/QP weapons be changed to "insane" control and spelling out the compelling reason why it was necessary.

In the insane weapons control mode, the computer periodically (say, every two hours) initiates launch sequence for the weapon, automatically. If any operating personnel remain alive on site, there is a designated short period in the sequence where the onsite personnel can countermand the order and abort the launch. If the order is not countermanded, the launch is not aborted and the "doomsday" weapon automatically fires. In that case, KGB military power and most of Russia would disappear from the face of the earth.

This was necessary to nullify the impending strikes of MindSnapper negative energy EMP weapons {33} on those critical friendly QP weapon sites to instantly kill all personnel on site. Strike by the MindSnapper instantly kills every living thing in the area, and a protracted contamination remains whereby the struck areas emit longitudinal EM waves. If one attempts to insert new crews to resume operation of the weapons, the crewmen sicken and then die in the entry attempt. First, increasingly severe interference between mind and body control occurs. Then the individuals waver, lose consciousness, go into seizures, and their minds gradually de-couple from their bodies and they die. Fortunately, after my fax message the C3 system was changed to the insane mode, and the Russians were notified, just in the nick of time {34}. To prevent their own destruction by the certain insane counterstrike, the KGB aborted the looming strategic strikes.

Ironically, at about the very time that the KGB strategic armada was standing down, Secretary of Defense Cohen {35} was making the following statement in Georgia:

> *"Others are engaging even in an eco-type of terrorism whereby they can alter the climate, set off earthquakes, volcanoes remotely through the use of electromagnetic waves...So there are plenty of ingenious minds out there that are at work finding ways in which they can wreak terror upon other nations...It's real, and that's the reason why we have to intensify our efforts."*

Almost certainly Secretary Cohen had no knowledge that, so to speak, a great Sword of Damocles hanging over his head was being removed by a friendly little foreign nation at that very moment, as he uttered those words apparently referring to the older longitudinal EM wave interferometer weapons. I suspect that Dr. Cohen is to this day still unaware of the incidents that were ongoing at the time of his poignant statement.

Attempts to Alert the Nation

We alerted the President and the National Security Council as early as 1984 (Figure 54). In 1998 we also furnished selected Senators, Congresspersons, and certain high-level U.S. government agencies with color copies of a 200-page briefing and expose {36} of—among other things—these weapons, their testing, and their clandestine use against the U.S. since 1963. Because of the nearly 50 years of demonstrated induction of diseases {37, 38} (Figure 11) in personnel in the U.S. Embassy in Moscow (e.g., responsible for the deaths of three U.S. Ambassadors), we also included part of the briefing on the Priore work {39} (Figure 12) showing the remarkable cellular changes (time-reversal of diseased states back to a previous earlier healthy condition) that can be and had been experimentally induced by energetics under rigorous scientific controls.


Former U.S. Embassy in Moscow.

BACKGROUND

- Began in latter 1950s
- Discovered on VP Nixon's trip
- Initially thought to be *nuclear* radiation (Discovered w/Geiger counter?)
- High level target -- U.S. Ambassador
- Guarantees personal attention of:
    - U.S. Ambassador to USSR
    - U.S. President
    - NSA, CIA, DIA, NSC, etc.
    - Top consulting scientists
    - Leading U.S. scientific institutions
- Two U.S. Ambassadors died, another sickened
- Anomalous health changes in personnel, only in zero-field (zero potential gradient) areas!
- Four U.S. Presidents requested Soviets cease
    - Cut from 18 watts/sq cm to 2 Then again increased
- No one could understand what was going on
- Aluminum screens were placed over windows
- Moscow was declared a hazardous duty zone

Figure 11 Microwave radiation of U.S. Embassy in Moscow.

We proposed to the DoD a very rapid, high priority development program to develop portable suitcase-sized computer-controlled treatment devices (Figure 13) capable of saving a majority of mass casualties—e.g., from a professional large anthrax attack on a major population center.



Figure 12 Priore[1] laboratory and device for treating small animals.


Two blankets have antennas in them.
Uses an advanced but simple concept.
Eliminates plasma tube mixing etc.
Computer-controlled complex signal structure.
Irradiation for 2 minutes.
Three such treatments one week apart.
Unit can be made self-powering on vacuum energy.
Equipment Case
Computer Control Unit
Signals Function Generator
See "Porthole Briefing" on website www.cheniere.org.
Antenna Pad

Figure 13 Portable unit for rapid treatment of mass casualties.

The Responses

The responses—or more exactly the near total lack thereof—by various U.S. government agencies were enlightening. E.g., the National Institutes of Health (NIH) never let the package out of its Policy (i.e., *political spin control)* section. It did not check a single scientific reference on a proven method documented in the hard French scientific literature for reversing terminal cancer, infectious diseases, etc. Not a single scientist called me to discuss such a proven, revolutionary effect. Instead, the NIH Policy section simply shipped the package over to the DOD as "their problem, not ours." That was because the package also explained how the Gulf War Disease was induced, including how semen can cause infection of the wife, and how the structured body biopotential of the sickened veteran can induce similar structuring of the biopotentials of his children by proximity, thus inducing various aspects of the disease.

Effective Survival Treatment of Mass Casualties Could Be Developed

Meanwhile, we had uncovered a way to dramatically speed up the Priore healing process, and use only normal transverse EM radiations for ready adaptation of existing equipment, while still forcing the same time-reversal of diseased and damaged cells back to normal. Just much faster. This meant that very small, suitcase-sized treatment units (Figure 13) could now be developed in a reasonable time—e.g., in two to three years, given a high priority, intense effort, adequate funding, and a carefully chosen scientific team.

So, we proposed a crash development by DOD of a small, suitcase-size portable device for quick, mass treatment of mass U.S. casualties following terrorist attacks on our cities using weapons of mass destruction. Eventually an innocuous reply (forced by my congressman) simply stated "it was not supported by the literature." In the package, of course, I had *specifically cited* the numerous scientific papers in the French scientific literature reporting and proving the experimental results. I had also worked 14 years to decipher the mechanism actually performing the revolutionary healing accomplished in rigorous animal testing by the Priore team. Eleven years after suppression of the Priore effort, the University of Bordeaux, which had been pressured into rejecting Priore's doctoral thesis, did approve and publish a doctoral thesis by Perisse on the work {40}.

The National Science Foundation (NSF) did not reply at all. Yet at the time the official strategic threat to the United States listed WMD attack on our cities and great population centers as the greatest threat of all (Figure 14). Today, as everyone knows we are in a war after the terrorist attack on the twin towers in New York and on the Pentagon on September 11, 2001. The U.S. government clearly recognizes that it is not a matter of if additional attacks on the U.S. cities and populace will occur, but *when.* The terrorists are also known to have already infiltrated weapons of mass destruction such as biological warfare weapons (anthrax, smallpox, bubonic plague, etc.) Nonetheless, apparently the NSF simply did not believe a novel but *rigorously demonstrated-in-the-1960s* unorthodox process that could potentially save most of those millions of Americans who otherwise will surely die—and who *are* going to die in the first major WMD strike on our population centers.


RECOGNIZED TODAY:
• Sabotage and interdiction
• Chemical and biological
• Nuclear materials
• Powerful explosives
• Assassination, hostages
• Contamination
• Shoulder-fired AD missiles
• Terrorism
• Nuclear weapons hidden in our cities (but shunned)
PRESENT BUT UNRECOGNIZED:
• Negative energy EMP weapons
• Quantum potential weapons
• EM biological warfare
• Scalar EM weapons
• EM disease induction and spreading of immune systems
• Alteration of behavior and emotions
• Alteration of memory and perception
• Control of thought and behavior
• Action at a distance effects
• Causal System Robots (CSRs)

Figure 14 The mass destruction weapons threat to our populace.

The entire scientific method is based on assigning priority to experimental truth rather than dogmatic belief. If experiments refute the theory, the theory must be changed and the experimental results accepted. Else one is not following scientific method. Apparently the National Science Foundation does not follow scientific method, nor does it seem interested in doing so. Neither do the National Institutes of Health. The decisive results of some 2,000 rigorous animal experiments reported in the refereed scientific literature in leading French journals, by multiple established French scientists, were simply ignored because the results are contrary to present dogma. Meanwhile, four years have been lost. During that four years, the portable units could have already been developed, mass produced, and made available to treat and save millions of coming U.S. civilian casualties. Apparently the lives of those Americans are not as important as maintaining the present medical dogma. When those millions do die—and they will—we shall most certainly remind those agencies of the caliber of their dedication to scientific method and of their service to their fellow Americans. In my personal view, ignoring a chance to save so many Americans is treason of a very special kind.

The Official Silence Was Deafening

Not a single scientist in any of those and other organizations seems to have taken the package seriously. Not one called me to discuss it, or apparently studied the references, etc. No one asked for a personal briefing. No one was interested in the actual photo of the strike of a Russian EM missile from a scalar interferometer, offset from a U.S. night shuttle launch (Figure 15) from Cape Canaveral in latter November 1985, or the photo of the actual registration point ball of light high in the air (Figure 16) over that same shuttle launch {41}. The same weapon then killed the Arrow DC-8 at Gander, Newfoundland about two weeks later (Figure 17). An eyewitness (or more than one) actually observed the streak of light from the sky that struck the Arrow DC-8 in the right fuselage ahead of the engines {42,43}, after the thrust of the engines were reduced during take-off by use of a negative energy (cooling) interferometer. A similar ball of light associated with the kill of a Titan missile fired from Vandenberg AFB in early 1986 {44} and printed in *Aviation Week & Space Technology* magazine, was also apparently of no concern.



PHOTO BY BOB GLADWIN

Scalar interferometer operator fires offset EM missile from Russia.





Figure 15 Soviet EM missile strike offset from U.S. shuttle launch at Cape Canaveral on 26 Nov. 1985. This is the smoking gun.

These remarks are intended to show the lack of understanding that has existed in our governmental, scientific, and intelligence communities of what energetics is and of the great energetics superweapons that have been developed. With the present rapidly growing interest in longitudinal EM waves, however, we suspect that such lack of understanding is now no longer the case. We certainly hope that is true, and we are


MARKER BEACON
Over Night Shuttle Launch
Cape Canaveral, Florida
26 Nov 1985
Photographed by George Suchary

Distant operator onsite in Russia slews away the registration point (the marker beacon)

Two weeks later, the same weapon killed the Arrow DC-8 at its takeoff from Gander, Newfoundland.

26 Nov1985

Figure 16 Marker beacon above U.S. shuttle launch at Cape Canaveral, 26 Nov. 1985. Russian crews were using shuttle launches as practice ICBM launch targets.


ENGINE THRUST IS REDUCED
AIRCRAFT GLOWING (THRUST REDUCED)
FUEL EXPLOSION
EM MISSILE STRIKE (MULTIPLE INSTRUMENT SPIKES)
CYANIDE INHALATION
KINDLING (SELF-TARGETING)
TAIL-DOWN CRASH
ELECTROSTATIC COOLING OF ENGINE COMBUSTION
EXPLOSIVE PLASTICS IGNITION, FIRE, OUTGASSING
ABOUT HALF THE OCCUPANTS DIE
RECOVERY PERSONNEL IRRADIATED
TIME CHARGING OF ATOMIC NUCLEI (SLOW)
MATERIALS EMIT LONGITUDINAL WAVE EM RADIATION FROM TIME-CHARGE DECAY
SHARP TIME-CHARGING PULSE (STRIKE OF EM MISSILE)

Figure 17 Kill of the Arrow DC-8 at Gander, Newfoundland Dec. 12,1985.

much encouraged that at least one—and possibly two—friendly Western nations now possess quantum potential weapons.

The Long Dry Spell in Correcting Electrodynamics May Be Slowly Ending

In over 20 years of unrelenting effort, until 1999 we were unable to get any significant Western scientists of real "horsepower" (e.g., in non-Abelian electrodynamics, foundations errors in electrodynamics, advanced gauge field theory, general relativity, etc.) to meticulously examine conventional U(1) electrodynamics and its glaring errors, and to look at weapons implications of higher group symmetry electrodynamics.

Beginning about three years ago, however, a noted scientist, Dr. Myron Evans {45,2}, along with other theoretical scientists of the Alpha Institute's Institute of Advanced Study (AIAS), have been extending electrodynamics by developing the 0(3) electrodynamics. They also have deeply examined the Whittaker work of 1903 and 1904 on which the early part of the Russian energetics weapons are based {24}.

The AIAS analyses, and subsequent papers by Dr. Evans and Alex Labounsky as well as by the entire AIAS group, have clearly established the primary importance of time-like precursors of EM fields, operating in massfree spacetime where fields E and B cannot exist. These time-like precursors *create* all the rest of the conventional electrodynamic entities {46}. This is a dramatic extension to electrodynamics and physics across the board. More than 100 papers have been produced to date, with more than thirty published in journals such as *Foundations of Physics,* and many of the others are either accepted or still in the referee process with various journals. Some 60 of the papers were published as a single special edition of the *Journal of New Energy* (JNE) in latter 1999, and a second edition of *Modern Nonlinear Optics,* Wiley, 2001 has been published with many important papers.

However, the problem is that the scientific community, which is strongly committed to "business as usual", has funded none of this work. The conventional lead agencies of the community are still in the "ostrich position", with their heads buried very firmly in the sand with respect to the terrible damage they continue to enforce on this nation by their continued perpetuation of an old, long-archaic, inadequate electrodynamics and electrical engineering.

Engineerable Unified Field Theory Is Now Clearly Appearing

The rapidly emerging AIAS extension of electrodynamics has "met in the middle" with Sachs' {4} revolutionary generalization of general relativity and electrodynamics. For the first time, an _engineerable_ unified field theory—employing 0(3) electrodynamic means—is now being produced. The AIAS work in 0(3) electrodynamics was shown to be an important subset of Sachs' approach. It also now provides the full, rigorous theoretical foundation and model for the Priore mechanisms and results.

We also comment most strongly that the important SU(2)xSU(2) electrodynamics as developed by Barrett (47) leads to essentially the same conclusions, since Barrett's electrodynamics is homomorphic with 0(3) electrodynamics. Barrett, of course, is one of the pioneers of ultrawideband radar—another scientific area that was fiercely opposed and suppressed by the orthodox U.S. establishment for some time. Ironically, today those very scientists who were so dogmatic in their vociferous condemnation of UWB radar, have assumed the mantle of "experts in the UWB field", sometimes even taking credit for having "advanced it" in the first place.

Examples of Some Major Non Sequiturs in Conventional Electrodynamics

In every textbook and millions of technical papers in the West, electrodynamicists routinely calculate the "magnitude of the scalar potential". Actually, not a single one—including Maxwell—calculated or calculates the *magnitude of the potential itself.* Instead, they universally calculate the *reaction cross section* of the potential at a point occupied by an assumed intercepting/collecting unit point *static* charge {48}. At best that is a representation of the *intensity* of the field at each point. The reaction cross section of the potential with a fixed unit point static charge is indeed a scalar value. The "scalar" potential itself, on the other hand, *is not* its own reaction cross-section at each point of itself, and it is not a scalar entity at all! Instead, it is a harmonic bundle of bidirectional EM longitudinal phase conjugate wavepairs, as shown by E. T. Whittaker in 1903 {49}. It is and always has been a multi-vectorial, multiwave entity. By slightly reinterpreting Whittaker's work to agree with quantum field theory, the scalar potential is also a circulation of EM energy from the time domain to 3-space and back to the time domain, at every point in space that is occupied by the potential.

Further, the "field" notion is utilized in two self-contradictory manners. On the one hand, it is assumed in the massless reaches of space, and on the other hand it is assumed in mass, *which is the only case in which a force field is properly defined.*[8] The so-called "electromagnetic field" existing in empty space is not an EM force field at all, but a curvature or curvatures of spacetime with assorted ilynamics. Spacetime is after all active, and being active means curvatures and ilynamics. As rigorously shown by the AIAS theoreticians, what exists in *spacetime*—before the force-fields appear on reacting charged mass—are time-like and longitudinal scalar potentials and fluxes. These "pre-EM field" entities in fact interact with mass to produce all the force fields (the electromagnetic fields). Mass is a *component* of force; simply by F == *d*p/dt, which is expanded into F = d(mv)/dt, which is ma + v*(dm/dt).* Note that both terms have mass as a component. Hence there is no force or forcefield when mass is absent. Present mechanics is seriously wrong (and has been wrong for hundreds of years) in assuming a separate massless force acting upon a separate mass.

---

[8] Since Maxwell and **the** original pioneers believed in a material ether filling all space, to them t**here** was not a single point anywhere in the universe that was devoid of mass. Hence to them there was only one kind of field: **the** kind that exists in mass.

Jackson, one of the ablest classical electrodynamicists of our day, adroitly states how electrodynamicists skirt that issue. Quoting, p. 249 of his *Classical Electrodynamics,* second edition: *"Most classical electrodynamicists continue to adhere to the notion that the EM force field exists as such in the vacuum, but do admit that physically measurable quantities such as force somehow involve the product of charge and field."*

Our comment is that one does not get an observable until after the interaction of a cause with a previous effect, to provide a change (a new effect). The 4-cause itself—in this case the field that actually exists in the vacuum—is never observed nor is it observable. Its *effect* (force with an affected observable mass as a component of it) is observed. The field in space and the field in matter thus do not even have the same fundamental units, but differ by a factor of m. In electrodynamics the m is avoided by "defining" the field as force per unit coulomb of "charge" (without saying or accounting "charged mass").

Wide Confusion of Cause and Effect

Present electrodynamics (and even the hoary old mechanics, as pointed out) has thoroughly confused the causal (4-space) side of the observation process with the effects (3-space) side—observation yields *3-spatial* entities, not 4-spatial. Indeed, as is well known, *time is not observable, even in theory.* That is really because observation is a *d/dt* process applied by the 3-space intermediary (e.g., mass) being acted upon by the causal (4-space) entity in spacetime, to produce a change in that intermediary (3-spatial) that results (is observed). *A priori,* the output of the observation process does not even exist in time, since its fundamental units are LLL and not LLLT. The observation process is thus *d/dt(LLLT)* => LLL.

Further, electrodynamics omits the fact that, not only does the causal entity act upon the intermediary to produce the *effect* (changes to the intermediary), but *those changes (effects) also act back (in reverse) through the intermediary to produce changes in the causal entity itself.* This mutual interaction between cause and effect (but never stressed in exactly that manner) is well known in GR, where the curvature of spacetime acts upon mass-energy to change it, and the resulting change in mass-energy also acts back upon spacetime to curve it. The omission of the latter "back reaction" in EM theory by Maxwell resulted in omitting half the energy, half the wave, and half the causal entity in spacetime, as well as half the effect. The missing half of the effect appears as the Newtonian third law reaction, which in electrodynamics is just mystically "assumed" to be an effect without a cause.

The vast importance of restoring this missing "back action of effect upon cause" is because it can be deliberately utilized to directly engineer the causal (4-space) state itself, producing nonmaterial "engines" and unobservable functioning robot systems comprised entirely of curvatures of spacetime and their dynamics. Such "causal system robots" (CSRs) can be designed and engineered to then perform almost any desired action upon normal mass systems they encounter. The robots also can easily penetrate vast depths of mass, which is mostly empty space filled with potentials, fields and waves—all of which are just bundles of longitudinal EM waves and their dynamics. "Mass" is actually a vast superhighway through which such CSRs can easily move at the speed of light {50}.

CSRs: Engineering the Unobserved Causal Side To Create Functional Systems

Understanding early on the mutual interaction between cause and effect that existed in their energetics, the Russians were able to engineer this totally new kind of system: the *causal system robot* or CSR (Figure 10). With sufficient theoretical development, one can "work backwards" by adroitly re-engineering the effect to obtain a desired causal system (spacetime curvature set along with its impressed dynamics; (Figure 18) corresponding to some physical system and its changes one desires to engender. One thereby directly creates a deterministic set of spacetime curvatures and impressed dynamics, which we call an "engine" (Figure 18). This *ST curvature engine* system can then function as a completely separate system {51} (Figure 10). One can communicate with it via longitudinal EM waves, control it, etc. By building in scalar interferometry functions, the **CSR** can be given "weapons" capabilities, etc.

- All levels of energy structures and all levels of time structures mold spacetime geometry.
- The "pattern" is called a *template* for a vacuum engine (spacetime curvature engine).
- Spatial and temporal structurings of the engine act upon mass at all levels.
- This produces a template of forces, for precise translations and stresses within the mass at all levels. The forces exist in both time and 3-space.



Figure 18 The principle of general relativity extended to include the concept of the vacuum engine.

In theory such a CSR can be assembled to perform any desired function or complex of functions upon matter, fields, potentials, etc. that is desired. In short, one can build real, functioning "infolded" (subspace) robot weapon systems using this "backward engineering of spacetime itself process. The huge underground facilities (hundreds) that the Russians continued to build after the collapse of the Soviet economy and the fall of the Soviet Union, apparently contained the full CSR development and control facilities as well as the operational systems employed for this totally new kind of weapon system.

A great engineering of the future lies in engineering CSRs, which already constitute a great leap forward past the material nanobot technology being pursued in the West.

Making the First CSR is Extremely Difficult; Making a Million Copies Is Easy

The development of a specific CSR with a specific set of functions is akin to developing a highly complex software system of major proportions (several tens of millions of lines of code). The job is extremely difficult, and tortuous "debugging" is required for a lengthy period. Once a single CSR is completed and debugged, however, the production of thousands or even many millions of copies is then a trivial task.

The CSR may be visualized as a sort of vast complex of longitudinal EM waves (recall, we are speaking of ST curvatures, not the conventional EM waves thought to operate on a flat spacetime. *All* EM waves operate in a curved spacetime *a priori*, as clearly shown by Sachs). It turns out that all matter is mostly empty space, filled with potentials and fields. Space itself, considering its energetics, may be taken as a giant scalar potential. All those potentials and fields and waves are in fact nothing but sets of longitudinal EM waves and dynamics. In short, they are vast superhighways for the travel of CSRs and the propagation of longitudinal EM waves.

A CSR can be embedded within any kind of EM potential, wave, or field. So to replicate one, one embeds it in a magnetic signal and records that signal on a diskette or other media. Then one makes millions of copies of the diskette, for perhaps 10 cents or less each. Or do it en masse, by first completing a CD-ROM with a hundred or two hundred CSRs embedded in its signals (Figure 19). Then simply reproduce the CD-ROM. Every reproduction has another hundred or two exact duplicates of those CSRs, made for almost no cost at all. With communications built into the CSRs, the command and control facilities take charge of them, give them individual numbers or designations, and a robot armada emerges with most unusual capabilities indeed.

The puzzling underground facilities in Russia (which our fellows apparently never deciphered and which remained a mystery) apparently contained the scientific teams, the research and development facilities, the production facilities, and the command and control facilities for the new vast CSR weapon complex. It was to see its first great employment at the end of 1999.


A
MAKE CSR
COMMAND AND CONTROL
INSERT CSR IN EM SIGNAL "CARRIER"
RECEIVE COMBAT RESULTS REPORTS FROM ATTACKING ROBOTS.
RECORD SIGNAL ON CD-ROM, TAPE, ETC.
REPLICATE CD-ROM EN MASSE
ACTIVATE, COMMAND, PARK EACH ONE. THEN DEPLOY EACH SEPARATELY, IN ARMY OF CSR'S ATTACKING MILLIONS OF TARGETS
A

Figure 19 Mass reproduction of a CSR is simple and inexpensive. The CSR resides in, or propagates inside, any EM signal, potential, or field.

In 1999 The KGB Deployed Massive Numbers of CSRs for a Strategic Attack

In latter 1999 the KGB began massively deploying these CSRs of various types throughout the Western world, particularly including the United States. They simply sent the CSRs back "inside" the potentials and fields and waves being emitted from radio stations, TV stations, power lines, satellites, communications systems, inside matter, etc. These CSRs were deployed and infiltrated in major command posts and installations throughout the U.S. and its allies. True to form, the KGB even "stimulated" some major computer systems in critical U.S. government facilities by having the robots "surface" some effects on the Computers, right through the firewall programs (whose EM signals and operations indeed provided nice superhighways for the robots). Our fellows **detected** the interference as a "sophisticated computer hacking attack" (puzzlingly from the Russian Academy of Science), and then the robots "submerged" again after deliberately performing actions to produce obvious changes and guarantee the U.S. detection of those changes. The purpose of this "stimulus and probe" was to see if the U.S. was aware of CSRs and CSR **technology.** We clearly showed we were not, and we still are not aware of them. Fur**ther,** the entire government apparatus—including all our vaunted national laboratories—knows absolutely nothing at all about CSRs, and none of the laboratories believe it. That is the same posture they've been in with respect to energetics weapons for a half-century. Apparently they will be in that same posture for another half century, left to their own devices.

However, I was not allowed to remain a casual onlooker for this new CSR armada! The KGB also planned to use me as a stimulus to ping the government yet another way, and then assess the government's response.

Here in Huntsville, suddenly I was personally struck by such a CSR right from my computer monitor, with the attack riding through the light from the monitor to my eyes and retinas and right into the brain and nervous system (Figure 20). This was the type of CSR that can lurk in any potential or field inside a computer, and then strike and kill the operator looking at the screen. The CSR took over control of the machine, split the screen so that only one-inch horizontal strips were luminous—one at the top and the other at the bottom of the screen with the middle dark. These two separated horizontal strips allowed scalar interferometry via the inner LWs comprising the light from the two strips. The LWI signals crossed in my vision center, where suddenly ordinary EM signals and waves were produced by the scalar interferometry occurring there.

Stimulating apparently the only analyst capable of recognizing a CSR attack and connecting it with the scheduled giant strategic CSR attack.

KGB General commanding the energetics weapon previously confirmed that what this analyst writes on his computer is received as soon as he writes it. Apparently accomplished by Tempest techniques or directly by energetics.



Figure 20 Present author struck by CSR in latter 1999 as a deliberate nonfatal stimulus.

I saw rapid blinding flashes like a hundred flashbulbs exploding at once right in my face. However, the signals representing those "flashes" were being created right there in my vision center. An external camera would have recorded only the weirdly separated screen display. It *would not* have shown the brilliant flashes of light I was seeing, unless it was set up stereoscopically. The strike was deliberately sustained for only about 10 seconds so as to be severe but nonlethal; about 30 seconds would be totally lethal. Violent fibrillation of the heart also resulted explosively, and I was instantly hypnogogic and seriously weakened by sudden hypoxia from near total lack of blood pumping (because of the fibrillation). The purpose was apparently to strike the only analyst in the U.S. who would recognize what the nature of the attack was, stimulate him, watch him try to notify the government, and then observe the government's reaction. It look four days to recover from the strike. But I knew immediately what had made the strike, and that I had been hit with a CSR weaponized by having a built-in scalar interferometry capability. It was also a very sophisticated CSR, as it showed by assuming complete "intelligent" control of my computer's functions.

When I finally recovered, I did notify the government and warn them of CSRs, exactly as anticipated by the KGB. As might be expected, the government's total disbelief and lack of reaction clearly showed they knew nothing of CSRs. They simply did not believe such weapons existed or even could exist. Sadly, once again one faced the "not invented here" syndrome. General relativity and its provision for spacetime curvatures and their associated dynamics (engines) operating back upon mass are apparently just supposed to remain a theoretical curiosity. Why, obviously no scientist in his right mind would think of weaponizing such!

A more correct answer is, *"Like hell they wouldn't!"* *American* scientists would not think of it, but *Russian* scientists with their national chess-playing psychology will immediately seize upon any opportunity—even many moves ahead in the game—and develop it and utilize it. They understand and use the boa constrictor. We only understand and use the immediate rattlesnake.

How the Asymmetrically Deployed Strategic Attack Was Stopped in Its Tracks

However, we also alerted the "little nation" that has advanced EM weapons technology, which—since early 1997—has been saving the U.S. by forcing the abortion of impending KGB energetics weapons attacks.

When I warned them in 1997 about the MindSnapper weapons and mind-control weapons used against Captains Button and Svoboda, unknown to me at the time they later reacted and suddenly destroyed those facilities in Russia (apparently with violent scalar interferometry strikes). So *that* mind-control type of attack being readied for 1999 was thwarted for a few years by these strikes sometime prior to mid-1998.

But to return to the CSRs. In the latter quarter of 1999, the Russians were developing and deploying throughout the West numerous kinds of CSRs. So the period at the end of 1999/first few days of 2000 attack was already scheduled for a massively programmed CSR attack. It was designed to cripple the entire **nation,** and perhaps even collapse it economically, yet all would be blamed on Y2K! Our scientific ignorance guaranteed that we would blame it on something **mundane that** our scientists could understand: Y2K problems in all the old software programs running so much of our automated systems, communications, and centralized functioning, accounting, banking, etc. In short, the KGB planned to give us a bicentennial gift: a Y2K nightmare far beyond our wildest fears.

After my recovery from the CSR strike in the latter quarter of 1999, I again urgently alerted the friendly nation of the development of CSRs and their widespread deployment—and informed them of the personal attack on me and specifically why it was made nonfatal. Of course I also alerted our own government. We were scheduled for a *real* Y2K problem that would curl one's hair, so to speak, with everything imaginable failing—and probably all blamed on Y2K.

Admirably, beginning just at the end of 1999, the friendly nation simply began methodically and massively cleaning out all the CSRs, and they disposed of them in very short order! Such CSR systems[9] may easily be located and destroyed by strategic longitudinal EM wave weapons {52}, when and if one has the longitudinal EM wave technology sufficiently developed. So Y2K came and went with only a few relatively minor incidents from the *normal* Y2k problems expected.[10]

However, unknown to our scientists and intelligence community, a great war of a very special kind—*the Earth's first strategic subspace war*—had just been silently fought and won, right there inside our power systems, command and control systems, major weapon systems, electrical power systems, electrical control systems of our nuclear submarines and strategic bombers and missiles, even inside the electronics of our nuclear warheads, etc. And not a bobble showed on the surface, anywhere. This was the first real "subspace" war, where weapons made of pure spacetime curvatures and dynamics were involved as the main offensive battle systems. LWI destruction of numerous CSRs inside potentials and fields in various electronic equipment throughout the nation, created little or no overt signs at all.

This time we won, thanks to the "good guys" and not to our own scientific community. Next time we may not be so fortunate.

The Mostly-Ignored Time-Energy Interaction

For some inexplicable reason, physicists in the West have omitted one-half the actual photon interaction.[11] If one allows the spatial energy component of the photon to interact, then one must also account for the simultaneous interaction of the time-component of the photon. A mass m absorbing a photon (AE)(At) becomes *masstime* (m+dm)t, not mass m. Mass *m* and masstime *mt* are as different as are force *F* and impulse *Ft.* No scientist in his right mind would ignore the *t* in *Ft* and consider just the force *F.* Yet that exact kind of giant *faux* ***pas*** has been done for many decades now in the photon interaction. And it is still ubiquitously done in physics. *Mass does not emit photons; masstime does.* Again, physicists confuse effect and cause.

---

[9] These early CSRs apparently had no "stealth" capabilities built-in, so they were easily detected and destroyed, rather like shooting fish in a rain barrel.

[10] Even so, a normally disastrous Y2K problem was narrowly averted, in the nick of time, by a concerted national software reprogramming effort massively mounted and costing billions of dollars. Otherwise, the expected "ordinary" Y2K problem would have been very bad indeed.

As the Russian energetics weapon scientists know full well, time is actually spatial energy compressed enormously, by at least the factor c^2. Hence time has at least the equivalent energy density of mass. The greatest amount of "energy" existing in a photon—particularly in lower frequency photons—is in that "time" part that is arbitrarily ignored and discarded. An ELF photon has enormously more total energy—by many orders of magnitude—than does a gamma ray photon.

Energy and time components in the photon are canonical. Low frequency photons are reduced in the magnitude of their *spatial* energy component and thereby maximized in their *time* components. For the ordinary (decompressed) *energy equivalency* of the time component, one must multiply the time in seconds by c^2. Halving the frequency, e.g., doubles the time component, whose spatial equivalent energy is now $(2t)\times(c^2)$. With respect to the original photon, the new total energy (achieved by halving the frequency) is given by $[(\Delta E)/2] \times [(2\Delta t) \times c^2] = [(\Delta E)(\Delta t)\times c^2]$. So halving the photon's frequency increases its total energy by a factor of c^2, which is approximately by a factor of $9x10^{16}$. Hence photons actually carry enormously greater total energy (most is locked up as time) at low frequency than at high frequency. Indeed, the highest energy photon interactions in the universe are at low frequency, *if and when* a transduction of the available time-energy into spatial energy occurs.

This has been completely missed in the West, but not by the Russian energetics weapons scientists. They have been *engineering* that formidable new high energy but low frequency physics—a physics far more energetic than that used in our most energetic colliding beams in "conventional high energy physics".

The cold fusion processes[12] stumbled onto by Western scientists are using the

---

[11] I.e., except for accounting for the overall "action" (angular momentum) and such things as **minimum** action theorems, etc. Treating the photon's increment of time specifically as a formidably compressed piece of spatial EM energy does not appear in Western physics. It has **long** been utilized in the KGB's secret energetics weapon science.

[12] For an explanation of the use of time-reversal zones in cold fusion experiments, and some of the resulting new transmutation reactions that result, see T. E. Bearden, *Energy from the Vacuum: **Concepts** and Principles*, "Chapter 10: Cold Fusion: Low Spatial-Energy Nuclear Reactions at High Time-Energy," Cheniere Press, Santa Barbara, CA, 2002. Available from www cheniere.org. Statistically, the formation of significant time-reversal zones is guaranteed by **the transient** fluctuation theorem of Denis Evans et al., and by recent experimental work by Evans et al. proving that such zones (where the reactions run backwards) can and do occur at up to **micron** (colloidal) size and for up to two seconds in duration. We stress that this is a recognized, **proven** violation of the second law of thermodynamics already known to physics.

time-energy component of photon interactions, to generate enormous localized EM energy directly upon the interior quarks and gluons of nucleons {53}. We worked out a speculative explanation of the active time-energy transduction mechanisms that fits all the experimental phenomena, including the eerie instrument anomalies occurring in rigorous electrolyte experiments at China Lake for some years. That is included in my new book, *Energy from the Vacuum: Concepts and Principles,* Cheniere Press, Santa Barbara, CA, 2002, available from www.cheniere.org.

Of course consistency alone does not prove it conclusively; consistency is a necessary but not sufficient condition for proof. But at least the proposed explanation is consistent, and nothing else seems to be, at this time. In one chapter in my referenced new book we do cover the cold fusion mechanism and give specific new nuclear reactions producing the excess deuterium, tritium, and alpha particles in so many successful cold fusion experiments worldwide.

My "time-reversal zone" approach is stringent, because the recent work by Denis Evans *et al.* {54} has clearly shown that reactions can and do run in reverse—totally in violation of the second law of thermodynamics—at micron (colloidal) level in size and for up to two seconds in duration (and sometimes even a little longer). So experimental demonstration that the "time reversal zones" I assumed can and do indeed occur has now been accomplished by Evans *et al.* This provides strong experimental and theoretical support for the basic assumption (of the formation and momentary existence of localized time reversal zones that subsequently decay) we used to derive the fundamental cold fusion mechanism including some of the specific reaction equations for excess deuterium, tritium, and alpha particles now demonstrated in hundreds of successful experiments.

In a reversed zone *the law of attraction and repulsion of charges is reversed,* so that like charges attract—sometimes so closely that each enters the strong force region of the other, forming a quasi-nucleus (Figure 21). As the time-reversal zone subsequently decays back to a time-forward zone, the reduced strong force is restored much faster than the Coulomb force is reduced and then reversed back to normal. So during this readjustment decay process, the quasi-nucleus will simply change to an isomer and a known nucleus by quark-flipping to change an H+ ion to a neutron. Note that the "reversal zone" momentarily changes the Coulomb barrier—always the only thing that has really prevented chemical fusion and transmutation at low spatial energy—to a Coulomb attractor. Hence cold fusion—as now backed up by more than 600 successful experiments worldwide, by multiple laboratories and researchers in multiple nations—is an established fact and a herald for a vast new science based on deliberate and intentional reversal of the Coulomb barrier and use of time-energy.

With its usual perspicacity, the organized U.S. scientific community has flubbed it—and flubbed it badly—with respect to cold fusion. Its contribution has largely been a tirade of ad hominem attacks, slander, and libel of a viciousness seldom seen in the annals of science. Once again, the community is far more devoted to defending its cherished dogma (and its own rice bowls from the conventional Big Nuclear Science that cold fusion thoroughly upsets), than it is in applying scientific method which calls for *believing the experiments* and changing the dogmatic theory.



- Fermions time-reverse in even numbers
- Like charges cluster
- Aqueous solutions contain H+ ions, which are just protons
- Quarks flip as TR zone fades

$$2({}_1H_1 + {}_1H_1) \rightarrow 4({}_1H_1) \rightarrow 2({}_0n_1 + {}_1H_1) \rightarrow {}_2He_4 = \text{helium (alpha)}$$

Figure 21 Example of a time-reversed zone nuclear reaction common in successful cold fusion experiments.

Development of Threats and Scheduled Attacks Aborted

KGB energetics weapons have long constituted our single most pressing yet largely unrecognized national security problem. That problem has also increased with the growing development and deployment of such weapons by other nations such as China. Some 10 nations, for example, now have scalar interferometry weapons, and even the Japanese Yakuza has them and also has their own secret facilities for producing them in Japan, including small portable units developed for use in assassination and terrorist type warfare within a targeted nation—the United States of America.

Unknown to our government, we narrowly escaped destruction twice in the first half of 1997 from scheduled all-out strategic KGB energetics weapons attacks. **Only** the actions of a friendly small country countered the attacks and caused the **KGB** to abort on each occasion.

When the second scheduled Russian strategic attack was aborted just prior to May 1, 1997, a new KGB counter-counter for the friendly counter used by the **little** nation in latter April 1997 was already rapidly being deployed. The new **Russian** counter-counter—seizure and control of the mind of an operator at a distance, and complete control of his actions while he performs sophisticated technical tasks—was tested in two separate incidents {55}, first on Captain Button (Figure 22, Figure 23) and then on Captain Svoboda about two months later (Figure 24), each flying an A-10 Warthog aircraft over the U.S.



- Instant hypnogogic state
- Sense of horizontal direction skewed
- Sense of time distorted
- Dream-thinking, flew a "normal mission" off course for over an hour and then crashed
- At one point, circled. May have dropped ordnance there, dream-thinking he was on range and attacking a target

- Purpose: Test psychoenergetic control of person and his precise actions at a distance.
- Multiple weapons can take over manning of an installation
- Can control crew operations
- Can cause crew to switch off an insane assured destruction quantum potential weapon

Figure 22 Captain Button's bizarre flight to his death on 2 April 1997.



Armed with:
- Four 500-lb bombs
- 30 mm Gatling gun

April 2, 1997

UTAH
COLO.
Area enlarged
1:40 p.m.
Vail
1:22 p.m.
Aspden
1:05 p.m.
Telluride
12:53 p.m.
Cortez
ARIZONA
11:58 a.m.
Breaks Formation
near Goldwater Range
12:20 p.m.
Young
NEW MEX.
12:11 p.m.
Apache Junction
Barry M. Goldwater
Air Force Range
DEPARTS
10:30 a.m.
Tucson
Tombstone
Eagle
Vail
Glenwood
Springs
COLO.
New York
Mountain
Range
Flight path
Aspden

Figure 23 Captain Button's flyaway path to his eventual fatal crash.

The highly successful test against Captain Button (Figure 22, Figure 23) is particularly significant, as we have explained. Captain Button was controlled while performing highly technical operations, for more than a full hour, and one hour was apparently the acceptance test specification. Captain Svoboda (Figure 24) simply had her mental perception of up and down instantly reversed while climbing her A-10 warthog from low level ordnance delivery on target. Erroneously perceiving she was diving, she immediately "corrected" sharply to "climb", thereby diving headlong into the ground and perishing in the resulting explosion of her aircraft.


• Purpose: Stimulate U.S. in same area again
• Determine if U.S. aware of psychoenergetics
• U.S. showed it is completely unaware
?
?
● May 27, 1997
● Captain Amy Svoboda
● Experienced night flyer
● Night training mission
● From Davis-Montham AFB
● From same wing as Captain Button, who flew his A-10 off course for over an hour and then crashed on April 2.
• Shifted Svoboda's sense of up and down.
• Perceiving she was diving, Svoboda sharply "corrected", diving headlong into the ground and dying in the explosion.

Figure 24 Climbing out of low-level ordnance delivery, Captain Svoboda suddenly dives headlong to her death on 27 May 1997.

Svoboda's kill demonstrated a *tactical destruction* usage, whereas Button's test demonstrated a *strategic* hostile usage of the adversary's defending weapons crew to take action against the adversary's defending strategic weapons system. A new KGB strategic energetics attack against the United States—using the mind control (psychoenergetics) weaponry to take over the operators of the little nation's QP weapon sites and stand the sites back down for maintenance—was rescheduled apparently for latter 1997 to mid-1998 or so. It appears that the extensive preparations for that attack were totally destroyed clandestinely and very suddenly by the friendly little nation some time after we warned them, as we mentioned above.

However, still another Russian counter—the development of "weaponized engines" (functioning causal system robot weapons, "infolded electromagnetic" in form) consisting of organized and functioning systems of spacetime curvatures operating in and traveling through EM fields, potentials, waves, and signals—came on line (Figure 10, Figure 18). The KGB simply altered the attack plan for a Millennium Strike and completed the forward deployment of these eerie new CSR systems by introducing millions of them directly throughout U.S. facilities, command centers, weapon systems, power grids, ships, aircraft, submarines, missiles, nuclear warheads, computers, communications systems, etc.

We estimate that several million such systems were introduced in that manner, and readied for the Millennium Strike. The United States and its allies were and are almost totally unprepared for this dramatically new kind of strategic warfare that has been developed and deployed against us. No such weapons have previously existed in history. Consequently our national survival and the survival of our allies was once again at stake—and right on schedule during the critical period from mid-1999 through mid-2000 that we had predicted back in 1997.

The die-hard elements of the KGB indeed had a new millennium gift for us, but it was not at all the kind of gift we would appreciate. The KGB is not a monolith! This plot apparently did not include Putin, and it did not include the rest of the KGB, particularly that element reporting to Putin.

Live Destructive Tests Over and Near the U.S. Have Continued

Without elaboration, we believe that the Learjet crash incident and the EA-990 crash incident may have been very sophisticated tests of these new robotic causal EM systems. We also believe that the long years of Russian construction of over a thousand mysterious underground facilities, even though the Russian economy was collapsed and the citizens and soldiers were destitute, is significant. Those facilities apparently contain the set of command and control systems for this vast new strategic weapon system.

The facilities also include the "factories" where the CSRs are made, because the factories are unlike any other factories ever conceived. They do not build "physical" systems, but something more like "software." Only now the "software program" itself is an independent robotic system, with a full set of weapon systems functions, and capable of independent navigation and functioning anywhere, while remaining under KGB command and control via longitudinal EM wave communications infolded inside the potentials of earth, ocean, and space. The facilities also contain the operational forces, headquarters, and communication and control systems that maintain, deploy, and employ (fight) these CSR systems, and direct the battle.

The purpose of the 1998 document we sent to DoD—which did not include the causal robot system armadas later deployed throughout everything in the West—was to inform selected members of the Senate and Congress of the energetics threat situation and summarize it for them. Accordingly, we presented the background of the development and testing of the KGB energetics weapons since WW II, in some detail, for selected Legislators and their staffs. We also included some specifics on the failure of the U.S. scientific community to keep American science and technology abreast of that of our adversaries.

The Scientific Basis For Energetics Weapons Is Established

As pointed out above, the scientific basis for our early use of Soviet scalar EM interferometry is now rigorously established by work accomplished by the Alpha Foundation's Institute of Advanced Study. It is also rather "old hat" now **that** all major weapons labs have discovered longitudinal EM waves and are **actively** working on and with them. The Director of the AIAS, Dr. Myron Evans, is an eminent scientist and theoretician with over 600 papers in the hard science literature. He and his colleagues also have had zero funding for their work on the higher group symmetry electrodynamics necessary to understand such things as energetics. A combination of non-Abelian electrodynamics, advanced gauge field theory, and the impact of E. T. Whittaker's work shortly after the turn of the century has shown that scalar interferometry is real, and that weapons based on scalar interferometry can be a potent threat on the battlefield. The time-like (time-energy) basis for electrodynamics is now clearly established.

With this important new work, we are now only some 40 years behind the **Russian** weapons scientists! But we are beginning to close the gap—and hopefully that will be done very rapidly.

In 1999 after being personally attacked by a CSR, I again contacted the office of the leader of the friendly small nation and again furnished all the information we possess on the new CSR systems programmed by the KGB as a countering method against the small nation's QP weapons. The outcome was that the little nation destroyed the CSRs in time, as we stated above. We were lucky that (i) the KGB did attack me with one of the weapons, deliberately to "get my strong and immediate attention", and (ii) deliberately did not kill me with the strike. Otherwise, there would have been no warning to the little nation, and the U.S. and its allies would have experienced a "Y2K" problem worse than their wildest fears, possibly collapsing the economy of the United States and much of the developed world.

Our Situation Here In the U.S. Is Precarious

Meanwhile, our own scientific community apparently does little or nothing in **these** areas, except to castigate, slander and libel anyone daring to suggest that such "out of the box" weapons areas even exist. E.g., there does not appear to be a single U.S. scientist who knows how to create a *time-polarized* EM wave.[13] There do not seem to be any concerted programs to deal with t-polarized photons and t-polarized EM waves. Our scientists still firmly believe that one has to propagate spatial EM field energy through space to affect a target electromagnetically, when that was obsoleted by Russian "subspace EM longitudinal wave propagation" weapon systems deployed as early as 1963, and was completely obsoleted by deployment of quantum potential weapons in 1989.

Yet a close colleague of the present author has single-handedly developed and demonstrated prototype superluminal communication systems using the infolded (longitudinal EM wave) electrodynamics, and these systems would have been heading onto the market in latter 2001 except for the sudden bankrupting of the major backing company. There has not been any funding forthcoming for his revolutionary work, but only clumsy attempts to take it from him. It is my fear that the further clumsy takeover attempts will be successful, and this desperately needed technology will never see the light of day in defense of our nation. As a single example without further discussion, his work revolutionizes the present notions used in the rapid development of quantum communication and quantum computing, because it revolutionizes the very notion of the Q-bit, completely removing the statistics of the quantum state and making it engineerable. This of course is completely counter to present QM notions, but is consistent with the Bohm hidden variable approach to quantum mechanics.

Meanwhile, our own weapon scientists apparently still do not recognize the possibility of a superluminal longitudinal EM wave communication system, and appear to have no motivation or intention to develop such. This is in a way quite sad; quantum tunneling at more than four times the speed of light, of a clearly recognizable Mozart symphony, has already been demonstrated in a section of a waveguide {56}. Whatever one wishes to call it and however one wishes to do it, superluminal communication of intelligible signals has been clearly demonstrated in the laboratory. For the "infolded" longitudinal EM waves, all the "normal" or "envelope" EM waves, potentials, and fields are just great *superwaveguides* for such longitudinal EM wave "tunneling through subspace" at superluminal speeds.

---

[13] Keeping one's sense of humor, apparently there has also not been a U.S. scientist who even recognized and knew what actually powered an electrical circuit, until our solution to the source charge problem and publication of it in 1998. Eerily, even after the technical basis for a solution had been proven in particle physics in 1957, no one seemed to have applied the broken symmetry of opposite charges to the common dipole and to a dipolarity such as a scalar potential and a charge (with its associated virtual charges of opposite sign, in the modern view). Everyone accepted that the fields and potentials and their energy are established by their associated source charges, but no one had stated that the source charge receives its input energy from its asymmetry in its seething energy exchange with the active vacuum.

The Dominant Weapons Are Quantum Potential Weapons

Full-bore deployment of Russian quantum potential weapons occurred by the end of 1989, the first lab prototype weapon having been tested in April 1986 against the U.S. air attack on Libya (Figure 25). Beside Russia, two other nations—Brazil and the "little friendly nation"—also had developed quantum potential {57} weapons. The United States did not develop them, or at least apparently not just yet.


Mild quantum potential weapon tested against electronics in U.S. aircraft and missiles
EM energy arises from every point in spacetime inside the electronics
• 33 U.S. AIRCRAFT IN STRIKE
• MANY HIGH-POWERED TRANSMITTERS
– COMMUNICATIONS
– JAMMERS
– RADARS
• SEVERE, UNEXPECTED "EMI" ENCOUNTERED
– ONE F-111 DOWNED
– NUMEROUS WEAPONS WENT ASTRAY
– THREE FOREIGN EMBASSIES DAMAGED
– SEVEN AIRCRAFT FORCED TO ABORT
• COMMANDERS: "US OR THEM?"
Washington Post 22 Jan. 1989, p. A4

Figure 25 U.S. air strike on Libya, April 1986.

Burlier this year (2002), China also deployed QP weapons, and we now find that an*other friendly* nation has them as well. That brings the total to five, as of this writing. Two of those are friendly, and a third is astraddle of the fence, so to speak. The other two are Russia (the KGB) and China.

At this point China could go either way, so it represents a future enigma. China **has** control of the Panama Canal, and has inserted more than 200,000 Chinese into Panama—which is on the way to gradually becoming a Chinese territory, as soon as the Chinese in Panama outnumber the native Panamanians. In addition, under the Clinton administration China gained access through two U.S. ports (with little checking, so anything can easily be inserted). China also has a**dditional** ports in the Western hemisphere. China is almost certain to eventually attack and seize Taiwan, which puts her on a collision course with the U.S., si**nce** the U.S. has an agreement to defend Taiwan. She has also declared the South China Sea—through which passes some 60% of the oil bound for Japan, a**nd** much oil for other nations also—to be Chinese territorial waters. China also has developed bioenergetics weapons, having long ago induced cancer into most of the GRU Russian representatives then serving in China. She almost certainly has or is rapidly working to develop psychoenergetics weapons as well.

So far as I am aware, there still exists not a single funded U.S. scientific program to directly correct the glaring errors in our own classical electrodynamics—such as those problems deplored by Nobelist Feynman and Wheeler {58,59,60}. Both knew that the force field concept in space was erroneous. As they put it, only the "potential" for the force field exists in space, in case some charged mass is available there for interaction. But the field itself is created by the interaction and is the effect of it. It does not exist before the interaction occurs. Yet all our texts continue to teach the disinformation of the "field in space." And our science community continues to fiercely defend such dogma, attacking and sometimes destroying the careers of those brave scientists who do try to change it.

One notes that time is multiply-connected, since in theory the same instant exists at every point in the universe. Or said another way, in any instant in time, every point in the universe simultaneously exists.

Operating in the time-domain as a causal system, and then turning out of one point there into any point in 3-space desired, is a means of producing "action at a distance" that obsoletes our old concept of transmitting the energy directly through space {61}.

Presently the U.S. scientific community has little predisposition toward energy turning into the time-domain, operating in the time-domain, then turning out of the time-domain into any desired point in 3-space, anywhere in the universe.[14] Every 3-space point in the universe simultaneously exists in (is superposed in) each point in time, as those points in time occur. In one sense, time can be considered to be the total multiple connectedness of space! We suspect that it may even be possible to interpret "instantaneous" communication—as by a quantum potential—in that "in here-out there" instantaneous fashion via "tunneling through the multiple connection of the time channel".

Finally, mass—being an observable and 3-spatial—does not exist in time. Mass continually turns into masstime (by photon absorption), then masstime turns back into mass (by photon emission). Masstime exists in time, but mass does not. U.S. scientists also seem unaware that the so-called "rate of flow of a mass through time" is generated by the sum total of all photon interactions (both virtual and observable) with that mass. The ubiquitous interaction of a mass with photons also causes that mass to continually recur, and thus to seemingly "continuously exist." It is continually observed, but it does not continuously exist! Since the photon interaction is engineerable, then it follows that a specific muss can be time-reversed back to an earlier state {62}.

---

[14] If one models the time domain in three dimensions instead of one, e.g., then in theory it becomes possible to "flip" a 3-dimensional mass object into the time 3-domain at a single "moment," then rotate from that "time 3-point" back into 3-space at a new 3-space location anywhere in the universe. Hence the "beam 'em up Scotty!" of the old Star Trek (and the more modern beaming version) may hold more of a promise than just for science fiction entertainment.

Cellular Time Reversal: Revolutionary Healing by a Team of French Scientists

Priore and eminent French scientists {39,40} unwittingly used the mechanism for time-reversing a mass and every part of it, to time-reverse diseased and damaged cells, including tumor cells, physically changing them back to their previous healthy physical state and condition in vivo. This included all parts of **the** cell, including its genetics. The Priore team demonstrated revolutionary **cures** of terminal tumors, infectious diseases, atheriosclerosis, and restored depressed immune systems.


BONE MARROW
Intestinal tissue, liver, etc.
Lymphocytes
Thymus
Special Defense
B-lymphocytes
suppressor cells
plasma cells
antibodies
T-lymphocytes
killer cells
helper cells
Complement system
complement factors
General Defense
Monocytes
granulocytes
Feeding cells
macrophage
bacterium (foreign invader)

Figure 26 Simplified diagram of the immune system.

The immune system (Figure 26) *heals nothing, not even its own damaged cells.* The human cellular regenerative system {63} is responsible for all healing in the body—and it utilizes time reversal of the damaged cells as the active healing mechanism. The regenerative system (Figures 27, 28, 29) pumps the damaged cells with longitudinal EM waves (and therefore with time-polarized EM waves, which always accompany longitudinal EM waves), inducing the cells and all their parts to add the phase conjugates, thereby forming time-polarized EM waves and pumping in the time-domain rather than the 3-space domain. This dramatically extends nonlinear optics to the time domain, and mass pumped in that fashion is time-reversed (propagated back along its own time-track, to a previous physical condition.


INJURY
INPUT STIMULATION DC SYSTEM (PAIN)
CENTRAL DC SYSTEM
GROWTH DIFFERENTIATION
LOCAL CELL INJURY FREE RADICALS
OUTPUT DC SYSTEM
TOTAL CURRENT OF INJURY DC SYSTEM
MITOSIS DEDIFFERENTIATION
STIMULATION OF REPAIR CELLS

Note: Becker only had conventional EM available, hence was unable to model the inner structuring and inner dynamics of the fields and potentials. *So he missed the deeper "engine and antiengine" mechanisms.*

"Robert O. Becker, "The significance of bioelectrical potentials," Bioelectrochemistry and Bioenergetics, Vol. 1, 1974, p. 191.

Figure 27 Becker's theoretical control system involved with response to injury.


Trauma Producing Tissue Loss
Local cellular effect
Local nerve effect
CNS effect
Alterations in hormone pattern (prolactin)
Alterations in local DC field pattern
Local electrical effects
Local and systemic pools of target cells
Dedifferentiation into primitive mesenchymal cells
Phase I
Blastema formation
Growth
Phase II
Redifferentiation into required cell types
Restoration of body part or tissue

"Becker & Spadaro, "Electrical stimulation of partial limb regeneration in mammals," Bull. N. Y. Acad. Med., 48(4), May 1972, p. 629.

Figure 28 Becker's proposed control system governing regeneration.


ADD PUMPS
B
CELL AS A PHASE CONJUGATE MIRROR
ANTIENGINE PRESENT?
N
RESIDENT VACUUM ENGINE
PRIORÉ AMPLIFIED PUMPING
START
Y
A
CYCLE
CELL AND INTERIOR SENSORS
LOCAL VICINITY SENSORS
NONLOCAL ALL-BODY SENSORS
APPLY ANTIENGINE
DELTA CATALOGS
CELLS AND INTERIORS
Y
DELTA?
N
AEROBE
ANAEROBE
B
A
N
SWITCH TO AEROBE CONTROL SYSTEM
SELECT LOCAL
Y
DELTA?
A
AEROBE
ANAEROBE
N
Y
SELECT NONLOCAL
Y
DELTA?
CROSS THRESHOLD BACK TO AEROBE?
AEROBE
ANAEROBE
AEROBE
ANAEROBE
N
SWITCH COMPARATIVE CATALOG
SWITCH TO ANAEROBE CATALOG
Y
END OF AEROBE CATALOG?
SUM FOR ENTIRE BODY
SWITCH ON CENTRAL, OFF DECENTRAL GROWTH CONTROL; RESET IMMUNE SYSTEM
N
SWITCH OFF CENTRAL GROWTH CONTROL
SWITCH ON DECENTRAL GROWTH CONTROL
CONDITION IMMUNE SYSTEM TO ACCEPT
A

Figure 29 Author's deeper block diagram of the cellular regeneration system.


GRAVITON LATTICE TEMPLATES
SICKEN OR KILL
ENVIRONMENTAL SHIELDING
CELL CULTURE SAMPLE #1
CELL CULTURE SAMPLE #2
QUARTZ CONTAINER
QUARTZ CONTAINER
THIN WINDOW
GLASS: No Effect
QUARTZ: Delayed Effect
Divided bottle setup

Note: Minimum lattice is one harmonic interval: IR to UV is such a minimum G-lattice. Consider particularly the dielectric pathway in the emitting diseased cells and in the receiving targeted healthy cells.

Figure 30 Kaznacheyev's electromagnetic induction of cellular disease and disorder.

Kaznacheyev has shown that essentially any cellular disease or disorder can be electromagnetically induced in cells at a distance (Figure 30). Together with Becker's work, this shows that the cells can be altered either detrimentally (disease induction) or beneficially (disease elimination) by purely e**lectromagnetic** means. It would seem that diseases such as AIDS, e.g., could be **rather** dramatically cured by use of whole-body longitudinal EM wave radiation (with its simultaneously time-polarized EM wave radiation), as was done for other diseases by the Priore team and properly reported in the French scientific literature. We have also uncovered a process and method for causing the body to directly produce the time-polarized EM wave pumping, reducing the irradiation to perhaps 30 seconds of pumping instead of two or three hours {64}.

Becker's Study of the Cellular Regeneration System

In all our medical science, the only true healing procedures being utilized appear to be the use of Becker *et al.'s* tiny EM stimulation across otherwise intractable bone fractures {65} (Figure 31), to dedifferentiate (time-reverse) red blood cells, then redifferentiate (time-forward) them again twice to form osteoblasts, which are deposited in the fracture site to make new bone growth. All the other medical procedures seem to be *interventions,* not *healing.* After the intervention—which of course may be urgently necessary—it is then up to the body to heal itself (restore its cellular and tissue damage and functioning). So we have little *healing* science today, and in fact our medical establishment hardly funds any *healing* studies at all. EM radiation is usually considered as something that simply heats tissue. Our present medical science is deeply engrossed in studying the immune system. Again, the immune system heals nothing, not even its own damaged cells.


• Tiny DC currents (picoamperes)
• Pulsed DC current can be utilized
• Pulsed magnetic fields may be utilized
(+)
ELECTRODE
(-)
ELECTRODE
DC POWER SOURCE
BONE
BONE
FRACTURE SITE
RED BLOOD CELL DEDIFFERENTIATES
Shucks hemoglobin coat
Grows nucleus
NEW CELL REDIFFERENTIATES
Turns into type of cell that makes cartilage
NEW CELL REDIFFERENTIATES
Turns into type of cell that makes bone
Deposits in fracture site, healing the fracture

Figure 31 Becker's epochal bone fracture healing.

After the immune system "kills the bad guys" and saves the day, the battlefield is littered with residue and many cells of the body are damaged. The immune system sends in large scavenger cells that clean up the residue. And that's it for the immune system. Comparing it to an army's operation in the field, the immune system is the combat troops, not the medical services.

Restoration (healing) of the damaged cells back to normal is accomplished by the *cellular regeneration* system (Figure 29). This system is little known and little studied, but mostly studied by Becker (Figures 27, 28). It is a system that functions electrodynamically, but uses time-domain pumping to time-reverse the cells and their every part (including their genetics) back to an earlier state. In biology, the effect is called *dedifferentiation*, but without any knowledge of the actual EM mechanism.

So, within its capabilities, the cellular regenerative system in the body already uses longitudinally polarized EM waves, time-polarized EM waves (TPWs), and optical pumping by LWs and TPWs. Here we point out that neither the longitudinal photon nor the scalar (time-polarized) photon is individually observable; however, the combination of the two is observed as the instantaneous scalar potential {66}. With a little correction to properly make the phase conjugate replica wave a time-polarized EM wave, Whittaker's fundamental bidirectional EM longitudinal wave decomposition of the scalar potential (Figure 32) is consistent. Immediately the direct involvement of both the scalar photon and the longitudinal photon—and both the scalar EM wave and the longitudinal EM wave—are seen in Becker's bone-healing work using a scalar potential (Figure 31).



The Structure Is:

A harmonic set of longitudinal wavepairs. In each wavepair the two waves superpose spatially, but travel in opposite directions. The two are phase conjugates and time-reversed replicas of each other. Thus they comprise a coupled longitudinal wave and antiwave. The photons must be coupled into photon/antiphoton pairs (gravitons) by a strong application of the distortion correction theorem of nonlinear optics. Each wave in the biwave pair is a galloping wave. Each wavepair is a standing electrogravitational wave.

Note: Think of the oscillations as velocity modulations. The time-density carried by the waves is oscillating.

Figure 32 Infolded longitudinal EM biwaves composition of a scalar potential, per Whittaker 1903.

Priore unwittingly stumbled onto the actual mechanism used by all biological systems in "healing" (cellular regeneration), and also recognized how to amplify it **(Figure** 12). But no one understood its exact nature, including Priore and the scientists who worked with him at the time, and the conventional community still does not understand it. The Russian scientists not only *understood* it early on, but *weaponized* it as well. So did the Chinese.

Need to Correct and Extend Classical Electrodynamics

The organized scientific community's protracted defense of a seriously flawed classical electrodynamics is long standing. The conventional, comfortable ways of "doing business as usual, leisurely" now threatens the survival of the nation itself. We need to quickly admit and correct long-standing EM errors—such as calculating a reaction cross-section of an entity and calling it the magnitude of the entity itself! Our electrical texts continue to make that fundamental mistake, and they have done it now for 100 years or more. We need to quickly change the classical EM model to include the active vacuum and its interaction, and we need to change all textbooks to clearly state that all EM energy in the universe comes from the active vacuum, via the asymmetry of the source charges in their fierce energy exchange with it.

We also need to point out that all primary electromagnetic entities—the charge, the field, the potential, and every joule of EM energy in the universe—totally violates the second law of thermodynamics. The charge produces continuously increasing negentropy, the field and the potential are formed at expanding light speed across the universe and are perfectly ordered (thereby totally violating the statistical mechanics basis of the second law), and every joule of EM energy is either field energy or potential energy, and hence violates the same statistical basis of the second law.

The Situation Is Serious

Admittedly these are strong statements highly critical of our scientific establishment's track record. But our national survival continues to be increasingly at stake, the situation is serious, and we must not continue to bury our collective heads in the sand like ostriches. We simply cannot continue to idly sit by and pontificate while other groups and nations methodically maneuver technically to cut our collective throats with advanced weapons we cannot defend against, once they find a way to "get by" the little nation that has been countering them for some years. Our own beloved nation may have less than 10 years {67} and perhaps less than three years to survive, unless the organized scientific community is galvanized to focus its very best scientific efforts in the energetics area.

So far, in truly innovative approaches to new methods for electrical energy, the U.S. scientific community is about as energetic as a sand terrapin sleeping in the tropical sun. There is no discernible move to recognize the seriousness of the problem, or to do anything effective about it. In 45 years, the asymmetry of the dipole (and the charge in its modern view as a dipolarity of special kind) has not made it across the university campus from the particle physics department to the electrical engineering department. In fact, the implication of broken symmetry to

electrical engineering and classical electrodynamics seems to still be completely unnoticed by the National Academy of Sciences, the National Science Foundation, our universities, and our great national laboratories. In the scientific community, other than work on vaccines etc., it is largely "business as usual."

A New Manhattan Project Is Warranted

Our need in the energetics weapons area is extreme, as are our needs in the medical area for quick, cheap, easy, and effective portable treatment of the coming mass casualties and our coming dramatic needs in energy. We *do* have superb scientists with the horsepower necessary to do something about it. The astounding, independent work of Sachs, the AIAS, and a few other scientists—which we stress has been unfunded—already clearly proves that. But unless we change the organized scientific community's normal rather snail-like pace—by a strong measure such as a Presidential Decision Directive and a declaration of a Nalional Emergency—the U.S. scientific community will overshoot the point of no return now approaching.

We need a new Manhattan-type project. We need it very quickly. If we do not change and focus our present scientific procedure, then—all too shortly—little that the scientific and intelligence communities are doing will be of value. We shall all be very, very dead or else in a new Dark Ages where most of the world economy has collapsed and freedom has largely disappeared from the face of the Earth.

T. E. Bearden, Ph.D.
Lieutenant Colonel, U.S. Army (Retired)
President & CEO, CTEC, Inc.
Director, Assoc. of Distinguished American Scientists

2002 ENERGETICS WEAPONS THREAT TO THE U.S.

T. E. Bearden 2000
Updated Oct. 1,2002

The U.S. Narrowly Escaped Energetics Destruction Twice in 1997

On two occasions in 1997 (latter February and on May Day), we were scheduled In be strategically attacked without warning and completely destroyed. Eerily, in public statements the leader of the Aum Shinrikyo sect (Figure 33) had foreshadowed the dates for the planned attacks, since his group was also involved—in fact, shooting down the TWA-800 (Figure 34) as advanced practice and stimulation of the U.S. to see if it knew what was afoot. Those two planned strategic strikes in 1997 were avoided only in the nick of time by actions of a friendly little foreign country, which was the only nation on earth at the time that could counter the KGB quantum potential (QP) weapons. I am sure that proper U.S. agencies intercepted my urgent personal faxes to the Defense Attache in Washington, DC and directly to the Prime Minister of the nation involved. Actions by that nation did succeed in averting our destruction in the nick of time.



- Formed in 1987. Over 60,000 members. More than $1 billion in gold and cash.
- Taught that U.S. would strike Japan with devastating blow in latter 1997
  - Japan should make preemptive strike first
  - AUM would get mass destruction weapons
  - Was developing BW weapons (anthrax, botulism, "Q" fever, etc.)
  - Developed own chemical weapons
- Sarin attack on Japanese subways
- Formed alliance with Japanese Yakuza
- AUM/Yakuza leased operational use of strategic Soviet energetics weapons in latter 1989
- Trained crews, planned to strike U.S. a terrible "pre-emptive" blow in 1997 by assisting KGB
- Using deception, killed targets such as TWA-800

AUM SHINRIKYO
"SUPREME TRUTH" CULT

Shoko Asahara, Leader

"I am certain that in 1997, Armageddon will break out. By 'break out' I mean that war will erupt and that it will not end soon. Violent battles will continue for a couple of years. During that time, the world population will shrink markedly... A Third World War will break out. I stake my religious future on this prediction. I am sure it will occur."

Figure 33 Planned KGB/Yakuza/Aum Shinrikyo attack in 1997 was foreshadowed in public statements made by Shoko Asahara.


Similar streak w/front glow, in clouds, Photographed by Linda Kabot
EM Missile Strike
Electromagnetic Missile (glowing)
>20 eyewitnesses!
Turbulent Wake in Clouds
OTHER INDICATORS
• Helicopter eyewitness to streak, initial strike glow, and then larger second glow.
• Pilot eyewitnesses, multiple aircraft.
• Radar tracked a nonsolid blip that closed with the aircraft.
• Explosives ruled out.
• Significantly differs from downing by a light SAM at envelope of its range.
• Simple mechanical failure does not fit.
Second strike: An EM burst inside a/c explodes fumes in empty gas tank
• 1985 photos of Soviet EM missiles offset from shuttle launch.
• 1985 eyewitness of similar EM missile strike on Arrow DC-8 at Gander AFB, Newfoundland.
• Multiple photos of EM missile tests over Western Australia (range).
• Probable: U-2 explosion 7 Aug 96.
• C-130 crash 22 Nov 96.
Emulation of surface-to-air missile (part of deception plan)
Emulation of a "leaking fuel" explosion (deception plan)

Figure 34 Kill of TWA Flight 800 on 17 July 1996 by Yakuza and Aum Shinrikyo.

Only five nations or national groups have quantum potential (QP) weapons, though one or more additional nations are almost certainly working on them and may even have them. First of the five is the KGB in Russia (the weapons are not in the regular Russian forces, and never have been). Second is the friendly little foreign country to whom we presently owe our continued survival. The third is Brazil (which has had a small and successful QP weapon program for some time). China deployed QP weapons in early 2002, and I recently found that at least one other friendly nation has them as well. I'm not too impressed with that other friendly nation, since they played no role in saving our bacon in 1997. It appears they did not actually know the coming attacks were imminent. They certainly do not have Causal System Robot weapons, nor do they believe such weapons even exist.

Initiation of the Brazilian Energetics Weapon Program

Brazil implemented an energetics weapons program after it employed the repatriated Dr. Hellman, a German scientist taken to Russia after WW II along with the German radar team. Years after being taken to Russia, Hellman was repatriated and made his way back to Germany. In a news interview Hellman reported that he had worked directly on the development of Soviet secret EM weapons which could suddenly free/.e large areas of the ocean surface. That of course is a scalar interferometry weapon, producing negative (converging) EM energy rather than positive (diverging) EM energy in their distant interference zones.

Also, when the U.S. made David Bohm *persona non grata* in the McCarthy witch-hunts, Bohm was later employed in lecturing and teaching in Brazil for some time. At the time our own scientists continued to pontificate as to whether they *liked* or could *tolerate* Bohm's quantum potential and his hidden variable interpretation of quantum mechanics {3}. Meanwhile, the KGB weapon scientists and the Brazilian Hellman project seized upon Bohm's hidden variable theory with alacrity as soon as he published his seminal paper. Those two weapon groups were already familiar with the internal longitudinal EM wave structuring of potentials, fields, and waves (Whittaker 1903), and immediately saw the fantastic weapons implications of a deliberately structured quantum potential, containing a specific "engine" as desired. Most of our scientists still are unaware of it to this day, and are unaware of its formidable weapon implications when combined with Whittaker's 1904 superpotential paper, his 1903 potential decomposition, and quantum field theory. Most of our scientists still adhere to the Bohr interpretation of QM, which excludes the normal, everyday, observable, ordered universe we all inhabit and observe.[15]

The Bohm quantum potential is, after all, a scalar potential, and at least in theory it has a Whittaker biwave decomposition {68}. Even in the Coulomb gauge, the scalar potential has infinite velocity, as pointed out by Jackson.[16]

Several tests of the "cold explosion" Russian weapons referred to by Hellman have since been openly made. One major test seen by at least five jetliner crews was the anomalous rapidly rising cloud and subsequent extremely huge light globe (ABM energy shield) effects off the Kurils in April 1984 (Figure 35). Two excellent scientific articles on the physical phenomena observed in that incident are published in the prestigious journal *Science* {69}. We had explained the cold explosion phenomena and the ABM energy shield effects some years before that incident. Even ordinary superpotential theory {70} and longitudinal EM wave interferometry at a distance can substantiate the capability. We also positively confirmed by private sources that the scalar interferometry, the MindSnapper (negative energy EMP), and the cold explosion weaponry are real.

---

[15] This exclusion is euphemistically known as the "missing chaos" problem in quantum mechanics, and it is resolved in Bohm's hidden variable approach.

[16] J.D Jackson, *Classical Electrodynamics,* 2nd Edn., John Wiley & Sons, New York, 1975, p. 222, 223. Usually the instantaneous scalar potential contributes only to the near field.


not to scale
380 miles diameter
200 miles
Sequence of Events
• Geyser of water rose rapidly from surface, mushroomed out
• Reached 60,000 feet altitude in about two minutes
• Brilliantly glowing small globe then appeared in top of cloud
• Globe increased greatly in size and altitude
• Reached diameter of 380 miles
• Center reached altitude of 200 miles
What They Were
• Superpotential interferometry using longitudinal EM waves
• Cold explosion just above surface (as antiship, antifleet)
• Smaller, higher density spherical shell (Tesla globe) for one-on-one shooting
• Larger Tesla globe for large area targets such as ICBMs coming in from midcourse
• Use in, out of atmosphere

Figure 35 Exothermic (cold) explosion off the Kurils 9 April 1984. A second test, an expanding globe of light, was added in the exothermic mode to demonstrate rapid serial switching between weapon modes.

Related Phenomena

In 1969 in Toronto, Canada, Sid Hurwich demonstrated a device capable of "freezing" a pistol lying on a table so that the gun could physically not be moved and the trigger could not be pulled {71}. For this exhibition of *strong electrogravitation,* general relativistic fields initiated by the EM force field (including the usually unaccounted Heaviside nondiverged component that Lorentz arbitrarily discarded) as the agent of spacetime curvature were used {72}. The strength of the effect was attested by the fact that the hands of the observers' watches all showed "no passage of time" during the half hour they were in the room with Hurwich's device operating.[17]

Rapid development of that strong electrogravitational technology and concomitant energetics then proceeded in another nation. Weapons of such nature were then employed by that nation a few years later, in two well-known international incidents. Clear signatures of the nature of the weaponry utilized were present in those incidents. Details of these incidents will not be included in this paper.

---

[17] We point out that this is highly interesting itself, since it showed that the observers were operating in a different frame from that of the watches and the gun, which were "frozen". We also point out that recently light itself has been "stopped" in quantum experiments, yielding something quite similar.

Since the energetics weaponry already utilized special EM "hidden variables," Bohm's hidden variable theory and quantum potential were directly adapted into the program to dramatically extend it into the development of quantum potential weapons.

Stalin *Personally* Initiated the Soviet Energetics Program with the Greatest Urgency

While Stalin was at the Potsdam conference, at the close of WWII, the U.S. exploded the first atomic bomb in the desert. Truman informed Stalin in general terms that a powerful new U.S. weapon had been successfully tested. Secretly, Stalin already knew of our atomic bomb progress, for he had a spy in the program. While he was still at Potsdam, he then secretly called the Director of the Soviet atomic weapons program and directed a speed-up.

After we exploded two atomic bombs on Japan, the Japanese surrendered and WWII was over. See again Figure 1. Stalin vehemently ordered his Academy of Sciences to produce the next great technical breakthrough at all possible speed, since the American atomic bomb had frustrated his plan to wait two years after the war while the West speedily disarmed, then march into Europe and take it in six weeks. Now his massed troops could just be bombed back into the Stone Age by U.S. bombers using atomic bombs.

A Great Technical Breakthrough in Physics Can Always be Had in Four Years

The scientific community can have a great new technical breakthrough whenever its furious and dogmatic resistance to innovative discoveries or the possibility of innovative developments can be suspended. All that is necessary is a concentrated group of highly skilled, open-minded scientists, the money and facillities, and a strong headlock placed on the powerful but dogmatic scientific groups who would otherwise hamstring the program and destroy it.[18]

---

[18] Present day examples are (i) the cold fusion fiasco, where the U.S. scientific community has revealed furious determination to ignore more than 600 successful experiments worldwide, (ii) a similar fury against any and all research into extracting EM energy from the vacuum, even though all EM energy comes directly from the active vacuum via the proven asymmetry of source charges and dipoles, (iii) violent suppression of proven "extended electrodynamics" methods of rapidly curing severe diseases, even in terminal stage (resistance to anything except "cut, drug, burn" and anything that would interfere with the monstrous profits of the large pharmaceuticals), (iv) continuing dedication to an electrical engineering model that does not even model or apply what powers an electrical circuit, (v) continuing resistance to quantum potential research and development, (vi) slavish dedication to "big nuclear science", massive accelerators, dangerous nuclear power plants, and a "hot fusion WPA program", even though much higher energy physics than these programs advocate and use can be and is being done on the tabletop, using time-energy instead of spatial energy, and (vii) increasing "lock-up" of all research funds into the organized hierarchy's politically approved agenda. The community has deviated so far from scientific

We proved it in the WWII Manhattan Project, where we went from nearly zilch to the operational atomic bomb in 4 years. But we did it only by secretly bypassing the conventional U.S. scientific establishment. Einstein wrote to President Roosevelt *around* the scientific community, and when the President approved and ordered the highly classified program, conventional scientists not on the project were just parked on the sideline and ignored so that the job could be completed. The naysayers were also muzzled because of the extreme classification of the project; they faced jail if they engaged in their usual ad hominem attacks and dogmatic eloquence.

Further, today the "Skunk Works" approach repeatedly proves that bold new projects can be done, when the skilled scientists and facilities are mobilized and no adamant opposition by the conventional community is tolerated.

Numerous examples of the U.S. scientific community's suppression of innovation and new technology can easily be furnished. Such are well known to any historian of science. Cold fusion, the amorphous semiconductor by Ovshinsky, the first laser papers, ultrawideband radar, Mayer's original conservation of energy law, Boltzmann's work, Wegener's continental drift, flight of heavier-than-air machines, the rocket as a great strategic weapon, and hundreds of other examples come readily to mind. Such suppression has been *the* major characteristic of the organized scientific community since its inception, as pointed out by numerous leading scientists and authors. As Planck stated, usually one gets a new physics only after the old physicists who so adamantly oppose it just die off and get out of the way.

Today, the U.S. scientific community is in fact our "front line troops," although—except for a little lip service—the managers of the organized scientific community are blissfully unaware of it and have little or no sense of mission in out-of-the-box areas with respect to national survival. It is ironical, e.g., that our orthodox scientific community does not even know what powers an EM circuit—energy extracted directly from the vacuum by the asymmetry of the source charge (considered in its modern view as a dipolarity) and by the source

method in defending archaic theory in the face of experiments that falsify it, that the ubiquitous violation of the law of increasing entropy (second law of thermodynamics) by electrodynamics itself continues to be adamantly resisted using ad hominem and inflammatory attacks, slander and libel, and destruction of scientific careers of researchers. We flatly are not getting our taxpayer money's worth from our present scientific community, and—barring a Stalin-like shakeup from top to bottom—we are not going to get our money's worth in the future unless the community is forced to free up funds for young graduate students and postdoctoral scientists wishing to work in "out of the box" scientific areas. As Max Planck stated, *"An important scientific innovation rarely makes its way by gradually winning over and converting its opponents: it rarely happens that Saul becomes Paul. What does happen is that its opponents gradually die out, and that the growing generation is familiarized with the ideas from the beginning."* In other words, one doesn't get a scientific innovation until the old dogs so bitterly opposing it just die off and get out of the way. This long-known and stated characteristic of the scientific community—its fierce and unrelenting resistance to change and innovation—is presently the greatest threat to the survival of this nation.

dipole (Figure 36).


Generators make dipoles.
They do not add one watt to the attached powerline.
BOILER
STEAM TURBINE
GENERATOR
FLOW OF TIME-ENERGY (in vacuum)
SOURCE DIPOLE IN GENERATOR
giant energy flow wasted
"Make dipole" function
(Entropic)
"True negative resistor" function
(Giant negentropy)

Figure 36 Energy extracted from the vacuum by the asymmetry of the source dipole powers every electric power line and electric circuit.

A Typical Example: The Suppression of Cold Fusion

As an example, much of U.S. Science—dominated by nuclear factions since the advent of the atomic bomb in WWII—vehemently attacked cold fusion and the cold fusion researchers, including wholesale ad hominem attacks, with a viciousness seldom seen in the history of science. Many dogmatic scientists declared the entire field at best a mistake and at worst a fraud. Even the character of many of the leading cold fusion scientists was openly impugned and the researchers were slandered and libeled. All this was done by conventional dogmatic scientists who have not solved the fundamental source charge problem {10,12}, have no inkling that all EM energy in 3-space comes from the time-domain {10}, and have not a clue as to what really powers every EM circuit. Since they also do not know where the electrical energy driving the chemistry actually comes from, they have no knowledge of the effects of time-energy in electrolyte solutions.

They also appear to have little or no knowledge of the implications of Evans' and Searles' *transient fluctuation theorem*[19] in thermodynamics showing to what degree the second law of thermodynamics can be violated and reactions can run in reverse, nor its extension to the micron (colloidal) size level and to two seconds in duration.[20] If they did, then they would realize that the Coulomb barrier provided by *repulsion* of like charges (such as two H+ ions), often reverses into the *attraction* of like charges, with the barrier changing into the Coulomb attractor. This can last (by experimental proof shown by Evans *et al.)* up to two seconds, in a volume of fluid up to a micron in diameter. Hence it is not "against the laws of physics and thermodynamics" to observe attraction of two protons in an electrolyte so closely that each enters the strong force region of the other and the two form a quasi-nucleus. In the decay of this reversal zone, the preferred decay of the quasi-nucleus can be by quark flipping in one of the protons, yielding an atom of deuterium emerging from the decayed time reversal zone. Such results have been meticulously observed in many cold fusion experiments in multiple labs and nations, and by multiple researchers. Since these and other novel nuclear transmutation results are *replicated* experiments (more than 600, in multiple labs, multiple nations, and by multiple researchers), it means that no amount of theory can refute them or the results. The harsh skeptics launching the frenzied ad hominem attacks are thus revealed as the unscientific bigots they are, since they ignore substantial experimental results that contradict the prevailing theory. The excess energy production and inexplicable new nuclides (Figures 21, 37, 38) obtained by these multiple experimenters are completely inexplicable by ordinary nuclear interactions in the accepted theory.

---

[19] D.J. Evans and D. J. Searles, *Phys. Rev. E*, Vol. *50*, 1994. p. 1645.

- Fennions time-reverse in even numbers
- Like charges cluster
- Aqueous solutions contain H+ ions,
  which are just protons
- Quarks flip as TR zone fades



$$({}_1H_1 + {}_1H_1) \rightarrow ({}_0n_1 + {}_1H_1) = {}_1H_2 \text{ deuterium}$$

Figure 37 Electronuclear reaction in a time-reversed zone producing excess deuterium ions.

---

[20] G. M. Wang, E. M. Sevick, Emil Mittag, Debra J. Searles, and Denis J. Evans, "Experimental Demonstration of Violations of the Second Law of Thermodynamics for Small Systems and Short Time Scales," *Phys. Rev. Lett.,* 89(5), 29 July 2002, 050601.



- As TR zone decays, quasi-nucleus is usually in an excited state
  - Decay action starts from every point in spacetime inside the nucleons
  - Moves from inside toward outside
  - Strikes the nearly free quarks first
- Decay occurs by easy quark flip
- Quasi-nucleus transmutes to an isobar
- If quasi-nucleus is a stable state in a forward time zone, no decay occurs.

$${}_1H_2 + {}_1H_2 \rightarrow {}_2He_4$$

Figure 38 Electronuclear reaction in a time-reversed zone producing excess alpha particles.

Meanwhile, the U.S. Patent Office has been instructed not to accept any patent applications that would interfere with present nuclear planning. Positive cold fusion results have also been successfully obtained in several U.S. government laboratories, including at China Lake where very strange instrumental effects have the experimental team puzzled. I proposed an explanation of those anomalies in August 1998, and have included it in my book just published in September 2002 {73}.

Revolutionary New Processes Are Hidden in the Cold Fusion Experimental Results

Once understood, cold fusion holds the breathtaking key to systems that consume *a tiny fraction of time flow itself* as a fuel to produce copious heat energy for the world's needs. Unknown to the conventional scientists, of course, electrodynamics itself already does this, but it has just not been recognized and accepted. Transducing one microsecond per second of time into transverse wave EM energy will produce some 9×10^{10} watts of real electrical power, if all the transduced EM energy is intercepted and used. This is the *real* way to extract energy from the vacuum and use it cleanly and cheaply.

To grasp such a notion, recall that the fundamental units used in physics are completely arbitrary. It is perfectly possible to express all physics in only a **single** fundamental unit—for example, *the joule*. Time then becomes totally a function of energy. So it is not so insane after all to express time as highly compressed energy. Mass is also highly compressed energy. That concept is now familiar after Einstein, the nuclear age, and $E = mc^2$. Time-as-energy is just as straightforward as mass-as-energy, but it has just not yet come into recognition.

The *use* of time as compressed energy, however, leads to some profoundly new types of electronuclear reactions presently unknown in particle physics. These new transduction reactions produce the new nuclides in cold fusion experiments, and generate the electronuclear interaction. We explain that in some detail in our new book, *Energy from the Vacuum,* previously cited {10}.

When interpreted as using time-energy, cold fusion shows us the way to a new electronuclear regime of nuclear reactions where nuclei, elements, and compounds can just be directly assembled by comparatively weak (in terms of *spatial* energy!) electromagnetic interactions. Presently we have made substantial progress in understanding the fundamental mechanisms generating these electronuclear reactions, after presenting preliminary results in August 1998.

As one example, time-reversing a single fermion (a particle with spin 1/2, 3/2, etc.) is precluded by the Pauli exclusion principle. But one can time reverse *two* of them, or any even number n, where they act as a semi-boson or group of semi-bosons. Simply put, if a time-reversal zone is established momentarily in the region where like charges exist, then the n-tuple fermion cluster can be achieved because the law of attraction and repulsion of charges is temporarily reversed {74,75}. This unexpected "attraction of paired fermions of like sign" will form quasi-nuclei in many cases, particularly in small clusters of two or four, etc.

Hence two H+ hydrogen ions (two protons) in such a time-reversal zone in a fluid are drawn together into a quasi-nucleus, which actually is an excited isomer of deuterium (Figure 37). Time-reversal zones are temporary in cold fusion experiments due to the statistics of their formation and the transient fluctuation theorem {76} of thermodynamics. As the time reversal zone decays, the quasi-nucleus of two protons is increasingly in an excited and unbalanced state. The excited-state diproton nucleus decays by flipping a quark in one proton, converting it to a neutron. That produces a *neutron + proton nucleus,* which is a deuterium ion, strictly by electronuclear means. Or four protons may cluster by "attraction in a time-reversal zone" and form a 4-p nucleus. That is an excited isomer of a helium nucleus. As the time-reversal zone decays, first one quark flips in one proton and then another quark flips in a second proton. That produces a helium nucleus - i.e., an *alpha particle.* Or two deuterium ions can attract and form a quasi-nucleus (Figure 38), which is already an exact isomer of a helium nucleus and thus easily decays into an alpha particle by simply "tightening" as the weakened strong force recovers faster than the Coulomb force can reduce, vanish, and resume in the opposite direction. The exact reaction equations for these reactions are given in my new book, *Energy from the Vacuum* {10}.

We filed an Invention Disclosure on the process of forming and using time-reversal zones to cause like charges to attract and unlike charges to repel *in* ***vacuo,*** in fluids, and in other media, resulting in the formation of semi-nuclei as excited isomer states of other nuclei, followed by decay into new nuclides. We will follow it with patent applications in the future. This represents a completely new kind of particle physics interaction presently not included in the textbooks, and not requiring high-energy processes. Literally thousands of new nuclear interactions—all *permissibly* violating the second law of thermodynamics because the statistics permit such violations and experiments prove it—are now possible.

Cold fusion does indeed hold a new kind of nuclear physics in its hand—but a physics presently considered very alien by our orthodox nuclear science community. For decades nuclear scientists have been seeking ever more spat*ially* energetic particle smashing, believing that extreme high energy nuclear reactions and transmutations cannot possibly be done with charged particles at low *spatial* energy. One is sympathetic to the scientists, because even the **concept** of "low spatial energy transmutation" itself sounds like an oxymoron. And it would be, *if one were limited to spatial energy alone*, as is presently assumed by physicists. But one is also speaking of the neglected and compressed *huge time-energy* component of those low-spatial energy photons, and that is quite a different matter. The lower the spatial energy of the photon (the lower its frequency), the greater the amount of compressed energy transported in the time component as "time". The transposition of time-polarized EM energy into longitudinally polarized EM energy—and vice versa—is already justified in quantum field theory. Use of that extremely high energy component by its transposition or partial transposition into spatial energy in fact provides a much higher energy physics interaction than present orthodox high **energy** physics utilizes, knows, or considers.

Almost all the learned scientists are thinking *only* of spatial energy, since that is **the** only kind they have been "taught" to consider. Hence, from their view (i.e., on the premise of their implicit *assumption)* it is perfectly "logical" to condemn cold fusion, since in their view, "cold" implies low (spatial) energy and "fusion" implies high (spatial) energy transmutation. What is unknown to the orthodox community is that the "cold" in cold fusion also implies "extraordinarily high time-energy". So with a little transduction of highly compressed time-energy **into** spatial energy, "cold" fusion actually can imply "extremely high spatial **energy** made available by transduction" also.

As an example, the Chief Editor of *Science* recently had the courage {77} to **publish** results of sonoluminescence research reporting positive experimental transmutation results {78}. A paper was then published in *Nature* {79}, pointing out that the (spatial) energy involved is insufficient for such nuclear transmutation temperature, thereby implying that the reactions reported by the first researchers are not possible.

However, given formation of a time-reversal zone, this second paper is not necessarily applicable to the sonoluminescence fusion process, because the paper is based on an unwitting two-part premise that *(i) only spatial energy can be used for nuclear transmutation and (ii) no time-reversal zones exist to nullify that premise by having reactions (such as the law of attraction and repulsion of charges) run backwards.* That premise is already experimentally proven to be invalid by Evans et al., and it fails when the time reversal zone effect is considered.

We strongly stress that thermodynamics—both in theory and as demonstrated in experiments—not only allows but predicts—for a certain fraction of the time—the formation and existence of just such "reversal zones" where the usual reactions *run in reverse* {76}. It is also experimentally proven {54}. In that case a much higher energy—time energy—can be and is employed to convert the Coulomb barrier into the Coulomb attractor.[21] We know now (from the experimental demonstrations by Denis Evans et al.) that such "reversal zones" may be up to a micron in size and may endure for up to two seconds. The subsequent decay of that TRZ then allows the quasi-nuclei temporarily formed in it to decay by quark flipping alone, allowing the quasi-nucleus to easily transmute into a perfectly well known nuclear reaction product.

To quote Arthur C. Clarke, when a learned scientist says something is *possible*, he is probably right. When he says something is *impossible*, he is probably wrong.

Stalin's Dictatorial Impact on Soviet Scientific Management's Response

Stalin was a powerful dictator. He simply killed or jailed those who opposed his will. So after his blunt order (Figure 1) circa latter 1945 to find a great new technical breakthrough area quickly, his Academicians and high level science managers were faced with a severe dilemma: They could not afford to *oppose or criticize a vigorous search* for new innovations and a great breakthrough, and they could not remain passive. Their very lives depended on they themselves *personally finding such a breakthrough in great haste and presenting it to Stalin*. They had to actively spur the efforts of their most outstanding subordinates and Soviet science itself, or suffer dire personal consequences. Siberia and prison camps loomed for the lot of them unless they produced.

To put it bluntly, Stalin "got their collective attention" and their "whole-hearted support." Those few who resisted simply were shipped post-haste to the notorious prisons of Siberia, and worked to death in short order.

---

[21] We strongly point out that, when the reactions run backward and negentropy appears in those reversed regions, the conservation of energy law is violated unless time-energy is being converted to spatial energy. Either we must begin accounting time as energy, or we must give up the conservation of energy law itself. The obvious solution is to account the time energy being utilized, as well as the 3-space energy.

So the highest-level Soviet scientific managers now desperately demanded of their subordinate scientists *anything*—*anything at all*—that was novel and had breakthrough implications. An almost convulsive national scientific effort was launched immediately, with hardly a detracting voice. A great team of the very **best** Soviet scientists was rapidly formed and methodically searched the scientific literature of the world from beginning to end. Nothing even remotely like that search and review has ever occurred in the West.

For example, one great technical center set up by the Soviets had a staff of about 2000 Ph.D.s with associated translators, staffs, etc. The Soviets purchased and **hauled** in copies of all the scientific literature of the West—by the shiploads—to such centers. Their scientists then methodically went through the material, **journal** by journal, paper by paper, page by page. There are and always have **been** myriads of innovations and discoveries sitting on the shelf in the scientific **literature,** never followed up, or opposed by standard models and credos. The first tier of reviewing Soviet scientists was composed of excellent scientists. They skimmed out the "cream" into a select pile which the second tier then analyzed in depth. The second tier was composed of the best nonlinear scientists in **the** world—the "superscientists."

They were seeking *new principles of nature that could rapidly be developed into highly advanced technology*, and they found them—sitting there in the literature, already pointed out, and long ignored by the Western scientific community.

Shortly Stalin had his great new breakthrough area emerging, and they had their heads.

Our Own Science Community's Progress During These Decades

For decades foundations physicists (Bunge, Feynman, Wheeler, Lindsey, **Margenau,** etc.) in the U.S. have repeatedly pointed out the substantial foundations problems in electrodynamics. Nobelist Feynman and the great John Wheeler tried to "fix" the problem whereby electrodynamics still erroneously assumes force fields in a space filled with a *material ether* (unit point positive charge, unit point north pole, and unit point mass assumed at every point in **space).** Unfortunately they failed, primarily because their absorber theory {80} contradicted the photon hypothesis and hence quantum mechanics.

Meanwhile, our own National Science Foundation and National Academy of Sciences has directed only minimal work on correcting electrodynamics and dramatically extending it. Faraday and Maxwell—as did every other scientist at the time—rigorously assumed a material ether. Maxwell's equations also implicitly included that material ether assumption. They still do, even after Heaviside's truncation and Lorentz's symmetrical regauging, because none of the Maxwell-Heaviside equations were changed to eliminate the material fields in **space** (material ether) assumption after the Michelson-Morley experiments falsified it.

Every major university in America still teaches that implicit material ether, even though it was falsified over a century ago. That is an exact measure of the caliber of "foundations" work our own scientific community does if left alone. *In more than 100 years, they have not even chosen to root out the material ether from electrodynamics.*



Figure 39 This polluted and suffering planet. Direct result of the scientific community's adamant resistance to upgrading classical electrodynamics and electrical engineering.

The prevailing flippant attitude is that, "Well, your TV set works, doesn't it?" Yes it does, but we also do not have practical electrogravitation and inertial propulsion, nor do we have cheap clean EM energy from the vacuum. Instead, we have a severely polluted planet (Figure 39), ever increasing deaths from biospheric fumes and polluting byproducts, increasing destruction of species, and a monstrous unleashing of far more coal and hydrocarbon burning in our near future while the world tears itself apart and destroys its economy and civilization in a rising series of oil and energy wars. The direct responsibility for that mess lies directly with the scientific community and its fierce resistance to innovative research and development, and changing a century-old, long outmoded classical EM and electrical engineering model.

Wryly put, it's high time we "got the lead out" of EM field theory, where the lead is the material ether and other non-sequiturs cluttering the theory.

Such drastic modeling errors would not be tolerated of government-funded aerospace engineers and contractors developing a new missile system. So it should be equally intolerable in the government-funded scientific community and in fact in the civilian scientific community as well, and it should not be tolerated of either the National Academy of Sciences or the National Science Foundation.

Einstein {81} said it perfectly, as follows:

> *"...the scientist makes use of a whole arsenal of concepts which he imbibed practically with his mother's milk; and seldom if ever is he aware of the eternally problematic character of his concepts. He uses this conceptual material, or, speaking more exactly, these conceptual tools of thought, as something obviously, immutably given; something having an objective value of truth which is hardly even, and in any case not seriously, to be doubted... in the interests of science it is necessary over and over again to engage in the critique of these fundamental concepts, in order that we may not unconsciously be ruled by them."*

Upholding and perpetuating flawed electrodynamics models seriously impedes **the** progress of scientific development and revolutionary new technology.[22,23] At some point, one must legitimately question the upper management of the U.S. scientific community for not modifying classical EM and electrical engineering to include the active vacuum exchange with every charge and EM system. In not doing so, they continue to advocate perpetual motion source charges, creating energy from nothing, on a scale unparalleled in history.

It is little wonder that we do not have electrical power systems that successfully a**nd** freely utilize more than a trillionth of the vacuum energy they freely extract from the local vacuum. *There is not now and there never has been a single*

---

[22] Oddly, the conventional electrodynamics model assumes that every source charge freely creates **energy** out of nothing at all, and pours this energy out continuously in all directions, thereby establishing its associated EM fields and potentials at light speed, reaching out across the u**niverse.** From the 1960s alone, the total assumption of incredibly vast numbers of perpetual motion machines has been carefully hidden from the new students, so that today even many **professors** do not realize that in their model all EM fields and potentials, and every joule of EM energy in the universe, are assumed to be created by a vast assortment of perpetual motion machines called source charges. That problem has not been solved in electrical engineering or in classical electrodynamics, and if the scientists have their way, it is not going to be solved. Yet the basis for its solution—the asymmetry of opposite charges such as the dipolarity (in the modern view) of a source charge—has been in particle physics since 1957, with the award of the Nobel Prize to Lee and Yang in December of that year.

[22] One keeps one's sense of humor. The raucous skeptics and "defenders of the orthodox EM fa**ith"** who so noisily denounce legitimate COP>1.0 EM system researchers as "perpetual motion nuts", are themselves unwittingly the greatest perpetual motion nuts ever recorded in history. Further, they are so ignorant of what their present model actually means, that they do not even know it. It is one thing to be ignorant and to recognize it; it is quite another thing to be ignorant and so ignorant one does not know it—45 years after broken symmetry was rigorously established experimentally by Wu and her colleagues, and the Nobel Prize awarded to Lee and Yang.

electrical engineering department, professor, or textbook that knows what actually powers an EM circuit—real observable EM energy extracted from the local seething vacuum by the source charges and the source dipolarity.

Since our scientific community cannot seem to make such a simple change (as including the active vacuum's interaction with every charge and the charge's broken symmetry in that interaction) even 45 years after the basis for that change has been resoundingly proven in particle physics, our national survival is at stake and the nation itself is seriously threatened by the superweapons developed by the KGB over the last five decades. We would have already been totally destroyed—twice in 1997 alone—had it not been for the intervention of a friendly little foreign nation. My colleagues and I played a very small alerting role in those affairs, so we are speaking from experience, not from extrapolation. We would be quickly destroyed today, were it not for the continuing "balance of terror" provided by the little nation.

U.S. Scientists Have Committed Monstrous Crimes and Gone Unpunished

Rather sadly, we also point out another thing that has to be said: *scientists are no more moral or immoral than any other slice of American citizens.* A percentage of scientists is capable of committing horrible scientific crimes, as distasteful as such a statement may be. That includes the deliberate experimentation on humans, resulting in deaths. In short, at least manslaughter and perhaps even murder, since knowledge of the probable results was there beforehand.

One would think U.S. scientists would *never* scientifically condone and perform experiments leading to mass deaths for 30 years (i) as they did in the Tuskegee case in Alabama. Over 400 poor blacks were supposedly treated for syphilis, while actually not being treated at all, but were deliberately tricked and allowed to rot with syphilis so our "ethical" scientists could watch how their brains decayed, so to speak. Over 100 of those poor blacks died with the disease while the scientists cold-bloodedly watched them expire and kept meticulous records. Or (ii) as they did in the case of whole body nuclear radiation for 30 years—again by trickery, deceit, and illegal use of security classification to hide these acts—of helpless retarded children and others, some of whom also died.

Once these heinous incidents were exposed publicly, the political power of the scientific community is such that *no scientist was ever indicted or tried for these heinous mass murders, and none is going to be.* The scientific community *has* *__not__* fiercely called for punishment of these mass murderers amongst their midst—guilty of precisely the same kind of horrible actions for which we tried and executed war criminals at Nuremberg.

Incredibly, the President of the United States formally apologized for these incidents! He did not turn the case over to the Justice Department for prosecution of high crimes against humanity and mass murder, *as would have* *been done for ordinary citizens.* Had a single doctor in his private clinic done such things on his own, he would have been arrested, summarily tried, and either sentenced to life in prison or executed.

The sad thing is that there was really no sharp clamor from the scientific community to bring their fellow scientists to justice, a la Nuremberg. By their silence, the organized scientific community showed a side that scientists are loftily not supposed to possess. *So long as the scientific community continues to tolerate those mass murders of American citizens and not call for justice, then just so long do they stand convicted by their own resounding silence and inaction.*

We cite these painful incidents (there are others!) to point out that one must not deify the scientific community. The conduct of science is no better and no worse than the conduct of human affairs in other areas. Science is also a big business, and it has its moral scientists and its immoral scientists. It does its moral business and it does its immoral business.

We painfully submit that both sides of the scientific character must be considered, when one examines such things as the tolerance or intolerance of the scientific community to dramatic innovation and "out of the box" research. We have to consider it now, because it has become a serious threat to the continued survival of our nation. The conduct of scientific affairs will unavoidably include suppression, maneuvering, spin control, and fierce struggle for power and funds—such is in the very nature of human beings, and it is present in the scientific community on a bell-shaped curve as in all other human communities. It is ongoing widely today, and to an uncomfortably large extent much of science has been captured and effectively controlled by controlling the scientific funding and prescribing what research must be done for the funds available.

As the French say, "The more things change, the more they remain the same." Science is still the same way as it was when Planck made his famous statement. It will still be that way tomorrow, and a century from now. As with any other big enterprise, it has to have checks and balances imposed and enforced on it from outside—by the government itself. Little or no indication exists of that happening in the near future, until we get something like an anthrax spray attack on a large city, and have a million or more Americans dying in the streets.

Energetics: New Principles of Physics and How the Soviets Found Them

Under Stalin's whip, the Soviets particularly sought anything that indicated *possible new principles of nature.* It is no accident that Nobelist Petr Kapitsa later informed Nikita Khrushchev that a means of total neutralization of foreign missiles could only come from *a group of new principles in physics called energetics.* A group of new principles is precisely what energetics *is.* So if our scientific and intelligence communities wish to understand energetics, they must first understand the new principles it is based upon. They cannot just simply apply ordinary electrodynamics and "business as usual" as they have largely done. The massive Soviet scientific search program spurred by Stalin is where those new principles came from.

When the first tier of Soviet review scientists found something that had not been followed up, and saw that it had significant implications if found valid, that paper was laid aside into a "select" pile. That select pile then went to the "super" scientists, for full-blown review and analysis by some of the brightest and sharpest minds on the planet.

The Russians came up almost immediately with Whittaker's 1903 and 1904 work. That work shows a hidden electrodynamic *longitudinal* EM wavepair structure (in phase conjugate pairs) inside the scalar potential and comprising it.

This is a dramatic extension of electrodynamics to incorporate a full-infolded general relativity infolded inside the electrodynamics. Whittaker showed that scalar potential functions in interference already *create* all the "normal" fields and waves anyway (the beginning of superpotential theory). This novel interferometry and its inherent capability for action-at-a-distance did not elude the Russian superscientists. The superb Soviet scientific team came up with that and with much, much more.

Nothing like the comprehensive, intense review of the entire scientific literature has been accomplished by the U.S. scientific community. Nothing like it is being done now.

Longitudinal EM Wave Interferometry Energetics Was Almost Immediately Uncovered

At the end of WW II, the German radar team and infrared team were taken to Russia. Both teams were years ahead of their Western counterparts.

One of my close colleagues has validated that the German radar team had some severe instrumental anomalies while still in Germany. We think this is what they were:

In WW II the Germans invented radar absorbing materials, to coat their submarine snorkels and prevent Allied antisubmarine warfare bombers from tracking the snorkels and destroying the subs. A wide variety of highly nonlinear, doped materials were investigated. In addition to single beam radar cross section, the Germans also examined the materials in multi-beam illumination circumstances.

It appears that, in some multibeam experiments with some materials, conditions were just right so that the multi-illuminated absorbing material acted as a pumped phase conjugate mirror (PCM), and wave-to-wave interactions emerged. This meant that the absorber material PCM would suddenly gather up all the energy in the pumping beams, use one of the other beams as a signal input beam, and fire an amplified retroreflected pulse right back down the signal input beam, wrecking the experiment and creating havoc in surrounding equipment.

When the German radar team went to Russia, their knowledge of these anomalies went with them. In the desperate Russian scientific climate to find *lust such anomalies,* this startling and anomalous phenomenon would have been exhaustingly examined and studied, once the German radar engineers got to Russia to their new laboratories.

In short, it appears that the Russians quickly came up with what today is called "nonlinear phase conjugate optics," but first in the radar band rather than optics.[24] So before 1950, it appears that the Russians already had working phase conjugating pumped phase conjugate mirrors for the radar bands and in other bands.

Fisher {82} details that we Americans did not "stumble onto" practical phase conjugate optics experiments until Russian physicists briefed Lawrence Livermore National Laboratory scientists in 1972 about the strange wave in **many** of their optical experiments that "came out of nowhere and restored order **from** disorder." At that time, the KGB energetics weapon scientists had known aboutphase conjugate retroreflection and its amplified pumping, for more than 20 years. Indeed, the first giant strategic scalar interferometers had already been deployed and utilized to kill the U.S.S. Thresher nearly a decade earlier (Figure **6).**

By 1950 Russian Energetics Was Off and Running

By the beginning of the 1950s, the Russian scientists under iron KGB control were already experimenting with "scalar potential interferometry" at a distance, a la Whittaker 1904. Here transverse EM waves, EM fields, and EM energy—either *divergent* (heating) positive energy or *convergent* (cooling) negative enery—could be readily created at a distance {83} (Figures 40 and 41). Further, the longitudinal EM wavepairs used in this interferometry had the marvelous characteristic of easily penetrating right through the earth and ocean, with only a little intervening interaction, given that the LWs are sufficiently well made {84}. The interferometry "beams" can and do also move superluminally—again, right through the earth and ocean.

---

[24] **Of course, they would also have investigated it at all other bands as well.**


Meeting of timed pulses causes explosive cooling
COOLING IN INTERFERENCE ZONE
Ambient vacuum potential in distant interference zone
Φ_a
subspace
Bias
Heat extracted
XMTR/RCVR
XMTR/RCVR
subspace
Φ_T
Electrical ground potential of transmitter
Heat emerges at transmitter/receiver
Heat emerges at transmitter/receiver

Figure 40 Scalar interferometry in the endothermic (cooling) mode.

It is not accidental that Admiral Gorshkov, head of the Soviet Navy, would later bluntly state: *"We have made the oceans of the world transparent."* And so they had.


Energy input to transmitter/receiver
Energy input to transmitter/receiver
XMTR/RCVR
Φ_T
Electrical ground potential of transmitter
XMTR/RCVR
subspace
subspace
Bias
Heating in interference zone
Φ_a
Ambient vacuum potential in distant interference zone
Meeting of timed pulses causes explosive heating

Figure 41 Scalar interferometry in the exothermic (heating) mode.

By 1950, the Russian scientists were experimenting with deliberately creating and phase conjugating longitudinal EM waves, forming phase conjugate wavepairs. They then assembled the desired (mathematically calculated) sets of those waves, adjusted frequencies and magnitudes, phasing, etc., to produce EM potentials having a desired deterministic internal spacetime curvature set (internal spacetime engines) and dynamics.

As a result, by the mid-50s Russian weapon scientists were already experimenting in *bioenergetics* with the direct inductance of diseases and health changes via the transmission into human targets of such "internally structured" EM potentials, fields, and waves. They were also experimenting with the production of EM energy, potentials, fields, and waves at a distance, directly through the earth and the ocean. Either heating (energy flow divergence) (Figure 41) or cooling (energy flow reconvergence) (Figure 40) could be produced at will in the distant interference zone, merely by altering the bias voltage on the chassis grounds of the interferometer's transmitters. Rapid switching between the exothermic and endothermic modes thus was straightforward{85}, as demonstrated (Figure 35).

By the latter '50s, longitudinal wave interferometry weapons had already emerged from advanced engineering development and were in full production engineering toward deployment. The LIDA device {86} and even more advanced versions for directly affecting the human mind and its state of consciousness had emerged in *psychoenergetics* as one class of devices rather openly released and utilized. The LIDA uses structured EM microwaves {87} to induce a hypnogogic or cataleptic type of trance-like state in either a human or a cat. as tested years later by Dr. Ross Adey of the U.S. Early prototypes were purportedly used against our prisoners in North Korea during the Korean War to assist in their brainwashing by their North Korean Captors. Prisoners reported that its effects were irresistible.

Meanwhile, energetics weapon testing in several major modes was being conducted, particularly from Soviet research ships over remote regions of the ocean and at night. Descriptions of such tests—many of them seen by passing ship's captains—can readily be found in the open maritime literature. We gathered and published many such incidents and cited references.

Deployment of the Soviet Energetics Weapons and Their Quick Use

In January 1960 Khrushchev spoke obliquely of these "fantastic" new superweapons, just within the portfolio of the Soviet scientists, so to speak, in an important speech to the Presidium. Parts of that speech were reported in the *New York Times* {88}. No one in the West knew what Khrushchev was talking about. Our intelligence community, which bases many of its assessments on the tired old phrase "We have no evidence that..." simply treated it as propaganda, It wasn't, and the U.S.S. Thresher was to be destroyed (Figure 6) three years later by that same weapon Khrushchev was speaking of.

Khrushchev began rapidly inserting long-range missiles and nuclear warheads into Cuba in 1962, precipitating the Cuban Missile Crisis. Kennedy knew Khrushchev's strategic bombers and rockets were in horrible shape, due to direct information received from Colonel Oleg Penkovskiy, a Russian spy in our employ courtesy of British Intelligence. No one knew of the superweapons, but they were not yet operationally ready in Oct.-Nov. 1962. So Kennedy called Khrushchev's bluff and faced him off. Blustering awhile to obtain U.S. assurance that it would not invade Cuba, Khrushchev was forced to back down and withdraw the missiles. In his exuberance he had simply moved too fast in inserting the missiles into Cuba. Had he waited a few months later, the strategic superweapons would have been operational and ready. Any U.S. naval blockading force would have thus faced quick and eerie destruction or disabling, as was soon to be demonstrated in the case of the U.S.S. Thresher and its surface companion, the U.S.S. Skylark.

This severe loss of face by Khrushchev, before the Communist Party, made it imperative that he do something quite dramatic to stay in power, and do it as quickly as possible.

Khrushchev's first large, full-up, strategic longitudinal EM wave energetics interferometer weapon became operational on site by April 1, 1963. A few days later, Khrushchev employed it to kill the U.S.S. Thresher atomic submarine (Figure 6) underwater off the East Coast of the U.S. By simply creating EM noise in an interference zone placed on, in, and around the sub underwater, and thus jamming the sub's electrical controls so that it could not be controlled, the helpless sub sank to crush depth and imploded. The U.S.S. Skylark on the surface had multiple systems seriously jammed or rendered nonoperational. This was the Russian deception plan, to have the kill of the sub resemble an accident.

One day after the successful clandestine kill of the Thresher, the same weapon was used to demonstrate a powerful underwater electromagnetic burst 100 miles north of Puerto Rico (Figure 42). The energetics underwater burst equaled a substantial deep underwater nuclear explosion in size. The burst was seen by a passing U.S. jetliner crew and was reported to the FBI and the U.S. Coast Guard when the aircraft landed in Florida. A colleague interviewed the co-pilot of the aircraft, and relayed the interview information to me.

Khrushchev's Second Demonstration

Deep Underwater EM Explosion 11 Apr. 1963

(Similar to this photo set of a deep underwater nuclear **test** explosion)

Phenomena observed and reported by passing U S jetliner

100 miles north of Puerto Rico, over Puerto Rican Trench (One of the deepest parts of the ocean)



Figure 42 Deep underwater nuclear burst, demonstrating same water phenomenology produced by Khrushchev's second demonstration on 11 Apr. 1963, the day after killing the U.S.S. Thresher.

Why the Soviets Could Continue to Attack and Kill U.S. Targets with Impunity

Ironically, Khrushchev clearly demonstrated the inability of U.S. science to comprehend the numerous test incidents of Soviet LW interferometers, including the actual destruction of strategic U.S. targets (our latest and greatest nuclear attack submarine!) right off our coast. *The greatest strategic weakness of the U.S.—and the thing that may yet completely destroy all of us—is the continuing snail-like pace of U.S. scientific progress in revising, correcting, and extending its seriously flawed classical electrodynamics model. This scientific inertia placed us several decades behind in development of defenses in the areas of longitudinal EM wave weapons, quantum potential weapons, and causal system weapons. It countered our strategic nuclear armada for two decades. We were for some time analogous to the Spanish Navy with its wooden ships, when it faced and was destroyed by American steel ships. Hopefully at least some more modern work has now been accomplished in higher group symmetry electrodynamics, so that we are not quite as defenseless as we formerly were. But we still have a very long way to go.*

When one performs a standard strategic analysis on a nation, one of the areas examined in depth is called *national style.* One of the major characteristics in the U.S. **national** style is that we do not react to slowly increasing threats or changes

(Figure 43). That style particularly applies to the scientific community. Because of it, the Russians knew that our government only inches forward in achieving new *basic* science. We run at enormous speed, doing *applied* science. We are essentially Romans and great engineers. We are largely not Greeks and not great esthetics discoverers. We also will just ignore new threats if they emerge very slowly and are only gradually perceived, and we will hide behind that infamous phrase, "We have no evidence that..."



BOA CONSTRICTOR LIGHTNING STRIKE

Americans tend not to react to slowly increasing things,
but react to rapidly increasing things.

Figure 43 America's national style: we do not react to slowly increasing threats.

In short, *we react to the coiled rattlesnake, not to the boa constrictor*. We are now in a long, bloody, costly war against terrorism because of that very characteristic of our national style. For decades, the slowly increasing infiltration of terrorists and their weapons was just ignored. Oh, yes, the official "threat studies" pointed it out, placidly.[25] But no one got very excited about it. The prevailing attitude was that "Ah, yes, but nothing like that will happen on *my* watch!"

As clearly demonstrated by their successful decades-long radiation of the U.S. Embassy in Moscow, the KGB chess masters knew that, if the test kills using their superweapons were not too often repeated, and if they even vaguely resembled other things known in the world, the U.S. scientific community and government investigators would resist all suggestions of Russian superweapons and super technology using new principles of nature. And so would our intelligence community, since they rely on the scientific community for their scientific assessments. They were well aware of our historical "ostrich" position (Figure44).

---

[25] Indeed, if one will look at the threat studies prior to William Cohen taking office as U.S. Secretary of Defense, one will find widespread complacency about the terrorist threat, and mostly just lip service to it. It was definitely not very important to most of the intelligence and scientific community. Cohen built a fire under the entire threat community, forcing them to get their act together and start actually studying the terrorist threat, asymmetrical warfare capabilities and dangers, and what could be done about it. He did force the research and threat communities to do a creditable job of studying it, and to publish reports detailing it. Unfortunately, the tenor of the political community outside SecDef Cohen's control was basically "business as usual, not to worry." September 11, 2001 changed all that forever. Once again we had waited until the rattlesnake struck and actually bit us, before the nation rose up and paid attention.


We're running out of energy!
We must redouble our efforts!
We must gigantically centralize!
We have to keep polluting the Earth, if we are to have lots of electrical energy! There is no free lunch!
No!
Every dipole in the universe is a continuous free EM energy generator, continuously extracting and pouring out enormous EM energy from the active local vacuum.

Figure 44 The only energy resource problem is the theoretical ostrich problem in science. We *must* become theoretical owls, rather than ostriches.

The KGB deception just depended upon the U.S. tiger to keep its stripes and exhibit its normal reactions or lack thereof. They also utilized (i) a series of strategic deception plans, deliberately designed to perform the tests suggestive of discredited phenomena such as UFO reporting and "lights at night" types of things, and (ii) a continuing series of subtle and anomalous stimuli (probes) designed to rather slowly attract the attention of U.S. Government at high levels, and of state-of-the-art U.S. government scientific contractors as well. The trick was not to attract U.S. attention *too suddenly or too strongly.* Show them the slow boa constrictor, not the lightning-fast rattler, and see how they reacted, if at all. By their reactions, the KGB could assess whether or not the U.S. government, intelligence, and scientific communities understood what was happening.

Precisely as anticipated by the KGB, we showed them for some decades that we really had little or no comprehension of the superweapons and their testing right over our heads. Even today, at least in the open community there is still little recognition, even of the violent weather war raging right over our own heads since July 4, 1976 and easily recognized.[26]

A case in point was the deliberate induction of diseases and health changes in U.S. personnel in the U.S. Embassy in Moscow for over 40 years (Figure 11). On a continuing basis, this excellent intelligence probe showed (by the U.S.'s actions or lack thereof) that we knew nothing about energetics.

Another KGB probe method was to kill a target once in a while, such as a jetliner or a submarine (deliberately rather seldom here, because the U.S. military would react if a certain frequency threshold were exceeded). Such kills resemble or can be posed as natural accidents or terrorist incidents. Quite a number of such incidents have occurred over the last three decades. The National Transportation Safety Board (NTSB) does not have higher group symmetry electrodynamics in its knowledge base or on its "checklists", nor does it have scalar interferometry, psychoenergetics, bioenergetics, or quantum potentials. In total, the results of deliberate stimuli of the U.S. continually assured the KGB chess masters (with 100% certainty) that we were a complete novice in the energetics game, and we were a lamb increasingly ready for the slaughter.

The major contribution to the continued success of these deliberate measures by the KGB has been provided for decades *in the "nonreaction of our own scientific community to slowly increasing threats."* To a lesser extent, our own intelligence community has also not focused sufficiently open-minded and highly qualified scientists to comprehend what is occurring in "new principles of nature" phenomena. "In the box" electrical engineers with Bachelor of Science degrees often are the analysts who analyze and assess such "out of the box" phenomena. Good luck!

Ordinary radar engineers may analyze an ordinary radar rather well. They will never, never become aware of a radar beam carrying infolded spacetime curvature engines. Such is not even in their lexicon or in their belief structure. They have no understanding or experience at all with longitudinal or time-polarized EM waves—most have never even *heard* of time-polarized EM waves. Mention curvatures of spacetime and their dynamics as deliberate "engines" impressed *inside* EM fields and potentials and waves, and one gets a glaze right over the eyes of the intelligence analyst recipient.

Western science conceives the mind as a meat computer, and does not understand that mind operations are totally electromagnetic and causal, but nonphysical—meaning in the time domain rather than in 3-space. Mind operations primarily use time-polarized EM waves rather than the transductions into transverse EM waves that the scientists actually measure. Hence Western science has not the foggiest notion as to what Russian psychoenergetics is all about, or how it can even "be." Certainly Western science has had no notion of deliberately creating time-polarized EM waves for direct engineering within the mind itself and within the mind's time-EM operations.

---

[26] The weather war over our heads has been particularly violent, and violently resisted, this year (2002).

As Arthur C. Clarke puts it in his "third law," *"Any sufficiently advanced technology is indistinguishable from magic. "*

Our long fascination with our "normal" (optics, IR, UV, radar, COMINT, satellite photography, etc.) technological intelligence collection systems will certainly not lead to any great breakthrough understanding of Russian energetics weaponry. That could only have come through HUMINT or COMINT. HUMINT is an area which, in the past, we have mostly just neglected or given lip service to for decades—and that came back to bite us severely on September 11, 2001. Even when we use HUMINT, it will not yield energetics results if the managers and directors themselves (and the agent handlers in the field) have no understanding of it and do not even know the proper questions to ask. And the system will not deliver results if the Intelligence Collection Requirements do not address the proper issues because ordinary electrical engineers and conventional electrical physicists having no inkling of psychoenergetics, or how it works, drew them up.

COMINT, on the other hand, suffers from its own extraordinary prolific output -as well as by only conventional analysts and conventional scientists examming it. Warehouses of COMINT information often have not even been read in any way except a casual glance by a junior analyst, and certainly have not had serious foundations scientists examine it in detail. ELINT does a little better insofar as a human analyst looking at it, but then what is a conventional electrical engineer or radar engineer to make of a giant hemispherical globe that slowly forms and expands from a tiny "seed bubble" of intense glowing light that appears (Figure 35), as it did off the Kurils in April 1984? What will he label it? "Light phenomena?" Where are the technical descriptors of the actual process forming the phenomenon? Where are the implications as to the strategic military use of such phenomena? The reader can see the point. For decades our analysts ignored prolific reports of such incidents by the hundreds. Why, everybody knew it was glowing swamp gas!

One cannot even write a proper "intelligence collection requirement" if one does not understand the basic phenomenology. So essentially no one in U.S. intelligence was writing the proper intelligence collection requirements.

The Science Behind the Soviet Energetics Weapons

The science behind these weapons is called *energetics*. (See again Figure 8.) Energetics consists of three branches, depending upon the nature of what is being targeted. The branch targeted against nonliving matter is just called the same name: *Energetics*. Targeted against living cells and biological material, the nervous system, etc., that branch of energetics is called *bioenergetics*. Against the mind and its functions (which are time-like and thus involve scalar photons and time-polarized EM waves), energetics is called *psychoenergetics* {89}. See Figure 45. Psychoenergetics includes both the conscious[27] and unconscious mind[28] of the individual—and even Jung's collective unconscious mind[29] of the entire human species {90}, and in fact even the collective unconscious mind in all species on earth, which corresponds to Lovelock's *Gaia* concept.


LEVELS OF CONSCIOUSNESS AND UNCONSCIOUSNESS
CONSCIOUS MIND
PERSONAL UNCONSCIOUS
FAMILY
CITY
STATE
CREED
NATION
GEOGRAPHICAL AREA
SPECIES
BIOSPHERIC
UNIVERSAL
INFINITE BEING
SPECIES
GAIA

Figure 45 Mind levels are subject to engineering by higher group symmetry electromagnetic (psychoenergetic) weapons.

We remind the reader that we are talking *physics,* not metaphysics and not mysticism. Strong Soviet physics developments over a sustained period have occurred in all three energetics areas, and these areas continue to be developed at present.

Once a nation enters into LW EM development, it has just entered into unified field theory development also. Particularly with longitudinal EM waves, one is directly engineering general relativity itself, and spacetime itself, as well as the dynamics of spacetime curvatures and sets of such curvatures. But it is an even greater unified field theory than Western physicists suspect. Not only does it unite the four forces of physics, but it also unites mind and matter and their dynamics as well.

---

[27] The conscious mind is a very fast serial processor, processing one snapshot at a time.

[28] The unconscious mind is a massively parallel processor, doing a great many things simultaneously. It is totally conscious, but multiply so. Since the serial processor conscious mind can only "see a single slide projector in the viewgraph at one time", when it "looks at the unconscious mind" it sees a large number of slides simultaneously, hence just sees "black" or "nothingness" (no single thing).

[29] Jung himself labeled it a *mind* (and hence a living entity). His modern followers shudder at such a concept, and very much downplay the "mind" and "entity" aspect, preferring that it just go away.

We shall also refer to time-polarized EM waves as *time-density waves*. The reason is that a time-polarized EM wave is one where the EM energy is on the time-axis and oscillating along it, like the squeezing of an accordion. In short, it is a longitudinal EM wave on the 4th Minkowski axis *ict*, where the only variable is *t*. Hence it is a wave of the variation of time-density along that axis.

All three branches of KGB energetics use longitudinal EM waves, longitudinal EM wave interferometry, and Whittaker-structuring of fields and waves to provide organized curvatures of spacetime known as *spacetime engines* or *vacuum engines*. They also use time-polarized EM waves, as mentioned above. Any or all can also employ the quantum potential as well as negative energy EMP aspects. For now, the reader should just recognize that each infolded longitudinal EM wavepair comprising the scalar potential, includes both a *time-density wave* along the time axis and a longitudinal EM wave in 3-space {91}. So ordinary electrostatic scalar potential fi—ordinary voltage—is made of a harmonic structure of *coupled time-polarized and longitudinal EM wavepairs.*

Oscillations of time density oscillate the local rate of flow of time. In turn, since time has the energy density of mass, its spatial energy equivalence W is given by $W = c^2t$. Any change in a time density wave is a very powerful oscillation of loca1 spacetime curvature. So time-density waves constitute a very powerful form of infolded general relativity, inside potentials and hence inside all EM waves and fields. The KGB weapon scientists call that inner general relativity (time density waves) the *information content of the field*. Unfortunately our follows confuse that term with common "spectral analysis" which it very definitely is not. But as part of the deception plan, the Russians are quite happy to help them think it is exactly that, and in fact the Russians go to some pains to continue to help our fellows think that.

KGB energetics involves the use of a highly structured general relativity infolded inside electrodynamics—inside EM potentials, fields, and waves regardless of type. In addition, that very special GR is using the very strong EM force along the time axis as the main agent of curvature. By deliberately structuring these time-polarized EM waves and their dynamics, extremely powerful *spacetime curvature engines* can be employed, either created locally or at a real distance, or also globally in an entire selected distant region.

Once these spacetime curvature engines structure the distant targeted spacetime region. Then in that interference zone the engines therein act upon any mass present. In theory, any physical effect known can be engineered, according to general relativity, once one can create and utilize the proper set of spacetime curvatures (the proper set of spacetime curvatures and their dynamics). In GR, curvature of spacetime acts directly upon any mass present, and vice versa. With such technology one can therefore *engineer mass* to any level and at any distance (and eventually in any quantity) at will, using energetics methodology. *The engineered mass may be either living or inert* {92}. It follows that bioenergetics and psychoenergetics effects can also be engineered at a distance in similar manner. All it requires is the proper engines for the effects desired in the targets desired.

By using time-density waves and their dynamics, mind itself can be engineered and controlled at a distance as in the cases of Captains Button (Figures 22 and 23) and Svoboda (Figure 24).

The Importance of Scalar Photons and Time-Density Waves

Now we digress momentarily. Again, there are four major photon polarizations in quantum field theory {93}. The first two are *transverse* photons, polarized in the x- and y-direction respectively (transversely to the line of propagation, which is customarily taken along the *z*- axis). Ordinary transverse EM waves are comprised of such photons or blends thereof. Though ignored, EM waves prior to interaction with mass do *transport EM time-energy* as well as EM spatial energy, though in electrodynamics that time-energy transport has been ignored, thus confusing the effect with the cause.

The third polarization is a *longitudinal* photon, vibrating along the *z*- direction (the direction of propagation). Obviously longitudinal EM waves are comprised of such longitudinal EM photons.

The fourth polarization is a *scalar* photon, since it oscillates only along the time axis (the word "scalar" refers to the fact that it has no vector field component in 3-space). In American physics the latter photon is largely ignored since time is not an observable in quantum mechanics. However, such scalar photons do comprise time-density waves and EM time-energy currents, and they are involved in powerfully curving spacetime via oscillating the time domain. Hence by their oscillations they produce spacetime curvature oscillations, which in turn project small components into 3-space. Sufficient such coherent projection components are in fact longitudinal waves in 3-space.

The combination of the scalar and longitudinal photons is observable as the instantaneous scalar potential, and when Whittaker's 1903 decomposition of the scalar potential is slightly corrected, then the scalar potential is comprised of coupled pairs of waves, where each pair consists of a time-polarized EM wave coupled to a longitudinal EM wave. The combination of the scalar and longitudinal EM waves in the presence of charge is observable as the macroscopic scalar potential. Negative charge absorbs the time-polarized photon from the time domain and re-emits a longitudinal photon in 3-space, while the positive charge absorbs a longitudinal photon from 3-space and re-emits a time-polarized photon in the time domain.

Psychoenergetics: Engineering the Mind-Matter Interaction by Engineering Mind

We shall be interested in what actually constitutes a living biological system in the psychoenergetics view (Figure 46). Mind operations are *time-like* rather than existing in 3-space, and for that reason mind and its operations are not observable. Observation is a *d/dt* operator acting on an LLLT ongoing interaction, which removes the T and leaves a frozen LLL snapshot, via d/dt(LLLT) => LLL. *Imposition of observation itself breaks,* any and all connection with time-like operations, including mind and its operations.


The body's cells and their parts are linked by a mutual quantum potential. Mind and thought (from a mindworld) occupy the internal SW biwave structure of the QP to that body, being continually disconnected and reconnected by the photon interaction generatrix for the flow of time.
ALL POTENTIALS IN THE BODY ARE ASSOCIATED WITH AND CONNECTED TO THE QUANTUM POTENTIAL.
THE BRAIN AND NERVOUS SYSTEM ARE SPECIAL TUNERS/SWITCHERS BETWEEN INNER AND OUTER EM "SIGNALS".
DEEP CONTROL IS VIA VACUUM ENGINES: NESTED STRUCTURING OF THE SWZ BIWAVES INSIDE, AND COMPRISING, THE SCALAR POTENTIALS.

Figure 46 A living biological system (psychoenergetics view).

"Dynamics" involves "velocity", and in general relativity's 4-space velocity is rotation (Figure 47). Any mind-operation or change is dynamics and produces a small velocity, which is a small rotation. This projects a very small component into 3-space, in the physical body, but still in the virtual state. We are speaking of physics rather than metaphysics! *Sufficient* coherent mind operations (changes) have just such small (virtual) rotation components in 3-space that will project coherent little projection components (virtual) into 3-space. Coherently sustaining these components (intent) results in their coherent integration to breach the quantum threshold and become detectable (produce an observable 3-space result). That is how an "intent" change sustained in the mind becomes an actual physical energy input to the body and nervous system.



- An object moving with velocity v < c has rotated slightly out of 3-space toward the time dimension.
- Its "projection" back into 3-space is shorter, providing the Lorentz-Fitzgerald contraction.
- When velocity v = c, a full right-angle turn has been made, and the object has "lost" its projection along its direction of motion.
- Hence it appears as a 2-dimensional plane moving at the speed of light; in short, a photon or a light wave.

Lorentz-Fitzgerald Contraction

Figure 47 Velocity is rotation. Necessary to understand the mind-body coupling mechanism.

We again stress that the scalar potential is comprised of coupled time-density and longitudinal EM wavepairs. Mental operations also are time-density wave changes, hence they are changes to the interior of potentials, including the ambient potential of the vacuum itself. Potentials superpose, and their coherent internal structures add (integrate) coherently. Hence, mind changes can coherently integrate to produce minute but real, observable, physical input changes to the body system. *Mind permeates the body via the interlinked and superposed potentials of the body.* The living bio-organism's mind and its operations can be modeled as an organized operating wave dynamics inside a scalar potential and superposed potentials of the body of that organism. Since fields are made from the more fundamental potentials, these operations also function inside the fields of the body. The organized time-density dynamics constitute both the conscious mind and its operations and the unconscious mind and its operations. More subtle depths of the time-density dynamics also constitute the human collective unconscious mind functions and operations. Again, we are speaking physics, not mysticism.

See Figure 48. The "component projection" (coherent integration) process from time-like mind operations into 3-space in the body potentials introduces into the living body the *physical* commands correlated to the *mental intent* of that entity. This is the solution {94} to the long unresolved *philosophical problem of intent*, and addresses the unresolved physics problem of *just what constitutes the "observer."* But the subsequent physical changes accomplished by the responding body as a servomechanism, also produce small rotations into the time domain (into the mind domain) but in the virtual state. However, a series ol' coherent physical changes produces coherent virtual state changes in the mind realm, which in turn coherently integrate into perceptual input. In this fashion, the mind senses the response of the body to its order, and any errors in that response that need correction. The time delay gives also the sense of identity and personal persistence, hence creates the perception of self, the "responding body belonging to self," etc. Interwoven perceptions of coherent rotation changes from other 3-space phenomena that do not respond to mind intent, also create the perception of the "separate physical world." That these phenomena do not respond directly to mental intent creates the perception of the "separateness" of this "external" physical world, while the interweaving creates the perception of "existing simultaneously" with or in the external world.


Any change in the spatial body/brain produces a tiny coherent change in the time dimension and hence in mind.
t
dt
ΔL
FEEDBACK
Time Delay
Δt
INTENT
L
dL
CHANGES
Any change in the time-like mind produces a tiny coherent change in 3-space and hence in the brain-body.
A series of coherent intent-induced body changes integrates to an observable input.
BRAIN AS A TWO-WAY TRANSDUCER

Figure 48 Mind-body coupling mechanism at work.

All of that perception, dynamics, rotation, and processing is subject to direct engineering via psychoenergetics means.

Without further elaboration, we again stress that the conscious mind is a serial processor, whereas the unconscious is a massively parallel processor. Westerners are prone to equate self to consciousness or conscious mind operation alone. That is not the case. Consciousness is just one attribute of the self (of the total feedback loop having delay between feedforward and feedback).

The totality is the mind-body coupling mechanism (Figure 48) enabling a living biological system (Figure 46).

By using time-density waves formed of scalar photons, the mind realm also can be directly engineered by the same energetics technology. Hence, for the Russian energetics weapon scientists there followed the development of psychoenergetics as an entire class of breakthrough electromagnetic weaponry.

This resulted in the development of not only a unified physics of matter and space, but also a unified physics of mind and matter reaction. Any true unified field theory must integrate the observer and the unobserved as well as the various categories of the observed. It is now possible to *directly model and engineer both physical and mental reality and their interaction.* Russian psychoenergetics has been developed to do precisely this {95}.

Quantum Potential Weapons Are Utilized in All Three Energetics Branches

In addition to scalar interferometers, there is another category of energetics weapons used in all three branches. That category involves the use of *quantum potential weapons,* after David Bohm's quantum potential in his hidden variable interpretation of quantum mechanics {96}, published in *Physical Review* in 1952. We openly published one mechanism for creating a quantum potential {97}; there are others.

Presently these quantum potential weapons are the most powerful and most flexible weapons on earth. Nothing else can stand against them. Any nation not possessing QP weapons is already a second-rate power, regardless of how many nuclear missiles, bombers, and submarines it possesses, or how many high-energy lasers and high power microwave weapons it possesses.

The greatest problem the Soviets had was not in *making* the QP itself, but in (a) *localizing* its creation to the specific area or region desired, and (b) restricting its coupling to the type of equipment, entity, level, size, type of nuclei, etc. that was desired. We have not yet fully solved the problem of how they are able to do that, but have made a little progress upon it.

The Importance of Longitudinal EM Waves

The KGB energetics weapons use longitudinally polarized and time-polarized EM waves as their basis, rather than transversely polarized EM waves. There is a surge of renewed U.S. interest—and a revolution in electrodynamics—just underway in this country (and in the major weapons laboratories of other nations) *vis a vis* longitudinal EM wave solutions to the major equations of physics. E.g., one may check the Los Alamos National Laboratory Internet web site for summary papers by Rodrigues and Lu {98}. There are now formal EM wave solutions faster than light speed, slower than light speed, etc. {99}. There is also experimental support for superluminal tunneling of EM waves in waveguides {100}. In addition, as is well known, the speed of the ordinary scalar potential is infinite in the Coulomb (transverse) gauge {101}

Higher topological algebra is being used to embed the electrodynamics in most of the KGB energetics work. Maxwell's original theory {6} was some 20 quaternion and quaternion-like equations in 20 unknowns. Quaternion algebra has a higher topology than either vectors or tensors. Heaviside and others reduced the quaternion-like theory of Maxwell down to four equations in four unknowns—or to two coupled equations, depending upon how represented—and formed the much lower topology vector algebra in the process. This serously demoted the topology of electrodynamics and placed undue limitations upon what can be done with it. The subsequent mathematical promotion of electrodynamics to tensor algebra still did not recover much of the EM functioning possible in quaternion algebra. An even vaster, far more powerful electrodynamics emerges in *Clifford Algebra* electrodynamics, which may be **the** coming modern trend.

However, even with Clifford Algebra, there remain fundamental foundations difficulties—such as bluntly confusing *energy transport* with *energy dissipation, by* arbitrarily integrating the Poynting vector around a closed surface so as to select only the divergent portion of the Poynting energy flow. That produces the ene***rgy*** *dissipation flow* associated with the circuit, not the overall energy flow associated with it. The overall energy flow is some 10^{13} times greater in a nominal case, as (i) discovered by Heaviside in the 1880s, (ii) never even considered by Poynting, and (iii) deliberately discarded by Lorentz with a little integration trick {102} still used by classical electrodynamicists and electrical engineers. Electrical engineering departments, professors, and texts do not know and do not teach that all EM power sources—such as generators and batteries—actually pour out of their terminals a far greater energy flow than the meager shaft energy input to the generator or the chemical energy dissipated in the battery. Lorentz arbitrarily discarded the huge Heaviside nondiverged output energy flow component a century ago, with the observation that it "has no physical significance" {103,104}.

Part of the emerging electrodynamics revolution is intuitively obvious. Higher topology algebra used in one's electrodynamics model means that lots more things can be done—in circuits, equipment, and components. As an example, su**ppose** one can only draw geometrical figures on a flat, uncurved plane. Then compare the figures there to what can be drawn when a third dimension is added so that the plane can be curved, twisted, folded, stretched, compressed, etc. in 3-dimensional space. That is similar to the dramatic differences between electrodynamics in a higher topology algebra and electrodynamics in the far more limited tensor and vector algebras.

Further, if someone's circuits *are working* in a higher topology, a lower topology **analysis** will not even see their true functioning. This turns out to be true for Tesla's work, where so many pundits have used vector or tensor algebra in the belief that they therefore knew what Tesla was doing. They did not, nor did they even use the proper tools to see what he did. For the proof, see Barrett's examination of Tesla's actual patented circuits, using quaternions {105}.

Energy, Wave Energy, and Wave Speed are All Dramatically Altered

The energy of a pure longitudinal EM wave (LW) is infinite (unlimited). In practice, only an imperfect LW is produced experimentally, and therefore its energy is finite, but that energy may be extremely large, and the wave's propagation may be many times faster than the speed of light. This is much like *quantum tunneling*, which has been measured to be superluminal. Nimtz *et al.*, e.g., have transmitted Mozart's 40th symphony through a barrier in a waveguide at 4.7 times the speed of light {100}. Other researchers have transmitted information at lesser velocities but still at greater than c, the speed of light in standard vacuum.

Einstein assumed light speed in vacuum to be universally constant. That is correct for *transverse* photons and *transverse* EM waves, but not necessarily for other polarizations. Instead, it can be a function of the energy density of the vacuum (i.e., its stress energy density), which can be a matter of the gauge and the wave polarization. Further, *c* as a constant applies to transverse polarized EM waves (which are "surface" waves of the medium, so to speak) and not to longitudinal or time-polarized EM waves (which are "subsurface" or "subspace" waves). In general, the speed of the EM wave can be a function of the energy density of the vacuum (i.e., its stress time-energy density). And it is also a function of the type of EM wave being utilized.

"Empty space" is filled and writhing with the continual transiting of higher order EM waves, the presence of standing high order EM waves, and energetically organized regions where the energy is in the LW mode and in the time-density mode. Indeed, space (more correctly, spacetime) itself is nothing but a plenum of such waves and their wave-to-wave interactions.

The longitudinal and time-density effects in empty space are correlated with seasonal and periodic variations of time-charging and longitudinal EM wave emissions from planets, stars, etc. As a result, the characteristics of empty space itself periodically vary, and these can be detected as variations in the speed of light through the affected space.

The interplanetary radar measurements, e.g., do indeed show several periodic variations of the speed of light in interplanetary space, on a weekly and essentially monthly basis. In this data the proclaimed constant speed of light is upheld only by averaging the measurements over a month-long period, as shown by Wallace {106}. Actually, the scientists are dealing with variations of the periodically varying local time-density of spacetime, but have not taken that into account.

There are also specialized "galloping wave" zones, created by variations in the interferometry of the interpassing and interfering longitudinal EM waves in space. Such galloping waves from wave interferometry are already known in the literature {107} from 0.1 to 100 times the speed of light, but they do this on a "surge forward and lag backward" mode about an *average* speed of c in the laboratory here on earth. In space away from planetary masses, that value "c" varies from its textbook value also.

All that has really been shown is that interplanetary space is *not quite* uniform after all, contrary to present scientific assumptions.

One would think that this *fundamental foundations anomaly* shown by the interplanetary radar measurements would excite the entire scientific community and trigger a massive scientific investigation. Instead, scientists such as Wallace who publish critical analyses showing that the data directly prove the variation of c in "ordinary" space, are just ignored and essentially "parked on the side-lines" until they eventually fade away.

A Process for Creating Longitudinal and Time-Density EM Waves

Today we know that some plasmas very often can produce a longitudinal EM wave from a transverse EM wave, and can produce a transverse EM wave from an input longitudinal EM wave. This was not known when the Priore team was performing its experimental work. However, it provides one method for producing and detecting longitudinal EM waves.

The Priore team in France unwittingly made longitudinal EM waves by inputing transverse EM waves into Priore's rotating plasma in a giant plasma tube (Figures 12 and 49).

- At the end of the project, Priore had developed a large unit to treat humans.
- A few were treated.
- Cures replicated what had been done in lab animals.
- The massive size of the unit and long treatment time (hours) made the process bulky and very inconvenient — and expensive.
- We proposed a way to do it with a suitcase-sized unit and a treatment time of two minutes.*


Giant coil around 12-ft long plasma tube
Pulsed DC Magnetic field
Table for reclining human body

*See *Porthole Briefing,* www.cheniere.org

Figure 49 Priore's large plasma tube installation in his 3-stories-high treatment facility for humans. Results obtained in animal experiments were also duplicated in human experiments.

Quantum Potentials and Multiply Connected Spacetime

It appears that a sufficiently clean longitudinal EM wave can be utilized to create a *quantum potential*, very similar to Bohm's notion, by iterative retroreflection between two phase conjugate reflectors. When sufficient *iterative self-targeting* occurs and persists, the waves eventually "snap in" and fully converge to laser-like beams without any energy divergence {97}. At that point, one has achieved an essentially "pure" LW, which has infinite velocity. For all practical purposes, there is then little or no difference between this wave and a quantum potential.

A pure longitudinal EM wave just "appears instantly" everywhere in space that it will be. It is already an element of a quantum potential. In this sense, all that a "quantum" potential is, is an ordinary scalar potential in which the composite EM longitudinal phase conjugate wavepairs really are pure longitudinal EM waves. It would seem that this also moves the gauge to the Coulomb gauge, so far as the potential is concerned. It follows that, by establishing significant and clean longitudinal EM wave contact between any two points via iterative retroreflections, one establishes a quantum potential if sufficient harmonics are established in the contact. The implications for "phase conjugate shooting" to go one step farther are obvious.

By "scanning" an area with the appropriate LW transmitter array, with deliberately imperfect LWs so that contact reaction occurs, and then decreasing the imperfections in the scanning by iterative retroreflection, it appears that a quantum potential can be created and connected between the transmitters and a desired distant region.

Essentially, in the case of pure longitudinal EM waves and quantum potentials, we must model the situation in terms of a *multiply connected spacetime*. The divergence-free waves are now pure longitudinal waves in one sense, and pure potential beams in another sense. In any case, the Coulomb gauge applies. As is well-known, the potential moves at infinite velocity in the Coulomb gauge.

Thus a single station can be connected by such a QP to any number of distant stations—by first "knitting them together" into a common multiply connected spacetime by iterative mutual LW self-targeting beams. It matters not if one or more distant station(s) is/are then moved beyond the star Sirius; the moment an energy signal appears in the initiating station, it is already instantly in each distant coupled station anywhere in the entire universe. There is no separation distance involved. Here *one no longer needs to propagate transverse EM wave energy painfully through space at the speed of light.* Instead, one is now dealing with multiply connected spacetime. One now has the instant appearance *in each and every distant coupled target* of the energy input into the single "transmitting" or "coupling" station. So the process is a startling and giant "energy amplification method" as should be expected from something that has infinite energy in the first place!

One vulnerability and disadvantage of a QP weapon is that, if the target is aware of one's coupling and also has QP technology, he can now immediately send back any energy form or "greetings" he wishes, from any one of his coupled targets. He can even do it inadvertently, without even knowing he has been coupled by a quantum potential. In other words, the QP provides a two-way street, if the target is aware of it and has the technology himself, *and even if he is unaware of it and does not have the technology*. For that reason, actual use of the QP weapon in strategic strikes requires caution and special considerations. Usually it requires very rapid single use and then cessation of any further usage.

Need for Caution with QPs Used Against Biological Organisms

Another QP weapon disadvantage is that rather extreme care must be rigidly exercised, particularly when linking living creatures. For living things, the QP is best utilized in the absolute minimum energy mode. E.g., *an extremely weak OP already links every member of the human species*. Suppose one increased that linkage intensity carelessly. Immediately the entire human race is in grave difficulty. Every death of a person feeds into every other living person. Every birth of a baby feeds into every living human. Even the fertilization of one **human** ova instantly feeds into all other ova. The integration of all those changes would totally disrupt—and instantly destroy—all human life on Earth. Since chimpanzees have very similar genetics to that of humans, all the chimps would probably die also. Other higher primates would also suffer or die, as would many other species.

What might be useful, of course, would be to use a QP to kill every smallpox, HIV, Ebola, and other dread disease pathogen on Earth. If so, it would first have to be made extraordinarily specific, else it could threaten all or most of the life on Earth.

A very useful adjunct would be to use a QP device to nearly instantly scrub and decontaminate (disinfect) an anthrax-contaminated large city—such as New York or Washington, D.C.—by instantly killing all the anthrax spores in that locality. Or to clean all the antibiotic-resistant staph pathogens out of U.S. hospitals by just killing them all instantly and periodically. Or to rid the Earth of necrotizing fasciitis—flesh eating disease pathogens.

An extremely localized QP could be used to connect with all HIV viruses and DNA inside an AIDS patient's own DNA. One could then kill the HIV viruses not yet integrated into the patient's cellular DNA. One could also time-reverse the patient's own HIV-infected DNA back to normal, effectively "removing" the HIV DNA already dumped into the patient's own infected cells. In theory, 100% of the HIV infection could be removed from the patient's body, restoring him or her to a completely HIV-free condition.

A Hypothetical Example

Suppose one arbitrarily increased the even weaker QP that presently joins all living things on Earth, regardless of species. Instantly every living thing on Earth would die, and the Earth would be instantly converted to a sterile planet.

Even though *physically embodied* life was gone, however, all the forms of those species would remain in spacetime activity, their vacuum engines—for both minds and bodies—forever embedded in the local potentials and fields of the material Earth. In other words, the Earth's potentials and the local spacetime potential would still be *dimensioned* and *conditioned* for the life forms that once moved upon it in physical form. The dimensioning and conditioning (engines) for every life form that ever lived on the Earth *exists now* at every point in the Earth and in the local spacetime. With proper application of energetics, in theory it is possible to recover any of these life forms desired, back into living form.

When one understands that environmental aspect, one understands why the Miller-Fox-Urey biogenesis experiments {108,109,110} (Figure 50) would still produce living organisms again. A *physically* dead planet or test flask is not necessarily a "completely dead" planet or flask, when one considers the presence of spacetime engines and dimensioned potentials. One recalls that these forms and engines contain not only physical forms, but also the mind-aspects and the mind/body coupling and dynamics aspects as well.

In short, the entire biochemical notion of biogenesis from truly inert matter devoid of any form of life or pattern of life appears to be a false premise. Since potentials reach to the end of the universe, then any structured potential structures *(dimensions)* the universal vacuum potential everywhere in the universe {111}. The Miller-Fox-Urey experiments were not performed in a truly "sterile" environment after all, when the new energetics is considered {112}. One realizes that the entire universe is alive; the mere presence of a single living microbe or other form anywhere establishes an entire living noosphere. The Russian researchers—such as Kaznacheyev {113}— into EM induction of disease in targeted cells at a distance also realized that biology included a noosphere, and it could be engineered.



- Engines of and from all life forms ever on earth or in the universe exist in the ambient vacuum potential.
- The Miller-Fox-Urey experiments were not in a "sterile" environment.
- Heat (IR) and UV constitute (1) a harmonic interval with a difference frequency, and (2) amplifying by the process previously shown.
- These experiments "kindled" previously living forms from the available gases etc. by amplifying the ancient living engines from their virtual state to the observable state, so that the masses were molded into the physical states of their templates.

Typical Biogenesis Experiments
To spark coil
Electrode
Sparking
Organic molecules
Gas molecules
Condenser
Gaseous mixture of ammonia, methane, carbon dioxide, hydrogen, and water vapor
Boiling water

Figure 50 Typical Miller-Fox-Urey biogenesis experimental apparatus.

Herman Kahn, then director of the Hudson Institute (a leading think tank), once remarked that it did not concern him that there existed mechanisms that would destroy all physical life on earth. Instead, he stated, it concerned him that he know almost 200 such mechanisms. The quantum potential weaponry is yet another doomsday weapon with a thousand lethal mechanisms to add to Kahn's list, were he still with us.

The QP Weapon Is a Superb Energy Amplifier "For Free"

In a multiply connected spacetime established between multiple separated (to the observer) stations, one can instantly input one megawatt of power into *every distant stution* by inputting it into a single station. Suppose that coupling station is coupled via QP to one million distant stations (scattered anywhere in the universe). Then in each distant coupled station there now instantly appears one megawatt of power, even though we have input only a single megawatt in our "transmitter" coupled station. This is a superb *one-on-many weapon system and energy amplifier*—perhaps the ultimate weapon system.[30]

AS an analogy for understanding, one can look at it this way. Put a dot (point) on a piece of paper. Mathematics tells us that an indefinite number of other points can be "superposed" directly on that original point. Now input some "energy" into the original point. It instantly appears in each and every other superposed point. That is precisely the way a quantum potential linkage between stations works, except that in normal singly-connected 3-space the points are *observed* by a normal observer to be widely separated. Aristotelian logic—which is an "either/or" logic—does not apply. Instead, a higher topology logic applies.[31]

---

[30] However, we should not be loo surprised at such "astonishing" effects, once we appreciate that with the quantum potential and pure longitudinal waves one is playing with infinite energy anyway.

The QP weapon can be used with microwatt input to induce low-level disease states or pre-disease states *(shadow disease states)* (Figure 51) in entire populations. Tests done in this fashion will violate the "vector carrier" aspect of infectious disease transmission. Instead, the tests will cause a few widely spaced nearly simultaneously cases of the disease being tested. Several such tests (e.g., with necrotizing fasciitis) have already been conducted in the populace of the United States.


MAGNITUDE OF STRESS EFFECT
Observable state
Immune system reacts
BODY
Local cellular changes (electrical, chemical, physical)
ELECTRICAL, CHEMICAL, AND PHYSICAL STRESS
T_4
Physical Threshold
Pre-physical change state
Quantum Level
T_3
Virtual state
Inner EM System Stress
T_2
T_1
"Shadow disease state" when immune system reacts
SEPARATION FROM CONTACT POINT
Most stressed location

Figure 51 The shadow disease state is that structured virtual state level of the promoting disease engine template, at which the immune system reacts.

Or a QP weapon can be used with megawatt or gigawatt input to blast multiple distant targets simultaneously. One may destroy, e.g., every single transmitter of a given type. Or one may instantly kill all ships and weapons and paraphernalia in a large naval task force steaming toward its target. Or if one wishes to take the ships and equipment, the weapon can just kill all the humans instantly in that task force. ICBM sites, e.g., are vulnerable and obsolete since 1990 to any nation possessing QP weapons. So are underwater nuclear submarines and long-range strategic bombers. The entire strategic and tactical armada we have built up so painfully over the decades is obsoleted—also meaning *countered*—by any enemy possessing sufficiently advanced energetics weapons, and particularly quantum potential weapons.

---

[31] We developed such a logic years ago, and have recently included **it** in *Energy from the* ***Vacuum*** 2002, *ibid.*

Other Novel Uses of QP Weapons

If an enemy has such QP weapons and you do not, you are easily and directly destroyed at will, once certain other deterrents are overcome. One of these previous deterrents that had to be overcome was the stability of nuclear weapons in our nuclear arsenal. To remove this stability and render them easily destroyed, the holder of a scalar interferometry capability could induce sudden massive fissioning and fusioning of many of the targeted onsite weapons if the scalar potential interferometers were used massively. However, the resulting tremendous nuclear explosions—many "in the dirt and dirty"—would also unacceptably damage the attacker. Further, major antagonists usually clandestinely introduced hidden nuclear weapons into the cities and target areas of their opponents, which practice was known as "dead man fuzing." The notion was that, even if one side suddenly destroyed the other, that destroyed side could still detonate its secret nuclear weapons hidden in the attacker's homeland territory, destroying him as well. In essence, the killed side (the "dead man") had set off the fuzing of his pre-planted weapons, to destroy the attacker even though the "dead man" was already dead.

One strong reason that the Russians pursued the quantum potential weapon so strongly was precisely because it offered a mechanism to solve this "dead-man fuzing" problem, removing it as a viable deterrent. Obviously it would be quite advantageous to be able to dud or destroy these hostile weapons in one's very midst, even though one did not know their locations, and pull the fangs of the dead-man fuzing installed by one's opponent.

There appear to be ways of directly connecting a QP, e.g., to every atomic nucleus of a given type, in a given region (say, in a region consisting of on the surface of the Earth, in the Earth to some depth, in nearby space, on the surface of the ocean, and beneath the ocean). Connection can be made, e.g., to every U235 nucleus and to every weapons grade plutonium nucleus. Or with the technology developed, the users ought to be able to make such connection only between certain pre-selected *localized amounts* of U235 nuclei or plutonium nuclei.

Now suppose that such a QP is established between weapon-sized groups of U235 atoms. Then one hits one U235 nucleus in such a group in an activator station with a neutron bullet. Voila! One simultaneously hits every other linked U235 atom (including the activator station—one just blew it to smithereens if it contained very many U235 nuclei) in such weapon-sized groups. The raw U235 in ores in nature is still okay if the ore contained only tiny traces of U235 nuclei. But all the "neutron-struck" fissionable nuclei in nuclear weapons worldwide—regardless of owner or location—fission in the weapons immediately. That destroys all the nuclear weapons on Earth—including the clandestine nuclear weapons that various nations have spirited into other nations perceived to be their enemies, as a "checkmate" against sudden surprise attack. *One* does not need to know where a weapon is at all.

However, it gets all the weapons by exploding them, and that itself could create a giant nuclear destruction and fallout problem that would probably do in most life on earth because a great many nuclear weapons will have exploded "in the dirt and dirty." In short, it is an entirely unacceptable solution to the dead-man fuzing problem.

Of course, no *sane* enemy would wish to use the QP in such fashion, because it is quite suicidal for him and essentially destroys civilization. But suppose the sane enemy is well aware of the exact nature of the new cold type nuclear reactions (we explained these in an initial rough paper given in August 1998 at an Energy conference in Utah). The energy initiating these "time-reversed" nuclear reactions starts from "inside" the nucleons in the nucleus and moves outward (that is true of any "reversed" zone).



- Via quantum potential joining U235 and Plutonium in warheads
- Includes weapons airborne, underwater, in storage
- Transmutations of the nuclides themselves
- Part of the initial barrage launched by Aum/Yakuza/KGB
- Will occur in the first minutes (10) of the strategic strike, following psychoenergetically crew-disabling QP weapons

Note: Duds both overt and covert nuclear weapons and weapons-grade materials -- including "suitcase-delivered" covert weapons on site in Russia which otherwise provide dead man fuzing

Figure 52 Simultaneous dudding of nuclear weapons worldwide. Also duds nuclear reactors and nuclear propulsion systems.

Direct *isomeric transmutation* then becomes a preferred decay reaction to induce in the nuclear weapons one wishes to dud. By gradually inducing (slowly "kindling") one of these transmutation reactions, one can just "transmute" the U235 to—say—an isomer such as U238, with some readjustment and energy balancing in the ensuing rebalancing decay processes. In that way, one gets no nuclear explosions. One can even choose the transformation or several successive transformations so as to minimize any resulting nuclear radiation. The attacker also destroys all the nuclear reactors, including those in civilian power plants, nuclear submarines, and elsewhere. But he gets just about all the nuclear weapons if he transforms both U235 and plutonium (Figure 52). In about 10 minutes he will dud them all, without any nuclear explosions, but he would probably allow about one hour "just for good measure and nearly 100% certainty."

This offered the Soviets the ideal solution to the worrisome hostile nuclear arsenals of the world, since they also had additional nonnuclear strategic weapons of a different kind and of great power.

Apparently that very kind of QP weapon became operational, on site in Russia, circa 1989 under KGB control. For the first time, it provided the KGB with a guaranteed solution to the nuclear dead-man fuzing problem that had until then prevented its massive use of the scalar potential interferometers (such as in 1985-1986 as originally envisioned by Brezhnev).

By almost simultaneously leasing the earlier scalar interferometer weapons to **the** Yakuza and Aum Shinrikyo at the end of 1989, the KGB obtained an influx of vast new funds {114}. It thus concentrated even more intensely on the more advanced energetics weapons such as QP weapons and psychoenergetics weapons {115}.

So with a QP weapon one can attack multitudes of targets, using a single "coupler" or "transmitter," all without "propagating the EM energy through 3-s**pace."** Further, with the technology developed, only the number of outrigger stations coupled limits the energy amplification achievable. One can alter matter at any level, from the quarks in the protons and neutrons in the nucleus, to the lattice bonds, to the molecular bonds, etc. Or one can structure the emerging energy (that emerges directly out of the local spacetime itself), so that *structured local spacetime curvatures* (engines) appear in the target zone(s). These ST engines can be generated so as to perform macroscopic functions against real systems—e.g., jamming electronics, as against the U.S. air attack on Libya in April 1986 (Figure 25), or as was done by a longitudinal EM wave interferometer in the attack and kill of the U.S.S. Thresher (Figure 6) in April 1963 {116}.

The U.S. Narrowly Escaped Destruction Twice in 1997 Alone

On two occasions in 1997 the United States would have been utterly destroyed by the die-hard faction of the KGB, except for direct countering by a friendly little foreign nation. The present author and three colleagues played a very minor role by alerting that nation to the impending attacks. There was certainly no reason to contact officials of our own country; the U.S. was and is powerless to prevent such attacks, although *hopefully* that is changing! It made much better sense contact the only nation that could possibly avert our impending disaster. Of course we later also informed proper U.S. government officials of our actions.

The first strategic attack was scheduled for between early to mid-February, and involved (1) dudding all nuclear weapons, (2) striking the QP weapons in the little nation simultaneously, as well as extant scalar interferometer weapon sites in other foreign nations, and (3) then leisurely blasting cities, facilities, and installations with iterative and continued scalar interferometer strikes. This third phase would include work assigned to the Yakuza/Aum Shinrikyo teams. That is how the Yakuza (and Aum Shinrikyo) expected to revenge themselves for the Western defeat of Japan in WWII, and for the West's dropping the atomic bomb on Nagasaki and Hiroshima. To be able to "get in on the kill" is why the Aum Shinrikyo and Yakuza leased the scalar (longitudinal EM wave) interferometers from the Russians in the first place {117}.

These, along with negative energy EMP weapons, are the kind of energetics weaponry that now determines our fate, and against which the U.S. presently has still inadequate defenses. Our own scientific community does not believe such weapons even exist—apparently due to the "not-invented-here" syndrome. Most of the U.S. scientific community is thus relatively useless and outdated as far as contributing to the strategic survival of the United States is concerned.

Purpose of the Novel Attack on Captain Button

Hopefully, some scientists are aware of the strange incident that involved the mental seizure of Captain Button in his A-10 (Figure 22) and controlling him for well over an hour (Figure 23), including controlling his perceptions, intent, and actions while performing complex technical tasks. That was the test of a KGB *psychoenergetics* weapon, developing and to be deployed by the KGB. That was the "acceptance test", so to speak—deliberately conducted over the United States—for the KGB's system that would be produced in numbers sufficient to counter the QP weaponry, if the QPs of the little friendly nation were to be placed in the insane command and control mode. This was yet another Soviet counter, planned for the near future against the counter by which the little nation did force abortion of the KGB second attack (scheduled for May 1) in 1997.

The purpose of the attack on Captain Button can be understood as follows: The later second scheduled strategic attack on the U.S.—scheduled for May 1, 1997—was forcibly aborted after the friendly defending nation switched to an *insane* command and control mode. The insane C3 mode counters the MindSnapper type attack that instantly kills all on-site operators and renders the sites too "hot" for new personnel to come in from outside and control it. In short, the U.S. could have been destroyed in that scheduled May 1 attack, but with the change of the friendly QP weapons to insane C3, Russia would also have perished in the immediate quantum potential counterblow from the little nation[32] that would have been automatically delivered by the site weapons themselves. The May 1 attack had been predicated upon the fact that a preliminary MindSnapper (negative energy EMP) attack on the friendly QP

[32] There are also variations. As an example, the insane C3 can also include a separate channel requiring a countering "punch in" code every 15 minutes (as in a heightened alert status) or the control system will order the launch initiation (this accepts that all on site personnel have now been suddenly killed). So the insane control system is also flexible, and many variations and considerations are possible.

weapon sites would have instantly killed all persons on site,[33] and neutralized the site for some months because of the resulting longitudinal EM radiation. However, the shift of the C3 of the QP weapons to insane mode rendered such a pre-emptive MindSnapper attack totally ineffective because Russia would still have been destroyed.

Hence another countering means was required, and in fact that additional system was already in development. It was a very sophisticated array of psychoenergetic weapons, each with a special, highly trained team of operators capable of fully controlling one targeted individual while he was directed and controlled to go about performing desired technical tasks. We estimate that it required one psychoenergetic weapon (very complex, multiple transmitters) and an operator team of perhaps 20 to 30 skilled operators (one for each major human function to be controlled) to adequately control the mind and actions of one distant person performing quite technical tasks. Hence several hundred such "weapon sets" were required to take over all persons on the targeted QP weapons sites in the friendly nation, have the controlled crews deactivate the QP weapons including using the security code and procedures to standdown for maintenance, etc.

Once the QP weapons were totally on standdown, then the MindSnapper would have struck suddenly and killed every living thing on site, neutralizing the site for several months due to subsequent strong longitudinal EM wave emissions from the struck site. No new crews could have entered the site and lived, so the sites could not be operated after MindSnapping, even though the QP weapons were still intact but just on standby. Of course, a third phase then would have involved strikes by scalar EM interferometers to leisurely and completely destroy the systems and sites, permanently taking out the physical system as well.[34] With the first two of that three-part series of strikes completed successfully, then the KGB weapon sites would have been absolutely free to blast North America and our European allies into smoking ruins, leisurely and at will, given the first 10 minutes of dudding all nuclear warheads worldwide, to take care of that old type of "dead man fuzing".

From the open reports of the Button incident, and from the kill of Captain Svoboda a few weeks later, the nature of the next strategic attack that would be scheduled was immediately apparent. Accordingly, we warned the little nation about the shift to a new attack plan, and estimated the new schedule between mid - 1999 and the first of 2000. Of course, we also passed that information on to our government as well, but apparently, no one believed it. The proper U.S. intelligence agencies, however, certainly intercepted my faxes to the little nation's Military Attache in Washington D.C., and particularly my fax a few days before May 1, sent directly to the Prime Minister of that nation and urging the change to an insane command and control system for the QP weapons and the reason why.

---

[33] We point out that it required a longer time to develop the more powerful negative energy EMP weapons capable of just destroying the sites, personnel and all. The first effective weapons of that type could easily kill personnel brains, nervous systems, and hearts while still doing little damage to the much more robust *QP* systems and on site equipment.

[34] We strongly believe there are shielding provisions at those sites, against scalar interferometry attacks, which reduces their effectiveness and delays their destructiveness. However, so far this analyst has not deciphered those shielding methods or mechanisms.

It turned out that, some months after I alerted them to the coming psychoenergetics, MindSnapper, and scalar interferometry attack in that order, to be scheduled between mid-to-end of 1999, apparently the friendly nation suddenly struck and utterly destroyed the KGB facilities for the MindControUer negative energy EMP weapons being painfully built up in sufficient number. Probably scalar interferometry weapons were used to destroy them. The onsite psychoenergetics crews and facilities were destroyed and neutralized completely.

Anyway, as we passed mid-1999, the type of "Y2K" problem we were worrying about was whether or not the attack was on, headlined by a psychoenergetics weapon strike on the little nation first, with the three phases as previously scheduled back in 1997.

Later, in early 1999 I realized the Russian/KGB development of the causal system robots (Figure 10), mentioned in the introduction. In the latter part of the third quarter of the year, working at my computer at night, I was struck by one of these very beasts from within my computer (Figure 20), in very bizarre but unmistakable fashion (previously detailed). In 10 seconds I was nearly killed and severely disabled for a period of time (it took four days to recover completely). Because of the features deliberately utilized by the CSR on my computer screen so I would recognize it, I grasped the nature of the attack (the KGB *wanted* me to recognize it, and live to tell about it!), how it was done, how it jammed the brain and vision center and strongly fibrillated the heart, upset the equilibrium, etc. I also realized that, in 20 seconds or so additional exposure, I would have been a very dead person, expiring with a very violent heart attack and severe brain embolisms. Note that the CSR deliberately struck directly from the computer screen through my retinas and onto the nervous system, passing through the vision center and flashing it tremendously, and jamming my mind, brain, and nervous system.

When I recovered shakily about four days later, I notified the small nation, once again, as best I could, giving the exact symptoms of the attack and explaining what it was. By then I knew what was coming down, the form it would take, and the deceptive cover (Y2K uncorrected errors!).

The little nation then quickly proceeded to search out—apparently *inside* the North American signals, potentials, fields, and waves "superhighways" for the CSRs—all the CSRs and destroy them in place. It turns out to be a fairly straightforward operation, once one possesses advanced longitudinal EM wave interferometry weapons and techniques. Locating a "very dense" and very dynamic set of LWs performing organized functions is analogous to a normal radar locating a large bomber in cloud cover. One "burst" from the LW "radar," and the targeted CSR is completely disrupted and electronically destroyed.

So a very short (lasting a few days) and strange strategic battle was fought in infolded space or subspace, inside our electrical and electrical systems and inside the fields, potentials, and waves in them. A mighty attacking armada of perhaps several million main battle systems was intercepted and destroyed throughout our homeland, without the slightest notice by our own government, scientific, and intelligence communities. And without a whimper of what is usually recognized as "combat actions".

Afterwards, a very simple and innocuous little message was received which, reading between the lines, simply meant "thank you very much." In short, my hard-pressed colleagues and I got a small "Attaboy!" for our role in alerting the friendly nation.

So Y2K and the Millennium Celebration came, while we waited to see if the CSRs were gone or if they would erupt with damage all over the U.S. Fortunately, they were gone like popping balloons, and so the *fourth* scheduled strategic attack upon the U.S. in the space of three years—this time actually launched—was successfully destroyed.

Whatever I can do to help the survival of my country I will continue to do without hesitation, regardless of whether the U.S. scientific, intelligence, and military communities are aware of the new threat or not, and regardless of whether they believe it or not. Presently our fate and that of the Western world rests on the shoulders of a small but advanced and friendly nation. That is beginning to change, it seems, but still not swiftly enough to suit our needs.

We simply must change all that, by developing QP weapons and defenses ourselves. It is not an option; as an example, China has now finished—as of earlier 2002—and deployed QP weapons. Almost simultaneously, China also finished and deployed the more powerful negative energy EMP (MindSnapper-type but much more powerful) weapons and deployed them as well. So we have entered a very dangerous period when the strategic changes that are likely to occur will be both massive and traumatic.

AS this is being written in early October 2002, it is obvious that our nation is also preparing to strike Iraq if need be, either with a coalition effort or alone. If so, then Saddam Hussein will certainly unleash whatever terrorist forces he has in North America. He will attempt to unleash upon us all the weapons of mass destruction at his command. This could even happen within the next 30 days, with the MidEast exploding, giant polarization of the Arab world, general chaos in the MidEast and upset of world oil supplies, and skyrocketing fuel and energy costs with severe impact upon the already seriously ailing U.S. stock market.

If Saddam Hussein succeeds in doing sufficient damage to our cities and energy infrastructure with more weapons of mass destruction than we have credited him with, then the potential economic collapse of the United States and much of the developed world is an uncomfortable possibility. If that happens, turf wars will erupt all over the world, the world economy may collapse, the KGB and rogue Japanese (Yakuza and Aum Shinrikyo) will move and unleash further destruction, Pakistan and India are likely to erupt into a nuclear war, and several other regions may also erupt into nuclear war and use weapons of mass destruction. What China might do in such event is anybody's guess.

In short, the Armageddon we have so long feared, with the resulting collapse or destruction of much of civilization, could well be approaching. Let us hope that dark picture is terribly, terribly wrong, and that we successfully avoid Armageddon one more time!

Meanwhile, we would be in much better shape to weather the coming storm had our scientific community not grossly betrayed us. But if and when millions of Americans are dying in the streets with no effective means of treatment, and no effective defenses to prevent onslaught after onslaught against our nation, all those deaths and all that suffering will be directly the fault of our own organized scientific community.

Rogue Japanese (Yakuza and Aum Shinrikyo) Have a Role

In the information briefing furnished the previously named agencies, we briefly detailed the elements of the attack, how our own nuclear weaponry can be dudded anywhere, etc.

We also detailed the strange role of the Japanese Yakuza and the Aum Shinrikyo, who leased the operational use of the early generations of KGB longitudinal wave interferometry weapons in 1990 directly from the KGB. The first down payment on the lease was $900 million. I previously furnished pertinent information on this to an investigative U.S. Government agency. Since then, the Yakuza have set up their own scalar interferometry weapons development facilities in Japan, including portable energetics weapons,[35] and have assumed a very secret and nearly unsuspected role somewhat similar to Bin Laden's role in the attacks of September 11, 2001—but much more deadly when the coming Armageddon erupts.

Inducing the Gulf War Disease

In 1986, the Russians had already solved the dead man fuzing problem theoretically, but had not yet completed the development and deployment of the necessary QP weaponry. The KGB's first "combat demonstration" test of the **ability** to localize a QP in a selected region of space was against the U.S. air attack on Libya in 1986. That test apparently used a laboratory apparatus to prove the process. In short, it was a major milestone whose success moved the system into full production engineering and production. The system was then developed at very high speed after the successful demonstration in 1986. The first strategic KGB QP weapon(s) became operational on site in latter 1989.

---

[35] We strongly suspect some of these portable weapons have already been infiltrated into the United States—e.g., to be used against nuclear power plants and other lucrative targets such as refineries, oil fields, etc.

It was this QP weapon that was used to generate the so-called *Gulf War Disease* in our soldiers in the MidEast. In the action package, I explained precisely how that was done. I have also finally placed the simplified gist of that explanation openly on the Internet for all to see (website www.cheniere.org). Those suffering U.S. veterans were *casualties of war,* not victims of just nerve gas whiffs or chemicals or their own stress, etc. The initial U.S. Government and U.S. scientific community's assertion that "it was all in their heads" and due to stress, insults every veteran who has ever served his nation. One justifiably has contempt for such treatment of our veterans. Sadly, the latest "studies" are **beginning** to conclude the same thing once again.

Apparently our intelligence and military command agencies have not yet learned **the** lesson of the decades long Soviet microwave radiation of the U.S. Embassy in Moscow, which was responsible for health changes of many kinds in U.S. personnel and was also responsible for the deaths of three U.S. Ambassadors to the Soviet Union. Apparently we are still using radar engineers and electrical engineers for electrodynamics analysis, and these analysts apparently still believe that in the absence of the EM fields there can be no induced EM effects. One sadly comments that, just as the electrical engineering departments of our universities have been unable to walk across the campus to the particle physics department and find out what the discovery of broken symmetry in 1957 portends for their discipline and model, then the intelligence community apparently has not yet learned that no EM analysis of such things as the microwave radiation of the U.S. Embassy in Moscow or the shootdown of the TWA-800 is worth a tinker's dam unless it is a higher group symmetry EM analysis. As Barrett showed, our fellows still have not grasped what Nikola Tesla already accomplished in actual patented circuits circa 1900 and shortly thereafter. Tensor analysis and vector analysis simply will not show what is really there.

Our veterans were hit with a "cocktail mix" of specialized disease "spacetime curvature engines" just below the observable threshold, in the "shadow" (virtual, but nearly observable) state[36] (Figure 53). The immune systems and the cellular regenerative systems do react to that shadow state level.

---

[36] One should think deeply about this, in terms of the solution to the source charge problem (which our engineers have not thought of very much, much less solved). Every charge already "engineers" the virtual stale at will, converting virtual energy into deterministic observable EM energy. That means we can directly engineer the virtual state vacuum itself if we put our minds to it. **Actually** Nobelist Lee has already pointed out that we have *not even tried to do this!* See T. D.


RESOURCES FOR DISEASE #1
RESOURCES FOR DISEASE #2
RESOURCES FOR DISEASE #3
RESOURCES FOR DISEASE #20
Immune system reacts to all 20 pre-disease conditions
Observable state
quantum level
Immune system reaction level
Virtual state
Interferometer or quantum potential weapons put in the disease templates for 20 diseases, deliberately kept in the "shadow state" magnitude

Figure 53 Spreading (thinning) the immune system's ability available to meet a new pathogen.

Such a "simultaneous mix" shadow induction "spreads" the reacting *finite* immune system and regenerative system (Figure 53) and their resources all across that entire mix of shadow diseases, so that only a much smaller portion of the immune system and of the regenerative system is directed against *any one* of the shadow diseases. This in turn greatly heightens (by a factor of 5 or more) the susceptibility of the body to all additional disease pathogens, and it greatly lowers the ability of the body to recover from any disease or biological warfare strike. In addition, the exposed veteran's body fluids and masses have accumulated a persistent "time-density charging" that very slowly decays (by emission of weak *longitudinal* EM waves) over months or even a few years.[37] The sperm from these veterans did indeed have the innate "engines" and therefore the capability to gradually infect their wives. So did the saliva in their mouths. The weak "dimensioned" LW radiation from their bodies could also slowly alter the cellular regeneration and immune systems of their family members in close proximity, over a period of time, thus inducing the disease in them {118,119,120}.

Lee, *Particle Physics and Introduction to Field Theory,* Harwood, New York, 1981, in his "Chapter 25: Outlook: Possibility of Vacuum Engineering," p. 824-828. On p. 383 Lee points out that the microstructure of the scalar vacuum field (i.e., of vacuum charge) *is not utilized.* We add that the West does not utilize it. It has been utilized for some decades in the former Soviet Union and now in the continuing KGB energetics and bioenergetics weapons programs.

[37] See T. D. Lee, "Can Time Be a Discrete Dynamical Variable?." *Phys. Lett.,* 122B(3,4), Mar. 10, 1983, p.217-220.

The induction of GWS in our troops was in fact a test for the *present* clandestine use—already ongoing—of that technique to spread the immune and regenerative systems of the targeted U.S. population. This in turn gradually makes us more susceptible to terrorist BW attacks and disease pathogens of all types *from anyone else.* This tactic is already in place and accomplished, and it will substantially increase the American civilian casualties in our cities when they are subjected to terrorist BW attacks in the near future. *Those attacks now will have some five times the effectiveness that our present planners estimate.* In short, it is going to insure the deaths of millions more Americans. The approaching war in the MidEast, with Saddam Hussein's unleashing of his terrorist assets in the U.S. to the maximum extent possible, thus will probably see a five-fold increase in the effectiveness of some of his mass destruction weapons that Hussein's assets are able to unleash on America.

The entire affair of the Gulf War Disease was both a preliminary test and also a magnificent intelligence probe by the KGB, to clearly demonstrate once again that the U.S. Government and the U.S. scientific community are still nearly totally unknowledgeable of QP weaponry, immune and regenerative system "spreading," disease induction by bioenergetics means, etc. It follows a methodology used with great success for four decades by the KGB,[38] and one that our own government, scientific community, and military community has yet to decipher. *So long as the threat only slowly increases, Americans remain complacent in their ignorance, ignoring the boa constrictor slowly strangling them, while awaiting the cobra seen in the distance?*[9] We have unwittingly cooperated with the KGB boa constrictor for four decades, even as it slowly prepared to crush us. In the Gulf War, that crushing moved to the next threshold, to actually inflict casualties and deaths on U.S. troops and totally get away with it because of the bioenergetics (in the Russian sense) ineptness of the U.S. scientific community.

---

[38] The decades-long microwave radiation of the U.S. Embassy and induction of health changes and diseases, was a case in point. A high level target—the U.S. Ambassador—was involved, guaranteeing U.S. Government attention at the highest level. Puzzled, the U.S. government would then call in their most trusted EM scientific analysis groups. By the responsive actions then taken by the U. S. at the Embassy, the KGB could ascertain with absolute certainty whether or not our scientists knew of the use of infolded engines in bioenergetics. For more than four decades our actions assured them with 100% certainty that we knew nothing of what their "information content of the field and potential" actually was, or how it had been weaponized and was being used right in front of our faces and before the entire world.

[39] It is bizarre that our scientific community—even after those decades of EM induction of diseases and health changes in American personnel in the U.S. Embassy in Moscow—*still do not and cannot believe that conditioned EM radiation can induce cellular disease.* Such total blindness is inexplicable.

40-Years of Russian Induction of Diseases In U.S. Embassy Personnel

Sadly, our own fellows have never even figured out how the diseases and health changes were previously induced by the KGB for decades in personnel in the former American Embassy in Moscow. Three U.S. Ambassadors to the Soviet Union died as a result of their exposure to that radiation. Many other Americans on site were made ill or suffered health changes.

When Johns Hopkins scientists studied the problem, they found a most anomalous thing: no health changes occurred in areas *where the EM forcefields existed* in the microwave radiation. Instead, the health changes only occurred in areas where the potentials were gradient free so that the force fields were zero—and thus the potentials (and their specific internal "engines") were *persistent.* Using only a classical EM force field analysis—which does not show any of the internal longitudinal EM wave substructuring of the fields, potentials, and waves—the Johns Hopkins scientists erroneously concluded that it could not have been the weak microwave radiation causing the health difficulties, *because no such health difficulties occurred where the forcefields were present.* That is, they very naively assumed that "no force fields" meant no EM effects were possible. Their entire findings thus were based on a total non sequitur, the assumption that there can be no electromagnetically induced physical changes in matter in the absence of fields! The Aharonov-Bohm effect alone falsifies that entire premise. So does general relativity and higher group symmetry electrodynamics.

Actually, the Johns Hopkins scientists had just clearly proven the exact opposite: *that it indeed was the radiation that induced the health changes.* That is simply shown statistically, and it is a deep and continuing mystery how good scientists and their governmental overwatch did not notice the violation of inference methodology.

Simply put, there was 100 percent correlation to the presence of *gradient free EM potentials— the persistent kind.* There was zero correlation (or 100% anticorrelation) to the presence of the normal electric and magnetic fields—i.e., where the potentials changed over a very small region of space. Hence it could only have been the constant potentials, else we must throw out statistical inference theory altogether.

If the changes had *not* been caused by the EM radiation at all, one would have had some health changes in regions where fields were present and some health changes where the fields were absent. Considering the lengthy time the radiation persisted and the number of personnel affected, the statistics are decisive. Without question, the cause was indeed the persistent potentials where the **force** fields were zero. Whittaker's two papers—one in 1903 and the other in 1904-would then show how it was done. The 1904 paper and superpotential theory alone would *not* have explained it, since that alone does not include the "information content of the field"—i.e., spacetime curvature engines infolded inside the normal EM potentials, fields, and waves.

So, the U.S. government and U.S. scientific community "botched it badly," unfortunately, by elemental statistical inference standards. And unfortunately, they have continued to "botch it" to this day. Both the scientific community and the intelligence community missed it. Elementary statistics theory alone, coupled with the Johns Hopkins results, clearly indicates that the microwave radiation was causing the health changes, to a very high degree of confidence.

This demonstrates how "totally inexplicable" some of the effects generated by longitudinal EM wave interferometry and by "structured" or dimensioned potentials, fields, and waves can seem to our conventional scientists. If we examine the serious foundations flaws in classical electrodynamics and electrical engineering taught in our universities, and the near-total lack of higher group symmetry electrodynamics training, we can understand why our scientists and intelligence analysts did not and do not have the background required to properly assess the incidents and effects.

Western Electrodynamics Is in Sad Shape

Actually, numerous scientists have long pointed this out. For example, quoting Mario Bunge {121}: *"...it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state."*

In quantum electrodynamics, it is the *potentials* that are the primary causes of all electromagnetic phenomena, not the force fields as used by Johns Hopkins and the Government in its analysis. We know that classical EM is wrong in its focus upon force fields as primary EM causes; the Aharonov-Bohm effect, Berry phase, and geometric phase work in some 20,000 papers in the physics literature already show that. Indeed, we also know that the classical force fields do not even exist apart from mass; in space, only the potential for such a force field exists, in case some charged matter is brought in to interact with the EM entity as it exists in mass-free space (as curvatures of spacetime).

The Aharonov-Bohm effect and its implications have been published in *Physical Review*—our most prestigious physics journal—since 1959. Later publications have included the Berry phase extension of the AB effect, and Aharonov and Anandan's further extension of the Berry phase to what is today called the geometric *phase.* The potentials are indeed the primary EM causes, and *the force fields do not even exist as such in mass-free space, but only in mass.* Yet our classical EM taught in our universities has not been changed in its fundamental acceptance of the material ether since 1865.

Every university in America is still teaching and defending a rather mangled electrodynamics where

(1) The material ether is still assumed, even though destroyed more than a

century ago by the Michelson-Morley experiments;

(2) The force fields are erroneously assumed to exist in massfree space, but in force-free form(!!!) when what actually exists there as an EM disturbance is a general relativistic perturbation of spacetime (i.e., an oscillation of the local curvature of spacetime). Actually, force identically is the time rate of change of momentum, where momentum is mass times velocity. Thus mass is a *component* of force and force field. There is no force or force field without mass. As Feynman put it, there is no force field in massless space; instead, there is only the potential for such a force field to be formed at the various points, should a charged mass be placed at (added to) each of them;

(3) The source charges are erroneously assumed to *create* their fields and potentials and all that energy in them, reaching across the entire universe from each and every charge, right out of nothing at all. This perpetual motion and creation of energy error continues even though particle physics has known (and proven, both theoretically and experimentally) that any charge (as a set of composite dipoles, when the charge is taken with its clustering virtual charges of opposite sign) is a broken symmetry in its fierce energy exchange with the vacuum. Hence the charge extracts that energy in its fields and potentials *from the active vacuum,* and outputs the extracted energy across space {122}.

Our own electrodynamicists and electrical engineering professors and departments would have us believe - and they continue to imply such in every university in America—that every charge is a perpetual motion machine clearly in violation of the master energy conservation dictum that *energy can neither be created nor destroyed.* The complete lack of scientific understanding that every charge extracts energy from the vacuum and freely and continuously pours it out as real observable EM energy, is reflected in rather silly "witch-hunts" {123} against electrical systems which exhibit more energy output than the operator himself inputs—i.e., systems which exhibit a coefficient of performance (COP) of COP>1.0, which are open EM systems far from equilibrium in their active environmental exchange.

Let us reason together! If the second law of thermodynamics really did prohibit COP>1.0 *electrical* systems, then it also would prohibit the demonstrated COP = oo of a solar cell array. It would also prohibit the demonstrated COP>1.0 *mechanical* systems such as a windmill, waterwheel, or sailboat—all of which have COP = oo! In other words, the second law cannot even be a law if it discriminates only one type of energy prohibited from being used for COP> 1.0,

For some inexplicable reason, EM COP>1.0 systems have come to be dogmatically labeled "perpetual motion machines" by the professional skeptics since EM systems must take their excess energy from the known active vacuum environment! In short, the dogmatic scientific community is saying that "windmill-type EM systems" with COP = oo are permissible for exchanges with *physically active and observable* environments (such as the sunlight used in solar cells, the heat in the air used in heat pumps, the water currents used hydroelectric power plants, the winds used in windmill power generation, etc.), but they are not permissible for exchanges with the proven modern active vacuum *virtual particle flux energy* environment, even though the discovery of **broken** symmetry in 1957 already proves that all EM energy is indeed freely taken from the seething vacuum environment by the asymmetry of the modern dipolarity of the source charge! We refer the interested reader to the proven broken symmetry of opposite charges {124}. We also refer the reader to Nobelist T. D. Lee's statement applicable to the skeptics' naive notion of symmetry. Finally, in modern physics all the major forces of nature are generated by the exchange of virtual particles. It is these forces that then translate against a resisting mass or entity to provide useful work. So all useful work in the universe already comes from the interactions of the seething virtual flux of the vacuum. On what distant planet have the skeptics been hiding while all this modern physics has been developed?

One must keep one's sense of humor! It is ironic but true that every major university in the U.S. continues to teach, uphold, and advocate—by implication—EM charges as ubiquitous perpetual motion machines, freely creating energy from nothing. And that is those professional skeptics and witch-hunters never mention that their own naive understanding of electrodynamics already implicitly assumes and teaches perpetual motion machines freely creating energy from nothing at all—and on a scale unparalleled in scientific history!

We have one chart with some 32 major foundations errors and flaws in the electrodynamics taught in all our schools; there are many others in addition. **This** erroneous teaching has so indoctrinated our graduate students that most **electrical** engineers no longer know the real difference between power (the rate of change of form of energy and thus the rate of production of work) and rate of energy flow (whether it is being dissipated or not).

Every textbook speaks of "sources furnishing power," when it is the rate of dissipation of energy in the individual loads and losses to provide the rate of doing work that *constitutes* power. Sources do not furnish power! They furnish energy flow (specifically, their source dipole furnishes energy flow, extracted and transduced directly from the active vacuum, and only a tiny bit of that enormous energy flow is diverged into the circuit and used). The various components of the receiving circuit interact with that energy flow to catch and dissipate a little of it, thus producing power and work locally in the intercepting and dissipating component.

A massive nondivergent (nonintercepted) energy flow has zero power (time-rate of doing work), but if intercepted and diverged, the divergence may develop enormous power (time rate of doing work) in and upon the interceptor, diverger, or collector. Even many physicists today are confused on the difference between rate of work and rate of energy flow per se. E.g., for about 30 years now, there has been a polite debate involving that very subject in the *American Journal of Physics.* It is still not completely resolved, because the argument has not actually addressed where all EM energy in fields, potentials, and waves comes from in the first place: directly from the seething vacuum via the asymmetry of the source charge. It also has not addressed the long unaccounted giant Heaviside nondiverged energy flow component.

Toward a Deeper Electrodynamics

The first thing the Soviet Academicians did after WW II was to completely overhaul electrodynamics, but in highly classified areas controlled totally by the KGB. Stalin's boot firmly planted on their backside saw to it, creating the terrible fear that if they failed to produce, they would surely die. Not having experienced such a "Stalin boot," our own scientific community continues leisurely onward, while it teaches 110 years old electrodynamic material filled with non-sequiturs.

The Russian use of the "information content of the field" euphemism is a case in point. Our fellows (in both the intelligence community and the scientific community) assume the Russians are speaking of simple transverse EM wave spectral analysis. Nothing could be farther from the truth. Let me explain.

In 1903, E.T. Whittaker—a leading theoretical physicist at the time—showed that any scalar potential is comprised of a harmonic set of bidirectional *longitudinal EM wavepairs.* Each pair consists of a longitudinal EM wave and its true phase conjugate replica (i.e., its "antiwave", or time-reversed twin, coupled together).

Unknown to Whittaker, that LW wavepair actually includes a *time-density wave* in the time domain, coupled to a longitudinal EM wave in 3-space. Per quantum field theory {66}, such a coupled pair would be observable as the scalar potential. Knowledge of this specialized coupling is necessary in order to properly decipher the Priore mechanism. That mechanism was demonstrated to *time-reverse* (dedifferentiate) a diseased or damaged cell and all its parts back to it previous normal state, *genetics and all.* The time-reversal was accomplished by "pumping" the cell and all its parts in the time-dimension so that time-reversal propagation of the mass-energy is achieved. The time-domain pumping is done by the associated time-density wave, which always accompanies any longitudinal EM wave a priori. So sometimes we sloppily say that the "longitudinal EM wave pumping" causes the time reversal of the mass, but it is really the associated time-density wave pumping that causes it. The time-density wave component also can cause *time charging* or *time-excitation charging* of a mass. During its alternate existence as masstime, the time portion is altered, and that is a time-excitation or time-energy excitation.

It turns out the human cellular regenerative system (Figure 29) also uses the same time-excitation charging methodology to produce time-pumping of the cell and all its parts. This produces a slow time-reversal (dedifferentiation) of damaged cells back to a previous state. This is in fact the basic mechanism for healing, as used by the living body.

Reversing aluminum, for example, just converts it back to ordinary aluminum. Not too interesting.

Reversing an HIV infected cell, however, would produce a healthy, normal cell with normal genetics. When a damaged cell turns into a cancerous cell, it is due to a process called *promotion* (change of the cell to a cancerous cell). *Reversing a* cancerous cell would change it back to a healthy, normal cell again—in short, it would constitute *demotion* of cancer and then healing of the damage in the now normal but damaged cell. In the AIDS patient, simply pumping the entire body with the time-density wave accompanying the longitudinal EM waves produced in a plasma—as Priore did for terminal tumors—would time-reverse all cells, completely ridding them of any residue of HIV infection. This would remove all the "HIV factories", thus completely solving the problem of AIDS. We have also uncovered a more advanced process where *matter can essentially be directly engineered in any conceivable manner,* including nuclear transmutation etc. We have filed a Provisional Patent Application and will file formal patent applications on those processes in the future, as soon as funds are available (patent attorneys are expensive!)

Time Is Highly Compacted Energy

Since time is energy compacted by some $9x10^{16}$, even small time-density changes can produce enormous spatial energy, should any of that compacted energy be *transduced* from time-density waves into transverse EM waves and thus into spatial EM energy. Such transduction can indeed occur in nonlinear materials and processes, such as in electrolysis.

The New Transduction Model Explains the Cold Fusion Results and Mechanisms

In August 1998, we presented a conference paper pointing out that cold fusion uses this very *transduction of EM wave types,* one into the other. We presented such new concepts as (i) TW to LW to TDW transduction and in the other direction also, (ii) time density charging of a particle to an excited time-density state (analogous to energy charging to an excited energy state), and (iii) the observation that excess phase conjugation in a local region can generate a time reversal zone where like charges attract and unlike charges repel.

With these concepts we were able to explain the excess heat appearing in the cold fusion experiments of hundreds of researchers. We also came up with (iv) a totally new class of nuclear reactions without the usual high-energy considerations. That is, we showed the exact nature of the electronuclear reaction that is forming the anomalous nuclides in cold fusion experiments. Production of the new nuclides was revealed to be simply what one would expect from this mechanism, as indeed was particle clustering of like-charged particles.

We also explained (v) all the instrumental anomalies occurring in a series of well-documented cold fusion electrolysis experiments at China Lake. In fact, (vi) we added a completely new term to the conservation of energy law, thereby extending it.

An updated explanation is included in my new book, *Energy from the Vacuum,* 2002, *ibid.* With the new transduction interactions, one must state that the total energy in (a) spatial energy form, (b) mass-energy form, and (c) time-energy form is what is conserved.

So when transduction occurs in cold fusion experiments (electrolysis), some of the time-density charge energy is gradually transduced into ordinary transverse EM wave energy, which as it scatters produces excess heat not accounted for in present particle physics interaction models.

Scientists with only the "old" 2-term Einstein conservation law in mind, will be firmly convinced that this excess heat represents a violation of conservation of energy, hence is impossible. So they will question the calorimetry ability of the cold fusion scientists, etc. Unfortunately, the more ardent defenders of the orthodox faith will unjustifiably impugn the intentions and morals of the experimenters themselves with vicious ad hominem attacks. Such has indeed been precisely the case. Many of the harsh scientific critics have acted like cur dogs in a pack attack, and not as scientists at all.

Once one analyzes cold fusion in the new 3-term conservation manner and with the new transduction concepts, one immediately sees that the *overall* conservation of energy is upheld, while the *special case* represented by the former energy conservation law (conservation of the sum of the spatial energy and the mass-energy) is *permissibly* violated. The former case was a special case in that it arbitrarily assumed that no transduction of time-energy into spatial energy or mass energy—or vice versa—occurred.

In essence, successful cold fusion experiments show that, via transduction, a bit of time itself can be "utilized for fuel" and transduced into ordinary EM energy. Energy-wise the system has become a nonlinear open dissipative system[40] far from thermodynamic equilibrium {125}. As such, it is permitted to (1) self-organize, (2) self-oscillate, (3) output more energy than it itself has, by merely receiving, converting, and using excess energy from its environment (in this rase, from the transduction of a tiny bit of the time-charging that has occurred), (4) power itself while simultaneously powering a load or performing useful work, and (5) exhibit negentropy. With the exception of transduction of time-charge into excess energy, all of that is already in the thermodynamics texts, though it has not been clearly spelled out in electromagnetics texts. The source charge, e.g., exhibits all five of those capabilities. *The inclusion of the time-domain as part of the external active environment, however, is an extension of* ***previous*** *open dissipative system work by leading researchers such as* *P****rigogine.*** *It dramatically extends the meaning of "active environment".*

---

[40] But we point out one idiosyncrasy of thermodynamics, which defines a "closed system" as one in which mass does not cross the system boundary, but energy is free to exchange across that boundary {125}. Hence, eerily a "closed thermodynamic system" is actually an open system with respect to energy exchange between system and environment. As such, energy-wise the system can be a system far from energetic equilibrium with its external active environment, and still be considered a closed thermodynamic system! Energetically, a *closed thermodynamic system* that exchanges energy but not mass is permitted to exhibit COP>I .0 and even COP = oo!

Why There Is a Time Delay in the Onset of Cold Fusion Phenomena

With an energy-to-time compaction ration of $9x10^{16}$, energy processes have to transduce spatial energy into time for quite a while in order to build up very much *time-excitation charge*. This leads to an initial delay in the onset of the "new law" transduction phenomena, as directly shown by the vast majority of careful cold fusion experiments. This build-up occurs during the "palladium-lattice loading" time, e.g.

By the same token, there is a time delay after cutoff of the input power to such experiments, during which time the slowly decaying time-density charge by its transduction into spatial energy continues to maintain the anomalous new processes (such as excess heat production) as they slowly subside. So the hours-long or even days-long delay phenomena after input power shutdown are also explained by the new approach.

In summary, there exist some very anomalous but very good experiments by excellent scientists—more than 600 of them—that are at least totally consistent with the above new wave polarization transduction model. Consistency with experiments is the first element of proof (it is necessary but by itself it is not sufficient). The new model also contains and obeys the conventional conservation of energy law until the new transduction phenomena become observable, at which time the extended energy conservation law applies. So in its lower limit, the new model corresponds to the present model—again, another requirement of any model purporting to extend a scientific area past that area's conventional model description.

The KGB weapons scientists—not the regular Russian academic establishment—have about a 40-year lead on us in all these areas. While our own scientists have dallied and pursued the standard model, the Russian weapon scientists have produced the equivalent of 10 Manhattan Projects, back-to-back, in the "new" energetics area.

The Early Soviet Longitudinal Wave Interferometers

Using longitudinal EM waves, the early KGB energetics interferometers could pass their beams right through the earth and ocean. LWs readily penetrate matter, reacting with it only weakly.

Some LW interferometry was also done using ordinary EM waves as carriers for the LW wave functions. Each such transverse wave carrier is in fact two scalar potential functions (Whittaker 1904, the initiation of superpotential theory). In each scalar potential for which functions are extracted and used to make the normal transverse carrier wave, there exist LW biwave pairs comprising said potential. So by assembling the desired LW biwave subsets, the two scalar potentials and their resulting interference-produced carrier wave are internally structured as desired. This is the use of the so-called *internal information content of the field*. We speak of such a deliberately structured potential, field, or wave as having been *conditioned*, *dimensioned*, or *activated*. If these terms are deemed inappropriate, just use the more generic term "internally structured." Then one has to explain what the "internal" is, and how this "internal" can be "structured."

In the distant interferometry zone, those *dimensioned* potentials, fields, or carrier waves would interfere and produce the desired alterations in the local spacetime (including specific spacetime curvature engines). Remember, the potentials are just bundles of special waves. We are discussing a special form of nonlinear multiwave interferometry, where the individual waves and waveforms comprising the total wave package assembly constituting a carrier have been carefully chosen in advance.

In the local spacetime in the distant interference zone, such multiwave longitudinal EM wavepair interferometry creates ordinary EM waves and energy that arise directly from each and every point in that individual interference zone. We stress that ordinary transverse wave EM energy propagation through the intervening space between the interferometer transmitters and the distant target *does not occur.*

In January 1960, in a speech to the Presidium, those are the weapons then in final engineering development for production that Khrushchev spoke of as "fantastic new weapons".

Khrushchev Killed the Thresher to Prevent His Own Dismissal

The first deployed large force-structure interferometer weapons became operational circa 1 April 1963. Khrushchev was still smarting from his Cuban missile crisis fiasco and his humiliation by Kennedy. Having overplayed his hand and gotten caught,[41] Khrushchev was desperate to stay in power and not be thrown out by the Communist Party leaders for such a massive loss of face.

On April 10 of 1963 Khrushchev used his new interferometers to reach through the earth and ocean and "kindle" EM jamming in the electrical controls of the **U.S.S.** Thresher nuclear submarine underwater off the East Coast of the U.S. **The** reader should recall that, wherever the interference zone is established—including in the earth or underneath the ocean, in the atmosphere, or in space—the energy arises directly out of the local spacetime. *There is no Faraday shielding of such effects, which do not depend upon ordinary transverse wave EM field energy propagation through space*. The energy appears everywhere within the targeted object, simultaneously.

It is extremely important that the reader recognize the dramatic difference in the way energy propagates in the new mode as compared to the old "propagation through space" mode. In the old mode, energy transport arises in one spatial location and is considered to proceed serially through the intervening spatial points to the intercepting and interacting particle's location. The Poynting model presently uses only this mode. In other words, the energy propagates from wi*thout* the object *to* the object, and thence *inward inside* the object, if possible as the object interacts.

On the other hand, when the energy arises at each and every point in spacetime, it then propagates outward from each arising point. Thus in the nucleus of an atom, the "energy flow" starts at all interior spatial points and flows or diffuses outward in all directions. So the energy "meets" and interacts with the quarks in the nucleons, *before* it meets the "nucleon as a whole" and translates it. For this reason, with energetics it is easier to alter and "flip" quarks in nucleons than it is to translate nucleons, since one is using the new energy propagation mode. *This simple reversal of the outside-to-inside energy propagation to an "inside-to-outside" mode, is a revolution in particle physics and effects on materials.*

In fact, the energy dramatically enters the "interior" areas of nuclei, nucleons, etc. in a manner heretofore impossible or extremely difficult to achieve by high-energy physics, which can only do it by smashing into the object with sheer brute kinetic energy. Therefore the new "inside to outside" energy propagation mode can produce—at feeble spatial energy—extraordinary nuclear interactions not possible by brute force "outside-to-inside" energy propagation means. By controlling the structuring of the arising of the energy at each point in spacetime, the energy structure interacting with the quarks and other interior components can be tailored to order. This is the primary secret of transmuting an element at a distance by a specialized energetics weapon. The structuring of the emerging internal energy can be deliberately tailored to change quarks in—say—some of the nucleons of U235 and plutonium nuclei. In this fashion nuclear warheads, nuclear powerplants, and nuclear propulsion systems of atomic submarines can be altered at a distance, beneath the earth's surface, beneath the ocean's surface, in space above the earth, etc.

---

[41] Oddly, had he simply waited a few more months or a year before injecting the missiles and nuclear warheads into Cuba, Khrushchev's strategic scalar interferometers would have become operational. With those in operation, a "Cuban missile crisis" might well have had a different outcome.

The EM "hash" emerging from the Russian interferometry simply jammed the electrical controls and systems of the Thresher *from inside its very electrical circuits.* Out of control and helpless, the Thresher sank to crush depth and imploded (Figure 6). The EM "splatter" from that interferometry, arising from the local spacetime throughout a surrounding region, engulfed the Skylark, the surface companion of the Thresher. The resulting spurious EM jamming severely interfered with multiple electronic systems on the Skylark. Several electronic systems just ceased working altogether. Their electrical forces were time-energy excited and time-reversed so that electron currents in them became impossible (blocked).

It required over an hour for the Skylark to transmit an emergency message back to the Navy that the sub was in difficulty, through all that interferometry jamming effects. The Russians undoubtedly "tracked" the sub till it imploded, then cut off the interferometry. As the "time-density charging" in the area slowly diminished, all failed electronic systems in the Skylark returned to full functioning. This was because the excess time-energy excitation just decayed away, so that electrical currents could again flow.

Khrushchev Demonstrated the Powerful Blast Capability of Strategic Interferometry

The next day, 100 miles north of Puerto Rico, the same KGB interferometer weapon was powerfully pulsed to produce a giant EM burst deep under the ocean's surface (Figure 42). A cone of water rose up from the surface to about a half-mile in height, observed by the startled crew of a passing U.S. jetliner and reported to the FBI and Coast Guard when the aircraft landed in Florida. As it rose, the cone of water spread into a cauliflower shape typical of a deep underwater nuclear burst that does not vent the gas bubble. Then that giant cauliflower of water fell back out of the sky and into the ocean. The second successful demonstration of Khrushchev's scalar interferometer weapon had been made for the benefit of the Presidium and the leaders of the Communist Party.

With those two dramatic tests, Khrushchev had killed the latest and greatest U.S atomic submarine and demonstrated the awesome power of energetics weapons. He had shown the leaders of the Communist Party that the U.S. had no inkling of his new superweapons. He had struck the U.S. a formidable blow in a direct act of war—but a new kind of *clandestine* energetics war—and gotten clean away with it. Now it was Kennedy, rather than Khrushchev, who had been duped. So had the entire U.S. Intelligence Community and the U.S. Scientific Community. Sadly, mostly they apparently remain duped or partially duped to this day.

Khrushchev managed to stay in power nearly two years longer by these two demonstrations. So the KGB/Soviets embarked on a decades-long program of buildup and development of the new weaponry, clandestinely, in order to take the U.S. by surprise attack and destroy it utterly.

In 1972 Brezhnev named 1985 as the target year when Russia would be able to do as it pleased, and would essentially control the land, the oceans, and space {126}. This was stated at a secret meeting of the European Communist parties in Europe. A British intelligence agent was in the meeting, and furnished the U.S. that information. Later it was openly released and published.

The Russians met that 1985 deadline, and the resulting increase in killing U.S. missiles and aircraft in 1985-1986 was most indicative. Other indicators such as massive weather engineering were already ongoing.

Weather Engineering Over North America

The first KGB weather engineering tests over the U.S., using their relatively new interferometers, produced signatures of anomalous perfectly round holes appearing in clouds. These experiments started in 1967 or thereabouts. The Russians gave us that very severe "deep freeze" winter of 1967, as an initial weather-engineering test of their energetics interferometry weapons.

The KGB communists do have a sense of historical dates, and they often do things on certain dates in symbolic fashion. Full-time Soviet weather engineering over North America started in earnest on July 4th, 1976—our Independence Day and our bicentennial. This was the KGB's "gift" to the United States on such a historic occasion. Full-bore weather engineering over the Americas has continued to this day, and even increased. It was passed into the hands of the Yakuza and the Aum Shinrikyo upon their leasing of those interferometers on site in Russia at the end of 1989. In 1985 I produced a rather crude videotape[42] (40 minutes) with pictures of the giant radial cloud signatures etc. associated with such weather engineering operations since 1976.

The *basic* weather engineering method is simple. Use an LW interferometer (LWI) to reach through the earth and *cool* the air in a region and produce a high-pressure area, due to the densification of the air. Use another interferometer to *heat an*other area and form a low-pressure area, due to the expansion of the air. Then carefully steer those *highs* and *lows* by gradually and slowing rotating the distant antennae and slowly adjusting the interferometry range simultaneously, according to a calculated schedule.

---

[42] T. E. Bearden, "Soviet Weather Engineering Over North America," 1985.

By that means, the LWIs easily catch, entrain, and steer the jetstreams largely responsible for our weather. Put sharp loops and twists in that steering, and the huge angular momentum of the jetstreams developed in those sharp turns and circles will spawn tornadoes, violent weather, etc.

The first complete weather engineering system over North America in 1976 also used the Woodpecker's normal EM carrier signals with dimensioning and internal assemblage of the composite longitudinal EM wavepairs. A giant "interference grid" was established over much of North America. A great deal of local adjusting of the interferometry in the grid was necessary. These local grid readjustments caused "sudden popouts" of EM energy, creating many atmospheric booms, rumbles, and explosions.

To really stir up big weather trouble, the Russians—and now the Yakuza and Aum Shinrikyo—also heat or cool areas of the ocean where El Nino and similar "water engines" form. A dimensioned LW interferometer is required for this operation. By slowly and protractedly heating or cooling the water in one of the "warm water engines" fueling the weather, one causes a very significant, long-term, later effect on perhaps an entire continent.

One can create great droughts in some areas, great floods in others, etc. The KGB has been doing this extensively, since 1976. The great floods in Red China a few years ago are a direct example of KGB/Yakuza weather engineering, as is much of the extreme heat of 1998. In fact, thanks to the weather operations of the Yakuza under their KGB mentors, 1998 was the overall hottest year on record till then, since records were kept. At least for the summer of 2002, the record may have been broken again, with a significant season of giant forest fires burning away.

One purpose of the excess heating of the atmosphere, of course, is to do damage. An added "benefit" to the KGB is to furnish support to the environmentalists who are concerned about global warming. Understand, there is indeed such a thing as global warming. But by augmenting the atmospheric (and ice sheet) heating just a bit in a single year, the statistical analyses are skewed. The skewed analyses will show that the global warming problem is far more imminent than it really is, if the LWI engineering of it were suspended. Nobody on either side of the global warming debate seems aware of the LWI intervention that is ruining the results of their models and calculations.

In turn, the heightened global warming indications, detected as a result of the LWI interruptions, impel strong activist support for such things as the Kyoto treaty, *which is specifically designed to the strategic detriment of the U.S.* if and when the U.S. Senate ever approves it. The Kyoto treaty does not even apply to some 160 countries including Russia, China, etc. This focuses a certain proportion of our government time and effort in grappling with an inflated global warming problem, immediately. It directly fits the KGB strategy of "spreading" our government energy and attention all over the map, anywhere but upon the coming strategic energetics strike and upon energetics weaponry.

The die-hard section of the KGB strategists are chess players. *They will come at you anyway, anyhow, and anywhen that they can.* Everything that can be impressed to serve or support the overall objective, will be impressed and used. **That** is the overriding principle when analyzing Russian KGB strategy.

Khrushchev meant every word of it when he said to Nixon in their famous Kitchen Debate: *"We will bury you!"* Interestingly, to this day Americans and **their** government officials have continued to be deceived as to exactly what Khrushchev meant. He meant it literally.

Earthquakes to Order

According to U.S. Defense Secretary Cohen, electromagnetic induction of earthquakes is now recognized by the U.S. Department of Defense, considering **his** little-noticed statement in Georgia in 1997, which we previously quoted. An interesting exchange of induced earthquakes (Figure 54) had occurred in latter 1988 and early 1989. Here two sides seemed to be "counting rifles."

Opening bet (induced quakes)
- Quebec 25 Nov 88
- Pasadena 3 Dec 88

Raise you
- Armenia 7 Dec 88

Call - what do you have?
- Malibu 8 Jan 89

Four aces
- Soviet Central Asia 23 Jan 89

***Clear** table (stress relief)*
- Bakersfield CA et al. various

Figure 54 Counting rifles with earthquakes: Put up or shut up.

As Secretary Cohen made his April 1997 statement obliquely recognizing the scalar interferometer weapons, the little friendly nation had just completed countering and averting a massive strategic energetics strike upon the United States and Western Europe, scheduled for May 1, 1997 —just three days later. A little more than two months earlier, a previously scheduled attack had also been countered and averted by the same friendly little nation.

Once one can reach into or through the earth and ocean and create energy in a desired interference zone, induction of earthquakes is simple. Use the interferometers to deposit energy in a fault zone over a period of time. Keep it up, and the piezoelectric plates build up enough mechanical stress to forcibly "slip" and produce an earthquake.

Put the energy in very slowly, and one gets a long "overpotential" effect where the rocks do not slip for a long time, while the energy builds to higher levels due to the static friction of the rocks. Then there occurs a rather rapid catastrophic slip. In short, one produces a large destructive earthquake. The KGB weaponry can produce earthquakes of the highest magnitude if they work at it.

If one wishes to induce a quake in an area where there are no known faults, then one simply focuses the interference zone there inside the solid rocks and proceeds to deposit the energy, preferably rather quickly (in hours instead of days). The entire rock will be expanded and it will fracture, producing an anomalous so-called "flat plate" earthquake.

Around the early 1900s, the "normal" rate of large earthquakes was two or three per year. That gradually increased after WW II. During one week in year 2000, there were some 20 major earthquakes around the globe. Obviously, someone is doing it, since this is far beyond what could be expected naturally. Presently that "someone" is mostly the Yakuza and Aum Shinrikyo, on site in Russia and leasing the LWIs. With the scheduled CSR attacks forcibly aborted, the KGB has the problem of restraining an increasingly impatient Yakuza and Aum Shinrikyo group, while keeping them paying the lucrative lease money. Consequently, inducing some big earthquakes is one way to "keep the troops occupied and busy." Shooting down the occasional aircraft or missile is another way.

I worked for 8 years or more with an inventor (Floyd Sweet, now deceased) who had an energy device {127,128} sensitive to *artificially* induced quakes of that fashion, even such quakes thousands of miles away. The device would sit right on top of a *normal* quake and not react. We could tell within some 8-10 thousand miles—and often even for greater distances— which quakes were artificial and which were natural.

So during that period I was able to clearly ascertain what was going on, and who was doing what to whom, and which quakes were normal and which were manmade. Several artificial U.S. quakes, the Armenia quake, and a subsequent big quake in Russia were particularly interesting in the mid and latter 1980s. The huge 1976 China quake was directly induced by the KGB.

Figure 55 Brewer briefs President Reagan on Soviet scalar EM weapons October 1984, then briefs National Security Council

In 1984, on my behalf Roy Brewer {129} had briefed President Reagan on these scalar interferometry weapons (Figure 55), then briefed the National Security Council. Let us hope that these high level briefings may have borne at least some fruit.

Readying the Weapons for the 1985 Readiness Demonstration Tests

In latter April 1985 I received an urgent call from my close colleague Frank Golden. In his avionics repair work, he suddenly found that his best calibration instruments were very "noisy." He replaced one expensive instrument, and the second was "noisy," also. A third proved equally noisy. This was unparalleled. It was not the instruments, but instead it was all the electronics to be repaired, that were emitting electromagnetic noise!

So Frank borrowed one expensive instrument and brought it home for the weekend. He altered it by a proprietary method so that he could detect energetics radiation. Voila! The entire earth was alive with Soviet energetics signals. The weak interferometry of so many signals impinging into the weakly interacting electronic systems to be repaired, had generated the electronic noise his instruments had detected.

In response to Frank's call, I immediately proceeded to his location. I personally observed on the oscilloscope, as detected by Golden, some 27 pairs of Russian energetics signals, each of the two in a pair being 12 kilohertz apart. (We have previously explained why two frequencies are used, and one "pretends" one transmitted the difference frequency). Each of these frequency pairs represented the entire earth held in entrained resonance. Each pair was an "energy tap" in the earth, extracting enormous energy from the heat of the molten core of the earth itself and outputting it as 12 kilohertz power for transmission to giant interferometry weapon sites.

Each "tap" was extracting energy sufficient to power perhaps 4 to 6 of the giant intercontinental energetics interferometer weapons. We were observing something like 100 to 150 massive weapons on line and radiating. A full-up strategic dress rehearsal—or preparations for a full-up strategic attack on the U.S.—was underway.

Gorbachev was still a "new man on the job" at that time. Further, 1985 was the 40th anniversary of the end of WWII, and a very important occasion for the Communists and in fact for all Russians. The May Day celebrations that year went on for several days, not just on May 1.

What we were seeing were preparations for a massive May Day weaponry demonstration in and around May 1, 1985. We were observing the preparation and demonstrated readiness of all that great armada of Soviet energetics weapons, to meet Brezhnev's 1985 schedule laid down back in 1972 {126}.

Longitudinal EM wave communications to deep underwater Soviet subs, the huge interferometer armada, and everything else—all were being readied and demonstrated. I can assure the reader that observing full rehearsal of preparations for the next World War was a most sobering experience.

After May 1, most of the armada of interferometers was stood down again because it had been demonstrated that the "ready schedule" had been met. All but one of the giant energy taps in the Earth were also stood down again. That one remained active.

The May Day report to the heads of the Communist Party that year must have really been something!

As usual, apparently our own scientific and intelligence communities did not detect the main activities, and would not have believed it if one told them. They certainly did not believe it when I published it in 1986 in *Fer-de-Lance*, but labeled it sheer fantasy or at best total conjecture.

It was neither fantasy nor conjecture. It was direct experimental measurement. It was in fact what used to be called *scientific method.* The problem with our intelligence agencies was that they operated behind *policies.* Once the *policy* is decided, then regardless of what the intelligence analysis indicates, anything against the official *policy* is just ignored. This neat little *policy* method of doing business has resulted in making our intelligence agencies some of the most political-minded and manipulative groups on Earth.

Meeting the 1985 Schedule for Readiness

In 1985, KGB/Russian preparations began in earnest for the energetics weapons readiness projected for that year by Brezhnev in 1972. Being full-bore tests, these actually went after destruction of vehicles and killing people. These were actual acts of war. The so-called "Cold War" was not nearly so cold as pictured in the news media!

Early that year, an LWI was used to cool the combustion in the engines of a jet liner off the coast of San Francisco, bound for Los Angeles (Figure 56). This flamed-out the engines. The stricken craft fell 30,000 feet before the time-density "cooling" charge drained away, sufficient for the pilot to restart his engines and limp into San Francisco. Gravitational and inertial anomalies—*a clear signature of the use of this EM/GR weapon*—were exhibited upon the personnel in the cockpit. The official investigators ignored those signatures; after all, such is not in their standard checksheets! And everybody knows the standard checklists are already perfect!

SIX MILE DROP IN TWO MINUTES


CHINA AIRLINES FLIGHT 006
-TAIPEI TO LOS ANGELES-
19 FEB 1985
Interferometric cooling of combustion gases in engines
1 ENGINE FAILS. OTHERS REDUCE, THEN FAIL
41,000 FT UPPER LEVEL TROUGH; TURBULENT POCKET
Differing G-forces experienced anomalously by pilot and copilot. Impossible without unknown force also acting.
LANDING GEAR DOWN, DOORS TORN OFF
11,000 FT ENGINE RESTART
SAN FRANCISCO
9,000 FT RECOVERY

Figure 56 Extinguishing combustion in the engines of a jetliner 19 Feb. 1985.

KGB Crews Regularly Practiced Against U.S. Rocket Launches from Cape Canaveral

In a late Nov. 1985 night shuttle launch at Cape Canaveral, the Russian interferometer crews continued their practice of using the U.S. shuttle launches as convenient "simulated" ICBM launches, for energetics interferometer crew practice (Figures 15 and 16). EM missiles (balls of EM energy formed in the area by distant LW interferometry through the earth) were used as the "destructive agent", but were offset from the actual launch in order not to destroy the shuttle. This was *normal crew drill,* not combat operations. The practice range for energetics weapons is—as might be expected—the actual targeted area and targeted nation itself.

As shown in *Fer-de-Lance,* I published an actual picture (Figure 15) of such a KGB EM missile strike, offset from that shuttle launch in late Nov. 1985 and snapped by Bob Gladwin. I also published an actual picture of a second such EM ball of glowing energy (Figure 16), over the launch site for the same launch, and used as a registration point (the LWs deviate slightly in passage through the earth, since the potentials in the earth are not constant). George Suchary took the second photo.

A standard artillery "shift-from-known registration point" method of firing was being used. In other words, the crews establish LW track on that EM registration ball, right through the earth. That represents *a point having a known set of coordinates*—a registration point—established in the firing computer. Then when the targeted strategic missile (in this case the shuttle's main booster) ignites, the interferometer also tracks the huge ionization target of the exhaust with the same weapon system.

That gives a known *relative* location of the missile rear end, with respect to one's registration settings for the registration point ball of light. Then add some meters to move up onto the missile body proper, and voila! The center of the target missile that will be fired is now in the bulls-eye, so to speak. That is a standard "shift from a known registration point" method of shooting, well known to every artillery group on the planet. The "marker beacon" is what is known as a "high burst registration," except it is not a burst but a steady ball of energy maintained over the area as the registration point.

The distant rocket or missile can now be destroyed in a variety of ways:

(1) Just create a sudden EM surge arising right in that spacetime (that is, just pulse the interferometer). That burns out some of the inner electronics of the missile, causing partial or complete missile failure.

(2) Sharply pulse the interferometer to introduce EM energy surges and sparks in the fuel or solid propulsion, igniting it massively and blowing up the rocket. Works well for aircraft fuel tanks as well.

(3) Form another EM missile and hit the missile broadside with that, burning

through it and destroying it immediately.

(4) Hit it with an explosive EM missile internally, instantly exploding the missile into pieces. Or

(5) Hit it with several of the above simultaneously.

Suchary and Gladwin had captured the direct evidence of KGB dress rehearsal for the strike and kill of the Arrow DC-8 in Gander, Newfoundland about two weeks later.

Kill of the Arrow DC: Practice Turned into Performance

Two weeks later, the same KGB weapon tested against the Cape Canaveral shuttle launch was used to destroy the Arrow DC-8 at Gander, Newfoundland, killing some 256 occupants, 248 of them being U.S. soldiers returning from peace-keeping operations overseas. The aircraft *was not* iced up; later that was clearly established.

See Figure 17. As the ill-fated Arrow aircraft began its thrust down the runway for takeoff, it was already under LW interferometer track (the exhausts of the **engines** were being precisely tracked) by distant KGB operators. The KGB operators simply began to cool the combustion gases in the engine combustion chambers as had been done to a U.S. jetliner earlier that same year (Figure 56) off the coast of San Francisco (there they had completely flamed out the en**gines).** Now they did not want to flame out the engines during take-off, but just wanted to reduce the thrust of those engines.

So the available thrust of the engines began decreasing as the aircraft picked up speed on the runway toward takeoff, even though the turbines were rotating at full speed. For powered flight, it is the *thrust-per-drag ratio* that is important. One can reduce that ratio by ice-loading and therefore increasing the overall aircraft drag, as all Transportation Safety Board checksheets assume if the engines are at full rotation and if operation and icing conditions are present. Or one can reduce the ratio by reducing the engine thrust itself, as was done for the Arrow, even though the plane is de-iced. All the Transportation Safety Board checksheets *assume* that it has to be drag increase, and thus due to icing.

The National Transportation Safety Board (NTSB) investigators know nothing about longitudinal EM wave interferometry and its capabilities—and its development by several nations of the world. Neither do their checksheets. Sad**lly,** the NTSB is not even aware that the electrodynamics and electrical engineering it assumes is so perfect is in fact a decrepit old model based on century-old errors. They are unaware that much better electrodynamics models have long been developed for particle physics, because the crusty old classical model is totally inadequate. Their checksheets also are "unaware" of anything really modern such as electrodynamics models of the higher group symmetry **kind.**

The thrust reduction by combustion gas cooling *does not appear on the official checksheets and is never considered.* It is not considered to this day. It will probably still not be considered this century.

Observers on the ground heard those engines "laboring," which can be a direct symptom of combustion gas cooling and engine thrust reduction. Rough running and missing can be another, if the cooling increases. Engine flameout occurs when the combustion no longer can be sustained because of the dramatically lowered temperature of the gases.

The Arrow Pilot Sensed the Lack of Power, But the Aircraft Was Immediately Hit

See Figure 17. At rotation and liftoff, the pilot of the Arrow DC-8 immediately sensed his lack of lift, and started a slow turn to the right, apparently intending to come around and land again as an emergency measure. Meanwhile, crossed beams had formed in the sky above and off to the right side. From those crossed beams of light, there shot down a bright "streak" of light that struck the fuselage of the aircraft in the right side, ahead of the engines. That was the EM missile strike—just as had been offset from the shuttle launch two weeks earlier in Florida, and photographed by Bob Gladwin.

That piece of Arrow DC-8 fuselage hit by the EM missile, with the burned hole in it, was recovered and tested. Tests showed no explosive residues on the edges of the hole, so it *was not* made by a bomb or other explosive device. Instead, it was made by an EM missile of the type that over a decade later hit the TWA-800 several times off Long Island and killed it.

In the Arrow aircraft's kill, the fiery EM missile sharply ignited the plastics in the forward cabin, which explosively outgassed. One product of such outgassing is hydrogen cyanide. A whiff or two, and all the passengers in that section were already dying of cyanide poisoning. *In the autopsies of the recovered bodies, about half the passengers were already dead of cyanide poisoning before the plane impacted the ground and exploded*. They died while that aircraft was still flying and sinking tail-first toward the ground.

The results of those autopsies were deliberately withheld from the Canadian investigative board.

The impact of the EM missile on the Arrow DC-8 was clearly recorded by sharp, vertical EM surges (spikes) in traces on both data recorders on board the aircraft. In *Gravitobiology,* on p. 82 I printed the recorded sensor responses **for** that signature also.

Elements of the U.S. Government Deliberately Suppressed Vital Evidence

Several eyewitnesses, including Judy Parsons, physically observed the formation of the crossed beams in the sky. Parsons and perhaps others actually saw the streak-down and strike of the EM missile when it hit the doomed Arrow DC-8. Parsons tried to testify, but her testimony was never allowed to be heard by the Canadian Transportation Safety Board. A major U.S. News agency interviewed her, but then squelched the story for some "unknown reason." Other witnesses (who are still reluctant to come forward) did observe the strike of the EM missile also.

Why would the U.S. government deliberately suppress information relating to the cause of the deaths of 248 of our soldiers returning from peacekeeping missions overseas? Why were they so determined that this direct act of war be declared an "accident" in the face of overwhelming evidence that it was not an accident at all?

Iran Contra was not yet divulged at the time. Recall, at very high level our own fellows had directly violated the law, and were engaged in the illegal Iran Contra fiasco up to their eyeballs. Also, some officials in Washington in certain high U. S. Government circles were in near panic, in their personal (erroneous) firm belief that a MidEast-sponsored terrorist bomb had destroyed the Arrow. In that case, so they reasoned, with the murder of 248 of our soldiers, the American public would be so aroused and angry that they would force military action against the MidEast nation or group, and that would then reveal Iran Contra. *Too many highly placed people's hands were dirty!*

So extreme spin control was the major requirement. Damn how many American soilders had just been killed in an overt act of war against the U.S. Damn the implications of the use of eerie new weapons we did not possess. A hue and cry from the U.S. public would almost certainly reveal Iran Contra and smoke out the duly secrets. That must not happen at any cost. Some high officials—particularly the ones who engage in such illegal acts, in assassinations, murders, etc.—are far more interested in covering up their nefarious deeds than they are interested in any kind of justice or morality. Consequently, the fix was in.

So *U.S. officials placed enormous pressure on Canada to produce a finding of icing.* Lots of other skullduggery occurred, which probably constituted criminal activity by some U.S. officials. A high-ranking U.S. military officer arrived on site quickly, apparently under orders to erase that scene as fast as possible. He almost immediately wanted the Canadians to bulldoze over the site, even before recovery operations were complete and while the investigation was just getting underway. The site was bulldozed over in unseemly haste not long thereafter. That would appear to possibly constitute deliberate tampering with the evidence at an official site of investigation, on the part of whoever ordered the General to bulldoze the site precipitously.

In addition, witnesses such as Parsons were never allowed to testify. The Canadian Board waited until the half of its members who strongly opposed any ad hoc finding were absent, and hastily approved a finding of icing as the cause of the "accident." Later the disgruntled Board members who were absent when the "voting" occurred, issued their own minority report. Unfortunately they knew nothing of scalar interferometry and energetics weapons, and so they strongly believed it had to be sabotage and explosives.

Anyway, the blackguards hiding Iran Contra buried the incident, and the savage kill of 248 of our soldiers and 8 civilians went unpunished. Anyone such as the present author who pointed out what had really happened and why, was just branded a lunatic. After all, the blackguards who do not flinch at murder and unapproved assassination do not blink an eye at slander and libel.

The sad part is those fine young soldiers and the 8 civilians who were killed, and the grief and lasting changes made to their families. It is the children who had to grow up without their fathers, the mothers whose husbands were suddenly dead, etc. They deserved much better from their government than they got.

Other Direct Energetics Signatures on the Arrow DC-8

Meanwhile, in the lifting DC-8 the strike of the EM missile had also *time-density charged* the forward cabin materials. Those materials slowly decayed from their excited states via longitudinal EM wave emission. When a human body is subjected to fairly significant LW waves (accompanied with their time-density waves), it gets its internal immune system and cellular regeneration system "jammed," since these systems use LWs and accompanying time-density waves. The cells and tissues are also "time-energy charged" as well, and so spurious LWs continued to be slowly emitted in their tissues and cells locally, leading to gradual, general debilitation. After a time delay for the effects of this time-charge decay to be exhibited, such exposed persons will get sick with odd symptoms of various diseases such as influenza.

The ground handlers on the scene and exposed to the struck materials of the aircraft, were also exposed to longitudinal EM wave radiation from those materials which had been instantly "time-charged" at the powerful strike. Hence they were exposed to fairly significant LW waves, and should therefore have shown later symptomology.

Some 60 or so of the ground handlers actually retrieving the crash materials later sickened with all sorts of mysterious maladies: dizziness, stomach cramps, flu-like symptoms, weakness, nausea, fatigue, etc.—precisely what would be expected if some the materials they were handling were emitting longitudinal EM radiation, exposing them to significant LW radiation. That is a clear signature again of a strike by an EM missile, and the exposure of those retrievers to LW emissions. *In no normal way could 60 of those ground crewmen handling the wreckage debris all come down simultaneously with the exact symptoms of*

LW radiation sickness, unless that was what it actually was.

Many of those sickened persons remained debilitated for years. Probably a few are still alive and debilitated.

There are other signatures on the Arrow DC-8 kill. I did a small bit of work on the problem in the interests of Arrow airlines, but of course the conventional investigators they also hired could only conceive of an ordinary explosive. Nevertheless, I did tell them as best I could what happened to their aircraft, their crewmembers, and our own valiant soldiers.

Our troops on board the tragic Arrow DC-8 *did not* die from a simple over-iced plane that crashed as a result of carelessness in deicing operations. *They died as the result of an act of war against the U.S., carried out by the KGB as a test in an entire series to demonstrate the 1985 readiness that Brezhnev had specified in 1972.* That war is still partially ongoing and undeclared to this very day, with other players such as the Yakuza and Aum Shinrikyo also now in the game—and possibly even the Chinese, who certainly have had the weapons for some time, and have had QP weapons and negative energy EMP weapons since earlier this year (2002).

With the kill of the Arrow DC-8, the KGB made its deadline that had been set down 13 years earlier by Brezhnev. To meet the 1985 schedule, something significant had to be killed successfully and clandestinely, no later than Dec. 31, 1985. The KGB made the schedule on December 12, 1985, by killing the Arrow DC-8 after a warm-up and full dress rehearsal against a U.S. night shuttle launch at Cape Canaveral about two weeks earlier. And they also demonstrated just how ignorant of such energetics weapons and their usage the U.S. government, scientific community, and investigative boards really were.

We were fortunate they did not just go ahead and kill that same shuttle in late November 1985. Instead, they waited and killed the Challenger a few months later.

Other Acts of War Completed the Milestone

Apparently the final demonstration of milestone completion called for the destruction of an aircraft, kill of an ICBM, kill of a space shuttle, induction of earthquakes, and demonstration of the new quantum potential weapon still in the advanced laboratory stage. The KGB completed much of the milestone demonstration in 1985. The remainder they completed in 1986.

In January 1986 they killed the space shuttle Challenger, and the very next night the KGB even gave a big party in Moscow, to celebrate the "perfect success of their active measures" against the shuttle. General Daniel O'Connor, former head of U.S. Army intelligence, personally issued an alert to many high-ranking U.S. government officials, pointing out the almost certain involvement of the KGB and the fact that the loss of the shuttle was almost certainly due to a hostile act by the Soviets.

In April 1986 (May Day report time was coming!) the KGB killed a Titan ICBM fired from Vandenberg Air Force Base. They also induced several large earthquakes for practice, and then began the induction of the long-dreaded "giant California quake" in the San Andreas Fault zone.

This latter induction of what would have been a massive quake in both San Francisco and Los Angeles, and all along the San Andreas Fault, was countered (destroyed) by a civilian group known to this author, with a backlash that resulted in the Chernobyl incident.

In April 1986 (for the same May Day report) the KGB also demonstrated the effectiveness of their newly emerging quantum potential weapon against the convenient U.S. air attack on Libya (Figure 25).

Kill of the Titan Missile Over Vandenberg Air Force Base

In 1986, the KGB began gingerly using those energetics interferometry weapons to kill other U.S. aircraft and several U.S. missiles, including killing a Titan 34-D fired from Vandenberg AFB on 18 April 1986. The Titan was killed 9 seconds after launch, partially crippling the U.S. space surveillance program. That kill was part of the demonstration of readiness milestone completion.

There was a completely decisive signature on the kill of the Titan. Simply check *Aviation Week & Space Technology,* 124 (17), Apr. 28, 1986, p. 18, where a picture (the one taken from longer range) of the Titan explosion is printed. Look about an inch above that explosion, which is already well developed. There above the Titan explosion sits the KGB ball of light registration point, just as it was sitting over the night shuttle launch in Cape Canaveral in latter Nov. 1985 when videotaped by a private photographer.

I persuaded NBC engineer Ron Cole and his colleagues to analyze a copy of that video tape frame by frame. In 17 frames, that little ball of energy above the explosion moved off on its own course, independent of the Titan explosion. Since the launch area for such missile launches is controlled and there were no aircraft over the explosion, then one again has a very clear signature. The KGB killed the Titan, with 100% certainty.

That of course was a test of the interferometry weapons in the role of *Launch Phase ABM system*. Tested against the Arrow, the KGB operators were emulating test of the system in a *Launch Phase Antibomber role*. These were vital *strategic* weapon tests. I published details of the use of the weapons in many other roles.

Dead-Man Fuzing and Outside Assistance Deterred a Full Strategic Attack in 1986

We have previously documented and published why the U.S. was not fully attacked and destroyed by the Soviets in 1986. It was because of our nuclear facilities, warheads, etc. which would have exploded, creating great fallout hazards worldwide, and because of nuclear dead-man fuzing weapons clandestinely placed in Russia by one or more other nations.

A friendly small nation possessing energetics weapons also intervened directly in l986, and blew up several Russian missile ammunition storage sites, some five or so in six months. In one such explosion, about one third of all the missiles in the Russian Northern Fleet were destroyed. As we stated, the so-called "Cold War" was not nearly so cold as has been represented.

In short, the friendly little nation served notice on the Soviets that, if they moved against the West, the Soviet Union itself would suffer terribly. They put it in language clearly understood by the KGB. So any full-up strategic attack for that period was stalemated by that combination of factors.

A major concern for the Soviets was their inability to counter the dead-man fuzing problem posed by nuclear weapons clandestinely hidden inside Russia and by the nuclear warheads and reactors inside the targeted nation(s). They already had the quantum potential (QP) answer *theoretically,* and had conducted a demonstration test of a laboratory QP device, but they had not yet completed the *QP* weapon systems and deployed them.

Nonetheless, a very powerful strike of peculiar nature—induction of a giant earhquake in the San Andreas Fault zone, including in both Los Angeles and San Francisco—was scheduled. This strike would have caused billions of do11ars worth of damage and would have killed perhaps 200,000 Americans. The initiation of the strike was actually begun in April 1986—as the reader can begin to see, there was to be one helluva May Day report in 1986! Incredibly, a private group here in the U.S. then made a unique and unprecedented contribution that saved the day for Los Angeles and San Francisco.

What Really Happened in the Chernobyl Disaster

Using the "inside" of the Woodpecker beams as superhighways for their longitudinal waves and interferometry, in April 1986 the KGB interferometers had started their build-up of substantial induced EM energy in the sides of the San Andreas Fault that runs through Los Angeles and up through San Francisco. Two beams were being used by the Soviets: One was coming down on the target from the North—coming over the North Pole regions and the ice caps—and one was coming around from the East and upon the target area. Completely (100%) certain signatures were present, including some ELF "chugger" waves symptomatic of the Soviet method of inducing very large quakes. The time-energy is being used, hence very low frequency ELF is employed to maximize the amount of time-energy available for transduction in the rocks on the side of the fault. The Soviets were building up a very large earthquake—indeed, to spawn a whole series of such quakes all along the San Andreas fault—with severe aftershocks following after the main quake had done terrible damage. In short, they were preparing to hit California with the "big one" that everybody had been anticipating and dreading for so long.

A private group contacted me. They stated they could take out one of the transmitters by producing a powerful (giant) phase conjugate replica signal pulse upon it that would backtrack right into the transmitter and catastrophically burn it out—a surface application of the "phase conjugate shooting" once considered for armed satellites that could shoot down rising hostile ICBMs at 10,000 miles distance. As I understood it, they had a new kind of essentially noise-free regenerative amplifier, used in a transmitter. This meant that *extreme amplification* could be achieved in a pulse response to a received Woodpecker signal, before the transmitter burned out.[43] Since the group had no knowledge of the exact KGB transmitter locations or the possible consequences of such an action, they asked my opinion as to the risks associated. This placed me in a real quandary.

At the time, the U.S. was literally under siege. We have mentioned some of the

---

[43] A very subtle but important point is this: An energy flow of any amount—say, 10^{20} joules per second—has absolutely *zero power* if none of that energy flow is diverted or changed in form. So if one has a truly perfect noise-free amplifier, and a pure noise-free energy signal input, the signal energy input can be directly and freely amplified without limit, so long as those noise-free conditions can be upheld. In short, that rigorously constitutes *regauging,* and the widely used **and** well-known axiom of gauge freedom—the ability to change the local energy density of a system or spacetime freely and at will—applies. Relativistically, such re-gauging is merely rotating the frame of the system away from the laboratory frame. This group indeed had such an amplifier, which I physically saw, and apparently has it today. Our present texts have not yet realized the real implications of gauge freedom: It means that one can freely amplify energy without limit, once certain conditions (no divergence of the energy or change of its form) are met. This does not violate energy conservation; the "potential energy of a system" is not a fixed number at all, but depends on the frame of the observer vis a vis the frame of the system. We point out that there really are no true conservation laws in general relativity unless introduced by arbitrary measured The great Hilbert already knew this in 1917, two years after the advent of Einstein's general relativity. Hilbert stated: "*/ assert... thatfor the general theory ofrelativity, i.e., in the case of general invariance of the Hamiltonian function, energy equations... corresponding to the* ***energy*** *equations in orthogonally invariant theories do not exist at all. I could even take this circumstance as the characteristic feature of the general theory of relativity.*" [D. Hilbert, *Gottingen Nachrichten,* Vol. 4, 1917, p. 21]. Loskutov and Logunov commented as follows: *"In formulating the equivalence principle, Einstein actually abandoned the idea of the gravitational field as a Faraday-Maxwell field, and this is reflected in the pseudotensorial characterization of the gravitational field that he introduced. Hilbert was the first to draw attention to the consequences of this. ... Unfortunately, ... Hilbert was evidently not understood by his contemporaries, since neither Einstein himself nor other physicists recognized the fact that in general relativity conservation laws for energy, momentum, and angular momentum are in principle impossible."* ["Nonuniqueness of (he predictions of the general theory of relativity," *Sov. J. Part. Nucl,* 18(3), May-June 1987, p I79).

"target year" activities, such as kill of the Arrow DC-8, flameout of jet engines early in 1985, target practice against shuttle launches at Cape Canaveral in November 1985, etc. Actually kill of targets had continued in 1986. A huge earthquake followed by several large aftershocks had been used against Mexico City on 19 September 1985, causing great damage and demonstrating a little of what might be expected when they chose to hit Los Angeles and San Francisco much harder. The Mexico City quake had been preceded by an induced, giant hailstorm weeks earlier, and on the evening of 18 September 1985 by giant **radial** cloud signatures accompanying the generation of excess energy in the underlying rocks as the KGB prepared next day's giant Mexico City quake. The **reader** should recall that, working with Sweet during this period, I knew with certainty which earthquakes were natural and which were manmade.

U.S. missiles and aircraft had been hit, the Challenger had been destroyed, and **the** Titan 34-D had been destroyed at Vandenberg AFB on 18 April 1986, accompanied by a 100% indicator (the substantiated presence of the marker beacon for registration and shift firing). In addition, a little Richter 5.3 quake in the San Francisco Bay area had been induced by the Soviets on 31 March 1986, a quake which was correlated with preparatory activity on the Woodpecker transmitter signals the day before, showing Soviet induction of the energy to **create** the quake. Again, we had instrumental evidence that it was manmade.

That quake on 31 March had been a "warm-up" and practice for the big one now **about** to be induced in both Los Angeles and San Francisco, and along the San Andreas Fault. In fact, it appeared that the entire fault zone would be stimulated by deposit of excess energy all along its length. In that case, induction of a distrituted California quake of unprecedented extent and great magnitude was now in process, though just beginning. If that event or those events occurred, the loss of American lives and property would be staggering.

The High Side Risk Factor

The group's query to me presented a very difficult decision situation. Such huge Soviet interferometer beams, once built up, contain *enormous* longitudinal EM wave energy. If a Soviet transmitter were near large nuclear facilities, and were instantly blown and shorted, all that potential energy might flash directly into the ground.

In case of such a catastrophic transmitter failure, an enormously powerful longitudinal wave pulse would spread out in all directions in the surrounding earth. The first nuclear material the pulse encountered would be fissioned abruptly and very violently. If the transmitter were within a few kilometers of one or more of the large "monster" Soviet ICBM sites, the full-up explosion of **several 30** or 40 megaton warheads might result—in the dirt and dirty. The resulting fallout and contamination would be massive, would spread round the world, and would eventually kill millions for years to come. Nuclear reactor stations were a similar risk; instant fission of all the fissionable material in one of them would constitute an unprecedented and giant nuclear explosion, in the dirt and dirty. That was the high side risk.

The Low Side Risk Factor

The low side risk would be that little or nothing at all would happen; perhaps a tremor induced in a nearby fault zone, etc. I knew that the Soviets—after an early Kyshtym transmitter failure—had produced such a flashover on a much smaller scale and that flashover had caused the nuclear explosion of nearby stored nuclear wastes. The resulting fallout contaminated some 1200 square kilometers, which is still contaminated to this day. I also knew that, after Kyshtym, the Soviets had installed safety devices on all their scalar interferometer transmitters in case of just such failures.

So if the safety devices held when the transmitter suddenly shorted out, they could hold the longitudinal EM wave beams and potentials long enough to drain the energy slowly and harmlessly into the earth over an extended period. That was the low side risk.

The *most likely* consequence, of course, would be somewhere in the middle, between the extreme upper risk and lower risk limits. In other words, we could expect some bad repercussions in the Soviet Union almost certainly, but hopefully it would mostly be confined to that spot.

Consequences of Not Taking Counterfire Action

If no action were taken, the risk to the U.S. was appalling. If the transmitters continued, then perhaps 200,000 Americans were going to die in Los Angeles and San Francisco and along the San Andreas Fault. Perhaps 300,000 more Americans would be injured, and many of them would also die. Enormous physical damage would also be done, and those basins would be disaster areas for some years to come. It would be interpreted by our inadequate scientific community as a great "natural" disaster caused by a giant earthquake, and the ghost of Khrushchev would have had one more laugh at us, with his words "We will bury you!" silently ringing in the ether.

My Recommendation to the Counterfire Group

To save those American lives, some reasonable element of risk had to be accepted. In other words, it became a classic "risk-to-benefit" military analysis, but one that was deadly serious. To me, as a military person the medium risk had to be accepted in such case.

I gave the group my reasoning. They then asked what I would personally do if my own finger were on the fire switch. I answered that I would take out the transmitter or transmitters and save those American lives, accept the medium risk, trust in God, and pray **for** the best. Military decisions often have to be made in just such uncertain conditions. If one's military could not make such tough decisions, then one's military forces would inevitably lose their wars.

The Group Fired and Took Out a Transmitter

The group thanked me, stated that they would fire, and hung up the phone. See Figure 57. They did fire on April 25, just as they promised, and they did destroy one of the KGB transmitters—apparently located some kilometers (perhaps 30?) from the Soviet nuclear reactors at Chernobyl.

At the moment the transmitter was hit and destroyed, engineer Bill Bise—out in the field with magnetic field detectors and measuring the Woodpecker beams—observed the abrupt failure of the Woodpecker transmitter beam coming around **the E**arth from the East. Thus, he actually detected the successful destruction of that distant interferometer transmitter. Unknowingly he had detected the results of a great counterstrike in a very dangerous strategic battle.


SAFETY CIRCUITS
TAIL–END ESCAPED AND DISCHARGED
EGP
CHERNOBYL NUCLEAR REACTORS
GIANT STANDING SCALAR EM WAVE
MODIFIED RADAR
STORAGE CELLS
SLOW DRAIN FIELD

- 25 Apr. 1986
  - –Bill Bise detects loss of East-West Woodpecker transmitter
  - –Safety circuits kick in
  - –Chernobyl shuts down nuclear reactors
- 26 Apr. 1986
  - –Safety circuits fail
  - –Potential flash-discharges
  - –Strikes nearest reactor
  - –U fuel rods flare in fission
  - –Ruptures container
  - –Spews out nuclear material

Figure 57 Chernobyl disaster 25-26 April 1986.

Results at the Transmitter and at Chernobyl

We were very, very lucky. At the destroyed transmitter site, the safety circuits kicked in and caught the huge beam potential and held it for about 24 hours, gradually draining down the intense beam energy into the earth in a slow manner all the while.

A **frantic** Russian message to the Chernobyl reactors galvanized the operators to immediately shut down those reactors (put in the cadmium control rods).

However, the uranium in the fuel rods was of course still sitting there. Chernobyl then waited with bated breath to see if the safety circuits would hold.

Then on 26 April, the safety circuits at the transmitter site finally crumbled, and a far weaker LW flashover occurred than would have occurred earlier without the safety. The spreading LWs in the earth struck the nearest reactor core at Chernobyl, preceded seconds before by a tremor induced in the earth at Chernobyl as the LWs arrived. *Part* of the struck uranium in the core fissioned immediately, venting the containment structure and spewing out radioactive material. Nuclear fallout spread over much of Europe. The rest of the disaster is well known.

That unknown group, in my estimation, saved a large number of American lives—at least 200,000 or more and perhaps as many as 300,000. They also prevented enormous physical damage to California, both to Los Angeles and San Francisco and to points in between. The members of that group are the unsung heroes of this bizarre episode. It is my hope that I may live to turn the names of those persons in for the award of a very high Presidential medal. Until then I will not reveal those names under any circumstance.

Whether or not the U.S. scientific and intelligence communities know it or believe it is of no concern. What matters is that a great many Americans are still alive, and their children born since then are alive. Those Americans otherwise would have been very, very dead or never born. I personally have reflected on those desperate circumstances many times. If I had it to do over again, I would unhesitatingly urge the same action: Fire and save those American lives, and accept the medium risk. And pray.

And I did pray after recommending the strike. In my opinion, this time my fervent prayers were answered. I am extraordinarily sorry for the civilian deaths that occurred; all one can say is that it was under severe circumstances and in a very peculiar—and very desperate—war.

The Soviets had many other interferometers on line. They induced a substantial earthquake in Mexico at the end of April. Thus they did complete their "earthquake footsteps" of the milestone. On 7 May they induced a 7.7 Richter quake in the Aleutian Islands. If 7.7 to 9.5 quakes had hit all along the San Andreas Fault in Los Angeles and San Francisco and in between, then the destructive scenario I had envisioned for the West Coast would have occurred.


OTHER CLOUDS
MOVING WITH WIND
APROX. 20 MPH
(WEST TO EAST)
CLOUDS LEAVING
OR JOINING ARC
UPPER EDGE
IRREGULAR
STATIONARY
ARC OF CLOUDS
WELL DEFINED
LOWER EDGE
HAWKS
Lee Giles
DATE: 11/12/86
TIME: 2130
OBSERVER LOOKING SOUTH FROM I-285, NEAR ROSWELL RD., ATLANTA, GA

Figure 58 "Bottling up" shield practice over Atlanta 12 Nov. 1986. With a real shield, aircraft or missiles flying into it (from inside or from outside) explode and are destroyed.

On 12 November 1986 the Soviets even placed a giant "dummy shield" (practice) over Atlanta, Georgia (Figure 58). If the shield had been real and not just practice, any aircraft and missiles flying into it would have been instantly exploded and destroyed. That mode—"bottling up" a strategic weapons area—is useful to nullify an entire strategic ICBM launch complex or a large bomber base, etc. It can also "bottle up" a large carrier task force at sea, including the aircraft and the Tomahawk missiles, the shells from the naval guns, etc.

Kill of the Challenger Included Use of Metal-Softening

As we mentioned, during that 1986 preparation period the Russians also destroyed the Challenger spacecraft (January 28, 1986). Numerous signatures abounded, all of which we have already published.

A few weeks before the kill of the Challenger, a close colleague had experimentally proven that a metal-softening signal was indeed placed on the Russian "woodpecker" signals (Figure 7). He did this quite simply: he wired himself into a receiver, through an intervening amplifier, and tuned the receiver to the Woodpecker signals.[44] Then he took nails from a can of nails he was using, and hit them with a hammer to drive them into planks. The nails all folded up instantly like totally wet noodles. A couple dozen, one right after the other. Simultaneously, his son—who was not connected to the Soviet signal—was pounding nails from the same box, normally and without difficulty. None of the nails picked up and pounded by his son experienced any difficulty or softness.

---

[44] Here he was taking advantage of the fact that the infolded LW signals inside the Woodpecker carrier wave, comprising the "engines" for metal-softening, also constitute "perfect" divergence-free EM energy, so to speak, at least overall. Amplifying the signal also amplifies the "engine" inside it. When connected to his body, "potentials superpose" is the rule, and that transferred the amplified engines to his body and into the EM field immediately surrounding his body. Hence he softened the hammer metal a tiny bit, and softened the much less tempered nails quite a bit more.

Then my friend disconnected himself from the signal, and waited a bit. Whereupon when he then used nails from that same box, he drove them in without difficulty. There were no more "wet noodle" nails.

We reach a very simple conclusion: When he connected to an amplified Woodpecker signal, his body was time-excitation charged (quick charge and quick decay) with a specific signal so that the nails he picked up were charged. Then when hit with the hammer, the nails acted as if made of very limp rubber without a rebound. When he disconnected from the amplified Woodpecker signal, and waited a moment for the induced charge in his body to dissipate, the nails also discharged their engines and quit acting like limp rubber bands when hit, and became normal nails with normal behavior. That would seem to be quite sufficient to prove the thesis.

The Challenger was then destroyed, as we previously printed, with numerous signatures of the hit, including even a KGB party in Moscow to celebrate the success of killing the vehicle (and getting away with it).

Cold Molding: An Epilog to the Metal-Softening Donnybrook

I was called a total lunatic for pointing out a metal-softening capability on the Russian signals. So be it. Metal softening is achieved by an engine which serves as a pumped phase conjugate mirror for the vibrations and signals in the lattice bonds of metals. Build up that engine in the metal until the precisely reversed and overlaid signals negate the normal signals, and one has "dissolved" the lattice bonds, converting the solid to a liquid. Lattice bond cancellation is not heating.

But that was not to be the end of the "metal softening" story.

A few years later, working informally with a large UK aerospace firm "for free", I furnished them an address in Moscow of some Russian scientists associated on the perimeter of the KGB energetics weapon program. The address had been taken from their cautious advertisement for business on the Internet and furnished to me by a correspondent. A UK engineer fluent in Russian was sent to meet with those scientists in Russia. They nervously showed him several novel things, one of which was "cold-molding" of metal. The liquefied the **metal**

The result was that a hammer blow onto a nail head resulted in the nail acting as a limp noodle upon impact.

without heating, poured it in a mold, and waited for the "effect" to wear off and the liquid to turn back into a solid again.

Briefly, an energetics charge (using LWs) was induced on the metal lattice vibrations, adding their phase conjugate replicas to the interior LWs comprising the lattice bond signals. The metal's atoms were time-density charged to an excited state (presently not recognized in Western science). Thereupon the metal lattice EM forces "dissolved" and the metal became liquid at room temperatures and without heating. The cool liquid metal was then poured into a mold. Then after awhile, the time-density charge and slowly drained away, and the metal resumed its normal solid state—all without any heating whatsoever.

On a subsequent trip the engineer brought that Russian team itself out of Russia and to the UK. The Russian scientists demonstrated cold molding to assembled UK scientists, and to some U.S. visitors. The phenomenon was physically demonstrated and proven.

I was correct about the metal softening then. We were also correct back there in 1986 about the metal-softening signal employed against the Challenger (together with several other things).

There are numerous other signatures on the death of the Challenger. Again, *the death of the Challenger was not an accident.* It was due to a deliberate act of war by the KGB. The KGB knew in advance—after substantial probing incidents—that they would get away with it. And they did so.

Additional Update from Year 1998 to Year 2,000 Has Been Given

In the action package we sent to the DoD in 1998, we told the rest of the KGB energetics weapons story up to that date. We gave the attack plans as we saw them and the most useful types of attacks to be expected.

I hope the reader is interested in this special energetics weapons information. High power microwave weapons, high energy lasers, and nuclear weapons are useful but no longer decisive weapons either strategically or on the battlefield against a foe equipped with such energetics weapons, and particularly against a foe equipped with quantum potential weapons and negative energy EMP weapons.

At present, we are intensely watching to see if we can pick up indicators for the next scheduled strategic attack, its probable timing, and the "new twists" included in it.

Presently, we have perhaps an 80% chance that the little nation can once again counter any new threat and cause the KGB to abort the impending attack. On the other hand, with Putin apparently limiting at least some of the action of the KGB, we have moved into our present asymmetrical warfare against terrorism—

and ultimately against the extensive terrorist teams and assets already infiltrated into our homeland.

As a single example, before the collapse of the former Soviet empire, the Russians long ago slipped in nuclear weapons (from 20 to 40 KT) and hid them in all our large cities and population centers, along with the Spetznaz teams to detonate them on command.[45] Several nations have introduced teams with normal sabotage assets and also with weapons of mass destruction such as radioactive nuclear materials (for a dirty bomb), anthrax, smallpox, bubonic plague, etc. Behind the scenes, the die-hard remnant of the old KGB crew are using QP weapons to "spread" the immune systems (Figure 53) of our populace and materially enhance any BW strikes that the terrorists unleash. The rogue Japanese team (Yakuza and Aum Shinrikyo) on site in Russia are using their LWIs in a giant weather war and the occasional kill of an aircraft, etc. Over the decades Castro infiltrated some 10,000 guerrilla/special forces types trained in camps in Southern Mexico for decades. Probably at least half are still loyal and dedicated—and waiting to blow up bridges, power substations, high voltage power distribution system towers, dams, harbor facilities, refineries, pipelines (both oil and gas), etc. The first phase of WW III—delivery of the weapons of destruction and mass destruction to the targets along with means to unleash them—has already been accomplished.

We are particularly struggling against the rise of asymmetrical warfare—the superpower's paradox (Figure 59)—and our present involvement in that "new" kind of warfare is still quite foreign to us. Only time will tell how well we fare in this new type of war, which we will be engaged in for many years to come. Vice President Cheney rightly regards it as almost a state of perpetual warfare we shall have to learn to live with, as shown by his words on Oct. 21, 2001:

"The war on terrorism will not be over in our lifetime. It is different than the Gulf War was in the sense that it may never end. At least not in our lifetime. The way I think of it is, it's a new normalcy."

---

[45] See Stanislav Lunev (with Ira Winkler), *Through the Eyes of the Enemy,* Regnery, Washington, 1998. Lunev is a high-ranking GRU defector. He is a former Colonel in the GRU, the military counterpart of the KGB. In p. 22-33, he summarizes the Spetznaz capabilities. On p. 22-27, he summarizes Spetznaz use of nuclear weapons already on American soil. On p. 26, he gives some of the ways in which the Soviets easily brought nuclear weapons into the U.S. On p. 30 he confirms Russian seismic weapons. Use of EMP weapons is on p. 30-31. Use of very, very low frequency weapons to destroy the human brain, put people into a zombie-like state, and aid in brainwashing is confirmed on p. 31. And this is i**nformation** Okayed by the CIA for release!



Complex, expensive, high tech

Simple, cheap, low tech initially.
Later includes high tech and very high tech.

Figure 59 The superpower paradox: Asymmetric cheap WMD strategic strikes and destruction, later becoming extremely high tech and extreme yield.

There is Also a Severe Bioenergetics (EM Biological Warfare) Threat

The threat from bioenergetics is equally vivid. That old die-hard section of the KGB can now attack an entire population, e.g., with electrodynamically (energetics) induced diseases of any kind whatsoever, particularly when using QP weapons. Such attacks are totally immune to inoculations and antibiotic treatment. Any kind of strain or variation of a disease can also be induced in the pathogen pool for that disease. Against a foe who has such capabilities, our entire medical establishment—including all our emergency treatment procedures and agents—*is obsolete right now.* A vaccination and the presence of antibodies, e.g., does absolutely nothing against the EM induction of the exact physical effects and form of a disease, as shown in the decades-long "microwave radiation" of the U.S. Embassy in Moscow (Figure 11).

To the Assistant to the SecDef in such matters, in 1998 we furnished a 200+ page briefing package and loosely proposed a crash development of the new type of medical therapeutic treatment devices pioneered and proven by the Priore group in France in the 1960s and early 1970s. Later, Congressman Cramer queried that office for an answer.

Unfortunately the Assistant SecDef s office erroneously responded to Congressman Cramer that nothing in the literature supported the mechanisms proposed. Indeed, the package we furnished contained a *detailed list* citing the hard French scientific papers in the literature, reporting the exact experiments and the astounding results obtained. Some 2,000 highly successful animal experiments for more than a decade of experiments in fact supported the thesis, and higher group symmetry electrodynamics fully supports the ability to use EM means to make spacetime curvature engines, so that these engines then interact back upon the targeted matter to perform the actions desired. That it does not appear in conventional electrical engineering is of no consequence; it appears in physics and it is good physics, just on the cutting edge.

We also reported, explained, and cited Becker's epochal work (Figures 27 and 28), which is copiously published in the hard literature and which was an example of the fundamental mechanism also. Becker was twice nominated for a Nobel Prize for his outstanding work. Unfortunately, the Assistant SecDef s office responded with a non sequitur.

Packages were sent also to NIH, NSF, CDC, and several other government agencies. Not a single one of those agencies was interested enough to have a competent scientist contact me and discuss the area. I strongly doubt that a single scientist anywhere in the Government bothered to *seriously* read and ponder the material so painfully and expensively compiled and furnished. Lieutenant Colonel (Retired) Ken Moore and I worked our fingers to the bone for weeks, preparing that briefing, and we spent all the spare money doing it that we could rake up and obtain.

The near-total lack of response itself seems astounding, but it clearly shows the state of U.S. science with respect to novel energetics innovations, even long after those innovations have been experimentally proven and documented in the hard literature, and even after they have been weaponized against us. It is a direct indication of why the U.S. never deciphered what was going on in some four decades of Soviet weak microwave radiation of the U.S. Embassy in Moscow, including the kill (eventual deaths) of three U.S. Ambassadors.

For decades there have been manipulations, to say the least, in the hotly contested field of the biological effects of EM radiation. We refer the interested reader to an excellent expose of that situation: The expose is by Dr. Andrew A. Marino, Ph.D., J.D., *Powerline Electromagnetic Fields and Human Health,* which is current. I believe it can be freely downloaded from: http://www.ortho.lsumc.edu/Faculty/Marino/PowerlineTOC.html. Dr. Marino has been personally and deeply involved in the investigation of EM bioeffects, in court cases, and in Blue Ribbon Panel investigations and proceedings. The book is an eye-opener, and it gives one a good view of the machinations in the EM bioeffects field. We quote directly from Dr. Marino, Chap. 6, p. 1:

> *"Oversimplistic as it may sound, whoever pays for EMF bioeffects research and analysis determines what data is produced and the way it is interpreted. Soon after the possibility that powerline EMFs were health risks was raised in a legal dispute involving the New York Public Service*

> *Commission, power companies and their trade associations, particularly the Electric Power Research Institute (EPRI), became massively involved in EM bioeffects research. Subsequently, the power industry dominated funding of the effects of powerline EMFs, both in terms of absolute dollars and compared with dollars from non-industry sources...the power companies and their trade associations were deeply deceitful regarding the information they provided to scientists and to the public regarding the potential health hazards of powerline EMFs."*

In the entire EM bioeffects field, there does not appear to be any mention of, study of, or recognition of EM bioeffects induced by the most powerful EM factors: longitudinal EM wave irradiation, time-polarized EM wave irradiation, and time-excitation charging of particles throughout the body and its cells, with resulting emission of transduced longitudinal and transverse EM radiation *from-within-to-without.*

National Institute of Health Reaction

NIH replied to my letter and action package from their *Policy*—read: *spin control*—Section. They noted that the package mentioned the Gulf War Syndrome, which was not in their mission area. So they just sent it off packing to DoD (simplest way to get rid of it, apparently no one seriously read it or even cared to read it). I queried them back by separate response letter about their lack of interest in a revolutionary proven new medical methodology well-documented to cure cancer and other dread diseases, in many hundreds of experiments by leading French medical scientists. This was certainly within their mission area.

They hastily replied from the *Policy* Section that, yes of course NIH was interested in all such things, and told me where to "submit a proposal." We never got out of their *Policy* department. Again, not a single competent scientist in the U.S.'s supposed master medical agency apparently even read the package or cared to call and discuss the matter. This was an indicator of their total lack of any grasp of the energetics threat, its testing, and its use to induce the Gulf War Disease.

Now perhaps one can see why we are so far behind the KGB energetics weapons scientists and weapons program.

Marino, *ibid.,* is particularly enlightening on the adamant opposition by appropriate sections of NIH vis a vis the harmful effect of nonionizing EM radiation.

No responses at all were received from the NSF and the CDC, or the other U.S. government agencies to which the package was furnished.

The CDC of course comes under NIH, and thus its responses or lack thereof would be dictated by the parent NIH policies. As for the NSF, Marino, *ibid.,* again is enlightening on the qualifications or lack thereof of its membership.

So as the reader can see, the top of the medical establishment in this nation is flatly not interested in any "controversial" or "out of the box" proven method for curing cancer, dread diseases, and mass treatment of those millions of American casualties that are coming in our cities and population centers. Again, they directly ignore scientific method's very premise: *If the experiment is replicated and contradicts the theory, accept the experiment and change the theory.* I personally concluded that the U.S. Medical establishment largely does not follow scientific method, but follows dogma and the already approved methodologies.

How the New Revolution in Medical Healing Works

For the reader who is a medical scientist and trained in physiology and biology, one might be interested in that revolutionary French therapeutic methodology and how it worked (before it was ruthlessly suppressed in the early 1970s).

Priore's apparatuses (Figures 12,49, and 60) simply pumped the cells of the entire body with longitudinal EM waves (each accompanied of course by its time-polarized twin, in a Whittaker pairing). The cells and every part of them are very nonlinear, so they act as pumped phase conjugate mirrors for Whittaker wave-pair engines resident in the cells and acting as "input signal complexes".

Once the cells are pumped by these now-established *time-density* waves, the damaged or diseased cellular masses slowly "charge up" with excess time-excitation. The irradiation took several hours, and this was the "activation" or "time-excitation charging" stage. Thereafter, the time-charge decayed slowly, all the while constituting *pumping* of every cell and every part of it, in the time domain.

The resident engine in the cell contains two components: (1) the normal or healthy component, and (2) the abnormal component representing disease or debility. Pumping these two components time-reverses both of them and amplifies that reversal. This creates amplified and incredibly precise *antiengines* in each cell and in each part of each cell. These antiengines override the weaker cellular engines resident. In turn, this "reversing" action of the antiengines causes the pumped cellular masses (actually the mass-energy, in its exact structure and dynamics)—at any and all levels, including the genetics—to be time-reversed back to normal. In biological instead of physics terms, it "dedifferentiated" the diseased or altered cells back to a previous healthy state by simply eliminating the diseased engine component. *This is a dramatic extension of nonlinear optical phase conjugation from the 3-space pumping domain to pumping in the complex (time) plane, and it is effective for time-reversing mass-energy at any and all frequencies. We accent that the cellular*

time *reversal back to a previous state includes all the cell's genetics and every* ***part*** *of the cell no matter how small.*


Time-reversing the cells back to normal state
START
SELECT A SET OF TRANSVERSE EM WAVES
MIX WAVES IN A PLASMA, CONVERT TO LONGITUDINAL EM WAVES
MIX OUTPUT INSIDE STRONG PULSED DC MAGNETIC FIELD
EXPOSE WHOLE BODY OF PATIENT TO DIMENSIONED MAGNETIC FIELD
CELL AND ALL ITS PARTS ARE PUMPED IN INNER EM CHANNEL IN TIME DOMAIN
VACUUM ENGINE FOR DISEASED CELL ALREADY PRESENT
DISEASED CELL PHASE CONJUGATES ITS VACUUM ENGINE
ADJUST WAVE FREQUENCIES IF REQUIRED, AND IRRADIATE AGAIN
FORMS AMPLIFIED VACUUM ANTIENGINE FOR CELL'S DISEASE VACUUM ENGINE
STOP
YES
NO
CELL RESTORED TO NORMAL?
ANTIENGINE CONTINUES TO ACT AND TIME-REVERSE CELL AND ALL ITS PARTS*
TIME-EXCITATION CHARGING ENDS. IRRADIATION IS HALTED.
*Includes genetics

Figure 60 Block diagram of Priore's healing (regenerative and time-reversing) process.

Normal cells are just backed up to a slightly younger condition. Diseased cells **have** their abnormal engine component overridden and reversed back to zero (its earlier state), so that only a slightly younger normal engine remains resident in the cell. This simultaneously reverses the cellular masses back to their previous healthy condition.

Contrast this direct healing mechanism to the action of the immune system.

The immune system itself does not *heal* anything. It contains the killers, the scavengers, the locators, the markers, the attackers, and the troops manning the ram**parts.** Usually after a fierce battle with invading hostile pathogens, it wins. Lots of cells still living are damaged in the melee. The immune system scavenger cells then scavenge up the residue littering the battlefield. But *the immune system itself cannot heal and restore a single damaged cell, including one of its own.*

That healing and restoration of damaged cells is the job of the *regenerative system,* still little known and inadequately studied today. Perhaps the most fundamental studies were mostly by Becker *et al.* some decades ago. The regenerative system (Figure 29) is an EM system in its operation, as clearly shown by Becker (Figures 27 and 28), yet it is able to physically differentiate and dedifferentiate cells from one form to another at will, and in highly selective fashion. The regenerative system acts within its limitations (only weak pumping can be done for the time-reversal of diseased or damaged cells) to eliminate the delta (the deviation from normal of the resident engines in the pumped cell). That restores the normal (healthy) engine and slightly amplifies it as well.

It is obviously of the utmost medical importance to understand and apply (and amplify) this little-known technical mechanism by which the regenerative system is able to restore damaged cells back to normal.

It turns out that *the regenerative system in its novel EM functioning uses precisely LW and TDW pumping of those damaged cells and gradually time-reverses their entire masses back to a normal healthy state, within its limitations.*

This is the secret of the mechanism of the cellular regenerative system—which is an electrodynamic system of very unusual nature. The exact mechanism has not previously appeared in the literature. It took me 14 years to uncover that fundamental mechanism, and another 4 or 5 to refine it a bit, even though both Priore and Becker (as well as others) applied it decades before without being able to fully decipher it.

The experimental proof is already in the literature, once one understands the higher topology EM unwittingly used by both Becker and the Priore team. The proper types of higher group symmetry electrodynamics required to understand the action of the cellular regenerative system are available. There exist scientists skilled in their application and use. These scientists and that higher group symmetry electrodynamics are little used, and are never used at all in the medical field. There exists no funding anywhere for higher EM examination and modeling of the functioning of the cellular regenerative system—i.e., for the fundamental healing process.

Just imagine what this could mean to medicine: *One can now develop a new medical science to amplify and apply nature's own proven method of restoration and healing of damaged cells, including all their damaged genetic material*. It matters not what caused the damage, whether pathogen or gamma radiation, whatever. This new therapeutic method is a totally new general relativistic process where powerful spacetime engines are created which work directly upon the damaged cell and every part of it, physically reversing the cell and all its parts precisely back to normal condition.

General relativity rigorously tells us that a precise spacetime curvature engine (set of precise spacetime curvatures) is present and active for every specific disease condition and every nuance in it. It also tells us this flawed (disease or damage carrying engine) continuously operates on the cellular mass at every level, maintaining the exact physical condition of the cell and its dynamics. By creating a precise "anti-engine" and amplifying and applying it, general relativity assures us that we are physically acting upon the cell and all its parts at every level, down to the smallest—to precisely return every part in perfect proportion back to a previous normal healthy condition. *Pautrizel directly proved the time-reversal to an actual earlier state of the cells and the organism* (Figure 61). Amplification by time-domain EM pumping, means that we can cause this time-reversal of the cells back to normal to happen much more quickly than can the body itself, which can only pump very weakly.

- Pautrizel compared identical treatment of immature rats with immature immune systems, and mature rats with mature immune systems.
- Treatment restored the damaged mature system back to full mature functioning, and it promptly recognized and dispatched the pathogens.
- Treatment restored the damaged immature system back to full immature functioning, unable to cope, and the pathogens promptly reinfected and killed the immature rat.
- The lesson: The body is indeed returned to a previous physical state. The pathogens themselves are not killed by the treatment, but by restoring the ability of the immune system to recognize and destroy them.
- Only *the previous ability* of the immune system is restored by the process.

PROF RAYMOND PAUTRIZEL
(Renowned Parasitologist)

Figure 61 Pautrizel's proof of time reversal of the stricken cells back to a previous state.

General relativity also assures us that any and every disease is subject to this novel treatment approach, even diseases which have resisted every other known therapy. The Sachs unified general relativity and electrodynamics, and GR/EM unification applications in O(3) electrodynamics produced by Evans, for the first time provide a solid theoretical basis for Priore's methodology and his evolutionary results. They also offer direct engineering of startling physical cures, once the technology is developed.

The profound implications of that treatment can be seen. Apparently, however, **our** leading governmental agencies and health agencies do not see it, do not wish to see it, have no appreciation for general relativistic effects in healing, and do not intend to have any appreciation for general relativistic effects in healing. Indeed, they seem totally uninterested in even trying to comprehend and research *the fundamental healing mechanism* demonstrated by nature herself.

What the French Researchers Showed

Among other things, the Priore team produced revolutionary cures of *terminal tumors, infectious trypanosomiasis, suppressed immune systems, and atheriosclerosis* in several thousand laboratory animals in rigid laboratory tests under rigorous protocols. Eminent scientists such as Robert Courrier and Raymond Pautrizel worked with the Priore team. Courrier was head of the Biology Section of the French Academy of Sciences at the time, also *Secretaire Perpetuel* of the Academy, and a noted scientist of high stature. Courrier personally presented the astounding Priore results to the entire assembled French Academy. He also sent his own most able scientist assistant to personally prepare the terminal tumor grafts on the lab animals before their treatment.

A world-renowned parasitologist who did enormously important work with Priore was Raymond Pautrizel, who is still alive at this writing though quite aged. Pautrizel was greatly persecuted for his years of determination and effort. Courtesy of Pautrizel via the late Christopher Bird, I personally have the very Ph.D. thesis that Priore himself submitted to the University of Bordeaux on his revolutionary work. That thesis was maliciously rejected in the suppression that was applied to the project. When the French Government changed to a Leftist government in the mid-70s, Government support was immediately withdrawn and the project was ruthlessly suppressed. Priore later sickened and died and that was the end of that. More than a decade later a brave and determined Pautrizel finally was able to get a doctoral thesis approved in the Priore work area, at the same university, by another doctoral candidate, Eric Perisse {40}.

There are two U.S. patents on the Priore device itself, and of course several French patents also.

All the above was rigorously documented in the 1998 package prepared and submitted by Ken Moore and I.

While Priore was still alive, a team with which I was connected attempted to mount a well-funded effort to restore the Priore methodology while Priore was still alive. We also were viciously suppressed. The lives of our financial backers and their families were threatened. The head of our project was viciously attacked financially and destroyed, fleeing the country for his very life. Whoever thinks that dramatically innovative medical science in this country is just sweet reason and scientific method, should have a strong enema to remove the serious blockages interfering with his perceptions.

This vicious outside suppression of our project so infuriated me that I made a solemn promise that, were it humanly possible, I would decipher the Priore process before I died. It took 14 years, but we made good on that promise. During the 20 years or so since our project was suppressed, it is heartbreaking to consider the millions of children and sickened and suffering people who could have been saved had the project continued and succeeded. It is heartbreaking now to consider the coming millions of casualties in our civilian populace in our cities, most of who are going to die from mass destruction weapons. And most of those would not have to die, would the scientific community waken from its long sleep and discover some modern physics and higher group symmetry electrodynamics—and their application to solve nature's mechanism for **healing.**

When one time-reverses the body's cells and all their parts, one forces the diseased cells to dedifferentiate back to healthy state. We strongly accent that this is accomplished by unified GR/EM processes involving precisely **organized** spacetime curvatures and their local actions in the cells and all their inner components, down to the finest level. It can be rigorously expressed in good unified physics, as expressed in an electrodynamics such as O(3).

The nondamaged or nondiseased cells just get a little younger. That is also highly beneficial; it reverses the ravages of aging, just a little. Indeed, one of the implications of the Priore mechanism is that aging can indeed be reversed by the process and treatment. Again, one must keep one's sense of humor. In order to get this technology and therapeutic method born, what seems to be needed is an extremely wealthy person, strongly desiring to live longer than the expected life span and do it in a vigorous, healthy body—and who is willing to fund the project with the necessary $60 million required so to redevelop and extend the Priore technology so it can be readily applied. A byproduct will be the saving of millions of American lives when those coming mass casualties from weapons of mass destruction occur in our cities.

How the Regeneration Mechanism Was Finally Deciphered

What took so long in deciphering the mechanism was the problem of how to make such precisely tailored and exact ST curvature engines, specifically so that they are *exact* antiengines for a specific disease and even a specific pathogen, and even for different versions of the engines for different cells in a single body having different strains of the same pathogen, having different body DNA, etc. For years, the solution of that task seemed hopeless. How on earth could one possibly work all that out in a hundred lifetimes, so that it could be precisely calculated even by an array of the most powerful computers on Earth?

After years of struggling with the problem, in one stroke of enlightenment it was revealed to be the simplest thing in all the world. Absolutely no calculation was necessary, and the exact amplified antiengine effect was a fairly simple and straightforward thing to obtain. General relativity tells us that every cellular mass and each part of it, has its own unique spacetime curvature engine, to the finest detail and an exact fit. As Wheeler put it so nicely {130}, *"Space acts on matter, telling it how to move. In turn, matter reacts back on space, telling it how to curve. "* The mass and its dynamics and the engine and its dynamics constantly interact upon each other, and "keep attuned and in perfect adjustment," so to speak.

That means that a "normal" cell already has just such a precise "normal" ST engine residing in it, and acting upon every component at every level—even in the atomic nuclei. Well, a diseased cell has an absolutely specific structuring, and therefore it also has an absolutely specific ST engine structuring. *A priori that* resident structuring for the diseased or damaged state in the individual cell differs (by some delta) from the structuring of the normal healthy cellular state for that individual cell.

Voila! That means that *the ST engine for the damaged cell can be decomposed into two parts (two engines):* (1) the normal "healthy cell" state engine, and (2) a delta ST engine that has been added to it so that together the two comprise the full ST engine for the exact individual condition of the cell.

What is now needed is a way to produce an exact antiengine of two parts: (1) one for the normal engine and (2) a second one for the delta (disease) engine. Applying this amplified and combined "antiengine" would overpower the resident combined engine, precisely reversing the cellular condition by reducing the delta to zero. Rigorously, the cellular mass and every part of it must then also revert to a previous physical state, or else we must complete discard general relativity itself.

Well, if we were to just time-reverse the resident engine and its two components, that would give us the perfect antiengine with its two components. Amplifying this antiengine would then produce one that was more powerful than the resident engine in the cell. Applying that amplified antiengine to the cell, that would not really change the "normal" engine component, but it would precisely reduce the delta engine component back to zero (its previous state, before it was there!) Voila! A specific healing signal of perfect structure, for the specific deviant condition of the individual cell and its every part.

Since we have a combined GR/EM to use, we can think electrodynamically about this general relativity problem. Immediately we see that phase conjugate optics is a candidate, since the "resident composite engine" can correspond to the "signal" or input wave, and the pumping of the nonlinear mass of the cell and its parts (where they act as nonlinear phase conjugate mirror materials) produces an exact phase conjugate replica (the exact amplified antiengine). The presence of that antiengine overrides the magnitude of the resident engine, and it moves the cell precisely back along the temporal path previously taken. In short, it applies a specific kind of dedifferentiation of the cell back to its previous healthy condition.

Since we extend phase conjugate pumping to the time-energy domain, then the resident composite engine and its time-stream component are the "input." The amplified antiengine and its time domain component will then forcibly propagate that pumped mass energy back over the time trajectory previously taken by it. In short, it will time-reverse the cell and all its parts back to a previous condition, completely eliminating the delta (disease or disorder). The beauty is that it will also reverse damaged or altered genetics, such as in the AIDS disease. It can do this prior to the appearance of health symptoms—it can be done as soon as the patient tests positive for HIV.

Since the antiengine is amplified, it moves the cell back to normal fairly rapidly (in a few hours, for example). At least the time charge for the reversal process is delivered in that period; one may allow (as Priore did) a full week for the time-charge and its transduction to continue reversing the cells. But it is much faster than the normal speed of the human regeneration system using the same process, because now we have greatly amplified the time-reversal rate.

It is therefore ideal for a method of quickly treating mass casualties, particularly since it can be developed and used in a portable unit about the size of a large suitcase (Figure 13).

Interestingly, during the radiation with LW EM radiation, one also pumps the pathogen and time-reverses it as well. Its "normal state" towards the beginning was a condition whereby it could move with relative immunity past the immune system's opposition, having deceived the immune system. In the treatment, a small amount of the pathogen is therefore converted back into this condition just shy of the beginning, where that part of the pathogens is resistant to the immune system. However, a very small, short "post treatment" irradiation with LW radiation for a much shorter interval and at weaker power, will clean up this altered pathogen residue by allowing the immune system to recognize it and destroy it. Pautrizel clearly demonstrated this significant fact.

Cellular and Body Rejuvenation are Possible, Once the Technology is Developed

One can in fact really accomplish *rejuvenation* of the aged and infirm, as the technology is developed. One could certainly solve the major problems of Medicare, and cut the patient load at least in half, relatively quickly and inexpensively. Of course lots of big U.S. drug companies will be rather violently opposed to any such idea, because much of their empire would be threatened. Much of the organized medical community depends largely on the Big Drug Approach. So the organized medical community will also vehemently oppose it, just as the formal medical science community in France viciously opposed it.

One could also produce cheap, portable LW treatment units *en masse,* which is what we were suggesting to the Assistant. SecDef. That way one could flood the emergency response system (response teams, hospitals, fire stations, police precinct stations, schools, etc.) with quick and effective treatment devices. They could be used to rapidly {131} treat those millions of American casualties that are going to occur when one or more of our cities are attacked in the near future by terrorist WMD attacks. This would save the lives of most of those stricken millions of Americans.

How Many Americans Could Be Saved?

For an anthrax attack on Washington, D.C., first generation equipment could save perhaps 70% of those sickened Americans, almost all of who are going to die with *present* capabilities. With second-generation equipment, one could save perhaps 90%.

For an anthrax attack without spreading via QP clandestine preparation of the populace, one would save 0.7 to 2.1 million Americans. With clandestine KGB QP spreading and a *5:*1 increase in the yield of the anthrax strike, one would save 3.5 to 10.5 million Americans.

For a truly nightmare attack (as a worst case scenario) perhaps 5 major cities might be attacked in such manner and to such degree. In that case, one is talking about saving 3.5 to 10.5 million Americans for the unspread attack case, and up to 17.5 to 52.5 million Americans for the spread case.

Further, the development of the necessary portable treatment units is doable and affordable, for mass treatment capability. Training on a portable machine could be done for a high school student in 30 minutes or less, and that student could then give emergency treatment effectively.

Absolutely nothing else out there can presently warrant such projections. Yet this is the very technology our own medical science community is eminently uninterested in, has no knowledge of, does not wish to obtain any knowledge of, and does not wish to scientifically discuss.

There Are No Resistant Strains to the New Technology, and There Cannot Be Any

A most interesting thing is that there cannot be a "resistant strain" of a pathogen for the new treatment methodology, *a priori.* No mass can shield against spacetime curvature effects. Slight adjustments of the controls will adjust the spacetime engines being utilized. Two or three hour's work with a developed unit and a lab team on a new strain would suffice to completely determine the required adjustments, once the technology is developed. The new information could then be quickly relayed to all stations treating patients. On each treatment device, adjusting a few dials and controls for the laptop computer controlling the unit will do the trick. The use of the final device would be so simple that a teenager could be trained to use it in less than 30 minutes.

Such new capabilities are urgently needed not only for the millions of civilian casualties we expect in the future, but also for support of our armed forces in the field. Frankly, the anthrax shots are not going to do them much good, once one realizes that the "spreading" of their immune and regenerative systems is already occurring via KGB quantum potential means. Camel pox is available to any terrorist foe, and has almost the identical actions and constitution as smallpox. Indeed, it is almost identical to smallpox.

The Gulf War Disease and Syndrome were just small preludes of what is to come and what is already being used against the entire U.S., though as yet very clandestinely. Look again at the Kaznacheyev work. *He clearly proved in thousands of successful experiments that any kind of cellular disease or damage or death whatsoever, can be induced at a distance by novel EM means.* Replication experiments were successfully accomplished at the University of Marburg and also at the University of Sydney.

Results of the Priore' Treatments Are Well-Documented and Independently Supported

The Priore team's results are well documented in the hard French scientific literature. At least one French doctoral thesis was eventually accepted upon the work. The astounding results really occurred. They were scientifically substantiated under rigorous protocols and even police-guarded labs for tests by a learn of outside scientists. To then deny those results simply because no one **has** *understood* the active mechanism until now, is to deny the scientific method itself: *Believe the experiment when it refutes the prevailing theory.*

There is also independent work by other scientists that strongly supports the Priore results, once the mechanism is finally understood.

Robert Becker *et al.* in the U.S. conclusively showed that living cells *in situ* can be dedifferentiated, redifferentiated, etc. by laughably weak currents (picoamperes) and DC potentials (which are comprised of those famous Whittaker pairs). Becker was unaware that his potentials included time density waves and longitudinal waves, as predicted by quantum field theory and as shown by Whittaker in 1903 (once one understands that a bidirectional phase conjugate longitudinal EM wavepair is a time-density EM wave coupled to a longitudinal EM wave). Application of such EM potentials by Becker transformed red blood cells into pre-cartilage cells, then further into pre-bone cells. That latter cell type was then deposited in bone fractures, healing them when nothing else would. Becker and others have demonstrated partial regeneration of limbs in small test mammals, using the technique. The bone-healing techniques were finally approved by the FDA and are often used in some hospitals for treating otherwise intractable bone fractures.

Since then, other scientists have shown the directed formation of other types of body cells from cells from distant parts of the body (i.e., muscle-type cells from cells produced in the bone marrow, etc.). Such things are now well documented in the U.S. literature, in at least several hundred papers and in the leading journals including *Nature, Science,* etc.

The Present Threat Is Urgent, and Our Strategic Destruction is Still at Issue

Our own medical community, our science community, and our intelligence community are at least 20 years or more behind the KGB right now. We are also behind the Chinese. In many respects our scientists have simply missed the biggest scientific breakthrough of the century.

It is urgent that we find some way to counter and avoid future strategic energetics attacks sure to be scheduled. The eventual attack actually launched—if the little nation's QP weapons can be countered first—would destroy the U.S. in about 2 hours. It only takes about 10 minutes, it seems, for the QP weapons *already deployed* to negate almost all our strategic nuclear arsenal. Thereafter, the KGB and Yakuza/Aum Shinrikyo can simply attack us at will and utterly destroy the U.S. To any loyal American, that is an entirely unacceptable solution.

The most urgent requirement would seem to be immediate and strong contact at the highest level between the U.S. government and the leaders of the little foreign nation (and the other friendly nation) that presently is guarding the ramparts and saving our necks. A cooperative crash program to develop our own QP weapons would seem to be the order of the day, if it can in any fashion be negotiated. But to have any chance of success, the President and the Congress will have to use the utmost care in selecting the U.S. negotiators and scientists to explore this possibility.

Immediate transfer of the requisite capabilities to the U.S. would be desirable, at least from our own view. From their view, of course, we do not necessarily resemble a trustworthy scientific partner at all, based on our past scientific performance, and it is up to the U.S. scientific community to prove to them that the leopard really has changed its spots. That would all have to be negotiated and worked out.

If that is not possible, then it is of extreme urgency that our own country embarks upon a new Manhattan Project to develop strategic quantum potential weapons and defenses. It would be a great relief to discover that such had already been started, but I fear not.

Desperately Needed Defensive Capabilities Can be Provided by a QP Solution

We pose one more very, very useful QP capability prior to closing. As we stated, if a large U.S. city is hit with—say—an anthrax attack done in professional manner, we would expect 1-3 million casualties, according to a well-known major U.S. government study. With immune/regenerative spreading presently already ongoing here in our populace by KGB QP weapons, that figure may actually increase by about 5-fold. So the casualties (prompt and delayed) might well reach 5-15 million, in a single *professional* anthrax spray attack by two persons from one light plane on a calm night dispensing 100 kilograms of anthrax spores sprayed over the city with a simple agricultural sprayer. With the indicated Priore technology and treatment units in all emergency response hands, at least 70% or so of those casualties could be saved. Otherwise, *presently almost all of them will die.* That dramatic saving of lives is one desperately needed capability that could be met.

But there is a further capability of LW technology that nothing else presently known can do without serious impact upon the populace.

After the prompt and shortly delayed casualties are mostly cured and the remaining fraction dies, a terrible problem of BW contamination still remains. No one anywhere really knows how to clean up an entire city from anthrax spores. But unless harshly decontaminated, that contaminated city is going to be effectively uninhabitable for decades to come, if only the present technology and methods are available. Islands of the coast of Scotland, where anthrax was tested decades ago, are still "hot" and contaminated—and off limits.

The indications are that our nation has developed chemical sprays that can kill and neutralize the anthrax, including in the lungs of the populace breathing the spray. On the other hands, it is indicated that the spray is a high physical stress factor, and some of the more debilitated citizens will be injured or even killed by the spray itself. This includes babies and small children, the aged, those with lung and breathing difficulties, etc. As a matter of national survival, desperate diseases do deserve desperate remedies. So while spraying the zone might itself sicken and kill some thousands of our weaker citizens, at least—so the thinking would go—it saves millions. This of course is similar to the use of triage—reserving treatment and scarce medical capabilities and supplies for treating those most likely to live and recover with treatment, rather than treating those more seriously affected and less likely to survive. Sadly, presently triage will almost certainly be necessary because of very short supplies and treatment teams, etc. So most of those 1 to 3 million casualties will simply be dragged aside and left to die, and just made as comfortable as possible.

However, the QP technology can be adapted to produce systems that can indeed do complete decontamination, very quickly, and without harm to the citizens in zone. The anthrax can simply be modified by specialized spacetime curvature engines—specialized EM fields and waves carrying hidden inner "information content of the field" engines that are designed specifically to change and destroy anthrax and nothing else. Eventually one could develop the capability to do it similarly for *any other* major contaminant, including nuclear radioactive materials contamination of a major city.

Any strategic and tactical analyst can immediately see the tremendous value of such capabilities.

In Conclusion

I hope the above admittedly lengthy overview is of interest to the reader and useful. If we are to survive the debacle that now looms before us in this new asymmetrical war we shall be in for decades, it will require the efforts of leading and dedicated Lawmakers and Overwatch persons. Without firm prodding, the military, scientific, and intelligence communities are likely to just continue their present pace until many or most of us all die suddenly.

The KGB energetics threat is still real and imminent; Russia is not a monolith and Putin still does not have complete control over the KGB. Another full strategic attack is sure to be scheduled before very long by either that die-hard faction of the KGB, the Yakuza/Aum Shinrikyo, the Chinese (particularly if they move against Taiwan and we defend), or someone. And so our possible deaths also to be taken into account, if we just continue to do business as usual.

Along with other Americans, I love my country and served it to the best of my ability for 20 years of active duty. It is the survival of America itself that is now at stake, both in the asymmetrical war against terrorists and in the continuing war against energetics weapons. Our scientific, military, and intelligence communities simply must be jolted awake and into massive efforts in energetics.

We have the scientists with the required capability. We have the facilities. We have the leadership, and we can do it if we can put this thing under a Presidential Decision Directive, under an Executive Order and a Declaration of National Emergency (along with the several already in effect).

Thomas E. Bearden, Ph.D.
Lieutenant Colonel, U.S. Army (Retired)
President and CEO, CTEC, Inc.
Director, Assoc. Distinguished American Scientists

1986

Fer De Lance

Briefing on Soviet Scalar Electromagnetic Weapons

T. E. Bearden, Ph.D.
LTC, U.S. Army (Retired)
Director, ADAS

1986

Note: This is the original Fer De Lance briefing paper wich includes some minor text and artwork editing.

1986 FER DE LANCE INTRODUCTION & BRIEFING ON SOVIET SCALAR ELECTROMAGNETIC WEAPONS

This briefing presents the basic concepts of Soviet scalar electromagnetic weapons, some of the major types available, and evidence of their widespread testing.

Scalar Electromagnetics is Electrogravitation

Scalar electromagnetics is an extension of present electromagnetics (EM) to include gravitation. That is, it is a unified, and, what is more important, it is a unified engineering theory. Nikola Tesla initially discovered its basis.

In the scalar EM extension, EM field energy can be turned into gravitational field energy and vice versa. This exchange can be patterned and localized, in specific areas or objects. Such a controlled change of electromagnetics to gravitation is not possible in the normal EM or physics presently taught in Western textbooks. However, the bits and pieces of the theory have been scattered through the physics literature for some time, but no orthodox Western scientist seems to have realized that these anomalous portions could be integrated into a startling new physics. Unorthodox experimenters, inventors, and scientists have made discoveries in this arena for several decades, but again have not realized the exact implications or the precise manner in which their results could be combined with present electrical physics.

Fer-de-Lance

Such sluggishness is certainly not present in the Soviet Union. For over three decades, the Soviet Union has been developing electrogravitation and applying it to develop strange new secret weapons of incredible power and capability. They have sustained the largest weapons development program ever launched by any nation, and they have kept it effectively hidden from prying Western eyes. 1 have called this program "Fer-de-Lance," after the deadly South American pit viper of that name.

The dreaded fer-de-lance is a snake of great agility and lethal effect. It often ambushes its hapless prey, and strikes unexpectedly and without warning. Its first sudden strike is usually lethal to its victim, which promptly expires in writhing agony. Since the Soviet development of scalar EM weapons has been designed for the same purpose, the name seems appropriate.

The equivalent effort of about seven Manhattan projects has been poured into Fer-de-Lance by the Soviets, and the program has been successful almost beyond imagination. The eery weapons are now developed, deployed, and tested. The ambush has been completed; Fer-de-Lance is coiled and ready to strike.

Energetics and Directed-Energy Weapons (DEWs)

The ordinary Soviet name for this type of weapons science is energetics. In the West, that term is believed to be associated with conventional directed-energy weapons (DEWs) such as particle beam weapons, lasers, radio frequency (RF) directed-energy devices, etc. The Soviets do not limit the term in this way.

Western scientists are familiar only with directed-energy weapons where fragments, masses, photons, or particles travel through space and contact the target to deliver their effects. Hence in their thinking they limit the Soviet term "energetics" to the type of weapons they themselves understand - exotic but normal weapons using energy or mass traveling through space to impact a target.

However, it is possible to focus the potential for the effects of a weapon through spacetime itself, in a manner so that mass and energy do not "travel through space" from the transmitter to the target at all. Instead, ripples and patterns in the fabric of spacetime itself are manipulated to meet and interfere in and at the local spacetime of some distant target. There interference of these ripple patterns creates the desired energetic effect (hence the term energetics) directly in and through the target itself, emerging from the very spacetime (vacuum) in which the target is imbedded at its distant location. As used by the Soviets, energetics refers to these eerie new superweapons, as well as to the more mundane DEWs known to the West.

As a consequence of the Soviet breakthrough and decades of feverish development, monstrous strategic weapons undreamed of in the West are already in Soviet hands. A noose is slowly and steadily being tightened about our throats, and it is already the 11th hour.

The Soviets Use a Deception Plan

Concomitant with this supersecret development program, the Soviets developed and implemented an elaborate deception plan to conceal these startling weapons and their nature from Western eyes until it is too late. Soviet deception has been so successful that even when Western scientists are confronted with the actual Soviet tests of these weapons directly over their heads, they do not recognize the weaponry nor the nature of the effects produced.

As early as January 1960, Nikita Khrushchev announced the Soviet development of a new, fantastic weapon. On May 1, 1960 Soviet defensive radars - rigged as prototype weapons of this new kind - probably downed Francis Gary Powers's high-flying U-2 reconnaissance plane over the Soviet Union, precipitating a major diplomatic incident.

On April 10, 1963 one of the first new superweapons operationally deployed was used to destroy the U.S.S. Thresher atomic submarine underwater, off the east coast of the U.S. The next day, April 11, 1963 the same deployed superweapon was utilized in a different mode to produce a giant underwater explosion in the ocean over the Puerto Rican Trench, 100 miles north of Puerto Rico.

Over the years, various aircraft were interfered with or downed as tests of these Soviet weapons. A particular case involved the mysterious loss of F-111s in the Vietnam conflict. At least one downed F-l11 crew was recovered in the subsequent prisoner-of-war exchange. On that aircraft, all electrical systems suddenly were in difficulty simultaneously. All emergency indicator lamps were lit up, "like a Christmas tree." This was probably due to special Soviet teams converting some North Vietnamese SA-2 missile system radars to the scalar EM mode, and employing "scalar beam" interference to produce spurious EM noise throughout the electrical and electronic systems of the aircraft.

In late April/early May of 1985, the entire armada of Soviet strategic scalar EM superweapons was activated as a special celebration of the 40th anniversary of the end of WWII. Activation of this armada (which probably contained over 100 giant weapons), together with 27 giant power systems and a large number of command and control transmissions, was monitored on an advanced, proprietary detection system by Frank Golden. After the giant strategic exercise, which lasted several days, most of the weapons and power sources were once again stood down to "standby."

The NASA shuttle launches provided a convenient opportunity for Soviet testing of these superweapons in a Launch Phase ABM mode, where a launched missile can be detected and destroyed shortly after liftoff. At first, electromagnetic pulse (EMP) bursts on the early shuttle trajectory were deliberately delayed in time, to prevent actual destruction of the target and avoid alerting the U.S. that something unusual was happening.

The shuttle launch of November 26, 1985 saw a particularly significant-test of this kind. In this case, a very loud "sonic boom" or explosion occurred over the launch site 12 minutes after shuttle liftoff, when the shuttle was already away and downrange. At least two previous shuttle launches had also been used as pseudotargets, with delayed booms occurring over the launch site well behind the vehicles.

After the lack of U.S. reaction to these three tests showed that the U.S. still had no knowledge of the new technology and did not even recognize its employment, the Soviets apparently decided to proceed with tests where the target vehicles would actually be destroyed.

On December 12, 1985 the same Soviet weapon tested against the NASA shuttle launches may have deliberately interfered with the controls of an Arrow DC-8 taking off from Gander Air Force Base, Newfoundland. At an altitude of 100 feet, the aircraft - carrying over 250 U.S. soldiers and civilian crew members - lost power and sank into the ground tail-low, killing everyone on board. Three Canadian witnesses to the crash were interviewed over the Canadian Broadcast Corporation's television news on April 8, 1986 at 10 p.m. No flame or smoke issued from the plane before its descent and crash. However, the aircraft was seen to be mysteriously glowing with a yellow glow. That is a signature of the use of a scalar howitzer in the "continuous EM emergence" mode, similar to the manner in which the F-111s were downed in Vietnam. In short, the DC-8's electrical systems were interfered with by electromagnetic noise created throughout each increment of spacetime occupied by the aircraft. The powerful charge created in and on the aircraft also apparently caused the loss of two engines, one after the other. With its controls ineffective and power drastically reduced, the aircraft sank to earth, still in its "tail down" configuration from takeoff, and crashed and burned. The "yellow glow" was a corona due to the acquisition of a high electrical charge by the skin of the aircraft.

Other factors contributing to the crash may have been reduced lift due to poor engine maintenance, increased weight of the aircraft due to icing, and heavy loading. Still, no one has recognized the significance of the "yellow glow" or what it implies, or the possible connection between loss of the aircraft and previous Soviet testing of-a Launch Phase ABM system against U.S. shuttle launches.

As this book goes to press, the last two U.S. Air Force Titan 34-D missiles fired from Vandenberg Air Force Base in California have blown up shortly after launch. The first one blew up on Aug. 28, 1985 just after lift-off. That loss has been attributed to failure of a high-powered fuel pump, causing a massive oxidizer leak and a smaller fuel leak. The second Titan loss occurred on April 18, 1986 when the missile blew up 5 seconds after lift-off. Its loss is still under investigation and no determination of cause has been made. Apparently the shuttle and the Titan presently provide the only viable launch vehicles for launching U.S. "spy" satellites. The loss of these sensitive satellites - if indeed they constituted the payloads - cannot help but be damaging to our strategic surveillance capability. According to the Los Angeles Times, the single remaining KH-11 satellite was launched in December 1984 and, with an expected life of two to three years, it could stop functioning later this year.

Whether or not significant Woodpecker grid activity existed in the vicinity of the Titan launch of August 1985 is unknown at this time. However, significant activity in the grid definitely occurred before the April 18 Titan disaster and on the same day.

On Easter Sunday, Mar. 30, 1986 engineer Ron Cole observed significant **cloud** signatures of grid pattern activity, correlated with Soviet Woodpecker measurements. On April 18, the present author observed traces of a cloud **radial** over Huntsville, Alabama and took photographs of it. Preliminary reports from

Thousand Oaks, California indicate extensive grid activity again on April 18, the day the second Titan exploded.

At least the second of these two missile destructions shortly after launch is suspicious, since the grid positively was active during that time. Also, a clear trail of Launch Phase A8M system indicators exists back to the massive scalar exercise of April/May 1985. The first Titan explosion in Aug. 1985 thus falls within the Soviets' "now let's test them against U.S. launch vehicles" period. The second Titan loss follows highly suspicious losses of the Arrow DC-8 on Dec -T7 1985 and the Challenger on Jan. 28, 1986. The same Soviet weapon system that destroyed those targets may also have destroyed one or both of the critical Titans.

The Soviets have also been able to significantly engineer the weather over North America for more than a decade without being found out. They have tested a fantastic range of anti-ballistic missile (ABM) defense weapons for over two decades, and no one is the wiser in the West.

As previously stated, prior to the end of November, 1985, at least three "wet-run" tests of a Soviet "launch phase ABM system" against actual U.S. shuttle launches were made directly over Cape Canaveral itself, and still no one recognized what was happening or what sort of weapon was being tested. On December 12, destruction of the Arrow DC-8 in Newfoundland produced no indications that the Americans and Canadians knew anything about the nature of the weapon possibly used.

Accordingly, after a sufficient wait to test our reactions (if any), the Soviets prepared to actually destroy a shuttle after its launch.

Destruction of the Challenger in January 1986

As the whole world knows, on January 28, 1986 the shuttle Challenger was launched from Cape Canaveral, Florida after exposure to undesirable weather conditions, and disastrously exploded shortly after launch. The evidence seems to indicate that, as the rising vehicle was stressed, one end of its right booster broke loose, twisting away and into the main fuel tank, causing rupture, spillage of the fuel and catastrophic explosion. Several other anomalies still exist, however, and it is clear that a problem existed with at least one of the booster scals. All seven astronauts aboard the flight were killed in the fiery destruction of the vehicle.

Of course no one had recognized that the Soviets had already tested a launch-phase anti-ballistic missile (LPABM) system against three of our previous shuttle launches. These "wet-runs" used a deliberate "time offset" to delay the explosive emergence of electromagnetic energy in a launched shuttle's location along its trajectory. The delayed test shots resulted in very large "booms" above the launch site after the shuttle was safely out of the area, but did not destroy the shuttle vehicles themselves. For example, the delayed-shot boom occurred 12 minutes after the evening launch of Nov. 26, 1985. Even a marker beacon (large light in the sky) was utilized on that launch shortly after lift-off. The marker beacon was photographed. In addition, another photograph taken in a time sequence shows another sudden streak of light coming down and ending in a burst of light. This was probably a spatially-offset test of the "pulse" mode for destroying the shuttle. The "light burst" would have been detected in the Soviet Union and scored against its intended offset position. However, another mechanism may have been used to cause destruction of the shuttle itself.

On Jan. 1, 1986 the presence of a metal-softening signal added on to the Soviet LPABM system's scalar EM transmissions was detected by a surprised Frank Golden. The metal-softening ability of the detected signal was experimentally verified by him. Golden also locally nullified the action of the scalar EM signal in a test, rather conclusively establishing (1) that it existed and (2) what it was. The signal was apparently being prepared for use against an upcoming U.S. shuttle launch.

Just prior to the launch of the shuttle in late January, 1986, the Soviets accomplished significant weather engineering over the U.S. The jet stream was severely bent southward in the middle of the U.S., bending rightward again to move across the Florida panhandle. Icy cold air from Canada was drawn far down, into Florida and onto the Challenger sitting on its launch pad. This exposure to cold outside its tested range was probably an additional factor contributing to the Challenger's failure. Positive signatures of the Soviet weather engineering and jet stream manipulation were observed and photographed by several persons, particularly in Alabama and California.

On January 28, 1986, the Soviet scalar EM weapon system effects were sharply localized in the launch zone. Localization involved higher frequencies being present; these are quite painful to small brains - whose hemispheres act as a scalar interferometer and detector - such as in birds. As commented upon by national news commentators, strangely the birds were not flying that morning. Indeed, they were staying down on the ground or avoiding the area, since the sky over the area was painful to them.

As the Challenger rose, the metal-softening signal would have been experienced in and around the boosters shortly after ignition, since the booster flame acts as a special "ion-plasma" turner/detector for the scalar signal. (Certain plasmas have a unique characteristic: they transform an input transverse wave to a longitudinal wave, or an input longitudinal wave to a transverse wave.) The effect of such a local signal is to "change mass in the immediate vicinity" with the particular scalar resonance signal. (Mass acts as a capacitance or accumulator for scalar resonance).

The ill-fated Challenger was doomed. After ignition, the booster flame acted as a ionic plasma detector/amplifier for the scalar metal-softening signal on the

Soviet Woodpecker grid. The metal in and around the booster flame was slowly and steadily weakening due to charge-up with the metal-softening pattern. This attributed to booster leakage from the already cold-damaged seal. The leaking booster poured out smoke and later flame, contributing to the impending disaster.

Substantial winds and air turbulence over the site increased the stress on the Challenger as it rose through this region. This also contributed to the impending disaster and may have been deliberately created there by Soviet weather engineering.

As the Challenger stressed, eventually one or more weakened metal mounts gave way, partially freeing the end of the right booster. The booster oscillated, rotating into the tank and rupturing it. Contact of the escaping liquid fuel and the flame resulted in a fiery explosion, destroying the vehicle.

Even so another anomalous flame or light was observed on the vehicle, and may have represented a very small additional "pulse mode energy form" produced by the Soviet weapon that was attacking the Challenger. The shock of the explosion probably killed the astronauts instantly, although the cabin appears to have remained essentially intact while it plunged several miles to the ocean below.

By treating excess cold exposure to the shuttle, inducing metal-softening in and around the ignited booster, and possible adding a deliberate "intensely hot spot", the Soviets caused the Challenger to weaken and destroy itself shortly after launch, in so subtle a fashion that NASA scientists would not suspect what had actually caused the mishap. The Soviets also had previously withdrawn all their trawlers and ships which normally shadow a shuttle launch, to prevent any suggestion of Soviet presence near or involvement in the catastrophic accident.

A few days later, sporadically intense "high frequency localization signals" were still present on the grid, at least at one hinge-point at Birmingham, Alabama. From 1-4 February 1986, many birds inadvertently flew into the zone when an intense breakout of these components occurred, and dead birds fell from the sky in substantial numbers.

* According to an Urgentgram sent out by General D. Graham, on the evening of the Challenger's loss, KGB headquarters held a party to celebrate "success of their active measure against the shuttle." Note that all Soviet scalar EM weapons - development, testing, deployment, and usage - is under command and control of the KGB.

Among other things, this briefing details the bizarre series of indicators that showed the Soviet intention to destroy the vehicle, and documents the accidental discovery of the signal with which they intended to cause the shuttle to fail and destroy itself.

Technological Surprise and a New Hiroshima

Sadly, the bureaucratic smugness of orthodox Western scientists has materially assisted the Soviet deception process. Most Western managerial scientists - particularly in weapons development activities — have continued to view the Soviets as ignorant peasants, still trying to clean the mud off their boots. This view, of course, is totally untrue and unwarranted.

It takes only a few examples to refute this attitude. In nonlinear mathematics, engineering and science, the Soviets have led their Western counterparts since the beginning. The electromagnetic pulse (EMP) effect of a nuclear explosion appeared in the ordinary Soviet scientific literature before Western scientists were even aware that the effect existed. The Soviets continue to lead the world in explosive welding, titanium forming and welding, etc. While the Soviet scientists exhibit little inclination to build good washing machines, they certainly do produce state-of-the-art technology — and beyond — in any area in which they focus their main efforts. (We do lead the Soviets in some areas such as computers, computer software, miniaturization, etc.)

Once before, a modern nation - the United States - developed a mighty weapon in secrecy and used it to force a powerful foe - Japan — to its knees. The mindbending atomic blows to Hiroshima, and shortly after to Nagasaki, showed once and for all that in the modern age technological surprise can prove instantly disastrous. Yet in our scientific arrogance, we have assumed that no one else will ever do such a thing. We have assumed that it certainly could never happen to us, and that the "secret weapon" scenario will never be repeated. On the contrary, it has happened again, someone else has done it, and it has happened to us.

It has also become fashionable in the West to believe that all the laws of physics are already discovered. We assume we already know all of them. While we have been pridefully crowing this tune, the Soviets have been steadily discovering new laws in secret, as well as new ways to circumvent the old laws.

We Have Given Up Defense in the Larger Sense

Meanwhile, to defend ourselves strategically, we have chosen to forego "defense" and rely almost totally on building a powerful strategic offense that is capable (we think!) of destroying our would-be enemies anywhere in the world. Our offensive striking power is based mostly on a triad of deterrent forces - land-based ballistic missiles, submarine-launched ballistic missiles, and strategic bombers. The cruise missile is presently being added to the triad. If this 4-part offense were nullified or destroyed by Soviet secret weapons, we would be powerless to prevent our own destruction and Soviet domination of the world.

We have been viewing ourselves as Samson, confident in the strength of our locks.

Yet literally our locks have been secretly shorn and the Philistines are already upon us. Indeed, Soviet energetics weapons are now capable of destroying our triad shield, our homeland, our armed forces in the field, and our population, quickly and efficiently. We have a new "gap" of monumental proportions: not a missile gap, not a submarine or bomber gap, and not even a particle beam or laser gap. We have a scalar electromagnetics or electrogravitation gap.

In this briefing, it is my purpose to show a portion of the Soviet weapons developments that have lead me to such dire conclusions. The Fer-de-Lance briefing is also an attempt to galvanize our leaders and scientists into action, for our present total vulnerability to the Soviet Fer-de-Lance weapons is intolerable and unacceptable.

Unless we achieve defenses — and quickly — our own demise in a fashion similar to the Hiroshima-Nagasaki scenario is inevitable and imminent.



CHARACTERIZATION

- SINGLE ANALYST
- PERSONAL INTERPRETATION
- UNOFFICIAL
- NO APPROVAL/DISAPPROVAL BY ANY
  - ¤ CORPORATION
  - ¤ GOVERNMENT AGENCY
- PREPARED
  - ¤ ON OFF-DUTY TIME
  - ¤ AT PERSONAL EXPENSE

Slide 001: Characterization

We point out at the beginning that this briefing and its interpretation are the result of 22 years of analysis and effort by a single analyst. It is entirely unofficial. It is not approved or disapproved by any corporation, company, or government agency. It has been prepared by this analyst at nights, on weekends, on holidays, and during off-duty time.

It has been prepared mostly at personal expense, though several grants and support have been received from R. J. Reynolds III, Peter Kelly, Mike Bearden, Interdimensional Sciences, Association of Distinguished American Scientists, and others. Very valuable assistance has been received from the U.S. Psychotronics Association and the Planetary Association for Clean Energy. These contributions are deeply appreciated and most gratefully acknowledged.

Graphics and artwork support by Hal Crawford, Margaret Wilson, Tommy Neumann, Ron Cole, and Lee Giles has been invaluable. My sincere thanks go to these artists who have made the presentation vivid and imaginative. A great deal of background support was given by Joe Gambill, Frank Golden, Tom Herold, Ken Moore, Pete Kelly, Eike Mueller and Mel Bartlett and is deeply appreciated.

Finally, the help of many other persons and colleagues too numerous to enumerate is also gratefully acknowledged.

If the U.S. bureaucracy ever moves and develops defenses against scalar EM weapons, it will largely be due to the support of the persons and organizations who have freely given of their talents and resources to further this effort.



OUTLINE

- THREE VIEWS OF ELECTROMAGNETICS
- EXTENDED AHARONOV-BOHM EFFECT
- SCALAR ELECTROMAGENTICS
- KILL/DAMAGE MECHANISMS
- VULNERABILITY
    - ¤ ELECTRONICS
    - ¤ PERSONNEL
    - ¤ EQUIPMENT
    - ¤ MATERIAL
- SUMMARY

Slide 002: Outline

This presentation does not attempt to cover the complete field of energetics weapons developed by the Soviet Union. Instead, it concentrates on the major areas necessary to understand the type of weapons likely to be unleashed on our strategic and tactical installations and our troops and their equipment. It does not attempt to present the frightful bio-electromagnetic weapons the Soviets have developed to be unleashed on our populace at large and on our troops in the field. Also, the briefing does not dwell on the historical progression, but on the types of weapons themselves.

Of necessity, it presents several shortcomings in classical EM, and presents three differing views of electromagnetics and what can be done with them. The briefing particularly stresses the Aharanov-Bohm (AB) effect. This mesoscopic effect, which produces action at a distance by pure EM flux and not EM force fields, has been extended by the Soviet weapons developers into the macroscopic world around us.

In addition, we develop the basic concepts of scalar electromagnetics and how electrogravitation is achieved. The basic concepts of scalar interferometry and scalar resonance are briefly advanced, and a few of the major kill and damage mechanisms are presented. The nearly total vulnerability of our present electronic equipment, personnel, communications, vehicles, aircraft, ships, missiles, submarines, nuclear weapons, and materiel is stressed.

Finally, a short summary is given to highlight the main points of the briefing.



ELEMENTS OF THE EMERGING THEORY

- FLAWS IN VECTOR THEORY
- ZERO-VECTOR SYSTEM
- KALUZA-KLEIN ASPECTS
- VACUUM/MASS EFFECTS
- SCALAR RESONANCE
- ELECTROGRAVITATION
- LOCAL GENERAL RELATIVITY
- IMPLICATIONS

Slide 003: Elements of the Emerging Theory

Specifically, we will point out some flaws in vector mathematics itself, particularly with the concept of the zero force vector. The zero force vector is a system of forces that sum to a zero resultant. Hence the components of the summation represent a patterned stress in the medium to which they are applied, or in which they are imbedded. This includes the vacuum (spacetime) medium. In classical electromagnetics, this vacuum stress due to a zero-vector summation of EM force fields has been totally omitted and ignored.

As such, the EM "zero" force-vector summation produces a "trapped internal EM flux and flux pattern, without resultant (external) force field" condition - precisely as does the Aharonov-Bohm effect. The components of the artificially zeroed system, however, can be transmitted and still maintain their special relationship and coherence. While the AB effect has been shown to hold for the mesoscale (a few thousands of angstroms), the zero-vector scalar EM effect can hold for hundreds of thousands of kilometers.

To provide a unified electrogravitation, we adapt Kaluza-Klein 5-dimensional gravitational concepts to the idea of the zero-vector stress system in vacuum-spacetime. We also point out how simultaneously varying the magnitudes of **the** force components of a stress, all in phase, produces a stress wave or scalar EM wave. Scalar waves are almost always absorbed and emitted by the nucleus of the atom, not by the electrons in orbit.

The relationship of mass and vacuum, and the constitution of the vacuum, are pointed out from the viewpoint of modern quantum mechanics.

How a scalar wave resonance differs from conventional EM resonance is developed briefly. Mass and inertia are the direct result of - and are - trapped scalar resonance. The trapping mechanism is the spin of the particle.

Severely limiting assumptions in ordinary general relativity (OGR) are pointed out. In OGR, it is assumed that the local frame is always a Lorentz frame, and never curved. In other words, local spacetime is always assumed to be flat. This **saves** the conservation laws, simplifies relativity, and reduces "general" relativity to special relativity with distant perturbations and curvatures.

By removing this ad hoc assumption, a much richer local general relativity results. This local general relativity is readily engineered. Note that, in OGR, the physicist has actually assumed that he can never "engineer" local general relativity! Indeed, with the scalar EM approach, he can easily do so, in contradiction to what is taught in all Western universities.

By engineering a local general relativity (LGR), the individual conservation laws can be violated locally. This includes the conservation of energy/momentum, and the conservation of charge, for example.

The major implication of this startling new engineering physics is that one can **engineer** physical reality itself. For example, elements can be transmuted with minuscule energy input, free energy devices are possible, action at a distance is possible, communication faster than light speed is possible, etc.

By using the zero-vector approach, the virtual state can be organized and made **largely** deterministic, rather than statistical. This means that the probabilities of the states propagated forward by the Schroedinger equation can be engineered and changed. Whether or not a certain quantum change shall emerge or not can be determined or substantially influenced in advance. Bohm's hidden variable **theory** now becomes directly engineerable. This is a drastic change to quantum mechanics and physics in general.

Another implication is that this is the final engineering, for it allows the direct engineering of physical reality itself. Humans must now find a way to resolve their differences peacefully, or shortly Man will destroy himself and his biosphere by his own hand.



3 KINDS OF ELECTROMAGNETICS

- CLASSICAL
  - POTENTIALS JUST MATHEMATICAL CONVENIENCES
  - ACTIONS CAUSED BY NONZERO FORCE FIELDS
  - NO ACTION WHEN FORCE FIELDS ZERO
- QUANTUM MECHANICS
  - POTENTIALS REAL
  - STATISTICAL SUBSTRUCTURE
  - FORCE FIELDS BY DIFFERENTIATIONS
  - ACTION WHEN FORCE FIELDS ZERO
- ARTIFICIAL POTENTIALS (ELECTRO-GRAVITATION)
  - POTENTIALS REAL
  - FORCE FIELDS EXTERNALLY ZEROED, INTERNALLY ACTIVE
  - ZEROS INDIVIDUALLY DIFFER
  - SCALAR INTERFEROMETRY
  - SCALAR RESONANCE

Slide 004: Three Kinds of Electromagnetics

There are actually three kinds - or three views - of EM. These are (1) the classical view, (2) the quantum mechanical view, and (3) the scalar EM or electrogravitational view.

In the classical view, the potentials are just mathematical conveniences and do not physically exist. The real causative agents are the force fields, and there is no longer any electromagnetics going on if the force fields reduce to zero. Further, the ideas of "charge" and "charged mass" have been made erroneously synonymous.

Of course the classical view was formed from the idea of a thin material ether, with electricity as a thin fluid, long before the discovery of the electron. Since most earlier scientists studied string waves and these are transverse, the EM wave was modeled as a transverse wave. Also, detection equipment actually detected transverse waves. The role of electron spin and drift velocity, which would have shown that force-field-causing EM waves in the vacuum could only be longitudinal, was not yet discovered. Maxwell's equations and the classical approach became so engrained that the basic derivations were never corrected for more modern discoveries.

The quantum mechanical view, on the other hand, regards the potentials as the real physical actants, and the force fields are just effects derived from the potentials by differentiating operators. Classically oriented physicists have adamantly opposed this foundations requirement of QM because it would require nearly a complete redo of EM theory. It would also rather drastically change our ideas of physical reality. For years a controversy has raged around the Aharonov-Bohm effect (which demonstrates the reality of the potentials, among other things). Only this year - 1986 - have most physicists finally accepted the AB effect with its implications (see Physics Today, Jan. 86). However, no changes have yet been made to EM theory and the basic classical approach to electrical physics and engineering.

Yet even the QM view is flawed, since it has not examined the structure of EM forces which sum to a vector zero. Such a system produces stress, and if the summation is in the vacuum itself, it produces stress of vacuum/spacetime. Rigorously, this is a gravitational effect, and the energies of the various EM components in the local region are locked into an artificial potential. From general relativity, this type of potential where the energy density of vacuum is altered is a gravitational potential. From Kaluza-Klein unified theory, it is at least a 5-dimensional gravitational potential.

If the individual force vector components of the vector zero are varying in magnitude - say, all in phase - then they produce a gravitational wave. The energy density of the local vacuum is being rhythmically varied. Call such an EM wave a scalar EM wave, where, by "scalar" we imply that, to an external observer, the EM force vector resultants are identically zero, but the local gravitational potential of the wave is varying. Thus this is an electrogravitational wave, and vector zeroing of EM force fields constitutes a means of changing EM field energy into G-field energy. On the other hand, by breaking up the coherence of the zero-vector summation of the EM forces, nonzero EM resultants are recovered, constituting the change of gravitational energy into EM energy.

A simple means to break zero-summed coherence is by interference of two or more such zero-vector waves.

In this, third view of EM, action at a distance is easily possible, and is the norm rather than the exception. In addition, a new kind of resonance - scalar resonance - exists. The scalar EM wave does not interact with orbital electrons, but rather with the interior of the nuclei of atoms. Thus the new scalar EM resonance is between nuclei and within nuclei.



BOHM-AHARONOV EFFECT

- IN FIELD-FREE REGIONS
  - ¤ E-FIELD IS ZERO
  - ¤ B-FIELD IS ZERO
- POTENTIALS STILL EXIST
  - ¤ CAUSE REAL EFFECTS
  - ¤ INTERFERENCE IS KEY
  - ¤ CONTAIN SUM-ZEROED SUBSTRUCTURE
- DOES NOT FOLLOW FROM
  - ¤ MECHANICS
  - ¤ CLASSICAL ELECTROMAGNETICS
- REQUIRED BY QUANTUM ELECTRODYNAMICS

Slide 005: Bohm-Aharonov Effect

In 1959, Aharonov and Bohm published a fundamental paper in Physical Review, which pointed out the QM implications of potentials as the real entities, while force fields were derived effects. They showed that, even in the presence of zero EM force fields, the potentials may still exist and produce real effects in physical systems. They also suggested experiments to prove these predictions.

Interference of the potentials is the key mechanism producing real effects in charged particle systems, even in the presence of zero E-field and zero B-field. Unfortunately the AB paper did not address the issue of zero-summed systems of EM force fields as one way of producing artificial potentials having unique characteristics

At any rate, the "AB effect," as it came to be called, was rather hotly resisted and debated over the years, until finally it has generally been accepted as proven in 1986. The principle represents a violation of both classical mechanics and classical electromagnetics. It is required, however, by quantum mechanics and quantum electrodynamics. And experiment has proved it.

(See Y. Aharonov and D. Bohm, "Significance of Electromagnetic Potentials in the Quantum Theory," Physical Review, Second Series, 115(3), Aug. 1, 1959, p 485-491.).



A-FIELD IS REAL

A – FIELD CAN INFLUENCE THE MOTION OF ELECTRONS'.

MAGNETIC FIELD AND VECTOR POTENTIAL OF A LONG SOLENOID.

THE FEYNMAN LECTURES ON PHYSICS, VOLUME II

Slide 006: A-Field is Real

In classical EM, the vector magnetic potential (the A-field) had been defined as a mathematical convenience by the equation

$$\nabla \times A = B \qquad [1]$$

But if the potentials are real, then conceivably the A field can be loosed from its enchainment to the $\nabla \times$ operator. In that case, it becomes a free, new, and independent field of nature with potentially unique characteristics. For example, its defining equation shows that magnetic force field can be made from it, and the rightmost term of the equation

$$E = -\nabla \emptyset - dA/dt \; [2]$$

shows that its time rate of change makes an electric field.

Let us explain this in more simple terms, and somewhat more precisely than conventional theory. We will use the Kaluza unified G-EM interpretation and electron flow in our explanation.

In the A-field, we have a certain kind of 5-dimensional G-potential which can bleed-off as EM force fields in two ways: (1) in a swirl fashion, where the vortex producing the swirl moves parallel to electron movement, and the swirling is a torque or spin, and (2) in a linear fashion, where the time rate of change of the A-potential produces a linear E-field on the electrons.

The first bleed-off as given by equation [1] constitutes the magnetic B-field, and the second bleed-off as given by the rightmost term of equation [2] creates a component of the overall electrical E-field. (Bleed-off of the electrostatic scalar potential produces the other component of the E-field).

Now in general relativity (GR) theory, "the" G-potential is just a conglomerate of many things, each of which has the characteristic of curving spacetime. "The" gravitational field is not a single thing at all, but is composed of a collection of many things.

Thus if we realize that both the electrostatic scalar potential (Ø-field) and the magnetic vector potential (A-field) are components of the 5-d G-potential, then we see immediately that bleed-off of these two components of the 5-d G-potential creates all normal EM force fields.

It follows that, if we produce a zero-vector summation of the two or more EM bleed-offs, we are actually "putting as much back in" to the 5-d G-potential through its A and Ø components as we are taking out electromagnetically. In that case, the 5-potential is in a state of equilibrium with respect to EM bleed-off. It is now forced to bleed-off in the only other way it can: as ordinary 4-dimensional gravitational field. Thus by vector-zeroing EM force fields, we turn EM field energy into G-field energy and vice versa, via the intermediary of the 5-potential.

At any rate, soon after publication of the Aharonov-Bohm paper, experiments showed that, if the magnetic field is trapped inside a long solenoid, a phase shift still is induced in the two-slit electron experiment, even though - classically - no contact of the enclosed magnetic field and the moving electrons occurs. This phase shift is explained by the fact that the freed A-field exists outside the trapping solenoid, even though the B-field does not. Consequently, interaction of this free A-field with the electrons produces a phase shift of the QM interference detection pattern.

This proves that A-field is real and causes physical effects.

It also proves that a form of action at a distance is real, just as required by quantum mechanics.

Years ago, Frank Golden and this author - together with Dr. William Tiller - experimented with "free A-field" devices. Golden went on to develop prototype transmitters and receivers and a prototype underwater communication system.

Since that time, Gelinas has patented several curl-free magnetic vector **potential** (free A-field) devices: see U.S. patent no. 4,447,779, May 8, 1984; 4,429,288. Jan. 31, 1984; 4,429,280, Jan. 31, 1984; and 4,432,098, Feb. 14, 1984. These patents are assigned to Honeywell.

(See also Theodor Kaluza, Sitz. Berlin Preuss, Adad. Wiss. 966, 1921.).



QUANTUM NON-LOCALITY

"The non-local aspect of quantum systems is ... a general property of nature, and not just a freak situation manufactured in the laboratory."

PAUL DAVIES, SUPERFORCE
1984 (PAGE 48)

Slide 007: Quantum Non-Locality

Indeed, quantum systems exhibit nonlocal effects that are general properties of nature. These effects are not just freak situations manufactured in subtle laboratory experiments.

However, if spatial coherence in such microscopic effects can be induced and sustained, then action-at-a-distance can be obtained in large macroscopic systems. This is the engineering aspect of the scalar EM approach.

It is also the aspect that the Soviets have secretly weaponized for over three decades.

The zero-vector EM force-field summation of multiple EM waves is used to transport specific time-phased patterns of EM polarization of vacuum to a distance. There interference of two or more such patterns results in the interference of the internal patterns, breaking of the phase relations, and appearance of positive (added) or negative (extracted) EM energy in the intersection region.



VECTOR MATHEMATICS HAS A FUNDAMENTAL PROBLEM

IN ITS AXIOM FOR THE ZERO VECTOR,
VECTOR ANALYSIS DISCARDS ZERO VECTOR
SUMMATIONS OF ACTIVE SYSTEMS
OF VECTORS.

VECTOR ZERO IS MADE THE ABSENCE
OF ALL VECTORS

(IT CAN ALSO BE THE PRESENCE OF REAL
VECTORS WHOSE VECTOR SUM IS 0ī.)

Slide 008: Vector Mathematics has a Fundamental Problem

In its concept of the zero vector, vector mathematics discards zero-vector summations of active systems of vectors. It replaces such a summation with a zero vector. This is fine for mathematics as an abstract system, but it is in error when applied to real electromagnetic force fields of nature.

In the abstract mathematics, a vector zero summation is made the "absence of all finite vectors". Further, all vector zeros are made equal. No concept of the "internal stress" of the zero vector exists in abstract vector mathematics.

However, physically the zero summation or "balancing" of vector forces in a medium represents stress in that medium. In the physical case, a vector zero summation system of non-zero vectors has a dynamic substructure, and this substructure is an individual.

Obviously, in the physical case vector zero summations may materially differ, both in the pattern of stress and the magnitude of stress. They cannot all be equated. Further, they are not the absence of vectors, but represent the presence of vectors in a special manner. Such a zero summation of EM vector forces directly stresses the "medium" - which may be the vacuum itself.

In the physical case, several changes to the axioms of abstract vector mathematics are required. (1) the "potential" of a vector zero must be taken into account, such as is represented by the sum of the squares of the magnitudes of its vector components. (2) the specific deterministic pattern of the vector components comprising the zero must be taken into account. (3) The dynamic variation in both the deterministic directions and deterministic magnitudes of the components and of the overall pattern must be taken into account. (4) Frequencies of the changes in the direction, magnitude, and actual makeup of the vector zero must now be accounted for. That is, *time* and *wavelengths* are rigorously aspects of the vector zero, and these may be deterministic variables. Since time itself is now a variable aspect of the vector, the vector zero system can affect its "rate of time flow" in the observer's system. (5) Since a "reference vector zero" can be established at any point of a vector magnitude, then individual vectors themselves may have dynamic substructures inside a special "zero reference" in and on the vector. The patterned potential of a vector is a reality.

This leads to a system of "vectors nested inside vectors" ad infinitum. In other words, it leads to an infinite-dimensional system, and the "opening" of every finite closed vector system *through its vector zeroes.*

For application to physical electrogravitational systems, at least 5 dimensions are required, four of space and one of time.

Here we still are considering only a special case where all vector zero summations represent EM force field energy locked in a gravitational potential, or gravitational force field energy locked inside the EM potentials. That is, we are prescribing a system where the only *intertranslation* of energy is among mass, EM field, gravitational field, and vacuum virtual energy (anenergy).

(See T. E. Bearden *Toward a New Electromagnetics: Part III: Clarifying the Vector Concept*, Cheniere Press, Santa Barbara, Ca. www.cheniere.org, 1983; Part 4: *Vectors and Mechanisms Clarified*, 1983. See also E. T. Whittaker, *Proc. Lond. Math. Soc.* 1, 367, 1903; Robert Bruce Lindsay and Henry Margenau, *Foundations of Physics*, Dover, New York, 1963, p. 283-287; Richard P. Feynman et al, *The Feynman Lectures on Physics*, Addison-Wesley, New York, **Vol.** I, p.2-4.).



THE ZERO-VECTOR AXIOM

- "THERE IS A UNIQUE VECTOR, $\bar{O}$, IN V (THE VECTOR SPACE) SUCH THAT

$$\bar{V} + \bar{O} = \bar{O} + \bar{V}"$$

$$O_i = O_j$$

- THIS MAKES ALL O_i EQUAL BY ASSUMPTION, SINCE THERE IS ASSUMED TO BE ONLY A SINGLE TYPE O WITHOUT REAL COMPONENTS

Slide 009: The Zero-Vector Axiom

This slide shows a standard mathematical statement of the zero-vector axiom, used in many texts.

As can be seen, all zero-vectors are made identical, and no substructure is considered.

Such an abstract system of vector mathematics does not fit physical reality. However, when all one's EM foundations concepts are strongly conditioned in this fashion, the gravitational aspects of EM are discarded.

Further, EM theory, experiments, and equipments will be developed along these limiting lines. In that case, EM engineering of gravitational effects will not be developed. One will assume that it is impossible to have a locally curved spacetime, and hence all local frames will be Lorentz frames. Therefore the conservation laws will rigorously apply.

Further, the nonlocal quantum effects will stay firmly in the microscopic world where they belong. Physical macro-reality will stay stable and predictable in a classical manner.

General relativity (in curved spacetimes) will be restricted to the special case of the local special relativistic (uncurved) spacetime, with only distant perturbations (spacetime curvatures).

The world will stay sane and "normal", and the totally variable insanity of physical reality will remain bottled up in the minute microworld or the distant maelstrom of suns, stars, black holes, etc.

The Aharonov-Bohm heresy will stay kaput in the real world and will not be unleashed beyond mesoscopic reality — a few thousand angstroms or so.

With such an error in the application of vector mathematics to physical science, we become "flatland physicists," so to speak. We become like skimmer bugs on the surface of a pond; we have no appreciation of the dynamics of the depths below or of the heavens above.

Worse, we condition our development of instruments according to the fixed notions in our heads. Then we use these "biased" instruments to do experiments that reaffirm our notions. Any deviation suggested to this is considered heresy and nonsense.

And as Max Planck once pointed out, you will get a new physics only when the old physicists — who so adamantly oppose it — die off.



ARE THESE SYSTEMS EQUAL?

Slide 010: Are These Systems Equal?

Shown here are some representations of various very simple zero-vector systems. As can be seen, the stress magnitudes and the spin and dynamics of all of these systems are very different.

Further, their "stress potential" substructures are not composed of a huge collection of little random force vectors. Instead, their substructures are deterministic. If the components being put into the zeros are varied in direction and magnitude, but always sum to a zero resultant, then highly complex substructure dynamics may be created and utilized, infolded (Bohm's term) inside the zero vector.

In theory one can establish "channels" of communication and power (magnitude) transmission without ever surfacing a nonzero EM force field. In practice one can do this with very little EM spillout. Thus one can establish electrogravitational channels and energy transmission inside normal EM potentials and/or ordinary EM carrier waves.

One can use a conventional system of EM potentials, force fields, and waves as a special kind of "wiring circuit" in and through which to transmit and produce electrogravitational effects. By distant interference, EM effects at a great distance can be accomplished, yet no "ordinary EM energy" has passed between the transmitters and the distant interference zone.


INFOLDED SYSTEMS ARE EXCLUDED BY PHYSICS

DYNAMIC ZERO-VECTOR SYSTEMS ARE NOT CONSIDERED IN ORDINARY GENERAL RELATIVITY, CLASSICAL ELECTROMAGNETICS, OR QUANTUM MECHANICS.

Slide 011: Infolded Systems are Excluded by Physics

Unfortunately, these infolded dynamic zero-vector systems have been eliminated from physics.

They are omitted in classical EM, ordinary general relativity (OGR), and qu**antum** mechanics.

That is, they have been omitted in Western physics.

They have not been omitted in secret Soviet weapons labs and weapons development programs.



KALUZA GEOMETRY

- THEORDOR KALUZA, POLISH PHYSICIST
- UNIFIED THEORY OF ELECTROMAGNETICS AND GRAVITY (1921)
  - 5- DIMENSIONAL SPACETIME
  - 5-DIMENSIONAL GRAVITY FIELD
  - ELECTROMAGNETISM IS THAT PART THAT *OPERATES IN THE FIFTH DIMENSION*

Slide 012: Kaluza Geometry

In 1921, Theordor Kaluza, a Polish physicist, published a unified theory of electromagnetics and gravitation. Albert Einstein, who had had the paper for two years, recommended his paper for publication. In that theory, five dimensions - four space and one time - are utilized in the basic model. This gives a 5-dimensional spacetime.

In the model, electromagnetics and ordinary gravity are two aspects of a single more fundamental field: the 5-space gravity field. Electromagnetism is that part of the 5-field that operates (bleeds-off) in the fifth dimension.

The ordinary 4-space G-field is the small residue that spills over into our ordinary 4-space, and doesn't slide around into the fifth dimension and bleed-off there as electromagnetics.

Implicit in the theory, but not explicitly stated, is the fact that the 5-space G-potential bleeds-off in two fashions: (1) in the 5th dimension nearly unopposed, to produce what we see as EM force fields, and (2) in the ordinary 4-space we live in, which we see as ordinary gravitational field.

Normally almost all the force field bleed-off is in the fifth dimension as EM; only a minuscule bit bleeds off as 4-gravity.

Just as one example, between two electrons the 5-space G-potential bleeds-off into electric force field about 10^{42} times as much as it bleeds-off into 4-space G-field.



A POTENTIAL IS A CHANGE IN THE STRESS OF VACUUM

Slide 013: A Potential is a Change in the Stress of Vacuum

In physics, the idea of a "potential" is very poorly defined, if at all. The normal "definition" for the electrostatic scalar potential, for example, is not a definition at all. Instead, it's an abstract operation that tells how to mathematically calculate the magnitude of the potential, by pushing a unit charge in from infinity, against the potential field.

Now ultimately a definition must be an identity statement, not an operational statement about something.

Since I could find hardly anyone who actually understood what a potential was, and how or of what it was composed, I simply took quantum mechanics at face value and constructed this model.

First, the modern view of the vacuum is that it is not an emptiness, but a plenum. It's teeming with an incredible amount of raw energy, existing totally as the temporary bits of energy of virtual particles. That is, the vacuum "energy" exists as the nonintegrated energies of little particles which appear from nothing fare spontaneously created) and disappear into nothing (are spontaneously annihilated) almost instantly. This happens so fast that the little particle and its energy cannot individually be detected; it doesn't hang around long enough.

Hence the fleeting little booger is called a "virtual" particle. Like, "We had 'im there man, for just a moment, but he was gone before we could grab 'im!"

This kind of ghostly particle, however, is very real in modern physics. All observable forces are theorized to be due to the integration or collection of a large number of virtual forces created by exchange of these little particles.

However, this implies a peculiar thing about the vacuum "energy." Actually it's vacuum energies, for each little bit of energy only exists momentarily, then returns to the nothingness from which it came. That is, vacuum virtual energies are totally unintegrated. Each "bit" of virtual energy exists individually. These virtual energies cannot be "added up" to compute the "available energy" unless some collector or integrating mechanism puts them together.

That is, unless some kind of "zipper" is there to "zip them together" into macroscopic, observable energy. The usual "zipper" is a spinning, observable particle of mass. We say that the vacuum energy is unzipped and hence unobservable in that state. We say that "observable energy" is just zipped-together vacuum energies - integrated by and on a spinning, observable particle of mass.

So the vacuum can be visualized as a special sort of violent, unzipped plasma, where the particles of the plasma are fleeting and do not last. We can speak of it also as a sort of special unzipped gas, in the same manner.

The "pressure" of the vacuum gas we refer to as "stress." Due to its violent boiling activity, the vacuum gas is always under very high stress.

This "stressed virtual plasma" identically IS the vacuum and identically IS spacetime. Length, time, frame, mass, etc. - all arise by zipping operations (or understood zipping operations) in and of this raw vacuum/spacetime. When one uses the vacuum notion in this manner, one now uses the term "ether" again. However, this is not the old "thin material ether that hangs around"; this is an entirely new kind. It's a virtual flux and a virtual plasma.

The ether is also what we call "spacetime" in relativity. As can be seen, spacetime is stressed. Further, spacetime has a substructure.

By an uncurved spacetime, we mean one in which the stress of these virtual particles (the "pressure in the ethereal gas," so to speak) is constant from one place to another and from one time to another. Indeed, we also should mean that the stresses of the individual components of the entire plasma are constant from one place to another and from one time to another.

By definition, when we determine the lengths between every two points, we determine a frame. (Actually, we have prescribed a universal "length zipping" operation/mechanism as well as its characteristics.). A "linear frame" or "Lorentz frame" is one in which the pressure or stress remains constant. It may be higher than ambient vacuum, however, due to a particle's or an object's motion through the observer's ether. In the case of constant velocity, the particle/object encounters a higher level of virtual particle flux in the observer's ether, like a vehicle moving through raindrops. It encounters a constant rate of flux, however. In such constant velocity case, the moving object's frame is said to be "rotated," but not curved, with respect to the laboratory frame of the observer.

In a "curved" spacetime, we mean one in which the stress of vacuum increases or decreases from one place to another, or from one time to another, or both. At one fixed location, if spacetime is curved, then the stress is increasing or decreasing as a function of time. That is, the flux density of that area is changing. We may visualize the local frame as undergoing angular acceleration, rotating more or rotating less. This is a non-Lorentz frame, or curved spacetime. It is also a nonlinear vacuum.

In such a vacuum, local gradients exist in the flux of virtual particles. If affected by (coupled to) one or more of these gradients by a nonzero coefficient, a local object experiences effects (forces and actions) "without observable cause." Observably, conservation laws may be locally violated by these "virtual rivers" of vacuum by coupling, just as a paddlewheel dipped in a river violates its own local "conservation of energy" due to the river providing an energy source to it.

One must be very careful with the "pressure" analogy, however, when one utilizes unified theory (Kaluza theory). We now have a virtual plasma vacuum in five dimensions, not four. But the basic notions to enable our visualization and understanding still apply.



TYPE OF POTENTIAL DEPENDS ON THE PARTICLE(S)

Slide 014: Type of Potential Depends on the Particle(s)

Now one can see that, by choosing the type or class of virtual particle, and looking at its potential or stress in the vacuum, one can have many kinds of "potentials" existing in the overall "gravitational potential" of vacuum spacetime.

For example, the stress of the virtual photon flux (which is what causes electrical charge) is called "electrostatic scalar potential."*

We can choose any other class of virtual particle we wish, and there exists a potential (and "change") for it. There are quark potentials, neutrinic potentials, etc.

Indeed, one of the reasons for ignoring Kaluza unified theory for so long was that it predicts a great many types of potentials and fields which have never been observed and which are unknown. Approximations, which neglected all these mysterious, and unknown fields, gave erroneous results. Perplexed physicists, seeking to simplify matters, simply turned away from it in frustration. They returned to it in the mid-70's when it appeared that 11-dimensional Kaluza-Klein theory possibly offered a complete unified theory.

Actually, the diversity of new fields in Kaluza theory was its strength not its weakness. That they are presently unobservable and undetectable is beside **the** point. Neither is time directly observable; however, we have worked out handy procedures and measurements of spatial quantities, which allow us to infer **time.** We have not just tried to drop it from physics!

And indeed the Kaluza theory is consistent with experiment when the higher fields are included. The message is, we must work out "clocks" for these new potentials and fields, so that they can be inferred with at least some degree of precision

- The character of movement also determines the type of potential. The longitudinal (radial) movement of the virtual photon flux is implied in electrostatic scalar potential. The swirl (tangential) component of this flux might be taken as the magnetostatic scalar potential - a magnetic pole - when the cw and ccw components of the swirl balance, but the sum of their absolute values differs from the sum of the absolute values of the corresponding tangential components in the swirl flux of the local ambient vacuum. If this swirl stress is higher than the vacuum swirl stress, this constitutes a north magnetic pole. If lower, it constitutes a south magnetic pole. If there is a prevalence of direction (cw or ccw) in the swirl (i.e., one component exceeds the other), this corresponds to the magnetic vector potential (the A-field) when the A-field is freed from the magnetic force field (B-field) — i.e., when A-field is freed from its ∇x operator in the equation $\nabla\text{x}A = B$. The bleed-off of the excess swirl stress from the north magnetic pole to the deficient swirl stress of the south magnetic pole constitutes the magnetic force field, B — usually referred to simply as the "magnetic field."


A POTENTIAL EXTENDS TO INFINITY & INVOLVES THE ENTIRE UNIVERSE

Slide 015: A Potential Extends to Infinity & Involves the Entire Universe

As shown on this slide, the change in the stress of vacuum due to a potential tapers off to infinity. Its magnitude normally does not reduce to zero until infinity.

Some types of potentials reduce much faster or slower than others, however, and so - at some distance away from a common origin of the potentials, one or more may be neglected in its (their) overall effects on an experiment or system.

Also, the speed of propagation of potential is highly dependent upon (1) what type of virtual particle or particles produce its stress, (2) its magnitude, (3) its composition, and (4) the presence or absence of coupling objects and other interacting potentials.

Fundamental observable particles are like little spray pumps and little vacuum cleaners at the same time.

Each is emitting virtual particles into the vacuum in a spray or flux, and at the same time it is absorbing virtual particles from the vacuum spray or flux. It's a little dynamo, and nature furnishes its driving energy unceasingly.

However, each little virtual particle it emits is itself such a little simultaneous pump and vacuum cleaner. That is, it's also emitting an even finer (and faster) flux of smaller virtual particles, and at the same time it's also absorbing flux al this time finer level.

"Bigger fleas have smaller fleas to bite em;

And so on ad infinitum".

We may consider the vacuum to be made of an infinite number of virtual state layers or levels.

It is not too difficult to show that each of these successively deeper, nested "layers" of virtual state corresponds to a successively higher dimension being added to our 4-space basic spacetime. So hyperdimensions and deeper levels of virtual state are one and the same thing.

The basic "speed" of the first layer is c, the speed of light.

The basic "speed" of the second layer is c^2.

And so on.

This is interesting. We may directly engineer the virtual state by means of the vector zero (scalar electromagnetics) approach. By nesting vector zeros inside other vector zeros, we may directly engineer the deeper layers of virtual state, and consequently hyperdimensions.

Scalar electromagnetics thus is virtual state engineering and hyperspatial engineering at one and the same time.

Superluminal communications systems, hyperspace drive, and materialization and dematerialization are all hypothetically possible, using scalar electromagnetics. As the technology develops, we should see the development of many of the systems long thought impossible except in science fiction.



Slide 016: A Natural Potential

There are two broad categories of EM potentials, depending upon the way in which they are formed.

The two categories of potential formation are: (1) natural, and (2) artificial.

The difference is in the virtual particle flux substructure that comprises the potential.

If the substructure of emerging and vanishing virtual particles is random and without deliberate order (polarization) except in one broad, overall sense, then that is a natural potential. As such, there is no deterministic functioning going on inside the substructure of the potential itself. The potential can only act "as a whole" on a charged particle system.

Natural potentials have substructures of random virtual vector components. Any small amount of coherence as a function of distance vanishes quickly (on the order of a few thousand angstroms at most, according to present Aharonov-Bohm experiments).



Slide 017: An Artificial Potential

An artificial potential by definition has a substructure composed of deterministic observable vector components, summed to an overall zero vector. Coherence as a function of distance can be maintained over enormous macroscopic distances - even hundreds of thousand of kilometers - by simultaneous transmission of the entire cluster of substructure components as a coherent "zero" group.

To the conventional linear EM detector, at any point along its transmission path, this substructure is detected as a zero-E vector and a zero-H vector. Hence the conventional detector does not see the artificial potential, even if its "stress magnitude" (a function of the magnitudes of all summed components) changes.

Action at a great distance is possible with this artificial potential, however, if a highly nonlinear situation is met so that the phasing of the components is broken or significantly altered. In that case, the components do not sum to zero after their dephasing, and real EM force fields emerge. This "dephasing" can be made to occur at the distant nonlinearity.

Action at a great distance is not possible with the natural potential, but is possible with the artificial potential.

Further, with the transmitted artificial potential, VO must be applied from the transmitter to the distant interruption zone, as if there were no intervening space between.

Note that VO may be positive or negative. Thus energy may emerge at the distant disruption, or be extracted from there. In the first case, energy is input to the transmitter, to re-emerge at the distant dephasing zone. In the latter case, energy is extracted (disappears) from the distant dephasing zone and is received (reappears) back at the transmitter



PRODUCING AN ARTIFICIAL POTENTIAL

- MAKE AN ARTIFICIAL SPACETIME STRESS
  - OPPOSING E-FIELDS
  - OPPOSING B-FIELDS
- FORCE FIELDS SUM-ZEROED
  - SCALAR FIELD
  - ZERO VECTOR FIELD
  - E AND B FIELD COMPONENTS STILL EXIST AND ACT
  - ENVELOPE IS ZERO VECTOR
  - ENVELOPE IS SCALAR
  - DYNAMIC SUBSTRUCTURE EXISTS
- ENGINEERS BOHM'S "HIDDEN VARIABLES"
- BENDS SPACETIME

Slide 018: Producing an Artificial Potential

AN artificial potential is deterministically patterned spacetime stress, made by opposing E-fields and/or B-fields so that they sum to vector zeros in a special pattern.

The resulting zero-summed envelope has no EM force field, to an external observer/detector.

However, the infolded E-field and B-field vector components still exist and act. They may dynamically vary, so long as their summation is always kept to zero.

The simplest variation is to vary all their magnitudes at once, by the same degree. In that case, each one comprises an "EM wave." However, the summations of this cluster or "locked group" of waves still exhibit a zero-E and zero-B field to any external observer/detector. In other-words, to an external observer, one now has a varying wave of pure spatiotemporal stress, but one that has a deterministic structure. This is a scalar EM wave, or electrogravitational wave. It is also an alternating current of specific scalar pattern.

Varying the stress of spacetime locally, curves it locally. This violates the conventional assumption of restricted general relativity that local spacetime is uncurved (is a Lorentz frame).

By use of scalar EM waves with deliberate substructures, one can engineer Bohm's "hidden variables" so that quantum mechanics becomes deterministic rather than statistical. This is a drastic change to the common (Bohr) interpretation of quantum mechanics.

And Einstein's intuition that God does not play dice with the universe turns out to be correct after all.

Since physicists haven't seen where the real game was being played, it has all seemed bewilderingly statistical to them.



IF NO OBSERVABLE MASS FLOWS:

EM POTENTIALS PRODUCE SUSTAINED G-FIELD FLOWS OF VIRTUAL PARTICLES

Slide 019: If No Observable Mass Flows:

Since there are no observable mass particles flowing in vacuum, there are no observable force fields produced. Only virtual force fields can be produced in the virtual particle medium that is vacuum itself.

Thus (here is no observable E-field in the vacuum surrounding a charged point. There is, however, a virtual E-field there. When an observable charged particle such as an electron is introduced in the surrounding vacuum and "couples to" (integrates, zips together) the virtual E-field, an observable E-vector force is produced on and of the observable charged particle.

(For the classically trained electrical engineer or electrical physicist, the statement that no E or B fields as such exist in vacuum, is usually bewildering. Let me point out that any so-called "vector field" (such as the assumed E and B vacuum fields) can mathematically be replaced with two scalar fields. See E. T. Whittaker, Proc. Lond. Math. Soc.l, 366, 1903. What we are saying here is that the definition of an E field is in terms of force per unit charged mass. The scalar fields - which are actually what exist in vacuum - provide only a virtual or unzipped E field, until an observable spinning particle couples to both of them by virtue of its "dynamo flux pump" action. The ensemble, then, of two electrostatic scalar potentials coupled to a spinning observable particle, constitutes and is the so-called "E-field.")

When detecting these "vacuum E-fields," it is the free electrons in the electron gas in our probe or antenna which couple to the two "Whittaker scalar fields". These electrons produce ensembles that interact with each other collectively.

Charges in this electron-gas coupled medium is what we actually detect - not "what is in the vacuum."

To repeat this again for emphasis: The usual detector is an "electron-wiggle" detector. It detects changes in its own conduction electron gas, not in the vacuum itself. That is, the disturbance in the virtual-particle vacuum interacts with the observable particles of the electron gas, if (and only if) the spins of these observable particles couple the vacuum disturbance to the electrons and integrate their virtual components. After integration, an observable disturbance of the integrating object - say, the electron - results. It is this electron gas disturbance that is "detected" by almost all orthodox EM detectors.

If the spin of the observable conduction electrons cannot couple the electron to the vacuum flux disturbance, then the normal "simple" detector will not detect the disturbance. (By a "simple" detector we mean one in which the electrons are able to couple to the vacuum disturbance! Little circular definition here!)

Now most potentials reach to infinity before reducing to zero. The change in the virtual particle flux intensity of vacuum - which comprises the potential - decreases with distance from the potential. The magnitude of the change tails off" toward zero as one approaches infinity.

To any finite distance, then, there exists a decreased gradient in the change of the virtual flux intensity of vacuum, from a potential. Therefore virtual particles are flowing in the direction of the decrease of this gradient, just as gas molecules flow from a region of high pressure toward a region of lower pressure.

So there is a virtual particle "river" in the vacuum between any two separated points of different potential magnitude. The type of potential determines the type of virtual particle(s) in the river.

If the potential is natural, the gradient river does not carry any coherent substructure.

If the potential is artificial, the gradient river carries the coherent substructure everywhere within it. In this case, there is a flow or "river" of the virtual structure of this coherent pattern in the vacuum between two separated points of different "potential" in that pattern.



GRAVITATIONAL POTENTIAL: A CONGLOMERATE OF STRESS TYPES

SPACETIME CURVATURE
NEUTRINOS
PROTONS
CHARGED PARTICLES
UNCHARGED PARTICLES
ETC.
VACUUM SPACETIME

Slide 020: Gravitational Potential: A Conglomerate of Stress Types

Rigorously, all EM potentials are actually part of the overall 5-dimensional gravitational potential.

There is no such thing as "the" singular gravitational potential: instead, it is a conglomerate of different stress types and patterns, each of which is named for the type of action that produces it.

The movement of charged particles, for example, creates electromagnetic potentials. At any point in vacuum, the potential consists of a flux of virtual particles.

The vacuum contains a great variety of particle fluxes. There are virtual photons, virtual electrons, virtual positrons, virtual protons, virtual pions, virtual neutrinos, etc.

The conglomerate stress from all these virtual particle stresses constitutes the overall gravitational potential



WHAT GRAVITATIONAL FIELD IS

¤ NO SUCH THING AS "THE" G-FIELD
¤ G-FIELD IS A CONGLOMERATE OF:
  - MANY COMPONENT POTENTIALS
  - MANY OTHER ENTITIES
¤ "G-FIELD" IS CURVATURE OF SPACETIME
¤ ANY COMPONENT(S) OF THE CONGLOMERATE CAN BE USED TO CURVE SPACETIME
¤ FLOWS CAN EXIST BETWEEN PAIRS, TRIADS, ETC. WITHOUT APPRECIABLE CHANGE OF THE OVERALL CONGLOMERATE POTENTIAL
¤ ALL FORCE FIELDS REPRESENT BLEED-OFFS OF ONE OR MORE COMPONENTS OF G-FIELD

Slide 021: What Gravitational Field Is

As previously stated, there is no such single thing as "the" gravitational field, as is assumed in the Newtonian sense.

G-field is a conglomerate of many component potentials and other entities.

Rigorously, anything that "curves spacetime" is a gravitational field.

In the modern view, all forces ultimately arise, by some means, from the curving of spacetime. Thus all forces and force fields are related to - and caused by, so to speak - gravitational field.

If the vacuum stress is uniform from one place to another in an observer's **frame** then the observer's spacetime is uncurved. The observer's frame, is said to be linear or uncurved; or a Lorentz, frame. In such a situation the conservation laws rigorously apply for macroscopic, closed systems.

If the vacuum stress is not uniform from one place to another, then the spacetime is curved. In such a situation the conservation laws may be violated for macroscopic systems, since they are "opened" to the vacuum stress, and vacuum virtual particle flux gradients exist across the system or portions of it.

Note that the overall stress magnitude may be constant across a region, but its composition may change. That is, two or more components may vary canonically. In that case, the spacetime is uncurved in the gross external sense, but contains specialized "internal" curvature patterns locally. Depending upon reaction to the canonical infolded curvature patterns, some macroscopic systems will still exhibit conservation, but certain other macroscopic systems may not.

An example is symmetry breaking. Here charge, parity, and time symmetry may be violated individually or in pairs, but not all three simultaneously. An overall conservation law is obeyed, but any two of the three conservation laws can be (und are) violated.



EM FORCE FIELDS ARE
RELEASES OF GRAVITATIONAL POTENTIAL VIA OBSERVABLE MASS FLOWS

Slide 022: EM Force Fields are Releases of Gravitational Potential via Observable Mass Flows

In Kaluza theory, we may take EM force fields to be the 5th dimensional "bleeding-off" of a 5-G potential. However, in vacuum alone this bleeding-off is totally within the virtual state. That is, only virtual EM force fields exist in vacuum.

By the ordinary term "EM force fields," physics has chosen to imply measureable or observable E and B force fields.

That implies that the 5-G potential gradient flows of virtual particle flux must be coupled to observable charged particles - such as electrons, protons, ions, etc. - before observable E and B force fields exist.

Rigorously, E and B force fields consist of the virtual E and B force fields coupled to observable charged particles. They do not "cause" a particle to accelerate; they are the product of the particle and its acceleration.

As these observable particles are themselves "spray pumps" producing virtual particle flux, then a collection of them represents an increased or decreased **flux** (for negative or positive charge) vis-a-vis the ambient background flux of vacuum. Nature furnishes the continuous power to drive these "virtual flux" pumps.

Normally, EM potentials are formed in natural and manmade electrical circuits by collections of these observable particle "spray pumps." Such collections of increased or decreased "spray flux" density, of course, represent 5-potentials, gravitationally.

Release of these pumps in conductors or in the vacuum itself results in creating E-fields and B-fields on and of the moving observable charged particles. But release of the observable-particle spray-pumps from the collection (the potential "pressure head" or "source") reduces the potential or "pressure" at the source.

Thus the formation of E and B fields represents the release of the 5-potentials. Hence EM force fields are the bleed-off of 5-dimensional G-potential via observable mass flow.

Since classical EM always seeks to create the force fields, it always bleeds-off and discards the gravitational effects that could be otherwise achieved.

To allow orthodox EM flow is to dissipate the gravitational effects.

Strangle the orthodox EM flows, and you can keep and use the amplified gravitational effects.


SCALAR Ō-WAVE PRODUCTION
+5
+Ē
Ē₀=ō
-Ē
-5
VIRTUAL GROUND
SPINNING
CHARGED PARTICLE
WILL NOT PRECESS
+10
+φ
φ₀=ō
-φ
-10
COMPRESSIVE
STRESS
TENSILE
STRESS
STRESS LEVEL
ON SPACETIME

Slide 023: Scalar O-Wave Production

We now visualize the formation of waves of pure stress in the spacetime medium (in the vacuum). These we call scalar EM waves, Tesla waves, electrogravitational waves, longitudinal EM waves, waves of pure potential, electrostatic/magnetostatic waves, and zero-vector EM waves. All these terms are synonymous. Each sheds its own particular light upon the nature of these waves or of their original discoverer, Nikola Tesla.

We use a gedanken experiment, or thought experiment, in which we can be "perfect."

Thus we have two single-frequency EM sine waves whose E-field componenls are shown on the slide. The two waves are of the same frequency, traveling together in the same direction, and superposed 180 degrees out of phase with each other.

In this case, at any spatial point, the summation E and B fields are vector zeros.

However, if we plot the spatiotemporal (vacuum) stress induced by the wave, wo see that it constitutes a sine wave, with compressive stress in one half cycle and tensile stress in the second half cycle.

Rigorously this defines a "longitudinal" EM wave - or what Tesla called a "sound wave in the nonmaterial ether."

Also, rigorously it is a gravitational wave, for it is a wave of the curvature of spacetime (nonlinearity of vacuum) itself. That is, what is changing in the wave is the vacuum stress, or intensity of the virtual particle flux of vacuum. That is identical to changing the curvature of spacetime. In one half-cycle, spacetime is curved positively. In the second half-cycle, spacetime is curved negatively.

Since the increase or decrease of the intensity of virtual particle flux (vis-a-vis the ambient vacuum's virtual flux intensity) represents electrical charge, then in one half-cycle negative charge is represented, and in the other half-cycle positive charge is represented. This directly explains the "positron-electron pair" representation of an electromagnetic photon - the "photon" being one wavelength.

In one half-cycle, time moves slower. In the second half-cycle, time moves faster. Thus scalar waves can also be considered to be "tempic" waves (to use Wilbur Smith's term), or oscillations of the rate of flow of time itself, about the ambient rate of time flow. Since these oscillations are variations in the curvature of spacetime, then they represent gravitational or force-generating waves, when coupled to a mass.

Variations in the rate of flow of time produce force, just as any other type of curvature in space-time does.



SCALAR ELECTROMAGNETICS

- ZERO-VECTOR ENVELOPE
- DELIBERATE, ORDERED SUBSTRUCTURE
  - ¤ SPECIFIC PATTERN
  - ¤ DETERMINISTIC
  - ¤ CONSTITUTES "HIDDEN VARIABLES"
  - ¤ PHASING IS KEY
- TO MAKE A SCALAR BEAM
  - ¤ USE PHASE-LOCKED FORCE-FIELD BEAMS
  - ¤ TWO OR MORE
  - ¤ STANDARD BEAMING ANTENNA
  - ¤ CONVENTIONAL BASIC CIRCUITS
  - ¤ SLIGHT CIRCUIT MODIFICATIONS

Slide 024: Scalar Electromagnetics

To rehash: scalar waves are zero-vector waves. Patterned E and B fields exist in a relationship where their summation equals vector zero. Electromagnetically, the zero EM "envelope" of a scalar EM wave is composed of a zero-summation of infolded finite EM force-vectors.

However, the internal (infolded) substructure is deliberate, macroscopic, and ordered. Vacuum is polarized deterministically by the wave, and macroscopic spacetime is locally curved by it.

These substructure components constitute Bohm's "hidden variables." They can be manipulated and varied at will. Phasing, beaming, frequency, superposition, interference, resonance, and Fourier expansion are the keys to scalar EM engineering.

To make a scalar beam, special modifications are made to the EM wave transmitter so that, effectively, the transmitter transmits multiple transmissions simultaneously, and these vectorially sum to zero. This is the same thing as transmitting multiple phase-locked EM force-field beams simultaneously, in **the** sum-zeroed fashion.

Standard beaming antennas and conventional circuits can readily be utilized with slight modifications.

Any radar can be converted to a scalar EM radar quite simply. Indeed, a modification kit to accomplish that can be developed and held until the **scalar** mode is desired. The modification kit can be quickly installed to provide the scalar capability.

Scalar radars, for example, cannot track "corner reflector" targets. However, they can magnificently track smoothly filleted corners; rounded, smoothly curved surfaces; and curved or flat metalized dielectrics. Against aerial targets using special construction to lower their cross-section to normal radars, the application of the scalar radar mode is immediately obvious.

Scalar waves pass through the electron shells of an atom and interact with the nucleus. They are continually absorbed and emitted by all nuclei in the universe.

BACKGROUND FOR THE BRIEFER.

Any large collection of nuclei - such as a star or a planet - is a strong absorber and radiator of scalar wave radiation.

The Sun is a particularly strong source of scalar radiation. This radiation penetrates the Earth deeply, interacting more and more with the deeper layers which, under greater mechanical stress, are more nonlinear. Most of the heat in the molten core of the Earth comes from the dephasing of a portion of this absorbed scalar radiation from the Sun, liberating ordinary EM energy as heat.

The Earth also re-radiates scalar wave radiation back to the Sun. The Sun and Earth are thus coupled into a "scalar" system in equilibrium or near-equilibrium. Each body in the couplet possesses both a feed-forward and a feedback loop.

The Earth also radiates scalar wave radiation to the Moon, and the Moon reradiates scalar radiation back to the Earth. The Earth and Moon also are coupled into a "scalar" system in equilibrium or near-equilibrium. Again, each body in the couplet possesses both a feed-forward and a feedback loop.

The Sun and Moon are correspondingly coupled into a scalar system in equilibrium or near-equilibrium, each with both a feed-forward and a feedback loop.

The Earth, Sun, and Noon thus form a triad-coupled system of special importance to the stability of our existence here on Earth, and the stability of our biosphere.

And so on with all the other planets in the solar system, and combinations thereof.

The solar system is thus a very sensitive scalar-coupled system, with strong subsystems within it.

ADDED FOR THE BRIEFER:

Actually this scalar coupling of the solar system provides a major check on unrestricted use of the large Soviet strategic scalar EM weapon systems. If significant scalar effects are produced on earth in a "pulse" mode, pulsed disturbance of the earth-sun and earth-moon systems results. Here a danger exists that one or more natural resonances of the coupled system may be excited. If the feedback stimulation of the Sun is not insignificant, for example, large sunspot activity may result sometime thereafter, say in a day or two. If too much or too sharp stimulation occurs on earth, the coupled resonant response from the sun could be disastrous. Indeed, a solar response could be stimulated so that the Sun would violently belch and destroy our biosphere, among other effects. The simplest doomsday stimulation would be for a violent expulsion of Solar EM energy and particles to occur. If this were due to resonance, the expulsion of Solar EM energy and particles would continue during some decay time. In that case, fiery destruction of the earth, strongly indicative of Biblical prophecy, would result. Particularly sensitive are the resonances of the sun-earth, sun-moon, and earth-moon systems.

Note the abnormal influence of the moon on tides - tides of both the tectonic plates and the oceans. One cannot help but point out that, if the earth-moon resonant system were overstimulated, one might expect violent earthquakes of extraordinary magnitude, and tremendous tidal waves hundreds of feet in height. (The potential connection to legends of earth-destroying floods, evidences of extreme water levels in mountains, and legends of ancient cataclysmic destruction of supposedly advanced technological oceanic cultures is obvious.)

Accordingly, use of huge scalar EM weapons is a double-edged sword. Unless carefully employed, use of the weapons could cause a terrible backlash to the user as well as the victim, and even accidentally cause the destruction of the earth itself. It is not accidental that in 1960 Khrushchev stated that his new fantastic weapon could - if unrestrainedly used - destroy all life on earth.

This appalling backlash potential is apparently what prompted Brezhnev in 1975 to make so strong an effort to get agreement to outlaw the development of "new weapons of mass destruction" more frightful than the mind of man had even dreamed of. Gromyko even introduced such a draft agreement into the proceedings of the United Nations. The first article of the draft agreement indicated that the nature of the weapons referred to would be negotiated. Sadly, the entire Western world did not even know what the Russians were talking about.



ROGERS' UNDERSEA & UNDERGROUND COMMUNICATIONS SYSTEMS

- SECRETLY USED BY U.S. IN WWI
- COMMUNICATED TO SUBS UNDERWATER
  - ¤ ANY DEPTH, UP TO 30 KHZ
  - ¤ REDUCED DEPTH, – 30 KHZ
- COMMUNICATED TO EXPEDITIONARY HQ OVERSEAS
  - ¤ 5000 TIMES STRONGER THAN AERIAL
  - ¤ STATIC-FREE
- DECLASSIFIED IN 1919
  - ¤ TO REVOLUTIONIZE COMMUNICATIONS
  - ¤ TO END ALL SURFACE ANTENNAS
- MYSTERIOUSLY "LOST"
- REDISCOVERED AND "LOST" 3 TIMES AFTER WWII

Slide 025: Rogers' Undersea & Underground Communications Systems

In an article in the March 1919 issue of the Electrical Experimenter, a real bombshell was released on an unsuspecting world.

In that issue, details of the Rogers'undersea and underground communication systems were released. These systems had been classified SECRET during WWI, and used to communicate with (1) U.S. submarines underwater around the world, and (2) U.S. Expeditionary Forces Headquarters overseas.

Subs at any submerged depth could be reached with transmitters of frequencies up to 30 kiloHertz. At reduced depths, frequencies above 30 kHz could be used.

At the headquarters of U.S. overseas forces, the signals were received through the earth. They were 5,000 times stronger than aerial signals through the atmosphere, and static-free.

The Rogers' systems were covered by a series of patents. They used special antennas implanted in the ground.

While the patents are somewhat confused, several of the diagrams in the Electrical Experimenter reveal that the antennas were producing scalar waves. Scalar waves can indeed travel through the earth and through the ocean. Indeed, if good quality scalar waves are made, then frequencies well above 30 kHz can be sent through the ocean. Multi-megahertz frequencies, for example, are easily achievable. (The problem, of course, is that these waves are pure zero-vector artificial potentials that do not move electrons in the conduction gas of a conventional antenna/receiver combination. Normal receivers and detectors do not see them. Special underwater detectors - such as those developed by Frank Golden - are required.).

With the startling declassification and revelation of the Rogers' systems, it was expected that all communications would be revolutionized, and that all surface antennas would be removed.

Strangely, this entire technology faded away quickly, as if it had never been. Certain powerful interests did not wish the extended electromagnetics to be discovered or taught. That, after all, would lead to free energy and loss of economic control of the citizens. That was precisely why Nikola Tesla had already been suppressed.

According to the important research of Dr. Robert Beck, the same scalar technology has been rediscovered and mysteriously "lost" at least three times after World War II!

Today the orthodox establishment is still suppressing it.

One wonders why no orthodox physicist - with the single exception of Dr. Hooper (see U.S. patents 3,610,971, Oct. 5, 1971 and 3,656,013, Apr. 11, 1972) - seems to have experimented with deliberately constructed zero-vector EM waves and devices, and published his results in the literature.

One would think that any university physics department would wish to explore such a gaping void with at least a few graduate student experiments, if for no other reason than scientific curiosity, particularly when the experiment is easily performed, it is totally different from anything else in the theory or literature, and the implications may be formidable. A true scientist in that related field ought to try it!



HOW DOES THE ROGERS SYSTEM WORK?

"WE DO NOT KNOW AS YET HOW THE ROGERS SYSTEM WORK.

... ROGERS HIMSELF TAKES THE VIEW— AND HE IS SECONDED BY TESLA—THAT THE TRANSOCEANIC MESSAGES WHICH HE RECEIVES ... ARE NOT HERZIAN WAVES ..."

H. GERNSBACK
ELECTRICAL EXPERIMENTER
6(11), MARCH 1919, PAGE 52

Slide 026: How does the Rogers System Work?

In the same March 1919 issue of Electrical Experimenter, Hugo Gernsback pointed out that no one as yet knew how the Rogers' system actually worked.

Rogers himself believed he was not using conventional Hertzian waves.

Nikola Tesla himself confirmed that the underground and undersea waves were not Hertzian waves.

If so, they could only have been scalar waves.


SCALAR EM WAVES ARE EMITTED & ABSORBED BY THE NUCLEUS

Slide 027: Scalar EM Waves are Emitted & Absorbed by the Nucleus

Normally scalar EM waves do not couple to orbital electrons. Entering into the atom, incoming scalar EM waves penetrate the electron shells without interaction. They continue, penetrating into the interior of the closely packed nucleus, where the extreme nonlinearity of the charged virtual particle flux that binds the nucleons together distorts the scalar wave, dephasing its summed EM vector components. This produces a nonzero EM resultant and polarized pattern directly inside the virtual particle charge flux of the nucleus.

The new EM resultant immediately couples the distorted scalar wave to the nucleus, resulting in absorption of the wave and incorporation of its polarization pattern into the nucleus' virtual flux. This in turn results in a slightly excited nucleus. Normally the excited nucleus will promptly decay by emitting another scalar wave, which passes through the orbital electron shells and radiates out into the universe.

However, as can be seen, if the same strong scalar pattern is constantly radiated into the nucleus and absorbed by it, the excitation of the nucleus "charges up," leading to decay by other modes. In this manner the nucleus can be engineered even transmuted - by rather minuscule power of the engineering radiation signal.

This is how living biological systems are able to transmute elements, as discovered by Louis Kervran. (Kervran was nominated for the 1977 Nobel Prize for this work.). The biosystem produces scalar EM waves. If the appropriate signal is employed into and on the appropriate nucleus, a changed element emerges. In this fashion chickens denied sufficient calcium in their diet, but allowed a surplus of potassium, are able to transmute some of the potassium into calcium. Note that one of the isotopes of potassium is an isomer of normal calcium. Transmutation of this potassium isomer to calcium is easiest.



NUCLEI OF THE UNIVERSE CONTINUALLY EXCHANGE SCALAR EM WAVES

Slide 028: Nuclei of the Universe Continually Exchange Scalar EM Waves

Thus scalar EM waves are continually exchanged by all nuclei of the universe, and the vacuum is - among other things - a seething cauldron of scalar radiation.

In fact, it is this seething scalar wave cauldron that creates the virtual particles and the virtual particle flux of vacuum itself. (Since the scalar EM wave represents an oscillation of the curvature of spacetime, and since everything - virtual or observable - is a curvature of spacetime, then scalar waves can be taken as the universal generatrix.

The intensity of the trapped scalar flux in the nucleus of an atom is responsible for the mass and inertia of the nucleus.

Mass is localized trapped scalar resonance.

The trapping agent is the spin of a particle.

The mass and inertia of the particle are due to the scalar resonance that is trapped. Increasing the amplitude of the trapped scalar resonance increases the mass and inertia; decreasing the amplitude decreases the mass and inertia.



CONVERTING EM FIELD ENERGY TO G-FIELD ENERGY & VICE-VERSA

Slide 029: Converting EM Field Energy to G-Field Energy & Vice-Versa

According to Kaluza theory, there are no such things as a separate EM field and a separate gravity field. Instead, in five dimensions there is only one field: the 5-d gravitational field. The EM field is the 5th dimensional aspect, while our **normal** 4-dimensional G-field is the other aspect of the 5-field, in our normal 4-space.

Thus we may say that the 5-field is composed of two components: the 5th dimensional component (our normal EM field) and the component occupying **our** normal 4 dimensions (our normal G-field).

The 5-d "force" field, of course - or the 5-space analogy to a force field - would be due to a gradient or "bleed-off of the 5-d gravitational potential. This gradient in turn is composed of two components: the 5th dimensional "bleed-off" outside our normal 4-space (this outer bleed-off is our normal EM force **field**) and the bleed-off inside our normal 4-space (this inner bleed-off is our normal G-field).

Normally the 5-potential bleeds-off outside our 4-space as EM field, far greater than it bleeds-off inside our world as G-field. Between two electrons, for example, the electric field is about 10^{42} times as strong as the G-field. Since in the Kaluza view there is only one 5-d G-potential that is causing both force fields, this shows that there is an incredibly greater EM bleed-off of the 5-

potential between the two electrons than there is a G-field bleed-off between them.

As shown on the diagram, the 5-d G-field is normally comprised almost entirely of the 5th dimensional EM field. Only a small 4-space G-field component exists.

However, suppose we were to "block" the bleed-off of the 5-potential in the EM mode. Then none of the 5-potential could bleed-off in the 5th dimensional EM field. Instead, it would be forced to bleed-off into the 4-space G-field. In our two-electron example, this "perfect case" would result in the disappearance of the E-field between the two electrons, and the G-field between them would increase to about 10^{42} times its normal strength.

The end result would be that, by blocking the EM force field bleed-off, EM field is converted to G-field. In addition, EM field energy is converted to G-field energy. With the extremely amplified gravitational and inertial effects that result, one can now accomplish direct engineering of gravitation, mass, and inertial effects.

We can effectively accomplish this "blocking the EM bleed-off by opposing EM force fields so that they sum to vector zero. This is the same as summing various 5th dimensional gradients of the 5-potential to a zero vector resultant. In that case, as much "EM bleed-back to 5-potential" occurs as there is "EM bleed-off from 5-potential." This places the 5-potential in equilibrium with respect to EM bleed-off.

Also, another nice thing results: Since we can readily vary the magnitudes of the EM force field components of the vector zero summation, we can actually form phased "zero vector waves" by increasing and decreasing the magnitudes of all the component EM vectors in phase, but retaining their vector summation always equal to zero.

In that case we have produced a very simple 5-space G-potential wave, which concomitantly forces phase-locked variations in the 4-space G-potential. In short, we have produced an electrogravitational (EG) wave, or scalar EM wave for short. This wave described is the simplest EG scalar wave we can produce; much more complex EG waves can be produced and used for highly **specialized** purposes.

The scalar EG wave changes EG potential energy into 4-gravity potential energy in one half-cycle, and changes 4-G potential energy into EG potential energy in the other half-cycle. However, the EG potential energy in the first half-cycle does not react electromagnetically in linear circumstances, since it is electromagnetically a linear vector zero.

So our scalar EG wave actually oscillates energy back and forth between a locked-in 5th dimensional EM potential and a 4-space G-potential. As can be seen, to the linear 4-space observer this scalar EG wave appears as a purely gravitational wave, with G-potential magnitude varying in a wavelike manner.


NORMAL EM BLEEDS-OFF G-FIELD
5-D G-FIELD
BIG PRESSURE TANK
(ACCUMULATOR)
WHOOSH
5th DIMENSIONAL EM BLEED
4-D G-FIELD BLEED

Slide 030: Normal EM Bleeds-Off G-Field

For easy visualization, we may regard the situation in the analogy shown on the slide.

The 5-potential of 5-space vacuum is like a high pressure in a big tank. The tank has a huge open door in the 5th dimension, leading to rapid bleed-off of the 5-presure through the big door; that is, as EM field. Only a very small hole in the tank normally exists in our own 4-space world, so only a very small amount of the pressure bleeds off as our G-field.



SCALAR EM FORCES 4-D G-FIELD

??
5-D G-FIELD
BIG PRESSURE TANK
EM
ZERO
VECTOR
(ACCUMULATOR)
BOOM!
← B̄
5th
DIMENSIONAL
EM BLEED
← Ē
4-D
G-FIELD BLEED

Slide 031: Scalar EM Forces 4-D G-Field

As can be seen however, if we shut the big door so that we have only a little bleed-off through the seals, then most of the pressure is forced to bleed-off through the small opening, greatly enlarging it. In that case, most of the 5-potential bleeds-off as 4-G force field.

The mass exposed to such increased 4-G bleed-off exhibits a much greater mass and inertia.

In fact, mass itself can act as an accumulator for the effect, and it can increase its ability to store trapped scalar resonance. This increases its inertia.

By the use of scalar EM (blocking the EM bleed-off), we can input normal EM energy and obtain powerful gravitational and inertial effects. Many other powerful effects can also be obtained.



DETECTION OF ELECTRO-GRAVITATION

- WHEN ORDINARY EM FORCE FIELDS ARE INTERFERED/SUMMED TO PRODUCE ZERO, AND ARE ALSO LOCKED TOGETHER, THEY PRODUCE STRESS OF VACUUM (GRAVITATIONAL POTENTIAL OF FIELD).
  THIS IS ELECTRO-GRAVITY.
- WHEN ELECTRO-GRAVITATIONAL FIELDS ARE INTERFERED/SUMMED TO PRODUCE ZERO, AND ARE LOCKED TOGETHER, THEY PRODUCE ORDINARY ELECTRO-MAGNETIC FORCE.

Slide 032: Detection of Electro-Gravitation

Here arc two magic rules in the scalar electrogravitational business:

(1) When ordinary EM force fields are interfered or summed so that they produce vector zero, and the fields are locked together, they produce stress of vacuum (5-potential). One component of this 5-potential is the 4-space G-potential. Since bleed-off as a gradient of this 4-space G-potential is all that is allowed, then the EM destructive interference/zero summation bleeds-off to produce gravitational force field. This is because opposing equal forces, which sum to a vector zero force field resultant, actually produce a stress potential having stress energy of spacetime. And that is a curvature of spacetime, hence gravitational.

In short, total destructive interference of EM waves or force fields produces excess stress potential energy in spacetime, and therefore gravitational force field on detecting/coupled particles.

(2) When electrogravitational fields are interfered/summed to produce vector zero, this destructive interference/zero summation bleeds-off to produce ordinary electromagnetic force field.

In short, destructive interference of scalar EM waves or fields (electrogravitational waves or fields) produces electromagnetic force fields on detecting/coupled particles.

BACKGROUND FOR THE BRIEFER:

Mathematically we can summarize this as follows;

$$G_{(1-4)} = G_{(1-4)}\,(m) + G_{(1-4)}\,(EM) \qquad [3]$$

$$G_{(1-5)} = G_5 + G_{(1-4)} \qquad [4]$$

If $$\mathbf{E} = \Sigma\mathring{\mathbf{a}}_i E_i = \mathbf{0},\ E_i \neq \mathbf{0};\ \mathbf{B} = \Sigma\mathring{\mathbf{a}}_i B_i = \mathbf{0},\ B_i \neq \mathbf{0} \qquad [5]$$

then $$G_{(1-4)}\,(m) = G_{(1-4)}\,(EM) = G_5 = G_{(1-5)} \qquad [6]$$

and $$G_5 = G_{(1-4)} = f[\Sigma(\mathring{\mathbf{a}}_i\,|\mathbf{E}_i|^2)] + g[\Sigma(\mathring{\mathbf{a}}_i\,|\mathbf{B}_i|^2)] \qquad [7]$$

and $$G_{(1-5)} = G_5 = G_{(1-4)}\,(m) = G_{(1-4)}\,(EM) = f(\phi) + g(\mathbf{A}) \qquad [8]$$

Where:

$G_{(1-5)}$ is the 5-d G potential, or total G-stress on dimensions 1-5.

G_5 is the combined EM potential, or G-stress on dimension 5 only.

$G_{(1-4)}\,(m)$ is the normal 4-d G-potential of mass alone, or the G-stress due to mass-gravity.

$G_{(1-4)}\,(EM)$ is any extra 4-d G-potential of mass due to conversion from G_5 stress (normally zero).

E and B are the electric and magnetic force fields.

ϕ is the electrostatic scalar potential.

A is the magnetic vector potential.

Thus the age-old scientific dream of direct engineering of gravitational field — and of spacetime itself — can now become reality. To start, one simply makes an intense EM vector zero and varies its stress intensity and internal pattern of summed components. One also varies the reference potential at which the patterned EM stress zero is created, and the frequency of internal component variation.

BACKGROUND FOR THE BRIEFER.

He that has ears, let him hear.

Here is the secret of antigravity

The "electrical charge" of a charged particle — such as one of the orbital electrons of an atom or one of the protons of its nucleus — represents a difference in flux intensity (potential) between the local particle and its ambient vacuum.

It's the continual bleed-off of gravitational charge as electrical charge.

If that bleed-off is reversed or stopped, a drastic effect on the gravitational potential and charge ensues. The 5-potential and 5-charge have become 4-G-potential and 4-d-charge respectively.

Thus "charging" an object with its scalar EM pattern charges it gravitationally.

Now the only "bleed-off channel" is through the 4-G force field.

Further, in a nucleus the nucleons continually change back and forth between proton and neutron, so the electrical charge is "spread" throughout the nucleus and shared by all the nucleons.

Further, each element (actually each isotope) has its own unique "ensemble pattern" of Fourier expansion scalar frequencies, amplitudes, etc. This pattern, of course, can be reproduced artificially and transmitted by modified EM transmitters (i.e., by scalar EM transmitters). There is, however, a sort of "master key" scalar EM (EG) pattern for nucleons (protons and neutrons which are changing back and forth into each other by exchange of virtual charge currents).

If one "reverses the charge" by inverting this pattern, and then "charges up a mass with the inverted charge," to the external observer the charging mass just gets lighter and lighter, and its inertia gets less and less. Eventually it seems (to him) to acquire negative mass and negative inertia, and just accelerate away from the earth. The object "falls upward" instead of "falling downwards."

There are also some weird time effects. The object can be moving slower through time than the laboratory observer, or even be moving backwards through time with respect to the laboratory observer. (Don't believe everything they taught you in relativity; none of those professors had ever engineered a single general relativistic situation. Little that they teach in GR is based on direct experiment. Most of what they teach is already experimentally proven to be incomplete or in need of further extension.).

But back to our slide.

Inside the pattern itself, it's just a quite normal pattern. No change in or on the object seems to have occurred, to it, if the charge is evenly accomplished throughout the object. Indeed, to an internal observer it's the external environment that seems to have suddenly gotten very strange! This is what occasionally happens to a hapless aircraft or ship that experiences anomalous spatiotemporal difficulty in an *occasionally scalar-active* area such as the Bermuda triangle. Under the right conditions, the vehicle's gravitational charge is affected by anomalous changes in the scalar radiation from the earth in that area. To the passengers and crew, it is the external environment that suddenly seems weird. In addition, on-board EM and inertial instruments may be affected, and other electrogravitational effects may also occur, due to differing rates of charge in different parts of the vehicle.).

"Reversing or lowering the EG-charge" is controlled by means of biasing the ground potential on the ensemble pattern transmitters. These transmitters can even be on-board the vehicle itself. (Remember, in scalar EM to transmit is also to receive. A vehicle can change its own bias potential (with respect to local vacuum G-potential) by properly transmitting, which translates to "receiving potential charge." The charge current can either be negative or positive (its potential can be lowered or increased vis-a-vis that of the vacuum.) Think of this as handling positive and negative energy, which means positive and negative gravity.

By "fiddling" with this, you can float metal. Or a human body. Or a battleship. Or a high-speed vehicle containing a crew.

You can even "dematerialize it" or "teleport it."

The Philadelphia Experiment may have been real after all. If so, the test ship and its personnel were "blasted" into this strange realm, instead of making a gentle, controlled entry.

Suppose you materially lower or reverse (adjust) the gravitational charge (gravitation 5-potential with zero-summed EM to throttle EM bleed-off). At zero gravitational charge, to the external observer, such an assumed vehicle would seem to have no mass and no inertia. It is capable of extreme accelerations, right angle turns at full speed, etc. It is also right on the point of dematerialization, and may appear to be glowing or just a vehicle of light.

If the pilot wishes to "land," of course he must adjust the charge on the vehicle.

If the pilot wishes to "dematerialize" or "teleport," again he must adjust the charge on the vehicle.

If he wishes to go "hyperspatial," again he must adjust the charge on the vehicle and allow the proper bleed-off to produce a hyperspatial force. That's done with nested zero summations and nested patterns of scalar EM transmission.

That is, he can charge and bias the vehicle in multiple, nested zero-summations simultaneously.

That is necessary for hyperspatial control and travel.

Note that in lower hyperspace such a vehicle could do some very strange things. Such as "penetrate" solid matter (actually, it goes "around" the 3-space matter in a 4th Kaluza-Klein space).

We might expect to see such vehicles glowing. Their various surface features and mechanisms might appear to be glowing or revolving lights, etc.

They could exhibit incredible "aerodynamic performance," seemingly in the atmosphere. Actually they would not be moving "through" the atmosphere at all but through a higher space outside each particle of atmosphere.

They could seem to materialize and dematerialize.

They could seem to plunge into the ocean or rise out of it.

They could even seem to operate under the ocean or inside the earth itself.

Such anomalous vehicle performances have been seen all over the world, particularly since a few years after WWII.



SCALAR WAVE DETECTOR*

(DETECTS ELECTROGRAVITATIONAL WAVES)

* BEDINI VERSION OF DEA/FARETTO DETECTOR

033

NOTE: MAGNET > 40,000 gauss

Slide 033: Scalar Wave Detector

On this slide we show a concept for a detector for scalar EG waves. This is the Bedini scalar wave detector, adapted from an original concept by Dea and Faretto.

The idea is quite simple: install a very powerful bar magnet vertically inside a grounded Faraday cage. Then install an open-ended coil longitudinally above the magnet so that a line through the longitudinal axis of the magnet passes through the longitudinal axis of the coil above it. The open end of the coil does not touch the magnet.

Connect the other end of the coil to a variable tuning capacitor, so that the coil and capacitor form a tunable, series-LC-oscillatory circuit. The output of the capacitor is connected to a transistorized preamplifier inside the cage. A tuning shaft for the capacitor is very carefully passed through a small hole in the shield to allow tuning from outside.

The output of the preamp passes very carefully through a small hole in the shield, through a shielded cable, to an adjacent oscilloscope. The cable shield in also grounded to reference ground potential.

The theory is as follows: Suppose a normal EM wave appears inside the cage, above the magnet or closely adjacent thereto. In that case a coupled **oscillation** appears in the field of the magnet, and this oscillation is coupled to the coil immediately above it. If the oscillation is within the bandwidth of the tuned series LC circuit, detection occurs. This is amplified by the preamp and passed to the oscilloscope, where it is displayed on the scope.

Note that the detector detects normal EM wave. Now our problem is: how do we get an EG wave to be detected? And how do we assure that we do not detect ordinary EM waves from outside?

Actually this is simple. Ordinary waves (except for quite low frequency) will be grounded out by the Faraday shield, and will not penetrate the cage. Thus these normal EM waves cannot enter the cage and appear above the magnet. They will not be detected.

Scalar EG waves, on the other hand, will enter the cage since they do not couple to conduction electrons in the metal of the cage. Above the pole of the magnet, spacetime is locally bent. After all, a pole is a magnetostatic scalar potential, which is a part of the conglomerate called "G-potential." The pole represents an increase (or decrease, depending upon whether it is a north or a south pole) in **the** magnetostatic component of the local G-potential. This is a curvature of spacetime. An EG wave entering this region adds a varying component of magnetostatic G-potential, which bleeds-off in the coil as an ordinary EM wave.

Another way to view the detector is to model the EG wave as a longitudinal wave, and an ordinary EM wave as a transverse wave. When the EG wave enters the curved spacetime region above the magnet, to the coil (the "observer" in this case) the longitudinal aspect of the EG wave appears to be rotating back and forth, so that an oscillating transverse component is present. This transverse component appears to the coil as an ordinary EM field, and so the LC circuit detects it if it is in the proper frequency band.

Yet another way to view the situation is to realize that an EG wave entering the magnet results in an oscillation component added to the magnetostatic scalar potential (pole strength) of the magnet. Accordingly, the magnet is a receiver **for scalar** waves, which are detected to "bleed-off as an oscillation of the magnetic field strength of the magnet. Coupling of this oscillating magnetic field **to the** coil creates an oscillating current flow into the capacitor. This oscillates the voltage input to the preamp, which amplifies and feeds the signal to the oscilloscope for display.

In fact rather like the latter view! It is important to remember that a magnetostatic potential and an electrostatic potential can be oscillated by a scalar EG wave. By placing a magnetic material inside a Faraday cage, the oscillation of the magnetostatic scalar potential (pole strength of the magnet) can be used as the EG detecting mechanism. By placing a chargeable material inside a Faraday cage, the oscillation of the electrostatic scalar potential can be detected. (Possible examples of the latter type detectors are given by Hodowanec, Radio Electronics, April 1986.)

Note also that one may detect waves at one reference level and not at another. Changing the bias on the zero-reference ground of the Bedini detector affects the detection. To look inside a normal EM carrier (such as the Woodpecker) and see what scalar signals are riding upon it, the carrier may be used to bias the reference ground of the Bedini detector.

To produce a spectrum analyzer, simply use additional series resonant LC tuning circuits in parallel (put multiple taps on the coil, and wire each tap to a separate tuning capacitor of different capacitance). Again, varying the zero reference level is important, as is varying the strength of the magnet.

Golden also has invented an excellent series of scalar wave detectors based upon quite different proprietary principles.

The bottom line is: we can indeed rigorously detect and measure scalar EG waves. When one considers the large sums of money presently being spent to bury large aluminum cylinders etc. in an attempt to detect gravitational waves, one wonders why some funds could not be released to a few unorthodox researchers by the National Academy of Sciences to fund the proven creation and detection of electrogravitational waves!

Note from TEB: I understand that it took Bedini about 600 attempts before he got the device to work. It was then handed over to a different party to produce, who made some "improvements," and the device then failed to work.


SCALAR RESONANCE
$\bar{E}_R = \bar{0}$
λ_1
λ_2
E
B
B
E
$\bar{B}_R = \bar{0}$
NOTE:
CAVITY IS
RESONANT
TO EITHER
WAVE
INDIVIDUALLY
WAVE AND ANTI-WAVE SUPERPOSE AND
MOVE ALONG TOGETHER, BACK AND FORTH

Slide 034: Scalar Resonance

Here we explain a new kind of resonance: scalar EH resonance, or electrogravitational resonance.

First, imagine we have a standard resonant cavity, represented by the two walls in our diagram. In this cavity we have a resonant EM wave moving back and forth, represented by the forward-most plane. In accordance with convention, we show the E-field vector and the B-field vector at right angles in this moving wave front. As the wave front moves back and forth, the vectors vary back and forth; however, at any one point between the walls, the two vectors always have the same value. Thus our resonant EM wave forms a standing wave in the cavity.

Now imagine that a second wave front, precisely like the first and of the same frequency, is superposed over the first wave front and travels along with it. This second wave - the "antiwave" - has its force vectors 180 degrees out of phase with the force vectors of the reference wave. Hence the E-fields and B-fields of the two superposed waves always sum to vector zeros, anywhere in the cavity. To an external observer, the cavity contains no ordinary electromagnetic force fields, hence no ordinary EM energy.

However, the energy density of a single EM sine wave in vacuum is given by

$$[E^2+B^2]/8\pi \qquad [9]$$

This energy density is always positive. Hence the energy density of the two waves at any point x between the walls is equal to

$$[E^2+B^2]/4\pi \qquad [10]$$

where

$$E = E(x)\ ;\ B = B(x) \qquad [11]$$

Thus the energy density of vacuum varies with x. But, rigorously, since the resultant E and B fields are zero, this describes a standing gravitational wave. Hence we have a standing EG wave, existing in the resonant cavity. This is an example of scalar resonance. Rigorously the cavity has mass and inertia, to an outside observer, as a result of the two warps in spacetime it contains.

Note that in one half-cycle the energy density of vacuum is greater than ambient, and in the other half-cycle it is less. In the region of one half-cycle, time flows at a faster rate than to the ambient observer, and in the other half-cycle time flows at a slower rate than to the ambient observer.

One half-cycle appears to contain negative electrical charge, and the other appears to contain positive charge.

One half-cycle appears to contain a north pole (positive magnetostatic scalar potential), and the other half-cycle appears to contain a south pole (negative magnetostatic scalar potential).

Perhaps now one can begin to understand why a continuously accelerated orbital electron in the atom does not radiate EM energy, completely in violation of Maxwell's equations. The electron is naught but a complex aspect of a standing scalar resonance, existing between the nucleus and the orbit.



SCALAR RESONANCE

- NOT IN PRESENT TEXTBOOKS
- CONTROLS NATURE OF PARTICLE
- BENDS SPACETIME
- CONTROLS MASS
- CONTROLS INERTIA
- CONTROLS GRAVITY
- CAN FLOW
- A "MASS" IS LIKE A CAPACITANCE
- HAS A SCALAR MAGNITUDE
- HAS SPECIFIC PATTERNING

Slide 035: Scalar Resonance

Scalar resonance is not in the conventional textbook.

Scalar resonance is a particular zero-summed multi-resonance, electromagnetically, so that it does not act in an electromagnetic manner.

A scalar resonance is a standing electrogravitational wave. It can be made e**lectrically,** but it is not electrical in behavior.

In any scalar resonance, spacetime is curved, and it is the magnitude (and direction; of this spacetime curvature that is oscillating in "standing wave" fashion. In respect to stress of the vacuum medium, one half of a standing sine wave of scalar resonance is tensile; the other half is compressive. However, this is with respect to the local ambient stress of vacuum.

"Mass" of a particle is just a characteristic exhibited by a trapped scalar resonance. Usually this trapping is done by the "spin" of the individual particle.

The concept of "mass" may be compared to the concept of "capacitance." That is, a mass is an accumulator for scalar waves; that is, for scalar resonances. It is continually being "charged" and "discharged" by absorption and emission of sca**lar** waves from and to the ambient vacuum scalar wave flux.

Indeed, the magnitude of a mass may be defined in terms of the absolute value of this "switching" (absorption = switch in; emission = switch out) rate. In a very early paper I defined the mass of an object as proportional to the absolute value of the sum of the input and output switching rates, where each "switch" represents a change of action of h/(4). (Bearden, Quiton/Perceptron Physics: A Theory of Existence, Perception, and Physical Phenomena, Mar. 1973, AD 763210, available through NTIS.) In that scheme, one kilogram of mass equals a switch rate of 17.053 x 10^{50} switches per second. An object is in a Lorentz frame when the switch-in and switch-out rates are equal in a given direction. If, in addition, the in-out rates in all directions are constant, the object is "stationary" with respect to a Lorentz observer. If not constant in all directions, the object is in a curved spacetime with respect to a Lorentz observer. In that case either the object's local spacetime is warped or the object is in a generalized, accelerated frame.

In the normal linear spacetime, the "charging" and "discharging" are equal in all directions; hence the "mass" exhibited in any direction is the same.

With respect to an "external observer's" equilibrium flux, a moving object encounters an increased amount of flux rate along its line of motion, just as a moving object in a rainstorm encounters more raindrops per second in the direction of its path, than does a stationary object. Encountering increased scalar wave flux (with respect to the external observer) forces the moving object to absorb and emit scalar waves at a higher rate along its direction of motion than when it is not moving. Thus to the external observer, the mass of the object has increased, insofar as any disturbing force along its line of motion is concerned.

At right angles to its line of motion, however, the flux rate is precisely the same as when the object is at rest. Therefore the "mass" of the moving object with respect to any disturbing force at right angles to its line of motion has not changed, as seen by the external Lorentz observer.

Thus is explained both parts of one of the alltime great mysteries of special relativity: (1) how the mass of an object increases with respect to its motion, and (2) why the mass only increases with respect to its line of motion, and not at right angles to it.

The inertia of a particle is due to its mass, i.e., to the total magnitude of its trapped scalar resonance.

The gravitational attraction between two masses is due to their spacetime curvature. Further, mass is like a capacitance. It can trap additional scalar waves as trapped resonance; hence increase its magnitude or "inertial charge." Or, it can discharge more scalar waves than it absorbs; hence decrease its magnitude or "inertial charge."

Those scalar waves emitted from resonance are emitted as a pattern ensemble of the resonance. Hence they may be regarded as constituting a current of scalar resonance leaving the mass-accumulator-object. Scalar waves absorbed into trapped resonance may be regarded as constituting a current of scalar resonance into the mass-accumulator-object. Thus it is proper to speak of scalar resonance as being able to "flow."

Further, it is possible to increase the mass of an object directly, by transmitting scalar EM waves to it so that it absorbs them. (By "absorbing" scalar waves one means that more enter the object than leave it, so the object acts as an inertial accumulator charging up with inertial charge. This is done by insuring that the reference potential of the scalar wave transmitter is higher than the reference potential of the irradiated object.)

It is also possible to decrease the mass of an object directly, by transmitting scalar EM waves to it so that it emits more than it absorbs. (By "emitting" scalar waves one means that more leave the object than enter it, so the object acts as if it were an inertial accumulator that is discharging its inertial charge. This is done by insuring that the reference potential of the scalar wave transmitter is lower than the reference potential of the irradiated object.)

As can be seen, the scalar wave "transmitter" is actually somewhat comparable to a heat pump; it can either act as an "energy transmitter" or as an "energy extractor," depending upon the difference in potential between "transmitter" and "receiver."

Finally, scalar resonance can have a specific pattern: both in frequency and in spatial curvature aspects, as well as "rate of flow of time" aspects. Indeed, scalar-wise every object has its individual "scalar pattern" which is a unique fingerprint. Since that print is spatiotemporal, it is a product of the object's entire past history. Thus - scalar-wise - no two objects are identical.

This brings up another rather amazing potential: If a reasonably precise scalar pattern of an object can be "irradiated" and resonated with scalar waves, energy may be created in or extracted from the distant object, just as stimulating one tunning fork can excite another at a distance by sympathetic resonance. We leave it as an exercise for the reader to ascertain the relevance of this statement to clairvoyance, radionics, remote viewing, etc.

For the skeptic, however, we must point out that - rigorously - quantum mechanics requires that, continually, in any localized region of spacetime, the "pattern" of any object in the universe appears momentarily in the virtual state, purely from statistical considerations alone. So long as the situation remains statistical, any place in the universe can continue to have the "ghosts" of everything present there, in an ethereally thin pattern, and the observable world will not be affected by it. However, if one can discriminate and scalarly "charge" or "discharge" individual patterns in this "ghost-realm," action-at-a-distance is directly possible, as is materialization and dematerialization. If one accepts that even thought itself produces such virtual "ghost-patterns" in the virtual particle flux of vacuum, then it is at least theoretically possible to even materialize thoughts and thought images.

We have entered a new kind of reality where the old rules and the old limitations do not necessarily apply.



SCALAR RESONANCE CURRENTS

CURRENTS OF SCALAR RESONANCE CAN FLOW TO CHARGE A MASS WITH ADDITIONAL "MASS" AND "INERTIA," OR TO DISCHARGE IT.

Slide 036: Scalar Resonance Currents

As we pointed out, we can often greatly simplify matters by considering currents of scalar resonance. These currents flow from higher potential to lower potential, regardless of whether we are considering "transmission" or "reception."

Indeed, to "transmit at lower potential" is to receive, and to "receive at higher potential" is to transmit.

Thus the "transmitter-receiver" is a special system where simply biasing the two nodes differently determines which way the scalar resonance current will flow.

We may increase or decrease an object's inertia and mass, simply by properly biasing the transmitter-receiver system's two nodes.

In one accidental experiment of some hours in duration, Golden charged up an area so that, locally, all clocks became erratic. This included electrical clocks, battery-driven watches, wind-up kitchen clocks, and a pendulum-operated grandfather's clock. The rate of flow of time itself was apparently altered in the local area by the accumulated charge, which took some four days to drain off and discharge. At the end of the four days of discharge, all clocks and watches had returned to normal.



TRANSVERSE WAVE INTERFERENCE

Slide 037: Transverse Wave Interference

On this slide we show the orthodox representation of EM wave interference.

The chart is stylized since we assume two single-frequency EM waves that intersect and interfere in the indicated region.

In the interference zone, in-phase wave amplitudes add (constructive interference) while out-of-phase wave amplitudes subtract (destructive interference). In our stylized mode, we show the zero-summed locations as lines.

Conventionally, these interfering waves are considered to be transverse waves in vacuum.

The point is, in this scheme we think of "putting in the waves of finite amplitude, and creating the zero-amplitude regions by destructive interference." We create additional waves of increased-amplitude regions by constructive iterference.

Note that this view is only half correct. It addresses the electromagnetics, but not the gravitational aspects. Actually the regions of destructive EM interference are regions of constructive G-interference, and the regions of constructive EM interference are regions of destructive G-interference.



Slide 038: Transverse Wave Interference

Here we show the same interference situation, only now we think of transmitting scalar EM waves, which we model as longitudinal waves.

Again we assume two single-frequency scalar EM waves that intersect and interfere in the indicated region.

However, to an external observer, each of these waves individually appears to have zero E and H fields, hence to contain zero EM energy. That is, conventionally we seem to be transmitting waves of "pure potential," without any "force field" amplitudes whatsoever. We say we are transmitting waves of "artificial potential," since we deliberately constructed the zero-vector-summation scalar waves in the first place.

In the interference zone, a strange thing now happens. The relative magnitudes of the artificial potential of one wave with respect to the artificial potential of the other depend upon the phase relationship between the two. Further, whether the "gradient" so established appears negative or positive also depends upon the phase relationship between the two.

What results is most interesting: the out-of-phase condition now produces an EM gradient whose sign and magnitude are functions of the location within the interference zone.

Thus one now has real, non-zero EM potential gradients, both electrical and magnetic. And so real EM energy has emerged in an interference pattern within the area.

Ironically, we get essentially what we had before! Only now we have "put in the zero-reference lines, and produced the non-zero gradient (energy) zones."

In other words, we have recreated ordinary EM energy at a distance, directly from the interference of gravitational potential energy (anenergy).

And, to the laboratory observer, there has been no "EM wave" energy flow through the intervening space.

This was Tesla's secret of "wireless transmission of energy to a distance without losses."

Further, in a hypothetically perfect case, the interference represents a sort of "energybottle."

But now recall our need to take the sign of the scalar current into account. In this energy bottle, then, EM energy emerges and stabilizes - if and only if our transmitters are at higher reference potential than the ambient interference zone. If our transmitters are biased at lower potential, then energy is extracted from the energy bottle and re-emerges back at the transmitters, where it must be extracted and disposed of, if the transmitters are not to be burned out.

BACKGROUND FOR THE BRIEFER:

If we interfere two transmitters in a region of great energy -such as the molten core of the earth itself- and bias the transmitters negatively, we can extract enormous energy directly from that distant source!

Indeed, a slight variation of this effect is precisely how the Soviet Union obtains the enormous energy with which to power its incredibly powerful strategic "continent-buster"scalar EM weapons. Scalar frequency pairs - 12 kiloHertz **apart** - are transmitted into the earth itself on some portion of the earth's "giant scalar resonance" frequency curve. Biasing the two transmitters differently with respect to each other produces a high potential difference (voltage) between them. At the same time, biasing them both negative with respect to the earth's molten core produces a scalar resonance current from the core to the two transmitters. In the "outer loop" between the two scalar transmitters, there appears a gigantic voltage and gigantic electrical current that can be captured by appropriatemeans. This electrical power is tapped off and transmitted to incredibly powerful scalar EM weapon systems. There special accumulators and switchers are are utilized to provide the power of many Niagaras to each weapon.

Just before May 1, 1985 the Soviet Union performed a "full-up" operational test of their entire strategic scalar EM weapons complex. This test was detected and monitored periodically by Frank Golden. Some 27 of these giant Soviet "power taps" were locked into the molten core of the earth, producing forced (entrained) scalar resonance of the entire planet on 54 controlled frequencies under our very feet. The remainder of the scalar frequency spectrum was ablaze with literally hundreds of Soviet scalar transmitters: probably the entire strategic scalar command and control system to underwater submarines, higher command centers, distant commands, etc. was activated in the giant exercise.

For several days, the system was exercised on a mind-boggling scale, apparently as part of the Soviet Union's highly accentuated 40th anniversary celebration of the end of World War II.

Ironically, not a single U.S. intelligence agency, laboratory, or scientist detected this monstrous exercise for the new Soviet leader, Gorbachev. Not a one of them had a detector for scalar EM radiation, and not a one of them officially believes the exercise ever happened.


CREATING ENERGY AT A DISTANCE
SCALAR XMTR #1
VECTOR ENERGY ZONE (ENERGY BOTTLE)
SCALAR INTERFEROMETER
SCALAR XMTR #2

Slide 039: Creating Energy at a Distance

A most useful device is obtained if one uses a scalar interferometer where the two transmitters transmit beams that intersect at a distance.

In the interference zone, an energy bottle is created.

By biasing the transmitter reference potentials well above that of the distant energy bottle, EM energy emerges in that zone. In that case the interferometer is operating in the exothermic mode.

By biasing the transmitter reference potentials well below that of the distant energy bottle, EM energy is extracted from the distant zone and emerges from the transmitter. In that case the interferometer is operating in the endothermic mode.

If the transmitters transmit continuously, the effect in the distant zone is continuous.

If each transmitter transmits a pulse, and the two pulses meet in the distant intersection zone, then an explosive emergence or extraction of energy occurs at the distant interference zone, depending upon whether the interferometer is operating in the exothermic or the endothermic mode.


EXOTHERMIC MODE (SCALAR INTERFEROMETER)

Slide 040: Exothermic Mode (Scalar Interferometer)

For a scalar interferometer, "del phi" (the gradient of the potential) applies between the transmitter site and the distant intersection site, not to the intervening space in between. Thus one speaks of "energy flow" as being between transmitter and intersection, without any "in between." In the intervening space, all the energy exists as locked-in artificial potential, not EM force field energy (gradient bleed-off of potential).

In the exothermic mode, the ground potential of the transmitter is biased well above the ground potential of ambient vacuum. Energy enters the transmitter and "disappears", to "reappear" in the distant interference zone.

If continuous wave transmission is used, the energy continuously appears in the distant zone.

If pulse transmission is used and timed so that the two scalar pulses meet in the distant zone, energy explosively appears there.

If multiple frequencies are transmitted in the manner of a Fourier expansion of a particular geometric form, then a 3-dimensional energy form appears at the distant intersection. In this manner, a spherical or hemispherical shell (a globe of "dome" of EM energy) can be created at a distance. If pulse transmission is used, this will be an impulsive or explosive emergence of that energy form. If continuous transmission is used, this will be a continuous glowing form.

By feeding incredibly powerful transmitters with large amounts of energy extracted from the earth's molten core by "energy taps," very large spherical globes and hemispherical domes of EM energy can be created. The energy in the interference "shell" of such a sphere or hemisphere is sufficiently dense to lift Dirac matter from the Dirac sea of the vacuum. Thus the shell contains a glowing plasma.

Many such scalar howitzer signatures have been seen over the oceans, particularly over the North Pacific by jet airliners flying into and out of Japan. Also, such globes and domes of light have been seen deep within the Soviet Union, by observers in Afghanistan and by pilots of aircraft landing in Iran.

In the impulsive exothermic mode, a large visible flash will occur if EM energy in the visible spectrum is produced. "Flashes" in the infrared may similarly occur, if the emerging energy is in that spectral band. In September 1979 our Vela satellites detected such a large "nuclear flash" over the South Atlantic, off the southern coast of Africa. A second "nuclear flash" detected by the Vela satellites in 1980 was in the infrared only. Some years ago, a series of Momalous "flashes" and "booms" occurred off the east coast of the United States. These were due to the orientation and alignment -and registration - of one or more Soviet "scalar howitzers" - scalar EM interferometers in the exothermic mode.

Large "booms" occurred over the shuttle launch site at Cape Canaveral, associated with three shuttle launches prior to the end of November 1985. These were tests of such exothermic scalar EM howitzers, being tested as part of the Soviet Launch Phase ABM system. In that mode, the scalar pulses from the two transmitters are injected into special zero-reference scalar EM "channels" established in the EM carriers of the Woodpecker over-the-horizon radars. The scalar pulses travel through these channels, traveling in the ordinary EM beam of the transmitter and following it in its curvature around the earth in the earth-ionospheric waveguide. The scalar pulses are timed, phased, and oriented so as to meet the rising shuttle. In these tests the transmissions were offset in time so the shuttle would not actually be destroyed, but the system could be tested against actual shuttle launches in the U.S.

The specific uses of these various exothermic modes will be covered in later parts of the briefing.


ENDOTHERMIC MODE (SCALAR INTERFEROMETER)

Slide 041: Endothermic Mode (Scalar Interferometer)

In the endothermic mode, the bias on the transmitters is such that energy is extracted from the distant intersection zone, to re-emerge at the transmitters. There the energy must be caught and disposed of if it is not to burn out the transmitters. When very large amounts of energy are extracted from distant points, the Soviets often use a "dump" method of temporarily capturing, and storing in an accumulator, the heat energy emerging at the transmitters. A "scalar energy tap" established into the accumulator then feeds a second howitzer in the exothermic mode. This howitzer is focused on a distant dumpsite - often Bennett Island, where U.S. weather satellites continually observe exhausts.

In the impulsive endothermic mode, energy is impulsively extracted from the distant intersection zone. In the atmosphere this results in a very sharp cooling, or a "cold explosion." It also results in the type of boom and rumble often associated with thunder after a lightning bolt.

On April 9, 1984 the Soviet Union tested such a "cold explosion" off the coast of Japan, near the Kuril Islands. In the suddenly induced low pressure "cold zone" above the ocean, ocean water was sharply sucked up from the ocean, forming a dense cloud. Then air rushing in to the low pressure zone forced the cloud upward, forming a mushroom much like that of an atomic explosion in visual appearance, except for the absence of a flash and the absence of a giant shock wave moving out away from the site of the explosion. (In this case the

Soviets controlled the rise time of the pulse so that no "giant atmospheric boom" occurred.).

As the cloud rises, it expands by mixing - very similar to a giant thunderhead buildup, except much faster. In this case the cloud rose to 60,000 feet in about 2 minutes, spreading out until it reached a diameter of about 200 miles. The pilots and crews of several Boeing 747 jet airliners in the general vicinity saw the incident. Sometime after that, a U.S. weather satellite photo of the area occurred. The cloud in that photo has an anomalous density distribution, differing from that of all other clouds in the area.


TESLA'S "BIG EYE" FOR REMOTE VIEWING
CAN BE FOCUSED TO A SPECIFIC DEPTH IN THE EARTH, THE OCEAN, OR INSIDE AN ENCLOSURE.
SCAN
SCALAR RCVR/XMTR
SMALL NEGATIVE BIAS
TARGET EXTRACTION ZONE
SCANNED INTERFERENCE SCREEN
SMALL NEGATIVE BIAS
SCALAR RCVR/XMTR
SCAN

Slide 042: Tesla's "Big Eye" for Remote Viewing

Nikola Tesla also planned a very special use for his endothermic scalar interferometer. He planned to produce what he called his "big eye to see at a distance."

This is accomplished as shown on the diagram. First, the system is only weakly endothermic, so that only a small amount of energy is extracted from the **distant** target. Also, the beams are "scanned" by an open receiver, timewise, from side to side and top to bottom. By scanning yet another single beam through the intersection zone and phasing its pulses, an even better representation can be obtained. Thus the receiver produces a representation of the energy extracted from various locations within the distant endothermic zone. By displaying the received signals on an appropriately scanned screen, a representation of the distant scene in the intersection zone can be created. Indeed this is a special kind of "microwave interferometry," and - with modern techniques - the imagery obtained might be surprisingly good. With development, it might even become as good as the image presently obtained by side-looking acquisition radars.

Interestingly enough, since scalar EM beams will easily penetrate the earth or the ocean, one can also look beneath the earth or beneath the ocean with this type of scanning scalar interferometer.

The importance of this capability to strategic and tactical reconnaissance is obvious. Camouflage, cover, and concealment have no effect on such a **system.** One can easily look inside buildings and into underground facilities. With a small system such as this, the U.S. Marines at Khe Sahn would have had **little** difficulty locating the tunnels continually dug under the perimeter by the Viet Cong. And targets under jungle canopies are directly visible.

BACKGROUND FOR THE BRIEFER:

It requires little imagination to see that this system is easily adapted to produce an "underwater radar." With such devices, the problem posed by the underwater nuclear submarine is solved. For example, an entire area can be continually searched, much like acquisition radar systems do now. A submarine can be detected and tracked, and none of its ordinary detectors will detect anything out of the ordinary. By using a separate pair of beams in the exothermic mode, powerful scalar pulses can be fired at the distant sub, intersecting at the submarine in a violent EMP throughout the sub and its armament. Thus the sub and all its missiles are destroyed instantly.

Or, continuous exothermic transmission can be used by the targeting weapon at lesser power, gradually interfering with the sub's electrical systems and causing it to lose control. The sub then sinks to crush depth and implodes.

Precisely that scenario seems to be what happened on April 10, 1963 to the U.S.S. Thresher nuclear submarine. It left a signature: the sub's surface companion, the nearby U.S.S. Skylark, was in the "splatter zone" of the underwater scalar interference. That is, spurious EM noise was being generated In all the Skylark's electrical systems, some of which were actually disabled. So intense was the "electronic jamming" that it required over an hour and a half for the Skylark to transmit an emergency message back to its headquarters that the Thresher was in serious trouble and contact with it had been lost. Some of the Skylark's communication systems actually failed, but later resumed operation inexplicably, once the jamming was gone. That type of "jamming" of multiple bands and multiple electronic equipments, of course, together with the anomalous failure of electronic equipment and its later mysterious recovery, were direct signatures of the use of the exothermic scalar interferometer against the undersea target area in the vicinity of the Skylark.

The very next day, Apr. 11, 1963, the same Soviet scalar EM howitzer system was tested in the "destroy submarine" pulse mode. A huge underwater EM blast occured off the coast of Puerto Rico, about 100 miles north of the island. The underwater explosion caused a huge boiling of the surface of the ocean, followed by the rising up of a giant mushroom of water about a third of a mile high. The mushroom of water then fell back into the ocean, completing the signuture.

Fortunately the startled crew of a passing U.S. jetliner that was just passing its checkpoint in that area saw the entire incident. (See Robert J. Durant, "An Underwater Explosion - or What?", Pursuit, 5(2), April 1972, p. 30-31.)

These two incidents were full-up operational tests of Khrushchev's newly deployed superweapons. He probably staged this dramatic one-two punch in a desperate effort to recover face with the Communist Party after his disastrous facedown by Kennedy in the Cuban Missile Crisis a few short months previously. Apparently the attempt was successful, since he remained in power another year before being deposed.


SITE OF MYSTERY CLOUD
SOVIET UNION
SEA OF OKHOTSK
KOREA
SAKHALIN I.
KAMCHATKA PEN.
JAPAN
KURIL I.
APPROXIMATE LOCATION OF CLOUD
LOCATION OF JAL FLIGHT #36 WHEN PILOT SAW CLOUD

Slide 043: Site of Mystery Cloud

On this slide we show the location of the "cold explosion" off the coast of Japan on April 9, 1984. The site of the explosion was only about 200 miles from downtown Tokyo. The crews of several jet airliners, including Japan Air Lines Flight 36, saw it.



Slide 044: Mushroom Cloud from Sea off Japan near Russian Test Area

A short time before, the Soviets had hastily announced missile tests would be conducted into a zone some distance away from the cold explosion site. This may have been intended as deception to cover this incident, should any foreign nation indicate they understood what was going on.

It also was a direct "stimulus" to the Japanese and the rest of the world: That is, stimulate the system and see if the scientists recognize what happened. If they do, then they know about scalar EM weapons. If they don't, then their countries know nothing of scalar EM weapons, and those countries are defenseless against them.

At any rate, at about 5:14 a.m. Pacific Standard Time on April 9, 1984, a **giant** mushroom cloud erupted above the ocean south of the Kuril Islands. The mushroom rose rapidly, expanding as it rose. In two minutes it had reached **an** altitude of 60,000 feet and a diameter of about 200 miles.

One pilot of a Boeing 747 who observed the cloud was a former B-52 bomber pilot. He described the cloud as very similar to a mushroom cloud from a gigantic nuclear explosion, except there was no flash of visible light. Taking evasive action, he turned off course away from the blast, and braced for a blast shock wave, which never came.



MUSHROOM CLOUD RISING FROM SEA (COLD EXPLOSION)

- 0514 HOURS, 9 APRIL 1984
- GRAY-WHITE CLOUD APPEARED
- ROSE 60,000 FT IN 2 MINUTES
- 180 MILES S.E. OF HOKKAIDO
  200 MILES FROM TOKYO
  SOUTH OF KURIL ISLANDS
- SOVIET MISSILE TESTING SCHEDULED
  ABOUT 350 MILES AWAY
  AT 2100 HOURS, 9 APRIL 1984

Slide 045: Mushroom Cloud Rising from Sea

Indeed, this highly anomalous cloud was due to a cold explosion - a test of a Soviet scalar EM howitzer in the pulsed endothermic mode.

In the weapon's targeted interference zone, EM energy (heat) was rapidly withdrawn when the biased endothermic extraction occurred. Above the ocean an intense low-pressure zone was created. Water from the ocean was sucked up, as if by a giant vacuum cleaner. The water was violently broken into droplets, forming a dense cloud, with a strong upward momentum.

The surrounding higher-pressure air rushed into the low-pressure zone, pushing the rising dense cloud of water vapor upward as its upward momentum continued. Mixing caused rapid expansion of the rising cloud, causing its density to thin measurably as it rose and expanded. An effect very similar to the formation of a strong thunderhead resulted, except much faster.

The mixing cloud also resembled the mushroom cloud from a giant nuclear explosion, just as an emerging thunderhead does.

But no outward blast wave resulted as does from a nuclear explosion. Also, no visible flash occurred, probably as a result of deliberate design by the Russians.

Thus a beautiful "stimulus" and test was conducted: quite a few airliners were "pinged," providing a high-level stimulus to competent observers. The news was sure to be reported by them to several nations. The press was sure to pick up the story. This was a high order stimulus to see whether the U.S., Japan, or other potential adversaries of the Soviet Union recognized the testing of a cold explosion weapon.

By our reaction, we assured them (with high confidence) that we still knew nothing of scalar EM interferometry or cold explosions.



MUSHROOM CLOUD FROM SEA OFF JAPAN

- FIVE BOEING 747s FLEW THROUGH OR NEAR THE CLOUD
  - NO CONTAMINATION
  - NON-NUCLEAR
- OCEAN 21,000 FEET DEEP
  - TOO DEEP FOR SUBMARINE VOLCANO TO CAUSE CLOUD
  - INDICATES MAN-MADE PHENOMENON

Slide 046: Mushroom Cloud from Sea off Japan

Five Boeing 747's flew through or near the cloud on their way to Anchorage, Alaska. The aircraft were checked at Anchorage for radioactive contamination, but nothing was found. This showed that the huge "explosion" had been non-nuclear.

The ocean in the area is also about 21,000 feet deep. That is really too deep for a submarine volcano to have erupted and caused the cloud. (Besides, a volcano would have continued to snort at least a bit, and so that appears to be out of the question as a possible cause of the incident.)

In short, a manmade phenomenon is indicated.

Indeed, we know it was a cold explosion. As I've stated previously, a colleague has in fact produced the basic effect over a dish of water in the laboratory, using a small scalar interferometer in the endothermic mode.



NOT A KNOWN NATURAL PHENOMENON

- DR. DANIEL A. WALKER ET AL
- GEOPHYSICIST, UNIV. OF HAWAII
- MONITORS ARRAY OF HYDROPHONES
  - ON OCEAN BOTTOM
  - RECORDS SIGNALS (SEISMIC, VOLCANIC)
- DATA SHOWS ABSENCE OF ANY NATURAL SEISMIC OR VOLCANIC EVENT THAT COULD HAVE CAUSED THE APRIL 9 PHENOMENON OFF THE COAST OF JAPAN
- PUBLISHED IN SCIENCE

Slide 047: Not a Known Natural Phenomenon

Further, the story does not end there.

A geophysicist at the University of Hawaii, Dr. Daniel A. Walker, together with his colleagues monitor an array of hydrophones on the ocean bottom, recording signals such as seismic incidents, volcano eruptions, etc.

Dr. Walker and his colleagues performed a comprehensive analysis of the data recorded by the hydrophones in and around the time of the incident in question. The data shows the absence of any natural seismic or volcanic event that could have caused the April 9th phenomenon off the coast of Japan.

He and his colleagues concluded that it was either an as yet unknown natural phenomenon, or a man-made phenomenon.

Their report is published in Science. (Walker et al, "Kaitoku Seamount and the Mystery Cloud of 9 April 1984," Science, 227(4687), Feb. 8, 1985, p. 607-611.)



EXPLOSIVE EVENTS SEEN ON SOVIET ISLAND

Slide 048: Explosive Events seen on Soviet Island

Here are two U.S. weather satellite photos of the anomalous exhausts on Bennett Island we previously referred to.

The exhaust in the left picture is about 150 miles long, and is nearly horizontal (about 1.5 degrees above the horizontal). It is entirely consistent with the continuous exhaust from a "dumping transfer" scalar EM howitzer in the continuous exothermic mode. (The primary howitzer, of course, was activated in the endothermic mode.)

I think any open-minded investigator must admit that that is indeed a very powerful jet-like exhaust, and not like anything one ever sees from a natural volcano or geological gas vent. If anyone knows of such an anomalous volcanic or geological exhaust, I would be most delighted to see a photo or report. To my knowledge, no such natural photo exists, and no such natural exhaust has ever **been** reported.

The right picture shows the "puff of an explosive emergence of the exhaust. In other words, this one is the exhaust from a "dumping transfer" howitzer used in the pulsed exothermic mode. Since it did not have so much energy to dump, it could dump it in a pulse. Again, the primary howitzer, of course, was activated in the endothermic mode.

Over 100 weather satellite photos of these anomalous exhausts have been taken since 19**74.**

One or more U.S. aircraft have even been vectored through the exhausts, and samples of the exhaust taken and analyzed. The exhaust is made up of a little clay and mud and water, and is colder than the surrounding air.

EXPLOSIVE EVENTS SEEN ON SOVIET ISLAND



Slide 049: Explosive Events seen on Soviet Island

U.S. weather analysts euphemistically call these exhausts from Bennett Island plumes.

Here is another U.S. weather satellite photo, showing the twin emergence of multiple puffs.

One might expect such exhausts if the secondary "dumping transfer" howitzer is operated in the continuous mode, with continuous extraction by "power tapping" the accumulator of the primary howitzer. In that case, the signature of the exhaust would expose the operation of the primary howitzer. For example, this exhaust would indicate multiple puffs, hence probably multiple frequencies and multiple primary transmitters, each phased in a controlled manner. That of course indicates the production of Fourier expansion forms - of 3-dimensional geometrical forms - by the primary howitzer(s). Since these are puffs, it may indicate the explosive formation of distant spherical balls of energy by the primary howitzer. This in turn indicates the use of a howitzer system in the "pulse firing" mode, which can be used against missiles, ships, aircraft, ground targets, armored vehicles, underwater targets, etc.


EXPLOSIVE EVENTS SEEN ON SOVIET ISLANDS
0 500 1000 km
0 500 1000 mi
Arctic Ocean
Wrangel Is.
Bennett Is.
Bering Strait
UNITED STATES
Bering Sea
U.S.
North Pacific Ocean
Barents Sea
Novaya Zemlya
SWEDEN
FINLAND
Murmansk
Petrozavodsk
St. Petersburg
Arkhangel'sk
MOSCOW
Nizhniy Novgorod
Kazan'
Yekaterinburg
Volgograd
Chelyabinsk
Astrakhan'
Omsk
Novosibirsk
Krasnoyarsk
Irkutsk
Noril'sk
Ural Mts.
Siberia
Lena
Yakutsk
Magadan
Sea of Okhotsk
Amur
Kholmsk
Khabarovsk
Nakhodka
JAPAN
050

Slide 050: Explosive Events seen on Soviet Islands

This slide shows the location of three areas of interest relative to Soviet scalar EM weapons testing.

Wrangel Island, north of the northeastern portion of the Soviet mainland, is associate with tests of these weapons in large circular breakups of the ocean's ice cover. This of course could aid submarines that wished to surface and fire cruise missiles, or submarines that wished to fire from underwater and needed the **ice** broken up.

Strangely enough, Wrangel Island has a most peculiar history: legally it still belongs to the U.S., but has been "given" to the Soviet Union without permission of the U.S. Senate, which is illegal.

Bennett Island, a little farther to the west and still north of the Soviet **mainland,** is noted for its phenomenal number of anomalous exhausts as previously discussed.

North of the Soviet mainland and near its middle lies the large island of Novaya Zemlya. Weather satellites have taken pictures of anomalous circulations over this island, which are further candidates for exhausts from scalar EM howitzer operations.


CREATING A SPATIAL 0-FIELD PATTERN

TRUNCATED FOURIER EXPANSION (3D)

$$y = y_0 + f_1(\lambda_1) + f_2(\lambda_2) + \ldots + f_n(\lambda_n)$$

$$z = z_0 + g_1(\lambda_1) + g_2(\lambda_2) + \ldots + g_n(\lambda_n)$$

NOTE:
INTERFERENCE OF TWO SUCH SCALAR HEMISPHERES CREATES A "GLOWING HEMISPHERICAL SHELL"

Slide 051: Creating a Spatial 0-Field Pattern

On this slide we show that a hemispherical dome (or other regular shape) can be composed from scalar waves by 3-dimensional Fourier expansion. By truncating the expansion - say after 10 or 12 frequency terms - a good representation of **the** desired form can be obtained with a practical number of frequencies, and in turn a practical number of transmitters. A computer is used to compute the multiplying functions for each frequency, and the entire complex of frequencies is **then** transmitted to produce the scalar form. By interfering two such scalar forms, a 3-dimensional shell of locked-in, ordinary EM energy is formed in **space.**

Interference of two such scalar hemispherical surfaces creates a "glowing hemispherical shell or dome of energy."

Interference of two such scalar spherical surfaces creates a "glowing spherical shell or globe of energy."

Both such geometric forms have been repeatedly seen.



Slide 052: Tesla Shield

Of particular interest is the hemispherical shell of energy, which years ago I dubbed the "Tesla shield."

As shown on this slide, two scalar hemispherical surfaces are created, using multiple frequency transmitters and truncated Fourier series expansions. Interference of the two scalar hemispheres creates a great, glowing hemispherical shell of ordinary electro-magnetic energy. In the shell, the energy density is sufficient to lift Dirac matter from the Dirac Sea of vacuum. The shell is thus filled with a glowing plasma.

Such a shell may be several hundred miles in diameter at the base. The enormous energy required to form such a defense shell is obtained by a "scalar power tap" into the molten core of the earth itself, as previously explained. In late April/early May of 1985, 27 such "power taps" were placed in the earth by the Soviets. If each tap is capable of powering four to six large scalar EM weapons, then the Soviet strategic scalar EM arsenal contains over 100 monstrous superweapons capable of generating exothermic explosions, endothermic explosions, engineering the weather, locating and destroying underwater submarines, detecting and destroying ballistic missiles shortly **after** launch, detecting and destroying long range strategic bombers as soon as they are airborne, etc.

At any rate, the giant Tesla shield is useful against any penetrating vehicle. If the shell is not so large, its energy density may be very high. In **that** case, **the intense** plasma heating will fuse and even vaporize metallic bodies. In addition, any vehicle encountering the shell is subjected to an extremely intense EMP arising everywhere inside its circuitry. EM shielding is of no use against the creation of energy throughout the spacetime of the circuits; such shielding only helps against energy flow through space in the conventional sense.

Thus the electronics of any vehicle encountering the shield are instantly dudded, whether or not they are shielded against ordinary electromagnetic interference (EMI). This includes the electronics operating a nuclear warhead, carried by a re-entry vehicle. Electrically everything penetrating the shell is totally dudded. Further, explosive materials are exploded when such an EMP is encountered, and combustible materials are fiercely consumed or set afire. Ablative shielding suffers an interesting catastrophe: since energy does not try to "flow into" the shielding but "arises everywhere in it simultaneously", "ablation" occurs everywhere throughout the ablative material, simply exploding it instantly. In addition, for smaller Tesla shells (say of 50 miles diameter) the energy density is sufficient to melt or vaporize metals such as in missile structures.

With such a Tesla shield, there is no need to discriminate true warhead-bearing re-entry vehicles from decoys, chaff, etc. The entire "mess" entering the shield is simply "cleaned up" and "sterilized" or destroyed. The shield can take care of ICBMs/IRBMs and their nuclear warheads, strategic bombers and their nuclear **bombs,** cruise missiles and their nuclear warheads, re-entry vehicles and their warheads, decoys, chaff, etc.



Slide 053: Expanding Dome-like Phenomenon

Here we show one instance of apparent Soviet testing of the Tesla shield (hemispherical shell of energy) over the ocean. This incident occurred in the Caribbean and Western North Atlantic Ocean on Mar. 20, 1969 and is reported in the Marine Observer, Vol. 40, 1970, p. 17. A semicircle of milky white light, quite intense at first, was sighted on the horizon. The semicircle enlarged, dimming as it expanded. The incident lasted for about 10 minutes. Seen from a passing ship, the top of the hemisphere reached a sighting elevation angle of about 50 degrees, while the base of the hemisphere of light subtended an arc of about 70 degrees. This is directly indicative of a test of the Tesla shield, first as a small, more intense shield and then expanding to greater size for a less intense shield whose primary destructive mechanism is EMP. Note that the EMP in a Tesla shield is locally contained in the energy-bottle shell. It is not an ordinary EMP of energy radiated out of the shell.


HEMISPHERE & GLOBES 1977
MODERATELY LUMINOUS HEMISPHERE FORMED IN APPROXIMATELY THREE MINUTES
SECOND LUMINOUS PATCH(S)
FOR TEN SECONDS SEARCHLIGHT SHINED DOWN BRIGHT LUMINOUS PATCH
30 DEGREES
DISAPPEARED AFTER APPROXIMATELY TEN MINUTES
40 DEGREES
MARINE OBSERVER VOL 48:Pg.21-22, 1978
054

Slide 054: Hemisphere & Globes 1977

Here is a second instance of apparent Soviet testing of the hemispherical Tesla shield over the ocean. This time it is combined with simultaneous testing of two smaller scalar interferometers creating Tesla globes of EM energy.
This incident occurred at 23 degrees 5 minutes north, 17 degrees 25 minutes west. It was sighted and reported by a British ship, H.M.V. Kinpurnie Castle, on Mar. 24, 1977. The report is in the Marine Observer. Vol. 48, 1978, p. 21-22.

First a large, moderately luminous hemisphere of light formed, requiring about 3 minutes to do so. Seen from the ship, the top of the hemisphere was at a sighting elevation angle of about 30 degrees, while the base subtended an arc of about 40 degrees. This was the basic Tesla shield.

Then two other luminous globes or patches of light, each of about 1 degree diameter as seen from the ship, formed in the same area; one inside the shield and one outside it. From the glowing globe inside the shield, a light beam similar to a giant searchlight shone down to the ocean's surface for about 10 seconds.

Again the phenomena lasted about 10 minutes and then disappeared.

The luminous globe or patch inside the hemisphere might be the test of a second weapon deployed from a Soviet aircraft in the area. If so, the aircraft has placed a **strong** spherical shield around itself. In addition, the aircraft is utilizing some sort of scalar interferometer beam weapon in an underwater mode. Probably this would imply a "shot" at a hostile nuclear submarine inside the shielded zone. Thus this aircraft would have the scalar EM equipment to search for the underwater sub and detect it, and also to concentrate interference energy upon it underwater, destroying it quickly.

Suffice it to say that it is possible to perform scalar interferometry by means of a single beam, in a proprietary process discovered by a close colleague. Thus the "glowing beam to the ocean" resembling a searchlight makes very good sense in the anti-submarine role. The same weapon, of course, could also attack any hostile surface vessel that might have been inside the shielded area at its formation.

The second luminous globe or patch, outside the hemisphere, is probably from a second scalar interferometer from the naval task force, simulating the continuous attack of a certain target (missile or aircraft) outside the protective dome.

As can be seen, this phenomenon is directly indicative of the types of operations one would expect from the testing of Soviet scalar EM weapons at sea, possibly to protect a Soviet naval task force during simulated combat operations.



SARYSHAGAN DIRECTION, SEPTEMBER 1979 (SEEN FROM AFGHANISTAN)

MULTIPLE EVENTS SEEN
IN SEPTEMBER 1979
FROM AFGHANISTAN

STRANGE LURID GLOW
THAT FLARED SILENTLY
OVER THE HINDU KUSH;
AS DESCRIBED BY
NICK DOWNEY.

THE SUNDAY TIMES
AUGUST 17, 1980

WITNESS TO A
SUPER-WEAPON?

Slide 055: Saryshagan Direction, September 1979

The London Sunday Times of 17 August 1980 contained information and a photo-sketch of incidents of sighting of the testing of very large Tesla globes deep within the Soviet Union. British war cameraman Nick Downie made the sightings from Afghanistan. The phenomena seen were in the direction of the Saryshagan Missile Test Range, which - according to the U.S. Defense Department's Soviet Military Power, 1986 - contains one or more large directed energy weapons (DEWs).

Even though Downie was seeing the giant globe of light from a great distance, it flared silently over the Hindu Kush and expanded to subtend an arc of about 20 degrees, dimming as it expanded. (An arc of 20 degrees subtended by an object many hundreds of miles distant indicates an object of well over a hundred miles in diameter. This gives some idea of the enormous energy being controlled and manipulated by these Soviet weapons.).

Downie saw the sight on more than one occasion in September 1979.

BACKGROUND FOR THE BRIEFER:

In the same month - September 1979 - a stationary luminous globe containing a vertical stripe of black in the center was seen in the sky off Saint Petersburg, Florida. This particular type of sighting in that area has been previously correlated with times of known activity at Saryshagan.

Further, in the same month U.S. nuclear-warning Vela satellites detected a mysterious "nuclear flash" over the South Atlantic, off the coast of Africa. Controversy has raged in U.S. intelligence and scientific circles to this day as to whether a nuclear explosion or some other mechanism produced the flash.

Indeed, the flash may have been produced by a scalar EM howitzer from Saryshagan as one more "ping" of the U.S. intelligence system, to ascertain whether or not it knew anything about scalar EM howitzers. Again, the negative response told them with high confidence that (1) we still didn't know about scalar EM stuff, and (2) we were still absolutely defenseless against the Soviet scalar EM weaponry.

In 1980, a second "Vela flash" was reported. This time it occurred in the infrared region only, which positively rules out any sort of nuclear explosion. Even this increased stimulus still evoked a U.S. action that revealed total ignorance of scalar EM weaponry.

An alternate possibility for the September 1979 Vela flash also exists: countries not hostile to the U.S. may have tested a scalar EM weapon that produced the flash.

At any rate, from Downie's sightings, it is highly probably that the DEW weaponry at Saryshagan Missile Test Range was active in September 1979, and was producing huge Tesla globes. If the DEWs at Saryshagan can produce the giant luminous Tesla globe, they almost certainly are scalar EM interferometers and can produce the giant Tesla shields as well. Downie reported other earlier sightings of similar phenomena seen by Afghans deep within the Soviet Union in the same direction toward Saryshagan.

Briefly let us cover the uses of such a "giant globe" or spherical shell of glowing EM energy and plasma.

By placing such a "giant globe" thousands of kilometers out away from the defended heartland, an entire arc of the sky can be defended against long-range ballistic missile attack in midcourse. During their midcourse trajectory, the attacking missiles would have to penetrate the globular shell twice, exposing them to giant internal EMPs twice. A very high probability thus exists that all missiles entering the space occupied by the globe are dudded upon entry and/or exit. This includes the electronics inside the nuclear warheads themselves. Also, this is particularly effective against MIRV and MARV missile carriers, since the multiple re-entry vehicles are normally still on the main vehicle during most of midcourse. The use of this midcourse ABM globe defense greatly reduces the number of vehicles arriving at the latter part of midcourse and at the terminal phase of their trajectory.

By using a smaller, more intense globe and placing it on incoming clusters of objects or single objects, both EMP and intense local heating are used against the objects. This is suitable in the latter part of midcourse and in the **terminal** phase of ICBM's, IRBM's, SLBM's, and cruise missiles. It is also useful against incoming strategic bombers and their air-to-surface missiles, both ballistic and cruise.

Two modes of the globes - especially the small ones - can be used. First, the continuous mode can be used to "fry" or vaporize incoming objects in a relatively small volume (say two or three tens of kilometers in diameter). Second, the "pulse" mode can be used to "service" all incoming objects, whether or not they have passed through the "large globe" midcourse defense. This provides an additional guarantee of killing the objects; discrimination is not required, just service all of them. The exposure of all incoming objects to multiple attacks raises the probability of kill to essentially 100%, or as close to that as one wishes. Of course the incoming vehicle may still encounter a terminal defense consisting of the Tesla shield and associated roving "quickshot" small intense globes.

In short, with these systems an essentially 100% ABM and anti-bomber defense is possible. Further, the Soviets have possessed such an effective defense for two decades, just as they have openly stated.



CONTINUOUS TESLA EMP GLOBE

TEHERAN, IRAN
JUNE 17, 1966

SEEN FROM NEAR
MEHRABAD AIRPORT

OBSERVED BETWEEN
4 TO 5 MINUTES

SEEN BY TWO AIRCRAFT

ARTIST'S CONCEPT

Slide 056: Continuous Tesla EMP Globe

Here is another verified incident of a gigantic test of a Soviet scalar EM howitzer deep within the Soviet Union.

This is a CIA report, released under the Freedom of Information Act. One can be quite sure that the incident occurred as stated.

The phenomenon was seen from two aircraft approaching Mehrabad Airport in Teheran, Iran on June 17, 1966 and reported by their pilots.

On the far horizon deep within the Soviet Union, an intense spherical ball of light appeared, "sitting on the horizon" so to speak. The globe of light increased to enormous size, dimming as it did so, literally filling an arc of the distant sky as it expanded. The sighting was shielded from most ground observers' view at the airport itself due to an intervening mountain range that masked most of the phenomenon from the ground.

The silent, expanding globe was observed for four or five minutes before it faded away.

BACKGROUND FOR THE BRIEFER:

Again, this is positive evidence of the testing of a giant scalar EM interferometer, in the "midcourse ABM globe" type of action.

However, note the date - mid 1966! The Soviets have therefore been testing such scalar weapons of enormous size and power for at least two decades. This implies that development must have started at least a decade earlier, or in the mid '50s.

Still earlier in January 1960 Nikita Khrushchev had announced the development of a "fantastic" Soviet weapon, one that could even destroy all life on earth if unrestrainedly used. In 1962 the ebullient Khrushchev was forced to back down and lose face before John Kennedy in the Cuban Missile Crisis. Khrushchev's missiles and bombers were in woeful shape, as Kennedy well knew (by courtesy of the Soviet spy, Colonel Oleg Penkovsky). Kennedy did not know that Khrushchev's new superweapons were nearing deployment, but were not yet quite ready.

To save face and prevent his immediate ouster, Khrushchev apparently conducted a startling two-strike demonstration of his new weapons as soon as they became operationally ready. On April 10, 1963 he detected and destroyed **the** U.S.S. Thresher nuclear submarine using a scalar EM howitzer in the underwater "continuous" mode.

The next day he demonstrated the "pulsed" underwater destruction mode for **nuclear** subs by producing a giant underwater EM explosion underneath the ocean 100 miles north of Puerto Rico. Ironically, just as the Atlantic was coming a**live** with U.S. naval vessels searching for the lost Thresher, a second test of the weapons that had finished off the sub occurred to the south of them, unnoticed and disregarded, even though seen and reported (to the FBI and the U.S. Coast Guard) by a passing U.S. jetliner's pilot and crew, who observed the underwater explosion.

We thus can peg the development of these weapons by the Soviets as starting **well** before 1960. The first operational deployment of the giant strategic weaponry occurred in early 1963.

Note that the 1966 testing observed here is completely consistent with this estimated development schedule.

Thus large Soviet strategic scalar EM weapons have been operational on site for 23 years! This implies that at least three additional generations of the scalar EM weapons have been developed and deployed by now.



MYSTERIOUS LIGHT OVER NORTH PACIFIC

SEEN FROM 42° N LAT, 153° E LONG

JUNE 18, 1982
OBSERVED IN
NORTHERN PACIFIC
700 KM EAST OF KUSHIRO

SEEN BY TWO AIRCRAFT:
JAL FLIGHT 403
JAL FLIGHT 421

NOTE:
SUCH INCIDENTS ARE
REPEATEDLY SEEN BY JETLINER
CREWS OVER THE NORTH PACIFIC

ASAHI EVENING NEWS, TOKYO
JUNE 22, 1982

Slide 057: Mysterious Light over North Pacific

Incidents of Soviet testing of the Tesla shield and the Tesla globe weapons are routinely observed by airline pilots flying over the North Pacific into and out of Japan.

This is one typical example. Two jetliners, Japan Air Line flights 403 and 421, sighted and reported a large glowing globe of light sitting just beyond the horizon and extending well above it. The aircraft were in the vicinity of 42 degrees N latitude and 153 degrees longitude at the time. The sighting was thus about 700 miles east of Kushiro.

The pilots estimated the diameter of the ball as at least 18-27 kilometers. Depending upon the actual distance to the sphere, it may have been of much larger size.

This incident is reported in the Asahi Evening News, Tokyo, June 22, 1982.

The jet airliner pilots flying over these waters have reported many other **similar** sightings.


2115
2120
OBS ELEV.
24° 30'
2125

WHITE SPHERE SEEN IN NORTH ATLANTIC 1976

JUNE 22, 1976
2113 — 2140 HOURS
OBSERVED IN NORTH ATLANTIC

- 2113: ORANGE GLOW BEHIND CLOUDS
- 2115: WHITE SPHERE OBSERVED ALT 10°, BEARING 290°
- WHITE SPHERE DEVELOPED AS SHOWN
- STARS COULD BE SEEN THROUGH SPHERE AT ALL TIMES
- BY 2140 THE SPHERE HAD DISAPPEARED

MARINE OBSERVER, 47:66, 1977

Slide 058: White Sphere seen in North Atlantic 1976

Here is another sighting closer to home.

This incident was observed from a passing ship on June 22, 1976 in the North Atlantic, at about 2113-2140 hours. It is reported in the Marine Observer, Vol. 47. 1977, p. 66.

First, an orange glow was sighted behind some distant clouds. A couple of minutes later, a glowing white sphere of light was observed to the left of the orange glow, just above the clouds. The white sphere then slowly expanded to a much larger sphere, dimming as it expanded. At its maximum size, the top of the white sphere reached about 24 degrees 30 minutes elevation angle to the observer. Development to maximum size required about 10 minutes.

By 2140 hrs the sphere had faded and disappeared. The sphere was sufficiently thin that the stars could be seen through it at all times.

Again this incident strongly fits the large Tesla globe mode of a Soviet scalar EM interferometer.

The significance and role of the orange glow are not known at this time.



CONTINUOUS TESLA FIREBALL

SEPTEMBER 10, 1976
BETWEEN
MOSCOW AND LONDON

SEEN BY
BRITISH EUROPEAN AIRWAYS
FLIGHT 831

CIA REPORT
RELEASED UNDER FOIA

Slide 059: Continuous Tesla Fireball

Here is another incident that represents a stimulus to the British government, to see if the British are aware of scalar electromagnetics.

Again, this is a CIA report released under the Freedom of Information Act, so the details are reliable.

On Sep. 10, 1976 British European Airways flight 831, flying between Moscow and London and over Lithuania at the time, observed an intense ball of light above the clouds below the aircraft. The light was so intense that it lit up the sky in the entire vicinity.

The concerned pilot reported the glowing object to the Soviet ground authorities with whom he was in contact. He received the harsh instructions to ignore the light, and essentially to continue on his way out of there.

Here we see an incident involving a small, intense Tesla globe, of the kind with which the defense could "service" objects that had already penetrated a large midcourse globe, or aircraft approaching the defended area.

Obviously the Soviet authorities were tracking the aircraft, and knew it was in the vicinity. It seems logical, then, that they deliberately placed the brightly glowing ball beneath the aircraft so that the pilot and crew could not fail to observe it.

The strange message to the pilot was simply designed to increase the intensity of the stimulus. The stimulus was to be something like, "The Soviets are doing something in research and development that allows them to create intense balls of glowing light at a distance, and place these objects in the air in and around aircraft, possibly to intercept them." The purpose, of course, was to observe the British government's reaction after the incident was reported by the pilot upon his arrival at London.

Again the reaction of the British - and the U.S. as well - was as predicted. Again we showed that we knew nothing of scalar electromagnetic weapons, and did not recognize one when we encountered its effects.


TERMINAL ABM SYSTEM
HIGH ALTITUDE DEFENSE SUPPRESSION BURST
DECOYS
WARHEAD
GAMMA RAYS
EMP
DEBRIS
SCATTERING AND ABSORPTION
X-RAYS
SCATTERING AND ABSORPTION
IR-VISIBLE-UV
SCATTERING AND ABSORPTION
RF NOISE
HEMISPHERES OF INTENSE LIGHT BANDS (WITH ELECTRON PLASMAS LIFTED FROM DIRAC SEA)
FARADAY CAGES ABSORB RF NOISE SHIELDING EQUIPMENT/INSTALLATIONS

Slide 060: Terminal ABM System

Very neat things can be done if one nests several Tesla shields - say three or four - concentrically, one inside the other. In that case even the nuclear radiation (such as gamma rays) from a defense-suppressive high altitude nuclear burst can be handled.

For example, suppose three such concentric shields are placed over a large vital area. Further, suppose a high altitude nuclear burst is placed up above the outer shield. Gamma radiation almost instantly strikes the plasma in the outer shell, where it is absorbed, scattered, and re-radiated at lower temperature. (That, after all, is what plasmas do.)

Inside the first shell, the scattered radiation is now in the x-ray and ultra-violet region. Let us track the most lethal component, the x-rays.

The scattered x-rays then strike the second plasma shell, and are absorbed, scattered, and re-radiated at lower temperature. Inside the second shell the scattered radiation is now in the visible and infrared region, with a little ultraviolet.

This optical radiation in turn strikes the third plasma shell, and is absorbed, scattered, and re-radiated at still lower temperature. Inside the third shell most of the energy is now in the form of radiofrequency (RF) energy, with a little IR and visible band spectral energy content.

At this point, ordinary electromagnetic interference (EMI) shielding of electronic equipments on the ground and inside the third shield can take care of any RF interference resulting from the emergent RF noise.

As can be seen, three shells are sufficient to convert the gamma and x-ray radiation (and ultraviolet and infrared) mostly to harmless RF energy before all three shells are penetrated. Thus the tactic of deliberate defense suppression by a preliminary high altitude nuclear burst can be countered by multiple Tesla shields.

In addition, of course, any ordinary vehicles penetrating all three shields are exposed to successive violent EMP's, and are almost certainly electrically dudded. The vehicles are also subjected to multiple periods of intense heating, so combustibles, fuels, explosives, and ablatives are destroyed. In addition, metal structures may be melted or vaporized.

Think of it this way: anything that hits one of these Tesla shields goes phht! Just **like** a bug hitting an electrified bugkiller screen.

For years passing ships have observed and reported such multiple-shield "light phenomena" over remote regions of the ocean. U.S. intelligence has routinely **not** paid any heed to reports of "lights at night" over remote ocean areas, and so Soviet tests in this manner have remained relatively unnoticed by officialdom.


TWO ARCS IN THE SKY
VERY BRIGHT ARC
TEN MINUTES LATER A SECOND, DIMMER, ARC APPEARED.
150°
INDIAN OCEAN / 1800 GMT / JUNE 1, 1961

Slide 061: Two Arcs in the Sky

Just to list one incident involving the testing of multiple concentric Tesla shields, here is an early test conducted in mid-1961 over the Indian Ocean.

The incident occurred at 1800 hrs. Greenwich mean Time (GMT) and was observed by a passing ship. The report is contained in Marine Observer, Vol. 32, 1962, p. 64.

First the ship's crew observed a gigantic, very bright arc of light on the horizon or beyond it, with both ends passing below the line of sight to the horizon. This was in fact probably a large Tesla shield, but of such low intensity that only its intersection arc could clearly be seen. The arc subtended an arc of about 150 degrees across its diameter at the bottom. After about 10 minutes, a second and dimmer arc appeared, concentrically inside the first one. The ship thus was observing what probably was the nesting of two giant hemispheres (of EM energy) to provide a multiple Tesla shield.

This was probably a test of an early research and development prototype, since Khrushchev had only announced his new "fantastic weaponry" in development in his January, 1960 speech to the Soviet Presidium. And apparently land-based weapons such as this prototype probably did not become deployed and operational until April 1963. However, even in 1961 the Soviets would have been developing and testing prototypes of the weapon adapted for naval task force protection and usage.

Several other similar phenomena involving nested hemispheres or giant concentric arcs of light have been seen by mariners at sea.



Slide 062: ABM Defenses

When the various capabilities of Tesla shields, globes, and scalar howitzers are integrated together into an ABM defense, a most formidable Soviet strategic defense capability is apparent.

On this slide we deal only with midcourse and terminal phase ABM defense. Later we shall cover the application of these weapons to launch phase ABM defense, primary phase bomber defense, underwater antisubmarine defense, etc.

Suppose the U.S. is provoked to desperately launch a missile attack toward Russia, as indicated on the slide.

First would come the launch phase destruction of the launched missiles, which we will cover shortly.

Any remaining missiles in midcourse would encounter extremely large, glowing spheres of light, where the EM energy density is contained and held in the spherical shell "energy bottle" of the glowing globes. Each globe might cover an are of up to about 20 degrees, as seen from the Soviet defended area. Missiles carrying MIRV and MARV payloads would not yet have deployed their re-entry vehicles.

As a missile and its payload encounter one of the globular shells, an intense EMP is suddenly experienced throughout the missile and all of its components. Again, EMI shielding is of no consequence since the EMP arises in each increment of spacetime throughout the vehicle volume. The result is instantaneous dudding of all electronic circuitry, including the electronics of the nuclear warheads themselves. The HE content of the nuclear warhead system is violently exploded, totally destroying the configuration of the warhead. A low-order nuclear detonation may occur, but more likely the warhead's nuclear material is just broken up, finely divided, and set afire.

In addition, all combustible materials are set fiercely afire or destroyed. Explosive materials such as booster propellants and HE explosives are violently exploded. Ablative and plastic materials literally explode into pieces, torn apart by sudden violent ablation and outgassing everywhere within. The remnants of the vehicle are now total duds, as is the payload, including re-entry vehicle, nuclear warhead electronics, nuclear materials from the disruption and explosion of the HE portion of the warhead system, etc.

Still, each piece of the debris must pass through the glowing shell once more before it exits. Thus a second "shot", precisely as effective as the first, still awaits each and every piece of the debris plunging along inside the shell as it exits.

As the debris continues on to the latter part of midcourse and early terminal phase, any portions large enough to track are subjected to small, intense Tesla globes where the energy density in the shell is many orders of magnitude greater than in the larger globe used in earlier midcourse. This part of the defense system simply services each incoming "blob" methodically, probably first in the pulse mode. Later, any blobs still remaining are given the maximum "continuous heating" mode with a small Tesla globe, to actually vaporize metals and materials.

In the unlikely event that anything active still remains, or that an object has managed to elude the large and small Tesla fireballs, a Tesla shield is still to bo encountered, towering over the protected area. For significant targets this shield will be concentric, and will contain three or more concentric Tesla shields. Again, the approaching vehicle will be subjected to multiple EMP's and severe heating throughout its volume. In addition, the concentric shields will "clean up and sterilize any gamma radiation and EMP resulting from any deliberate high altitude defense suppression nuclear burst that somehow (inconceivably!) gets through the launch phase ABM system, and the Tesla-globe midcourse and earl terminal phase defenses.

As can be seen, the system complex represents a most formidable defense **that** certainly approaches 100% effectiveness against the present triad, and even against the addition of cruise missiles.

In addition, since these weapons suffer from very strange constraints and limitations, the scalar transmitters are actually dual mode: they become conventional radars by simply switching into the ordinary EM mode. They arc part of the more conventional ABM defense system complexes we presently recognize in the Soviet Union. In this conventional role, backup ABM missile interceptors are available, to be employed in case the conventional role must be assumed.

Later we will address the reason for the strange limitations that must be placed upon unqualified use of the large scalar EM systems, particularly in the pulse or "burst" nodes.

NETWORK OF VIRTUAL TRANSMITTERS

Slide 063: Network of Virtual Transmitters

In July 1976 the U.S. received very special Bicentennial greetings from the Soviet Union.

At that time, communications systems of the world in the 3-30 megaHertz band suddenly met substantial interference from extremely powerful, chirped Soviet transmitters that were suddenly activated. These transmitters continue their transmissions to this day.

Estimates of the power of these enormous transmitters vary, but figures range as high as several hundred megawatts, with a nominal figure being 100 megawatts.

These powerful transmitters were promptly nicknamed "Woodpeckers" because of the characteristic sound of the chirped signal when received. That is, the received signal made a "pecking" sound much like a woodpecker's beak hitting a block of wood.

Several nations protested, but the powerful signals have continued, right down to this day. The only Soviet response was to add a "spread spectrum" capability, so that the transmitter did not dwell too long on one specific frequency, but shifted periodically to other frequencies.

These transmitters have apparently never been precisely located by U.S. intelligence, but their beams carry much of the characteristics of an **over-the** horizon (OTH) radar. They have been dubbed OTH-radars by U.S. intelligence, and can without question perform that mission, in addition to some very interesting missions which U.S. intelligence does not assess.

Soviet Military Power, Department of Defense, 1985, p. 45 shows the direct intersection over the United States of the Woodpecker radar beams used in an OTH-role. We show an illustration of that intersection on this slide.

In addition, we show an additional "scanner" beam that can be scanned across the intersection "grid" over the U.S., formed by waveform interference of two main Woodpecker beams.

These Woodpecker transmitters have a great many diverse functions.

First, they can be used in a conventional over-the-horizon radar node, since their beams follow the earth-ionosphere waveguide and curve around the earth. In this mode they can detect missiles at launch and thereafter, and strategic bombers when taking off and thereafter.

However, these scalar interference grid weapons have many other uses.

First, they can be used to biologically attack entire populations in a targeted area. This aspect is not covered in this briefing. Suffice it to say that phase-locked ELF modulation signals ot 10 Hz and less are often detected on multiple Woodpecker frequencies simultaneously. In a target area, this modulation - if sufficiently stronger than the Schumann resonance of the earth's magnetic field - will entrain a percentage of the brains into "forced entrainment." In that case, these human brains are "synchronized" to the Woodpecker signals so that multiple coherent frequencies are phase-locked into them. That is, multiple coherent EM channels directly into these entrained brains now exist. At that **point,** Fourier expansions may be used to attack specific portions of the brain geometrically.

In addition, scalar EM disease patterns can be modulated upon the carriers, again with Fourier expansions. Specific biological effects can be induced in the entrained populace at will, limited only by the state of the art of the Soviet technology used to attack them. Possible induced effects include instantaneous **death,** heart seizure, severe emotional disruption, loss of control of internal functions, diseases, disabling of the immune system, and even implantation of **thoughts,** emotions, and ideas which are interpreted by the targeted subjects as their own.

While further discussion of this area is beyond the scope of this briefing, the biological aspects of the Woodpecker transmitters are horrible. It suffices to say that, in thousands of experiments, Kaznacheyev demonstrated that almost any **kind** of cellular death and disease pattern could be electromagnetically transmitted. Kaznacheyev reported the effect in the near ultraviolet. Experimenters at the University of Marburg in West Germany duplicated the experiments in the infrared.

The bottom line is that photons themselves can carry death and disease patterns between cells. Scalar E*M* technology allows the synthesis of the actual potential pattern (which after all represents total control of charge and charge distribution, hence biochemistry in the cell) of a particular cellular disease or death mechanism. Symptoms (and cellular death from them!) of nuclear radiation, chemical poisoning, bacterial infection, and other mechanisms were successfully induced by the Kaznacheyev experiments.

Dr. Popp of West Germany has published an analysis of the virtual photon master control system of the cells. Since scalar EM represents the deliberate ordering of virtual particle flux into deterministic patterns, the master control system can readily be entered with scalar techniques to induce disease and disorder at will.



NETWORK OF VIRTUAL TRANSMITTERS

WOODPECKER INTERFERENCE GRID
(SCALAR COMPONENTS)

Slide 064: Network of Virtual Transmitters

On this slide we diagrammatically represent the Soviet woodpecker interference grid over the U.S. This grid can easily be used to influence and control the weather, and for over a decade the Soviets have manipulated the weather over the U.S. and other parts of the world.

By the peculiar title of this slide, we wish to call attention to the fact that, in the exothermic mode of scalar interferometry riding on the woodpecker radar signals, each of the woodpecker grid interference cells can act as a little "virtual transmitter." It's exactly as if the Soviets had been permitted to enter the U.S. and build thousands of EM transmitters at regular intervals all over the country!

And of course it's even worse. In the endothermic mode, it's as if the Soviets had been permitted to enter the U.S. and build thousands of "cold generators" all over the U.S. That is, in that mode, each of the "transmitters" can actually extract electromagnetic energy.

These two modes have enabled the Soviet Union to drastically manipulate the weather at will over the U.S. during the last decade (and similarly, for other places as well.)

(For a disclosure of the Soviet weather control operations over the U.S., see T.E. Bearden, Soviet Weather Engineering Over North America, 1-hr. videotape, 1985, available from The Tom Bearden Website www.cheniere.org. We will only summarize here.).

Briefly, inside various reference level zeros on the ordinary EM woodpecker carriers, scalar "channels" are established. Scalar beams, signals, and interferometer pulses and transmissions can be transmitted through these reference channels as if directly through a wire. Phasing, pulse shaping, and Fourier expansion formation of geometric forms are then the key to be used in scalar interferometry through the internal scalar channels of the Soviet woodpecker signals.

By choosing one or more grid cells and using scalar interference there in the exothermic continuous mode, local heating and expansion of the air, and formation of a high-pressure area, occurs.

By choosing one or more grid cells and using scalar interference there in the endothermic continuous mode, local cooling and shrinking of the air, and formation of a low-pressure area, occurs.

By electromagnetic "rotation" of the interfering scalar beams, the hotspots and coldspots can be moved along a desired path and at a desired speed.

By these methods the entire jetstream across the U.S. can be deviated and controlled to a large degree. Moisture can be drawn from the Pacific beyond Southern California and Mexico, and collided over the southern U.S. with extremely cold air brought down from Canada, producing ice storms such as those in and around February 1, 1985.

Violent thunderstorm activity can be induced and directed. By adding "spin", these same storms can be induced to form extensive tornados.

By sustained weather engineering operations, drought or excessive rain and flooding can be induced in areas of the U.S. as desired. Crops can be destroyed or heavily damaged by severe and unseasonal weather.

If the grid is placed in the ground on scalar EM carriers instead of normal EM carriers (and the woodpecker "radars," can switch to, or add, scalar carrier mode whenever they wish), it can be used as an anti-submarine weapon, as we shall see later. It can also be used to cause substantial ocean effects that have drastic consequences on the world's weather - such as the anomalous El Nino of 1982-83.

By localizing one spot of heating at the top of a thunderstorm anvil, and another spot of cooling at its side, a localized downburst can be created. Our weather satellites have detected just such an anomalous combination heating and cooling of thunderstorm anvils over the U.S. While there may exist natural mechanisms to cause this anomalous dual pattern, it may also be caused by Soviet weather engineering, which can cause either broad-area or highly localized effects.

All these types of weather engineering incidents have been deliberately created over the U.S. by the Soviet Union.

Perhaps the greatest weather effects can be induced by altering some of the large-scale normal mechanisms that influence and control our weather. Thus the **artificially** induced El Nino of 1982-83 was a case in point, causing drastic weather upsets worldwide for a year or more.

The last decade has seen weather so anomalous that it could only occur once in 1200 years by chance. It has not been due to normal chance, but by Soviet weather engineering, particularly since the advent of the Woodpecker transmitter complexes.

ADDITIONAL BACKGROUND FOR THE BRIEFER:

The Woodpecker transmitters can carry scalar components, which, in addition to biological strikes, can be used for many other purposes such as to

1. Influence and control the weather,
2. Deviate the giant jetstreams of the upper atmosphere,
3. Detect, track and destroy missiles shortly after launch,
4. Detect, track and destroy strategic bombers and other aircraft,
5. Attack land and ocean surface targets by large aerial electromagnetic explosions: the EM explosion produces the fireball, the thermal effects, and the blast wave of a nuclear explosion without the nuclear radiation and radioactive fallout contamination;
6. Attack surface land and ocean targets by large "cold explosions", where living things freeze almost instantly, leaving the surface facilities and equipment intact,
7. Attack land and ocean surface targets by severe internal electromagnetic disruption, so that all electronics are dudded,
8. Attack personnel on land and sea by direct destruction of their nervous systems with an internally induced strong EMP,
9. Disrupt the operation of distant facilities, equipment, and personnel or destroy food crops in large areas by severe cold or severe heating, or even startling oscillation between the two.

   In addition, the scalar aspects of the Woodpecker transmitters can be beamed through the earth and ocean as surface waves or at a given depth to intersect at a distant region. This mode can be used to

10. Cause distant earthquakes in a distant fault zone by depositing energy in the rocks there, increasing the plate stress until slippage occurs at a fault zone,

11. Cause large, anomalous rocking of an entire plate or large area, by depositing and extracting energy from alternate areas, causing buckling of the large rock plate,
12. Set up an interference grid under the water, so that underwater submarines can be detected, tracked, and destroyed on station and with their missiles still unfired,
13. Attack naval vessels and task forces through the water and through their hulls, without warning,
14. Attack missile silos and nuclear storage sites "before launch", directly through the earth itself,
15. Initiate the full nuclear explosion of implosion-type nuclear warheads on-board missiles on station,
16. Initiate full nuclear explosion of implosion-type nuclear warheads in storage sites and ready reserve,
17. Destroy seaborne and ocean-bottom-mounted mines and underwater sensors, even including entire "fields" of them,
18. Detect and destroy hostile torpedoes, ship-to-underwater anti-submarine missiles, and dumped anti-submarine munitions and charges,
19. "Pump" the electrical grounding of distant electrical power distribution and generation systems so that the system catastrophically fails,
20. "Pump" the electrical grounding of distant electrical power systems so that radio and television transmitters, power grids, and wiring complexes in buildings and facilities radiate a desired scalar wave component or signal complex at equipment and personnel.

All in all, the woodpecker transmitter complexes and other associated scalar EM weaponry are most useful in the major missions required in war.



LAUNCH PHASE ABM SYSTEM

- "BIG EYE" SCANS GRID SQUARES, DETECTS PENETRATION
- COMPUTER TRIGGERS MULTIPLE TRANSMITTERS
- PULSES PHASED SO EMP PULSE OCCURS IN DESIRED SQUARE
- PENETRANT IS DUDDED OR DESTROYED

Slide 065: Launch Phase ABM System

On this slide we show the use of the Woodpecker grid in the Launch Phase **ABM** system role.

The scalar components establish an interference grid over the U.S., at some altitude above the earth. One or more separate scalar interferometers transmit through scalar channels established in the Woodpecker's normal EM carriers, scanning through the grid square cells one by one in the "just barely extract energy" endothermic mode.

Back in the Soviet Union, the energy extracted passes through a scanned receiver biased just so that the normal energy extracted from the distant atmosphere does not show on a scanning screen. Any substantial amount of additional energy appearing in the cell - such as from the jet engines of a large aircraft or the rocket exhaust of a large missile - will be detected.

The **operation** of this weapon is four-fold: (1) the scanning interferometer or "big eye" scans the grid squares, detects penetration, and tracks the rising missile. (2) A separate scalar EM interferometer (a howitzer) is controlled by a computer and fired through a separate scalar EM channel opened in the ordinary EM woodpecker carriers. (3) Two timed scalar pulses are fired so that they converge and meet in the grid cell containing the rising missile. This results in the **sudden** emergence of a violent EMP pulse throughout the missile and the surrounding vicinity. (4) All missile and warhead electrical and electronic systems are instantly dudded and destroyed. In addition, fuels, propellants, and explosives of the missile are immediately ignited, explosively destroying the penetrating missile.

That takes care of the missile target. (The same weapon, of course, can be used against airborne strategic bombers - including Stealth-type bombers. In fact, Gary Powers' high flying aircraft was probably shot down in 1960 by a "jury-rigged" scalar EM howitzer using modified radars and timed scalar pulses to provide an aerial explosion and EMP.)

The Woodpecker grid/howitzer weapon system can be placed over the ocean and used against cruise missiles, naval surface-to-air and surface-to-surface missiles, submarine-launched ballistic and cruise missiles, etc. Placed over a carrier task force, it can also take care of the aircraft launched by the carrier as fast as they are launched. It can also handily take care of the missiles launched by guided-missile cruisers of the accompanying task force.

Now let's take a look at the command and fire control end of this weapon system, way back in the Soviet Union.

SOVIET COMMAND & CONTROL CONCEPT



Slide 066: Soviet Command & Control Concept

On this slide we show a postulated Soviet fire control system for the grid weapon.

Two or more operators sit at a control console, facing a giant display (screen). The display contains a grid, which represents the distant interference grid of the Woodpecker carriers (or scalar EM carriers, if in the underground or underwater mode). A distant missile launched into the real interference grid overhead will cause a spot of light to appear in the appropriate grid square (cell) on the operators' screen. The operators will track the displayed target, select firing mode and type of action, engage the target, and assess whether or not the distant target is killed or missed by the firing.

When a missile is launched in the distant area over which the Woodpecker grid has been placed, it quickly rises through one of the scanned grid cells on its upward journey. As it penetrates the cell, additional energy is extracted (since part of the missile's exhaust energy is now extracted also). At the screen in the Soviet Union, the additional energy received rises above bias, causing a "bloom" or spot of light to appear on the screen at the appropriate grid cell representation.

The distant operator has now detected the missile launch and its location. He places a marker over the target track and activates the computer, also inputting the type of firing or action to be performed. In this case, let us say he wishes a burst of **energy** to emerge inside the distant launched missile, and has activated that mode of firing action.

The computer computes the necessary parameters for another scalar interferometer channel in the exothermic mode, and for firing at the location of the rising missile so that two scalar pulses will meet in the cell penetrated by the rising missile on the other side of the earth. As the channel is opened, the firing solution settled, and the interferometer howitzer readied, the computer activates indicators on the console notifying the operator. When all is ready, a "ready-to-fire" light is lit on the console.

Upon receiving the command to fire and destroy the missile, the operator presses the fire button. The computer fires the activated scalar EM howitzer in the pulse mode. The operator continues to watch his screen.

When the pulses meet in the distant grid cell, a violent EMP suddenly arises in and throughout the missile and its surrounding vicinity. This explodes the missile propellants and warheads, destroying the target.

On the distant screen, a sudden drastic "blossoming" of the target results from the sudden extraction of a great deal of additional energy by the scanning scalar interferometer. The operator thus knows he has made a "kill."

Should for some reason the target be missed, additional energy will still be extracted by the scanning interferometer from the grid cell/vicinity in which the EMP suddenly emerges. The distant operator will still see a bloom on his scope, but not nearly so great as when the missile explodes. He thus knows that the EMP effect of the firing has occurred, but the target has been missed (he will see the bloom in its offset location as well). In that case, the operator can quickly mark the EMP location, hit the switch, and the computer will automatically correct and fire again.

At any rate, for a miss a large "sonic boom" or blast still results in the EMP emergence zone from sudden heating of the air. These are precisely the type of booms that were associated with three NASA shuttle launches prior to the end of 1985. These were actual testing of this weapon system, using the shuttle launches to provide a target, and delaying the burst some minutes so the shuttle would not actually be destroyed. On Nov. 26, 1985 a "marker beacon" (glowing ball of light) was also created over the site. This was probably to orient **satellites** and other detection systems. Some 12 minutes after that nighttime launch, **a** large blast occurred over the site, heard for hundreds of miles up and down **the** coast. Shortly after, the light suddenly moved away very rapidly - faster than **a** jet aircraft.

If many missiles are being launched, the operator marks them rapidly, one **after** the other, and the howitzer fires burst after burst at them, decimating the launched missiles, one after the other. In this fashion most of the counterstrike missiles launched by the U.S. would be destroyed shortly after launch, greatly reducing the number of missiles that make it to midcourse.

However, apparently the loss of the shuttle launched on Jan. 28, 1986 was caused by the addition of a metal-softening pattern in the exothermic mode, in and around the booster, using the actual booster ionic flames as a receiver-amplifier. This led to the failure of one of the supports and the partial breakaway of the right booster. The booster rotated into the tank, causing damage and the resulting explosion when the venting main fuel hit the booster flame.

By spread spectrum techniques and proper timing and phasing, one system of Woodpecker transmitters can set up multiple interference grids, in various parts of the world. The scanners and howitzers can operate in the appropriate zones, again by spread spectrum techniques and proper timing and phasing.

In fact, the latest versions probably can operate in the "ordinary EM carrier" (atmospheric) mode and the "scalar EM carrier" (underwater and in the earth) mode simultaneously - again by timed switching between EM and scalar EM carriers, spread spectrum techniques, and timing and phasing of howitzers and Manners.

Thus a single system can operate in the earth, underwater, and atmospheric modes. It can operate against the very wide range of different targets previously mentioned. It can do all this "simultaneously," from a real-time practical viewpoint.


LAUNCH PHASE ABM SYSTEM (ANTI-SLBM)
CCCP

Slide 067: Launch Phase ABM System (Anti-SLBM)

Here we show the operation of the system in the atmosphere over the ocean, to destroy sub-launched ballistic missiles such as Poseidon and Polaris. The system operation shown uses the normal EM Woodpecker carrier frequencies, with scalar components to establish the interference grid, and scalar channels for the scanners and howitzers. The grid can be set up by this method anywhere in the world.

As can be seen, during their early launch phase, this mode will take care of the missiles launched from underwater U.S., British, and French nuclear submarines.

Remember, this is just one mode in which the system is operating. It can at the same time have other interference grids at other locations, and even in other modes, including underwater grids used against the submarines themselves, it can be engaging a multitude of targets of a wide variety of types, essentially all simultaneously.


DETECTING & MARKING MISSILE LAUNCH

Slide 068: Detecting & Marking Missile Launch

Here we show the missiles launched from the underwater submarines, when just detected in the atmosphere over the ocean. As each rising missile is detected, an operator at the screen places a cursor (a "marker") over the detected track spot on the scope.

The computer quickly computes the firing parameters and indicates when the system is "ready to fire."

By using additional scalar scanner frequencies in the multi-gigaHertz range and fine scanning, the operator is able to accomplish non-cooperative target identification.

After the operator places a cursor over a target, the advanced system fine-scans and identifies it as hostile, then continues the track in automatic.

When the operator presses the fire button for a designated target, the computer intiates fire by the appropriate scalar EM howitzer through established grid scalar firing channels.



Slide 069: Destroying the Launched Missiles

On this slide we temporarily omit the interference grid and diagrammatically show the operation of the scalar EM howitzer. As shown, two pulses are fired so that they meet in the grid cell where the rising missile is located. A drastic EM pulse suddenly emerges everywhere throughout the missile and its vicinity causing instant missile destruction.

Of course, individual howitzers not in the Woodpecker carrier's scalar channel can also fire at the missiles in the purely scalar exothermic mode. Or they can utilize the large "Tesla globe" in the continuous mode, the small Tesla "ball of light" in the continuous or pulsed mode, etc.

Also, continuous EM energy can be caused to emerge in a broader, "defocused" interference area causing electronic dudding of circuits in vehicles over a wider area. This is a very useful mode to use against mass attacks by many aircraft and/or many missiles at the same time. That is, the entire formation can be attacked in the "dud electronics" mode, and then followed up by more intense servicing of each individual hapless target.

Again, in 1960 Gary Powers was probably downed by a crude prototype scalar interferometer "howitzer" obtained by modifying two ordinary radars. At least the Soviets had previously been unable to down a penetrating U-2 with missiles they possessed. We know the scalar howitzers were in development, for Khrushchev had announced to the Presidium in January 1960 that a new "fantastic weapon" was in development. A development prototype was probably used to down Powers' aircraft.



Slide 070: Shift to Anti-Sub Mode

In the underwater mode portrayed on this slide, the Woodpecker transmitters have been switched to "scalar carriers" mode and the carrier beams transmitted through the ground and into the ocean underwater. (Remember, an artificial EM potential that does not couple to charged particles or ions will travel through the ocean, but a force field will not.)

Thus a giant scalar interference grid is now established underwater. Additional scalar beams in the weakly endothermic mode scan this grid. When a submarine enters the grid, it substantially changes the potential in that cell, and the scanner picks this up. The distant screen now displays the sub as a "track" of light in the appropriate grid square cell. The computer switches in fine-scanning and non-cooperative target identification. It identifies the target as hostile and alerts the operator (by blinking the track and changing its color to red, for example).

As before, the operator marks the target and enters the firing mode and type of action desired. Again, let us assume the "EMP burst" mode of destruction is to be used. The computer computes the firing parameters and readies the howitzer, When the commander gives the command to fire, the operator presses the firing button. The computer fires the howitzer.

Two scalar pulses proceed through the howitzer scalar channel and meet in the submarine. Throughout the sub and its vicinity, a violent EMP is suddenly experienced, knocking out the electrical systems, electronic equipment, and igniting propellants and explosives in the on-board missiles and armament. This explodes the submarine, missiles, and torpedoes instantly.

At the distant command console, the scanners detect the violent eruption of energy from the exploding submarine. It appears on the screen as a sudden strong blossoming of the track. The operator assesses that the target has been destroyed. He immediately engages another target if one is present.

If the EMP is off-course and misses, the scanners still pick up a smaller blossoming in the offset location. The operator immediately knows he has missed the target. He marks the offset bloom, presses the switch for "Correct!" and the computer makes the firing correction. When the operator again gets a Ready-to-Fire light illuminated, he presses the firing button and fires again at the target, this time with corrections applied.

Again, the same Woodpecker system - using timing, phasing, scalar/EM switching and spread-spectrum techniques - may be involved in several grids and many types of targets. When in a target-rich environment, the firing operators may be very busy indeed.

As we shall later see, the same weapon system may also be firing in the "cold explosion" or pused endothermic mode, where intense bursts of instant and severe freezing are unleashed in the target zone.

SHIFTING TO EARTHQUAKE MODE



Slide 071: Shifting to Earthquake Mode

The uses of the complex grid, scanners, and scalar howitzers is limited only by human ingenuity and state-of-the-art of the technology developed.

By shifting to the scalar-carrier mode and transmitting in the surface layer of the earth, the interference zone can be established in a distant region of the earth, beneath the earth's surface.

Suppose we establish a very small interference grid in the earth at and around a distant fault zone. Then by steadily depositing energy in the zone in the continous exothermic mode, the stress in the fault area is steadily and gradually increased. Eventually the plates on each side of the fault will slip, and a "natural appearing earthquake" occurs. If the energy is deposited slowly and gently, a gentler quake can usually be effected. If the energy is deposited fairly rapidly, a higher peak stress can usually be reached before the rocks slip, and a larger, more destructive earthquake results.

By making a wider grid in the earth in a larger area, a strange kind of earthquake can be induced, whether or not a fault zone exists in the area. By pouring energy out of alternate cells and extracting energy from the others, a "wave-like" buckling tensile and compressive stress is created throughout the zone. As this continues, the entire plate area will try to oscillate, moving and causing an anomalous sort of "rocking, flat earthquake" throughout a large area.

Not too many days after the destruction of the Challenger on January 28, 1986, such an anomalous "flat earthquake" occurred in the U.S., near the Great Lakes, involving some 10 states. This was probably the subsequent testing of an additional weapons mode of the same Soviet scalar EM system that destroyed the shuttle.


SUPPRESSION ATTACK - MARV'S (WITHOUT DEFENSES)

DELIVERED BY ONE VEHICLE
(MARV'S)
MULTIPLE MANEUVERABLE
RE-ENTRY VEHICLES
EACH MANEUVERS AND
ATTACKS A DIFFERENT TARGET

Slide 072: Suppression Attack—MARVs (without defenses)

Now to shift the emphasis a bit, and look at the impact on some "normal" strategic systems and concepts.

On this slide we show the basic idea of suppression attack against an enemy's ground based missile force in fixed-site silos. The attack uses multiple maneuverable re-entry vehicles (MARVs) delivered by a single carrier missile, which acts as a "bus." The bus ejects the MARVs at the appropriate time, and each of the MARVs heads toward its predesignated target, maneuvering as it re-enters the atmosphere and proceeds to the target. The maneuver makes conventional intercept of the MARV by conventional anti-ballistic missiles more difficult.

In this manner, missile silos without defenses may be caught by surprise and destroyed.

The "bus" concept actually multiplies the number of targets a single launched missile can attack, and the maneuvering of the MARV increases the difficulty of defending the target area by orthodox means.



SUPPRESSION ATTACK – MARVs WITH DEFENSES

(OVERKILL CAPABILITY MAXIMIZES P_k)

Slide 073: Suppression Attack—MARVs (with defenses)

Now suppose some of the scalar EM defenses we have discussed are added to the picture.

On this slide we show a similar missile field, defended by a Tesla dome and by multiple scalar howitzers.
The howitzers take the incoming buses under attack during the early midcourse phase, by means of very large spherical EMP globes. Many of the buses - and their entire payloads, including the nuclear warheads themselves - are dudded by these midcourse defenses.

Servicing of dudded vehicles that have penetrated the globe now occurs farther along in midcourse. Each dud vehicle may be serviced, for example, with a small globe in the continuous mode for an appreciable number of seconds. This causes vaporization or fusing of the physical structures of the vehicles.

Groupings of incoming vehicles may also be serviced by medium-sized globe in the pulse mode. This assures dudding, and is especially useful for clearing away chaff and debris with smaller ballistic coefficients. It also is useful to further insure that the nuclear warheads themselves are totally dudded.

An additional wrinkle is to place scalar signal patterns - that affect and transmute a nuclear warhead's radioactive nuclei - onto a continuous globe. In short, by the proper scalar signals it is possible to transmute plutonium and uranium into harmless elements, and it can be done at a distance. The 4th and 5th generation Soviet scalar EM technology is probably capable of doing **this**

This insures that, not only are the incoming nuclear warheads electromagnetically inert, but they are also nuclearly inert and incapable of generating nuclear explosions.

Still another wrinkle - particularly useful against implosion-type weapons - is to utilize a scalar signal pattern that causes sudden generation of neutrons in the active material (plutonium or uranium). This harmlessly explodes the nuclear warheads while they are far away from their intended targets and out in space. The burst mode is probably the most useful for this tactic.

Note that, if desired, this same tactic - exploding the nuclear weapons themselves - can also be utilized in the Launch Phase ABM system grid against the missiles after launch. This capability converts an adversary's intended nuclear attack against you to an actual attack against himself!

Also note that the adapted grid system in the surface of the earth can be used to explode the nuclear warheads in ICBMs while they are still in the silos, or to explode nuclear warheads in storage. In the underwater mode, the nuclear warheads in the Poseidon and Polaris missiles on-board the nuclear submarines can be exploded in a similar manner. In fact, the nuclear reactor used to furnish the power for the nuclear submarines can also be exploded or disabled in this manner, as can land-based and ship-based reactors.

Again, this actually turns an adversary's own nuclear weapons against him. His own weapons can be used to obliterate him. Without scalar defenses, possessing the capability of nuclear attack becomes a serious detriment!

But back to our slide. Just in case something gets through this formidable defense somehow, the Tesla Shield (dome) provides the final reiteration that takes care of any residue "leakage."

The sum total of these defenses fully justifies the 1968 Soviet statement in Military Strategy that the USSR has achieved a 100% defense, and the West has



RESPONSE TO COUNTERFORCE STRIKE – WITH NO DEFENSE (FIRST STRIKE)

Slide 074: Response to Counterforce Strike with No Defenst

Here we show the orthodox concept of response to a surprise counterforce nuclear strike when the surprised force has no defenses.

A great percentage of the attacked missile silos are destroyed. The surprised side thus is able to mount only a limited strike in retaliation. Perhaps he is able to launch some remaining silo-based missiles that escaped destruction. He is also able to launch missiles from any of his underwater nuclear submarines that escaped. Some of his strategic bombers may have escaped destruction on the ground or while airborne on station; these surviving bombers can be directed to proceed with strategic reprisal against the enemy.

As can be appreciated, this entire concept is now totally obsoleted by the Soviet possession of scalar EM weapons.

The "mutual assured destruction" capability - or MAD concept as it was so aptly named! - is no longer mutual.

And for two reasons: (1) the Soviet surprise attack could destroy essentially all our Triad forces wherever they are, in the first attack. (2) Even if a very small number of our strategic forces survive, the puny strike we could attempt to launch could be repeatedly decimated from launch to terminal phase.

The restraint on the Soviets is not because of our Triad forces. The restraint is twofold: (1) a second nation has scalar EM weapons, and would undoubtedtly unleash them upon the Soviet Union with great violence if such a massive world-wide destruction of U.S. forces occurred or was threatened (is it really "accidental" that six major Soviet missile ammunition storage sites mysteriously exploded within seven months?); (2) the closed-loop scalar radiation exchange system of Earth-Sun could be inadvertently "tweaked" in the feedback loop from Earth to Sun, so that a large solar scalar resonance was stimulated. In that case the Sun could emit a mighty resonant "burp" that would simply wipe out all life on Earth in a fiery shower.

The "terror" in the "balance of terror" between nations has just increased by many, many orders of magnitude.

The biblical prophecy that the Earth will be wiped out by "fire and brimstone from heaven" is very near fulfillment now.

Put another way, the pucker factor - even on the Russians who may contemplate unleashing Armageddon - is higher than any Western strategic analyst has ever imagined, even in his wildest nightmares.

Truly these weapons are "more frightening than the mind of man has imagined," as Brezhnev put it in 1975.

The frightening scalar EM weapons can be used, but only very, very gingerly indeed. If a slight mistake is made, everybody loses everything.


RESPONSE TO COUNTERFORCE STRIKE – WITH DEFENSE

Slide 075: Response to Counterforce Strike with Defense

On this slide we show the impact of scalar defenses against an adversary who possesses only the orthodox nuclear weapons and delivery systems, and makes a "first strike" by surprise against his opponent.

In this case, the attacked opponent has scalar EM defenses.

With just the midcourse and terminal scalar EM howitzer defenses, almost all of the attacking missiles and re-entry vehicles are destroyed.

If for some reason (such as to prevent triggering the sun and destroying the world inadvertenly!) the attacked adversary does not wish to attack strategically with scalar EM weapons, he may now launch a massive retaliatory strike on his opponent.

And if that opponent has no ABM defenses, he's just bought the farm.

What a funny coincidence! Long ago, we crazy Americans chose to put all **our** eggs in the offensive basket. That is, we thought the Soviets cannot dare to strike us because we will have enough surviving missiles to penetrate any orthodox defense and destroy them in return. They would also have the same "mutual assured destructon (MAD)" capability, of course!

The MAD concept was aptly acronymmed - it was an insane idea from its inception. That is, the Soviets were not supposed to defend their cities **and** populace, and neither were we. That way, you see, we could destroy their citizenry at will, and they could destroy ours at will. We deliberately agreed to that, thinking - in our insanity - that the Soviets agreed also.

Of course the Soviets weren't playing the same lunatic's game at all. They simply fed our own garbage back to us, and we importantly thought we were negotiating something. Unknown to us, they were secretly building and deploying scalar EM defenses even then. Since we didn't know of any other defense, we assumed the Soviets could not defend their citizenry with ABMs any better than we could defend ours with ABMs. So we blithely scrapped our ABMs.

The high government officials of the United States of America grossly violated our constitution and their sworn oaths of office. Our constitution specifically charges the government of the United States to defend the people of the United States. That means our officials are specifically charged with defending our people. Yet they deliberately agreed not to do so, and they deliberately sacrificed us in advance.

They committed treason of the highest kind, by deliberately surrendering us to total destruction anytime the big balloon goes up.

The constitution doesn't charge the government with surrendering our citizens to destruction under any circumstances. It charges the government with defending us against destruction.

Ronald Reagan is the first U.S. president in some time to see through the MAD concept. At least he stands forthrightly for defense. It's just a shame that the government and scientific leaders under him aren't aware of the Soviet scalar weapon developments, so they could brief him on these startling developments.

Be sure you understand what the government leaders before Reagan have been saving. For years, our official policy has effectively said to the Russians: "We will allow each side a token defense only. We deliberately will not defend ourselves, so that anytime you decide to strike us you can destroy us. In return, however, we do not think you will want to strike us, for we believe that - before we become ashes from that strike - we can get enough away at you, to destroy you as well. Of course we believe you are in the same sort of boat."

Then we said, "There! That's settled! What a relief! Nobody can strike anybody anymore. Now can we talk about partial disarmament and on-site inspection?"

The Soviets just kept their astonished amusement to themselves and kept building scalar defenses (and scalar offenses as well!). Their deception plan called for imbedding the scalar EM weapons in ordinary systems when possible, and hiding the scalar EM weapons tests in ordinary weapons tests when possible. Of course they had to be adamant in their opposition to on-site inspection; after all, even Western scientists, if allowed on site with the dual-mode weapons, might suspect something was different and possibly things were amiss.

The Soviet deception has worked like a charm. The U.S. MADmen who created and implemented the MAD doctrine have succeeded in prejudicing two generations of academicians and elected U.S. leaders against the need for effective defense. A vast wasteland of inane paper studies - learnedly dealing with ABM's, penetration tactics, leakage, force and counterforce, radar blackout, electronic warfare, etc. etc. - has been churned out by our military, industrial, and university "think tanks" to clog the minds, efforts, and literature of our defense and governmental establishments.

Our homeland has no effective ABM defense (and very little defense against aircraft or subsonic cruise missiles).

Our field army has no effective ABM defense (or air defense). Our naval forces have no effective ABM defense (although they are better defended against air attack than the field army). Yet ballistic missiles - and to some extent cruise missiles - have supposedly been our greatest threat for decades, followed closely by the secondary threat of massed aircraft attack.

A cynic might take the stand that, if our Defense Department hasn't been allowed to defend us (with deployed weapon systems, not by "paper studies") against what we ourselves have proclaimed is our biggest threat, then why is it called the Defense Department? Why not call it the No-defense Department'?

Understand, a great many fine, hard-working people in DoD have certainly tried to get adequate defenses developed and deployed. The sheer weight of the bureaucracy and its mind-numbing entanglements has prevented it.

But it's even worse. Our bureaucrats - both in government and in "big, organized science" - have been so caught up in the "Russians are really just ignorant peasants" syndrome and the "not-invented-here" (NIH) syndrome that they've not recognized the greatest scientific and technical breakthrough in history. Such a breakthrough - far greater in importance that the nuclear bomb has been made, developed, and deployed by the Soviet Union, all in secrecy and behind the smokescreen of a masterful deception plan.

We've totally missed the most incredible "secret superweapons" development program of all times, and the worldwide testing of the weapons themselves.

Hiroshima and Nagasaki should serve as object lessons in the price of ignorance of such technological breakthroughs.

History does repeat itself. But this time it's not we Americans who got the growl new superweapon first.



Slide 076: Clear Communications

Now let us rapidly give some unique capabilities that one can do with scalar EM in smaller things. Not only can scalar EM weapons be used in the big "continent burning" strategic weapons, but they can also be used for a variety of smaller defense tasks.

For example, one can establish a zero reference anywhere one wishes in an ordinary carrier. Inside that zero, one can establish as many independent "carriers" as one wishes, and hide them completely from ordinary detectors.

The way to do that is easy. Take as complex a signal as you wish. Subtract it from zero. That gives a "complement" which, when summed with the original signal, will produce the zero. Then only a scalar detector can go inside the zero and pull out the individual components.

So take a carrier wave. Let the enemy jam it completely, with gobs of power.

Your scalar communication channel stays serenely there, calm and unjammed. The enemy thinks you're jammed and can't communicate. Meanwhile, you continue to communicate just fine.

Or be real smart. Take one of those components inside the first zero. Pick a zero reference inside it. Hide still more carrier components inside the second zero. Do this as many times as you wish.

You can put all the telephone calls in the United States of America on one carrier. And you can keep them clear, right through total jamming.



Slide 077: Unique Communications

But that's still not all.

You can also communicate with your submarines underwater. High data rate. Chat away as you wish. You can scramble, frequency hop, encrypt, the works. They can also communicate back to you.

Remember. EM force fields of any appreciable frequency won't travel through the water. Natural EM potentials grab charged particles and ions, so they won't travel through the ocean either. But artificial potentials don't grab onto charged particles or ions, and they will go through the ocean quite nicely.

Everything - aircraft, ships, shore installations, submarines, etc. - can communicate like gangbusters if they possess scalar EM technology.

In fact, you can even build scalar EM underwater radar if you wish.

The airborne scalar EM radar can see under the ocean with a little adjustment. perhaps as well as a conventional side-looking radar sees distant targets today, The airborne scalar EM radar can detect and track the underwater submarine while tooling along.

In fact, the airborne scalar EM radar can then destroy the sub, by using a **little** scalar interferometry. And it's even possible to do scalar interferometry with a single transmitter! How, is proprietary to a friend.

In fact, you can even use your enemy's jamming transmission as a "wire" along which to establish your scalar EM channels. You can use these scalar channels In the "weakly endothermic mode" to locate his transmitter and "lock-in" on it. You can "walk" the lock-in right past his encryption function to the "clear" Input, and receive and record that in the clear. All this from a distance.

You can then destroy his equipment if you wish, or just continue to monitor him in the clear if it's important to do so. Perhaps now we can understand what the decades-long weak microwave radiation of the U.S. Embassy in Moscow is all about. Or why the Soviets are building a nice new Embassy, bristling with antennas, on the high ground in Washington, D.C.



MINE COUNTERMEASURES – ORTHODOX SYSTEM

Slide 078: Mine Countermeasures—Orthodox System

Take something like mine countermeasures, for example. Finding and destroying mines - particularly those placed on the bottom in relatively shallow areas such as ports and rivers - is a really tough problem.

Presently it's often done as portrayed on this slide.

Here a minehunter ship uses an underwater sonar to locate the mine, or what resembles a mine. Then it directs a submersible robot vehicle to proceed over to the object and examine it with an underwater television camera. If it's a mine, the submersible places a remotely operated charge beside it, then chugs away. When it reaches a safe distance away, the charge is exploded, causing the mine to detonate.

A very painful process. Very time consuming, and very difficult.



MINE COUNTERMEASURES – SCALAR EM SYSTEMS

Slide 079: Mine Countermeasures—Scalar EM Systems

Now try the same thing while using scalar EM underwater systems. The scalar EM acquisition system is really a sophisticated scalar radar. It scans a large area rapidly, locating moored mines, bottom-planted mines, and drifting mines.

The acquisition system is also a scanned "underwater eye." The operator in the surface vessel can tell whether or not it's a mine he's located.

Once the target mine is detected, a computer computes the firing parameters for a scalar interferometry pulse to hit it and destroy it. The operator fires the pulse, destroying the mine.

The same system that detects the mine at a distance identifies and destroys it at a distance. In this way large areas can be quickly scanned and swept clean of mines.

If a suspicious object is detected and one is still not quite sure it's a mine, shoot it anyway! If it's a mine, it explodes. If it's just a rock, nothing happens. So the same system can do "discrimination by fire."

The same system is useful to destroy midget submarines, bottom crawlers, etc.

It can also wipe out whole arrays of underwater sensors by electromagnetically dudding them.

It can take on a sub if it has to! Here it would just gently kindle EM energy inside the sub's controls, causing it to lose control of all its systems. The sub would then sink to crush depth and implode. The scalar EM mine sweeping system could, of course, simply "blow" the sub, but might itself get caught in the resulting explosion.

SCALAR ANTI-PERSONNEL WEAPON



Slide 080: Scalar Anti-Personnel Weapon

From a military viewpoint, these scalar EM weapons are really quite all-around weapons.

For example, they are very lethal against personnel.

Set in the "high intensity pulse mode," one blast and a person's nervous system is destroyed instantly. Total, instantaneous death results. One can blast away at entire groups of infantrymen, for example. It's the peak power that's important, not the average power. So the weapon doesn't require too much battery power.

Set on a lower intensity pulse mode, one zap can simply knock out a person, rendering him instantly unconscious.

Quite useful if one needs prisoners to interrogate. Also very silent, which is useful in operations employing stealth and surprise.


AFGHANISTAN
INSTANT DEATH
DEPLOYED ROCKET WITH DECOY GAS CHEMICALS
BODIES DO NOT DECAY FOR MORE THAN 30 DAYS

Slide 081: Afghanistan

The Soviets are employing just such a scalar "death ray" weapon in Afghanistan, apparently in the noses of some of their HIND helicopters.

These choppers usually fire gas rockets to camouflage the testing of the tactical scalar death ray. For example, they may fire rockets filled with nerve gas, and some persons will die convulsively from the chemical.

Those hit by the scalar EM weapon, however, have a most peculiar death **mode,**

Death comes instantly and totally. There is no convulsion, no response. The entire nervous system is destroyed instantly. Every living cell in the body is killed instantly, including all bacteria, germs, etc.

A body hit with this thing falls like a limp rag and lies where it falls. It doesn't decay in even 30-45 days. In a macabre fashion, it's been reduced to something like food irradiated with nuclear radiation; everything is killed, so the material is preserved for an extended period before any decay can set in.

Western military authorities have speculated that this strange death is due to some sort of eery new gas.

However, even with the most virulent gas, some seconds are required for a b**ody** to die. And while it's dying it goes into convulsions. Violent convulsions.

This eery, instant death that leaves a non-decaying corpse is not due to a **gun,** This is the signature of a high-powered pulse kill using a scalar EM weapon

The associated gas rockets are the disguise used to fool our intelligence analysts.

They're just part of the Soviet deception plan.

ADDITIONAL NOTES AND REFERENCES

15. For details of the mysterious, instant deaths in Afghanistan, see Yossef Bodansky, "Soviets testing chemical agents in Afghanistan," Jane's Defence Weekly, 1(13), Apr. 7, 1984, p. 508



SCALAR ANTI-TANK WEAPON

Slide 082: Scalar Anti-Tank Weapon

Such weapons are also effective against armored vehicles, for example.

They can be carried by personnel, mounted on vehicles, mounted in helicopters, etc.

They are truly all-purpose weapons.

An infantryman with a bazooka-sized scalar EM pulse weapon can easily knock out a tank with one shot. The armor has no effect; scalar EM goes right through conductive shielding and Faraday cages.

And with the same weapon he can knock out another tank, and another, and another...



SCALAR ANTI-AIRCRAFT WEAPON

Slide 083: Scalar Anti-Aircraft Weapon

And, if a helicopter or a fixed-wing aircraft attacks him, he can bring the same weapon to bear on it.

He can knock down a chopper or a jet. With one shot.

And another. And another.

Also, it's a line-of-sight weapon. He doesn't have to compute lead angle and all that jazz. Just aim, get the target in his sights, and pull the trigger.


RADAR INVISIBILITY
ENERGY CAPTURED (NO REFLECTION)
ACQ RADAR
TRACK RADAR
ENERGY BOTTLE (INTERFERENCE PATTERN BETWEEN FOURIER EXPANSION PATTERNS)

Slide 084: Scalar Anti-Aircraft Weapon

Another neat trick you can do with scalar EM is make an aircraft invisible to ordinary radar.

Just use multiple transmitters on the airplane to establish a spherical interference shell, in the bandwidth of the threatening radar, around the aircraft.

When the signal pulse (or continuous wave) from the ground-based radar strikes the "energy bottle" in the shell, it interferes with it and is diffracted, scattered, and partially absorbed.

The ground-based radar doesn't get any coherent return pulse or return signal reflected from the target.

Radars don't track aircraft; they track the reflection of their own signal bouncing off aircraft. No reflected signal, no aircraft - as far as a radar is concerned.

To shield against a passive radar (one which tracks emissions from the aircraft), just detect and complement your own emissions so that "near zeroes" result In the spectrum of interest.

Or do both, to protect against both.

It's even possible to cool the exhaust and heated surfaces of the aircraft by a scalar EM adaptation of electrostatic cooling. Theoretically it's even possible to cause the aircraft to "disappear" optically. Takes a bit of doing, but it's possible The basic scheme here is that, when a photon hits the target from a given direction, it's absorbed totally, and a corresponding or "matching" photon is emitted from the opposite side in the same direction the original photon was going. In that fashion, the light emitted from the target from one direction seems to have "passed through it" from the other direction.

Since that's what empty space does, then what a distant observer sees is "empty space," so far as he can tell.



AN EFFECTIVE PENETRATION AID (CM AGAINST ACQN & TRACKING)

MAIN RV
XLTR/XMTR ANTENNA
AUX #1
X/X ANTENNA
AUX #2
X/X ANTENNA
FOURIER EXPANSION
ENERGY BOTTLE
TRACK RADAR

Slide 085: An Effective Penetration Aid

Of course you can do the same thing for re-entry vehicles.

Use some multiple antennas on a vehicle. Or better yet, use satellite RV's to carry the extra transmitters necessary for scalar interferometry.

Deploy the interferometer RV's and activate the scalar EM transmitters. Place an energy bottle Fourier expansion interference shell around the ensemble in the bandwidth of interest.

Radars in that bandwidth now will be unable to detect the incoming ensemble. If nothing detects the threat, nothing is going to shoot at it or react to it.

This can also be used on a bus vehicle during midcourse, for example.



UNIQUE CAPABILITIES: ATM/AD/AARTY

Slide 086: Unique Capabilities: ATM/AD/AARTY

But the uniqueness of scalar EM devices and weapons doesn't end there.

You can hit lots of other threats that are presently difficult or impossible to effectively handle.

For example, on the tactical battlefield, the same scalar EM radar interferometer system can defend against tactical missiles (ATM role), aircraft (AD role), cruise missiles (ACM role), and even artillery and mortar shells (AARTY role).

How the devil, you might ask, can it defend against artillery and mortar shells?

Simple. Sweep the artillery or mortar barrage with closely spaced pulses. Sorta like a machinegun. Or more like a phased-array radar.

If the peak power in the sweeping pulses is sufficient, the explosives are sparked and detonated. Fuses are destroyed.

So even mortar and artillery rounds can be destroyed, by the same system providing air defense and anti-tactical missile defense.



UNIQUE CAPABILITIES

Slide 087: Unique Capabilities

That's still not all.

An incredible number of different types of targets can be attacked with scalar EM weapons.

For example, aircraft equipped with scalar EM weapons can attack targets such as loaded artillery pieces. The round in the chamber explodes, destroying the weapon.

It can also attack nearby stored ammunition. Again, the high explosive in the ammunition explodes, destroying the store.

Even underground missiles can be attacked. The scalar pulse will go right through the overhead cover and dud the electronics, including the nuclear warhead. It will also detonate the HE in the warhead and detonate the fuels and propellants.

A great variety of other targets can also be attacked, as we shall see.



UNIQUE CAPABILITIES

PERSONNEL
DIE
INSTANTLY
AMMUNITION
EXPLODES
FUEL
EXPLODES
ELECTRONIC
SYSTEMS
DUDDED

Slide 088: Unique Capabilities

For example, suppose one attacks a tank.

With scalar EM pulse, the personnel die instantly. Total personnel kill is achieved.

All electronic systems of the tank are dudded. Total systems kill is achieved.

The ammunition in the tank explodes. Total kill is achieved.

The fuel explodes. This is another total kill mechanism.

That tank has been killed totally, by a variety of mechanisms, all simultaneously.

That's a k-kill in any analyst's book.

And **don't** worry about retrieval and repair. That tank is finished permanently.

Even **the** most modern tank is just as vulnerable as the most obsolete.



UNIQUE CAPABILITIES

ELECTRICAL SYSTEMS DUDDED
PILOT DIES INSTANTLY
ENGINE FLAMEOUT
FUEL EXPLODES
ELECTRONICS DUDDED

Slide 089: Unique Capabilities

Suppose one attacks a fighter-bomber aircraft.

Again, the kill is catastrophic from multiple simultaneous kill mechanisms.

The pilot and crew die instantly. Total destruction of their nervous systems.

The electrical systems are dudded.

The electronics in all avionics and ordnance is dudded.

The fuel explodes.

HE in on-board or out-board ordnance explodes.

The jet engine flames out if the pulse is powerful enough.

That aircraft is finished. Permanently.

And it's point-and-shoot, line-of-sight.

Even the most modern aircraft is just as vulnerable as the most obsolete.


UNIQUE CAPABILITIES: PENETRATE SHIELDING
INSTANT DEATH OF SHIELDED PERSONNEL
HIGH PEAK PULSE POWER
WEAK AVERAGE POWER

Slide 090: Unique Capabilities: Penetrate Shielding

Shielding is ineffective.

The scalar pulse (or continuous wave) can go anywhere gravity can go.

It penetrates the steel hull of tanks and armored vehicles.

It penetrates underground shelters and bunkers.

It penetrates pillboxes and fortifications.

Foxholes are no protection. Just shoot through the earth into them.

There is no longer any place to hide.


MULTI-PURPOSE WEAPONRY

AMMO DUMP
GASOLINE DUMP
RADIOS AND COMMO GEAR
RADAR

Slide 091: Multi-Purpose Weaponry

These scalar EM weapons are all-purpose. Things such as ammunition dumps, radar systems, radios and communication gear, communications centers, gasoline dumps, etc. can easily be destroyed.

Not only that, but the weapons can be swept, giving area coverage.

You can hit both point targets and area targets.



MULTI-PURPOSE WEAPONRY

Slide 092: Multi-Purpose Weaponry

Look at what a weapon a helicopter becomes.

The same vehicle, equipped with scalar EM weapons, can engage and destroy jet aircraft, other helicopters, cruise missiles, personnel, and armored vehicles.

It can also hit all the other targets we've been talking about. Any vehicle equipped with scalar EM weapons becomes a formidable destroyer on the battlefield.

And "reconnaissance by fire" takes on a particularly lethal meaning.

For example, don't worry about the enemy in cover and concealment, or highly camouflaged.

Don't worry about decoys or dummy positions.

Just sweep the area with scalar EM fire. The actual targets will be discriminated by fire and destroyed.



MULTI-PURPOSE WEAPONRY

Slide 093: Multi-Purpose Weaponry

As can be seen on this slide, most targets of interest can be attacked.

A single aircraft can sink an aircraft carrier or destroy a battle cruiser from afar.

It can also destroy aircraft, ground installations, artillery, personnel, nuclear weapons storage sites, tanks, vehicles, fuels, and combustibles.



UNIQUE CAPABILITIES: HEAT EXTRACTION

- IN A ZONE, INSULATION HAS NO EFFECT.
- EXTERNAL HEATING HAS NO EFFECT.

SCALAR
INTERFEROMETER
(ENDOTHERMIC)
FROZEN TANK
FROZEN
SOLDIERS
IN ARCTIC GEAR

Slide 094: Unique Capabilities: Heat Extraction

Or one can get truly exotic.

To prevent destroying equipment and installations, the endothermic mode can be utilized.

Cold explosions can be used to freeze tanks, personnel, and equipment.

The equipment and tanks thaw out.

The personnel thaw out too, but they are dead when they do. Heaters and arctic clothing are no protection.



UNIQUE CAPABILITIES: COLD EXPLOSIONS

Slide 095: Unique Capabilities: Cold Explosions

For example, suppose three cold explosions, each 50 miles in diameter, are placed upon the front-line strength of NATO.

In seconds there is no longer any "front line strength" of NATO. Every living thing is frozen into a block of ice.

A few more of these things placed on selected rear area installations, and the battle is over before it gets started. Say in about one minute flat!

Suppose NATO is quickly defeated - say in two days. And then the Russians offer us a "Dunkirk." They agree to allow us to evacuate the beaten remnant of our forces.

Are we going to evoke a strategic nuclear exchange, or are we effectively "decoupled" from Europe? Particularly if the Soviets also offer sweeping accommodations to the Europeans, and they accept? If we punch the strategic button, we guarantee our own absolute destruction. (MAD doctrine and all **that,** old chap!)

Whether or not we could do anything to the Russians is a matter of conjecture.

For a demonstration, they could even invite us to launch a couple of missiles, and destroy them over our heads shortly after launch.

And they could take out a few submarines under the ocean, just to make it believable.

And destroy some SAC bombers that are orbiting on station.

Or take out a U.S. Naval Task Force, with a nuclear carrier, as a demonstration that they mean business.

Would a sane President go ahead and destroy us, or accept the Soviet's "Monroe Doctrine" and an "armistice"?

If the Soviets thought he was seriously contemplating ordering a nuclear strike, they could immediately destroy all our nuclear armaments where they sit. Our own weapons would obliterate us!

What would Congress do - after the Soviet Union had demonstrated its absolute power, offered a Dunkirk and armistice, and threatened our total destruction if we "reached for the holster," so to speak - when it realized the President might actually be contemplating evoking assured national suicide?

What would you do if you were a Congressman? If you were the President?


THE TRANSMITTER IS THE MAJOR WEAPON

Slide 096: The Transmitter is the Major Weapon

As shown on this slide, with scalar EM the transmitter becomes the major weapon on the battlefield.

Almost every type of target of any importance can be easily and effectively attacked and destroyed or nullified by scalar EM weapons.

Small wonder the Soviets do not discard their thousands of "old" radars!

How effective do you suppose some of their "old" transmitters on their "old" aircraft might be?

What chance do you think SAC bombers would have against thousands of "old" radar-directed gun sites and "obsolete" air defense missile sites?

Could it be that even something like the old SA-1 could be startlingly effective?


STAR WARS—THE FINAL FRONTIER?
SPACE-BASED SENSOR
CHEMICAL LASER BATTLESTATION
ELECTROMAGNETIC RAILGUN
MID-COURSE PHASE
SPACE-BASED SENSOR
EXOATMOSPHERE INTERCEPTOR
AIRBORNE SENSOR
POST-BOOST
TERMINAL PHASE
SUBMARINE-LAUNCHED BALLISTIC MISSILE
BOOST PHASE
ICBM
TACTICAL BALLISTIC MISSILE
BOOST
USA
GROUND-BASED RADAR SYSTEM
USSR
ENDOATMOSPHERE INTERCEPTORS
GROUND-BASED RADAR SYSTEM
EUROPE

Slide 097: Star Wars—The Final Frontier?

But what of our advanced concepts, such as the strategic defense initiative?

Here we show some of the expensive and complex components of that powerful system.

We have ground-based radars, endoatmospheric interceptors, exoatmospheric interceptors, airborne sensors, space-based sensors, chemically propelled interceptors, electromagnetic railguns, particle beam weapons, high energy lasers, etc. all tied together by a massive command and control system. This massive, expensive system is designed to detect and destroy missiles, including ICBMs, IRBMs, cruise missiles, SLBNs, etc.

The system detects the missile launches and engages them from launch on in to the terminal phase.

Massive systems. Electromagnetic marvels. Nuclear-pumped lasers of staggering power. Perhaps even x-ray and gamma ray lasers. Directed energy RF weapons. Stupendous railguns. Sensors everywhere. Giant webs of communications. Banks of computers and control systems.

And it's totally vulnerable to scalar EM interferometer weapons. Giant scalar EM "radars" can simply sweep through all that like a scythe through standing hay.

As it stands, it's obsolete before its design is even finished.

It's obsolete to Soviet scalar EM weapons that are already deployed and operationally tested in place!

Without scalar EM weapons and defenses, all our present weapons and concepts are deadly vulnerable.

The war is over before it hardly gets started. It's not a war; it's more like a clay pigeon shoot.

Understand, if orthodox science was all the Russians possessed, the Strategic Defense Initiative would be the way to go.

But they do possess something else, and presently they have all the trump cards in the deck.



COMPARISON OF EM CONCEPTS

CHARACTERISTIC	THEORY		
	CLASSICAL EM	QM VIEW	SCALAR EM (ARTIFICIAL o)
VACUUM SPACETIME	LINEAR NO CHARGE	LINEAR, CHARGED (VIRTUAL) STATISTICALLY	NONLINEAR, CHARGED (VIRTUAL) W/ DETERMINISTIC COMPONENTS
VIRTUAL SUBSTRUCTURE	NONE (FLUID EQUATIONS)	YES STATISTICAL	YES. STATISTICAL. DETERMINISTICALLY WEIGHTED
FORCE IN VACUUM?	CAUSE YES	EFFECT YES	EFFECT NO
ZERO FORCE FIELDS	NO EFFECT	BOHM-AHARONOV EFFECTS	SUBSTRUCTURE EFFECTS, ENGINEERABLE
POTENTIALS	FICTICIOUS	REAL, PRIMARY. STATISTICAL SUBSTRUCTURES	REAL, PRIMARY. DETERMINISTIC SUBSTRUCTURES
CAUSATIVE AGENT	FORCE FIELDS	POTENTIALS	POTENTIALS AND INFOLDED FIELDS OF SUBSTRUCTURES

Slide 098: Comparison of EM Concepts (Chart)

On this slide and the three that follow, we show a comparison of some of the major characteristics of the three kinds of electromagnetics.

We compare the classical, the quantum mechanical, and the scalar EM (electrogravitational) views of electromagnetics

Notice the differences between the three in regards to vacuum spacetime, virtual substructure, force, whether or not force exists in vacuum, the effect of zero force fields, potentials, and what is to be regarded as causative agents.



COMPARISON OF EM CONCEPTS

CHARACTERISTIC	THEORY		
	CLASSICAL EM	QM VIEW	SCALAR EM (ARTIFICIAL ø)
CHARGE CONSERVATION	YES	YES	NOT NECESSARILY
ACTION AT A DISTANCE	NO	NO, EXCEPT BOHM-AHARONOV EFFECTS	YES, SCALAR INTERFEROMETRY
SCALAR (ZERO-VECTOR) RESONANCE	NO	NO	YES
INERTIA IS ELECTRICAL	NO	NO	YES
GRAVITY IS ELECTRICAL	NO	NO	YES
MASS IS ELECTRICAL	NO	NO	YES

Slide 099: Comparison of EM Concepts (Chart)

Now note the differing views of charge conservation, action at a distance, scalar resonance, and whether inertia, gravity, and mass are electrical.



COMPARISON OF EM CONCEPTS

CHARACTERISTIC	THEORY		
	CLASSICAL EM	QM VIEW	SCALAR EM (ARTIFICIAL φ)
CHARGE	WITH MASS	WITH MASS	MASSLESS
RELATIVISTIC EFFECTS DUE TO	VELOCITY	VELOCITY, INTERFERING POTENTIALS	INTERFERING POTENTIALS
HIDDEN VARIABLE	NO	STATISTICAL, NEGLIGIBLE	DETERMINISTIC, MAJOR ROLE
VECTOR THEORY APPLIED TO EM	OK	OK	REQUIRES REVISION
VACUUM EM WAVE	TRANSVERSE	TRANSVERSE	LONGITUDINAL W/ SWIRLS
ENERGY/MASS CONSERVATION	YES	YES	NOT NECESSARILY, AN ENERGY CONSERVED

Slide 100: Comparison of EM Concepts (Chart)

Continuing, note the differences in the views of charge, what relativistic effects are due to, whether or not one has hidden variables and whether they are enginerrable, how vector theory is applied to electromagnetics, the nature of the EM wave in vacuum, and conservation of energy/mass.



SUMMARY (1)

- AHARONOV-BOHM EFFECT
  - VERIFIED
  - MESOSCOPIC SCALE (CENTIMETERS)
  - NEED MACROSCOPIC COHERENCE
  - POTENTIAL WEAPON IMPLICATIONS
  - PROBABLE SOVIET WEAPONIZATION
- 6 TO 8 ADDITIONAL ORDERS OF MAGNITUDE NEEDED

Slide 101: Summary (1)

Now we examine the three views for whether or not electro-gravitational waves exist and what they interact with, the number of required spacetime dimensions the type of geometry, the nature of a zero-summed EM vector, local and distant relativity aspects, and whether or not the probability states propagated by the Schroedinger equation can be deterministically engineered.

As can be seen from the last four slides, the three views are quite different, and the scalar EM view is drastically different.



SUMMARY (1)

- AHARONOV-BOHM EFFECT
  - ¤ VERIFIED
  - ¤ MESOSCOPIC SCALE (CENTIMETERS)
  - ¤ NEED MACROSCOPIC COHERENCE
  - ¤ POTENTIAL WEAPON IMPLICATIONS
  - ¤ PROBABLE SOVIET WEAPONIZATION
- 6 TO 8 ADDITIONAL ORDERS OF MAGNITUDE NEEDED

Slide 102: Summary (1)

In summary, we can now state unequivocally that the Aharonov-Bohm effect has been conclusively proven, at least for the mesoscopic scale over a few thousand Angstroms, and possibly over a few centimeters.

But in these experimental proofs; the "natural" type of potential has been used, it is basically incoherent in its substructure, dooming the effect to stay small.

By utilizing macroscopic EM force fields and waves to zero-sum and comprise artificial potentials, the coherence can be maintained over a macroscopic distance - even for hundreds of thousands of kilometers.

The weapons implications - only some of which we have set forth in this treatise - are mindboggling.



SUMMARY (2)

- ZERO-VECTOR (SCALAR) EM SYSTEMS
  - ¤ SCALAR EM WAVES
  - ¤ KEY TO ELCTROGRAVITATION
- DETECTORS
  - ¤ INITIAL DETECTORS DEVELOPED
  - ¤ NEED IMPROVED DETECTORS
- INITIAL THEORY BEGUN
- PRELIMINARY EXPERIMENTS SUPPORT

Slide 103: Summary (2)

Zero-vector (scalar) EM systems are the key to scalar EM waves, which are actually electrogravitational waves.
Scalar wave detectors nave been developed and are being improved. Further improvement is needed. This development is limited only by funds.

The initial theory has been begun. More work is needed. Again, this development is limited only by funds.

Preliminary experiments support the scalar EM concepts.

Equipment can be designed and made to work electro-gravitationally.

And it has been.



SUMMARY (3)

- INTERFERENCE PHENOMENA ARE KEY
  - ¤ ACTION AT A DISTANCE
  - ¤ EXOTHERMIC MODE
  - ¤ ENDOTHERMIC MODE
  - ¤ 3-D FOURIER EXPANSIONS (TRUNCATED)
- EFFECTS IN/ON NUCLEUS
- NOT ENERGY TRANSMISSION THROUGH SPACE
- SHIELDING INEFFECTIVE

Slide 104: Summary (3)

Interference phenomena are key.

One can get action at a distance - even over hundreds of thousands of kilometers.

One can engineer gravitational and inertial effects.

One can engineer the nucleus, including transmute it, easily and cheaply. One could clean up all the nuclear wastes.

Electromagnetic energy can be produced at a distant target, or extracted from a distant **target.**

This is is not energy transmission through space in the form of EM force fields. Instead, it is transmission through spacetime in the form of electrogravitational potentials.

Conventional EM shielding is ineffective against scalar EM.



SUMMARY (4)

- MOST SYSTEMS ARE VULNERABLE
  - ¤ ELECTRONICS (INCLUDING OF FUZING/WARHEAD)
  - ¤ PERSONNEL
  - ¤ EXPLOSIVES/PROPELLANTS/FUELS
  - ¤ ORDNANCE
  - ¤ SHIPS/SUBMARINES/TORPEDOES
  - ¤ AIRCRAFT/HELICOPTERS/MISSILES/DRONES
  - ¤ TANKS/APCs/WEAPONS CARRIERS/SP ARTY
  - ¤ COMMUNICATIONS/SATELLITES/RADARS/C^3I
  - ¤ DEW SYSTEMS
  - ¤ SURVEILLANCE/SENSOR SYSTEMS
  - ¤ MINES/ARTY ROUNDS/NUCLEAR WARHEADS

Slide 105: Summary (4)

Almost every weapon system we presently have - or are developing - is totally vulnerable to scalar EM weaponry.

This includes personnel, electronics (including fuzing and warhead), explosives, propellants, fuels, ordnance, ships, submarines, torpedoes, aircraft, helicopters, missiles, drones, rockets, tanks, armored vehicles, weapons carriers, self-propelled and towed artillery, communications, satellites, radars, command and control, directed energy weapon systems, surveillance and sensor systems, mines, artillery rounds and ammunition, nuclear warheads, etc.

We are in dire straits. We need a "Manhattan Project" of the highest priority. Now!

The Soviets have already had the equivalent of seven or eight Manhattan Projects in this area.



SOVIET DEFENSE AGAINST MISSILES

"In our country the problem of eliminating rockets in flight has been successfully solved by Soviet science and technology...

It is interesting to note that the problem of anti-missile defense is far from being solved in the West."

SOKOLOVSKIY
MILITARY STRATEGY
THIRD EDITION, 1968

Slide 106: Soviet Defense Against Missiles

Here is a significant statement by Sokolovskiy, contained in Military Strategy, 3rd edition, 1968.

This is not propaganda. The Soviets really do have an effective missile defense. We do not. At the present rate we're going, we may not have one in the year 2000 - if we live that long.



SURPRISE BY USING SECRET WEAPONS

> "Each side secretly develops new means of warfare in order to employ them unexpectedly. History knows many examples how the employment of a new weapon initially gave considerable success because the enemy, caught unawares and not knowing the combat capabilities of this weapon, was for some time incapable of effective counteraction."

V. YO SAVKIN
THE BASIC PRINCIPLES OF OPERATIONAL ART AND TACTICS
MOSCOW, 1972

Slide 107: Surprise by Using Secret Weapons

The Soviets took to heart the lesson of our secret development of the atomic bomb. Thrust suddenly upon a fanatical nation, the atomic bomb brought the empire of Japan to its knees.

Other lesser examples - such as the impact of the German V-l and V-2 missiles and jet fighter - also were not lost on the Soviets.



SOMETHING RUSSIA DOESN'T WANT THE U.S. TO KNOW

"Of particular importance is basic research aimed at discovering still unknown attributes of matter, phenomena, and the laws of nature, and developing new methods for their study and use to reinforce the state's defense capability."

COMMENTS:

¤ PORTION OF A BOOK BY MARSHALL GRECHKO

¤ DELETED FROM ENGLISH TRANSLATION, BY SPECIFIC REQUEST OF THE U.S.S.R.

Slide 108: Something Russia Doesn't Want the U.S. to Know

But Marshall Grechko said it even plainer.

He made it clear that the Soviet Union has actively searched for great technical breakthrough areas, particularly in discovering new laws of nature, unknown attributes of matter, and new phenomena, and developing their use for defense.

He made it so clear that the Soviet Union formally requested the U.S. State Department to have deleted from its. English translation that portion of his book.

That is a positive signature that the statement is exceedingly sensitive to the Soviets. In other words, it's a real tipoff.

So of course the State Department leaned on the publisher and got that section eliminated.

ADDITIONAL NOTES AND REFERENCES

1. Nikola Tesla, "The Problem of Increasing Human Energy," Century magazine, June 1900, p. 208-209. In this article Tesla spoke of using standing waves to produce distant effects and locate objects such as ships. At this point he was thinking of a scalar radar locator, something more advanced than even our radar today. It was also capable of producing electrical effects at any part of the globe. To quote: "Stationary waves... mean something more than telegraphy without wires to any distance... For instance, by their use we may produce at will, from a sending station, an electrical effect in any particular region of the globe; we may determine the relative position or course of a moving object, such as a vessel at sea, the distance traversed by the same, or its speed..."

2. Nikola Tesla, "The True Wireless," Electrical Experimenter, May 1919, p. 87.

3. T. E. Bearden, Comments on the New Tesla Electromagnetics: Part I: Discrepancies in Present EM Theory, Tesla Book Co., 1580 Magnolia, Millbrae, CA 94030, 1982.

4. T. E. Bearden, Toward a New Electromagnetics: Part III: Clarifying the Vector Concept, Tesla Book Co., 1580 Magnolia, Millbrae, CA 94030, 1983.

5. T. E. Bearden, Toward a New Electromagnetics: Part 4: Vectors and Mechanisms Clarified, Tesla Book Co., Millbrae, California, 1983, p. 6, 39.

6. T. E. Bearden, Solutions to Tesla's Secrets and the Soviet Tesla Weapons, Tesla Book company, 1981

7. T. E. Bearden, Tesla's Secrets and the Soviet Tesla Weapons, 1 hr. 40 min. videotape, Weather Engineering, POB 1472, Huntsville, AL 35807, 1981.

8. T. E. Bearden, Soviet Weather Engineering Over North America, 1-hr. videotape, Weather Engineering, POB 1472, Huntsville, AL 35807, 1985.

9. T. E. Bearden, Star Wars Now! The Bohm-Aharonov Effect, Scalar Interferometry, and Soviet Weaponization, Tesla Book Co., 1984

10. Stefan T. Possony, "The Tesla Connection," Defense & Foreign Affairs, Aug. 1984, p. 12-14, 27.

11. Stefan T. Possony, "Psy-War: Soviet device experiment," Defense & Foreign Affairs Daily, 12(104), June 7, 1983, p. 1-2. Reports on Dr. Ross Adey's investigation of the Soviet LIDA device which is used to bombard human brains with radio waves in the 40 MHz region. Also reports on work by A. S. Davydov of the Ukrainian Academy of Sciences, who discovered how the blood-brain barrier can be penetrated by low-frequency radio waves so that brain cells are affected.

12. Fritz Albert Popp, "Photon storage in biological systems," in Electromagnetic Bioinformation: Proceedings of the Symposium, Marburg, Sep. 5, 1977. Edited by Fritz Albert Popp et al, Munchen, Wien, and Baltimore, 1979, p. 123-149. Dr. Popp has discovered, both theoretically and experimentally, that mitogenetic radiation from cells can be seen as a sort of "waste" from a virtual electromagnetic field with a high coherence. This field has a tendency to become stationary over the whole organism. In addition, it includes the storage of "virtual" coherent photons. (In other words, there is a master EM field with high coherence, stationary over the whole body. This is the cells' master control system. Storage of virtual photons -- i.e., scalar signals -- occurs in this field.).

13. To gain an appreciation of the Aharonov-Bohm effect, see Y. Aharonov and D. Bohm, "Significance of Electromagnetic Potentials in the Quantum Theory," Physical Review, Second Series, 115(3), Aug. 1, 1959, p. 485-491. For an exhaustive discussion of the Aharonov-Bohm effect and a large number of references, see S. Olariu and I. Iovitzu Popescu, "The quantum effects of electromagnetic fluxes," Reviews of Modern Physics, 57(2), April 1985. See also Bertram Schwarzschild, "Currents in normal-metal rings exhibit Aharonov-Bohm effect," Physics Today, 39 (1), Jan. 1986, p. 17-20.

14. For details of the mysterious explosions of six major Soviet missile ammunition storage sites in seven months, see photograph, Jane's Defence Weekly, 2(3), July 28, 1984, p. 92; see also Mark Daly, "Goa and Goblet SAMs in Severomorsk explosion," Jane's Defence Weekly, 2(6), Aug. 18, 1984, p. 224; Derek Wood, "Soviets' northern fleet disabled... 'not viable' for six months," Jane's Defence Weekly, 2(1), July 14, 1984, p.3; Derek Wood, "Six explosions in the past seven months," Jane's Defence Weekly, 2(1), July 14, 1984, p. 3; John Moore, "The aftermath of Severomorsk," Jane's Defence Weekly, 2(6), Aug. 18, 1984, p. 224.

15. For details of the mysterious, instant deaths in Afghanistan, see Yossef Bodansky, "Soviets testing chemical agents in Afghanistan," Jane's Defence Weekly, 1(13), Apr. 7, 1984, p. 508.

16. For details of the Enhanced-V cloud signature of severe weather, see Gary Ellrod, "Dramatic examples of thunderstorm top warming related to downbursts," National Weather Digest, 10(2), May 1985, p. 7-13; T. J. Fujita, "Manual or Downburst Identification for Project Nimrod," SMRP Research Paper No.156, University of Chicago, 1978; D. W.McCann, ., The Enhanced-V: A Satellite Observable Severe Storm Signature," Monthly Weather Review, 111, 1978, p. 887-894.

17. For a good discussion of the modern view of the vacuum, see
I.J.R. Aitchison, "Nothing's plenty: The vacuum in modern quantum field theory," Contemporary Physics, 26(4), 1985, p. 333-391.

18. For a discussion of the ring interferometer experiments related to quantum and gravitational effects, see G.E. Stedman, "Ring interferometric tests of classical and quantum gravity," Contemporary Physics, 26(4), 1985, p. 311-332.

19. For information on self-induced transparency with pulsated light, see E. L. Hahn, Scientific American, June 1967. This is a scalar EM effect. The phenomenon is observed only in insulators, not in conducting materials. A dielectric tends to stop the flow of electrons, thus stopping the bleed-off of the Kaluza-Klein 5-potential as EM force fields. Thus through the insulator or dielectric, an electrogravitational pulse is transmitted. When this pulse emerges from the other side of the

dielectric, then electrons are free to move again and form ordinary EM fields, resulting in resumed EM bleed-off of the KK (Kaluza-Klein) 5-potential. Thus ordinary photons strike the dielectric, changing into electrogravitational waves which transit the opaque dielectric, and these EG waves transform back to EM waves on the far side of the dielectric. Advanced scalar EM application of this effect can make an object optically invisible.

20. For a lucid and profound presentation of the entire subject of elementary particle physics and quantum field theory, see T. D. Lee, Particle physics and introduction to field theory, Harwood Academic Publishers, New York, 1967. Subjects covered include those at the forefront of current research. Chapter 16, "Vacuum as the source of asymmetry," is particularly important. Here Lee concisely covers the idea of degenerate vacuum states, vacuum structuring, and vacuum effects causing symmetry breaking (violation of conservation laws). An excellent coverage of asymmetries and observables is given on p.181-188. For example, whenever symmetry is spontaneously broken, a nonobservable (virtual entity) has become observable. Thus there exist mechanisms for the direct translation between virtual and observable states.

Most engineers are unaware that physics has already rigorously proven (both theoretically and experimentally} that conservation of energy can be physically violated, even by excitation of the vacuum.

However, in the present assumption of a randomized virtual microstructure of a vacuum potential, these broken symmetry effects are individually confined to very small microlevels. For example, on p. 383, Lee points out that the microscopic structure of the scalar vacuum field (i.e., of vacuum charge or "potential") is not utilized.

This of course is reasonable if all vacuum potentials used in particle physics are treated as having a randomized microstructure of virtual particle flux vectors. Since any appreciable directional coherence in such a randomized microstructure could persist only over extremely tiny distances, then the microstructure of vacuum degenerate states has negligible local effects in ordinary macroscopic systems.

In other words, these conservation violation effects would be very difficult to coherently capture and utilize to provide "free energy, emerging from the vacuum."

The randomized momentary coherences, however, are responsible for the violent microfluctuations of the EM fields, well-known in classical electrodynamics. An approach such as taken by Yater or Moray would be necessary to achieve a vacuum energy tap under such conditions. To achieve usable macroeffects, a very large collection of charge or magnetic material, etc. would be required before the probability of usable coherences would become sufficiently large. Therefore this area is neglected in practical physics and engineering.

However, this is precisely where scalar EM is lost in conventional theory and engineering practice. In scalar EM, the coupling together of macroscopic EM force field vectors into a summed zero system means that the vacuum potential's microstructure is now macroscopically ordered by that system. Further, it is sustained during translation through space. In such case, one has produced directional gravitational potential gradients that have macroscopic range and form. Further, by coherently varying the amplitude of the individual components of the zero vector system, a gravitational wave -- a controlled oscillation of the degenerate states or vacuum -- is produced. By processing the EM components, this gravitational wave can be narrowed, formed into a beam, and projected. Two such beams can be interfered, even at a great distance, producing G-interference and causing EM effects to emerge in the distant interference zone. Thus scalar EM profoundly affects quantum mechanics, quantum field theory, particle physics, general relativity, and electromagnetics.

21. For some strong and pertinent critique of present scientific bias, see Ruggero Maria Santilli, Ethical probe on Einstein's followers in the U.S.A.: An insider's view, Alpha Publishing, POB 82, Newtonvllle, MA 02160. Santilli is a highly published physicist and the editor of a refereed scientific journal, the Hadronic Journal. After lengthy attempts to correct injustices within the Scientific system, to no avail, he finally has gone public with his specific charges. Santilli references senior Russian physicist G. Yu. Bogoslovsky, whose 1984 paper "Generalization of Einstein's relativity theory for the anisotropic spacetime," whose research would have been impossible in the U.S. Quoting Santilli: "He would have been discredited, humiliated, and chased out of these institutions [Harvard, M.I.T., and Yale] beyond any reasonable doubt by ample documentation on similar cases." Again to quote Santilli: "Papers bearing the title of 'Generalization of Einstein's relativity' are routinely permitted with human dignity at Moscow University in the U.S.S.R., but they are absolutely inconceivable today at the departments of physics of Harvard University, of the Massachusetts Institute of Technology, of Yale University and of other similar institutions in the U.S.A., as numerous senior scientists would readily testify."

You see, dear reader, there has been a deep scientific conspiracy in the U.S. to prevent any change in the severe restrictions placed on general relativity by Einstein. This has reduced GR to a sort of "special relativity, with only distant perturbations." Specifically, it has excluded scalar electromagnetics and branded as heresy the inconceivable idea that general relativity could be local, and engineerable.

Now you know why the Soviets have been able to develop these monstrous weapons for over three decades while our scientists slept at the wheel. Scientific arrogance and pride has been our greatest enemy.

See also Bryan G. Wallace, "The great speed of light in space coverup," Scientific Ethics, 1(1), Feb. 1985, p. 2-3; "Radar testing of the relative velocity of light in space," Spectrosc. Lett. 2, 1969, p. 361; Wallace, "Letter to the editor," Physics Today, 36(1), 1983, p. 11; "Letter to the editor," Physics Today, 37(6), 1984, p. 15. See M.E. Ash et al, Astron. J., 72, 1967, p. 72. Direct experiments on Einstein's second postulate, in the 1961 interplanetary radar contact with Venus, challenge whether relativity is correct. Variations of over 30,000% of the best possible general relativity fit the MIT Lincoln Lab could generate were measured. The variations were not random but contained diurnal, lunar, and synodic periodic components. See also Bryan G. Wallace, Spectrosc. Lett. 4, 1971, p. 79 for an analysis of published 1961 data on the interplanetary radar contact with Venus that concludes that the data showed a component that was relativistic in the Galilean c+v sense. See also Wallace, "The Unified Quantum electrodynamic ether," Foundations of Physics, 3, 1973, p. 381. which details Measurements strongly challenging the Einstein assumption of the constant velocity of light, and deals with the nature of the ether. See also Thomas E. Phipps, Jr., "Critique of accepted theories of special relativity and electromagnetism," Scientific Ethics, 1(2), Apr. 1985, p. 17-23.

22. For a sample of Soviet scientific freedom from narrow-minded bias in general relativity, see V. I. Denisov and A. A. Logunov, "The inertial mass defined in the general theory of relativity has no physical meaning," Teor. i Matemat. Fizika, 51(2), May 1982, p. 163-170 (In Russian). See also A. A. Vlassov and V. I. Denisov, "Einstein's formula for gravitational radiation is not a consequence of the general theory of relativity," Teor. i. Matemat. Fizika, 53(3), Dec. 1982, p. 406-418. Here we find that the intensity of gravitational radiation and the total intensity determined in the general theory of relativity in accordance with Einstein's formulas depend on the choice of the coordinate system, so that they can be made to vanish or even become negative. [Note by T.E.B.: If local curvature is

engineerable, as in scalar EM, the local choice of coordinate systems can itself be directly engineered. This clearly implies that scalar EM can thus produce either "positive" intensity radiation or "negative" intensity radiation; thus it can "produce energy at a distance" or "extract energy from a distance.]
Continuing with Denisov: This result is a particular consequence of the general assertion to the effect that in general relativity there are no energy-momentum conservation laws for a system consisting of matter and the gravitational field. [Note by T.E.B.: Thus we can have an energy source or energy sink appear in the distant interference region, where matter has been lifted from the Dirac sea and exposed to the highly nonlinear interfering EG fields.]. See also V. I. Denisov and A. A. Logunov, "New theory of spacetime and gravitation, "Teor. and Matemat. Fizika, 50(1), July 1982, p. 3-76. Points out that ". . . the gravitational field in general relativity is completely different from other physical fields and is not a field in the spirit of Faraday and Maxwell." (p. 3, English version).

23. In the Proceedings of the Tesla Centennial Symposium, an IEEE Centennial Activity, Colorado College, Colorado Springs, Colorado, Aug. 9-11, 1984, see Richard A. Blade, "Modification of Maxwell's equations in free space to account for nonzero photon mass and scalar electromagnetic waves," p. 91-92; Jack Y. Dea, "Scalar fields: their prediction from classical electromagnetism and interpretation from quantum mechanics," p. 94-98; Robert W. Bass, "Self-sustained non-Hertzian longitudinal wave oscillations as rigorous solutions of Maxwell's equations of electromagnetic radiation," p. 89-90; T. E. Bearden, "Tesla's electromagnetics and its Soviet weaponization," p. 119-138.

24. To see the limiting assumptions imposed on general relativity that results in the severely restricted "ordinary general relativity" taught in almost all Western universities. see Charles W. Misner, Kip S. Thorne and John Archibald Wheeler, Gravitation, W. H. Freeman and Co., San Francisco, CA, 1973, p. 19-21, 71-72, 367-369. Among other things, these arbitrary restrictions save the conservation laws. When they are removed. the conservation laws can be violated.

25. Several anomalous events -- skyquakes, booms, or earthquakes -- have been documented in Europe. See H. W. Haak. "The Seismic event of November 9, 1983: Earthquake or sonic boom." Seismic Activity in Western Europe, (With particular consideration of the Liege Earthquake of November 8, 1983), Ed. by Paul Melchior, D. Reidel Publishing Co., 1985, p. 215-222. For such events in the United States, see S. Claflin-Chalton and G. J. MacDonald, "Sound and light phenomena," The Mitre Corporation, McLean, Virginia 22102, Nov. 1978.

26. Fundamental experiments were performed by Eotvos et al. in the early 1920s. See R.V. Eotvos, D. Pekar and E. Fekete, Ann. Phys. (Leipzig) 68, 1922, p. 11. Actually a fifth force of nature due to hypercharge may have been found by these experiments. See Ephraim Fischbach et al. "Reanalysis of the Eotvos experiment," Physical Review Letters, 56(1), Jan. 6, 1986, p. 3-6. See also F. D. Stacey and G. J. Tuck, Nature 292, 230 (1981); S. C. Holding and G. J. Tuck, Nature 307, 714 (1984); G. W. Gibbons and B. F. Whiting, Nature 291, 636 (1981); F. D. Stacey, in Science Underground, edited by M. M. Nieto et al., AIP Conference proceedings No. 96, (American Institute of Physics, New York, 1983, p. 285. See also S. H. Aronson et al, Physical Review Letters 48, 1982, p.1306; Physical Review D 28, 1983, p. 476, 495. Also, comparison of satellite and terrestrial determinations of the gravitational field constant reveals significant disagreement: see R. H. Rapp, Geophys. Res. Lett. 7, 1974, p. 35; Bull. Geod. 51, 1977, p. 301.

27. John J. A. O'Neill. "Tesla cosmic ray motor may transmit power 'round the earth: Famed scientist, on eve of 76th birthday, says he has succeeded in harnessing 'penetrating rays' to operate small motive device." Brooklyn Eagle, July 10,1932. Tesla reported he had harnessed "cosmic rays" and caused them to operate a small motive device. Tesla's use of "cosmic rays," however, encompassed scalar EM radiation. Tesla later seems to have progressed to a simpler motive unit. In the Kansas City Journal-Post, Sep. 10, 1933, he stated: My power generator will be of the simplest kind -- just a big mass of steel, copper and aluminum, comprising a stationary and rotating part, peculiarly assembled." A similar type of "gravitational turbine" seems to have been invented by John Bedini.

28. To see just how arbitrary and postulational are present "definitions" of mass and force, see Robert Bruce Lindsay and Henry Margenau, Foundations of Physics, Dover Publications, New York, 1963, p. 283-287. Note on p. 283 that a "field of force" at any point is actually defined only for the case when a unit mass is present at that point. Also see Richard P. Feynman, Robert B. Leighton, and Matthew Sands, The Feynman Lectures on Physics, Addison-Wesley, New York, Vol. 1, 1963, p. 2-4 for a definition of the electric field in the context of its potentiality for producing a force. This problem did not exist for the original foundation of electromagnetic force fields in vacuum, since the vacuum was assumed to be a material ether. With the modern view a nonmaterial ether has emerged, yet the classical electromagnetic theory has not been made sufficiently rigorous in distinguishing "observable" and "virtual" electromagnetic force fields.

29. E. P. Battey-Pratt and T. J. Racey, "Geometric Model for Fundamental Particles," International Journal of Physics, Vol. 19, No. 6, 1980, p. 437-475.

30. Some years ago, Dr. William Tiller produced very important "free A-field" theoretical work which showed waves which did not fall off as $1/r^2$. Interesting theoretical work in scalar wave theory has also been advanced by Dea. See Jack Dea, "Fundamental Fields and Phase Information," presented at the 1985 U.S. Psychotronics Association Conference, Bergamo Center, Dayton, Ohio, July 1985. Dea has formulated an important theory for vacuum EM scalar waves, derived from Maxwell's equations with zero E and B fields. He predicts waves whose intensity falls off with distance as $1/r$ instead of $1/r^2$, and detection of these waves by various means. He shows simple generators for the waves. Detection is quantum mechanically by electron interference, not by single electrons. Thus such scalar waves will pass through normal Faraday shields. In his theory Dea does not address the question of spin vortexes in vacuum scalar waves. It is the present author's view that all vacuum waves are scalar waves, and the primary distinction between the "transverse" EM wave and the longitudinal scalar wave is simply the presence or absence of spin-vortexes. Indeed, one may argue that the present "vector wave" EM theory can be replaced by a scalar wave theory. In 1903 Whittaker proved that any vector field can be replaced by two scalar fields. See E. T. Whittaker, Proc. Lond. Math. Soc.1, 367, 1903. By implication, since a vector wave is simply a moving vector field, it can be replaced by two moving scalar fields.

31. David Jones, "Israel's Secret Weapon," Weekend Magazine, Dec.17, 1977.

32. John Hutchinson, private communication. Masses of wood, metal, etc. -- some weighing over 60 lbs. -- have been levitated by Hutchinson.

33. For a description and details of the April 9, 1984 incident off Japan, see Daniel A. Walker, Charles S. McCreery, and Fermin J. Oliveira, "Kaitoku Seamount and the Mystery Cloud of 9 April

1984," Science, 227(4684), Feb. 8, 1985, p. 607-611. See also transcription from Japan Airlines flight 036 to Anchorage International Flight Service, 9 April 1984, at 1406 Greenwich mean time, Federal Aviation Administration (FAA) — Alaska Region; Jim Derry, Special Agent, FAA-Alaska Region, interviews with Captain C.H. McDade, Japan Airlines Flight 036, with Captain Cornelis Vander Berg, KLM Royal Dutch Airlines Flight 868; with First Officer Reint Sol, KLM Royal Dutch Airlines Flight 868, and with Captain Mike Howe, Flying Tiger Lines Flight 078, Anchorage Daily News, 10 April 1984, p. A-l; Anchorage Daily News, 12 April 1984, p. A-l; Honolulu Advertiser, 10 April 1984, p. B-l; Newsweek, 30 April 1984, p. 25, Gregg Ripee, "Mushroom cloud sighted off Japan," Los Angeles Daily News, 11 April 1984, p. 1,8; Ross Gelbspan, "Mystery cloud baffles scientists," Boston Sunday Globe, 13 Jan. 1985, p. 1, 14; T.E. Bearden, Soviet Weather Engineering Over North America, 1-hr. videotape, 1985. See also McKenna, Daniel L. & Daniel Walker,"Mystery Cloud: Additional Observations", Science, 234(4775), Oct. 24, 1986, p. 412-413.

34. For a description of the April 11, 1963 anomalous underwater explosion north of Puerto Rico, see Robert J. Durant, "An Underwater Explosion — or What?", Pursuit, 5(2), April 1972, p. 30-31.

35. For details of the loss of the U.S.S. Thresher and the interference experienced by the U.S.S. Skylark, see John Bentley, The Thresher Disaster, Doubleday, Garden City, N. Y., 1975, particularly p. 164. Some of the communications systems of the Skylark experienced temporary failure, but were not disabled, later resuming operation.

36. The Soviet Union has a well-established history of interfering with and destroying aircraft; for example, for a listing see "Soviet and Warsaw Pact air incidents," Jane's Defence Weekly, 3(2), Jan. 12, 1985, p. 58.

37. For details of the anomalous "nuclear flashes" detected by U.S. Vela satellites, see "Scientists Fail to Solve Vela mystery," Science, 207, 1 Feb. 1980, p. 504-506. "Satellite Evidence Shows 'possibility' of Nuclear Test, DOD Says," Aerospace Daily, Oct. 29, 1979, p. 286. "A Flash of Light," Newsweek, Nov. 5, 1979, p. 64-65. "Was It a Nuclear Device?", Newsweek, July 21, 1980, p. 19. "Diverging Views," Washington Roundup, Aviation Week & Space Technology, July 21, 1980, p. 15. Philip J. Klass, "Clandestine Nuclear Test Doubted," Aviation Week & Space Technology, Aug. 11, 1980, p. 67, 69, 71-72. "Debate continues on the Bomb That Wasn't," Science, 209, 1 Aug. 1980, p. 572-573. "Navy Lab Concludes the Vela Saw a Bomb," Science, 209, 29 Aug. 1980, p. 996-997. See also Jack Anderson and Dale Van Atta, United Press Syndicate, "CIA knew South African-Israeli nuclear test was coming," Birmingham Post-Herald, Apr. 26, 1985, p. A5. The latter article repeats the CIA/DIA argument that the Vela incidents represent concurrent South African-Israeli testing of atomic weapons. Taiwan is considered a possible third partner. According to Anderson and Van Atta, a South African navy contingent was "in the area" at the time of the 1979 Vela detection, and Israel and South Africa were cooperating on an atomic bomb project as early as 1966. Apparently U.S. announcement of an impending South African atomic test in the Kalahari Desert in 1977 led to such an outcry that the test was suspended. Anderson and Van Atta cite succeeding visits to South Africa by Israeli scientists, technicians, and defense officials. However, since the actual Vela detections showed some deviations from what would be expected from nuclear tests, one can speculate that Anderson and Van Atta have presented evidence for the development of scalar electromagnetic weapons by two additional countries. One may further speculate that this could reveal what has been checking the Soviets from simply moving against the West with scalar electromagnetic weapons.

Indeed, the mysterious destruction of six major Soviet missile ammunition storage areas within the space of seven months could have been a preemptive measure and warning to the Soviets if they had actually been considering moving against the West. Also, other incidents reported in the South Atlantic may possibly be associated with the program producing the "Vela flashes." For example, see N.W.C. Rutherford, "Unidentified Phenomena," Marine Observer, 51, 1981, p. 186 for a description of a great bluish-white flash and small bolt of lightning, indicating some sort of anomalous electrical discharge, on Dec. 23, 1980 at 2245 hours (10:45 p.m.). Many other anomalous flashes for which no known causative mechanism exists have been detected by satellites. For example, the OSO-2 and OSO-5 satellites have detected about one mysterious short (less than 0.1 sec) flash about every ten orbits, at times when the fields of view of the telescopes were well above the earth. As many as three of the satellite's photometers have detected a flash simultaneously. These flashes must be removed from any discussion of satellite-observed lightning; see J. G. Sparrow and E. P. Ney, "Lightning Observations by Satellite," Nature, 232, 1971, p. 540.

38. For a description of sightings of enormous glowing globes of light deep within the Soviet Union in the direction of Saryshagan, see Gwynne Roberts, "Witness to a Super Weapon?", The Sunday Times, London, England, Aug. 17, 1980. Several incidents were observed by Downie and others.

39. For an artist's conception of a directed energy weapon installation at Saryshagan, see Aviation Week & Space Technology, July 28, 1980, p. 48. For a DOD sketch, see Soviet Military Power, 1985. Obviously classically-trained U.S. military analysts, with no knowledge of scalar interferometry, have not considered the installation as a candidate hyperspatial howitzer.

40. For a description of multiple pilot sighting (from Iran) of an enormous glowing globe of light deep within the Soviet Union, see Central Intelligence Agency (CIA) Information Report No. CO-B-321/15354-66, "Sighting of Unusual Phenomenon on Horizon Near Iranian/USSR Border," Sep. 8, 1966, released on 15 Dec. 1978 under the Freedom of Information Act (FOIA). The sighting occurred at 2142 hours (9:42 p.m.).

41. For details of sighting of the intensely glowing ball of light near British European Airways flight 831 between Moscow and London, see CIA Foreign Intelligence Information Report CO-B-324/33601-76, "Aerial observation of intense Source of Light," Nov. 18, 1976, released on 15 Dec. 1978 under the FOIA. The incident occurred between 1800 and 1900 hours (6:00-7:00 p.m.). The light was observed for 10-15 minutes, until the aircraft had flown past and left the light behind.

42. For other examples of pertinent 1ight phenomena: F. S. Angus and G. Carling, "Optical Phenomenon: Caribbean Sea; Western North Atlantic," Marine Observer, 40, Jan. 1970, p. 17-18; R. A. Holmes, "Unidentified Phenomenon, off Barbados, West Indies," Marine Observer, 40(229), July 1970, p. 107-108; H. K. Dyer, "Unidentified Phenomenon: Western North Atlantic," Marine Observer, 43, July 1973, p.114. For a 1961 double concentric hemispheric shape observed in the Indian Ocean, see Marine Observer, 32, 1962, p. 64. For a particularly significant combination of forms, see Marine Observer, "Unidentified Phenomenon," 48, 1978, p. 21-22. Also, on the night of July 26, 1984 the pilot and crew of a Boeing 747 (American carrier) flying from Tokyo to Fairbanks, near the Kuriel Islands, at 47 5'44" N: 161 00'05" E, noticed a slowly expanding hemisphere of white light off to their left above the horizon. The shell of light continued to expand over a 10-minute

period until ahead of them and to the right. The crew braced for a shock wave which never arrived. Their weather radar saw nothing out of the ordinary. The shell of light had sharp edges and was semi-transparent so that stars became visible through it. (Richard F. Haines, private communication, Sept. 27, 1984). See also Richard Hall, "Aerial anomalies at sea," The Info Journal, 4(3), May 1975, p. 6-9 for an unusual light phenomenon seen in the Caribbean by the R.M.S. Carmania (British). The phenomenon occurred four times at precise hourly intervals, strongly suggesting an artificial origin. See also F. Shepherd, "Cloud: Strait of Gibraltar," Marine Observer, 51(273), July 1981, p. 107-108 for an incident of associated cloud, arch, and anomalous pressure effects. For another significant airline sighting by Japan Airlines flights 403 and 421 of a giant, expanding globe of light on June 18, 1982, in the North Pacific, 100 km. east of Kushiro, see the Asahi Evening News, Tokyo, Japan, June 22, 1982. For additional evidence that nomadic tribesmen passing through Kazakhstan repeatedly observe such gigantic light phenomena in close association with Saryshagan missile test range, and that Soviet deception planners foster the notion of "UFO activity" as a Red Herring, see Robert Jackson, "KGB takes to the flying saucers!", Northern Echo, Darlington, England, March 15, 1984.

43. For details of Khrushchev's announcement of a Soviet superweapon, see Max Frankel, "Khrushchev Says Soviet Will Cut Forces a Third; Sees 'Fantastic Weapon'", New York Times, Jan. 15, 1960, p. 1.

44. See Christopher S. Wiren, "Brezhnev Calls for Accord against 'Terrifying Arms,'" New York Times, June 14, 1975, p. 1, 11. In a major Kremlin speech on June 13, 1975, Leonid I. Brezhnev included a statement that one major concern not covered by existing agreements was "assuming ever greater urgency with each passing day." Calling for a ban on new weapons of mass destruction, the Soviet leader stated: "The level of modern technology is such that a serious danger arises of creating weapons more terrifying than nuclear ones." He stated, "The reason and conscience of humanity dictate the necessity of erecting an insurmountable barrier to the development of such weapons." See also Malcolm W. Browne, "Senatorial Group Received by Brezhnev," New York Times, July 3, 1975, p. 2. Leonid Brezhnev repeated his proposal to a group of U.S. senators on July 2, stating that the capability to develop more terrible weapons was obvious. He emphasized, however, that he "had no particular weapon in mind." Here he may have been deliberately misleading the U.S. senators, to prevent revealing that the Soviet Union had already developed such weapons, and was horrified at their potential for total destruction. E.g., if massive and rapid scalar explosions occur, the linearity of spacetime -- and the orderly flow of time itself -- may be seriously perturbed throughout the earth and its adjacent space. From a general relativistic viewpoint, such an event might well prove catastrophic for the entire biosphere. Boris N. Ponomarev, a Soviet national party secretary, again raised the same issue to a delegation of visiting U.S. congressmen in the Kremlin on Aug. 11, 1975; see Christopher S. Wren, "Moscow Now Pressing Disarmament." New York Times, Aug. 12, 1975, p. 6. At the United Nation's thirtieth session of the General Assembly on Sept. 23, 1975, Foreign minister Andrei A. Gromyko strongly raised the same issue, warning that science can produce "ominous" new weapons of mass destruction. He urged that all countries, led first by the major powers, should sign an agreement to ban the development of these unspecified new weapons. He even offered a draft, entitled "Prohibition of the Development and Manufacture of New Types of Weapons of Mass Annihilation and of New Systems of Such Weapons." The first article provided that the types of these new weapons would be "specified through negotiations on the subject." Because of its fixation on nuclear weapons, the West may have lost its only opportunity to prevent the spread of scalar electromagnetic weapons of power unprecedented even by nuclear arms. Of course, it may also have

been a Soviet ploy to prohibit the U.S. from developing scalar electromagnetics defensive weaponry to counter the massive strategic scalar electromagnetics weapons already developed, tested, and deployed by the Soviet Union. Certainly in 1973 at a secret meeting in Prague with European communist leaders, Brezhnev had laid out a firm statement of Soviet domination of the world by 1985. See "Secret Speech: Did Brezhnev Come Clean?", National Review, 29(8), Mar. 4, 1977, p. 248, 250. Brezhnev's speech contained statements such as: "We are achieving with detente what our predecessors have been unable to achieve using the mailed fist...come 1985 we will be able to extend our will wherever we need to." Brezhnev stated the Soviet Union would control the oceans of the world, 90% of the land, and the air and space above. A front-page Boston Globe article on Feb. 11, 1975 was the first to carry the story. A copy of Brezhnev's secret speech was obtained by British intelligence in 1973, but denigrated by Secretary of State Kissinger. Apparently the first official U.S. reference to Brezhnev's startling speech did not appear until the 1976 National Intelligence Estimate. Although the big intelligence bureaucracies can do a fantastic job with "current intelligence," their record at predicting a drastic change is woeful, precisely because of the political nature of bureaucracies. See "What is Intelligence," Colonel William V. Kennedy et all, Intelligence Warfare: Penetrating the Secret World of Today's Advanced Technology Conflict, with an introduction by Dr. Ray S. Cline, Crescent Books, New York, 1983, p. 8-23. Intelligence Warfare is heartily recommended as the single book which best gives the reader a grasp of modern technical intelligence organizations, capabilities, and operations.

45. For details of Soviet weather engineering operations over the U.S., see Thomas E. Bearden, "USSR: New beam energy possible?", Defense & Foreign Affairs Daily, 13(111), June 12, 1984, p. 1-2. Cloud signature patterns reported in the article have been repeatedly sighted over multiple areas in the U.S. A series of anomalous "hole in the cloud" patterns, possibly associated with early Soviet weather engineering efforts over the U.S., was widely seen in 1967-68. See Weatherwise, 21(4), Aug. 1968, cover and p. 143; 21(5), Oct. 1968, p. 194-195, 204-205; 21(6), Dec. 1968, p. 238-245. Peculiar stationary blocking patterns have also been observed to occur and influence weather over the U.S., leading to severities such as the winter of 1976-77. See K. K. Tung and R. S. Lindzen, "A theory of stationary long waves, Part 1, A simple theory of blocking; Part 2: Resonant Rossby waves in the presence of realistic vertical shears; Part 3, Quasi-normal modes in a singular waveguide," Monthly Weather Review, 107(6), June 1979, p. 714-774. See also T. E. Bearden, Soviet Weather Engineering Over North America, videotape, 1985 for an expose or the physics and some major incidents of major Soviet weather engineering, including details and photographs of cloud signature patterns. See also C. B. Baker, "Soviet Weather Mayhem," Youth Action News, Nov. 1983, P.O.B. 312, Alexandria, Virginia 22313, p. 1-8; C. B. Baker, "Diabolic Soviet Warfare," Youth Action News, Nov. 1984; For a conventional Soviet look at weather modification (possibly intended to mislead the West), see E. T. Protasevich, "Microwave weather modification," Soviet Technical Physics Letters, 7(3), March 1981, p. 114-115. For a downburst mechanism, see Gary Ellrod, "Dramatic examples of thunderstorm top warming related to downbursts," National Weather Digest, 10(2) May 1985, p. 7-13. See Art and Kay Westermann, Weather War — Worldwide, Liberty Bell Books, POB 288, Sedona, Arizona 86336, 1983. See also U.S. Senate Resolution on Environmental warfare, July 11, 1973.

46. For details of the Soviet Woodpecker beams bending around the earth and intersecting over the U. S., see Christopher Chant and Ian Hogg, Nuclear War in the 1980's?, Harper & Row, New York, 1983, p. 71. See also Soviet Military Power, U.S. Department of Defense, 1985, p. 45. The

intersection forms an interference grid. Scalar EM channels added to the Woodpecker carriers then provide a corresponding sca1ar EM interference grid in the scalar area.

When adjusting the scalar interferometry components of the grid, bursts in the interference and discharges of energy as well as bursts of energy extractions occur. This leads to the production of anomalous aerial phenomena such as explosions, rumblings, airquakes, etc. In addition, direct Bohm-Aharonov forces may be engendered in ground structures, shaking buildings and windows, etc. without seismic disturbances. Such anomalous disturbances have been widely noted in the open U.S. press. E.g., particularly see Kenneth F. Bunting and Daniel M. Weintraub, "Mysterious Rumbles Jar Southland," Los Angeles Times, Dec. 8, 1984, CC(II), p. 1,10; Let Scarr, "People shook up over mystery shakes," The San Diego Union, Dec. 8, 1984, p. Bl, 4. Following this and a Dec. series of anomalous aerial disturbances off the Los Angeles/San Diego coast, a sharp and unexpected weather front appeared, racking the area with high winds on the night of Dec. 12, producing widespread damage and power outages. The newly-formed front moved on to produce significant snowstorms in other areas. See Ted Thackery, Jr., "Winds Kill Two, Wreak Havoc as They Sweep Through the Southland," Los Angeles Times, Dec. 14, 1984, MF/Part II, p. 1,8; "Even Tucson gets snow in storm that dumps 20 inches," AP release, Los Angeles Herald Examiner, Dec. 14, 1984, p. A-12. During several months prior to the December 1984 Los Angeles incident, anomalous electrical failures and outages had occurred in the San Diego and Southern California area, possibly due to scalar interferometry adjustments in the Woodpecker grid over the area. For other typical incidents possibly associated with adjustment of the interference grid, see "Who boomed? Odd Noise unnerves Ohioans," Journal, Milwaukee, Wisconsin, Dec. 28, 1982; "Tremors shake Miss. Gulf Coast," Times-Picayune, New Orleans, Louisiana, Feb. 27, 1983; Sandra Skowron, "Sonic boom is just Mother Nature," Beaver Co. Times, Beaver Falls, Penn., Jan 13, 1983; "Booms in Rockland, New York Times, Mar. 1. 1979, Sec. 8, p. 82; "Loud 'boom' unexplained," Star-Beacon, Ashtabula, Ohio, Feb. 21, 1983; Paul Senecton, "The word is now IDENTIFIED," Mail, Hartlepool, England, Feb. 3, 1985: On Jan. 23, 1974 a mysterious explosion over North Wales rocked a 60-mile radius area. Associated anomalous light phenomena were also seen. Hundreds and hundreds of anomalous booms, aerial rumbles, and aerial explosions, many accompanied by flashes or anomalous shaking of ground structures, buildings, windows, etc., have occurred over the U.S. and other Western nations in the 60's, 70's, and 80's.

On occasion, an aircraft at the proper altitude and position can conceivably experience interference in its electrical systems and in its engine combustion processes due to exothermic kindling or endothermic extraction of electromagnetic energy. The combustion processes of aircraft engines produce highly ionized gases in very nonlinear conditions. These can act as strong dephasers and decouplers of the vector EM components of a vector zero summation in a scalar interference zone. Exothermic interference would have little effect on combustion, but strong endothermic interference can result in engine flameout. Anomalous simultaneous failure of jet and propeller-driven aircraft engines sometimes occurs. For high altitude grids, this can result in engine flameouts, but restart and recovery after unusual loss of altitude has dropped the aircraft out of the scalar interference zone. Several candidate incidents over and near the U.S. exist, particularly where power failures were experienced by multiple aircraft. The more usual exothermic case, however, if substantial could result in anomalous loss of control of the aircraft. For a recent candidate incident, see "Jetliner drops 32,000 feet; 400 aboard; 50 are injured," Associated Press release, Huntsville Times, Feb. 20, 1985, p. 1 and "China Airlines Pilot Denies Cockpit Error," Associated Press release, Huntsville Times, Feb. 21, 1985, p. A-9. Deliberate use of this effect as an anti-strategic-bomber weapon capable of destroying bombers at or shortly after takeoff is possible (the Arrow DC-8 which crashed just after takeoff from Gander Air Force Base, Newfoundland on December 12, 1985 may have been deliberately interfered with by just such a Soviet weapon -- see extensive newspaper and TV news coverage of that event).

In scalar EM interference with aircraft, certain signatures may occur. Different instruments may sharply contradict each other, since their activation and inactivation is no longer a simple function. The pilot's instrument panel, for example, may indicate failure of the control system, when actually it has not failed, and the flight recorder may record that the control system is still operating. In such case, the pilot may take proper action based on his own instrumental readings, yet these actions may be contraindicated for the actual status of the aircraft, resulting in opposing pilot/autopilot actions. Tentative indications of the jetliner that anomalously dropped 32,000 feet and recovered are that apparently such anomalous instrument disagreements occurred. Another signature is that, as the EM charge accumulates in and on the aircraft, its skin charges up electrically, producing a glowing corona similar to St. Elmo's fire. The Arrow DC-8 was observed to be glowing yellow by eyewitnesses, according to the Canadian Broadcast Corporation's 10:00 p.m. network TV news on April 8, 1986.

47. T. E. Bearden, Star Wars Now! The Bohm-Aharonov Effect, Scalar Interferometry, and Soviet Weaponization, Tesla Book Co., Millbrae, California, 1984, p. 19-22.

48. For a paper possibly related to the first Bedini scalar wave detector from the "free A-field is a scalar field" view, see Robert R. Lewis, "Aharonov-Bohm effect for trapped ions," Physical Review A, 28(3), Sept. 1983, p. 1228-1235. This paper analyzes the role of the Aharonov-Bohm effect for the bound states of a charged particle in the superposition of two fields: a uniform magnetic field plus the vector potential of a solenoid. Gives exact solutions for a solenoid of zero size and discusses the corrections due to a solenoid of finite size. Shows that a series of new "betatron resonances" appear in the spectrum, dependent on the flux quantum number. The fundamental betatron resonance remains narrow and unshifted for solenoid radii large enough to broaden and shift the cyclotron resonance. See also W. Ehrenburg and R. E. Siday, Proc. Phys. Soc. London, Sect. B62, 1949, p. 8 which, among other things, discusses the effect of the vector potential in electron interferometry, where the insertion of a tiny solenoid between the interfering paths is shown to give an additional phase difference proportional to the flux through the solenoid. The resulting shift in the fringe system is called the Aharonov-Bohm effect.

49. Frank Golden has developed a most important and precise scalar EM detection system to display scalar EM signals on a cathode ray tube. His important measurements have mapped the scalar resonant frequency responses of the entire earth. Two completely different types of scalar instrumentation show precise agreement on the frequency maps. The measurements show that the Soviet Union has for some time entrained the entire earth into giant scalar electromagnetic resonances on two frequencies approximately 12 kilohertz apart. It is the opinion of the author that the beat frequency between these two giant resonances is utilized by the Soviet Union to extract enormous power from the earth, essentially by a mechanism that Golden has uncovered. A complex of four to eight weapon systems might reasonably be powered from the single bi-resonant tapping source. In April 1985 Golden discovered the rather sudden activation of many other scalar frequencies with characteristics resembling command and control communications. In addition, a significant number of additional paired scalar resonances had been entrained upon the earth. It is the

opinion of the author that this showed a major activation of the Soviet strategic scalar electromagnetic defense system, with the power up of from 80 to 100 weapons, along with the complete command and control system. Golden has previously built a prototype of an actual Soviet scalar communications system and demonstrated that it works. Because of the impending mayday and the 1973 statement by Brezhnev indicating that 1985 was a critical planning year, the sudden activation of such massive numbers of weapons and communications was alarming. Accordingly, the author discreetly notified certain contacts to alert the U.S. system. Golden then detected the periodic turn-on and turn-off of the systems, indicating a large command and control exercise rather than preparations for direct tactical use. An additional difference, however, was the change from scalar electric to scalar magnetic field on many of the large transmitters. This is indicative of electrostatic location, targeting, and adjustment of the target on the earth and then switching to the "power input" mode. It is the opinion of the author that this indicated the choice of a geological target and proceeding to attack that geological target in the "slow buildup" mode. Again, proper contacts were so notified.

50. A very good coverage of the Soviet microwave radiation of the U.S. Embassy in Moscow is given in Paul Brodeur, The Zapping of America, W. W. Norton & Co., New York, 1977, passim. None of our U.S. Embassy security personnel knew of scalar interferometry, nor did they possess scalar electromagnetics detectors. Further, orthodox U.S. scientists were also ignorant of scalar electromagnetics. The Soviets were thus in a position to tailor the radiation signals and precisely determine what our on-site personnel would detect. Details of the effects on U.S. Embassy personnel, possibly associated with the microwave radiation, are given by Brodeur. A great number of related releases by the open news media also exist. For example, see Robert C. Toth, "Radiation Devices Bug U.S. Embassy," Huntsville Times, reprinted from the Los Angeles Times, Feb. 8, 1976; "U.S. Screening out Soviet 'Listening Rays'," United Press International release, Washington D.C. Star, Feb. 11, 1976; Norman R. Beebe, "Nixon Exposed to Radiation In Russia?", Associated Press release, Huntsville Times, Apr. 30, 1976; Barton Reppert, "U.S. Scientists Puzzled Over Embassy Radiation Effect," Associated Press release, Huntsville Times, May 28, 1976; Barton Reppert, "Radiation Entering Embassy in Moscow through Phone Line," Associated Press Release, Huntsville Times, May 28,1976. See also Martin Ebon, Psychic Warfare: Threat or Illusion, McGraw Hill Book Co., New York, 1983.

51. For details of the electromagnetic transmission of cellular disease and death, see Vlail P. Kaznacheyev, "Information function of ultraweak light flows in biological systems," Problems in Biophysics, Novosibirsk, 1967, p. 7-18. Kaznacheyev et al, "Conditions necessary for appearance of distant intercellular interactions after UV-radiation," Bulletin Experimentalnoy Biologii i Meditsiny, (5), 1979, p. 468-471; Distant intercellular interactions in a system of two cultures connected by optical contact," Ultraweak Luminescence Biology, Moscow, 1972, p. 224-227; "Distant intercellular interactions caused by UV-radiation," Photobiology of a Living Cell, Leningrad, 1979, p. 221-223; "Studies on the biological role of electromagnetic emission as a factor of adaptive behavior of cells under conditions of latitude changes," Abstracts of the second all-union conference devoted to the problem of human adaptation to different geographical, climatic, and labor conditions, Novosibirsk, 1977, p. 101-104; Vlail P. Kaznacheyev, S. P. Shurin and L. P. Mikjhailova, "Distant intercellular interactions in a system of two tissue cultures," Official Bulletin of the committee on inventions and discoveries affiliated to the council of ministers of the USSR, Discovery no. 122 (19), 1973, p. 3, also printed in Psychoenergetic Systems, 1(3), Mar. 1976, p. 141-142; "Apparent Information Transfer

Between Two Groups of Cells," Psychoenergetic Systems, 1(1), Dec. 1974, p. 37.

52. For evidence of anomalous scalar reflection out of the scalar grid caused by a Navy chaff drop, See "Navy sabotages traffic lights, TV sets," United Press International, PM cycle, Jan. 11, 1985; "Power blackout blamed on anti-radar particles," United Press International, AM cycle, Jan. 11, 1985; "Power Disrupted Briefly After Navy Plane Drops Metallic Strands," Associated Press, AM cycle, Jan. 16, 1985.

53. A good summary of the early incidence of the Soviet Woodpecker signals is given by Bradley Wells, "The Russian woodpecker: a continuing nuisance," CQ, Nov. 1984.

54. A particularly important Soviet Paper is E. B. Smetanin, "Electromagnetic field in a space with curvature -- new solutions," Soviet Physics Journal, 25(2), Feb. 1982, p. 107-111. In this paper, a solution to the stated problem is obtained, which may be regarded as a classical model of a charged particle that has both a magnetic moment and a nonzero magnetic charge density. Interaction with spacetime curvature can disrupt the gauge invariance of the EM field, and it can also reestablish invariance in an initially noninvariant theory. (Hutchinson has had anomalous breaks of metal caused by standing scalar waves, which seems to be due to a mechanism that produces monopoles and deposits them in the metal at standing-wave nodes. This paper should be directly applicable.)

See also Yu. S. Vladimirov and A. A. Kozlenkov, "6-optics and a general theory of gravitation and electromagnetism," Soviet Physics Journal, 27(12), Dec.1984, p. 1039-1041; V. G. Bagrov and M. D. Noskov, "New exact solution of the Dirac equation. XI," Soviet Physics Journal, 27(12), Dec. 1984, p. 1030-1034. See particularly V. I. Petukhov and I. A. Kuzin, "Weak processes in the field of a gravitational wave," Soviet Physics Journal, 27(12}, Dec. 1984, p. 1025-1029.

In the latter paper it is significant that the decay probability increases in a locally curved spacetime, and that solutions are obtained for circularly polarized waves.

(In EM waves, circularly polarized waves have special characteristics in nonlinear isotropic media: exact solutions exist. Also, when two longitudinal sine waves of differing frequencies are transmitted into a nonlinear isotropic medium, the apparent difference frequency is transmitted as a sine wave, undistorted. This characteristic has been used by Westinghouse to produce improved sonar transmission through seawater, for example. The scalar EM (electrogravitational) wave may be represented as a longitudinal EM wave. Immediately, if one wishes to produce a pure scalar EG wave in the nucleus of an atom, two frequencies should be transmitted such that their difference is the frequency wished. Or circularly polarized waves may be utilized.)

Note that, by implication, one should be able to deliberately tailor scalar EM waves to greatly speed the decay of long-lived radioisotopes, such as are contained in radioactive wastes from nuclear reactors and other processes.

55. For some evidence of continuing persistence of the higher frequency scalar components applied to the scalar grid on Jan. 28, 1986 to localize the effects when attacking the Challenger, see "Poison suspected in unexplained deaths of birds," Huntsville Times, AP release, Feb. 6, 1986. From 1-4 Feb.

1986, various kinds of dead birds -- such as blackbirds, cardinals, sparrows and bluebirds -- plummeted to the ground in Birmingham, Alabama. At first some sort of mysterious poison was suspected, but later was ruled out. During this period, the woodpecker grid was particularly active in weather engineering operations. Multiple sightings of giant cloud radials occurred in various places throughout the U.S. The retention of the high frequency components possibly was intensified in the Birmingham area sporadically during the period. Birds flying into this zone would be killed if their brains acted as scalar receivers and were sufficiently jammed by the signals. Normally Huntsville (further north) is a "hinge point" for increased scalar activity, to start the Jetstream bending northeast to move along the Appalachian mountain chain. However, just before 28 January the jetstream had been diverted further south than usual by the Soviet interference, bringing unseasonably cold weather to Florida and the waiting Challenger on its launch pad. Probably hinge points further south than Huntsville were needed for this operation. If these more southern points were retained for a few days, and the high frequency components were retained, then an inadvertent high intensity area of these components may have sporadically occurred in the Birmingham area, killing the birds.

For description of the Apr. 18, 1986 Titan blast and its ramifications to the spy satellite program, see James Gerstenzang and Ralph Vartabedian," Los Angeles Times News Service, "Titan Blast to Hurt Spy Program," Huntsville Times, Apr. 19, 1986.

56. For another very important paper indeed, see Vu. G. Ignat'ev, "Relativistic kinetics of an anisotropic plasmalike medium with damping in a field of gravitational radiation," Soviet Physics Journal, 27(12), Dec. 1984, (English translation: Plenum, June 1985), p. l066-1069. If we substitute the vacuum "virtual plasma" for the observable plasma, this paper may be part of the smoking gun to show that the Soviet Union has developed scalar electromagnetics. Extrapolating from this paper, the amplitude of the "induced longitudinal field" is proportional to the square of the amplitude of the gravitational wave (GW) in an initially isotopic medium, but reduces to a linear proportionality as the medium develops nonlinearities (anisotropies or inhomogeneities). Whereas conventional GW are considered to be weak, the scalar GW may be very strong since we ourselves determine the variation in the energy density of vacuum it involves. Further, sharply spiked scalar EM (EG) pulses may develop appreciably more amplitude that the linearly calculated amplitude from the magnitudes of the zero-summation components. The end result is that (1) we can produce powerful gravity waves using the scalar EM approach, (2) local spacetime can be curved, producing violation of the conservation laws, and (3) the assumption of a local Lorentz frame made by Einstein as a limitation on ordinary general relativity is falsified.

In passing, note that immediately one also has a clear basis for the excess local production of energy when the battery furnishing power to a DC series motor is sharply spiked backwards in a "recharging" fashion. Further, the ions in the battery (which are several hundred thousand times as massive as an electron) possess a resonance on the order of 16 megahertz in a typical lead-acid battery. Under the correct conditions, the ions collect the excess energy (due to the initial square effect) produced by a sharp pulse of recharging potential. The ions are shocked into resonance and, on reversal, "overshoot" and deliver this excess energy to the plates, recharging the battery. Thus such a system can violate linear conservation of energy because spacetime is locally curved by the spiking, and excess energy from the excited local vacuum is collected by the ions and delivered to the plates. This is precisely the effect upon which the first Bedini free-energy motor depended. The timing and adjustment, however, are highly critical and difficult, and the battery takes a rather severe beating.

57. For details and photographs of highly anomalous exhausts seen on Bennett Island, see "Explosive Events Seen on Soviet Island," Aviation Week & Space Technology, Sept. 26, 1983, p. 31. NOAA-6 and NOAA-7 weather satellite photographs of massive smoke plumes, one of them 150 miles long and nearly horizontal, are shown. Also, in U.S. weather satellite photos of Novaya Zemlya, similar plumes have been detected, making this location a tentative candidate for a second Soviet "exhaust site." See also Letter John M. Miller, Geophysical Institute, University of Alaska, Jan. 4, 1985 with attachment, "Bennett Island plume cases recently found." Satellite photos showing actual circular breaking of arctic ice have also been taken near Wrangel Island. See Sam Bishop, "UA photos show Soviets break ice for missiles," Fairbanks Daily News-Miner, Dec. 15, 1984, p. 1,3; Craig Covault, "Soviet Abi1ity to Fire through Ice Creates New SLBM Basing Mode," Aviation Week & Space Technology, Dec. 10, 1984, p. 16-17. Wrangel Island in fact has a bizarre history: it belongs to the U. S., but has been illegally given to the Soviets and occupied and used by them. For details, see "Wrangle over Wrangel and the Weather War," Don Bell Reports, 32(9), Mar. 8, 1985.

58. For details of anomalous blinding (probably by scalar EM means) of U.S. satellites, see Philip J. Klass, "Anti-Satellite Laser Use Suspected," Aviation Week & Space Technology, Dec. 8, 1975, p. 12-13. For details of anomalous failures and recoveries of a British satellite, see Joe Schwartz, Nature, 280, July 12, 1979, p. 95.

59. For other possible evidence of traces of Soviet scalar EM activity over the oceans, see George D. Curtis, "An electromagnetic radiation pattern over the ocean," Undersea Technology, 5(8), Aug. 1964, p. 29-30, 40. In producing a scalar wave, there exists a sort of "signal to noise" ratio of the desired scalar wave to an accompanying, undesired normal EM component. Due to practical equipment imperfections, the generated scalar wave inevitably is accompanied by a small residue of ordinary EM wave. While measures can be taken to further purify the scalar wave, a residue always remains. Curtis may have detected the weak EM residue accompanying early Soviet interference gridding for weather control testing over the U.S.

60. Interactions which occurred between Khrushchev and renowned physicist and Nobelian P. Kapitsa are of interest. Khrushchev desired absolute defense of the Soviet Union so that the Soviets might be able to launch any action desired without risk or serious concern. Kapitsa informed the Soviet leader that, if a means of total neutralization of foreign missiles was to be found, it could only come from a group of new principles in physics which was called " energetics." The term "energetics," of course, was contracted from "psychoenergetics," and is essentially the expanded physics/electromagnetics that this author has dubbed scalar electromagnetics.

Strangely, a portion of a book by Marshal Grechko was deleted from its English translation at the specific request of the Soviet Union to the U.S. State Department. The passage stated: "Of particular importance is basic research aimed at discovering still unknown attributes of matter, phenomena, and the laws of nature, and developing new methods for their study and use to reinforce the state's defense capabilities."

The most definitive Soviet book on military strategy is titled Military Strategy (Voyennaya

Strategiya). See V. D. Sokolovskiy, Soviet Military Strategy, third edition, edited with an analysis and commentary by Harriet Fast Scott, Crane, Russak & Company, Inc., New York, 1975. There are three editions, the latest in 1968. In the third edition, the exotic weapons normally proposed for defense against strategic ballistic missiles -- such as particle beams, high energy lasers, exotic nuclear warheads, plasma weapons, antigravitational weapons, etc. -- are discussed and discounted by implication. The statement is made several times that 100% defense against missiles and aircraft is possible. A statement is also made that it is interesting to note that this capability (a solution to the strategic missile defense problem) has been achieved by the Soviet Union, but not by the West (e.g., p. 298.) In the same edition, a previous definition of antimissile defense obviously consisting of radars, computers, and interceptor missiles is deleted (see author's note 190, p. 454).

The Soviets also recognize the great importance of technical surprise: "The experience of war shows that warring sides quite often have tried to employ new types of weapons to this end to achieve surprise, which are a surprise for the enemy or are little known to him. Each side secretly develops new means of warfare in order to employ them unexpectedly. History knows many examples how the employment of a new weapon initially gave considerable success because the enemy, caught unaware and not knowing the combat capabilities of this weapon, was for some time incapable of effective counteraction… The mass introduction of new weapons into an army usually cannot remain secret for long for the other side. -- New means of warfare, and in mass numbers, are impossible to create often and quickly. In this regard, the sides have begun to take other paths concerning the attainment of surprise along with searches for new weapons and their sophistication." V. Ye. Savkin, of The Basic Principles Operational Art and Tactics, Moscow, 1972, U.S. Air Force translation, U.S. Government Printing Office, Washington, D.C. 20402.

61. The Soviets have not discarded most of their old radars, and have continued to develop, build, and deploy giant new radars (in apparent violation of SALT agreements), which U.S. analysts always analyze in conventional fashion. It is fairly straightforward, simple, and inexpensive to modify an ordinary pencil beam radar to produce scalar wave beams and geometrical scalar Fourier expansion forms. Radars can provide a wide array of totally new and unexpected capabilities when utilized in the scalar electromagnetics mode. Even older Soviet radars, with antiaircraft gun sites and older surface-to-air missile sites, will exhibit new and startlingly advanced capabilities against ballistic and cruise missiles and Strategic Air Command bombers. Since there are many thousands of these older Soviet radars still operationally deployed, in the scalar mode the Soviet strategic defense may well approach 100%, just as Military Strategy implies. Also, the antiaircraft and antimissile defense capability of Soviet land forces may be far greater than anything presently estimated by U.S. analysts.

62. To the physicists, engineers, and researchers who have made the tough sledding to this point, congratulations! Here's a bonus for you.

Turn to page 32, equation [7]. Time differentiate it (this is left as an exercise for the reader). Collect terms and study the result intensely.

Now you have the reason why rise time is so important from a scalar EM viewpoint. You can also see why spiking the innate inductance of any system very sharply is so important. Fast rise time greatly increases the value of the time derivative terms, and your gravito-inertial effects go up with the collective squares of your zero-vector summed components. Any system has at least a little inductance. For sharp spikes, the gravitational potential goes very high. The inductance of the system momentarily opposes any current (translation: opposes any current bleed-off, or EM force field bleed-off). During that time you've got the 4-space G-potential to use. If you need to hold it longer to use it, then increase the inductance.

Now you can see why extremely rapid discharge of properly tuned, giant Tesla coils give gravitational and inertial effects sometimes.

You can see why the sharp "EMP" (electromagnetic pulse) from a nuclear explosion or EMP generating device can penetrate the ocean.

That's why the spikes (such as used by the neurophone) can carry messages directly into the brain and nervous system. You also should see why the Soviet woodpecker carriers (a Soviet over-the-horizon radar system) are loaded with scalar EM spikes (Bedini has precisely detected them from 50 Hz to 10 MHz; Golden has detected them into the gigahertz range.) to work on the humans in the targeted area. They're zapping the hell out of us. And they have done something similar at the U.S. Embassy in Moscow for decades.

Bedini has developed a simple, cheap device to mess up the phaselocking of the scalar EM spikes on the woodpecker carriers. It's based on the fact that the Russkies use a lot of circularly polarized transmitters when they make the spikes. Here's what to do: Take 4 strong bar magnets and an old (but operational) long-playing record turntable. Set it on 33-1/3 RPM speed. Glue the magnets on the top of the turntable, standing vertically, symmetrically placed around the turntable's outer edge. Place them so that on one a north pole is up, on the next a south pole is up, then a north up, then a south up. Now turn the turntable on and let it run. This gadget makes a slowly rotating magnetostatic wave. (Yes, it will also make a rotating "magnetic" wave, which is actually two rotating magnetostatic waves.). These rotating magnetostatic waves will interfere with the scalar spikes, changing them to EM (electromagnetism) and slowly rotating their phase. This breaks the phaselock of the Soviet circularly polarized scalar EM signal on the human brain. This gadget will protect the average large room.

But back to our differentiated equation.

Now you should also see why the first Bedini motor is so "devilishly difficult" to adjust. You've got to get the effect and examine it in well under 20 nanoseconds. You'll need an oscilloscope of 350 MHz range or so. Microwave-quality bench equipment is necessary; the ordinary electrical and electronic shop equipment is not good enough. You can also see why the ordinary lead-acid battery takes such a beating. However, a special battery certainly can be designed to take it. Now you know.

Okay, you tigers. Go get 'em.

63. Now here's a final bonus for the persistent reader.

This time, see J. N. Brittingham, "Focus Wave Modes in Homogeneous Maxwell's Equations:

Transverse Electric Mode," J. Appl. Phys. 54, 1983, p. 1179-1189; T. T. Wu and R. W. P. King, "Comment on 'Focus Wave Modes in Homogeneous Maxwell's Equations: Transverse Electric Mode' [J. Appl. Phys. 54, 1179 (1983)]", J. Appl. Phys. 56, 1984, p. 2587; T. T. Wu and H. Lehmann, "Spreading of Electromagnetic Pulses," J. Appl. Phys. 58, 1985, p. 2064-2065; T. T. Wu, "Electromagnetic Missiles," J. Appl. Phys. 57, 1985, p. 2370-2373. Pay particular attention to the latter paper.

Because of the Strategic Defense Initiative (SDI) and other programs, great interest has recently been kindled in using EM pulses to carry energy from a high-powered source to a target. However, so far almost all the work is still couched in terms of purely ordinary (though sophisticated) electromagnetics. It still involves the EM concept of "EM energy flow through the intervening space from the transmitter to the target." As such, the work to date still suffers from all the self-imposed ills and limitations of using the classical force fields concept of EM.

However, the theoretical work of these referenced papers is of great interest to us here.

In the first paper, Brittingham sparked a great deal of interest with theoretical work which promised a permanently focused 3-dimensional concentration of EM energy that propagates in a straight line with the speed of light. That is, this mode used a newly formulated wave packet (called the "focus wave mode") that acted as a non-dissipating EM soliton.

In the second reference, it was concluded that Brittingham's focused wave packet actually satisfied Maxwell's equations, but not the associated boundary conditions.

[Comment by this reviewer: both of these formulations use "linear time" and a "linear frame," ignoring the local general relativity aspects. Indeed, Brittingham's "focused wave packet" can be made by the zero-vector approach! However, it will not be an "EM" packet, it will be a pulse (or oscillating wave, depending upon how it is made) of 5-gravity potential. As such, it contains a multiplicity of locked-in, 5th-dimensional, non-zero EM gradients in and EM gradients out. Collectively these gradients themselves constitute a deterministic "flux of gradients" or an EM flux in the 5th dimension, with no resultant effective current of EM gradients. In other words, it's possible to build a "flux of gradients" and to have a "current of gradients," just as in ordinary EM it's possible to have a "flux of virtual particles" and a "current of virtual particles." The argument concerning the EM boundary conditions of Maxwell's equations is not relevant in such a case. The only boundary involved is the zero itself.]

Be that as it may, the 4th reference is of direct interest. In this paper, Wu has done us a great service. He shows that, under transient excitation, an antenna of finite size can transmit energy to a faraway receiver so that the energy decreases as slowly as one wishes. An electromagnetic pulse of energy with such slow decay is conveniently referred to as an "electromagnetic missile."

The electromagnetic missile has important applications, according to Wu. One possible application is the transmission of information in a manner that is very difficult to intercept or jam. A second possible application is to destroy or disable a distant target. However, Wu feels that so much energy is required [remember, he is speaking of EM non-zeroed force fields traveling through ordinary space] that a like1y radiating source must be something like a nuclear explosion. However, as Wu points out, a nuclear explosion produces a powerful EM pulse which includes frequencies from microwaves to gamma rays. To weaponize the explosion to produce a coherent beam, the nuclear explosion must be controlled to produce a coherent radiating source and a pulsed laser-like EM beam. Wu points out that such a technology is difficult and has not been developed.

We comment as follows: It is certainly true that enormous energy is required if the waves in the pulse remain electromagnetic -- that is, if they have non-zero resultant E and B fields to the external observer.

On the other hand, if we form a complex of waves in opposition so that we control the energy content of each individual component wave, but blend all the waves so that their collective envelope wave has zero E-field and zero B-field resultants, then -- to the external observer -- the EM energy is infolded and unzipped electromagnetically. It is now electrogravitational energy, and limitations of "EM force field energy flowing through space or through a physical medium" need no longer apply. However, we may still look at each EM component wave as an individual EM wave, moving in the Kaluza-Klein 5th dimension that is wrapped-around each and every point in our ordinary 4-space. In other words, to the ordinary 4-spacetime observer, each component wave has a special channel around every point of his space, not through it. Thus we have established multiple EM channels "just outside" each point of observer space. These we call "scalar channels," and EM energy can move through each one as if it were moving through a wire. The relative potentials between the "ends of each wire" determine in which direction the "EM energy current" flows along the wire.

And in each of these "special channels," we just have a normal kind of space (to the internal observer). Wu's paper assures us that we can get as much of the input energy to the distant target as we desire. The problem then is how to break the zero-summed EM envelope (and hence the "zero channel" for each component EM energy wave) in the distant target itself, spilling the infolded contents of all the special channels back into ordinary spacetime as EM energy (either positive or negative).

That, of course is easily done by interference in the distant zone. As previously stated, there is a way in which we can even perform this interference in a single scalar beam. Since the newly formed EM energy emerges from each and every increment of spacetime occupied by the distant target, it already emerges inside the very vitals of the target. It does not have to translate through the intervening ordinary space between transmitter and target. Instead, it goes through the Kaluza-Klein fifth dimension. It translates along a line through our space, but not through our space. With the scalar EM approach, we transmit EM energy through hyperspace, not through normal space.

Hereafter we will adapt and expand Wu's SDI term "electromagnetic missile" to include these electrogravitational aspects. In other words, we include the "scalar EM missile", which consists of an infolded multiple of Wu's ordinary EM missiles moving together coherently in special sheathed hyperspace channels.

In Appendix I we show an anomalous photograph taken by Bob Gladwin, just before the shuttle launch of Nov. 26,1985. While the photograph may be an artifact, it also is a candidate for the test strike of such a Soviet scalar "electromagnetic missile" tested against an aiming point offset from the shuttle launch which followed a few seconds later. The test was accomplished before the shuttle was launched, and offset from it, so that it positively would not endanger the shuttle itself. The conditions under which this spectacular photograph was taken happened to coincide with the special conditions required to photograph such scalar EM energy. Those conditions are clarified and explained in the Appendix.

My deep appreciation goes to Mr. Gladwin for allowing me to use this photograph. As we will point out in Appendix I, the video camera caught a picture of the Soviet scalar EM marker beacon associated with the Titan explosion of April 18, 1986. One can rest assured that the Soviets probably destroyed that vehicle, using a scalar EM missile.

APPENDIX 1: SOME IMPORTANT INDICATORS AND DESTRUCTIVE TESTING

Some of the indicators which bear on the use of the Soviet
scalar electromagnetic grid via the Woodpecker EM carrier beams are given in this appendix. along with other information believed pertinent to overall scalar EM effects.

IN ADDITION, THE THESIS OF ACTUAL LIVE TESTING OF THESE WEAPONS BY THE SOVIETS -- TO INCLUDE THE DESTRUCTION OF A TROOP-CARRYING U.S. AIRCRAFT, A SHUTTLE, AND A TITAN MISSILE -- IS ADVANCED AND INDICATORS PRESENTED.

An anomalous photograph taken by Bob Gladwin is presented which possibly may have captured the "smoking gun" -- the strike of a
Soviet scalar EM missile at an offset aim point near the shuttle Atlantis, just before its launch on Nov. 26, 1985. However, this photograph is caveated since it may also represent an anomalous but ordinary artifact. captured in some as yet unknown manner. The manner in which such a photograph may have been taken -- when normally the scalar energy does not show on a photo -- is explained.

Another photograph taken by George Suchary after the launch did
capture the Soviet "marker beacon" utilized in the test firing, however. This independent photograph is presented, and adds credence to the thesis that the Gladwin photograph captured the test of a Soviet scalar EM pulse missile.

- INDICATORS AND SUCH -

1. Continual cloud radials have repeatedly been seen and photographed over Los Angeles, California or its vicinity.

Los Angeles is also apparently a "hinge point" for bending and controlling the jetstream. Three typical radials seen to form one after the other by Margaret Wilson (and sketched and airbrushed by her) in the greater Los Angeles area are shown in figures 1, 2, 3, and 4. These radials were formed on Sunday, Jan. 26, 1986. Ms. Wilson had heard my Saturday night "Soviet Weather Engineering" broadcast over KABC Los Angeles, and my request that anyone who saw the typical radial cloud formation should photograph or draw it, noting time and location, and send the photos or drawings to me.

As Margaret described it. "To my astonishment, the next day I not only saw one, but three in the sky at the same time.

The time of the first one was Sunday, Jan. 26, at 1:15 p. m.

. . . I stepped out the back door for some minor errand and noticed a fan of long straight clouds in the sky. The sky had been filled with dark clouds most of the morning but this had been breaking up and the western half of the sky was now clear with these lines of clouds spread out on it. I immediately thought of your request and tried to see the bottom of the fan which was hidden behind bushes and a garage. When I stepped into the street, I saw there was a semi-circle beneath them.

Not having film and a wide-angle lens on my camera. I knew I couldn't capture it in its entirety. I am, however, a retired commercial airbrush artist so I quickly sketched the formation. It is illustration #1.

It was in the western sky, the base of the central semi-circle sitting about 15 degrees above the ocean horizon. It was very clear and sharply defined. The semi-circle was broken at the top and the two broken ends curled inward like commas. As I sketched the wind deformed it somewhat, the right half of the whole formation sliding down away from the left.

Ten minutes later it was getting quite clear of clouds except for a bank over the Santa Monica Mountains to the north and there, straight north, another fan was forming. As I watched it took shape -- illustration #2. The same broken semi-circle (with commas') but this time the bases of the rays were feathered about half-way out with end halves long straight wisps.

As I sketched, another fan had begun to take shape further east. It was hard to tell its size but I had estimated the first one at about 15 miles across and the second a little larger and the third larger yet. At the peak of its formation it looked like illustration #3. ...There in the middle of the central circle, hazy and a little faint was what looked like the top of a mushroom cloud. Or was it only a distant thunderhead that coincidentally found its way to a place behind the formation? The arms of the last, largest formation were rather wavy and feathery like some gigantic sea creature. It did not disperse as fast as the others, but held for a couple of hours, though it was pretty distorted by then. I could not estimate its size as I wasn't sure of its altitude.

Were they aircraft contrails? Certainly not! There was an airliner in the sky at the time -- a mere scratch on the smooth blue sky (see illustration #3, right center.).

The three formations were present in the sky at the same time although the first was getting quite distorted by the upper level winds before the last reached its peak.

Tuesday our weather changed from hot and sunny to rainy as the weather man said the path of the jetstream altered, and then there was the space shuttle explosion.

...The Russians seemed very sincere in their sympathy for the loss of our astronauts but only two days later it was printed in TASS and I personally heard Vladimir Posner say that Russia hoped that the United States would now realize what could happen if the S.D.I. program was further pursued. Was this friendly concern or a threat? It is very evident that if the S.D.I. can destroy a missile in flight, it can also destroy one on the ground. This would immediately put all Russian missiles in [reach of] our arsenal. They are already in place in the most desirable target areas -- their own launch sites. I'd be panicky too if I were a Soviet leader."

[Ed. comment: My sincere thanks to this thoughtful lady who took the time to sketch the cloud radial phenomena occurring in the Los Angeles "jetstream pivot point" at this critical time, just prior to the launch and destruction of the Challenger.

Anomalous cloud grid activity (formation and dissolution) in
the Los Angeles area has been positively correlated with Soviet Woodpecker activity by engineer Ron Cole, with 100% correlation in 30 straight Woodpecker measurement runs. Statistically, of course, this
is quite decisive.].

2. Continual cloud radials have repeatedly been seen and photographed over Huntsville, Alabama, associated with weather engineering and grid activity. Typical radials seen by this author are shown in Bearden, Soviet Weather Engineering Over North America, 1-hr. videotape, 1985. Huntsville is apparently a pivot point or "hinge point" for bending and controlling the jetstream.

3. Spectacular cloud grid patterns have been seen over Huntsville, Alabama and Los Angeles, California. An excellent videoclip of one of the Los Angeles area grids, personally observed and shot by KABC Open Mind talk show host Bill Jenkins, is shown in Bearden, Soviet Weather Engineering Over North America, 1-hr. videotape, 1985. An artist's sketch of an earlier gigantic grid, extending from horizon to horizon in every direction, seen over Huntsville, Alabama by Tom Bearden and Ken Moore, is also shown in the tape. The videotape is available from P.O. Box 1472, Huntsville, AL 35807. Sketches and details of another highly anomalous grid pattern observed in the greater Los Angeles area by engineer Ron Cole are shown in figures 5 and 6.

The reason that clouds of water droplets and/or ice particles detect the scalar interferometry and form signature patterns is simple: Consider each H_2O molecule as having two light little hydrogen atoms hanging on to the much heavier oxygen atom. The covalent sharing with the oxygen atom of the electron from each hydrogen atom means that (1) the electrostatic scalar potential between the H ion and the O ion it is bonded to, is rhythmically varying as the electron is shared back and forth, (2) this varying potential contains "electron spin holes" since it is made by the moving electron, (3) two such varying potentials exist since there are two H atoms sharing covalent electrons with the O atom, (4) the two H ions are at an angle of over 100 degrees with respect to each other, (5) the molecule assembly thus constitutes one part (one half, so to speak) of a scalar interferometer with imbedded electron spin holes for electron hooking, (6) Incident scalar waves from outside the system interact with the "half scalar interferometer." This scalar interferometry interaction is coupled to the covalent bonding electron because of the internal spin hole pattern of the molecular half of the interferometer. The coupled electron moves with the scalar pattern's changes, causing an observable interaction with and in the electrical structure and ionic potential of the molecule, (7) the weak H to H hydrogen bonding between molecules connects resulting ionic potential changes to the structuring of the entire macroscopic cloud assembly. Thus by scalar interferometry with the H_2O "half interferometers", an incident scalar EM pattern is detected and translated into patterns of E and B force fields. The H_2O molecules then "line up" in accord with the electrical patterns detected.

Thus the clouds form "signature patterns" according to the incident scalar EM radiation patterns. Giant cloud radials in the targeted area are probably due to the type and shape of antennas -- including the type and shape of the electrical wires establishing the antennas' ground planes -- 640used by the Soviet Union to project the scalar waves. Note that such "radial" antenna patterns were occasionally used by James Harris Rogers in his underground and undersea scalar EM transmission system.

[For Rogers' patents, see U.S. patent numbers 1,316,188, Radiosignaling system, Sept.16, 1919; 1,322,622, Wireless Signaling System, Nov. 25, 1919 (figure 6 of this patent clearly shows a "radial wire" ground plane antenna); 1,349,103, Radiosignaling system, Aug. 10, 1920 (the fourth version in figure 1 shows inside/outside variation which, for the long waves used, to a distant observer appears as a varying magnetostatic scalar potential using opposing B fields); 1,349,104, Radiosignaling system, Aug. 10, 1920; 1,220,005, Wireless Signaling System, Mar. 20, 1917; 1,303,729, Wireless signaling system, May 13, 1919; 1,303,730, Radiosignaling system, May 13,1919; l,315,862, Radiosignaling system, Sept. 9, 1919; also 958,829, Method and Apparatus for Producing High Frequency Oscillating Currents, May 24,1910.].

4. Anomalous power outages in Ventura County, Southern California on Nov. 8 and 9, 1985. Again, engineer Ron Cole, who lives in the affected area, investigated and reports as follows:

"On the evening of 11-8-85 in a rural area of Ventura County known as Carlisle Canyon, a strange electrical phenomenon began to occur at about 10:15 p.m. Our first observation was that random white dots began to appear on the TV screen, then began to increase in size and brightness. The brighter the dots got, the dimmer certain lights in our home became. Yet later we found that, when some lighting circuits were dimming, other circuits were causing lights to shine much brighter than normal. After a bit of checking, we were able to determine that lighting circuits common to pole 1 of the service transformer were the ones that were seeing a reduction in voltage, while all circuits on pole 2 were seeing an increase in voltage.

There is another interesting condition that was observed on the TV screen. The dots were in sync with the vertical field or frame rate of the signal. This means that the interference had to be of a frequency of 59.7 Hz or 29.85 Hz. Normal power line interference will form a grouped dash pattern across the screen and will strobe upward at the rate difference of 59.7 Hz or 29.85 Hz. In the 8 November case, there was no strobing of the dots whatsoever.

These conditions continued off and on for the rest of the entire evening and were observed by no less than six other persons that I know of. They were observed over the entire TV frequency spectrum, low band VHF, high band VHF, and on two UHF channels. Line interference is almost always most prominent on the low band VHF frequencies only.

These anomalous events would take place on a somewhat irregular time pattern; anywhere from 3 to 10 minutes apart. They would always last for about 2 minutes.

At 12:30 a.m. I went to bed and was not aware of any further activities until 6:20 a.m., at which time I was awakened by several sharp snapping or cracking sounds coming from the walls of my house. I rolled over and went back to sleep, only to be reawakened about 15 minutes later by my wife, who informed me that the power and phones were out. My comment was, "Some dummy must have crashed into a power pole," and I dozed off again.

At 10:15 a.m. the power and phones came back on line. Shortly after, our phone began to virtually ring off the hook. About a dozen neighbors up and down the canyon wanted me to check out their electrical wiring and various appliances. All of them were trying to explain their individual encounters and what took place when the power went out. Such things as wires snapping in walls, singing and humming sounds coming from wiring in walls, strong smell of ozone, light bulbs exploding, buzzing coffee pots, and a handful of other phenomena all took place just before the power went out at 6:20 a.m.

A typical example was that of Rob Steel. [Ed: Name changed for this report; his real name is in my files.] Rob lives four miles down the canyon from us. He had just turned on the lights in his barn and was getting ready to feed the livestock, when he realized he had left several needed items in the garage located about 75 yards from the barn. Upon entering the garage, he saw the garage lights began to flicker, then go to a dim orange glow. Upon stepping from the garage area, Steel saw that lights in the barn were so bright that he thought the entire structure was about to explode. He froze in his tracks for a moment and his whole house and garage began to hum. Then everything went out.

An interesting point to inject is that Mr. Steel's home and several others farther down the canyon from us are being fed from a different 19 kv power feeder source than the 14 kv feeder that supplies us and most homes in the canyon.

At about 2 p.m. on 11-9-85 I was in contact with the power utility company (Southern California Edison Company) to inquire as to the cause of the power outage. My first assumption was wrong. No power poles had been knocked down; only a ceramic fuse in the 19 kv feeder system had blown and a two-pole oil breaker had kicked out on the 14 kv feeder system. Load charge recorders at the power company show that both fuse devices kicked out at exactly the same time, but they are in no way common to each other as to load distribution. They only supply power to adjacent areas.

Also, the phone company has no record of its service being out, yet the phone service was restored when the power was restored. The phone company does not use Edison Company's power to power its phones. Again, the only commonality is that the phones and phone lines were in the same area.

Numerous magnetic breakers, used as manual switch devices for well pumps and other services, were on when power was returned. These switches had previously set in their off state.

A strong electrical-type ozone odor was detected at five locations at the time the power went out.

Later we found that a Research and Development laboratory in a nearby area measured 29 Hz intermittent signals late on the night of 11-8-85. These signals were interfering with some critical tests the lab personnel were trying to accomplish. The laboratory itself did not experience a power outage.

At this point in time, the only realistic surmise we can come up with is that a tremendous ELF or scalar ground wave was adding and subtracting to the grounded neutral service side of the power pole transformers so as to sum in and out of phase. When peak nodes were achieved, all line transformers ended up back-feeding the feeder lines out of phase, causing the final power outage.

Twenty-one persons are aware of the strange conditions of the power outage and prior events. [Ed: Their names are in my files.]"

Editor's comment: Another anomalous power outage also occurred in the same area. This occurrence is possibly associated with effects of the scalar interference grid adjustments. If the Soviets were preparing for a major test of the grid in the Launch Phase ABM mode, substantial tests and exercises may have been performed before the actual "wet run" against the shuttle launch on Nov. 26, 1985 -- about two and a half weeks after the anomalous power outage at Carlisle Canyon.

See the Rogers' patents, referenced above, for ideas of how scalar EM signals couple to the power lines and telephone lines.

As this book goes to press, John Bedini has notified me that his new and very sensitive developmental scalar detector positively verifies scalar frequency "spike" activity on the Woodpecker grid (and possibly the ground reference) from 50 Hz to 10 MHz. A normal instrument will definitely not see these signals. John's lab is at Sylmar, California and about 70 miles from Carlisle Canyon.

5. During the Skylab mission, NASA astronauts observed and photographed a mysterious green glow of the atmosphere. The glow was over 1,000 miles long and over 100 miles wide. From Carlisle Canyon, Ventura County, California the sky has also been observed to possess a mysterious green glow from horizon to horizon, on three occasions. [Editor's comment: It is hypothesized that this green glow is associated with grid activity in the Launch Phase ABM System mode.]

6. Just prior to the hapless launch of the Challenger on Jan. 28, 1986, the Soviet Union sharply bent the jetstream down through the center part of the country, then curved it eastward across the Florida panhandle. This exposed the waiting Challenger on the launch pad to severe cold air, brought down from Canada by the sharply deviated jetstream. The use of the scalar interferometry aspects of the Woodpecker grid for weather engineering over the U.S. has been documented previously. [Bearden, Soviet Weather Engineering Over North America, 1-hr. videotape, 1985;

Bearden, "USSR: New beam energy possible?", Defense & Foreign Affairs Daily, 13(111), June 12, 1984, p. 1-2.]. Wilson's cloud radial sightings on Jan. 26, 1986 and Cole's giant cloud grid sightings on Jan. 24, 1986 are directly connected with adjusting the Woodpecker grid and deviating the jetstream, to carry cold air to the Florida launch site.

7. The previous testing of the grid in the Launch Phase ABM/Anti-bomber Mode, using actual jet aircraft as "wet-run" targets, has been demonstrated by various anomalous incidents.

As one probable example, see "Jetliner drops 32,000 feet; 400 aboard; 50 are injured," AP release, Huntsville Times, Feb. 20, 1985, p. 1 and "China Airlines Pilot Denies Cockpit Error," AP release, Huntsville Times, Feb. 21, 1985, p. A-9. In this incident (see figure 7) a Boeing 747, flying at 42,000 feet and bound for Los Angeles, experienced unusual engine flameouts while still out from San Francisco. In a hair-raising plunge toward the earth, the pilot fought to restart the engines and regain control of the aircraft. After a fall of some 32,000 feet in two minutes, the engines finally restarted, and the pilot was able to fly into San Francisco and land safely.

We have already explained how the Soviets are able to track the aircraft's jet engines. Later in this Appendix we show just how accurately an actual "scalar EM missile" may be focused by the Soviets on a hapless target. If a negatively biased pulse or continuous wave scalar EM "energy extraction" beam hits the engines, the extraction of energy will result in engine flameout. (No heat energy, no combustion of the fuel.). This is apparently what happened to this aircraft. In the presence of "splatter" from the extraction beam targeted at the engines, the aircraft instruments were seriously affected. Different instruments have different responses to such an anomalous scalar EM kindling effect. Thus a signature would be that the instruments disagree with each other, and need not record what actually occurred. This appears to have been the case, constituting a signature that scalar EM was targeted against the aircraft. The pilot's instruments apparently indicated that the control system had failed, while the flight recorder apparently indicated that it had not.

Let us assume this was a Soviet test. When the distant Soviet operator turned off the extractor beam, the engines returned to normal state after a "discharge time constant" period. They normalized before the plane struck the ground, so the pilot was able to restart the engines and proceed.

Notice that this was a limited test to cause engine flameout only. If the scalar EM missile had been used against the aircraft in the "pulse" mode, it would instantly have exploded in mid-air.

The crash of an India jet aircraft outside Great Britain may have been a test of the same weapon in the pulsed "destroy aircraft" mode, since there are indications that the aircraft suffered an anomalous midair explosion. Another candidate for such a possible "shoot-down" of a jet aircraft is an (Italian) Itavia DC-9 that crashed into the Mediterranean in June, 1980. Both Itavia and the Italian Transportation Minister Salvatore Formica believed that a missile struck the jetliner and was the likely cause of the crash. It may have been a scalar EM missile and a full-up test by the Soviet Union. See "Plane was probably hit, judge says," Birmingham Post-Herald, Jan. 17, 1981.

Also the present author has knowledge of at least one instance in the early 1980's when an American-made tactical ballistic missile was anomalously destroyed shortly after being launched by troops in Europe. The destruction was anomalous and a large hole was inexplicably burned through the side of the missile -- exactly as if it had been struck by a scalar EM missile test in the anti-tactical missile (ATM) role.

8. As another example of airborne scalar EM activity in the Woodpecker grid, in January 1985 a U.S. Navy-dispensed chaff cloud, dispensed well-offshore from San Diego, California was caught by an unexpected wind and blown toward the city. (See figure 8.). As the chaff cloud moved in, significant failures of electrical systems and electrical components resulted. Power was disrupted to as many as 60,000 homes by the incident.

The sudden, unpredicted wind was suggestive of a wind blowing toward an artificially created low pressure area. Under certain conditions, a specialized structure such as that of a piece of sophisticated chaff will reflect scalar waves of frequencies within its cut bandwidth. If scalar modulation frequencies within the chaff bandwidth were present on the Woodpecker carrier grid above and surrounding San Diego, a myriad of reflecting bits of chaff in the moving chaff cloud would produce myriads of random, invisible "fireflies" of EM energy kindled at a distance, from random scalar interferometry, in a zone surrounding the cloud. As these invisible "firefly" pulses of

EM energy pulsed inside components of the electrical systems and electrical controls in San Diego and vicinity, extensive and random internal electrical interference occurred. This lead to widespread, anomalous electrical failures throughout the city.

Note that this activity preceded the huge Soviet scalar EM exercise of April-May 1985. The grand exercise would certainly have been scheduled well in advance by Soviet strategic forces controlling the scalar EM howitzers and Woodpecker grid weapons, and adjustments and smaller tests would have been being made for some months before the tests.

9. Other anomalous "electrical strikes" certainly exist, suggesting Soviet testing may occur widely throughout the world, yet be reported as ordinary but anomalous phenomena. An example which comes readily to mind is the anomalous blast (or blasts) that struck Bell Island, off the east coast of Newfoundland, on April 2, 1978. Persons on the shore of Conception Bay reported seeing fireballs coming down out of the sky and hitting the island, according to Royal Canadian Mounted Police. Highly anomalous atmospheric electrical activity preceded the blast. This may have been Soviet testing of scalar-created electromagnetic missiles. Extensive information on this incident can be obtained from P.A.C.E., 100 Bronson Ave., Apt. 1001, Ottawa, Canada T1R 6G8.

As another possible example, villages in an area of West Donegal in Ireland have been terrorized by freak "lightning bolts" for over two years. Roofs have been literally stripped off, windows smashed, telephones and television sets blown up, and pipelines wrecked. On Dec. 25, 1984 a mighty blast caused a three-day blackout: it accompanied a snowstorm, the first "white Christmas" in the area in 20 years. See "Bolts from the blue," Fortean Times, Issue no. 45, Winter 1985, p. 5.

10. Scalar spikes or pulses from the Soviet testing may also cause other anomalies, including deaths of unsuspecting persons using the telephone. For a candidate event of this type, see "Killer Phones," Fortean Times, Issue no. 45, Winter 1985, p. 8-9; also AP release, Huntsville Times, May 30, 1985; AP newswire June 2, 1985; and New York Times, Sep. 11,1985.

On May 21, 1985, five days after passing a complete physical examination, 17-year-old Jason F. Findley of

Piscataway, New Jersey was on the phone at his grandmother's house, talking to his girl friend. An odd click occurred on the line, followed by a gasp from Findley and then only the TV playing in the background. His grandmother found him unconscious, still clutching the phone in his hand. Rushed to Muhlenberg hospital, he was pronounced dead shortly afterwards. An autopsy could not determine the cause of death, and the telephone company found the phone working properly, properly grounded, and no evidence of excess electrical charge. Findley was lying on a wooden bed which would not conduct electricity. He had a hemorrhage of the inner ear. There had been an electrical storm over Scotch Plains, New Jersey the night Findley died.

AP wire services were told by the special forensic investigator with the New Jersey medical examiner's office that about six people had died in the U.S. in similar circumstances. Others had reported being knocked unconscious by "high voltage shock" from their telephones. Several weeks before Findley's death, another man from Whitehouse Station, New Jersey had been found unconscious with a telephone in his hand. According to the Consumer Product Safety Commission in Washington, D. C., in 1984 nearly 12,000 people in the U. S. were taken to emergency rooms with injuries related to telephones. A hundred of them died, although exact details were not revealed.

Note that the giant Soviet scalar exercise of May 1985 had been detected and verified by Golden. Substantial activity in the Soviet weapon complex, and in the Woodpecker grid over the U.S, continued throughout May and beyond. A phone line may by chance detect one or more atmospheric scalar EM pulses, just as occurred in the blackout in Ventura County, California on Nov. 8-9, 1985. These scalar pulses can travel along a phone line and be broadcast into a person's ear and brain from the telephone earpiece. The proper scalar EM pulse can induce both "acoustic shock" in the inner ear and "electrical shock" conditions in the nervous system. The pulse may also interrupt the body's electrical timing pulses to the heart, causing the heart to stop without physical damage. The scalar EM shock to the brain and nervous system can knock the person unconscious or, if sufficiently strong, kill him instantly. The condition is worsened if the person is ungrounded, since then he acts as a large, open-ended capacitance in series with the telephone instrument's inductance. In such case, the scalar resonance of the equivalent series LC circuit can be sharply excited and resonated. By the nonlinearities of the body and nervous system, the scalar resonance can be translated into an ordinary electrical pulse or resonance. Since the scalar power is not translated into ordinary power except inside the nonlinearities of the human capacitor/nervous system, no damage to the telephone or phone lines need happen. [At the ComTec exhibit in Las Vegas in 1984, John Bedini demonstrated powering a 200-watt speaker system through a 100-foot length of #40 magnet wire, using scalar EM means. He put some 200 "watts equivalent" of scalar energy through the tiny wire to the speakers, where a small Bedini translator translated it back into ordinary electrical "force field" energy, powering the speakers. This was much to the astonishment of the technical audience, since the wire was quite cool and exhibited no evidence of heating, even though by conventional thinking it should have been instantly melted.]

The bottom line is: With increased Soviet scalar weapons activity over the U.S., the telephone system is likely to become more hazardous to humans using it, when the instrument is connected to the external wire. A radio phone is much safer against anomalous scalar EM "spiking."

11. The metal-softening detected and verified by Frank Golden on Jan. 1, 1986 is certainly indicative of a new mechanism or effect added to the Woodpecker grid. The highly specialized nature of the particular detector/amplifier which Golden was using provides strong evidence that the signal was actually derived by recording the scalar EM signals produced by a human cerebrum (two cerebral hemispheres connected by the corpus callosum, forming a scalar interferometer) when the human was successfully performing psychokinesis (metal-bending). The fact that Golden was able to nullify the signal locally by special methods worked out by him lends further credence to this hypothesis. In any event, three hours of very objective experimental data strongly support this thesis. It is therefore indicated that (1) the metal-softening signal had been added for a purpose, and (2) something made of metal was going to be softened, leading to its failure. Certainly the *Challenger* would have been an ideal target; softening the metal on its boosters and fasteners by even a small percentage would significantly reduce the vehicle's ability to withstand the

stress during launch. This of course is circumstantial evidence only, but the finger of suspicion is there nonetheless. It is a fact that the metal-softening signal was and is in the Soviet Woodpecker-repertoire; it is a presumption that it was intended for use against the Challenger.

- FINAL DRESS REHEARSAL BEFORE THE BIG SHOW -

12. The shuttle launch from Cape Canaveral on the evening of Nov. 26, 1986 seemed smooth as silk to the army of official observers and onlookers. In reality the Soviet Union clandestinely conducted one or more Launch Phase ABM System tests against the vehicle, using it as a convenient target.

Figures 9, 10, 11, and 12 are included to give the reader some preliminary background on the highly significant events which occurred in conjunction with this flight, and previous to it. These figures are newspaper articles from the News Tribune, Fort Pierce, Florida. The articles are used by permission.

Anomalous atmospheric "booms" and airquakes had occurred in the Florida area for over three and a half years prior to the launch. Sixteen counties, most of them on the northern Gulf coast or close to it, had reported booms during the two-year period preceding April 1984. State and local emergency preparedness officials and U.S. Air Force Base representatives met but could not resolve the mystery of what was causing all the anomalous booms.

In fact, many booms had occurred in and around the gulf coast of Florida, particularly offshore from St. Petersburg, starting from several years earlier.

These anomalous booms were caused by the Soviets adjusting and testing the Woodpecker scalar EM grid for weather engineering and potential weapons use. The booms and airquakes were certainly not confined to Florida alone, but also occurred at many other locations throughout the U. S. and Europe.

Mysterious, highly localized seismic microquakes also had occurred at widely scattered locations throughout the U. S.

On at least two shuttle flights prior to the Nov. 26, 1985 launch, large anomalous "booms" had occurred over or around the launch site after launch. No one in NASA knew what they were or what caused them.

So prior to Nov. 26, the Soviets had already prepared and tested the Launch Phase ABM system mode of the grid against at least two U.S. shuttle launches. However, so eerie and strange are the scalar EM weapons that they had been able to do so without the U. S. government even becoming aware of what was going on. In the Kremlin, they must have marveled at our continued ignorance.

At any rate, they tested the Launch Phase ABM system again on Nov. 26, and this time private U.S. citizens happened to capture at least some evidence of what was going on. It still would have died there without surfacing, except for a curious chain of events. Let me briefly recount those events.

****

Lucius Farish publishes a fine little monthly newsclipping collection called UFO Newsclipping Service (Route 1, Box 220, Plumerville, AR 72121). In it she includes clippings on all sorts of anomalies, including UFO's, strange light phenomena, etc. Because of my long work in UFOs (for some time now, placed on the back burner due to the press of my work in Soviet scalar electromagnetic weapons), I've subscribed to Farish's service for several years.

And this time my unorthodox interests certainly paid off. Farish published a clipping of the article, "NASA officials stumped by strange light, boom," by Susan Burgess, News Tribune writer (see figure 10). The moment I read the article, I realized that the Soviets had actually tested the Launch Phase ABM System's area mode against the shuttle launch of Nov. 26, 1985. Further, George Suchary had taken a picture of the marker beacon as it was slewed away at the conclusion of the test.

With alacrity I contacted Ms. Burgess and, through her, George Suchary. Both were very helpful, and Mr. Suchary gave me permission to use his important photograph of the light moving away after the test.
Ms. Margery Bril , the kind librarian at the News Tribune, sent me four clippings.

After reading the article by Julie Enders, Showcase Editor of the News Tribune, I contacted her also. Although extremely busy, Ms. Enders kindly gave me additional details, including the fact that Bob Gladwin had taken a series of eight stills of the launch itself, and in one frame an anomalous, curving line of light with a splash on the end appeared.

At first I thought it might be the answer to a dream. Very tentative information suggested that the "curved light with a splash on the end" might have occurred in one of the pictures taken during the launch sequence itself, with the light striking directly under the shuttle shortly after it lifted off. I was positive the Soviets could strike at the shuttle (or a missile) with a "scalar EM pulse" missile, but hardly dared hope someone could have actually been lucky enough to get a photograph of it.

From my acquaintance with two masters of paranormal photography -- the indomitable Trevor James Constable and a close friend, Joe Gambill -- I understood how one could possibly get a picture of such a strike -- assuming it occurred -- at night, when the same picture could not have been taken in the daylight. I also understood why the camera might catch it when the human eye would not see it.

It seemed that, between them, these friendly, cooperative persons just might have gathered together the positive evidence to prove that the Soviets had struck at the shuttle with an offset test of a scalar EM missile, using a marker beacon for adjustment. (As it turned out. it was not to be as definite as that!) However, time was of the essence.

The Soviet tests had definitely included a test in the "area burst" mode, which can catch and destroy several missiles fired from a deployed silo complex at once. The clinching evidence I had needed for so long on a Soviet test of the pulse mode -- the scalar EM pulse missile -- just might be there in one of Bob Gladwin1s photographs. But there was no time to lose; such evidence is fleeting. and unless I moved quickly, it was likely to fade away and disappear forever. With persistence, the rest followed swiftly. Mr. Suchary graciously gave me permission to use his photographs. These of course prove that the marker beacon was there. (In addition, it was seen by numerous persons.). The News Tribune gave me permission to print the articles. Mr. Gladwin furnished his negatives and gave me full permission to analyze and use his photographs. Personal friends, Everett and Shirley Edwards, printed the photographs in their private darkroom so the negatives would not be out of safe hands for even a moment.

At the time, this book was almost finished. If the photo of the candidate Soviet use of the electromagnetic missile was accurate, quick work would be necessary if it was to be included. My friend and publisher, John Ratzlaff. had already agreed to swiftly publish this large output as soon as I could get it to him. At Omni Video Publishing, Ms. Electra Briggs was alerted to the potential importance of what was coming. She and Mr. Glenn Shoemaker swung by my house from New Orleans, and a quick, informal videoclip was taped, announcing the book. (Murphy's law -- if anything can go wrong, it will -- got me there. Inexplicably, in my near-total fatigue from months of 19-hour days and 7-day weeks on this project, I spoke the date of the Titan explosion as April 19th, knowing full well it was the 18th! It happens. Electra suggested she slap a correcting statement over the video. Done. Be ready to get it out. It's too important; don't sweat the small stuff.)

Zerox copies of the photos were received. There in the fifth photo (or so it seemed) was an unequivocal strike of the scalar EM missile, in the launch sequence itself. The assumed strike seemed to have occurred right under the shuttle, a few seconds after liftoff.

The evidence seemed complete. All that was left was to receive the actual negatives and verify the sequence. At last we seemed to have the smoking gun. The Soviets would have been caught redhanded.

Based on the advance zerox copies, the manuscript was altered. Everything was ready. And then the negatives came in.

In this business, you learn to meet and accept a lot of failures. Things often go astray, and don't wind up as they seem at first blush. This time was no exception. Murphy got us again! The photos on the negative were in a different order then they had been on the zerox copies.

There's no mistaking the order in which the pictures were taken. There they are on the negatives, one right after the other, and clearly numbered. And the curving light with a splash at the end did not occur during the launch sequence at all. Instead, it was taken before the launch -- just how long remained to be seen. Everett and Shirley took the photo and developed it at both extremes: very dark and very light, to bring out all the details possible.

The results were most interesting. As shown on the lighter print (figure 13), the light does not curve down out of the sky and strike toward the ground, it turns up toward the sky and strikes above the distant treeline. Further, as shown on the darker print (figure 14), it does consist of a little ball of light, just like a scalar EM missile would appear. No apparent structure to hold the light appears in either picture, though one could not positively rule this out completely without microdensitometer tests. (One can inadvertently get artifacts like this by focusing on a ball-like light bulb, for example, and then moving the camera while the shutter is still open. On the other hand, there is no evidence that this happened at all, and no street lamp post or other foreign object in the photo.)

(The remaining photos of the liftoff sequence are shown in figure 15.).

We called Mr. Gladwin. He verified that the photos had been taken in order, one right after the other. He had not had the camera on a tripod, but had steadied it on a railing. In other words, the "light streak with a burst on it" had been taken just before the liftoff. Also, Mr. Gladwin had not observed 'the marker beacon, and had not attempted to photograph any such "light in the sky." In fact, visually he had not observed any such streak and burst of light in any scene he was photographing.

So the question is, exactly what did Mr. Gladwin photograph in that photo, just prior to the shuttle's liftoff? The answer is. we just don't know for sure.

Let's run through the two possibilities:

(1) He may have snapped an artifact while moving the camera. If so, the camera was definitely quite still at least most of the time the lens was open, for the treeline is quite clear in the lighter photo, which reduces light saturation and shows details more clearly. Further, there is no evident support or structure attached to the light itself; it seems to be a "disembodied" light. So this possibility is ambiguous, though reasonable. Mr. Gladwin does not recall any such movement of the camera; it was steady while he was shooting.

(2) He may still have snapped a scalar EM missile. If so, it means the Soviets fired a "small test" of the exothermic pulse or scalar EM missile in advance of the actual shuttle launch. Let's pursue that for a moment, and suppose it to be true.

The Soviets already had the marker beacon up in the sky -- that's certain. Many persons saw it. Soviet trawlers off shore and Soviet satellites could also have given the actual position of the marker beacon. Thus the Soviet LPABM System would have had (a) the actual parameters the computer had used to transmit the beacon, and (b) the actual location at which the beacon emerged. Comparison of (a) and (b) is much like having a "meteorological data message" in field artillery: One has the corrections to apply for specific conditions of the medium that cause deviation.

These corrections can then be applied to calculated or "table" data to adjust firing for real-world conditions.

So far so good. The Soviets had the exact position of the registration beacon, and could apply corrections for a shot of the scalar EM missile. They certainly would know the exact position of the shuttle on its launch pad.

If a fairly substantial offset for the scalar EM missile shot were used, "mett corrections" could be applied and a small scalar missile could be zinged in, stopping momentarily at the final offset "strike" position so that a track could be obtained by the scanner extraction beam. Then by comparing the detected offset position of the "burst" of the scalar EM missile to the detected offset position of the marker beacon, the difference could be applied to the beacon's true position to get the true strike position of the missile. The offset used could then be subtracted to give the location where the missile would have struck without the offset, had it actually been fired at the rising shuttle after liftoff. This "adjusted final strike position" could be compared to the shuttle's expected early trajectory (which varies only slightly from standard for the first few seconds) to determine the expected combat success of the shot. It's a little roundabout, but it's a very safe way to do it if one wants quite positive assurance that the missile will not strike the shuttle and destroy it. Since the Soviets delayed the "area burst" and its concomitant atmospheric "boom" to T + 12 minutes, it is evident that a large offset was used for the area strike -- probably about 10 extra minutes -- to positively assure that there would be no actual damage or threat to the shuttle.

It seems logical, then, that they might fire the small scalar EM missile well offset from the shuttle, and just before its launch, to prevent any possibility of actual damage to the shuttle.

So there you have it. Mr. Gladwin's photograph is consistent with such a careful, safe scalar EM missile test by the Soviets, prior to the actual liftoff of the shuttle. On the other hand, it's not possible to say with certainty that that is what it is. It may simply be a very peculiar artifact. In fac, if it were not for the other indicators, one would most certainly not consider such a bizarre possibility as an offset Soviet scalar EM missile strike at the shuttle.

If the "streak" photo is examined as a candidate for a sca1ar EM missile test, then one other thing must be explained: Why did the film capture the test when observers did not see it at all? That, of course, we can explain!

So back to our presentation. Here I'm going to assume -- and accent that this is a postulation -- that the Gladwin photo actually represented a scalar EM missile test. We will run through a possible sequence of events, based on that assumption. We will hypothesize the LPABM system operation and the Soviet conduct of the test. The major events here in the U.S. may be quite real; those assumed to occur in the Soviet Union, of course, are "author's license" -- but hopefully realistic.

****

The evening of Nov. 26, 1985 is perfect. At Cape Canaveral, the shuttle Atlantis is poised on its launch pad waiting to move majestically into the heavens on its impending journey. As launch time approaches, everything is as smooth as a cat's whisker. There is, however, just one small anomaly.

A mysterious light is hanging up in the sky, staying still for awhile, then gently rocking back and forth. The light is a Soviet marker beacon for a scalar EM howitzer. The howitzer, employed in a special scalar EM channel contained in the Woodpecker transmitters and interference grid, will shoot through the EM carriers at an aiming point offset from the shuttle.

Since this is still to be a nondestructive test, no chances will be taken. The pulse mode will be used, and a "scalar EM missile" -- a bundle of energy buried in hyperspace around its moving zero-point in this world -- will be fired directly at an offset aiming point prior to launch of the shuttle. A substantial offset in distance will be used to prevent posing any danger of inadvertently hitting the shuttle on its launch pad.

The marker beacon is necessary for precision. Its desired position will be calculated and the beacon will be placed on station. By placing this source of continuous EM energy in the area, it can be detected by the scanning "energy extraction beam" and tracked by the distant Soviet operator. Soviet trawlers and satellites monitoring the test will report the true position of the marker beacon, which will deviate from the calculated location due to conditions of the channel medium (the Woodpecker beams) at the time. Comparison of the beacon's true position to its desired, calculated position "registers" the marker beacon and yields the "meteorological corrections" which must be applied to standard firing table calculations. These corrections can be applied to any further shot into the area to correct its aim, just as standard field artillery applies registration corrections in the target area.

When the shuttle boosters ignite, an additional track will be obtained from it. The offset from the received track of the marker beacon and the received track of the shuttle booster flame thus will give the exact correction or "shift" from the marker beacon settings that should be used to set the howitzer's aim. In other words, a "relative" firing, offset from the marker beacon registration track, will automatically compensate for any vagaries of the medium experienced by the beams in transmission.

The Russians, being excellent artillerymen, have simply applied the standard artillery technique of shifting from a known registration point.

The Soviet Launch Phase ABM System is cocked and ready. This is the last test in the "wet run" series in which an offset will be used. If everything goes as planned, future shots will move into the next phase, where actual U.S. targets will be destroyed. The two great powers are already at war, but one of them does not know it yet. Because of the importance of this last test before the next step in hostilities commences, Gorbachev himself is monitoring the test.

The countdown begins. In Florida a great many persons are observing the event. George Suchary has already spotted a strange light hanging in the sky, where none ought to be. Bob Gladwin, resting his camera on a railing, prepares to snap his first picture so that he will be sure to have a sequence completely across the launch.

Deep within the Soviet Union, a large display screen is illuminated. The marker beacon's track is clearly shown on the display, as are synthetic symbols for the shuttle on its launch pad, several Soviet ships off the coast of Florida, and several Soviet satellites.

The control officer barks, "Missile test! Proceed!" The simulation officer presses a switch, and a simulated shuttle launch track appears.

The operator responds immediately, "Launch detected!" The identification officer, scanning the frequency components and the signature of the energy extracted from the launch, calls out, "Missile! Target hostile!" He presses a button, and a light illuminates on the panel, marking the target as a hostile missile. The launch track begins to blink.

The control officer announces, "Prepare to fire!" "Pulse mode!" "Strength one!" "Test!" "Apply burst offset!" The operator rapidly flips switches, setting the mode of fire and the offset. Instantly lights light to show that the computer has computed the shift and offset, and corrections. A red "Ready to Fire" light illuminates and a low siren begins its wobbulating growl.

The control officer orders, "Fire!" The operator presses the fire switch. A "Fire" light appears. A slight, deep shudder is felt briefly as the howitzer fires its scalar EM pulse missile of deadly energy. On the screen, the path of the scalar EM missile is traced out as it speeds toward its target far over the horizon.

In Florida, George Suchary is getting more and more curious about that pesky light. Bob Gladwin is preparing to snap his first photo as the final seconds of the countdown tick away.

On the distant Soviet screen, a sudden small burst appears, superposed over the synthetic shuttle track. The operator yells, "Burst!" On a smaller screen, a vertical profile shows the strike directly underneath the target. Immediately a blinking "Target Killed" light appears as the computer assesses the shot a kill.

The operator excitedly calls out, "Kill !" "Direct Hit!" Cheering breaks out from the firing team and the onlookers. Gorbachev and his entourage are smiling broadly and clapping. The cheering quickly hushes as the crew and participants continue to watch the track of the rising shuttle, and prepare for the launch and the next test.

Bob Gladwin has snapped his first picture (figures 13 and 14) leaving the shutter open a bit to allow for the nighttime conditions. As luck would have it, the scalar EM missile strike Occurs during the time the shutter is open. The film has captured the strike by a special process, even though human eyes have not seen it. (We will explain that shortly.).

At 7:29 the Atlantis's boosters ignite and the vehicle begins to rise smoothly off the launch pad. She will continue to rise, then pitch over to a 45 degree angle and proceed down range..

Bob Gladwin is snapping pictures regularly, one after the other.

In the local Florida area, hundreds and hundreds of persons are watching the flawless launch. The tip-off of the Indian River Community College basketball game and the St. Lucie County School Board meeting are held up while participants watch the Atlantis begin to rise serenely upward.

In the Kremlin, another track has appeared on the control screen display. Once again the sharp-eyed operator snaps, "Launch detected!" The identification officer, scanning the frequency components, tersely rasps "Missile! Target hostile!" Again he presses a button, and a light lights on the panel, marking the target as a hostile missile.

The control officer orders, "Simulate multiple firings!" The simulation officer acknowledges, "Multiple firings simulated!" and presses a button to cause the computer to simulate multiple launches on the display.

Immediately other synthetic target tracks begin to appear on the display screen, one by one, clustered around the shuttle launch at various separation distances, pre-arranged to represent multiple firings from a missile silo complex for this exercise. A special audio alarm sounds as each track appears.

The operator immediately calls out, "Multiple tracks! Missile launches!" and then "Identified hostile!"

The control officer orders, "Prepare to fire!" "Area pulse mode!" "Test!" "Apply time offset ten!"

The operator flips switches rapidly, acknowledging. Lights illuminate on the console, showing status of preparation for firing. The "Ready to Fire" light illuminates and the low siren begins again.

Back in Florida, Bob Gladwin has stopped snapping photographs. George Suchary has gone into his house to find his Polaroid camera and take a picture of that pesky light still hanging up there in the sky.

Back in Russia, the fire control officer orders, "Fire!" The operator presses the fire switch. The "Fire" light illuminates, immediately blinking, and the siren changes tone. On the display screen, all target tracks are blinking. A large light on the console comes on, showing that an "exercise time offset" of 10 minutes has been applied. A digital clock starts ticking off the minutes.

Minutes pass as the offset time ticks down.

Back in Fort Pierce, George Suchary is coming out to take photographs of that darn light, which is still hanging up there!

Folks are streaming back into the Indian River Community College gymnasium for the basketball game. Attendees at the St. Lucie County School Board meeting are wandering back inside, to get ready for the meeting.

More minutes pass.

Back at the control console in the Kremlin, the offset clock ticks down to zero. The siren ceases its wobbulating tone and holds a steady note. The "Fire" light ceases blinking and illuminates with steady brilliance. A deep shudder is felt as the howitzer fires again. On the screen, the rapid trace of the mighty scalar EM serpent is shown as it races toward its target.

Suddenly it reaches the target area, and a large blossoming light appears, covering all the target tracks. The operator announces, "Burst!"

All the target tracks flare brightly, then dwindle and die. The "Targets killed" light illuminates and the operator yells, "Kill! All targets killed!"

Wild jubilation breaks out. Everyone is grinning and clapping. Gorbachev personally congratulates the fire control officer and pumps his hand. The tension relaxes visibly. In the noise, the operator touches a joystick and slews away the marker beacon, preparing to shut down the system.

The final test has been a crowning success. Now the real first phase of active combat begins. "And the fools don't even know it yet!" a grinning Gorbachev delightedly announces.

Back in Fort Pierce, precisely 12 minutes after liftoff, high in the atmosphere above the launch site and a little downrange, a tremendous rumbling boom suddenly rocks the coast for hundreds of miles in each direction. The blast is heard as far north as Charleston and as far south as Key West.

George Suchary is taking pictures (figure 10) as the hanging light in the sky suddenly begins to move away, obeying the controls of a Russian operator thousands of miles away. Bob Gladwin has already finished snapping his photographs (figures 13, 14, and 15) of the launch and taken down his camera.

The anomalous light disappears rapidly in the distance, moving faster than any jet aircraft.

People gradually resume their normal activities, talking about the beautiful evening and the perfect launch. Many of them have noticed the strange light that hovered and bobbled in the sky, then sped away.

The final Soviet registration of their eerie weapons for World War III has been completed. A totally different kind of Pearl Harbor -- more akin to a Trojan Horse -- has been prepared for the unsuspecting United States.

Countdown toward Armageddon begins.

****

George Suchary's photograph of the marker beacon, just after it had started slewing away, is shown in figure 10, as printed in the News Tribune.

Bob Gladwin's photographs of the shuttle launch are shown in figures 13, 14, and 15.

Figures 13 and 14 show two developments of the same shot, one light and one dark. The light one shows the treeline in focus in the distance, with the light streak and burst.

Figure 15 shows liftoff of the shuttle and its rise and tilt over on the first part of its trajectory.

Figure 16 shows a possible detailed interpretation of the first Gladwin photo. The simulated aim point was offset from the shuttle, and the strike was directly at the offset point. The computer computed the burst strike strike of the scalar EM missile from the adjusted registration data, and determined whether or not the target was killed.

The control precision is shown by the small size of the scalar EM missile.

The strike of the weapon is caught by the camera, but not seen by the naked eye. None of the many hundreds of onlookers saw the strike, though all of them saw the shuttle launch.

There is a very good reason for that, though it is not commonly known.

Constable

The reason is that Bob Gladwin's camera was utilizing a form of photography pioneered -- to the best of my knowledge -- by Trevor James Constable. At least I learned about it from Constable's books and articles. I then told it to my good friend, Joe Gambill, and Joe applied and adapted it to the unusual photography which he performs. Both Constable and Gambill are masters of this type of photography. Once I got deeply into scalar electromagnetics, I finally figured out what was going on in this methodology.

Briefly, here's the way it works. Scalar energy, of course, has to be detected by some sort of interference phenomenon. There exists a very special way to get a camera to perform such interference for you.

In the EM spectrum, the infrared and the ultraviolet have a special relationship to each other. The ultraviolet is exactly twice the frequency of the infrared, if the two zones are properly chosen. In other words, the UV is the first harmonic of the IR.

The scalar EM energy, since it operates in the Kaluza hyperspace surrounding every point in ordinary space, may be considered to be composed of pure spin. (That is, it's moving in a dimension where each particle of that dimension is spinning). Harmonics there are spin harmonics.

In this photon-interaction produced level of reality (the ordinary world), the IR and UV bands are more closely connected to the "shadow world" in which scalar energy moves. Thus there is a sort of shadowy "swirling" of the scalar energy near the IR and the UV. Entry of the scalar energy into this world, through the IR and UV windows by a kind of "harmonic interferometry," is normally prevented by the presence of visible light. That is, visible light "squelches" the "paranormal channel" that lurks beneath the IR and UV zones.

To make use of the IR and UV interference source zones, Constable covered his camera lens with a special filter (18A) which is opaque to the visible light spectrum and transparent to the IR and UV. Note that the film is sensitive to the IR and UV region we are talking about, but the human eye is not.

When pointed at a sufficiently strong source of scalar energy, such a specially filtered camera has unique characteristics. It strips out the visible spectrum, but still admits the IR and UV spectrum. The scalar energy surges through these two source windows, and phaselocks harmonically. That is, the scalar energy entering through the UV window fits twice neatly in the scalar energy entering through the IR window. This interference, on the film, is (recall) swirling in frequency. The net result is that the film records the interfering scalar energy as visible spectrum energy.

Infrared film can be used to increase the response in many circumstances.

Both Constable and Gambill have rigorously proven this technique in literally thousands of "paranormal" photographs. (They do not necessarily use my scalar EM terminology, but the technique is rigorous and works, regardless of terms.)

Under nighttime conditions, sometimes the particular lens and film combination will phaselock between IR and UV for incident scalar EM energy. This is particularly true when a relatively strong source of IR is in the vicinity.

While Bob Gladwin was taking his photographs, there was no suppression of the IR/UV phase-lock effect by visible light because it was night and there was hardly any visible light entering his lens.

Thus his camera lens and film formed an IR/UV phase-locked interferometer that detected and recorded the strike of the scalar EM missile underneath the shuttle, even though human eyes did not detect it.

At this point it would be interesting to know whether NASA may have had IR cameras focused on this shuttle launch (which was at night). If so, it would also be interesting to know whether any of them may have developed the IR/UV phaselocked interferometer effect, and captured the strike of the weapon.

Note that daylight shots would automatically break the IR/UV phase-lock possibility, by jamming out the effect with visible light, unless a special filter is used to filter out the visible light but leave both the IR and UV.

One would hope that both NASA and the U.S. Air Force will take note and discreetly add a specially filtered camera to the instrumentation observing and recording all future daylight launches.

To recapitulate the major events at the shuttle launch on Nov. 26., 1985, see figure 17. A marker beacon was placed in the vicinity, high over the area, for precise registration and location of tracks relative to it. A scalar EM missile strike may have occurred just prior to launch, and offset from the shuttle.

Then the shuttle lifted off. The exercise called for simulating multiple launches from a missile field. The area code was computed, and the fire order given. A substantial time delay -- say, 10 minutes or more -- was used to absolutely assure that the actual shuttle was well away from the engage blast.

Twelve minutes after launch, the delayed firing in an area "multiple missile kill" mode occurred, producing a massive boom heard for hundreds of miles up and down the east coast. After the boom, the marker beacon was slewed away, and photographed by George Suchary just as it moved.

The shuttle moved on downrange and went merrily on its way, blithely unaware of the jaws of the tiger that had snapped shut behind it.

To the Soviets, this final test of the preparation phase was highly successful. They were now ready to increase the risk level and fire the first round of World War III.

- THE SHOW BEGINS -

13. On Dec. 12, 1985 the same Soviet weapon tested against the previous NASA shuttle launches and against various aircraft may have deliberately interfered with the controls of an Arrow DC-8 taking off from Gander Air Force Base, Newfoundland. At an altitude of 100 feet, the aircraft -- carrying over 250 U.S. soldiers and civilian crew members -- lost power and sank into the ground tail-low, killing everyone on board. It was a tragedy of enormous proportions to the U.S., and especially to the families and friends of the brave servicemen and crewmembers who lost their lives.

Three Canadian witnesses to the crash were interviewed over the Canadian Broadcast network television news on April 8, 1986 at 10:00 p.m. No flame or smoke issued from the plane before its descent and crash.

However, witnesses reported seeing the aircraft mysteriously glowing with a yellow halo. That is a signature of the use of a scalar howitzer in the "continuous EM emergence" mode, similar to the manner in which several F-111's were downed in Vietnam.

In short, the DC-8's electrical systems were interfered with by electromagnetic energy and noise created throughout each increment of spacetime occupied by the aircraft. A powerful charge was rapidly created in and on the aircraft structures and skin. The "yellow glow" seen by the witnesses was a corona due to the skin of the aircraft acquiring a high electrical charge.

Something also apparently caused the rapid loss of two engines, one after the other. This indicates that the distant Soviet operator may have struck at the engines, one after the other, with a scalar "energy extractor beam." Thus he apparently tracked the aircraft as it moved down the runway, then used two modes against it: one to create serious EM interference with the electrical systems of the aircraft, and one to disable the engines.

With its controls ineffective and power drastically reduced, the doomed aircraft sank to earth, still in its "tail down" configuration from takeoff, and crashed and burned.

Admittedly other factors may also have contributed to the crash. These included reduced lift due to poor engine maintenance, increased weight of the aircraft due to icing, and heavy loading. However, normally the aircraft could still have taken off and flown to its destination. (See "Arrow Air was absolutely safe, FAA official says," UPI release, Birmingham Post-Herald, Apr. 17, 1986.)

To date, no official seems to nave recognized the sinister significance of the "yellow glow" or what it implies. No one seems to have connected the loss of this aircraft, the mysterious booms over U.S. shuttle launches, the Woodpecker interference grid, the anomalous loss of the U. S.S. Thresher, the high altitude "booms" off the east coast of the U.S. some years back, the puzzling loss of two critical Titan launch vehicles in a row, anomalous engine flameouts of civilian jetliners, etc.

Certainly officialdom has not recognized that a Soviet Launch Phase ABM System is being tested directly over its collective head, to include actual destruction of U.S. aircraft, missiles, and space vehicles with concomitant severe loss of American lives.

Direct and diabolical acts of war have been committed upon us by the Soviet Union, but in a fashion that still eludes our erstwhile pundits.

However, it is not as simple as that. To even energize giant scalar EM weapons is to run a risk -- to all mankind -- so horrendous that it boggles the imagination. Truly it deserves Brezhnev's 1975 phrase, "...more frightful than the mind of man has ever imagined."

Shortly we will reveal exactly what he meant.

- Apr. 18, 1986: Death of a Titan -

14. As this book goes to press, the last two U.S. Air Force Titan 34-D missiles fired from Vandenberg Air Force Base in California have blown up shortly after launch. The first one blew up on Aug. 28, 1985 just after lift-off. That loss has been attributed to failure of a high-powered fuel pump, causing a massive oxidizer leak and a smaller fuel leak. The second Titan loss occurred on April 18, 1986 when the Missile blew up 5 seconds after lift-off. Its loss is still under investigation and no determination of cause has been made. Apparently the shuttle and the Titan presently provide the only viable launch vehicles for launching U.S. "spy" satellites. The loss of these sensitive satellites -- if indeed they constituted the payloads -- cannot help but be damaging to our strategic surveillance capability. According to the Los Angeles Times, the single remaining KH-11 satellite was launched in December 1984 and, with an expected life of two to three years, it could stop functioning later this year.

Whether or not significant Woodpecker grid activity existed in the vicinity of the Titan launch of August 1985 is unknown at this time. However, significant activity in the grid definitely occurred before the April 18 Titan disaster and on the same day.

On Easter Sunday, 30, 1986 engineer Ron Cole observed significant cloud signatures of grid pattern activity, correlated with Soviet Woodpecker measurements. On April 18, the present author observed traces of a cloud radial over Huntsville, Alabama and took photographs of it. Preliminary reports from Thousand Oaks, California indicate extensive grid activity again on April 18, the day the second Titan exploded.

At least the second of these two missile destructions shortly after launch is highly suspicious, since the grid positively was active during that time. Also, a clear trail of Launch Phase ABM system indicators exists back to the massive scalar exercise of April/May 1985. The first Titan explosion in Aug. 1985 thus falls within the Soviets' "now let's test them against U.S. launch vehicles" period.

The second Titan loss follows highly suspicious losses of the Arrow DC-8 on Dec. 12, 1985 and the Challenger on Jan. 28, 1986. The same Soviet weapon system that destroyed those targets probably also destroyed one or both of the critical Titans.

At least, on the second Titan explosion, the Soviets left another signature. In one of the videotapes taken of the explosion, the marker beacon can be seen well , above the exploding debris, moving away from the explosion site.

See for yourself! Refer to "Titan Explosion Cripples U. S. Launch, Surveillance Capability," Aviation Week & Space Technology, 124(17), Apr. 28, 1986, p. 16-19. Specifically, look at the color photo of the explosion on p. 18.

Look well above the explosion (about one inch on the page) and to the left (about one inch on the page) of the center of the top of the fireball portion. There you will see a little light, caught in the very act of moving away.

At my rather frantic urging, engineer Ron Cole sought out a copy of the original videotape. He and a team spent two hours, going through this portion of the tape frame by frame. The light is there. It's real. And it moves on out of there, well above the explosion and independent of it.

It's the Soviet marker beacon, caught in the very act. Here I want to express my sincere appreciation to Ron Cole for his untiring efforts to nail this light down. Without his dedication to supporting this investigation, it would have been impossible to say for sure that the light was there.

So we have caught the bear red-handed, with his fingers in the cookie jar. If the marker beacon is there, you may rest assured that the Soviets destroyed that Titan missile, with very high probability. [See also "Investigators Search for Clues to Cause of Titan Blast," Aviation Week & Space Technology, 124(17), Apr. 28, 1986, p. 19-20; also "Titan Accident Prompts Funding, Technology and Policy Questions," AW&ST, 124(17), Apr. 28, 1986, p. 21.].

Continue



Figure 1. Wilson's first cloud radial



Figure 2. Wilson's second cloud pattern


JET AIRCRAFT

Figure 3. Wilson's third cloud radial

Figure 4.

PLACEMENT OF WILSON'S THREE RADIALS



Figure 5.

VIEW FROM WESTLAKE OVER VENTURA COUNTY, CA

1-24-86, 280• WEST/NORTH-WEST

11:45 AM PST


1
2
3
4
5
6
7
A
B
C
C
CLOUD RADIAL I.D.
9 LATERAL CROSS RADIALS WERE COUNTED IN GRID PATTERN.
280°
230°
330°
N
Ⓐ PINE MTN.
Ⓑ SULPHUR MTN.
Ⓒ THOUSAND OAKS HILLS

Figure 6.

GRID VECTOR APPROXIMATION

1-24-86 VENTURA COUNTY, CA


TOP VIEW
CITY OF VENTURA, CA.
[1]
[2]
[3]
[4]
[5]
[6]
[7]
[8]
[9]
7
6
5
4
3
2
1
0° N
270° W.
E 90°
S 180°
280° APROX. VIEW ANGLE FROM WEST LAKE
APROX. 28 MILES
[ ] CROSS RADIALS
◇ IN LINE RADIALS

The Tom Bearden Website

Fer de Lance

Figure 7.

SIX-MILE DROP IN TWO MINUTES

CHINA AIRLINES FLIGHT 006
- TAIPEI TO LOS ANGELES -
19 FEB 1985


41,000 FT
UPPER LEVEL
TROUGH;
TURBULENT
POCKET
1 ENGINE FAILS,
OTHERS REDUCE,
THEN FAIL
LANDING GEAR
DOWN, DOORS
TORN OFF
11,000 FT
ENGINE
RESTART
SAN
FRANCISCO
9,000 FT
RECOVERY

Return to Fer de Lance Index

Figure 8.

SAN DIEGO CHAFF INCIDENT, JAN. 1985


GRID
CHAFF CLOUD
RANDOM SCALAR INTER FEROMETRY
SAN DIEGO
SAN DIEGO INCIDENT
JANUARY 1985

Return to Fer de Lance Index



EM Missile Strike, Offset from Night Shuttle Launch

Cape Canaveral, Florida



EM MISSILE STRIKE
26 NOV 1985

(LIGHT DEVELOPMENT)

OFFSET FROM NIGHT SHUTTLE LAUNCH

PHOTO BY BOB GLADWIN



EM MISSILE STRIKE
26 NOV 1985

(DARK DEVELOPMENT)

OFFSET FROM NIGHT SHUTTLE LAUNCH



MARKER BEACON
Over Night Shuttle Launch
Cape Canaveral, Florida

26 Nov 1985
Photographed by George Suchary

© T.E. BEARDEN 1995



The Smoking Gun on 26 Nov. 1985

Longitudinal EM Wave Interferometry: Exothermic



Energy input to transmitter/receiver

Energy input to transmitter/receiver

XMTR/RCVR

XMTR/RCVR

Φ_T

Electrical ground potential of transmitter

Bias

subspace

subspace

Heating in interference zone

Φ_a

Ambient vacuum potential in distant interference zone

Meeting of longitudinal EM waves causes heating

ⓒ T.E. BEARDEN 1999

Longitudinal EM Wave Interferometry: Endothermic

Meeting of longitudinal EM waves causes cooling



COOLING IN INTERFERENCE ZONE

Ambient vacuum potential in distant interference zone

Φ_a

subspace

Bias

XMTR/RCVR

XMTR/RCVR

subspace

Heat extracted

Φ_T

Electrical ground potential of transmitter

Heat emerges at transmitter/receiver

Heat emerges at transmitter/receiver

ⓒ T.E. BEARDEN 1996

- More Frightening Than the Mind of Man Has Ever Imagined -

Brezhnev's unheeded 1975 characterization of these weapons as "more frightening than the mind of ran has ever imagined" has very real justification. In a moment we shall explain what he meant. We shall also explain why the Russians may be serious about substantial nuclear disarmament.

There is now a "balance of terror" loose in the world that makes the old MADmen's MAD concept look like a sunny day in Hawaii.

Let me explain just a little of what I mean.

The scalar EM can and does use an ordinary EM beam as a medium. Many, many scalar EM channels can be infolded into an ordinary carrier. Thus the amount of energy stored in the carrier as "electrogravitational" energy has little to do with the feeble amount of electromagnetic energy stored in the EM carrier signal.

Thus in one sense, when the Soviets are employing the big "continent buster" weapons, literally hundreds of millions -- or even billions -- of watts of energy may be infolded into the seemingly weak carrier beams. All this energy is in the scalar EM channels established in the carriers.

Plus which, the scalar beams are employed in a "standing wave" node. Each scalar standing wave is like a gigantic "capacitor": It is highly charged. Under normal conditions, it has a charge and discharge time constant as well. If something were to "short circuit" one of these huge standing waves -- say, one with a thousand megawatts in it -- all that stored electrogravitational charge would discharge through the short circuit into whatever is on the other end of the short, and into the ground itself. In other words, the earth itself in that location would receive a mighty electrogravitational pulse (EGP). The ground in a region surrounding the discharge point would "charge up" just like a capacitor, and would transmit the EGP as a hemispherical current into the earth and spreading around it. This is where the real problem cores in.

The problem, as originally discovered by Wilhelm Reich [orgone energy was and is real, and is simply one form of scalar electromagnetics], is that radioactive material has a very great affinity for this EGP and undergoes a drastic reaction to it. Crudely, it works like this:

Imagine the vacuum as a virtual particle gas. This gas is under extremely high "pressure" or, more correctly, internal Stress. This stress is a gravitational potential.

However, the stress of the ambient vacuum is normally about the same in most localities. So a chunk of radioactive material doesn't experience a difference in vacuum potential across itself or throughout itself. In other words, the scalar EM fluxes in and out of every part of the nucleus are very high, but of equal magnitudes. The radioactive nucleus, however, is "unbalanced"; that is, it has an extra bit of unresolved EG potential which it would very much like to get rid of or discharge, by spitting out one or more particles. That is, it would like to "decay" to a more stable configuration. A nucleus that is trying to decay to a more stable configuration is a radioactive nucleus.

Remember, the radioactive nucleus is involved in a tremendously dynamic virtual particle flux exchange with the vacuum potential. And a part of it isn't quite in balance in that flux. Sooner or later the right "bobble" in the input flux will come along, and the nucleus will decay and emit a particle and/or radiation. By measuring the level of decay activity in a certain amount of the radioactive material, we can determine a "decay constant," or basically the probability that a nucleus will decay in one second. We can then determine how long it will take that chunk of material to decay away to a stable, relatively inert material. Some materials only require a few minutes to decay, while others may require thousands of years.

Now if you suddenly and drastically change the stress of the vacuum in which a radioactive nucleus is imbedded, you change the potential placed on the unbalanced nucleus. You hit it, in other words, with a strong EG potential pulse -- an EGP. That instantly unbalances the nucleus and it decays explosively. That is, it changes the decay constant and the probability of decay.

Basically that's what happens in a nuclear implosion weapon: You hit the radioactive hunk of material in the center with a very high, imploding pressure wave, which is carrying an EGP. The EGP causes all the nuclei to decay nearly instantly, producing a nuclear explosion.

The bottom line is: strong EGPs wreak havoc if they happen to hit anything radioactive. Such as nuclear warheads, in missiles or in storage. Such as nuclear reactors. Etc.

Now do you begin to see the problem? Let me spell it out.

Suppose the Soviets have activated some of their giant scalar EM transmitters, to place a giant weather engineering grid over the U.S., or to knock down a Challenger or a Titan. They've got their scalar EM beams all charged up. One of the giant Woodpecker transmitters has -- let's say -- 500 megawatts in its infolded scalar EM standing waves. Everything is going good. They're socking it to the Americans and the Europeans.

All those multiple scalar EM frequencies they're using to form the patterns, etc. have to all be absolutely phaselocked. Therefore all the transmitters have to be rigorously phaselocked, too.

And suddenly something goes wrong. A major amplifier/transmitter controlling or stabilizing the phaselocking malfunctions. The phaselock is disturbed, and begins to quiver.

Emergency circuits react instantly, trying to stabilize the situation and restore the quivering phaselock. Little "shorts" are being applied to the circuitry and to the "giant capacitor" that is the scalar EM standing waves. Dumps and discharges of EM energy are beginning to flash in the transmitter and associated circuits -- and into the ground. These make the situation more unstable. Feverishly the emergency circuits struggle to contain this thing -- and Wham! they cave in, all at once.

Now you get a mighty and continuing discharge of the scalar EM energy in that standing wave back into the transmitter and into the ground. It burns out the transmitter. And the discharge continues as the "capacitor" drains all its EG energy into the earth in a giant pulse.

Around the transmitter site, the EGP is transmitted radially away, still very much like a standing scalar wave. It reaches the first nuclear facility. Let's suppose it's a nuclear reactor. Specifically, let's suppose it's a nuclear reactor at Chernobyl.

If you'll check Soviet Military Power, DoD, 1986 you'll find that there's a big ABM radar site not far from Chernobyl. And Canadian sources verify that one of the large Woodpecker transmitters seems to be sitting in that general location. Now check "The Soviet Nuclear Disaster," The Wall Street Journal, Apr. 30, 1986, p. 24. Check the small drawing in the lower right corner of the bigger drawing. Here you can see that a Woodpecker transmitter located near Chernobyl would ideally transmit nearly due west to intersect over the U.S., entering across North America from its east. Other Soviet "over-the-horizon (OTH) radar transmitters" go over the north polar regions, to enter the U.S. from the North. The two then form a giant interference grid over the U.S. (You can see that in Soviet Military Power.).

Suppose you were in the field in the U.S., measuring the Woodpecker signals. Suppose the stronger beam was coming from the east. You would be able to see this with your instruments.

Now suppose the giant transmitter near Chernobyl got into the type of failure we're talking about. The emergency circuits panic and cut down the EM carriers, trying to drain away the standing scalar waves in a controlled fashion. Then your instruments would suddenly record the "new" direction as coming from the north, since the east carrier is gone.

That's exactly what engineer Bill Bise detected out in California, about the time it appears the reactor at Chernobyl began to get in trouble.

Let's continue with our scenario. Suppose the emergency circuits at the discharging Chernobyl transmitter contain things for awhile. The standing scalar waves are steadily draining into the earth. The EG potential starts to rise at the Chernobyl nuclear power plant.

In the nuclear reactors, the decay constant of the uranium in the fuel rods changes. Additional radioactivity begins to pour out of the uranium. The reactor alarms go off, and the crew takes measures to reduce the problem. The control rods go further in, to slow it down.

But the EG charge keeps increasing. The radioactivity of the uranium continues to increase. The control rods go further in to counteract this. The electrical controls begin to act up, showing anomalous indications. The radioactivity increases. In panic, the controls are fought until the control rods go all the way in. The reactor should in fact now be shut down completely, in normal circumstances.

Things settle and hold a bit. The scalar EG charge increases. Finally the "shutdown" reactor starts to increase in radioactivity again. The control rods can't handle it. Everything is heating up, including the graphite moderator. Back at the transmitter, the emergency circuits finally are overwhelmed and give in. They fail all at once. The dreaded "uncontrolled short circuit" now exists between the collapsing standing wave and the earth. A gigantic discharge of EGP into the earth occurs at the transmitter site.

In the desperate reactor, suddenly a great EGP appears. Instantly the uranium goes intensely radioactive. A gigantic pressure of heat, steam, graphite and radioactive materials bursts out of the reactor, breaching the building and erupting violently into the atmosphere. The core melts down. The graphite moderator ignites. You've got the realization of the nuclear engineer's worst fears: core meltdown and reactor out of control. It's afire and spewing deadly radioactivity out by the gobs. And the heat! It's like hell itself opened up for business in this spot.

At any rate, something very similar to that seems to have happened at Chernobyl.

This author believes something similar happened in 1957 in the Southern Urals. (See Zhores A. Medvedev, Nuclear Disaster in the Urals, Translated by George Saunders, W. W. Norton & Co., 1979, p. 150.). In the Kyshtym area, an explosion of nuclear wastes stored underground occurred in the winter of 1957-58. The area for miles around was contaminated, and is still contaminated to this day.

Recall, Khrushchev spoke of a fantastic weapon in development in January 1960. Early prototypes of the weapon would have been in development and testing in 1957. Probably at that time there were no emergency control circuits to handle standing wave collapse, or only primitive circuits at best.

If the failure of a transmitter occurred in full-power experiments, the unrestrained collapse of the standing scalar EM wave would most certainly have produced a large EGP in the ground, and instantly activated the nuclear wastes stored nearby. Eyewitness accounts reportedly stated that the wastes exploded, and that is totally consistent with our thesis. It is in fact a scalar EM accident signature.

Any nuclear facility at all is an incredible and monstrous risk whenever scalar EM weapons are active.

Of course, one's nuclear facilities are at risk if one's enemy has scalar EM weapons and fires at them, as we covered earlier in this book.

However, they are at terrible risk even from one's own scalar EM weapons. The consequences ot a relatively simple electronic failure can be catastrophic; not only for the local nation, but for the earth as a whole.

To show what we mean:

Suppose a similar scalar EM accident -- such as seems possibly to have happened at Chernobyl -- occurs at some other giant Soviet "radar" facility. Further, suppose this particular transmitter is not too many tens of kilometers away from a Soviet missile silo complex. Just to really throw in the grit, suppose these missiles are the "big monsters" with--- say -- a 50 megaton warhead in each missile. Suppose there are 10 of them in the complex.

Let's say this accident occurs "catastrophically" -- that is, the emergency control circuits are overwhelmed immediately and a discharge of all the scalar energy begins at once.

A giant EGP strikes the earth, spreads in all directions, and strikes the waiting monster missiles. In their implosion trigger warheads and in their fissionable and fusionable payload, everything goes at once. Actually, it goes better than when normally triggered. So each one goes at about 100 megatons.

You've just had a monstrous 1,000 megatons of nuclear explosion in the earth. You get a giant earthquake. If it's not too far from the ocean, you get a tidal wave also. You get incredible amounts of lethal dirt and debris, radioactive and deadly, hurled violently into the air.

This is just about the equivalent of a "normal all-out nuclear war!"

And what about the other side's detection and early warning systems? Who's going to alert whom, and for what? How many missiles get launched?

I think you see the point.

And I haven't even covered what a giant EGP can do to humans. If it's truly a catastrophic failure, you can get an EGP that can wipe out half a mighty nation in one burst!

And if the discharge happens to tickle the Sun and Moon's feedback loops the wrong way, you'll get convulsions of the earth, mighty burps of the sun raining fire and brimstone on the earth, and a violent increase in the interior heat of the earth's molten core, with a concomitant eruption of that core right up though the mantle.

In other words, it could be "back to the beginning" for the earth, and start all over -- if, that is, some semblance of an earth survived.

The Soviets know full well the implications of their giant scalar EM weapons. (Remember, I estimate they have over a hundred of these monsters, based on Frank Golden's detection of their full-up exercise in April/May 1985.).

Scalar EM weapons have added a totally new dimension to the meaning of the word "terror". If one develops them and his adversary does not, nothing on earth can stand against them. So in Man's present state, the temptation to develop them is nearly irresistible.

On the other hand, if one's adversary already has developed them, one is already totally defeated unless one also develops them. Again, the need to develop them is imperative.

Yet, whenever one activates a large scalar EM weapon, one immediately places the entire earth in deadly peril. The slightest misstep, and it's curtains for everyone. And it's curtains for the earth as well.

So one is damned if one does, and damned if one does not.

We have reached the final turning point in human history. The clock is ticking away the last years -- or days -- of the lives of all humans on earth. There has never been such a threat.

We simply have come to the crossroads. somehow, all Mankind has to change.

Infatuated with the thirst for ultimate power, we are facing two doors. Behind one is a beautiful lady, and the fulfillment of all man's dreams: control of physical reality itself. Behind the other is the deadliest tiger ever dreamed of in our wildest nightmares.

Which is it to be, the lady or the tiger?

SCALAR EM INOCULATION AND ITS IMPLICATIONS

My appreciation goes to Gary North for his openly sharing the above important information with the public. Human nature being what it is, one or more of his more dire scenarios is going to happen sooner or later.

The problem becomes enormously more compounded if the hostile agent or agents possesses sophisticated scalar EM technology.

With scalar technology, there exists the potential that the worm or virus can be implanted from a distance. If scalar scanning devices of sufficient precision can be developed, then major software residing in a chip, a computer, or on a disk can be read from a distance. With scalar EM methods, the ordinary software "guards" are totally ineffective. The scalar "reader" could simply read off the software directly as the disk or device goes about its normal operations.

After the software is read, a germ or a virus is designed to produce a particular problem as desired and upon special stimulus. Then a scalar "imprinter" device is used to produce the necessary digital pulses directly upon the media in which the software resides. The required code has now been .implanted. In effect, the operating system has been injected from a distance, and contaminated with the desired "sleeping agent" -- germ or virus. From there on, it's just like Gary North's scenarios.

So the scalar EM technology can probably be used (at least eventually) to place "mines" in systems in advance, for damage or destruction at a future date. At least it's possible in principle.

However, it's not the injection of computers and equipment that bothers me. It's the injection of human beings. Here's generally how it can be done (and possibly is being done).

Basically, human brains have various rhythmic waves which represent "envelope pulsations" of the entire electrical system. However, it is not the EM force fields represented by these pulsations which are important: it is the summed-zero (scalar) patterning of the entire complex of neuron firings which represents the real activity of the brain -- and represents it thoughts and emotions. A storage system for these patternings exists, but it's a scalar pattern storage, not an E and B field storage. The storage system is in the nuclei of the tissues of the nervous system itself, not in electrical or electrochemical potentials.

At any rate, the human brain rhythms are also "riding along" relatively entrained to the Schumann resonance of the earth's magnetic field. So all the patterning of the brain is grouped together into giant overall orders, and one or more of these is normally synchronized to our natural environment.

If a varying magnetic signal of extremely low frequency -- say 10 hertz -- bombards the brain with greater power than the earth's magnetic field, it is possible for the brain's rhythm to be "forcibly entrained" to synchronize with that signal, rather than with the normal Schumann resonance. If a large number of brains are forcibly entrained to such a signal, and the signal is artificial, then a master coherent phasing of all the brains to the transmitted signal has been accomplished.

And that can be utilized -- and is utilized -- by the Soviet Union. On the Woodpecker signals, Bob Beck has detected up to 16 carriers, each with a 10 Hertz modulation, and with all the 10 Hz modulations in phase.

Let's stress what we're saying here. At times, the Woodpecker signals have shown 16 carrier frequencies which contain the same 10 Hertz modulation, and which are all kept coherently sync-locked.

If those signals and the modulations are strong enough, the brains in a targeted area demodulate the 10 Hertz signal and phase-lock to it -- actually, to them. At that point, the brains are entrained to a 10-Hertz driver, and 16 channels of multimegahertz frequencies are locked-in to the brain.

Now if the Soviets have broken the genetic code of the human brain (which they have) and succeeded in developing the ability to implant thoughts, emotions, pictures, etc. (which at least to a degree they have), then they can simply record the proper signals from human guinea pigs, using scalar technology and instrumentation. They can tailor those signals and add them onto the Woodpecker carriers, using scalar EM techniques. By using most of the sixteen carriers as a means to express Fourier frequency expansions, specific areas and functions of the brain can be targeted.

Notice that the distant transmitters al ready "know" the correct phasing; just use the 10 Hertz modulation signal as a reference. In that case, phasing takes care of itself inside the captured human brains.

The brain has a unique characteristic. If a signal arises inside it, it interprets that it itself originated the signal. Thus for the first time in history , true unwitting "robot" actions and emotions can be engendered in masses of human beings.

But it's still worse. The Kaznacheyev experiments (see references) proved conclusively that electromagnetic signals can carry and transmit cellular disease and death patterns into a targeted biosystem. You can rest assured that the Soviets continued on to actually measure and determine a wide variety of death and disease scalar patterns. All of that can be added on to the Woodpecker carriers so that the population in the intersection grid area is devastated. One can even test it out in advance by producing a modified pattern of a disease in the targeted populace, and keeping the percentage of brains entrained down to a small level. This lowers the number of persons "injected" from a distance to a small percentage of the populace. Then the outbreak of the "new strain" of a familiar disease -- such as influenza, pneumonias, and something like AIDS -- can be monitored to provide targeting and effectiveness data. Notice that a series of diseases was experienced by U.S. personnel assigned to the U.S. Embassy in Moscow, probably as a result of the so-called "weak microwave radiation" of the Embassy by the Soviet Union.

But that's not all. Much more subtle effects can be produced in the targeted populace, without anyone getting wise. Cancers and leukemias should be relatively easy to induce. Also, the immune system can simply be attacked directly. If done slowly, a series of common, ordinary diseases will just seem to get "tougher and tougher to cure." Actually it's not the disease that got tougher, it is the immune systems that got weaker. It is my opinion that precisely that sort of testing -- against the immune system -- has been accomplished by the Soviet Union against the U.S. since about October, 1985. A great percentage of influenza patients during the period from then until now have had complications. So much so that multiple sessions -- as many as 3 to 5 -- of antibiotics are necessary before the patient recovers. At least in the Huntsville, Alabama "hinge pin" area, that seems to have been the case. This author personally experienced this, having influenza and follow-on complications for a period of seven months -- something quite different indeed for him.

But it's even worse.

The human scalar EM nervous system ("inside" the ordinary EM signals and functioning of the system) also has its own resident "software." It has special storage media contained in its brain. its cells, and its genetic material, and its actual nucleons. All of these storage media are continually telecommunicated with via scalar EM means. The "stability" of what each of us is, is largely conditioned by those recordings. As personalities we literally "are" what we have experienced, felt, thought, and did. Our whole "functioning conscious system" has been evolved by our experience, and it continues to be "us" by means of continual reference to the record base.

I hope you now realize that the actual record base itself can conceivably be altered by scalar electromagnetic means, even from a distance. Even by the hidden scalar EM content of 16

Woodpecker carriers, locked into a captured brain and pouring in their deadly content. It is conceivable that even what one is can be taken from him, and what someone decides he will be, he will be.

A totally new -- and ultimate -- form of "slavery" has emerged.

Also, look at all this scalar EM functioning of the human system as a special kind of cybernetics. A scalar EM computing software and hardware system.

What if scalar techniques are used to plant "worms" and "viruses" in this system? With hidden triggers? What about a series of them, so that a range of "eruptive software diseases" can be stimulated at will?

And guess what. Such scalar EM "worms" and "viruses" can even be induced by contact with or consumption of "contaminated" water and food. Or saliva. Or other body fluid.

So you can see the possibilities of "seeding" a population with a staggering variety of time-bombs.

I think you begin to see the point. Now you can change North's "Soviet blackmail" scenario drastically. In a new scenario, Gorbachev simply announces to Reagan that a graduated series of specific sweeping changes are going to happen in our population -- changes which we are absolutely powerless to stop. The last stages are various deaths. The master "trigger" for this series has already been initiated. Incidentally, the Soviet populace has been carefully "seeded" with the proper antidotes. The Russian leader demands certain things (very similar to what North's scenario utilized). Unless his demands are met, a "killer virus" will be activated by a special signal. If so, everyone dies. The first step change in the series will start to occur in a few hours. And it does.

In fact, this scenario could be added to North's scenario, and both used simultaneously. What do you think the President and the Congress would do? Or could do?

There are other even more diabolical possibilities, but these should be quite sufficient to illustrate the point.

Pandora's box has already been spilled, and the end of humanity is ticking away like a time-bomb. It's already nearly midnight, and the watchman hasn't even sounded the alarm yet.

I certainly can anticipate the next question: Have the Soviets already "seeded" the populations of the U.S. and other selected western nations with scalar EM viruses and germs"?

The answer is, I simply don't know. And just like Gary North, I don't know what if anything can be done about it if they have. This researcher certainly doesn't have all the answers. An immediate national crash program to develop scalar EM defenses is essential if we are not simply to be crushed beneath the hammer and sickle. It takes funding, people, facilities, and time.

In some 22 years of unrelenting struggle to convince the system we've got a terrible problem, I've hardly been able to move it off dead-center (no pun intended). This book, produced under extreme workload stress, is all I can do to raise the alarm. I've given it my very best shot.

What happens now remains to be seen. Other hands, hearts and minds are going to have to take up the task and carry it forward. This researcher has reached his limit, and has no more left to give.

1986 APPENDIX II

COMPUTER WORMS AND VIRUSES, AND THE IMPACT OF SCALAR EM

Source: - Gary North, "Electronic Aids (Parts 1 and 2)," Remnant Review, 12(20), Nov. 1, 1985, p. 1-8; 12(20), Nov. 15, 1985, p. 1-8. POB 8204, Fort Worth, TX 76124. Phone (817) 595-2691.

Annotation: - Two deliberately un-copyrighted issues to alert the public to software worms and viruses, and their implications for drastic interruption of society. Describes a hypothetical scenario in which drastic scrambling and destruction of banks' computer tapes, files, and records occur due to software worms and viruses. Written in first person by Gary North. [Slightly edited.]

Article: - "Worms." Earlier this year, I read a very interesting article on a major problem facing computer software (programs) development companies. A program comes on one or more 5.25-inch plastic discs. It takes only a few seconds to copy a program on one disc to a blank disc, which costs $3. Yet these programs normally run at least $250, and usually sell at $495, and sometimes cost thousands. Very few are less than $100. So you have a major temptation: make a $500 asset out of a S3 asset. Insert the $500 program into drive A, write "COPY A:*.*.B:" and hit the "enter key;" sixty seconds later, you have a $500 program in drive B.

There are ways to make this copying more difficult. The companies code the programs, and force you to have a control disc in drive A at all times. These "copy protected" programs are a hassle for users. We cannot put them on "hard (big) disc" easily, and sometimes the control disc dies for some reason. Then what? Your data are locked in your hard disc or on a floppy disc, but you can't get to the data because the control disc is not functioning. You order a replacement. Weeks go by.

Last year, several firms came up with a solution. It is called a worm. A worm is a command that is built deep into the complex code that creates the program itself. These are incredibly complex codes, and it is easy to bury a command in them. They cannot be traced.

What does the worm do? It "eats" things. Say that you are a software thief. You make a copy of a non-copy-protected disc, either to use on a second computer, or to give (or sell) to a friend. The program works just fine. But when the program is copied to a new disc, the worm is "awakened." It bides its time, maybe for many months, maybe for years. The program's user is blissfully unaware that a monster lurks inside his pirated program. He continues to enter data, make correlations, etc. He becomes completely dependent on the program.

Then, without warning, the worm strikes. Whole sections of the data disappear. Maybe the data storage disc is erased. Maybe it is just scrambled. Even his backup data discs have worms in them. Everything he entered on those discs is gone. Forever.

Can you imagine the consternation of the user? He has become dependent on a booby-trapped program. His business could simply disappear. For the savings of $500 (stolen program), he could lose everything he has.

Several firms threatened to insert worms into their programs. But then they backed off. They are afraid that lawsuits initiated against them might go against them in court. They could be hit for damages suffered by the thieving victims. Juries might decide that the punishment, a bankruptcy) was too much for the crime (a $500 theft).

So far, no worms are lurking in any commercial software programs — as far as I know and the industry knows, anyway. But what if a disgruntled programmer was to hide one in a master copy of, say, Lotus 1-2-3, the most popular business program on the market? What if ten thousand copies a month go out for, say, three years? Then, without warning, every company that has started using them loses three years of data? They sue Lotus. Lotus goes bankrupt paying lawyers. No company in the industry is willing to talk about this sabotage threat publicly. Obviously.

LARCENISTS

I just happened to stumble across an article on worms in a computer magazine. It occurred to me that it might be possible to use the worm technique as a form of deliberate sabotage rather than just as a copy protection device. But what did I know? I'm not a computer expert.

I know a computer expert, however. I mean, a real expert — one of those people you occasionally read about. In the world of business, they're called "space cadets." They operate somewhere in between the asteroid belt and Jupiter. But this one is different. He's a businessman, too.

I got him to sit down with me to discuss the problem of worms. It turned out that he has a real fascination for the topic. He tells me that there are advanced design worms, called 'viruses' by 'hackers' — computer freak programming geniuses. "The software virus is the most terrifying thing I've ever come across," he told me. And then he showed me why. My initial scenario is based on only a portion of his estimation of the threat. It gets a lot worse.

He gave me a 90-minute FIRESTORM CHAT interview. He must remain anonymous. He used to be a software developer for programs that were used in the U.S. banking system, but is now employed in a highly sensitive job in a related industry. Therein lies his problem. If he were to tell the story of what he is capable of doing to these banks, his firm might lose a lot of sales. He can't "go public." Let's call him Tom.

Let me summarize briefly some of the details he gave to me. They floored me. They're going to floor you.

(1) Jackpotting. The rush is on in the banking world to get automated teller machines (ATM's) into shopping malls, supermarkets, and in front of every bank. We've all seen them. Just walk up, punch in your card number, ask for cash, and you get it.

In a busy location, one of these machines can hold as much as $250,000 in cash, mostly small bills. These machines are controlled by computer. They are hooked up to the bank's computer system, usually by phone lines. This local line, Tom tells me, is what computer freaks call THE LOOP. The loop is wide open to tampering. He says that what computer thieves are doing is to hook up a cheap Apple II computer, tie into the phone lines, break into the ATM, and get it to empty itself. This is "jackpotting."

He tells me that ATM thieves are hitting banks continually, but nothing is getting to the press. The banks have yet to show a profit with the ATM's so far, which is understandable. They are hoping to get their machines placed in key locations, so "market share" is crucial to their plans. They are suffering horrendous losses in the short run in the hope that long-run profits will pay off, if and when a defense is developed.

The banks are saying nothing because of their fear that if the extent of the losses gets into the press, they will be forced by pressure from depositors — bank runs — to cancel the ATM's. The losses are horrendous, he says. At present, there is no known defense, given the communications technology.

(2) Rounding Off. This is the "preferred" computer bank theft system. Someone on the inside who has access to the software takes advantage of the banks' need to round off numbers. The programs carry numbers out to 13 places. Banks can't use all that space. So when they balance the books (interest rates at, say, 9.873), they just don't count every tenth of a cent. The program is assumed to round off the numbers randomly. What does the bank care? But the thief has set up bank accounts that absorb those random tenths or hundredths of a cent. In millions of dollars worth of transactions (federal funds, etc.), programmers in some cases have stashed away hundreds of thousands of dollars — maybe millions — over a few years. No one knows how much of this goes on.

How could a bank spot this? The books would always balance to the penny. How would the accountants ever know?

I think of a story that Adam Osborne tells in his paperback book, Running Wild. The president of a large firm was looking out his window one day, and he noticed two Rolls Royce cars parked next to each other. He inquired as to the owners. They were two men in the data processing department. He called in investigators, and the cars and the men disappeared. They fled to Brazil and took their cars with them; **Brazil** has no extradition treaty with the U.S. Years later, as

Osborne was writing the story, the firm still hadn't figured out what they had done.

ARSONISTS

These are the fearful ones, far more than the larcenists. These are the practical jokers who get into a major data bank and trash things. It's a kind of multimillion-dollar "Kilroy was here" graffitti.

How easy is it to get in? Incredibly easy. The boy in "War Games" really could have broken into most firms' telephone-connected computers. Computer programs exist that allow the user to hook up his computer to a phone line and randomly dial numbers until they hear the telltale whine of a computer line. It then notes the phone number and goes on its way, searching out more lines.

They can do it by long distance, free of charge. The telephone company has a tough time tracing those who use various sorts of electronic black boxes to call anywhere on earth at no charge. Some people get caught, of course. "The tip of the iceberg," says Tom.

How do they get in? Easy: few systems are protected, once you locate the line. If one is, he says, you create a deliberate error. Most programs then collapse the protective shell, and the hacker finds himself inside the heart of the system. Tom has designed a program that keeps this from happening to his company's programs, but few companies have anything like it.

It's very easy to get in if someone has "logged on," — opened his terminal's connection to the main computer — if the system is connected to phone lines. Or anyone in the company can just tap in, if someone has left his desk and left the computer on. It's common to forget and leave an open terminal.

He showed me. He says anyone can get fired for leaving a computer on. He demonstrated his point. With 40 computers on line, he ran a quick search and found two of them "logged on," despite the fact that it was after hours. All the security in the world can't do anything if a computer line is open. It's like a burglar alarm; it's worthless if you leave the door unlocked or leave the keys lying around. That janitor you hired. Is he a computer illiterate? Or a plant?

Once inside, what can you do? Steal a fortune? Yes, if you really know the system. He told me he could easily steal $3 million from a local bank, even as an outsider. He would then offer to give it back and keep his mouth shut about how easy it was if the bank would pay him 10% the take. He thinks most banks would capitulate for fear of the publicity. In any case, he knows that he probably wouldn't get caught.

How about creating a new identity? The grade-changing scene in "War Games" is true. You could even create a new identity, give yourself high grades in any academic discipline, just by breaking into a university's database. There is very little security here, he says.

But for sheer vindictiveness, for sheer envy, consider the possibilities of a virus-implanter. He gets inside the computer for a major communications link: telephones, large information database, bank wire transfer, or whatever. Then he lays the egg: a tiny, untraceable brief instruction. Inside a huge database are just a few characters. These float inside a system, seeking to devour certain kinds of data, or executing certain routines.

There is a game played by computer freaks called "Core War." They try to implant these killer messages, which seek out each other and battle one another. If you find one morning that yours has been consumed, you lost the battle. That was probably the origin of worms and viruses.

TERRORISM

Say that a revolutionary terrorist group, or some anti-zionist group gets a "ringer" into a system. He might be a computer genius type. Everyone knows they are either oriental, dark-skinned people with accents, or teenagers. The firms don't hire teenagers, but they hire a lot of foreigners. They may even check the guy's credentials. Electronic credentials. (Ha!) Then they turn the guy loose in the system.

The virus is implanted deep inside the system. It can then be transferred to any other bank's computer by means of EFT (electronic funds transfer). Maybe it is triggered when someone with a peculiar name and address opens a bank account. Three days later: Bam! The data disappear. They haul out the back-up tapes. Bam! The virus is on them, too. It is a process of infection, contamination, and incubation. There is no known defense. Not yet. This is the bottom line.

ANTIBODIES

The designer of a virus can also design an "antibody." The antibody is a counter-virus agent that seeks out a virus and destroys it. But like other antibodies, it must be specific. The only way today that an antibody system can be created is to know what kind of a virus is involved beforehand.

Tom says that people are now selling antibodies at very high prices. Who is paying? Big companies that suspect that there is a virus present in their computers. In all probability, the guy selling the antibody created and injected the virus. But now can any businessman prove it? So he pays the blackmail.

NATIONAL DEFENSE

A Soviet agent or American spy working for the Soviets penetrates any of a dozen computers used by the military. He plants a virus. The computers talk to each other, and the virus spreads to all of them. It tells them to execute a certain routine when a certain command is entered at a missile-controlling terminal. That command might interfere with a routine that activates a missile or launches it. Upon reading that command, the virus shuts down the computer, or scrambles the executing program, or scrambles the data. No more "launch on warning." No more launch at all. Dead metal.

Scenario: The President of the United States receives a telephone call on the "red phone" — the direct link to Moscow. He lifts the receiver and says, "Hello."

"Mr. President, this is Michael Gorbachev. You must recognize my voice. I have very little time. I will come directly to the point. You have refused to back down on your threat to implement your Strategic Defense Initiative. You intend to go ahead with space-based weapons. My military staff informs me that they think that the United States has the technology to implement it, and that it could place my nation's military strategy in jeopardy. We cannot allow you to do this.

"If we allow you to deploy the SDI, it will be too late for us to respond effectively. Therefore, we are taking the initiative today. I issued orders this morning to put Soviet military units on immediate alert. We are abiding by your biblical rule to announce the initiation of hostilities before striking. Neither the Japanese nor the Germans gave us this courtesy. If you do not come to terms with us, we will launch a first strike against your nation in three hours. We will delay for one day, if you agree to follow a precise procedure that I will outline shortly.

"At one time we feared nuclear retaliation. We no longer do. Within two hours, you will know why not. I suggest that you instruct your ballistic missile team to prepare your missiles for a strike. Then, to prove to yourself that we no longer are concerned about retaliation, launch one or two of them. As far as I am concerned, launch all of them. But please instruct your senior military commanders to report back to you concerning the effects of their instruction. I suggest that you try launching three or four as a test. We don't care which ones.

"Mr. President, let me tell you what is going to happen. As soon as anyone attempts to launch a missile, that missile's computer guidance system will shut down. It will lock up tight, and you will not be able to unlock it within the time you need to respond to our attack. Two hours and thirty minutes from now, your nation will have no remaining Minuteman III missiles to respond with, should you finally unlock your frozen computers.

"I suggest that you contact your senior officers now. You will have to mobilize them within 60 minutes. The test should take about 30 minutes. I will telephone you again in 90 minutes to present our terms of surrender." Click.

The President calls the Joint Chiefs. If he is lucky, he will be able to locate two of the three in time. They will be paralyzed. Who wouldn't be? But in all likelihood, they will at least test Gorbachev's theory. They will order one or (wo missiles launched. The computer guidance system on both will shut down the system. They will try two or three more, with the same result. They will attempt to launch one from a submarine, with the same result.

The President brings in senior Congressional officials and the remaining Joint Chiefs member to the White House.

Exactly 90 minutes after he had hung up, Gorbachev telephones back. He presents his list of demands. First, the immediate removal of U.S. troops from Europe. Second, the withdrawal of personnel from Diego Garcia Island in the Indian Ocean. Third, the breaking of diplomatic relations with Red China and Taiwan. Fourth, the removal of all U.S. troops from Korea. Fifth, a moratorium on all debts owed to U.S. banks by the Soviet Union and its client states. Sixth, the removal of all Minuteman III missiles from their silos. Seventh, the return of all U.S. submarines to port. If he agrees, and the orders are delivered within two hours, the Soviet Union will delay launching a first strike. The President complies.

They might do it with our communications satellites, Tom says. You might do it with any aspect of U.S. data transmission. The virus could sit dormant in a system for years, and no one would know. Triggered, it would then strike.

THE WEST'S VULNERABILITY

The West has become increasingly dependent on computers. We can no longer function without them. The Third world hasn't. Neither has the U.S.S.R. Their technology is still pre-computer. They are inefficient, but they are far less vulnerable.

Tom says that the world of computers presumes that almost everyone is essentially honest, and that all the brightest programmers must be honest. They aren't. Thus, the members of the entire system — banks, national defense, large and small businesses, public utilities — have opened themselves to attack. The attackers are invisible.

"Nothing I have seen in all my years of computers scares me as much as this does," he says. "The system has been designed in terms of a far older set of standards, especially with respect to security. It is totally vulnerable."

He compares it to plague, or venereal disease. People copy each other's software to save a few bucks. They use public access databases. They use "loops" — the phone lines. Yet these transmission belts of information can become transmission belts of collapse.

This is what I have harped on for twenty years: the potential for a collapse of the division of labor. We become rich by means of a brilliant technology, yet we become dependent on it to an extent that no previous society ever has.

Centralized institutions are most vulnerable, but because we use public transmission lines, from microwave transmissions to cables in the ground, each local unit is vulnerable. Those who would choose to bring down the system need only plant electronic viruses in a handful of major common-use databases or transmission sources, and live years or ten years later, the disease hits.

It could bring down the system if technological defenses are not developed. Nothing on the immediate horizon points to a solution, he says. The silence of those who should know what to do indicates that they don't know what to do, but they don't want panic to spread.

Is this fantasy? Last summer a 23-person team broke in (by phone) to Chase Manhattan Bank's computer.

Break-in: - Continuation of part 1, a treatise on worms and viruses in cybernetic systems.

"Maybe you saw the article buried somewhere in your newspaper. I saw it in the New York Times (Oct. 19):

> "A group of at least 23 teen-age computer users broke into a Chase Manhattan Bank computer installation by telephone in July and August and "significantly damaged" bank records, the Federal Bureau of Investigation said yesterday.
>
> Chase officials insisted that no money was stolen or transferred out of customer accounts as a result of the break-ins, and said no intrusions have been detected recently. But Federal officials, in an affidavit, said that in several cases the youths changed passwords, preventing customers — and in one case a unit of the bank itself — from gaining access to their own computer files."

And where were these teen-agers located? In San Diego, across the continent! It gets even more ludicrous:

Federal officials said that most of the offenders were probably too young to be prosecuted.

Robert D. Rose, the assistant United States Attorney handling the case, said: "We're not yet sure what we are going to do. But these things can get out of hand — it did get out of hand — and we have to treat them seriously."

Treat what seriously! "These things?" What things? If they can't legally treat the electronic trespassers seriously, just what is the man talking about? He is talking about the topic, above all topics, that bank and government officials don't want to face: the vulnerability of their computer records.

I have seen no follow-up on this story in the conventional press. A brief article did appear in the computer-oriented tabloid, Info World (Oct. 28). It turns out that the students had broken into the fifes of Interactive Data Corp. of Waltham, Massachusetts, which maintains the bank's financial records. The break-ins were discovered in late July. They had obtained the toll-free 800 number which was restricted (Ha!) to Interactive Data subscribers. As late as October 9, an illegal entry was observed. In short, it took ten weeks after the break-ins were discovered to put a stop to them.

The response of the bank's bureaucracy was predictable. It will ever be thus: "Bank officials are claiming that the FBI exaggerated the nature of the activities of the suspected individuals. A spokesperson for Chase Manhattan said that Interactive's customers were not prevented from accessing their accounts and that none of Interactive's data was altered or manipulated in any way." In response, FBI supervisory agent John Kelso said that the FBI has sworn affidavits from bank officials that say data has been manipulated or damaged. "That sounds pretty serious to me," he volunteered.

Here is the capper: Interactive Data has 25,000 subscribers who are tied into that toll-free phone line. Try keeping tight security on a system with 25,000 users. Chase Manhattan couldn't. If they can't, who can?

And if Chase Manhattan Bank was vulnerable to 23 teenagers who are too young to prosecute, consider its vulnerability to just one envy driven genius who knows all about electronic viruses. The students that did this were apparently just goofing around. But what if just one malevolent computer freak decided to "get even" with Chase Manhattan? What if he had phoned in just once or twice, implanted a long-dormant data-killing virus, and quit? What if he had tied its detonation to, say, a calendar clock in the Interactive computer? If it took security forces from July until early October 15 to raid the 23 students' homes, they would never have spotted one break-in. They could not have traced it, either. Conclusion: we have a risk-free opportunity for electronic arson. We face a potential electronic epidemic. And when I say "we" I mean the entire financial system of the West.

Sure, all the bank "spokespersons" in the world will tell you, "No problem." But there is a problem. A horrendous problem.

At this point, it really gets interesting. Chase Manhattan Bank has just announced that we will be able to set up our own personal electronic banking facilities with them by buying an expanded version of *Managing Your Money*, Andrew Tobias' home financial management.

Citicorp and Bank of America have opted for *Dollars and Sense* a rival program. You will be able to pay monthly bills electronically, balance your "checkbook," monitor your net worth, buy and sell stocks, etc., etc., just by dialing Citicorp or Chase Manhattan. Fantastic! But despite all the assurances, I get nervous. Yes, I know no one will be able to break in and tamper with the numbers. But 23 teenagers shouldn't have been able to do it, either. And now we're talking about a lot more subscribers than 25,000.

Obviously, the master program used by the banks will prohibit easy entry. Unfortunately, someone has to write the program. Can you imagine the blackmail possibilities? Some hotshot programmer could build-in a bomb, and then threaten to detonate it. In fact, he could merely pretend to have inserted a virus. Who would want to call his bluff? Not Chase Manhattan, I would bet.

CORE WARS REVISITED

In May of 1984, A. K. Dewdney published an article in Scientific American's "Computer Recreations" column. It was a light-hearted-piece on how computer experts can get involved in playing this exciting game of "blow up your opponent's defenses." You know: recreation! In the March 1985 issue, he wrote a follow-up. It begins:

"When the column about Core War appeared last may, it had not occurred to me how serious a topic I was raising. My descriptions of machine-language programs, moving about in memory and trying to destroy each other, struck a resonant chord. According to many readers, whose stories I shall tell, there are abundant examples of worms, viruses and other software creatures living in every conceivable computing environment. *Some of the possibilities are so horrifying that I hesitate to set them down at all.*"(emphasis added.)

It turns out that tne French nave been enjoying a novel on the international implications, *Softwar: La Guerre Douce,* by Breton and Beneich. A translation is scheduled for publication here by Holt, Rinehart & Winston. The study revolves around the sale of a high-power computer to the Soviet Union. The U.S. allows its export because it has a "software bomb" in it. When the U.S. Weather Service announces a certain temperature at St. Thomas in the Yirgin Islands, the program proceeds to subvert every piece of software in the Soviet Union.

A pair of Italian programmers was "inspired" by the translation of Dewdney's original article to dream up a virus (a virus is a computer-to-computer killer, whereas a worm is resident in one man's computer). They figured out that by infecting a disk operating system disk (these start computers and tell them what to do with programs and electronics), and then installing it on disks used by the biggest computer shop in the city, they could create an epidemic. They decided not to do it. In short, the only restraint is self-restraint.

A high school student in Pittsburg wrote a virus that was subtler than a data-destroying virus, which at least tells us that we have a problem. His virus created a plague of very subtle errors in the disk operating system. "All of this seems pretty juvenile," he wrote, but "Oh woe to me! I have never been able to get rid of my electronic plague. It infested all of my disks, and all of my friends' disks." He wrote a program to destroy the virus (an "antidote" to it) but it is not anywhere near as effective as the virus is.

Warning: do not copy disks from your friends' copies. This act of piracy could cost you plenty.

A COMMERCIAL WORM

Just a few days after I wrote "Electronic AIDS, Part 1," 1 read a column in the Washington Times, the conservative (Moonie-owned) daily newspaper. One of the reporters has a computer. He had purchased a newly released program from

Microsoft Co., called "Access." Understand that Microsoft supplies the disk operating system that is used by the IBM PC, the most popular microcomputer. In other words, this is no backyard company. It is one of the two or three software giants in the U.S. (Its owner is under age 30, which tells you something about who is pioneering the microcomputer revolution).

As he was setting up his computer to take advantage of this telecommunications program, a warning flashed on his screen: "The weed of crime bears bitter fruit. Now trashing your program disk." Wham! He lost all his files — probably a couple of year's worth of work. Sure, he was probably smart enough to have made back-up copies, but think of the risk. And what if it had been a worm that kept silent for a few years, infecting all of his back-up disks?

He called Microsoft, and they gave him the runaround. They told him that they were not responsible. Some programmer had put in the worm in order to zap program pirates, but the journalist insisted that he was an original buyer. Tough luck, they told him. Obviously, they didn't know that he was a reporter.

Then he published his article. All of a sudden, the victim was not some average buyer. He was big trouble. Things started moving. InfoWorld (Oct. 28) reports that Microsoft has admitted that a programmer put in the worm, but without permission. The offending text has now been removed, we are assured. But what if it had sat in the master for three years? Here is the premier firm in the software.

This is not idle speculation. It has already happened, verifying my hypothetical scenario within a few days after I published it.

Can you imagine the absolute havoc that a dormant worm or virus could create if it were imbedded in all updates of Microsoft's masters of PC DOS and MS DOS, the operating systems for all IBM microcomputers and IBM-compatible microcomputers? It could cost the U.S. economy billions, and some microcomputer-dependent firms wouldn't survive. Any Microsoft spokesman who says, "It's impossible; it could never happen," has to explain how it already did happen to "Access."

ADAM OSBORNE'S WARNING

You may know the name Adam Osborne. He invented the revolutionary portable computer, the Osborne 1. Before there was an Osborne 2, the company went bankrupt. Compaq, the most successful first-year firm in U.S. history (over $100 million in sales in its 12 months of operations) and others built imitations that were far superior.

That isn't my point, however. Adam Osborne was "present at the creation" of the microcomputer industry. He created Osborne publications, and then sold out to McGraw Hill. He knows what is going on. In his delightful paperback book, Running Wild, which is a history of the microcomputer (desk top) revolution, 1975-82, he offers this warning. He says that three areas should not be allowed to be computerized: 1) bank money transfers; 2) the stock market; 3) elections.

All three are just about fully computerized. Another ten years, or maybe five, and they will be 100% computerized. Several firms allow microcomputer buying and selling of stocks (e.g., Charles Schwab), and New York Stock Exchange floor transactions eventually will be fully computerized, at which time it will be pressured to get rid of the "specialists" who make (and sometimes manipulate) the market, short-term — Richard Ney's hated "Wall Street Gang" — but the price of getting rid of them may turn out to be horrendously high.

"The great fortunes of the 21st century," Osborne predicts, "will be the legacies of the great computer thieves of the 20th."

Three years ago, I used a firm to supply computer services I needed. The head of it was a former businessman, quite young, and a true "space cadet." I've quoted him in the last issue. I call him Tom. He operated in a world far removed mentally from the rest of us. He is a nice fellow, a Christian, and a moral philosopher of sorts.

He ran the operations of the local elections. He did it fairly inexpensively. He told me why: "I want to keep these elections honest. It would be incredibly simple to rig the program to produce whatever outcome I wanted in close races. If I can do it, anyone with enough skill to set up the system could do it."

I asked him if he thought Osborne was correct in his predictions about bank theft. "It would be a piece of cake for me to steal three or four million from any local bank. I could go in the next week, offer to give the money back, keep 10% as a finder's fee, and promise not to tell the press how easy it was to steal. They would probably pay me my 10% just to keep me quiet."

Look, These people are geniuses. Worse, they are geniuses in a very narrow field technically, which is now being used to control darned near everything. This unique intellectual-technical skill is the possession of literally a handful of people, mostly under 35 years of age. They are "fooling around" with Chase Manhattan Bank's computers. What happens when a few of them stop fooling around and get deadly serious?

Computer program designers keep telling us that there is no 100% secure way to defend data banks. Maybe there will be a 98% secure system someday, but not now. To defend itself, the system relies on the integrity of youth. In short, self-government is the major defense.

And where have they learned self-discipline? In the public schools?

"NOW YOU'VE DONE IT!"

About four years ago, I read an article in the *Rolling Stone,* the tabloid aimed at rock music fans. It was the only article I ever read in that periodical. It was a gem.

It described a subculture of students at Stanford University, "hackers." These people are computer freaks. The mainframe computer at Stanford was cheaper to use after midnight, so from midnight to 6 a.m., the hackers gathered at their terminals. They lived on candy bars, junk food, and high-technology dreams.

One of the games they played was breaking into each other's programs. It was considered the mark of a master hacker to be able to crack another hacker's defenses. They would spend hours trying. They were "hacker-crackers."

One bright fellow then designed a classic booby trap. He wrote a program that warned trespassers not to tamper with it. This, of course, alerted every would-be electronic safe cracker to the challenge. It was a complex program, and it took days to crack it. Then, after repeated warnings, the successful trespasser got a surprise. Japanese letters appeared on his screen. Roughly translated, the words proclaimed, "Now you've done it!"

At that point, the victim's computer screen went blank. Then the names of all his own computer files appeared on the screen — files that may have taken years to assemble. One by one, they blipped off the screen. In horror, the victim would stare at the screen, unable to stop the process.

As it turned out, the booby trap was only a practical joke. It really didn't erase all the victim's files. It only listed the names, and then erased them. But for a horrifying few minutes, the victim wouldn't know this.

Hackers play games. Very interesting games.

The kind of people who spend six hours, midnight to 6 a.m., trying to break into each other's programs are different from the rest of us. Among their ranks are some highly individualistic people. Some of them are libertarians. I mean anarchists. They are electronic "don't tread on me" sorts of people. They do not appreciate bureaucracy. They appreciate being pushed around even less.

The folks at Chase Manhattan really do have a problem. Do you attempt to prosecute a legally un-prosecutable kid? A kid who has already cracked your computer system? I don't think you do. You play the role of stern but appreciative banker. "Son, I am impressed by your ability to break in. But understand, we are honest people. There is a code of honor here. You wouldn't want to break that code — of honor, I mean — would you?" Because if this kid gets angry, he can do it again. Quietly. And next time, he deposits a virus.

Of course, Chase may hire a programming team to create an unbreakable system. Sure. "Hire fox A. Give him chain link fence B. Hire him to build fence B around chicken coop C."

TEEN CHALLENGE

Suppose that the public gets wind of the threat to the whole banking system that is posed by viruses. What do the bankers (or anyone else) announce to the public? "We want to assure you that our computer program is impenetrable. No one can break in. It is foolproof."

Here is the challenge — rather like the Stanford program that announced: "Do not trespass." These kids see breaking-in as a challenge, a kind of sport. They do not regard it as theft. They do not regard it as vandalism, even if it costs a company millions of dollars to unscramble. They may be ethical in other respects, but they think of "core wars" as a game.

How would you like to be the 60-year-old banker who doesn't know a byte from usury, but whose public relations department tells him to inform the public that nobody can crack his bank's code? To cite Mr. T in "Rocky III," that bank is dead meat. So are its depositors.

But if he keeps quiet, and the story still gets out about the vulnerability of the system, one or two small "virus-demolished" banks could trigger a collapse of the system, as people do the only smart thing: run for cash. The whole fractional reserve banking system would deflate; only the FED's printing presses could "save the day," in a wave of fiat money.

What I am saying is this: I think that we will see the end of fractional reserve banking in our day. At the very least, I think we will see it subjected to tremendous shocks. People will lose faith in electronic promises made by bureaucrats who do not know anything about the monsters that their efficient computers can be turned into.

Attack on Martinsburg. Now, let's take it a step farther. Some day some state or Federal bureaucrat is going to step on the toes of some genius entrepreneur who has created a software development firm. The bureaucrat will try to wrap this entrepreneur in red tape. Or maybe — just maybe — he will try to sock him with a tax bill that the entrepreneur regards as unfair.

In Martinsburg, West Virginia, there is a large computer. It is owned and operated by the Internal Revenue Service. Into it, over the next five years, the I.R.S. apparently intends to deposit all the records it can assemble on every U.S. taxpayer. This computer database will be the biggest in the world. It is the tool by which the I.R.S. hopes to increase taxpayer compliance. And it may succeed. For a while.

This is one reason for saving all letters to and from the I.R.S. If the I.R.S. becomes dependent on its computer system, which is likely, then any short-circuiting of its database could create havoc for tax collecting. If word gets out that a major failure has hit the I.R.S., the tax revolt could multiply overnight. You would see the deficit become astronomical. If the I.R.S. continues to tie its "voluntary" compliance program to the myth of the "all-seeing computer," then news of the computer's scrambling could backfire.

It is possible that the story of the I.R.S. database is a myth. Maybe they aren't going to build it. But if the public believes that such computer power is at the disposal of the I.R.S., and taxpayers then learn either that the system has been blown, or that it was mythical from the start, the tax revolt could spread like an epidemic. The electronic epidemic-could trigger a tax revolt epidemic.

He who lives on the cutting edge of technology eventually dies on the cutting edge of technology.

"PEOPLE ARE BASICALLY GOOD"

Let's return to my taped interview with "Tom." In a 90-minute interview, we covered a lot of ground. But one topic that stands out in my mind is our discussion of the pre-supposition that goes into the creation of a computer-based society. The computer people have all adopted the assumption that undergirds modern science, namely that, participants are well meaning, that they will not fake their experiments, and that they will play fair. If scientists had to check every aspect of every article, science could not advance very fast.

What about the computer industry? The whole system rests on faith: "Men are not malevolent. They are not envy-driven. They will not deliberately seek to destroy the work of some random victim." Tom says categorically that this assumption is false. There are bad people with tremendous computer skills, and modern society has not restructured its economic institutions to protect itself.

Here is one example of a break-in technique. Someone phones in to a computer, which has been left open temporarily by some user. The lock is unlatched; he needs no key to get in. He then seeks to penetrate the inner core of the program, such as a bank's program. He creates a deliberate error, which all too often triggers a kind of electronic explosion. The protective shell self-destructs, and the invader now finds himself inside the system, where far fewer defense mechanisms exist.

Tom designed his own firm's defense against this tactic. His program automatically records the source of the error, and throws the user out of the program. The program has protection against deliberate errors, but most of them don't, he says. A major error simply collapses the program's outer shell.

In my previous issue, I speculated that a Soviet spy or agent could penetrate U.S. computers. Note: I did not assume that he would simply phone in; I assumed that a disloyal programmer, or a team, could plant the virus as insiders. From there, the virus would spread through the system through normal telecommunications. Several people have written in to tell me that a wrecker cannot destroy the system by penetrating it from the outside. They may be correct. But when informed that I am assuming an inside job by someone with access to a major computer, the critics have admitted that this might be possible.

The weed of crime bears bitter fruit: for honest, computer-dependent people.

FEDERAL FUNDS

The Federal Funds bank transfer lines allow banks to borrow money overnight. Hundreds of billions of dollars go across these lines every working day. The bank's computers communicate with each other by means of this telecommunications hook-up. What if someone were to plant a long-delay virus in the software that operates these transfers? And what banker has even thought about this problem?

What if this scenario was to take place: a virus triggers the disruption of bank records — not a total breakdown initially, but disruptions in the data? It might be weeks or months before auditors recognized the extent of the problem.

As rumors begin to leak out about complex accounting or other data-management problems of major banks all over the U.S. (including off-shore branches), the various banking regulatory agencies would be swamped with crises and outside rumors. Then, all at once, bank computers begin breaking down.

The rumors then explode. The lines appear in front of banks. The only answer at this point is to print up paper money. It would be printed by the hundreds of billions in order to offset the deflationary effects of bank runs (paper money that is pulled out but not re-deposited in another bank).

You could topple the fractional reserve banking system all over the world. The entire payments system could easily become engulfed in chaos. Debits and credits would no longer be meaningful. A pure paper money inflation would replace the manipulated, "fine-tuned" monetary inflation of modern central banking.

All of a sudden, market-created alternative currencies would be revived. It would then be metallic cash that talks loudest. Silver dimes are not electronic. "They can't be infected electronically." They still circulate when banks are "temporarily closed, due to circumstances beyond our control."

The loss of efficiency would be initially horrendous, I would guess. The division of labor would break down. You could then have the crash that lurks in the minds and suspicions of average depositors. Who says it cannot happen? A lot of public relations firms hired by the banks — computer illiterates in high places?

What we have is an internal bank money wire system that is totally vulnerable to some vindictive programmer. There is little doubt in my mind that the bankers are desperately fearful of this sort of vandalism. It could topple people's confidence in the fractional reserve banking system, and confidence is the only thing that keeps it going.

Conclusion. Technologically, there is no solution at this point. I have no heartening message. Maybe later; not now. Keep precious metal coins. Don't assume that it can't happen here. It can. The only thing holding it back is the restraining hand of God, through the temporary self-restraint of a technological priesthood.

[Reviewer's comment: I was unaware of the problem of computer worms and viruses until I read Gary North's two articles. His open release of this important information is appreciated.]

SCALAR EM INNOCULATION AND ITS IMPLICATIONS

My appreciation goes to Gary North for his openly sharing the above important information with the public. Human nature being what it is, one or more of his more dire scenarios is going to happen sooner or later.

The problem becomes enormously more compounded if the hostile agent or agents possesses sophisticated scalar EM technology.

With scalar technology, there exists the potential that the worm or virus can be implanted from a distance. If scalar-scanning devices of sufficient precision can be developed, then major software residing in a chip, a computer, or on a disk can be read from a distance. With scalar EM methods, the ordinary software "guards" are totally ineffective. The scalar "reader" could simply read off the software directly as the disk or device goes about its normal operations.

After the software is read, a germ or a virus is designed to produce a particular problem as desired and upon special stimulus. Then a scalar "imprinter" device is used to produce the necessary digital pulses directly upon the media in which the software resides. The required code has now been implanted. In effect, the operating system has been injected from a distance, and contaminated with the desired "sleeping agent" — germ or virus. From there on, it's just like Gary North's scenarios.

So the scalar EM technology can probably be used (at least eventually) to place "mines" in systems in advance, for damage or destruction at a future date. At least it's possible in principle.

However, it's not the injection of computers and equipment that bothers me. It's the injection of human beings. Here's generally how it can be done (and possibly is being done).

Basically, human brains have various rhythmic waves, which represent "envelope pulsations" of the entire electrical system. However, it is not the Et, force fields represented by these pulsations which are important: it is the summed-zero (scalar) patterning of the entire complex of neuron firings which represents the real activity of the brain — and represents its thoughts and emotions. A storage system for these patternings exists, but it's a scalar pattern storage, not an E and B field storage. The storage system is in the nuclei of the tissues of the nervous system itself, not in electrical or electrochemical potentials.

At any rate, the human brain rhythms are also "riding along" relatively entrained to the Schumann resonance of the earth's magnetic field. So all the patterning of the brain is grouped together into giant overall orders, and one or more of these is normally synchronized to our natural environment.

If a varying magnetic signal of extremely low frequency — say 10 hertz — bombards the brain with greater power than the earth's magnetic field, it is possible for the brain's rhythm to be "forcibly entrained" to synchronize with that signal, rather than with the normal Schumann resonance. If a large number of brains are forcibly entrained to such a signal, and the signal is artificial, then a nester coherent phasing of all the brains to the transmitted signal has been accomplished.

And that can be utilized — and is utilized — by the Soviet Union. On the Woodpecker signals, Bob Beck has detected up to 16 carriers, each with a 10-Hertz modulation, and with all the 10 Hz modulations in phase.

Let s stress what we're saying here. At times, the Woodpecker signals have shown 16 carrier frequencies that contain the same 10-Hertz modulation, and which are all kept coherently sync-locked.

If those signals and the modulations are strong enough, the brains in a targeted area demodulate the 10-Hertz signal and phase-lock to it — actually, to them. At that point, the brains are entrained to a 10-Hertz driver, and 16 channels of multimegahertz frequencies are locked-in to the brain.

Now, if the Soviets have broken the genetic code of the human brain (which they have) and succeeded in developing the ability to implant thoughts, emotions, pictures, etc. (which at least to a degree they have), then they can simply record the proper signals from human guinea pigs, using scalar technology and instrumentation.

They can tailor those signals and add them onto the Woodpecker carriers, using scalar EM techniques. By using most of the sixteen carriers as a means to express Fourier frequency expansions, specific areas and functions of the brain can be targeted.

"Notice that the distant transmitters already "know" the correct phasing, just use the 10 Hertz modulation signal as a reference. In that case, phasing takes care of itself inside the captured human brains.

The brain has a unique characteristic. If a signal arises inside it, it interprets that it itself originated the signal. Thus for the first time in history, true unwitting robot actions and emotions can be engendered in masses of human beings.

But it's still worse. The Kaznacheyev experiments (see references) proved conclusively that electromagnetic signals can carry and transmit cellular disease and death patterns into a targeted biosystem. You can rest assured that the Soviets continued on to actually measure and determine a wide variety of death and disease scalar patterns. All of that can be added on to the Woodpecker carriers so that the population in the intersection grid area is devastated. One can even test it out in advance by producing a modified pattern of a disease in the targeted populace, and keeping the percentage of brains entrained down to a small level. This lowers the number of persons "injected" from a distance to a small percentage of the populace. Then the outbreak of the "new strain" of a familiar disease — such as influenza, pneumonia, and something like AIDS — can be monitored to provide targeting and effectiveness data. Notice that a series of diseases was experienced by U.S. personnel assigned to the U.S. Embassy in Moscow, probably as a result of the so-called "weak microwave radiation" of the Embassy by the Soviet Union.

But that's not all. Much more subtle effects can be produced in the targeted populace, without anyone getting wise. Cancers and leukemia should be relatively easy to induce. Also, the immune system can simply be attacked directly. If done slowly, a series of common, ordinary diseases will just seem to get "tougher and tougher to cure." Actually it's not the disease that got tougher, it is the immune systems that got weaker. It is my opinion that precisely that sort of testing — against the immune system — has been accomplished by the Soviet Union against the U.S. since about October 1985. A great percentage of influenza patients during the period from then until now have had complications. So much so that multiple sessions — as many as 3 to 5 — of antibiotics are necessary before the patient recovers. At least in the Huntsville, Alabama "hinge pin" area, that seems to have been the case. This author personally experienced this, having influenza and follow-on complications for a period of seven months — something quite different indeed for him.

But it's even worse.

The human scalar EM nervous system ("inside" the ordinary EM signals and functioning of the system) also has its own resident "software." It has special storage media contained in its brain, its cells, and its genetic material, and its actual nucleons. All of these storage media are continually telecommunicated with via scalar EM means. Those recordings, largely condition the "stability" of what each of us is. As personalities we literally "are" what we have experienced, felt, thought, and did. Our whole "functioning conscious system" has been evolved by our experience, and it continues to be "us" by means of continual reference to the record base.

I hope you now realize that the actual record base itself can conceivably be altered by scalar electromagnetic means, even from a distance. Even by the hidden scalar EM content of 16 Woodpecker carriers, rocked into a captured brain and pouring in their deadly content. It is conceivable that even what one is can be taken from him, and what someone decides he will be, he will be.

A totally new — **and** ultimate — form of "slavery" has emerged.

Also, look at all this scalar EM functioning of the human system as a special kind of cybernetics. A scalar EM computing software and hardware system.

What if scalar techniques are used to plant "worms" and "viruses" in this system? With hidden triggers? What about a series of them, so that a range of eruptive software diseases can be stimulated at will?

And guess what. Such scalar EM "worms" and "viruses" can even be induced by contact with or consumption of "contaminated" water and food. Or saliva. Or other body fluid.

So you can see the possibilities of "seeding" a population with a staggering variety of time-bombs.

I think you begin to see the point. Now you can change North's "Soviet blackmail" scenario drastically. In a new scenario, Gorbachev simply announces to Reagan that a graduated series of specific sweeping changes are going to happen in our population — changes which we are absolutely powerless to stop. The last stages are various deaths. The master "trigger" for this series has already been initiated. Incidentally, the Soviet populace has been carefully "seeded" with the proper antidotes. The Russian leader demands certain things (very similar to what North's scenario utilized). Unless his demands are met, a "killer virus" will be activated by a special signal. If so, everyone dies. The first step change in the series will start to occur in a few hours. And it does.

In fact, this scenario could be added to North's scenario, and both used simultaneously. What do you think the President and the Congress would do? Or could do?

There are other even more diabolical possibilities, but these should be quite sufficient to illustrate the point.

Pandora's box has already been spilled, and the end of humanity is ticking away like a time bomb. It's already nearly midnight, and the watchman hasn't even sounded the alarm yet.

I certainly can anticipate the next question: Have the Soviets already "seeded" the populations of the U.S. and other selected western nations with scalar EM viruses and germs7

The answer is, I simply don't know. And just like Gary North, I don't know what if anything can be done about it if they have. This researcher certainly doesn't have all the answers. An immediate national crash program to develop scalar EM defenses is essential if we are not simply to be crushed beneath the hammer and sickle. It takes funding, people, facilities, and time.

In some 22 years of unrelenting struggle to convince the system we've got a terrible problem, I've hardly been able to move it off dead-center (no pun intended). This book, produced under extreme workload stress, is all I can do to raise the alarm. I've given it my very best shot.

What happens now remains to be seen. Other hands, hearts and minds are going to have to take up the task and carry it forward. This researcher has reached his limit, and has no more left to give.

APPENDIX III: CONTINUING THE SCENARIO

On May 3, 1986 a stunning loss of a U.S. Delta rocket carrying a critically-needed weather satellite occurred. The rocket suffered a shutdown of its main engine during launch and began to veer off course, causing the range safety officer to destroy it.

The takeoff of the blue and white Delta "workhorse" from launch Pad A at Cape Canaveral at first appeared picture-perfect. About a minute later, six of the nine booster rockets were expended and the remaining three switched on. Shortly after that, the rocket seemed to lose power. The main liquid-fueled engine had suddenly shut down, with the three strap-on boosters still burning. The rocket then had no stability and started to slowly drift off course, creating an increasing angle of attack. Within a few seconds, the nose cone snapped off under the severe stress. The U.S. Air Force range safety officer then sent a destruct command to the stricken rocket, which exploded in a ball of flame.

The Delta, built by McDonnell Douglas, had previously piled up a continuous string of 43 successful launches. Since 1960, 177 launches have occurred, and the success rate has been 94%. The Delta is one of the most reliable rockets ever built.

The unexpected shutdown of the main engine was perplexing. At a news conference following the mishap, William Russell. NASA's Delta project manager. stated: "It was a very sharp shutdown. almost as if it were a command shutdown."

Preliminary data, such as turbine speed and temperatures in and around the engine, "all appeared to be very normal." Russell said.

It may well have been a "command shutdown," unknown to Bill Russell and his NASA engineers.

Preliminary runs of the videotapes of the incident, aired by the national TV news media, show that during liftoff, a mysterious light approached the rocket from below and from the side. rising and striking the vehicle. This light and its path are strongly reminiscent of the first anomalous "light streak and ball" photo taken by Bob Gladwin just prior to the shuttle launch on November 26, 1985.

Let' s suppose that on May 3 the Soviet scalar EM grid was in the launch Phase ABM system mode and was tracking the launch of the Delta rocket.

If the anomalous light that moved up and contacted the rocket was a small ball of continuous electromagnetic energy formed by a distant Soviet scalar EM howitzer, then the rocket's main engine control circuits would have received a sudden and continuous pulse of EM power. This would probably have shutdown the engine by an actual "command" signal, artificially delivered. *

---

*Engineers have now determined that such a shorting of the engine circuitry occurred, causing engine shutdown.

Certainly such mysterious switching of satellite circuits has occurred before, probably due to Soviet scalar EM precision testing. For example, the British Ariel VI satellite has exhibited very strange anomalies in its command and control circuitry -- in fact, with very precise control switching being exhibited as if from an external source.

Thus a very small scalar EM missile may have been utilized by the Soviets to disrupt the control circuits in the rocket. A resulting pulse of power in the engine shutdown command circuit could have "ordered" the shutdown of the main engine -- just as it appeared.

It remains to be seen whether or not the Soviets used a "marker beacon" associated with the disruption of the Delta launch. One news photograph seems to contain a suggestion of such a light, but the videotapes must be studied frame by frame before it can be ascertained exactly what if anything is really there.

If a marker beacon was not used, the distant Soviet operator could simply have "popped out" the continuous EM ball of energy, tracked it and the ascending rocket exhaust, and "joysticked" the scalar EM missile up into the rocket.

Analysis of this incident is continuing, so nothing is certain as we go to press.

However, if this incident was indeed another Soviet kill, then it will have served the Russians well. Much of the world's media attention will now be focused on NASA's launch difficulties, and away from the recent Chernobyl nuclear reactor disaster in the Soviet Union. It's bound to take some of the media pressure off the Soviets.

In addition, it further cripples the U.S. satellite program. Loss of this critical weather satellite payload seriously reduces U.S. weather monitoring capabilities.

Further, the U.S. space program now appears to be all but grounded by the Challenger, Titan, and Delta explosions. For example, it will require about 18 months for the U.S. to redesign the shuttle so that America's shuttle program can get going again. So things are delayed until summer of 1987 at the earliest.

Meanwhile, the Russians are set to grasp the lead in the space race. In 1985 they launched about 100 rockets, five times as many as the U.S. They have a shuttle program of their own, well underway, with a flight expected within months. Earlier this year, they launched Mir, a second generation space station; a U.S. version is still some eight years away.

Charles Vick, of Huntsville, Alabama's Space and Rocket Center, summed it up: "They have their standard military program, a shuttle program and the equivalent of an Apollo program, all within a 10-year period. It's awesome."

An experienced propagandist like Gorbachev certainly understands the advantages of a strong Soviet push into space, such as (1) military advantage, (2) national prestige, (3) scientific achievement, and (4) projecting an image in the world's news media that the Soviets are first in space exploration.

So the failure of the Delta rocket provides many benefits to the Soviet Union.

It also continues to exercise and demonstrate Soviet mastery of the skies over North America itself.

Meanwhile, two U.S. nuclear submarines have "inadvertently" run aground in the last month or so.

Gorbachev again seems disposed toward a summit meeting soon.

If it's held, the agenda may be quite different from the one President Reagan is prepared for.

The clock ticks on toward midnight.

2002 ENDNOTES

1. It is actually a unified field theory since the infolded electrodynamics inside all EM potentials, fields, and waves is utilized—and the internal electrodynamics forms spacetime curvatures and dynamics of those ST curvatures.

2. M. W. Evans, "0(3) Electrodynamics," *Modern Nonlinear Optics,* 2nd Edition, M. W. Evans (Ed.), Wiley, New York, 2001, Vol. 2, p. 79-267.

3. David J. Bohm, "A Suggested Interpretation of the Quantum Theory in Terms of'Hidden' Variables, I and II." *Phys. Rev.,* 85(2), Jan. 15, 1952, p. 166-179 (Part I); 180-193 (Part II); — "Quantum theory as an indication of a new order in physics." A:, *Found. Phys.,* Vol. 1, 1971, p. 359; B: "Implicate and explicate order in physical law," *Found. Phys.,* 3(2), 1973, p. 139-168.

4. Mendel Sachs, General *Relativity and Matter,* Reidel, 1982; — "Symmetry in Electrodynamics: from Special to General Relativity, Macro to Quantum Domains," *Modern Nonlinear Optics,* 2nd Edition, Wiley, New York, Vol. 2, p. 677-706.

5. M. W. Evans, P. K. Anastasovski, T. E. Bearden et al., "On Whittaker's Representation of the Electromagnetic Entity in Vacuo, Part V: The Production of Transverse Fields and Energy by Scalar Interferometry," *J. New Energy,* 4(3), Winter 1999, p. 299-301 gives a basic mathematical expose of scalar interferometry.

6. James Clerk Maxwell, "A dynamical theory of the electromagnetic field," *Phil. Trans. Roy. Soc,* Vol. 155, 1865, p. 71, 459. Orally presented in 1864. This was Maxwell's definitive presentation of his theory, with 20 quaternion and quaternion-like equations in 20 unknowns. Also in *The Scientific Papers ofJames Clerk Maxwell,* edited by W. D. Niven, Dover, New York, 1952, Vol. 1, p. 526-604.

7. In T. E. Bearden, *Gravitobiology: A New Biophysics,* Cheniere Press, Santa Barbara, Ca. www.cheniere.org, 1991 we first exposed the quantum potential weapon and some of its uses and characteristics.

8. A negative energy EMP weapons strikes the target or target area with an extreme pulse of negative energy empty Dirac Sea 4-holes. As a result, the free electrons flowing in electrical currents in the struck target instantly disappear by re-absorption into the Dirac Sea. A living body struck by such a blast is totally and instantly dead in every smallest part, since all its brain and nervous system currents, cellular currents, etc. are instantly and totally extinguished. The Russians tested this weapon in the 1980s in their war in

Afghanistan, against two Afghan villages. I spent two hours in Washington D.C. with the then-representative of the Mujahedin to the U.S. Government, verifying the incidents and going over the exact characteristics of the instantaneous deaths of those villagers. With such a sudden death, the mind-body interconnection loop is instantly severed, so that the mind is instantly snapped loose from its connection to the body—hence my use of the term "MindSnapper." The struck body usually emits longitudinal EM waves for an extended period, so that vultures and other predators will not approach the bodies and eat them. All bacteria, viruses, etc. in the body are also killed instantly, and the body does not decay, even in 30 or 60 days.

9. As can be seen, the negative energy EMP weapon is an all-purpose weapon extremely effective against every kind of target: missiles, aircraft, communications, satellites, ships and particularly aircraft carriers, personnel, generators, power systems, the electronics of nuclear warheads, submarines, tanks and vehicles, and the electrical and electronic controls of any kind of machinery or equipment. Such weapons are the second most powerful weapons on earth. In the first part of 2002, a U.S. 2-carrier task force maneuvered in the South China Sea as a precautionary warning to the Chinese that we would defend Taiwan. Unknown to that fleet, tracking it and trained on it were the newly deployed Chinese negative energy EMP weapons, which could have destroyed the entire task force—everything in it—with a few shots in less than 10 minutes.

10. T. E. Bearden, *Energy from the Vacuum: Concepts and Principles,* Cheniere Press, Santa Barbara, CA, 2002. Chapters 1 and 2 give a deeper coverage of this and similar foundations principles.

11. As is well known, Russian theoreticians have always been the best nonlinear scientists on Earth, since the beginning. They still are.

12. See T. E. Bearden, "Giant Negentropy from the Common Dipole," *J. New Energy,* 5(1), Summer 2000, p. 11-23 for solution of the source charge problem. On DoE restricted website http://www.ott.doe.gov/electromagnetic/ and on www.cheniere.org. The problem of the source charge can be solved by treating (with the modern quantum field theory viewpoint) the "isolated" observable charge and its cluster of virtual charges of opposite sign as a composite dipole. Because of the broken symmetry of its opposite charges, any dipole or dipolarity continuously receives virtual energy from the seething vacuum, transduces it into real observable EM energy, and pours out observable photons in all directions at the speed of light. See also E. T. Whittaker, 1903, *ibid.* There is a scalar potential between the ends of each dipole. The scalar potential may be decomposed into a bidirectional set of longitudinal EM phase conjugate energy from the time dimension (from the imaginary plane) and outputs that EM energy in the real 3-space. 3-space conservation of energy flow

is violated, but 4-space conservation of energy flow is upheld. This rigorously follows from the discovery of broken symmetry of opposite charges in 1957—one of the types of asymmetry for which Lee and Yang received the Nobel Prize.

In classical electrodynamics, the charged particle itself is *assumed* to be the source of its own fields and potentials. In other words, the charge is implicitly considered to be *creating*—right out of nowhere—the Poynting energy flow it continuously pours out across the universe in all directions. That makes the charge a perpetual motion machine of the grossest kind, violating the maxim that energy can neither be created nor destroyed.

So the greatest perpetual motion advocates of all times are our own classical electrodynamicists and electrical engineering departments and professors who still ignore the active vacuum interaction that is missing from the classical model. They thereby ignore that the charge is a broken 3-symmetry in its violent exchange of virtual energy with the active vacuum, and merely organizes and emits in observable form a fraction of the energy it continuously receives from the imaginary plane (from the time domain). Yet, that broken symmetry has been known in particle physicists, both experimentally and theoretically, for 45 years.

When Maxwell wrote his theory, neither the electron, the atom, nor the nucleus had been discovered. There was no knowledge of the Drude electron gas, electron spin, etc. There was no knowledge of the nucleus of the atom, and even the atom itself was still contentious. A thin material ether (fluid) was believed to fill all space, so that no point in all the universe was empty of mass. Consequently, E and B were conceived as physical force fields in a material medium—the luminiferous ether. All Maxwell's equations—including the subset selected and modified by Heaviside that today are called "Maxwell's equations"—assume this material ether to this day.

Electricity was thought to be a "thin material electric fluid" running through wires like water through a pipe. The magnitude of the potential was not used; its reaction cross-section was calculated and erroneously used as its magnitude, as it is today (although a good electrodynamicist does know that it is only the *intensity* of the potential, not its magnitude).

Faraday believed that his "lines of force" were taut physical "strings" in this material ether, and that EM perturbations were the vibrations of these taut strings. As he clearly states in his 1873 *Treatise...*, Maxwell sought to capture Faraday's work exactly. He simply *assumed* Faraday's "plucked taut string" waves. Later the measurement in instruments of what was actually the lateral gyroprecession of electrons in receiving wires was thought to prove that the incoming ether vibrations were transverse, like those string waves, because the detected electric **fluid (electron** precession) waves in the receiving wire were transverse. The drift velocity of electrons longitudinally in a wire (in a typical case, several inches per hour) was unknown. A charge *q* was just a piece of electric fluid, much like a cubic centimeter or other volume of fluid; it had no connotation of "charged particle." There was no concept in all of physics of EM energy flowing through space. There was no knowledge that the same fields created in the transmission wire, which perturbs the Drude electrons laterally, also perturbs the positively charged nuclei laterally, in the opposite direction, highly damped but with equal energy.

There was no way to realize that the energetic perturbation of the curvature of spacetime around the sending wire antenna, by the Drude electron perturbation energy, is simultaneously accompanied by an equal and opposite perturbation of the curvature of spacetime in the opposite direction (energy density, not amplitude of the disturbing wave, determines the degree of curvature of the surrounding spacetime). Hence Maxwell omitted precisely one half the EM energy, one half the EM wave, and one-half the electrodynamics. As a consequence, the "Newton's third law recoil" of the nuclei today is thought to spontaneously arise as if some mystical demon observes the Drude electron perturbations, and simultaneously kicks the positively charged nuclei in the equal and opposite direction. Hence Newton's third law, so to speak, is erroneously still omitted from classical electrodynamics, and the better texts say so.

In the 1880s, the Michelson-Morley experiments falsified the material ether. Not a single one of the Maxwell-Heaviside equations were ever changed to this day. Instead, the electrodynamicists eventually announced that, since there was no longer an ether, they were not using one! Then a total non sequitur was incorporated: that in massfree space, the same E and B fields (defined as material entities and thus existing only in mass) still remain but the forces go to zero. Simple algebra reveals this clever, insidious faux pas, using the E-field as an example: First, F == d/dt(mv), so mass is a component of force. (This reveals the great error due to the hoary old notion that a separate force acts upon a separate mass; the mass is a component of the force, and the force is a coupled system of a curvature of spacetime and a charged mass.). Then E == F/q, which rigorously holds when mass is present.

Now for whatever reason, let F = 0. Then F/q = 0 and E = 0 also, else we must discard algebra. What actually remains is easily explained in general relativity terms (available since before 1920). The couplet of a curvature of spacetime and a charged mass is broken up by absenting the mass. What remains is that specific curvature of spacetime. GR assures us that curved ST acts upon mass, and that any force involves a curvature of ST. Yet in more than 80 years, this erroneous old "material ether remnant" in electrodynamics has been fiercely defended. Every textbook today uses and confuses the E and B fields in two dichotomous fashions: (1) as massive force fields existing only in the presence of mass, and as "massless force-free fields" existing only in the absence of mass. This of course is a non sequitur.

13. E. T. Whittaker, "On the Partial Differential Equations of Mathematical Physics," *Math. Ann.,* Vol. 57, 1903, p. 333-355. The "scalar" potential itself is not even a *scalar entity,* as shown rigorously by Whittaker. Instead, it is a harmonic series of bidirectional EM longitudinal phase conjugate wavepairs, and it decomposes into that series. Hence it is a *multiwave, multivectorial entity.*

14. C. N. Yang and R. L. Mills, "Conservation of Isotopic Spin and Isotopic Gauge Invariance," *Phys. Rev.,* Vol. 96, 1954, p. 191.

15. The term "energetics" simply means *energy as the primary thing in the universe.* Rankine first used it. G. Helm in 1887 revived Rankine's term "energetics" and factored energy into an *intensity* factor and an *extensity* factor (which today we would call potential and kinetic energies). William Ostwald in 1893, 1895, and 1901 raised the concept of "energetics" (energy as the primary thing in the universe) to the forefront. Thus when the Russians developed new extensions and principles in weapons physics, they simply used the historical notion of "energy as the primary thing in the universe" and adopted the earlier name for it: *energetics.*

16. Later when Khrushchev demanded a 100% antimissile defense, famed Russian Nobelist Petr Kapitsa answered, *"If a means of total neutralization of foreign missiles is to be found, it can only come from a group of new principles in physics, called energetics".*

17. See T. E. Bearden, "Mind Control and EM Wave Polarization Transductions, Part I", *Explore,* 9(2), 1999, p. 59; Part II, *Explore,* 9(3), 1999, p. 61; Part III, *Explore,* 9(4,5), 1999, p. 100-108. It appears that Sachs' unified GR and EM approach is perhaps the best Western physics model to apply to analysis of the KGB energetics weapons. However, because of the third branch *(psychoenergetics:* engineering the mind directly), Sachs' work would appear to need further extension along the lines indicated by the present author in the cited paper.

18. See T. E. Bearden, "EM Corrections Enabling a Practical Unified Field Theory with Emphasis on Time-Charging Interactions of Longitudinal EM Waves," *J. New Energy,* 3(2/3), 1998, p. 12-28; — *Energy from the Vacuum,* 2002, *ibid.* For nuclear transmutation at a distance (e.g., dudding all nuclear weapons by transmuting U235 and weapons grade plutonium), extension is required along the lines indicated by the present author in these references.

19. See M. Sachs, *ibid.,* also M. Sachs, "Relativistic Implications of Electromagnetic Field Theory," in T. W. Barrett and D. M. Grimes, eds., *Advanced Electromagnetism,* World Scientific, 1995, p. 551. The Sachs theory

already expresses the greatest generalization possible of electrodynamics, and fully justifies the preceding view.

20. See Whittaker, 1903, *ibid.;* — "On an Expression of the Electromagnetic Field Due to Electrons by Means of Two Scalar Potential Functions," *Proc. Lond. Math. Soc,* Series 2, Vol. 1, 1904, p. 367-372. The latter paper was published in 1904 and orally delivered in 1903. Per these two Whittaker papers, it is known that (i) ordinary EM fields and waves are the result of interference of two or more scalar potential functions, (ii) scalar potentials are comprised of harmonic sets of bidirectional EM phase conjugate wavepairs, (iii) all ordinary EM fields and waves and potentials have LW EM dynamics internally, and (iv) in theory, this "infolded" electrodynamics can be engineered. Sachs' theory dramatically extends the richness of that internal electrodynamics ignored in the West, and highlights the general relativity (sets of spacetime curvatures, or "engines", involved).

21. E.g., *Marine Observer* was a rich source for Russian energetics weapons testing in remote ocean areas, sighted by ships' captains and crews and entered into the ships' logs.

22. Portions of Khrushchev's statements to the Presidium are given in Max Frankel, "Khrushchev Says Soviet Will Cut Forces a Third; Sees 'Fantastic Weapon'," *New York Times,* Jan. 15, 1960, p. 1.

23. See Whittaker 1903 and 1904, *ibid.,* for the original basis of scalar interferometry and its creation of any kind of EM field, potential, and wave in the interference zone.

24. Also see M. W. Evans, P. K. Anastasovski, T. E. Bearden et al., On Whittaker's Representation of the Electromagnetic Entity in Vacuo, Part V: The Production of Transverse Fields and Energy by Scalar Interferometry, *J. New Energy,* 4(3), Winter 1999, p. 76 for mathematical proof of scalar interferometry. There are several other AIAS papers in the same issue of *JNE,* dealing with interferometry and with the implications of the Whittaker papers.

25. As an example, the U.S.S. Skylark, surface companion of the Thresher, was beset by mysterious "jamming" of multiple types of EM systems in multiple bands. So bad was it that it required more than an hour to get an emergency message to Naval headquarters that the Thresher was in serious difficulty. Later, as the scalar interferometry died away, all the EM systems aboard the Skylark resumed normal functioning. The Skylark was in fact in a "splatter zone" of the underwater interference zone around the Thresher.

26. Circa the end of 1989, the earlier longitudinal EM wave weapons on site in Russia were leased to a rogue Japanese group comprised of Aum Shinrikyo and Yakuza, who have been operating those weapon systems—on site in Russia—since then. Senator Sam Nunn's investigations revealed the presence

of the Aum Shinrikyo in Russia, to include establishing a university there. His investigators missed the Yakuza involvement and also missed the exotic weaponry aspects as one might expect.

27. I concluded from this remark that TEMPEST techniques are probably used at some nearby site not too distant from my home here in Huntsville, to read and record my work as I write it on the computer. That appears to be a good assumption.

28. As a small example of what can be done, see a series of papers by M. W. Evans, P. K. Anastasovski, T. E. Bearden et al, published in *J. New Energy*, 4(3), Special Issue, Winter 1999. The papers are: (a) "On Whittaker's Representation of the Electromagnetic Field in Terms of Two Scalar Potentials, Part I"; (b) "An Experimental Test of the Existence of Whittaker's *g* and/Fluxes in the Vacuum"; (c) "On Whittaker's Representation of the Classical Electromagnetic Field in Vacuo, Part II: Potentials Without Fields"; (d) "On Whittaker's F and G Fluxes, Part III: The Existence of Physical Longitudinal and Timelike Photons"; (e) "Representation of the Vacuum Electromagnetic Field in Terms of Longitudinal and Time-like Potentials: Canonical Quantization"; (f) "On Whittaker's Analysis of the Electromagnetic Entity, Part IV: Longitudinal Magnetic Flux and Time-Like Potential Without Vector Potential and Without Electric and Magnetic Fields"; (g) "On Whittaker's Representation of the Electromagnetic Entity in Vacuo, Part V: The Production of Transverse Fields and Energy by Scalar Interferometry"; and (h) "On Extending Whittaker's Theory, Part VI: Photons Without Fields and Vector Potentials".

29. As an example, one part of the strategic deception plan was devoted to convincing the West that Soviet psychoenergetics was nothing but a technical wrinkle upon the rather harmless Western parapsychology. This part of the program was completely successful for decades. Another very clever use of deception is to allow release of some real scientific advances that lead the West, but are not too important to the KGB in the weapons arena. The increasing emphasis on torsion fields is an example of this "deception by giving good information that directs the adversary upon a path one wishes him to take", effectively steering him away from the path one wishes him to avoid. Lately, however, there is an uproar amongst the academicians in the Russian Academy of Sciences over this very point, that torsion fields being presented as the "end all, be all" is simply disinformation.

30. With their deployment of QP weapons in 2002, the Chinese are also on the way to having this capability.

31. The multiply connected spacetime (MCS) or quantum potential weapons went on site circa latter 1989. A laboratory prototype had been tested against the U.S. air attack on Libya in April 1986. For details of the extremely anomalous jamming **of aircraft** and missile guidance and control systems in that

attack on Libya, see Mark Thompson, "Mixed signals may have misguided U.S. weapons," *The Washington Post,* Jan. 22, 1989, p. A-4.

32. One or more QP weapons also apparently induced the Gulf War Disease in MidEast forces in the Gulf War. We have previously explained the peculiar anomalies, how it was done, why the endemic natives did not contract the disease, why the French forces did not contract it but U.S., British, and Canadian forces did, etc. We briefly discussed quantum potential weapons in T. E. Bearden, *Gravitobiology: A New Biophysics,* In T. E. Bearden, *Gravitobiology: A New Biophysics,* Cheniere Press, Santa Barbara, Ca. www.cheniere.org, 1991.

33. (a) Yossef Bodansky, "Soviets testing chemical agents in Afghanistan," *Jane's Defence Weekly,* 1(3), Apr. 7, 1984, p. 508 gives something of the two Soviet tests of this weapon in Afghanistan. In addition to the fierce blast of empty Dirac Sea 4-holes, these weapons produce a powerful time-polarized EM pulse in the area, producing a very sharp "jerk" in the rate of flow of time, (b) The mind-body coupling mechanism—which cannot withstand such a sharp jerk in the rate of flow of time—has been given by T. E. Bearden, "Mind Control and EM Wave Polarization Transductions," *Explore,* 1999, *ibid.* This sharp "jerk" in time-flow instantly snaps the mind-body coupling mechanism for any living thing in the struck area. A very small version of this weapon was tested twice in Afghanistan, where the bodies in the "mind-snapped" zone died instantly, fell like limp rags, never twitched, and did not decay or get molested by insects or scavengers for the 30 days it required the Mujahedin to fight their way back into the two struck villages. The Mujahedin thought it was some new, extremely fast acting nerve gas, which they dubbed "smerch" or "death wind".

34. Two Ph.D. scientists were working closely with me on this entire effort, as was another close colleague. There was much more involved in the effort that is so briefly mentioned here.

35. Secretary of Defense William Cohen at an April 1997 counterterrorism conference sponsored by former Senator Sam Nunn. Quoted from DoD News Briefing, Secretary of Defense William S. Cohen, Q&A at the Conference on Terrorism, Weapons of Mass Destruction, and U.S. Strategy, University of Georgia, Athens, Apr. 28, 1997.

36. T. E. Bearden, *Energetics: Extensions to Physics and Advanced Technology for Medical and Military Applications,* CTEC Proprietary, Mar. 21, 1998, 200+ page inclosure to CTEC Letter to Gen. (Ret.) Walter Busby, Deputy Secretary of Defense for Counterproliferation and Chemical and Biological Defense, March 21, 1998. Copies were sent to various other U.S. government agencies, including to NIH, CDC, the USAF, etc.

37. See Vlail Kaznacheyev and L. P. Mikhailova, *Ultraweak Radiation in Intercellular Interactions,* [in Russian], Novosibirsk, 1981. An English exposition of much of the Kaznacheyev material is given in Vlail Kaznacheyev, "Electromagnetic Bioinformation in Intercellular Interactions," *Psi Research,* 1(1), Mar. 1982, p. 47-76. The work of Vlail Kaznacheyev led to the understanding of how to electromagnetically transmit cellular death and disease into targeted cells (or bodies) at a distance, and involved thousands of lab experiments. Highly sanitized work revealing the results but not the mechanisms, were permitted in order to stimulate the West to see if it knew about energetics.

38. See Stanislov Lunev and Ira Winkler, *Through the Eyes of the Enemy: Russia's Highest Ranking Military Defector Reveals Why Russia Is More Dangerous Than Ever,* Regnery, Washington, D.C., 1998. The Red Chinese also were able to decipher the Russian EM disease transmission methodology, early on. As a strange kind of "poetic justice" action the Chinese induced cancer into many Russian spies stationed in the Russian Embassy in China. Quoting Lunev, p. 160: "...I *was not the only person who was stationed in Beijing to come down with cancer...Almost all of the GRU officers stationed in China with me have been diagnosed with cancer. People assigned to the embassy had told me that they were picking up high levels of radiation from the apartment building around the embassy compound. Whether it was a form of high-tech monitoring or a conscious effort to harm our health, it seems to have been successful. So much so that in 1992 the GRU was asked to investigate the high rate of cancer among embassy officials. The findings, however, have never been made public; in part, no doubt, because of the rapprochement between Russia and China."*

39. See my "Porthole Briefing", on www.cheniere.org. Also see "Le Probleme Priore," *Rapport de la Commission de I'Academie des Sciences a Monsieur le Ministre d'Etat charge de la Recherche et de la Technologie,* France, 1982, p. 1-22; J. B. Bateman, "Microwave Magic," Office of Naval Research London Conference report, ONRL C-14-77, 1977; —*A Biologically Active Combination of Modulated Magnetic and Microwave Fields: The Priore Machine,* Office of Naval Research, London, Report R-5-78, Aug. 16, 1978; —"Staging the Perils of Nonionizing Waves," *European Scientific Notes,* ESN 32-3-85-88, 1978; T. E. Bearden, "Energetics Update and Summary," Parts 1, *Explore More,* No. 1, 1996, p. 13-18; Part 2, *Explore,* 8(1), 1997, 53-56; Part 3, *Explore,* 8(2), 1997, p. 42-45; Christopher Bird, "The Case of Antoine Priore and His Therapeutic Machine: A Scandal in the Politics of Science," Explore, 5(5-6), 1994, p. 97-110; R. Cambar, "Rapport general des travaux de la Commission de Controle constituee en vue de verifier l'un des effets biologiques obtenu par l'utilisation de l'appareillage de Priore A. Bordeaux," [General findings of the work of the control commission formed to verify one of the biological effects obtained by use of the apparatus of A. Priore at Bordeaux],

1969; R. Courrier, "Expose de M. le professeur R. Courrier Secretaire perpetuel de 1'Academie des Sciences fait au cours d'une reunion a l'lnstitut sur les effects de la machine de M. A. Priore 26 Avril 1977" [Presentation by Professor R. Courrier, Perpetual Secretary of the Academy of Sciences, made at the meeting of the Academy on the effects of the machine of M. A. Priore.]; Jean-Michel Graille, *Dossier Priore: A New Pasteur Affair,* De Noel, Paris, 1984 [in French]; Antoine Priore, "Apparatus for producing radiations penetrating living cells," U.S. Patent No. 3,368,155, Feb. 6, 1968; — "Method of producing radiations for penetrating living cells," U.S. Patent No. 3,280,816, Oct. 25, 1966; — "Procede et dispositif de production de rayonnements utilisables notamment pour le traitement de cellules vivantes," [Procedure and Assemblage for Production of Radiation Especially Serviceable for the Treatment of Living Cells], Republique Francais Brevet d'Invention P.V. No. 899.414, No. 1,342,772, Oct. 7, 1963; A. Priore, *Guerison de la Trypanosomiase Experimentale Aigue et Chronique par L'action Combinee de Champs Magnetiques et D'Ondes Electromagnetiques Modules* [Healing of intense and chronic experimental trypanosomiasis by the combined action of magnetic fields and modulated electromagnetic waves], thesis submitted in candidacy for the doctoral degree, 1973—rejected when the project was suppressed.

40. Eric Perisse, *Effets des Ondes Electromagnetiques et des Champs Magnetiques sur le Cancer et la Trypanosomiase Experimentale* [Effects of Electromagnetic Waves and Magnetic Fields on Cancer and Experimental Trypanosomias], Doctoral thesis, University of Bordeaux No. 83, March 16, 1984. Although Priore's own thesis was suppressed in 1973, Pautrizel nevertheless finally succeeded in getting this doctoral thesis by Perisse approved on the work, at the University of Bordeaux which had rejected Priore's thesis, after eleven more years had passed. Considering the viciousness of the suppression, this was a major accomplishment.

41. The photo was taken by George Suchary of the registration point (ball of light) high over the Nov. 1985 night shuttle launch from Cape Canaveral. For a photo of the same kind of "ball of light" registration point above the kill of a Titan missile launched from Vandenberg AFB in early 1986, see reference 39 below.

42. The picture by Canadian investigators showing the hole burned through the right fuselage ahead of the engines of the Arrow DC-8 is shown in T. E. Bearden, *AIDS: Biological Warfare,* Cheniere Press, Santa Barbara, Ca. www.cheniere.org , 1988, p. 52.

43. See T. E. Bearden, *Gravitobiology: A New Biophysics,* Cheniere Press, Santa Barbara, Ca. www.cheniere.org, 1991, p. 82. Two sensors on-board the Arrow DC-8 independently recorded the sharp electrical spike generated by the strike of the EM missile.

44. "Titan Explosion Cripples U.S. Launch Surveillance Capability," *Aviation Week & Space Technology,* 124(17), Apr. 28, 1986, p. 16-19. Specifically see the picture of the explosion on p. 18. It clearly shows the Soviet marker beacon (little ball of light) well above the missile explosion. General background on the Titan explosion and investigation is given in "Investigators Search for Clues to Cause of Titan Blast," *Aviation Week & Space Technology,* 124(17), Apr. 28, 1986, p. 19-20.1 persuaded NBC engineer Ron Cole with a team of engineers to examine the videotape of the explosion, frame by frame. In 17 frames the ball-of-light (registration point) is visible, and moves away completely independent of the explosion. No "bogies on the range" were reported at Vandenberg AFB.

45. Dr. Evans is co-discoverer with Vigier of the B(3) field, now well established but still not in the textbooks. He is the Director of the Alpha Foundation's Institute of Advanced Study (AIAS) and has over 600 papers and books in the literature.

46. M. W. Evans, P. K. Anastasovski, T. E. Bearden et al., "On Whittaker's F and G Fluxes, Part III: The Existence of Physical Longitudinal and Timelike Photons," *J. New Energy,* 4(3), 1999, p. 68-71; — "Representation of the Vacuum Electromagnetic Field in Terms of Longitudinal and Time-Like Potentials: Canonical Quantization," *ibid.*, p. 82-88; — "On Extending Whittaker's Theory, Part VI: Photons Without Fields and Vector Potentials," *ibid.*, p. 79-81.

47. Terence W. Barrett, "Electromagnetic Phenomena Not Explained by Maxwell's Equations," in Lakhtakia, A. (ed.): *Essays on the Formal Aspects of Electromagnetic Theory,* World Scientific Publishing, River Edge, NJ, 1993, p. 6-86; — "On the distinction between fields and their metric: the fundamental difference between specifications concerning medium-independent fields and constitutive specifications concerning relations to the medium in which they exist." *Ann. Fond. Louis de Broglie,* 14(1), 1989, p. 37-75; — and D. M Grimes. [Eds.] *Advanced Electromagnetism: Foundations, Theory, & Applications.* World Scientific, (Singapore, New Jersey, London, and Hong Kong), Suite 1B, 1060 Main Street, River Edge, New Jersey, 07661, 1995. In the latter book see T.W. Barrett, "Sagnac Effect: A Consequence of Conservation of Action Due to Gauge Field Global Conformal Invariance in a Multiply-Joined Topology of Coherent Fields," p. 278-313.

48. But see Craig F. Bohren, "How can a particle absorb more than the light incident on it?" *Am. J. Phys.,* 51(4), Apr. 1983, p. 323-327. By *resonating* the intercepting charged particle, its reaction cross section increases, and more EM energy is collected and re-radiated by the charge than is input to it by the conventional accounting (which only accounts the input Poynting energy that would be intercepted by a *static* charge). The conventional input energy

calculation therefore ignores the huge nondiverged Heaviside component surrounding the Poynting component and wasted. The resonant particle sweeps out past the usual Poynting component into the unaccounted Heaviside input component, and collects excess energy. The Bohren experiment with resonant charged particles produces COP =18. Metallic particles at ultraviolet frequencies are one class of such particles and insulating particles at infrared frequencies are another. For independent confirmation of the Bohren experiment, see H. Paul and R. Fischer, {Comment on "How can a particle absorb more than the light incident on it?'}," *Am. J. Phys.,* 51(4), Apr. 1983, p. 327.

49. E. T. Whittaker, 1903, *ibid.*

50. A beneficial use, e.g., would be to use such CSRs to investigate and report the interior of the sun and planets, including the Earth and its core. Since a CSR can also travel "through" the interior of a light beam, in theory such could be dispatched back into some of the nearer stars to also explore and report their interior.

51. This is no more curious than stating that sets of waves and their dynamics can exist in space, without interacting with mass, and that they can then later interact with a mass system to change it in specifically designed manner. Since longitudinal EM waves and their dynamics are "infolded" inside ordinary EM waves, fields, and potentials, they are also infolded "inside" the ambient vacuum potential, which itself is a part of the local vacuum potential. In short, one forms highly complex LW wavesets and functional dynamics, in essentially a sort of "subspace" as popularized by the Star Trek television series. The LW "engines" are identically ST curvature engines. A close colleague of the present author has in fact already invented and rigorously demonstrated such a communication system, but his former funding by several very large communications companies collapsed before he could develop and employ this system for the commercial market.

52. This is easily understood if one shifts one's vision from "space" to "subspace." Subspace is filled with (literally is composed of) longitudinal EM waves and their dynamics. The CSR's are quite unique, enormous systems "singing away" with longitudinal EM waves. So a longitudinal EM wave interferometer can easily locate them by sweeping its beams through subspace, as a radar sweeps to track aircraft in space. Once the CSR target "pings", the system automatically hits it with a profusion of interacting LWs, completing disrupting and destroying its dynamics. Scratch one system. Probably several million such systems were destroyed throughout the West (command centers, power grids, submarines, nuclear bombers, etc.) in rapid fire order, all without any external "spatial" sign other than perhaps a wee bit of very low level "EM noise" briefly as a struck CSR fractured.

53. See M. Sachs, *Quantum Mechanics from General Relativity,* Reidel, 1986. Sachs'unified field theory, e.g., applies equally to the quarks and gluons, as it does to the nucleons, the atoms, molecules, and macroscopic objects and phenomena. See also M. Sachs, "Symmetry in Electrodynamics: From Special to General Relativity, Macro to Quantum Domains," in *Modern Nonlinear Optics,* Second Edition, 3 vols., M. W. Evans (ed.), Wiley, 2001; vol. 1, p. 677-706.

54. G. M. Wang, E. M. Sevick, Emil Mittag, Debra J. Searles, and Denis J. Evans, "Experimental Demonstration of Violations of the Second Law of Thermodynamics for Small Systems and Short Time Scales," *Phys. Rev. Lett.,* 89(5), 29 July 2002, 050601.

55. The tragic death of Captain Hess was also very probably such a test. Hess, perfectly normal and happy, laid out his uniform in the early morning and then went for his customary morning jog. He suddenly veered aside, sat down in a path and stabbed himself 26 times, all deep stab wounds, four of which would be totally incapacitating (two right through the heart) to any normal individual experiencing normal shock, etc. To a psychoenergetically controlled individual where shock does not occur nor does emotion or pain, this is understandable. Add this to the incidents involving Captains Button and Svoboda, and one begins to see the picture.

56. W. Heitman and G. Nimtz, "On Causality Proofs of Superluminal Barrier Transversal of Frequency Band Limited Wave Packets," *Phys. Lett. A196,* 1994, p. 154-158. Aichmann and Nimtz and co-workers at the University of Cologne have transmitted 8.7 GHz microwaves (free space wavelength 3.4 cm) traveling in a rectangular wave-guide that contains a "barrier" section of reduced dimensions. They have recently transmitted Mozart's 40th Symphony as frequency modulated microwaves through a barrier wave-guide at an FTL group velocity of 4.7 c, receiving audibly recognizable music from the microwave photons that survived their barrier passage. The transit time through the barrier was about 81 picoseconds and was observed to be constant for barriers with widths varying from 4.0 cm to 11.4 cm.

57. Quantum mechanics in fact requires instantaneous transmission of effects. A mishmash of learned contention would have us believe one can "transmit" energy instantly, but not intelligence. This argument has essentially stymied our scientific establishment so that it has not really funded strong investigation in this area. It is a stupid argument: Simply transmit one change, then a second one, then a third one, in serial order, where the "order" contains the intelligence. No different from Morse code. Somehow the pundits so certain that intelligence cannot be superluminally transmitted seem to have forgotten what "intelligence" is. They also seem to have assumed that one superluminal change can be **transmitted** on order, but a second, third, and fourth cannot.

58. Feynman and Wheeler tried very hard to formulate a new absorber theory of electrodynamics to eliminate many of the fierce foundations problems. Wheeler described the effort this way: *"...we may summarize the account of radiation reaction given by Wheeler and Feynman in 1945. In it every charged particle is envisaged as coupled to every other charged particle by a field that is symmetric in time: half advanced, half retarded. Interconnections run forward and backward in time in such numbers as to make an unbelievable maze. That weaving together of past and future seems to contradict every normal idea of causality. However, when the number of particles is great enough to absorb completely the signal starting out from any source, then this myriad of couplings adds up to a simple result: the familiar retarded actions of everyday experience, plus the familiar force of radiative reaction with its familiar sign."* [John Archibald Wheeler, "Law without law," in *Quantum Theory and Measurement.*, preprint, p. 39].

Unfortunately, when the foundations of any science are closely examined in their roots, one runs into the age-old bane of the philosopher: ultimately opposites are identical, at least prior to the observation (separation) action to separate them. It follows that all scientific reasoning is circular at its most primary basis.

59. See Charles W. Misner, Kip S. Thorne and John Archibald Wheeler, *Gravitation,* W. H. Freeman, San Francisco, CA., 1973, p. 71. Wheeler spoke of that inescapable fact in this manner: *"Here and elsewhere in science, as stressed not least by Henry Poincare, that view is out of date which used to say, 'Define your terms before you proceed.' All the laws and theories of physics, including the Lorentz force law, have this deep and subtle character, that they both define the concepts they use (here B and E) and make statement about these concepts. Contrariwise, the absence of some body of theory, law and principle deprives one of the means properly to define or even to use concepts. Any forward step in human knowledge is truly creative in this sense: that theory, concept, law, and method of measurement—forever inseparable—are born into the world in union."*

60. Also see T. E. Bearden, *Energy from the Vacuum: Concepts and Principles,* 2001, *ibid,* for a rework and extension of Aristotelian logic to eliminate its present fatal flaw, extending it into a 5-law logic.

61. The very notion of "propagation of energy through space" is radically extended in the extended unified EM and GR being pursued by AIAS and Sachs. Time-like EM energy currents dominate in the vacuum. E.g., see M. W. Evans et al., "Representation of the Vacuum Electromagnetic Field in Terms of Longitudinal and Time-like Potentials: Canonical Quantization," *J. New Energy,* 4(3),Winter 1999,p. 82.

62. Multiwave interactions (between transverse EM waves) produce time-reversed EM waves (phase conjugate replicas of the signal wave input). That method time-reverses EM energy in waveform. To time-reverse EM energy in mass form, simply pump that mass with time-polarized EM waves. As an alternative, it may be pumped with longitudinal EM waves (which are always accompanied by time-polarized EM waves anyway), and the pumped mass is also pumped in the time-domain because of the presence of the time-polarized EM waves in the pumping. We previously filed an invention disclosure with the U.S. Patent Office dealing with how to do that.

63. Mostly studied by Becker. See (a) R. O. Becker, "The control system governing bone growth in response to mechanical stress," *J. Ark. Med. Soc,* Vol. 62, 1966, p. 404; (b) — and David G. Murray, "The electrical control system regulating fracture healing in amphibians," *Clinical Orthopaedics and Related Research,* Vol. unk, No. 73, Nov.-Dec. 1970, p. 169-198. This latter paper is the definitive technical exposition by Becker of his electrical control system ideas and findings. Good references for the educated layperson are (c) R. O. Becker, "A technique for producing regenerative healing in humans," *Frontier Perspectives,* 1(2), Fall/Winter 1990, p. 1-2; (d) Robert O. Becker and Gary Seldon, *The Body Electric: Electromagnetism and the Foundation of Life,* William Morrow and Company, New York, 1985; and (e) Robert O. Becker, *Cross Currents: The Promise of Electromedicine, the Perils of Electropollution,* Tarcher, St. Martin's Press, New York, 1990.

64. A provisional patent application has been filed on the process, and an overview of the method can be seen as the "porthole briefing" on my website www.cheniere.org.

65. (a) C. A. L. Bassett; R. O. Becker, and R. J. Pawluk, "Effects of electric currents on bone in vivo," *Nature,* Vol. 204, Nov. 14, 1964, p. 652-654. The complete electrical control system (conventional EM theory) for the healing of bone fractures is given in (b) R. O. Becker, *Clinical Orthopedics and Related Research,* Vol. 73, 1970, p. 169. A paper "putting it all together" is (c) R. O. Becker, J. *Bioelec,* Vol. I, 1982, p. 239.

66. F. Mandl and G. Shaw, *Quantum Field Theory,* Wiley, 1984, Revised Edition 1993, under the heading "5.2 Covariant Quantization" and "5.3 The Photon Propagator" in Chapter 5. The longitudinal and scalar photon polarizations are not directly observable, but only in combination, where they manifest as the instantaneous Coulomb (i.e., electrostatic) potential interaction, *"which emerges as an exchange of longitudinal and scalar photons."* So the common old electrostatic scalar potential is actually comprised of longitudinal EM waves and time-polarized EM waves.

67. With the MidEast increasingly set to explode, we may be facing the unleashing of weapons of mass destruction, a vast shortage and curtailment of

available oil and energy, and a total collapse of the Western economy and therefore most of the world economy, in as little as three or four years, if the impending energy crisis worldwide is not resolved quickly. See T. E. Bearden, ADAS position paper, "The Unnecessary Energy Crisis: How to Solve It Quickly," *ibid.* As this is written, we have already had a warning shot across our bow: the vicious terrorist attacks on September 11, 2001. We are in Afghanistan and elsewhere in a war against terrorism, and anyone can see the escalation in the MidEast toward war between the U.S. and Iraq, and almost certainly a resulting explosion in the MidEast and unleashing of the hostile terrorists assets and mass destruction weapons already inside the United States. Since modern economies are based on cheap energy, and cheap energy is largely based on cheap oil, then with surging energy demands worldwide we shall see "oil wars" erupt and rage worldwide, with terrorist retaliations and attacks—using weapons of mass destruction—occurring in U.S. cities. *Unless energy from the vacuum is quickly developed and deployment begun at high speed, we risk the coming collapse of the world economy, great destruction of populaces, and a new Dark Ages.*

68. E. T. Whittaker, 1903, *ibid.*

69. Daniel A. Walker, Charles S. McCreery, and Fermin J. Oliveira, "Kaitoku Seamount and the Mystery Cloud of 9 April 1984," *Science,* Vol. 227, Feb. 8, 1985, p. 607-611; Daniel L. McKenna and Daniel A. Walker, "Mystery Cloud: Additional Observations," *Science,* Vol. 234, Oct. 24, 1986, p. 412-413.

70. Superpotential theory was initiated by E. T. Whittaker, extending earlier concepts advanced by G. Johnstone Stoney. See E. T. Whittaker, *Proc. Lond. Math. Soc,* Series 2, Vol. 1, 1904, p. 367-372. Nisbet extended the Whittaker and Debye two-potential solutions of Maxwell's equations to points within the source distribution. This is a full generalization of the vector superpotentials (for media of arbitrary properties) together with their relations to such scalar potentials as those of Debye. See A. Nisbet, *Physica,* Vol. 21, 1955, p. 799. Also, A. Ricci in 1901 introduced what might be called the magnetization potential, satisfying a certain equation, as an alternate to the Hertz vector. This was a part of early vector superpotentials. For an excellent overview discussion of superpotentials and related things, see Melba Phillips, "Classical Electrodynamics," in *Principles ofElectrodynamics and Relativity,* Vol. IV of *Encyclopedia ofPhysics,* edited by S. Flugge, Springer-Verlag, 1962. Phillips discusses, for example, that Whittaker 1903 (note: oral delivery; paper was published in 1904) was the first to prove that one can derive a general electromagnetic field from two scalar functions, which are really components of the vector superpotentials, with proper choices of the gauge functions. Whittaker's method is well known in the treatment of transverse electric and transverse magnetic modes of a cylindrical cavity or a waveguide. Nisbet has shown that this result may be extended within the source distribution (assumed

given) by a suitable choice of stream functions. The Debye potentials and the Bromwich potentials are essentially radial components of the vector potentials of which Whittaker potentials are the real parts. So in general the particular integral (the stream potentials) of the inhomogeneous Maxwell equations may be so chosen that the complementary function can be expressed in terms of only two scalars, which are components of the vector superpotentials. The Whittaker and the Debye-Bromwich potentials are special cases of two vector superpotentials.

71. David Jones, *Vancouver Sun Times,* Weekend Magazine, Dec. 17, 1977, p. 17.

72. For more specific information on the production of practical antigravity and an experiment demonstrating it, see T. E. Bearden, *Energy from the Vacuum: Concepts and Principles,* Cheniere Press, Santa Barbara, CA, 2002, Chapter 8. Approach to Antigravity.

73. T. E. Bearden, *Energy from the Vacuum: Concepts and Principles,* Cheniere Press, Santa Barbara, CA, 2002, Chapter 10. Cold Fusion: Low Spatial-Energy Nuclear Reactions at High Time-Energy. By inadvertently using highly compressed time-energy, cold fusion researchers are actually using—on the tabletop—higher energy density than our present high-energy physics uses in its largest accelerators. The conventional scientific community does not have a single scientific program dedicated to using time as energy, even when one's physics model can legitimately be made of a single fundamental unit. When the joule is chosen as that unit, then time becomes totally a function of energy, just as is mass. The use of mass-energy gave us the nuclear age; the use of time-energy will give us a far greater age, if we can ever get the scientific community off its duff and moving.

74. Further, the second law of thermodynamics has long been known not to apply to a single charge, atom, or molecule or to a small group. For such microscopic phenomena, there will occur reversed reactions a certain small fraction of the time. But also see G. M. Wang, E. M. Sevick, Emil Mittag, Debra J. Searles, and Denis J. Evans, "Experimental Demonstration of Violations of the Second Law of Thermodynamics for Small Systems and Short Time Scales," *Phys. Rev. Lett.,* 89(5), 29 July 2002, 050601. These researchers have experimentally proven that the second law can be and is violated for much larger scales—up to micro (colloidal) size—and for much longer times (up to two seconds). Hence it is now proven that such "reversed zones" where reactions run backwards for quite a bit, can and do in fact occur on the colloidal scale, sufficient for the formation of large clusters of like charges. Evans and his colleagues have pointed out that these results dramatically affect chemistry.

75. Shoulders has been creating and using such charge clusters for years. See Kenneth R. Shoulders, "Energy Conversion Using High Charge Density,"

U.S. Patent # 5,018,180, May 21, 1991; — "Energy Conversion using High Charge Density," U.S. Patent No. 5,123,039, 1992; — "Method and Apparatus for Production and Manipulation of High Density Charge," U.S. Patent #5,054,046, 1991; — U.S. Patent #5,054,047, 1991; — "Circuits Responsive To and Controlling Charged Particles," U.S. Patent 5,148,461, 1992; — and Steve Shoulders, "Observations on the Role of Charge Clusters in Nuclear Cluster Reactions,"J. *New Energy,* 1(3), Fall 1996, p. 111-121.

76. D. J. Evans and D. J. Searles, *Phys. Rev. E,* Vol. 50, 1994, p. 1645.

77. See Donald Kennedy, "To Publish or Not to Publish," *Science,* Vol. 295, 8 Mar. 2002, p. 1793.

78. R. P. Taleyarkhan, C. D. West, J. S. Cho, R. T. Lahey Jr., R. I. Nigmatulin, and R. C. Block, "Evidence for Nuclear Emissions During Acoustic Cavitation," *Science,* Vol. 295, 8 Mar. 2002, p. 1868-1873. Quoting from the abstract: "In cavitation experiments with deuterated acetone, tritium decay activity above background levels was detected. In addition, evidence for neutron emission near 2.5 million electron volts was also observed, as would be expected for deuterium-deuterium fusion. Control experiments with normal acetone did not result in tritium activity or neutron emissions."

79. Yuri T. Didenko and Kenneth S. Suslick, "The energy efficiency of formation of photons, radicals and ions during single-bubble cavitation," *Nature,* Vol. 418, July 25, 2002, p. 394-397.

80. E.g., see John Archibald Wheeler and Richard Phillips Feynman, *Phys. Rev.* 59, 1941, p. 683; —"Interaction with the Absorber as the Mechanism of Radiation," *Rev. Mod. Phys.,* 17(2, 3), Apr.-Jul. 1945, p. 157-181.

81. Albert Einstein, "Foreword," in Max Jammer, *Concepts of Space: The History of Theories of Space in Physics,* Harvard University Press, Cambridge, Massachusetts, 1969, p. xi-xii.

82. Robert A. Fisher, [Ed.], *Optical Phase Conjugation,* Academic Press, NY, 1983, p. xv.

83. Basically, the choice between distant heating in the interference zone, or distant cooling, is as simple as how one biases the ground potential used for the electrical grounds of the interferometer transmitters. Biasing well above the ambient potential in the distant IZ produces divergent EM energy (heat) forming and radiating in the distant zone. Biasing well below the ambient IZ potential produces convergent EM energy (cold) forming and radiating in the distant zone.

84. Mass is mostly empty space filled with EM potentials, fields, and waves. Since these potentials, fields, and waves are simply bundles of longitudinal EM waves and their impressed dynamics, it follows that mass itself

is mostly a "giant superhighway" for the transmission of LWs. This is actually a sort of "subspace" transmission "right through" matter, so to speak.

85. As demonstrated by such dual serial usage by a giant interferometer in the anomalous and explosive "cloud" phenomena near the Kurils in April 1984. For excellent descriptive articles and a hard look at the phenomena, see Walker et al., *Science, ibid.*

86. See "Soviet device uses radio waves as tranquilizer," AP release, *Huntsville [Alabama] Times,* May 19, 1983. See also W. Ross Adey, "Biological effects of low energy electromagnetic fields," *Proc. NATO Adv. Study Inst. on Advances in Biological Effects and Dosimetry of Low Energy Electromagnetic Fields,* Plenum Press, New York, 1983, p. 359-391. Adey apparently was aware only of ordinary U(l) electrodynamics. He describes the **LIDA** device as follows: *"Soviet investigators have also developed a therapeutic device utilizing low frequency square wave modulation of a radiofrequency field. This instrument know as the LIDA, was developed by L. Y. Rabichev and his colleagues in Soviet Armenia, and is designed for the 'treatment of neuropsychic and somatic disorders, such as neuroses, psychoses, insomnia, hypertension, stammering, bronchial asthma, and asthenic and reactic disturbances.' It is covered by U.S. Patent #3,773,049. In addition to the pulsed RF field, the device also delivered pulsed light, pulsed sound, and pulsed heat. Each stimulus train can be independently adjusted in intensity and frequency. The radiofrequency field has a nominal carrier frequency of 40 MHz and a maximum output of approximately 40 watts. The RF field is applied to the patient on the sides of the neck through two disc electrodes approximately 10 cm. in diameter. The electrodes are located at a distance of 2-4 cm from the skin. Optimal repetition frequencies are said to lie in the range from 40 to 80 pulses per minute. Pulse duration is typically 0.2 sec. In a 1-year trial period, the instrument was used on 740 patients, including adults and children. Positive therapeutic effects were claimed in more than 80 percent of the cases treated."* We accent that this is one of the simplest Russian psychoenergetics devices, obsoleted very early on, and thus released very early for public use.

87. Since U.S. researchers are unaware of the EM wave polarization transduction mechanisms, and in general have no instruments for detecting longitudinal EM waves, the specific transduction effects on humans would not be measured by U.S. laboratories. Hence the U.S. scientists could only think of it in conventional electrodynamic terms, and remained totally unknowledgeable about the specific transduction mechanisms in the human body producing time-polarized EM waves and effects from the device.

88. Max Frankel, "Khrushchev Says Soviet Will Cut Forces a Third; Sees 'Fantastic Weapon'," New *York Times,* Jan. 15, 1960, p. 1.

89. For a simplified introduction to psychoenergetics and the mind-matter coupling mechanism, see T.E. Bearden, "Mind Control and EM Wave Polarization Transductions, Part I", *Explore,* 9(2), 1999, p. 59; Part II, *Explore,* 9(3), 1999, p. 61; Part III, *Explore,* 9(4,5), 1999, p. 100-108.

90. One of the serious goals of the die-hard KGB psychoenergetics scientists appears to be to achieve the capability of directly engineering the entire human collective unconscious mind. The plan envisioned is to convert the human species into a sort of "giant ant species" where each one has perfect, machine-like niche and function (except, of course, for the elite Communist masters). In short, they conceived back there in the 1960s that such a "perfect communist state" for all humanity was in fact possible to achieve technically, with sufficient development of psychoenergetic technology. They are apparently well along the way toward achieving that goal. [The U.S. has not even conceived such a scientific possibility, and modern cognitive science in the West seems bent on the rather astounding proposition that mind itself does not even exist!]. We point out that no type of physical defense is even possible against such a capability engineered into the collective human unconscious, once it is achieved. The only "counter" is to use the same technology (it has to first be developed) to "re-engineer" what will have been done. But our fellows have not even conceived the possibility of the threat, much less the cause or the counter. Hence they continue to totally misunderstand what happened to Captains Button, Svoboda, and Hess in successful mind-control tests achieved perfectly at great distance.

91. To see the nature of the time-density wave (which is basically a longitudinal EM wave along the time axis), due to the perfect correlation between time-energy flow currents and variations with respect to longitudinal EM waves, see T.E. Bearden, "Giant Negentropy from the Common Dipole," 2000, *ibid.* Not stressed in the paper is the fact that the same dipolar negentropy with correlated EM time-energy currents and EM spatial energy currents, exists in the "individual" photon. Further, they can occur in coupled photon-antiphoton pairs, yielding the graviton. For time-polarized EM photons, it appears that two photon-antiphoton pairs are coupled, yielding the "supergraviton." Elsewhere we have briefly and addressed these novel formations as hypotheses.

92. Induction of specific diseases and health changes in the U.S. Embassy in Moscow over four decades, included causing the deaths of three U.S. Ambassadors. It was accomplished by implementing desired disease-pattern "engines" infolded inside field-free potentials. The Johns Hopkins study of the radiation patterns revealed a most significant finding: All the affected persons were in regions of the Embassy where the Russian microwave radiation *fields* were absent. In short, where the field-free—and thus very stable—potentials existed. Since these scientists (and most others in classical EM) consider that EM effects are caused only by fields, they concluded (totally erroneously) that

these health changes could not have been caused by the microwave radiation. To the contrary, they had just clearly proven that the radiation was indeed the cause. They showed a 100% correlation to the *presence of field-free potentials*, and a 100% anticorrelation to where the fields were present. This was for induced phenomena over several years. Had the radiation not been the culprit, then some health changes would have occurred where the fields were present, and some would have occurred where they were absent. That is not what happened at all, and this inexplicable logical non sequitur against common statistical inference was the accepted decision. The truly revealing aspect was that *apparently the entire U.S. Intelligence community had no competence or capability in higher group symmetry electrodynamics.*

93. E.g., see Lewis H. Ryder, *Quantum Field Theory*, Cambridge University Press, 2nd Edition, 1996, p. 147+ which covers the four photon polarizations. See also F. Mandl and G. Shaw, *Quantum Field Theory*, Wiley, 1984, Revised Edition 1993, under the heading "5.2 Covariant Quantization" and "5.3 The Photon Propagator" in Chapter 5.

94. We elaborate on this somewhat, in "Mind Control and EM Wave Polarization Transductions", *ibid.*

95. Again, we point out the unified field approach of Mendel Sachs as probably being the best Western model in which to grapple with these phenomena.

96. David J. Bohm, "A Suggested Interpretation of the Quantum Theory in Terms of'Hidden' Variables, I and II." *Phys. Rev.*, 85(2), Jan. 15, 1952, p. 166-179 (Part I); 180-193 (Part II).

97. T. E. Bearden, *Gravitobiology: A New Biophysics*, Cheniere Press, Santa Barbara, Ca. www.cheniere.org, 1991.

98. W. A. Rodrigues Jr. and J.-Y. Lu, "On the existence of undistorted progressive waves (UPWs) of arbitrary speeds 0 < v < oo in nature," *Found. Phys.*, 27(3), 1997, p. 435-508. A slightly corrected version is downloadable as hep-th/9606171 on the Los Alamos National Laboratory web site. It includes corrections to the published version.

99. W. A. Rodrigues Jr. and J. Vaz Jr., "Subluminal and Superluminal Solutions in Vacuum of the Maxwell Equations and the Massless Dirac Equation," *Adv. Appl. Clifford Algebras*, Vol. 7(S), 1997, p. 457-466.

100. E.g., see A. Enders and G. Nimtz, *Phys. Rev. Lett.*, Vol. 48, 1993, p. 632. Enders, Aichmann, Nimtz and co-workers at the University of Cologne have transmitted 8.7 GHz microwaves (free space wavelength 3.4 cm) traveling in a rectangular wave-guide that contains a "barrier" section of reduced dimensions. They transmuted Mozart's 40th Symphony as frequency modulated

microwaves through a barrier wave-guide at an FTL group velocity of 4.7c, receiving audibly recognizable music from the microwave photons that survived their barrier passage.

101. J. D. Jackson, *Classical Electrodynamics,* 2nd Edition, Wiley, New York, 1975, p. 222.

102. See H. A. Lorentz, *Vorlesungen Uber Theoretische Physik an der Universitat Leiden, Vol. V, Die Maxwellsche Theorie (1900-1902),* Akademische Verlagsgesellschaft M.B.H., Leipzig, 1931, "Die Energie im elektromagnetischen Feld," p. 179-186. Figure 25 on p. 185 shows the Lorentz concept of integrating the energy flow vector around a closed cylindrical surface surrounding a volumetric element. This is the procedure which arbitrarily selects only a small component of the total energy flow in space outside a circuit and associated with it—specifically, the small Poynting component diverged by the surface charges into the conductors to power the electrons—and then treats that tiny component as the "entire" vast energy flow (which may be a trillion or more times greater in magnitude). Thereby Lorentz arbitrarily discarded all the huge *Heaviside* energy transport component that does not strike the circuit at all, is not diverged into the conductors, and is just wasted. See Oliver Heaviside, *Electrical Papers,* Vol. 2, 1887, p. 94. Quoting: *"It [the energy transfer flow] takes place, in the vicinity of the wire, very nearly parallel to it, with a slight slope towards the wire... . Prof. Poynting, on the other hand, holds a different view, representing the transfer as nearly perpendicular to a wire, i.e., with a slight departure from the vertical. This difference of a quadrant can, I think, only arise from what seems to be a misconception on his part as to the nature of the electric field in the vicinity of a wire supporting electric current. The lines of electric force are nearly perpendicular to the wire. The departure from perpendicularity is usually so small that I have sometimes spoken of them as being perpendicular to it, as they practically are, before I recognized the great physical importance of the slight departure. It causes the convergence of energy into the wire."*

103. When it is associated with positive energy fields and potentials from positive mass, positive energy source charges, we have nominated that long-unaccounted Heaviside energy flow component as the source of the excess gravity holding the arms of the spiral galaxies together (a solution to the dark matter problem). When it is associated with negative energy fields and potentials from negative-energy Dirac Sea holes in 4-space, we have nominated that unaccounted energy flow component as the source of the excess antigravity responsible for accelerating the expansion of the universe (a solution to the dark energy problem).

104. About a year from now, Bedini and I will also release a very novel use of this Heaviside energy flow component in inverted circuits—circuits that

operate almost completely in reverse from normal textbook circuits. This is a totally new kind of circuit that we hope will revolutionize power systems and electronic control systems. Until our intellectual property rights are secured, we are not releasing any details at all.

105. Terence W. Barrett, "Tesla's Nonlinear Oscillator-Shuttle-Circuit (OSC) Theory," *Ann. Fond. Louis de Broglie,* 16(1), 1991, p. 23-41. Tesla was able to shuttle energy around in his circuits at will. Barrett went on to improve the process and patent two versions. See T. W. Barrett, "Active Signalling Systems," U.S. Patent No. 5,486,833, Jan. 23, 1996. This is a signaling system in time-frequency space for detecting targets in the presence of clutter and for penetrating media. See also T. W. Barrett, "Oscillator-Shuttle-Circuit (OSC) Networks for Conditioning Energy in Higher-Order Symmetry Algebraic and RF Phase Conjugation," U.S. Patent No. 5,493,691. Feb. 20, 1996.

106. Bryan G. Wallace, "The Unified Quantum Electrodynamic Ether," *Found. Phys.,* 3(3), Sept. 1973, p. 381-388.

107. William G. Harter, John Evans, Roberto Vega, and Sanford Wilson, "Galloping waves and their relativistic properties," Am. J. *Phys.,* 53(7), July 1985, p. 671-679. Most waves caused by a single frequency source have a galloping motion. The only exceptions are the very special cases of absolutely pure moving waves or absolutely pure standing waves. The superposition and resulting interference of two oppositely moving waves generally yield a wave having nonuniform motion; in short, the wave rushes forward rapidly, then slows appreciably, etc. A relativistic example is given in which the source frame observes a very nonuniformly galloping wave whose velocity varies between 0.01 c and 100 c, even though its average velocity is c. Relativistic properties of interfering electromagnetic plane waves are discussed.

108. S. L. Miller, "The Formation of Organic Compounds on the Primitive Earth," *Ann. NYAcad. Sci.,* Vol. 69, 1957, p. 260; — *Bioch. Biophys. Acta.,* Vol. 23, 1957, p. 480-489; — *Science,* Vol. 117, May 15, 1953, p. 528-529; — and H. C. Urey, "Organic Compound Synthesis on the Primitive Earth," *Science,* Vol. 130, 1959, p. 245-251.

109. R. Harada and S. Fox, "Thermal Synthesis of Natural Amino-Acids from a Postulated Primitive Terrestrial Atmosphere," *Nature,* 201(4917), 1964, p. 335-336; S.W. Fox, "How Did Life Begin?", *Science,* 132(3421), July 22, 1960, p. 200-208; — and S. Yuyama, "Abiotic Production of Primitive Protein and Formed Microparticles," *N.Y. Acad. Sci. Ann.,* Vol. 108, June 1963, p. 487-494; — and K. Harada, "Thermal Copolymerization of Amino Acids to a Product Resembling Protein," *Science,* 128(333), 1958, p. 1214; — and M. Middlebrook, "Anhydrocopolymerization of Amino Acids Under the Influence of Hypothetically Primitive Terrestrial Conditions," *Federation Proc.* Vol. 13, Mar. 1954, p. 211.

110. H. C. Urey, "On the Early Chemical History of the Earth and the Origin of Life," *Proc. Nat. Acad. ScL,* 38(4), 1952, p. 351-363.

111. I.e., one may speak of the "potential" of a specific engine of a former life form, and then realize that the potential for that form reduces in magnitude inversely as the radial distance from the Earth. However, it does not reduce to zero until an infinite distance is reached.

112. As an example, a great EM energy flow—produced by the cross product ExH of the earth's magnetic field and the earth-to-electrosphere electric field—flows from West to East around the earth, nearly parallel to the equator. Infolded in that great EM energy flow are all the structures of all the genetics and life forms on earth, or that have ever been on earth and conditioned the natural scalar potential of the earth. The vials in the laboratory experiments of Miller, Fox, and Urey were all continually bathed in that great energy flow, which within it contained the entire life structure and dynamics of the planet. So no "inert" experiments were ever performed, contrary to the interpretations of the scientific community.

113. Vlail Kaznacheyev and L. P. Mikhailova, *Ultraweak Radiation in Intercellular Interactions*, [in Russian], Novosibirsk, 1981 [an English exposition of much of the Kaznacheyev work is given in Vlail Kaznacheyev, "Electromagnetic Bioinformation in Intercellular Interactions," *Psi Research,* 1(1), Mar. 1982, p. 47-76.] Kaznacheyev, e.g., appears to have headed the Soviet team actually producing the basis for the disease-inducing technology utilized for four decades in the microwave radiation of the U.S. Embassy in Moscow.

114. Specifically, the down payment was $900 million in gold. The lease is probably about $1 billion per year. Thus the Yakuza acquired very powerful strategic weapons, and became a secret power to be reckoned with internationally and strategically. Since 1990, weather engineering over the U.S. and occasional shootdown of aircraft (such as the TWA-800) have been by rogue Japanese fingers on the scalar interferometer weapon triggers, on site in Russia.

115. The Yakuza has also transferred some of the longitudinal EM wave interferometry technology to their Japanese facilities. One such system has apparently been deployed in the power grid, and has been used to kill some government officials who opposed the Yakuza. This information was obtained by some brave Japanese risking their lives to get the information to the present author.

116. Many important KGB weapon tests happened in April of various years; the KGB weapons folks were simply preparing for their May Day reports, and each wished to have a good one.

117. Sen. Sam Nunn's investigation teams verified that the Aum Shinrikyo were actively seeking the "Tesla Weapons", with the Aum Shinrikyo even visiting the Tesla Museum in Beograd for that purpose. We have 100% certain confirmation of the Yakuza and Aum Shinrikyo leasing of the scalar interferometers from the KGB and Russian Mafia (working for the KGB) at the end of 1989 or first few days of 1990. Sen. Nunn's report confirms that the Aum Shinrikyo set up a University in Moscow. Our comment is that this is where the Russians actually taught the Japanese crews the science and technical functions so that they could successfully man and use the scalar (longitudinal EM wave) interferometry weapons.

118. Recall that in the 1950s and early 1960s, Kaznacheyev et al., *ibid.,* had already clearly proven that nearly any form of cellular change, damage, or disease could be induced in cells at a distance by purely electrodynamic means.

119. In the kill of the Arrow DC-8 at Gander, Newfoundland on 12 Dec. 1985, the struck aircraft did charge up with time-density charging, and many pieces of the wreckage did indeed emit longitudinal EM waves thereafter for some time. Consequently, the Canadian recovery crews working the site and handling the materials, were exposed to longitudinal EM wave radiation for varying degrees of exposure. It follows that many of those on-site handlers should have later come down with physical ailments, with symptoms such as flu-like features, weakness, heart palpitations, headaches, dizziness, disturbance of equilibrium, and with various infections because of weakened immune systems. They also should have had weakened cellular regenerative (healing) systems, so their physical problems would endure and largely remain. About five dozen of the recovery personnel did come down with those exact symptoms, and many remained disabled or debilitated for some years.

120. We have also explained (a) why the French forces in the Gulf War did not get GWS, while American, British, and Canadian forces did, (b) why the native population did not exhibit GWS, and (c) the remaining anomalous phenomena associated, such as the semen "infecting" the wife, the children catching similar or related conditions from sustained close proximity to their father's biofields (transmission of engines), etc.

121. Mario Bunge, Foundations of Physics, Springer-Verlag, New York, 1967, p. 176.

122. T. E. Bearden, "Giant Negentropy from the Common Dipole," J. *New Energy,* 5(1), Summer 2000, p. 11-23 gives the solution to the long-vexing source charge problem. The paper is also carried on DoE restricted website http://www.ott.doe.gov/electromagnetic/ and on www.cheniere.org

123. Two examples of inane articles and actions in this respect, revealing no knowledge that every charge in the universe already exhibits COP = oo, are (a)

Graham P. Collins, "There's No Stopping Them: Perpetual Motion is alive and well at the U.S. Patent Office," and (b) Resolution by the Executive Board at the June 2002 meeting of the American Physical Society (APS) as follows: *"The Executive Board of the American Physical Society is concerned that in this period of unprecedented scientific advance, misguided or fraudulent claims of perpetual motion machines and other sources of unlimited free energy are proliferating. Such devices directly violate the most fundamental laws of nature, laws that have guided the scientific progress that is transforming our world."* So the learned APS has just declared the source charge as an unacceptable "free energy" machine and perpetual motion machine, since the charge simply sits there and continuously pours out real observable EM energy in all directions at the speed of light, without any observable EM energy input. Thus the APS has implicitly declared all EM fields and potentials and their energy—which includes every joule of EM energy in the universe, in matter or in space—to be unacceptable byproducts of perpetual motion nonsense. We heartily call upon the APS in the name of science to enforce their resolution in the orthodox academic community, who are the greatest perpetual motion advocates in history. To be consistent with their own resolution, they must root out and destroy—from all texts and universities and from the scientific literature—any mention whatsoever of charge, field, potential, and EM energy. Either they must do that, or stand hoisted on their own petard as a dogmatic group still very much unaware of why the Nobel Prize was awarded to Lee and Yang in 1957 and what the proof—by Wu et al.—of the asymmetry of opposite charges means with respect to the source charge considered in its modern quantum field theory view as a dipolarity of a bare infinite central charge surrounded by clustering virtual charges (also infinite charge) of opposite sign in the active vacuum. Every electrical engineering department and professor and textbook still uses a model and teaches a subject assuming that every charge in the universe freely creates energy from nothing at all. Further, the APS in every annual meeting also tolerates, encourages, and publishes multiple papers and presentations with the same such unacceptable perpetual motion assumptions in them. Such is the lofty understanding of our present organized scientific community, which seems much more politically bent than scientifically bent. The simple Bohren experiment and the entire area of negative resonance absorption of the medium has long been established in nonlinear optics, and such experiments widely yield a nominal COP = 18. In other words, the experiments nominally output 18 times as much energy as the operator inputs, and the excess input energy is furnished absolutely for free from the active vacuum's exchange. In this case the Executive Board of the APS is not even aware of what its own physics discipline has long proven and accepted in particle physics, for nearly a half century. Neither are the self-appointed defenders of the faith, who also are totally unaware of what physics has already proven with a Nobel Prize awarded nearly a half century ago.

124. C. S. Wu, E. Ambler, R. W. Hayward, D. D. Hoppes and R. P. Hudson, "Experimental Test of Parity Conservation in Beta Decay," *Phys. Rev.,* Vol. 105, 1957, p. 1413. We also quote Nobelist T. D. Lee as follows: *"Since nonobservables imply symmetry, any discovery of asymmetry must imply some observable. The experiment of Wu, Ambler, Hayward, Hoppes and Hudson... established the asymmetry between the positive and negative signs of electricity."* [T. D. Lee, *Symmetries, Asymmetries, and the World of Particles,* U. Wash. Press, Seattle, 1988, p. 11.].

125. Dilip Kondepudi and Ilya Prigogine, *Modern Thermodynamics: From Heat Engines to Dissipative Structures,* Wiley, New York, 1998, reprinted with corrections 1999.

126. See "Secret Speech: Did Brezhnev Come Clean?" *National Review,* 29(8), Mar. 4, 1977, p. 248, 250

127. For the energy description of this device and some results, see Floyd Sweet and T. E. Bearden, "Utilizing Scalar Electromagnetics to Tap Vacuum Energy," *Proc. 26th Intersoc. Energy Conversion Engineering Conf. (IECEC '91),* Boston, Massachusetts, p. 370-375.

128. Also see my book, *Energy from the Vacuum,* 2002, *ibid,* which includes photographs of the self-powering Sweet device, courtesy of Walter Rosenthal.

129. Roy Brewer was very active in Hollywood Unions against Communists when they were busily penetrating the Hollywood complex. He was a staunch anti-communist, fighting them out of control of the unions, way back when. Ronald Reagan was a personal friend of his of long standing, and Roy had open access to the White House when Reagan was President.

Roy briefed Reagan on the Russian scalar weapons, and Reagan believed him. Three times, Reagan ordered his Secretary of Defense to take action in that area, but neither of the three did so because the U.S. Intelligence Community did not believe it and adamantly opposed any such action. We took quite a beating in those days, for quite a long time (some years), before certain key parts of the Government finally believed us, checked it out experimentally, and found that it worked.

Roy also introduced me to the Duke de Grantsmesnil, one of the last of the great old British intelligence men, now unfortunately deceased. In the hectic 1997 days when we were trying desperately to warn a little friendly nation (and our own) against a coming great strategic strike on the U.S. and other allies, the Duke played a major role in introducing us directly to higher political levels in that little nation - which was the only nation on earth that could counter the pending strike. The first planned strike scheduled in February 1997 was successfully countered, only to be immediately rescheduled. In the second incident, the attack was scheduled for May 1, 1997. We finally realized why the hostile nation could reschedule and go ahead, and needed then to warn the little nation of the reason in some detail. We had tried everything to get certain information through, and all means had failed. A former ambassador of that nation to Great Britain was also assassinated during that struggle. Roy Brewer was one of the key fellows assisting in that attempt, as were other personal colleagues of mine who also were witnesses and direct participants in those desperate events. When all else failed, I finally just faxed the Prime Minister directly, in the clear, some five days before the attack, urging the most urgent and immediate action possible by the Prime Minister. A complete change in command and control of the weapon was required, and that change had to be made and then the hostile nation had to be notified that the change was in place (and probably shown that it was). The Prime Minister accepted the message and the necessary action was carried out immediately. So two days or so before the actual attack was scheduled, that great hostile armada began standing down. Oh, the hostile nation and its leaders could have easily destroyed the entire United States in two hours or so, without fail! But then their own country would have promptly disappeared from the face of the earth. So they stood down. And our own Intel community never even picked it up (they did get my messages alerting the U.S. Government, but thought it was a joke or something). They, of course, also intercepted my open fax to the Prime Minister, and so were all over me for that one for a while thereafter.

Interestingly, at the very time that great armada was just beginning to stand down, then Secretary of Defense William Cohen made the following statement at a conference in Georgia: "Others are engaging even in an eco-type of terrorism whereby they can alter the climate, set off earthquakes, volcanoes remotely through the use of electromagnetic waves...so there are plenty of ingenious minds out there that are at work finding ways in which they can wreak terror upon other nations...It's real, and that's the reason why we have to intensify our efforts, and that's why this is so important." Secretary of Defense William Cohen at an April 1997 counterterrorism conference sponsored by former Senator Sam Nunn. Quoted from DoD News Briefing, Secretary of Defense William S. Cohen, Q&A at the Conference on Terrorism, Weapons of Mass Destruction, and U.S. Strategy, University of Georgia, Athens, Apr. 28, 1997.

Ironically, the Secretary was referring to the earlier scalar interferometer weapons, and now the quantum potential weapons etc. He was completely unaware that a great strategic strike had actually been scheduled and was just being aborted as he was speaking those words.

Roy Brewer is one of those fellows who has been a great American, has served his country admirably during his lifetime, and contributed greatly to preventing a planned take-over by the Communists of the labor unions of America. In addition, he helped set up the contacts with the friendly **liltle foregn nation, so** that on four occasions planned attacks to destroy the United States have been successfully aborted or handled.

As you know, one of the great failures in the Communist plan to have America go communist was their failure with the labor unions. And we owe that failure to the steadfast efforts of some staunch folks like Roy Brewer. He helped save our nation when many of us were still wearing knee pants.

130. Wheeler's principle, as stated in W. Misner, K. S. **Thorne, and J.** A. Wheeler, *Gravitation,* W.H. Freeman and Co., San Francisco, 1973, p. 5.

131. With the new improvements we uncovered, treatment time can be reduced to 5 minutes per patient. Three such treatments one week apart would be what are required. Hence one machine station could treat a patient every five minutes, around the clock. With sufficient portable treatment units, mass treatment for mass casualties would become a practical reality.





AIDS

BIOLOGICAL WARFARE

Lieutenant Colonel Thomas E. Bearden (U.S. Army, Retired) PhD, is the author of numerous books, papers, briefings, and presentations dealing with anomalous phenomena, scalar electromagnetics, free energy devices, Soviet Tesla weapons, and Soviet scalar electromagnetic weather warfare.

At the time of writing this book, Lt. Col. Bearden was a senior scientist and department manager with the Alabama division of a major aerospace company where he directed the company's design and production of expert systems (artificial intelligence) applications for the U.S. Army command control systems. He had more than 29 years experience in air defense systems, tactics, and operations; technical intelligence; nuclear weapons employment; computerized wargames; anti-radiation missile countermeasures; and military systems requirements.

Bearden obtained a Master of Science degree in nuclear engineering from the Georgia Institute of Technology and a Bachelor of Science degree in Mathematics from Northeast Louisiana University. He is a graduate of the U.S. Army Command and General Staff College.

Tom was also then a member of Mensa, Society for the Investigation of the Unexplained, International Tesla Society, American Association for the Advancement of Science, Association of American Physics Teachers, the Air Force Association, the Association of the U.S. Army, the American Nuclear Society, and the American Defense Preparedness Association. He was also the Alabama and East Coast Director for the Association of Distinguished American Scientists, was a member of the Alabama Academy of Sciences, and was previously on the Board of Directors of the U.S. Psychotronics Association.

In private life, Tom has two sons and daughters, and lives in Huntsville, Alabama with his wife, Doris.

Sweating done by red_gonzo.

Note: sometimes formatting of the text may be a little fuzzy. It's all because the OCR process didn't go as smoothly as I expected. Also there may be some errors inside text so be vigilant. In any case share this book, send emails to people about knowledge contained in it. This book should especially be interesting to any person in medical community (being as a doctor or as patient) as it provides factual evidence of successful (but supressed) treatments through electromagnetic means. But before any devices can be understood and developed a new and extended kind of physics must be introduced into our educational system. Only then can this proper foundation be learnt and used by applicative sciences such as medicine. So far such knowledge has been contained in highly classified military circles and hopefully now, after many decades of suppression, it will finally be used for the good of mankind.

Dedication

This book is sincerely dedicated to the millions of persons who have died needlessly of cancer, leukemia, and AIDS in the last two and half decades. They were men, women, and children. Some were weak, some were strong. Some died in agony, some died silently. All of them were our fellow human beings. We remember them. They were important. Their anguish cries out to be heard. God willing, the new electromagnetic medicine so long suppressed will flower, and save the millions otherwise yet to die.

Special Acknowledgements

Mr. Christopher Bird's kind permission to print, his summary of the Priore Affair is gratefully acknowledged, as is the contribution of his own extensive Priore research material to this effort. The author owes a great debt indeed to Chris Bird for his magnificent assistance.

Mr. Robert Whitney graciously contributed rare photographs of Antoine Priore's device and also translations of background papers by French scientific journals. His previous valiant though fruitless efforts to bring the Priore machine into the mainline of Western medical treatment are specifically recognized and commended.

Vital contributions by Drs. Robert B. and Theodore A. Strecker are particularly acknowledged. Their March 1986 alert to the federal government, that AIDS was a deliberate biological attack spawned by Soviet agents working in Western research laboratories, is specially pointed out.

Heroic efforts by Dr. John Seale and other scientists to alert the medical research community to the true source of AIDS is specifically recognized and gratefully acknowledged.

Continuing efforts by Dr. William C. Douglass to "tell it like it is" on the AIDS crisis is specially pointed out. His permission to extract and present an excerpt from his research, pointing out tested healing of viral infections by UV irradiation of the blood, is deeply appreciated.

The unyielding and continuing efforts of Dr. Eva Snead, to alert the national authorities to the fact that there is more to AIDS than meets the eye, is also particularly recognized and appreciated.

Decades of effort by John Crane to bring Royal R. Rife's work out of suppression are specifically recognized and appreciated.

Important scalar EM experiments by John Bedini and Frank Golden are fully recognized and deeply appreciated. Their experimental efforts over a period of years have profoundly influenced my own thinking and understanding.

As always, my great admiration and deep thanks go to my friend Hal Crawford, whose keen artistic vision and skilled hand have contributed key illustrations to my work for years.

Other important illustrations and artwork by Messrs. James Thomas Neumann and Lee Giles are gratefully acknowledged.

Photographs furnished by John Moray showing his father's pioneering free energy work are appreciated. T.H. Moray's genius and achievements will yet be recognized.

Support from the Association of Distinguished American Scientists and Mr. Richard J. Reynolds III is deeply appreciated. Without that support, this effort could not have been accomplished.

Important contributions from a host of other colleagues and persons are deeply appreciated. These persons include Frank Golden, John Bedini, Ken Moore, Tom McLaughlin, Joe Parrot, Randy Davidson, George Fencl, Andrew Michrowski, Stefan Possony, Tony Gideon, Electra Briggs, and many others too numerous to mention.

Finally, nothing that I have attempted could have been accomplished at all without the unflinching and loyal support of my beloved wife, Doris.

To all of you I owe a great deal. If this bizarre struggle to save humanity is ever won, it will largely be due to the significant contributions you have made.

Thomas E. Bearden
Jan. 17, 1988

TABLE OF CONTENTS

DEDICATION iii

SPECIAL ACKNOWLEDGEMENTS iv

TABLE OF CONTENTS vi

LIST OF FIGURES xi

LIST OF TABLES xv

FOREWORD 1
  What This Book Is About 1
  Desperate Diseases, Desperate Remedies 3
  The "Dirty Dozen" 5
  An Analogy 6

THE VACCINE CONNECTION 8
  The "Monkey Bite" Theory 9
  Retroviruses and Recombinants 10
  Cancer Research Produced Ideal Biological Warfare Agents 11
  U. S. "Cancer War" Labs Were Infiltrated 12
  The Deed Was Easily Done 14
  It's Actually Documented 15
  Soviet Biological Warfare Background 17
  We Need An Immediate, Full-Scale Investigation 20

THE SOVIETS KNEW THE U. S. WOULDN'T REACT 24
  Administering the Coup-de-Grace 24
  Murky "Behind-the-Scenes" Intentions 26
  The USSR Has Repeatedly Verified Our Nonreaction 30
  The Asian Tiger Mosquito: A New and Efficient Vector 62

TABLE OF CONTENTS

WORLD WAR III IS RAGING AND WE'VE NEARLY LOST IT ... 66
- More On Aids Doubling Time ... 66
- World War III is Already Raging ... 68
- Communism is Savage Enough to Do Diabolical Things ... 68
- Western Medicine is Inadequate ... 69
- The Soviets Will Not Be Decimated ... 71

EXTRAORDINARY PHYSICS ... 74
- Maxwell's Lost Unified Field Theory ... 74
- Heaviside's Mutilation of Maxwell's Theory ... 83
- Building Upon Whittaker's Fundamental Work ... 86
- Symmetry and Parity ... 90
- Charge-Parity-Time and Negative Energy ... 97
- Free Energy and Antigravity ... 100
- Phase Conjugation (Time Reversal) ... 104
- The Phase Conjugate Mirror ... 114
- Amplifying the Phase Conjugate Effect ... 117
- The Phase Conjugate Mirror as a Vacuum Triode ... 122
- Newton's Third Law and the Full Law of Entropy ... 125
- Scalar Electromagnetics ... 134
- Scalar EM View of the Vacuum ... 139
- Charge, Potential, and Curvature of the Vacuum/Spacetime ... 151
- Twin Flows of Time ... 152
- Engineering Local General Relativity ... 154
- Engineering Antigravity ... 157
- Curved Spacetime and the Disintegrated Vacuum ... 159
- Separation of Vacuum and Observable States ... 160
- Partial Potentials, Curvature, and Warping ... 161
- Force and Mass are Inextricably Intertwined ... 164
- The Concepts of Zipped and Unzipped Forces ... 166
- Force, Force Field, and EM Waves in Vacuum ... 168
- Zero-Summed Vector Systems: Shortcoming in Vector Analysis ... 172
- Maxwell's Theory was Altered and Curtailed ... 174
- Scalar Waves and Polarization of the Vacuum ... 177
- Vector Zero Systems and the Kaluza-Klein Approach ... 180

TABLE OF CONTENTS

Electrogravitation Amplification Factor 186
Comparison of EM Concepts 187
The Aharonov-Bohm Effect 188
Curl-Free Magnetic Vector Potential (A-Field) 190
Fractional Charges, Magnetic Monopoles, and Magnetic Currents 192
Some Ehrenhaft Experiments 194
What is a Magnetic Monopole? 199
Supercharges and Fractional Charges 202

EXTRAORDINARY BIOLOGY 204
Kervran's Proof of Biological Transmutation 204
Biological Transmutation Has a History 207
Surplus-of-Energy Mechanisms Proposed By the U. S. Army 208
Alchemy and Unusual Critters 210
The Cell Also Lives and Functions in the Virtual State 213
The Kaznacheyev Experiments 214
Structuring and Charging a Biopotential 217
The Cell's Electromagnetic Breathing 218
The Summed Virtual Structures of Kaznacheyev "Death Photons" Physically Kindle the Disease 219
Electromagnetic Infection Results in Physical Disease 221
A Possible Cure For AIDS 221
The Mirror Cytopathogenic Effect and Factors Influencing It 223
Some Biological Warfare Implications 225
What Kaznacheyev Hid: The Role of Phase Conjugation 226
Popp's Master Cellular Communication System 228
Scalar EM Comment on Popp's Communication System 230
A New View of the Nature of Mind and Thought 231
Kindling, Life, Mind, and Negentropy 236
The Priore Machine and Phase Conjugation 247
Phase Conjugates of "Death Photons" are "Healing Photons" 249
The Effect is Universally Applicable 251
In the Mid-70's It Ended 252

TABLE OF CONTENTS

Work of Australians Reid and Barsamian, and the American G. Wilbanks 254
Concepts of Dr. Reid and Associates 259
Other Important Ideas 261
Wider Implications of Structured Field Information 262
Dr. Barsamian's Important Theoretical Insights 264
Royal Raymond Rife 266
Rife's Universal Microscope 267
Rife Proved That Everything Is Alive 272
Rife's Microscope Used Evanescent Waves 275
Rife Revealed a Far More Fundamental, Living Biology 277

DEVELOPING THE ELECTROMAGNETIC CURE FOR AIDS 280
Reversing the Kaznacheyev Effect 280
The Proof: Priore's Work 282
What Is Needed 284
Encouraging Preliminary Work 284
Conclusion 288

SELECTED BIBLIOGRAPHY 290
References Related to Chapters 1 and 2 290
References Related to Chapter 3 297
References Related to Phase Conjugation (Time Reversal) 303
References Related to William J. Hooper's Work 309
References Related to Ehrenhaft's Work 312
References Related to Louis Kervran's Work 314
References Related to Popp's Master Cellular Communication System 316
References Related to Kaznacheyev's Experiments 319
References Related to The New View of The Nature of Mind and Thought 324
References Related to Antoine Priore's Work 333
References Related to the Australian Work 339
References Related to Royal R. Rife's Work 341

TABLE OF CONTENTS

APPENDIX I: The Case of Antoine Priore and His Therapeutic Machine: A Scandal in the Politics of Science (Christopher Bird) (Used by Permission) 346

APPENDIX II: Patents 376

APPENDIX III: A Conditional Criterion for Identity, Leading to a Fourth Law of Logic 428

APPENDIX IV: List of Selected Incidents 444

APPENDDIX V: Dead Man Fuzing: The Real Meaning of the Reykjavik Summit 484

LIST OF FIGURES

No. Title Page

1. Conventional science cannot do the job 4
2. The "Monkey-Bite" theory 9
3. The Soviets have delivered an intended knockout 15
4. The U.S. Embassy in Moscow 32
5. Decay of a radioactive nucleus 33
6. EGP fission of a radioactive nucleus 33
7. Bottled up energy in a standing scalar EM wave is a potential 34
8. EGP shortout 34
9. EGP initiation of the Chernobyl event 35
10. The U-2 high-altitude reconnaissance aircraft 36
11. The U. S. S. Thresher disintegrates 37
12. Soviet helicopters have used a "death ray" in Afghanistan 40
13. Mushroom cloud from the sea off Japan, near a Russian test area 40
14. The Tesla Shield, a giant hemispherical shell of energy 41
15. The Tesla shield: A 1969 Virgin Islands incident 41
16. Tesla shields: Two nested arcs of light in the sky 42
17. Tesla shield: An expanding hemispherical circle of light 42
18. Tesla shield: Hemisphere and globes, 1977 43
19. Large Tesla shield observed by Red Chinese fighter pilots 43
20. Large glowing "Tesla Globe," Red China 44
21. 1966 test of giant Tesla globe, expanding deep within the Soviet Union 45
22. A giant Tesla globe, deep within the Soviet Union in 1979 46
23. Engines disabled, a passenger jet drops six miles in two minutes 47
24. Giant "Woodpecker" beams intersecting over the U. S 48
25. Third Soviet non-destructive testing against shuttle launches Nov. 26, 1985 50
26. Death of the Arrow DC-8, Dec. 12, 1985 52

LIST OF FIGURES

No. Title Page

27. Anomalous hole in the right fuselage ... 52
28. Part of the Soviet engineering of U. S. weather, just prior to the death of the Challenger ... 53
29. Soviet trawler spyship ... 54
30. Launch of the doomed Challenger, Jan. 28, 1986 ... 54
31. Loss of a Delta rocket, May 3, 1986 ... 56
32. Probable Soviet test of a Tesla Shield over Atlanta, Georgia ... 60
33. The riddle of time ... 99
34. Raindrop model of physical change ... 99
35. Phase conjugate reflection of a time-reversed wave ... 107
36. Phase conjugation by four-wave mixing ... 119
37. Soviet launch phase and midcourse strategic defense system ... 120
38. Power reflection coefficients and oscillation ... 123
39. Photons have virtual substructures ... 127
40. Once established, a virtual river is for free ... 129
41. Local energy conservation can be violated ... 130
42. T. H. Moray adjusts the controls of his radiant energy device ... 130
43. Charge affects anything existing in spacetime ... 136
44. Vacuum/spacetime is pure virtual particle flux ... 140
45. A simplified charged particle ... 141
46. A charged particle is a special kind of "spray nozzle." ... 141
47. An observable charged particle is directly connected to virtual particle vacuum flux ... 142
48. In a flux gradient (virtual particle river), a charged particle moves itself ... 143
49. A natural potential is a *disorganized* change in the stress of vacuum ... 143
50. An artificial potential is an *organized* change in the stress of vacuum ... 144
51. Gravitational potential is a conglomerate of stresses, organized or disorganized ... 144

LIST OF FIGURES

No. Title Page

52. EM force fields are releases of gravitational potential via observable charged mass flows 145
53. As beyond (without), so within 147
54. Internested levels of virtual state vacuum interact with neutrino, photon, and mass 147
55. Virtual state patterns are absorbed and emitted by the atomic nucleus 148
56. Nuclei of the universe continually exchange scalar EM waves and virtual particle fluxes 148
57. First order reality 149
58. Higher order (hyperspatial) reality 149
59. A photon is a single oscillation of a carrier wave 153
60. A potential is trapped energy 162
61. A force-field vector is a movement of mass in one direction 171
62. The zero-summed vector system is an engine and an artificial potential 173
63. An analogy for how scalar electromagnetics can engineer Kaluza-Klein unified field theory 182
64. The zero-vector system can engineer Kaluza-Klein theory 182
65. The basic idea of Klein's explanation of where the extra dimension is 183
66. Normal EM bleeds-off G-field 184
67. Scalar EM forces 4-dimensional gravitational field 184
68. The curl-free A-field 190
69. Earth, sun, and moon are locked into a triad system 195
70. Forming magnetic monopoles with a standing scalar EM wave 202
71. Metal fracture by depositing magnetic monopoles 203
72. The Kervran effect 205
73. The Kaznacheyev effect 215
74. A photon is one oscillation of an electromagnetic carrier 215
75. Nested modulations are the key to hyperspatial engineering 216

LIST OF FIGURES

No. Title Page

76. Hyperframes, vacuum, virtual state, minds and thoughts ... 233
77. Internested levels of virtual state vacuum contain mind and thought ... 237
78. The human cerebral cortex is a natural scalar interferometer ... 238
79. Consciousness and life ... 238
80. Life and death ... 239
81. Layers of unconsciousness intersect hyperspatially ... 239
82. Scalar electromagnetics can directly interact with the various levels of human mind and personality ... 240
83. What personality is ... 241
84. Jamming the "older files recall" process produces simple amnesia ... 241
85. To sustain one's personality, continual functioning is required ... 242
86. If the files themselves are changed, the personality itself is changed ... 242
87. The mind and personality can be affected—and changed or controlled—from a distance ... 243
88. The mind and personality are physical things, albeit hyperspatial and virtual ... 246
89. One of Priore's intermediate devices ... 248
90. The large special phase-conjugating plasma tube for Priore's giant device ... 252
91. Capping assembly for the top of Priore's giant plasma tube device ... 253
92. Royal Raymond Rife in his laboratory ... 268
93. Rife's first virus microscope ... 268
94. Side view of Royal R. Rife's prismatic universal microscope ... 269
95. Front view of Royal R. Rife's prismatic universal microscope ... 270

LIST OF TABLES

No. Title Page

1. Interesting Soviet statements 25
2. Microwave radiation of the U. S. Embassy in Moscow 32
3. Khrushchev's 1960 statement 35
4. Death of the U. S. S. Thresher 37
5. Severe EM interference experienced by U. S. S. Skylark 38
6. Massive 1985 strategic May Day exercise 48
7. Shuttle launch anomalies, Nov. 26,1985 51
8. Soviet escalation after 3rd test against shuttle launch on Nov. 26,1985 51
9. Arrow DC-8 disaster Dec. 12, 1985 53
10. Death of the Challenger, Jan. 28,1986 55
11. KGB celebration 55
12. Brezhnev's 1975 proposal 59
13. Symmetry 91
14. A force field is a special local symmetry 92
15. Gravity and local symmetry 92
16. Hindsight is better than foresight 93
17. When symmetry is violated (broken) 93
18. Some proven asymmetries 93
19. Spontaneous symmetry breaking 94
20. Why such drastic difference? 95
21. Aspects of strong local asymmetry 96
22. Flow of time 100
23. Physical change 100
24. Negative energy 101
25. Phase conjugate waves 108
26. Phase conjugate replica 108
27. Distortion correction theorem 108
28. Four-wave mixing 119
29. A zero vector system 135
30. Stress is fundamental 136
31. Vacuum is 140
32. Spin couples vacuum to particle 142
33. Residue universe, residue science 145
34. Reality is a hologram 151

LIST OF TABLES

No. Title Page

35. Physical change 153
36. Ordinary General Relativity (OGR) is a special case 155
37. Maxwell's equations 175
38. Kaluza geometry 181
39. 5-D G-field bleed-off (Kaluza 5-D theory) 181
40. Physical reality is eleven dimensional 183
41. Comparison of EM concepts 188
42. The Aharonov-Bohm effect 189
43. The living aura: The cell's electromagnetic breath 220
44. Lisitsyn's report 243

Chapters 4 and 5
contain complex scientific material
and are suggested for those who are
technically proficient.

FOREWORD

What This Book is About

In my book, **"Fer-de-Lance: A Briefing on Soviet Scalar Electromagnetic Weapons,"** (Tesla Book Co., P.O. Box 1649, Greenville, Texas 75401, 1986), I specifically pointed out that I was of necessity neglecting the biological warfare (BW) aspects. I intended to later write a second book covering the BW aspects.

This book contains the most important item of that planned second book, including the photobiology aspects of BW.

The material is put down in great haste, for it is meant to serve as an urgent warning. There is no time to do the six months additional research and compilation necessary to "flesh it out", sculpture it and meticulously document it, as should be done by a careful scholar.

I apologize to the reader for this lowered standard, but in this case the basic information is far more important than scholarship.

Further, I acknowledge the fundamental contributions of Dr. Robert B. Strecker, M. D., Ph. D., who together with his brother Ted, has for some time urgently called attention to the terrible threat posed by the AIDS epidemic.

I specifically acknowledge his important warning, "This is a Bio-Attack Alert," Mar. 28,1986, which was sent to the U. S. President and Vice-President, Governors of the states, various federal agencies such as Departments of State, Defense, and Agriculture; National Security Agency, Federal Bureau of Investigation, Central Intelligence Agency; and three members of Congress.

Dr. Strecker has also strongly pointed out the covert involvement of Soviet and other communist agents in the epidemic, and the absolute necessity for an *electromagnetic* solution.

Also recognized are the efforts of the other medical scientists, such as Dr. John Seale, M.D., and Dr. Eva Snead, who have tried repeatedly to call attention to the nature of the AIDS initiation, only to have their submitted papers resoundingly rejected by important journals such as New Scientist, **The** Lancet, etc.

Work by Dr. William C. Douglass in alerting the public to the no-nonsense truth about aids is particularly recognized. His monthly newsletter, **The Cutting Edge,** is an oasis of clarity sharply standing out in a sea of misinformation. Permission to reproduce his published research article on UV irradiation of the blood to successfully heal viral infections is deeply appreciated.

The continuing efforts of Dr. Andrija Puharich and Dr. Robert Beck to assist in achieving an AIDS solution are pointed out and recognized. Important contributions by Ed Skilling are also recognized in this regard.

The vital and extensive contributions of Christopher Bird are particularly acknowledged. Chris has unstintingly and unselfishly shared with me the results of his enormous research on the Priore device and affair and the results of his translations from the French. He has most graciously permitted me to publish his important summary of the Priore affair, and I am greatly in his debt. The reader will find that material most illuminating, and well may be shocked at the depth and malevolence of the scientific and political suppression of Priore's rigorously demonstrated electromagnetic cure for cancer, leukemia, and other killer diseases.

Special acknowledgement is made to Robert Whitney, who so nobly labored to bring the Priore technology into the mainstream of medical treatment, only to be ruthlessly suppressed in his efforts. Photographs of the Priore machine were furnished by Bob from his collection.

My special thanks to colleagues John Bedini, Frank Golden, Andrew Michrowski, George Fencl, Ken Moore, Tom McLaughlin, Joe Parrott and Randy Davidson, without whose assistance this project could not have been accomplished.

The material in this present small book is intended to be of any assistance possible to certain brave colleagues who — with little or no funds or resources except what they can tear out with their bare hands — are already laboring around the clock to develop a permanent solution to the AIDS problem.

As a matter of discretion, I shall not mention the names of those colleagues. The solution sought is radical, by orthodox assessment. Yet it is the only possible approach that has any chance whatsoever of succeeding.

What they are doing, I cannot do. If they do not succeed, no one can. But I will say this, and most strongly: In my view, the only hope for humanity lies in the work they are doing, and they have my utmost admiration and support.

Their initial results are exciting and encouraging. Basic phase conjugated electromagnetic "mixed-modulations" signals lethal to bacteria, nematodes (hookworm-like organisms), various amoeba, viruses, etc. at very weak power levels have been synthesized and demonstrated.

In my best estimate/opinion, these researchers must succeed in *two years or less, certainly in no longer than three years,* else the **AIDS** incubation already accomplished by then, and the implementation time delay — even given a cure —together will insure a devastation of humanity unparalleled in all of history.

Let me accent that developing this AIDS cure is far more important than developing our entire arsenal of new military weapons. It is even more important than the development of defenses against the Soviet scalar electromagnetic weapons I detailed in **Fer-de-Lance.** Problems in the Middle East, Korea, and Nicaragua are insignificant compared to the AIDS problem.

Desperate Diseases, Desperate Remedies

Spurred by the looming holocaust of AIDS, and by the strong efforts of my colleagues, I have decided to release specific *information on how to develop electromagnetic healing, essentially against any and all of the "killer" diseases including cancer, leukemia, and AIDS.*



Figure 1. Conventional science cannot do the job.

Unavoidably this also releases a major principle of scalar electromagnetics: what is really going on in phase conjugation. If phase conjugation is truly understood and applied, all the Soviet weapons I have pointed out in **Fer-de-Lance** can be understood, designed and developed.

I'm also releasing specific information on mind and thought that will enable them to eventually be directly detected, measured, and investigated scientifically. Unfortunately, this also will enable them to be technologically manipulated for nefarious purposes.

However, the developing scalar EM technology for the AIDS cure must not be hamstrung. There is no time to apply the standard "Let's classify it!" response. If we do, we'll win the skirmish and lose the war.

As shocking as it sounds, I am convinced that the Soviets have already launched WW III, to the hilt. And it's not at all the kind of war we've been expecting.

There's no time to rail against the Soviets, who have cunningly and in great secret "struck our vitals with the mailed fist." We've been struck in such a way that, *unless we can solve the AIDS problem, in two to three years or less, we are already finished.*

We have been preparing to fight a better World War II. The one we're preparing for is never going to be fought. The real World War III is already raging. Our death knell has been sounded, *and we've not yet even recognized that the battle is underway.*

A great Soviet "first strike to finish us" has already been accomplished. The new "Pearl Harbor" has already happened. The enemy has already overrun our Maginot Line; we are at our Dunkirk. There are no boats waiting, and there are none on the way.

The great Soviet first strike has been delivered with surreptitious biological warfare, not with nuclear weapons or ground forces.

As always in the past, we have almost no troops facing the brunt of the first strike and trying to turn it. This time we have far fewer than we've ever had. Just two or three unorthodox researchers. All the orthodox researchers are manning the wrong ramparts.

Ironically, this time our entire system—the government, the medical establishment, the scientific establishment, the universities — all are far too dogmatic, and have far too sluggish a response time, to offer any assistance at all. They are simply so "out of it" that they don't even know what's really happened.

The bureaucracy simply is so stagnated that, even with a giant paroxysm, it cannot change quickly enough to do the job in time.

The best response the orthodox system could theoretically make —if it immediately placed the nation under martial law, marshalled all the universities and scientists, everything — would require at least seven years to produce results. A more likely response time is 10 to 14 years. That won't do the job.

So the job has to be done from completely *outside* the system. It has to be done with *independent* financing. Financing without a lot of conventional, bureaucratic strings on it. Resources must be committed as needed, immediately, not with a several months' approval process.

Everything in the orthodox establishment simply has to be bypassed.

The government, the medical establishment, the scientific establishment, the universities, everything.

Otherwise, we're as good as finished *right now*.

The "Dirty Dozen"

In the West, there are only perhaps a dozen persons or so that I know of, who are qualified to work on the main task required. They are all unorthodox researchers and scientists.

There are thousands of fine orthodox scientists, of course, who can help with the peripherals — making and testing viral solutions, setting up and operating equipment, doing interminable tests, all the lab stuff, etc.

But only about 12 unorthodox guys are qualified and mentally and emotionally prepared to come to grips with the particular scalar EM technology required for rapid development of an AIDS cure.

Right now, there are just two or three of the 12 working on this, hammering away as best they can, at terrible cost to themselves and their normal endeavors.

Obviously immediate funds are needed for facilities, equipment, and marshalling that dozen unorthodox researchers and a team of scientists — along with support staff and personnel.

An Analogy

I'm reminded of a story from WWII.

On the beach at Anzio, in a battle lull some doughboys were briefly resting near their foxholes, eating lunch from C-ration cans.

A lone German Messerschmitt appeared, closing on them fast and low with machineguns blazing. They were forced to hastily jump into their foxholes as the Messerschmitt strafed their position.

The pilot continued to make strafing run after strafing run, low and "on the deck." Obviously lunch was rather totally disrupted.

Suddenly, in total disgust a soldier leaped up and flung his half-filled C-ration can into the air directly at the approaching aircraft, full in the teeth of the machinegun fire.

Incredibly, the can sailed straight up into the air intake of the hurtling aircraft, where it was sucked into the engine, which sputtered and died.

The surprised German pilot banked his plane upward and bailed out.

He was promptly captured by the very troops he had been strafing only moments before.

Those two or three colleagues of mine are literally "throwing their C-ration cans" in a desperate effort to ward off a monstrous threat.

Those two or three are striving to the limit of their endurance.

This book and the release of the material in it represent my own "Oration can" hurled into the teeth of the actual Soviet threat as a last resort. Hopefully we can "hit the air intake" of the Soviet juggernaut, so to speak, and stop its progress.

The giant Soviet scalar electromagnetic weapons that I detailed in **Fer-de-Lance,** e.g., are easily countered — in six months or less. Primarily, it is necessary to make a pumped phase conjugate mirror adjunct (PPCMA) that operates at the frequency band of interest, and associate it with a receiver. Once a signal is received from the enemy weapon — say, from a Woodpecker transmitter — it is introduced to the PPCMA. A powerful phase conjugate replica energy pulse is returned into the distant hostile transmitter, totally destroying it.

To meet the viral biological warfare weapon, however, we must develop electromagnetic healing.

In an important article, "SDI vs. the plague," Mar. 8,1988, p. 6, the **Washington Times** revealed a startling Pentagon conclusion that the Soviets may counter SDI with genetically engineered weapons.

Valentin Falin, Chief of the Soviets' Novasti Press Agency, is quoted as saying:

> *"We won't copy you anymore: We'll take asymmetrical means with new scientific principles... genetic engineering could be a hypothetical example. Things can be done for which neither side could find defenses or countermeasures, with very dangerous results. If you develop something in space, we could develop something on earth. These are not just words. I know what I'm saying."*

The genetically engineered Soviet counterstrokes exist and are already being taken. This book tells you what the asymmetrical means, new scientific principles, and genetically engineered weapons are.

May God help us all. If we do not move immediately and correctly to augment the effort of my colleagues, the Free World and half of the peoples of the earth will perish before another decade passes.

CHAPTER 1

THE VACCINE CONNECTION

The following quote is from Don Rowe, **Wall Street Digest,** 214 Carnegie Center, Princeton, New Jersey 08540.

"The AIDS Plague will affect society in ways that you cannot now imagine. AIDS is 100% fatal. Scientists and medical research people are not optimistic about an immediate cure to [or] vaccine. They do not expect to develop an effective vaccine within the next two decades. Public health officials estimate that as many as 2.4 billion people (half the world's population) will die from AIDS within the next 15-20 years."

"Economically, the insurance and medical health systems could be devastated in the 1990's. Nothing short of a spectacular medical breakthrough will keep Western civilization from suffering the worst catastrophe in the history of the world."

The first official U. S. AIDS case was diagnosed in San Francisco in 1981. This followed the puzzling outbreak of the disease in Third World areas such as Africa and Haiti in the 1970's.

The U.S. AIDS outbreak at first seemed to be confined to the gay community, such as in San Francisco.

No one seemed to connect the apparently unrelated facts that, before the outbreak in the U.S. gay community, (1) the World Health Organization had accomplished substantial smallpox vaccination in Haiti, and (2) West Coast gays — particularly from San Francisco — had made Haiti a main playground and vacation spot.

Most orthodox medical scientists have not the foggiest notion why such a drastic "explosion" of the virus has occurred.

It has occurred because *AIDS was introduced by contaminated vaccine used by WHO in its smallpox eradication campaign.* A high correlation exists between WHO vaccination and subsequent outbreak of AIDS.

Figure 2. The "monkey-bite" theory.

The "Monkey-Bite" Theory

As the prevailing rationale goes, a naturally-mutated monkey AIDS virus derivative or strain is believed to be the cause of the monstrous plague looming to strike down half of all the humans on earth.

That is, a monkey is supposed to have bitten a man—an African —and transmitted the normally harmless monkey AIDS virus to him. The virus is then supposed to have naturally "recombined" its genetic material with other viral genetic material and the man's human genes, to produce the virulent new strain of AIDS.

Then this new strain, *from its single human host,* is supposed to have rapidly started spreading through Africa and around the world.

That is simply nonsense.

In Africa, for example, monkeys as well as other animals have had their viral diseases for thousands of years. If monkey virus were the culprit, African man would have been devastated by AIDS thousands of years ago. He either would have been dead or—as have the monkeys — he would have developed a certain resistance and tolerance for the disease, so that it is no more harmful than others.

Understand, the "monkey bite plus human cell modification" undoubtedly does occur in Africa with great rarity — once in several thousand years.

However, even if that rare natural recombination of the monkey AIDS virus were to occur in a single human, normal contact between other humans and the infected human is totally insufficient to provide any substantial infection rate *unless the rate of infection of new individuals is greatly assisted and vastly speeded up by some other outside mechanism — for example, by something like AIDS-contaminated vaccine and a mass inoculation program.*

Retroviruses ***and Recombinants***

As Dr. John Seale has pointed out, "The AIDS virus (human immunodeficiency virus or HIV) is a lentivirus — a little-studied sub-family of the retroviruses. It is highly pathogenic to man but it differs profoundly from any other virus of humans. It is spreading rapidly in the general population of central Africa, and amongst homosexual men and drug addicts in the West. *It is the first virus to have appeared in mankind for many centuries which is entirely new, highly lethal, and spreading steadily from person-to-person world-wide."* [accent by the present author.]

Dr. Seale has courageously pointed out some other very disturbing facts:

(1) Retroviruses of animal origin, if repeatedly passed from human cell culture to human cell culture, will gain the ability to infect human cells *preferentially.* Indeed, they may then even cease to be infectious to their original animal hosts.

(2) In 1982 Robert Weiss pointed out that, in the laboratory, the genetic code of retroviruses commonly recombine if two of them infect the same cell simultaneously.

(3) In a 1984 article in the **Journal of Virology,** David Baltimore showed an efficient means of overcoming the cell's block against simultaneous infection by two or more retroviruses.

(4) Further, Baltimore reviewed how *this had widely been done during the preceding ten years!*

(5) Outside the laboratory, recombination of multiple simultaneous retroviruses has not been shown to occur naturally in humans.

(6) In animals, there is some evidence that it may occur naturally with extreme rarity — indeed, only once in many thousands of years.

(7) By the early 1970's, the technology to make new recombinant retroviruses virulent to humankind was already developed and had been widely published.

To the layman, the infection and reproduction by retroviruses is peculiar to say the least.

When a retrovirus infects a cell, from its own genetic material (RNA) it first makes a "template" or pattern (DNA) for forming other retroviruses just like it. It then inserts this "DNA template" into the DNA of a cell. The host cell itself is now a "sleeping factory", ready to start producing retroviruses.

When activated, the "template" in the cell causes the factory to go into production of retroviruses. Activation is varied. The "infection production factory" can just remain dormant, be slowed over years, take place almost immediately, or be slowed for years and then "explode" to rapidly increase the infective viruses.

Genetically, the cells of any person infected with AIDS or any other recombinant retrovirus have been permanently transformed. Literally that person has acquired a new set of genes. He or she has been converted into a "factory" for producing—and spreading—the virus.

Cancer Research Produced Ideal Biological Warfare Agents

In 1971 President Nixon signed into law the National Cancer Attack Act. Though certainly not intended by the President and the Congress, *the inadvertent result of this act was that taxpayer's funds were used to research and develop the precise things that constitute the most lethal kind of viral biological warfare.*

The on-going small effort in medical research laboratories to alter animal tumor viruses — including retroviruses —to replicate efficiently in human cells was drastically speeded up, as part of the new "war on cancer." In other words, whether intended or not, much of our cancer research money was converted into the precise kind of research that develops virulent biological retroviruses for potential use in biological warfare.

Not only was the research drastically accelerated, but also the direct participation by Communists and scientists sympathetic to the communist cause was accepted and encouraged.

Astoundingly, this open invitation to the communist scientists was issued at a time when one of the high KGB priorities was to infiltrate our recombinant DNA genetics laboratories! To the Soviets' utter astonishment, we simply opened our labs and invited them in.

The Soviets participated — and penetrated — with alacrity. It is an obvious conclusion that a number of the Iron Curtain scientists sent to help staff our laboratories were undercover KGB agents.

In the cancer laboratories, on a wide-spread scale, animal retroviruses were injected and reinjected into human cell cultures, until these retroviruses had become efficient, lethal recombinants favoring human cells as their hosts.

At that point, infection of one or more persons by one of these lethal new retroviruses could unleash a massive AIDS-like plague on all mankind.

A single laboratory accident (or a single act by one Communist agent) could unleash the Great Death Plague.

Weak and ineffective reference to this forthcoming danger was made in 1974 by the Committee on Recombinant DNA Molecules, which had been established by the U.S. National Academy of Sciences. According to **Science,** July 26,1974, p. 303, the Committee made the following rather bland and ineffectual recommendation:

"Scientists throughout the world (should) join with the members of this committee in voluntarily deferring experiments (linking) segments of the DNA from (cancer-causing) animal viruses to... possibly increase the incidence of cancer or other diseases."

So much for the great scientific watchdogs.

U. S. "Cancer War" Labs Were Infiltrated

As we said, ironically we ourselves helped load and cock this potentially disastrous biological warfare cannon. Incomprehensibly, enemy fingers were permitted — even encouraged! — to be placed on the trigger. Many of our medical research facilities involved in this research contained known Communists, dissidents, etc.

For example, see page 106 in Omni, March 1986. Carlton Gajdusek, presently Chief of the National Institute of Health's Laboratory of Central Nervous System Studies and Laboratory of Slow, Latent and Temperate Virus Infections, was asked the question, "Isn't Fort Detrick in Maryland such a biological-warfare research facility?" He responded:

> **"No, emphatically no! There is no defensive or offensive warfare microbiology done at Fort Detrick today. It is the national cancer research facility of NIH. In this facility I have a building where more good and loyal Communist scientists from the USSR and mainland China work — with full passkeys to all the laboratories — than Americans. With night-working U. S. citizens and foreign Communist investigators here, obviously there is no "secret" bacterial warfare activity going on. Even the Army's infectious-disease unit is loaded with foreign workers — not always friendly nationals. It is a valid basic research unit on worldwide problems of infectious -diseases in which no classified or secret activities unfold."**

The point is, what was being produced in these labs were viruses that would grow in human cells. Under tight control, these new lethal agents could be safely studied, and many things could be tried experimentally to see if they would slow, stop, or kill the viruses and heal or benefit the virally infected human cell cultures.

The viruses were being developed to benefit man by aiding in the war on cancer — we accent this most strongly.

However, many of them were precisely the same things that would be developed in a biological warfare lab: lethal new viruses that preferred the human as a host, and against which humans have developed little or no immunity.

The Deed Was Easily Done

Now one can see the subtlety and irony in the Soviet Union accusing the U. S. of having made the AIDS virus at Ft. Detrick!

It's both true and false at the same time.

There is substantial information indicating that the AIDS disease is manmade, and has been deliberately unleashed on mankind by Soviet and other Communist agents, augmented by the international control groups and shockingly inept work by U. S. and European medical researchers.

Human cell cultures deliberately infected with animal viruses were carelessly handled in U. S. and European laboratories — carelessly handled in that far too great (essentially open) access to the new viral strains was permitted.

Our own scientists were apparently unwitting pawns, and Soviet agents performed the "final touchups" to insure release — whether intentional or inadvertent — of the lethal new agents against an unsuspecting world.

Viruses can infect bacteria, since a bacterium is a one-celled organism and the virus is a single molecule.

Cell cultures where vaccine is made from weakened bacteria could easily be contaminated with the desired recombinant viruses available in the cancer laboratories.

To insure worldwide release of the lethal virus, covert Communist agents apparently caused contamination of the smallpox vaccine that was prepared in quantity in Western laboratories.

This contaminated vaccine then was widely used to inoculate Third World peoples and others, in the successful international program to eradicate smallpox.

With only a few agents in key places, the Soviets could easily have taken advantage of the looseness of Western laboratory procedures to deliberately contaminate the animal cell cultures used to make the vaccines.

They had an abundance of agents in the key laboratories, for they were openly invited in and accepted!

The Soviets had their fingers in it, up to the elbow.

And at just exactly the right time, the answer to a Communist's biological warfare dream was available: The World Health Organi-



©Hal Crawford 1979

Figure 3. The Soviets have delivered an intended knock-out.

zation was already involved in its 13-year campaign of massive smallpox inoculation in the Third World, to eradicate smallpox.

All that was needed was to contaminate the WHO vaccine by one or more of the lethal new recombinant retroviruses that had been developed — and were continually being developed — in cancer research laboratories filled with Communists agents.

The opportunity was presented for a great Soviet "first strike" against the West, using biological warfare agents developed in U.S. and European laboratories and administered by an international agency.

The opportunity was ripe for the taking. It was irresistible. You can be sure the Soviets took it.

It's Actually Documented!

Virus-contaminated vaccines were then widely administered to Third World countries—particularly in Africa, South America, and Haiti. Administration of these vaccines by the World Health Organization is precisely correlated to the subsequent outbreak of the AIDS epidemics in those countries.

This strongly indicates that the vaccine itself was the "precursor" agent initiating the start of the AIDS infection.

In a shocking article, "Smallpox vaccine 'triggered Aids virus'," in the London **Times** of May 11,1987, **Times** Science Editor Pearce Wright announced that the AIDS epidemic may have been caused by World Health Organization (WHO) smallpox inoculations in third-world countries.

In an important article in **Easy Reader,** June 4, Jon Rappoport reported the **Times** article and the results of an interview with Robert Matthews, technical correspondent of the **Times.**

According to Rappoport, Matthews informed him WHO itself had somehow suspected that its immunization program against smallpox might be connected to AIDS. An outside consultant was employed to perform an independent study, and the study confirmed that WHO vaccines were indeed — somehow — causing AIDS to evidence in inoculated persons.

Needless to say, WHO promptly buried that report—whose conclusion must have been the last thing WHO wanted to hear.

The consultant then came to the **Times.** The **Times** heard him out and printed the story.

This astounding story has almost startling correlations: *"The smallpox vaccine theory would account for the position of the Central African states as the most afflicted countries; why Brazil became the most afflicted Latin American country; and how Haiti became the route for the spread of AIDS, to the U.S.: Brazil, the only South American country covered in the eradication campaign, has the highest incidence of AIDS in that region."*

Rappoport confirms that the subject of contaminated vaccines— "vaccines which, made in tissue cultures of animal parts, contain 'extra' dangerous viruses" — has been of increasingly serious concern to medical scientists in recent years, and the WHO smallpox vaccines may have been contaminated in this fashion.

A documented U.S. Army incident is a case in point.

New U.S. Army recruits are routinely vaccinated against a range of diseases. One of them is smallpox, in case an enemy should try to use smallpox as a biological warfare agent.

A healthy 19-year old Army recruit developed AIDS after vaccination, and was admitted to Walter Reed Army Medical Center, where he died.

In a paper published in the **New England Journal of Medicine,** Walter Reed medical team scientists reported their discovery of the connection between vaccination and stimulated AIDS disease.

They also warned against the WHO plan to use modified versions of the smallpox vaccine to combat other diseases in developing countries.

WHO's 13-year vaccination and eradication program ended in 1980. The program is credited with saving two million lives a year and preventing 15 million infections.

It may be inadvertently responsible for the ultimate death of billions.

In a meeting of 50 experts near Geneva in May, 1987, it was revealed that millions of new AIDS cases are about to hit Southern Africa. The experts believe that up to 75 million Southern Africans — about a third of the population — may have AIDS within the next five years.

From our previous statements above, it appears almost certain that Communist agents who had penetrated U.S. and European laboratories manipulated the contamination of the altered vaccines.

Further, the Soviets may be stimulating the disease and guiding it electromagnetically, by special implanted signals carried by the giant Soviet woodpecker "over-the-horizon radars" and other Soviet transmitters.

Or, the Soviets may be using their own transmitters and ours, including our own power lines and radio and TV stations, to broadcast signals that "precondition" and greatly amplify our population's vulnerability to certain selected diseases — AIDS and otherwise.

We will address these issues and Soviet subtle EM capabilities later.

Soviet Biological Warfare Background

In World War I, the Russians suffered half a million casualties to gas warfare, including 50,000 dead.

At 10,000 troops per light division, that's the equivalent of 5 divisions killed and 45 divisions incapacitated.

This made a deep and lasting impression on the Soviets. Lenin himself ordered a major effort mounted to develop and manufacture chemical and biological weapons, for he understood the implications of such mass-destruction weapons.

In 1919 the Soviets began work in earnest on BW weapons. Work on them has not stopped since then. It will not stop so long as the Communists remain in power.

To loyal Communists, Lenin's dictate to develop and lead the world in biological weapons is absolute and unquestioned.

By 1937, the Red Army was fully equipped and psychologically prepared to wage chemical and biological warfare.

Continuing today, the Soviet forces have the highest training in chemical warfare of any troops in the world. Red Army soldiers practice regularly, often using actual chemical agents. Decontamination is a standard measure and practiced as a matter of course.

Even though the Soviets, along with many other nations, signed the Geneva Protocol of 1925 which banned the use of deadly chemical and bacteriological weapons, the Soviets have never ceased development of such weapons.

In the 1930's, a secret Soviet bacteriological institute was set up at the town of Suzdal. Prisoner microbiologists worked on a variety of new weapons and vaccines, including bubonic plague and tularemia (rabbit fever). By World War II the Soviets were prepared to retaliate vigorously to any use by the Germans of chemical and biological warfare agents.

After the war, Soviet research and development in chemical and biological weapons continued apace. However, much of the genetic work was hampered by Stalin's stern support of the autocratic control of agronomist Trofim D. Lysenko. Lysenko's crackpot theories on genetics, for example, held that genes did not even exist. After the death of Stalin, Lysenko's work was discredited, and the Soviets set forth immediately to "catch up" with the West in genetic implications such as recombinant DNA techniques.

Thus in the early 1960's the Soviets began sending Russian scientists to the West to catch up with Western genetics research. One of these scientists was David Goldfarb, who later became a leading Soviet expert in the field of molecular genetics. He headed up the Laboratory of Molecular Genetics of Bacteria and Bacteriophages of the Soviet Academy of Sciences in Moscow. Although he did not work on secret Soviet projects, the Soviet authorities stopped him cold when he applied for a visa to leave in 1979. Goldfarb was a specialist in plasmids, antibiotic resistances, and recombinant DNA technology—all very, very useful to the Soviet effort in biowar.

One can readily understand the reluctance of the authorities to release scientists such as Goldfarb. After all, the Soviet "dirty work" with the deliberate AIDS contamination of the World Health Organization's smallpox vaccine had already been accomplished and a great Soviet biological warfare "strike" was already underway, thanks to the massive smallpox vaccination program of WHO.

In 1972, in the Biological and Toxin Weapons Convention, the Soviet Union and every major power agreed not to develop or use biological weapons. The agreement went into effect in 1975. Although it bans the development, production, and stockpiling of biological agents and toxins for hostile purposes, it has not slowed or altered the Soviet program.

In the early 1970's, Soviet leaders made a decision to use genetic engineering to produce new and improved BW weapons. Highly secret institutes for this purpose were set up in Moscow, Leningrad, and Novosibirsk. These laboratories specialize in seeking ways that genetic engineering techniques can be used to develop virulent strains and agents that their opponents cannot resist.

Every Soviet civilian institution dealing with bacteriology and epidemiology is responsible for certain military work as well. The Soviet Academy of Sciences in fact funds appreciable research of such nature at these institutions.

One of the major Soviet centers for recombinant DNA techniques in biological weapons research is in the village of Protvino, near Moscow. Research on chemical and biological weapons is very easy to conceal, and the Soviets are sure that they will not be caught. Satellites cannot detect what is going on in the labs. The payoff is big and the risk is minimal. The Soviets push this area vigorously.

A number of installations capable of producing disease agents and toxins on a large-scale basis and placing them in munitions and delivery systems have also been identified. One such facility is in the city of Sverdlovsk and has a long history of BW research and development and production, with emphasis on anthrax. During early April 1979, an accidental release of anthrax occurred in Sverdlovsk that caused many casualties and deaths in spite of heroic efforts by Soviet doctors and cleanup and decontamination crews.

Note that, according to DoD's 1987 edition of **Soviet Military Power,** page 110, *"Anthrax causes a high mortality rate when the infection results from ingestion (up to 70 percent fatal) or inhalation (almost 100 percent fatal) if treatment is not promptly begun."*

In addition to military BW institutes, military officers and KGB agents are assigned to key posts in the Soviet Union's normal health and science ministries to monitor research and development that has possible military significance.

Also, the KGB has a continuing and highly active program to insert recruited Soviet Scientists in Western genetic research institutes and agencies. This is a high priority effort, and it has been very successful. Also, it obviously says something about the probability of Soviet agents penetrating U.S. and Western European cancer research institutes, particularly those using recombinant DNA techniques. To make it even worse, we simply invited them in with open arms!

Indeed, it was that KGB program plus the "open arms" in Western cancer virology research institutes that enabled the Soviets to set up and bring about a massive "first strike", using WHO and Western laboratories to do the actual dirty work unknowingly.

We ***Need An Immediate, Full Scale Investigation***

Annually, President Reagan makes a report to the U.S. Congress on the subject of Soviet noncompliance with Arms Control agreements.

In April, 1984 Defense Secretary Caspar Weinberger put it this way:

> *"There is an apparent effort on the part of the Soviets to transfer selected aspects of genetic engineering research to their biological warfare centers... Soviet research efforts in the area of genetic engineering may also have a connection with the biological program...Normally harmless, non-disease-producing organisms could be modified to become highly toxic or produce diseases for which an opponent has no known treatment or cure. Other agents, now considered too unstable for storage or biological warfare applications, could be changed sufficiently to be an effective agent."*

At the time that Secretary Weinberger made this statement, a devastating biological warfare strike using those exact techniques had already been unleashed on the Western world by the Soviet Union, cleverly disguised under the banner of the World Health Organization's smallpox vaccination program.

It is imperative that the Congress of the United States launch a full investigation of the entire background of the AIDS biological warfare strike, as a matter of the highest priority.

The investigation should include the role of the Soviet Union, fellow-travelers, and Western scientists openly sympathetic to the Soviet cause.

It requires little investigation to see that there is a well-marked trail for several decades, showing that such a biological warfare strike against humanity has long been considered — and even preferred — by those advocating the Communist cause and world domination.

For example, Bertrand Russell, philosophical spokesman for a group of Westerners, explicitly stated this diabolical BW capability for consideration, in his **Impact of Science on Society:**

> **"At present the population of the world is increasing at about 58,000 per diem. War, so far, has had no very great effect on this increase, which continued throughout each of the world wars... War has hitherto been disappointing in this respect... but perhaps bacteriological war may prove effective. If a Black Death could spread through the world once in every generation, survivors could procreate freely without making the world too full. The state of affairs might be**

unpleasant, but what of **it?"**

The blood of every American — and every European, African, and Asian — should curdle at such words. We are now facing the very "Black Death" type of plague referred to by Russell in such glowing terms!

Highly influential followers of the Russell philosophy — and his callous approval of the periodic slaughter of much of the world's population — may have continued to view the great destructive power of new viral warfare agents as the best means to achieve their end: Selective thinning of the world's population.

At least a few such men may have continued to cooperate with the Soviet Union to work powerfully behind the scenes in international organizations, trying to arrange the proper opportunity to achieve their nefarious purpose.

The "East-West cooperative effort" in cancer research created and gave them the precise biological agent custom-made for the job.

WHO's massive, worldwide smallpox inoculation program gave them the precise means to rapidly get the deadly virus into enough human veins to assure a new "Black Death."

All that had to be done was surreptitiously contaminate the vaccine — the easiest thing of all.

This plague has been knowingly, with malice aforethought, unleashed upon mankind. The perpetrators should be hounded down like the wild beasts they are, uncovered in the full light of day, and suitably punished with the swift and sure justice they deserve.

At least one outstanding medical consultant had the courage to report to WHO that their vaccine was generating the AIDS epidemic. When WHO suppressed the evidence, the London Times had the courage to print the story.

I strongly urge every U.S. Senator and Congressman to introduce and/or support immediate legislation that would launch a full-scale, massive investigation, with no stone left unturned. I urge every concerned activist to demand and support such an investigation at the highest level.

By preoccupying ourselves with lesser things — "IranGate," Nicaragua, the Middle East, etc. — we are simply fiddling while Rome burns.

CHAPTER 2

THE SOVIETS KNEW THE U.S. WOULDN'T REACT

Administering the Coup-de-Grace

As we've seen, the present AIDS viruses were deliberately created in Western cancer research laboratories strongly penetrated by Communist scientists and Soviet agents.

In laboratory experiments that were a legitimate and vital part of the war against cancer, animal retroviruses were repeatedly injected into human cell cultures until they recombined to produce **strains** hostile to human life—strains that would thus live in human cell cultures.

Even though their work was accomplished for a totally different purpose, cancer laboratories produced the ultimate, made-to-order biological warfare agents.

The World Health Organization (WHO) is also strongly penetrated — and even controlled at some levels—by communist agents, **as** are many other such international agencies.

And WHO's massive smallpox vaccination program in Third World countries provided the Soviets a made-to-order opportunity to have (ostensibly) "someone else" deliver the actual BW strike.

In other words, the Soviet deception plan was complete.

It was very simple for Soviet agents to contaminate the cultures in which smallpox vaccine was being produced for WHO's inoculation campaign. This insured the production ofvaccine contaminated with AIDS viruses, and the subsequent massive infection of the African peoples and other Third World nations.

It delivered what will be the knockout punch against the West, unless AIDS is countered.

Table 1. Interesting Soviet Statements

"WE HAVE A NEW WEAPON, JUST WITHIN THE PORTFOLIO OF OUR SCIENTISTS, SO TO SPEAK — SO POWERFUL THAT, IF UNRESTRAINEDLY USED, IT COULD WIPE OUT ALL LIFE ON EARTH."

NIKITA KHRUSHCHEV,
1960, SPEAKING TO THE PRESIDIUM

"WE WILL BURY YOU!"

NIKITA KHRUSHCHEV,
TO RICHARD NIXON, "KITCHEN" DEBATE

"IF A MEANS OF TOTAL NEUTRALIZATION OF FOREIGN MISSILES IS TO BE FOUND, IT CAN ONLY COME FROM *A GROUP OF NEW PRINCIPLES IN PHYSICS, CALLED ENERGETICS!"*

NOBELIAN PETER KAPITSA, TO NIKITA KHRUSHCHEV

"EACH SIDE SECRETLY DEVELOPS NEW MEANS OF WARFARE IN ORDER TO EMPLOY THEM UNEXPECTEDLY. HISTORY KNOWS MANY EXAMPLES HOW THE EMPLOYMENT OF A NEW WEAPON INITIALLY GAVE CONSIDERABLE SUCCESS BECAUSE THE ENEMY, CAUGHT UNAWARES AND NOT KNOWING THE COMBAT CAPABILITIES OF THIS WEAPON, WAS FOR SOME TIME INCAPABLE OF EFFECTIVE COUNTERACTION."

V.YO. SAVKIN, THE BASIC PRINCIPLES OF OPERATIONAL ART AND TACTICS. MOSCOW, 1972.

"OF PARTICULAR IMPORTANCE IS BASIC RESEARCH AIMED AT DISCOVERING STILL UNKNOWN ATTRIBUTES OF MATTER, PHENOMENA, AND THE LAWS OF NATURE, AND DEVELOPING NEW METHODS FOR THEIR STUDY AND USE TO REINFORCE THE STATE'S DEFENSE CAPABILITY."

PORTION OF A BOOK BY MARSHALL GRECHKO
DELETED FROM ENGLISH TRANSLATION, BY SPECIFIC REQUEST OF THE U.S.S.R.

"WILL SHORTLY SEE DEVELOPMENT OF NEW WEAPONS, MORE POWERFUL THAN NUCLEAR WEAPONS, AND THEY WILL BE NONVERIFIABLE."

LYSENKO (FIRST NAME UNKNOWN)
USSR REP/SOVIET EMBASSY WASHINGTON, D.C.
WORLD FURTURESCONFERENCE, WASH. D.C, 20 JUL 82.

Murky "Behind-the-Scenes" Intentions

As was pointed out, the WHO inoculation program is well-correlated as the precursor or "initiator" of the AIDS epidemic.

Where WHO smallpox vaccination occurred, the mysterious symptoms of AIDS disease appeared in due time.

Even the eventual spread of the AIDS virus to the U.S. homosexual community is explainable.

For example, the economy of Haiti had earlier been made a shambles. The poor citizens of that impoverished island had been reduced to desperate straits.

In desperation many younger Haitian males had begun to prostitute themselves to visiting homosexual tourists. The Haitian males were not homosexual themselves; rather, they were desperate to gain money to provide for their starving families.

In response, U.S. homosexuals — particularly from San Francisco and New York — had made Haiti their vacation playground. They even ran ads to this effect in their gay newsletters and mngazines.

WHO then vaccinated some 15,000 or so Haitians against smallpox, using the vaccine contaminated with the AIDS virus. This introduced AIDS into Haiti and into the Haitians.

The U.S. homosexuals quickly picked up the AIDS virus by direct contact, and brought it back to the U.S. with them. There the nature of the activities engaged in by homosexuals was responsible for enhanced spread of the virus among members of the homosexual community.

Engineering the AIDS epidemic appears to have been a collusion between Communists and the international control groups.

Apparently the control groups wished to "clean out the African continent and other Third World areas" — possibly to provide room for relieving population pressure in the developed countries. This may have been seen as the way to solve the problem of the ballooning human population — the so-called "biological time bomb."

The Soviets, however, realized that contamination of the smallpox vaccines would result in an epidemic of unparalleled proportions. They recognized the opportunity for safely initiating — and winning — World War III with a great first strike.

The Soviets themselves already possess an electromagnetic cure for diseases such as AIDS, but they have not unveiled it.

All such products of scalar electromagnetics (which the Soviets call energetics) are held tightly by the KGB.

That the Soviets have kept such a cure secret strongly implies that they regard it as a known antidote for biological warfare agents, and thus highly classified.

The importance of this can easily be seen: Presently the West has absolutely zero defense against a biological warfare strike using viruses as BW agents.

In such a strike, fast-acting viral strains can easily be used — say, agents which are highly infectious and kill within two or three days.

Development of a vaccine is impossible. There is simply no time to do that. Further, even if the virus was slow-acting, a vaccine could only be developed if the virus is stable. If it is unstable (constantly mutating), development of a vaccine is impossible.

The greatest vulnerability of the U.S. today is its total vulnerability to unknown BW viral agents. Absolutely nothing we have or are doing in our Department of Defense is of any consequence or protection against new BW viruses for which no vaccine is developed or possible.

The great ease with which such cheap new, highly lethal viral BW agents can be developed means that even a relatively small military power—such as Libya, Cuba, or Iran—can develop and use them against the U.S.

Such BW viral agents can also easily be clandestinely planted across the U.S., to devastate an unsuspecting, unprotected American populace.

In fact, even a single deranged madman can readily develop lethal BW viral agents sufficient to devastate even a great military power. Further, in an open society such as the U.S., that same madman can easily introduce such an agent he develops — and, if he's clever, not even get caught in the act.

Past isolated cases of "contamination" of on-the-shelf drugstore medicines is just a faint prelude of that which is to come.

Indeed, we may unwittingly do it to ourselves by accident, even without a BW strike by the Soviets, small enemy powers, or a madman.

Throughout the West, it is now most fashionable to experiment with the production of new bacteria and viruses. Gene-splicing, rccombinant DNA genetics, etc. are being employed on a grand scale as the latest "scientific marvel."

Even some high school students have experimented with this sort of thing. Many other colleagues, universities, and private persons are proceeding full-tilt with casual experiments.

Most of this "casual experimentation" is uncontrolled. When finished, the residue gets dumped in the trash can or flushed down the drain. In any case, it goes into our biosphere. Some of this residue contains unstable, highly adaptable viruses.

It's only a matter of time until one of these unwitting agents gets loose and survives — one that's lethal, fast, and highly infectious.

Make no mistake: It's a *near certainty* that this will happen. The only question is *when.*

Also, with the recent Supreme Court decision allowing the patenting of a virus or bacteria, a number of laboratories and companies are now feverishly developing new agents to unleash in the biosphere upon persons, animals, and plants.

For the most part, these experiments are tightly controlled. However, it is impossible to test in the laboratory the result of the natural recombination and mutation of these agents once they are loose in the environment and in a free exchange with all the natural bacteria and viruses.

Once loosed in the biosphere, a new viral agent undergoes combinations and recombinations with the greater number of viruses already present. The situation is like an increase in a large factorial number: Only a few additional viruses will result in millions and millions of additional combinations — at least some of which inevitably will be lethal and quick-acting. This is *not* tested in those laboratories making, patenting, and releasing new viruses.

Humans have spent millions of years developing sufficient immunity to the natural BW agents to allow humanity to survive.

Very shortly we are going to have increasingly large numbers of new environmental BW agents emerging all around us. For some of them, it is a foregone conclusion that we have little or no natural immunity developed.

So we are going to enter an increasingly harsh environment, characterized by the rise of great epidemics and pandemics of many kinds.

Inevitably some of these coming scourges are going to rival the "Black Death" in ferocity and lethality.

Effective defense against one or more **such BW viral attacks — either against our forces in the field or against our civilian population — can only be provided by a ready, fully developed technology of electromagnetic healing.**

It does not really matter whether the BW strikes are performed by a hostile foe, a madman, natural mutations within our now drastically stimulated viral environment, or as a result of some particular "residue" discarded by an enthusiastic high school or college student.

The end result — the decimation of humankind — is going to be the same unless we develop and use electromagnetic healing technology.

However, with the present enormously self-hostile state of mankind, one or more enemies or madmen will almost certainly launch a strong, clandestine BW strike against the United States Armed Forces and the U.S. populace.

With EM healing technology, a specific "antidote" to any viral disease — known or unknown **— can be developed in a matter of hours.**

Mass electromagnetic treatment can then be started immediately, even for an entire army in the field or for our population in the heartland. Within hours of recognizing a BW strike, cure rates above 90% can be quickly achieved in exposed personnel.

Further, using electromagnetic healing technology, if necessary a more conventional vaccine can also be rapidly developed — say, in two weeks — for mass distribution and inoculation of the civilian populace.

The bottom line is this: Neither the U.S. Armed Forces nor the U.S. civilian populace can or will survive the coming lethal viral warfare strikes unless we quickly develop electromagnetic healing technology and have the necessary diagnostic and treatment devices already ready and waiting.

The clandestine AIDS strike by the Soviet Union is just the precursor of a great deal more to come.

The USSR Has Repeatedly Verified Our Nonreaction

The Soviet Union already knows that Western science and governments are too stereotyped and dogmatic to react to anything highly unorthodox.

For years, the Soviet have been proving this, over and over, in their development and testing of frightful scalar electromagnetic superweapons of unprecedented power. In the face of overwhelming evidence of this, the West has kept its head buried in the sand like an ostrich.

It wasn't invented in the West. Therefore it cannot be.

Years of substantial Communist indoctrination of students in our universities, by leftist/liberal professors, has placed a massive imprint into our society. An entourage of sympathetic groups has resulted — groups which believe that the Soviet leaders are just like us, that the Stalinist era is long since over, and that the Communist leopard has changed its spots and really isn't trying to take over the world anymore.

As a system, then, much of the West simply refuses to accept anything unorthodox, anything "not invented here", and anything that indicates Soviet aggression.

The Soviets know the U.S. is totally ignorant of advanced scalar EM weaponry. They have proven over and over that the U.S. will not even comprehend that it has been deliberately struck, if the strike is sufficiently unorthodox.

The Soviet scalar EM superweapons have already been documented in **Fer-de-Lance,** Tesla Book Company, 1986, and that documentation will not be repeated here.

Only a short summary of events will be presented, to put the Soviets' confidence into perspective. A longer chronology of selected events is included as Appendix IV.

31 Soviets Knew The U.S. Wouldn't React

The Soviets were quite confident in arranging for a great biological warfare strike, because of the total lack of the U.S. to comprehend incidents such as the following:

1. Beginning in the late 1950's, hidden Soviet transmitters across the street targeted "weak microwave radiation" against the U.S. Embassy in Moscow. Over the years the radiation continued, sometimes continuously, sometimes intermittently. The Soviets electronically induced diseases that resulted in extensive health problems of Embassy personnel, the death of two U.S. Ambassadors, and the sickness of a third. Several U.S. Presidents have protested the radiation. Both U.S. Intelligence and the U.S. scientific community have been totally baffled. They still do not know the true nature of the radiation, nor its purpose.

2. In the winter of 1957-58, an unexplained nuclear event happened near Kyshtym, within the Soviet Union. A huge explosion occurred in the stored nuclear wastes in the disposal section of the Soviet atomic weapons industry located in the southern Urals. Radioactive contamination covered 1,000 square miles. For years the story was opposed — or suppressed — by U.S. intelligence agencies, perhaps to allay public resistance to the U.S. nuclear industry. At the time, Soviet experimentation with large scalar electromagnetic transmitters was well underway. A large transmitter probably failed, discharging its built-up, giant electrogravitational potential (EGP) into the earth. Such a pulse would have propagated through the earth as a wave; the first nuclear material contacted would have been fissioned immediately. The stored nuclear wastes probably exploded due to receipt of an EGP from the inadvertent failure of one of the Soviet Union's new superweapons in development. Survivors reported that indeed the nearby nuclear wastes exploded.

3. In January 1960 Khrushchev announced to the Presidium that a new fantastic weapon was in development. He stated that the weapon was so powerful that, if unrestrainedly used, it could wipe out all life on earth.

Figure 4. The U.S. Embassy in Moscow. The Soviet Union has bombarded this **facility** with weak microwave radiation for decades.

Table 2. MICROWAVE RADIATION **OF THE U.S. EMBASSY** IN MOSCOW

- **SINCE 1959 OR 1960**
- **HIGH LEVEL TARGET (U.S. AMBASSADOR)**
- **GUARANTEES PERSONAL ATTENTION OF**
    - **PRESIDENT**
    - **NSA, CIA, DIA**
    - **TOP CONSULTING SCIENTISTS**
    - **STATE DEPARTMENT**
    - **LEADING SCIENTIFIC INSTITUTIONS**
    - **NATIONAL SECURITY COUNCIL**
    - **ETC.**
- **TWO AMBASSADORS DIED, ANOTHER SICKENED**
- **U.S. REACTION REVEALS ANY KNOWLEDGE OF TESLA ELECTROMAGNETICS**
- **FOUR U.S. PRESIDENTS REQUESTED SOVIETS TO CEASE**
    - **CUT FROM 18 WATTS/CM^2 TO 2**
    - **THEN AGAIN INCREASED**


ORDINARY DECAY
• EGP MUST BE LARGE ENOUGH
• EGP MUST BE LONG ENOUGH
Δt
Δt
Δt
DECAY
ϕD
POTENTIAL
ϕ̄N
ϕ̄V
t→
ϕD = DECAY THRESHOLD
Δt = THRESHOLD BREACH TIME REQUIRED
ϕ̄N = AVERAGE POTENTIAL OF NUCLEUS
ϕ̄V = AVERAGE POTENTIAL OF AMBIENT VACUUM

Figure 5. Decay of a radioactive nucleus. When it absorbs a scalar EM wave (electrogravitational pulse) that is long enough and large enough, the nucleus fissions.


Δt
DECAY
ΦD
POTENTIAL
Φ̄N
Φ̄V
ΦV(t)=Φ̄V+ΔΦEGP(t)
ΦV(t)= AN INCREASED POTENTIAL OF VACUUM
ΦD = DECAY THRESHOLD
Δt = THRESHOLD BREACH TIME REQUIRED
Φ̄ = AVERAGE POTENTIAL OF NUCLEUS
Φ̄V = AVERAGE POTENTIAL OF AMBIENT VACUUM
ΔΦEGP(t)= CHANGE IN VACUUM POTENTIAL DUE TO ABSORBED EGP

Figure 6. EGP fission of a radioactive nucleus. If an initial EGP is large enough and long enough, it will fission any and all radioactive nuclei it strikes.


G–POTENTIAL
GIANT STANDING WAVE
SCALAR EM WAVE
SCALAR EM TRANSMITTER
POTENTIAL OF AMBIENT VACUUM
ϕ_{WAVE}
BIAS NO. 2
ϕ_{XMTR}
BIAS NO. 1
ϕ_{GND}
$(\Delta\phi)_1$
$(\Delta\phi)_2$

Figure 7. Bottled up energy in a standing scalar EM wave is a potential.


G–POTENTIAL
SCALAR EM WAVE
GIANT STANDING WAVE
MODIFIED RADAR
EGP
NUCLEAR WASTE

Figure 8. EGP short-out Transmitter failure and consequent discharge of a giant standing scalar EM wave potential caused the explosion of stored nuclear wastes at Kyshtym, USSR, in the winter of 1957-58.


TAIL–END
ESCAPED AND
DISCHARGED
SAFETY
CIRCUITS
CHERNOBYL
NUCLEAR REACTORS
EGP
GIANT STANDING
SCALAR EM WAVE
MODIFIED
RADAR
STORAGE
CELLS
SLOW DRAIN FIELD

Figure 9. EGP initiation of the Chernobyl event. Failure of another giant transmitter near Chernobyl in 1986 eventually caused the eruption of one of the Chernobyl reactors by EGP-pulsing its nuclear fuel rods. When the transmitter failed, the alarmed Soviets shut down the four Chernobyl reactors while waiting for drain-off of the EGP potential by the safety circuits of the disabled transmitter. These circuits finally gave way, producing a mild EGP pulse into the earth. Had they failed immediately, all four reactors at Chernobyl would have violently exploded.

Table 3. KHRUSHCHEV'S 1960 STATEMENT

(Speaking to the Presidium)

WE HAVE A NEW WEAPON,
JUST WITHIN THE PORTFOLIO OF
OUR SCIENTISTS...
SO POWERFUL THAT,
IF UNRESTRAINEDLY USED,
IT COULD WIPE OUT
ALL LIFE ON EARTH!

4. In May 1960 Gary Powers' high-flying U-2 spy plane was mysteriously disabled over the Soviet Union, resulting in its subsequent crash and the Soviet capture of Powers himself. A flash appeared behind Powers' aircraft, as if from an explosion — except that *the flash persisted,* showing that it was not a normal HE explosion at all. A tracking radar, employed in a scalar EM mode, probably was used to cause the electromagnetic "flash ball" and disable Powers' aircraft. Harmless SA-2 missiles fired far below him may have been employed to deceive Western intelligence analysts.

Figure 10. The U-2 high altitude reconnaissance aircraft. On May 2,1960 Francis Gary Powers high flying U-2 spyplane was disabled over the Soviet Union. Some difficulties with the autopilot were first experienced. Then a single dull thump was felt, and a tremendous orange flash lit the cockpit and sky — *and persisted.* (See Francis Gary Powers with Curt Gentry, **Operation Overflight,** Holt, Rhinehart and Winston, 1970, p. 82.)

5. In April 1963 the Soviet Union utilized a newly deployed scalar EM weapon to destroy the submerged U.S.S. Thresher nuclear submarine, off the coast of the U.S. itself. In spite of intense and totally anomalous electronic jamming experienced by the U.S.S. Skylark, surface companion to the Thresher, the U.S. failed to recognize this major indication of a scalar EM attack. *One day later, a Soviet scalar EM weapon placed a giant*

underwater burst in the ocean, 100 miles north of Puerto Rico. With these two tests Khrushchev, still smarting from his Cuban Missile Crisis facedown by John Kennedy, avenged himself and convinced the Presidium to allow him to remain in power for yet awhile.



Figure 11. The U.S.S. Thresher disintegrates. © Hal Crawford 1979

Table 4. DEATH OF THE U.S.S. THRESHER

APRIL 10, 1963

- **DURING TRIALS OFF EAST COAST OF U.S. IN ATLANTIC**
- **SURFACE COMPANION: U.S.S. SKYLARK**
- **UNDERWATER PHONE BETWEEN THE TWO**
- **THRESHER DIVED AND WAS LOST**
    - **GARBLED MESSAGE**
    - **DID NOT RESPOND TO CONTROLS**
    - **SANK TO CRUSH DEPTH**
    - **IMPLODED**
- **SKYLARK ENCOUNTERED SEVERE ELECTRONIC INTERFERENCE**

Table 5. SEVERE EM INTERFERENCE EXPERIENCED BY U.S.S. SKYLARK

APRIL 10,1963

- **SKYLARK JAMMED (1.5 HR TO TRANSMIT MESSAGE)**
- **MULTIPLE SYSTEMS**
- **SIGNATURE:**
  - **SCALAR INFEROMETRY**
  - **SKYLARK IN "SPLATTER" ZONE**
  - **THRESHER PROBABLE TARGET**
- **OTHER SYMPTOMS**
  - **ONE SYSTEM KNOCKED OUT**
  - **OTHERS THEN WENT OUT**
  - **LATER RESUMED WORKING**

6. In Afghanistan, in 1981 and at intervals since then, Soviet helicopters have sometimes attacked Afghan guerrillas or villages with a strange new weapon. A body struck by this weapon dies instantly and completely. It falls like a limp rag, **and** does not decay even in 30 days. Every cell, bacterium, virus, etc. in the body has been killed instantly. Nerve gas rockets and chemical rockets are also usually fired to provide **a** "deception cover" for the nature of the real weapon. This eery Soviet weapon has been mislabeled as some strong new gas, **and** is referred to as "Smirch", a combination of the two words "smert" (death) and "semerch" (sandstorm).

7. In April 1984 a monstrously huge scalar EM incident occurred off the coast of Japan, near the Kuriles. Subsequent interviews with the pilots sighting the incident have revealed that several combined tests of the various modes of a scalar EM howitzer occurred. A giant "cold explosion" occurred, raising a giant mushroom cloud to over 60,000 feet and greater than 150 miles diameter in two minutes. A glowing dome appeared, and expanded to monstrous size. According to Dr. Walker and colleagues, **the diameter of this great** glowing, **hem-**

ispherical **shell expanded to several hundred kilometers.** * He and his colleagues were able to rule out any possible known natural events or mechanisms that could have caused the incident.

8. Numerous incidents of hemispherical shells of light and giant balls of light within the Soviet Union have been seen from Iran and from Afghanistan. Such giant artificial phenomena have also repeatedly been seen over the oceans by mariners and airline pilots.

9. Several instances of anomalous disabling of jet engines of commercial airliners have occurred while the aircraft were in flight.

10. Direct and intensive weather engineering over the U.S. itself has been accomplished by the Soviet Union for a decade, using the interference grid resulting from the crossing of two or more giant beams from the woodpecker "over-the-horizon radar" transmitters. Specific cloud signatures (anomalous holes, giant radials, twin giant radials, and razor-sharp giant interference patterns) have continually occurred, but the orthodox system has blithely ignored them.

11. A giant test of over a hundred huge Soviet scalar EM weapons occurred in and around May 1, 1985 for the 40th anniversary of the end of WWII. The entire Western scientific and intelligence establishment remained sublimely unaware of the giant exercise. They had not a single scalar EM signal detector — even though the air, land, and ocean was filled with hundreds of Soviet scalar EM transmitters, chattering away to Soviet armed forces, submarines under the water, etc. Underneath our feet, the earth itself was in giant scalar EM resonance on 54 frequencies — 27 pairs, each of which tapped energy directly from the molten core of the earth and fed it to an ensemble of giant Soviet strategic scalar EM weapons.

*See Science, 227 (4584), Feb. 8, 1985, p. 607-611; Science 234 (4775), Oct. 24, 1986, p. 412-413.


INSTANT DEATH
BODIES DO NOT DECAY, EVEN IN 30 DAYS

Figure 12. Soviet helicopters have used a "death ray" in Afghanistan.


160 MI. DIA.
200 MI. FROM TOKYO
SOUTH OF KURIL ISLANDS
5:14 a.m. PST
9 APRIL 1984

Figure 13. Mushroom cloud from the sea off Japan, near a Russian test area.



©Hal Crawford 1981

Figure 14. The Tesla shield, a giant hemispherical shell of energy. Seen repeatedly in Soviet tests in out-of-the-way places and remote regions of the ocean.



8:15 PM
THURSDAY
AUG 1969
VIRGIN ISLANDS
SEEN BY MANY RESIDENTS

SMOOTH, CURVED EDGE
FAINTLY LUMINESCENT
NORTH

Figure 15. The Tesla shield: A 1969 Virgin Islands incident.


MARINE OBSERVER 32:64, 1962
1800 GMT
JUNE 1, 1961
INDIAN OCEAN
VERY BRIGHT ARC
10 MIN LATER,
2nd (DIMMER) ARC
APPEARED
150°

Figure 16. Tesla shields: Two nested arcs of light in the sky.

MAR 20, 1968
AND WESTERN
NORTH ATLANTIC

MARINE OBSERVER 40:17.1970



- **SEMICIRCLE**
- **MILKY WHITE LIGHT**
- **QUITE BRIGHT AT FIRST**
- **DIMMED AS ENLARGED**
- **LASTED 10 MINUTES**

Figure 17. Tesla shield: An expanding hemispherical circle of light.


0855 GMT
21 MAR, 1977
23°05' N; 17°25'W
M.V. KINPURNIE CASTLE
(NOT TO SCALE)
SECOND LUMINOUS PATCH
MODERATELY LUMINOUS HEMISPHERE FORMED
FOR 10 SECONDS, SEARCHLIGHT SHINED DOWN
BRIGHT LUMINOUS PATCH (1° DIA)
(3 MIN TO FORM)
30°
DISAPPEARED AFTER 10 MINUTES
90°
MARINE OBSERVER, 48:21-22, 1978

Figure 18. Tesla shield: Hemisphere and globes, 1977.



Figure 19. Large Tesia Shield observed by Red Chinese fighter pilots. Electrical difficulties in the aircraft were also experienced.



Figure 20. Large glowing Tesla Globe," Red China. Observed by hundreds of **persons.**

45 Soviets Knew The U.S. Wouldn't React



©1980 Hal Crawford

Figure 21. 1966 test of giant Tesla Globe, expanding deep within the Soviet Union. Seen from Teheran, Iran June 17, 1966 by two aircraft approaching Mehrabad Airport. Observed for several minutes.



Multiple events seen in Sept. 1979 from Afghanistan

Strange lurid glow that flared silently over the Hindu Kush; as described by
Nick Downie.
The LONDON SUNDAY TIMES, 17 August 1980

Figure 22. A giant globe, deep within the Soviet Union in 1979. Seen several times frorn Afghanistan, looking toward Saryshagan.


CHINA AIRLINES FLIGHT 006
-TAIPEI TO LOS ANGELES-
19 FEB 1985
41,000 FT
UPPER LEVEL
TROUGH;
TURBULENT
POCKET
1 ENGINE FAILS.
OTHERS REDUCE,
THEN FAIL
LANDING GEAR
DOWN, DOORS
TORN OFF
11,000 FT
ENGINE
RESTART
SAN
FRANCISCO
9,000 FT
RECOVERY

Figure 23. Engines disabled, a passenger jet drops six miles in two minutes.



Figure 24. Giant "Woodpecker" beams intersecting over the U.S. Used for weather control, as a launch phase ABM and anti-bomber system, electromagnetic attack of distant populations, and disease conditioning. Using phase conjugate radar mirrors, any amount of energy desired can be delivered to any distant target from which a radar return has been received. Real-time distant holography, to produce powerful energy forms at a distance, can also be accomplished.

Table 6. MASSIVE 1985 STRATEGIC MAY DAY EXERCISE

APRIL/MAY 1985

- **BREZHNEV'S 1972 STATEMENT FULFILLED**
- **40th ANNIVERSARY OF WWII**
- **GORBACHEV NEWLY IN POWER**
- **EARTH IN GIANT SCALAR EM RESONANCE**
  - **54 FREQUENCIES**
  - **27 "POWER TAP" PAIRS**
  - **4 TO 6 WEAPONS EACH PAIR**

- **C^3I SCALAR EM LINKS**
  - **UNDERWATER SUBS**
  - **NAVAL FORCES**
  - **OTHER FORCES**

12. In late November, 1985 the Soviets tested their Launch Phase ABM system over Florida, using the launch of a U.S. space shuttle as a convenient test target. A marker beacon (ball of light) was placed in the sky, hovering near the launch area. It was seen by hundreds of persons, and photographed by George Suchary. During the final countdown to launch, a scalar EM "missile" (ball of intense energy) was fired, offset from the shuttle. This ball of energy was not in the visible spectrum, but may have been accidently photographed by Bob Gladwin. Twelve minutes offset after launch, a tremendous rumbling overhead boom echoed through the area — so huge it was heard for hundreds of miles up and down the East Coast. This was the third U.S. shuttle launch in which NASA had noted associated anomalous phenomena, but did nothing.

13. On December 12, 1985 the Soviets used the same weapon in the anti-bomber mode to destroy an Arrow DC-8 jet just after its takeoff from Gander Air Force Base, Newfoundland. **Over 250 U.S. soldiers and civilian crew members were killed.** Gander has long been a registration point for the Soviet scalar EM weapons. For example, in one 4-day period in 1982, 36 anomalous incidents occurred in and around Gander, involving moving lights, lights in the sky, etc.

14. On January 28, 1986 the Soviets destroyed the U.S. space shuttle Challenger, shortly after its launch. A dozen signatures are associated with this Soviet kill, too many to mention all of them. To give only a few: First, the Soviet ships monitoring the launch site suddenly departed at high speed, four hours before the launch. This was unparalleled. Second, according to General Daniel Graham, *the following evening KGB headquarters gave a party to celebrate the success of the KGB's perfect active measures against the Challenger!* Direct and unmistakable indications of extreme localization of the Soviet transmitters to the Challenger's launch site existed on the day of the launch. In addition, a metal-softening signal was confirmed on the Soviet Woodpecker beams as early as

January 1,1986. Many other indicators also exist. The total is a very strong statement that the Soviets destroyed the Challenger with the same weapon they had tested against three previous shuttle launches, and which they had used to kill the Arrow DC-8 at Gander Air Force Base only six weeks earlier.

15. A whole series of anomalous missile failures occurred, involving Titan, Delta, and Ariane launches. The odds against all these launches failing in that pattern were millions to one. In one Titan failure, video taken of the event showed the anomalous "marker beacon" light in the vicinity, high overhead. Frame-by-frame analysis of the video showed that the light was indeed independent of the explosion, and it moved off separately after the rocket exploded.


MARKER
BEACON
SHUTTLE
T = 12 MIN.
SHUTTLE TRAJECTORY
BOOSTERS
(AREA EXPLOSION)
WELL BEHIND VEHICLE
(SONIC BOOM)
T = 12 MIN.
t = –n seconds
SHUTTLE
ELECTROMAGNETIC
MISSILE

Figure 25. Third Soviet non destructive testing against shuttle launches, Nov. 26, 1985.

Table 7. SHUTTLE **LAUNCH ANOMALIES, NOV. 26, 1985**

- **MARKER BEACON**
    - **PHOTOGRAPHED**
    - **SEEN BY HUNDREDS**

- **OFFSET SCALAR EM MISSILE**
    - **INVISIBLE TO HUMAN EYES**
    - **STRIKE PHOTOGRAPHED**

- **GIANT ATMOSPHERIC BOOM**
    - **T + 12 MINUTES**
    - **HEARD FOR HUNDREDS OF MILES**

- **THIRD LAUNCH WITH SUCH A BOOM**

Table 8. SOVIET ESCALATION AFTER 3RD TEST AGAINST SHUTTLE LAUNCH on Nov. 26,1985.

- **U.S. STILL UNAWARE OF SCALAR EM WEAPONS USE**
- **SOVIETS ESCALATED ACTION**
- **DESTROYED OR DISABLED:**
    - **ARROW DC-8 (DEC. 12,1985)**
    - **CHALLENGER (JAN. 28, 1986)**
    - **TITAN 34-D (APRIL 18, 1986)**
    - **DELTA ROCKET (MAY 3, 1986)**

- **MAY HAVE DISABLED:**
    - **ARIANE II(MAY 31,1986)**
    - **TWO U.S. NUCLEAR SUBS WHICH RAN AGROUND**
    - **STEALTH FIGHTER WHICH CRASHED**


AIRCRAFT GLOWING
KINDLING
TAIL–DOWN CRASH
ANOMALOUS HOLE
ENGINE POWER INTERFERED WITH

Figure 26. Death of the Arrow DC-8, Dec. 12,1985. Three eye-witnesses saw the **doomed** airliner glowing. An anomalous hole was found in the fuselage, forward of **the** engines. Engine combustion was interfered with, by phase conjugate (negative) e**nergy.** Engines were rumbling laborously, not roaring with power, as the aircraft **passed** 100 ft directly over a witness.



Figure 27. Anomalous hole in the right fuselage of the ARROW DC-8, ahead of the engines. With crossed over-the-horizon radar beams and multiple phase conjugate **radar** mirrors, real-time holography allows the production of a ball of EM energy at a great distance. The ball may be as small as desired, and contain as much energy as desired.

Table 9. ARROW DC-8 DISASTER, DEC. 12, 1985

GANDER AFB, NEWFOUNDLAND

- **AIRCRAFT LIFTED OFF**
- **AIRCRAFT WAS GLOWING YELLOW - ORANGE**
- **SANK TAIL-DOWN AND CRASHED**
- **SIGNATURE OF ENGINE/COMBUSTION INTERFERENCE**
  - **LAUNCH PHASE WEAPON**
  - **ANTI-BOMBER MODE**
  - **ANOMALOUS HOLE IN FUSELAGE, FORWARD OF ENGINES**
  - **STRUCK BY ELECTROMAGNETIC MISSILE?**
  - **EXTENSIVE "BALLS OF LIGHT" WEAPON TESTS IN AND AROUND GANDER**
- **CLOSELY FOLLOWED THIRD TEST AGAINST SHUTTLE NOV. 26,1985, IN ABM MODE**



Figure 28. Part of the Soviet engineering of U.S. weather, just prior to the death of the Challenger. Three "giant radial" clouds sighted over the greater Los Angeles area by Margaret Wilson. Appeared one after the other, at 10 min. intervals.

Soviets Knew The U.S. Wouldn't React



DOD PHOTO

Figure 29. Soviet Trawler spyship. About four hours before the launch of the Challenger, all Soviet ships off coast, that normally monitor each launch, suddenly and mysteriously departed at high speed. Unprecedented event.



- **SOVIET WEATHER ENGINEERING**
- **SEVERE COLD STRESS**
- **METAL-SOFTENING**
- **BOOSTER SEAL PROBLEM**
- **SOVIET SHIPS ABSENT**
- **LOCALIZATION**
- **AIR TURBULENCE**
- **BIRDS NOT FLYING**

Figure 30. Launch of the doomed Challenger, Jan. 28,1986.

Table 10. DEATH OF THE CHALLENGER, JAN 28, 1986

- **METAL-SOFTENING SIGNAL ON WOODPECKER GRID AS OF JANUARY 1, 1986**
- **SOVIETS ENGINEERED COLD WAVE INTO FLORIDA**
- **SEVERE COLD STRESS ON VEHICLE**
- **GRID LOCALIZATION SIGNATURES**
    - **BIRDS NOT FLYING IN LAUNCH AREA**
    - **BIRD FALLS IN BIRMINGHAM, AL (HINGE)**
- **SOVIET SHIPS/TRAWLERS DID NOT TRACK LAUNCH**
- **BOOSTER SEAL PROBLEM SEVERELY AGGRAVATED**
- **CAUSED SHUTTLE FAILURE**
- **SOVIET KGB HEADQUARTERS CELEBRATED "PERFECT SUCCESS OF ACTIVE MEASURES" AGAINST THE CHALLENGER!**

Table 11. KGB CELEBRATION

EVENING OF JAN. 28,1986

- **AFTER DEATH OF CHALLENGER**
- **KGB HEADQUARTERS**
    - **JUBILANT PARTY**
    - **CELEBRATED SUCCESS**
    - **OF ACTIVE MEASURES AGAINST THE CHALLENGER**

SOURCE: GENERAL DANIEL GRAHAM, URGENTGRAM

- **NOTE: SOVIET SCALAR EM WEAPONS ARE CONTROLLED BY KGB**



- **SHORTLY AFTER LAUNCH**
- **ANOMALOUS POWER SURGE**
- **"COMMANDED" ENGINE SHUTDOWN**
- **VEHICLE THEN UNSTABLE**
- **RANGE SAFETY OFFICER DESTROYED ROCKET**
- **EXTERNAL RANGE SENSORS DID NOT RECEIVE SURGE SIGNAL**
- **SIGNATURE OF TIME REVERSED WAVE**
- **WHICH LOCALIZED ON ROCKET**

Figure 31. Loss of a Delta rocket, May 3, 1986.

16. In 1975, Brezhnev had surprisingly urged U.S. senators to have the U.S. cooperate in banning the development of new weapons of unparalleled horror. He used the phrase, "more frightful than the mind of man has ever imagined." Shortly after, at the United Nations, Gromyko had even introduced a draft agreement for all nations of the world to sign. Again, the West had not the foggiest notion as to what the Russians were talking about.

17. The orthodox U.S. news media has been, and is, almost totally "out of it." Ironically, at the time of our deadliest peril, and the most momentous period in history, incidents such as the indiscretions of a presidential candidate and of a television evangelist, and the "Iran Gate" actions of the National Security Council in trying to illegally get arms to the Contras, are the "burning issues of the hour" — and the week, and the month, and the year, and HO on ad nauseam.

18. The Congress — great watchdog and the direct representative of the U.S. citizenry — is equally immersed in interminable hearings of little or no substance except news media coverage and publicity.

19. A belabored president, misled and now hemmed in on all sides and on the defensive, has had his power to act greatly constricted. In addition, the orthodox filtering networks surrounding him have effectively isolated him. He has been unaware of the extensive information that shows just how certain it is that the Soviets have fantastic superweapons and have been gingerly using them against us for decades. He and his immediate advisors are fed highly filtered, shaped and interpreted data. U.S. intelligence is very good at doing the things that it does. However, it is also very good at ignoring the things that it ignores! Further, the intelligence community is a past master at "slick-tonguing" the interpretation of anything new, and anything it really doesn't understand, in terms such as "We have no evidence that ..." For decades, the community has consistently underestimated the Soviet threat, and it has also usually projected any unpleasant present Soviet capability in the terms that "If the Soviets keep this sort of thing up, it may prove to be a real threat 30 years from now!" For years U.S. intelligence was unaware of a Toronto inventor's development and public demonstration in the late 1960's of an inertial field generator device, for example, because it simply did not place high value on simple overt intelligence such as reading the newspapers! The entire event was printed in detail in a Canadian newspaper. Only very recently, within the last few years, has the community again realized that the most important intelligence can only come from human (HUMINT) sources. And in relying on the scientific community — which itself knows nothing of scalar electromagnetics — the intelligence community has not received the technical advice necessary for it to properly task its collection agencies to collect information on the Soviet superweapons.

20. Western science has also shown itself to be highly dogmatic and ensconced in the comfortable "status quo." It has regally ignored the important Soviet developments in unified field **theory.** It has assumed an aristocratic stance, regarding the Soviet scientists as little more than peasants still trying to cl**ean** the mud off their boots. In fact, the Soviet scientists have been ahead of the rest of the world in *nonlinear* science — the **truly** hard stuff— since the beginning. They have always been **the** best nonlinear mathematicians in the world. Soviet scientific papers regularly appear which deal with local general relativity and the overcoming of the sacrosanct conservation laws as a matter of course. That subject is still a "no-no" in U.S. scientific publications, even though breaking symmetry and consequent violation of conservation laws has long boon proven in particle physics. To my knowledge, with the exception of Hooper's obscurely published work, not a single US. scientific paper appears in the literature showing any detailed investigation of "bucking fields" as such and investigating the behavior of materials exposed to such "sum-zeroed" fields. Yet ironically a whole area of optical physics — phase conjugate optics (PCO) — has shown great activity since we discovered it in the open Soviet literature in the late 60's, and **since** two Soviet scientists visited Livermore* in 1972 and briefed us upon the subject (as another stimulus to see if we recognized the awesome weapon implications). In PCO, the s**calar** EM wave formed by two waves 180 degrees out of phase w**ith** each other, and locked (modulated) together by a nonlinear medium, is blithely called the *pump wave.* Using it on nonlinear materials produces extraordinary results — such as electromagnetic waves traveling backward in time. Further, the PC effect is known to be universal, and not just in the optics **region** at all; for example, it has also been done with sound waves. **The obvious experimental and theoretical proof of scalar EM has been in our literature for nearly two decades, and even in PCO our scientists do not yet realize that the** "pump" **wave is a scalar** wave, **a** wave **of**

***Lawrence Livermore National Laboratory**

artificial potential, and a gravitational wave that pumps the nuclei of the atoms in the nonlinear medium. They also still do not understand that it is the nucleus of the atom that produces the phase conjugate replica wave in PCO.

Table 12. BREZHNEV'S 1975 PROPOSAL

AT THE SALT TALKS ON JUNE 13, 1975

- **THE SOVIETS URGED THE U.S. TO AGREE ON A BAN AGAINST RESEARCH AND DEVELOPMENT OF NEW KINDS OF MASS DESTRUCTION WEAPONS MORE TERRIBLE THAN ANYTHING THE WORLD HAS KNOWN!**

- **BREZHNEV PERSONALLY URGED VISITING U.S. SENATORS TO AGREE TO THE BAN.**

- **GROMYKO INTRODUCED A DRAFT AGREEMENT INTO THE UNITED NATIONS MEETING AND URGED THE NATIONS OF THE WORLD TO SIGN IT.**

- **THE WEST HAD NO IDEA WHAT THE SOVIETS WERE TALKING ABOUT!**

- **SOVIET HAWKS THEN GAINED DOMINANCE, AND THE USSR STARTED ITS MASSIVE BUILDUP FOR EVENTUAL WORLD TAKEOVER.**


2nd OBSERVER
DAVID WOLSTEN
1st OBSERVERS
STEVE MOORE
LISA BARGER
285
85
75
ROSWELL RD.
N
W
E
S
ATLANTA

A. Location of the incident


OTHER CLOUDS MOVING WITH WIND APROX. 20 MPH (WEST TO EAST)
CLOUDS LEAVING OR JOINING ARC
UPPER EDGE IRREGULAR
STATIONARY ARC OF CLOUDS
WELL DEFINED LOWER EDGE
HAWKS
Lee Giles
DATE: 11/12/86
TIME: 2130
OBSERVER LOOKING SOUTH FROM I-285, NEAR ROSWELL RD., ATLANTA, GA

B. Artist's sketch of the incident.

Figure 32. Probable Soviet test of a Tesla Shield over Atlanta, Georgia.

Continually assured that Western science and intelligence remained outrageously ignorant and would obstinately persist in wearing orthodox blinders, the Soviets felt quite safe in striking the U.S. and its Western allies a mortal death blow.

The Soviets knew there would be no retaliation, so long as the blow was sufficiently unorthodox.

After all, the Soviets have been waging a slowly increasing unorthodox war against us for decades, and totally getting away with it.

Consequently the Soviets manipulated the cancer research and the contamination of the World Health Organization's smallpox vaccine to produce the perfect biological warfare "first strike," administered unwittingly by the WHO itself in its mass immunization program to eradicate smallpox. The Soviets continue to manipulate the spreading AIDS viruses electromagnetically so that the West will be devastated, as well as Africa and the Third World.

At least one other spreading AIDS-strain has already appeared in Africa. Testing for exposure to the first strain in most cases did not detect exposure to this second strain.

Officially no one knows whether it will be as infectious as the first strain. However, a suspicious correlation has appeared between hepatitis vaccination in several large U.S. cities and consequent outbreak of AIDS among the persons inoculated.

Further, the latest studies are beginning to show that (1) AIDS may be just as spreadable, though more slowly spread, in the heterosexual community as in the gay community, (2) the AIDS tests themselves are far more unreliable than suspected; one may have the AIDS virus — and serve as an active carrier —for up to three years before the tests begin to detect it, and (3) no one has any real idea as to how many persons have already been infected.

As can be seen, even orthodox scientists are beginning to suspect a coming AIDS infection "asymptote" which may represent an explosion of the disease into a mass pandemic in the world population. In Africa, for example, AIDS is spreading freely among the hetersexual population as well as the homosexual population. * We may be on the verge of seeing a similar phenomenon emerge in the

---

*Although there is much speculation as to why African heterosexuals seem so vulnerable, at present no one knows why it is true.

Western world.

If so, we are looking full in the face of a forthcoming AIDS massacre that makes the 1918 influenza pandemic pale by comparison. Not only will AIDS decimate Africa and the Third World, but it will also decimate the West a little later.

In the Soviet plan, after the AIDS massacre has peaked, the remaining much smaller U.S. and European populations will be decimated and totally powerless. The demoralized and devastated Western nations will easily capitulate and pass under the Soviet hammer and sickle.

In their deception planning, the Soviets even are allowing some contamination of their own citizens by AIDS. Thus they can keep up *a pretense* that they are just as much victimized as we are, and just as much "in the dark" as we are about the whole thing.

Of course, once the AIDS infection does its lethal dirty work in the West, the Soviets can easily eradicate it in their own population at will, using the electromagnetic healing technology they already posess. The Soviet planners regard the loss of a few Soviet citizens along the way as one of the things necessary to insure the success of the Great Strike and the Final Revolution. Forward divisions in the standard Soviet attack are always regarded as such sacrificial pawns to guarantee the success of the follow-on echelons in the attack. In this BW strike, the sacrifice of some Soviet citizens is deemed necessary to the overall success of the attack.

Remember, these are the same type of Soviet communist planners who killed 20 million Kulaks — their own people — to forcibly collectivize Soviet agriculture. For their highest purposes, these planners are still quite capable of ruthlessly sacrificing millions of their own people to achieve their objectives.

The *Asian Tiger Mosquito: A New and Efficient Vector*

As almost everyone now realizes, in the past our government has greatly understated the AIDS problem. Past projections of the limitation oft he spread of the disease have been far more optimistic than warranted.

For example, officially the government is still denying any possibility of insect vectors for the disease.

Don't believe it. In fact, highly efficient insect carriers of the disease are already on the way.

Insects in Africa have positively been verified to be harboring the AIDS retrovirus. Of course, such reports are always accompanied by the bland assurance that "We have no evidence... (that the insect bites will give AIDS to humans).

Let's see now: We're supposed to believe that a monkey bite will do enormously more than that. Even when the monkey didn't have the exact present form of the AIDS retrovirus. Even though monkey bites hadn't done the trick in thousands of years.

But we're supposed to turn right around and believe that an insect carrying the live AIDS retrovirus can bite you, inject into you some of his body fluid containing AIDS viruses, and you won't stand any chance of developing AIDS .

What are we supposed to believe? That the injected AIDS virus from an insect bite won't bother you, but the injected AIDS virus from other causes will?

Nonsense!

Anyone who believes that is a prime candidate for purchasing that bridge down the road...

Of course insect vectors will give you AIDS!

And we've got a real tiger — mosquito, that is, on the way to do just that.

The Asian Tiger mosquito has been introduced into the U.S. (it just "accidentally" appeared, of course!) and is now spreading through the Southeastern states. This vigorous and voracious mosquito prefers man as its target, and has an unusually wide range.

Recently U.S. scientists have reluctantly confirmed the presence of the AIDS virus in the Asian Tiger mosquito. However, as usual we are presented with the same tired refrain, "We have no evidence that... the mosquito's bite is capable of causing a human to develop AIDS."

Of course, you can be sure that eventually we *will* have evidence of precisely that!

The AIDS virus is now known to be able to live outside the body for up to at least 15 days, if not longer.

Also, the AIDS virus is an unstable virus — it's constantly mutating and changing its form. That means it's "highly adaptable" - **that** is, it's continually adapting to its environment, at a rate millions of times faster than normal stable viruses change and

That fact implies that some mutant strain of the virus will almost certainly be adapted to living in the Asian tiger mosquito and being introduced into its human host by the mosquito's bite.*

It's not a matter of "Can it do that?" or "We have (as yet) no evidence of that."; instead, it's a matter of "How long will it be until that occurs and we confirm it?"

The Asian Tiger mosquito apparently is intended to serve as the major vector (carrier), or at least one of them, to eventually rapidly increase the AIDS infection rate and devastate the U.S. population.

AS the vector spreads and the virus adapts to that mode of transmission, the rate of increase of the AIDS infection will itself accelerate. This means that all the projections for "doubling times" are seriously in error.

The latest data from Alabama, for example, shows that the disease is now doubling every six months instead of every year. Also, the doubling interval itself has been shortening, at least up to the p**resent.** Note also that, from the data of the new studies confirming a much longer lag time for the AIDS test to indicate the presence of the infection, even the present data on the number of persons infected and the doubling time are underestimated.

If these and other data are a true indication, it appears that we literally may have an "explosion" of the AIDS infection in no more than two to three years.

In addition, as we said the AIDS virus is an unstable virus. Mutations in the virus itself are occurring so rapidly that producing an effective vaccine essentially will be impossible. Without a totally new means applied to produce an AIDS cure, AIDS simply cannot be **stopped.**

•And one or more strains will eventually evolve that can be infectuously spread like the influenza virus is.

In fact, recenly it has been discovered that the AIDS virus is far more devious than previously susupected.* It attacks in more ways than suspected. It changes in the body, increasing its virulence as the disease progresses.

Macrophages, the immune system's scavenger cells, become infected and carry the virus to other body cells. It appears that macrophages may pass the virus to the T-cells, conditioning the destruction of the immune system. Infected macrophasges are found in rectal material of AIDS patients and in cervical fluid and semen. Thus through infected macrophages the AIDS virus is able to infect partners through exhange of semen, cerical fluid, and rectal material — even though there are no breaks or tears in the skin, and even though the number of free AIDS viruses in the fluids is too small to pass the infection.

Other immune system cells —such as Langerhans cells—are also suspected to be capable of serving as AIDS carriers when infected. The end result is that, as the AIDS patient sickens, the virulence of the AIDS virus increases, so that it attacks a greater variety of cells and can more easily infect them.

Present orthodox methods cannot cure AIDs in time, if ever.

Unless unorthodox technology is applied to solve the problem the West is already defeated.

---

*See Gina Kolata, "Fatal Strategy of AIDS Virus Grows Clearer," Science Times section, **New York Times,** Mar. 22, 1988; see also "Growth in AIDS Virus Virulence Found," **Los Angeles Times,** Apr. 1, 1988.

CHAPTER 3

WORLD WAR III IS RAGING AND WE'VE NEARLY LOST IT

More on AIDS Doubling Time

AS we said, the AIDS problem is much, much worse than officially announced. As stated, in some areas at least, the number of new AIDS cases diagnosed has been doubling every six months instead of every year. New studies have shown that the tests to identify infection by the AIDS virus may themselves have a 3-year lag period in which they do not reliably indicate the presence of the infection.

These facts probably make all previous "officially announced" estimates and projections off by several orders of magnitude (at least three).

If the incubation period (nominal) is, say, 5 years, then there is a factor of up to 2 (exp 10) of AIDS cases already in incubation.

The lag in accuracy of the AIDS tests however, may mean that there are even more AIDS cases in incubation than this.

And we may have a new entry into the equation at any time, once the AIDS virus adapts to its transmission by the Asian tiger mosquito and possibly even other insect vectors.*

Remember, we've got the U.S. data for only a relatively few years since 1981. So it's statistically difficult to project ahead with any accuracy. However, the best interpretation of the data we can make shows a spiraling (speed-up) trend in the rate of acceleration of the disease, indicative of a forthcoming asymptote. If that interpretation of the data holds true, the asymptote represents literally an "explosion" of the disease.

That is, the six-months "doubling interval" is slowly becoming **the s**ix-months "tripling interval," the six-months "quadrupling interval," etc.

The best indication/projection I can tentatively arrive at is this: If the total cure is not accomplished within about two to three years, then - considering the incubation ongoing by then and the speedup

---

***Another HIV virus has now been identified.**

ahead — somewhere between a third and two thirds of all humans on earth will perish.

In other words, nominally half the humans on earth will inevitably die, say within five years (the incubation) after that two to three year point.

Most of the people who die are going to be highly selected. Most of them are going to be Westerners, Africans, Asians, and Brown people.

And all of our tanks, ships, bombers, missiles, nuclear weapons, and armed forces put together can't save a single AIDS victim.

We've got more generals than ever before in our history, including World War II. And not a one of them has a single tactic or a single weapon to use against this mortal attack.

Understand, our generals have not failed us against the enemy they know and recognize. The bellies of our B-52 bombers and the aircraft aboard our distant aircraft carriers are filled with nuclear bombs sufficient to destroy the world many times over. Our powerful nuclear-tipped missiles sit in land-based silos and in sleek submarines cruising silently under the oceans, waiting to respond in an instant to hostile attack, again with the power to destroy the world many times over.

Yet the fine men and women who have built and maintained that awesome force, and who man it in constant vigilance to protect our nation, are absolutely vulnerable and defenseless against the smallest foe of all —just as were the Martians in H.G. Wells' **War of the Worlds.**

With all our awesome forces, we do not have the power to stop a single AIDS virus — or indeed, any other similar new BW virus.

We can be defeated with ridiculous ease by even the tiniest determined hostile nation — or even by a single terrorist, madman, or genetic accident by a high school youth.

And if there's one thing that we can learn from history with iron certainty, it is this: If we can be defeated with ridiculous ease, then most certainly we will be!

Since the strike has already occurred, then our defeat is just a matter of time if we continue our present courses of action.

All other threats — nuclear, chemical, scalar EM, the works — pale in comparison to this seemingly innocuous, doomsday BW viral weapon that has already been unleashed upon an unsuspecting world.

World War III is Already Raging

World War III has long been unleashed and a final, decisive first strike has now occurred. We've already lost the war unless unbelievably heroic measures are taken immediately.

This thing is deliberate. It's fiendishly clever. It's effective. And a smiling Gorbachev — master propagandist — is just part of the icing on the cake to deceive us until it's too late.

Ironically, Soviet announcements have cleverly started claiming that the U.S. has produced the AIDS virus and unleashed it.

That's a very clever propaganda trick to shift suspicion from themselves. Indeed, in the Third World the propaganda has been very effective. Most Third World peoples now give at least credence to the Soviet claim.

Unless we move immediately to effect a total cure, the armed forces and the populaces of all the Western nations will shortly be devastated — perhaps even worse than if they been attacked with nuclear weapons.

With our armed forces and populations devastated, we surrender. We lose.

The Soviets get the U.S. (and European) farmland. That's what they really need.

Of course they also will have rid themselves of about 200 million Americans or so along the way.

That, solves the old "winner's problem" of what to do with, and how to effectively control and care for, a conquered, resentful populace. That problem will have already been taken care of, for most of the U.S. populace will essentially have been eliminated.

There won't be many U.S. military prisoners, for example, since most of the military personnel will also have been eliminated by the virus or viruses clandestinely released.

Communism Is Savage Enough to Do Diabolical Things

The Communist's doctrine is to wage total war. Win any way, with any weapon, at any cost.

ALSO, communism has always taught that it is necessary to destroy capitalism. That equates with destroying the U.S., the major capitalist country. Communists have always taken the long view, willing to struggle for decades to eventually accomplish their aim.

If you think no modern nation could be so incredibly savage as to deliberately destroy untold millions of people, look at the actual record of the Communists.

When the Khmer Rouge took over Cambodia, they murdered a third of their own people.

The Soviets murdered some 20 million or so Kulaks when they collectivized the Soviet farms.

The Red Chinese also slaughtered Chinese peasants by the tens of millions — perhaps as many as twenty or thirty million — when they collectivized the farmers.

Lenin's followers have proved over and over that they are capable of murdering even their own people, on a scale of millions.

Dedicated communists are highly religious people — even fanatics. Deliberate murder to achieve communism's goals is part of the accepted dogma.

The communists are quite capable of killing a billion or more "foreigners" and "enemies," given the chance. Particularly when the goal is to win the "Final Revolution."

The opportunity to strike the decisive final blow without consequences, using as simple and unorthodox a weapon as the AIDS viruses, could simply not be ignored by men who have spent their lives trying to control the world.

The unparalleled strike opportunity was particularly irresistible since someone else (the Western cancer research institutes) would develop the weapon itself, someone else (the World Health Organization) would unwittingly deliver the strike, and the blow could easily be clandestinely arranged (simply by secretly contaminating the WHO smallpox vaccine) and accomplished without repercussions to the Soviet Union.

Western Medicine is Inadequate

But what of Western medicine? Doesn't it always come through to save us?

Present Western medical science is totally inadequate to do the task required.

For example, present medicine is largely based on "slowing or killing the invader of the body." Whether that invader is a germ, bacterium, virus, or whatever.

If there's a mechanical difficulty, then present treatment is to try to mechanically remedy it — remove a bad appendix, set a broken leg, etc.

However, then it's strictly up to the body's own natural healing system - its immune system and its repair system — to actually do the healing and repair/reconstruction.

The problem with AIDS is that it directly affects and suppresses the body's systems for healing and repair.

Once this protection and repair system is in disarray, any disease organism can attack the body and infect it. If the immune system can't handle the problem, eventually the invading disease organism kills its host.

Even if a way is found to destroy the AIDS virus itself, present medicine has not the foggiest notion of how to restore the healing and repair system from the damage and destruction it will have already sustained by massive AIDS infection.

Compare the situation to division combat: Hostile invaders are met at the front of the division by the division's combat forces. A battle ensues, with penetration and damage to the rear area support and sustenance facilities. After the enemy is beaten back or destroyed, the rear support and the combat forces must be renewed and restored. If that cannot be done, the seriously weakened division can still literally be boiled over by almost anything that comes along and hits it.*

---

*For this reason, standard Soviet doctrine is to attack in echelon, say, by three divisions — one behind the other. Thus, even if the first division is annihilated in the attack, the second and third divisions meet a seriously weakened enemy division and blast right over it. Similar tactics in the BW crisis - multiple viral strikes, one after the other — can almost inevitably be expected, now that the "first division" - AIDS - has engaged us.

The Soviet "repetitive attack" method *works,* in case anyone has doubts. For example, see George C. Wilson, "Army training exercises raise troubling questions," The Washington Post, as printed in the Huntsville (AL) Times, Feb. 28, 1988, p. 21A. Repeated U.S. Army tests in the Mojave Desert have shown that, in nonnuclear combat, when attacked by multiple Soviet echelons with 3:1 strength, U.S. forces lose every time! In particular, U.S. troops have poor anti tank defenses.

Modern medical dogma has concentrated almost entirely on the combat forces' problem of destroying and/or repelling the invader.

Western medicine has almost no tools or means of restoring the support and rear maintenance functions.

Even in a paroxysmal effort, dogmatic Western medical science would take decades to totally reorient its medical thinking to where it could even attack the real problem of AIDS and catastrophic sickness due to other viral BW warfare agents.

The same inability to cope with the problem also applies to our government bureaucracy, government agencies, the private companies, the universities, and to Western science in general.

If we have to depend on any or all of our present "system," the war is already over and we are all already doomed. Half of humanity will die within possibly five years after the upcoming two- to three-year "point of no return."

Medical insurance, treatment centers, and even private physicians are quickly going to be bankrupted as the AIDS plague increases. With the collapse of Western medicine, panic and pandemonium will reign in the streets. Martial law will be a necessity, and rioting on a scale unparalleled in American history will occur. We are likely to see our own U.S. dictatorship, in the form of a military junta making a coup and seizing power "to restore order and keep the lid on."

Study carefully the performance of governments and military regimes in such countries as Korea and South Vietnam, when those countries were hard pressed by enemy forces and in great disarray.

You may be looking at your own future.

The Soviets Will Not be Decimated

With the devastation of our armed forces, our governmental and civil agencies, and our population at large, a simple show of strength by the Soviets will collapse any further resistance. The hammer and sickle will wave supreme over the residue.

That's because the Russians *do* have the necessary developed scalar EM medical technology, not only to control and destroy the AIDS viruses, but also to directly restore the immune and repair systems.

The Kaznacheyev experiments alone show they have extensively studied electromagnetic induction of cellular disease and death.* We will have much more to say on that later.

If the Soviets extensively studied cellular death transmission by electromagnetics, you can bet they also studied the reverse: electromagnetic healing, or time-reversing the electromagnetic "death" signals themselves to produce specific "healing" signals for any type of cellular disease.

This is particularly certain since the Soviets also discovered and possessed the necessary "time reversal" electromagnetics: phase conjugation. This had been widely used by the Soviets in developing their enormous scalar EM weaponry, beginning about 1950 or so.

The curative signal technology was kept secret, of course, since the Soviets realized that it provided the only viable defense against viral biological warfare weapons.

The Soviets most certainly have the necessary AIDS cure. They can readily make the correct electromagnetic healing signal, by phase conjugating the AIDS death signal from dying human cells that contain AIDS retroviruses.

They also know we most certainly do *not* have the necessary EM cure. Years of weak microwave radiation of personnel in the U.S. Embassy in Moscow, and inducing illnesses in those personnel and even U.S. ambassadors, have shown that our own intelligence and scientific communities don't know what's really going on there.

Specificially, we've demonstrated (after checking with the DIA, CIA, NSA, and the orthodox scientists) that we do not recognize electromagnetic *biological warfare* —the deliberate introduction of cellular disease and death by electromagnetic means. Not only do we not recognize it, we can't do anything about it when it hits us.

And make no mistake, time-reversed electromagnetic medicine is shockingly cheap and effective, once developed. Specific healing signals for specific diseases — viral or whatever — can be quickly developed (within hours) and immediately used for mass treatment of entire populations.

For example, given the developed healing or "antidote" signal, it can even be recorded and played over ordinary transmitters, using their normal transmissions as carrier waves. A populace continually bombarded by such "healing" television, radio, and powerline signals simply doesn't get the disease. And those already infected recover when continually exposed to such healing signals.

---

* There is now reliable information more closely associating Kaznacheyev with military *institutes near Moscow, engaged in* microwave weapon (directed energy) research

So the Russians can stop the AIDS epidemic cold, anytime they choose to do so.

Electromagnetically they can also gently guide and stimulate the progress of a disease such as AIDS, once the disease is introduced into a targeted population.*

Or, the Soviets can pull out all the stops and induce the disease in a distant population directly, placing the "death signals" on common carriers. Such as on our power lines, radio stations, televisions, and directly by induction from the Woodpecker over-the-horizon radar signals which continually bombard us.

The West cannot do any of these things. Neither can the West counter them, or defend against them effectively.

Unless a totally different tack is taken in the Western effort to counter this viral BW threat, Gorbachev's entrancing smile has already lured us to our doom. We are faced with a direct realization of Lenin's words:

"In the final revolution it does not matter if three-quarters of the earth is destroyed, so long as the remaining quarter emerges communist."

And Khrushchev's ghost will have the last laugh after all. We will have fulfilled the prediction he made to Nixon in their famous "Kitchen debate":

"We will bury you!"

Quite simply, for some decades the Soviets have had a new science — one they call *energetics,* and one which I have called *scalar electromagnetics.* The keystone or "heart" of this new science is time-reversed (phase conjugation) electromagnetics and electrogravitation.

*A candidate for an eery test of just this capability may be the highly anomalous deaths of numerous dolphins off the East coast of the U.S. in 1987. Nearly 500 died in the summer and late fall, apparently as a result of the weakening of their immune system to the common bacterium Vibrio. See Julia Lawlor, "Key: Failure of Mammals' **defenses,"** USA Today, **Jan. 19, 1988, p. 1A-2A.**

Chapters 4 and 5
deal *with complex scientific material*
and are suggested for those who are
technically proficient.

CHAPTER 4

EXTRAORDINARY PHYSICS

Maxwell's Lost Unified Field Theory

About the time of the U.S. Civil War, James Clerk Maxwell succeded in unifying magnetism and electricity. Actually he did far more than that, in his theory as originally written.

In fact, he had produced a theory which also captured the free interchange between electromagnetic energy and gravitational energy, but no one — including Maxwell himself—realized it at the time.

Maxwell wrote his original theory in quaternion and quaternion-like mathematics. The modern form of vector mathematics had not yet been finalized by Gibbs and Heaviside. It is most instructional to examine some of the fundamental differences between a vector and a quaternion.

In a conventional 3-dimensional vector, one may have three vector components, such as

$$v = ai + bj + ck \qquad (4\text{-}1)$$

where i, j, k are unit vectors in the directions of the x, y, and z axes respectively and a, b, and c are constants.

Obviously if the vector components of vector v are zero, then

$$v = 0 \qquad (4\text{-}2)$$

We shall be interested in the "vector product" of two identical vectors v, where

$$\mathbf{v} \times \mathbf{v} = AA \sin\emptyset = \mathbf{O} \qquad \textbf{(4-3)}$$

and A is the length (magnitude) of vector v, $\emptyset$ is the angle between the two vectors (in this case zero), and O is the zero vector.

Now let us look for a moment at the quaternion situation.

First, in addition to the three vector components, a quaternion also has a separate scalar component, w. So the quaternion q for this situation is

$$q = w + ai + bj + ck \qquad (4\text{-}4)$$

Now when this quaternion is multiplied times itself, the vector part zeros, just as it did for the vector expression. However, the scalar part does not go to zero. Instead, we have

$$q \, X \, q = A^2 = a^2 + b^2 + c^2 \qquad (4\text{-}5)$$

There is a very good physical interpretation of this result. It is a square of the amplitude, hence for the vector part of a wave, it is directly proportional to the energy density of the vacuum, as a function of time, at the particular position. However, we now need to make a short explanation of variation of stress energy density of spacetime.

First, we note that, according to general relativity, the "gravitational potential" is just a conglomerate of potentials of all kinds. Basically, a potential represents a G-potential, and consequently a curvature of spacetime. The potential also represents "trapped energy."

Second, we note that Kaluza combined electromagnetics and gravitation as a unified theory in 1921. Kaluza added a fifth (spatial) dimension to Minkowski's 4-space, and applied Einstein's relativity theory to 5 dimensions.

To Kaluza's delight, a common 5-d potential is responsible for both electromagnetic field and gravitational field. The "bleed-off of this 5-potential in the 5th dimension (which is wrapped **around** each point in our 3-space) is what we know as the **electromagnetic force field.** The bleed-off of this 5-potential *in and through* our 3-space is what we know as the **gravitational force field.**

Since the EM field is very much stronger (by a factor of 10^{42} for electrons) than the gravitational field, it is obvious that most of the bleed-off of the 5-potential is in the 5th dimension, as EM force field. Only a tiny bit is left to bleed-off in 3-space, producing a very weak gravitational field.[1]

We state this fact: as a mass moves in space, it generates increased "activity" with the virtual particle flux of vacuum itself. **The** Increased virtual particle flux activity exchange between vacuum and mass is analogous to a strange kind of "virtual resistance." Since the resistance is virtual, it does not observably slow down an observable object moving in an (unobservable, virtual-particle flux) vacuum.

The increased flux activity represents an increased "virtual energy density" of space time, and an increased "trapped potential" (mass; resistance to an accelerating force) of the moving object. It represents a rotation of the spacetime frame, vis a vis the laboratory observer).

In the virtual vacuum (which contains both positive and negative time), one sees two antiparallel virtual forces: one in positive time, along the velocity vector of the object, and one in negative time (time reversed, or phase conjugated). The reason one sees virtual forces is that, each virtual (subquantal) change in the virtual flux activity represents an individual (unintegrated), separate change, hence a virtual acceleration. The observer (where things are integrated), sees the integral of all these accelerations, hence observable velocity.

The vector sum of these two virtual forces in the vacuum is a zero vector; however, the two taken together represent a stress in the local energy density of vacuum.

Since we may regard an EM wave as a stream of virtual electrons/positrons, each engaging in tremendous virtual particle flux exchange with the vacuum, then the same basic picture applies.

Now for our physical interpretation of (4-5): If we refer to an EM wave moving in the vacuum, the rotation of the frame is maximum (90 degrees). But this same rotation is just the same as additional vacuum stress, so the vacuum stress is maximum.

---

[1] **Electromagnetics is 5-gravity sliding around our 3-space. 3-gravity is 5-gravity oozing** through our 3-space.

This leads to these conclusions: An electrical force field vector represents a local maximum linear stress in spacetime, along the line of the vector. (Note we specifically deny that the electrical force field vector, of an EM wave in vacuum, is transverse. Instead, it is longitudinal. That has been addressed elsewhere by the author and will not be covered further here.)

Another electrical (stress) vector interacting with the first one adds more "urging" stress to the first. However, this action is occurring in the rotated frame of the moving wave, and so is rotated 90 degrees from the electrical velocity vector. Therefore it is lateral (but in a hyperdimension, not in 3-space) at right angles to the electrical velocity vector.

The combined "urging" action of the two vectors thus sweeps out an area with respect to the laboratory observer.

This means that the total "urging" or "stressing" action of the two vectors is analogous to a vector area.

It also means that this "area" function may be taken as the "swirl" of the electrical vector, but in a hyperdimension, not in 3-space. That is, we have described the magnetic force field.

Thus any two electrical vectors that interact will have an "area" or "resistance" component generated. *Any two that interact.* Whether they add vectorially, cross-product multiply, or dot-product multiply.

What is actually happening is that the wave exists in the 5-potential. The E and B fields just represent the oscillations in that 5-potential. They represent oscillations in the bleed-offs of that potential as E-field (longitudinal) and B-field (swirl).

The drag-area represents the accumulation of extra potential — hence the local rotation of spacetime. Since this accumulation is moving (along with the EM wave), as it passes a point it represents a change in the local virtual particle flux density of vacuum at that point, **hence a local curvature of spacetime.**

Hence, the EM wave makes a 5-dimension G-potential wave as it travels. The 3-dimensional gravity wave associated with this is normally very, very much smaller in magnitude — say, by a factor of 10^{-42} or so.

However, if the two vectors interact so as to produce a vector zero resultant, then all the electromagnetic energy of tho two vectors **is** captured. That is, all the "EM vector zero" resultant means is that the EM bleedoff of the 5-space gravitational potential wave has been stopped. The 5-potential is still oscillating, and now all its trapped 5-energy must bleed off as 3-gravity force field.

Mass acts as an accumulator for this "trapped-EM energy turned into local curvature of 5-space." If we continually irradiate a mass with such a wave, the atomic nuclei of the mass slowly charge up with the new energy. Note that this potential delta may be positive or negative, if one adjusts accordingly.

In this fashion one may change the mass of a static object in the laboratory. One may either increase the mass or decrease it, or cause it to float, or even cause it to accelerate upwards.

But to return to our vector interaction and our interpretation of the scalar remainder of the quaternion.

The rule is, when the two EM vectors interact so as to form a zero EM resultant, then the EM energy represented in each of the two vectors has been converted into a special form of 5-space gravitational potential, one that is not bleeding-off in the fifth dimension (electromagnetically), but one which will gradually produce a 3-gravity potential in a mass's atomic nuclei as a function of time, the individual element, permeability and absorption factors of those nuclei, etc.

Therefore in our mathematical theory we ought to have a scalar component remaining when two EM vectors interact to form an EM vector zero resultant. That scalar component represents what is happening in the 5-potential, that will only bleed into 3-gravity.

With exploration of this phenomenology in the laboratory, one can work out the functions, constants, coefficients, and parameters which specify how the "5-G to 3-G and vice versa" component works in conjunction with mass, motion, and other fields.

That's the magic secret of electrogravitation.

It was captured inherently by the quaternion theory of Maxwell published during the American Civil War!

After Maxwell's death, when the scalar portion of the quaternion was discarded (by Oliver Heaviside) to form "modern" EM theory, that also discarded the unified field interaction between electromagnetics and gravitation.

Electromagnetic field and gravitational field were then modeled and regarded as mutually exclusive. EM field, therefore, was thought to produce no specific gravitational effects in the vacuum itself.

Hence when Albert Einstein was formulating general relativity some decades later, he knew only one way to "curve" spacetime: that was gravitationally, by "attraction of mass" forces.

But gravitational force was so weak that only a huge collection of mass would exert enough of it to measurably curve spacetime. That would require a sun or star. Since the observer and his instruments would never be on the surface of the sun or a star, **Einstein** assumed **that the local** spacetime **of the observer would not be curved.**

Hence he severely crippled his general relativity theory. In the West, it remains an assumption to this day. It is not a universal assumption in the Soviet Union, however, since the Soviets have long since written — and developed in the laboratory—unrestricted general relativity with *local* spacetime curvature, and hence *local violation of conservation laws.*

So the scalar part of the quaternion interaction, that remains when the vector part of the resultant is zero, is magic indeed.

That is the magic unified field portion that everyone has been seeking for decades and decades!

It was there at the beginning. Then we inexplicably threw it away!

But to return to our vector/quaternion examples.

Note also that the two vectors

$$V_1 = ai + bj + ck,$$
$$v_2 = -ai - bj - ck \qquad (4\text{-}6)$$

sum to zero vectorially when added, such that

$$v_1 + v_2 = 0 \qquad (4\text{-}7)$$

However, quaternions may behave quite differently, even under addition. For example, the two quaternions

$$\begin{aligned} q_1 &= w + ai + bj + ck, \\ q_2 &= w - ai - bj - ck \qquad (4\text{-}8) \end{aligned}$$

sum their vector parts to a vector zero resultant, but do not sum to a scalar zero as well. Instead, they sum to

$$q_1 + q_2 = 2w \qquad (4\text{-}9)$$

AS can be seen, quaternions which have the same vector parts as vectors, do not necessarily yield a complete zero when the vector parts sum to zero. And when two vectors multiply to provide a zero vector resultant, corresponding quaternions may yield a scalar term that is equal to the product of the magnitudes of the two vectors. In this way, the quaternion approach can capture the *stress of the medium,* induced by opposing or multiplying vectors. In the vector approach, the stress of the medium is entirely lost when the two vectors sum or multiply to a zero resultant.

Let us see just how important this "vacuum stress" can be.

First, the "stress in the medium" represents curvature of spacetime when that medium is the vacuum/spacetime.

In other words, the quaternion approach captures the ability to utilize electromagnetics and produce local curvature of spacetime, in an engineering fashion. Heaviside wrote a subset of Maxwell's theory where this capability is excluded.*

---

*Dr. Henry Monteith has independently discovered that Maxwell's original quaternion theory was a unified field theory. See his important "Dynamic Gravity and Electromagnetic Processes," in publication

Note that, by Maxwell's original quaternion theory, however, Einstein's assumption need not be true at all. For example, look at equations (4-5) and (4-9): Here we may utilize electromagnetic force quaternions to produce zeroed EM forces, and an increased stress in local spacetime. In other words, we have curved local spacetime electromagnetically. Since (with electrons) electromagnetic forces are about 10^{42} times as strong as the gravitation force, this local curvature of spacetime is not negligible.

That is, we have produced a scalar effect from zeroing vector operation between electromagnetic forces. I have called this **scalar electromagnetics,** and pointed out that it is truly *electrogravitation.*

We stress again that this violates one of the severely limiting assumptions that Einstein placed upon his theory of general relativity. He assumed that curving spacetime could only be done by the weak gravitational force due to mass. Since gravitational force is so weak, only a stupendous collection of mass — such as the sun or a star — could curve spacetime enough to notice experimentally.

Since obviously the observer and his laboratory instruments would never be located on the surface of the sun or a star, *Einstein assumed that the local spacetime would never be curved!* In other words, the local frame would always be a Lorentz frame. This meant that, locally, the familiar conservation laws of physics would always apply. Curvature of spacetime would only occur at great distances, and at huge collections of mass such as a star or dwarf star.

Einstein did not write a complete, unlimited general relativity. He wrote a sort of "special relativity with distant perturbations."

If Einstein had had electromagnetic theory in quaternions, the scalar "vacuum pressure" parts would have been there for him to ponder. It is highly probable that he would have captured the "electromagnetics-to-gravity conversion remainder" in the quaternion interactions.

If so, he would have written the full theory of general relativity, involving local violation of conservation of energy, a unified field theory, and the direct engineering of

gravitational and antigravity effects on the laboratory bench by electromagnetic means.

In that case, we should long since have navigated all around the solar system, colonized the planets, produced practical free energy devices and power systems, and avoided two great world wars and a host of little ones.

But let us now see if we can make a gravitational wave, electromagnetically.

Again, regard equations (4-5) and (4-9). Suppose these are instantaneous operations of EM force quaternions whose vector parts are varying in magnitude, but in such a manner that the vector parts ways form a zero vector resultant. Now one can see that the scalar part remaining — which represents the stress of local spacetime - is varying as the product of the magnitudes of the vectors in the interaction vary.

This means that one has now produced a scalar wave that represents the local variation of spacetime curvature in an oscillating manner.

Rigorously this is a gravitational wave. It has been produced locally. It has been produced by Maxwell's original unified theory.

Again, I have called this area *scalar electromagnetics*. The Soviets call it *energetics*.

Where local spacetime curvature is varied, conservation laws (energy, conversation, etc.) need not hold. Curved one way, the local spacetime acts as a source (of energy, charge, etc.) Curved the other way, the local spacetime acts as a sink (of energy, charge, etc.)

The Soviets often do not utilize the same restricted kind of general relativity that Western scientists adhere to.

Soviet papers in general relativity regularly point out the complete and unrestricted theory, where local spacetime curvature is allowed. They also point out that all conservation laws may be violated by such local curvature. Thus the Soviets have no unduly dogmatic respect for conservation laws.

Further, by assuming the possibility of local spacetime curvature, Soviet scientists have assumed the possibility of direct experimentation with general relativity on the laboratory bench.

In the West, we have assumed that such cannot possibly be done, because of Einstein's limiting assumption of no local spacetime curvature. Thus Western physicists are strongly conditioned away from electrogravitation.

This is particularly ironic since the basis for just such an experimental theory was produced by none other than Maxwell himself in his original theory of electromagnetism.

Indeed, shortly after the U.S. Civil War, we should have been developing antigravity spaceships. We should have developed electromagnetics a la Maxwell and been on our way to the planets of our solar system. For Maxwell had — admittedly somewhat unwittingly — given us the basis for the necessary engineering theory of unified electrogravitation.

Heaviside's Mutilation of Maxwell's Theory

Well after Maxwell's death, Oliver Heaviside helped to finalize what is today vector analysis.

Then he undertook to "translate" Maxwell's theory from quaternion form to the new vector mathematics form.

Now quaternions were devilishly difficult to calculate in. So much so, that a majority of the electrical scientists (there were not very many of them in those days!) were in despair.

Not to worry! Heaviside took a broadax, figuratively speaking, and simply chopped off the scalar term, leaving only the vector components.

With that artifice, he greatly simplified the calculations to be performed.

Of course, he also threw away the EM stress of spacetime! That is, he threw away the "gravitation" part of Maxwell's theory!

Let me stress this fact most strongly. **After Maxwell's death a single** man**—Oliver Heaviside—directly altered Maxwell's equations, eliminating localized electrogravitation and producing the form of the theory taught throughout the West today as "Maxwell's theory."**

Maxwell's theory has never been taught in Western universities! Only Heaviside's crippled subset of the theory has been taught!

Then, shortly before the turn of the century, a short, sharp "debate" erupted in a few journals — mostly in the journal *Nature*. Only about 30 scientists took part in the "debate."

It wasn't really much of a debate! The vectorists simply steamrolled right over the remaining quaternionists, sweeping all opposition before them.

They simply threw out the remaining vestiges of Maxwell's quaternion theory, and completely adopted Heaviside's interpretation

Thus, a little over a decade later when Einstein wrote his general relativity theory, he did not know that the original work of Maxwell already indicated the unification of gravitation and electromagnetics, and indicated the ease with which local spacetime could be electrogravitationally curved locally and *engineered.*

Accordingly, he placed the scientists of the West on a road which rigorously assumed that a unified field theory was yet to be discovered. It also strongly discouraged any experimentation aimed at curving local spacetime, for it assumed that such could not be done.

After Potsdam and World War II, a frustrated Stalin was to drive his scientists to review the entire scientific literature of the Western world, actively seeking a great new technical breakthrough area such as the Allies had demonstrated with the development and use of the atomic bomb.

Great Soviet institutes — one staffed, for example, with over 2,000 PhD's — were set up to thoroughly review all the Western scientific literature from its very beginning. Anything interesting, anomalous, or unknown was put aside for further examination.

It is a good bet that the meticulous Soviet scientists discovered the difference between Maxwell's original electromagnetic theory and Heaviside's mutilation of it. Great mathematicians that they are, Soviet scientists would have realized the implications of the difference. With their knowledge of unlimited general relativity, they would have made the connection to electrogravitation.

By 1950 they had indeed done so, and were deeply into the development of what they called "energetics", and I have called *scalar electromagnetics.*

They had also reached another milestone about the same time — 1950 or so.

After WWII, both the Soviets and the U.S. were keen on securing the best of the German scientists. The U.S. particularly wanted missile scientists and rocket engineers. The Soviets wanted them too; but they also wanted the German radar specialists and infrared specialists.

The West didn't care about the German radar scientists and engineers, and the IR fellows. The Soviets did, and they got them. That was to prove a most spectacular benefit indeed.

During the war, the Germans had placed extreme emphasis upon radar and radar absorbing materials (RAM). The German scientists had fantastically developed and extended the science of radar cross section — which is the heart of the matter and very, very complex. **They were much further ahead in radar cross section theory at the end of WWII than where the U.S. is today, in the opinion of** some **U.S. radar experts.**

So the Soviets started with a great jump on us in radar knowledge, and they have steadily increased the lead over the years.

In addition, the Germans had developed highly successful radar absorbing materials, and much of the theory to accompany them.

Such materials turn out to be the key to how to build and develop a radar phase conjugation mirror, to produce a time-reversed radar wave.

Thus, because of the German scientists, by 1950 or so the Soviets had already discovered phase conjugation. And they had discovered it in radar first, not in optics!

They would have been primed for the discovery by their great review of Western literature and the foundations of science, since they would probably have noticed that the time-reversed wave is a solution to the wave equation. If so, they would certainly have realized its generality throughout all physics, all frequency bands, and all types of waves.

Superb mathematicians that they are, the Soviets would certainly have made the Kaluza-Klein theory connection, and also realized that phase conjugate waves carry negative energy as well as negative time. They would quickly have seen the gravity and antigravity implications.

So about 1950 or so, the Soviet Union would have started phenomenology experimentation in earnest, with phase conjugate radar mirrors and phase conjugate radars. This is what was referred to as *energetics.* The Soviets began a massive program in energetics about the time of the beginning of the Korean War.

By 1957-8 the Soviets had progressed to the point of a giant scalar EM accident in the Urals which exploded nearby atomic wastes, devastating the area. They had also progressed to development of great new superweapons using their new energetics — weapons to which Khrushchev referred in 1960 when he informed the Soviet Presidium of a new, fantastic weapon in development, a weapon "so powerful that it could wipe out all life on earth if unrestrainedly employed."

About the same time (mid-to-late 50's), the Soviets had also started the eery low-level microwave radiation of the U.S. Embassy in MOSCOW, to see if the U.S. knew of scalar electromagnetics (energetics) and was developing its own electrogravitational weapons and defenses.

Building Upon Whittaker's Fundamental Work

In 1904, a most fundamental paper in the foundations of electromagnetics was delivered by the British mathematician E. T. Whittaker. (E. T. Whittaker, "On an expression of the electromagnetic field due to electrons by means of two scalar potential functions," Proc. Lond. Math. Soc., Series 2, Vol. 1, 1904, p. 367-372.).

In this important paper, Whittaker showed that the electromagnetic force field equations can be replaced with the derivates of two scalar potential functions.

He also derived the most general form of electromagnetic disturbances in the ether.

This means that the coupling of two dynamic scalar functions can replace vector electromagnetics in the vacuum.

Note that Whittaker's work pointing out the overriding importance of scalar fields also accents the erroneously discarded scalar part of Maxwell's quaternion electromagnetic theory even more strongly.

Let me explain now how I got from Whittaker's paper to scalar electromagnetics, Soviet Tesla weapons, free energy, antigravity, and electromagnetic healing.

When I discovered Whittaker's paper, I had already strongly objected that "charges" and electromagnetic vector force fields — as presently included in the Heaviside version of Maxwell's equations — included observable mass. Of course there was no observable mass in the vacuum, hence the prescribed kind of EM force fields could not exist as such in the vacuum.

Obviously the foundations of our ordinary electromagnetics theory were seriously flawed. Although my objections fell on deaf ears, I determined to examine the foundations of EM theory, discover the flaws, and at least point out the necessary corrections to be made.

Though this was an arduous task to undertake and it required many years, slowly the flaws showed themselves, and the necessary corrections slowly became clearer.

Most exciting of all, in working with several unorthodox researchers, I was able to see many of these new ideas tried, adjusted, and demonstrated. In addition, the proprietary discoveries of these colleagues continued to reveal new and unique principles and concepts. The only disadvantage was that I could not reveal the propriety apparatuses and demonstrations of my inventor associates, but only the principles and concepts that developed. In turn, I also developed principles and concepts to explain what they were doing and the results they were obtaining.

So over the years I have slowly been releasing the principles and concepts. Some of them are my own discoveries, many of them are the discoveries of my associates. Some of them are simply a mixture of both.

Early on, it became obvious that the Soviet Union was far ahead on this path, and was already utilizing the new unified field theory to build eery, powerful new superweapons.

Since no one else in the U.S. seemed to be "watching thin particular store" (I was rather universally regarded as some peculiar sort of fool!), I also began to compile information and data on the Soviet weaponization of this unrecognized technology. This information I have released in a series of papers, briefings, and books, the most recent being a 1-hour videotape, "Soviet Weather Engineering Over North America," 1985, and a detailed book, Fer-de-Lance: A Briefing on Soviet Scalar Electromagnetic Weapons, Tesla Book Co., Greenville, Texas, 1986.

Building upon Whittaker's important work, I formulated a conceptual revision to electromagnetics, which I dubbed *scalar* electromagnetics to accent that the observable EM vector force fields did not exist as such in vacuum, but dynamic scalar fields did. I also wished to call strong attention to the fact that observable force does not exist until an observable particle of mass is coupled to the interference of the two scalar fields (much like in the Aharonov-Bohm effect). The Soviets, of course, call this area *energetics,* Energetics technology has been used in gigantic weapons programs of the Soviet Union for decades, and it appears to be developed under the most highly classified program that the Soviet possess. All development and deployment of energetics weapons is under the KGB and controlled directly by that organization, not by the Soviet Armed Forces.

Peter Kapitsa, the great Soviet physicist, was once pressed by Nikita Khrushchev for a total defense against missiles and air- and space-borne vehicles. Kapitsa replied that it could only come from the new energetics. In 1960, of course, Khrushchev gleefully announced to the Presidium that a new, fantastic Soviet weapon was in the development, "so powerful that, if unrestrainedly used, it could wipe out all life on earth."

Ironically, Khrushchev "jumped the gun" before his new superweapons were deployed. In the fall of 1962 he began inserting long range missiles into Cuba, bracketing the U.S. with nuclear firepower in an attempt to immediately change the balance of power. Kennedy, of course, backed him down "eyeball to eyeball," so to speak, in a blunt confrontation, but promised not to invade Cuba.

Khrushchev, with his days numbered, was desperate to deploy his new superweapons and provide a dramatic demonstration to recover face.

By destroying the U.S.S. Thresher on April 10,1963 and, on the next day, producing a gigantic underwater explosion 100 miles north of Puerto Rico, the Soviets demonstrated that the new superweapons had been deployed. Khrushchev managed to retain his position a while longer.

In the 1960's and early 1970's, I was also deeply involved in the study of paranormal phenomena.

In 1969, I entered the Georgia Institute of Technology to pursue a Master's Degree program in nuclear engineering, graduating in 1971.

In 1973, I published a rather simple paper, "Quiton/Perceptron Physics: A Theory of Existence, Perception, and Physical Phenomena," in which I pointed out the nature of quantum change, gave a new definition of mass and acceleration, and pointed out the fundamental nature of inversion of time. The paper also contained a simplified derivation of Newton's laws of motion, relativistic form. The elements of this paper had been worked out in 1971 while I was finishing my Master's program in nuclear engineering. Finishing the work had been interrupted by a slight sidetrack — a tour in Vietnam from summer of 1971 until summer 1972.

At about the same time, I formulated a fundamental correction to Aristotle's logic, adding a fourth law of logic to Aristotle's three, and a proof of it. The new logic was of great use in discovering and uncovering new concepts in unified field theory.

Incorporating Kaluza-Klein 5-dimensional concepts, scalar EM became a field theory that unifies electromagnetics and gravitation.

Incorporating dynamic sum-zeroed EM vector systems (which are discarded in normal EM theory) allowed the direct engineering of the unified field theory, including structuring the vacuum, curving local spacetime, and producing effects at a distance and in higher dimensions. Actually it allowed the recovery of much of the scalar part of Maxwell's original theory.

I then realized that, inside a vector zero EM force field summation/multiplication, the virtual particle flux of vacuum/spacetime was ordered and controlled locally and macroscopically. This of course violated one of the major assumptions (a postulate) of quantum mechanics; the assumption that the structure of vacuum was randomized, and could not be deliberately ordered, engineered, and curved locally.

Adding phase conjugation (time reversal) aspects and extended quantum mechanical concepts allowed local antigravity and local curvature of spacetime to be included — again, on an engineering basis. It also allowed one to produce a mechanism responsible for Newton's third law, and to engineer the reaction force at will.

Further, it revealed that the law of entropy was simply the *positive time* statement; it showed that there was another half of the law, the *negative time* part or the law of negentropy.

In addition, a startling new concept of mind, thought, life, biofields, disease, and healing emerged from all this — again, on an engineering basis. As we stated in the beginning of this book, it is now an urgent necessity to release my work on the basis for electromagnetic disease and electromagnetic healing. We must produce a very quick, positive treatment and cure of AIDS and other coming lethal viruses before the world is decimated.

Accordingly, this work is being released in this book.

In this chapter we will next present some perhaps surprising material on phase conjugation, from the scalar EM viewpoint, after first briefly explaining symmetry and parity.

In following subsections, we will cover briefly the remaining major concepts in scalar electromagnetics. This will then set the stage for the following chapter, Extraordinary Biology, in which we will deal with the basis for unparalleled electromagnetic healing.

Symmetry and Parity

The basic idea of symmetry is the arrangement of the parts of a body or system about an axis so that two or more parts appear the same with respect to some operation.

The most obvious example is to look in a mirror, where we notice that our image has been reversed, left to right. Yet otherwise there is no difference; and so we may say that the reflection has "mirror symmetry." It's the same except that left and right are reversed.

If you know the details of a system at one point, and at another point you know that the system will possess mirror symmetry, then you can predict exactly what state the system will be in at the latter point. It will be "left to right reversed." You don't have to calculate the laws of reflection and the laws of motion of the system.

All the laws of nature that possess "mirror symmetry" have a special property: If the words "right" and "left" are interchanged in the statement of the law, then the behavior of a system that obeys the law is unchanged.

Thus symmetry became a powerful idea in physics. For a system with a great number of possible interactions, etc., one can usually eliminate a very great number of them due to symmetry considerations. In other words, if one can assume that symmetry of the system will not be violated, then all the possible interactions that would yield "broken symmetry" can be eliminated.

On the other hand, if symmetry is broken in a physical interaction, at least one of the conservation laws is broken in that interaction. Broken symmetry — and hence violation of individual conservation laws — is a well-established fact in particle physics today.

Another concept intimately associated with mirror symmetry is parity. Each particle is assigned a number (+1 or -1), depending upon what kind of particle it is. One adds up these numbers for an assembly of particles, to obtain an overall "parity" number for the system. If parity is conserved in an interaction, then this total number does not change in the interaction.

Table 13. SYMMETRY

- **SOMETHING IS SYMMETRIC IF IT REMAINS UNCHANGED UNDER A CERTAIN OPERATION**

- **A SPHERE IS SYMMETRIC WITH RESPECT TO ROTATION ABOUT ITS CENTER**

- **A CATHEDRAL ARCH IS LEFT AND RIGHT SYMMETRIC ABOUT A VERTICAL LINE THROUGH THE CENTER**

- **LAWS OF ELECTRICITY ARE SYMMETRIC WITH RESPECT TO REVERSAL OF POSITIVE AND NEGATIVE CHARGE**

Table 14. A FORCE FIELD IS A SPECIAL LOCAL SYMMETRY

"..THE FORCE OF GRAVITY IS SIMPLY A MANIFESTATION OF AN ABSTRACT SYMMETRY — A LOCAL GAUGE SYMMETRY — THAT UNDERLIES THE PHYSICS OF THE WORLD."

"ALL FOUR FORCES OF NATURE CAN BE GENERATED IN THIS WAY."

PAUL DAVIES, SUPERFORCE.
1984, p. 115

Table 15. GRAVITY AND LOCAL SYMMETRY

- **THE** LAWS OF PHYSICS CAN BE MADE SYMMETRIC EVEN UNDER LOCAL GAUGE TRANSFORMATIONS

- A GRAVITATIONAL FIELD IS INTRODUCED TO COMPENSATE FOR PLACE-TO-PLACE VARIATIONS

- THE GRAVITATIONAL FIELD IS NATURE'S WAY OF MAINTAINING A LOCAL GAUGE SYMMETRY

- IN THE ABSENCE OF GRAVITY, THERE IS ONLY GLOBAL SYMMETRY

Table 16. HINDSIGHT IS BETTER THAN FORESIGHT

- **FROM THE TWIN REQUIREMENTS OF**
  - **SIMPLEST LOCAL GAUGE SYMMETRY**
  - **LORENTZ-POINCARE SYMMETRY OF SPECIAL RELATIVITY**

- **ONE CAN CONSTRUCT OR INFER**
  - **MAXWELL'S EQUATIONS**
  - **ALL THE LAWS OF ELECTROMAGNETICS**
  - **THE EXISTENCE OF RADIO WAVES**
  - **THE POSSIBILITY OF MOTORS AND GENERATORS**
  - **ETC.**

- **IN REALITY THESE WERE FIRST DISCOVERED EXPERIMENTALLY**

Table 17. WHEN SYMMETRY IS VIOLATED [BROKEN]:

- **A "NON-OBSERVABLE" TURNS OUT TO BE AN OBSERVABLE**
- **AN INVARIANCE IS BROKEN**
- **A CONSERVATION LAW OR SELECTION RULE IS BROKEN**

COMMENTS:
- **A VIRTUAL OBJECT BECOMES AN OBSERVABLE OBJECT**
- **LOCAL SPACETIME BECOMES CURVED, AT LEAST TO SOME POTENTIAL INVOLVING THAT OBJECT**

Table 18. SOME PROVEN ASYMMETRIES

- **POSITIVE AND NEGATIVE SIGNS OF ELECTRIC CHARGE**
- **TIME REVERSAL**
- **RIGHT/LEFT HANDEDNESS**

Table 19. SPONTANEOUS SYMMETRY BREAKING

PRESENT VIEW

1. IF 4-MOMENTUM $K\mu = 0$,

   $\O_{(X)} = \O_{VAC}$

   WHERE $\O_{(X)}$ IS AS COMPLEX

   AS ANY SPIN-0 FIELD
2. **FOR** VOLUME Ω » RELEVANT MICRODIMENSION.

   $K\mu \neq 0$ BUT $K_M \sim 0$

   $\langle \O_{(X)} \rangle \neq \O_{VAC}$ [INSIDE *Q]*

   $\langle \O_{(X)} \rangle \neq \O_{VAC}$ [OUTSIDE Q]
3. INSIDE Ω, SYMMETRY PROPERTIES DIFFER

   FROM THOSE OUTSIDE Ω
4. T. P AND CP MAY BE SLIGHTLY ASYMMETRIC
5. CPT REMAINS INTACT

SCALAR EM VIEW

1. IF ARTIFICIAL POTENTIAL $\O_{ART} >> 0$, VOLUME Ω

   MAY BE SMALL
2. $\O_{ART}$ MAY BE ENGINEERED IN
   - SPATIAL SIZE
   - LOCATION
   - MAGNITUDE
   - SUBSTRUCTURE
3. SYMMETRY PROPERTIES INSIDE Ω MAY
   - DRASTICALLY DIFFER
   - BE DELIBERATELY ENGINEERED
   - BE PATTERNED
4. T, P, AND CP MAY BE APPRECIABLY ASYMMETRIC
5. CPT MAY BE ASYMMETRIC

Table 20. WHY SUCH DRASTIC DIFFERENCE?

IN PRESENT THEORY

$\emptyset_{(X)}$ • **IS USED ONLY AS A PHENOMENOLOGICAL DESCRIPTION**

- **MICROSCOPIC STRUCTURE OF $\emptyset_{(X)}$ OF NO CONCERN**
- **ONLY LONG-WAVELENGTH LIMIT OF FIELD IS OF INTEREST**
- **VACUUM ENGINEERING IS ONLY A REMOTE POSSIBLITY**
- **ACTION AT A DISTANCE IS NOT POSSIBLE**
- **LOCAL SPACETIME NOT CURVED**

IN SCALAR EM

$\emptyset_{ART}$ • **REPRESENTS A LOCAL CURVATURE OF SPACETIME [LOCAL GENERAL RELATIVITY]**

- **MICROSCOPIC STRUCTURE OF $\emptyset_{(X)}$ IS DETERMINISTIC AND COHERED INTO MACROSCOPIC STRUCTURE**
- **ALL WAVELENGTHS OF THE FIELD ARE OF INTEREST**

$\emptyset_{ART}$ **WAVES ARE REAL, ENGINEERABLE AND ELECTROGRAVITATIONAL**

- **VACUUM ENGINEERING IS A REALITY**
- **ACTION AT A DISTANCE IS POSSIBLE**

Table 21. ASPECTS OF STRONG LOCAL ASYMMETRY

- **PROPERTIES OF AN OBJECT MAY DIFFER APPRECIABLY FOR**
  - **DIFFERENT OBSERVERS**
  - **DIFFERENT DETECTING MEANS**
  - **ONE TIME TO ANOTHER**
  - **ONE POSITION TO ANOTHER**

- **CONVERSATION LAWS MAY BE APPRECIABLY VIOLATED**
  - **ENERGY**
  - **CHARGE**
  - **SPIN**
  - **MOMENTUM**
  - **ANGULAR MOMENTUM**

- **LOCAL SPACETIME IS CURVED**
- **LORENTZ INVARIANCE OF VACUUM IS VIOLATED**
- **MAY BE A LOCAL "SINK" OR "SOURCE "**
- **GRAVITATIONAL/INERTIAL EFFECTS FROM EM**
- **TRANSLATION BETWEEN VIRTUAL AND OBSERVABLE**
- **ELECTROGRAVITATIONAL SOLITONS**
- **ACTION AT A DISTANCE**
- **TRANSMUTATION EFFECTS MAY EXIST**
- **SCALAR/PSEUDOSCALAR FIELD TRANSLATION**

For years the idea of conservation of parity convinced physicists that it would never be possible to tell right from left in the universe, Then in 1956, Yang and Lee pointed out a class of reactions where parity need not be conserved. This effect — broken parity — was confirmed experimentally, and so certain parts and interactions of the universe do possess asymmetry.

The result of all this was that particle physicists established that

(1) symmetry can be, and is, sometimes broken, (2) individual conservation laws can be, and sometimes are, broken.

Particle physics, however, concerns itself primarily with microscopic interactions. Most of the delightful new things discovered in the microworld have not yet been applied — by *physicists,* that is — in the macroworld.

If you can successfully apply broken symmetry in a major system, for example, you should be able to violate the conservation of energy law and thus produce a "free energy" engine. Several inventors with whom I work have done precisely that. The techniques and technology are still primitive and they need much further development, but the principle has been clearly established and replicated.

Physics is correct in certifying broken symmetry, and you can do it in large systems as well as in microscopic particle interactions. Of course you also *curve local spacetime* as well, something which Einstein and his followers have assumed cannot be done.

Charge-Parity-Time ***and Negative Energy***

The upshot of all this is that the physicists came up with the idea that what is really conserved is a consolidated thing called Charge-Parity-Time. You don't have to conserve any one or two of these three, but only the combined product.

Here they overlooked one key factor that is very important to our thesis: In the photon interaction, if you reverse charge and time, you reverse the sign of the energy.

That is, a photon that is emitted from a positive charge carries negative time negative energy. It is different from a photon that is emitted from negative charge, for that one carries what we have conventionally established as positive energy.

Thus physics has not considered the exclusive use of negative-energy / negative-time photons, even when some of its interactions produced them. Instead, it has just lumped together photons and antiphotons, and considered them both to have positive energy.

Antimatter systems don't have positive energy, for example; they have negative energy. *Here we don't use the positive and negative signs to indicate the direction the energy is traveling, but the fundamental kind, of energy that it is—time forward or time reversed.*

For example, consider the local conservation of energy. As conditoned, one almost always unconsciously thinks of the conservation *of positive* energy, without so stating. Yet one is perfectly free to build a system into which he inputs 100 joules of positive energy, and from which he outputs 300 joules of positive energy and 200 joules of negative energy!

For the real conservation law, that's the equivalent of putting in **100 j**oules of positive energy and outputting 100 joules of positive *energy.*

Now negative energy will run motors, light lamps, etc. —often much better than positive energy. It can be transmitted, transformed, stepped up or down in "voltage," rectified, received, etc. It can be translated into positive energy or vice versa.

Circuits run "cool" when using negative energy. If you short out a circuit of negative energy so that a violent discharge occurs, it produces cooling instead of heating, greatly lessening the danger of fire and destruction. If you mix negative energy onto a line that is carrying the same amount of positive energy, however, the two negate each other and there is suddenly "no power" on the system.

Think of what you were taught in simple arithmetic. You can take a zero — the absence of any single specific number — and replace it with any set of multiple numbers whose algebraic sum is zero. The presence of this special set of numbers you choose does not violate the condition that the zero means that you could not use just a single number.

Although zero is the absence of just a *single* thing, it can be the presence *of multiple* things.

The same thing works with energy. In the microworld, everything is fantastically energetic, and wildly fluctuating. For example, in a copper wire carrying a current of one ampere, wild momentary fluctuations at extremely high frequencies are occurring.

According to classical electrodynamics, the instantaneous current in a single one of these micro-micro fluctuations may reach thousands of amperes, and the instantaneous voltage may reach 10^{40} volts or more. As can be seen, the instantaneous energy and power are enormous. Yet outside the wire, we see a very placid and peaceful situation.

TIME IS NOT OBSERVABLE



WHAT THEN IS TIME?

WHERE THEN DOES TIME EXIST?

Figure 33. The riddle of time. Unsolved by both physicists and philosophers.


PHOTON INTERACTION CREATES OBJECTIVE AND NONOBJECTIVE
NUCLEAR FISSION MODEL
NUCLEUS
NEUTRON
COMPOUND NUCLEUS
FISSION FRAGMENT
FISSION FRAGMENT
PHYSICAL CHANGE MODEL
L_1^3
MASS (M_1)
$L^2 \Delta T_1$
PHOTON
$L^3 \Delta T_1$
COMPOUND UNION → SPACETIME
$(M\Delta T_1)$
$L^2 \Delta T_2$
PHOTON
L_2^3
MASS (M_2)
VIRTUAL STATE DISCONNECTED
VIRTUAL STATE CONNECTED
VIRTUAL STATE DISCONNECTED
FOURTH LAW OF LOGIC APPLIES
FIRST THREE LAWS DO NOT
THREE LAWS APPLY
FOURTH DOES NOT
THREE LAWS APPLY
FOURTH DOES NOT

Figure 34. Raindrop model of physical change.

Table 22. FLOW OF TIME

- **PHOTON INTERACTION CONSTITUTES TIME CHANGE**
  - $\rightsquigarrow \langle \text{NEGATIVE CHARGE} \rangle \rightarrow + \Delta T$
  - $\rightsquigarrow \langle \text{POSITIVE CHARGE} \rangle \rightarrow - \Delta T$
- **CHARGE-PARITY-TIME [CPT]**

  $\rightsquigarrow \langle e \rangle \rightarrow + \Delta T$ **(note: ~ = photon)**
  - **UBIQUITOUS**
  - **PREDOMINANT**
- **ANTIPHOTON IS A PHASE CONJUGATE REPLICA**

Table 23. PHYSICAL CHANGE

- **COMPOSED OF ACTION**
  - **h = BASIC QUANTUM**
- **TWO CANONICAL VARIABLES**
  - **ENERGY/TIME (dE dt)**
  - **MOMENTUM/LENGTH (p L)**

    ETC.
- **ENERGY/TIME**
  - **h = (+ E) (+ t)**
  - **h = (- E) (- t)**

Free Energy and Antigravity

Let's say the current flowing in the wire is alternating current at a frequency of one megahertz. Let's say we have one watt of power in the wire (there's one volt on it, and one ampere of flowing current). As a working rule-of thumb for engineering use, the available absolute micropower in an alternating current in a wire can be taken as:

$$P_a = 40 \times f \times P_c \qquad (4\text{-}10)$$

where P_a is the absolute power available, in watts; f is the frequency in Hertz; P_c is the conventional power available, in watts; and 40 is a constant of proportionality.

In our example, the absolute power actually available in the current is 40 million watts! We've got about 20 megawatts of positive power, and about 20 megawatts of negative power, in there — *in the microstructure of the electrical current itself--but disintegrated*

By applying unconventional scalar EM engineering techniques, we ought to be able to take such an "input" (a straight wire with one watt of power at a frequency of a megahertz) and get an "output" of up to 40 megawatts. It is relatively straightforward to get out 1 megawatt; such ratios have actually been achieved on the laboratory bench by my associates.

Of course we will have curved the local spacetime to do such a thing. But it is absolutely permitted to do that, by the laws of nature as best we know them from particle physics.

It is also possible to do that by Maxwell's original theory. And it has been proven in the laboratory.

Table 24. NEGATIVE ENERGY

- **CAN BE**
  - **GENERATED**
  - **TRANSMITTED**
  - **TRANSFORMED**
  - **RECTIFIED**
  - **RADIATED**
  - **TRANSLATED**
- **EASILY POWERS**
  - **AC MOTORS**
  - **DC MOTORS**
  - **LAMPS**
  - **TRANSFORMERS**
  - **RECTIFIERS**
- **CIRCUITS STAY COOL**

In scalar electromagnetics, we deliberately seek to produce such effects and systems by nonclassical application and extension of the modern conservation law CPT. And we include negative energy/ negative time production in those systems and effects.

Here's the extended magic rule: First we write down the expression **CPTEGS.**

In this expression, C stands for charge, P stands for (space) parity, T stands for time, E stands for energy, G stands for gravity, and S stands for entropy.

We are referring here to the algebraic sign of each term, and to a complete photon interaction (absorption and re-radiation) with a charged particle inside an atom of matter. Specifically, we are refferringto the result, after the reaction has occurred.

Normally the photon interacts with one of the electrons in the atom's outer shell. This interaction with the negative electron charge *produces* the "normal" physical world/physical reality we see around us. In the interaction, normal parityis produced, andnormal gravitation (attraction of mass) is produced. Also, in a series of such interactions, the normal entropy (movement from order to disorder) is txperienced and produced.

So in the expression CPTEGS normally the charge term is negative, and every other term is positive, for the complete photon interaction in an atom.

Now here is the magic engineering rule: In the complete photon interaction with a charged particle in an atom, if one of these terms is reversed in algebraic sign, all the others will be reversed also.

For example, if the photon interacts with the positively charged nucleus,then parity is reversed, the bit of time-advance is reversed, a negative/time-reversed photon is emitted, a tiny bit of antigravity is produced in the nucleus, and negentropy is produced. By negentropy, we mean that the emitted photon exhibits the strange characteristics of time reversal, and hence it will return from disorder to order.

This rule is actually a statement of phase conjugation and time reversed waves, as we shall see later.

For example, using the rule, the production of antigravity is straightforward. Simply produce a great excess of negative energy and negative time in an object or generator by scalar photon interaction with the nucleus, at a sufficient rate.

In negative time, gravitational force is reversed. Thus in negative time gravity is a repulsion, not an attraction. Production of excess negative time in the atomic nuclei of a system produces antigravity in that system. Period.*

*At 100 Hz about 500 negative watts/lb is required for flotation. At 1 GHz, the effect is so *weak it cannot be measured, and no amount of power will float* the mirror.

Let me amplify that statement. There are two kinds of energy, negative and positive. Normally, everyone thinks only of positive energy.

Take Einstein's formula for the amount of energy that's "bottled up" and stored in mass:

$$E = mc^2 \qquad (4\text{-}11)$$

That's positive energy and positive mass. It automatically implies that we are looking at things where time is forward-going.

Now suppose we "charge up" that mass with negative energy: Then the mass is negative, like this:

$$-E = (-m)c^2 \qquad (4\text{-}12)$$

And negative mass is repelled by positive mass. (Like mass G-charges attract, unlike mass G-charges repel.)

That's all there is to it! Simply charge up the protons/neutrons of the atomic nuclei of a mass with excess phase conjugate (negative) energy/time, and it exhibits antigravity compared to the earth. Nothing could be simpler.

Again, it's been done in the laboratory by an associate.

So, with respect to a negative energy/negative time generator, you just add more load and draw more negative power from the machine, forcing it to produce more. It produces more negative time, and hence more antigravity and more "repulsion." When the repulsion balances the earth's attraction, the system "floats in air." Draw still more power by adding still more load, and it accelerates upward. Draw less power by decreasing the load, and it sinks downward again. That's all there is to it.

We should have been working upon this, shortly after the U.S. Civil War.

Again, there exist two completely different kinds of electromagnetic energy: positive and negative. These have been totally and hopelessly confused by modern physics, even though physicists sometimes use these terms.

But in dealing with CPTEGS in the photon interaction in an atom, we must clearly keep in mind what kind of energy we are dealing with.

The basic engineering rules are these: (1) If any one of the factors - C, P, T, E, G, or S — is reversed, all the others are reversed. (2) If positive charge is involved in the photon interaction, then time (carried by the emitted photon) is negative and so is the energy carried by it. (3) The simplest scalar EM wave may be considered as two EM waves locked together (modulating each other), where one component wave carries positive energy and time and the other component wave carries negative energy and time. (4) Separation of the two components by interaction with charged particles creates both positive and negative time and energy. (5) If the interacting particle is negatively charged, the positive energy/positive time component will interact with it. (6) If the interacting particle is positively charged, the negative energy/negative time component will interact with it. (7) The interacting particle phase conjugates (time reverses) the component with which it interacts. (8) The primary interaction with negative electron shells of atoms yields positive energy and positive time: constituting ordinary physical reality as we observe it. (9) The secondary interaction with the positive atomic nucleus produces phase conjugated (time-reversed) physical reality. (10) Secondary interaction (nuclear phase conjugation) normally produces Newton's third law of motion. (11) In Newton's third law, the reaction force need not be equal, and need not be antiparallel. Note, however, in such case local spacetime is curved. (12) The present law of entropy is only the positive-time half; the other (negative time) half is the negentropy law.

Phase Conjugation (Time Reversal)

It is a most remarkable fact that Soviet radar engineers and radar scientists are also trained in optics. While this seems little short of astonishing by Western standards, the Soviets have an exceedingly good reason: As a matter of course, most Soviet radar systems are also operable in, or associated with another system that is operable in, a time-reversed (phase conjugate) mode.

In this mode the radar and/or its associated system is also an extremely powerful directed energy weapon, having capabilities undreamed of in the West.

A phase-conjugate (time-reversed) wave actually is a wave that travels backward through time.* That is, it is capable of precisely retracing the path through space, taken by another wave that traveled that path to a nonlinear mirror, stimulating the reflection of the time-reversed wave.

Further, in retracing its invisible path through space, the phase conjugate replica wave does not diverge as do normal waves. Instead, it continually converges upon its invisible trace.

Consequently all its energy arrives back at the distant source that emitted the stimulus wave originally. This was Tesla's original secret of his "wireless transmission of energy at a distance with no losses."**

It can easily be shown, however, that the phase conjugate wave is a legitimate solution to the wave equation. Hence it is a general property of all types of waves: sound, magnetohydrodynamic, etc. It is not confined just to the optical band.

Obviously such a startlingly different wave has phenomenal uses. Literally it ushers in a new physics.

Let us turn now to look at this strange wave that has emerged on our scientific horizon.

In the late 1960's, Soviet researchers cautiously pointed out the possibility of a time-reversed wave. Papers appeared in the open Soviet scientific literature, and shortly thereafter U.S. physicists began to read about it.

In 1972, Soviet scientists visited Lawrence Livermore Laboratory and specifically briefed U.S. scientists on the optical phase conjugation (OPC) phenomenon. Thereafter the effect became of increased interest to American scientists.

(Note, however, that phase conjugation (PC) is a major phenomenon of all physics. It is not confined merely to the optical spectrum, nor just to electromagnetic waves. Phase conjugation is a general phenomenon true of all waves, regardless of type. We will primarily discuss OPC, since most Western experimentation has

*The external positive-time observer sees this time reversal as length (space) reversal.

**The great electrician had actually discovered what today is known as phase conjugation or time reversal of EM waves.

been in the optics domain, and the literature is rich in that respect. However, we also point out that Western scientists have absolutely no inkling of the mechanism causing OPC. They have simply written a model for a time-reversed wave by taking the equation of a normal wave und writing the conjugation (adding an asterisk exponent) to the appropriate term, and pointed out that this new equation also satisfies Maxwell's wave equation. They also do not clearly recognize that an EM wave carries time and energy, and that a time-reversed EM wave carries negative energy and negative time. Further, they do not at all comprehend the startling implications for generating gravitational fields, including antigravity and inertial effects, directly on the laboratory bench.)

In optical phase conjugation, when an input EM wave (ordinary) enters a nonlinear medium, the medium "reflects" or produces a strange, time-reversed EM wave in response.

Figure (35a) shows the effect. In the figure, E1 is the normal input wave, entering a distorting, nonlinear medium (the "blob") as shown. Wave E_1 moves on through the blob, emerging on the other side and continuing, though now in distorted form.

The medium produces a second wave, E_2, which precisely retraces the steps of E_1 That is, everywhere E_1 is, E_2 now appears. The phases of the E_2 wave are precisely reversed from those of E_1 The only difference in the two waves is that wave E_1 carries positive time and positive energy, while wave E_2 carries negative time and negative energy.

(U.S. physicists are well aware of everything in the above statement except for the negative energy portion.) The historical background of the phase conjugate wave is given in Table 25.

(We strongly stress that the West did not discover the time-reversed wave; the Soviets did. At the time (late 1960's) this appeared in the open Soviet literature, the Soviets had already been using it for about two decades in their giant energetics (scalar electromagnetics) weapons development program.)

However, to return.

The time-reversed wave is called the phase conjugate replica of wave E_1. The overall characteristics of the phase conjugate replica E_2 are summarized in Table 26.


X
0
Z
E2
E1
E2
E1
DISTORTING
MEDIUM

a. Phase conjugation by a nonlinear, distorting medium.


SOURCE
ORDINARY
MIRROR
PHASE-
CONJUGATE
MIRROR
SOURCE

b. Ordinary mirror reflection versus phase conjugate mirror reflection.

Figure 35. Phase conjugate reflection of a time-reversed wave.

Table 28. PHASE CONJUGATE WAVES

- NONLINEAR OPTICS TRANSIENTS
  - DISCOVERED BY SOVIETS
  - LATE 60s-EARLY 70S
- **PRESENTLY** "HOT ITEM"
- INITIALLY THOUGHT RARE
- NOW KNOWN WIDESPREAD
- THIRD POWER OF E-FIELD
- S**TILL** MUCH UNEXPLORED

Table 26. PHASE CONJUGATE REPLICA

- TIME-REVERSED
- CARRIES NEGATIVE TIME
- CARRIES NEGATIVE ENERGY
- "HEALING" PROPERTY
- DISTORTION CORRECTION
- F**ROM** DISORDER TO ORDER
- **MAY** DWARF INPUT WAVE

Table 27. DISTORTION CORRECTION THEOREM

"If a scalar wave E_1 (r) propagates from left to right through an arbitrary but lossless dielectric medium, and if we generate in some region of space [say near z=0] its phase conjugate replica E_2 (r) , then E_2 will propagate backward from right to left through the dielectric medium, remaining everywhere the phase conjugate of E_1."

We point out here that the basic nonlinearity (nonlinear medium) in spacetime is a single particle of mass. In a photon interaction with that particle of mass, the interacting (input) photon (positive energy, positive time) causes the generation and emission of a phase-conjugated (time-reversed) photon. This time-reversed photon provides the precise mechanism for generating Newton's third law: **For every action there is an opposite and equal reaction.** This will be covered later.

But back to our nonlinear medium, and the two waves E_1 and E_2.

E_1 and E_2 are "locked together" as a scalar EM wave unless something else is specially done to separate them. That is because the nonlinear medium is a *modulator,* and the two waves modulate each other (lock together as a single wave).

(We interrupt again to strongly point out this fact: This directly shows that all EM waves in vacuum exist as scalar EM waves, not as the so-called Maxwell-Hertz transverse waves of conventional theory. Nikola Tesla, the greatest electrical scientist the world ever produced, always adamantly insisted that EM waves were "sound" type waves, not "transverse" waves. For one thing, the vacuum-medium would have to be a solid to produce transverse waves! Tesla even visited Hertz in Europe and tried to convince him of the error of his so-called "proof of transverse EM waves." Tesla found Hertz, adamant on the subject, however, and returned without changing Hertz's mind. Ironically, Tesla was right and all the textbooks in **the** Western world have been consistently in error as to the nature of the EM wave in vacuum.)

We simply state here that, for a single-frequency EM sine wave in vacuum, a "full photon" of that wave in vacuum is actually a *single sine-wave oscillation.* The positive (positive energy, positive time) half of that sine wave is the same thing as a virtual electron (negative charge). The negative (negative energy, negative time) half of that sine wave is the same thing as a virtual positron — a virtual electron travelling backwards in time, or "time-reversed", which we detect as length-reversed and charge-reversed.

Further the vacuum — including the vacuum inside each relatively empty "mass structure" such as an atom or molecule — is **a** seething inferno of activity of virtual particle fluxes. It is upon that medium that all physical reality and physical changes are impressed. Thus there is nothing static in the world; what actually exists is *switching of virtual particle fluxes.* What we call a "static thing" is only an equilibrium in this switching activity. And, once switched on, any stream continues until switched off or switched to change it.

For that reason, the full photon has always contained twice as much absolute energy as is provided by the presently used equation

$$E = hf \qquad (4\text{-}13)$$

Where E is energy, h is Planck's constant, and f is frequency.

One half the photon carries negative energy and negative time, while the other half carries positive energy and positive time. In the full photon interaction, one half of the photon interacts and "switches off" the stream. Thus the photon interaction makes a single change of action, energy x time, both switching on the beginning of the quantum change and switching off the ending of it.

The full photon in vacuum is, and has always been, a scalar EM photon. It rigorously is the presently accepted photon plus its directly "hooked on" and accompanying phase conjugated replica photon.

That is, in terms of the present physical view, the scalar electromagnetics view of a full photon in vacuum is that it consists of a photon and its antiphoton, directly combined in serial fashion. Further, this antiphoton part is not identical to the photon, since it is time- and energy-reversed.

The present physics makes no distinction between the two types of photons, hence makes no distinction between positive and negative photon energy. It also still considers "static" things to independently exist. It does not pursue the fact that all things appearing "static" are equilibrium states in nearly unbelievably intense virtual particle streams. Since it does not pursue that fact, it does not build a "switching" model for quantum change, not does it arrive at a method of directly engineering these "switching" operations.

For that reason, present physics has totally missed local general relativity and the engineering of spacetime curvature by electrogravitational methods, as was contained in

Maxwell's original theory.

For the same reason, present Western physics has not worked out the basic mechanism that produces phase conjugation, and it has not realized that all conservation laws can be locally violated with the new methods — methods actually hailing back to Maxwell's original theory!

Now returning again to our nonlinear medium and waves E_1 and E_2:

It is possible to separate (demodulate) wave E_2 from wave E_1 In that case, E_1 is an ordinary EM wave, carrying positive energy and positive time. E_2 is a phase conjugate replica, carrying negative energy and negative time.

Irradiation of an atom in a new sample of material with a normal EM wave such as E_1, just provides the normal photon interaction with the electron shells. That is, the electron part of the full photon adds to the orbital electron's energy state in positive time, raising the orbital electron to an "excited state." (Remember, this has switched on a continuous process of "keep raising the energy level of the electron" in positive time.) The "state-increasing" orbital electron then interacts with the second, positron-part of the full photon, which switches off the increasing, leaving the electron in its "static excited state." Simply put, one half of the full photon turns on an uplifting spray, and the second half of the full photon turns off the uplifting spray, leaving the electron in equilibrium state at a new level.*

Thus in orthodox physics we have taken the view that an electron in a shell absorbs a "photon" from the incident wave, taking extra energy and being raised into an excited energy state.

In the orthodox view, the excited-state electron then decays to release another ordinary photon (since it comes from a negative charge).

What actually happened was that, when the "full photon" of the incident wave is absorbed by the orbital electron, increase of the electron energy is switched on, then switched off, leaving the elec

*We state here a magnificient principle without proof. When one furnishes (inputs) electrical power to a system, all the "input work" is expended purely upon switching fields by fighting against them in brute-force fashion. E.g., electrical power furnished to an electric motor does **not** run the motor, but only continually wrestles the internal fields to switch them. Obviously, to build an over-unity device, one must get it to switch its own fields, at least a significant fraction of the time.

tron in equilibrium at a new energy level.

What happened in the middle was phase conjugation. In absorbing the first half of the incident full photon, the electron acted as a phase conjugate mirror (we will explain that term shortly). It emitted a forward-travelling phase conjugate replica (PCR) of that first photon half, and this conjugate replica entered the nucleus, where it is absorbed to cause the Newtonian reaction force. Note that this PCR emission by the electron does not generate recoil in the electron-PCM, as is well known in OPC theory and experiment.

The same type of phase conjugation happened when the state-increasing electron absorbed the second half of the incident full photon. It phase conjugated again, sending this half to the nucleus to acompany the former PCR half. In the nucleus, this second half switches off the increase in excited state of the nucleus that was engendered by absorption of the first half.

The photon interaction is a process for switching on and off a continuous rate of action increase or decrease.

At the conclusion of the full photon absorption, both the orbital electron and the nucleus are in excited states. The nucleus has incre**ased** its gravitational mass.

Then the situation precisely reverses. Both nucleus and electron dec**ay,** again emitting full photons and again phase conjugating.

The PCR photon emitted by the nucleus reduces the positive mass of the nucleus. The PCR photon emitted by the electron is reversed from the electron's absorption record, reducing the negative charge's energy state, and the electron is said to "decay" from its excited state. The PCR photon emitted by the electron now (to the observer) will appear to carry positive time and positive energy.

(In passing, we point out that, actually, the situation is far more complicated. Both the electron and the positively charged nucleus are enmeshed in continuous streams of virtual particle flux, including intense streams of virtual photons. One must go to n-wave mixing, where n is greater than 4, to fully understand the total reaction. The main points are, the Newtonian reaction forces within the atom are generated by phase conjugation, the photon emitted by the decay of an excited state electron will normally carry what we call positive energy and positive time, and the photon emitted by the decay of an excited state positive charge will normally carry what we call negative energy and negative time. Full coverage of these interactions is beyond the scope of this book, and must wait for another effort in the future.).

Now once again we return to our simplified model of phase conjugation, and waves E_1 and E_2 in our nonlinear, modulating medium!

As we stated, we can engineer the situation so that the phase conjugate replica E_2 can be separated from E_1. A separated E_2, however, is a quite different breed of cat. It is a phase conjugate wave, carrying negative energy and negative time.

E_2 is a magic wave indeed!

Irradiation of the nucleus of an atom in a new sample of material with a phase conjugate replica such as E_2 causes the nucleus of the atom to interact in reverse of its normal interaction.* That is, one of the positive charges in the nucleus interacts with a photon resulting from wave E_2, and goes into an excited "negative energy" state. That state, in decaying, emits an ordinary virtual photon which promptly interacts with a virtual positive charge in the nucleus, which decays to emit the virtual photon, which interacts with another positive charge in the nucleus, etc.

In other words, the negative energy of the absorbed antiphoton is captured by the nucleus, and the nucleus overall does not *immediately* decay to discharge the negative energy.

Instead, the nucleus acts as an accumulator or capacitance, charging up and then discharging far more slowly than the normal photon/electron interaction.

(For the purist, the nucleus does phase conjugate the input negative energy/negative time wave, and phase conjugates it again — upon an electron in the electron shells, through spin coupling This second phase conjugate replica is now just a normal EM wave, and the electron exhibits a normal EM interaction. Thus **our** instruments (Which are electron wiggle detectors) detect a normal

---

*Irradiation of the nucleus with a PCR wave is easily accomplished by using ordinary magnetic resonance, and modulating the PCR wave upon the magnetic carrier, as Antoine Priore did.

EM wave detection and do not discriminate between photon and antiphoton halves of a full photon. For that reason, scientists have not clearly noticed the difference between positive and negative energy, and between photons and antiphotons. They have also not resolved the basic conflict between the particle and wave theories of electromagnetics. *Note that the full photon concept, where the full photon is a normal photon and phase conjugate replica of that photon hooked together into a single sine wave, resolves the long-standing wave-particle controversy.)*

In most of their instruments, present scientists are detecting a secondary normal EM wave for the phase conjugate replica interaction, since the phase conjugate interactions in the instrument are not sorted out, and since the instruments measure only one kind of PCR, that emitted by a negatively charged electron. Hence scientists think the antiphoton has positive energy, and interpret it in positive time. Consequently they tend to accent that the wave is "phase-reversed," and not accent the negative time/negative energy implications since they have not clearly sorted them out.

Let us return to our consideration of the irradiation of the nucleus of an atom (with an incident E_2 phase conjugate replica wave carrying negative energy and negative time, with respect to our electron-wiggle-detecting observer).

AS irradiation continues, the actual "structured charge pattern" existing on the incident E_2 wave slowly charges up the nucleus of the atom with that exact charge structure, in the negative energy/ negative time state.

We shall find that most interesting fact of great utility when we later discuss the mind, thought, cellular control systems, and generating a specific electromagnetic phase conjugation pattern to reverse cellular disease.

We shall also find that it is of great interest in accomplishing antigravity when we use extremely low frequency PCR irradiation.

The Phase Conjugate Mirror

Any system which phase conjugates the input wave and returns a phase conjugate "reflection" is called a phase conjugate mirror, or PCM for short.

But the phase conjugate mirror has some very unique properties, as can be seen in figure 35b.

For example, if you look in a *normal* mirror, you see your own reflection. You see your shoes and legs, for example. Light from your shoe scatters across the mirror, and it hits one spot on the mirror which reflects it at the proper angle to strike your eye.

But that simply doesn't happen with *a phase conjugate* mirror! If you were looking into a phase conjugate mirror (PCM), the light that left your shoe and scattered across the mirror would be reflected right back to the shoe, since it would retrace the path taken by the previous light striking all across the PC mirror from the shoe. So all you would be able to see would be two black dots: the retinas of your eyes. Light reflecting off them and striking the PCM would be reflected back to the source — the retinas — so you could see that light and that light only.

This path reversal is most important to keep in mind. With a phase conjugate signal, you are not functioning with an ordinary signal. Further, it has a "precursor" path taken by the incident wave that stimulated its emission from the PCM. Unless interfered with, the PCR will trace back down the invisible vacuum trace of that incident wave, or back down its wave path, like electricity goes down a wire.

This, by the way, is the secret of Tesla's wireless transmission of energy at a distance with no losses.

When broadcast into space, a normal EM wave (positive time, positive energy) diverges or scatters from its path.

Precisely the opposite happens with a PCR wave. When broadcast (reflected) into space, the PCR wave continually converges back upon the invisible trace taken by its incident stimulus precursor. Thus all the PCR energy is continually converging upon an invisible beam or "wire" through the vacuum, back to the source of the original incident wave.*

If the PCR wave is highly amplified (and means to do this are now well-known), then large amounts of EM energy can be precisely

---

*One can effectively move the entire imprinted vacuum path, however, by adding an additional input vector wave computed so that the **resultant** input would have come from the desired shifted distant point. In this way the PCR can be steered in space to lead and intercept a distant moving target.

returned to distant points from which a stimulus wave of any kind is received.

If a micro-microwatt is received from a point thousands of miles distant, then a gigawatt can readily be returned precisely to that distant point.

This was Tesla's magic secret. The great electrician had discovered phase conjugation, though he did not use that term. He did, however, point out that he could create an invisible wire through space to a distant point, and could send any amount of energy to that distant point without any scattering losses along the way.

He also accomplished the same thing with sound waves and mechanical waves. He pointed out that he could produce an undiminished physical (mechanical) effect at any distant point, and could eventually split the earth if he added power long enough.

Tesla had given the principles of radar in World War I! He later even spoke of his "big eye that can see at a distance." Here he was probably referring to stimulating the emission of a PCR return from that target. The PCR would automatically correct for the distortion in the intervening medium, and fairly sharp pictures of the distant scene — without showing the size dispersion of distance — could probably be obtained. Note that a non-scattering signal to a distant observer does not make him suffer any loss in field or apparent size and detail of the scanned object, which can be recovered to any resolution, limited only by the state of the art of the physical realization technology.

The implications for far greater resolution microscopy— far heyond the present limitation to about 4,500 — should be immediately obvious. The implications of such a microscope - that can see directly inside atomic nuclei; photograph nuclei and fundamental particles directly; see living viruses, molecules, and atoms directly; and theoretically see even into the virtual state itself— should be immediately obvious.

In discovering phase conjugation, the Soviet Union was attempting to break Tesla's secret of wireless transmission of energy without losses, and the Soviet scientists did so by about 1950. They highly weaponized the effects of phase conjugation, phase conjugate mirrors, and amplified phase conjugate mirrors, both in radar waves, mechanical waves, and sound waves, for nearly two decades. Then the Soviets cautiously stimulated the open literature with a limited paper on optical phase conjugation, to ascertain whether or not we realized the severe weapon implications of time-reversed waves, their production and use, and their amplification.

So phase conjugate mirrors can do very useful things. For example, look again at figure 35a. Suppose we are trying to photograph something on the other side of the distorting medium, say through a distorting gas, such as a turbulent atmosphere. In that case E_1 on the left is, say, light coming from an object on the left and passing through that distorting medium. If we just used ordinary waves in a camera on the right, we would see a very distorted wavefront, as represented by the distorted E_1.

However, if we illuminate the object by sending a wave through the distorting medium, and detect the *phase conjugate* signal that returns, it will have reversed the distortion when it gets to us, and we will get a clear picture. A very nice photo of just this process is contained in David M. Pepper, "Applications of Optical Phase Conjugation," **Scientific American,** 254 (1), Jan. 1986, p. 75.

Phase conjugation has many more uses than we have covered in this brief paper, of course, but this is an important use: the removal of distortion effects from optical systems.

It would, however, be nice to be able to amplify the effect. And so we can.

Amplifying the Phase Conjugate Effect

Let's look now at figure 36, where we will develop how to amplify the phase conjugate replica.

Be careful to notice that we are changing subscripts on you. By convention, optical scientists use A_1 and A_2 as two additional waves, called the *pump waves,* that are used to stress the nonlinear medium, and input signal wave A_4. Wave A_3 then is the stimulated PCM output, or the phase conjugate replica (PCR) wave.

In this figure we show a scheme for amplifying the phase conjugate signal that is generated and returned by the phase conjugate mirror (PCM).

We do this by adding two opposing waves of the same frequency (in this simplified case). These are the two "pump waves", and impressing them upon the PCM is called "pumping" the PCM.

Actually, in producing the pump wave, we are adding two input waves of the same frequency, 180 degrees out of phase with each other. Since the nonlinear medium is a *modulating* medium, the waves are forced to modulate each other and "lock together" as a *single scalar* EM wave of most interesting characteristics. Indeed, its E fields sum to a zero resultant vectorially, and its B-fields sum to B zero resultant vectorially. However, the scalar parts remain and are multiplied together, as in the original Maxwell quaternion theory. Since the magnitudes of the vector components in the scalar summation (quaternion multiplication, since we are addressing modulation) are varying, then the magnitude of the remaining scalar part is varying. We have therefore produced a standing scalar wave in the nonlinear material medium, having zero vector EM gradient components. We have produced a purely scalar EM wave of pure potential — and this is an electrogravitational wave, rigorously, since it represents a time oscillation of the local energy density (local virtual particle flux density) of vacuum. This scalar EM wave passes through the electron shells and enters the nuclei, where it is phase decoupled by the extreme nonlinearity of the violent virtual particle currents of the nucleus. Its energy is then absorbed by the nucleus, raising it to an excited pseudopotential. This potential decays, returning the scalar EM stress wave into the local vacuum and area. We are now pumping the atomic nuclei of the nonlinear PCM material with our two pump waves, and we have created an oscillating local gravitational field around the PCM.

This increased nuclear G-potential, looked at in Kaluza-Klein theory, is a 5-space potential. It is ready to burst out in the 5th dimension (as electromagnetic bleedoff) at the slightest provocation. That provocation is the entrance and absorption of the input signal wave, E_4. Note that E_4 acts as an "initiator" (or a pinprick into a highly inflated balloon, if you will) on the built-up, excited 5-dimensional gravitational pseudopotential of the nuclei. The moment so initiated, the entire 5-space G-pseudopotential collapses, emitting a time-reversed phase conjugate replica (PCR) of E_4. This emitted, highly amplified PCR is labelled E_3. It now "backtracks" down the invisible trace through space taken by the incident stimulus wave E_4, returning to the distant source that originally emitted

Voila! Tesla's wireless transmission of energy to a distant point without losses. *Voila!* The Soviet Launch Phase ABM system and the Soviet Launch Phase Anti-Bomber System, when used in conjunction with an over-the-horizon radar (such as the giant Wood-

Table 28. FOUR-WAVE MIXING

- **NONLINEAR MEDIUM**
- **OPPOSING PUMP WAVES**
    - **CROSS MODULATION**
    - **SCALAR WAVE**
    - **INTO NUCLEI**
- **TRANSMISSION WAVE**
- **REFLECTION WAVE**
- **REFLECTION GAIN**



Figure 36. Phase conjugation by four-wave mixing.


IONOSPHERIC REFLECTION
AMPLIFIED PHASE CONJUGATE REPLICA
EARTH'S SURFACE
NORMAL RADAR RETURN
STRATEGIC MISSILE LAUNCH
GIANT PHASE CONJUGATE TRANSMITTER

a. Soviet Launch-phase and midcourse ABM system.


IONOSPHERIC REFLECTION
AMPLIFIED PHASE CONJUGATE REPLICA
EARTH'S SURFACE
NORMAL RADAR RETURN
STRATEGIC BOMBER TAXIING TAKING OFF
GIANT PHASE CONJUGATE TRANSMITTER

b. Soviet launch-phase and midcourse anti-bomber system.

Figure 37. Soviet launch-phase and midcourse strategic defense system.

peckers) to provide a reflection signal from a distant target. *Voila!* The true use of Soviet Stand-Off-Jammers to knock out enemy antiaircraft, air control, and anti-tactical missile radars wholesale. *Voila!* The Intermediate Phase ABM system, where a long range strategic radar is used to provide reflections from incoming targets. "Fire and fire again!" is the rule, and 100% defense is directly achievable. *Voila!* How the Soviets knocked down Gary Powers' high-flying U-2 reconnaissance aircraft. *Voila!* How SA-2 missile system radars were temporarily modified in North Vietnam to knock down several hot new F-111 aircraft. *Voila!* How the Arrow DC-8 aircraft, Titan missiles, Delta rocket, and Ariane rockets were "electromagnetically surged" from inside to destroy them. *Voila!* Why the Soviets almost never throw away old radars, since they can now add PCMs and make them formidable destroyers of incoming targets. *Voila!* How one solves the ABM problems of discrimination and weapon kill; simply pulse-fire everything — nuclear material explodes in a full nuclear explosion when struck with potential pulses of sufficient magnitude and duration.

Summarizing figure 36 and amplification of the phase conjugate replica:

When we consider the addition of the input wave and the resulting phase conjugate wave that will be produced, we shall have a total of four waves. Thus this particular process is called four-wave. *mixing.**

On the diagram in Figure 39, A_1 and A_2 by convention are taken to be the two opposing EM pump waves. Notice that these two pump waves stress the medium. Since the medium is nonlinear, it is a modulator. Hence the two pump waves modulate each other. The two waves thus lock together into a scalar EM wave. This scalar EM wave is an oscillating artificial scalar EM stress wave, and it goes directly into the atomic nuclei of the medium and pumps the nuclei themselves.

The atomic nuclei are now rhythmically stressed with the oscillating scalar wave.

---

*Probably the best single introduction to optical phase conjugation in the English language is David M. Pepper, "Nonlinear optical phase conjugation," **Optical Engineering,** 21(2),**Mar.**/ Apr. 1982, p. 156-183. Especially read Pepper's footnote on p. **166.**

We now input a weak signal (wave A_4) into the "pumped nuclei" medium.

By our CPTEGS rule, the positively- charged nuclei generate a negative energy/negative time wave — in short, a phase conjugate replica wave. Further, it is a highly amplified PCR, and may contain *as* much raw energy as was fed into the pumped mirror by our pump waves. This "seeker wave" or "electromagnetic missile" wave then sets out on its invisible path through space, seeking a distant "A_4 source point" and delivering all its energy intact to that point.

The Phase Conjugate Mirror as a Vacuum Triode

The pumped phase conjugate mirror (four wave mixing) can best be understood as a special kind of vacuum triode.

The pumped artificial potential on the atomic nucleus provides a powerful cathode in positive time, and a powerful plate as well in negative or reversed time. The electron shields, in their spin coupling to the nucleus, act as a grid in positive time. The input signal A_4 itself acts as a relatively weak signal onto the grid of the triode.

The positive charge difference in potential between the powerful pump potential of the nucleus (cathode, in forward time) acts as the plate voltage. The decrease of this potential when discharging (increase of the negative time, negative aspect) acts as the production of a plate signal to the negative time operation (production of the amplified, time-reversed PCR wave).

The excited nucleus immediately decays upon stimulus by the "grid signal" A_4, emitting a "time- and energy-reversed" strong signal — in short, amplified phase conjugate replica wave E_3.

The amplified phase conjugate signal moves from the cathode (nucleus) out to the electron shells and beyond, precisely because it is time-reversed. To a time-reversed signal, the grid (normal input) acts as the final plate (external output) — that is, in negative time, the elements of the triode are reversed. This makes it possible for the material to emit the powerful PCR.

I have called this effect/analogy a vacuum triode, to accent the direct engineering possibilities. My associates have already engineered this effect to obtain enormous amplification of energy ("free energy") and practical antigravity, from solid-state devices, directly



a. Typical nonlinear power reflection coefficients.



b. Intensities for the oscillation condition.

Figure 38. Power reflection coefficients and oscillation.

on the laboratory bench.

The actual "amplitude gain" of the vacuum triode is the ratio of the amplitude of A_3 to the amplitude of A_4. The square of the amplitude gain is proportional to the power gain; this entity is called the nonlinear power reflection coefficient.

Figure (38a) shows the typical nonlinear power reflection coefficient for a pumped phase conjugate mirror, as a function of the input energy and the depth of the material. As the input signal increases, the gain increases. The ultimate condition would be that the "free oscillation" condition is approached. This occurs when the angle between the input wave A_4 and the pump waves A_1 and A_2 is 90 degrees.

Figure (38b.) shows the oscillation condition and the fraction of the total pump power that is in the input wave A_4 and its output **phase** conjugate replica A_3.

At the oscillation condition, an "infinite" gain exists at the correct depth in the medium. This means that essentially all the energy being fed into the pump waves A_1 and A_2 will now be emitted **in** the output wave A_3. At that point, "saturation cutoff" of the triode output occurs, and it cannot output higher energy, since it has no more.

Notice that, at the oscillation condition, for the slightest output, the full power of the pump waves is fed into the phase conjugate replica. This powerful wave then retraces the path taken by the o**riginal** input signal, unless something else is done to divert it.*

The interesting question then arises: Since we can have infinite **gain,** can we get a special oscillation condition so that the pump wave furnishes its own energy? In other words, can the pump wave "resonate" with the vacuum flux in such a fashion that it is self-pumping and self-perpetuating?

In at least three materials, the answer is yes. Such effects have **been** experimentally accomplished in special forms of barium tita**nate.** See, for example, J. O. White et al, "Coherent oscillation by self-induced gratings in the photorefractive crystal $BaTiO_3$," **Appl. Phys. Lett.,** vol. 40, 1982. p. 450.

*Recall that the PCR can be steered by introducing a minute wave A_5 to vectorially sum with input A_4, In that case, the effective input is the vector resultant of $(A_4 + A_5)$. The apparent distant source point and invisible vacuum path are shifted correspondingly.

Phase conjugation is a universal phenomenon. Theoretically it applies to any sort of wave: electromagnetic, scalar, sound, mechanical, etc. By using it, incredible new effects and an entirely new physics can be accomplished. It is a new and exciting field, little-known outside specialist circles, and still not well-understood. Most discoveries in the field are yet to be made.*

Newton's Third Law and the Full Law of Entropy

For example, the present author noticed that Newton's third law— for every action there is an opposite and equal reaction — is actually a result of phase conjugation. To explain that, we diverge a bit.

First, phase conjugation is also involved in the fact that a charged particle of mass is a little "dynamo" or engine.

Actually, a particle of mass is itself a "nonlinearity" in vacuum spacetime. When a photon (virtual or observable) strikes a particle of mass and is absorbed by it, it's the same as "interacting with a nonlinear medium."

In terms of virtual photons, the charged particle is continually bombarded with them, from the vacuum flux. The charged particle, being a "nonlinear medium", phase conjugates each input virtual photon, emitting a phase conjugate replica.

If it absorbs a normal virtual photon, it emits a "negative energy, negative time" phase conjugate replica.

If it absorbs a normal virtual photon, it emits a "negative energy, positive time" phase conjugate replica — just a normal virtual photon. Note that the particle of mass thus does not exist in time. Or, it exists equally in positive and negative time. Since we only observe particles, it follows that time is not normally an observable, as quantum mechanics has assumed.

The emission of a phase conjugate replica does not affect the momentum of the emitting PCM, as is well-known.

For an observable photon, the particle (nonlinear medium) absorbs the normal photon, which does not affect the energy and momentum of the PCM particle of mass.

If there is no other mass to accept the PCR, it just moves off.

---

*The U.S. may finally be waking up. SDI is now starting to study EM missiles "in the time domain" as opposed to frequency. See **Av. Wk. & Spurn Tech., Feb. 29, 1988, p. 56.**

If there is another mass to accept the PCR, the PCR is absorbed and phase conjugated by it.

A charged particle in vacuum is continually bombarded by a flux of essentially "randomized" fluctuations. However, on the average these all "average out" to zero. Any particle is automatically in a very high vacuum potential, and is in a state of great agitation at all times, even if it's "at rest" with respect to ordinary observers. It's really "smeared all over the place," so to speak.

When we expose a charged particle to a *normal* potential, the interior virtual particle flux of that potential is disorganized. Hence the particle just "wiggles a bit more frantically," so to speak, randomly in every direction.

However, when we expose a charged particle to an *artificial* potential made by zero summed/multiplied EM force fields or waves, the particle wiggles more frantically in *organized directions.**

This is just as true for virtual particles as it is for observable particles.

Thus the use of such artificial potentials in scalar electromagnetics enables us to overcome the disorder of the internal structure of normal electromagnetics. By this means, we can structure the vacuum, organize electricity and electromagnetic waves, accomplish negentropy, curve local spacetime in complex, deterministic fashions , produce free energy and antigravity, reorganize and transmute nuclei (transmute elements) with miniscule input energy, etc.

Rigorously, this means that the present law of entropy is only half of the full law of entropy. Specifically, it is the "positive time, positive energy" half of the law, and it states that in closed real physical systems, continuing operations of ordered "positive time, positive energy" effects tend to inevitable "disordered" effects produced in the apparatus or system.

In other words, the present law of entropy really states that no ordered system is totally closed. The system will inevitably have energy and actions that escape the system's order, and hence (to the system) this escape represents "loss of order" — or in short, disorder.

The present law of entropy specifically excludes (by implication)

---

* I.e., **the** electronic noise is partially organized. This is a major key toward building scalar EM detectors. It is also a primary cause of many solid-state circuit malfunctions. The exact principle: (Random changes) + (artificial potential) equals (chaos).



© 1978 Hal Crawford

Figure 39. Photons have virtual substructures. These may be statistical or deterministic.

negative time aspects, where external (disordered) energy time-reverses to again enter the ordered system, in perfect order. By implication, it also excludes negative energy production and operations.

However, **experimentally we can produce both negative energy and negative time, in deliberately time-reversed operations such as phase conjugation and with devices thnt serve as phase conjugate mirrors. Further, we can amplify the phase conjugation and disorder-to-order operations.**

Hence the present law of entropy is incomplete, and states only half the true possibilities. The other half of the law is the **law of negentropy.** In this law, disordered operations outside the **ordered** system undergo time-reversed (and possibly amplified) effects. These reordered energy effects — which may be highly amplified in comparison to the disordered escaped energy—reenter the "ordered system", restoring order. Since this process moves in negative time, it goes from disorder to order. Hence it is negentropic.

Therefore we have solved the old thermodynamic problem of the "eventual decay of the universe into disorder." Not to worry; the other half of the full law of entropy prescribes negentropic operations in negative time/negative energy, and these restore the order of the universe. That takes care of the problem.

It also means that, in highly disordered systems of many degrees of freedom and far from thermodynamic equilibrium (that is, when the disorder law is saturated), then one can expect to see further stress "create" negative time and hence create order emerging and stabilizing from disorder.

And of course that is exactly what is seen. Ilya Prigogine was awarded the Nobel Prize in 1977 for writing a new thermodynamics predicting precisely such effects, and experiments have proved his case.

But to return to Newton's third law:

Newton abstracted his third law from the classical interaction between two colliding balls.

If one ball is at rest and another approaches it at some velocity, the approaching ball carries momentum and kinetic energy. As it "collides" with the resting mass, quantum mechanics tells us what actually happens: Particles of mass in the moving ball are producing virtual photons continually, and these virtual photons strike the particles of mass of the resting ball and are absorbed by it.

The resting mass now acquires extra energy and momentum from the absorbed photons. At the same time, it acts as a nonlinear medium. It produces phase conjugate replica virtual photons, and these time-reversed virtual photons are emitted. These photons produce no change in momentum or energy upon the emitting mass. However, being phase conjugates, they precisely follow back along the paths taken by the first or "stimulus" virtual photons, striking the moving ball. They are absorbed by that ball, producing (to the external observer) negative momentum and negative energy in it.

These subtract from the kinetic momentum and kinetic energy of the moving ball, reducing them.

The virtual photons emitted by the approaching ball perform positive work upon the target ball.

The virtual, phase conjugated photons, emitted in return by the mass of the struck ball as a PCM, reverse to strike the approaching ball to do negative work upon it.

Notice that twice as much absolute work is always done on the system of two balls as we "input" with the approaching ball.

Also notice that, if we directly "engineer" the phase conjugation of the struck system, we can directly tamper with, and drastically change, the production of the negative energy and negative momentum in the moving ball. Hence we can drastically alter Newton's third law. We can now make a Maxwell's Demon.

This alone clearly establishes that it is perfectly possible to build a so-called free energy device. Though subtle mechanisms must be used, it's nothing more spectacular than putting a paddle wheel in a river, and extracting shaft power from the wheel, furnished by the river's current. Phase conjugation yields other exciting possibilities


VIRTUAL PARTICLES
VIRTUAL RIVER
VIRTUAL RIVER
VIRTUAL RIVER
OBSERVABLE PARTICLES NOT RELEASED
VACUUM SPACETIME
MUST INITIALLY PAY TO CONCENTRATE THE SPRAY PUMPS. THE SPRAY ITSELF IS FREE AND CONTINUALLY PROVIDED BY THE UNIVERSE.

Figure 40. Once established, a virtual river is for free.


OBSERVABLE POWER
ø
VIRTUAL POWER
GENERATOR
VACUUM SPACETIME
(Locally Curved)

Figure 41. Local energy conservation can be violated.



Figure 42. T.H. Moray adjusts the controls of his radiant energy device. Salt Lake City, Utah, in Feb. 1937. Moray obtained 50 kilowatts of power from a 55-lb. device, straight from the ether. Its characteristics (cool circuits, brilliantly lit lamps) reveal that It was negative energy.

too numerous to explore here. For just one example, by phase conjugation, real-time holography can be accomplished without having to separately make and illuminate the holograms.

Now with holography and multiple projectors — and particularly with two intersecting "normal" beams to backtrack upon with ever-converging PCR signals—you can assemble a "form of energy" at an appreciable distance from the projectors in three dimensional space. With phase conjugation, you can do it in real time. And you can do it at a great distance back along the path of any signal you use as an input.

By using PCM holography, degradation with distance is not appreciably experienced. After all, the PCR waves utilized are ever-converging. The energy does not diverge and spread. Therefore, if you can make a 6" diameter ball of intense EM energy at a short distance in the laboratory, you can make that same 6" diameter ball of intense energy at several thousand kilometers distance, using PCR real-time interference holography.

With highly amplified PCM's, you can put far more energy into the distant interference form than you can with normal holography. Conceivably it is possible to assemble so much energy in the holography "object" that it condenses into a real material object! In other words, it materializes or semi-materializes.

Both the "intense light form" usage and semi-materialization of forms (such as light forms, flying geometrical forms, etc.) have been created worldwide by the Soviets for decades, to stimulate UFO reports and provide a deception plan for their development and testing of large, strategic energetics weapons using highly amplified PCMs and PCR holography.*

Other bizarre considerations also arise. For example, in **radionics** one utilizes a "witness"—such as a photograph—of the object one is attempting to send "energy" to. (For example, this might bo a sickly plant one is attempting to spruce up). Now when the plant was photographed, the light from it struck the photoemulsion of tho film, producing a photochemical reaction. It also produced phase conjugation in the atomic nuclei of the film emulsion, since the emulsion acts in some respects as a nonlinear medium.

---

*For an example of highly reliable detection and observation of "Soviet hololography UFOs," see Leif Havik, "Project Hessdalen," MUFON UFO Journal, Jan. 1988, p. 4-7. The present author certainly does not imply that all UFO phenomena are due to Soviet PCR holography, only that some UFO phenomena are.

There exists a continuous, invisible "stimulus photon and its connections" trace in time and space, between the plant when the photo was taken and that photo now, even if one or both of them have moved. That trace is highly persistent (as Australian experimenters Reid and Barsamian have shown). A phase conjugate (time-reversed) signal can be made to retrace that track and travel all the way back to the plant, in the present. The effect of using the photo (or sample of the object) as such a "witness" of the real plant and directing weak PCR energy back along the invisible trace into the object is called radionics. In most cases, the two cerebral hemispheres of the operator's brain are depended on to form the necessary scalar "pump wave" to pump the "witness" and produce phase conjugated signal energy, time-reversed to travel back into the distant object.*

The problem with present radionics is that it is far too weak, and it is "operator dependent", changing with the mood, temperament, and skill of the operator. It does objectively work, however, though Often erratically. In countries such as England, France, and Germany, use of radionics to treat human disease is legal and permitted, though operators (for example, in England) must undergo extensive training and certification. Its results are roughly comparable to the results of normal medical doctors. Radionics does not replace orthodox medicine. It can successfully treat certain things that orthodox doctors have little or no success with (such as lupus), and orthodox medicine can successfully treat many things that radionics has little success with (a broken leg or ruptured appendix, for example). The two treatments are best used in conjunction with each other.

However, we must point out that a new, amplified PCM radionics is likely to emerge in the near future. Such a new approach will offer highly effective, powerful treatment of diseases, even at a distance, by amplified PCR electromagnetics. Again, the radiation in and from a photo or witness of a diseased patient can be used as a "grid signal" into a powerful, pumped phase conjugate mirror. The

---

•Again recall that we observe time-reversal of waves as **spatial path** reversal, not as time **travel.**

PCM will produce a specific, powerful, amplified signal that will travel directly to the patient, be absorbed in his entire system, including the atomic nuclei comprising his cells, and directly reverse the chemistry, toxins, and cellular damage in the patient from that disease. It will also kill or destroy the harmful viruses, bacteria, etc. causing the disease, and it can even reverse the actual genetic changes in the cell caused by disease-inducing viruses.

Of course, any powerful tool is two-edged. It can be used for harm as well as good. I think the reader can appreciate the damage that can be done to systems and persons at a distance by means of such powerful new amplified PCM radionics devices.

You can also see the security problems posed to large computing facilities in banks, federal facilities, state and municipal facilities, the IRS, U.S. military weapon systems, ships, aircraft, etc.

Obviously such devices are going to have to be highly regulated and controlled. Else criminal operators will be killing people and destroying things wholesale, secretly and at a distance, and they will have perfect legal alibis to allow them to escape prosecution.

To summarize: if a photograph or witness pattern of an object or person can be correctly stimulated by phase conjugate electromagnetics so that the emulsion acts again as a PCM, can one not argue that—theoretically — phase conjugate energy from the photograph and the instrument can be sent back along all paths, all the way back to the original object? After all, this has been rigorously demonstrated by University of Sydney researchers. Is there not an actual physical mechanism for radionics? For highly amplified, powerful radionics where the operator himself is removed from the circuit? Just because it changes our present notion of physical reality, must we dogmatically reject the results being shown on the laboratory benches, some of which are in the hard-core scientific literature?

Phase conjugation and time-reversed engineering have a diversity of applications unparalleled in the history of science. They literally present us with a new physics. New rules apply.

Most of the major discoveries in phase conjugation have yet to be made.

Scalar Electromagnetics

The scalar electromagnetic approach modifies classical electromagnetics (EM) to include gravitational waves and effects.

To do this, scalar EM utilizes summed-zero vector forces and force fields to construct polarized vacuum potentials.

Although externally it has zero E and B vector gradients, an "artificial" potential possesses an internal, dynamic E and B vector field structure. This "infolded" (Bohm's term) structure has finite size and is deterministic. The infolded structure of the artificial potential in turn deterministically structures and polarizes the vacuum and curves spacetime locally, contrary to presently assumed limitations of general relativity.

Since in free vacuum a potential normally extends to infinity in a decaying exponential fashion, then this infolded E and B vector structure of an artificial potential extends to infinity in a decaying exponential fashion.

The artificial potential itself may be rhythmically varied either in structure, magnitude, frequency, or all of the above. This produces waves of potential, and waves of the structure of vacuum/ spacetime — again, in the free vacuum case, reaching to infinity in a "decaying exponential" fashion. These "scalar EM waves" are gravitational waves.

Each photon (one major wave length of the "carrier", complete with modulations) of the scalar EM wave also has structure (its included modulations).

Modulated waves have compound or "giant" photons — photons containing infolded photons.

Each compound photon of such a scalar EM wave is a vacuum engine. It deliberately structures and patterns — dynamically — the energy density and charge of vacuum.

(1) By canonically varying two or more components of the electromagnetic vector structure of the zero-summed EM force vector system, the local structure of vacuum spacetime is macroscopically varied in its internal composition. This is the compound variation of "curvature within curvature" — and hence hyperdimensional.

Table 29. A ZERO VECTOR SYSTEM:

- **IS AN ACCUMULATOR**
- **DOES "INTERNAL" WORK ON MEDIUM**
- **HAS NO "ENERGY" EXCEPT STRESS OF VACUUM, YET**
- **CAN YIELD THE ENERGY OF ITS COMPONENTS WHEN DISSIPATED**
- **IS A SPECIAL SORT OF "PUMP"**
- **CAN YIELD CONTINUOUS ANENERGY FLOW IF NOT DISSIPATED**

(2) By prohibiting internal canonical variance while coherently varying the amplitudes of all the EM components, the total stress of vacuum/spacetime — and hence its overall curvature — is locally varied, without modifying its structural form. This is simple variation of overall curvature of local spacetime, involving primarily relativistic effects.

Rigorously, each of these two methods produces a localized gravitational wave, where the local stress of vacuum is deliberately patterned as well as oscillated in amplitude.

Both methods may be applied simultaneously (and multiple infolded times) to produce an even more sophisticated gravitational wave, and more sophisticated structuring of the local stress energy density of vacuum.

The resulting unified electromagnetics/gravitation is called **scalar electromagnetics,** since the electrogravitational effects are obtained by deliberately opposing EM vector force fields so that they vectorially sum or multiply to a zero vector EM resultant, while **the** infolded (Bohm's term) EM vector components structure and vary the stress energy density of vacuum.*

---

*Gravitational potential is just "in-folded and locked in" dynamic electromagnetic forces. The infolded EM energy is locked-in, representing a change in the local energy density of vacuum and hence a curvature in spacetime. Electromagnetic force fields are just the out-folding of the G-potential's inner EM contents into the 5th dimension. Ordinary gravitational force field is just the "trickle leakage" of the G-potential's infolded contents, out into and through *3*-space.

Note immediately that scalar EM also deals with internally structured and patterned electricity and electromagnetism.

"Normal" electromagnetics has no deterministic internal structure.

The new electrogravitational (EG) wave is called a scalar EM wave, and is believed to have been originally discovered by Nikola Tesla.

James Clerk Maxwell was aware of the potential for electromagnetics to stress and structure the vacuum ether.

His original electromagnetic theory — written in quaternions, not vectors (which had not yet been completed by Oliver Heaviside) - can allow for these effects to be expressed.

Unfortunately Heaviside's interpretation of Maxwell's work

Table 30. STRESS IS FUNDAMENTAL

- **THE MOST FUNDAMENTAL REALITY IS STRESS**
- **THE COMPONENTS COMPRISING STRESS ARE THE GREAT CAUSATIVE AGENTS**
- **MOST OF THESE ACTIVE AGENTS ARE HIDDEN INSIDE ZERO-VECTOR SYSTEMS**
- **THE COMPONENTS OF STRESS MAY BE STATISTICAL OR DETERMINISTIC**



figure 43. Charge affects anything existing in spacetime.

eliminated these effects, and they have remained eliminated from the Western EM theory to the present day.

The use of the scalar EM wave directly engineers the virtual state and the vacuum itself.

Hooper's work represented important work in this respect, as does other related experimental work by Bedini, Watson, Golden, Dea, Faretto, Beck, and other inventor colleagues who do not wish their names mentioned.

Scalar EM theory also bears a strong relationship to the Kaluza-Klein unified theory of gravitation and electromagnetics. At least five dimensions — four spatial and one time — are required as a minimum.

Nested levels of virtual state may be modeled as identical to successive hyperspaces.

Internested levels of zero-summed vector EM force fields allow the direct engineering of those hyperspaces.

Negative energy and negative time flow are especially important when building free energy devices and antigravity. The mechanism producing negative energy and negative time flow is the forced amplified production and absorption of phase conjugated waves.

In addition, phase conjugation is a basic phenomenon of nature: for example, as previously pointed out, it is the direct mechanism that generates Newton's third law of motion. It also adds a negentropy law (for negative energy/negative time).

Accordingly, if we engineer phase conjugation, we can change Newton's third law to our will. And we can invoke the negentropy half of the total law of entropy, so that we can go from disorder back to order. Again, we can make a Maxwell's Demon at will!

In Newton's third law, when manipulated locally, the reaction force need not necessarily be equal in magnitude to the action force It also need not necessarily be parallel to it. It can even be phase conjugated itself to yield an addition force, assisting the propelling of a particular engine or device.

Phase conjugation may also be manipulated so as to cause like magnetic poles to attract, and unlike poles to repel.

Magnetic "force field lines" of a bar magnet normally exist in conjugate co-existing pairs. One of the pair is in observer positive time, and (by convention) runs from the north pole to the south pole. The second line of the pair is a phase conjugate of the first, and exists in negative observer time. Thus, to the "positive time only" observer, it will appear to run from the south pole to the north pole, perfectly retracing the path of its twin.

Howard Johnson uses a "two particle" theory of magnetic field, for example, where one particle (photon) is the phase conjugate of the other. This is identically the same as the scalar electromagnetics concept of phase conjugate pairs of field lines. By very complex, specialized, compound permanent magnets, Johnson is able to partially separate the two lines, and spatially concentrate or diminish the phase conjugation (negative time) component in a given area of operation.

If the negative time component lines are concentrated to outweigh the positive component lines in a local region, then the laws of magnetics are reversed in that region. There like poles attract and unlike poles repel.

In his rotary permanent magnet motor design, he concentrates the negative time component in that part of the rotation where a north rotor pole is approaching a north stator pole. Normally, in this part of the cycle, one has to overcome the repulsion of like poles to "force energy" into the device for later extraction.

However, *now* in that region *like poles attract.* There the north pole of the rotor is attracted toward the north pole of the stator, adding impetus to the rotor.

As the rotating north pole passes the stator north pole, it leaves the region of negative time concentration and returns to a normal "positive time" region again. Now the north poles repel again, and impetus is again added to the rotor.

In that manner Johnson is able to violate local conservation energy, and make a "free energy" permanent magnet motor. The motor will rotate itself and deliver constant shaft power to a mechanical load. By attaching a standard electrical generator, normal electrical power is continually and freely produced by the complete motor generator power system.

Johnson's complex nonlinear magnets severely curve local spacetime, allowing *local* violation of energy conservation.

Scalar EM View of the Vacuum

In the modern quantum mechanical view, the vacuum is not an emptiness, but instead is a plenum.

Today the vacuum is considered to be filled with incredible virtual particle activity. From nowhere, virtual particles continually arise — even with fierce energy — then disappear again into nowhere, so rapidly that they cannot be individually observed.

However, these virtual particles are quite real, for they cause all the forces of nature when they interact in the aggregate with observable particles.

To the observer, the fleeting particles also appear and disappear in both positive time and negative time. That is, the flux consists of both particles and antiparticles.

Thus the vacuum is a seething inferno of virtual particle fluxes.

The concept of an **ether** is again accepted. It refers to this "virtual flux" vacuum.

Note, however, that this is an ether far different from the old material ether that was theorized prior to relativity.

In the new vacuum ether, every imaginable type of particle continually and spontaneously arises (creation) and disappears (annihilation) at every point in the vacuum, according to modern quantum mechanics.

The rate of this seething virtual particle creation and annihilation is essentially unlimited. Hence the "flux density" of vacuum is essentially unlimited.

Further, any virtual particle created has a flux of even finer virtual particles associated, and so on without limit.

The vacuum's virtual particle flux is thus comprised of nested levels of ever finer virtual particle fluxes, in the modern view. We state without proof that **each deeper virtual level may be modeled as a higher dimension** (hyperdimension). **This yields an infinite-dimensional vacuum spacetime (hyperspace) that is identically the infinite nested levels of virtual state.**

At the same time, every nucleus in the universe is continually absorbing and emitting scalar EM (electrogravitational) waves. The emitted scalar EM waves of pure potential are waves in the stress and structuring of the vacuum itself.

VACUUM IS IDENTICAL TO:

- VIRTUAL PARTICLE FLUX
- SPACETIME
- ANENERGY
- $Ø_o$
- MASSLESS CHARGE

VACUUM IS:

- MADE OF UNQUANTIZED ACTION
- WITHOUT DEFINITE LENGTH INTERVALS
- WITHOUT DEFINITE TIME INTERVALS
- N-DIMENSIONAL (UNFIXED)

Figure 44. Vacuum/spacetime is pure virtual particle flux.

Table 31. VACUUM IS:

- SPACETIME (L^nT, WHERE $n >= 3$)
- CHARGE (MASSLESS)
- ELECTROSTATIC SCALAR POTENTIAL
  ($Ø_o \neq 0$)
  (ERROR IN PRESENT THEORY)
- BROKEN BITS OF ENERGY (SUBQUANTAL)
- PURE VIRTUAL PARTICLE FLUX
- Ø -WAVE FLUX
- MULTILEVEL, STRUCTURED, PATTERNED
- A VIRTUAL PLENUM
- AN OBSERVABLE EMPTINESS


VIRTUAL PARTICLE FLUX
CHARGED PARTICLE ATTACHED TO FLUX BY ITS SPIN

Figure 45. A simplified charged particle.


SPRAY ON AND OFF
POINT IN 4-SPACE
Ø IS INTENSITY OF FLUX OR SPRAY
SPINNING CHARGED PARTICLE
Ø-FLUX

SPRAY IS THROUGH 4 OR MORE DIMENSIONS, NOT JUST 3

Figure 46. A charged particle is a special kind of "spray nozzle."



Figure 47. An observable charged particle is directly connected to virtual particle **vacuum** flux.

Table 32. SPIN COUPLES VACUUM TO PARTICLE

- **SPHERICAL ROTATION IS THE KEY**
- **A PARTICLE CAN BE MODELLED AS A SPHERICALLY ROTATING VORTEX OF SPACETIME**
- **ITS MASS IS DUE TO ITS SPIN**
- **THE SPINNING OBJECT IS CONTINUALLY CONNECTED TO ITS ENVIRONMENT**
- **VERY HIGH VALUES OF ELECTROSTATIC POTENTIAL CAN INDUCE RELATIVISTIC CONDITIONS**
    - **CHANGE RATE OF FLOW OF TIME**
    - **EVEN THOUGH VELOCITY IS NONRELATIVISTIC**

E.P. BATTEY-PRATT AND T.J. RACEY,
"GEOMETRIC MODEL FOR FUNDAMENTAL PARTICLES,"
INTL. J. OFPHYS.19. NO. 6, 437-475, 1980


∇ø>0 IMPLIES A MOVING RIVER, AND THE CHARGED PARTICLE IS "HOOKED TO" THE RIVER
∇ø RIVER
ø1
ø2

Figure 48. In a flux gradient (virtual particle river), a charged particle moves itself.


POTENTIAL
DIRECTIONS OF PARTICLES ARE RANDOM
VACUUM SPACETIME

Figure 49. A natural potential is a **disorganized change** in **the stress of** vacuum. It has a random virtual substructure.


POTENTIAL
Ø
DIRECTIONS OF PARTICLES ARE PARTIALLY ORDERED (POLARIZED)
VACUUM SPACETIME

Figure 50. An artificial potential is an organized change in the stress of vacuum. It has a deterministic virtual substructure.


SPACETIME CURVATURE
PHOTONS
CHARGED PARTICLES
UNCHARGED PARTICLES
NEUTRINOS
ETC.
VACUUM SPACETIME

Figure 51. Gravitational potential is a conglomerate of stresses, organized or disorganized.



Figure 52. EM force fields are releases of gravitational potential via observable charged mass flows.

Table 33. RESIDUE UNIVERSE, RESIDUE SCIENCE

- **VECTORIALLY, STRESS IS SUM-ZEROED**
- **THE VECTOR FORCE FIELDS REPRESENT NON-ZERO GRADIENTS IN MORE FUNDAMENTAL STRESS**
- **FORCE FIELDS ARE THE RESIDUE LEFT OVER FROM THE SUM-ZEROED STRESSES**
- **PHOTON INTERACTIONS ARE FORCE-FIELD INTERACTIONS**
- **PHOTON-DETECTED REALITY IS ONLY "FIRST ORDER." IT SHOWS ONLY "RESIDUE-LEVEL" REALITY**
- **WE HAVE BUILT A "RESIDUE SCIENCE" AND A "RESIDUE PHILOSOPHY" BASED ON FORCE FIELDS AND PHOTON DETECTION**

Hence at every point in the vacuum, an intense flux of these scalar EM waves, with concomitant interferences, exists — in both positive and negative observer time.

This scalar EM flux causally **drives (constitutes) all the** enormous **quivering of the vacuum** spacetime medium **itself. In other words,** it **drives subquantum (virtual) change, which in turn drives quantum change.**

This is a drastic reorientation of quantum mechanics. In scalar EM, we view that the virtual flux of vacuum is *causally driven or created* by interacting scalar EM waves. This replaces the present **view** that the virtual flux is entirely chance. It opens up the direct engineering and structuring of the vacuum — and hence the atomic nucleus — by scalar EM means.

However, it does not replace the normal *statistical nature* of the **basic** changes of the background vacuum medium. We normally **have** little or no knowledge of the myriad of drivers that cause the basic background waves of that medium. We may, however, deliberately create special vacuum potential waves which are deterministic, and which we have knowledge of.

To the observer, from a purely statistical viewpoint, in this violent vacuum flux *any* and *every* finite pattern of virtual particles is also continually being momentarily created and destroyed — and at every level and in every hyperdimension.

Thus, in the vacuum there continually exists — at any and every point, and in any and every region — the ghostly image of anything and everything, whether in the past, present, or future; and whether **potential,** probabilistic, or actual. Even everything that could have been in the past but wasn't, or might be in the present but isn't, or could be in the future but won't be, is continually present in thin, ghostly form.

Rigorously, the universal vacuum may be taken to be a sort of giant hologram, for the whole is in each part, albeit in ghost-like manner. Everything that is, or was, or shall be; and everything that could be but isn't, wasn't, or shan't be; already exists *at once, any*where and everywhere, in this ghostly, holographic, virtual state.

We point out in passing that, conceivably, one can engineer any **part** of this "potential for reality." That is, one can directly engineer physical reality itself, in the scalar EM view.

All that must be done is to amplify (continuously and coherently


In the shaded region the object is in the virtual state with respect to the S-frame. It is also rotated further than the first hyperframe; $\alpha > \pi/2$.
Time
A critical angle (α_c) exists where contraction reaches the quantum threshold in length. Note $\alpha_c < \pi/2$ and the object becomes photonic.
moving object is rotated in hyper-space at angle α
For modeling, we consider that rotation "jumps" to $\pi/2$ just immediately past the quantum threshold.
α_c
α
S-frame
ΔL"
ΔL'
ΔL
Lorentz-Fitzgerald Contraction

Figure 53. As beyond (without), so within. Hyperspaces are internested virtual states, and rotated orthogonal frames. They are also substructures within and of vacuum state potentials.


L^3
MASS
L^2
PHOTON
L^1
BARE NEUTRINO
L^0
THOUGHT

Figure 54. Internested levels of virtual state vacuum interact with neutrino, photon, and mass. "Thought" or "mental state" refers to the third and more levels down in virtual state.



Figure 55. Virtual state patterns are absorbed and emitted by the atomic nucleus. The built-up nuclear "charge" in that particular pattern is a partial potential — for that pattern only.



Figure 56. Nuclei of the universe continually exchange scalar EM waves and virtual **panicle** fluxes.


"NORMAL" EM WAVES
ELECTRON'S EXCITED STATE
ELECTRON'S GROUND STATE
NUCLEUS
PHOTON ABSORPTION
PHOTON EMISSION

- **HEAVY NUCLEUS RELATIVELY UNAFFECTED**
- **MACROSCOPICALLY. MASS APPEARS STABLE AND "BRICK-LIKE"**
- **SPECIAL RELATIVITY APPLIES**

Figure 57. First order reality. Rough-hewn by observable photon interaction with electron shells of the atoms of physical mass. This process is "physical observation."


SCALAR PHOTON ABSORPTION
SCALAR PHOTON EMISSION

- **HEAVY NUCLEUS AFFECTED**
- **MACROSCOPICALLY. MASS APPEARS FLUID AND CHANGEABLE**
- **GENERAL RELATIVITY AND KALUZA-KLEIN GEOMETRY APPLY**

Figure 58. Higher order (hyperspatial) reality. It exists as stored in the potentials ot the atomic nuclei of physical mass.

add energy to) one of these "ghost images" virtual state forms. In that case, the form becomes "denser and denser," until eventually it starts to breach the quantum threshold. At that time, the form will be seen emerging as a sort of "coalescing form of light," where the light seems to be forming in little "chunks" or pieces. As the coalescing operation continues, the light-form will eventually become fully formed. If it continues, it will start to coalesce further into *thin, ghostly material* form, appearing much like a faint fog-form. With continued coalescing, it will become a very solid, material form which exerts pressure on tree limbs, breaks them, leaves traces, etc.

Long ago I dubbed this process *kindling.* It is rather widely met in paranormal phenomena of many types.

But back to the basic idea of ghostly images in the virtual states of vacuum.

In this view, Everett's many-worlds interpretion (MWI) of quantum mechanics is literal and real, albeit the additional worlds are to bo taken as virtual and hyperdimensional to the laboratory observer.

(It is rather simple to show that ever deeper, nested levels of the virtual state are exactly the same thing as ever higher dimensions. By "rotating" an object in many-dimensional space, one can show that, after three rotations, a physical object has lost all physical intersections with our normal 3-space, to us now only occupying time. Since this is the precise characteristic of a *thought form,* I used this phenomenon and spatiotemporal model to make a multidimensional space model directly including thought, mind and matter. That is, one is thus able to form a unified field theory of mind, th**ought,** life, and matter — a model that is testable, makes predictions, and actually unites physics and metaphysics. That work and its plications, however, are largely beyond the scope of this book.)

It is stressed that the basic scalar EM image (interpretation) of reality is directly implied by quantum mechanics. It is not idle metaphysics. Other than the scalar EM wave causality for the observer's statistical microscopic dynamics (and the extended model unifying mind, thought, life, and matter), it is not the construct of this author. Instead, it follows from interpretation of the equations and axioms of quantum mechanics (QM) itself, as changed and extended by the "zero vector system" dynamics.

Charge, Potential, and Curvature of the Vacuum/Spacetime

The flux of one type of virtual particle through a point in the vacuum may be examined.

A single type of virtual particle flux (VPF) at a point constitutes one particular type of charge at that point. For example, the flux of virtual photons constitutes the electrical charge.

Further, the magnitude of the selected flux (usually expressed as a flux density) through the point may be taken as the magnitude of the vacuum's charge there in that type of particle. In other words, at a point the magnitude of the vacuum's charge (VPF) is one type of *potential* at that point.

Various kinds of fluxes constitute various kinds of charge, and comprise various kinds of potentials. Immediately we see that one type of charge may always be decomposed into other kinds of charge, as can potentials. This point is beyond the scope of this book and will not be further amplified.

Continuing our example, the magnitude of the electrostatic scalar potential at a point in vacuum represents the magnitude of the flux of virtual photons through the point, and hence the electrical charge at the point.

Table 34. REALITY IS A HOLOGRAM

TO ESTABLISH THIS:

1. **ALL DETECTION IS INTERNAL**
   PHYSICAL REALITY CONSISTS OF THE INTERNAL DETECTIONS OF THE PERCEIVER/OBSERVER.

2. **THE OBSERVER MAY BE AT ANY POINT IN THE UNIVERSE**
   THE UNIVERSE CAN BE DETECTED FROM ANY POINT INSIDE ITSELF.

3. **THE PHYSICAL UNIVERSE IS TOTALLY INSIDE EACH POINT IN ITSELF**
   THIS DEFINES A HOLOGRAM: THE WHOLE IS IN EACH PART.

Twin Flows of Time

In quantum mechanics, each virtual photon is continually turning into an electron/position pair, and vice versa.

By Dirac theory, *a positron is an electron traveling backwards in time.*

Further, pair production produces time-smeared particles — an electron and a positron.

Pair production, then, actually produces two *electrons,* one coupled to (smeared in) a positive piece of time and one coupled to (smeared in) a negative piece of time.

Thus in the vacuum two discretized streams of time, one positive and one negative, are continually created in conjunction with pair production, and destroyed by pair annihilation.

Further, integration of tiny virtual pieces of time (from virtual photons) to form "passage of time" macroscopically is directly associated with the charge (the absorption and emission of virtual particles) of an observable particle.

This is what is meant by an object "existing" (persisting). Its continual virtual photon interactions are integrated by its mass (timeless part) to continually create its energy states and its march through time.

The absorption and emission of an observable photon, however, moves the mass (timeless part) in (comparatively) larger jumps through time. The absorption of the photon connects a positive piece of time to the mass of the particle, converting it to masstime. The subsequent emission of an observable photon "tears off the little time-tail," so-to-speak, and leaves behind a totally spatial mass entity, having no large connection to "the flow of time."

This is what is really meant by "observation."

Because the "observation" disconnects time from the previously "excited mass" (masstime), then it follows that time is not an observable.

It also follows that the twin streams of time are not continuous. Each is broken into incredibly tiny bits.

The bits of time are continually interlaced between negative and positive, and neither of the two streams of time bits is integrated in the vacuum. The vacuum is disintegrated!

A photon — the basic quantum — is composed of discretized energy and time, bound together (integrated) as action (angular momentum). That is, a photon is a little piece of energy, welded to a little piece of time, with no seam in the middle.

Two kinds of photons exist: the normal photon exists as (+dE) (+dt). The phase conjugate photon exists as (-dE) (-dt).


VIRTUAL ELECTRON
(NEGATIVE CHARGE GOING FORWARD IN TIME)
+t
0
-t
VIRTUAL POSITRON
(NEGATIVE CHARGE GOING BACKWARD IN TIME)
λ*

Figure 59. A photon is a single oscillation of a carrier wave. It is also two virtual electrons, one going forward in time, and one going backward in time. With internested modulations (subphotons), the structure of the photon becomes extremely complex.

Table 35. PHYSICAL CHANGE

- **COMPOSED OF ACTION**
- **h = BASIC QUANTUM**
- **TWO CANONICAL VARIABLES**
    - **ENERGY/TIME** $(\Delta E \Delta t)$
    - **MOMENTUM/LENGTH** $(\Delta p \Delta L)$
    ETC.
- **ENERGY/TIME**
    - $h = (+\Delta E)\ (+\Delta t)$
    - $h = (-\Delta E)\ (-\Delta t)$

If the photon is of a certain magnitude, given by Planck's constant, then it is an **observable photon.**

If the photon is less than h in magnitude, then it is a **virtual photon.**

A simple photon in vacuum can also be considered to be one cycle of a sine wave. One half of the sine waves exists in positive time, hence is/contains a virtual electron.

The other half of the sine wave exists in negative time, hence it is/contains a virtual positron — an electron traveling backward in **time.** This second half of the full photon (a single sine wave oscillation) is the phase conjugate (time reversal) of the first half.

As we stated previously, the full photon in vacuum actually exists as a presently visualized "positive time" photon and a phase conjugate "negative time" photon , a "serially linked pair," where **each** photon is only one-half the sine wave. This resolves the conflict inherent in wave/particle duality.

It also has a great deal to say about engineering the vacuum and about detectors and the detection process.

In the spontaneous decay of a virtual photon, it can be seen that one part (the virtual electron) is associated with positive energy and positive time; the other part (the virtual positron) is associated with negative energy and negative time.

The continual "switching" between positive and negative time in an observable particle's absorption and emission of virtual photons **(and** the associated electron/position +t/-t pairs) means that the positive flow of time, to the macroscopic observer, is continually being "started" and "stopped" (created and destroyed).

This continual attachment **and detachment of positive time to and from the "observer particle" creates the "past" and the "future" to which the observer seems somehow to be connected, and yet not connected.**

Engineering Local General *Relativity*

In a flat spacetime (linear vacuum), the two time flows are balanced, as are pair creation and pair annihilation. In this case, conservation of charge and energy hold.

Table 36. ORDINARY GENERAL RELATIVITY (OGR) IS A SPECIAL CASE

- **OGR HAS ASSUMED AWAY MOST LOCAL GR SYSTEMS, OF THE TYPE WHERE MAXWELL'S EQUATIONS AND THE CONSERVATION LAWS CHANGE LOCALLY.**

- **PHYSICISTS ARE THUS STRONGLY DISCOURAGED FROM CONSIDERING THAT GR CAN EASILY BE ENGINEERED IN A LOCAL EM SYSTEM.**

In a curved spacetime (nonlinear vacuum), one of the two triplets (positive electron/energy/time or negative electron/energy/time) predominates. Hence in a curved spacetime the rate of flow (production) of the two time streams is unequal, as is the production of the two kinds of energy and the two kinds of electrical charge.

A locally curved spacetime thus produces a predominance of either positive or negative electrons, and either positive or negative energy, and a predominance of the addition of either positive or negative time production.

The curved spacetime acts as a local source or sink accordingly, and both conservation of energy and conservation of charge can be locally violated in such a curved spacetime region.

As we stated, the locally curved spacetime produces either positive time or negative time more predominantly, acting as a source or sink for normal (positive) observer time. The local rate of flow of the observer's time can thus be speeded up or slowed down, depending upon the type of local spacetime curvature utilized.

It follows, then, that standing local gravitational waves can result in localized, stable gradients in the vacuum virtual particle flux, between the "high potential" part of the standing wave and the "low potential" part.

This allows the violation of conservation laws such as charge and energy in the local gravitational gradient, utilizing the localized curvature of vacuum to provide a special source.

For proof that conservation laws need not apply to a curved spacetime, see A.A.Vlasov and V.I. Denisov, "Einstein's formula for gravitational radiation is not a consequence of the general theory of relativity, **Theoretical and Mathematical Physics,** 53(3), June 1983 **(English translation);** Russian, Dec. 1982, p. 406-418. Quoting:

"This result is a particular consequence of the general assertion to the effect that in general relativity there are no energy-momentum conservation laws for a system consisting of matter and the gravitational field."

See also V.I. Denisov and A.A. Logunov, "New theory of spacetime and gravitation," **Theoretical and Mathematical Physics, 50**(1), July 1982, p. 3-76. This paper (p. 3) points out that:

"... **the gravitational field in general relativity is completely different from other physical fields and is not a field in the spirit of Faraday and Maxwell."**

A 1984 Soviet paper by senior Russian physicist C. Yu. Bosgoslovsky, "Generalization of Einstein's relativity theory for the anisotropic spacetime," is also very relevant.*

In composing his theory of general relativity, Einstein assumed that the local spacetime of the observer could never be curved, and instead would always be represented by a Lorentz frame (flat spacetime).

This severe assumption had the effect of "saving" the sacrosanct conservation laws, and maintaining the exclusion of electrogravitation.

Since then, Western physicists have raised Einstein's assumption — and the conservation laws — to a dogmatic belief system — in some cases, to near fanaticism.

To see a clear statement of these limiting assumptions imposed on general relativity to provide the severely restricted version taught in almost all Western universities, see Charles W. Misner, Kip S. Thome and John Archibald Wheeler, **Gravitation,** W.H. Freeman and Co., San Francisco, California, 1973, p. 19-21, 71-72, 367-369.

In other words, Western physicists still use a sort of "special relativity with distant curved spacetime pertubations," and call it *general* relativity!

---

*See also V.I. Denisov and A.A. Logunov. "The inertial mass defined in general relativity has no physical meaning," preprint p. 0214, Institute of Nuclear Research, USSR Academy of Science, Moscow, 1981.

The Soviets do not limit themselves to the same restricted general relativity theory as does the West.

Santilli (Ruggero Maria Santilli, **Ethical probe on Einstein's followers in the U.S.A.: An insider's view,** Alpha Publishing, Newtonville, Massachusetts) has documented what essentially amounts to a conspiracy in Western physics to shut out any generalization of Einstein's severely limited relativity.

It is precisely this near-total Western scientific prejudice — along with Heaviside's mutilation of Maxwell's original theory — that has excluded electrogravitation from being developed in the West.

Note also that, by embracing a "locally flat spacetime" assumed to be decreed by the "laws of the universe," in their rigid mindset Western physicists have excluded any possibility of performing simple laboratory experiments in locally curved spacetime.

They do not believe it can be done, so they have never tried.

But let us further address the importance of the negative triplet (electrical charge/energy/time) and its concomitants parity, gravity, and entropy:

Engineering Antigravity

In negative time flow, gravity is a repulsion, not an attraction.

Producing antigravity in an object is simply the production of excess negative time flow in that object.

That is readily achieved by curving local spacetime in the appropriate direction, and forcing the object to produce excess negative energy.

Mass, for example, is just a special form of trapped energy—and trapped energy (potential) is just trapped charge of one kind or another, whether observable or virtual.*

As such, mass represents a "localized potential" in the ambient vacuum, of a certain kind of "trapped energy/time charge."

---

*Actually, since it is in equilibrium in a dynamic and continual flux, a mass particle is actually a special trapped **rate** of action flow. A defining equation for mass in terms of the rate of action flow was given by the author in **Quiton/Perccptron Physics,** NTIS, 1973. Report AD-763210.

The mass/potential is continually being charged by the vacuum flux, and discharging and emitting charge flux into the vacuum flux. The mass is "in equilibrium" at its fixed potential.

Normal ("positive") mass is simply charged up with positive energy and positive time. And its external electron shells result in it presenting a "negative charge" face to the world.

If we charge up the mass, however, with negative energy and negative time, so that some of its charge potential now is of this second type, the trapped energy will now consist partially of negative energy. In addition, the mass will partially exist in negative time (be charged up partially with negative time).

When excess negative time flow is produced in a mass, the mass begins to be repelled by the earth as well as still being attracted to it in its positive time stream. The net result of the object's fixed attraction and increasing repulsion is that the object begins to lose weight in the earth's gravitational field and gets lighter.

When a sufficient rate of excess negative time flow (sufficient local spacetime curvature) is produced, the mass floats freely.

With additional negative time production rate, it accelerates ("falls") upward.

The rate of excess negative time produced may be controlled very simply by using a "negative time/negative energy" generator and varying the amount of the load applied to the device.

The negative time/negative energy generator can be rigidly affixed to a flying apparatus, serving as a sort of gravitational rocket or gravitational propulsion system.

Of course, the negative energy produced in the propulsion process can be used to light lamps and power electrical loads, as well as host of other things. (Yes, Virginia, it can also be used to generate force fields, power weapon systems, etc.)

Thus one can "eat his cake and have it too"; by using negative energy flow for power, a very practical antigravity spaceship can be developed.

An additional side benefit to the passengers probably exists: they should age at a slower rate when traveling in the vehicle.

As can be seen, since many kinds of VPFs exist in vacuum, the vacuum is filled with (and consists of) many types of "potentials." Overall, this matches very closely the view of general relativity, if we regard the vacuum itself as indefinite "spacetime", where no ordered universal frame with a fixed metric has yet been associated or prescribed.

Curved Spacetime and the Disintegrated Vacuum

From general relativity, additional characteristics of the modern vacuum/spacetime may be inferred or interpreted.

First, we may take a "flat spacetime" to consist of a charged vacuum, such that both the magnitude and structure of the VPF are essentially unchanged from point to point, and the flux of virtual particles and virtual antiparticles are balanced. Equal positive and negative time flows/charges exist.

Note, however, that we can have what casually may appear to be a "flat spacetime" but instead is "warped." This case exists when the magnitude of the overall VPF comprising the vacuum does not change from point to point, but the component structure of the VPF does vary from point to point.

In other words, the overall vacuum potential remains the same from point to point, but two or more individual potentials may canonically vary. Let us further clarify this point by analogy.

Suppose we view the vacuum/ether/spacetime as a special sort of gas, where the "gas" is actually a mixture of many, many gases.

It is a rather peculiar sort of gas; it exists in five or more dimensions and is composed of very strange, fleeting particles which . spontaneously are created and destroyed, each arising out of nowhere and returning to nowhere almost immediately.

There is only minuscule (negligible) time overlap (integration) of the existence of these virtual particles in the main.

That is, mostly each virtual particle — along with its associated energy, movement, momentum, charge, and increment of time — exists almost entirely as an individual.

The energies, movements, momenta, charges, and time increments of the individual virtual particles do not integrate or sum to any appreciable degree in vacuum.

Thus, although casually this ether/gas may seem to contain enormous "energy density", momentum density, charge density and time increment density, these are not *integrated* energy density, momentum density, and time density in the normal sense.

Instead, they are the densities *of disintegrated* energy, *disintegrated* momentum, and *disintegrated* time flow.

In scalar electromagnetics, we have called the disintegrated energy of vacuum **anenergy.** This clearly distinguishes that it exists in a fashion altogether different from normal, *integrated* energy with which we are accustomed.

By integrating anenergy, of course, one obtains ordinary energy—but it first requires an integrating agent. The most **usual integrating agent/operation is the spin of an observable particle of** mass.

Similar considerations apply to momentum and time.

With this more **precise interpretation, the vacuum contains enormous anenergy, but essentially no energy. It contains enormous virtual energy, but no observable energy.**

Unfortunately, however, orthodox physics does not yet clearly differentiate between the two states of energy, virtual and observable (disintegrated and integrated).

Instead, it continues to loosely utilize the term "energy" for both states, whether integrated or not. Thus it exclusively uses the term **"energy** density of vacuum." Rigorously, the term should be "anenergy density of vacuum."

Indeed, most physicists are not clearly aware of the distinct difference between the two different states of energy, insofar as the implication of integration or nonintegration.

Regrettably, then, we will continue to utilize the orthodox term, "energy density of vacuum." but the reader should be clearly aware that the vacuum "energy" and vacuum "stress energy density" as **such** are totally disintegrated.

Separation of Vacuum and Observable States

Because the energy density of vacuum is unintegrated, an integrated physical body — including one's personal body — can **exist** "in" the vacuum medium of incredible "energy" density, yet observably exist in a medium of zero energy density.

The unintegrated vacuum ether has enormous spatial density of *virtual* energy, but essentially has zero spatial density *of observable* energy.

Note, however, that in our hyperdimensional interpretation of the levels of virtual state, the vacuum spatially does not exist in the normal 3-space of observable matter.*

The vacuum occupies the 4th dimension (time) and all spatial dimensions (hyperdimensions) greater than the third — it occupies all levels of virtual state, but not observable state. It occupies all levels of disintegration, but not the levels of observable integration.

Exchanges occur between normal 3-space and the hyperspatial vacuum, through the common connecting dimension, time.

These exchanges (of virtual particles) are integrated by the spinning observable mass particle into the first quantally excited state — a delta (change) representing a single entrapped quantum — of the 5-space potential represented by the particle and its accumulating VPF. At that time a sharp electromagnetic (fifth dimensional) discharge of the quantum occurs, converting the accumulated 5-G quantum to the ordinary EM quantum of the 4th (time) and 5th (infolded space) dimensions.

This accounts for the so-called "collapse of the wave function", the production of unitary quantum change, and the discretizing of observable change.

We note in passing that time is the only "dimension" where everything can be considered to occupy the same "point" or "interval", but it is discretized and chopped into pieces (disintegrated), quite different in nature from the familiar three spatial dimensions of the observable (integrated) universe.

The dimensional separation (spatially) of the seething vacuum "energy" (anenergy) and the 3-space of normal matter allows a physical body to enormously interact with the vacuum at or near equilibrium at the microscopic level, but maintain its macroscopic form and stability as if no interaction were going on.

Partial Potentials, Curvature, and Warping

At any rate, we view the magnitude of the overall "potential" of this vacuum gas mixture, as the magnitude of the entire **"stress**

---

*Here we sharply differ from conventional physics, which hopefully confuses the concepts of vacuum, spacetime (indeterminate), spacetime (determinate), and frame.

ENERGETICS OF A POTENTIAL
Running in Place and Getting Nowhere



Figure 60. A potential is trapped energy. A potential in vacuum is trapped virtual-state "energy" or flux. A natural potential is trapped random energy. An artificial potential is trapped organized energy.

energy" or "pressure" of the mixture — IF AND ONLY IF this stress energy or pressure were somehow integrated.*

As can be seen, we can now look at each of the component gases in the mix as contributing a partial pressure or partial stress energy (an individual component potential) of the vacuum conglomerate.

We may have the overall pressure remain the same, yet canoni-

---

***Thus it's** really the **potential** stress energy density. The vacuum is nothing but potential!

cally change the partial stress energies (individual potentials).

In that case one has an internally twisted or "warped" spacetime.

A warped spacetime may prove quite useful, for example, for direct translation of one type of "energy" into another. In that fashion, one may conceivably obtain radiation energy at the expense of mass, or mass at the expense of radiation energy.

Or one may convert between potentials where one or more of the converted potentials are as yet unknown to orthodox physics.

Kaluza theory, for example, contains many potentials that are as yet unknown and undiscovered in nature. When undue simplifications are made to arbitrarily exclude the unknown potentials, the adapted theory leads to error in its predictions.

This was originally regarded as a great imperfection, and Kaluza theory fell into disfavor for decades. Then as modern particle physicists began to produce fundamental particles of an astounding variety, a Kaluza-Klein theory of 11 or more dimensions was found to very reasonably describe the emerging situation. Once again, then, Kaluza-Klein theory became a moving force among modern theorists.

One may also convert electromagnetic field energy into gravitational field energy, for example, and obtain enormous amplification of gravitational effects.

This is precisely what scalar electromagnetics seeks to do.

Since the electrical field between two electrons is about 10^{42} times as strong as the gravitational force between them, conversion of the EM charge flux into gravitational charge can conceivably yield up to 10^{42} times as much gravitational force as normal, depending upon the efficiency of the conversion process. Even with a process or device that uses electron currents and has an efficiency of only 10^{-22}, gravitational/inertial gains of 10^{20} are possible.

Note, however, that the levels of vacuum may also be compared to horizontal planes beneath the ocean.

For example, we may take a particular level of vacuum potential, and that level constitutes a sort of included "flat spacetime" of its own. By biasing the potential of a scalar transmitter and receiver to a given level, one may transmit (in either direction) at that level only, Receivers at higher or lower levels will detect nothing.

The immediate application to engineering the nucleus for such things as nonradioactive transmutation of elements, controlled nuclear fusion, electromagnetic healing, and processing nuclear wastes to render them harmless should be apparent.

To recapitulate our analogy, a true "flat spacetime" is a vacuum whose VPF does not essentially vary overall or in each constituent part, between two comparative points.

A "curved spacetime" is a vacuum whose overall VPF varies in overall magnitude, between two comparative points.

A "warped spacetime" is a vacuum whose VPF may or may not **vary** in overall magnitude between two comparative points, but whose partial VPFs vary their ratios, between the same two points. Note that a vacuum/spacetime can be both warped and curved.

It is stressed that we have not limited the number of dimensions **that** can be placed on the vacuum to Minkowski's four. We hold the number of dimensions necessary to represent both vacuum and observable matter to be arbitrary, but greater than four.

To unify electromagnetism and gravitation (which is what scalar electromagnetics is about), we must take five dimensions — four spatial and one time — to be the minimum necessary in modeling the unified theory, similar to Kaluza.

We state now a major characteristic: **Vacuum/spacetime consists entirely of potentials, nothing else, and these are hyperspatial a priori.**

The vacuum does not contain observable force fields nor any **Other** *non-potential* entity.

We also state without proof that in scalar EM theory it seems **very** possible to model the mind and its unification with physical **reality,** in a fashion subject to experimental verification.

Force and Mass Are Inextricably Intertwined

In foundations of physics, it is well-known that, paradoxically, force and mass can only be defined one in terms of the other.

We may use that paradox for a new interpretation of force and **force** fields: a force may be interpreted **to consist of** the time rate of changing the "mv" momentum of a mass system or object, instead of **being the cause of** its dp/dt.

That is, we may take the view that

$$\mathbf{F} \equiv \mathbf{dp}/\mathrm{dt} \qquad (4\text{-}14)$$

not just that

$$\mathbf{F} = \mathbf{dp}/\mathrm{dt} \qquad (4\text{-}15)$$

We have previously pointed this out and called it the "strong definition of force."

This immediately suggests the question: If force is an effect and not a cause, what, then, causes force?

Quantum mechanics already provides the answer: A differentiating operator must be applied to (coupled to) potential in order to produce a force field. The most usual "differentiating operator" is an observable spinning charged particle.

A charged particle exposed to the variation of electrostatic scalar potential between two points is exposed to a gradient (flow) in the virtual photon VPF, and hence to a directional "stream" of virtual photons. The observable charged particle couples to that stream. **Its** spin integrates the unobservable, disintegrated anenergy of the gradient flux into integrated, observable energy of the particle.

With greater integrated "pressure" on one side of the particle than on the other, the observable particle accelerates and translates This produces or "detects" (and comprises) an electric force between the two points.

Force is the mass particle(s) accelerating, either in time or in mass. Observable force is observable particle(s) accelerating. **Virtual** force is virtual particle(s) accelerating.

In **Quiton/Perceptron Physics,** I gave a new definition of mass that is consistent with this viewpoint:

$$1 \text{ kg. mass} = 17.053 \times 10^{50} \text{ switches/sec} \qquad (4\text{-}16)$$

where a switch is h/4*pi), having the units of action/time, or energy. This directly defines mass in terms of energy accumulation, where the energy accumulated is in equilibrium in a differentiated action flow.

Note that "energy" is the time rate of flow of action. Energy can only be accumulated (as a mass or a potential) by possessing two rates of flow of action simultaneously, one in positive time and one in negative time. This is a very deep statement that affects all of physics, but unfortunately it is beyond the scope of this present book.

To return:

The observable electric force field does not exist as such in vacuum. The vacuum and all its constituents are totally virtual. Only the potential ("potential for the electric force field, given a coupled charged observable particle") exists in vacuum, as pointed out by Richard P. Feynman et al, The Feynman Lectures on Physics, Addison-Wesley, Reading, Mass., 1964 vol. 2, p. 2.

The Concepts of Zipped and Unzipped Forces

As noted previously, the potential exists as an unintegrated virtual particle flux (VPF). Further, each little moving virtual particle is smeared in length and time, is coupled to finer VPF, and thus may be said to constitute a minute "force vector" while it exists.

Thus, the electrostatic scalar potential is composed of a myriad of little individual "virtual particle force field" vectors.

Since these little virtual vectors are essentially separate and unintegrated, one may say that the electric field is *unzipped* in vacuum. By "unzipped" we mean that the individual virtual particle E-field vectors are unintegrated.

A potential, for example, is composed of unzipped vector fields since it is comprised of unintegrated, virtual vectors.

To be static, the potential must be comprised of a pair (at least one pair) of unzipped vector fields, one in positive time and one in negative time. These unzipped vector fields must in turn be locked together. In this case, the positive time observer sees nothing (vacuum only), until he "observes" or detects. Normal detectors detect (and in so doing, they zip together) only the positive time unzipped component. The negative time (phase conjugate) vector held retraces the positive time field, in Newton's third law. Or, if generating a wave or pulse, it would be seen as a phase conjugate replica which affected the disturbing source.

Let us be very plain. **A "scalar EM potential" is actually two vector fields zipped together: one is in positive time, and the other is in negative time.** Each half is composed of microvectors. A dynamic gradient in this scalar EM potential (i.e., a scalar wave, for example) actually consists of two waves: one is the normal" positive energy/positive time" EM wave, while the other is the phase conjugate replica. When we detect the normal half (with electron detectors), we actually detect the second half with the atomic nuclei. Since it is a phase conjugate, it produces a negative momentum change on the nucleus {since one has p/(-t)} instead of LeSage's positive momentum change. In other words, it produces a drawing (attracting) force on the absorbing nucleus, instead of LeSage's assumed repelling force on it.

That is the entire secret of gravitation. And of electrogravitation. Knowing that, you can easily work out how to apply the necessary engineering to get antigravity.

But to return.

The potential can also be comprised of many unzipped vector fields at once. These may be deterministic (artificial potential) or randomized (natural potential).

The "force field" is disintegrated (unzipped) in vacuum, and integrated (zipped) on, of, and by an observable charged particle. In vacuum, it is always accompanied by its phase conjugate twin. When detection by an observable particle occurs, the spin of the particle acts as the "zipper," producing an observable force (which is actually of the particle accelerating, not "acting independently upon it.")

Vacuum is unzipped; observable mass is zipped.

Any zipped entity exists observably in 3-space; any unzipped entity exists in hyperspace outside 3-space, and is unobservable and virtual to the 3-space observer.

This interpretation is still consistent with the extended quantum mechanical view, where ultimately all observable forces are considered to be generated by absorption and emission of virtual particles by/from an observable particle (mass), at least insofar as what we may observably measure or detect.

Force, Force Field, and EM Waves in Vacuum

In the new interpretation, consistent with the quantum mechanical view, observable force becomes an effect, not a cause.

One may interpret quantum mechanics as stating that **any observable is an effect, since it is assumed to have a virtual state cause.** In the axioms of quantum mechanics, an operator is required for every observable.

The primary **causative agents are potentials, not force fields, as** is **now** firmly **established in** quantum mechanics.

The Aharonov-Bohm (AB) effect is a striking illustration of the primary reality of the potential rather than of the force field.

In the AB effect, potentials may still exist when the force fields **are** zero, and their interference can still cause real effects. The AB effect has finally become generally accepted by physicists after nearly three decades of controversy.

The immediate result is that, contrary to the outdated view imbedded in classical EM, observable E and B force fields do not exist *as such* in vacuum. This allows a totally new interpretation of the **nature** of the EM wave in vacuum: It is longitudinal. And actually, it exists in longitudinal pairs: the second is the phase conjugate of the first.

But of course we detect transverse waves with our detectors! However, this has a simple explanation.

Examine, for example, a straight-wire antenna. The spinning conduction electrons are longitudinally constrained, as is well known. The electrons are relatively unrestrained transversely in the **wire,** but can only "drift" longitudinally down the wire with a speed usually on the order of centimeters per second. The signal potential, however, moves longitudinally down the wire at almost the speed of **light.**

Obviously it is not the longitudinal movement of conduction electrons that constitutes the "signal", even though classical electromagnetics represents it that way.*

We note that a spinning electron whose movement is longitudinally restrained, but is unrestrained transversely, may be characterized as a gyroscope. Further, the axis of this gyroscope may be taken as lying in a plane perpendicular to the straight wire conduction path, since the electron is relatively unrestrained transversely.

---

*Actually, we do not really know how current/electrons travel down a wire, or even if it does/ they do. See three articles by Chappell Brown in Electronic Engineering Times: "Railgun Research Shoots Holes in Lorentz's Theory," April 6, 1987,p. 49-50; "Anomalies in Electromagnetic Law Spur Debate," Sept. 14, 1987, p. 58; "Electrons and Conduction: Not So Simple After All," Dec. 28, 1987, p. 21-22.

If now disturbed by a vacuum potential gradient, the gyroscopic electron is free to precess at right angles to the length of the wire. In other words, given a disturbing force, the electron will move transversely, or radially in the cross sectional plane of the wire, because of gyroscopic precession.

Thus, assuming a gyroscopic electron and its longitudinal constraint, we will detect transverse oscillations in the electron gas in the wire, IF AND ONLY IF the incoming disturbance in the vacuum is longitudinal, and IF AND ONLY IF the unzipped vacuum disturbance "couples" to (is zipped by) the gyroscopic conduction electrons.

Two things are certain in our electron-detector model: First, by the nature of a gyroscope, the conduction electrons move (precess) at right angles to the "disturbing force." Second, we only detect the movement of the electrons themselves.

Since we do detect transverse oscillations of the precessing electrons in the straight wire antenna, then it follows that normal electromagnetic waves in vacuum—that is, the component half that, interacts with the atom's electron shells and not with its nucleus — are (1) longitudinal, and (2) of such form that they couple to electrons.

Note that Tesla always insisted that electromagnetic waves in vacuum were longitudinal. For example, he called them "electromagnetic sound waves" in the ether. In "Tesla Maps Our Electrical Future," H. Winfield Secor presents Tesla's view of transverse waves in this fashion:

"Tesla upholds the startling theory formulated by him long ago, that the radio transmitters as now used, do not emit Hertz waves, as commonly believed, but waves of sound... He says that a Hertz wave would only be possible in a solid ether, but he has demonstrated already in 1897 that the ether is a gas, which can only transmit waves of sound; that is such as are propagated by alternate compressions and rarefactions of the medium in which transverse waves ***are*** *absolutely impossible."*

In his "The True Wireless," **Electrical Experimenter,** May **1919,** Tesla himself further stated:

"The Hertz wave theory of wireless transmission may be kept up **for** *a while, but I do not hesitate to say that in a short time it will be recognized as one of the most remarkable and inexplicable aberrations of the scientific mind which has ever been recorded in history."*

It should also be pointed out that our analogy permits the option of making a longitudinal wave in the vacuum in such a fashion that It will not couple to electrons.

In that case a normal"electron gas" conduction detector will not detect the new wave. Such a noncoupling EM longitudinal wave is **referred** to as a **scalar electromagnetic wave,** where by use of the **term** "scalar" we call attention to the fact that the vacuum potential **is** varying, but electron coupling to form vector force fields in an **electron** gas does not occur.

Since according to general relativity the variation of a potential in vacuum rigorously is a gravitational wave, then the scalar EM wave is a gravitational wave.*

We often say it is an *electrogravitational* wave to call attention **to** its electromagnetic origin, and to the absence of EM force field "bleeding away" of the 5-space Kaluza-Klein gravitational potential. We will discuss the 5-space G-potential shortly.

The conventional equation

$$\mathbf{E} = -\nabla \varnothing \qquad (4\text{-}17)$$

thus applies in the detecting electron gas, but not in the vacuum. Instead, in the nonmaterial vacuum, rigorously

$$\nabla \varnothing \neq -\mathbf{E} \qquad (4\text{-}18)$$

and this states that a gradient in a vacuum electrostatic scalar potential produces an antiphased electric force on and of a particle, on condition that a particle is present. The intent of equation (4-17) should be stated as

---

*It is also a very powerful gravitational wave, since for electrons it is some 10^{42} times as strong as "mass attraction" gravity waves.

$$\nabla \emptyset = -\mathbf{E} \qquad (4\text{-}19)$$

where the vertical line means "on condition that", and cp means "charged particle" (i.e., "that a charged particle is there.).

Equation (4-19) clearly shows that, in the vacuum, only the organized potential for an E field exists due to the quantity $\nabla \emptyset$ essentially as pointed out less strongly by Feynman et al in **The Feynman Lectures on Physics.**

Certainly, in the quantum mechanical interpretation, it is the potential that is real. The force field can only be made from the potential by a differentiating operation.

Since there is nothing in vacuum to perform this differentiating operation observably, one may interpret quantum mechanics as already prohibiting the existence of observable electromagnetic force fields in vacuum, at least in the form prescribed in classical electromagnetics.



Figure 61. A force-field vector is a movement of mass in one direction.

One may regard quantum mechanics — and physics in general - to be incomplete until electromagnetic theory is changed to incorporate the implications of quantum mechanics.

In scalar electromagnetics a new interpretation is taken, and the "overhaul" of electromagnetic theory is in progress.

We accent that scalar electromagnetics is still embryonic. It is at a stage similar to that where electromagnetism was when experimenters were still rubbing glass rods with cat fur and experimenting with little charged pith balls.

Early experiments are enlightening and encouraging; nonetheless, the phenomenology and the myriad of variables are not at all well-understood, even by the experimenters themselves, and certainly not by this author.

Zero-Summed Vector Systems: Shortcoming in Vector Analysis

It has long been pointed out by this author that a fundamental shortcoming exists in classical vector analysis itself when applied to physical systems. Let us briefly look at the construction of the vector mathematics theory, to clarify this shortcoming.

First, an abstract entity called a "vector" is conceptualized. This vector has both direction and magnizude, as contrasted to a "scalar" quantity, which only has magnitude.

Next, an abstract "vector space" is defined; this is a sort of "container" for mathematical objects called vectors, with certain inherent properties of the system specified. In other words, a vector space is an abstract "system" or "space" which can contain objects called "vectors."

Next certain other properties, operations, and entities are defined, one of which is the is the "zero vector".

Essentially the zero vector is defined by a set of operations; however, one simplified interpretation is "the absence of any vector of finite magnitude." By implication, in the abstract vector theory, all zero-vectors are defined to be identical.*

---

* Because, by their nature assumed in the concept, they have no internal structures. That is, effectively the zero vector has been too restrictively defined as "the absence of any and all finite vectors." It should be redefined as "the absence of any single vector being present alone." In that case the definition would admit "the presence of multiple translation vectors, where their combined translation action is zero."

In the vector addition operation, a group of finite vectors adds to a single vector called the "resultant."

It is standard practice in abstract vector analysis to replace a system of summation vectors by their resultant, since all appropriate properties of the summation system are retained by the vector resultant, in the abstract mathematical model.

This, however, is only possible because the abstract vector space has no such thing as stress, and a zero-vector has no substructure by definition. In the abstract space, only translation and rotation are possible, *by assumption*

It is also possible for two or more finite vectors to add to a zero resultant, in which case the system is replaced with a zero vector. Note that all further action by the summing vector components is eliminated by this assumption.

Again the appropriate properties of the summation system are retained by the zero resultant, in the abstract mathematical model, only because the *medium* (the abstract vector space) is not subject to stress, translation, rotation, and structuring.

Note however, that in physical systems, one cannot simply



Figure 62. The zero-summed vector system is an engine and an artificial potential.

replace a zero summation system of force vectors with a zero vector and retain all characteristic physical effects caused by the replaced system. The physical medium - including the virtual flux of the vacuum, *is* subject to stress, translation, rotation and structuring.

Physically, the presence of the summing vector component forces creates a stress and a dynamic macroscopic structure in the physical medium in and on which the forces are acting. Therefore the stress of the medium and its structure must be preserved and accounted for, even though a zero vector resultant force exists.

This is particularly true in the vacuum, where internal (infolded) stresses cause charge and energy conversion between one kind of charge/potential and another.

Maxwell's Theory Was Altered and Curtailed

In fact, Maxwell seems to have been well aware of the electromagnetic stress of the ether and its importance. After all, he believed the ether to be material and mechanical, and developed his theory accordingly.

For example, in his Treatise on Electricity and Magnetism, he wrote:

> *"There are physical quantities of another kind which are related to directions in space, but which are not vectors. Stresses and strains in solid bodies are examples of these, and so are some of the properties of bodies considered in the theory of elasticity and in the theory of double refraction. Quantities of this class require for their definition nine numerical specifications. They are expressed in the language of quaternions by linear and vector functions of a vector."*

Maxwell worked out his theory in quaternions since, at the time, the modern form of vector analysis had not been originated by Heaviside and Gibbs.

To recapitulate what we stated earlier: A quaternion consists of a vector part and a scalar part and can readily take into account the stress and strain of the medium. A vector consists only of the vector part, and does not take into account the stress of the medium.

It seems certain that Maxwell knew that the scalar part of the quaternion could be present and vary, even though the vector part was sum-zeroed. Quaternions, however, are devilishly difficult, and even in the time of their founder, Hamilton, few mathematicians and scientists ever mastered them.

Maxwell's theory was transposed (shortly after his death) to its modern vector form by Oliver Heaviside. Many of the characteristics of the scalar part of the quaternion were effectively discarded.

In the remodeling, the "unified" basis was omitted, and electro-

Table 37. MAXWELL'S EQUATIONS

- **INVARIANT**
  - **UNDER CONFORMAL GROUP OF TRANSFORMATIONS**

  - **IN 4-D MINKOWSKI SPACE**

- **GROUP INCLUDES**
  - **TRANSLATIONS**
  - **ROTATIONS**
  - **REFLECTIONS**
  - **INVERSIONS WRT HYPERSPHERES OF M-SPACE**

- **HENCE MAXWELL'S EQUATIONS INCLUDE TRANSFORMATIONS THAT**

  CHANGE INERTIAL FRAMES INTO FRAMES THAT ARE NOT INERTIAL.

  PROVED IN 1910 BY
  H. BATEMAN AND E. CUNNINGHAM

gravitation was accordingly discarded. Heaviside wrote a severely limited subset of Maxwell's theory; he did not by any means capture all of it.*

The new Heaviside vector reinterpretation of EM was far easier to calculate in than Maxwell's quaternions. Many physicists (there were really very few scientists in those days!) immediately loved it.

FitzGerald wrote glowingly of Heaviside's translation (and mutilation!) of Maxwell's theory:

> *"Since Oliver Heaviside has written, the whole subject of electromagnetism has been remodelled by his work. No future introduction to the subject will be at all final that does not attack the problem from at least a somewhat similar standpoint to the one he puts forward."*

Thus it was that Heaviside discarded the basis for scalar electromagnetics and electrogravitation from Maxwell's original work, and **the** so-called "classical Maxwell Equations" appeared for the first time in their modern vector form in Heaviside's work.

Then in the early 1890's a short but vigorous debate on vectors and vectorial methods occurred, involving eight journals, twelve leading publications, and over 30 scientists. Over half the publications were in the leading British scientific weekly journal Nature.

This debate, which Lord Rayleigh characterized by the statement "Behold how these vectorists love one another," together with **the** far greater difficulty of quaternion methods as compared to Gibbs' and Heaviside's vector analysis, spelled the death knell to the position of quaternions.

After some years, the Gibbs-Heaviside vector theory was firmly entrenched. The quaternion theory of Maxwell was forever modified **and** limited to the form we know today as "Maxwell's equations."

What really happened was that electrical physicists, faced with the formidable difficulties of quaternions, simply stampeded down the far easier road blazed by Heaviside, bowling over all protests against Heaviside/Maxwell/Hertz theory.

*Specifically, Heaviside wrote the subset of Maxwell's theory where gravity and electromagnetism do not interact and are mutually exclusive.

In Western universities today, no one actually teaches Maxwell's true theory! Instead, Heaviside's curtailed reinterpretation —- a severely restricted subset of Maxwell's theory — is taught.

And so that is the EM theory that is learned and applied.

One may rightly argue, therefore, that **Maxwell's theory has only been partially applied in its modern translated form, and the modern form of the Maxwell/Hertz electromagnetic theory is very much incomplete.**

To recover the stress factor in Maxwell's original theory, electromagnetics must take into account the *artificial* potential, which has a deliberately ordered, dynamic, deterministic structure. Scalar electromagnetics takes the patterned stress into account and deliberately uses it. Normal electromagnetics only considers the *natural* potential with randomized VPF structure implicitly assumed.

Scalar Waves ***and Polarization of*** *the* ***Vacuum***

Let us use a simple analogy. This will lead us into the profound implications of the deliberate vacuum polarization and curving of local spacetime that is provided by the vector zero summation (artificial EM potential) method of scalar electromagnetics.*

Visualize two sets of opposing and balanced forces pressing on the sides of a plate.

The forces sum to zero, so the resultant force acting on the plate for translation is zero. Hence the plate does not translate (move away or accelerate).

However, the plate is under internal stress (compression), and is in a quite different condition than when it has no external forces at all acting on it.

Now visualize the forces being applied with rigid rods welded to the sides of the plate, so that the forces may alternately "pull" as well as "push." Let the forces rhythmically vary, alternately "pulling" and "pushing", but always remaining balanced so that their summation for a translation resultant is constantly a zero vector.

The plate never accelerates or moves in translation, but it now contains an internal stress wave which rhythmically varies between compression and tensile stress. Rigorously the plate internally

*Vector **multiplications** that yield a zero vector product are also highly significant.

possesses a scalar stress wave, or a wave of "internal stress in the medium."

Now visualize a similar "plate-like" region of vacuum, with its virtual particle flux, instead of the material plate. Visualize two opposing sets of (unzipped) EM force fields, acting in and on the plate-like region, so that they rhythmically increase and decrease, changing direction also, but always with a zero vector summation.

In this case, there is an unzipped zero resultant EM force field (it is zero, by our assumed conditions), but there is a rhythmic oscillation of the intensity of the vacuum flux (intensity of the vacuum potential) and the vacuum structuring in the region. That is, there is a rhythmic and steady oscillation of the stress energy and structuring of vacuum, and hence of the curvature of spacetime, in **the** plate-like region.

Rigorously, this oscillation — which we call a scalar electromagnetic wave—is a gravitational wave, since the local curvature of spacetime is being oscillated.

Further, it differs from a "natural" gravitational wave in several respects:

1. It has a deterministic pattern or substructure,

2. It patterns or "polarizes" the vacuum,

3. It constitutes local curvature of spacetime, and hence localized general relativity - something which ordinary general relativity assumes cannot be accomplished,

4. It deterministically engineers the virtual state and local spacetime,

5. Since it is achieved by converting EM field energy into artificial G-field energy, one can expect tremendous gains of gravitational and inertial effects in and around electrical circuits utilizing such fields precisely,

6. It affects the Schroedinger wave and the probabilities of the

states being propagated forward by the Schroedinger wave. **With the scalar EM wave, one can thus deterministically engineer the emergence of quantum change, and violate one of the fundamental assumptions of quantum mechanics, that of the totally statistical nature of quantum change,**

7. The scalar wave can accomplish direct and localized change of the rate of flow of time (even to its reversal) and variation of mass and inertia, without concomitant translation of matter,

8. By locally curving and patterning vacuum spacetime, a stabilized standing scalar EM wave can provide macroscopic violation of the conservation laws, which rigorously depend upon a locally flat spacetime (Lorentz frame),

9. Since the components in the zero summation may be EM waves, and may be "locked together" and broadcast to a great distance and interfered there, effects at great macroscopic distances may be achieved, in violation of present assumptions of physics, and

10. Since excess negative time flow may be locally produced, antigravity, negative energy, and negentropy may be locally produced.

These are the startling implications inherent in correcting classical electromagnetics' improper treatment of zero-summed EM force vector systems in vacuum.*

By classically replacing the force vectors in a zero EM force field summation with a zero vector and discarding the components, one is totally discarding the fact that such a patterned system of oppositive forces forms a deterministically patterned stress in the vacuum medium.

By this innocuous error, classical EM discards electrogravitation, and avoids unification of gravitation and electromagnetics. It also avoids direct engineering of gravitation, vacuum/spacetime, inertia, rate of time flow, free energy, and quantum change.

---

*And its zero - multiplied force vector systems as well.

Generations of Western physicists and electrical engineers have acquired a mindset in only one aspect of the vastly expanded electromagnetics actually available.

Vector Zero Systems and the Kaluza-Klein Approach

Prior to 1921, Theodor Kaluza applied Einstein's new general relativity to five dimensions.

He produced a unified theory of electromagnetism and gravitation.

In Kaluza's theory, the ordinary 4-dimensional gravitational field and the electromagnetic field are but two different aspects of a single more fundamental field: the 5-dimensional gravitational field.

Kaluza's theory was published in 1921, on the personal recommendation of Albert Einstein, who had had Kaluza's paper for two years.

In Kaluza's model, electromagnetics is the 5th dimensional aspect of the 5-d G-field, while the ordinary 4-d G-field is the intersection of the 5-d G-field with our ordinary world.

Five years after Kaluza's epochal paper, Oskar Klein explained where the extra space dimension — the fifth dimension — was. He modified it as "wrapped around" each point in our ordinary 3-space.

In the Kaluza-Klein model, then, an electromagnetic wave— which moves spatially only in the fifth dimension — does not move through our 3-space at all. Instead, on its trajectory it "flows around" each point in our 3-space along its path.

Using Kaluza's model, we may regard the EM field as the normal "bleed-off' or escape of the 5-dimensional gravitational potential in the 5th dimension.

Any gradient in a potential represents a bleed-off of the potential from the high point to the low point. The way to prevent effective bleed-off of a potential at a point is to add an equal amount of bleed-in! The bleed-out and the bleed-in at the point then become balanced, so that an equilibrium state exists in the potential.

By this mean, the magnitude of the potential can be fixed by the two opposing bleed processes in equilibrium.

Table 38. KALUZA GEOMETRY

- **THEORDOR KALUZA, POLISH PHYSICIST**
- **UNIFIED THEORY OF ELECTROMAGNETICS AND GRAVITY [1921]**
    - **5 - DIMENSIONAL SPACETIME**
    - **5 - DIMENSIONAL GRAVITY FIELD**
    - **ELECTROMAGNETISM IS THAT PART THAT OPERATES IN THE FIFTH DIMENSION**

Table 39. 5-D G-FIELD BLEED-OFF [KALUZA 5-D THEORY]

- **FAR EASIER TO BLEED-OFF AS ORDINARY EM FIELD**

- **VERY DIFFICULT TO BLEED-OFF AS ORDINARY 4-D G-FIELD**

- **E.G., BETWEEN TWO ELECTRONS:**

$$\frac{EM}{G(4)} \approx \text{[illegible]}$$

- **BETWEEN TWO PROTONS:**

$$\frac{EM}{G(4)} \approx \text{[illegible]}$$


4-SPACE
EM INTERSECTION IS ZEROED
GRAVITY INTERSECTION (MASS, INERTIA, TIME FLOW)
EM VECTOR ZERO SYSTEM
ENERGY
ENERGY
ENERGY
ENERGY
ENERGY
SUBSTRUCTURE
Σ|K_i| = ANENERGY

Figure 63. An analogy for how scalar electromagnetics can engineer Kaluza-Klein unified field theory.


5-D G-FIELD
EM FIELD
4-D G-FIELD
ZERO VECTOR EM SYSTEM

Figure 64. The zero-vector system can engineer Kaluza-Klein theory.

WHERE DID THE EXTRA DIMENSION GO?



- **FROM A DISTANCE, A HOSE-PIPE LOOKS LIKE A WIGGLY LINE**

- **WHAT WE REGARD AS A POINT IN 3-SPACE IS REALLY A TINY CIRCLE AROUND ANOTHER DIMENSION OF SPACE**

Figure 65. The basic idea of Klein's explanation of where the extra dimension is.

Table 40. PHYSICAL REALITY IS ELEVEN DIMENSIONAL

- **IN THE KALUZA-KLEIN THEORY THE GAUGE FIELD SYMMETRIES BECOME CONCRETE**

- **THEY ARE THE GEOMETRICAL SYMMETRIES ASSOCIATED WITH THE EXTRA SPACE DIMENSIONS**

- **AN 11-SPACE IS REQUIRED BY THE GRAND UNIFIED FORCE THEORY**

PAUL DAVIES, SUPERFORCE.
1984, P. 160-161


5-D G-FIELD
BIG PRESSURE TANK
(ACCUMULATOR)
!!
??
PSSSS
WHOOSH
5th DIMENSIONAL EM BLEED
B̄
Ē
4-D G-FIELD BLEED

Figure 66. Normal EM bleeds off G-field.


5-D G-FIELD
BIG PRESSURE TANK
EM ZERO VECTOR
(ACCUMULATOR)
??
PSSSSSS
5th DIMENSIONAL EM BLEED
B̄
Ē
BOOM!
4-D G-FIELD BLEED

Figure 67. Scalar EM forces 4-dimensional gravitational field.

Note that this positively establishes that two or more zero-summed EM force field gradients produce and stabilize an artificial potential.

Usually, very little bleed-off of the 5-potential occurs in our normal 3-space. When the 5-space G-field is bled off on electrons, e.g., the resulting 5th dimensional E-field bleed-off is on the order of 10^{42} times as much as the 3-space G-field bleed-off.

This accounts for the enormous magnitude of the ratio of the electrical force between two electrons to the gravitational force between them.

Even when the 5-space G-potential is bled-off on and against the greater inertia of much more massive protons, its 5th dimensional E-field bleed-off is still on the order of 10^{36} or so times as much as the 3-space bleed-off.

Note that if we can stop the acceleration of the charged particles, bleed-off of the 5-space G-potential as EM force field cannot occur, and instead all of it must bleed-off as 3-space G-force field. This 3-G bleed-off normally occurs only minimally in electromagnetics, even for so-called "static" charges. This can be seen as follows:

When one charges a conductor such as a large metal sphere, for example, the electrons are unconstrained on the surface of the sphere. They are in constant agitation and motion on the surface, thus constantly bleeding-off the 5-space potential as myriads of squirming little E-fields. Only a very little is bled off as 3-dimensional G-field.

On the other hand, when one charges a dielectric, the electrons cannot be in as much agitation movement as they are on a conducting surface. Hence slightly more of the 5-dimensional G-potential is bled off as 3-dimensional G-field.

Therefore, charged conductors and charged dielectrics should exhibit slightly different gravitational and inertial properties when exposed to a gravity field potential difference. Highly charged capacitors, for example, should exhibit a small but detectable unidirectional thrust in vacuum. Apparently they do, as exhibited by the Biefield-Brown effect.

In addition, different materials should exhibit slightly different fall rates gravitationally. Again there is some evidence that they do, as exhibited by the Eotvos experiments in a modern reinterpretation by Fischbach et al.*

Electrogravitation Amplification Factor

If the movement of two free electrons could be entirely stopped, all EM bleed-off of the 5-d G-potential between them would be effectively zeroed or blocked. Then the 5-d G-potential would be forced to totally bleed-off into ordinary 3-d G-field.

For two electrons, this could increase the gravitational force between them by a factor of 10^{42}, if the EM bleed were perfectly blocked.

Such perfect blockage of the 5th dimensional EM bleedoff cannot be accomplished in practice. Normally, with the increase in potential caused by zero-summing, agitating electrons in a statically charged object agitate more intensely, moving and squirming in local, erratic constraints.

However, conversion efficiencies on the order of 10^{10} or even 10^{20} appear to be achievable in ordinary circuitry. In that case, gravito-inertial amplification gains of up to 10^{22} or even 10^{32} appear to be achievable. Gains of 10^{10} or more appear to be fairly readily achievable.

Time delay in producing the gravito-inertial effects may be experienced, however, because mass (nuclei) acts as a capacitance to incident scalar waves, exhibiting capacitive charging and discharging "time constants" when charging scalarly for a particular effect or to a particular pattern.

In these achievable amplification ranges, a single milliwatt of electrical power can control enormously powerful local gravitational and inertial effects, once the scalar EM charge is built up in the nuclei of the target material.

Excessive and frustrating "fiddling time" with the circuits is usually required, however, due to the charging "time constant" effect, the general lack of adequate measuring instruments, and the great uncertainty as to the phenomenology and major variables involved.**

---

*Ephraim Fischback et al, "Reanalysis of the Eotvos experiment," Phy. Rev. Lett., 56(1), Jan, 1986, p. 3-6.

**A series of scalar EM instruments, however, is being developed by Bedini, Schnur, Golden, and perhaps even Hewlett-Packard.

However, with persistence, in rather ordinary EM circuits and devices, the use of "summation to zero-vector" techniques and "multiplication to yield a zero-vector" techniques can lower the EM bleed-off of the 5-potential sufficiently to allow substantial local gravitational/inertial effects. By beaming and wave interference, effects at a distance can be achieved.

When gravito-inertial amplification of many orders of magnitude are involved, the assumption in ordinary general relativity of a local Lorentz frame (local special relativity, with local conservation laws applying) is readily violated.

Now one may have local general relativity, with concomitant violation of conservation laws, and local broken symmetry on a macroscopic scale.

Soviet papers already strongly point out that such unrestricted general relativity allows the violation of all conservation laws.

In the Soviet Union, scalar electromagnetics is called *energetics.*

Comparison of EM Concepts

Table 41 shows a comparison between three concepts of electromagnetics: classical, quantum mechanical, and scalar electromagnetic views.

As can be seen, scalar EM re-introduces Maxwell's original potential for electrogravitational variation and structuring of the stress energy density of vacuum spacetime. It applies Kaluza-Klein 5-dimensional unified theory in an engineering fashion.

It deliberately utilizes phase conjugation as a tool to achieve startling negative time/negative energy capabilities and results, including "free" energy and antigravity.

With scalar EM, it should be possible to overcome or circumvent most of the severely limiting assumptions of present physics and engineering.

The great conservation laws yield to direct manipulation and violation. The previously inviolate statistical structure of quantum change becomes deterministic and engineerable.

General relativity becomes an experimental scientific discipline in the laboratory, instead of a complex description of effects only observable in distant, massively curved regions such as on the surface of a star or near a black hole.

God does not play dice with the universe after all, just as Einstein suspected.

The Aharonov-Bohm Effect

In 1959, Y. Aharonov and David Bohm published a fundamental paper in **Physical Review** which pointed out the quantum mechanical implications of potentials.

The seminal paper is Y. Aharonov and D. Bohm, "Significance of Electromagnetic Potentials in the Quantum Theory," **Physical Review,** Second Series, 115 (3), Aug. 1, 1959, p. 458-491.

In classical electromagnetics, the potentials had largely been regarded as mathematical conveniences, having no real effects.

Table 41. Comparison of EM Concepts

CHARACTERISTIC	THEORY		
	CLASSICAL EM	QM VIEW	SCALAR EM (ARTIFICIAL ϕ)
VACUUM SPACETIME	LINEAR, NO CHARGE	LINEAR, CHARGED (VIRTUAL) STATISTICALLY	NONLINEAR, CHARGED (VIRTUAL) W/DETERMINISTIC COMPONENTS
VIRTUAL SUBSTRUCTURE	NONE (FLUID EQUATIONS)	YES, STATISTICAL	YES, STATISTICAL, DETERMINISTICALLY WEIGHTED.
FORCE, IN VACUUM?	CAUSE, YES	EFFECT, YES	EFFECT, NO
ZERO FORCE FIELDS	NO EFFECT	BOHM–AHARONOV EFFECTS	SUBSTRUCTURE EFFECTS, ENGINEERABLE
POTENTIALS	FICTICIOUS	REAL, PRIMARY, STATISTICAL SUBSTRUCTURES.	REAL, PRIMARY, DETERMINISTIC SUBSTRUCTURES.
CAUSATIVE AGENT	FORCE FIELDS	POTENTIALS	POTENTIALS AND INFOLDED FIELDS OF SUBSTRUCTURES
CHARGE	WITH MASS	WITH MASS	MASSLESS
RELATIVISTIC EFFECTS DUE TO	VELOCITY	VELOCITY, INTERFERING POTENTIALS	INTERFERING POTENTIALS
HIDDEN VARIABLES	NO	STATISTICAL, NEGLIGIBLE	DETERMINISTIC, MAJOR ROLE.
VECTOR THEORY APPLIED TO EM	OKAY	OKAY	REQUIRES REVISION
VACUUM EM WAVE	TRANSVERSE	TRANSVERSE	LONGITUDINAL W/SWIRLS
ENERGY/MASS CONSERVATION	YES	YES	NOT NECESSARILY. ANENERGY CONSERVED
CHARGE CONSERVATION	YES	YES	NOT NECESSARILY.
ACTION AT A DISTANCE	NO	NO, EXCEPT BOHM–AHARONOV EFFECTS	YES, SCALAR INTERFEROMETRY
SCALAR (ZERO-VECTOR) RESONANCE	NO	NO	YES
INERTIA IS ELECTRICAL	NO	NO	YES
GRAVITY IS ELECTRICAL	NO	NO	YES
MASS IS ELECTRICAL	NO	NO	YES
ELECTRO-GRAVITATIONAL WAVES?	NO	NO	YES
PRIMARILY INTERACT W/ (IN ATOM)	ELECTRONS	ELECTRONS	NUCLEONS
SPACETIME DIMENSIONS	4	4	>5
GEOMETRY	MINKOWSKI	PRIMARILY MINKOWSKI	KALUZA–KLEIN
ZERO-SUMMED VECTORS REPLACED BY	ZERO VECTOR	ZERO VECTOR	ARTIFICIAL POTENTIAL
RELATIVITY ASPECTS: LOCAL, DISTANT	SPECIAL, SPECIAL	SPECIAL, MAY BE GENERAL	GENERAL, GENERAL
CAN AFFECT SCHROEDINGER EQUATION	NO	NO	YES, CAN ENGINEER IT.

Table 42. THE AHARONOV - BOHM EFFECT

- **IN FIELD-FREE REGIONS**
    - **E - FIELD IS ZERO**
    - **B - FIELD IS ZERO**
- **POTENTIALS STILL EXIST**
    - **CAUSE REAL EFFECTS**
    - **INTERFERENCE IS KEY**
    - **CONTAIN SUM-ZEROED SUBSTRUCTURE**
- **DOES NOT FOLLOW FROM**
    - **MECHANICS**
    - **CLASSICAL ELECTROMAGNETICS**

However, according to quantum mechanics, the potentials are the real entities, while the electromagnetic force fields are just effects derived from the potentials by imposed operations on them.

Aharonov and Bohm showed that, even in the absence of the EM force fields, the potentials may still exist and interfere to produce real effects in physical systems. They suggested experiments to prove these predictions.

Interference of the potentials is the key mechanism producing real effects in charged particle systems, even in the presence of zero E-field and zero B-field.

Unfortunately, Aharonov and Bohm did not address this issue of zero-summed systems of EM force fields as one way of producing artificial potentials having unique interference characteristics.

That is, by implication they did not consider the deterministically substructured "artificial" potential, but only the randomly structured "natural" potential.

At any rate the "AB effect," as it came to be called, was rather hotly debated and fiercely resisted over the years. Steadily, more and more experiments were added, validating the AB effect. Finally, in 1986 it came to be generally accepted as proven to any but the most die-hard skeptic.

The AB principle represents a violation of both classical mechanics and classical electromagnetics. It is absolutely required, however, by quantum mechanics. And experiments have now established it as proven beyond question.

The potential, then, can be a free and independent field. Further, it can directly act on charged particle systems, even when classical electromagnetics does not recognize the interaction.

Curl-Free Magnetic Vector Potential (A-Field)

As an example, in classical EM the vector magnetic potential (the A-field) had been defined as a mathematical convenience by the equation

$$\nabla \times \mathbf{A} = \mathbf{B} \qquad (4\text{-}20)$$

But if the potentials are real, then conceivably the A field can be loosed from its enchainment to the $\nabla \times$ operator. In that case, it



A - FIELD CAN INFLUENCE THE MOTION OF ELECTRONS.

MAGNETIC FIELD AND VECTOR POTENTIAL OF A LONG SOLENOID.

THE FEYNMAN LECTURES ON PHYSICS. VOLUME II

Figure 68. The curl-free A-field. The magnetic vector potential (A-field) may be freed from its attachment to the magnetic field (B-field) and electric field (E-field). It can interfere at a distance to cause real effects. From it, either E-field or B-field, or both, can be made at a distance.

becomes a free, new, and independent field of nature with potentially unique characteristics.

For instance, its defining equation shows that magnetic force field can be made from it, and the rightmost term of the equation

$$\mathbf{E} = -\nabla \emptyset - d\mathbf{A}/dt \qquad (4\text{-}21)$$

shows that its time rate of change makes an electrical field.

Let us explain this in simpler terms, and somewhat more precisely than conventional theory. We will use the Kaluza unified G-EM interpretation and electron flow in our explanation.

In the A-field, we have a certain kind of 5-dimensional G-potential which can bleed-off as EM force fields in two ways: (1) in a swirl fashion, where the vortex producing the swirl moves parallel to electron movement, and the swirling is a torque or spin, and (2) in a linear fashion, where the time rate of change of the A-potential produces a linear E-field on the electrons.

The first bleed-off as given by equation (4-20) constitutes the magnetic B-field, and the second bleed-off as given by the rightmost term of equation (4-21) creates a component of the overall electrical E-field. Bleed off of the electrostatic scalar potential produces the other component of the E-field.

Now in general relativity (GR) theory, "the" G-potential is just a conglomerate of many things, each of which has the characteristic of curving spacetime. "The" gravitational field is not a single thing at all, but is composed of a collection of many things.

Thus if we realize that both the electrostatic scalar potential ($\emptyset$-field) and the magnetic vector potential (A-field) are components of the 5-d G-potential, then we see immediately that bleed-off of these two components of the 5-d G-potential creates all normal EM fields.

It follows that, if we produce a zero-vector summation of the two or more EM bleed-offs, we are actually "putting as much back in" to the 5-d G-potential through its A and $\emptyset$ components as we are taking out electromagnetically.

In that case, the 5-potential is in a state of equilibrium with respect to EM bleed-off in the fifth dimension. It is now forced to bleed-off in the only other way it can: as ordinary 3-dimensional gravitational field. Thus by vector-zeroing EM force fields, we turn KM field energy into G-field energy and vice versa, via the intermediary of the 5-potential.

At any rate, soon after publication of the Aharonov-Bohm paper, experiments showed that, if the magnetic field is trapped inside a long solenoid, a phase shift still is induced in the two-slit electron experiment, even though — classically — no contact of the enclosed magnetic field and the moving electrons occurs. This phase shift is explained by the fact that the freed A-field exists outside the trapping solenoid, even though the B-field does not. Consequently, interaction of this curl-free A-field with the electrons produces a phase shift of the QM interference detection pattern.

This proves that curl-free A-field is real and causes physical effects.

It also proves that a form of "action at a distance" is real, just as required by quantum mechanics.

Years ago, Frank Golden and this author — together with Dr. William Tiller — experimented with "free A-field" devices. Golden went on to develop prototype transmitters and receivers and a prototype underwater communication system.

Since that time, Gelinas has patented several curl-free magnetic vector potential (free A-field) devices. See U. S. patents numbers 4,447,779, May 8,1984; 4,429,288, Jan. 31,1984; 4,429,280, Jan. 31,1984; and 4, 432, 098, Feb. 14,1984. These patents are assigned to Honeywell.

Fractional Charges, Magnetic Monopoles, and Magnetic Currents

Fifteen years ago, a most distinguished gathering of physicists occurred in Trieste, Italy to review the physicist's conception of nature and how it developed. Seven Nobel Laureates were in the prestigious audience. The keynote address, appropriately, was given by P.A.M. Dirac, and — appropriately — was entitled "Development of the Physicist's Conception of Nature."

Dirac called attention to the possibility of fractional charges, and unexpectedly presented some of the data from experiments done lung before by Felix Ehrenhaft.

Years earlier Felix Ehrenhaft, former director of the Physical

Institute at the University of Vienna, had reported a number of experiments where — purportedly — he easily obtained fractional electrical charges.

Whereas Millikan had used liquid oil drops in his experiments to determine the charge of the electron, Ehrenhaft used little solid, red selenium oxide spheres. Not only could Ehrenhaft get a fractional charge, but he could actually vary the size of the fraction by varying the size of the spheres.

(Knowing what has been discovered in the last two decades on the complex bond structuring of water and liquid hydrocarbons, one might very well suspect that a solid — which has one less degree of freedom than a liquid — could possibly yield a very different experimental condition from a liquid, from first principles. However, no one seems to have noted that, or taken it into account.)

(Also, Ehrenhaft's results were replicated by other researchers who used his experimental methods. They published scientific papers, but that made not a whit to the scientific community, which simply rejected the experimental evidence.).

Dirac pointed out that Millikan himself, in his oil drop experiments that established the charge of the electron, reported one anomalous experiment which yielded a fractional charge. He discarded the results of that experiment.

Ending his speech, Dirac stated that it all made him wonder if perhaps Millikan did have a fractional charge in that one experimiment after all. And well he might wonder. Ehrenhaft — almost unknown now to the present generation of physicists — may have found not only fractional electrical charges, but the magic magnetic monopoles as well.

Over and over, Ehrenhaft reported the results of experiments which disagreed with the notions of magnetic theory at the time.

Again, some of these experiments were replicated, and reported by those researchers replicating them.

It didn't make any difference at all.

Now, finding a magnetic monopole — and the accompanying magnetic charge current — would be most satisfying to many theorists. That would make the equations of magnetics quite "balanced" with respect to electricity.

However, no one —at least whose results have been accepted -

has yet found a magnetic monopole or magnetic current.

Stanford researchers have perhaps come closest, and even reported the results of one exciting experiment that found the magnetic monopole. However, the team has consistently failed to be able to replicate those results. And in science, "no replication, no acceptance" is necessarily the dictum.

In a moment we will address a possible cause for this failure to find the magnetic monopole and magnetic charge current.

Some Ehrenhaft Experiments

Let's look at some simple, rather informal experiments that Ehrenhaft showed. We call attention to Alden P. Armagnac's excellent article , "Magic with magnetism," in **Popular** Science **Magazine,** June 1944, p. 130-133, 222, 226. In the first experiment, Ehrenhaft seems to have dissociated water with a permanent magnet.

First, Ehrenhaft seals two rods of pure iron, in holes through opposite sides of the U in a U-shaped glass tube filled with water. Then he uses the two rods — which protrude through the tube into the water — as the pole pieces of a horseshoe magnet — either an electromagnet or a permanent magnet. Dilute sulfuric acid — one percent by volume — is in the water, to give it a very slight acidity.

Bubbles of gas rise up through the twin vertical columns of water, and are collected and analyzed. Most of the gas is hydrogen, as is to be expected from common chemical interaction of the iron rods with the very dilute sulfuric acid. However, some of the gas — ranging from two to twelve percent — is oxygen, and most of the oxygen is produced at the north pole of the magnet.

The pole pieces may be short-circuited with wire, to insure they are at the same electrical potential and prevent any electrical dissociation of the water.

Without the magnet, all the gas liberated is hydrogen, as is to be expected. No oxygen at all is produced.

And another very interesting phenomenon occurs. A strong permanent magnet of the Alnico type gradually loses a marked fraction of its strength — say, 10% in 24 hours. It appears that the energy dissociates water — very similar to electrical energy from a battery draining away when electric current is used to dissociate water.

The real question is: Is this experiment a demonstration of magnetic current?

If it is, then the textbooks are wrong, and there's another constituency in magnetism that has not been taken into account. Further, if it proves magnetic current exists, it has also proven magnetic charge — the magnetic monopole — exists.

If it is not a demonstration of magnetic current, then what is it? Why don't you get any oxygen liberated when the magnetism is removed? What causes the magnet to discharge its magnetic strength?

These serious questions do not appear to have ever been resolved.

In all fairness, however, we must warn the reader that other factors in the water can very seriously affect the outcome of this

EARTH • SUN - MOON TRIAD



Figure 69. Earth, sun, and moon are locked into a triad system. They exchange both normal energy and phase-conjugate energy. The phase-conjugate energy (negative energy, negative time) streams affect all "subtle-energy" earth experiments

experiment. As we now know, the bonding structure of water is incredibly adaptive. Every bit of water you examine, for example, is absolutely unique in many respects. And in other respects, it's a sort of "single giant molecule."

Be forewarned also that subtle experiments with water are affected by just about everything under the sun. Including the sun!

Ehrenhaft himself was quite embarrassed when this "decomposition of water" failed to be 100% repeatable. It can be done — but you may have to work at it a bit. The best water for this experiment is the most natural, pure ground water you can obtain.

At any rate, it may be that these experiments of Ehrenhaft's are related to the old notion of "watergas" — the changing of water in some fashion so that, as it enters an internal combustion chamber, it decomposes into hydrogen and oxygen, and is ignited by the spark and burns as a fuel. In the typical watergas case, the experimenter has a "green powder" which, when added to water, will allow it to be burned as a fuel when it is used in an ordinary engine. Such a capability, for example, seems to have been exhibited at least once, to the U.S. Navy, by an unorthodox experimenter named Anderson.

Of course, if fractional charges exist and can be controlled (and Ehrenhaft's experiments certainly seem to confirm this), then it is conceivable that a material could be found that would do the "green powder" function. That is, if the bonding electron that bonds hydrogen and oxygen in water were replaced by a fractional charge, the "fractionated water molecule" could just barely be holding together an a liquid. A strong hydroshock — such as going through the jet nozzles in a carburetor — could then cause many of these molecules to break apart, effectively dissociating the water.

A possibly related phenomenon was reported by Le Bon in his Evolution of Matter. The experiment was to hold a piece of ordinary aluminum under the surface of mercury in a container for a period of time. Then the piece of aluminum is taken out and thrown into a container of water, where it violently dissociates the water. At least one colleague was able to replicate this experiment by holding the aluminum beneath the mercury for 36 hours.

These Ehrenhaft experiments may also be related to the extensive use in the Soviet Union (and to some extent, in the U.S.) of magnetic treatment of water pipes so that boilers do not develop so much hard precipitate. Magnetic treatment of water, for example, can rigorously be shown to alter some of a liquid's properties.

Ament, for example, in numerous well-controlled repetitions has clearly shown an increase in auto gas mileage by using a strong magnetic apparatus on the fuel line. Best results are obtained by a magnet which only has one polarity facing the fuel line, and using three stages where the middle polarity is reversed. The effect of this apparatus is definitely scalar EM (gravitational) and expressed in the atomic nuclei in the molecules of the fuel flowing through the line.

Again, the Ehrenhaft experiments may be related to the strange results of Viktor Schauberger, who obtained motive results with water and natural energy that have not been duplicated before or since, so far as anyone can tell.

Schauberger utilized "implosive" energy rather than "explosive" energy — strongly suggesting he was using the negative time aspects of energy, hence negentropy. Schauberger also conceptualized this energy in a spiral form — and that is precisely the type of motion Ehrenhaft observed in many of his bubble experiments. That such negative time/negative energy is "natural" energy will be apparent from our next chapter, where we point out that all living things must use negative time/negative energy processes if they are to defeat the inexorable law of entropy — the increasing disorder of a system as its positive flow of time progresses.

Note, **for** example, **that a** system **that is 20% efficient in positive time would be 500% efficient in negative** time.

Let's look at another of Ehrenhaft's magnetic experiments.

Taking the air gap between two very flat, very parallel pole pieces of sufficient width, one obtains a very accurately-parallel, uniform magnetic field in between them. Now suppose you place some very small particles of material—both magnetic and nonmagnetic — in the air gap.

Common sense assures us that, if closer to the south pole, for example, one of the little magnetic particles will be attracted by **the** preponderance of south polarity. That is, a little magnetic north **pole** will be induced on the side of the particle nearest the south polepiece, and a little south pole will be induced on the particle on the side away from the south polepiece. The little particle will then be attracted to the south polepiece.

Again, common sense assures us that, if closer to the north pole, the situation is reversed and the little particle is attracted to the north polepiece.

Well, that isn't quite what happens. Some move to the south polepiece, and some move to the north polepiece. And it seems to vary by the type of material the little particle is comprised of.

Now try another experiment. Let's make a permanent magnet motor. Understand, this one is not quite "for free," for we'll consume "fuel"—the strength of the magnet and the acidified water solution.

In this one, we use a glass cylindrical cell, with one vertical iron rod at the top and another at the bottom, and the rods serving as the pole pieces of a giant horseshoe magnet. (Or, for ease you can use an electromagnet). The cell is filled with the same acidified solution as before.

Without the magnet, hydrogen bubbles can be seen rising as before.

Now put on the magnet (or turn on the switch). Voila! the situation with the bubbles changes drastically. A spectacular miniature merry-go-round — a "whirligig" — of bubbles forms between the faces of the poles and parallel to them.

Add some copper particles to the solution. The particles will rotate in the same plane, but in opposite directions from the bubbles. The stronger the magnetic field, the faster the particles and bubbles will contrarotate.

If the magnetic field is reversed, the rotation of both the bubbles and the copper particles is reversed.

Only a few months after this was reported in Popular Science Magazine, Brother Gabriel Kane of Manhattan College and Charlea B. Reynolds of the Federal Communication Commission confirmed Dr. Ehrenhaft's discovery of magnetic currents.

They made a drop of copper sulfate solution spin between the polepieces of a permanent magnet. They also made an interposed microscope cover glass spin from the rotation of the copper sulfate.

It was hinted they were heading toward power machinery. If so, nothing else was heard — possibly because they never solved the problem of consuming the magnet's strength and the acidified solution.

Bill Mueller, the present inventor of a free-energy device, has also demonstrated the spinning of a piece of plastic in a magnetic field.

After WWII, Dr. Ehrenhaft returned to his post in Vienna, published later work in French and other scientific journals, and died not long after.

What is a magnetic monopole?

First, let's reiterate what we mean by "magnetic field." It'll take a little bit to get there, so please bear with me.

By electric charge, we mean the virtual photon flux connected with a particle of mass or an object (of mass). One type of charge (by convention, positive) is modeled to constitute a "source" of this flux. The second type of charge (negative) is modeled to constitute a "sink" of this flux.

Everything in electromagnetics is fluid flow, you see. The old guys who formed the theory believed that electricity was a thin material fluid. So they modeled it that way.

They modeled the positive charge as an everlasting "sprayer" and the negative charge as a "sink" or everlasting accumulator.

They reasoned that of course this "stream" of electric fluid could "swirl" or rotate, just as normal fluids can.

This "swirl" in the stream of virtual photons is magnetostatic scalar potential — or magnetic pole for short.*

Obviously there can be two directions of swirl — one right-handed, and one left-handed, with respect to the direction of the virtual photon stream. So there are two kinds of "magnetic pole" — north (right-hand swirl) and south (left-hand swirl).

The strength of one of these "swirls" can vary, of course, and that's a variation in the strength of the corresponding pole.

You can also think of the "pressure" of the swirl, so to speak, **at** least for modeling purposes. In that model, north swirl is "higher

---

*Rigorously, a permanent magnet does not produce an observable B field in vacuum! Instead, it produces the dynamic, swirling "potential" for that field — i.e., an **unzipped** field. A particle of observable mass placed in this field integrates and "zips" — producing the observed B-field on and of the spinning observable particle.

than ambient" pressure, and south swirl is "lower than ambient" pressure, where "ambient" means "with respect to right-hand swirl." The swirl pressure is then considered to "bleed off/flow" from north pole to south pole. This is modeled by Faraday's "flux lines of force." This bleed off (gradient) from north pole to south pole is called the magnetic force field, or just "magnetic field" for short, even though in vacuum it's really an *unzipped* magnetic field.

Note that the original modelers didn't consider negative time and negative energy at all. And they didn't know anything about phase conjugation — in fact, the electron had not even been discovered when all this model was originally put together.

But back to the model. Considering the swirling fluid as "conserved", if you produced a concentration of one kind of swirl at one place, you had to decrease the concentration elsewhere, which is the same as producing and adding opposite swirl there. Thus, conceptually, in the simplest case (only two swirls allowed), a north pole and a south pole always occur together in a pair — though of course there's no limit to the distance between the pair.

Notice that if you have a conservative field such as we assumed, you are keeping your overall frame of observation Lorentzian — in other words, conservative. You do not have a "curved spacetime" to speak of, by assumption.

Now of course, you can have compound and very complicated magnets and magnetic fields — you don't always have to have everything so neat and simple. In that case, conceptually you could have — for example — one north pole and two south poles.

In fact, it's easily possible to demonstrate that: a bar of magnetic material is simply magnetized so that a north pole is in the middle, and a south pole is at each end. Now bend it around a bit, and you get the point.

However, now let us suppose that we curve spacetime itself, locally — something they avoid in present physics by pure assumption.

Specifically, we curve our local spacetime in such a fashion that there's more right-hand swirl in the local region than there is left-hand swirl there.

In that case, we have a north-pole region there , all by itself. We have a magnetic north monopole. If that "curved spacetime" region of trapped swirl is moving, that constitutes magnetic current, and it may be either positive (north polar) or negative (south polar) flow.

It's as simple as that! Only when you curve local spacetime can you get a magnetic "charge" or monopole. Everyone who's trying to demonstrate a magnetic monopole in uncurved spacetime is doomed to failure a priori. It takes but little reflection to see that, conceptually, a magnetic monopole is a curvature of local spacetime. Indeed, each of the two poles of a bar magnet is precisely that anyway.

Now a monopole can indeed be "made", by bending local spacetime correctly. It can be made in two ways: in the virtual state vacuum itself, or in and on physical materials. It's easiest to make it in the virtual state: just curving the local spacetime will do that. When this "excess swirl flux without corresponding antiswirl flux" is impressed into and onto matter, however, the atomic nuclei are affected, producing excited "magnetic states." In addition, a great deal of physical stress is created in the material, due to monopolar repulsion between the various "nuclear monopoles deposited in it."

If a sufficiently strong monopole intensity (magnetic charge) is produced in the material, the material will violently fragment from internal stress. When a metal, for example, undergoes such **a** "monopolar fragmentation", it is common to see "tiled edges" of the metal rupture, much as twisted little "planks" or tiles of metal unfurled and "split." Such a break may be a positive signature of the involvement of virtual magnetic monopoles (i.e., by the metal having acquired virtual magnetic monopolar charge, causing the disruption).

This precise type of metal fracture has been very well demonstrated in experiments by Canadian experimenter John Hutchinson. Anomalous, powerful breaks in metal have been obtained by Hutchinson where the two ends that break apart both have a north pole or a south pole.

The anomalous **hole in the fuselage of the Arrow DC-8 destroyed at Gander Air Force Base, Newfoundland on Dec. 12,1985,** strongly suggests that an electromagnetic missile struck the aircraft, inducing monopolar effects. That would also match the-**three** eyewitnesses' description of an anomalous glow on part of the aircraft as it faltered and then fell.

Supercharges and Fractional Charges

Now without further ado, let me just state flatly that the only way to get a fractional charge is to have an appreciable curvature of local spacetime.

To get that local curvature, it's going to be very difficult to use liquid. For weak effects, it will almost always change its bond structure and not localize the curvature in the nuclei. So "fractional charges" in liquid are much harder to come by.

However, with solids it's a different thing, particularly if you make the solid material very, very small and nonlinear — precisely like Ehrenhaft's little red selenium oxide spheres. There you can get **the** curvature to localize without so much bleedoff through the bonding lattice.

The greatest electrical wizard of all, Nikola Tesla, reported producing electrons with 50 times the normal electrical charge of an electron. That's readily understandable if you look at what's happening to the charge of a particle: To have 50 times as much charge, the electron must be exchanging virtual photon flux with its surrounding vacuum at 50 times the rate of the normal vacuum.

In other words, *it's the vacuum (spacetime) which must be*



Figure 70. Forming magnetic monopoles with a standing scalar EM wave. In a nonlinear vacuum (locally curved spacetime), virtual magnetic monopoles can be formed and deposited in materials.



Figure 71. Metal fracture by depositing magnetic monopoles. Demonstrated by Canadian researcher John Hutchinson.

changed, not the electron! Actually, that happens anyway whenever the electron is in an electrical potential field. There are many unrecognized assumptions in the postulate that the electron charge is fixed.

If you curve local spacetime in one direction, you get the charge, of an electron increased. If you curve it in the other direction, you get the charge decreased. In that case it's called a *quark*.

At any rate, our own scientists have been looking in the wrong way and in the wrong place for magnetic monopoles and fractional charges.

Work such as that of Ehrenhaft and others should be re-evaluated. And, most certainly, the basis of the present electromagnetic theory should be both re-examined and reformulated.

---

*Such as the implication that the free electron is always free to move, and that potential surrounding the electron always possesses a translating gradient when it changes. It does not consider the case where the virtual flux exchange between electron and vacuum increases isotropically, centered on the electron. That, of course, represents an *excited charge* of the free electron.

CHAPTER 5

EXTRAORDINARY BIOLOGY

Kervran's Proof of Biological Transmutation

In orthodox chemistry, one of the strongest dogmas is the stubborn insistence that it is impossible to create another element by chemical reaction. Most chemists also insist that all reactions occurring in living systems are chemical in nature. They believe fervently that chemistry can and must explain life itself.

In the early 1960's, a French researcher named Louis Kervran published work which flew directly in the face of the accepted chemistry dogma. Kervran reported the astounding results of his research showing that living plants were able to accomplish limited transmutation of elements. Kervran was then the Conferences Director at the University of Paris, and his first paper was published in **La Revue Generale Des Sciences,** July 1960.

What was so revolutionary was that, according to the prevailing wisdom of science, you can't transmute elements (permanently change the nucleus) except with enormous energy — certainly not with the microvolts and millivolts (and microwatts and milliwatts) that living systems can muster electromagnetically. *

Rutherford, the British physicist who discovered the nucleus of the atom, had shown in 1919 that you can bombard elements with alpha particles and transmute them. The accepted wisdom of today is exactly the same, except that the physicists have used heavier and heavier "bullets" in their artillery approach. No one has tried a controlled approach, for the catchecism is that you have to use the *wham it harder!* approach.

In other words, to most scientists the whole thing had to be preposterous, and Kervran had to be deluded.

Kervran published further details of his work in a book, **Transmutations Biologiques,** Maloine, Paris 1962. But the initial reaction of most scientists was disbelief and skepticism. Few scientists would stoop to repeating Kervran's experiments, which of course they knew could not work anyway.

---

*Note, however.that since gravity is infolded EM, one can have extremely powerful infolded EM, yet only have miniscule electrical (outfolded) residues. Thus the actual "available power" in artificial biopotentials may not be quite so small after all.

Actually the effect is widespread amongst living systems. As Kervran pointed out, the ground in Brittany contained no calcium; however, every day a hen would lay a perfectly normal egg, with a perfectly normal shell containing calcium. The hens do eagerly peck mica from the soil, and mica contains potassium — a single step below calcium in the standard table of elements. It appears that the hens may transmute some of the potassium to calcium.

Further, if one tests this assumption, it is quickly shown to be true. Hens denied calcium but not potassium, stay perfectly healthy and lay perfectly normal eggs. Hens denied both potassium and calcium will be sickly and lay only soft-shelled eggs. If these sick chickens are allowed to peck only mica — which they will frantically do — everything returns to normal again.

Most orthodox scientists nevertheless remained skeptical or downright hostile.

However, a few other scientists began to repeat Kervran's



Figure 72. The Kervran effect. A biosystem can accomplish limited transmutation of elements.

experiments and replicate his results. Several of these corroborating scientists were (1) Professor Hisatoki Komaki, Chief of the Laboratory of Applied Microbiology at a leading Japanese university, (2)Professor Pierre Baranger, Head of the Laboratory of Chemical Biology of the Ecole Polytechnique in Paris, and (3) J.E. Zundel, then head of a paper company with a chemical analysis laboratory, and later a chemical engineer of the Polytechicum School of Zurich, Switzerland.

Later work by Zundel was particularly decisive: he utilized the mass spectrometer at the Microanalysis Laboratory of the French National Scientific Research Center, and neutron activation mass analysis at the Swiss Institute for Nuclear Research in Villigen to positively confirm an increase in calcium of 61% to an accuracy of 2%. Such results and instrumentation, of course, removed any doubt that the effect could be due to statistical variation. In the same experiments, the plants increased their phosphorus 29% and their sulphur 36%.

Komaki became head of a research laboratory at Matsushita Electric Company. There he conducted research conclusively proving that microorganisms (including some bacteria and two kinds each of molds and yeast) could transmute sodium into potassium. In fact, he placed a brewer's yeast product on the market that, when applied to composts, increases their potassium content.

Extensive work in the area has been done in the Soviet Union, where results similar to Kervran's have been substantiated.

Thus all doubt (to an open-minded scientist) was removed: living systems are able to change one element into another by some unknown means, using very feeble energy.

A noted French physicist, O Costa De Beauregard, suggested a mechanism for the transmutations, using weak force interactions and advanced waves.

No one — even Kervran himself— thought of negative energy/negative time interactions. The jury is still out on the actual mechanism, but it is absolutely clear that the transmutation does indeed occur.

The Japanese researchers, having replicated Kervran's astounding results to their complete satisfaction, recommended him to the Nobel Committee for a Nobel Prize for such epochal work. Thus Kervran became a Nobel nominee, though he was not granted the prize.

Kervran has since passed away, leaving behind his books and papers that point to a revolution in chemistry and physics - transmutation of elements at very weak energy.

Biological Transmutation Has a History

Actually biological transmutation — and transmutation of elements (alchemy) in general — has a history, of both results and suppression.

Louis Nicolas Vauquelin, a celebrated French chemist, discovered that chickens could produce more calcium in their eggshells than entered their bodies. Hence they had to be able to "create" the calcium, else their own bodies would have been completely depleted.

One of his contemporaries, however — Antoine Laurent Lavoisier — became the "father of chemistry." Lavoisier laid down the dictum that nothing was created. So chemistry fixed upon the notion that the combinations of elements could be shifted, but the element itself could not be transformed.

Not until the discovery of radioactivity did any crack in this solid wall appear. But still, the basic ideas of chemistry said the element couldn't be transformed chemically. It could only be transformed if one blasted the daylights out of it with an atomic or particle bullet. .

Today most chemists still hold that exact same opinion, unshaken.

To resume: Over a century ago, a chemist named Albrecht von Herzeele proved that germinating seeds somehow transmuted elements in the process. In 1873 von Herzeele published a book, **The Origin of Inorganic Substances,** where he showed research proving that plants continuously create material elements.

Even earlier, in 1822 an Englishman named William Prout had studied chicken eggs in incubation. He found that hatched chicks had more lime (calcium) in their bodies than was originally present in the egg!

Another French scientist named Henri Spindler discovered that, a kind of algae called Laminaria could create iodine.

A German researcher named Vogel had planted cress seeds in a

bell jar. They were fed nothing but distilled water; still, when grown they contained more sulphur than had been in the seeds originally.

Lawes and Gilbert, two British researchers, also found that plants could "extract" more elements from the soil than the soil actually contained in the first place.

Baranger performed thousands of meticulous experiments in plant transmutation of elements. He proved that the transmutations do occur. He also discovered that many things affected the germinating seed transmutation process: the time the seeds germinate, the type of light they are exposed to, the phase of the moon, etc.

None of these experimenters understood the transmutation process used by the living organism. But they proved beyond question that the process existed, and universally occurred.

Surplus-of-Energy Mechanisms Proposed by the U.S. Army

There has also been other very positive support for the thesis that if living systems transmute elements, they can produce a net source of energy in the process.

In 1978 an officially-funded effort of the U.S. Army Mobility Equipment Research and Development Command, Fort Belvoir, Virginia positively confirmed that mechanisms for elemental transmutations could occur in biological systems, from an energy consideration.

The work was performed under the direction of Emil J. York, Chief of the Material Technology Laboratory. Solomon Goldfein was the principal investigator for the effort. Robert C. McMillan, Chief of the Radiation Research Group of the laboratory, provided guidance on matters of physics and nuclear physics.

The abstract of the final report (S. Goldfein, Report 2247, **Energy Development from Elemental Transmutations in Biological Systems,** U.S. Army Mobility Equipment Research and Development Command, May 1978. DDC No. AD A056906.) reads as follows:

"The purpose of the study was to determine whether recent disclosures of elemental transmutations occurring in biological entities have revealed new possible sources of energy. The works of ***Kervran,*** *Komaki, and others were surveyed, and it was concluded*

that, granted the existence of such transmutations (Na to Mg, K to Ca, and Mn to Fe), then a net surplus of energy was also produced. A proposed mechanism was described in which Mg adenosine triphosphate, located in the mitochondrion of the cell, played a double role as an energy producer. In addition to the widely accepted biochemical role of MgATP in which it produces energy as it disintegrates part by part, MgATP can also be considered to be a cyclotron on a molecular scale. The MgATP when placed in layers one atop the other has all the attributes of a cyclotron in accordance with the requirements set forth by E.O. Lawrence, inventor of the cyclotron."

"It was concluded that elemental transmutations were indeed occurring in life organisms and were probably accompanied by a net energy gain."

The researchers also concluded that elemental transmutations occurring in life organisms are accompanied by losses in mass representing conversion to thermal energy, and that such energy probably is a net gain when compared to the amount required to effect the transmutation.

All in all, they concluded that the little cell with its feeble energy does quite well! It's in control of cyclotrons, and cyclotron forces, and direct conversion of mass to energy. Pretty good for a little bitty beastie, wouldn't you say?

Actually, one should point out that, according to nuclear physics, an atom gets a little heavier when it absorbs (usually by means of an orbital electron) a normal "positive energy" photon. That is, the addition of positive energy results in the addition of a little bit of "positive mass."

Negative energy, of course, does a similar thing to the nucleus — except that it adds "negative mass." Thus the nucleus of the atom, when it absorbs negative energy, gets lighter. This is seen in the external world as "loss of mass."

With our present nuclear physics, only positive energy is assumed except in extremely rare cases.

Thus the Army study — which was conducted and controlled by some excellent scientists — worked out a "loss of mass" the way they're trained to.

By adding some positive energy, the nucleus would gain some positive mass. **By adding some negative energy, the nucleus would lose some corresponding positive mass. The conventional physics then would equate this "loss of mass" as the direct conversion of mass to energy. And so it is, only it's conversion to negative energy!**

However, by pointing out the cyclotron mechanism in the cell MgATP, the Army researchers have made a most important contribution.

Note also that the whirling motion may be very much related to Viktor Schauberger's work and to Wilhelm Reich's work. Both of them worked with what they viewed as an unusual kind of living, spiraling energy.

All the orbital electrons of an atom also are whirling around in orbit, in the simplest model. Further, these orbits themselves move and rotate or precess.

Similar orbits and shells occur in the nucleus, at least in some models (several rather independent models are used there for specific things.)

It may be that a whirling, spiraling (cyclotron) energy motion is necessary to connect positive energy to orbital electron (negative charge) shells, and to connect negative energy to positive charge shells in the atomic nucleus. *

*Alchemy **and Unusual Critters***

In ancient times, the old alchemists pursued the dream of making gold. Obviously, if one could do that economically, one could become quite wealthy.

Just as obviously, the kings and rulers of the world took rather **a** dim view of such proceedings. After all, much of their own power rested on their ability to get and control gold. And if some "loose cannon" could make all the gold anyone wanted, then the national **treasury** of the king wouldn't be worth a plugged nickel. And that would finish the king, for he would be powerless.

•The spinning/whirling motion may be viewed as integrating the unzipped vacuum flux virtual vectors into zipped observable force vectors —just as great grandma's spinning wheel integrated fibers into continuous threads.

There are some unorthodox researchers today who take the view that the alchemists were stamped out—*not because they failed, but because they succeeded.*

I subscribe to the same view.

T.H. Moray had a process to "recover finely divided gold from quartzite sands." My personal, strong belief is that he possessed a practical transmutation process. His knowledge and techniques, of course, are still possessed by his sons, and reside through them in Cosray Research Institute, Salt Lake City, Utah.

The possession of such a technical secret may be one of the major reasons why the Morays have met with such intrigue, harassment, and suppression over the years.

To speak further on "making gold," we first have to present some details on some special "critters" that live, but that can't be observed through a normal microscope — even an electron microscope.

In that vein, toward the end of this chapter, we will present some of Royal R. Rife's fundamental discoveries. Pay particular attention to his discovery of "finer" living forms — which today we could only refer to as "living energy, virtual-state forms."

Let's call them **critters** for short.

At one time, when the earth was young and the radiation from the sun was different, conditions on earth were much hotter. Great volcanic activity and fiery eruptions were commonplace and nearly continuous. Huge storms, of size and magnitude undreamed of today, swept the primitive atmosphere. The oceans were frenzied.

Under those conditions, many types of "critters" were highly active. Most of the critters, for example, lived in and worked on the atomic nuclei of matter .

After all, the critters are living, virtual-state organisms. There's a continual exchange between the virtual state (the vacuum, or spacetime) and mass (the observable state). An atomic nucleus is like an island in the "virtual state ocean", and the flux interchange is like waves breaking onto the island and then washing back to sea. The critters live in that ocean, and wash upon, so-to-speak, the mass-islands and interact with them.

In those primal days, many of the present great mineral deposits of the earth were created due to the transmutation activities of the critters.

One kind, for example, lived in copper. In an "energetics" sense, this critter "ate" copper and "excreted" gold, so-to-speak. Much of the gold that occurs in great copper deposits today was formed this way in the old days under primal conditions.

When conditions on earth changed, these little "copper critters" ceased their incessant activity and became dormant, just as viruses can do. But the critters are still there in the copper ore, waiting to be activated.

And activate them you can! You can even get the critters into a solution, and then crystallize them out as crystals.

These crystals are what the alchemists of old called the **philosopher's stone,** with the power to transmute base elements into gold. There are several kinds of philosopher's stones; this kind is for copper.

At any rate, you can then place these special crystals on some copper (and add another thing or two), and restore them to a similar primal environment as of old. That is, heat them in an electric furnace. Blast them with terrible electrical bolts. Bathe them in intense ultraviolet light. That's just a nice, refreshing spring day for the critters!*

That stimulates them and revives them. They wake up after a long sleep — and they're immediately "hungry." So they go right to work on the copper. Boom! In a little bit there isn't any more copper, just mostly gold, with a little other miscellaneous residue thrown in, such as black ruby and silver (in the experiments of one of my close colleagues).

The gold is radioactive when first made. Fortunately, all isotopes of gold are very short-lived: just minutes suffice for the radioactivity to die away. So you wait half an hour and everything's okay.

That's all there is to it.

And if you do that and try to capitalize upon it, your life expectancy is about 24 hours.

I don't know whether or not biological systems, in their Kervran-transmutations at weak energy, deliberately manipulate similar "critters." I suspect, however, that they do, at least to some extent.

---

*Note the probable similar effects involved in the Miller-Fox-Urey experiments in biogenesis

The Cell Also Lives and Functions in the Virtual State

Obviously, to transmute elements the living system has to be able to directly affect and influence the atomic nucleus.

It has been shown that this is a cellular capability, for single-celled organisms can do it.

As we shall see, Rife's work showed that the living cell is connected to at least 16 intemested deeper levels of reality than a relative "point" under an ordinary microscope. Further, all levels are structured and organized.

Think of it! Each one of those levels is to the preceding level as microscopy today is to the normal world. Sixteen levels!

I think it's reasonable to state that the life of the cell is patterned and dynamically structured and functioning all the way into the virtual state; indeed, to very deep intemested levels of the virtual state. That is, it also functions *hyperspatially.*

We shall also see that the mind and thought involve these more subtle physical (though virtual) levels.

Thus the living virtual-state levels are a reality, for Rife proved it.

The living organized structures at each level are a reality, for Rife proved it.

The living ordering and control of dynamic functions on all those levels is a reality, for Rife proved it.

Those living virtual-level parts of the living organism — plant or animal — thus affect, function in, and reside in the atomic nuclei of the material that composes its bodily structures.

Beasties like bacteria and viruses also have living, organized energy structures in multiple levels of virtual state. Apparently, for these more primitive life forms, the virtual-state "energy part" can be separated and pass through a filter, then re-engender the physical form and/or itself cause the disease in a host! At least that is what Rife and other scientists showed.

"Bigger fleas have smaller fleas to bite 'em, And so on, ad infinitum."

Of course the living system can "work on" the nucleus and change it a little bit! If it couldn't do so, it couldn't stay alive and function in there in the first place!

The Kaznacheyev Experiments

Dr. Vlail Kaznacheyev is Director of the Institute for Clinical **and** Experimental Medicine in Novosibirsk.

For 20 years he has been directing highly unusual experiments with twin cell cultures. These experiments are vital to understanding disease and healing on a more fundamental basis than is presently utilized by orthodox medical science.

The Kaznacheyev experiments (several thousand) in the Soviet Union proved conclusively that any cellular disease or death pattern can be transmitted electromagnetically, and induced in target cells absorbing the radiation.

In the experiments, two sealed containers were placed side by side, with a thin optical window separating them. The two containers were completely environmentally shielded except for the optical coupling.

A tissue was separated into two identical samples, and one sample placed in each of the two halves of the apparatus.

The cells in one sample (on one side of the glass) were then subjected to a deleterious agent — a selected virus, bacterial infection, chemical poison, nuclear radiation, deadly ultraviolet radiation, etc. This led to disease and death of the exposed/infected cell culture sample.

If the thin optical window was made of ordinary window glass, **the** uninfected cells on the other side of the window were undamaged **and** remained healthy. This of course was as expected in the orthodox medical view.

However, if the thin optical window was made of quartz, a most unexpected thing happened. Some time (usually about 12 hours) after the disease appeared in the infected sample, the same features of disease appeared in the uninfected sample.

This startling "infection by optical coupling" occurred in a **substantial percentage of the tests (70 to 80 percent). From an orthodox medical view, these results were unexpected and unheard of.**

Further, if the originally uninfected cells were in optical contact


each cell as it dies emits a uv photon containing the exact virtual pattern of its death.
CELL CULTURE (sample #1)
uv photons
WINDOW
glass: effect not transmitted to 2nd sample
quartz: effect transmitted to 2nd sample after kindling lag time
environmental shielding
VIRUS INFECTION
CHEMICAL POISON
TOXIC IRRADIATION
UV
OTHER
quartz container
CELL CULTURE (sample #2)
quartz container

Figure 73. The Kaznacheyev effect. Thousands of experiments proved that (1) cellular disease is electromagnetic, and (2) it can be induced electromagnetically at a distance. Also called the cytopathogenic effect.


PHASE-LOCKED MODULATION
CARRIER
PHOTON

Figure 74. A photon is one oscillation of an electromagnetic carrier. It may have substructures that are modulations. Such a structure is called a "giant photon," or a "compound photon."


MAXWELL'S EQUATIONS
$\partial^3/\partial L^3$
$\partial^2/\partial L^2$
$\partial/\partial L$
$(\partial/\partial T)$
SECOND ORDER MODULATION, etc.
FIRST ORDER MODULATION
EM CARRIER
MASS AND MASSTIME
WEAK MIND-FIELD
WEAK NEUTRINIC FIELD
EM FIELD
MATTER
T
LT
L^2
L^3 (T)

Figure 75. Nested modulations are the key to hyperspatial engineering.

with the infected cells for 18-20 hours or so, and then were correspondingly exposed (optically coupled) to another uninfected cell sample, symptoms of the infection appeared in this third sample an appreciable portion of the time (20 to 30 percent).

Guided by A.G. Gurvitsch's work that showed that cells give off mitogenetic radiation (photons) that can affect other cells, the Kaznacheyev team sought an answer by looking for photons given off by the infected culture sample as its cells died.

They found that the cells in the infected culture gave off photons in the near ultraviolet when they died. The normal window glass was opaque to these near-UV photons and absorbed them. In that case, the uninfected culture on the other side of the glass was not exposed to radiation by the UV "death" photons from the dying cells, and they remained serenely healthy.

However, the quartz window was transparent to the UV "death photons". When the quartz window was installed, the UV "death photons" passed through it and were absorbed in the uninfected culture on the other side of the window. Most of the time, the uninfected culture which absorbed "death photons" sickened and **died** with the same disease symptoms.

The Kaznacheyev experiments proved conclusively that cellular death and disease patterns can be transmitted and induced electromagnetically.*

Structuring and Charging a Biopotential

Kaznacheyev thus demonstrated that a photon information/ regulatory system exists in biological systems due to a continual influx of EM energy from outside the system. That is, the cells of the biosystem are charged with an electromagnetic potential, and additions and changes to the potential are continually received. The cell is thus in minute disequilibrium.

Usually the myriad of continual inputs from the external environment into the cell's potential charge pattern (in its atomic nuclei) may be taken to be potential changes whose substructures are *disordered.* In that case, no specific environmental effect is observed except slight fluctuations without order — a miniscule form of "heating."

However, if a continual *ordered* substructure exists in the input from the external environment into the cell's potential, the cell's potential will gradually "charge up" with that pattern.

An analogy will prove helpful. Imagine an accumulator, a largo pot, that holds a volume of water. Several pipes are connected to tho pot, some are inputs for water coming in, and some are outputs for water flowing in.

Imagine the inputs all containing "blue" water, just in slightly varying shades. The water in the pot is blue, and may slightly rise and fall in level as the input flow rates vary. The water in the pot may also vary slightly in its blueness as the inputs vary. However, it will still be blue.

Now suppose that yellow water starts flowing through one of the input pipes, and at a goodly rate. Slowly the water in the pot will start to turn greenish as a greater percentage of yellow builds up. In other words, the pot slowly charges up with some of the "yellow" charge, in the process acquiring a "green" charge.

---

*We point out that this effect has been investigated in both the infrared and ultraviolet. IR to UV may be taken as a single harmonic interval — an **octave,** musically speaking. The same effect can be reproduced in any other "octave" (single harmonic interval) of the electromagnetic frequency spectrum. The **reversal** of the effect can also be achieved in any harmonic interval. The mechanism for these effects involves the cellular biopotential, Popp's master cellular control system, and the deterministically-tailorcd substructure of photons.

The biopotential in the cell experiments works the same way.

A cell has a biopotential built up, which represents the "nominal equilibrium" of the scalar charge on the cell. This biopotential, being mostly a "sum-zero" of virtual state vectors, is centered in and on the atomic nuclei of the cell, constituting charge patterns in these atomic nuclei. The biopotential extends out of the atomic nuclei, through the electron shells, into and through the molecules, through the internal cell structures and membrane, and outside the cell.

From the atomic nucleus on out through the cell, every layered structure or organization of the cell will layer, structure, and organize the biopotential accordingly.

This organized, structured cellular biopotential is continually receiving "charge patterns" contained in incoming photons absorbed by the cell. The biopotential is also continually exhausting some of its biopotential charge pattern in the photons (heat, light, etc.) that the cell emits.

The Cell's Electromagnetic Breathing

Via structured photon exchange, the biopotential of the living cell thus "breathes in" the virtual state charge structure of its environment, and "breathes out" its own internal virtual state charge structure.

So, in the experiment, the uninfected cells are continually absorbing photons from their surrounding environment, and emitting photons back to it as well. According to our scalar EM view, each photon it absorbs has a substructure that depends upon the part of the environment from whence it came.

These "substructures" are actually patterns of the sum-zeroed virtual vectors comprising the potential of the absorbed photon carriers.

Normally, since a large number of very different substructures are continually being "input" into the cell's potential from the absorbed photons, the substructure of the cell's potential receives an essentially disorganized continual input from the environment. This liquates to the fact that the environment does not normally specifically influence or change the cell's potential with ordered information (organization).*

When a cell dies, it ceases to maintain the bio-dynamics that sustained its artificial potential (that part due to bio-ordering by its organized life processes, above the background level of its "inert matter" potential). The dead cell's built-up artificial potential then "discharges" by emitting a structured photon.**

Since this photon (energy) comes from an *organized potential drop, the virtual substructure of the emitted photon is organized.* The photon, then — among other things — carries the exact organized virtual charge pattern of the dying cell's disease.

We strongly insist on the quantum mechanical view here: All physical changes — chemical, material, mechanical, whatever — at root level are constituted and caused by virtual state interactions, in direct patterns of virtual particle exchanges.

In the full QM view, what's really going on in primary physical reality is just a complex set of patterns and changes in potentials anyway.

The Summed Virtual Structures ofKaznacheyev's "Death Photons" Physically Kindle the Disease

At any rate, the Kaznacheyev experiments showed that the dying cells from the infected culture emitted photons in the near UV that contained artificial (structured) potentials. The virtual-state, patterned-substructures in this photon flux directly represented tho cellular disease pattern caused by the original cell's specific infection.

In other words, as the infected cells died, they emitted "death photons" which contained the **template** pattern of their death condition.

When these "death photons" are absorbed into uninfected cells, their deterministic substructures gradually diffuse into the cell's bio-potentials. Gradually the biopotentials of the new cells are

---

*There may be sufficient ordered input from the environment, however, to have something to do with territoriality in living things, salmon returning to a fixed place to spawn, turtles returning to the same beach to lay eggs, the migration of birds, etc.

Note that this photon is emitted from an atomic nucleus. Hence it is a phase conjugate (time-reversed) photon. It will interact with the biopotential of targeted cells, and thus reach their own atomic nuclei. This is the mechanism for Kaznacheyev's cytopathogenic effect. See particularly C.W. Rietdijk, **Found. Phy , 7(5-6), Jun **77, p.** 351

Table 43. THE LIVING AURA: THE CELL'S ELECTROMAGNETIC BREATH.

- **VIRTUAL EM FIELD**
- **STORES VIRTUAL PHOTONS**
- **ENVIRONMENTAL INPUTS**
- **OUTPUTS BIOPHOTONS**
- **COHERES ORGANISM**
- **TENDS TO STABILIZE**
- **EXPERIMENT ESTABLISHES**

Popp, "Photon Storage in Biological Systems,"
Electromagnetic Bio-Information. 1979

"charged up" with the integrated pattern of the disease.

The master cellular control system of the biosystem is itself a dynamically changing, ordered pattern in the biopotential of the cells, which is centered in the atomic nuclei comprising the cell materials. As the bio-potentials of the cells gradually acquire the "death photon's" substructure pattern, this pattern is also diffused throughout (modulates) the master cellular control system. All the cells in the sample (or in a biosystem) are now slowly charging up with the "death photon" pattern.

As Popp discovered, photons continually "leak out" of the virtual photon master control system of the biosystem. Some of these *leakage photons* are observable photons, **but most are virtual photons.**

Further, they are *structured* photons.

In other words, as leakage photons spill out of the master control system, observable change is now being slowly initiated in the physical structures, biochemistry, etc. of the biosystem's cells — and those changes are in consonance with the integrated "cellular death pattern" of the originally infected cells.

Note particularly that it is already well-known in quantum mechanics/electrodynamics that, when a photon is emitted from **the surface of a dielectric body, the entire dielectric body participates in that emission. If a photon is absorbed on the surface of the dielectric body, the entire**

dielectric body participates in that absorption.

Thus as irradiation by the "death photons" continues, the "death structure" in the irradiated cells increases. It is spread throughout the cell culture by the master communication system, gradually charging the virtual state structure of that system with the death pattern.

Spillage photons from the cellular control system occur throughout the culture. These photons are structured with the death pattern, and gradually affect the cell and its biochemistry physically. The previously uninfected cells thus physically start to acquire and exhibit the symptoms and characteristics of the disease pattern that killed the infected cells.

Electromagnetic Infection Results in Physical Disease

The new cells are now electromagnetically infected and physically diseased.

After all, that is all a cellular disease is in the first place — physical, electrical, and biochemical changes in the normal functioning of the cell.

For a given pattern of changes in the cells, a specific "disease" exists in them.

It absolutely does not matter what causes this exact pattern. If the specific physical pattern is there, the specific disease is there.

Note that **any ghost pattern in the virtual state flux can charge up physical matter — that is, the atomic nuclei of a mass. All that is necessary is that a continual flux of thin virtual pattern continually bathe (irradiate) the mass's atomic nuclei.**

The eventual emergence of this "ghost template pattern" into observable physical reality is called **kindling.** Kindling is charging up one or more atomic nuclei with an integrated virtual charge pattern until the integrated pattern breaches the quantum threshold, resulting in emergence of that pattern into observable physical change.

A Possible Cure for AIDS

One of the things going for the "good guys" and EM defense against AIDS is that cells are a lot tougher than viruses. Thus even non-structured EM signals can be used to effect cures in many disease cases.

In fact, ordinary ultraviolet (UV) irradiation of the blood has already been utilized to cure or control severe infections, including severe viral infections. I am indebted to Dr. William C. Douglass for pointing this out to me, and for permission to reproduce the following information from his important newsletter, **The Cutting Edge, Nov.** 1987, p. 3. The following material is quoted verbatim, with no editing.

"It's amazing what you can find by nosing around in the dusty archives of a good medical library. I came across another remarkable therapy that the AMA and drug industry (or whoever is in charge of supressing non-toxic treatments that work) have shoved down the memory hole."

"Back in 1933, Doctors Hancock and Knott treated a patient dying of septicemia (blood poisoning) with ultraviolet irradiation of the blood.[1] The patient was moribund with a blood stream infection **and** obviously near death. (Remember that this was before antibiotics and there was nothing to lose.) The patient made a complete **and** uneventful recovery."

"Searching further, I found that in 1928 a similar terminal infection was treated by ultraviolet light to the blood. This patient also made a complete recovery.[2] "

"So in 1928, practically in the middle ages, an incurable disease, blood stream infection, was cured with ultraviolet light. With such **a** breakthrough why wasn't it tried again for *5 years?* According to **the** record, *another 6 years* passed before it was tried for a third time.[3]"

"Back in those days infection was the number one cause of death. You can't help but wonder how many lives could have been saved if doctors weren't so resistant to new ideas. Just imagine a cure for **AIDS** being set aside for 11 years. Yet bacterial infections of the blood were uniformly fatal in 1935, just like AIDS is today."

---

[1] Northwest Medicine, 33:200, 1934.

[2] Knott, AM. J. Surg., Aug. 1948, pp. 165-171.

[3] Am. J. Med. Sci., 197:873, 1939.

"Finally, in 1940, 110 cases treated with ultraviolet spectral energy were reported. The results were uniformly good. Between 1940 and 1948 many other conditions were successfully treated, including vein inflammation (phlebitis), polio and asthma. Up to the late 40's *over 40 thousand* treatments were given with ultraviolet blood irradiation."

"And now for the most interesting part. In 1947, Dr. G.P. Miley reported on 79 cases of virus infection.[4] Miley stated that ultraviolet blood irradiation therapy could be relied upon consistently to control an infection of a virus in a safe and efficient manner.[5]"

"AIDS is a virus. AIDS-II is a virus (the HTLV-IV leukemia and lymphoma now sweeping the world). Remember that these killer viruses are within the cell and any chemical agent that enters the cell to kill the virus will often kill the cell as well. But ultraviolet irradiation *kills the virus without harming the cell."*

"A fine piece of crystal can be shattered by exposing it to just the right frequency. You can be standing in the room and the energy from that frequency won't harm you in the least. Viruses have the same characteristics, and so, in my opinion, frequency irradiation of the blood in the ultraviolet range is our greatest hope for curing AIDS."

"But the treatment is simple, safe, inexpensive and unpatentable. That doesn't bode well for its future, at least until a few *senators* get AIDS."

The Mirror Cytopathogenic Effect and Factors Influencing It

The cellular disease induction effect was called the **mirror cytopathogenic effect** (CPE for short) by the Kaznacheyev group. Mirror CPE appeared only when the quartz or mica window was no thicker than 0.8 mm. A. F. Kirkin also duplicated the experiments using a thin plexiglas window.

There are conditions which enhance the effect, and others which inhibit or degrade it. Irradiation of the detector-culture with a low dose of UV prior to its optical contact enhances the effect, increasing it to certainty (99-100%). Increasing the temperature to 38.5 degrees centigrade also enhances the effect (from 37% to 90% for example).*

---

[4] Rev. Gastroenterol. 15 271-277, 1948.
[5] Am. J. Surgery, Aug. 1948, pp. 170.

A necessary condition for the success of the experiment is the rotation of the holder with its two optically-coupled samples at a rate of about 24-25 revolutions per hour. Optical contact between the inductor and detector cells for a minimum of 4-6 hours is necessary, after which the cell cultures can be separated. A longer contact time is necessary for complete development of the irreversible effect.

Both cultures must be maintained in complete darkness throughout the experiment. Use of the detector as a new inductor in a successive state reduces the effect by 20-30%. Three or four such stages is sufficient to eliminate the effect.

There is a seasonal variation in the results. In more than 15,000 experiments, monthly variations and daily variations were noted. (The present author's interpretation of this is that it is due to the monthly variations in the virtual photon substructure input from the moon to the substructure of the cell's bio-potential. The daily variation is due to the daily variations in the virtual photon substructure input from the sun to the substructure of the cell's bio-potential.)

Negative results appear more often in winter. (The present author's interpretation of this is that it is due to the fact that the scalar potentials of the earth and the biopotentials of each living cell on earth are lowered in winter by the weaker flux from the sun.)

Effects are correlated with the polarity of the interplanetary magnetic field. Negative polarity of the field usually precedes the appearance of mirror CPE. (This is because of the positive nuclei — which prefer one direction of the magnetic field over another). Disturbance of the geomagnetic field several days before a culture planting also results in enhancing the mirror CPE effect. (Disturbing the geomagnetic field provides a "dithering magnetic disturbance" in the atomic nuclei which "livens" them. Consequently their readiness to charge-up and emit structured virtual state charges is increased).

Kaznacheyev further discovered that the Sun's activity and the

---

•This is very important. Preconditioning the cells by "dithering" them in the frequency band of interest, or in a subharmonic band, "livens" the cells for developing the irradiated pattern. Thin is similar to a dither voltage placed on a missile fin, making it much easier and quicker for the fin to move when an actual order is placed on it.

Earth's magnetic field greatly affected the results of his experiments. Large flashes on the sun seem to inhibit the effect. (Such flashes cause substantially increased irradiation of the atomic nuclei by sun-emitted substructures, charging them mostly with this disordered substructure pattern and literally "burying" the disease structure several decibels below it.) In a season of active sunspots, the mirror CPE effect becomes highly unstable. (The sun emissions are sporadically jamming the effect.) Under active sun conditions, the effect varies from 90-100% on some days to complete absence on others.

Some Biological Warfare Implications

The Soviets reported detecting near-ultraviolet photons — bioluminescence — as carriers of the death/disease pattern.

However, scientists at the University of Marburg in West Germany also duplicated the effect in the infrared. This shows that bioluminescent photons in the near UV and in the IR can definitely carry "disease and death" information between cells. Further, integrating a continuing input of such photons coherently integrates the disease or death pattern from the virtual state into the observable state.

Note also that portions of the infrared spectrum are a subharmonic of the near ultraviolet. Harmonics are well-known in nonlinear oscillator theory, and biological systems are filled with nonlinear oscillators. It may be that harmonics and subharmonics are directly involved in the death pattern.

If so, the induction of such "death patterns" upon normal electromagnetic carriers is directly indicated. For example, modulations covering several octaves in the region of 10 gigahertz and above might be constructed that are the analogues of some particular cellular disease. This modulation pattern could then be added to a common microwave carrier — say in the communication band, from 3 to 30 megahertz. Say, that is, to something like the giant Soviet Woodpecker "over-the-horizon radar" signals as carriers.

In that case, a large population could be bombarded, even on the other side of the earth, with "death photons" whose virtual state substructures carry the particular disease pattern. With sufficient time, many of the targeted persons would develop the disease.

Note that, even if the power and/or irradiation time is reduced so that the absorbed "death photons" are insufficient to actually kindle the disease in the targeted population, a heightened change in the substructure of the biopotentials of the cells of the targeted persons is still accomplished.

In that case, a precursor pattern — a predisposition for that disease — exists in the targeted persons.

If the actual disease agent is now loosed on that population, the agent will be far more **infectious and lethal than it otherwise would.**

In this way, even diseases which normally do not kill or seriously debilitate the infected person can suddenly become very lethal agents indeed.

Influenza, the common cold, etc. can become devastating killers if the exposed population has been electromagnetically "pre-conditioned" for enhanced susceptibility.

What Kaznacheyev Hid: The Role of Phase Conjugation

If cellular disease can be electromagnetically induced, can it not be electromagnetically corrected or healed?

If one could time-reverse the exact signal structure (the information) that kindled the effect, and bombard the diseased cells with that reversed pattern, would not the cell deviate back to "normal" and be healed?

The burning question as to whether cellular disease conditions can be corrected by time-reversed disease signals must certainly have occurred to the Soviet experimenters.

It is highly significant that they did not openly publish those results.*

As we have explained in the sections on phase conjugation and scalar electromagnetics, there are really two major kinds of photons:

---

*Recent information indicates the strong connection of Kaznacheyev with the Institute of Physiology and Biophysics and the Frank Institute in Pushkino, just outside Moscow. Since these institutes are deeply involved in microwave and coherent microwave "directed energy" weapons, it is highly probable that the Soviets are applying Kaznacheyev's "death photons" to microwave weapons — such as the Woodpecker transmitters. If so, obviously they would develop phase conjugate countermeasure signals as well.

(1) the "normal" photon carries positive energy and positive time. (2) the "time reversed" or phase conjugate photon carries negative energy and negative time.

Further, the Soviets certainly knew all about phase conjugate signals. After all, they discovered and developed the effect. We discovered it only from the open Soviet scientific literature!

Let us assume that the "death photons" in the mitogenetic radiation emitted by the dying cells are ordinary photons. Their virtual state structures (in positive observer time) are exact "templates" for the disease pattern.

Now suppose we detect the "death photons" with a phase conjugator, which by definition will produce a time-reversed counterpart to the input signal detected. In other words, the death photons are allowed to strike a phase conjugate mirror (PCM). Time-reversed counterpart photons — carrying the exact time-reversed template of the death pattern — will be created and emitted by the PCM.

These newly emitted photons now carry the exact "healing pattern" for that specific "death/disease pattern that was received and detected."

Further, if we "pump" the phase conjugate mirror, we can greatly amplify the output pattern, and hence greatly increase the healing pattern!

If one records the pattern of the "death photons" for a specific disease, one could of course modulate that pattern upon ordinary photons/signals — such as the Woodpecker signals — and accomplish disease induction or precursor conditioning.

By phase conjugating the pattern of the "death photons," one can produce an exact antidote. One can modulate this specific healing pattern upon ordinary photons/signals — such as the Woodpecker signals — and accomplish healing induction for that specific disease.

In other words, one can create the healing pattern — the antidote, if you will, for any biological warfare agent. Cancer, leukemia, AIDS, viral diseases, bacterial diseases, whatever. One can create the antidote within minutes after the first symptoms of the disease or death pattern appear.

One can then simply add the negating (healing) signal to power line signals, television and radio signals, special transmitters, etc. —

and immediately start to "administer the antidote" to the irradiated population one wishes to protect. *Now one can see why the Soviets are so ready to expose the entire world to something like AIDS. It doesn't represent a real problem to them, the instant they decide to negate it.*

So they can devastate the rest of the world, with the assurance that their population is safe.

They can allow some of their own people to develop AIDS — and even some to die of it — as a deception plan to delude the West while Western populations are succumbing en masse.

Then they can snatch their own population right back to health, from "the brink of the grave," so to speak.

Our government must immediately develop the same capability. It is straightforward. As weapons and counterweapons go, it is enormously cheap. It can be immediately and widely implemented. **And** it can protect our population against AIDS or any other biological warfare strike by the Soviet Union.

We can save our people from the AIDS knockout already unleashed upon us by the Soviet Union.

First let us do that. *Then* let us negotiate.

Remember this: **You can negotiate with the Russians only from a position of strength. If you are weak, they will bury you.**

If we do not immediately develop this biological warfare countermeasure, we are already as good as dead.

Popp's Master Cellular Communication System

Dr. Fritz Albert Popp has already discovered and pointed out the "virtual state" master communication system that controls all cells in the body, and all their functions.

Based on a thesis derived to best fit experimental results by Ruth nnd others, Popp postulates that biological systems generally have the capacity to store coherent photons that come from the external world.

In other words, the biosystem is open to environmental communication and exchange.

He has shown that the cell population is in a quasistationary state that is far away from thermodynamic equilibrium, as pointed out by Ilya Prigogine.

Popp also concludes from his analysis that ultraweak photon emission within biological systems can influence chemical reactivity. In fact, his analysis strongly implies that "ultraweak" photon intensity can regulate the whole cell metabolism and related phenomena.

The cell takes up photons from external radiation. This includes both "observable" photons and "virtual" photons. Since it stores virtual photons, it stores charge, or biopotential changes. Since its stored virtual photons may be coherent virtual photons, it effectively "polarizes" or structures its stored photon charge, hence its biopotential.

The cell emits "spillage" photons — both coherent and incoherent — from its stored potential.

Although Popp only uses conventional "unstructured" photons in his analysis, he shows that, at the molecular level, there is a stationary equilibrium, as far as photon storage and emission are concerned, between the molecular photon traps, the cell population, and the external world.

It follows that *coherent* photon/charge inception from the external world can directly and precisely influence the cell's biopotential, hence its functioning and control, by information input.

Incoherent photon inception, on the other hand, can only grossly affect the cell, such as by heating or sporadic effects.

In his "Photon Storage in Biological Systems," Popp points out the master cellular communication and control system as follows:

"The photons which we have measured can be seen as a sort of "waste" from a virtual electromagnetic field with a high coherence. This field has a tendency to become stationary over the whole organism."

After additional analysis, he adds:

"....Consequently, biological systems must exhibit 'holographic' properties to an extremely high degree. The successful trials in

finding 'pictures' of various organs in each other organ, such as the ear, the hands, the eyes (acupuncture, iris diagnosis) support these conclusions. Our assumption that the entire genetic information of the DNA is stationarily delocalized over the body in form of genons may be seen as a further striking example."

"From this we can easily deduce that pattern recognition, as, for example, repair mechanisms and immunity, depends finally on the coherence of the photon field within the body."

Finally, Popp states a most important conclusion:

"...In medicine **new aspects have developed, and not only for cancer problems. Diseases in general can possibly be understood in terms of electromagnetic interactions within the organism."**

Scalar EM Comment on Popp's Communication System

Popp and his colleagues have produced most important work and results indeed. They only need to add the impact of the zero-summed/multiplied electromagnetics (electrogravitation).

As we cover in this book, the biopotential of the cell is rooted in the nuclei of the atoms of the cell's constituent materials. To be sure, every internal physical structure of the cell correspondingly "levels" and structures the biopotential. The overall cellular communication system is actually the exchange of "leakage" photons — both observable and virtual — throughout the overall biopotential of the organism.

Further, going beyond Popp's work, both the biopotential and the leakage photons have extensive, complex internal substructures. Leakage and intercommunication occurs laterally at all levels of the biopotential, and vertically among cells and substructures.

The master cellular control system's primary electrical conductivity path is not through the electron shells of the atoms, but is through the nuclei-to-nuclei scalar EM "biopotential levels" pathway.

With scalar EM methods, organized signals (signals with specific internal nonzero vector EM waves, but which externally sum to zero vector resultant E and H fields) can be constructed for essentially any specific purpose. This includes "killing" a cancer or leukemia cell, destroying a virus, changing the DNA, etc.

This approach can directly reach and manipulate all immune and repair system functions.

The entire biochemistry and functioning of the cell — including its genetics — **is totally engineerable.** The Soviets have long known this, and have long since done it.

Further, a specific "charge pattern" of desired specific immunity (antibodies, etc.) can be designed and used to "charge up" the nuclei of the biosystem. This charge is then maintained by the system to provide permanent immunity. Thus one can develop, for example, an "electromagnetic innoculation" for AIDS, one for cancers and leukemias, etc.

Since the cellular control system is holographic, the "charge pattern" of immunity resides in every cell, including the blood cells.

Injecting a drop of blood from a scalarly immunized animal into another non-immune animal carries the scalar EM immunity pattern into the new animal. That charge diffuses throughout the overall biopotential of the organism, and the charge pattern activates the animal's immune system, including causing it to produce antibodies — according to the EM-transferred antibody template.

Antoine Priore demonstrated this effect numerous times. Thin was one of the great mysteries that confounded the orthodox members of the French Academy of Sciences.

The French Academy did not know of scalar electromagnetics, the cellular biopotential rooted in atomic nuclei of the cellular material, the cytopathogenic effect of mitogenetic radiation from diseased and dying cells, phase conjugation, and phase conjugated electromagnetic healing.

It is little wonder they did not comprehend the operational healing mechanism of the Bordeaux cancer-curing machine of Antoine Priore!

A New View of the Nature of Mind and Thought

The reason that Western science has not discovered what mind and thought are is simple: They have only built instruments and tools to look where the mind and thought *are not to be found.*

Let's look where they are to be found.

For example, consider the ionic discharges in and across the tremendous numbers of synapses of the human nervous system, and the slower discharge and migration of ions across cellular membranes, etc.

Considered as a single biological ensemble, these are much like a vast array of continual and continuing spark discharge vectors, slow charge current vectors, etc.

Overall, within the macroscopic space occupied by the body, these electromagnetic vectors sum almost entirely to a zero vector resultant. Only a tiny nonzero vector residue remains.

However, this vector zero summation has incredibly rich infolded signals, channels, and dynamic relationships (structure) within it.

Modern science/medicine measures the small nonzero electromagnetic residue (the remaining weak E and H fields) and tries to ascertain where and how mind and thought are accomplished, by studying that residue.

However, the residue E and H field remainders are simply the "garbage thrown out" of the glorious engines dynamically operating inside the vector zero summations (and multiplications).

The E and H field residues are the wastes or exhaust byproducts. They are not the functions of the mind/thought process itself; instead, they are the spillage or leakage from those functions.

Take a "frozen time" snapshot of the components of the zero vector summation. Regard the highly complex, infolded structure or pattern these components form.

Now take a second "frozen time" snapshot of the components of the zero vector summation, a very, very short time later. Subtract **the** previous "frozen pattern" from this second "frozen pattern."*

The difference or "delta" between the two patterns represents a myriad of thoughts, hence it represents the contents of the "thinking mind," in the most general sense.

The "mind" is the overall functioning and changing of the entire pattern's substructure, and the ability of an organism to have such **and** do such. The "ability of the organism to do such" requires at least

---

*Similar to the magnificient "double **exposure holography"** work of Dr Robert Powell.

two more nested levels of virtual state—two more hyperdimensions.

In simplest Kaluza-Klein theory, all those electromagnetic component vectors are in the fifth dimension. Hence they are hyperdimensional.

The zero-vector system may well have further infolded, internested levels of zero-vector systems. Systems within systems. These are hyperspatial, going into the 6th, 7th, 8th, etc. dimensions. Rife's microscope, for example, could reveal some of these levels; using evanescent waves, it could resolve some 16 ever-deeper levels of dynamic energy structure.

Everything driving the component vectors themselves is higher dimensional.

"A thought" is the exact change of a localized pattern (localized zero vector summation whose components are changing but remain ing zero summed) from one moment to the next.


EACH BIOFRAME HIGHER THAN S'''
IS CONNECTED, BY ONLY THREE
ORTHOROTATIONS, TO LAB FRAME S.
EACH S''' AND HIGHER BIOFRAME IS A MIND.
A PARTICLE IN ONE OF THESE FRAMES IS A
"THOUGHT" OR "THOUGHTFORM" IN A MIND.
LABORATORY FRAME
π/2
π/2
π/2
velocity wrt s
C
C2
C3
mind
mind
mind
mind
S^N
THOUGHTS
S
MATTER (PARTICLE)
partially material
virtual photon
virtual neutrino
S'
S"
S'''
ELECTROMAGNETIC FIELD (PHOTON)
DEBROGLIE WAVE REGION & virtual state vacuum
FLUX LINES (NEUTRINO?)
MINDS (VIRTUAL)
(thoughts)
(thought-forms)
(bioenergy)

Figure 76. Hyperframes, vacuum, virtual state, minds and thoughts.

Thought is always a pattern change, of the components inside an EM vector zero summation.

Most thoughts are totally "unconscious" (multiple simultaneous or "parallel" thoughts). A few are conscious (serially ordered, singularly considered and processed).

The unconscious mind is totally a parallel processor (many things/thoughts at once).

The conscious mind is totally a serial processor (only one thing/ thought at a time).

Most persons never take the time and trouble to reflect and notice that, consciously, they only can perceive one single thing at a time. Of course, the conscious mind is so rapid that by habit they assume they can perceive many things at once.

Since the conscious mind cannot discriminate the "multiple images in the slide projector at once" of the unconscious mind, that's what makes it unable to "be conscious" of the contents of the "unconscious."

In fact, the unconscious mind is totally conscious — it's just **multiply conscious "simultaneously."** (Which sheds some interesting light on why one can develop multiple personalities, for instance).

When the conscious mind "regards" the unconscious contents, it sees "something" which has "multiple meanings at once."

That's what we call *symbolic*. A symbol is something which can have many meanings at once.

That's why the unconscious content always "symbolizes" something when it's trying to communicate to the conscious mind. It's necessary to interpret the symbols to understand what the message being communicated is.

That's why dreams, for instance, are symbolic. And why it usually takes a trained psychiatrist or psychologist to properly interpret the symbolic representations manifested in mental disorder, and get at the underlying cause being symbolized.

With deliberately constructed scalar EM, any or all of the conscious/unconscious portions of the mind can be available for engineering and control/change. Eventually you will be able to put contents of the mind and memory on a video screen if you wish to.

It will also be possible to interact with the mind's contents electromagnetically. Mental illness will be treated directly, on an engineering basis.

Of course this opens up the frightening possibility of hostile misuse to the detriment of an individual. It will even be possible to change or erase his or her very personality itself. We pray, of course, that such a powerful tool will not be utilized this way, but will be used to heal humans, not hurt or kill them.

Unfortunately, Lisitsyn's work reveals that the Soviet Union has long since applied energetics (scalar electromagnetics) to mind control and mind engineering, including deciphering the genetic code operation. Controlled induction of images and sensations inside the brain — where they are processed as if self-originated — has been reported by the Soviets. Indeed, they have reported being able to control whether or not the induced material should rise to conscious awareness, as well as when it should rise to consciousness.

For years, U.S. intelligence analysts and U.S. scientists simply did not believe that electromagnetic signals could directly influence consciousness.

However, they were forced to reevaluate that position when a Soviet medical machine — the LIDA device — was openly obtained and evaluated.

The LIDA machine — a small unit somewhat larger than a briefcase — has been used in Soviet medical facilities to treat humans for decades.

The device uses a 40 megahertz EM carrier and very complex waveforms (signal modulations with complex mixtures of frequencies, phases, etc.)

When exposed to it, a person is caused to gradually fall into a trance-like, catatonic-like state within a few minutes. That person becomes very still and very quiet.

It was reported that the machine was tested upon a cat and had the same effect upon it.

One American scientist stated that the device had actually been used in North Korean "brainwashing" of U.S. prisoners of war in the early 1950's during the Korean War!

If so, one can see just how long the Soviets have achieved success with electromagnetic biological warfare/medical treatment techniques.

Reportedly, prisoners exposed to the machine were rendered unable to psychologically resist their harsh brainwashing interrogation.

But to return to the brain activity, with its innumerable, zero-summed minute EM vectors, and its extremely rich and complex deterministic substructure.

Note that the ensemble of sum-zeroed vectors forms potentials. These potentials — i.e., the scalar EM — penetrate to the atomic nuclei in the brain and body. Internal changes in the potentials' substructures (i.e., thoughts) also penetrate to the nuclei.

The nuclei continually "charge up" (the particles change their states) to these impressed potentials, including the "potential" or "charge" of each component of the impressed potential. That is, the nuclei charge up with both dynamic overall potential (mind) and thought (individual substructure changes).

Notice that **mind, thought, and memory reside in, and are recorded in, the atomic nuclei. At many virtual state levels. In many hyperdimensions.**

Thus the functioning mind and bio-control systems — including Popp's master cellular communication system, the immune control system, the acquisition control system, and the repair control system - all "reside" in the nuclei as dynamically interacting, patterned potentials or "patterned charge," complete with resonances and frequencies, etc.

We can regard the mind and its interactions as physical, in the extended sense we have briefly developed here.

Everything "mental" can be directly interfaced with and engineered.

One day, for example, "education" will be by direct loading of patterns into the brain/body/cellular biopotentials, much as we now place a diskette in a disk drive and load the computer memory. And then everyone can be educated, in the widest range of skills and to the highest degree ever dreamed of.

Kindling, Life, Mind, and Negentropy

The mass of the atomic nucleus can be charged up with a particular dynamically structured biopotential.

In scalar electromagnetics, I use the term **kindling** to refer to the effect of charging up mass by a specific structured charge pattern to form such a structured potential in the nuclei.

Note that we are actually and physically restructuring the nucleus itself. That is because, if the structure of the potential in the nucleus is changed, local spacetime of the nucleus is polarized in complex electromagnetic structures. The electromagnetic currents, actions, and charges of the affected nucleus adjust automatically to this structure or "grid." *



Figure 77. Internested levels of virtual state vacuum contain mind and thought. **The** vacuum also contains their interaction toward and upon mass.

---

*See Richard E. Prange and Peter Strance, "The semiconducting vacuum," Am. J. **Phy.** 52(1), Jan. 1984, p. 19-21. The vacuum may be regarded as a semiconductor. This semiconductor, particularly in the region close to the nucleus, may be manipulated by subjecting it to external fields, doping, etc. Extra energy density can even be extracted; see H. Paul and R. Fischer, "Comment on How can a particle absorb more than the light incident on it[7]'" Am. J. **Phy. 51(4),** Apr. 1983, p. 327. For the involvement of negative time/negative energy, see C.W. Rietdijk, **"How** do 'virtual' photons and mesons transmit forces between charged particles and nucleons?" **Found. Phy** 7(5-6), June 1977. p. 351-374.


Φ1
Φ2
Hal Crawford © 1981
© 1981 Hal Crawford

Figure 78. The human cerebral cortex is a natural scalar interferometer. It is a virtual state tuner, processor, and transmitter-receiver. It also can produce...and control to some extent...phase conjugate energy and phase conjugate waves.


T
M2
M1
S'''
c2
c1
S''
M2
S
M1
S'

Figure 79. Consciousness and life. These phenomena refer to/constitute a deterministic hyperspatial (virtual state) coupling between mass and an ordered hyperworld.


S^k
S^j
S^n
S
A
C
B
D
1:1
1:1
S'
S''

$A \circlearrowright S^n$ is a living system.
A is the physical body, the incepted mass.
S^n is the mind.

$B \circlearrowright S^j$ is also a living system.

To S, D is inert; i.e., D is not preferentially incepted.

To S, S^k is a "disembodied mind." I.e., S^k is "dead," since it is not preferentially incepting its former body, C.

Whenever a proper retuning body, say E, appears in S, S^k will reestablish a coherent crosstalk with E. This constitutes "reincarnation" of S^k.

Figure 80. Life and death. If the tuning or coupling between the mindworld and the tuned, structured mass body is broken, that is physical "death." Discharge of the structured cellular potentials then produces "death photons." Discharge of the overall, structured biopotential of the body constitutes discharge of the "living spirit."


CONSCIOUS MIND
PERSONAL
UNCONSCIOUS
FAMILY
CITY
STATE
CREED
NATION
RACE
GEOGRAPHICAL AREA
SPECIES
BIOSPHERIC
UNIVERSAL

Figure 81. Layers of unconsciousness intersect hyperspatially.

© Hal Crawford 1979

Figure 82. Scalar electromagnetics can directly interact with the various levels of human mind and personality.


ADDING TO FILE
EXPERIENCE FILES
CONSCIOUS RECALL
NEW FILES
CONSCIOUS RECALL
OLDER FILES
MOOD
TEMPERAMENT
UNCONSCIOUS RECALL
EMOTIONAL TONE
ETC.

Fgure 83. What personality is.


ADDING TO FILE
EXPERIENCE FILES
CONSCIOUS RECALL
NEW FILES
NO CONSCIOUS RECALL
OLDER FILES
MOOD
TEMPERAMENT
UNCONSCIOUS RECALL
EMOTIONAL TONE
ETC.

Figure 84. Jamming the "older files recall" process produces simple amnesia. If the recall process is then restored, the person regains his or her former memories.


UNCONSCIOUS LOOP
EXPERIENCES
DEEP STORE
DEEPER STORE
TEMPORARY PROCESSING
CONSCIOUS LOOP

Figure 85. To sustain one's personality, continual functioning is required. All channels must be functioning.


ADDING TO FILE
EXPERIENCE FILES
NEW FILES
CONSCIOUS RECALL
CONSCIOUS RECALL
OLDER FILES
CHANGED
MOOD
TEMPERAMENT
UNCONSCIOUS RECALL
EMOTIONAL TONE
ETC.

Figure 86. If the files themselves are changed, the personality itself is changed. It is possible to alter who or what a living person is.


CARRIER
CARRIER & MODULATION
CARRIER & MODULATED MODULATION
S′
S″
S‴
EM FIELD
NEUTRINO FIELD
MIND FIELD

Figure 87. The mind and personality can be affected — and changed or controlled from a distance. The Soviets have developed at least a substantial part of this technology.

Table 44. LISITSYN'S REPORT

- **THEORY DEVELOPED & FITTED**
- **HYSTERESIS MEMORY LOOP**
- **CONTROLLED INDUCTION**
    - **IMAGES**
    - **SENSATIONS**
    - **PREDETERMINED EMERGENCE**
- **23 EEG BANDS**
    - **UP TO 8.1 X 10^{20} HZ**
- **11 INDEPENDENT CHANNELS**
- **BRAIN CODE BROKEN**
- **44 DIGITS OR LESS**

Thus by tailoring the specific scalar waveform and wave substructure with which we irradiate a mass, and utilizing phase conjugate (time reversed) waves, we can directly engineer the nucleus itself when sufficient charge structure has been built up in it to form a structured potential that is powerful enough to alter/ **shape** the nuclear processes.

We can, for example, transmute the nucleus into another form. Here an isomer form is the easiest. An isomer for an atomic nucleus (a specific isotope) has the same number of nucleons (protons and neutrons) overall as that isotope does, but a different number of protons. So it's a different element, but very specially related to its isomeric "brother."

All that it takes to change a neutron into a proton or vice versa, **is** to "flip" a single quark (subparticle of the nucleon).

Living systems can do that and transmute elements, to a small degree.

For example, living systems must use phase conjugation, negative time, and negative energy. To do so, they must function nonlinearly. That is the only way they can defeat the otherwise inexorable second law of thermodynamics: that all (linear) processes continue to more and more disorder as time passes. (That's called "increasing the entropy (disorder)." Unless a biosystem could defeat **that** law, its genetic pattern would inevitably be disordered in a few generations, and the species would disappear.

By using phase conjugation and time reversal, the **living system is** able to reverse the law of entropy in its time-**reversed channel.** That is, in that channel things go in reverse: fro***m*** disorder back to order! That's called "negative entropy" or negentropy" for short.*

It follows a priori that, to do this, the living system of necessity possesses phase conjugate energy systems (negative energy, negative lime systems) that are rooted in the atomic nuclei of its body. Further, it must deterministically manipulate these phase conju-

---

To* show how fully one can integrate physics and metaphysics, we point out that, since the vacuum imprints with every **change, nothing *is* ever lost! Death, where is thy sting?

gate systems.

This allows the precise definition of a living or nonliving system. If the system deliberately utilizes and manipulates phase conjugate energy/time in its atomic nuclei, it is a living system. If it does not deliberately use this, it is an inert or nonliving system.

For example, this sheds a great deal of light on the nature of a virus.

A virus is a single molecule. Ordinarily it clouds the distinction between life and death. Viruses can be crystalized out of solution, formed into "rock-like" crystals, and placed on the shelf, so to speak. There they can remain for many years or centuries, seemingly an inert rock. Then when placed back into their "preferred medium," so to speak, the virus crystals dissolve, separate, and "come back to life" and resume their living function. Yet the virus can be killed, in which case it is just a "hunk of rock," sitting on the shelf. In that case, it won't come back to life when placed back into its preferred medium.

In one case its "deterministic phase conjugate energy system" — its mind, to put it simply — remained in the nuclei of the atoms of the crystaline form. In the other case its "mind" was destroyed or disconnected from the crystalline form.*

A somewhat similar effect can be demonstrated in bacteria.

You can "kill" bacteria, for example, with UV radiation, then hold them in the dark for 24 hours (say, for 12 generations, since a nominal bacterial generation is about 2 hours.) They will remain absolutely "lifeless" and static, with no movement or cell division.

Then if you place them in the sunlight, you will be astounded to see them revive by the hundreds of thousands. In the "special kill" case here, the virtual state substructure of the UV photons just totally "jammed" the biopotential substructure functioning of the

---

*In the living case, the atomic nuclei remained patterned by the structured biopotential In the case of true death, the structured biopotential is lost and the nuclei revert to their "inert" form.

"minds" of the bacteria on one key channel. It didn't physically damage their bodies or "physical tuners." Then when placed in the sunlight, the broad frequency spectrum of the virtual substructure of the photons "dithered" and stimulated the bacteria's body-tuners, much like a "frequency massage" in all the bands. This set the physical tuners vibrating — and therefore responding once again to the biopotential substructure changes of the mind. Hence the bacteria "revived" and swam about — fat, dumb, and happy.

We have stated that **the mind is a physical thing, albeit a virtual or hyperspatial thing. In virtual/hyperspatial reality, it is a functioning, hyperspatial thing.** Interchanges be-



©Hal Crawford 1978

Figure 88. The mind and personality are physical things, albeit hyperspatial and virtual.

tween it and an otherwise inert, functional, 4-dimensional ordinary physical system (a "body") comprise life functions, "thought," cellular control, etc. Those interchanges in a living system occur in the biopotentials residing in the atomic nuclei of the physical body, in the higher levels of biopotential in the body structures such as cells, membranes, and organs, and in the overall biopotential of the entire mass of the body.

We accent that this is not mysticism, but physics.

But now let us return to phase conjugation and the Priore machine.

The Priore Machine and Phase Conjugation

In the 1960's and 1970's, in France Antoine Priore built and tested electromagnetic healing machines of startling effectiveness.

In hundreds and hundreds of rigorous tests with laboratory animals, Priore's machine cured a wide variety of the most difficult kinds of terminal, fatal diseases known today.

Funded by the French government in the amount of several million dollars, **Priore's machines concretely demonstrated a nearly 100% cure of all kinds of terminal cancers and leukemias, in thousands of rigorous laboratory tests with animals. These results were shown to medical scientists as early as 1960.**

Many of the experiments and tests were done by prestigious members of the French Academy of Sciences. Robert Courrier, head of the Biology Section and Secretaire Perpetuel, personally introduced Priore's astounding results to the French Academy.

The operation of the Priore machine was seemingly incomprehensible. Many orthodox French scientists — some of them world renowned — were outraged at the success of such a machine, shrilling that science had nothing to do with "black boxes."

They loudly called upon the inventor to explain the mechanism utilized by his machine, but the inventor either wouldn't or couldn't, explain the curative mechanism.

Priore certainly knew how to build the machine and make it work. It is debatable to this day whether anyone — Priore included — actually understood its principle of operation.

Neither the French Academy nor Antoine Priore knew anything of phase conjugation at the time.

In fact, the entire Western World knew nothing of phase conjugation in the 1960's when Priore was getting his finest results. At that time, only the Soviets knew of time-reversed waves.

Certainly Priore's machine was impressive.

Into a tube containing a plasma of mercury and neon gas, a pulsed 9.4 gigahertz wave modulated upon a carrier frequency of 17 megahertz was introduced. These waves were produced by radio emitters and magnetrons in the presence of a 1,000 gauss magnetic field. Experimental animals were exposed to this magnetic field during irradiation, and the mixture of waves (some 17 or so) coming from the plasma tube and modulating and riding the magnetic field passed through the animals' bodies.

Amongst other things, a plasma can convert a transverse wave to a longitudinal wave. Also, phase conjugate (time-reversed) waves



Figure 89. One of Priore's intermediate devices. This device cured terminal cancers and leukemias in thousands of laboratory animals. (Courtesy Bob Whitney)

can be produced by plasmas. Priore's apparatus produced a scalar EM wave/signal with deliberately constructed, infolded components including phase conjugate waves.

One may roughly view a cancer cell as a normal human cell gone "awry" and out of control of the body's master cellular control system. The cancerous cells, viewed as a sort of separate, parasitic group of cells, form a special kind of organism having its own master cellular control system "level," immersed in the host's biopotential.*

There is thus a specific, constant electromagnetic "delta" that differentiates the parasitic cancerous "organism" **from the normal human cellular organism.**

This "delta" can be considered a sort of constant, complex-structured charge existing in the body's atomic nuclei. It's exactly as if the body biopotential had been charged up by Kaznacheyev's "death photons" for that specific cancer condition.

If this cancerous "delta" (which may be rather like a complex intermodulation mix of waves) — or a frequency shifted "transform" of it to a different frequency band — is phase conjugated, a specific healing delta frequency pattern results.

If phase conjugate replicas of a cancer's cell's specific "delta" frequencies are fed into the body having that cancer, the deviation of the cancer cell's master cellular control system will be "time-reversed."

That will return the cancer cell to control of the animal's proper master cellular control system. The cancerous cell will be immediately destroyed, or reverted back to a normal cell of the animal.

A very similar process exists for just about every disease bacterium and infectious agent that attacks the body.

Phase Conjugates of "Death Photons" are "Healing Photons"

The Kaznacheyev experiments in the Soviet Union proved that, any cellular death and disease pattern can be induced by a specific electromagnetic pattern carried on an electromagnetic signal, if the target cells are bombarded with the pattern-carrying carrier signals for a length of time.What was not published of Kaznacheyev's work was the correspondent work showing electromagnetic reversal of cellular death and disease conditions by irradiating the diseased cell cultures by phase conjugate replicas of the pattern-carrying induction signal.

---

*One strongly points out the relevance of Dr. Robert Becker's epochal experiments proving that cells can be dedifferentiated and redifferentiated electrically. Those experiments are strong indicators that the cancer cell should be capable of being reverted to its more primitive state — that of the normal cell — by electromagnetic means.

In simplified terms, if an action in forward time induces a condition, then the time-reversal of that action will reverse the condition.

The concept is almost laughably simple. **The time-reversal of an electromagnetic disease process is a specific healing process for that disease.**

In his device, Priore internally structured the carrier photons themselves — making them **vacuum engines.** He phase conjugated his vacuum engines, and then passed these time-reversed vacuum engines down and through a strong magnetic field which thoroughly penetrated all cells of the biological organism being treated.

The scalar components (structured photons) representing the time-reversal of the disease were absorbed and reradiated in all the cells, "charging up" the nuclei of the atoms in the organism to some potential level of the exact "healing and reversing pattern."

In the process, the cancer/leukemia pattern/charge also destroyed the cancer cells, or converted them back to normal cells as appropriate.

As a highly simplified analogy, the complex signal — viewed as a scalar Fourier expansion — represented a "stress" against any abnormal cellular control system encountered and returned it to the normal cell's master cellular control system of the body.

Encountering the normal control system in normal cells, it produced zero stress.

Encountering the abnormal control system in tumerous cells, it produced great stress on it, reverting it to the normal control system of the body's normal cells.

Thus to a normal cell the Priore signal pattern acted somewhat as a comb passing through one's hair.

No interference occurred with the normal cell (one whose scalar control pattern is phase-locked to the body's master cellular control system and in phase with it).

The Priore signal stimulated and "stroked" the normal cell, but did not hurt it at all.

On the other hand, the scalar control pattern in and of an abnormal (cancerous) cell is out of phase with the body's master cellular control system, and is not phase-locked to it.

Hence the Priore signal caused direct interference with the abnormal cell's independent scalar control system. The interference pattern constituted the reconstruction of normal energy directly in the cancerous cell, and also jammed its abnormal scalar life signal.

This destroyed the cancerous cell by two mechanisms: (1) physical energy was kindled directly in the abnormal cell, causing direct mechanical damage, and (2) the cancerous cell, being an "independent living critter," had its scalar life channel (connecting its primitive "mind" to its "body") jammed and stopped.

If the cancerous cell was reverted to a normal cell by the Priore stress before being destroyed, it became just a normal cell and the Priore stress had no further effect upon it.

The Effect is Universally Applicable

Any disease with cellular, biochemical, or genetic basis can be cured in like fashion.

Priore's method, for example, was clearly shown to be able to completely reverse clogging of the arteries with fatty deposits, and to be able to lower the cholesterol level to normal, even in the presence of an abnormally high cholesterol diet.

His method also showed complete mastery and cure of sleeping sickness and trypanosome-induced illnesses.

Often Priore found that every cell of the body — even the hair — must be irradiated and treated ("charged up") with the signal, for the disease pattern was in every cell. The master cellular control system is holographic — the pattern (substructured potential with its dynamic, oscillating components) is in each component (each atomic nucleus, hence in each cell.)

Every structural level of the body larger than the cell also has its own correlated pattern, or modulation, on the overall.

A biological organism can regenerate lost limbs, for example, if it can utilize its natural recovery process in a Priore manner.

Even though Priore's work was presented to the French Academy of Sciences by Robert Courrier, the prestigious head of the Biology Section, the Academy could not understand the device and its functioning.

That was because the Academicians knew nothing of scalar electromagnetics, and phase conjugation, and the Priore machine was a scalar electromagnetic device using phase conjugation.

In the Mid-70's It Ended

In 1974, a change of local government lost Priore his government supporters. His support and funding were lost.

Ironically, Priore was just completing a 4-stories-tall apparatus capable of radiating and treating entire human bodies. It would have been capable of curing cancer and leukemia in humans rather than just in laboratory rats. (His previous machines were much



Figure 90. The large, special, phase conjugating plasma tube for Priore's giant device. The final machine would have treated humans "whole-body." (Courtesy Bob Whitney)



Courtesy Bob Whitney

Figure 91. Capping assembly for the top of Priore's giant plasma tube device. The last device would have treated human patients "whole-body." The cap assembly was on the third floor of the device.

smaller, and only a small animal could be irradiated whole-body.)

In that machine Priore used a "lamp," a special section, in which 17 specific frequencies were mixed and modulated upon the 9.4 gigahertz carrier.

The machine was large enough to irradiate humans over their whole body. **It should have been capable of curing cancer and leukemia in** two **five-minute irradiations, one week apart.**

While Priore was still alive, with my associates I spent nearly two years of my life in an effort to bring the Priore device to market and into the mainstream of medical research and development.

Robert Whitney, Frank Golden, and Tony Gideon played the major role, going to France and negotiating directly with the Priore group and the French government.

Verbal agreements with both the Priore group and with the French government were obtained. The machines were to be built, assembled, and tested in Bordeaux. Then they were to be dismantled and shipped to the purchasers — large medical research and development laboratories where they would be reassembled on site.

A group of wealthy backers was going to provide the necessary millions to fund the effort. Final contracts were being drawn.

Mysteriously, all funding for the project was suddenly withdrawn. Our backers were "leaned on" very hard and strongly threatened. Nothing we could do could revive the project.

Priore never again recovered his funding, and later died. The machine fell into disarray and was disassembled.

However, the proof that the requisite time-reversed signal can be produced, and will ride down a magnetic field, to penetrate every cell and every atomic nucleus in the body, is already in the present hard-core physics literature, if one knows where to look and how to properly interpret the work.

The fact that such signals can reverse nearly every major cellular illness condition of the body also has been proven by Priore and the scientists who worked with him, and it is in the French scientific literature.

The Priore-type cure for AIDS and other diseases only requires the necessary funding and personnel to be redeveloped and reestablished.

Work of Australians Reed and Barsamian, and the American G. Wilbanks

At the University of Sydney, Department of Obstetrics and Gynaecology, some magnificent work of great importance to our thesis has been accomplished. Indeed, this Australian research may well be some of the most important work going on in the Western world today.

Dr. B. L. Reid, Dr. S. Barsamian, and their colleagues have produced experimental studies that positively verify pattern and form transmission at a distance, even through Faraday shielding. They have directly shown the reaction to, and results of, an unexplored information field on both living cells and inert crystalline matter.

In addition, they have replicated — and extended — the published results of Kaznacheyev on the cytopathogenic effect. In fact, they have obtained the effect at over 100 meters.

This shows, of course, that the effect is not just mesoscopic, but also macroscopic. Whether we like it or not, structural patterns of cellular disease can positively be transmitted electromagnetically, and kindled in target cell structures at a distance.

Dr. Reid has been interested in the origins of cancer since at least 1958. After much work in the standard models, by the late 1970's he was convinced that the present approach of medical science is wrong. He reasoned that we should pay stricter attention to the nature of growth before examining new growth, i.e., cancer. Growth, of course, is creation — and so the problem became, what is creation?

As a metaphor for biological growth to work with, he and his colleagues chose the growth of crystals. With keen foresight and intuition, they directed their inquiry so as to expose the complicity of some force — if any — external to solute and solvent.

Their work began to show that such a force existed, and it was a type that was unaffected by interposition of a Faraday cage. In other words, *it was not a conventional electrical force.**

Dr. Reid and his colleagues then included biological subjects in the form of living cells. They were familiar with Kaznacheyev's work in Alma Ata, Kazakstan on the subject of long range transmission of pathological (viral) effects on cells. In addition, they were familiar with the seminal studies of Gurwitsch on transmissions by onion roots cells, in the 1920's.

Most of their basic studies on the nature of the new force, however, were made with common salt, drying from aqueous solution, Some of their major results were as follows:

1. The familiar cubic symmetry is altered toward a higher energy form of dendrite crystals when biopolymers such as protein are included in the solvent.
2. A mass of lead 12-20 kg in the crystal space (up to 1 meter distant) causes an interference pattern in the salt crystal display.
3. A prospective dendrite pattern is not realized when a prospective cubic-pattern of the salt is dried in the local space (up to

---

"For one related possible scalar EM (electrogravitation) interaction, see Ya. B. Zel'dovich, "Electromagnetic current and charge due to interaction between a gravitational and a free electromagnetic field," **J. Exper. and Elec. Phy.** (Soviet translation), 16(7), Oct. 5, 1972, p. 302-303, 1 meter). The latter by its presence in space is able to prevent the dendrite expression and enhance the cubic symmetry expression. **A photograph of crystals of cubic symmetry when moved by a vibrating holder (2 cps) has the same effect on the real crystals drying from the solvent.**

4. Dendrite forms of salt crystal result when certain chemical reactions involving proton or ion movement occur up to 30 meters away, separated by brick walls, glass, etc. These reactions were detailed by Dr. Reid and his colleagues. If the mother solution is examined by ac capacitance on a sensitive bridge, variations in capacitance of over 300% accompany the receipt of the signal.

5. If such a transmission from 30 meters distance is regarded as a carrier wave which is modulated by a foreign — and thus detectable — chemical, **the chemical can be detected in the distant atmosphere some 3 months later in the form of a discrete or adiabatic 'cloud' which contaminates sodium chloride drying at the same time.** In this way, copper sulfate dissolved at a site A in June 1985 could be repeatably detected at site B, 30 meters distant and separated by walls, screens etc., by a drying solution of sodium chloride solution in September 1985. Serial dryings of the sodium chloride solution on glass slides showed that each day, the cloud hovered over a space of 1-2 cm at the end of a venturi tube for several hours before 3 p.m., and then moved off at 1 meter per hour in a NW direction. The copper content of the cloud was discernible by crystal structure and chemical means from the adjacent sodium chloride.

6. All of the above crystal forms required ambient oxygen for their manifestation. Atmospheres of nitrogen and argon prevented their display. At the time, the researchers suspected that the effects may have been carried by orbital electrons of oxygen showing unpaired spin which had interchanged with electrons of the copper solution. They then

developed an information-carrying device which could 'infect' the electron cloud of a target molecule sufficient for the chemical display of properties of the infecting electron's parent atom. This concept seemed to explain the experiment of the following paragraph.

7. Two beakers of sodium chloride solution were connected in series with a small voltage source (say a 1.5V dry cell) to provide a transfer of electrons through each beaker. The second beaker in series was sampled for subsequent drying and display of the crystal form. A crystal form of cubic symmetry resulted. When the solvent of the first beaker was altered by the addition of a protein solution (such as albumen or globulin), the crystal pattern of the second beaker was altered from cubic to dendrite pattern as though protein were present in the second solution.

8. During attempts to stabilize salt crystals on glass by means of thin plastic films drying from appropriate solvents (in order to stain the salt with aqueous solutions of dyestuff), it was discovered by chance that the crystalizing process is accompanied by structural patterns on the plastic film so exposed. These patterns were of two major types: (a) vortices, or spirals in the film plane, of 0.1 to 1.0 mm diameter, and (b) smaller curled structures into which the spiral could be seen to merge or grade. From a concurrent mathematical study of vorticeal interaction as designed by Barsamian, the similarity of the curl structures in plastic films (the researchers usually used 0.25% polystyrene in benzol) to computer simulations of vorticeal vectors was shown to be remarkable.

9. The researchers then dispensed with the underlying crystals and exposed the drying polymer film to a variety of spaces where the field, thought to be responsible for many of these tele-effects, was operative. With this technical advance, the team has made rapid progress over the last year or so. They have come to have a more comprehensive grasp of the ether

field than was possible by less direct methods involving formation of crystals.

10. On the biological side, they repeated the Russian studies done at Alma Ata with transmission of the cytopathogenic effect of viruses on animal cells. They used the cytopathogenic effect of colchicine and its relative vinblastine on cells with the following differences from the published Russian work: (a) The effect can be transmitted at least 100 meters between campus buildings, (b) it is not necessary to use a magnetic field for the propagation, (c) it is not necessary to use quartz vessels; glass is quite effective. These experiments came to the attention of a colleague, Dr. G. Wilbanks, Head, Department of Obstetrics and Gynaecology, Medical School, University of Chicago in 1983. Dr. Wilbanks was able to repeat them with similar results. However, in a more faithful copy of the Russian experiments, he used quartz vessels with cells placed in a magnetic field, with the vessels separated by no more than 1 mm. Both the Australian researchers and Dr. Wilbanks shared another thing in common: their uniform inability to interest the editors of several scientific journals such as **Science, Nature, Naturewissenchaften,** and others in publishing papers describing these fundamental experiments and results.

11. Experience with interference of a lead mass in the crystal work prompted the use of several metals in the ambient field of growing cells. Only lead (and to a lesser extent tin) showed the following properties: (a) Cell growth with 0.5-5 Kg lead in the ambient field is depressed sometimes to one third normal, (b) The cells die (dye exclusion test) but then can be revived by placing a small bar magnet in the local space with its poles in an E-W orientation. At least in Sydney, a N-S orientation of the bar magnet does not revive the stricken cells.

12. The effects of energy flowing through living matter have been documented by Kirlian's method. It was therefore of interest

to the Australian researchers to expose living systems to drying films of polystyrene. They found that the staining properties of the ambient-derived image on plastic films parallel those of the real organism.

13. By appropriate use of an imposed potential on living cells, it proved possible to match the field strength and show the actual imposition of the ambient (scalar) field on the biopolymer content of the material during the permeation process. The traces obtained are not unlike noise and would be so regarded by the casual investigator. The design of this apparatus and associated experiments was the work of Dr. Barsamian.

Concepts of Dr. Reid and Associates

Dr. Reid has kindly shared with me some of the concepts he and his colleagues have formulated. These concepts, it is stressed, are consonant with direct physical results they have obtained in the laboratory.

Note that any errors in this explanation are strictly the fault of this author, and not of Dr. Reid and his colleagues.

1. Matter is bathed in an energy sea familiar to quantum theorists. The Australian team prefers to call this sea of energy **ether,** as a relatively bland term, perhaps in a way to rescue it from the oblivion where Einstein banished it. The key to the silence of this sea is its "fractional-charge" charged particle status and low energy values. The former conceals it from physics, while the latter conceals it from chemistry and thermodynamics.

2. The differing energy levels of this sea, combined with its enduring motion, are theoretically and practically best expressed as a **vortex.** Dr. Reid and associates have detailed this theory to explain the creativity of biology. The incipient creativity of the vortex is given material expression by its association (as part of the EM field) with an electron which it

now endows with equivalent novel properties. There is no intuitive reason why the energetic rearrangements of the electron cloud cannot proceed to the nucleus, there to set up a quark or proton rearrangement — or, as the quantum theorist would say, a virtual particle exchange — leading to transmutation. Kervran's work on biological transmutations is relevant; the literature of such effects goes back to 1798 at least! The team suspects that some such mechanism may underlie their experimental result of the transition of sodium to copper.

3. **A further prime property of vorticeal interaction is its proclivity for amplification,** wherein the atomic-size vortex can be built up to the meteorological hurricane by such adherence or affinity. The team has noted the affinity of ambient field vortices to those produced by an electric current in a metallic conductor, with particular reference to the ill-defined boundary between the two. This parasitism was the reason behind the team's use of "carrier waves" from chemical reactions as transporters of fields whose identity of origin were sufficiently specific to trace the field subsequently. It is at least conceivable that the whole process could be amplified and used to parasitize (modulate) a radar beam as carrier. The affinity property of fields may be exhibited by the experience of mariners with what they loosely term "magnetic phenomena" thought to be derived from luminescent plankton. In the South China and Arabian Gulf seas, giant "wheels" of light, 5-15 km in diameter and containing spiraling spokes, revolve about the ship at night, reversing their direction of rotation as they pass the midpoint of the vessel. The key observation in the context of the field affinity concept is that the luminescence is manifoldly enhanced when the ship's radar is switched on. There could thus exist a chain, scalar-EM/plankton-optical, the first leg (scalar EM) of which can be amplified by radar EM.

4. The property of affinity means that **a scalar field's** transform **or copy, of the energy disposition imposed on it by the experience of matter last permeated, may persist as**

> **a** memory **in space,** as many of the Australian observations attest. The team found that recall was not all that difficult technically. **The energy transform for copper** sulfate **existing as a non-dissipated cloud with marked adiabatic properties could be recalled five months after its formation. There is no reason why informationally more elaborate spatial configurations of energy, including human thoughts, will not behave in precisely the same way.** The cell nucleus could conceivably be the candidate for the first site for storage of such energy. The nucleus has a highly ordered structure and an associated high permittivity, and this would make it a real target. In the human subject, there is experimental evidence that the mongoloid polymer constitution will have a higher activity for storage of the ambient field than will the Caucasian.

Other Important Ideas

Dr. Reid also shared other important insights:

Lavoisier in 1748 advanced the concept that matter itself (chemicals) is inert. The activity of all chemicals, according to Lavoisier, resided in their associated ether — and God sent the ether!

Taken to its limit, this suggests that the source of the energy which we call *thought* is a property of the scalar field. Matter (say, the nervous system) interacting with these fields, would be incapable of discerning the source of the field as presented, whether of self or external origin.

In his book **Hidden Variables in Quantum Theory,** Dr. David Bohm felt that in 'elevating' (his word) matter (as particles) from the sea, it might be possible to consider the idea as containing even more elaborate energy transforms such as biological shapes, these transforms themselves undergoing metamorphosis. [Comment by this author: Rife's microscope, using evanescent waves, actually allowed one to directly see and photograph such forms, proving the thesis.]

The ability of the Australian researchers to rescue these transforms on films together with evidence that they could be seeing the results of the exclusively space interaction of virtual forms (say microbe and antibiotic), is also a direct technical step toward validating Bohm's important idea.

Wider Implications of Structured Field Information

As T.D. Lee points out in his important book, **Particle Physics and Introduction to Field Theory,** particle physicists have not attempted to use the structure of the vacuum nor the structure of potentials.

Dr. Barsamian has shared other wider implications of the structured ether.

Over the ages a phenomenon which, as discussed, can have no representation in real (that is, electromagnetic or thermodynamic) terms can hardly have been thought of as possessing specific structure or function. Instead, it signaled its undoubted presence to generations of philosophers and physicists before Einstein, solely through statistical effects.

The writings of Helmholtz, James Clerk Maxwell, and Neils Bohr are examples. The more recent Dirac and Fermi statistics are **a** continuation of the process.

If an alternative definition of science is the continuing refinement of that which we partially knew or took for granted, then the refinement of these statistical approaches ~ with their obligatory uncertainty as defined by Heisenberg — is a worthy goal.

In this sense, a more articulate description of the anatomy of the field is a logical progression from the beginnings of the ether concept in Classical Greece through to the statistics of the nineteenth to the early twentieth century.

A hundred years ago, this orderly progression even reached the concept of a vorticeal atom at the hands of J. J. Thompson. However, **it** was interrupted very effectively by Einstein's publication of the special theory of relativity.

Einstein was fortunate in that he had chosen for his mathematics a pivotal feature of the ether field, its elasticity. The mathematics of elasticity had been evolving — through the developments of Hooke, Young, invariance, and the calculus — to handle its historically increasing complexity (by tensors). This mathematics of elasticity was then available to Einstein. The wisdom of this choice was vindicated by the remarkable special relativity predictions which were born out in subsequent observation and experiment.

There was seemingly no need to suspect, let alone probe, any special properties of the medium underlying the mathematics.*

The success of these predictions effectively blocked any chance of a return to the ether field concept. Indeed, it was seen as an arrogance to despoil the "elegance" of the mathematics. Nor was the success of quantum mechanics — the other leg of the Western World statistical approach to the nature of reality — able to get the physicists to heed Bohm's 1958 ideas on the hidden variables in its fabric or Dirac's 1952 ideas on a lesser uncertainty of the particle-field relationship than Heisenberg had formulated.

Recently Dr. Barsamian has originated the concept of an **alienation of the electron from its field.** The full expression of this could see the field so alienated that it is well-nigh autonomous, and some kind of fundamental entity in its own right.

In this sense, the freed autonomous field — at least conceptually — could proceed with its creativity by hybridization with other fields and so return the product of these asides to the particle. In atoms of the next fragment of matter with which the particle then associates, this product could create novel properties derived from the interchange.

The multiple properties of such a field allow it to be resolved in EM (electrostatics and electrodynamics), in atomic structure (electrons and nucleons), and in pressure (gravity) terms. This universality makes a new concept possible, long beloved of the GUT (Grand Unified Theory) theorists: that there is only one energy.

It is also quite possible that this ubiquity need not be confined to physics. It may penetrate the biological imponderables of growth, new growth and consciousness.

In view of the work of Dr. Reid and his associates, and other work — such as that of Hines and Chimonas showing atmospheric gravity waves launched by auroral currents — the prospect of amplification and transmission of transforms and patterns over long distances,

---

*As, for example, whether or not the concept of an abstract vector space in vector mathematics must be modified to correspond to what we know about the vacuum medium. If the vectors are to correspond to the movements of physical things in the *vacuum medium,* then the vector medium must correspond to the vacuum.

through affinity with long distance carriers, is indicated.

Dr. Reid stated that it would be surprising if other laboratories outside Russia had not progressed as far, if not further, than he and his associates had. Obviously the lack of similar publication indicates the nearly impenetrable editorial curtain confronting Western researchers in this and related areas.

Dr. Barsamian's Important Theoretical Insights

Dr. Barsamian has formulated a theory in relation to the development of cancer that is of great importance.

In his theory, he is developing the approach of classical mechanics to electromagnetic interactions between charged particles and between dipoles. The field associated with the primary moving particle is not neglected in his theory, and this part of it differs from Dirac's "new electromagnetic theory."

The field associated with the primary moving particle, in Dr. Barsamian's approach, is viewed as an important part of the particle's interactions. This field is stressed in the sense that diverse phenomena — from Maxwell's EM field radiating from the remotest regions of the universe to the controlled charge flow in the matter medium — are viewed as manifestations of EM forces.

This of course is unlike the traditional relativity view of EM force action on moving charges.

In Dr. Barsamian's view, the potential vectors (derived by a reatment from fluid mechanics theory) form an EM field and are positioned on a vortex curve. All parameters of such a field can be treated mathematically, and Dr. Barsamian has one or more papers presently in publication.

The duality of such potential vectors (gradients) is to conduct the motion of particles (which are always either charged or dipolar) appearing in nonmatter, which is taken as an incompressible continuum — the "void." Because the final results of these forces are always movement of matter, Dr. Barsamian prefers not to classify them by their origin.

Such a field may persist with great permanence. There are some limitations in summation (triplet conditions) and selectivity (periodicity) of the vortices themselves. Part of these limitations takes the form of particle characteristics. Presently he is rather sure that the formation of patterns of organic, inorganic and liquid crystals (typical to living biomatter) are partially responsive to the effect of the described field.

Dr. Barsamian is attempting to synthesize his own experimental findings on the dielectric behavior of biosystems as they enter the cancer process with the data that Dr. Reid is producing with respect to action at a distance.

With respect to living systems, he has slowly been approaching the conclusion that existing physical laws are just not applicable concerning (1) entropy, or (2) energy breakdown, or (3) random collisions of particles in quantum terms, or (4) electron-ion exchanges in bioelectrochemistry terms.

Under such circumstances, it is difficult to find a referee who sincerely understands the related experiments and their underlying theory. This presents a nearly impenetrable barrier to publication in leading scientific journals.

This is tragic, because these considerations and experimental results at least provide an entry into more fundamental experiments with present lethal diseases such as cancer and AIDS which annually take large numbers of human lives.

The present state of the art is telling everyone loud and clear that something fundamental is wrong with present theory, and that we should come to terms with more novel views.

Comment by the present author: In his prophetic insights, Dr. Barsamian has placed his finger squarely on the fundamental struggle of living systems against the "positive energy/time" laws of present physics. In its struggle, the living system must use negative energy/time, to correct from disorder to order and provide the extra free energy to do so. Otherwise, the steady progress toward increasing disorder in all its actions, would very shortly reduce the living system to such a disordered state that it could no longer reproduce the clear genetic pattern of its own kind. We have already pointed out the hitherto unexpected role that phase conjugation plays in allowing the living system to violate and break the iron dictates **of** conservation, nontransmutation, entropy, and raw statistics.

To live and survive, a living system must have access to other functional levels and other mechanisms beyond those contained in our present physics, electromagnetics, and biochemistry.

The incredibly productive and important work of Drs. Reid, Barsamian, and associates is of the utmost importance. Their work clearly moves everything in biochemistry and the knowledge of cellular functioning a major step forward.

It is a betrayal of the scientific method that such vital work goes so largely unreported in the leading journals. Indeed, the work of these Australian scientists should be galvanized and well-staffed and funded. They can literally usher in a new science, given the chance to further exploit and develop their results.

Royal Raymond Rife

In the 1930's and 1940's, Royal Raymond Rife revolutionized everything that has been done before or since in high resolution optical microscopy.

He also revolutionized everything before or since in cellular biology. He carried cellular structure far beyond anything ever dreamed of at the time or presently. He revealed the direct connection between organized living energy forms and organized biological systems. He revealed that life itself is organized and dynamic, to a far finer level than anything in the textbooks today. **He revealed that our present theory of disease is fundamentally very, very wrong.**

He produced direct, economical, electromagnetic cures of cancer, leukemia, and other such debilitating diseases. His work presages a future mankind could have had, where most debilitating diseases were quickly and economically corrected, and where no poisonous drugs, violent nuclear irradiation, and harsh chemotherapeutic "burning" of the patient would be necessary.

For such epochal work, he was ostracized, essentially imprisoned in a medical treatment facility, broken, condemned, and rejected by his peers. His findings, though printed in reputable publications and journals, were discredited and ridiculed.

He literally was reduced to a non-person by the power of the medical cartel.

Finally escaping from his enforced confinement, he lived out his remaining years and died quietly and unknown.

Rife's Universal Microscope

With his universal microscope, Rife achieved optical resolution of up to 31,000 diameters and magnification up to 60,000 diameters. His microscope could examine living viruses, living bacteria, and other as-yet-undiscovered living organisms and living energy forms that no other microscope before or since could see.

Even today, only the electron microscope furnishes such resolution, and it zaps-to-death the objects that are being examined. Further, it will not at all detect or see the "living energy forms" revealed by Rife's microscope.

To appreciate Rife's accomplishment, let's briefly summarize some of the performance factors of an optical microscope.*

Several factors are important in the functioning of a microscope: Resolution, magnification, and contrast lead the list.

By **resolution** we refer to the ability of the instrument to distinguish a small object. In other words, something like looking at a medical doctor's eye chart, and specifying the smallest print one can clearly see. Resolution is often referred to as resolving power.

By "magnification" or **magnifying power** we mean the ability of the instrument to "blow up" or enlarge the image produced. Roughly, it's the ratio of the apparent size of the object seen through the microscope to the apparent size of the same object seen without the instrument.

Magnifying power is exactly like enlarging a photograph. It won't improve the resolution or make the photograph any clearer, but may make whatever was captured (resolved) easier for the human operator to see. If you just keep enlarging the photograph, it will get more and more grainy, until no further details can be seen with higher magnification.

Contrast refers to the distinctness by which the various parts of the object can be distinguished from one another. To enhance contrast of objects under the microscope, staining of the objects is often used. Very often the act of staining will itself kill the living organisms — such as bacteria — that are being examined.

---

*The electron microscope reveals only the "dead carnage" of the battlefield after everything is destroyed. With it, one is observing physical residuals, not the living players. For some encouraging modern work, however, see Michael Hercher, "Virometer — an instrument for the measurement of the size of viruses using an optical microscope," **SPIE Seminar Proc.**, 1977, p. 17-22.

Figure 92. Royal Raymond Rife in his laboratory. Courtesy Christopher Bird



Figure 93. Rife's first virus **microscope.** Courtesy Christopher Bird



Figure 94. Side view of Royal R. Rife's prismatic universal microscope. Largest and most powerful of five Rife microscopes With it, living filterable viruses could be observed. Courtesy Christopher Bird.



Figure 95. Front view of Royal R. Rife's prismatic universal microscope. Built in 1933 in Rife's San Diego, California laboratory. Courtesy Chris Bird.

We may state the resolution of an optical microscope in terms of the diameter of the smallest object resolved: for example, so many nanometers. Or we may just simply and loosely speak of so many thousands of diameters.

The resolution of an optical microscope depends upon the illumination conditions, its optical system, and the fact that the object viewed diffracts and spreads the light. A wide variety of mechanisms for illuminating, resolving, contrasting, etc. are used in optical microscopes.

According to standard Rayleigh theory, normal optical microscopes are limited in resolution to about half a wavelength. That corresponds to about 250 nanometers for visible light illumination. One can do a little better than that by using ultraviolet light and quartz optics. The UV has a higher frequency than visible light and hence a shorter wavelength. However, beyond 240 nanometers the resolution of an optical microscope quickly disappears.

A few researchers — notably in the 30's and 40's — remarked about other factors, such as "quality of the lenses," affecting resolution. Some of them reported results to about a tenth of a wavelength. Loosely, that translated to somewhere in the order of 5,000 to 6,000 diameters. The dependable upper limit seemed to be — and still is — about 3,000 diameters, however.

Normal optical microscopes simply are almost useless for trying to look at viruses. They will not resolve any but the very largest viruses, and will not resolve the internal features of even those few giants.

Much of today's knowledge of virus structures and shapes comes from the use of electron microscopes. They bombard the object viewed with a fierce rain of energetic electrons. These instruments see nothing of the *functioning* of the virus, for they kill it instantly in trying to view it.

With Rife's universal microscope, the dynamic living functions of the virus could be observed without killing it.

With Rife's microscope, a whole range of complex organisms and structures below the size of bacteria was revealed. Many of these organisms are still not known to present science, even though some of them were written about at the time. Filterable forms of bacteria

— forms which readily passed through filters supposed to easily block their passage — were discovered and reported by Rife and his medical colleagues.

In addition, Rife's microscope — which contained block-quartz prisms and lenses and interference stages — revealed halos around living organisms that other microscopes could not see, even though the object was within their resolving power. Further, it revealed the existence of entire organisms and forms which other microscopes could not see — even though, again, the size of the organisms was within their resolving power.

In other words, Rife's microscope not only revealed smaller physical forms than any other microscope could see, but it also revealed sizeable "living energy" forms which no other microscope could see.

Rife Proved That Everything Is Alive

The degree of smallness to which Rife's microscope would resolve, and the extraordinary energy forms it could detect, showed that direct detection of the virtual state organization of the living organism was accomplished by the instrument.

The science of the day was only just groping its way toward any sort of physics that could explain such an astounding instrumental result. Today, however, in the hard-core literature there is demonstrated proof that the optical limit of resolution can be drastically overcome, using evanescent waves.*

Shortly we will briefly give an "ad hoc" explanation of such evanescent waves.

Electromagnetism has been shown by Kaluza-Klein theory to actually exist in the fifth dimension. In other words, EM itself is hyperdimensional. It flows in the fifth dimension, which is "wrapped around" each point in our ordinary space. It is — to the first approximation — the external environment of every normal point in

*E.g., see T. Sato et al, "Application of evanescent waves to microscopic observation," **Bull. Tokyo Inst. Technol.** (Japan), No. 125, 1974. p. 35-41. See also G.A. Massey, "Microscopy and pattern generation with scanned evanescent waves," **Appl. Opt.** (Poland), 13(3), 1983, p. 247-255.

our 3-space.

Let's say that again.

The electromagnetics "medium" itself is totally external to each point in our space. Each of our points is surrounded in higher space by the electromagnetic medium.

We live inside a totally electromagnetic medium. It's not just an "electromagnetic environment" in our own space; instead, it's an electromagnetic environment in hyperspace.

Everything already is just the internal structure of the electromagnetic medium!

That's what the "vacuum" is.
That's what "spacetime" is.
That's what the "virtual state" is.
That's what physical matter is.

And it's all alive. Totally and completely alive. Everything is alive. There is nothing but life. The electromagnetic medium is alive.

Except within a locally-organized biopotential area, it's just "equally alive in all directions." So it appears inert, where by "inert" *we mean not singly preferential.*

Every biopotential change, at any level in a biopotential, extends "decaying-expotential-wise" to infinity, by standard theory. Part of that potential change exists at every point in the entire spatial universe. And there at that point, so do the biopotential changes for every other biosystem in the universe.

Everything's alive. There is nothing but life. Anywhere. Anytime.

An interchange between this "living, surrounding electromagnetic medium" and each particle of mass in our 3-space continually occurs. This exchange involves the so-called virtual particle flux.

If we model higher dimensions, such as are necessary to include the "particle zoo" discovered by modern particle physics, each of these "higher dimensions" corresponds to a "successively deeper-"

internested level of virtual particle flux—of the vacuum, or of this electromagnetic medium that surrounds us.

The living system orders, structures, and dynamically functions and interchanges electromagnetically throughout many higher "dimensions" — throughout many such internested levels of virtual-state/vacuum/spacetime.

Except for the first layer of virtual state (the 5th dimension in Kaluza-Klein theory), gross (classical) electromagnetic theory totally ignores the infolded, ordered deeper structure of electromagnetism (of the EM medium).

Using such gross electromagnetics, orthodox science thus can only detect and grasp the gross results of the living organism's functioning. Further, it can only detect and grasp those gross results that actually move 3-space matter — observable particles.

So it only detects the grossest interchanges between "mind" or "life" and matter. Specifically, it only detects the final results of that interchange—the gross movement of material particles themselves.

The first hypernumber — "i," the square root of minus 1 — is used to model another dimension at right angles to our normal three. An electromagnetic wave thus is modeled to have two parts: the first is the part that affects or moves a material particle, and that's called the "real" part or "observable" part. The second part of the EM wave is the component that lies in this "imaginary" (unfortunate standard term!) dimension. That imaginary part does not of itself move charged particles, so it is considered to be "something other than real."

Note that what's really done in this sort of orthodox modeling is to define observation as the movement of observable charged particles.

The human "conscious mind" is a functioning part of the overall human mind that has been specifically fitted to function almost totally with our gross bodily detection of the photon interaction.

We thus consciously detect and "are aware of only the first level of reality: the interface between the first layer of virtual-state/vacuum/spacetime/ and the 3-space of observable particles of mass.

Since the physicist must be "conscious" of his observation or instrumental detection, the detection process ultimately has to have a final stage that produces a photoelectric interaction with his body — for that is all the conscious mind detects and processes.

Everything chemical, electrical, etc. — according to quantum mechanics — will involve at its root level only the photoelectric effect.

Rife's Microscope Used Evanescent Waves

However, it is certainly possible to build an instrument which is multi-staged, and one in which higher stages interact primarily with deeper internested levels of vacuum virtual state. That is, an instrument that interacts with higher dimensional phenomena. That is, one that interacts with deeper internested levels of electromagnetics. If these stages interact causally in a vertical manner, then the final interaction with the human body and nervous system can still be "normal electromagnetics" and yet indicate a higher dimensional phenomenon, event, or function.

That is precisely what Rife did: His universal microscope penetrated to a much finer level of reality because its multiple stages used **evanescent waves.**

Here's what we mean by that.

An electromagnetic wave consists of a "real" part and an "imaginary" part, as we have discussed. It's possible, however, to have the real part become zero, and still have the "imaginary" part remain and dynamically vary.

This sort of wave — containing only the "imaginary" part — is said to be one type of **complex wave,** or an **evanescent wave.**

In advanced EM waveguide and optical theory, such evanescent waves can function to guide or determine the real parts of the EM waves. That "real part" is the part that is then going to interact with electrons and move them, and give us a "detection."

In other words, the "real" part of the EM wave will be moved and guided by the "higher dimensional" or evanescent part, or even by separated evenescent parts — pure evanescent waves.

So one can build a device or instrument that utilizes such an effect to reveal what's going on in a whole dimension beyond what we normally see. Waveguides in certain RF radars already do that.

Such instruments are not limited to the resolution determined by the "real" part of the EM wave (such as the "real part" of light).

Such a microscope would not necessarily be limited in resolution by the wavelength of the light it used to illustrate the observed object.

Indeed, if one uses a higher dimensional Kaluza-Klein model (which particle physics of necessity has to consider), one could build a "repetitive stages" instrument which could view many more higher dimensions. That's exactly the same thing as viewing many more deeper internested levels of virtual state.

That is precisely what Royal R. Rife did: **He developed a microscope using multiple stages, special interferences, etc. He built a multistaged evanescent wave instrument that could see into higher dimensions and deeper levels of virtual state.**

Rife's microscopes were thus startlingly different from normal microscopes. That is why he could see phenomena and organisms, ostensibly within the size capability of normal microscopic resolution, which ordinary microscopes could not see.*

Evanescent waves penetrate the virtual state (hyperdimensions) and interact with what to us is "dimensionless" (what does not spatially intersect our 3-space). Interfering multiple evanescent waves reflected from/having interacted with these (to us) nonphysical forms can again reproduce ordinary electromagnetic "light." Thus the evanescent wave microscope, if properly built, allows one to directly "see" (and photograph) what is to us living forms of energy, nonphysical, and without 3-space matter bodies.**

The same scheme can be used to develop instruments capable of directly revealing the living nonphysical world around us — such as the human biopotentials, their internal structures (including

---

*However, Rife's microscope was extraordinarily difficult to focus. Rife often spent 24 hours straight at his universal microscope, just in focusing it.

**If one is going to accept the many-dimensional theories necessary to explain particle physics, one must accept the possibility of higher dimensional living things, which we would see as living energy forms or as thought forms. These would appear nonphysical to us - as is time itself— but would be real and interactive nonetheless.

"thought forms"), etc. What the Soviets call **bioplasma** can be directly observed and photographed in this fashion. We have only to develop the necessary instruments; the science required is difficult, but it is already in the literature.

That is what Rife's microscope did. It was a forerunner of the instruments we need to develop in electromagnetic healing, and Rife was a truly great and unappreciated pioneer.

In one swoop medical science could have jumped a century ahead. The ruthless suppression of Rife and his fantastic scientific breakthrough was one of the most dastardly deeds ever perpetuated by the orthodox scientific establishment.

Rife Revealed a Far More Fundamental, Living Biology

With Rife's powerful universal microscope, it was also possible to view the interiors of the so-called "pinpoint" cells situated between normal tissue cells and just barely visible to ordinary microscopes.

Here is the astonishing living world inside those "pinpoint" cells, as revealed under Rife's powerful instrument: When one of the "pinpoint" cells was magnified, still smaller cells were revealed within its structure. When one of these still-smaller cells, in turn, was magnified, it too was seen to be composed of even smaller cells.

With Rife's microscope, this process could be repeated 16 times. An astonishing internested series of organized levels of a living cell was revealed, far more fundamental than anything that exists in present biological theory.

The present author points out most strongly that these levels correspond electrically to, and are in virtual particle flux pattern exchange with, the electromagnetic potentials of their environment. This includes their own biopotentials that are centered in the atomic nuclei of the atoms comprising the physical material of the cells, and that charge up with specific internal patterns.

The biopotential itself is organized into a corresponding virtual-state series of internested levels and functions. **The structured biopotential of the cell is a living, organized, functioning thing, and its internal functioning literally constitutes the "spirit" or "true nonmaterial deep mind" of the organism.**

All the internested levels are in constant electromagnetic exchange "up and down" with each other, particularly with respect to organized virtual particle flux patterns.

In addition, all the cells are in constant electromagnetic exchange "across" with each other, at all levels. This provides a dynamic, structured, living biopotential for the entire bio-organism (the entire body). Within this potential, dynamic interchange on all levels is continually occurring. This is the basis for the master cellular communication system that Dr. Fritz Albert Popp discovered.

Rife's powerful microscope had revealed nonmaterial functioning life forms (structured, dynamic, living biopotentials) connected to material bodies.

He could follow "filterable" forms of bacteria — actual living biopotential forms of the organisms that could not be separated out by filters, but which would easily pass through any filter.* He could observe interactions of these forms, changes of forms, translations and transmissions of forms, etc. — none of which is detectable by present biological theory or medical science.

Rife had advanced biology and biophysics a century in one jump. As always, orthodox scientists — most of whom in their scientific paradigm are self-admitted materialists — were quite unready to tolerate such heresy.

Obviously the materialistic dogma of the science of his day — and of the science of today — reacted most hostilely to such hogwash. Contrary to the prevailing mystique, most scientists are dogmatically attached to materialism and to the dogma of their present paradigm. Faced with a conflict provided by experiment, most will uphold the dogma and reject the experiment — the exact opposite of the scientific method they espouse.

Rife's revolutionary work was no exception. He incurred the unending, total opposition of powerful individuals controlling the direction of biology and medical science for their own personal gains.

Rife was hounded into court on trumped up charges. Though he was acquitted, he emerged a shaken, broken man and an alcoholic.

*More precisely, they would easily flow *around* the 3-dimensional filter, since they were hyperdimensional.

His work was suppressed. His equipment was left to gather dust. He was also forcibly committed to a medical treatment facility.

Finally escaping from his "prison," Rife lived out his remaining years quietly. He died without ever being vindicated for his marvelous, world-shaking discoveries.

But at least he left us a legacy. Persons are still alive who knew Rife and his work, to one degree or another. Some of his microscopes are still in existence, though non-operable due to missing or stolen parts. With proper funding, an enlightened team of scientists and researchers can be assembled to quickly repair Rife's remaining instruments and duplicate his incredible work.

With concentrated effort, Rife's work will yet play a primary role in the development of a direct electromagnetic cure for AIDS. As a byproduct, it will play a role in rapid development of cures for cancer and other debilitating diseases.

Royal R. Rife's contributions may yet help save half of humanity, and prevent a Soviet takeover of the world.

CHAPTER 6

DEVELOPING THE ELECTROMAGNETIC CURE FOR AIDS

By now, how one goes about developing a electromagnetic cure for AIDS — and for cancer and other killer diseases — should be apparent.

One must set up a modern research laboratory and assemble as many of the "dirty dozen" together as is possible. One then tackles the problem head-on, adding the necessary support staff and special consultants.

First the Kaznacheyev effect for AIDS must be isolated and determined. Then it must be reversed, to yield the precise "curative" signal.

Transforms for these Kaznacheyev IR/UV "death photons" and their phase conjugated "healing photons" must be obtained for a lower electromagnetic frequency band — such as, say, 10 to 20 gigahertz.

Away must be found to irradiate the whole human body with the curative signal. The ideal way is to utilize a scalar EM curative transform so that the atomic nuclei of the body — and hence its entire master cellular control system and immune control system—will be "charged up" with the correctly structured "AIDS cancellation message."

The entire procedure and apparatus must be as simple and small as possible. My colleagues have already achieved very promising — even remarkable — progress in this respect.

Reversing the Kaznacheyev Effect

The "Kaznacheyev effect" for AIDS virus condition must be stimulated between cell cultures, so that the disease condition is electromagnetically transferred from one to another. The actual electromagnetic "delta" constituting the contribution of the AIDS infection must then be isolated electronically. The best way to do this is probably to subtract the normal cell radiation pattern from the "cell plus AIDS" radiation pattern.*

With the "AIDS delta" determined, the delta is then fed into the appropriate phase conjugating mirror system, so that its time reversed replica is produced.

The new phase conjugated signal is then the required *AIDS reversal signal* to reverse the effects of the AIDS virus itself, inside the cell where it resides dormant. This " time-reversed" signal will reverse the genetic change in the cell, not just kill the HIV virus.

In a crude way, one is making an **electromagnetic anti-virus.**

For ease of development and treatment, microwave technology is most attractive. Obtaining transforms of the signals in the radar band is ideal, since a wide variety of techniques, instruments, and electronic parts are available for that region. Millimeter waves would be most attractive, for the equipment could then be highly miniaturized.

One can regard it another way also: energy forms (critters) are involved. The action of the AIDS virus in its host cell, upon the DNA of the host, is underlaid by manipulation of energy critters. If one makes the electromagnetic anti-virus form, one is also manipulating the energy critters in their virtual state substrata.

The net result is that essentially the virus pattern — even the virus itself — can be phase conjugated by the energy critters. The result can be to turn the actual virus in the cell into a negative virus, accomplishing recombinant DNA procedures in reverse.

Remember that the signal we seek to use involves negative energy and negative time. We are also engineering the virtual state directly. The ordinary positive energy/positive time/observable state rules and limitations do not necessarily apply. And the "fixed form" first order physical reality as we normally conceive it need not be so fixed at all.

---

*Procedures along the lines of the extraordinary double-exposure holographic work of Dr. Robert Powell will probably be necessary. His work on biologically significant spatial frequency spectroscopy has blazed the trail as to how to obtain the specific delta patterns desired. It is hoped that Powell will shortly publish the remarkable results of his 15 years' work.

Physical reality itself can be directly engineered.

The engineering we seek to accomplish is directly upon the probability states propagated by the Schroedinger equation, before observation and collapse of the wave function occurs. **We seek to engineer physical reality before it is born, while it is yet forming.**

Only at such a level can the previous action of the AIDS virus — that in which it combined its genetic material with the genetic material of the host cell — be reversed and undone.

Only at such a level can we convert the infected human body from an "AIDS virus factory" back to an uninfected normal human body without AIDS.

The Proof: Priore's Work

Antoine Priore's pioneering work largely proves that it can be done. Cancers, leukemias, and many other virulent diseases yielded to his phase conjugated signals passed down through a powerful magnetic field to totally penetrate every cell in the treated patient's body.

And Royal R. Rife's work proved that a virus and a bacterium are not at all the "rigidly fixed" physical forms that our normal science has led us to believe they are. Instead, both the organisms and their biochemical and genetic actions can be addressed — and changed — on a much finer level of reality.

Of course, it would be enormously helpful if one had a working Rife microscope.

My colleagues are attempting to rebuild one of the original Rife microscopes, which has parts that were missing from it. They have every hope of having the microscope in action in the future.

Another angle of attack is also possible.

One of my colleagues has discovered a very peculiar, weak electromagnetic signal that will kill viruses, harmful bacteria, toxic protozoa, etc. but not harm living human cells. Only a few volts and a few milliamps are used.

However, there exists a major problem in getting any such very weak signal into every cell in the body — which is required if one is to heal blood diseases such as AIDS and leukemia. After all, that was the reason that Priore utilized a powerful magnetic field of thousands of gauss. The magnetic field penetrated every cell in the body — even those in the bone marrow where all the blood cells are manufactured. By using the all-penetrating field as the carrier, the phase conjugated healing signal pattern could thus be introduced into every cell in the body, bathing it completely, inside and out, with the restorative signal.

Remember, **one must not just get the signal into the cells themselves — instead, one must get the restorative signals directly into, and absorbed in, the atomic nuclei.**

Again, that is why Antoine Priore found it necessary to employ a "rippling" magnetic field. The "ripple" was actually a magnetic wave, and nuclear resonance then provided the magic mechanism to penetrate all the atomic nuclei.

So the initial problem is, how does one provide a mechanism to carry the desired signals into and through each and every cell of the body and into each and every atomic nucleus of the matter of the body?

Obviously one can utilize nuclear magnetic resonance, after the fashion of Priore. If so, the resulting apparatus is going to be extremely large and expensive. It would be highly desirable to do it a different, simpler, much cheaper way.

After many hundreds of back-breaking experiments, one of my colleagues appears to have discovered a completely unique and direct way of introducing the desired EM restorative signals into and completely through every cell of the body, and into every atomic nucleus. Though much additional work to confirm this still remains, the initial results are marvelously encouraging.

Another colleague has succeeded in developing a peculiar sort of detector that should prove adaptable to detecting the actual "biopotential structural patterns" themselves, directly in and out of the atomic nuclei. Though obviously much more work is necessary before the final instrumentation is ready, the preliminary results are again most encouraging.

As I write these words on paper, this work is proceeding, but very, very slowly due to lack of the necessary funds to attack the research problems in force.

What is Needed

Time is running out —most conventional science appears to be driven by special interest groups/Drug Manufacturers who are unable and/or unwilling to counter the AIDS epidemic with anything other than extensive "Addict Style" symptom-reducing drugs that generate dollars, not cures. Though this is not universal, it *is* the conventional norm.

Unconventional disorders or diseases require *unconventional* science for *unconventional* cures.

Immediate funding is required if this awesome threat to humanity is to be stopped. An American public alerted in time to this desperate situation can demand that the government and/or private business immediately address and act on this life-threatening issue in a different, unconventional manner.

Encouraging Preliminary Work

One of my associates, already familiar with scalar EM devices, has exerted every effort to try to reduce the scope of the problem. In literally hundreds of experiments, he has been able to narrow down the search, and obtain at least some very promising results.

He has obtained an initial candidate phase conjugated signal for further test and trial.

He may well have succeeded in discovering a new and unique method to communicate signals directly into the atomic nuclei inside the matter in the human body. This signal presently appears to directly interact with the cellular biopotential and with the body's master cellular communication system.

Remember, however, these are preliminary results. They still must be fully substantiated in a great many more tests. Undoubtedly a great deal more research, analysis, and adaptation is necessary. We certainly cannot presently say we have any sort of "cure" for the AIDS virus or anything else — or that these results are to be considered as proven in any **fashion.**

But what we can say is that my colleague has been able to derive a very complicated phase-conjugated signal, which produces negative energy and negative time of the general sort required. And he may just have made a most marvelous discovery that will point the way to eventual equipment much, much smaller than the 4-stories high machine with which Priore intended to treat terminal human cancer patients.

The initial signal discovered by my colleague, when applied to the body at miniscule voltage, seems to zap all sorts of "bad things" — viruses, harmful bacteria, dangerous protozoa, microworms, you name it — without harming the blood cells, the normal body cells, or the hosted friendly bacteria.

The signal does this at miniscule voltage and amperage.

It can be applied directly to the body through special electrodes. Through a special feature, my colleague has been able to get the signal to reverberate the entire body, all cells, all parts, and even penetrate the atomic nuclei and establish scalar resonance therein.

There turned out to be some extremely strange things that have to be done to the phase conjugated signal before it will accomplish what is being sought. At least some of these "strange things" have been uncovered by my colleague.

One of the peculiarities is that the entire electrical apparatus is part of the input "form" (that conditions the potential wave structure) being phase conjugated and sent to the organism. If a lead-acid battery is included in the apparatus to power it, one will inject the electromagnetic form for the battery acid directly into the organism,* destroyingit. This includes destroying the host's cells. In this case the signal is lethal, not curative. Substitution of a dry cell battery with no liquid electrolyte eliminates the problem. Exactly why a liquid electrolyte has a toxic effect and a "sludge" or solid electrolyte does not, is not understood at this time.

Other such anomalies in the tentative process have been discov ered and compensated for.

However, the way ahead is exciting. It suggests that the body

---

*Via a mechanism similar to that found by Reid and Barsamian (atomic nuclei) can literally be "charged up" (i.e., the living biopotentials can be "charged up" with the signal structure) so that the "disease-proofing" is very lasting, possibly for many years or even for a lifetime.

At least my colleague has pressed this to the point of demonstrating a long-lasting charge being acquired by the body.

For example, at one time his body became so "charged" from his lengthy experiments that a one-inch blue spark often leaped from his fingers when he reached out for something metallic. The discharge was cool, negative energy — living energy, if you will. It should be negentropic, not entropic. It was definitely not the type of energy the orthodox scientific community is accustomed to. And normal electricity will definitely not charge up the body in such a continuing fashion, so far as is known.

Let me clearly state again that we have not yet produced the specific anti-pattern per se. What my colleagues have discovered appears to be a broad-band signal that appears to act hyperspatially, analogous to the manner in which a broad-band drug such as penicillin acts biochemically. Even this much remains to be clearly established.

However, it is a most encouraging and promising first step.

Much more work, and a great deal of experiments to substantiate or adapt these tentative results, still need to be done. Now there is no substitute for rigor and thoroughness — and there is no substitute for clearly and scientifically demonstrating the proof of the concept in the laboratory.

It is not just good intentions that we seek, but solid, concrete, proven results substantiated by proper scientific procedures. Much work remains to be done.

But the preliminary results are very encouraging indeed.

Let me briefly share with you some of the things we foresee, if this present line of successful development continues.

We foresee being able to eventually develop and set up — legally and under proper medical auspices, of course — tested and proven devices that can easily treat up to two or three hundred persons at once. A treatment of about 45 minutes to one hour is all that would be required. Several repetitive treatments a week or so apart, might prove advisory.

In addition,once the entire gamut of the treatment process is validated and proven, and shown to be completely harmless and safe in accordance with legal medical requirements, if need arises we foresee simply adding the signal to ordinary radio and television transmitters — perhaps as simply as modulating the electrical ground. If so, a "maintenance" signal could be established to negate the AIDS virus (or other disease such as cancer and leukemia) in an entire area, and keep out other diseases such as malaria, sleeping sickness, etc.

Another advantage of such machines would be their portability in time of conflict. Also, they would be most useful indeed as defensive measures against biological warfare. For example, the inhalation of only a relative minor amount of anthrax agent is sufficient for 100 percent certain death unless treatment begins promptly. With the portable machines, however, this would be easily negated in any troops exposed to the agent, even before the lethal disease is evidenced. For a totally new agent, a "phase-conjugate delta signal" could be rather quickly ascertained and developed, and the proper settings made on the machines for immediate treatment and immunizing.

And even later, when we proceed to the direct engineering of the living energy form strata themselves, we shall see remarkable cures and remissions of diseases for which medical science offers little hope today. Arthritis, multiple schlerosis, lupus, and other such debilitating diseases come readily to mind. **Even reversal of the aging process should be possible.***

*Two other promising approaches have recently been discovered First, an electrolyte compound has recently been approved by the FDA for clinical testing. This compound has the remarkable property of raising the cellular electrical potential back to that of a strong, healthy cell. In several years of lab animal testing, this alone was indicated to be over 80% effective against cancer. It may also prove effective against diseases such as arthritis, where the body's immune system attacks body tissue with lowered cellular potentials, since it fails to recognize the weakened cells as those of the body. Second, Baylor University reseachers have found that treating blood with certain laser EM radiation kills the AIDS virus, but does not harm the blood cells This means that it will be possible to assure that blood used in transfusions will be AIDS - free, eliminating one sorce of AIDS transmission.

Conclusion

We have now come to the end of our road, literally and figuratively.

All of us have been struck a mortal blow by the Soviet AIDS first strike.

Make no mistake, this is **real.** We and our children are already as good as dead unless we move as we have never moved before.

We have a chance. A slim chance.

Americans have always come through when the chips are down. We can conquer this thing. We can overcome this mighty death blow that has been launched against us. We can defeat the others yet to come.

But we've got to move. *Now.*

Remember, Pandora's box has already been spilled. Even without the Soviet biological warfare strike, hosts of new viruses and different strains of old ones are going to be, and are now being, dumped into the biosphere by our own culture. It is also only a matter of time before terrorists and meglomaniacs turn to the use of this potent weapon against a wide-open society such as ours.

Both our Armed Forces and our civilian populace are totally defenseless against electromagnetic biological warfare. Now. At this moment.

Even without the Soviet BW strike implication, it is only a matter of time until we perish, unless we develop electromagnetic healing and electromagnetic biological warfare countermeasures.

We've come to one of those profound momentary pauses in history that determine the fate of the entire world henceforth.

It's like the parable of the lady or the tiger.

We're facing, so to speak, two doors.

Behind one is the most fearsome and hungry tiger of all time. If we delay, that door will open and we'll get the tiger full upon us. We shall be utterly destroyed. That mighty tiger will consume half the world in his roaring frenzy. Our children, and our children's children — what few of them will be left — will wear the hammer and sickle yoke for eons.

Those few future survivors will be taught strange things. How you and I were the real enemy. How we were absolutely destroyed for the good of all mankind. How glorious and necessary it was to unleash the great plagues upon us. And how heroic were those who performed the "noble deed."

Our own distant children will curse us and revile us, and they will be taught to worship at the throne of a false prophet.

The world will descend into a new "Dark Ages" far more frightful than George Orwell ever envisioned.

On the other hand, behind the second door is the most beautiful lady of all history. Literally all of humanity's dreams of health, beauty, and vitality lie behind that door.

If we open it, we achieve a freedom from disease and a measure of bountiful health for all mankind that has heretofore only been dreamed of. *Even reversal of the aging process itself lies beyond the second door. Health and youth — the dream of the ages—can be ours.*

But we have only a moment to open the second door. It is firmly shut, and we must exert ourselves to the fullest if we are to open it at all.

On the human stage, the first door is already slowly opening, inexorably. In only a few moments it will be open and the tiger will be upon us.

We must move quickly.

Which will it be for mankind, the lady or the tiger?

The next few moments in the human play will most assuredly tell.

SELECTED BIBLIOGRAPHY

Note: An extended bibliography for this book would consist of literally thousands of references. Since there has not been time for that, a few key references on most substantive matters are listed. Where possible, one or more of the listed references will direct the interested reader to the pertinent literature on that subject.

References Related to Chapters 1 and 2

1. Pearce Wright, Science Editor: "Smallpox vaccine 'triggered Aids virus'," **The Times** of London, Mon. May 11, 1987, p. 1, 18.

2. Jon Rappoport, "News blackout on pox vaccine link to AIDS protecting WHO?", **Easy Reader,** June 4, 1987, p. 12.

3. Jonathan Tennenbaum, "Parameters for a research mobilization against AIDS," **Executive Intelligence Review (EIR),** Science & Technology, Mar. 6, 1987. p. 38-45.

4. Steve Connor, "AIDS: mystery of the missing data," **New Scientist,** Feb. 12, 1987, p. 19.

5. Steve Connor, "AIDS: Science stands on trial," **New Scientist,** Feb. 1987, p. 49-54.

6. "The virus reveals the naked truth," **New Scientist,** Feb. 12, 1987, p. 55-58.

7. Michael Gold, "Cancer Cover-up: How honest scientists evaded the issue of renegade cells that contaminated research labs worldwide," **Science Digest,** May 1986, p. 64-67, 80-81.

8. Michael Gold, **A conspiracy of Cells,** State University of New York Press, Albany, New York, 1985.

9. Kenneth J. McLeod, Raphael C. Lee, and H. Paul Ehrlich, "Frequency Dependence on Electric Field Modulation of Fibroblast Protein Synthesis," **Science,** Vol. 236, Jun. 12,1987, p. 1465-1468.

10. "Leukemia Virus Linked to Nerve Disease," **Science,** Vol.236, May 29, 1987, p. 1059-1061.

11. R.C. Desrosiers, "Origin of the human AIDS virus," **Nature,** vol. 319, 1986, p. 728.

12. R.B. Strecker, "AIDS virus infection," J.R. **Soc.** Med., Vol 79, 1986, p.559-560.

13. S.A. Aaronson, "Common Genetic Alterations of RNA Tumor Viruses grown in Human Cells," **Nature,** Vol. 230, 1971, p. 445-447.

14. A. Chandra et al, "Serological relationship between reverse transcriptase from human T-cell lymphotropic viruses defined by monoclonal antibodies," FEBS Lett., Vol. 200,1986, 327-332.

15. E. Dermott, J.K. Clarke and J. Samuels, "The Morphogenesis and Classification of Bovine Syncytial Virus," **J. Gen. Virol.** 1971; 12:105-119.

16. G. Corneo and L.C. Nelli, "Could Bovine Leukemia Virus be a possible Agent of Some Human Lymphatic Leukemias?", **Acta Haemat.** 72; 1984:65-66.

17. C.A. Mims, "Vertical Transmission of Viruses," **Microbiol. Rev.** 45; 1981:267-286.

18. C.W. Molander et al, "Isolation and Characterization of Vi ruses from Fetal Calf Serum," **In Vitro** 1972; 7:168-173.

19. P. Legrain, B. Goud and B. Buttin, "Increase of Retroviral Infection in Vitro by the Binding of Antiretroviral Antibodies," **J.Virol.** 1986; 60:1141-1144.

20. S. Kennedy -Stoskopf and O. Narayan, "Neutralizing Antibodies to Visna Lentivirus: Mechanism of Action and Possible Role in Virus Persistence," **J. Virol.** 1986; 59:37-44.

21. E.K. Knott, "Development of Ultraviolet Blood Irradiation, **Am. J. Surg.** 1948; 76:165-171.

22. Dr. John Seale, "The Origins of AIDS," Mar. 15, 1987.

23. R.B. Strecker and T.A. Strecker, "The Bioattack Alert (on AIDS)," Los Angeles, California, 1986.

24. R.B. Strecker, "Aids Virus Infection," J.R. **Soc. Med.,** vol. 79, Summer 1986, p. 559-560.

25. T.E. Bearden, "AIDS: Urgent Comments on Mankind's Greatest Threat," June 1987. Privately printed and circulated. "Aids: Urgent Comments on Mankind's Greatest Threat; and the Secrets of Electromagnetic Healing," presented in absentia at the U.S.P.A. Annual Symposium, July 30-Aug. 2,1987, Golden, Colorado.

26. **Executive Intelligence Review (EIR)** Special Report, "Global Showdown: The Russian Imperial War Plan for 1988," July 24, 1985.

27. **Executive Intelligence Review (EIR)** Special Report, "The Soviet role in covering up the deadly threat of AIDS," 12(42), Oct. 25,1985. Charges that Soviet infectious-disease experts control the Communicable Diseases Division of the World Health Organization. Nearly hysterical responses were stimulated by this report: for example, less than a week later, **Literaturnaya Gazeta,** Oct. 30, 1985 published a counter, and claimed the AIDS virus may have been produced in U.S. laboratories by the CIA and the Pentagon.

28. Jeanne Toal, "Supervaccines," **Omni,** July 1987, p. 20, 122.

29. The Kaznacheyev work. See appropriate section for references.

30. The Priore work. See appropriate section for references.

31. William Kucewicz, "The gates slam shut on a microbiologist," "Beyond Yellow Rain: The Threat of Soviet Genetic Engineering," Sixth of a Series, **Wall Street Journal,** May 8,1984. p. 34.

32. Department of Defense, **Soviet Military Power,** 1987.

33. William Kucewicz, "A non-stop Russian response to WWI," "Beyond Yellow Rain: The Threat of Soviet Genetic Engineering," Seventh of a Series, **Wall Street Journal,** May 10,1984. p.34.

34. Lewin, Leonard C, **Report from Iron Mountain on the**

Possibility and Desirability of Peace. The Dial Press, New York, 1967. If you want to read something that will curdle your blood, take a look at this book. There exists a surprising body of material where intelligentsia and "think tank" mentalities have grappled with the idea of non-warfare types of "control mechanisms" for humanity — including induction of biological disease on a mass scale, subtle forms of slavery, etc.

35. Bennett,William and Joel, Gurin, "Science that Frightens Scientists," **Atlantic Monthly,** Feb. 1977. Millions of persons in this country were inadvertently injected with a widely-used substance called simian virus 40, or SV40. Tests proved that SV40 caused cancerous cell growth when injected into animals. SV40 was an unrecognized contamination of polio vaccines given before 1962 and of some cold shots given about the same time. The authors conclude by stating: "The ultimate question is not whether bacteria can be contained in special laboratories, but whether scientists can be contained in an ordinary society."

36. Letter, Lynn M. Draft, White House Policy Staff, to Dick Gregory, April 11, 1977. Quoting: "It is true that the SV40 virus was discovered in the early 1960's. It is also true that the virus was found in certain viral vaccines prepared from virus pools grown in monkey kidney cell cultures. However, the virus had not been recognized as a contaminant prior to that time, although millions of people have received the vaccine during the 1950's."
"... contamination of the vaccine was unintentional due to lack of knowledge."

37. Snead, Dr. Eva Lee, M.D. "AIDS - Immunization related syndrome," **Health Freedom News,** July 1987, p. 14-17, 22, 44-45. Strongly and rigorously points out just now little we actually know, even today, about the cause of AIDS and some of the anomalies connected with it. Specifically, SV40 does not appear to have been searched for in AIDS victims. Lack of detection has little meaning, since SV-40 may disappear and not reappear until triggered or promoted by another virus or chemical. Yet SV-40 has been shown to be one of the activators of the HIV or AIDS virus, as reported by Howard E. Gendel man et.al, in an article published in the **Proceedings of the National Academy of the United States of America,** vol. 83, p. 9759-9763, Dec. 1986. Also, SV-40 carries other viruses

"piggyback" and may have that type of role in AIDS disease. SV-40 may predispose one to a secondary infection by nullifying the immune system. SV40 is ideally suited for genetic manipulation, splicing, and the creation of hybrids or mutants.' Dr. Snead rigorously points out that no one has proved as yet that any virus positively causes AIDS. What has been proven is that HTLV-III is present in large percentages of the AIDS victims. Dr. Snead raises many excellent issues which cry out for answers.

38. Pearl Ma and Donald Armstrong, **The Acquired Immune Deficiency Syndrome and Infections of Homosexual Men,** Yorke Medical Books, 1984.

39. Ostrow, David G; Terri A. Sandholzer and Yehudi M. Felman, Eds., **Sexually Transmitted Diseases in Homosexual Men,** Plenum books, 1984.

40. Snead, Dr. Eva Lee, M.D., **aids-update,** Jun. 15,1987. In this incisive summary, Dr. Snead "tells it like it is" about Salk vaccine, how vaccines are made, the lack of sufficient scientific accuracy and safety in making vaccines, the nearly general contamination of vaccines by at least some viruses, some macabre details of the constitution of the vaccine 'soups." etc.

41. Gallo, Robert C, "The AIDS Virus," **Scientific American,** 256 (1), Jan. 1987, p. 46-56.

42. **Institut Pasteur v. United States of America,** United States Court of Claims, Civ. A. No. 730-85. See also Steve Connor, "AIDS: Science Stands On Trial," **New Scientist,** Feb. 12, 1987, p. 49-58. Reveals some direct monetary interests involved in discovery of the AIDS virus, and in royalties for the blood test which detects the antibody to the virus. Extended litigation occurred between French scientists at the Pasteur Institute and Robert Gallo regarding who should receive credit for discovery of the virus causing AIDS. The two sides eventually agreed to share the credit for the discovery, and donate royalties to an AIDS research foundation. Note that Dr. Gallo is head of the Laboratory of Tumor Cell Biology at the National Cancer Institute.

43. Curran, James W. et al, "The Epidemiology of AIDS: Current Status and Future Prospects," **Science,** vol. 229, Sep.**27,**

1985, p. 1352-57. Among other things, this report downplays the role of non-viral agents in causing AIDS.

44. Duesberg, Peter H., "Retroviruses as Carcinogens and Pathogens: Expectations and Reality," **Cancer Research,** vol. 47, Mar. 1,1987, p. 1199-1220. Cites 278 references. Duesburg is a pioneer in the study of retroviruses and a professor in the Department of Molecular Biology and Virus Laboratory, University of California at Berkeley. To show some of the scientific disagreement as to the cause of AIDS, we quote from Dr. Duesberg's article: "AIDS virus is not sufficient to cause AIDS and ... there is no evidence, besides its presence in a latent form, that it is necessary for AIDS." Dr. Duesberg presents an impressive set of technical objections to the present, theory that the accepted AIDS virus actually causes AIDS.

45. **Steadman's Medical Dictionary,** Williams and Wilkins, Baltimore, 1966. p. 874. A German bacteriologist named Robert Koch established three "laws" to determine whether a certain micro-organism is the cause of a specific disease. These laws provide a basis for scientifically investigating infection and its causes. Koch's laws are: (1) Whether it be a bacterium, protozoan, or virus, the micro-organism must be present in all cases of the disease. (2) Inoculating animals with pure cultures of the micro-organism must produce the same disease in them. (3) It must be possible to obtain the micro-organism from these animals and further propagate the micro-organism in pure cultures. (Note that this leaves a real problem with any disease caused by complexes of different organisms, rather than just one.)

46. Altaian, Lawrence K., "Aids Development in Infection; Data Suggest AIDS Rises Yearly After Infection," **New York Times,** Mar. 3, 1987, p. C1. Among other things, points out that the AIDS seropositivity rate rose from 4 percent in 1978 to 68 percent in 1984 among 6,875 members of a San Francisco hepatitis B study group.

47. Moyo, "Fighting AIDS in Africa," **AfricAsia,** May 1987, p. 55

48. Altaian, Lawrence K., "AIDS in Africa," **New York Times.** Nov. 1, 1986, p. Al, A8.

49. Krieger, Nancy, "The Epidemiology of AIDS Riddle," **Science for the People,** Jan./Feb. 1987, p. 18.

50. Nordheimer, Jan, "Florida Pig Farm Poses AIDS Riddle," **New York Times,** May. 2, 1986, p. A7.

51. Saul, Stephanie, "A Focus for the AIDS Mystery," **Newsday,** Jan. 26, 1986, p. 7.

52. Segal, Jakob and Lilli, **AIDS: USA Home-Made Evil: Not Imported from Africa,** date unknown (believed 1986). Pamphlet widely circulated in Africa. The two scientists are a biologist and a biophysicist, affiliated with the Humbolt University of Berlin. In the pamphlet the authors charge that the AIDS virus was manmade, and suggest that it may have been created at Fort Detrick, Maryland. This and other such literature, plus deliberate Soviet propaganda releases charging that "U.S. biological warfare" is responsible for the AIDS pandemic, have significantly influenced widespread belief in Africa that the U.S. government is responsible. Our own thesis is that this merely shows how clever and coordinated the Soviet BW strike really is: the deception plan was complete and ready made. The viruses were made elsewhere (in cancer research labs), someone else unwittingly injected the contaminated vaccines (World Health Organization), and a good cover story was immediately at hand (simply blame the U.S.).

53. Pearce Wright and Thompson Prentice, "WHO seeks evidence over vaccine link to Aids virus," **The Times** of London, May 12, 1987.

54. "Near disaster with the Salk vaccine," **Science Digest,** Dec. 1963.

55. Bernard Fields, Malcolm A. Martin, and Daphne Kamely, Eds., "Genetically Altered Viruses and the Environment," **Banbury Report,** Cold Spring Harbor Laboratory, 1985.

56. The following summary articles are in Science, 239 (4948), Feb. 5, 1988: (1) Peter Piot et al, "AIDS: An International Perspective," p. 573-579; (2) Anthony S. Fauci, "The Human Immunodeficiency Virus: Infectivity and Mechanisms of Pathogenesis, " p. 617-622; (3) James W. Curran et al, "Epidemiology of HIV Infection and AIDS in the United States," p. 610-616; and (4) Richard W. Price et al, "The Brain in AIDS: Central Nervous System HIV-1 Infection and ATDS Dementia Complex," p. 586-592.

References Related to Chapter 3

1. Publications by **T.E.** Bearden:

- **a.** **Fer-de-Lance: A Briefing on Soviet Scalar Electromagnetic Weapons.** Tesla Book Co., POB 1649, Greenville, Texas 75401, 1986. Extensive coverage of Soviet scalar EM weapons and their testing. Heavily documented and illustrated. See a review of **Fer-de-Lance** in **Defense Science & Electronics,** June 1987, p. 80.
- b. **Excalibur Briefing.** Foreword by John White. Strawberry Hill Press, San Francisco, California 1980. An updated second edition, jointly published by Strawberry Hill Press and Tesla Book Co., 1988.
- c. **Tesla's Secret and The Soviet Tesla Weapons.** 1 hr. 40 min. videotape. 1981. Available from Tesla Book Co. Generally poor quality; lots of information.
- d. "Soviet Psychotronic Weapons: A Condensed Background." **Specula,** Journal of the AAMS, POB 1182, Huntsville Alabama 35807. 1(2), Mar.-June 1978. pp. 18-32. (Journal is now defunct).
- e. **Star Wars Now! The Bohm-Aharonov Effect, Scalar Interferometry, and Soviet Weaponization.** Tesla Book Co., 1984.
- f. **Soviet Weather Engineering Over North America**. 1-hr, videotape, 1985. Available from Tesla Book Co. Excellent quality; a great deal of information.
- g. **Solutions to Tesla's Secrets and the Soviet Tesla Weapons.** John T. Ratzlaff, ed. **Part II: Reference Articles for Solutions to Tesla's Secrets.** Tesla Book Co., 1981.
- h. "Tesla's Electromagnetics and Its Soviet Weaponization," **Proceedings of the 1984 Tesla Centennial Symposium,** International Tesla Society, Colorado Springs, Colorado 1984.
- i. USSR: New Beam Energy Possible?", **Defense & For-**

eign Affairs Daily, 13 (111), June 12, 1984, p. 1-2.

j. T.E. Bearden and Andrew Michrowski, eds., The **Emerging Energy Science,** Planetary Association for Clean Energy, Ottawa, Canada, 1985.

k. "AIDS: Urgent Comments on Man's Greatest Threat; and the Secrets of Electromagnetic Healing," presented in absentia at the U.S.P.A. Annual Symposium, July 30-Aug. 2, 1987, Golden, Colorado.

l. "Soviet Phase Conjugate Weapons: Weapons that use Time-Reversed Electromagnetic Waves," **Bulletin,** Committee to Restore the Constitution, POB 986, Ft. Collins, Colorado 80522, Jan. 1988.

m. "Tesla Electromagnetics: Weapons or Healing?" Presented at the Whole Life Expo, Los Angeles Airport Hilton Hotel, Los Angeles, California, Oct. 3, 1987.

2. William C. Douglass, **The Cutting Edge,** Nov. 1987, p. 3.

3. Stefan T. Possony, "Psy-War: Soviet Device Experiment," **Defense & Foreign Affairs Daily,** 12(104), June 7,1983, p. 1-2. Reports on Dr. Ross Adey's investigation of the Soviet LIDA device which is used to bombard human brains with radio waves of complex waveform in the 40 MHz region. Also reports on work by A.S. Davydov of the Ukranian Academy of Sciences, who discovered how the blood-brain barrier can be penetrated by low-frequency radio waves so that brain cells are affected.

4. Stefan T. Possony, "The Tesla Connection," **Defense & Foreign Affairs,** Aug. 1984, p. 12-14, 27. Highly recommended.

5. David Jones, "Israel's Secret Weapon," **Weekend Magazine,** Dec. 17, 1977.

6. Daniel A. Walker, Charles S. McCreery, and Fermin J. Oliveira, "Kaitoky Seamount and the Mystery Cloud of 9 April, 1984," **Science,** 227(4584), Feb. 8,1985, p. 607-611. See also Daniel L. McKenna and Daniel A. Walker, "Mystery Cloud: Additional Observations," **Science,** 234(4775), Oct. 24,1986, p. 412-413 for update to the information in the first article.

7. Robert J. Durant, "An Underwater Explosion — or What?",

Pursuit, 5(2), April 1972, p. 30-31.

8. Gwynne Roberts, "Witness to a Superweapon?", The **Sunday Times,** London, England, Aug. 17, 1980.

9. Central Intelligence Agency (CIA) Information Report No. CO-B-321/15354-66, "Sighting of Unusual Phenomenon on Horizon Near Iranian/USSR Border," Sep. 8,1966, released on 15 Dec. 1978 under the Freedom of Information Act (FOIA).

10. CIA Foreign Intelligence Information Report CO B-324/ 33601-76, "Aerial Observation of intense Source of Light," Nov. 18, 1976, released on 15 Dec. 1978 under the FOIA.

11. Max Frankel, "Khrushchev Says Soviet Will Cut Forces a Third; Sees 'Fantastic Weapon'", **New York Times,** Jan. 15, 1960, p. 1.

12. Christopher S. Wren, "Brezhnev Calls for Accord against 'Terrifying Arms," **New York Times,** June 14, 1975, p. 1,11.

13. Malcolm W. Browne, "Senatorial Group Received by Brezhnev," **New York Times,** July 3, 1975, p. 2.

14. Christopher S. Wren, "Moscow Now Pressing Disarmament," **New York Times,** Aug. 12, 1975, p. 6.

15. Draft agreement introduced by Andrei A. Gromyko to the United Nations' thirtieth session of the General Assembly on Sept. 23,1975: "Prohibition of the Development and Manufacture of New Types of Weapons of Mass Annihilation and of New Systems of Such Weapons." The first article provided that the types of these new weapons would be "specified through negotiations on the subject."

16. "Secret Speech: Did Brezhnev Come Clean?", **National Review,** 29(8), Mar. 4, 1977, p. 248, 250.

17. William Beecher, "Brezhnev termed detente a ruse. 1973 report said," **Boston Globe,** Feb. 11, 1975, p. 1, 12.

18. See a series of articles by C.B. Baker in **Youth Action** NEWS,

POB 312, Alexandria, Virginia 22313: "Soviet Weather Mayhem." Nov., 1983; "Diabolic Soviet Warfare," Nov. 1984; "The Soviet Zapping of America," Dec. 1986; "Fifth Column Treachery," May 1987; and others.

19. "Jetliner drops 32,000 feet; 400 aboard; 50 are injured," Associated Press (AP) Release, **Huntsville (Alabama) Times,** Feb. 20,1985, p. 1. Also "China Airlines Pilot Denies Cockpit Error," AP Release, **Huntsville (Alabama) Times,** Feb. 21, 1985, p. A-9.

20. Paul Brodeur, **The Zapping of America,** W.W. Norton & Co., New York, 1977.

21. "Navy sabotages traffic lights, TV sets," United Press International (UPI), PM cycle, Jan. 11,1985; "Power blackout blamed on anti-radar particles," UPI, AM cycle, Jan 11, 1985; "Power Disrupted Briefly After Navy Plane Drops Metallic Strands," AP, AM cycle, Jan. 16 1985.

22. Bradley Wells, "The Russian woodpecker: a continuing nuisance," CQ **Magazine,** Nov. 1984.

23. "Explosive Events Seen on Soviet Island," **Aviation Week & Space Technology,** Sept. 26,1983, p. 31. Also Letter John M. Miller, Geophysical Institute, University of Alaska, Jan. 41985 with attachment, "Bennett Island plume cases recently found." Incredibly, the U.S. State Department is now attempting to **give away,** to the Soviet Union, the five-island chain of Wrangel, Herald, Bennett, Henrietta and Jeannette Islands and an outer continental shelf portion of Alaska twice the size of California! If this happens, the Bering Sea will become a Soviet pond.

24. Sam Bishop, "UA photos show Soviets break ice for missiles," **Fairbanks Daily News-Miner,** Dec. 15 1984, p. 1,3. See also Craig Covault, "Soviet ability to fire through ice creates new SLBM basing mode," **Aviation Week & Space Technology,** Dec. 10, 1984. See also "Wrangel over Wrangel and the Weather War," Don Bell Reports, 32(9), Mar. 8,1985. See also, "Wrangel Giveaway Imminent," **The Spotlight,** Jan. 18, 1988,p.1,3.

25. Philip J. Klass, "Anti-Satellite Laser Use Suspected," **Avia-**

tion Week & Space Technology, Dec. 8, 1975, p. 12-13.

26. Joe Schwartz, **Nature,** 280, July 12, 1979, p. 95.

27. V.D. Sokolovskiy, **Soviet Military Strategy,** third edition 1968, p. 298.

28. T.T. Wu, "Electromagnetic Missiles," **J. Appl. Phys.** 57,1985, p. 2370-2373. See also "Filter Center," article on SDI, **Aviation Week & Space Technology,** Feb. 29, 1988, p. 55.

29. Michael McClelland, "State officials bend an ear to boom talk in Panhandle," **News Tribune,** Fort Pierce, Florida, Apr. 22, 1984.

30. Susan Burgess, "NASA officials stumped by strange light, boom," **News Tribune,** Fort Pierce, Florida, Nov. 28, 1985.

31. Bernie Woodall, "Residents are baffled by boom," **News Tribune,** Fort Pierce, Florida, Nov. 27, 1985.

32. Julie Enders, "Star of wonder: booming, bright," **News Tribune,** Fort Pierce, Florida, Dec. 6, 1985.

33. April 8, 1986 Canadian Broadcast Network television news interview of three eyewitnesses to the crash of the Arrow Air DC-8 jet liner at Gander Air Force Base, Newfoundland on Dec. 8, 1985. A yellow light was seen on the aircraft.

34. "Arrow Air was absolutely safe, FAA official says," UPI release, **Birmingham (Alabama) Post-Herald,** Apr. 17,1986.

35. "Titan Explosion Cripples U.S. Launch, Surveillance Capability," **Aviation Week & Space Technology,** 124(17), Apr. 28, 1986, p. 16-19.

36. Zhores A. Medvedev, **Nuclear Disaster in the Urals,** Translated by George Saunders, W.W. Norton & Co., 1979, p. 150

37. Gary North, "Electronic Aids (Parts 1 & 2)," **Remnant Review,** 12 (20), Nov. 1,1985, p. 1-8; 12 (21), Nov. 15,1985, p. 1-8. POB 8204, Fort Worth, Texas 76124.

38. Captain John D. LaMothe, **Controlled Offensive Behavior**

— USSR, Defense Intelligence Agency (DIA) Report ST-CS-01-169-72, 1972 (Released under FOIA).

39. Captain John D. LaMothe and Mr. Louis Maire, **Soviet and Czechoslovakian Parapsychology Research,** DIA Report DST-1810S-387-75, 1975. (Released under FOIA).

40. John Bentley, **The Thresher Disaster: The Most Tragic Dive in Submarine History,** Doubleday & Co., Garden City, New York, 1975.

41. Canadian Aviation Safety Board (CASB), **Public Inquiry Into the Aircraft Accident Which Occurred Near Gander Airport, Gander NFLD. December 12, 1985,** Vol. 1, Apr. 8, 1986. Hull, Quebec, Canada.

42. Department of Defense, **Soviet Military Power,** 1987.

43. "America's Space Program Sabotaged?" Robert Herzberg, **International Combat Arms,** Mar. 1987. p. 12.

44. Pearce Wright, Science Editor: "Smallpox vaccine 'triggered Aids virus'," **The Times** of London, Mon. May 11, 1987. p. 2.

45. Jon Rappoport, "News blackout on pox vaccine link to AIDS protecting WHO?", **Easy Reader,** June 4, 1987, p. 12.

46. R.B Strecker and T.A. Strecker, "The Bioattack Alert (on AIDS)," Los Angeles, California, 1986.

47. EIR Special Report, "The Soviet role in covering up the deadly threat of AIDS," 12(42), Oct. 25, 1986.

48. Dr. John Seale, "The Origins of AIDS," Mar. 15, 1987.

49. Martin Ebon, **Psychic Warfare: Threat or Illusion,** McGraw Hill Book Co., New York, 1983.

50. For details of mysterious, instant deaths in Afghanistan, see Yossef Bodansky, "Soviets testing chemical agents in Afghanistan," **Jane's Defense Weekly,** 1(13), Apr. 7, 1984, p. 508.

51. " 'Observers' at the August Minuteman Shot?", **The INFO**

Journal, 2(1), Fall 1968, p. 35.

52. Dietrick E. Thomsen, "The Mystery of the Cosmic Gamma-Ray Zaps," **Science News,** 105 (22), June 1, 1974, p. 357-358.

References Related to Phase Conjugation (Time Reversal)

1. Amnon Yariv, **Optical Electronics.** Third Edition. Holt, Rinehart and Winston: New York, 1985. See particularly Chapter 16: "Phase Conjugate Optics — Theory and Applications."

2. Robert A. Fisher, Ed., **Optical Phase Conjugation.** Academic Press, New York, 1983. Collection of papers. An extensive bibliography is given at the end of the book. Note that Fisher's introduction to the phase conjugation effect was as a result of two Russian visitors who briefed scientists at Lawrence Livermore Laboratory on optical phase conjugation. Also note (p.xv, p. 20) that almost any nonlinear optical effect can phase conjugate an incoming beam.

3. B. Ya Zel'dovich and V.V. Shkunov, "Spatial-Polarization Wavefront Reversal in Four-Photon Interaction," **Soviet Journal of Quantum Electronics,** Vol. 9, 1979. p. 379.

4. B. Ya Zel'dovich et al, "Connection between the wave fronts of the reflected and exciting light in stimulated Mandel'shtam-Brillouin scattering," English translation, **Sov. Phys. JETP** 15,109(1972).

5. B. Ya Zel'dovich, N.F. Pilipetsky, and V.V. Shkunov, **Principles of Phase Conjugation,** Vol. 42, Springer Series in Optical Sciences, Theodor Tamir, Ed., Springer-Verlag, New York, 1985.

6. J.P. Woerdman, "Formation of a transient free carrier hologram in Si," **Opt. Commun.,** vol. 2, 1971. p. 212.

7. B.I. Stepanov, E.B. Ivakin, and A.S. Rubanov, "Recording two dimensional and three-dimensional dynamic holograms in bleachable substances," Translation: **Soviet Physics-Doklady-Technical Physics,** vol. 16, 1971. p. 46.

8. A. Yariv, "Three-dimensional pictorial transmission in optical

fibers," **Appl. Phys. Lett.,** vol. 28, 1976. p. 88.

9. A. Yariv, "On Transmission and recovery of three-dimensional image information in optical waveguides," **J. Opt. Soc. Amer.,** vol. 66, 1976. p. 301.

10. R.W. Hellwarth, "Generation of time-reversed wave fronts by nonlinear refraction," **J. Opt. Soc. Amer.,** vol. 67,1977. p. 1.

11. A. Yariv and D.M. Pepper, "Amplified reflection, phase conjugation, and oscillation in degenerate four-wave mixing," **Opt. Lett.,** vol. 1, 1977. p. 16.

12. R.L. Abrams and R.C. Lind, "Degenerate four-wave mixing in absorbing media," **Opt. Lett.,** vol 2, 1978, p. 94. Erratum is contained in **Opt. Lett.,** vol 3, 1978, p. 205.

13. P.F. Liao, D.M.Bloom, and N.P. Economou, "CW optical wave-front conjugation by saturated absorption in atomic sodium vapor, **"Appl. Phys. Lett.,** vol. 32, 1978, p. 813.

14. A. Yariv, "Compensation for atmospheric degradation of optical beam transmission," **Opt. Commun.,** vol. 21, 1977. p. 49.

15. R.W. Hellwarth, "Third order susceptibilities of liquids and gases," **Progress in Quantum Electronics,** vol. 5, 1977. p. 1.

16. J. Auyeung et al, "A theoretical and experimental investigation of the modes of optical resonators with phase-conjugate mirrors," **IEEE J. Quant. Electr.,** vol. 9, 1979. p. 1198.

17. I.M. Beldyugin and E.M. Zemskov, "Theory of resonators with wave-front reversing mirrors," **Sov. J. Quant. Elect.,** vol. 9, 1979. p. 1198.

18. A. Yariv and T.L. Koch, "One way coherent imaging through a distorting medium using four-wave mixing," **Opt. Lett.,** vol. 7, 1982. p. 113.

19. J.O. White and A. Yariv, "Real time image processing via four-wave-mixing in a photorefractive medium," **Appl. Phys. Lett.,** vol. 37, 1980. p. 5.

20. N.V. Kukhtarev et al, "Holographic storage in electrooptic crystals," **Ferroelectrics,** vol. 22, 1979. p. 949.

21. M. Cronin-Golomb et al, "Theory and applications of four-wave mixing in photorefractive media," **IEEE J. Quant. Elec,** vol. 20, 1984. p. 12.

22. J.P. Huignard, J.P. Herriot and G. Rivet, "Phase conjugation and spatial frequency dependence of wavefront reflectivity in $Bi_{12}SiO_{20}$(BSO) crystals," **Opt. Lett.,** vol. 5, 1980. p. 102.

23. J.O. White et al, "Coherent oscillation by self-induced gratings in the photorefractive crystal $BaTiO_3$," **Appl. Phys. Lett.**, vol. 40, No. 6, 1982. p. 450-452.

24. J.W. Haus, CM. Bowden, and C.C. Sung, "Optical phase conjugation with smooth pump profiles," **Phys. Rev. A, General Physics,** vol. 35, No. 8, Third Series, Apr. 15, 1987. p. 3398-3405.

25. Mary J. Miller et al, "Time response of a cerium-doped $Sr_{0.75}$ $Ba_{0.25}$ Nb_20_6 self-pumped phase-conjugate mirror," **Opt Lett.,** vol. 12, No. 5, May 1987. p. 340-342.

26. Mark Cronin-Golomb et al, "Passive (self-pumped) phase conjugate mirror: Theoretical and experimental investign tion," **Appl. Phys. Lett.,** vol. 41, No. 8, Oct. 15, 1982. p. 689 691.

27. Philip S. Brody and Richard P. Leavitt, "Dynamic holographic method of imaging phase objects," **Applied Optics,** vol. 26, No. 5, Mar. 1, 1987. p. 913-916.

28. J. Feinberg, "Self-pumped, continuous-wave phase conjugator using internal reflection," **Opt. Lett.,** vol. 7, 1982. p. 486.

29. T.Y. Chang and R.W. Hellwarth, "Optical phase conjugation by backscattering in barium titanate," **Opt. Lett.,** vol. 10, 1985. p. 408.

30. J.P. Huignard et al, "Phase-conjugate wavefront generation via real-time holography in $Bi_{12}Si0_{20}$ Crystals," **Opt. Lett.,** vol 4, 1979. p. 21.

31. David M. Pepper, "Nonlinear optical phase conjugation," guest editorial, **Optical Engineering,** vol. 21, no. 2, Mar./Apr. 1982. p. 155. One of the leaders of the field of nonlinear optical phase conjugation (NOPC) tells one in clear English what all the excitement is about. He also points out that the conceptual extension of these techniques to other portions of the electromagnetic spectrum should follow.

32. David M. Pepper, "Nonlinear optical phase conjugation," **Optical Engineering,** vol. 21, no. 2, Mar./Apr. 1982. p.156-183. This paper is the best introduction to, and summary of, nonlinear optical phase conjugation (NOPC) in the English language. Also, on p. 156 the author specifically notes that "...these processing techniques can, in principle, be extended to other portions of the EM spectrum (e.g.,, rt, radio, microwave, radars, UV, etc.); and can also involve other fields (e.g., acoustic waves), given the proper nonlinear medium." In other words, phase conjugation is a universal nonlinear phenomenon, unknown until recently. An extensive bibliography of over 200 references is included.

33. Jeffrey O. White and Amnon Yariv, "Spatial information processing and distortion correction via four-wave mixing," **Optical Engineering,** vol. 21, no. 2, Mar./Apr. 1982. p. 224-230.

34. R.W. Hellwarth, "Optical beam phase conjugation by four-wave mixing in a waveguide," **Optical Engineering,** vol. 21, no. 2, Mar./Apr. 1982. p. 263-265.

35. I.M. Bel'dyugin, V.N. Seminogov, and E.M. Zemskov, "Possible wavefront reversal of fields using nonlinear-optics methods," **Sov. J. Quantum Electron.,** vol 9, no. 3, Mar. 1979. p. 385-387.

36. I.M. Bel'dyugin, M.G. Galushkin, and E.M. Zemskov, "Properties of resonators with wavefront-reversing mirrors," **Sov. J. Quantum Electron.,** vol 9, no. 1, Jan. 1979. p. 20-23.

37. G.S. Agarwal, Ari T. Friberg, and E. Wolf, "Elimination of distortions by phase conjugation without losses or gains," **Opt. Commun.** 43 (6), Nov. 15,1982. p. 446-450. Using scalar wave theory, the authors show the conditions for complete cancellation of distortion by phase conjugation: (1) scatterer is non-absorbing, (2) infinite phase conjugate mirror, (3) conjugate

wave generated without losses, (4) effects of evanescent waves are negligible outside the scatterer. Comment: By reflecting upon this paper, one can grasp that essentially the same approach can be used to show that phase conjugation generates Newton's third law of motion.

38. G.S. Agarwal and Emil Wolf, "Theory of phase conjugation with weak scatterers," J. **Opt. Soc.** Am., 72(3), Mar. 1982. p. 321-326. The effect of a distorting medium on an incident wave is eliminated by phase conjugation if certain conditions are satisfied: (1) the incident wave contains no evanescent components, (2) the transmitting medium is a weak, nonabsorbing scatterer, (3) backscattering of incident waves and of conjugate waves is negligible, (4) effects of scattered evanescent waves are negligible. Comment: A similar approach can be used to show that phase conjugation generates Newton's third law of motion.

39. T. Sato et al, "Application of evanescent waves to microscopic observation," **Bull. Tokyo Inst. Technol. (Japan),** No. 125, 1974. p. 35-41. Evanescent wave illumination for microscopy can be used for recognizing higher frequency components impossible to recognize by conventional illumination.

40. S. Twareque Ali. "Evanescent waves in quantum electrodynamics with unquantized sources," **Phys. Rev. D,** 7(6), Mar. 15,1973. p. 1668-1675. An identity between evanescent waves and virtual photons is established.

41. J.D. Lawson, "Some attributes of real and virtual photons," **Contemp. Phys. (Great Britain),** 11(6), Nov. 1970. p. 575-580.

42. J.L. Agudin et al, "The behaviour of evanescent waves under Lorentz transformation," **Lett. Nuovo Cimento (Italy),** vol. 23, ser. 2, no. 15, Dec. 9, 1978. p. 547-551. Two linear combinations of transverse magnetic and electrical evanescent waves (the left-and right-handed circularly polarized modes) remain the same in all systems under Lorentz transformation.

43. M. Hercher, "virometer—an instrument for the measurement of the size of viruses using an optical microscope." **Proc. Soc. Photo-Opt. Instrumentation Engineers,** vol. 126,1978. p. 17-22.

44. G.A. Massey, "Microscopy and pattern generation with scanned evanescent waves," **Appl. Opt. (Poland),** 13 (3), 1983. p. 247-255. This article shows how to materially violate the usual "wavelength limitation" of optical systems. Much better resolution can be obtained, and very sharp images can be performed. Comment: This mechanism may be the secret ofthe Rife microscope, which could see viruses and other small organisms otherwise quite beyond normal optical microscopy's wavelength resolution.

45. H.J. Gerritsen, "Nonlinear effects in image formation," **Appl. Phys. Lett.,** vol. 10, 1967. p. 237.

46. D. Gabor, U.S. patent No. 2,770,166.

47. H.W. Kogelnik, "Controlled transmission of waves through inhomogeneous media," U.S. Patent 3,449, 577.

48. V.I. Bespalov. Ed., **Optical Phase Conjugation in Nonlinear Media,** IPF AN SSR, Gorky, USSR, 1979 (in Russian).

49. B. Ya. Zel'dovich et al, "Phase conjugation by a surface," **Dok. Akad.Nauk SSSR 252,**1980, p. 92. English translation: **Sov. Phys. Dokl.** 25, 1980, p. 377.

50. F.V. Bunkin, D.V. Vlasov and Yu. A. Kravtzov, "On sound phase conjugation with amplification of phase-conjugated wave," **Kvantovaya Elektron.** 8, 1981, p. 1144. English translation: **Sov. J. Quant. Electron.** 11, 1980, p. 687.

51. A.G. Gyulamiryan et al, "Tunable nonlinear four-wave filter," **Opt. Spektrosk.** 52, 1982, p. 387. (In Russian).

52. R.Y. Chiao et al, "Stimulated Brillouin scattering and coherent generation ofintense hypersonic waves," **Phys. Rev. Lett.** 12,1964,p.592.

53. S.A. Akhumanov et al, **Problems in Nonlinear Optics (Electromagnetic Waves in Nonlinear Dispersive Media), INI** AN SSSR, Moscow, 1964. (In Russian).

54. N.B. Baranova and B.Ya. Zel'dovich, "Wavefront dislocations and zeros ofthe amplitude," **Zh. Eksp. Teor. Fiz.** 80,1981, p. 1789. English translation: **Sov. Phys. - JETP** 54, 1981, p. 925. Might one infer from this paper a cautious hint (and

probe) at "do you Westerners know of scalar EM?"

55. V.I. Bespalov, Ed., **Phase Conjugation in Nonlinear Media,** IPF AN SSSR, Gorky, USSR, 1982. (In Russian).

56. D. Gabor, "A new microscopic principle," **Nature** 161,1958, p. 777.

57. Yu F. Kir'yanov et al, "Four-wave mixing in resonantly amplifying media under inversion saturation," **Kvantovaya Elektron.** 8,1981, p. 1734. English translation: **Sov.J. Quant. Electron.** 11, 1981, p. 1047.

58. V.L. Vinetsky et al, "Amplification of coherent beams by dynamic holograms in ferroelectric crystals," **Izv. Akad. Nauk. SSSR** 41, 1977. p. 811.

59. V.P. Kondilenko, G.G. Odulov and M.S. Soskin, "Amplified reflection of phase-conjugate waves in crystals with the linear electrooptical effect in an external electrical field," **Izv. Akad. Nauk. SSSR, Ser. Fiz.** 45, 1981, p. 958.

60. Yu. I. Kucherov et al, "Copropagating four-beam interaction in slowly-responding media," in **Phase Conjugation in Nonlinear Media,** ed. by V.I. Bespalov, IPF AN SSSR, Gorky, USSR, 1982, p. 111.

61. A.P. Brysev et al, "Model realization of a NbLi parametric phase-conjugating sound amplifier," **Pis'ma Zh. Tokhn. Fiz. 1,** 1982, p. 546.

References Related to William J. Hooper's Work

1. William J. Hooper, "Apparatus for generating motional electric field." U.S. patent #3,656,013, Apr. 11, 1972.

2. William J. Hooper, "New horizons in electric, magnetic and gravitational field theory," presented at a meeting of the Particles and Fields Division of American Physical Societies, University of Colorado, Boulder, Colorado, Aug. 21, 1969.

3. William J. Hooper. "New horizons for the BxV theory of gravity," undated, unpublished.

4. William J. Hooper, "Equivalence of the gravitational field and

a motional electric field," Session S6, American Physical Society Meeting, Chicago, Illinois Nov. 28-29, 1958.

5. William J. Hooper, "Equivalence of the gravitational field and a motional electric field," **Proceedings of the Boulder Conference on High Energy Physics,** Colo. Assoc. Univ. Press, 1970. p. 483.

6. William J. Hooper, "The motional electric field generator," **Bull, of the Am. Phys. Soc,** Series II, 15(2), Feb. 1970. p. 209.

7. J.H. Jeans, **The mathematical theory of electricity and magnetism,** 4th edn., Cambridge University Press, 1923. p. 125, 606.

8. Henry W. Kendall and Wolfgang Panofsky, "The structure of the proton and the neutron," **Scientific American,** June 1971.

9. William J. Hooper, "All-electric motional electric field generator." U.S. Patent #3,610,971, Oct. 5, 1971.

10. William J. Hooper, "Similarities of the motional electric and gravitational fields," undated, unpublished.

11. P. Moon and D.E. Spencer, "Some electromagnetic paradoxes," **Journal of the Franklin Institute,** vol. 260, 2955. p. 373.

12. Leigh Page and Norman I. Adams, **Electrodynamics,** D. Van Nostrand Co., 1940.

13. William J. Hooper, **New horizons in field theory,** revised 1965, unpublished. Chapter 1, "Fundamental Fields," is particularly important.

14. G.I. Cohn, **Electrical Engineering** 68,1969. p.441. Pointed out difference between flux linking law and flux cutting law of induction. Comment: Recently the Lorentz force law has been proven false. A modified version of Ampere's law results and saves the day.

15. G.I. Cohn, **Paradoxes of Electromagnetic Induction,** thesis, Illinois Institute of Technology library.

16. Pharis E. Williams, "**The Possible unifying effect** of the **dy-**

namic theory," Los Alamos National Laboratory report LA-9623-MS, Los Alamos, New Mexico, May 1983 .

17. Pharis E. Williams, **On a possible formulation of particle dynamics in terms of thermodynamic conceptualizations and the role of entropy in it,** thesis, U.S. Naval Postgraduate School, 1976.

18. Pharis E. Williams "The Principles of the dynamic theory," Research Report EW-77-4, U.S. Naval Academy, 1977.

19. Pharis E. Williams, "The Dynamic theory: A new view of space, time, and matter," Los Alamos Scientific Laboratory report LA-8370-MS, Dec. 1980.

20. Pharis E. Williams, "The Arrow of time in the dynamic theory," Los Alamos Scientific Laboratory report LA-8690-MS, Feb. 1981.

21. Pharis E. Williams, "The Dynamic theory: Some shockwave and energy implications," Los Alamos Scientific Laboratory report LA-8402-MS, Feb. 1981.

22. Dan C. Ross, "Plane electromagnetic waves in the dynamic theory," Los Alamos National Laboratory report, date unk.

23. Dan C. Ross, "Speed of light in the dynamic theory," Los Alamos National Laboratory, date unk.

24. G. Gilbert and B. McClain, "Fermions and stability in quan turn Kaluza-Klein theories," **Nuc. Phys. B, Part. Phy.s. (Netherlands),** B244(l), Sept. 24,1984. p. 173-185. Oscilla tions of the internal space produce conformal gravity waves in the four-dimensional space.

25. M. J. Perry, "Magnetic monopoles and the Kaluza-Klein theory," **Am. Inst. Phys. Conf. Proc.** No. 116,1984. p. 121-125. Kaluza-Klein theory admits soliton solutions which constitute magnetic monopoles. These monopoles have inertial mass, but no gravitational mass.

26. M.W. Kalinowski, "The nonsymmetric Kaluza-Klein theory." **J. Math. Phys.** 24(7), July 1983. p. 1835-1845.

27. D.J.Toms, "Induced Einstein-Maxwell action in Kaluza-Klein

theory," **Phys. Lett. B (Netherlands),** 129B(1-2), Sept. 15., 1983. p. 31-35.

References Related to Ehrenhaft's Work

1. Alden P. Armagnac, "Magic with magnetism," **Popular Science** Magazine, June 1944. p. 130-133, 222, 226.

2. "Ehrenhaft discovery confirmed by new experiments," **Popular Science** Magazine, date unk., p. 208. [Comment: Later than June 1944, and still during WWII.]

3. "Magnetic current — discovery of the age?", **Radio-Craft** Magazine, Mar., 1944. p. 332.

4. "Discovery of the age?" **Radio-Electronics** Magazine, date unknown, p. 58.

6. Felix Ehrenhaft and Emanuel Wasser, "New evidence of the existence of charges smaller than the electron," **Philosophical Magazine and Journal of Science,** Seventh Series, 5(28), Feb. 1928. p. 225-241.

8. Felix Ehrenhaft, "The microcoulomb experiment. Charges smaller than the electronic charge." **Philosophy of Science,** 8(3), July 1941. p. 403-457.

7. Felix Ehrenhaft and Leo Banet, "Is there 'true magnetism' or not?", **Philosophy of Science,** 8(3), July 1941. p. 458-462.

8. Felix Ehrenhaft and Leo Banet, "Magnetization of matter by light," Nature, Mar. 8, 1941. p. 297.

9. Felix Ehrenhaft, J. Franklin Inst., vol. 230, 1940. p. 381.

10. Felix Ehrenhaft, **Nature,** vol. 146, 1941. p. 25.

11. D. Morichini, **Gilberts Ann. Phys.,** vol. 43, 1813. p. 212.

12. D. Morichini, **Gilberts Ann. Phys.,** vol. 46, 1814. p. 367.

13. M. Sommerville, **Gilberts Ann. Phys.,** vol 52, 1826. p. 493.

14. F. Zantejeschi, **Gilberts Ann. Phys.,** vol. unk. 1829, p. 187.

15. V. Baumgartner, **Gilberts Ann. Phys.,** vol. unk., 1827. p. 508.

16. Felix Ehrenhaft, "Rotating action on matter in a beam of light," **Science,** 101(2635), June 29, 1945. p. 676-677.

17. Gordon Ferrie Hull, "The torque or rotating action in a beam of light," **Science,** vol. 101, 1945. p. 220.

18. F. Ehrenhaft, **Wiener Akad. Anz.,** vol. VII, Mar. 4, 1909.

19. F. Ehrenhaft, **Wiener Akad. Anz.,** vol. X, Apr. 21, 1910.

20. F. Ehrenhaft, **Wiener Berichte,** vol. 119, 1910. p. 815.

21. F. Ehrenhaft, **Physik. Ztschr.,** vol. 11, 1910. p. 619.

22. F. Ehrenhaft, **Physik. Ztschr.,** vol. 39, 1938. p. 673.

23. F. Ehrenhaft, **Ann. der Physik.,** vol. 56, 1918. p. 81.

24. F. Ehrenhaft, **Comp. Rend.,** vol. 190, 1930. p. 263.

25. F. Ehrenhaft, **Ann. der Physik.,** vol. 13, 1940. p. 151.

26. F. Ehrenhaft, **Jour. Frank. Inst.,** vol. 233, 1942. p. 235.

27. F. Ehrenhaft, **Nature,** vol. 154, 1944. p. 426.

28. F. Ehrenhaft, **Phys. Rev.,** vol. 65, 1944. p. 287.

29. F. Ehrenhaft, **Bull. Am. Phys. Soc.** (New York Meeting), vol. 6, 1945.

30. H.S. Renue, **Radio Electronic Engineering (Radio News),** vol. 4, 1945. p. 22.

31. Woldemar Voigt, **Festschrift fuer Heinrich Weber,** 1912.

32. P.A.M. Dirac, "Development of the physicist's conception of nature," **Symposium on the Development of the Physicist's Conception of Nature,** ed. Jagdish Merha, D. Reidel Pub. Co., Boston, 1973. p. 12-14.

33. Olof Alexandersson, **Living Water: Viktor Schauberger**

and the Secrets of Natural Energy, translated by Kit and Charles Zweigbergk, Turnstone Press Limited, Willingborough, Northamptonshire, England, 1982. An excellent bibliography is included in the book.

34. O. Alexandersson, "Implosion contra explosion," **Seklet,** vol. 4, 1965.

References Related to Louis Kervran's Work

1. Publications by Louis Kervran:

a. **Biological Transmutations.** Crosby Lockwood, London, 1972.

b. **A la Decouverte des Transmutations Biologiques, une Explication des Phenomenes Biologiques Aberrants.** Le Courrier du Livre, Paris, 1966.

c. **Preuves Relatives a L'existence de Transmutations Biologiques, Echecs en Biologie a la loi de Lavoisier d'invariance de la Matiere,** Maloine, Paris, 1968.

d. **Transmutations Biologiques; Metabolismes Aberrants de L'azote, le Potassium et el Magnesium,** Librairie Maloine, Paris, 1962.

e. "Les Transmutations Biologiques en Agronomie," Maloine, Paris, 1970.

f. **Biological Transmutations,** Swan House Publishing Co., Binghamton, New York, 1972.

g. "Alchimie d'hier et d'aujourd'hui," **L'Alchimie, Reve ou Realite,** Revue des Ingenieurs do L'Institut National Superieur de Rouen, 1972-73.

h. **Transmutations biologiques et physique moderne.** Paris: Maloine S.A., 1982.

i. **Transmutations a faible energie (naturelles et biologiques).** Paris: Librairie Maloine, 1972.

- j. **Transmutations biologiques.** Rue de l'Ecole-de-Medecine, Paris: Librairie Maloine S.A., 1963.
- k. **Transmutations naturelles.** Librairie Maloine S.A., Rue de l'Ecole-de-Medecine, Paris Vie, 1963.

2. Rudolf Hauschka, **The Nature of Substance,** Vincent Stuart Ltd., London, 1966.

3. V.B. Neiman. ed., **Problems of Transmutations in Nature: Concentration and Dissipation.** (Collection of papers in Russian), Aiastan Pub. House, Erevan, Armenia, USSR, 1971.

4. Peter Tompkins and Christopher Bird, **The Secret Life of Plants,** Harper & Row, New York, 1973.

5. The Kaznacheyev work and references. See appropriate sections.

6. Dr. Fritz Albert Popp's work and references. See appropriate sections.

7. The Australian work of Reid and Barsamian. See appropriate sections.

8. Fritz Albert Popp et al, eds. **Electromagnetic Bio-Information.** Proceedings of the Symposium, Marburg, September 5, 1977. Urban & Schwarzenberg, Baltimore, 1979.

9. Thomas E. Bearden, **The Excalibur Briefing,** Second edition, Strawberry Hill Press, San Francisco, 1988.

10. N.A. Kozyrev, "Possibility of the Experimental Study of the Properties of Time," Sep. 1967. English translation JPRS 45328, May 1968, p. 1-49.

11. Captain John D. LaMothe and Mr. Louis Maire, **Soviet and** Czechoslovakian **Parapsychology Research,** DST-1810S-387-75, Defense Intelligency Agency, Washington, D.C., 1975. Released under the Freedom of Information Act.

12. Jeff Hecht, "IBM Reports on Dark-Pulse Solitons," **Lasers & Optronics,** 7(3), Mar. 1988, p. 42 -44.

References Related to Popp's Master Cellular Communication System

1. Fritz Albert Popp, Gunther Becker, Herbert L. Konig, and Walter Peschka, Eds., **Electromagnetic Bio-Information: Proceedings of the Symposium,** Marburg, September 5, 1977, Urban & Schwarzenberg, Baltimore, 1979.

2. V.P. Kaznacheyev et al, "On distant intercellular interactions in a system of two tissue cultures connected by optical contact," **Transactions of the Moscow Society of Naturalists,** Vol. XXXIX, 1972. p. 224-227.

3. F.A. Popp, **Biophotonen. Ein neuer Weg zur Losung des Krebsproblems.** Verlag fur Medizin, Heidelberg, 1976.

4. F.A. Popp et al, "Biosignale zur Steuerung des Zellstoffwechsels. Eine Resonanzhypothese der Karzinogenese (vorl. Mitt.)" **Munch, med. Wschr,** vol. 116, 1974. p. 381-384.

5. F.A. Popp, "Molecular aspects of carcinogenesis, in Deutsch et al, eds.: **Molecular Base of Malignancy**, Stuttgart, 1976.

6. A. Gurwitsch, "Die mitogenetische Strahlung der Optischen Bahn bei adaquater Erreguns." **Pfluger Arch. ges. Physiol.**, vol. 231, 1932. p. 254-264.

7. A. Gurwitsch, "Die mitogenetische Strahlung des markhaltigen Nerven," **Pflugers Arch. ges. Physiol.,** vol. 231,1932. p. 234-237.

8. A.A. Gurwitsch, "The problem of mitogenetic radiation as an aspect of molecular biology." (in Russian), Leningrad, 1968.

9. A.A. Gurwitsch, V.F. Eremeiev, and Yu. A. Karabchievsky, "Energy bases of the mitogenetic radiation and its registration on photoelectron multipiers," **Medicina,** Moskva, 1974.

10. J.W. Hastings, "Bioluminescence," **Ann. Rev. Biochem.,** vol. 37, 1968. p. 597-630.

11. L.W. Latmanisowa, "Die mitogenetische Sekundar-strahlung des Nerven," **Pflugers Arch. ges. physiol.,** vol. 231,1932. p. 265-279.

12. H. Ninnemann et al, "Inhibition of respiration in yeast by light," **Biochim. Biophys. Acta,** vol. 205, 1970. p. 499-506.

13. T.I. Quickenden and S.S. Que Hee, "Weak luminescence from the yeast saccharomyces cerevisiae and the existence of mitogenetic radiation," **Biochem. Biophys. Res. Comm.,** vol. 60, 1974. p. 764-770.

14. A. Babloyantz, "Self-organization phenomena resulting from cell-cell contact," **J. Theor. Biol.,** vol. 68, 1977. p. 551-561.

15. R.M. Benolken, "Reversal of photoreceptor polarity recorded during the graded receptor potential response to light in the eye of limulus," **Biophys. J.,** vol. 1961. p. 551-564.

16. H. Breithaupt, "Biological rhythms and communication," in Fritz Albert Popp, Gunther Becker, Herbert L. Konig, and Walter Peschka, Eds., **Electromagnetic Bio-Information: Proceedings of the Symposium,** Marburg, September 5, 1977, Urban & Schwarzenberg, Baltimore 1979. p. 1-23.

17. Herbert L. Konig, "Bioinformation - Electrophysical Aspects," in Fritz Albert Popp, Gunther Becker, Herbert L. Konig, and Walter Peschka, Eds., **Electromagnetic Bio-Information: Proceedings of the Symposium,** Marburg, September 5, 1977, Urban & Schwarzenberg, Baltimore, 1979. p. 25-55.

18. Ulrich Warnke, "Information transmission by means of electrical biofields," in Fritz Albert Popp, Gunther Becker, Herbert L. Konig, and Walter Peschka, Eds.., **Electromagnetic Bio-Information: Proceedings of the Symposium,** Marburg, September 5,1977, Urban & Schwarzenberg, Baltimore, 1979. p. 55-79.

19. Walter Peschka, "On kinetobaric effects and bioinformational transfer by electromagnetic fields," in Fritz Albert Popp, Gunther Becker, Herbert L. Konig, and Walter Peschka, Eds., **Electromagnetic Bio-Information: Proceedings of the Symposium,** Marburg, September 5, 1977, Urban & Schwarzenberg, Baltimore, 1979. p. 81-94.

20. Gunther Becker, "Communication between termites by means of biofields and the influence of magnetic and electric fields on termites," in Fritz Albert Popp, Gunther Becker, Herbert L. Konig, and Walter Peschka, Eds., **Electromagnetic Bio-In-**

formation: Proceedings of the Symposium, Marburg, September 5,1977, Urban & Schwarzenberg, Baltimore, 1979. p. 95-106.

21. Bernhard Ruth, Experimental investigations on ultraweak photon emission," in Fritz Albert Popp, Gunther Becker, Herbert L. Konig, and Walter Peschka, Eds., **Electromagnetic Bio-Information: Proceedings of the Symposium,** Marburg, September 5,1977, Urban & Schwarzenberg, Baltimore, 1979. p.107-122.

22. Fritz Albert Popp, "Photon storage in biological systems," in Fritz Albert Popp, Gunther Becker, Herbert L. Konig, and Walter Peschka, Eds., **Electromagnetic Bio-Information: Proceedings of the Symposium,** Marburg September 5, 1977, Urban & Schwarzenberg, Baltimore, 1979. p. 123-149. A most important paper, presenting what I have been calling the master cellular communication system. Ruth has confirmed the existence of the "degradation radiation," ("death photons"). Experimental results of Ruth and others have led Popp to postulate that biological systems generally have the capacity to store coherent photons which come from the external world, and that ultraweak photon emission from biological systems is governed by photon storage ("charge up") within the cell population.

23. S.S. Sung, "A possible biophotochemical mechanism for cell communication," in Fritz Albert Popp, Gunther Becker, Herbert L. Konig, and Walter Peschka, Eds., **Electromagnetic Bio-Information: Proceedings of the Symposium,** Marburg, September 5,1977, Urban & Schwarzenberg, Baltimore, 1979. p. 151-174.

24. Helmut A. Fischer, "Photons as transmitter for intra- and inter-cellular biological and biochemical communication — the construction of a hypothesis," in Fritz Albert Popp, Gunther Becker, Herbert L. Konig, and Walter Peschka, Eds., **Electromagnetic Bio-Information: Proceedings of the Symposium,** Marburg, September 5, 1977, Urban & Schwarzenberg, Baltimore, 1979. p. 174-180.

25. Walter Kroy, "The use of optical radiation for stimulation therapy," in Fritz Albert Popp, Gunther Becker, Herbert L. Konig, and Walter Peschka, Eds., **Electromagnetic Bio-In-**

formation: Proceedings of the Symposium, Marburg, September 5,1977, Urban & Schwarzenberg, Baltimore, 1979. p. 181-193.

26. Ulrich Warnke and Fritz Albert Popp, "Some aspects of magnetic influences on biological systems," in Fritz Albert Popp, Gunther Becker, Herbert L. Konig, and Walter Peschka, Eds., **Electromagnetic Bio-Information: Proceedings of the Symposium,** Marburg, September 5, 1977, Urban & Schwarzenberg, Baltimore, 1979. p. 195-199.

27. A.S. Presman, **Electromagnetic Fields and Life,** Plenum Press, New York, 1964.

28. F.A. Popp and B. Ruth, "Untersuchungen zur ultraschwachen Lumineszenz aus biologischen Systemen unter Berrucksichtig ung der Bedeutung fur die Arzneimittelforchung," **Arzneimittel-Forsch,** vol. 27 (I), 1977. p. 933.

29. B.Ruth and F.A. Popp, "Experimentelle Untersuchungen zur ultraschwachen Photonenemission biologischer Systeme," Z. **Naturforsch,** vol. 31c, 1976. **p.** 741.

References Related to Kaznacheyev's Experiments

1. V.P. Kaznacheyev et al, "Apparent information transfer between two groups of cells," **Psychoenergetic Systems,** 1(1), Dec. 1974.

2. V.P. Kazacheyev et al, "Distant intercellular interactions in a system of two tissue cultures," **Psychoenergetic Systems,** 1(3), Mar. 1976.

3. Captain John D. LaMothe, **Controlled offensive behavior — USSR,** Report ST-CS-01-169-72, Defense Intelligence Agency, Washington, D.C. (Released under FOIA).

4. Captain John D. LaMothe and Mr. Louis Maire, **Soviet and Czechoslovakian Parapsychology Research,** Report. DST-1810S-387-75, Defense Intelligence Agency, Washington, D.C. (Released under FOIA).

5. Trevor James Constable, **The Cosmic Pulse of Life,** Merlin

Press, Santa Ana, California, 1976.

6. John White and Stanley Krippner, eds., **Future Science,** Anchor, 1977.

7. B. Ruth, "Experimental Investigations on Ultraweak Photon Emission," in **Electromagnetic Bioinformation, Proceedings of the Symposium,** Marburg, September 5, 1977 (Munchen-Wien-Baltimore, 1979). p. 107-122

8. H. Fischer, "Photons as Transmitters for Intra- and Intercellular Biological and Biochemical Communication — the Construction of a Hypothesis," in **Electromagnetic Bioinformation, Proceedings of the Symposium,** Marburg, September 5,1977 (Munchen-Wien-Baltimore, 1979). p. 175-180.

9. F.A. Popp, "Photon Storage in biological systems," in **Electromagnetic Bioinformation, Proceedings of the Symposium,** Marburg, September 5, 1977 (Munchen-Wien-Baltimore, 1979). p. 123-149.

10. A.G. Gurvitsch, **Theory of Biological Field,** Moscow, 1944 (in Russian).

11. A.G. Gurvitsch,"A Concept of 'the Whole' in the Frame of Biological Field Theory," in **Works on Mitogenesis and Theory of Biological Field,** Moscow, 1974, p. 141-147 (in Russian).

12. E.S. Bauer, "General Theory of Living Substance. The Problem of'Living Protein'," **Archives Biol. Sci.,** Vol. 35, Ser. A, Issue 1, 1934, p. 1-36 (in Russian).

13. E.S. Bauer, "Contradictions between the Inner and Outer Work of Living Systems," **Archives Biol. Sci.,** Vol. 35, Ser. A, Issue 1, 1934, p. 37-52 (in Russian).

14. E.S. Bauer, **Theoretical Biology,** Moscow, 1935 (in Russian).

15. S.V. Konev, "On the Question of Nature and Biological Significance of Ultraweak Luminescence of Cells," in **Bioluminescence,** Moscow, 1965, p. 181-183 (in Russian).

16. B.N. Tarusov, A.I. Pllivoda, and A.I. Zhuravlev, "Study of Ultraweak Spontaneous Luminescence of Animal Cells," **Biofzika,** Vol. 6, No. 4, 1961. p. 490-492 (in Russian).

17. M. Rottemeyer, "Modelle zur Interpretation der Ultraschwachen Photone-emission aus Biologischen Systemen," **Diplomarbeit** (Marburg, 1978), (in German).

18. Yu. A. Vladimirov, "Ultraweak Luminescence of Subcellular Structures," **Ultraweak Luminescence in Biology, Proceedings of the Symposium,** Moscow, 1969 (in Russian).

19. I.S. Marchenko, **Biofield of Forest Ecological Systems,** Bryansk, 1973 (in Russian).

20. S.S. Sung, "A Possible Biophotochemical Mechanism for Cell Communication," in **Electromagnetic Bioinformation, Proceedings of the Symposium,**, Marburg, September 5, 1977 (Munchen-Wien-Baltimore, 1971). p. 151-174.

21. P.A.Popp and B. Ruth, "Untersuchungen zur Ultraschwachen Luminiszenz aus Biologischen Systemen uter Berucksichtig ung der Bedeutung fur die Arznei-mittelforschung," **Arzneimit. Forsch.** (Drug Research), Vol. 27, No. 5,1977 (in German).

22. V.P. Kaznacheyev, "Informational Function of Ultraweak Flows of Light in Biological Systems," in **Materials of Scientific Conference: Physical and Mathematical Methods of Research in Biology and Medicine,** Novosibirsk, 1965, pp. 38-41 (in Russian).

23. V.P. Kaznacheyev, N.V. Ignatovich, and S.P. Shurin, "Intercellular Distant Interactions in a System of Two Tissue Cultures Connected by Optical Contact," in **Ultraweak Luminescence in Biology,** Moscow, 1969 (in Russian).

24. V.P. Kaznacheyev, L.P. Mikhailova, and S.B. Stephanov, "Studies on Cellular Monolayer and Cellular Distant Interaction in High Latitude Conditions," in **Technical-Scientific Progress and Circumpolar Medicine,** Novosibirsk, 1978, p. 133-134 (in Russian).

25. V.P. Kaznacheyev, L.P. Mikhailova, V.N. Sudarev, and S.P

Shurin, "Studies on the Biological Role of Electromagnetic Emission as a Factor of Adaptive Behavior of Cells under Conditions of Latitude Changes," in **Abstracts of the Second Ail-Union Conference Devoted to the Problem of** Human **Adaptation to Different Geographical, Climatic, and Labor conditions,** Novosibirsk, 1977, p. 101-104 (in Russian).

26. V.P. Kaznacheyev, L.P. Mikhailova, V.N. Sudarev, and S.P. Shurin, "Distant Intercellular Interactions Caused by UV-radiation," in **Photobiology of a Living Cell,** Leningrad, 1979, p. 221-223 (in Russian).

27. V.P. Kaznacheyev, L.P. Mikhailova, D.G. Kadayeva, and M.P. Dranova, "Conditions Necessary for Appearance of distant Intercellular Interactions after UV-radiation," **Bulleten Experimentalnoy Biologii i Meditsiny.,** No. 5. 1979, p. 468-471 (in Russian).

28. V.P. Kaznacheyev, L.P. Mikhailova, and S.P. Shurin, "Distant Intercellular Interactions in a System of Two Tissue Cultures Connected by Optical Contact," in **Regulation of Biosynthesis and Biophysics of Populations,** Krasnoyarsk, 1969, p. 372-374 (in Russian).

29. V.P. Kaznacheyev, S.P. Shurin, and L.P. Mikhailova, Discovery No. 122, "Distant Intercellular Interactions in a System of Two Tissue Cultures," **Official Bulletin of the Committee on Inventions and Discoveries Affiliated to the Council of Ministers of the USSR,** No. 19, 1973, p. 3.

30. V.P. Kaznacheyev, S.P. Shurin, L.P. Mikhailova, and N.V. Ignatovich, "Distant Intercellular Interactions in a System of Two Tissue Cultures Connected by Optical Contact," in **Ultraweak Luminescence in Biology,** Moscow, 1972, p. 224-227 (in Russian).

31. V.M. Inyushin, "The Concept of Biological Plasma and Some Questions of Photoenergetics," in **Questions of Bioenergetics,** Alma-Alta, 1968 (in Russian).

32. E. Makovsky, **Nature and Structure of Living Matter,** Bucharest, 1976 (in Russian).

33. A.L. Chizhevsky and Yu. Shishina, **In the Rhythm of the Sun,** Moscow, 1969.

34. Stefan T. Passony, "Psy-War: Soviet device experiment," **Defense and Foriegn Affairs Daily,** 12 (104), June 7,1983, p. 1-2.

35. V.I. Vernadsky, **Collected Works,** Moscow, 1960, (in Russian).

36. A.L. Chizhesvsky, **The Earth's Echo of the Sun Storms,** Moscow, 1973.

37. A.S. Pressman, **Electromagnetic Fields and Living Nature,** Moscow, 1968, English translation: **Electromagnetic Fields and Life,** Plenum, New York, 1970.

38. H.Z. Konig, "Bioinformation. Electrophysical Aspects," in **Electromagnetic Bioinformation, Proceedings of the Symposium,** Marburg, September 5,1977 (Munchen-Wien-Baltimore, 1979). p. 25-54.

39. V.P. Kaznacheyev, "Information Function of Ultraweak Light Flows in Biological Systems," in **Problems in Biophysics,** Novosibirsk, 1967, p. 7-18 (in Russian).

40. V.P. Kaznacheyev and L.P. Mikhailova, "Ultraweak Radiations in Intercellular Interactions," Novosibirsk, 1981 (in Russian); English Translation: San Francisco: Washington Research Center, 1982.

41. John F. Gilbey, "The delayed death touch," **Secret Fighting Arts of the World,** Charles E. Tuttle Co., Rutland, Vermont, 1963. p. 13-22.

42. Edward W. Russell, **Report on Radionics: Science of the Future,** Neville Spearman, London, 1973.

43. Paul Brodeur, **The Zapping of America,** W.W. Norton & Co., New York, 1977.

44. Waldemar Kaempffert," 'Dead' organisms revived," Science in the News: **Science Digest,** May 1950, p. 77-78.

45 "Rejuvenating light," **Scientific American,** May 1949.

46. Death-rays and life-rays discovered," **Science Digest,** Feb. 1950, p. 56. A "death" frequency seems to be at 2,537 angstroms, while a "life" frequency seems to be at 3,659 angstroms.

47. Lewis R. Roller, **Ultraviolet Radiation,** 2nd edn., John Wiley & Sons, New York, 1965. p. 236-237.

48. T.E. Bearden, Appendix: "Theory of Pulsor(R) operation," and "A partial glossary for scalar electromagnetics and subtle phenomena," in George T.F. Yao, **Pulsor(r): Miracle of Microcrystals,** Gyro Industries, Newport Beach, California, 1986.

49. The Antoine Priore material.

50. The Louis Kervran material.

51. Thomas E. Bearden, **The Excalibur Briefing,** Strawberry Hill Press, San Francisco, 2nd Edition, 1988.

52. Martin Ebon, "Moscow, June 11, 1977," in his **Psychic Warfare: Threat or Illusion,** McGraw-Hill Book Co., New York, 1983, p. 1-11.

References Related to the New View of the Nature of Mind and Thought

Author's Note: So far as I can find, there are no available references other than my own that deal precisely with my particular approach to the nature of mind and thought. There is, however, a serious debate over whether (a) the mind is simply the physical brain, similar to a computer (the prevailing materialist view of orthodox science), or (b) the mind is something else altogether, and metaphysical — at least with respect to the level of scientific knowledge today. My own approach utilizes a non-Aristotlean fourth law of logic (included in an appendix to this book) by means of which the dichotomy between mind and matter is removed. In that fashion, one can model the mind as material, or model matter us mind.

Some references that have influenced my thinking are given **below.**

Selected Bibliography

1. Publications by Thomas E. Bearden:

   a. "A Conditional Criterion for Identity, Leading to a Fourth Law of Logic," **Pursuit,** 13(1), Winter 1980. p. 6-10. (Appendix III to this present book.).

   b. "A mind/brain/matter model consistent with quantum physics and UFO phenomena," **Mutual UFO Network Annual UFO Symposium Proceedings,** 1979. Also available through the National Technical Information System, Port Royal Road, Springfield, Virginia 22161. Report AD-A068988.

   c. "An approach to understanding psychotronics." Paper delivered to 1977 Annual Symposium of the U.S. Psychotronics Association. Oglethorpe University, Atlanta, Georgia. 1977. Available through the National Technical Information System (NTIS), Port Royal Road, Springfield, Virginia 22161. Report AD-A027866. (This report is mostly rough notes).

   d. **Excalibur Briefing: Understanding Paranormal Phenomena.** Second edition. Foreword by John White. Strawberry Hill Press, San Francisco, 1988.

   e. "Hyperspace (virtual state) engineering." presented at the 11th MUFON UFO Symposium, Clear Lake City, Texas, June 6-8. 1980. Published in **UFO technology: a detailed examination: 1980 MUFON UFO Symposium Proceedings.** Edited by Walter H. Andrus, Jr. and Dennis W. Stacy. Mutual UFO Network, Seguin, Texas, 1980.

   f. "Photon quenching of the paranormal (time) channel: **a** brief note." Paper presented in absentia at the Third International Psychotronics Congress, Tokyo, 1977. Available through the NTIS, Port Royal Road, Springfield, Virginia 22161. Report AD-A038588.

   g. **Quiton/Perceptron Physics: A Theory of Existence, Perception, and Physical Phenomena." NTIS, 1973. Report AD-763210.**

h. "The Boundary Identity of Exact Opposites: A simple Solution to the Age-old Philosophical Problem of Change." NTIS, Oct. 1975. Report AD-020798.

i. "The fourth law of logic." NTIS, 1979. Report AD-A068987.

j. **Field, Formon, Superspace, and Inceptive Cyborg: A Paraphysical Theory of Noncausal Phenomena.** U.S. Army Medical Intelligence and Information Agency, Report MIIA-1-74, Dec. 1974. Available from the Defense Documentation Center (DDC), Report AD A-005579/8GI.

k. "The One Human Problem, Its Solution, and Its relation to UFO Phenomena." **Pursuit,** January 1976. Available from NTIS, Report AD-A034236.

1. "Writing the Observer Back Into the Equation," Address given to the Princeton Center for Alternative Futures, Princeton, New Jersey, Mar. 5,1976, published in June, 1976. Available from NTIS, Report AD-A027867.

m. "Species Metapsychology, UFO Waves, and Cattle Mutilations, May 23, 1977. Privately published.

n. "The Holography of Being," 1975. Unpublished,

o. **Yoseikan Aikido,** 1973. Privately published.

p. "AIDS: Urgent comments on mankind's greatest threat; and the secrets of electromagnetic healing," presented in absentia at the annual USPA Symposium in Golden, Colorado 30 July-2 Aug. 1987.

2. Mike Costello, "Without a Brain," letter, Fortean Times, 96 Mansfield Road, London NW 8 2HX, England, Spring 1987, p. 78. Information on hydrancephaly, persons with normal intelligence but with large cavities in the area normally occupied by cortical tissue. Most of the data on these anomalous cases is buried in obscure medical journals. (Hydrocephaly — an excess of fluid in the cerebral/spinal system — is much more widely known.). See also Anthony Smith, **The Mind,** Hodder & Stoughton, 1984 for additional information on hydrancephaly.

Quoting from Costello: "Actually cases of this kind have been turning up at autopsies for years, and reported in the appropriate medical journals, but have been disregarded, perhaps because they are so destructive of established beliefs about the relationship between consciousness and the human brain."

Costello goes on to point out that a group at Sheffield University has collected a great deal of data on this subject, from case studies of 253 hydrocephalics and hydrancephalics. There seems to be no correlation between the IQ of these individuals and the amount of residual brain tissue.

One living subject, Roger, has an IQ of 126 and a First Class degree in Mathematics, yet has no more than 5% of the normal amount of brain tissue.

A Swedish documentary on the subject was shown on ITV in 1982.

Fortean Times 38, **p.** 30 also contains an item on surviving adults with no detectable brains.

3. Hugh Everett, **III,** The **Many-Worlds Interpretation of Quantum Mechanics: A Fundamental Exposition,** with papers by J.A. Wheeler, B.S. DeWitt and Neill Graham, Princeton Series in Physics, Princeton University Press, 1973.

4. Louise and Galen Hieronymus, **Tracking the Astronauts in Apollo 11, With Data From Apollo 8 Included,"** Advanced Sciences Research and Development Corporation, Fort Lauderdale, Florida, 1969.

5. Vlail Kaznacheyev's work and publications related to it (see Kaznacheyev references).

6. Antoine Priore's work and publications related to it (see Priore references).

7. Charles Muses and Arthur M. Young, eds, **Consciousness and Reality.** Outerbridge & Lazard, 1972.

8. George Meek, **Healers and the Healing Process,** Theosophical Publishing House, 1977.

9. Harold Puthoff and Russell Targ, **Mindreach,** Delacorte, 1977.

10. Harold Puthoff and Russell Targ, "A Perceptual Channel for Information Transfer Over Kilometer Distances: Historical Perspective and Recent Research," **Proceedings of the IEEE,** 64(3), March 1976.

11. Edward W. Russell, **Report on Radionics,** Neville Spearman, London, 1973.

12. John White and Stanley Krippner, eds., **Future Science,** Anchor, 1977.

13. C. Louis Wiedemann, "Results ofthe N.J. 'Spook Light' Study," **Vestigia Newsletter,** Stanhope, New Jersey, May 1977.

14. David Bohm, **Wholeness and the Implicate Order,** Routledge, Kegan Paul, 1980.

15. Renee Weber, "Reflections on David Bohm's Holomovement: A Physicist's Model of Cosmos and Consciousness," in Valle and von Eckartsberg, editors, **The Metaphors of Consciousness,** Plenum Press, 1981.

16. "The Physicist and the Mystic: Is a Dialogue Between Them Possible?" A Conversation with David Bohm, conducted by Renee Weber, edited by Emily Sellon, **ReVision,** 4(1), Spring 1981, p. 22-35.

17. The Tao of Physics Revisited," A Conversation with Fritjof Capra, conducted by Renee Weber, **Revision,** 4(1), Spring 1981, p. 36-52.

18. "Reflections on the New Age Paradigm," an Interview with Ken Wilber, **ReVision,** 4(1), Spring 1981, p. 36-52.

19. Fritjof Capra, **The Tao** of **Physics,** Shambhala, Boulder, Colorado, 1975.

20. Fritjof Capra, **The Turning Point,** Simon & Schuster, New York, 1982.

Ken Wilbur, **Up From Eden,** Doubleday, 1981.

22. G. Spencer, **Laws of Form,** Julian Press, New York, 1972.

23. Bernard D'Espagnat, **Conceptual Foundations of Quantum Mechanics,** W.A. Benjamin, Menlo Park, California, 1971.

24. Robert Linssen, **Zen: The Art of Life,** Pyramid, New York, 1969.

25. E.P. Wigner, "Remarks on the Mind-Body Question," **The Scientist Speculates, I.J.** Good ed., W. Heinemann Ltd., London,1961.

26. Thomas G. Hieronymus, U.S. Patent No. 2,482,773, Sept. 27, 1949.

27. Langston Day and George De La Warr, **New Worlds Beyond the Atom,** Vincent Stuart Publishers Ltd., London, 1973.

28. Jule Eisenbud, M.D., **The World of Ted Serios,** Pocket Books, Simon and Schuster, New York, 1968.

29. Sheila Ostrander and Lynn Schroeder, **Psychic Discoveries Behind the Iron Curtain,** Prentice-Hall, 1970.

30. Carl G. Jung, **Man and His Symbols,** ed. by Carl G. Jung **and** after his death by M.S. von Franz, Aldus Books Ltd., London. 1964.

31. **The Unfathomed Mind: A Handbook of Unusual Mental Phenomena,** compiled by William R. Corliss, The Sourcebook Project, Glen Arm, Maryland, 1982.

32. Charles Panati, ed., **The Geller Papers: Scientific observations on the paranormal powers of Uri Geller**, Houghton Mifflin Company, Boston, Massachusetts, 1976.

33. Ken Wilbur, **The Spectrum of Consciousness,** The **Theo**sophical Publishing House, Wheaton, Illinois, 1977.

34. "Godel's proof," **Scientific American,** June 1965, p. 81-86
As Ken Wilbur puts it, "Thus logically as well as **physically** verification is not an absolute mark of reality. If all **is** to be verified, how do you verify the verifier, since he is part of **the** all?"

35. Erwin Schroedinger, **What is Life? and Mind and Matter,** Cambridge University Press, London, 1969.

36. Teilhard de Chardin, **The Phenomenon of Man,** Harper Torchbooks, New York, 1965.

37. D.T. Suzuki, **The Zen Doctrine of No Mind,** Rider, London, 1970.

38. Frederick S. Perls, **Gestalt Therapy Verbatim,** Real People Press, Lafayette, Indiana, 1969.

39. Frederick S. Perls, Ralf F. Hefferline, and Paul Goodman, **Gestalt therapy,** Dell, New York, 1951.

40. John White, ed., **The Highest State of Consciousness,** Anchor, New York, 1972.

41 J. Blofeld, trans., **The Zen Teaching of Huang Po,** Grove Press, New York, 1958.

42. R.E. Ornstein, **The Psychology of Consciousness,** W.H. Freeman and Company, San Francisco, California, 1972.

43. Joseph C. Pearce, **The Crack in the Cosmic Egg,** Julian, New York,

44. Andrija Puharich, **Beyond Telepathy,** Anchor Press, Doubleday & Company, Garden City, New York, 1973.

45. Jacques Vallee, **Passport to Magonia: From Folklore to Flying Saucers,** Henry Regnery Company, Chicago, Illinois, 1969.

46. Robert Bruce Lindsay and Henry Margenau, **Foundations of Physics,** Dover publications, New York, 1957. See p. 2-3 for the blunt statement that physics has nothing at all to say about a possible real world lying behind its concepts and equations. That is, physics is simply a model, and the assumption of a kind of reality is an interpretation and an hypothesis.

47. Ted Bastin, ed., **Quantum Theory and Beyond,** Cambridge University Press, 1971.

48. Edgar D. Mitchell, **Psychic Exploration: A Challenge for Science,** edited by John White, G.P. Putnam's Sons, New York, 1974.

49. Hector Hawton, **Philosophy for Pleasure,** Fawcett Publications, 1956, Fifth printing, June 1970. (A real gem.)

50. Jiro Kikkawa and Malcom J. Thorne, **The Behavior of Animals,** Plume, The New American Library Inc., New York, 1974.

51. Helena Curtis, **Biology,** Worth Publishers, Inc., New York, 1968 (fourth printing); p. 614-637 contains a good discussion of instinct, learning, and memory.

52. John Cunningham Lilly, **The Mind of the Dolphin: A Nonhuman Intelligence,** Avon, New York, Mar. 1969.

53. Isaac Asimov, **The Human Brain: Its Capacities and Functions,** Signet Science Library, The New American Library, Inc., New York, 1963.

54. R.W. Sperry, "The Great Cerebral Commissure," **Scientific American,** Jan. 1964, p. 42-52.

55. Michael S. Gazzaniga, "The Split Brain in Man," **Scientific American,** Aug. 1967, p. 24-29.

56. Roger Sperry, "Problems Outstanding in the Evolution of Brain Function," James Arthur Lecture, American Museum of Natural History, New York, 1964.

57. Jose M.R. Delgado, **Physical Control of the Mind: Toward a Psycho-Civilized Society,** Harper Colophon Books, Harper & Row, New York, 1971.

58. B.B. Kazhinskiy, **Biological Radio Communications,** Izdatel'stvo Akademii nauk Ukrainskey SSR, Kiev. 1962. Trans, available through DDC, AD 415676.

59. S.K Lisitsyn "New Approach to the Analysis of Electroencephalograms," in **Problems of Bionics (Selected Articles), p.** 16-25, DDC Report **AD** 730045.

60. Evert W. Beth, **The Foundations** of Mathematics, Harper Torchbooks, Harper & Row, New York, 1966. p. 481-518 contains a discussion of the "contradictions" of logic painfully noted by mathematicians shortly after the turn of the century.

61. Stanley Krippner and James Hickman, "West Meets East: A Parapsychological Detente," **Psychic,** May/June 1974, p. 51-55.

62. G.G. Globus, ed., **Consciousness and the Brain,** Plenum, New York, 1976.

63. Karl Pribram, **Emotion: the Search for Control,** McGraw Hill, New York, 1968.

64. Karl Pribram, **Languages of the Brain,** Prentice Hall, Englewood Cliffs, 1971.

65. Charles Hampden-Turner, **Maps of the Mind: Charts and Concepts of the Mind and Its Labyrinths,** Collier Books, Macmillan Publishing Co., New York, 1981.

66. Adam Smith, **Powers of the Mind,** Random House, New York, 1975.

67. Peter Tompkins and Christopher Bird, **The Secret Life of Plants,** Harper & Row, New York, 1973. (a real gem.)

68. The Louis Kervran material.

69. The Antoine Priore material.

70. Langston Day and George De La Warr, **Matter in the Making,** Vincent Stuart, London, 1966.

71. Sister Justa Smith, "Paranormal Effects on Enzyme Activity," Professional Paper No. 2, **Human Dimensions,** 1(2), 1972.

72. John Pierrakos, **The Energy Field in Man and Nature,** Institute of Bioenergetic Analysis, New York, 1971.

73. Jeffrey Mishlove, **The Roots of Consciousness,** Random House, New York, 1975.

74. Andrija Puharich, "Psychic Research and the Healing Process," in **Psychic Exploration,** ed. John White, Putnam, New York, 1975.

75. Andrija Puharich, **Beyond Telepathy,** Darton, Longman and Todd, London, 1962.

76. Lyall Watson, **Supernature,** Hodder & Stoughton, London, 1973.

77. Jule Eisenbud, "The Mind-Matter Interface," **Journal of American Society for Psychical Research,** 69(2), Apr., 1975.

78. George W. Meek, **From Enigma to Science,** Samuel Weiser, New York, 1973.

References Related to Antoine Priore's Work

1. Antoine Priore. "Procedeet dispositif de production de rayonnements utilisables notamment pour le traitement de cellules vivantes." Republique Francais: Brevet d'Invention P.V. No. 899.414, No.1.342.772,1963. For the U.S. patent, see Antoine Priore, "Method of producing radiations for penetrating living cells," U.S. patent No. 3,280, 816. Oct. 25, 1966.

2. Letter, R. Pautrizel to his colleagues at the University of Bordeaux, Sept. 11, 1979.

3. Letter, R. Pautrizel to his colleagues, Mar. 26, 1969.

4. Jacques Sylvain and Jean-Michel Graille, "Depuis quinze ans le "rayon Priore" divise le monde scientifique." [For fifteen years the "Priore Ray" has divided the world of science.]. **Sud-Ouest Dimanche,** Jan. 27, 1980.

5. "Affaire Priore: L'armee va trancher? [The Priore Affair: Will the Army resolve it?] **Sud-Ouest Dimanche,** May 20,1980.

6. "Affaire Priore: L'armee va tranchera." [The Priore Affair: The Army will resolve it.]. **Sud-Ouest Dimanche,** Apr. 12, 1981.

7. M.R. Riviere, A. Priore, F. Berlureau, M. Fournier and M. Guerin, "Action de champs electromagnetiques sur les greffes de la tumeur T8 chez le Rat." [Action of the electromagnetic fields on the graftings of the TB tumor on the rat.]. **Compt. Rend. Acad. Sci.** (Paris), 1964, **259,** 4895-4897.

8. M.R. Riviere, A. Priore, F. Berlureau, M. Fournier and M. Guerin, "Effets de champs electromagnetiques sur un lymphosarcome lymphoblastique transplantable du Rat." [Effects of Electromagnetic fields on lympheuplastic lymphosarcoma transplantable from a rat.]. **Compt. Rend. Acad. Sci.** (Paris), 1965, **260,** 2099-2102.

9. M.R. Riviere, A. Priore, F. Berlureau, M. Fournier and M. Guerin, "Phenomenes de regression observes sur les greffes d'un lymphosarcome chez des souris exposees a des champs electromagnetiques." **Compt. Rend. Acad. Sci.** (Paris), 1965, 260, 2639-2643.

10. G. Delmon and J. Biraben,"la croissance du carcinome de Guerin sous Faction de champs electromagnetiques." **Rev. Path,** comp, 1966, 3, no. 2, 85-88.

11. M.R. Riviere and M. Guerin, "Nouvelles recherches effectuees chez des rats porteurs d'un lymphosarcome lymphoblastique soumis a l'action d'ondes electromagnetiques associees a des champs magnetiques." **Compt. Rend. Acad. Sci.** (Paris), 1966, **262,** 2669-2672.

12. R. Pautrizel, M.R. Riviere, A. Priore, and F. Berlureau, "Influence d'ondes electromagnetiques et de champs manetiques associes sur l'immunite de la souris infestee par **Trypanosoma equiperdum."** [Influence of electromagnetic waves and associated magnetic fields on the immunity of the mouse infected with the Trypanosoma equiperdum.]. **Compt. Rend. Acad. Sci.** (Paris), 1966, **263;** 579-582.

13. R. Pautrizel, A. Priore, and F. Berlureau, and A.N. Pautrizel, "Stimulation par des moyens physiques des defenses de la Souris et du Rat contre la trypanosomiase experimentale." [Stimulation, by physical means, of defenses of the mouse and of the rat against the experimental Trypanosoma.]. **Compt. Rend. Acad. Sci.** (Paris), 1969, **268,** 1889-1892.

14. R. Pautrizel, A. Priore, F. Berlureau, and A.N. Pautrizel, "Action de champs magnetiques combines a des ondes electromagnetiques sur la trypanosomiase experimentale du Lapin" [Action of magnetic waves combined with electromagnetic waves on the experimental trypanosoma on the rabbit.]. **Compt. Rend. Acad. Sci.** (Paris), 1970, **271,** 877-880.

15. A.J. Berteaud, A.M. Bottreau, A. Priore, A.N. Pautrizel, F. Berlureau, and R. Pautrizel, "Essai de correlation entre revolution d'une affection par **Trypanosoma equiperdum** et l'action d'une onde electromagnetique pulsee et modulee." [Trial of the correlation between the evolution of a disease by Trypanosoma equiperdum and the action of a pulsating and modulated electromagnetic wave.]. **Compt. Rend.** Acad. **Sci.** (Paris), 1971, **272,** 1003-1006.

16. R. Pautrizel, P. Mattern, A. Priore, A.N. Pautrizel, and D. Bernard, "Etat de protection vis-a-vis de **Trypanosoma equiperdum** chex des souris splenectomisees et soumises a une stimulation physique." **ler Multicolloque Europeen** de **Parasitologie,** Rennes, 1 au 4 Septembre 1971.

17. R. Pautrizel, A. Priore, M. Dallochio and R. Crockett, "Action d'ondes electromagetiques et de champs magnetiques sur les modifications lipidiques chez le Lapin par l'administration d'un regime alimentaire hypercholesterole." [Action of electromagnetic waves and magnetic fields on provoked lipidic modiications in the rabbit by the administration of an alimentary hyperchloresterol diet.]. **Compt. Rend. Acad. Sci.** (Paris), 1972, **274,** 488-491.

18. G. Mayer, A. Priore, G. Mayer and R. Pautrizel, "Action de champs magnetiques associes a des ondes electromagnetiquea sur 1' orchite trypanosomienne du lapin." [Action of the magnetic fields associated with electromagnetic waves on the trypanosomian orchitis of the rabbit.]. **Compt. Rend.** Acad. **Sci.** (Paris), 1972, **274,** 3011-3014.

19. R. Pautrizel, A. Priore, P. Mattern, and A.N. Pautrizel, "Stimulation des defenses de la souris trypanosomee **par** l'action d'un rayonnement associant de champ magnetique et ondes electromagnetiques." [Stimulation of the defenses of the trypanosomized mouse by the action of a ray associated with a magnetic field and electromagnetic waves.]. **Compt. Rend. Acad. Sci.** (Paris), 1975, **280,** 1915-1918.

20. R. Pautrizel, A. Priore, P. Mattern, A.N. Pautrizel, and A. Capbern, "Guerison de la trypanosomiase chronique du Lapin a **Trypanosoma equiperdum** par l'action combinee de champs magnetiques et d'ondes electromagnetiques modules." **J. Protozool.,** 1975, **22,** no. 3, A 84.

21. R. Pautrizel, "La trypanosomiase experimentale: stimulation des defenses de L'organisme par des moyens physiques." **XVIIth Seminar on Trypanosomiasis Research,** Londres, 22-23 Septembre 1976.

22. R. Pautrizel, P. Mattern, A.N. Pautrizel, and A. Priore, "Effets des champs magnetiques et des ondes electromagnetiques modules sur la trypanosomiase experimentale." [Effect of magnetic fields and modulated electromagnetic waves on the experimental trypansomiasmis.]. **Ann. Soc. Beige Med. trop.,** 1977, **57,** 501-523.

23. R. Pautrizel, P. Mattern, A. Priore, A.N. Pautrizel, A. Capbern and T. Baltz, "Importance des mecanismes immunitaires dan la guerison de la trypanosomiase experimentale par stimulation physique." [Importance of immune mechanisms in the cure of the experimental trypanosomias by physical stimulation.]. **Compt. Rend. Acad. Sci.** (Paris), 1978, 286, 1487-1492.

24. R. Pautrizel, and A. Priore, "Un aspect spectaculaire du bioelectromagnetisme: permettre a l'organisme de se debarrasser d'une infection aig ue ou chronique sans l'aide d'aucune substance medicamentese." [A spectacular aspect of bioelectromagnetism: permitting the organism to rid itself of an old chronic infection without the aid of any medical substance.] **Communication presented to the 104 eme Congres National des Societes Savantes,** Bordeaux, 17-21 Avril 1979 — section Sciences, p. 112.

25. R. Pautrizel, and A. Priore, "Guerison de la trypanosomiase experimentale par association de champs magnetiques et d'ondes electromagnetiques," [Cure of the trypanosomias by associated magnetic fields and electromagnetic waves.]. **Communication presented to the Symposium International des Therapeutiques Ondulatoires,** Versailles 19-20 Mai 1979, p. 9.

26. R. Pautrizel, A. Priore, A.N. Pautrizel and P. Chateaureynaud-Duprat, "Guerison de la trypanosomiase experimentale par l'association de champs magnetiques et d'ondes electromagnetiques: une stimulation des defenses de l'organisme." [Cure of the trypanosomias by associated magnetic fields and electromagnetic waves: a stimulation of the organism's defenses.]. **Communication presented to the Journees Nationales Microondes - Colloque Hertzienne et Dielectriques,** Lille 26-29 juin 1979, p. 31.

27. David M. Rorvik, "Do the French have a Cure for Cancer?" **Esquire** Magazine, July 1975, p. 110-111,142-149. Excellent summary of the Priore Affair, with some details of the working of the machine.

28. J.B. Bateman, "A Biologically Active Combination of Modulated Magnetic and Microwave Fields: The Priore Machine," Office of Naval Research, London Report R-5-78, Aug. 1978. Comes very close when he states that "The possibility that some hitherto unrecognized feature of the radiation from a rotating plasma may be responsible for the Priore effects should not be dismissed out of hand..." Indeed, none of the persons who checked the machine or pondered over it knew anything about phase conjugation — which plasmas can do.

29. J.B. Bateman, "Microwave Magic." Office of Naval Research London Conference Report, ONRL C-14-77, 1977.

30. D.S. Greenburg. "The French Concoction." **Saturday Rev. Sci.,** May, 1978. p. 36-44.

31. Lord Zuckerman, "The great Bordeaux magnetic mystery machine." **Sunday Times Weekly Review,** Jan. 7, 1973.

32. Lord Zuckerman, "Pride and Prejudice in Science. William Randolph Lovelace Commemorative Lecture. **Aerospace Medicine,** 1974, 45, 638-647.

33. L.B. Bateman, "Staging the perils of non-ionizing waves." Office of Naval Research London, **European Scientific Notes,** ESN 32-3: 85-88.

34. R. Courrier, 1977. "Expose de M. le professeur R. Courrier secretaire perpetuel de l'Academie des Sciences fait au cours d'une reunion a l'Institut sur les effets de la machine de M.A. Priore le 26 Avril 1977.

35. M. Riviere, A. Priore, F. Berlureau, M. Fournier and M. Guerin, "Phenomena of regression observed on the graftings of a lymphosarcome in mice exposed to electromagnetic fields." Mar. 1, 1965.

36. Jean-Michel Graille, **Le Dossier Priore:** De Noel, Paris, 1984. Published in France.

37. G. Lakhovsky, "Apparatus with circuits oscillating under multiple wave lengths," U.S. Patent No. 1,962,565. June 12, 1934.

38. G. Lakhovsky, "Tube for producing multiple wave lengths." U.S. Patent No. 2,351,055. June 13, 1944.

39. Thomas H. Moray, "Electrotherapeutic apparatus," U.S. Patent No. 2,400,707. Feb. 1, 1949.

40. Robert C. Beck, "Extremely low frequency magnetic fields and EEG entrainment: A psychotronic warfare possibility?" Audiotape; presentation at the 1978 U.S. Psychotronics Association (USPA) Conference, Atlanta, Georgia.

41. T.G. Hieronymus, "History of radionics. Parts 1 and 2." Audiotape; presentation at the 1979 USPA Conference, University of Houston, Texas.

42. Robert C. Beck, "Extreme low frequency magnetic pulses and E.E.G. entrainment: Soviet Psychotronic Weapon?" Audiotape; presentation at the 1979 USPA Conference, University of Houston, Texas.

43. Al Bielek and William Bise, "A magnetic pacer." Audiotape; presentation at the 1980 USPA Conference, Dayton, Ohio.

44. Thomas E. Bearden, "Mind and matter interaction." Audiotape; presentation at the 1980 USPA Conference, Dayton, Ohio.

45. John Moray, "Sea of energy." Audiotape; presentation at the 1980 USPA Conference, Dayton, Ohio.

46. T. Galen Hieronymus, "Sunspots trigger earthquakes." Audiotape; presentation at the 1981 USPA Conference. Available from USPA, 3459 Montrose Ave., Chicago, IL 60618.

47. Al Bielek and Bill Bise, "Measurements of ELF and its parameters." Audiotape; presentation at the 1981 USPA Conference.

48. Martin Ruderfer, "Misconceptions in established science and their relevance to psychotronics." Audiotape; presentation at the 1981 USPA Conference.

49. Material on the Kaznacheyev experiments. See Kaznacheyev section for references.

50. Material on phase conjugation. See phase conjugation section for references.

51. Material on Ehrenhaft experiments. See Ehrenhaft section reverences.

52. Material on Kervran's work. See Kervran section for references.

53. Extensive proprietary scalar electromagnetics experiments by Frank Golden and John Bedini.

54. Material on Royal Raymond Rife's work. See Rife section for references.

References Related to the Australian Work

1. Private correspondence, Dr. B.L. Reid.

2. Private correspondence, Dr. S. Barsamian.

3. B.L. Reid, "Propagation of properties of chemical reactions over long distance in the atmosphere as seen by crystal growth pattern changes," **Australian Journal of Medical Laboratory Science,** Vol. 7, Feb. 1986. p. 30-35.

4. H.E. Anderson and B.I. Reid, "Vicinal Long Range and Extremely Long Range effects on growth of sodium chloride crystals from aqueous solutions containing protein," **App. Phys.** Comm, vol. 4, 1984. p. 217.

5. W.H. Campbell and J.M. Young, "Auroral zone observations of infrasonic pressure waves related to ionosopheric disturbances and geomagnetic activity," **J. Geophys. Res.,** vol. 68, 1963. p. 5909.

6. G. Chimonas and C. Hines, "Atmospheric gravity waves launched by auroral currents," **Planet Space Sci.,** vol. 18, 1970. p. 565.

7. F.B. Abeles, **Ethylene in Plant Biology,** Academic Press, New York, 1973.

8. G.I. Distler, **Jour. Cryst. Growth,** Vol. 3 & 4, 1968. p. 175.

9. G.I. Distler and V.P. Vlasov, **Thin Solid Films,** vol. 3, 1969. p. 333.

10. G.I. Distler, **Jour. Cryst. Growth,** Vol. 9, 1971, p. 76.

11. B. DeWitt, **Phys. Rev.,** 19C, 1975, p. 297.

12. W. Greiner and J. Hamitton. **Amer. Sci.,** vol. 68,1980, p. 154.

13. P. Davies and T. Birrell, **Quantum Fields in Curved Space,**

    Cambridge University Press, Cambridge, 1982.

14. P. Mitchell, Nature,vol. 191, 1961. p. 144.

15. A Rothen. **Proc. Nat. Acad. Sci.** (U.S.), vol. 72,1975. p. 2462.
16. L. Niemeyer, L. Betroniero, and H.J. Weismann, **Phys. Rev. Lett.,** vol. 52, 1984. p. 1033.

17. T.A. Witten and L.M. Sander, **Phys. Rev. B.,** vol. 27,1983. p. 5686.

18. T.D. Lee, **Particle Physics and Introduction to Field Theory,** Harwood Academic Publishers, New York, 1981. See particularly Chapter 16, "Vacuum as the source of asymmetry."

References Related to Royal R. Rife's Work

1. Royal R. Rife, "Bacteria," Apr. 28, 1939.

2. Royal R. Rife, "The filterable virus of carcinoma," Apr. 26, 1939.

3. Royal R. Rife, "The Rife microscopes," Apr. 28, 1939.

4. Royal R. Rife, "History of the development of a successful treatment for cancer and other viruses, bacteria and fungi." Allied Industries, Dec. 1, 1953.

5. Arthur Isaac Kendall and Royal Raymond Rife, "Observations on Bacillus Typhosus in its filterable state," **California and Western Medicine,** California Medical Association, Dec. 1931.

6. Arthur Isaac Kendall, "Filtration of bacteria; studies in bacterial metabolism," **Science 75,** Mar. 18, 1932. p. 295-301.

Arthur Isaac Kendall, "The filtration of bacteria," **Science,** Mar. 18, 1932.

8. E.C. Rosenow, "Observations on filter-passing forms...," **Proceedings of the Staff Meeting of the Mayo Clinic,** July 13, 1932.

9. E.C. Rosenow, "Observations with the Rife Microscope of Filter-passing forms of micro-organisms," **Science,** n.s., vol. 76, Aug 26, 1932. p. 192-193.

10. E.C. Rosenow, "Microdiplococci in filtrates of natural and experimental poliomyelitic virus compared under the electron and light microscopes," **Proceeding of the Staff Meeting of the Mayo Clinic,** 17(7), Feb. 18, 1942. p. 99-106.

11. E.C. Rosenow, "Observations of filter-passing forms of Eberthella Typhi (Bacillus Typhosus) and of the Streptococcus from Poliomyelitis," **Proc. Staff. Meet. Mayo Clinic** 7, July 13. 1932. p. 408-413.

12. E.C. Rosenow, "Transmutations within the Streptococcus-Pneumonococcus Group," **Journal of Infective Diseases,** vol. **14, 1914.**

13. "Powerful microscope makes very tiny objects visible," **Science Newsletter,** vol. 33, Jan. 22, 1938. p. 55.

14. "The Rife microscope or "facts and their fate'," Reprint No. 47, The Lee Foundation for Nutritional Research, Milwaukee, Wisconsin.

15. R.E. Seidel, M.D. and M. Elizabeth Winter, "The new microscopes," **Journal of the Franklin Institute,"** Feb., 1944. p. 103-129.

16. R.E. Seidel, M.D. and M. Elizabeth Winter, "Filterable bodies seen with the Rife microscope," Science Supplement, **Science,** Dec. 11, 1931. p. 10-11.

17. "Is a new field about to be opened in the science of bacteriology?" Editorial, **California and Western Medicine,** California Medical Association, Dec. 1931.

18. Christopher Bird, "What has become of the Rife microscope?", **New Age Journal,** Mar. 1976.

19. Peter Tompkins and Christopher Bird, **The Secret Life of Plants,** Harper & Row, New York, 1973.

20. Lida H. Mattman, **Cell Wall Deficient Forms,"** CRC Press, Cleveland, Ohio. 1974.

21. Georges Lakhovsky, **La Cabal: Histoire d'une Decouverte L'oscillation Cellulaire,"** G. Doin, Paris, 1934.

22. Georges Lakhovsky, "Apparatus with circuits oscillating under multiple wave lengths," U.S. Patentno. 1,962,565. June 12,1934. See also G. Lakhovsky," Tube for producing multiple wave lengths," U.S. Patent No. 2,351,055. June 13, 1944.
23. Georges Lakhovsky, **"L'oscillation Cellulaire," Ensemble des Recherches Experimentales,** G. Doin, Paris, 1931.

24. Harold Saxton Burr, **Blueprint for Immortality: The Electric Patterns of Life,** Neville Spearman Ltd., London, 1972.

25. George De La Warr and Douglas Baker, **Biomagnetism,** De La Warr Laboratories, Oxford, 1967.

26. Ruth Beymer Drown, **The Theory and Technique of the Drown H.V.R. and Radiovision Instruments.** (Private printing.). Artists' Press, Los Angeles, 1939.

27. Ruth Beymer Drown, **The Science and Philosophy of the Drown Radio Therapy.** Los Angeles, 1938.

28. Albert Abrams, **New Concepts in Diagnosis and** Treatment. Philopolis Press, San Francisco, 1916.

29. Albert Abrams, **Iconography: Electronic Reactions of Abrams.** San Francisco, 1923.

30. Jagadis Chandra Bose, **Response in the Living and Non-Living,** Longmans, Green & Co.; New York, 1902.

31. Jagadis Chandra Bose, **The Physiology of Photosynthesis,** Longmans, Green & Co.; New York, 1924.

32. D.M. Bose, "J.C. Bose's Plant Physiological Investigation Relating to Modern Biological Knowledge," **Transactions of the Bose Research Institute,** Vol. 37, Bose Research Institute, Calcutta, 1947-48.

33. "Invisible ultra-violet life frequencies made visible," **New Light on Therapeutic Energies,** Source/data unk., p. 51-55.

34. Wilheim Reich, **The Cancer Biopathy.** Orgone Press, New York, 1948.

35. V.M. Inyushin and P.R. Chekorov, "Biostimulation through laser radiation and bioplasma," Kazakh State University, U.S.S.R.

36. Philip Medley et al, "The filterable forms of bacteria," **Journal of Infectious Diseases,** vol. 48, 1931.

37. Gianni A. Dotto, "Method for constructing a thermionic pile," U.S. Patent no. 3,839,771. Oct. 8,1974.

38. Gianni A. Dotto, "Story of the Dotto Ring." notarized in Montgomery County, Ohio on Feb. 8, 1972. Certain parts of Dotto's theory, apparatus, and recommended treatment method suggest potential effects on recombinant genetic structures.

39. Gianni A. Dotto, "Electrostatic Wand," U.S. Patent No. 3,785,383. Jan. 15, 1974.

40. T.H. Moray, **The Sea of Energy.** 5th Edition. History and biography by John E. Moray. Foreword by Thomas E. Bearden. Cosray Research Institute, 2505 South 4th East, Salt Lake City, Utah 84115. 1978.

41. T.H. Moray, "Electrotherapeutic Apparatus," U.S. Patent no. 2,460,707. Feb. 1, 1949.

42. John Moray, "Radiant Energy," in **1st International Symposium on Non-Conventional Energy Technology,** Toronto, Canada. Planetary Association for Clean Energy, 1981. p. 316-319.

43. Antoine Priore's research and devices.

44. Wilheim Reich's orgone energy work and devices.

45. Radionics researchers' work and devices.

46. Jonathan Tennenbaum, "Soviet Work on Electromagnetic Pulse Weapons," EIR Special Report, **"Electromagnetic-Effect Weapons: The Technology and the Strategic Implications,"** Wiesbaden, Federal Republic of Germany, 1988.

47. Ron Iscoff, "Dye Lasers Used to Treat Blood," **Lasers & Optronics,** 7(3), Mar. 1988, p. 26-28.

APPENDIX I

The Case of Antoine Priore and His Therapeutic Machine: A Scandal in the Politics of Science

© 1984, 1988 Christopher Bird (Used by permission)

Forty- four years ago, in 1944, an Italian engineer working as a prisoner and forced laborer for the Germans in the huge submarine base in Bordeaux, approached a French police agent to plead for his **life.** He would be killed when the Germans left Bordeaux, he said, and since they were by that time obviously losing the war, the day of his execution was at hand.

The police officer, who also worked clandestinely for the French underground, told the engineer to get in his car, then simply drove him out of the base and introduced him to the 7th battalion of underground resistance fighters, in the nearby province of Dordogne. There he so distinguished himself in military operations that he was ultimately decorated by the French government.

It was due to his thankfulness to his savior, and his loyalty to his companions-in-arms, that Antoine Priore decided after the war's end to live out the rest of his life in Bordeaux. Thus he became the focus of one of the strangest, and most scandalous, chapters in the scientific history of France or any other nation.

Antoine Priore had earlier graduated from a small provincial school for electricity in Trieste, Italy and become a radar operator in **the** Italian Navy. During this period he observed what to him was an exciting anomaly: some oranges left in a room filled with electrical bric-a-brac had fallen into an assemblage where they seemed to have been preserved in the same fresh state they had enjoyed when **bought** off a fruit stand. Other oranges in the room, bought at the same time, were rotten and putrid.

Stunned by his observation, Priore dreamed throughout the war of one day working out an electrical means of conserving foods in **their** fresh state based on what he surmised was a new, and wholly unexplained, principle. Newton's apple had become Priore's orange.

Occupied during the day as a humble electrical repairman — and **projectionist** in a movie theater — the almost wholly self-taught **Priore** devoted all his free time and his meager resources to research. With the help of his war-time companions, some of whom had attained high rank in the Bordeaux police force, he was able to beg, borrow, steal, scrounge, or otherwise acquire a mini-warehouse of electrical and electronic components and parts. With these he put together a device worthy of Rube Goldberg. Exposing lentil seeds to a magnetic field of 225 gauss and electromagnetic frequencies of 80, 32, 3 and 10 Hertz, Priore's device caused the lentil plants which sprouted from them to grow 12-15 centimeters in length, as against only 5 centimeters for controls not subjected to the same treatment. He got similar results for tulips, asparagus and other plants.

Shifting his focus, he next irradiated fertilized hens' eggs, only to see the chicks hatch in 19 days, instead of the normal 21. Though he could not explain these astonishing results, he realized he had stumbled upon a process basic to the enhancement, or speeding up, of cellular growth.

It was at this point that one of his police friends introduced him to Francis Berlureau, the former Director of Studies at the School for Veterinary Medicine in Toulouse and, at the time of their meeting, director of the Bordeaux abbatoir. Priore asked Berlureau to supply him with various animal tissues for experimentation. For 10 years they worked together, Priore's free time allowing, during which Priore noticed he could get no electrical measurement from a cancerous bull's testicles. Since he realized that, in some way, his newly constructed device (no trace of which remains today, except for a snapshot of it) affected the electrical properties of cells, he put two and two together and his sum of four led him to believe that he might be onto an electromagnetic cure for cancer. Newton's gravity had become Priore's cancer cure.

Berlureau next allowed him to expose a cat with cancer of the mammary glands to radiation of his machine. To make absolutely sure that he was not exposing himself to mockery, the veterinarian had all the histological work done by his friend and colleague, a Professor Drieux at the famous Veterinarian School of Maisons-Allfort, near Paris. Drieux wrote a technical report proving that a tumor taken from a cat had, before treatment, started to become cancerous and, after treatment, had become benign.

By 1953, with the help of a doctor of general medicine, Maurice Fournier, Priore began treating human patients whose cancers had been judged hopeless. The huge file of cases maintained by Fournier, and filed with a notary until after his death, was subsequently mysteriously lost. But a few details were preserved in letters discovered in an old dog-eared file.

Some of these dating to the year 1954 concerned a 12-year old boy, Alain B., whose diagnosis wavered between one of reticulo-histio-sarcoma and a malignant form of Hodgkin's disease. The boy was taken by his parents to Priore, who irradiated him. Though the exact nature of the radiation was not known, 12 years later a Bordeaux physician, after a medical examination, certified that the boy, now become a man of 24, was free of disease.

A second case unearthed from the old file indicated that a patient with cancer of the larynx was able to avoid a laryngectomy and be totally cured after Priore's new ministration.

Fascinated by the principle which he suspected must lie behind the strange Priore Ray, Dr. Berlureau tried to get some Bordeaux University physicists interested in the problem but was laughed out of their offices. He next turned to cancer specialists, beginning with Professor Lachapele, the Director of the Bergonie Foundation, a prestigious center for cancer research, to whom he proposed animal experiments to prove the efficacy of Priore's methodology. His plea met with a stony affirmation on Lachapele's part to the effect that he and his colleagues had no need of the new discovery, inasmuch as "all the patients treated in his hospital were cured and departed in perfect health." As if bound in the chains of his curt reply, years later Lachapele was to become one of the bitter adversaries of Priore's pioneering research.

Only somewhat discouraged, Priore kept up his momentum. He went on to build a new and more complicated version of his treatment device, called the P-l, over the next year. When it was finished he secretly and unofficially began to treat dozens of cancer patients who had been given up by their doctors as incurable. At his funeral in March of last year, among the crowd of mourners was, it is said, a small platoon of older people who had been cured of their terrible afflictions by Priore in the 1950s.

While his findings excited him, he nevertheless felt tremendously frustrated that he could apparently get no one in the world of medicine or science to pay attention to them. Undaunted by his previous rebuffs, his friend Berlureau next introduced the Italian at the end of 1959 or the beginning of 1960 to Professor Tayeau, vice dean of Bordeaux's Medical Faculty. Unlike Lachapele, Tayeau behaved as a true physician and scientist. He sent Priore to two researchers, Biraben, head of the Faculty's Department of Pathological Anatomy, and his assistant, Delmon. The two had been working together on cancerous rats for two years—specifically on animals grafted with T-8 tumors, discovered by the internationally famous team of Guerin and Oberling in Paris, which had proven to be intractable to any form of treatment yet known. To their utter surprise, the tumors in the rats treated with Priore's machine were reduced in volume by 60%, marking the first time in the history of cancerology that the virulent T-8 tumor had in any way been affected by any form of treatment.

Knowing that the mayor of Bordeaux, Jacques Chabans~Delmas-who has kept his post until this day, and was soon to become prime minister of France-- was most interested in the work of Priore (who, he too, had known as a fellow resistance fighter), they also informed Chaban.

Promptly Chaban convoked not one, but two, commissions made up of Bordeaux and Parisian scientists to study the Biraben-Delmon results in detail. Both commissions rejected Priore and his machine out of hand, and without appeal. It is curious that, in the science of our day, a result, undeniable though it may be, seems to have no hearing unless and until all means to effect it can be adequately explained. It was for this ostensible reason that the two commissions decided to so adamantly reject the research: Biraben and Delmon could not explain the nature of the radiation engendered by the Priore device.

One can stress the word *ostensible* here because the principal reason for the rejection lay elsewhere. The decision by the first commission was, in fact, hardly unanimous. But among its members was the same Professor Lachapele who had refused Berlureau's plea for assistance. His opinion was that even the results themselves were of little value because they were obtained, not on spontaneously arising, but on grafted, cancers. The fact that no treatment whatsoever had ever affected a T-8 tumor was totally discounted. As the sole cancerologist on the commission, Lachapele's dictum was preponderant.

When he learned that the rejection of the first commission had actually been a split decision, the Bordeaux mayor asked for the formation of a second commission to re-examine the problem. Fearing a reversal, Lachapele was able to get one of his colleagues, Professor Courtial, director of the Radium Institute in Paris, and one of the so-called top authorities of French cancer research, named to it. It was all but impossible for the other physicians on the new commission now to outvote not one, but two, cancer specialists, so again the antagonists won the day.

At no time did either of the commissions bother to interview Priore himself or to run a supplementary experiment under their own control.

This seemingly incomprehensible attitude on the part of scientific authority was only a foretaste of what was to come, again and again, over the years. Biraben and Delmon went on to do new experiments. They modified either the time after grafting that the radiation was applied, or the length of its duration. This time their efforts were crowned with unequivocal and complete success. The tumors stopped growing and, when still living cells were excised from them and implanted in healthy control animals, none of them became malignant.

Though these results should normally have fascinated any academy of medicine or sciences, the two researchers did not publish them. Why? The reasons horrify or disgust. It seemed that Biraben was simultaneously preparing an examination for the *agregation*, the highest French academic degree leading to a senior university teaching post. In charge of the committee to pass on, and award, this degree was none other than that same Professor Lachapele who told him: "Either you get the degree, necessary to your professional advancement, or you publish your research paper. But not both!" Discouraged, Biraben ceded to this demand but nevertheless continued to work on the research that looked so exciting and promising.

Most mystifying to him was how the machine operated to achieve its startling results. At the 3rd Congress of Biometerology held in 1963 in the Pyrennees mountains, a New York City researcher by the name of Kenneth McLean reported he had been able to obtain regressions on tumors and improve the health of cancer patients by using a magnetic field of a strength of 3000 gauss or more. Acting on this hint, Biraben and Delmon made an electromagnet that put out a field of 4,500 gauss and tried it out on the T-8 tumors but without the slightest success. Obviously, something other than a simple magnetic field was at issue.

In 1966, after others had had the same success with the T-8 tumor by irradiating it with the "Priore Ray," the two scientists finally published a memoir in the Revue of Comparative Pathology in which they stated that neither magnetic fields nor X-rays had any effect on the T-8s and that "only certain devices associating a magnetic field with high frequency waves seem at present to reveal therapeutic properties..."

Their conclusions were too late for, by that time, a campaign to stamp out Priore and his electromagnetic approach to cancer cure was well underway, a campaign that has lasted right up to the present moment.

The all-powerful Lachapele had sealed the fate of the Priore device as far as the local Bordeaux medical community was concorned. Veterinarian Berlureau and Priore next decided to carry their case to Paris. They contacted Professor Guerin at the cancer Institute at Villejuif, the leading French center for cancer research nnd the equivalent of the American National Cancer Institute in Bethesda, Maryland. Guerin, one of the discoverers of the T-8 tumor, which for the first time had been stopped in its tracks by the Priore device, courteously received his guests and heard them relate the whole story of how the device had come into being, starting at the point. when Priore had seen the oranges strangely preserved by some unaccountable electromagnetic effect.

Guerin was sufficiently impressed that he assigned his colleague, Marcel-Rene Riviere, to delve into the whole question. For two years, Riviere, who also had teaching responsibilities at the University of Rennes in Brittany, unremittingly worked to corroborate the Biraben-Delmon findings. On 9 December 1964 a note was sent for publication in the **Proceedings** of the French Academy of Sciences detailing the research and modestly concluding: "... as of now, one may already state that our first observations show that electromagnetic fields used can lead to most interesting data from a point of view of the biological behavior of grafts and their therapeutic action on experimental tumors."

Riviere next decided to see if the Priore Ray could affect another tumoral form that had never been affected by any therapeutic method, the 347 lymphoblastic lymphosarcoma. The results were even more spectacular than for the T-8 tumor. The effects produced were of broader scope and took place more rapidly. A second note was sent to the Academy for publication. The conclusion read: "We can now already affirm that our research offers proof that electromagnetic fields are capable of producing effects on quite different types of neoplasms."

At this point one of the key characters in this extraordinary drama must be introduced. There might have been no drama at all without his appearance on stage. This personage was Robert Courrier, an eminent endocrinologist, who had been named, while still in his 30s, a full professor. Courrier was now perpetual secretary of the Academy of Sciences and later would become President of the Academy of Medicine. Because no scientific paper can be accepted by an academy unless introduced by one of its members, Riviere would have had no chance to see his work so prestigiously published had not Courrier, who knew Riviere well, since he had shepherded him through the winning of his doctorate, taken the responsibility for its introduction.

It was Courrier who, at this point, also took up the cudgel to interest various highly placed French organizations responsible for the administration of scientific projects and their funding. Thus, ho sent a personal letter to the French Minister for Scientific Atomic and Space Research, who immediately offered to try to make funds available for further research on and with the Priore Ray. He also personally asked the Director of the CNRS (National Center for Scientific Research, which coordinates and oversees all such activity in France) to receive Priore and Riviere.

That this meeting was, in its way, somewhat of a disaster, can be explained in part only by a brief resume of the complex character of Priore himself. Priore throughout his life had great difficulty making himself understood in the French language and, as the **years** went by, he even forgot how adequately to speak his own mother tongue, Italian. Added to these twin impediments was his lifelong fear that his discoveries and inventions were prone to being stolen, a fear which led him never to fully explain the exact nature of the complex radiation emitted from his machine, far less the settings which controlled its various parameters. Whether Priore would not, or could not, exactly explain the functioning of his invention (which, as we shall see, went through several increasingly complex generations) is a question to which no precise answer has been given. It would appear that Priore was an excellent engineer gifted more with a God-given intuition than with school-book reasoning and logic. In short, Priore had a combination of talents that could remind one of the same enigmatic personality that was Nikola Tesla, the deductive reasoning behind some of whose discoveries has never fully been unravelled.

Highly placed scientific administrators are neither comfortable with, nor sympathetic to, what they see as self-appointed geniuses who have not run the same academic gauntlet through which they themselves had to pass. Thus the CNRS director took aversion to Priore's somewhat incomprehensible, yet fairly prolix explanations of his technology and only recommended that a physicist be sent to look over his device to properly decipher its working. At the same time, the Minister, together with the head of the general delegation for Scientific Research (DGRST) — still another key body in the administration of the French scientific decision-making process — let it be known to Robert Courrier that they had not understood a tingle thing about Priore's invention despite his best efforts to present it.

Advancing one more step into what was to become for him a 20 year-long expedition into a jungle of scientific intrigue, Courrier next resolutely decided to send to Bordeaux one of his most trusted laboratory workers, Madame Colonge, to repeat Riviere's experiments under her personal supervision. The DGRST director fully Concurred with Courrier's decision, while letting slip his admission that he strongly suspected that Riviere might well have been duped in some manner by Priore. When Courrier asked the minister for travel funds for Madame Colonge, he was refused with the dry remark that such a request was "premature." The now angry Courrier telephoned to reply: "You've been spending millions for programs and hypotheses about the cancer problem. Riviere has been presenting you with facts!"

The physicist who had been sent to try to elucidate the functioning principles of Priore's device, reported that he could make neither "head nor tail" of the machine.

Madame Colonge's experimentation was as prolonged as necessary. She was so meticulous that, in order not to take her eyes off the experimental animals for an instant, she limited her lunches to sandwiches eaten in the laboratory. She returned, profoundly impressed, to Paris.

Nor was Riviere idle during this period. He decided to experiment with the L-52 lymphosarcoma, a tumor similar to, but even more malignant than the 347. This time, he used not rats, but mice, as hosts for the grafts. So successful were his results that, this time, Courrier decided to bar no holds. Instead of simply having a note published in the Academy Proceedings on the quiet, he decided to present it personally, orally, and in all solemnity, before his fellow academicians at an official meeting scheduled for 1 May 1965.

That date was, and is, a turning point in what came to be known in France as the "Priore Affair." From then on the whole French, and even the international, scientific community could be divided into a minority and a majority group, the first that believed in the research, the second that did not know enough details about it, did not or would not believe, or simply didn't give a damn.

Before Courrier could make his presentation, its scheduling and subject were inadvertently and prematurely leaked to the press. Immediately thereafter, a horde ofjournalists arrived in Bordeaux. After one or two of them managed to all but force entry into his lab, Priore closed its doors and, with the help of his friends, wrote a printed press release that stressed his thankfulness to the many people who had helped him over the years rather than providing any comprehensible details about the machine he had brought to birth. Stymied, many of the newsmen travelled across town to seek an explanation from its leading cancerologist, Professor Lachapele, who informed them acidly that the machine was all but useless and unworthy of their attention or their time.

The journalists' reports, founded as they were on rumor of outright lies, roiled the pages of their newspapers and magazines in such a way that they either over-exaggerated the potential or a forthcoming cancer cure, or came close to billing Priore as just one more cancer-cure charlatan. All of which so alarmed, among many others, Dr. Wilhelm Bernhard, world specialist in electron microscopy, that he called his friend Courrier to warn him that his forthcoming presentation to the academy might put his hard-won reputation at risk as well as those of Guerin, Riviere and the Villejuif cancer institute itself.

In the journalistic melee, no one had bothered to read the declaration carefully issued by Riviere from Rennes, where he was occupied with his university courses, which formally stated: "Our experiments are of real interest. Much more experimental research has of course to be done before any therapeutic application on human cancer victims can even be considered. It goes without saying that this will take a certain time and no little effort of many types, both scientific and financial. Our work, as fascinating a perspective as it might hold, in no way, therefore, allows anyone to offer the public hope which could only lead to deception at the present time."

On May Day, Courrier gave his report to an Academy assembly hall crowded with scientists, newspapers and television reporters, photographers and an unusual number of curious bystanders. Accompanied with slides showing histological details, and animals before and after treatment, his lecture was heard out in almost tomb-like silence. When the lights came on again, he announced that he had personally checked the validity of Riviere's findings through the offices of his personal assistant, Madame Colonge. He then went on to say that he had taken the responsibility of presenting three notes to the Academy for two reasons. The first was a ringing declaration and a challenge to critics and skeptics of every stamp. It reads "When it is a question of a problem as serious as that of cancer and when one sees a little light beginning to dawn, one has the obligation to see what this light might represent. One has no right to snuff it out before learning what it may be worth."

The second was a tribute to his colleagues who had done the pioneering work, particularly Guerin, Riviere and Madame Colonge, and a statement of the essence of the problem to be faced down the road. It read: "Attention must naturally be given to the apparatus which Monsieur Priore has conceived and constructed. It has apparently already been examined by several physicists. It is found to be too complicated. While that may be possible, it is nevertheless a fact that Guerin and Riviere have obtained results with it that had to be made public. What is emitted from such an apparatus? I hope Monsieur Priore will allow disinterested physicists to study it at their leisure, for Science cannot tolerate apparatuses enveloped in mystery." Then, as almost a footnote to the history of the moment: "The biological action of magnetic fields is the object of intense research in the United States. In specialized institutes, the influence of these fields on tissue cultures, microbes, plant forms, diastases and certain tumors is under study. Up to now, the results obtained on grafted tumors seem less significant than those which have here been presented."

After Courrier sat down, a leading cancer specialist, Professor Lacassagne, rose to ask snidely why the notes had included no bibliographical references on work done on the bio-effects on tumors from electromagnetic fields, and criticized the experimentation as "impromptu." When Courrier denied this allegation as ludicrous, Lacassagne stalked out of the assembly hall in full view of the audience.

The meeting caused a new eruption of media reports which unfortunately accented one of three aspects of the problem at the expense of the other two. These were 1) the hope that a miraculous cure for cancer was in the offing 2) the contradictory, not to say discordant, reception of the data by various academics and 3) the enigma of Priore's personality.

Remarkably, no serious discussion among the scientists present at the meeting ever took place. This led a foreign scientist, present in Paris at the time, to remark: *"I don't understand. Here is a report given to the most authoritative scientific body in France by one of the most respected and eminent of its members and it is publicly subject to doubt without that leading to any reaction whatsoever."*

The General Delegation for Scientific Research was at this point still open to the idea of providing funds for more research with the Priore Ray. The big stumbling block, however, was one related to niceties involved in relations up and down the scientific hierarchy. To open the way to the allocation of such funds required the approval of the Delegation's own section for cancer research and that section was headed by none other than the same Professor Lacassagne who had so rudely walked out of the Academy's assembly hall.

At the same time the General Delegate diplomatically covered himself by suggesting to Robert Courrier that he had to have more information underscoring the potential importance of the research accomplished. Courrier told him to simply re-read the three notes he had presented to the academy. His matter-of-fact, yet terse, come back then elicited his invitation to a full-dress meeting of scientific experts at the Institute for Scientific Cancer Research.

In this short historical account we obviously cannot go into the ins and outs of what transpired at this meeting or any of the many similar meetings which followed it. A paragraph in a brilliant book, four years in the writing, by the courageous Bordeaux journalist, Jean-Michel Graille and entitled: **Dossier Priore, A New Pasteur Affair** (of which this account is but a tenuous synopsis) must suffice to pointedly characterize the nature of the problem in its most general sense.

Writes Graille: "To read what follows in this chapter might well seem tedious: an enumeration of names and titles, the content of a debate held at an administrative meeting, personal remarks by one ranking personage or another, exchanges of letters following the meeting itself and the official report which came out of it. Tedious but indispensible for not a few reasons. It is important to know who were the participants at this meeting and what of these participants each was trying to represent. It is important to know how such scientific meetings go about their business at the 'top level,' And, finally, it is important to learn about and to understand, in the particular case of the Priore Affair, the behavior and reactions of all concerned. A reading of all this could be difficult (and it won't be the only such passage in this book) yet it is necessary to understand the essence of the dossier in order to be able to create for oneself as clear and well-motivated a personal opinion about it as to subsequently be able to discuss it, or to hear it discussed, with a thorough knowledge of the facts."

In this single paragraph, Jean-Michel Graille has, in my opinion, pointed to both the nub and the difficulty in getting at the essence of the real facts behind a case such as that of Priore's that are so important to its proper understanding, an understanding which can be painted against the backdrop of the history of science and the backdrop of human pettiness and maliciousness or human courage and magnanimity.

One of the participants, Professor Andre Lwoff, soon to become n Nobel Laureate for his work in virology, was violently against the meeting's central issue: namely, whether or not funds should be spent to build a new and better Priore machine. Not only did Lwoff aver that the three notes presented to the Academy never should have been published, but he also opined that since all the work was done, not on spontaneously generated but on grafted cancers, the effects of the machine were hardly impressive. He later added in writing that 1) the patents issued to Priore for his device were nothing but a web of nonsense, 2) the machine itself could never be duplicated based on any description given for it by its inventor and, in a repetition of his oral remarks, 3) the fact that only cancer grafts were experimented with was nothing to shout about. He strangely added that because the animals who had been irradiated subsequently were able to entirely reject new grafts, the whole phenomenon offered no proof that cancer cells could be killed while healthy cells were not. The whole thing came down to a question of immunity, he said, as if that were not of the greatest possible importance.

To which, in due course, Guerin and Riviere replied: "It has been claimed that our experiments are valueless because they were carried out on grafted tumors and that other therapeutic measures were known to get rid of such tumors and their metastases. *We defy those persons who have made such affirmations* to prove, *with the use of such other measures, that animals infected with T-8 tumors can be cured at a percentage rale identical to those obtained by using the device which Monsieur Priore has developed."*

Not a soul has responded to this challenge, then or since.

A second cancer expert at the meeting, a woman of great influence, resorted only to the cavil that the experiments had been of doubtful quality since none of the animals had been *weighed.* The fact that those same animals had survived normally lethal cancers seemed not to have *weighed* with her.

There were many more observations of the same ilk. They seem atrociously paltry, trifling and picayune coming from professionals who, if they no longer believed in the Hippocratic oath to which they once swore, are considered by the public in general, and by cancer patients in particular, at least to be concerned with seeing what a little light on the problem might reveal before extinguishing it, as Professor Courrier expressed it.

At the same time, we must not forget Priore's decidedly difficult personality. He was an inventor determined at all costs that his invention be developed for the benefit of humanity, yet anxious that that same humanity not steal it from him. As author Graille puts it, "His conceptions and attitude directly or indirectly conditioned the overall essence of this affair. Full of enthusiasm, from the very day he discovered that the ray he had developed had a curative effect on a cancerous cat, he developed a single-minded fixation on cancer One could understand and sympathize with him on this score. Here he is, a little Italian immigrant without money or means, and he is going to offer the world a cancer cure. He is so convinced that he wants to move ahead to doing just that. He will never understand or accept the exigencies of Science or Medicine. For him, experiments, controls, verifications and parallel research are a waste of precious time. 'I've made machines which cure cancer. Take them and treat cancer patients. Don't bother with the rest.' Such would be a summation of his point of view."

Through the efforts of persons kindly disposed to the inventor, this point of view was softened and he came finally to understand the-necessity for what has been called scientific rigor, on the other hand. another aspect of his character never changed an iota. This was his determination to preserve the secret of his invention, motivated first of all by his unshakeable desire that it be developed in Bordeaux, the city of his adoption, for the citizens of that city. Deeply rooted was his belief that if he made his secret public, the machine would be taken from the Bordeaux region and further developed by Parisians, those who considered themselves to be in the penthouse of the scientific edifice. Once this was accomplished, he would likely not have one more word to say about the matter. Therefore he continued jealously to conserve his secret and put confidence in nobody.

As Graille generously concedes, he may well have been right. and adds: "All his life he had to go up against men, whether scientists or industrialists, who had but one idea in their heads: to get to the bottom of the inventor's secret in order to build for themselves a machine which they then could exploit for their own account, for their own glory. Many such 'Priore Machines' were to be actually built more or less surreptitiously or clandestinely. Not one of them ever worked."

While one might easily accuse Priore of a limited view, the horizons of the researchers themselves were certainly not as broad us they might have been. Those involved in bio-medicine were content with the results produced by the machine, the workings of which were of no concern to them. A black box, as it were, emitted a ray that definitely affected experimental animals. At the same time, as researchers specifically interested in the cancer problem, they never gave a thought to what the Priore Ray might accomplish in the wider clinical domain of other afflictions.

As for the physicists, they were seemingly not up to the task of comprehending a complex radiation that had miraculously sprung, as from the head of Zeus, out of the intuition of a man they considered to be an undereducated and all but illiterate gadgeteer. Still others, whether physicists, biologists, doctors of medicine or specialists in a dozen other fields, were willing to throw the baby out even before it went into the bath water. In their eyes Priore was just a nobody.

Behind the scenes, many of these scientists resorted to using the press to achieve their own ends. Thus, the chief medical chronicler for Le Monde (the French New York Times), herself a doctor of medicine, was led to write outright lies about the Priore Affair—specifically and falsely stating that cancer patients had been treated with the Priore Ray in the clinic of Professor Lachapele in Bordeaux with not only negative, but disastrous, results.

On the other hand, a journalist for another leading Paris daily, Le Figaro, scrupulously conscious of his responsibility to fairly report what was going on, aptly wrote: "We would like to see at least one thorny point clarified as soon as possible. Several years ago P'rofessor Biraben of the Bordeaux Medical Faculty (who at that time had not become a ranking professor) was involved with the Priore device. According to certain reports from medical circles, his results seemed, even at that time, to have been already quite positive on small animals and he seems to have written a report to that effect, He was advised by highly placed authorities "to keep quiet" and stop talking about this affair. If this turns out to be true, it would be a veritable medical scandal to be judged in the harshest terms."

Could one have put it more succinctly?

The foregoing is to present something of the flavor of what was transpiring in the wide world far removed from the laboratory of

Priore who, at the time unaware of it, was revelling in the fact that his machine had been successfully used by high-ranking French cancerologists and its results reported in three separate notes to the Academy of Sciences.

His courage was also more than buoyed by the arrival on the scene of the commercial director of a large French industrial firm specializing in the intricacies of manufacturing glass components. This man had heard that Priore needed a large tube that was beyond all existing norms and perhaps did not exist anywhere in the world. This tube, it can be stated, contained a rare gas, neon, which when excited into a plasma, seemed somehow to convert the various electromagnetic inputs into a single Priore Ray which surged from the business end of the tube. In the tube were an anode and cathode. Peculiar to the anode was that it had to *rotate* to produce the desired biological effects and this is but one of the anomalies in Priore's equipment which physicists and bio-physicists have to this day been unable to explain.

The manufacturing company, a subsidiary of the internationally known company, Saint Gobain, was looking for a new product. The commercial director thought the new tube might fill the bill, particularly if it could be adapted to a machine that might ultimately cure cancer, a product that indubitably would have an enormous market across the world. There were plenty of problems with regard to the tube, notably those of its large dimension, its resistance and its conductability. When the tube was finally made, it now seemed that. Priore would have to explain his discoveries to the scientists of the company that had made it. One of these was sent to elicit such an explanation but was, so to speak, "shot down in flames" by Priore. So a second attempt was made by Ivan Peyches, a senior executive of the company, and president of the Society of Civil Engineers of France, who made a detailed investigation of the device. His reports were subsequently lost, but there remained an article he published in a leading French journal, Sciences and Technics, a short time before his death in 1978. It bore the intriguing title: "What Are So-Called Paranormal Phenomena?"

In it the engineer wrote: "There was so great an accumulation of components capable of having some kind of action, and being unable to work separately, that the results of measurement were limited to proving that there were no specific rays that issued from the tube (Priore talked about canal rays), no more than there were any X **rays.** On the other hand one could detect a magnetic field which was the end result of a field proper to the tube and of the magnetic field of a solenoid that constituted the experimental chamber, an electromagnetic field with a frequency of 16 megacycles (19 meters) and a high frequency field (metric waves), the whole being pulsed at a very low frequency of an order of one per second. It was impossible, in such an imbroglio, to determine what was necessary and what was sufficient. Priore maintained that the simultaneous action of his various generators was indispensible to achieving his effect."

Peyches then went on to relate how he tried to persuade Priore to offer a more precise definition of his thinking about the workings of his device. He wrote the inventor: "At this point, I would say that all reticence on your part, which in your eyes would be justified by the fear of seeing yourself partially dispossessed of your work, would be of far greater detriment to you than any safeguard of your interests. Moreover, since it has become a question involved in public health, you are no longer entirely your own boss...you absolutely must bring all this to the clear light of day and I don't believe you can do it alone...You must supply all the characteristics so that third parties can reproduce your results." Then, he concluded by citing the words of an academician: "Many phenomena are rejected by the scientific world because they are considered irrational: But it is not B proof of scientific honesty to refuse a priori to try, out of homage to truth, to have a look at them and perhaps to understand them. Will Science one day be able to abandon its taboos?"

It was Peyches' final conclusion that, in the end, Priore was a man of genius who knew absolutely nothing about what occurred in his machine from the scientific point of view. The company which he represented no longer exists since it was bought out by the American firm of Corning Glass.

Industrial interest in the Priore device was not limited to the Saint Gobain subsidiary. Next into the lists was a company in Anguouleme, Leroy-Somer, which specialized in electric motors, generators and later was to branch out into solar power. Its president, Georges Chavanes, took the initiative to write to Priore in 1965 that his company was interested in providing some of the complex electrical equipment needed by the inventor, more particularly high-powered generators, on the condition that Priore move his operation to the company seat at Anguouleme. When the inventor categorically refused, Chavanes tentatively agreed to build a factory to manufacture the Priore device in Bordeaux itself.

The alliance between Leroy-Somer and Priore, shaky at best, lasted two years and blew up on Holy Thursday of 1967. The period was a stormy one for both parties to the agreement. Priore did his best to convince Chavanes to commit himself to building a huge machine with a magnetic gauss strength of 10,000 gauss. In the end he got one that put out only 920 gauss, not much stronger than the machine he had already built which put out 620 gauss. Since the field of action increased with the gauss strength, Priore reasoned that a machine of literally behemoth size would be able to irradiate the whole, or every part, of a human cancer victim lying on a stretcher, whereas the smaller machines had been effective only for small animals or for treating a limited portion of the human body.

Chavanes and his company were aware that it would be a tremendous financial burden to contemplate building the larger machine. So they went ahead with plans for the smaller one while at, the same time putting great pressure on Priore himself to make him feel that he was the least important cog in a new gear, in fact that his status was reduced to being a simple employee of Leroy-Somer. In Graille's estimation, this lack of psychological finesse on Chavanes' part constituted what he called "the blackest pages in the Dossier Priore."

Even the smaller machine was to cost about half a million dollars, a price which today, due to inflation, could be tripled or quadrupled. During a stage in which an intermediate machine was designed by the chief Leroy-Somer engineer, Ribeau, a machine that never did function properly, Chavanes all but forced Priore, who was heavily in debt, to sign a contract which was falsified. The falsification was a matter of one word which was changed in the contract. In a phrase reading that an exclusive license of patents, and subsequent patent modifications, would accrue to the company "for all countries solely for therapy on cancers concerning animals and humans," a word was inserted by hand so that the phrase read. *"concerning particularly* animals and humans" implying that other uses of the machine, whatever they might turn out to be, would also accrue to the company. This one word change was amended on Priore's copy of the contract by calling the word "particularly" a "nullified word," but on Chavanes' copy it was called an "added word."

Leroy-Somer believed it was sufficiently well positioned in the driver's seat to be able to deal on behalf of Priore himself with the French governmental institutions, mainly the General Delegation, concerned with the funding of the new machine. When Priore learned of Chavanes' contact with the General Delegation he wrote a letter informing it that no one had the right to deal in his name. Nor did Chavanes even attempt to cut the Saint Gobain subsidiary, which alone could supply the tube, key to the device's functioning, in on the government funding.

In the meantime, no less a figure than Professor Kastler, soon to win the Nobel Prize in Physics, came down from Paris to inspect. the existing Priore device. He brought with him Delmon, who, we recall, had worked with Berlureau on the first animal experiments and who

NOW, it turned out, was trying to build his own version of a Priore device on the sly without telling Priore. Kastler's bringing Delmon with him to Priore's lab so angered Robert Courrier that he told the physicist he had committed a real gaffe. He also convinced Kastler that Leroy-Somer should build a machine with a power of at least 5000 gauss, but Chavanes refused. There seemed to be no harmony of outlook between the leading industrialist concerned, on the one hand, and the top physical and biological scientists on the other.

While all these, and many more, peripatetics were proceeding, Priore's sister in Italy came down with cancer. Beside himself with grief, Priore informed all concerned to commit themselves either to building an intermediate machine correctly, under his supervision or, better, the 5000-gauss machine, and to do this in time to save his sister, or he would wash his hands of the entire matter. Confronted with this ultimatum, the company began to work round the clock to perfect the intermediate machine but engineers involved, believing themselves to be more adroit with respect to its design than Priore, left out a host of what, to them, were unnecessary components. The result was that when the machine was first put to trial, most of the components burned out or otherwise failed, and the machine itself became a useless pile of rubble.

Shortly thereafter, Priore's sister died of cancer. Her grief-stricken brother went into what amounted to total isolation, unwilling to talk to a soul.

The whole Priore affair might have ended at that point, in the early part of 1967, were it not for the entry onto the scene of a key figure, Professor Raymond Pautrizel. Born on 3 June 1916 in Basseterre, capital of the French Carribean island of Guadeloupe, at forty years of age he was on the Faculty of Medicine at Bordeaux. He soon became known, world-wide, as the "father of parasitological immunity," a title he never accepted, saying that, if others had awarded it, it was simply because "he had searched through old scientific publications to find ideas that were as valid for modern research as they were forgotten by modern researchers." And he later was quoted as adding: "It is really too bad that researchers today don't pause from time to tome to dig into studies made by their predecessors, some of which were performed even decades ago!"

Professor Pautrizel was awarded the first academic chair in France for immunology, and later a special unit was created for him for parasitological immunology, a subject which is both simple and complex. The simple part involves the fact that various immunological techniques can be applied to diagnosing specific parasites that have invaded an organism in order to develop preventative actions against them via vaccines, or curative actions via serums.

When invaded by parasites, organisms react by creating antibodies, specific substances aimed at killing the invaders also known as antigens. These antibodies are liberated, like an attacking army, into the blood. Simple enough so far. The complexity arises because the defending army, the parasites, don't just lie down and die under the attack. They are capable of modifying their "personalities," as it were, and of changing various of their characteristics such that the mechanisms that the host uses to recognize, or detect, the invaders are invalidated. Thus, the substance which an organism would secrete to destroy an invader A becomes incapable of recognizing A, now become A-l, and therefore incapable of destroying it.

The organism at this point seems to realize it has to create a different substance to rid itself of its antagonist but, in the meantime, the metamorphized parasite is getting on with its assigned destructive task. Alternatively, the parasite has another capability: that of itself liberating substances which can annul or annihilate the organism's overall defense system. A sort of "in the blood" version of Star Wars is going on at the microscopic level.

The study and classification of the substances - - call them weapons - - emitted by parasite-attacked organisms allows for the establishment, in turn, of batteries of tests to define the exact nature of the parasites themselves in order to come up with an appropriate therapy or counter-weapon.

This then, is the essence of parisitological immunology, Raymond Pautrizel's area of research. He specialized on a particularly lethal parasite known as trypanosome, the scourge of tropical third-world countries where, in one form, it causes sleeping sickness in animals and humans, in another, equine syphillis, in still othera, other afflications. Over the years, during which he produced a small library of literature on the problem (known mostly to specialists in countries where that problem is acute), Pautrizel and his team discovered, among other things, that the trypanosome can modify itself, again and again, up to 101 times over a period as short as only three weeks.

Even before his work on trypanosomes, Pautrizel, back in 1949, was one of the first researchers to discover what is known as *ambivalence* in drugs, notably histamine. Histamine is a substance which is secreted by an organism as a defense mechanism but if oversecreted by certain cells circulating in the blood, it becomes virulently noxious, mainly by overdialating blood vessels, thus making them permeable to water and leading to edema and even death. This process occurs, for instance, in some human beings who are highly susceptible and over-reactive to bee or wasp stings.

Pautrizel's research on the noxious aspects of histamine led to his finding that the same substance, applied in requisite small doses, is extremely important to the defense system of the organism. Today he stresses the notion of *ambivalence* in many areas of his work and characterizes it as "a key to the biology of the day after tomorrow."

To finish with the background on Pautrizel, before bringing him on stage in the Priore drama, it may be added that only a few years ago, at a formal reception for him attended by the medical elite of France, he was given a Basque *makila,* an iron-bound honorific cane of sculptured wood, in tribute to his work. On it was the incised inscription: "Sometimes to heal, often to alleviate, always to console," an epithet that perfectly characterizes a medical doctor imbued with that kind of rare compassion that marked Pautrizel's character.

When Robert Courrier sent Madame Colonge to Bordeaux, it was Pautrizel whom he asked to provide her with every assistance. In this way, Pautrizel was first introduced to Priore and his device. After witnessing the results obtained with it he was to say: "What stupified me, and led me to ponder the question, was to see the control animals die from their tumors in 3 weeks, while at the same time I could observe that the tumors in the animals under treatment were literally melting away and the same animals were taken back to Courrier's lab at the College de France in Paris in perfect health." AS a result of his thinking about the problem, Pautrizel came to the belief that the machine, however it worked, did not exert any action at all to kill cancer cells but, through as yet unexplained mechanisms, stimulated the afflicted organisms to provide themselves with new immunological weapons that could overpower the cancer cells.

To shed light on this problem, Pautrizel proposed the simple expedient of experimenting, not on cancer-infested animals, but on *in vitro* cultures of cancer cells. He made this proposition to both French and British cancerologists but they were convinced that the Priore device *had to be actually killing cancer cells themselves,.* They could not see the point that, if the machine did not kill cancer cells, then it was doing something else to the body to allow it, and not the machine, to do that job.

Pautrizel's involvement with the British was the result of a team being sent from England to experiment with cancer mice with the Priore Ray. What happened cannot be related in this brief resume except to say that, out of a lack of understanding on the part of certain British cancer experts and malicious conniving on the part of one member of the cancer "aristocracy" in Paris, the experiments were put under a cloud. It was alleged that mice had been substituted somewhere during their long round-trip voyage between

England and Bordeaux to make it look as if a failed experiment had been successful. This did not prevent Sir Alexander Haddow, chief of the prestigious Chester Beatty Research Institute for Cancer from stating, at a meeting in Paris, that the Priore machine had been indubitably effective on the English mice and supporting Pautrizel's idea that experiments should forthwith be done to see if the Priore Ray had any effect on cancer cells *in vitro.* Haddow's suggestion backing Pautrizel's recommendation fell on deaf ears.

Because of the emotional turmoil and rancor with respect to cancer that had so long surrounded Priore and the workings of his machine, Pautrizel suggested that it be tried in a completely new area, one he knew so well, namely on afflictions caused by the trypanosomic pathogen. Before these could get underway, however, someone had to persuade the still desolate Priore to return to work. Pautrizel, known to those really concerned with and knowledgeable about the potential of the Italian's invention, at last was able to convince the inventor to cooperate and get back into harness. This ho did with that rare combination of diplomatic tact and warm human sympathy with which only the Pautrizels of this world are gifted.

In the meantime, Riviere had gone on to implant new 347 tumor grafts in rats previously cured of 347 tumors. When none of the tumors developed, that result added one more argument to back Pautrizel's idea that the machine was, in fact, affecting the immunological defense system of the animals. However, when Riviere tried the same procedure with the T-8 tumors, his animals died. This lead to the conclusion that the immunity acquired by the animals to lymphoblastic lymphosarcoma 347 was specific to that tumor. When a note on this research was sent, again through Courrier's good offices, to the Academy, for the first time, it strangely omitted from the listing of the participating researchers the name of Antoine Priore. It seemed that Riviere had been taken to task by fellow cancerologists who believed that Priore was nothing but a naive bumpkin or, worse, a swindler. They had warned him against publishing any papers with which Priore's name would be associated This rank injustice and lack of fair play again sent Priore into a fit of despondency and depression from which he could only be wilth drawn by those subtleties involved in Pautrizel's sympathetic and friendly counsel.

On 25 July 1966, another note was sent to the Academy filed for the first time not under the rubric Cancerology but under the rubric Immunology. It was entitled "Influence of Associated Electromagnetic and Magnetic Fields on the Immunity of Mice Infected with Trypanosoma equiperdum." The conclusion read: "The treatment allows the organism to rid itself of parasites even when these have invaded it in a most intensive way.... There is an enhancement of both the specific and aspecific factors of immunity."

Thus, for the first time, the field of research shifted from the narrower field of cancer to the much vaster domain of immunology. And, for the first time, Pautrizel's name appeared as the senior author on the paper. It also appeared that, for the first time, there should no longer be any problem about experimenting with the I'riore machine. Such was not the case.

Still complicating the whole issue was the fact that Priore himself was using different setting to produce different varieties of radiation depending upon his own intuitive evaluation of the particular biological experiments being run with his machine. He would never reveal the nature of these settings.

At this point there appeared on the scene a new researcher who became Pautrizel's loyal ally, a young woman, Pierette Chateau-Reynaud Duprat. During her work in Paris, she had learned of the Priore controversy, and, against the stern advice of mentors senior by many years to her in the cancer hierarchy, she came to Bordeaux to meet Pautrizel and learn more about the research.

Her work, performed over many years, is too detailed for presentation here but it led to important conclusions. One was that the Priore Ray had no direct effect on the trypanosomes themselves but stimulated and reinforced the defense mechanism of the infested organisms, allowing them to reject the parasitical influence with an effect so durable that they were no longer subject to this influence even after treatment stopped.

Another conclusion was even more important and involved, in part, British research. It pertained to the effects of the machine on both *allografts* or those made between two different individuals of the same species, and *isografts,* or those made between two different individuals of the same genetic line having in common antigens that were characterized by what is called the same histocompatability. The conclusion was that not only was the rejection of *allografts acce*lerated by the Priore Ray but that *isografts* were also rejected. This meant, in sum, that the ray stimulated not only the *defense* mechanisms of the organism but also, and more importantly, its re*cognition* mechanisms. In the case of an isograft, this allowed the recognition of weak antigens that were not recognized in non-irradiated animals. In other terms, where at first the anti-aircraft batteries could not shoot down the aircraft because they could not see them.now they could shoot them down because they could see them. In immunological terms, the ray affected both humoral and cellural, both specific and aspecific, immunity.

Here we must return to the mystery of the settings on the device.

As a result of the new experimentation it seemed that, depending on those very settings, the active ray, complex as it was, could have either similar, totally different, or diametrically opposed effects. Thus it was not a question of a ray having universal effects — a kind of magic bullet capable of killing any target — but of multiple radiations which, due to the complexities in Priore's personal makeup, have unfortunately yet to be sorted out and explained.

Thus, the machine originally designed by Priore, called the P-l when it put out a wave length of from 19-21 meters, had a radical effect on certain animal cancers, on *cellular* defense mechanisms, and finally, but not universally, on organisms infested with **Trypanosoma equiperum,** (hereinafter called T.e.).

A second machine, dubbed the P-2, was at first not able to produce these frequencies. What it did put out was a frequency of 17 meters that *was* universally effective against T.e. and seemed to act. not on the cellular, but the *humoral,* defense mechanisms. The rejection of grafts depends on the cellular defense mechanisms, which partially explains why Pautrizel when using the P-2 machine, selected the T.e. vector, as it is called in microbiology, just because this creature is fought by the organism's humoral defense system.

Consequently, the bio-effects that were successfully attained depend on the varying, not to say quixotic, nature of the radiation At one point Pautrizel actually did experiments on animals infected with *plasmodia* — the vector for malaria which attacks red cells - and found that the settings used were effective while never learning exactly what they were or the exact nature of the radiation. Further more, Priore himself maintained that over the years he had success fully treated cases of human tuberculosis but, again, never revealed which frequencies had been used to achieve this.

Several more notes were sent to the academy on the successful work performed with the Priore Ray on animals affected with T.e. But the central issue remained: how to find out exactly how the-machine worked. It fell, not to civilian scientists, but to those in the-French army service to attempt, at this point, to work out the problem. The army service brought into the picture was the DRME (an acronym which translates as Administration for Research **and** Test Methods), to which Pautrizel had sent a request for funds in 1968.

This request was the subject of a meeting at which were present three of the top names in French science, one representing biology, the second physics and the third, medical physics. The latter two turned in extremely unfavorable reports recommending that no money be wasted on the problem. The biologist, however, turned in a most favorable report and, despite the fact that he was in the minority, his opinion won the day.

As remarkable as was this victory, it was even more stunning and incredible given the fact that this biologist was the same Andre Lwoff who had so adamantly opposed the Priore research a couple of years previously. Lwoff had summoned the courage to completely reverse himself only after he sent one of his most trusted colleagues to do secret experiments with the Priore Ray on mice injected with peroxydase (an antigenic solution) to see if they would produce a higher level of antibodies than non-irradiated animals. This they did so well that Lwoff became convinced that the Priore Ray caused an extremely important increase in immune reactions. These results were never published because, before the experiments could be repeated to be absolutely sure of their results, the machine suffered one of its many interminable breakdowns.

The DRME report was at length, and in length, issued but not publicly since it was protected by a military classification. However, a synthesis of it was finally published in November 1979 by Herbert Gossot, Secretary General for the French Association for Bioelectromagnetism, under the title: "A Scientific Balance Sheet on the Priore Ray." Its contents were as follows:

"The two physicists assigned by the army made a complete analysis of the electromagnetic radiations and magnetic fields activated by the Priore device. They thus determined the spectrum of frequencies which the device emitted. They showed particularly that frequencies in the visible light and infrared range had no biological effect; that there were no X-rays or Y-rays; and that the pulsed ultra-high frequency electromagnetic wave was modulated in amplitude to that of a high-frequency wave. They did a topographic survey of the respective intensities of the various magnetic and electromagnetic fields in the experimental plane of the device. In particular, they determined the spatial repartition in this plane of the density of the strength of the ultra-high frequency wave. They showed that its value was very weak and that it could not produce any kind of overall significant thermal effect imputable to the hyperfrequency ray.

Finally, and most importantly, by using what they had learned about these repartitions, they demonstrated a clear correlation between the biological effects obtained and the intensity of the hyperfrequency ray. What they actually observed was that, on the biological model used, i.e. experimental trypanosomosis of the mouse, there was a diminution of the rate of evolution of the parasitemia that was proportional to the strength of the hyperfrequency wave. To quote them: *'These experiments of correlation are of certain interest: they confirm, if there is still any need of so doing, the* *biological efficacy ofthis device."*

The two physicists, Bottreau and Berteaus, are still interested in rebuilding a Priore device with which additional biological research could go forward. At the same time they suggested to administrative bodies in French science the creation of a special laboratory for bioelectromagnetism to fund more work, a suggestion in which Professor Pautrizel concurred. No action was taken and their report was kept under wraps. In a note they presented to the Academy of Sciences on their investigation, they were not allowed to include the names ofthe laboratories where they worked: in the case of one, the CNRS Magnetic Laboratory at Bellevue near Paris, and ofthe other, the Laboratory of Ultra-Hertzian Optics and Talence near Bordeaux. Why? Because the directors of these laboratories did not want any mud in the Priore affair to be spattered on them.

The next experiment done by Pautrizel was on rabbits whose testicles had been so seriously affected by trypanosomes as to be almost entirely destroyed. After radiation the same testicles took on their normal histological appearance and the rabbits, able to procreate again, in no way abstained from their newly regained ability. **This implied the complete regeneration of an organ that had all but completely degenerated.**

Yetjournalists, who sought out truths about the Priore affair in Paris from high officials they believed would know best about what was going on, continued to be led astray. For example, an American scientific reporter, writing in the **Saturday Review** of **Science** in 1973 saw fit to state: "It is really a question of a mystical problem that has little to do with science." He was quoting Professor Bader, a man who for 15 years held top administrative posts in science that could have allowed him to back the Priore research with all the funding necessary to its accomplishment. At the time Graille's book came out, Bader issued a book of his own about the Priore affair which offers no real idea of what was involved. When I asked several people in France why Bader had written the book, they were unaware of Bader's inmost motivation.

Machinations continued to swirl about the case over the next several years. Behind-the-scenes intrigues, distorted accounts in the press, lethargic attitudes on the part of administrative officials who would not take responsibility to cut an increasingly tight Gordian knot, outright fear of various personalities to become too deeply implicated lest they lose their jobs - - all these, and more, continued their daily round in an atmosphere of "Business AS Usual," and "Don't Risk Your Neck."

To get to the nexus of the situation, we have but to cite the observation of one of the few perspicacious journalists who, in **the** prestigious scientific monthly, Sciences and Life, wrote: "The physicists are convinced that the effective Priore Ray is very complex but to analyze this further some things first have to be made clear. One is to raise the suspicion that has surrounded Monsieur Priore with a fabulous acretion of misunderstandings, insults and accusations of being a swindler over many years. What is needed is a veritable national effort to act effectively and to act rapidly."

Over the next two years the decision-making process of the French government lumbered its way along until it was finally decided to back the construction of a powerful machine. This decision was not favorably accepted in many quarters. As Le Monde would comment: "The decision was made in spite of the disapproval of many scientists. When money is tight, one should pay particular attention to how it is being spent. Such seems not always to be the case. A credit of some $3.5 million francs (or about a million dollars) has just been accorded to finance the construction of a new Priore machine."

The scientists to whom the article referred were in a rage. They understood, at this juncture, that the only way to put an end to the affair was to eliminate Pautrizel who, because of the very success he was having with his research, was seen as a dangerous competitor that might even become one of the top figures in medicine and science on a national, or perhaps, on a world scale. Indeed, it was learned that Professor Courrier had gone to the length of sending a report on Pautrizel's behalf to the Nobel Committee in 1979.

To make a long story short, the large powerful machine, the M-600, was built but a huge tube in it, after functioning for about a week, exploded. Due to the galloping inflation of the 1970's, to replace it would have cost another million dollars. The money was not forthcoming.

In the meantime Pautrizel, ever experimenting with the still functioning smaller machine, was to discover new facts. Mice with their spleens cut out, for example, also could survive injections of T.e. The Priore Ray had important implications for Arterio-sclerosis, since it effected lipid modifications in rabbits given a dietary regime high in cholesterol. This research, published in another note in the Academy Proceedings, instead of being warmly received, only irritated the cardiological fraternity which felt, as some of its members put it, "trapped" by Pautrizel's efforts.

One particularly virulent opponent was Professor Bricault, Dean of the Bordeaux Medical School who, as late as 1980, was telling his own students that the published results were a farce and had never been obtained. The students, who carried out a special investigation of the matter on their own, were able to judge what a farce their own medical dean might represent.

L'Express, the **Time** magazine of France, read by at least half the population of French intellectuals, had the gall to compare the results of the Priore research to those of the infamous Trofim Lysenko of the Russia of Stalin's day. Haughtily **L'Express** added: "Today Priore's defenders explain that his machine has not only cured cancer but, in all probability, altered the immunological characteristics of mice. Were this, in fact, so, all the immunologists, all the geneticists of the world would unite to affirm that a machine capable of changing the genetic patrimony is the discovery of the century, far more important than the atomic bomb or the conquest of the moon. Unfortunately, the history of the whole thing has never been properly elucidated." The article was illustrated with photos distortedly selected to convince viewers that the Priore machine was as serious and effective as the one that purportedly brought Frankenstein to life.

In this poisonous atmosphere the slow work of building the M-600 went forward. To give anyone who was not there a feeling for this endeavor we may now cite verbatim a passage from Graille's book: "The construction and assembly of the prototype —the M-600, that of highest power and variable parameters — were fraught with many uncertainties and delays on the one hand and, on the other, were marked by the stamp of Antoine Priore's sparkling genius.

"To go from an apparatus that developed 1,240 gauss applied over an effective area of some 20 centimeters, to one developing 5000 gauss over an area of 60 centimeters means to take on an extremely risky technical and technological wager. Electrical, mechanical and glass-blowing specialists plunged into the unknown. They had to conceive, make, adapt and put together all the various myriad components almost haphazardly with no precise technical study being previously available. Priore's stubbornness forced them to take on a trial-and-error manufacturing "gimmickry" without precedent. As the thing was put together and preliminary tests made, it became clear that many of the components were unsuitable and that they would have to be modified or replaced. The tube itself, made of pyrex, 60 centimeters in diameter, and 6 meters tall, had to be replaced twice after it imploded. In fact, practically everything had to be reconsidered or readapted. "Everything" meant the parts going to make up a generator of 50 tons in weight. For example, the coil which created the magnetic field: 5.5 tons with 11 miles of copper wire. For example, the numerous cooling circuits which stabilized the thermal equilibrium of the generator and its environment or, additionally, the circuits governing command, control regulation and selection — 6 tons of electrical cables of which 15 miles were of tele-command wiring.

"Priore astonished everyone. Breakdown after breakdown, incident after incident, it was he alone who showed what to do next, indicated the proper steps to take, the right settings to adopt, the right way to assemble the components: He was virtually building his machine by himself, nursing its construction along day after day, all the engineers' studies and efforts actually, and ultimately, serving only as a preliminary attempt, a sketch as it were. When Priore made his presence felt, things began working."

Then.... after the machine was built: "The part of the entire apparatus to generate electricity was set up on a provisional basis. It was so noisy that, while functioning, it woke up the whole neighborhood. The number of experiments had therefore to be curtailed so that the machine would not be used at night. And, all at once, everything came to a halt. The Faraday cage, shielding and isolating Priore's apparatus, was torn and fissured by the shock of the cement pilings that were being sunk into the ground all around to hold up the building under construction. This allowed high-frequency waves to escape which disturbed radio broadcasts emitted by local radio stations, the army, and civilian aircraft for miles around."

Nevertheless during the week or ten days that the machine was in good operation the results of experiments performed with it were more than formidable. First of all, it allowed for as many as forty experiments to be performed on some 280 animals in a remarkably short period of time. Among the discoveries made were: The ray emitted provided the treated animals with an extremely strong immunitary response. Animals whose immune defenses had been attentuated by an immuno-depressant were able to overcome the effects of injected parasites but relapsed a few days later. One could therefore conclude their immune response was much weaker than those normally infested and treated.

Newborn animals, whether treated or not, developed a marked parasitemia leading to their deaths. At the time of death, the parasites had the same antigenic structure as those ofthe innoculum which thus implied that they had met with no defense at all in the infected organisms. This also proved that the Priore Ray did not act directly on the parasites themselves but only by way of an increase in the immune defense system of the organisms. The newborn animals succumbed to their parasitemia because their immune sytem was not yet sufficiently developed to be stimulated by the P-Ray. The phenomenon of a stimulation ofthe immune defenses was demonstrated by the fact that animals which had received soluble antigens developed, after being irradiated, a level of antibodies far superior to the controls.

These and other conclusions were the object of notes presented to the Academy of Sciences by Pautrizel and his team in 1978. Even before, at a colloquium held in Antwerp, Belgium devoted to African human trypanosomiasis, the same team had offered the conclusion that the stimulation of the immune defense system that allowed organisms to throw off the effects of trypanosomiasis had to be very significant in that all attempts to try to effect such stimulation through immuno-stimulants as well known as B.C.G., or Corynebacterium granulosum, had led neither to the cure produced by the Priore Ray, nor to any prolongation of the infected animals' lives, nor even to the slightest modification in the evolution of the Trypanosomiasis.

These three scientific papers did little for the cancerologists who read them except to exacerbate their urge to oppose the Priore research, if not to arouse their outright hatred for the principal experimenter, Raymond Pautrizel. Could this have been because, for over 20 years, the same cancerologists had been working in vain to provoke in cancerous organisms immuno-stimulative reactions by intensively and successively vaccinating them with B.C.G.? Many others had been life-long apostles of chemotherapeutic cocktails of all sorts, or life-destroying ionizing radiations, or, what more recently has become the fashion, of applying the two methods in endless combination.

For this reason, they saw Priore and Pautrizel as nothing more than spoil-sports who had to be destroyed.

One of the opening shots in this campaign was a letter received by Pautrizel to inform him that his request for funds to continue his research through Unit-89, a unit that had been specially set up for him to direct, had been denied. It took many months of investigation for Pautrizel to learn that the real reason for the refusal was because of his work with Priore.

Next Pautrizel was informed that his appointment as director of the same research unit would be extended for only two years, whereas the normal extension for similar units was five years. A third insult came when Pautrizel tried to win a post within his unit for a high-ranking military physician, who had been his student and who had decided to quit the military in order to participate in the fascinating research prosecuted by his mentor. Pautrizel's request for funds to pay this physician, who all his life had been working on tropical medicine closely associated with problems of trypanosomiasis, were refused four times in a row with no cogent reason given. The physician, who in the meantime had volunteered his time without pay, finally became so emotionally overwrought that he gave up his medical career and retired to the countryside where he gave himself over to alcohol. Then Pautrizel tried to get a salaried post for another ofhis brilliant collaborators (who still works with him). He was told that this man could take up his new functions only if he left Bordeaux. One could go on with many other shocking stories but we will leave it to Graille to conclude: "Everything possible was done to isolate Pautrizel, to separate him from his collaborators. Every single one of these collaborators saw their careers put in jeopardy, compromised, or broken."

As a final insult, when the time came again to renew Pautrizel as director of Unit 89, those responsible, not daring to overstep what even they knew to be decent limits by not extending him, simply abolished the unit. And to add injury to that insult, a doctoral thesis that had now been prepared by Priore, and backed not only by Pautrizel but by Nobel Laureate Andre Lwoff himself, was summarily refused by the President of the University of Bordeaux.

It is perhaps unnecessary to state that the details behind all of this skulduggery could, and did, fill up two chapters of a book and make for the most heart-rending reading imaginable.

So what happened next? In the autumn of 1977, Professor Georges Dubourg, one of the leading lights in Bordeaux's company of surgeons and a friend and admirer of Pautrizel's, came to him to say openly and baldly: "My friend, at the point you've reached, there is only one more way to jolt medical opinion and that is to treat human cancer patients." Pautrizel was hesitant, believing his role to he one of continuing with his animal experiments but where would the funds for that come from now? He therefore asked his old mentor, Robert Courrier's advice. Courrier gave the green light. The treatments were restricted to terminal cancer patients whose immune defense systems had been disastrously weakened by chemotherapy or radiation or both. At least one of them was totally cured. The other 1ived, without pain, for a period many times longer than predicted by prognosis. Dubourg, Pautrizel and their collaborators wrote up the results and sent them as an official communication to the French Academy of Medicine for publication.

The reply they received from that Academy's perpetual secretary reads: "Experts whom we consulted consider that your work does not fall within the jurisdiction of our members and that it would doubtless find an audience more worthy of its purpose in a more specialized society."

To which Pautrizel formally replied: "Since two of the four signatories of our note are corresponding members of your Academy, could we not benefit from the remarks and comments made by the committee which saw fit to refuse our paper? And even, if this is not too indiscreet a request, to learn the names of the expert members who were consulted which would allow us to get into contact with them directly and to benefit from their singular competence?"

His letter has remained unanswered for four years.

There was nothing more to do except one thing which Raymond Pautrizel, as a man of science, had always been careful to avoid: Get a responsible journalist interested in the case, inform him of all possible details, and let him carry the Priore Affair in all its harrowingly loathsome aspects to the broad reading public. That journalist was Jean-Michel Graille.

For four years, Graille went about his task, publishing three consecutive long articles in his newspaper **Sud-Ouest France** and finally the book to which we have referred and of which this presentation is largely a resume. As early as 1980, Graille would write in his newspaper: "The Priore Affair is simple in essence. It can be reduced to a simple alternative: either the machine developed by Antoine Priore is of no interest and, having shown this, the affair can be considered at an end. Or else the machine is of real and demonstrable medical interest and, if that is officially recognized, he would be allowed to get on with the work. For this dilemma runs the risk, yet again, of being buried under delays and evasions. Beyond all the powers-that-be that have been directly connected to the affair for many years now — the power of finance, the power of medicine, the power of science — perhaps it is now political power with which responsibility lies if it can rise to meet and assume that responsibility through decision."

That was Graille's statement in 1980. His book which came out four years later ends with the sentence: "The Dossier Priore thus depends, from here on out, on a decision that must be taken on the very highest level, and imperatively. This responsibility devolves, in last resort, on the chief of state and on him alone. Will he assume it?"

Would the President of the United States?

Note added by T.E.B.: Antoine Priore is now dead. His machine has been dismantled. The iron dogma and hatred of electromagnetic medicine by bureaucratic science may have doomed hundreds of millions of humans - - whom Priore's device could have saved - - to bitter, agonizing, and unnecessary deaths. Hitler, Stalin, and Mao combined were not responsible for the deaths of so many.

APPENDIX II

PATENTS

English Translation of the French Patent No. 1,342,772 of Antoine Priore, 7 Oct. 1963.

Procedure and Assemblage for Production of Radiation Especially Serviceable for the Treatment of living cells.

Brevet d'Invention. P.V. no. 899.414 no. 1.342.772 Classification Internationale: A61 k-H 05 g

Procedure and assemblage for production of radiation especially serviceable for the treatment of living cells.

Antoine Priore
Requested 1 June 1962, 14.52 hours, Paris
Released by decree (arrete) of 7 Oct 1963

The invention deals in a general manner with radiation capable of penetrating matter. More exactly, it aims at a procedure and an apparatus making it possible to obtain a combination of radiations of different types able to penetrate matter and especially to penetrate intimately living organic tissues in order to produce in them certain effects, particularly in human tissues with a view to a therapeutic effect without destroying essential elements such as the enzymes.

In conformity with the present invention, one emits in a cavity a stream (rayonnement) of electrically charged particles upon which one superposes electromagnetic radiation of the centimeter wavelength range, the wavelength of which is preferably between 3 cm and 80 cm, and one directs the resulting radiation emerging from the cavity on to the object to be irradiated.

This applicant has shown that the penetration and, in particular, the curative effects are very distinctly improved when one gives the electromagnetic radiation a frequency determined as a function of the organ or the tissue to be penetrated or to be treated. For example, a wavelength of 14 cm is suitable for the liver and a wavelength of 19.5 cm for the spleen.

Preferably, the stream of charged particles is accelerated in a particle accelerator in such a way as to increase the force of penetration.

The resulting radiation is advantageously applied and directed upon the target, that is to say, upon the tissue to be penetrated, by the intermediary of a tube which is the site of electric fields and of magnetic fields for acceleration and control, the said radiation being preferably guided and/or reflected by a rotary deflector placed in the tube.

It is often advantageous to modulate or impose rhythm on this stream of particles by means of variable magnetic and/or electric fields so as to augment still more the force of penetration. This rhythm is preferably consistent, especially in medical applications, with the intrinsic period of the tissue to be penetrated or of the neighboring tissues, for example, muscle. These intrinsic periods arc well-known in medicine and are applied, particularly, for diathermy: they are situated in the wavelength range from 1 m to 50 m and more especially from 1 m to 18 m.

Preferably, one arranges to modulate the emission of radiation, the accelerating magnetic and electric fields, and perhaps also the rotatory deflector, to the cardiac rhythm of the subject.

It seems that the result obtained by the invention in the treatment of maladies of living cells (vegetable or animal) are due to certain phenomena which will be described, it being understood that this exposition will not circumscribe the invention.

As a function of its electro-physico-chemical constitution, the cellular pair nucleus-protoplasm is endowed with electric conductivity in direct relationship with ion exchange processes provoked by metabolic phenomena. One finds in tissues the presence of an accumulation of electricity at different potentials according to the different cellular densities of the tissues.

The work of Renshaw, Forbes, Morison, Amassian, de Vito, Ruset, Albe-Fessard, Tauc, Adrian, etc. has shown with the aid of micro-electrodes the existence of slowly oscillating elementary electric activity in the interior of cells; it can be thought that the *rythmeur* (or pace-maker) is achieved by the oscillatory electromagnetic system comprising the cell nucleus. This nucleus, in effect, is made up essentially of tubular filaments of insulating material (related to chitin) containing in its interior an electrically conducting saline liquid, and these filaments, coiled upon themselves, can be considered to constitute real little oscillatory circuits.

The recent work of Warson (sic) in America, as well as that of French scientists, including a communication from Polonsky, Don zon and Sadron presented to the **Academie des Sciences** by Prof. Francis Perrin on 16 May 1960 **(Rec. comptes rend, heb.,** 250 No. 20, 3414-3416) making it clear that experimental samples of **solid** DNA manifest properties analogous to those known in ferroelectric materials, makes plausible the hypothesis that a potential difference may exist between nucleus and periphery of cells. Certain recent theories go even further and liken the cell to an electronic receiver-emitter device normally functioning in harmony with the ambient media. The oscillatory system of demand waves, constituted by the cell nucleus, would behave in accordance with the laws governing semi-conducting materials.

The applicant is led to the conviction that in a normal state of physico-electric equilibrium, the cell nucleus is positively charged, but can acquire a negative surcharge following phenomena analogous to polarization.

The invention, especially, enables organs afflicted by this inversion of their electric potential, particularly in the case of the pathologic negative surcharge of cancerous nuclei, to recover their former equilibrium.

The following description in regard to the attached drawing, given as a non-restricting example, will make it possible to understand how the invention can be realized, the details which emerge both from the text and the drawing being, of course, part of the said invention:

Fig. 1 is a schematic section showing an apparatus for production and emission of an electromagnetic field combined according to the invention.

Fig. 2 is a frontal elevation of the cathode, taken from the right of Fig. 1.

Fig. 3 is a section through III- III in Fig. 1.

Fig. 4 is the overall scheme of the electric supply.

Fig. 5 is a view analogous to Fig. 1 showing another mode of implementation.

Fig. 6 is a section through VI-VI in Fig. 5.

Fig. 7 represents schematically an apparatus for pulsing the electric current.

Fig. 8 is the circuit of an amplifier permitting activation of the apparatus of Fig. 7 at the cardiac frequency.

Fig. 9 is the circuit of an oscillator permitting modulation of the electric current according to a wavelength between 1 m and 18 m.

The assemblage of Fig. 1 contains an apparatus 1 emitting electrically charged particles 2 in a cavity or passage 3, a cyclotron 4 accelerating the particles 2 and sending them into a cavity 5 forming a tube into which merges another cavity 6 acting as waveguide for electromagnetic radiation of frequency in the centimeter range emitted by a magnetron 7. The cavity 8 formed by the joining of tube 5 and waveguide 6 leads into a tube 9 in which the resulting radiation is accelerated and aligned. The interior of the cavity-formed by the assemblage of elements 1, 3, 5, 6, 8, and 9 contains argon at a pressure of 2 mm mercury.

The particle emitter 1 consists of an electron gun comprising a plate 10 and a cathode 11.

The cathode 11 is of molybdenum and has the very special form represented in Figs. 1 and 2. It consists of a rim 11a connected by two aligned spokes 11b to a hub 11c pierced by a hole 11d with its axis along XX'. The rim 11a is in two parts (as one sees in Fig. 1) which may be held together by screws (for example) forming a cavity of revolution 11e traversed by a number of holes 11f parallel to the axis XX' and regularly spaced. The filament for heating, 12, situated in the interior of the cavity 11e and is connected to the power supply conductors 12a.

The best results are obtained with a cathode 11 of molybdenum. The applicant has obtained satisfactory, but slightly inferior, results with tungsten cathodes. It turns out that molybdenum, and to a lesser degree tungsten, are the metals whose valency is closest to the mean valency of the chemical molecules constituting living tissues and more particularly those of human beings. One might well seek to use this fact to explain scientifically the phenomena involved, but it is understood that *the invention is not limited by any scientific explanation.* Concerning, on the other hand, the gas present in the apparatus at low pressure, the best results have been obtained with argon; the applicant has also obtained satisfactory, but slightly inferior, results with other gases of the rare gas series.

Surrounding the tube which constitutes the electromagnetic chamber are arranged: an electromagnet 13 with its winding 13a, placed at the level of the accelerating coils 14 and 15. Other accelerating coils 14,15 and 16 are similarly dispersed around the cavities 3, 5 and 8.

The two semi-circular boxes or "dees" 4a of the cyclotron 4 are placed in the usual manner between the poles of the frame around which are wound the accelerating coils 4b and 4c.

The magnetron 7 is of a familiar type and must be capable of emitting in the cavity 3 a centimeter wave of adjustable wavelength from 3 cm to 80 cm.

The lower portion of the tube 9, for acceleration and alignment, contains a cathode 17 resembling the cathode 11, with a filament 17a. This cathode 17 is supported by a hollow pillar 18 pierced by holes 18a close to its junction with the bottom of tube 9. This pillar 18 communicates with a tube 18b emerging on the axis of a rotary deflector 19 carrying at each end a "crown" of graphite plates 19a inclined at 45° to the vertical. The rotating axis 19b of the rotary deflector is mounted in a support 20 fixed to the interior of tube 19 and carries at its upper extremity magnetic bobs 19c which ensure that it will be set in motion in cooperation with the magnetic bobs 21a mounted on the shaft 21b of a motor 21. The lower extremity of the rotary deflector 19 is composed of a piece of molybdenum or of tungsten 19d in the form of a pyramid whose apex is opposite the open end of the tube 9.

The hollow base 18 and the tube 18b can be of a borosilicate glass of low coefficient of expansion such as that sold under the trademark "Pyrex." They may also be of quartz. Tube 9 itself can be of "Pyrex" as above or of another glass of the quality currently used for the manufacture of electronic tubes, but its bottom 9a, which is traversed by the radiation, is advantageously made of quartz.

The duct 8 joins the tube 9 by way of several tubulures such as 8a and 8b directed in vertical planes towards the plates 19a at a certain angle, which is advantageously about 22.5°. An electromagnet 23 analogous to the electromagnet 13 of the emitter tube 1 is placed around the cathode 7. Similarly, accelerator windings 24 are disposed around the tube 9. This tube also carries, at positions indicated in the drawing, three electrodes 25, 25a, and 25b surrounded by windings 26, 26a, and 26b, respectively. The drawing shows the supply lines, 17b, 17c of the cathode and its filament and that of the plate, 22a.

The basic plan of the electric supply is represented in Fig. 4. The part 27 feeds an initial branch with low voltage alternating current: this consists of a rectifier 28 (e.g., a Kenotron) whose rectified current is modulated at a frequency variable between 30 and 120 pulses per minute by means of a resistance 29, the control apparatus lor which will be described with reference to Figs. 7 and 8. The current so modulated is passed through the electromagnets 13 and *23* in such a manner as to generate, normal to the cathodes 11 and 17, a modulated field of 10,000 to 20,000 gauss.

The part 27 also feeds a variometer (interrupter) 30 which modulates the current of this part at a variable frequency 30 to 120 pulses per minute, the current pulsed in this way serving to feed the remainder of the installation, to wit: The magnetron 7; a converter 31 whose excitation is modulated at a variable frequency *300 to 900 Hz,* yielding a doubly modulated current (first at 30-120 pulses per minute, then at 300-900 Hz) which feeds the coils 15, 16 and 26; another converter 32 producing a low voltage direct current modulated at 30-120 pulses per minute by the variometer 30. This current feeds the motor 21 as well as the motors driving the variometer 30 and the apparatus controlling the resistance 29.

The current produced by the converter 32 also feeds a voltage step-up apparatus 33 consisting of a vibrator followed by a transformer and a rectifier, and producing a direct current varied at 30 to 120 pulses per minute imposed by the variometer 30. The maximum value of the voltage produced by the apparatus 33 is, for instance, 300,000 V, but this value may vary up or down, depending on the power one wishes to operate with.

The current produced by the voltage step-up apparatus 33 feeds the coils 4b of the cyclotron and 24 of tube 9, as well as a rheostat 34 permitting regulation of voltage to the desired value between 5000 V and 70,000 V. This voltage is applied to an oscillatory circuit 35 which produces oscillations at a frequency variable at will of wavelength between 1 m and 18 m. The current available to the output terminals 35a, 35b of this oscillating circuit 35 is thus a high tension current modulated first at 30 to 120 pulses per minute (by the variometer 30) and secondly at a wavelength 1-18 m. This current feeds the coils 4c and 14; the electrodes, 25a and 25b are connected to terminals 35a and 35b, respectively, and electrode 25 is connected to the mid-point 35c.

Cathodes 11 and 17, the "dees" of the cyclotron, and the plates 10 and 22, not shown in the diagram of Fig. 4, are connected to the output of the step-up assembly 33, while the heating current for the filaments 11e and 17a is furnished by the resistance 29.

To operate the apparatus, one adjusts the controls of the resistance 29 and the variometer to the desired rhythm; in medical applications, this is advantageously the subject's cardiac rhythm: This rhythm is thus imposed upon the whole installation. The cathode 13 emits toward the left a stream of positively charged particles 2, which are concentrated by the electromagnet 13 and accelerated by the coils 14, 15 and 16 and by the cyclotron 4. Superimposed on this particle stream in the duct 8 is the electromagnetic radiation from the magnetron 7, which is adjusted to the wavelength found by experience to be most appropriate to the cells which are to be penetrated, e.g., 14 cm for the liver and 19.5 cm for the spleen. The resulting radiation is deflected, directed and accelerated in tube 9 and is directed by way of the base of this tube toward the target to be penetrated.

It must be noticed that the magnetic field of the coils 15,16 and 26 is modulated, by means of the converter assembly 31, at a frequency adjustable *between 300 and 900 Hz.* This modulation has the effect of concentrating the particles, that is to say to detach them from the walls of the tubes, and it also permits an appreciable saving in weight of the iron cores of the coils. One chooses the highest frequencies (i.e., around 900 Hz) when one wishes to produce hard radiation at the exit of tube 9, and the lower frequencies for soft radiation.

The unidirectional magnetic fields of the coils 4c of the magnetron (sic) (cyclotron?) and the accelerator coils 14 as well as the electric field of electrodes 25, 25a, 25b, are modulated by the oscillatory circuit 35 at a chosen wavelength between 1 m and 18 m. In medical applications notably one selects the wavelength that best suits the organ to be treated or its surroundings, such as muscle. As already indicated, experience with diathermy makes it possible to determine the most suitable wavelength.

It must be noted that the resulting radiation already possesses, in tube 8 (Fig. 1) a considerable penetrating force. One could therefore use the assemblage described by omitting tube 9 and terminating the cavity at the end of tube 8 by means of a glass or quartz base, the resulting radiation being accelerated and directed, for example, immediately upstream from the base, by a final coil (not shown) surrounding tube 8. However, tube 9 appreciably improves the results.

Figs. 5 and 6 represent another mode of realizing the assemblage in accordance with the invention, in which the elements playing the same role are indicated by the same signs as in Figs. 1 and 3, modified by primes.

The arrangement of the connecting ducts of Fig. 5 in relation to tubes 1' and 9', to the magnetron 7' and the cyclotron 4', is different from that of Fig. 1 and has been used successfully by the applicant. The waveguide 6' of the magnetron 7' opens into the end of tube 1' and the duct 3', carrying the resulting radiation, divides into two branches: Branch 36, which conducts the radiation directly to tube 9', and branch 37 which conducts it to the cyclotron 4'. This blocks the electromagnetic radiation and accelerates the stream of particles which is passed by way of duct 38 to the tube 9'.

This arrangement can be used with a particle emitter and an accelerator and director tube similar to tubes 1 and 9 of the preceding figures. However, tubes 1' and 9' of Figs. 5 and 6 are constructed in a different manner with regard to their cathodes and anodes.

Tube 1' contains a first electrode 11' exactly like that of the cathode 11 of tube 1, and an identical second electrode 39 furnished with a filament 39a. Tube 9' (Fig. 6) contains in its lower part a first electrode 17' with filament 17'a and an identical second electrode 40 with its filament 40a.

In normal operation, i.e., to produce radiation identical to that described in connection with Figs. 1 to 4, electrode 11' serves as cathode and electrode 39, given a positive potential, plays the role of the plate 10 in Fig. 1, the filament 39a being unheated. Electrode 40 and its filament 40a are disconnected; cathode 17' and plate 22' are supplied as in Fig. 3.

To obtain particularly penetrating radiation, the polarities are reversed: Electrode 11' becomes an anode and its filament 11'e is disconnected, while electrode 39 receives the cathode supply and its filament 39a is heated; electrode 17' (with filament 17'a disconnected) and electrode 22' become anodes, while electrode 40 serves as cathode and its filament 40a is heated. For example, one can establish a potential difference of 250,000 V between 40 and 17', and 50,000 V between 40 and 22'. It is understood that in these conditions the cathode 39 emits to the left a stream of electrons which is concentrated, modulated and accelerated by the various coils and in the cyclotron, the polarities of which must of course be established in the proper direction. This stream of electrons is combined with the centimeter radiation emitted by the magnetron 7', resulting in tube 9' in the emission of very hard x-rays, modulated at the chosen frequencies, combined with the centimeter radiation of the desired frequency.

The assembly shown in Figs. 5 and 6 thus permits one to obtain at will either very hard x-rays or the radiation described in connection with the preceding diagrams.

The following description, referring to Figs. 7 and 9, relates to certain details of the apparatus used for modulating the electric current.

Fig. 7 represents schematically the apparatus for control of the resistance 29 and the variometer 30. The variable resistance 29 consists of a graphite helix 29a immersed in a conducting liquid **29b;** another electrode 29c, also of graphite, partly immersed in the liquid, is set into up-and-down oscillations by a connecting rod 41a linked to a fly-wheel 41. The fly-wheel is set in rotation, through the intermediary of a worm transmission 41b, by an axle 42 which can be driven, thanks to a double clutch 42a, 42b, either by a motor 43, or by the shaft 30a of the variometer 30. The variometer 30 is driven by a motor 44 by way of the worm transmission 44a.

If the fly-wheel 41 is driven by the motor 43 at the proper speed, the resistance 29 causes the supply current of the electromagnets 13 and 23 (Figs. 1 and 4) to vary at the chosen rhythm which as we have seen can be between 30 and 120 pulsations per minute and which can be checked by means of a rotation counter shown schematically in 45. In this case, the motor 44 of the variometer 30 can be stopped and the remainder of the installation is then not pulsed. If, on the contrary, the fly-wheel 41 is engaged in 42b and disconnected from 42a, the motor 44 activates the variometer 30 and the resistance 29 at the chosen rhythm.

The speed of rotation of motors 43 or 44 can be regulated at the required speed, corresponding visibly to the cardiac rhythm of the subject, by acting upon the excitation of these motors by means of a manually adjustable rheostat. If one prefers to regulate the speed of motors 43 or 44 in direct accord with the cardiac rhythm of the subject, one can use an assembly such as that represented schematically in Fig. 8: At 46 there is a contact microphone which, when placed over the subject's heart, produces impulses. These are amplified in the circuit shown and applied to an electromagnet at 47 with a moving core which activates a rheostat; this in turn regulates the current running the motors 43 or 44.

Fig. 9 shows schematically the principle of the oscillating circuit 35. The rectified potential, adjustable between 5000 V and 70,000 V by means of rheostat 34 (Fig. 4) is applied between the terminals 48 and 48a. Terminal 35c (which is also connected to electrode 25, Figs. 2 and 4) is connected to the neutral point on the high tension side of **the** transformer which is a component of the step-up assembly 33 (Fig. 4). The terminals 49 and 49a receive the heating current produced by the resistance 29. The variable condensers 50 and 50a make it possible to regulate to the desired wavelength (which, as seen, is between 1 m and 18 m) the current available at the output terminals 25a and 25b of the oscillator shown.

The modes of implementation described gave been successfully carried out but it is self-evident that these are only examples, and that they might be modified, notably by substitution of equivalent techniques, without going beyond the bounds of the invention. In particular, the electron gun 1 or 1' could be replaced by another charged particle generator.

Resume

The invention includes especially:

> A procedure for obtaining a combination of radiations of different kinds capable of penetrating matter, especially of

intimately penetrating living tissues in order to produce in them certain effects and more particularly in human tissues with a therapeutic effect in mind, consisting of the emission in a cavity of a stream of electrically charged particles, upon which is imposed electromagnetic radiation in the centimeter wavelength range, and the guiding of the resulting radiation emerging from the cavity toward the target to be penetrated.

2. Types of implementation exhibiting the following features taken separately or in the various possible combinations:

    a. The centimeter radiation has a wavelength between 3 cm and 80 cm;

    b. This wavelength is set at the value found by experience to be most suitable for the tissues to be penetrated, e.g., 14 cm for liver and 19.5 cm for spleen;

    c. The particle stream is accelerated by magnetic and electric fields such as those which are used in particle accelerators;

    d. The resulting radiation is accelerated and guided, before its emergence from the cavity, by means of electric and magnetic fields;

    e. The resulting radiation is guided, before its emergence from the cavity, by means of deflecting and/or reflecting surfaces;

    f. The stream of particles and/or the resulting radiation are concentrated and accelerated by means of individual magnetic fields modulated at a frequency between 300 and 900 Hz, the highest frequencies being used to produce hard rays and the lower frequencies to produce soft rays;

    g. The emission of the particle stream, as well as the acceleration and concentration of the radiation resulting at its exit from the cavity, are aided by individual magnetic fields of temporally variable intensity, advantageously pulsed at a rhythm between 30 and 120 pulsations per minute and preferably at the cardiac rhythm of the subject;

h. The assemblages for production of the resultant radiation are pulsed in their entirety at the same rhythm as the magnetic fields according to g;

i. The stream of particles and/or the resulting radiation are accelerated and concentrated by direct magnetic and/or electric fields modulated at a wavelength between 1 m and 50 m and preferably between 1 m and 18 m, this wavelength being advantageously chosen as that which is known in diathermy as suitable for the tissues to be penetrated or for the surrounding tissues.

3. An assemblage making it possible to obtain a combination of a stream of electrically charged particles and a beam of centimeter electromagnetic waves in order to penetrate intimately and to irradiate living tissues and particularly human tissues, the said assemblage comprising at least a particle emitter, means for channeling said particles in a cavity serving as waveguide for an emitter of electromagnetic radiation of which the wavelength is included in the range of centimeter waves and preferably adjustable from 3 cm to 80 cm, means for generating in the cavity magnetic field for acceleration and concentration and means for concentrating and accelerating the resulting radiation at the exit of the cavity.

4. Modes of implementation with the following details taken separately or in the various possible combinations:

a. The particle emitter is an electron gun of which the anode is at the end of the cavity and the cathode is situated further along, this cathode being hollow and placed in the magnetic field of an electromagnetic in order to ensure emission of a stream of particles towards the mouth of the cavity;

b. The cathode consists of a rim connected by two aligned spokes to a hub, the said rim being provided internally with an annular housing containing a heated filament and the said housing communicating with a number of holes arranged annularly and traversing the rim transversely;

c. The cathode is made of a metal of valency close to the mean valency of the chemical molecules comprising the tissue to be penetrated;

d. The cathode is of tungsten or preferably of molybdenum;

e. The cavity contains a rare gas, preferably argon, under a vacuum of the order of 2 mm Hg;

f. The cavity contains a duct carrying at least part of the stream of particles to a cyclotron and a duct bringing back into the cavity the particles accelerated in the cyclotron;

g. The cavity passes through several coils, the supply current for the various coils being capable of undergoing modulation at different frequencies;

h. The downstream end of the cavity is composed of a tube containing, in the part from which the resulting radiation must emerge, a cathode and an electromagnet which may be identical to the cathode and the electromagnetic according to para. a, an anode near the other end, and a rotary deflector consisting of a number of plates arranged *en couronne* on a rotor lacing the incident radiation at such an angle that the radiation deflected and/or reflected is directed toward the cathode, several coils whose supply current can be modulated being distributed over the length of the tube;

i. This tube also contains electrodes supplied by alternating current generating an electric field at the level of the rotary deflector, each of the said electrodes being surrounded by a bobbin of which the supply current can be modulated;

j. Methods are anticipated for modulating, at an adjustable rhythm between 30 and 120 cycles per minute, the supply current of the electromagnetic according to a and h, and preferably to modulate the supply current of the rest of the assemblage at the same rhythm;

k. Methods are anticipated for modulating, at a frequency between 300 and 900 Hz, the supply current of the bobbins surrounding according to i and one or several coils according to g;

1. Methods are anticipated for modulating, at an adjustable wavelength between 1 m and 50 m and preferably between 1 m and 18 m, the supply current of the electrodes according to i, of one or several of the coils generating the magnetic field of the cyclotron;

m. The electrodes of the electron gun consist of two electrodes identical to the cathode according to a, b, c, or d, the cathode of the tube according to h is replaced by a double electrode reproducing the arrangement of the electrodes of the electron gun, and methods are anticipated for reversing at will and simultaneously the polarities of these two pairs of electrodes and the direction of flow of the current supplying the acceleratory coils, a first pattern of polarities assuring the functioning of the apparatus in the conditions which are laid down according to a, and a second pattern of polarities assuring emission in the cavity of a stream of electrons combined with the centimeter radiation and giving rise, at the exit of the said tube, to emission of very hard x-rays.


44
44a
30
30a
42b
41
41b
42
42a
41a
43
45
29c
29
29b
29a

Fig. 17



Fig. 18

Fig.:9


vers 13'
vers 13


Secteur
27
28
29
30
31
32
33
34
35
vers 13
vers 7
vers 15, 16 et 26
vers 21, 43 et 44
vers 4b et 24
35a
35c
35b
vers 25a
vers 25
vers 25b
vers 4c et 14

Fig.:4


Fig.2
Fig.1
4a
4b
4c
II
III

Fig.: 3


8a
8b
9a

Fig.: 6


25'b
17'c


11'e
4'b
4'c
VI
25'b
26'b
25'a
26'a
VI

Fig. 5

Two Patents of G. Lakhousky

June 12,1934 G. LAKHOVSKY 1,962,565

APPARATUS WITH CIRCUITS OSCILLATING UNDER MULTIPLE WAVE LENGTHS

Filed Nov. 13, 1931

Fig. 1.


f
b
e
d
c
a
or Leyden jar
T
+
P
S
C
E
L1 L2
-
V

Fig. 2.



Fig. 3.



G. Lakhovsky
INVENTOR

By: Marks & Clerk
ATTYS.

Patented June 12, 1934 | 1,962,565

UNITED STATES PATENT OFFICE

1,962,565

APPARATUS WITH CIRCUITS OSCILLATING UNDER MULTIPLE WAVE LENGTHS

Georges Lakhovsky, Paris, France

Application November 12, 1931, Serial No. 574,987
In France May 2, 1931

7 Claims. (Cl. 250—33)

The present invention has for its object an apparatus capable of sending out simultaneously different wave lengths so that among these waves or their harmonics there is found almost always one or several capable of producing the best effect sought for any application whatever.

There is used for that purpose the property of open circuits having a fundamental or natural self induction and capacity to oscillate upon a well determined wave length if they are excited by electric impulses emanating from discharges of any source.

The radiating part of the system, producing waves of various lengths, is therefore constituted by a certain number of concentric open rings of different diameters, which are maintained insulated by any appropriate process. These rings may or may not be terminated by small spheres forming capacities.

These rings may be arranged either in the same plane or in different planes so as to form any surfaces, such as portions of cones, spheres, paraboloids, ellipsoids, etc. . . . , these surfaces being of a nature to concentrate the waves in a determined direction in the manner of a reflector, for example.

These rings may be fed by any producing device whatever of high frequency, for example, a combination comprising a trembler coil (or any other transformer) and a high frequency circuit provided with a self-induction coil and a capacity.

One or several points of this high frequency circuit is or are connected to the end of one or several of the rings forming the radiating apparatus. The other rings not connected are excited by induction.

The complete apparatus (coil, high frequency circuits, rings, etc. . . .), may be mounted in a box or upon a small board capable of sliding along a guide or rocking so as to be able to be placed in the most convenient position.

In the accompanying drawing, by way of example, not limitative, there is shown:

Fig. 1 a diagram of the system.

Fig. 2 the position of the rings in the form of a cone.

Fig. 3 the apparatus mounted upon a foot or base.

In Fig. 1 there is seen at T the transformer or coil (P the primary, S the secondary of this coil), V, the screw of the trembler, C the condenser the discharge of which across the spark gap E produces oscillations in the self-induction coil L^1, which in its turn acts by induction upon the self-induction coil L^2; this self-induction coil L^2 is connected on one side to the first exterior ring *a*, on the other side to the following ring *b*. It thus forms an electrostatic field of high frequency which induces oscillations in the other rings *c*, *d*, *e*, *f*.

As a modification, L^2 may be suppressed and the rings *a* and *b* may be connected each to one of the ends of L^1.

One of the ends, or even any point of the self-induction coils L^1 or L^2 may likewise be connected to any one of the rings.

Fig. 2 shows the arrangement of the rings in the form of a cone.

The open circuits *a*, *b*, *c*, . . . *f* can be constituted by solid conductors. They can also be tubular circuits, this being advantageous, since, for the same bulk, the radiating surface is larger. Finally, the area of the cross section of each of these various circuits can vary from one circuit to the other; for instance, this area can decrease from the periphery (ring *a*) to the center (ring *f*) of the radiating system.

Fig. 3 shows the apparatus mounted upon a foot A along which it can slide, in order to be placed at any desired height and upon a hinge B which allows it to be oriented upon the horizon.

I claim:—

1. An apparatus adapted to produce electric fields of high frequency having multiple wave lengths, comprising a high frequency producing device, a series of high frequency radiating circuits constituted by concentric insulated split rings of different diameters, the split ends being spaced from each other and terminating with small spheres.

2. An apparatus adapted to produce electric fields of high frequency having multiple wave lengths, comprising a high frequency producing device, a series of high frequency radiating circuits constituted by concentric insulated split rings of different diameters and terminated by small spheres forming capacities.

3. An apparatus adapted to produce electric fields of high frequency having multiple wave lengths, comprising a high frequency producing device, a series of high frequency radiating circuits constituted by concentric insulated split rings of different diameters and arranged in one and the same plane the split ends being spaced from each other and terminating with small spheres, in staggered position as regards adjacent rings.

4. An apparatus of the type described comprising a base, a plate slidably mounted on said

base, a support pivoted to the said plate, a series of open and insulated, high frequency radiating circuits mounted on the pivoted support, and a high frequency producing device for the excitation of the said circuits.

5. An apparatus adapted to produce electric fields of high frequency having multiple wave lengths, comprising a high frequency producing device, a series of high frequency radiating circuits, said circuits being open, insulated, and having dimensions different from each other.

6. An apparatus adapted to produce electric fields of high frequency having multiple wave lengths, comprising a high frequency producing device, a series of high frequency radiating circuits arranged in the same plane, said circuits being open, insulated, and having dimensions different from each other.

7. An apparatus of the type described comprising a transformer, a high frequency energising circuit fed by the said transformer and provided with a self-induction coil and a capacity, a series of open and insulated high-frequency radiating circuits having dimensions different from each other, an inductive connection between two of these radiating circuits and respectively each of the poles of the outgoing element of the high frequency energising circuit.

GEORGES LAKHOVSKY.

Patented June 13, 1944 **2,351,055**

UNITED STATES PATENT OFFICE

2,351,055

TUBE FOR PRODUCING MULTIPLE WAVE LENGTHS

George Lakhovsky, New York, N. Y.; Anne-Marie Louise Lakhovsky, administratrix of said George Lakhovsky, deceased, assignor to Henry S. Blum, Chicago, Ill.

Application November 21, 1941, Serial No. 420,006

11 Claims. (Cl. 250—33)

This invention relates generally to electric devices excited by electric impulses and more particularly to multiple wave length conducting and/or producing means. This invention has for its primary object the provision of such means disposed within a vacuum tube or a tube containing rare gas or gases.

My work over a period of more than 20 years has led me to the belief that there is great need for means conducting and/or producing multiple wave lengths which may be employed in many industrial and medical fields. Suitable apparatus for producing waves of various lengths is disclosed in my U. S. Letters Patent No. 1,962,565, dated June 12, 1934. Embodiments of this apparatus have been in use the world over. Because of the need for simplification in such apparatus so that it may be handy and easily used by persons lacking skill in electrical matters, I have concluded that by providing one unit which incorporates oscillation generating means and another in which the wave lengths are produced, the apparatus may be more universally used in the treatment of cellular life in therapy, in the aging or treating of liquids and in other industrial fields.

The present invention deals with those units, preferably combined with one another and constructed as a portable device and as stated above, has for its major object the provision of a unitary multiple wave length producing and/or conducting device in the form of a vacuum tube.

The present invention further contemplates the incorporation in such a tube, of means for varying the effect of wave lengths, or selectively employing the means therefor enclosed in or forming part of said tube.

This invention further seeks to provide a tube of the indicated type incorporating means for generating oscillations.

Another object of the invention is to provide a single unit which contains an oscillation generator, which produces waves of definite frequency, and further inductance means each permitting emanation of wave lengths of various values.

The structural features of my invention also form a material part of this disclosure, the objects and advantages being attained in structures such as shown in the accompanying drawing, which exemplifies the invention. The following specification, based on said drawing, more clearly points out the purposes and advantages of my invention.

In the drawing:

Fig. 1 is a vertical, partial sectional, partial elevational view of a tube incorporating features of my invention.

Fig. 2 is a similar view of an alternate form thereof.

Fig. 3 illustrates in a similar manner a modified form of my invention.

Fig. 4 is a fragmentary sectional view of a modification made in accordance with the invention.

Fig. 5 is a similar view of another modification.

Figs. 6 and 7 are sectional views illustrating types of wires used in either of the forms of my invention as shown in Figs. 1, 2 and 3.

Fig. 8 is a partial sectional, partial elevational view illustrating a tube incorporating a plurality of grids and selective capacity means for varying the effects of said grids.

Fig. 9 is a similar view of a tube, such as shown in Figs. 1 or 2 and incorporating oscillating or vibrating means.

In that form of my invention shown in Fig. 1, there is provided a sealed preferably transparent envelope 10 made of glass or like material affixed in the usual manner to a screw or Edison plug 11. The latter is conventionally provided with a shell terminal 12 and a central terminal 13. The support or seal 14 of the tube serves to hold wires such as 15 and 16 which connect to the terminals 12 and 13.

Connected to the wires 15 and 16 is a primary inductance member in the form of a loose coil 17 which may be disposed axially of the envelope 10, as shown. The upper end of said member 17 forms a tight wound coil 18 which serves to radiate the strongest induced wave lengths.

Surrounding the primary inductance member 17, there are arranged a plurality of separate coils of wire each being of different length and capacity. Thus, I provide a coil 19 having greatest capacity and successive coils 20, 21, 22, 23, 24, and 25, each having less capacity than the preceding coil. These coils 19 to 25 form secondary inductance means each permitting emanation of a wave length of different magnitude and value than the other.

I may support the secondary coils in several ways. As shown, I prefer to provide a dielectric member such as a glass sleeve 26 surrounding the primary inductance wire member 17 and to mount the secondary coils 19 to 25 on the outer surface of said sleeve, leaving the coil 18 exposed at the top thereof. In order to effectively support and centralize the glass sleeve 26, I provide spacing washers 27 and 28 of mica or the like, top and bottom, and provide a supporting cross-piece 29 on the lower portion of the wire 17.

June 13, 1944. **G. LAKHOVSKY** 2,351,055

TUBE FOR PRODUCING MULTIPLE WAVE LENGTHS

Filed Nov. 21, 1941

Fig. 1.


18
27
19
20
21
17
22
10
23
24
25
26
28
29
15
16
14
11
12
73

Fig. 2.


18
19
20
17a
21
26
22
10a
23
24
25
11

Fig. 3.


46
30
31
32
44
45
33
34
42
35
36
41
37
38
39
40
15a
16a
10b
14b
43
11

Fig. 4.


19c
26
20c
21c

Fig. 5.


30d
31d
41
32d
33d
34d
35d

Fig. 6

Fig. 7.

Fig. 8


52
51
53
50
54
55
57
63
56
58
61
59
60

Fig. 9.



INVENTOR
GEORGE LAKHOVSKY
BY Leon M. Strauss
ATTY.

The tube above described may be employed as indicated for the treatment of cellular structures by connecting it to any one of the rings in the electrostatic field of high frequency, such as shown in said U. S. Letters Patent No. 1,962,565, each of the coils **13** to **25** producing by induction a different wave length, as can be understood.

In the form of my invention shown in Fig. 2, the envelope **10*a*** is somewhat differently shaped, and the wire **11*a*** straight instead of arranged as an open coil. In other respects, the structure follows that described with reference to Fig. 1.

As shown in Fig. 3, there may be arranged a plurality of open rings **30**, **31**, **32**, **33**, **34**, **35**, **36**, **37**, **38**, **39**, and **40** in frustro-conical form, for instance, with the largest of said rings at the top and the smallest one adjacent the bottom. I have shown said rings as supported, for instance, by glass posts **41** and **42**, said posts being supported on the seal **14*b***, as by a band **43**. I provide extensions for the terminal wires **15*a*** and **16*a*** and connect said extensions **44** and **45** to the upper ring **30** and the next lower ring **31**, respectively.

The rings **30** and **31** may become the primary inductance members, whereas the remaining rings constitute the secondary inductance members as before set forth. Electric current conducted to the suitably spaced rings **30**, **31** will cause a spark **46** to be drawn between the rings **30** and **31** providing oscillations emanating from electrical discharges therebetween and causing the radiation of waves of various lengths within the envelope **10*b*** and affecting the remaining rings.

In Figs. 1 and 2, I have shown the secondary coils as formed of wires having uniform cross-section. Fig. 4 illustrates how such wires may be made progressively smaller in the succeeding coils **15*c***, **20*c***, and **21*c***, etc. Similarly, I have shown the rings of Fig. 3 made progressively smaller in Fig. 5, said rings being designated by numerals **30*d***, **31*d***, **32*d***, **33*d***, **34*d*** and **35*d***, etc. In such various manners, the wave length producing effect of the secondary coils or rings may be arrived at.

The secondary coils or rings may be round or somewhat flattened wire as shown in Fig. 6 or tubular as in Fig. 7, offering a yet greater flexibility of design.

The devices of Figs. 1 and 2 above described may be incorporated in the system shown in said U. S. Letters Patent by connecting one of the rings *a*, *b*, *c*, *d*, *e*, or *f* with plug **11** of Fig. 1, since either terminal **15**, **16** is in contact with primary inductance member **11**. To this end a conductor (not shown) connects such a ring with said plug or socket.

In Fig. 8, I have shown a modification of the invention which comprises a vacuum tube **50** containing a plate **51** and a plurality of different wave lengths producing grids **52**, **53**, and **54**. I connect each grid with a variable capacity device, such as **55**, **55**, and **57** carried by said tube **50** and preferably by its base support **63**, whereby the grids may be selectively connected into an operating circuit (not shown) by means of the respective prongs **58**, **59**, and **60**, and the plate prong **61**. Heating or other exciting means may be incorporated in the tube in a well-known manner. This combination tube **50** is designed to replace a plurality of known tubes each operating with different and variable wave length effect, mere exterior manipulation at said base support brings about change of the capacities **55**, **56**, and **57** and cutting in one or more of the grids **52**, **53**, and **54**.

The effect of the spark as produced in the form of the invention depicted in Fig. 3 may be further utilized in Fig. 9 in which I also incorporate a vibrator **62** which produces electrical oscillations by a spark intermittently generated between the end of the primary inductance member **11*d*** and vibrator armature **64**. In other respects the structure follows that of Fig. 1.

It may be noted that any type of spark producing or oscillation generating means may be substituted for the vibrator shown. The tubes shown in Figs. 3 and 9 may be used in the manner described for Fig. 1 by connecting one terminal of the base as set forth to produce an induction effect. These tubes may be also connected across both terminals with a suitable potential to obtain the spark effect.

From the foregoing it may be seen that I have provided tubes in various forms for the purpose of generating and conducting multiple wave lengths. Other forms of the invention may be produced within the spirit and scope of the invention as claimed.

Having thus described my invention, what I claim as new and desire to be secured by Letters Patent, is:

1. A device of the character described comprising a vacuum tube having an envelope and base, primary inductance means, and a plurality of separate secondary inductance means of different length for radiating waves of various lengths extending above said primary inductance means, all said inductance means being arranged within said envelope.

2. A device of the character described comprising a vacuum tube having an envelope and base, a primary inductance member axially arranged in said envelope, and a plurality of secondary inductance members spaced apart and independent from each other each member surrounding a respective portion of said primary inductance member and within the field of influence thereof.

3. A device of the character described comprising a vacuum tube having an envelope and base, a primary inductance member axially arranged in said envelope, and a plurality of secondary inductance members each surrounding the primary inductance member and within the field of influence thereof, each of said secondary inductance members having a different wave length effect than the others.

4. A device of the character described comprising a vacuum tube having an envelope and base, a primary inductance member comprising a pair of split rings in inductive relation, and a plurality of secondary inductance members each comprising split rings.

5. A device of the character described comprising a vacuum tube having an envelope and base, a primary inductance member comprising a pair of split rings in inductive relation, and a plurality of secondary inductance members each comprising split rings, said latter rings being arranged in different planes and being of different length to produce a different wave length effect.

6. In a device of the character described, means for producing multiple wave lengths comprising a wire member, enclosing dielectric means for said member, and a plurality of separate wire coils of different lengths on said dielectric means and in the field of inductance of said wire member.

7. In a device of the character described,

means for producing multiple wave lengths comprising a wire member, enclosing dielectric means for said member, and a plurality of wire coils on said dielectric means and in the field of inductance of said wire member, each coil extending over said wire member and having a different number of convolutions than the others.

8. In a device of the character described, means for producing multiple wave lengths comprising two split rings in inductive relation, and a plurality of split rings in inductive relation to the two split rings.

9. In a device of the character described, means for producing multiple wave lengths comprising two split rings in inductive relation, and a plurality of split rings in inductive relation to the two split rings, the plurality of rings being of smaller diameter than the mentioned two rings and each progressively smaller than the others.

10. In a device of the character described means for producing multiple wave length, comprising two split rings in inductive relation, and a plurality of split rings in inductive relation to the two split rings, the plurality of rings being of smaller diameter than the mentioned two rings and each progressively smaller than the others, all of the rings being arranged in frusto-conical disposition.

11. In a vacuum tube having a primary inductance member and secondary inductance members, a vibrator arranged in the field of influence of said primary inductance member and secondary inductance members, a vibrator arranged in the field of influence of said primary inductance member for affecting the induction of said secondary members.

GEORGE LAKHOVSKY.

T.H. Moray's Patent
Electrotherapeutic Apparatus
Feb. 1, 1949

Feb. 1, 1949. T. H. MORAY 2,460,707

ELECTROTHERAPEUTIC APPARATUS

Filed April 30, 1943 3 Sheets-Sheet 1

FIG. 1.


D
38
36a
36
37
A
17a
15
14
11
10
12
16
17
Y
121
122
120
123
B
34
35
C
E
50
50-1
52

FIG. 11.



FIG. 3.


16
15
17
17a
17a
14
14a
17 to 12
15 to 12

FIG. 2.



FIG. 12.



Inventor:
T. H. MORAY,
R. Mallinckrodt and
Philip A. Mallinckrodt,
Attorneys.

Feb. 1, 1949. T. H. MORAY 2,460,707

ELECTROTHERAPEUTIC APPARATUS

Filed April 30, 1943 3 Sheets-Sheet 2

FIG. 7.



FIG. 5.



FIG. 9.


10
40
42
45
10

FIG. 8.

FIG. 10.




9
10
9
40a
45
40
10
44
42
41
41a
44
43
40-1
41-1

FIG. 6.


32
31
27b
7
7
27a
27a
26
33
26a
28
32
30
29

FIG. 4.


20b
20
5
5
20a
21
25
21a
24
22
23

Inventor:
T. H. MORAY,

R. H. Mallinckrodt and
Philip A. Mallinckrodt.
Attorneys.

Feb. 1, 1949. T. H. MORAY 2,460,707

ELECTROTHERAPEUTIC APPARATUS

Filed April 30, 1943 3 Sheets-Sheet 3

FIG. 13.


60
61
62
63
66
65
69
GOVERNOR
64
67
68

FIG. 14.


84
74
73
71
72
76
15
15
70
79
72
83
70.1
to 62+63
77
82
78
80
81

FIG. 15.


71
74
70
72
73
76

FIG. 16.


87
88
85
91
103
97
98
94
102
98a
17
17
96
95
99c
99a
99b
99
86
81
92
93
90
100
101

FIG. 18.


113
107
108
112
105
19
19
114
111
106
109
110

FIG.


87
95
94
97
103
85
98a
93
91

FIG. 19.


111
108
112
115
113
114

Inventor:
T. H. MORAY.
By R. W. Mallinckrodt.
Chas. A. Mallinckrodt.
Attorneys.

Patented Feb. 1, 1949 **2,460,707**

UNITED STATES PATENT OFFICE

2,460,707

ELECTROTHERAPEUTIC APPARATUS

Thomas H. Moray, Salt Lake City, Utah

Application April 30, 1943, Serial No. 485,112

8 Claims. (Cl. 128—421)

This invention relates to electrotherapeutic apparatus, and to methods of applying electrical, radioactive, and other radiant phenomena therapeutically.

The invention is primarily concerned with the use of high potential, high frequency electricity though not necessarily limited thereto, in conjunction with radioactive and other types of electronic and radiation phenomena, for therapeutic purposes.

Among the objects of the invention are the following:

First.—To render highly effective, from a therapeutic standpoint, radioactive and other types of electronic and radiation phenomena, and, likewise, to render highly effective, from a therapeutic standpoint, high potential, high frequency electricity.

Second.—To augment the therapeutic effect of radioactive and other types of electronic and radiation phenomena by the conjoint use of high potential, high frequency electricity, and, conversely, to augment the therapeutic effect of high frequency, high potential electricity by the conjoint use of radioactive and other types of electronic and radiation phenomena.

Third.—To accomplish the above without danger of burning or of otherwise harming the patient.

Fourth.—To provide apparatus for accomplishing the above, which is relatively simple in construction and operation and relatively inexpensive to produce and operate.

Fifth.—To provide novel electronic and radioactive devices especially adapted for use in conjunction with high potential, high frequency electrical therapy.

I have found that, by enveloping a patient in a high potential, high frequency electrical field in such a manner that no closed circuit is completed through his body, radioactive and other electronic and radiation phenomena can be used therapeutically with considerably greater effectiveness than if used alone. The exact reason for this is not known, nor is it known definitely which, the electric field or the radioactive phenomena, acts upon the other to produce the advantageous results. It is thought, however, that the electric field, permeating the body of the patient as it does, attracts the radioactive emanations or radiations and enables them to penetrate considerably deeper into the tissues and vital organs of the patient than would otherwise be the case. In any event, remarkable therapeutic results have been achieved by use of the invention in the treatment

of malignant tumors, arthritis, sinus infections, and various other diseased conditions.

The invention contemplates the use, in therapeutics, of high potential, high frequency electricity to produce diversified forms of radiant energy, such forms being those which have been found best suited, individually, to benefit various human ailments. In accomplishing this purpose, several special discharge tubes have been developed to serve as treatment electrodes, by means of which correspondingly different curative results are obtained. Throughout the practice of the invention, a prime consideration is that only one terminal of any particular circuit shall be in contact with a patient's body at one time, so there will be no flow of current through a closed circuit of which the patient's body is a part. Such a terminal, too, is usually non-heat producing, so there is no danger of burning. In cases where there is a tendency for a tube to produce X-rays or other injurious rays, these are filtered out.

The present application constitutes a continuation in part of a copending application filed by me November 15, 1940, which bears Serial No. 365,798 and is entitled "Method of and device for the therapeutic application of electric currents and rays," and which has now become abandoned.

In the accompanying drawings, which illustrate several embodiments of apparatus preferred for carrying the method of the invention into practice:

Fig. 1 represents a wiring diagram of a preferred embodiment of apparatus for carrying out the method of the invention in general therapeutic work, several independent treatment stations being provided;

Fig. 2, a top plan view of the novel corona regulator of Fig. 1, employed in the circuit to control and adjust the current and as a governor to safeguard the transformer;

Fig. 3, a vertical section taken on the line 3—3, Fig. 2;

Fig. 4, a vertical section taken centrally through one novel type of discharge tube used as a treatment electrode in the apparatus of Fig. 1;

Fig. 5, a horizontal section taken on the line 5—5, Fig. 4;

Fig. 6, a vertical section taken centrally through another novel type of discharge tube used as a treatment electrode in the apparatus of Fig. 1;

Fig. 7, a horizontal section taken on the line 7—7, Fig. 6;

Fig. 8, a vertical section taken centrally through a novel discharge tube used as a treating device in the apparatus of Fig. 1;

Fig. 9, a horizontal section taken on the line **9—9**, Fig. 8;

Fig. 10, a fragmentary vertical section taken on the line **10—10**, Figs. 8 and 9;

Fig. 11, a fragmentary view in vertical section, and drawn to a reduced scale, of a tub bath capable of use as a treatment station in the apparatus of Fig. 1;

Fig. 12, a view similar to that of Fig. 11, but showing a shower or vapor bath arrangement for the same purpose;

Fig. 13, a wiring diagram similar to that illustrated in Fig. 1, but fragmentary in nature, and of a somewhat different embodiment of apparatus;

Fig. 14, an elevation, partly in central vertical section, of a novel tube used in the apparatus of Fig. 13 in place of the corona regulator of Figs. 2 and 3;

Fig. 15, a top plan view, partly in horizontal section on the line **15—15**, Fig. 14, of the tube of Fig. 14;

Fig. 16, a vertical section of another novel tube which may be used in place of the tube of Figs. 14 and 15;

Fig. 17, a vertical section taken on the line **17—17** of Fig. 16;

Fig. 18, a top plan view of still another novel tube which may be used in place of the tubes of Figs. 14 and 15 and of Figs. 16 and 17; and

Fig. 19, a vertical section taken on the line **19—19** of Fig. 18.

In accordance with the invention, provision is made for enveloping the patient in a high potential and, in certain instances, a high frequency electric field, and for applying to the patient, while so enveloped in the electric field, radiations and emanations having therapeutic value.

The apparatus of Fig. 1 is capable of administering various specific kinds of treatment, pursuant to the invention, at the several treatment stations provided. The treatment stations are indicated A, B, C, D, and E, respectively.

For supplying the high potential electric field, a suitable transformer is employed. This may be of any type capable of delivering high potential electricity, say from 10,000 to 30,000 volts. It is preferred, however, to utilize a conventional double magnetic circuit type of transformer, indicated at **10** in Fig. 1, having adjustable, laminated, magnetic shunts (not shown), the transformer being connected across an ordinary power line **11** charged with the customary 115 v. The output lines **12** from this transformer advantageously extend to the treatment stations A and B, respectively. The first secondary of the transformer **10** is preferably direct connected to the second secondary thereof. It is noted that this high potential electricity may be applied, without causing injury, direct to a patient who is not grounded. However, in order to safeguard the transformer **10** from damage by sparking across its output terminals, and to render the high potential electricity more suitable for therapeutic purposes, which is believed to include the automatic changing of the frequency to an extent which depends upon electrical characteristics of the patient's body, a governor or control device **14** is shunted across the leads **12**.

This governor or control device **14** is a sparking condenser of high capacity embodying a multitude of spark gaps. A preferred embodiment of this governor or control device **14** is illustrated in detail in Figs. 2 and 3.

As illustrated, the device comprises a cylindrical, electrically conductive plate **15** surrounded by a cylindrical dielectric **16**. An outer cylindrical and electrically conductive element **17** surrounds the dielectric **16** exteriorly. It is provided with a multitude (for example, 250) of inwardly extending prongs **17***a*, which are advantageously formed by stamping out, and inturning, triangular portions of the electrically conductive element **17**. The internal plate **15** preferably contacts the interior surface of the dielectric **16**, but, in any event, should lie closely adjacent thereto. Likewise, the tips of the prongs **17***a* preferably contact the outer surface of the dielectric. The several elements are advantageously mounted in a plug-in base **14***a*, which is adapted to mate with a suitable receiving socket (not shown) carrying the required electrical connections. The internal plate **15** connects with one of the electric lines **12**, while the external element **17** connects with the other electric line **12**, as shown diagrammatically in Fig. 1.

It is preferable that the dielectric **16** be in the form of a closed tube or envelope, as shown, and be exhausted to vacuum condition. The multitude of sparking prongs **17***a* product a brush discharge.

Where the dielectric **16** is not a closed tube or envelope, it is preferred that it be of quartz.

The treatment station A is a discharge tube of a novel type, exemplified by the tubes illustrated in detail in Figs. 4 and 5 and Figs. 6 and 7. Either tube is plugged into the circuit of Fig. 1 at a suitably provided, single-terminal outlet. High potential electricity is, therefore, fed directly into the tube, which serves as an electrode. The tube also embodies radioactive material, which supplies radioactive emanations to the patient simultaneously with the electrical discharge.

As illustrated in Figs. 4 and 5, the tube or electrode may comprise an electrically conductive discharge element **20**, having a supporting stem **20***a* and a major discharge cap or head **20***b*, which is preferably in the form of a thin, convex-concave plate. The head **20***b* may be spot welded to the end of the stem **20***a*.

The discharge element **20** is enclosed within a tube **21** of dielectric material, preferably glass, the stem **20***a* being fixed in the fused tongue portion **21***a* of the tube. The tube or shell **21** is fitted into an insulating base **22**, provided with a single plug-in terminal **23**, and an electrical connector **24** extends from the terminal **23** to the stem **20***a*.

The inside surfaces of the side walls of the tube or shell **21** are coated with a radioactive material, as at **25**. The coating is conveniently made from uranium salts or powdered carnotite or other radioactive ore. The ends of the tube or shell are left uncoated.

Air is evacuated from the tube **21**, and a small quantity of mercury introduced. The mercury is preferably triple-distilled to insure great purity. It is preferred that argon or like inert gas be also introduced.

Since the tube just described is plugged into the circuit of Fig. 1, the discharge element or cathode **20** is charged with high potential electricity, and, in its capacity of a treatment station in the apparatus of Fig. 1, serves as an electrode to similarly charge the patient. The patient is insulated from the ground, and the tube is applied directly to the afflicted part of his body, preferably in close contact with the body.

Because of the construction of the tube, radiation of a radioactive nature is also directed against the patient through the uncoated top end of the tube. This radiation has been found to differ somewhat from the radioactive emanations discharging from the side walls of the tube, and is thought to comprise rays lying close to X-rays on the radiation spectrum. These rays appear to have a definite healing value, and to lack the injurious nature of X-rays. Where a predominantly radioactive emanation treatment is desired, the side walls of the tube are placed against the body of the patient.

Best results are obtained when the discharge element or cathode **20** is made of an alloy metal compounded from copper, lead, sulphur, and, if desired, aluminum. The relative percentages of the several ingredients may vary considerably, but a satisfactory mixture comprises 5.0% copper, 55.0% lead, 30.0% sulphur, and 10.0% aluminum. Should aluminum not be used, the difference may be made up by additional copper.

In preparing the alloy, the copper and aluminum are heated to a molten state, after which the sulphur is added while stirring the mixture. After cooling, the mass is again melted, and the lead, in a molten state, is mixed with it, the molten mass being thoroughly stirred. This new mass is then cooled, being later reheated, and, while hot, rolled to make it ductile, so it can be shaped into the desired forms.

The discharge tube or electrode of Figs. 6 and 7 is similar to that of Figs. 4 and 5, having an enclosing tube or shell **26** which is evacuated. A cathode discharge element **27** is positioned within the shell, being fixed in the tongue portion **26***a*. A conductor **28** connects the stem **27***a* of the element **27** with a plug-in terminal **29**, which extends outwardly of the base **30**. The cap or head **27***b* of the element **27** differs from the cap or head **20***b* of the electrode of Figs. 4 and 5, in that it is spherical in form and hollow. It has an opening **31** formed at its top, contiguous with the top inside surface of the tube **26**. A quantity **32** of radioactive material, which may be the same as used for the coating **25** of the electrode of Figs. 4 and 5, is introduced into the tube or shell **26**, along with a relatively small quantity of mercury, before the tube is sealed tight. Such material **32** is preferably powdered or granulated, and is shaken into the hollow of the head **27***b* through the opening **31** before any given treatment is commenced. The mercury is provided primarily as a getter, and does no harm if shaken into the head **27***b* along with the radioactive substance. The mercury also tends to produce a vapor in the tube, which aids in the operation thereof. As in the case of the electrode tube of Figs. 4 and 5, this tube may have a radioactive coating **33** covering the inner surfaces of its side walls.

The treatment station B of Fig. 1 differs from the treatment station A only in the fact that a condenser **34** is interposed in the electric supply line **12**.

The treatment station C of Fig. 1 differs from the stations A and B only in the fact that the high potential electricity is supplied from the supply line **12** through an inductance **35**.

The treatment station D utilizes a germicidal discharge tube, a preferred form of which is illustrated in detail in Figs. 8, 9, and 10. The high potential electricity is taken by induction from the particular supply line **12** concerned. For this purpose, an induction coil **36** is provided, tapping the line **12** at **37**. A pair of leads **38** from an ordinary 115 v. supply source extend to a plug-in socket connection for the germicidal tube, one of the leads passing through a glass tube **36***a*, Fig. 1, which is disposed within and extends along the length of the induction coil **36**. Thus, high potential electricity is impressed, by induction, upon the ordinary current flowing through the particular lead **38** concerned.

The germicidal discharge tube of Figs. 8, 9, and 10 has a pair of discharge terminals **40** and **41**, respectively, positioned in an evacuated tube or envelope **42**, and electrically connected with plug-in terminals **40—1** and **41—1**, respectively, by means of stems **40***a* and **41***a*, respectively. The tube or envelope **42** and plug-in terminals are mounted in a conventional base **43**. It is preferred that insulating material **44**, such as a ceramic sleeve, cover the major portions of the stems **40***a* and **41***a*. A piece of lithium metal **45**, see particularly Fig. 10, is advantageously secured to the stem **40***a* adjacent the discharge terminal **40** to act as a getter. It may, however, be placed at any other convenient location in the tube. It is preferred that the discharge terminals **40** and **41** be formed of the special alloy previously described. Argon or other suitable inert gas is preferably injected into the tube or envelope **42**, as is, also, a small quantity of mercury. The mercury, by vaporizing, aids electrical arcing between the discharge terminals. As will be noted, the high potential electricity induced in the one lead **38** will manifest at the upper discharge terminal **40**, and will charge the patient simultaneously with the discharge into his body of germicidal rays from the tube.

The treatment station E embodies the tube of Figs. 8, 9, and 10, as above described, but impresses the high potential electricity directly on the patient instead of passing it first through the tube. For this purpose, a discharge device **50**, in the form of a soft, flexible pad in which a coil **50—1** is embedded, taps one of the high potential electric lines **12**. This pad **50** is wrapped around the patient's body adjacent the afflicted portion thereof, thus charging the patient. Any other electrode capable of charging the patient with high potential electricity may be used in place of the pad **50**. The germicidal tube has its terminals **40—1** and **41—1** plugged into a suitable plug-in socket connected to leads **52** which extend to an ordinary 115 v. source of supply. The high potential electricity with which the patient is charged is induced into the germicidal tube, thereby further activitating the discharge therefrom. A certain beneficial discharge from this germicidal tube will be had by induced activation alone, it being unnecessary, in such instances, to plug the tube into the 115 v. line.

Other types of germicidal and discharge tubes may be used in place of the tube of Figs. 8, 9, and 10, as, for instance, the well known infra-red and ultra-violet lamps, to produce results surpassing those ordinarily attained by the use of such infra-red or ultra-violet lamps apart from the apparatus of the invention.

It should be remembered that the patient is insulated from the ground while being treated at any of the treatment stations of the invention.

Figs. 11 and 12 show how a patient is treated, pursuant to the invention, while immersed in an electrically conductive fluid bath. In Fig. 11, a bath tub **53** is insulated from the ground by a layer of insulation 54. A treatment electrode of the type shown in any of the figure groups 4 and 5, 6 and 7, and 8, 9, and 10 is positioned to charge the fluid of the bath with high potential electricity, as well as to discharge healing radiations and emanations into the patient. The particular electrode illustrated is diagrammatic in form and is designated 55. It may be connected into the circuit of Fig. 1 as shown at any of the treatment stations A, B, C, and D. In Fig. 12, a shower or vapor stall 56 is insulated from the ground by a layer of insulation 57. A plurality of treatment electrodes are designated 58, respectively. These correspond to the treatment electrode 55 of Fig. 11. A water spray or vapor, such as steam, may be admitted to the stall 56 in any well known manner (not shown), thus enveloping the patient during treatment.

Another embodiment of apparatus, pursuant to the invention, is illustrated diagrammatically by the wiring diagram of Fig. 13. While no treatment stations are shown, those provided are identical with the several treatment stations designated A, B, C, D, and E in Fig. 1. The distinction in this embodiment of apparatus resides in the fact that a special generator of high frequency electricity is provided in the system.

A transformer 60 has its input terminals connected across an ordinary 115 v. electric power line 61. Electrical conductors 62 and 63 lead from the respective output terminals of the transformer to a high frequency generator of the Oudin coil type, indicated generally at 64, a variable condenser 65 being interposed in the line 62, and the circuit being grounded at 66. Output conductors 67 and 68, leading from the high frequency generator 64, provide connections for the several treatment stations in the same manner as illustrated in Fig. 1.

The transformer 60 may be any ordinary high voltage type. A governor or control device 69 is shunted across the conductors 62 and 63.

In the illustrated instance, the governor or control device 69 preferably takes the form of a vacuum tube, having the construction shown by Figs. 14 and 15, Figs. 16 and 17, or Figs. 18 and 19. These tubes all possess high capacity, and include elements effecting a brush discharge. They serve, as does the device 14 of Figs. 2 and 3.

The tube of Figs. 14 and 15 embodies an outer shell or envelope 70 of insulating material such as glass, a plastic, or fiber coated with shellac. Inside the shell 70 is a bi-cylindrical element 71 formed of electrically conductive material. Separating element 71 from the enclosing shell 70 are spacers 72 made of rubber, Bakelite, or other insulating material. Inter-fitting with the element 71 is a second electrically conductive, bi-cylindrical element 73, the two elements being separated by a dielectric 74. Inwardly of the element 73, and separated therefrom by a dielectric 75, is a corrugated, cylindrical element 76. The shell or envelope 70 is secured in an insulating base 70—1, provided with plug-in terminals. One of the terminals, designated 77, is electrically connected with the element 71, while another, designated 78, is electrically connected with the corrugated element 76. These two terminals connect with the conductors 62 and 63, as illustrated in Fig. 13, and the brush discharge takes place at element 76.

Under certain circumstances, it is desirable that the outer shell 70 be made of quartz glass, and that a filament 79 be provided, the filament being heated by connection, through plug-in terminals 80 and 81, with a source of low voltage heating current (not shown). Plug-in terminal 82, which is electrically connected with element 73, may be used instead of or in connection with the terminal 77, since element 73 acts in a manner similar to element 71. A getter 83 of suitable material, and an insulating and reflecting shield 84 may be provided, as shown. While the tube may have either a high or a low vacuum condition, or may be filled with an inert gas, I have also found it advantageous to fill the tube with a moist vapor. The tube acts as an oscillator for electric currents, and has an enormous capacity, a capacity many times that of a condenser of approximately equal size.

The tube of Figs. 16 and 17 comprises an outer shell or envelope 85, which may be made of metal, glass, or fused quartz. This shell is mounted in an insulating base 86. Inside the shell 85 is a metal plate 87, and, spaced apart therefrom, a corrugated metal plate 88. A plug-in terminal 89, which extends from the base, is electrically connected with the plate 87, and a second plug-in terminal 90 is electrically connected with the corrugated plate 88. These terminals are adapted to connect, through a suitable socket, with the electrical conductors 62 and 63 of Fig. 13.

Under certain conditions of use, it is desirable to have other elements in the tube. These are provided, and may be utilized or not as occasion warrants. A filament 91 is disposed between the plates 87 and 88. It is electrically connected with the two plug-in terminals 92 and 93, which are adapted to be connected to a source of low voltage heating current (not shown). A slit screen, comprising shields 94 and 95, with apertures 96 extending therethrough, is disposed adjacent that side of corrugated plate 88 which is remote from plate 87. The apertures 96 are in alignment with each other, and the shields 94 and 95 are made of lead or other material capable of screening off X-rays. Between shields 94 and 95 is a sheet 97 of material which is readily permeable to X-rays. Within the shell 85 there is also mounted a shell or envelope 98 of glass, quartz glass, or similar material, having a portion 98*a* which is ground like a lens and directed toward the slit screen. This shell 98 really constitutes a tube within a tube. A filament or cathode 99, comprising electrically conductive legs 99*a* and 99*b* and an electron-emitting portion 99*c*, is disposed within the shell 98, plug-in terminals 100 and 101 being electrically connected to the respective legs 99*a* and 99*b*. A bombardment element 102 is disposed within the shell 98 opposite the portion 99*c* of cathode 99. Within the shell 85, but outside the shell 98, is a reflector 103 directed toward the slit screen.

The tube of Figs. 18 and 19 is essentially the same as the tube of Figs. 16 and 17, being equipped with a shell or envelope 105, a base 106, a plate 107, and a corrugated plate 108, the two plates being connected to plug-in terminals 109 and 110, respectively, which are adapted to connect electrically with the conductors 62 and 63 of Fig. 13. There is a filament 111 and an inner shell or envelope 112, but no slit screen. Instead of a lens portion being provided on the inner shell 112, a partition 113 of lens formation is disposed between the inner shell and the corrugated plate 108. It is fused to the walls of the outer shell 105. Within the inner shell 112 is a filament or cathode 114, which corresponds to the similar element 99 of the tube of Figs. 16 and 17. A reflector 115 is directed toward the lens partition 113.

Reverting now to Fig. 1, there is another advantageous way of treating a patient pursuant to the invention. As shown at Y, a foot pedestal 120 may be provided for making the patient a part of a condenser. The pedestal comprises an electrically conductive plate element or electrode 121, connected electrically with one of the high potential lines 12, and covered by an insulating platform 122 upon which the patient rests his feet while being treated at any of the previously described treatment stations A, B, C, D, or E. The electrode 121 and insulating platform 122 are conveniently mounted in a frame 123, which insulates the plate from the ground. The insulating platform 122 is made of a high quality insulating material, such as first grade hard rubber. In certain instances it is desirable that the device be made in other than foot-pedestal form. For instance, it may be of cylindrical formation for use in a bed against any part of the patient's body.

If desired, the patient may be charged with the high potential electricity by direct contact with a metal or electrically conductive electrode in place of the pad 50 of treatment station E, or of the tube electrodes.

The invention has been described in the foregoing with sole reference to its use for therapeutic purposes. It should be noted, however, that inorganic matter may also be treated to advantage pursuant to the method and with the apparatus of the invention. It has been found that metals, for example, lead, have changed physical properties after treatment in accordance with the above. In instances where the invention is not being used therapeutically, it is not always necessary to insulate the subject from the ground.

Whereas this invention is here illustrated and described with respect to particular specific embodiments thereof, it is to be understood that various changes may be made in such specific embodiments and various other embodiments may be utilized by those skilled in the art without departing from the spirit and generic scope of the invention as set forth herein and in the claims which here follow.

Having fully described my invention, what I claim is:

1. Apparatus for applying radiant energy therapeutically, comprising means for producing high potential, high frequency electricity; a high capacity sparking condenser, and a treatment electrode connected in circuit with the foregoing, said treatment electrode including a discharge element adapted to charge the patient with said high potential, high frequency electricity, and radioactive means adapted to discharge radioactive emanations into said charged patient.

2. Apparatus in accordance with claim 2, wherein the sparking condenser is in the form of a vacuum tube of high capacity having mutually spaced capacity elements adapted to produce a corona discharge.

3. Apparatus for applying radiant energy therapeutically, comprising means for producing high potential, high frequency electricity; a high capacity sparking condenser; and a treatment device connected in circuit with the foregoing, said treatment device including discharge means adapted to charge the patient with said high potential, high frequency electricity, and radiating means adapted to discharge radiations into the charged patient.

4. Electrical treatment apparatus, comprising a high capacity sparking condenser; a treatment outlet electrically connected to said condenser; and means for electrically connecting said condenser to a source of high potential electricity.

5. Electrical treatment apparatus, comprising a transformer for producing high potential electricity; a high capacity sparking condenser electrically connected across the high potential output terminals of said transformer; and a treatment outlet electrically connected to said condenser.

6. Electrical treatment apparatus, comprising a transformer for producing high potential electricity; a high capacity sparking condenser electrically connected across the high potential output terminals of said transformer; and a plurality of treatment outlets independently electrically connected to said condenser.

7. Electrical treatment apparatus, comprising a transformer for producing high potential electricity; a treatment electrode electrically connected to one of the output terminals of said transformer; an electrical conductor sheathed by insulation electrically connected to the other of the output terminals of said transformer and disposed adjacent said treatment electrode so the subject to be treated may be placed between and in contact with the two; and a high capacity sparking condenser connected across the said outlet terminals of the transformer.

8. In electrical treatment apparatus equipped with means for the supply of high potential electricity and a treatment electrode, a high capacity sparking condenser electrically connected between the said supply means and the said treatment electrode.

THOMAS H. MORAY.

REFERENCES CITED

The following references are of record in the file of this patent:

UNITED STATES PATENTS

Number	Name	Date
628,351	O'Neill	July 4, 1899
647,687	Topham	Apr. 17, 1900
765,470	Friedlander	July 19, 1904
950,842	Davis	Mar. 1, 1910
1,156,317	Santos et al.	Oct. 12, 1915
1,193,018	Howard	Aug. 1, 1916
1,466,777	Winkelmann	Sept. 4, 1923
1,590,930	Falkenberg	June 29, 1926
1,655,783	Gallois	Jan. 10, 1928
2,010,018	Hodnette	Aug. 6, 1935
2,073,428	Schmid	Mar. 9, 1937
2,126,070	Wappler	Aug. 9, 1938
2,192,638	Dixon	Mar. 5, 1940

OTHER REFERENCES

Tousey; Medical Electricity and Roentgen Rays (1910), pp. 493 to 498. Copy in Division 55.

Two Patents of William J. Hooper

FIG. 1


B
B
10
12
r1
14
P
B x V
B
B

FIG. 3


48
46
44
50
42
A
40
52
D.C.
CURRENT

FIG. 2


20
D.C. CURRENT SOURCE
22
16
LINEAR CONDUCTORS
18
POLYSTYRENE INSULATION
28
34
26a
30
32
24
ELECTROMETER
26
26b

FIG. 4


60
62
68
66
70
72
60
62
64

FIG. 5



FIG. 6



FIG. 8


80
84
82a
90a
82b
86
90
82

FIG. 7


76
73
73a
71
74c
74

INVENTOR
WILLIAM J. HOOPER

BY
Oldham & Oldham
ATTORNEYS.

UNITED STATES PATENT OFFICE
CERTIFICATE OF CORRECTION

Patent No. 3,610,971 Dated October 5, 1971

Inventor(s) William J. Hooper

It is certified that error appears in the above-identified patent and that said Letters Patent are hereby corrected as shown below:

Col. 1, line 14, after "conductor" insert -- with -- and delete "electric charges".

Col. 1, line 45, "10^{17}" should be -- 10^{-7} --.

Col. 2, line 4, "nd" should be -- and --.

Col. 2, line 25, "3.6×10^{12}" should read -- 3.6×10^{-2} --.

Col. 2, line 44, "motion" should be -- motional --.

Col. 4, line 7, "anitgravitational" should read -- antigravitational --.

Col. 4, line 22, "he" should be -- the --.

Col. 5, line 20, "out" should be -- our --.

Col. 6, line 26, after "conductor" delete "o" and insert -- to --.

Signed and sealed this 16th day of May 1972.

(SEAL)
Attest:

EDWARD M.FLETCHER,JR.
Attesting Officer

ROBERT GOTTSCHALK
Commissioner of Patents

United States Patent

[11] 3,610,971

[72] Inventor William J. Hooper
Sarasota, Fla.
[21] Appl. No. 816,356
[22] Filed Apr. 15, 1969
[45] Patented Oct. 5, 1971
[73] Assignee Electrodynamic Gravity, Inc.

[54] ALL-ELECTRIC MOTIONAL ELECTRIC FIELD GENERATOR
5 Claims, 8 Drawing Figs.

[52] U.S. Cl. 310/10
[51] Int. Cl. H02n 11/00
[50] Field of Search 310/10, 11; 324/109; 336/181, 225; 338/284, 297

[56] References Cited

UNITED STATES PATENTS

2,553,875	5/1951	Shaw	338/284 X
3,259,784	7/1966	Vogel	338/297 X

OTHER REFERENCES

Textbook—The Electromagnetic Field in Its Engineering Aspects by G. W. Carter. 2nd Edition, 1967, Published by Longmans—48 Grosvenor St. London W.1, pp. 168, 169, 170 (Copy in Central Library, Washington, D.C.)

The Feynman Lecture on Physics by Feynman, pages 13-6 to 13-11; Addison-Wesley Publishing Co., New York.

Primary Examiner—D. X. Sliney
Attorney—Oldham & Oldham

ABSTRACT: This invention relates to an all-electric generator yielding a motional electric field in the space surrounding the device, but requiring no mechanical movements of its parts in generating this field. The Theory underlying the production of such a field postulates that each moving electron constituting the current in a linear conductor carries with it a loop of magnetic field energy about it.



ALL-ELECTRIC MOTIONAL ELECTRIC FIELD GENERATOR

This application is an extension of the teachings presented in my earlier filed pending applications, Ser. Nos. 722,587, filed Apr. 19, 1968 and 803,187, filed Feb. 28, 1969.

PRIOR HISTORY

The detection of a magnetic flux about a current-carrying conductor was first made in 1820 by Hans Christian Oersted. This discovery unified the then separate sciences of electricity and magnetism. My experimental discovery that this magnetic flux actually moves along the conductor electric charges the electric charges constituting the current has great promise of now unifying the three known fields of electricity, magnetism and gravitation.

For a better understanding of the invention, reference should be had to the accompanying drawings wherein:

FIG. 1 is a schematic illustration of a wire containing flowing electrical current indicating the magnetic field generated with respect thereto;

FIG. 2 is a perspective block diagram schematic of a preferred embodiment of the invention;

FIGS. 3 and 4 illustrate modifications of the generator of FIG. 2 adapted to techniques for studying and utilizing gravitational and antigravitational phenomena;

FIG. 5 illustrates the winding of the wire in the device of FIG. 2;

FIG. 6 illustrates the winding of the wire in the device of FIG. 4;

FIG. 7 illustrates the incorporation of a plurality of the devices of the invention into a spacecraft where they might be appropriately utilized; and

FIG. 8 illustrates a coil wound embodiment useful for producing the separation of oppositely charged ions in gases or liquids.

BACKGROUND INFORMATION

The law of Biot and Savart yields the magnetic flux density B (webers/m.^{2}) at a point distant *r* meters from the conductor carrying a current of I amperes and is given by

$$B=\mu_0 I/2\pi r \qquad (1)$$

where $\mu_0=4\pi\times10^{-7}$ webers/amp. meter. With reference to FIG. 1 of the drawings, this flux consists of circular magnetic loops directed counterclockwise, as shown by arrow 10, for current directed in a linear conductor wire 12 at right angles to this paper and outwardly toward the reader.

Electrons producing this flux will be moving perpendicularly into the paper, carrying the flux B with them, at a velocity V meters/sec. Thus, at any point P, distant r_1 from the long linear conductor 12, there will be existent a motional electric field of intensity $E=B\times V$ volts/meter directed radially inward toward the wire in the plane of the paper, as indicated by vector arrow 14, where $B\times V$ is the vector cross product of *B* and *V*.

PREFERRED EMBODIMENT

The preferred embodiment of the invention is illustrated in FIG. 2 and consists in part of many insulated linear conductors indicated generally by numeral 16, all parallel, packed and held in close proximity, and connected in series, so as to form a solid package 18 preferably cylindrical in shape. When a constant direct current from a source 20 is caused to flow through wires 22 this device with its axis in the vertical direction, half of the linear conductors 16 will have current flowing upward and half downward. It will be a noninductive device, since surrounding it the magnetic flux due to the upward currents will be superimposed on the flux due to the downward currents, so that no magnetic flux can be measured. On the well recognized "Principle of Superposition of Fields," each one exists however, and acts as though the other was absent.

When the package 18 of linear conductors has a circular cross section there will exist two systems of circularly directed magnetic flux, one directed clockwise and the other counterclockwise as seen from above, and one set moving upward and the other set moving downward. What is of capital interest however is that each of these two systems give rise to equal radially and inwardly directed $B\times V$ motional electric fields distributed laterally in horizontal planes in the space about the cylindrical device. Here we have a field which is not magnetic, is not electrostatic, and which I have shown experimentally to be immune to electrostatic shielding. No such spacially distributed field is known to Physics today except that of gravity. I have shown theorectically that this field should act attractively on electrically neutral matter. I have shown experimentally that the intensity of this field can be measured with the aid of an electrometer system 24, 28 driven by the potential difference induced electromagnetically in the conductors 30 connecting the electrometer to the capacitor plates 26*a* and 26*b* of the capacitor 26. The electrometer head 24 actuates a visual dial indicator 28.

At cryogenic temperatures the drift velocity of the electrons in the linear conductors will be greatly enhanced. Theoretical calculations indicate that this velocity in copper at 20° C. is of the order of 3.6×10^{-2} cm./sec. in a current density of 480 amp./cm^2. The random velocity of free electrons in conductors is theoretically estimated at 10^8 cm./sec. At superconducting temperatures when the electrical resistance approaches zero, it is generally believed that the drift velocity of electrons approaches the value of 10^8 cm./sec. This velocity is 10^{10} times greater than the velocity at 20° C. (See "Physics," Halliday and Resnick, pages 681 and 691, J. Wiley, 1962). This indicates that the intensity of the $B\times V$ field about the device, herein described, might possible be enhanced 10^{10} times at or near the absolute zero of temperature. Hence, the invention contemplates that each of the devices described hereinafter will preferably be operated at or below the critical temperature at which the conductor used becomes superconducting. As the state of the art advances new conducting materials will undoubtedly become available with critical temperatures very considerably above the absolute zero.

Not only does the device that has been described in FIG. 2 afford apparatus hitherto unavailable for the generation of a spacial distribution of the motion electric field, but it affords means for investigating the properties of this field in connection with its relation to gravity and antigravitational phenomena. In addition, it affords for the first time, a direct experimental method for determining the electron drift velocities and mobilities in linear conductors made of different materials.

When the cylindrical capacitor 26 is charged by the $B\times V$ field and its potential difference (P.D.) measured, it is determined by the equation

$$\text{P.D. (volts)}=B\times V\cdot l \qquad (2)$$

where *l* is the distance between the thin capacitor plates. The direct measurement of V meters/sec. can then be made

$$V=\text{P. D. (volts)}/Bl\ \text{m./sec.} \qquad (3)$$

where B is in webers/m.^{2}.

This device will exhibit an attractive force on electrically neutral matter, better defined as a differential force; i.e. the difference between a pull and push, in which the pull is greater. (See reference to general theorem, page 125, The Mathematical Theory of Electricity and Magnetism, by Sir James H. Jeans) The $B\times V$ field is an electrical field acting on all the elementary charges comprising the atoms of matter, electrons, protons and even neutrons, as I believe neutrons also consist of electrons and protons in close bond. The $B\times V$ force being relatively weak does not ionize the atoms of matter, but being immune to shielding, electrically polarizes them. This causes a slight elongation of some of the electrons orbits within the atoms in the direction of the field. The positive charges move slightly into the more intense region of the converging, radially directed field while the negative charges move slightly further way from the device into the weaker portion of the field. Thus the differential force between the pull and the push upon the component parts of an atom results in the polarization of the atoms and a resultant attractive force, equivalent, I believe, to that of gravity.

A small, electrically neutral, simple pendulum 32 suspended close to one side of my device of FIG. 2, about pin 34, should thus undergo a slight measurable deflection under a fairly strong $B \times V$ motional electric field. At cryogenic temperatures this attractive force should be greatly enhanced. When the device is lying horizontally, a gravity meter placed centrally over it should give a measurable reading in milligals.

Modifications of my generator such as are shown in FIGS. 3 and 4 show diverse methods for studying gravitational and antigravitational phenomena which the invention makes possible. FIG. 3 illustrates a rectangular coil 40 made up of a single wire passed many times in the coil configuration so as to provide a large leg A preferably having a circular cross section. However, any cross-sectional configuration would meet the objects of the invention as long as the wires are parallel to each other and closely packed. About one leg of the coil, a cylindrical shell 42, made of electrically neutral, conductive or nonconductive material, is suspended by a carrier frame 44 from one end of a sensitive beam balance 46. The beam pivots about a support bar 48 and carries a load 50 to normally counterbalance the weight of the shell 42. When a fairly strong DC current I is fed through lines 52 and is built up in the coil, the flux density B is generated in the region of the cylindrical weight whose walls are a distance r from the central axis of the coil and n is the number of linear conductors in the coil.

$$B=\mu_0 nI/2\pi r \text{ (webers/meter}^2\text{)} \qquad (4)$$

If the current I is suddenly cut off the flux B will rapidly collapse. This flux in the act of collapsing should cross the walls of the suspended cylinder with a considerable inwardly directed horizontal velocity of V meters/sec. This should yield a very considerable vertical $B \times V$ in the walls of the cylinder directed either up or down, depending on the direction of the current in the coil.

In this device the motional electric field $B \times V$ is not convergent, but is uniformly vertical, hence the pull and push exerted on the electric components of the atoms in the cylinder will be equal. In other words the action of this field will either enhance or decrease the state of polarization already existing within the cylinder and produced by the gravitational field of the earth. If the polarization is increased, then the gravitational pull of the earth's field should be greater. If the polarization is decreased then the weight of the cylinder should be less. It is conceivable that the polarization could be reduced to zero. In this case, the object should be weightless. If the intensity of the depolarizing $B \times V$ field is still further increased, then polarization in the opposite direction to that produced by the earth's field should be achieved. In this event the earth's gravitational field would act repulsively on the cylinder. This would be antigravity in its truest sense.

The apparatus I have just been describing acts only momentarily (during the time interval in which the flux is collapsing) to change the weight of the cylinder shell 42 (shown in FIG. 3).

It is desirable to have an apparatus with which to experimentally study gravitational and antigravitational phenomena under steady continuous conditions. In FIG. 4 of the drawings is shown another modification of the device shown in FIG. 2. Here I utilize a noninductive coil wound in the form of a solid, low, thick walled, hollow, right circular cylinder, and indicated generally by numeral 60. DC current is supplied through lines 62 to the coil 60. In the region directly beneath this coil disk 60 I place a similarly shaped nonferrous disk 64, suspended by a carrier 66 to the end of a beam 68. The beam 68 is pivotal about a fulcrum 70 and is counterbalanced by a load 72. For positions of disk 64 below coil 60, the $B \times V$ field can only be directed vertically upward when a continuous DC current is flowing in the wires composing the disk 60. It should be noted that this field is practically uniform and parallel close to the disk, hence it is not attractive in its action on neutral matter. Its action on such matter can only change the state of electrical polarization in the matter. Any change thus effected in the state of polarization should cause the earth's gravitational field to act less intensely, on any object placed close to the under surface of the device, causing it to weigh less, become weightless, or to actually be accelerated upward by the anitgravitational action of the earth's field.

FIG. 5 of the drawings illustrates the manner in which the noninductive device in FIG. 2 is wound with wire 22, by turning the linear conductors back on themselves through a 180° turn. FIG. 6 illustrates the way the noninductive windings of the device illustrated in FIG. 4 is achieved. One very long insulated wire is simply turned back on itself at its midpoint and wound double into a solid coil held together in the shape illustrated.

FIG. 8 illustrates a modified embodiment of the invention which comprises a wire coil 80 either simply wound, or noninductively wound, around a hollow tube 82. Electrical current is passed to the coil 80 through wires 84, and at low temperature this coil will produce a radially, outwardly directed, internal $B \times V$ field from the axis 86 of the cylinder to the internal circumference 80*a* of the coil 80. The electrical wire making up coil 80 is preferably a ribbonlike conductor which is coated with any appropriate electrical insulation. A minimum space between adjacent turns with concentricity between adjacent turns is the preferred winding embodiment for coil 80. As many courses of turns as deemed appropriate to generate field strength desired will meet the objects of the invention. The tube 82 is preferably made of material having little or no magnetic permeability. Both the coil 80 and tube 82 are stationary.

An apparatus of the type illustrated in FIG. 8 might be utilized to effect separation and concentration of fluids. For example, in the desalinization of water, a $B \times V$ electric field generated by the passage of the current through the coil 80, acts upon the disassociated ions of the sodium chloride in solution. Hence, by introducing a flow saline water at end 82*a* of tube 82, and providing a concentric separating tube 90 at end 82*b* of tube 82, increments of fluid which are concentrated with chlorine and depleted of solium may be drawn off through the stationary tube 90, while the increments of fluid which are concentrated with sodium and depleted of chlorine may be drawn off through the space between the exterior walls of tube 90 and the interior walls of tube 82.

FUTURE APPLICATIONS

This country's space projects have become expensive beyond the ability of the average man to comprehend. Achieving lift by means of costly propellants will some day soon be seen as akin to primitive men's use of awkward clubs as a means of exerting force. In a very short interval of time an intense $B \times V$ field should effect the reversal of the gravitational polarization of an object. Once achieved, only a very small expenditure of energy would be required to hold the polarization. Energy from the atoms of the earth would supply the lift and propulsion through the medium of the earth's gravity field. The most formidable problem would appear to be the problem of holding the $B \times V$ generator at cryogenic temperatures. In view of the overall possibilities of this invention, this problem does not appear to be incapable of a solution. A breakthrough in finding superconducting materials or even near superconducting at slightly elevated temperatures from those presently required would greatly aid in the solution of this problem.

FIG. 7 of the drawings illustrates in outline, the future possible application of this device, obtaining regulated lift by an operator 71 adjusting the current into the coils 73 and 74 which incorporate the structural features of the devices of FIG. 4. The antigravity gravity control features of the coils 73 and 74 thus control the lift and movement of vehicle 76. Suitable cryogenic generators 73*a* and 74*a* are associated with each of the coils 73 and 74 to provide the cooling thereof to as near absolute zero as possible to give the enhanced current passage characteristics necessary to the objects of the invention.

While I have demonstrated that AC current can be used in my device, it appears at present that DC current is much to be preferred.

This invention could be uniquely adapted to a communication system from one side of a solid barrier to the other side whether this barrier be solid concrete or battleship armor, by pulsing the $B\times V$ generator coil with signals, Morse Code or even voice modulated signals to be picked up by a capacitor-electrometer circuit on the other side of the barrier. Secret communications could be carried on and with the electrometer circuit as shown in FIG. 2 connected to a relay radio broadcasting unit, so that one might conceivably broadcast by radio from the interior of a solid metallic enclosure.

It is conceivable that the invention might be useful in the highly specialized art of concealed detonation devices. A detonating circuit connected to the capacitor electrometer receiving circuit of my device such as shown in FIG. 2 could be actuated through a solid barrier by out $B\times V$ generating coil placed on the other side of such a barrier.

It is conceivable that for some specialized purposes, it might be highly desireable to transmit electrical power from one side of a fixed solid barrier, concrete or armor plate, etc. by pulsing, DC or AC, in our $B\times V$ coil on one side of such a barrier. A resonant LC circuit could pick up these $B\times V$ pulsations and supply a source of electrical power on the other side of the barrier, in a manner somewhat analogous to my electrical receiving methods outlined in U.S. Pat. Application, Ser. No. 803,187, identified above.

In accordance with the patent statutes, only the best known embodiments of the invention have been illustrated and described in detail, but it is to be understood that the invention is not limited thereto or thereby, but that the scope of the invention is defined in the appended claims.

What is claimed is:

1. Apparatus for demonstrating an electrical phenomenon comprising,

a coil made from an electrically conductive material having a very large plurality of sections compacted in close proximity arranged in substantially complementary relation around a common central axis, where the coil forms a solid cylindrical shape with the sections parallel to the axis thereof, and

means to pass current through the coil so that about half the sections will pass current in a direction opposite to the other sections to cancel magnetic flux.

2. Apparatus according to claim 1 where adjacent sections are electrically insulated from each other, and the coil comprises a single wire bent back on itself to make the sections.

3. Apparatus according to claim 1 which includes means to increase the passage of electrical current through the conductor.

4. Apparatus according to claim 3 where the means to enhance is a cryogenic generator which reduces the temperature of the conductor o or below its critical temperature at which it becomes superconductive.

5. Apparatus according to claim 1 which includes an elongated hollow tube having an axis, the conductor formed around the tube.

Patented April 11, 1972 3,656,013

4 Sheets-Sheet 1


3
N
4
8
2
P
9
1
5
7
6
+

FIG.1



FIG.2

INVENTOR:
WILLIAM J. HOOPER

BY Oldham & Oldham
ATTORNEY.


10
12
24
26
28
13
27
14
41
15
25
23

FIG.3


33
34
35
36
27
28
25
26
5
46
30
24
57
29
56
54
31
32
49
48
55
47
51
40
41
50
39
38
43
42
44
5
23
37

FIG 4


4
11
22
12
44
45
46
21
10
52
51
13
20
50
55
14
19
15
46
18
17
16
4

FIG.5


7
7
112
153
146
147
150
148
151

FIG.6


112
113
111
146
111
113
112
151
150

FIG.7


101
104
101'
102
105
102'
103
106
103'
100
108
109
107
107
112
113
111
111
113
112
108
112
113
111
111
113
112
109
108
109
108
107
107
109
108

FIG.8


280
250
256
200
254
270
210
261
230
260
220
264
262

FIG 11



FIG. 9


ELECTROMETER

FIG. 10

United States Patent
Hooper

[15] 3,656,013
[45] Apr. 11, 1972

[54] **APPARATUS FOR GENERATING MOTIONAL ELECTRIC FIELD**

[72] Inventor: William J. Hooper, Cuyahoga Falls, Ohio

[73] Assignee: Electrodynamic Gravity, Inc., County of Sarasota, Fla.

[22] Filed: Apr. 19, 1968

[21] Appl. No.: 722,587

[52] U.S. Cl. 310/10
[51] Int. Cl. H02k 1/00
[58] Field of Search....310/10, 11, 178, 177, 156, 310/42, 268, 211, 169, 216, 269, 259; 103/1; 55/2, 14, 101, 123, 127, 120; 73/194 EM; 328/233–238

[56] **References Cited**

UNITED STATES PATENTS

3,285,179	11/1966	Resler, Jr.	103/1
3,336,489	8/1967	Volger	310/40
3,431,441	3/1969	Shair	310/11
399,800	3/1889	Thomson	310/115
460,087	9/1891	Hewett	310/46
2,066,343	1/1937	Gillen	310/46
2,558,540	6/1951	Clos	310/46
2,705,762	4/1955	Pile	310/104
3,277,631	10/1966	Sunnen	55/3
3,385,983	5/1968	Bohn et al.	310/11

OTHER PUBLICATIONS

Book–Theory and Calculation of Electrical Apparatus by C. P. Steinmetz; N.Y.– 1917.

Text Book– The Electromagnetic Field in its Engineering Aspects G. W. Carter– 2nd edition– 1967 pages 168 to 171 incl., 328, 329, 334, 335 and 336

The Feynman Lecture on Physics by Feynman, Leighton and Sands Addison– Wesley– Publishing Co., New York; pages 17–1 and 17–2

Primary Examiner—D. X. Sliney
Attorney—Oldham & Oldham

[57] **ABSTRACT**

Apparatus for producing and demonstrating properties of motional electric fields by means of rotating magnetic flux produced by a plurality of magnets extending parallel with the axis of rotation, said flux of these magnets being put into rotation about a common axis by mechanical or by electro magnetic means.

6 Claims, 11 Drawing Figures



APPARATUS FOR GENERATING MOTIONAL ELECTRIC FIELD

This invention relates to the generation of motionally induced electric fields as distinct from electrostatic fields, and as distinct from the electric field (illustrated by transformer action) which is induced by the time rate of change of magnetic induction. Hence, all reference herein to a motional electric field means the electric field that is generated by the movement of magnetic flux.

The motional electric field generated by rotational motion of magnetic flux is non-uniform in both direction and radial intensity. Particles (large or small) of matter (solid, liquid or gaseous) which are within the ambit of this motional electric field are acted upon with a force which tends to accelerate them. It is well known that a particle carrying a charge Q (coulombs) in an electric field of intensity E (Newton/coulomb) will be acted upon by a force F (Newton) given by the equation $F = EQ$. The electric intensity E of a motional electric field is given by the vector equation $E = B \times V$, where B is the magnetic flux density at a point in space, expressed in webers per square meter, and V is the velocity of the moving magnetic flux at that point in space, expressed in meters per second. What is not so well known, however, is the fact that a non-uniform electric field exerts a force upon electrically neutral matter. In his celebrated text, "The Mathematical Theory of Electricity and Magnetism", Sir James H. Jeans describes, in the case of a non-uniform electrostatic field, how a "slab of dielectric will be sucked in between the plates of the condenser" thus demonstrating the mechanical force produced by such a field. He states (P. 125), "This, as will be seen later, is a particular case of a general theorem that any piece of dielectric is acted on by forces which tend to drag it from the weaker to the stronger parts of an electric field of force." According to Clerk Maxwell in "Electricity and Magnetism" (Vol. II, p. 181), Faraday discovered that the electric field due to electromagnetic induction penetrated within and throughout all materials. The motional electric field is just such a field. Apparatus for demonstrating the "general theorem", stated by Jeans, has, in the case of the non-uniform motional electric field, not heretofore been provided.

Accordingly, it is one of the objects of the present invention to provide a device for generating a non-uniform motional electric field whose force is of magnitude such that it can be sensed.

Since the motional electric field acts within and throughout all matter, such a non-uniform field will exert a physical force on any kind of electrically neutral matter, in a manner quite analogous to that of the electrostatic field with respect to dielectric material.

Another object of the invention is to provide apparatus for obtaining useful work from a non-uniform motional electric field.

The several objectives of the invention may be accomplished by rotating an elongate magnetic field about an axis which is concentric with the field and parallel with the field's elongation. For example, an array of magnets may be mounted on a rotor so that all magnets are parallel with the axis of the rotor, and all have the same polar orientation relative to the rotor. A solenoidal electro magnet, or another array of magnets, with magnetic axis concentric with the rotational axis may also be employed to enchance the flux density of the array of rotating magnets by flux linking with them. When such an array of magnets is rotated about the axis of the rotor, the magnetic field of each is rotated with it. As another example, an elongate magnetic field can be rotated about its axis, without mechanical movement, by the provision of stationary solenoidal electro magnets arrayed like the staves of a barrel and connected to a source of multi-phase alternating current (half wave rectified to prevent reversal of sign) in a manner comparable to the stator winding of a three-phase motor to produce "revolving field." While the composite magnetic field is thus in rotary motion, every charged, or uncharged particle of matter (solid, liquid, or gaseous) within the non-uniform motional electric field thus generated in the neighborhood of the rotor, will be acted upon by a force due to the electric intensity E. Positively charged particles will be forced in the direction of the vector E, negatively charged particles will be forced in the opposite direction, and electrically neutral matter will be pulled from the weaker regions of field intensity to the stronger regions. This latter mechanical force is called a differential force due to the action of the field on the internal electrical polarization of the neutral matter.

The three vectors E, B, and V are always (with a possible exception) mutually at right angles to each other. If the thumb of the right hand is pointed in the direction of the magnetic flux density vector B, and then rotated like a right-handed screw so that it points in the direction of the velocity V of the moving magnetic flux, then the forefinger of the right hand will point in the direction of the electric vector E. The rotation of the composite magnetic flux about its axis produces a motional electric field which will, except at the axial ends of the magnetic field, be quite generally directed radially with respect to the axis of rotation. The possible exception is the case of a magnet having a homogeneous electrically conductive core of perfectly circular cross-section, in which case the force of the electric field may be somewhat off radial.

With a given polar orientation of magnets relative to the axis of rotation, rotation of the magnetic field in a clockwise direction will generate a motionally induced electric field of sign (positive or negative) opposite that which is generated when the rotation is counterclockwise. For any given sense of rotation, reversing the polar orientation of the magnets relative to the axis of rotation likewise reverses the sign (positive or negative) of the motionally induced electric field. Reversing both the direction of rotation and the polar orientation of the magnets (a situation exemplified by viewing the apparatus first from one axial end, and secondly from the opposite axial end) produces no change in the sign (positive or negative) of the motionally induced electric field.

In the accompanying drawings, three embodiments of the invention are exemplified. Also, there are two model schematics to illustrate in its simplest form the principle of the invention, in which a plurality of commonplace permanent magnets are mounted upon a rotor.

The first embodiment is one in which an array of electro magnets is mounted on a rotor having a hollow center, through which particles of matter can be moved and their response to the motional electric field perceptibly demonstrated.

Second, there is an embodiment in which electro magnets are arrayed as in the first embodiment, but are stationary and their composite magnetic field is rotated electromagnetically by phase displacement.

Third, there is an embodiment in which a pair of oppositely rotating rotors, nested one within the other, are each provided, on its circumference, with an array of electro magnets oriented as aforesaid on each rotor, but oppositely oriented on the respective rotors, and wherein the effect of the motionally induced electric fields can be perceptibly demonstrated by the behavior of particles of matter externally of the rotor.

In the accompanying drawings:

FIG. 1 is a diagrammatic view illustrating the effect of rotating an array of spaced permanent magnets about an axis which is parallel with each of the magnets when all magnets have corresponding polar orientation;

FIG. 2 is a diagrammatic view representing a side elevation of the arrangement shown in FIG. 1, and illustrating the external magnetic flux paths of the several permanent magnets;

FIG. 3 is a perspective view of a rotor for generating a radially directed motional electric field in accordance with one embodiment of the invention, wherein electro magnets are arrayed within a hollow rotor with axes parallel to that of the rotor;

FIG. 4 is a sectional view taken along a diametric plane of the rotor shown in FIG. 3, together with its cooperating parts;

FIG. 5 is a sectional view along line 5—5 of FIG. 4, and showing, in addition, driving means for the rotor.

FIG. 6 is a sectional view taken along a diametric plane of a stationary form of apparatus similar to that shown in FIGS. 3, 4, and 5, but wherein the magnetic flux field is rotated electromagnetically by phase displacement;

FIG. 7 is a sectional view taken along line 7—7 of FIG. 6;

FIG. 8 is a wiring diagram for the apparatus shown in FIGS. 6 and 7.

FIG. 9 is a longitudinal sectional view of an apparatus having a plurality of rotors for generating a $B \times V$ electric field;

FIG. 10 is a sectional view taken along line 10—10 of FIG. 9; and

FIG. 11 is a diagrammatic illustration of an apparatus for exhibiting moving field phenomena.

In FIGS. 1 and 2, the principle of the invention is diagrammatically illustrated with the utmost simplicity, wherein a catena of magnetic flux fields, all with the same polar orientation, is produced by arranging an array of rod-type permanent magnets parallel with each other, and parallel with the axis about which they are to be rotated. In FIG. 1, the axis of rotation is designated 1, and may be considered as the center of a shaft of a rotor, preferably composed of material having low, if any, magnetic permeability, and low, if any, electrical conductivity. The periphery of such a rotor is designated by the circle 2. In the form shown, a series of permanent magnets 3, 4, 5, 6, 7, and 8 is appropriately secured to the periphery of the rotor with the respective magnets in equi-spaced relationship, and all with their north poles addressed in the same direction which, as shown in FIG. 1, is in the direction of the reader or, as shown in FIG. 2, to the reader's right. The external flux fields from the respective permanent magnets 3, 4, 5, and 6 are illustrated in FIG. 2, where it will be observed that the external flux path of all magnets is from right to left, a relationship designated by the plus (+) marks in FIG. 1. With such an arrangement, the flux fields of all magnets may be concurrently rotated about axis 1. Considering the rotation to be in the direction of arrows 9 and the polar orientation of the several permanent magnets to be as illustrated, a $B \times V$ motional electric field will be generated both externally and internally of rotor periphery 2 upon rotation of the rotor. The thus generated motional electric field will exert a radially directed force upon every particle of matter, neutral or charged, such as particle P, which is within the ambit of the catena of magnetic flux fields. The magnitude of the so impressed electric field intensity will depend upon the magnetic flux concentration at the particle P and the relative velocity between the flux field and particle P. While, if particle P is in motion, its velocity must be considered in arriving at the relative velocity V (in the formula $E = B \times V$) the disclosure will be simplified if the particle P be considered as stationary, and in such event V will be 2 R times S, where R is the radial displacement of particle P from axis 1, and where S is the revolutions per unit of time made by the rotor. Hence, with the particle P stationary, the magnitude of the force impressed upon it is increased when the speed of rotation of the rotor is increased at a given flux density; and is increased by an increase in the flux density at a given speed of rotation. The direction in which the force of the motionally induced electric field acts upon particle P is always *perpendicular to the magnetic flux field B and to its velocity V.* The sign of the electric force field may be either positive (acting radially outward from the axis of rotation) or negative (acting radially inward toward the axis of rotation), which, for any given polar orientation of the permanent magnets, may be reversed by reversing the direction of rotation of the rotor. With the polar orientation shown in FIGS. 1 and 2, and the direction of rotation indicated by arrow 9, if particle P is a proton or a positively charged molecule, the force of the $B \times V$ *electric field will be radially inward as indicated by the* solid line arrow attached to particle P; but if particle P is an electron or a negatively charged molecule, the particle will tend to move radially outward as shown by the broken line arrow; and if the particle P is electrically neutral, it will tend to move in the direction of increasing electrical intensity E. Increase of E requires either that both B and V be increasing or that one be increasing at a sufficiently greater rate than the other is decreasing so that the product $(B \times V)$ increases. In the relationship of field and particle shown in FIG. 1, the product $(B \times V)$ increases radially inward.

For practical purposes, however, commonplace permanent magnets produce insufficient flux density in their external flux paths to impress upon a particle of charged matter such as P, an electric force of sufficient magnitude that the force of the electric field can be measured with ease, at least at speeds of rotation within practical limits. Consequently, the practical embodiments of the invention, later to be described, make use of electro magnets of a form capable of producing external flux fields of vastly greater flux density B, as well as higher velocities V.

The term "unipolar induction" has been used to indicate the induction of an electric field in the vicinity of an axially symmetrical magnetic system rotating about its axis of symmetry. There has been disagreement about whether as the magnetic system is rotated the lines of magnetic induction are carried with it or remain stationary while the magnetic system rotates through them. For example, when a bar magnet is rotated about its magnetic axis, it is believed by many that the magnetic field is stationary. I have demonstrated that under certain conditions, at least, the magnetic lines can be made to move, and I have devised certain methods and apparatus for utilizing this phenomena as in the production of localized and high intensity electric fields.

Turning now to FIG. 11 of the drawings, an apparatus for demonstrating certain magnetic phenomena is illustrated in diagrammatic form. A magnetic system, indicated generally by numeral 200, includes a pair of permanent magnets 210 and 220 which are axially magnetized and mounted in axial alignment between the ends of a U-shaped yoke 230 of highly permeable magnetic material. The adjacent surfaces of magnets 210 and 220 being of opposed polarity are spaced apart, providing an air gap 240 therebetween. The lines of magnetic flux are shown in the drawing and indicated generally by numeral 262. A brass rod 250 extends axially through magnets 210 and 220. The magnetic system 200 is rotatable about rod 250. A stiff conductor 260 is electrically connected by a collar 261 at one end in rotatable or fixed relation as selectively desired, with the brass rod 250 at a point in the gap 240 between magnets 210 and 220. The other end of conductor 260 extends substantially perpendicularly from rod 250 to a distance in space away from the magnets and yoke where the magnetic field falls to approximately zero intensity. In order to complete an electrical circuit through galvanometer 270 and conductor 280 to the brass rod 250 and conductor 260, a flexible and extensible electrical wire 264 connects the end of conductor 260 to the galvanometer 270. A gear 252 locked alternatively by set screw 254 to rod 250 or by set screw 256 to yoke 230 can serve to provide driving motion to either the rod 250 or YOKE 230 as selectively desired. Normally, for the purposes of the experiment, the driving motion will be reciprocal because of the connection of wires 280 and 264.

With this apparatus, if the magnetic system 200 is held fixed and a given angular displacement imparted to conductor 260 *by rotating it horizontally about or with rod 250 through the* air gap at a given angular speed, a voltage is induced which provides a deflection of galvanometer 270. Furthermore, when the conductor 260 is held fixed and the magnetic system 200 rotated through the same angular displacement about rod 250, at the same given angular speed, a similar voltage of exactly the same magnitude but opposite direction is induced in the galvanometer circuit. The same deflection is obtained whether or not the magnets 210 and 220 rotate with the yoke 230 or are held stationary while the yoke alone is rotated. This indicates clearly that the lines of magnetic induction in the quantity rotate about the axis of rotation 250 as if they were rigidly attached to the magnetic system 200.

A most important aspect of the operation of the apparatus of FIG. 11 is noted when the magnets 210 and 220 are held fixed in relation to the conductor 260 and rod 250 and the yoke 230 is rotated about the rod 250. This action causes induction of current in the galvanometer circuit exactly as occurs when the entire magnetic structure or the conductor itself are moved. However, if the magnetic yoke 230 and conductor 260 are held fixed and magnets 210 and 220 rotated, there is no deflection of the galvanometer. Thus, it appears that the yoke structure plays an important part in controlling movement of the magnetic flux. Furthermore, it should be noted that the magnetic flux does not link the galvanometer circuit in the usual sense that this term is used, but that a current is induced in the galvanometer circuit through the action of the conductor 260 in merely cutting across the field extending between adjacent faces of magnets 210 and 220.

It has also been found that the permanent magnets 210 and 220 may be replaced by an electromagnet and the results described above duplicated. Furthermore, it can be demonstrated that the magnetic flux within the air core of a solenoid may be rotated about its magnetic axis. A brass tube formed in the shape of a toroidal C has a winding applied to its entire length with holes drilled in the tubing to receive a brass rod, as 250 in the structure shown in FIG. 11. With the winding energized, the above-described procedures produce similar galvanometer deflections.

This application is concerned with certain methods and apparatus which make use of the phenomena described above.

Referring now to FIGS. 3, 4, and 5 for an illustration of the second embodiment, a tubular rotor 10 is provided on its inner periphery with 12 keystone cross-sectional electro magnets 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, and 22 of the solenoid type. As seen in the cross-section of FIG. 5, the several electro magnets are arranged as sectors of a cylindrical annulus. While in the form shown, the several electro magnets 11–22 are shown in circumferentially wedged relationship, whereby to minimize the likelihood of relative movement radially inward as at standstill, as well as in the interest of achieving substantial uniformity of external flux density throughout the inside circular area of the rotor, it will be understood that when and if desired, the several electro magnets can be circumferentially spaced one from the other, and, if desired, a spacer of relatively low, if any, magnetic permeability interposed between them. Any suitable means may be employed for securing the several electro magnets to the shell of the rotor.

In order to facilitate the assembly of the several keystone-shaped electro magnets on the interior of the rotor as shown, the shell thereof is made of at least two pieces 23 and 24. In the form shown in FIGS. 3–5, the two pieces 23 and 24 are cup-shaped, and are respectively provided with outwardly extending flanges 25 and 26. Once the several solenoids have been positioned within the longer shell piece 23, the shorter shell piece 24 may be applied as a cap so that flanges 25 and 26 abut, and may be appropriately secured together as by riveting, bolting, welding, or cementing.

The shell pieces 23 and 24, as well as their interconnecting means, may be formed of material having little or no magnetic permeability, or in cases where it is desired to shield the exterior from the escape of magnetic flux, they may be formed of material having a high magnetic permeability. Instead of dividing the rotor shell in twain axially, it may be divided in twain radially, in which event the two halves will have axially extending joints when assembled, and may be held in such assembled position by banding or other appropriate means capable of sustaining the centrifugal force to which the rotor will be subject in use.

At the end of shell piece 23, remote from flange 25, there is provided a pair of slip rings 27 and 28 which, in the event the shell piece is formed of electrically conductive material, may be separated from the shell piece by sub-rings 29 and 30, of appropriate insulating material. The slip ring 27 is connected through a conductor 31 to the free end on the inner course of the solenoid winding for each of the electro magnets 11–22. The slip ring 28 is connected trough a conductor 32 to the free end of the outer course of winding in each of the solenoids 11–22. All 12 solenoids are connected so that the direction of electric current flow is the same in all solenoids. The energizing current is supplied from an external source through conductors 33 and 34 and brushes 35 and 36, in a manner well understood in the art.

The rotor is mounted upon an appropriate frame 37, having opposite stationary stub axles in the form of ferrules 38 and 39 which project toward each other. On the projecting portion of each of ferrules 38 and 39, there is provided an inner race 40 and 41 for each of two ball bearing sets whose outer races 42 and 43 are appropriately mounted to the respective ends of the rotor 10, so that the rotor 10 is free-running, with respect to the frame 37, about an axis concentric with the rotor 10.

In the embodiment shown, the exterior cylindrical surface of rotor 10 serves as a pulley for a drive belt 44 which connects the rotor to a source of power 45, but any other suitable means of driving the rotor in rotation may be utilized.

In the form shown in FIGS. 3–5, the apparatus is intended to concentrate the magnetic flux of the several solenoids radially inward, and to facilitate this each of the solenoids is provided with a core 46 of material having high magnetic permeability. As shown in FIG. 4, the several cores 46 are of squat U-shape, and extend, for the most part, parallel to the axis of the rotor, but at each end the cores are curved so as to provide faces 47 and 48 addressed radially inward. To minimize the radially outward escape of magnetic flux from the several solenoids, they are preferably wound of ribbon-like conductor which is coated with any appropriate electrical insulation. The first course of winding begins at 49, and proceeds in helically wound fashion with the minimum of space between adjacent turns about core 46, to the opposite end thereof, whereupon, without interrupting the continuity of the conductor, the second course is wound helically over the first course, with the pitch of the helix reversed from that in the first course. In this way, any gaps between successive turns in the first course are overlapped by turns in the second course. While the drawings show only two courses of conductor about each core 46, it will be understood that, in practice, there may be many more courses.

With the several solenoids connected through the slip rings to a source of direct current as above-described, it will be understood that all the solenoids 11–22 have the same polar orientation with respect to the axis of rotation of the rotor. For example, all core ends 47 are North poles, and all core ends 48 are South poles.

A tube 50 of circular cross-section is mounted in fixed relationship within the respective ferrules 38 and 39. The tube 50 is preferably made of material having little or no magnetic permeability. The tube 50 is stationary, but the rotor 10 rotates about the axis of the tube 50.

A stationary solenoid 51 is fixedly mounted on the exterior of tube 50 in a position such as to fit, with clearance, into the bight of the squat U-shaped solenoids 11–22. Solenoid 51 may be wound directly on tube 50, but in the form shown, it is wound on a cylindrical core 52 of material having little or no magnetic permeability, and the core 52 is telescoped on tube 50. The stationary solenoid 51 is energized through appropriate leads (not shown) from conductors 33 and 34 or other source of direct current, and is so connected that its magnetic polarity is opposite that of solenoids 11–22, that is to say that when, as aforesaid, the core ends 47 are North poles, the adjacent end of solenoid 51 will be its South pole. Thus, magnetic flux of solenoids 11–22 has an external path, through tube 50, which is coincident with, and in the same direction as, the internal path of magnetic flux in solenoid 51.

Thus, the magnetic field generated by each of the solenoids 11 through 22, as well as that generated by solenoid 51, penetrates the interior of tube 50, and when the rotor is driven in rotation, these magnetic fields rotate collectively about the axis of tube 50. During such rotation, particles of matter within the tube 50 are within the motional electric field generated by the rotating magnetic flux. Such an apparatus has a demonstrable effect in the separation and concentration of fluids. For example, in the de-salinization of water, the $B \times V$ electric field generated by the rotating magnetic fields, acts upon the disassociated ions of the sodium chloride in solution. This is explained by the fact that if the rotor 10 be rotated in the direction shown by the arrows in FIG. 5, the $B \times V$ field tends to drive the positively charged sodium cations toward the center, and tends to drive the negatively charged chlorine anions away from the center of tube 50. Hence, by introducing a flow of saline water at end 54 of tube 50, and by providing a concentric separating tube 55 at end 56 of tube 50, increments of fluid which are concentrated with sodium and depleted of chlorine may be drawn off through the stationary tube 55, while the increments of fluid which are concentrated with chlorine and depleted of sodium may be drawn off through the space between the exterior walls of tube 55 and the interior walls of tube 50.

Another utility of the apparatus shown is that of transmuting hydrogen into helium, in which event tube 55 is omitted and electrodes are provided at opposite ends 54 and 56 of tube 50, so that an electric arc may be established between them. Heretofore, difficulty has been encountered in maintaining the plasma of the arc in a relatively straight path between the electrodes as it ends to wiggle and extinguish itself when it makes contact with one of the confining walls. However, by impressing a $B \times V$ electric field upon such an arc, its path may be confined within controllable limits. The $B \times V$ electric field has the further effect of driving hydrogen protons toward the center of the tube, and driving electrons away from the center of the tube. Add one neutron to a hydrogen atom nucleus, and there is produced the isotope known as Dueterium; add one more neutron to the Dueterium nucleus, and it becomes Tritium; add one more proton to the Tritium nucleus, and it becomes Helium.

A third embodiment of the apparatus is shown in FIGS. 6, 7, and 8. With the significant exception that the embodiment of FIGS. 6, 7, and 8 has no moving mechanical parts, its organization is, in general, quite similar to that shown in FIGS. 4 and 5, and hence the last two digits of the reference characters utilized in the previous embodiment. As shown in FIG. 6, a cylindrical tube 150 has a solenoid 151 wound on the exterior thereof, and is energized with direct current from a suitable source through leads 153. A plurality of squat U-shaped solenoids 111, 112, and 113, of keystone-shaped cross-section, of which there are four each or any multiple of four, are wound as described in connection with the previous embodiment, and securely mounted in any suitable way with their pole faces 147 and 148 contiguous with, and addressed toward the axis of, tube 150. In this embodiment, however, the several squat U-shaped solenoids 111, 112, and 113, have cores which are made of material having little or not magnetic permeability, such as tubes 146 of paperboard wound to a keystone shape with hollow interior. As in the previous embodiment, the magnetic polarity of solenoid 151 is opposite that of the solenoids 111, 112, and 113, which is to say that if ends 147 of the solenoids 111–113 are the North poles thereof, the adjacent end of solenoid 151 is its South pole, so that the external magnetic flux path from solenoids 111–113 is coincident with, and in the same direction as, the internal flux path of solenoid 151.

In the embodiment shown in FIGS. 6–8, the several squat U-shaped solenoids 111, 112, and 113 are energized with non-interconnected three-phase alternating current, each phase of which has been half-wave rectified to produce direct current pulsating at alternate half cycles. One phase of the alternating current is connected to all solenoids 111; another phase of the alternating current is connected to all solenoids 112; and the third phase of the alternating current is connect to all solenoids 113, as shown in the wiring diagram of FIG. 8, where a three-phase alternator 100 is provided with six leads arranged in three pairs, to wit: leads 101 and 101' for the first phase, leads 102 and 102' for the second phase, and leads 103 and 103' for the third phase. The respective phases are not electrically interconnected. In each of leads 101, 102, and 103, there is a rectifier 104, 105, and 106, respectively. Leads 101 and

101' serve all four of solenoids 111; leads 102 and 102' serv all four of solenoids 112; and leads 103 and 103' serve all fou of solenoids 113. Across leads 101 and 101', between th rectifier 104 and the respective solenoids 111, there is provided a capacitor 107. Such capacitor is to coordinate th capacity and inductance of input, and to neutralize the effec of induction in solenoids 111 by adjacent solenoids during th off half-cycle of energization. Likewise, a capacitor 108 i connected between leads 102 and 102', and a capacitor 109 i connected between leads 103 and 103'. It will be apparent t those skilled in the art that since the four solenoids of like phase are arranged in quardrature with each other, and since solenoids 111 will reach their peak of magnetic flux 120° ahead of solenoids 112 reaching their peak flux, and the latte 120° ahead of solenoids 113 reaching their peak flux, a revolving magnetic field is created. Due to the rectification of the alternating current, and the consequent utilization of the half cycles which all flow in the same direction, there will be no reversal of the direction of magnetic flux generated by any of solenoids 111, 112, and 113, and hence, as in the case of the previous embodiment, the external path of all magnetic flux generated in the solenoids 111, 112, and 113 is coincident with, and in the same direction as, the internal flux generated by direct current energization of solenoid 151. When such an arrangement is supplied with alternating current at high frequency, such as a thousand cycles per second, the same results are achievable with this embodiment as with the previous embodiment but without movement of any mechanical parts.

For the purpose of illustrating the effect of the $B \times V$ electric field, and segregating that effect from the effect of stray magnetic or electrostatic forces, reference may be had to FIGS. 9 and 10. The device there shown is intended to be encased in an electrically grounded box 70 of material which has a high magnetic permeability, and which also has the property of electrical conductivity for shielding electrostatic fields.

Within the box 70, there is a compound rotor machine, wherein the respective rotors are driven in opposite directions. In a suitable frame having spaced pedestals 71 and 72, there is mounted a shaft 73 and an independent shaft 74. Both shafts 73 and 74 may be driven from a single source of power, and are preferably driven at the same rotational speed, but in opposite senses. A yoke 75 is fixedly mounted to shaft 73 for rotation with it. The yoke is cup-shaped with cylindrical skirt 76. About the inner periphery of the skirt 76, a plurality os solenoidal electro magnets 77 are fixedly mounted thereto. The several electro magnets extend parallel with the common axis of rotation of shafts 73 and 74, and are of the same polar orientation with respect to those shafts. The several electro magnets 77 have identical solenoids wound, in the manner previously described, about identical cores of material having high magnetic permeability. The solenoids of the several electro magnets 77 are energized from a suitable source of direct current through conductors 84 and 85, brushes 86 and 87, slip rings 88 and 89, and conductors 90 and 91. The respective solenoids 76 are preferably connected in parallel circuit relationship, but, if desired, may be in series so long as uniform polar orientation is maintained.

Shaft 74 is provided with a hub 78 having a coaxial bore 79, into which is rotatably fitted a pilot 80 projecting concentrically from shaft 73. On the outer periphery of hub 78, there is fixedly mounted a plurality of electro magnets 81, each of which is an identical solenoid, and each of which has an identical core of material having high magnetic permeability. As in the previous case, the several solenoids 81 are all energized so as to have the same polar orientation with respect to their axis of rotation. Each of the solenoids is energized from a suitable source of direct current through conductors 68 and 69, brushes 82 and 83, slip rings 95 and 96, and conductors 97 and 98. All of the solenoids 81 are preferably connected in series circuit relationship, but, if desired, may be in parallel.

If desired, and as shown, the several solenoids 81 may be surrounded by a simple solenoid 99 wound helically thereabout and electrically connected in parallel or series relationship with solenoids 81 and to conductors 97–98 so that the current flow through solenoid 99 is in the same direction as through solenoids 81. Thus the winding 99 serves the dual purpose of boosting the magnetic fields generated by solenoids 81 and of mechanically binding the latter to the surface of hub 78.

When, as contemplated, the shafts 73 and 74 are driven in rotation simultaneously, but in opposite directions, the solenoids 77 which rotate with shaft 73 have opposite magnetic polar orientation to those (81) which rotate with shaft 74. The several solenoids 77 are preferably designed to create external magnetic flux fields of flux density approximately equal and opposite to those created by electro magnets 81 and 99, but by the principle of superposition ("Elec. & Mag.", by Ralph W. Winch, 1963 Ed., p. 202), each flux field acts as if the other were not present. Despite the fact that the flux fields created by the *responsive* series of electro magnets 77 and 81 and 89 are oppositely directed, since their rotation is in opposite senses, their resultant effect, insofar as concerns the generation of a $B \times V$ electric field, is cumulative. Accordingly, the external $B \times V$ electric field is intensified at the exterior of the device, and its effect on the outside of shielding box 70 is demonstrable, even though the resultant magnetic flux density there is approximately zero. Such demonstration might be through a capacitor and electrometer as shown in FIG. 9, for example.

In order to achieve the maximum flux density and hence the maximum $B \times V$ electric field intensity, it is desirable to take measures which keep the apparatus cool. This may involve resort to such means as: winding the several solenoids with so-called "super-conductors" such as that known commercially as "Supercon"; or refrigerating the apparatus as by immersing it in a bath of liquid helium which is capable of maintaining a temperature of approximately 4° Absolute.

While several illustrative embodiments of the invention have been disclosed in detail, it is not to be understood that the invention is limited to those embodiments. On the contrary, the principles of the invention are susceptible of application in a vast variety of forms without departing from the spirit of the invention or the scope of the appended claims. The apparatus defined in the following claims is believed by the applicant to demonstrate his unique theory disclosed above.

What is claimed is:

1. Apparatus for generating an electric field, comprising:
a frame;
a cylindrical rotor;
a shaft journalled on the frame and supporting the rotor for rotation about is longitudinal axis;
a plurality of electro magnets, each of which is an identical solenoid having a core formed of a material having a high magnetic permeability, the electro magnets being fixedly mounted on the rotor with each electromagnet extending parallel to the axis of rotation thereof,
means to energize the solenoids of the electro magnets from a direct current source, the solenoids being energized so as to maintain a uniform polar orientation; and
an enclosure surrounding the frame and the rotor, the enclosure being formed of an electrically conductive material the enclosure being grounded.

2. Apparatus according to claim 1 wherein the rotor is a hollow cylindrical rotor, the electromagnets being affixed to the inner cylindrical surface of the rotor.

3. Apparatus according to claim 1 wherein the solenoids are connected in parallel circuit relationship.

4. Apparatus for demonstrating magnetic phenomena comprising:
a frame;
a cylindrical rotor;
a shaft journalled on the frame and supporting the rotor for rotation about its longitudinal axis;
a plurality of electro magnets, each of which is an identical solenoid having a core formed of a material having a high magnetic permeability, the electro magnets being fixedly mounted on the rotor with each electro magnet extending parallel to the axis of rotation thereof,
means to energize the solenoids of the electro magnets from a direct current source, the solenoids being energized so as to maintain a uniform polar orientation;
an enclosure surrounding the frame and the rotor, the enclosure being formed of an electrically conductive material, the enclosure being grounded; and
means surrounding at least a portion of the enclosure to detect and measure the electric field generated during rotation of the energized rotor.

5. Apparatus for demonstrating magnetic phenomena, comprising:
a U-shaped yoke of highly permeable magnetic material;
a pair of permanent magnets mounted in axial alignment between the ends of the yoke, one magnet being mounted to each leg of the yoke;
an electrically conductive non-magnetic rod extending axially through the magnets;
a stiff conductor mounted at one end to the rod for rotation relative to the yoke in a plane perpendicular to the rod and intermediate the magnets, the conductor extending a sufficient distance beyond the magnets so that its other end is located at a point where the magnetic field from the magnets falls to approximately zero intensity;
a galvanometer; and
circuit means connecting the ends of the conductor to the galvanometer to measure current flow through the conductor.

6. Apparatus according to claim 5 wherein the magnets are rotatably mounted to the yoke for rotation about the axis of the rod, and where the magnets are axially magnetized and adjacent faces are of opposite polarity.

* * * * *

APPENDIX III

A CONDITIONAL CRITERION FOR IDENTITY, LEADING TO A FOURTH LAW OF LOGIC

Summary

If logic is regarded as a set of perceptual operations, then logic has a chronotopology (time structure). Identity or nonidentity then results as a decision from an algorithm — a set of perceptual operations and comparisons — in which case the nature of a particular identity is conditional upon the nature of the set of perceptual operations comprising the algorithm.

Ordinary logic does not account for the temporal aspects of perception, merely accounting for the spatial aspects.

In other words, Aristotlean logic is a synthesis of primitive observation, fitted to the partial (spatial) reality emerging from spacetime after the imposition of the monocular (one-at-a-time) photon interaction with matter.

In quantum mechanics, time is a parameter, not an observable. Hence measurement/detection (of observables) deals with primitive observation and Aristotlean logic (topology).

Total reality includes nonprimitive observation — hence, non-Aristotlean logic (chronotopology) — as shown in Young's two-slit experiment.

By applying temporal accounting to each perceptual operation, Aristotle's three laws can be shown to be self-contradictory and incomplete as written. That is, they are topolological, not chronotopological.

A simple derivation of a fourth law is shown and an application rule given which itself may be regarded as a fifth law of logic.

A proof of the fourth law by demonstration is given.

The resulting four law logic is chronotopological. The applica-

tion rule states that either Aristotle's three laws apply explicitly and the fourth law is implicit, or the fourth law applies explicitly and Aristotle's three laws are implicit.

The four-law chronotopological logic is theoretically capable of resolving every present three-law paradox.

Aristotle's Laws and the Paradox of Change

Aristotle's three laws of logic, on which foundation rests all mathematical, physical, and rational thinking, can ordinarily be stated as shown in Table 1.

Table 1. Aristotle's three laws of logical thought

1. $A \equiv A$
2. $A \not\equiv \overline{A}$
3. $A \vee \overline{A}$

A variety of arguments can easily be produced to show that these laws are incomplete; i.e., they do not specify all reality, for parts of reality can be shown to contradict one or more of Aristotle's laws.

Indeed, all "observed" reality can be shown to violate all three-laws.

E.g., the most direct violation is posed by the problem of change, a problem originally propounded by Heraclitus about 500 B.C., and unsolved to this day. Heraclitus pointed out that, for a thing to change, it must turn into something else, and then asked how a thing could be something other than itself?

We may think of a thing — say, α — some feature A of which is said to change. If A changes, it turns into $\overline{A}$, thus violating logic laws one and two. Further, we are considering A as the "changed thing. $\overline{A}$," i.e., something which is somehow both A and $\overline{A}$, so logic law three is violated as well.

Thus, if Aristotle's laws are taken to be all the fundamental laws of logic, then logically there can be no change whatsoever, because change negates all three laws. I.e., either change does not exist or it is totally illogical.

Since all measurements, detections, thoughts, and perceptions are simply changes, then it follows that these operations logically cannot exist. Or, if we assume the "operations" to exist, their outputs cannot exist. If the operations do not exist, then again their outputs do not exist.

So if the products or outputs cannot exist, then by this reasoning no perceived, detected, measured, conceived thing exists. If we then insist that such things do indeed exist, then all is paradoxical and illogical. This is essentially the nature of the paradox posed by Heraclitus.

Heraclitus's change paradox has not been satisfactorily resolved to this day, and rigorously all the rational science of the Western world, being based on paradoxical change (detection, perception, observation) is itself totally illogical by its own logical standards.

Resolving the Paradox of Change

However, the conditions necessary to resolve the problem of change can be stated simply by inspection of the problem as follows: (1) Aristotle's three laws must specify or apply to only that which is not changing, since change violates or negates all three laws; (2) If change is to logically exist, there must exist at least a fourth law of logic, one which applies to change; (3) This fourth law must contain the negations of each of the first three laws, since change negates them; (4) To be consistent, in any particular logical case, either the three laws explicitly apply or the fourth law explicitly applies (i.e., either change explicitly exists in that particular case or it does not); (5) Since all four laws must apply at all times, then when the three laws apply explicitly, the fourth law must be implicit—and when the fourth law applies explicitly, the three laws must be implicit.

With the five stated conditions, a fourth axiom of logic can be written simply by writing down the negations of Aristotle's three laws, and synthesizing these negations into a single fourth law, as shown in Table 2.

Table 2. Negations to Aristotle's laws.

Aristotle's law	Negation	of negation*
$A \equiv A$	$A \not\equiv A$	$A \equiv \overline{A}$
$A \not\equiv \overline{A}$	$A \equiv \overline{A}$	$A \equiv \overline{A}$
$A \vee \overline{A}$	$A \wedge \overline{A}$	$A \equiv \overline{A}$ or $[A,\overline{A}]$

However, even though we can synthesize the negation into a single law — the old "identity of opposites" idea — we still have the problem of understanding such a law. Though at first glance the negations and the synthesized fourth law seem bewildering, we can readily comprehend them if we carefully consider the temporal nature of the process that occurs in logical thinking.

The Importance of Time

Specifically, a finite interval of time is required to perceive, think, detect, or observe an entity — regardless of whether we refer to "physical" or "mental" detection, because both physical and mental processes are temporal. Indeed, we flatly state without further discussion that ultimately the identifying or mapping of physical and mental operations onto each other is what time is a *priori.*

At any rate, we now carefully account for each individual time interval required to think, conceive, detect, perceive, or observe any entity — whether that entity is physical or mental — and we also account for the finite time interval required to perform a logical operation. So we rewrite Aristotle's three laws as shown in Table 3, with subscripted numbers indicating the separate time intervals in each law.

*These negations mean that A and $\overline{A}$ are totally undifferentiated.

Table 3. Temporally accounted laws and negations.

	Aristotle's law	Negation
1.	$A_1 \equiv_3 A_2$	$A_1 \equiv_3 \overline{A}_2$ or $A_1 \not\equiv_3 A_2$
2.	$A_1 \not\equiv_3 \overline{A}_2$	$A_1 \equiv_3 \overline{A}_2$
3.	$A_1 \vee_3 \overline{A}_2$	$A_1 \wedge_3 \overline{A}_2$ or $[A_1 ,\overline{A}_2]_3$

The resolution to the entire mystery so long inherent in these axioms of logic now stands simply revealed: Whether one of Aristotle's laws holds or its negation holds is determined solely by the nature of the logical operation in time interval three.[1]

I.e., the operation in interval three may be regarded as an *algorithm* comprised of subsidiary (assumed) operations in separate time subintervals that, taken together, comprise the overall operation implied by the logic symbol.

Thus in the first law, if temporal tags (time snapshots) are not accounted (i,e., if they do not apply), then Aristotle's laws hold, for the snapshot 1 of A is not differentiated in algorithm 3 from snapshot 2 of A. This then rigorously holds for spatial (L^3) entities, but not for spacetime entities. The snapshots in this case for Aristotle's first law (and the others as well) are *spatial* snapshots. On the other hand, if snapshots 1 and 2 of A are themselves temporally differentiated in algorithm 3, then the negation of Aristotle's law applies, because the *spacetime* snapshots A_1 and A_2 are different. This is immediately apparent, e.g., in a Minkowski geometry representation, where the second snapshot of A will have a time coordinate different from the time coordinate of snapshot 1. This is represented as shown in figure 1, where "A" is taken as a simple magnitude, in this case 5.



Figure 1. Spatial snapshots of spatiotemporal A differ.

As can be seen from figure 1, 5_1 is not identical to 5_2 *unless we imply the operator* $\partial/\partial t$ *in the time interval three algorithm.*

The negation of the second law may also be simply understood if we use temporal accounting. E.g., suppose we take $A_1 = +1$, $\overline{A}_2 = -1$ and then pose the absolute value operator || for potential use in algorithm 3. If || is not used, then

$$(+1)_1 \not\equiv_3 (-1)_2$$

and Aristotle's second law holds. If || is used, then

$$\left|\,(+1)_1\,\right|_3 \equiv_3 \left|\,(-1)_2\,\right|_3$$

and in that case

$$A_1 \equiv_3 \overline{A}_2$$

Note we are taking the view that there is nothing "absolute" or "inherent" about identity or non-identity; instead, each is a conditional result that can only be established by some logical, comparn tive set of operations. If the suboperations comprising the decision algorithm for the identity/non-identity determination are changed, the finding of the algorithm (the decision) may often change. Specifically, one can have the cases

$$\equiv_1 \not\equiv_3 \equiv_2$$

$$\not\equiv_1 \not\equiv_3 \not\equiv_2$$

Thus we advance a *conditional identity criterion* to be incorporated into formal logic: "Identity" or "non-identity" is defined by a decision made as a result of applying an operational algorithm; changing the internal operator components assumed inherent in the algorithm can change the decision. We are stating a fundamental principle that "identity" and "non-identity" are conditional and only conditional; they are never absolute.

Primitive Observation and "Reality"

With these points made, we now turn to the third law. From Table 2, on examination it can be seen that the third law actually is a statement for *monocular* perception, detection, observation, thought, or conception. Indeed, this law says that only a single thing at a time can be perceived, detected, observed, thought, or conceived.

As we pointed out in a previous paper[2] , there is a very good reason for this "law." Primitive man lived almost exclusively in a reality detected by light, by the photon interaction. Even in the absence of visible light, all bodies have temperature, and man is immersed in a "sea" of continual electromagnetic photon with interactions. The photon interaction is monocular - - only one at a time interacts with a particle of mass. Further, photon interaction constitutes the operator $\partial/\partial T$ invoked upon L^3T spacetime. Photon emission carries away time (the photon is made of $(\Delta E\ \Delta T)$, leaving behind an L^3 *spatial* reality, as we have previously pointed out.[3]

So all our primitive concepts, ideas, and notions about reality have come from over four million years of hominid and human experience in the photon-detected partial reality ("physical," "objective," or "spatial" reality) that remains when the time "dimension" (fundamental **variable)** is destroyed from L^3T spacetime, leaving only L^3 space behind. Specifically, our observed macroscopic reality consists of large temporal (mental) aggregates of such spatial results, where we cannot distinguish the tiny temporal separations of the pieces. Thus all our observed/perceived entities are spatial, and further, each perception/observation snapshot results in a frozen, unchanging spatial entity (resulting — in physical detection — from the so-called "collapse of the wave function." The loss of a wave function is simply the loss of time.) We vaguely sense "time" and "change" as the relation between these snapshots — i.e., by causality, or the ordering of the spatial changes — much as we see "movement" in movie frames rapidly projected onto a screen one-at-a-time.

Thus our primitive observations, from which have painfully been formed our relational concepts and ideas, are monocular, unchanging, and spatial. Aristotle's three laws of logic — which indeed may be taken to be only a simple synthesis of our primitive observation and corresponding relational concepts — then exhibit the same characteristics; they are monocular, unchanging, 3-dimensional, spatial, non-temporal relational statements. Any statement that is temporal, changing, or 4-dimensional will thus appear as a logical paradox to this logical shorthand.

But from Young's two-slit experiment, we already know that reality and relationships between its parts are quite different if the photon interaction is not invoked — i.e., if $\partial/\partial T$ is not invoked. Classical reality (as prescribed by Aristotle's laws) is directly violated by an electron in the two-slit experiment, e.g., if and only if photon interaction with the electron is not invoked. Again, this has been simply explained by the present author[4], and Charles Muses as early as 1957 pointed out the absence of any mystery in Young's experiment if the chronotopological aspects were considered.[5]

The Conscious Mind is Fitted to the Photon Interaction

However, what is normally referred to as the "conscious, thinking mind" is simply a functioning temporal (rigorously, chronotopological) mechanism that is painfully built up in the individual's awareness (his mind in the greater sense of both thought and awareness, whether monocular or multiocular) by training, conditioning and experience. Its functioning is largely conditioned by one's 90% or so attention to visual stimuli (to the partial reality remaining after photon interaction has been invoked, and to the memory-collated ordering of vast numbers of such photon interactions) and by one's cultural conditioning — which itself has been almost exclusively conditioned and shaped by the monocular photon interaction at base root.

Thus, since the beginning of man, his conscious, rational mind has been trained and constructed to function almost exclusively in basic correspondence with the photon interaction, and his experiential reality consists of the partial reality stripped from fundamental reality by photon interaction.

All "perceived differences," e.g., are created by this deep mindset. As has been previously pointed out,[6] the solitary human problem responsible for all man's inhumanity to his fellow man is directly dependent upon man's almost exclusive detection, observation, perception, and conception of "difference" between humans, these "differences" being due exclusively and totally to the fitting of men's conscious minds to the photon interaction's monocular separation of spatial reality from nonspatial reality, i.e., to

$$\partial/\partial T\,(L^3T) \Rightarrow L^3$$

Such well-nigh total devotion to, and enslavement by, photon interaction also is responsible for the scientist's well-nigh total devotion to, and enslavement by, the present imperfect and incomplete three laws of logic, as presented by Aristotle. The depth of that devotion and enslavement is evidenced by the fact that the resolution of such paradoxes as Heraclitus's problem of change have eluded the best minds of humanity for several thousands of years. Indeed, these paradoxes cannot be resolved by the conscious, rational mind in its present state, for it has been most firmly constructed and fitted to function in accordance with the photon interaction.[7] One cannot hope to resolve any logical paradox by using only those same logical methods that found the situation to be paradoxical in the first place!

Dimensionality

That we need not be constrained by such universal delusion is already shown by binocular vision. Specifically, in viewing a three-dimensional **object, each** eye **never** detects a "third dimension," but detects only **an L^2 2-dimensional** picture. By taking two slightly different 2-dimension snapshots and superposing them, the third dimension is gained. One then essentially sees the resultant superposed pictures as "almost the same but not quite." I.e., the Aristotlean identity algorithm, if satisfied, yields "no difference, hence one object," and if not satisfied, yields "difference, hence multiple (extended) object(s)." So if the two snapshots are almost Aristotlean-identical but not quite, we get an extended-two-dimensional (three-dimensional) object. Otherwise we see two separate, two-dimensional snapshots blurred together (the reader is urged to try this and see).

The point is, "dimensionality" and the identity algorithm are directly related, and geometrically one follows from the other.

Awareness of Time

In very similar manner, we can only gain cognizance of awareness of "time" (as a fourth dimension) by the superposing of two slightly differing (Aristotlean-wise) 3-dimensional snapshots. As is well known, e.g., time is not an "observable" in quantum mechanics; it is a "parameter." Rigorously, the only place such snapshots — each of which is "past" (spatially separated by the annihilation of time in the collapse of the wave function) — can multiply exist is in the "mind" in its most general sense. In a rigorous sense, mind and time can be taken as identical, and the "flow of time" can be taken as the "flow of mind connections or superpositions" of its spatial components. I.e., measured/detected/observed "physical phenomena" are a priori 3-dimensional and spatial, while a mind is four-dimensional and hyperspatial.[8] Spacetime exists mentally but not observably. Time is logically implicit, not explicit.

Temporal Aspects of Logic

Now we return to the temporal aspects of logic. Each perceptual part of each Aristotlean law is fitted to the photon interaction, hence monocular. The logic operation, inherent in the logic symbol in each statement, involves temporal superposition or comparison of spatial perceptual objects. Hence the logic operation is hyperdimensionally a function of mind and injects mind/time into the statement. Yet these laws, being fitted to or synthesizing photon interaction, attempt to prescribe the absence of time, even though writing down the logic operation rigorously invokes time. They are thus totally contradictory, since as written they implicitly violate themselves.

Table 4 summarizes the operations now to be permitted in the time-three algorithm, in developing a new four-law logic:

Table 4. Conditional identity rules.

1. $\left|\overline{S_1, S_2}\right|_3 = (\text{zero})_3 \Rightarrow (\text{identity})_3$

2. $\left|\overline{S_1, S_2}\right|_3 = (\text{nonzero})_3 \Rightarrow (\text{non-identity})_3$

3. $\left|\overline{S}\right|_3 = \left|\,\left|\overline{S}\right|_1, \left|\overline{S}\right|_2\,\right|_3 \Rightarrow$ monocular separation, differentiation internally

4. $\overset{S}{\left|\overline{}\right|}_3 = \overset{S}{\left|\overline{}\right|}_3 \Rightarrow$ nonseparation, no differentiation internally

Rules one and two simply state that, when snapshots 1 and 2 are superimposed (subtracted) in time interval 3, the resultant snapshot 3 may be zero or nonzero. If zero, snapshots 1 and 2 are said to be identical, and if snapshot 1 is to be labeled A, then snapshot 2 is to be labeled A. If snapshot 3 is nonzero, snapshots 1 and 2 are said to be nonidentical; if snapshot 1 is labeled A, then snapshot 2 is labeled $\overline{A}$.

Rule 3 says that snapshot 3 is a "memory" snapshot, and it may be particulately examined to monocularly separate snapshots 1 and 2.

Rule 4 states that snapshot 3 is not a "memory snapshot" and may not be further separated.

Note that in logic we repeatedly apply these rules in combination, serially or compositely. Note further that Rule 1 must serially apply both rules 3 and 4, as must rule 2 also.

If we take $4|_{3}$ to mean "rule 4 applied conditional to rule 3 also being applied," and $4|_{\overline{3}}$ to mean "rule 4 applied conditional to rule 3 not also being applied," we may write Table 5:

Table 5. Conditional identity, non-identity, and oneness.

$4|_{\overline{3}} \wedge 1 = \text{identity}\ (S_1, S_2)$

$4|_{\overline{3}} \wedge 2 = \text{non-identity}\ (S_1, S_2)$

$4|_{\overline{3}}$ = oneness without separate-ones; oneness, extraordinary and unperceivable; thing-in-itself

$4|_{3}$ = "ordinary" one, perceivable separation, "thing-as-separate-from-others"

As can be seen, this type of reasoning also sheds a great deal of light on the long-standing problem of the "thing-in-itself," but that is beyond the scope of this paper.

The Fourth Law of Logic

Now we write the fourth law of logic as follows:

$$4.\quad (A_1, \overline{A}_2)_3 \Rightarrow A_1 \equiv_3 \overline{A}_2$$

where all we have said is that, by rule 4, in snapshot 3 no memory process is allowed, and no separation/differentiation whatsoever of A_1 and $\overline{A}_2$ is permitted. Under these operational conditions for identity, what had previously been called A_1 in snapshot 1 and what had been called $\overline{A}_2$ in snapshot 2 are indistinguishable, hence identical.

Figure 2 shows this concretely, and may be taken as a proof of the fourth law by demonstration.



Figure 2. Proof that two opposites can be identified. What was separately perceived as A_1 in time snapshot 1 and what was separately perceived as $\bar{A}_2$ in time snapshot 2, cannot be distinguished in time snapshot 3.

Thus the age-old philosophical dilemma posed by the illogical identity of opposites has a simple resolution if one considers temporal aspects, and introduces temporal conditions for identity or non-identity decisions.

We now write the new four law conditional identity logic as shown in Table 6:

1. $A_1 \equiv_3 A_2$
2. $A \not\equiv_3 \bar{A}_2$
3. $A_1 \vee_3 \bar{A}_2$
4. $A_1 \equiv_3 \bar{A}_2$

Further, we point out that all four laws now apply. Laws 1,2, and 3 are the laws of explicit monocular perception, with implicit binocular perception. Law four is the law of explicit binocular perception, with implicit monocular perception. Both monocular and binocular perceptions must be and are used in each law. So in any situation, either the triad applies explicitly and the fourth law applies implicitly, or the fourth law applies explicitly and the triad applies implicitly.

Indeed, one can **even take the** view that we have prescribed a five-law logic, **the fifth law being taken** as shown in Table 7:

Table 7. A possible fifth law of logic.

$$5.\ [1,2,3,\ \wedge (4\,)] \vee [4\ \wedge (1,2,3,)]\ \text{where}\ () \Rightarrow \text{implicit}$$

In a previous paper[9], the author has already presented methods to apply this new logic to resolve present paradoxes. At least hypothetically, every present paradox should be simply a statement of the explicit fourth law, and it should be resolvable by explicit application of that law[10].

NOTES AND REFERENCES

1. Specifically, by whether or not exclusivity applies. I.e., we may read Law 1 as "In snapshot (time interval) 3, what was A in snapshot 1 is exclusively identical to (unseparated from) what was A in snapshot 2." Law 2 may be read as "In snapshot 3, what was A in snapshot 1 is exclusively not identical to (is exclusively separated from) what was not-A in snapshot 2." Law 3 reads, "In snapshot 3, what was A in snapshot 1 and what was not-A in snapshot two are exclusively separated." Thus it can be seen that the three laws simply are statements involving whether or not two former perceptions are to be separated in a third perception. These three statements presently prescribe the total separation of the two previous perceptions and prohibit any admixture of the two — the so-called "excluded middle." Thus the three laws prescribe monocular, one-at-a-time perception.

   What we call a "wave" exists in time and is considered to contain an admixture of timeless, static spatial states (such as "wavelengths.") The prohibiting of admixtures thus represents the "collapse of the wave function" and corresponding loss of time. This defines "observation" and explains why all "measurement" and "detection" and "observation" — requiring a collapse of said wave function — are spatial and not spatiotemporal. That is why time is a parameter in quantum mechanics, not an observable.

   Relativity, being constrained by such logic, obviously can find nothing "physical" (observed, spatial, timeless thing frozen by the collapse of the wave function as engendered by or fitted to the photon interaction) that is traveling faster than light — i.e., that violates the conditions implied by the "observing/detecting agent."

That reality need not at all be so constrained is clearly shown by Young's two-slit experiment, the heart of all quantum mechanics. In this experiment, "classical' reality is violated if and only if the photon interaction is not invoked. Classical reality is obeyed if the photon interaction is invoked.
With appropriate change to logic to fit "reality that has not been interacted with by photons" and therefore is spatiotemporal, a new physics becomes possible.

2. Thomas E. Bearden, "Solution of the Fundamental Problem of Quantum Mechanics," January 3,1977, Defense Documentation Center.

3. Bearden, "Photon Quenching of the Paranormal (Time) Channel: A Brief Note," 20 April 1977, Defense Documentation Center.

4. Bearden, "Virtual State Engineering and Its Implications," 1979, Defense Documentation Center.

5. With the possible exception of Kozyrev — whose more technical works on time remain undisclosed to open science — no other person known to this author seems to have grasped the implications of a dynamic structure of time as penetratingly as has Charles Muses. The importance of the time interaction explaining the two-slit experiment (i.e., in explaining wave-particle duality) was noted as early as 1957 by Muses. See, e.g., Muses' introduction to Jerome Rothstein's **Communication, Organization, and Science,** The Falcon's Wing Press, Indian Hills, Colorado, 1958, p. lxii, where Muses pointed out that the celebrated wave-particle paradox remains a paradox only so long as the chronotopological (his word) phases of the phenomena are left unrealized in the analysis. The entire foreword by Muses is a remarkable document which analyzes the structure of time itself. With his hypernumbers Muses can describe the nested structure of time, which is what is actually

being carried by the photon. Further, he can theoretically predict mechanisms by means of which these structures can be orthorotated. It would appear that practical devices should be constructable on the principles elucidated by Muses, and it is little short of astonishing that fundamental work of such importance and application has been thus far little used by theorists, though it is already recognized in the standard literature; e.g., the profound summary paper "Hypernumbers II" in the January 1978 issue of the journal **Applied Mathematics and Computation,** published by Elsevier.

6. Bearden, "The One Human Problem Its Solution, and Its Relation to UFO Phenomena," Defense Documentation Center, January 3, 1977.

7. Which is why a Zen master often gives the student a koan to confound and overwhelm this automatic, robotic mindset and functioning that has been constructed as the student's "conscious mind."

8. Specifically, consciousness/life involves a seven dimensional body/being in an infinite-dimensional universe. See Thomas E. Bearden, "A Mind/Brain/Matter Model Consistent with Quantum Physics and UFO Phenomena," prepared for the 1979 MUFON Annual Symposium, available in the **Proceedings,** MUFON, 103 Oldtown Road, Sequin, Texas 78155.

9. Bearden, "The Fourth Law of Logic," **Specula,** Journal of the American Association of Meta-Science, P.O. Box 1182, Huntsville, Alabama 35807, Vol. 2, No.l, January-March 1979, pp. 30-40; also in publication in Defense Documentation Center. (The journal **Specula** is no longer pulished).

10. No consideration of the foundations of logic and mathematics is complete until one has read Morris Kline, **Mathematics: The Loss of Certainty,** Oxford University Press, New York, 1980.

APPENDIX IV

LIST OF SELECTED INCIDENTS

Author's note: In 1985-1987 a series of anomalous missile and space failures swept the U.S. and the West. These incidents were not unique, as many think, but were actually only a portion of thousands of related incidents showing the Soviet testing of advanced weapons throughout the world. This listing will show the types of incidents referred to.

The listing is not intended to be complete at all, but only representative. Hundreds of incidents of weather engineering, giant cloud radials and grids, suspicious light incidents, etc. could easily be added, were there time and room. No attempt has been made to exhaustively map the "aerial booms" that have blanketed the U.S., Europe, and other parts of the world. The light and "maybe it's UFO's" reports alone would add thousands of incidents to the list.

Our message is succinct: The Soviet Union has developed a new science and weaponized it, since at least the latter 1940's. It has utilized that science — energetics — to develop superweapons and supervehicles. Because of the danger from accidental initiation of nuclear weapons and materials, it is exceedingly difficult and dangerous for the Soviets to make extensive use of these weapons. Accordingly, a biological warfare strike — AIDS — has been utilized to deliver what is to be the knockout blow to the West.

DATE, INCIDENT, LOCATION, REMARKS

Early spring 1966 - Malstrom AFB Montana.
UFO sighting coincident with simultaneous problems in 10 strategic missiles in launch site associated with Malstrom AFB, Montana. *Similar event in Mar 1967 also. (Source: **Clear Intent.**).*

20 **Mar** 67 - Malstrom AFB Montana.
Flight of 10 strategic missiles in launch site associated with Malstrom AFB, Montana experienced problems with guidance and control system. UFO in area and confirmed on radar. Jet fighters scrambled, results unknown. *Similar event one year earlier.* (Source: **Clear Intent.).**

1972 - Prague.
At a secret meeting of European communist leaders in Prague, Brezhnev lays out firm statement of Soviet intent to be able to dominate the world by 1985. Stated would control the oceans, 90% of the land, and the air and space above. *Notice he said control, not invade and conquer.*

Aug 73 - Over ocean.
USAF Minuteman ICBM is launched from Vandenberg AFB, aimed for Kwajalein missile range. Unidentified object appears and is tracked next to the ICBM's nose cone. Crossed the RVs trajectory. Object about 10 ft long. Seen by 2 separate radars. Three other identical objects were seen in the vicinity. *Probable Soviet advanced flying vehicles. Also a deliberate stimulus to see if U.S. knows of the technology, and how the U.S. reacts. (Source:* ***Clear Intent.).***

18 **Oct 73 -** Near Mansfield, Ohio.
U.S. Army helicopter is intercepted by glowing red object that converged on it with terrific speed. Object placed some sort of "tractor beam" on helicopter. Object was gray metallic structure, 50-60 ft long. Helicopter was stopped in mid air. Radio blacked out. Official report filed by pilot. *Probable advanced Soviet flying vehicle. Also a deliberate stimulus to see if U.S. knows of the technology, and how the U.S. reacts.*

21 Oct 73 - Near St. Joe, Indiana.
20 or 30 lights sighted circling in the sky near St. Joe, Indiana near a woods fire, by firemen. *Probable Soviet holographic tests to stimulate UFO reports.*

1973 to date - Bennett Island.
Bennett Is. exhaust plumes detected by U.S. weather satellites. *Well over 100. spotted so far. Weirdly, 5 islands and part of the continental Alaskan area are in process of being secretly given to the USSR; Bennett Island is one of them.*

May 1974 - Lake Michigan.
Blue-green glowing ball of light seen to fall into Lake Michigan. *Soviet scalar EM testing.*

8 July 74 - Lake Okeechobee, Florida and Atlantic Ocean.
Orange red ball of light lights up sky over south Florida. Crashes in area of Lake Okeechobee. Was accompanied by a large boom. Several other booms 5-7 min. after "object crashed." Pilots also saw object plummeting in from over Atlantic. *Probable Soviet scalar EM weapons testing and calibration.*

Nov. 74 - Saryshagan. USSR.
Construction of Tora facility begins at Soviets' Saryshagan test facility. Believed to be directed energy facility. *Probably connected with Soviet scalar EM weapons systems development.*

Oct? 74 - Antarctic.
Ozone hole over Antarctic first detected. Did not appear in measurements from 1957-1973. Note did not appear until exhaust plumes noted from and around Bennett Island, with substantial activity. *Looms over the continent every Oct. Diminishes through Mar. More severe each year since 1974.*

1975 - USSR.
Soviet article in **International Life** speaks of weather war, changing the nature of lightning, increasing the power of lightning, and directing electric charges of tremendous power against specified targets. "Atmospheric electricity" can be used to suppress mental activity of large groups of people. *Tip of the iceberg. Unclassified reference to Soviet's scalar EM (energetics) weapon program. Note involvement of "lightning" in destruction of U.S. missiles a decade later.*

16 **Feb 75 -** Caribbean.
R.M.S. Carmania (UK) observes bright white circular light appear and rise to 20 degrees, leaving comet-like trail, circle and disappear. Repeated four more times at exact hourly intervals. *Soviet scalar EM weapons tests. May have been a shipborne device.*

13 June 75 - Kremlin.
Brezhnev calls for ban on frightful weapons of mass destruction. *Major speech. Repeated proposals to U.S. Senators.*

2 **Jul 75** - Kremlin.
Brezhnev repeats his proposed ban on development of frightful new weapons, to a group of U.S. Senators. *To visiting U.S. Senators. No one knew what he was talking about.*

Aug. 1975 - Kremlin.
Ponomarev calls for ban on frightful new weapons of mass destruction. *To visiting Congressmen.*

23 Sep 1975 - United Nations.
Gromyko presents draft agreement to UN General assembly, for banning development of frightful new weapons. *30th session of UN Gen. Assy. No one knew what the Soviets meant.*

Oct - **Dec 75** - Satellite, over the Indian Ocean.
U.S. satellites illuminated or "blinded" over the Indian ocean. *Source 10-1,000 times as strong as natural sources. 5 incidents. One 4 hrs. long. Soviets wasted no time after Sep. fiasco.*

28 **Oct** to **11** Nov **75** - Mid-U.S. and Canada.
Series of "UFO's" seen at Malstrom AFB, Montana; Loring AFB, Maine; Minot AFB, North Dakota; Wurtsmith AFB, Michigan and Canadian Forces Station, Falconbridge, Ontario, Canada by reliable military personnel. Reported to NORAD. Some objects seemed like helicopters. Radar tracked objects. One object at 72,000 ft. was 100-ft sphere, with seeming "craters" around it.

Malstrom F-106's scrambled on one object but could not close on it in darkness and low altitude. Efforts by Air Guard helicopters, SAC helicopters and NORAD F-106's were fruitless. Probable Soviet activity in and around the SAC bases and Canadian radar site. (Source: **Clear Intent.).**

30 Oct 75 - Wurtsmith AFB, Michigan.
UFO's and "unidentified helicopters" sighted (multiple incidents) at or near Wurtsmith Air Force Base, Michigan. Helicopter hovered over the weapons storage area. Radar reported low-flying objects. Returning KC-135 tanker a/c diverted to intercept one UFO. Observed two objects, unable to close. Visual and radar contacts. Low on fuel, KC-135 returned to base to land, again seeing lights over the weapons storage area. (Source: **Clear Intent.)** *Soviet Activity.*

7 **Nov** 75 - Near Lewiston, Montana.
Giant glowing disc, football field sized, hovered over Minuteman missile launch site K-7, just south of Lewiston, Montana. When it rose to 1,000 ft., NORAD radar picked it up. Two F-106's were scrambled. UFO rose to 200,000 ft. and disappeared from NORAD radars. *Probable advanced Soviet flying vehicle, using antigravity propulsion system.* (Source: **Clear Intent.).**

Nov 75 - Semipalatinsk, USSR.
Large amounts of gaseous hydrogen with traces of tritium begin to be detected by USAF/TRW early warning satellites.
Nuclear debris apparently related to nuclear facility at Semipalatinsk labelled PNUTS (possible nuclear underground test site.) Probable large scalar EM development and test site.

Jan 76 - Cannon AFB, New Mexico.
Two UFO's reported near flight line at Cannon AFB, New Mexico. 25 yards in dia., gold or silver in color with blue light on top, hole in the middle and red light on bottom. Observed and reported by security police. (Source: **Clear Intent.).** *Probable Soviet activity.*

31 **Jan 76** - Eglin AFB, Florida.
MG Lane, CG, Armament and Development Test Center, Eglin AFB, Florida reported a UFO sighting near an Air Force Radar site from 0430 to 0600 Eastern Standard Time. Photographs were taken. Later press release called it "building lights." (Source: **Clear Intent.)** *Probable Soviet Scalar EM activity.*

1976 - U.S. Embassy, Moscow.
State Dept. declares U.S. Embassy in Moscow an unhealthful post. Installs Aluminum window screens against Soviet microwave radiation, which has been underway since 1950's.
Provided 20% pay extra differential. Embassy radiated with weak microwave radiation since 1950's. Two U.S. Ambassadors died, Stoessel ill with strange leukemia-like malady. Soviet stimulus to see if we knew about scalar electromagnetics, phase conjugate waves, and EM disease induction. (Stoessel died recently of cancer).

1976-U.S.
Soviet nuclear scientist named Rudakov visits U.S., proposes cooperative effort in some a**reas of** fusion research. Showed work he **had**

been doing and results obtained. U.S. officials reacted drastically, classified his talk as top secret, even ripped off blackboard and carried it away.*Very strange incident. Soviet open, public scientific work considered Top Secret by the U.S. One wonders why.*

30 **Mar** 76 - Netherlands.
Huge atmospheric boom occurs over northern part of Netherlands. *Through 1983, in 10 years 7 events took place.*

22 Jun 1976 - North Atlantic.
Expanding white sphere of light developed for about 10 min. then faded. Other associated light phenomena observed. *Seen and logged by passing ship.*

4 **Jul** 76 - Soviet Union.
Giant Soviet Woodpecker transmitters activated. *3-30 MHz band. Worldwide interference with communications.*

30 **Jul** 76 - Fort Ritchie, Maryland.
Several UFO's sighted in and around Ft. Ritchie, Maryland. One hovered over the ammunition storage area. Reported. *Temperature inversion at the time provided a convenient pseudoexplanation. Could not have caused the incidents.* (Source: **Clear Intent.)**

10 **Sep** 76 - Lithuania.
European Airways flight 831, Moscow to London, at 31,000 ft over Lithuania sees blinding single ball source of light at constant altitude about 5-6,000 ft. below them and above a lower cloud.
Pilot contacted Soviet authorities. Received negative response and suggestions he should not ask questions. Probable deliberate stimulus of flight so, from reports to British authorities, could ascertain whether Britain knew anything about scalar EM weaponry.

19 Sep 76 - Near Teheran, Iran.
In early morning hours, UFOs were spotted north of Teheran, Iran. Two F-4's attempted to intercept. The first lost all communications and instrumentation at 25 miles distance. When the F-4 turned away, equipment was restored to functioning. Second F-4 acquired radar lock at 27 nm. and attempted to close. Object moved to stay at 25 nm distance. Second object came out of it, headed straight for the F-4. F-4 attempted to fire AIM-9 missile and at that instant weapons

control panel and communications went off. F-4 took evasive action. A third object was seen to emerge from first. The F-4 returned to base. Each time it passed through 150 degrees magnetic bearing, it lost communications and INS fluttered 30 to 50 degrees. A civilian airliner also experienced loss of communications in the vicinity. *Signatures of scalar electromagnetic weapons and antigravity.*

1976 - Soviet Union, Sweden.
Swedish national authorities detect anomalous radionuclides — similar to those from nuclear explosions — over Sweden. No accompanying seismic activity. Correlated with known Soviet activity at Semipalatinsk. *In other words, nuclear explosions were occurring, but they did not shake the earth. Total anomaly. Indicates transformation of the explosive energy. Positive signature.*

1976 - Philadelphia.
Legionnaires Disease precipitously strikes Legionnaires attending convention in downtown Philadelphia. Kills 34, makes 187 others seriously ill. Similar malady struck Odd Fellows convention at same hotel in 1974. *Odd person with apparent transmitter and antenna was expelled. Informed members: "It's too late! You are all dead!" Probable scalar EM conditioning of convention with an immune suppression pattern for the disease.*

21 **Jan 77 -** Columbia.
Columbia A/L Avianca night flight. Instruments went haywire. Saw enormous, zigzagging glowing light, traveled at fantastic speed back and forth. Blinked landing lights, UFO responded. Sped away at incredible speed. *Probable Soviet advanced performance antigravity flying vehicle. Such have been widely sighted over South America.*

3 **Mar 77 -** Columbia.
Columbia A/L Avianca night flight. Pilot abruptly changed course to circle a huge, glowing UFO. Object had cigar-shaped fuselage and was twice as big as the aircraft. Blinked lights, UFO responded. Sped away. Air traffic control radar tracked object at ten times the speed of normal aircraft.
Probable Soviet advanced performance antigravity flying vehicle. Such have been widely sighted in South America.

24 **Mar 77** - Off coast of Spanish Sahara, Africa.
M.V. Kinpurnie Castle, off coast of Spanish Sahara, Africa, observes complex, dynamic light phenomena. Third phenomenon was the formation of a semi-circular area of moderate luminosity, a hemisphere of light. Took 3 min to form about a previous luminous patch. Then another luminous patch formed over the hemisphere. After about 7 min., phenomena dispersed. *Soviet test of Tesla shield and globes.*

11 Jun 77 - Moscow, USSR.
Soviet biophysicist hands Robert Toth, Los Angeles Times journalist, a report containing proof that certain particles existed in cells, carried information, and were radiated. Both seized by KGB and charged with possessing Soviet state secrets. Interrogated, released. *Neither knew what they actually had. Soviet Academician I.M. Mikhailov pronounced secret such phrases as "micro-organism self-radiation... by means of vacuum particles in space." Use of such particles was discussed, and was secret. Paper contained basis of Soviet energetics use in biology. Positive connection of Soviet classification to mitogenetic radiation and scalar EM waves ("vacuum particles" indicate virtual flux structuring).*

13 July 77 - New York.
Massive electrical blackout strikes New York City. Affects 8 million persons. Staggering series of "natural" electrical shocks, mechanical failures, and human errors occurred. Anomalous "lightning strokes" supposedly initiated the collapse of the power grid. *Probable Soviet test.*

1977 - Ocean off Yugoslavia.
M.V. Dolphin, between Yugoslavia and Israel, observed extensive light balls and repeated phenomena, appearing and disappearing. Men were disoriented. Compass was disrupted. Okay after the phenomena dispersed. *Probable Soviet test. Stimulus to see if Britain recognized the weaponry and knew anything about it.*

13-14 Dec 1977 - Leitchville, Australia.
Large aerial light plus 3 smaller ones observed for four hours by multiple persons. Lights simulated activity of a "mother ship" and smaller craft assigned. Changed colors. Then a shower of orange

lights occurred. *Probable Soviet test. Part of deception plan, to create "UFO" phenomena to hide weapons testing. TR wave holography.*

Dec 77 to **Jan 78 -** Off East U.S. Coast.
Mysterious atmospheric explosions occur off U.S. Atlantic Coast. *Some accompanied by light phenomena. Soviet tests and calibration (registering the long-range artillery, so to speak.)*

13-14 Dec 77 - Leitchville, Australia.
Large arrays of light phenomena sighted by multiple witnesses. *Probable Soviet creation. Reported as "UFO" phenomena. Holographic creation of "UFO" phenomena as part of deception plan to disguise tests of the weapons worldwide. TR wave holography.*

1977-78 - North Pacific Ocean.
Two huge hot spots in North Pacific ocean, 2,000 mi by 1,200 mi. *May have caused El Nino and one of most severe winters on record. May have been caused by Soviets as a weather experiment.*

27 **Jan 78 -** U.S. East Coast.
Boeing 727 off east U.S. coast experiences engines failing, 1 at a time, in all three engines. A/c plunges 8,000 feet; engines restart one at a time. *First time ever that all three engines on a 727 had failed. Probable Soviet test.*

Feb 78 - Rocky Mtns. NW of Las Vegas.
Four aircraft crash in a 6-day period in the rugged Rockies, NW of Las Vegas. *Connected with a crashed military a/c from Nellis AF Base. Should be further investigated.*

Feb 78 - Texas coast. Nova Scotia. Charleston, SC.
Atmospheric booms occur. *Multiple booms in Charleston. Soviet tests. Scalar EM weapons.*

2 **Apr 78 -** Bell Island, Nova Scotia.
Mysterious fireball, explosion accompanied by anomalous electrical effects. *Small bldgs blown apart, trees scorched, fireballs seen. Probable Soviet test. Apparently even registered on U.S. satellite.*

10 **May** 78 -Off Florida.
Women pilots in race experience anomalous "time loss" on their watches from Fort Myers to Freeport (Bahamas). *39pilots. Watches synchronized. Up to 3 min. lost. Definitely not normal EM effect. Probably due to sporadic natural scalar interferometry and time-reversed waves generated in area from time to time. "Bermuda Triangle" mechanism?*

May 78 - Florida.
Unexplained lighted objects sighted in sky over remote sector of Florida. Tracked on radar at a Navy EW center. Naval personnel also observed them through binoculars. *Probable Soviet advanced flying vehicles, or tests of intense holograms with energy sufficient to ionize air and reflect radar.*

18 **May** 78 - England.
Several atmospheric explosions shake houses over a wide area in Hull, Scunthorpe, Holderness coast, and Brough and Grimsby. *Probable Soviet weapon testing and calibration.*

Jun 78 - Indiana.
Large ball of light streaks across sky, stops, hovers, then explodes with a large boom. *Possible test. Standard Soviet incident to generate deception.*

7 **Sep** 78 - Netherlands.
Large acoustical event (boom) occurs over the Netherlands. *Soviet scalar EM weapons testing and calibration.*

Sep 78 - Tabas, Iran.
Anomalous Richter 7.4 earthquake strikes Tabas, Iran, killing 25,000. No aftershocks. Anomalous depth. Soviets needed to relievo pressure in rocks at nearby Askhabad on the Soviet/Iran border, else lose the city to a large earthquake. *36 hrs. earlier, Soviets exploded monstrous 10 Megaton underground nuclear explosion, to disguise what caused the earthquake. Almost definitely a Soviet- induced earthquake.*

Oct. 78 - USSR.
U.S. DOD weather satellite purportedly photographs a semi-rectangular object climbing out of atmosphere at 4,000 to 4,500 **mph.**

Object was over the Soviet Union. *Probable Soviet advanced flying vehicle, using antigravity propulsion system, if photograph is real.*

31 **Oct** 78 - Fairbanks, Alaska & Lake Ontario.
Red and yellow flash seen descending through sky S. of Fairbanks, Alaska by multiple observers. One minute later, U. of Alaska seismograph registered a tremor 1.5-2.0 on Richter scale. Ten days prior, a similar phenomenon was observed over Lake Ontario and a photo taken of the light. *Probable Soviet scalar EM wpns testing calibration.*

Nov 78 - Kuwait.
Large flying vehicle lands at Umm. Alaish oil pumping sta., Kuwait. Disrupts elect, comm, and pumping activities. Leaves after 7 min. *Probable antigravity propulsion system. Soviet vehicle. One of a series of "UFO" sightings in oil fields of Kuwait. Positive scalar electromagnetics and time-reversed wave signatures.*

Nov - Dec 1978 - Kuwait.
Series of "UFO" incidents over Kuwaiti oil fields occur. Kuwait Gov't. investigates, makes official report. *U.S. Pentagon noted incidents. Probable Soviet-induced incidents.*

1979 - British Columbia & Caspian Sea.
Ariel 6 satellite experiences anomalous turnoff of two power supplies. *Over British Columbia and Caspian Sea, when sun is shining. Probable Soviet stimulus.*

Jun 79 - Vienna.
Pres. Carter signs SALT II agreement in Vienna. After that, his acts and speech are erratic and he seems to be in a depressed state. *Suggestive of exposure to EM behavior modification. Soviets had possessed the LIDA technology for 29 years.*

Sep 1979 - USSR.
Strange giant semicircular light phenomena observed in USSR, toward Saryshagan. Observed several times. Source: London **Times.** *Observed from Afghanistan by British cameraman Nick Downie. Definitely Soviet tests of a Tesla globe and/or shield.*

22 Sep 79 - South Atlantic.
U.S. Vela satellites detect anomalous flash over South Atlantic, as if from a nuclear event. *U.S. Govt Agencies still disagree as to whether this was a nuclear event or not. May have been a Soviet test, or a test of a scalar EM weapon by another nonhostile country.*

25 Dec 79 - Afghanistan.
Soviets invade Afghanistan. *This is the Soviet "Spanish Civil War," where wpns, training, and the state of their ready reserves are tested. It is not primarily the regulars who are fighting there. Some scalar weapons — e.g. Smirch death ray — are tested also.*

1980 - Afghanistan.
Soviets kill 225 women and children in a village in the province of Maiden, near Kabul, Afghanistan. A month and a half later, bodies still undecayed. Bodies were also shot, to try to deceive Mujaheddin as to cause of death. *Bodies perfectly preserved. No smell, no bugs, no scavengers had eaten them. Probable Soviet test of a "death ray." Definitely scalar electromagnetic weapon signature.*

Feb 1980 - Duncanville, Texas.
About 100 startlings suddenly start falling from flight, instantly dead. *One of several such anomalous bird falls. Connected with very high frequency components added to Woodpecker signals for sharp localization. Birds entering such an area are killed.*

May 1980 - Seminole, Florida.
Start of mysterious plague of assorted illnesses striking healthy persons in a 20-block section of Seminole, Florida. Animals affected also. Lack friendly bacteria in their intestines. *Signatures of EM induction of disease and kill of intestinal bacteria. The lack of friendly bacteria is important. May indicate one direction of biological warfare planned by Soviets.*

June 1980 - USSR.
Huge, luminous hemisphere of light seen within Soviet Union, from Kuwait. Probably over Caucasus region of USSR. Source: personal communication from observer. *Tesla shield. A definite test, un equivocal.*

July 1980 - U.S. and Canada.
Richter 5.1 quake centered in northern Kentucky rumbles through 14 states and into Canada. *No known fault. Was predicted two wks in advanced by an associate.*

7 **Nov 80** - Applegate Valley, Oregon.
Mysterious explosion, earth rumbling, brilliant light turns night into day in Southern Oregon. *Associated with subsequent earthquake next day?*

8 **Nov 80** - California.
Richter 7.5 earthquake off coast of Southern California. Shakes CA and Southern Oregon. *Note anomalous phenomena in S. Oregon the preceding day.*

Dec 1980 - South Atlantic.
U.S. Vela satellites detect another anomalous nuclear-like flash over the South Atlantic. *In infrared only. Obviously not a normal nuclear wpn.*

28 **Dec 80** - South Atlantic.
Great bluish-white flash over the South Atlantic. Clear sky except 2 or 3 small cumulus clouds, one about 600 ft. above ship. *Possibly connected with the second Vela flash detection, or generated by the same system. One of many such incidents.*

1 **Jan 81** - Somerset, Pennsylvania.
Pilots of two a/c report the descent of a bright, shiny object with fiery tail over Pennsylvania. Large boom rumbles across most of Western PA. *Possible Soviet scalar EM testing. Part of deception plan.*

Jan 81 - Minnesoto, Wisconsin, South Dakota.
Great skyflashes and rumbling noises occur around Morris, Minnesoto and Wisconsin and South Dakota. *Possible Soviet scalar EM testing. Part of deception plan.*

Feb 81 - San Jose California.
Two pilots menaced by 10 ft. dia. light which flew directly at aircraft over San Jose, CA airport. Plane climbed, light followed, then sped away. *Totally consistent with exercise of the Soviet Launch Phase*

Anti-bomber system's real-time holography aspects of the Woodpecker OTH radars.

6 **May** 81 - Fredericksburg, Maryland.
EC-135 a/c crashed near Fredericksburg, MD. Severe nose-down from 29,000 ft. Apparent loss of all power. At 5,000 ft., either fire or minor explosion occurred. At 1,500 large explosion destroyed the aircraft. *Possible Soviet test of OTH radar anti-bomber weapon system?*

Mid-81 - Afghanistan.
Soviet helicopters use mysterious, highly lethal agent in Afghanistan. Causes death so quickly victims do not have time to make the slightest move. Rpt by Jane's Defense weekly. Referred to as Smirch gas or Smert gas. *Probable test of a Soviet scalar EM "death ray."*

20-23 Jan., 1982 - Gander, Newfoundland.
"Object with red, green and yellow lights sighted in the Gander, Newfoundland area more than 36 times. Alternately hovered and darted in a complex "flight" pattern. *Possible real-time holographic phenomena produced by Soviet scalar EM weapons as part of the worldwide deception plan. Gander is a major "registration point."*

3 **Feb** 82 - Newfoundland.
Red and green flashing lights travelling across the horizon at 2,000 mph reported by 3 Armed Forces officers at Gander, Newfoundland. *Possible real-time holographic phenomena produced by Soviet scalar EM weapons as part of the worldwide deception plan. Possible major "registration point."*

Feb 82 - Ankasaray, Turkey.
Cluster of high, multiple lights pass over Turkish town of Ankasaray, 200 km. from Ankara. Dogs were disturbed also. *Possible real time holographic phenomena produced by Soviet scalar EM weapons as part of the worldwide deception of plan. Gander is a major "registration point."*

Sep 82 - Ankara, Turkey.
Cluster of 10-14 high, multiple lights pass over Ankara, Turkey in clear night sky. Dogs were also disturbed. *Possible real-time holographic phenomena produced by Soviet scalar EM weapons as part of the worldwide deception plan.*

Early 82 - St. Petersburg, Florida.
Extended series of booms occur off coast of Florida, near St. Petersburg. *Continued lengthy period of time. Years of Soviet scalar EM interference grid adjustments have been registered in Florida and off St. Petersburg. Booms are so numerous that meetings of civil defense, federal, and state officials have been held.*

June 82 - Washington/Canada border and off-shore.
Extended series of booms occur over Pacific Ocean, centered about Port Angeles and Sequim near Washington state/Canadian border. *Persisted for several weeks. As many as 10 blasts per day. Fireballs and lights also seen. Soviet extended scalar EM tests.*

18 June 82 - Northern Pacific Ocean.
Two JAL flight crews observe large, yellowish-white globe of light over the North Pacific Ocean 700 mi. east of Hokkaido, Japan. Covered one fourth of the sky. Light gradually dimmed and disappeared. *Tesla globe. Definitely a Soviet weapons test.*

June 1982 - Red China.
Several Red Chinese giant light hemisphere and globe incidents. In one instance, a/c electrical power systems began to fail in several Red Chinese fighter a/c when encountering a huge hemisphere of glowing light. *Tesla globes. Tesla shields. Balls of light. Definitely Soviet weapons tests.*

24 **Sep** 82 - Maryland, New Jersey.
Anomalous airquakes off the coast of Cape May and Northern Maryland, and Atlantic City, New Jersey. *Adjustment of Woodpecker grid. Soviet tests. 3 weeks later also.*

14 **Oct** 82 - Maryland, New Jersey.
Anomalous airquakes off the coast of Cape May and Northern Maryland, and Atlantic City, New Jersey. *Adjustment of Woodpecker grid. Soviet tests. 3 weeks earlier also.*

16 **Nov** 82 - Delaware, New Jersey.
Five mysterious booms rock Sussex county, Delaware and southern New Jersey. *Adjustment of Woodpecker grid. Soviet tests.*

1983 - Loma Linda, California.
Photos and information about the Soviet LIDA machine released. 40 MHz carrier, complex waveforms. Induces catatonic state in humans and animals. *Shows consciousness can be affected by EM means. Was used on U.S. prisoners of war in Korea. Suggests similar capabilities are possible for Woodpecker. U.S. scientific community had said impossible. President Carter affected in Jun. 79?*

Early 1983 - Bennett Island.
Large exhaust plume detected coming from Bennett Island and vicinity, one on-shore and two offshore. Plume was 6 mi. wide, 155 mi. long and reached 23,000 ft in height. *U.S. weather satellites detected it. Nearly horiz. jet, 155 mi. long. Definitely not natural. At angle ofperhaps 1.5 degree above horizontal.*

27 **Sep** 83 - England.
British RAF/Panavia Tornado aircraft loses all electrical power and crashes. *Possible Test? Tornado system is triplexed.*

22 **Oct 83** - Off Okinawa.
Two a/c operating off U.S.S. Midway apparently lost w/o trace, about 127 mi. E. of Okinawa, under anomalous conditions. *Causes unknown. Additional data needed.*

8 **Nov 83** - Western Europe.
Anomalous earthquake occurs in Western Europe. All foreshocks and aftershocks were missing. Called the "Leige" earthquake. Definite symptoms of manmade (Soviet) origin. *Large boom occurred over Netherlands the next day over 35,000 sq. km. area. Soviet scalar EM weapon testing.*

9 **Nov 83** - Netherlands.
Large acoustic event occurs over Netherlands. Detected over 35,000 sq. km. First mistaken as a Dutch quake. *One day after the anomalous Leige quake. Soviet wpn testing.*

Dec 83 - Alma Ata.
Stored munitions exploded at Dolon (Soviet) airfield. 150 km south of Alma Ata. One of six that mysteriously exploded in 7 months. *May be evidence that another nation also has Scalar EM wpns, and*

is checking the Soviets. If so, probably was warning that Soviets also would suffer if they moved.

1984 - Novaya Zemlya.
First mysterious plume detected from Novaya Zemlya by U.S. weather satellites. Sometimes plumes are 200 mi. long. *Novaya Zemlya contains Soviet atomic facilities including weapon facilities.*

1984
Senior Soviet physicist G. Yu. Bogoslovsky publishes paper, "Generalization of Einstein's Relativity theory for the anisotropic space-time." Such Russian research published regularly. Would be impossible in U.S., where similar attempts meet discredit, humiliation, and rejection by leading U.S. physics journals and departments. *The West has decreed that general relativity must not be local, and above all must not be lab-bench experimental. Open Soviet publication indicative of experimental development of local space-time curvature technology.*

1982 - 84 - Florida (& elsewhere).
Airquakes, booms (hundreds). *16 counties, near coast.*

28 Jan 84 - Pennsylvania, New Jersey.
Bright orange light streaks across sky from Pa. to N.J.'s Cape May. Similar "fireball" explodes in Clementon. Two other sky explosions observed. *Possible Soviet activity. TR wave holography and pulses. Part of Soviet deception plan.*

Feb 84 - in space.
All three payloads of the Challenger flight fail. *2 commication satillites, 1 balloon.*

10 **Feb** 84 - Netherlands.
Large atmospheric boom occurs over Netherlands. *7 others thru 1983.*

29 Mar 84 - Bennett Island.
Bennett Island exhaust plume detected by U.S. weather satellite. *Over 100 such anomalous exhaust plumes detected there.*

9 **Apr.** 84 - S. of Kurils toward USSR.
Giant rapid cloud tower rose, then faded. Small semicir. halo of light replaced it. Halo expanded to full circle of light. Expanded to giant globe then faded. *Cloud 60,000 ft in 2 min. Light globe expanded to about 380 mi. dia. and center over 200 mi. high. Source:* ***Science*** *Journal. Definitely a Soviet test of multiple weapon modes.*

26 **Apr.** 84 - Bennett Island.
Bennett Island exhaust plume detected by U.S. weather satellite. *Over 100 such anomalous exhaust plumes detected there.*

May 84 - S.E. U.S.
Series of devastating storms breaks out over S.E. U.S. in early May. Tornadoes, large hail, downbursts. Some loss of life. Persisted through night into early morning hours. Several instances of rapid thunderstorm top warming were observed in satellite photography. Occurred near downbursts. Very heavy plume activity at Bennett Is. noted in Apr. and May, 1984. *Warming of tops of thunderstorms can produce downbursts. In literature. Note that Soviet scalar EM wpns can perform such top-warming of thunderstorm anvils, and induce downbursts on command.*

13 **May** 84 - Severomorsk, USSR.
Soviet missile storage facility at Severomorsk Naval Base on the Kola Peninsula 1450 km north of Moscow blows up in a series of vast explosions. Over 200 wounded. Soviet North Fleet lost about 1/3 of its missiles. Speculation of an "electromagnetic cause, possibly by reflection of radio waves from ionosphere." Detected by satellites; first thought to be nuclear explosion. *One of six such explosions of Soviet ammunition storage sites in a period of seven months. Definitely not accidental. Probably use of scalar EM weapons by another nation, not hostile to U.S., to warn the Soviets that they also will suffer if they move.*

15 **May** 84 - Bobrwjk Airfield.
Major blast occurs at Bobrwjk Airfield, 138 km SE of Minsk and the base of a Badger-equipped air-to-surface missile regiment of the Smolensk Air Army. 10 of the 11 ammo storage bldgs blow up and admin, and access control bldgs. are destroyed. Note that fires and explosions were still raging at Severomorsk, from 13 May event. *Same note as above.*

25 **Jun** 84 - Schuerin, East Germany.
Explosion occurs at an ammunition depot at Schuerin, south of Wismar in East Germany. Windows blown out within 10 mi. radius of depot. *Same note as above.*

27 **Jul** 84 - Kuril Islands.
Slowly expanding ball of light seen by Boeing 747 crew near the Kuril Islands. Expanded for 10 min. Shell was sharply defined. Light semi-transparent and nearly perfect half-circle. *Tesla globe. Bennett Is. exhaust plumes detected by U.S. weather satellite. Definitely a Soviet test. Related to 9 Apr. 84 incidents S. of Kurils.*

29 **Aug 84** - Edwards AFB, California.
B-l bomber prototype crashes in flight test about 10 mi. NE of Edwards AF Base.

1983-84 - Ireland.
For two years, freak lightning terrorizes villages of West Donegal, Ireland. Roofs stripped off, windows smashed, pipelines wrecked, telephones and TVs blown up. *No known cause for the anomalous lightning. Shows natural potential in area is disrupted.*

25 **Dec 84** - Ireland.
Freak lightning continues in West Donegal, Ireland. Causes 3-day power blackout. *Extensive plume activity at Bennett Island.*

1985 - Worldwide.
After years of a superb safety record, airline industry suffers a series of disastrous crashes. 20 major air crashes occur worldwide, with more than 2,150 lives lost.

Early 85 - Worldwide.
KGB begins a worldwide campaign to blame the U.S. for starting the AIDS epidemic. *Effort continues. Disinformation; is believed in 3rd world.*

Jan 85 - San Diego, California.
U.S. Navy chaff caught by wind, blown in over San Diego. Power knocked out to 60,000 homes. *Symptoms of presence of Soviet scalar EM grid in San Diego urea.*

7 **Jan 85 -** Cantrell, Alaska.
Cantrell, Alaska. Blinding white light passes in sky overhead, lights up sky and mountain range for 30-40 seconds for 16 mi. Est. 3-mi. altitude. *Probable Soviet test. Note that plume activity at Bennett Is. is heavy in Jan. 85.*

Feb 85 - Zimbabwe.
Zimbabwe suffering worst electrical storm season in history. Death toll up to 116. 21 persons killed by a single bolt in one case. *Anomalous lightning. Shows natural potential in area disrupted.*

17 & **18 Feb 1985 -** Anchorage, Eklutna Flats, Northway, Alaska.
Several anomalous lights and sky booms incidents in Alaska. Skyflashes, balls of light, booms, etc. Seen both from ground and by pilots of aircraft. *Probable Soviet realtime holography tests as part of worldwide deception plan.*

19 Feb 85 - Out from San Francisco, California.
China Airlines Flight 006 Boeing 747 enroute to Los Angeles. Engines fail. A/c falls 32,000 ft. in 2 min. Restarts engines, lands at San Francisco. *Note previous incidents over Alaska on 17 & 18 Feb. Probable Soviet test of launch phase anti-bomber system capability of woodpecker transmitters.*

10 **Mar 85 -** Tblisi & Tallin, USSR.
Soviet Academy of Sciences announces an Aeroflot a/c had been followed by a UFO for 800 mi. *Soviets occasionally produce light phenomena in their own territory and near Soviet a/c as part of their deception plan. They do not wish to appear different.*

1 **May 85 -** Near Nashville (monitoring station).
In and around May Day 1985, the Soviet Union held a giant exercise of all its strategic scalar EM weapons. 27 "power taps" into the earth — each two frequencies 12 KHz apart — were activated. The earth was thus in forced gravitational resonance beneath our feet on 54 frequencies. Each tap estimated to power up to six of the giant weapons; thus over 100 major strategic scalar EM weapon transmitters were activated. Frequency bands were filled with scalar EM transmissions, command and control, including to subs on station underwater. *Frank Golden monitored this startling giant exercise, which was probably held for Gorbachev, and this author observed it by courtesy of Golden's special detection equipment. Thus the Soviets*

met the 1985 timetable established by Brezhnev in 1972 at a secret meeting in Prague of European Communist leaders. Western nations do not appear to have the equipment to monitor scalar EM emissions, and so Western intelligence agencies are believed to have totally missed this giant exercise and its significance. At conclusion, two power taps (four frequencies) were left in the earth to power "ready firing batteries," so to speak.

11 **Jun** 85 - Lanzhou, China.
China B747 crew encounters a huge, expanding yellowish glow of light, with very intense spot at center. *Probable Soviet test.*

11 **Jun** 85 - Mongolia.
Chinese jumbo jet, Peking to Paris flight, encounters giant "UFO" light form over Mongolia. 10 km. wide. Lit sky for 50 km. Extremely bright spot at center. Paced aircraft for 2 minutes. *Probable Soviet test. Soviet operator tracked a/c exhaust with long range antibomber system. Added giant light form for deception, and to create UFO reports, which are largely ignored.*

23 **Jun** 85 - Iowa, Nebraska, Kansas, Illinois, Kentucky.
Thunderstorms over Iowa, Nebraska and Kansas organized into single circular pattern rainstorm 200,000 sq. km. in area. Declined until dawn, then rejuvenated to unleash severe weather over Illinois and Kentucky. *Such organization never before had been seen. Now called "mesoscale convective complex." Shows unique new weather pattern involving giant organization.*

2 **Aug** 85 - Dallas/Ft. Worth, Texas.
Delta Airlines flight 191, a Lockheed L-1011, encounters microburst while approaching runway at Dallas/Ft. Worth International Airport. Crashes and kills 134 of the 163 persons on board. *While such microbursts occur in nature, this was during a period of intense Soviet scalar EM activity. Note that warming the tops of thunderstorm anvil causes a downburst. May have been just accident. May have been test.*

23 **Aug** 85 - Italy, Adriatic Coast.
More than 28 "UFO" sightings reported along Italy's Adriatic coast soon after **midnight.** Light phenomena. *Probable Soviet test. Part of deception plan. Scalar KM holography (real-time).*

28 **AUG 85 -** Vandenberg AFB, California.
Titan B fails after launch at Vandenberg AFB, California. Believed to have carried sensitive U.S. satellite. *Suspicious.*

Sep 85 - Kourou.
Ariane rocket explodes at Kourou. 3rd stage engine failed to ignite properly, forcing loss of power. Destruct then ordered. *French officials suspect Soviet sabotage. Probable Soviet test.*

Sep/Oct 85 - Cape Canaveral, Florida.
Anomalies observed on two U.S. shuttle launches by NASA. *No action taken; NASA does not recognize scalar EM weapons capabilities nor testing over its Cape Canaveral launch site. Nor does it connect the mysterious "booms" that have rocked the Florida coast for several years with the Soviets or with the anomalies noted on its two shuttle launches, such as giant booms.*

2 **Sep 85 -** Mexico City, Mexico.
Worst hailstorm in 50 yrs. strikes Mexico City, leaving some streets more than a foot deep in ice. 1-hr pelting. 25 bldgs collapsed. 4,000 roofs heavily damaged. 1 killed, 185 injured. Power blacked out. *May have been due to extensive Soviet long range weather engineering. 17 days prior to suspicious giant Mexican earthquake.*

5 **Sep 85 -** Australia.
Premier Wran, Australia, along with Minister of Agriculture Hallam, observe a brigh spherical "UFO" from their government jet. It was photographed. Radar contact showed object at 100,000 ft. *Probably Soviet advanced performance antigravity flying vehicle.*

18 Sep 85 7:15 pan. - Catalina Is. Channel Is.
Cookman observes giant cloud radial, awesome to behold, between Catalina and Channel Islands, off California coast.
18 "funnel" strobes, dynamically boiling. Activity indicates great energy poured into earth and atmosphere. Mexican quake the next morning. Indicator of Soviet scalar EM connected to quake.

19 **Sep 85 7:18** a.m. - Mexico City, Mexico.
Large earthquake strikes Mexico City, causing great damage. Largest of several. *Preceded wks earlier by giant anomalous hailstorm. Evening before, giant radials showed extensive Soviet power*

transmission activity. Positive indications of Soviet test.

8-9 **Nov** 85 - Ventura County, California.
Highly anomalous power blackout in Carlisle Canyon, Ventura County, Calif. Accompanied by severe electrical anomalies totally beyond normal electromagnetics. *Investigated and reported by engineer Ron Cole, who lives in the area. TV, light, phone, electrical anomalies plus intermittent 29 Hz signals.*

Nov- Dec 85 - California.
Mysterious hum continues to baffle people at Pacific Heights, Calif, and Marina district on San Francisco Bay. Previously had had same hum. Note such hum in England persisting over long period. Note 8-9 Nov 29 Hz. anomalous elec. signal at Carlisle Canyon, Ventura County, CA. *Possible indications of Soviet scalar EM activity. Area appears to be one of Soviet register / test points.*

26 **Nov** 85 - Cape Canaveral, Florida.
Launch of space shuttle Atlantis from Cape Canaveral, Florida is accompanied with high anomalies. (1) Seconds before launch, Bob Gladwin inadvertently photographs nearby strike of what appears to be an electromagnetic missile, probably of Soviet origin. (2) Anomalous light is hanging in the sky, near the launch site: a marker beacon, placed there by the Soviet scalar EM weapon system being tested. Seen by hundreds of persons, and photographed by George Suchary. Printed in Fort Pierce **Tribune.** (3) 12 minutes after shuttle is launched, when it is well down range, a tremendous rumbling atmospheric boom occurs, heard 600 mi. up and down the East Coast. Marker beacon then slewed away by distant Soviet operator at high speed. *With offset EM missile strike, Soviets tested the weapon to be used on the Arrow DC-8 two weeks later at Gander AFB, Nfld. Marker beacon used in precise registration. Note it was evidenced again above the explosion of the Titan on 18 Apr. 86 at Vandenberg AFB. Boom is from energy induced over a large area; which can catch multiple missiles being launched, a large Naval task force at sea, or a whole flight of airborne bombers, fighters, or helicopters. Also can catch an entire organization on the ground, or an installation - - wiping out all electronics, exploding explosives and ordnance, stunning or killing personnel, etc.*

*Again hundreds of NASA engineers and scientists did not recognize what was **happening** at the **site** and over their own heads.*

12 Dec 1985 - Gander, Newfoundland.
Arrow DC-8 crashes immediately after takeoff at Gander AFB, Newfoundland. Lost power just after takeoff; engines "rumbling" abnormally rather than roaring, according to eyewitness whom the a/c flew directly over, 100 ft up. Aircraft seen by three eyewitnesses to have an orange glow on it. Symptoms of negative energy introduced into engines, cancelling some of heat energy of the engines and seriously interfering with combustion process, causing loss of power. Glow may have been steady, small electromagnetic ball of energy against the aircraft, causing it to electrically charge and exhibit corona. Anomalous hole in right fuselage, just ahead of engines, as if from internal explosion; however, no explosive residue (it was tested). One other anomalous hole found. Wild swings of some instruments recording just at/after liftoff — ignored by investigation. *Note previous 36 light incidents in and around Gander, Jan. 1982. Gander Airport is major stopover for Soviets, and a major "registration point" for scalar EM weapons. Note anomalies in shuttle launch 2 wks earlier, and apparent actual test of the small EM missile then, offset so as not to destroy that shuttle.*

Aircraft crew one of Arrow's best. Aircraft should have flown okay, if not interfered with. Serious indications that the DC-8, with over 250 U.S. soldiers and air crew, was deliberately destroyed by test of a Soviet launch-phase antibomber system.

Note metal-softening Soviet signal detected on 1 Jan 86 by Frank Golden may actually have been on the Woodpecker transmissions on Dec 12,1985. This metal-softening signal probably played a part in the destruction of the Challenger on 28 Jan 86.

1 **Jan** 86 - Near Nashville, Tennessee.
Frank Golden discovers a metal-softening signal on the Soviet Woodpecker interference grid. Performs experiments to verify the metal-softening ability of the signal. *Signal is of such a nature that only Golden's instrumentation could have detected it. He then scalarly cancelled the signal to totally prove it.*

24 **Jan** 86 - Ventura, California.
Engineer Ron Cole observes and sketches a giant grid cloud pattern over Ventura, Calif, at 11:45 p.m. PST. Giant cloud fingers, separated from each other, formed the crossed-grid pattern. *Shows Woodpecker scalar EM power very high and active.*

26 **Jan** 86 - Northern California.
Strong quake hits Northern Calif. 5.5 on Richter scale. Hollister area, about 120 mi. south of San Francisco. Several power outages in southern Bay area, where quake knocked out transformers, downed 21,000 V. power line, and set off burglar alarms. *May have been induced by Soviet scalar EM transmitters.*

26 **Jan** 86 - Los Angeles, California.
In greater Los Angeles area, Margaret Wilson observes 3 classic giant radial clouds form at 10 min. intervals: 1:15, 1:25, and 1:35 p.m. Appeared one after the other, till all three were there. Last one lasted about two hours, gradually distorting. *Shows a great amount of structuring to capture and turn the Jetstream, to direct cold weather to the Florida Panhandle and catch the Challenger before its impending launch, exposing it to drastic cold conditions. Definitely Soviet engineered.*

27 **Jan** 86 - Santa Monica, California.
On evening prior to the Challenger disaster, Al Matthews photographs a strange bar-grid cloud formation, absolutely rectangular bars, from the Los Angeles freeway. Pattern approx. over Santa Monica Bay, due north of Catalina Island. Edges and ends very straight, as if drawn in sky by a giant draftsman. *Shows severe high frequency content, and fine-point localization of Soviet scalar EM transmitters, in preparation for forthcoming launch of the ill-fated Challenger.*

27 **Jan** 86 - Florida Panhandle.
Avalanche of freezing air temperatures to record lows across the Southeast. Low temperature records set all across the South. Jetstream bent far south, across Florida Panhandle. *Definitely caused by Soviet weather engineering. Preceeded by giant radial cloud signatures in "hinge" areas of Los Angeles and Huntsville, Alabama, showing steering of Jetstream.*

28 **Jan** 86 - Cape Canaveral, Florida.
Low temperature records shattered all across the South. Into 30's in Florida and into teens elsewhere. *Definitely result of Soviet weather engineering, and definitely directed against the Challenger rocket on the launch pad.*

28 Jan 86 - Off Florida Coast.
About 4 hr. before the launch of the Challenger, all Soviet ships off-coast, which normally monitor shuttle launches, suddenly depart at high speed. *Soviets do not want any suggestion that the ships' radars and transmitters may have interfered with the Challenger launch. Total anomaly. Unprecented event.*

28 Jan 86 - Cape Canaveral, Florida.
National radio and TV newsmen comment on the highly unusual fact that no birds are flying in the launch area. *Reason: For severe localization, high frequency content of the scalar EM signals had been drastically increased. A bird's brain will detect and resonate to this energy, if the wavelength approaches the diameter of its brain. This resonance will cause great pain and/ or death of the bird. Thus the birds flee the area when this begins to occur — or they die. When birds accidentally fly into such a high frequency scalar EM signal, their nervous systems are instantly jammed. They die and fall from the sky.*

28 Jan 86 - Cape Canaveral, Florida.
Space shuttle Challenger, launched from Cape Canaveral after exposure to cold weather conditions, disastrously explodes. Booster seal problem. Encounters air turbulence during launch, at most critical altitude. *Soviet metal-softening signal has been added to grid. Extreme localization in area because of high frequency content added; shown by birds having vacated the area. Anomalous departure of Soviet ships offshore, 4 hrs. earlier. Three previous tests of the weaponry in that exact launch area, against the three previous shuttle launches. Kill of the Arrow DC-8 about 6-112 weeks earlier. Actual celebration by the KGB of perfect success of their active measures against the Challenger! U.S. space program crippled and set back severely.*

29 Jan 86 - Moscow.
At KGB headquarters in Moscow, the KGB holds a jubilant party to celebrate the perfect success of their active measures against the Challenger. *Note that Soviet scalar EM weapons — development, deployment, and use — are under the control of the KGB rather than the regular Soviet armed forces.*

31 **Jan 86** - Mid-U.S.
Richter 5.0, Earthquake rattles 9 states and Great Lakes. *Possible test of weapon that killed the Challenger, in the earth transmission / earthquake induction mode.*

2-4 **Feb** 86 - Birmingham, Alabama.
In Birmingham, Alabama dead birds plummet from the air to the ground for three days. Blackbirds, cardinals, sparrows, bluebirds, etc. No trace of poison in carcasses. *Only a few days after kill of the Challenger. To divert the Jetstream further south and hit Florida, the Soviets had moved the normal "hinge pin"—where scalar EM energy, either positive or negative, is focussed —from Huntsville to Birmingham. Hinge pin area was still activated. The high frequencies used for extreme localization against the Challenger were lethal to birds. Therefore birds that inadvertently flew into this zone were instantly killed and dropped from the sky.*

10 **Feb.** 86 - Europe.
Super Frelon (French) helicopter crashes, with 11 killed. Aeronautique Navale aircraft. Part of a spate of crashes of French military aircraft in four months (through June 86). *Defense Minister Andre Giraud launched a special investigation.*

23 Feb 1986 - Irish Sea.
Over the Irish Sea in an airplane, England's Prince Charles sights a brilliantly glowing, red object hovering near them. His pilot reports the object to air traffic control. Four other aircraft traveling through that area radioed similar reports. *Probably either a Soviet craft or a Soviet holographic scalar EM demonstration as part of the overall deception plan, and/or a stimulus to a member of the Royal Family to observe what action is taken by British Ministry of Defense. By actions, could ascertain whether or not Britain knew what was going on.*

30 **Mar** 86 - Ventura, California.
Engineer Ron Cole in Ventura CA observes significant cloud patterns, positively correlated with his measurements of the Soviet woodpecker transmissions. *Cloud pattern changes were directly correlated to signal changes on the Woodpecker. Shows cloud signatures can be indications of specific Woodpecker activity.*

31 **Mar** 86 - San Francisco, California.
Strong earthquake, Richter 5.3, rocks San Francisco Bay area. Third in region in 3 days. Three aftershocks within minutes. *Note correlation of Woodpecker activity previous day.*

31 **Mar** 86 - San Francisco, California.
Crew error on Delta flight accidentally shuts down engines after normal takeoff from San Francisco. Engines restarted. *Definitely a crew error. Possible human effects from earthquake energy in area. Same type incident on Jun. 30, 1987.*

3 **Apr.** 86 - Florida.
Loud boom shakes houses and rattles windows over Brevard County, Florida. One of a whole series over the years. Not far from Kennedy Space Center. *Soviet adjustment of scalar EM grid.*

Apr 86 - France.
French Armee de L'Air has lost two Jaguars and two Alphajets in April 86. Part of a spate of losses in 4 months, leading Defense Minister Giraud to launch a special investigation.

7 **Apr** 86 - Sacramento, California.
Charlotte King of Sacramento calls UPI and predicts a major earthquake will strike in Canada, Alaska, Aleutians, or Japan. She had predicted eruption of Mt. St. Helens in 1980. On Apr. 27th, she predicted quake that shook Mexico three days later.
Note that human brain is a scalar EM interferometer, capable of transmitting and receiving scalar EM waves. Unfortunately, not conscious — output of system is in deep unconscious. Some persons are more sensitive than others, and can detect the scalar activity from the increasing stress in rocks that is leading toward an earthquake. Charlotte King is such a person, having over an 80% accuracy of prediction of quakes. She will be able to detect the increasing stress in rocks, whether naturally or artificially induced.

9 **Apr.** 86 - Aleutian Islands.
Three quakes rock the Aleutian Islands. Predicted by Charlotte King on Apr. 7. *Documented prediction.*

18 **Apr.** 86 - Huntsville, Alabama; Thousand Oaks, California.
T.E. Bearden sees and photographs remnants of a giant radial cloud

in Huntsville, Alabama. Extensive Soviet woodpecker grid activity noted over Thousand Oaks, California by Engineer Ron Cole. *Both show increased scalar EM activity in the interference grid.*

18 **Apr** 86 - Vandenberg AFB, California.
USAF Titan 34-D rocket explodes nine seconds after launch from Vandenberg AFB, California. Video captured the Soviet marker beacon **(Aviation Week & Space Technology).** Engineer Ron Cole and team study video of the explosion frame by frame and verify the anomalous beacon light is present, is separate from the explosion, and moves away separately after the explosion. *Sensitive satellite believed on board the rocket. U.S. Space surveillance program crippled. Probable Soviet kill. TR wave adjunct with Woodpecker.*

25 **Apr** 86 - New Mexico.
NASA research rocket misfires over the New Mexico desert. No public announcement made at the time. Was first failure in 25 consecutive missions of the Nike-Orion rocket. Said NASA spokesman Kukowski: "It looks like we're snakebit."
Possible Soviet test kill.

25 **Apr** 86 - California; Chernobyl, USSR.
Bill Bise detects the sudden loss of the East-West Soviet woodpecker transmitter he is monitoring in the field, leaving the North-South transmitter. The failed transmitter was about 20-30 km. from Chernobyl. The *Soviet transmitter sites safety circuits go-in full, trying desperately to hold back the giant scalar EM standing-wave potential that has been built up, and slowly and safely drain it away into the earth. In alarm, Soviets shut down nearby reactors at Chernobyl. Any "flash discharge" escape as a flash-over pulse of the scalar EM potential will produce a giant EGP pulse into the earth. When this EGP pulse reaches the four reactors, they will violently explode, full-up nuclear, like giant hydrogen bombs — perhaps 1200 megatons equivalent. Later the Soviets will claim that the operators shut the plant down to do some "unauthorized experiments."*

26 **Apr** 86 - Chernobyl, USSR.
With the giant scalar EM standing wave almost all drained away, the safety circuits finally ***fail,*** *dumping a small EGP into the earth. The nearest reactor at* ***Chernobyl*** *gets* ***it,*** *and the uranium fuel roils*

suddenly go half-decayed, instantly heating and blowing out the reactor, destroying it. Nuclear radiation fallout spreads over much of Europe.

3 **May** 86 - Florida.
Delta 178-rocket destroyed by range safety officer at T + 91 after two anomalous power surges occurred in the rocket, causing premature shutdown of 1st stage Rocketdyne RS-27 engine 71 sec. into the flight, and rocket to go aerodynamically unstable. Previous 43 launches had been successful. Since 1960, 177 launches 94% successful. One of most reliable rockets ever built. *Soviet weapons test. One of a series. TR wave adjunct with Woodpecker.*

7 **May** 86 - Aleutian Islands.
Great earthquake measuring 7.7 Richter strikes Aleutian Islands. Centered about 100 miles SE of the island of Adak. Tsunami alert issued for the North Pacific, but no major waves ever materialize. Thousands evacuate coastal areas. A *U.S. researcher known to this author used a powerful scalar interferometer to block the tsunami. The researcher must remained unnamed.*

9 **May** 86 - Redstone Arsenal, Alabama.
All power on Redstone Arsenal, Alabama suddenly and mysteriously fails all at once. *Similar related incident on May 12. No explanation.*

12 **May** 86 - Huntsville, Alabama.
In Huntsville, Alabama — adjacent to Redstone Arsenal — on local radio program Feedback, public radio discussed the mysterious failure of all power on Redstone Arsenal on Fri., May 9, 1986 and requested that, if anyone knew why all circuits would go off at once, to please get in touch. *Immediately the station's radio transmitter went off the air! (Almost as if "Big Brother's listening to you!")*

18 **May** 86 - Dijbouti.
French Breuguet Atlantic aircraft crashes in Dijbouti, killing 19. *Part of spate of crashes of French military aircraft in 4 months that leads French Defense Minister to open special investigation.*

19 **May** 86 - Brazil.
Brazilian fighter jets are sent to chase multi-colored "ping- pong ball sized" UFO's in skies over Brazil. 4 jets, two Mirages and 2 F-5's

chased them at speeds of 840 mph. Tracked on radars. Chase lasted 3 hrs. Planes could not catch them; ran low on fuel and returned. Discussed on TV by Brazil's Air Force Minister Brig. Gen. Otavio Moreira Lima. *Soviet scalar EM holographic production; distant Soviet operators having fun and games as part of the deception plan, generating UFO incidents and reports?*

22 **May** 86 - California.
High-speed orange "X" object with lights seen above Sonoma CA before dawn. At one time the object slowed and hovered.

29 **May** 86 - Huntsville, Alabama.
Huntsville and Madison County, Alabama electrical power dipped momentarily and mysteriously, causing a seconds-long outage in businesses and homes, playing havoc with traffic signals and computer centers throughout the area. Some traffic signals continued to malfunction for 30-45 min. after power was restored, then mysteriously resumed normal functioning. Some phones also went out inexplicably, and many battery-powered radios went off, and were awry for seconds or minutes before recovering. *Obviously this was not caused by any kind of ordinary electromagnetics. Shows anomalous and high activity (pulsed) in the Soviet scalar EM grid (Huntsville Ah. is a pivot point).*

30 **May 86** - French Guinea.
Ariane 2 rocket fails because of a faulty ignition system for the third stage engine. Rocket destroyed by ground command 4-1/2 min. after launch from Kourou, French Guinea. The third stage has failed 3 times since start of Ariane's operations in 1979.
Possible Soviet test.

Tad Szulc, Washington journalist, implies that French Defense Minister Andre Giraud may have discussed the possibility of Soviet sabotage of the rocket with Washington.

May? 1986 - Straits of Gibralter.
USS Atlanta nuclear sub runs aground in Straits of Gibralter and suffers "serious damage," according to reports in Madrid. A hole was made in one ballast tank and the sonar wrecked.
*Another **U.S. nuclear sub** ran aground within a month or so (earlier?) of this incident. C**ould something** have interfered with their navigation systems underwater? Continued Soviet Scalar EM tests?*

11-12 July - California.
Secret USAF crashes approx. 14 mi. NE of Bakersfield, CA along the Kern River. Site secured. Possible Stealth fighter. Crippled aircraft in trouble seen and photographed by Andy Hoyt, who turned photos over to USAF (properly so). Aircraft not on fire when came down. Did not explode in the air. *No information as to whether any Soviet scalar EM hanky-panky involved or not. Suspicious because follows a series of anomalous missile failures. Woodpeckers definitely have good anti-stealth capability.*

11 July 86 - Tennessee and Georgia.
Moderate quake with sonic boom shakes SE Tennessee and Northern Georgia. 3.7 on Richter scale. Centered just east of Chattanooga Tennessee on the TN/GA line.

12 July 86 - Michigan, Ohio, and Kentucky.
Mild quake in Michigan, Ohio, and Kentucky. 4.0 on Richter scale.

18 July 86 - Los Angeles, California.
Sharp aerial boom rattles Los Angeles Basin at about 0930 hrs. FAA and USAF unable to identify a potential source from an aircraft.

Aug 86 - Soviet Union.
Two huge new Soviet "radars" discovered on Western Soviet border by U.S. intelligence. One near Skrunda, on Lithuanian border. Other near Mukachevo, on the Czech border. *With phase conjugate adjuncts, represent significant strategic weapon system deployments.*

2 **Sep** 86 - Baltic Sea.
Finnish ferry Scandinavia in Baltic Sea observes a strong light rise from the sea near the Finnish Coast. After 3 to 4 seconds, a giant mushroom reached 500 feet into the sky and covered the moon. *Probable Soviet test.*

12 Sep 86 - Dallas, Texas.
Mysterious, powerful "explosion" rocks South Dallas. No source found or explained. No supersonic jets in area.

Selected ***Incidents***

15 **Sep** 86 - Australia.
Katherine, Australia. Object with flaming orange **tail** moved **from** sky toward ground at 45 degree angle. Katherine's electrical **power** suddenly cut off and phone lines in the town disrupted. ***Probable*** *Soviet scalar EM generated.*

Oct-Nov 86 - Los Angeles, California.
Giant radial clouds observed in Los Angeles area.

Oct 86 - Reykjavik, Iceland.
Gorbachev and Reagan meet at Reykjavik, Iceland. Gorbachev proposes "zero option." *Seeks to get nuclear missiles removed, since they constitute "dead man fuzing" because of nuclear warheads, and severely limit pulse use of Soviet scalar EM weapons. Adamantly insists on bottling up SDI — because if space laser is converted to scalar EM laser, its power (effective) goes up about* 10^{20} *times, and single shot could devastate Russia.*

10 **Oct** 86 - Vandenberg AFB, California.
U.S. forced to scrub another missile launch when a USAF Scout satellite malfunctions during final countdown at Vandenberg AFB, Calif. *The booster's gyro system failed a checkout sequence at about T-5 hr. Scalar EM can inertially interfere also.*

13 Oct 86 - ABC News.
On Peter Jennings' ABC News show, Gennadi Gerasimov, Soviet spokesman, indicated that SDI as presently designed was of no concern to Soviets. Real concern is that U.S. will make a "great technical breakthrough" and deploy new, modified devices, presenting an unacceptable threat to the Soviet Union. *Here he is thinking of changing the laser to a scalar EM laser.*

6 **Nov** 86 - Albuquerque and Phoenix.
Power failures at Albuquerque air traffic control tower and a radar station near Phoenix, Arizona occur. Radar controlling high altitude air traffic from Texas Panhandle to southern California was knocked out for 40 min. First such incident in Albuquerque center. The Arizona radar was out for 59 hrs. *Note similar incident at Montreal on Nov. 11, 1986.*

10 **Nov** 86 - Huntsville, Alabama.
Three giant radial cloud formations in Huntsville, Alabama photographed by T.E. Bearden. One is a twin giant radial. *Shows heavy activity in scalar EM interference grid.*

10 **Nov** 86 - SE U.S.
Red glowing light with tail flares across sky in Southeast about sunset. Seen over parts of TN, AL, GA, MS. Ground searches conducted in several areas for possible crash. *Probable Soviet scalar EM activity. Note heightened activity in grid same day.*

10 **Nov** 86 - Near Nashville, Alabama: Hemet, California.
Frank Golden measures scalar EG field of earth — highly agitated and dynamic, about half as much as when Soviets induce earthquakes. Anomalous winter storm in progress. Cold records broken in Mid-U.S. Heat records broken in Florida. Storm penetrates very deeply southward. *Soviet weather engineering.*

11 **Nov** 86-Canada.
Air traffic control radar in Montreal, Canada region broken down. Backup system employed. *Note similar occurrences to Albuquerque and Phoenix on Nov. 6, 1986.*

12 **Nov** 86 - Atlanta, Georgia.
Stationary arc (dome) of clouds sighted over Atlanta. Well defined lower edge. Upper edge irregular. Multiple witnesses. Clouds moved into top of dome and flowed around it. Very strange sight. *Probable Soviet "gentle test" of placing a suppressive covering over a distant U.S. city. Performed at night, at minimal level (no glow) so no great notice would be taken. Dome was stable against 20 mph winds and other moving clouds that collided with it.*

13 **Nov** 86 - Huntsville, Alabama.
Twin giant radial cloud observed moving over Huntsville, Alabama by T.E. Bearden. West to East. At nearly noon. At dusk, single giant radial cloud was also spotted over Huntsville.
Significant scalar EM activity in grid.

17 **Nov** 86 - off Alaska.
JAL Flight 1628 observes giant UFO while enroute from Reykjavik, Iceland on mid-leg of Europe to Tokyo. Crossed Beaufort Sea off

Alaska's north coast. Sighted flashing lights which moved alongside the aircraft. Pilot descended, so did light. Glimpsed craft in profile, twice as big as aircraft carrier. On board radar located it. USAF and civilian controllers reported brief radar echoes, but tapes did not show it. Approaching Fairbanks, Alaska. Pilot made 360 degree circle, object stayed with him. Finally disappeared as he was approaching Anchorage. *Probable Soviet test as part of deception plan. TR wave holography.*

27 **Nov** 86 - Fort Pierce, Florida.
Flash of light in sky and sonic boom occurred vicinity of Fort Pierce, Florida. *Probable Soviet EM test. Note that a classified payload was scheduled for launch in near future at Cape Canaveral nearby.*

4 **Dec** 86 - Huntsville, Alabama; Hemet, California.
Twin giant radials seen and photographed over Huntsville AL. Large radial cloud seen in skies over Hemet, Calif, and photo printed in **The Press Enterprise,** Hemet, CA 5 Dec 86.

4 **Dec** 86 - Cape Canaveral, Florida
Atlas/Centaur rocket successfully launched at Cape Canaveral, orbits a communications satellite for DOD. *The Soviets had to allow one or two of the missiles to succeed, else even the lethargic U.S. bureaucracy would have caught on. Grid activity indicates they probably just tracked it without the other goodies.*

5 **Dec** 86 - Vandenberg AFB, California.
MX ICBM launched from Vandenberg AFB. Two of RVs did not deploy although all impacted within the Kwajalein Missile Test Range. *Note: Soviets let one go from Vandenberg.*

21 **Dec** 86 - Huntsville, Alabama.
Twin giant radial photographed over Huntsville Alabama.

23 **Dec** 86 - Huntsville, Alabama.
Small flash in lower sky over Huntsville, Alabama observed by T.E. Bearden. Followed by faint boom. Momentary loss of power occurred in large area of Huntsville. Positive correlation between the aerial flash/boom and the loss of the power. *Soviet test.*

7 - 21 Jan 1987 - Florida.
Several giant radial clouds seen in vicinity of Fort Lauderdale, Florida. *Indicates substantial action in scalar EM grid.*

20 **Jan** 87 - U.S.
Highly unusual bend in Jetstream. Completely down West Coast, curving east under Texas, NE along SE USA. *Shows great action in scalar EM grid. Significant weather engineering.*

20 **Jan 87** - Vandenberg, AFB, California.
Minuteman missile destroyed in launch. *Note substantial action in scalar EM grid.*

23 **Jan** 87 - Huntsville, Alabama.
Bearden photographs twin giant radial over Huntsville AL. Cloud fades with great and unusual rapidity. A private-type jet, similar to a Learjet, continually circled under the strange twin radial cloud, as if observing and/or photographing it. *Perhaps someone in the U.S. system wised up.*

28 **Jan** 87 - Vandenberg AFB, California.
Minuteman missile successfully launched from Vandenberg AFB. Note: *Anniversary of the Challenger disaster.*

7 **Feb** 87 - Alabama - Tennessee border.
Loud aerial boom or explosion shakes area from Tennessee, New Market, Monte Sano through Huntsville Alabama area.

10 **Feb** 87 - Huntsville, Alabama.
Bearden photographs twin radial cloud in Huntsville, AL. Cloud stayed fixed, although winds present and other clouds moved. Note big storm in NE - Cape Cod, etc. *Associated with weather engineering.*

11 **Feb** 87 - Huntsville, Alabama.
Bearden photographs another twin giant radial in Huntsville, Alabama. *Shows activity in Woodpecker grid.*

Feb 87 - Vandenberg AFB, California.
USAF Titan launched from Vandenberg AFB, Calif.

12 Feb 87 - California.
Blue Angel F-18 a/c crashed near Brawley, CA. Fourth military air crash in the Imperial Valley since October. *Note Woodpecker grid activity on previous day.*

26 Feb 87 - Cape Canaveral, Florida.
GOES-H weather satellite launched from Cape Canaveral on a DELTA rocket.

26 Mar 87 - Cape Canaveral, Florida.
Stunning failure of an Atlas/Centaur rocket launched from Cape Canaveral. May have been hit by lightning. Failed suddenly 51 sec. after liftoff. Veered out of control and destroyed. *Note: Possible Soviet scalar EM involvement. Much to do later about multiple lightning strikes; very suspicious.*

June 1987 - Vandenberg AFB, California.
Minuteman 3 missile fired from Vandenberg AFB, Calif, is aborted and destroyed in flight. *Note similar incident in July.*

12 **Jun** 87 - Cape Canaveral, Florida.
Trident III launched successfully from flat pad.

21 **Jun** 87 - Alaska.
Three strong earthquakes shake parts of remote Alaskan Peninsula.

30 **Jun** 87 - Los Angeles, California.
Delta 767 flight 810 crew inadvertently shuts down engines shortly after takeoff from Los Angeles. Starts to fall, restarts engines and recovers. *Definitely crew error. Similar incident on Mar. 31, 1986 after takeoff from San Francisco.*

12 July 87 - Over Pacific Ocean.
Minuteman missile is destroyed in flight over the Pacific Ocean because of a problem in flight. Launched from Vandenberg. *Note similar incident the previous month.*

16 **Jul** 87 - Huntsville, Alabama.
Anomalous largo "boom" occurs at Huntsville, Alabama.

17 **Jul** 87 - Huntsville, Alabama.
Another anomalous, large "boom" occurs at Huntsville, Alabama. *Note that Huntsville is a pivot point on the Soviet grid. Adjustments in the grid often "spill out" energy, causing such a boom. It causes a sharp boom if pinpoint spillage occurs. It causes a more general quaking, rumbling sound of longer duration if spillage occurs over an area.*

20 July 87 - Cape Canaveral, Florida.
Tident III successfully launched from flat pad.

14 **Oct.** 87 - Nellis Air Force Gunnery range.
Top secret plane crashes; possible stealth fighter. *Did the Soviets kill another one?*

9 **Nov.** 87 - Vandenberg, AFB, California.
Minuteman II missile is destroyed seconds after launch. *Unnamed anomalies cited. Did the Soviets interfere?*

4 **Jan.** 88 - Madison and Huntsville, Alabama.
Giant radial sighted for several hours. Three mysterious booms rattle Huntsville. *Soviet scalar EM activity continues.*

APPENDIX V

*DEAD MAN FUZING** *THE REAL MEANING OF THE REYKJAVIK SUMMIT*

Soviet Foreign Minister spokesman, Gennadi Gerasimov, following failure of the Iceland Summit, said in a radio interview that SDI (U.S. Strategic Defense Initiative), as presently designed, is of no concern to the Soviet Union. The real Soviet concern, he indicated, is that the U.S. would make a great technical **breakthrough** and deploy new devices in space as a modification to SDI **presenting** an unacceptable threat to the Soviet Union.

Peter Jennings' ABC News Show, Los Angeles, CA
13 October 1986.

Gerasimov let the cat out of the bag!

With their deployed scalar electromagnetic weapons, the Soviets would immediately hold the winning hand-if these weapons could be unrestrainedly brought to bear.

As pointed out in **Fer-de-Lance: A Briefing On Soviet Scalar Electromagnetic Weapons,** Tesla Book, Co., 1986, the use of massive Soviet scalar EM weapons can only be gingerly applied. Activation and use of the Soviet scalar EM weapons is fraught with grave danger to the entire earth and to the whole human species because of the presence of nuclear facilities in the desired target area, and because of the "backlash" potential against the Soviet Union's own nuclear weapons and facilities.

The explosion at Chernobyl was apparently caused by the accidental failure of a nearby scalar EM transmitter, and the eventual impulsive loss of part of the electrogravitational potential built up by the transmitter before it failed. The resulting electrogravitational pulse (EGP) in the earth "pulsed" the nearest nuclear material... feul rods in the reactor at Chernobyl.

Had the EGP not been depleted prior to its escape, all four reactors at **Chernobyl** would have exploded with the same intensity as if they had been "triggered" by a fission explosion.

---

*The term "Dead Man Fuzing", means that, even though your opponent kills you, a weapon or effect of your own will inevitably result which will then kill your opponent.

In short, if unrestrainedly used, the EGPs from the Soviet scalar EM weapons would initiate most of the nuclear weapons where they are in the targeted area-in storage, in silos, in aircraft, etc. Target area nuclear reactors and nuclear wastes would also be violently initiated into nuclear explosion. The resulting vast megatonnage of nuclear explosions, much of them "in the dirt, " would provide an unthinkable holocaust. The effects of these giant explosions, deadly fallout and dense clouds of smoke and dirt, would blanket the earth with nuclear effects greater than is presently expected from an all out nuclear war, in which many of the weapons are expected to be destroyed or lost without being exploded nuclearly. Deadly nuclear radiation would blanket the globe, contaminating it for thousands of years. From the covering of the earth by dense smoke and dirt clouds, a new and deeply bitter global ice age-not just a "nuclear winter"-would almost certainly be initiated. In 1960 Khrushchev appropriately characterized these fantastic weapons by stating that they could wipe out all life on earth if unrestrainedly used.

A country's nuclear weapons and facilities, then, become its inadvertent "dead man fuzing" to prevent any substantial employment of large scalar EM weapons against it. So long as nuclear "dead man fuzing" is in place in a country, its adversary can only utilize scalar EM superweapons against it with great difficulty, and then only sparingly. At present, both the U.S. and its NATO allies are "dead man fuzed" by the presence of Western nuclear weapons-and to some extent, by the presence of nuclear reactors and stored nuclear wastes.

Obviously the Soviet Union's task of world domination—and the mind-rending risks it must take in employing large scalar EM weapons—would be greatly expedited if the obstacle of "deployed U.S. and NATO nuclear weapons and facilities" could be eliminated or minimized.

Also, Gorbachev must be acutely aware that the U.S. is finally beginning to look at the possibility of scalar EM weaponry. He would assume that either the U.S. is already on the way to acquiring scalar EM weaponry of its own, or else the time is imminent when it will do so. If this happened, and the U. S. then were to deploy SDI **scalar** EM lasers in space, the effects of each laser would be enormously increased by the electrogravitational amplification factor. Reasonable gain increases of the yield of each laser shot might approach, for example, on the order of 10^{20}. In that case, each laser could suddenly devastate a whole state or region with one or two shots, instead of just being able to destroy one little missile. The Soviets know that Reagan's Star Wars weapons-if modified to the "improved" kind and deployed in space—could deliver a surprise first strike in seconds, and devastate Russia before all the Star Wars space weapons could be knocked out by Soviet ground-based scalar EM beams.

The Soviets also know that it is not too difficult to modify lasers to become such powerful scalar EM lasers.

This means that Gorbachev needs to insure that the Star Wars weaponry is not actually tested in space. Testing in space requires developing at least prototype "space deployment" SDI weapons, to get them up in space to test them from there in the first place. And even such "prototype" SDI weapons would be sufficient to devastate the Soviet Union, given that the prototypes employed the technological breakthrough represented by scalar EM weapons. This is what Gerasimov was really referring to!

Thus Gorbachev simply cannot allow such space testing of SDI weapons, if he hopes to be able to safely seize the opportunity to employ his own already-deployed, massive scalar EM weapons during the "window of time" that would be provided by dismantling of U.S., NATO, and Soviet nuclear weapons.

And-given that he gets agreement and implementation of the "zero option"-Gorbachev knows he will only have a narrow "window" of time in which he can hope to achieve world domination. It can be only a short time until the U.S. produces results in scalar EM weapons, and promptly develops such weapons of its own. Faced with that eventuality, Gorbachev would then have no choice but to turn away from the Communist dream of world domination, and reach a mutually agreed accommodation with the West. Both the West and the Soviets then would have to take immediate and drastic measures to prevent the rapid development and spread of the relatively cheap scalar EM weaponry throughout other nations, particularly those motivated from fanatical beliefs and quite capable of "blowing up the earth" deliberately.

Thus, before the U.S. becomes aware of scalar EM weapons and builds its own, Gorbachev desperately needs to get rid of the "dead man fuzing" problem posed by the nuclear weapons and facilities possessed by the U.S. and its Nato allies, so that he can utilize his superweapons to dominate the world without destroying it.

And he needs to block any chance that the U.S. would be able to have space-tested high energy laser prototypes which could be quickly modified to scalar EM weapons, fired into space, and used to counter Soviet aggression or even destroy the Soviet Union in retaliation.

In short, today the paramount and almost desperate need of the Soviet Union is to reduce American dead-man fuzing and keep the SDI space laser genie bottled up in the lab on the ground.

Accordingly, in Iceland, in what appeared to be a stunning concession on nuclear arms, Gorbachev suddenly offered Reagan a complete dismantling of all nuclear weapons-Reagan's "zero option." Actually this move had been planned by Gorbachev from the beginning; it was not a spur-of-the-moment offer. The reason was simple: If the U.S. could only be persuaded to quickly get rid of its nuclear weaponry, the Soviets would hold an absolutely winning hand. Their massive, deployed, operational scalar EM weapons could then be unleashed with minimal restraint. The extremely delicate and incredibly dangerous problem of bringing the large scalar EM "continent-buster" weapons to bear, without inadvertently causing world destruction, would be vastly eased if only the ordinary U.S. nuclear facilities such as nuclear power plants and radioactive wastes had to be reckoned with.

Fortunately, Ronald Reagan fervently believes in defense .

He made the right decision, whether or not it was for the right reasons.

Indeed, he probably knew in advance that SDI was to be targeted in Iceland by the Soviets, and that sweeping concessions might be offered by them for that purpose. According to one report (" 'Blinded' Satellites," Rowland Evans and Robert Novak, **Washington Post,** Oct. 29,1986), just before Reykjavik the CIA-sent a report to Reagan with the warning that "the sole reason for Gorbachev's wanting the Iceland summit was to offer unprecendented inducements for Reagan to drop SDI."

Fortunately, Reagan rejected Gorbachev's proposal, because he does not wish to give up what he truly regards as a potential defense against incoming Soviet missiles.

Apparently neither Reagan nor his advisors were aware of the real reason for Gorbachev's unexpected and breathtaking proposal for what would essentially be near-total nuclear disarmament.

The Soviet ground-based scalar EM lasers could sweep the heavens of the presently conceived SDI weapons, as **Gerasimov** obliquely implied. However, this would not change the barrier represented by U.S. nuclear dead man fuzing, unless the nuclear weapons had been removed.

Meanwhile, Gorbachev's chess game to remove the dead man fuzing is certainly not over. The Soviets have mounted an intense propaganda campaign urging nuclear disarmament and cancellation or restraint of SDI. With a Democratic Senate now in, and with the approaching end of Reagan's term in office, the Soviet effort to clear the U.S. nukes-and the dead man fuzing-out of the way for Soviet deployed superweapons, while keeping the SDI genie in its laboratory bottle, can only be intensified. Already the Soviets are beating every drum to get substantial antinuclear segments of the U.S. scientific, congressional, political, and pacifist communities aroused to oppose SDI and urge a quick zero nuclear option.

The treaty for dismantling certain missiles in Europe has already been signed by the President, and its ratification by the U.S. Senate appears imminent. More is yet to come, and quickly.

In its aching desire for peace, if an unsuspecting America falls into Gorbachev's trap, shackles SDI and removes its dead-man fuzing, the Soviet Union will be free to enforce its will wherever and whenever it wishes.* If that happens, our beloved stars and stripes will be replaced with the atheistic hammer and sickle. And the noblest experiment of all—freedom for the common person—will have come to an ignoble end.

---

*Just as **Brezhnev forecast** for 1985, **at a** secret meeting in 1972 of the communist party leaders of E**urope.**



BEARDEN

ENERGY FROM

THE VACUUM

Concepts & Principles



ENERGY FROM
THE VACUUM

Concepts & Principles

Energy from the Vacuum is the culmination of 30 years of original thinking and looking with fresh eyes at concepts that are presently considered to be foundations of science, a process of on-going analysis recommended long ago by Albert Einstein.

Dr. Bearden's findings are good news, for his theories point the way to the extraction and harnessing of inexhaustible clean energy from the vacuum.

With the development and ubiquitous deployment of free-energy mechanisms, the strategic vulnerabilities of centralized power systems can be eradicated, and the run-away degradation of the biosphere reversed. And there is suddenly a viable antidote for the perpetual poverty of under-developed nations.

Also contained in this book are the true stories of inventors who, over the past 150 years, have pioneered some of these processes and their secrets. Dr. Bearden rigorously analyzes more than 40 embodiments that can produce this free energy, including some capable of investigation at the high-school level.

Lt. Col. Thomas E. Bearden (U.S. Army, retd.) has a Ph.D. in science, an M.S. in nuclear engineering, and a B.S. in mathematics.

Lt. Col. Thomas E. Bearden, Ph.D.
(U.S.Army, Retired)

The definitive energy book of the 21st century.

Sweating done by red_gonzo.

Note: sometimes formatting of the text may be a little fuzzy. It's all because the OCR process didn't go as smoothly as I expected. Also there may be some errors inside text so be vigilant. In any case share this book, send emails to people about knowledge contained in it. If you are an amateur electronic guy/girl try to make some good use of this knowledge and post your results. Try to use physics vocabulary as is presented in this book because as the author concludes, there are many good inventors around but they each use their own vocabulary and explanations of their inventions which are only understandable to them.
And please don't be naive and expect you'll be buying those devices in your local supermarket any time soon. Although some progress is being made it's still to slow, especially with the suppression factors watching over it. The knowledge has been handed to you and it's expected that at least a few of us make some use of it. Gather together and try to share your results with the rest of us.

TABLE OF CONTENTS:

Acknowledgements xi

Foreword xiv

Chapter 1 1

Foundations and Scientific Mindset 1

1.1 Introduction 1

1.2 Organized Science Often Resists Innovative Change 24

1.3 Scientific Disagreement or Street Fight? 32

1.4 A Few Significant and Unresolved Scientific Problems 36

1.5 Electrodynamics is Still Developing 51

1.6 A Summarizing Letter 55

Chapter 2 75

Background and Concepts 75

2.1 Comments on the Foundations of Classical Electrodynamics .. 75

2.2 Lorentz Regauging of the Maxwell-Heaviside Equations 108

2.3 The Suicidal Closed Unitary Current Loop Circuit 119

2.4 In Summary 122

Chapter 3 125

Giant Negentropy, Dark Energy, Spiral Galaxies and Acceleration of **the** Expanding Universe 125

3.1 Broken 5-Symmetry of the Dipole 127

3.2 Reinterpreting Whittaker's Decomposition of the Scalar Potential 137

3.3 **How** the Dipole Charges Transduce Time Energy 141

3.4 Reordering of the Local Vacuum: Giant Negentropy 143

3.5 Some Implications of Giant Negentropy 143
3.6 How Circuits Are Powered 153
3.7 The Heaviside Component vs. the Poynting Component 155
3.8 Dark Positive Energy: The Unaccounted Heaviside Component 157
3.9 A Short History of the Discarding of the Heaviside Dark Energy 158
3.10 The Problem of the Accelerating Expansion of the Universe **164**
3.11 In Conclusion **166**

Chapter 4 171

Setting the Stage for Understanding Overunity Power Systems 171

4.1 Introduction 173
4.2 Demonstration Gedanken Experiment **180**
4.3 Iterative Retrorefiection and Collection in a Circuit **194**
4.4 Tesla's Iterative Retroreflection Work **197**
4.5 Perspective on Tesla vs. Marconi 203
4.6 Conclusion **209**

Chapter 5 219

Selected Approaches to Overunity Power Systems 219

5.1 Introduction 219
5.2 Tesla's Shuttling of Potential Energy and Barrett's Extension 220
5.3 Moray's Radiant Energy Device 220
5.4 Anti-Stokes Emission and Similar Processes 225
5.5 Gain in Intensely Scattering Optically Active Media 227
5.6 The Fiber Fuse 230
5.7 Multiple Feedforward and Feedback Semiconductor Loops. ..235

5.8 Negative Resistors 236
5.9 Suppression of Free Energy Systems Has Been Common 288
5.10 In Conclusion 289
Chapter 6 293
Additional Approaches to Overunity Power Systems 293
6.1 Introduction 294
6.2 Energy Conversion and Energy Amplification 295
6.3 Other Systems of Electrical Interest 304
6.4 Some Magnetic Processes of Interest 341
6.5 Conclusion 381
Chapter 7 385
Aharonov-Bohm Effect, Geometric Phase, and the Motionless **Electromagnetic Generator** (MEG) **385**
7.1 Introduction 387
7.2 Aharonov-Bohm (Geometric Phase) Effect 390
7.3 Abbreviated History of the Geometric Phase 391
7.4 Possible New Aspect of the Curl-Free Magnetic Vector **Potential** 393
7.5 Use of Aharonov-Bohm Effect in the MEG 397
7.6 Collection of Field Energy in the MEG 403
7.7 Experimental Path to Development of the MEG 408
7.8 **Additional** MEG Functions 411
7.9 In Conclusion 419
Chapter 8 421
Approach to Antigravity 421
8.1 Introduction 422
8.2 Selected Theories of Gravitation 423
8.3 Selected Antigravity and Inertial Engineering Research Efforts 431

8.4 The Author's Engineering Approach to Local Antigravity.....454
8.5 In Conclusion 471

Chapter 9 473

The Supersystem and Remarks on Gravity, Antigravity, and Testing 473

9.1 The Supersystem and Its Considerations 476
9.2 Differences between Effects in COP»1.0 and COP<1.0 EM Systems 479
9.3 Primarily Concerned With Dirac Sea Holes and Not Lattice Holes 487
9.4 Peculiarities of Spacetime Curvature and Dirac Hole Interactions 488
9.5 Charging and Discharging a Capacitor 490
9.6 The Open-Loop COP>1.0 EM Power System 495
9.7 Remarks on Dirac Sea Holes, Currents, and Negative Energy 501
9.8 Remarks on the Observed Acceleration of the Expanding Universe 505
9.9 A Solution to the Hole Current Problem and Close-Looping..509
9.10 Negative Energy: Localized and Nonlocalized 510
9.11 Tests Reinforcing the Antigravity Mechanism 514
9.12 Susceptible Unitary System without Conversion of Dirac Sea Hole Current 519
9.13 Unitary System with Conversion of Dirac Sea Hole Current 521
9.14 Non-unitary Outrigger Array System 521
9.15 Some Instrument Considerations 525
9.16 Still Anomalous Aspects 528

Chapter 10 537

Cold Fusion: Low Spatial-Energy Nuclear Reactions at High Time-Energy 537

10.1 Explaining Time as Energy 539

10.2 Mechanism Generating Flow of a Mass through Time 540

10.3 Time-Polarized EM Waves and Longitudinal EM Waves 542

10.4 Time Reversal Zone and New Nuclear Reaction Mechanisms 554

10.5 Revision of the Conservation of Energy Law 560

10.6 Some Resulting *Low Spatial Energy* Nuclear Reactions 566

10.7 Time-Energy Can Generate Instrumentation Anomalies 570

10.8 Additional Implications for the Future 577

Chapter 11 583

Final Perspective: Permissible COP>1.0 Maxwellian Systems 583

11.1 Introduction 583

11.2 Source Charges, Curved Spacetime, Efficiency, and COP....585

11.3 Truncations of Maxwell's Theory and Discard of System Classes 590

11.4 Examples of COP>1.0 Electromagnetic Systems 594

11.5 Motionless Electromagnetic Generator (MEG) 596

11.6 Physical Considerations of Gauge Freedom 599

11.7 Special Modeling of the Vacuum 600

11.8 Every Charge and Dipole in an EM System Receives and Transduces Vacuum Energy 601

11.9 Energy from the Vacuum Powers Every Electrical Power Line **and** EM Circuit 601

11.10 Significant Developments in Negative Resistance 602

11.11 In Conclusion 605

Annotated Glossary of Selected Terms 609

Appendix A 739

Appendix B 767

Index (not included because you can search in PDF) 774

ENDNOTES 849

Acknowledgements

This book is dedicated to those lone researchers and stalwart inventors who have succeeded in building working model COP>1.0 electrical systems in the face of overwhelming odds and strong scientific opposition. We particularly mention Gabriel Kron , T. Henry Moray, John Bedini, Jim Watson, Ed Gray, Frank Golden, Floyd Sweet, Howard Johnson, Ken Shoulders, Bill Fogal, the Correas, and Teruo Kawai. There are quite a few others, of course, and no slight is intended by not listing all their names.

Also, I particularly acknowledge the contributions of my long-suffering close colleagues Dr. Lee Kenny, Dr. Jim Hayes, Ken Moore, and Steve Patrick, whose efforts on the bench have produced the working motionless electromagnetic generator (MEG) experiments as well as several variants. Our first MEG patent was issued in April 2002 and a second patent application has been filed. The MEG represents the first practical macroscopic application of the geometric phase (extended Aharonov-Bohm effect) for EM power systems. I particularly thank Lt. Col. (Retired) Ken Moore for watching my back and keeping me alive. I'm also grateful to both Dr. Fred Wood Sr. and Dr. Fred Wood Jr. for their personal support, action, and encouragement. I particularly acknowledge more than two decades of close cooperation and work with John Bedini, who is one of the most creative inventors on this planet; nearly a decade of work with Floyd Sweet and his vacuum triode amplifier; more than a decade of work with Frank Golden in COP>1.0 motors and uncurled A-potential communication systems; and a special thanks to Don Jensen for his important contributions and work in special combustion systems. Working with these inventors, I was able to physically examine working COP>1.0 power system prototypes and also experience and study the novel phenomenology that results in such systems.

With deep appreciation I acknowledge the kind assistance and helpful critiques of Dr. Myron W. Evans and other members of the Alpha Foundation's Institute for Advanced Study (AIAS) such as Alex Labounsky, Alain Beaulieu, and Bob Flower. Dr. Evans encouraged me to write down the basic concepts of the theory of permissible COP>1.0 Maxwellian systems I have been working on for three decades. This book is the result of that effort.

A special note of thanks goes to Dr. Dave Hamilton of the Department of Energy, who oversees a DoE restricted website provided for the important

ongoing scientific work **and drafts of the AI**AS. On that site, now there are more **than** 100 AIAS papers, many **of them dealing** with EM energy from the vacuum in rigorous fashion. Many of these AIAS draft papers have been published in leading journals such as ***Foundations*** *of Physics Letters, Physica Scripta, Optik,* etc. **This** is an invaluable scientific effort that clearly establishes the importance and potential for extracting copious EM energy directly from the active vacuum. It also extends the present U(1) electrodynamics to the much more extensive O(3) group symmetry electrodynamics, in which such things as I discuss in this book can indeed be accomplished on the bench and mathematically modeled.

The outstanding work and encouragement of Dr. Hal Fox and Dr. Eugene Mallove are particularly recognized, and I am grateful to them for their continued publication of important information and developments in cold fusion and the entire field of anomalous energy systems. I am also grateful to Dr. Robert Flower for his cogent explanations of some tough issues and points in quantum field theory that were beyond my ken before his explanation. Dr. Hal Puthoff introduced me to his cosmological feedback mechanism, and I am grateful for his important work with his colleagues in the areas of inertia, permissible thermodynamic extraction of energy from the vacuum, and possible mechanisms of antigravity.

A special thanks goes to Tim Ventura and to Jeffrey Cameron and the engineers of Transdimensional Technologies, Inc. for their courtesy and demonstrations of Transdimensional's successful lifter and rotary devices, and for an introduction to the field of inertial propulsion and antigravity now ongoing under the NASA Breakthrough Propulsion Physics (BPP) research program.

To Marcia Stockton I owe very special thanks indeed for her tireless efforts in reading and proofing the manuscript and translating the graphics. Also, I am much indebted to Michael Anderson for the art direction, and to Tony Craddock for making it possible. I am deeply grateful to Tony for his unfailing encouragement and support, and for operating and maintaining my website www.cheniere.org. I also deeply appreciate the continued contributions of Mike Rieker, of Network Innovations, who furnishes the website pro bono. A special thanks also goes to Dr. Steve Greer, who gave my wife and I great assistance and personal uplift at a time of personal tragedy. Dr. Greer has also now taken up the effort to develop and deploy practical electrical power systems, freely taking their EM energy from the vacuum.

Stalwart modern researchers in the overunity movement such as Jerry Decker and Walter Rosenthal are particularly to be commended for both their work, assistance to others, and their communication of work in the field. I am much indebted to Walt for furnishing the pictures of the closed-loop Sweet vacuum triode amplifier used in this book.

To Jean-Louis Naudin, I also am very grateful for his extraordinary experimental work and extensive publication of valuable information, his personal replication of a variety of systems, and his kind permission to use several illustrations in the book. His important website, http://jnaudin.free.fr/, is a cornucopia of information, experiments, and results in this entire area, with important links to many other appropriate web sites.

Also, to more than a dozen special persons — including those now passed on such as Glenn Foster and R. J. Reynolds III — who encouraged and supported these efforts through the years, I am very grateful. Throughout the years their kind words and friendship have made a very great difference to me personally and professionally, and they still do.

Finally and most importantly, I acknowledge the continuing and unwavering support of my dear wife, Doris, without whose encouragement and tolerance this work could never have been accomplished. She made all these long years of seven-day weeks and 18-hour days possible and humanly bearable. Without her, this book simply could not have been written.

Foreword

The original purely scientific purpose of this book was interrupted en route by two events: The first was a sudden heart attack and onslaught of severe hypoxia resulting from the resurgence in Spring 2001 of a 33-year old chronic mycoplasma infection, of the modified biological warfare kind produced by a combined U.S./Canadian team, which got loose in Canada and Florida in the 1950s. I contracted this "mysterious, unknown ailment" in 1968 while in the U.S. Army and stationed in Quebec, Canada as the U.S. Army Liaison Officer to the Canadian Armament Research & Development Establishment (CARDE). The second event was the sudden terrorist attack on the U.S. on September 11, 2001, which propelled this nation and others into a war against international terrorism.

For the mycoplasma, Kenn Thomas recognized and informed me exactly what the difficulty was, and I was finally tested and diagnosed correctly in December 2001 due to the efforts of a courageous family physician. Accordingly, in December 2001 we started a yearlong (or longer) regimen of antibiotics and supplementary oxygen, with additional medication to control the runaway heart fibrillation associated with this virulent form of the disorder. If we make it through this yearlong program, we will probably survive with at least some significant recovery. Now on a much-reduced regimen, this made me realize the absolute necessity of passing the "energy from the vacuum" information and baton, so to speak, to those sharp young graduate students and post doctoral scientists who are interested in this area. They simply must not have to spend 30 years of their lives getting to this point. Instead, they should start where I am now, correct any errors I have inadvertently made, and go much farther.

Accordingly, we sharply changed the intent and content of the book to comply with that new purpose. We also deeply considered the potential U.S. and World energy implications of that second shocking event of 9/11 when international terrorists struck the World Trade Center in New York Center and the Pentagon, having also targeted the White House.

In the new asymmetric form of warfare, the internal aspects of a nation - its civilian population, its vulnerable installations, its energy infrastructure, its food crops, and its transportation modes — are the targets. Terrorist teams and groups in significant numbers are already inside every targeted developed nation, and these teams have weapons of mass destruction including biological weapons and even nuclear weapons. For confirmation of the hostile nuclear weapons already secreted in large U.S. cities, read Lunev's book[1] to see how the former Soviet Union brought them in, along with the Spetznaz teams to detonate them on call. The nuclear weapons and the Spetznaz teams are still here. Other hostile nations have inserted terrorist teams with weapons such as anthrax, smallpox (camel pox is nearly identical to smallpox, and widely available), bubonic plague, etc. At the end of the 1991 Persian Gulf War, most of Iraq's calutrons and its nuclear program escaped the weapon inspectors and were hidden. In the few calutrons we did get, weapons-grade U235 residues were found. In a formal threat study for a foreign nation, begun before the Gulf War and delivered after its end, my analysis team and I estimated that Iraq had produced sufficient U235 in 1991 for from 7 to 12 nuclear weapons, particularly of the gun assembly type. My personal estimate now would be that Iraq has made sufficient weapons grade U235 to build three dozen to six dozen nuclear weapons. If so, then some of those weapons are undoubtedly long since spirited into the United States, and planted in our large cities.

In modern asymmetric strategic war, the first phase of the war is conducted in "peacetime". The first phase is to insert the weapons of destruction into the targeted nation and hide them at the intended targets, along with the teams to detonate and unleash the weapons when desired. In that sense, the first phase of WW III has already been accomplished.

According to Vice-President Cheney,[2] *"The war on terrorism will not be over in our lifetime. It is different than the Gulf War was in the sense that it may never end. At least not in our lifetime. The way I think of it is, it's a new normalcy."*

With much of the cheap oil of the world in its borders, the MidEast is a powder keg ready to explode. If a clash between the U.S. and Iraq occurs, Saddam Hussein has already clearly shown that he will attack and destroy his foe's energy infrastructure and he will also use weapons of mass destruction. Simply witness the hundreds of oil wells set afire in Kuwait by Iraqi forces during the Persian Gulf War, and the use of chemical weapons on his own people. As this is being written, Pakistan and India are skirting the brink of war, and both have nuclear weapons. Either side that decides on war **will have to make a n**uclear strike on the other. They have no antimissile defenses, hence **making the** "first knock-out" or pre-emptive strike is each **nation's** only **chance of survival.** Hopefully cooler heads will prevail, but **If that** war erupts, the Mid East, oil, and present energy infrastructures will never again be the same, for the entire world.

---

[1] Stanislov Lunev and Ira Winkler, *Through the Eyes of the Enemy,* Regnery, Washington, D.C., 1998, p. 26.

[2] Vice President Richard B. Cheney, October 21, 2001.

There are other very serious U.S. vulnerabilities of gas and oil pipelines, port facilities, Gulf of Mexico oil rigs, nuclear power plants, power substations, hydroelectric dams, long power transmission lines on towers, etc. that are too numerous to enumerate. With but a moment's reflection, one realizes that even normal and cheap guerrilla-type or commando-type forces with C-4 explosives and timers can destroy a very substantial portion of the energy infrastructure with minimal risk and loss of assets. For those who wonder about a nuclear power plant's vulnerability, visualize a seized Boeing 747 loaded with fuel and flown directly into the main reactor container . If meltdown occurs, the nuclear tragedy at Chernobyl in 1986 will appear tame by comparison. There are also several other electromagnetic ways (such as a portable EMP "shooter" hauled in the back of a personal SUV) to instantly destroy the electronic controls of the nuclear power plant, seriously risking runaway and core meltdown.

Consequently, increasing attention is now focused on the extreme vulnerability of the centralized energy infrastructure in the U.S. and every other developed nation. So what started for me as a purely scientific endeavor to set out the concepts and principles of permissible COP>1.0 EM systems suddenly assumed a role of potentially critical strategic significance to the U.S. and to the entire developed world. Quite simply, some 20,000 terrorists in teams already in the United States can - at this very moment —destroy large portions of the nation's energy infrastructure at will, easily and cheaply. The economy of any modern developed nation depends on the availability of cheap energy. So this kind of hostile strategic capability means that the power to readily destroy a nation's economy — and thus defeat a mighty nation itself in the ensuing economic collapse — has passed into the hands of hostile forces already in country and awaiting the order to commit their assets.

In this new asymmetrical form of warfare, it would appear that the rapid development and deployment of significant distributed power sources is now a critical element of national survival for many nations of the world. Decentralization **does** little **good, however, if fuel** for the decentralized generators must remain **centralized and distributed** by very large and complex systems.The **fuel and Its distribution** are still extremely **vulnerable resenting** easy **targets allowing paralysis** of the decentralized generators. Self-refueling *{self-powering)* of the electrical power systems is therefore a mandatory additional requirement.

So sober assessment dramatically reveals the need for self-powering electrical power systems, freely extracting their EM energy from the local vacuum. Thus an engineerable theory of permissible COP>1.0 EM systems has become essential to the national survival of the U.S. and many other nations, so that an effective decentralized energy infrastructure — with the seething vacuum as the "localized and inexhaustible free fuel supply" — can be rapidly designed, developed, and deployed.

Sadly, the leaders of the scientific community are still in a "business as usual" mode with respect to energy, and intend to remain so. They do not even recognize what powers and *always has* powered an EM circuit and system: EM field and potential energy extracted directly from the vacuum by the broken symmetry of the source charges and dipoles. Since no scientific research on EM energy from the vacuum is going to be launched by the scientific leaders at the top, then the results of the broken symmetry discovered in 1957 are going to have to be applied in the scientific community from the bottom up. Consequently, a rather desperate need to communicate everything possible to the young graduate students and post-docs has become imperative, if the nation is to survive.

From the beginning of my effort in COP>1.0 systems, and then my effort on this book and prior to the events leading to the attack on September 11, 2001, the appalling *humanitarian* need for COP>1.0 electrical power systems taking their energy from the vacuum has been obvious and overwhelming. One third of the human population usually goes to bed hungry at night. One third is infested with worms and parasites of one kind or another, in addition to other diseases. Simple things such as clean water, common sanitation, medical treatment, and jobs to support one's family are difficult things in many parts of the world.

In the final analysis, the only way to get a suffering, impoverished, and undeveloped nation up and going is to provide cheap clean energy, and to do it with systems which get their "fuel" for free, such as from the vacuum itself. Once cheap clean energy and self-powering systems are widely available, then the economy and infrastructure of that nation can be slowly and steadily built up to get the society moving. Roads, bridges, hospitals, schools, teachers, industry, and jobs then follow as the economy rises. Until there is a cheap energy infrastructure available and growing, essentially fuel-free, none of that is going to happen in most impoverished nations because presently the world's fuel is monopolized, controlled, and

fought over, and it will become even more expensive as the supply vs. **demand** ratio falls, prices escalate, and additional wars - almost certainly involving weapons of mass **destruction** - are engendered. With present aid concepts, at best the politicians and warlords usually get the bulk of whatever assistance is sent in, and the warlords on the take from foreign masters will continually plunge the country into turmoil, war, and human tragedy. *Assistance is necessary,* but the eventual aim has to be to enable and empower the common citizens to be self-supporting, educated and trained, relatively free from disease, and living in a nation having a growing and developing infrastructure, jobs, and a decent economy. Availability of cheap and affordable energy — and *clean* energy if we wish to save the precious environment — is the primary key to "freeing and empowering the developing nations" as well.

Along with this omnipresent, desperate humanitarian need, the increased strategic need for decentralized energy systems freely fueled from the vacuum itself has led me to make every effort possible — particularly after the heart attack in 2001 and in continued hypoxia from severe chronic mycoplasma infection — to finish the book and at least outline the major concepts and principles that enable the construction of a sorely-needed COP>1.0 electrical power systems theory, followed by the development and rapid deployment of actual self-powering systems. The Alpha Foundation's Institute for Advanced Study (AIAS), spearheaded by Dr. Myron Evans, has also been vigorously preparing and publishing papers in leading scientific journals and other publications[3] showing that EM energy from the vacuum is permissible, possible, and feasible.

In my three decades of work with multiple inventors of working prototype COP>1.0 electrical systems, I have been privileged to experience and work with several actual COP>1.0 circuits and prototype systems, study them, and slowly comprehend some of the advanced and unusual principles involved. In short, thanks to the courtesy and kindness of others, I have been able to gradually acquire at least an elementary understanding of the mechanisms which enable COP>1.0 EM power systems. With this background, one can understand why conventional EM systems and circuits do not develop COP>1.0 or self-powering, even though all the energy collected and used in every electrical power system comes from the vacuum and not from the shaft energy input to the generator, chemical energy dissipated in a battery, wind energy collected by a windmill (that just "feeds" the shaft of the generator), or from the water power dissipated in a hydro turbine (the hydro turbine also only turns the shaft of the generator, which does not actually furnish the power to the external power line connected to it).

---

[3] E.g, *Modern Nonlinear Optics,* Second Edition, 3 Vols., edited by M. W. Evans, Wiley, 2001; M. W. Evans et al, "Derivation of 0(3) Electrodynamics from the Irreducible Representations of the Einstein Group," *Found. Phys. Lett.,* 15(2), Apr. 2002, p. 179-187; "Anti-Gravity Effects in the Sachs Theory of Electrodynamics," *Found. Phys. Lett.,* 14(6), Dec. 2001, p. 601-605; "Classical Electrodynamics Without **the Lorentz Condition: Extracting Energy** from the Vacuum," *Physica* ***Scripta,*** **61(5),** May 2000. p. 513-517; "Runaway Solutions of the Lehnert Equations: The **Possibility of Extracting Energy from the Vacuum,"** *Optik,* 111(9), 2000, p. 407-409.

It seems appropriate that other researchers should be able to start where 1 am now, understand what I have learned or think I have learned, find and correct any errors, and simply go forward with alacrity — much farther than I have been able to go, and much faster. This is particularly true of the young researchers who have excellent theoretical and experimental skills and a vigorous lifetime ahead of them. When an old and tiring runner falters with the baton, it is time to pass it on to the fresh young runners who can carry it to the successful end of the race.

The purpose of this book, then, is to lay out in some little detail what I have learned in all these years of sustained effort, but in such a way that it ties directly into good physics. In some cases, the tie-in to physics is unavoidably to a somewhat esoteric area such as the geometric phase and to time as a special form of energy. COP>1.0 EM systems are not simple, and they involve special phenomenology rarely encountered in conventional EM circuits and systems. COP>1.0 EM systems simultaneously involve a combination of particle physics, modern active vacuum theory, advanced materials science, higher group symmetry electrodynamics, quantum mechanics, and general relativity. They also involve areas where foundations of physics are presently in error. We found it necessary to think in terms of the *supersystem,* defined as having three components, which are (i) the physical power system itself, (ii) the active local vacuum, and (iii) the active local curvatures of spacetime. All three components of the supersystem interact and exchange energy with each other continuously. Any legitimate COP>1.0 power system must freely receive, collect, and use some excess energy from its active environment — in this case, the latter two components of its supersystem. By definition, this COP>1.0 function requires disequilibrium between the system and its active environment, so that classical equilibrium thermodynamics does not apply. Instead, the thermodynamics of systems far from **equilibrium** in **their** energetic exchange with an active environment applies.

However, since the "environmental energy" we are extracting is virtual photon energy from the vacuum and energy from local curved spacetime, the fundamental definitions of classical thermodynamics and classical electrodynamics have to be re-examined and altered. A closed system, e.g., can no longer be defined just as one closed to the transfer of mass across its boundary, but permitting energy to exchange across it. Since the advent of general relativity in 1915, we have known that energy and mass are the same thing. Whenever any system changes its energy, it also changes its mass by the well-known $E = mc^2$ rewritten as $dm = dE/(c^2)$. Further, in the fierce virtual particle exchange of the vacuum with every part of every system, both virtual mass and virtual energy continually cross the system boundary. Neither classical thermodynamics nor classical electrodynamics deals with the transduction of time-energy into spatial energy in a system, which is a totally different type of energy exchange accomplished by charge.

Further, certain phenomenological areas — such as strong gradients — are already well known to violate present thermodynamics. These are presently being researched under the aegis of *extended nonreversible thermodynamics.* Finally, as the present laws of classical thermodynamics are stated in the textbooks, *every charge and dipole in the universe already violates those laws, and has done so since the beginning of the universe.* Let us put it bluntly: Every charge in the universe already freely and continuously pours out EM energy in 3-space in all directions, without any observable EM energy input. That is the well-concealed *source charge problem,* known but ignored by the leaders of the scientific community for. a century. *All* EM fields and potentials and their energy come from those source charges, according to electrodynamics itself. Either we must give up the conservation of energy law entirely, or else we must accept the fact that unobservable *virtual* EM mass and energy are continuously absorbed

The vacuum by the source charge, transduced into real observable EM energy, and then re-radiated in 3-space in all directions as observable EM energy, creating the associated fields and potentials reaching out across the universe. That this problem continues to be ignored by the scientific community — some 45 years after the basis for its solution has been proven and is well known in particle physics — is totally inexplicable. But it continues to be resoundingly ignored, which means that *the scientific community itself is and remains totally responsible for the energy crisis and the associated vast desp**oilment of the** biosphere, because it adamantly* *insists on using a seriously flawed electrical energy science whose hoary basis is more than a century old.*

Accordingly, we have simply extended the first law of thermodynamics appropriately, pointed out that the second law does not apply absolutely but only as an approximation when conditions are appropriate, and revised the third law and the zeroth law. In this book we simply show the results of that revision, particularly in Appendix A.

We were also able to trace the history of electrodynamics, and to find exactly how the permissible Maxwellian systems far from equilibrium with an external active environment — which are included in Maxwell's 1865 seminal theory and even in Heaviside's vector truncation later — were arbitrarily discarded by Lorentz with his symmetrical regauging of the Maxwell-Heaviside equations. The purpose of such arbitrary regauging was and is to provide simpler equations that can usually be solved analytically without resorting to numerical methods. In the name of mathematical simplicity and ease, that entire great class of Maxwellian systems far from thermodynamic equilibrium in their supersystem was just arbitrarily discarded. Those Maxwellian systems are still arbitrarily discarded in every electrical power-engineering textbook today.

So the first requirement for a COP>1.0 EM system becomes *building-in a mechanism to violate the Lorentz symmetry condition, at least for a significant fraction of the time.* Further, the standard closed current loop circuit — including the entire external circuit in the same closed current loop as the source dipole inside the generator is what already *self-enforces* the Lorentz symmetry condition. Consequently, in any legitimate COP>1.0 electrical system, the operation of that closed current loop circuit must be violated for some portion of the system's operation. This of course places the system in disequilibrium with its active supersystem environment, allowing intake of extra energy from the environment and therefore permitting COP>1.0. So one of the immediate requirements in COP>1.0 electrical systems research is to seek out and find known or suspected mechanisms that accomplish just such violation of the Lorentz symmetry condition. In the book, I show a sampling of the various mechanisms I found other inventors using or that I uncovered myself, or that already exist in physics.

Finally, we discovered (and found the basis for it was shown in the hard literature in Heaviside's original work) that every generator and battery as an energy transducer already extracts from the vacuum and outputs from its terminals a far greater *nondiverged* energy flow than is accounted in the

Poynting diverged energy flow theory (which captures only that small **fraction that** is **diverged** into the circuit and captured by it). The total output energy flow from the terminals of a generator is also far greater than the mechanical energy input to the shaft of the generator. So in its *energy transduction* function, every dipolar electrical circuit ever built is already a "free energy circuit" and a COP >>1.0 system, extracting its utilized electrical energy from the vacuum and extracting additional energy also. But presently the electrical power system is unwittingly designed and constructed by engineers to deliberately destroy the source of that enormous energy flow from the vacuum faster than the system can use some of it to power its load. Wryly put, that does not seem to be the proper way to build energy systems or "run an energy railroad," even though it's always been done that way.

This led to recognition of a great scientific faux pas, perhaps the greatest in history. One must keep one's sense of humor! So with tongue in cheek, let us state it this way: *There is not now, and there never has been, a single electrical engineering department, electrical engineering professor, or electrical engineering textbook that teaches what powers an electrical circuit. Yet the basis for it has clearly been in particle physics since 1957, as certified by the award of the Nobel Prize to Lee and Yang. What powers every electrical circuit and system is the broken symmetry of the primary power system's source charges and source dipole (i.e., the broken symmetry of the opposite charges on the ends of the dipole) in its fierce energy exchange with the seething vacuum, once that dipole has been made. The modern "charge" is also a dipolarity, once its associated clustering virtual charges of opposite sign are considered. Further, any dipole will freely extract EM energy from the vacuum, convert it into real, usable, observable EM energy, and pour out real, usable EM energy continuously and indefinitely, so long as the dipole remains intact.*

The external circuit attached to a generator is not powered by the mechanical energy that is input to the generator shaft. The external circuit attached to a battery is not powered by the chemical energy expended by the battery. Astonishingly, every electrical power system and electrical circuit ever built, and every one built today, was and is powered by energy extracted and transduced directly from the active vacuum by the broken symmetry of the opposite charges on the ends of the source dipole (or a charge considered as a modern dipolarity), once that dipole is formed. A Nobel Prize was awarded to Lee and Yang in 1957 for the prediction of broken symmetry (strongly in 1956). Wu and her colleagues proved it **experimentally** in early 1957. So revolutionary a change in physics was that startling discovery of broken symmetry, that — in a nearly unparalleled action — the Nobel Committee awarded the Nobel Prize the same year, December 1957, to Lee and Yang. *One of the broken symmetries proven was that of opposite charges such as are on the opposite ends of every dipole, or such as constitute a classical "isolated charge" when the charge and its clustering virtual charges of opposite sign are considered as in modern physics theory. Rigorously, every source dipole is continuously extracting EM energy from the vacuum and pouring it out of the "terminals" of the dipole in all directions in 3-space. And so is every charge as well.* That the leaders of the scientific community continue to ignore this solidly proven fact is astonishing. But they do.

We also came to realize that the great Gabriel Kron, who was never allowed to reveal the secret of his *open path,* had in fact discovered the precursor of that very broken symmetry of opposite charges (of dipolarity). His open path is simply the recognition that any two points in the universe, that are at differing potentials and therefore can be considered as a dipolarity of opposite charges, acts as a source dipole that already extracts virtual photon energy from the vacuum, transduces it into real, observable photon energy, and pours out that energy in all directions. In reaching that understanding, he had applied general relativity to rotating electrical machines, simulated various forms of electromagnetics equations, and dealt deeply with quantum mechanics and the Schrodinger equation.

Sadly, the electrodynamics model used in electrical power engineering still does not even model the active vacuum, *much less* a broken symmetry in the virtual photon exchange between that active vacuum and all the charges in every electrical system. The electrical engineering model does not model the *supersystem,* hence cannot be used to design and produce COP>1.0 systems. *A priori,* that seriously truncated and crippled model arbitrarily discards all permissible Maxwellian systems far from thermodynamic equilibrium (i.e., with broken symmetry) in their vacuum flux exchange. And those are precisely the systems that are permitted to perform the five magic functions of great interest to the COP>1.0 energy researcher. Such a disequilibrium system can permissibly (i) self-order, (ii) self-rotate or self-oscillate, (iii) output more energy than the operator inputs (the excess energy is freely received from the active environment), (iv) power itself and its load simultaneously (all the energy is freely received from the active environment), and (v) exhibit negentropy. *Every charge and dipole in the universe already performs all five magic functions.*

It is **the purpose** of this book **to** clearly show that all EM systems are already powered by vacuum energy, and always have been. We cite the references and experimental proof that this is true, and the interested reader can check the extensive references himself or herself. The intent is to show that only a part of what has been discovered and is already known in particle physics is presently included in the woefully inadequate and ancient electrical power-engineering model. And frankly, unless there is a groundswell from the bottom of the scientific community, the leadership of the scientific community has no intention whatsoever of funding or allowing significant research in extracting copious EM energy from the vacuum (very simple) and learning to use it effectively (more difficult). A single 200 million dollars of good research in EM energy from the vacuum would solve the energy crisis forever, and dramatically reduce the pollution of the biosphere. The scientific community will spend many times that amount on their favored "big science" projects, but not one cent on EM energy systems powered by energy extracted from the vacuum.

Also, we show a sampling of the present work ongoing in inertial propulsion and antigravity research. Working with Sweet, in the 1980s I designed and Sweet performed a highly successful antigravity experiment.[4] I share with the reader the concepts and theoretical basis for that experiment, why it worked and how it worked, and the excellent results achieved. One of the tragic losses to science was the loss of the Sweet COP»1.0 vacuum triode amplifier (VTA) system with the death of Floyd Sweet. Nonetheless, we apply the mechanism we conceived so long ago to propose a mechanism generating the antigravity recently confirmed to be accelerating the expansion of the universe. We offer the long-neglected, Lorentz-discarded giant nondiverged Heaviside energy flow component accompanying every field-charge interaction as the probable generatrix of the excess gravity holding the arms of the spiral galaxies together. And we offer that same component — when connected with a flow of *negative* EM energy and with *negative energy* EM fields and potentials — as the specific generatrix of the excess antigravity that is accelerating the expansion of the universe. Both theses are testable on the laboratory bench.

Our target audience is several fold. Even though presented conceptually, the material is not oversimplified, and it is targeted at (i) the sharp young grad students and post-docs interested in extended (higher group internal symmetry) electrodynamics and in researching and developing COP>1.0 electrical power systems, (ii) the forward-looking electrical engineering professors who will at least consider that extended electrodynamic models and the laws of nature do permit COP>1.0 electrical power systems, and (iii) the still open-minded leaders of the scientific community, such as the National Academy of Sciences, National Science Foundation, the U.S. Department of Energy, the great national laboratories, etc. In *one area* of physics much better models of electrodynamics enabling COP>1.0 power systems, antigravity, and novel propulsion systems already exist (and a few such systems *experimentally* exist in the hands of independent inventors as well), while in a *second area* of physics that part of electrodynamics dealing with permissible COP>1.0 EM systems and unified field theory has been arbitrarily excluded at great cost to society, to the environment, and a tragedy to science and technology. Additional secondary targets are (iv) governmental leaders responsible for advanced research and development planning and funding, to argue that the "energy crisis" is a direct result of an inexplicable and sustained shortfall in the scientific mindset, and not as a result of the laws of nature and the need for cheap oil, coal, and gas or nuclear power plants, (v) science writers, journalists, and entrepreneurs to sensitize them to (hopefully) a coming energy revolution of unparalleled proportion, (vi) strategic and tactical planners in our Department of Defense to make them aware that the great logistics burden of modern highly maneuverable armed forces can and will be dramatically lowered by rapidly developing and using self-powering power systems "fueled" directly by the local active vacuum, and by adapting novel new propulsion methods, (vii) theoretical and experimental physicists to make them aware that the easiest thing in the world is to extract copious EM energy freely from the vacuum; just pay *once* to make a little dipole or assemble a charge and do not let it be destroyed, (viii) the Department of Energy upper level managers to bring into their awareness the coming advent of (and terrible need for) self-powering decentralized EM power systems worldwide, and the pressing need for a major role to be played by the DoE, (ix) the struggling but serious COP>1.0 researchers and inventors, to give them a technical overview — rather than just anecdotal material — of much of what has been done, tried, and conceived, and what seems to be successful and what is still to be determined, (x) the environmentalists devoted to cleaning up the biosphere and saving this precious planet, to make them aware that the answer to the world's energy problems and saving the biosphere cannot come to them from their conventional scientific consultants, who are trained in applying the very scientific disciplines responsible for the problem in the first place, and (xi) **the long suffering undeveloped** and impoverished nations and peoples of the earth. Our fervent message is one of hope after all, *once a **change** occurs in the scientific mindset.* There is a cheaper, cleaner, and better way to get their economies and nalional infrastructures up and running, and it is imminently doable.

---

[4] Floyd Sweet and T. **E. Bearden,** "Utilizing Scalar Electromagnetics to Tap Vacuum Energy," *Proc 26th Intersoc.* ***Energy Conversion*** *Eng. Conf. (IECEC '91),* Boston, Massachussets, 1991, p. 370-375.

The main message of this book is that there is not now and there never has been an *electrical energy availability* problem. Every large centralized power generator actually outputs enough EM energy flow, extracted directly from the seething vacuum, to power all electrical loads on earth, if all the energy pouring from its terminals were caught and utilized. However, there is certainly an *EM energy flow interception* problem, to get more of the available energy flow from a source dipole intercepted and diverged into the circuit in a manner not complying with the Lorentz symmetrical regauging condition. Also, once the excess energy has entered the circuit and been collected, there certainly is a problem in *using the intercepted and collected energy in the circuit without destroying that part of the generator or battery — the source dipole — that is actually extracting all the energy from the vacuum.* Or at least to use the circuit's collected energy in such fashion as to destroy the source dipole in the generator *slower* than the energy is used to power the external load.

That conglomerate of the two sub problems — the "energy flow *interception, collection, and usage* problem — is the single energy problem. There is no other energy problem, and there has never been any other. One finds it very ironic that, in the conventional agencies, universities, the DoE, the National Science Foundation, the National Academy of Sciences, the national laboratories, etc., not one of them is working on the real, solitary electrical energy problem, even though they are importantly spending billions of dollars purporting to do so.

We fervently hope that the content of the book will reach a sufficiently interested audience to begin to change that century-old erroneous scientific mindset. We hope that the book, along with the important contributions of other COP>1.0 inventors and researchers having success, will spark a new creative drive in the scientific spirit that solves the problem of cheap, clean energy in three years or less. This is a doable. I firmly believe in the scientific method and what it can do once it is unleashed from the century-old dogma that COP>1.0 systems are against the laws of nature, physics, and thermodynamics. Just turn the young scientific and engineering tigers loose on the problem, give them some funding, and watch them do it.

As we stated in a formal rebuttal to a charge of perpetual motion nonsense, it only takes one white crow to prove that not all crows are black. And with respect to COP>1.0 EM systems far from thermodynamic equilibrium with their active environment, every charge and dipole in the universe is already a "white crow" pouring out EM energy freely and continuously with the speed of light, and exhibiting COP = ∞. This is in fact reluctantly recognized in physics, but it has essentially been buried from the attention and knowledge of generations of electrical engineers and most physicists.

A COP>1.0 experiment well known to nonlinear optics is the Bohren-type experiment, demonstrating the known negative resonance absorption of the medium. A typical experiment of that type outputs some 18 times as much EM energy as the experimenter inputs by standard calculations. We note that a single replicable experiment can and does negate any theoretical model that contradicts it. Hundreds of such materials experiments proving the feasibility of COP>1.0 EM systems are performed every year in any major nonlinear optics laboratory without a second thought. Together with the known but avoided source charge problem and proven broken symmetry of any dipolarity, it is almost unthinkable that our electrical engineering departments still do not incorporate the active vacuum exchange — and every EM circuit's broken symmetry in it — into the classical electrodynamic model used. In short, to really understand what powers every EM circuit, just now the electrical engineer would have to go across campus to the particle physics department and investigate broken symmetry of opposite charges — as are on the ends of the source dipole, once created in the generator or the battery, or as are involved with the single "isolated charge" considered with its associated virtual charges of opposite sign.

It is high time that our electrical power engineers and scientists heed the message of all these demonstrated white crows of nature, and begin developing and deploying self-powering COP>1.0 electrical power systems with alacrity.

We have a biosphere, a planet, a strong world economy, and an uplifting for the long downtrodden poor people of the world to recover. We strongly urge the scientific community to accept the challenge and meet it head-on.

Tom Bearden

22 July 2002.

Chapter 1

Foundations and Scientific Mindset

> *"...the scientist makes use of a whole arsenal of concepts which he imbibed practically with his mother's milk; and seldom if ever is he aware of the eternally problematic character of his concepts. He uses this conceptual material, or, speaking more exactly, these conceptual tools of thought, as something obviously, immutably given; something having an objective value of truth which is hardly even, and in any case not seriously, to be doubted. ...in the interests of science it is necessary over and over again to engage in the critique of these fundamental concepts, in order that we may not unconsciously be ruled by them."* [Albert Einstein]{1}

1.1 Introduction

Einstein's quote is a beautiful statement that scientists should never take the present understanding — and the present models — as absolute. That is the approach the present author has taken for some 30 years, in a struggle to comprehend that class of electromagnetic (EM) systems that are open systems in disequilibrium in their *virtual photon energy exchange* with the active vacuum, and exhibiting a broken symmetry in that exchange. The statement beautifully expresses that the major problems encountered in grappling with such EM systems have been the existing errors and non-sequiturs in classical electrodynamics and other parts of physics. Many difficulties have resulted from the continued propagation of a 137-year old classical electrodynamics model formed before electrons, atoms, nuclei, positrons, the active vacuum, special and general relativity, quantum mechanics, etc. were discovered or known.

1.1.1 EM Foundations Are Incomplete and Contain Errors

In any model, there are many assumptions. Even when a model is well-fitted and well-developed, it still applies only when the foundations assumptions on which it is based are true or are not too much in error. Whenever one or more of the fundamental assumptions is violated by phenomena uncovered, then there is a new class of phenomena where the model does not hold, or does not hold well and is only an approximation at best. In that case, either the existing unsatisfactory model must be improved and advanced, or a new model must be constructed.

Great scientific minds continue to point out Einstein's beautiful principle in different words. E.g., expressing the thought of Stephen Hawking, one of the great physicists of our day:

> *"All we ever know is our models, but never the reality that may or may not exist behind the models and casts its shadow upon us who are embedded inside it. We imagine and intuit, then point the finger and wait to see which suspect for truth turns and runs. Our models may get closer and closer, but we will never reach direct perception of reality's thing-in-itself.*" [As stated by George Zebrowski] {2}.

Excellent scientists — Feynman, Wheeler, Bunge, Evans, Barrett, and many others — have indeed pointed out that classical EM theory is seriously flawed. In the words of Bunge {3}:

> *"...it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state."*

The author also found it imperative to return to many of the original seminal papers of physics, particularly in electrodynamics. The major concepts in those papers led to the present classical EM model. This was particularly true of the work of Poynting {4a, 4b} and Heaviside {5a-5c}, who independently and simultaneously arrived at the notion of the flow of EM energy through space[5]. Their work occurred in the 1880s, after Maxwell was already deceased. It also necessitated reviewing Lorentz symmetrical regauging of the Maxwell-Heaviside equations, where Lorentz arbitrarily discarded all permissible COP>1.0 Maxwellian systems.

The science of this "EM energy flow through space" is controversial to this day. Which is the real "EM energy flow vector" as such has never been adequately resolved, and there continue to be polite debates about it {6}. One should also be aware that physicists really do not know what many things — including energy — *are*. The definitions of these fundamentals are still uncertain, as stated rather poignantly by Feynman {7} in this quote:

---

[5] As we shall point out later, the concept of energy flowing through 3-space is a non sequitur and requires substantial revision today, to be consistent with the nature of observation and the fact that no observable continuously persists. Any observation is an instantaneous frozen 3-space "snapshot" at a single instant, gone the next instant when almost immediately replaced by another such frozen snapshot. In between observations, not mass but *masstime* exists. The same is true for 3-space, which only exists as the output of an observation process. Prior to observation, *spacetime* exists.

> *"It is important to realize that in physics today, we have no knowledge of what energy is."*

As another fundamental example, Feynman {8} also pointed out that we really do not know what *force* is[6] either! Quoting:

> "*One of the most important characteristics of force is that it has a material origin, and this is not just a definition. ... If you insist upon a precise definition of force, you will never get it!"*

1.1.2 Physics Is Not the Mathematics, But What It Manipulates

Following Feynman's ansatz, one should realize that the physics is not really in the mathematics itself, but in the physical meaning of the concepts that the mathematics manipulates. Here again, the inimitable Feynman {9} cautioned against over-attachment to the mathematics itself. He said it very clearly:

> *"Mathematicians or people who have very mathematical minds, are often led astray when "studying" physics because they lose sight of the physics. They say: "Look, these differential equations – the Maxwell equations – are all there is to electrodynamics it is admitted by the physicists that there is nothing which is not contained in the equations. The equations are complicated, but after all they are only mathematical equations and if I understand them mathematically inside out, I will*

---

[6] The problem is the ubiquitous and erroneous use of a "separate" force acting on a "separate" mass. Actually mass is a *component* of force, as can be seen from $F \Sigma d/dt(mv)$. Hence there is no such thing as a separate force in empty space, acting upon a mass. Instead, the massless 4-field in space acts upon mass to produce force *in that interaction*. Force is not a cause, but an effect of an ongoing interaction — as is any observable. An observable is a continuing series of frozen 3-space LLL snapshot entities given by the result of continual application of $\in/\in t$ (LLLT) ♥ LLL by photon emission. The formation of the LLLT (spacetime and masstime) in between observed m as LLL, is produced by photon absorption of the previous $m = \in/\in t$ (LLLT).

> *understand the physics inside out." Only it doesn't work that way. Mathematicians who study physics with that point of view – and there have been many of them – usually make little contribution to physics and, in fact, little to mathematics. They fail because the actual physical situations in the real world are so complicated that it is necessary to have a much broader understanding of the equations."*

Such matters and similar thoughts had bothered me even back in the early 1950s, when I could not find a single professor or dictionary of physics that *logically* defined a field or a potential. Considered rigorously, the definitions all fell apart and violated elementary logic. Improper, insufficient, or just plain *wrong* definitions in physics have continued and are still widespread to this day. To give a single example from an excellent book by Kraus {10}: On p. 60, Kraus gives the formula for a potential referred to as the "absolute potential" of a charge source. Quoting:

> *"This potential... is, by definition, the work per coulomb required to bring a positive test charge from infinity to the point* r_1*."*

Kraus erroneously "defines" the scalar potential identically as work, which is equating the cause with the effect. The work that dissipating a potential does or can do, is not the potential itself! Else "human" means nothing but how well one can chew one's food or drive an automobile. Actually, Kraus gives one theoretical way to measure or calculate the effect of the potential's *local intensity at a point.*[7] Note that what is measured is the energy *diverted from* the potential at that point, around that test charge. This does not specify the *entity* (the potential itself) at all, but only what has been diverted from it. It is rather like confusing the whirlpool (water diverged from the normal river flow) in a river as being the river itself.

---

[7] To show the non sequitur, a million more positive test point charges could be brought from infinity to that same point, and the potential — without any change in it — would cause the same amount of work to be done upon each of those charges. As can be seen, even noted professors can speak rather casually when they "define" the potential's point intensity as "the" potential (which extends over all space, not just at that one point). There may be different intensities at different points in the potential, but the potential itself remains one-and-the-same thing regardless of which one or all of the point intensities are discussed. And neither the point intensity of the potential nor the potential is the work that is done upon a moving charge by that potential or its intensity.

Integrating what has been diverted from it does not yield the potential itself! At best, the measurement gives an indication of the *intensity* of the potential at a point, insofar as its reaction with charge is concerned. More rigorously, what is being utilized is the potential's reaction cross section presented to a *unit point static charge* at that point. The same unit point charge, if placed in particle resonance, will sweep out more geometrical area and exhibit a greater reaction cross section. That will increase the energy collected divergence of the energy flow that is being moved around the particle itself. By normal calculations, the resonant charge may collect some 18 times as much energy as is possible at the same point by the same charge in static mode — e.g., as shown by Bohren {24, 25}.

A definition must present an identity. Examining the proposed definition as "the potential is identically … work" one sees the problem immediately. *The potential exists whether or not there is a positive test charge, or whether one moves such a charge in from infinity or not, and whether there is any work done or not.* None of that is what a potential *identically is*, but only one aspect of what it *does* or *can do* or *can cause.* One leaves as an exercise for the reader the task of further examining dictionaries of physics and textbooks, to try to find a satisfactory definition of that common scalar potential.[8] We do not believe the reader will find it.

Yet any good textbook will also contain some real gems of great insight, simply said. As an example from Serway {11}, we eventually took a most marvelous cue, of how to get around classical thermodynamics' prohibition against heat energy "running uphill" from hot to cold. In an insightful statement, Serway said {11}:

> *"The second law [of thermodynamics] does not rule out the possibility of pushing heat uphill, as it were, from a cold object to a hot one, or of creating order out of*

---

[8] The scalar potential identically is actually a harmonic set of phase conjugate longitudinal EM wavepairs, as shown by E. T. Whittaker in 1903 {85}. Even Whittaker, however, misinterpreted his wavepairs only after interaction with that ubiquitous unit point charge assumed at every point in space. He gave two *effects* of that interaction, not the *cause* (which exists prior to interaction) *and the effect* (which exists only after interaction). Reinterpreting to get at the causal wave, each wavepair is a matched set of two waves; an incoming EM longitudinal wave in the time domain prior to interaction with a charge, and — after the time-energy wave is absorbed by the charge, an emitted outgoing EM longitudinal EM wave in 3-space. The so-called "static" potential is not static at all, but is a dynamic, ongoing 4-space process. This follows the re-interpretation by the present author {12} of Whittaker's decomposition — a reinterpretation then found to be consistent with quantum field theory {19} and with broken symmetry of opposite charges in particle physics {73}.

> *disorder. It merely states that such a reversal of the natural flow requires an influx of energy…"*

This essentially states the *law of entropy*, where to reverse entropy (disorder), one must apply ordering (energy).[9] We also note that the original concept of entropy was as *dissipation of potential*. There are of course different ways to apply the energy, and it need not be by the operator himself. Chapters 4, 5, 6, 7, and 8 of the present book give some unusual ways. A special paper {12} published by the author in 2000 gives another. Indeed, when the flow of time is predominantly reversed, so is the "entropy" of a situation, since the "videotape is running backward", so to speak. In that case, the entire classical thermodynamics must be extended to essentially include its own opposite. The making of a small time-reversal zone where such things happen is as simple as involving a predominance of antiphoton interactions with the charged particles in that zone, rather than a predominance of photon interactions. What we are saying is that the notion of irreversibility in thermodynamics is not necessarily absolute. It usually assumes a “time forward” situation, and may not hold in a “time-reversed” situation. In our chapter on cold fusion, we will present some specific and quite startling nuclear interactions that occur as a result of the time reversal of the coulomb barrier (repulsion of like charges in a forward time situation) into a coulomb attraction between like charges in a time-reversal zone and time-reversed situation.

---

[9] Now notice what Serway’s statement means with respect to the classical thermodynamics “definition” of closed system. Thermodynamics defines a *closed system* as one in which mass is not exchanged across its boundary, but energy can be. That definition permits a closed system to receive excess energy from its active environment, and thereby reduce its entropy. A specific example is simply potentializing a circuit, prior to movement of the current. Hence the entropy of a closed system does not necessarily increase, but may decrease or increase if the system is in disequilibrium (difference in energy received from its active environment and energy escaping back to the active environment from the system. For the same system, if energy exchanges across its boundary equally in both directions, the system is said to be in “equilibrium” with respect to external energy exchange. One must be very careful in interpretation of the second law of thermodynamics! One has a very different “closed thermodynamic system” when it is in *energy exchange disequilibrium*, than when it is in *energy exchange equilibrium*. Equilibrium is the condition of maximum entropy. For substantial disequilibrium condition, entropy cannot be computed, but is less than the entropy of the same system in equilibrium. The entire ansatz of thermodynamics may be violated once time-energy is transduced into internal EM energy inside the system. That is a fundamental disequilibrium, performed by every charge in the universe. Hence of necessity we have advanced and utilized new definitions of “open system” and “closed system” in our approach in this book, as discussed in the Appendix.

If Serway's statement were reversed, it would then be a statement of the *law of negentropy*. It would state that self-ordering (i.e., freely receiving energy from the active environment) in a system could indeed "push heat uphill from a cold object to a hot one", and the system could simultaneously emit energy in the process. Every charge does it!

We did find it necessary to correct the classical thermodynamic definitions of "open system" and "closed system". To define a closed system as closed only to mass transfer, but open to energy transfer, is a gross non sequitur. Since general relativity was published in 1915, energy and mass are known to be the same thing (*mass is just a special form of energy*), hence the term "mass-energy" (mass as energy) in physics. Whenever energy crosses the boundary of a system, the system's mass changes and mass (or certainly mass change) has also crossed that boundary. Indeed, as we shall point out, in 1917 Hilbert specifically pointed out that in general relativity there can be no energy conservation equations of the kind usually employed elsewhere. The fact that general relativity falsifies much of the present foundations of classical thermodynamics seems to have been either ignored or missed by most of the scientific community, although we will quote leading Russian scientists who have noticed it and are aware of it.

The reader is thus warned that, henceforth, when we use "open system" we mean one where either energy or mass or both exchanges across the system boundary. When we use "closed system" we mean one in which *neither* energy nor mass exchanges across the boundary. In short, the notion of a "closed system" has been redefined into what classical thermodynamics calls an "isolated system". We already know from particle physics and the active vacuum (and from general relativity and the change of spacetime curvature with every change of spatial energy or mass-energy), and from the giant negentropy involving time energy transduced into 3-space energy and vice versa, that there is no such thing in all the universe as a truly closed system.

In Appendix A, we have discussed how extension and change to classical thermodynamics must be made. We do this by extending the first law, refuting any absoluteness of the second law and third law, dealing with the zeroth law in a new way, etc. We also urge the better theoreticians to re-examine classical thermodynamics along such lines, to modernize and upgrade it. We believe that the present scientific work to extend thermodynamics so it fits those situations now known to violate it should include additional considerations such as we present in Appendix A.

In short, with the new definitions Serway clearly states the difference between classical equilibrium thermodynamics, where no excess energy from the environment is received, and the thermodynamics of systems far from equilibrium with their active environment (using the new definition of open system for clarity), in which case excess net energy from the environment can be received and used in electromagnetic systems, providing COP>1.0 systems or even COP = ←systems. The windmill, sailboat, and waterwheel are age-old examples of disequilibrium systems where of course the energy of mass in motion is what is transduced. It is our objective in this book to point out the use of electromagnetic systems in energetic disequilibrium with their active environment (the active vacuum and curved spacetime) to provide just such negentropy.

1.1.3 Time Is Energy and Must Be Considered As Such

In a physics model, one's choice of fundamental units is arbitrary.[10] As an example, in one type of physics only a single fundamental unit — length — is employed. All other entities then become functions of length.

We are also free to choose the *joule* as the single fundamental unit in our physics model. The result that mass is a function of energy is now familiar and quite accepted, by the famous formula $E = mc^2$. Indeed, as can be seen, in that equation mass and energy are one and the same thing, since c^2 is a dimensionless constant. However, in our new model time becomes a function of energy similarly, and thus time is identically energy.

Let us perform a thought experiment. Suppose we take some spatial EM energy in 3-space, and compress it by the factor c^2. What can we do with it? If we leave it there in 3-space, it is known as "mass". If we place it on the fourth Minkowski axis *ict*, it is known as time because *t* is the only variable on that axis, and the only "place we can set it".

So to first order, *time has the same energy density as mass*. Multiplying an amount of time *t* (in seconds) by c^2 gives the decompressed spatial energy *E* that the time *t* will transduce into. In short, $E = tc^2$ also.

Now we notice what special relativity has to say about the relationship between time-energy and mass-energy. When the mass-energy increases

---

[10] E.g., see Jackson, *Classical Electrodynamics*, 2nd Edition, Wiley, 1975, p. 811-812; *ibid.*, 3rd Edition, 1998, p. 775. Jackson wryly remarks on how much excess heat and passion have been unnecessarily expended on that subject.

(e.g., as a function of velocity), time "dilates" or “decreases”. In other words (hint), there is a sort of special new extension to the conservation of energy law: If mass (3-space) gains some 3-spatial energy, then time loses some time-energy. Since time is spatial EM energy compacted by c^2, then *the relativistic energy changes in the time domain are enormously greater than the corresponding relativistic changes in spatial energy in the photon*. To the external 3-space observer, this is the injection of negentropy with respect to the present 3-spatial conservation of energy law. In the reverse case (as when the object reduces its velocity), if mass (3-space) loses some energy, then time gains some time because the time dilation reduces — i.e., time contracts or densifies (less time has more energy). To the observer, this is the production of entropy with regard to 3-space energy conservation. Yet the observer misses the fact that, accompanying entropy in 3-space is negentropy in time energy on the 4th Minkowski axis, and vice versa.

We believe this to be a rather dramatic extension to the previous concept of entropy in thermodynamics. We get 3-space entropy in physical processes only by gaining 4th dimensional negentropy accordingly. One can thus appreciate the impact upon the entire subject of thermodynamics, once time-energy is accounted and the new interplay of entropy and negentropy are accounted. We believe that this mechanism may involve the fundamental mechanism for both entropy and negentropy. Neither is produced alone; both are always produced in tandem. This of course is not what we “observe” since all observation is 3-spatial. Hence to observe the system and see 3-space entropy or negentropy is to hide the simultaneous 4th dimensional negentropy or entropy that unobservably accompanied the observable that we did see.

Again we call attention to the original meaning of entropy: the dissipation of potential (i.e., potential energy).

Once we understand that *time* is a special form of energy (we discuss this shortly), we may input the energy required to "move heat energy backwards" — i.e., we may directly engineer negentropy — by transducing some time-energy into 3-spatial energy. We can do it easily by time reversal, and every charge in the universe does it already. On the other hand, we can do it by breaking the symmetry of time-energy flow — which is as simple as forming a little dipole. The broken symmetry of unlike charges — and therefore the dipole — was discovered by Lee and Yang {13a-13c}, who strongly predicted it in 1956. Wu *et al.* {14} confirmed it experimentally in early 1957. This was such a revolutionary change to physics that Lee and Yang were awarded the Nobel Prize in the same year, 1957 — an almost unprecedented action.

Its broken symmetry tells us that the dipole's unlike charges continuously absorb virtual photon energy from the active vacuum, transduce it into real observable energy, and pour out real, observable EM energy in all directions in 3-space. That puts an entirely different perspective on *what really powers every dipolar EM circuit; i.e., what produces the flow of energy pouring from the terminals of every generator and battery, filling all space around the external circuit and its conductors*. The EM energy pouring from the generator or the battery is not due to the generator outputting some of its own available internal energy (from the shaft energy input to the generator, transduced into magnetic field energy inside the generator, and then dissipated to separate the charges and form the source dipole between the generator terminals) or the battery transducing and outputting some of its available chemical energy (which is only dissipated inside the battery to separate the internal charges and form the source dipole between the battery terminals). We will explain that later, and explain how any dipole or charge simply pours out real, observable energy continuously in all directions, without any *observable* input of energy. The input energy is there, but it is in *unobservable* (virtual) form.

In 1971 while a graduate student at the Georgia Institute of Technology, I realized the mechanism that generates the "passage of time" insofar as the observer is concerned {15}. With a little more work, this gave the clue in the 1990s for the mechanism generating little momentary *time-reversal zones* (TRZs) {16} in the electrolyte utilized in cold fusion experiments. Hence we proposed the use of little time-reversal zones forming momentarily in the electrolyte after loading of the palladium lattice of the electrodes with hydrogen or deuterium. Such time-reversal zones can form in the region of excessive positive charge accumulation, since positive charge can be said to receive negative EM energy from the time domain and output negative EM energy in 3-space.

This led to uncovering an entire class of new nuclear reactions — fusion reactions at low spatial energy but high temporal energy — in these little temporary time-reversal zones (TRZs), in which like charges attract and unlike charges repel {17}, followed by rapid decay of the TRZs where the normal law of attraction and repulsion is restored again.

In theory, a fermion cannot be time-reversed because the Pauli exclusion principle prohibits it. However, a boson can be time-reversed, so fermions can be time-reversed in pairs, where each pair acts as a *quasi*-boson. The

TRZ completely overcomes and *reverses* the "coulomb barrier" between a pair of like fermion charges.[11]

As an example, two deuterium ions in a little TRZ would momentarily form a quasi-nucleus of helium, since the two positive deuterons are attracted so closely that each enters the strong force region of the other. At the same time, the strong force is weakened by the partial time reversal of the gluon forces, so that the quarks are nearly freed. As the other ions in the surrounding solution then move to destroy the momentary time-reversal zone, their movement forces the TRZ to decay back to a time-forward zone — with the decay action starting from every point in spacetime inside the nucleons themselves[12]. The TRZ decay-induced action thus strikes the *nearly freed* quarks first, and decay can occur by easy quark flipping while the gluon forces are still much reduced and not back to normal strength. Hence as the gluon forces return toward normal, the quasi-nucleus decays by the strong force increasing and overpowering and drawing the quasi-nucleus into a full-blown helium ion — i.e., an alpha particle —flipping the partially-freed quarks as necessary to do so (that is not necessary in equation [1] below.

During decay of the TRZ, the weakened strong force grows much more rapidly than the Coulomb force zeroes and then increases. Consequently, the quasi-nucleus of two D+ ions merely draws together due to the rapidly increasing strong force, forming an alpha particle without quark flipping. Four H+ ions — four protons — in a quasi-nucleus in a TRZ will undergo quark flipping twice when the TRZ decays, thereby resulting in an alpha particle.). So that explained the anomalous formation of the alpha particles in the experiments. The interaction for two ions of deuterium is given by:

$$ {}^{2}H_{1}^{+} + {}^{2}H_{1}^{+} \Downarrow {}^{4}He_{2}^{++} \qquad [1] $$

---

[11] In a TRZ, the law of attraction and repulsion of charged particles is reversed.

[12] Any moment in time exists everywhere simultaneously throughout the universe. In short, time is a multiple connection in 3-space. Hence in any time-reversal zone (a TRZ) where time is reversed, then starts fading away and back to a time-forward zone (TRZ), the changes induced by the "fading back to TFZ" *simultaneously* involve every point in the 3-space of that TRZ that is changing (decaying). An easy change is quark flipping, since the quarks are almost freed in the TRZ to begin with. The reason the reaction proceeds in that direction is that the recovery of the strong force is much faster than the restoring of normal electrical repulsion, hence the quasi-nucleus is drawn further together into a full nucleus, constituting a legitimate nuclear transmutation at low spatial energy but high time-energy.

This interaction between two deuterons in solution does not occur in a normal time-forward zone because of the coulomb barrier preventing the two deuterons from entering each other's strong force region and acting as a quasi-nucleus of helium, so particle physicists have missed it. It does exist in a time-reversal zone; such zones form and then decay back into normal time-forward zones. This is possible because the coulomb barrier is momentarily reversed. The use of such TRZs in particle physics opens up thousands of new nuclear reactions, all at low *3-spatial* energy, but involving very high *time*-energy. Because of the extreme energy density of time, *these time-energy-induced reactions are actually much higher-energy reactions than high-energy physicists presently consider and utilize!* Indeed, it opens up a new kind of far more energetic "high energy physics".

Cold fusion experimenters have unwittingly opened a window upon a vast new particle physics, previously overlooked by our scientists because they have disregarded the use of time-energy, time reversal zones, and transmutation of time-energy into 3-spatial energy in their nuclear reactions. However, a few physical theorists attempting to better explain particle physics have recognized the importance of the time domain, and probing work in that respect is occasionally done {18}. In our view, it is not accidental that more than 600 successful cold fusion experiments have been obtained, by a variety of researchers in many labs in several nations. We strongly suggest that much of the conventional physics community has firmly placed its collective head in the sand, and is refusing to grapple with the startling new time-energy physics that is being initiated by cold fusion research.

In 1999 (published in 2000) {12} we finally discovered a great new symmetry in EM energy flow, whereby time-energy flow symmetry and 3-space energy flow symmetry are each individually broken, while an overlooked and more fundamental 4-symmetry energy flow — between the time-domain and 3-space — is sustained. *The result is that all EM energy in 3-space comes from the time domain locally and returns to the time domain locally, in a giant negentropic circulation.*[13] Together by the discovery of relevant quantum field theory work by Mandl and Shaw {19}, this now lends strong support to the use of time-energy in physics as a practical matter for strenuous investigation.

---

[13] This is also understandable from the implications of the observation process, which yields a frozen 3-space snapshot existing only at a single instant. Thus any 3-space energy existing there in that frozen instant, had to just come from 4-space (from the time-domain via the giant negentropy process, if we take the view that "the past exists only in time itself".). For the frozen snapshot to "change", time must be added to it, which converts it to a 4-space process again. So the "3-spatial" observed

As an example, Mandl and Shaw {19} treat the four polarizations of the photon. Neither the longitudinal nor the scalar photon is directly observable, but in the presence of charge the two are observable in combination, where they manifest as the "instantaneous" Coulomb (i.e., electrostatic) potential. This argument, translated from particle terminology to wave terminology, directly fits our re-interpretation {12} of Whittaker's 1903 decomposition of the scalar potential {85}. For the combining mechanism of the fields of the photons, we must account for *the field as a ubiquitously assumed interaction with the detecting/observing unit point charge*. Thus we must account for the absorption of the incoming time-polarized wave or photon, the transduction of that excitation energy of the charge into longitudinal EM wave/photon energy, and subsequent emission of that excitation energy in 3-space. That is what happens for a negative charge. For the positive charge, the process is time-reversed, hence occurs in opposite fashion. Or as an alternative, the positive charge can be said to continuously receive negative time-energy from the time domain and emit negative spatial EM energy.[14]

There is an *energy polarization transduction function* of charge, whereby it transforms received time-polarized photon energy into emitted longitudinal photon energy in 3-space (for the negative charge, and vice versa, for a time-reversed positive charge). This transduction appears to have been overlooked in physics prior to our recognition of it. It can in fact be used to generate an acceptable definition of charge itself. Charge is the

---

energy must come from an immediately previous 4-space process, and must return to an immediately following 4-space process.

[14] As we will find in our chapter on antigravity, there is good reason to treat the positive charge as a source of negative energy and negative energy fields. However, this is pertinent only prior to observation of the charge, while it is still a 4-spatial unobserved negative energy electron entity. For the observable charge, one has already conjugated — after all, the positron is observed as if it were an electron going backwards in time, which we observe as an electron with its charge reversed and with parity reversal (of its spatial direction). For the observable charge, we have already reversed the negative energy fields into positive energy fields by simply reversing their direction and the time associated with the photon (quantum of the EM field).

continuously active entity which performs that ongoing process or those ongoing processes of energy transduction between the time domain and 3-space (between the causal unobserved 4-space process and the observed 3space snapshot). Or in other words, it is an active process connecting 4-space cause and 3-space effect, and connecting the unobserved (such as virtual) to the observed (such as mass).

So for a dipole, the "causal" time-polarized EM wave or photon as a 4-space entity comes to the dipole[15] (3-spatial as observed) and is absorbed by the detecting negative charge or dipole, then is re-emitted as the longitudinally polarized EM wave or photon in 3-space. *That absorption and remission is what charge does, since it is an entity for performing that process*. The emitted energy in turn is absorbed by the nearby positive charge, retransduced into time-energy, and re-emitted back to the time domain. This ongoing very special 4-space energy circulation (even with a virtual charge in the vacuum) is what a scalar potential *identically is and is doing*, at every spatial point of itself, inducing vacuum polarization and "point dipoles" in the virtual state in the process. Recognition of these missing functions allowed at last a solution to the long-vexing problem of the source charge and its associated fields and their energy, often called the most difficult problem in both quantum and classical electrodynamics {68}. We discuss that solution later.

1.1.4 The Search for COP>1.0 Circuits and Systems

A very long search and much intense study and reflection eventually revealed the concepts and principles of those long-neglected disequilibrium Maxwellian systems that permissibly output more energy than the operator inputs. The active environment — not the operator — simply inputs the rest of the energy. Such disequilibrium systems are indeed permitted in Maxwell's theory {20}, and are also still prescribed by Heaviside's severe curtailment of it {21} into what is two vector equations with variables unseparated, rather than Maxwell's 20 equations in 20 variables.

---

[15] Prior to interaction of the incoming time-energy with the observable charge or dipole, it interacts with the virtual particles of the vacuum, generating vacuum polarization. Neither the virtual particles nor the time-energy are observable; only the effects of their conglomerate interactions with observable charges are observed. Hence one can take the particle view that virtual particle energy is continually absorbed, or one can also take a quantum field theory view that time-energy is continually absorbed. The two are always present in combination.

When Lorentz[16] symmetrically regauged the Maxwell-Heaviside equations, he arbitrarily discarded the entire class of Maxwellian systems that are far from equilibrium in their exchange with their active (vacuum) environment. Lorentz revised (symmetrically regauged) the Maxwell-Heaviside equations to make them amenable to separation of variables and closed analytical solutions, thus reducing the onerous chore of numerical methods. This Lorentz symmetrical regauging is given in most EM textbooks {22}, and we show it in Chapter 2. The symmetrically regauged Lorentz equations are not Maxwell's equations, nor are they the truncation of Maxwell's theory by Heaviside *et al*. Considering an active environment, under our altered thermodynamics definitions Lorentz implicitly selected and retained only the equilibrium class of Maxwellian systems, while *arbitrarily discarding* the entire disequilibrium class. He thus discarded all those Maxwellian systems permitted to produce COP lying in the range $1.0 <$ COP Ω←.

Maxwell's electrodynamics is a *material fluid flow theory* and it assumes a material ether. Anything that fluid systems can do, electrodynamics systems can do, at least in theory, because their mathematical models are the same form. So when one cites known examples of fluid-driven physical systems where the energy to run the system is freely furnished by the active environment, analogous electrodynamic systems in active environments — and in disequilibrium exchange with that environment — must also exist in nature. Indeed, particle physics requires it and proves it. These are the very systems arbitrarily discarded by Lorentz symmetrical regauging in every university.

So there exists a direct analogy between fluid systems and classical electromagnetic systems. The common windmill, waterwheel, and sailboat demonstrate by analogy that open EM systems far from equilibrium — powered by free EM "winds" and "energy flows" in the active vacuum environment — also exist in consonance with natural law. They are no more mysterious than a solar cell power system, which is after all a recognized "free energy" or "overunity" system, as is the humble charge (thought to be the source of all EM energy, fields, and potentials). In physics, the powering of systems by receipt and use of energy from their active environment leads directly to the thermodynamics of systems far from thermodynamic equilibrium in their energetic exchange with that active environment.

---

[16] Actually first accomplished by Ludwig Valentin Lorenz in 1867, then by H. A. Lorentz much later. Lorentz was given the credit erroneously. Lorenz actually derived electromagnetic theory independently in his paper. See J. D. Jackson and L. B. Okun, "Historical roots of gauge invariance," *Rev. Mod. Phys*, Vol. 73, July 2001, p. 663-680.

It follows that the seeming absence of such *electrodynamic* systems arises not because they are impossible but because present-day circuits and systems are ubiquitously designed to self-enforce an inherent energy equilibrium with their active vacuum environment. The closed-current loop circuit turned out to be the Lorentz self-regauging demon involved in destroying the COP>1.0 capabilities of every EM circuit. So little by little, we unraveled the long tedious trail of Maxwell's electrodynamics and what had happened to those missing Maxwellian-Heaviside systems far from equilibrium with the active vacuum.

We learned how, where, and by whom those permissible overunity Maxwellian systems were discarded. That is, we found what happened to all those Maxwellian *open disequilibrium systems* — originally included in Maxwell's and Heaviside's theories — where such a system receiving and using excess energy from its active environment[17] is permitted by the laws of physics, electrodynamics, and thermodynamics to:

---

[17] For the discerning reader, of necessity we have revised the foundations of the ancient classical thermodynamics, as further discussed in Appendix A. We refer the reader to Bimalendu N. Roy, *Fundamentals of Classical and Statistical Thermodynamics*, Wiley, New York, 2002, and to any good book on the history of thermodynamics. Also particularly good is Kondepudi and Prigogine, *Modern Thermodynamics: From Heat Engines to Dissipative Structures*, Wiley, Chichester, 1998, reprinted with corrections in 1999. The foundations of classical thermodynamics (and its fundamental definitions) were basically frozen prior to the advent of Maxwell's 1865 seminal theory, and well before the 1880s discovery (modeling) of the flow of EM force field energy through space. Some of the fundamental definitions of thermodynamics now will not withstand critical review in terms of "meshing" with the Heaviside/Poynting material fluid energy flow theory. Neither will they withstand the new concepts of energy such as mass-energy, time-energy and transduction between time-energy and spatial energy by every charge. E.g., thermodynamics defines an *open system* as one that exchanges energy and mass with its surroundings. Yet it defines a *closed system* as one closed only to mass exchange, not to energy exchange. *If the energy exchange is analogous to material energy flow and changes the mass of the system, then that definition of closed system is a non sequitur.* From general relativity, mass is simply energy anyway, and so "mass" exchanging across the boundary of the system is actually energy exchanging, and vice versa. Since Maxwell's theory is a *material fluid* theory, the Poynting and Heaviside energy flow models are *material fluid flow energy* models by analogy. The specialized thermodynamics definition of *closed system* rigorously will not logically allow the exchange of "material fluid energy flow" (or energy as matter)

since it prohibits matter flow, but the specialized definition of *open system* would and does. In short, with respect to material fluid energy flow, the concept of the “closed system” in thermodynamics has forced itself to become the *isolated system* instead, which is unacceptable since we must model EM energy flow exchange between the environment and the system. So we must change the thermodynamic definitions of *open system* and *closed system*. Else there cannot be any EM energy-mass or mass-energy flow between environment and system, which totally violates what is well known to be happening in all EM systems. In modern physics, every charge and every dipole already have such energy exchange with the active vacuum environment, and it is never zero; instead, it is of enormously high magnitude. Without that exchange, as we advance in this book, there cannot even be a “source charge” or associated EM fields and potentials and their energy, reaching across space. In other words, without it we can have no electrodynamics at all. So we have uncovered a fundamental and major contradiction between classical thermodynamics and general relativity, as well as between thermodynamics and the “material EM fluid energy flow” model used in electrodynamics. What classical thermodynamics calls a “closed system” permitting energy flow exchange, we must now logically regard as an *open* system because it is open to energy exchange across the boundary! The previous notion of the *isolated* system — with no exchange of either energy or mass — is what we must treat as a truly *closed system*. And there is none such in the universe, as we know in particle physics (e.g., because of the discovery of broken symmetry in 1957 and because of the well known active vacuum exchange with every EM charge and dipole). So we have corrected these direct contradictions between “EM as a material fluid energy flow theory” and the old classical thermodynamics.

As the reader will later see, this strongly affects our new definitions of *efficiency* and *coefficient of performance*. The new definitions we advance are rigorous, and they also apply to COP>1.0 EM systems, and even to self-powering (COP = ↔) EM systems. They also hold for very novel new energy processes such as quantum potential energy in a multiply connected space, multiple retroreflections and re-use of the same energy, conversion between time energy and spatial energy, and 4-space giant negentropy energy flow circulation.

But one can no longer be allowed to equate *efficiency* with *coefficient of performance*. Now they are never the same thing, just as a six-foot tall man and a six-foot tall doorway are never the same thing, even though they have the same height magnitude. We warn the reader that a great deal of thought and study must be put into appreciating these suddenly encountered changes to the quite old classical thermodynamics definitions. The changes are absolutely necessary. Bluntly put, in light of much more modern knowledge, a rigorous foundations analysis reveals the classical thermodynamics as well as disequilibrium thermodynamics to contain logical contradictions, such as its direct contradiction with general relativity and the EM material fluid energy flow theory. Either we give up or dramatically change the present EM energy flow theory, or we must make the necessary foundations changes to thermodynamics. We have chosen the latter option in this book, and the reader is forewarned of that dramatic change. The specific changes and rationale are discussed in Appendix A.

(1) self-order,

(2) self-oscillate or self-rotate,

(3) output more energy than the operator inputs (the excess being freely received from the active environment),

(4) power itself and its load simultaneously (all the energy being freely received from the active environment), and

(5) exhibit negentropy.

We vigorously pursued those long-lost Maxwellian systems, and we eventually found them. We also found real experiments {23, 24, 25, 26, 27, 28} and real devices {29a, 30, 31, 32, 33, 34, 35a, 36a, 36b} that performed one or more of those fabulous five functions, though there was often no realization by the experimenters, inventors, and scientists of the actual mechanism involved. Eventually my colleagues and I were also able to produce a successful experimental device {37, 38a-38c, 39}, the motionless electromagnetic generator (MEG), which outputs more energy than we input to it. We cover the MEG in Chapter 7. Presently a cooperative research program is ongoing with the National Materials Science Laboratory of the National Academy of Sciences of a friendly foreign nation, to develop and market commercial power systems based on successful laboratory experiments with the MEG. At this writing, we are also strongly seeking the extensive funding required to set up a physics lab and complete the final research allowing production of power systems.

1.1.5 Additional Very Important Implications

We also formally proposed {40} that the vast nondiverged EM energy flow component — Heaviside's "dark" nondiverged energy flow component, accompanying every reaction of a charge with a field or a potential, but arbitrarily discarded by Lorentz and modern classical electrodynamicists — is the generatrix for the extra gravity holding the arms of the spiral galaxies together, after all the dark matter is accounted.[18]

---

[18] Heaviside himself recognized the gravitational implications of his extra component of energy flow, which is in closed circular loops. Beneath the floorboards of his little garret apartment, years after his death, handwritten papers were found where Heaviside used this component for a unified EM approach to gravitation. See E. R. Laithwaite, "Oliver Heaviside – establishment shaker," *Electrical Review*, 211(16), Nov. 12, 1982, p. 44-45. Laithwaite felt that Heaviside's postulation that a flux of gravitational energy combines with the (**EΔH**) electromagnetic energy flux, could shake the foundations of physics. Quoting from Laithwaite: *"Heaviside had*

In addition, my close colleague Bedini and I have filed a patent application upon a very special process to "freeze-frame and lock-in" a disequilibrium Maxwellian system in its otherwise far-from-equilibrium state, so the apparent disequilibrium operation of the system can be maintained stably as a new equilibrium condition. This appears to be a method to produce and utilize what Kondepudi and Prigogine refer to as a *nonequilibrium stationary state*. This stabilization is necessary in order for such a system to maintain its COP>1.0 excitation and steadily output more energy than the operator inputs, or to steadily power itself and its load {41}.

We also found that COP>>1.0 EM systems (and some COP>1.0 systems) produce (as a function of the COP) a current of Dirac sea holes (positrons) *in the local vacuum environment itself*, from the output section back to the input section. At COP<1.0 and COP not too greatly above 1.0, a Dirac sea hole in the vacuum almost immediately interacts with an orbital electron in the material lattice of the system. This converts the negative energy, negative mass "vacuum hole or state" into a lattice hole, which is attached to the large positive mass of the ion left by the disappearance of the electron. This "lattice positron" type of problem has been known in semiconductor design for some decades. Normal EM circuits do not usually meet the phenomenon overtly because the semiconductor designers controlled it in the semiconductors themselves by use of appropriate donors and acceptors.

There is a great difference between the actions of Dirac sea holes in the vacuum prior to observation, and lattice holes in materials (after observation). So there is a great difference between the action of a “positron” on spacetime before its interaction with mass and observation, and its action on spacetime after it interacts with mass and is observed.

For COP>>1.0, significant phenomenology and novel effects occur because a substantial fraction of the Dirac sea holes (unobserved positrons) sweeping from output to input do not convert to lattice holes (observed and bound positrons) along the way. For substantial values of COP above 1.0, Bedini's invention (patent application filed by Bedini and the present

---

originally written the energy flow as $\mathbf{S} = (\mathbf{E}\Delta\mathbf{H}) + \mathbf{G}$*, where* $\mathbf{G}$ *is a circuital flux. Poynting had only written* $\mathbf{S} = (\mathbf{E}\Delta\mathbf{H})$*. Taking p to be the density of matter and* $\mathbf{e}$ *the intensity of a gravitational force, Heaviside found that the circuital flux G can be expressed as* $p\mathbf{u}$ *4* $c\mathbf{e}$*, where* $\mathbf{u}$ *represents the velocity of p and c is a constant.”*

author)[19] covers the master process for intercepting and transducing this appreciable flow of negative energy from the output section back to the input. Otherwise, that flow — if not intercepted and not converted — will "eat" extra input electrons from the power supply, thus acting as a novel "extra load" appearing in the input section. That extra load then draws additional current and power from the external power supply by electron-hole annihilation[20].

With the Bedini invention, the negative energy (unobserved positron) flow appearing at the input section is transduced into a flow of positive energy (a flow of electron current) from the input section back into the system. The process deliberately uses the "interaction and observation" process to phase conjugate the charge and reverse its direction of flow! In that case, the otherwise detrimental *negative* energy output back through the COP>1.0 system (which is nature's decay process for COP>1.0 interactions) is changed to a beneficial *positive* energy input within the system itself, freely received from the vacuum environment. This process is then used to close-loop the system for self-powering in a "locked" and stabilized disequilibrium condition — a nonequilibrium stationary state.

If we consider mass to be a special kind of positive energy state, then positive energy states represent curvatures of spacetime that are positive gravity. Negative energy states generate antigravity (the time-reversal of gravity).

---

[19] Bedini personally discovered and implemented the solution before the exact nature of either the problem or the solution was recognized! My contribution was to recognize the nature of the problem and the mechanism used in the solution. We also stress that, contrary to conventional treatment, all EM circuits do involve not only lattice holes in the conductors and components, but also Dirac sea holes in the local vacuum. That the Dirac sea is involved whenever there are EM fields is clearly shown by Felix Finster, "Definition of the Dirac Sea in the Presence of External Fields," *Adv. Theor. Math. Physics*, Vol. 2, 1998, p. 963-985.

[20] With a proper change in the curvature of local spacetime, pair annihilation can occur with no accompanying photon radiation. The condition is that the part of the curvature of spacetime representing the energy change of the otherwise emitted radiation, does not "relax" even though it is an "excited state". Rigorously, the emission of the radiation from pair annihilation occurs in two steps: (i) first the local spacetime is curved for and by the energy excitation, as a *static change* of the curvature, and (ii) then that curvature relaxes back to its former value, propagating that specific curvature in space, which is recognized as the radiation propagating in space. If the spacetime curvature excitation does not relax, there is no photon emission and propagation.

Before their interaction and observation, the Dirac sea hole (positron) currents — produced in natural COP>1.0 processes in the universe — are still negative energy electrons in 4-space. They are not 3-positrons until interaction with matter has occurred. These "negative energy electrons" generate negative energy EM fields, including both the Poynting energy flow component and the Heaviside nondiverged energy flow component. These negative energy EM fields appear to be *generating the antigravity* whose effects are seen in the distant parts of the universe. They produce far more powerful effects than the accounted electrogravitation effects in astrophysics, which only uses the gravitational effects of the very much smaller Poynting energy flow component. Also, astrophysicists do not use the "positron before observation," when it is still a negative energy electron with negative mass. The accumulation of the negative energy (Dirac holes) in space (in the surrounding vacuum) is connected with massive objects and violent processes, where very strong gradients are produced.[21] As a result, very large negative energy fields and potentials are produced. In turn, this results in cumulating antigravity. This cumulating and interacting antigravity appears to be the mechanism for the forces *accelerating* the expansion of the universe — rather than it decelerating as would be the case if the net gravity there were positive. In Chapter 8 we propose this explanation for the observed acceleration of the expanding universe — and the basis for the explanation can be and has been successfully demonstrated in a legitimate overunity EM circuit or system {42}. We offer this in honor of Heaviside, who first discovered the gravitational aspect of his huge nondiverged energy flow, but did not live to publish it. He also did not consider the Dirac sea prior to hole interaction with matter, as it was not yet formulated, so he had not yet recognized the way to produce and utilize the practical antigravity potential of his discovery.

1.1.6 A Scientific Dilemma

There would seem to be a sufficient abundance of techniques, devices, processes, and theoretical works to impel a crash project in the scientific community to develop successful overunity electrical power systems {43a-43d}. This would be especially appropriate at this time, since the escalating energy crisis now threatens to slow the world economy, and then eventually collapse it. At this writing, the MidEast has heated considerably, and appears headed for another MidEast war, with resulting severe interruptions of cheap oil supplies from the MidEast. Nonetheless, in spite of Russia having opened its oil field spigots to try to fill the need, a crisis in oil appears to be looming.

---

[21] Kondepudi and Prigogine, *ibid.*, p. 459 already point out that strong gradients produce situations that violate present thermodynamics. Research in these and other situations violating present thermodynamics is going forward under the caption of "extended thermodynamics" research. A discussion of the area is given by D. Jou, *Extended Irreversible Thermodynamics*, Springer-Verlag, New York, 1996.

So *why* does the U.S. scientific community still so adamantly oppose the very notion of Maxwellian systems freely extracting EM energy from the vacuum? Why is there no outcry pointing out what the hoary old Lorentz regauging really means in terms of equilibrium or disequilibrium of the regauged system with the active vacuum? The unequivocal participation of the vacuum in a continuous energy exchange with the charges and dipoles of every EM system has long been affirmed by particle physics. All the fields and potentials — and their energy — manipulated in any EM circuit come from the vacuum, as proven in particle physics for 45 years. Why have our electrical scientists not understood — from the broken symmetry of the vacuum exchange with the opposite charges of the source dipole between the charged terminals of every generator and battery — that *EM energy from the vacuum powers, and has always powered, every electrical power system and circuit ever built?* Why have the later rigorous broken symmetry findings of particle physics not been incorporated to update the ancient classical EM theory used to design and build electrical power systems, nearly a half-century after those broken symmetries were discovered and proven? Why do our classical electrodynamicists continue to assume that every charge and dipole in the universe is a perpetual motion machine, freely creating energy out of nothing and pouring it out across all space at the speed of light?

Therein lies one of the real problems of present science — its historical and continuing resistance to "out-of-the-box" thinking[22] and to research that overcomes conventional strictures. More than 40 years after the basis for the vacuum-energy powering of every dipolar system (and of every observable charge once its clustering virtual charges of opposite sign are accounted) was discovered and proven in particle physics, all our university electrical engineering departments continue to erroneously teach that the shaft energy input to the generator powers its external circuit. Internal EM energy in the generator, transduced from the input shaft energy, does not directly add a single watt to the external circuit. Instead, it only continually forces the generator's internal charges apart, to continually remake the source dipole, which then extracts energy from the vacuum and pours it out of the terminals, filling the space surrounding the conductors of the external system for the system to intercept and utilize some of the available external energy flow.

---

[22] "Out-of-the-box" thinking is a widely used concept among planners and program formulators, when conventional thinking will not suffice to solve a major problem with which they are struggling. Conventional thinking is considered "in the box" thinking, so by demanding out-of-the-box thinking, a problem demands an unconventional solution outside those normally proposed. In short, some new thoughts and concepts are required. Much lip service is given to the concept as a favored buzzword, but few proposed programs with truly "out of the box" approaches will be funded. In the energy field, none at all are funded that are truly "out of the box", whether or not that or similar phraseology is used.

Once the dipole is established, it will extract and transduce EM energy from the vacuum and pour it out in all directions at the speed of light, without ceasing. Else, the Nobel Committee should admit its grave error and revoke the Nobel Prize awarded to Lee and Yang. Real observable EM energy extracted and transduced from the vacuum's virtual energy is precisely what the "broken symmetry of the opposite charges" on the ends of the dipole *means*. Indeed, all the forces of nature are already considered as generated by the interaction of virtual particles with observed particles. Since force produces energy changes in the system affected, then it follows directly that energy changes are produced by the interaction of virtual particles with observable particles.

However, our power system engineers ubiquitously use the closed current loop circuit. This inane circuit self-enforces the Lorentz symmetrical regauging condition. It uses half the energy captured by the external circuit (from intercepting some of that "energy flowing around the circuit from the seething vacuum" that is copiously pouring out of the generator terminals) to ram the spent electrons back through the back emf of the source dipole itself. That scatters the dipole charges and kills the dipole and its broken symmetry — and also kills the free flow of transduced EM energy from the vacuum.

That insane circuit kills the source dipole in the generator faster than it powers its external loads! So one has to keep rotating the shaft of the generator, to keep producing a magnetic field inside the generator, so that this magnetic field energy can continue to force the charges back apart and continually reform the source dipole.

In short, our engineers build the equivalent of an electrical windmill, then — so to speak — force it into a closed barn so the environmental wind cannot reach it any longer. It is little wonder that we ourselves then have to do work on that "electrical windmill" to crank it around!

We pay the power company to engage in a giant wrestling match inside its own generator and *lose*. We also wildly pollute the planet with hydrocarbon and nuclear wastes, poison species (including killing of X numbers of humans every year via the disruption of their body functions and health), and enhance global warming. We are slowly strangling our biosphere and ourselves. None of that is necessary.

1.2 Organized Science Often Resists Innovative Change

The history of science is littered with examples where the scientific community has ignored the principle behind Einstein's statement quoted at the beginning of this chapter. As pointed out by Smith {44}, science has become reoriented toward profit. Quoting:

> *"...science is not the danger; scientists encouraged to do bad science to survive are." ... "...changing the way modern science is funded is an enormous undertaking, but it is a necessary one if we want to protect our future. Call it managed risk."*

Science's resistance to change is so well known to historians of science that it is rather universally accepted — although usually not made explicit to undergraduates. Further, scientists are under great pressure to conform:

1. After all, science is *patronized*; someone must fund the laboratories, the research supplies, the salaries and personnel benefits, etc.
2. To procure and protect its patronage, science has become quite organized, particularly with respect to how the funds — received and channeled down from the top — are cut into individual packages (research grants and research programs) and made available for competition among the "performing" chain of universities and research laboratories.
3. In the last few decades, there has risen an increasingly fierce demand by universities that the scientific researchers (i) be successful in attracting outside funds and (ii) file patents assigned to the university. So fierce has this demand become, that the research professor's continued livelihood may literally depend upon his or her success in bringing in extra funding. Further, much of his time is now spent in writing proposals to

compete for these "packaged funds". When he wins them, the kind of research and the areas of research are already stringently defined, and he dare not deviate — else there will shortly be no more funding packages won, no funding for his graduate students, and soon thereafter there will be no job of any importance for the professor!

4. In the United States, all the government National Laboratories and our universities are intensely seeking and filing patents! So small, independent inventors cannot deal with these organizations, without risking and almost guaranteeing the loss of their patents and intellectual property. Funding dangled in front of the inventor, much like a carrot dangled in front of a horse, is often tied to "march in" rights {45, 46} calling for surrender of the inventor's patent rights altogether, *whenever the government — i.e., a single bureaucrat — wants to take it*. All that has to be done is to declare that the inventor is not getting it developed and to market fast enough. Science has thus become more avaricious and — some inventors would even say — it increasingly involves overt and covert piracy of intellectual property rights. From personal experience, reluctantly I would not argue with that statement. Simply ask Larry Fullerton of Time Domain Corporation about his struggle with a National Laboratory over patent rights to his ultrawideband communications invention and technology.[23] It eventually resulted in a "draw" of sorts. He did not lose his rights, but the government gained them also, in competition with him. The government *circumvented* his patent, even though they did not succeed in taking it. We were delighted to recently see that Larry (the company is Time Domain, Inc.) received its 74th patent in this technology, as well as a ruling that will allow the technology to at last go to market.
5. The result is a dramatic increase in the pressure on working scientists and independent inventors to conform, and to "play the game by the rules". Then everybody up the scientific food chain is fed, and is happy and secure. The journals happily publish the research papers and results, the professor gets

---

[23] Stephen Fenichell, "Radio Flyer," *Discover*, 22(5), May 2001. Fullerton's technology has been given a limited go-ahead by the FCC, which has drafted standards and regulations in the area as of February 2002.

funding for his graduate students, the university gets that wonderful overhead cut of the research funding — such as half or it or more — and the entire apparatus is like a very large and tidy Titanic adhering to its ponderous course toward the iceberg. Meanwhile, truly new and innovative science discoveries — vulnerable and desperately needing nurturing funding during their initial embryonic state — get shoved aside, crushed, and starved in the funding rush to adhere to performance of the *prescribed* funding packages.

6. In this environment, the day of the "defenders of the scientific faith" has arrived! A small percentage of conventional scientists who are dogmatic and vociferous, are now very prominently attacking any novel experiments and ideas with a vehemence seldom seen in organized science. It is again reminiscent of some of the noted scientific attacks in history, e.g., as pointed out by Hellman {47}. Yet, because of the financial pressure upon the scientific community, and the increased pressures to conform, there is little restraint of the dogmatists and they are almost never called to task. Cold fusion is a current example. The American Physical Society has recently issued a statement condemning perpetual motion machines — yet the society's members continue to condone and use a classical EM model that assumes every charge in the universe to continuously be creating energy from nothing. Even the American Physical Society has not recognized what broken symmetry of opposite charges means with respect to the common dipole and dipolarity in every circuit. Nuclear reactions at low spatial energy (which means at extraordinarily high total energy when the c^2*-compressed* time energy is considered) do indeed sometimes occur in carefully controlled experiments, whether or not we yet sufficiently understand the reactions theoretically, and regardless of whether we can get the anomalous results to happen every time. Yet this area of nuclear interactions at low *spatial* energy {48} — and unknown to the scientific community, at very high *time* energy {49, 50, 51} — has been savaged by these self-appointed spokespersons for the "official" community, none of whom even account the compressed energy in the time increment portion of the photon. More than six hundred successful experiments in multiple laboratories, by respected scientists in multiple nations worldwide, are now

> rather resoundingly ignored. Yet the replication rate for good cold fusion experiments is certainly higher than many of the replication rates for novel and little-understood phenomena in large particle accelerators, and the cold fusion experiments are also *far cheaper*.[24] While particle accelerators are "popular" in their ability to garner huge funding, their cost/benefit ratio compared with, say, cold fusion experiments, may be abysmally low. Simply examine the decades of effort and many billions of dollars expended on the search for *warm* fusion (using spatial energy only). What has it produced, in terms of watts of power on the power lines? When will it produce any electrical power of any significance? Prototype cold fusion power systems have in fact been produced and patented {52}. With seed money from the scientific community and using a higher symmetry electrodynamics, cold fusion power could proceed at a rapid pace.

Strangely, the ever-present pressure to conform to *that which is already known and accepted* has often made science its own worst enemy throughout its history. Establishment scientists and the "system itself" now probably block — and have blocked over the decades — more innovative scientific research than does any other factor {53}.

1.2.1 Many Scientists and Historians Have Pointed It Out

The scientific community is well known to have always been highly resistant to novel ideas and innovations. Here are some selected pertinent comments regarding this phenomenon, where organized science is itself the obstacle to the advance of science, and where such has been recognized for many decades:

---

[24] As an example, see R. P. Taleyarkhan *et al.*, "Evidence for Nuclear Emissions During Acoustic Cavitation," *Science*, Vol. 295, 8 Mar. 2002, p. 1868-1873; Charles Seife, "'Bubble Fusion' Paper Generates a Tempest in a Beaker," *ibid.*, p. 1808-1809. See also Donald Kennedy, "To Publish or Not to Publish," *ibid.,* p. 1793. *Science* had the courage to publish the peer-reviewed results of a tabletop sonoluminescence experiment that apparently produces nuclear reactions. Editor Kennedy essentially advises all protagonists on both sides to cut the rhetoric and allow the scientific community to do its replication work, to either validate or refute the successful experiments of Taleyarkhan *et al*. This action by *Science* is a shining beacon to remind the scientific community that science is based on experimental method, and that prevailing theories cannot refute new experiments that contradict them. Instead, laboratory bench experiments must decide such an issue.

"Every great scientific truth goes through three stages. First, people say it conflicts with the Bible. Next they say it had been discovered before. Lastly they say they have always believed it." [Louis Agassiz, 1807-1873.]

"There are three steps in the history of a great discovery. First, its opponents say that the discoverer is crazy; later that he is sane but that his discovery is of no real importance; and last, that the discovery is important but everybody has known it right along." [Sigmund Freud].

"Anybody who has studied the history of science or worked as a scientist knows that whenever something novel is discovered or proposed, there is a polarization of scientists, with hostility and bitterness that may last for generations. What wins arguments is scientific fact, and that may change as the years go by. A good example of this is the geological theory of continental drift, as proposed by Wegener in 1912. When I studied geology around 1950, continental drift was acknowledged in my undergraduate textbook as a crank theory. The first serious confirmation was in 1956, and it was finally established as the dominant theory in the early 1970s. Until that time, anybody who admitted that he or she believed in continental drift was the subject of derision and scorn. Sorry, folks, science is not and has never been the 'idealized portrait painted in textbooks'." [Allan Blair] {54}

"... the four stages of response to any new and revolutionary development [are]: 1. It's crazy! 2. It may be possible — so what? 3. I said it was a good idea all along. 4. I thought of it first." [Arthur C. Clarke]. {55}

"...I suggest that most revolutions in science have taken place outside the lofty arena of the refereed journals, and with good reason. The philosophy by which these journals govern themselves virtually precludes publication of ideas that challenge an existing consensus." [William K. George] {56}

"At every crossway on the road that leads to the future, tradition has placed against each of us, 10 thousand men to guard the past." [Maeterlinck].

> *"An important scientific innovation rarely makes its way by gradually winning over and converting its opponents: it rarely happens that Saul becomes Paul. What does happen is that its opponents gradually die out, and that the growing generation is familiarized with the ideas from the beginning."* [Max Planck] {57}.

> *"Peer review is widely seen as a modern touchstone of truth. Scientists are roundly drubbed if they bypass it and 'go public' with their research… The first limitation of peer review is that nobody can say quite what it is… A more pernicious danger is that peer review may reject the important work. As Charles W. McCutchen, a physicist at the National Institutes of Health, has put it, peers on the panel reviewing a grant applicant 'profit by his success in drawing money into their collective field, and by his failure to do revolutionary research that would lower their own ranking in the profession. It is in their interest to approve expensive, pedestrian proposals.' "* [Jonathan Schlefer] {58}.

The sheer massive size and inertia of the modern scientific establishment also exert mind-numbing difficulty in "hearing" and recognizing an innovative scientist's message, even a message of utmost importance, and even if it gets through the censors. For example:

> *"We used to be able to say things once; if the message was reasonable, it had a good chance of becoming a permanent part of the structure of the field. Today, a single publication is lost; if we say it only once, it will be presumed that we have changed our mind, and we therefore must publish repeatedly. This further fuels the large publication volume that requires us to repeat."* [Rolf Landauer] {59}

1.2.2 Some Specific Examples

There are hundreds of examples of new discoveries in science that have at first — and often for an extended period of years — been severely obstructed and ridiculed. Here are just a selected few:

1.2.2.1 *Conservation of Energy*

Von Mayer {60}, the discoverer of the modern statement of the conservation of energy and the mechanical equivalent of heat, was severely chastised for his "insane" work. He was hounded and severely ridiculed. This extremely harsh treatment, together with domestic problems, drove him to a suicide attempt and a nervous breakdown, and into psychiatric treatment for some years. Toward the end of his life, his principle of energy conservation had so greatly increased the ease of calculations and the understanding of systems that the same scientific community — due to the commendable efforts of Helmholtz, Clausius, and Tyndall — began to recognize his great contributions and lionize him. In 1867, he was made a member of the nobility, dying in 1878 with his "insane" work by then well respected. He was fortunate to have the "cur dog attack" reversed in his lifetime. Most scientists with novel discoveries are not so fortunate.

1.2.2.2 *Continental Drift*

Alfred Wegener {61} proposed the theory of continental drift in 1912. The reception was extraordinarily hostile. So ferociously was he ridiculed for the notion that huge continents of rock could "float" and "drift" that his very name, "Wegener", was often used as a synonym for "utter idiot". To refer to someone as "a Wegener" was to cast the greatest slur possible upon that person's mental powers and to label him a gibbering lunatic. Only in the 1960s when sea-floor spreading from ocean ridges was discovered, proving that ocean basins are not permanent features, did Wegener's concept of continental drift concept finally gain acceptance.

1.2.2.3 *Kinetic Theory of Gases*

As pointed out by Paul Nahin {62}:

> *"J. J. Waterston's paper on the kinetic theory of gases, in 1845, was rejected by the Royal Society of London. One of the referees declared it to be 'nothing but nonsense, unfit even for reading before the Society.' ... "Waterston's dusty manuscript was finally exhumed from its archival tomb forty years later, because of the efforts of Lord Rayleigh..."*

Lord Rayleigh was the Secretary of the Royal Society when he had Waterston's paper reprinted nearly a half-century after submitted. Lord Rayleigh also gave an introduction to the paper, regretting it lying so long unpublished when its content was quite important. His introduction is a way of explaining the delay.[25]

---

[25] Waterston's paper was finally published as John James Waterston, "Free and Elastic Molecules," *Phil. Trans. Roy. Soc. Lond.*, Vol. 183, 1892, p.1-79. Lord

1.2.2.4 *Surgical Pain Deemed Necessary*

It has *always* been this way in science. As another example, the famed surgeon Alfred Velpeau wrote in 1839:

> *"The abolishment of pain in surgery is the chimera. It is absurd to go on seeking it today. 'Knife' and 'pain' are two words in surgery that must forever be associated in the consciousness of the patient. To this compulsory combination we shall have to adjust ourselves."* [Martin Gumpert] {63}.

Wryly we observe that today a similar attitude of "we must glory in the pain" — where the "pain" is due to the yoke of COP<1.0 EM systems and of the second law of classical equilibrium thermodynamics — consumes most modern electrical power system scientists and engineers.

1.2.2.5 *The Photoelectric Effect*

Almost every household now knows Albert Einstein's epochal achievements. Yet his formative three papers — on Brownian motion, the photoelectric effect, and special relativity — were published in 1905 while he was working in the Swiss Patent Office. The most renowned physicist of the time was Max Planck. Planck was embarrassed that a scientist who was not even employed in physics was doing such important work in physics. So Planck and other scientists arranged for Einstein to be awarded a chair in physics at a proper university. In their letter to the university, they pointed out Einstein's brilliance in his papers. They also then excused him for straying down the road of the photoelectric effect, because — as they put it — everybody knew that was foolishness, but persons of such brilliance could be forgiven a few such little bobbles along the way. Years later, in 1921, Einstein was awarded the Nobel Prize for Physics, for his work in theoretical physics and *especially* for his explanation of the photoelectric effect.

The Einstein incident is a typical illustration of Arthur C. Clarke's cogent observation:

> *"When a distinguished but elderly scientist states that something is possible he is almost certainly right. When he states that something is impossible he is very probably wrong*." [Clarke's First Law]

Rayleigh's introduction and Waterston's paper also are given in Jefferson Hane Weaver, *The World of Physics*, Simon and Schuster, New York, 1987, p. 632-651.

1.2.2.6 *Amorphous Semiconductors*

Stanford R. Ovshinsky's development of amorphous semiconductors {64, 65} is another modern example. "Everybody knew" that a crystalline structure was necessary in order to have a semiconductor at all; in short, a semiconductor formed out of non-crystalline material was deemed to be totally impossible, never mind this “phase” change that Ovshinsky advanced. However, some young graduate students, e.g., began to look at Ovshinsky's amorphous materials and his phase change approach.

Finally funded by the Japanese, Ovshinsky's company, Energy Conversion Devices, Inc. (ECD) simply placed its amorphous semiconductor devices into working equipment. Copy machines appeared with his amorphous semiconductors installed in them — with the machines and their amorphous semiconductors working very well. More graduate students and post-docs enthusiastically entered the area, did research, and wrote dissertations.

As a result, amorphous semiconductors finally became accepted, and they are now part of the established technology and scientific knowledge base. The interested reader can simply look up Ovshinsky's company and statistics on http://www.ovonics.com . The Japanese have reaped a continuing bonanza from the sales of amorphous semiconductors, because of the shortsightedness and bias of the U.S. scientific community.

1.3 Scientific Disagreement or Street Fight?

It is one thing to scientifically disagree — even strongly — in a technical and courteous fashion, and quite another to engage in ad hominem attacks. The first is science; the second is a cur dog fight. Unfortunately the history of science far too often reveals "cur dog fights" instead of respectful scientific disagreements {66}.

A recent modern example of legitimate research and qualified researchers still being savaged in a "cur dog fight" manner is cold fusion (low energy nuclear reactions). Quoting one learned orthodox scientist, whose name is withheld, speaking to a learned scientist in cold fusion:

> *“How stupid do you think we are? My assessment of you and your colleagues is that you are complete frauds or totally mad. There is no known physical principle that would support the kind of results that you claim your technology can accomplish, nor is there any credible argument why there should be such a principle."*

We answer that "cur dog attack" unemotionally and scientifically. The key is in the scientist's own phrase: "no *known* physical principle." If the experiments work and are replicated, but are not understood by the conventional theory, then they refute the prevailing theory, whether the physical principle is understood or not. Else scientific method has been totally abandoned in favor of “truth by authority and dogma”. The experiments clearly show that a previously *unknown* physical principle is at work. The real task then is to rediscover this new principle — that being one of the primary ways that science advances. We propose new principles in this book as a possible explanation of those experiments.

The dogmatic scientist's statement was made in spite of some two hundred (200 at that time; now more than 600) scientific experiments worldwide, in many nations, many at prestigious institutes, where dozens of scientists have reported positive and anomalous results in cold fusion experiments.

So yes, there is indeed a very "credible argument" — *the results and replicability of the experiments*, which are supposed to be the *decisive* statement of science. If that view in science has changed, then we are no longer practicing the scientific method. Instead of accepting successful and replicable experiments and seeking to change the model, the scientist is insisting that we must first understand the principle and thus have a model. This of course is a total violation and reversal of the scientific method. We used aspirin effectively for decades without the slightest notion as to the mechanism enabling its beneficial actions. The mere fact that "there is no known physical principle" for the results achieved has nothing to do with the validity of the replicated experimental results. Instead, it merely substantiates that *there should be a vigorous scientific program to uncover the new principle or principles obviously involved*, since the old model has either failed or been revealed as too limited.

The derogatory statement by the dogmatic scientist is also made from the viewpoint of the conventional nuclear physics model. The conventional physics has not taken into account that all 3-spatial electromagnetic energy associated with charges and dipoles and their fields and potentials in fact comes from the time domain {85, 86, 12, 19}. It has also not taken into account that time itself (as in the time component transported by the time-polarized photon or a time-polarized EM wave) may be comprised of extraordinarily dense energy. Indeed, time appears to be spatial EM energy compressed by the factor c^2, so it has the same energy density as mass {67}, which we pointed out earlier. The smaller the *spatial* energy of the photon, the greater its time component and hence its *time*-energy in seconds expressed in decompressed spatial energy joules[26]. The highest energy particle physics is not *spatial*-energy physics as presently practiced, but *time*-energy physics, where some of the time-energy of photons is transduced into spatial energy. One second of time transduced (decompressed) into spatial energy yields approximately $9\Delta10^{16}$ joules. Further, every negative charge in the universe continuously accomplishes that decompression, and every positive charge continuously accomplishes the recompression.

In other words, not all physical principles were discovered in the particle physics of, say, five years ago, as the literature since then clearly shows. To assume that everything is already known today is ludicrous; science is never completed. The new principles reported in the present book now are at least "candidates" for the physical principles that do support cold fusion results. There is also another powerful argument for these hypothesized principles: they have produced the final resolution of the source charge problem — something for which the arch skeptic quoted has no solution whatsoever, and which he himself cannot explain. *If the arch critic cannot produce an alternate solution to the source charge problem, and is unaware of that new principle that may solve it, let him go and learn the new principle. Until then, he unwittingly assumes that every charge in the universe is a perpetual motion machine, continuously creating and pouring out EM energy in all directions at the speed of light.* So we return his own argument and approach to him: he should attack the conventional scientific community for accepting the source charge, while having absolutely no principle to explain how it continuously pours out observable EM energy without any observable EM energy input. In short, he should practice what he preaches; else he brands himself a total hypocrite. The alert reader will note that none of the arch skeptics doing all the ad hominem attacks on cold fusion and COP>1.0 EM systems are practicing what they preach.

---

[26] The spatial energy of the photon decreases linearly as the frequency is lowered, while the time component in seconds increases linearly. But the highly compressed time energy, comprising that time component, increases nonlinearly (by the factor $c^2 \div t$). Hence the highest energy photons are actually the low frequency photons — something completely alien to particle physicists — and not the high frequency photons chased by "high energy physics". Indeed, high energy physicists are practicing a high spatial energy physics, which — overall — is a much lower energy physics than radar, microwave, VHF, or ELF, *if the total energy of the photon, to include its time energy, is considered.*

What we are saying is this:

(a) If one's physics knowledge was current five years ago, it may be stale today. A few years ago, no one believed the expanding universe was accelerating. Today we know that it is, rather unequivocally. And by "no known physical mechanism". We will later present a strong candidate for that missing mechanism. The results of experiments will substantiate or refute it.

(b) The proposed principles in this book, e.g., are newer, and may shed light on the mechanism for the cold fusion results as well as other phenomena. The experimental results themselves are irrevocable; any proposed explanation requires validation.

(c) The new principles do explain cold fusion and are consistent with the phenomena encountered in multiple experiments by multiple researchers in many laboratories. We readily admit that the stale and incomplete principles presently utilized in nuclear physics *do not* explain cold fusion. Neither do they explain how a charge continuously pours out EM energy. So do the skeptics attack all those physicists who believe in source charges and their provision of the fields and potentials and all EM energy? Of course not. They themselves believe in that greatest of all "perpetual motion" *faux pas*.

(d) The proposed new principles also solve the source charge problem, which is still ignored by most conventional physicists and electrodynamicists, even though often referred to as the "most difficult problem in electrodynamics" {68}.

(e) Scientists should not be close-minded, but should consider new proposals and let the experimental results decide their validity or falsity — precisely the position taken by the journal *Science* in publishing the results of some new cold fusion experiments. That is the scientific method in action.

(f) Those scientists who remain close-minded, and viciously attack experimentally demonstrated new processes and mechanisms, are guilty of practicing dogma and not science. They are in fact guilty of being what they so frequently charge: *pseudo-scientists*.

When science does not allow proposed new mechanisms and principles to be considered in science following demonstration of new phenomena inexplicable by present models, then science is no longer practicing scientific method. When any scientist rejects these demonstrated new experimental phenomena out-of-hand, he is practicing dogma rather than science. The "friendly skeptic" attitude is welcomed and appropriate. The cur dog attack has no place in science, but only among cur dogs — and those who behave like them.

1.4 A Few Significant and Unresolved Scientific Problems

1.4.1 Time as Structured Energy

Time also has internal structure and dynamics {69, 70}, as we explain later, as well as the same energy density as mass. So it should not be surprising that a tiny bit of time-energy, transduced into ordinary spatial EM energy, might be capable of energetically inducing a wide variety of nuclear reactions. One has transduced not only "gross" energy, but also energy structuring and dynamics — which *act internally* on any object with which interaction occurs. Further, the overall spatial energy component and the time-energy component in a photon are canonical. Being quanta, all observable photons have the same fixed "total magnitude" with respect to angular momentum. The photon is also "made" of $(\div E)(\div t)$ which may be taken as $(\div E)(c^2 \div t)$ in terms of *purely spatial* energy equivalent content, assuming that the time energy is decompressed into spatial energy. As can be seen, the so-called "low (spatial) energy" photons are precisely the photons that transport the greatest time-component. When that time-energy component $(\div t)$ is converted to spatial energy $(\div E_C)$, the formula is $(\div E_C) = c^2(\div t)$. As can be seen, the converted time energy will produce far more spatial energy in the *converted* interaction, than was carried by the photon in its spatial energy $(\div E)$ component prior to interaction and time-energy transduction. Hence the highest energy photons are actually low frequency photons — under the circumstances where time-energy transduction into spatial energy is involved. With transduction, the highest energy particle physics can be conducted at low frequencies and low spatial energy if conversion of time-energy occurs in the interaction.

Since cold fusion involves transduction of a little bit of the time-energy, the total lack in physics of knowledge of time-energy transduction into spatial energy explains why conventional nuclear physicists find the cold fusion results so confusing and astonishing.

1.4.2 The Obsolete Foundations of Classical Electrodynamics

Another modern example of science's resistance to change is the failure to update classical electrodynamics to include the active vacuum interaction and the interaction with the local curved spacetime[27], as we shall discuss in Chapter 2. It has been scientifically established (in particle physics) that there can be no equilibrium of any physical system without accounting for the vacuum interaction.[28] To simply observe a physical electrical power system sitting there stably and running, is to prove its vacuum interaction in order to even *have* such equilibrium.

An interesting point then arises since every charge and dipole in the system is a *broken equilibrium* in the exchange between the material system and the vacuum. Not only does an electrical circuit receive some energy from the vacuum, but also the energy from the vacuum is *massively hemorrhaging* from the vacuum into the system (and back out)! The isolated charge, e.g., is infinite if one removes the screening clustered virtual charges of opposite sign, as is well known in modern physics. Further, the screening virtual charges also have infinite charge, again as is well known. The difference between these two infinite values of charge, e.g., gives the standard finite observed charge of the charged particle. The lay reader may wish to positively verify that statement; e.g., as given by Nobelist Steven Weinberg.[29] Quoting:

> *"[The total energy of the atom] depends on the bare mass and bare charge of the electron, the mass and charge that appear in the equations of the theory before we start worrying about photon emissions and reabsorptions. But free electrons as well as electrons in atoms are always emitting and reabsorbing photons that affect the electron's mass and electric charge, and so the bare mass and charge are not the same as the measured electron mass and charge that are listed in tables of elementary particles. In fact, in order to account for the observed values (which of course are finite) of the mass and charge of the electron, the bare mass and charge must themselves be infinite. The total energy of the atom is thus the sum of two terms, both infinite: the bare energy that is infinite*

---

[27] We again stress the concept of the *supersystem*, introduced in footnote 11.

[28] E.g., see T. D. Lee, *Particle Physics and Introduction to Field Theory*, Harwood, New York, 1981. On p. 380-381, Lee shows how there is no symmetry of matter alone, but only of matter and vacuum.

[29] Steven Weinberg, *Dreams of a Final Theory*, Vintage Books, Random House, 1993, p. 109-110.].

> *because it depends on the infinite bare mass and charge, and the energy shift ... that is infinite because it receives contributions from virtual photons of unlimited energy."* [Steven Weinberg].

So a simple charged particle actually involves a polarization of the vacuum involving two charge energy functions — the bare charge and the charge change functions — each of which has a known and recognized COP = ←!

A priori, the conventional system's overall actions must incorporate functions (whether intentional or unintentional) that continuously adjust to provide *net equilibrium in that exchange by adjusting the hemorrhaging-out to equal the hemorrhaging-in*. In this book, we will spell out just what those unintentional functions are, such as the ubiquitous closed-current-loop circuit, and how to beat them so that excess energy from the vacuum can be utilized by the system to power the loads.

1.4.3 What Powers an EM Circuit or Electrical Power System?

Another modern example of science's resistance to change is the continued engineering of electrical power systems with the erroneous notion that mechanically powering the shaft of a generator directly powers the power line. The notion is that the generator transduces some of the mechanical shaft energy into output EM energy added to the power line {71}. To the contrary, *all EM systems are powered by energy extracted from the vacuum*. They are not powered by the mechanical energy we input to the shaft of a generator, or by the chemical energy in a battery. In this book, we discuss at some length what powers the EM system, and we have previously published the basis for our "shocking" statement {12, 72}. The basis for how an EM system is powered by energy from the vacuum has been known in particle physics for nearly a half-century {73}, since the experimental proof of broken symmetry {74}, including the broken symmetry of opposite charges (and hence of any dipole) in its fierce energy exchange with the active vacuum {75}.

A generator or battery expends all of its available energy to separate its internal charges and form its source dipole between the terminals. Once made, the dipole's broken symmetry — in its violent energy exchange with the active vacuum — converts virtual photon energy absorbed from the vacuum into observable EM energy, and emits it — *pours it out* — through the terminals and along the power line, filling all space around the conductors.

If one wishes to appreciate the enormity of the vacuum changes engendered by formation of that source dipole, simply visualize those two infinite charge energy functions (from Weinberg's quotation above) for every charged particle on the ends of that dipole. The dipole then is a great set of offsetting infinities in EM energy (photon energy) boiling and being ordered in the vacuum. Making a simple little dipole or producing a simple charge initiates into motion an enormous set of infinite energy changes in the vacuum! None of these startling, enormous vacuum energy changes and functions is modeled in classical electrodynamics and electrical power engineering. So when we speak of the Heaviside nondiverged energy flow component pouring from the terminals of a generator, as being a trillion or ten trillion times as great in magnitude as the intercepted Poynting component, the reader should not be appalled. The reader should recall that we are dealing with the difference between sets of infinities that combine to provide finite differences. These finite differences can be very small, or they can be extraordinarily large, depending on the exact situation. In the case of a source dipole formed in an ordinary generator or battery, the difference of the infinities is very large.

Figure 1, adapted from Kraus {76}, illustrates that small part of the external energy flow around a typical transmission line that is intercepted by the surface charges and their fields, and that is drawn into the wires to power the circuit as these charges are driven axially back and forth across the conductors. The surface charges are constrained to the "drift velocity" (usually a few inches per hour) movement down the wire by repulsion of the electrons ahead of them.

The spinning, *longitudinally restrained* electrons precess laterally, thus withdrawing across the transverse axis of the wire. So the laterally precessing electron withdraws a little ways, withdrawing that first small portion of its fields and their energy increased by intercept of additional energy from the outside energy flow. The further part of the fields is not withdrawn into the conductor, and is not used to power the electrons.


0.5
1
2
5
10
20
30
50
70
100
150
NONLOCAL FLOW. (The numbers represent the intensity of the Poynting component being withdrawn into the conductors.
Tiny "sheath" Poynting component strikes the surface charges and is diverged into conductors to power the circuit. Axial movement of the electrons draws in the energy density indicated by the numbered contours.
NONLOCAL (Nondivergent)
Contours are in watts/ sq meter.

Figure 1-1 Poynting (caught energy) flow contours surrounding a transmission line.

Most of the available energy flow misses the circuit and is not drawn into the conductors. However, that large component is not shown by Kraus, and Poynting did not consider it. Heaviside {5c} pointed out that the remaining flow component is hardly reduced (hardly changes direction) from the entire flow component before the extraction of the small Poynting component. Given sufficient intercepting charges outside the wires in separate receiving circuits, the total remaining energy flow that could potentially be intercepted is enormous — far more than the feeble amount of energy that is input to the generator shaft or that is in the chemical energy of a battery.

This is easily established by actual experiments placing intercepting charges in separate "receiving" circuits in the otherwise nondivergent energy flow outside the conductors, or one may show it with Bohren's experiment {24}. Collecting additional energy completely outside conductors is one part of the COP>1.0 operation of the motionless electromagnetic generator (MEG) {37}, to be discussed later in this book. The Sweet device {29a} established sustaining self-oscillation of the barium nuclei in a barium ferrite magnet, by using the surrounding vacuum as a semiconducting medium.[30]

1.4.4 The Incompleteness of Aristotelian Logic

Another false notion usually perpetuated in much of science and mathematics is that Aristotelian logic is complete and consistent {77, 78}. To the contrary, it is both incomplete and inconsistent, as is easily shown. Let us use the symbols "A" for a particular thing, "Ā" for that which is not-A, "∑" for "is identical to," "≢" for "is not identical to", "∨" for "or", and "∧" for "and". Using these symbols, the three laws of Aristotelian logic may be expressed as follows:

$$A \sum A \qquad [2]$$

$$A \not\equiv \bar{A} \qquad [3]$$

$$A \vee \bar{A} \qquad [4]$$

The first law states that a thing is identical to itself. The second states that a thing is not identical to that which is not itself. The third states that a thing is either itself, or it is something else. Those are the three laws of Aristotelian logic. As written, the process of perception, observation, etc. *has been excluded*. More on that in a moment.

Specifically excluded are the laws

$$A \not\equiv A;\ A \sum \bar{A};\ A \wedge \bar{A} \qquad [5]$$

Which says that a thing is not identical to itself but is identical to something else that is not itself.

Heraclitus posed a profound challenge to Aristotelian logic, a challenge that has not been adequately resolved by Aristotelians to date. He simply observed that, for a thing to change, it had to change into something else. "But then," he asked, "how can a thing be itself but also something else as well?" In philosophy that is still known as the unresolved "problem of change". It has no resolution in Aristotelian logic, but can be resolved in an extended logic we shall advance. The solution to Heraclitus' problem of change is the nature of observation, as advanced in this book.

---

[30] E.g., see Richard E. Prange and Peter Strance, "The Semiconducting Vacuum," *Am. J. Phys.,* 52(1), Jan. 1984, p. 19-21. The vacuum may be regarded as a semiconductor. In particular, the vacuum in the region close to the nucleus of a superheavy element is analogous to the inversion layer in a field effect transistor. The authors introduce the idea of the inverted vacuum. Just as a semiconductor may be manipulated by subjecting it to external fields, doping etc., it appears that so can be the vacuum.

We now critique Aristotelian logic, by observing a simple Venn diagram of the type used in "proving" logic theorems in axiomatic logic. See Figure 1-2.



1-2a. Usual Venn diagram of A and A.



1-2b. Applying second and third laws to divider.



1-2c. Applying second and third laws to divider and outer boundary.

Figure 1-2 **Applying Aristotle's laws to Venn diagram used to prove logic theorems destroys the entire diagram.**

In Figure 1-2 a, we have introduced a dividing boundary line between A and Ā. *Unfortunately that dividing line belongs entirely to both A and Ā.* So it violates all three Aristotelian laws, and must be removed.[31] Therefore, we remove it in Figure 1-2 b. Now we have neither a discernible A or a discernible Ā, but we have removed naught but the boundary separating them, so we may argue that they are both still there although not discernible. However, if they are not discernible, we cannot distinguish what A is or what Ā is, and so we cannot discern whether they are identical or not. Here again this violates all three laws of Aristotelian logic, so we have to remove the diagram. Indeed, the outer rectangle line is also such a boundary, between the "inside" and the "outside" (the not-inside), and so it must be removed. In compliance with Aristotle's laws, we are left with the trivial diagram shown in Figure 1-2 c, which is nothing at all.

---

[31] A clever fellow once proposed regarding the boundary as a total discontinuity, being neither A nor Ā. However, in that case A and Ā could never meet, so there could not be a cause interacting with not-cause to produce an effect. So that suggestion as to how to "fix" Aristotelian logic does not hold.

If this Venn diagram method is objected to, then we must insist that all those papers and texts using that method of proof of logic theorems be either abolished or corrected!

Sometimes the objection is raised that, as far as the center boundary line is concerned in Figure 1-2a, the line "belongs to A on the left and belongs to Ā on the right". Fine! Then we have a unique situation where a line (call it L) is an entity made of two entirely different things, which we may refer to as L_L and L_R. Yet $L \sum L$, without any qualifications as to "sides" L_L and L_R. It can be shown that every point in L is a point in L_L, and is simultaneously a point in L_R. The point in L is obviously identical to itself, by Aristotle's first law. Further, the same point in L_L and in L_R is identical to itself, by the same first law. But L_L is the set of all such points, and so is L_R, and so is L. Therefore $L \sum L_L \sum L_R$, since each one consists of each point that the others consist of. There is absolutely no distinction between the three things themselves, unless we are to violate Aristotle's laws.

Note that in passing from left to right across the boundary, a "change" occurs. This simply re-resurrects Heraclitus' original objection that, according to Aristotelian logic, there can be no change. That is, a line cannot change from "a different entity as seen from the left" compared to that entity as seen from the right. None of Aristotle's three laws contains a "left and a right" for A or Ā.

So the question of logic is a little more complex than writing three simple laws and drawing simplified Venn diagrams. In short, one cannot have Aristotelian logic without having something else *outside* it, which follows directly from Gödel's theorem and proof {78}. Note that we are introducing the required notion of "perception" into the formal notions implied as axioms in Aristotle's laws, as that "something outside the prescription of the laws themselves" and in addition to them. We are perfectly free to *use* Gödel's theorem and observation.



Figure 1-3 Mechanism for observation of change to a previous observation.

See Figure 1-3. We now add the notion that a thing is a perceived, thought, or observed thing. So let us use the symbol ⇒to mean *explicit*, i.e., *output* by a given perception, thought, or observation process as the result of a ∈/∈*t* operator having been applied to whatever exists prior to perception, thought, or observation. The symbol ⇔is used to mean *implicit*, e.g., when one observes an observation "Y" at time two, and later is deciding in time three whether or not that observation "Y" in time two is identical to a previous observation "X" made during time one, then *memories* of the observations of X and Y are involved in time three rather than the observations X and Y themselves, and so the observations of X at time one and Y at time two — by whatever manner they were observed and according to whatever decision algorithm is used — is said to be "implicit".

We note that we can know nothing about the so-called "thing in itself" *without* thought, perception, observation, or other process involving ∈/∈*t*. Further, at the moment the ∈/∈*t* operator is applied, time momentarily ceases. The resulting perception, thought, or observation exists therefore as a "frozen output" at that single moment in time. To have it "persist" or exist a moment later, we have to apply the ∈/∈*t* operator *again*, and stop time again, so that we again perceive, think, or observe.

But at any moment later than when we made a particular perception, thought, or observation of "A", *that* specific "perceived A" no longer exists, except in our memory as a recording of "observed A" that we can *continually recall*. Our conscious mind is a very fast serial processor, with only one "perception" or "thought" at each fleeting moment — only one slide at a time in the slide projector, so to speak. But it is very rapid. However, our so-called "unconscious" mind is totally conscious, just multiply so. It is a massively parallel processor, and has "a great many slides in the slide projector" at any given time.[32] Hence in our genetic multiprocessor mind, we can indeed record, recall, compare, etc. — and perform all the modern massively parallel computer operations.

Let us now re-examine the three Aristotelian laws. Let us label the "slide snapshots" with the time instants when each "perception, thought, or observation" is or was consciously made, by use of a subscript, such as $A_{1,}$ which means *what was perceived, thought, or observed as "A" in time-snapshot 1*. Let us also note that each of the symbols $\sum$, $\not\equiv$, $^\vee$, and $^\wedge$ actually involves the output of a *comparison and decision algorithm* in the massively parallel processor, after the two observations X_1 and X_2 were made. Let us use the symbol $\heartsuit$ to mean "results in the decision that" or "implies that". As a check for identity, e.g., simple comparison algorithms for determining identity or nonidentity might be

$$\{[A_1 - A_{(2)}] = [0]_3 \heartsuit_4 (A_1 \sum A_2) \qquad [6]$$

$$\{[A_1 - A_{(2)}] \prod [0]_3 \heartsuit_4 (A_1 \sum A_2) \qquad [7]$$

Thus we more precisely rewrite Aristotle's laws as

$$A_1 \sum_3 A_{(2)} \qquad [8]]$$

$$A_1 \not\equiv_3 \bar{A}_{(2)} \qquad [9]$$

---

[32] E.g., this can be seen by a moment's reflection. At any one time, the "unconscious" mind is controlling and directing a great multitude of ongoing physical processes, is also processing short-term and long-term memory processing, filing conflicts for resolution or later presentation to the conscious mind in symbolic fashion, etc. One can physically measure the electromagnetics associated with this activity, after the mind transduces its time-polarized EM interactions into 3-space EM actions. The process is two-way, and certain recorded EM stimuli will be "reverse-processed" back to affect the time-polarized EM operations of mind. Mind operations are electromagnetic; but they use time-polarized (scalar) photons and time-polarized (scalar) EM waves which are unobservable a priori. Mind operations are also electrodynamically engineerable, but that is beyond the scope of this treatise.

$$A_1 \curlyvee_3 \bar{A}_{(2)} \qquad [10]$$

Where — surprise! We have now accounted for all those different times and periods of observations, processing, comparison, decision, etc. We are dealing not with some mystical "thing-in-itself", but with interactions (perceptions, thoughts, observations, associations) in the mind and psyche of the observer. And hidden in time 3 is the application of a decision algorithm such as given in [6] and [7] above.

Now the first law [8] states that in time one an observation was made and named "A", notated (A_1), by comparing it to a previously recorded observational memory of what we call "A". The existence of that *memory* of what we call A is implicitly assumed in the first law, as well as the others. We do not show the memory itself in [8], [9], and [10]. In time two an observation X_2 was made (not notated), but it is not then known at the moment whether that X_2 is A or $\bar{A}$. So in time interval three the decision algorithm to determine identity or non-identity occurred in the mind, and the zero output of that algorithm [6, 7] established that $A_{(2)}$ was actually identical to A_1, *according to the decision algorithm actually used. The algorithm matters, and it too is a variable.*

A similar process occurs in law two [9], but this time the algorithm had a different output. Note that the little line over $X_{(2)}$ to make it $\bar{A}_{(2)}$ was not assigned until time interval four (not shown) after the decision algorithm had given its output in time interval three.

The second law merely states that the operation of the decision algorithm in time interval 3 found the two snapshots (in time 1 and in time 2) not to be identical, *by the decision algorithm and comparison process utilized. Again, the algorithm matters, and it too is a variable that must be taken into account.*

All three laws [8, 9, 10] written one after the other *assume* that the identity algorithm does not change between snapshot 1 and snapshot 2, in all three of them. This is the key point.

With two different versions of the identity decision algorithm, the results of two different comparisons may differ. If the identity decision algorithm does not change during the time between snapshot one and snapshot two, then we have one case. This is like a person with good color vision, looking at a red marble beside a black marble. That observer clearly distinguishes the marbles, and to him they do *not* appear identical. Every time he looks again, they still differ because he did not change his decision algorithm between looks. On the other hand, a color-blind observer cannot distinguish the marbles, and to him they are seen as identical. Every time he looks, they are seen as identical, because his identity decision algorithm did not change.

Or, suppose a proponent argues that the "rightness" or "leftness" of the dividing line L, between A and Ā in the Venn diagram, can be taken into account. He is actually invoking a different algorithm (it belongs to the left and therefore to A) in one time snapshot than the algorithm (it belongs to the right and therefore to Ā) used in the other time snapshot. So his right side and left side of a line implicitly invokes the very point we are making: *the algorithm utilized is a variable and must be accounted.*

The point is this: *identity — whether in perception, thought, or observation — is not absolute, but depends upon the precise nature of the operation of the perception, thought, or observation process utilized and specifically on the "decision algorithm" used for "determining" identity or nonidentity.* For example, two antennas certainly "see" quite differently, if one is a VLF (very low frequency) antenna and the other is an IR (infrared) antenna! As another example, two observers in different frames may see a particular object as quite different observed things! In n-space, an observer in a frame at right angles to the lab frame, will see any mass in the lab frame as a wavefront going at light speed; in short, as a photon or photonic object, whereas the observer in the lab frame will continue to see it as just a common old mass object. So the "same object" *physically* differs to the two different observers, according to their frame of reference. An observer whose frame is rotated by three orthogonal rotations from the lab frame, will see that object as an "object existing in time only," i.e., as simply a sort of "thought" image, so to speak. To be more scientific, he may assign it to something called the "virtual state".

In short, we can violate any and all of the laws of Aristotelian logic, because identity per se is *perceived, thought, or observed* identity — the output of a variable decision algorithm — and is not absolute.

For clarity, we add a fourth law that violates all Aristotle's three:

$$A_1 \sum_3 \bar{A}_{(2)} \qquad [11]$$

All this really says is that, in time 3, the decision algorithm being used was changed from what it had been in times 1 and 2, and now could not distinguish between what was seen in snapshot 1 and what was seen in snapshot 2, even though to some "ultimate" observer the two were distinctly different.

In addition, we say that it "implicitly includes" the negations of all three Aristotelian laws. We then add an "application rule" (or a fifth law, as one wishes) as follows:

$$\{\ [(A_1\ \Sigma_3\ A_2)\Rightarrow^{\wedge}\ (A_1\ \not\equiv_3\ A_2)]\Leftrightarrow\}_5\ \ {}^{\vee}\ \{\ [(A_1\ \Sigma_3\ A_2)\Leftrightarrow^{\wedge}$$

$$(A_1\ \not\equiv_3\ A_2)]\Rightarrow\}_5 \qquad [12]$$

This winds up producing an extension of Aristotle's logic, so that the following explicit laws emerge:

$$A_1\ \Sigma_3\ X_{(2)}\ \heartsuit\ \ A_1\ \Sigma_3\ A_{(2)} \qquad [13]]$$

$$A_1\ \not\equiv_3\ X_{(2)}\ \heartsuit\ \ A_1\ \not\equiv_3\ \bar{A}_{(2)} \qquad [14]$$

$$A_1\ {}^{\vee}{}_3\ \bar{A}_{(2)} \qquad [15]$$

We also have the exact opposites of those three laws implicitly. The opposites can all be congealed into a single fourth law:

$$A_1\ \Sigma_3\ \bar{A}_{(2)} \qquad [16]$$

To make sense of these, we also have the master application rule or 5th law:

$$\{\ [(A_1\ \Sigma_3\ A_2)\Rightarrow^{\wedge}\ (A_1\ \not\equiv_3\ A_2)]\Leftrightarrow\}_5\ \ {}^{\vee}\ \{\ [(A_1\ \Sigma_3\ A_2)\Leftrightarrow$$

$${}^{\wedge}\ (A_1\ \not\equiv_3\ A_2)]\Rightarrow\}_5 \qquad [17]$$

We prefer to refer to this extension as a "four-law logic", where equations [13], [14], and [15] are the normal "explicit" laws, with the implicit law [16] understood but not explicitly written, and where equation [17] is the master application rule that puts it all together. But if one wishes to be rigorous, we have specified a 5-law extended logic that contains but expands Aristotle's 3-law logic. The application rule is the fifth law.

The point is this: In every case, we have a part of the perception, thought, or observation that obeys the explicit laws, and we also have a part that obeys the implicit laws. If opposites are not *explicitly* identical, then they are simultaneously *implicitly* identical. If opposites are *explicitly* identical, then simultaneously they are also *implicitly* not identical.

The new approach then covers what we observe more completely. As an example, any "wave" (observed) is implicitly a non-wave (particle), but not observably so. If its particle nature is observed and therefore explicit, its wave nature is unobserved and therefore implicit, and vice versa.

One also resolves such dilemmas as stating something "does not exist" but having to first call it into existence to even state it does not exist. In the new approach, it simply does not *explicitly* exist, but *implicitly* exists. *Not-being* is something like that: explicitly it doesn't exist, but implicitly it exists. The great problems of the philosophers were never solved, mostly because the logic brought to bear was Aristotelian and incomplete. The ultimate answers they sought all involved the fourth and fifth logic laws. So the ultimate answers all appeared to them to involve such things as "the accursed necessity for the identity of opposites." Precisely!

In physics, there has been the same problem over whether a fundamental particle is a particle or a wave. Physicists argued fiercely until they realized the futility of further argument, and settled for the duality principle. That simply states, well, in one case it can be a particle as observed in your experiments, and in another case it can be a wave as observed. So simply treat it as whichever one is useful! The philosophers, on the other hand, split into different schools, where each school had its "interpretation" usually involving a very "smooth" position statement of the school's position. In physics also, there are eight or more "interpretations" of quantum mechanics, for example. So the same centuries-old problem is still with us today in modern physics.

Opposites are no longer the formidable opponents they once seemed. Instead, they become more like the two sides of a coin, lying with only one side up. To see heads or tails is to decide which is explicit. The other is always there, implicitly. But notice also that the "two sides" require a 3-dimensional object, and not just the 2-dimensional "head" or the 2-dimensional "tail". This juxtaposition of "identical" opposites is strongly met with in modern physics. For example, quoting Lee[33] :

---

[33] T. D. Lee, "Space Inversion, Time Reversal and Particle-Antiparticle Conjugation," *Physics Today*, 19(3), Mar. 1966, p. 23. Positive charge is really *observation* imposed on negative charge moving backwards in time, and the positron is really observation imposed upon an electron traveling backwards in time, etc.

> *"As we expand our observation, we extend our concepts. Thus the simple symmetries that once seemed self-evident are no longer taken for granted. Out of studies of different kinds of interactions we are learning that symmetry in nature is some complex mixture of changing plus into minus, running time backward and turning things inside out."*

Any addition to the Aristotelian laws of logic is actually a higher dimensional form of it. Three-law Aristotelian logic is in fact fitted to primitive observation — the result or output of single-photon interaction and observation processes.

This "four-law" logic (or "five-law" logic if one includes the master application rule as another "law") has proven very useful over the years, particularly in bioenergetics applications. It has also been most useful in attempting to decipher that branch of Russian energetics weapon science called "psychoenergetics", and in attempting to decipher the mind-body coupling mechanism, but that is beyond the scope of this chapter {79}.[34]

1.4.5 Substitution of Effect for Cause

Refer to Figure 1-3 again, to see the relationship of the unobserved cause, the interaction of cause and a previous effect, and the production of the resulting "new effect" as a change to the old effect or the output of a second replica of it. The greatest non sequitur in electrodynamics — and in parts of physics such as mechanics — is the widespread substitution of the *effect* for the *cause,* as a result of considering an observable to *persist in time* without any physical interaction. We discuss that more fully in Chapter 2, particularly with respect the notion of the same EM field existing both as a component of a material environment and as a component of a nonmaterial environment, but with the "force reducing to zero" in the latter. Jackson {80} points out the prevailing view of electrodynamicists as follows:

> *"Most classical electrodynamicists continue to adhere to the notion that the EM force field exists as such in the vacuum, but do admit that physically measurable*

---

[34] The interested reader is referred to my website, www.cheniere.org, for papers dealing with the nature of the mind-body coupling mechanism and the body-mind coupling mechanism, as well as direct engineering of the mind, and limited information on the weapons referred to.

> *quantities such as force somehow involve the product of charge and field."*

On the other hand, Bunge {81} very clearly stated that the standard electrodynamics and physics itself are in terrible shape. Here is a direct quotation:

> *"... the best modern physicist is the one who acknowledges that neither classical nor quantum physics are cut and dried, both being full of holes and in need of a vigorous overhauling not only to better cover their own domains but also to join smoothly so as to produce a coherent picture of the various levels of physical reality."*

We shall try to further clarify these unresolved difficulties with the field concept in Chapter 2.

1.5 Electrodynamics is Still Developing

1.5.1 Statement by Penrose

Roger Penrose, one of the leading physicists of our time, pointed out the still-developing nature of electrodynamics with respect to the developments from conventional gauge-theoretic interpretation of Maxwell's equations. Quoting Penrose {82}:

> *"These facts should not, however, deter theoretical or experimental physicists from seeking alternative descriptions, unconventional formulations, surprising electromagnetic effects, or radical generalizations. The various articles in this book provide the reader with a great variety of different kinds of approach to developments of this nature. We have historically motivated accounts, suggestions for new experiments, unconventional viewpoints and attempts at generalizations. We also see novel and ingenious formulations of electromagnetic theory of various different kinds... I am sure that this book will make it clear that electromagnetism is a subject that is in no way closed to stimulating new developments. It is very much alive as a source of fruitful new ideas."*

1.5.2 An Example of a Ubiquitous Error

One of the rather horrid "bad examples" of ubiquitous errors in electrodynamics is the conventional illustration of a so-called planar EM wavefront moving through space, as shown in Figure 1-4.

A succinct evaluation of that diagram and notion is given by Evans {83}, one of the great electrodynamic theoreticians of our times:

> *"I broadly agree ... that the transverse plane wave view of vacuum electrodynamics is the biggest blunder of twentieth century science."*



Figure 1-4 The erroneous but ubiquitous supposed illustration of the transverse EM wave in 3-space.

Dr. Robert H. Romer, former Editor of the *American Journal of Physics*, also chastised the horrid diagram shown in Figure 1-4, purporting to illustrate the transverse plane wave traveling through 3-space. In endnote 24 of his noteworthy editorial, Dr. Romer {84} takes that diagram to task as follows:

> *"...that dreadful diagram purporting to show the electric and magnetic fields of a plane wave, as a function of position (and/or time?) that besmirch the pages of almost every introductory book. ...it is a horrible diagram. 'Misleading' would be too kind a word; 'wrong' is more accurate." "...perhaps then, for historical interest, [we*

> *should] find out how that diagram came to contaminate our literature in the first place."*

Indeed, each point along the z-axis, is a momentary "3-space frozen slice" of the $\in/\in t$ operator being applied to the ongoing 4-space interaction of the causal field in 4-space interacting with the previous "observed effect" (in this case, the previous 3-space slice) to produce a change to it. So the entire diagram is a set of "frozen 3-space observations", in which nothing at all is moving, and where the fields shown are in the mass (detecting/observing) medium. There is no such thing as a "traveling EM wave in 3-space", because "moving" or "changing" or "traveling" *a priori* must involve time as well as 3-space. What we are looking at in Figure 1-4 is the iterative and very rapid results of continual "3-space observations" (frozen 3-snapshots) of an on-going 4-space interaction.

1.5.3 An Extremely Important EM Omission

There is an enormous amount of development yet to be done in electrodynamics! As a simple example, for nearly a century there has been waiting quietly a fundamental "internal" or "infolded" electrodynamics by Whittaker {85, 91a, 86}, based on more primitive initial work by Stoney {87}, existing inside — and *comprising* — all conventional EM potentials, fields, and waves. This internal electrodynamics {88} has been essentially ignored in the West, but has already been weaponized in the weapons laboratories of several nations under the aegis of *energetics*. The U.S. Secretary of Defense, Secretary Cohen {89}, alluded directly to some of these weapons in a speech in 1997 as follows:

> *"Others [terrorists] are engaging even in an eco-type of terrorism whereby they can alter the climate, set off earthquakes, volcanoes remotely through the use of electromagnetic waves... So there are plenty of ingenious minds out there that are at work finding ways in which they can wreak terror upon other nations...It's real, and that's the reason why we have to intensify our [counterterrorism] efforts."*

The weapons are already being utilized against various nations in the form of terrorist acts in an undeclared war {89}, and have been so used since the 1950s.

This internal longitudinal-wave EM and its dynamics is a much more fundamental electrodynamics (actually a subset of a unified field theory) consisting of correlated longitudinal EM wavepairs in both the 3-space and time domains. Each Whittaker decomposition wavepair is comprised of an incoming longitudinal wave — a "time-polarized" EM wave {90a-90c} — in the time domain, perfectly correlated with an emitted longitudinal EM wave in 3-space. See Figure 1-5. This multiwave structuring and dynamics in both the time domain and in 3-space simultaneously *comprises* the scalar potential.



The Structure Is:

- A harmonic set of longitudinal phase conjugate wavepairs.
- In each wavepair the two waves superpose spatially after detection, but travel in opposite directions.
- Prior to detection, the convergent wave set is in the imaginary plane, and hence is not observable. It is EM energy incoming to the potential (dipolarity) from the time domain.
- The charges receive the complex convergent EM energy, transduce it into real EM energy, and emit enormous energy at the speed of light in all directions -- which includes bidirectional pairs in 3-space (after the reaction, being after "observation").
- This produces the fields and potentials from the "source charge or dipole."
- Mandl and Shaw argue that the scalar (time-polarized) photon and longitudinal photon are observable only in similar pairs, which then makes the instantaneous scalar potential. Thus quantum field theory work strongly supports the "negative resistor" interpretation of the scalar potential and our solution to the source charge and source dipole problem.

Figure 1-5 The scalar potential is a harmonic set of phase conjugate longitudinal EM wavepairs.

We specifically stress that the dynamics occur in the *time* domain (in its specific structuring, propagation pace, etc.) as well as in 3-space.

Deliberately changing the internal longitudinal EM wave structuring produces precise energetics (both energy and dynamics) in spacetime itself. This is a special form of "spacetime curvature structure and dynamics" which we call a *spacetime curvature engine* or *vacuum engine*. Together with superpotential theory in the original form initiated by Whittaker {91a} and extended by others {91b, 91c, 91d}, this internal electrodynamics — together with scalar potential interferometry {92} — creates all ordinary EM fields and waves {79}. Superluminal communication is possible using the internal longitudinal EM wave structure of the EM fields, potentials, and waves {93a, 93b}.

1.6 A Summarizing Letter

Our thrust in this book is to attempt to (1) reveal some of the major flaws in electrodynamics that have prevented development and use of COP>1.0 electrical power systems, and (2) point the way toward the development and use of such systems. To give a general summary of the ground this book will cover, we conclude with an informal E-mail letter I sent to the recent editor of *American Journal of Physics*, pointing out the greater implications of his cogent observation of that "dreadful diagram" and where it leads. Indeed, it (i) leads to a dramatic change in electrodynamics, (ii) changes the way in which we regard "propagation of EM energy through 3-space", (iii) solves the long-vexing problem of the association of the source charge or source dipole with its fields and potentials and their energy, (iv) changes dramatically the way we view what powers an electromagnetic circuit or power line, (v) allows extraction and use of copious EM energy from the vacuum, and (vi) solves the energy crisis permanently.

Here is the letter sent informally to Dr. Robert H. Romer — *slightly edited* to improve the grammar, correct one error of misstatement, and with reference citations added and listed at the end of this chapter:

To: Dr. Robert H. Romer Thursday, Mar. 8, 2001
American Journal of Physics
Amherst College, Box 2262
Amherst, MA 01002

Personal communication

Subject: Implications of your cogent comments on that atrocious illustration

Dear Dr. Romer:

This is not a submission of a manuscript, but a personal communication to you on a matter of great importance in physics, directly related to endnote #24 of your seminal editorial {94}.

It will take a little exposition, so please bear with me and read this when you have the spare time to do so. We are going to show you how your keen insight can be extended to solve some extraordinarily formidable foundations problems in present electrodynamics. We will also show how to apply the implications of your insight to totally solve the present electrical energy crisis permanently.

In your endnote #24, {94} you took to task (quoting):

> *"...that dreadful diagram purporting to show the electric and magnetic fields of a plane wave, as a function of position (and/or time?) that besmirch the pages of almost every introductory book. ...it is a horrible diagram. 'Misleading' would be too kind a word; 'wrong' is more accurate." "...perhaps then, for historical interest, [we should] find out how that diagram came to contaminate our literature in the first place."*

Dr. Romer, you have lifted the corner of a dark cover concealing one of the most important flaws in electrodynamics and in fact in all of physics: the unwitting and pervasive substitution of the effect for the cause. A marvelous extension to the present physics is enabled if one removes this terrible non sequitur in physics, and particularly in electrodynamics. For openers, one solves what has been called the most difficult problem in electrodynamics (the problem of the source charge and the association of its fields and potentials and their energy) {100}. I will solve that problem for you in this informal write-up. I will also explain how to extract enormous EM energy from the vacuum, anywhere and anytime, easily. Extracting it is easy; catching it and using it to power loads without killing the extraction process is another matter.

One also gets a unified field theory, engineerable by novel electrodynamic means, as is steadily being shown by a series of rigorous Alpha Foundation's Institute for Advanced Study (AIAS) papers published in various leading journals (and more than 90 of them carried on a Department of Energy website restricted primarily to DoE scientists). Dr. Myron Evans, Director of the AIAS, has over 600 papers published in the literature, including such journals as *Physical Review*, *Foundations of Physics*, *Physica Scripta*, etc. Many of the other AIAS co-authors are excellent theoreticians and scientists.

The early pioneers of electrodynamics (Maxwell etc.) all assumed a material ether filling all space {95}. To these early scientists, there was not a single point in the entire universe that was devoid of matter, because the ether was present there. Hence their outlook as to the nature of EM fields etc. was quite material. Faraday conceived his "lines of force" as physical, taut strings, so that perturbations were "plucking these taut strings".

Maxwell himself points out in his famous "Treatise" that he specifically captured the thinking of Faraday in his theory. In fact, Maxwell wrote a *material fluid flow dynamics* theory.

In the light of more modern knowledge, let us see the impact of these and similar early *but still retained* erroneous electrodynamics assumptions.

First, observation/detection is totally spatial, as is well known in quantum mechanics. In fact, observation is a $\in/\in t$ operator imposed upon 4-space (LLLT spacetime), yielding a frozen instantaneous snapshot LLL of an ongoing 4-space dynamic process. At the next instant, that particular *previous* observation no longer persists. Why?

Well, no observable *persists*, since it is only an instant frozen 3-space snapshot, at a single point in time, *a priori.* Here again we have another horrendous non sequitur in all of physics: the assumption that observables "continue to exist" and therefore persist in time in a passive manner. In fact, there is an interactive process that generates their (seeming) persistence, involves time, and continually changes mass into masstime and back to mass, etc. With the reader's permission, we will pass discussing that mechanism until another time (pun intended!).

What we conceive as "an observable such as mass, traveling through space and persisting in time while doing so", is actually an iterative, continual series of these frozen 3-space snapshots or observations, much like the frames of a motion picture film. We ourselves mentally add the "continuity" to provide "the sensed motion", but rigorously what is actually "observed" is not continuous, but is a vast continual series of those frozen 3-space snapshots.

We're getting directly at that atrocious diagram!

Each snapshot is an *effect*, not a cause, because it was the output of the observation process whereby a 4-space *causal* entity (non observed *a priori*) interacts with a previously observed frozen entity (say, a unit point charge at some point in space) to produce the observation (change or effect generated in that interacting observed charge) as the "next instantaneous observation".

The usual "representation" of a "3-space EM wave" propagating in 3-space is indeed atrocious, just as you stated! It is actually just an iterative succession of such instantaneously frozen snapshots in 3-space, one after the other. There is no such thing as that set of snapshots independently existing in spacetime, *prior to interaction with charge* in that series of interactions and observations, unless we wish to discard quantum mechanics and the laws of logic.

There is, however, a continual iterative stream of those observations — those frozen 3-space snapshots — that we interpret (erroneously) by recall from memory as the "EM wavefront propagating in 3-space". As you eloquently pointed out, that is not so, and it is atrocious. An observation, being an absolutely frozen entity, cannot "move through time" anyway, since it cannot persist, nor can it move. A change to an observable can only be another observable snapshot of the ongoing 4-space entity and action, which is then compared to the first snapshot and a difference noted {96} [See Figure 1-3].

In short, a great stream of "frozen effects" (frozen instant observations) does not constitute a "picture" of the ongoing 4-space action, but only a series of frozen 3-space intersections involving the interaction of that fixed observed (3-space) charge with the ongoing causal 4-space entity. If we add and integrate a series of 3-space pieces, we *do not* get a 4-space entity! Instead, we get a longer or bigger 3-space slice/piece, but one for which each piece of it only existed at a single point in time as a 3-space "slice" at that moment. That is precisely what is wrong with that horrible illustration.

But it is also "wrong" with electrodynamics itself! Electrodynamicists mistakenly conclude that the same *effect* "series of static 3-slices" — which they might call, e.g., the "field" in a case where the field is the subject — is the same as the 4-space continuous *causal* field prior to observation interaction with charge at all. Well, LLLT is definitely not LLL, nor is it n(LLL) where n is some large but finite number of 3-slices LLL.

So the field concept is dichotomously used in two contradictory manners in electrodynamics:

(1) it is considered to be in 4-space prior to the observing/detecting interaction with the observable (such as a unit point 3-space charge), and it is also considered a 3-space entity *after* that interaction. The dimensions of the two entities are not the same, and neither are the dynamics. The causal EM wave is dynamic and 4-spatial, the effect "3-space EM wave" (ugh!) is static and 3-spatial at each instant it is "observed". Assuming that the two are the same thing is a non sequitur.

In fact, it substitutes the *effect* for the *cause*, a rather gross violation of the causality principle itself.

(2) then an attempt at glossing over the illogic is used by the smooth statement that "the field (meaning that atrocious series of frozen 3-space snapshots) remains in the absence of charge, but the force goes to zero." Well, if the field is defined as a force field, it cannot be a "non-force field in the same observation!" Else, opposites are always identical.

So of what importance is all that?

It is of great importance. Let me show you one very startling thing that comes out of correcting this "biggest foundations non sequitur in physics, that of substituting the effect for the cause".

Consider a very special paper by E. T. Whittaker {97} in 1903. [I can send you a pdf file of the paper if you do not have it and are interested]. In this much-neglected paper, Whittaker decomposed the so-called "static" potential into a harmonic set of bidirectional longitudinal EM wavepairs, where each pair consists of a longitudinal 3-space wave (an *as-observed* wave) and its longitudinal phase conjugate wave (*considered unwittingly as having also interacted with charge, and therefore as being shifted into 3-space as an "as-observed" wave with inverse parity*).

Whittaker — as has everyone since him — unwittingly assumed the "iterative continual observation" interaction in there for the phase conjugate wave also. In so doing, he came up with two *effect* "waves" that are the outputs of the assumed observation process. Neither of these effect waves would be a wave in spacetime {98} at all, but the two in ensemble are an example of the same thing you objected to in your cogent commentary on that abominable "illustration".

In short, Whittaker invoked *observation* as a process with two effects and no cause, rather than with a cause and an effect, with the interaction with the observing/interacting unit point charge being assumed for both waves. Whittaker and everyone since seem to have made the same error in interpreting that seminal Whittaker decomposition. This misinterpretation of the decomposition has until now hidden one of the greatest secrets of all times in Nature's electrodynamics!

Let us correct the interpretation, and uproot that great secret to the light of day.

First, for observation to occur, one must have a cause acting upon the affected (observable) entity, and an effect (observable change) must be produced in, on, or of that affected (interacting) entity. One *must not* have two effects (two observables) and the affected entity (another observable and therefore another effect)! Again, assuming that one has three effects (observables) constituting the observation process is a logical non sequitur of first rank.

Let us now correct that logical non sequitur made by Whittaker and other physicists and electrodynamicists, and see where it leads us.

First, we go to particle physics, where broken symmetry {99} was discovered in the 1950s. Lee, e.g., received a Nobel Prize for his work in that area {75}. Lee also showed that any dipole is a broken 3-symmetry in its violent energy exchange with the active vacuum.

Well, a scalar potential is a dipolarity; always a potential is actually a difference between two potentials, so to speak. So the potential itself represents a broken 3-symmetry in an energy flow exchange with the active vacuum.

Let us further examine that interesting broken symmetry aspect. It means that the "static" potential is a process whereby energy is received from the vacuum in *one* form, not observable, and hence unusable, but is output in *observable* (usable) form. In short, the dipolarity or dipole receives and absorbs (QM view) virtual photons, integrates them into observable magnitude, and emits real, observable EM energy ("continual observation" snapshots of the latter being assumed).

In physics, all observation is 3-spatial, as is well known. And 3-space is the realm of the observed. The EM energy from the vacuum is not received in 3-spatial (observable) form, else there would be no broken 3-symmetry of the dipolarity.

We can also *experimentally* verify that there is no 3-space input of EM energy to the potential — e.g., to the potential between the ends of any source dipole, because we cannot measure any 3-space observable energy feeding the charges of the dipole. Instead, observable 3-space energy is continuously pouring out of the dipole.

Let us continue now with the notion of a real dipole of separated source charges, with our "scalar potential" between its ends, so we have something concrete in mind.

First, our instruments prove there is a continual emission of EM energy in all directions in 3-space (of the kind in that atrocious diagram; a "series of iterative film-snapshots"). That is the way it is conventionally represented, as if observed at each and every point successively in that 3-space, and along every radial.

But secondly, our instruments also prove there is no such observable *input* of EM energy in that same 3-space *to* the dipole. Bummer! That is precisely what has stopped electrodynamicists from solving that vexing problem of where all the energy pouring out of the source dipole is coming from, and how! They unconsciously assume that the only possible source of the EM energy input is in 3-space. That is totally wrong. Further, the conservation of energy law does not require that energy be conserved in 3-space! Instead, rigorously — if we are using a 4-space (i.e., spacetime) model — it requires that energy be conserved in 4-space. The assumption of the extra condition of 3-space energy conservation is an added and arbitrary extra condition.

Since electrodynamics has not resolved this "source dipole and its associated fields and potentials" problem, it has stopped work on the problem and implied that every dipole in the universe is a perpetual motion machine, freely creating all that EM energy it continuously pours out across space, in all directions, creating its associated fields and potentials. That implicit assumption, if true, of course destroys the conservation of energy law.

It isn't true, and the energy conservation law is alive and well!

We can experimentally prove that the source dipole *does* continuously pour out energy in all directions in 3-space, without ceasing, as follows:

In a gedanken experiment, we set instruments every 300 million meters or so, along a radial line from an origin in the lab. With the instruments and clocks synchronized, we suddenly form a dipole at the origin. One second later, the first instrument reads. A second later, the second instrument reads. And so on. But it is not a "passing pulse". Whatever reading the instrument makes as the forward edge of the energy flow reaches it, is then continuously maintained thereafter. This proves that the energy is poured out continuously and at the speed of light, and in any (and all) directions in 3-space, *and it continues to pour out at exactly the same rate so long as that dipole remains intact.*

Dipoles in the original matter of the universe have been pouring out EM energy in that fashion for some 14 billion years, and they have not "exhausted" their unobserved energy input source yet.

A newly formed simple dipole, e.g., in one year will have poured out energy into a spherical volume of space that is a light-year in radius. Wait another year, and that volume of space whose energy density has been changed will be two light years in radius. The dipoles in the original matter have filled the universe itself with that energy outpouring from them.

In other words, an incredible amount of EM energy has been and is being poured out into space from every dipole in the universe.[35] And electrodynamicists have had not the foggiest notion of where that mind-boggling amount of outpoured EM energy has come from.

Unless we wish to totally discard the conservation of energy law, we must have an equal input of energy *from outside 3-space*, going into every dipole continuously. In 4-space, that only leaves the fourth axis, along which and from which the input energy must move into the dipole.

And so it does. If we re-interpret that phase conjugate half set of the Whittaker decomposition, *before* observation has occurred, it then is a harmonic set of longitudinal EM waves moving in the time-dimension, *into* the source dipole (parity is not inversed because no interaction with charge has occurred to shift it into 3-space.

So voila! We have strangely (but quite rigorously) solved what Sen {100} referred to in this manner: *"The connection between the field and its source has always been and still is the most difficult problem in classical and quantum electrodynamics."*

We express our reasoning as follows: (i) we know from particle physics that the source dipole[36] is a broken 3-symmetry in its flux exchange with the vacuum. This means that we know the energy is received from the vacuum in an *unobservable* form, absorbed by the dipole, and emitted as *observable* EM energy. It remains to translate that into classical electrodynamics rather than quantum physics {101}. (ii) The *time* domain is the only domain outside 3-space, in the standard 4-space model. (iii) Anything in the time domain exclusively, is indeed nonobservable, since the ∈/∈*t* observation operator destroys time and all its internal structure and dynamics whenever observation occurs. (iv) Looking for a "3-space" input is looking for an "observable" EM energy input, which would in fact disagree with the known broken 3-symmetry of the source dipole.

---

[35] Later we will see that, in a time-forward situation, the negative charge pours out positive EM energy while the positive charge may be said to pour out negative EM energy. Charge conservation then implies that an energy balance is maintained overall.

[36] Because of the broken symmetry of the opposite charges on its opposing ends.

Let me digress now to speak of fundamental units. As is well known, the fundamental units one chooses to make his physics model represent an arbitrary choice. One can, if one wishes, make a perfectly valid (but mentally nightmarish!) physics using only a single fundamental unit. In that case, all other "fundamental units" in the present model become functions of that single fundamental unit.

Suppose, e.g., that we make the joule our only fundamental unit. Then "mass" becomes totally a function of energy — and we have no heartburn with that one since the Einstein revolution and the nuclear age. But then "time" also becomes totally a function of energy — and that surprises us, because we have unconsciously been taught (erroneously) that "time is a flowing river down which a mass drifts like a drifting boat". That is not the nature of time at all; the totality of the photon interactions with a mass create that mass's "motion through time". I can later explain that to you also, if you wish, but let us pass it for now.

It turns out that time is spatial energy compacted by the factor c^2, so it has the same energy density as mass, but in the time axis instead of 3-space. Intuitively, if we are interested in cause and effect, the energy of the cause (time) should be equal to the energy of the effect (in this case, mass). After one reflects a moment, one also sees that "time energy" is required to "drive" a mass through time, just as "spatial" energy is required to "drive" a mass through space. The notion that mass in an inertial frame moves through "empty space with no reaction" is false; it continually moves through the energetics of spacetime, and interacts continuously with it.

Anyway, from still another viewpoint there is no magic in EM energy currents moving in the time domain! Quantum field theory already recognizes multiple polarizations of the photon, including transverse, longitudinal, and time-polarized. Thus, it implies a time-polarized EM wave also. A longitudinal EM wave *moving in the time domain* oscillates along its line of travel. That is indeed oscillating its energy density in the time domain, so that it is "time-polarized". Hence it is a proper time-polarized EM wave, and appears to "gallop" {102} or vary its speed periodically.

The solution to the "source dipole" problem is that the phase conjugate wave half-set of the Whittaker decomposition, when reinterpreted, is the *incoming* EM energy in the time domain, continuously input to the charges of the dipole. The charges interact in the imaginary plane (the time domain), and absorb the time-energy, then transduce it into 3-space, and emit it as Whittaker's set of real observable longitudinal EM waves in all directions in 3-space (as observed). The time-energy waves that are input to the dipole cannot be observed, since observation destroys time and its constituents.

All 3-spatial EM energy comes from the time domain! Broken 3-symmetry of the source dipole immediately releases our arbitrary additional restriction on nature's energy conservation law — i.e., our insistence that the energy input for conservation must be input in 3-space. By removing these arbitrary "shackles" from nature's feet, we allow nature to joyously resume her much-preferred special 4-symmetry in EM energy flow: the circulation of EM energy from the time domain into 3-space, and outpouring of that energy in all directions in 3-space, at the speed of light {103}.

Now let us solve the source-charge problem as well. That one is now easy to resolve.

We know from quantum mechanics that any "isolated" observable charge is actually clustered around by virtual charges of opposite sign. So we simply take one of these clustering opposite charges while it exists, and a differential piece of the observable charge, and we have a composite dipole. Hence the "isolated charge" may be represented as a grouping of such momentary dipoles, each (while it exists) with a scalar potential between its poles, and hence each subject to the same decomposition and reinterpretation we have done.

That is why the source charge can "sit there" and pour out EM energy in 3-space (as observed) continuously, and indefinitely. It is also continuously absorbing EM energy from the time domain. As a set of composite dipoles, it is a set of broken 3-symmetries in EM energy flow. Hence it exhibits nature's preferred 4-symmetry in energy flow, between the time-domain and 3-space.

Note also that, to the 3-space observer, this 4-symmetry is purely negentropic. It is a continuous and ongoing (and expanding) reordering of the vacuum energy, in the form of the reinterpreted Whittaker decomposition.

We can easily engineer negentropy! Just make a little dipole, and nature happily starts pouring out energy and reordering part of the vacuum, with that reordering spreading at the speed of light, steadily increasing all the while.

Reinterpreting Whittaker's marvelous decomposition tells us many things: (i) the source charge or dipole does indeed continuously receive and absorb its input energy from the time domain, (ii) it continuously transduces its absorbed energy to real 3-space energy (as observed!), and (iii) it continually outputs its absorbed and transduced time-energy as 3-space energy emitted in all directions in 3-space (as continually observed).

So the terrible foundations problem of the source charge and source dipole is resolved, and the energy conservation law is maintained.

We have also uncovered a most important thing: Given a little broken 3-symmetry in EM energy flow, t-symmetry in EM energy flow is also broken. A more primary 4-symmetry {104} between time-energy flow and 3-space energy flow emerges *automatically*. In short, every potential, every dipolarity, and every charge is such a broken 3-symmetry and an example of the new, preferred 4-symmetry of EM flow, with input flow in the time-domain (nonobservable!) and output flow (as continually observed in a series of 3-snapshots) in all directions in 3-space.

This also resolves the logical cause and effect problem for observation.

This 4-symmetry is a purely negentropic process, once the dipole is established! Well, we should have known that from the gauge freedom axiom in gauge field theory anyway! That axiom says that we can change the potentials anytime, freely and at will. In electrodynamics, that means we can change the potentials at will, anytime we want to. But that means *we can freely change the potential energy of a Maxwellian system at will, whenever we wish*. It costs nothing — at least in theory; in the real world we have to pay a little for switching — to suddenly potentialize an EM system, prior to the time the Drude electrons relax and current flow begins.

I have applied this great new 4-symmetry in EM energy flow, that is freely evoked and persists indefinitely after one pays a little to make the dipole and thus produce a little broken 3-symmetry, to produce EM energy freely from the vacuum. Without going into it, I refer you to our forthcoming papers {105}. Indeed, we can use this negentropic process to extract as much EM energy from the vacuum as we wish, anywhere, anytime, for peanuts. Let us now move to discuss that area.

First, we point out another astounding result that comes from resolving this "source charge and source dipole" foundations problem.

Generators do not use any of the shaft energy input to them — even in transduced form — to power their external circuits! A generator itself does not add a single watt to the power line, and neither does a battery's chemical energy dissipation add a single watt to its attached circuit.

Neither does burning all those hydrocarbons, consuming all those nuclear fuel rods, building all those dams, etc. to provide our conventional power systems and grid. None of that enormous destruction of the biosphere and pollution of it has ever directly produced one watt on the electrical power line.

Just follow the energy flow, in light of what we now know. Here's how it works.

Typically, we burn some fuel to boil water and make steam, and use the steam to power a steam turbine, which forcibly rotates the shaft of the generator, thereby inputting mechanical shaft energy into the generator. So far, so good. That took care of all the hydrocarbon burning and fuel rod consuming, extracting and transporting the oil, etc.

This input of the shaft energy forcibly rotates the rotor against internal resistance, forming an internal magnetic field. Assuming a 100% efficient generator with no internal losses whatsoever, this means that the *mechanical shaft energy input* has now been totally transduced into *internal magnetic field energy*.

So what does that magnetic field energy *do*? It is totally dissipated upon the internal charges of the generator, performing work on them and forcing the positive charges in one direction and the negative charges in the other direction. That dissipation of the energy in the internal magnetic field *forms a source dipole inside the generator, connected to the terminals*.

And that is all the generator does. Period. *None* of the energy transduced from that shaft input, went roaring out of the terminals and down through space outside the conductors of the power line. Not a single watt. So let us turn to particle physics to find out what happens next, because *it does not yet appear in the electrodynamics model, even though proven.*

The internal source dipole, *once formed*, is a great broken symmetry in the vacuum flux, as we discussed and as is well known in particle physics. But the proven and well-known vacuum interaction with the generator and the dipole charges is not even modeled in the classical EM theory used by the scientists and engineers to build electrical power systems — much less a *broken symmetry* in that active exchange! That's atrocious, since it's been proven in particle physics for nearly a half century, Nobel prizes awarded, etc. But the hoary old 137-year old Maxwell-Heaviside model, further curtailed by Lorentz symmetrical regauging, does not incorporate what has already been proven in physics. *It does not accurately model the situation as it is and as it is known to be.*

Let us continue.

Once that dipole is formed, it extracts *enormous* EM energy from the vacuum, and pours it out of the terminals of the generator, filling space surrounding those conductors of the attached external power line. It is a huge EM energy flow, trillions of times larger than what we account after Lorentz taught us to disregard almost all of it.[37]

Only the tiny little bit of that EM energy flow in space along and surrounding the conductors — the little "boundary layer" that skims down the surface of the conductors — will strike the surface charges in the conductors and get diverged into them to potentialize the Drude electrons and "power the power line and its circuits and loads". *All the rest of the giant EM energy flow in space surrounding the conductors, and generally parallel to them, misses that power line entirely and is just wasted.*

Check the original papers by Poynting {4a, 4b} and by Heaviside {5a, 5b, 5c}, who independently discovered the flow of EM energy through space (as if continually observed!) in the 1880s, after Maxwell was already dead. I can furnish the citations required. From the beginning, Poynting only considered that component of the energy flow that actually enters the circuit. He considered only the "boundary layer" right on the conductor surfaces, so to speak.

Heaviside considered that component that enters the circuit, and also uncovered and recognized the *gigantic* component in the surrounding space that *does not* enter the circuit but misses it entirely and is wasted. [Added] Here is Heaviside's {106} own statement:

> *"It [the energy transfer flow] takes place, in the vicinity of the wire, very nearly parallel to it, with a slight slope towards the wire… . Prof. Poynting, on the other hand, holds a different view, representing the transfer as nearly perpendicular to a wire, i.e., with a slight departure from*

---

[37] However, contrary to what is in the textbooks, **E** Δ **H** energy flow is not in observable EM field form **E** and **H** until it interacts with charge. Instead, the flow is in the form of virtual energy currents in the vacuum. We point out that the fields **E** and **H** utilized in the Poynting energy flow theory are effects and not causes. They are rigorously defined as **E** and **H** only after the causal 4-fields have interacted with charge. E.g., **E** is "defined" as force per unit point massive charge — i.e., as the force created by interaction of the "vacuum field" (curvature of spacetime) with a unit point charge. No unit point charge interaction, no force or force field intensity per interacting unit point charge.

> *the vertical. This difference of a quadrant can, I think, only arise from what seems to be a misconception on his part as to the nature of the electric field in the vicinity of a wire supporting electric current. The lines of electric force are nearly perpendicular to the wire. The departure from perpendicularity is usually so small that I have sometimes spoken of them as being perpendicular to it, as they practically are, before I recognized the great physical importance of the slight departure. It causes the convergence of energy into the wire."* [End of Added].

But Heaviside had absolutely no explanation for the enormous and startling magnitude of this energy flow that "misses the surface charges of the conductors and is wasted". You can see an elementary illustration of the "point intensity" of this Poynting diverged energy flow component in Kraus {107}. Kraus's figure 12-59, p. 576 shows a good drawing of the *Poynting* component *being withdrawn* from the total EM energy flow filling all space around the conductors [see our Figure 1-1 in the present chapter].[38] Most of that available energy flow is not intercepted and thus not diverged into the circuit to power it, but just "wasted." The *remaining* huge component discovered by Heaviside is not shown on Kraus's diagram. Kraus's numbers on the contours represent the amount of power (watts per sq meter) being withdrawn from each contour, by the very limited axial movement of the electrons and the very ends of their associated fields into the wire.[39]

---

[38] The energy flow in space near the surface of the wires strikes the surface electrons and their fields, potentializing them and creating a force field with respect to inner electrons. This drives the surface electrons axially into the wire, since they can only move down the wire with the drift velocity, nominally on the order of a few inches per hour. The short inwards drawing of those small portions of the fields and of the increased potentials attached to the charges that move into the wires, interacts with the internal charges in the interior of the wire, powering the Drude electrons throughout the conductor and the circuit. For a discussion of the importance of the surface charges, see J. D. Jackson, "Surface charges on circuit wires and resistors play three roles," *Am. J. Phys.*, 64(7), July 1996, p. 855-870.

[39] Obviously the increased fields on the withdrawing surface charges reach toward infinity radially outward from the wire. Thus most of this increased field on a withdrawing electron remains outside the wire, radially reaching toward infinity, since the electron and its field cannot be withdrawn further than the diameter of the wire. As the surface charges and their fields change in Jackson's discussion, obviously those distant parts of the field remain outside the conductors. Hence there remains an extensive field and field energy outside the conductors and the circuits

So Heaviside {106} spoke cautiously of the *angles* and *relative directions* of the flow components; he did not wish to be scientifically destroyed for pointing out such an inexplicably large EM energy flow, far larger than the known energy input to the generator. There was then no such thing yet discovered as the electron, the atom, the nucleus, special relativity, general relativity, quantum mechanics, the active vacuum, etc. Poynting {4a, 4b} never even thought of the "nondiverged component that misses the circuit", nor did he consider it.

Lorentz, however, understood the extra Heaviside component and its vast magnitude, but he also could not explain it in any fashion. Even the great Lorentz could not risk publishing or advocating such an enormous energy flow, lest he be called a "perpetual motion nut" and destroyed. So he reasoned that, since that stupendous nondiverged energy flow component misses the circuit and powers nothing, it has "no physical significance" (his words).

Jackson in his famous 1975 *Classical Electrodynamics*, 2nd edition, uses essentially the same phrase {108a} as did Lorentz. And so do most other electrodynamicists.

So Lorentz {109} originated a little trick of integrating the energy flow vector itself around a closed surface surrounding any volume element of interest. Obviously, that zeros all *nondiverging* EM energy flows — including precisely that inexplicable and enormous Heaviside "dark energy" component. The integration trick does retain that small, *diverged* Poynting component that enters the circuit. In addition, our instruments measure energy dissipation from the circuit, and the energy has to *enter* the circuit to *be dissipated* from it. So our instruments and their measurements will indeed agree with the Poynting energy flow component. Lorentz thus arbitrarily discarded accountability of trillions of times as much EM energy flow as was retained and accounted.

In a later book by Lorentz, one can see that little trick {109} that is still used by electrodynamicists {110}.

---

that is never drawn into the wire. Additional separate receiver circuits with resistive loads, adroitly placed in this "externally remaining" field energy flow, can be made to intercept additional EM energy and will perform additional work in those external loads in the secondary circuits, separate from powering the loads in the primary circuit.

The Lorentz trick does not cancel the *actual* flow of the Heaviside dark energy component around every circuit! It just drops it from any accountability.

Indeed, we do precisely a similar thing for the "field" and the "potential". There is not a single text in the U.S. that calculates the magnitude of the *field itself*, prior to point interaction. Instead, we are taught to calculate the reaction of that field at a point in it, with a unit point static charge at that point. In short, we calculate *what is actually locally diverged from the field or potential by that little point static unit charge*, and call it "the magnitude of the field". At best, it is indicative of the field intensity at a point, because we have prescribed the magnitude of the static point charge's *reaction cross section* with the field, *not* the overall magnitude of the entire field itself. Another major non sequitur! By identifying the "field" as "that which is diverged from it", we gravely err. We do the same for the potential, again using its reaction cross section for a unit point charge at a point in the potential.

There is hardly a living electrodynamicist, it seems, who has calculated the magnitude of the field itself, or of the potential itself! All calculate the respective reaction cross section (and the *static* reaction cross section at that!) and erroneously call that the "magnitude of the field" or the "magnitude of the potential". It is no such thing. No thing filling all space is identical to a little something diverted from one point in itself, else we discard all logic.

Now we can return to our source dipole and its extraction of an *enormous* energy flow from the vacuum, once we account for the long-neglected (for more than a century) Heaviside dark (nondiverged, unaccounted) energy flow component. That is the essence of one of my papers {111}.

The easiest thing in the world to do is to extract enormous usable EM energy flow from the vacuum, *from the time domain*. Every circuit and every electrical power system already does it, and every electrical power system is powered by vacuum energy, *not* by burning all that coal, oil, etc. None of that does anything to actually power the circuit. It only makes dipoles.

If you will check the characteristics of the ubiquitous closed current loop circuit, you will discover a diabolical thing: that closed current loop circuit forces all the spent (depotentialized) electrons from the ground return line back through the source dipole (back through the back emf). It is easily shown that precisely half the energy *collected* in the circuit from that feeble Poynting energy flow component is then used to perform work on those dipole charges and scatter them, thereby destroying the source dipole and abruptly shutting off all energy extraction from the vacuum. The other half of the collected Poynting energy is dissipated in the external loads and losses. That means that half the collected Poynting energy is used to kill the source dipole, and less than half is used to power the loads {112}.

Well, we must input at least as much energy (assuming a 100% efficient generator with no losses) to the shaft of the generator to *restore* the dipole, as was used to *destroy* it. This means we shall always have to input *more* energy to the generator shaft, than we get dissipated in the loads.

That is precisely what is responsible for our ubiquitous COP<1.0 systems. *COP* is Coefficient of Performance, and is the average load power output in the external circuit divided by the average shaft power we pay to input to the generator.

COP < 1.0 comes from (i) the ubiquitous usage of the closed-current-loop circuit, and (ii) the prevailing notion that electrical power systems far from equilibrium in their energetic exchange with the active vacuum are impossible to build. In fact, every electrical power system is *already* just such a COP > 1.0 system, as far as the energy flow out of the generator or battery — compared to the shaft input energy to the generator or battery — is concerned.

As is well-known in the thermodynamics of open systems far from equilibrium with their active environment (in this case, the active vacuum), such a system is permitted to: (1) self-organize, (2) self-oscillate or self-rotate, (3) output more energy than the operator himself must input to the system (the excess energy being freely received from the active environment, in this case the active vacuum), (4) power itself and its loads simultaneously (all the energy being freely received from the active environment, in this case the active vacuum), and (5) exhibit negentropy.

But by designing all our systems so that they use more of their collected energy from the vacuum to kill their source dipoles than they use to power their loads, we have foolishly wasted the planet's resources, vastly overcharged the consumer, artificially created a great energy crisis, fomented wars for precious oil and other energy resources, polluted the planet, enhanced global warming, and strangled species.

In short, we pay the power company to have a giant wrestling match inside its generators and lose! And we pay our electrical engineers to keep designing and building such asinine systems!

This sad state of affairs is what is now upon us as a great and increasing energy crisis, polluting and destroying the biosphere, etc. and threatening to eventually collapse the world economy.

It is astounding that, since the basis for the above has been in physics for nearly a century (Whittaker decomposition) and for nearly a half century (broken 3-symmetry of the source dipole, as well as the active vacuum), the hoary old classical EM model has not been updated to incorporate what has already been proven in particle physics. Such is inexplicable and unconscionable.

It is also astounding that no electrical engineer realizes that energy extracted from the vacuum powers every electrical power system, and few if any professors are aware of it either.

This is where your cogent realization of the terrible non sequitur in that atrocious "wave in 3-space" standard diagram leads.

Our AIAS (Alpha Foundation's Institute for Advanced Study) advanced theorists now have a series of papers published in the hard literature pointing out the feasibility of extracting EM energy from the vacuum {113a, 113b}. About 20 other AIAS papers along such lines or related have been submitted to the various journals and are in the referee process.

I just wanted to contact you informally and, for your personal information, show you how perceptive and correct your objection to that atrocious diagram is. You have lifted the corner of the veil on electrodynamics' confusion between effect and cause, with effect being widely used as the cause. The entire notion of a "separate force" acting on a "separate mass" in mechanics is also a non sequitur. If we define force as $F \sum \in / \in t(mv)$, then we see that mass is a *component* of force! So here is another major and uncorrected non sequitur. This one was also largely responsible for the dichotomy of the field concept, where the "same field" is used in both a force (mass-containing) manner and a force-free (without mass) manner, as if the two were the same!

I very much enjoyed your editorial, and would urge you to publish additional material along that same vein. You are striking at the very heart of the problem, and every bit of insight and change in those terrible non sequiturs will result in enormous progress in electrodynamics and physics.

Sincerely,

Tom Bearden, Ph.D.

Lt. Col., U.S. Army (Retired)
Director, Association of Distinguished American Scientists
Fellow Emeritus, Alpha Foundation's Institute for Advanced Study

---

Chapter 2

Background and Concepts

> *"[Hypotheses made without realizing that they are being made] ...are what Poincare has called "unconscious" or "natural" hypotheses — a type which one hardly ever challenges, for it seems too unlikely that we could make progress without them. Nevertheless it should be the endeavor of the physicist always to drag them out into the light of day, so that it may be perfectly clear what we are actually doing."* [Lindsay and Margenau] {114}
>
> *"Equilibrium states are the only ones that are capable of explicit analysis in thermodynamics... "* [Lindsay and Margenau] {115}
>
> *"Non-equilibrium conditions cannot be specified by variables of state, and their entropy cannot be computed. ...the condition of equilibrium is the condition of maximum entropy. "* [Lindsay and Margenau] {116}

2.1 Comments on the Foundations of Classical Electrodynamics

2.1.1 Faraday, Maxwell, Quaternions, and Heaviside

For our purposes, we start with the important experiments of Faraday {117}, which produced experimental integration of electricity and magnetics {118}. Faraday's own work contained very little mathematics, and so he himself did not capture his own seminal experimental work in adequate theoretical fashion. That task was undertaken by James Clerk Maxwell {119a, 119b}, who deliberately set about to capture Faraday's results in a proper mathematical theory, using quaternion-like and vector expressions. Of the quaternion algebra, Maxwell had this to say {120}:

> *"...the virtue of the 4nions lies not so much as yet in solving hard questions as in enabling us to see the meaning of the question and its solutions. "*

Quaternion algebra {121a, 121b} is an advanced algebra created by William Rowan Hamilton, brilliant Irish mathematician. Hamilton was widely regarded as a "new Newton" by his peers. Hamilton coined the word "vector", wrote two books on quaternions, and hoped the books would find extensive use in physics. Vectors and tensors later came to suffice for most problems of that day, and so quaternions faded to the background.

Hamilton also grasped the importance of a science of time, and realized that such a science was possible. E.g., in 1837 Hamilton stated:

> *"The notion of time may he unfolded into an independent pure science... a science of pure time is possible."*

In that statement, Hamilton anticipated that a physics model can be comprised using only a single fundamental unit, and that unit could be the second.

In the early 1890s, quaternions in electrodynamics were discarded in a short "debate", mostly in the journal *Nature,* and vector electromagnetics was adopted. So Maxwell's 20 quaternion equations {20} in some 20 unknowns contain a wealth of electrodynamics {122} that is not included in Heaviside's {123} later vector curtailment after Maxwell's death, or in the modern tensor formulation. As an example, Nikola Tesla's patented circuits cannot be properly understood in either a vector EM or tensor EM analysis. However, very novel functions performed in them can be seen in a quaternion EM analysis, as has been clearly shown by Barrett {124}. Any electrodynamicist, who has looked at Tesla's work only in terms of tensor or vector classical electrodynamics, has no concept of what Tesla was actually doing. Since that is precisely how most academics have examined Tesla's work, they have had little idea of the functions he was actually able to accomplish in circuits — functions that U.S. electrical engineering departments still cannot perform.

Along with other electrodynamicists at the time, Faraday and Maxwell believed in a material ether — a thin material fluid filling all space. Hence there was thought to be no point in the universe that was devoid of mass. For that reason, the EM field conceived in mass and the EM field conceived in "space" — actually, in the "luminiferous ether" thought to fill all space — were identically force fields and material entities, at least in the minds of the electrodynamicists at the time. The equations of Maxwell, the later truncation by Heaviside and others, and the final truncation by Lorentz are all still material fluid flow models. They still assume the material luminiferous ether, more than a century after its falsification.

See again Figure 1-3 in Chapter 1. Contrary to the conventional view, force is not a fundamental causative entity, but is a system of two coupled entities. It involves a nonobservable, dynamic, causative 4-space entity (which may be modeled as a curvature of spacetime) interacting with a previous "frozen" observable (a 3-space mass). The output of this interaction is another observable (i.e., a change to the previous observable or an iterative output of its replica). Observables do not continuously exist, but continually recur as continual outputs of the iterative observation process (photon interaction).

Mass is a *component* of force, as is apparent if we define force F as $F \equiv d/dt(mv)$, which gives $F = m(dv/dt) + v(dm/dt)$. Both terms on the right of the expansion contain mass; hence force F contains mass as a *component.* Both terms on the right also contain nonmass terms; hence force F also contains nonmass coupled to and interacting with mass. So there can be a force generated by a nonmassive non-force entity in spacetime interacting with a mass, and the force only exists when that interaction is ongoing. The ether was erroneously considered to be a material system, containing mass, and hence capable of supporting a force. Maxwell modeled his fields (in what we know today to be mass-free space) as material force fields in the material ether.

In the 1880s, the Michelson-Morley experiments {125a-125d} destroyed the material ether. However, the fundamental Maxwell-Heaviside equations *assuming* those material force fields in the vacuum — which depended on the notion of a material ether and are a function of it — have never been altered, even to this day. Instead, electrodynamicists just assume the force "somehow" goes to zero in the field in space, but the same field remains. The equations still assume the same old material ether.

This is a non sequitur; a *force* field cannot be the same as a force-free *non-force* field. As an example, the EM force field in observable matter is an output of observation. It is therefore a *3-space effect containing mass.* The force-free field in mass-free spacetime (4-space) is a causal 4-space component of massless spacetime. *A priori,* it exists prior to interacting with the charged mass. It contains no observable mass and hence no force since mass is a necessary component of force. It independently exists without the presence of the charged mass at all.

In short, the field in massless spacetime is a specialized curvature (changed region) of that spacetime. *Spacetime consists of spacetime,* to slate a tautology. Once one fixes the concept of the medium, then any changes to the medium can only consist of "medium-stuff. So any "changes" in spacetime can only be changes of 4-space itself, in the Einstein general relativity sense. This area is handled quite well by Sachs' unified field theory {126a, 126b}, extending and completing the work of Einstein.

Sachs' epochal theory provides a great generalization of general relativity and electrodynamics reaching from the quarks and gluons to the entire universe. Further, Evans' extension of electrodynamics into a higher 0(3) group symmetry turns out to be demonstrably a special subset of Sachs' electrodynamics.[40] Hence, for the first time, an *electromagnetically* engineerable unified field theory is available. Much of general relativity, quantum mechanics, etc. can be engineered directly by Evans' electrodynamics subset of Sachs' overall unified field theory. I am much indebted to Evans {127} for the following statement with respect to O(3) electrodynamics:

> *"In 1992 it was shown (Phvsica B. 192, 227, 237 (1992)] that there exists a longitudinal component offree space electromagnetism, a component which is phaseless and propagates with the transverse components. Later this was developed into a Yang-Mills theory of electromagnetism with O(3) Lagrangian symmetry. This theory is homomorphic with Barrett's SU(2) electrodynamics and has far reaching implications infield theory in general. Recently it has been recognized to be a sub theory ofthe Sachs theory ofelectromagnetism, based on the irreducible representations ofthe Einstein group of general relativity.[41] The Sachs theory produces a non-Abelian structure for the electromagnetic field tensor. The O(3) electromagnetism also has implications for the* ***potential*** *ability ofextracting energy from the vacuum,* ***and its*** *topological implications are currently being* ***investigated*** *by Ranada. The O(3) electromagnetism has* ***been tested*** *extensively against empirical data, and succeeds* ***in*** *describing interferometric effects and*

---

[40] E.g., see M. W. Evans, "The Link Between the Sachs and 0(3) Theories of Electrodynamics," in M. W. Evans (Ed.), *Modern Nonlinear Optics,* Second Edition, Wiley, 2001, part 2, p. 469-494.

[41] Evans et al, "Derivation of 0(3) Electrodynamics from the Irreducible Representations of the Einstein Group," *Found. Phys. Lett.,* 15(2), Apr. 2002, p. 179-

> *physical optical effects where the conventional Maxwell-Heaviside theory fails. Implicit in both the O(3) and Sachs theories of electromagnetism is the ability to extract electromagnetic energy from curved space-time. Working devices based on this ability would help solve the current energy crisis."*

2.1.2 Mass Is a Component of Force

The dichotomy of using the field concept in two mutually contradictory fashions as something massless and also as something massive — still unresolved in electrodynamics — is clearly summarized by Jackson's important statement {128} of the prevailing view:

> *"Most classical electrodynamicists continue to adhere to the notion that the EM force field exists as such in the vacuum, but do admit that physically measurable quantities such as force somehow involve the product of charge and field."*

In trying to rationalize the "massive field versus massless field" dichotomy, Jackson {129} also states:

> *"...the thing that eventually gets measured is a force..."*
> *"At the moment, the electric field can be defined as the force per unit charge acting at a given point."*

Actually, field is not force, so cannot be force per unit charge. Field *produces* force when it interacts upon charge. *Causing* something as an effect, but then *being* that same effect identically, is a confusion of cause and effect and a non sequitur.

We point out that spacetime is charged, but with *observably massless* (virtual) charge. So the field in spacetime is observably massless and therefore observably force-free. That massless field then interacts with an observable massive charge in the "observable" world, to create an observable force and an observable forcefield. In space, from a quantum mechanical view we may consider the field to have *virtual* force x time, since the field may be regarded as a curvature of spacetime acting upon the *virtual* charged masses in the ever-bubbling *virtual particle fluctuations* of the vacuum permitted by the Heisenberg uncertainty principle. Nonetheless, that is only the "potentiality" for an observable force, as pointed out by Feynman and Wheeler, should the field — including its interactions with the virtual charges of the vacuum to produce forces and accelerations on those virtual particles — interact upon an observable charged mass.

Obviously, the force-free field as a product of spacetime curvature and massless (virtual) charge, and the force field as a product of *that* observably force-free field but virtual force field (in the vacuum) with observable charged mass, cannot be the same thing. Assuming they are the same assumes an oxymoron, and confuses cause and effect. This illustrates the continuing dreadful foundations difficulties propagated in classical electrodynamics.

To resolve these EM foundations difficulties so long maintained and cherished as dogma, the scientific community at the highest priority should (1) fund extensive and rapid work by our very best theoreticians and foundations physicists to heal these century-old festering sores, (2) extend electrodynamics back to a higher group symmetry theory, as in O(3) EM theory for example, and (3) provide a rigorous dictionary of science foundations concepts and terms which does contain valid definitions and full discussions — clearing misdefinitions and disinformation now notable in the electrodynamics literature.

Nobelist Feynman, co-founder of quantum electrodynamics, was careful to state the notion of the field in mass-free space very differently. Quoting Feynman {130}:

> *"...the existence of the positive charge, in some sense, distorts, or creates a "condition" in space, so that when we put the negative charge in, it feels a force. This potentiality for producing a force is called an electric field."*

Feynman's imagery clearly invokes a "distortion condition in spacetime" {131}, eventually coupled to a charged mass and interacting with it — and *then* one has a force and a force field. He erred in still somewhat making the force separate from the charged mass, in the phrase "it feels a force" — which ignores the fact that the mass of the interacting charge is a *component* of the force, not separate from it and not "feeling it as a separate external thing". He pointed out that the field in spacetime represents only the *potential for* a force field, *if a* charge should be placed there. And he points out that the field is a "condition in space" — in the full sense, a condition in spacetime.

We comment that, in a sense, spacetime and vacuum may be considered one and the same. Vacuum contains many fluctuations and virtual state dynamics, all of which are curvatures of spacetime or produce curvatures of spacetime. Vacuum has energy density, and is therefore a potential. This energy density has dynamics, so the ambient vacuum potential has dynamics, and so therefore does spacetime {132}.

However, a dynamic of the potential is precisely what a field *is.* It follows that dynamics of spacetime are what fields are. So fields (as force-free entities in spacetime) may be taken more accurately as the dynamics of the vacuum-spacetime, or as dynamics of the ambient vacuum-spacetime potential, or as dynamics of the ambient curvature of spacetime.

Again quoting Feynman {133}:

> *"We may think of E(x, y, z, t) and B(x, y, z, t) as giving the forces that would be experienced at the time t by a charge located at (x, y, z), with the condition that placing the charge there did not disturb the positions or motion of all the other charges responsible for the fields."*

Here Feynman very clearly shows that E and B involve functions of spacetime *(x, y, z, t)* only, prior to interaction, but do not physically exist until interaction with charge has occurred. But he has not quite yet completely eliminated the "force field" as a separate force acting on the charged matter independently. This centuries-old fundamental mistake in mechanics — that force is independent of and external to mass — has simply been propagated into electrodynamics, without correction. Physicists such as Feynman and Wheeler have been trying very hard to correct it.

The observed/measured force field is an output of observation, and observation is a *d/dt* operator imposed upon spacetime LLLT. All observables are 3-spatial, and any observation is an instantly frozen "3-space snapshot" at a single point in time. A single observation has no temporal existence *a priori,* since it is only an instantaneous 3-space snapshot existing at one moment only. Hence an observable — being 3-spatial and frozen — does not persist *as such* in time. Indeed, the next instant after an observation, that particular snapshot does not exist any more. [Refer again to Figure 1-3 in Chapter 1].

2.1.3 Mechanism for the Flow of Time and Related Matters

It is well recognized that the nature of time is itself an unresolved question. For our purposes, we are interested in the energetics[42] approach. So we apply that approach to arrive at a mechanism generating the "flow of an object through time". First we will choose our fundamental units.

2.1.3.1 *Getting Creative with Fundamental Units*

In physics, the choice of fundamental units one chooses for one's model is arbitrary. Usually mass, length, time, and charge are used, but a perfectly valid model can be generated using only a single fundamental unit.

This is well known to modern physicists and leading electrodynamicists, but sometimes comes as a shock to electrical engineers! Jackson {134} expresses it very succinctly: Quoting:

> *"For example, theoretical physicists active in relativistic quantum field theory and the theory of elementary particles find it convenient to* ***choose*** *the universal constants such as Planck's quantum of action and the velocity of light in vacuum to be dimensionless and of* ***unit magnitude.*** *The resulting system of units (called 'natural' units) has only* ***one*** *basic unit, customarily chosen to be length. All quantities, whether length or time or force or energy, etc., are expressed in terms of this one unit and have dimensions which are powers of its dimension. There is nothing contrived or less fundamental about such a system than one involving the meter, the kilogram, and the second as basic units. It is merely a matter of convenience."*

So let us consider what happens if we use the joule as the single fundamental unit for a model of physics. Then each of the entities "mass", "length", "time," and "charge" will become totally a function of energy. Since the dawn of relativity and the nuclear age, the notion that "mass is energy" is no problem, and everyone is familiar with Einstein's $E = mc^2$. Solving for m in that expression, one realizes that spatial energy E has been compressed by the factor c^2, to yield what is called "mass m". More rigorously, compressing the 3-space energy by the factor c , *and then leaving it in 3-space,* produces what we call "mass". However, if we remove it from 3-space and place it over on the fourth Minkowski axis *ict*, it becomes what we call "time" because *t* is the only variable in *ict*. Hence time has or can have similar energy density to mass. Specifically, 1 sec => 9×10^{16} joules of spatial EM energy, when transduced (decompressed) into spatial energy by a transducing charge.

---

[42] **Energetics** is an **old term from the early birthing** days of electrodynamics. Russian scientists resurrected **the term to cover their use of an** expanded electrodynamics in a unified field-engineering **manner, particularly in new** superweapons developed and tested after WW II and deployed in 1963 and subsequently.

In our new model using only the joule for our fundamental unit, we can also legitimately state that "time is energy", and be rigorously accurate. In that case, we must see what happens to 3-space EM energy when it is shifted to the time domain.

First, we take "EM energy in 3-space" as EM wave energy, in the usual transverse EM wave model (see Figure 1-4 of Chapter 1) of a field entity. We choose, say, the vector E oscillating in the x-direction, and another field entity (say, the vector B) oscillating in the y-direction. If we then rotate each of these vectors into the time axis, then that is an orthogonal rotation for each, which is what the velocity *c* actually is. So we have to do two orthogonal rotations, and the two resulting *c's* multiply to give c^2. With these two orthogonal rotations into the time axis, we have completely rotated the EM field wave energy vectors into the time axis. We have also compressed that EM field energy by c^2.

Hence "time as energy" is just EM spatial energy compressed by the factor c^2, but rotated into the time-axis as "time" rather than remaining in 3-space as "mass". Again, by this second analogy time has the same energy density as mass, but the highly compressed spatial energy has been rotated into the time domain to "produce time" rather than remaining in 3-space to "produce mass" {135}.

This sheds new light upon the scalar (time-polarized) photon of quantum field theory. Note that, prior to compression of the wave energy into time, the magnitude of the electric field *E* in the EM wave was oscillating lengthwise along its x-direction, which means that, with respect to x, it was a longitudinal EM wave. A similar consideration exists for the oscillation of the magnitude of *B* in the y-axis. Along the time-axis, we also have a "time-energy" vector having magnitude, and the magnitude of that time-energy can only vary along the time axis. Oscillating the time energy produces a longitudinal EM wave in the time dimension (on the fourth axis). What is actually varying is the time-density itself. This is a *time-polarized* or *scalar* EM wave, where by use of the term "scalar" we mean that it has no vector component in 3-space. In fact, this variability of time density produces a "galloping motion" in the speed of light itself, which has been recognized {136}.

We have uncovered a direct connection between the time-polarized EM wave (which can only oscillate its time-energy magnitude longitudinally in the time-domain) and the longitudinal EM wave in space. Such waves can only be observed when coupled or paired with an interaction existing between them, very similar to what Mandl and Shaw {167, 168} argue for the time-polarized and longitudinal photons of quantum field theory.

Again see Figure 1-3 in Chapter 1. Any observable is an instantaneous, frozen 3-spatial snapshot (or 3-intersection) of a 4-dimensional ongoing event. "Observation" itself may be taken as a process where a *d/dt* operator is invoked upon 4-space (spacetime), leaving a purely 3-spatial output. However, the resulting observable does not "exist or persist in time", since rigorously it is what was "caught" in only a single, frozen "3-slice" at one single instant, forever fixed.

For that reason, time is not an observable. It cannot be directly observed, even in principle, since *a priori* it is discarded by the observation process itself!

For further work along such lines, we recommend the Sachs unification approach to a combined general relativity, quantum mechanics, and electrodynamics, generalized from a topological standpoint {126a, 126b}. To work electromagnetically in that theoretical approach, we recommend the 0(3) electrodynamics as extended by Evans {137a, 137b}.

2.1.3.2. *The **Four Polarizations of** Photons **and** EM Waves*

In quantum field theory, four polarizations of a photon are recognized {138}. These are the *x*-, *y*-, *z*-, and /-polarizations, where *x*-, *y*-, z- and *t*- are assumed as the four dimensions in a 4-space. By agreement, z- is used as the direction of motion of a free photon or an electromagnetic wave. So at least in theory, there must also be four polarizations of electromagnetic waves, even though not all these waves are yet experimentally known.

The *x*- *and y*- polarizations are the familiar transverse photon and the transverse wave. The z- polarization along the line of propagation gives the longitudinal photon in 3-space and the longitudinal EM wave in 3-space.[43]

---

[43] Here we are **applying the conventional** model of the "EM wave in space", which is known to be erroneous **but is** in **ubiquitous** usage. See Romer, {84} for a scathing characterization **of that** erroneous model **But here we are stuck with it, so will use it** as "just a model".

2.1.3.3 *Imperfect Longitudinal EM Waves* ***in 3-Space***

When attempting to produce longitudinal EM waves (LWs) in 3-space, from transverse EM waves (TWs) input to some sort of polarization transduction process, only imperfect LWs are produced and a residue of TW content remains. The resulting imperfect LW is referred to as an *undistortedprogressive wave* (UPW). Some work has been done on UPWs {139}. UPWs are expected to have remarkable characteristics including wave velocities either slower or faster than *c {*140}.

The *t*- polarization in the time dimension is quite unique: The *spatial* energy overall is in equilibrium and not vibrating at all; instead, the energy of the photon or wave is vibrating in the time domain and therefore exists in the time domain. That is called a "scalar photon" (time-polarized photon). Its wave version does not yet seem to be known in the literature, although in 2000 we uncovered its secret hiding place {12}. It was unexpectedly hiding in Whittaker's {85} decomposition of the scalar potential in 1903, but had been slightly misinterpreted.

2.1.3.4 *Photons andEM Waves Carry* ***Energy and Time***

On the other hand, the concept of "EM waves flowing in 3-space" may be in need of a thorough overhaul {141}. A photon *y* is a "piece of angular momentum" in the form of $y = (dE)(dt)$. Hence the photon carries an increment of spatial energy d*E* and also an increment of time-energy d*t.* The time-energy component *(dt)* may be regarded as ordinary spatial energy that has been compressed by the factor c^2 {142}.

As can be seen, since *c* represents an orthogonal rotation in n-space, the multiplication or division by *c* and by powers of c changes the dimensionality of an entity, as seen by the observer in the laboratory frame.

So the photon transports two types of energy: (i) a "weak spring" (spatial, decompressed) energy d*E,* so to speak, and (ii) a "very stout spring" (time) energy d*t,* so to speak.

When a mass *m* absorbs a photon *(dE)(dt),* the *(dE)* component is compressed spatially by c^2, turning it into an extra amount of mass d*m,* so that the mass becomes *(m + dm)*d*t the same time, the *(dt)* component is joined, so that what results is *(m +* d*m)*dt.* In short, mass *m* is changed to masstime *mt* by photon absorption. So in the absorption of a photon y by a mass *m,* we have

$$y+m\text{->} (dE)(dt) + m \text{->} (m + dm)dt$$

In short, the mass *m* turns into masstime *mt*, by absorbing a photon, and masstime *mt* is as different from mass *m* as impulse *Ft* is different from force *F*. We point out that "mass" *m* alone does not even exist in time, but masstime *mt* does exist in time. This is proposed as a simple but fundamental correction to much of present physics. Further, the state "mt" is an excited, time-charged state, excited by very dense time-energy.

For the simplest case, in the next instant the excited state *mt* decays and a photon is re-emitted, and so we have

$$(m + \Delta m)\Delta t \rightarrow (\Delta E)(\Delta t) + m \rightarrow \gamma + m \qquad [12]$$

So emission of a photon changes the excited masstime state (time-charged state) back to mass (uncharged state with respect to time-charging), in the simplest case.

See again Figure 1-3 in Chapter 1. "Observation" and "observable change" are in fact generated by the photon interaction. The total photon interaction with a mass creates the "flow of that mass" through spacetime, macroscopically as seen by the observer and microscopically in myriad streams of virtual time changes. Mass is continually charged to the masstime state, and the masstime state is continually decayed to the mass state. Time flow itself thus has a myriad internal EM energy streams and a vast dynamic EM energy substructure.

The photon itself is not observable, as it exists prior to interaction. It is thus a "causal" entity in 4-space. It *is not* a simple 3-space observed "frozen snapshot" particle! When the causal photon is absorbed, its spatial energy component goes through the c compression function, thus adding a small amount of new mass to the previous mass (previous effect), but simultaneously connecting its d*t* time-tail, so that the slightly increased mass in fact now exists as masstime and not mass. Observation has not been completed at that point.

In the next instant, a photon is re-emitted (from masstime, never from mass!), in the simplest case removing that extra little mass increase and orthogonally rotating it back into 3-spatial EM energy, coupling that spatial energy increment d*E* to that "time-tail" d*t* and tearing it away as the photon is re-emitted. That leaves behind a frozen 3-space snapshot of the mass (the interacting particle) and completes the "observation". In the simple case, this is a replica of the previous particle (frozen 3-space snapshot) with which the causal photon interacted. So this process accounts for the so-called "persistence in time" of an object or mass, as seen by the observer's continual recall process accompanying his stream of iterative observations. Mass does not *continuously exist* in time, but *continually recurs* in time.

As is well known, what we call "observable" change must involve the expression in equation [13] in the fashion discussed and with the observation mechanism given.

We first pointed out the preceding mechanism for the "flow of a mass through time" in 1971, as a graduate student at Georgia Institute of Technology, and later published it in a crude paper {143} in 1973. It still needs a far more thorough theoretical treatment, which perhaps some graduate student will take up as the subject of his or her doctoral thesis.

2.1.3.5 ***Photon Interaction:*** *Mechanism Generating Flow Through Time*

See Figure 2-1. Mass does not really "travel through time" continuously *per se*, but proceeds with an overall serial change mechanism as

$$m \rightarrow (mt) \rightarrow m \rightarrow (mt) \rightarrow m \rightarrow \ldots \qquad [14a]$$

where *(mt)* symbolizes a nonobservable ongoing "coupled" interaction state prior to observation completion. Equation [14a] represents the results of the continual photon interaction process, observation process, and "flow of a mass through time" process, at the highest single-photon interaction or quantum change level, and as "seen" or measured by the external observer.


SPATIAL
SPATIOTEMPORAL
L^2T PHOTON
SPATIAL
PHOTON
MASS L^3
L^2T
MASSTIME L^3T
MASS L^3
$(\Delta E)(\Delta t) + M \Rightarrow (M+\Delta M)\Delta t \Rightarrow M + (\Delta E)(\Delta t)$
Flow of macroscopic time (observable photon interactions)
SPATIAL AND SPATIOTEMPORAL
"MASS"
MASSTIME L^3T
MASS
MASS
MASSTIME L^3T
"MASS"
Flow of microscopic time (via virtual photon interactions)

Figure 2-1 Mechanism for the flow of a mass through time.

Also, in that overall quantum level "flow" there are anyt number of ongoing streams and "sublevels" in the underlying subquantum level (in the virtual vacuum and in its virtual photon interaction with observable mass). We might write one of these "internal time-stream interaction flow substructures" as:

$$(\delta m) \rightarrow (\delta mt) \rightarrow (\delta m) \rightarrow (\delta mt) \rightarrow (\delta m) \rightarrow \qquad [14b]$$

In equation [14b] we have used parentheses, because all terms individually are nonobservable. We hypothesize that each stream continues until one of its terms participates in a summation which eliminates it by enfolding it into another interaction.

When a mass is observed as in [14a], a photon has been emitted (we observe the mass as the "effect" remaining). Time has been stripped away by the resulting *d/dt* operation, leaving a frozen 3-spatial snapshot, which we will see as (having been) a particle (simplest case). That occurs just after major ("observable") photon emission from the masstime state {144}. Immediately another observable photon is absorbed, and so state *mt* occurs. The particle of mass actually oscillates at a very high rate between the *m* and *mt* states — so high a rate that by arranging the interaction conditions one may interact with it either as a wave (react predominantly in the *mt* state) or as a corpuscle (react predominately in the *m* state).

Hence we propose that the process in [14a] may account for the duality of particle and wave.

2.1.3.6 *The Overall Flow of Time Has an Internal Dynamic Structure*

During the transition in any mass to masstime state by reaction of the mass with an "observable" photon, a myriad of fleeting virtual photon interactions involving very tiny *(dE) (dt)* components occurs with the mass *m.* These tinier increments of time, and their increments of energy, constitute internal structures in the time flow process. Therefore they may be considered as "energy currents" or "time-like energy currents" and dynamic structures or streams inside the flow of time. This is particularly straightforward if we use a model having only a single fundamental unit, the joule. In that case, time is energy, and we are speaking of energy flow and its constituent internal structures of energy flow.

So the d*t* component of masstime at the observable-photon action level has a myriad of energy-time structured dynamics infolded within it. Hence the *mt* state is very dynamic in time, particularly for fundamental particles. The *mt* state is in fact a "collection of time-energy dynamics" and therefore "wavelike".

See again Figure 2-1. A major point is that ***mass*** does not emit a photon; *masstime* does. Mass "travels through time" by an extremely high oscillation between corpuscle-like state *m* and wavelike state *mt,* and with a vast internal "dynamic streams" of other such high oscillations between corpuscle-like *m* states and wavelike *mt* states.

The concept can be very much extended, of course, but this suffices for our concept of energy currents in time, the interaction of such energy currents with mass in a mass system, and the internal dynamic structuring of the "flow of time".

This internal structuring is important in the event of *"time-energy" charging.* There the internal structure of time has experimental consequences. We will discuss those consequences in later chapters.

2.1.4 The Ubiquitous Substitution **of** Effect **for** Cause

See Figure 1-3. To repeat, no observable exists or persists *as such* in time. An observable *as such* only exists at all when time has been momentarily stopped. It then quickly changes into (observable x time) form, for a time interval after a photon absorption. Then it changes again to observable form by photon emission and the corresponding *d/dt* differentiation imposed by that photon emission.

What happens when we think we see an "observable moving through space" is that we make or suppose a continual series of very fast *d/dt* 3-spatial snapshot observations, one after the other in serial fashion (much like the individual frames of a motion picture film). For more than a million years, human brain and mind processing have "always interpreted" this serial set of iterative operations occurring in the eyes and in the physical senses — and continually recalled and processed by the mind — as an "observable persisting in time", which it is not.

This age-old "natural" and inbred, instinctual *mental practice* and assumption by humans — and therefore by scientists — has provided a major problem in physics and especially in electrodynamics. It has resulted in the substitution of the "effect" for the cause in a great number of models. Even a rapid and continual series of 3-space effects after reaction of an observable (frozen snapshot) with a 4-space causal entity, does not and cannot constitute that 4-space entity which interacts with the previous "frozen snapshot" observable and causes the resulting "comparative change or sameness" of the new observable with the former. Hence, e.g., Romer's scathing condemnation {84} of the conventional drawing of an "EM wave in space".

In general relativity, it is straightforward. The curvature of spacetime — the cause — is not the mass (the 3-space observable effect) that is further changed or created again in the ongoing interaction, as seen in the "next

3-space snapshot" (next output of observation) when comparing that snapshot to the previous one.[44]

The same non sequitur — unwitting substitution of effect for cause — has existed for hundreds of years in mechanics, for example. There it is strongly passed on in the erroneous old notion of a separate force acting upon a separate mass. *Prior to* the interaction, no "force" exists. *During* the ongoing interaction, force exists because it is the product (interaction) of a "non-force" causal entity (e.g., a field in 4-space, as a certain curvature of spacetime there) and a previous effect (a 3-spatial frozen snapshot called "mass"). The force exists during the interaction and only during the interaction, when both cause and previous effect are coupled (and will produce the new effect at the completion of the next serial *d/dt* operation as a photon is emitted). The force can only exist when the mass (previous effect) is coupled to the cause (the curvature of spacetime), since *a priori* mass is a *component* of force {145}, and curved spacetime is another *component* of it. After the interaction "ends" in a new *d/dt* observation, the mind compares the new effect with the former, to determine whether there is a "change" or a replica (sameness). This comparison of the new observation (observable) with respect to the former, *occurs in the brain and mind processing,* and gives the sense of "persistence of an object in time" as well as of an object "changing in time".

So a great faux pas in physics — and especially in electrodynamics — is this widespread substitution of the effect for the cause. Understanding this non sequitur clearly, and correcting it, is a prerequisite to understanding the principles and concepts of legitimate COP>1.0 Maxwellian systems. Also, if we would ever hope to adequately correct electrodynamics, this tremendous faux pas must be recognized and rooted out of the model. Indeed, the same is true for mechanics and other branches of physics.

2.1.5 Some Additional Foundations Non Sequiturs

Another gross non sequitur is made in calculating the amount of EM energy flow continually being diverged around an intercepting unit static charge at a point in space, from a potential in which that point is located, and then calling this "local intensity" of the collecting interaction the "magnitude of the potential" itself.

---

[44] Rigorously, if one wishes to connect spacetime and mass, spacetime can be interpreted in *masstime* units, but not ***mass*** units And vice versa. Again, masstime *mt* is as different from mass *m* as impulse Ft is **different** from force *F.*


E ≡ F/q
S = ExH
Note problem:
No "E" or "H"
as such in
vacuum.
Source q is a
broken symmetry
in vacuum flux
S = ExH
SOURCE
CHARGE
Assumed perpetual
motion machine
in classical EM
ϕ "pileup" in front
So E ≡ -∇ϕ
Point
coulomb
ϕ ≡ joules continuously
in geometrical flow
distortion zone around
a point coulomb

Figure 2-2 Field and potential are defined in terms of the diversions from them around a unit point static charge assumed at any spatial point

(See Figure 2-2). At best, it is a measure of the *local intensity of the diversion of energy flow from* the "bidirectional" EM longitudinal waves comprising a potential, as they are diverged around the unit point static charge. It is not the magnitude of the entire potential, filling all space, nor does it prescribe the spatial energy magnitude of that entire potential {146}. It is a small energy flow, *diverted* by an assumed standard fixed charge at a single point in the potential, from the overall energy flows comprising the potential. Calling this little "diversion of a bit of energy" the magnitude of the potential is rather like calling a little whirlpool in a river the "magnitude of the river". Or more exactly, it is like calling the amount of little "swirl diversion of a river's flow" around a standard small fixed rock the "magnitude of the river".

A similar non sequitur exists in the usual calculation of the "field" magnitude at a point, which is not the "entire field entity itself at all. It is merely what is *diverged from* the "field as it exists in spacetime" at a single point in it, by an assumed fixed standard point charge at that point that is interacting with the field. The field takes into account the patterning of the diverged flow, e.g., the difference in potential (difference in pressure) across the unit point charge. That is not the field itself at all, and the textbooks and dictionaries of physics are completely wrong in calling it such. Again, at best, it is an indication of *the field intensity* at that point, and the reaction cross section of the field to an assumed unit point static charge. Even that indication of local intensity of the field will change if the intercepting charge is not static but is in resonance, as shown by the Bohren experiment {24}.[45]

As can be seen from these few examples, a great deal of work needs to be done to clean up the "definitions" promulgated in physics and electrodynamics for more than a century. It is inexplicable[46] that this has not long since been accomplished. These errors permeate almost every textbook, and they desperately need correcting. The National Academy of Sciences and the National Science Foundation should fund the best possible effort on this rework of the foundations of physics.

2.1.6 System Coefficient of Performance (COP) and System Efficiency

See again footnote 11 in Chapter 1 and Appendix A. In 1915, general relativity in fact destroyed several of the fundamental definitions (axioms) of classical thermodynamics. It necessitated our correction of some thermodynamical definitions (open system and closed system) and our more rigorous definitions of COP and efficiency advanced below.

Once mass is recognized as energy and the two are just different sides of the same coin, there can be no thermodynamically closed system which passes energy across the system boundary without passing mass across it. Any system changing its rate of flow through time also changes its mass and its energy, and vice versa. Energy has mass characteristics, and any mass system with added or subtracted energy — either kinetic or potential

---

[45] Many Bohren-type experiments are continually done in nonlinear optical labs in universities and elsewhere. The effect (excess radiation from the medium) is euphemistically called "negative absorption of the medium," "negative resonance absorption of the medium," etc. Such terminology avoids clearly recognizing that more energy is output than the scientists (erroneously) calculate was input. Bohren faced the issue head-on, and clearly stated that more energy was output than was input (or than was thought to be input).

[46] A true pessimist might point out that it may be quite understandable, considering that it solidly blocks COP>1.0 EM electrical power systems and electro-gravitational anti-gravity systems from being developed by our universities, which would solve the energy and transportation crises forever. Thereby it also keeps about $1.5 to 2 trillion a year pouring into the coffers of controlling financial groups behind many great interlocking corporations.

— will also change its mass relativistically as well as its other characteristics such as inertia and gravitational attraction. As pointed out by Logunov and Loskutov {635}, in 1917 the new characteristics of general relativity led Hilbert {632} to observe that in general relativity there can be no energy conservation rules of the usual classical kind. This also follows from our consideration of the supersystem with multiple active environments rather than a single active environment.

We have formally destroyed any absoluteness of the present classical thermodynamics, which is just an imperfect model. It is a special case which can be approached but never completely reached in a real dynamic system.

With that in mind, we now more exactly define *coefficient of performance* and *efficiency* of a system.

The term "coefficient of performance" (COP) is a ratio whereby the useful energetic output performance of the system is characterized *purely with respect to the operator's energy input.* Simply put, it represents "how much you get for what you have to input yourself and pay for". It does not characterize the performance of the system with respect to the *total energy input from all sources.* For our purpose, in general there are two major ways of expressing this COP:

(a) COP == (work accomplished in the load during a representative time of operation) divided by (energy input by the operator during that representative time of operation). Or for short, COP = (useful work out in the load) + *{operator's* energy input). We stress that there may be other free inputs of energy to the system, in addition to the operator's input, but only the operator's input is accounted in the COP calculation.

(b) COP == (average power out in the load) divided by (average power input by the operator).[47] Again, there may be additional average power inputs that are freely input from the environment, without cost to the operator, but only the *operator's* input is accounted. We stress that "power input" is another of electrical engineering's misnomers, but we use it here because it is universally used in power system engineering.

---

[47] This is in standard electrical engineering terminology, which is mangled. For a more precise physics statement of (b), COP == (the average rate at which the system dissipates energy in its load to do useful work) / (the average rate at which the operator must furnish energy to be dissipated as work in the input section of the system to make it operate and do its output work).

For a system such as a transducer, which merely changes the form of the energy in some fashion and does not perform work in an external load (the transducer is its own load), we may express the COP as

a. COP == (effective energy output) / (energy input by the operator). Here we accent that there may be additional energy inputs to the system from the active environment, and these inputs are "free" and are not input by the operator, so they are not accounted in the COP calculation.

b. COP == (average power output) / (average power input by the operator). Again, additional average power inputs may be freely received from the environment, but they are not accounted in the COP calculation.

The "efficiency" E of a system is a ratio less than or equal to 1.0 (or a percentage less than 100%), where E indicates the percentage of the total input energy (from all sources) that is dissipated in the load as useful work. It follows that (7 - E) indicates the percentage of the total input energy that is dissipated in the internal losses in the system, not directly resulting in useful work by the system in its load. So the efficiency E of a system may be expressed as:

a. E == (total work output in the load during a representative operational period) / (total energy input to the system, from all sources, during that period).

b. E == (average power output in the load) / (average energy rate of input to the system, from all sources, during that representative operational period.).

We accent that no system can have an efficiency greater than 100%, for then it would be "creating energy from nothing" {147}. No system can dissipate or convert energy that it does not first receive. The conservation of energy law states that energy can neither be created nor destroyed. This means that *there actually are no energy sources per se, in the sense that the source creates the energy,* even though we use the terms "energy source" and "source of energy" informally. E.g., Semiz {148} states it this way:

> *"The very expression 'energy source' is actually a misnomer. As is known since the early days of thermodynamics, and formulated as the first law, energy is conserved in any physical process. Since energy cannot be created or destroyed, nothing can be an energy source, or sink. Devices we call energy sources do not create energy, they convert it from a form not suitable for our needs to a form that is suitable, a form we can do work with."*

A medium inefficient system can easily have a COP>1.0, if it receives additional energy from its active environment, and if that extra free energy is sufficient to overcome its internal inefficiency losses. An example is a common windmill, where a very good one may have an efficiency of less than 50% due to friction and drag losses in the gears and wind spillage losses in the blades, etc. Yet the operator himself does not have to input any energy at all, for the windmill to operate continually. In this case, the COP»1.0 and approaches infinity, but the efficiency of the windmill is still less than 50%.

Another example is the home heat pump, which may also have an efficiency of less than 50%. When acting as a refrigerator, its theoretical maximum COP = 8.22 under nominal conditions {149}, and a well-designed 50%-efficient home heat pump will produce COP = 4.0 when conditions are suitable.

On the other hand, if the only net energy input to the system is that energy that the operator inputs, then the COP < 1.0. This is a system in equilibrium with respect to any energy exchange with its external environment — *except* with respect to the energy input by the operator (i.e., with respect to its "fueling" by the operator, so to speak) and with respect to the energy subsequently dissipated in the loads and losses. If the system is 100% efficient (has no internal losses or conversion losses at all), its COP = 1.0. Almost all real systems do have internal losses, so their efficiency is E < 100%. In that case, the system in equilibrium with its environment, and having E < 100%, will also exhibit COP<1.0

irrevocably. Indeed, the same number will give both the efficiency E and the COP, because numerically they are then the same.[48]

For electromagnetic systems, the state of confusion between efficiency E of the system and the COP of the system is due to one fact. *Numerically* the two are always equal in *equilibrium* systems — and the Lorentz regauging condition enforced by the closed current loop circuit self-enforces the equilibrium condition of the system with respect to its active environment. Because electrical engineers usually have zero experience with COP>1.0 electrical systems, they tend to loosely and erroneously use the two terms "efficiency" and "COP" as if they meant the same thing. They do not.

Now suppose that we have an open system, far from equilibrium in its energy exchange with its active environment. Suppose that the system's efficiency E is very poor, so that E = 20%. Now suppose that the environment inputs twice as much energy as does the operator. Let the operator's energy input be E_1. Then the total energy input to the system, from both the operator and the environment, is $3E_1$. The efficiency is only 20%, so the system outputs W, as work in the load, of $W = 0.2(3E_1) = 0.6 E_1$. The COP of the system is the work out divided by the operator's input, which is $COP = W/E_1$, which is $COP = 0.6 E_1 / E_1$ which gives COP = 0.6. As can be seen, even though this system receives twice as much additional free energy as what the operator inputs, it is so inefficient that **its COP<1.0.**

Suppose we have a similar system with the same energy inputs from the operator and from the environment, but now the system's efficiency E is E = 90%. Then the total energy input to the system, from both the operator and the environment, is $3E_1$. The efficiency is 90%, so the system outputs W, as work in the load, of $W = 0.9(3E_1) = 2.7 E_1$. The COP of the system is the work out divided by the operator's input, which is $COP = W/E_1$, which is $COP = 2.7 E_1 / E_1$, which gives COP = 2.7. As can be seen, a more efficient system in the same energy input situation, now outputs more work than the energy input by the operator. Energy is conserved at all times; the excess energy for the additional work was in fact freely input to the system — which is an "open" system far from equilibrium in its exchange with its active environment.

---

[48] We emphasize that COP and efficiency are two quite different concepts, however, even when their numerical values are the same. A 6-foot tall man and a 6-foot tall door have the same number for their **height,** but only a fool would consider them the "same thing".

Thus a system far from equilibrium in its energetic exchange with its active environment, is *permitted* to exhibit COP>1.0 even though its efficiency is always less than 100%. On the other hand, if the system is very inefficient and the energy input from the environment is not too great, the system will still exhibit COP<1.0. But the operator will pay less for his energy costs to operate that inefficient system, than he would pay to operate it if he himself had to furnish all the energy input.

Two cautions are emphasized:

(a) First, electrical engineers use the term "power" to mean "energy flow rate without dissipation or change of form", as well as "energy flow dissipation and change of form rate." This is inexact and unfortunate, but it appears ubiquitously throughout the electrical engineering literature. So we are essentially "stuck with it" for the moment. From a rigorous physics point of view, energy flow without divergence or change has absolutely no power, because power is defined as the rate of change of the form of that energy flow — e.g., the rate of dissipation (scattering) of that energy flow, which in physics is a rate at which work is being performed.

(b) Second, it seems that more than half the engineers and scientists — and many textbook authors — do not clearly understand the difference between COP and efficiency, and often interchange these two terms as if they were the same. They are not at all the same, and a great deal of confusion exists in the casual engineering literature because of using them interchangeably. That is why we have clarified them and given some simple explanatory examples, sufficient for our purpose in this book.

2.1.7 COP>1.0 and the Question of Perpetual Motion

Legitimate scientific researchers attempting to work in open EM systems far from thermodynamic equilibrium are often subjected to rather vicious ad hominem attacks, charging that they are perpetual motion machine addicts and therefore raving lunatics. This of course is not true. We are simply trying to do with Maxwell's "electric fluid" systems what nature already shows us can be done with material fluid systems. We are in fact seeking the equivalent of "electromagnetic heat pump" processes and systems. It is the strident critics who are thoroughly confused and who reveal an immature knowledge of physics and thermodynamics.

As we explained, prior to their Lorentz symmetrical regauging, the Maxwell-Heaviside equations already clearly prescribe and permit COP>1.0 EM systems, including EM power systems. In addition to the present EM systems in equilibrium in their exchange with their active vacuum environment, the non-regauged equations also include Maxwellian systems far from equilibrium in their energetic exchange with an active environment, such as the active vacuum. Classical *equilibrium* thermodynamics — stridently waved as a sacred banner by the critics accusing COP>1.0 researchers of being "perpetual motion nuts" and such EM systems as being "perpetual motion nonsense" — does not even apply to such *disequilibrium* systems! One should simply read the literature of the thermodynamics of such disequilibrium systems {160a-160f}. Or one should read why Prigogine was awarded the Nobel Prize in Chemistry in 1977, for his contributions to such open systems in disequilibrium.

We accent again that, under our new rules where we corrected the thermodynamic definitions of open system and closed system, we are in compliance with general relativity. Further, every EM system must be taken as an open system, since in the supersystem energy (with mass-like changes resulting across the system boundary) is always exchanged between the three supersystem components.

Fortunately there are also rational, reasonable critics such as Angrist {150, 151} where the criticism is properly scientific and not ad hominem, even though still misguided. Usually the rational perpetual motion critic applies the three laws of classical *equilibrium* thermodynamics, to classify "perpetual motion machines" of class 1, 2, and 3 after equilibrium thermodynamics laws 1, 2, and 3. This of itself has no intellectual content for open systems in disequilibrium with their active environment. The classical equilibrium thermodynamics — including laws 1, 2, and 3 interpreted only in terms of the operator's energy input — does not apply to *open systems far from equilibrium* — which are the only systems permitted to exhibit COP>1.0 in the first place. And we insist that all EM systems are open systems far from thermodynamic equilibrium, since every charge is, and all fields and potentials come from those source charges. Indeed, such open disequilibrium systems are *permitted* to violate the laws of classical thermodynamics! As an example, the entropy of such an open disequilibrium system cannot even be computed {152}, and it is less than the entropy of the same system in equilibrium, since the equilibrium state is the state of maximum entropy.

The rational critic then falls upon the horns of a dilemma, by admitting that, yes, such open dissipative systems do exist and do permissibly exhibit

COP>1.0. He then labels these *as, false or fictitious perpetual motion machines* {150, 151}. In short, when such COP>1.0 machines are real and admittedly exist, they are not *"true"* perpetual motion machines but *fictitious* perpetual motion machines. My comment is that they are not perpetual motion machines at all, but permissible disequilibrium machines freely receiving excess energy from their energetic exchange with their active environment. They are no more mysterious than a windmill, a sailboat, a watermill, or a solar cell bank.

One must be precise. A bicycle is a free-energy COP>1.0 machine while going downhill. It is not such at all when going uphill. The difference is that gravitational input of energy aids the bicycle's motion in the downhill case, and opposes it in the uphill case. The active environment gives the system additional energy in one case, and takes energy from the system in the other case. Disequilibrium exchange can cut either way!

It is precisely the EM system far from equilibrium with its active environment — where the environment puts in additional energy — that the serious overunity researcher is seeking. It is a perfectly valid pursuit, even by the standards of the perpetual motion critics, who really should study *both* kinds of thermodynamics, not just *one.* They also should study how Maxwell's equations were curtailed and truncated; one result is that all Maxwellian disequilibrium systems were — and are — discarded *arbitrarily* by the Lorentz symmetrical regauging.

The only criticism one needs to raise vis a vis COP>1.0 and perpetual motion machines is this: If an inert (no hidden internal source) machine receives no net energy from its external active environment, but is in equilibrium in its energetic exchange with that environment,[49] then classical thermodynamics rigorously applies to it and the machine cannot and will not exhibit COP>1.0. However, all EM systems contain charges, and these are indeed "hidden sources" of EM fields and potentials and their energy. It *rigorously follows that, since they contain hidden energy sources, all EM systems are potentially COP>1.0 systems a priori.* Further, *it follows that some ubiquitous design characteristic of the system itself must prevent the system from achieving COP>1.0, since nature does not prevent it.* That characteristic feature is the ubiquitous closed current loop circuit, directing all spent electrons in the external circuit right back through the source dipole in the generator or other primary power source.

---

[49] Here we quibble again and point out that Lorentz's symmetrical regauging actually does require that the system receive and take on excess EM potential energy from its environment (the active vacuum and the local curved spacetime). However, this excess energy can only be received in the form of two injections of field energy, where the fields are equal and opposite. Hence the energy is "bottled up" as a stress potential, with net zero translation force available to it. Since this stress potential energy cannot translate electrons, it cannot do work in an external load. It merely changes the stress of the system itself. The net result is actually a rotation of the frame in which the system exists, away from the "laboratory frame" of the observer. In short, the Lorentz condition establishes a new "equilibrium condition" for the system, by rotating its frame. It also implies that EM energy is continuously received by the system from both the active vacuum and local curved spacetime, in order to maintain the rotated frame and **the** new equilibrium condition. Further this

It is indeed mandatory that — if at all possible - the inventor or independent researcher *identify* a legitimate source of environmental energy that his purported COP>1.0 device receives and collects, and how it receives it and then uses it to power the loads. That means he should identify where and how his system violates the Lorentz self-regauging condition imposed by the standard closed current loop circuit. If the inventor himself cannot explain it — and this does happen — then someone else must explain it for him. If the machine works under proper independent test and replication, then criticism that no explanation exists for it in normal physics is of no relevance. It is a spur to the theorist to enlarge his horizons and to find the proper physics that *does* explain it.

We stress that we cited the works of Angrist because his voice is reasoned and he does not stoop to name-calling and ad hominem attacks. He also does point out a historical rash of machines that clearly must comply with classical equilibrium thermodynamics, because they have no discernible or stated extra input of energy from their active environment and have no self-asymmetrical regauging. When such machines have no external free input of energy from their active environment, they are systems in equilibrium with their active environment, and cannot exhibit COP> 1.0 — exactly as pointed out by Angrist. With such a reasoned critic, a scientific dialog is possible, and his main thrust — that no *equilibrium* system can exhibit COP>1.0 — is quite valid. With the vehement critic, it is already a cur dog fight from the outset and there can be no scientific discussion at all.

The only contention one has with a rational critic, whose criticism is based on classical thermodynamics, is when he then generalizes that *all* EM

continuous input of two energy flows, equal and opposite, does continuous internal work on the Maxwellian system to increase and maintain its stress.

systems fall within this class. That conclusion is a non sequitur, and ignores the entire science of disequilibrium thermodynamics and a vast body of scientific literature and scientific experiments in electrodynamics. When stated for electrodynamic systems, it also ignores the actual documented history of electrodynamics, and ignores Lorentz's *arbitrary discard, from all accountability,* of the Heaviside giant nondiverged energy flow component accompanying every circuit and system. It also ignores Lorenz's and then Lorentz's symmetrical regauging of the Maxwell equations to give new and simple equations easier to solve. This arbitrary regauging did in fact unwitting discard all open disequilibrium Maxwellian systems — precisely those permitted to exhibit COP>1.0.

See again Figure 1-1. The energy entering the circuit is entering it from the surrounding space outside the circuit. Heaviside showed that the energy flow component remaining alter the Poynting component is withdrawn is orders of magnitude greater than the Poynting component entering the circuit and powering it. *It can easily be demonstrated that every generator outputs far more EM energy in space surrounding the power line attached to it, than the operator inputs as mechanical energy to the shaft.*[50]

---

[50] E.g., just use a gedanken experiment followed by the Bohren {24} experiment as validated by Paul and Fischer {25}. Consider a 100% efficient DC system, powered by a DC generator, using a closed Current loop circuit. All the Poynting energy received by the system appears at first blush to be dissipated in the external load. That is not true, but let us not yet belabor the point. Include the complete circuit loop back through the source dipole in the generator. The back emf voltage across the source dipole between the terminals is precisely equal to the forward emf voltage between the terminals but around the external half-loop. The same current flows through both the forward voltage drop and the reverse voltage repotentialization. So precisely as much energy is dissipated to force the current through the back emf, as is recovered from the load.

Accept the conventional view that the shaft energy input to the generator is transduced into magnetic energy, which is then dissipated to force those charges back though the back emf. Now examine the energy flow in space surrounding the external circuit, using both the Poynting theory and Heaviside's theory. We have accounted for the Poynting diverged component, but we have not accounted for the huge remaining nondiverged Heaviside component. From whence comes this excess remaining energy flow that did not enter the circuit, was not included in the Poynting calculation, and was not expended in the circuit but was just wasted? To prove the excess energy flow really exists, perform the Bohren experiment {24} where the intercepting charges in the circuit are in resonance, and thus "sweep out" a larger geometrical cross section of interception of the impinging energy flow. These charges do sweep beyond the static unit charge cross section conventionally assumed in the definitions of field intensity (e.g., of the fields E and H in the Poynting vector S in S = (E x H). If the defining unit point charges are in resonance and sweep out a

Heaviside knew this in the 1880s. All the energy flow that is intercepted by the circuit and enters (i.e., the Poynting component) at essentially right angles, hardly even changes the angle of flow of the remaining huge flow of energy surrounding the circuit and missing it. Quoting Heaviside {153} directly:

> *"It [the energy transfer flow] takes place, in the vicinity of the wire, very nearly parallel to it, with a slight slope towards the wire.... Prof. Poynting, on the other hand, holds a different view, representing the transfer as nearly perpendicular to a wire, i.e., with a slight departure from the vertical. This difference of a quadrant can, I think, only arise from what seems to be a misconception on his part as to the nature of the electric field in the vicinity of a wire supporting electric current. The lines of electric force are nearly perpendicular to the wire. The departure from perpendicularity is usually so small that I have sometimes spoken of them as being perpendicular to it, as they practically are, before I recognized the great physical importance of the slight departure. It causes the convergence of energy into the wire. "*

So every electrical power system is rigorously a COP>1.0 "energy gating" system already, if the neglected, enormous Heaviside energy flow through space around the circuit (and missing it and wasted) is re-accounted. In that case, much greater energy pours out of the terminals of every generator, than the feeble amount of mechanical energy we input to the shaft.

We do not have an *energy availability* problem, and we never have had one! Instead, we have an *energy flow interception and collection* problem

greater cross section, then the assumed Poynting vector S, for the static case, changes in magnitude by some ratio k for the resonant case to the vector S_R, so now $S_R = k_1E \times k_2H = k_3(E \times H)$. Since k_3 is just the ratio of the actual geometrical cross section swept out by the charge to the standard geometrical cross section swept out by the static charge, then for a static charge $k_3 = 1.0$, and for a resonant charge $k_3 > 1.0$. Hence the Bohren experiment, with $k_3 = 18$ or so, produces 18 times as much collected (Poynting) energy "out" as we erroneously think we input by normal calculations ignoring the input Heaviside nondiverged component. The Bohren experiment {24} proves the argument; validation by Paul and Fischer {25} appears in the same journal issue.

— and we always have had one, due to the ubiquitous use of the closed current loop circuit.

Texts — e.g., such as by Kraus {154} — do show the Poynting (intercepted and collected) component of the EM energy flow surrounding the power line attached to the generator terminals, but none of them today go into the remaining nondiverged Heaviside component. Each of Kraus' contours {76} of energy flow in space, around those power line conductors, shows *only that part of the energy flow in space that is being drawn into the circuit.* It does not show the remaining huge energy flow that (i) is not intercepted, (ii) does not enter the circuit, and (iii) is wasted. Presently no texts illustrate this Heaviside nondiverged energy flow component, and no text accounts for it except to point out that the Poynting component must be considered to be indefinite, since it can be accompanied by an additional energy flow component. The texts then erroneously conclude that the excess flow can have no physical significance.[51]

One can easily prove the existence of additional energy flow to be collected, in addition to the Poynting component. E.g., simply examine the Bohren experiment {155} and its replication by Paul and Fischer {156} — or one can repeat the experiment oneself. The Bohren experiment outputs some 18 times as much energy as is input by normal "Poynting component" calculations alone, because it also intercepts additional energy from the unaccounted and ignored *free* Heaviside input component remaining and not diverged by a *static* unit point charge. Bohren simply places the charge in resonance, so it sweeps out a greater geometrical reaction cross section in the energy flow, thereby penetrating into the free — but arbitrarily discarded and unaccounted — Heaviside component, and intercepting and collecting additional energy. Bohren is perfectly aware that the excess energy caught by the resonant charges comes from the surrounding vacuum. However, he seems quite unaware of Heaviside's discovery and cautious statement of the excess energy involved in *every* field-particle interaction, and particularly in electrical circuits.

---

[51] E.g., J. D. Jackson, Classical Electrodynamics, Second Edition, Wiley, 1975, p. 237: *"...the Poynting vector is arbitrary to the extent that the curl of any vector field can be added to it. Such an added term can, however, have no physical consequences. "* Jackson errs in stating that the added energy flow vector cannot have any physical consequences. It cannot, of course, unless one catches some of it and uses it to power a load, without using half of the caught energy to destroy the source dipole faster than the load is powered. One of the major applications of it is to use it with Dirac sea negative energy 4-holes in the vacuum, where the holes produce negative energy fields and potentials in surrounding spacetime, acting back upon the system which is the source of the 4-holes to produce practical antigravity.

There are several such "white crows" which are legitimate COP>1.0 EM processes in physics. It only takes one small white crow to prove that not all crows are black. As another example, the papers of Letokhov {157a-157d} are especially recommended. So long as excess energy is received freely from the environment, the system is permitted to be in disequilibrium where COP>1.0.

So far as this author could discover, none of the perpetual motion machine critics have noticed another very simple fact: The conventional electrodynamics they utilize to refute COP>1.0 Maxwellian systems implicitly assumes that the source charge — which is any and every charge in the universe — continuously *creates* and pours out energy in 3-space without any energy input at all. Their own conventional classical electrodynamics contains a "perpetual motion machine assumption" of the most fundamental and grossest kind. The ardent skeptics of overunity EM systems — in using that implicit conventional assumption — are themselves the greatest perpetual motion advocates of all, though perhaps unwittingly. In 2000 we resolved that long-vexing problem[52] of the source charge {12}.

The more strident critics simply set up the "equilibrium thermodynamics" straw man, then knock it down and attack independent COP>1.0 experimenters with it, erroneously implying that all overunity researchers seek such in an equilibrium system. They fail to notice orthodox science's implied assumption that every charge and every dipole in the universe is already assumed to be a COP => inf. perpetual motion machine, freely *creating* all that continuous outpouring of energy from nothing. None of the critics have noticed and critiqued this greatest of all perpetual motion assumptions right in their own ranks, without a single exception, and the most ubiquitous. Undoubtedly that is because the scientific community honestly and freely admits that it has not heretofore solved that problem {68}, and also points out that the outpouring of energy is an experimental fact and therefore unquestionable.

The better critics — at least the rational ones such as Angrist — already admit that there exists a class of legitimate "fictitious perpetual motion machines" which are powered continuously without the operator inputting the energy. The phrase "fictitious perpetual motion machine" is an attempt to retain the classical thermodynamics straw man, when dealing with the thermodynamics of a system far from equilibrium in its energy exchange with its active environment. That phrase has been a non sequitur since the award of the Nobel Prize to Ilya Prigogine in 1977. We stress again our new use of all EM systems as open systems, in accord with general relativity.

---

[52] After publication of our paper, we also discovered very powerful support for our solution in quantum field theory. E.g., see F. Mandl and G. Shaw, *Quantum Field Theory,* Wiley, 1984/1993, Chapter 5.

So when rigorously analyzed from the breadth of physics and thermodynamics, and not just from a selected very narrow portion, the entire "perpetual motion" critical literature is inappropriate or — more exactly — is inappropriately focused upon a fictitious or false target. It is simply a classic example of reasoning from a false premise.

Not one such critic seems to have noticed that every generator and battery already pours out more energy than what is input to the shaft, and that it is easily proven experimentally via the thousands of experiments showing negative absorption from the medium. None seems to have bothered to read the original Heaviside, Poynting, and Lorentz papers to see how this startling fact was buried more than a century ago.

Finally, a self-appointed "expert" who does not even know what furnishes the energy to power every electromagnetic circuit, cannot be taken seriously in his "learned criticism" , regardless of what journal publishes it. If he continues to accept the unsolved source charge problem, implying that all charges freely create EM energy from nothing, he is not expert in any facet of powering electromag letic systems and circuits.

2.1.8 Prescribed Systems Versus Changes to Maxwell's Equations

As we stated, Maxwell's theory {20} was some 20 quaternion-like and vector equations in some 20 unknowns. By discarding the scalar component of the quaternion to retain only the vector subcomponent, and by discarding many of Maxwell's potentials, Heaviside {158} truncated the Maxwell equations to essentially the present familiar set of four vector equations - or in potential form, to two equations with variables unseparated.

While this truncation discarded a great deal of Maxwellian electrodynamics phenomenology, from a thermodynamics view the resulting *Maxwell-Heaviside* equations still contain and prescribe two types of Maxwellian systems:

(1) systems in equilibrium with their active environment, such as the active vacuum, and

(2) systems far from equilibrium with their active environment, such as the active vacuum.

Systems in the first class of Maxwell-Heaviside systems — i.e., in equilibrium in their energetic exchange with their active environment — rigorously obey classical equilibrium thermodynamics {159}. No system in that Maxwellian class can output more energy than the operator himself inputs to the system. The greatest coefficient of performance (COP) that these systems can accomplish, is COP = 1.0 for a theoretically perfect system without internal losses whatsoever, and thus with 100% efficiency of conversion of their input energy into work in the load. Since any real system has internal losses and thus is less than 100% efficient, the *practical* systems of this first class exhibit COP < 1.0.

These Maxwellian systems of the first class are the electrical systems always "understood" by ardent skeptics who proclaim that no other kind of Maxwellian system exists, that therefore no Maxwellian system can exhibit COP > 1.0, and that a claim to COP>1.0 is perpetual motion lunacy and not science at all. These fellows often launch scathing and unjustified personal attacks upon any serious researcher trying to work with that second class of permitted Maxwellian systems! It would be scientifically beneficial if these self-appointed defenders of the faith would simply study some more physics and thermodynamics, review the history of Maxwell's theory and how it was altered, and understand the well-established thermodynamics of systems far from equilibrium.

This false charge — that there can be no COP > 1.0 EM system because that would violate the laws of physics and the laws of thermodynamics — has been insidiously indoctrinated into generation after generation of physics and electrical engineering students. Today most of our electrical engineers and electrical scientists have absorbed it and believe it without question. Our power-engineering scientists believe it, and so advise the government. Hence our government believes it on the advice of our best scientists, such as the National Academy of Sciences and the National Science Foundation. Our great national laboratories also believe it and are just as mentally conditioned. The universities — especially the electrical engineering departments — also believe it, and provide a mainstream suppression of the sharp young graduate students and post-docs that would otherwise have long ago revised this mess and solved the energy crisis permanently.

Again we are reminded of that first quotation by Einstein, which we included at the beginning of Chapter 1, and which admonished us to ever examine the foundations of our science to root out and correct the errors. We are also reminded of another quote by Tolstoy:

> *"I know that most men, including those at ease with problems of the greatest complexity, can seldom accept even the simplest and most obvious truth if it be such as would oblige them to admit the falsity of conclusions which they have delighted in explaining to colleagues, which they have proudly taught to others, and which they have woven, thread by thread, into the fabric of their lives. "* [Count Leo Nikolaevich Tolstoy].

The second class of Maxwell-Heaviside systems — rigorously prescribed and permitted by Heaviside's truncated Maxwellian theory — is comprised of systems in disequilibrium with their active environment. A system in this class does not obey classical equilibrium thermodynamics. To the contrary, this system obeys the well-known *thermodynamics of systems far from equilibrium* {160a-160f} with their active environment — such as the active vacuum.

Such a system *is permitted to:*

(i) self-order,

(ii) self-oscillate or self-rotate,

(iii) output more energy than the operator himself inputs and thus exhibit COP>1.0 (the excess energy is freely received by the system from its external active environment),

(iv) power itself and its load simultaneously (all the energy is freely received by the system from its external active environment,[53] without any operator energy input being required), and

---

[53] We accent the concept of the supersystem. consisting of three components: (a) the system and its dynamics, considered as in normal electrical engineering (with a flat spacetime and an inactive local vacuum), (b) the active local vacuum and its dynamics, and (c) the active local curvatures of spacetime and their dynamics. All three components of the supersystem interact with each other. In conventional electrical engineering, the assumption in U(1) electrodynamics of a flat local spacetime and equilibrium with the local vacuum exchange eliminates any

(v) exhibit negentropy, which every charge and every dipole in the universe already does {12, 68}.

Let us now see why Maxwellian EM systems of the second class *are not being designed and built as such,* even though they are permitted by the laws of physics and reinterpreted thermodynamics, and even though they are prescribed in the Maxwell-Heaviside equations before further truncation by Lorentz {161a, 161b}. We may use the Maxwell-Heaviside equations in vacuum, because the energy flow intercepted by the external circuit pours out of the generator terminals and fills all space surrounding the power lines. It is therefore a transmission-reception problem, prior to the "potentialized current-transport" problem in the circuit.

2.2 Lorentz Regauging of the Maxwell-Heaviside Equations

2.2.1 Introductory remarks.

The domain of Lorentz's symmetrically regauged equations is only a small subset of the domain of the Maxwell-Heaviside equations they replace. Indeed, the later Lorentz {161a, 161b} symmetrical regauging discards an entire class of Maxwellian systems permitted by nature and by the Maxwell-Heaviside equations before they are symmetrically regauged.

Lorentz's symmetrically regauged EM equations discard all Maxwell-Heaviside systems that are far from equilibrium in their energetic exchange with the active vacuum. They retain only that subset of the Maxwell-Heaviside theory wherein the system being described is in forced equilibrium {162} in its exchange with its active vacuum environment. Hence the present Lorentz-Maxwell-Heaviside theory, by which EM circuits and electrical power systems are designed, produces only systems in self-forced equilibrium with the active vacuum, *specifically during the symmetrically regauging discharge* of the circuit's excitation energy. The closed current loop circuit in fact discharges half its collected energy to destroy the source dipole in the generator, thereby destroying that dipole's extraction from the vacuum and furnishing of the energy flow pouring out of the terminals. These circuits kill themselves faster than they can power the load, and they use more energy to kill the energy flow from the vacuum than they use to power their load. Hence all present EM systems

disequilibrium of the system with its active environment, hence arbitrarily discards all Maxwellian disequilibrium systems - precisely those that can exhibit COP>1.0.

rigorously conform to classical equilibrium thermodynamics, and exhibit a coefficient of performance (COP) of COP<1.0 since any real system also has losses {163}.

2.2.2 Technical regauging of the Maxwell-Heaviside equations {164}. For asymmetrical-regauging (A-regauging) considerations, we are speaking of A-regauging the potential energy in and around a circuit. We include not only the Poynting energy flow component that is diverged into the circuit conductors, but also the remaining Heaviside *nondiverged* energy flow in space surrounding the conductors. This means that the energy is in field energy (E-field and B-field) form, both overtly as ordinary EM fields and covertly or "infolded" inside the corresponding scalar potentials {165, 166, 167, 168}, or both. Consequently, we must analyze Maxwell's equations as we would for radiating energy, rather than employ only the $\mathbf{j}\phi$ circuit analysis conventionally utilized, where the collected energy is sluggishly transported by the Slepian vector $\mathbf{j}\phi$. We show in this book that asymmetrical self-regauging (ASR) allows permissible overunity operation of electromagnetic engines and devices {169}, if other requirements are fulfilled also.

In Gaussian units, Jackson {170} shows that Maxwell's four equations (vacuum form) can first be reduced to a set of two coupled equations in the $(\mathbf{A}, \Phi)$ representation as follows:

$$\nabla^2\Phi + \frac{1}{c}\frac{\partial}{\partial t}(\nabla \bullet \mathbf{A}) = -4\pi\rho \qquad [15]$$

$$\nabla^2 \mathrm{A} - \frac{1}{\mathrm{c}^2}\frac{\partial^2 \mathbf{A}}{\partial t^2} - \nabla(\nabla \bullet \mathbf{A} + \frac{1}{\mathrm{c}}\frac{\partial \Phi}{\partial t}) = -\frac{4\mathrm{p}}{\mathrm{c}}\mathbf{J} \qquad [16]$$

The result is two coupled Maxwell equations rather than four. Jackson shows that potentials A and Φ in these two equations are arbitrary in a specific sense, since the A vector can be replaced with $\mathbf{A'} = \mathbf{A} + \nabla\Lambda$, where A is a scalar function and VA is its gradient. The B field is given by $\mathbf{B} = \nabla\times\mathbf{A}$., so that the new B' field becomes

$$\mathbf{B'} = \nabla\times(\mathbf{A} + \nabla\Lambda) = \nabla\times\mathbf{A} + \mathbf{0} = \nabla\times\mathbf{A} = \mathbf{B} \qquad [17]$$

In other words, the B field has remained entirely unchanged, even though the magnetic vector potential has been asymmetrically changed. However, if no other change were made, then the electric field E would have still been changed because of the gradient $\nabla\Lambda$. In that case the net change would be asymmetrical, because one obtained a "free" E-field which could then do work on the system — either beneficially or detrimentally, depending upon the specific conditions, geometry, and timing. To prevent this excess "free" E-field from appearing, the electrodynamicists simultaneously and asymmetrically regauge (transform) the scalar potential Φ so as to offset the E-field change due to the regauging of equation [15]. In short, they also change Φ to Φ',, where

$$\Phi' = \Phi - \frac{1}{c}\frac{\partial \Lambda}{\partial t} \qquad [18]$$

With that additional change, now the net E and B fields remain unchanged {171, 172}, even though both potentials have changed and the fundamental stored energy of the system has changed, as has the stress of the system. Unchanged force fields just mean that only a set of zero-summation forces (a zero-summed stress system) has been utilized to effect the change in potential energy. It also means that the net summation of the two *asymmetrical* regaugings has been entirely *symmetrical* {173}.

Jackson points out that, conventionally, a set of potentials $(\mathbf{A}, \Phi)$ is habitually and *arbitrarily* chosen by the electrodynamicists such that

$$\nabla \bullet \mathbf{A} + \frac{1}{c}\frac{\partial \Phi}{\partial t} = 0 \qquad [19]$$

This *net symmetrical* regauging operation creates a new and simpler Maxwellian system, with different system stress and different system potential energy. It successfully separates the variables, so that two inhomogeneous wave equations result. This procedure yields a new and simplified system, and the new Maxwell's equations for it are as follows:

$$\nabla^2 \Phi - \frac{1}{c^2}\frac{\partial^2 \Phi}{\partial t^2} = -4\pi\rho \qquad [20]$$

$$\nabla^2 \mathbf{A} - \frac{1}{c^2}\frac{\partial^2 \mathbf{A}}{\partial t^2} = -\frac{4\pi}{c}\mathbf{J} \qquad [21]$$

The two previously coupled Maxwell equations [15] and [16] (potential form) have been replaced by equations [20] and [21], to leave two much simpler inhomogeneous wave equations, one for Φ and one for A. These are *new equations for a new system!*

Of course, this arbitrary *net symmetrical* regauging (let us use the term ***S-regauging)*** is quite useful for purposes of simplifying the theory and for easing calculations. But its unquestioning and rather universal usage has arbitrarily eliminated the freedom of the system designer to *asymmetrically* regauge the system's potentials, and *use* the resulting excess free force fields to change the stored energy in the system without the operator performing extra work upon the system. So we advance the condition for violating this S-regauging, violating the exclusion of net A-regauging, and violating the "frozen gauge" process as

$$\nabla \bullet \mathbf{A} + \frac{1}{c}\frac{\partial \Phi}{\partial t} \neq 0 \qquad [22]$$

Any regauging of the potentials that complies with equation [22] will *a priori* produce one or more net excess forces in the system, as well as a change in potential energy of the system. By controlling the regauging, the system designer is then able to control where, how, and when these excess forces appear, and whether they enhance the system's operation or hinder it. These net forces can then be used to perform work and dissipate the excess potential energy taken on in the asymmetrical regauging. That is what we do when we ourselves add potential (and potential energy) to an EM system to enable it to do work! *If we always have to asymmetrically regauge the system to get it to do subsequent work, why do we not just let the system asymmetrically regauge itself so we get the input energy freely and also get the resulting work freely?* The gauge freedom axiom in quantum field theory assures us that nature will indeed freely change the potential energy of any system for us, if we but arrange it and permit it.

In short, we have had a gauge freedom principle for some time, which guarantees us that COP>1.0 EM systems are permitted and possible. Yet we have failed to realize it, or take any advantage of it. So we continue to pay to asymmetrically regauge (potentialized) all electrical power systems, and to insure that we have to continue to do it, we specifically design the systems so they will then re-enforce Lorentz's symmetrical regauging condition.

This is another of those "inexplicable aberrations of the scientific mind" referred to by Nikola Tesla!

2.2.3 A Humorous Comment but an Exact Analogy

Again see Figure 1-1 in Chapter 1, and see Figure 2-3. In Figure 2-3, we show how Lorentz's integration trick {174a, 174b} discarded the huge nondiverged Heaviside component of energy flow outside the conductor, while retaining the small Poynting component that strikes the surface charges and gets diverged into the conductor to power the electrons. In justifying his integration trick, Lorentz stated that all the rest of that wasted Heaviside energy flow

See Panofsky & Phillips
Classical Electnqtv and Magnetism. 2nd edn
Addison Wesley 1962.
p 178-181

The Lorentz procedure arbitrarily discards the enormous Heaviside component that misses the circuit entirely and is wasted This results in a non sequitur of first magnitude in EM energy flow theory


S
S_R
I^2R
$S_{TR} = S - S_R$
S_{IN}
S_{TR}
S_R
S_{TR}
S_{TR}
S_{TR}
I^2R
S_{OUT}

2-3a. Lorentz surface integration

2-3b. Actual S in and S out.

Figure 2-3 Lorentz's integration trick to discard the enormous Heaviside non-diverged energy flow component

The Heaviside component is often 10 trillion times the Poynting component but is simply wasted in ordinary single-pass energy flow circuits


Heaviside component (nondiverged)
Poynting component (diverged)
Drude electron gas
CONDUCTOR

Figure 2-4 Heaviside nondiverged and Poynting diverged energy flow components.

(Figure 2-4) was "physically insignificant" (his term) because it did not strike the circuit, was not intercepted, and did not power anything. Well, Maxwell's theory is a material fluid flow theory, so let us evaluate Lorentz's justification in a fluid flow analogy.


The Heaviside component is often 10 trillion times the Poynting component, but is simply wasted in ordinary single-pass energy flow circuits
Heavlside component (nondiverged)
Poynting component (diverged)
Drude electron gas
CONDUCTOR

Figure 2-4 Heaviside nondiverged and Poynting diverged energy flow components.

Contrast Lorentz's statement if applied to the ocean wind on a sailing ship, where the wind represents the total energy flow and the ship represents a single Maxwellian system under consideration.


Selects only the locally divergent portion of the Poynting energy flow that powers the component.
ENERGY FLOW GENERATOR
S.S. LORENTZ
Only the wind on my ship is of physical significance!

Figure 2-5 Lorentz in his sailing ship in an ocean wind, with no other ships around.

As shown in Figure 2-5, Lorentz's argument is analogous to stating that the huge component of the wind *that does not* strike the ship's sails is "physically insignificant" — in other words, it has no physical use. Now that is true for the single ship under consideration, as shown in Figure 2-5. None of that wind component that misses the ship's sails does anything at all to power *that ship* (that individual system). Hence it is indeed physically insignificant *to that ship itself.* Of course, if we flare the sails wider, the ship will catch more wind and develop more power. That is an analogy to the Bohren experiment, which resonates the charges (the "sails" intercepting the incoming EM energy flow "wind") so that they sweep out a greater geometrical cross section. Hence 18 times as much energy is caught, as when the charges are not resonated (the sails are not flared to a greater area).


Using the nondivergent Poynting flow that Lorentz integration arbitrarily discarded
ENERGY FLOW GENERATOR
S.S. LORENTZ
How can they use that old physically insignificant wind?!!

Figure 2 6 Lorentz in his sailing ship in an ocean wind, with many other ships alongside.

However, now see Figure 2-6. If we put some more ships (some more systems) with "intercepting and collecting sails" in there, they will be powered quite well with some of that "physically insignificant" wind. So Lorentz (following earlier work by Ludwig Lorenz) really did advance and impose upon electrodynamics a non sequitur of first rank.

And the wind-fluid analogy helps to "lighten things up" a bit here and inject a little good-natured humor!

2.2.4 Discussion

Equation [22] has now become the first *necessary but not sufficient* principle of asymmetrical self-regauging (ASR) for overunity electromagnetic engines and devices. That is, we are now free to A-regauge in a *nonconservative* field manner, where excess net force fields automatically appear and remain for our use in the system. All that remains is for the designer to:

(i) evoke "nonconservative" (asymmetrical) regauging in accord with equation [22];

(ii) have the system assembly in disequilibrium with its energetic external environment, so that the system itself performs this nonconservative A-regauging in some sector or part {175} of its normal operation,

(iii) insure that any "free force" that is produced and allowed to do work upon the system will do some positive work upon the system, so as to increase its collected energy, and

(iv) assure that the "free" forces that are otherwise produced by the circuit design (this includes, e.g., the back emf) do not seriously degrade the system (i.e., do not substantially reduce its energy available to dissipate as work in the load). Usually this means that, contrary to the standard closed current loop circuit, the circuit must not dissipate half its collected Poynting energy to dissipate the charges in the source dipole and destroy it. *These four considerations we now advance as the primary or master principles of asymmetrical self-regauging of electromagnetic engines and devices for permissible overunity efficiency.* We will meet additional principles in a later chapter when we discuss what the form of the energy output of an overunity EM system is, and the considerations for close-looping a COP>1.0 EM system into stable disequilibrium and continuous self-powering.

It is understood that the asymmetrical regauging portion of the circuit or system must be a broken symmetry in the energetic exchange between the active vacuum environment and that portion of the system. We exclude, g., solar cell-powered systems, windmill-driven generators, etc.

For simplicity, the system designer may wish to A-regauge only one potential, producing a desired "free" force F_1 to work on the system and increase its energy, while allowing any other extraneous force F_2 to appear, but just "bottling up" that additional force F_2 so that it cannot do any work at all on the system and therefore cannot degrade the system's operation. A most useful ASR corollary that immediately suggests itself is to simply A-regauge onto that force operation that normally produces the back-drag in a system or device, to either *eliminate* the back-drag altogether or reverse its algebraic sign so that it becomes an *assisting* force instead of a *hampering* force {176}.

In overunity systems, this becomes a startling and unexpected exercise in novel new phenomenology effected by tempic potential differences, tempic force, etc. It involves not only the system, but also the entire *supersystem* consisting of the physical system, its associated altered local vacuum, and its associated curved local spacetime. See Chapter 9 for our expose of these phenomena, and how one must transduce[54] the effects of a very novel kind of tempic force back emf, if the COP>1.0 system is to remain in disequilibrium with the active vacuum and thus maintain its stable COP>1.0 operation.


Dissipative power inside source = V x iT and V x iT > V x iL
Other losses
emf
V
+
−
r1
r2
rn
i1
i2
in
iL
LOAD
back emf
iT = i1 + i2 +...+ in + iL
COP = PL / PT = V x iL / V x iT
V x iL < V x iT ; SO COP < 1.0

Figure 2-7 Why a conventional closed current loop circuit is limited to COP<1.0.

Again see Figures 2-3 and 2-4, and equations [20] and [21]. Electrodynamicists have previously *assumed away* the capability of work-free "refueling" of an electromagnetic system directly from the local vacuum {177}. They have deliberately designed their systems *to prevent self-evoking and positively utilizing asymmetrical self-regauging of their own potential energy during system excitation discharge.* (See Figure 2-7).

---

[54] A patent application on the process has been filed by John Bedini and the present author.

In fact, by forcibly pumping the ground electrons from the external circuit back up through the primary source dipole in the generator or battery, our closed current loop circuits self-enforce the Lorentz condition and require that precisely half the regauging energy freely intercepted and collected in the external circuit is used to destroy the source dipole providing the regauging energy. This destruction of the energy source is accomplished faster than the external load is powered. Hence all such systems with losses are COP<1.0 systems. For more than 100 years, this "self-destroying, suicidal system" is the only kind of electrical power system our energy scientists and engineers have designed and built. To inject a little humor, we can only describe this in Tesla's words[55] as *"one of the most remarkable and inexplicable aberrations of the scientific mind which has ever been recorded in history."*

Thereby electrodynamicists have narrowed the inherent flexibility of the Maxwellian EM gauge theory model to an artificially symmetrized subset of Maxwell-Heaviside-Lorentz equations that utilize a single fixed gauge. This prohibits the free use of the system's vacuum energy freely received by the source dipole's broken symmetry in its violent exchange with the active vacuum. If the system increases its dipolarity (regauges freely), it simultaneously increases the speed at which it destroys the dipolarity! *Maxwell's equations themselves do not require this, and neither does Heaviside's truncation of them into the resulting Maxwell-Heaviside equations. Lorentz's symmetrical regauging of the Maxwell-Heaviside equations does require it.*

The Maxwell-Heaviside theory without Lorentz symmetrical regauging allows regauging asymmetrically to place the system in disequilibrium so that it freely receives and utilizes excess energy from the surrounding vacuum. Then it can again asymmetrically regauge by dissipating that freely received energy in an external load. *The theory specifically does not require destroying the primary source dipole as is done in the arbitrary closed current loop circuit between load and primary source dipole in the generator or battery.*

---

[55] Nikola Tesla, "The True Wireless, *Electrical Experimenter,* May 1919.

By arbitrary habit, electrodynamicists have discarded the Maxwell-Heaviside major EM overunity mechanism: *Asymmetrically self-regauging accomplished by the system itself, without requiring external work being done on the system by the operator,* in order to freely gather in and collect excess potential energy in the system from its broken symmetry with its active vacuum environment. In this self-A-regauging, associated *excess net force* does appear, whereupon that excess collected/stored regauging energy can then be used to "drive" the forces against load resistance and system losses to freely power the system and its loads {178}. They have also discarded the major overunity corollary whereby the designer is free to utilize *system self-regauging asymmetrically so that the normal back-drag or back-emfwork — usually done upon the system in its closed current loop configuration to reduce its kinetic energy — vanishes or reverses sign and becomes beneficial work done in the opposite sense, to freely increase the energy ofthe system.*

The failure to do this is bluntly met with, when one does succeed in producing a COP»1.0 system momentarily by suddenly and very powerfully breaking the system's equilibrium in its vacuum energy exchange. Nature then exhibits a very novel kind of Dirac sea hole reaction (powered by tempic force generated in the locally curved spacetime and resulting effects generated in the altered semiconducting vacuum). This reaction sharply jerks the system (or the system plus its external power supply) back into equilibrium and COP<1.0 operation. In Chapter 9, apparently for the first time in the literature[56] we present this novel mechanism exhibited by nature as a new kind of "tempic back emf phenomenon in systems in disequilibrium. We also explain how to handle the problem and in general how to use it for "freeze-framing" and stabilizing the system's disequilibrium operation in sustained COP > 1.0 configuration while powering itself and its load.

All that is required for "self-powering" COP»1.0 EM engines directly powered by the vacuum, is that (1) initially the engine must asymmetrically self-regauge to produce COP»1.0, and (2) positive *transduced* feedback (from the output) of a very special and previously unknown kind — where negative energy is transformed into normal electron current and energy — must be utilized to its input, in a clamped and controlled fashion {179}. The clamped positive feedback can be designed and applied, once the fundamental engine is designed for self-regauging and overunity efficiency, and once the novel feedback and transformation requirements are understood and incorporated. The remaining excess output can then be utilized to power loads, while the engine seemingly "powers itself."

---

[56] The basis for it, however, is in Dirac's electron theory published in 1930, nearly three quarters of a century ago. See P. A. M. Dirac, "A theory of electrons and protons," *Proceedings of the Royal Society of London, Series A,* 126(801), Jan. 1, **1930, p. 360-365.**

We stress, of course, that this system is just analogous to the windmill, and it continuously receives a "free energy wind" from its active environment. The conservation of energy law is obeyed at all times, as are physics and thermodynamics.

In a later chapter we present the concepts and processes for these novel phenomena involved in close-looping a COP>1.0 system for self-powering operation.

2.3 The Suicidal Closed Unitary Current Loop Circuit

The present Lorentz-Maxwell-Heaviside theory, by which EM circuits and electrical power systems are designed, produces only systems in net usable equilibrium with the active vacuum, specifically during the symmetrically regauging discharge of the circuit's excitation energy (Figure 2-7). Hence all present EM systems designed by that model rigorously conform to classical equilibrium thermodynamics, and exhibit a coefficient of performance (COP) of COP<1.0.

Since the Maxwell-Heaviside equations do not restrict the designer to systems in equilibrium with their active environment, some ubiquitous characteristic of the standard circuit approach must be self-enforcing the Lorentz symmetrical condition as far as using any excess free potential energy of the system to freely power loads. That is the closed-loop circuit, as we have discussed. Let us now illustrate what goes on in such a circuit.

Taking into account Figure 2-4, Figure 2-8 shows a modified diagram of what is actually happening between the vacuum and the dipole to power the circuit. Figure 2-9 shows how a pair of conductors constitutes an extended series of parallel dipoles. Once the dipole is formed by dissipating some chemical energy in the battery, the dipole extracts energy from the surrounding vacuum and pours it out of the battery terminals, producing an energy flow filling space around the conductors of the external circuit. Only a very small portion (Figure 2-4) of the very large energy flow is intercepted by the external charges in the conductors, and diverged into the conductors to power up the Drude electrons.


The broken 3-symmetry of its opposite charges is the generatrix for the dipole's continuous absorption of virtual energy from the vacuum and for its continuous emission of observable Poynting energy flow S = EXH.
Field lines of ordered flux energy
Field lines of ordered flux energy
Vacuum flux exchange
Vacuum flux exchange
DIPOLE
−
+

Figure 2-8 Virtual photon flux exchange intensity **with the charges of a** dipole.

As can be seen from Figure 2-7, half of the energy collected upon the internal electrons to drive them as **jϕ** is expended as work required to pump the spent electrons from the ground return wire back through the source dipole in the battery. This scatters the charges of the dipole (in this case, by changing the chemistry of the battery plates) and destroys the dipole. The other half of the collected energy is dissipated in the external circuit's losses and in the load.

Then some more chemical energy has to be dissipated by the battery to perform work upon the internal charges and restore the dipole (in this case, to change the plate chemistry of the battery plates). So even if this process is 100% efficient, the battery has to dissipate as much chemical energy as was electrically dissipated upon those former dipole charges to scatter them and destroy the dipole.

In Figure 2-7, we show the small internal resistance of the conductors, as well as the load resistor. Half the energy dissipated by **jϕ** is expended just to forcibly ram the spent electrons back through the back emf of the source dipole. The other half is expended in the circuit's internal losses and in the load resistance. Therefore, less energy is expended as usable work in the resistive load than is expended to destroy the dipole and cut off the flow of free EM energy from the vacuum.



Figure 2-9 Paired conductors as an extended set of dipoles.

The battery has to input as much energy to restore the dipole as was used to destroy it. The battery has to expend at least as much chemical energy as equals half the entire energy originally collected in the external circuit and expended as $\int j(t)\phi(t)dt$. It must expend chemical energy $CE \geq \frac{1}{2}\int j(t)\phi(t)dt$. The energy RE dissipated as work in the load resistor R is $RE < \frac{1}{2}\int j(t)\phi(t)dt$. Thus CE>RE, and this system is forced to exhibit

$$COP \equiv \frac{RE}{CE} = \frac{< \frac{1}{2}\int j(t)\phi(t)dt}{\geq \frac{1}{2}\int j(t)\phi(t)dt} \Rightarrow COP < 1.0 \qquad [23]$$

As can be seen, this system symmetrically regauges itself during its excitation discharge, so that it self-enforces the Lorentz condition during that period. The circuit self-enforces COP<1.0, even though all the energy — both the energy powering the external circuit and also destroying the internal source dipole in the battery to enforce the Lorentz condition during discharge — is freely received from the active vacuum via the broken symmetry of the source dipole,[57] once established, in its energetic exchange with the active vacuum.

---

[57] The broken symmetry of opposite charges is one of the broken symmetries predicted by Lee, {13a} and by Lee, Oehme, and Yang, {13b}. Broken symmetry was proven experimentally in early 1957 by Wu *et ai,* {14}. So profound were the implications for physics that the Nobel Prize was awarded to Lee and Yang in latter 1957, the same year! E.g., see T. D. Lee, "Weak Interactions and Nonconservation of Purity," Nobel Lecture, Dec. 11, 1957 in *T. D. Lee, Selected Papers,* Gerald **Peinbcrg,** Ed., Birkhauscr, Boston, 1986, Vol. 1, p. 32-44.

The problem is that *the source dipole is destroyed faster than the load is powered,* as shown in Figure 2-7. Because of the inexplicable scientific pre-occupation with the conventional closed current loop circuit, the planet and biosphere have been increasingly polluted for more than a century, by burning more hydrocarbons, building more dams, using more nuclear fuel rods, etc. to provide ever more electrical energy.

2.4 In Summary

COP>1.0 operation in EM systems via work-free *asymmetrical* regauging has been inherent in the Maxwell-Heaviside equations for more than a century. Since Lorentz first did so circa the latter 1880s, electrodynamicists have just conveniently and arbitrarily *assumed away* COP>1.0 systems by (i) artificially limiting the theory to only that fraction of Maxwell-Heaviside systems in usable net force field equilibrium in their vacuum exchange during their excitation discharge, and (ii) using the ubiquitous closed current loop circuit to self-enforce the Lorentz symmetry condition during that excitation discharge. In other words, our engineers have only been building systems which self-enforce the overly restricted Lorentz-regauged theory.

Electrodynamicists have never seriously tried to build overunity circuits, nor until recently have they explored the discarded Maxwellian systems by removing the Lorentz regauging condition and examining EM energy from the vacuum.[58]

---

[58] Under the directorship of Dr. M.W. Evans, the Alpha Foundation's Institute for Advanced Study (AIAS) has been gradually developing the physics of EM systems far from equilibrium with their active environment (the local active vacuum and local curved spacetime). Some of the papers of interest are: M. W. Evans et al., "Derivation of the Lehnert field equations from gauge theory in vacuum: Space charge and current," *Found. Phys. Lett,* 13(2), Apr. 2000, p. 179-184; Evans et al., {38b}, {38c}, {113b}, {233a}, {233b}, {233e}; {233g}, {233j}; Evans et al., "Schrodinger Equation with a Higgs Mechanism: Inherent Vacuum Energy," *Found. Phys.* (in review); — "Vacuum Energy Flow and Poynting Theorem from Topology and Gauge Theory," *Physica Scripta* (in review); — "Energy from the Vacuum," *Physica Scripta* (in review); — "Some Notes on Asymmetric Regauging", *J. New Energy* 4(3), Special Issue, Winter 1999, p. 325-326; — "Inconsistencies of the Maxwell-Heaviside Theory of Electrodynamics: The Aharonov-Bohm Effect," *J. New Energy,* 4(3), Special Issue, Winter 1999, p. 236-240; — "Spontaneous Symmetry Breaking as the Source of the Electromagnetic Field," *Found. Phys. Lett.* (in press), A monumental work. *Modern Nonlinear Optics,* Second Edition, 3 vols., ed. M. W. Evans, Wiley, 2001 gives a broad coverage of higher group symmetry electrodynamics and energy from the environment (the local active vacuum and the

Every electrical power system ever built is and has been powered by electrical energy freely extracted from the seething vacuum exchange with the source dipole in the system, due to that dipole's broken symmetry. But the engineers and scientists have designed and built only those electrical systems which self-enforce Lorentz's symmetrical regauging.

The time for energy scientists and engineers to correct this procedure and cease this inane practice is long overdue, following the direction pointed out by the AIAS.

---

local curved spacetime). Some 60 AIAS papers are published as a Special Issue of **the** *J, New Energy,* 4(3), Winter 1999. More than 100 AIAS papers are also carried on DoE restricted website http://www.ott.doe.gov/electromagnetic/.

Chapter 3

Giant Negentropy, Dark Energy, Spiral Galaxies and Acceleration of the Expanding Universe

"... the discoveries made in 1957 established not only right-left asymmetry, but also the asymmetry of the positive and negative signs of electric charge. In the standard nomenclature, right-left asymmetry is referred to as P violation, or parity nonconservation. The asymmetry between opposite signs of electric charge is called C violation, or charge conjugation violation, or sometimes particle-antiparticle asymmetry. " [T. D. Lee]. {180}

"The ends of a dipole, being oppositely charged, exhibit charge conjugate symmetry violation. An 'isolated' charge, considered with its clustering virtual charges of opposite sign, also exhibits symmetry violation. " [T. E. Bearden, this book, below].

"A generally acceptable, rigorous definition of radiation has not as yet been formulated." ... "The recurring question has been: Why is it that an electric charge radiates but does not absorb light waves despite the fact that the Maxwell equations are invariant under time reversal? " [B. P. Kosyakov]. {181}

"It [the energy transfer flow] takes place, in the vicinity of the wire, very nearly parallel to it, with a slight slope towards the wire... . Prof Poynting, on the other hand, holds a different view, representing the transfer as nearly perpendicular to a wire, i.e., with a slight departure from the vertical. This difference of a quadrant can, I think, only arise from what seems to be a misconception on his part as to the nature of the electric field in the vicinity of a wire supporting electric current. The lines of electric force are nearly perpendicular to the wire. Their departure from perpendicularity is usually so small that I have sometimes spoken of them as being perpendicular to it, as

they practically are, before I recognized the great physical importance of the slight departure. It causes the convergence of energy into the wire. " [Oliver Heaviside]. {182}

"The funny thing about the dark matter is it doesn't show up in light, X-rays, gamma rays, infrared, ultraviolet, radio waves, or submillimeter. We're running out of places to look for it." [William Keel]. {183}

"... baryonic, ordinary matter — the stuff of stars and of people — makes up just over 4% of the energy and matter in the universe. ...about 30% of the stuff in the universe is dark [unobserved] matter. The remaining two-thirds, theorists believe, is a mysterious 'dark energy' or 'quintessence' — a large-scale antigravity-like effect that is making the universe expand ever faster.... " [Charles Seife]. {184}

"And yet, curiously enough, we do not know exactly what charge is, only what it does. Or, equally significantly, what it does not do."[M. P. Silverman]. {185}

*"**Charge** is the ongoing circulation of EM energy flow between the time and 3-space domains, as seen by the observer. Negative charge is the ongoing absorption of EM energy input from the time domain (from ict), transduction of the absorbed energy into 3-space EM energy, and re-emission of the EM energy in all directions in 3-space. **Positive charge** is the ongoing absorption of EM energy input from 3-space, transduction of the absorbed energy into the time domain, and re-emission of the EM energy in the time domain. If we wish, we may also consider the positive charge as radiating negative energy, while the negative charge radiates positive energy. Once we consider vacuum polarization, we recognize that this circular flow process is involved at each "dipolar point" of the polarized vacuum. "* [T. E. Bearden, this book, below].

"The matter density of the Universe is extremely low. On average there might be one atom per cubic metre of space. The major constituent of the Universe is believed to be some kind 'dark energy', which is pushing the Universe apart. " [Matthew Colless]. {186}

3.1 Broken 3-Symmetry of the Dipole

To recap from Chapters 1 and 2: In 1956, Lee and Yang {187} strongly predicted broken symmetry in physics, suggesting experiments to detect it in the weak interaction. In early 1957, Wu *et al.* {188} experimentally demonstrated broken symmetry, thus furnishing the experimental substantiation of broken parity in the weak interaction. The emergence of broken symmetry was such a dramatic change to the view of physics, that in December of the same year, 1957, Lee and Yang were awarded the Nobel Prize.

One of the asymmetries shown by Lee *et al.* is the asymmetry of opposite charges. That means that a dipole, which consists of slightly separated opposite charges, exhibits broken symmetry in the seething vacuum virtual particle flux. In short, a dipole — any dipole or dipolarity — must absorb or receive virtual photon energy from the active vacuum, integrate at least some of it to observable state, and re-radiate that integrated EM energy in observable form in 3-space.

We stress: *The ends of a dipole, being oppositely charged, exhibit broken symmetry. An 'isolated' charge, considered with its clustering virtual charges of opposite sign, is a set of composite dipoles and also exhibits broken symmetry.*


Dipole formed instantly in laboratory at time = 0
Time after dipole formation when instruments at radial point first read
1 SEC
2 SEC
3 SEC
1 YEAR
>1 YEAR
+
−
Continuous EM energy flow
0
C
2 C
3 C
1 LIGHTYEAR
Radial distance reached by front of continuous EM energy flow
Edge of solar system
Deep Space

Figure 3-1 The source dipole experiment, demonstrating continuous energy flow.

Let us now consider a gedanken experiment, as shown diagrammatically in Figure 3-1, to illustrate Kosyakov's quotation cited above. At a point in the laboratory corresponding to the origin of a 3-dimensional frame, a dipole is produced instantly by separating charges, such as in a flash-charged ca**pacitor.** Along two radial lines in 3-space from that origin, we have previously placed perfect EM field and potential detectors, at distances *ct* apart, where *t*= 1, 2, 3, 4, *n*,... and so on in seconds, with the radials extending across the universe, and where c is the speed of light. We neglect the transient pulse that momentarily occurs at each instrument package, since we are examining steady state conditions.

At the end of one second, the instruments at *t* = 1 instantly read, and those readings remain thereafter. One second later, the instruments at *t* = 2 instantly read, and those readings remain thereafter. And so on with each of the instruments progressively farther from the origin reading at the proper light-time travel, and with all field readings then *remaining continuously* thereafter.

This gedankenexperiment demonstrates that what is emitted from the dipole, from its moment of creation at the origin, is a continuous flow of EM energy in all directions in 3-space.[59] This energy continuously flows from the dipole, indefinitely or as long as the dipole physically exists. Other than paying once to initially separate the charges and make the dipole, we have neither added nor input any additional energy. Yet energy continues to flow out from the dipole in all directions, unceasingly, as shown by the continued of the reading on each field energy density instrument, once the leading edge of the energy outpour reaches that instrument and passes it by. In short, the experiment shows that it is not a "pulse" that passes each instrument, but a continuous and sustained flow of EM energy, remaining steadily thereafter so long as the dipole remains.

One year after making the dipole, the instruments at one light year distance suddenly read, and their readings remain. *The energy density of a volume of space one light year in radius has now been changed, and that change in spatial energy density continues to spread outwards at light speed.*

---

[59] More exactly, what is observed is a spreading change in the energy density and point-like polarization of the vacuum itself, and of the local curvature of spacetime. At each point, once the change of energy density and ST curvature occur, the energy density and ST curvature remain fixed in a new equilibrium condition, steadily fed by the energy radiating from the dipole. See our point made in {181}. The discovery of giant negentropy {12} requires a change in how we view the very process of energy propagating in space. Now it has become a quite different *propagation of energy circulation between time and space domains at each affected point in space.*

Yet there has been no input of *observable 3-space* EM energy flow to the dipole whatsoever, as our instruments also verify. All observable energy flow in 3-space is *outward* from the origin where the dipole is located.[60]

We have shown that the *observable* EM energy flow from a source dipole is not conserved in 3-space, which is consistent with a broken 3-symmetry since symmetry implies conservation. Either we must discard the conservation of energy law altogether, or it must be conserved in 4-space since we have proven the dipole does not conserve energy in 3-space. If we assume that the experiment must conform to the conservation of energy law, then 4-symmetry EM energy flow must exist since 3-symmetry energy flow is broken. The energy steadily pouring out of the dipole in all directions in 3-space must therefore be received by the dipole *charges from the time-domain,*[61] assuming we are working in Minkowski 4-space. In particle physics, this is essentially the same as receiving the energy from the virtual domain, and therefore is consistent with the proven broken symmetry of every dipole and dipolarity.

The energy flow is indeed received from the time domain, as we have argued {189} in a wave manner consistent with (i) quantum field theory as shown by Mandl and Shaw in the photon model {190}, (ii) broken charge conjugation symmetry of particle physics using the virtual photon and observable photon concepts, and (iii) a re-interpretation of Whittaker's decomposition of the scalar potential {191} when applied to the scalar potential between the ends of the dipole {12}.

We state the obvious: A dipole is a Maxwellian system. This gedanken experiment also proves by demonstration that a Maxwellian system — e.g., a dipole — is permitted by the laws of nature, physics, and thermodynamics to output more energy than the operator inputs, since we input nothing to the source dipole[62] once we have made it. After paying to produce the dipole initially, the operator has made no other energy input to the dipole at all, yet the dipole will continue to pour out observable energy in 3-space for the next 14 billion years if the dipole remains and is not destroyed. In addition, every positive charge and every negative charge in the universe form a dipole, regardless of the separation distance between them. That dipole is also performing the gedanken experiment process. Every dipolar EM circuit contains innumerable such dipoles — e.g., across "open paths" between the various points in the circuit, as shown by Kron {192}. Kron {193} stated:

---

[60] Obviously, we are utilizing the prevailing notion of the flow of energy through 3-space, which is actually a non sequitur. No 3-space observable entity can "move" in 3-space alone; it requires time to move, and so any movement is in 4-space a priori. We previously discussed this and the *dldt* operator being applied by the observation process. But for simplicity, we are using the conventional view here, so the negentropy of the dipole can be easily grasped.

[61] Again, we have stated the positive time case only. In the spreading special 4-circulation, energy appears in 3-space at each point dipole from the time domain (courtesy of the action of the negative charge of the dipole), and then returns from 3-space back to the time domain (courtesy of the action of the positive charge, which is a time-reversal of the action of the negative charge).

> *"... the missing concept of "open-paths " (the dual of "closed-paths") was discovered, in which currents could be made to flow in branches that lie between* *any* *set of two nodes. (Previously - following Maxwell - engineers tied all of their open-paths to a single datum-point, the 'ground'). That discovery of open-paths established a second rectangular transformation matrix... which created 'lamellar' currents... " "A network with the simultaneous presence of both closed and open paths was the answer to the author's years-long search."*

By considering all dipoles in the universe, one has in fact finally defined Kron's open path. One has also defined the master mechanism responsible for the incredible EM energy density of the vacuum — the so-called "zero-point EM energy". Overall, every electrical circuit thus has innumerable energy flow broken 3-symmetries in it, with respect to exchange of EM energy flow between the time and 3-space domains. To sum all these broken 3-symmetries to an overall net 3-symmetry during the discharge of the free excitation energy of the circuit, obviously requires some specific macroscopic cohering function in the circuit. Moreover, one exists. Specifically, the closed current loop between the external circuit attached to the generator and the internal source dipole created between the terminals of the generator, is what enforces the circuit's net 3-symmetry and Lorentz symmetrical regauging. That is an arbitrary man-made condition, and not a law of nature, physics, or thermodynamics.

---

[62] Or to a charge with its clustering virtual charges of opposite sign, if we redo the experiment with a single "isolated" observable charge and consider it more exactly as a set of composite dipoles, each of which exhibits broken symmetry in the vacuum virtual particle flux.

By our gedanken experiment's demonstration and the existence of innumerable disequilibria between the active environment[63] and the system in an ordinary EM circuit, it follows that a Maxwellian circuit must be *capable* of exhibiting a coefficient of performance (COP) of COP>1.0. It is a giant collection of open dissipative systems, far from equilibrium in the vacuum exchange.

That concept of course is contrary to the entire present mindset of electrical engineering and Maxwell-Heaviside-Lorentz classical electrodynamics. Those disciplines merely continue to accept the source charge as if it freely created from nothing all that energy in its associated fields and potentials reaching across the universe. Ironically, so long as the giant negentropy of the common dipole and its disequilibrium with its active environment (the local active vacuum and the local active curvatures of spacetime) are unaccounted, engineers and scientists will continue to produce the inane Lorenz/Lorentz-regauged power systems they produce today and have produced for more than a century. Also, they will continue — wittingly or unwittingly — to implicitly prescribe that every charge and dipole in the universe violates the conservation of energy law and is thus a *perpetuum mobile* of the grossest kind: a system which massively and continuously creates EM energy from nothing.

We now point out something deeper and very important. In modern physics, the *observed* positive charge is regarded as the time reversal of the *observed* negative charge. See Figure 3-2. If the negative charge is responsible for EM energy flow from the time-domain into 3-space, then *as observed* the positive charge must represent a time-reversed situation. We observe time reversal in the charge domain as a parity reversal and a charge reversal, but with the energy remaining positive. In other words, one imagines that one records a process on videotape, and then runs the video backwards to observe the "time-reversed" situation. When observed, both the sign of the positive charge and its direction of motion appear to us to be reversed from the negative case.

---

[63] In paragraph 3.10 and in Chapter 9 we will introduce — more deeply — the notion of the supersystem, consisting of three parts: (1) the system and its dynamics, (2) the active vacuum and its dynamics, and (3) the active spacetime curvatures and their dynamics. All three components of the supersystem interact with each other. In our gedanken experiment, the system (component 1) must receive the excess energy from the system's external environment, which consists of components 2 and 3 of the supersystem.

It follows that the positive charge as observed involves a flow of (positive) energy from 3-space back to the time domain. If we wish, before observation we can accept that "observed positive energy inflow" as an unobserved outward radiation of negative energy. Thus, a dipolarity involves a continuous flow of energy from the time domain into 3-space, and back from 3-space into the time domain (Figure 3-2). The energy flow circuit (circulation) is completed by a remaining energy flow across the dipolarity in the time-domain only, from the positive charge where the energy enters the time domain, to the negative charge where it exits again.[64]



- 4-spatial energy flow circulation between time domain and 3-space
- Broken energy flow symmetry in time axis and in 3-space
- Energy flow symmetry in 4-space
- A sort of "Lorentz symmetrical regauging" of 4-space
- Thus the EM energy in 3-space does not build-up and explode the universe

Nonobservable EM energy flux
Negative Charge
Vacuum's active virtual state
Time Domain
Observable EM energy flow
Positive Charge

- What spreads from the source charge or dipole is a circulation, and the polarization of the vacuum

Figure 3-2 Circulation of energy flow in a dipole, between time domain and 3-space.

---

[64] Rigorously, we should speak of +*qt* and -*qt*. Charge *q* is an observable, and therefore an instant frozen snapshot. No observable exists continuously in time, but instead it recurs continually as the photon interactions — iteratively producing the *d/dt* (LLLT) = LLL observations — continue. The moment a charge *q* absorbs a photon, it changes to *qt* in form. The moment the charge-time *qt* emits a photon, it changes back to *q* in form. This incessant change of *q* -> *qt* -> *q* -> *qt* —» .... is continual, at every level of the macroscopic charge, with its entire ensemble of photon interactions, including both virtual and observable photon interactions. As can be seen, the "charge as it persists" and "moves through time" has a rich dynamic substructure essentially ignored in present electrodynamics. It is, however, recognized by leading theoreticians and Nobelists.

However, even each of the clustering virtual charges and each of the differential charges of the observable charge, may be further broken into a central charge and clustering charges of opposite sign, in the modem view of the vacuum and its polarization. Hence, at any level — electron or positron — we actually have a dual and slightly separated bidirectional flow, at least in the observable equilibrium condition. The "positive energy" and positive flow of time is usually associated with "inert" matter with the electrons on the outside, so that the observer observes normal matter through the "forward time" situation mostly. Hence much of the accompanying backwards or time-reversed flow — from the positive charges in the nuclei, etc. — is "buried in the vacuum virtual state" in the Dirac sea and in Dirac sea hole flows.

Indeed, the vast hierarchy of nested structures and nested dynamics in charge as it exists in the vacuum, is recognized in physics, as is the fact that it involves infinite energy. E.g., quoting Nobelist Weinberg {194}:

> *"[The total energy of the atom]... depends on the* *bare mass* *and* *bare charge* *of the electron, the mass and charge that appear in the equations of the theory before we start worrying about photon emissions and reabsorptions. But free electrons as well as electrons in atoms are always emitting and reabsorbing photons that affect the electron's mass and electric charge, and so the bare mass and charge are not the same as the measured electron mass and charge that are listed in tables of elementary particles. In fact, in order to account for the observed values (which of course are finite) of the mass and charge of the electron, the bare mass and charge must themselves be infinite. The total energy of the atom is thus the sum of two terms, both infinite: the bare energy that is infinite because it depends on the infinite bare mass and charge, and the energy shift... that is infinite because it receives contributions from virtual photons of unlimited energy."*

Here again we have met Kron's "open path" in a new and unrecognized form.

Hopefully we now are in a position to rigorously define charge — or try to — for the first time in physics.[65] **Charge** is the ongoing circulation of EM energy flow between the time and 3-space domains, as seen by the observer. **Negative charge** is the ongoing absorption of positive EM energy input from the time domain (from ict), transduction of the absorbed energy into positive 3-space EM energy, and re-emission of the EM energy in all directions in 3-space. **Positive charge** is the ongoing absorption of EM energy input from 3-space, transduction of the absorbed energy into the time domain, and re-emission of the EM energy in the time domain. Or contrary-wise, one may regard the positive charge as the ongoing absorption *of negative* EM energy input from the time domain, transduction of the absorbed negative energy into 3-space, and re-emission of the negative EM energy in all directions in 3-space. The negative charge then absorbs the negative EM energy impinging on it from 3-space, and transduces it into negative energy flowing back into the time domain.

Any *overall* curvature of spacetime, as seen by the observer, results in one of the two flows *predominating* as seen by the observer. Usually, at COP < 1.0, this Dirac sea hole current does not bother our circuit's operation, but remains confined to the local vacuum. It is often not bothersome or is minor for other than very high COP's. The reason is that, for such moderate and small COP's, most of the Dirac sea hole currents react either with (i) the seething local vacuum virtual particle cauldron, or (ii) the atoms in the material lattice to form lattice holes.

As the COP increases, the fraction of Dirac holes interacting with the lattice to form lattice holes increases. As the COP further increases greatly, a large fraction of the Dirac sea holes do not react with the local vacuum cauldron (they become stable forms in that cauldron) or the lattice, but flow into the input section of the system to react with and "eat" incoming electrons from the external power source.

If the inflow of electrons is insufficient to fill the arriving Dirac sea hole current at the input section, the hole current passes back into the feeder line and into the distant power source, eating electrons all the while. This includes eating electrons in the distant power source, which simply "sees" that it must furnish additional current and voltage (power) toward the distant circuit or system.

---

[65] This is still a first order, macroscopic definition. For a more comprehensive statement, one must spell out the hierarchy and dynamics of the virtual state, the participating mass of the charged particle and its generatrix, the operations and dynamics of the *d/dt* observation operator, etc. We have not yet succeeded in getting all that into a single reasonable but sufficiently short statement!

In that operational COP region where strong interaction with the lattice occurs, the attachment of the lattice positron (lattice hole) to the mass of the atom or other ion, results in a very sluggish response of the overall ion with EM fields, compared to the response of an electron or a negative energy state electron hole (Dirac sea hole). Hence much of conventional electrical power circuit theory ignores the lattice holes and hole currents which no longer have negative energy because they have reacted and been "observed". Semiconductor designers, however, account for it and handle it in the semiconductor (in a given range of operation) primarily by the use of donor and acceptor materials.

At COP»1.0, however, the Dirac sea hole current must be strongly taken into account because it produces substantial and novel new effects in the power system itself. This Dirac sea hole current "flows in reverse" with respect to the circuit — from output back to the input. In short, it flows *through the vacuum* from the output section of a unitary COP»1.0 system, back through the middle section of the system, and back into the input section where it "eats" incoming electrons from the external power supply. The power supply thus must furnish electrons to "kill (power the killing of) the Dirac sea hole current arriving in the input section", while still furnishing the necessary amount of additional electrons to power the circuit's losses and loads.

The hole current arriving back in the input section of the unit poses an additional "power system load". These holes must be filled with incoming electrons (which disappear into the Dirac sea hole in the vacuum without radiation, due to the concomitant relaxation or change of the local curvature of spacetime) before any incoming electrons are left to power the circuit in normal fashion. So the hole current appears as a highly undesired extra "load" formed in the input and "eating input power from the external power supply".

We further discuss this situation and how to deal with it, in Chapter 9.

Finally, we propose a formal modification of the concept of "EM energy flow through space" (perhaps the first since its formulation independently by Heaviside and Poynting). The EM energy flow connected with the charge is a circulation of EM energy flow between the time domain and 3-space and back, *as a result of dipolarity*. This 4-circulation flow occurs at every point in 3-space (at every point dipole in the 3-space vacuum).

The formation of an observable charge results in an immediate, continuing, spreading re-organization (polarization) of the polarization of the vacuum virtual particle flux itself. It is this *spreading polarization of the vacuum* — and its accompanying giant negentropy EM energy flow circulation in 4-space connected with the spreading dipolarity and the observable "source" charge — that moves outward in all directions at the speed of light in 3-space from the newly formed charged particle or group of them.

We also define charge itself as that *continuously spreading dipolarity in 3-space*[66] accompanied by the giant negentropy EM energy flow 4-circulation from the time domain to 3-space and back.

The giant negentropy circulation in 4-space — represented by the spreading vacuum point-polarization and hence broken 3-symmetry — is what (observably) moves out in all directions from the newly formed observable charge. Since we "observe" only the 3-space aspect, we "see" it as the spreading appearance of 3-space EM energy (the polarization change of the vacuum itself) moving in 3-space, because we "see" it as the iteratively observed frames of a motion picture. *As observed,* that is one way of expressing it. As it actually *exists and happens prior to observation?*[67] the so-called "flow of EM energy in space" is not that at all. It is the radial spread of the appearance of a giant 4-space negentropy EM energy flow circulation between the dipoles formed in the polarization of space. In that process, the special 4-symmetry between time and space is maintained but with broken 3-energy flow symmetry and broken time-energy flow symmetry with respect to the 3-space observer.

---

[66] I.e., the spreading partial restructuring and re-organization of the vacuum energy or energy flux.

[67] The sharp-eyed reader will note that we clearly distinguish between the operation of a "tree falling in the forest" without an observer to see it, and a "tree falling in a forest" as an observer sees it. Without observation, there is no observed tree, no observer, and no "observed falling". Yet there exists the "tree x time", the "observer x time", and the "falling x time" whether or not their observation occurs with its resulting *d/dt* differentiation operation. One set (the causal set) is 4-spatial, and the other set (the event set after observation) is 3-spatial. The cause is 4-spatial and unobserved, and the effect is 3-spatial and observed. They are not the same, though related by the *d/dt* observation operator and by the interaction of the 4-space cause with a previous 3-space frozen observation to change it to a new 3-space frozen observation. Note that one can and does have a cause without an effect in any legitimate theory of causality, but not an effect without a cause. The cause only assumes the potential for interaction and observation, whereas the effect assumes that the interaction has occurred, yielding the observation as the effect.

The 4-circulation (giant negentropy) of the EM energy flow "from" or "connected with" a charge, is intimately connected with the spin of the charged particle, since the charged particle spins in both the time domain and in 3-space, as discussed in paragraph 3.3 below. We believe the spin itself is the basic giant negentropy generator.[68] If that hypothesis is true, then giant negentropy, the circulation of EM energy between time-domain and 3-space and back, broken 3-symmetry and broken time-energy symmetry (as seen by the observer), the flow of EM energy through space (as observed), the nature of charge itself, and polarization of the quantum mechanical vacuum are all just different sides of the same coin.

Without amplification, we state that his giant negentropy outflow process has additional important ramifications in electrodynamics, general relativity, particle physics, and unified field theory. However, we leave further discussion of the subject for a future paper or book and for the advanced theorists.

3.2 Reinterpreting Whittaker's Decomposition of the Scalar Potential

As previously stated, we applied and re-interpreted Whittaker 1903 decomposition of the potential {85} between the ends of the dipole. The scalar potential is actually a harmonic set of bidirectional longitudinal EM wavepairs, where each wavepair consists of an outgoing EM longitudinal EM wave in real 3-space and an incoming EM longitudinal EM wave in the complex plane. Hence we have a new and novel EM energy flow symmetry in 4-space, where (as seen by the observer) the broken 3-symmetry of the dipole has removed the usual arbitrary imposition of an additional condition of 3-space energy flow symmetry as well. Simply making a dipole permissibly breaks the 3-space conservation of energy flow symmetry, and moves to 4-dimensional conservation of energy flow. Both EM energy conservation in 3-space and in the time domain are individually broken, but conservation of energy flow is now upheld between the time-domain and the 3-space domain. In blunt terms, we "consume a little time" to get any EM energy that exists in 3-space.

---

[68] We leave to a future sharp young graduate student the business of expressing the angular momentum (spin) of the charged particle as a result of giant negentropy in EM energy flow between the time domain and 3-space. It can probably be done by deeply considering the giant negentropy process for an "isolated" observable charge considered as also containing its clustering set of virtual charges of opposite sign.

The broken symmetry of a source dipole — or of a source charge considered with its clustering virtual charges of opposite sign as a set of dipoles — produces a continuing giant 3-negentropy, as seen by the observer. He only sees the steady 3-space outpouring of energy, and sees that it will continue as long as the dipole or charge remains intact.


Polarized Vacuum
DIFFERENTIAL PIECE OF THE ELECTRON
OBSERVABLE ELECTRON
VIRTUAL (MOMENTARY) POSITRONS

Figure 3-3 Observable electron charge as a set of composite dipoles.

To clarify the "isolated charge" as a set of composite dipoles, see Figure 3-3. There is no such thing as an *isolated* observable charge in 3-space; instead, the observable charge is surrounded by attracted virtual charges of opposite sign in the active vacuum. We take a differential piece of the observable charge and a momentary virtual charge of opposite sign, and call the two a "composite dipole". An observable charge is simply a set of composite dipoles connecting virtual and observable energies and energy flows.

Hence any source charge (classical sense) may be considered such a set of composite dipoles. So any source charge also multiply initiates the broken 3-symmetry and broken t-symmetry in EM energy flow (as interpreted by the observer), but conserves energy flow 4-symmetry between the time domain and the 3-space domain. In 4-space, there is an energy flow circulation from the time domain to 3-space and back to the time domain again.

This special circulation of energy is strikingly similar to, and may be an extension of, Heaviside's unpublished theory of combined electrodynamics and gravity, where he used closed circulation of EM energy as exhibiting gravitational effects (in modern terms, producing spacetime curvature) {195, 172b.}. This approach or extensions of it may yet have a profound impact on physics, as commented upon by Laithwaite {196}. Certainly Heaviside considered his own energy flow theory. So it appears that he considered the excess energy flow — that "misses" the interaction with the circuit or assumed unit point charge and is not utilized — as producing gravity. That of course would be in perfect agreement with modern general relativity, since any change in the local energy density of vacuum is also a change in the local curvature of spacetime. We have called that Heaviside nondiverged and unaccounted EM energy flow by the label *dark positive energy*. See our further discussion of unaccounted (dark) positive energy in paragraph 3.8 below.


BOILER
STEAM TURBINE
GENERATOR
FLOW OF TIME-ENERGY IN VACUUM
giant energy flow wasted
−
ϕ
+
SOURCE DIPOLE IN GENERATOR
"Make dipole" function
(Entropic)
"True negative resistor" function
(Giant negentropy)

Figure 3-4 Dipole in generator powering circuits, taking energy from the time domain.

See Figure 3-4. This 4-symmetry is a far more fundamental energy flow symmetry than either 3-symmetry or t-symmetry. Both the "isolated charge" and the dipole are open systems far from equilibrium with their external active environment (the active vacuum and the active curvatures of spacetime). They are permitted to perform the five "magical" functions of disequilibrium thermodynamical systems. Such a system can: (i) self-order, (ii) self-oscillate or self-rotate, (iii) output more energy than the operator inputs, (iv) power itself and its loads (the "load" of a source dipole or source charge may be said to be comprised of the associated fields and potentials reaching across all space, and the continuous flow of energy necessary to maintain those fields and potentials), and (v) exhibit negentropy.

The source charge and the source dipole exhibit all five functions. We often refer to these characteristics of a charge or dipole as its *giant negentropy* functions {197}.

It only takes a single white crow to prove that not all crows are black. Every charge and dipolarity in the universe is already a Maxwellian system far from thermodynamic equilibrium with its local active environment — the very class of Maxwellian systems that Lorenz/Lorentz symmetrical regauging of the Maxwell-Heaviside equations arbitrarily discards. That local environment consists of the local curvatures of spacetime and the local active vacuum. The system together with the two components of its active environment is called the *supersystem*. All three components of the supersystem continuously interact with each other and exchange energy. All is dynamic, continuously. Any appearance of a "static state" in the system is actually an equilibrium condition stabilized in the ongoing supersystem dynamics.

So one does not have to "prove" that Maxwellian systems exhibiting COP>1.0 (even COP = ∞) are possible. Every charge and dipolarity in the universe is already just such a Maxwellian system, even though all such systems are erroneously discarded by Lorenz/Lorentz symmetrical regauging. Either one must accept asymmetry and COP>1.0 EM systems in electrodynamics, or one must purge from the theory all the charges and dipoles and all effects from them. That destroys all the charges, all the fields, and all the potentials.

That also destroys electrodynamics itself, as well as chemistry, particle physics, and most of modern science. The arch critic of overunity EM system research would do well to acquaint himself with some additional physics. Either that, or practice what he advocates, and give up all charges and dipoles and all effects from them — including in chemistry, particle physics, materials science, etc. When he holds on to the charges and dipoles while insisting on the impossibility of COP>1.0 Maxwellian systems, his cherished conventional EM theory eats itself by its own tail and becomes an oxymoron.

3.3 How the Dipole Charges Transduce Time Energy

We present a simplified analogy[69] that allows one to visualize how the dipole transduces the incoming time-like longitudinal EM energy flow into 3-space real EM energy flow for negative charge, or vice versa in the case of positive charge. With a little oversimplification, a charge may be said to spin 720° degrees in one complete rotation. For our purposes, it spins 360° in the imaginary plane (over in *ict),* and then spins 360° in the real plane (in 3-space). Thus the negative charge can absorb the incoming EM energy flow in the complex plane, transduce or "flip" the absorbed EM energy into 3-space to begin its 360 degrees in 3-space, and the excitation can decay during that 3-space spin part of the cycle. The only "variable" in *ict* is the t, so any energy flow has to be "by means of the variation of the t-variable". We already argued in a previous chapter that time can be treated as highly compressed spatial energy, having the same energy density as mass. So absorbing a very tiny amount of time-energy and transducing (decompressing) it into spatial energy produces enormous spatial energy *(t* multiplied by the factor c^2).

The negative charge absorbs a *little bit* of positive time energy, transduces it into a much larger amount of 3-space excitation energy, and re-emits it in 3-space as an observable, real flow of EM energy radially outward in all directions. The positive charge receives the large amount of 3-spatial EM energy and absorbs it, transduces it back into time-energy (highly compressed energy) and re-emits it in the time domain as a little bit of highly compressed time energy.

Conversely, we may consider that the positive charge absorbs a little bit of negative time energy, transduces it into a much larger amount of negative 3-space excitation energy, and re-emits this negative 3-space energy in all directions in 3-space. That consideration is important in the cold fusion phenomenology, and in fact accounts for the formation of little fleeting "time-reversal zones" in the electrolyte solution where the law of attraction and repulsion of charged particles is momentarily reversed. The omission of the giant negentropy mechanism and the negative energy mechanism from particle physics reaction theory is why there do not exist such nuclear transmutation actions at low spatial energy (but high time energy) in conventional particle physics. All such permissible reactions have been arbitrarily omitted from the discipline.

---

[69] **For** simplification, the analogy treats "spin" of the charged particle as if it really were something like that of a spinning top, at least in its 3-spatial component. However, in physics the entity **spin** is not confined to a flat plane or even to 3-space. C**onsequently,** we caution that the analogy is primarily a mnemonic aid.

For the positron (or any positive charge), we assume that the process is reversed: 3-space energy is continuously absorbed (from the active vacuum exchange) by the positive charge during its 360° spin in 3-space. This 3-space excitation energy is then flipped into the time domain as time-charge or time-energy, as the charge starts its second 360° spin in the time domain. During that latter part of its 720° spin cycle, the spinning charge re-emits the time-charge energy (time-excitation) as a flow of a little bit of very dense EM energy in the time domain.

The effects of these mechanisms in systems of charges in motion are met with as time dilation effects, spacetime curvature effects, frame rotation effects, etc. in relativity theory.

A charge that has received excess EM energy from the time domain is said to be *time-charged* or *time-excited.* Since time-charge or time-energy is c^2 denser than spatial energy, a tiny amount of time-energy excitation or time-charge may be re-emitted as substantial spatial energy over a period of time. In short, the decay of time charging or time-excitation of charged particles can occur slowly and over time. The decay is marked by the presence of longitudinal EM wave radiation, by mysterious ionization phenomena appearing in some Geiger counters depending on their individual time-histories (individual initial time-charging condition), and by excess energy appearing in electrolytes and emitted as heat where such decay of time-charge is occurring.

Usually in ordinary circuits and EM systems the time-charge and time-charge-decay effects are minimal, being offset by their opposites in close adherence to equilibrium. However, when this is not the case and time charging does appreciably occur, then novel phenomena result in those circuits and systems. Such effects have occurred for some time in instruments associated with rigorous electrolyte experiments at U.S. Naval research facilities at China Lake {198}, but the researchers have not recognized the cause. We have pointed out the time-charge and time-decay solution to those novel phenomena, and explained why apparently "identical" instruments need not respond to the stimuli in the same manner {199}. Along the way, we also explained several of the low spatial energy (thus high time-energy) transmutations, including giving the typical reactions producing the excess deuterium, tritium, and alpha particles. We also explain those new nuclear reactions at low spatial energy (but high time-energy) in Chapter 10.

As we stated in Chapter 1, paragraph 1.1.3: In such electrolyte experiments where the palladium electrodes load with concentrations of positive charges on hydrogen ions of one form or another, then in the adjacent solution there can arise fleeting **time-reversal zones.** Such a zone is simply a very tiny volume of fluid in which antiphotons temporarily comprise the majority of the ongoing photon interactions with the local ions in solution in that zone. The result is that the normal (time-forward) law of attraction of unlike charges and repulsion of like charges is reversed; *in the TRZ, like charges attract and unlike charges repel.* This allows two positive ions such as H+ to be drawn together so tightly that each enters the (reduced) strong force region of the other, forming a quasi-nucleus. When the other ions move to eliminate the TRZ, during the decay of the TRZ the strong force increases more rapidly than the EM force. Hence, the preferred method of decay of the now-excited quasi-nucleus is by quark flipping to allow the quasi-nucleus to become a new nucleus. This nuclear transformation interaction allows the production of the excess deuterium, tritium, and alpha particles.

3.4 Reordering of the Local Vacuum: Giant Negentropy

A giant negentropic reordering of a fraction of the surrounding vacuum's energy is initiated when a dipole or charge is formed. This reordering is deterministic, and is the 4-flow energetic structure shown by Whittaker {85}, slightly reinterpreted, with perfect coordination of the converging EM energy inflow in the complex plane with the outflowing converted real EM energy in 3-space. Hence this negentropic reordering introduces "hidden order" into the vacuum's otherwise disordered energy. This reordering of a fraction of the vacuum's disordered energy also changes the Gibbs statistics assumed in quantum mechanics, replacing it with an "already chaotic" statistics containing hidden order. We propose this as a possible contribution toward resolving the presently unsolved problem of the missing chaos in quantum mechanics {200}.

3.5 Some Implications of Giant Negentropy

Giant negentropy has many envisioned impacts upon physics, such as:

(a) Allows development and use of negentropic EM circuits (COP>1.0 systems) rather than entropic circuits. Once a broken 3-symmetry with stable 4-symmetry is established (as by forming a dipole), it continues indefinitely unless deliberately destroyed.

(b) Allows direct negentropic reordering of a practical and usable fraction of the vacuum's energy at will, at any point in the universe, easily and cheaply.

(c) Provides for electrodynamic engineering of the vacuum energy and of spacetime curvatures clustered in specific templates (the concept of vacuum engines or spacetime curvature engines). This has significant medical applications {387c}.

(d) Utilizes time as energy (per our previous discussion) and thus allows use of the Whittaker phase conjugate half of the biwave set as an EM energy flow within the flow of time. Observably this translates to the continuous receipt of free time-energy by the formed broken 3-symmetry (e.g., the charge or dipole). Accordingly, the charge or dipole continuously pours out real observable EM energy in 3-space, without any observable EM energy input (time is not observable, and neither is the time-polarized photon alone).

(e) Allows "burning a little time for fuel", so to speak, in order to transduce it into a very large spatial energy flow, due to the enormous compression of 3-spatial energy represented by time-energy by a factor of c^2.

So from the giant 3-negentropy discovery, we have arrived at some intriguing findings:

(a) As is well known in particle physics, the opposite charges of a dipole constitute a broken 3-space symmetry in the violent flux exchange between the active vacuum and the dipole.

(b) This dipole's broken 3-space symmetry in EM energy flow, provides a *relaxation* to a more fundamental EM energy flow symmetry between the time domain and 3-space, and therefore in 4-space.

(c) There is no law of nature or physics that requires 3-symmetry of EM energy flow as an additional condition applied to 4-symmetry of EM energy flow. Instead, 4-symmetry energy flow is more basic, by the hierarchy rule.[70]

---

[70] Quoting Steven Weinberg: *" ..there is a hierarchy of symmetries; whatever symmetry unites the gravitational and strong nuclear forces with the electroweak*

(d) The dipole is a practical and very simple means of "breaking" the additional 3-flow symmetry condition in EM energy flow our systems have previously exhibited, and relaxing to the fundamental 4-flow symmetry *without* 3-flow symmetry.

(e) So long as the dipole statically exists (e.g., imagine an electret suddenly formed, or a charged capacitor with no leakage), real usable EM energy circulation between time and 3-space, at each point in 3-space, will continuously move out from the dipole at light speed in all directions. In the view of the observer, at the same time, reactive EM power (actually, time-energy) will continuously flow into the dipole from the time-domain (the complex plane), and be transduced into real EM power output radially outward in 3-space from the dipole.

(f) Observably, a dipole or dipolarity and its scalar potential thus comprise a *true negative resistor* system of the most fundamental kind. The dipole continually receives EM energy in unusable form (reactive power, which cannot perform real work), converts it to usable form (real power, which can perform real work), and outputs it as usable, real EM energy flow (real power) in 3-space. Further, it spreads this "transformation of time-energy into 3-space energy at every dipole point" outward in 3-space in all directions.

(g) So at its formation the dipole initiates a continuing *giant negentropy* — a progressive reordering of a substantial and usable portion of the vacuum energy {201} that begins with dipole formation and continues. Further, this reordering of vacuum energy flow at every point in space continuously spreads in all directions from the initiation point, at the speed of light. Dipoles in original atoms formed shortly after the beginning of the universe, have been pouring out real EM energy for some 14 to 15 billion years or so (i.e., in the prevailing view; the age of the universe and whether it is expanding are still controversial {754}), and have reordered a fraction of the vacuum's energy, where the magnitude of the re-ordering varies inversely as a function the

forces is broken roughly a hundred million million times more strongly than the symmetry that unifies the weak and electromagnetic interactions. The puzzle of explaining this enormous difference in fundamental energies is therefore known in elementary particle physics today as the hierarchy problem." [Weinberg, *Dreams of a Final Theory,* Vintage Books, Random House, 1993, p. 205], radial distance from the dipole.[71] This is in fact the solution to the long-vexing problem of the source charge and its associated fields and potentials and their energy, reaching across the universe. The charge together with its associated clustering virtual charges is a set of composite dipoles, hence a multiple *broken 3-symmetry* energy flow system.

(h) If the dipole is destroyed, the ordering of the vacuum energy ceases, leaving a "separated chunk" of reordered vacuum energy dynamics that continues to expand at the speed of light in all directions, steadily reducing in local intensity as it expands.

(i) At any very small volume in space, from the dipole dynamics of the universe it follows that a great conglomerate of reordered vacuum flows and fluxes — some continuous, some chopped — is continually passing through that volume. Further, the situation is totally nonlinear, so that direct wave-to-wave interactions occur continuously amongst these energy flows and waves. We hypothesize that this is the actual physical mechanism constituting Puthoff's cosmological feedback mechanism {202}.

(j) Further, in 1904 Whittaker {203} showed that any EM field or wave pattern can be decomposed into two scalar potential functions. This initiated what is called *superpotential theory*. Each of the two potentials for those functions, of course, decomposes into the same kind of harmonic longitudinal EM wavepairs as shown in Whittaker 1903, plus superposed dynamics. In other words, the interference of scalar {204} potentials — each of which is actually a set of longitudinal EM waves, and not a scalar entity {205} at all, but a *multivectorial* entity — produces EM fields and waves and their dynamics. Hence we hypothesize that the Whittaker interference of the propagating reordered EM energy entities, continuously occurring at any point in space, generates the zero-point EM field energy fluctuations of the vacuum itself. Indeed, an AIAS group paper by Evans *et al.* {206} has already shown that just such "scalar interferometry" produces transverse EM fields and waves in the vacuum at a distance.

---

[71] The field energy density in the fields produced by the source charge varies inversely as the square of the radial distance. The potential energy density in the potentials produced by it will vary inversely as the distance.

Since energy can neither be created nor destroyed, there really are no true *energy sources* in nature in the sense that they *create* energy and pour it out {207}. Instead, what we call "energy sources" merely convert the energy already there in one form, into another form. All energy sources are no different from a solar cell in the sun, or a windmill in the wind, at least in principle. They are actually energy transducers rather than energy sources. This corresponds well with the conservation of energy law wherein not a single joule of energy can be created or destroyed. Instead, the form of that joule of energy can be continually changed. Every joule of energy present in the universe after its formation is still present, and is still doing joule after joule of work in iterative interactions with transducers that change its form.

A priori, we can measure no real 3-space input of EM energy to the unchanging charge but we can measure real 3-space EM energy pouring from it. Energy must be input to it from the active vacuum in a *nonobservable* form, and converted by it into an *observable* form that is re-emitted, usable, and produces what we call the "fields and potentials" and their energy, associated with that "source charge". As is common usage, we will continue to use the term "source charge" or "source dipole", but with the understanding that we refer to a special kind of *energy transducer.*

When we "make entropy", we must do work. Even so, doing work is not really entropic unless we also lose control of the energy[72] — whose form was merely changed by doing the work — and thence lose any *further* ability to use that energy (change its form, or transduce it) to do useful work. And when we observe entropy, we also do work in the observing. Some of the erroneous notions about entropy desperately need correcting. E.g., quoting Weinberg {208} for a lay definition of entropy:

> *"**..a certain quantity called entropy:** To define entropy, imagine that some of the system's temperature is very slowly raised from absolute zero. The increase in entropy of the system as it receives each small new amount of heat energy is equal to that*

---

[72] An interesting point is that energy is energy and remains energy. "Disordered" ultimately means "unusable" or "inconvenient" and nothing else. Disordered energy is still energy, and if we do not lose it from the system we can in fact have the **system** automatically reorder it, e.g. by use of simple retroreflection. The entire concept of entropy must be rigorously interpreted in terms of "energy whose reuse is lost", at least by the processes being performed by the system considered. In our view, "entropy" itself is just additional usually "lost" energy to be recovered.

> *energy divided by the absolute temperature at which the heat is supplied."*
>
> *"....entropy, which always increases with time in any closed system..."*

However, we point out that apparently there exists no completely closed system in the entire universe. In the notion of entropy and the escape of the energy from their "closed" system, thermodynamicists themselves ubiquitously negate the latter premise that entropy in a completely closed system always increases with time. That simply does not follow. The real situation is as follows: (i) Entropy in a half-open system with no allowed external input of energy, but with allowed escape of energy, does decrease with time if the energy of the system decreases with time by escaping.[73] Hence the cooling of "hot" water with time, if and only if the excess energy in the system can have a net escape to the (cooler) environment as time passes, (ii) Energy in a completely closed system (closed to both energy and mass), with no input and no output of energy at all, simply remains constant because it is not dissipated; simply apply the conservation of energy law. It may rearrange within, and the subcomponent energies may disorganize with respect to range, but the total energy remains. Entropy actually only deals with the loss of ability to utilize the energy. To wit, the assumed (and apparently true, so far as we can tell) conservation of energy in the present universe is an example. A closed system is in this sense a special case of a system in equilibrium with its active environment.[74] I.e., any "closed system" is such a special case.

---

[73] In case the reader has not thought of it, until the energy "escapes" it is not dissipating or dissipated from the dissipating "object". A "hot" object is energetically excited but not hot; the *energy dissipated* from it (including from every component within it) is scattering, and hence disruptive and "hot" in its interaction with a test instrument (or one's finger). The thermometer (or any other instrument) is external to the rest of the system (even if imbedded in it). Hence merely to "measure the temperature" is actually to pass energy out of the system into the thermometer (or other instrument), so that the thermometer measures the heat of the dissipating energy that has just escaped from the system. For these and similar reasons, Romer — former editor of *A. J. Phys.*— pointed out that "heat" should not even be used as a noun {84}.

[74] The concept of energy always requires that one can write "energy of. ..(X)" and fill in the (X). We usually write the phrase "of...(X)" as "X energy". Thus we write the phrase "energy of heat" as "heat energy," the "energy of the vacuum" as "vacuum energy", and the "energy of the EM entities" as "EM energy". At least in its usage, energy always requires a medium or entity "having" or "exhibiting" the energy. As Feynman pointed out, we really do not know what "energy" per se *is.*

(iii) In a system closed with respect to output (escape) of energy, but with the system opened only to allow external input of energy, the system energy will increase, simply by the conservation of energy law. That system's entropy will decrease and its negentropy will increase. (Its mass will also increase, and so it violates the thermodynamic misdefinitions of closed system; see Appendix A). It is well known that the entropy of an open system far from equilibrium cannot even be computed! (iv) Energy in an open system where input of energy and escape of energy both occur, may either increase, decrease, or remain constant, depending upon whether the input rate exceeds the output rate, or vice versa, or the energy input and output rate are equal. Therefore such a system can exhibit overall entropy, overall negentropy, or overall equilibrium, (v) Net energy scattering rate (rate of energy escaping the system in disordering fashion) from a hot system determines the observed temperature of that system at the time of observation. The system itself is cold, prior to escape of the energy. The "heat" is due to the interaction of the escaping energy with an external object, in its disordering fashion. Inside the system prior to escape, the energy is ordered hence cold.

A system in equilibrium in its exchange with its active external environment is in a state of maximum entropy *for that specific rate of energy exchange with its environment.* As we will point out in Chapter 9, by deliberately balancing the *system-and-vacuum* exchange with the *system-and-curved spacetime* exchange, so that the two exchanges are equal and opposite at a desired rate of exchange, one may establish (at least in theory) system equilibrium at whatever specific rate of energy exchange is desired.[75, 76] In this fashion, e.g., an "impossible" molecule normally intensely unstable and decaying in a nanosecond or less, can in fact be stabilized once an appropriate balance between the two opposing energy exchanges with the system is achieved at the required specific rate of energy exchange. This is actually a new Lorentz symmetrical regauging

---

[75] This is necessary, e.g., to close-loop a COP>1.0 EM unitary system taking its input energy from the vacuum, as we shall see in Chapter 6.

[76] The Fogal superluminal transmission system in fact uses a conventional signal input to change this "symmetrical regauging" condition in consonance with the amplitude of the input signal. Thus suddenly Lorentz symmetrical regauging becomes a way to transform a conventional signal into a signal consisting of changes in the stress energy potential of the vacuum. That constitutes a longitudinal EM wave, and so it is not limited by the speed of light. To use this process, a Fogal semiconductor must be used as the modulator in the "transmitter", and another must be used as the demodulator in the "receiver".

condition; change of symmetrical regauging is very useful in this fashion. In this way, a great new chemistry with reactions presently deemed impossible is in the offing, and it is already being developed by at least one U.S. company. We do not name the company, under our tacit agreement with the scientists doing the work.

To operate conventional entropic systems,[77] first we must input energy to the inert system to force it out of equilibrium and back into excitation (back into an asymmetrically rcgauged system, violating the Lorentz condition) so that it has some excess energy (and negentropy). Then we allow the decay of the excited system's excess energy to pass through a load and be dissipated from it, doing work for us by powering the load. Conventional systems usually do not recapture the "escaping dissipated energy" but just waste it. *"Dissipating" energy is merely allowing it to escape from the system and from further system control.* Then we brutally force more excitation energy into the system, opening it and breaking its equilibrium to do so. Again we dissipate the system's excitation energy in the load to produce some more work, usually wasting an appreciable fraction of the excitation energy.

In EM systems, it is a little more complex. We continually "switch on" a negentropic flow of EM energy from the vacuum by making a source dipole. In the circuit, we collect a small part of the resulting huge energy flow in space surrounding the circuit conductors. Then we use half the collected energy to destroy the dipole source of the energy flow, while less than half of the collected energy is dissipated in the load (the rest of that second half is dissipated in the external circuit's losses). Hence we must continually restore the source dipole and pay more to do it than we get out in the load as useful work. We make a perfectly good negentropic system, and then forcibly destroy its negentropic ability faster than we power the load and get any use out of it. That's a terrible way to make and use power systems, but it is what has been done for more than a century.

So with our present entropic EM systems (actually our *self-killing negentropic* EM systems) we continually wrestle nature fiercely to the mat, so to speak, by brute force, repeatedly, to bind her into 3-space EM energy conservation. All the while, nature protests our continual entropic brutality by providing the Newtonian third law reaction force[78] back upon our causative wrestler performing the "forcing". To do entropic engineering, we have to continually input 3-space energy to the wrestling mechanism or engine, losing a bit of the input energy in the inefficiencies, and fighting the "back emf", "back mmf", or Newtonian third law reaction that is nature's cry of protest all the while. Those are nature's penalties for imposing a monstrous 3-space EM energy flow symmetry[79] upon her as an *additional, highly undesired, and highly unnatural condition* added upon her beloved special 4-symmetry energy circulation between the time domain and 3-space.

---

[77] By "entropic system" we mean a system whose excitation energy decays and is dissipated from the system or at least from its further control, so that the entropy (lost or unusable energy) of the system continually increases until equilibrium (total decay of the excitation energy) is achieved. As can be seen, this also can be used to define entropy and increase in entropy. What is usually unappreciated is that *equilibrium is actually a counterbalance between ongoing entropy and negentropy.*

In short, because we so love entropic engineering and 3-space EM energy flow symmetry, we have to provide the continual input energy to our entropic processes by burning fuel, damming rivers, erecting windmills, building waterwheels, erecting solar cell arrays, building and charging chemical batteries, etc. In the process, we destroy and pollute the biosphere on a giant scale as we rip down forests, strip-mine and drill the earth, pile up thousands of tons of radioactive nuclear wastes —that will be hot for thousands of years — from our power plants and related facilities, and spew streams of pollutants into the atmosphere, the rivers, the oceans, etc. We do all that biosphere destruction because we inexplicably insist upon placing cruel chains on nature by brutally enforcing 3-space energy flow symmetry upon her. In the process, we adamantly require adherence to classical equilibrium thermodynamics (as given a somewhat altered explanation above, and also in Appendix A).

We do not have to do it that way. In avoiding solving the source charge problem for so long (more than a century), we have been extremely backward in our thinking and in our consequent development of entropic engineering technology.

---

[78] Note that Newton's third law reaction is implicit in the special negentropic energy flow circulation of the dipole, or of the charge considered as a set of composite dipoles. The same energy that moves into 3-space from the time domain, then returns from 3-space to the time domain, at every point in the 4-circulation. If we consider the positive charge as a "source" of negative energy, then there is a concomitant circulation of negative energy from the time domain to a point in 3-space, and back to the time domain.

[79] The 3-space symmetry of energy flow equilibrium is actually between the energy we input (from its external environment) to the system, and the energy that escapes from the system back into its external environment, either in its losses or in its loads. As we stated, equilibrium condition is a balance between ongoing entropic and negentropic operations.

For our dullness, we have had to pay and pay continuously for insisting on doing such atrocious entropic work and forcing nature to do it that way. In so doing, we "tie nature's feet" with that added arbitrary 3-symmetry in energy flow. We ourselves prohibit nature from performing the giant negentropy she so dearly loves and much prefers. We also arbitrarily and *meanly* discard the bountiful electromagnetic energy flow that nature loves to furnish us so freely by her vast preference for giant negentropy. We meanly discard nature's bountiful giant negentropy banquet free for the taking, by our vast thirst for giant entropy and doing violence to nature. Because we act like brutes instead of scientists, we destroy nature in spite of nature's continuing attempt to give us all the EM energy we wish, freely except for a little switching cost.

A far better way is to cooperate with nature and "let nature make her beloved copious negentropy" as she yearns to. To do that, we now can see the startlingly simple mechanism. We simply make a little dipole, *once*, entropically. So we have to pay for *making* the dipole, *once*, and we have to do just a little gentle violence to nature, *once*. Then we need do no more violence, if we just leave the dipole intact and do not destroy it. In short, we do have to tap nature gently on the shoulder. We do not have to brutally knock nature down to the mat, repeatedly.

When we make the dipole, we make a little bit of "broken 3-symmetry" in the universe's energy flow. Voila! Nature sings for joy at finally having her feet freed from the shackles of the horrid 3-symmetry energy flow. In great glee, she instantly relaxes into her dearly preferred giant negentropy and 4-symmetry. She instantly sets to re-ordering a substantial and usable

---

[80] E.g., so far as I am aware, there have been no funded research programs to discover how to deviate and collect some of the freely flowing energy from a permanent magnet or an electric dipole. Instead, electrodynamics has smugly continued to call it "statics" as if there were no dynamics, and ignored the giant negentropy circulation that is "seen" as the steadily outflowing field energy in 3-space, and erroneously called the "static field". There is no such thing as "statics" in the entire observed universe *a priori;* the very process of observation itself is dynamic. What we see as "static" is continual recurrence of a given condition or state or magnitude, as beautifully pointed out by Van Flandern {628}. One might even say that, not only is nature energetic, nature *is* energy, constantly changing and in motion in innumerable ways at once! One might even define "energy" as the process by which nature both acts and observes its actions, in every form and structure and possibility.

portion of the vacuum energy of the universe, in all directions at the speed of light, spreading her preferred giant negentropy EM 4-energy circulation flow from the dipole toward the ends of the universe at the speed of light. As long as we do not destroy the dipole (the broken 3-symmetry) that gently breaks the 3-symmetry shackles, nature's feet remain freed from brutal 3-space symmetry in EM energy flow. In that case, she delightedly continues to reorganize a portion of the vacuum energy, with the reordering spreading radially outward at the speed of light. Simply making a common dipole or charge[81] sets nature to going about reordering an ever-increasing fraction of the entire vacuum energy of the universe, and continuing indefinitely.

Simultaneously with freeing her from enforced 3-space EM energy flow symmetry, in great gratitude nature pours out an immense real EM energy 3-flow from that little dipole or charge. She will continue to pour it out forever for us, if we do not destroy the dipole or charge.

Instead of the present universal entropic engineering, the smart thing to do is make just a little bit of entropy wisely, using the work we get to break 3-space energy flow symmetry (basically, to make a dipole). *Then leave that mother of all negative resistors and free energy flow generators alone and forever unchanged!* Concentrate on intercepting, extracting, and using the free 3-space energy copiously flowing forth from the giant negentropy, without destroying the dipole that is freely providing it.

3.6 How Circuits Are Powered

Let us now look at the great magnitude of the energy flow that nature gives us from that dipole. We have to get into the subject a bit, because EM energy flow theory has been rather thoroughly confused for more than a century.

First, batteries and generators *do not* use their available internal energy — the shaft energy we input to the generator, or chemical energy available in the battery — to power the external circuit. Instead, each uses its available internal energy {209} to perform work on its own internal charges, forcibly separating the charges to form the *source dipole.*

See again Figure 3-4. *All the hydrocarbons ever burned, all the nuclear fuel rods ever consumed, and all the dams ever built, added not one single watt directly to the power line.* All the energy from those activities was input to the generator shaft after normal losses en route, to provide internal magnetic energy available to the generator. In turn, the generator used that available internal magnetic energy only to do internal work on its own internal charges to force them apart, forming the source dipole connected to the terminals. Generators are energy transducers only; they do not directly power their own external circuits.

---

[81] As we previously explained, a charge is just a set of composite dipoles.

Batteries and generators expend their internal energy available to them, to make the source dipole, and for no other purpose! None of their internal energy is used to power their external circuit. It never has been, and it never will be.

Once the source dipole is formed, it does all the hypothesized 4-functions we pointed out previously. It induces the spreading giant negentropic reordering of the vacuum energy, extracts (transduces) EM energy from the continuously reordering vacuum, and pours out from the terminals of the generator (or battery) a vast 3-flow (as observed) of EM field energy along the external circuit. As indicated by Kraus's illustration of the Poynting component {210}, this giant EM energy flow fills all space surrounding the circuit, out to an infinite lateral radius.[82] The energy flow is generally parallel to the conductors of the circuit. Only a tiny component of this flow — due to the surface charges of the conductors and the little boundary layer of energy flow that slides along the surface of the conductors — strikes the surface charges and gets diverged into the conductors (by the lateral withdrawal of the surface charges — with the "stub" or "base" of their field energies — laterally into the conductors. The electrons move mostly laterally, withdrawing from one side of the conductor surface to the opposite. Only the tiny component of its field vector integrated over that small distance is withdrawn into the conductors to power the electrons. This small amount of "withdrawn" energy is the diverged Poynting component, "collected" by the circuit. It also is the small component then used (dissipated) to power the Drude electrons and the circuit.[83] All the rest of that vast EM energy flow in the surrounding space, that pours forth from the terminals, just misses the circuit entirely. It roars on off into space and is wasted.[84]

---

[82] We accent that Kraus, along with other authors, only shows the 3-space *Poynting component* of that flow; i.e., he shows the very small amount of that external 3-space energy flow that is diverged into the circuit to potentialize the Drude electrons and power the circuit. Kraus *does not* show the remaining Heaviside component that is not diverged.

[83] As shown by Kraus, some of the energy flow at the various radial distances from the wire is withdrawn, as the surface electrons and the "stubs" of their near fields precess laterally into the depths of the wire when potentialized. Jackson, *Classical Electrodynamics,* Second **Edition,** Wiley, 1975, p. 223 also points out the nonlocal

The diverged, utilized, and accounted energy flow component — the *Poynting component* — is only a tiny, tiny fraction of the entire giant EM energy flow produced by the source dipole for every circuit.

3.7 The Heaviside Component vs. the Poynting Component

Unless Heaviside and Lorentz did rigorous calculations in a work we have not yet uncovered, we could not find any development of the functions and equations required for computing the numerical ratio of the unaccounted Heaviside "dark energy flow" {*nondiverged* energy flow component that misses the circuit), to the tiny Poynting energy component thai strikes the surface charges of the conductors {211} and is diverged into the wires to power the circuit when the surface charges precess laterally into the wire.

Consequently, we performed a very crude "special case" estimation {212} — a back-of-the-envelope type, with highly simplifying assumptions — for a very simple circuit in which one resistor is powered by a DC source. Our crude estimate showed that about 10^{13} times as much EM energy flow *misses* the circuit, is *not diverged,* and is *wasted* — as *strikes* the circuit, gets collected, and then is dissipated in the circuit to power the load and losses. Until electrical physicists re-examine the energy flow theory and

---

involvement of the transverse current. Quoting: *"...the transverse current... extends over all space, even if J is localized. "* One notes that present electrical power systems concentrate exclusively on the J current, making no attempt to collect and utilize the recognized but rather ignored transverse current.

[84] Note, however, that this Heaviside energy flow component differs from ExH. The Heaviside component is totally nondiverged (being actually in curl or swirl form), and since E and H are both diverged energy components assumed around an interacting unit point static charge, there is neither E nor H in the electrical engineering sense prior to interaction with charge. So the energy flow in both the Poynting and Heaviside components is in a force-field-free form until intercepted by and interacted with charge. Poynting's component, e.g., assumes only that energy component that does interact with charge and get withdrawn into the circuit. Heaviside's component assumes only that energy component that does not interact with charge and does not get withdrawn into the circuit.

again recover the Heaviside unaccounted component in it, that brute force estimate will have to suffice as at least an illustrative example.[85]

What does that 10^{13} ratio mean? For a little 1 watt generator of that DC type with that specific size conductors and that specific resistor, the Heaviside unaccounted energy flow component was about *10 trillion watts,* occupying all space surrounding the wire,[86] if all of it could be intercepted, collected, and used to power loads {213}. But the little circuit was only intercepting and collecting — and using to power loads — about 10^{-13} of the available energy flow surrounding the circuit, *if all* of it could have been intercepted, collected, and used to power loads.[87]

We have never had, and we do not now have, an *EM energy* shortage or problem. We never will have one, due to nature's bounty in providing us with the giant negentropy of the common dipole and of the charge considered as a composite dipole. Instead, we have the two problems that

(i) only a tiny, tiny component of the available 3-energy flow extracted from the vacuum (decompressed from time-energy) by the source dipole and poured out of the terminals of the power source, is caught and used by the circuit, and

---

[85] We would very much welcome a much more accurate functional expose by a capable higher group symmetry electrodynamicist!

[86] We also point out that none of this nondiverged energy flow component is accounted in conventional electrodynamics and electrical engineering (the closest it comes is Jackson's mention of the transverse current over all space), and neither has it been accounted or even investigated by biophysicists seeking to determine the effects of EM radiation and fields upon biological systems. We strongly suspect (and have done a little work on the problem) that these "force-free fields" and neglected excess "strange energy" flows do have interactions throughout the highly nonlinear cells of the body, and can indeed have profound long term effects on long-exposed biological systems. We particularly stress the potential for time-charging and subsequent *combined scalar and longitudinal photon pair* decay of time-charge excitation in the body. Several major areas of electrodynamics — such as the transverse current effects, Heaviside component effects, and internal Whittaker structuring (engines) effects of EM radiation — have not been investigated by the scientific community.

[87] We accent that time-energy may be regarded as spatial EM energy compressed by the factor c^2. Hence one second = 9×10^{16} joules of EM spatial energy, if decompressed by time-energy interaction with charge. The crude estimate for one circuit of 10^{13} times as much energy being wasted in the Heaviside energy flow component as is caught and used in the Poynting component, is thus quite reasonable when one recognizes that *all* the EM energy flow appearing in the circuit or outside it actually comes from the time domain, hence constitutes *decompressed time-energy.*

(ii) in the closed current loop circuit, half of that small spatial EM energy component that is intercepted and caught, is used by the circuit only to destroy the source dipole and cut off the free flow of EM energy from the vacuum faster than it powers the load.

We have previously discussed this further in several papers {214}.

One must occasionally keep one's sense of humor. The real problem that the Department of Energy should be working on, with massive resources, is simply the alteration of the closed current loop circuit so that it does not destroy the source dipole faster than it powers the loads. Secondly, they should then be working on how to close-loop the COP>1.0 EM systems that readily emerge from that research. Yet it appears that this fundamental energy problem — and the *only* energy problem — has no conventional work being openly done on it anywhere in the open Western world.[88]

3.8 Dark Positive Energy: The Unaccounted Heaviside Component

Now we restate a deceptively hidden thing: The EM field and potential are defined as the observed effect of the deviation from them by an assumed unit point charge. Then that same field and potential are assumed to be in mass-free space, before the interaction with charged matter. Hence the field and potential have each been defined erroneously as both a cause and an effect. This is a gross non sequitur. There is also a total lack of accounting that all EM energy in 3-space comes from the time domain. There is no consideration that every dipolarity and every charge represents a giant circulation of EM energy between time and 3-space. In ensemble, this non sequitur and these omissions are responsible for most of the present formidable foundations problems in electrodynamics.

---

[88] Using the U.S. as an example, the U.S. classified community is highly compartmented, and the real "organization" of a given compartment often consists of laterally connected "same clearance" compartments in multiple outside agencies rather than vertical chain of command through one agency. We accent that some highly compartmented "lateral" classified organizations in the West and elsewhere already have working COP>1.0 systems, and have had them for several decades. Some of these laterals in the U.S. are very dedicated to the duly elected government of the United States, with good national security reasons for the fact that they "officially do not exist". Some are not so dedicated at all, and have their own agendas having little if anything to do with official U.S. government policy. These latter "rogue" laterals often have convenient connections with outside shadowy groups of the High Cabal (Churchill's phrase). A similar situation exists in several other major foreign nations. Substantial electrodynamic technology has been developed (and weaponized) for decades, in secret, and this technology does not appear in the open news, the university texts, or the scientific journals. Such is the case for COP>1.0 EM power systems, which have actually existed in secret for decades.

We submit the following new hypothesis: *The present "definition" of field and potential as a function of interception and divergence by a unit point static charge are only indications of their point intensity, obtained as an estimate after their observed interaction with a unit point static charge.*[89] *Thus the actual field and potential contain not only their Poynting components that interact with the unit point charge, but also their Heaviside nondiverged components that do not interact with it. The true "magnitudes" of the massless field and potential prior to interaction with charged mass are many orders of magnitude greater than the magnitudes of their standardized point intensities* {215}.

In short, we propose that *every field and potential, in its interaction with charged mass, produces not only the accounted energy aspects presently calculated by electrodynamicists and astrophysicists, but also contains Heaviside's vast unaccounted "dark positive energy" component presently discarded.* We further propose that this ubiquitous and unaccounted "dark positive EM energy" component in the interactions of the fields and potentials of the spiral galaxies is what is producing the excess gravity that is holding the spiral arms together. We specifically do this in honor of Heaviside, whose unpublished papers clearly establish that he recognized the overwhelming gravitational importance of his extra and unaccounted energy flow component {172a, 172b, 196}.

3.9 A Short History of the Discarding of the Heaviside Dark Energy

3.9.1 Independent Work by Heaviside and Poynting

Let us now see how the enormity of the EM energy flow from the dipolar source was treated in the early electrodynamic theory, and how it is treated in the received view today.

---

[89] This is recognized by leading electrodynamicists, but not by most electrical engineers building power systems!

In the 1880s after Maxwell was already deceased, Poynting {216} and Heaviside {217} independently (and rather simultaneously) discovered EM energy flow through space. Before that, the concept did not appear in physics. Poynting {216} published prestigiously, while at first Heaviside published more obscurely {217}, then finally more prestigiously {218, 219}.

With respect to circuits, from the beginning Poynting assumed only that small amount of EM energy flow that enters the circuit from the surrounding space. Here are Poynting's {220} own words:

> *"This paper describes a hypothesis as to the connexion between current in conductors and the transfer of electric and magnetic inductions in the surrounding field. The hypothesis is suggested by the mode of transfer of energy in the electromagnetic field, resulting from Maxwell's equations investigated in a former paper ("Phil. Trans.," vol. 175, pp. 343-361, 1884). It was there shown that according to Maxwell's electromagnetic theory the energy which is dissipated in the circuit is transferred through the medium, always moving perpendicularly to the plane containing the lines of electric and magnetic intensity, and that it comes into the conductor from the surrounding insulator, not flowing along the wire."*

As can be seen, Poynting considered only the energy flow actually entering the wire, and subsequently being dissipated in the circuit. Hence Poynting never considered the huge EM energy flow component around the circuit that is *not* diverged, *misses* the circuit entirely, *does not* contribute to the energy dissipated by the circuit, and is *wasted.* In short, there is a vast "dark energy flow" associated with every dipolar interaction — a huge energy flow component which Poynting never considered.

Heaviside's theory was an extension of what Poynting had considered, and Heaviside also corrected Poynting as to the direction of flow. Heaviside was fully aware of the enormity of the "dark energy" flow missed by Poynting, but had absolutely no explanation as to where such a startlingly large EM energy flow — pouring from the terminals of every dipole, generator, or battery — could possibly be coming from. Consequently, Heaviside was very cautious in referring to it, usually doing so only obliquely in terms of the angles and components. In Heaviside's {221} own words:

> *"It [the energy transferflow] takes place, in the vicinity of the wire, very nearly parallel to it, with a slight slope towards the wire... . Prof. Poynting, on the other hand, holds a different view, representing the transfer as nearly perpendicular to a wire, i.e., with a slight departure from the vertical. This difference of a quadrant can, I think, only arise from what seems to be a misconception on his part as to the nature of the electric field in the vicinity of a wire supporting electric current. The lines of electric force are nearly perpendicular to the wire. The departure from perpendicularity is usually so small that I have sometimes spoken of them as being perpendicular to it, as they practically are, before I recognized the great physical importance of the slight departure. It causes the convergence of energy into the wire. "*

As can be seen, Heaviside was fully aware that the energy flow diverged into the wire was only a minuscule fraction of the total. He was fully aware that the remaining component was so huge that the energy flow vector remaining — after the divergence of the Poynting component into the circuit — was still almost parallel to the conductors. However, he had no explanation at all of where such an enormous and baffling energy flow could possibly originate.

Had Heaviside strongly stated the enormity of the nondiverged component of the energy flow, he would have been viciously attacked and scientifically discredited as a perpetual motion advocate. His words were measured and cautious, but there is no doubt that he recognized the enormity of the nondiverged EM energy flow component.

We have chosen to call that huge unaccounted component the "Heaviside dark energy component" in his honor, since he actually discovered it. By the word "dark" we mean "unaccounted", which hides it from scientific view. We have also nominated it as the previously unsuspected source of the extra gravity holding the arms of the spiral galaxies together.

3.9.2 Lorentz Disposed of the Problem Rather than Solving It

Lorentz then entered the EM energy flow scene to face the terrible problem so quietly raised by Heaviside. Lorentz understood the presence of the Poynting component, and also of the extra Heaviside component, but could find no explanation for the startling, enormous magnitude of the EM energy pouring out of the terminals of the power source (pouring from the source dipole) {222} if the Heaviside component was accounted. Had he retained and advanced this enormous dark energy flow component, even the great Lorentz would have been castigated as a perpetual motion advocate who did not accept the law of energy conservation. Even today, when one points out that far more energy is pouring out of the terminals of every generator than the small mechanical energy input to the shaft, one is immediately labeled a raving lunatic — even though the Bohren experiment {24} clearly proves the presence of an extra energy flow component not usually intercepted. It is not difficult to understand how such a bombshell would have been received in the 1880s! At least today, we have particle physics and its broken symmetry of opposite charges, together with its active vacuum, to explain where the excess energy comes from and how.

Unable to *solve* the dark energy flow problem by any rational means, Lorentz found a clever way to *avoid* it. He reasoned that the nondiverged Heaviside component was "physically insignificant" (his term) because it did not even enter the circuit. Since it did nothing of any physical consequences, or so he reasoned, then it could just be discarded.

So Lorentz simply integrated the entire energy flow vector (the vector representing the sum of both the Heaviside nondiverged component and the Poynting diverged component) around an assumed closed surface enclosing any volume of interest {223}. *A priori,* this mathematical procedure discards the dark *Heaviside* energy flow component because of its nondivergence. It retains only the intercepted *Poynting* diverged component that enters the circuit.

A century later, electrodynamicists are still happily avoiding the dark energy flow problem by continuing to use the Lorentz integration procedure {224} to dispose of all but the Poynting component that enters the circuit and is then dissipated by the circuit. As a result, the "Poynting energy flow" has come to be loosely regarded as "the" entire EM energy Mow, though electrodynamicists find it necessary to give stringent warnings about it. E.g., Panofsky and Phillips {225} state it this way:

> *"...only the entire surface integral of N [their notation for the Poynting vector] contributes to the energy balance. Paradoxical results may be obtained if one tries to identify the Poynting vector with the energy flow per unit area at any point."*

Most electrodynamicists note the freedom to add a vector — few call it an *energy flow* vector, though that is the type of vector being discussed, and one must add apples to apples — which has zero divergence. Jones {226} states:

> *"It* is *possible to introduce the Poynting vector S, defined by S = ExH, and regard it as the intensity of energy flow at a point. This procedure is open to criticism since we could add to S any vector whose divergence is zero without affecting [the basic integration procedure's result]."*

Jackson {227} says it even more plainly, and also uses Lorentz's "no physical significance" argument for disposing of any energy flow vector with a zero divergence. Quoting:

> *"...the Poynting vector is arbitrary to the extent that the curl of any vector field can be added to it. Such an added term can, however, have no physical consequences."*

Any energy flow vector, which is the curl of a vector field, will have zero divergence, by elementary vector algebra. In short, to be pertinent at all, it must be an *energy flow* vector (since energy flow is what S = E x H is all about. Since the curl of any vector has no divergence *a priori,* then any energy flow vector that is a curl of a vector field will be part of the Heaviside dark energy flow component, rather than part of the Poynting energy flow component. It will also be discarded by Lorentz's closed surface integration.

We refer the reader again to Figures 2-5 and 2-6 in Chapter 2, p. 113-114. Electrodynamicists err in assuming that such a divergent free vector (energy flow) can have no physical consequences. If one inserts *additional intercepting charges* into that formerly nondiverged energy flow component, the charges will immediately diverge some of the formerly nondiverged energy flow around them and hence "collect additional energy". In other words, "divergence" is the result of a physical process, accomplished by intercepting charges. We can easily change "nondiverging" energy to diverging energy, by simply interacting it with charges. We can also "bunch" the energy flow lines closer together (as in some waveguides), thereby increasing the local flow intensity and the concomitant energy collected by each intercepting charge in the densified energy flow stream.

So whether the Heaviside energy flow component is of physical consequence or not, depends on whether or not we "add more sail to the sailboat", or "add more sailboats" before the wind. That is most certainly a useful physical consequence, and with a little ingenuity we ought to be able to use it to power loads "for free" or nearly so. There are other consequences also, as we used in deriving the negentropy of the dipole or charge. There the input of a non-Poynting energy flow component certainly has universal and physical significance — e.g., to the curving of local spacetime, conditioning the active vacuum, furnishing all the energy to form the EM fields and potentials from their source charges, etc.

Schwarz {228} expresses it this way:

> *"There will be many opportunities in which the interpretation ofE xH as a rate offlow ofenergy per unit area will be profitable. In most cases ofpractical interest, such an interpretation is valid, although it must always he kept in mind that only the integral of S over a closed surface can be physically measured... Just how it is that the connections to the energy source, say a battery, are at the ends ofthe wire, yet energyflows in through the sides, should be pondered by the reader. "*

Note carefully that Schwartz recognizes the difference between the observed (deviated or diverged) part of the EM energy flow and the unobserved nondeviated or nondiverged part of it. However, he did not follow it up and apply it back to the basic "definition" of the field and potential as what are diverged from them.

For recommended changes to the Poynting vector, Jones {229} presents many conditions the changed vector must fulfill. Then he falls back on the Lorentz closed surface method again, but without realizing that he therefore (i) first includes both the diverged and nondiverged component, and (ii) invokes a procedure that arbitrarily discards the nondiverged component. In thus disposing of the problem, Jones says:

> "It *does not seem likely that an expression satisfying all these conditions will be simple........fortunately, we are rarely concerned with the energyflow at a point. In most applications we need the rate at which energy is crossing a closed surface."*

Finally, we note that even today, a debate on what the Poynting vector is or should be, is still politely ongoing. As an example, it has been ongoing for more than 40 years in the *American Journal ofPhysics* alone as well as in other journals {230a-230i}. One thing is clear: The Poynting vector does not represent the total energy flow at right angles through a square meter in space surrounding the conductors of the electrical circuit. It is, however, the *component or fraction* of that actual energy flow through the square meter in force-field-free form *that will subsequently be diverged and collected in the circuit in force-field form and dissipated in the circuit loads and losses.*

3.10 The Problem of the Accelerating Expansion of the Universe

As briefly stated earlier, we introduce the notion of the supersystem, consisting of three parts: (i) the system and its dynamics, (ii) the active vacuum and its dynamics, and (iii) the active spacetime curvatures and their dynamics. All three components of the supersystem interact with each other.

In Chapter 9, we explain in some detail how a COP>1.0 EM circuit — and especially a COP»1.0 EM circuit — has an induced flow of negative energy (Dirac sea hole current) from the output section of the system, back through the system, and into the input section. Reaching the input section, if the hole flow is not completely filled by incoming electrons, the remaining Dirac hole current will flow on back into the feeder line from the external power supply, and into the distant power supply itself, eating electrons and electron current all the while.

We also explain our reinterpretation of the *unobserved* (non-reacted) Dirac hole with negative energy or negative mass, without time reversal and parity reversal. This dramatically differs from the "as observed" (interacted) Dirac positron with positive mass, and with charge-reversal and parity reversal from the electron. The Dirac hole is "as unobserved and non-reacted" and it is still an *electron* having negative mass and negative energy. The Dirac positron with positive mass, opposite charge, and opposite direction is "as observed and reacted with charged matter". The unobserved Dirac hole is the "cause" of an observational interaction; the Dirac positron is the "effect" of an observational interaction. The two are very different because the cause differs from the effect. Here again, the confusion of cause and effect has had very detrimental consequences in the use of Dirac's electron theory.

Very powerful astronomical phenomena, such as giant astronomical explosions of great energy, involve COP>1.0 and COP»1.0 processes, particularly when the unaccounted Heaviside energy flow is accounted for every field and potential interaction with charged mass. Hence all such phenomena also provide very powerful "explosions" of negative energy

(Dirac sea holes moving outward in the vacuum). The negative energy is the equivalent of negative mass, so long as it is unobserved.

So there is a "dark negative energy explosion" in the Dirac Sea vacuum, accompanying every large astronomical explosion seen through our telescopes and other sensors. This accompanying dark negative energy explosion has not been accounted in astrophysics until now.

We thus live in an astronomical universe of neglected "giant dark negative energy explosions" as well as one of accounted "giant positive energy explosions".

The dark (unaccounted) negative energy radiating outward in the vacuum from gamma bursts, x-ray bursts, etc. produces antigravity. The spreading negative energy, moving at light speed, is a change to the vacuum itself, which also interacts upon spacetime to negatively curve it, producing negative gravity. For those energetic processes of COP sufficiently greater than one, the processes produce more antigravity than gravity. As of this writing, we are in fact filing a patent application on this method of performing and producing antigravity, and it will be filed before this book is published.

Over the 14 billion or so years of the observed universe, the dark negative energy content of spacetime has been slowly changing by the results of giant astronomical explosions and other such processes producing negative energy radiated outward into the Dirac sea vacuum. Slowly the vacuum itself has undergone transformation from the perfect Dirac sea with all holes filled by particles, to a vacuum where there is a slowly growing fraction of negative energy (negative mass) unobserved Dirac sea holes.

Thus, slowly the antigravity generated by the gradual altering of "space" (the vacuum) itself has been growing for some 14 billion years. At some point in the past, the excess antigravity effect accumulating in space reached the equal of the "outside" gravity acting upon energetic explosive astronomical phenomena. From that point in time, the antigravity effect has been increasing slowly. The result is that the present violently explosive astronomical phenomena, by adding a sudden and sharp increase in their external space antigravity, produce acceleration away from all positive mass and positive energy phenomena. Hence astronomers now observe the acceleration of the expanding (positive energy/positive mass) universe, instead of the previously expected slowing (due to positive gravity) of the expanding universe (conventional view).

The antigravity-producing phenomena have not been openly investigated in Western science because Western science has arbitrarily discarded COP>1.0 EM systems, primarily with the Lorentz regauging of the Maxwell-Heaviside equations. Hence, Western science has not experimentally studied the type of system that produces the effect in the first place.

On the other hand, it is possible to directly investigate the antigravity-producing phenomenology on the laboratory bench, by utilizing overunity EM systems with very high COP (e.g., COP = 10^6 or more). The Sweet experiments {231} did in fact produce such phenomenology on the laboratory bench, but these experiments were privately performed under proprietary conditions {232}. We discuss the Sweet experiments and device in a later chapter.

In science, such experiments are quite properly deemed interesting but anecdotal until replicated independently. Similar experiments should certainly be repeated by the scientific community, using various interactions (some given in this book) that develop COP>1.0. The problem is nowhere near as difficult as hot fusion, but it has not been tackled and overcome because of (1) the prevailing and erroneous scientific mindset against COP> 1.0 electromagnetic processes, and (2) the present "kill" of the supersystem and its effects in the standard U(1) electrodynamics model.

In Chapter 8 we further discuss the antigravity effect in practical or potentially practical systems where COP » 1.0.

3.11 In Conclusion

In this Chapter, we have stressed what we believe to be a great new principle of giant negentropy, leading to direct and easy extraction of EM energy from the vacuum in copious quantities. That principle is that nature retains *her preferred 4-symmetry* of EM energy flow, while breaking 3-symmetry of EM energy flow and the symmetry of EM time-energy flow on the fourth axis. It is implemented by making a common dipole or charge.

The electrical energy problem is *not* due to any difficulty in inducing giant and indefinitely continuing EM energy flows from the vacuum! The easiest thing in the world is to extract EM energy — any amount, anywhere, anytime — from the seething vacuum, by making a simple dipolarity. The problem is only in then intercepting and collecting some of the energy to dissipate in loads, and doing it *without* using half the collected energy to destroy the dipole producing the energy, faster than the loads are powered. In other parts of this book we have given some of the many mechanisms that can be applied to attack this "power the load without killing the source dipole" problem, and have also included such in papers in the literature {233a-233u}.

We have pointed out the implications of the new principle of negentropy in EM energy flow, and how all our circuits and electrical power systems actually use it but then arc designed so as to kill the negentropic process's potential for self-powering electrical power systems.

Presently we are told by the conventional scientific community that the dream of freely extracting EM energy from the vacuum, and using it to efficiently and easily power our electrical needs cleanly, is either a fool's concept of perpetual motion, or the science of the next century. It is neither; it is good physics, and it is already *present and misused* in all our electrical power systems and circuits — and always has been. Unlimited electrical energy from the vacuum is here and now, if we but overcome the prevailing mindset and grasp it.

We have argued that all electrical loads and circuits are now and always have been powered by just such EM energy extracted directly from the vacuum by the giant negentropy principle, evoked by the source dipole. We have removed the artificial and erroneous notion that batteries and generators provide some of their available 3-space internal energy to the external circuit. Instead, we have emphasized that batteries and generators dissipate their available energy to form and then continually reform their source dipole, and nothing else. Once their source dipolarity is formed, a battery or a generator is nothing but an energy gate, gating and transducing enormous EM energy from the vacuum. We only have to keep inputting energy to keep reforming the dipole that our external circuit is designed to destroy faster than the load is powered.

In dealing with the function of the dipole in extracting the EM energy from the vacuum and pouring it out to power the circuit, we have shown errors in present energy flow theory and how they came to be made. We also indicated the enormous magnitude of the EM energy flow actually **extracted** and present with every conventional circuit, but wasted and **arbitrarily** removed from accountability. Some processes for intercepting, co**llecting,** and using additional amounts of this available Heaviside "dark EM energy" flow component, surrounding every circuit, have been mentioned, and references have been given to other papers more fully discussing such processes. In a previous paper {234} we have proposed that the Heaviside dark energy, accompanying all EM field-charge interactions, is responsible for the excess gravity observed to be holding the spiral arms of those distant spiral galaxies intact — in short, we have proposed an unaccounted Heaviside *dark positive energy* solution to the well-known *dark matter* problem in astrophysics.

The ordinary closed current loop circuit inherently yields a system COP<1.0, because it destroys its source dipoles faster than it powers the load. Indeed, the circuit self-enforces the Lorentz symmetrical regauging condition during discharge of its free excitation (potential) energy.

In addition, we have presented an hypothesis to explain that negative energy (negative mass) created in the Dirac sea vacuum by giant astronomical explosion phenomena produces the excess antigravity in the space surrounding those entities that is accelerating the expansion of the universe. We have also indicated how this hypothesis can be investigated and tested on the bench. We have provided one experiment whose results did support the hypothesis.

The present world energy crisis is real and increasing, while at the same time the availability of oil is beginning to decrease and oil becomes more costly.[90] Unless a substantial fraction of the "electricity from oil" curve is shifted to "electricity from the vacuum" rather quickly, the economic collapse of the Western world, followed by concomitant collapse of other economies, may ensue within a surprisingly few years, and even within the present decade.

---

[90] As this was first being written in Dec. 2001, there was a temporary relief in the oil crisis, due to the sudden decrease in travel, air traffic, etc. after the terrorist attack on Washington and New York on September 11, 2001. As the present war on terrorism has continued, the MidEast is now heating up toward another war, and oil prices are again trying to climb. Iraq, Iran, and Libya called for an oil embargo on the United States, for example, which would almost immediately plunge the nation into an oil crisis. Meanwhile, should effective terrorist attacks occur upon the highly vulnerable energy distribution infrastructure of the United States and other allied nations, the oil crisis will again emerge catastrophically and almost immediately thereafter. It is held off for now, only because Russia under Putin is seeking U.S. financial assistance to further develop its rich oilfields. When OPEC votes to curtail production and then curtails it, Russia opens the spigot and keeps the prices down. Putin is seeking to become a trusted U.S. oil partner, in the role long played by Saudi Arabia but now declining due to perceived Saudi payments to terrorist organizations and reluctance to close down terrorist activities in their own country. So in a strange way, a new alliance between the U.S. and Russia has prevented the oil and energy prices from escalating right through the roof.

We believe that a transfer of much of the "electricity from oil" curve to an "electricity from the vacuum" curve can be quickly accomplished, if the government and the scientific community can be induced to move with full priority and vigor in the directions indicated in this book. However, to get that done, it apparently will be done over the writhing bodies of our leading scientific organizations, literally dragging the organizations to face the proven fact of giant negentropy of every charge and dipole in the universe over their strenuous objections.

As a major objective, we fervently hope that undergraduate students, graduate students, post-doctoral scientists, other scientists, engineers, and environmentalists will interest themselves in these new principles and viewpoints. We have called attention to the new electrodynamics pioneered by AIAS, Evans, Sachs, Barrett, Lehnert, and others, and indicated the capability of this emerging electrodynamics to model this new *energy from the vacuum* functioning.

It has been said that no idea is accepted until its time has come. We strongly believe that the time for cheap, clean extraction of electrical energy from the vacuum is an idea whose time has arrived. Hopefully our efforts in this book will at least conceptually show the interested reader the outline and course that energy from the vacuum can and will take in the scientific community and in the world at large.

We accent again that modeling the extraction of EM energy from the vacuum demands the use of higher symmetry electrodynamics, particularly a theoretical model capable of expressing the interactions of the three components of the supersystem. Barrett and Grimes {235} said it beautifully:

> *"In the case of electromagnetism, the theory was first simplified before being frozen. Maxwell expressed electromagnetism in the algebra of quaternions and made the electromagnetic potential the centerpiece of his theory. In 1881 Heaviside replaced the electromagnetic potential field by force fields as the centerpiece of electromagnetic theory. According to him, the electromagnetic potential field was arbitrary and needed to be "assassinated" (sic). A few years later there was a great debate between Heaviside and Tait about the relative merits of vector analysis and quaternions. The result was the realization that there was no need for the greater physical insights provided by quaternions if the theory was purely local, and vector analysis became commonplace.*

> *The vast applications of electromagnetic theory since then were made using vector analysis. Although generations of very effective students were trained using vector analysis, more might be learned physically by returning, if not to quaternions, to other mathematical formulations in certain well-defined circumstances. As examples, since the time when the theoretical design of electromagnetism was frozen, gauge theory has been invented and brought to maturity and topology and geometry have been introduced to field theory. Although most persons view their subject matter through the filter of the mathematical tools in which they are trained, the best mathematical techniques for a specific analysis depend upon the best match between the algebraic logic and the underpinning physical dynamics of a theoretical system. "*

The problems we face today are ever more demanding of the necessary EM change pointed out by Barrett and Grimes, along with many others. Let us hope their words are heeded. Given rapid development of higher group symmetry electrodynamics models, we shall very rapidly see the solutions to many previously intractable human problems — including cheap clean energy from the vacuum, understanding and directly using antigravity as well as gravity, a revolutionary new medical therapy, a new chemistry and biochemistry, and a new appreciation for the electromagnetic interactions of mind and matter.

Let us hope this new scientific revolution comes swiftly.

Chapter 4

Setting the Stage for Understanding Overunity Power Systems

[Dissipative structures] *"This leads precisely to a distinction between 'equilibrium structures' [which may be understood in terms of classical equilibrium thermodynamics] and 'dissipative structures'. The latter are formed and maintained through the exchange of energy and matter in non-equilibrium conditions."* [I. Prigogine] {236} [Internal brackets added for clarity.]

[The energy in space itself] *"What might appear to be empty space is, therefore, a seething ferment of virtual particles. A vacuum is not inert and featureless, but alive with throbbing energy and vitality. A 'real' particle such as an electron must always be viewed against this background of frenetic activity. When an electron moves through space, it is actually swimming in a sea of ghost particles of all varieties — virtual leptons, quarks, and messengers, entangled in a complex melee. The presence of the electron will distort this irreducible vacuum activity, and the distortion in turn reacts back on the electron. Even at rest, an electron is not at rest: it is being continually assaulted by all manner of other particles from the vacuum."* [Paul Davies] {237}

[Modernizing the fluid analogy of EM]. *The intensity of the vacuum virtual particle flux may be treated as the intensity of a potential, thus by analogy corresponding to pressure in a fluid. Polarity (charge) is a process for establishing a change in the intensity of the vacuum potential — and thus a change in the ambient pressure of the vacuum fluid. Difference between vacuum pressures at two separated points creates a force upon any charge placed between those two points. Just as a differential in pressure between points in a fluid induces currents, a differential in vacuum pressure induces energy flow currents in the vacuum fluid, which are called 'fields'. All*

EM circuits, charges, potentials, and forces in electrodynamics involve altering the vacuum to include altering its pressure and thereby producing the forces that the resulting pressure gradients (fields) induce upon charges. All observable EM energy in space is EM energy intercepted and collected on charges, and it comes from the vacuum via these fundamental vacuum-engineering dynamics." [T. E. Bearden, private communication to a colleague, 2001].

[Impact of EM energy from the vacuum.] *"If they [quantum fluctuations of vacuum] can be [tapped], the impact upon our civilization will be incalculable. Oil, coal, nuclear, hydropower, would become obsolete — and so would many of our worries about environmental pollution." "Don't sell your oil shares yet — but don't be surprised if the world again witnesses the four stages of response to any new and revolutionary development: 1. It's crazy! 2. It may be possible — so what? 3. I said it was a good idea all along. 4. I thought of it first."* [Arthur C. Clarke] {238}.

[Broken symmetry of opposite charges.] *"Since nonobservables imply symmetry, any discovery of asymmetry must imply some observable. The experiment of Wu, Ambler, Hayward, Hoppes and Hudson... established the asymmetry between the positive and negative signs of electricity."* [T. D. Lee] {239}.

[On implications of asymmetry of opposite charges of a dipole.] *"In particle physics, the proven asymmetry of opposite charges establishes that the source dipole — with opposite charges on each end—* is *a broken symmetry in the violent virtual photon flux of vacuum. The dipole charges constantly receive and absorb virtual photon energy from the seething vacuum, and re-emit that excitation energy. By the very definition of broken symmetry, some of this absorbed* *virtual* *energy must be integrated into* *observable* *3-space EM energy, and emitted by the dipole in observable form, in all directions in 3-space. Hence there is a rigorous basis for the source dipole extracting virtual EM energy from the vacuum, integrating it, and continuously pouring it out in* *observable and usable EM energy form. It has been in particle physics since 1957, being certified by the award of the Nobel Prize to Lee and Yang in that year. "* [T. E. Bearden, private communication to a colleague, 1995.]

[On powering an electromagnetic circuit] *"In the United States there is not now, and there never has been, a single electrical engineering department, professor, or textbook that knows and teaches what directly powers an electromagnetic circuit. Neither is it in any publication of the National Academy of Sciences, National Science Foundation, National Academy of Engineering, Department of Energy, or the great national laboratories. Yet the proof that every circuit is powered by EM energy extracted directly from the vacuum has been in particle physics for 45 years, since the award of the Nobel Prize to Lee and Yang in 1957, following the experimental proof by Wu et al. earlier that same year. "* [T. E. Bearden, private correspondence, 2002].

4.1 Introduction

In this chapter, we present a selection of potential overunity notions, some inventions, and some experiments. Its purpose is to show some of the more relevant work that has been done, and hopefully to stimulate new thinking by the interested reader. Much of the work addressed is by other inventors and scientists, and we give an appropriate commentary from our viewpoint. Not all the concepts presented can be clearly explained, though some can and are. This is not intended to be a "kit of parts" or an "assembly instructions" type of presentation. For that, the interested researcher will have to rely on his or her own ingenuity and lots of bench experiments, because no such "kit of parts with instructions" for COP>1.0 electrical power systems exists at present {240, 241}.

Because of the broken symmetry of its opposite charges, we do know that any dipolarity — such as a permanent magnet, a charged flat-plate capacitor, an electret, or a simple EM scalar potential — continuously pours out EM energy circulation extracted from the vacuum. E.g., see Figure 4-1, which shows a very simple "free energy generator" that will generate a flow of EM energy indefinitely, even by ordinary U(1) electrodynamics theory (by standard Poynting theory). E.g., quoting Buchwald {242}:

> *"[Poynting's result] implies that a charged capacitor in a constant magnetic field which is not parallel to the electric field is the seat of energy flows even though all macroscopic phenomena are static."*

This is easily seen by applying the standard Poynting formula, S = E x H. With the H-field of the magnet at right angles to the E-field of the capacitor or electret, the Poynting flow of energy S is maximized and orthogonal to E and to H.

The problem is not in extracting energy - even enormous energy — from the vacuum The problem is collecting and using the energy to power loads, without destroying the source dipole



EM energy continually flows from this "static" arrangement, without any further input of energy by the engineer.

Figure 4-1 Poynting generator providing endless EM energy flow from the vacuum.

Buchwald errs, e.g., in assuming the macroscopic phenomena are static. They are not; they are highly dynamic in the same sense that a perfect macroscopic whirlpool in a river, seemingly static, nonetheless involves a continuous flow of water through it and a continuous dynamics. So far as can be observed, it appears there is no such thing as a truly "static" object. As an example, just to "exist" an object must "travel through time", which is itself a special kind of dynamics in the time domain.

A beautiful explanation of what is meant by "static" is given by Van Flandern[91]:

> *"To retain causality, we must distinguish two distinct meanings of the term 'static'. One meaning is unchanging in the sense of no moving parts. The other meaning is sameness from moment to moment by continual replacement of all moving parts. We can visualize this difference by thinking of a waterfall. A frozen waterfall is static in the first sense, and a flowing waterfall is static in the second sense. Both are essentially the same at every moment, yet the latter has moving parts capable of transferring momentum, and is made of entities that propagate."*

Now suppose that the capacitor in Figure 4-1 is rotated until E and H are either parallel or anti-parallel. In that case, the Poynting theory predicts zero EM energy flow. That is an incomplete assessment; it means that there is no overt field energy flow. There is, however, still quite a lot of covert or "infolded" field energy flow ongoing anyway, inside the static fields E and H themselves.[92] To see this, we first turn to the static potentials.

Between the charged plates of the capacitor or electret, there exists an electrostatic scalar potential ϕ. Between the polar ends of the permanent magnet, there exists a magnetostatic scalar potential Φ. We may independently decompose both ϕ and Φ via Whittaker decomposition {243}, applying a necessary correction {244} to Whittaker's interpretation. Then in all space surrounding the two dipoles, we have a hidden harmonic set of bidirectional longitudinal EM wavepair flows of energy comprising each of the static potentials ϕ and Φ filling all space[93] around the assembly in Figure 4-1. Each of those potentials ϕ and Φ is formed of a combination of scalar (time-polarized) and longitudinal photon pairs, as strongly argued by Mandl and Shaw {245} and as previously discussed in an earlier chapter. Further, each of the "static" fields can be decomposed into two scalar potential functions, as shown in 1904 by Whittaker {246}. Then each of the base scalar potentials further decomposes into the set of time-polarized EM wave and longitudinal EM wave pairs. The result is that every "static" field or potential in the universe is actually a set of longitudinal EM wave dynamics.

---

[91] Tom Van Flandern, "The speed of gravity — what the experiments say," *Phys. **Lett.** A.*, Vol. 250, Dec. 21, 1998, p. 8-9.

[92] Indeed, by the asymmetry of its opposite charges, each of the dipoles is co**ntinuously** pouring out EM energy extracted from the seething vacuum.

[93] In the conventional view. We corrected that view in {12}, to agree with quantum field theory and to use a *cause and effect* instead of the *two effects* used by Whiltaker.

Further, in each coupled Whittaker wavepair as reinterpreted, there is perfect correlation between the time-domain EM energy wave (scalar or time-polarized EM wave) and the 3-space longitudinal EM wave. So even a "static" EM field, such as from the permanent magnet and from the charged capacitor or electret, does involve an enormous number of hidden internal EM energy flows in longitudinal and scalar EM waveform.[94]

---

[94] One of the great omissions of modern Western electrodynamics is the failure to follow up on direct engineering of this "vast, internal, infolded, far more fundamental" scalar and longitudinal electrodynamics hidden inside all present overt EM potentials and transverse EM fields and waves. Russian secret weapon scientists under the former KGB called this internal electrodynamics the "information content of the field" and have strongly weaponized it. A deception plan has been used to successfully convince the West that the Russians are speaking only of conventional spectral analysis. Use of this internal EM structuring, in the form of longitudinal or scalar wave interferometry, formed the first giant superweapons deployed by the former Soviet Union in 1963. To see a proof that ordinary EM fields and waves and potentials can be formed at a distance, *arising out of the local spacetime in the interference zone,* see M. W. Evans et al., {79}. Longitudinal EM waves easily pass through the entire earth and ocean relatively undiminished, since mass is mostly empty space filled with fields, potentials, and waves — i.e., filled with incredible numbers and bundles and dynamics of longitudinal and scalar EM waves. Mass is thus a great superhighway for the passage of longitudinal EM waves, and longitudinal interferometry can be performed right through the earth and ocean, on the other side of the earth from the transmitters. Such interferometers can also easily focus inside the earth or beneath the surface of the ocean. Hence in April 1963 the first giant Soviet LW interferometer deployed was used to kill the U.S.S. Thresher beneath the ocean, off the East Coast of the U.S. Intense production of EM signals — emerging everywhere in the space in that underwater interference zone placed around the submarine — filled the sub and its electronic controls. This jammed the electronic controls of the sub, rendering it helpless. The hapless sub then sank to crush depth and imploded. The signatures are clearly present in the jamming and cessation of multiple electronic systems functioning in the sub's surface companion, the U.S.S. Skylark (which was in a sort of surrounding "splatter" zone and survived because it was not individually targeted). Today at least 10 nations have scalar or longitudinal wave interferometer weapons, to one extent or another, other nations are working on them, and the Yakuza also has them. These were apparently the weapons

Ultimately there is no frozen waterfall, but only the dynamic waterfall always reappearing the same but filled with dynamic movement and energy flow.

These latter EM energy flows *infolded inside* the scalar potentials and the **fields** exist for a single charged capacitor or electret alone, or a single magnet alone. They also exist for any two points in a circuit that have differing electrical or magnetic potentials with respect to the ambient vacuum potential (energy density). This latter fact, of course, was part of the secret of Kron's *open path.* Indeed, every dipolarity in the universe — between any two potentials or any two differing charges anywhere — is an open path and an energy flow source. E.g., quoting Kron {247}:

> *"...the missing concept of "open-paths" (the dual of "closed-paths") was discovered, in which currents could be made to flow in branches that lie between any set of two nodes. (Previously— following Maxwell— engineers tied all of their open-paths to a single datum-point, the 'ground'). That discovery of open-paths established a second rectangular transformation matrix... which created 'lamellar' currents... " "A network with the simultaneous presence of both closed and open paths was the answer to the author's years-long search. "*

As can be seen, Kron had discovered how to create currents — *currents could be made to flow* — in individual branches between any two nodes in **the** circuit, physically connected or not. We point out that deliberate use of Kron's "open path" in a network circuit constitutes a strong violation of **the** standard closed current loop circuit's self-enforcement of the Lorenz/Lorentz symmetrical regauging condition. Hence it is a magnificent method for achieving COP>1.0 circuits. It is the belief of this

confirmed in 1997 by Secretary of Defense Cohen in these words: *"Others are engaging even in an eco-type of terrorism whereby they can alter the climate, set off earthquakes, volcanoes remotely through the use of electromagnetic waves... So* there *are plenty of ingenious minds out there that are at work finding ways in which they can wreak terror upon other nations...It's real, and that's the reason why we have to intensify our efforts."* [Secretary of Defense William Cohen at an April 1997 DoD counterterrorism conference sponsored by former Senator Sam Nunn. Quoted from DoD News Briefing, Secretary of Defense William S. Cohen, Q&A at the Conference on Terrorism, Weapons of Mass Destruction, and U.S. Strategy, University of Georgia, Athens, Apr. 28, 1997.]. As the reader can see, the Cold War **was** not so "cold" after all. This mere "tip of the iceberg" should also give the reader a little more insight as to why a war on terrorism is so necessary to all civilized nations.

author that such "open path" functioning in his patented circuits was part of Tesla's secret, though he did not think of it in those terms. However, Tesla's ability to shuttle potential energy independently in his circuits — invisible to a tensor analysis — was rigorously shown by Barrett {124}. Barrett extended the method and obtained two patents in the field of communications {286a, 286b}.

Thus the COP>1.0 problem *is not* in the part or function (the dipole or the charge) that extracts real EM energy flow from the vacuum. That is extraordinarily simple and straightforward. Engineers and scientists have been using it for two centuries without understanding what they were doing. Every charge, dipole, charged capacitor, electret, and permanent magnet already continuously extracts EM energy from the vacuum. The two-fold COP> 1.0 problem is in (i) *separately intercepting and catching (in an external circuit) some of the copious free flowing energy from the "extractor"*, and then (ii) *separately dissipating that collected energy in an external load without killing the "extractor" itself* — or at least only killing it more slowly than the load is powered. The most elegant way to violate the closed current loop circuit is with Kron's open path, typified by Tesla/Barrett potential energy shuttling. Since vector and tensor analysis will not even show it or model it, then a higher group symmetry electrodynamics is imperative in modeling COP>1.0 EM systems and their functions. Much of that work remains to be done.

Our main purpose in this chapter is to point out some selected efforts and approaches by scientists, engineers, and inventors. We will give a brief description and a few details, and leave it to the researcher for further experimentation and reflection. Hopefully, knowing what some others have tried and the results they achieved will prove helpful to the serious researcher.

We also strongly encourage the reader to again read this section after studying Chapter 9. In any COP>1.0 system, the excess energy must come from the "active environment". The active environment of an EM system consists of (i) the active vacuum and its interactions and dynamics, and (ii) the active local spacetime curvatures and their interactions and dynamics. Contrary to naive belief and the received view, overunity electrical power systems — particularly very high COP systems — are neither simple nor easy, but are extraordinarily difficult and highly nonlinear even when their appearance is deceptively simple. Chapter 9 will give a brief expose of some of the difficulties for higher C OP systems. There we will refer again to the intricate circuit analysis work of Gabriel Kron {248}, to Dirac sea electron theory {249} both prior to observation and after observation, and to the need for higher group symmetry O(3) electrodynamics by Evans {250} which is a subset {251} of the electromagnetics used in the unified field theory of Sachs {252}.

Chapter 9 indicates how mathematically complex these systems really are, even when they appear deceptively simple. The phenomenology is highly complex, and it has not yet been scientifically explored because of the erroneous received view that COP>1.0 EM systems are not permitted by Maxwell's theory or the laws of physics. That is a non sequitur. More exactly, *they are not permitted in that equilibrium class of Maxwellian systems described and selected by Lorentz's arbitrary symmetrizing of the Maxwell-Heaviside equations, following their previous symmetrizing by Ludwig Valentin Lorenz* {253}. Prior to applying the Lorenz-Lorentz symmetrical regauging, the Heaviside equations — which in field form are already a truncation to four vector equations of Maxwell's 20 quaternion-like equations — do prescribe both disequilibrium COP>1.0 and equilibrium COP<1.0 Maxwellian systems. The variables are not separated (potential formation) and the equations are difficult to solve, usually requiring numerical methods. With Heaviside's truncation and Lorenz-Lorentz regauging applied, the resulting "special case" equations — now for only that class of COP<1.0 Maxwellian systems that receive and use no net input from their active environment — continue to be used because closed analytical solutions can usually be had and numerical methods can be largely avoided.[95]

So with tongue in cheek, we humorously remark that COP>1.0 electrical power systems have not been developed or known because the early scientists were a bit lazy and wished to avoid ubiquitous use of numerical methods. These days, with computers, proper math programs, and sharp graduate students to easily crunch the numbers, there is no longer any reason for continued arbitrary discard of Maxwellian COP>1.0 systems.

---

[95] For some reason, electrodynamicists ignore the fact that the Lorentz regauging does assume two *additional* equal and opposite energy exchanges of the system with its external active environment, but carefully selected so that all the excess energy received in the system is purely in the form of a stress potential. Hence this energy continually does internal work on the system to produce additional stress, but cannot translate electrons through an external load to power it. Also, this regauging condition represents an effective rotation of the frame of the described system out of the laboratory frame. To then argue that this severely altered system (increased stress, constant additional internal work being done on the system, frame rotation, altered potential energy) is the same system prior to Lorentz regauging, and that such a system is not receiving excess energy from its active vacuum environment, is naive in the extreme and a non sequitur.

For such reasons, no legitimate theory of COP> 1.0 EM power systems has been developed, except for light shed by Prigogine {254a-254f} and others {255a-255c} as to the necessary active environment, disequilibrium nature, and disequilibrium thermodynamics of COP>1.0 systems. Further, the energy flow theory (Poynting's theory) has not been further extended to include the Whittaker decompositions {243, 246} as should long ago have been done. Neither has it been extended to account for the arbitrarily discarded giant Heaviside nondiverged energy flow component.

The researcher should be aware that the energy input to a system is always in the voltage[96] (the *potential;* one input volt of potential will cause one joule of energy to be collected upon each interacting unit point electric charge in the system; one volt of drop in potential results when one joule of collected energy is dissipated per unit point collecting charge in the system.). The fields and their energy are functions of the potentials and their energy, not the other way round. After potentialization of the circuit, the subsequent movement of the potentialized Drude electrons, as current in the system, is connected with (and part of) the *dissipation* from the circuit of previously collected/intercepted energy from the vacuum.

4.2 Demonstration Gedanken Experiment

4.2.1 Work and Energy

Doing work is defined as *changing the form of energy*. No energy is lost per se when work is done; the energy is only changed from one form to another. All the energy since the beginning of the universe is still present,[97] and it is still repeatedly changing its form to do work, over and over. The point is, a single initial joule of energy can be "used" (changed in form) to do more than one joule of work, if multiple changes of form occur serially. *One joule of energy changing its form gives one joule of work, only if a single and total change of form of that joule of energy occurs and then no further change of form occurs.* If the joule changes form once, a joule of work is done and a joule of energy still remains in a second form. If this second form of the joule of energy is not lost, but is retained and then changed in form, a second joule of work is performed and there is still a joule of energy left in different form. And so on. Tricking a system to self-induce multiple iterative form changes of each joule of input energy (or at least of some fraction of each input joule), without losing the energy after each change of form, is one way of providing COP>1.0 in a system.

---

[96] The reason is that all 3-space EM energy — in the circuit or elsewhere — must come from the time domain to each 3-space point and return from that point to the time domain. The scalar potential (voltage) actually is an ongoing process whereby, for any interacting charge, energy in the time-domain and energy in 3-space are functionally combined in that 4-circulation at every point dipole in space. In quantum field theory, e.g. as shown by Mandl and Shaw {19}, the *combination* of the time-polarized photon and the longitudinal photon in 3-space is observed as the instantaneous scalar potential, but neither photon is *individually* observable. We comment that an "observable" 3-space potential is the result of an iterative set of *d/dt* differentiations of the ongoing "combination" of scalar (time-polarized) photons having their energy oscillations in the time domain, with longitudinal photons having their energy oscillations in 3-space along their line of motion. Hence each *d/dt* differentiation of the ongoing 4-space combination yields the instantaneous 3-space potential. Cumulating, one has the ordinary 3-space potential or "voltage" of macro electrodynamics.

Remember that COP (coefficient of performance) is best defined as *the usable work output obtained, divided by the EM energy that the operator inputs.* Since "usable work output" is just usable "change of form of the energy", it can be seen that multiple changes of form of every joule of energy input by the operator can lead to COP>1.0.

This illustrates that one must be careful in applying the law of conservation of energy. For a thorough analysis, several features must be identified and accounted: (i) The flow of the energy impinging upon the collection, (ii) the collector itself and the type of collection process utilized, (iii) the linear or nonlinear operation of the collection/collecting process, (iv) the dissipation process used to dissipate the collecting mechanism, (v) what happens to the energy flow that was collected and then its collection "dissipated", (vi) what type of energy flow was collected, and then its collecting "dissipated", (vii) what happens to the collector after the dissipation interaction, (viii) what happens to the energy in different form after each previous change of form, (ix) whether single-pass or multiple-pass of the energy flow is used, (x) whether single collection or multiple collecting is used, and (xi) the effects of any nsymmetrical regauging of a local component or region (e.g., as in simply increasing one of the potentials of the region) that in turn acts as a free energy flow.

---

[97] However, "present" means in spacetime, not just in 3-space. The EM energy we think of as being in 3-space is macroscopically in continuous circulation from the tine domain to 3-space and back to the time domain. Microscopically it is in *continual* circulation.

See again Figure 2-4 in Chapter 2. In general, the available energy flow surrounding a circuit will be far greater than the intercepted and collected energy in that circuit, particularly in a "single pass" collection — i.e., where the impinging energy only passes once. In analyzing a system or circuit, one must be very careful to ascertain whether the system utilizes any mechanisms to enhance and increase the energy collection fraction. If it does, then a necessary (but not sufficient) criterion for COP>1.0 has been identified in the system. Letokhov's negative absorption of the medium (i.e., excess energy emission) {256} and Bohren's experiment {257} are examples. Bohren's experiment is easily replicated by any nonlinear optics lab, and outputs 18 times as much energy as the conventionally calculated energy input.[98]

If the impinging Heaviside nondiverged component of the energy flow beyond the collecting/collector is rerouted and passed back to impinge again in the system — even on another collector or other collectors — this must also be taken into account.

Conventionally, the "magnitude" of the fields[99] E and H in the Poynting (collected) energy flow S = E x H are "defined" by the collection from the fields by an assumed unit point static charge at each point in space. In short, the conventional fields have already been "defined" as a standard linear collection upon standard charged *mass, from the field entities as they*

---

[98] Energy conservation is not violated! Instead, the conventional calculation assumes a static intercepting unit point charge, which has the minimum reaction cross section in the stream of bidirectional longitudinal EM energy flows comprising the potential, etc. By placing the intercepting charged particles into particle resonance, the particles' reaction cross section is increased because each resonating charge sweeps out a greater geometrical cross sectional area. Hence the charges collect more energy from the energy flow comprising any "field" (actually field intensity) or "potential" (actually potential intensity) than is assumed in the standard input energy calculation. In short, Bohren's experiment takes advantage of that arbitrarily discarded Heaviside energy flow component that remains and is present but not considered in the conventional Poynting calculation and field intensity calculation. The experiment in fact proves the existence of the unaccounted but ubiquitous giant Heaviside nondiverged EM energy flow.

[99] At best, the 3-space point intensity of each 4-space field is so defined, for a forthcoming reaction with unit point static charge, and where the forthcoming reaction does not involve lingering time - charging but only simple time-excitation followed by full decay of the time-excitation via normal photon emission.

exist in 4-space prior to interception and collection, and where the collector itself is absolutely fixed and "static". So nonlinearity in energy flow collection — by additional disruption of the impinging energy flow induced by the dynamics of the collector itself— may easily increase the "reaction cross section" of the collector. The static reaction cross section of a unit point static coulomb and the dynamic reaction of a unit point resonant coulomb may differ appreciably.

Without stating it this clearly, Bohren has shown that the interaction cross section for a single-pass collection by one static particle may be increased by a factor of 18 in a given example, *by inducing resonance and thus increasing the "collection" dynamics of the collecting particle* in the impinging S-flow {257}. The work has been independently substantiated by Paul and Fischer {258}. It also is a direct proof of the existence of Heaviside's neglected nondivergent energy flow component surrounding every field and charge interaction.

So indeed there are COP>1.0 EM processes in the literature. The Heaviside component also pouring from the terminals of every generator and battery, already proves that *every generator and battery ever made already was and is a COP> 1.0 energy transducer, because far more energy pours from the terminals of the generator and battery than the shaft energy input to the generator or the chemical energy dissipated in the battery.*

4.2.2 Extending the Work-Energy Theorem

The standard work-energy theorem in mechanics may be conventionally stated as: *The change in the kinetic energy of a particle is equal to the net work done on the particle by the net force acting upon it.* As in any "model", here there are assumptions that are seldom taken into account. First, the collected/collecting kinetic energy of a particle is due to its increased interaction rate with the vacuum flux, because of its acceleration through that flux.[100] In mechanics the increase in flux interaction (and hence "Newtonian 3rd law resistance" is just treated as a sort of resistance to acceleration, and known as *inertia.*[101] The actual energy of the vacuum flux interaction rate is a function of the square of the particle velocity through that flux — hence the formula $K = 1/2\, mv^2$ for the kinetic energy K of a mass m moving through the flux of space at velocity v. Relativistically, the mass of the particle is moving through the ambient potential flux, or we may view it from the particle's frame of reference where the ambient potential flux is moving through the particle but interacting with it. Only a single pass of the flux impinges upon the "particle collector", so there is only a "single-pass" type of energy collection ongoing.

---

[100] As we cover elsewhere in this book, any charge (which, together with its clustering virtual charges of opposite sign is a dipolarity) is a broken symmetry in the fierce flux of the vacuum. This means that every charge in the universe absorbs virtual energy from the vacuum, coherently integrates some of it into observable energy, and pours out that observable energy in all directions. The negative charge does that for positive energy; the positive charge does it for negative energy. The latter can be better interpreted as the return of positive observable energy from space to the positive charge, thence disintegration of that positive energy back to virtual energy, and subsequent re-radiation of that virtual energy back to the vacuum. One **can** in fact model the **Bohren** experiment in terms of the extra vacuum flux

All energy in the vacuum exists in "vacuum flux" or "change in vacuum flux" form. There is no force in the vacuum, although there is polarization that will produce a force upon a charge when one is introduced. The force occurs only after the "change in vacuum flux" that we call a field is interacting with a mass. The force is *already* a change to the mass, a priori, since mass is a part of force by $F = d/dt\,(mv)$. If energy is then added by a AK energy flux (usually mistakenly called a force) performing work upon mass m, this constitutes an additional energy flux or flow impinging on the

encountered and transduced by the resonant charge, as compared to flux encountered and transduced by the static charge. In the same vacuum flux density, a resonant charged particle will intercept and absorb more virtual photon energy than the same particle in static condition. Hence its broken symmetry will convert more absorbed virtual photon energy into real observable emitted photon energy.

[101] If one wishes to understand that inertial reaction, here is how it works. Consider the virtual charges of the vacuum as an analog to the Drude electron gas in a conductor. At the instant an observable charge starts to move, it is momentarily affecting all the surrounding virtual charges — an enormous number, which are initially repelling and attracting it in all directions intensely. To move, the observable particle must create a change in that entire participating virtual particle "gas". Just as the Drude electron gas, the vacuum "gas" of virtual charges has a certain relaxation time constant. So a finite time delay occurs before the vacuum gas relaxes and movement of the observable charge occurs. As the relaxation continues apace, the particle being acted on by a force accelerates. Even mass with a net charge of zero is filled with charges, and even the neutrons in the atoms are continuously changing into protons and back, etc. So all mass continually exists in the "charge and charge-changing" state. Inertia is in fact due to the relaxation time curve of the vacuum virtual charges "gas". We dealt crudely with this in Bearden, "Quiton/Perceptron Physics," NTIS Report AD-763-210, 1973, p. 11; hopefully a far better treatment will eventually be undertaken by qualified higher group symmetry electrodynamicists.

particle, imposing an additional "energy collecting" and gradient across the mass. Rigorously, the dynamic system comprised of the dK gradient coupled to the particle, and interacting with it, identically is a force.[102] Depending upon the situation, it may accelerate or decelerate the particle, or change its direction, or a combination. This is summarized in the usual work-energy formula

$$W = K_f - K_i = \Delta k \qquad [4\text{-}1]$$

where the work W that was done is given by the change dK in kinetic energy of the particle from its initial kinetic energy K_i to its final kinetic energy K_f.

In applying the conservation of energy law, usually physicists utilize either the work-energy theorem or an approach closely paralleling it. This application is valid in any linear single-pass collection situation. It may not be valid — and usually isn't —for a multi-pass, multicollection system where the same energy, changed in form to accomplish work in a single reaction, is then changed in form iteratively, again and again, in the same system or material. In such case, one joule of input energy can and will accomplish multiple joules of work in and on the system. So for our purposes we must modify the work-energy theorem to give

---

[102] We stress again that the hoary old mechanics, some four centuries old, is seriously in error in assuming a separate force acting on a separate mass. That remains an inexplicable non sequitur in modern physics, in its very foundations. We call attention to how classical electrodynamicists' wrestle with the problem. E.g., quoting Jackson, *Classical Electrodynamics,* 2nd edition, Wiley, 1975, p. 28: *"...the thing that eventually gets measured is a force... " "At the moment, the electric field can be defined as the force per unit charge acting at a given point. It is a vector function of position, denoted by E."* Our comment is that the "definition" is in error, including the use of the word "field" for "field intensity", when field and its intensity are two entirely different things. A proper definition should be stated as *"...the observable electric field intensity can be defined as the force per unit static charge and mass, existing at a given point in an interacting gradient of the virtual particle flux of the vacuum, as inferred from the changes induced upon the unit static charge and mass. "* The field intensity is a vector function of position, charged mass, and vacuum virtual particle flux gradient. The standard definition substitutes an effect (of collection) for a cause (prior to collection), and this error is widespread through physics, from mechanics to electrodynamics and on into particle physics. On p. 249, Jackson shows how the electrodynamicists largely capitulate and continue to promulgate the substitution of effect for cause. Quoting: *"Most classical electrodynamicists continue to adhere to the notion that the EM force field exists as such in the vacuum, but do admit that physically measurable quantities such as force somehow involve the product of charge and field."* We comment that actually mass is a component of force, as shown by $F = d/dt(mv)$.

$$W = \lambda(K_f - K_i) = \Delta k \qquad [4\text{-}2]$$

where λ is the averaged energy collection fraction, adjusted for multipass, multicollection and also for asymmetrical self-regauging (self-increase of the potential in, and hence the energy flow from, one or more regions of the active system's source). In formula 4-2, K_f and K_i and Δk still refer to single-pass collection only.

In the new work-energy theorem, $\lambda = 1.0$ for that vast number of conventional cases that have successfully utilized the conventional form of the theorem. These are almost always single-pass, single collection systems. The new COP>1.0 systems have deliberately enhanced energy collection — and hence multiple *energy collection and work amplification*[103] — such as multi-pass collection. For these COP>1.0 systems, the expanded work-energy theorem form applies and in general $\lambda > 1.0$. In an ideal COP>1.0 system, $\lambda >> 1.0$. In some versions of the Patterson Power Cell®, for example, $\lambda = 1200$. In the Sweet device (discussed later), a very high value of lambda resulted, so that $\lambda = 1.5\text{x}10^6$. We sometimes refer to λ as the *energy amplification factor, energy collection fraction, Poynting amplification, collection amplification,* etc. Bohren and others have referred to it indirectly as the *interaction cross section,* the *resonance absorption cross section,* and the *negative absorption cross section.*

Again, we strongly iterate that *there is no conservation of work law in physics!* When energy is input to a system, acts on it, and is "dissipated" by a change of its form (doing work), the "dissipated" energy is still available after the work (change of the energy's form) is accomplished. However, usually by "dissipated" energy we mean energy that has permanently left the system (or a component in the system) and cannot be recovered and used by the system. The original input energy is not work, because it did not undergo any change of form prior to interaction with the system to change its form. So one does not do "work" as input, which is a non sequitur. Any work accomplished in the input section of a system is due to inefficiencies of the system,[104, 105] usually allowing extra change in form of some of the energy in non-useful processes called "input losses". As we stated, it is quite possible for a single joule of original input energy to perform many joules of work. During the subsequent billions of years following the formation of the observable universe and the energy in it, every joule of the primordial energy is still here. And every joule of it has been steadily performing joule after joule of work since then. Further, it has continually been recycled between 3-space and the time domain and back, and is continually being so recycled today.

---

[103] There is no "conservation of work" law in physics or thermodynamics. It is energy that must be conserved. A single change in form of K joules of energy gives an equal number of K joules of work done upon the interacting mass system. However, there remains an equal number of joules available, just in a different form. If that second K joules of energy is then changed in form again and not allowed to escape from the system, an additional K joules of work is performed in the system, without the operator having added any extra input energy. And so on, until the inefficiency of the system and some inevitable losses allow all the "recycling" energy to escape from the system. We strongly believe that ignition, quenching, and re-ignition phenomena such as in gamma ray bursters and x-ray bursters are due to exactly such processes where iterative change of form of each initial joule of energy occurs.

Suppose input energy to a system has been dissipated (changed its form) once, doing work (single change of form of energy) in the system. If the dissipated energy in a different form is then recovered or partially recovered — without escaping the system — to change its form yet again in the system and produce additional useful work, that system is

---

[104] Almost always due to a negative feedback mechanism such as Newton's third law, self-regauging symmetry, the closed current loop circuit, inertia as due to a self-regauging 4-symmetry, etc.

[105] E.g., a transformer would be an overunity system, because the current in its primary is separate from the current in its secondary, if these two currents were completely decoupled and independent. In that case, the transformer would simply propagate and "couple" or pass energy emitted from primary to the receiving secondary, without back-coupling. However, the closed current loop in the secondary, routing all spent electrons in the secondary back through the back mmf of the secondary coil, produces a back-field coupling interaction with the primary, and this "back mmf/back emf" coupling requires energy dissipation in the primary section to overcome. In short, the transformer is designed so that the secondary lights the primary to a draw and the designer loses. With some losses and inefficiencies in the device, that makes the transformer a COP<1.0 device (unless free external energy is received in the input). The interested reader might extract several hints and suggestions in this book, passim, of things that overunity researchers have tried in their search to break up the back-coupling of a transformer. The simplest way, of course, would be to place a true negative resistor shunt across the secondary, so that part of the secondary current does not return back through the primary.

considered to be an open system far from single-dissipation equilibrium with its external environment.[106] In that case, instead of the first dissipation simply "returning" the energy to the external environment, the energy is recovered by another change in form (which may simply be a change in direction in the internal environment). The thermodynamics of an open system far from equilibrium with its active environment applies, whether that "environment" is internal or external to the system. It is "external" to the subcomponent of the system forcing the "local change of form" of the energy.

4.2.3 Gedanken Experiment: Multicollection by Regenerative Feedback

After a COP>1.0 collecting process with subsequent proper discharge of the energy, more work output as "dissipation of the collected-energy" exists than the energy being input by the operator or experimenter. By regenerative, clamped, carefully controlled positive feedback of a portion of the output *positive* energy[107] to the system input, the system can be converted to a self-powered (self-asymmetrically-regauging) system that powers both itself and its loads. However, see Chapter 9 for special considerations of the Dirac sea hole current and excess negative energy that arises for COP»1.0 EM systems. Positive clamped feedback will fail dramatically for any COP»1.0 EM system, and for many COP>1.0 systems it will also fail unless conversion of negative energy — arriving at the input section — to positive energy is accomplished.

To ease visualization of the energy multicollection process, consider a gedanken experiment iteratively retroreflecting a steady small EM energy input. Particularly see Figure 4-2.

---

[106] The vacuum environment is also "internally" penetrating throughout any macroscopic system, to the finest level! So the notion of separated "external" and "internal" environments requires strong qualification in any system engaged in iterative, work-amplifying interaction with its local vacuum.

[107] The output may contain appreciable negative energy as well as positive energy, however. In that case, in the feedback loop the negative energy must be transduced into positive energy by regauging, else it will appear in the input section of the system as an extra system load there in the input itself. It will "eat" incoming electrons from the external power supply, so that the external power supply has to power this "extra load" in the input section as well as powering the normal system load presented. This reduces the system COP to COP<1.0.


INSIDE SURFACE IS A MIRROR
Escaping heat
heater
SOURCE
STEADY INPUT
without limiting process
much greater asymmetry in vacuum flux exchange
with limiting process
Results
COP = f(t) Reflectivity > 0.5
increasing asymmetry in vacuum flux exchange
COP = 1.0 (Reflectivity = 0.5)
small asymmetry in vacuum flux exchange
output energy rate
time

4-2a. Experiment.

4-2b Result

Figure 4-2 Heater wire in a hollow sphere with certain retroreflectivity properties.

As shown, a heater-emitter is placed inside a closed hollow sphere, through a tiny hole for the two wires connecting the heater wire into the external power supply (the external power supply is not shown). The heater emitter is 100% efficient; any joule of energy absorbed by it is re-radiated by it. One joule of energy (one watt of steady "input power" — conventional electrical engineering terminology where rate of work and rate of energy flow are confused!) is furnished from the power supply to the heater element inside the sphere. The inside of the sphere is coated with a substance that acts as a phase conjugate mirror (PCM) reflector with, say, 0.5 reflection coefficient. In other words, when scattered photons are emitted from the wire in all directions, they strike the inner surface of the sphere. Half are retroreflected precisely back to the spot on the resistor from whence they came, where they are absorbed and "re-collected" to further heat the resistor, causing emission of additional photons from it. The other half of the absorbed photons on the inner surface of the sphere diffuse through the cylinder walls as heat, and escape as heat radiation from the sphere to the outside world.

If that sphere's operation could be maintained intact and stable, without change of the physical characteristics and mechanism, then the buildup of energy in the heater wire inside the cavity — and the buildup of the energy icing emitted from the outside of the sphere — would be ever increasing. It would increase without bounds as time passed. Wait a short time, and the sphere would be outputting 10 watts of power while one would still be inputting one watt. Later, the sphere would be outputting 1,000 watts of power, while one would still be inputting one watt. And so on. Indeed, the rise in energy density of the output would be asymptotic, and would increase toward infinity. The only limitation as to the energy output for a steady 1 joule per second input, would be the limit at which the mechanism goes unstable and changes occur to dampen and curtail the process.

Before the reader objects on conservation of energy grounds, one should realize that this rise in the energy density inside the sphere is an example of iterative regauging. The principle of *gauge freedom* — one of the axioms of quantum field theory and well established — assures us that *the potential energy of a system can be changed at will, and freely.*[108] What the gauge freedom principle does *not* state is a *mechanism for providing the additional potential energy and a source for it* — nor do the quantum field theorists and electrodynamicists. Without such a source and mechanism specified, the conventional gauge freedom principle assumes total violation of the conservation of energy law.

---

[108] Conventional scientists are almost always very careful to regauge symmetrically, so that the two excess force fields that result are equal and opposite, and sum to a net zero resultant field. That "zero-summed system" comprises a stress potential *a priori.* So such symmetrical regauging alters the stress in the system and alters its potential energy, but only in the form of additional stress energy. There is no *net* force and "force field energy" that can be used to dissipate that additional free stress energy in an external load, thereby doing free work. This regauging is a purely arbitrary practice by the electrodynamicists. We are far more interested in "asymmetrical regauging", where only one potential is freely changed or the two are changed unequally, resulting in a *net nonzero force field* that can then be dissipated in an external load to perform free work. Only by asymmetrically regauging an otherwise inert system can usable field energy be added and any work then be done by it anyway. In conventional systems, we do the "asymmetrical regauging" by adding the voltage (potential difference). As current flows with dissipation of energy from the circuit in the loads and losses, the system is able to develop "power" and thus do work in the external load. Unfortunately, the electrodynamicists are still obsessed with symmetry, so they ubiquitously employ in all electrical power systems the closed current loop circuit. This guarantees that the circuit will kill its source dipole (the source of the potential and potential energy generated from the virtual flux of the vacuum by the broken symmetry of the opposite charges of the dipole) faster than it powers its load. That way, lovely symmetry is maintained, beautiful free energy and negentropy are avoided and tossed away, and ugly pollution and destruction of the biosphere continues worldwide to fulfill the ever-increasing and insatiable thirst for electrical power.

In our supersystem view, the gauge freedom mechanism providing the energy is straightforward: the excess energy is freely supplied from disequilibrium in the active vacuum interaction with the system and in the disequilibrium represented by the local curved spacetime. Since a change in system potential energy is also a free change in spacetime curvature, then it follows that simply changing the potential energy of the local vacuum (the vacuum is also an electromagnetic system!) and of the local curvatures of spacetime is also "for free", or it can be. One does not have to perform work oneself upon spacetime to curve it! The mere *presence* of a spatial energy change — including a free potential energy change allowed by gauge freedom — is sufficient to freely curve spacetime also. That is a real energy change, because any curvature of spacetime acts back upon mass. Higher group symmetry electrodynamics does indeed include vacuum energy and energy current {259a-259c}, and it is possible to extract useful EM energy from the vacuum.

But back to our sphere, where the internal potential energy of the sphere is rising asymptotically without bound.

In the real world, of course, the reflection coefficients and the materials characteristics will change as the energy density changes, the sphere will heat, etc., and these changes will start damping the perfection of the retroreflection process to limit it to some finite plateau value which may be a COP>1.0 or COP»1.0 condition. Or, the materials will melt or soften so that the sphere ruptures and explodes, sharply quenching the process entirely and emitting a violent burst of energy to signal the disruption of the localization of the process.

Nonetheless, a successful real bench experiment similar to this should be possible with some tinkering, and it should readily yield COP>1.0, after one waits for build-up and stabilization at some level. We would hope that a sharp young graduate student may eventually prepare a doctoral thesis on this experiment or a variant. The principle is demonstrable.

Similar buildups by regenerative feedback and multiple collections by the collectors do appear to occur in nature, up to and including such phenomena as gamma ray bursts, x-ray bursts, etc. These occur in some systems such as exploding gases (and in some cases, even in the upper atmosphere of the Earth). In such a system, the "physical particles in suspension in space" do move and continually disrupt the geometry for the increasing buildup, resulting in decay of the process after a time delay.

However, there is a finite time during which the movement of the particles is still insufficient to appreciably break the geometry and cause quenching.[109] During this "nearly linear stage", the build-up applies and the energy density very rapidly increases. Build-up occurs and continues while the relaxation time of the initial countering symmetry-restoring mechanism for the old or former state or condition (the initial reaction) is occurring. A well-known conventional example is the Lenz law reaction. Then as the geometry changes significantly, a rapid damping of the energy density increase occurs, quenching the asymptotic rise and "discharging" or "decaying" back to a less-than maximum condition. However, the decay position or state (in the quenched condition) will be different from the initial condition before asymptotic rise (regauging) set in. The system usually will have itself absorbed and collected additional potential energy, and so it will be "hotter" or more energetic. This is often called the "afterglow". In the simple case, parts of the system will be in greater motion (more energetic).

An intermediate plateau can appear as quenching occurs and it can stabilize. However, if no stable plateau is reached during the damping, then further rapid quenching and a rapid reduction of the increased energy density occurs as the geometry changes become decisive and break the asymmetric self-regauging. Thus the "damping" of the process may yield a plateau of steady COP»1.0 operation, or it may simply go immediately into full catastrophic quenching and decline back to some lesser level of COP>1.0 operation, but still more energetic than the beginning condition. The latter case produces a sort of "afterglow" - - observed in the gamma ray bursters, e.g. — of increased energy density from the beginning of the quenched phenomenon. Indeed, in that new system of more energetic gases or particles, once the new state is stable, continuing regenerative feedback versus the new geometry can then reinitiate or "re-ignite" another "burster" followed by subsequent quenching. And so on.

We submit that the gamma ray bursters fit this schema and are consistent with it. So do the phenomena observed in intensely scattering photoactive media on the nonlinear optical laboratory bench. We hypothesize that the gamma ray burster and similar violent burst emission phenomena are generated by this mechanism or a similar version of it.

---

[109] Regardless of what we call it or what it has been conventionally named, any impulsive, explosive process involves at least momentary broken symmetry, resulting in instant and countering broken symmetry. Then a relaxation time passes, and the countering broken symmetry is dissipated by change of the system to a new potential energy state, the new dynamics state, etc.

Figure 4-3 diagrammatically shows a proposed range of such "excess energy" emissions due to this regenerative positive feedback and multiple collection mechanism. As can be seen, this may place our view of very powerful astrophysical emission phenomena in a completely different light, arranged energetically by the length of the initial "nearly linear" phase of exponential increase. There is a scale of stability levels up to just before the Big Bang itself {260}. A so-called Big Bang, of course, would result when the "containment" ability of 4-space itself is breached, resulting in a rupture of 4-space and a consequent violent blow-out into n-space (where n>4), with a very rapid "false vacuum" created *outside* the blow-out region and pumping itself up by asymmetrical self-regauging in a "new" 4-space. When a new stability level is reached outside the blowout hole from the spawning 4-space, it represents an outside "new" 4-space and a new, infant 4-spatial expanding 4-universe, freshly born.


Corrected Work-Energy Theorem:
Universality in Scale-Up Processes
Sizing Scaleup
Less Limiting
Anti-Stokes
Energy Density
ASR*
Nuclei Affected
MICRO —— MACRO —— SUPERMACRO
Increasing changes to nuclei
decreasing threshold limiting efficiency
Increasing asymmetry in vacuum flux exchange
multipass, multicollection efficie
Increasing local spacetime curvature
Note: *ASR = Asymmetrical self-regauging
BIG BANG
???
???
Galactic antimatter streamers
Pair Annihilation radiation sources
γ - ray bursters
X-ray astro-sources
Part of Sun's Energy Output
Lawandy-Patterson-Correa Region
Conventional anti-Stokes emission
COP = 1.0 (Resonant Stokes Emission)
COP < 1.0 (Stokes Emission)
Decreasing probability of initiation

Figure 4-3 COP>1.0 **stability levels for the asymmetrical self regauging process invoked by multipass and** multicollection **of same energy.**

So from inside the spawning universe, the burster phenomenon would be so great as to "burst" 4-space, producing a sort of "super black hole" as seen by the spawning universe. We hypothesize that the asymmetrical self-regauging mechanism produces a great burst of EM energy in its universe if a stability plateau is reached that is below the threshold of 4-space rupturing. If such a stability plateau is not reached, the asymptotic rise in local spatial energy density increases until the primary 4-space ruptures to produce a "blowout" seen from the old universe as a sort of black hole. There is a sort of "white hole" in the new universe being spawned on the other side of the blowout. This white hole and its associated phenomena produce the birth of another 4-universe outside the original spawning 4-universe. At least we propose that as a hypothesis.

We propose that this could be a legitimate process for the birth of multiple 4-space universes in the infinite-dimensional cosmos.[110] It has an added advantage of accommodating the vexing question of "What existed before the beginning of time (in this universe)??? The answer then would be, *"The existence of time in another universe that birthed this one. "* We emphasize our interpretation of time as just a special form of EM energy, and not at all a "mysterious river down which we float helplessly as if in a drifting boat in the river's current."

4.3 Iterative Retroreflection and Collection in a Circuit

The normal circuit attached to a generator or other external power supply is the "external" portion of the overall closed current loop circuit passing back through, and including, the source dipole in the power supply. In a DC external circuit, we may consider that the energy flow pours forth steadily from the terminals of the generator (from the dipolarity between them) into space surrounding the external circuit. Since the external conductors act as a sort of guide, this *transmitted* external energy flow is generally parallel to the external conductors.

The external circuit further acts as a *receiver.* The surface charges and their fields intercept and interact with some of the transmitted energy flowing parallel to the conductors and outside them. This interaction diverts a component of that passing energy flow into the conductors, powering the Drude electrons. This powers the external circuit. The nondiverted component of the passing energy flow — usually much larger — escapes on out into space beyond the external circuit. According to Heaviside's energy flow theory {261}, this escaping nondiverged energy flow may be interpreted to exist in closed circulations.[111] Laithwaite

---

[110] After all, a "dimension" ultimately is just a fundamental variable in a physics model or, in other words, a "degree of freedom" in mathematical modeling. We may construct any number of dimensions we desire, merely by assigning a sufficient number of variables, including both overt variables and hidden variables, etc.

[111] We point out the interesting possibility of re-interpreting this "closed circulation" Heaviside component as the giant negentropic circulation of EM energy from the

{172b} has specifically commented upon the potential importance of this aspect of Heaviside's theory.

As we shall later address, Heaviside worked out but never published a draft theory of gravitational effects from this extra escaping energy flow {262}. Interestingly, since Lorentz's integration of the energy flow vector around a closed surface surrounding any volume element of interest, the discarding of this "excess nondiverged energy flow" has been ignored by electrodynamicists, and it has been ignored by gravitational theorists.

Consider a theoretically "perfect" generator, loss free. Consider the presence of the Heaviside nondiverged component emerging from the generator terminals — and filling all space around the external circuit. That is the part of the energy outside the circuit that is not caught and processed by the circuit, but is just wasted. By definition, in this "perfect" situation the magnitude of the Poynting or "caught" component of energy flow will precisely equal the magnitude of the mechanical energy input flow (rate) to the generator.[112]

But the presence of the additional huge Heaviside component rigorously means that far more energy pours from the terminals of every battery and generator than the amount of mechanical energy the operator inputs as shaft horsepower. This easily demonstrated fact — e.g., proven by the Bohren experiment {24} — continues to meet with a resounding silence from electrodynamicists and physicists, and particularly from those dogmatic skeptics so keen on defending the classical thermodynamics of closed or equilibrium systems as if they also applied to open systems far from equilibrium in their exchange with their active environment. We refer particularly to the dogmatists so supremely confident that COP>1.0 EM systems are prohibited by the laws of thermodynamics. These stalwart fellows would thus exclude every charge (and its associated fields and potentials) in the universe, were they logical and speaking scientifically. So they strangle at the gnat of COP = 4, and swallow COP = oo while proclaiming that COP>1.0 EM systems cannot exist.

The dogmatists have achieved a major nefarious goal, however. They have silenced most inquiry into such matters by electrical engineering

---

time-domain to the negative charge, to 3-space, to the positive charge, and back to **the** time-domain. To our knowledge, that has not been examined.

[112] That is merely a statement of the Lorentz symmetry condition self-enforced by the closed current loop circuit itself.

professors, young graduate students, and young postdoctoral scientists. They have glorified classical equilibrium thermodynamics into a religion rather than the partial and imperfect model it really is. They are directly responsible for the continuing rape and pillaging of the planet's resources, pollution of the biosphere, global warming, and the increasing death of species. They are indirectly responsible for the deaths of more human beings than Hitler, Mao, and Stalin combined. Most of the blame for environmental pollution problems concerned with power and electricity is squarely at their feet. Sadly, the environmentalists seeking to save this planet and biosphere have not yet recognized the true nature of the scientific Taliban that has generated the environmental problem. In tolerating its own scientific "terrorism", the scientific community seriously aborts much of the scientific method.


REFLECTORS FOR HEAVISIDE COMPONENT
POWER SOURCE
EXTERNAL CIRCUIT AND CONTROLS
LOAD

Figure 4-4 Iterative retroreflection of the "passed" **Heaviside component back and forth across a** circuit -- **thematic.**

See Figure 4-4. The neglected large nondiverged energy flow component need not be wasted. As an example, part of it can be captured and used, by applying near-field antenna techniques and such methods as Bohren's resonance increase of the intercepting charge's reaction cross section.[113] It is possible to intercept part of that excess energy that is there and available. E.g., even after it passes on by the immediate circuit, the Heaviside energy flow component can be intercepted beyond the circuit and retroreflected back across the same circuit again. In this way — at least in theory — extra Poynting energy can be collected and recollected by the same external circuit for a single given input energy.

---

[113] Or other methods we cannot yet divulge because of patent situation.

In essence, such an "iterative, multi-collecting circuit" is now fed with transmitted energy from multiple (iterative) paths simultaneously. This is *physically doable,*[114] but it is not a simple procedure, and antenna theory and especially near-field antenna theory must be utilized as well as focused retroreflection techniques. To directly model it, higher group symmetry electrodynamics (such as quaternion EM, O(3) EM, etc.) must be used. Precisely such phenomena are met in modern experiments in intensely scattering optical materials {263a-263b, 264a-264b} and in Bohren-type experiments where more energy is collected than the operator has input via standard calculations {257, 258}.

4.4 Tesla's Iterative Retroreflection Work

4.4.1 Tesla's Single Wire Circuit

See Figure 4-5, which diagrammatically shows one of Tesla's developments, which used a retroreflective single wire circuit between two large separated capacitances. This was the basic approach used in his magnifying transmitter and in several other circuits. Here the dipolarity exists between two accumulators, one at each end of a long conductive path with a load in the middle. AC operation is used, by setting up oscillation end-to-end along the "single wire" circuit, from accumulator to accumulator. Even so, no overunity operation will be experienced unless passive retroreflection of the normally wasted Heaviside component of each energy flow "passage" occurs back from each receiving end, so to speak {265}. That is possible if specialized dielectric material and construction is used in the end capacitors.

---

[114] E.g., some of Tesla's actual patented circuits do it, but that part of their functioning is not described by any vector or tensor analysis. However, a higher group symmetry electrodynamics analysis of the circuits will indeed show the effect clearly as a "shuttling" of potential (regauging) around the circuit at will. E.g., see T. W. Barrett, {124, 286a, 286b}.



Tesla's intent was to eliminate the forced pumping of the spent *electrons back through the back-emf* of the power source, and back through its source dipole to destroy it. The circuit must operate as a tuned oscillator.

Similar reflections occur *end-to-end in today's powerlines*, but are considered detrimental, are damped out, and not used.

Figure 4 5 Tesla's iteratively retroreflective single wire circuit.

Further, it may usually be necessary to place the individual charges comprising the "current surging to and fro" into particle resonance at either the frequency being transmitted or some subharmonic of it. This schema is doable, but it is difficult and most everything affects it, including even the impurities in the conductors.

4.4.2 Strain to Stress Potential Energy Transduction

See Figure 4-6. This is a diagrammatic representation of a fundamental "strain-to-stress" transduction mechanism we believe was involved in Tesla's "single wire circuit" (i.e., his iterative retroreflecting circuit).

At each end of the circuit, the electrons are "trapped" in the open outside end. Hence when EM energy rushes to the capacitor on one end of the circuit, the forward emf tries to strain the dielectric from the inner plate toward the outer plate. However, the trapped electrons in the outer open wire cannot move, so they produce an equal back-emf and back force trying to strain the dielectric from the outer plate to the inner plate. The result is that the translational field "strain" energy (dipolar charging) is transduced into stress potential (monopolar charging) energy. Electrons try to strain the dielectric from the inner plate toward the outside with a "forward emf so as to charge the capacitor normally, while the trapped external electrons simply push back the other way, exerting a back emf force that is equal and opposite to the straining force from the forward emf and simultaneously tries to "charge" the capacitor in the opposite direction.



Dielectric in capacitor is stressed not strained
This changes field (strain, translation) energy from the
circuit into stress potential energy (curvature of spacetime)

Figure 4-6 Transaction of translational field energy into stress potential energy.

Here is the importance of the "vector zero resultant" stress (monopolar) charging that occurs: The input EM strain field energy familiar in dipolar charging of a capacitor is converted to a dielectric stress (monopolar) potential for monopolar charging. This changes *translational* field energy (external energy) into *stress potential* energy (internal energy), adding an equal amount of back-emf translational field energy in so doing. In short, the charging captures an equal amount of charging energy from its external environment — in this case, from the back emf of the trapped external electrons in the outside open wire. This is one way to capture and use the back emf energy normally reducing the energy available.

We point out that this is charging the capacitor by *Lorentz's symmetrical regauging,* and it represents a rotation of the frame of the capacitor itself out of the laboratory frame. As is well known, the trapped energy of a capacitor in a rotated frame is not the same as the energy of the same capacitor in the nonrotated lab frame.

The single-wire system destroys the symmetry-enforcing function of a closed-current-loop circuit conventionally used. In short, it does not return the "spent electrons" from the ground return line back through the source dipole of the outside power source, so it does not use half the collected energy in the circuit to destroy the source dipole and its extraction of EM energy from the vacuum (to destroy its broken symmetry). Because it retains the broken symmetry, Tesla's single wire system is an open system far from thermodynamic equilibrium with its active vacuum environment. It is thus permitted to exhibit those five magic functions of such open dissipative systems: (1) self-ordering, (2) self oscillation or self-rotation, (3) outputting more energy than the operator inputs, (4) self-powering of itself and its load, and (5) exhibiting negentropy.

4.4.3 Potential Energy Shuttling in a Circuit

The net result is to "shuttle" the (stress) potential energy back and forth in the circuit, between the ends. See Figure 4-7. When this stress potential energy shuttling is done at the natural (or tuned) resonant frequency of that single wire circuit as an oscillator, the monopolar charge transfer is optimized and amplified by the resonance effect, with an increase in the energy being shuttled. It is this type of Tesla single wire circuit that can in theory exhibit COP>1.0.

Tesla's single wire system also forces the change of energy between internal energy and external energy. A deeper analysis will also involve Dirac sea hole current effects as well as lifting of electrons from the Dirac Sea and combination of unobservable Dirac sea holes and electrons without radiation. However, we leave that for the advanced theorists. A taste of it is included in Chapter 9.



open capacitor to change field energy into stress potential energy

Note: System is designed with a certain resonant frequency At that frequency, the current can become mostly "squeeze" and "relax" as a standing wave emerges and stabilizes

open capacitor to change field energy into stress potential energy

Whether COP>1 0 or not depends on successful additive collection and use of the Heaviside nondiverged energy flow component due to the multipass and reflection operation

Figure 4-7 Tesla's resonant single wire circuit **operation.**

But is there any evidence for this "shuttling" of the monopolar potential in Tesla's circuits? Yes, there is, and indeed some of Tesla's patented circuits do exhibit such energy shuttling in them, as rigorously shown by Barrett {124, 286a, 286b}.

4.4.4 Other Considerations

For COP»1.0 systems and some COP>1.0 systems, the concepts of Chapter 9 must also be applied, since the system outputs not only positive energy but also negative energy. The negative energy — in the form of Dirac sea hole current — then sweeps back through the system from its output section to its input section. At various places, these "vacuum holes" eat electrons (as on atoms, causing ionization).[115] In short, the Dirac sea holes are converted to more normal lattice holes, and thus can be dealt with in the same fashion as semiconductor designers handle lattice hole problems inside their semiconductor designs. Positron (hole) effects are well known in materials science, and are increasingly being used in actual systems such as the antimatter (positron beam) microscope {266a-266b}.

We accent that a simple LC oscillating circuit does not produce COP>1.0 of itself. If, however, the charges in the currents surging to and fro are in particle resonance at the "feed frequency", then they will "sweep out" a greater geometrical cross sectional area to intercept additional Heaviside energy flow existing outside the normal "static charge" Poynting energy flow. This is similar to the "intercepting resonant particles " process utilized by Bohren {257}, and it allows output of more EM energy than the operator inputs *in the calculated Poynting component* of his own input energy flow. It *does not* output more EM energy than the operator inputs in the sum of his Poynting input component and his Heaviside input component.

The real energy conservation law is that the input energy from all sources and of all types must equal the output energy of all types, where by

---

[115] The union of a Dirac hole (4-space negative energy electron before observation) and **a** positive energy electron before observation, can occur without radiation. The two curvatures of spacetime involved are equal and opposite, so they just get **replaced** by a flat spacetime, which involves a filled Dirac sea (all the holes filled with electrons). In short, the energy can go into changing the stationary local double re**curvature** of local spacetime, by a sort of "superposition of two spacetime curvatures", to give a net flat spacetime, rather than dynamically radiating EM energy away at the speed of light. However, if either of the two interacting particles has been observed, this is not the case and standard pair annihilation will be observed. The point is that particles in their unobserved *mt* state rather than their observed *m* state, can interact without observation, similar to the way that wave-to-wave interaction occurs in nonlinear optics.

"output" we mean output as useful energy and output as loss or non-useful energy.

So conservation of energy flow is not violated, because one also inputs an additional *Heaviside nondiverged* component, unknown to Bohren. Circa the 1880s or early 1890s, Lorentz arbitrarily discarded it from accountability. One does not have to "pay" for that *nondiverged* and *unaccounted* input energy flow component. Except in continually applying Lorentz's integration trick to discard it, the nondiverged Heaviside component has been almost totally neglected in the textbooks since Lorentz arbitrarily discarded it back there circa the late 1880s. However, it is roughly dealt with in near field antenna theory, sometimes under the topic of "Poynting energy bunching". In the near field, e.g., there also may be a substantial *longitudinal* E-field component. One region may be oscillating back and forth along the flow direction, while the region in quadrature may be flowing in only one direction.

By causing the intercepting charges themselves to resonate and sweep out a greater reaction cross section in an energy flow, the normal definitions of "field intensity" and "potential intensity" are no longer true, because their reaction intensity to a unit point *static* charge has been used as their stated "magnitude". The conventional definition is only for an indication of the *intensity* of the energy flows comprising the field and potential. With the unit point *resonant* intercepting charge rather than the assumed *static* charge, the reaction cross section for the same charge increases, and so the "apparent magnitude of the (intercepted) field intensity" also increases beyond what is in the textbook. So far as I am aware, there is no previous precise term associated with this phenomenon, except to lump it in the euphemism of "negative absorption of the medium" or "negative resonance absorption of the medium" in certain materials {267}. It is more nearly a Poynting energy amplification process, since the "intercepted" or Poynting component of the energy flow is increased. Thus it can be a mechanism for COP>1.0, if the closed current loop circuit's use of half the collected energy in the circuit to kill the source dipole is also defeated.

Nonetheless, energy bunching or Poynting component amplification by altering the reaction cross section function of the intercepting particle is a legitimate way to provide excess "free" energy input for COP>1.0 EM power systems.

4.5 Perspective on Tesla vs. Marconi

Tesla was neither deluded nor mistaken, though some electrodynamicists have mistakenly considered him in that light. On the other hand, Jackson — one of the leading electrodynamicists of our time — pays Tesla a significant compliment as follows {268}.

> *"In U.S. patent no. 787,412 (April 18, 1905), reprinted in Nikola Tesla, Lectures and Patents and Articles. Nikola Tesla Museum, Beograd, Yugoslavia (1956), this remarkable genius clearly outlines the idea of the earth as a resonating circuit (he did not know of the ionosphere), estimates the lowest resonant frequency as 6 Hz (close to the 6.6 Hz for a perfectly conducting sphere), and describes generation and detection of these low-frequency waves. I thank V. L. Fitch for this fascinating piece of history."*

We also point out that many present science texts err by continuing to credit Marconi with the *discovery* of radio, although he certainly did much to pioneer it and received a Nobel Prize in 1909. Hertz must be given credit for the first deliberate signal transmission per se, during the period 1886-1888. As his transmitting antenna, Hertz used an end-loaded dipole with a gap, and as his receiver he used a resonant square loop antenna with a gap {269}. Sparks produced at the gap in his transmission antenna resulted in sparks appearing at the gap in his receiving antenna.

Marconi became obsessed with Hertz's results nearly a decade later, and in mid-December 1901 Marconi announced the reception of signals at St. John's, Newfound that were transmitted across the Atlantic from Cornwall, England. He later recorded radio signals transmitted around the Earth, and began regular trans-Atlantic message service in 1903.

Marconi's patent {270}, however, was eventually overturned by U.S. Supreme Court decision {271}, because Tesla's patents (and demonstrations) substantially preceded it. Tesla also demonstrated radio transmission before Marconi, and Marconi actually used a modified Tesla circuit in his famed transmission in 1901. Nonetheless, this is not to detract from Marconi's accomplishments; he definitely put "wireless communications" on the map. It is simply to give *discoverer of radio* credit where credit is due.

Tesla was also closer to the truth of the form of an EM wave in space than are modern electrical engineering and most electrodynamics texts. In the present book we have stated that what exists in 3-space as the so-called "transverse EM wave" are actually longitudinal EM waves and functions of them, with the energy entering each 3-space point from the accompanying time-polarized (conjugate) EM wave at that point (i.e., from the time domain) and emerging in 3-space in the form of a longitudinal EM wave, in 1:1 correspondence.[116] This is followed by a return of the energy from 3-space back to the time domain. This "circulation" from the time domain to 3-space and back to the time domain occurs at every point dipole in 3-space. Only the presence and combination of both the time-polarized photon and the longitudinal photon at each point in an EM wave makes the wave "observable", when we translate into wave phenomena the photon phenomena pointed out by Mandl and Shaw {19}. What spreads as EM energy flow in space (from a source charge) is the local polarization of the vacuum, associated with this giant negentropy circulation from time to the negative charge, to the positive charge, and back to time.

The notion of the transverse EM wave flowing through space is an artifact of the ubiquitous *substitution of the effect for the cause* in Maxwellian electrodynamics. E.g., a completely erroneous "definition" of the causal field (as it exists in space prior to interaction with charged mass) is given as the *effect of its interaction with a ubiquitously assumed unit point charge at every point in space where the field is present.* This in fact substitutes the effect (existing *after* the interaction) for the cause existing *prior to* the interaction. That of course is a gross non sequitur.

We give a concrete example from the first edition of a standard dictionary of physics and mathematics {272}:

> *"**electric field...** 1. one of the fundamental fields in nature, causing a charged body to be attracted to or repelled by other charged bodies; associated with an electromagnetic wave or a changing magnetic field. 2. Specifically, the electric force per unit test charge."*

---

[116] Later we shall deal a little further with how EM energy iteratively recurs statically in 3-space and propagates dynamically and continuously in 4-space, in more detail. The solution to the long-vexing particle-wave duality is the process of observation. Before observation, an entity is dynamic and continuous in spacetime, not 3-space. After observation (by emission of a photon), it is a momentary frozen 3-snapshot (particle) at a single instant of time. At the next immediate instant, a photon is absorbed, reconverting the "static snapshot" into a dynamic 4-entity again. Since observation (photon emission) and de-observation (photon absorption) iterates at extremely high rate, the entity and each tiniest part of it oscillate back and forth between being a frozen 3-entity (particle) and a dynamic 4-entity (wave).

In the first definition, the field is given as the "cause" of the interaction that exists between like and unlike charges. In the second definition, the field is given as the effect — of the interaction with a test charge — of *something undefined* as the cause.

An entirely different "definition" is given by Gray and Isaacs {273}:

> *"**electric field** ... The space surrounding an electric charge within which it is capable of exerting a perceptible force on another electric charge."*

Here it is defined as simply the space around an electric charge, and not really the cause or effect of anything, unless that local spacetime has been curved (which it has).

Not to belabor the point, this sort of thing led Feynman to "define" the EM field in this fashion {274}:

> *"...the existence of the positive charge, in some sense, distorts, or creates **a "condition"** in space, so that when we put the negative charge in, it feels a force. This potentiality for producing a force is called an electric field. "*

So Feynman made the electric field a *condition in space* surrounding a charge, where the condition can produce (has a potentiality for producing) a force on another charge. He also was aware that force is an effect of the reaction of the causal field with charged mass, in the following statement {275}:

> *"...in dealing with force the tacit assumption is always made that the force is equal to zero unless some physical body is present... One of the most important characteristics of force is that it has a material origin..."*

In Maxwell's theory, the electron, atom, and nucleus had not yet been discovered, and electricity was considered a thin material fluid, flowing in a wire (hence the name "currents") much like water through a pipe. The surrounding space was considered filled with a thin material fluid called the luminiferous ether. A very rough notion existed that the "shaking" of the ether disturbance coming in to an antenna would disturb or perturb the electric fluid in the wire directly. Hence, if one "measured" a transverse oscillation of the electric fluid in the wire due to this "detection", it conclusively "proved" that the incoming ether-perturbations were also transverse. On that notion — together with Faraday's notion that "field lines" were taut physical strings, so that "field perturbations" were naught but plucked oscillations of these taut strings — the entire notion of the transverse EM force field wave in space was created.

It really is not that way, as is easily shown with modern re-examination of what happens in the receiving wire, considering the Drude electron gas {276} and electron drift velocity. Today we know that the electrons move *longitudinally* down the wire only with a small drift velocity (usually a few inches per hour), while the signal (field) races longitudinally down the wire at essentially light speed or nearly so.

The electrons are longitudinally constrained in the wire because of the vast number of electrons ahead of them that tend to repel their longitudinal movement. The electrons are far less constrained laterally in the wire. However, each electron is also spinning, and its 3-space performance may be compared to a spinning gyro, whose spin axes are now longitudinal restrained. Accordingly, the electrons readily *precess laterally* in the wire[117] when perturbed *longitudinally* by the incoming longitudinal 3-space components of the "wave in vacuum" — by gyroscope precession theory. The electrons at the surface layer of the wire are somewhat less constrained longitudinally, and they "slip" a little down the wire in each oscillation, accounting for the very slow electron longitudinal drift velocity.

Accordingly, one of the most important dynamics of the circuit is the dynamics of the surface charges, as pointed out by electrodynamicists {277}.

If the incoming waves were true lateral waves, there would be no longitudinal force component on the laterally precessing electrons, and coherent current would not flow longitudinally in the wire at all. Instead, one would just get some longitudinal to and fro noise in the coherent lateral motions of the electrons, due to electron collisions.

---

[117] It is this lateral precession movement of the electrons that is "detected" in most of our instruments. To the early electrodynamicists prior to the discovery of the electron, this detected lateral motion was considered the "shaking of the material electric fluid" in the detecting wire. It was thought that the incoming "electric fluid" from space also had to be material (in the material ether) and transverse, because otherwise the oscillations from space could not have mechanically transferred their "lateral oscillation" to the electric fluid in the wire. Faraday's "material lines of force" concept and the notion that EM disturbances (waves) were simply the mechanical pluckings of these taut strings which also involved similar "material ether" concepts.

Nonetheless, it seems we are stuck with the ubiquitous transverse EM wave model. For more than 100 years, scientists have universally substituted effect for cause in the case of much of electrodynamics — as in the continuing substitution of what is *diverged from* the field and potential at each point in them, by an assumed static point charge, as being the magnitude of the field or potential itself at that point. At best, what is diverged from the field or potential is an indication of the point intensity of the energy flows comprising the field or potential at each point, and in the case of the field, of the prevailing direction.

So electrodynamics is still riddled with that nearly all-pervasive error, and it seems it will likely never be corrected. The leaders of the scientific community do not seem to wish it done and will not allow it to be funded. In short, the community is so comfortable with that grave error that it will almost defend it to the death. The so-called transverse EM wave in 3-space has come to be accepted as if it were a law of nature.

Occasionally a journal will point out the terrible non sequitur in the prevailing notion of the EM wave in space as a "plane wave of oscillating orthogonal E and H fields along the x- and y- axes moving at light speed in the z- axis direction." Romer, former editor of *American Journal of Physics,* provides a prime example {278}. Romer takes to task:

> *"...that dreadful diagram purporting to show the electric and magnetic fields of a plane wave, as a function of position (and/or time?) that besmirch the pages of almost every introductory book. ...it is a horrible diagram. 'Misleading' would be too kind a word; 'wrong' is more accurate." "...perhaps then, for historical interest, [we should] find out how that diagram came to contaminate our literature in the first place."*

At any rate, once we understand how the real EM wave exists in space, then we can sympathize with Tesla's view of it from the following {279}:

> *"Tesla upholds the startling theory formulated by him long ago, that the radio transmitters as now used, do not emit Hertz waves, as commonly believed, but waves of sound... He says that a Hertz wave can only be possible in a solid ether, but he has demonstrated already in 1897 that the ether is a gas, which can only transmit waves of sound; that is such as are propagated by alternate compressions and rarefactions of the medium in which transverse waves are absolutely impossible."*

In Tesla's own words {280}:

> *"...I showed that the universal medium is a gaseous body in which only longitudinal pulses can be propagated, involving alternating compressions and expansions similar to those produced by sound waves in the air. Thus, a wireless transmitter does not emit Hertz waves which are a myth, but sound waves in the ether, behaving in every respect like those in the air, except that, owing to the great elastic force and extremely small density of the medium, their speed is that of light."*

From quantum field theory, the instantaneous scalar potential in space is actually a coupling of a scalar photon and a longitudinal photon {19}. The only EM component in 3-space is that longitudinal photon.[118] Transforming to wave language, Tesla appears to have been correct in his view of the longitudinal form of the EM wave in 3-space, whereas all the texts are still wrong even today.[119] However, Tesla was also noted for grandiose pronouncements, a trait which certainly did not endear him to the struggling electrodynamicists of the time, even when he was correct and they were wrong. An example is the following {281}:

> *"The Hertz wave theory of wireless transmission may be kept up for a while, but I do not hesitate to say that in a short time it will be recognized as one of the most remarkable and inexplicable aberrations of the scientific mind which has ever been recorded in history."*

Unfortunately, in electrodynamics we are still stuck with that "most remarkable and inexplicable aberration" today, and we will remain stuck with it until the leaders of the scientific community (such as the National Academy of Sciences and National Science Foundation) recognize it and fund a complete overhaul of the foundations of classical electrodynamics, which is so sorely needed. On the other hand, *one should not hold one's breath while waiting for the mountain to come to Muhammad! One might as well ask the stars to fall from the sky as to ask the leaders of the scientific community to correct the serious foundations errors in physics and especially in electrodynamics.*

---

[118] Hence it is not surprising that all EM in 3-space decomposes into bundles of longitudinal EM waves and their dynamics, as shown by Whittaker {85, 91b}.

[119] However, Tesla did not appear to realize the involvement of time-energy transduction to longitudinal KM 3-space wave energy and vice versa.

4.6 Conclusion

Hopefully we have set the stage for our next chapter, where we will be advancing mechanisms and approaches that have been tried by a variety of researchers. Several of these researchers have indeed produced COP>1.0 devices and processes. However, at this writing none of the devices produced by these inventors and researchers are in production and on the market. As we mentioned in Chapters 1 and 2, there are very powerful forces that have been applied to prevent such development.

Briefly, such suppression has resulted due to one or more of the following:

(a) Sheer greed by the group that gathers around the inventor/researcher, including multiple competing investors and/or "backers". Often a struggle for control develops, and the project is decimated in the process. In many cases a legal struggle also develops, with the result that the legal status of the invention may be fouled beyond repair.

(b) Naivete on the part of the inventor and his surrounding group. The inventor needs the frequent advice of a patent attorney, a regular corporate attorney, a person familiar with research and development projects and procedures, a person expert in testing (particularly with sophisticated multichannel digital oscilloscopes which gather multiple channels of data simultaneously and integrate under the curve, an accountant, and a person skilled in negotiation with potential investors and backers. Most inventors do not have access to all that, or only have access to it after much of the die has been cast and serious mistakes have been made.

(c) Animosity and fierce attack from the scientific community and self-appointed "defenders of the faith". Few inventors are prepared for the onslaught that awaits them if they succeed in producing a genuine COP>1.0 electrical system. Slander and libel are just part of it. An inventor or researcher caught up in always trying to defend himself against vicious ad hominem attack is an inventor successfully deviated from his work. The family also often suffers.

(d) Just now, after the Enron fiasco much of America is becoming aware that powerful organizations often pull out all the stops in a blind pursuit for money and power. Of course they have done so for a very long time; this is nothing new. The inexperienced inventor or researcher is ill prepared for the fact that portions of government organizations,[120] national labs, universities, etc. may be precisely that way also! U.S. government laboratories also file patents; check it out! Check out Fullerton's defense of his patent rights for his ultrawideband communication system work.

The people in any large organization form a bell-shaped distribution curve. About 9% of that curve represents folks who have — to put it mildly — little ethics when it comes to position, power, and money. Some of these 9% fellows will go to quite some length to twist the patent or part of it or control of it away from an inventor. An inventor who has never heard of "march-in" rights (a neat little "theft" phrase favored by DARPA, for example) is often an easy mark. Government agencies will be on an interesting invention and its hapless naive inventor like vultures on a fat calf. They dangle some money and a contract to "assist the inventor to get his invention developed". There is a little clause in the fine print of the contract where the government reserves "march-in" rights. This is a hidden bombshell that really says the government — *anytime it wishes* — can just unilaterally declare that the funded inventor isn't getting the invention to market fast enough, so a single bureaucrat just *seizes it* — in the name of the government, of course. Anyone who has been in serious aerospace contracting very long is also aware of the deals between a few government fellows who control award of the funds, and their "favored contractor". If enough business is steered to the contractor by the government person, it is implicitly understood that when the government fellow retires, he goes to work for that company with a Vice President position, lucrative salary, and a fat stock option. It's easy to become an instant millionaire or multimillionaire that way. A small percentage of government contracts are actually contaminated in such a hidden fashion. The universities usually are much more open and blatant, and just put in a clause that says, "All patents revert to the university!" Also, the inventor must be aware of the difference between "nondisclosure" and "non-circumvention". Just try getting the latter clause from a university, or either clause from a government agency (yes there are rules for "proprietary information", and they are widely violated). Non-circumvention means the outfit agrees not to change a coil or something, and go and patent your invention. Nondisclosure means they just agree not to talk or write about it openly.

---

[120] Interestingly, the government is not allowed to copyright its own publications by federal servants. Neither should the government be allowed to patent its own inventions by federal servants and federal agencies. This has set up direct conflict in the federal funding channels for the taxpayers' funds intended for independent research, providing a wonderful opportunity for hanky panky by that lower 9% of the people comprising any large group. By the bell-shaped distribution curve, those comprising that 9% will rise to the opportunity. They are manipulative, greedy, and some are immoral and self-serving. Partially coupled with a similar low "bad apple percentage" in the contracting game, this enables many travesties in the name of federal research and development with respect to patents and misdirection of funds.

(e) And yes, in addition to these many "petty" little conspiracies, there really is a *great* conspiracy — in fact, there are many of them. Churchill just referred to the entire set of conspiring cartels as the "High Cabal". This is a loose-knit set of extraordinarily wealthy cartels that between them control much of the financial power of the world. You can only find the principals behind a couple of hundred interlocking corporations, if you penetrate deeply enough. Much of their great financial income comes from the control of energy at its various levels, through a net of interlocking corporations. Something like $2 trillion dollars per year is their "take" from energy worldwide. Oil plays a great role in that. These "high cabal" fellows make or break nations financially, as is almost being done to Argentina as this is being written. They also have been stopping COP>1.0 electrical power systems since shortly after the turn of the century, using whatever means are necessary — fair or foul. That is why we still are burning oil, coal, and natural gas, and why our automobiles and trucks run off gasoline and diesel, and not off free electrical energy from the vacuum. The high cabal intends to keep it that way. Some of the major primary means of "stopping" an invention have been as follows:

a. Manipulation and improper use of the law (Gray's production line was shut down by law officers before his engines could roll off there and onto the market).

b. Involving the unsuspecting inventor in drug charges by planting drugs on his property surreptitiously, then secretly notifying the drug enforcement officials who suddenly raid the premises and discover the narcotics, resulting in the inventor going to jail since he has been caught "red-handed".

c. Threatening the inventor's life and the lives of his family, to frighten him away from what he is doing.

d. Arranging a fatal accident for the inventor, such as a fatal auto accident, a fall from a high place, or drowning.

e. Assassination (hit men are fairly simple to hire; a good one is a bit more difficult to hire but is doable. A good hit man might assume a disguise and fake a robbery, shooting and killing the target in the "robbery". In an extreme case, he just fires at a distance with a professional sniper rifle that is silenced. A variation is the use of a "throwaway" assassin, a fellow who has been deeply conditioned by very harsh methods, to deeply involve his autonomic nervous system. He can be spotted by the "glaring eyes" effect of autonomic nervous system involvement. This fellow is only marginally functional in real life, and requires a handler. He also must "fixate" for some minutes (usually from 20 to 30) on the target, by staring at him for a period. Then — say, the next day — while the target is at lunch in a public restaurant, the throwaway walks in, walks straight to the target, and empties a pistol in him at point blank range. He remains there until the police arrive and arrest him. He is immune even to torture; nothing can be gotten out of him, even by electrical shocks on his genitals. There are two levels of throwaways; that is the older and less functional version produced by very harsh means. The more modern version is without the glaring eyes with white showing above the iris; this fellow is more functional, fixates very quickly (couple minutes to five minutes), and can operate without the close immediate presence of the handler.

f. Making the inventor an offer he "cannot refuse", in the old Mafia sense. In the latter, nicely dressed persons come to the inventor's house, meet with him, and offer him a large sum of money to quit what he is doing for the rest of his life. The going sum varies between $5 million and $10 million, usually. The offer is real and it cannot be refused; either the inventor accepts it, or he and all his family are dead when these gentlemen leave the premises. If the inventor refuses anyway, he and his family are killed.

Usually the bodies also just "disappear" and are never found or heard from again.

g. These days, variations are used such as a careful crash of another auto into the back of the inventor's car so he is really shaken up badly but not seriously hurt. He goes to the hospital for checkup, in case of concussion etc. Everything is seemingly okay, but he is kept overnight for observation. That night he is given a hypodermic of air in his veins. Next morning his family receives a call that the inventor has suffered seizures from an apparent concussion after all, and is fighting for his life. If he doesn't die, he becomes a human vegetable. Piece of cake.

h. Then there's the ice dart dipped in curare. The curare paralyzes the muscles of the heart and lungs; the inventor goes down in convulsive floundering, gasping and unable to breathe or to pump blood. He expires very quickly. The curare breaks down in the body, the ice melts, and you have a fellow the medics find died of convulsive heart seizure, etc. Works like a charm. This is an adapted "dirty spooks" trick, adapted from those branches of the intelligence communities of the world that specialize in assassinations.

i. Use of "gaming", which was originally developed to influence or change the behavior of foreign leaders. Imagine writing a scenario, as for a movie. Only you have the deep psychological profile of the targeted individual. You also have the deep psychological profiles of quite a few other individuals who have "knee-jerk" reactions in a certain direction useful to you in your games (in your scenarios). These are called "agents of influence" since, to get them into interacting with the target, only a phone call or other contact need be made and a stimulus given, and they are off and running, self-powered and going after that target with their knee-jerk response. So very sophisticated computers are used, the scenario (intended plot of events to happen) is prepared (the artificial intelligence programs will even give the probabilities of success of all the variants), and a recommended scenario variant is derived and accepted. Then the controller has one or more agents working **for** him that contact the players (the agents of influence). They get their phone calls or stimuli, react in predictable fashion, and come pell-mell at the inventor, interacting all over the board with him. The range of games is enormous, from stock schemes to lawsuits to infiltrating agents of influence into the internal organization of the inventor to money laundering, etc. The controller follows the progress, and only once in awhile makes slight adjustments (may need to trigger other agents of influence, send in one actual agent, etc.). Over the last 20 years, the gaming has become very expert. So many games can be launched against a single inventor that he usually is finished or nullified by one of them, eventually. Having been gamed over 200 times in the last two decades, I plan to write a book one day on the subject of the games and what to watch for.

j. Finally, here is a sad and disconcerting rule, usually true. If you gather six persons together that you have known for years or even all your life, and they are the nucleus of the organization around you, watch what happens when success occurs and you really do pull EM energy from the vacuum and power loads, lights, etc. One-sixth of the population, seeing that, will shortly contract a very strange malady known as "gold fever". It is not just an *obsession;* instead it becomes an all-consuming *possession* almost in the biblical sense. An individual possessed by gold fever would kill his own grandmother to try to gain control of that system. If one or more of these "gold fever" transformations occur, that sets the group into profound conflict and vicious infighting, on every front. You get sabotage of equipment, sabotage of demonstrations, stealing of equipment, legal shenanigans, just name it. This has destroyed many groups. It will destroy many more.

k. A variation is to send in a special agent who penetrates the group and becomes a member. Indeed, the high cabal has certain persons who specialize in just such penetration and are specialists at setting up disruption. They have had plenty of practice, and are very good at their trade. The identities of some of these "special agents" would surprise the casual observer. The so-called "overunity community" is rather strongly penetrated and misdirected by a number of such special agents, in addition to a greater number of agents of influence.

1. Finally, the technical knowledge of most inventors and researchers in this field has been largely limited to ordinary electrical engineering and electronics. This means that the inventor often forms his own lexicon and way of thinking about how he does the "magic" COP>1.0. It may be difficult or impossible to connect the way he thinks back to legitimate physics. Further, most of the COP>1.0 community, the majority of electrical engineers, and nearly half the physicists do not understand the technical difference between the *efficiency* of a power system and its *coefficient of performance.* We have insured that the reader of this book will know the precise difference — it's even in our glossary! Further, the entire group around the inventor, and the inventor himself, may not have a clear understanding of the source of the extra energy, the mechanism by which it is obtained, or even the difference between a system in equilibrium with its active vacuum environment and one in disequilibrium with it. Most engineers and a great number of scientists also are still unaware of the dramatic difference between the thermodynamics of equilibrium systems and the thermodynamics of disequilibrium systems. Many have no notion of what the active vacuum is or does. So the inventor may actually be able to build the device himself, but may later err and actually build it away from COP>1.0 with further development.

m. Another problem can be measurement. Sometimes very simple errors — such as "measuring" highly nonlinear, spiky signals with an RMS meter, or using an inferior oscilloscope, or using inferior probes with good oscilloscopes, tricks a relatively inexperienced inventor himself into believing his unit achieves COP>1.0 when it doesn't. Also, some standard engineers will insist on calorimetry, which is inappropriate for COP>1.0 EM systems since they output a mix of both positive and negative energy. The positive energy will heat the calorimeter fluid and the negative energy will cool it simultaneously, and the "expert measurer" will always measure the difference and thus COP<1.0 with his calorimeter (unless the inventor is a rare one who has also transduced the negative energy fraction of his output into positive energy). Yet the conventional engineer or scientist — who has never seen negative EM energy or a COP>1.0 EM system in his life — will be so confident from his "positive energy only" thinking that he will be completely convinced that a real COP> 1.0 system, measured with a calorimeter to show net positive energy COP<1.0, is *actually* a COP<1.0 system instead of the error in measurement that it is. One of the purposes of this book is to try to explain such things and get a better procedure and protocol made available for the testing.

n. Finally, there are a few actual charlatans who deliberately deceive both the group around them (if it's sufficiently naive) and naive investors and backers. E.g., if one builds a huge starter motor (very high current, very high torque, cannot run long without burning up!) and puts it in an automobile, then fills the back of the automobile full of batteries, that beast will draw 400 amps and leap across the pavement or warehouse floor with an agility one is shocked to see. Then if the inventor is always "having difficulty with his controller unit", and "everything will be fine once the controller problem is licked" or some such, many small and naive investors will leap to invest their life savings eagerly. There are many other scams also, and unfortunately every experimental field, with great financial promise if successful, does attract them. Here the old adage is best: If it is just too good to be true, it probably isn't. One should insist on a technical explanation of the source of the excess energy, the mechanism by which it is taken from the environment, how asymmetrical self-regauging of the circuit occurs, etc. If these questions cannot be answered, the inventor himself does not know what he is doing. At best, he cannot explain it; or he may just be honestly mistaken. In the worst case, the inventor knows it is not genuine, but is deliberately deceiving the investors. So my advice would be to first assess the scientific level of the understanding of the inventor group. Then get an independent test of the device or see one done properly. Then decide whether what you have seen and heard is real or not.

o. Meanwhile, there are from time to time legitimate COP>1.0 systems initially developed. The place where all of them have failed is where the inventor group seeks to obtain the appreciable financing (something like 30 million dollars is required these days) to complete the phenomenology experiments, modeling, scale-up factor determination, and prototyping before a production model can be built. To date, every one of the legitimate COP>1.0 systems has foundered and failed right at that sheer vertical cliff. Our own MEG system is at that cliff at the moment, so that cliff is very near and dear to the hearts of the five of us who have struggled so long and invented the MEG. Time will tell whether we succeed where all the others have failed, or whether we also just get defeated by the cliff. As of this writing, we have not yet obtained the necessary capitalization. But we are giving it our very best try, and we believe we will win it eventually.

Chapter 5

Selected Approaches to Overunity Power Systems

> [On point-contact transistors]. *"First, the theory underlying their function is imperfectly understood even after almost a century..., and second, they involve active metal-semiconductor contacts of a highly specialized nature. ...The manufacturing process is deceptively simple, but since much of it involves the empirical know-how of the fabricator, the true variables are almost impossible to isolate or study. ... although the very nature of these units limits them to small power capabilities, the concept of small-signal behavior, in the sense of the term when applied to junction devices, is meaningless, since there is no region of operation wherein equilibrium or theoretical performance is observed. Point-contact devices may therefore be described as sharply nonlinear under all operating conditions. "* [William B. Burford III and H. Grey Verner] {282}.

5.1 Introduction

In this chapter we present a selection of potential overunity notions, inventions, and experiments by various inventors and researchers. Its purpose is to show some of the more relevant work that has been done, and hopefully to stimulate new thinking by the interested reader. It is not intended to be all-inclusive, but merely representative. Most of the work addressed is by other inventors and scientists, and we give an appropriate commentary from our viewpoint as best we understand the invention and the process used. Not all the concepts presented can be clearly explained, though some can and are.

This is not intended to be a "kit of parts" or an assembly instructions type of presentation. For that, the interested researcher will have to rely on his or her own ingenuity and lots of bench experiments, because no such "kit of parts with instructions" for COP>1.0 electrical power systems exists at present {283,284}.

5.2 Tesla's Shuttling of Potential Energy and Barrett's Extension

See Figures 4-4 and 4-5 in Chapter 4. In his patented circuits, Tesla accomplished the novel function of "shuttling" the potential itself (and therefore potential energy) around in the circuit at will. This startling function accomplished by Tesla is impossible to see in a conventional vector or tensor analysis of his patented circuits, but it is clearly evident in a higher symmetry EM analysis of them. So it does not appear in the conventional texts, which use vectors or tensors for their circuit analyses. Barrett, one of the leading higher group symmetry electrodynamicists and also one of the pioneers of ultrawideband radar, utilized quaternion electrodynamic analysis to clearly show this novel effect in Tesla's actual circuits {285}. Thus, Tesla was able to produce and move around asymmetrical self-regauging in his circuits, wherever he wished. That has been totally missed by scientists prior to Barrett's revealing analysis.

Barrett then went on to extend Tesla's basic mechanism and employ it for communication and radar purposes, obtaining two patents {286a-b}.

It would appear that use of such shuttling techniques is probably applicable to reducing the back emf in conventional nonshuttling circuits, leading to new COP>1.0 mechanisms. The definitive answer remains to be determined by some future researcher.

5.3 Moray's Radiant Energy Device

One of the remarkable examples of a successful COP>1.0 system was the radiant energy system of Dr. T. Henry Moray of Salt Lake City, prior to World War II. Figure 5-1- shows Dr. Moray and his final 50 kW unit, powering an assembly of light bulbs {287}. The device weighed 55 pounds, used an antenna connected as a "signal input" from the ether, but needed no input of electrical energy by the operator in order to achieve its steady power output.

As shown in Figure 5-2 and Figure 5-3, the various Moray tubes were complex in structure. In addition to various grids, they usually contained (in quadrature) three or more amorphous semiconductor pellets pressed in large presses and sintered with locked-in stresses. One points out the presence of optical effects including phase conjugation, possible use of the built-in stress as a sort of self-pumping and mild self-amplification, possible iterative feedforward and feedback loops due to iterative phase conjugation, collecting of additional energy from the usually nondiverged

Heaviside component via the iterative reverberation of energy, and non-interfering fields in quadrature.



Figure 5-1 T.Henry Moray's 50-kW unit.

The blown quartz tube envelope, in the dark of an enclosure, is open to the passage of infrared (heat) and ultraviolet, which spans a harmonic interval. This allows the passage *of difference* frequencies as sine waves without breakup, even in a nonlinear isotropic environment. Moray stated unequivocally that the tubes would not work unless the envelopes were made of blown quartz. The pellets (shielded from outside light) would nonetheless receive IR input from the ambient temperature, and probably triggered at least weak UV due to the radioactive decay continuously ongoing in the semiconductors. We point out that the UV band is roughly twice the frequency of the IR band, so the "difference frequency" is roughly the IR band itself. In short, it may be that "difference frequency" IR is thus processed in Moray tubes in much more sophisticated fashion than has previously been suspected, including in a self-amplifying (regenerative) manner.


MORAY PELLETS MADE OF MIX OF SEMICONDUCTOR MATERIALS WITH RADIOACTIVE INGREDIENT, PRESSED UNDER HIGH PRESSURE AND SINTERED TO LOCK-IN STRESS.
SIMILAR TO JOSEPHSON JUNCTIONS IN SOME WAYS ALSO TO POINT CONTACT TRANSISTOR.
USED SOPHISTICATED FEEDBACK AND FEEDFORWARD BETWEEN MULTIPLE STAGES, SIMILAR TO MULTITRANSISTOR COP>1.0 UNIT PLACED IN ORIGINAL MINUTEMAN MISSILE BY WESTINGHOUSE.
LOCKED-IN STRESS MAY PLAY A SIMILAR ROLE AS THE BARRIER POTENTIAL IN FOGAL SEMICONDUCTOR.
NOISE-FREE RECEPTION THROUGH THE EARTH OF BYRD'S POLAR EXPEDITION INDICATES LW EM RECEPTION.
JUNCTIONS
MANY CONTACTS AND JUNCTIONS BETWEEN SPECIAL MORAY PELLETS.
MANY TUBES MADE TO GET ONE THAT DOES REQUIRED FUNCTIONS.
JUNCTIONS
THE DEVICE WOULD SEEM CAPABLE OF SELF-OSCILLATION VIA CONTROLLED CHAOTIC OSCILLATION (29 STAGES).
BLOWN FUZED QUARTZ ENVELOPE ALSO ACTS AS SET OF NANOCRYSTAL OSCILLATORS WITH LOCKED-IN STRESS.

Note: see T. H. Moray, The Sea of Energy in Which the Earth Floats, Fifth edition, Cosray, Salt Lake City, 1978, p. 70.

Figure 5-2 Diagram and some novel features of T. Henry Moray's special tube.

The pressed semiconductor pellets were placed in the tube in quadrature, in a sort of "point or junction contact" with each other.[121] Each semiconductor contained a mix of triboluminescent zinc (a semiconductor material), a radioactive material (probably uranium dioxide), and another material of unknown composition, rumored — but not confirmed — to possibly have been diatomaceous earth which also has some unusual properties one may look up. There were some 29 amplifying tube stages in the device. A U.S. patent {288} was eventually granted on an electronic therapeutic unit containing Moray tubes, but the patent on the power system was never granted, although the application was kept current for some years by the Moray family. Eventually the power device patent application files disappeared from the U.S. Patent and Trademark Office.

Although its full technical details were never released, the Moray device is of interest because Moray demonstrated it many times to engineers and scientists, under rigorous measurement conditions, for years. These expert witnesses then signed affidavits to the results achieved by Moray in the tests. Moray also discovered that he could produce an additional 50 kW of power simply by inserting an additional tap just prior to the formal output.

---

[121] Indeed, the junctions of such sintered pellets are most interesting. Such a grainy junction can be compared to a host of very close point contact junctions, particularly with finely-ground powdered materials used in the pressing and sintering. In essence, Moray's junctions contained a great many "point contact transistors", and it is known that such transistors can behave (particularly under pressure!) as true negative resistors. This also appears to be one of Moray's secrets.



Figure 5-3 A variety of Moray tubes showing their complexity.

Repeated assassination attempts were made against Dr. Moray. While driving his car on the streets of the city, on several occasions he was fired at from an alley or from the sidewalk, but he had bulletproofed the car because of continual threats and ambushes. He was also shot in his own lab in a physical struggle with one would-be assassin, but survived although seriously wounded. A Russian company tried to steal the device, and a Russian agent was planted in Moray's lab, gradually sending essentially all the technical details of the Moray device to Russia. That agent later destroyed the unit right in Moray's lab by suddenly smashing it with a hammer.

Moray's tubes were quite expensive and were painstakingly made by hand. He fabricated a number of tubes (as many as 30 or more) before he obtained one that "worked" and exhibited the self-amplifying effect. Over the years, he spent several hundred thousand dollars on the project, which is the equivalent of some twenty million dollars today. The 29 tubes in his final 50 kW unit were the result of years of labor and fabrication of several hundred rejected tubes to get the 29 that worked. Accordingly, once those 29 were destroyed, Moray was never again able to obtain sufficient financing to rebuild his unit.

However, Moray had demonstrated a special type of transistor years ahead of the first transistor patent. He had demonstrated the importance of multiple junctions in transistor materials. Optical and nuclear functioning of the tubes was also woven in with nonlinear oscillations, multiple feedforward and feedback loops, etc. The sophistication of the tubes and feeds alone almost certainly guaranteed chaotic self-oscillation. We suspect but cannot prove that the Casimir effect may also be involved in some of his conducting metallic double surfaces.[122] He had demonstrated a remarkable "tube-with-internal-transistors" that produced energy output self-gain, without any operator input of energy. In addition, he had successfully used his special tube/transistor hybrids to produce a very successful COP>1.0 EM power system.

After Moray's death, his two sons John and Richard continued to try to rebuild the unit, but were never successful due to lack of sufficient funding and lack of a proper scientific team. They do know how to build the tubes, however, and they do know how to build the unit.

It appears that no electrodynamicist or physicist skilled in higher group symmetry electrodynamics ever examined the Moray device or worked with Moray. No particle physicist or electrodynamicist skilled in non-Abelian electrodynamics ever worked with the device. Since broken symmetry was not discovered and proven until 1957, no technical person who worked closely with the unit was ever aware of the various broken symmetries by which some of the virtual energy of the vacuum can be and is transformed into observable EM energy.

---

[122] The "grain" of the stressed semiconducting pellets may be important with respect to the Casimir effect versus the frequency. In short, Moray's contact surfaces between his semiconductors were "grainy" and these grains would have constituted Casimir surfaces. For the importance of the shape of the double surfaces, see M. Chaichian et al., "Quantum theories on noncommutative spaces with nontrivial topology: Aharonov-Bohm and Casimir effects," *Nucl Phys B,* Vol. 611, 2001, p. 383-402.

Certainly no one ever worked with it that understood the peculiar action of the difference frequency in traveling linearly through an isotropic nonlinear medium. John Moray, who stalwartly carried on the Moray lab in Salt Lake City until a few years ago, does know how to build the tubes, and he knows the circuitry for the device. That he does not understand the "deep theory" is of no consequence — no one else does either. In the opinion of this author, a funded scientific team — carefully chosen and working with John Moray — could probably rebuild the Moray device. We would very much like to see a Moray unit in production and contributing to permanently solving the energy problems of the world. Sadly, that does not seem likely.

5.4 Anti-Stokes Emission and Similar Processes

Stokes' law states that the wavelength of the fluorescent light emitted by a phosphor or other luminescent substance is always greater than the wavelength of the radiation used to excite the fluorescence {289}. This condition was observed by Stokes in 1852 {290}. From an energy viewpoint, the collecting medium collects and dissipates some of the input energy in the medium itself (e.g., to accelerate moving molecules) and then emits the remainder of it. The "system" consisting of the medium, the experimenter's input, and the output is such that it usefully outputs as luminescence less energy than the experimenter inputs. Hence it exhibits a COP<1.0, by absorbing excess energy in its "environmental surroundings".

Usually such a "law" generally holds but is sometimes violated in at least a lew cases. Stokes' law is no exception. It applies for most cases of fluorescence and luminescence, but it does not hold for a few of them. In a few cases, the emitted wavelength is precisely the same as the input wavelength. This means that the collector/absorber re-emits all the collected input energy as fluorescence or luminescence. Here the COP = 1.0. This condition is known as the *resonance condition* and the emission is called *resonance emission.*

In other well-known cases, Stokes' law is violated and the energy emitted is greater than the energy absorbed. In other words, the system exhibits a **COP>** 1.0 *with respect to energy emitted versus energy input by the experimenter.* This is known as anti-Stokes emission. It has been well known for six decades that anti-Stokes emmision processes do indeed output more energy than one has to input oneself {291}. This excess energy emission is usually euphemistically attributed to "additions from the internal energy of the molecule" and referred to as "negative resonance absorption by the medium" or just as "negative absorption by the medium".

Unless the excess energy taken from the physical medium of the system is replaced from outside the physical system, the anti-Stokes emission process produces cooling in the physical system and is self-quenching once the medium loses all the energy it can afford. For the overunity researcher, a huge hint is to search the literature for anti-Stokes type emission phenomena that do not result in media cooling. The Letokhov phenomena {292} are in fact such phenomena where the excess emitted energy is received from outside the physical system medium, and therefore from the surrounding active vacuum and/or the surrounding local curvature of spacetime.

Other than for a very few physicists — e.g., Bohren {24}, Letokhov {157}, H. Paul and R. Fischer {25} — there appears to have been little *effective* discussion of where the excess energy "extracted from the molecule" really came from initially, and how it is replenished to the molecule (if at all), and particularly *whether or not it has to be replenished to the molecule by the operator*. There has been no discussion of the local potentials as dipole asymmetries in the virtual energy exchange with the vacuum, although there has been inadequate discussion of the involvement of the Poynting energy flow (e.g., by Bohren, Paul, and Fischer). There has been no discussion of the possible involvement of the Heaviside nondiverged component of the energy flow, which is additional to the Poynting component but unaccounted by today's electrodynamicists. To my knowledge, the broken symmetry of every dipolarity has not been discussed with respect to such experiments.

The reader can see the point. If a mechanism exists or can be evoked to freely resupply the lost energy to the molecule from the other two components of the supersystem, then the resulting *self-replenishing* anti-Stokes emission phenomenon can be utilized as a legitimate and continuing COP>1.0 process. It remains to be seen whether this can be worked out. If we wish, the giant negentropy mechanism of the source dipole and source charge {308} may be considered universally proven cases of self-replenishing anti-Stokes emmission, already exhibited by every charge and dipole in the universe.

At least one audacious scientist — Letokhov — has suggested that similar processes in certain systems can perhaps comprise true Maxwell's demons, yielding excess energy output and perhaps eventually a COP> 1.0 operation {293}. Russell has suggested that a similar COP>1.0 process is involved in the fiber fuse phenomenon {299}.

Over the last few decades there has been slow but important work in an optical area of possible anti-Stokes emission phenomena {294a-c}. A variety of strongly scattering, optically active media have been shown to produce substantially more energy output than the experimenter inputs to stimulate the output. However, most are being done in laser-like pumping situations and so the pump energy has to be furnished by the operator. This means that the "replenishment" energy to the medium is furnished by the operator, resulting in overall COP<1.0 performance. However, in self-oscillation conditions, the medium can be self-pumped (self-replenished, taking its replenishment energy from the active vacuum exchange when viewed in the supersystem), and in such conditions COP>1.0 performance is possible, at least in theory. Presently we know of no one who has achieved it — except in the destructive fiber fuse effect — but the work seems to be progressing steadily toward that eventual outcome.

5.5 Gain in Intensely Scattering Optically Active Media

This modern work — which may be regarded in one sense as extending the anti-Stokes emission effect — is largely being pursued in intensely scattering optically active media. A very nice example is given by Lawandy's experiment {295a-d}, shown in Figure 5-4. Figure 5-4a shows a comparison experiment in water without an intensely scattering optically active medium but with a fluorescent dye to show the emission interaction. Figure 5-4b shows the same experiment with titanium dioxide particles added to the fluid. The TiO_2 particles are sized so that their optical resonance is within the laser's frequency domain.[123]

First, as shown in Figure 5-4a, a small, weak laser beam is aimed into the solution, and a small "warm little glow" of fluorescence results just around **that** region where the laser beam interacts with the solution. Scattering in **the** medium is rather normal, and provides nothing of any great interest to the overunity researcher.

---

[123] In passing, we point out the involvement of the Bohren effect due to particle resonance. This collects additional energy from the usually nondiverged large **Heaviside** energy flow component.



Nabil M. Lawandy et al. "Laser action in strongly scattering media." Nature. Letters. 368(6470). Mar. 31. 1994. p. 436-438.

Fig. 5-4a. Without TiO_2.

A pure dye is dissolved in a liquid (left). A green laser pulse excites the dye (center). A laser pulse of equal intensity is sent into the same dye mixed with tiny particles of titanium dioxide suspended in the liquid (right). The latter experiment produces a much stronger, room-filling glow.

Fig. 5-4b. With TiO_2.

Figure 5-4 The Lawandy experiment

Then the titanium dioxide particles are added, and the same weak illuminating laser beam is directed into the colloidal solution. Figure 5-4b shows the new and spectacular results.[124] Immediately a very bright, room-filling emission of scattered coherent light fills the entire room. The intense optical scattering includes extensive retroreflections for some "ping pong" between individual particles, so that the optical gain is enormous. A highly enhanced energy emission is now evoked, for the same energy input by the operator as was used in the first experiment without the TiO_2 particles. Lawandy's experiment is inexpensive and can be repeated in any university nonlinear optics laboratory and by many individual experimenters. It gives results every time, without fail.

Oddly, no one seems to clearly state that, for a single pulse of input laser energy to the suspension of TiO_2 particles, precisely how much energy was input and how much energy was then emitted by the medium. Instead, "gain" is mentioned, but never the COP = (energy output by medium emission) / (energy input by operator). One suspects that journal referees would probably not allow such a clear and unequivocal statement of overunity, but would apply quibbling and spin control to prevent stating that more energy is output by the medium than is input to it by the operator.

---

[124] This is a very easy and very convincing argument for the presence of the long-ignored Heaviside component of energy flow arbitrarily discarded by Lorentz more than a century ago, and still discarded by modern electrodynamicists.

It follows that, if sufficient "ping pong" iterative retroreflection and multiple collection occurs in the medium, the COP>1.0 because more work is done on exciting the medium than the energy input to it by usual (Poynting) calculations. No one accounts the energy unwittingly input to it by the ignored Heaviside component accompanying the Poynting component. Usually the output/input is just referred to as "optical gain". We stress, however, that we are considering only the actual laser beam energy being furnished into the colloidal solution as input, and we are not calculating the efficiency of the laser, its pumping, etc. Anyway, for this stimulated emission process, it is possible that the COP>1.0, and one can see the parallel to anti-Stokes emission. In short, we are considering the TiO_2 solution itself as exhibiting a true negative resistor action.

The field of high gain stimulated optical emission is advancing rapidly {296}, although many experiments still use external pumping furnished by the operator. If the operator has to pay for the replenishment (pumping) energy as well as the input energy, then the COP<1.0 overall. But the experiments are tending toward sustained self-oscillation and self-pumping conditions. If such conditions are obtained in sufficient magnitude, the process will then become a legitimate COP>1.0 operation overall. In that case, it will be usable as a basis from which to develop self-powering COP>1.0 electrical power systems, particularly for infrared "heating" systems etc.

The more recent experiments have shown positive feedback loops both in the time-forward and time-reversed paths; trapping of light flow energy (both time-forward and time-reversed) in large random walks of more than 1,000 individual interactions; weak Anderson-type localization; and constructive interference of forward time and reversed time light paths. since such experiments can be performed in the infrared, they point toward a potential *"vacuum-energy-powered overunity heater"* as a **feasible** achievement in the future. In our opinion, there should be a determined and major Department of Energy program oriented to develop exactly that kind of system.

Such a heater can become self-powering by the presence of greater governed positive feedback during self-oscillation conditions, which will allow sufficient excess collection due to *multipass multicollection* from the usually wasted giant Heaviside energy flow component. This process —

with the self-excitation occurring spontaneously as a "kick-in" positive feedback process in an exploding gas — probably accounts for the phenomena observed in the gamma ray burster and other such violent "burster" cosmic phenomena. Re-ignition, afterglow, and similar effects are observed in gamma ray bursters. They are also observed with *remarkable* similarity in the latest experiments in intensely scattering optically active materials the laboratory. Similar phenomena occur in x-ray bursters as well, and perhaps even in the recently observed and confirmed gamma ray emissions from intense storm clouds.

Finally, we point out that many magnetic materials are also photorefractive, and they readily produce nonlinear optical effects at various frequencies. Some barium compounds are typical examples. As an example, multivalued phase conjugate reflection can occur {297}. Such effects did occur in the Sweet vacuum triode amplifier, to be discussed shortly. It may be that Sweet's conditioning of his magnets conditioned their barium nuclei into self-oscillation, self-pumping, and thereby into *self-replenishing* stimulated optical-type emission at ELF frequencies.

5.6 The Fiber Fuse

See Figure 5-5. Although presently a one-shot destructive process, another multicollection phenomenon exhibiting a novel COP>1.0 process is the *fiber fuse* {298a-e}. This is a well-known but unusual effect in optical fibers and in fiber optic cables.

See Figure 5-5a. Once initiated by simply heating the cable (as with a butane cigarette lighter), the fiber fuse ignites and is self-sustaining. In those susceptible systems utilizing power on the order of one watt or so, the ignited fiber fuse propagates down the cable slowly, at about a meter per second nominally. It is evidenced by a bright white light propagating down the fiber, resembling the burning of a fuse for explosives — which led to the name "fiber fuse".

In fiber optic cables, it occurs only in those that contain germanium in their cores, and not in those containing just silicon in their cores. It moves down the fiber or cable at approximately one meter per second, and it is unlimited in the length of cable that it will continue along and march to the end. In the core, the marching fuse is actually "hopping", so to speak, and it melts a little "hole" about every centimeter or so, blowing out the material from the hole as it occurs. This "steadily and slowly marching" series of core melts results in the catastrophic destruction of the optical fiber core of the cable and thus destroys the functioning of the cable.



Figure 5-5 A. Fiber fuse destroys core of fiber optics cable of indefinite length, pitting core with holes.



Figure 5-5 B. Reversed second fiber fuse often *restores* pitted core in cable, filling holes back up.

Figure 5-5 The fiber fuse.

The mechanism has been theorized to be self-propelled and self-focusing. Other experiments have found evidence for thermal shock waves and chemical reactions.

But see Figure 5-5b. Astonishingly, after a — say — 1 kilometer fiber optics cable is destroyed by such a fiber fuse, it is often possible to "heal" the damage by reversing the direction of the normal laser light propagating down the cable, while re-initiating the fiber fuse from the other end by heating the cable on that end. In that case, sometimes the *reverse-ignited* fiber fuse will then march right back down the cable, precisely refilling those previously-melted little holes every centimeter or so, *restoring the functioning of the cable!* If ever a phenomenon cried out for further painstaking investigation to determine its actual mechanism, the fiber fuse is it.

Truncated coupled-wave theory applies to this phenomenon. A rigorous analysis by Russell {299} of power conservation in dielectric gratings has shown that truncated coupled-wave theories do not rigorously conserve power. Predictably such conclusions have been disputed {300a-300d}, however, and are adulterated by the same old use of Lorentz-surface integration of the Poynting vector around the grating and discarding of the nondiverged Heaviside energy flow component. Those disputing the results and claiming the impossibility of COP>1.0 systems continue to ignore the unaccounted Heaviside energy flow component accompanying every EM energy flow situation. In fact, they continue to unwittingly discard that component, and so have never performed *a fully* adequate analysis of any circuit or process. They also are unaware that all EM energy in 3-space comes directly from the active vacuum — specifically, it enters 3-space from the time domain and then returns to the time domain.

As long as the Lorentz surface integration scheme continues to be ubiquitously used without understanding what it does with respect to energy flow accounting, the dispute will not be dissolved. Presently both sides still use the Lorentz integration and discard the available Heaviside component. So they are really disputing whether the *Poynting diverged component* of the input energy can be equal to the energy dissipated. The answer to that is simply "No!"

Of course in a lab test the fiber fuse can be initiated with small Poynting energy input by precision point heating. In that case, the total energy required to melt the holes and move the material out of them, every centimeter or so down that (unlimited) length of cable, can be made as large as one reasonably wishes, simply by making the cable as long as one wishes. In short, COP»1.0. As can be seen, it can be experimentally proven that the input *Poynting* energy component can be far less than the total energy dissipated in damaging the cable. On the other hand, the energy dissipated in damaging the cable *is not* greater than the sum total of the usually calculated Poynting component together with the neglected extraordinarily large Heaviside nondiverged component. Conservation of energy is upheld, but only if the long-neglected Heaviside component is also accounted.

It stands to reason that the reverse fiber fuse can also be initiated by less input Poynting energy component that the total energy dissipated in restoring the cable. At that point, conventional theory has a problem. One can start with a good cable, put in a little EM energy twice — once to ignite the fiber fuse and once to ignite the reverse fiber fuse — and one winds up with a good fiber optics cable and having done lots more work inside the cable than the amount of energy one input by conventional considerations. We leave the solution to that problem as an exercise for the reader. Again, unless one includes the long-neglected Heaviside component, there is no way to make the energy flow balance, and one will have an experiment that seemingly contradicts the conservation of energy law. It doesn't, and that is the exercise the reader should understand.

So unless one uncovers and specifies the external source (Heaviside's energy flow component) of excess energy feeding the fiber fuse, it is a demonstrable experiment whose efficiency ξ seemingly winds up being ξ >1.0. It works every time and seemingly violates the conservation of energy law *as that law is conventionally and imprecisely stated for an equilibrium system only.* The COP>1.0 fiber fuse phenomenon does not violate overall conservation of energy because the system is not in equilibrium with the other two components of its supersystem. It only violates (permissibly!) the conservation of energy statement for a system in equilibrium. The "system" consisting of the fiber fuse and the cable is *not in equilibrium in its energy exchange with its active environment (with the other two components of the supersystem, consisting of the active vacuum energy exchange and the active local curvature of spacetime).* We point out, of course, that the Heaviside component is flowing in space outside the physical system, hence in the vacuum and therefore in the external environment.

Specifically, every dipole in the system is extracting and pouring out energy from the vacuum, and only the small Poynting diverged component of this available energy flow is ordinarily caught. The extreme nonlinearity (and some resonances!) of the particles in and exposed to the extraordinarily locally heated fiber fuse do sweep out a greater reaction cross section than do cold, static charges, in a fashion similar to the separate demonstration of such extended geometrical reaction cross section in the Bohren experiment {301}. *Hence the fiber fuse subsystem and the associated particles of melted matter from the holes do intercept, diverge, and collect some of the accompanying but usually nondiverged Heaviside component.*

See again paragraph 2.1.6 in Chapter 2. Iterative retroreflective systems — such as in intensely scattering nonlinear optical materials — are not necessarily limited to COP < 1.0. Such a system is not necessarily limited to only the energy input by the operator, and it is not limited to only the operator's input Poynting component. Instead, the system can receive an input of excess energy from (i) its active local vacuum, and/or (ii) the local curvatures of spacetime. Its efficiency ξ, however, is always $\xi < 1.0$, even when its COP is clearly greater than 1.0.

Since scientists disputing the energy aspects of the fiber fuse only have assumed an equilibrium system and have not considered the neglected Heaviside energy flow component, the present arguments against COP>1,0 performance of the fiber fuse are quite irrelevant.

We also point out that an optical phenomenon is involved, and that the core materials in the melt are optically active. Hence, appreciable iterative phase conjugate retroreflections occur in the fiber fuse itself and particularly in the melt materials (in the "inferno" of the "spot" itself). This asymmetrical self-regauging process gets more than one joule of work from one joule of original input Poynting energy, because of the iterative (and reciprocating) change of form of the energy. That operation produces iterative joules of work for each joule of original input energy, plus the unaccounted original input of the Heaviside component.

Again, there is no law of *conservation of work* in nature. The present conventional energy-work theorem erroneously considers only a "single interception and change of form" of the energy collected in the system, before loss of the energy from the system. Therefore, it only considers each joule of input energy performing one joule of work on the system to "excite" it to a higher potential energy state. It also considers that, once a joule of energy is then dissipated from the system as work in an internal load or process, it has departed the system forever and is not returned to do additional work by having its form changed yet again! In intensely retroreflective or intensely scattering systems, those conventional assumptions do not necessarily hold. For analysis of the fiber fuse phenomenon, the extended work-energy theorem must be utilized.

Finally, we point out the connection of this fiber fuse phenomenon to the similar "runaway" phenomena we have previously postulated as involved in producing the x-ray burster, gamma ray burster, etc. where iterative retroreflection and thus asymptotic rise in energy density is involved.

Another possibly related phenomenon is the unexpected explosion of porous silicon, as discovered at the Technical University of Munich {302}. The porous pellet involved in the unexpected experiment is covered with a layer of hydrogen atoms. In the presence of oxygen penetrating the oxygen barrier, an extraordinary and superfast chain reaction is initiated. The power of the explosion is some 10 times that of TNT. In the inferno portion of the fiber fuse, the "melt" as it puddles and then particulates, should be in the presence of oxygen and hydrogen from air in the cable. This dramatically differs from the explosive pellet, but may be sufficient to ignite at least in a local area rather than explode violently. If so, between the ablating particles of silicon there could exist iterative phase conjugation, thus producing an asymptotic rise in temperature and energy, perhaps sufficient to sustain the fuse. At least this possibility should be investigated.

5.7 Multiple Feedforward and Feedback Semiconductor Loops.

DeSantis *et al.* {303} showed that feedback systems with a multipower open loop chain can produce COP > 1.0 performance. In semiconductors, the present author hypothesizes that complex feedforward and feedback loops involving semiconductors can induce time reversal effects, hence some movements of current against the voltage. In short, there can arise a true negative resistance effect, as demonstrated in the Fogal transistor.

Indeed, a Westinghouse frequency converter using 64 transistor stages and similar sophisticated feedforward and feedback mechanisms was placed in the original Minuteman missile, then was later deliberately modified by Westinghouse engineers to prevent its demonstrated COP > 1.0 performance.[125] The specific germanium transistor used in the converter was also withdrawn from the market.[126] In those days, power meant weight and weight was at a premium in missile design. The power supply was very tightly designed, so that the weight could be minimized.

The converter had been deliberately designed to be 90% efficient, which was quite the state of the art. However, placed in the missile, the average converter would produce from 105% to 115% times as much output power as input power. (We are stating a COP > 1.0, *not* $\xi > 100\%$!) This was more output power than the tightly designed succeeding stages were designed to accept; consequently those overloaded follow-on circuits often burned out and deadlined their Minuteman missiles — something of great strategic concern at the time. The increased rate of Minuteman missiles out of action due to this problem placed great pressure on Westinghouse executives. In turn, they simply ordered the engineers to "fix it!"

Westinghouse simply "fixed the problem" very directly. The engineers reduced the output power of the converter by adding limiting diodes etc. Very quietly, Westinghouse then obtained several patents {304a-c} surrounding the technology, but no further mention of it appears in the literature. The Westinghouse work continued for at least a decade, judging by the spread of the patent dates.

---

[125] Our information came directly from private conversations of a close scientific colleague with the Westinghouse engineers who thoroughly tested the converter causing the Minuteman problems, and who then altered it to prevent the problems.

[126] Germanium has some unique properties, particularly with respect to transducing surface longitudinal waves to transverse waves and vice versa.

Such multi-loop, multi-feedback transistor circuits can apparently be developed to exhibit true negative 4-resistor effects. With specialized clamped positive feedback of the Bedini type, such open dissipative systems can then exhibit stable COP>1.0, since the energy is taken from the vacuum via the broken symmetry of dipoles, and then discharged asymmetrically in the loads so as not to destroy the source dipole negative 4-resistors. However, the reader should see Chapter 9 for special considerations and phenomenology.

5.8 Negative Resistors

We define a *true negative resistor* as a circuit component or system that receives energy from the environment and outputs useful energy, either in altered form or to power loads usefully. This contrasts sharply with a *differential negative resistor,* which exhibits negative resistance in one part of its regimen, but where all the excess energy to move the current against the voltage in that regime was previously drawn from the circuit itself and therefore was not freely received from the active external environment. Instead, the operator paid for it already. We are not interested in differential negative resistors, which are well known in the literature {305} and do not enable COP>1.0 system performance, so we will not discuss them further. Hereafter when we use the term "negative resistor", it is understood that we mean "true negative resistor" unless the term is otherwise qualified.

The true negative resistor is an open dissipative system *a priori,* and equilibrium thermodynamics therefore does not apply. Instead, the thermodynamics of open systems far from equilibrium applies. The negative resistor freely receives energy from outside the system (from the . environment), and "dissipates" it in interception and collection actions inside the system, to freely increase the available potential energy in the system.

In circuits, the main characteristic of a negative resistor is that the environment freely furnishes some excess energy to (i) power the load, and/or (ii) move the current back against the voltage, particularly when shunted across the back emf region of the source dipole. The *operator* does not have to furnish this excess energy dissipated to propel the current backwards or dissipated to power the load!

One must incorporate the entire supersystem into the analysis of a negative resistance element or system. Since the operator does not furnish the input energy dissipated by the negative resistor, then the active vacuum or curved local spacetime — or both — must furnish the input energy to it. One must consider local curvature of spacetime interactions with the negative resistance and the active vacuum interactions with it, as well as the interactions between active vacuum and local spacetime curvature. In other words, one must again include the active environment of the Maxwellian system that Lorenz/Lorentz symmetrical regauging arbitrarily discarded.

We specifically do not include the well known "differential" negative resistor, such as a tunnel diode, which in one regime moves current against the voltage, all the while drawing all its enabling energy to move current against the voltage from an overall previous energy input by the operator. Unless the input enabling negative resistance energy is freely received from the external environment, true negative resistance is not involved.

Several true negative resistors other than the point-contact transistor have been produced. We review a few of them in the following subparagraphs.

5.8.1 Kron's Negative Resistor

One of the greatest American electrical scientists was Gabriel Kron. Working for General Electric (GE), Kron built a true negative resistor in the 1930s, which could power itself and the network analyzer[127] at Stanford University, under a GE support contract with the U.S. Navy. Here **is** a direct quote from Kron {306} to show what we refer to:

> *"When only positive and negative real numbers exist, it is customary to replace a positive resistance by an inductance and a negative resistance by a capacitor (since none or only a few negative resistances exist on practical network analyzers.) "*

In that sentence we believe that Kron was forced by the censors to insert **the** words "none or" in the expression in parentheses. Particularly note the suggestion that in the imaginary realm it may not be the same as the accepted practice of using inductance as a positive resistor and capacitance **as** a negative resistor. Of course, the fourth Minkowski axis is - *ict,* and so this is very probably an oblique reference to the fact that energy can also "flow in" from the time domain. Kron was quite knowledgeable in general relativity as well as advanced electrodynamics, and he applied full general relativity to rotating EM machines etc. In another quote, Kron {307} also revealed that he had the negative resistor but was not allowed to use it to openly power the Network Analyzer. Quoting and reading through the "spin control":

---

[127] The network analyzer was a large analogue simulation capable of modeling sophisticated equations — such as Maxwell's equations, the Schrodinger equation. **etc.** — for use in designing, simulating, and analyzing naval communications systems or proposed systems. It was one of the most advanced simulations of its day. Kron was the chief engineer and scientist on the project, and one of the ablest electrical physicists the United States ever produced.

> *"Although negative resistances are available for use with a network analyzer, in practice it is more convenient to use a second type of circuit, in which the positive and negative resistances are replaced by inductors and capacitors and the dc currents and voltages are replaced by ac currents and voltages of fixed frequency. The use of the second type of interpretation is equivalent to multiplying the wave equation by* $i = \sqrt{-1}$*."*

After the word "although..." Kron includes the blunt statement that negative resistors were indeed available for use with the network analyzer. But if the "convenient" replacement of the positive and negative resistors by inductors and capacitors was made, then there was no COP>1.0 involved, and there was no true negative resistance involved. Kron is trying to clearly tell us that fact in the above quotation. He also strongly hints that energy from the time domain on the axis *ict* is involved, but that multiplication by $\sqrt{-1}$ discards this "energy from the time domain".

Kron's negative resistor secret has never been released by General Electric, Stanford University, or the U.S. Navy and it is not going to be released. It has never been deciphered outside those groups, with the possible exception of knowledge by Floyd Sweet of Kron's negative resistor construction. Sweet worked in General Electric but not on the Network Analyzer project. Kron, however, was Sweet's mentor and patron, and Sweet often spoke of Kron in glowing terms. In our opinion, Sweet's vacuum triode amplifier was a further development of Kron's early negative resistor, as Sweet understood it.

We further believe that Kron's "open path" is simply the other two components of the supersystem, being (i) local curved spacetime, and (ii) the active local vacuum. Obviously the *external environment* connects any two points in the physical circuit, in addition to the circuit's physical connection (the "closed path"). Between any two points at differing potentials in an electrical circuit, there exists a potential and a dipolarity. Therefore, there exists a broken symmetry because of the dipolarity. The potential difference of that dipolarity is also a curvature of spacetime; i.e., it is a "field" between the two points, and the field is identically a curvature of spacetime. Hence from any two such dipolar points in the circuit, there exists the giant negentropy flow of EM energy that we pointed out in 2000 {308}. This "open path" EM energy flow between any two unlike charges (any dipolarity) in the universe, not intercepted by the circuit and thus nondiverged, is discarded by Lorentz's integration of the energy flow vector around a closed surface enclosing any volume element of interest. It appears that Kron not only recognized (in different terms) what we are calling the "supersystem", but also recognized the equivalent of Heaviside's nondiverged EM energy flow component from any dipolarity — referring to that energy flow as the "open path" flow of energy. It is almost certain that he fully recognized what Lorentz symmetrical regauging did to the Maxwell-Heaviside equations. Thus it appears that Kron was the first scientist to discard Lorenz/Lorentz symmetrical regauging, producing his negative resistor by doing so.

We do not have firm knowledge, however, but only circumstantial evidence that Kron recognized the flow of EM energy from the time domain into 3-space, and vice versa, though he was certainly capable of seeing that. Nevertheless, this would also be included in his notion and discovery of the "open path", since it is included in every dipolarity, generating the scalar potential between the poles of the dipolarity. It may also have occurred to him from his excellent grasp of general relativity and spacetime curvature {309}.

Kron's concepts are certainly capable of being modeled and used to produce COP>1.0 EM circuits and systems, including his negative resistor. Kron did tremendous work in advancing EM networks and power systems. He left behind a great legacy of network and system analysis capable of dealing with the COP>1.0 electrical power system problem {310a-e}. Unfortunately, that legacy has been little used, if at all, in design of electrical power systems and power distribution networks today. To our knowledge, there are no electrical power systems deliberately using Kron's open path.[128]

5.8.2 Chung's Negative Resistor

A highly simplified diagrammatic illustration representing the Chung negative resistor is given in Figure 5-6. In a July 9, 1998 keynote address at the Fifth International Conference on Composites Engineering in Las

---

[128] A possible exception is provided by Barrett's extensions {286a, 286b} of Tesla's "potential shuttling" technique {124}, which can only be seen in higher group symmetry electrodynamics such as quaternions. However, as far as we know, Barrett has **not** applied energy shuttling techniques to electrical power systems.

Vegas, Dr. Deborah D. L. Chung,[129] professor of mechanical and aerospace engineering at State University of New York (SUNY) at Buffalo and Director of the Composite Materials Research Laboratory, reported that she had observed apparent negative resistance in interfaces between layers of carbon fibers in a composite material prepared under pressure.[130] The negative resistance was observed in a direction perpendicular to the fiber layers. By varying the pressure at which the composite material was prepared, Chung *et al.* were able to control whether the material would exhibit negative, minimal, or positive resistance. Apparent negative resistance was also observed in carbon fiber cement-matrix composites and in bare carbon fibers held together by pressure.



- Acts as a true negative resistor
- Dipolarity extracts energy from vacuum
- Does not use half the extracted energy to destroy dipolarity
- Open system far from equilibrum with active vacuum environment

Figure 5-6 Chung's negative resistor (diagrammatic).

A formal technical paper was later published by Wang and Chung {311}. A few years earlier a patent {312} had been issued to Chung and assigned to The Research Foundation of State University of New York, Albany, NY for a superconductive material using a laminate combination of carbon fibers and metal.[131] The patent mentioned mesoporous carbon filaments, strikingly similar to our previous discussion of the surprising explosion of porous silicon at the Technical University of Munich, as well as possibly a special kind of "porosity" consideration in the fiber fuse phenomenon (in the material of the fuse itself).

---

[129] Professor Chung holds the Niagara Mohawk Chair in Materials Research at SUNY and is internationally recognized for her work in smart materials and carbon composites. The reader may peruse a curriculum vitae, research work, and papers at http://www.mae.buffalo.edu/people/faculty'chung/researchl.doc.

[130] The preparation of "locked-in" stress in Chung's carbon fiber material is reminiscent of Moray's similar preparation of his amorphous semiconductors with locked-in stress also.

An initial offer on the State University of New York at Buffalo website to provide a technical package with respect to the negative resistor — for which a patent had been filed — to those submitting a nondisclosure agreement was abruptly withdrawn. The project may have been classified, or — far less likely — it may have been retained as deeply proprietary by the University. We suspect that both the technical package and the patent application have been classified by one or more U.S. government agencies.[132]

In our opinion, Chung's fruitful discovery deserves rigorous and continuing investigation, particularly in higher group symmetry electrodynamics and in terms of supersystem interactions to include Dirac sea hole current interactions. We also believe Chung may have been required by referees (or by declassifying authorities, if such were involved) to use the term "apparent" in the paper. The reported measurements in the technical paper do seem to unequivocally include true negative resistance with current running backwards against the voltage. It is not clear, however, whether this is Dirac hole current or electron current or a mix of both.

We also call attention to the fact that Dirac sea holes in the local vacuum — as will be discussed in Chapter 9 — will and do run backwards against the voltage. Further, such hole current can be transformed from negative energy to positive energy by the Bedini process shown in Chapter 9. The pressure used by Chung *et al.* in fabricating the material produces a stress potential in the material and thus decomposes into our reinterpreted Whittaker 1903 decomposition, preciously discussed. So giant negentropy is involved in the composite material, which implies that true negative resistance can be involved, at least in some operational regimes as pressure etc. are varied. Such results were found by Chung *et al.* and are reported in the paper.

---

[131] We stress that the issuance of this unclassified patent does not rule out a possible negative resistor (hence COP>1.0) patent that may have been classified. Some sensitive defense work in special materials is indeed performed at SUNY at Buffalo.

[132] At least the gist of the work is not lost, however, due to Naudin's duplication of the Chung effect and placing the results and building instructions on his website in France; see http://jnaudin.free.fr/cnr/.

Naudin reported independent success with a simpler variant of the Chung negative resistor {313}. This assures that at least the effect will not just be buried.

5.8.3 The Fogal Charge-Barrier Device

Figure 5-7 shows an illustration from one of William Fogal's patents {314} on a new kind of transistor (more accurately, a charge barrier device). Fogal's device incorporates a very special electrolytic capacitor[133], which introduces optical-type functions as well as the more familiar capacitor functions.



Fogal Semiconductor

- Blocks electron current flow $i = dq/dt$
    - As capacitor charges electrons in emitter junction attracted to plate
    - Charging plate produces high barrier
    - AC conduction electrons cannot penetrate barrier
    - AC displacement current $d\phi/dt$ and Poynting current $S = ExH$ are passed through the barrier
- AC into the barrier produces AC Lorentz symmetrical regauging, which produces AC stress waves, which are longitudinal EM waves a *priori*
- Semiconductor becomes "energy pipe"
- Massless displacement current is energy flow without losses
- Energy can be collected and separately discharged through load for free work
- Transmission mode Holding potential while changing displacement current produces enfolded longitudinal EM waves inside potential accompanied by time-polarized phase conjugate twins
- Reception mode Receiving longitudinal EM waves at barrier provides scalar interferometry, making transverse EM waves
- Fogal semiconductor can both receive and transmit via enfolded longitudinal EM waves, which are not limited to the speed of light in vacuum
- Semiconductor can also be used as a true negative resistor.

DIAGRAMMATIC
ONLY

Figure 5-7 Novel characteristics of the Fogal semiconductor.

Most semiconductor materials are optically active materials. Further, the individual electrons in a signal with a frequency well below light frequencies, are "jittering" with higher frequencies including the entire optical band. A "frequency" of a signal thus is imbedded in a jittering higher frequency complex set, and that set is quite able to interact in optical fashion *if the complex itself is used and controlled.* Fogal's process does appear to both use and control that jittery high frequency signal complex.

---

[133] The exact method of manufacturing this electrolytic capacitor, and its internal structuring, is proprietary to Fogal and a major capacitor manufacturer, who is under a nondisclosure agreement with Fogal.

Hence Fogal's process can "tunnel under" the normal *detected* force-field frequency responses of the individual electron,[134] and directly affect, change, and alter its higher-frequency environmental changes in the force-free field or field-free potential condition. In this way, Fogal has carried the electron (and hole) functions of a transistor to functions well beyond those in the present texts {315}. He may have also extended quantum mechanical tunneling effects to signals between widely separated regions of spacetime, since superluminal communication is possible with the Fogal semiconductor properly used. Longitudinal EM waves — which Fogal's semiconductor is able to utilize and control — can and do move at superluminal speeds {93a) because it uses the long-neglected "infolded" longitudinal electrodynamics revealed by Whittaker in 1903 and 1904. Further, superluminal solutions to Maxwell's equations do exist {93b}.

The charge barrier device is formed in a bipolar design that can be incorporated in Metal Oxide Semiconductor (MOS) designs as well as multiple gate devices. The device also produces a Hall effect EM field internal to the device. The Hall effect magnetic force will force electron flow and angular spin of the electrons in the same direction to the top of the conduction bands in the crystal lattice on semiconductor devices, unlike Silicon On Insulators (SOI) devices that force electron flow to the surface of the semiconductor lattice. This forcing function, together with the "extended tunneling" effects on the embedded EM environment of the electrons and holes, produces a unique effect. The device is able to stop and "pin" electrons while continuing to process the signal energy flow (the entire jitter signal complex) in which the electrons were coupled and moving. Thus the Fogal transistor is able to operate upon and with mass-free spacetime itself, and curvatures thereof. It is the first practical semiconductor capable of performing *engineering of the active vacuum.*

In the last few years we have stressed that EM waves in spacetime are longitudinal EM waves *a priori* — but they are accompanied by time-polarized waves (phase conjugates). Hence the two in combination become observable, as pointed out in quantum field theory by Mandl and Shaw {316}. *We detect effects a priori and not their causes.* We detect transverse *electron precession waves* in our detector circuits, and not the causal waves interacting with them to produce their precession. *The Fogal transistor is able to process the causal longitudinal EM waves directly, prior to their interaction with matter.* It in fact opens up an entirely new region of "detected physical reality" to our vision and detection, a region far more extensive than the development of infrared and ultraviolet sensors opened up to our sight.

---

[134] The electron itself is enveloped in the jittering of whatever background it is exposed to and interacts with. Hence a coupling interaction exists to arrange and **control** the jitter of the electron as well.

The pioneers of electromagnetics, who erroneously assumed a material ether and EM force fields in space, confused the transverse "material detected waves" (electron precession waves) in the detector with the "material undetected waves" they assumed to be incoming from space. Note that neither the electron nor the atom had been discovered when all these assumptions were used to determine how the EM wave in space was to be viewed and modeled. The transverse waves observed in the interacting/detecting of the Drude electron gas — i.e., the detected electron precession waves — were considered to be direct interceptions of the incoming causal waves from space. This already substituted the effect for the cause, as we have previously discussed.

Further, Faraday envisioned the "material field in space" as consisting of a series of "taut physical strings". A "perturbation" of this field in space was, in his view, simply the transverse wave plucking of those strings. Maxwell, who closely followed Faraday's experimental work and concepts, simply assumed the transverse "plucked string waves" advanced by Faraday. Therefore, the erroneous notion of the transverse EM wave in space arose and stayed firmly fixed in the theory.

One can check Whittaker's decomposition of the scalar potential into longitudinal EM wave pairs, then realize that the energetic vacuum is naught but a giant scalar potential — which can be decomposed by Whittaker's method. In short, as a scalar potential, space itself is a writhing mass of longitudinal EM waves and their highly nonlinear dynamics and interferences, or it can be modeled in that fashion. The energy continually enters 3-space from the time domain to the negative charge of every point in space considered as a point dipole, thence to the positive charge, thence back to the time domain. Notice the giant 4-space circulation involved. One also notes the polarization of the vacuum continually happening and arising spontaneously, as is well known in quantum mechanics. We also suspect that this or a similar mechanism is at the root of spontaneous broken symmetry in physics.

An interesting thing emerges from Whittaker's 1904 paper {317}, where he showed that all EM fields and waves can be decomposed into differential functions of two scalar potentials. Each of these two base scalar potentials can be decomposed by Whittaker's earlier 1903 paper {85} into a set of longitudinal EM waves. All EM fields, potentials, and waves are comprised of longitudinal EM waves and their internal dynamics, which also comprise waves of spacetime curvatures and their dynamics. Further, each longitudinal EM wave in 3-space is accompanied by its phase conjugate twin in the time-domain.

This far more primary "internal electrodynamics comprised of pure spacetime dynamics" — comprising and creating the recognized EM potentials, waves, and fields, their internal dynamic spacetime structuring and also the structuring of time — has not been developed and applied in physics theory. This internal or "infolded" electrodynamics is the primary "medium" in which the Fogal semiconductor appears to work and work upon. The Fogal semiconductor seems able to modulate and demodulate this internal structuring or parts of it, as has been demonstrated.

Imperfect longitudinal EM waves — called *undistorted progressive waves* - are already known to be able to travel at superluminal velocity, e.g., as shown by Rodrigues and Lu {318}. Indeed, Maxwell's equations have both subluminal and superluminal solutions, as shown by Rodrigues and Vaz {319}. Further, these waves can carry information. However, the *technology* of employing these waves has been lacking {320}. The use of scalar EM wave interferometry to produce normal EM fields and EM field energy at a distance has been shown by Evans *et al.* {321}.

As pointed out by Rodrigues and Lu {318}, perfect longitudinal EM waves travel at infinite velocity. This eliminates the difference between potential, field, and wave; a perfect longitudinal EM wave can also be taken as an instantaneous scalar potential with net force-free iterative regauging (varying at each point instantly and simultaneously). Both ways of looking at it produce the same end result: instantaneous remote energy change of spacetime energy density itself, in general relativity terms, or of the energy density of the vacuum, in particle physics terms.

Elsewhere, (e.g., Chapter 2), we also pointed out the "total photon **interaction"** mechanism that generates the flow of an entity through time. We also have advanced the concept of a "time-reversal zone" (TRZ) as a region where antiphoton interactions with charges predominate over photon interactions. We used these new concepts to propose exact nuclear **reactions** for the production of excess deuterium, tritium, and alpha particles in cold fusion experiments. In such an "excited state" TRZ region, the law of attraction and repulsion of charges is reversed. In the TRZ, like charges attract and unlike charges repel. Further, the gluon forces are reduced, so the quarks in the nucleons are much more lightly bound. In such TRZ zones, dense clustering of like charges occurs due to their mutual attraction.

A time-reversal zone is created in one part of the Fogal transistor, greatly assisting in the "electron pinning" action. That is, the usual strong mutual repulsion (the Coulomb barrier) of the electrons at the pinning site vanishes in the TRZ inside the Fogal semiconductor, and the resulting mutual attraction of the electrons greatly facilitates the pinning process far beyond what is usually obtained against "like charge" repulsion in a time-forward zone. Indeed, the TRZ in the Fogal semiconductor also materially enhances the electron pinning process beyond what can usually be obtained with cryogenics. At least some indication of trapping and perhaps pinning has been reported in amorphous semiconductors at room temperature {322a-b}.

The Fogal device is able to remove EM noise (electron noise) from existing EM signals, displays, etc. by 96% or more, by pinning the electrons and simultaneously time-reversing the spatial EM signal back to its original noise-free state prior to hosts of interaction electron collisions. This "noise removal" capability has been rigorously tested by independent parties, including at a leading university in the Netherlands,[135] and by several large electronics companies and several other universities. By pinning the electrons (and electron currents) while still processing and propagating the EM energy effects, the Fogal device can move noiseless EM energy without loss at room temperatures, at superluminal velocities, and reconnect the lossless propagated energy to electrons past the pinning region at a receiving region, releasing the electrons in the receiving region. The Fogal semiconductor therefore already accomplishes *room temperature superconductivity* as well as tunneling.

The Fogal device's basic mechanism (consisting of all the submechanisms) is to restore and move EM energy in force-free form, using direct regauging of the vacuum instantaneous scalar potential itself (or the vacuum potentials themselves). It operates directly upon the longitudinal EM waves comprising the vacuum potential. Hence it directly engineers the active vacuum and curved spacetime. I.e., it is the first *supersystem engineering* device of (hopefully) many more to come.

---

[135] The university researchers verified room temperature superconductivity being produced by the Fogal semiconductor in their independent verification measurements. They also measured that some 96% of the noise already present in a circuit was removed by Fogal's semiconductors in Fogal's circuits.

In the "jitter" environment of the space in which the individual electron is embedded, there exist many (and essentially all) field gauges, simultaneously. One of these, of course, is the Coulomb gauge where there exists an instantaneous scalar potential. Usually the instantaneous scalar potential is considered only a *near-field* effect, with no contribution at any significant distance. However, as Jackson points out {323}, transverse radiation fields are given by the vector potential alone. Also, in the Coulomb gauge the scalar potential "propagates" instantaneously everywhere in space {324}.

Along with other electrodynamicists, Jackson avoids the obvious superluminal communications implications of the instantaneous scalar potential by stating that *"..it is the fields, not the potentials, that concern us."* As he points out, a detailed *(though conventional)* discussion of causality is given by Brill and Goodman {325}. Again as pointed out by Jackson, in the Coulomb gauge the quantization of the photon involves only the vector potential. *The use of the scalar potential in the Coulomb gauge, together with deliberate engineering of the internal longitudinal Whittaker wave structure of that potential, directly allows distant engineering via multiply connected spacetime, even inside the nuclei of distant objects. This is in fact a unique and marvelous engineering application and extension of Bohm 's quantum potential concept.*

My "pinning" the electrons, apparently Fogal is able to essentially "hold" the vector potential and all the force fields while the instantaneous scalar potential *persists and now extends over all space, not just to the near field since all formerly moving field dynamics that would limit it have been frozen.* If this effect is substantiated, I have nominated it as the "Fogal effect". Further, this unrestricted instantaneous scalar potential now i lunges in field-free form (pure regauging form) over all space according to the signal energy being perpetuated and propagated[136] by the Fogal semiconductor independently of its pinned electrons. In this fashion, the Fogal semiconductor is indeed capable of "instantaneous" communication over essentially unlimited distances. At least one independent test has verified the Fogal instantaneous communication effect, but the test is still held proprietary by the testing agency.

---

[136] Here we again point out that the usual notion of a signal as energy propagating in 3-space is wrong. It propagates in 4-space, but not in 3-space. Also, what propagates is the spreading point-like polarization of the vacuum itself.

Since Fogal is able to alter and control the internal longitudinal EM wave Whittaker structuring of the scalar potential used in this Coulomb gauge manner, he is able to accomplish superluminal (and even instantaneous) communication, so long as a Fogal semiconductor is available in both the transmitter and the distant receiver. In the transmitter, the Fogal component is necessary to *infold* the information into the internal LW structure of the scalar potential to be used in the Coulomb gauge, thus transforming the input signal information into output longitudinal EM wave information directly in spacetime itself. The Fogal component in the receiver is necessary in order to detect, transduce, and *outfold* the infolded longitudinal EM wave information inside the instantaneous scalar potential. We have stressed that these internal longitudinal EM waves and their dynamics are spacetime curvatures and their dynamics. Hence their transmission and detection is a viable process for superluminal communication, including instantaneous communication.[137]

Further, once the electrons are pinned, all "signal fields in charged matter" (i.e., all EM force fields) are frozen and localized. This, we believe, involves a new physical effect introduced by Fogal that is analogous to the Aharonov-Bohm effect.[138] So I have called it the "Fogal effect". That is, the force-fields are frozen and localized by the pinning, but the field-free potentials then remain, including the instantaneous scalar potential ϕ and probably the curl-free magnetic vector potential A as well. The result is that the instantaneous scalar potential can be directly *regauged* everywhere at once by the changes of magnitude of the "frozen fields", rather as if they were "static voltage", possibly simultaneously regauging the field-free A-potential — all as part of a new kind of Lorentz symmetrical regauging. After all, a single Lorentz symmetrical regauging {326} changes both the potentials A and ϕ. Changes in symmetrical regauging produce stress waves, which are longitudinal EM waves. Continual changes of symmetrical regauging also continually changes both the potentials A and ϕ, *including over all space when operating in the Coulomb gauge.* This is one explanation of the beautiful effect that Fogal has discovered and is utilizing.

---

[137] We believe that physics books will have to be substantially rewritten, once the internal longitudinal structuring of the scalar potential (and of EM fields and waves) is employed directly in open technology. We further believe that the Fogal semiconductors are the first pre-developments in that coming vast new technology, at least in the open Western scientific world.

[138] There have long been, and still are, efforts to "fit" the Aharonov-Bohm effect into slightly modified classical electrodynamics after all. E.g., see C. J. Carpenter, "Electromagnetic energy changes due to charges moving through constant, or zero, magnetic field," *IEE Proc. A,* 138(1), Jan. 1991, p. 55-70; — "Electromagnetic energy and power in terms of charges and potentials instead of fields," *IEE Proc. A,* 136(3), 1989, p. 101-113; G. M. Graham and D. G. Lahoz, "Observation of static electromagnetic angular momentum in vacuo," *Nature,* Vol. 285, 1980, p. 154-155; T. H. Boyer, "Semiclassical explanation of the Matteucci-Pozzi and Aharonov-Bohm phase shifts," *Found. Phys.,* 32(1), Jan. 2002, p. 41-49; — "The Aharonov-Bohm effect as a classical electromagnetic-lag effect: An electrostatic analogue and possible experimental test," *Nuovo Cimento,* Vol. 100B, 1987, p. 685-701; — Classical electromagnetic deflections and lag effects associated with quantum interference pattern shifts: considerations related to the Aharonov-Bohm effect," *Phys. Rev. D,* Vol. 8, 1973, p. 1679-1693; — "Does the Aharonov-Bohm effect

We accent that, with pinned electrons frozen in place, the normal ϕ and A in matter (defined in terms of interaction with charge and the movement of charge) cannot occur. With time reversal zone utilized, electron pinning is greatly eased and the instantaneous scalar potential ϕ now assumes the primary active propagating role in surrounding space. Neither ϕ nor A is free to develop the normal $\partial\phi/\partial t$ and $\nabla\times A$ *spatially propagating dynamics of the force fields (effect fields) observed in matter.* In the Fogal process, the instantaneous scalar potential "signal" (the causal signal in 4-space) is generated in the transistor when it pins the electrons and freezes the force fields into "equal and opposite" form. Since no net force field can develop, the instantaneous scalar potential is a stress potential in spacetime itself and simply changes its magnitude instantly, at each and every point in space that it occupies, when the Fogal chip's input EM fields change in its signal input.

In the output, the net force fields remain zero and frozen, even though the individual force fields change constrained to "equal and opposite" manner. If one wishes, one may take this part of the Fogal output — the field free changes in the stress energy density of the vacuum — as one expression of *modululating the instantaneous scalar potential's energy density in perfect correspondence to the field changes in the normal EM input to the Fogal transistor.*

---

exist?". *Found. Phys.,* Vol. 30, 2000, p. 893-905; — "Classical electromagnetism and **the** Aharonov-Bohm phase shift," *ibid.,* p. 907-932.

The instantaneous Fogal changes in magnitude (e.g., instantaneously induced upon a distant collecting charge) are no longer limited to near field effects, or to the speed of light — and communication is not bound to the retarded wave. Now the induced changes of the instantaneous scalar potential exhibit far field effects and these changes — being naught but these special Lorentz condition magnitude regaugings — are instantaneous. This of course is a form of *action at a distance.* We stress that the best astronomical evidence also points to a startlingly superluminal speed of gravitation (curvature of spacetime, which after all is just a longitudinal EM wave or set of them) itself, as pointed out by Van Flandern.[139] If so, since any change of energy in spacetime is a curvature of spacetime, and one form of spacetime curvature can move at superluminal velocity, so can other forms of spacetime curvatures. In our favorite expression, *it only takes one white crow to prove that not all crows are black.*

As is well known, the de Broglie waves of matter always move faster than light, as do appropriate quantum tunneling processes. Further, the quantum potential used by Bohm in his beautiful hidden variable theory of quantum mechanics {347} also appears instantly throughout space, wherever it will be, and with the value it will have. The question of whether a quantum potential can be used to communicate has been posed but not definitively answered in the previous literature. We propose a resounding "Yes!" if one uses the internal structure of the quantum potential for one's communication, applying some component such as the Fogal semiconductor to do the infolding and outfolding.

We also propose that a process for forming and using an instantaneous scalar potential in the Coulomb gauge can be interpreted as the formation and use of a quantum potential or its direct equivalent. If that assumption is true, then the Fogal semiconductor seems to be the first component ever openly built and patented which produces and uses Bohm's quantum potential, *including* its infolded Whittaker structuring and dynamics. It also definitively answers in the affirmative the question of whether the quantum potential and the scalar potential in the Coulomb gauge can be used in superluminal communications.

---

[139] Tom Van Flandern, "The speed of gravity - What the experiments say," *Phys. Lett. A,* vol. 250, Dec. 21, 1998, p. 1-11. Van Flandern gives an extremely important, clear, and succinct summary showing that experiments refute the standard far field assumption of light speed in gravitational effects. Laboratory, solar system, and astrophysical experiments for the "speed of gravity" yield a lower limit of 2×10^{10}c.

Thus Fogal has apparently found a way to directly modulate intelligent change of magnitudes into and upon the internal longitudinal EM wave structure of the instantaneous scalar potential (and upon the quantum potential), as well as iterative "pure *net-field-free"* regauging of the instantaneous scalar potential {327}. It seems to have previously escaped notice that varying the Lorentz symmetrical regauging of a circuit or system easily produces pure longitudinal EM waves. This strongly implies that Fogal has surmounted and removed the barrier to practical superluminal communication and even further has reduced the barrier to practical instant communication.

Several tests — in one of which the present author participated — have indeed shown Fogal transmission of signals, including video signals, between two widely separated points with less delay than light-speed signals exhibit, and also with video bandwidth infolded inside a DC signal. In at least one series of tests in a large company's own laboratory and by its own engineers, communications from a ground-based Fogal chip transmitter apparatus occurred between the ground station, through the uplink into the satellite, back through the downlink to earth, into a ground-based transmission system with repeater stations, and into the receiving Fogal transistor unit in the lab. The transmissions occurred with *no discernible time delay,* something previously deemed impossible in all the textbooks. This was particularly significant since even the conventional time-delays in the repeater station amplifiers and the satellite receiver-transmitters were apparently eliminated. This further accents that the infolded "longitudinal EM waves superhighway" inside all EM fields, potentials, and waves — including inside matter such as the ocean and the earth itself— is a multiply connected space phenomenon. It is the most ideal communication medium, enabling deep space communication without delay, etc.

The implications for nondelayed future remote control of robot spacecraft and robots landing on the surface of planets and asteroids are obvious, as are the implications for direct exploration and measurement of conditions *inside the interiors* of the planets, the sun, the moon, and the earth via **internal** scalar interferometry. We accent that Fogal has done private experiments exploring this vast new physical reality revealed by the "internal longitudinal EM wave dynamics" and its interferometry, and it is mind-expanding (some would say *mind-boggling!).* It is also a great new step in physics and in our very notion of physical reality itself.

T**he** vacuum itself, being highly energetic, is indeed a scalar potential. **Further,** it has any and all gauges. Since potentials superpose, we postulate that Fogal's use of the instantaneous scalar potential is directly superposed on the corresponding instantaneous Coulomb gauge scalar potentials of the entire vacuum. His discovery of how to modulate the instantaneous ϕ magnitude without allowing modulated EM field propagation, constitutes a very special case of tunneling right through "space" itself, using one aspect or "component" of space.

In short, to be a little dramatic one might even apply the term *subspace communication* to this long distance tunneling effect. That interpretation would also seem consistent with the deterministic variation of the internal stress energy density structuring of the vacuum that is produced in the Fogal process.

From another viewpoint, Fogal has succeeded in not only finding the missing chaos of quantum mechanics, but in deterministically engineering and using it.

This is also consistent with Whittaker's decomposition of the scalar potential into bidirectional longitudinal EM waves {328} and his connection between time-polarized EM waves and longitudinally polarized EM waves as reinterpreted (12) to be consistent with quantum field theory {19}. We point out that a single point in time is simultaneously "connected" to every point in the universe. By using a transmission system that back-pedals from 3-space into the time domain, an instantaneous connection to any other spatial point in the universe is therefore available, if one's technology can take advantage of it. Fogal's technology does.

It is also consistent with quantum tunneling experiments that have demonstrated the transmission of intelligent signals (such as Mozart's 40th symphony) at superluminal speed between two points in a waveguide {329a-b}. Regardless of how one chooses to model intelligent superluminal communication, it has been experimentally demonstrated — multiple times and by multiple experimenters in multiple laboratories — that such can occur.

The difference in those superluminal experiments and the performance of the Fogal chip is that the chip uses iterative regauging of the magnitude of the instantaneous scalar potential, as well as deterministic alteration of the scalar potential's internal longitudinal EM wave substructuring, and probably also modulates the internal structuring of a quantum potential. The presently proposed quantum tunneling mechanisms apparently do not do this, at least as they are presently modeled. Further, the quantum tunneling mechanism is difficult to apply; the Fogal mechanism is fairly simple and straightforward to apply, given the Fogal semiconductor at both the transmitting and receiving ends of the communication system.

Pure longitudinal EM waves readily penetrate matter to great distances, since matter is mostly empty space between widely separated mass particles. On the microscopic scale, matter is comparable to something like the solar system, except that intense fields and potentials (bundles of longitudinal EM waves and their dynamics) occupy the space between the particles. All this vast empty space inside matter, being a potential and comprised of longitudinal EM waves, is a giant "superhighway" for the passage of longitudinal EM waves and their dynamics, as indeed is matter itself which is mostly such empty space. Further, even the masses themselves are such, since mass is simply highly compressed spatial energy density, and therefore is highly compressed longitudinal EM wave energy and dynamics. It is just a "denser" superhighway.

Hence a longitudinal EM wave system can readily be developed to "see through matter" using Fogal semiconductors in transmitter and receiver. Fogal in fact has made at least one proprietary prototype demonstration unit that demonstrates this startling capability. The vision is very clear, due to the remarkable absence of noise in the Fogal process. It is also shockingly unique, and it changes our very notion of physical reality. We are not at liberty to further discuss this new "sub-submicroscopic" reality revealed in such experiments. We simply interpret it as jumping the presently assumed restrictions of observation, and allowing the direct or correlated observation of the virtual state entities.

As alluded to, the previously modulated "Fogal type signals" emitted by all matter and other physical entities can also be displayed on a screen using the Fogal process, revealing a hitherto unsuspected physical reality and EM signals environment. In this prototype system, Fogal showed a remarkable and startling new extension of our very perception of physical reality itself. This is another reason why we expect that physics books will have to be rewritten, once the Fogal semiconductors are on the market and available in practical equipment. As every physicist knows, any dramatic increase in our ability to sense finer levels of physical reality inevitably leads to new and startling advances in physics itself and changes our very knowledge of the nature of physical reality.

The ability to bypass and "park" force fields by pinning their source electrons in a time-reversal zone, while continuing the flow of noise-free EM energy at will and at infinite velocity, obviously enables COP>1.0 systems. A pure longitudinal EM wave already has infinite energy, for such a wave appears across the entire universe simultaneously, instantly changing the stress energy density of the entire vacuum in which the longitudinal EM wave is present.[140] The back emf and back mmf fields in an EM system or electrical power system can be frozen and held from restoring the Lorentz condition in the circuit, using the Fogal semiconductor {330}. We presently have an agreement with Fogal for the licensed use of his semiconductors in all such energy unit applications.

A quantum potential is modeled in a multiply connected spacetime, so that a given joule of input energy to one multiply connected point simultaneously appears in every other multiply connected point.[141] Since the Fogal semiconductor apparently can operate in quantum potential or Coulomb gauge fashion, it can act as a *direct energy amplifier,* with respect to the lab observer in a singly connected space. In short, the Fogal process dramatically extends the concept of "conservation of energy" to include conservation in multiply connected space and therefore incorporates observed energy amplification in singly connected space. Again, a broken symmetry (in singly connected space) reveals a higher symmetry (in multiply connected space), and the hierarchy principle is alive and well. In short, with the Fogal semiconductor used in power systems, the law of conservation of energy must be extended to include energy symmetry in multiply connected space but asymmetry in singly connected space. Obviously, such functioning totally transcends the limitations of the present thermodynamics models.

We carefully point out that this is not "energy creation" but simply the energy following the known kind of statistics in physics that allows a thing to be in multiple different places simultaneously. What is actually "instantly transmitted" is the simultaneous regauging of the energy density of the vacuum. At any point in space, the vacuum has an energy density and thus is a scalar potential with a given magnitude. Changing the energy density is simply regauging, which is freely permitted under the gauge freedom axiom of quantum field theory. So instant amplification of energy" over a region of points is simply the instant regauging of the potential already present at each point in the region. It is *a permissible multiply connected space violation* of the present more limited "special case" energy conservation concept, which implicitly assumes a singly connected space. We have been working with Fogal for some time in this area, and we expect to rapidly develop and introduce commercial EM power systems based on the Fogal semiconductor's abilities in multiply connected space, as soon as it is in production and available. Until then, the details of our work in that area must remain highly proprietary.

---

[140] This should not be too surprising, since the bare charge and the bare mass of every electron each has infinite energy, as is well known in particle physics. For confirmation in very straightforward language, see Nobelist Steven Weinberg, *Dreams of a Final Theory,* Vintage Books, Random House, 1993, p. 109-110.

[141] If we wish, we can even take time itself as a special kind of quantum potential, since time also displays such a "multiplicity of connection" in 3-space. In one sense, time is the ultimate quantum potential, since a single point in time is "connected" to every single 3-space point in the universe, simultaneously.

5.8.4 Point-Contact Transistor.

Figure 5-8 diagrammatically shows a point-contact transistor with n-type base in a typical circuit for power gain. The point of the contact is under pressure on the material with which it is in contact.


Emitter contact
Collector contact
i
αi
n-type Ge base
re
rc
RL
Load
Reverse bias on collector
Forward bias on emitter
Current gain = α >1.0
re ≈ 25 ohms
rc ≈ 25,000 ohms
power gain ≈ α2 RL / re
Device can exhibit negative resistance

Figure 5-8 Point contact transistor with n-type base.

The point-contact transistor often behaved in true negative resistor fashion, outputting more energy than was input to it. Its production was always far **more** of an art than a science.

As can be seen from our quotation at the beginning of this chapter, the original point-contact transistor was never thoroughly understood technically.[142] Specifically, there does not appear to have ever been any deliberate attempt to capitalize on the ability of the transistor to become a true negative resistor under certain manufacturing techniques and under certain conditions.[143] Instead, the variations and difficulties in manufacture resulted in use of the point-contact transistor being essentially bypassed rather quickly, by advancing to other transistor types more easily manufactured and with less manufacturing variances. In reducing the manufacture of other types of transistors to a science rather than an art, the point-contact transistor and its further development and optimization into reliable true negative resistors were abandoned.

We present this transistor as a straightforward and relatively inexpensive area in which young researchers in COP>1.0 systems and phenomenology may wish to begin, assuming they have access to semiconductor facilities in a university or similar or are willing to work meticulously under a jeweler's loupe. A rich combination of effects in the transistor awaits optimization and control. We predict that we shall yet see, on the world market of the future, such point contact transistors reliably exhibiting negative resistance. It will be necessary, however, to also take into account the symmetrical self-regauging characteristics of the common closed-current-loop circuit. By adroit switching of a true negative resistor in and out of a closed-current-loop branch, or placing it in parallel with the back emf of that branch to reduce it, asymmetry can be introduced into the overall closed current loop circuit, defeating the Lorentz symmetrical regauging. Defeating the Lorentz condition is essential to COP>1.0, of course.

---

[142] E.g., different theories are given in: (a) W. Shockley, "Theories of high values of alpha for collector contacts on germanium," *Phys. Rev.,* Vol. 78, 1950, p. 294; (b) W. R. Sittner, "Current multiplication in the Type A transistor," *Proc. I.R.E.,* Vol. 40, Apr. 1952, p. 448-454. Also of interest is (c) W. van Roosbroeck, "Theory of the flow of electrons and holes in germanium and other semiconductors," *Bell System Tech. J.,* Vol. 29, Oct. 1950, p. 560-607. See also (d) J. Bardeen and W. H. Brattain, "The transistor, a semiconductor triode," *Phys. Rev.,* Vol. 74, 1948, p. 230. For a more modern re-examination, see Shuji Hasegawa *et at,* "Electronic transport at semiconductor surfaces — from point-contact transistor to multi-tip STM," *Oyo Buturi,* 70(10), 2001, p. 1165-1171 (in Japanese).

[143] E.g., the point contact is usually under pressure, and this pressure of course can be varied. The full phenomenology of points (which increase voltage) and pressure, complicated by surface effects as well, has not been worked out in physics. Note the similarity of the pressure in the point contact transistor to the pressure in the Chung negative resistor. Note the almost certain involvement of the "overpotential" of chemistry and electrode chemistry, as well as the "double surface" effect of the small gap between the point and the substrate on which it rests in contact. Part of the gap probably even involves the Casimir effect as well. Any electrical signal variation in that very complex point junction will vary the overpotential, the stress potential, the "point increase in voltage" effect, etc. As can be seen, the phenomenology of the point contact is remarkably complex and rich in several areas of physics and in a great variety of physics variables. Obviously, the reasonable control of all these highly nonlinear variables — and their mutual interactions — is a difficult matter. Hence the readiness with which point contact transistors were dropped with substantial sighs of relief.

We envision such a development as an ideal "negative resistance shunt" to add across the secondary of a transformer, and another possibly across its primary and across the external power supply as well, in producing more amenable and easily fabricated COP>1.0 electrical systems. We also point out that, once the back emf or back mmf forcing of equal power dissipation in the primary of a transformer or in the emf section of a circuit is dramatically reduced or eliminated, one does not require "large intensity" potentials and voltages to collect a great deal of power in the intercepting and receiving external circuit. Again, by simple W = Vq, as much energy W can be collected from any nonzero potential V as there are charges q to intercept.

We also envision such a true negative resistor being close-looped by the Bedini process, thus producing a small "self-powering" transistor, which in effect becomes a small self-powering "battery". This is absolutely a doable process, and it will be done once the Fogal semiconductor is in production.

Almost all semiconductor materials are also optically active materials, and a point discharge into such materials represents a very sharp regauging (higher voltage) discharge at a point or into a very small area, due to the increase in potential at the tip where it contacts the base material. The point junction is under pressure, so a stress potential exists there. In addition, the well-known "point" effect also increases the potential in the junction pointer itself, from its base to the point. The point contact phenomenology of different materials — one conductive and one semiconductive — is of much interest, and with novel phenomenology.

The fact that the point-contact transistor in its most usual formulation primarily uses holes more than electrons, is also of much interest in COP>1.0 situations. Holes in a circuit move against the voltage. The trick is to let the Dirac holes *before observation* move in an open path from the ground return line against the back emf to the potentialization line, and **transduce** the moving hole current (via the Bedini process) into electron current after the holes have already freely reached the vicinity of the high side of the circuit.

When Dirac sea holes (causal positrons before observation and thus prior to their alteration to lattice holes and parity reversal) and Dirac sea hole current are also involved with point-contact transistors, the resulting phenomenology has been but little investigated and none of it is in the present textbooks. However, from recent work with positron probes and positron microscopes to examine semiconductors and semiconductor materials, it is known that the holes (positrons) tend to be repelled from nuclei in the material into defects (voids) in it {331}. These effects have been investigated, for example by Triftshauser *et al.* {332}.

Both the mechanical stress potential (which is fundamentally electromagnetic) and the heightened junction potential decompose via our reinterpretation of Whittaker's 1903 decomposition of the scalar potential. This leads to optical-type pumping in both the time domain as well as the 3-space domain. Hence novel optical-type effects and time-reversal of material states can be involved, leading to a very complex set of phase conjugate phenomena, time-reversal phenomena, etc.

Certain Hall effects employed in conjunction with a point contact transistor could be a fruitful area of investigation. As an example, narrow Hall bars with junctions between current and voltage leads of various geometries could be investigated. Widening the junction from the normal square-cornered shape can sometimes produce a negative Hall resistance.

The junction of the point contact involves asymmetrical self-regauging, iterative time-reversal retroreflection, increased Poynting and Heaviside energy flow components, optical scattering processes inside the junction materials, etc. The transistor can indeed be manufactured so that these highly nonlinear effects sum to a negative-resistor-like movement of the output current against the voltage, although with so many other phenomena involved it will require some hard work and research in order to develop and stabilize it — and understand it.

5.8.5 Bedini's Negative Resistor Process in a **Battery** {333}.

5.8.5.1 Some Pertinent Lead-Acid Battery Processes

A lead-acid storage battery is a highly nonlinear device. The plates may be plante, pasted, or tubular etc. They are usually highly porous and have a thin oxide layer. They may have other coatings and the electrolyte solution may include additives to enhance operation. The plates consist of a mix of crystalline materials in most cases. The plate materials include acicular (needle-like) crystals, particularly the negative plate. The plates usually are porous, knit, and have gridded separators.

The chemistry of the battery electrolyte is complex and — even today — not all of it is well understood, particularly when mass transport is accounted. In our discussions, we will be including some of the previously neglected phenomena during mass transport (ion sluggishness in moving) that are responsible for some of that lack of understanding. In the battery chemistry, there are many double surfaces between the ions and also there is a variety of point voltages. There is a separate theory for double surfaces.

One of the most important phenomena is that the ion currents in the electrolyte are confined to the battery, and do not pass out into the external circuit. Much of the electron currents in the external circuit are blocked at the plates from moving within the electrolyte. Consequently, we will limit our discussion to two major currents of interest[144] in a battery-powered system, and these currents are effectively isolated from each other (at least to first order). Those currents are (i) the ion currents in the electrolyte, confined to between the plates and therefore internal to the battery electrolyte, and (ii) the electron currents between the outside of each plate through the inside of the plate and on out through the external circuit and **then** around to the inside and thence to the outside of the other plate. Chemical changes occur on the plates themselves as a result of these two currents.

It is usually assumed in power systems that these two currents are in phase or almost entirely so. That need not be true at all, and Bedini takes specific advantage of deliberately arranging these two currents to be antiphased part of the time. Part of the Bedini effect can be understood from this fact alone; the other part must consider one other most unusual electrical current that is encountered only in battery-powered systems or COP»1.0 systems.

So indeed there are *several* (many) currents in a lead acid battery [334], not just one, and we will consider three of them — the two previously mentioned, and an additional Dirac sea hole current in the local vacuum **itself.** The reader interested in greater technical depth should also turn to the literature of electrode chemistry and electrochemistry {335a-f}, which is quite complex.

---

[144] Of course, there are many other currents in a battery as well, but — although an oversimplification — these two major currents together with the Dirac sea hole current will suffice for our introductory modeling and explanation purposes.

5.8.5.2 Dirac Sea Hole Current

In a battery-powered COP»1.0 system (and in some COP>1.0 systems), there is a previously unrecognized significant flow of Dirac hole current in the local vacuum, running from the output section of the system to the system input section and thence through the conductors into the battery terminals and onto the battery plates, and on into the battery electrolyte chemistry. This hole current may be greater — *even far* greater — than the normal electron current running from input to output.

So in the battery-powered overunity system with positive feedback, not only does an electron current run from the battery through the connecting conductors to the input section of the system, but also a Dirac hole current pours back out of the system input section, and — if not intercepted and transduced — through the conductors and back into the battery. All the while, this Dirac hole current is "eating" electrons being furnished by the battery to the system. The net result is that the battery "sees" an extra load to be powered, in addition to the ordinary load presented to it by the normal system input section. It "sees" the situation as an "extra load" because it first has to furnish sufficient electron current to fill the hole current and "kill" it, before it can furnish the additional electrons to power the system in normal fashion.[145]

---

[145] An odd effect occurs in the battery, however, when the battery completely discharges in the normal sense. Actually, it is still fully charged with positive energy charge, but also has been simultaneously charged with negative energy charge. With the excess negative energy holes continuing to charge the battery with negative energy charge, the battery becomes increasingly *charged with net negative energy.* There is almost no limit to the negative energy charge the battery (i.e., the local Dirac vacuum portion of its supersystem) can take, except the eventual development of antigravity effects due to the inverse and increasing curvature of local spacetime in which the battery is embedded. After a battery has been used to power a COP»1.0 system for some time, one can take the battery off, place it on a normal battery charger, and it will then "eat" positive power for an extended period of time — e.g., a week or longer. During this period, one is steadily negating the inverse curvature of the local vacuum via the increased positive energy collecting in that spacetime. The battery again finally passes through zero voltage and net charge again, and suddenly starts charging up again in a "normal" sense with positive energy charge. This process actually increases the lifetime and function of a battery in a startling manner. Bedini has used batteries almost devoid of charge and energy in the normal sense, and powered systems very well with them, even for longer than a year continuously.

A COP»1.0 EM system is an excited system far from equilibrium in its exchange with its active environment. For all such excited systems, there exist significant decay mechanisms to bring the system back into equilibrium with its environment, since equilibrium yields the lowest energy state and maximum entropy. The Dirac sea hole current (negative energy current) is nature's unexpected natural decay mechanism to sharply decay a COP»1.0 system back to an overall COP<1.0 system when the external power supply is considered also.[146]

So when Dirac hole current back through the local vacuum and through the system is involved, the battery first has to furnish electron current to fill these holes at the rate they are appearing in the input section, thereby furnishing a primary "hole-filling" electron current component which "disappears" into the Dirac vacuum and is lost.[147] Only after the holes in the hole current are filled — and the hole current is being steadily nullified

---

[146] It decays the *true negative resistor* power system back into being only a *differential negative resistor section* of a slightly extended metasystem including the power system and its external power supply. This novel decay mechanism also prohibits close-looping the now differential negative resistance power system for self-powering, unless the hole current is first converted into electron current, as discussed in Chapter 9 and in paragraph 4.9.6 below.

[147] The filling of these Dirac sea holes is not pair annihilation in the usual sense, and no radiation is emitted. Instead, the energy of the radiation that would otherwise be emitted is added to the negative energy curving the spacetime. Hence the net curvature of spacetime relaxes because of superposition. In effect, the vacuum/spacetime itself reabsorbs the energy as relaxation spatial energy added to the curvature energy of the curved spacetime, reducing that curvature. Particularly see Mendel Sachs, *Quantum Mechanics from General Relativity: An Approximation for a Theory of Inertia,* Reidel (now Kluwer), 1986. A generalization of quantum mechanics is demonstrated in the context of general relativity, following from a generally covariant field theory of inertia. Nonrelativistically, the formalism corresponds with linear quantum mechanics. In the limit of special relativity, nonlinearity remains and several new features are derived: (i) Particle-antiparticle pairs do not annihilate; an exact bound state solution is derived corresponding with all experimental facts about annihilation/creation — which, in approximation, gives the blackbody radiation spectrum for a sea of such pairs, (ii) A result is proven, without approximation, that is physically equivalent to the Pauli exclusion principle- which in linear approximation gives the totally antisymmetrised main-body wave function and Fermi-Dirac statistics, (iii) The hydrogen spectrum is derived, including the Lamb shifts, in agreement with experiment; new results are found for high-energy electron-proton scattering, (iv) Finally, several applications to the elementary particle domain are demonstrated, in agreement with results from experimental high-energy physics.

— can the battery then send additional electrons which do not disappear and which are accepted in the system input section to power the system. We discuss this Dirac hole current in some detail in Chapter 9, including how to convert it into useful input electron current to the system, reducing the current load on the external generator and enabling self-powering. Bedini invented the method of transducing available negative energy hole current in the vacuum into electron positive energy flow to charge the battery and power the system, preventing decay of the COP»1.0 system back to COP<1.0.

We shall not discuss the complexity of the additional chemical reactions ongoing in the battery electrolyte and on the plates. The two main mass-containing currents and the negative energy Dirac hole current will suffice to explain the Bedini negative resistor formation and usage, at least to first order and sufficient to stabilize systems.

5.8.5.3 Changing Symmetrical to Asymmetrical Regauging

To first order, we reiterate that the electrons flow from one plate of the battery through the external circuit to the other plate, but the lead ions do not. There is thus a sharp "two separate currents" interface at the plates and thus a sharp separation between the electron current and the ion current. In short, there are actually two half-circuits in the battery-powered system if one chooses to use them semi-independently.

The current carriers in the two half-circuits are quite different. Therein lies the opportunity to separate and antiphase the two currents, using one to recharge the battery while the other is used to power the loads. It also allows a good opportunity to asymmetrically regauge both half circuits, greatly and freely increasing the Poynting energy component intercepted, collected, and used by each half-circuit's carriers. This is the basis for a profound "opening" of the system and influx of excess vacuum energy.

The two half circuits meeting at a common interface allow a stress potential upon that interface to *individually* use the two halves of what is normally Lorentz's symmetrical regauging. That usually *symmetrical* regauging (if the complete circuit were unitary) is now comprised of two separated *asymmetrical* regaugings, one for each of the two circuit halves, because the net stress potential (net Lorentz symmetrical regauging) — consisting of two opposing fields and forces — is split into two now-individually-separated and separately utilized force fields.

We accent this process by an analogy. Suppose we suddenly place a scalar potential ϕ upon a point in the middle of a transmission line. Immediately the potential ϕ races off (spreads) in both directions simultaneously, at nearly light speed. Further, in each direction there is a moving gradient of ϕ, hence an E-field by $\mathbf{E} = -\nabla\phi$. These E-fields or "emfs" are oriented in opposite directions, so there is a movement of charge from the middle of the line toward each of the ends. The same "dephasing" current effect can be applied to any conductive medium or to the interface between two conductive circuits.

In Bedini's negative resistor case, the placement of the potential ϕ — for its movement in both directions — is on the interface (the face of the lead plates) between the two half circuits and therefore between the two different current carrier types. An initial "Lenz's law" reacting with the suddenly placed E-field onto the plate surface, creates an E-field in opposition, forming a stress potential ϕ which is much higher than the normal potential of the battery (in a nominal case, 100 volts instead of the 12 volts of the battery).

Immediately this potential "takes off in both directions", with a powerful E-field and emf back into the outside circuit and its load, while a powerful E-field and emf also proceed into the battery electrolyte in the opposite direction. So the ions in the battery have a sudden, much higher energy interception and collection forced upon them, with the excess emf now being in *battery-charging mode.* The electrons in the outside circuit simultaneously have an excess emf and potentialization *in the load-powering mode.* Let us see how the two very different current carriers react to these "dual emfs" in the overall circuit.

5.8.5.4 Mass-to-Charge Ratios of the Two Current-Carrier Types

We stress the dramatic difference in the *mass-to-charge (m/q) ratio* of the two currents. The lead ions' m/q ratio is some few hundred thousand times the m/q ratio of electrons, as we recall. For our purposes, all we need to know is that the m/q ratio for the lead ions is *very much larger* than the m/q ratio for the electrons. For a given force, the ions in the internal half circuit in the electrolyte will therefore respond very much slower than will the electrons in the external circuit half.

5.8.5.5 Hysteresis Between the Responses of the Two Half-Circuits

Because of this great disparity in the m/q ratios of the two mass currents, there is obviously a relatively significant hysteresis (time delay) between the *response* of the more massive ion current and the *response* of the far **less** massive electron currents that interact at the plates to try to change the ion current and its momentum. This time-delay between ion response in the electrolyte (the effect) and electron pileup urging (the cause) can be adroitly manipulated. Specifically, it can be used to alter the local vacuum potential and cause it to add excess energy to the ions in charging mode **and** simultaneously to add excess EMF to the electrons in circuit-powering mode. In short, the response delay can be manupulated to "asymmetrically regauge" the mass currents in the system, freely changing their potential energy, and dramatically increasing how much potential energy is available for battery recharging and how much is available for powering the external circuit (loads and losses). Further, during the antiphase condition of the two current halves, the battery can be charged simultaneously while the external circuit half and load is being powered. Excess energy is fed into both actions by the *overpotential* (the stress potential) created at the surface of the plates.

5.8.5.6 Evoking the Initial Bedini Negative Resistor Effect

Figure 5-9 shows the first phase of Bedini's negative resistor process. Consider the battery in normal load-powering operation. From the external circuit, a very sharp leading edge rise of a pulse of electrons and potential is sent to the battery plates in "back-popping" or "battery charging" mode. The back-popping electrons drive in nearly instantly, piling up on the negative plate[148] and trying to force the heavy ions to start moving in the battery recharging direction. The pile-up that results in the stopped electrons on the battery plate surface represents an increase in local current density, hence an increased potential. This produces the 100 volts potential, during the time that the ions have not yet responded to any appreciable degree.

Due to much larger m/q ratio of the sluggish for a moment they lag due to their greater inertia, and this allows the much more agile electrons to "pile-up", producing a substantial overpotential as the local current density increases. The lagging ions are being steadily overpotentialized during this "lag time", up to about 100 volts in a normal 12-volt battery. At the same time, electrons are being forced back out of that higher 100-volt area and into the external circuit and its load, which had been at 12 volts. Recall now that these electrons can move longitudinally only at the drift velocity. Hence all electrons in the external circuit are now highly overpotentialized, and in *load-powering mode. The* overpotentialized electrons are thus producing excess power in the external circuit, much more than normal.

---

[148] We are not using conventional "positive current and positive plate" as the high side of the potential. We are using "electron current and the negative plate" as the driving potential plate.



1 Sharp leading edge voltage pulse produces intense electron clustering and large potential (negative resistor) *at* interface *Sluggish ions only beginning to move*

2 Bidirectional Poynting energy flow from potential overpotentializes both the electron cluster and the ions, which are only beginning to move in charge mode

4 Large back emf Into circuit returns overpotentialized electron current, powering circuit with excess energy pouring from negative resistor potential Continues dunng ion delay

5 Simultaneously overpotentialized ion current is overcharging battery

Figure 5-9 Phase I of the Bedim negative resistor process in a storage battery.

Then the overpotentialized ions very slowly (compared to the electrons!) slow, stop, and begin to move in the opposite direction. They reluctantly respond and move in *battery recharging mode.* During that ion-response lag time, and the slower initial portion of the response, the electrons in the pulse continue to furiously surge in and pile-up on the negative plate, overpotentializing both the ions and the external circuit's electrons, while also some of them are being impelled back out into the external circuit to power it with extra overpotentialized energy dissipation. The charge density at that plate sharply increases due to the pile-up where the charges are "squeezing" together (clustering). There is a much higher potential suddenly rising in the squeezed charge cluster, because of the increased charge density there. As we stated, this potential nominally may be about 100 volts during this initial phase.

We call attention to the simple equation W = VQ, where W is the potential energy added to charges Q exposed to voltage V.

Simplified, the excess energy W_{IONS} freely impressed upon the ions is

$$W_{IONS} = f(100 - 12)(Q_{IONS}) \qquad [4\text{-}3]$$

where Q is the total coulombs of charge of overpotentialized ions and f(100 -12) is the magnitude of the overpotentialization of the ions.

At the same time, an excess energy is impressed upon the electrons in the external circuit by the same potential extending along the conductors into the external circuit. Again, this excess energy WE is given by

$$W_E = f(100 - 12)(Q_E) \qquad [4\text{-}4]$$

where Q_E is the total coulombs of charge of the overpotentialized electrons and f(100 -12) is the magnitude of the overpotentialization of the electrons.

But the emf on the electrons from the pile-up is directed in load-powering direction, as can be seen. Consequently the ion current and the electron current have been deliberately dephased by 180°, and so the overpotential energy of the ions is delivered in battery-recharging mode, while the overpotential energy of the electrons is delivered in circuit load powering mode.

Recapitulating: Pulsed pile-up of excess electrons on the negative plate interface between the two currents, while the ions are beginning to respond or only sluggishly responding, produces a much higher potential (an *overpotential)* on the sluggish ions — nominally some 100 volts in a 12-volt battery. On the negative plate, momentarily there is now a much higher voltage (with respect to the positive plate) than normally exists in the 12-volt battery. This voltage *overpotentializes* both the reluctant charging ions in the battery solution between the plates, and the powering electrons back into the circuit in powering mode due to the reversal of the emf. Since there is, say, 100 volts across the battery momentarily, there is also 100 volts now across the external circuit momentarily. Accordingly, overpotential excess powering of the external circuit load is suddenly evoked, while at the same time overpotential recharging of the battery is also evoked.[149]

In short, the ion current in the battery and the electron current into the external circuit have been placed 180° out of phase, achieving one major requirement for a COP>1.0 electrical system: *violating the integrity of the closed current loop circuit.* The battery is recharging at the same time that the external circuit is being powered, *from the same free overpotential,* and both recharging and circuit powering are driven by increased emf.

---

[149] Another of Bedini's innovations is to shunt the excess voltage (say, above 14 volts) into an external capacitor on the circuit side. In that way with his overpotential he can be (i) overcharging the battery, (ii) powering the load, and (iii) storing excess energy in that capacitor, from the altered vacuum — all simultaneously.

We strongly accent that the overpotential at the plates represents a change in the local vacuum potential, and it *identically is* part of that now-altered local vacuum potential. The vacuum, since it contains enormous EM energy in virtual state, is a very powerful EM potential. Any EM potential in our circuits is automatically a change to the ambient vacuum potential, or a change to another potential that is such a change to the vacuum potential. In the most exact sense, this is a method of overpotentializing the plate interface with excess energy from the vacuum, and then letting that energy flow onto the ions to recharge the battery and onto the electrons in the external circuit to power it and its load.

The Bedini overpotential at the battery plates decomposes via Whittaker 1903 {85} as reinterpreted and previously explained, so that excess energy is entering 3-space there, *from the time domain.* Further, the piled-up electrons on the plates and the ions (as charges) in the solution receive such potential energy from the increased potential on them via the same decomposition process. So the creation of the Bedini overpotential on the battery plates, together with dephasing the two currents, is the creation of a true negative resistor at the plates, freely receiving energy from the external vacuum (from the time domain and virtual state) and transducing it into real potential energy and emf on the internal ions and on the external circuit electrons.

Hence Bedini has invented a process for creating a true negative resistor inside a storage battery, and for suddenly thrusting the system out of equilibrium with both the active local vacuum and the active local curvatures of spacetime. As such, the thermodynamics of open systems far from thermodynamic equilibrium applies, and that system is permitted to exhibit COP>1.0, while complying with energy conservation and the laws of physics and thermodynamics. With adroit use and collection of the excess energy, the externally collected energy can be used to close-loop the system and power all its functions. So the system is permitted to power itself and its loads, with all the energy being received from the vacuum via the broken symmetry created. Any overpotential is a dipolarity *a priori,* since any potential is. Hence creating an overpotential is precisely producing an extra broken symmetry of that dipolarity right there at the interface between the two half-circuits and the two dephased, localized currents.

During the "back-popping" pulse signals, one should not think of the energy pulses that Bedini inputs to the battery as the "powering" energy. Instead, one must think of each pulse as "triggering" and "timing" energy which initiates certain other key *negentropic* interactions to freely occur, once the electron pile-up occurs. The resulting negentropic interactions then add substantial additional energy (from the local active vacuum) to the ions in the ion current and to the electrons in the electron current. The freely added energy can be appreciably more than the switching or triggering energy that is dissipated as the "input by the operator".

In short, Bedini deliberately "switches"' and "triggers" certain kinds of vacuum exchange interactions, effectively creating a *true negative resistor* in the battery itself.[150] Due to the broken symmetry of the increased dipolarity *(overpotential)* that Bedini makes in "electron pile-ups" urging reluctant and delayed ion response, the vacuum furnishes extra virtual particle flux to this pile-up of electrons on the plate, which produces an enhanced Poynting energy flow that interacts with the ions in the battery electrolyte. Being charges, these ions thus transduce some of the excess absorbed virtual photon energy into real observable energy, thus increasing their potentialization and energy.

Bedini's method does the following: (i) It forms a true negative resistor in an unexpected way, upon the plates between a pile-up of electrons and the ions in solution in a common lead acid battery, (ii) it uses that negative resistor to extract excess energy from the vacuum and furnish it both to the ions forced into charging mode and simultaneously to the electrons in load powering mode, and (iii) it adds several other stimuli (such as Lenz law effects) which further amplify the negative resistor and enhance the effect, increasing the excess energy extracted from the vacuum and collected in the battery-charging process and also in the circuit-powering process simultaneously.

Specifically, the delay in ion response is adroitly allowed for and manipulated by Bedini to place the battery in ion current recharging mode while the signal pulse electrons between the plates and the external circuit are simultaneously placed in external circuit powering mode. By manipulating the hysteresis and adroitly timing the electron pulses and pulse widths, *Bedini breaks the usual forced Lorentz symmetry of the excitation discharge in a usually closed current loop containing both the*

---

[150] Again we stress that any dipolarity or potential is a negative resistor, producing giant negentropy {12}.

battery's source dipole and the external load. This is possible since his method deliberately opens the system so that vacuum energy enters freely, increasing the potentialization (energy collection) of the ions in the battery solution and upon the electrons between the plates and the external circuit as well.

We stress that Bedini has chosen to *avoid the* usual dissipation of half the energy collected in the external circuit to do nothing but kill the source dipolarity between the battery plates. He works on "that half of the circuit" that is usually just called the "back emf region" and ignored, and he separates and dephases that half of the circuit from the other half. By interrupting that normal "back emf battery-discharging section dynamics and converting it to "forward emf battery recharging section dynamics, while simultaneously powering the external load, Bedini temporarily produces and utilizes a negative resistor right there on the surface of the battery plates themselves.



1 Sharp trailing edge of voltage pulse produces intense Lenz law effect Sharply increases electron clustering and potential (negative resistor) at interface Sluggish ions delay speedup further increasing the Lenz law effect

2 Increased bidirectional Poyntjng energy flow from potential overpotentializes even further both the electron duster and the ions, which are only beginning to accelerate in charge mode

4 Large new increased back emf into circuit returns overpotentialized electron current powering circuit with new excess energy pouring from negative resistor potential Continues during ion delay

5 Simultaneously, re-overpotentialized ion current is overcharging battery even faster

Figure 5-10 Phase II of the Bedini negative resistor process in a storage battery

5.8.5.7 Further Increase of the Negative Resistor Effect by Lenz's Law

See Figure 5-10. To further increase the Phase I effect just before it would end, and requiring precise timing of his switching of the pulse leading edge and trailing edge, Bedini then invokes a second phase by carefully controlling the timing for the sharp *cutoff of* the "stimulus pulse" creating the negative resistor. This is usually invoked just as Phase I is preparing to end, but experimentation and adjustment for optimization to the individual circuit conditions may be required.

Invoking the Lenz law reaction by minimizing the stimulus pulse cutoff time, Bedini sharply increases the already-increased negative resistor overpotential by a Lenz's law induced voltage surge, and sharply raises it to as much as 400 volts nominally. The process also sustains the negative resistor overpotential for a longer period, while increasing it again during this second phase. Thus even more free energy from the altered local vacuum potential is delivered to the ions in charging mode inside the battery, while simultaneously even more energy is delivered to the external circuit electrons in powering mode. The overpotential period is also extended. In this second phase, the extra energy W_{IONS} added to the ions in recharging mode is given by

$$W_{IONS} = f(400 - 12)(Q_{IONS}) \qquad [4\text{-}5]$$

and the extra energy W_E added to the electrons in system powering mode is given by

$$W_E = f(400-12)(Q_E) \qquad [4\text{-}6]$$

The total energy added to the system in Phase I by the negative resistor is

$$W_T = W_{IONS} + W_E = f(100-12)(Q_E + Q_{IONS}) \qquad [4\text{-}7]$$

The total energy added to the system in Phase II by the negative resistor is

$$W_T = W_{IONS} + W_E = f(400-12)(Q_E + Q_{IONS}) \qquad [4\text{-}8]$$

And so the total energy added to the system by the Bedini process is just the summation of equations [4-7] and [4-8]. With adroit switching, Bedini need only "pay" a small fraction of that freely received excess energy, in his own operator's input pulse energy and switching costs.

So by invoking a novel negative resistance effect directly upon the driving plate of the battery, Bedini creates (in the first phase) and then further enhances (in the second phase) a "nearly free" overpotential and overpotential period inside the battery. This excess potential directly upon the electron-pileup plate acts in both directions — out into the electrolyte between the plates to overpotentialize the ions in charging mode, and back out into the external circuit in powering mode to overpotentialize the electrons now powering the load. During a fraction of the operating cycle, Bedini recharges the battery while powering the circuit simultaneously, and thus has invented a novel method for extracting energy from the vacuum and curved spacetime to enable a COP>1.0 power system.

This is just a description of one fundamental period where Bedini applies his negative resistance process.

Several other places in the operation of the circuit lend themselves to additional phases of negative resistor formation and usage, and Bedini does use them. We do not discuss them here, since our purpose is only to advance the *fundamental principle involved.*

5.8.6 Independent Replication of the Bedini Negative Resistor Effect

Independent replication of the Bedini effect was accomplished early on by Nelson and by Cole, and also by Watson. Nelson has chosen not to further publicize his own work for some years, perhaps due to his employment as a microwave switching engineer in a large (and conservative) aerospace company. Cole is deceased, and Watson abruptly withdrew —forcibly, in our opinion — from public research and all further contact with his close colleagues after successfully demonstrating (in 1984) an 8-kilowatt power system utilizing a modification of the Bedini process. We are almost certain that Watson received the "offer he could not refuse", and that Watson-type COP>1.0 power systems are in fact already powering exotic underground facilities that "officially do not exist" but which we are aware of. We briefly discuss Watson's 8 kW generator at the end of this Chapter.

For non-battery powered systems, as we explain in Chapter 9, any unitary COP»1.0 EM system may experience a Dirac sea hole current decay mechanism which will produce an effective extra "load" in the system's input section, including on out into the external power system. As a general rule (sometimes violated), we estimate that the effect begins to be of importance at COP > 10^3 or so. Certainly it is of great importance in the range of COP > 10^5. To operate stably at COP » 1.0, this decay mechanism must be dealt with and prevented. For close-looping into self-powering mode, this negative energy feedback must be converted to positive energy feedback, thus allowing self-powering mode where all the input energy is freely received from the vacuum.

For battery powered systems, the hole current and "extra load in the input section" becomes of significance near COP = 2.0 or even less, because of interaction with the complex battery chemistry and the tendency to charge **the** battery with negative energy as well. So battery powered systems present a special problem for close-looping to achieve sustained self-operation. Bedini has long solved and demonstrated solutions to that problem in a variety of successful experimental systems.



Figure 5-11 **Bedini motor** similar to the **type which ran continuously off a battery for three years, simultaneously recharging the battery.**

To utilize Bedini's battery-powered system at COP > 2.0, or to close-loop it for sustained operation, one must add another Bedini process that transforms negative energy current into positive energy current. That is Bedini's *transducing* negative resistor process {336}. We describe that process briefly in the next paragraph below.

Bedini has built many different motor-generator versions of systems self-powered by use of his negative resistor processes. Figure 5-11 shows a Bedini motor similar to one that once ran off a single battery for more than three years without stopping, using the forerunner of the Bedini back-popping process for creating a negative resistance in the battery. Bedini is still building and testing such power systems; one of his prototype motor-generators today, capable of operating and self-powering off a single battery, is shown in Figure 5-12.

5.8.7 Bedini's Transducing Negative Resistor.

Figure 5-13 gives a simplified block diagram of Bedini's transducing negative resistor process, which asymmetrically regauges negative EM energy into positive EM energy. With this process Bedini is able to intercept the Dirac sea hole current running from the output section of a COP>1.0 EM system to its input section, and divert the negative energy Dirac hole current to "reverse charge" a capacitor. The "reverse charge" consists of providing a hole current to the anti-negative plate of the



Figure 5-12 Modern Bedini motor prototype which operates off a single battery, powering the load and recharging the battery also.

capacitor, so that holes acting as positrons pile up in the local vacuum of **that** plate. This attracts the trapped electron charges in the dielectric, straining the dielectric in the direction of the hole collection. At the same time, the other plate draws electrons from the system that would otherwise be in currents that fight the back emf of the primary source dipole for the system. That reduces the back emf of the system during the charging of the capacitor; in effect, the back emf has participated in charging the capacitor with excess electrons on the negative plate.

Then Bedini reconnects the charged capacitor to the conductors leading to **the** power supply, discharging the capacitor by electrons furnished to the negative driving plate of the battery powering the system, and simultaneously to the input section of the system itself in normal powering mode. Note that the holes simultaneously discharge from the capacitor's anti-negative plate to the ground side of the battery, further charging the **battery** (the power source!) and the load as well.


A
START
SQUEEZE COMPONENTS
Switch in position #2 Ion current flowing, electron current flowing
INCREASED STRESS POTENTIAL 1
SHARP PULSE GENERATOR
Throw switch to position #1, fire sharp back pulse
ION CURRENT IN ELECTROLYTE
1
2
1
EDGE OF BATTERY PLATE
1
2
ELECTRON CURRENT IN EXTERNAL CIRCUIT
END
Battery Recharge
Throw sw to position #2 while ion current just reversed, potential high
2
INCREASED STRESS POTENTIAL (Lenz's Law)
2
Power to circuit
Short delay, Lenz law pulse ends
STOP MOTOR?
Y
N
A

Figure 5-13 Bedini transducing negative resistor process block diagram. Adjusting **timing of rear edge of pulse adds additional Lenz law** increase.

Though it does not appear in the conventional textbooks,[151] one can power a load directly by Dirac hole current, but one does so by using the hole current in exactly reverse fashion from how one would use electron current to power the load. Semiconductor components are also critical and usually should be avoided. In short, one simply reverses the terminal that is considered the "driving terminal", and feeds the hole current to that "anti-negative" terminal as now the temporary driving terminal.

The Bedini process thus allows the Dirac hole current (negative energy) produced by a COP>1.0 EM system to be fed back to the input section and transduced into positive energy input to power the system with electron current and also to recharge the battery with positive energy.

---

[151] Lattice hole currents of course do appear and are considered. However, even though the circuit designers consider a lattice hole as a positron, it is not such at all, because the m/q ratio of the ion with one + charge is quite different from the m/q ratio of a true positron. The Dirac hole in the vacuum is effectively the "4-positron" — still in negative energy Dirac 4-electron state — before its observation or interaction with mass. It is a true negative energy entity, and thus a negative mass entity. Prior to observation, it actually should be said to be a "negative energy x time" entity and a negative "masstime" entity. It is also a negative energy electron entity. This subtlety is essential if one wishes to produce successful antigravity experiments on the bench, as we point to in this book and as were exhibited by the Sweet vacuum triode amplifier at COP > $1.5x10^6$.

This converts what would otherwise be negative energy feedback to the input section of the system (and to the battery) to positive energy feedback **to** its input section and to the battery. Instead of seeing the negative energy current in the input as an additional "load" to be powered, the external power supply sees it as excess positive energy input by the environment to the system, reducing the "load" represented by the system. It thus reduces the power required by the system from the external power supply.

When the amount of "transduced" positive feedback electron current to the input section equals the "normal electron current draw" required by the system, the battery (or generator) can be disconnected and the unit will continue to operate in the self-powering mode, fed completely by the positive energy from the Bedini transduction process. The other *supersystem components* (comprising the external environment of the system) will continue to power the system and its loads and losses, with all the input energy to the system being taken from the combined active local vacuum and local curvature of spacetime.

5.8.8 Gray's "Splitting the Positive Pole" Engine.

One of the real pioneers in early application of causal positron energy was inventor Edwin V. Gray of Van Nuys California. In WW II Gray learned radar during his tour in the U.S. Navy, having previously attended advanced engineering school in the Army until discovered to be under age 15 and discharged. After the war, by 1958 he had learned to perform what he called "splitting the positive pole", using "cold electrical energy" (his name for negative EM energy) as well as the normal positive electrical energy. His first motor was operating by 1961. Preparing to put units into production, in 1974 the Los Angeles District Attorney confiscated all Gray's records and prototypes. To escape bogus charges, Gray later pleaded guilty to two minor infractions and was released. His prototypes were never returned. After several mishaps, moves, and more prototypes, Gray died in Nevada under mysterious circumstances in April 1989. We quote directly from Lindemann {341}:

> *"In the early 1980's, Gray offered the U.S. Government his technology to augment Reagan's SDI program. He actually wrote letters to every member of Congress, both Senators and Representatives, as well as the President, Vice-President, and every member of the Cabinet. Remarkably, ... Gray did not receive a single reply or even an acknowledgement!"*

In fact, during his early experiments, Gray discovered he could power light bulbs with cold energy, etc. Later he was to demonstrate this fact in a sensational manner: With a light bulb lit from his generator, he simply immersed the lamp — electrical leads and all — in water, where it remained lit. With his hands in the water, he would have been electrocuted or severely shocked if the electrical energy involved had *been positive* (diverging) energy. Instead, it was *negative* (converging) energy.[152] Another demonstration was to hit the coil of an electromagnet with some 3,000 volts, which hurled the electromagnetic into the air — but did not heat it. The electromagnet's coil would have been instantly melted if the energy had been positive, and the magnet would have been heated.

The reader should recall the timing of Dirac's theory of the electron {498a-b, 249}, which included the negative energy electron as early as 1930. Dirac also pointed out that we would observe this negative energy electron as a positive energy electron of opposite (positive) charge and positive mass, going in the opposite direction. The *observed* 3-positron and the *unobserved* negative energy 4-electron are quite different entities, producing quite different EM fields. The positron produces positive energy EM fields and positive gravity while the negative energy 4-electron produces negative energy EM fields and negative gravity.

In 1930, to his previous theory of the electron Dirac introduced the vacuum energy: the electron sea filled with electrons occupying negative energy states. The holes are treated as the positive electrons (as if observed). This vacuum energy medium is now referred to as the "Dirac Sea." First, Dirac attempted to identify these holes with protons, but that was falsified. Later the positron was experimentally discovered.

---

[152] By convention, "positive" energy has been associated with diverging EM energy, which is heating. Negative EM energy is associated with converging EM energy, which is cooling. In scalar interferometry {79}, one can control whether the distant EM field energy emerging in space in the distant interference zone shall be diverging (positive) EM field energy or converging (negative, cooling) EM field energy. This is determined simply by the biasing of the electrical grounds of the interferometer transmitters. The weather control referred to in 1997 by Secretary of Defense Cohen {89} is accomplished by using multiple scalar interferometers, some to gently heat the atmosphere in certain selected local areas (forming low pressure areas by expansion of the air) while cooling it in other selected local areas (forming high pressure areas by contraction of the air). By then moving these highs and lows around adroitly, one can capture and steer the giant jet streams, thereby steering the weather as one wishes, and directing significant weather changes into an area. By placing fairly sharp turns on the jet streams, one can induce great spin energy, thereby spawning tornadoes. Interestingly, by sharply pulsing the interferometer and controlling its electrical ground bias, distant cold explosions or hot explosions can be produced at will. Such weapons have been tested worldwide, and many test incidents are given in our older books F*er-de-Lance* and *Gravitobiology.* Information on such incidents is available on website http://www.cheniere.org .

One of the problems with present conventional application of Dirac's theory is that the positron is not used in its *unobservable causal negative energy 4-electron state* by modern theorists and experimentalists, but *after observation* where its direction has been reversed, its charge has been reversed, time has been stripped away, and the mass has become positive. So it is actually used as a positive energy entity having positive mass, and producing positive energy EM fields and positive gravity. This defeats the entire magic of the causal (unobserved) 4-positron as the electron carrier of negative mass and negative energy {*convergent* electromagnetic energy) in currents in the vacuum (spacetime) itself, rather than the electron carrier of positive mass and positive energy in ordinary 3-space. By replacing the unobserved (causal) vacuum 4-positron (negative energy electron) with the observed (effect) 3-positron with positive mass and positive energy, the entire vast area of negative energy EM fields — and thus direct antigravity via electromagnetic means — is discarded.[153] But the physicists avoided having to grapple with practical negative mass and practical negative energy (cool mass and cool energy). It also set back the pace of physics in discovering and engineering antigravity transportation for nearly three quarters of a century.

It appears that Gray's thinking about cold energy was more prosaic than the somewhat esoteric considerations of the Dirac Sea theory. Conventional electrical engineering circuit theory considers positive charges moving around a circuit (although some electronics technical circuits required thinking in terms of electron current). Hence the "high" side of the standard circuit was the positive polarity, or the positive pole of the terminals of a generator or battery. From this "positive pole", positive current was sent around the external circuit to the ground return line by the forward emf (forward voltage). However, forcibly returning to the positive pole from the ground return line (i.e., from the negative pole) were those same positive charges, being forced back up by the back emf and requiring expenditure of half the external circuit's collected Poynting energy.

---

[153] When the huge nondiverged Heaviside energy flow component is appreciably of "convergent" or of negative EM energy rather than positive EM energy, the antigravitational aspects are substantive and observable (and practical). The unaccounted Heaviside negative energy flow component is often a trillion or more times as great as the accounted Poynting negative energy flow component. Hence antigravity technology is possible and practical, as we present in a later chapter.

So to Gray, the positive pole had two currents, one useful and one usually detrimental. The positive pole had (i) outgoing positive emf current powering the external circuit's loads and losses, doing the beneficial work (dissipating energy) in the external circuit with its load, and (ii) incoming positive current being forced back up against the back emf, doing the harmful work against the back emf and using up half the energy previously collected out there in the external circuit. Gray was aware that the work against the back emf was equal to the work done by the forward emf. So he set out to split these two currents apart, and catch the incoming current against the back emf separately, then use that normally wasted or oppositional energy to further power loads and/or recharge the batteries powering the system. Something like this was the way he was thinking.

That is what Gray called "splitting the positive pole". He also reasoned (and found) that the "reverse current" must be cooling instead of heating, since it moves against the voltage and acts backwards from regular current dissipated in resistors, etc. This precisely matches the cold (negative) energy phenomena met in the Sweet vacuum triode amplifier and in the motionless electromagnetic generator, as well as other COP>1.0 electrical systems.

Gray's later demonstrations showed that he had recognized this process or something very similar to it, in his "splitting the positive pole".



5-14 b Cross section view

US Patent No 3,890,548
issued 17 June 1975

5-14 a The Gray engine

Figure 5-14 Gray's "splitting the positive" COP>1 0 engine.

To take advantage of his concept and principles, Gray developed a special engine shown in Figure 5-14. In 1975 Gray received a patent on this engine {337} along with his special means of battery powering and special switching circuits.

Gray's engine uses pulsed capacitive discharge to power a magnetic motor, with recharging of the powering capacitors taking place *between* successive discharge positions of rotor and stator. The motor runs by initiating repulsion rather than attraction, which — apparently without Gray recognizing it in such terms — invokes the notion of the "superpole" pioneered by Bedini. The superpole is an important concept in COP>1.0 research, though most researchers in the field have never heard of it. John Bedini conceived it several decades ago and demonstrated the surprising difference between a superpole and a common pole of double strength.

When two equal and like magnetic poles are facing each other in repulsion with a small gap between them, a net stress magnetic potential (pole) is formed in that gap which has an energy density some four times as strong as the normal field energy density in the field from one of the two opposing like poles. Hence the local energy density of the vacuum in the gap has been substantially increased above the energy density in the field region between a north and a south pole facing each other. Further, this energy density is in a "field-free" Lorentz-regauged form, i.e., a stress potential form. From that superpotential *outward,* there exists a normal magnetic field. But in it, there is no net magnetic field, but there is a "stress" field nonetheless.

Compared to an ordinary magnetic motor using attraction as well as some repulsion, the exclusive use by Gray of the Bedini "superpole" principle caused an extra *symmetrical* regauging[154] of the local vacuum energy input to the system (to the gap between the poles) as the magnetic superpole

---

[154] Every conventional electrodynamics text already assumes and uses the Lorenz-**Lorentz** symmetrical regauging as being absolutely free. Symmetrical regauging assumes that the energy of the system has been freely changed twice, but in such a way that the two free fields formed are equal and opposite, forming a stress potential. Gray found how to split apart and separately use these two "free-flowing exc**hanges** of energy between system and active vacuum" that comprise the overall stress potential of the system, and thereby violated the Lorenz-Lorentz symmetry condition, freeing the two equal and opposite EM fields and their free energy to be used individually and beneficially to (i) provide extra power to the load and (ii) recharge the powering batteries so they did not run down. Using a different method. **Bedini** has done likewise.

(stress magnetic scalar potential). However, this stress potential is comprised of bidirectional longitudinal wavepairs, as shown by Whittaker in 1903. This superpole or stress potential thus can and does "split" into two different fields in antiparallel directions from each other. Since the north pole is deemed "positive" in magnetics, then using the two anti-fields comprising the free positive superpole is indeed "splitting the positive pole". Gray coined a very apt phrase for what he was doing.

Each of those antiparallel fields also involves an associated and unaccounted phase conjugate field {338a-c}, hence it is a time-reversed field (after observation). So opposing time-polarized EM waves also accompany Whittaker's decomposition waves. In short, the scalar potential accomplishes *optical-type pumping* in the time domain, and can be used to demonstrate time-reversal (as in Becker's bone-healing method).

Before observation (interaction with charged mass) and while still in the causal state, *the EM field from the positive pole is actually an EM field from a negative energy 4-electron, and the field can be taken to be a negative energy field!* In our view, positive energy enters every point dipole in the polarized vacuum at the negative charge, thence to the positive charge, thence back to the time domain. From the positive charge, the positive energy is leaving 3-space back to the time domain. Hence positive EM energy diverges from the negative charge and converges on the positive charge, then "disappears", so to speak, back to the time domain from whence it came. The "disappearance" of positive (divergent) energy is the disappearance of heat energy; hence it is a cooling process rather than a heating process. Or said another way, *negative* EM energy enters 3-space at each point dipole, entering from the time domain to the positive charge. Thence it moves to the negative charge, and back to the time domain. We see or detect the positive energy flow in 3-space directly, while the negative energy flow in the Dirac vacuum is evidenced by the "backwards" interaction creating Newton's third law reaction force.

By splitting the positive superpole, one has effectively destroyed the Lorentz symmetry condition. Hence the excess energy in the superpole will be capable of performing real work in the system in two directions. One direction is from the system to the external environment so that it produces the dissipation of energy (therefore work) in the loads and losses. The other direction produces a "negative resistor" or negentropic action that adds that much excess usable energy to the system back into its input section. By adroitly intercepting and switching that energy into capacitors and/or batteries, Gray was able to charge capacitors, recharge batteries, and even power loads with cool energy (as demonstrated later by immersing a lighted electrical line and a lit light bulb in water).

A positive-energy resistor becomes a negative resistor when fed with negative energy. Then it converges positive EM energy from the external environment and outputs it into the circuit in which the resistor is connected. Note that this is the same statement as the resistor receiving (extracting) negative energy from the circuit and emitting it back to the time-domain. *That's like extracting back emf from the circuit and tossing it off to the time domain.* A conductor to positive energy flow is an insulator or dielectric to negative energy flow. Hence the normally "conductive" water was a neat insulator for Gray's "dunking" demonstration of negative power, as were his own normally conductive hand and body. To negative energy, a coil seems to produce capacitance rather than inductance, while a capacitor seems to produce inductance rather than capacitance.

Thus when the "positive pole is **split"** in the system, the system has broken **its** Lorentz regauging and is an open system in disequilibrium with the external vacuum environment, freely receiving excess energy from it.[155] With adroit switching and energy capture, such a system is permitted to exhibit COP>1.0 because it has violated the free Lorentz regauging once the excess energy in the superpole region is discharged and used.

---

[155] When one analyzes the supersystem of any Lorentz-regauged EM system, one realizes that the extra stress potential energy — entering the system and "locked up" as a stress potential due to the Lorentz condition — is actually a special relativistic **rotation** of the frame of the power unit away from the laboratory frame. That is, the system when rotated away from the lab frame, takes on free symmetrical regauging energy in that rotated frame as an excess stress potential. Gray's "splitting the positive" process simply separated the two appositive fields comprising the stress potential, then produced excess free energy from that *broken* free regauging Lorentz condition. Literally Gray splits Lorentz's stress potential into halves, the halves being its two opposing EM fields and their energy. This is equivalent to the system being rotated back into the lab frame, releasing its excess energy it possessed in the rotated frame back into the lab frame. Richard "Scott" McKie has also filed a patent on an invention deliberately rotating a capacitor's frame and fully charging it — while it is in its rotated frame. The rotated capacitor can be charged with less energy furnished from the lab frame, than is obtained back out of the capacitor in the lab frame when the charged capacitor is suddenly rotated back and discharged. At least in **theory,** McKie's overunity process should be workable if the switching costs are negligible. Our contribution to McKie was to advance the theoretical mechanism for **the** experimental mechanism he had discovered and was using.



From US Patent No **4** 661747
issued 28 April 1987

Also in U S Patent No 4595,975
issued June 17,1986

Figure 5-1S Gray's conversion tube used with power systems,

Gray also utilized a special conversion discharge tube, shown in Figure 5-15. This tube uses the fact that a very sharp pulsed discharge in it results in a temporary COP»1.0 condition. This COP»1.0 condition instantly involves causal Dirac sea 4-positrons, moving as negative mass current and negative energy current in the local vacuum, which sweep back from the output side of the discharge to the input side.

We also point out the severe overpotential that must accompany any such violent pulse discharge process. The overpotential is a departure from equilibrium conditions, and is the difference between the actual potential and the equilibrium potential. The overpotential is well known and utilized extensively in electrochemistry {339a-c}, but is little used in conventional circuit theory. Nonetheless, it is involved in cold fusion processes due to the double layer phenomena {340a-b}, and it is involved in all electrode discharges (as from a cathode to an anode). It is also involved widely in electrochemistry and ion processes in solution.

Figure 5-16 shows Gray's circuit containing his conversion tube. Figure 5-17 shows Bedini's successful replication of the Gray conversion tube. Figures 5-18, 5-19, 5-20, and 5-21 show four pertinent pages from Bedini's laboratory notebook on his replication of the Gray conversion tube and the Gray motor system.



From U S Patent No 4 661 747
issued 28 April 1987

Also in US Patent No 4 595 975
issued June 17, 1986

Figure 5-16 Gray's circuit containing his conversion tube.



Figure 5-17 Bedini's successful replication of theGray conversion tube.


GRAY MOTOR
TUBE IS SIMPLE
IN HOW IT WORKS
12VDC
LOW VOLTAGE
LOW VOLTAGE 12V
DIODE 5KVA
ON SHAFT
ROTOR
COPPER ROD
TEFLON CYLINDER
CARBON
SILVER TIP
GRIDS
GRID
GRID
ELECTRON FLOW
COPPER ROD
CARBON TUBE
GRIDS
SILVER TIPS
TO COIL ON MOTOR
5KVA 12UF
GRIDS
COPPER ROD
90°
ELECTRONS FLOW TO GRIDS
5KVA 12UF
GRIDS MADE FROM COPPER MESH
HIGH VOLTAGE 5KVA
OVER LOAD GAP
CURRENT TO COIL
CURRENT CHARGE
FIELD IN ELECTRONS
SPARK
1979

Figure 5-18 Page 1 from Bellini's lab notebook on the Gray conversion tube.


ED GRAY SYSTEM 1984
ON ROTOR
12V RECOVERY
5KVA 12UF
5KVA 12UF
5KVA 12UF
S3
MOTOR COILS 250
- 12V + STORAGE BATT PRI
MOTOR ON
INVERTER ON
12V DC
RESISTOR
SILVER
RESISTOR
ROTOR SHAFT
RESISTOR
SILVER
GRIDS
5KVA SWITCHING SUPPLY
5KVA
5KVA 12UF
5KVA 12UF
FLASH OVER
GND
ED GRAY MOTOR
LAB MOTOR 1984

Figure 5-19 Page 2 from Bedlnl's lab notebook on the Gray conversion tube.



-
+
12 VOLT
LOW VOLTAGE
MOTOR ON
0°
ONE WAY
240°
120°
5KVA 12UF
5KVA 12UF
5K 12
COPPER ROD
GAP ADJUST
ON ROTOR
COIL 1
COIL 2
CO 3
ROTOR MAG
N
N S
TEFLON
MOTOR COIL
CARBON
SILVER TIP
COPPER MESH GRIDS
0°
S1
INVERSION
TEFLON
TEFLON
ED GRAY TUBE
One Tube Shown
COPPER ROD TO GRIDS
TEFLON
GAP ADJUST
EV GRAY TUBE
SAFETY GAP
0°
-
+
DC INVERTER 5KVA
TUBE 1
TUBE 2
TUBE 3
5KVA 12UF
5KVA 12UF
5KVA 12UF
5KVA
5KVA
5KVA
5KVA
Notes
John Bedini
1982

Figure 5-20 Page 3 from Bedini's lab notebook on the Gray conversion tube.

In science, when a novel experiment is replicated independently, that experiment then is established as a scientific fact. It then becomes the task of the theorists to either change the theory to accommodate the experimental results, or come up with a new theory to explain them. With Bedini's successful replication of Gray's work and extension of it, that work has now been scientifically established. With his "splitting the positive pole", Gray was referring to an actual, useful mechanism he evoked and used in the processes ongoing in his motor, in his conversion tube, and in his power system.


1982
LAB Notes
on Ed Gray
LOW VOLTAGE IN
+
ONE WAY
VALVE FROM INC. (ROTOR)
HOLD DOWN
HOLD DOWN
GRID'S
COPPER MESH
CARBON
RESISTOR
TO FIT
ELECTRODE
TEFLON CASE
TEFLON CASE
HOLES DRILLED
IN COPPER TUBE
WORK'S BEST
OUTPUT TO
COIL
CARBON
RES
COPPER
ROD
PRESS
FIT
COPPER
SILVER
TIP
SILVER
TIP
COPPER
ROD
ELECTRON FLOW
90°
FLOW
OUTWARD
90°
ELECTRON
FLOW
MAKE FOR ADJUSTMENT
OF SPARK GAP
5KVA DC

Figure 5-21 Page 4 from Bedini's lab notebook on the Gray conversion tube.

For further discussions about the Gray motor, conversion tube, and the history of it all, one is referred to the book by Lindemann {341}.

5.8.9 Watson's Self-Powering Generator

See Figure 5-22. In 1984, Jim Watson demonstrated a self-powering 8-kilowatt generator at the International Tesla Conference in Colorado Springs. This generator was a modified extension of smaller motors and generators built by Bedini over a period of years. At the conference, engineers from the audience were invited to the platform to perform their own independent measurements of the unit, while it was running and powering its load. The engineers directly confirmed that the system was delivering power to the load (as could be seen visually also), and that it was recharging its batteries as well.



Figure 5-22 Watson's self-powered 8 kW generator demonstrated in 1984.

Interestingly, one of Watson's batteries was stolen that night. The reason was obvious. First, at the conference there was present one of the major persons charged with suppression of COP>1.0 electrical power systems world wide, along with several of his henchmen. Since they have been involved in suppressing many dozens of similar COP>1.0 systems, they are thoroughly familiar with both the theory of COP>1.0 electrical power systems and the various types of devices and mechanisms that have been invented in that area over the past century.

One feature of Watson's unit was that it charged the batteries with negative energy (i.e., with Dirac sea hole current, or "cold energy" as sometimes referred to), and could use negative energy for powering the unit. Hence, his batteries became charged with negative energy as the machine ran and powered its loads. After much demonstration and running, such a negatively charged battery has its local curved vacuum charged with an appreciable number of unfilled Dirac holes. Such a negatively charged "battery supersystem" will then absorb positive energy charging (electron current charging) for a protracted period before it will start to change its voltage and accept the positive charge. Instead, during that protracted initial period the battery will just "eat electron currents and positive energy" from the battery charger, with no apparent effect and no change in Its discharged state or its voltage.

A very simple way to absolutely ascertain whether or not a unit such as Watson's (without a Bedini negative energy converter) is genuine, is to simply take one of his batteries from a unit that has been running quite a bit, and recharge it on a conventional battery charger. If it exhibits that two-phased recharge phenomenon, it proves that the unit is real and is indeed a true COP>1.0 device, or certainly has the potential to be one. Coupled with the demonstration and independent measurements, this removed all doubts about the validity of Watson's COP>1.0 system.

So it appears that certain parties who were concerned about that system decided to do the "simple test" to see if Watson's device was real. It was real, and so they discovered. At that point, the High Cabal — Winston Churchill's term — recognized they had another successful unit and inventor to suppress.

Bedini and I were in close contact with Watson over a period of years, as often as three or more times a week. Later, some time after that conference, abruptly Jim ceased all communication with his former close colleagues. For two days a rather crazy recording **was** on his phone, stating the Watsons had moved. Then that disappeared. Watson never again contacted either Bedini or me, or his own financial backer (the late R. J. Reynolds III). Even Reynolds could not find Watson's whereabouts at that time.

We are quite certain that Watson received the "offer he could not refuse". Simply put, this is the old Mafia trick of visiting the target, offering him a deal, and he has no choice but to accept or die. When this is used to suppress COP>1.0 systems, and some medical systems, the offer is usually: *"Accept the money and you and your family will live very comfortably, but you will never openly work on this again or communicate it. You either accept our generous offer, or you and your family will be dead when we leave here."* Assuming that happened Watson had no choice but to accept the several million dollars offered him.

He is still alive, because Jeane Manning physically ran into him at a conference — and recognized him and spoke to him — whereupon he withdrew abruptly and left the conference very hastily.

5.9 Suppression of Free Energy Systems Has Been Common

This is only one of many cases we know of where such suppression of overunity systems and inventors has been accomplished. Others are not so benign. Marinov was killed with a longitudinal EM wave shooter in Europe, and his body was thrown off a building to make it appear a suicide. The police allowed the body to lie on the pavement for a protracted time (it was emitting longitudinal EM waves from the time-charging action of the strike). When finally moved, the pavement glowed in that area that had been underneath the body. Only one weapon on earth will kill a person in that manner, and that is a longitudinal EM wave "shooter".

Another prominent researcher was killed with a Venus technique (look it up, it's a distortion of the wave front) modified beam that plunges the heart into violent fibrillations. He rushed from a restaurant exclaiming, "They're killing me!" and died of a resulting heart attack. The present author was hit with just such a weapon in a restaurant here in Huntsville. A friend and I actually saw the weapon and the person wielding it. Knowing what it was and recognizing the symptoms, my seated companion and I were able to bolt out of the nearby back door during that minute or so we could still physically function. I personally saw the device and the person doing the beaming, and I have a witness to the event.

The partner of a colleague in Australia was killed on an upper floor by such a shooter from the street below, right through the walls. The assassin was observed, and was seen putting the bazooka-sized shooter back in his car, then speeding away. There are many other true incidents we could also relate, including a person killed by an ice-dart dipped in curare (a very professional hit method, used by some of the sinister arms of various intelligence systems). So there is more than just scientific work involved in pursuing COP>1.0 EM power systems. There can also be a direct threat to one's life, essentially at any time.

Almost any serious overunity researcher, who succeeds, will have had confrontations with assassination attempts, suppression attempts, threats, deliberate legal entanglements, etc. The present author is no exception. It is sad that one of the prerequisites for serious scientific work in this area is o**ften** a legal gun permit (for both the inventor and his wife) and either legally carrying a hidden weapon or never being very far from a weapon when working at home. As an old soldier, of course, one just shrugs and accepts it, and gets on with the job to the best of one's ability, albeit remaining very watchful and always on guard.

5.10 In Conclusion

In this chapter we have introduced many of the approaches to COP>1.0 EM systems or processes, or the possibility for such in some novel mechanisms known in science. Recalling our previously presented solution to the source charge problem, we emphasize to the reader that all assumed 3 - space EM processes are actually 4-space processes prior to observation, continually observed in iteratively frozen 3-snapshots by iteratively invoking the *d/dt* operator that produces observation. Hence from the source charge (and source dipole) solution we realize that all EM energy in 3-space comes from the time-domain and returns to the time domain. It iteratively appears along the "line of propagation" in 3-space at each successive position, but does not continuously propagate in 3-space. It does continuously propagate in 4-space. Since all the EM energy in any EM circuit comes from the time domain via the broken symmetry of the source charges and source dipoles, then we need to apply this greater vision to the COP>1.0 mechanisms and approaches so that we see the 4-space to 3-space to 4-space interplays.

The notion of the negative resistor is particularly significant and direct in that respect, and we have presented several versions of true negative resistors. For those wishing to experiment, we would suggest the easiest thing to start with is the point contact transistor. Or, simply go to Naudin's website {313} and download his instructions for making a Chung-type negative resistor, build it, and do experiments with it by varying the pressure on the fibers etc.

Again, we have not presented "parts kits" with instructions, but we have presented things that have worked or can reasonably be expected to work with some effort. We have also discussed the principles involved, to the best of our ability. In a few cases, we have directed the reader to information on websites where building instructions for selected negative resistors and other devices are posted.

As in any other scientific endeavor, we also urge the interested reader to read the literature and check the references cited, or as many as possible. Increasing one's understanding of the area is necessary to increase one's probability of success in the area.

We also wish the reader good results and success in his or her research and experimenting. The energy crisis is not going to go away, and the demand for oil will double in the lifetime of many of our middle-aged or younger readers. The cheap oil peaks shortly and declines in availability forever thereafter {342}; this alone will drive up the price of oil and seriously impact the economies of the nations of the world. To keep from destroying the world economy and the biosphere, it is absolutely essential that COP>1.0 electrical power systems — including self-powering systems taking their input energy from the seething local vacuum — be developed to produce the necessary electrical energy needs of the world, cheaply, cleanly, and easily.

If one or more of the readers should succeed in developing and producing such systems, then the entire purpose of this book will have been fulfilled.

Chapter 6

Additional Approaches to Overunity Power Systems

> *"Can the quantum potential carry a signal? If it can, we will be led to a violation of the principles of Einstein's theory of relativity, because the instantaneous interaction implied by the quantum potential will lead to the possibility of a signal that is faster than light... a signal has in general to be a complex structure, consisting of many events that are ordered in definite ways. In terms of our language, each signal is a supersystem of events, while each event is in turn a system of subevents.... At present, the answer is, of course, not known. "* [Bohm and Hiley] {343}. A comment:[156]

---

[156] We comment that the "event" involves observation: i.e.. it is conceived as an *observed* event. In that exact sense, no signal in space carries "events" because there is no interaction with mass and no *d/dt* operation induced on entities (curvatures) of spacetime. The effect (observed) 3-space field cannot propagate faster than light, because it cannot even propagate in the first place! The totality of light's EM interactions with matter is what makes the observed field or observed signal to appear to be propagated at light speed. It is not actually "propagating", but being iteratively recreated from point to point in space *if observed at every point.* Signal in spacetime is causal and hence nonobservable; the interaction of causal signal with charged mass is observable and makes an "event". When we clearly differentiate the nonobserved (causal) 4-field or dynamic from the iteratively observed 3-field or dynamic, then the *nonobserved 4-field* or dynamic is not limited to light speed. Propagation along the time axis, e.g., can be at "infinite velocity" because a single point in time is connected to every point in the universe simultaneously. Since all EM energy in space comes from the time domain locally at each point dipole in 3 - space and returns to the time domain from that same point dipole, it is the notion of "propagation continuously through 3-space" at *any* velocity that is a non sequitur. Absolutely nothing propagates through 3-space! If general relativity is re-interpreted **to account** the difference between observed and unobserved (effect and cause), then the unobserved cause can propagate superluminally without violation of the "observed event (effect) propagation at light speed" of general relativity. It is the notion that anything propagates in 3-space that is the non sequitur, and it should be removed from special and general relativity as well as electrodynamics.

> *"...contrary to the conclusions of classical mechanics, there exist effects of potentials on charged particles, even in the region where all the fields (and therefore the forces on the particles) vanish."* [Aharonov and Bohm] {344}.

> *"...for any force varying as the inverse square of the distance, the potential of such force satisfies both Laplace's equation and also the wave equation, and can be analyzed into simple plane waves propagating with constant velocity. The sum of the waves, however, does not vary with time, i.e., they are standing waves. Therefore the force potential can be defined in terms of both standing waves, i.e., by a global, or non-local solution, and by propagating waves, i.e., by a local solution changing in time... Thus, Whittaker's mathematical statement related the inverse square law of force to the force potential defined in terms of both standing wave (i.e., global) and propagating wave (i.e., local) solutions. The analysis also showed that the electromagnetic force fields could be defined in terms of the derivatives of two scalar potentials."* [Barrett] {345}.

> *"What might appear to be empty space is, therefore,* ***a*** *seething ferment of virtual particles. A vacuum is not inert and featureless, but alive with throbbing energy and vitality. A 'real' particle such as an electron must always be viewed against this background of frenetic activity. When an electron moves through space, it it actually swimming in a sea of ghost particles of all varieties — virtual leptons, quarks, and messengers, entangled in a complex melee. The presence of the electron will distort this irreducible vacuum activity, and the distortion in turn reacts back on the electron. Even at rest, an electron is not at rest: it is being continually assaulted by all manner of other particles from the vacuum."* [Davies] {346}.

6.1 Introduction

In this chapter, we continue to present a selection of potential overunity systems, inventions, approaches, and selected mechanisms. We also make the reader aware **that quantum** mechanics, an entire branch of physics, requires nonlocality and "instant propagation" in space. We utilize the quantum potential from Bohm's hidden variable theory of quantum mechanics {347} to impress the nonlocality. Further, the staid old scalar potential — which we meet as voltage in a circuit — also exhibits nonlocality and instant propagation in the Coulomb gauge {348}. Our purpose is to show that electrodynamics is not limited to the cut-and-dried subject as usually taught to electrical engineers and applied by them, but also covers a wide range of phenomenology that electrical engineers usually do not consider or account.

6.2 Energy Conversion and Energy Amplification

6.2.1 The Mead-Nachamkin Zero Point Energy Converter

It is well known that the vacuum interacts with electrical charges and dipoles, and also with the electrons in an atom. For example, Lamb received the 1955 Nobel Prize in physics jointly with Polykarp Kush for experiments measuring the small displacement later called the "Lamb shift" of 0+ne of the energy levels in atomic hydrogen {349}.

Casimir {350a} proved that closely separated conducting plates also alter the energy density of the vacuum, thereby becoming an "energy extracting" method, although the energy is miniscule. It is quite real, however, as shown in meticulous experimental work by Lamoreaux {351}. The principle that vacuum energy interacts with matter, plates, and electrical double layers and circuits is well proven experimentally.

In 1996 Mead and Nachamkin were granted a patent on an overunity EM power system process for extracting zero-point energy of the vacuum {352}. If one closely examines the patent wording, the device is properly patented as an energy converter and does not overtly state that it is a COP>1.0 system. It is a COP>1.0 system, however, since the input energy is freely received from the vacuum and not input by the operator himself. One embodiment of the invention inserts a tiny coil between the plates to extract the energy. See Figure 6-1. The energy is based on the Casimir effect {26}, which was accurately measured in 1997 by Lamoreaux {27} and since then by others.[157] Further investigation of the force's behavior with the shape of the conducting plates has been performed by Chen *et*

---

[157] See also U. Mohideen and A. Roy, "Precision measurement of the Casimir force from 0.1 to 0.9 microns," *Phys. Rev. Lett.*, Vol. 81, January 1998, p. 4549.

al.[158] Numerous other papers of interest on the Casimir effect have also been published {353a-d}.

Because energy cannot be created or destroyed, any COP>1.0 system is an *energy converter,* a priori. It must receive the excess energy from the environment (in this case, from the curvature of spacetime and from the local active vacuum) and convert that energy to a form usable to power or assist in powering the system loads and losses.


TYPICAL
MEAD-NACHAMKIN
EMBODIMENT
ZPE radiation encompassing extraordinary frequency band is continuously absorbed by conductor
Tuned "cavity" between conducting surfaces selects frequencies which can be coherently received and processed. This is "trapped Casimir power" extracted from the seething vacuum by the Casimir effect..
Receiving antenna
Transformer transfers the received energy
Rectifier
LC receiver oscillator tuned to cavity frequency
Voltage developed
Power to loads

Figure 6-1 Mead-Nachamkin conducting surfaces, antenna, and receiver for extracting EM energy from the vacuum,

The Mead-Nachamkin patent is interesting because the physics of the device is proven and accepted. Getting sufficient power output to be useful for electrical power purposes, however, remains to be demonstrated, since the Casimir effect is very tiny.

6.2.2 The Quantum Potential As an Energy Amplifier

In Bohm's hidden variable theory of quantum mechanics {354}, an extra potential is added to the Schrodinger equation, and is known as a *quantum potential.* Figure 6-2 lists the novel characteristics of this potential, and

---

[158] F. Chen, U. Mohideen, (G. L. Klimchitskaya, and V. M. Mostepanenko, "Demonstration of the Lateral Casimir h'orce," *Phys. Rev. Lett,* (in press as of the time of this writing).

Quantum Potential Characteristics

- No point source; not radiated
- Just appears instantly
- Quantum potential between two particles
  - Interaction does not vanish as spatial separation becomes very large
  - **Instantaneous connection**
- Depends on quantum state of system as a whole
- System parts can be greatly separated



Figure 6-2 Quantum potential characteristics (table).

Figure 6-3 lists technical features of Bohm's hidden variable theory from whence the quantum potential is taken {355}. It can "move instantaneously", at "infinite velocity", which means it just suddenly appears everywhere it will be, and does not "propagate at a finite speed" through singly connected space at all {356}.

$$V_{quantum} = \frac{h}{2m} \frac{\nabla^2 \sqrt{\rho}}{\sqrt{\rho}}$$

A quantum particle moves as if it were subject, in addition to its external potentials, to a potential which is a function of its own probability distribution.

Bohm's hidden variable theory assumes:

- **Particle and wave function real and separate**
- **Wave function obeys Shrodinger's equation**
- **Particle obeys classical mechanics**
- **Particle couples to wave function through a quantum potential**

Figure 6-3 Technical features of Bonn's hidden variable theory.

The potential is after all *potential energy.* With the quantum potential (QP), a joule of energy placed upon one collector, where that collector is connected via a QP with one or more distant collectors, will also result in a joule of energy (or some fraction thereof) instantly emerging upon and in each of those distant participating (QP-connected) stations simultaneously. It appears that, if only a fractional participation — say, 0.50 — exists with one or more of the distant stations, each of those stations will experience the appearance of that fraction (in this case, 0.5 joule) of the energy input to the initiating station. Any station can input energy, and it will appropriately appear at every other participating station, regardless of where these stations are located in ordinary 3-space as seen by the external observer.

One way of expressing this "instantaneous QP connection" between separated objects is to model the different objects (or stations) as linked together in a multiply connected space, with a certain QP connection or collection fraction. Presence of energy at one station in the multiply connected group, results in the simultaneous appearance of the energy — or an appropriate fraction of it — at every other station in the group.

To understand multiply connected space, consider a single point on a plane. Now consider 999 more points superposed on/in that same point. But suppose that those thousand points are really located at different locations in 3-space, though superposed in this "crazy space" containing a plane where all of them are superposed at one point.

As the ordinary external observer, suppose you input a joule of energy into one of these — to you — separated points, which happens to be the original point and is located in your laboratory. Supposed the fractional connection is 1.0 (the connection is perfect in multiply connected space). Voila! Instantaneously one joule of energy appears at each and every one of those (to you) widely separated points. If you vary your input energy (e.g., as in communication), it varies precisely the same in each of those distant QP-connected points.

Those who continue to advocate that superluminal communication of information is impossible are ignoring present experimental proof that it does occur. As a single example (there are others), it has been shown by Enders and Nimtz {357} that Mozart's 40th symphony can be transmitted as frequency modulated microwaves through a barrier wave guide between two points in a waveguide, via quantum tunneling, at 4.7 times the speed of light c. We point out that this is achieved using *transverse* EM waves.

If *longitudinal* EM waves are used together with longitudinal modulation (which engineers might think of as a sort of "pulse compression" technique), the only limitation to the speed of communication is given by the impurity of the longitudinal EM wave one is able to make. The Fogal semiconductor, e.g., can be used to transduce ordinary transverse EM wave signals into longitudinal EM wave modulations inside a scalar potential. Hence that scalar potential can move in the Coulomb gauge at infinite velocity. It requires another Fogal semiconductor circuit on the receiving end to receive and transduce the longitudinal EM waves and their longitudinal modulations back into transverse EM waves for processing and amplification by normal means. This capability of the Fogal semiconductor circuits has been demonstrated through satellite uplinks and downlinks coupled with long transmission line links, with essentially no delay from transmission to reception. One may think of the Fogal superluminal process as *tunneling through subspace.*

The best way to vary the energy is apparently by use of a variable stress potential (which translates to a longitudinal variation or modulation). In short, one must modulate the "internal energy" of the vacuum, so to speak, and not the "external energy". A reasonable discussion of internal energy versus external energy is given by Chen {358}. If one longitudinally modulates the internal energy of the vacuum potential — which, being a scalar potential, decomposes by the Whittaker decomposition {359} — then superluminal communication is not only possible but also practical. We expect Fogal to eventually place just such a system on the market, shortly after his semiconductors get into precision production.

One possible method of producing modulated internal stress potentials is by use of a Davis noninductive resistor {360}. Another is by use of a biwound coil with two windings, so that the two currents through two equal "superposed" coils are equal and opposite. We point out that, while there has been published much stuff and nonsense about such biwound coils, the truth is quite mundane. Simply examine the Lorentz symmetrical regauging applied to the Maxwell-Heaviside equations. It is the deliberate production of two equal and opposite force fields, which is in fact the creation of a stress potential and extra stress energy. By varying the magnitude of the Lorentz forces comprising the stress potential, the stress potential is varied in amplitude. Hence the concomitant longitudinal EM waves are varied in amplitude. A biwound coil is a variable Lorentz-regauging coil, *a priori.*

By oscillating the magnitude of any Lorentz regauging (which in the simplest case is simultaneously changing both opposing fields equally and oppositely), one can make longitudinal EM waves. By appropriately modulating both Lorentz regauging components, one can make longitudinal EM modulations upon those concomitant longitudinal EM wave carriers.

So with some careful tuning and adjustment, and a little nonlinear material in the core,[159] one should be able to have the superposed appositive magnetic fields lock together *(modulate,* rather than linearly *add)* and produce a magnetostatic scalar potential stress signal in and from a nonlinear core material. We caution, however, that the biological effects of the radiation of such stress potentials internal to spacetime have not been investigated. The experimenter is cautioned that he experiments at his own risk, and he is cautioned to experiment only at low power levels until the phenomenology in a particular case is understood.

---

[159] The opposing waves must modulate (multiply), not mix (add), and modulation is a nonlinear process. Linear mixing of opposite waves or fields will not cause the

If we compare the stress potential oscillation (wave) to a sound wave, the similarities suggest that the stress potential oscillation can be treated as a longitudinal EM wave, if the two superposed opposing EM waves "lock together". Simple addition is insufficient; modulation is necessary. Hence the nonlinearity of the conductors and core material is of significance.

For instantaneously propagating potentials and pure longitudinal EM waves, any conceived difference between the two becomes somewhat academic. The characteristic of interest is the instant appearance of the input energy at multiple points via a multiply connected space.

To the ordinary observer, use of a quantum potential and multiply connected space measurably yields a fantastic *energy amplifier.* One furnishes one joule, and gets out — say — 1,000 joules in those distant locations altogether. As shown in Figure 6-4, the QP system is a communication system of enormous implications, particularly as humans travel into space across the solar system and even beyond. Unfortunately, by using appreciable power in the initiating station, the QP system also leads to weapon systems of incredible destructive capabilities. Some five nations {361} now possess such quantum potential weapons, which are the dominant weapons on Earth. We do not further discuss the quantum potential weapons aspects in this book.

Back to our little energy exercise, inputting one joule and getting out some 1,000 joules. Suppose these 1,000 participating points are not distant at all, but are gathered closely together into a local material but still QP-connected with a connection fraction of 1.0. Now we input a joule of energy to that device, and it develops and outputs one kilojoule. It is hypothesized that this becomes the ultimate negative resistor. It will also exhibit separated Dirac hole current phenomena as the COP increases and, if sufficient COP is developed, it will exhibit antigravity effects such as

---

fields to "lock together" into a common stress potential. Nonlinear mixing (modulation) will. Hence the nonlinear core is required for conversion of appositive fields to stress potentials and **Lorentz** regauging.

those shown by the Sweet vacuum triode amplifier discussed in this chapter.



- Quantum potential decomposes per Whittaker 1903 into bidirectional longitudinal EM waves
- Can insert additional longitudinal waves, thus information using a Fogal semiconductor
- Can receive "signal" and discriminate the information using a Fogal semiconductor

Figure 6-4 Quantum potential communication system.

Strangely, overall conservation of energy is not violated by the quantum potential COP>1.0 energy system. It's just that the energy now is furnished from space (from the vacuum) in a *multiply connected* manner. However, all the excess energy is still furnished by the active external environment - i.e., from the time domain, according to the giant negentropy process {12} — though that environment now is quite novel and multiply connected. So we still have a system analogous to a windmill, though *a very novel windmill and a very novel wind indeed.*

Without belaboring the point, action-at-a-distance is absolutely required in quantum mechanics. Further, photon correlation experiments have long demonstrated experimentally that such action-at-a-distance effects do exist, just as predicted. This was a refutation to Einstein's objection to quantum mechanics' "spooky action at a distance".

We point out without further comment that, if a self-powered process is Invoked in the initiating station, then all other participating stations also contain that self-powered process. However, note that one does not really wish to "invoke" a quantum potential connection and use it except occasionally and very quickly! Otherwise, if a strong QP is turned on and **left** on among many distant stations, anything and everything happening to each one of them can instantly appear in all of them, so long as the "constant of connectivity" remains a constant or nearly so.[160] For that reason, strong quantum potential connections can be self-destroying and strong effects do not seem to normally appear in the physical world.[161] The proper energy use of a quantum potential is thus to use it only for fleeting "inductions" of effects in the desired stations, in *momentarily* multiply connected spacetime, at least until the self-limiting behavior is ascertained.

Apparently, a quantum potential can sometimes be formed in the limit of an iterative, mutually phase conjugating operation of EM signals passed back and forth between two phase conjugate mirrors, or among many of them. Such iterative mutual phase conjugate reflection of signals — particularly pumped signals — is technically known as iterative *self-targeting.* Sometimes we use a more picturesque term, *ping-pong,* for iterative self-targeting.

Conceivably, strongly coupled, strongly pumped optical self-targeting mirrors can — in the extreme limit — initiate or partially initiate a quantum potential. The superposing beams of energy may be thought of as first narrowing to laser-like beams, then gradually subsiding into pure longitudinal waves with transverse components "canceled" to form simply "stress energy". In short, if this reaction occurs, the energy is transformed into a stress energy potential, which acts either as a scalar potential in the Coulomb gauge or as Bohm's quantum potential. In our view, the pure longitudinal wave has infinite velocity, as pointed out by Rodrigues and Lu {93a}, so Lorentz-Fitzgerald contraction results in "zero-separation distance", which in turn results in a multiply-connected spacetime.

One points out that the "input energy" to the initiating station may be deliberately structured internally, including altering the internal Whittaker longitudinal EM wave functions comprising the input electrical field energy. In this manner, in theory deliberate spacetime curvature sets and dynamics can be introduced into the distant but multiply connected targets. A form of highly advanced electro-biological warfare induction of disease has been developed by at least one nation (Russia) in this regard, as an extension of Kaznacheyev's experiments showing induction of cellular disease at a distance. It appears that the cells of a living body are interconnected by a very weak quantum potential in such manner. Again, a great deal more research on that possibility is needed.

---

[160] Fortunately, it appears that this connectivity constant is not really constant, but reduces as the feedback of each station's fluctuations to the other stations increases. The result seems to be a "leveling off process reaching a plateau and a fixed amount of gain in the overall system. In short, the system usually seems to be "self-adjusting" and "self-limiting" as the overall gain increases. Nature is riddled with quantum potentials, but this self-limiting process keeps most so tiny that they are not even noticeable.

[161] However, the validity or invalidity of this statement for some of the highly energetic phenomena of astronomy remains to be determined. It also remains to be determined as far as the quantum potential's role in generating the zero point energy fluctuations of the active vacuum.

Given a quantum potential connection between separated objects including our initiating station, one can also add vacuum *engines* (energy structuring of curvatures of spacetime itself) as our input to the initiating node. Those vacuum engines will then simultaneously appear unabated (or only partially abated) in the multiply connected separated objects. In this way, in theory one can use the QP and QP energy to perform highly anomalous *momentary* engineering of nuclides, materials, fields, etc. in widely separated, distant objects and areas. By repeating the momentary engineering "pulses", distant objects and areas can be profoundly altered.

The use of vacuum engines in medical applications is of particular future interest.[162] Very radical extension of those techniques can be achieved once quantum potential technology is developed and available in the open scientific community.

But let us ignore the weapons, free our scientific imagination, and let it roam. As an example, in the future a vacuum engine (spacetime curvature engine) might be developed and utilized in a world-wide quantum potential to *momentarily* strike and eradicate all AIDS viruses on Earth, and do only that. Or, the engine could be slanted to simply *momentarily* slightly change those viruses into an innocuous kind of new virus. The cells of the individual human body are already connected, it appears, by a very weak quantum potential. By connecting an external initiating station to that body's quantum potential, the energy of the body could be directly scanned, all abnormalities noted, and tailored engines created and *momentarily* used to treat the body and correct its abnormalities and malconditions. This, we believe, may well be a medical therapy of the future, a few generations from now. [163]

---

[162] See Vlail Kaznacheyev and L. P. Mikhailova, *Ultraweak Radiation in Intercellular Interactions,* [in Russian], Novosibirsk, 1981; Vlail Kaznacheyev *et al.,* "Distant intercellular interactions in a system of two tissue cultures," P*sychoenergetic Systems,* 1(3), Mar. 1976, p. 141-142; Vlail Kaznacheyev, "Apparent information transfer between two groups of cells," *Psychoenergetic Systems,* 1(1), Dec. 1974, p. 37. Unfortunately this QP induction of cellular disease has already been used by the former Soviet Union to develop a QP extension of the **force**-free structured potentials method first used to induce cellular disease and **health** changes in U.S. personnel in the former U.S. Embassy in Moscow for several decades. Now QP weapons using such techniques can target the entire population of a targeted nation. Using the internal Whittaker structuring of quantum potentials and EM fields and waves, *electromagnetic biological warfare* has already been born and highly developed. The actual dimensions of possible biological warfare strikes are far greater than has been mentioned in the open literature.

6.3 Other Systems of Electrical Interest

6.3.1 Russian Parametric Oscillator Power Systems

In leading physics institutes and laboratories in the 1930s, Russian scientists built COP>1.0 parametric oscillators, including some of appreciable size. The work is documented in the literature {362a-k}, both in Russia and in France. The devices were developed and tested in several Russian laboratories. With linear loads, the oscillators would progressively build to self-destruction. With nonlinear loads, the devices would stabilize and power themselves and their loads, at a level depending on conditions — reminiscent of the behavior shown in Figure 4-3 in Chapter 4 for stability COP>1.0 levels for the asymmetrical self-regauging process.

Standard references for parametric oscillation in EM circuits are available. However, with standard practices none of these conventional oscillators produces COP>1.0, primarily because the conventional closed current loop circuit is applied without special modifications. For overunity work, the

---

[163] Apparently, tests of such QP capabilities in weaponry have been gingerly conducted for direct induction of disease patterns in the population of a targeted nation or area. One symptom of such a test is that a very small number of widely isolated cases of the same disease breaks out simultaneously, in isolated cases scattered widely and puzzlingly throughout the population, *without the possibility of any direct carrier vector connection.* Apparently, the test inductions have deliberately been held mostly to the "shadow state" (or upper virtual state, just below observable state) in most of the targeted populace, to prevent giving away the tests. However, the human immune system and cellular regenerative system do respond to such "near-observable-state" signals and engines, when sustained or repeated in time, by a sort of coherent addition (integration) over time. The bell-shaped distribution curve predicts that a few individuals, randomly scattered throughout the populace, will have quite lower induction thresholds and will evidence the actual disease after a certain time, whereas in almost all the other members of that population the "disease" will never evidence in the observable state during that time. The test is deliberately terminated when only a few observable cases occur, which are sufficient to prove the efficacy of the test and the method.

Russian and French literature (as we referenced) should be meticulously studied and analyzed in a higher group symmetry electrodynamics, to see how the Lorentz condition is broken during discharge of circuit excitation energy in the load, and how the COP>1.0 Dirac hole current decay mechanism is avoided or contained.

The Russian COP>1.0 parametric oscillation work appears to have been suppressed by the Communist regime just prior to WW II. After the war, all such technology passed under the rigid control of the KGB (by whatever name it took and takes from time to time) and into the special weapons research and development area — still highly classified in Russia. We know of no similar work presently ongoing in the West, although at least an English translation of one of the major summary documents of the Russian parametric oscillation COP>1.0 power system developments was performed under NASA auspices {363}. However, in conventional U.S. parametric oscillation research, I know of no case where COP>1.0 operation is being sought, or where the Dirac sea hole current decay mechanism is even mentioned or recognized {364}.

6.3.2 Sweet Vacuum Triode Amplifier

During the 1980s and 1990s, the present author worked —sometimes closely for extended intervals — with inventor Floyd Sweet, the inventor of the Sweet vacuum triode amplifier (VTA). Indeed, we gave the unit its VTA name, at Sweet's request.

Fig. 6-5 (pg. 384) shows a diagrammatic illustration of the fundamental VTA construction. Two coils in quadrature are between two barium ferrite "brick" magnets, of the kind formerly used in many power audio systems. The vertical coil is the "input" signal coil, and the horizontal coil is the "output" power coil. The input consisted of a 33 microwatt 10 volt 60-Hertz signal, and the output was a 120-volt 60-Hertz 500-watt signal. The barium nuclei in the magnets were specially preconditioned by Sweet so that they were in powerful self-oscillation with the surrounding energetic vacuum. A double-edged razor blade or piece of shim stock placed on one of these magnets would oscillate back and forth, incessantly, without cessation — showing that the magnetic field itself was "waving" back and forth (Figure 6-6). It was also continually doing work against air **resistance,** by moving the air.


Self-oscillating shim-stock,
waving to and fro steadily,
continuously performing work
against air resistance.
Conditioned barium ferrite magnet
with self-oscillating H-field

Figure 6-6 Blade waving continuously on Sweet's conditioned barium ferrite magnet.

Sweet had a Master's degree in electrical engineering from a leading university and handled the mathematical theory very well. He had worked at General Electric for many years, and Gabriel Kron was his patron and mentor. Sweet often spoke glowingly of Kron, and I came to believe that Sweet's VTA was probably an outgrowth of, or very similar to, Kron's negative resistor.

- Two activated magnets facing, with fields in self-oscillation.
- Barium ferrite magnets, barium nuclei in self-oscillation
- Barium nuclei self-pumped
- Two coils in quadrature, load is lamps, six watts
- Next unit produced 500 watts output with 330 microwatts input; later made 5 kW VTA



Figure 6-7 First Sweet VTA producing 6 watts output.

When I first met Sweet, his little VTA system was producing a 6-watt output, enough to light four 1.5 watts of auto lamps (Figure 6-7. But there was no question as to the genuineness of the device. Nothing was hidden, and Sweet allowed me to measure the device at will, disassemble it, play with it, and examine it in any fashion. It was genuine, and not a hoax or trick. I also locked up one of his specially conditioned magnets for 24 hours, with a piece of shim stock sitting on the flat of the magnet and waving to and fro continuously, steadily performing work by moving air. When I opened the lock the next day, the shim stock was still there on the magnet and oscillating, having continuously done work against the air resistance for 24 hours with absolutely no energy input by the operator. And it was still working. Indeed, that single "kinetic" permanent magnet destroys all objections to COP>1.0 EM systems, including those that are self-powering and thus have $COP = \infty$.

It seems little known that the vacuum around nuclei, in some cases, can be treated as a semiconductor, e.g. as discussed by Prange and Strance {365}. It is also known that nuclei do exhibit resonances at ELF frequencies. In particular, the vacuum in the region close to the nucleus of a superheavy element is known to act in a fashion analogous to the inversion layer in a field effect transistor. Prange and Strance introduce the idea of the inverted vacuum. Just as a semiconductor may be manipulated by subjecting it to external fields, doping etc., it appears that the vacuum can be similarly manipulated by appropriate means. We personally suspect that the semiconducting vacuum can be and is resonantly involved in any ELF resonances of the nucleus, which can occur in lighter nuclei such as barium.[164]

The virtual particle flux of vacuum, regarded as noise, may provide noise amplification of the coherent self-oscillation frequency between the semiconducting vacuum and the barium nucleus. Certainly, analogous noise amplification of signals is known in electrical physics {366}.

---

[164] Here our concept of the supersystem may be of utility. The "lock-in" or "freeze-framing" of an equilibrium condition for a system — such as in a state of nuclear ELF self-oscillation — is stabilized and made a "new equilibrium condition" when the force field reaction from the curved local spacetime into the system is equal and o**pposite** to the force field reaction from the local active vacuum into the system. We believe Sweet's undisclosed activation process was a method for synchronizing those two force field reactions and making them equal and opposite in one short discharge. We hope that this speculation is of use to future experimenters trying to duplicate Sweet's activation of his magnets into sustained and powerful supersystem self-oscillation.

I hypothesized that Sweet's activation process treated the vacuum surrounding the barium nucleus in such fashion, so that he was able to establish self-oscillation between the local activated vacuum and the concomitantly activated barium nucleus. Since barium ferrite is optically active, it may be that Sweet discovered how to get sufficient "self-pumping gain" for the self-oscillation to endure and not die away in a decaying oscillation manner. Since the "gain" of the second VTA as a self-pumping device was some 1,500,000 (Figure 6-8), obviously Sweet's activation method introduced a powerful state of self-oscillation.[165]


- Two activated BaFe magnets in self-oscillation
- Barium nuclei self-pumped
- Two coils in quadrature
- Load is 5 lamps, 500 watts
- Input 330 microwatts

Figure 6-8 Second Sweet VTA producing 500 **watts and C0P=1,500,000.**

---

[165] Here we point out that "small" things with very close "double surfaces" of opposite charge or potential usually have very large fields. The tiny Lamb shift, e.g., has a local energy density greater than the surface energy of the sun. Jackson, *Classical Electrodynamics,* Second Edition, 1975, p. 10-11 points out that *"field strengths of the order of* 10^9*-*10^{15} *volts/cm exist at the orbits of electrons in atoms, while the electric field at the edge of a heavy nucleus is of the order of* 10^{19} *volts/cm."* It should be obvious to the reader that, if our speculation is true and nuclear oscillation of the barium nuclei is involved, the production of optical gains of 1.5 x 10^6 in Sweet's self-pumped, optically acting barium ferrite magnets is not surprising because of the extreme magnitude of the oscillating nuclear fields. In that case, optical gain converts directly to true power gain because the pumping energy is furnished freely by the environment and not by the experimenter.

6.3.2.1 Mapping the Magnetic Field of the Magnets

Figure 6-9 shows a small magnetic field mapping device built by test engineer Rosenthal for Sweet. Sweet "scanned" and mapped the consistency of the magnetic field from his candidate magnets (barium ferrite magnets bought from surplus stores at the time). If the consistency varied over 12 to 15%, the magnet was useless because it would not "hold" the activation and retain it. Magnets whose magnetic field variation did not exceed 10% were ideal. So Sweet only found about 1 in 10 or even 1 in 30 magnets that would retain the self-oscillation state when initiated.



Figure *6-9* Test engineer Rosenthal points to a magnetic field strength mapping device he built for Sweet.

Sweet may have actually used two appreciably higher frequencies in his activation process, with the difference frequency between them being a precise ELF frequency (60-hertz, 100-hertz, 400-hertz, etc. as he desired). That would make sense, when one realizes that the magnet is a highly nonlinear medium and then treats it (to first order) as an isotropic nonlinear medium. In that case, the two wave frequencies actually used would be subject individually to the normal overshoot, breakup, reconstitution, etc. inside the material of the magnet — but the difference frequency would behave as if it were a sine-wave frequency {367}.

This makes sense, since the output wave of Sweet's activated magnet was essentially a pure sine wave. Also, the presence of noise-enhanced heterodyning can sometimes be used to amplify a difference signal even further {368}. As we stated, since the activation is a self-oscillation between the local semiconducting vacuum and the barium nuclei, one wonders whether much of the rest of the vacuum virtual particle flux can be treated as noise, and whether an effect is obtained for noise amplification of the coherent self-oscillation frequency.

L'vov and Prozorova {369} point out some interesting characteristics of the formation of self-oscillating spin waves which occur above parametric excitation. These oscillations result when internal stability does not occur, and they evidence themselves as oscillations of magnetization. The frequencies of the oscillations usually lie in the range from tens of kilohertz to tens of megahertz. At small above-threshold ratios, the shape of the oscillations is nearly sinusoidal. At larger ratios, the shape differs appreciably from sinusoidal. At still larger ratios, the oscillations become chaotic.

If Sweet did use the "difference frequency" conditioning, one suspects he may thus have been able to utilize larger above-threshold ratios, where the two frequencies actually transmitted would have resulted in chaotic oscillations. It is interesting to speculate that, in that case, for a suitably chosen barium ferrite magnet, the difference frequency still can behave sinusoidally, but now much stronger. If so, that might account for the tremendous COP Sweet attained in his second unit, which exhibited a COP = 1.5×10^6, and could be pushed even higher.

6.3.2.2 Sweet VTA for Closed-Loop Self-Powering Operation

Courtesy of Walter Rosenthal, we now present a visual record of the Sweet closed-loop self-powering version of the VTA and its momentous successful acceptance test on May 1, 1990, as closely observed by Rosenthal.

Figure 6-10 shows Sweet and a different version of the VTA, with the coils in a slightly different configuration and the windings altered. This is the two-magnet, 2-coil VTA that he built and tested for self-powering operation. Figure 6-11 shows the unit mounted on a special test fixture built by engineer Rosenthal. This fixture and its components allowed the sensing of the sine wave output power at the zero-value crossover points. To switch in the special clamped feedback system for self-powering operation of the input, and simultaneously switching away from external power, the switching had to be done very accurately at that zero-point crossover. Feedback would not stabilize and hold if the switching were done at any other point in the output cycle.

Unit independently examined and testing observed by
test engineer Walter Rosenthal



Figure 6-10 Sweet with 2-magnet 2 coil VTA, loads, and instruments for historic self-powering operational tests on May 1,1990.

Figure 6-12 shows the set-up for the tests, with the unit and loads as well as some of the instruments used. Figure 6-13 shows the closed-loop VTA powering itself and its loads, after being initially set into operation with outside input power by the operator, and then adroitly switched into self-powering by switching the input from external to internal at an output

Fixture allowed unit to be started into operation on external power then switched to self-powering internal power at the zero crossing of the *output* voltage The device in its fixture has a row of test points (disconnects) on every conductor going to the device



Figure 6-11 Two-magnet two-coil VTA mounted on a special test fixture built by Walter Rosenthal.

power zero crossover point. This picture shows the unit in self-powering and stable operation, taking all its input energy from the vacuum, including the power necessary to power its own internal losses and the power necessary to power its controls and loads.

Independently examined and testing observed by test engineer Walter Rosenthal



Figure 6-12 The 2-magnet, 2 coil VTA, loads, and instruments for its historic self-powering operational tests on May 1,1990.

Formal self-powering test on 1 May 1990 The loads and the VTA are powered by electrical energy extracted directly from the activ e vacuum Independently observed by professional test engineer Walter Rosenthal



Figure 6-13 Historic self-powering operational test of the VTA May 1,1990 with no energy Input by the operator.

We strongly stress that this operation is permitted by the laws of physics and thermodynamics for an open EM system far from equilibrium in its exchange with its active environment. The active environment in this case is the combination of the active local vacuum and the active local curvatures of spacetime. The closed-loop condition is a new and stable equilibrium condition in the dynamics of the mutual exchanges between all three supersystem components: the system, the active vacuum, and the curvatures of spacetime. The *system* is in stable disequilibrium; the *supersystem* is in a stable new equilibrium condition.

6.3.2.3Discussion

We do know that the output current of the second Sweet device was comprised of a significant Dirac hole current[166] as well as electron current — showing the expected heavy involvement of the altered local vacuum (the Dirac sea) and the curved local spacetime. The negative energy majority of the output revealed itself readily. If the output leads were shorted, ice formed instantly on the shorted leads from the moisture in the air. That is, an electrical short resulted in the sudden production of cold (negative) EM energy rather than positive EM energy.[167] That can only occur if the majority of the output is negative energy, and any sudden surge in output (as from the shorted leads) increases the ratio of negative energy to positive energy so that very strong net cooling results.

For many predominantly mechanical components (simple electrical motors, light bulbs, etc.), Dirac hole current applied to the positive lead will power the circuit equally as well as electron current applied to the high voltage (negative) side, if the grounding is simply by a conductor and not a "vast reservoir" of charge. In such case, the wire chosen to conduct or direct the Dirac hole current should be made very small. It can and will carry intense hole current and will cool rather than heat.[168] The wire to the electron side of the device should be made normal sized, appropriate to the electron current to be carried.

---

[166] We do mean hole current in the Dirac sea, consisting of Dirac holes in the vacuum itself, prior to their interaction with charged matter to form lattice holes in matter. We do not mean the standard lattice hole current at all.

[167] In local curved spacetime, Dirac holes constitute "negative energy EM fields and potentials". In such case, one can have negative energy entities and reactions analogous to positive energy entities and reactions in 3-space. On the time axis, one also has negative energy entities and currents, potentials, waves, fields, etc. Because **classical** Maxwell-Heaviside-Lorentz theory eliminates any modeling of the local vacuum or the local curvature of spacetime, these negative spacetime curvature **(negative** energy) potentials, fields, and currents have not been added into the electromagnetic theory. That of course is a serious shortcoming of the normal theory.

Several other inventors over the years have been able to activate a barium ferrite magnet into sustained self-oscillation of its material particles or domains, in similar but weaker fashion for varying lengths of time — up to a month or so in the longest time that I am aware of. Sweet's magnet would continue in self-oscillation indefinitely unless (i) the magnet was sharply shocked mechanically (as with a hammer blow), (ii) the magnet was heated to too high a temperature, (iii) the leads of the output circuit were electrically shorted, or (iv) external artificial field interference (electrical pulse shock, particularly from longitudinal stress waves) was encountered.[169,170]

Unfortunately, Sweet signed multiple conflicting agreements with several financial backers, and his work was legally entangled so deeply that it was never straightened. He eventually died, taking with him his activation secret. He was often threatened, and was once fired at by a professional assassin using a silenced rifle. He survived the incident because, being old and a bit feeble, he stumbled and fell over the front steps just as the assassin fired. The bullet snapped by his ear, right where his head had just been. The incident was reported to the FBI, but with nothing else to go on, the assassin was never caught.

---

[168] This is very probably the secret of Tesla's "single wire system". At an exposition in Nevada, Bedini demonstrated just such a system, by powering 600 watts of audio speakers at the end of a long, very thin wire across the stage from his power amplifier. If he had been using positive EM energy, the wire would have instantly melted.

[169] During that period, the Russians were playing with earthquake induction via scalar interferometers, at various places around the world, including inside the U.S. heartland. Sweet's machine would sit above a natural quake and not be affected. But when a quake within many hundreds — even several thousands — of miles was artificially induced, the Sweet device would react to it. A fairly close artificially induced quake would destroy the self-oscillation of the magnets, and sometimes a very close artificially induced quake would actually explode the intensely activated magnets. So for several years one had a way of ascertaining which quakes were natural and which were artificially induced, by simply having Sweet confirm how his magnets interacted.

[170] For those who do not believe such an activity, here is a direct statement by then-Secretary of Defense William Cohen: *"Others are engaging even in an eco-type of terrorism whereby they can alter the climate, set off earthquakes, volcanoes remotely through the use of electromagnetic waves... So there are plenty of ingenious minds out there that are at work finding ways in which they can wreak terror upon other nations...It's real, and that's the reason why we have to intensify our efforts. "* Quoted from DoD News Briefing, Secretary of Defense William S. Cohen, Q&A at the Conference on Terrorism, Weapons of Mass Destruction, and U.S. Strategy, **University of Georgia, Athens, Apr. 28, 1997.**

By whatever means, we do know that Sweet's magnets had to be activated by a special process that Sweet used and never fully revealed. An activated or "kinetic" magnet, it seems, was actually something a few of the "older magnetics guys" had known about, and Sweet had learned of it either from them or from Gabriel Kron. Sweet was also a transformer designer and expert, and he remarked that he had also observed specialized self-oscillation in certain transformers. Although most power engineers approached were either nonplussed or completely skeptical of a "self-oscillating field in a permanent magnet", self-oscillation of the fields, spin waves, etc. in permanent magnet materials *are* known to materials scientists today, especially to those working with magnetic effects in thin film materials {370, 371a-b}.

From a general relativity viewpoint, particle spin has a unique spin field of its own {372}, and there are such spin fields involved and operating in magnetic systems. The simple classical electrodynamic approach to magnetism and magnetic assemblies — or the view of a magnet as simply a bar with a north pole and a south pole — is quite insufficient when one wishes to research magnetic assemblies that will act as open systems far from equilibrium with their active environment, and thus will be capable of COP> 1.0 operations.

Recent work in coupled spins has revealed long-range coherence effects, previously unsuspected, as well as dual spin states participating in such phenomena {373a-b}. For example, Johnson has long used a 2-particle approach to spins and spin flipping in his own highly nonlinear magnetic assemblies {374}. His recent laboratory work has also shown similar and unsuspected *long-range coherence* effects in large multiple-magnet macroscopic systems {375} such as large assemblies of neodymium-iron magnets. This is strongly suggestive of the expected general relativistic spin field previously mentioned.

This work by Johnson is very important, since it may reveal a hitherto unsuspected mechanism for decay — of an otherwise nonconservative magnetic field around a closed loop — back into a conservative field. If one seeks an all-permanent-magnet rotating motor, a nonconservative magnetic field around a rotation loop must be established and sustained if one is to have self-rotation and self-powering. A nonconservative magnetic field around such a rotation loop means that the system acts as an open system far from equilibrium with its active vacuum and active curved spacetime environment, by means of some asymmetry mechanism such as multi-valued magnetic potential {376a-c, 377a-g}, elucidation of exchange forces {378a-c} at selected positions and directions, etc. It also requires both a stable broken 3-symmetry and a stable 4-symmetry.

On the other hand, in our opinion, Sweet employed spin waves triggered into self-oscillation in the nuclei of the barium atoms in his barium ferrite magnets. Indeed, such nuclear spin waves in magnets have been known for some time {379}. We postulate that, as in any other COP>1.0 power system, a self-rotating all-permanent-magnet motor must also involve Dirac sea hole current interacting in the various magnetic components. It is reasonable to suspect that these also interact with the electrons and their spin fields, perhaps producing the active mechanism providing that observed long-range coherence that apparently can decay the nonconservative magnetic field around the rotation loop, causing it to revert back to a conservative field and thereby stop the self-rotation and self-powering. If so, that long-range coherence must be violated and the violation stabilized. However, we could find no papers in the literature that deal with such possibilities. Hence it is a subject for further investigation by COP>1.0 researchers.

***6.3.2.4 The** Highly Successful Anti-Gravity Test*

On one trip to California to work with Sweet, we noticed that, at full power output of 500 watts, his unit weighed a little less on the bench than when not powered. Struck by this anomaly, I considered the negative energy aspects of the output — as evidenced by the Sweet's demonstration of icing when the output leads were shorted — and the very high gain, which added up to a predominance of negative energy in the output.

Pondering this from a general relativity viewpoint, I reasoned that: (i) increase of positive EM energy density in space increases the curvature of spacetime to produce additional positive gravity G_P; (ii) increase of negative EM energy density in space must increase the curvature of spacetime in the other direction, and thus it must produce negative gravity G_{N}., and (iii) the total gravity G_T produced in the immediate spacetime of an object producing both positive gravity G_P and negative gravity G_N, was $G_T = f(G_P + G_N)$. Thus if we increased the output of the VTA unit, we must inevitably increase the weight reduction (antigravity) effect since the predominance of the energy output was negative energy, and this output was in the neglected negative energy fields aspect as well as in the local vacuum (spacetime) itself. After several back-of-the-envelope estimates and educated guesses over some weeks, I concluded that if the efficiency of the antigravity process[171] were 10% and the unit was pushed to 1500 watts output, it would lose all its weight and hover weightless.

However, because of the nonlinear local spacetime, magnetic monopoles[172, 173] were deposited in Sweet's magnets when the unit was producing power, and the density of these monopoles varied as the output power. Increasing the power output thus increased the tensile stress of the magnets, and at some point they would explode into fragments, like a hand grenade.[174] This explained why conditioned magnets sometimes exploded when experiencing fluctuations from artificial earthquake induction testing.

---

[171] We again accent the difference between efficiency and COP. Here we are definitely speaking of efficiency, not COP.

[72] Dr. Robert Flower has confirmed that the 'symmetrized" (or "extended") Maxwell equations (Eqs. 7.1 in Springer's *Encyclopedia of Physics,* Vol. 16, p. 431) include non-zero magnetic charges and magnetic currents. Antenna engineers (Henning Harmuth, and others) know that these terms must be included for proper description of boundary conditions, even though, at the final step of computation, their integrals are set equal to zero (apparently to snuff out magnetic monopoles). For Dirac's original theory of the monopole, see P. A. M. Dirac, "Theory of magnetic monopoles," *Phys. Rev.,* Vol. 74, 1948, p. 817-830. See also F. A. Bais and B. J. Schroers, "Quantisation of Monopoles with Non-abelian Magnetic Charge," *Nuclear Physics B,* Vol. 512, 1998, p. 250-294; G. Lochak, "The Symmetry Between Electricity and Magnetism and the Problem of the Existence of a Magnetic Monopole," in T. W. Barrett and D. M Grimes. [Eds.] *Advanced Electromagnetism: Fundations, Theory, & Applications,* World Scientific, 1995, p. 105-147. Particularly see T. W. Barrett, "On the distinction between fields and their metric: the fundamental difference between specifications concerning medium-independent fields and constitutive specifications concerning relations to the medium in which they exist." *Annales de la Fondation Louis de Broglie,* 14(1), 1989, p. 37-75; — "Electromagnetic Phenomena Not Explained by Maxwell's Equations," in Lakhtakia, A. (ed.): *Essays on the Formal Aspects ofElectromagnetic Theory,* World Scientific, River Edge, NJ, 1993, p. 6-86; — "The Ehrenhaft-Mikhailov effect described as the behavior of a low energy density magnetic monopole-instanton." *Annales de la Fondation Louis de Broglie,* Vol. 19, 1994, p. 291-301. The work of Ehrenhaft, which is now substantiated and thoroughly replicated by Mikhailov, has produced experimental evidence of the magnetic monopole in many replicable experiments. In these experiments, magnetic particles move in a magnetic field along the lines of force. Reversal of the magnetic field, H, causes a reversal of the magnetic particle's motion, which is not the case with magnetic dipoles, since that can only occur for a monopole. See V. F. Mikhailov, "Observation of magnetic monopoles in the field of a line conductor," *J. Phys. A: Math. Gen.,* Vol. 18, 1985, p. L903-L906; — "Observation of the magnetic charge effect in experiments with ferromagnetic aerosols." *Annales de la Fondation Louis de Broglie,* Vol. 12, 1987, p. 491-523. See also M J. Perry, "Magnetic monopoles and the Kaluza-Klein theory," *Am. Inst. Phys. Conf. Proc,* No. 116, 1984, p. 121-125; E. V. Smetanin, "Electromagnetic field in a space with curvature — new solutions," *Soviet Physics Journal,* 25(2), Feb. 1982. p. 107-111. [English translation]. See also T. T. Wu and C. N. Yang, "Dirac monopole without strings: monopole harmonics," *Nuclear Physics,* Vol. B107, 1976,

Having no explosive control facilities, I warned Sweet not to push the unit past 1,000 watts, for safety reasons. At my urging, Sweet made a new output load of ten 100-watt lamps in sockets, so the load could be varied from 100 to 1,000 watts easily.

---

p. 365-380; — "Dirac's monopole without strings: classical Lagrangian theory," *Phys. Rev. D.,* 14(2), July 15, 1976, p. 437-445.

[173] We emphasize that a magnetic monopole can be taken simply as a highly localized magnetic scalar stress potential. See, e.g., P. A. M. Dirac, "Theory of magnetic monopoles," *Phys. Rev.,* Vol. 74, 1948, p. 817-830. Dirac pointed out that the existence of a single magnetic monopole in nature would allow an explanation for charge quantization. We believe that the reverse of Dirac's argument may be true also: The existence of charge quantization should allow an explanation for the magnetic monopole. However, we also surmise that a magnetic monopole exists only in (and as) a sharply localized curvature of spacetime. Jackson, *Classical Electrodynamics,* second edition, 1975, p. had this to say about magnetic dipoles and Dirac's argument: *"Dirac's argument... is that the mere existence of one magnetic monopole in the universe would offer an explanation of the discrete nature of electric charge. Since the quantization of charge is one of the most profound mysteries of the physical world, Dirac's idea has great appeal. "*

[174] Sweet in fact did explode several magnets by pushing the power output of the device. Pushing the output was easy (and is easy for any unit outputting mostly negative energy), because all one had to do was connect additional load.



Figure 6-14 **Results** of the "pushed" VTA **antigravity test:** Weight **of VTA on the bench versus power output.**

Sweet completed the new load section and performed the experiment in California after 1 had returned to Huntsville, reading off the results to me over the phone. I took down the data, and then plotted the curve. Figure 6-14) shows the beautiful results. At 1,000 watts the unit had lost 90% of its weight. This was electrifying, because it was an unprecedented and highly successful antigravity experiment. Even my original "rough" assumption of levitation at 1500 watts was not too far from the indicated 1250 watts or so from the actual curve.


NEGATIVELY CURVED LOCAL SPACETIME ACTS BACK UPON SOURCE VEHICLE, PRODUCING ANTI-GRAVITY AND UNILATERAL THRUST
NEGATIVE ENERGY EM FIELDS; NEGATIVELY CURVED SPACETIME
COP>>1.0 GENERATORS FOR NEGATIVE ENERGY EM FIELDS
SOURCE VEHICLE
NEGATIVE ENERGY EM FIELDS; NEGATIVELY CURVED SPACETIME.
Varying individual generators warps negative energy fields, warping negatively curved spacetime, producing additional directional thrust up, down, laterally as needed.

Figure 6-15 Proposed mechanism for practical antigravity.

Figure 6-15 shows my proposed mechanism for antigravity. We simply use negative EM field energy generators to produce a negative EM energy field in space surrounding the source vehicle. The associated positive energy from the same energetic power source can power the vehicle simultaneously. The local reversed curvature of spacetime now interacts back upon the mass of the vehicle, to produce an antigravity component. By adjusting the output of the power source, the amount of negative energy — and hence the amount of antigravity component — can readily be varied and controlled. By controlling the directions of the field components, one can have unidirectional antigravity force, or antigravity and thrust force vectors simultaneously. Hence such a vehicle could be maneuvered and controlled, and be self-powering. This at least was and is my concept of a practical antigravity technology.

6.3.2.5 Later Developments and the End of the VTA

Later I prepared a paper on the VTA, including the antigravity experiment's results. We succeeded in getting the paper published {380} but I deliberately did not include the real details of the negative energy aspects as I wished to withhold that information for patenting. I prepared the entire paper, but placed Sweet's name first, as was appropriate since he was the inventor of the VTA.

Unfortunately — but understandably! — Sweet became a bit paranoid after the sniper assassination attempt (he was shot at by a distant sniper using a silenced rifle), and then would never allow a formal demonstration of his antigravity test. I strongly wished to present it to a major national U.S. scientific committee for independent testing and confirmation — which could have been done without Sweet having to reveal his activation process for the magnets. However, Sweet would not hear of such. Indeed, he fearfully kept the antigravity capability a secret from most of his backers. He strongly believed that he would be killed almost immediately if he revealed our antigravity experimental success. He may have been correct.

In fairness, the inventor and his backers of necessity have different priorities from those of scientists doing open research in a university. But at least a record of the test results is in the literature, though certainly not as rigorously or as extensively as I wished. Sometime later, I withdrew from any further association with the VTA unit, after the backers changed, a lawsuit broke out, and the entire project unraveled. Sweet later died without ever revealing his full secret for such powerful activation of self-oscillation in permanent magnets at low ELF frequencies.

The loss of the Sweet vacuum triode was a severe blow to science and a real setback to the scientific progress that could already have been made. Nonetheless, I contributed what I could, documented what I could, and made a videotape of the operation of the open-loop 500-watt device in the power mode. I also made a video of as much as Sweet would reveal of his activation process. I was not allowed to videotape a second antigravity experiment, even though I frequently and strongly requested it. By that time, Sweet mortally feared for his life. Perhaps what we have written in this book will be sufficient to provide some needed clues to some future graduate student or post-doctoral scientist who will succeed in recovering the necessary activation of magnets and both the COP»1.0 power capability and the antigravity experiments.

Meanwhile, I have filed a provisional patent application on the mechanism for antigravity, the gist of which I worked out solely on my own back in 1971 at Georgia Institute of Technology, and that I include in Chapter 8. As far as I am aware, no one else had thought of it previously, or has thought of it in that exact form *{using the causal positron prior to observation, and while it is still a negative energy, negative mass electron, as the source charge for negative EM field energy, and also using the causal positron's corresponding giant Heaviside nondiverged negative energy flow for substantial negative curvature of spacetime.).*

6.3.3 Intense Discharges in Ionized Gas

Intense sudden discharges in ionized gases are especially of interest due to the presence of optical frequency components and the involvement of iterative optical retroreflection etc. These processes seem to be involved in several investigations and inventions. Further, it appears that such intense discharges do produce bursts of negative EM energy as part of their overall discharge energy.

In the case of plasmas, some are known to transduce an input transverse EM wave into an output longitudinal EM wave, and vice versa. We know now that such a longitudinal EM wave is also accompanied by a time-polarized (scalar) EM wave in the time domain. The connection with the Whittaker 1903 decomposition of the potential, and with the new 4-symmetry negentropy law, is apparent. Several COP>1.0 researchers — notably Shoulders {381a-f} and Paulo and Alexandra Correa {382a-e} — have performed extensive research into anomalous discharge phenomena, and also have developed experimental devices capitalizing on the novel effects available.[175, 176] The Correas' U.S. Patent No. 5,449,989 includes many tests of a Correa glow discharge apparatus, one of which in 20 minutes of operation produced 0.988 kilowatt-hour of energy output for an input of 0.258 kilowatt hours. Using the known negative resistor characteristics, the Correas achieved sustained self-oscillations in the discharge.

As an aside, we point out that the well-known anti-Stokes emission — which produces more energy output than the experimenter inputs, and hence exhibits COP>1.0 — has long been validated in certain gases such as aniline vapor {383} and H_2 {384}. Stimulated anti-Stokes radiation occurs in many solid materials such as oxides and doped oxides {385}. Assuming the excess energy comes from the internal energy of the molecules, this is a prime candidate for free replenishment of that furnished internal energy of the molecule, via the broken symmetry of the molecular dipoles in their fierce virtual energy exchange with the local active vacuum and local curved spacetime. Of course, conventionally the energy furnished by the molecules, etc. is not replenished from the vacuum, hence anti-Stokes emission can be used for coherent light cooling effects {386}. Apparently the Correas' process accomplishes the energy replenishing, hence the COP> 1.0 performance over a 20 minute period.

Formation of longitudinal EM waves in the plasma forms in certain gas tubes, such as in Priore's gas-filled tubes {387}, may also occur in the Correa experiments and probably do. Longitudinal EM waves, of course, always involve their concomitant, accompanying time-polarized EM waves, since the combination comprises the scalar potential and hence the local curvature of spacetime provided by that scalar potential. The replenishment mechanism involved in longitudinal EM waves and scalar potentials — time-energy transduced into 3-space energy — apparently is

---

[175] Both Shoulders' electron cluster discharges and the discharge phenomena of Paulo and Alexandra Correa have been independently verified. Fox and other scientists have verified COP>1.0 in Shoulders' work, and Mallove has formally observed a self-powering Correa system. Both these highly reputable scientists are well known, have the highest integrity, and I would trust either of them with my life. Further, we point out that strong gradients — as exist temporarily in strong discharge phenomena — are already known to violate thermodynamics. That is one of the areas being researched today to advance thermodynamics, under the aegis of "extended thermodynamics". See Appendix A.

[176] In addition, the Correas have demonstrated a form of energy that demonstrates latent heat. See discussion in Paragraph 6.3.9.

invoked and utilized in the Correas' sustained self-oscillations in the plasma discharge.

6.3.4 Shoulders' Electron Cluster Processes

Valone {388} has summarized Ken Shoulders' charge clusters and processes as follows:

> *"An unusual energy source is the clustering of electrons by a discharge needle into a high density bundle equaling Avogadro's density of a solid.... Ken Shoulders has patented a process (Pat. #5,153,901) that produces electron clusters with such high energy density, they equal processes exceeding 25,000 degrees Celsius upon impact. Yet, he only uses 20 microjoules to produce the effects. The clusters travel at a maximum of one tenth the speed of light and penetrate any substance with accuracy and sharp precision. It is similar to xenon clustering techniques currently used at megavolt energy levels. Low energy nuclear transmutation of the target has also been achieved with this process. Using a deuterium-loaded palladium foil, only the bombardment areas show transmutation into silicon, calcium, and magnesium with electron clusters upon analysis with X-rays. Jin and Fox {389} have postulated that the high velocity electron clusters achieve results similar to accelerators, including penetration of the nucleus, with substantially less power. The new physics of like-charges clustering in bundles under low power conditions opens a wide range of applications including spacecraft maneuvering microthrusters. Overunity efficiency* [sic: should be COP] *is 9 to 1, or higher."*

Ken Shoulders is an accomplished experimental scientist who has discovered and patented many aspects of electron charge clusters, including their COP>1.0 characteristics {390}.

According to his experiments, one of the most remarkable characteristics of these charge clusters seems to be their dramatic reduction of the permittivity of space {391}. Shoulders has noted the remarkable removal Of **positive** charge during the self-formation process of the clusters {392}. In our opinion, the involvement of the supersystem of these charge clusters is shown by that phenomenon. We hypothesize that an accompanying Dirac hole current is shown by the experimental occasions where — in addition to the Shoulders' negative charge clusters — additional charges unite but show effects of having opposite charge {393}. Such changes would change the permittivity of space, which Shoulders has noted. They could also create a time-reversal zone (TRZ), which would account for the clustering of like charges since in a TRZ the law of attraction and repulsion of charges is reversed. In such a zone, like charges attract and unlike charges repel. This could explain why Shoulders has observed both negative charge clustering and positive charge clustering.

This would also explain the remarkable separation of the positive charges from the negative charges — they are simply *repelled* by the negative clusters in a TRZ.[177] This of course immediately involves curvature of spacetime effects, including local changes in the speed of light etc. As stressed by Shoulders, the entire area cries out for extensive and sophisticated experimental investigation on a continuing basis, as well as some powerful new theoretical work. Shoulders has also noted both "black" and "white" (dark and bright) clusters, including their combination and separation, strongly suggesting Dirac holes as well as the electrons in the charge clusters. He has proposed a form of "inertial propulsion" based on some of the mechanisms and asymmetrical forces observed in his experiments, and such asymmetry is possible in curved local spacetime conditions.

The relation of Shoulders' effects to cold fusion phenomena was shown by an experiment in which a deuteron-loaded palladium cathode was impacted by a charge cluster {394}. An explosive-like reaction occurred, and an X-ray analysis of the impact crater showed a number of elements not seen in the nearby palladium surface away from the impact site. Elements such as oxygen, calcium, silicon, and magnesium were detected in the impact site, but not in the surrounding palladium lattice. We would suggest the presence of TRZ-based nuclear transmutation reactions (via quasi-nucleus formation followed by quark-flipping in nucleons as the

---

[177] Since the same TRZ phenomenon generates specific nuclear transmutation reactions at low spatial energy, explaining the anomalous transmutation of elements in cold fusion electrolyte experiments, a strong indication exists that it is a viable mechanism. In our mechanism proposed for the flow of time, a TRZ is produced for charges whenever antiphoton interactions predominate over photon interactions. This indeed implies a change in the permittivity of the local space, local curvature of spacetime, and local changes in the speed of light — all phenomena Shoulders notes in his experiments.

TRZ decays to a time-forward zone). Additional information on this charge cluster phenomenon has been given by Fox {395}.

Other Shoulders patents are pending and his research is continuing. It is our understanding that at least one application is presently being developed for the market.

6.3.5 Mills's Hydrino Energy Cells and Developments

Dr. Randell Mills {396a-396c}, {397} has proposed a cosmic sea of hydrinos (the hydrino is a proposed reduced energy state of the hydrogen atom) to explain his tested energy cells. He envisions — and produces a theory for — hydrogen that is reduced to a lower energy state (the "hydrino"). He has gathered considerable evidence for his theory, and has accounted for some sixty or so infrared spectral lines in the sun's radiation that have previously not been explained. Independent tests appear to have validated his energy production claims.

Several major companies are presently working with Mills and his parent company, BlackLight Power, Inc. Progress can be followed from the company website, www.blacklightpower.com. Developments are ongoing in light, power, plasma, and new compositions of matter. A technical book by Mills {398} is freely downloadable from the website, giving his overall theory, as are other publications by Mills *et al.* {399a-h}. Critical objections to various parts of Mills' theory have been given, e.g., by Zimmerman {400}, with Mills responding strongly and — in our opinion — successfully.

Certain concepts utilized by Mills are, in our opinion, valid and insightful - whether or not the classical quantum mechanics developed by him is found to hold, and whether or not it agrees with ordinary quantum mechanics (which has problems of its own). The point is that *the experiments work.* It is thus the job of the theorists to find what changes must be made to the theory for it to remain consistent with experiment. If they do not like Mills' theory, the proper procedure is to advance one that **is** consistent with all the experimental results, and also to show where Mills' theory is inconsistent with the results.

In our own view, an *observed* positive charge is the output of an ongoing time-reversal process and therefore represents a "time-reversed entity" as observed. Before observation (imposition *of d/dt* operator), the positive **charge** is thus a negative 4-charge comprised of *qt*, not *q.* From that viewpoint, the H+ ion, which is just a hydrogen nucleus (a proton) without an electron shell, may be regarded as a time-reversed 4-entity prior to observation. Further, any energy change in and of the hydrogen atom results in a change in the local energy density of spacetime (ST) *a priori,* hence a change in the local ST curvature.

If we regard the entire hydrogen atom as a set of such ST curvatures and their dynamics, then Mills' consideration of a lower positive energy state *hydrino* simply implies the addition of an additional negative ST curvature to the ST curvature set associated with the normal hydrogen atom. We note that binding energy of the nucleons is already negative energy, and thus just such a negative spacetime curvature. But the binding energy is itself a spacetime curvature *capable of being increased,* as can be any spacetime curvature. In the supersystem, addition of such ST curvature is possible, and it is *doable* electrodynamically, particularly when Heaviside's normally unaccounted huge energy component is accounted and utilized.

In our opinion, Mills' theory should probably be recast into a higher group symmetry electrodynamics — such as O(3) — which has been shown to be intimately connected with Sachs's unified field theory. This would provide an adjusted model that is not only testable but also *engineerable.* Nonetheless, the concepts of Mills' theory and the theory should be closely examined as they stand, and at least some of the key concepts are engineerable as witnessed by his successful experimental results. That is better than what the critics have offered! A higher group symmetry recasting would enhance and expand his theory even more, and correct any errors that might be present. It would also allow a full theoretic treatment (i.e., a supersystem treatment) of Mills' main concepts, which we believe have much merit.

Further, given Mills' hydrino as we approached it, two hydrinos will each possess such a set of spacetime curvatures (each will possess such a *vacuum engine).* Later in this book — and elsewhere {401} — we have pointed out that, in a time-reversal zone (TRZ), the law of electromagnetic charge attraction and repulsion is reversed. Accordingly, in a TRZ two or more hydrinos will attract each other so closely that each enters the now-reduced strong force region of the other, forming a quasi-nucleus. As the TRZ decays away back to a normal time-forward zone, because of their power law form the strong forces restore back to normal much faster than the electromagnetic forces do. Hence during its "decay", the quasi-nucleus is energetically compacted into a permanent nucleus, either flipping quarks or giving off one or more particles as necessary to balance its new energy state in the process. We have previously argued that a similar process where a TRZ induces formation of quasi-nuclei also yields the major transmutations {402} demonstrated in a large number of cold fusion experiments worldwide.

The present author has previously proposed an engineerable mechanism (the totality of all photon interactions with a mass) that generates the flow of that mass through time {403}. By manipulating the arrow of time between forward vector and reversed vector, the strong forces in a nucleus (or for a particle) can be directly manipulated in magnitude (and to some extent, even in sign although the latter involves gluon and quark manipulations in the nucleons). By adroit use of these manipulated strong forces and TRZ formation and decay, the energy states of nuclei can indeed be manipulated, including reduced in energy level —just as Mills assumes and presents experimental evidence for, and as cold fusion experiments present experimental evidence for.

We note that two such interacting hydrinos must each possess a specific vacuum engine (specific set of ST curvatures and dynamics). Novel new interactions are available in TRZ's because of manipulation and even reversal of electromagnetic forces, strong forces, etc. and because of nuclear fusion of like charged particles into quasi-nuclei followed by decay into stable nuclei, etc. These novel new particle interactions caused by manipulation of strong spacetime curvature engines and their magnitudes are presently missing from particle physics. Mills, however, does come at them from a somewhat different direction in his own concepts.

The reason for the absence of dominant general relativity effects in most particle physics is that the "total photon interaction" mechanism generating the flow (persistence) of a mass or field through time has not been recognized and used. Consequently, in general only those far weaker ST curvatures due to the weak G-force have been considered. To Mills' great credit, he is aware of the gravitational significance of manipulating much stronger forces and spatial energy densities such as the electromagnetic fields and their energy densities.

The U.S. Patent and Trademark Office then refused a new patent to Mills on one of his processes, and revoked another Mills patent even after already agreeing to award it within two weeks. BlackLight Power, Inc. initiated and lost a lawsuit against the Commissioner of Patents, seeking to reverse this unusual action by the U.S. Patent Office. However, the company's patent portfolio has continued to grow, with extraordinary international applications {404a, 404b}, and several European patents have been filed appropriately. BlackLight Power Inc. seems well funded (some millions of dollars) and well staffed, and we expect to see BlackLight Power, Inc. products entering the market place. Those products will probably be related to fuel cells, plasmas, power converters, generators, separation methods, and novel compounds materials.

and

6.3.6 Switching Circuits with Extended Electron Gas Relaxation Time

See Figure 6-16. Suppose an instantly applied voltage to the high side of the circuit instantly potentializes a pair of circuit conductors, with the other acting as ground. The charges in the conductor are thus instantly potentialized and excited, so that through the external circuit there exists an E-field E, where $\mathbf{E} = -\nabla\phi$ between the high side of the circuit and the ground return side. An acceleration force on the energized electrons thus exists. It requires a finite time for the energized electrons in this force field E to break their static friction or inertia, move, and accelerate to the requisite slow drift velocity down the wire. During that delay or "electron relaxation time", no current is initially in progress, then a little current is flowing, and finally all of the current is flowing. This delay time is called the electron gas relaxation time.



Note: May use many strands of Fe-doped Al wire instead of one, for each conductor

Figure 6-16 Extended-relaxation-time circuit with diodes.

In the usual copper conductor, the delay time arguably may be on the order of 10^{-16} sec. This is so slight a delay that it can be ignored, for all practical purposes. Current — with resulting dissipation of the collected potential energy — usually occurs "as soon as" we apply the voltage, for all practical circuit work. However, suppose we could increase that electron gas relaxation time to, say, one millisecond? Then for an appreciable number of microseconds, there would be essentially no current flowing at all in the now-potentialized circuit.

We previously proposed a mechanism whereby a degenerate semiconductor alloy (say, of a tiny bit — perhaps 2% or so — of iron alloyed in aluminum wire) is utilized for the conductors of the external circuit. This should give a vastly extended electron relaxation time, somewhere on the order of a millisecond. By obtaining a millisecond, one can excite the circuit with current-free potential alone, which becomes pure regauging during the electron relaxation period.

We strongly point out that this is an asymmetrical regauging; the E-field previously mentioned is present, but the electrons are still frozen in the circuit since their relaxation has not begun. The gauge freedom principle, recognized in quantum field theory, assures us that we do not have to perform work to simply inflow potential energy to change the potential energy of the system. In real circuits, we may have to pay a tiny bit for switching to connect and disconnect the external potentialization source, but we can be at pains to make that very efficient and minimal {405}. The point is, other than minor switching costs, the dramatic change in the potential energy of the system is cost-free and no current is drawn from the external potential source. Hence — in the language of the electrical engineer — we draw no power from the source of potential, during this potentialization time.

Suppose we switch away the excitation source prior to its decay while the electrons are still frozen. Simultaneously, we complete the "freed" potentialized circuit with a strategically placed diode, as shown in Figure 6-16. Again, we pay a little switching cost, but it can be minimized. The electrons in the *now asymmetrically potentialized circuit* are still frozen, so no power has yet been drawn by the system from the external power supply furnishing the voltage only. In this way, pure asymmetrical regauging is used to excite the circuit with additional potential energy, without requiring work (except minimally for switching).

A little more time passes, and suddenly the electrons in the potentialized circuit wake up and move. We stress again that the full emf is acting on the electrons, and now they are finally free to move. There is a net nonzero regauging E-field (force field) also. The excited closed current loop circuit then discharges in normal Lorentz symmetrical fashion, killing the source dipolarity as current is driven back up through the diode, but all the work in the load is "free". The circuit specialist will also recognize the usefulness of additional components associated with the shunt, such as a capacitor or even an LC oscillator for AC work.

If L*E* is load work obtained and *SE* is switch energy utilized, this approach yields COP = *LE / SE* and COP > 1.0 is possible. The reason is that the *primary* source dipole providing the potential for potentialization of the electrons and regauging of the circuit is removed from the closed current loop circuit and the effect of current through the back emf. Thus the primary source dipole is not destroyed faster than the load is powered. It is only depleted by the small amount of switching energy we utilized. This appears to be a major way to avoid the COP<1.0 limitation of the usual closed current loop circuit.

This is a circuit with legitimate COP>1.0 capability, without violation of the laws of thermodynamics or physics. We break the Lorentz condition between the initial "external circuit" and the primary source dipole for the regauging energy. After regauging, we "cut loose" the circuit with its own primary dipolarity and newly transferred "separate source dipole". *By such adroit use of electron gas relaxation time, we can use one source dipole to freely make another of equal intensity, without any depletion of the first.*

The difficulty is in getting the Fe-Al alloy wire, which must be made in an inert atmosphere since Al corrodes easily and the two elements have very different melting temperatures.

Alternatives can be visualized, such as to utilize a capacitor whose plates are made of the Fe-Al alloy. This might be useful in the triode-capacitor, to be discussed next. A series of pulses might then be used to charge the capacitor, without depletion of the primary source dipole in the external source of potential, if it is repeatedly switched in and away. An interesting question arises if such a capacitor with tailored "hysteresis" in its charging is utilized in various circuits and schemes containing a coil of useful time delay also, particularly since the electron gas relaxation phenomenon involves decaying oscillations. Interesting phase angle results can be constructed in such circuits, but we leave the resolution of this question to future experimenters.

6.3.7 The Triode-Capacitor and Other Curious Components

See Figure 6-17. In this rough concept by the present author, the notion is to implant a grid of very small copper wire mesh inside the dielectric and near one or both of the capacitor plates, and then to utilize grids as if they were grids of a triode tube, for gating and controlling the displacement current in the capacitor and the dielectric strain. As an example, when charging the capacitor, the grids can be used to increase the displacement current (which also increases the voltage on the capacitor and dielectric strain). This increases the charge and energy in the charged capacitor, without putting in as much "enhancement and gating" energy as the extra energy obtained in the charged capacitor. If desired, we can also incorporate the 2% Fe-doped Al wires in the grid, or connected to it, to further move the grid toward a "pure current-free potential" operation.



Figure 6-17 The triode-capacitor concept.

The scheme is that a voltage on this grid will intercept only a small current during charging of the capacitor, but can have an appreciable voltage upon it. The charging potential is placed across the capacitor, and simultaneously the grid has a similar potential placed upon it. The external source of charging potential is then disconnected, and the capacitor charges with more energy rearranged in its circuit than the energy one dissipates in the grid. The similarity to an old vacuum tube triode is apparent. For the purist, additional grids with tetrode and pentode functions can also be added.

One or more inventors has unwittingly tried to approach this in one way or another, but have not directly incorporated this schema and have not used the grid. They do not seem to have obtained positive results with those different schemas without the grid, nor have they specified the difficulties and phenomenology encountered, etc. We were curious about possible results of combining this (the triode grid in the capacitor) with the known elimination of capacitor losses by appropriate pulse charging {406a-b}. It seems that experimentation and research with the triode capacitor and its variations is definitely indicated.

We were also curious about the Davis non-inductive resistor {407a}, which is a special kind of "capacitor" that becomes an inductance-free resistor. One may argue that the resistor may be multiply inductive after all, though it is *net* noninductive. It may well be "equally and oppositely inductive," which is quite a different thing altogether, since it produces an artificial stress potential (and in the presence of AC, it produces a longitudinal EM stress field wave) in spacetime even though it produces a *net* zero reactance. In short, it produces a Lorentz-regauging, directly, and this can be a varying Lorentz regauging producing longitudinal EM stress waves. Whether this odd characteristic can be utilized in a COP>1.0 process remains to be seen. Preliminary indications are that it can be so utilized.

The various versions of the biwound coil, wound with two conductors at once and then the currents passed through the conductors in opposite directions, also presents interesting capabilities. Here again, it is multiply inductive, but may be tuned and adjusted to be *net* noninductive. We strongly suggest comparison with the well-known hairpin dual dipole antenna.

In short, this biwound coil arrangement — with various variations — can produce (and modulate) a magnetostatic scalar stress potential in the local vacuum and, in the case of AC, a longitudinal EM wave. This would appear to be a direct change (and oscillation) of the stress potential of the vacuum itself, which can be decomposed via the Whittaker process into a harmonic set of phase conjugate longitudinal EM wavepairs. The potential longitudinal EM wave communication possibilities can be seen, although one might require a Fogal transistor to receive the longitudinal EM wave modulations of such signals.

Further work in this area of unusual capacitors and components is left to the interested reader for his or her experimentation and research.

6.3.8 A Surprising Thing About Thermodynamics and Reservoirs

Thermodynamically, it is fashionable to state that one cannot take energy from a reservoir at constant temperature. That is true for *equilibrium* conditions, but not for *nonequilibrium* conditions {408}. That is, we cannot take energy from a reservoir *in equilibrium* at constant temperature. We can indeed take energy from a reservoir at constant temperature *but not in equilibrium.* More exactly, we can take energy from a nonhomogeneous reservoir at constant temperature.

We quote Hsu-Chieh Yeh {409} for a vivid statement of this little-recognized fact:

> *"From Planck's statement of the second law of thermodynamics it is generally inferred that it is impossible to construct an engine which produces work at the expense only of heat taken*

> *from the air or the ocean. ...[It is demonstrated that]... when the air and the ocean are combined as a nonhomogeneous reservoir of uniform temperature, it is possible to construct an engine which produces work by extracting heat from the said reservoir. This does not constitute a violation of the second law of thermodynamics, rather that the "reservoir" in the Planck's statement must be clearly stated as being in equilibrium. "*

Yeh's article falsifies the general, mistaken inference that Planck's statement of the second law of thermodynamics requires it to be impossible to construct an engine that produces work at the expense only of heat taken from the air or ocean. The experiment described in Yeh's paper demonstrates that when the air and the ocean are combined as a nonhomogeneous reservoir of uniform temperature, it is possible to construct an engine that produces work by extracting heat from the said reservoir. This does not constitute a violation of the second law of thermodynamics, but rather shows that the "reservoir" in Planck's statement may be in equilibrium or disequilibrium, and the statement holds only for the equilibrium case. Also, an entire reservoir can be in "overall" equilibrium, but in raging disequilibrium between various parts of itself. Classical thermodynamics only applies with the reservoir or part of it that is used by the system in its supersystem, when that part is in equilibrium.

We bring this out to show the analogy to our concept of the two additional components of the supersystem as the "reservoir" or external environment of the system itself.

We also point out that the concept of temperature itself is not strictly defined under disequilibrium conditions, as pointed out by Gabriel Laufer {410}.

The proof and a schematic diagram of a machine to do just such an energy extraction process at constant temperature in an environment in disequilibrium are shown by Yeh {408}.

6.J.9 Latent Heat Work of the Correas

In addition to their glow discharge work previously discussed, Paulo and Alexandra Correa have demonstrated a method to optimize some anomalous form of energy from the sun, which transduces into heat, producing an anomalous T_0 - T difference registered in Orgone Accumulators[178] invented by W. Reich in 1939-1940. They have also employed the optimized difference in this "latent" heat — their term — to drive a low dT Stirling engine of the MM6 type, to perform free work {41 la-b}. The Correas employ their own new theory of the aether {412} to explain the effect.

---

[178] **This** is Reich's terminology, not used in conventional physics. We suspect that **proper** application of quantum field theory with its four photon polarizations could

Against the assertion that this is just normal solar energy warming, they have demonstrated the successful driving of the Stirling engine for several hours during nighttime {413}. With their latest improved version, they report speeds of the Stirling engine of 150 rpm during daytime (with dT values reaching 22.5° C), and speeds of 30 to 80 rpm during nighttime (with dT values of 3.1 to 9° C). There appears to be no obvious standard thermodynamic explanation or standard theory to explain how the anomalous heating occurs — although once it does occur, the explanation from then on is thermodynamically normal.

The Stirling energy is driven on a difference in temperature created between the top plate and bottom plate of a box by this anomalous energy. It is the production of the heat that is anomalous, not the driving of the engine. For comparison, imagine a bank of solar cells that would somehow operate at night, when no normal radiation from the sun was striking them. The Correa effect demonstrates such an anomaly.[179]

Dr. Eugene Mallove, an excellent scientist with impeccable credentials, has personally observed the Correa accumulator system driving the Stirling engine, and has examined it inside and out {414}. Though small, the heat and the motive power are real and the engine is really driven, in the absence of any kind of conventional batteries or other known power source.

---

be applied to transform the notion of "orgone" energy into specialized EM energy. We further suspect that orgone energy is really the transduction of the time-polarized photon energy into normal photon energy. We are assured by quantum field theory and the giant negentropy solution to the source charge problem that the instantaneous scalar potential involves this process.

[179] We point out that local regions of the sun may well produce Aharonov-Bohm effects, and probably do. Such reactions in the sun would localize some of the B-fields and emit curl-free magnetic vector potential radiation into space, striking the earth. Close examination and analysis of the possible reaction of uncurled A-potential radiation with the accumulator box and plates in the Correa process might yield a novel mechanism for the observed heating (scattering) effects, including the difference between daytime and nighttime levels, periodic variations, etc.

While the Correas utilize some of Reich's orgone and aether terminology, they are quite aware that the energy being converted is not normal transverse EM wave energy. Quoting {415}:

> *"Aetherometry demonstrates that what traverses space is not transverse electromagnetic radiation (and certainly not sensible heat), but longitudinal electric ambipolar radiation emitted from the sun. All that electromagnetic radiation consists of is a local production of photons (for those who care to listen): aether energy is not composed of photons, actual or virtual."*

We can generate sympathy for that statement, although we would still not rule out time-polarized (scalar) photons and longitudinal photons from quantum field theory, each of which is individually nonobservable, but when paired the two comprise an instantaneous scalar potential. As we previously discussed, the classical notion of the EM force fields E and B implicitly assumes interaction of the unseen causal "field-as-it-exists-in-massfree space" with charged mass having been accomplished, with the E and B being the 3-effect of this interaction after observation. Thus these force fields E and B are 3-effects (after interaction and after observation) rather than 4-causes prior to interaction and observation. We suspect that the Correas are trying to get at the causal 4-photon, rather than the usually assumed 3-photon. Further, a virtual photon spends much of its time existing as a dipole comprised of a virtual electron and a virtual positron. Therefore it spends much of its time in the presence of the giant negentropy 4-circulation, involving transduction of time energy into spatial energy and vice versa. It is this negentropy circulation represented by the virtual photon (or accompanying it, whichever one chooses) that the Correas are confronting as the "aether energy".

As previously discussed, an analysis of the Drude electrons in the electron gas of a detector builds a convincing case for EM waves in space existing in longitudinal EM waves, *if the spinning and longitudinally restrained electrons precess and act as gyros.* The detected transverse EM waves are in fact transverse precession waves of the gyro-electrons when perturbed by incoming longitudinal EM waves (longitudinal photons appearing in 3-space from the time-domain's scalar photon couplet). As Feynman put it {416},

> *"We may think of E(x, y, z, t) and B(x, y, z, t) as giving the forces that would be experienced at the time t by a charge located at (x, y, z), with the condition that placing the*

> *charge there did not disturb the positions or motion of all the other charges responsible for the fields."*

The E and B force fields — and transverse photons — are not the form in which EM energy *causally* exists in 4-space prior to its interaction with charged mass. In that causal form, EM energy seems to exist in field-free form, as a direct curvature of spacetime — at least in Sachs's unified field approach. Further, this form may be represented as the causal precursor of longitudinal EM waves accompanied by time-polarized EM waves.

We will not repeat our past discussion of the great necessity to change the very notion of "propagation through 3-space", but that is the issue. In our opinion, the Correas have had to struggle with the use of this causal EM energy as it exists in 4-space prior to interaction with charge and prior to observation. Hence their view is solidly based that the photon does not exist until after the interaction — which in fact has much support once we remove the still-present assumption in classical electrodynamics that a material ether exists.

Our own recommendation is that this anomalous energy should be deeply investigated with the view that all EM energy in 3-space comes from the time-domain and the 3-space aspect is in terms of longitudinal photons, as we have proposed in our solution to the source charge problem previously cited. That is the only way that the nature of the EM wave in vacuum can be reconciled with quantum field theory's findings {19} and with Whittaker's decomposition of the scalar potential {85}, slightly corrected {12}.

Mallove also points out {417} that, if this aether energy view of the Correas has validity, it *"...suggests that physics is not just wrong, it is profoundly wrong — catastrophically wrong about even the most fundamental questions of existence, such as: 1) Is there an energetic aether? and 2) What is the nature of light?"*

We profoundly agree with Mallove's observation, and we believe we have explained the reason why physics is indeed profoundly wrong (widely substitutes effect for cause). Further, classical physics is decidedly wrong about the nature of light — from quantum field theory, experimental proof of superluminal communication, and action-at-a-distance effects.

In our view, the Correas presently have a replicable experiment that, once independently and thoroughly investigated, may force a deeper examination of the foundations of physics. Hopefully, the Correas' experiment and others like it will finally force the separation of effect from cause, presently so mangled in physics and particularly in electrodynamics.

If the National Academy of Sciences and the National Science Foundation can be convinced of the horrible manglement of cause and effect in physics and especially in electrodynamics, perhaps they may yet wake from their long slumber and get the foundations corrected to eliminate such non sequiturs. If so, we shall have a magnificent new physics as a result.

If not, then the NAS and NSF will continue to profoundly reduce the security of this nation, since several nations have already made and weaponized such corrections to physics to produce what is called "energetics". Further, extraordinarily powerful energetics weapons have **already** been developed and deployed (and even employed), putting the U.S. at a strategic disadvantage because of the continuing reluctance of the NAS and NSF to correct the glaring and extraordinary errors in both physics and electrodynamics — and especially in electrical engineering.

Meanwhile, we believe that the work and experiments of Paulo and Alexandra Correa are at the forefront of capturing and transducing energy from the vacuum, in whatever form one chooses to consider the vacuum energy itself. They are also pointing the way to the corrections and changes necessary in the "old physics" if we are to better understand the world we live in.

6.3.10 Swiss Overunity Converter

We must also include the "Testatika" devices invented by Paul Baumann in **a** religious commune, Methernitha, adjacent to the village of Linden in Switzerland[180]. Figure 6-18 shows one of the machines, which over a period of 20 years were developed in various output sizes up to 30 kilowatts. Once started, the device is self-powering while also powering a very substantial external load (up to 25 kW). Many engineers and scientists have observed the machines in observation, examined them, and measured one or more in operation, so there is little doubt of their **authenticity.**

[180] The website for Methernitha is www.methernitha.com. One may read the statements of the religious group for oneself.



Figure 6-18 Swiss Methemitha machine.

However, there the science stops and mysticism and speculation begin. The religious commune releases no real details, except deliberately tantalizing clues. When questioned, the reply is that humankind in its present state cannot be trusted with such free energy. Almost all those examining the device have thought in ordinary electrical engineering terms, so very little comes from their examination because standard electrical engineering does not contain any theoretical explanation of COP>1.0 electrical power systems whatsoever. Baumann himself sometimes cryptically replied that his study of lightning discharges in nature gave him the operational principle. As we shall see, that may indeed be a very substantial clue as to the possible technical COP>1.0 mechanism, and one that does not exist in conventional classical electrodynamics.

The Methernitha (Baumann) machine resembles a Wimhurst machine with contra rotating static wheels, made of plastic or other insulating material with copper ribs and structures on one side and aluminum on the other. Use is made of the discharge into and from large capacitors and large coils. Also, at least one horseshoe-shaped permanent magnet assembly at the bottom is utilized. The major operating feature seems to be the contra rotating disks of a "Wimhurst" static generator machine, a magnetic field at right angles, and the sharp discharge of high voltage into and from large capacitors and large coils. The voluminous material on the Internet and in articles about the machines is mostly of little real use in contributing understanding or in proposing any legitimate mechanism.

We have not "solved" the machine's mechanism, since that would require close study of the device for a protracted time, and there has been no opportunity or time for that — although Baumann invited this author to come and see the machine some years before he died. Regrettably, I was unable to make the trip, and Baumann himself has now been dead for some years. We will therefore offer some technical suggestions pertaining to mechanisms that may be operating in the machine (or others like it).

First, we call attention to a paper by Aguirregabiria {418}. Quoting:

> *"An ohmic ring that rotates with constant angular velocity in an external uniform magnetic field is considered as a simple model for a current generator. Under the assumption that all quantities vary slowly in time, the lowest-order approximation to the surface charge density is found. The flux of the Poynting vector through the loop surface is also computed. Unlike the examples that are given in textbooks, this flux is not always incoming: It has the outgoing direction around the loop parts where the electrons are moving against electrostatic forces."*

In other words, contrary to textbooks, there are positions where such a ring produces currents in one direction, and positions where it produces current in the other direction — *in fact moving against the voltage and E-field, and thus serving as a true negative resistor in those latter regions.* This may be a profound clue to the negative resistor operation of Baumann's machine.

This unexpected negative resistor effect is in theory usable to provide a true negative resistance. If there are transformers in the machine (and there are in some of them at least), then if a true negative resistor were used as an external shunt across the external circuit connected to the secondary of a transformer, the transformer could be operated as a true COP>1.0 device. The back-field connection from secondary to primary would be reduced by the fraction of the return current to the secondary that is shunted in parallel to that current "pumped" back up through the secondary.

This should be considered as an important possibility in the Baumann machine's operation.

Second, a charging and discharging capacitor involves not only energy flow in a direction perpendicular to the plates, but also an energy flow in a direction parallel to the plates {419}. Each of the rotating "plates" is actually a rotating capacitor of sorts, with a dielectric between two plates of special construction and dissimilar metals. The dielectric and the plates thus involve a complex intermingling of the negative resistor effect, a positive resistor effect, magnetic energy flows (both in entropic and negentropic manner in various regions), etc.

Baumann once handed two dissimilar plates, with a dielectric between them, to an engineer who measured it and found a startling several hundred volts across the plates! To date, no one is known to have been able to reproduce that effect.[181] We suggest that, if the dielectric material is layered and photorefractive in nature, it may be related to the negative resistors built by Chung {420}. If so, the physical pressure of the plates against the layered dielectric may also be quite important. By varying this pressure, Chung and her team found that their device could be made to exhibit negative resistance, positive resistance, or zero resistance. This leads us to speculate that Baumann may have used a "stressed dielectric" capacitor as a device having a built-in negative resistance. In that case, build-up of such a surprisingly high voltage would indicate high stress locked into the negative resistance dielectric.

We also call attention to a paper by LaPointe {421}, which will be discussed later under inertial propulsion and antigravity. Essentially, true Dirac hole current in the adjacent vacuum/space can be generated by powerful electrical discharges, particularly from capacitors or coils. When the unaccounted Heaviside energy component is also considered as well as the Poynting component, LaPointe's despair at the difficulty of obtaining sufficiently large voltage gradient across a very tiny distance is dispelled.

---

[181] We are reminded, however, of the peculiar phenomenon that can occur in large power capacitors stored on a warehouse floor. If their leads are not shorted, the capacitors will build up a self-charge gradually, and this can become quite lethal. For that reason, such large capacitors when stored will have their leads shorted, to prevent this "free cumulative charge and energy" from appearing and posing a serious hazard. To our knowledge, there has been no complete scientific explanation advanced for this "self-charging" effect in large storage capacitors. Our own hypothesis is that it is probably an effect of unaccounted Heaviside nondiverged energy flow components associated with various field/charge interactions in the area and with ordinary Poynting EM energy flow in the area, including within the earth itself. Further, with respect to the surface of the earth there is an increase in potential with altitude. Hence from any point above the earth's surface and a point on the surface, there exists a dipolarity and a "Kron open path". The broken symmetry of that dipolarity means that within it a continuous 4-circulation of EM energy flow occurs as well as point-dipole polarization.

If this speculation holds, then in examining lightning strikes and their more bizarre phenomena, Baumann may well have hit upon the fact that such discharges also generate negative energy as well as positive energy, although it appears that the technical concept of negative energy was foreign to him, at least in such terms. In short, he could have been unknowingly charging his large capacitors by Dirac sea hole currents, somewhat similar to Bedini's process.[182] In that case, most of the "negative resistance" operation could be explained by Baumann's transduction of large bursts of negative energy into large bursts of positive charging energy and current in his capacitors.

Or, said another way in terms of Aguirregabiria's effect, Baumann may simply have been charging capacitors in that "negative resistance" Aguirregabiria region where the current does flow backwards against the voltage.

At least we have proposed some known though rare phenomena, which Bedini and my four colleagues and I have discovered in independent efforts. We strongly suggest that the Baumann device may unwittingly incorporate several of these mechanisms, but that neither Baumann nor the other members of Methernitha seem to have any technical notion of them.

With that, we leave it to the interested researcher to perform his or her independent Baumann-type system experiments and build-ups. Eventually, as is always true in science, the experiment must determine the truth of what is really happening. Given the successful experiment, then a model must be contrived or fitted that (i) explains the new effects produced, and (ii) complies with normal EM operation of normal COP<1.0 systems.

6.4 Some Magnetic Processes of Interest

There are some 200 or more magnetic effects in the literature, and only about half of them are well understood. Of the remaining half, some are partially understood and some are not understood at all. The COP>1.0 researcher interested in magnetic systems would do well to study magnetic materials science {422a-422c}, known magnetic effects, and particularly those magnetic effects that are still anomalous such as in leading edge superconductivity research. The new area of *spintronics* {423}, e.g., is rapidly advancing and will have future impact on COP>1.0 magnetic systems. We do not further discuss spintronics in this book, but merely call this rapidly emerging area to the attention of the interested COP>1.0 researcher.[183]

---

[182] Bedini and the present author have filed a patent application upon this exact mechanism and process, and typical embodiments for accomplishing it. Bedini discovered the effect and used it for two or more decades, and after some intense struggle with the problem I was able to find the exact technical mechanism, including literature justification. This becomes a system to close-loop a "unitary" type of COP>1.0 system, which is covered in the patent application also. A different system can be used to close-loop a non-unitary COP>1.0 system, and that method is contained in the second MEG-type patent application of my four colleagues and I who invented the motionless electromagnetic generator (MEG).

Let us examine a very few magnetic effects of interest, as a sampling of what we are referring to.

6.4.1 Self-Powered Magnetohydrodynamic Motors

Interesting self-powered magnetohydrodynamic motor work has been shown by Bednarek {424}. He shows a multi-branch rotor in a galvanic cell composed of sulphuric acid electrolyte with copper and zinc electrodes. The unit develops an emf of about 1 volt, with the rotor placed in a vertical magnetic field such as from a large rectangular permanent magnet, where the field of the magnet is a few teslas in strength. The electrolyte and the rotor revolve in opposite directions. To change the direction of revolution of the rotor, the magnetic field direction is reversed. A linear self-powered magnetohydrodynamic motor is also shown, and has a similar principle of operation.

The interesting point is that these motors work, but less efficiently, when a water solution of table salt is used as the electrolyte. With the worldwide availability of seawater, this becomes an interesting possibility of "renewable energy" application. We leave it to the reader to further investigate this proven experimental technology as desired and to determine its practicality.

6.4.2 Multivalued Magnetic Potential

Conventional system designers work with conservative fields, as shown in Figure 6-19. Conservative fields arise from a single-valued potential — a potential that has only one value at each point in 3-space that it occupies. Consider a rolling ball of mass *m* on the "oval track" shown in Figure 6-19, starting from point A and rolling on the right side path. With the ball at rest at point A, we give it a slight push to velocity V_i adding kinetic energy $K_i = 1/2\, m(V_i)^2$. At point A, the ball has its maximum potential energy P_A due to gravity.

---

[183] For technical information, see (a) Michael Ziese and Martin J. Thornton, Eds., *Spin Electronics,* Springer-Verlag, 2001; (b) D. D. Awschalon, N. Samarth, and D. Loss, Eds., *Semiconductor Spintronics and Quantum Computation,* Springer-Verlag, 2001.



Note The vertical distance above the horizontal base represents the magnitude of the scalar potential at the point where the vertical line is taken

A circular closed path in potential ϕ is given by A-B-C-B'-A
Line integral from A around any closed path back to A is conservative
Along path A-B-C, work W(1) may be extracted from rolling ball
Along path C-B'-A, must do work W(2) on ball, where W(2) = - W(1)

Figure 6-19 Conservative field use (single-valued potential).

As it moves to the right because of our push, the ball will accelerate due to the force of gravity and increase its kinetic energy until it reaches point C at the bottom, reaching its maximum linear velocity Vc and kinetic energy Kc at point C. Its change (PA - Pc) in potential energy at from point A to point C has been converted to kinetic energy $[\frac{1}{2} m(V_1)^2 + \frac{1}{2} mVg^2]$ at point C.

Continuing on around on the left half of the path, as the ball rises toward A again, the portion $(P_A - P_C) = \frac{1}{2} mVg^2$ —of the ball's kinetic energy at C that was added by the force of gravity from A to C — is returned to potential energy P_A. The ball reaches its lowest kinetic energy $\frac{1}{2} m(V_1)^2$ at A and also its lowest velocity V_1. For a perfect lossless system, once started in motion the ball would rotate around the track indefinitely, freely changing potential energy into kinetic energy and then back to potential energy. Nevertheless, it would not do any outside work, for that would represent losses or dissipations of energy from this conservative system. Consequently, the ball would quickly run down if work were being done, even if the system were otherwise "perfect".

If one integrates the change in potential energy around the track, the net change in potential energy is zero. The work done on the ball by increasing gravity to increase the ball's energy in one half-cycle, is taken back from the ball back when it climbs back out into decreasing gravity in the other half cycle. If one integrates the changes in kinetic energy around the track, once the initial velocity and kinetic energy are produced by outside forces in a perfect system, the net change in kinetic energy is zero. Of course, it is easily seen that the ball gains kinetic energy on its downward half of the track, and then returns the kinetic energy on its upward half of the track.

This situation is said to involve a *conservative fields* and the system will not produce any net energy to use as free work. Indeed, a real system will almost always have some friction and other losses around the path {425}, so the ball will gradually lose net initial energy given it, slow down, and eventually come to rest at point C, the lowest potential energy of the system.

(Multivalued magnetic scalar potential arises readily in magnetics)



(Asymmetrical self-regauging).

*Potential is multi-*valued here and freely regauges the system with excess potential energy. Ball is lifted by the free regauging.

Note: The vertical distance above the horizontal represents the magnitude of the scalar potential at the point where the vertical line is taken.

A circular closed path *in* potential ϕ *is given by A-B-C-B'-D-A.*
Potential ϕ is multi-valued from D to A.
Line integral from A around this closed path back to A is nonconservative.
Along entire path A-B-C-B'-D, work may be extracted.
No work is required to go from D to A. When ball arrives at D, it also
arrives at A simultaneously. I.e., the potential "jumps" in magnitude.

Figure 6-20 Field may be non-conservative for a multivalued potential.

A charge circulated through a closed current loop circuit also moves through a conservative field region in similar manner. Hence, there is no net excess energy input available for such a conventional circuit. It follows that one must arrange for inputting all the input energy (intercepted and collected by the circuit) that is then dissipated from the circuit's loads and losses. Unfortunately, half the collected circuit energy also goes to destroying the dipole, with less than half powering the load. Therefore, that circuit always exhibits COP<1.0.

Now see Figure 6-20, where we provide an analogy using a rolling ball around a circular track, in a gravitational potential. In this case, the potential has a multiple magnitude A and D at point A-D, which is the same point (we plot a point in the potential's magnitude, not a point in 3-space, although there can be close approximation).

Approaching magnitude D from point B', the value of the potential is steadily reducing and is much lower prior to reaching A-D than it was when leaving magnitude A. During this phase, the ball is gaining kinetic energy from the gravitational potential, and can be used to perform useful work (up to all the energy gained, in a perfect system). Upon passing through point A-D, instantly the ball is again at point A on the right. We accent that the "instantaneous jump" on the diagram represents a free insertion of excess energy (asymmetric regauging energy) from outside the system. Rigorously that is a broken symmetry, which also breaks the internal energy conservation of the system. In short, the "ball" has been instantly "lifted" (in this simplified analogy) back to a higher potential by a free insertion of excess energy from the external environment. The main point is that a surge of potential energy into the "ball system" occurred, freely input by nature and the environment. The system can now go through the "doing work" routine again, traversing from A back to D and through it.

Note that this is a nonconservative system, because it continually receives a free and sudden input of excess energy from its environment. So this system — because of its broken symmetry — can continually do work and keep on going.

Indeed, so long as that free energy input from the environment occurs without fail, this is a "self-powering" system, completely complying with **the** laws of physics and thermodynamics. It violates the equilibrium thermodynamics because the system is periodically not in equilibrium with its environment. Consequently, the system can exhibit those five magic functions we spoke about previously. It can exhibit (i) self-organizing (in this case, freely getting that little ball from low potential energy D back to high potential energy A), (ii) self-oscillation or self-rotation (the ball will continue to go around and around the loop, even doing a little work in the process), (iii) output more energy than the operator inputs (in this case, the operator is not inputting any energy at all, so the energy output is indeed more than the operator furnishes), (iv) power itself and its load simultaneously (all the energy is being input from the external environment at the insertion of excess energy at point D to move the ball **back** to position A), and (v) exhibit negentropy.

This is an analogy to a nonconservative field and a multi-valued potential. In the case where a potential has discontinuous values at a single point, with the value depending upon whether the detecting charge (the "ball", so to speak) is to the left or to the right of that point, one has a *multivalued potential*. This multivalued potential actually represents a change of potential energy in the system, freely occurring without operator input. In short, it is an asymmetrical self-regauging, violating Lorentz's symmetrical regauging condition.

Actually, multivalued *magnetic* potentials arise naturally in magnetics theory, but —foolishly, in our view — theoreticians do all in their power to minimize or eliminate their consideration {426a-k}. They consider such a nonlinear change as being embarrassing and troublesome, and to be gotten rid of at all costs! However, if deliberately used and optimized, rather than eliminated, incorporating a multivalued magnetic potential can provide a *nonconservative magnetic field* (analogous to the illustration), where $\oint \mathbf{F} \bullet \mathbf{ds} \neq 0$ around a rotary permanent magnet loop. The multivalued potential represents a broken symmetry that further produces a nonconservative field.[184] In theory, such use of the multivalued potential and the resulting nonconservative field can enable a "self-powering" permanent magnet rotary engine, operating as a negative resistor freely extracting and using magnetic energy from the broken symmetry in the system's energetic exchange with the active vacuum.

However, note that the multivalued potential represents a point of sharp "self-regauging asymmetrically" by the circuit, with the regauging potential energy coming from the external environment. It requires that some external process in the exchange between environment and system must be automatically invoked at the multiple-value point, so that there is a sharp and sudden entry of excess potential energy received by the circulating ball (or by the circulating charges in an electrical circuit, or by the circulating flux in a magnetic circuit).

One such means of evoking such a sudden surge of excess energy at a point, momentarily, is given by Lenz's law, as discussed in the magnetic Wankel engine. Another means is by Johnson's sudden evocation of the exchange force, which momentarily can produce a pulse of energy density even several hundred times as strong as the usual field energy at that point. For example, imagine that the ball in Figure 6-20 represents a magnetic rotor in a magnetic potential represented by the height of the ball above the dotted line base. The point (D-A) then represents the results of the system having suddenly injected an instantaneous exchange force at point D, to freely increase the potential and potential energy of the rotor system back to point A. The rotor is immediately lifted back at its starting potential energy situation at point A, freely, by this sudden and free evocation of the exchange force. We will briefly discuss the exchange force in our discussion of the Johnson engine.

---

[184] In physics, the appearance of a force and its subsequent action to perform work is nature's way of restoring symmetry to a situation where symmetry has been violated. As can be seen, the net force can be used to translate something (such as current) and do work, thereby dissipating the excess potential energy received from the broken symmetry condition.

6.4.3 Dromgoole Effect as an Example of a Novel Magnetic Effect

An example of a novel magnetic effect is the *Dromgoole effect* {427}. This is an interesting phenomenon where a voltage placed on a solenoid wrapped around a longitudinally magnetized iron wire may be increased up to 300 times in magnitude by twisting the wire through 90 degrees. If a scheme can be worked out whereby this dramatic increase in voltage potentializes and moves very substantial current, then perhaps the extra output can — at least momentarily — produce more output energy than the work required to twist the wire.[185] At least that could be a working hypothesis from which to launch experiments to see if it is possible.

The reason this may be possible is that any amount of energy W one wishes can in theory be collected from any finite potential intensity ϕ, according to the simple equation $W = \phi q$, where q is the collecting charge exposed to and interacting with the potential intensity ϕ. In the case of magnetics, q is analogous to the pole (magnetic charge), where the north pole is positive magnetic charge. The ϕ then becomes the magnetostatic scalar potential.

So if we can produce ϕ with only a little expenditure of energy, and then have that ϕ potentialize a very large amount of charge q, we can collect upon the charge q much more energy than what we ourselves expended. The ϕ produced is a change to the local vacuum potential, and hence the collection of energy W on charges q is actually a collection of EM energy from the local altered vacuum potential itself. Any potential we make becomes a change to the local vacuum potential, and hence a change to the local active vacuum. That does not seem to appear in electrical engineering, which model does not even incorporate modeling the active vacuum or its potential, much less a change to it.

---

[185] The scheme must prevent *at least an appreciable fraction* of the spent electrons- from the external circuit and load — from being forcibly rammed back up through the coil against its back EMF. Otherwise the Lorentz symmetry condition applies and the arrangement will not produce COP>1.0.

While we discuss a few interesting magnetic effects in this paper, there are many more. The interested researcher is referred to such easier sources as Burke {428} and Cullity {429}. For more complex scientific sources and explanations, other publications are available {430a-430r}. In addition, it is helpful if the researcher is aware of some of the foundations problems in physics and electromagnetics {431a-431e}. Our point is that there are more than 200 known effects in magnetics, and only about half of them are well understood. For the other half, the understanding ranges from "partially understood" to "not understood at all." The latter half of the magnetic effects provides a rich ground for investigation by researchers seeking an asymmetrical self-regauging mechanism.

The COP>1.0 researcher must be prepared for an extended self-education period, and appreciable study and work. Some research discipline is highly recommended, such as starting one's own database and rigorously maintaining it up to date with one's latest interests. For the experimenter, a good lab notebook, meticulously kept and regularly posted, is an absolute necessity. Reading and searching the scientific literature is also highly recommended. It is not as simple as applying the principles one learned in university or technical school. Those techniques and principles are involved, but at some point in the circuit they must also be violated. Else COP>1.0 systems would long ago have been developed and marketed by sharp young students, graduate students, and post-doctoral scientists.

6.4.4 Exchange Force and Johnson's Approach

Refer again to our discussion of conservative versus nonconservative fields, above.

If one wishes to build a self-powering rotary permanent magnet motor, obviously one must evoke a condition whereby $\int \mathbf{F} \bullet \mathbf{dl} \neq 0$ around a single full rotation of the rotor (and where F is the instantaneous magnetic force between stator and rotor). For permanent magnets without any external switching, etc., that condition can only arise if an excess force is freely triggered by changes occurring freely in the magnetic materials themselves.

Fortunately, magnetic materials are almost always highly nonlinear, and **so** such self-triggering opportunities abound. They can occur because there are a multiplicity of mechanisms (dozens and dozens) going on simultaneously in the materials of the magnets of both the rotor and the stator, and not just the standard polarity and field repulsion and attraction that electrical engineers use. These materials processes also involve direct and ongoing exchange of energy between the active vacuum and the local materials in the magnet.

The trick is to take one of these automatically ongoing processes that is already there and freely available but just not adroitly used, and deliberately evoke and enhance it to induce excess energy at the appropriate time, with a force in the appropriate direction. In simple terms, if you have eight more horses available to put into the harness to pull the load, and you only have two normal horses but wish to pull more load, then by all means you should hitch up and use at least one more additional horse, and take him from the six that are usually just standing by and not working at all. They may run back and forth a bit, while watching the others work, but that of itself contributes nothing.

One such additional force and free regauging mechanism always available is the exchange force, which can be checked in Feynman's three volumes of physics {433} and also in the reference by Cullity {429} previously **cited.** Good science dictionaries {432} also include helpful information. Reading the literature will add enormously to one' data base of effects and methods.

Howard Johnson's approach is to arrange highly nonlinear assemblies of geometrically asymmetrical magnets into complex configurations. At certain points in a magnetic field, these Johnson assemblies will trigger the sudden brief self-generation (actually a sudden release) *of exchange force* between stator and rotor. The exchange force is a known phenomenon {432, 433, 434}, though still not completely understood theoretically. It **can** be evoked asymmetrically by evoking electron-spin flipping, for example, which has led to the development of a new field of technology, **spintronics.** *Microscopically,* the exchange energy is much greater than the magnetic field energy, sometimes by a factor of 10^3 to 10^4 {435, 436}. *Macroscopically,* the resulting exchange energy can momentarily still be many times the magnitude of the ordinary magnetic field energy; e.g., by a factor of 200, which Johnson often achieves.

If **the** stimulated momentary exchange forces are oriented to always add to the thrust upon the rotor in the "powering rotation" direction, then the **multivalued** potential condition and $\int \mathbf{F} \bullet \mathbf{dl} \neq 0$ are met. In that case, self-powering is permitted, if enough of these exchange force triggerings occur so that the extra potential energy added to the rotor is sufficient to overcome the load and the losses being powered.

The self-triggering of each exchange force appearance produces an excess burst of force and energy[186] input into the system from its active supersystem environment. Thus, repeatedly the system is momentarily converted (in each exchange force burst) into an open system in disequilibrium in its energy exchange with its active environment, freely receiving excess energy from it. Because the exchange force "input energy burst" is short, multiple such "input bursts" must be used in a single rotation cycle so that the total energy input by all of them is significant.

In that case, COP>1.0 performance is permitted by the laws of physics, thermodynamics, and nature. Conservation of energy is not violated. Classical equilibrium thermodynamics with its infamous second law does not apply to the Johnson system, since the system is periodically an open system far from equilibrium and receiving excess energy from its active environmental exchange. *A priori* the Johnson system has increased its negentropy overall, and that negentropy (increased order or increased potential energy) can then be dissipated (disordered) to produce free shaft horsepower if the bursts of exchange force are properly coherent in direction and timing.

We diverge for a moment: As is well known, the equilibrium condition in a system is the condition of maximum entropy in the system; any disequilibrium condition reduces the entropy *a priori* because it is an excited state of the system containing additional potential energy. It is worth rigorously clarifying the infamous second law of thermodynamics. Quoting Lindsay and Margenau {437}:

> *"[The]...statement of the second law: (a) the entropy... is a variable of state, (b) Its value, for a closed system, can never decrease."*
>
> *... "Non-equilibrium conditions cannot be specified by variables of state, and their entropy cannot be computed. ...the condition of equilibrium is the condition of maximum entropy."*

---

[186] Technically speaking, the exchange force is not a magnetic field force, but a force that arises independently due to quantum mechanical considerations. Nonetheless, it is a real force arising in magnetic materials and affecting magnetic materials, as in permanent magnets.

In the first statement, the reader should note the assumption of a closed system in the first subparagraph, and the absolute requirement that the calculated entropy be a variable of state.

Also, the quotation can be falsified. Oddly, the "closed system" in classical thermodynamics is defined (illogically) as a system that does not exchange mass across its boundary, but may and often does exchange energy across it. We negate any absoluteness of that statement by Lindsay and Margenau by citing a counter example of a "closed" system with continuously increasing energy, fed by transfer of energy from the environment, and with no escape of the energy or very little escape of it. A specific example is a photon absorption by a mass particle. This system achieves increasing energy (order) as the process continues, hence achieves negentropy. This may be considered a fluctuation, of course, but it still places severe limitations on this law of thermodynamics and in fact negates any absoluteness of it. For such reasons, in this book we have redefined "closed system" as one that exchanges neither energy nor mass with its environment, and we recognize that there are no such systems in the universe. We have defined an "open system" as a system that exchanges either energy or mass or both across its boundary, so that we do not encounter the problem of the counter example cited. Further, general relativity requires an increase in the mass of any system that increases its potential energy, and a decrease in the mass of any system that decreases its potential energy. Hence energy exchange at all with the system, involves mass exchange since mass and energy are the same thing. The classical thermodynamic definition of a "closed system" has thus been falsified since 1915, with the definition becoming only an approximation rather than a generally valid definition.

In the second subparagraph of that first statement by Lindsay and Margenau, the reader should note that the closed-system assumption must be violated *a priori* if the entropy does decrease, and vice versa. If the system is broken into a set of subsystems, then the only way the entropy of the overall closed system to decrease is for one or more of the subsystems to be open (new definition!) and energy (order) to pass out of the system. Then an interesting thing emerges: For order (energy) to remain in the system as such, the subsystems taken as a whole must produce as much negentropy as they do entropy. Energy from an ordered subsystem can be emitted in disordered form, but then it has opened that subsystem and has entered the space between parts (subsystems) of the overall system. In other words, in a closed system, *any increase in entropy requires the subsystems to become open subsystems.* Again, the statement of this law of thermodynamics eats itself. To stay in the overall system, this scattered energy *outside the subsystems* must then interact totally with another part of the system, and so on. This introduces disorder to the succeeding parts that interact. Therefore, the second law of thermodynamics itself *internally* violates its own "closed system" assumption because, to operate at all, the law requires continuing interaction between the active local vacuum environments and the subsystem components. In short, it requires a very special kind of overall or average equilibrium in an unavoidable energy exchange between the local vacuum and all the parts of the system. The source charge problem already demonstrates the universal violation of the second law and the thermodynamic definition of "open system", but both classical electrodynamics and classical thermodynamics have ignored this source charge problem for more than a century. Our solution to it was published in 2000.

Quite simply, there is no such thing as a truly closed system in the first place. Kondepudi and Prigogine come close to this statement in the following quotation[187]:

> *'Anyway, equilibrum thermodynamics covers only a small fraction of our everyday experience. We now understand that we cannot describe Nature around us without an appeal to nonequilibrium situations. The biosphere is maintained in nonequilibrium through the flow of energy coming from the sun, and this flow is itself the result of the nonequilibrium situation of our present state in the universe."*

In short, all systems on the planet — and we ourselves — are immersed in a nonequilibrium state a priori. Rigorously there is no such thing as an absolute equilibrium state on the planet, except as an approximation.

Now consider a perfectly insulated system, so that no heat can pass from the system outside it. An interesting constraint then exists on those "open subsystems" producing disorder (entropy). Unless equal reordering occurs in the subsystem-to-subsystem reactions, then disordering (heat) grows a priori. But this is not observed to happen in well-insulated systems approximating our theoretically perfect example! Otherwise, the temperature of a well-insulated system would increase until system rupture and failure. And experimentally that does not happen.

---

[187] Dilip Kondepudi and Ilya Prigogine, *Modern Thermodynamics: From Heat Engines to Dissipative Structures,* Wiley, 1998, p. xii.

It follows that, to maintain the internal equilibrium between subsystems and a constant internal temperature, a negentropic process is clandestinely involved. We submit that this process is revealed in our discovery of giant negentropy of the negative charge, and what may be said to be the giant entropy of the positive charge — i.e., in the discovery of the common " 4-circulation" of energy surrounding a dipole from the time domain to the negative charge of a point dipole in 3-space (thereby entering 3-space once emitted by the negative charge), thence to the positive charge of the point dipole, and thence back to the time domain. For a single charge, the well-known vacuum polarization provides virtual charges of opposite sign, to convert the "isolated charge" into a set of composite dipoles, as previously explained.

The second law of classical thermodynamics, considered in a more modern light, appears to conceal hidden giant negentropy and hidden giant entropy, in the ongoing 4-circulation of EM energy in the supersystem. *It is not possible to eliminate the supersystem or the interchange between its parts; particle physics told us in 1957 that there is no equilibrium of any system without this ongoing exchange.* Any thermodynamics attempting to discard the supersystem exchange (which involved both mass and energy) is at best an approximation for special "reasonably well-behaved" situations.

If the entire system is not in net equilibrium with the external environment (i.e., if there exists disequilibrium between the separated parts of the supersystem), then classical thermodynamics does not *absolutely* apply to that system. The system is no longer *absolutely* describable by "variables of state".

Those objecting to COP>1.0 in an EM system on the grounds that it would violate the second law of thermodynamics (which already violates itself), would be well-advised to restudy the very notion of the second law and the thermodynamics definition of *open system.* Compare relativity's equating mass as energy. Then ponder the thermodynamics of open systems far from equilibrium with their active environment. Every system in the universe is open, and it has an ongoing exchange with its proven active environment (local active vacuum and curved spacetime). This exchange Includes and exchange with every particle in the system. As pointed out by Lee: [188]

---

[188] T. D. Lee, *Symmetries, Asymmetries, and the World of Particles,* U. Wash. Press, Seattle, 1988, p. 46-47.

> *"...symmetry implies conservation. Since our entire edifice of interactions is built on symmetry assumptions, there should be as a result a large number of conservation laws. The only trouble is that almost all of these conservation laws have been violated experimentally. "... "...this difficulty could be resolved by introducing a new element, the vacuum. Instead of saying that the symmetry of all matter is being violated, we suggest that all conservation laws must take both matter and vacuum into account. If we include matter together with vacuum, then an overall symmetry could be restored."*

The *system itself is* always in disequilibrium; only the supersystem can exhibit equilibrium. The second law of thermodynamics specifically does not and cannot apply to a system far from equilibrium, because of its implicit assumption of overall equilibrium without the active vacuum exchange. Also, a deeper balance is required between the hidden asymmetries existing between the subsystems and their local vacuum (and local spacetime curvature.

Indeed, *one cannot even calculate* the entropy for a system that — overall — is far from net equilibrium with its active environment. We quote Lindsay and Margenau even more strongly {438}:

> *"Equilibrium states are the only ones that are capable of explicit analysis in thermodynamics... "*

And again {439}:

> "... *variables of state have meaning only if they define an equilibrium state. Hence the quantity we are seeking will be meaningless unless it refers to equilibrium states. "*

While we are at it, let us also address a serious flaw in the first law of thermodynamics. We again use Lindsay and Margenau for a succinct statement of the First Law {440}:

> *"First law of thermodynamics. A complete statement of the first law comprises two assertions: (a) heat is a form of energy, (b) Energy is conserved. "*

All that really says is that energy is conserved. It does not state that it is conserved in an object. It states that, whether the system is in equilibrium or not, energy is conserved. If heat is taken as disordered energy, then it merely states that overall the energy is conserved, whether ordered or disordered with respect to some ordering criterion. It does not state that the disordering is conserved, and it does not state that disordering must increase or decrease. But *it does implicitly assume that all energy at some most basic level is ordered, else it cannot be energy (order).* So it assumes that, at higher levels, energy can be disordered (incoherent). However, at the underlying basic level, it is and remains perfectly ordered — else it could not remain "energy and could not be conserved. As an EM example, in so-called "heat", *every scattered photon retains its perfect order; it is only the photon ensemble that is "disordered".*

In short, each "basic piece" of energy is perfectly ordered, but the *ensemble* of the pieces may be disordered. Therefore, entropy applies only at a level higher than the basic energy quantum. Contrary to the assumptions of classical (macroscopic) thermodynamics, processes which directly engineer the basic energy quanta[189] — more exactly, the *action* quanta, consisting of *energy x time,* since energy cannot be "engineered" or changed in 3-space without also being engineered "in time" as well — are time-reversible. Hence they can be negentropic — simply because every observable system is "open" to, and in continuous energy exchange with, its active time environment (and also its active vacuum environment). Also, no system changes its spatial energy in any fashion, including ordering or disordering, without interacting with spacetime and spacetime curvature dynamics. It also changes its time-energy.

So in our view the notion of "disordering" and "disordering of energy" must be carefully reconsidered, as to exactly what is and is not being disordered, when the assumed "disordering" occurs, at what level it occurs, where and how the compensating reordering occurs, etc. We also point out that the simple discovery of giant negentropy {12} as the solution to the long-vexing source charge problem already removes the "absoluteness" of classical thermodynamics. Giant negentropy already violates the assumptions of classical thermodynamics at the elemental level in every physical system. Indeed, every charge in the universe already falsifies any "absoluteness" of the assumptions of classical thermodynamics.

This problem in the old classical thermodynamics has long been indirectly solved in particle physics, with the discovery of broken symmetry. As Lee states so clearly {441},

---

[189] Actually, energy is discretized, not quantized. Energy x time (i.e., *action)* is **quantized.**

> *"As we expand our observation, we extend our concepts. Thus the simple symmetries that once seemed self-evident are no longer taken for granted. Out of studies of different kinds of interactions we are learning that symmetry in nature is some complex mixture of changing plus into minus, running time backward and turning things inside out."*

We point out that a symmetry involves a conservation law, such as are stated in classical thermodynamics, and a broken symmetry involves a broken conservation law. So the discovery of broken symmetry in physics was a profound change affecting all physics, including the staid old classical thermodynamics. Lee further points out the new complexity of concepts {442} such as symmetry (which is behind every conservation law, including the first law of thermodynamics):

> *"At present, it appears that physical laws are not symmetrical with respect to C, P, T, CP, PT and C. Nevertheless, all indications are that the joint action of CPT (i.e., particle <-> antiparticle, right <-> left and past <-> future) remains a good symmetry."*

So unless the first law is stated in terms of modern CPT symmetry, it does not absolutely apply! Further, every charge is changing time-energy into spatial energy or vice versa. Yet there is nothing about time-energy and its transduction into spatial energy, or vice versa, in the present textbook statements of the thermodynamics. The term "heat" does not refer to the presence of energy at all, but to the scattering (disordering) and escape of energy.[190]

Considering heat as "energy of the system", or "heat energy" of the system, is a grand non sequitur. Rigorously, "heat" refers to the reduction of higher levels of ordering of energy, and since the gist of energy is ordering, reduction of ordering is the very antithesis of energy! "Heat energy" thus is an oxymoron. Before the "escape", there is no "heat energy" (ugh!) in the system at all. The energy is present in the system *not as disordering, but as ordering, a priori.* If it were in the system, it would not have escaped nor would it be escaping from the system. More energetic molecular motion, e.g., is actually more energetic ordering, simply at an excited state (of greater energy!).

---

[190] Think closely: We never take the temperature of a "system"! We take the temperature of the disordered energy (heat) leaving that system or its subsystems. We do measure the effect of the emitted disordered energy. But that has already left the system and is in the local vacuum (a second component of the supersystem). Thermodynamics might be usefully redone more exactly in terms of the supersystem. We leave that task to some budding young future thermodynamicists for a recommended doctoral thesis.

We stress again (and strongly advise the researcher to read) Romer's strong objection to the use of heat as a noun {443}, and we suggest that the entire subject of classical thermodynamics needs a thorough revision to tighten up its terminology, correct its definition of closed system, eliminate its conflict between the first and second laws, and remove its inappropriate consideration of heat as "energy". Otherwise, the presentation and general interpretation of thermodynamics itself will continue to be one of the great confusion factors one encounters in trying to think clearly about extracting EM energy from the active vacuum environment to produce and utilize **COP>** 1.0 systems.

Effectively a phase conjugation (time reversal) occurs on the leading edge. The rotor is attracted in; regauging occurs. The rotor is accelerated on out. Regauging injects free potential energy into the system, from the vacuum. The laws of physics are not violated since the system is an open system freely receiving excess energy from its environment.

The stator gate magnets are highly nonlinear and produce a multivalued magnetic potential. The rotor pole enters and experiences a sharp "jump" in the stator's magnetic potential, and reversal of its sign. The rotor pole is accelerated on through the gate and out of it.



Figure 6-21 Concept of operation of Johnson's patented magnetic gate.

Johnson's approach produces a peculiar kind of multivalued potential. One **part** is conservative and of magnetic energy in nature, and the other part is nonmagnetic, being direct exchange force and energy effects on the **participating** atomic nuclei arising from quantum mechanical considerations. Nonetheless, the net *hybrid* potential can be multivalued at various points around the stator, and that is all that is required for broken symmetry. If $\int \boldsymbol{F} \cdot \boldsymbol{dl} \neq 0$ around a closed path, regardless of which set of forces F represents, then that overall composite force field acting upon the rotor or object moving around the closed path is nonconservative. In that case, self-powering is permitted.

Figure 6-21 diagrammatically illustrates the operation of a nonconservative force-producing magnetic gate in Johnson's approach to a permanent magnet motor. As Johnson has shown, by using a multivalued hybrid potential (MVP) in his gates so that the resulting excess exchange force is properly oriented in direction and timing, a rotor magnet is attracted into a highly nonlinear stator gate region where the MVP is located. When it enters the MVP region where the exchange force is initiated, the rotor encounters a dramatic jump in the net potential with a change of polarity as the exchange force suddenly fires automatically. In turn, this produces a sudden accelerating tangential force in the region, usually against the prevailing magnetic force in the normal back mmf region!


Stored Energy
Pseudo Multivalued Potential (Dotted Line)
(Asymmetrical Self-Regauging) True Multivalued Potential (Solid Line)
Boost Signature of pseudo-MVP (as in Johnson's magnetic gate) attained by evoking exchange force reaction
ϕs
Drag Signature of Pseudo-MVP
0°
360°
720°
Pseudo MVP
Work Region
Regauge Region
Work Region
Regauge
True MVP
Work Region
Work Region
Regauge
Regauge
Rotor
Degrees of Rotation

Note Single regaugmg per notation shown Johnson uses multiple regaugings per rotation

Figure 6-22 Johnson's "refueling" a permanent magnet engine by asymmetrical self regauging. A multivalued potential is momentarily created by precisely evoking an exchange force reaction.

Johnson often confounds professors of electromagnetics by showing them that his special gate can produce attraction between like poles, with a north rotor pole being drawn into a north stator pole in that exchange force region. This can be understood by tracing the spin field flow patterns, but cannot be understood by simple "like poles repel and unlike poles attract". In short, Johnson knows he is adding a force completely different from the magnetic force the professors have in mind as the sole acting force. It is rather like pushing two like poles of two little magnets together. You can do it because an additional force — your mechanical force pushing them together — is acting and overcomes the normal repulsive force between the two poles.

The sudden exchange force burst produces a sudden accelerating tangential force in the normal deceleration (back mmf) region of the stator-rotor arrangement. In short, Johnson utilizes a deliberately evoked burst of exchange force to freely overcome most or much of the back mmf (back-drag) region. This in turn produces a net driving force around the rotor's complete rotation, because the overall field combination is nonconservative.

Rigorous force meter measurements taken at 0.01-second intervals prove that this occurs as the rotor enters and passes through Johnson's gate. The results of one such experiment are given in Figure 6-22.

Johnson thus uses highly nonlinear magnet assemblies of novel design to create a special kind of multivalued potential in his magnetic gate by adroitly evoking exchange forces — *extra quantum mechanical forces* in addition to the usual magnetic field forces. The MVP produces a sudden extra rotational force, backwards to the back-drag (back mmf) region of the stator-rotor magnet arrangement where the rotor magnet assembly is entering and passing through the conventionally repelling like-polarity situation. The result is that a net north rotor pole is seemingly attracted in[191] to the otherwise repelling stator north pole region, then accelerated out the other side by the normal magnetic repulsion.[192] Net drive force results, instead of a net zero force. Engineer Ken Moore, a close colleague of the present author, independently tested a Johnson gate and verified the net driving force effect {444} within the limits of our little laboratory.

---

[191] In reality it is "forced in" against the repulsive magnetic force, by a superior force of a different nature, suddenly evoked.

[192] I.e., as the exchange force dies, the forces now acting are the normal repulsive magnetic forces, but the rotor has moved to a position where now this repelling force accelerates the rotor in the "load powering" rotational direction. In other words, the observer sees a like pole suddenly "attracted" into a like polarity region, move partially through it, and then suddenly be accelerated out the other side. But the "attracting in" force and the "accelerating out" force accelerate the rotor in the load-powering rotational direction.

Technically, Johnson's apparatus asymmetrically and suddenly regauges its exchange forces in such a manner as to momentarily overpower the back mmf region of the engine's rotation, thus producing a net multivalued potential and a net accelerating force around the overall rotation loop. However, correlated distant effects in magnetic materials are known. If distant compensation does occur, then the closed-loop capability might conceivably be defeated, if the total compensation is sufficient to provide an $\int \mathbf{F} \bullet \mathbf{dl} = 0$ overall condition. Hence the research probably demands attention to maintaining both *local* asymmetry and *distant* asymmetry. If the distant correlation effects occur, only in that manner can an overall nonconservative field represented by $\int \mathbf{F} \bullet \mathbf{dl} \neq \mathbf{0}$ be maintained around a completely closed magnetic loop.

This may be the problem with which Johnson appears to have been struggling for so long. He did solve the problem once, and produced a self-rotating permanent magnet motor that the present author personally tested over a period of about 2 hours. During a two-hour test period, the motor apparatus was allowed to self-rotate for up to 15 minutes at a time. Shortly after it became known that Johnson had successfully produced such a prototype, his laboratory was mysteriously broken into. The only thing taken was the magnet assemblies on that specific little successful demonstrator — in a laboratory with more than a hundred thousand dollars worth of magnets and magnetic assemblies of many kinds present.

As a personal aside, I have been associated with Johnson, off and on, for many years. He is a man of the highest integrity and an indefatigable researcher. It is my fervent hope that Johnson will succeed in his permanent magnet rotary motor project. All I can say as this goes to press, is that he is getting very close again, now that he has help and good machining accuracy, etc. for higher precision buildups. In the near future, I hope to be among the first to drink a good glass of champagne to celebrate his success.

6.4.5 Radus Effect: Magnets with Preferred Flux Path Memory

In the early NASA space program, magnetic boots for holding the astronaut to the skin of the space vehicle when outside it were required. A Westinghouse engineer named Raymond J. Radus had found that a permanent magnet applied to a dual flux path (Figure 6-23) would "remember" the flux path taken initially, until switched to the other flux path in an initial condition, after which it would remember that path as preferable {445a-445c}. A permanent magnet with such "memory" will split its flux in two parallel flux paths by some ratio, e.g., 20% in the non-preferred path and 80% in the preferred path. This preference can be switched at will by proper manipulation. So Radus developed switchable magnetic astronaut boots for the space program, using his magnetic memory and flux path switching technique {446}.


A
B
D
N
S
Attracted
Little or no attraction for anything else
Flux path
C
Permanent magnet
A
B
D
Little or no attraction for anything else
N
S
Attracted
Permanent magnet
C
Flux path

Figure 6-23A.
Once the magnetic circuit is made, there is little attraction for anything else

Figure 6-23B.
A single pulse through a coil can reverse ttie direction of the flux path

Figure 6-23 One example of the Radus effect.

The Radus circuit differs from ordinary permanent magnet circuits in three ways: (i) It exerts strong magnetic force at one end while exerting hardly any at the other, (ii) the strong and weak magnetic poles can be switched end-for-end easily and at will, thus, in effect, turning the magnetism on and off at one given side of the circuit, and (iii) once switched, it remembers its direction of greatest magnetic pull indefinitely.

The original Radus boots were excellent. For the acceptance tests, an engineer clad as an astronaut walked across the bottom of a steel beam in a high bay research area, upside down against the pull of Earth's gravity (Figure 6-24). He *stepped as* he walked, putting his foot "down" and then picking it "up" {447}.

There is no problem in finding modern magnets strong enough to hold the astronaut firmly in such an upside position. The problem with simple magnetic boots using such strong magnets is that, once the foot is planted, the astronaut cannot pick up the foot again. Consequently, the best the astronaut can do with such magnetic boots is walk rather laboriously by "scooting" the foot forward, with the boot remaining in contact and the astronaut unable to pick it up.



Engineer *walked* upside down on the underside of a steel beam in a high-bay area, wearing the Radus boots He used a stepping movement, not shuffling

Figure 6-24 Acceptance test of the Radus astronaut boots.

The Radus boots completely solved that problem. The permanent magnet fields are switched away from the "boot sole contact with the beam" for that foot that the astronaut wishes to lift, so he can lift it easily and take another step. Then the fields are switched back in again so that the strong field is on the boot sole as he places his foot down. This switching of the fields allows him to walk in a manner resembling normal walking, though a little slower. To do that switching by normal "battery and electromagnet coils" would be prohibitively bulky and heavy — and awkward. With the Radus boots, the astronaut could walk in a manner very similar to slow but normal walking.

However, it is easily seen that an adaptation of the Radus process could conceivably be used to produce a self-switching, self-powered permanent magnet motor. Being a permanent dipole, a magnet is already a particular kind of "free energy generator", since it continuously extracts magnetic energy directly from the active vacuum due to its dipole asymmetry in the virtual photon flux of the vacuum.

The Radus boots were abandoned quickly. NASA then developed the present inferior "shuffler" kind of magnetic boots where the astronaut cannot lift his boot from the surface, but must "scoot" his feet along in a sliding and painfully awkward fashion {448}.

Even today, it is little known that in many virgin magnets fresh from the factory, their very first use conditions them with a Radus-type memory! *Thatfact can be used, e.g., to create magnets whose fields appear normal, but which deviate from the normal behavior ofordinary magnets, and whichproduce anomalies in their magnetic fields.*

The Kawai engine {31} uses a novel means of switching the flux path itself instead of overpowering the magnetic poles in an electromagnet. As this is written, Bedini has been notified that his patent with a "path-switching" effect control method has been accepted and will be issued. Although control of the Kawai engine was seized by the Yakuza, we expect to see that some of the first COP> 1.0 motors on the world market will be magnetic motors using the Radus effect or other flux path switching method.

6.4.6 Hole Currents and Electron Currents

In a conducting solid, there are both hole currents and electron currents moving in response to a forcing electric field. In the simple case, electrons move in one direction along the conductor and lattice holes move (migrate) in the other. However, when additional fields are added, the situation can become very complex. The holes and electrons can move oppositely or together in the same direction, depending on the arrangement of the fields and voltages. One can even use fields at right angles to the conductor to affect the currents, and even stop them. This is a rich subject for the inventor, and one that does not appear to have been adequately explored for potential energy and power purposes. This is particularly true when the conductor material is bent or shaped, etc. This area is so broad that it will not be treated here; instead, we refer the reader to Burke {449} for a basic idea of some of the effects and current combinations that can be obtained. From there, an interested experimenter should search the materials science literature on electron and hole current responses of materials.

6.4.7 The Magnetic Wankel Engine

For baseline comparison, Figure 6-25 shows a conventional linear magnetic motor. As can be seen, due to the difference between magnetic poles, a magnetic field exists along the line of the linear track, from the end having the magnets separated the least to the end having the magnets separated the most.

Figure 6-26 diagrammatically shows the scheme of operation of the magnetic Wankel engine. It is basically a linear magnetic motor, wrapped into almost but not quite a complete circle. A set of permanent magnets, each at an angle to the various radial lines of the device, comprises a slightly widening spiral stator that forms most of a circle. A circular rotor with a sector magnet is mounted inside this spiral stator. An end gap exists in the stator as shown, so that the stator is not a completely closed ring. The direction of rotation of the rotor is clockwise as shown. For demonstration of the principle, the beginning air gap between rotor and stator is 0.1 mm and the ending air gap is 5 mm.


Suspended moving platform
Propulsion force direction
PLATFORM AND SLIDER RIGIDLY FIXED TOGETHER
SLIDER
STATOR
S
N
Propulsion force direction
S
N
S
N

Stator opening is slightly wider at right end than at left end. North field is weaker at right, so slider is repelled to the right.

Figure 6-25 Type of conventional linear magnetic movement device

An electromagnet is mounted along the perimeter of an angular sector of the rotor, completing the stator gap. The electromagnet is weakly magnetized by a weak trickle current in the associated coil, furnished by a coil with a make-and-break magneto point gap. The electromagnet is magnetized, say, with the north pole facing radially outwards, and the south pole facing radially inside. In the stator, the permanent magnet north poles are facing radially inward toward the rotor, but at an angle, and the south poles are facing radially outward but at an angle.

Tangentially the north pole of the rotor is in a nonlinear magnetic field, and it will experience a clockwise force and acceleration from position 1 where the air gap between rotor and stator is the 0.1 mm minimum, to position 2 where the air gap reaches the 0.5 mm maximum.

If this were all that was involved, the engine would not produce COP> 1.0 because the tangential field is conservative unless additional *free* energy is introduced to overcome the back mmf region in the stator gap. When the rotor crossed the end gap in the stator between point 2 and point 1, very sharp and dynamic magnetic braking due to the back mmf would be done back upon the rotor magnet by the field of the stator magnets at position 1.

Since any real machine will have at least some friction and drag, the actual COP would be less than 1.0.


STATOR ELECTRO-MAGNET
AIR GAP 5.0 mm
DISTRIBUTOR (WITH BREAKER POINTS)
BATTERY
SLANTED PERMANENT MAGNETS
AIR GAP 0.1 mm
ASYMMETRICAL REGAUGING SECTOR
STATOR PERMANENT MAGNET ASSEMBLY (FERRITE)
SHAFT
POWERFUL PERMANENT MAGNET
DIRECTION OF ROTATION

figure 6-26 Magnetic Wankel engine with asymmetrical regauging section.

Let us use the notion of the magnetostatic scalar potential (roughly, magnetic pole strength) to examine a new situation in the end gap.

Technically, let us regard a single unit north pole in the rotor, going from position 1 to position 2 (the acceleration cycle, where the engine will deliver shaft horsepower against a load), and going from position 2 to position 1 (where the magnetostatic scalar potential must be suddenly regauged asymmetrically to equal or exceed the potential at position 1, in order for the rotor to continue unabated or with even further acceleration. That is, when the rotor enters the "back mmf' end gap between position 2 and position 1, a sharp and sudden increase in the "stator magnetostatic scalar potential" must be accomplished, so that the potential in that region is equal to or greater than the potential at position 1. This effect, nearly freely obtained, is what is required for a self-powering magnetic Wankel engine.

In normal machines, conventionally this asymmetrical regauging part of the cycle is where the design engineer forcibly inputs energy from outside the system to do brute physical work on the rotor to forcibly "reset" the machine, and to forcibly wrestle its potential energy storage back to initial conditions. In short, the operator himself arranges to furnish all the excess energy from outside the system that is required to brute force "regauge" the potential at that point, thus effectively creating a multivalued potential instead of a single valued potential. A multivalued potential achieved only by the operator himself furnishing the extra potential energy will not produce COP> 1.0. It will in fact produce $\int \mathbf{F} \bullet \mathbf{dl} \neq 0$ of the motor section, but only at the expense of extra energy that the operator himself had to input and pay for. In that case and in a real system with some system losses, the net work out because of $\int \mathbf{F} \bullet \mathbf{dl} \neq 0$ will still be less than the total energy input by the operator.

The forcible "reset" work is conventionally done by simply overpowering the field and reversing it (building it up equal and opposite in the other direction), but with energy totally input by the operator and not "free energy input from the environment" at all. The operator first pays to "kill" the existing field, and then pays to establish a field in the opposite direction.

To obtain COP>1.0 and self-powering, we must trick something else or some other process into furnishing that asymmetrical regauging energy — or most of it — for regauging of the magnetic Wankel engine in that stator gap zone. In other words, instead of engaging in the conventional wrestling match against the back mmf, we must let something else provide most of the energy for the wrestling.

During rotation of the stator from position 1 to position 2, we have been maintaining (and paying a little for) a tiny trickle current and small voltage from the battery into the coil around the electromagnet. As the rotor enters the stator gap, suddenly a sensor sharply breaks the distributor points, momentarily inducing a sudden powerful voltage in the coil. With a very short delay, a very sharp surge of current appears in the coil, producing a sharp and suddenly increased magnetostatic scalar potential (pole) in the gap region. That is the "multivalued potential" effect, where we pay a little to achieve it suddenly at that point, by invoking Lenz's law.

The effect is that suddenly the rotor is raised to the same or greater magnetostatic potential as exists at position 1, and "almost freely though not quite". If equal, the rotor suddenly is in a region with no back mmf, hence it experiences no deceleration braking. If the sudden potential is greater than the potential at position one, the stator in this normally back mmf region now actually experiences a further acceleration (a forward mmf) in that region.

Note that no *radial* mechanical work can be done on either the electromagnetic pole piece (part of the stator) or on the rotor, since neither the stator nor the rotor can move *radially.* However, there momentarily exists a clockwise circumferential magnetic field on the rotor in the stator gap, due to the gradient between the sharply regauged pole piece magnetostatic potential and the potential at position 1.

So we pay a little energy continuously (tiny trickle current, sharply broken breaker points) to get much more energy density momentarily in that small back mmf gap region only. The former back mmf in the stator gap is sharply eliminated by the Lenz force and converted to forward mmf. The rotor experiences a continuous acceleration throughout a complete rotation, due to the judicious use of an artificially induced multivalued magnetostatic scalar potential.

If the average shaft power output during the complete rotation cycle is made greater than the average power input to the asymmetrical regauging circuit during that same rotation cycle, the engine will produce COP>1.0. This type of engine is also easily close-looped, since the excess output is **not** electromagnetic energy but mechanical shaft rotation energy.[193] Hence the problem of the Dirac sea hole current (discussed in Chapter 9) is eliminated.

Such engines have been built and placed in an automobile to power it, in Japan {450}, though there is no information on the exact overall COP. The design was lighter and smaller than a gas engine of the same power, and it was a pygmy when compared to other electric engines of similar power. **The** prototype 45-hp unit weighed 155 pounds compared to 440 pounds for a comparable electric motor. The rotary engine was compact enough to fit inside a two-foot cube. The engine was in development by Kure Tekko, a sizable firm that supplies auto parts to Toyo Kogyo, the Mazda maker. To my knowledge, no hard data on the input electrical power utilized for the trickle current and current-breaker has been made available by the Japanese. The principles, however, are quite clear and easily analyzed.

This may be one of the Japanese COP>1.0 engines suppressed by the Yakuza.

---

[193] For example, a geared or belted arrangement can be used to drive a very small but efficient DC generator that replaces the battery. Many other efficient arrangements are possible.

The researcher might like to consider using a strategically-placed Wiegand wire sensor (discussed in the next section) as the free "generator" providing a pulse of electrical energy to the pulse-magnetizing coil in the stator gap region at the precisely appropriate time. If that or some other similar "self-furnished" pulse of sufficient power can be delivered to the pulse-magnetizing coil, then the system would self-initiate a multivalued magnetic potential in that gap region. In that case, the driving magnetic field around the loop need not be conservative, and self-rotation would be possible without violating any laws of nature or electrodynamics. At least a small toy demonstration model might be possible, simply to illustrate the principle. Presently we know of no one who has tried it.

6.4.8 The Wiegand Effect

If a Permaloy® or other suitable magnetic wire is properly tensioned and worked by repeated torsion while under tension, the skin of the wire is work-hardened and caused to have different magnetic characteristics from that of the internal core. This type of wire is called a *Wiegand wire,* or *pulse wire,* or "self-nucleating magnetic wire" (SNMW™).

When the pulse-wire experiences a certain level of ambient magnetic field strength, it will automatically switch its magnetic state, very sharply, producing a sharp magnetic field pulse. The effect is generally called the *Wiegandeffect.*


Permanent magnets field causes Wiegand wire to reverse polarities, inducing voltage pulse in the coil
Permanent magnet
Magnetic alloy pulse wire
soft core
hardened outer shell

Figure 6-27 The Wiegand effect

If a coil of many turns of fine electrical conductor is wound around the Wiegand magnetic pulse wire, then when the wire suddenly alters its magnetic state, the sudden magnetic field pulse "cutting" the conductor bundle will produce a sharp electrical pulse. Thus the apparatus produces a sharp pulse of electrical energy, when the ambient magnetic field intensity reaches the pulse-initiation value. No input of outside energy is necessary. The apparatus simply gates the energy from the vacuum when it sharply changes its magnetic polarity.

Wiegand effect sensors may achieve voltage pulses up to a nominal 12 volts, in a typical application.

Numerous patents were issued to Wiegand prior to his death {451a-451h}.

Figure 6-27 diagrammatically shows the primary parts of a typical Wiegand sensor application, where the Wiegand wire is also known as a *pulse wire.* The operation of the pulse wire itself is shown in Figure 6-28. Figure 6-29 shows a typical rotary Wiegand effect pulse transmitter.


Flux direction
Shell (top)
Core
Shell (bottom)
Wire saturated Shell and core magnetized in same direction
Small reverse field switches core in reverse direction
Reverse field increases and switches shell in reverse direction also This large change in magnetic flux induces a pulse in surrounding pickup coil

Figure 6-28 Operation of the Wiegand effect in a pulse wire.

Pulse wires find many modern "switching" uses, since one does not have to connect them to a power supply in order to obtain the electrical signal pulse generated in a magnetic field as it changes. The magnetic experience of **the** wires can be arranged (using a "resetting magnet") to automatically **reset** the pulse wire to its original condition after the initiation magnet has **fired** it. Many identification cards for personal access to restricted facilities use these wires. Some magnetic memories use the effect. At least one European automobile firm has even used Wiegand wires to trigger the timing of automotive ignition systems.

The pulse characteristics created internally by the Wiegand wire represent a sharp, asymmetrical, self-regauging of the magnetics. The combined magnetic field consisting of the ambient magnetic field and the Wiegand wire magnetic pulse is momentarily a nonconservative magnetic field. It follows that a closed-loop integration $\int \mathbf{F} \cdot d\mathbf{l}$ around some paths in the combined magnetic field of the system do not sum to zero.


MAGNETS
CORE
SHELL
PULSE
Magnets rotate past core and induce pulses in surrounding coil as the Wiegand device functions
Wiegand device

Figure 6-29 Operation of the rotary Wiegand pulse generator

In theory, at least, it should be possible to utilize something like the magnetic Wankel engine together with exactly self-triggering and self-resetting Wiegand units to form a self-powering permanent magnet motor. In short, referring to our discussion of the magnetic Wankel engine, it might be possible to use a special Wiegand sensor and pulse generator to furnish the properly timed pulse to the coil that enables the continuous operation of the Wankel engine. Obviously this type combination would have occurred to the Japanese scientists working on the magnetic Wankel engine.

We accent that the resulting system would be an open dissipative system, far from equilibrium in its energetic exchange with the vacuum during the Wiegand pulsing. The disequilibrium is achieved by the momentary self-regauging of the magnetic gap in the magnetic Wankel engine.

My colleagues and I have experimented with Wiegand wires and Wiegand sensors to a limited extent. The effect is quite real, fully documented in the scientific literature, and the wires and sensors are not too expensive. A typical coil of 1,000 turns on a 3-cm Wiegand wire will produce pulses of about 2 volts in a 1,000-ohm resistor. The pulse width (half maximum height) is about 20 microseconds. Essentially the Wiegand wires are immune to stray magnetic fields. Viewed on an oscilloscope, the pulses are very clean without spurious oscillations or hash. The field required to switch a typical Wiegand wire is typically about 150 Oersteds. The resetting field is quite a bit smaller, being about -20 Oersteds. With further work, it is probably possible to come up with Wiegand wires whose coils produce up to 20 Volts in a 1,000-ohm resistor. If 25 of these 20-volt Wiegand pulse generators wired in series could be induced to fire simultaneously across a 1,000-ohm resistor, something like a momentary half-watt device could be built. That might be enough to operate a very small version of the magnetic Wankel engine, etc. purely for demonstration purposes.

For practical power, of course, one would need to find a way to increase the power output in each Wiegand generator pulse. So far, no one has been able to successfully find a way to do it, at least to our knowledge. If the reader finds a way to do that, then the reader should certainly patent the process and use it in a self-powering magnetic Wankel engine!

So to those experimenters wishing to experiment with something relatively inexpensive, we would suggest investigating the possibility of incorporating Wiegand units into a magnetic Wankel-type small magnetic motor, and attempt to get a self-powering little unit, or try to build a self-powering version of the rotary Wiegand pulse generator. It is at least possible in theory, and if achieved in practice it will prove that self-powering EM engines are perfectly possible.

6.4.9 Kawai Path-Switching Motor

Japanese inventor Teruo Kawai has invented a process for adroit self-switching of the magnetic path in magnetic motors, rather than directly overpowering the magnetic field and then forcibly reversing it. The process reduces most of the back mmf in an otherwise rather conventionally switched magnetic motor, and results in producing a COP that is approximately double the stated efficiency rating of the unmodified motor. Understand, the Kawai motor always has an efficiency less than 100%, even when its COP>1.0! Hence if one starts with a *high efficiency* magnetic motor — e.g., efficiency of 0.7 or 0.8 — one can obtain a modified motor having a COP of 1.4 to 1.6. Two Kawai-modified Hitachi high-efficiency magnetic motors were tested by Hitachi engineers, and the tests did indeed show COPs of 1.4 and 1.5, respectively, under rigorous and totally independent testing conditions.


16g
14b
14c4
16h
14c5
16f
16e
16i
13
16d
16j
14b
14c5
11
16k
16c
14b
16b
16l
16a
14d
16e
16i
14d
13
11
14d
16a
16e
16i
14d
14d
14d
16a
16e
16i
16a
16e
16i
16a
16i
16e
14d
14d
14d
16a
16f
14c3
14d
16e
16i
14c5
14d
16j
13
11
14c
16a
16f
14d
13
14d
11
16j
16b
14d

Fig 6-23A

Fig 6-23B

Fig 5-23C

Fig 6-23D

Fig 6-23E

Fig 6-23F

Fig 6-23G

Fig 5-23H

Figure 6-30 The Kawai path-switching process.

Figure 6-30 shows eight snapshots A, B, C, D, E, F, G, and H of the rotor advance of a typical Kawai engine, taken from Kawai's 1995 patent {452}. This is one end rotor/stator side of a two-rotor device, where a similar rotor/stator device is on the other end of the central shaft *11.* In snapshot A, pole piece *14* had three outward teeth *14b* dispersed equally around the circumference, alternated with three notches. An end magnet *13* provides the source of flux passing through the pole piece. With the electromagnets DC-energized, their core materials *16c, 16d, 16g, 16h,* and *16k, 16l* are shown shaded by flux from central magnet *13* out through teeth *14b.*

In snapshot B, electromagnets *16a, 16e,* and *16i* are energized. The shaded area shows the sharp convergence *14d* of the flux from magnet *13* through pole piece *14* and the edge of teeth *14d.* Since the electromagnets are magnetized in attracting mode, the rotor will experience a torque tending to widen the flux path from magnet *13* to the activated electromagnets. Thus a clockwise torque exists on the rotor, and it will start to rotate clockwise.[193] Note that each electromagnet is operating independently of the other two.

As shown in snapshots C, D, E, and F, the rotation of the rotor continues clockwise, widening the connecting flux path to the three activated electromagnets. During this time the torque on the rotor is clockwise.

In snapshot G, the flux path to the activated electromagnets is fully widened. In addition, the leading edges of the three teeth are just beginning to enter the domains of the next electromagnets *16j, 16b* (see snapshot A) and *16f.* This is getting symmetrical to the original position shown in snapshot B.

Now the electromagnets *16i, 16a,* and *16e* of snapshot G are deactivated, as shown in snapshot H, and electromagnets *16j, 16b,* and *16/*are activated. This action asymmetrically self-regauges and resets the engine back to the original situation shown in snapshot B, but one more electromagnet beyond. The action cycle begins anew. As can be seen, in each complete rotation of the shaft, each of the three teeth of the rotor will be asymmetrically self-regauged multiple times. So multiple total asymmetrical self-regaugings, resettings, or "refuelings" are utilized per shaft rotation.

In each motor coil, at energization a tooth is just entering that coil, Energized in attractive mode with respect to the ring magnet around the shaft, the flux in the pole piece jumps from fully widened flux (and small **or** vanishingly radial torque on the rotor) to angled and narrowed flux (with full radial clockwise torque on the rotor). This is an asymmetrical self-regauging action. As previously explained, the narrowed flux and its angle exert a clockwise accelerating tangential component of force upon the rotor. By the asymmetrical self-regaugings of the engine, each coil is de-energized prior to beginning to exert radial back emf— which it would do if it remained energized as the trailing edge crossed it and again narrowed the flux path).

So the Kawai engine uses normal magnetic attraction to accelerate the **rotor** for a small distance, and then asymmetrically self-regauges to zero attraction to eliminate the back-mmf drag portion of the attractive field. It regauges to zero as the reset condition.

---

[193] The Kawai patent contains a small error of misstatement. It states at first that the torque and rotation are counterclockwise, and then shows it moving correctly clockwise from figure to figure in the series.

For appreciable power and smoothness, the typical Kawai engine uses an extensive number of asymmetrical self-regaugings per axle rotation, for example 36 times on each end, or a total of 72 times for the two ends. The force field of each coil, accompanying its increased magnetostatic scalar potential, is oriented radially inward, so that radial work cannot be done by the coil on the rotor because the rotor does not translate radially. Advantage is taken of the initial clockwise acceleration force initially produced, and self-regauging eliminates the counterclockwise decelerating drag force that would be produced without the regauging.

The major benefits are that (a) multiple self-regaugings occur for a single rotation of the rotor assembly, enabling high weight-to-power ratio, (b) each electromagnet is energized only when positively contributing to the clockwise torque that drives the rotor, and (c) each coil is de-energized to asymmetrically self-regauge the system during those periods when the coil would otherwise create back-drag (counterclockwise torque) if it remained energized.

A conservative cycle is one in which the work done in the back-drag (mmf) region is equal to the work done in the forward boost (forward mmf) region. Self-eliminating the back-drag portion of the cycle is a form of asymmetrical self-regauging, and makes the net field highly nonconservative. The Kawai approach is thus permitted to attain COP>1.0. In his U.S. patent, Kawai quotes performance measurements showing COP = 3.18. As we stated, Hitachi engineers measured two Kawai-modified Hitachi magnetic motors which exhibited COP =1.4 and 1.6 respectively.

Since the output is shaft horsepower, in principle the Kawai engine can be close-looped for self-powering, without consideration of the Dirac sea hole current. With its external close-looping system (not shown), it falls within the second close-looping class, that of an "outrigger" system. Only the unitary system closed-looping class requires consideration of hole currents in the Dirac Sea.

The Kawai process and several other Japanese overunity systems have been blocked from further development and marketing by the Japanese Yakuza. The present author and the Board of Directors of CTEC were physically present and in final negotiations (having reached agreement!) with Kawai to market his self-powering motors worldwide, when control of the Kawai company and process were suddenly seized on the spot in our presence.[195]

6.4.10 Bedini's Skin Depth Magnetic Switching

Bedini found a most interesting variation of flux path switching: he switches the direction of just a little fraction of the ongoing magnetic flux in a material flux path, on the skin of one side of it and with only a slight "skin depth".[196]

Suppose a flux path material is used as the stator pole of a permanent magnet motor. A large permanent magnet is used to magnetize that short length of flux path, as shown one the left in Figure 6-31, which illustrates a concept for a magnetic motor. For convenience, imagine that the small magnet on the right is not yet placed on the material flux path extension. The flux path extension is energized by the south north pole of the large permanent magnet on the left, and used as the stator in a rotary magnetic motor.

---

[195] To anyone who understands Japanese culture, Kawai paid me one of the greatest compliments possible. After his company representative called from Japan, Kawai shipped his *original proof of principle engine* — which first successfully demonstrated his flux-path switching process without being optimized for COP>1.0 — to me, here in the U.S. In the Japanese manner, he had entrusted me with his single most valued possession. From years of aikido experience, I fully understood the meaning of this unprecedented gesture, and expressed my deep appreciation accordingly. From our first meetings with Kawai and his group, I have and always shall have the utmost respect for Teruo Kawai. In my view, it is a sad loss to humankind to have his engine buried and withheld so brutally. Kawai had already achieved a closed-loop self-powering version, and it is this version upon which we reached agreement. In less than 24 hours after that agreement, the Kawai engine and company — and Kawai's own fate — were seized and no longer in Kawai's hands. For those unfamiliar with the deep spread of the Japanese Yakuza, the following are recommended: (a) Brian Bremner, "How the Mob burned the Banks: The Yakuza is at the center of the $350 billion bad-loan scandal," *Business Week,* Jan. 29, 1996, p. 42-43, 46-47; Michael Hirsh and Hideko Takayama, "Big Bang or Bust?" *Newsweek,* Sept. 1, 1997, p. 44-45; Adam Johnston, Yakuza: Past and Present," downloaded from the Internet, Committee for a Safe Society, Organized Crime Page: Japan: History and present status of Japanese organized crime.

[196] Close colleague Ken Moore also independently discovered this effect in his own experiments, but then we found that Bedini had discovered it earlier. That was fine with Ken; he greatly admires Bedini and the marvelous discoveries Bedini has made. I greatly admire both of them, and am happy to call them best friends. After all, science has a human side as well as a materials side. Without one's close colleagues and best friends, science alone would be a miserable enterprise!



Figure 6-31 Bedlni skin depth magnetic edge switching.

As can be seen, the north pole of the rotor, shown in the figure, is attracted to the resulting south pole of the stator. Power can be taken from the shaft of the rotor while it is being attracted in to the extended north pole of the stator flux extension. As it begins to pass the extension end, obviously if nothing else is done it will develop back mmf "drag" by being attracted back toward the north pole of the flux extension as it passes it.

However, suppose that —just when the rotor south pole is passing dead center of the stator north pole extension, one suddenly pulses a small flat coil placed on the face of the extension, which serves the function of the small permanent magnet shown on the right of the material flux path extension. Further, suppose the magnetic field produced by the coil is oriented as the field of the small permanent magnet, but is much weaker than the magnetic field of the large permanent magnet on the left. A very curious effect then occurs. This energized coil magnetizes the edge of the flux path extension, to a small "skin depth" as shown, with a *north* polarity. The magnetic flux is now bidirectional in that same material flux path extension.

Further, this edge-switching action is performed so that it is this "partial north polarity" of the now-altered extension that faces the rotor north pole as it begins to pass the extension and enters what previously would have been a back mmf section. Instead, now that former back mmf section is a weakened forward mmf region, *further accelerating the rotor.* This action breaks the Lorentz symmetry around the rotation path of the rotor, resulting in a net nonzero (nonconservative) magnetic field. Hence the entire rotor exhibits a net drive force around its loop. The rotor will accelerate until the mechanical work performed upon the shaft, friction, etc. is equal to the net magnetic energy furnished to the rotor.

The beautiful part of this motor is that one does not have to "overcome" by brute force — and then reverse — the north polarity of the entire stator extension. In theory, the overall energy added to the rotor is greater than the energy that must be added for the "edge switching" of the magnetic flux path extension, because the entire back mmf of the motor has been eliminated and replaced by a weaker forward mmf. If the process of furnishing the "skin depth" weaker magnetic north field to the edge of the flux path extension is made sufficiently efficient, this engine also can be made self-powering, at least in theory.

The former "motor" design has been converted to a "motor/generator" design, by the addition of the edge-switching action. The novel factor is the use of bidirectional flows of magnetic flux in a single material flux path.

An additional improvement is to rig a Wiegand sensor and pulse generator or sensors in conjunction with the rotor action, to freely furnish and kill the edge-switching pulse to the face-magnetizing coil on the flux path extension, at the appropriate times. This is an area where even high school students will be able to experiment.

Bedini's patent on the edge switching process and its various embodiments and improvements has been issued {453}.

6.4.11 Bedini's Flux Path Switching with Energy Capture

One additional embodiment of the Bedini flux path switching motor is shown in Figure 6-32. Here the entire flux path is switched, by moving a small coil on the bottom side of the material flux path, as shown in the figure. As Radus showed {454}, it turns out that a much weaker magnetic field in that left bottom position will switch the flux path of a powerful permanent magnet field at the left top of the path, as shown.

Now, however, Bedini adds a transformer coil around the right end of the core (the right end of the extension is still the stator pole in the magnetic motor diagrammatically shown in Figure 6-32). When the flux path is switched back and forth, this transformer coil produces an AC signal output, which can power a load as shown, and can even be used to power the switching power supply. The trick is that it requires less energy to make the vertical flux path preferable to the horizontal flux path, than the energy delivered into the flux path by the permanent magnet. The potential **for** self-powering of a sufficiently efficient magnetic motor is obvious.


N
PERMANENT MAGNET
VACUUM
(Virtual photon flux)
Virtual photon flux exchange
(MAGNETIC DIPOLE IS AN ASYMMETRY IN VACUUM FLUX EXCHANGE)
RESISTOR
i_2
LOAD
P'_o
F''_i
flux
S
transformer output
FLUX PATH
P''_o
FLUX PATH SWITCHER
N
F'_i
S
COIL (cutaway)
losses
P'''_o
Switching Power Supply
P_i

Requires less power to switch flux than the power the switched flux produces in the transformer.

Figure 6-32 Bedini's total path switching and energy recovery process in a transformer.

So the motor can be powered while simultaneously acting as a partial generator. For efficient switching, this motor/generator can in theory develop COP>1.0 and can even be made close-looped and self-powering. We strongly accent that the primary excess energy input to the system is from the vacuum itself, via the broken symmetry of the large permanent magnet dipole at the left top of the material flux path. As we have repeatedly stated, the only energy problem is how to capture and utilize the EM energy freely received, transduced, and poured out from the vacuum by the source dipole's broken symmetry, without using half of it to destroy the source dipole.

6.4.12 Transformer Secondary Shunted by a Negative Resistor.

See Figure 6-33. This embodiment assumes the availability of a true negative resistor — possibly an adaptation of a point contact transistor or other device. As shown in the figure, a transformer exhibiting COP> 1.0 can be developed by adding a shunting *true* (not differential!) negative resistor across the terminals of the secondary, adjacent to the secondary. In this manner, the Lorentz symmetry of the closed unitary current loop containing the external loads and losses, and normally the secondary of the transformer in series, is broken.

Part of the return spent current is now "pumped" back up from ground side to power side of the transformer secondary without passing through the secondary. The pumping work is providing by dissipation (in the negative resistor) of energy freely obtained from the active vacuum environment. In short, one adds a negentropic process in parallel with the secondary coil, in the secondary external circuit, breaking the otherwise enforced Lorentz symmetrical regauging of the discharge of the collected EM excitation energy in the secondary circuit. This provides the capability for a permissible COP>1.0 transformer.

ON EACH HALF CYCLE, ONE OF THE NEGATIVE RESISTORS SHUNTS PART OF THE RETURN CURRENT AROUND THE SECONDARY, FROM LOWSIDE TO HIGH SIDE, THUS DECREASING THE BACK-FIELD COUPLING FROM SECONDARY TO PRIMARY ACROSS THF TRANSFORMER. THIS LESSENS THE ENERGY DISSIPATION REQUIRED IN THE PRIMARY FOR A GIVEN ENERGY FLOW TRANSFER FROM PRIMARY TO SECONDARY



Figure 6-33 Transformer shunted by a negative resistor.

In theory, if the negative resistor can bypass all the current in the secondary, or almost all of it, the transformer can become a COP»1.0 device.

This overunity transformer can use step-up of the voltage from primary to secondary, and exhibits an asymmetry in its forward and backward field coupling between primary and secondary. Thus the dissipation of energy in the primary circuit need not be as great as the dissipation of energy in the secondary circuit. The *energy flows* are of course in perfect conservation, but there is no law of nature requiring the *energy dissipations* to be conservative between the primary and the secondary. It is strictly the backfield coupling from secondary to primary that enforces equal energy dissipation in the primary as in the secondary, in normal transformers. And that backfield coupling's strength is a function of the return current through **the** transformer secondary. By reducing that current, the back coupling to the primary is reduced, which in turn reduces the current draw of the primary from the external power supply.

No laws of physics, electrodynamics, or thermodynamics are violated by the asymmetrically coupled transformer power system with broken symmetry in its secondary to primary circuit couplings. In short, there is less backfield coupling from primary to secondary than there is from secondary back to primary. The additional energy dissipated in the secondary circuit is freely extracted from the vacuum by the negative 4-resistor shunt.

Again, this application assumes the availability of a true negative resistor, to use as a shunt of the secondary.

The beauty of this application is that, once achieved, such a COP>1.0 transformer can easily be close-looped for self-powering by standard "governed" positive feedback. No concern as to hole current effects usually need be accounted for unless the COP becomes very large.

6.4.13 Eddy Current Multiplier.

Figure 6-34 shows an example of an eddy current multiplier, adapted from Burke {455}. This is given as a somewhat unusual system which may exhibit novel effects and possibly can be adapted into a COP>1.0 system (e.g., by using permanent magnets instead of the coils and triggering things into unbalanced condition using a rotary pulse wire generator. We simply list it here as a candidate for the experimenter.


ROTATION
DRIVING VOLTAGE V_1
EDDY CURRENTS FROM TWO DIFFERENT SOURCES INTERACT TO ROTATE THE DISK
EDDY CURRENTS
DRIVING VOLTAGE V_2

Figure 6-34 Eddy current multiplier.

In Figure 6-34, the shaft of the conducting disk is connected to a rotor, which could have arrangements for rotary type of Wiegand pulse generator of Figure 6-29 (with self-initiation and self-recovery) around it (not shown in Figure 6-29). One would start the rotating disk by hand. These Wiegand sensors would then automatically and repeatedly deliver a series of electric pulses to the coils, momentarily generating the two eddy currents shown, so that dynamic force and rotary acceleration is obtained during the endurance of the pulses. In short, one would "electrically kick" the coils so that they continually deliver a propulsive "magnetic kick" to the conducting disk to repeatedly generate eddy currents to rotate it. The rotor is powered as shown by the interactions of the two unbalanced induced eddy currents. Such an arrangement could possibly exhibit COP>1.0.

To experiment with such an apparatus, the major parts that must be developed are (i) the rotor and coils arrangement (the motor), (ii) the integrated rotary Wiegand effect pulse generator with self-recovery, and (iii) the proper timing arrangement. Each should be developed and optimized individually in the researcher's experiments, then combined and optimized together. This is an experimental area that can be cheaply investigated, e.g., by a college student or high school student for a science project. Whether COP>1.0 is achievable or not depends upon the efficiencies that can be obtained with the various processes involved. It is possible, at least in theory, for such an arrangement to be self-rotating once rotary motion is underway.

6.5 CONCLUSION

In this chapter we have advanced many approaches to COP>1.0 systems, that have been tried or considered by various inventors and researchers in the field. Many of these experimenters have attained concrete, replicable results, including results published in the hard literature.

We hope this sampling shows the reader that indeed we can have "self-powering" electrical power systems and COP>1.0 electrical power systems whenever the scientific community will come out of its preoccupation with the present seriously restricted electrodynamics and electrical power engineering practice and fund the necessary research. Simply funding a few graduate students for research and doctoral theses in these areas would be very useful and immensely more productive for electrical energy purposes than all the billions and years spent on chasing hot fusion.

Hopefully the iron dogma of the scientific community against COP>1.0 electrical power systems is slowly changing. If so, and if the community will turn loose those sharp young graduate students and post-doctoral scientists on the problem, very shortly there will no longer be an electrical energy problem on Earth, ever again. We strongly refer the reader to Deffeyes' book {456} to rigorously validate the coming increase of the price of oil, in the middle of the present decade. See particularly the quotation from Deffeyes in our Endnote {342}. With the present extreme volatility of the MidEast and the continuing war on terrorism, the probability is high of eventual severe disruption of oil supplies and the energy infrastructure of the U.S.

An independent review of Deffeyes' book is given by Young {457} and we recommend that the reader digest that commentary also.

If the scientific community will fund the necessary research on permissible COP>1.0 Maxwellian systems, the quick results will solve the energy crisis, clean up the biosphere — including much cleaner air in our cities for the populace to breathe — provide cleaner streams, and result in far less polluted oceans. It will stop the pollution-caused destruction of species, and dramatically reduce the hydrocarbon combustion contributions to global warming. There will no longer be a necessity to consider "burying" in the bottom of the sea the excess CO2 from massive hydrocarbon combustion to provide the much-needed electrical power, because it will no longer be necessary to burn the oil, coal, and gas to get the power. And there will no longer be any necessity for expensive and highly vulnerable nuclear power plants with their resulting nuclear wastes that will remain radioactive for thousands of years.

If cheap, clean EM energy from the vacuum is rapidly developed, we may *finally* get the scientific community's head wrenched back out of the big nuclear power business, as a colossal waste of research manpower and taxpayer dollars — as well as providing ticking time-bombs for the terrorist teams now already in the United States to attack and destroy. It is so easy for a person with appropriate technical knowledge to build a portable electromagnetic pulse (EMP) "shooter" that one shudders at the consequences of in-country terrorist teams that can do so. Try imagining what we would face when the electronic controls of one or more operating nuclear power plants are suddenly disabled and destroyed with the reactor on line and providing power. Chernobyl might look like a mild spring breeze in comparison, should we have one or more actual meltdowns.

It is not a pleasant consequence to contemplate, and that alone may eventually dictate the overwhelming urgency of achieving decentralized, vacuum-energy-powered electrical power systems as soon as humanly possible. The present centralized, cumbersome energy infrastructure is vulnerable beyond all sanity, considering the thousands of terrorists already in country, with weapons of mass destruction as well as more conventional sabotage means. As a single example, the former Soviet Union clandestinely brought in nuclear weapons into the U.S., and

Spetznaz teams to detonate them on order. Such weapons (and teams) are already in large U.S. cities and population centers. The reader is referred to Lunev's book,[197] for details about how the nuclear weapons were introduced.

After all, we do have to live and survive in the real world, and not just in an idealistic scientific environment. We are already at war, with alerts of potential danger to our nuclear power plants already having been given on several occasions. In the present very disorderly and very dangerous world we live in, many of the former options we have had for decades are rapidly ending. That includes the option for the leaders of the scientific community to continue "business as usual", if they wish this nation and their own families to survive. There is an old adage in war: *Whatever your determined enemy can do to hurt you desperately, he will do as his highest priority.* Sadly, in my opinion the leaders of the scientific community — unwittingly — are presently doing almost everything they can do to insure that the energy infrastructure goes, the national economy goes, a nuclear meltdown possibly occurs, and this nation and much of civilization perishes in a new dark ages.

---

[197] Stanislav Lunev (with Ira Winkler), *Through the Eyes of the Enemy,* Regnery, Washington, 1998. Lunev is the highest ranking GRU defector. He is a former Colonel in the GRU, the military counterpart of the KGB. On p. 22-33, he summarizes the Spetznaz capabilities. On p. 22-27, he summarizes Spetznaz use of nuclear weapons already on American soil. On p. 26, he gives some of the ways in which the Soviets easily brought nuclear weapons into the U.S. On p. 30 he confirms **Russian** seismic weapons. Use of EMP weapons is on p. 30-31. Use of very, very low frequency weapons to destroy the human brain, put people into a zombie-like state, and aid in brainwashing is confirmed on p. 31. The present war on terrorism has many more facets than are presented by the conventional news media.

Just as the dinosaurs were confronted with a new and dangerous threat, and failed to adapt, the electrical power infrastructure is now confronted with a potent threat against its very vitals and — so far — is completely failing to adapt. It is going to have to adapt or perish, which presently implies that we all perish along with it. Those who make it their nefarious business to see to it, will see to it.

So let us "see to it" first, scientifically, as rapidly as human research and development can do the job. The very existence of civilization may well depend upon it.


N
Activated
Barium Ferrtte magnet
magnetized through face
Signal
coil
(input)
N
Power
coil
(output)
Actuated
Barium Fernte magnet
magnetized through face

Figure 6-5 Sweet vacuum triode amplifier (VTA) construction.

Chapter 7

Aharonov-Bohm Effect, Geometric Phase, and the Motionless Electromagnetic Generator (MEG)

[Decision that hydrogen fuel is the future]. *"We are at the peak of the oil age but the beginning of the hydrogen age. Anything else is an interim solution. The transition will be very messy, and will take many technological paths ...but the future will be hydrogen fuel."* [Herman Kuipers, Royal Dutch Shell.].

[Vacuum energy is real] *"...the acceptance of a structured vacuum described by an O(3) gauge group leads directly to the existence of novel charges and currents in the vacuum. These are conserved, or Noether, currents and charges and are clearly topological in origin. They spring from the fact that the vacuum is a topological space. Four such entities emerge: [1] A topological vacuum electric charge, also proposed empirically by Lehnert et al. [2] A topological vacuum electric current, also proposed empirically by Lehnert et al. [3] A topological vacuum magnetic charge, proposed also by Barrett and Harmuth. [4] A vacuum topological magnetic current, proposed also by Barrett and Harmuth.*

Each of these four objects can provide energy, which can be loosely termed 'vacuum energy': energy coming from the topology of the vacuum. " [Evans] {458}.

[Aharonov-Bohm effect] *"...the Aharonov-Bohm effect is a local gauge transformation of the true vacuum... [which] produces a vector potential from the true vacuum. [This gauge transformation] produces topological charge..., the electromagnetic field, which carries energy, and the vacuum charge current density first proposed by Lehnert ... and developed by Lehnert and Roy... ".* [Evans and Jeffers] {459}.

[Geometric phase] *"The concept of the geometric phase is closely related to the effect of a state function acquiring a non-zero phase factor after a quantum system undergoes a cyclic evolution. This means, that if a system after some time returns to its original state, the result of such an evolution will be recorded in the phase of the wavefunction. Moreover, this phase factor can be measured by interfering initial and final states. ... Although there are no widely recognized practical applications of the geometric phase, its experimental observations have been reported in many fields of science. The largest group of experiments have been carried out on polarized light ...and polarized neutrons ... The geometric phase has also been observed in magnetic resonance experiments ..., mesoscopic structures ...and molecular systems ...Analogues of GP — the Hannay angles — have been shown to exist in classical mechanical systems ..., the most famous example of which is the Foucault pendulum."* [Aleksiejunas][198]

[Practical use of geometric phase]. *"The motionless electromagnetic generator is the first practical macroscopic use of the geometric phase. "* [T. E. Bearden, 2001, to a correspondent].

[Impact of extracting energy from the vacuum] *"If they [quantum fluctuations of vacuum] can be [tapped], the impact upon our civilization will be incalculable. Oil, coal, nuclear, hydropower, would become obsolete — and so would many of our worries about environmental pollution." "Don't sell your oil shares yet — but don't be surprised if the world again witnesses the four stages of response to any new and revolutionary development: 1. It's crazy! 2. It may be possible — so what? 3. I said it was*

---

[198] I am much indebted to Dr. Rimvydas Aleksiejunas for this clear statement of the geometric phase. See his very elegant summary, " Introduction to The Geometric Phase Decomposition," on his Internet website at http://signalogram.free-hosting.lt/Research/gp dec.htm. His own publications in scientific journals and proceedings are also listed on **the** website, and many are available for downloading. His doctoral thesis dealt **with geometric phase** and he is a specialist in that field.

> *a good idea all along. 4. I thought of it first."* [Arthur C. Clarke] {460}.

7.1 Introduction

In this chapter we give a history, some information, and comments about the Aharonov-Bohm effect {473}, which was generalized by the Berry phase {477} for adiabatic conditions, which itself was further generalized by Aharonov and Anandan {480} to remove the adiabatic limitation. The modern all-inclusive term is *geometric phase,* which has been found to be involved in a very wide variety of physics areas. In its embodiments, the motionless electromagnetic generator (MEG) does utilize the Aharonov-Bohm effect (geometric phase) in a unique manner that we explain. We also remark on what we hypothesize may be some related new aspects of the curl-free magnetic vector potential itself.



Figure 7-1 Motionless Electronic Generator (MEG)

The motionless electromagnetic generator (MEG) (Figure 7-1) was invented by Patrick, Bearden, Hayes, Moore, and Kenny {461} after years of research and experimentation. It has been technically described elsewhere {462}, and scientific explanations of the fundamental mechanism by which it successfully extracts useful EM energy from the active vacuum have been published in the recognized literature {463, 38a, 464}. Other closely related papers on extracting EM energy from the vacuum have been published or are submitted and in review {465a-465h}.

A version of the MEG has also been independently replicated by Naudin {466}, and in fact by others who did not wish to publish their results. By permission, Naudin's Mark II MEG replica is shown in Figure 7-2. Consequently, the MEG is a validated and replicated COP>1.0 system, as required by proper scientific methodology. Further, sufficient information has been released for any competent laboratory team to replicate a version of the MEG.



Figure 7 2 Nuadin's Mark II Replication of the MEG.

We give an overview of the MEG, the principles of its operation, the status of the project, and some indication of future plans.

7.1.1 Status

As this is written, the first MEG patent has just issued {37}. A second Provisional Patent Application has been filed, and at this writing is in process of being replaced by a formal regular patent application. Two other patent applications are in preparation. All rights to the MEG are assigned to Magnetic Energy Ltd., Huntsville, Alabama, U.S.A., whose CEO is Dr. James L. Kenny.

In addition, Bedini and the present author have filed a provisional patent application on the process and embodiment for close-looping a COP>1.0 system for self-powering operation, and are in process of replacing it with a regular patent application also. Magnetic Energy Ltd. has permission to utilize the Bedini-Bearden close-looping process. In addition, Magnetic Energy Ltd. has its own proprietary close-looping process, for which a patent application is being prepared. The Company is also involved in serious discussions with several large companies and financial groups for potential financing. When that funding is obtained, we will open a substantial research and development laboratory here in the United States, serving a separate production company to be set up with our financial partners to produce and market the MEG. Meanwhile, laboratory work to complete the research and development of the MEG is also ongoing under a cooperative arrangement with the National Materials Science Laboratory of the National Academy of Science of a friendly foreign nation formerly under the Soviet bloc.

7.1.2 Future Plans

Our plans are straightforward. We will continue to pursue and update our patents and file additional ones as additional discoveries are made. We will continue our negotiations with major financial parties until satisfactory and mutually beneficial capitalization is obtained (we expect that to occur before the end of 2002). At that time we will establish a modern Magnetic Energy Ltd. U.S. laboratory devoted to advanced research and development, as well as a separate production company in partnership with our funding partners. The final research necessary on the MEG (four areas of physics as well as the electrodynamics) will be completed in somewhat less than one year after setup of the lab and lab team, and the production company is expected to have the first engineering development production prototype at the end of that first year. We expect it to be a self-powering unit. We will simply put the first MEG units into production and on the world market immediately thereafter.



Figure 7-3 Block diagram of envisioned **modular** MEG design.

See Figure 7-3. The first production MEG is envisioned as a modular 2.5 KW unit together with a synchronizer unit simultaneously developed, so that up to six 2.5 KW MEG units can be synchronized in a power system array. This will yield power units from 2.5 to 15 KW. We are struggling to have the closed-loop process completed and ready in that same first year, and if possible the very first MEG units will be close-looped and self-powered. At the end of the second year or before, we plan to have the close-looped basic MEG unit in 10 KW size, again with synchronizer so that up to six MEG units can be synchronized in an array. That will cover the 10 - 60 KW power system size, which is ideal for homes and small businesses. Once the units go on the world market, we believe that the market will be extraordinarily dynamic and productive. We intend to license multiple companies for production and competition for various markets, with no single company being given total monopoly worldwide.

7.2 Aharonov-Bohm (Geometric Phase) Effect

The Aharonov-Bohm (AB) {473} effect, or geometric phase (GP) {477, 480} effect, is now well known {467} in quantum mechanics and quantum electrodynamics, but does not exist in classical electrodynamics. The effect proves the reality of the potentials and their primacy over the fields. Further, it shows that electron effects can be generated by the magnetic vector potential A even in the absence of the magnetic field B.


UNCURLED
FIELD-FREE
A-POTENTIAL
PARALLEL TO
CURRENT I
CURRENT I
IN COILS
A-POTENTIAL
S
N
DIRECTION
OF B-FIELD
FLUX
(CIRCULAR)
INSIDE
TOROID
INPUT
A-POTENTIAL
MAGNETIC
B-FIELD FLUX
CONFINED TO
INSIDE THE
TOROIDAL
COIL

Figure 7-4 Aharonov Bohm effect for a tightly wound toroidal coil.

According to Feynman {468}, it required 25 years for quantum physicists to clearly face the issue eventually pointed out in 1959 by Aharonov and Bohm of the primacy and separate action of the force-field-free potential, in regions where no force fields were present (Figure 7-4) {469}. After the effect was experimentally demonstrated by Chambers {474} in 1960, it then required another 25 years before physicists would accept it. Even today, another 16 years after full acceptance in 1986, to our knowledge the Aharonov-Bohm effect has not previously been utilized in any practical electrical power system {470}, much less one that has a COP>1.0. As Aleksiejunas[198] states (see his quotation at the beginning of this chapter), there have not previously been any widely recognized practical applications of the geometric phase. Now there is a practical application of major worldwide importance, since the operation of the MEG depends upon the geometric phase (Aharonov-Bohm) effect to produce real electrical power from the active vacuum itself.

We also believe that the curl-free potential may not have been adequately investigated, particularly along the lines of its utilization in the MEG.

7.3 Abbreviated History of the Geometric Phase

The earliest work with a state function acquiring a non-zero phase factor after a quantum system undergoes a cyclic evolution was published in 1956 by Indian scientist Pancharatnam {471}. Pancharatnam noticed phase shifts of cyclic evolutions in optical phenomena. This means that, if the system leaves its original state and after some time returns to it, the result of the system's evolution will be recorded in the phase of its wavefunction. In addition, this phase factor can be measured by interfering the system's initial and final states.[198] Sadly, Pancharatnam's anticipation of the geometric phase factor did not receive the attention it so justly warranted, and his paper languished almost unnoticed for nearly four decades, when it was finally rediscovered. This was an excruciating scientific tragedy to Pancharatnam, comparable to that which befell Waterston {472}.

The effect of the field-free potential and the geometric phase issue were pointed out strongly by Aharonov and Bohm {473} in 1959 in a leading U.S. physics journal, causing much consternation in physics. Before that paper, most physicists still believed that all electromagnetic forces and effects were induced only by the force fields,[199] and not by the potentials.

---

[199] Indeed, the force fields do not even exist in mass-free space, but only in matter. Force is defined as $F \equiv \partial/\partial t\,(mv)$ so that mass is a *component* of force. Feynman states: *"...in dealing with force the tacit assumption is always made that the force is equal to zero unless some physical body is present... One of the most important characteristics of force is that it has a material origin... " "...the existence of the positive charge, in some sense, distorts, or creates a "condition" in space, so that when we put the negative charge in, it feels a force. This potentiality for producing a*

In the prevailing belief, when the fields were zero there were no EM effects. Indeed, the potentials were largely regarded as mathematical conveniences.

Another point of consternation was that the A-potential is not uniquely determined, but is determined only up to a particular gauge transformation. So there can be two (or even more) magnetic vector potentials A and A' corresponding to a specific magnetic field. Aharonov and Bohm raised a disturbing question: How can two different "causal" A potentials produce the same effect? We will rigorously answer this question shortly.

While the experiments suggested were difficult, they were performed shortly after the publication of the Aharonov-Bohm paper. The very next year, in 1960, Chambers {474} experimentally demonstrated the Aharonov-Bohm effect, though not with complete decisiveness. A 1983 paper by Tonomura *et al.* {475} was significant, and a 1986 publication of further work of Tonomura *et al.* was decisive {476}.

In 1984, Berry generalized the Aharonov-Bohm effect into the geometric phase {477}. In 1985 the Tonomura effort plus experimental work by Webb *et al.* {478} settled the matter, as strongly stated by Schwarzschild the next year {479}. In 1987, Aharonov and Anandan {480} further generalized Berry's geometrical phase, freeing it from its adiabatic

force is called an electric field. " So Feynman was fully aware that not the force field but only the potential (i.e., the potentiality) for producing the force field exists in mass-free space. The electrodynamicists continue to be confused on that point. E.g., on p. 28 of his *Classical Electrodynamics,* 2nd edition, Wylie, 1975 Jackson states: *"...the thing that eventually gets measured is a force... ",* confirming that force is an observable and thus a *d/dt* operation imposed upon spacetime LLLT to give a purely spatial entity LLL. On p. 249, Jackson also states that *"Most classical electrodynamicists continue to adhere to the notion that the EM force field exists as such in the vacuum, but do admit that physically measurable quantities such as force somehow involve the product of charge and field."* The two parts of the conventional assumption, as stated by Jackson, contradict each other. We point out that Jackson's book has been a standard of excellence for years, and no EM library is complete without it. It merely shows the extraordinary difficulty of rooting out the exasperating and mind-numbing confusion in physics between the observed effect and the unobserved cause. Force is an effect, after interaction (observation or measurement), hence cannot be the cause (which exists prior to interaction or measurement). Else, there is no difference between cause and effect, which destroys causality itself. This confusion is still there in even the hoary old classical mechanics, now some centuries old. By that standard, electrodynamicists have a long time remaining before they will have propagated this non sequitur" as long as the mechanical physicists have.

restriction and generalizing the geometry. Much discussion of the AB effect and Berry's geometric phase occurred {481a-481c}, but the scientific consensus was in: *The Aharonov-Bohm effect is real and the geometric phase is a widespread fact of nature.*

In 1985, Olariu and Popescu {482} published a very good overview and discussion of the AB effect up to that time, with hundreds of references.

Thousands of papers on the AB effect, the Berry phase, and the geometric phase have since appeared in the literature, and continue to appear at a rather steady and prolific rate. A few are listed for a sampling {483a-483k, 484a-484i}. The original Aharonov-Bohm effect has now expanded and spread widely through physics and into a myriad other effects and areas, such as the scalar AB effect, the Aharonov-Casher effect, magnetic vector potential vortices, quantum tunneling, chemical reactions, chaotic oscillation, and others. These related extensions are far beyond our interest here. We are, however, interested in what we hypothesize may be a new aspect of the perturbed curl-free magnetic vector potential A. We shall address that aspect briefly.

7.4 A Possible New Aspect of the Curl-Free Magnetic Vector Potential

We propose what may possibly be a unique new aspect of the curl-free A-potential — and thus of the Aharonov-Bohm effect — that has been uncovered in our MEG experiments. We caution, however, that this is a tentative interpretation and remains to be further validated.

First we state that the equation, $\mathbf{B} = \nabla\times\mathbf{A}$, usually accepted as the "definition" of the magnetic vector potential A, is not even a definition, because no equation is a definition.[200] If we rewrite the equation as the identity $\mathbf{B} \equiv \nabla\times\mathbf{A}$, then it is a proper definition — though not of the A-potential, but of the B-field itself, *given* that the A-potential exists and is primary. It also states that the B-field is simply a magnetic vector potential having swirl; i.e., the notion of the B-field captures that swirl aspect of a swirling A-potential. Hence the statement that B = zero implies only that **the** A-potential remaining is swirl-free and hence a linear EM energy current flow. Note that the B = 0 condition does not specify the magnitude of the remaining A-potential, but only specifies that it has no curl. This is a rigorous answer to the original question posed by Aharonov and Bohm of how two different A-potentials can have the same magnetic field B (the same swirl). It is no more mysterious than two different rivers having a whirlpool of exactly the same swirl magnitude.

---

[200] No equation is a definition, *a priori.* It merely states the relationship of the total magnitude of the entities on the left to the total magnitude of the entities on the right. It does not define any entity on either the left or the right. One of the gross non sqeiturs in physics texts is to continue to present equations as "definitions".

At least to first order, it appears we have arrived at a "semi-definition" of the A-potential along these lines:

> *The magnetic vector potential A is an EM energy current in 4-space, which can be swirling or linear, or can have two components where one is swirling and the other is linear. The swirling component of the A-potential is also known as the B-field, and the linear component is known simply as the "curl-free A-potential". The A-potential exhibits a remarkable property: If its swirl component is localized and confined, the remaining space where the swirling A without localization would have been is filled by a remaining unswirling linear A-potential energy current. In short, by swirl-localization the swirling A-potential can be freely 'regauged' into two separated entities, with the sum of their energy being greater than the apparent energy of the previous swirling A-potential. Hence swirl-localization is a method of asymmetrical self-regauging of the A-potential itself with the excess energy coming directly from the active vacuum.*

If we take the view that any curled A is identically a B-field, then the "natural" A is not curled, because it requires a curl operation applied to it to produce a "curled A" or B-field. Therefore the "natural" magnetic vector potential A is simply a magnetic energy current in space, since it is a vector and has direction {458}. That is a *longitudinal EM energy flow process?*[201] We shall be very interested in the uncurled A-potential; i.e., in that linear energy current in space that is uncovered and freely produced when the B-field is localized. Indeed, we shall perturb it to make a large E-field, which we intercept and use to furnish emf to the secondary circuit and power loads.

---

[201] Interestingly, around a toroidal localization zone, the uncurled A-potential does curve, but is only linearly following the curving current and the moving E-field from the moving charges in the current. In the MEG, the uncurled A-potential is even more complex, since we use each half of the toroid-like localization zone differently, with the B-flux going one direction (say, counterclockwise) in the left branch and the B-flux going in the other direction (say, clockwise) in the right branch, and with a crossover point in the middle.

Given a localized B-field so that we have an uncurled A-potential outside the localization region: If we now increase the magnitude of the A, that produces an increased linear energy flow rate outside the localization zone, in addition to increasing the B-field in the localization zone. If we decrease the magnitude of the A, that produces a decreased nonlocalized energy flow rate and a decreased localized B-field. In our view it follows that, when we oscillate the magnitude of the A-potential by any means whatsoever, we oscillate the nonlocalized linear EM energy current flow rate as well as the localized B-field. In fact, that creates a normal oscillation of the localized B-field, and also creates a nonlocalized *longitudinal wave* of electric field E by the equation $\mathbf{E} = -\partial\mathbf{A}/\partial t$, if the conditions localizing the curl operator — and hence localizing and holding separate the concomitant B-field produced by a changing E-field — continue in effect.

We have produced a mechanism for generating a nonlocalized longitudinal E-field wave without a nonlocalized B-field component being allowed to act outside a confined locality. We stress that a B-field component is produced, but remains localized in the special core material (that is one of the conditions required in the MEG).

We have also produced a mechanism for generating a nonlocalized longitudinal E-field wave with another very novel feature: the magnitude of the E-field and thus the magnitude of its energy density (its intensity) does not depend on the *magnitude of the input energy* used to perturb the A-potential, but only depends on how sharply we perturb it. Thus we have produced a mechanism for energy intensity amplification and magnification, freely. This is possible because the system is an open system far from equilibrium with the active vacuum, and specifically with the curl-free A-potential as an energy current at large in the local vacuum where it can be intercepted, collected, and used to power loads. The energy intercepted from the uncurled A-potential by the output section(s), is *additional* energy in excess of what is intercepted from the E-fields generated in core material B-field magnetic flux changes.

However, see our discussions of the giant negentropy process, earlier in this book. Any longitudinal EM "wave in 3-space" is accompanied by a longitudinal EM wave on the fourth Minkowski axis, in the time domain. EM energy does not observably propagate continuously in 3-space, since observed propagation is a series of frozen iterative observation processes a priori). The "energy flow" actually consists of a propagation in 4-space of a *continual local circulation* of EM energy from the time domain (time-polarized EM energy) to each interacting point dipole in 3-space via the negative charge of the point dipole, thence to the positive charge of that point dipole, thence back to the time domain. In a time-reversed zone, the circulation is in the opposite manner. So what spreads as the "longitudinal EM energy current in 3-space" is actually the spreading point polarization of the vacuum and this giant negentropy 4-circulation involved in every point dipole of that polarization.

We believe this previously unsuspected process is involved in the Aharonov-Bohm effect (which is a sort of polarization in the time domain), other aspects of the geometric phase, fundamental polarization of the vacuum itself, and the very notion of "propagation of EM energy through space". At any rate, the hypothesis does fit the phenomena observed to happen in the MEG, so it warrants additional careful experimental investigation as well as attention from leading theorists.

Further, the MEG is practical and produces practical electrical power, but with a *purely electrical reaction* in the output secondary coils of the transformer section.[202] Hence there is finally a very practical use for the geometric phase: It extracts additional *nonlocalized* EM energy from the vacuum (and local curved spacetime) in addition to extracting and retaining *localized* energy. Both the extra "free" nonlocalized EM energy and the localized EM energy from the vacuum can be intercepted, collected, and utilized to power practical fuel-free MEG-type power systems.

We point out that the rate of changes of all E-fields produced in the secondary and primary coils also produce B-fields proportional to the time rate of change of those E-fields in each case. These secondary B-fields are retained in the core rather than reaching out into surrounding space. Their rate of change then further produces E-fields, which pass out of the core and interact with the coils. Hence there are very novel "multiple feedforward and feedback" regenerative loops in the MEG's highly nonlinear operation, as well as chaotic oscillations.

---

[202] This follows from the localization of all B-fields in the core material — including the B-field of the permanent magnet, those B-fields produced by dE/dt operations, and those B-fields produced inside the secondary coils, etc. All E-fields produced, however, including in the changing flux of the core and in the $d\mathbf{A}/dt$ operations of the external uncurled A-potential — are free from that localization restriction and can pass out of the core and interact with the output coils of the transformer section. In short, we have produced the world's first purely electric "induction-free" magnetic transformer device. The voltage and current, measured directly across the secondary coil's ends, is in phase within 2 degrees and even that 2 degrees can be eliminated. We expect the theorists to have a field day in modeling these new phenomena.

7.5 Use of the Aharonov-Bohm Effect in the MEG

From the standpoint of electrical power systems, our own interest in the AB effect focused upon one important characteristic: the clear separation (and localization) of the B-field (the swirl component of the A-potential), leaving the remaining "natural" uncurled field-free A-potential as a free linear flow of energy current in the vacuum. This operation is iterative, and is produced by the core for every B-field produced in the transformer section. So a localized dynamic B-field makes nonlocalized dynamic E-fields, which themselves make further localized dynamic B-fields, which then further make nonlocalized dynamic E-fields, and so on. The result is a very extensive chain of feedforward and feedback field energy loops.

7.5.1 Separation of **the** Swirled **and** Linear A-Potentials

The AB effect has long been known in toroidal coils and in long solenoids. In a theoretically perfect toroid, for example, the AB effect separates and localizes the entire B-field inside the toroid, while the *curl-free* magnetic vector potential A appears in surrounding space outside the toroid. By our new interpretation and hypothesis, based on AIAS theoretical work published in the literature, this curl-free A-potential represents a nonlocalized longitudinal EM energy current in space.[203,204] Further, the curl-free A-potential is an extra flow of EM energy that can be intercepted, collected, and used while also still using the entire "normal" B-field energy localized in the core. The neat thing is that the E-field made from the

---

[203] This is addressed in M. W. Evans, T. E. Bearden, and A. Labounsky, "The Most General Form of the Vector Potential in Electrodynamics," *Found. Phys. Lett.,* 15(3), **June** 2002, p. 245-261. See also M. W. Evans et al., "The Aharonov-Bohm Effect as the Basis of Electromagnetic Energy Inherent in the Vacuum," *Found. Phys. Lett,* (in review).

[204] See also B. Lehnert and J. Scheffel, "On the Minimum Elementary Charge of an Extended Electromagnetic Theory," *Physica Scripta,* vol. 65, 2002, p. 200. In extended EM theory, the elementary charge may no longer be considered as a **fundamental** constant of nature, but is expressed in terms of the Planck constant and **the** velocity of light.

A-potential, and thus providing the actual intercepted and collected EM energy, can be made as large as desired, merely by manipulating the rise time and decay time of the pulses used to perturb the A-potential external to the core. Further, the same perturbation also perturbs the B-field flux in the core, giving rise to nonlocalized E-fields whose magnitude again depends upon the rise time and decay time of the perturbing pulses. Hence the dA/dt and the dB/dt become energy amplification causes, where all the excess F-field energy is furnished freely from the vacuum via a special kind of asymmetrical regauging and gauge freedom. In that sense, the MEG produces and applies a hitherto unrecognized form of direct field energy amplification by asymmetrical regauging.

We noted that this mechanism represents the formation of a locally curved spacetime[205] and engineering of the magnitude of the curvature itself. By freely increasing the local spacetime curvature, the appearance of additional EM energy density in the region follows *a priori.* That is, one still has all the B-field energy produced by the permanent magnet, but it is just confined to the space inside the core. All the energy one "pays for" or inputs with current and voltage to the input coil, in the normal sense, is the energy to *perturb* the localized B-field and the curl-free A-potential. However, even before perturbation to evoke energy amplification, there is already additional energy current that has appeared outside the core, where the magnetic field B would have normally extended. All the A-potential energy[206] is "extra" energy in addition to the normal B-field energy that would otherwise have appeared out there but is now confined inside the core.

---

[205] More accurately there is one specific curvature of spacetime in the core of the MEG, representing the confined magnetic field B (the localized swirling A-potential), and there is another different curvature of spacetime outside the localization zone, filled with the nonlocalized curl-free (non-swirling) A-potential as a nonlocalized linear energy flow in space. Further, in the MEG we freely change and increase the magnitude of those spacetime curvatures, by the *rate of change* of the input energy rather than by its *magnitude,* and hence we easily increase the magnitude of the energy density of local space both inside and outside the core. That is the fundamental principle of the MEG"s energy amplification (free regauging).

[206] Some scientists even deny that the curl-free magnetic vector potential has any energy! We answer that it produces energetic effects upon charged particles, hence must either contain energy itself or direct and gate the interaction of some local vacuum energy with those charges. In the MEG, the uncurled A-potential is oscillated, which does not appear to yield a *transverse* EM E-field wave at all. Instead, it appears to yield a *longitudinal* E-field wave with an associated scalar KM wave in the time domain. We also explained what appears to happen to the concomitant B-field wave produced by any changing E-field in the secondary

Further, the uncurled A-potential outside the core reduces its magnitude only inversely as the radial distance, whereas the normal B-field that would otherwise be there in the absence of localization would have reduced its magnitude inversely as the square of the radial distance. This far less rapid fall-off of the magnitude of the nonlocalized curl-free A-potential than the former nonlocalized magnetic field B can result in a remarkable increase in communications range — when a normal EM field antenna with oscillating EM field transmissions is compared to a curl-free A-potential antenna radiating the same power but as curl-free A-potential oscillating transmissions. Golden[207] has applied that effect for long-range communications.

With the application *of the free* Aharonov-Bohm effect produced by the core material and permanent magnet combination, rigorously there has appeared much more available EM energy from the local vacuum than the energy one inputs to the device as one's input energy "payment". Again, this is because the system is an open system far from equilibrium with the active vacuum processes such as the appearance of the uncurled A-potential and the iterative appearance of powerful extra B-fields and E-fields. The rise time and decay time of the input perturbation pulses produces an energy amplification effect both in the core and in space outside the core. When one utilizes this extra uncurled A-potential energy, as well as the now-confined B-field energy, as well as the extra B-fields and E-fields appearing from the iterative processes, then one can extract and use more energy than one himself "paid for" or input to perform the perturbation. Indeed, one can easily extract and use more energy from the curl-free A-potential alone, than one has input. By simply controlling the rise time and decay time of the input pulses, the magnitudes of the resulting E-fields formed in the uncurled A-potential (and in the perturbed trapped B-field perturbations inside the core) can be controlled at will.

(output) coils of the transformer section, etc. The core material withdraws and holds localized, all such magnetic fields formed in the internal MEG core processes.

[207] In the late 1970s Frank Golden demonstrated such an uncurled A-potential antenna which attained a range of 20 miles for a tiny CB radio, compared to a range of only 1 mile for the same CB radio with a normal EM field antenna. The energy density of the potential drops off inversely as the distance, while the energy density of the field drops off inversely as the *square* of the distance.

We also point out that all these amplified E-fields produced by multiple actions have both a conventional Poynting energy flow component and an unaccounted, much larger Heaviside energy flow component. Thus the total energy amplification factor can be very large (several orders of magnitude). With efficient interception and collection, in the future we expect to be able to produce at least 100 kilowatts of power out of the same size core and buildup now producing 80 watts or less in a highly nonoptimized set of laboratory experiment MEGs.

We again call the reader's attention to our previous discussions in this book, showing that all EM energy in EM circuits comes from the vacuum anyway (particle physics view) or from the time-axis (relativistic view). This has previously been hidden by the failure of classical electrodynamics to solve the source charge problem, which we also solved in this book after our paper {12} in 2000. Circuit theorists avoided it by indirectly assuming the source charges freely created from nothing all the EM energy in their fields and potentials. The use of the assumed fields and potentials and their Poynting energy was calculated, but never was the source of those fields, potentials, and their energy presented or accounted.

7.5.2 Using the Uncurled A-potential as a Linear Energy Current

A very simple equation allows utilizing the extra nonlocalized A-potential energy, even though it has no curl and therefore no magnetic B-field. That is $\partial \boldsymbol{A}/\partial t = -\boldsymbol{E}$. This equation means that, if one perturbs that large field-free A-potential outside the toroid, it produces an E-field, which we have argued must now be a longitudinal EM wave due to the perturbations *if the B-confining operation is still imposed.* By oscillating the A-potential perturbations, one produces an oscillating E-field that is also an oscillating longitudinal electric E-field wave without an accompanying B-field wave.

The oscillating B-fields in the core also produce E-fields proportional to $\partial \boldsymbol{B}/\partial t = -\boldsymbol{E}$. These extra E-fields are in phase with the E-fields produced by the perturbed external A-potentials, considering the wavelength of the frequencies at which the MEG is operating (30 to 80 kHz nominally).

Interestingly, the time-oscillating rate of change of the E-field in this longitudinal E-field wave does produce a magnetic B-field, but it is confined to only the core material and not in the nonlocalized external spatial region *because of the localization capability of the core material.* The core simply changes its permeability and holds the additional B-fields and their flux in there, thus forming additional uncurled A-potential outside the core. The E-fields produced by variations of the core B-field flux is not confined, but freely passes out of the core material

If that B-field (curled A) is sharply localized by an ongoing localization capability, the longitudinal E-wave has its produced magnetic B-wave component stripped from it and localized. In that case, the process produces a purely longitudinal E-field wave outside the localization region — with the possible exception that a longitudinal B(3) field wave component pioneered by Evans {485} *may be produced as well. That is left as an open question presently unresolved in our MEG experiments. We tentatively believe that the B(3) field wave component is in fact produced, but also forcibly localized in the core along with the magnetic field B. If so, its perturbations will also contribute to producing extra E-fields.*

See Figure 7-5. In the MEG, the localization is accomplished as a unique function performed freely by the special nanocrystalline layered core material. So contrary to the case of the solenoid or toroid, one does not to have to "pay" any EM energy to the localizing component to obtain the localization function itself.



Figure 7-5 Diagrammatic drawing of the MEG.

Further, if one deliberately uses a nearly rectangular perturbing pulse that has very sharp rise time and very sharp decay time, the nonlocalized E-fields, resulting localized secondary B-fields, and resulting nonlocalized secondary E-fields produced can be made very large, with rapid rates of change also. In other words, the magnitudes of the nonlocalized E-fields and localized B-fields produced can be adjusted at will, including in their higher orders. The magnitudes of these evoked fields do not depend on the *magnitude* of the input perturbation energy, but on its *rate of change*. This is very important, because it means the MEG permissibly achieves energy magnitude increase in its nonlocalized output E-field waves by simple instantaneous power deliberately prepared in its low-energy input perturbation waves.[208] In short, the motionless electromagnetic generator uses perturbation of the Aharonov Bohm effect as an energy amplifying mechanism.

This also affects all the iterative processes, hence all the other E-field waves produced outside the core material.

With the localization process remaining and ongoing (simply because the core material remains), the B-field continues to be stripped away, leaving the perturbed A-potential to produce a longitudinal E-field wave (ignoring the possible presence of a B(3) field also). In the MEG transformer section, the output (secondary) coils are wound around the nanocrystalline core that performs a B-field and B-flux localization within the core itself. Hence a purely net E-field interaction occurs with the electrons in the secondary coils, and the output of these coils is an output having the output voltage in phase with the output current.[209] The AC current in the secondary coils does in fact still produce magnetic field B-flux and B-waves in them, but the core material draws the extra B-flux and B-waves inside and localizes them within the core. The fact that localization is *not quite* 100% at the imperfect junctions of the ends of the permanent magnet and the core material, gives a tiny bit of leakage of

---

[208] It also means that the MEG operation is highly nonlinear, with very extensive feedforward and feedback field transduction loops. For the MEG, its scale-up, mathematical modeling, and engineering simulation are not simple things at all, but highly complex. In addition, control and stability are more complex, since one must utilize nonlinear oscillation theory (including chaotic oscillation theory) as well as nonlinear oscillation control theory. In addition, a higher group symmetry electrodynamics is required for the modeling and simulation. Consequently, because of these considerations and the geometric phase aspects, as well as the additional close-looping considerations for self-powering operation, an expensive physics lab must be established as well as the usual electrodynamics laboratory aspects. The result is an expensive final research and development program required to complete the MEG to final production prototype units, ready to start rolling off the assembly lines. A minimum capitalization of $20 million is required.

[209] In the actual lab experiment MEG, there is a slightly imperfect junction between the ends of the permanent magnet and the core material. This results in a very tiny bit of leakage of nonlocal B-field —just enough to produce a 2° phase shift between the voltage and current in the secondary coil's output. With a better junction, this phase shift can be further reduced or eliminated.

B-field, so a tiny B-field component does escape, interact, and generate the *2%* or so variation from the complete in-phase condition of the secondary output voltage and current. Again, that can be further reduced or eliminated by improving the junction.

So essentially there is a purely electric field interaction with the electrons in the output coil current of the MEG, hence the result that the output current is in phase with the output voltage — something previously unheard of in a simple secondary coil of a transformer. This is a major practical macroscopic application of the Aharonov-Bohm effect and therefore of the geometric phase.

7.6 Collection of Field Energy in the MEG

To collect and use EM energy in a power generating system, first the EM energy must be evoked from local spacetime (the local vacuum) by the broken symmetry of the source charges and dipoles in the circuit {12}. In the open system far from equilibrium in the resulting EM energy flow, the operator must usually pay for (i) the energy required to *initially* produce the requisite source dipolarity and (ii) the energy required to perform necessary switching and control functions, unless close-looping is incorporated. Using the permanent magnet as a source dipole in the MEG, and using the special nanocrystalline core material to generate the Aharonov-Bohm effect to furnish excess energy from the vacuum, the MEG operator does not have to *furnish* the evoked and available field energy at all. So the first "payment" is totally avoided. Further, the magnetic dipole is not destroyed by passing magnetic flux back through its back mmf. No additional input energy is required to continually restore the source dipole, since it is never destroyed.

In an open-loop MEG system, the operator only has to pay for the second part: the switching and control function energy. In later closed-loop MEG systems, a method of controlled and positive feedback has been developed so that, once the system is up and operating and powering its load, the necessary switching and control function energy can be siphoned off the output and fed into the input in governed fashion, first being transduced into positive energy input form. Once the process is properly synchronized and governing properly, the operator can throw a switch for feedback and transduction, and the unit will be "self-powering", or "fueled entirely by **the** local vacuum energy", so to speak.

Let us consider the open-loop MEG system we have presently attained in a series of embodiments.

The total emf force F collected from a given nonzero electric field E, e.g., depends only upon the amount of available intercepting charge, by the simple equation $F = Eq$. Similarly, from any potential ϕ the amount of collected EM potential energy W depends on the amount of intercepting charge q, by $W = \phi q$. Hence in the MEG a legitimate COP>1.0 system is possible if (i) more energy is collected and used from the evoked EM energy flow than is input to gate that energy flow's appearance from the active environment, and (ii) none — or appreciably less than half— of the energy collected in the circuit is used to destroy the source dipolarity.

By invoking the AB effect in a local region, the vacuum contributes additional energy density in the space outside that region, and that energy density can be sharply perturbed so that substantial field energy amplification appears by asymmetrical regauging. The excess energy to provide COP>1.0 performance is freely furnished from the active vacuum (and from the local curved spacetime) {38b, 38c}. The excess energy can be intercepted in the perturbed curl-free A-potential region outside the transformer section, collected, and used to power additional loads, in addition to being intercepted in the transformer secondary region to power the secondary circuit and main load.

Similar contributions of extra energy and extra energy collection outside the core localization region occur for the iterative processes also.

At the same time, the B-field inside the core material is perturbed, but the core material self-varies its permeability to adjust to the additional magnitude of the perturbed B-field. The production of any B-field oscillation inside the core does produce an electric field E, which is not localized in the core. Consequently, energy from the perturbed core-localized B-fields is transduced into nonlocal E-field energy, passing out of the core and interacting with the output secondary coils of the transformer section in purely electric field fashion.

Because of the purely electrical interaction, the voltage and current output from the secondary coils of the transformer section are in phase, and not 90° out of phase as in a transformer. The actual 2° experimental phase shift of current with respect to voltage is a measure of the slight inefficiency of the junctions of the permanent magnet ends with the B-localizing core material.

In the MEG, we are using a novel new kind of component: an *external-induction-free cored inductor*, which might alternately be called *a purely electrical inductor — at least externally*. In short, the inductive action remains localized in the core, while the electrical action escapes the core and interacts with the coil to drive the current electrically. So here is another excellent, novel, and practical use of the Aharonov-Bohm effect and the geometric phase: Eliminate the inductive reaction of a coil's output, and transduce it into a purely electrical action. At this writing, we are preparing to file a separate patent application upon this latest application and process, and it will already be filed by the time this book is published.

We accent that any field or potential, once made, already involves an ongoing giant negentropy and overunity process {486}, as we previously discussed in this book. Simply calculate how much energy it requires to separate and form the source charge — which can be as simple as charging a tiny little sphere — and recognize that the field formed by that charge is an altered energy density of surrounding space and a polarization of the vacuum. Once the charge is formed, the corresponding alteration and sustaining of spatial energy density change and vacuum polarization freely moves radially outward at the speed of light from the charge, from the very moment it is produced. So a steady flow of observable EM energy is speeding out in all directions from the source charge. An enormous change in the energy density over that external spatial region surrounding the source charge occurs and spreads steadily, moving radially outward in all directions at speed c.

Hence a magnificent and rapidly extending curvature of spacetime — which energetically acts upon any available charged matter therein, by conventional general relativity — is formed and spreads outward in all directions from any source charge, once formed. How much effect on charged matter is exhibited by this freely created and spreading spatial EM energy density change, depends only on the amount of interacting/receiving charged matter in that surrounding space that is available to interact with the energy of the new fields and new potentials.

If **the** source charge or source dipolarity (in this case, primarily the magnetic dipole of the permanent magnet) is left alone and not destroyed, an unlimited amount of energy can be intercepted and discharged from a local load, again and again, from the charge's surrounding field or potential because the energy in the field and potential is steadily replenished from the active vacuum. The only problem is discharge the collected energy in the load(s) so as to leave the original source charges (the magnetic poles) inviolate, and not to destroy them. The MEG accomplishes this function.

This also rigorously follows from the gauge freedom axiom of quantum field theory. Consider this: the ability to freely change the potential — assumed by all electrodynamicists — can be applied directly to the load to potentialized it without any current moving, if there exists a somewhat lengthy electron gas relaxation time in that part of the load that is potentialized. After potentialization, one can switch the source of free potential away, and complete the load circuit separately, so that the excess potential energy is dissipated from the load, powering it. In that case there is no dissipation of the primary source dipole. *Gauge freedom already assumes one can produce EM energy from the local vacuum freely, anywhere and at any time.* In real life, one has to pay a little for the switching, but not for the energy input itself.

Why the scientific community for decades has fiercely opposed the funded experimental investigation of the implications of gauge freedom is quite inexplicable.

As can be seen from the conservation of energy law alone, in theory energy can be continually intercepted and collected from these free fields and potentials, once the source dipolarity (or source charge) creation has been paid for. Further, by applying gauge freedom to potentialized the load without energy dissipation, with a little adroit switching the collected energy can then be dissipated entirely in a separated external load circuit, so that the free potential energy completely exits that circuit without re-interacting with the source dipole and its back emf or mmf.

We predict that the above application of gauge freedom will eventually power most of the world's electrical systems, when the scientific community gives up its present "ostrich position". Once the engineers can build it, the scientists do not have to agree.

That such is not done in our conventional circuits is purely due to the limited vision of the scientific community and its refusal to fund appropriate research. To date, it has not even recognized what actually powers every electrical circuit, or that a common practice (the closed current loop circuit) has eliminated COP>1.0 and self-powering Maxwellian power systems for more than a century. The entire electrical energy crisis hurtling at the nations of the world is due entirely to the shortsightedness of the scientific community, particularly since 1957.

Once the energy is pouring (transmitted) from the dipole and out of the terminals of the generator to fill space around the external conductors, then a straightforward energy transmission and reception problem exists. The source dipolarity produces the steady emission and flow of energy filling space around the circuit. In the "receiving external circuit" the surface charges and their fields must intercept some of that available EM energy flow and diverge it into the conductors to power the circuit electrons. The intercepted and diverged component entering the circuit is the Poynting component, while the nonintercepted and nondiverged component missing the circuit and usually wasted, is the extra Heaviside component.

Fortunately, every source dipole pours out enormously more EM energy than our feeble conventional circuits intercept and catch to provide the Poynting calculations. So to produce COP>1.0 in the MEG, all we have to do is insure that we have (i) a mechanism easing the interception and collection process, and (ii) sufficient "antennas" containing sufficient conduction electrons (and their fields) to intercept and collect more energy than we pay to make the source dipole and perturb it. Since we pay nothing at all to make the source dipole (which is the permanent magnet), and since the magnetic flux back through the permanent magnet does not destroy the dipole, then all we have to pay for is the perturbation and for switching and control.

The resulting field energy generated outside the core localization region is primarily a function of the rise and decay times for the input perturbation pulses and not the energy of those pulses. From a little input energy with fast little changes, we can easily generate very powerful oscillating E-fields and provide dramatically increased "antenna collection" area with **the** necessary magnitude of intercepting charge. It rigorously follows that COP>1.0 is easily obtainable.[210, 211]

[210] Again, for the MEG, changing and controlling the rise time and decay time of the input pulses is a method for directly engineering and controlling the general relativistic curvature of the local surrounding spacetime, because it controls the magnitude of the E-field that is created by $\mathbf{E} = -\partial\mathbf{A}/\partial t$ from the curl-free A-potential outside the core. This also directly engineers and controls the magnitude of the polarization of the local active vacuum. That simple fact allows the use of a unified field theory operation, with a net energy interchange between the system and **the** local active vacuum. To understand the MEG, one must think in terms of the *supersystem.*

[211] All EM energy at any point in space must have been "gated" from the time-domain and it must return to the time domain (as, e.g., by the source charge for it). It **requires** quite a shift of one's mind to realize that all 3-space energy (such as "energy at each point in a potential") involves a gating process and a giant negentropic 4-circulation of EM energy ongoing at each point dipole. Much of the extraction of **energy** from the vacuum has been hidden by thinking in terms of "inputting energy" instead of "inputting or arranging energy flow gating" by the source charges and sourcedipoles.

The MEG is an open system far from equilibrium with its active environment (its active local vacuum and its active local curvatures of spacetime). By attending to the interception and collection part of the overunity problem, the MEG can permissibly collect and use more EM energy to power its loads than one oneself has to input to it. In short, one only has to input a little switching and perturbation energy with properly shaped waveforms, to generate very powerful fields and appreciable field energy available for collection and use. With sufficient collection mechanisms in place, the unit easily produces COP>1.0. Then with proper closed-loop principles implemented, the MEG can be self-powering.

7.7 Experimental Path to Development of the MEG

In our experiments with the Radus effect previously discussed in Chapter 6, paragraph 6.4.5, we had already done extensive work with switching magnetic fluxes for less switching energy than can be intercepted from the switched flux. We had also experimented with various cores for transformer and coil variants, including eventually the new layered nanocrystalline cores.

In our experiments, we noticed a remarkable thing. With certain modern nanocrystalline core materials, and using a permanent magnet to provide B-flux, we found that *the core material would extract and hold essentially all the permanent magnet's B-flux inside the core.* Field measurements right against the outside of the poles of the powerful little neodymium-iron-boron magnet itself showed very little B-flux spilling out into space! In short, we had discovered how to make a magnetic system that *nonlocally* propagated only the uncurled magnetic vector potential A, without any operator energy input. We realized we had discovered a marvelous and free way to freely obtain an excellent Aharonov-Bohm effect, similar to the way a nearly perfect toroid would localize the B-field inside the core, with the uncurled A-potential appearing in space surrounding the toroid. The advantage of our approach over the toroid was that we did not have to furnish any current and voltage to obtain the localized B-flux and the non-localized curl-free A-potential energy.

Further, if we perturbed the B-field flux in the core, we consequently perturbed the uncurled A-potential in space surrounding the core. From both sources — the perturbed B-flux in the core and the perturbed

A-potential outside the core — we could produce very large E-fields and concomitant very large voltages capable of driving more "power" through the secondary coils of the transformer section than the power required to perform the switching and perturbation.

We could easily prove this by perturbing the localized B-flux (and the concomitant surrounding uncurled A-potential automatically) with weak energy. We proved that increasing the rate of the rise time and decay time of even a weak input EM energy perturbation could produce quite large E-fields, including 1,000 to 5,000 volts (or even 20,000 volts!) appearing in the secondary coil if desired. We also proved another thing: *the special nanocrystalline core material in some buildups self-adjusted its permeability, continuing to localize the perturbed and alternating B-fields and their fluxes while freeing the resulting E-fields and passing them out of the core.* In short, the permeability of the specially selected core material automatically adjusted with the perturbation of the localized B-flux and nonlocalized A-potential, so that all the oscillating B-flux remained localized in the core. Further, the highly layered nanocrystalline material produced essentially no eddy currents at all, hence no heating, even in the presence of dramatic B-flux oscillation and dramatic E-field intensities in the surrounding uncurled A-potential space and in the output (secondary) coils of the transformer section of the MEG.

The absolute proof that the core changed its permeability was in the lack of a phase lag between voltage and current in the output from the output coils. Here a remarkable thing was observed: the output current was in phase with the output voltage, within about 2°. In short, under certain circumstances the output coils wound around the nanocrystalline core would exhibit essentially a purely E-field interaction, with only minuscule B-field leakage — something deemed impossible in the typical electrodynamics textbook. This meant that the excess E-fields produced by the perturbed A-potential in space outside the core also reacted with the output coil's conduction electrons in a purely electrical manner! This was because the B-fields locally produced in the output coils by the interacting changing E-fields, *were in fact instantly drawn into the core material as they were produced, and were held there so they did not react in magnetic fashion with the electrons in the output current from the secondary coils.*

So this is a dramatic localization of Faraday's law of induction. Consequently, one entire group of embodiments of the MEG uses a purely electrical interaction with the secondary (output) coils of the transformer section.[212] Or more exactly, the core material draws in all the magnetic fields from the reactions of the output coils, leaving only the electrical reaction outside the core — including in the coil conductors, which obviously are wound outside the core material.

On the other hand, the perturbed localized magnetic B-flux inside the core material did produce the normal E-field to be expected, as a function of the time-rate of change of the B-field. Such an E-field is not localized in the core material, but extends outside the core and interacts with the electrons in the output secondary coils of the MEG's transformer section. Again, the magnitude of this E-field is a function of the time-rate of perturbation of the localized B-field flux in the core.

The nanocrystalline core also has excellent high frequency response, with negligible eddy currents. Thus we can "fine tune" the engineering of the rise time and decay time of the input perturbation pulses.

Hence we accomplish several kinds of "gated energy amplification" in the MEG: (i) the amplified magnitude of the external E-field interacting with the external collectors (such as the output secondary coils) due to perturbation of the nonlocalized external uncurled A-potential, (ii) the amplified magnitude of an additional E-field interacting with the external collectors (such as the output secondary coils) due to perturbation of the localized internal B-field flux inside the core material, (iii) a large number of additional derivatives of higher order B-fields and E-fields are formed and utilized, and (iv) adding additional collectors (either coils wound on the core or external "receiving antenna circuits" produces additional power for heavier loads, for a given perturbation input.

We had exhibited a cored output coil with a remarkable adaptation of the AB effect. Essentially the output of the secondary coil was driven by the large electric field component created from the uncurled A-potential perturbations *and* by the large electric field component created from the B-field flux perturbations inside the core. This peculiar transformer-like section operated from the E-field fluxes emerging or produced *outside* the transformer core material, rather than from the magnetic field flux being produced and oscillated *inside* the core material itself.

---

[212] Again we accent that the magnetic field reactions do occur, and the B-fields are in fact produced. But the resulting B-fields are also extracted into the core material and localized therein. Even the magnetic B-fields produced in the input and output coils themselves, is so localized and not allowed to interact with the electron currents through the coils to produce the conventional 90° phase lag between voltage and current.

Obviously we had found a remarkable but legitimate COP>1.0 process and embodiment — in fact, a whole set of them. We had also invented a new kind of "transformer" or energy generator-transducer.

From that we progressed to discovering ways to a dual use of both the perturbed B-flux in the core and the E-fields from the perturbed A-potential outside the core. To first order, that turned out to be fairly simple: any changing B-flux inside the core material and thus inside the output (secondary) coils of the transformer section, produces not only B-field which is held and localized, but also the changes of this local "pinned" B-field further produces E-field oscillations which are not pinned in the core. Hence the electric field half of a normal transformer action could and did occur in the secondary coils, but the magnetic field half did not occur *in the coils themselves*. The MEG used and uses a nearly pure E-field interaction in the output coils of its transformer section secondary, where that net interacting E-field comes from a variety of E-field generating mechanisms.

We filed our first patent, and then filed a second patent application soon after. Presently we are preparing to file our third and fourth patent applications on additional phenomenology and mechanisms uncovered in our experiments. As we are writing this section, our first patent has issued {37}.

In the view of the present author, we have uncovered a remarkable new application of the Aharonov-Bohm effect and the geometric phase, one that is practical and eminently useful in novel new electrical power systems.

7.8 Additional MEG Functions

Figure 7-6 diagrammatically shows the core material inside the input coil for either open-loop operation using an external power supply or closed-loop (self-powering) operation using clamped and governed positive feedback. As can be seen, the B-field and B-field flux are confined to the core material (which is in the form of a closed transformer coil path, as shown diagrammatically in Figure 7-5). The external space surrounding **the** core material is filled with the uncurled A-potential, due to the Aharonov-Bohm effect being imposed by the core material. The two leads from the input coil are shown at the bottom of Figure 7-6.


NOTE: One input coil required. Additional input coils may be used, to increase feedforward and feedback intensity and thus increase gain.
A (field-free)
Coil
B
Magnetic field retained inside core material
Input coil (input energy)
Microcrystalline core material
V, i, E from external signal generator or from a clamped positive feedback fraction of the output

Figure 7-6 Input coil for open- or closed-loop **operation.**

We pulse the input coils with nearly rectangular pulses each having a sharp leading edge and a sharp trailing edge, so that the resulting rapid time-rates of change of the two edges create very large perturbations of the B-flux in the core and of the A-potential outside the core. The large E_2-field resulting from the fast rate of change of the perturbed B-field in the core is not localized, but appears in space outside the core. In addition, an E_3 field created directly in the coil itself also appears in space outside the core. In addition, the sharply perturbed A-potential outside the core creates a third large E_1-field in space outside the core. The net E_t-field in the surrounding outside space is the vector summation of the E-fields produced by these processes, or to first order (neglecting the further differentiations)

$$\mathbf{E}_t = \mathbf{E}_1 + \mathbf{E}_2 + \mathbf{E}_3 \qquad [7\text{-}1]$$

We also may adjust the pulse width to generate a further Lenz law effect, increasing the three component fields E_1, E_2, and E_3 if desired. To do that, the pulse must be narrow enough to suddenly decay while each of the fields E_1, E_2, and E_3 is still rising and not yet reached maximum. As can be appreciated, considerable pulse shaping and timing can be adjusted for optimization of the output voltage, current, and power when interception and collection from E_t is accomplished in the secondary coils. In addition, it can be appreciated that slightly differing materials delay times do occur in the production **of** $\mathbf{E}_1$, E_2, and E_3. Hence there is appreciable optimization that can be and is accomplished on a given MEG variant and build-up type.

More complex waveforms of various shapes can be used to further optimize the output. It is also possible to accomplish further optimization and control by adjusting the shapes and timing of the feedback signals in the case of the closed-looped MEG system. For the externally powered open-loop version, additional optimization and control can be achieved by adding additional simultaneous pulses fed into the input coils in various fashions.

In addition, the response of the output coils produces feedback into the core material, into external space, and into the input coils. These in fact provide three more E-field *return* or feedback inputs, so that the total feedback input is

$$\mathbf{E}_f = \mathbf{E}_4 + \mathbf{E}_5 + \mathbf{E}_6 \qquad [7\text{-}2]$$

Without doing the more complex iterations for this feedback and feedforward set of loops, to first order the total input E_I to the input coil may be considered to be

$$\mathbf{E}_I = \mathbf{E}_t + \mathbf{E}_f \qquad [7\text{-}3]$$

Equations [7-1], [7-2], and [7-3] are for simple analogy only; in the real MEG, full nonlinear feedforward and feedback analysis techniques must be utilized because of the iterative operations, and much more sophisticated optimization techniques are appropriate. Also, chaotic oscillations can and do appear, and techniques for control of such oscillations are indicated, particularly along the lines indicated by Fradkov and Pogromsky {487} without use of probability etc. Quoting:

> *"1. There is ... great benefit of using the modern nonlinear and adaptive control theory. ...2. There is no need to distinguish periodic and chaotic behavior. Accurate control is possible without accurate prediction. ...3. There is no need to define chaos in order to control it. ...4. There is no need to use probability in order to control systems with seemingly random behavior."*

For any given MEG build-up design, one experiments with these optimization and control factors and mechanisms to provide the best performance, and to provide rock-steady performance.

Figure 7-7 shows the output coil for either open-loop operation from an external power supply or closed-loop (self-powering) operation using clamped and governed positive feedback. Here the situation is partially reversed. There are three major inputs to the output coils, and these are (i) the external input from the total outside E-field, (ii) the internal input from the perturbation changes in the confined magnetic flux inside the core through the output coils, and (iii) the ensuing feedforward and feedback from all E-fields.


A (field-free)
Coil
B
Magnetic field retained inside core material
Input coil (input energy)
Microcrystalline core material
V, i, E to external loads in open loop operation, and also with a fraction fed to input for closed loop operation and "self-powering".

NOTE: One input coil required. Additional Input coils may be used, to increase feedforward and feedback intensity and thus increase gain.

Figure 7-7 Output coil for open- or closed-loop operation.

Again, this is simply an easy way to visualize the situation to first order. In the real case, sophisticated feedforward and feedback analysis is required and utilized. Optimization usually consists of two steps: (1) the simpler, more direct optimization techniques such as adjusting pulse width, pulse rise time and decay time, actual pulse form, etc., and (2) the deeper and more complex optimization arrived at from detailed feedback and feedforward loop analysis as well as nonlinear oscillation and nonlinear control theory analysis.

In the actual optimization analysis, the feedback and feedforward loops are mathematically endless and thus should be optimized for quick decay and stability. On the other hand, the MEG also has the ability to self-oscillate over the entire unit, in which case the feedback and feedforward loops are optimized for stable self-oscillation of the entire unit. The self-oscillating

MEG is permitted since it is an open system far from equilibrium with its active environment.

So if desired, an entirely different kind of optimization can be utilized for self-sustained nonlinear oscillation and closed loop operation. Because of the gain achieved in the large E-fields produced by the perturbed uncurled A-potential in space surrounding the core, there is sufficient excess energy collection available in the output coils to use the available feedback and feedforward loops in the system itself to achieve system self-oscillation. The system can be operated as a self-oscillating open system freely receiving excess EM energy from its active environment — the local active vacuum, local curvatures of spacetime, and local freely furnished uncurled A-potential and resulting nearly free E-fields from the A-potential's perturbations). As we are writing this, our experiments are now in this direction, and we are preparing the material for filing a formal patent application on this additional process. The patents will be filed, of course, by the time this book is published.


Magnetic field inside coil (curved spacetime)
INPUT COIL
Curl-free A-potential outside coil (curved spacetime)
Clamped Positive Feedback Control
Closed loop operation position
Signal input (elec)
SW
Open loop operation position
Magnetic field inside material flux path (curved spacetime)
Magnetic field inside permanent magnet (curved spacetime)
Magnetic dipole in permanent magnet (giant negentropy and ordered curved spacetime)
OUTPUT COILS
Magnitude of mag dipole's broken symmetry in vacuum exchange
Vacuum A-flow energy interacted with by mag dipole (curved spacetime)
curl-free A-potential from permanent magnet (energy flow extracted from curved spacetime)
EXTERNAL ELECTRICAL LOADS
BLOCK A'

Figure 7-8 Energy gain process using feedforward and feeback subprocesses

A highly simplified block diagram of energy gain process using feedforward and feedback subprocesses is shown in Figure 7-8. As can be appreciated from this high order diagram, the actual feedforward and feedback loops are extremely complex, and a great deal of complex analysis is required for a self-oscillating, stable, controlled system. We also stress that control measures to insure and hold stable self-oscillation must be included in the overall features implemented in this self-powered, self-oscillation variant of the MEG. Not only must we use chaotic oscillation techniques to achieve the self-oscillation, but also we must use advanced techniques for stable control of such nonlinear oscillations, as indicated by Fradkov and Pogromsky {487}.


Output
Output
N
S
Output
Output
Clamped feedback control
SW
Input if open loop operation desired

Figure 7-9 Typical MEG embodiment application on site.

In Figure 7-9, we show a typical diagrammatic embodiment envisioned for the MEG in a household, using a large MEG to later be developed. For interim installations, the single large MEG will be replaced with an array of MEGs together with a synchronizer, as shown in Figure 7-10.



Figure 7-10 MEG self-powering array concept for increased powering applications.

Figure 7-11 shows a MEG unit where additional special collection antennas feeding separate circuits are employed in an "outrigger" fashion. One major advantage of this configuration is that the complexity of close-looping and its control are materially reduced, although the complexity of the MEG build-up and stabilization is increased. Another advantage is the *ease* with which close-looping for self-powering operation can be achieved, as shown in Figure 7-12. In this case, the external antennas are collected to independent output circuits (not shown) in the output section, and each of these independent outrigger outputs is a COP<1.0 circuit if we count the perturbed A-potential energy input as an "operator's" input. Completely normal clamped positive feedback can be used with sensing and governing, to allow self-powering and self-adjusting to varying loads. The outrigger embodiment can be made to almost entirely avoid the Dirac sea hole current problem.


Governor
Interaction farther out, of curl-free A-potential and E-fields
External E-field antennas, each with its own separate circuit and separate load. For each circuit, ξ < 1.0 and COP >>1.0.
(LOADS)
Close-in interaction of curl-free A-potential and E-fields
External Power Supply
Input Power
MEG
OUTPUT

Figure 7-11 MEG unit with outrigger antennas for extra energy collection.


A
B
Input power
N
S
L1
L2
L3
L4
L5
A
A
B

Figure 7-12 Use of outrigger antennas for damped positive feedback method of close-looping.

As can be seen, the MEG has many possible configurations and embodiments, each of which has special advantages and uses. One of the embodiments we discussed is the deliberate use of self-oscillation forced by the feedforward and feedback loops. That is a separate embodiment, and capable of a very high power per pound ratio, but it also requires more sophisticated sensing and control techniques.

7.9 In Conclusion

By the time this book is published, Magnetic Energy Ltd. is hopeful it will have achieved its major funding requirement, and be well along the way to completing the research for full production and marketing of MEG units on the world market. We have arrived at that part of development — the need for substantial funding (several tens of millions of dollars) — where every previous COP>1.0 EM power system has died. We intend to do everything within our power to see that we obtain the funding, finish the complex research task, and get the MEG onto the world market.

For additional information on the MEG and on its preliminary replication by Naudin, the reader is referred to other technical articles {488} and to Jean-Louis Naudin's website.[213] Actual measurements for one of Magnetic Energy Ltd.'s MEG test units is given in reference {488a}. The MEG patent {37} shows the variation of COP for a test MEG with various conditions. Curves for Naudin's measurement of the performance of his replicated MEG unit are given on his website.

The MEG project is a most interesting project, because of the involvement of so much advanced physics and several different physics areas, as well as the prerequisite for higher group symmetry electrodynamics. Once funded, we are confident we succeed in crashing through the barriers and getting working MEG power units — including self-powering MEG units — on the market. We also believe the MEG will represent a substantial contribution to alleviating the coming worldwide energy crisis. Hopefully it will materially hasten the growth and evolution of the present highly centralized — and terribly vulnerable — national energy infrastructure into a highly decentralized — and much less vulnerable — national energy infrastructure. We also believe it will provide a great contribution to helping alleviate global warming, reducing pollution of the biosphere, and reducing the production of hazardous wastes. If so, it will be a continuing contribution, not only to humanity today, but also to generations yet unborn.

---

[213] Naudin's website MEG material and information is at http://jnaudin.free.fr/html/meg.htm. Particularly see his Mark III replication, shown powering a light on that webpage.

Chapter 8

Approach to Antigravity

[Large-scale antigravity exists] *"...baryonic, ordinary matter—the stuff of stars and of people—makes up just over 4% of the energy and matter in the universe. ...about 30% of the stuff in the universe is dark [unobserved] matter. The remaining two-thirds, theorists believe, is a mysterious 'dark energy' or 'quintessence'—a large-scale antigravity-like effect that is making the universe expand ever faster.... "* [Charles Seife] {489}.

[On the nature of the vacuum] *"...the (electromagnetic) vacuum is the ground state of the quantized electromagnetic field. ...The Dirac electron vacuum is that state with all negative energy electron states fully occupied."* [Aitchison] {490}

[On forces and how charge exists] *"Vacuum polarization, in general, alters the effective force law. Forces, in quantum field theory, are understood as being due to the exchange of virtual quanta ...In the case of QCD and QFD, ... a crucial new feature is that the force-field quanta themselves carry the 'charge' of the force-field, i.e. it is as if the photon of electromagnetism carried electromagnetic charge."* [Aitchison] {491}

[Possible gravitational circuits] *"There is an implication ... that gravitational excursions might be controllable by gravitational 'circuits', analogous to electronic circuits, which could lead to a controllable form of negative gravity."* [Robert Neill Boyd] {492}.

[Gravitational circuits] *"The supersystem concept utilizes a unified fields approach so that specialized electrical circuits in COP» 1.0 condition generate strong Dirac sea hole currents of negative energy in the immediate local vacuum. Thus a strong negative energy field is formed surrounding the circuit and changing the curvature of local spacetime as an action by the source*

> *circuit. This produces a direct antigravity field around the circuit or physical system, acting upon the mass of the system. The net gravitational interaction by that circuit or physical system is therefore the summation of the local positive gravitational field and the new local negative gravitational field produced by that negative energy field."* [T. E. Bearden, correspondence to a colleague, February 2002.]

> [On the multiplicity of spacetime curvature components] *"The full mathematical expression for the curvature of four-dimensional space-time ...is given by something called the Riemann curvature tensor. This is a somewhat complicated object, needing twenty real numbers at each point in order to specify it. These twenty numbers are referred to as its* components. *The different components refer to the different curvatures in different directions in the space-time."* [Penrose] {493}.

> [Physics studies and prepares imperfect models, not perfect truth] *"All we ever know is our models, but never the reality that may or may not exist behind the models and casts its shadow upon us who are embedded inside it. We imagine and intuit, then point the finger and wait to see which suspect for truth turns and runs. Our models may get closer and closer, but we will never reach direct perception of reality's thing-in-itself"* [Hawking] {494}.

8.1 Introduction

In this chapter, we first present a highly abbreviated background of the theory of gravitation, sufficient for our experimental orientation. Of special interest are unified field theories, which cover general relativity, electrodynamics, and quantum mechanics in one overall master theory. Even more of interest is an engineerable unified field theory, which is presently closest approached by the theory of Mendel Sachs {510}.

We then present a short overview of work that has been done in the fields of lifters and inertial propulsion, listing some of the inventions of interest, the approaches, results achieved, and our comments on each.

Finally, I present my own approach to antigravitation, and give some results of the Sweet device's antigravity test (the test was designed by the present author) that successfully reduced the weight of a device by 90%.

In our view, this experiment fully demonstrated the veracity of our theoretical approach.

8.2 Selected Theories of Gravitation

8.2.1 Newton's Theory and a Negative Mass Extension

The first mechanism for gravity of interest to our purposes was advanced by Newton in his work on mechanics {495}. Newton's law of gravitation may be stated as {496}:

> *"A particle of mass m_1 attracts a particle of mass m_2 a distance d away with a force* $F = G\frac{m_1 m_2}{d^2}$ *in the direction of the line joining the particles."*

Of course, it should have stated "in a time forward zone". The situation is precisely reversed in a time-reversal zone. It is also reversed for negative mass-energy.

In the Newtonian view, antigravity would mean repulsion of mass rather than attraction of mass. Given that negative mass is possible, then a negative mass would exhibit antigravity — i.e., it would be repelled by all other positive masses.[214] This can be seen in the quoted equation, by

---

[214] The discussion of what attracts what and what repels what, in a mix of negative and positive masses and negative and positive energies, is still controversial in physics. Different theorists have taken differing positions, and there is no formal experiment that has decided between them. In our opinion, the successful antigravity test of the Sweet vacuum triode amplifier answered that question experimentally, although independent replication was not accomplished. The scientific discussions heavily involve discussions (and assumptions) of the nature of "gravitational" mass, inertial mass, and electrodynamic mass etc. Again, there is no decisive selection among several possibilities, and there is no clear and universally accepted definition of **any** of those three types of mass.

In addition, all the discussions have included a fundamental error: They **assume** a separate 3-force acting upon a separate 3-mass, which is unequivocally false. Another fundamental error is the assumption of an observed (effect) 3-positron interacting with normal matter rather than a non-observed (causal) 4-positron (negative energy 4-electron) in massfree spacetime. In effect, this applies the CPT (charge-parity-time) symmetry, and converts the direction of the 3-positron to the antidirection of the 4-positron while also changing the negative mass of the 4-positron to positive mass of the 3-positron. Further, in physics there is still no firm **definition** of either force or mass, but only circular definitions between the two. We are using the simple definition of mass as $F = d/dt\,(mv)$, where mass is a component of force F and hence there is no separate force F acting upon a separate mass m. We interpret that equation as "the force *F* observed in a new observation is proportional to the time-rate of change of the ongoing 4-space interaction between the just-observed 3-mass *m* and the average interchange of time-energy and space-energy represented by v in the ongoing dynamics between spacetime and mass *m.* Whatever adjective is prefaced upon the *F* is also prefaced upon the *m* in the *mv* term.

We politely but firmly disagree with one prevailing notion that positive mass *attracts* both positive and negative mass, while negative mass *repels* both types. Further, we believe that the Sweet vacuum triode amplifier antigravity experiment falsified that notion. We hold to the dictum that $m == E/c^2$, where E is real spatial energy and may be positive or negative, c^2 is always positive, and therefore negative mass is highly compressed negative spatial energy while positive mass is highly compressed positive spatial energy. (Imaginary mass is a separate consideration.) We also prefer to reason in "single fundamental units" physics where the joule is the only fundamental unit. Gravity then becomes a function of the joule, whether electromagnetic, mechanical, or whatever. *We consider the energy in spacetime to he the source of the curvature of spacetime that is known as " gravitational field".* If the joule is of positive energy, the accompanying gravity is positive. If the joule is of negative energy, the accompanying gravity is negative. And we consider gravity as the 4-space causal spacetime curvature. So for gravitational interaction theory, we insist on examining the interaction of the curvature of local spacetime with the mass-energy. Further, we postulate that the gravitational effect upon one mass from a second mass is an improperly posed concept. It actually is an effect of the local curvature of spacetime around the first mass, where that curvature of spacetime was induced by the second mass's energy. Further, we consider that positive energy fields surrounding a positive mass will curve spacetime in the "positive gravity" direction. The positive mass is attracted by all other positive masses. Negative energy fields surrounding that positive mass system curve spacetime in the "negative gravity" direction so that the positive mass of the system is at least partially repelled by all other positive masses in the universe.

We further prefer to think in terms of the *supersystem* and the unobserved causal 4-field, not the frozen iterative 3-field snapshots defined only after iterative . observations. As we stated previously, the "observed" 3-positron is, in our view, a very different beast from the as-yet-unobserved 4-positron. The 3-positron is a frozen momentary "effect" entity with no dynamics at all and no continuous existence in time (and hence in spacetime) at all; instead, it continually *recurs* as the iterative effect of iterative observation by iterative application of the *d/dt* observation operator. The 4-positron is still a negative energy electron with negative charge, and still going in a non-reversed direction since broken parity has not been applied (because observation has not been applied), a causal entity with ongoing dynamics, continuously existing in spacetime, not just in 3-space. Until interacted and observed, it also has negative energy and negative mass-equivalency.

If one wishes to accurately deal with spacetime effects from the "positron," in our view one must deal with the 4-positron before observation, and hence with the supersystem. The 3-positron is not a *spacetime* entity, but only a frozen *3-spatial* snapshot. Scientists, including Dirac himself, were horrified at the negative mass implications of the negative energy states. Therefore, they moved the interpretation simply replacing positive mass m_1 by negative mass $-m_1$. That two negative masses would attract can be seen by replacing positive mass m_1 by negative mass $(-m_1)$, and also replacing positive mass m_2 by negative mass $(-m_2)$.

Now consider mass m_1 to be the rest of the net positive mass in the universe, and mass m_2 to be the "effective" mass in a local supersystem consisting of the local physical system, its local active vacuum, and its local active curvatures of spacetime — in short, in a local supersystem consisting of the physical system and its local active environment, and the interchanges between them. Let $m_2 = m_p + m_n$, where m_p is the amount of local positive mass (or mass-equivalent) in the system and m_n is the amount of negative mass (or mass equivalent) in the system. This supersystem now simultaneously exhibits both positive gravity (attraction) to all net positive masses in the universe and negative gravity (repulsion) to them as well. The net gravitational response of the supersystem depends upon the fraction of the effective mass that is positive and the fraction that is negative — in short, upon the net vector sum of the two gravitational forces.

to the 3-positron, and thereby twisted the interpretation to substitute the effect for the cause. Hence circuit theory treats the *lattice hole* as a positron, yet that "hole" acts very differently from a true Dirac positron (a Dirac sea negative energy electron) in free space.

Consequently, matter-antimatter interactions and the interaction between positive energy and negative energy are quite different, or they can be if so manipulated prior to observation. In the matter-antimatter interaction, the initial curvature of spacetime formed by the union decays by radiation of EM positive energy and the "effect particles" disappear back into the uncurved vacuum from whence they came. In the positive energy and negative interaction, there is a change of the local curvature of spacetime without its decay and subsequent re-radiation of EM energy. Equal amounts of interacting positive and negative EM field energy thus are simply transduced into stress energy potential of the vacuum and consequent sustained change in the curvature of the local spacetime. Indeed, the radiation of pair annihilation energy is obtained only at the expense of negating (relaxing) the local polarization of the vacuum (and the two consequent curvatures of local spacetime) represented by the independent positron and electron. Indeed, normal pair annihilation is a sort of Lorentz symmetrical regauging of the locally asymmetrical vacuum.

The reader is certainly free to disagree with our conclusions; we are merely explaining them. Experiment will eventually sort out the truth or falsity of the approach. So far, based on the Sweet experiment designed by the present author, a highly successful experiment was consistent with this approach.

In a "mixed" mass system containing both positive and negative component masses, the fraction of the total mass that is positive and the fraction that is negative is thus significant. When the mixture's negative mass is less than its positive mass, the mixture would exhibit a "reduced" gravitational attraction to other masses of the universe. Then the ratio of negative mass to positive mass might be taken as the "gravitational shielding" coefficient (fraction).

When the amount of positive mass and the amount of negative mass were equal, the overall mass system would exhibit no net gravity or antigravity, and would "float" or "hover" in the Earth's gravitational field. It would be equally attracted and repelled by the Earth's positive mass (and by all other positive mass in the universe, hence could — at least under certain conditions — *appear inertia-free.).* When the amount of negative mass exceeds the amount of positive mass, the overall mass system would exhibit a net antigravity effect. It would be repelled more strongly by the Earth's positive mass, as well as more weakly by the distant positive masses of the universe, and hence would accelerate upwards and away from the Earth. Notice that the key to antigravity in the Newtonian approach is the availability of negative mass, but in the new sense in which we use it. Note also that we did not discuss the separate issue of imaginary mass.

If we translate that into modern terms, where we consider not the "mass" but the condensed energy comprising the mass, then m_p and m_n become positive mass-energy and negative mass-energy terms respectively. Given the ability to produce electromagnetically produce substantial negative field energy in the immediate vacuum environment of the system, where the source of the field is the physical system, then the creation of a direct antigravity component in the system's environment — the other two components of its supersystem — becomes not only possible but also feasible.

The key to antigravity becomes the *availability of negative field energy in the local space surrounding the physical object, with the physical object containing the source of that surrounding spatial negative energy field.* Voila! This impels us directly to electrodynamics and a modified Dirac sea {497, 498a, 498b), one with excess empty holes as source charges producing negative energy EM fields. We deliberately create these unique source charges by actions taken in a COP»1.0 system. This gives the key to the approach to antigravity taken by the present author.[215] However, we use as negative energy not just the accounted *Poynting* energy flow component in space where the field is present, but also the unaccounted *Heaviside* energy flow component, which is much greater in magnitude (in a nominal case, nearly 10^{13} times greater). In this way, we dramatically increase the amount of antigravity effect that can be obtained by a given EM power dissipation in the physical electrodynamic system itself. *This antigravity effect of a Heaviside component of EM negative energy flow has not been accounted in previous analyses.*

8.2.2 Riemann Surfaces and Riemann Geometry

The next development of interest to us is the doctoral thesis of Riemann {499}, which founded the theory of Riemann surfaces. Three years later, **he** founded Riemann geometry in a famous lecture. Riemann was working on a unified explanation of gravity and electromagnetism when he died of tuberculosis a dozen years later. It was Riemann's multiply-connected topologies that eventually resulted in the view of electric charge producing lines of force trapped in the topology of space {500}. Had Riemann lived, we believe that engineerable unification of electrodynamics and gravity would have occurred early on. In that case, we might have already had practical antigravity vehicles and explored the solar system and beyond.

8.2.3 Heaviside's Excess Energy Circulation Flow and Gravity Theory

The next theory of gravity of interest to us is that of Oliver Heaviside. Heaviside noted that his extra EM energy flow term was a trapped EM energy circulation {501}. He realized that, if that trapped EM energy circulation were taken as gravitational in nature, his energy flow theory could be converted into a unified theory incorporating both electrodynamics and gravitation. After his death, his handwritten notes on **the** theory were found beneath the floorboards in the little garret apartment he had long occupied. No one knows what other papers he may have had; **the** place was ransacked and looted prior to the discovery of these remaining papers hidden beneath the floorboards — papers the looters had missed.

[215] We also point out that a Dirac sea with empty holes (excess negative energy states) exists in (or constitutes) a negatively curved spacetime *a priori.* So we get back to the other two components of our "supersystem", the active vacuum and its dynamics and the local curvature of spacetime and its dynamics.

Other scientists such as Laithwaite have felt that Heaviside's approach might still shake the foundations of physics itself. Quoting Laithwaite {502}:

> *"Heaviside had originally written the energyflow as S = (ExH) + G, where G is a circuital flux. Poynting had only written S = (ExH). Taking p to be the density of matter and e the intensity of a gravitational force, Heaviside found that the circuital flux G can he expressed as pu — ce, where u represents the velocity of p and c is a constant."*

8.2.4 Mach's Principle

After Heaviside, the next item of interest to us is Mach's principle {503}, which essentially states {504}:

> *"The properties of space have no independent existence but depend on the mass content and distribution within it. Thus, acceleration dealt with in Newtonian mechanics can only have meaning if it is an acceleration with respect to the stars or with respect to something equally well-defined."*

Mach's principle does not adequately deal with spacetime, and certainly does not even acknowledge or encompass how energy exists in 3-space at each point dipole, as an entering flow from the time domain into the negative (charge x time). It does not include transduction by the negative charge into 3-space energy, passage of the 3-energy to the associated positive charge, transduction back into time energy by the positive charge, and re-emission of the transduced time-energy back into the time domain, by the positive charge. In short, Mach's principle will never get one a practical antigravity system, regardless of how one applies the principle.

8.2.5 Einstein's General Relativity

Next comes Einstein's epochal general relativity theory of gravitation {505}. In that theory, Mach's principle is interpreted as pointed out by Misner, Thorne and Wheeler {506} in the following quote:

> *"...Einstein's theory (1) identifies gravitation as the mechanism by which matter there influences inertia here; [and] (2) says that this coupling takes place on a spacelike hypersurface..."*

The great contribution of Einstein's general relativity was to remove the notion of the "field occupying space", where field and space are separate things. Quoting {507}:

> *"If we imagine the gravitational field, i.e., the functions* g_{ik} *to be removed, there does not remain a space of the type (I) [Minkowski Space], but absolutely* *nothing, and also no 'topological space'. For the functions* g_{ik} *describe not only the field, but at the same time also the topological and metrical structural properties of the manifold. ... There is no such thing as an empty space, i.e., a space without field. Space-time does not claim existence on its own, but only as a structural quality of the field."*

In passing, we note that in the conventional sense we can and do have many fields "in the same space", which is merely the statement that a net field has internal structure, and so does a net spacetime. Extending that notion, we can conclude that spacetime is in fact naught but a set of fields, both static and dynamic. The total energy density of all those fields at any point in space constitutes *a potential* with that energy density at that point, and with that internal field dynamics and structure. So because of its incredible field energy density, space is also *identically* a giant potential with internal structure and dynamics. With that observation, we rather casually join the seething vacuum of particle physics, the spacetime of general relativity, and the fields of electromagnetics as *different aspects of the same thing.* We point out that our concept of the supersystem therefore only identifies the three separate things into which this "one-thing" has been arbitrarily divided in much of physics.

Although he tried more than once, Einstein himself failed to achieve a successful unified theory of gravitation and electrodynamics. One thing he added in his earlier theory was a cosmological constant, which he felt was necessary to explain a stable closed universe. He later regretted that assumption, but today with the discovery of the acceleration of the expanding universe, which can only be caused by antigravity, his cosmological constant has assumed a new and vital role in the search for the source of this observed antigravity effect in the cosmos.

8.2.6 Kaluza-Klein 5-Dimensional Unified Theory

Using five dimensions, a unified theory of general relativity and electrodynamics was advanced by Kaluza {508} as extended by Klein (509}. This is a notable extension of Einstein's theory, and a very substantial literature exists in the Kaluza-Klein area.

8.2.7 The Sachs Unified Field Extension of Einstein's Theory

Another notable extension of Einstein's theory, which does include electrodynamics and the results of quantum mechanics as well, is the theory by Sachs {510}. Starting with Einstein's general relativity view and the group symmetry of its underlying mathematics, Sachs extended Einstein's theory into a fundamental theory of matter in all domains. Einstein's group formalism and the spinor-quaternion calculus in a curved spacetime provide the genesis of matter fields. The theory encompasses globally covariant field equations for inertial features of matter including its force manifestations. Unification is provided by the generalized spinor formalism. Quoting a popularized summation {511}:

> *"Novel features of general relativity are shown to emerge, in elementary particle physics as well as astrophysics. Especially noteworthy ...is a factorization of Einstein's field equations to a quaternion field formalism which, by way of a single covariant field, includes both gravitation and electromagnetism coupled to matter field equations — whose linear (low energy) limit recovers quantum mechanics. The ...original approach also furnishes derivations, not previously available, of several observed properties of inertial mass and gravitational force. "*

For a more technical description of how the unification of electrodynamics with general relativity is derived, we quote directly from Sachs {512}:

> *"It was demonstrated earlier that the factorization of Einstein's second-rank, symmetric tensor field equations, by removing the space and time-reflection elements from the underlying covariance group, yields a 16-component quaternion metrical field equation. The 16 equations were then re-expressed in a second-rank tensor form, breaking up into 10 ⊕ 6 equations. The 10 equations are in one-to-one correspondence with Einstein's symmetric tensor equations for gravitation; they are even under reflections. The remaining 6 equations are in antisymmetric tensor form; they are odd under reflections. Taking the covariant divergence of the latter equations then puts them into one-to-one correspondence with the structure of Maxwell's equations for electromagnetism. What was shown earlier was that the four of Maxwell's equations with sources followed. What is shown in this paper is that the other four of Maxwell's equations that are source-free also*

> *follow, thus indicating the absence of magnetic monopoles from this theory, as in the usual Maxwell formalism. This shows that the factorization of Einstein's field equations to the quaternion form fully unifies the gravitational and electromagnetic manifestations of interacting charged matter."*

To freely download several of Professor Sachs's important technical papers, one is referred to his website at http://www.compukol.com/mendel/articles/articles.html.

The O(3) electrodynamics of Evans and Vigier has been shown to be a special subset of Sachs's electrodynamics {513a}. Hence O(3) can be used to engineer much of the Sachs unified field theory phenomenology, including — in our view — both gravity and antigravity. The first theoretical indication of this has been published by the AIAS (Alpha Foundation's Institute for Advanced Study) {513b}. Shortly we discuss our own views on how to directly perform engineering of antigravity.

A great many excellent publications on general relativity and the background of scientific knowledge in gravity exist; e.g., the text by Wheeler *et al.* {514} is particularly good. Einstein himself wrote a book on his special and general theory for the nonspecialist {515}. A collection of English translations of some of the original papers on relativity is provided in a book by Einstein, Lorentz, Minkowski, and Weyl {516}. Many other gravitational theories or changes to major theories have also been proposed by other scientists, but are not discussed here. For our purposes, an abbreviated discussion will suffice to understand a fundamental approach to feasible antigravity.

Since we are interested in actual working systems, a short review of some of the efforts in asymmetric lifting and propulsion experiments is useful.

8.3 Selected Antigravity and Inertial Propulsion Research Efforts

We give only a small sampling of the many efforts performed or ongoing in this area over the last few decades, and some still ongoing today.

8.3.1 T. Townsend Brown

Our first example is the work of T. Townsend Brown. Brown was working **on** a "gravitor" before he finished high school, and continued work in electrogravitation throughout his life. Space is a dielectric, and Brown reasoned that the displacement current in a capacitor dielectric could influence the space dielectric itself.[216] Hence he built, tested, and patented several variations of lifting devices based on this concept {517a-517e}. Essentially, he found that certain high capacitance dielectrics could be subjected to high voltage (50 to 300 kilovolts), and would exhibit thrust in the direction from the negative to the positive pole.

Here we point out our contention that all EM energy in space comes from the time domain via the negative charge, and re-enters the time domain via the positive charge. This is consistent with Brown's finding. Although he demonstrated many such lifting and thrusting devices, Brown was never able to obtain sufficient financial and scientific backing to bring a practical embodiment of his inventions into practice. His work, however, has been replicated by multiple experimenters, including NASA researchers (see below) and several researchers contributing results to Jean-Louis Naudin's website http://jnaudin.free.fr/html/lifters.htm.

8.3.2 Jonathan W. Campbell

Recently a U.S. patent {518} on a thrusting capacitor, by Campbell, has been issued and assigned to the U.S. Government (NASA), and made available for commercial licensing. The patent write-up states that thrust from capacitors is well known, but has been too small to be practical. The patent purports to remedy that impracticality. A version of the NASA device has been replicated by the Naudin researchers also. So an adaptation of Brown's work has been patented by the U.S. government with intentions of licensing. This would appear to validate much of Brown's approach and efforts.

8.3.3 The Dean Drive

Our second example is the inertial drive patented by Dean {519a-519e}. Unfortunately, the effects of the Dean drive later appeared to be a problem in accurate measurement. Nonetheless, work still continues along the direction shown by Dean. One may argue that mechanical materials also contain charges and have a certain kind of capacitance. Hence, mechanical motion of the parts of the machine does move these charges and dielectrics, opening a possibility of interacting with the dielectric of space. For example, Sweet's VTA involved a sustained self-oscillation between the local vacuum and the barium nuclei in his barium ferrite magnets.

---

[216] We have not yet explored the gravitational effects — if any — of our concept of the triode capacitor, discussed in paragraph 6.3.7 and diagrammed in Figure 6-17. We will examine it as soon as we have the proper equipment.

Dean's approach still has merit, even if a particular embodiment gave a negative result when very accurate measurement was performed. It is particularly of interest that mechanical force is essentially derived from electromagnetic forces (and fields) at basis. These base EM fields involve (and identically are) curvatures of spacetime, and hence the motions of the inertial drive mechanical apparatuses do involve at least some curvatures of spacetime and dynamic changes to them.

Our comment is that, when the additional but neglected Heaviside nondiverged energy flow component is accounted, these field interactions internal to matter can produce many orders of magnitude greater curvature of spacetime than is accounted by the diverted Poynting energy flow component only.

The "inertial antigravity" approach may be visualized as the use of excess gravitational thrust in a specific direction. If that direction is against the local pull of gravity, and is more powerful, then "lift against the gravitational pull" is obtained. Rigorously, this is not true antigravity but manipulated excess positive gravity.

In our approach to antigravity, one way to approach the problem is to have the mechanical apparatus also the source of an intense *negative energy* EM **field,** producing an intense flux of Dirac sea holes into and in the local surrounding spacetime. The excess charge removed from the Dirac holes can in fact be used in the electrical powering of the physical system, as was demonstrated in the Sweet VTA antigravity test. Then movements of the mechanical parts could involve movement of strong negative energy fields, hence strong curves of local spacetime that are local *strong negative gravity fields*. Or, better yet, movement of the charges themselves will also produce field-induced movement of the Dirac sea hole negative energy. This appears to be a practical method to manipulate the metric itself, along the lines proposed by Puthoff *et al.*[217]

8.3.4 Henry Wallace

Other work has been by Henry Wallace, an engineer working for General Electric in the 1970s. His work dealt with the interactions of relatively moving masses of various kinds, and it is described in his patents {520a, 520b}. The discussion under the Dean drive probably applies to Wallace's work as well.

---

[217] H. E. Puthoff, S. R. Little, and M. Ibison, "Engineering the Zero-Point Field and Polarizable Vacuum for Interstellar Flight," *J. British Interplanetary Soc,* Vol. 55, 2002, p. 137-144.

8.3.5 J. F. Woodward

Next is the work of J. F. Woodward, resulting in one or more patents {521} and multiple articles in the legitimate physics literature {522a-522k}. Woodward uses an adapted theory based on Mach's principle and on the thesis that the mass of a capacitor can be made to vary from its normal mass by rapidly charging and discharging it — say, at a frequency of 20 kHz. This predicted effect is testable, although some sophistication in the testing is required.

Woodward's publications show the results of actual experiments, measuring a very small change in the mass, and are worthy of much further investigation. Here we note that the actual mechanism generating the inertia of an object is still an open issue, with several different contending theories.[218] Whether the gravitational mass and the inertial mass are identical or not, also remains an issue. If the exact local mechanism generating the inertia of a mass could be decisively found, then direct methods of changing the inertial mass and the gravitational mass might be a real possibility, and research to try to find such methods would be strongly indicated.

Our further comment is that the mechanism that generates mass itself has never been specified in formal physics,[219] particularly when one views an observable (such as mass) as continually recurring in 3-space rather than continuously existing in 3-space, due to the *d/dt* operator imposed on spacetime by the observation process. Before the reader assumes that mass is well understood, a reading of Jammer's scholarly work {523} is highly recommended.

From our viewpoint we stress that observed mass cannot continuously exist, but must be an effect and the instantaneous frozen output of the *d/dt* observation process invoked on an ongoing 4-space process. Hence, from this view there is indeed a "process" that (continually) creates mass — it is at least the emission of EM angular momentum (a photon) from the *masstime* entity. Similarly, there is a "process" that continually destroys or converts any mass — it is the absorption of a photon and conversion of the mass m into masstime $(m + dm)dt$. Mass "flows through time" via this time charging and discharging, in the form $m \Rightarrow mt \Rightarrow m \Rightarrow mt \Rightarrow m$... etc.

---

[218] E.g., (a) A. Rueda and B. Haisch, "Inertia as reaction of the vacuum to accelerated motion," *Phys. Lett. A,* Vol. 240, 1998, p. 115-126; (b) B. Haisch, A. Rueda and Y. Dobyns, "Inertial Mass and the Quantum Vacuum Fields," *Ann. Phys.,* Vol. 10, 2001, p. 393-414.

[219] The present author made an early **and** crude attempt at doing it in his "Quiton-Perceptron Physics." 1973, NTIS Report AD-763-210.

Again we stress that masstime mt is not mass m, but is as different from it as impulse Ft is from force F. We crudely proposed such an initial mass-generating mechanism in 1973 {524a}, with additional information published in 1998 {525a}, which may have bearing on the mechanism involved in Woodward's experiments.

8.3.6 E. **R. Laithwaite**

Eric Laithwaite was for some years a professor with the Imperial College in London. He was one of the pioneers of the linear electric motor and of portions of the magnetic levitation (MagLev) train concept. An illustrious career headed for greater things (perhaps knighthood, Fellow of the Royal Society, etc.) was abruptly derailed in 1973 after he lectured to the prestigious Royal Institution by invitation and demonstrated that a heavy gyroscope, difficult to lift with one hand while not turning, could be lifted easily with that same hand, once turning at speed. Laithwaite's suggestion that Newton's laws of motion might be in difficulty proved much too controversial. The Royal Institution (apparently for the first time in its 200 year history) did not publish proceedings of that invited discourse.[220]

One of the remarkable things Laithwaite achieved was a form of "indefinite motion" device that he demonstrated circa 1970 {526}. The Centennial Centre of Science & Technology in Ontario was looking for working models to decorate the entrance hall. Laithwaite showed that if a linear-motor primary was rolled into a cylinder, so that it became simply the stator of a conventional induction motor,[221] a steel washer (about 3 cm. in diameter) could be made to roll continuously in a vertical plane around the inside of the stator. A combination of centrifugal force and magnetic attraction kept the washer in contact with the stator at all times. At the same time, a pivoted copper cylinder could be held in the center of the stator and would be seen to rotate on its own axis in the opposite direction.[222] Laithwaite completed and delivered a working model to the Centennial Center of Science & Technology. The reader should note the similarity of Laithwaite's proven experimental device to the magnetic Wankel engine.

---

[220] With some humor we point out how shocking is our proposal that such a thing as "continuous" propagation of an object or energy through 3-space does not exist. Instead, small differential "pieces" of it continually "recur" at successive positions, much like the projection of the frames of a motion picture frame, where continual observation is the "projection process". Nonetheless, in our proposed solution to the source charge problem, either that is true or every charge in the universe is a perpetual motion machine, freely creating energy out of nothing. In our view, that is the impact of the long-neglected source charge problem in quantal and classical electrodynamics. It has produced the wrong and naive notion of what "propagation through space" actually entails.

[221] Something similar to diagrammatic Figure 6-26 in Chapter 6.

In addition to his attention to Heaviside's unpublished draft notes and manuscript on a combined theory of electromagnetics and gravity (previously discussed above) {502}, Laithwaite spent the latter years of his life working on sophisticated gyroscopic systems {527a-527h}. Ultimately he felt he had successfully produced a mass transfer effect {528} and the basis for a propulsion system. He and William Dawson applied for a patent in 1993, which was granted in 1995 {529}, with a U.S. patent granted in 1999 {530}. Regretfully, Professor Laithwaite died in 1997.

8.3.7 Floyd Sweet's Vacuum Triode Amplifier (VTA)

See again Chapter 6 and Figures 6-5 through 6-14 on the work of Floyd Sweet, previously discussed in paragraph 6.3.2. My concept of antigravitation used in the experiment is shown in Figure 6-15. By now, the sharp-eyed reader will recognize that my method actually constitutes a conceptual extension and definitization of the Dirac electron theory, reinterpreted to recover negative mass, negative energy, negative energy fields, and negative energy potentials. The defining feature is the deliberate use of a COP»1.0 main power system (perhaps constituting the power system of a flight vehicle) as a source of locally strong negative energy EM fields generated by the concentrated Dirac sea holes (causal 4-positrons being negative energy 4-electrons prior to observation) locally produced in the power system. We collaborated with Sweet on the vacuum triode amplifier for more than a decade, and in fact suggested the name of the device.

The antigravity approach designed by the present author was based on realizing that negative energy sources (e.g., 4-positrons as negative mass 4-electrons prior to their reaction and observation) produce *negative*

---

[222] We have had the distinct notion that the fundamental *contrarotating* mechanism found by Laithwaite is probably an analogous mechanism — or very similar — to the mechanism utilized by Bauman in his Swiss converter (Methernitha device). As pointed out, it also has remarkable similarities to the magnetic Wankel engine, except that the magnetic Wankel does not utilize two contrarotations.

energy EM fields. The field can reach out over all space, so a negative EM energy field represents a reversed curvature of a large volume of spacetime. Hence it represents a considerable antigravity field — particularly when one considers the unaccounted huge Heaviside component of the negative energy field and charge interaction. Since the field strength falls off as the inverse square of the distance from its source, the strong antigravity effects of negative energy EM fields are much stronger locally than at a distance. This is particularly true when the conventionally ignored Heaviside nondiverged EM energy flow accompanying the accounted diverged Poynting energy flow of every field-charge reaction is accounted. This usually ignored factor dramatically increases the antigravity intensity produced by the local negative EM energy field by many orders of magnitude, often by nearly 10^{13}.

My antigravity concept (then and now) is shown in Figure 6-15 of Chapter 6. At the time, the only available device I knew of that produced a substantial percentage of output negative EM energy was Sweet's vacuum triode amplifier. So I persuaded Sweet to fabricate a new output section (an output load similar to Figure 6.8 but containing ten sockets for ten 100 watt lamps). Thus the output of the unit — which adjusted automatically to the available load — could be increased in 100-watt increments by merely screwing in the lamps one at a time and making laboratory readings after each new 100-watt load increase was added. This was done and the concept was successfully tested by Sweet {531}, who was making the measurements in California and reading them off over the phone to me (I was in Huntsville, Alabama). The experiment worked beautifully.

The setup and progress of the experiment were intended to materially increase the strength of the *negative energy* EM field and Dirac sea hole flux already produced to a lesser extent by the Sweet vacuum triode amplifier (VTA) in its normal operation. Thus the hypothesized negative energy antigravity field, produced weakly by the negative energy from the device in its ordinary power output range of 500 watts, was to be substantially increased at 1,000 watts. The response to the net gravitational field surrounding the object would thus be the resultant of two factors: (i) the normal response of the device's positive mass to the positive gravitational field of the Earth etc., and (ii) the additional response of the device's positive mass to the local antigravitational field produced around it. The measurable result was expected to be a decrease in the measured weight of the object on the laboratory bench.

As discussed, this stratagem succeeded dramatically. The weight of the vacuum triode amplifier was decreased, smoothly and controllably, by

90% on the laboratory bench (see again Figure 6-9).[223] The results were later published in a joint paper {531} prepared by the present author. I placed Sweet's name first on the paper because he was the inventor of the VTA, which demonstrated the effect once properly modified as I requested. Note that the extra antigravitational field effect on an object is indeed a local effect, which the experiment also showed. This effect was obtained at a COP>1,500,000 (actually, at nearly a COP = 3,000,000) and at ELF frequency.

The ELF frequency is important. As we explained previously, the highest energy photons of all are the lowest frequency photons, when the highly compressed time-energy component of the photon is accounted as well as the decompressed spatial energy component. Hence, for very appreciable local curvature of spacetime to produce considerable antigravity, the antigravity source must produce negative energy fields consisting of negative energy photons at low frequencies (such as 60 Hz). Else, the curvature of spacetime is so small that little effect will evidence. My best "back of the envelope" estimate of the efficiency of the antigravity process in the VTA was 10%.

8.3.8 Ning Li and (separately) E. Podkletnov

Very interesting work was performed by Ning Li {532a-532d}, a scientist originally with the University of Alabama in Huntsville (UAH), who returned to China for a while but is now back in Huntsville. Quoting David Brown from the UAH website from 1997:

> *"In 1989, Dr. Ning Li of UAH predicted that if a time varying magnetic field were applied to a superconductor, charged and deformed lattice ions within the conductor could absorb enormous amounts of energy via the*

---

[223] Many times I have been asked how such small output power increase (from 500 to 1,000 watts) could possibly achieve such dramatic antigravity results. The answer - due to the neglected Heaviside nondiverged energy flow component — lies in multiplying the power output by the "Heaviside energy amplification factor *k* " where *k* may be as large as 10^{13}. A 500-watt accounted increase, multiplied by 10^{13}. is actually an incredible increase in the total EM negative energy field density being created in the local vacuum. In short, a very little "accounted" power increase of the COP»1.0 VTA output is actually a very vast negative power output increase when the long neglected k-factor is accounted. It is just this missing k-factor and the failure to account for the negative energy KM fields generated in COP»1.0 discharges in violent astronomical phenomena that seem to be responsible for generating the excess antigravity that is accelerating the expansion of the universe.

> *magnetic moment effect. This acquired energy would cause the lattice ions to spin rapidly about their equilibrium positions and create a miniscule gravitational field. Dr. Li's calculations showed that if these charged, rotating, lattice ions were aligned with each other by a strong magnetic field, the resulting change in local gravity would be measurable."*
>
> *"Podkletnov and Nieminen (1992)* {533} *made the accidental discovery that a single-phase, dense, bulk, high T_c, superconducting, ceramic disk spinning at 5,000 rpm can produce a 2 percent reduction in the weight of non-conducting, non-magnetic objects placed over the spinning disk. UAH and MSFC [Marshall Space Flight Center, a part of NASA] [cooperated] on a joint research project to independently confirm the results of the Podkletnov experiment and to validate Dr. Li's theory of gravity modification via superconductor. On March 26th, 1997, as a part of this project, the joint UAH-MSFC research team produced the largest high temperature superconducting disk ever manufactured in the USA. This disk measures 12 inches in diameter and is 0.5 inches thick"*

We now explain the experiments, from our point of view of the mechanism for antigravity. We remark that, at least in theory, the charges in such a rotating superconducting disk have an inward "discharge" acceleration force that is a function of the distance of the charge from the rotation axis center. Hence, in the rotating frame, some of these charges are very strongly "accelerating" toward the center, as are their spins whose magnetic vector is orthogonal to the E-field vector. A flow of EM energy exists perpendicular to the rotating flat disk and is accelerating at right angles to the disk surface. This is analogous to a *discharge* (sudden acceleration) phenomenon, and it will also produce accelerating negative energy Dirac sea 4-holes in the vacuum component of the supersystem of the spinning disk. So from the spinning disk there is a sort of "wide beam" of Dirac sea 4-hole current in the vacuum, radiating at right angles to the disk surface, with heavier concentrations toward the outside of the disk. The result is that objects in the Earth's gravitational field, and also placed in the path of this negative energy Dirac sea 4-hole current, is acted upon by two superposed curvatures of local spacetime: (1) the positive curvature due to the Earth's gravitational field, and (2) the negative curvature due to the negative energy field's curving local spacetime. The total net gravitational effect will be due to the algebraic sum of the superposed two spacetime curvatures — the normal positive curvature from the Earth's gravitational field and the second a negative curvature created by the Dirac sea hole current's negative energy fields (Heaviside energy flow component considered). The expectation is therefore a *reduction* in the weight of the object, as is shown in the experiments.

The UAH-MSFC group was unable to confirm Podkletnov's findings.[224] Ning Li and the NASA group later split amicably. Ning Li continued her theoretical work, eventually ceased publishing papers for a period to protect the techniques and experimental results achieved in her work, and focused upon potential applications. She apparently returned to China for some time, but is now back in Huntsville, Alabama and still experimenting. We suspect there may also be a Chinese research effort into antigravity, using the approach taken by Ning Li. Perhaps information from that program will be released in the future.

But what of the work of Podkletnov since his original experiments? NASA continued to try to replicate his disk and his work, with Podkletnov acting as a consultant. Presently, NASA has paid an independent research firm to replicate the disk to full specifications, which has just been accomplished as this is written. At this writing, the experimental results of this new attempt are not yet available as the work is still in progress. It should be available by the time this book is published.

Meanwhile, a relatively new paper by Podkletnov and Modanese has been published on the Los Alamos National Laboratory website.[225] This method uses high amperage sharp pulse discharges from a superconducting ceramic electrode, to produce an anomalous radiation in a focused beam. Significantly, the beam does not noticeably attenuate through different materials. The beam exerts a short repulsive force on small movable objects on the propagation axis, with the force proportional to the mass of the objects.

---

[224] E. Podkletnov and R. Nieminen, "A possibility of gravitational force shielding by bulk $YBa_2Cu_30_{7-x}$ superconductor," *Physica C,* Vol. 203, 1992, p. 441-444.

[225] Evgeny Podkletnov and Giovanni Modanese, "Impulse Gravity Generator Based on Charged $YBa_2Cu_10_{7-y}$ Superconductor with Composite Crystal Structure," carried on website http://xxx.lanl.gov/abs/physics/0108005.

We interpret the results as completely consistent with our own proposed excess gravity and antigravity mechanism. We know that such sharp discharges produce significant Dirac sea 4-hole currents in the local vacuum component of the supersystem. Such currents in a beam interact very little with intervening materials, and the major spacetime curvature effects are concentrated upon the propagation axis. On that axis, force effects can be expected upon small independent objects, due to the *additional* negative curvature added to the local spacetime in their supersystem. The impulse produced on the object should indeed be proportional to the mass of the object and independent of its composition, since it is a gravitational force effect induced by local curved spacetime. The force should be repulsive in the beam, since that is the direction of the antigravity force that will be induced in objects in the axis of the beam, by the beam of negative energy Dirac 4-holes. A positive gravity force would mean attraction between the object in the propagation path and the source of the beam. A negative gravity force would therefore mean repulsion.

So Podkletnov and other scientists are still working on a successful effect. It will be interesting to see what results are reported in the future, and whether they will deviate from their present attempt to explain the effect by a combined quantum gravity and anomalous vacuum fluctuations approach.

8.3.9 NASA's **Breakthrough Propulsion** Physics **(BPP) Project**

NASA's Breakthrough Propulsion Physics Project was established in 1996. It seeks a breakthrough in space transportation involving "(i) propulsion that requires no propellant mass, (ii) propulsion that attains the maximum transit speeds physically possible, and (iii) breakthrough methods of energy production to power such devices." Investigations involve coupling of gravity and electromagnetism, the quantum vacuum, hyperfast travel, and superluminal quantum effects. The project is managed by the Glenn Research Center, sponsored by the Advanced Space Transportation Program, with overall management by NASA Marshall Space Flight Center, Huntsville, Alabama.

NASA continues its investigations and experiments in methods to change **the** force of gravitational attraction. The scientist in charge of the project is David Noever of the Marshall Space Flight Center. The work is still considered a work in progress, with the need for both experimental investigation and meticulous design of experiments, instrumentation, and measurement techniques.

The overall NASA program also spreads to other supporting laboratories and projects. For example, at the Jet Propulsion Laboratory (JPL) Kulikov {534} has measured the difference between inertial and gravitational mass of a boson in a heat bath. At least one invention seems to have resulted or to be in progress, assigned to JPL.

As mentioned, the U.S. Patent by Campbell {518} on a capacitor device producing a net thrust force (a more modern version of T. Townsend Brown's work) has been issued and assigned to NASA.

8.3.10 Scientific Conferences

There are regular conferences (several per year) being held in the U.S. and elsewhere, dealing with antigravity and electrogravitic propulsion. We give a little-noticed but pertinent example: In a nice presentation in 2001, LaPointe {535} proposed a new method for producing anti-matter. Currently antimatter production is accomplished in very large accelerators, and is therefore quite expensive. For increased experiments, a cheaper and much smaller (and much more available) process is highly desirable.

In the Klein paradox, which involves very large potential drop across a very short distance — less than the Compton wavelength of the antimatter particle — matter and anti-matter pairs are produced. LaPointe hypothesized that it may be possible to use the Casimir effect to push one side of the step into the negative energy range. He is at least *thinking toward* negative EM energy sources that produce negative EM fields and negative gravity in the surrounding space, without explicitly enunciating it in that fashion.

We already briefly discussed our own approach to antigravity, which is a much simpler and cheaper anti-particle producing mechanism, as demonstrated by the Sweet device. In short, overunity EM systems with COP»1.0 do produce free flows of causal (before observed) 4-positrons (still in negative energy 4-electron state prior to interaction) in local spacetime immediately surrounding the system. Consequently, LaPointe's efforts are in what we believe to be the correct direction, but he is still using a very difficult mechanism to engender the antimatter production. Also, the positrons or other antimatter sources of the negative energy fields must remain in the causal (unobserved and non-interacted) 4-state, in order to produce negative energy EM fields and potentials and antigravity.

8.3.11 James Corum *et al.:* Rectified Slepian AC Force Resonator

Another example is some promising work by Corum *et al.* {536}. We quote from the abstract and summary of his paper:

> *"Corum presented an experimental paper on the use of the Heaviside force in conjunction with a Slepian antenna as a form of space drive using nothing more than the classical Maxwell stress tensor. Slepian proposed the same thing in 1949, but came to the conclusion that it would not be useful, since the time average of the resultant AC force would be zero. Corum's contribution has thus far been two-fold: (1) In conjunction with Dr. Alan Barnes of WVU he has experimentally shown that the AC version of the Slepian Resonating Antenna does produce a force, and has measured it to within 3.6%, and (2) has designed a way for Hartley's variable capacitor rectification to be used with the Slepian resonator such that the rectification results in a DC force component. The first experiment has already been achieved, the second experiment is the logical next step. If successful, the result would be quite revolutionary: a true space drive."*

Our comment is that this unilateral thrust force work is important. In our view, the Heaviside energy flow component does not appear in Slepian's vector $\mathbf{j}\phi$, which contains only the diverged EM energy flow surrounding a circuit or component, but it is present immediately outside the circuit where the Slepian vector exists. Hence there is an enormous, extra energy flow closely associated with every EM circuit, that is unaccounted since Lorentz's closed surface integration of the energy flow vector discarded it quite arbitrarily.

We already know from the Bohren experiment (and thousands of others similar to it) previously cited that resonant charges do collect excess EM energy from a given EM energy flow input, compared to the collection from that flow by the same charges in nonresonant state. In using the Slepian resonator and then rectifying its output, it would appear that both the diverged (Poynting) energy flow component and the Heaviside nondiverged energy flow component are first resonated and then rectified. In addition, excess energy is collected — much more than is in the normal "static charge" formula assumptions for Poynting energy flow and in assuming only a "single pass, single interception and collection" of the energy.

An important factor then is obvious: Once the energy flow is surrounding the circuit, there exists a certain local curvature of the immediate external spacetime. The rectification represents not only a change in the Slepian vector current in the circuit, but also a change in this local ST curvature interaction upon the circuit matter and charges. In short, it should produce a DC component in the direct excess interaction of the rectified local curvature of spacetime. This should produce *excess direct propulsive force,* just as Corum theorizes and the experiments support to date.

Further, the oscillation of the large, *unaccounted* Heaviside nondiverged energy flow component involves the oscillation of a "dark energy" component that may be orders of magnitude greater than the *accounted* Poynting component's magnitude. By involving this huge energy flow component in oscillation and synchronized to the resonant Slepian circuit, Corum has unwittingly involved the supersystem as a $COP \gg 1.0$ EM "energy converter" system. Hence, there is appreciable Dirac hole current (in causal 4-form) in the local vacuum, not reacted with the materials in the system and therefore not converted to material lattice holes attached to positive mass. The time rate of changes of the negative energy fields and potentials are thus significant for antigravity effects, in the approach taken by the present author. In short, we believe Corum *et al.* are in fact producing significant evidence for a workable approach to unilateral thrust force.

This work by Corum *et al.* thus is highly promising, is solidly based experimentally, and certainly bears watching closely. We would strongly suggest that Corum *et al,* analyze their proposed mechanisms and results obtained in terms of supersystem analysis rather than system analysis, using higher group symmetry electrodynamics, and recover and include the long-neglected Heaviside energy flow component.

8.3.12 Gravitec, Inc. and H. Serrano

A patent {537} was issued to H. Serrano on Oct. 5, 2000 and assigned to Gravitec, Inc. whose principal investigator and corporate officer is Tim Ventura. Based on this invention, Gravitec, Inc.. has developed and demonstrated a rotary device that develops unilateral thrust. Purdue University began a small but steady effort to test the unit, first in the atmosphere and later under high vacuum conditions. The first tests have been successful, and a paper {538} from the Purdue study shows it is not the ion wind effect, which is orders of magnitude too small to account for the demonstrated thrust. Further, Jean-Louis Naudin has replicated and tested the Serrano thruster, and it works beautifully {539}. Ventura also hopes to develop a toy kit, with safe power supply, which would allow persons to perform their own successful lifter experiments and perhaps rotary experiments at nominal cost.

8.3.13 Transdimensional Technologies, Inc.

There is also ongoing important propulsion work at Transdimensional Technologies, Inc. of Huntsville, Alabama {540}. Founded in 2000 by its chief scientist, Jeffrey Cameron, the company has developed several novel propulsion and lifting mechanisms. Independent tests of some of these systems have been accomplished by Jean-Louis Naudin, and the results can be seen on his website (previously cited).



Figure 8-1 Naudin's **replica of the T**ransdimensional Technologies **lifter.**

As we go to press, Transdimensional's most recent propulsion effect is called Power3 (power "cubed"). It uses an asymmetric capacitor to produce the thrust in space, and the principle has been successfully tested in a vacuum. A larger, triangular lifter made mostly of pipe was demonstrated in vacuo to NASA officials in Huntsville, Alabama. Cameron has patents pending on magnetocaloric hybrid rocket engines and asymmetric gravitational waves {541}. A replica of the Transdimensional lifter successfully tested by Naudin is shown in Figure 8-1, by courtesy of Jean-Louis Naudin. Naudin's replica of the Transdimensional Technologies rotational device is shown in Figure 8-2.



Figure 8-2 Naudin's replica of the Transdimensional Technologies rotational device.

We understand that new Transdimensional Technologies systems, now in patent process and still closely held, represent dramatic advances in the state of the art. The corporation foresees eventual commercial licensing of some of its developments, and the development of practical lift vehicles and space propulsion systems within 3 to 5 years.[226]

[226] Ken Moore and I personally visited Transdimensional Technologies here in Huntsville, and we found a very straightforward, enthusiastic, and hard-working group. We were treated with great courtesy, so much so that Jeff Cameron graciously cut short his vacation day and came in to show us the lab equipment and give a demonstration. We very much appreciate the work that Transdimensional Technologies is doing, and we certainly wish this fine group outstanding success in their efforts. We also are very appreciative for their courtesy and consideration in showing us the demonstrations and for their cogent discussions with us, which **were** most helpful.

8.3.14 American Antigravity (Tim Ventura's Company)

Tim Ventura is a very energetic lifter and antigravity researcher, who has done work independently and for others such as Transdimensional Technologies. The results of his many experiments and replications, tests, photos, etc. are on his website at http://www.americanantigravity.com. He also has several videos showing his testing, as well as detailed instructions for a researcher to build his own demonstration unit and verify the tests. Tim kindly furnished some needed information in this area, and put me in touch with other researchers and websites, which I appreciate.

8.3.15 Jean-Louis Naudin

Jean-Louis Naudin is a tireless researcher in the fields of COP>1.0 systems and processes, and in the field of lifters, inertial thrusters, and possible antigravity systems. His website is a cornucopia of information, patent references, inventions, processes, and replications or replication attempts by Jean-Louis and others who regularly work on such things and communicate with him. The website is http://jnaudin.free.fr/. From there, one may click on the various parts of the site and on the links to other sites to gain a wealth of information on these subjects.

His lifter work, including successful replications and instructions on how to build lifters, can be accessed from http://jnaudin.free.fr/html/lifters.htm, and will keep the interested researcher busy for many productive hours. We especially commend Jean-Louis for his extraordinarily important efforts and for making all this work available to researchers worldwide. Once on the site, one is free to choose from a very wide variety of projects, subjects, etc. The information value of this site is very, very high. We consider Naudin's site to be the single best information site on the web for COP>1.0 system information and for the new space propulsion methodology and effort. Necessary links to other related sites of interest are also provided.

Good hunting!

8.3.16 Other Research Work and Inventions

While we have given a sort of quick overview of work done in this field, there have been many other patents filed by numerous inventors and additional work done by them. This is a dynamic field and it is moving; the biggest problem is that it is still sorely hampered by highly limited funding and an attitude by much of the scientific community that "if it has not been invented here, it doesn't exist".

In the table in Figure 8-3 below, we list some of the pertinent patent numbers for reference, with the emphasis on U.S. Patents. The Naudin website previously referenced has a great deal of information on these thrusters and lifters, including instructions for building and testing several of the simpler proof-of-principle versions. There are links to other sites with even more information. Naudin also includes the results of his successful replication and testing of a variety of these devices and inventions, as well as the successful replication by other experimenters. Naudin also gives construction instructions and information on some of these, so that independent researchers can build test units and test them if desired.

For those researchers interested in pursuing this area further, we would heartily recommend a determined search on the Internet, using Google (www.google.com) as their search engine. A good place to start is Jean-Louis Naudin's web site, and then run the cross-links. The combination will turn up quite an amount of specific material, from which the individual researcher can choose which approach and experimental method he wishes to pursue.

Figure 8-3.

Selected Inertial Propulsion System Patents

T. Townsend Brown, "A Method of and an Apparatus or Machine for producing Force or Motion, British Patent 300,311, Nov. 15, 1928.

Norman L. Dean, "System for Converting Rotary Motion into Unidirectional Motion," USP #2,886,976, May 19, 1959.

T. Townsend Brown, "Electrokinetic Apparatus," USP #2,949,550, Aug. 16, 1960.

T. Townsend Brown, "Electrokinetic Transducer," USP #3,018,394, Jan. 23, 1962.

T. Townsend Brown, "Electrokinetic Generator," USP #3,022,430, Feb. 20, 1962.

T. Townsend Brown, "Electrokinetic Apparatus," USP #3,187,206, Jun. 1,1965.

Henry Wallace, "Method and Apparatus for Generating a Secondary Gravitational Force Field," USP #3,626,605, Dec. 14, 1971.

Henry Wallace, "Method and Apparatus for Generating a Dynamic Force," USP #3,626,606, Dec. 14, 1971.

Fernand Estrade, "Device for Transforming Kinetic Energy," USP #3,807,244, Apr. 30, 1974.

Leo J. Novak, "Centrifugal Mechanical Device," USP #3,810,394, May 14, 1974.

Everett H. Benson, "Inertia Engine," USP #3,863,510, Feb. 4, 1975.

Oscar Mast, "Propulsion System," USP #3,889,543, Jun. 17, 1975.

Arthur N. Lehberger, "Centrifugal Propulsion Drive and Steering Mechanism," USP #3,897,692, Aug. 5, 1975.

Howard A. Gaberson, "Vibratory Locomotion Means," USP #3,916,704, Nov. 4, 1975.

Calvin I. Cuff, "Device for Converting Rotary Motion Into a Unidirectional Linear Motion," USP #3,968,700, Jul. 13, 1976.

Nicholas Joseph Schnur, "Method and Apparatus for Propelling an Object by an Unbalanced Centrifugal Force with Continuous Motion," USP #3,979,961, Sep. 14, 1976.

Calvin I. Cuff, "Device for Converting Rotary Motion Into a Unidirectional Linear Motion," USP #3,998,107, Dec. 21, 1976.

George Knap, "Orbital Propulsion Apparatus," USP #4,087,064, May 2, 1978.

Calvin I. Cuff, "Device for Converting Rotary Motion into Unidirectional Motion," USP #4,095,460, Jun. 20, 1978.

Robert L. Cook, "Device for Conversion of Centrifugal Force to Linear Force and Motion," USP #4,238,968, Dec. 16, 1980.

Ladislaw G. Srogi, "Mechanical Propulsion System," USP #4,242,918, Jan. 6, 1981.

Harry S. Melnick, "Unidirectional Force Generator," USP #4,261,212, Apr. 14, 1981.

Frederick L. Dehen, "Apparatus for Converting Rotary Motion to a Rectilinear Force," USP #4,347,752, Sep. 7, 1982.

Harry S. Melnick, "Mechanical Power Transmitting System," USP #4,398,431, Aug. 16, 1983.

Peter Kleber, "Apparatus for Acceleration-Free Mounting of a Body in a Spacecraft," USP #4,408,740, Oct. 11, 1983.

Fred de Weaver, III, "Propulsion System," USP #4,409,856, Oct. 18, 1983.

Ronald K. Linde, "Centrifugal Reaction Chamber," USP #4,450,141, May 22, 1984.

Fred de Weaver, **III,** "Propulsion System," USP #4,479,396, Oct. 30, 1984.

Joseph Colla, "Mechanical Propulsion System," USP #4,577,520, Mar. 25, 1986.

Elmer M. Dobos, "Propulsion Apparatus," USP #4,579,011, Apr. 1, 1986.

Brandson R. Thomson, "Apparatus for Developing a Propulsion Force," USP #4,631,971, Dec. 30, 1986.

James E. Cox, "Dipolar Force Field Propulsion System," USP #4,663,932, May 12, 1987.

Alvin C. Peppiatt and Alfred J. Peppiatt, "Impulse Drive," USP #4,674,583, Jun. 23, 1987.

Henry North, "Apparatus for Producing a Force," USP #4,712,439, Dec. 15, 1987.

Harry S. Melnick, "Continuous Force and Impact Generator," USP #4,726,241, Feb. 23, 1988.

Oscar F. A. Peterson, "Apparatus for Producing a Directional Unit Force," USP #4,744,259, May 17, 1988.

James D. Mundo, "Universal Propulsion Powerplant and Impulse Drive Unit for Self-Propelled Vehicles," USP #4,770,063, Sep. 13, 1988.

Lancelot I. Kethley, "Gyroscopic Propulsion Device," USP #4,784,006, Nov. 15, **1988.**

Charles Fulop, "Flywheel," USP #4,788,882, Dec. **6, 1988.**

Charles E. Rogers and Fred Van Arsdell, "System for Propulsion and Positioning of a Transitory Object," USP #4,801,111, Jan. 31, 1989.

Paul J. Montalbano, "Conversion of Rotational Output to Linear Force," USP #4,856,358, Aug. 15, 1989.

George J. Zachystal, "Device for Obtaining a Directional Centrifugal Force," USP #4,884,465, Dec. 5, 1989.

James E. Cox, "Dipole Accelerating Means and Method," USP #4,891,600, Jan. 2, 1990.

Hector Serrano, "Propulsion Device and Method Employing Electric Fields for Producing Thrust," WO 00/58623, Oct. 5, 2000.

Brian C. Motts, "Airship," USP #4,967,983, Nov. 6, 1990.

Lyle M. Mason, "Centripedal Device for Concentrating Centrifugal Force," USP #4,991,453, Feb. 12, 1991.

Alexander D. Kidd, "Gyroscopic Apparatus," USP #5,024,112, Jun. 18, 1991.

Paul J. Montalbano, "Conversion of Rotational Output to Linear Force — a Transmission," USP #4,042,313, Aug. 27, 1991.

Andrew T. Rodgers, "Controllable Gyroscopic Propulsion Apparatus," USP #5,054,331, Oct. 8, 1991.

Mortimer S. Delroy, "Gyrostat Propulsion System," USP #5,090,260, Feb. 25, 1992.

Kemal Butka, "Propulsion System," USP #5,111,087, May 5, 1992.

Rex L. Schlicher, Steven M. Rinaldi, David J. Hall, Peter M. Ranon, and Charles E. Davis, "Nonlinear Electromagnetic Propulsion System and Method," USP #5,142,861, Sep. 1, 1992.

Thomas L. Navarro and James D. Isaacson, "Apparatus with Rotatably-Driven Asymmetrically-Accelerated Eccentric Mass for Generating Translational Force," USP #5,150,626, Sep. 29, 1992.

Theordore R. Bristow, Jr., "Method and Apparatus for Converting Rotary Motion to Lineal Motion," USP #5,156,058, Oct. 20, 1992.

John C. McMahon, "Energy Transfer Device," USP #5,167,163, Dec. 1, 1992.

James W. Black, "Non-Linear Propulsion and Energy Conversion System," USP #5,182,958, Feb. 2, 1993.

James R. Taylor, "Electromagnetic Energy Propulsion System," USP #5,197,279, Mar. 30, 1993.

Michael J. Sohnly, "Magnetohydrodynamic Propulsion System," USP #5,211,006, May 18, 1993.

Ross C. Wood, "Stabilization System for a Freely Rotatable Platform," USP #5,256,942, Oct. 26, 1993.

James F. Woodward, "Method for Transiently Altering the Mass of Objects to Facilitate Their Transport or Change Their Stationary Apparent Weights," USP #5,280,864, Jan. 25, 1994.

Robert C. Willis, "Spaceship Propulsion by Momentum Transfer," USP #5,305,974, Apr. 26, 1994.

Harold L. Hull and Donald E. Joslin, "Reusable Mass Propulsion System," USP #5,313,851, May 24, 1994.

Kemal Butka, "Propulsion System," USP #5,334,060, Aug. 2, 1994.

James Harvey, "Impulse Converter," USP #5,335,561, Aug. 9, 1994.

Maurice Mitchell, "Net Kinetic Energy Differential Guidance and Propulsion System for Satellites and Space Vehicles," USP #5,377,936, Jan. 3, 1995.

Howard M. Woltering, "Rotating Eccentric Weights Vibrator System," USP #5,388,469, Feb. 14, 1995.

Richard O. Marsh, Jr., "Centrifugal Force Drive Machine," USP #5,388,470, Feb. 14, 1995.

Kemal Butka, "Propulsion System," USP #5,410,198, Apr. 25, 1995.

Thomas L. Navarro, "System for Generating Controllable Reference Environment and Steerable Translational Force

from Interaction Therewith," USP #5,473,957, Dec. 12, 1995.

Richard L. Lieurance, "Centrifugal Inertia Drive," USP #5,488,877, Feb. 6, 1996.

John C. Claxton, "Centripetally Impelled Vehicle," USP #5,557,988, Sep. 24, 1996.

Ezra Shimshi, "Apparatus for Energy Transformation and Conservation," USP #5,673,872, Oct. 7, 1997.

Richard E. Foster, Sr., "Inertial Propulsion Plus/Device and Engine," USP #5,685,196, Nov. 11, 1997.

James D. Booden, "Electromagnetically Actuated Thrust Generator," USP #5,782,134, Jul. 21, 1998.

George J. Howard, "Propulsion System," USP #5,791,188, Aug. 11, 1998.

Timothy J. Stopplecamp, "Boot Strap Propulsion System," USP #5,831,354, Nov. 3, 1998.

Eric Laithwaite and William Dawson, "Propulsion System," USP #5,860,317, Jan. 19, 1999.

Jonathan W. Campbell, "Apparatus and Method for Generating Thrust Using a Two Dimensional, Asymmetrical Capacitor Module," U. S. Patent # 6,317,310 Bl, Nov. 13, 2001. Assigned to U.S. Government.

8.3.17 Mechanism for the Antigravity Accelerating the Universe's Expansion

Finally, in addition to sorely needed better means of space propulsion, one of the real incentives for antigravity research is provided by the search for a source of the now-established mysterious antigravity that is accelerating the expansion of the universe. Elsewhere in this book we have advanced our own proposal for the mechanism generating that *antigravity* effect in the cosmos.

Simply put, a very violent astronomical process may be considered a giant and very violent discharge phenomena, since it first involves a giant excitation followed by a giant release (discharge) of that excitation. All such phenomena involve strong broken symmetry during the discharge itself, with the concomitant strong available of causal 4-sources of negative energy and negative energy fields. These processes — in their causal unobserved state - do produce locally strong negative energy EM fields from the source causal 4-positrons (Dirac sea holes prior to observation as positive mass 3-space positrons having positive energy and reverse-oriented). When the unaccounted and very large Heaviside nondiverged EM energy flow component accompanying every field and particle interaction is accounted, the causal negative "mass-energy" states produce strong antigravity fields, particularly considering the *lower frequencies* of many of the phenomena.

With the long-neglcctcd Heaviside nondiverged energy component considered and not just the accounted Poynting diverged component, the total amount of negative EM field energy available in these violent process is dramatic. Accordingly, just as was the Sweet VTA in its increased power and its ELF pulsations, these giant astronomical sources are also giant negative "mass-energy" sources and strong antigravity sources as well. In short, such astronomical sources produce strong antigravity components repelling each other across the universe. Hence the observed acceleration of the expanding universe; the violent astronomical phenomena are continually "pulsing" the universe with antigravity and hence continually accelerating its expansion velocity.

In 2000, we also published a proposed mechanism for the source of the excess *positive* gravity holding the arms of the spiral galaxies intact {542}.

8.4 The Author's Engineering Approach to Local Antigravity

See again our discussion under Newton, subparagraph 8.2.1 above, and our discussion of a negative field energy extension to it. For a major laboratory, we believe that antigravity is straightforward,[227] if one first produces a COP»1.0 situation in a higher group symmetry electrodynamics process. This provides a very strong "displacement current" of causal 4-positrons (before parity inversion, time-reversal, etc.) as true negative energy "particles" or "states" or "Dirac holes" in the surrounding 4-vacuum. The actual "negative mass-energy field" is very large, due to the unaccounted Heaviside nondiverged negative energy component. Consequently, a substantial antigravity field is established.

---

[227] However, this is based on the assumption that the lab team first gives up some erroneous but widely held misconceptions, and really does a little "thinking outside the box" as they are prone to suggest.

8.4.1 Sweet Antigravity Test.

See again our discussion in paragraph 8.3.7. A practical realization of antigravity was clearly shown by the Sweet antigravity test designed by the present author. See previous discussion under paragraphs 6.3.2 in Chapter 6, and see again Figures 6-5 through 6-15.

In Chapter 6, the Sweet vacuum triode amplifier device shown in Figure 6-8 had a very large COP = 1,500,000 at 500 watts output with a 33 microamp, 10 volt operator's input. It had an even greater COP when pushed to 1,000 watts output because of only a slightly greater input.

The Sweet VTA used an induced powerful self-oscillation between the local vacuum and the barium nuclei in the barium ferrite magnets. This resulted in what is called a "kinetic" magnet (and one magnetized through its flat face). In a kinetic magnet, its nuclear magnetic field (in this case, in the barium nucleus) is self-oscillating (waving) in an angle about its local direction, as shown in Figure 6-6 in Chapter 6.

The conditioning was performed with the barium ferrite magnet itself in forced resonance at its resonant condition (some 11 to 12 Hz, in the case of Sweet's magnets). Then the 60 Hz signal was impressed orthogonally to the primary direction of the resonant magnet. After conditioning each of the two magnets, they were placed together on a separation box, carefully keeping the corresponding ends together similar to their original orientation during activation, but in attracting mode (through their face) across the separator. The assembly itself was then further conditioned, again orthogonally to the coupled oscillating fields. This "synchronized" the two magnetic self-oscillations and phase-locked them together in a common self-oscillation with the local vacuum.

Similar treatment of the vacuum as a semiconductor, together with self-oscillation between vacuum and nuclei, has been advanced independently by Prange and Strance {543}, who showed that the vacuum may be regarded as a semiconductor. In particular, they showed that the vacuum in the region close to the nucleus of a superheavy element is analogous to the inversion layer in a field effect transistor. It is similarly analogous for the barium atom, though Prange and Strance do not discuss that element. They introduced the concept of the inverted vacuum. Just as a semiconductor may be manipulated by subjecting it to external fields, doping etc., it appears that so can be the vacuum — along the lines shown by Prange and Strance and along the lines demonstrated by Sweet's conditioning of his kinetic magnets.

8.4.2 Bearden's Proposed Antigravity Mechanism

Any EM process that produces a COP»1.0 condition, such as can be done in intensely abrupt ionic discharges and other processes, will also produce intense causal (4-space) Dirac sea holes in the immediate surrounding vacuum. This is the negative energy mechanism, conceived by the author in the 1970s and finalized in the 1980s, for producing a negative energy causal (unobserved) EM field[228] in the immediate space surrounding a system. The overunity system must be the "source" of that negative energy EM field. So the negative energy EM field in surrounding local space is "attached" to the mass and energy dynamics of the "unit's supersystem" as being its "source or generatrix". Its attachment to the system mass produces the antigravitational force upon that mass.

Negative energy state charges (Dirac holes) are also *source charges.* Prior to observation converting them (as observed) to 3-space positive mass-energy positrons with positive energy and going the opposite direction, they must be accepted as negative energy source 4-electrons "pouring out negative energy" in all directions in 3-space, continuously, via the giant negentropy process for source charges. Since they pour out "negative" energy, we may consider that negative energy field action at any point in 3-space to be a continuous absorption of positive energy from 3-space and a return of that extracted energy to the time domain as increased time — in short, time dilation.

Either way one considers it, the 4-space Dirac holes do produce negative energy EM fields, potentials, and spacetime curvatures and these must be accounted during their existence *prior to observation and interaction.* Further, their accompanying giant Heaviside negative energy flow component must also be accounted. In other words, do not reverse the spatial direction and thus the location and direction of these fields, do not turn them into positive energy fields by such reversal of direction, do not turn the negative mass into positive mass, and do not reverse the sign of the source charge (the Dirac sea hole). All that happens after interaction of the Dirac sea holes with matter, forming the usual lattice holes or *observed* 3-positrons.

---

[228] We strongly stress that the continuous, dynamic, ongoing causal 4-field before it interacts with charge and is observed, is a totally different entity from the iteratively and continually observed frozen "effect" 3-field in matter after the 4-field has interacted with charged matter to produce an observation or "event". The great barrier to using electromagnetic fields in practical antigravity application has been due to the substituting, in electrodynamics, of the iterative "effect" 3-field of the observed positron for the continuous "causal" 4-field of the unobserved negative energy 4-electron (the Dirac sea hole). The "effect" 3-field is simply the iterative, continual energy gradient of the diverted EM field energy flow around the assumed intercepting unit charged particle.

Therein lies the magic secret of antigravity. Instead of thinking of the *fields* interacting on the craft or system that is producing them,[229] think of these negative energy fields interacting upon the *local spacetime surrounding the craft or system, and curving that spacetime negatively. Then* think of this negative curvature of spacetime interacting back upon the craft or system in general relativity fashion. *That* is what will and does produce practical antigravity upon the interacted craft or system, once the Heaviside energy flow component is accounted! But to understand its magnitude and the practicality, one must also account for the long neglected Heaviside nondiverged component.

The mechanism is also consistent with general relativity and Wheeler's succinct statement that mass acts on spacetime to curve it, and curved spacetime acts back on that mass to move it or produce a translation force upon it. We are simply applying that fact of general relativity to produce a local antigravity effect of a locally curved spacetime upon the source system (in this case, the power system itself, which is the source of the negative field energy in the vacuum.

The entire notion of "curvature in spacetime" — and indeed of spacetime itself— is a notion applying *before observation and interaction to produce the observed effect* — i.e., prior to the *d/dt* operation occurring upon an ongoing 4-space process to produce a momentary frozen 3-space snapshot (an observed effect). Think carefully. Wheeler's rule does not mean that 3-space acts back on the mass (actually on the masstime), but that 4-space (spacetime) acts back on it. Spacetime does not exist in the observed object after the application of observation's *d/dt* operation has occurred and until a new causal interaction begins. The *d/dt* operation strips away the time, and hence most of the energy (i.e., all the time-energy) of the spacetime that is to do the interacting.

---

[229] The ongoing interaction of the vacuum/spacetime with the source of the unobserved 4-fields is their cause, and the observed 3-fields are the effect. The effect *a priori* does not interact upon the cause! So thinking that "one should make a 3-field in a craft or system that will interact with it and produce antigravity force upon it" is a non sequitur. Instead, one more correctly thinks that "one should make a 4-field *from* a craft or system which will interact with the local spacetime to curve it negatively. Then that negative curvature of spacetime is itself a negative energy 4-field that will interact back upon the observed craft or observed 3-system to produce observed antigravity force upon it.

As source charges, the Dirac sea holes — before observation and in their vacuum state condition — produce a locally curved *spacetime* around the source unit. That induced *(negative energy x time)* curvature interacts back upon the physical system that is the source of the field producing the negative spacetime curvature. It specifically acts upon the mass of the 4-system when it exists as *(mass x time) form.* That interaction produces *antigravity* force and momentum upon the system, rather than *positive gravity* force and momentum[230]. Adding negative EM field energy (in the causal, unobserved state) is precisely the same as adding extra negative masstime, i.e., extra *(-m)t,* since the 4-field is being used in unobserved state.

Using the principle of superposition of fields[231], the external observer sees the "weight" of the unit (the force developed on it by the *net* gravitational field — see again our discussion of the Newtonian approach under paragraph 8.2.1 above) — as being reduced. The intensity of the *negative energy x time (negative angular momentum or negative action)* EM field (including with the Heaviside component accounted) produced by the unit determines the intensity of the antigravity produced, and hence determines the fraction of the unit's weight[232] that is observed to be "lost". See again Figures 6-14 and 6-15 in Chapter 6.

---

[230] Note that, if the Dirac hole interacts with the mass lattice of the system, it converts to a "hole" that is attached to the positive mass of an ion. Hence the "observed" positron is said to have "positive mass", which is a non sequitur for the state in which the "positron" exists prior to observation or interaction. The lattice hole 3-positron and the true spatiotemporal "4-positron as still a negative energy 4-electron'" are two very different entities, and their fields and concomitant field effects are very different.

[231] Note that identification of spacetime and field in general relativity extends the notion of superposition of multiple fields to the notion of superposition of multiple curvatures of spacetime. Thus, it is the *net* superposed curvature of spacetime that interacts back upon the physical mass system, to produce gravity (either positive or negative, depending on the sign of the net curvature).

[232] We remind the reader that the "weight" of an object on Earth is a measure of the force developed on the object by the (Earth's) gravitational field. "Loss of weight" is simply "reduction of that net force" due to the combination of the Earth's positive (attractive) gravitational field and the Dirac hole curvature of the object's local spacetime producing a negative (repulsion) gravitational field.

At sufficient intensity of this local negative energy 4-field in spacetime with the unit as its source, the back interaction upon the unit will balance the action of the earth's gravitational field. At that point, the unit will hover and "float" against the force of terrestrial gravity.[233] By further increasing the intensity of the negative energy EM field, the unit will accelerate upward, now being repelled by the local earth more than it is attracted by it. By "angling" the negative energy EM field direction — or by producing a second such negative energy EM field from the source unit as an "angled add on" superposed on the first one — one also provides unilateral propulsion in a given direction.

As can be seen, all the requirements for a practical antigravity vehicle and negative energy propulsion system are met. The only real problem in this approach is the requirement to first attain a $COP \gg 1.0$ EM power system at ELF frequencies.[234] There is, however, an additional problem of correcting one's thinking to be along the lines indicated.

Antigravity becomes straightforward if one first does overunity discharges or steady output in a system with $COP \gg 1.0$ and understands the difference between the observed "effect" 3-field and the unobserved "causal" 4-field. Sweet's VTA unit had a beginning COP = 1,500,000 at 500 watts output. The unit was pushed to nearly double its COP, by connecting additional load so that the output was now 1,000 watts. The additional input draw was minimal.

Designing the experiment with that in mind, I convinced Sweet to build a new output load unit, and to perform the experiment. In advance, I roughly predicted levitation of the 6-pound device at about 1500 watts output power, by some back-of-the-envelope estimates assuming a 10% efficient process. The projected curve (again see Figure 6-14 in Chapter 6) shows that levitation would have occurred at about 1250 watts or so.[235]

---

[233] Sweet later did push the VTA to hovering and upward acceleration, with the unit on a tether. After he was shot at by a distant sniper, thereafter he was very fearful **and** refused to show many experiments, including the antigravity experiment and particularly its extension to the hover point and upwards acceleration extension. In my opinion he had good reason for his paranoia and his fear for his life.

[234] The reason for ELF frequencies is simple: for the most powerful curvatures of spacetime, one wishes to use EM fields whose photons have the greatest *total* energy (including time-energy). That of course is the lower frequency photons, not the higher frequency photons. So ELF is the way to go, not gamma rays etc.

Here is why we advocate a Dirac sea hole's negative energy field as a practical antigravity inducing mechanism.[236] At COP»1.0, there is a very appreciable vacuum energy density difference between the operator's energy input and the energy output of the system, *particularly when the Heaviside nondiverged energyflow component is taken into account as well as the Poynting energyflow component?*[237] There is a production of negative EM mass-energy x time (causal Dirac sea holes) in the immediately surrounding vacuum. That represents the production of a causal, unobserved antigravitational field (curvature of spacetime) with the system-associated anticharge as its source.

Meanwhile, the Earth's causal, unobserved gravitational field is still normal and unchanged. Now the two causal fields superpose, and interact with the system mass. As seen by the external observer, the net effect is a reduction in the weight of the object — the effect of the interaction of the system mass with the two superposed causal gravitational fields simultaneously.

Reasoning that increasing the COP of the Sweet unit should increase the ratio of output negative energy to output positive energy even further, 1 calculated that doubling the output of the device would result in a sufficiently intense negative mass-energy field in the immediate space around the unit, to approach or reach levitation of the unit. However, as the increasing curvature of spacetime would further increase the deposition of magnetic monopoles in the magnets,[238] at some point the magnets would simply explode like hand grenades if the unit were pushed too far. With no explosive control facilities available, it appeared that doubling the output was the maximum that could safely be done under the circumstances. My own estimate showed that 1500 watts output would be required for levitation, but one dared not go beyond 1000 watts or one would risk a fragmentation explosion and injury or death.

---

[235] I strongly warned Floyd not to exceed a 1 KW load, no matter what. In the resulting local curved spacetime surrounding the barium nuclei in the magnets, it appears that magnetic monopoles are deposited or appear. Since these barium ferrite magnets were made by pressed powder metallurgy, they had little tensile or torsion strength, and under sufficient stress they would explode violently like a fragmentation hand grenade. In his little lab (a converted bedroom), Floyd had no explosive facility. He did explode several magnets, but while cautiously remaining some personal distance from the unit as its output was increased. We warn the reader that experimentation with such procedures is at his own risk, and all proper laboratory safety precautions must be utilized.

[236] A provisional patent application has now been filed on the process in 2002.

[237] In a nominal circuit, the unaccounted Heaviside energy flow may be up to 10^{13} times as great as the Poynting energy flow component. This is a completely unaccounted, vast EM energy flow accompanying every field and particle interaction. Hence one can understand why such an energy density for a macroscopic system with COP»1.0, is sufficient to achieve on a macroscopic scale what LaPointe is attempting on a microscopic scale. The total macroscopic scale energy density is so great that the required LaPointe microscopic energy density {535} is present or approached.

I convinced Sweet to build a 1,000-watt output load box, which simply contained ten sockets for ten 100-watt light bulbs. This was a modification to the 500-watt VTA unit shown in Figure 6-8 in Chapter 6. By successively installing the bulbs one by one, the load could be adjusted in 100-watt increments up to 1 kilowatt.

The foregoing is the reasoning behind how I designed the experiment, and the purpose was to show very substantial and smooth weight loss of the VTA unit itself. The experiment was performed in that 100-watt incremental manner, with highly successful results as shown in Figure 6-14 in Chapter 6.

With each 100-watt increase in power output past 500 watts, the fraction of negative energy produced was greater. Hence the unobserved 4-positron fields (Dirac sea hole negative energy fields) were stronger, because there were more unobserved 4-positrons. This meant that the local negative mass-energy curvature of spacetime was increased also.

In turn, this negative curvature of spacetime interacted back upon the mass of the VTA to add negative mass equivalent, or more simply, antigravity force. The observed weight of the unit was the sum of the normal gravitational weight (due to earth's gravity curvature of the local spacetime), and the abnormal antigravity weight (negative weight) due to the antigravity curvature of the local spacetime superposed. So as the fraction of negative curvature of spacetime increased, the net weight of the VTA was observed to decrease.

---

[238] Contrary to popular opinion, one does meet with effective magnetic monopoles in a magnetic field — including in the magnetic field of a permanent magnet — in a strongly curved local spacetime. The stronger the field, the greater the magnitude of the effective monopole charge.

As stated, Sweet was performing the experiment on the bench in California, and reading the instrumental results over the phone (I was in Huntsville, Alabama) where I recorded them. The spectacular results are shown in Figure 6-14 in Chapter 6.

The high COP (corresponds to gain) of energy density present in the Sweet VTA system's output section — with a greater percentage of it being negative energy — versus input energy one inputs to the input section, is what is important. In short, increasing the load effectively increased the gain, which further increased the ratio of the negative mass-energy to the positive mass-energy. This in turn steadily decreased the observed weight of the object.

Anything outside the system mass of that very high COP system will "see" the weight of the system mass as having decreased. Weight is just so much mass making so strong a *net* G field (spacetime curvature) in the surrounding spacetime. Reduce the *net* G-field that the system mass is normally making (by having it *simultaneously* make the additional antigravity field which then vectorially adds to the mass's normal G-field), and the external observer, external scales, etc. will see the object as having very much reduced its weight.

Positive spatial EM energy density of a system makes positive gravity (as seen by the external observer in the lab frame) because of the way it curves the immediately surrounding spacetime and the way that curved spacetime interacts back on the system's mass-energy. Negative spatial EM energy density makes negative gravity because it curves the immediate spacetime the opposite way. A system under those "high negative energy field" conditions will produce a great deal of antigravity, because the immediate spacetime surrounding is dramatically curved by the negative energy. That was my concept when designing the experiment, and it worked beautifully. So that is how the Sweet device reduced its weight on the bench by 90%, for a 1 kilowatt total output and minuscule input power {544}.

If one were dealing with the source in a flying vehicle system, there is another effect due to momentum. Note that force F is defined as $\mathbf{F} \equiv \partial p/\partial t = +\partial/\partial t\,(\mathrm{mv})$. That is in a positive energy density local spacetime. When an extra negative energy density is added to the local spacetime, then there are two forces, a new one being $\mathrm{F} \equiv -\,\partial/\partial t\,(\mathrm{mv})$ and the normal one being $\mathrm{F} \equiv +\partial/\partial t\,(\mathrm{mv})$. These forces are created by any change in momentum in space containing an extra increment of negative EM field energy.

If the two forces balance, then there is essentially no net centrifugal force produced on the object (or any occupants in it) in a turn. In theory, maneuvers that are far more powerful can be made, without undue G-stress to any occupants inside. This of course remains to be tested in future work and experiments, and so must be taken as a strong hypothesis at present. It could be tested, given availability of the proper COP»1.0 energy system or process on board a test vehicle. Laithwaite's demonstration of the dramatic reduction in force necessary to lift a rotating gyroscope compared to lifting the same heavy gyroscope when not rotating, may have been a partial test of this "inertial resistance decrease" effect.

The Sweet device was the only available COP»1.0 device which could have been used for the experiment. That is why I designed the experiment and convinced Sweet to perform it. Had it not worked, much of what I had worked out for more than a decade would have been falsified — which of course is one of the purposes of experiment: to validate or falsify a thesis. In this case, I breathed a great sigh of relief because — in my view — the spectacular results completely validated my approach to antigravity, and also much of my approach to COP>1.0 systems.

Sweet was never in a position to be able to go with this to the scientific community. The VTA was completely fouled legally, by various entangling agreements Sweet had made with different backers, without ever changing or resolving any previous agreement. Also, he realized that his life really was in danger should he try to take the system openly to the scientific community. Consequently, he never tried and in fact adamantly turned all further work away from the antigravity effects.

Aging and rather defenseless, Sweet also began playing all sorts of games to prevent having to have the project validated independently, even for its COP>1.0 capability. He was mortally fearful of being killed if he had it resoundingly validated. He was motivated by the necessity to survive and not be killed, and he firmly believed that any such attempt for full scientific validation and open publicity would absolutely guarantee his quick death. His fears appear to have been well founded.

His most carefully guarded secret was his activation process for the barium ferrite magnets, which he guarded with his life. He also began telling different persons all sorts of different stories and "mechanisms" for the activation, which were clever ruses and disinformation designed to throw them off the true trail and prevent his activation secret from being uncovered. I made a personal videotape of the activation process, or what he released of it, before he began such disinformation. So we do know much of the activation process, though not all of it.

Eventually, with changes in backers yet once again, Sweet died and never revealed the full secret of strong self-oscillation activation in permanent magnets to anyone. I knew and know part of it, even most of it, but still not all of it. What I understand about it has been briefly included in this book. From there, the interested researcher must find his own way.

The VTA was real, my gravitational mechanism is real, and — in my opinion — validated. However, it has not been *independently* validated in formal order, which is the proper scientific requirement. I did try very hard to convince Sweet that we should take this to the leaders of the scientific community and have it independently verified (e.g., by UCLA), but he would not hear of it after the assassination attempt. By that time, he was so afraid from the constant threats and constant stalkers that he had totally decided against any such releases. He also would not permit it to be taken to a major scientific conference and demonstrated, even though several scientists and engineers knowledgeable and experienced in measurement engineering did measure and certify the device's operation. But they were never allowed to see it in the antigravity mode. He would not discuss it with them, and he would not allow it.

Sadly, with the death of Sweet there passed away the VTA and its major secrets. I regard the VTA as one of the great scientific accomplishments of all time, and I regard Sweet as one of the most capable lab experimenters I ever met and one of the greatest inventors I ever met. The loss of the VTA and the absence of its full, independent scientific testing and validation were in my opinion two of the greatest losses to science of all time.

8.4.3 Discussion

Particle physicists speak of antimass and antigravitational field, but do not speak of anti-electromagnetic field and do not like negative mass. Antimass is actually "anti-mass-energy". When did one hear any scientist speak of a *negative energy* electromagnetic field or *negative energy* force field (except possibly as a hypothetical "tractor beam")? Or a *negative energy* electrical or magnetic potential? Yet the EM fields from an accumulation of Dirac sea holes (causal state) as a source charge are precisely negative energy EM fields. The EM potentials from an accumulation of Dirac sea holes are precisely negative energy potentials. Further, these fields and potentials produce opposite curvatures of spacetime as compared to positive energy causal EM fields and potentials from conventional source positrons and electrons.

Conventionally, scientists speak and think of *the positive energy* electromagnetic field. In our view, they do not apply the implications of the negative energy state part of the Dirac 1930 electron theory {545}, because of a built-in horror of negative mass (and antigravity!). Recall again our discussion of Laithwaite; a promising career was cut down in mid stride because he "mentioned the unmentionable": antigravity and possible failure of Newton's laws (they *do* fail in a curved spacetime!). His exhibiting to the Royal Society a very heavy gyroscope, very difficult to lift when placid, but easy to lift with one arm when spinning, was the final straw. The British scientific community simply cut him down and ostracized him from the rewards and positions he would otherwise have been given.

To conceal the relationship of the negative energy fields, hide negative mass, and pretend it does not exist, much scientific effort is exerted to consider the positive energy, positive mass positron *only after it has been observed.* So scientists can assign this "observed" 3-positron a positive mass and positive energy but with spatial direction reversal. That immediately moves to an *effect* field and an *effect* positron, not a causal field or a causal Dirac sea hole. It effectively eliminates the antigravity field of the negative mass of the unobserved negative energy Dirac electron, which is produced by the *causal* (unobserved) Dirac sea hole's electromagnetic field, not the *effect* (observed) positron field which then is "seen" to have positive mass but with field direction reversed.[239]

The positron is quite a different beast before it is observed, just as is a mass (and just as is any other observable, and just as is a field). For one thing, the positron before observation and the positron after observation have different dimensionalities; the unobserved causal entity is 4-spatial and continuous,[240] while the observed effect entity is continually and iteratively 3-spatial. Mass before it is observed exists as masstime, not mass.

---

[239] Note also that the causal field, being unobserved, is a 4-field, while the observed (effect) field is a 3-field. By reversing the parity, one has made the antigravity field **into** a gravity field, by substituting the effect for the cause and erroneously using the old non sequitur of a separate 3-force acting upon a separate 3-mass. Also, when one reverses its spatial direction, one converts a *positive* gravity field into an *antigravity* **field.**

[240] Along with Bohm, we point out that — strictly speaking — in 4-space one does not have "things", but only "processes". To speak of a "4-space field" is to redefine the field as an ongoing process, rather than as an observed frozen 3-snapshot or "3-thing". The solution to the long-vexing duality problem is there, but we leave its solution to the reader. It is necessary to extend Aristotelian logic itself if one is to resolve the duality problem.

Simply consider the delayed choice two-slit experiment and Wheeler's famous comment that no phenomenon is a phenomenon until it is an observed phenomenon. Once the observation occurs, one can even change the "if it had been observed but was not" previous past. One gets the magic from the delayed choice two slit experiment without the observation, and then by making the observation such that the "magic" is not revoked *after the fact.* The whole experiment proves that, if one insists on applying the observation, one kills the magic, even if one thinks the magic has already occurred and must have already occurred, but it has not been *observed* to have occurred.

Causal 4-spatial "things" are not things at all, but are ongoing processes and their cessations have not "occurred" to yet produce a "thing"! The *observed* event is 3-spatial and has occurred. It is something in the past, not the present. That is different from something ongoing (happening or unhappening)[241] in 4-space, before having been observed and therefore a frozen snapshot taken in 3-space. As is well known in quantum mechanics, observation is a physical interaction and it indelibly changes and stops the "ongoing 4-process", converting it to a momentarily frozen "3-thing" as an effect of the observation process at that particular instant. So any "thing" is continual and iterative, *not continuous,* in its travel through time, and in its "observed existence in 3-space".

Because of such, physicists also have difficulty realizing that mass — being an observable — does not and cannot exist continuously in time. It cannot even *continuously exist!* No observable can. Masstime exists in time, but mass does not, as we previously discussed. Observation is a *dldt* operator imposed upon an ongoing 4-space process, destroying the time portion and producing an instantaneous, frozen snapshot at that instant. It's just *d/dt* (LLLT) => LLL. That is why all observation is 3-spatial, as is well known in physics. We long ago pointed out how the common photon interaction — the total photon interactions (both virtual and observable) with a mass — is what drives the mass through time, so to speak {15}. But it does it iteratively, frozen snap after frozen snap —just like progressively showing the frames of a movie film.

---

[241] When a frozen instant 3-space snapshot (observable) interacts with a second causal process to generate another frozen snapshot (observable), the first observation "unhappens" because it is thereby moved into the "past", disappearing from 3-space forever. With every change of an observable (with every observation), even if the new effect appears identical to the previous one, it is still a *new* observable (a new effect) where a former effect "seems" to have recurred (been created, happened). Even if it is spatially the same as the previous observation output, it is at a different point in time and hence is the result of the *d/dt* observation operator being iteratively applied. The serial outputs — even of what we loosely call an "entity existing in time with no 3-space change" — are *successive and different* serial outputs from a serial time-differentiating process.

What really has to be changed is the old notion by Heaviside and Poynting that 3-energy propagates continuously through 3-space.[242] No observable can propagate continuously in 3-space, but only in 4-space and then only during its nonobservable state! So a "mass propagating through time" (i.e., just sitting still and "existing", so to speak) is doing so in an iterative fashion by recurring iteratively in observation output at the same spatial position. The mass turns to masstime, then to mass, then to masstime, etc. Or $m_1 \Rightarrow m_1t \Rightarrow m_2 \Rightarrow m_2t \Rightarrow m_3\ldots$ etc. In short, *observation continually recurs at an enormous rate,* so *an observable (effect or output of that observation process) continually recurs at an enormous rate,* destroying the previous observation as the next one occurs.

Because of the history of thinking in 3-space terms rather than 4-space terms, one of the ubiquitous errors widespread in physics is the substitution of the effect (the frozen output of the observation process) for the cause (that 4-space initiator process which continuously exists prior to observation, hence unobserved). So causes (4-space initiators which are unobservable a priori) interact with a previous "frozen 3-space snapshot" or observable, to produce a change (either a temporal change or spatial change or both) in or to or of that observable (that 3-snapshot) to a new observable (3-snapshot). If the object is seen to iteratively change in time but not position or form, it is said to "exist" or "persist" at rest continuously in time. It doesn't. It *continually recurs*[243] in that form, but does not *continuously exist* in that form!

---

[242] And also the hoary old mistaken notion that the "same observable thing" can continuously exist in time or persist.

[243] More rigorously, the continual recurrence is at the quantum level. So a larger mass or other observable actually is a great horde of very small "continual recurrences" of tiny incremental pieces of itself. At any time interval of observation via observable photons, a vast number of nonobservable (virtual) "continual recurrences" occur in the "observed object". In short, the "observed object" is the **end** summation and result of a vast number of infinitesimal changes. Hence the entry of statistics and the uncertainty principle. Each one of the infinitesimal

The antigravity mechanism has been implicitly present in the Dirac theory of the electron since his 1930 paper {497}, where he brought forth the Dirac sea and the anti-electron, if the *causal* Dirac sea negative energy states are applied to general relativity before they interact with charge and are "observed". General relativity deals with spacetime and spacetime curvature. Therefore, it is concerned with causal 4-fields, 4-potentials, and 4-waves in 4-space prior to observation.

As we stated previously, there is really no such thing as a "3-space EM wave", e.g., as rather strongly pointed out by Romer {546}.

One can produce and have an EM field of *negative* EM energy in spacetime, coming from the 4-positron charges of the anti-charged mass of a system, as well as one can produce and have an EM field *of positive* EM energy in space, coming from the charged mass of a system. But negative energy EM fields have been swept away from our minds by interpreting the negative energy 4-electron as the 3-positron, after the negative energy 4-electron has interacted with charged matter (been observed as the *effect),* rather than how it exists in spacetime prior to observation (as the *cause).*

So physicists reverse the direction and the charge, and make the mass positive, which is how the Dirac sea hole is "seen" *after observation.* That makes it a material lattice hole and a special kind of positive ion. Before observation, it is not seen at all, but it exists as negative action (energy x time) and therefore in "negative masstime" state form. Before it has been observed, it's still there in spacetime, as a curvature of spacetime. It's just a *negative energy state curvature* in the vacuum/spacetime.

Make lots of these negative mass-energy state Dirac holes from a source system, such as one producing a very powerful negative energy EM field, and voila! That's it. The system is producing — and surrounding itself by — its own negative energy EM field (negative curvature of 4-space), which is also its own local antigravity field. That antigravity field superposes with the prior local curvature of spacetime, altering it. The *net* curvature of local spacetime is itself a field which interacts back upon the mass system to produce "net gravity" whose sign may be positive or negative, depending on the sign of the net spacetime curvature. If the two back-acting curvatures of spacetime are opposite and equal, that represents the source object existing in a zero gravitational field, and thus "hovering" in the Earth's gravitational field, for example.

changes may be modeled causally, but since there is no individual information available on each one of them, they can only be calculated statistically.

The use of negative energy EM fields and Dirac sea holes to alter the curvature of the local spacetime in a negative direction provides the present author's engineering approach to practical antigravity. Note that our approach gathers in the gist of both of the major two approaches to antigravity: (1) the shielding theory as typified by Modanese {547}, and (2) the opposing force theory as typified by Ling Ni and Torr {548}. The opposing force, considered as a field that is identically a curvature of spacetime, is also a "gravity shielding" force via superposition of fields. We state unequivocally that a theoretical model of the new approach can be constructed from Sachs's theory {510}, and implemented in the 0(3) electrodynamics of Evans and Vigier {549}. Further, it is a directly engineerable theory, without the necessity for superconductivity, spinning wheels, etc. as demonstrated by the highly successful Sweet experiment previously discussed.

We quote Evans {550}, on the appearance of the B(3) field in general relativity, to indicate the nature of such a future theoretical model:

> *"I have chosen a metric that gives circular polarization (as observed), but in the framework of general relativity using the irreps of the Einstein group according to the Sachs theory. This is a closed field theory which is analytical, using a Lie group, the Einstein group. As such there are no particles, only spacetime curvature, so everything in physics reduces to spacetime curvature, i. e. to a metric vector and its components. This is then incorporated in the Sachs theory to produce a metric four-vector which is a generally covariant component of a quaternion-valued metric with sixteen components, the most general form of the metric allowed by general relativity and topology. The Einstein-Sachs equations for electromagnetism are six metrical equations in six unknowns, the components of an antisymmetric field tensor of electromagnetism. By choosing a metric that corresponds to circular polarization,* $B^{(3)}$ *appears automatically.*
>
> *This method gives the* $B^{(3)}$ *field from Einstein's theory of general relativity applied to electromagnetism by a consideration of the irreps of the Einstein group. It follows that whenever the conjugate product* $-gA^{(1)} \times A^{(2)}$ *is observed, the* $B^{(3)}$ *field must also be observed, otherwise general relativity fails. Examples of*

> *the $B^{(3)}$ field at work are the inverse Faraday effect and RFR [Radiatively induced fermion resonance]. "*

Evans and the AIAS have already taken the first theoretical steps showing that antigravity does indeed arise from Sachs's theory {551a-551c}.

We are convinced that practical antigravity only occurs at extremely low frequency (ELF) for reasons[244] explained previously. Certainly that seems to be true for our approach to it. The highest "total energy" photon is the low frequency photon with low spatial energy and a larger time increment. The larger time component has the same energy density as mass. So one multiplies the time component increase (in seconds) by roughly $9x10^{16}$ to get the increase in spatial energy equivalency. Halve the frequency of a photon, and one increases its *total energy* by $4.5xl0^{16}$ {552}.

High energy physicists have not realized that the time component of the photon has enormously more energy than the spatial component, and that low frequency photons contain enormously more trapped energy than do high frequency photons. So they largely ignore the time-energy component, focus on the spatial energy component, and erroneously consider *high energy* physics as *high frequency* photon physics. Instead, present high frequency photon physics is only a high *spatial* energy physics, not a high *total* energy physics at all. Today's high energy physics is really still a very low total energy physics, compared to what can be done with the time-energy component of the photon rather than its spatial-energy component. By transducing and using the highly compressed time-energy, experiments can be done on the lab bench with fairly simple and cheap equipment, that actually utilize *higher total energy nuclear reactions* (though at low spatial energy) than are presently obtained in the largest accelerators.

That is also why there is presently no understanding in the conventional community of the "low spatial energy transmutations" of cold fusion, where the experiments unwittingly use the high time-energy component. The scientific community has not even recognized the time-energy aspects, and has not recognized that time-energy physics is an ultrahigh total energy physics, where the present "high energy physics" is tame by comparison.

---

[244] Dramatic increase in the magnitude of the time-component, hence an enormous increase in the time-energy component with only a small decrease in the spatial energy component total energy of the photon. The *total energy* thus dramatically increases, when the spatial energy equivalent of the time-energy is considered. The present conservation of energy law in physics is inadequate because it does not account time energy at all; thus completely discards the most fundamental EM energy mechanism of all: the giant negentropy of source charges and source dipoles.

The previously unknown time-energy induced transmutation interactions are the precursors to, and the opening salvo of, a new *ultrahigh total energy physics* struggling to be born in spite of the adamant opposition of the conventional scientific community. Allowing for the time-energy component, for the mechanism generating the flow of time, and for formation and decay of time-reversal zones, we previously wrote the exact new nuclear reactions for the production of the excess deuterium, tritium, and alpha particles {553} in numerous cold fusion experiments. We also explained the highly anomalous nuclear instrument effects — due to (i) time-charging, (ii) the slow decay of time-charge with radiation of Whittaker longitudinal waves, each accompanied by its phase conjugate twin time-polarized wave, and (iii) the previous time-charge history of the instrument. These puzzling anomalies have been observed at U.S. Navy research facilities at China Lake now for some years in rigorous electrolyte experiments {198}. We summarize that work in Chapter 10 of this book.

With a little effort and development, practical antigravity appears to be straightforward for any good modern laboratory. But the lab physicists should first (i) rethink the entire subject, from its very fundamentals, to include considering the positron before observation and not after observation, (ii) remove the Lorentz symmetrical regauging from electrodynamics and recover the presently missing COP >1.0 and COP»1.0 Maxwellian systems again, and (iii) rapidly develop COP»1.0 systems and processes to use in antigravity experiments and development. At least in this approach, the COP»1.0 EM systems — once developed — are an immediate gateway to practical antigravity devices, unilateral thrust propulsion systems, and antigravity vehicles. And of course they are the immediate gateway to practical transport vehicle power systems, fuel-free, clean, and self-powering.

Hopefully, such a scientific reassessment will be performed, and it may provide the gateway for practical transportation and travel to the ends of **the** solar system and beyond, to be achieved in the first two decades of this century.

8.5 In Conclusion

We have briefly reviewed the presently developing field of inertial space propulsion and antigravity, and presented our own approach to practical antigravity as well as an informal experiment that strongly supported that approach. We have strongly stressed that the causal field from the system as its source constitutes a curvature of the local spacetime superposed upon the pre-existing local spacetime curvature. Instead of thinking of that causal field from the source system as acting back upon the source system, we have stressed thinking of that *net superposed curvature of local spacetime* acting back upon the source system and producing a net gravitational force upon it. That net gravitational force may be either positive or negative, or zero, depending upon the sign of the net curvature of spacetime that is interacting back upon the system.

We presented and explained the results of the Sweet VTA antigravity experiment as probable verification of our approach to antigravity. Nonetheless, we also emphasized that the formal independent replication required by the scientific method has not been accomplished, and it remains to be accomplished before the approach is to be considered as scientifically validated.

We believe that this approach to antigravity can be modeled and engineered by use of the Evans-Vigier O(3) electrodynamics as a subset of the Sachs electrodynamics that is a part of the Sachs unified field theory.

If so, then tentatively we have laid out the basis for eventual practical antigravity systems and a practical antigravity technology. We fervently hope that this approach will in fact lead to practical technology and working transportation means during the next decade.

Finally, we hope that these notes and concepts will stimulate many sharp young graduate students and post-doctoral scientists to examine, model, correct, and greatly enlarge the ideas and principles advanced. If so, then the purpose of this chapter will have been realized.

Chapter 9

The Supersystem and Remarks on Gravity, Antigravity, and Testing

"What might appear to be empty space is, therefore, a seething ferment of virtual particles. A vacuum is not inert and featureless, but alive with throbbing energy and vitality. A 'real' particle such as an electron must always be viewed against this background of frenetic activity. When an electron moves through space, it is actually swimming in a sea of ghost particles of all varieties - virtual leptons, quarks, and messengers, entangled in a complex melee. The presence of the electron will distort this irreducible vacuum activity, and the distortion in turn reacts back on the electron. Even at rest, an electron is not at rest: it is being continually assaulted by all manner of other particles from the vacuum." [Paul Davies] {554}.

"Space acts on matter, telling it how to move.. In turn, matter reacts back on space, telling it how to curve." [Wheeler's principle] {555}.

"...the Aharonov-Bohm effect is a local gauge transformation of the true vacuum... [which] produces a vector potential from the true vacuum. [This gauge transformation] produces topological charge..., the electromagnetic field, which carries energy, and the vacuum charge current density first proposed by Lehnert... and developed by Lehnert and Roy... ". [M. W. Evans and S. Jeffers] {556}.

"The energy density (En_d) in curved spacetime

is given in the Sachs theory by the quaternion-valued expression

$$En_d = A_m j_m^* \qquad [1]$$

where A_μ is the quaternion-valued vector potential and j_m^* is the quaternion-valued 4-current as given by Sachs ...Equation [1] is an elegant and deeply meaningful expression of the fact that electromagnetic energy density is available from curved spacetime under all conditions; the distinction between field and matter is lost, and the concepts of "point charge" and "point mass" are not present in the theory, as these two concepts represent infinities of the closed-field theory developed by Sachs from the irreducible representations of the Einstein group. The accuracy of expression [1] has been tested to the precision of the Lamb shifts in the hydrogen atom without using renormalization of infinities. The Lamb shifts can therefore be viewed as the results of electromagnetic energy from curved spacetime." [Myron W. Evans] {557}.

"Old habits of thought die hard, and it is not always easy to remember that a particle with negative mass if pushed to the right will move to the left; or that in a given reference frame a particle with imaginary mass can have infinite speed, in which case its energy is zero." .... "... extremely powerful energy sources may occur if particles of negative mass really exist in nature. " [Banesh Hoffman] {558}.

"The observed (3-spatial) positron is a quite different entity from the unobserved (4-spatial) Dirac hole. Its direction has been reversed, and its mass and energy have also been reversed. Before the 4-spatial hole in the vacuum has interacted and been observed, it has negative energy and therefore negative mass equivalency, as well as negative charge. As a source charge, it also is the source of negative energy fields and negative energy potentials — all in the

nonobservable 4-state. " [T. E. Bearden, private communication to a correspondent, 2001].

"The...visible structure of orthogonal' 1-networks possessing coupled open-paths and closed-paths represents only an introductory step in the development of a correct topological theory for conventional electric networks...An electric network is like an iceberg...Its visible portion is only a small fraction of the submerged invisible structure. " [Gabriel Kron, who developed special tensor methods and diakoptics to deal with the large number of visible and invisible multidimensional p-networks surrounding the branches of every electric circuit.] {559}.

"...symmetry implies conservation. Since our entire edifice of interactions is built on symmetry assumptions, there should be as a result a large number of conservation laws. The only trouble is that almost all of these conservation laws have been violated experimentally. "... "...this difficulty could be resolved by introducing a new element, the vacuum. Instead of saying that the symmetry of all matter is being violated, we suggest that all conservation laws must take both matter and vacuum into account. If we include matter together with vacuum, then an overall symmetry could be restored" [T. D. Lee] {560}.

"One perhaps oversimplified way to deal more conventionally with the new unified field approach to electrodynamic systems is to utilize the notion of the 'supersystem', comprised of three components: (I) the ordinary EM system and its dynamics—conventionally assuming flat spacetime and inert vacuum, (2) the local nonlinear vacuum and its dynamic interactions with the system and with spacetime, and (3) the local curvatures of spacetime and their dynamic interactions with the system and with the local

> *active vacuum. In the rich feedforward and feedback interactions that result, there emerges a dramatic new physics, new electrodynamics, and new chemistry including a new biochemistry. This is in fact a much simplified conceptual approach (good to 'first order', so to speak) to the multinetwork and multipath work of Gabriel Kron. It also allows the retention of symmetry, considered so necessary to particle physicists. "*
> [T. E. Bearden, private communication to a correspondent, 2001].

9.1 The Supersystem and Its Considerations

In classical electrodynamics, the Maxwell-Heaviside-Lorentz equations implicitly assume a local flat spacetime and no net action by the vacuum {561}. Both these implied assumptions are false. All real EM systems involve interactions with both curvatures of spacetime and the active vacuum. Yet to try to include both additional interactions requires a unified field theory approach, such as that of Sachs {562}. Unfortunately, any unified field theory is replete with quite difficult mathematics, little of which can be illustrated pictorially or simply.

What is required — at least for most electrical engineers and applied electrical scientists — is a conceptual way of visually thinking about the EM system in a way that is consistent with unified field theory to something like first order, but which can also be conceptualized easily.

9.1.1 The Supersystem Concept

Accordingly, we introduce a new and very simple way of thinking of electrical circuits in terms of a unified field theory. We utilize the notion of the supersystem, consisting of three components: (1) the EM system and its dynamics, considered in conventional fashion (as if the local vacuum were inactive and the local spacetime were flat but perturbed), (2) the local interactive vacuum and its dynamics, and (3) the local curvatures of spacetime and their dynamics. All three components of the supersystem interact. This produces both feedback and feedforward functioning; e.g., energetic changes in the system produce corresponding changes in spacetime curvatures. In turn, the alterations in spacetime curvature produce nonlinear changes in the active vacuum, which in turn acts back upon the system. So every action in a system produces a corresponding set of feedforward and feedback reactions from and with its complex environment, and vice versa.[245]



Figure 9-1 The Supersystem concept (block diagram).

Figure 9-1 shows a diagrammatic illustration of the supersystem concept. Figure 9-2 illustrates the effect of the classical EM assumptions of a flat spacetime and a locally inert vacuum. As can be seen, the classical assumptions *arbitrarily discard the* interaction effects upon and in the system due to the active vacuum dynamics and due to the local spacetime curvatures and their dynamics.[246]

As stated, all three components of the supersystem interact with each other. This is a dramatic change to classical U(1) electrodynamics. Hence the total interactions — with the system — of both the active vacuum and the locally curved spacetime, and their interactions with each other, are more general than either classical EM, general relativity, or the quantum mechanical vacuum of particle physics prescribes individually.

---

[245] We hypothesize that the feedback contains the mechanism generating Newton's third law as a restoration of symmetry, but leave that to the master theorists to explore and decide.

[246] As one example, the nondiverged Heaviside component of energy flow — previously discussed in earlier chapters — is part of the supersystem activity. This **flow** alters both the local active vacuum and the local spacetime curvature associated with an electrical power system and its connected external circuits. Since the resulting local "environmental" changes in the supersystem are extensive, then one can conceive ways in which these changes can be interacted with additional intercepting/receiving systems to produce extra "EM energy from the vacuum".



Figure 9-2 Classical EM destroys two-thirds of the supersystem.

Immediately it can be seen that the concept of energy from the vacuum is a "supersystem active and not negligible" concept involving a unified field theory approach *a priori.* It can also be seen that a "system" in equilibrium must be in equilibrium with its active environmental exchange — its exchange with the active local vacuum and the active local curvatures of spacetime. Since energy "exchange" with the system means both incoming and outgoing exchange, it follows that the equilibrium system has equal incoming and outgoing energy exchange. It follows that the symmetrically regauged system has equal incoming and outgoing energy, and so the symmetrically regauged system must be in additional stress from two net equal and opposite direct interaction forces, one general relativistic and the other from the active vacuum. Further, this "equal and opposite" equilibrium stress state must be accompanied by equal and opposite interaction effects between the two environmental media of the system.[247,248]

---

[247] We point out but do not pursue the fact that this is a very important new concept associated with *coherently* changing the symmetrical regauging, which allows a new physics, a new electrodynamics, and a new chemistry including biochemistry. For one thing, it permits such things as a self-maintained excitation state that simultaneously continuously discharges its excitation energy. This is simply a redefinition and more general broadening of the "source charge" concept. From the normal system view (assuming away the vacuum and curved spacetime interactions), an "impossible" system state can nonetheless be possible and stabilized, by changing the *intensity* of the Lorentz regauging condition. As an example, new molecules or ions can be made and stabilized in an excited state, that otherwise would be so unstable that the excitation would decay in a nanosecond with the state disappearing also. We believe this alone will lead to a great new biochemistry and medical

9.1.2 Time and Space Effects and Positive and Negative Energy

From curved spacetime considerations, we must include the effects on the system, and on the vacuum, of dynamics in the *time* domain as well as in the *spatial* domain. Indeed, in Sachs's theory space and time do not separately exist, but only spacetime. We consider time as highly compressed EM energy — as heretofore pointed out, where time is spatial EM energy compressed by the factor c^2 and having energy density similar to mass. We must include not only EM *energyflow* along the time-domain (fourth Minkowski axis *ict),* but also EM *force, potential, energy oscillations*, etc. in the time domain itself. We shall have to deal with time-force, time-energy, time-potential, time-energy current, longitudinal EM waves in the time domain (time-polarized EM waves), etc. {563}. The complexity of the full supersystem analysis is thus easily seen and appreciated. In most cases, a higher group symmetry model for a particular situation will prove intractable for closed solutions, and numerical methods must be used.

Further, when curved spacetime interacts with the active vacuum, we shall also have to consider *negative energy* currents in the nonlinear vacuum itself, as well as in the time-domain. We may also speak of the *negative energy density* in the vacuum as a special kind of negative energy *potential* in the vacuum that is created by a negative energy potential in the time domain. We may speak of a gradient in this vacuum negative energy potential as a negative energy force or "force in the negative energy domain". Applied to the time domain, these concepts constitute a causality condition placed on the Dirac sea, in the same vein as more technical causality considerations given by Finster {564}.

9.2 Differences between Effects in COP»1.0 and COP<1.0 EM Systems

In this chapter, we utilize the Dirac hole in a different manner from the received interpretation. The received interpretation assumes an electron hole in the vacuum, with the hole filled with a negative energy electron

---

therapeutic science; one company is already working in this area, with positive results.

[248] We leave to the advanced theorists the connection between this "stable equilibrium state under a change in symmetrically regauged stress", occurring as a *net-force-free* intensity change in the conventional Lorentz symmetrical regauging of the Maxwell-Heaviside equations.

having negative mass, negative energy, and negative charge. In that interpretation, when the electron is lifted out of the hole, the hole is said to be *a positive energy* electron with positive mass and positive charge, (i.e., when interacted and observed). In short, with reaction one has a complete transformation of negative energy into positive energy, negative mass into positive mass, etc. In our view, this totally destroys the notion of "how the hole exists in the vacuum prior to its interaction and observation". That kind of positron only occurs after a physical interaction and observation has occurred — in short, *the positron exists only after an interaction with the Dirac hole has been made, to change the very nature of the negative energy hole.* The positron is the 3-effect of an invoked extra 4-interaction, and is not at all the "negative energy electron" or hole as it actually exists prior to being interacted and transformed. The positron is a different beast from the beast we wish to harness and use. The conventional interpretation leaves the question of the unobserved and unreacted "hole" left behind by an electron lifted out of the hole, before another interaction is performed on the hole to change it. So it is an incomplete accounting (as all observations are).

In our interpretation, the Dirac "hole" in the vacuum is itself the true negative energy electron before its interaction and observation. It is the "causal" 4-space negative energy electron, while the received interpretation is only for the "observed" or "effect" positron. In our view, the received interpretation thus leaves out a goodly part (and the most interesting part) of the Dirac sea hole. When the negative energy hole is filled, we consider the *electron* in the hole to be a normal, positive energy, positive mass electron. Hence the summation of the energy of the filled hole is zero, as is its summation mass and its summation charge. This accords with the properties of the "normal" vacuum, said to contain a sea of such "filled Dirac holes".

Our purpose is to use *emptied* Dirac sea holes before their interaction or observation, and thus to use them as *causal 4-electrons having negative mass and negative energy, but where each of those quantities is multiplied by time. So the hole has negative masstime and negative action.* Unless otherwise stated, that is our interpretation of a Dirac sea hole, and that will be how we use it. This way we avoid having to replace a true negative energy, negative mass, positive charge causal (unobserved) 4-electron by a positive energy, positive mass, positive charge observed (effect) 3-electron. We do not just artificially "dispose of" the question of the "nature of the hole that is left behind" when the positron is observed. We consider the (hole x time) as the fundamental negative energy 4-electron. We will sometimes refer to that as the "4-positron".


Normal "forward flow of time" tempic force
1.0
<1.0
Holes mostly locally confined
by forward time tempic force
and local recombination
i
BATTERY
+
FUNCTIONING
SYSTEM
NORMAL
RESISTOR
LOAD
i
A few empty Dirac sea holes
negligible Dirac hole current ignored
0.0
Input
COP<1.0 Circuit/System
Output
Immediate
recombination of
Dirac holes with
virtual Dirac
electrons

Figure 9-3 Time potential gradient across a COP<1.0 EM system.

See Figure 9-3. In a COP<1.0 EM system, the tempic potential gradient (tempic force) is oriented from input to output and on out beyond the system. A very slight Dirac hole current moves outward from the output, but is immediately "eaten" by the virtual electron flux fluctuations of the vacuum in the space immediately adjacent to the output. There is a slight Dirac hole current also exiting the system in its losses, but again these are immediately "eaten" by the virtual electron flux fluctuations of the vacuum in the immediately surrounding space.


No excess tempic force
1.0
1.0
Φ_T
Φ_T
Lattice holes gently released.
Electron-electron pairing.
Well-behaved below
transition temperature.
FUNCTIONING SYSTEM
i
BATTERY
+
Cooper pairs, excitons
NORMAL
RESISTOR
LOAD
i
Occasional empty Dirac sea hole
Vanishing current because zero tempic force
0.0
Input
COP = 1.0 Circuit/System
Output

Figure 9-4 Time potential gradient across a COP = 1.0 EM system.

See Figure 9.4. In a superconductive system or section, COP =1.0 and on the average there is no net gradient of the time potential across the system, hence no time-force across it in either direction. Accordingly, one sees ready Cooper pairing of charges and formation of excitons. We shall not concern ourselves further with the superconductive EM system; such a system has not yet produced COP>1.0.


COP > 1.0
Additional tempic force
Dirac hole current will "eat" some of the electrons by recombination
1.0
Dirac holes forced from many local areas.
Some pairing, many broken.
Dirac hole current formed, flowing, amount varies with tempic force, so with COP.
FUNCTIONING SYSTEM
i
-
+
BATTERY
Dirac hole current flowing at sufficient COP
NORMAL RESISTOR LOAD
i
0.0
Input
COP > 1.0 Circuit/System subsection
(section in disequilibrium with vaccum)
Output

Figure 9-5 Time potential gradient across a COP»1.0 EM system.

See Figure 9.5. In a COP>1.0 EM system, there is a net tempic force across the system from the output section to the input section. However, unless the COP»1.0, the hole current in the local vacuum is mostly used up in interacting with the system material and converting to lattice holes (lattice positrons). Hence at "nominal" or moderate COP>1.0, except in fast pulsed discharges one *usually* has little to worry about, concerning Dirac sea holes in the vacuum, since those readily convert to lattice holes as already accounted. One effect of concern is that, if the semiconductors in the system are exposed to sufficient extra lattice holes or interacting 4-holes, their donor-acceptor arrangement is disrupted, spoiling the action of the semiconductors and perhaps destroying them.

When COP»1.0 (and even for some COP>1.0 systems), then there results a substantial Dirac sea hole current in the local vacuum occupied by the system, flowing through the supersystem from the output section back to the input section. This is an additional hole current component from the

Dirac hole current component converted into lattice hole current.[249] This unconverted Dirac sea vacuum hole current runs through the system from the output section back to the input section of the system and beyond. If not "filled" there in the input section by the incoming input electrons from the external power supply, the 4-hole current can and will pass on back into the feed line and to the distant external power supply, *eating electrons and electron current all along the way.* Usually semiconductors in the path of a substantial 4-hole current will either malfunction or be quickly destroyed.

In the input section and on back into the external power source, the effect of the unrestrained Dirac sea hole current's reaction is to interact and convert into lattice holes all along the route, which lattice holes then "eat" incoming electrons from the distant power source. Thus, the external power source "sees" the hole current as a dynamic additional load in the system's input section itself (and in the external conductors leading to it) *that also must be powered with additional positive energy electron current.*

---

[249] Here we wish to recognize the perceptivity of Peter Lindemann, who recognized the importance of "cold electricity" in COP>1.0 systems without going deeply into the more technical aspects of negative EM energy. As an example, we cite his book, *The Free Energy Secrets of Cold Electricity,* available from Clear Tech, Inc., Box 37 Metaline Falls, WA 99153, U.S.A. Particularly note his efforts to explain the Gray overunity device via the negative energy that can be associated with very strong discharges. Gray referred to this appearance of an associated negative energy component associated with the normally positive EM energy as "splitting the positive pole" (a "pole", after all, involves a stress potential). The Gray engine drawing is shown in Figure 5-14, his conversion tube is shown in Figure 5-15, and his circuit for the conversion tube is shown in Figure 5-16. As Lindemann explains, Gray also apparently succeeded in converting the negative energy into positive energy in his conversion element switching tube. Bedini's successful replication of the tube along with pertinent lab notes are shown in Figures 5-17, 5-18, 5-19, 5-20, and 5-21 by permission. Since Bedini is one of only two or three persons truly experienced in converting negative energy into positive energy, his successful replication is significant and decisive. Gray's process thus transformed negative energy into positive energy, allowing positive energy COP>1.0 self-powering systems. Bedini and the present author have filed a joint patent application filed on the process explained in this Chapter. We recognize Ed Gray as being a real pioneer in the area of COP>1.0 electrical power systems and in energy conversion. His pertinent patents are E. V. Gray, "Pulsed Cap. Electrical Discharge Engine," U.S. Patent #3,890,548, 1976; "Efficient Power Supply Suitable for Inductive Loads," U.S. Patent #4,595,975, **June 17, 1986.**

Aside from destruction of semiconductors etc.,[250] the overall effect is to increase the draw of power and current from the external source, so that the COP» 1.0 power system is thereby converted back to a COP<1.0 system!

The increased power draw due to the Dirac hole current can be remarkable. For an external battery power supply, if the hole current is sufficient to pass on into the battery itself, the battery may *charge* with negative energy while also powering the circuit! A remarkable phenomenon then takes place. A battery having been appreciably charged with negative energy may appear to be discharged (and so it is, with respect to positive EM energy). Yet, it may also continue to power a circuit. Sometimes it will, sometimes it won't, depending on the circuit. However, on connecting a normal positive energy battery charger to recharge it, the battery *precharged* significantly with negative energy will "eat" positive energy for an extended period, filling its localized Dirac Sea holes in its negative charge all the while, with the external voltage of the battery not changing at all. When all the negative energy holes are filled in the internal vacuum environment of the battery, and the negative energy charge is thus removed, suddenly the battery will start recharging with the input positive energy in a normal manner.

The batteries in Watson's generator (again see Figure 5-12) exhibited that phenomenon. Sometimes in recharging one of his batteries that had been extensively used, the battery would "eat" positive energy from the charger for a week or more before finally filling up its negative energy charge and then recharging normally from that point on.

The Dirac 4-hole current is nature's decay mechanism for the COP»1.0 system, sharply bringing it back to COP<1.0. Any successful COP»1.0 EM system must contain a mechanism for defeating (or transducing and using) this Dirac sea vacuum 4-hole current into its input section and beyond. We shall cover that subject shortly. The 4-hole current decay mechanism can *sometimes* become significant for semiconductors in the lattice 3-hole stage at COP = 5 or more, though the exact figure varies as the type and size of system and the semiconductor type. At COP > 10 or so, some systems will frequently begin to ravage themselves back into equilibrium with the vacuum, and destroy their overunity performance, unless the 4-hole current phenomenon is dealt with.

---

[250] As an example, novel effects may also happen in resistors, capacitors, and coils, and the effects depend on both the materials and construction of these components. A resistor can act as a true negative resistor and cool rather than heat, a capacitor can have its current lagging its voltage, and a coil can have its current leading its voltage. Mixtures of all three of these effects can happen in each of the three components, since each usually has some aspects of resistance, capacitance, and inductance. The emfs and back emfs in the circuit can also be altered and disrupted in a manner varying with the individual circuit and the individual operating conditions. Nonlinear oscillations and discharges of negative energy are particularly difficult to foresee and understand. Effects in dielectrics may vary widely, as can effects in conductors because of their internal impurities, etc.

Let us recap. We have assumed — to first order — a sweeping generalization that COP<1.0 systems exhibit an overall average spacetime curvature across the system (from input section to output section and load) such that excess positive energy electrons exist in the Dirac sea, without any appreciable accompanying excess Dirac sea holes interacting in the circuitry itself.[251] The slight excess of Dirac sea holes that are generated is "swept" forward out of the output section, and "eaten by the vacuum interaction" (particularly by the vacuum fluctuations) immediately upon exit from the output section. In that case, we do not have to concern ourselves particularly with Dirac Sea 4-holes and Dirac sea 4-hole currents, or at least they are usually negligible in most cases.[252]

For COP»1.0 systems, however, the overall average spacetime curvature across the system — from output section and load to input section — is such that Dirac sea 4-holes and their currents do independently continue to exist and independently flow in the local vacuum occupied by the physical system. Specifically, we shall have to consider the *tempic* effects upon such holes and hole currents, which are oriented from the output section back through the system to the input section.[253] In the COP»1.0, the effect of the increased tempic force is to sweep a Dirac sea 4-hole current back through the system from output to input, and even on out into the conductors from the external power supply, and on further out into the external power supply itself. The 4-hole current continues its "reverse feedback into the powering end of things" until quenched by filling it with incoming electrons. This conversion of 4-hole current to filled Dirac sea 4-holes by induction of lattice holes also squelches the concomitant negative EM energy fields, potentials, and waves associated with Dirac 4-holes as sources.[254] The reason is that a filled Dirac hole is a dual system of two opposite charges, hence produces counteracting positive and negative energy fields.

---

[251] In short, the requisite number of Dirac holes have interacted with and do interact with the lattices, converting into the normal "lattice hole" type of positron connected with positive mass, positive energy, but slowly migrating around the circuit in the opposite direction from the electrons. Here the true Dirac hole current exists only in short "hops" from atom to atom as the lattice holes are steadily filled by the "hopping" electrons.

[252] As stated, a kind of "hole" phenomena still exists in the circuit, but now as lattice holes and currents. Since these are attached to ions each having a mass much greater than that of an electron, the lattice hole currents may usually be neglected except in semiconductors, where they are taken into account in the very design of the semiconductor component itself.

[253] When we state a concept such as "negative mass" or "negative energy", we have conceptualized it *as if observed.* Hence, unwittingly we have made it an instantaneous, but iterated, concept. Rigorously, no such thing as mass or energy

The "4-hole-eating and filling process" is therefore the exact decay mechanism that squelches the natural electrogravitation associated with Maxwellian circuits which use Dirac 4-holes and 4-hole currents, negative energy fields, negative energy potentials, etc. When the circuit converts its free Dirac 4-holes into lattice holes, all electrogravity capability is lost, insofar as practicality is concerned.

For electrical power system purposes, the external environment of the COP»1.0 system furnishes an extra "electrical load" demand upon the external power supply, so that the extended system consisting of the (external power supply + power system) decays back into overall COP<1.0 condition and operation. For this reason, any appreciable involvement of Dirac 4-hole currents in a COP>1.0 EM power system must be *transduced* into positive energy electron currents, which requires just a special form of regauging. One need not confine regauging and gauge freedom to positive energy potentials and positive energy fields alone.

From the vacuum consideration and particularly from Dirac's theory of the electron, in COP>1.0 EM systems and circuits we shall consider that the Dirac sea 4-holes involve negative energy states (negative mass), and that positive energy states involve positive mass. In our approach, we shall consider a negative energy state (Dirac 4-hole) in the vacuum as having

---

independently exists except at one instant in time. Instead, mass exists in a continual iteration of *m* —> *mt* —> *m* —> *mt*... and energy exists in a continual iteration of *E* —> Et—»E—» *Et*.... and so on. So during the masstime or energy-time (action) state, time and either mass or energy are intimately interactive. See our previous discussion in this book of the mechanism for the flow of a mass through time.

[254] Obviously that kills the antigravity aspects, because it kills the negative energy fields that would give negative curvature of local spacetime.

negative mass, which means that antigravity can be involved as well.[255] In this treatise, we consider only electron states, thus only negative energy and positive energy electron states.

9.3 Primarily Concerned With Dirac Sea Holes and Not Lattice Holes

We also stress the dramatic difference between a Dirac sea "electron 4-hole" in the vacuum (prior to observation) as compared to a lattice 3-hole in a semiconductor or other material component (after interaction and therefore after observation). In the case of a lattice 3-hole, usually the "positron" (hole) is attached to an ion, whose mass (i) is very much greater than the mass of an electron, and (ii) is also positive. In other words, a lattice hole is just a part of an ordinary positive ion. So the theory of "lattice holes" and "lattice positrons" does not primarily apply to the situation we are discussing. On the other hands, semiconductors exposed to any significant currents of pure Dirac sea 4-holes in the vacuum usually react and are nearly instantly destroyed because of the immediate disruption of their donor-acceptor arrangement and functioning. Interaction (filling the incoming Dirac 4-holes with contributed electrons) causes sudden mass disarrangements in their atoms and nuclei and lattice bonds. Thus, in the presence of Dirac sea 4-holes and 4-hole currents, usually any interacting solid-state electronics of the circuit or system will be dramatically affected. For switching in the presence of holes and hole currents, in most cases one may have to turn away from semiconductors and utilize mechanical or electro-mechanical switching, although this requirement varies with the type of semiconductor, the COP, the system geometrical layout, and the subsystem operations and layouts. Sometimes semiconductors may still be used if they are "brutes", with current handling capabilities well beyond what is "normally expected" in that circuit.

---

[255] We assume that the important thing about mass is its localized energy. Hence we associate positive mass with positive localized energy (with respect to the ambient energy density of the massless vacuum) and we associate negative mass with negative localized energy (with respect to the ambient energy density of the massless vacuum). In this view, the empty Dirac sea hole has both negative energy and negative mass. Note that this differs from the conventional assumption, which unwittingly addresses the positron as having been observed, producing a directional reversal. The rigorous test of our thesis is that concentrations of Dirac sea holes *must* generate antigravity *potential,* while currents of Dirac sea holes must generate antigravity *force.* The conventional view, assigning positive mass to the positron after observation, would produce gravity, not antigravity, but the force would be reversed by the reversed parity after observation. We argue that antigravity has been hidden and lost by its parity reversal in the assuming positive mass for the positron *as if that were the mass of the positron before it is observed.* In an overunity system with powerful steady-state Dirac 4-hole currents, the 4-hole currents can be differentiated by the cooling (negentropy) effect of the COP»1.0 system—when shorted to produce a "current surge" — rather than heating (entropy) effect. The magnitude of the hole current (which determines the average presence of the hole density) can be differentiated by a measurable weight loss in the COP»1.0 system. The successful antigravity production of the Sweet COP»1.0 device — discussed later in this chapter — experimentally verified these hypotheses.

9.4 Peculiarities of Spacetime Curvature and Dirac Hole Interactions

When considering the interaction between *curved* spacetime and the Dirac vacuum, immediately we violate the premise that all electron states in the Dirac Sea are always filled (which condition we surmise — along with Dirac — only exists on the average in a flat spacetime region). In a curved spacetime, we can have sustained excess 4-holes in the vacuum, or we can have holes that accept an electron falling into them *without emitting radiation.* The radiation-free "pair annihilation" reaction is possible when the spacetime simultaneously changes its curvature appropriately and thereby "absorbs" and holds the excess EM energy that would otherwise be emitted if the spacetime remained flat or decayed back to the flat state.[256] So long as that "energy-storing ST curvature" remains, there is no photon energy emission. If the "energy storing ST curvature set" has a net curvature instead of being flat, and then decays to a flat spacetime, then the previously retained energy is emitted as photon energy.

In that case the reaction provides the conventional emitted pair annihilation energy. In *that* case, the emitted energy may also transform into emitted particles in reactions well known in particle physics.

---

[256] Eerily, this interaction represents a situation where opposite reaction forces (the vacuum upon spacetime, and spacetime upon the vacuum) can create a special kind of stress in the system and changes in that stress. This leads to a peculiar kind of stress waves (scalar waves — longitudinal EM waves, so to speak) that are not covered in circuit theory anywhere. A symptom is that these stress waves react with components, amplifiers, preamps, etc. to create electrostatic waves. The effect of these waves is seen as the "crawling" of electrostatics all over and in the electrical equipment that is in one's laboratory. The effect can readily damage oscilloscopes, etc.

The normal emission of photons by pair annihilation need not occur, if the excess decay energy is absorbed *and held* by the local spacetime changing and holding its energy density and therefore (i) changing its curvature and (ii) stabilizing in that new excited state instead of decaying back to a flat spacetime.[257] Under such "non-emitting" pair recombination, a Dirac Sea 4- hole may simply "eat" a free 4-electron, and instead of emitting radiation the process simply affects the curvature of spacetime (and the state of the local Dirac sea) and changes it accordingly. A new "equilibrium state" is therefore reached in the supersystem between the opposite forces of the vacuum acting on spacetime and spacetime acting on the vacuum.[258] In other words, we consider change in the curvature of spacetime to exhibit EM energy *source* (emission) or *sink* (absorption) capability, with respect to the nominal ambient flat spacetime and with respect to conventional EM interactions.[259]

Or simply put, the energy emitted by the combination of positive and negative energy in the vacuum may be "locally radiated", "locally absorbed", or "locally transferred" to the other local component of the supersystem: the local curvature of spacetime. *It is all spacetime curvature dynamics.* By definition, a flat local spacetime consists of a vacuum with all its Dirac sea holes filled. Therefore, if "filling a 4-hole" results merely in relaxation of a set of local ST curvatures back to a flat spacetime, no EM radiation need be emitted, contrary to the usual pair annihilation phenomenon where additional energy (curvature of spacetime) is involved.

---

[257] Our view is that in normal pair annihilation this curving of spacetime to absorb the emission energy occurs first, and then the new ST curvature decays by what is called "emission of photon energy". We regard the photon as a specialized ST curvature traveling at light speed. So what is emitted as a photon is in fact the formation of a locally structured spacetime curvature (an "engine") traveling at light speed. It is a propagating spacetime curvature "engine" or "set of engines". In the process we are describing, the emission of the photon is the decay of the locally formed ST curvature set. If that set does not decay, the locally formed ST curvature set remains and no photon is emitted.

[258] This new kind of equilibrium is extraordinarily important, particularly in chemistry, where it will allow the "locking" of impossible combinations of particles into strangely stable "impossible molecules" with ongoing "impossible chemical reactions". The further discussion of the startling new chemistry that emerges is well beyond the scope of this paper, but such chemical states are included in nonequilibrium thermodynamics as *stationary states* — e.g., see Kondepudi and Prigogine, *Modern Thermodynamics,* Wiley, 1998, Chapter 17. At least one company has already succeeded in initiating this startling new kind of chemistry, with several patents granted and several more in process. Similar new "impossible stabilized excited states" and "impossible nuclear reactions" also occur in nuclear physics.

[259] The classical EM assumption of the flat local spacetime is in fact an assumption that the decay of the intermediate "ST curvature absorber/sink" occurs instantly.

Similarly, in a ST curvature, there can conceivably be electrons without "holes". If the curvature is negative, there *will* be unfilled Dirac sea holes present. Of course this is just a normal positive energy 4-electron, where the flat spacetime assumption in classical electrodynamics is in error. Instead, the local spacetime is positively curved, producing positive gravity. Whenever the energy density of spacetime-vacuum interaction changes from the "ambient vacuum and flat spacetime" condition, either positively or negatively, that constitutes an appropriate curvature of spacetime as well as a change in the vacuum dynamics. Therefore, in classical electrodynamics the assumption of a normal electron (or any other charge or mass) existing in an uncurved spacetime and an unaltered vacuum is a non sequitur. The local spacetime has in fact "curved" to an extent of holding the energy of one electron mass.[260] Further, the Dirac Sea has also changed to contain one unfilled and unobserved Dirac 4-hole.

With these things in mind, let us now introduce a conceptual model for dealing with these novel 4-hole phenomena that are experienced in COP>1.0 systems — and that have been the bane of many a would-be energy researcher attempting to develop a system extracting its EM energy from the vacuum and using it to also power the system itself.

9.5 Charging and Discharging a Capacitor

In electronic circuits, we usually think of charging a capacitor with electrons, and then discharging the capacitor to emit electrons again. However, we can charge the same capacitor with Dirac sea holes, or with a combination of Dirac sea holes and electrons. Then we can switch the capacitor adroitly and force it to give us back electrons. This "regauging" effect can thus be used to transduce negative energy current into positive energy current. So let us examine the charging and discharging process more closely. This is part of the Bedini process for handling the 4-hole current problem in overunity EM systems, to allow close-looping a system into self-powering operation.

---

[260] Mostly physicists think only of the *spatial* energy change. However, the time domain of spacetime also acts as a sink or source. Essentially one kilogram of mass only has the energy of 1 second of time. Hence the minuscule *mass* of the electron results in such a minuscule "sink" in the time domain that it has been inadvertently ignored. However, during that fraction of time where the electron exists as "mass time" and "charge time", it has considerable time energy, and *that* curvature of local spacetime cannot be neglected with respect to supersystem interactions.



Figure 9-6 Normal strain in a dielectric capacitor that charges with electron current

Figure 9-6 shows the normal strain induced in a capacitor containing a dielectric between its plates. We charge the left plate with electrons, which repel the negative ends of the molecules in the dielectric, straining them to the right.



Figure 9-7 Strain relief in a charged dielectric capacitor that discharges.

Figure 9-7 shows the relief of this dielectric strain, by allowing the piled electrons on the left plate to be pushed back into the circuit from the left plate. Note that the electrons emitted in the relaxation of the dielectric strain pass back into the circuit from the same plate that was charged. This is a special kind of "reflection" symmetry. For a perfect capacitor, the total

Vq joules stored in the charged capacitor and drawn from the circuit, is returned to the circuit.


(−)
(−)
(−)
(−)
(−)
(−)
(+)
(+)
(+)
(+)
(+)
(+)
(+)
e +
real electrons lifted from Dirac Sea
Dirac hole charge in local Dirac Sea

Figure 9-8 Strain in a dielectric capacitor supersystem that charges by Dirac hole current and lifted Dirac electrons

Figure 9-8 shows a remarkable thing when we charge the capacitor with Dirac sea holes. Suppose we charge the rightmost plate of the same capacitor used before, while the leftmost plate is temporarily disconnected from the circuit (or connected to another capacitor). Now Dirac Sea holes pile up in the local vacuum connected with the right plate. Whether or not they interact with the right plate, these positively charged holes attract the negative ends of the dielectric molecules, again straining the top of the dielectric molecules to the right. The strain of the dielectric is a force interacting upon the local vacuum, and it lifts real electrons from the Dirac Sea (or pulls them from the circuit or other attached capacitor) and onto the leftmost capacitor plate. The charged capacitor *in its supersystem* thus has additional functions that occur. The total *Vq* joules stored in the charged capacitor, were this time drawn (converted) from the applied Dirac hole current and the resulting interaction upon the vacuum, to lift real electrons onto the leftmost plate.[261]

---

[261] The reader should recall that a force is something automatically produced by nature to restore symmetry to a broken symmetry condition. A "4-hole negative energy force in the Dirac Sea" produced on one plate of the capacitor will evoke a "positive energy force outside the Dirac Sea" on the other plate as an attempt to restore symmetry. To produce this "positive energy force", positive energy electrons are lifted from the local Dirac Sea of that plate.


e⁻
Real electron current discharge into circuit input section
(0)
Recombination of Dirac holes with virtual Dirac electrons in seething local vacuum

Figure 9-9 Strain relief in a dielectric supersystem that discharges after charging by Dirac hole current and lifted Dirac electrons.

Figure 9-9 shows the strain relief of the charged capacitor in Figure 9-8. First the charged capacitor is re-connected to the circuit or element to which one desires to provide with electron current. The strained dielectric relaxes, and electrons in the leftmost plate are returned to the circuit. The Dirac holes in the rightmost plate discharge back into the local vacuum (a supersystem interaction) and are "eaten" immediately by the readjustment of local curved spacetime.[262]

The result is that the Dirac sea 4-hole current arriving in the input section has been intercepted by a waiting capacitor, and has been effectively transposed into normal electron current that is furnished back to the input section from the capacitor. This additional electron current helps power the circuit and reduces the power drawn from the external power source. The 4-hole current feeding this capacitor, together with transduction of the 4-hole current into electron current, effectively comprises a true negative resistance process. In other words, energy in unusable (in this case, detrimental) form is received, transformed into energy in usable (beneficial) form, and that usable energy is discharged back into the circuit input to assist in powering the system.

Transducing negative energy into positive energy — and vice versa — in the system does not violate the conservation of energy law in the supersystem, when most generally stated. With such regauging (which involves supersystem reactions), it is the *absolute value* of the energy that is conserved in the system, not its algebraic sign. Regauging (by gauge freedom) is after all an effect or condition locally imposed, but with appropriate energy exchange with the rest of the external universe via spacetime curvature dynamics exchange and vacuum dynamics exchange. The algebraic sign *is* conserved in the universal supersystem by the additional compensating reactions occurring in the other two components of the universe's supersystem.

---

[262] From experiments, it seems that Dirac holes forming at the "output" section of a **COP<1.0** device or system are almost instantly filled with electrons in the violent fluctuations of the zero-point energy. When forming at the "input" section of a **COP>1.0** device, this is not the case, and usually the holes can only be filled by incoming electrons in the power input, unless special provisions are taken to convert **the** arriving hole current (in the input section) into electron current.

The reader should strongly realize that energy is only required to be conserved in the universe's supersystem, not the system component alone. Again, this is an open system far from equilibrium with its active environment. In that case, energy is conserved in the ensemble of system and environment, but not necessarily in the system itself. This is no stranger than a common windmill or waterwheel.


e^-
(some)
Some electrons lifted from Dirac Sea
e^+
(some)
Dirac hole charge in local Dirac Sea

Figure 9-10 Strain in dielectric in a capacitor supersystem that charges with a mix of electron current, Dirac hole current, and lifted Dirac electrons.

Figure 9- 10 shows a "mix-charging" variant of the 4-hole current charging of a capacitor, in which some real electrons are fed from the circuit to the left plate. Also, the Dirac sea hole current arriving in the input section is intercepted to charge the right plate, and some electrons are also freely lifted from the local Dirac Sea onto the left plate. Figure 9-11 shows the discharge of this type of charging of the capacitor, and the relief of the strain in the dielectric.


e⁻
Real electron current discharge into circuit input section
(0)
(0)
(0)
(0)
(0)
(0)
(0)
Recombination of Dirac holes with virtual Dirac electrons in seething local vacuum

Figure 9-11 **Strain relief in a dielectric that discharges after charging of capacitor supersystem with mix of electron current, Dirac hole current, and lifted Dirac electrons.**

In Figure 9-11, for example, we accent that the holes on the right plate are maintained only so long as there is a net strain on the dielectric and a net force across the capacitor. When the capacitor is discharged, the holes are discharged into the local vacuum in such a way that they now instantly recombine with virtual Dirac electrons in the vacuum fluctuations.

There are other ways and "tricks" of transducing the Dirac sea hole 4-current into electron current, but these methods are still proprietary to Bedini and will not be included in this presentation. We accent that all such "tricks" are actually methods of re-engineering the other two components of the supersystem — the active local vacuum and the local curvature of spacetime. This is using and applying what we have referred to as "engines".

9.6 The Open-Loop COP>1.0 EM Power System

Figure 9-12 shows the use of the transduced Dirac hole current as real input energy to "catch and lock" a COP>1.0 system in its overunity condition and stabilize its operating point for stable self-powering of the system and its load. The COP>1.0 operation reverses the normal tempic potential across the system, so that Dirac hole 4-current arrives in the input section, preparing to "decay" the system back to COP<1.0 condition.


Primary power Supply
Excess Dirac holes recombine in local vacuum activity
Energy from the vacuum
P4
Load
Tempic potential = k
Tempic force
Tempic potential > k
P3
Dielectric transducer with second reversal of tempic force
Dirac sea hole current
P2
Electron current
I2
P1
INPUT SECTION
MIDSECTION
OUTPUT SECTION
P5
Input section losses
P6
Midsection losses
P7
Output section losses

Figure 9-12 Open-loop use of transduced Dirac hole current energy as real input energy to reduce power input required from the primary power supply.

However, the arriving hole current is intercepted by an adroitly switched dielectric transducer, which again reverses the tempic force. As explained above, the capacitor is charged with 4-hole currents (or a mix) and then discharges electron currents into the system — in this case, into the input section itself— by adroitly engineering the local vacuum state and the local curvature of spacetime.

The input section does not care where it receives its electron current from; it merely needs sufficient for its powering needs. Hence, the input section happily accepts this transduced electron current to partially power the system. This in turn reduces the "system load" that the external primary power supply "sees". The primary power supply thus reduces the current and power that it is furnishing to the system. In short, now the external power supply sees the combination of the normal system load and a "negative resistor (negative load)" represented by the transduced current and power. Its required input power is reduced accordingly.

9.6.1 Close-looped System: A True Negative Resistor

Figure 9-13 shows the use of the same process given in subparagraph 9.6 above and in Figure 9-12, except that now there is additional 4-hole current received and available, for transduction into normal electron current into the input section of the system. Sensors and governing are added to this operational mode, so that the system may *adjust and regulate its self-furnished electron current* to meet the total needs of its losses and its load. The system thus adapts the transduction of Dirac sea hole current: to fit its needs and is capable of regulated self-powering operation.


Primary power Supply
P8
P1
Tempic potential = k
Excess Dirac holes recombine in local vacuum activity
Energy from the vacuum
P4
Load
Tempic force
Tempic potential > k
P3
Dielectric transducer with second reversal of tempic force
Dirac sea hole current
P2
Electron current
I2
INPUT SECTION
MIDSECTION
OUTPUT SECTION
P5
Input section losses
P6
Midsection losses
P7
Output section losses

Note: Power outputs P3 and P8, and current I2 have sensors reporting to the Governor in the output section. The governor adjusts the potential energy in the output section to maintain steady output or adjustment of output to demand.

Figure 9-13 Close-looping the C0P>1,0 system with transduced hole current.

The system is first started in open-loop mode. The governor then gradually increases the transduction of 4-hole current into electron current, and the supply of that transduced electron current to its own input. This steadily reduces the "current draw" from the external primary power supply. When the "external current draw" reduces to zero (the Kron condition), the system "locks" into that position, with automatic governing to adjust the transduced electron current as the loads and losses vary. At that point, the external power supply is disconnected automatically.

This "locked and governed" system is now a *self-powered system,* freely taking its energy from the active vacuum and local curvatures of spacetime, to power both itself and its load. So far as we are aware, this is the first time that the technical means of locking and stabilizing COP>1.0 operation in an EM system in an open loop and closed-loop operation has been given.

If sufficient Dirac sea 4-hole current is available and transduced, excess electron current can be available at the system input section, even when the system is fully self-powering. In this case, the additional current can be fed back to the power line, so that the self-powering system not only powers its own load but also helps power the power network. Or additional load can be added and powered.

We point out that Gabriel Kron apparently had a solution to these problems in the late 1930s, and that solution has been suppressed to the present day. We give the following quotations to show Kron's knowledge of these things.

Quoting Lynn and Russell {565}:

> *"Kron has never published details of his method of making the polyhedron self-organizing, although his published results show that in this state it has some remarkable properties, associated with harmonic integrals on multiply connected spaces."*

In reference to Lynn and Russell's remarks, we point out that the Dirac sea 4-hole current from the output to the input is a special case of Kron's more general discovery of the multiply-connected open path existing through space between any two points in a circuit that are at differing potentials.

Quoting Kron {566}:

> *"...the missing concept of "open-paths" (the dual of "closed-paths") was discovered, in which currents could be made to flow in branches that lie between any set of two nodes. (Previously —following Maxwell - engineers tied all of their open-paths to a single datum-point, the 'ground'). That discovery of open-paths established a second rectangular transformation matrix... which created 'lamellar' currents... " "A network with the simultaneous presence of both closed and open paths was the answer to the author's years-long search."*

Again quoting Kron {567}:

> *"Although negative resistances are available for use with a network analyzer, in practice it is more convenient to use a second type of circuit, in which the positive and negative resistances are replaced by inductors and capacitors and the dc currents and voltages are replaced by ac currents and voltages of fixed frequency. The use of the second type of interpretation is equivalent to multiplying the wave equation by* $i = \sqrt{-1}$."

The reader should particularly note that in the first part of the sentence Kron stated unequivocally that negative resistances were available for **use** on the network analyzer, a large analogue simulation used by the Navy **and** administered at Stanford University with the contractor being General Electric. The censors missed that one.

Again quoting Kron {568}:

> *"When only positive and negative real numbers exist, it is customary to replace a positive resistance by an inductance and a negative resistance by a capacitor (since none or only a few negative resistances exist on practical network analyzers).*

We believe the censor caught this one, and forced Kron to add the words, "none or". Kron had at least three negative resistors, and possibly more.

Again quoting Kron {569}:

> *"Now a value E of the negative resistances, at which the generator current becomes zero, represents a state at which the circuit is self-supporting and has a continuous existence of its own without the presence of the generator, as the negative resistances just supply the energy consumed by the positive resistances. ... When the generator current is positive the circuit draws energy from the source, and when the current is negative the circuit pumps hack energy into the source. At zero generator current the circuit neither gives nor takes energy, and theoretically the generator may be removed. "*

Here we believe the censor forced Kron to add the word "theoretically". In this quotation Kron reveals that he was well aware of the process for close-looping a system — starting it in open-loop mode and bringing the negative resistor currents up to match the system needs and reduce the generator current to zero, then disconnect the generator. He also was quite aware that excess transduced energy from the negative resistor could be available at the input, in which case energy could be furnished back to the power network while the system powered itself and its load simultaneously.

We also point out that Dirac's definitive electron theory — covering the Dirac Sea and Dirac sea holes — was published in 1930, the year the present author was born. In the late '30s and in the 40's Kron certainly was well aware of that work. In addition, Kron applied full general relativity to electrical circuits and machines, and he was far ahead of his time. His work is also still far ahead of the present time, at least in the open scientific community. He also was aware of developments in particle physics, and so he did have the gist of the supersystem concept in his mind {570}, however he may have thought of it. His concept of the "open path" effectively includes the effects upon the system from the other two components of the supersystem, so it appears that Kron's "system plus its open path" roughly corresponds to our concept of the "supersystem."

Further, Kron was a mentor to Floyd Sweet, who also worked at General Electric but in a different project. Sweet often spoke glowingly of Gabriel Kron.[263] Sweet almost certainly knew the secret of Kron's negative resistor. It is the present author's opinion that Sweet's vacuum triode amplifier was derived from Kron's negative resistance unit. With both deceased, we will never know for certain.

9.6.2 Suppression of COP>1.0 Systems Should be Investigated

During our decades of research, we ran across several cases where U.S. scientists actually produced working COP>1.0 systems.[264] None of these overunity systems was ever allowed to go forward with independent development. This is an area that cries out for a full and vigorous Congressional investigation, and appropriate legal action should be taken by the U.S. government against the suppressing parties, whomever they might be {571}. Simply put, the U.S. government, the U.S. taxpayer, and the scientific community have been ripped off and deluded in the field of electrical energy for more than half a century. That continues to the present, as witness the disappearance of the Watson generator (accompanied by Watson and family breaking off all contact with their close colleagues) and the suppression of the Kawai device and process. The latter suppression was accomplished in 1996 in the personal presence of the present author and the members of the Board of Directors of our company, CTEC, Inc. An accidental overunity frequency converter was even initially placed in the original Minuteman missile, but was altered back to COP<1.0 operation when the electronics past the converter kept failing because of overload power furnished by the converter.

---

[263] The present author worked with Sweet off and on for a decade or more, and designed the antigravity experiment that Sweet performed.

[264] These incidents were previously exposed in a draft book, *Matters Arising,* carried on the Internet for some months and then withdrawn. Some things must wait for their appointed time, and so must certain kinds of information.

9.7 Remarks on Dirac Sea Holes, Currents, and Negative Energy

The subject of the Dirac Sea, Dirac holes, Dirac hole currents, and negative energy still has elements of strong disagreement within the scientific community and among leading theorists. Often the "conclusion" one reaches depends on the way the starting assumptions are made and then on how the mathematics is applied. There is no definitive experiment establishing that negative energy cannot exist; to the contrary, many things do occupy negative energy states. The binding energy of the nucleus, e.g., involves a loss of mass (loss of positive energy) and hence involves negative energy states, as is well known. Here the "negative mass" effect is immediately and experimentally verifiable, and is recognized. The total mass of the bound nucleons is less than the total mass of those same nucleons when unbound, and this fact is widely known and accepted.

A single white crow is sufficient to prove that not all crows are black. Hence a single experimental proof of mass-energy "loss" and negative energy states establishes that negative energy and negative mass are real. Indeed, every photon absorption by mass and every photon emission by masstime prove the same point universally: mass is a variable. The same assembly of protons and neutrons in a nucleus, having lost mass, also has "lost" some of the gravity that the positive masses of those unbound protons and neutrons would otherwise produce. Therefore, there is an appropriate amount of "negative gravity" already acting in conjunction with positive gravity, in every atomic nucleus. It is associated with the negative energy states of the bound nucleons in every nucleus.

Consistent with the initial quotations and comments at the beginning of this chapter, we present an interpretation by which we can understand some of the major novel phenomena that arise in laboratory experiments with COP>1.0 electromagnetic systems, including COP»1.0 systems.

We propose that COP»1.0 EM interactions are widespread in highly energetic astronomical interactions {572} and even in highly energetic phenomena on Earth, when the supersystem changes are also accounted.[265] We argue that novel negative energy phenomenology — such as encountered in the COP>1.0 experiments by Magnetic Energy Ltd. in various versions of the COP>1.0 motionless electromagnetic generator (MEG) {573, 574}, by Bedini {575} in his induction of negative resistor actions inside the batteries of battery-powered COP>1.0 EM systems, and by Sweet and the present author in experiments with the Sweet COP» 1.0 vacuum triode amplifier system {576} — is also generated in these COP»1.0 highly energetic astronomical interactions, yielding the same kind of negative energy and negative energy currents.

---

[265] As an example, in looking at sprites and other such sharp electrical discharge phenomena, we may be observing the prompt *decay* of COP»1.0 interactions which were self-initiated in the atmosphere.

This Dirac hole negative energy generation of COP»1.0 EM processes is proposed as the mechanism which directly produces the negative energy fields and potentials that generate the mysterious antigravity accelerating the expanding universe {577}. This is a reasonable assumption, even though it is against the received view, because it is based on some laboratory experiments, not just theory. It also is the unexpected effect of the cosmological constant introduced by Einstein {578}, and it is consistent with Zeldovich's demonstration that the energy density associated with Einstein's repulsive cosmological constant is — or is associated with — vacuum energy.[266] The received view *is not* based on direct experiments with COP>1.0 EM systems, but only on COP<1.0 EM systems. Until the received view is broader based, it does not adequately represent nature. Hence it does not represent a valid refutation of experimental negative energy systems producing antigravity processes.

In Bedini's experiments and in the MEG experiments, antigravity is essentially absent or so small as to be nearly nondetectable. However, these experiments generally have COP of 1.5 to 4.0, mostly, and sometimes 10 or 12 (we have experimented up to 20 or more stably, and unstably at nearly 100). Hence the Dirac hole current is relatively small in them, since the magnitude of the Dirac current is a function of (COP - 1).

Sweet's COP > 1,500,000 experiments produced a very large flow of negative energy back across the system, substantially curving the local spacetime and reducing the weight of the system on the laboratory bench. Figure 6-7 shows the first Sweet device, which produced six watts output in open-loop operation. Figure 6-8 shows a later Sweet device which produced COP = 1,500,000 and was pushed past that COP to produce the antigravity in the laboratory, smoothly reducing its weight by 90%. Figure 6-9 is a plot of the actual readings taken during the antigravity experiment. Sweet performed the experiment in California, reading off the measurements to me over the phone as he made each one.

---

[266] Believed to have been demonstrated in 1967. But check Ya. B. Zeldovich and A. A. Starobinsky, "Particle creation and vacuum polarization in an anisotropic gravitational field," *Zh. Eksp. Teor. Fiz.*, Vol. 61, 1971, p. 2161 *(Sov. Phys. -* ***JETP,*** Vol. 34, 1972, p. 1159); Ya. B. Zeldovich, "Vacuum theory — A possible solution to the singularity problem of cosmology," *Uspekhi Fizicheskikh Nauk,* vol. 133, Mar. 1981, p. 479-503. Translation in *Soviet Physics — Uspekhi,* vol. 24, Mar. 1981, p. 216-230.

Another indication of the negative energy effect present in the output section of the Sweet device was tested by suddenly shorting the output leads. This resulted in instant freezing of moisture from the air, so that the leads were instantly frozen and covered with ice. Contrast this to the normal heating of shorted wires, where the energy is positive.

Sweet never revealed his activation process, whereby he initiated very strong self-oscillation — of the nucleus of the barium atom in barium ferrite magnets — with the local vacuum treated as a semiconductor. One part was known to the present author and another part was known to Rosenthal, a professional test engineer. In addition, how Sweet converted his excessive hole current is not completely clear. It appears that he somehow used his coils in quadrature together with special circuitry to interact the excess hole current into his magnets, directly with the self-oscillating barium nuclei and thence with the other nuclei in his magnets. If so, it created the "rough equivalent" of increasing the associated binding energy offset and locked with concomitant additional local spacetime curvature.

If this speculation is correct, he "locked" the nuclei of his magnets to the local curved spacetime, maintaining the overall local binding energy in the nuclei themselves while producing a great excess of "binding energy" (negative energy) in the immediate vacuum. This would explain the antigravity, and would be consistent with the experimental results as well as the increase in antigravity as the output load of the device was deliberately increased.

We must use the supersystem concept, as in the quoted comment at the beginning of the chapter, to enable a better understanding of these novel phenomena. Together with the Dirac negative energy production and high COP system, the hypothesis of "additional negative energy acting on local spacetime immediate to each nucleus" allows the generation of the observed antigravity to be understood. However, we accent that this mechanism is still a hypothesis, and it must be further substantiated by experiment.

9.7.1 Lattice Holes

In a material conductor or other component of an electromagnetic circuit, the conventional model envisions currents in the Drude electrons as the electrons moving by "hopping" from molecules or atoms in the material lattices into the Drude gas, with each hop leaving behind a positively charged "vacated electron position" called a *lattice hole,* or just a "hole". Subsequent Drude electrons are attracted to fall into the holes, etc. This net movement of the hopping electrons down the conductor, etc. comprises the conventional electron current through the conductor. We point out that the actual movement of the electrons in their "hopping" is vastly more energetic than the very feeble net "drift" of the overall ensemble of Drude electrons longitudinally down the wire as current. The energy of the total electron activity ongoing in a simple 1-foot length of copper wire would power a city, if it could all be harnessed and utilized.

At the same time the electrons hop with a slow net progress down the wire, the "holes" in the material lattices are also collectively seen by the external observer as if "slowly changing their net positions" longitudinally in the opposite direction. One speaks of a corresponding "hole current" or "lattice hole current" in the opposite direction to the electron current. However, there are subtle differences in the flow of the two currents, because an electron in the Drude gas is far more kinetic than the positive ion left behind by an electron that has "hopped up into the electron gas". Nonetheless, the positive lattice ions do "rock" physically from the induced forces upon them, as the holes are opened and filled. In conventional electrical power systems, this equal and opposite energy reaction in the ions of the lattice materials, induced by the applied fields, is usually ignored. In most classical EM power system theory the holes and their "composite equal and opposite energy and work in the system" are also ignored, except in semiconductors and semiconductor circuits.

9.7.2 Newton's Third Law Is Accounted in the Supersystem

Because half the EM energy and work in the circuit is usually ignored (e.g., in the Maxwell-Heaviside-Lorentz standard equations), electrodynamics is said to be free from Newton's third law reaction. This may be a non sequitur, and it follows from the assumption that — for an EM wave, field, or potential in space — no interaction exists with the active vacuum or with the curvature of spacetime. In fact, those reactions do exist in the supersystem. The field, wave, and potential do indeed interact with both the quantum mechanical vacuum and the general relativistic spacetime.

Indeed, the field, wave, and potential may be said to *identically be* changes induced in general relativistic spacetime. The absence of the "transmitting" physical system leaves us with the remaining two components of the supersystem, each of which extends to infinity. Again, Figure 9-1 shows the actual interactions (the supersystem) and Figure 9-2 shows the erroneous and arbitrary "kill of the supersystem" by standard classical electrodynamics.

When higher group symmetry electrodynamics such as O(3) is applied, then the interactions between the three parts of the supersystem emerge and must be accounted. This is particularly true of COP>1.0 EM systems. However, as Finster points out {564}, the Dirac sea effects exist *wherever* there are EM fields, potentials, and waves. We add that curved spacetime effects also exist *wherever* there are EM fields, potentials, and waves. And wherever Dirac sea effects exist, or wherever curved spacetime exists, then there the local vacuum and local spacetime interact with each other.

However, as we shall point out, usually most of the Dirac sea hole effects can be neglected in COP<1.0 systems and in most lower gain COP>1.0 systems because of the time-energy aspects. For COP»1.0 EM systems, the time-energy aspects are partially reversed, and instead of carrying the hole effects away from the system, the time-force from system output to input forces the Dirac sea holes to flow back in the local vacuum across the system from its output to its input. This flow constitutes an additional "load" appearing in the input section and requiring additional electron current from the external power supply to fill the holes. If the power supply does not furnish sufficient electrons to fill the hole current at the input section of the system, then the unfilled hole current passes back into the feeder line toward the external power supply, and even into the distant power supply itself. In its progress, it eats incoming current all along the way, requiring that more current be furnished by the distant generators.

9.8 Remarks on the Observed Acceleration of the Expanding Universe

As a candidate for *dark negative energy*, the present author has proposed vacuum negative energy and currents in curved spacetime regions partially containing excess *empty* Dirac sea holes as well as normal *filled* Dirac sea holes. The process by which these excess Dirac holes are produced has been advanced, and is supported by at least one dramatic experiment. One result of such "negative energy areas" of negative spacetime curvature would be "jumps" increasing the velocity of light and high-energy particles traversing these altered regions of spacetime. In fact, there is some evidence for just such jumps, according to a hypothesis by Richard Lieu of the University of Alabama in Huntsville {580a, 580b}. Otherwise, high-energy particles produced in distant processes in the cosmos would not be detected on earth, but would be annihilated in highly energetic collisions.

The departure of large-scale spacetime from homogeneity would also result in some loss of correlation in the presently fitted red shift versus distance relationship. Again, there is tentative indication that such may prove to be the case. The most distant galaxy recently detected has a red shift of 6.56, which — assuming homogeneity of space — implies look-back of 14 billion years or so.[267] (conventional view) Best estimates of the age of the universe based on the Big Bang assumption is some 14.7 billion years. It would seem that 0.7 billion years is a very short time for that observed galaxy to have formed. If even more distant galaxies are observed with larger telescopes to become available, then by the redshift correlation to homogeneous space one would be observing galaxies "before the beginning of the universe" — an obvious non sequitur. It appears that the redshift correlation to velocity and distance, as well as the homogeneity of space and in fact the Big Bang itself— are already in some difficulties and may be in serious trouble in the near future.

The empty Dirac sea 4-holes in the vacuum are special "Dirac negative action quanta" and the holes and their dynamics form negative action potentials, currents, and fields. This type of vacuum condition containing some empty Dirac sea holes is referred to as a *Dirac-polarized vacuum.*

However, we do not envision the Dirac-polarized vacuum as just simple *static* polarization, but as possessing rich dynamics such as negative energy currents, potentials, fields, waves, etc. including in the time-energy medium in the time domain. We also include the interaction of the dynamic Dirac-polarized vacuum with spacetime.

---

[267] I am indebted to Prof. Stanley Jeffers for this information, in his E-mail discussions with the Alpha Foundation's Institute for Advanced Study fellows. Dr. David Roscoe contributed the fact that the Big Bang theory has so many parameters that nearly anything can be "fitted in". But he also pointed out that W. M. Napier, *Astronomy & Astrophysics,* Vol. 310, 1996, p. 353 gives a very thorough analysis of the quantized cz phenomenon, which does present a difficult obstacle to Big Bang theory. Napier is **the** originator of the cometary catastrophe theory of biological extinction. One way or another, the theory of the Big Bang is in trouble, even though many theorists are still complacent about it.

Due to ongoing COP»1.0 processes involved in highly energetic astronomical phenomena, Dirac sea 4-hole regions and dynamics are believed to occur and exist in the vacuum across the observable universe. These occur especially in appreciably curved spacetime regions with large tempic potential gradients and thus large *time-forces* across the region.[268] The 4-holes and 4-hole currents in the vacuum are generated in great quantity in large cosmic explosions. Also, the energetic fluctuations of the local vacuum energy can separate a Dirac hole from its occupying electron by lifting the electron (pair production), and so can a curved spacetime. In a properly curved spacetime, fluctuation can lift an electron from a hole, and enter a stationary state by accommodating reaction of the local spacetime curvature. In that case, hole and electron go their separate ways. The hole and that or another electron may later recombine, or in sufficient local spacetime curvature, they can remain apart. We point out that every positive energy electron is accompanied by an appropriate local curvature of spacetime that prevents the accoutrement of a free Dirac sea hole,[269] and thus prevents the electron from disappearing.

The more energetic the local region, the more severe and violent are local spacetime curvatures in that region, and — in our view — the more frequent the occurrence of COP»1.0 interactions producing significant Dirac 4-hole currents, negative energy EM fields and potentials, etc. Indeed, the measurements that yielded the accelerating expansion of the universe were measurements of the relative velocities existing with stellar explosions known as type la supernovae. In our view, in explosions of such violent nature — particularly including in optically active gases such as where gamma ray bursters form — an appreciable fraction of the hole currents are transduced into positive energy electron currents. This produces — at least for a finite time — a net positive feedback, self-powering COP»1.0 phenomenon, resulting in very rapid asymptotic output energy increase. This is what we have hypothesized as producing the gamma ray burster itself. *Quenching* of this asymptotic rise in COP occurs only after the physical geometry of the "closed-looping" gas particles is broken a short time later. The maximum output energy is determined by a function of the *rate* at which the geometry is broken and the corresponding *rate* at which damping of the asymptotic rise and quenching occurs. The afterglow remaining in the gas is due to the extra positive energy produced in it by the transduction of negative energy into positive energy during the asymptotic rise of the self-powering burster, with excess positive energy being absorbed in the gas while the burster magnitude is rising. After damping and quenching, the gas has been heated (that is how the geometry was disturbed in the first place, to produce damping and then quenching). Re-ignition can occur whenever a new close-looping COP»1.0 situation spontaneously occurs. As in the gamma burster, this can often happen as the disrupted geometry of the gases stabilizes.

---

[268] We also conjecture that these regions may account for a tentatively observed slight change in the fine structure constant, but leave that to the advanced theorists to validate or falsify.

[269] This needs a bit of modification. Rigorously, the so-called "isolated" observable electron is clustered around by *virtual* positrons (Dirac sea 4-holes) in the vacuum. So a positron influence is present, though from virtual positrons instead of observable positrons. The magnitude of both the positive charge and the internal or "bare" negative charge is infinite. The difference, however, is finite and is the "observed" magnitude of the observable central charge. There is thus a net observed shielding of the bare charge of the electron, and this is taken into account to yield the observed charge of the electron.

All 3-space EM energy comes from the time domain, as previously developed. In the more violent positive energy COP»1.0 regions, there is an increased conversion of time-polarized EM energy into 3-spatial energy and back. On the average there is a higher "time-energy conversion" or "tempic" potential. In those regions, a tempic conversion potential is higher at the higher center magnitude of the spatial energy density. Hence there are strong tempic forces from "inside to outside", providing a "tempic broom" effect to sweep outward the excess Dirac sea holes separated from their electrons in the curved spacetime. The result is the presence of increasingly unoccupied Dirac sea 4-holes toward the outside of violent regions of spacetime,[270] until the effect is overcome by the decreasing spacetime curvature. The 4-hole current radiating out from an asymptotically increasing (exploding) burster provides an asymptotically increasing (exploding) negative energy and negative mass reaction with spacetime. That reaction explosively creates curved spacetime for negative gravity (repulsive gravity), acting upon the local system and upon distant masses as well. The result appears to be the cause of the acceleration of the expanding universe.

It follows that re-ignition of the gamma burster can occur if, as the quenching continues, the geometry stabilizes and reaches another "close-looping" positive feedback condition. In fact, just such re-ignition of the gamma burster is very often observed.

---

[270] I.e., the violent astronomical phenomena — while generating and increasing are more violent at the center, and less violent at the outside.

Therefore, we hypothesize that the more distant violent astronomical regions have greater amounts of repulsive gravity being produced by their local Dirac-polarized vacua particularly during their explosive asymptotic energy density rise. This produces violent streams or bursts of negative energy outflow, which is equivalent to negative mass outflow and which provides outgoing negative curvature of spacetime (antigravity). At sufficient distance from us, the increasingly earlier, more violent events and resulting greater curved spacetime regions have created sufficient cumulated Dirac-polarized vacua to override the normal attractive gravity between galaxies, etc. and produce net repulsive gravity. This results in observed distant acceleration of the expanding universe {581a-581f}.

9.9 A Solution to the Hole Current Problem and Close-Looping

Bedini and the present researcher have filed a patent application {582} on the above special capacitive process to *convert* or *transduce* the detrimental Dirac sea hole current reaching the system's input section into electron current, and put it to use in powering the system. This transduction process receives the hole current as a special potential, then regauges the "negative energy" potential into a "positive energy" potential. This regauging is accomplished by charging the capacitor with Dirac hole current and then discharging electron current from it. The transformed positive energy potential is then applied to the Drude electrons, producing an ordinary electron current in the input that can be used to power the system itself. If sufficient excess positive electron current is provided, then the system can "feed itself in self-powering mode and also feed power back into the main power supply line.

When conversion of the arriving hole current in the input section produces an output "positive energy" electron current equal to the system's normal power needs (Kron's condition), the external power supply can be disconnected and the system will remain powered by the steadily converted negative hole current arriving in the input section.

Our patent-pending process allows this otherwise devastating special form of "negative energy feedback" to be converted into "positive energy feedback", allowing the system to be close-looped successfully for self-powering of the system and its load. Regulators of the transduction process may be added to cover the situation when the load is erratic and changing.

At Magnetic Energy Ltd., we have also filed a patent application for an outrigger method of close-looping a COP>1.0 system, which greatly eases the problem. This method is covered in Paragraph 9-14 below.

9.10 Negative Energy: Localized and Nonlocalized

It sometimes appears there are as many views on negative energy as there are scientists who mention it. Simply put, the Dirac theory of the electron requires negative energy states. The negative energy electron state was envisioned by Dirac as a sort of "hole" in the ambient vacuum, where the hole could contain a positive energy electron. The combination of equal positive energy of the electron and negative energy of the hole itself, would give a "normal" vacuum zero state of the "filled hole". In other words, the normal or ambient vacuum consists of holes filled with electrons. Considered in that fashion, such a vacuum is referred to as the **Dirac Sea** or the **ambient Dirac Sea,** or the **ambient Dirac vacuum.**

If positive energy is added to a filled Dirac hole, the electron can be lifted out, leaving the hole. Note that adding positive EM energy, e.g., is actually the addition of spacetime curvature and dynamics to the Dirac sea vacuum. In short, it is a supersystem interaction, not a system interaction.

In that case, the curvature of the local spacetime interacts upon the electron mass, producing a force that lifts it from the hole. The result is the appearance of a positive energy, positive mass electron and a Dirac sea hole (a 4-positron) in a curved spacetime. That is known as *pair production,* and it is a supersystem interaction. When a positron and an electron meet, the electron falls into the hole, changing the Dirac sea which also changes the local ST curvature. That change in local ST curvature is a change in the energy density of space, and is normally radiated away as a photon or photons as the local curvature decays back to a flat spacetime. The emitted radiation may further decay into particles, etc. by several reactions well known in particle physics. That "conventional" set of supersystem interactions is known as *pair annihilation.*

If we deliberately change the ST curvature appropriately, however, the pair annihilation radiation need not be emitted since the excited local spacetime curvature does not decay back to a flat spacetime to emit it.

Dirac's original paper tried to identify a negative energy state vacuum hole as the proton, but later that was falsified and it was taken as the positron. There is a very strong aversion in physics to considering negative mass; hence, the mass of the positron was proclaimed positive (for many reasons not really connected with our thesis). Nevertheless, some physicists (in the minority) still speculate or theorize that negative mass "can exist." Not only "can" it exist, but also it *does* exist widely and one can demonstrate it in actual electrical circuits. It certainly exists in the binding energy of the nucleons in the nucleus of an atom. Again, a single white crow is sufficient.

We take a very straightforward view: we consider a positron — an electron observed with positive mass and "observed" to be traveling backward in observer time — to be a different (transformed) entity than a Dirac 4-hole traveling forward in observer time.[271] The observation operator accomplishes both velocity reversal and time reversal, and — since time is not an observable, the time reversal is "seen" as a reversal in spatial direction. *Prior to observation, neither reversal has been imposed.* The major distinction, we hypothesize, is that the observed positron has positive mass in 3-space, which is concentrated positive energy, and therefore produces positive energy electrical fields and positive gravitational field. Mass is an observable, hence, it is the iterative frozen 3-space snapshots of an ongoing 4-space process. Observation (and any observable) is the effect of applying the operator $\partial/\partial t$ upon spacetime LLLT in which a 4-space process is occurring. As we stated earlier in this book, our view is that no observable *continuously persists* (in time), but continually and iteratively *recurs* by the continual ripping of time from the ongoing 4-space reaction, to see the 3-space intersection at a frozen moment. We also advanced the *mechanism* that generates the flow of a mass through time, consisting of a mechanism for $\partial/\partial t\,(\mathrm{LLLt})$ - photon emission, converting *mt* to *m* — and the mechanism for $\int_t (\mathrm{LLL})dt$ — photon absorption, converting *m* to *mt.*

---

[271] This point is stressed. The *unobserved* positron is not identically a positive mass electron traveling backwards in time, but a negative mass, negative energy electron traveling forward in time. When Dirac theory of the electron was written, broken symmetry and the CPT theorem had not been discovered. Further, there was no distinction made in the difference between the observed entity (the *effect* of the observation interaction) and the non-observed entity (the *cause* of the observation interaction).

[272] We stress that we are once again confronting the ubiquitous substitution of the effect for the cause in classical electrodynamics. The observed positron and the unobserved positron are two quite different entities —just as the "cause" of an observation is quite different from the "effect" of the observation.

We may also consider mass to be condensed 3-spatial energy (say, EM energy) compacted by c^2. Modern physicists tend to consider the mass-energy itself as the source of the gravitational "attraction of mass" rather than the mass itself {583}. Let us accept that assumption, but differentiate between the observed 3-positron with positive mass and opposite direction in positive observer time, and the unobserved Dirac sea 4-hole with negative mass and without change of direction in the observer's positive time. The 3-positron is an *observed effect,* while the unobserved Dirac sea 4-hole is an *as-yet-unobserved cause.*

We also surmised that all EM energy in 3-space comes from time, by our solution {584a} to the long-vexing source charge problem {68}. In our view, we may then consider that the positive energy compressed as 3-space mass has been extracted from the time domain of surrounding spacetime, via entry of that time-energy into the surrounding 3-space at each 3-space point, producing a surrounding spacetime curvature which is known as the *gravitational field.* This gravitational field represents "withdrawn" 3-space energy from surrounding space, and withdrawn time-energy from the time associated with each surrounding 3-space point.

Hence the gravitational field may be said to consist of "negative energy" since it represents *lowered* energy of spacetime due to the curvature. This viewpoint yields results consistent with the received view that the energy of the gravitational field is negative. In our view, it is negative precisely because it represents "withdrawn energy" from the normal energy density of that otherwise flat space. The withdrawn nonlocal energy has been localized (as what we call "mass"). Simultaneously that withdrawn 3-spatial energy also represents "withdrawn energy" from the time-domain, since all the withdrawn spatial energy came from the time domain in the first place. The result is the curvature change in spacetime, that is taken as the gravitational field.

The 3-space energy comprising the mass is positive because it is *added to* the normal energy of an otherwise flat spacetime, at that concentrated locality.

The "energy in the gravitational field" is negative because it represents lowered energy density (i.e., lowered "pressure" in a fluid analogy) of that surrounding nonlocal spacetime compared to when that spacetime was flat

Thus when we add positive energy (a positive energy state) to 3-space, we create normal "positive" gravity because "mass" is a process of withdrawing some positive energy from the energy density of surrounding 3-space.

Here is the shocker: When we add localized negative energy (a localized negative energy state or "4-hole" — or a localized negative mass!) to a local 3-space region, we create "negative" gravity (antigravity) in surrounding space because the withdrawn energy from the local 3-space "hole" must have been added to the energy density of the surrounding spacetime, once we apply conservation of energy. Or in other words, the surrounding spacetime changed (curved) in interaction to the production of the hole.

If we wish, for simplicity we can just consider localized positive energy to generate positive gravitational charge in the surrounding nonlocal spacetime. We can consider localized negative energy to generate negative gravitational charge in the surrounding nonlocal spacetime.

This is where our concepts differ from the rather arbitrary way that a Dirac sea hole is interpreted in the received view. In spacetime, we try to account for the entire energy process and we apply a conservation law by including the supersystem interaction in every case. We insist that positive energy concentrated in positive local mass must have been extracted from surrounding spacetime.[273] That "negative energy" in the surrounding spacetime is what is known as the *gravitational field of the source mass* (where the energy was withdrawn to). Similarly, we insist that positive energy extracted from a localized region of the ambient vacuum to leave a "Dirac sea hole" must have been spread out into the surrounding spacetime, where it would properly be known as the *antigravitational field of the source Dirac hole.*

As an analogy in very simple lay terms, the holes associated with a local mass system or region involved in COP>1.0 operations create higher "pressure" outside the system or region with respect to other objects. Higher pressure between any two objects pushes the objects apart. The masses associated with a mass system create lower "pressure" outside the system or object with respect to other objects. Lower pressure between any two objects results in the objects being pushed together by the higher pressures beyond them.

---

[273] Alternatively, if we add local spacetime curvature, the surrounding nonlocal spacetime interacts as mediated by the supersystem changes in all three components. What we are saying is that there is no such thing as just a system, vacuum, or spacetime change. Any change to one is accompanied by a change to the other two, *a priori.*

We submit that this new view provides an exact (and testable) antigravity mechanism. It appears to have been validated by the Sweet antigravity experiment {576}, which was designed in advance by the present author with increasing the local negative energy reaction in mind.

9.11 Tests Reinforcing the Antigravity Mechanism

9.11.1 Dirac Sea Hole Current Effects in a COP»1.0 EM System.

For COP»1.0 electromagnetic systems, we recall that the temporal energy will flow negatively across the system from output section to input section. Hence the Dirac sea hole current in the local vacuum flows back across the system, from its output to its input section. Regarding the output section: Specifically, *all COP> 1.0 systems produce both positive and negative energy outputs. The greater the COP of the system, the greater the fraction of negative energy produced with respect to the fraction of positive energy produced.*

The positive energy will flow on out of the system output section (as into the external load) as in a normal circuit, but the negative energy output will flow from the output section through the local vacuum back across the system to its input section.

At the input section, the arriving Dirac holes appear to the input electrical current as a special kind of "load" added to the system input section. Hence, as previously stated, the external source must input electrons (as electron current) to "fill the holes" prior to having any input electrons available to power the circuit in normal fashion.

That is nature's unexpected *overunity decay mechanism* for COP>1.0 EM systems. The COP>1.0 system is in a condition of disequilibrium *a priori,* since the system exhibits negentropy and only systems in energy flow disequilibrium with their active environment can do that. Any COP»1.0 EM system is therefore in a highly excited state, and all excited states in nature have decay mechanisms. A highly excited state usually has a prompt decay mechanism, and the COP»1.0 system is no exception.

This emergence of the Dirac hole current from the system output section back to the system input section, is nature's decay mechanism to trigger COP»1.0 EM systems back into COP <= 1.0. With this current, a "negative energy load" is added to the input section, causing the system to draw additional electrical power from the external power supply to "power" the killing of the Dirac holes[274] as well as to "power" the normal circuit (the system itself).

If the external power source connected to the COP»1.0 system is not furnishing sufficient electron current to kill the hole current in the input and power the system as well, the excess hole current will pass back through the conductors and on into the external power source, "eating current" and power as it goes. The product of the hole current and the voltage gives a negative power imposition, wherever the hole current interacts with the power system and its external power supply, even back into the distant huge power generator in the distant power plant. For a battery-powered circuit, e.g., excess hole current will pass into the battery and discharge it (change its chemistry in discharge mode) more quickly.

Indeed, a lead-acid battery (and some other kinds as well) can be supercharged with Dirac holes. What this actually means is that the local vacuum — in which the battery and its components and chemistry are embedded and in a continual exchange with — is altered to increase the number of empty Dirac sea holes devoid of electrons. At the same time, the local spacetime is also negatively curved. The end effect is that the battery is charged with negative energy, rather than positive energy. We propose that a battery or capacitor possessing an extreme negative energy charge should be lighter in weight than the same capacitor when uncharged.

As previously stated, some years ago, Jim Watson developed a very large multi-kilowatt COP>1.0 battery-powered generator, publicly demonstrating it at a technical conference (see again Figure 5-12). Engineering measurements at the conference verified that the batteries were constantly charging while the load was constantly powered at 8 kilowatts.

The longer Watson's system would run, the more charged his batteries became with *negative energy*. After one of his batteries had been used for a couple of weeks in extensive experiments, one could obtain a most novel effect when it was placed on a normal "positive energy" battery charger. The battery's excess "Dirac hole charge" or "negative energy charge" accumulated in its local vacuum would "eat positive power and electrons" from the battery charger for an extended period, sometimes as long as a week, with no symptoms of "charging" the battery at all (no increase in battery voltage at all). During this period, the battery charger was indeed recharging the *battery supersystem.* It was filling the excess Dirac sea hole charge in the vacuum with the steadily supplied electrons. In the process, it was gradually relaxing the previously formed negative spacetime curvature.[275] When all the Dirac holes were filled, the relaxed spacetime then was relatively flat (normal) as was the local vacuum, and suddenly the battery would charge-up normally again with positive energy, with its voltage increasing in quite normal fashion.[276]

---

[274] By converting separated incoming electrons and incoming holes to resulting filled Dirac sea electron holes, in the input section itself.

With tongue in cheek, we point out to the COP>1.0 researcher that these effects are not described in the available storage battery manuals, no matter how technically they are written. To the electrical engineer, we point out that they are not in his textbook.

Whenever Dirac sea holes have accumulated in the input area of the COP>1.0 system and are being filled by the external power supply, normal ammeters and voltmeters will only "see" that the external power system is furnishing more current. That is true, because the holes are an additional load being powered. The holes "eat incoming electron current and power", and require the external power supply to "power the killing of the holes" as well as "power the system".

The unwary overunity experimenter can successfully have the first phase of an overunity system working and not realize it, because his initial COP is too high and he does not know about the associated hole current decay of overunity systems back to underunity systems. His system may actually be at COP>1.0, but the negative energy component being produced in his output section is back-flowing and continuously degrading his input section by adding a "new load" right in the input section.

---

[275] This proves that a system's supersystem can indeed be negative-energy-charged, so that the local spacetime around that system is negatively curved, even though the system itself seems normal and functions normally. If the negative energy charge is . sufficient, conceivably the antigravity produced will be sufficiently great that the system itself "floats" or even levitates. We hypothesize that an intense negative energy beam can indeed be technically created which will accomplish this "negative-energy-charging of the supersystem" effect when continuously absorbed by a targeted system's local spacetime supersystem component, as the system is continuously irradiated by the beam. In that manner, levitation beams, tractor beams (both attracting and repelling) are at least hypothetically possible. If this proves to be a valid hypothesis, we foresee the day when such beams will revolutionize transportation and handling of otherwise heavy loads and very heavy systems. Even the heaviest vehicle could then negatively charge its own supersystem's local curved spacetime, thereby floating in the earth's gravity, in the atmosphere, in space, and under the ocean.

[276] We deliberately omit discussion of the extraordinary all-purpose weapons implications of negative energy electromagnetic pulse (EMP) directed energy weapons, already developed and deployed by several major nations.

So his overall power draw from the external power source can be such that his positive power output in the load is less than his total power draw at the input of his system. Unless he is aware of the process and how to handle it, he may never realize that his system is actually at COP>1.0 condition, when the negative energy component is credited as an output "plus".[277] *COP>1.0 research starts by evaluating the absolute value of the output energy, then working from there!* The experimenter must be ever aware that he can and will have Dirac sea 4-holes and currents in any unitary COP>1.0 electrical power system, and particularly in those with very high COP. He must understand what the 4-hole currents and the negative energy actually do and how they function in the overunity system unless corrected.

Any COP»1.0 EM system demonstrates the Dirac sea 4-hole current phenomenon as nature's special decay mechanism to reduce overall performance of the COP»1.0 power system and its external power supply to COP < 1.0 — unless one *corrects* the problem and prevents the decay process (developed later in this chapter).

One symptom of the negative 4-hole currents is their cooling capability rather than heating. Another is that the excess current (and power) drawn from the external power supply also does not heat the input section of the system. Another is that semiconductors operating within the Dirac 4-hole current flow are likely to fail immediately and permanently.

We strongly suggest that, for high COP systems experimentation, the experimenter use a system of synchronized clocks where the lab clock is synchronized with a remote clock prior to the experiments, then the two clock times are examined after significant experimentation at COP»1.0. If deviation beyond normal error in synchronizing occurs, then the involvement of spacetime curvature effects is indicated. Two decades ago, anomalous experiments by Golden — with whom I was working at the time — charged the area with negative energy, producing a significantly curved local spacetime which disrupted local clocks and watches for four days as the charge gradually decayed away. Another indicator is that Geiger counters and other nuclear radiation detectors often "read" when bathed in vacuum 4-hole current, because of the ionization changes induced in them and also because of their individual previous "time-charge" histories. After all, ionization instruments "read" anything which causes ionization of their internal gases. Dirac sea hole current, if interacting with the gas, is in fact a very special new form of "ionizing" radiation.

---

[277] In other words, in the presence of both positive and negative energy output, true COP is not "positive energy out" divided by "positive energy input by the operator", but is more appropriately "total absolute value of the energy output" divided by the "positive energy input by the operator".

9.11.2 Antigravity Hole Current Effects in a COP»1.0 EM System.

Any COP>1.0 EM system can exhibit minor, usually barely detectable antigravity effects due to the presence of the negative local energy 4-holes in the hole current if the hole current is not transduced or corrected. It can also produce minor antigravity "thrust" due to the flow of the local energy holes. Usually these effects are not even noticeable in an overunity system unless it has very high gain (very high COP, say in the range of 10^5 to 10^6 or more.).

However, if the EM system's COP » 1.0, and reaches 10^5 to 10^6 or more, the antigravity and thrust effects may become significant and easily detectable. At 10^9 they become highly significant and are very detectable: The unit will lose appreciable weight on the laboratory bench, and may even levitate easily.

An example is provided by the Sweet vacuum triode amplifier discussed above, with the results that were given in Figure 6-9. Such effects are also what generate the anomalous levitation phenomena of free-spirited John Hutchison.[278]

9.11.3 Negative Energy Effect When Leads Shorted

When the leads of a COP>1.0 EM system are shorted, a noticeable cooling effect can sometimes be detected. If COP»1.0, shorting the leads will result in instant icing from the water vapor in the surrounding air.

If one accidentally shorts oneself across the leads of a COP»1.0 system, the effect is to freeze the nerves along the pathway of conduction. Experimenters are cautioned to use every safety precaution. Their experimentation is at their own assumed risk.

---

[278] John Hutchison, "The Hutchison Effect apparatus." *Proc. Intl. Symp. New Energy,* Denver, Colorado, May 12-15, 1994, p. 191-198.

Anecdotally, some older researchers reported that their constant handling of overunity circuits resulting in charging their bodies, apparently with negative energy. The body after all may be considered as a special kind of complicated capacitor or set of capacitors, so this is reasonable, based on Bedini's and Watson's demonstrated negative energy charging of a battery. Some of the older overunity researchers reported that, after charged in that manner, they could produce a 3-inch spark from their fingers, or a "slight shock" into the body of a person they touched.

There is even a special form of acupuncture in the East in which the practitioner uses special exercises to charge the body with negative energy in this fashion. The "electro acupuncture" is then administered by the operator twirling the inserted acupuncture needles between his fingers, and deliberately administering a jolt of negative energy from his body into selected points in the body. I have personally tested a person who could deliver strong "electric shocks" into one's hand or body, and who could consistently produce a 1-inch spark discharge between the hands at will. That person could also deliver a very astonishing "jolt" to one's body, particularly in the vicinity of the liver.

There appear to be similar rare negative energy phenomena in semiconductors {585a-585c}. Anecdotally, it appears that the body does have structures or methods of storing and using Dirac sea holes (negative energy) and mechanisms for accessing the negative energy charged in its supersystem. This is suggested as a fruitful line of future research for interested biophysicists. Again, we call attention to the fact that, whenever EM fields, potentials, and waves are present, Dirac sea effects are also present and involved. Little or no biophysical experimentation has been done utilizing higher symmetry electrodynamics and analysis of the supersystem effects. Contrary to the received view, the understanding of EM effects on biological systems is not mature at all, but is still in its infancy.

9.12 Susceptible Unitary System without Conversion of Dirac Sea Hole Current

A *unitary system* is simply a self-contained single power system with an overall closed current loop between the source dipole and system loads and losses. A unitary system is contrasted to an array system of synchronized separate power subsystems without a common closed current loop, with the array subsystems connected to the source dipole by energy transmission-reception only. Hence the array system utilizes the Kron open path concept.

Beginning at about COP = 1.2 to 1.5, a few highly susceptible unitary COP>1.0 electrical power systems will experience significant Dirac hole current from output to input. This will produce a "negative energy load" in its input section and feed line from the external power system, resulting in decay back to an overall "system plus negative energy load" of COP<1.0. At the COP = 2.0 level, in the susceptible system the effect will forcibly decay the COP back down to overall COP<1.0. It does this by forcing excess power to be furnished by the external power system to "power" (fill) the Dirac hole current arriving in the input section of the power system. In short, it converts the system to a composite system containing an additional Dirac negative energy load in its input section.

Or in other words, it forces the operator to "pay" for both the *positive* energy output and losses of his system and the *negative* energy output and losses of his system.

In addition to usual powering of its load and losses, such a system is also "powering" the return of its own locally altered vacuum back to a more normal ambient vacuum, instead of stabilizing its supersystem in a stationary disequilibrium state. It is a supersystem interaction and effect. A COP>1.0 system that significantly exhibits this phenomenon is said to be a "susceptible" system.

One of the first tasks of the COP>1.0 experimenter is to ascertain whether he is working on such a highly susceptible COP> 1.0 system. Ironically, he does this by observing his COP>1.0 system kick itself back into a COP<1.0 system. If he carefully observes the initial COP>1.0 condition followed by decay into COP<1.0 condition, he must then realize that not all is lost! In short, he must realize he has developed a susceptible system. If he obtains COP>1.0 only to watch it subsequently decay back to COP<1.0, he has just discovered he is working on a susceptible COP>1.0 system, *and that is experimental progress.* He isn't there yet, but he is en route. In that case, he must concentrate on transducing the excess hole current into usable electron current, to "stabilize" and "lock" his system in its COP>1.0 operating condition.

9.13 Unitary System with Conversion of Dirac Sea Hole Current

Using the Bedini conversion process, a unitary system can be close-looped to maintain COP> 1.0 and stable overunity operation. The 4-hole current reaching the input section is intercepted by the Bedini mechanism, and transformed to ordinary electron current furnished to the input section. Thus the transduced negative energy feedback becomes a positive energy feedback, by conversion. This converted positive energy in the input section will reduce the demand for incoming electron current from the external power supply, increasing the COP>1.0 even more.

A feedback and governing system is adjusted until the system's converted positive energy feedback current reaches the Kron condition. At that point, the transformed electron current is sufficient to power the system with the external power supply disconnected. The governing and control system thus disconnects the external power supply, and the system is smoothly transitioned to self-powering operation, powering both itself and its load.

We stress that all the energy to power the system and its load is now being furnished from the active local vacuum interaction and from the local curved spacetime. No laws of nature, physics, higher symmetry electrodynamics, or thermodynamics are violated. Conservation of energy rigorously applies, but to the supersystem. The system is an open, *stabilized* disequilibrium system — of the kind referred to by Kondepudi and Prigogine as nonequilibrium stationary states — as a freely receiving all its energy from its active external environment. No standard U(l) electrodynamic analysis will show this condition or this mechanism, and neither will electrical engineering. Higher group symmetry electrodynamics such as SU(2) or O(3) will show it easily. For a modern treatise on O(3), we refer the reader to the recent *tour deforce* by Evans {586}.

9.14 Non-unitary Outrigger Array System

See Figure 9-14, which is a diagrammatic representation of a COP>1.0 array system that is non-unitary. In the non-unitary (outrigger array) system, no part of the outrigger array works at $\xi > 1.0$. All external parts operate at $\xi < 1.0$, but independently and with COP>1.0. Each of the external outrigger systems is an open system freely receiving excess energy from its active environment, because it is an "energy-receiving" system and the energy is freely transmitted from the central system. The central part of the array is the unit whose purpose is to stimulate or evoke an excess energy flow from the vacuum, so that the outrigger receiver/power units can individually intercept and utilize radiating energy flow surrounding the central unit.[279] The usable (output) energy intercepted and captured (collected) from a given free flow of energy depends totally on the intercepting reaction cross section — usually the total array amount of intercepting charge, together with the degree of resonance (sweeping a larger geometrical cross section) of the intercepting charge.



Figure 9-14 The nonunitary (outrigger array) system and its functioning.

Each outrigger unit (subsystem) has its own complete closed current loop *separate* system and load, plus its "antenna" or "interception section" or receiving component for intercepting and collecting the free flow of energy coming from the central source unit (the energy transmitter). Thus, the loads in the outrigger units are not closed-current-connected with the central source unit at all. Each outrigger unit has its own independent electrical ground and its own closed loop system with its load.

---

[279] We emphasize that, when the usually unaccounted Heaviside nondiverged energy flow component surrounding the conductors of the external circuit is accounted, every EM power system is already a COP»1.0 EM energy transduction system. Consequently, in the received view the array system can be operated at COP>1.0, or even in self-powering mode, even though the central system is "said" to be at COP<1.0. It is at COP<1.0 only because of the self-applied Lorentz symmetrical regauging and ignoring the excess unused energy flow available to and surrounding the circuit, but not conventionally used. If we account the COP for what we have to furnish to the central unit, then the COP of each array unit is COP = ∞. The point is that we ourselves do not have to pay any *extra* input energy for the output energy of each array circuit.

This schema in fact separates the two functions of Poynting energy flow theory: (i) the extraction and radiation of the EM energy flow from the seething vacuum, and (ii) the interception, collection, and dissipation of some of that available energy flow, to power the loads and losses of the intercepting system.

In this fashion, multicollection from a single energy flow (generated from a central source "transmitter") occurs by direct, independent interception and collection in each of the COP<1.0 outrigger units. However, the input power to each outrigger units is *free* with respect to that outrigger circuit itself. We of course must pay to generate the flow of energy from the central unit, but that can be done in normal COP<1.0 manner (such as COP = 0.95) while powering its load.[280] Let the output power of each numbered unit (including the central source unit) be given by P_i, n be the number of power units, and P_T be the total power output. Then the total output P_T of the array system is given by

$$P_T = \sum_i P_i = P_1 + P_2 + \cdots + P_n \qquad [2]$$

The total input power P_I is simply the input power $P_{I(1)}$ to the central source unit. The COP is given by COP = $P_T/P_{I(1)}$.

In the motionless electromagnetic generator (MEG) array, for example, the central unit is the transformer-like unit, deliberately using a special core to contain the magnetic flux of a permanent magnet in contact with the core material, thereby stimulating the Aharonov-Bohm effect and freely filling the surrounding space with the uncurled magnetic vector potential A. We will explain the non-unitary (outrigger array) system using the MEG as an example.

---

[280] We again stress that, from any nonzero potential ϕ, or from any EM field in space, any amount of EM energy can be collected if there is sufficient intercepting and collecting charge. For example, the simple equation $W = \phi q$ applies for the potential, where W is the energy collected from a potential with point intensity ϕ by collecting charges q. A similar equation applies with respect to collecting as much force (emf in the various outrigger circuits) as desired. Here a single given E-field E can be assumed, and $F = Eq$. What is happening in the outriggers is that they are intercepting and collecting some of the excess Heaviside energy flow component that is wasted by the central circuit.

The MEG freely induces the Aharonov-Bohm effect,[281] thereby extracting excess energy from the vacuum in the form of that novel field-free A-potential. Being field-free, A represents an energy flow without swirl (without curl). When the MEG input section is perturbed, the surrounding A-flow is perturbed also, giving a pulsed or AC flow of energy that can be intercepted and utilized by each outrigger circuit as an E-field energy interception.

The central unit's COP<1.0 function is to output almost as much, or as much, energy as is required to power the MEG, while also evoking that excess A-flow and serving as a $COP \gg 1.0$ energy flow transducer. The function of each outrigger is then to intercept some of the pulsed A-flow (as E-field energy via the equation $dA/dt = -E$), in its antenna or interceptor section. Each outrigger has its own independent and conventional closed loop circuit. It simply is a receiver and user of extra Heaviside EM energy produced from the central MEG unit in the new form of the curl-free A-potential. Perturbing the A-potential produces a large E-field impinging on all the external outrigger subunits. Hence these units freely collect and use some of that available excess energy. The COP of the total array is thus COP>1.0. For best results, tuned antenna theory and near field theory should be utilized.

Suppose we operate the MEG central unit at COP = 1.0. In that case, there is no 4-hole current of significance associated with the central unit or the outriggers, and transduction of hole current into electron current for close-looping is not necessary. Instead, sufficient outriggers are employed so that the total energy W_O caught and dissipated in their loads by all the outriggers is given by $W_O \geq W_I$, where W_I is the input energy in the main central section. Since COP = 1.0 for the central unit in isolation, the total input E_{IN} is $E_{IN} = W_T$ (the additional huge Heaviside nondiverged EM energy input component is there also, but just neglected in conventional engineering). The total output W_A of the entire array is $W_A = W_O + W_T$. The overall COP_A of the entire array is thus

$$COP_A = W_A/E_{IN} = (W_O + W_T)/W_T = (W_O/W_T + 1.0) > 1.0 \quad [3]$$

---

[281] The reader should recall that the Aharonov-Bohm effect is not included in classical U(1) electrodynamics. See Terence W. Barrett, "Electromagnetic Phenomena Not Explained by Maxwell's Equations," in A. Lakhtakia (ed.): *Essays on the Formal Aspects of Electromagnetic Theory,* World Scientific Publishing, River Edge, NJ, 1993, p. 6-86.

Hence the array has a COP>1.0, even though every single component of the array has $\xi < 1.0$. With the outriggers fully functioning, many schemes of operation can be used. E.g., the energy from the outriggers can be used to steadily charge a capacitor bank by "shuttling". We define shuttling as use of two capacitor banks: (1) a capacitor bank which is continually connected and charged by the outriggers as their effective output, and (2) an input capacitor bank for the central unit that is continually connected and recharged from the outrigger capacitor bank. By adroit switching, the charge of the input capacitor bank is maintained by replenishing from the output capacitor bank, and the input capacitor bank powers the entire system, including the output load in the central section.

The non-unitary outrigger array construction is one means of close-looping a non-unitary overunity power system without bothering with the transduction of hole current into electron current. It is the easiest of all COP>1.0 systems to close-loop for self-powering.

An additional adaptation is for each outrigger also to continuously power a separate load, and only contribute *intermittently* along with the other outriggers to charging the output capacitor bank.

Another adaptation is to operate the central unit in the array in solitary self-powering mode.

These and similar modes of nonunitary array system operation allow close-looping the system for self-powering of itself and its load, without concern **for** 4-hole current transduction. A real advantage of such nonunitary systems without worrisome 4-hole current is that transistors can readily be used for switching etc. in them, without the destruction of the transistors by a damaging Dirac 4-hole current in the supersystem.

The nonunitary overunity system can also be close-looped by *conventional* (simple) "clamped positive feedback" means if good isolation (e.g., optical isolation of the circuitry switching) is used in the feedback loops.

9.15 Some Instrument Considerations

9.15.1 Time Effects

As previously indicated, there are time-domain effects (potentials, forces, and currents) associated with a COP>1.0 EM system, particularly as the COP increases toward COP»1.0. A useful method of indicating time-effects is to utilize a transistor in a circuit capable of measuring recombination time in the transistor.[282] NASA has such circuitry available, but I do not have the reference at hand. We leave it as an exercise to the reader to explore that possibility.

For "very large COP" devices, ordinary watches, clocks etc. may be affected. Particularly significant is the slowing of timepieces in the presence of substantial time-domain effects due to substantial negative energy. In addition, for high gain devices (and for some at lower COP), the negative energy charge can build up in the local area, and may then require some days to dissipate. As we stated, in experiments years ago with Frank Golden, we experienced just such alteration of multiple kinds of clocks and watches in an area. It required four days for the negative energy charge in the area to gradually drain off (for the excess Dirac sea holes to gradually be filled with electrons, as the tempic potential gradually returned to normal).

Effects that were even more dramatic were exhibited in experiments conducted by Sid Hurwich in Canada some years ago {587}. In a series of experiments lasting a half-hour, Hurwich inertially jammed a police revolver so that a human finger could not pull its trigger. *The watches of the witnesses did not change their setting during that entire half-hour.* This cannot be understood by conventional electrical system analysis, but potentially it can be understood by supersystem analysis.

9.15.2 Calorimetry Is Taboo for Overunity System COP Measurement

It is standard dogma that calorimetry is a "true" measurement of power, and is always accurate in the hands of a skilled practitioner. In general, that is true for a COP<1.0 system, where one is concerned only with *positive energy* in the input and output sections. However, with respect to COP>1.0 systems, nothing could be farther from the truth. Indeed, for a significant COP»1.0 system, a calorimeter is one of the most inaccurate instruments that can possibly be used.

As previously stated, all COP>1.0 EM systems produce a mixture of negative and positive energy in their output section. The higher the COP, the greater the percentage of negative energy and the greater the flux of Dirac 4-holes back to the input section. The output energy, immersed in a calorimeter, will both cool the water with its negative energy output fraction and heat the water with its positive energy output fraction. Hence, the calorimeter will show the *difference* between the water's simultaneous heating and cooling. If the calorimeter measurement is misinterpreted as the *total energy output*, this "definitive test" will always erroneously show COP<1.0. After all, it itself already applies the decay mechanism for converting any overunity system to an underunity system.

---

[282] This suggestion is courtesy of John Schnurer some years ago, and is appreciated.

The only good use of the calorimeter in an overunity EM system is to verify that negative energy is present, when comparing its measurements to more sophisticated electrical measurements of the system. It can be used along with other measurements to ascertain (1) the total energy output, whether negative or positive, (2) the difference in the two forms of energy output and the algebraic sign of the resultant (positive if calorimeter heated, negative if calorimeter cools), and (3) thereby help determine the output's energy fractions (positive energy divided by total energy, negative energy divided by total energy).

Any test group insisting on testing a purported COP>1.0 electrical system with a calorimeter as the *definitive statement of energy output* is totally devoid of knowledge of COP>1.0 systems and their phenomenology. Usually such "test groups" tend to regard themselves as "measurement experts" (which they well may be, in COP<1.0 positive energy systems!). That does not make the team even minimally knowledgeable or qualified in COP>1.0 system measurement. To the contrary, the team members have zero experience or knowledge of COP>1.0 systems. The proposed test group may consist of physicists, thermodynamicists, electrical engineers, technicians, or all four, but they still will have no knowledge or expertise in COP>1.0 EM power systems unless they have actually worked with such systems before, and at length.[283] This is particularly true of COP»1.0 systems. My advice to all COP>1.0 researchers is simply to keep the "calorimeter addicts" out of one's laboratory in the first place.

9.15.3 Other Instrumental aspects.

Here we just point out some simple and obvious things, familiar to the experienced researcher but sometimes not appreciated by the novice. One is usually dealing with nonsinusoidal waves, pulses, spikes and the like. As is well known, RMS meters are useless for measuring such nonsinusoidal electrical entities, since they are designed and calibrated to measure sine waves only, or to measure DC. One must use a good differential sampling scope with multiple synchronized channels, with professional software to perform accurate integration under the curve, and with special differential probes for the scope. Simultaneous triggering of the multiple measurement channels on the same time line is required. The necessary high quality probe set may cost as much or more than the oscilloscope!

---

[283] To date, we have found none who have actually worked with COP>1.0 electrical systems. We have, however, found quite a few who, though totally inexperienced with COP>1.0 systems and not knowledgeable, have regarded themselves as "real experts" in such systems. They claim to already know how COP>1.0 systems work and behave, and assume just ordinary electrical system phenomena.

Dirac sea hole currents are generally not separately measurable, so one measures where the hole currents are not significantly present. Results may be compared to measurements where the hole currents are known to be present. When directly measuring hole currents, the conventional meters often read "backwards" and interpret a negative energy output at the system output section as subtracted from the positive energy, and interpret a negative energy output at the input section of the system as additional input electron currents from the external power supply. If the electron currents from the external power supply are not present, then measuring hole currents will draw electron currents from the power system inside the meter itself, resulting in a "backward measurement". Again, the meter actually will measure a real electron current, whether from the external power supply or from a conversion within the meter itself.[284]

Recombination time in semiconductors can sometimes be used in instrumented circuits to differentiate between negative hole current and electron current, by observing the change in recombination time due to the negative energy currents. It will differ from the change in recombination time due to positive energy currents.

Again, what is needed in the field is a set of solid, reliable instrumentation specifically developed for these peculiar measurement phenomena involving both positive energy and negative energy. To my knowledge, no such thoroughly designed and tested instrument package presently exists. Further, there are not even any standards for such, since there are apparently no standards for negative energy measurement at all.

9.16 Still Anomalous Aspects

Several aspects of COP>1.0 systems are still not properly understood. The behavior of curl-free A-potential, sometimes produced in such systems, is a case in point. This type of energy can exhibit characteristics as if it were electrostatic energy, which my associates sometimes refer to as the "crawly stuff. It exhibits the characteristic of "crawling" all over the surfaces (outside and inside) of the objects in the area, including the scopes, producing internal electrostatics and possibly magnetostatics everywhere. This can easily destroy the amplifiers etc. in a good scope or an expensive meter. It is best to transform this field-free A-potential into an ordinary "EM field energy AC wave", and then utilize it in that fashion.

---

[284] What is very much needed is a meter of sophisticated design where this "drawing of excess electron current from within the meter itself has been taken into account in the design, so that the meter functions correctly for either positive energy measurement or negative energy measurement.

Scalar stress waves are also sometimes produced, leading to anomalous effects. This is best regarded as a "time-polarized" EM wave, or more accurately, as a combination of scalar (time-polarized) EM waves and longitudinal EM waves in 3-space. For macroscopic waves in COP>1.0 systems, the Mandl and Shaw 1:1 correlation between scalar photons and longitudinal photons can apparently be corrupted, so then one has "abnormal" (improperly correlated components which normally correlate to make "ordinary" EM waves). These abnormal EM scalar stress waves also exhibit the "crawly" phenomenon, and can be hazardous to one's instruments.

In addition, some instruments such as ionization counters, Geiger tubes, etc. read in the presence of such waves as if nuclear radiation were present (which it is not). Also, the individual time-charge history of a given instrument determines or substantially influences how the instrument reacts in the presence of the "corrupted" scalar stress waves. Essentially, at a given time any instrument has a small "time-energy charge" depending upon its past history. The corrupted scalar stress wave accomplishes further "time-charging" of the instrument, which combines with the initial time-charge to produce more time-charge, ordinary EM waves by scalar EM interferometry {588}, or abnormally correlated longitudinal EM wave emission.

In an ionization-measuring instrument, *ionization is ionization, by whatever means achieved.* And in the presence of the "abnormal" radiation and charging, ionization-type "nuclear radiation" instruments will vary from one to another, *depending upon the individual time-history ofeach instrument.* So from a group of identical instruments made the same day on the same assembly line, one may read anomalously and several others read normally. Or two may read anomalously, while all the rest read normally. A very good example of this anomalous measurement effect is seen in the rigorous electrolyte experiments in U.S. Navy research facilities at China Lake {589}. The present author has previously given an explanation of this time-charging and decay phenomenon {590}.

Negative energy reacts in different ways with different materials. The more nonlinear the material, the greater the effects and unpredictability of the interaction, as a rule of thumb. In a copper wire, Dirac hole current introduced into the wire will "eat" Drude gas electrons, reducing the "pressure" at that point or area in the wire. This "combining of electrons and causal Dirac holes is not normal pair annihilation, and radiation does not occur. Instead, the two curvatures of spacetime (one by the positive energy of the electron and the other by the negative energy of the Dirac hole before observation) interact and adjust.

The Drude gas in the copper further back toward the external power system still has normal (higher) gas pressure, and so the differential in pressure induced in the Drude gas will drive electrons from the "normal" pressure areas into the "reduced" pressure area where some of the Drude electrons disappeared after being "eaten" by the Dirac holes. To look at that in lattice hole terms, the "eating" of Drude electrons in a selected volume of the wire leaves positive ions, which are "lattice holes" vacated by the eaten electrons. So these excess positive charges attract electrons from further up the wire nearer the distant power supply, filling the lattice holes to bring the Drude gas back up to "normal". However, that also draws and "eats" additional power from the distant power supply. Meanwhile, the Dirac 4-holes fed from the input of the COP>1.0 system back into the power feed conductors continue to interact with the lattice and eat electrons to create more ions (lattice holes).

One may visualize the Dirac sea holes producing excess lattice holes, which then causes the Drude electron gas to change so that the "average" demand current increases. In short, we must also consider the effect of Dirac hole charges or currents upon the lattice material itself, and the structure of holes and electrons as charge carriers in the material lattice.

Semiconductors are very vulnerable to negative energy due to its disruption of their donor-acceptor and band gap design functions. With mild negative energy exposure, a semiconductor may just cease operation entirely and later recover when the negative energy application ceases, or it may fail and never recover. For pulsing, strong "opposing force pulses" (stress pulses) are created deep inside the semiconductor materials. In case of sharp pulsing, sometimes an exposed semiconductor will just suddenly explode in a nice little fireball about one foot in diameter. This along with some minute stinging fragments from the explosion assures that the COP>1.0 bench researchers stay alert and on their toes. Needless to say, when experimenting with COP>1.0 systems and circuits, one should exercise all safety precautions, including safety glasses, until the **"negative** energy beasts have been tamed and controlled". One should not experiment with such things unless one is an experienced and safety conscious experimenter. One experiments at one's own risk.

Negative energy effects in coils and toroidal coils are largely still unknown, though we have outlined some of the major effects. For a normal helical coil, one can derive a concept of the effects by considering the lattice effects in the wire. In this case, introduction of hole current at one end of a helical coil will induce electron current from the other end and into the coil. Thus, hole current can be "switched" back and forth between the ends of a helical coil to induce an ordinary AC electron current in the coil, accompanied by normal magnetic fields etc. A point can be reached where the coil is actually in resonance with the frequency of the switching, and with the "seeming capacitance" of the hole current introduction in each switching. With the proper material in the coil and a keen balance between the negative energy capacitance effect and the normal positive energy induction effect, *in theory* a single coil can be turned into a self-oscillating, self-powering system.

With core material inside the core of a coil, the situation dramatically changes. Often the type reaction experienced will appreciably depend upon the core material, and changing the core material can dramatically change the effects upon the coil and the effects that the coil produces. One may even use dynamic changes in the core material to produce corresponding dynamic changes in the coil. A toroid may act differently from an ordinary helical coil, as does a flat (spiral-wound) coil. Here the experimenter must simply perform his own experiments to seek out and understand the phenomenology he uncovers.

For exploratory experimenting with core-filled coils, we advise strong caution and testing at very low power only. Sometime effects can apparently be experienced by the researcher (headaches, nausea, dizziness, etc.) It is suspected from some evidence (but not proved) that the core material's chemical characteristics can sometimes be "imprinted" upon the human body chemistry, from the novel radiation of a core-filled coil or some core-filled coils. This is particularly true in the presence of strong stress potentials, such as from bi-wound coils with fields in opposition, and particularly if the biwound coil contains a nonlinear material core. The nonlinear core induces modulation (multiplication) of the two waves, rather than linear mixing. Thus, the two waves are "locked together" to form a true stress potential and local spacetime curvature sets, when the biwound coil has a nonlinear material core. In short, one is now engineering pure general relativity, locally.

Again, we iterate that the experimenter should be knowledgeable and take all safety precautions. He experiments at his own assumption of risk.

The appearance of an extra stress potential (field-free) in a biwound coil is in fact a new Lorentz symmetrical regauging, and the equivalent of rotating the frame of the coil. As signals are introduced, this is the equivalent of continually changing the degree of the frame rotation, which is a general relativistic effect, with direct curvatures of spacetime being produced. In short, one is producing spacetime curvature and rotation engines, previously discussed.

The magnitude of the stress potential (field-free) falls off inversely as the distance. Thus one's body can be exposed to it, including the body chemistry, every cell and every part of every cell, the nervous system, etc. Placing signals on the biwound coil can conceivably result in slight variation of the scalar stress potential, including inside the body, and inside each cell and each part of each cell. Variation in the stress potential ϕ in a little local region inside the body produces $-\nabla\phi$, which is an electric field E. The rate of change of this E-field then produces a magnetic field H.

Consequently, very minute EM fields are produced throughout the body and all its parts, or can be. It is as if the entire body is "electromagnetically washed" in internal EM fields throughout its matter, structures, and dynamics. The hydrogen bonding actions ever ongoing are particularly sensitive and can restructure appreciably in the presence of this stimulus. They can also "imprint" and take on a specific induced structure and dynamics, correlated to the persistent changes induced from the biwound coil. As can be seen, such EM biological effects have not been appreciably investigated and documented in the Western scientific literature. Hence our urging and insistence that the researcher use all caution, and our warning that he experiments at his own will and assumption of risk. Neither the publisher nor the present author is responsible for any accidents or blunders that may occur.

Capacitor effects also vary between types of capacitors, when applying negative energy or a mix of positive and negative energy. Some capacitor dielectric materials are also photo-refractive and are semiconducting materials, hence photoactive. The rich effects capable of being generated in capacitors — by EM fields, waves, potentials, and pulses of negative energy or negative and positive energy mixed — are largely unexplored and not catalogued.

Almost all modern permanent magnetic materials are also photo-refractive or photoactive materials as well, and many are semiconducting materials. Hence a rich variety of effects can be produced in permanent magnets by the introduction of negative energy fields, potentials, waves, and pulses.

As can be seen, a very rich combination of effects exists for "normal-appearing" coils, capacitors, semiconductors, and magnets when applying appreciable negative energy or controlled mixes of positive and negative EM energy. This is a still largely unknown materials science region, and one that has not been systematically and rigorously explored and catalogued, if at all.

In addition, there are effects from *pulsing* negative energy (Dirac hole currents) that are not completely understood. These appear to occur almost — or partially — at random, and also seem to be affected by the natural surroundings, by the various materials, etc. The "imprinting" phenomenon, when it occurs, seems to be augmented by pulsing, and sometimes by the pulse shape and pulse repetition frequency as well as the surroundings.

We also legally state that we are not responsible for any risks the researcher chooses to take, but are only alerting him to be very careful and use very good safety practices. Any experimenter is himself responsible for stringent adherence to good safety practice and common sense, and he legally assumes his own personal risks for all experiments he chooses to undertake.

Another effect to be alert to is the effect of "charging" the local area's supersystem with an altered active vacuum and curvatures of spacetime. This phenomenon is usually experienced as a "slow growth" of the COP of the system, over a long time (months or years). Tiller in private discussions has reported such phenomena in his detector built at Stanford University. Golden and I experienced such phenomena with a small COP>1.0 system Golden was developing. Over a period of five years, the system slowly increased its COP to about 2.0. Moved several hundred miles, the system then exhibited COP of about 0.9, but with occasional fluctuations of overunity temporarily.[285] Golden had gradually charged his local area with the "engine" or spacetime curvature operational and functional form of his unit. Thus in that repeatedly charging area, gradually the operation of the unit improved. We referred to this *engine-*

---

[285] In fact, Golden and I were astounded at these results, until Tiller explained it to us and explained his own experiences with "growing" his detector. Thanks to Professor Tiller, thereafter we had this new phenomenon firmly fixed in our lexicon.

charging of the environment with a particular effect or dynamic form as *kindling.*

The kindling or "charging to favor the dynamic form of the engine or device" problem, should it occur, is in fact usable because it is possible to produce it everywhere on earth, and fairly permanently. To use the kindling effect once discovered, the mechanism is to build several identical units. Keep the original unit working in the original area, and "outrigger" the others at radial distances as distant as possible, but maintaining COP>1.0 for the outriggers. Then simply run both the outriggers and the central unit, steadily. The "structural charge" will grow and reinforce at the outrigger locations, then spread on beyond the outriggers, and a much larger area will now be "charged with that dynamic form". With sufficient additional outriggering (three to five, or seven in an especially difficult case) where the successively internal outriggers arc retained and operating, the charging will eventually spread around the entire Earth, and *it will become a permanent fixture of the Earth environment itself.*[286] Thereafter, anytime one of the units is turned on anywhere on earth, it will perform with its normal overunity condition. In other words, not only can one grow the dynamic form (engine) in a supersystem in a given locality, but one can also kindle it into the entire Earth's supersystem permanently {591}. One is strongly reminded of Feynman's observation that physicists with their big accelerators may in fact be partially creating their own reality. He pointed out that often the physicists look and look for a new, predicted particle. At last and after years of difficulty, finally a "glimpse" of the particle occurs in an accelerator and is reported. The physicists quickly crank up the other accelerators and look intensively, and — after some moderate difficulties — they find that particle. Thereafter, *every time an accelerator turns on and looks, that particle is readily seen, easily.*

The supersystem's spacetime is part of the local spacetime of the Earth, and all supersystems also interact with each other. As Kron put it {592}:

> *"An electric network differs from all other types of non-electric networks in that it is always surrounded in all directions to infinity by an invisible dynamic electromagnetic field of its own creation. ... Each Inductance L produces its own magnetic field, each*

---

[286] We have proposed an application of this phenomenon to kindle and maintain a specific disease organism's "anti-engine" as a startlingly new kind of medical therapy for permanently eradicating a particular disease vector from the earth.

> *capacitance produces its own electric field and each resistance R creates a thermodynamic field of its own. Moreover, there exists a continuous interaction between the magnetic, electric, thermodynamic, and radiation fields. Thus any correct and basic theory of the electric network must include all the parameters of its surrounding electromagnetic field and must satisfy all the field equations of Maxwell. The theory must also dovetail with the Hamiltonian and Lagrangean equations of dynamics containing both time and space derivatives, as well of the equations of irreversible thermodynamics. "*

So decades ago, Kron was struggling with the "supersystem" problem, in different terminology, and he eventually originated *diakoptics* {593}, an entirely new way of breaking the problem down piecemeal so it could be solved. But Kron strongly stressed that the interactions of the fields and potentials of a circuit and all its parts reach to infinity and have an n-dimensional set of degrees of freedom and an infinity of spaces. The fields and potentials of every charge reach to infinity (for those charges in matter from the beginning), and so every charge in the universe interacts with every other charge and its fields, potentials, and dynamics. Spacetime itself is filled with these interacting EM fields, potentials, waves, and dynamics. Little wonder that the horrendous set of ongoing EM interactions at every point in the vacuum has such incredible energy density and fluctuations. We may even regard the fluctuations and interactions as completely causal, but — with no information on each interaction — they must be treated as totally statistical. Ultimately nature confounds our Aristotelian logic and insists that, in the limit, one is dealing with 5-law logic as developed earlier in this book.

Since the earth near an ongoing COP>1.0 system experiment has innumerable electrical aspects, materials, etc., it follows that the surrounding earth is indeed in direct interaction with the experiment. It then follows that "slow conditioning" of the surrounding area should be possible, say, after some years as Golden experienced. It also follows that the effect diminishes in magnitude with distance from the experiment.

The "growth of the activation (kindling) to include the entire Earth" is a slow process, requiring years and much expense to aid the "spreading" — as the physicists may be experiencing, according to Feynman. But it is a doable.

We highly recommend that the researcher work on COP>1.0 systems that are not charge and location dependent, so that the kindling problem does not arise. We have assumed non-kindling COP>1.0 systems throughout most of this book.

Chapter 10

Cold Fusion: Low Spatial-Energy Nuclear Reactions at High Time-Energy

"This book is about time. I would have liked to have named it Time, the Forgotten Dimension..." **[Ilya** Prigogine]. {594}

"The notion of time may be unfolded into an independent pure science... a science of pure time is possible." [Sir William R. Hamilton, 1837]. {595}

"...contrary to the conclusions of classical mechanics, there exist effects of potentials on charged particles, even in the region where all the fields (and therefore the forces on the particles) vanish. " [Y. Aharonov and D. Bohm] {596}.

"...global behavior greatly modifies the very meaning of space and time. Much of geometry and physics is based on a simple concept of space and time, generally associated with Euclid and Galileo. In this view, time is homogeneous. Time translations may have no effect on physical events. Similarly, space is homogeneous and isotropic; again translations and rotations cannot alter the description of the physical world. It is quite remarkable that this simple conception of space and time may be broken by the occurrence of dissipative structures. Once a dissipative structure is formed, the homogeneity of time, as well as space, may be destroyed. " [Ilya Prigogine] {597}.

"As we expand our observation, we extend our concepts. Thus the simple symmetries that once seemed self-evident are no longer taken for granted. Out of studies of different kinds of interactions we are learning that symmetry in nature is some complex mixture of changing plus into

minus, running time backward and turning things inside out." [T. D. Lee] {598}.

"The desirable features of a system of units in any field are convenience and clarity. For example, theoretical physicists active in relativistic quantum field theory and the theory of elementary particles find it convenient to ***choose*** *the universal constants such as Planck's quantum of action and the velocity of light in vacuum to he dimensionless and of* ***unit magnitude.*** *The resulting system of units (called 'natural' units) has only* ***one*** *basic unit, customarily chosen to be length. All quantities, whether length or time or force or energy, etc., are expressed in terms of this one unit and have dimensions which are powers of its dimension. There is nothing contrived or less fundamental about such a system than one involving the meter, the kilogram, and the second as basic units. It is merely a matter of convenience."* [J. D. Jackson] {599}.

[Violation of Second Law of Thermodynamics] *"We experimentally demonstrate the fluctuation theorem, which predicts appreciable and measurable violations of the second law of thermodynamics for small systems over short time scales... Our results show entropy consumption can occur over colloidal length and time scales."* [Evans et al.][287]

[Implications] *"This result has profound consequences for any chemical or physical process that occurs over short times and in small regions."* [Evans et al.][288]

[Implications] *"The smaller a machine is, the greater the chance that it will run backwards."* [Evans et al., *ibid.]*

[Implications] *"Physicists knew that at atomic scales over very short periods of time, statistical mechanics is pushed*

---

[287] G. M. Wang, E. M. Sevick, Emil Mittag, Debra J. Searles, and Denis J. Evans, "Experimental Demonstration of Violations of the Second Law of Thermodynamics for Small Systems and Short Time Scales," *Phys. Rev. Lett.*, 89(5), 29 July 2002, 050601.

[288] BBC News, **18 July 2002, http://news.bbc.co.uk/l/hiscitech/2135779.stm.**

> *beyond its limit, and the second law does not apply. Put another way, situations that break the second law become much more probable. ...the new experiment probed the uncertain middle ground between extremely small-scale systems and macroscopic systems and showed that the second law can consistently be broken at micron scale, over time periods of up to two seconds."* [Chalmers][289]

10.1 Explaining Time as Energy

See Chapter 1, paragraph 1.1.3 and 1.4.1; see also Chapter 2, paragraph 2.1.3. As highlighted in the quotation from Jackson {599}, it is well known that the fundamental units chosen to model physical phenomena are arbitrary. In a physics model whose only fundamental unit is the joule, time is obviously modeled solely as a function of energy, just as mass is modeled today as a function of energy — hence the term "mass-energy". We may also equally well use the term "time-energy", since in a model using the joule as its only fundamental unit the second is purely a function of energy. Specifically, for our purposes 1 sec = 9 x 10^{16} joules of spatial energy, compressed by the factor c^2 and placed on the 4th Minkowski axis to constitute one second of time. If the compressed spatial energy had been left in 3-space, it would be recognized as *mass*. For our purposes, *time* has the same energy density as mass.

The flow of time becomes a special form of EM energy flow, analogous on the fourth axis to mass flow (translation) in 3-space. Further, as previously pointed out the overall flow of time has extensive internal structuring of component time-energy flows. However, time-flow is in the imaginary plane or connected with it, since in Minkowski space the 4th dimension is modeled as -i*ct*. Note that the only variable in *ict* is the *t*, hence anything varying on the fourth axis is a variation of time and time-energy *a priori.*

Further, we can apply conservation of EM energy to the time domain as well as in 3-space. And we can have "broken symmetry" in time-energy flow as well as in 3-spatial energy flow, so long as the net energy flow is conserved. The most fundamental conservation of energy law is giant negentropy: the automatic circulation of energy from the time domain into 3-space via decompression by the negative charge, thence the slight flow of 3-space energy to the positive charge where the 3-space energy is recompressed, thence from the positive charge back into the time domain.[290] That was our solution to the long-vexing problem of the source charge and its associated 3-space fields and potentials and their 3-space energy. From special relativity, one already knows that time can dilate and then *un*-dilate, but each action is associated with an appropriate change in spatial energy. While that change in spatial energy can be kinetic, it does not have to be. It can be a change in potential energy instead. In short, a static object rotates its frame with respect to the observer (lab) frame, whenever it absorbs or emits potential energy.

---

[289] Matthew Chalmers, "Second law of thermodynamics 'broken'." *New Scientist,* 19 July 2002, http://www.newscientist.com/news/print.jsp?id=ns99992572 .

We also pointed out the connection of time-energy to electromagnetics and to quantum field theory, via the four polarizations of the photon considered to travel in the z direction in 4-space. These four polarizations are with the energy vibrating along *x*-, *y*-, *z*-, and t- respectively. Vibration of the spatial energy of the photon along the *x*- or *y*- axis gives an ordinary transverse photon. Vibration of the spatial energy of the photon along the z- axis gives the longitudinal photon. Vibration of the time-energy component along the t- axis gives the scalar or time-polarized photon. We assume a similar four polarizations for EM waves in 4-space.[291]

10.2 Mechanism Generating Flow of a Mass through Time

As we covered in the referenced paragraphs in Chapters 1 and 2, the fundamental generatrix of the flow of a mass through time — and the structuring of that flow — is the total photon interaction with the mass and all its parts. This includes both observable and virtual photon interactions.

As a recapitulation: Mass *m* does not exist in time, since it is an observable and observation is the imposition of d/*dt* upon spacetime LLLT, removing the T to give a "frozen LLL snapshot." In short, mass m is an *effect* (of the iterative very high speed observation process), not a *cause* (which is an *input* to the observation process). This is why all observation is 3-spatial rather than spatiotemporal: it yields the 3-space *effect* (at a given time, of a given interaction), not the 4-space cause of the interaction and not the ongoing 4-space interaction.

---

[290] Note the relationship with such things as time dilation, which represents a broken time-flow symmetry, where net energy flow from the time domain to the 3-space domain occurs. Hence time dilation is associated with the increase of spatial energy, such as kinetic energy due to the relativistic velocity of the moving object.

[291] In this book, we have limited our discussion to four dimensions. If we model in five or more dimensions, then additional symmetries and broken symmetries **are** possible, as are new kinds of multi-dimensional EM waves.

By absorbing and emitting photons, observed mass m may be said to move through time in a succession of $m \Rightarrow mt \Rightarrow m \Rightarrow mt \Rightarrow m$ ... jumps, each involving change of physical state as a photon is absorbed by m, changing it to mt which is nonobservable. Then a photon is re-emitted by mt, changing it back to m and completing another observation with this new m as the output (effect). We note that masstime mt is as different in nature from mass m, as impulse Ft is from force F. In mass m, every tiniest differential dm is also interacting with photons continuously (even though they may be *virtual* photons), hence dm also exhibits its own "digital flow through time" as a part of the structure of the overall flow of the parent mass through time.

Interaction primarily with the mt state yields wavelike interactions. Interaction primarily with the m state yields particle-like interactions. This is proposed as a possible resolution of the wave-particle duality problem, which has never been resolved but just accepted without further argument. Previous consideration of wave-particle duality has assumed that "mass has two states, one particulate and the other wavelike". We correct that assumption by pointing out that two different "states in which mass exists" are involved, and the two are quite different: one is mass m, and the other is masstime mt. We stress the function of the myriads of virtual photon interactions during an mt state, where an observable photon has not yet been re-emitted. These virtual photon reactions create streams of virtual $dm \Rightarrow (dm)dt \Rightarrow dm \Rightarrow (dm)dt \Rightarrow \ldots$ on all the differential parts of mass m, which creates the rich structuring inside the "time-flow" of the overall observable mass m through time. The rich dynamics of the $dm \rightarrow (dm)dt$ streams also accounts for the seeming existence of mass m as a set of 4-dynamics which interpret as a set of waves. We note that the emitted photon carries with it the internal structuring of the spatial energy domain and the time-energy domain. Herein we have the basis for the Kaznacheyev's demonstrated electromagnetic induction of cellular damage and disease at a distance.[292]

Finally, we tentatively assume that, prior to its interaction, the antiphoton carries negative spatial energy and positive time increments, while the photon carries positive spatial energy and positive time increments. In a very small region where an excess of antiphoton interactions occurs temporarily, time-reversal occurs and the physics "runs backward". It has recently been experimentally proven that such "reversing" of the physics processes occurs up to micron size and for times up to two seconds. [293]

---

[292] Vlail Kaznacheyev and L. P. Mikhailova, *Ultraweak Radiation in Intercellular Interactions,* [in Russian|, Novosibirsk, 1981.

10.3 Time-Polarized EM Waves and Longitudinal EM Waves

10.3.1 Waves, Photons, Spacetime Curvature, and Observation

Spacetime (ST) curvature involves not only the change of *spatial* energy density of local spacetime but also a change of its *time-energy* density. That component of the total ST curvature due to time-energy density change — i.e., time-polarized EM photons and waves — can be far more powerful, because of the enormous energy density of the time-energy compared to the far lies dense 3-spatial energy. As previously stated, time may be regarded as having the same energy density as mass, except that the highly compressed 3-spatial energy is moved to the 4th Minkowski axis to constitute "time" rather than being left in 3-space to constitute "mass".

Hence ST curvature can be made very powerful when one uses longitudinal phase conjugate EM *wavepairs,* as shown by Whittaker {600} in 1903 with slightly corrected interpretation as argued by the present author {615}. Each longitudinal EM wave in 3-space is accompanied by a precisely coupled time-polarized (scalar) EM wave in the time domain, which latter wave is a longitudinal EM wave on the fourth Minkowski axis involving changes in the t variable in the axis *-ict.* We previously discussed the giant negentropy that this represents with respect to the source dipole. At various times in the past, we have emphasized the time-domain aspects of the coupled phase conjugate longitudinal EM wave-pair by calling such a coupled wave by terms such as *time-density EM waves, time-polarized EM waves,* etc. These terms imply additionally altering and structuring the *time density* and *time-energy density* of spacetime rather than merely altering and structuring its *3-spatial energy density.* Such time-density induced ST curvatures may be nearly 10^{17} times stronger than ordinary spatial energy density ST curvatures {601}.

Interestingly, at least one researcher — Matsumoto {602} — has realized the basic implication in cold fusion processes of using the strong EM force as the agent of spacetime curvature. He has shown consistency of the postulated EM-induced ST curvature approach with some important cold fusion results. However, Matsumoto has utilized the conventional interpretation of spacetime curvature due to alteration of *3-spatial energy density* of spacetime. This misses the primary time-density functions, but does include the resulting spatial-energy functions after transduction from time-energy to spatial-energy. His work, however, does support the involvement of a more intense form of energy in the cold fusion effects.

---

[293] See footnotes 287, 288, and 289.

There are intriguing but still mysterious relationships to be noted between cold fusion and deep astrophysical mechanisms. Continuing reference is made to these similarities, including black holes and white holes. Black holes and white holes involve spacetime curvatures — extreme, but still spacetime curvatures. So one would suspect that the entire scale of spacetime curvature — including black holes and white holes in the limit — should be of interest to cold fusion researchers, since in their use of time energy they are inadvertently involving more intense forms of energy than ordinary spatial EM energy.

Most nuclear scientists and even some relativists seem unaware of the much more powerful spacetime curvature effects obtained by alteration of the *time density* of spacetime rather than just its *spatial energy* density. Physicists have largely omitted specializing on time density ST curvatures because they have largely omitted the absorption and emission interactions of the time components transported by photons and EM waves.

Longitudinal EM phase conjugate wavepairs (each wavepair a coupling of a time-polarized EM wave and a longitudinal 3-space EM wave) of the type shown by Whittaker {600} in 1903 involve net *time density oscillations* as well as 3-spatial energy density oscillations, according to our reinterpretation. The infolded "inner EM content" of all conventional EM potentials, fields, and waves thus contains extraordinary dense time-energy, normally lost in the *d/dt* observation interaction.

In short, the infolded "internal Whittaker electrodynamics is a pure "general relativistic electrodynamics" and a unified field dynamics. Further, it can be engineered, which leads to startling new physical processes previously thought to be impossible and forbidden by the laws of nature.

Prior to observation, the internal highly compressed time-energy structures associated with the interior EM structure of all conventional EM potentials, fields, and waves are extremely powerful spacetime curvatures.

In short, all "conventional" electrodynamics has an internal structure of strong spacetime curvatures and dynamics.

Organization and patterning impressed on, or inserted in, this internal structuring can provide extraordinary actions in materials, living biological systems, cells, etc. Adding deterministic structuring inside these normal EM entities is referred to by Russian energetics weapon scientists as engineering the *information content ofthe field.* This is the approach behind deliberate engineering of *spacetime curvature engines,* or vacuum engines — or just "engines" for short.

In theory, any physical change to a mass can be engineered by inserting such "engines" into the mass. Any mass-energy is a mass-energy EM potential with an internal structuring (engine) for all the mass's internal dynamics. This engine is referred to as the *resident engine* of that mass (and all its dynamics). Introducing to a given mass a potential with a desired "delta engine" structure, results in the superposition of the two potentials, resulting in exchange sharing of the engines. In that manner, a desired "delta engine" diffuses into the mass's potential structure and its resident engine, changing it to a new resident engine which now acts on the mass at every level to change it. Potentials superpose, and their engines diffuse and superpose as well. Direct engineering of matter — even inside the nuclei and inside the nucleons themselves — can be performed by introducing the desired engine or engines for the changes desired.

This area has been highly weaponized by one or more nations. E.g., the Russians — in several decades of so-called "microwave radiation of the U.S. Embassy in Moscow — induced health changes and diseases in U.S. personnel in the Embassy by inducing deliberate "disease engines". Such EM-induced diseases and health changes were generated in the zones where the potentials were field-free, and therefore stable for stable engine diffusion.

Note that the common scalar potential decomposes by Whittaker's 1903 decomposition {600} into the longitudinal EM wavepairs we are speaking of. Also note that, per a second paper by Whittaker in 1904 {91b} that initiated superpotential theory, all EM fields and waves can be decomposed into two scalar potential functions. Each of those base potentials involved in the potential functions further decomposes by Whittaker 1903 into a harmonic set of phase conjugate longitudinal EM wavepairs as previously discussed. Therefore, the infolded EM inside all the "conventional" EM fields, waves and potentials is indeed a highly organized set of such bidirectional longitudinal EM wavepairs and thus a highly organized set of extreme localized ST curvatures. In other words, it is comprised of these special "engines" of deterministic spacetime curvatures and their dynamics.

Constructing the potential by assembling one's own set of phase conjugate longitudinal EM wavepairs to form it, one can insert any kind of ST curvature set — any kind of vacuum engine desired — inside the base potential(s), hence inside the two potential functions comprising a given set of EM fields and waves utilized as "carriers". The specific internal structure of a "carrier" radiation field or potential designed to carry such engines is called the "information content of the field".[294] The Russians have long had a disinformation campaign to suggest that the term refers to conventional spectral analysis. It does not.

Johns Hopkins scientists did detailed measurements inside the Embassy and confirmed that all the anomalous health changes and diseases had occurred only in areas where the EM fields B and E were absent. That is, the health changes occurred only where the potentials were field-free and therefore stable and unchanging, so that an exposed body was immersed in a steady sea of "vacuum engines" being diffused throughout the targeted body's EM potentials in and on its cells, its cellular membranes, etc.

In general relativistic terms, every physical set of changes and altered dynamics (syndrome) of a specific disease has a specific *delta* set of spacetime curvatures and dynamics associated with it, which interacts on the body, its chemistry, its electrodynamics, its cells, etc. A desired set of

---

[294] Indeed, in theory one can *construct, functioning robotic systems* of these internal engines. In clandestine Russian weapon research, it appears that at least elementary "causal robots" of such internal engine type have been developed and tested. In a sense, these are the ultimate "nanobots" made of infolded longitudinal EM waves and their dynamics. In theory, command and control functions (via longitudinal EM wave communication) can be included, as can certain kinds of weapons effects based on scalar interferometry. The eventual development of such startling weapons seems intended to produce an army of eerie "internal EM" robots which can be "sent in'" *through the interior of EM fields, waves, and potentials,* to targets anywhere on earth, beneath its surface, in space, or beneath the ocean. This may be intended to become the ultimate robot or "high tech" warfare, and it is also the ultimate "information" warfare. There are no shields against this type weaponry. Defense, however, is accomplished by first using longitudinal wave "scanning" to pick up and track the systems, much like radar picking up aircraft. Once detected, scalar interferometry is utilized to disrupt and destroy them in place. Progress on these robotic weapon systems appears to be well along, as does progress on their countering longitudinal EM wave weapons.

ST curvature deltas for a given disease was inserted inside the base potentials in a combined Whittaker 1903 and 1904 decomposition of the stable field-free potentials in the Embassy. The Russians thus induced the desired engines for induction of the specifically desired disease(s) in the assigned personnel in those field-free potential zones in the Embassy. The purpose was to use the tests as (i) a guaranteed means to provoke high level U.S. governmental attention, and (ii) a probe to see if the U.S. knew about such technology and had developed defenses. Other tests of such disease induction in entire populations have also been conducted, but these are beyond the scope of this book.

We point out one very important thing: the cells of the body have their normal "resident engines" and resident engine dynamics inside their internal fields and potentials and waves. For any specific disease or disorder condition, there exists a specific associated change (delta) in the normal set of vacuum engines and their dynamics, in the cells and the body. In short, there exists a specific "delta engine" for any cellular disease or disorder, added to the normal engine.

It is not the immune system that heals. Instead, it is the cellular regenerative system. The natural healing method used by the cellular regenerative system is not chemical. The regenerative system uses the phase conjugate wavepair composition of increased scalar potentials (on cellular membranes and every part of the cell) to "pump" the cells in the time-domain. This creates an "anti-engine" for the specific disease delta or disorder, and it slightly amplifies this anti-engine within the limited capabilities of the body. This action places this amplified anti-engine also into the stricken cells' engine complex. Engines superpose, just as do potentials. This action by the regenerative system has the effect of slowly producing complex anti-forces in the body and inside the cells themselves, eliminating the detrimental engine delta, restoring the normal resident engine and thus time-reversing the stricken cells back to a previous healthy condition. It does not kill pathogens at all; that is the function of the immune system. In the 1960s and early 1970s, Antoine Priore in France demonstrated remarkable cures of terminal tumors, infectious diseases, clogged arteries, and other disorders in laboratory animals,[295] unwittingly amplifying the body's own master regenerative mechanism. His work was suppressed in the mid-70s.

---

[295] See (a) A. Priore, *Guerison de la Trypanosomiase Experimental Aigue et Chronique par L 'action Combinee de Champs Magnetiques et D 'Ondes Electromagnetiques Modules* [Healing of intense and chronic experimental trypanosomiasis by the combined action of magnetic fields and modulated electromagnetic waves], Priore's thesis submitted in candidacy for the doctoral degree, 1973. The thesis was rejected when the project was suppressed. See also (b)

Check our website, www.cheniere.org, for a 119-slide "porthole" briefing on the present author's extension whereby specialized mixes of ordinary EM waves can be used to initiate and perform this "delta engine elimination" healing process, and it can be highly amplified well beyond the body's normal healing capabilities.

In 1998 we seriously proposed to the DoD, the USAF, the NIH, and other U.S. government institutions that a crash development program be initiated to develop portable units capable of rapidly (5 minutes per patient) treating mass casualties from coming terrorist attacks with weapons of mass destruction such as anthrax, smallpox, bubonic plague, Ebola virus, etc. Sadly, no one in the U.S. government had the foggiest notion of what we

---

"Le Probleme Priore," *Rapport de la Commission de 1'Academie des Sciences a Monsieur le Ministre d'Etat charge de la Recherche et de la Technologie,* 1982, p. 1-22; (c) Antoine Priore, "Precede et dispositif de production de rayonnements utilisables notamment pour le traitement de cellules vivantes," [Procedure and Assemblage for Production of Radiation Especially Serviceable for the Treatment of Living Cells], Republique Francais Brevet d'Invention P.V. No. 899.414, No. 1,342,772, Oct. 7, 1963; (d) Antoine Priore, "Method of producing radiations for penetrating living cells," U.S. Patent No. 3,280,816, Oct. 25, 1966; (e) Antoine Priore, "Apparatus for producing radiations penetrating living cells," U.S. Patent No. 3,368,155, Feb. 6, 1968; (f) A. J. Berteaud and A. M. Bottreau, "Analyse des rayonnements electromagnetiques emis par l'appareil Priore," [Analysis of the electromagnetic radiations emitted by the Priore apparatus], D.R.M.E., 1971, p. 3-12.; (g) R. Courrier, "Expose par M. le Professeur R. Courrier, Secretaire Perpetuel **de** L'Academie des Sciences fait au cours d'une reunion a LTnstitut sur les effets de la Machine de M. A. Priore le 26 Avril 1977," [Presentation by Professeur R. Courrier, Perpetual Secretary of the Academy of Sciences, made at the meeting of **the** Academy on the effects of the machine of M. A. Priore]; (h) R. Pautrizel, A. Priore, M. Dallochio and R. Crockett. (1972) "Action d'ondes electromagnetiques el de champs magnetiques sur les modifications lipidiques chez le Lapin par l'administration d'un regime alimentaire hypercholestrole." [Action of electromagnetic waves and magnetic fields on provoked lipidic modifications in the **rabbit** by the administration of an alimentary hypercholesterol diet.] *Compt. Rend. Acad. Sci. (Paris),* Vol. 274, 1972, p. 488-491. The same university that rejected Priore"s doctoral thesis in 1973, accepted a doctoral thesis on the same subject some 11 years later due to the persistence of Pautrizel: See (i) Eric Perisse, *Effets des Ondes Electromagnetiques et des Champs Magnetiques sur le Cancer et la Trypanosomiase Experimentale [Effects of Electromagnetic Waves and Magnetic* ***fields*** *on Cancer and Experimental Trypanosomias],* Doctoral thesis, University of **Bordeaux** No. 83, March 16, 1984.

were discussing. At NIH, we never got out of their "policy" (i.e., "spin control") department. Not a single capable scientist reviewed the extensive package. The attack on the World Trade Center and the Pentagon on Sept. 11, 2001 is just a forerunner of that which is to come. We could have been prepared to save hundreds of thousands of Americans, even millions. We shall not be ready, and the first really professional anthrax or smallpox (or camel pox, which is easily available and almost exactly the same as smallpox) attack on a major U.S. population center may leave from one to three million Americans dying in the streets and in their homes. Presently nothing will save them. It could have been different.

10.3.2 Photons and Waves in Minkowski Spacetime

Photons are made of angular momentum (action); i.e., of *energy x time.* Waves, being made of photons, carry both spatial (decompressed) energy and time (highly compressed) energy — although physics has largely omitted the *time-energy-carrying* aspect, and only accounted for the *spatial energy-carrying* aspects. An EM wave in space is actually a wave of the particular spacetime curvatures that produce angular momenta in interacting charged masses. The standard notion of E and B fields at right angles in a plane in 3-space, traveling along the *z*- direction and with the plane orthogonal to *z*-, and with E and B field vectors oscillating back and forth, is nonsense, as acidly commented upon by Romer {603}, the former editor of *American Journal of Physics.*

Nonetheless, using the standard way of modeling the "transverse" EM wave: In conventional electrodynamics, a *transverse EM wave* is one where the 3-spatial energy density is considered to be varying rhythmically at right angles to the direction of wave propagation, and the time-density is assumed to be non-varying, or at least altered only by special relativistic considerations in certain cases.[296] A longitudinal EM wave has its spatial energy density fixed in *x*- and *y*- directions, and its energy density is oscillating along *z*-, the direction of wave propagation, by a "compression" and "rarefaction" process much like squeezing an accordion. This, however, leads to a "galloping" motion where the wave is alternately very superluminal and very subluminal at given instants, but moving at an *average* velocity of *c* {604}. On the other hand, a *time-density (scalar) EM wave* by definition is not varying in its 3-spatial energy density, and therefore is not varying in *x-, y-*, or *z-*. Instead, the energy is in the form of time-energy, and its variation is in time density. So its energy density is oscillating along the fourth Minkowski axis, *ict,* as an oscillation of the energy density of the variable *t.* It is therefore polarized in the t- direction.

---

[296] We point out that a wave of varying spatial energy density is moving in a varying curved ST a priori, by general relativity. If the "wave" were in a flat spacetime as normally assumed, the EM flat spacetime would eliminate the EM wave itself. **This** has been particularly pointed out by Sachs and by Evans.

10.3.3 Time-Charging, Internal Structuring, Vacuum Engines, and Diffusion

Photon interaction as a *spatial* energy collection or energy exchange process is well known in physics. However, the time-charging or time-excitation interaction between the mass and the time component carried by the photon is usually ignored.

As is well known, an atomic electron that absorbs a transverse photon increases its spatial energy and changes into an excited spatial energy state. When the electron subsequently "decays" from that excited energy state to a lower state, the spatial energy differential between the two states is emitted as the spatial energy component of an emitted photon. This is the *spatial energy density* reaction of a transverse photon with an absorbing and emitting mass particle.

Unaccounted for by physics, at the time of the energetic excitation of the mass (i.e., when the photon is absorbed), a time excitation — time charging — also occurred because the time-component of the absorbed photon is also attached to the mass, converting it to *masstime,* a new entity. Re-emission of the photon is accomplished by the decay of both the *spatial energy* excitation and the *time-energy* excitation. In the previously excited state after photon absorption, however, one did not have the entity "mass", but the entity *masstime* having greater topology. If mass is an observable and taken to be 3-spatial (as is conventional), then photon absorption and emission oscillates between 3-space and 4-space effects, generating both spatial energy and time-energy (or *angular momentum)* excitation and decay.

Further, only *masstime* emits a photon. This immediately casts a very different light on such things as radioactive elements, which are in an initially excited state. Discussion of this aspect, however, is beyond the scope of this treatise.

On the other hand, a *scalar (time-density)* photon {605, 606} has a rather different interaction, regardless of how physics presently treats it. Any atomic electron at any energy level is continually receiving and emitting virtual photons - transverse, longitudinal, and scalar- in its virtual photon exchange with the energetic vacuum. Hence it is continually "connecting to" or "absorbing" time components, thereby changing its nature from mass to masstime, back to mass, back to masstime, etc. Not only the entire electron but also each differential piece of it is performing that dance between mass and masstime. This is a continual changing from 3-space to 4-space and back. There thus is a violent "chatter" of the electron (and each differential piece of it) in the myriad levels of its *time* exchanges, giving it

(i) An average rate of time component exchange,

(ii) An average "time-charge", and

(iii) A dynamically changing, specific structuring of its time components.

Whenever a mass absorbs an observable photon, the mass converts to masstime, with an "extension in time" as well as extension in 3-space. During the time-interval created in the masstime, myriads of virtual photons are absorbed and emitted by that mass component of the masstime entity. Hence every dt portion of the masstime state after observable photon absorption, is "internally structured" by the entire virtual photon interaction set's At's occurring within that time interval.

By tailoring at least the larger elements of this internal structuring of the masstime state's virtual photon bombardment, by a deliberately induced virtual photon bombardment, the emitted photon from the masstime decay will carry away with it a desired internal "vacuum engine" structure of organized curvatures of spacetime. In short, two potentials superpose; that is one of their primary features. When they superpose, they also diffuse their internal structures (internal vacuum engines) into each other.

We speak of the *diffusion ofa specific vacuum engine* placed in one interacting EM potential, field, and or wave as *dimensioning* the potential, field, or wave. Adding a dimensioned potential, field, or wave to other potential(s), field(s), or wave(s) diffuses the dimensioning (the engines) between all of the participating entities. With steady radiation of such dimensioned signals into a targeted object, field, wave, or potential, the dimensioning is gradually created (kindled) in the target, simply diffusing throughout it and gradually accumulating. If the irradiating signal carries a specific disease — e.g., necrotizing fasciitis — then gradually in the irradiated body there will emerge all the symptoms of necrotizing fasciitis. If the irradiating signal carries a specific disease antiengine — e.g., for necrotizing fasciitis — then gradually the necrotizing fasciitis condition will be eliminated, with the disease organisms also being eliminated.

This is a more fundamental extension of the disease vector concept. Not only can a disease vector be induced by a physical organism such as a virus or bacterium, but it can also be introduced by simply capturing the fundamental vacuum engine pattern of the disease and using it to condition or dimension signals used to steadily irradiate the targets.

This is the explanation of the Kaznacheyev experiments {607}: thousands of experiments performed by Vlail Kaznacheyev and his colleagues demonstrated the induction of almost any kind of remote specific cellular death and disease patterns in targeted cells, by absorption of radiation emitted from appropriate dying or diseased "emitter" cells with that condition, if the experiments were performed in the dark.

Instead of looking for biogenesis causes in amino acid precursors to cellular life in meteorites etc., one might well look into the *vacuum engine structures* inside the light from the sun, the planets, the stars, and the universe in general. E.g., dead sperm can often fertilize female cells, if not too much physical damage and deterioration to the dead sperm cells has yet occurred. This is understandable, since for a time a dead but undamaged sperm cell will have the same resident engine as a living sperm cell.

10.3.4 Some Cosmological and Gravitational Effects

Each of the observable-sized dt's in all the serial masstimc excited states of the mass moving through time, is internally and precisely structured. The precise time history of any mass — together with all its interactions, experiences, etc. — is present inside the time stream of ongoing interactions of that mass with photons. These virtual photon changes are in fact deterministic and come from every part of the universe, as shown by Puthoff {608} in his self-regenerative cosmological feedback cycle. We have merely extended his cosmological feedback to include the time domain as well as the energy domain. We hypothesize without further discussion that this internal structuring of the time-domain for every mass or object will eventually be connected with the quantum concept of the geometric phase {609}.

When a transverse photon interacts with a mass in the presence of other photon interactions, the mass can act as a phase conjugate mirror and form the phase conjugate replica photon (an antiphoton). For a longitudinal photon, the antiphoton *prior to observation* is a scalar photon. We propose that in the unobserved causal state the photon and antiphoton can couple (strong interpretation of the distortion correction theorem) and form a spin-2 graviton. According to quantum field theory, one may already interpret the common scalar potential as being comprised of such spin-2 gravitons {610, 611} if we speak of the situation prior to observation.

As opposed to the accounted *spatial energy charging* of the familiar transverse photon interaction, the longitudinal photon interacting with mass will cause immediate phase conjugation by the mass because of the accompanying scalar photon (accompanying antiphoton prior to observation). When one pumps with longitudinal EM waves, one also inadvertently pumps with time-polarizcd EM waves simultaneously.

From its background "time-energy pumping" in its vacuum exchange, the mass forms the phase conjugate replica, which couples to the incident longitudinal EM photon. This forms (wave view) bidirectional longitudinal EM wavepairs (conjugate pairs), comprised of (particle view) internal coupled longitudinal photon-antiphoton pairs. Each of those internal photon-antiphoton pairs is a spin-2 graviton.

Each such conjugate longitudinal wavepair actually contains a time-density (time-polarized) or scalar EM wave. So the interaction of LWs and their accompanying scalar waves immediately initiates the formation of time-density waves, which then primarily perform a *time-charging* interaction. In addition, even for an equilibrium time-charging state, the "masstime" state of the interacting electron contains a specific structure of the time elements in the electron-time's time component. Each of these infolded time elements is also time-charging the electron.

10.3.5 Charging and Excitation Considerations For Cold Fusion Purposes

So there are several new types of charge or excitation that are involved in cold fusion and other phenomena. One may speak of charging and excitation such as gravitational charging, time charging, time-energy excitation, time-energy charging, etc.

Both the longitudinal photon and the scalar (time-polarized) photon are in fact known in physics, but usually neglected, at least at the end of calculations. E.g., Gray {612} puts it this way about the four kinds of photon polarizations and the habitual elimination of the higher ones:

> *All that quantum theory can say is that there are two transverse photons, a longitudinal photon and a scalar photon. It must be decided by other means which are "desirable" states and then it is customary to "eliminate" the longitudinal and scalar photons by invoking a*

> *subsidiary condition, now somewhat weakened from the Dirac form.*

For our purpose in examining the cold fusion experiments, there exists a completely unsuspected "time-charge" set of excited states for an atomic electron, a proton (as in an H+ ion), etc.[297] There also exists a "time-structuring" of the time-charge excited time-state, which we will see is important in certain highly anomalous instrument phenomena. Uncovering this time-charging and time-structuring interaction has been one of the major results of this author's long effort to decipher the functioning of the healing (cellular regeneration) system of the body as well as his efforts to decipher the fundamental nuclear transmutation mechanism in cold fusion transmutation interactions at feeble *spatial* energy.

In summary: For longitudinal photon interaction, the atomic electron "absorbs" the longitudinal photon and its accompanying scalar photon, being simultaneously spatial-energy excited (charged) by the longitudinal photon and time-energy excited (time-charged) by the scalar photon. This time-excited state (of masstime) then subsequently decays, emitting a longitudinal photon accompanied by a scalar photon in the process.

---

[297] See again footnotes 287, 288, and 289. From our mechanism propelling a mass through time, time-charging and discharging play the causal role. The acquisition of dt by mass *m* produces masstime *mt,* then the subsequent photon emission decay of *mt* back to *m* produces "propagation of mass *m* forward through time" by one "jump". Time charging with -dt and subsequent photon emission is what produces "propagation of mass m backwards through time" by one "jump". Evans et al. proved that even up to the micron scale physical particles and their dynamics can run backwards in time for up to two seconds or more. The fluctuation theorem proved by Evans and his colleagues in 1993 shows us that, at the scale of a proton and neutron, there can become a high probability of significant time reversal of the physical dynamics. This means that the law of attraction and repulsion of charged particles -such as two H+ ions in solution — "runs backwards" or is reversed, so that momentarily like charges attract and unlike charges repel. We have called the region in which this reversing of the physics occurs a *time reversal zone* (TRZ). With the reccentwork of Evans et al., the existence and occurrence of TRZs even well above the proton (the H+ ion) level is now clearly established, including the reversing of the physical dynamics. These concepts have not yet been applied to cold fusion interaction results by the leading cold fusion researchers, but they now stand as explaining the most probable mechanism for the observed phenomena. In this Chapter we have written some of the typical new nuclear reactions that can occur in such a TRZ, and the exact products of these reactions are widely reported in several hundred successful cold fusion experiments.

We shall return to time-charging and time-charge decay when we examine and explain the odd instrumental anomalies experienced for some time in experiments at China Lake.

10.4 Time Reversal Zone and New Nuclear Reaction Mechanisms

It follows that the flow of a mass through positive time must involve a preponderance of reactions with photons rather than antiphotons, since *net* absorption and re-emission of photons (rather than antiphotons) is involved. Otherwise, the absorbing and emitting mass would not accomplish little "jumps" forward in positive time.

Suppose we deliberately arrange a situation where the target mass is interacting with a preponderance of antiphotons. In this case, the mass will be time-reversed, as will be the EM energetics.[298] This leads us to the novel concept of a *time reversal zone* just described in footnote.

A time-reversal zone (TRZ) is a region of space, or electrolyte, etc. in which given masses or charges of interest are interacting on the average with more antiphotons than photons. Consequently, in the TRZ the usual EM energetics are reversed and normal charge reactions appear to "run backwards" insofar as the spatial 3-space observer is concerned.

For example, in electrolytes in a region of highly loaded positive charges in a loading palladium lattice with properly prepared surface, a very great number of double surfaces exist. Hence a great number of scalar interferometries continually occur from that large number of double surfaces acting as scalar interferometers {613}. Because of the highly excess positive charge loading, these interferometers are predominately fed by negative EM energy from the positive charges. Hence, in the distant interference areas in the electrolyte outside the palladium lattice, some negative energy fields and negative energy potentials are produced dominantly. An excess of antiphotons is produced in those interference zones where an excess of antiphotons appear due to the scalar interferometry. In *those* little interference zones, the simple positive ions are momentarily bathed in an excess of antiphoton interactions. This is therefore a time-reversal zone of momentary time-reversed EM energy flow.

---

[298] This *is not* time-travel in the classical science fiction sense. For time-travel, the traveling object must remain moving in its own forward time, while the entire remainder of the universe must be reversed in its time and must move backward in time to a past coordinate. That is not what is happening here, and no one is suggesting we can time-reverse the rest of the universe! Instead, energy can be reversed in time, as proven in nonlinear phase conjugate optics. So can mass-energy and charge-energy, as shown by the Dirac theory of the electron. An *observed* positron is an electron observed while traveling backwards in time, so to speak, with respect to the observer. But it is observed in observer forward time as traveling in the opposite spatial direction, having positive mass and positive energy, and with the sign of its charge reversed from negative to positive.

From a palladium lattice loaded with H+ or D+ ions, and also having a proper surface with many work grooves and thus many small interferometers, random fluctuations in the scalar interferometry occur in the adjacent electrolyte. Some of these random scalar interferometries continually form fleeting time reversal zones (TRZs) in their interference zones in the surrounding electrolyte. The very large energy required for the formation of each TRZ and its reversal of the normal laws of attraction and repulsion of charges, is available from conversion of time energy from the time domain as a result of the giant negentropy mechanism in 4-space ongoing in the loaded positive charges (614, 615} in the palladium lattice.


COULOMB BARRIER
H+
H+
STRONG FORCE (ATTRACTIVE) REGION
COULOMB FORCE (REPULSION) REGION
• COULOMB REPULSION FORCE REVERSES INTO A COULOMB ATTRACTION FORCE
• STRONG FORCE SHRINKS IN RADIUS
COULOMB ATTRACTOR
H+
H+
STRONG FORCE (REPULSION) REGION
COULOMB FORCE (ATTRACTIVE) REGION

10-1a. Normal time-forward zone.

10-1b. Time reversal zone.

Figure 10-1 Forces on nuclei of simple ions in time-forward and time-reversal zones.

See Figure 10-1. In Figure 10-la, two hydrogen ions (two free H+ protons) in a normal electrolyte and in a normal time-forward zone are shown. The

Coulomb barrier dramatically increases the forces of repulsion between the two H+ ions as their kinetic energy may be driving them momentarily toward each other. This Coulomb barrier becomes so strong that it stops the approach of the two ions and forces them back apart, or to deviate aside from their paths, before each can ever enter the very short-ranged strong force region of the other. Consequently no nuclear reaction occurs, but only a common chemical reaction. The maintenance of that Coulomb barrier is all that prevents energetic ions from being driven together closely enough to engage the strong force and cause the ions to form a new nucleus (cause a transmutation).

Now see Figure 10-lb, for the same two ions that suddenly find themselves in a momentary time-reversal zone (TRZ). In a temporary TRZ, suddenly like charges attract and unlike charges repel, exactly in reverse of the *normal* behavior of charge attraction and repulsion. The usually increasing Coulomb barrier (repulsive force between the two approaching H+ ions) has disappeared and been replaced by an increasing Coulomb attractor (attraction force). Further, the strong force has been partially reversed and much weakened since the gluon forces are dramatically reduced and fluctuating.[299] The attractive strong force is now a partially *repulsive* force and so it is much weaker. Consequently, the quarks in a proton or neutron are not nearly so strongly bound as they are in a normal time-forward zone (TFZ).

A TRZ represents a highly time-charged excited local state in that local region of the electrolyte. The moment a TRZ is formed, the surrounding ions in the electrolyte outside the TRZ immediately move or deviate their movements to reverse this TRZ action[300] and convert it back to a time-forward zone (TFZ). Hence once it is born in the electrolyte, the TRZ decays rapidly due surrounding ion movement changes, and even more rapidly due to the rapid variation in the fluctuating scalar interferometers in the loaded palladium lattice. In most cases, the random fluctuation in the scalar interferometry is so rapid that the TRZ decays back to a normal TFZ before the two approaching H+ ions can reach each other (reach each other's reduced strong force repulsion region). However, in a certain percentage of approaches, the two approaching like-charged ions will "reach each other" — i.e., each will enter the weakened strong force region of the other before decay of the TRZ occurs.

---

[299] Again we stress the tremendous energy density of the time-energy involved. These cold fusion interactions are actually higher *total* energy reactions than nuclear physics presently uses, even though the *spatial* energy density of the reactions is very small. Together with the now-proven fluctuation theorem of Evans et al., the TRZs and reversal of the normal Coulomb barrier into a Coulomb attractor open up a vast new nuclear chemistry of direct nuclear transmutation reactions at low spatial energy but at very high tempic energy. The ability to directly engineer the quarks and the gluon forces, e.g., opens up a new chemistry of direct subparticle engineering heretofore considered quite impossible by chemical means.

[300] Their approach increases the fraction of photon reactions relative to antiphoton reactions, since the other ions are moving in a TFZ on the average.

See Figure 10-2. In Figure 10-2a, we show the case in which the TRZ lasts long enough for the two H+ ions to reach each other's strong force repulsion zones and form a quasi-nucleus. Here they vibrate back and forth in a dynamic dance around the zero net force axis between their repulsive strong forces and their attractive Coulomb forces. In this case, a new kind of nuclear reaction is set up to occur. Decay from this excited quasi-nucleus state in a TRZ can occur into a real nucleus in a normal TFZ. Energetically, because the quarks are so loosely bound now[301] the preferred decay mechanism when TRZ -> TFZ is by appropriate *quark flipping.*

As a little bit more time passes, the interferometry changes and the TRZ decays, returning back to a normal TFZ. In a change from TRZ to TFZ, the energy change is enormous because time-energy is involved, with energy density equal to mass. The only difference in a proton and a neutron is the orientation of one quark (three quarks make up each of the particles). As TRZ decay starts and progresses, the strong force changes back to a powerful attractive force. It increases its strength far more powerfully and quickly than the Coulomb attractive force reduces its reversal and changes back to a repulsive force. The addition of the extra energy from the now-increasing strong attraction force simply causes one nearly-freed quark in one of the two H+ ions to flip, converting that H+ ion into a neutron n. Instantly the preferred decay product is the deuterium ion D+. So the H+ and the n simply draw a bit closer together, each now fully inside the rapidly increasing attractive strong force region of the other. This converts what had been a quasi-nucleus of two H+ ions into a real D+ nucleus. This result is shown in Figure 10-2b.

---

[301] To appreciate the sheer raw power of the time-energy control of interactions, simply examine the enormous *spatial* energy density required in high energy physics to try to approach the "free quark" condition. Enormous and very expensive *spatial energy* accelerators are used, at the absolute state of the art. By going to the use of the extraordinarily dense time-energy, quarks can readily be freed or nearly freed in electrolytes, and they are nearly freed in more than 600 relatively simple and inexpensive cold fusion experiments {753) on the bench-top to allow new nuclear reactions by quark flipping, where a proton turns into a neutron or vice versa.


ZERO-FORCE AXIS
(Equal attraction
and repulsion)
DECAYS TO
D+
Nucleus
Quasi-nucleus
H+
H+
A QUARK
FLIPS
H+
n
REDUCED STRONG
FORCE
(REPULSION)
REGION
COULOMB
FORCE
(ATTRACTIVE)
REGION
AS TRZ DECAYS,
AND RETURNS TO
NORMAL TFZ:
NORMAL STRONG
FORCE
(ATRRACTION)
REGION
COULOMB
FORCE
(REPULSIVE
REGION

10-2a. Ions move to form a quasi-nucleus.

10-2b. Quasi-nucleus decays by quark flipping into a new nucleus.

Figure 10-2. Production of quasi-nucleus and its decay by quark-flipping into a new nucleus as the time-reversal zone decays back to a time-forward zone.

Recapitulating: As the TRZ subsequently decays back to a normal time-forward zone (TFZ), the new quasi-nucleus becomes an excited state, and decays. However, the quasi-nucleus decays by very novel means. Because of the time reversal, the energy changes induced in the decay *start* at each spacetime point inside the quasi-nucleus, deep inside the quarks, and proceed outward. The first interaction of the decay mechanism is with the quarks comprising the nucleons (in this case, the protons). With the gluon forces still very much weakened, quark flipping becomes the preferred decay mechanism. Hence one quark in one proton flips its orientation (that is the mechanism of decay!) and the nucleus — now a nucleus comprised of a proton and a neutron — becomes a nucleus of deuterium.

As can be appreciated, the clustering of different types of like-charged but relatively simple positive ions in TRZs in solution, with subsequent decay of the TRZ into a TFZ, initiates a revolutionary new family of nuclear reactions at low spatial energy (but very high temporal energy), completely contrary to, and not included in, the present forward-time high-spatial energy (but very low time-energy) reactions model known in particle physics.

In the future, as these new time-energy-based reactions are extended and mastered, scientists will simply assemble desired nuclides in solutions in the laboratory, at low spatial energy (but high time-energy) and at will. We point out but do not pursue further the fact that these new reactions also open up cheap, practical, electrochemical means of altering nuclear and chemical wastes. We therefore foresee a dramatic development in this area, in order to clean up the presently polluted biosphere of much of the chemical and nuclear waste contaminants.

Indeed, we propose that a very strong program in mastering these new nuclear reactions be launched and supported by the U.S. Department of Energy, so that the nuclear wastes storage problem can be permanently solved, much more cheaply, and without having to store hazardous nuclear wastes for centuries. Instead of merely *talking* about "out-of-the-box thinking and research", the DoE should actually do some of it, over the violent objections of the entrenched conventionalists of the national laboratories. Their own great national laboratories are the major part of the problem, not the solution, for both innovative nuclear reactions and innovative energy systems! The problem is that "in-the-box" entrenched conventionalists do not perform or allow "out-of-the-box" research that strongly threatens their vested interests.

The TRZ decay conversion of two protons into a deuteron — by easily flipping one quark in one proton — is an example of the so-called "nuclear reaction at low energy" that has been so controversial *to* the orthodox scientific community, even in the face of some 600 successful cold fusion experiments. Contrary to the assumption of the conventional physics community and the skeptics, these are not "low *total* energy" physics reactions at all. Instead, they utilize energy density on a level commensurate with that achieved in the largest accelerators available and even much higher. *This is actually a much higher total energy physics than the present conventional high energy physics heretofore known or used.*

Particularly in a deuterium-enriched (deuterated) electrolyte, a variety of simple ion arrangements of D+ ions and H+ ions can occur. Many of these combinations and arrangements can and will occur in TRZs if sufficient loading of the palladium lattice is achieved. Below we will present and explain a few of these new nuclear reactions that have occurred in successful cold fusion experiments. First, to be tidy we must correct the present statement of the conservation of energy law by extending it to include time-energy.

The excess heat usually experienced in the electrolyte is explained by the added negentropy (added energy) from the time-domain, which then dissipates randomly in the solution, producing excess heating. Later we will cite strong experimental evidence for the involvement of such time charging (time-energy charging), with subsequent time-charge (time-excitation) decay as ordinary photons in cold fusion experiments.

10.5 Revision of the Conservation of Energy Law

10.5.1 Unaccounted Transduction Extends the Conservation of Energy Law

Along with the re-emission of all the previously absorbed spatial energy, all the previously absorbed time-charge of the excited electron may be re-emitted with a longitudinal photon/scalar photon pair (a graviton) when the time-excited state decays. In that case, no energy-charging permanent change results to the electron's original energy state. Hence no "electron wiggle" will be created and our normal "electron wiggle" detectors performing such non-transducing longitudinal EM wave interactions will not exhibit an indication. In short, the "pure" time-charging EM LW interaction is unobservable to present instruments. All they "see" is the "same electron" sitting there and "flowing through time".

However, if two or more such gravitons are simultaneously emitted from various reactions in time-decays, the emitted scalar photons and waves may interfere at some little distance. In that case, transverse EM waves and ordinary EM energy will be produced in the interference zone {613}. To the external observer, these EM fields and forces will simply seem to arise spontaneously and emerge from every point in spacetime inside that interference zone, moving outward from there in conventional "propagation through space" manner. In that case, the normal "photon" (actually, graviton) decay processes plus scalar interferometry have resulted in transducing some time-energy into ordinary spatial EM field energy. Such reaction provides the excess heat demonstrated in successful cold fusion experiments.

This is also a true action at a distance reaction, presently unaccounted in particle physics. Action at a distance is required in quantum mechanics, and it has been experimentally demonstrated multiple times in distant photon correlation experiments. Once any action at a distance is admitted because it has been experimentally proven, there is no logical restriction that only a single mechanism exists for it. Consequently, many of the present foundations assumptions of physics and some of the things previously abandoned because of their conflict with those assumptions will have to be re-examined {616}.

Scalar interferometry is indeed a mechanism for action at a distance. While still mostly absent from open physics, it has already been weaponized by some 10 nations of the world. Indeed, U.S. Secretary of Defense William Cohen confirmed in 1997 that (novel) electromagnetic processes are already being used to initiate earthquakes, stimulate volcanoes into eruption, and engineer and control the weather {617}. Whether or not it is present in the particle physics texts, scalar interferometry is being widely used clandestinely in several armies today. It has also been used to shoot down missiles and aircraft as tests. The so-called "Cold War" was not quite as cold as the news media and U.S. scientific community were led to beleieve.

Because of the ubiquitous involvement of unaccounted time-energy in all photon interactions, an extension to the present form of the conservation of energy law is required. The present (special case) law is

$$E(E)_1 + E(m)_1 = E(E)_2 + E(m)_2 \qquad [1]$$

where E(E) = energy in conventional non-massive energy form, E(m) = energy in mass form, subscript 1 refers to the measurement at time 1, and subscript 2 refers to the measurement at time 2. This is just the well-known Einstein formulation that the sum of the ordinary energy and the mass-energy is conserved.

However, that law is for a special case. It assumes that there is no transduction of time-energy into either mass-energy or ordinary energy. I.e., it assumes 3-symmetry and t-symmetry in EM energy flow. Since every charge in the universe already violates both that 3-symmetry and t-symmetry of energy flow, the fundamental assumption in the Einstein formulation is falsified by the general case. The conventional conservation of energy law is a special case where only the two mentioned energy flow symmetries are upheld. When they are violated, then transduction of EM energy between 3-space and time occurs. For that case, the conservation of energy law must be extended to

$$E(E)_1 + E(m)_1 + E(t)_1 = E(E)_2 + E(m)_2 + E(t)_2 \qquad [2]$$

The **new** law simply states that the sum of the ordinary spatial energy, the **mass-energy,** and the time-energy is conserved. This extension of the conservation of energy law becomes important in successful cold fusion experiments, where transduction of time-energy into ordinary heat energy occurs and where one encounters very anomalous reactions differing from those reactions known and accepted in conventional nuclear physics.

10.5.2 Transduction Between Time-Charging and Spatial Energy-Charging

The oscillating energy (spatial and temporal) in a moving EM wave in the vacuum represents a moving oscillation of spacetime curvature. Simply put, the so-called electromagnetic wave in space is actually a gravitational wave in space, since it is an oscillation of the local energy density of spacetime and therefore an oscillation of the curvature of local spacetime. It "transports" gravitons (scalar photon/longitudinal photon pairs) rather than merely photons. So let us now consider it as a gravitational wave.

In the absorber under special conditions, a small fraction of the graviton wave time-density absorbed will sometimes change (transduce) its time-energy into what we call transverse photon energy effects {618}, with something like a 10^{17} gain in spatial energy in joules compared to the time in seconds that actually transduces. In other words, 1 second of time transducing into EM transverse wave energy (using the standard EM modeling approach) will yield approximately 10^{17} joules of spatial EM energy. Since one can change energy from one form to another, *one can change time-energy into 3-spatial energy* and 3-*spatial energy into time-energy,* the two being merely opposite sides of the same coin, and both always involved in any situation exhibiting electrodynamic dipolarity.

In one's physics model, the choice of fundamental units is purely arbitrary. Everything can be expressed in a single fundamental unit, as pointed out by Jackson (see quotation from Jackson at the beginning of this chapter).

In a situation where 3-symmetry and t-symmetry in EM energy flow are broken, part of the *time charging* of the atomic electrons (or ions) sometimes changes (transduces) into *spatial energy charging* and vice-versa. This cross-dimensional decay of time-excitation states results in the emission of some extra transverse photons that may be either photons or antiphotons, depending on the exact interactions. The point is, *tremendous excess EM spatial energy can appear and either be emitted as heat or interacted to perform new nuclear interactions as extraordinarily high local energy density.* This is the master mechanism enabling anomalous cold fusion transmutation reactions. The amount of time transduced will be so small that it will usually escape notice, unless stringent efforts are used to measure changes in the local flow of time.

The excess photon energy (excess 3-space EM energy) appearing in these rather random but powerful transduction interactions often accounts for the production of anomalous excess heat - for example, as occurs in many cold fusion experiments. Where scalar interferometry is maximized, a more exact action will be detailed below for the specific nuclear transformations that occur by novel new nuclear reactions. These novel nuclear reactions occur at low *initial* spatial energy but with some time-energy transducing into additional very high spatial energy to initiate the interactions.

10.5.3 Resolving the Energy Conservation Problem in Cold Fusion

When transduction is involved, standard "transverse EM waves only" computations will seemingly yield violation of energy conservation — e.g., from the emission of excess heat. That is an erroneous interpretation; energy overall is conserved, but some of the unaccounted *time-energy flow* is transduced into 3-spatial transverse photon energy dissipation. Neither 3-spatial energy nor mass-energy nor time-energy alone, or in any pairing, need be individually conserved; only the combined *total energy of all three energy components* is conserved. This resolves the present major "sticking point" between the cold fusion researchers and the conventional "transverse wave" nuclear and electrodynamic communities regarding energy conservation difficulties and perpetual motion accusations. Those making the accusations and those defending against them are both using only a special-case conservation of energy law, and a more general law is required.

Let t = time in seconds, and W= energy in joules. Rounding the speed of light to 3 x 10^8 meters/sec, the energy W_{TW} emerging as transverse wave EM energy in 3-space by the transduction of time into 3-space energy is approximately

$$\text{One sec} = c^2 \text{ joules} = 9\times10^{16} \text{ joules} \qquad [3]$$

and

$$t \Rightarrow W_{\text{TW}} = 9\times10^{16} \times t \quad \text{(in joules)} \qquad [4]$$

Let us present the new energy conservation law in slightly different form. Let W_{TW} = energy measured in spatial energy form, conveniently taken as transverse wave (TW) EM energy. Let W_m = energy in mass form (energy compressed by c^2). Let W_t = energy in time form (energy compressed by c^2).**The** present conservation of energy law is

$$W_{\text{TW}} + W_{\text{m}} = W_{\text{(total)}} \qquad [5]$$

The new extended conservation of energy law is

$$W_{\mathrm{TW}} + W_{\mathrm{m}} + W_{\mathrm{t}} = W_{(\mathrm{total})} \qquad [6]$$

The conventional particle physics accounting will see only

$$W_{\mathrm{TW}} + W_{\mathrm{m}} = W_{(\mathrm{total})} \qquad [7]$$

The conventional accountant will be unable to see

$$t \Rightarrow W_{\mathrm{TW}} \qquad [8]$$

so he will observe that the experimenter is reporting that

$$[W_{\mathrm{TW}} + W_{\mathrm{m}}]_1 \neq [W_{\mathrm{TW}} + W_{\mathrm{m}}]_2 \qquad [9]$$

which in his lexicon is a violation of the conservation of energy law itself. In short, he will identify it as a typical example of a claimed perpetual motion machine or interaction. Then the defender of the faith will wax eloquent, applying labels such as "perpetual motion nonsense", "voodoo science," etc. He himself is practicing a hoary old "voodoo" science and ignoring newer science. None of these defenders of the faith even know what powers an electromagnetic circuit or how it is that every little charge in the universe is able to continuously pour out observable EM energy in all directions, with no observable EM energy input.

On the other hand, a reasoned response will be given by real scientists still following scientific method, when faced with the numerous replicated successful experiments. The scientific method insists on the absolute priority of the replicable experiment over the predictions *of any* theory. Consequently, such reasonable scientists will advise that the protagonists cease their vitriolic rhetoric and let real science take its course; i.e., let further experiments confirm or refute reported successful results of cold fusion experiments.[302]

---

[302] Precisely such a reasoned response by chief editor Donald Kennedy of the journal *Science* has recently been given, providing a breath of fresh scientific air into an attempt by "defenders of the conventional faith" to destroy publication of important experimental results in sonoluminescence. The article which courageous editor Kennedy approved for publication — over intense objections of the professional critics — is R. P. Taleyarkhan et al., "Evidence for Nuclear Emissions During Acoustic Cavitation," *Science,* Vol. 295, Mar. 8, 2002, p. 1868-1873. We heartily commend Editor Kennedy for this classic example of how science should be conducted — so that experiments, not prevailing dogma, determine what is valid and what is invalid.

What the professional skeptic will not see is that his own expression of the conservation of energy law has been incomplete, and that it is his own inadequate "measurement yardstick" assumption that is now in error. The *extended* conservation of energy law of course still holds, but the *conventional* special case law is violated because its fundamental assumption — that time is not transduced to spatial energy in the experiments —has been violated in the experiment.

Indeed, with the publication of the work of Evans et al., experimentally proving the fluctuation theorem and the high probability of time reversal zones appearing for short but significant periods at up to micron levels, the second law of thermodynamics has been rigorously proven to be violated. Hence the conventional scientific community's rather dogmatic objection to the extra heat of cold fusion interactions is no longer scientifically justifiable.

Understanding of the extended conservation of energy law and the permissible violation of the second law of thermodynamics resolves the present thorny dissension within the scientific community over the excess spatial energy produced by cold fusion. It also resolves the issue of what could possibly be a source of such intense energy density as is required for nuclear transmutation reactions.

Any ordinary system is indeed an open system, freely and continuously exchanging energy with its ***temporal*** environment as well as the seething active vacuum.[303] If the system is in temporal energy equilibrium in that exchange, then the present restricted conservation of "spatial and mass" energy law applies and one does not have to consider the interactions between supersystem components. If the system is placed in disequilibrium with its temporal energy environment, then supersystem components interact asymmetrically and the extended conservation of energy law applies. In that case, excess spatial energy can be and will appear in the system whenever time transduction into spatial energy is occurring.

---

[303] But see our Appendix A. Present thermodynamics rather inanely defines a "closed" system as one where no mass exchange crosses its boundary with its environment, but energy exchange can and does. In that view, a "closed" system can be far from equilibrium in its energy exchange with its active environment, and thus demonstrate the five magic attributes of such disequilibrium systems. In this book we have deliberately chosen to treat a "closed" system as one in which neither energy nor mass exchange crosses the system boundary — which classical thermodynamics refers to as an "isolated" system. We explain all this (and why) in Appendix A.

The implications of cold fusion energy transduction are that

(1) Time is being "burned" or transduced as a "fuel" and source of energy,

(2) Transduction of only one microsecond per second will yield 9×10^{10} watts steadily. That's 90,000 megawatts of energy per second — the equivalent of 90 large 1,000-megawatt power plants — if all the transduced energy were collected and used to power loads with 100% efficiency.

(3) Thousands of new nuclear reactions are made possible and feasible by local transduction of time-energy into 3-spatial EM energy.

(4) Appropriate capture and use of a portion of the excess energy can be accomplished to power loads.

Even if we capture and utilize only 1% of the transduced time-energy to power the loads, where the *time-energy to spatial energy transduction* is only the transduction of 1 microsec/sec, that system will produce the normal EM energy to power 900 megawatts in the load. That's almost 90% of the capability of a modern 1,000-megawatt power plant. That is quite a respectable electrical power system. It only requires the transduction and "burning" of one microsecond of time per second, without any nuclear wastes or hydrocarbon byproducts.

As can be seen, transducing time into energy is by far the most efficient way to go to develop new power plants for the future. This is particularly true since every charge in the universe already transduces time-energy flow into spatial EM energy flow. Indeed, we may consider that the negative charge transduces time-energy flow into the spatial outflow of EM positive energy, while the positive charge transduces negative time-energy flow into an outflow of EM negative energy. The process is useful not only for power applications, but also for transport applications as we briefly pointed out in Chapter 8.

10.6 Some Resulting *Low Spatial Energy* Nuclear Reactions

Refer again to paragraph 10.4 above. Summarizing: The formation of time-reversal zones (TRZs) is what enables the appearance of the new nuclear reactions in the electrolyte in cold fusion experiments. It does this by changing the Coulomb barrier between like charged ions into a Coulomb attractor. Further, the rate at which TRZs form and decay in the solution is a function of the frequency and intensity of the scalar interferometry from the loaded palladium lattice. This means that the appearance of the new nuclear interactions in the electrolyte is also a function of the degree of loading of the palladium lattice, as well as the "double surface" interferometry preparation of the palladium, its cracks, etc. These are the major variables. Once the major variables provide the solution for significant formation of TRZs, then the following reactions can and do appear.

The sample reactions we present here are just a few of the thousands of new reactions possible. These example reaction products have been found in a great many successful cold fusion experiments in various laboratories around the world. Some 600+ successful experiments have now been done, and a sizable literature has built up and continues to be built up on the experiments and their results.

For our sample reactions, the primary mechanism of interest consists of several parts:

(i) Formation of a TRZ, in which two positive ions (we shall look at H+ and D+), now attract each other. Also, the gluon forces in the proton and neutron, in the ions of interest, are significantly lessened, so that the quarks in each proton and neutron are very much more loosely bound. Consequently, decay from an excited state by quark flipping to turn a proton into a neutron or vice versa becomes an attractive option. The strong force is therefore reduced in radius.

(ii) Two positive ions now attract each other so closely that each enters the edge of the weakened strong force region of the other. This forms a *quasi-nucleus* because of the limited involvement of the weakened strong force.

(iii) The other ions in solution surrounding the TRZ immediately move (as soon as the TRZ is formed) to negate the TRZ and decay it back to a time-forward zone (TFZ). This action initiates the decay of the TRZ.

(iv) As the TRZ lessens and then turns back into a TFZ, the strong force expands its size faster than the novel Coulomb "like attracting like" force reduces and reverses.

(v) The rapidly expanding strong force of each of the two ions in the quasi-nucleus fully envelops the other ion, increasing the disequilibrium of the two-ion quasi-nucleus. A condition is reached where the most probable mode of decay is the flipping of one quark in one of the positive nuclei.

(vi) The quark flips, turning that H+ ion into a neutron n. This is a quasi-nucleus of deuterium (D+), still in an excited state but with less excess potential energy in the excited state. At this point, the TRZ is vanishing and the TFZ state is returning.

(vii) As the TRZ vanishes and TFZ state increases back to normal, the most probable mode of decay increasingly is to a full deuterium nucleus. Hence the H+ and n simply draw completely into normal deuterium binding position, bound by the normal strong force. This constitutes a normal D+ ion, now existing in a normal TFZ.

(viii) So by formation and decay of a significant TRZ, two H+ ions have been drawn together into a quasi-nucleus consisting of two H+ ions partially bound by a weakened strong force. As the TRZ decays and the Coulomb repulsion resumes, the strong force increases back to full strength faster than the Coulomb repulsion force returns and repels the two H+ ions. Since the quarks are much more loosely bound than normal, a quark in one of the H+ ions has flipped, turning the ion into a neutron n. The H+ ion and the neutron, partially bound already in a quasi-nucleus, simply "tighten" into a normal D+ nucleus as the TFZ condition is fully resumed.

The nuclear reaction equation for the above interaction may be written as

$$ {}^1H_1^+ + {}^1H_1^+ \Rightarrow (({}^1H_1^+ + {}^1H_1^+)) \Rightarrow ({}^1n_0 + {}^1H_1^+) \Rightarrow {}^2H_1+ = {}^2D_1^+ \qquad \textbf{[10]} $$

In equation [10] we use the left superscript as the number of nucleons in the ion nucleus, the right subscript as the protons in the ion nucleus, and the right + superscript to show the overall charge of the ion and its sign. We use the expression in parentheses to show the involvement of a time-reversal zone (TRZ). Double parentheses show a stronger TRZ than single parentheses. Thus from double parentheses to single parentheses to no parentheses shows the initial formation and subsequent decay of the TRZ.

Another interaction involves a D+ ion and an H+ ion, to produce tritium. This is:

$$^{2}D_1^{+} + {}^{1}H_1^{+} \Rightarrow ((^{2}D_1^{+} + {}^{1}H_1^{+})) \Rightarrow (^{2}D_1^{+} + {}^{1}n_0) \Rightarrow {}^{3}H_1^{+} = 3T1^{+} \quad [11]$$

That reaction transmutes a deuterium ion and hydrogen ion into a tritium ion. Without showing it, in a TRZ three $^{2}H_1^{+}$ ions may also attract into a quasi-nucleus, and as the decay of the TRZ occurs, first one proton turns into a neutron and then a second one does also, by quark flipping. This nuclear reaction also produces a fusion into tritium.

Another reaction between two deuterium ions is"

$$^{2}D_1^{+} + {}^{2}D_1^{+} \Rightarrow ((^{2}D_1^{+} + {}^{2}D_1^{+})) \Rightarrow [2(^{1}H_1^{+} + {}^{1}n_0)] \Rightarrow {}^{4}He_2^{+} = \alpha \quad [12]$$

That interaction — particularly in pre-deuterated electrolyte solution — gives the excess a particles produced in a great number of the cold fusion experiments.

A rarer but still occurring interaction is:

$$4[^{1}H_1^{+}] \Rightarrow ((^{2}D_1^{+} + {}^{2}D_1^{+})) \Rightarrow {}^{4}He_2^{+} = \alpha \quad [13]$$

Indeed, reaction [13] may occur to completion and formation of a particles in some of the transmutations in an electrolyte, while it proceeds only to the intermediate phase in others. In that case, both deuterium ions and a particles may be produced out of the same overall "chain of reactions" where some reactions proceed all the way and some do not.

These interactions are directly using and transducing time-energy by use of the TRZ to time-reverse the Coulomb repulsion law for like charges. From the reactions, excess energy given off as heat may and will occur.

The nuclear physicist and nuclear chemist can immediately see a great many new nuclear reactions now made possible by the adroit production and decay of TRZs. A great number of these new nuclear reactions are now possible by this means, which are impossible in ordinary nuclear chemistry without the deliberate formation of TRZs.

These few examples serve to illustrate the process, and these reactions represent results already achieved in numerous cold fusion experiments worldwide, by many researchers and multiple laboratories. Now we turn to other evidence strongly supporting the novel nature of these reactions rather than several other proposed reaction equations yet to be proven. The other proposals do not explain the next type of new experimental reaction.

10.7 Time-Energy Can Generate Instrumentation Anomalies

Strong evidence for time-charging and time-charge decay is experimentally demonstrated in electrolyte experiments where time-reversal zones (TRZs) are operating, and thus where some localized processes are running backwards in violation of the second law of thermodynamics. Weak time-charging of photon-absorbing and emitting matter, with special patterns of spacetime curvatures (engines) induced by time-density oscillations and structuring, is persistent in matter, having "charge-up" and "decay" times that may last for minutes, months, or even years. A very wide range of previously anomalous phenomena, both in inert and living matter, is explainable by these new interactions. This is very probably also related to the "memory phenomena" noted by Kondepudi and Prigogine[304] as outside the present thermodynamics, but being worked on at the forefront in what is called "extended thermodynamics". Quoting Kondepudi and Prigogine, p. 460:

> *"...interesting memory effects ...appear for long times (as compared to characteristic relaxation times). ...nonequilibrium processes may have 'long-time tails'. In other words, the approach to equilibrium is not exponential, as was generally believed, but polynomial ...which is much slower. ... As a result, Nature has a much longer memory of irreversible processes than it was thought before. Again this shows that local equilibrium is an approximation, albeit a very good one."*

In this book, we focus primarily upon some typical anomalous measurements in China Lake experiments that are directly involved with time-charging and decay effects, lending strong support to our thesis of the novel TRZ-induced nuclear reaction chains. Note that these instrumental anomalies are also strong evidence for the association of time-charging and time-charge decay with the proven fluctuation theorem of Evans et al.

---

[304] Dilip Kondepudi and Ilya Prigogine, *Modern Thermodynamics: From Heat Engines to Dissipative Structures,* Wiley, Chichester, 1998, p. 459. For a discussion of extended thermodynamics, see D. Jou, *Extended Irreversible Thermodynamics,* Springer-Verlag, New York, 1996.

at the Australian National University. We believe this to be a contribution to that very important work of Evans and his colleagues.

10.7.1 Ionization Detectors, Transduction, and EM LW Interferometry

Ionization processes obviously are processes where the partial transduction of LW time interaction into 3-spatial energy interaction would yield ordinary excited energy states of the affected electrons or ions. In turn, this would lead to ionization (e.g., of the atoms and molecules of a gas, liquid, etc.) Hence, ordinary ionization detectors such as Geiger Miiller tubes have the innate *capability* of detecting such transduction that generates ionization, and thereby have some capability of serving as "detectors" of longitudinal EM wave interactions (and time-charging) ongoing in the detector. In the usual situation, no excess time-charging results and no time reversal zones result. In that case, symmetry of energy flow in the time-domain exists, as does symmetry of energy flow in 3-space. Absolutely normal chemistry and nuclear chemistry results, and the nuclear detectors function normally, as familiar to every laboratory.

However, when significant TRZs emerge and persist for short periods, the symmetry of both time-energy flow and 3-spatial energy flow is broken. In this case, transduction of time-energy into 3-spatial energy (and vice versa) can result in anomalous ionization in nuclear ionization detectors, even in the absence of normal transverse EM nuclear radiation. The trick is to use and compare different detectors and different types of detectors to clearly demonstrate anomalous ionization detection effects.

As an example, a Geiger Muller tube will detect any ionization of its internal gas, regardless of what caused that ionization. If the ionization is caused by normal ionizing radiation from nuclear reactions, the instrument will detect and read a resulting internal ionization of the gas inside the tube.

On the other hand, if time-charging and decay are involved, then the asymmetry resulting in 3-spatial energy excitation of the gas inside the Geiger Muller tube (due to transduction of some time-energy into excess 3-spatial energy) may be sufficient to ionize the gas. In that case, the instrument will read "as if nuclear radiation were present. Note that there is indeed "ionizing radiation" present in the gas. However, now this ionizing radiation is not transverse EM wave in nature, but is due to the time charging and decay, and transduction of time into 3-spatial energy in the detecting gas.

This capability of an ionization detector to ionize in the presence of non-transverse wave ionizing radiation and energy can be used to provide an indication of time-density waves being formed and interacting in a process (such as a cold fusion process) where some transduction from time-energy to 3-spatial energy occurs.

Further, the previous "time history" of the individual instrument plays a part in whether the instrument "reads" or not for a given transduction situation. There will be a statistical variation of the actual "already present" low-level time-charge (and in its internal structure and engines) between instruments, even those made in the same factory on the same day from the same batch of materials and parts. That is because the time-charging and discharging history of each instrument has been different.

The production of transduced TWs, however, must be a function of scalar interferometry in the gases or other detecting media of the instrument, since scalar interferometry *creates* all transverse EM waves, as shown by Whittaker {619} and confirmed by Evans *et al.* {620}. In such interferometry, the entire inner structures of the transverse EM waves formed in the interference zone also interact wave-to-wave. Thus, this kind of interferometry is extremely sensitive to the exact internal longitudinal EM bidirectional wave structure (internal engine substructure) of the involved potentials.

As a consequence, the ability of an ionization detector to transduce a specific set of LWs and give ionization detection will vary appreciably, including for different variations in the instrument's original manufacturing process, and even for the specific past photon interaction history and experience of the individual detector itself. One detector's set of cumulated internal time-charges (and hence spacetime engines) may vary considerably from those of a second detector of exactly the same type. In general, multiple ionization detectors are unlikely to all detect a given time-density EM wave emission and interaction set {621}.

Even for two detectors of the same brand, from the same manufacturing plant, and from the same batch of manufacture, it is likely that significant differences in LW detection of a specific TDW set will occur because of the "past history" time-charge differences of the individual detectors. Indeed, a likely phenomenon is that, when one ionization detector detects the LW emissions (transduces them), several others will not detect them at all. This is one of the peculiarities of the new unified field area that must be overcome by further research in order to develop reliable, calibrated TDW and transduction detectors. It is one of the primary problems - if not *the* primary problem - of cold fusion research to resolve this *"time-charge experience history"* problem, so that transduction detectors having calibrated, uniform responses to given TDW sets and interactions can be provided.

At present, no one has the foggiest notion as to how to "calibrate" a nuclear ionization detector that one desires to use as a time-energy transduction detector. Speculating, we would envision such calibration (in the transduction detecting functional response) to become possible when small, standard, calibrated sources of transduction are developed and available. In that case it will be possible to formulate procedures whereby varying the output of the transduction source will vary the transduction irradiation of the GM tube. The level of transduction intensity required to create ionization in the instrument will be a direct indicator. When small, calibrated sources of TDWs are also available, it will be possible to irradiate the GM tube to a specifically desired rate and level of time-charge and decay. In that case, an array of GM tubes can be "standardized" or "calibrated" for transduction detection. So far as this author is aware, those developments have yet to be accomplished or even undertaken. Indeed, the need for such a development program has not even been realized.

10.7.2 Experimental "Detector Transduction Phenomena" in Electrolysis

Let us look at one set of ongoing scientific experiments where just such anomalous detector results have been obtained.

Researchers at the Naval Air Warfare Center at China Lake, and at the Department of Chemistry, University of Texas at Austin, have detected precisely the kind of "anomalous" radiation and transduction effects we expect to be in the ionization processes of multiple kinds of detectors {622}.

According to a report by Miles and Bush {623}, anomalous radiation at China Lake was first detected by the exposure of dental X-ray films in two experiments producing excess power (excess TW energy emission). Film used in a control study during these experiments showed no exposure. There was also no exposure of similar films in more than 20 experiments where no excess power was present. In other words, the presence of excess heat (excess TW energy emission) strongly indicates the presence of transduction. In turn, the presence of transduction implies the presence of scalar interferometry wave interaction, where TDW waves and LW waves **are** absorbed and **a** mix of LW and transduced TW waves are emitted consisting of gravitons (paired scalar and longitudinal photons). This only occurs when significant time-charge excitation has built up. Taken in reverse, the presence of LW wave absorption and emission — with transduction into detected excess ionization energy — directly indicates the emission of "anomalous" TDW or graviton radiation, as detected by the resulting TW exposure of the x-ray film. So the "anomalous" radiation detections are consistent both forward and backward.

The film in manufacture is quite strongly quality-controlled. Also, it is used (interacts and indicates) only once. Its past time-charge history has minimal variations between two samples of the film, because there is no repetitious past *detection interaction* history. Hence one would expect a high degree of uniform film detection interaction responses from film to film, to the same graviton emission set. That is precisely what occurs.

We conclude that the behavior of the film in the combined China Lake experiments clearly shows the time charging, graviton emission and interaction, and transduction nature of what is happening when it is known that no normal nuclear radiation is present.

Geiger-Muller (GM) detectors and sodium iodide (NaI) detectors were also utilized when electrolysis experiments using heavy water were ongoing. We again accent that a Geiger-Muller tube does not detect nuclear radiation per se; instead, it detects *anything* that will cause its internal gas to ionize sufficiently. Sufficient transduction in graviton absorption-emission interactions in a Geiger-Muller tube will cause the counter to indicate, because it ionizes the gas and produces an ionization discharge. However, both the specific transduction and scalar interferometry aspects of the ongoing experiment are involved, as well as the previous background time-charge history of the Geiger-Muller tube counter.

Several Geiger-Muller detectors gave anomalously high readings, reaching some 73 sigmas above normal background counts. Most experiments (i.e., most GM detectors), however, gave normal radiation counts, and no anomalous count rates were ever observed when the experiments were turned off. So these anomalous results are differentiated by using multiple, carefully calibrated Geiger-Muller tube detectors. Our interpretation here is that

(i) There was a variation in the presence of transduction and scalar interferometry from experiment to experiment,

(ii) The majority of the experiments did not produce significant time-charge and sufficient transduction or scalar interferometry to cause detection (ionization discharge) on most (typical) Geiger-Muller tubes, and

(iii) The transduction effects in the ongoing experimental process were mostly of the rapid variety, and not due to long-term "charge-up" effects conditioning the time-charge aspects and structuring of the experimental apparatuses.

(iv) By using multiple detectors, the probability of one or more of the instruments having increased time-charge from specific time-charge histories was increased.

(v) With sufficient experiments and sufficient detectors, there resulted a high probability of having at least one or more detectors capable of detecting the levels of graviton radiation and transduction expected from the experiments.

(vi) A direct correlation would be predicted — and was observed — in the appearance of the anomalous radiation effects and the expected time periods required to load the palladium with deuterium. As reported by Miles and Bush, *ibid.*:

> *"... the anomalous radiation would appear within a few hours in the co-deposition experiments where the palladium is loaded with deuterium as it deposits from solution. In contrast the appearance of anomalous radiation required days of electrolysis for the palladium rods that load much slower."*

We previously discussed the major variables indicated from many cold fusion experiments to include the strong correlation with the degree of loading of the palladium lattice. Hence the effect pointed out by Miles and Bush would indeed be predicted by the present approach and proposed mechanism.

Our interpretation is that the experiments show the time-charge rate effect to be expected in such graviton radiation and transduction interaction phenomena using collection of ions (in this case deuterium) that are much heavier than electrons. The faster the deuterium loaded, the greater the buildup of the interaction of the deuterium in phase conjugating and self-targeting iterative interactions — and therefore the greater the increase in scalar interferometry interactions — inside the palladium lattice. The rate of graviton radiation production and transduction production increases as some function (not necessarily linear!) of the rate of loading of the **deuterium.** As the rate of graviton and transduction production increases, so does the expectation of anomalous ionization effects in the nuclear radiation detectors. And so does the rate of production of TRZs and the appearance of the new nuclear cold fusion reactions at low spatial energy but very high time-energy.

10.7.3 Experiment Confirms It

A clinching observation is given by Miles and Bush, *ibid.,* as follows:

> *"One GM-detector would measure anomalous radiation while another GM-detector would be "blind" to any anomalous effect. A few experiments, nevertheless, gave simultaneous anomalous effects from two different radiation detectors."*

Here our comment is that this precisely fits our expectations for demonstrating involvement of

(i) Time-charging and decay interactions,

(ii) Consistency with transduction expectations,

(iii) Consistency with the fact that two different radiation detectors may or may not exhibit or detect the anomalous ionization effects, depending upon the individual past time-charge histories of the two detectors, and

(iv) Predictable variations in the individual experiments (based on palladium lattice loading time, specific geometry, ionization state of the chemical solution, internal time-charge state and decay rate, and structuring of the apparatuses and their parts, etc.) when transduction-associated phenomena are considered.

The anomalous non-nuclear, non-transverse wave — but ionizing — EM radiation detected at China Lake, and the resulting peculiarities in the measurement apparatus functioning, do strongly support the present proposed approach, the proposed graviton radiation phenomena, and the time-charging and decay and transduction mechanisms presented. It is decisive that sometimes two detectors both indicated, and sometimes one indicated and the other would not. Sufficient replications have ruled out any defect in a single given instrument as the cause of the anomalous detections. That immediately eliminates from consideration all purely transverse EM wave phenomena, conditional only upon the premise that the instruments were properly functioning and calibrated, and that sufficient replications were made for decisive statistics. Those conditions were all met in the numerous experiments producing these results over a long time and in many repetitions.

As a final thought on the subject, we pose the possibility that the longitudinal EM waves involved may be the B(3) longitudinal field waves advanced convincingly by Evans {624a-624c}. We would recommend the attention of leading theorists and experimentalists to this possibility, as a matter that should be investigated both theoretically and experimentally.

10.8 Additional Implications for the Future

10.8.1 Longitudinal EM Waves and Undistorted Progressive Waves

There is a revolution in electrodynamics presently underway, due to the unique characteristics of *longitudinal* EM waves[305] and *pseudo-longitudinal* EM waves. A summary by Rodrigues and Lu {625} is particularly revealing.

A pure longitudinal EM wave has infinite energy and infinite velocity — i.e., it appears everywhere at once. "Propagation through space" does not apply; instead, one has stumbled into that weird region where spacetime is multiply connected. In the real world, one meets imperfect longitudinal waves — or *pseudo-longitudinal* EM waves — that still retain a transverse energy density variation residue. These waves are called *undistorted progressive waves* (UPWs).

Such UPWs can move in space faster than the speed of light. This should not be too surprising, since superluminal velocity of intelligent signals has been positively demonstrated by several researchers in quantum-tunneling experiments. As an example, Nimtz {626} and his colleagues have beamed Mozart's 40th Symphony through a barrier in a waveguide at a speed of 4.7c. So the old notion that information cannot be transported at superluminal velocities is passe. The Fogal semiconductor has been used in experimental transmitter-receiver pairs to demonstrate superluminal transmission, such as TV pictures and programs. Direct signal transmission from earth to satellite back to earth and through many en route amplifiers and processors has been demonstrated by Fogal to occur far beyond the speed of light. Again, theoretical summary papers by Rodrigues *et al.* {627a-627f} are revealing.

---

[305] We have pointed out a direct way to generate longitudinal EM waves, by simply oscillating the magnitude of the L**orentz self-regauging** of a system.

10.8.2 Death Knell of the Speed of Light Limitation

Another giant shock has emerged in astrophysics during the last few years, and it is now threatening a dramatic revision to physics. Heretofore, it has been fashionable to assume that gravity itself propagates at light speed. A great deal of very comfortable physics theory has been built around that assumption.

Well, the assumption is not true. Experiments in astrophysics continue to refute it. It now is almost certain that the speed of gravity is at least 2×10^{10} c. A beautiful though somewhat controversial paper by Tom Van Flandern {628} summarized the entire situation. He articulates the comfortable general relativity view held to date {629} as follows:

> *"...GR proposes that such changes appear to act instantaneously in the 'near field', but eventually show their true, light-speed-delayed character in the 'far field', which is conveniently beyond our present ability to observe. The necessity of this dual behavior is to prevent the logical need for changes to continue to appear to act instantaneously at ever increasing distances, even to infinity."*

In fact, Van Flandern {630} points out that general relativity already admits superluminal effects in the near field region. He also pointed out the startling nature of the experimental results to relativists, and points out that an attachment to a paradigm has been involved:

> *"To many, this result* [astronomy's verification that gravity's speed $v_g >= 2x10^{10}c$] *is so contrary to 'common sense' in the light of relativity theory as to be absurd. But Thomas Kuhn has cautioned all scientists to avoid the trap of becoming so steeped in a prevailing paradigm that it starts to seem like common sense and makes other ideas sound and feel wrong. Eventually, even one's professional status can become linked to a prevailing paradigm. "*

As Van Flandern further emphasizes, it is not difficult to show by computer calculations of astrophysical situations that any strong limit on the speed of light destroys conservation laws:

> *"...anyone with a computer and orbit computation or numerical integration software can verify the consequences of introducing a delay into gravitational interactions. The effect on computed orbits is usually*

> *disastrous because conservation of angular momentum is destroyed."*

So here we have a new paradigm in the making. This is a startling change to standard relativity. Either we have to give up the conservation of angular momentum, or we have to accept superluminal speed of gravity in the far field. Years of struggle to detect quadrupole gravitational wave radiation have failed; no direct detection has ever been made. Indeed, the rather arbitrary nature of the entire quadrupole radiation assumption is not required by general relativity, as long pointed out by leading Russian scientists. For example, Vlasov and Denisov {631} *et al.* bluntly state it in these words:

> *"...Einstein's well-known quadrupole formula, which is usually employed in general relativity for calculations, is not a consequence of general relativity and is not contained in it. "*

Therefore, it may not really be so surprising that physicists have not been able to detect such quadrupole radiation in a great many laboratory experiments. It is not in general relativity at all.

Of course, our thesis developed in this book is that what we have long called "EM radiation" is in fact gravitational radiation, always involving paired scalar and longitudinal photons and hence time-density waves and longitudinal EM waves. We have pointed out that prior to observation there is no such thing as a separate photon, but there is such a thing as two correlated photons, one time-polarized and the other longitudinally polarized. We believe that there is sufficient meat in our proposed explanation of the anomalous cold fusion results and the anomalous instrument results at China Lake to warrant serious and strenuous investigation of these hypotheses and proposed mechanisms.

Another oddity - usually never stated by Western physicists - has long been known but ignored. When Einstein characterized the gravitational field as a pseudotensorial field, and not a field in the sense of the Faraday-Maxwell field, the consequences were that the 3-space energy laws of the familiar kind really do not exist in general relativity. Shortly after Einstein published his theory of general relativity, this absence of familiar energy conservation was pointed out by Hilbert {632} in these words:

> *"I assert... that for the general theory of relativity, i.e., in the case of general invariance of the Hamiltonian function, energy equations... corresponding to the energy*

> *equations in orthogonally invariant theories do not exist at all. I could even take this circumstance as the characteristic feature of the general theory of relativity. "*

With our publication of the giant negentropy of 4-space once arbitrary 3-space symmetry and time-symmetry in EM energy flow is removed, one of the truths involved in Hilbert's remark was finally recognized. In addition, what Sen called "the most difficult problem in classical and quantum electrodynamics" {633} has been explained by giant negentropy {12}. Also, it is consistent with an appropriate reinterpretation of Whittaker's 1903 decomposition of the scalar potential {600, 615}. Finally, it is consistent with quantum field theory {634}.

Hilbert was evidently not understood by his contemporaries, since neither Einstein himself nor other physicists recognized the fact that, in general relativity, conservation laws for 3-space energy, momentum, and angular momentum — in the sense we are accustomed to in the rest of physics —in principle may be impossible. That is because one can readily remove 3-space energy symmetry when curved spacetime is permitted. Again, Russian scientists such as Logunov and Loskutov {635} have long pointed out the "unthinkable" and "astounding" fact that the predictions of general relativity are not unique.

In the West until recently relativists were conservative, and this resulted in the sidelining of innovative Western physicists who challenged the prevailing interpretation or extended it. With the experimental falsification of one of the fundamental tenets — that gravity moves at speed c in the far field — of the prevailing interpretation of general relativity, it appears that we may be approaching an asymptotic burst of great new theoretical work and a dramatic new reinterpretation. If it ever gets into production, we believe that the Fogal semiconductor will usher in that great change of communication speed paradigms that now appears imminent.

Nonetheless, general relativity — whatever the modifications and extensions now called for — will remain a very useful tool indeed. There is simply nothing else on the horizon that can replace it, string theory notwithstanding. The reinterpretation is likely to shed additional light on many present problems such as the nature of spacetime itself, the nature of dark matter, and new insight and progress on unifying physics.

In the new openness that should result, we hope that a great extension and reinterpretation of electrodynamics will also be undertaken, and that it will reveal the underlying powerful structured general relativity infolded inside conventional EM potentials, fields, and waves, as originally revealed by

Whittaker {636}. It may even be that one of the novel concepts {637} we have proposed in this book will yet see the light of day in practical systems.

If so, then hopefully much of what we are addressing in this book will be incorporated in the emerging new physics of the twenty-first century.

Chapter 11

Final Perspective: Permissible COP>1.0 Maxwellian Systems

"Are you certain of that?" [Augustine, in his famous confrontation with the Skeptics, who held that nothing can be known with certainty.]

"[It is usually]...assumed that the magnitude of potential energy is irrelevant, being arbitrary to the extent of an additive constant." [Block and Crater]. {638}

"The potentials V and A, defined ... in terms of the fields E and B, are considered to be nonobservable in Maxwellian electromagnetism, since the energy density associated with them is zero..." [Lakes]. {639}

"[The total energy of the atom] depends on the bare mass and bare charge of the electron, the mass and charge that appear in the equations of the theory before we start worrying about photon emissions and reabsorptions. But free electrons as well as electrons in atoms are always emitting and reabsorbing photons that affect the electron's mass and electric charge, and so the bare mass and charge are not the same as the measured electron mass and charge that are listed in tables of elementary particles. In fact, in order to account for the observed values (which of course are finite) of the mass and charge of the electron, the bare mass and charge must themselves be infinite. The total energy of the atom is thus the sum of two terms, both infinite: the bare energy that is infinite because it depends on the infinite bare mass and charge, and the energy shift... that is infinite because it receives contributions from virtual photons of unlimited energy." fWeinberg]. {640}

11.1 Introduction

The central message in this book is that all EM devices are already powered — though in an inappropriate fashion — by EM energy freely extracted from the seething vacuum. It is also intended to be a clarion call that we must rapidly develop the *appropriate* vacuum-energy powering of our EM circuits and electrical power systems, or else the survival of the nation and of the biosphere is at stake rather immediately.

For this summary chapter, we wish to place that specific area — EM energy from the vacuum — in sharp focus, with the major facets together in one place.

Consequently, for this closing chapter we have chosen and slightly adapted a previous technical rebuttal to the objections of "perpetual motion", "violation of the second law of thermodynamics," "impossible", etc. that we wrote in 2001 in the referee process, to the referees of one of the AIAS papers submitted to a major physics journal. The rebuttal was successful, and it was accepted and upheld by the referees. The paper was then published by the journal, after very vigorous refereeing.

That is as it should be.

Scientific journals provide a proper forum for the free expression and debate of scientific ideas and work. They do not and should not ensure that every paper conforms to commonly held concepts or to the most widely accepted model. As we stated, Chief Editor Kennedy of the journal *Science* has only recently had to restate and accent the principle that science is free from "truth by prevailing authority," and bound by "truth by replicable experiment". Insuring that every paper meets the accepted models and notions would be enforcement of religious belief, not experimental science. Ideas which are wrong will be refuted experimentally; experiment is still the basis of scientific method. In our rebuttal, the argument of the conventional skeptics is thoroughly refuted by experiments already well known in the literature, as we detail.

So we thought it appropriate to close the book with this strong statement of its primary pbjective: economical, clean, copious electrical energy from the vacuum.

11.2 Source Charges, Curved Spacetime, Efficiency, and COP

11.2.1 The Source Charge Problem

The received interpretation of the Maxwell-Heaviside theory treats the source charge and source dipole as perpetual motion machines, freely and continuously pouring out EM energy in 3-space in all directions with no energy input. Experimentally one verifies that there is no *3-space observable energy input* to the charge or dipole. In accepting that model, a scientist objecting to COP>1.0 EM systems has unwittingly hoisted himself upon his own perpetual motion machine petard, by already accepting every source charge and dipole as precisely that to which he is objecting. To explain the source charge, either one holds to the U(1) Maxwell-Heaviside theory and surrenders the conservation of energy law, or one accepts a change to U(1) electrodynamics to add the concomitant input of energy flow from the active vacuum (from the *time* domain, which in Minkowski geometry is all that is left outside 3-space) to that charge or dipole. That corresponds to a violation of the second law of thermodynamics, as — as we discussed in Chapter 10 — Evans and his colleagues at the Australian National University have already experimentally proven that the second law can be violated up to micron scale and for times of up to two seconds.[287] At the much smaller fundamental charged particle level and far shorter "switching" time of one spin completion, the probability is 100% and a certainty that the second law is violated. Hence the broken symmetry of the charged particle considered in the modem sense as a dipolarity (considering its associated **clustering** virtual charges of opposite sign).

Either way, the classical Maxwell-Heaviside theory must be changed. Every charge and every dipole — which themselves are Maxwell-Heaviside EM systems *a priori* — refutes the erroneous argument that no Maxwell-Heaviside system can output more energy than the operator himself inputs from an external power supply. To adamantly continue to challenge something already *experimentally demonstrated by* every charge and dipole in the universe is the epitomy of scientific blindness.

As have others, Sen {641} called this source charge paradox the "most **difficult"** problem in electrodynamics. However, the basis for its solution - absorption and transduction of virtual KM energy from the vacuum via the broken symmetry of a charge or dipole in its vacuum energy exchange — has now been known in particle physics for nearly a half-century {642a-642d}. It is not included in the Maxwell-Heaviside-Lorentz theory. Neither the proven vacuum interaction with Maxwellian system nor the broken symmetry in that interaction has been added to the model.

The present author has proposed an EM wave solution {643} to the source charge problem, by reinterpreting Whittaker's {644} decomposition of the scalar potential (as between the ends of a dipole) and treating the "isolated charge" and its clustered virtual charges {645} of opposite signs as a set of composite dipoles. Each of the dipoles then becomes a broken symmetry in the energetic exchange with the vacuum. Hence the charge pours out observable EM energy with no *observable* energy input because the input energy is in virtual photon form.

In the solution, the EM energy is input to the charge or dipole from the time-domain, so conservation of EM energy flow is upheld in 4-space, while time-like symmetry and space-like symmetry are broken individually. Powerful support for the proposed solution was given in a quantum field theory argument by Mandl and Shaw {646} nearly three decades ago. We challenge any scientist skeptical of COP>1.0 Maxwellian systems to produce a solution of the source charge problem in Maxwell-Heaviside-Lorentz theory alone. In conventional theory, every charge in the universe experimentally exhibits COP = oo. Any theory conflicting with a replicable experiment is falsified a priori.

11.2.2 EM Waves Imply Curved Spacetime

The oscillating energy of an electromagnetic wave is continuously changing its local spatial energy density. This is an *oscillating change of spacetime curvature* if one accepts general relativity (GR). Hence the EM wave in space is *always* moving in a locally curved spacetime; else, no EM wave exists because no change in spatial energy density exists. To reject that, is to reject GR in its entirety as well as all the experiments consistent with GR. If one accepts GR, then the classical U(1) EM *assumption* of the EM wave moving in a fiat spacetime is a non sequitur. It is unscientific to be suspicious of a higher group symmetry O(3) electrodynamics which *does* correct this known non sequitur in U(1) electrodynamics, while limiting oneself to U(1) electrodynamics *with* that known error. One might as well be suspicious of tensor algebra because it is more comprehensive than vector algebra.

There are many EM experiments such as the Aharonov-Bohm effect {647a, 647b} which violate Maxwell-Heaviside EM, as is well known

{648, 649a-649i}. The foundations of the Maxwell-Heaviside theory are well over a century old, and Maxwell's theory was substantially truncated in the 1880s (more on that below). The considerable physics developed since then has required dramatic extensions to the Maxwell-Heaviside theory such as developing non-Abelian gauge field EM theory, quantum electrodynamics, and modeling of the interaction of vacuum and matter in any material system.

11.2.3 On EM Systems with COP>1.0

Conservation of energy requires that all energy output by an inert system must be input to it {650}. It does not require that the *operator* input all or even any of the energy utilized. The active environment can permissibly input part or all of it, else there could be no such thing as a windmill — or a charge, or a dipole, or a solar-cell electrical power system.

The *coefficient of performance* (COP) of a system compares the system's useful energy or work output to the *operator's* energy input. The *efficiency* ε of a system compares its useful output to its *entire* energy input. No inert system can output more useful energy than its total input, hence $\varepsilon <= 1.0$, being $\varepsilon = 1.0$ for a theoretically lossless "perfect" system and $\varepsilon < 1.0$ for a real system with losses.

Whether the operator must input all the energy that is output by the inert system depends upon whether the system is (i) an open system in disequilibrium with its active environment, and (ii) *designed* to accept and utilize excess energy from that environment, such as from the active vacuum. If appreciable environmental energy input is received and utilized, then a system with losses may permissibly exhibit COP>1.0, even though its efficiency ε is $\varepsilon < 1.0$. The common home heat pump is an example. While the efficiency of a home heat pump may be $\varepsilon = 50\%$, its **COP** may be COP = 4.0.

As does the skeptical scientist, the electrical engineering community erroneously assumes that an inert electrical power system that outputs more energy than *one oneself* inputs to it — e.g., a generator outputting more EM energy flow than the magnitude of the mechanical energy input to the generator shaft — is against the laws of physics. To the contrary, it is permitted by the laws of physics and thermodynamics, *once the modern* ***Vacuum*** *interaction is included and disequilibrium exists in the interaction* ***between*** *vacuum and system.* Not only is it permissible, it is a universal fact once the arbitrarily discarded Heaviside energy flow component is re-ac**counted,** and the source charge problem is reluctantly placed back on the table. If we account all that EM energy pouring freely from the source charges in any EM circuit, then the actual output of EM energy from that circuit is enormous. It is many orders of magnitude greater than the magnitude of the input energy that the experimenter or operator provides.

We do not have to reprove the active vacuum; it has long been proven in particle physics. We also do not have to reprove the disequilibrium between electromagnetic systems and the active vacuum environment; that also has been proven since 1957 by the prediction and discovery of broken symmetry. One of the proven broken symmetries is that of opposite charges, such as are on the ends of a dipole. Hence every dipole or dipolarity in electromagnetics already freely absorbs virtual photon energy from the vacuum, transduces (coherently integrates) it into observable photon energy, and re-emits observable EM photons in all directions at the speed of light. If there are no COP>1.0 Maxwellian systems, then there can be no Maxwellian charges, dipoles, or dipolarity, and therefore no resulting fields and potentials from these sources — an absurdity falsified by every standard two-wire electrical circuit and ever charge and dipole in the universe. Any potential is a dipolarity, hence exhibits broken symmetry. That is why from any finite potential, as much EM energy as desired can be intercepted and collected, by the simple equation $W = \phi q$, where W *is* the collected energy in joules, ϕ is the scalar potential intensity in joules per unit point static coulomb, and q is the intercepting charge in coulombs.

Systems far from equilibrium in their energy exchange with their active environment {651a, 651b} can permissibly perform five important functions impossible to equilibrium systems. Such a disequilibrium system can:

(1) Self-order,

(2) Self-oscillate or self-rotate,

(3) Output more energy than the operator inputs (the excess energy is freely received from the active environment),

(4) Power itself and its load (all the energy is freely received from the active environment), and

(5) Exhibit negentropy.

Any charge or dipole already exhibits all five of these functions — forbidden by classical thermodynamics but permitted by the well known thermodynamics of systems far from equilibrium in their exchange with their active environment {651a, 651b}.

It *only takes one small white crow to prove that not all crows are black.* The known performance of the charge and the dipole totally refutes the notion that no EM system can output energy without operator-arranged input from other than the active vacuum. The entropy-consuming reactions from the fluctuation theorem, experimentally proven by Evans et al. in 2002, also is a sufficient proof to destroy any argument against permissible COP>1.0 EM systems. Since all the EM field energy and potential energy in a power system or circuit must come from the source charges and dipoles, it follows that all our EM energy systems already take *all* their EM energy from the active vacuum, *not* from the operator's input. A solar cell array also refutes the notion that the operator has to input the energy, but the solar cells' environmental energy input may not be ubiquitous or dependable. The active vacuum is both.

Most power system electrodynamicists avoid the particle physics solution {652} to the source-charge problem {641} involving disequilibrium exchange with the active vacuum. Instead, they adhere strictly to the Maxwell-Heaviside-Lorentz theory with its *assumed* equilibrium between system and vacuum. Therefore they avoid modeling the vacuum interaction and solving the problem of open dissipative EM systems which freely and dependably receive energy from their vacuum environment in unusable form, translate it into usable form, and furnish it for further capture and use. They therefore cannot resolve the source charge problem in their model, for the model has already artificially excluded the solution.

By definition, an EM system in equilibrium cannot output more useful energy than the operator inputs. However, considered as an *energy* ***transducer,*** every EM system is in disequilibrium with the vacuum **because** of the charges and dipoles in the system, and it continuously receives energy from the vacuum. Because of the broken symmetry of the charge and the dipole, some of this energy from the vacuum is discharged by every charge and every dipolarity in the circuit as observable energy *a priori.* This creates a truly enormous outpouring of rather disorganized (in this case, *uncollected)* EM energy extracted from the vacuum and poured out without being intercepted and diverged into the circuit, where it is organized for dissipation and use. The circuit "uses" only that amount of this enormous available outpouring EM energy that it first organizes (collects) and directs. That is its "organized excitation" energy, commonly known as *input energy* macroscopically — the Poynting energy flow component.

Upon completely discharging its excitation (input energy), the inert system outputs all its received (organized) energy, from whatever source. So every EM system already outputs far more energy than the experimenter inputs — when the system's *nondiverged, non-organized, and nondiverged* output energy flow is considered as well as its *diverged, organized, and collected* energy flow component. The fact that the *diverged Poynting* energy received in the external circuit enters the circuit from the surrounding space is shown by Krauss {653} (See Figure 1-1 in Chapter 1). We show it in Figure 2-4 of Chapter 2 as well. The remaining and nondiverged Heaviside energy flow component in space, which misses the circuit and is wasted, is also shown in Figure 2-4 of Chapter 2 and contrasted to the diverged (caught) Poynting component. To understand this experimentally demonstrable fact {653}, we need a bit of EM history.

11.3 Truncations of Maxwell's Theory and Discard of System Classes

11.3.1 Concept of EM Energy Flow Through 3-Space

The concept of the connection of EM energy and space did not occur until 1876 in a faulty work by Croll {654}. In the 1880s Heaviside {655} showed the huge nondiverged component filling all space around a circuit (see Figure 2-4 in Chapter 2). Poynting {656} never even considered the external nondiverged flow missing the circuit, but assumed only the *diverged* energy flow component that enters the circuit. Figure 2-4 in Chapter 2 shows both components of EM energy flow laterally, so they can be seen clearly.

It is stressed that the Heaviside nondiverged component of EM energy flow around every circuit is far greater (by many orders of magnitude) than the circuit's intercepted, diverged, and collected Poynting energy flow component. This follows from Heaviside's own original papers. So when the entire output energy flow is considered, every generator and every battery is already a $COP \gg 1.0$ *energy transducer,* outputting far more energy flow than the rate at which mechanical energy is input to the generator shaft or the rate at which chemical energy is dissipated in the battery.

In the 1880s the electron, atom, nucleus, special and general relativity, quantum mechanics, quantum electrodynamics, and active vacuum had not been discovered. There was no knowledge of any possible active vacuum interaction source for such an enormous energy flow pouring from the terminals of the generator or battery and surrounding the circuit, filling all space around it. Heaviside's extra energy flow component was thus shocking and inexplicable, smacking of "perpetual motion" and total violation of the conservation of energy law. Heaviside — a brilliant, self-taught hermit who never attended university - spoke cautiously and obliquely of its magnitude in terms of angles with respect to a reference direction {657}.

11.3.2 Elimination of the Non-Intercepted Energy Flow Component

A perplexed and concerned Lorentz {658} cut the Gordian knot and arbitrarily *discarded* the Heaviside nondiverged component, eliminating the quandary. Lorentz stated that the huge nondiverged component had "no physical significance" (his phrase) since it powered nothing. Of course it **has** no physical significance, and powers nothing, unless one intercepts it and uses it!

By analogy, the component of a great wind on the ocean that is *outside* the intercepting sails of a single sailing ship, does not contribute to further powering *of that ship.* Figure 2-5 in Chapter 2 shows that situation. However, that nondiverged wind component can power a whole flotilla of ***additional,*** *separate* sailing ships with separate sails, as we showed in Figure 2-6 in Chapter 2. Electrodynamicists {659} have continued to utilize Lorentz' clever integration trick (Figure 2-3 in Chapter 2) to dispose of the huge nondiverged Heaviside energy flow component surrounding **every** circuit and missing it, and therefore pouring from the terminals of every generator. Most electrical engineers today do not realize that the original purpose of Lorentz's integration of the energy flow vector around a closed surface assumed surrounding every volume element of interest was merely to get rid of that perplexing and bothersome Heaviside nondiverged energy flow component while retaining the Poynting diverged energy flow component.

11.3.3 Lorentz's Previous Discard of all COP>1.0 Maxwellian Systems

Previously (circa 1890s) Lorentz had symmetrically regauged Heaviside's **equations** that had already seriously curtailed Maxwell's seminal equations of 1865. This Lorentz symmetrical regauging retained only that class of EM systems that are in equilibrium in their seething energy exchange with their active vacuum environment. It discarded that entire permissible class of the Maxwell-Heaviside systems far from equilibrium with the active vacuum. In short, it *arbitrarily* discarded all COP>1.0 Maxwellian **systems,** and all those even *permitted* to exhibit COP>1.0.

The ubiquitous use of closed current loop circuits containing both the ex**ternal** circuit and the source dipole inside the generator forcibly applied (and continues to forcibly apply) the Lorentz symmetrical regauging. Thus all electrical engineers began using circuits which self-enforced equilibrium in the vacuum exchange, so that no *net usable* energy[306] that could translate electrons and do work in an external load —could be received from that source.

However, so long as the enormous Heaviside nondiverged energy flow component outside the circuit remained, then separate outrigger antenna circuits and systems could always be inserted in this external energy flow to divert some of it into separate additional circuits. This would have opened up the COP>1.0 *ensemble* of systems and separate outrigger receiver circuits (with separate loads) fed by a single central generator, such as one version of the motionless electromagnetic generator of Chapter 7.

Consequently Lorentz integrated the entire energy flow vector around a closed surface assumed around any volume element of interest {658}, as shown in Figure 2-3. This integration trick — still universally applied {659a-659c} in all the texts today — arbitrarily discarded that troublesome and massive Heaviside energy flow component that could not be explained, and for which no source was known.

---

[306] Lorentz symmetrical regauging does indeed require that the system receive excess energy from the environment (the active vacuum). It requires that the potential energy of the system is changed twice and continuously, which means the excess energy in each of those two changes must continuously enter from the active vacuum and do internal work on the system. Two new free force fields are created, each with its field energy, which is additional energy being continuously dissipated in the circuit to perform continuous work. However, the two free changes of energy in the system have been precisely selected so that these two force fields are equal and opposite. The two free changes of energy thus produce a *stress potential* without a net translation field. This means that the local spacetime has been curved, in a manner representing a rotation of the system frame away from the lab observer's frame. Further, the stress potential represents the continuous entry of extra stress energy from the vacuum, whose two force fields continually perform opposing local *internal work* within the system to stress it, while unable to translate electrons and power external loads. Contrary to the received view, the Lorentz-regauged Maxwell-Heaviside system is a dramatically altered and different system than the original system before the arbitrary application of the Lorentz condition. The system's inertial frame has been rotated, it has taken on extra energy from the vacuum that can only be used to do internal work upon the system, and that internal work on the system is continuously being done to increase the system's stress and hold it at the new level.

11.3.4 The Heart-Breaking Result of Lorentz's Actions

The combination of these two actions by Lorentz — symmetrical regauging of the model equations and discarding the excess Heaviside nondiverged energy flow component — unwittingly resulted in the design and building of only those electrical power systems which symmetrically and automatically regauge their discharge of their excitation energy. The symmetrical regauging is self-applied by the closed current loop circuit. That circuit uses half of its collected Poynting energy to destroy the source dipole in the generator, and the other half to power the loads and losses in the external circuit {660}. Conventional EM systems are unintentionally designed to destroy their own source dipoles — and their free extraction of organized EM energy from the vacuum — faster than they power their loads.

11.3.5 Agreement with Classical Equilibrium Thermodynamics

These curtailments of Maxwell's theory resulted in the exclusive building of equilibrium EM systems. These systems obviously obey the classical equilibrium thermodynamics with its infamous second law. Lorentz had unwittingly discarded all that entire class of Maxwellian systems in disequilibrium in their exchange with their active vacuum environment; in those days, there was nothing known about an "active vacuum environment" or broken symmetry in its virtual energy flux. Consequently, Lorentz had discarded all those Maxwellian systems that *do not* obey classical equilibrium thermodynamics, but do obey the newer thermodynamics of systems far from thermodynamic equilibrium with their active environment. He discarded all permissible COP>1.0 Maxwellian systems.

However, there was a total agreement between all the EM systems actually built using Lorentz's symmetrized equations and all measurements in their ubiquitous closed current loop circuits — all self-enforcing the Lorentz condition. This led to the iron dogma that all EM systems must inevitably comply with classical equilibrium thermodynamics — the circuits that were built *were* repeatedly and universally observed to do so!

11.3.6 Dogma that COP>1.0 EM Systems are Perpetual Motion Machines

Finally, this total agreement (now for more than a century) between the theoretical model used, the circuits actually built, the measurements performed, and classical equilibrium thermodynamics led to the present fallacious but iron dogma that EM circuits and power systems cannot output more energy than we ourselves input. Today the vast majority of scientists consider it absolutely proven that the laws of nature prohibit

COP>1.0 electrical power systems, and particularly prohibit self-powering systems that freely power themselves and their loads (i.e., EM systems analogous to "windmills in a free wind"). As we stated, every charge and dipole falsifies the "COP>1.0 EM systems are impossible" dogma, as does the fluctuation theorem and its experimental proof by Evans et al.

Sadly, no one seems to have realized that we do not presently have COP>1.0 electrical power systems only because engineers have specifically designed and built their EM systems to destroy their own source dipole faster than they power their load. Ironically, every circuit and every power system used and measured by our engineers already outputs far more EM energy than is input by the operator or by turning the shaft of the generator, if the Heaviside nondiverged energy flow component is re-accounted. The Bohren experiment clearly proves it experimentally {662}, along with thousands of other similar experiments in "negative resonance absorption of the medium" {157a-157d).

11.4 Examples of COP>1.0 Electromagnetic Systems

The motionless electromagnetic generator (MEG) {661} (Figure 11-1) does catch and use some of this available free energy, as explained below. So does the familiar Bohren experiment {662a, 662b} by resonating each intercepting charge so it sweeps out an increased geometrical reaction cross section in space, reaching past the usual Poynting interception cross section (for a static charge) and thereby absorbing additional energy from the otherwise non-intercepted Heaviside energy flow component.

Every charge and dipole in the universe also already acts as an electrical "windmill in a free wind," having a COP = oo.

The present author has also nominated the long-neglected but vast nondiverged Heaviside EM energy flow, accompanying every field and charge interaction, as the long-missing source of some 90% of the gravity holding the arms of the spiral galaxies intact {663}. Our *supersystem* examination of several COP>1.0 EM systems developed by various inventors has also uncovered a proposed solution for the source of the distant antigravity accelerating the expansion of the universe {664}.



Figurei 11-1. Transformer section of the MEG.

Experimental proof that EM energy COP>1.0 is both possible and demonstrated is already in the literature — e.g., as in the Bohren experiment {662} which outputs 18 times as much energy as one inputs (see Figure 11-2). As another experimental example, the Aharonov-Bohm (AB) effect {647, 665, 666} freely adds additional nonlocalized field-free A-potential energy while all the magnetic B-field energy is sharply localized but still present and available. The AB effect is routinely implicated in physics, but apparently was never applied in an electrical power system prior to its use in the motionless electromagnetic generator

Bohren's experiment {662} was quickly and independently replicated by Paul and Fischer {667}. It can be replicated by any university laboratory at will, totally negating the conventional COP < 0 assumption. The AB effect is also easily replicated, using a toroidal coil, a long solenoid, or a permanent magnet and the special cores used in the MEG. When the toroid system's *total available output energy flow* is measured and accounted — including both the confined magnetic field energy flowing inside the toroidal windings and the field-free A-potential flowing outside — the toroidal coil system outputs more energy flow than the operator furnishes from his external power supply by conventional accounting {668}.



At or near resonance frequency, in the case shown the energy collection fraction (reaction cross section) increases dramatically.

Figure 11-2 The Bohren experiment outputs 18 times as much energy as one inputs

In conventional terms, for a theoretically perfect toroid the operator only "pays for" the magnetic field energy "output component" confined inside the toroidal windings. The presence of an extra energy output component outside the toroid produces COP>1.0 performance as *an energy transducer.* It *does not* produce system COP>1.0 performance in a closed-loop circuit containing the primary power supply's source dipole.

The AIAS has previously nominated more than a dozen mechanisms as promising COP>1.0 systems for investigation, research, and development {669}.

11.5 Motionless Electromagnetic Generator (MEG)

11.5.1 Overall Description

In the MEG {661} (Figure 11-1), one uses a nanocrystalline material core path with the unique characteristic of drawing in almost all the magnetic field energy of an emplaced permanent magnet. The B-field flux from the magnet is withdrawn from its normal position in surrounding space and sharply confined to that material core path. Around the core there freely appears an *additional* curl-free magnetic vector potential A energy flow, since the surrounding spacetime is still curved due to the interaction exchange of vacuum and magnet dipole, and therefore still contains extra energy. The operator inputs no energy whatsoever after the magnet is once emplaced, yet has appreciable magnetic field energy and field-free magnetic vector potential energy available to utilize. As an *energy transducer*, the MEG has a $COP \gg 1.0$. As a power system powering loads, its $COP > 1.0$.

11.5.2 An Example of MEG Operation

As a replicable example, suppose one operates the MEG core at less than saturation, and places a small "square wave" pulsed signal upon a primary coil wound around the core. The core changes its permeability as the internal magnetic B-flux is perturbed and changes, so all the perturbed B-flux is retained in the core material. The large E-fields produced by the changing B-flux in the core as a function of $-\partial \mathbf{B}/\partial t$ are *not* localized, but pass readily out of the core and interact with the coils, particularly with the secondary.

In the A-potential region in the space outside the core, one also produces very large E-fields by $\mathbf{E} = -\partial \mathbf{A}/\partial t$. At the frequencies being used (40 to 80 kHz nominally), all these E-fields produced by the core flux perturbations and by the external A-potential perturbations are essentially in phase. The large E-fields thus coherently add and interact directly with the secondary coil acting as a receiver.

In the secondary, the very large and sharply changing E-fields interacting with the coils also produces large B-field flux changes in the core. However, again the core changes its permeability and holds-in all the extra B-flux. The changes in that secondary B-flux also make additional non-localized E-fields, and so on.

The surprising and shocking result is that the transformer secondary undergoes a coherent, purely E-field reaction with the electrons in its coils. This results in the output voltage and current being in phase (within 2°, since there are inevitably some small remaining inductance effects due to a tiny bit of external B-field leakage from the junctures of the ends of the permanent magnet with the core material).

The magnitude of the powerful E-fields produced by these processes — and interacting with the secondary coils — depends on the rise and decay times of the input signal's pulse edges. So the *average* power input to the signal coil may be small, but — using sharp rise and decay times of the input pulses — very large E-fields will be produced in the adjacent surrounding space outside the transformer section and interacting with the secondary coils, as well as in the sharply changing B-flux localized in the core.

One then uses transmission-reception theory and near-field antenna theory for separate receiving circuits containing loads, added in the large E-field region in space outside the core. Those E-fields arise from both the changing A-potential outside the core and the changing localized flux inside the core. We stress again that the E-fields produced in the core are not localized, but pass outward into the external space to interact with whatever interceptor/receivers are placed out there.

A "outrigger array" version of the MEG uses separate external receiving circuits, containing loads, to intercept, collect, and use more of the EM energy available in the surrounding space outside the core.

Within physical space limits, the energy intercepted and utilized by these *separate, independent receiving circuits containing loads* can be increased by adding more receiving circuits with loads or adjusting the rise and decay time of the input pulses to provide greater collected voltage. These *separate* loads will be powered by the incident E-fields' interception in the external receiving circuits. This is not at all a *transformer* action, but a *near-field transmission and separated multiple antenna circuits' reception* action.

There is no back-current coupling between the external circuits and loads with the primary circuit of the transformer section. In the external A-potential region alone, the secondary coil in the transformer section will interact with the large incident E-fields from that adjacent space and from the changing B-flux inside the core, producing at least as much energy as one inputs to the primary. Actually, that process alone will produce more output energy in the secondary than the operator inputs in the primary.

If one operates the core below saturation, the magnetic flux in the core will also be switched, giving additional intercepted E-field energy in the secondary coil attached to its load. The total work out in all loads is permissibly greater than the total energy dissipated in the input by the operator's energy input {668}. The MEG is an open system far from equilibrium with the active vacuum {670}.

11.5.3 The MEG Is Replicable

Any university laboratory can replicate this effect, and demonstrate more work in resistive loads than is input to the MEG primary from the external power supply. For replication, we suggest initially designing to COP = 1.5, since beginning at COP = 2.0 there *can* be other effects not in the U(1) EM literature, but which are dealt with in the actual MEG. Some of the methodology {671} used for COP >2.0 is still proprietary information not yet releasable due to patent law requirements, while some of it was included in Chapter 7.

Without elaboration we advance the *supersystem* concept, and strongly insist that, to properly analyze the performance of any similar EM circuit or system, one must analyze the dynamics of the entire supersystem consisting of (i) the physical system and its dynamics, (ii) the curved local spacetime and its dynamics, and (iii) the local vacuum and its dynamics {672}. All three components of the supersystem are mutually interacting.

For a COP>1.0 system, the mutual interactions are utilized from disequilibrium processes evoked between all three supersystem components. U(l) electrodynamic analysis system in an inert vacuum and a flat spacetime is insufficient. Previous AIAS analysis {661} has addressed the supersystem by use of higher O(3) symmetry electrodynamics to include vacuum dynamics (energy currents, both space-like and time-like) and curved spacetime dynamics.

11.6 Physical Considerations of Gauge Freedom

Additional physical considerations must be accounted when *gauge freedom* is invoked or utilized with respect to physical systems. Applied to electrodynamics systems, gauge freedom assumes the ability to freely change any potential of the system being studied. From the physics of the situation, a system potential change concomitantiy assumes changing the *potential energy ofthe system itselffor* which gauge freedom changes are being theoretically applied to system-descriptive equations.

If one *can freely increase* the potential energy of an EM system, the extra energy has to come from a physical asymmetry of the system with its active environment — the active vacuum. Else, one must surrender the conservation of energy law. At worst, gauge freedom would then imply the creation and destruction of energy at will. At best, it would imply a return to the view that potentials are mere mathematical conveniences with no physical reality — a notion falsified for decades by the AB effect {647}. ***freely** decreasing* the potential energy of the system by simply depotentializing it, has a similar vacuum asymmetry requirement for de-excitation of the system, where energy must flow from the system to the vacuum.

11.7 Special Modeling of the Vacuum

Having EM energy density, the vacuum *is and should be modeled as* a scalar potential of great magnititude. For deeper (supersystem) analysis, one will also have to examine the internal EM longitudinal phase conjugate wavepair structure and dynamics of the scalar potential vacuum {672}, along the lines shown by Whittaker {644} in 1903 and re-interpreted by the present author {643} in 2000. From quantum field theory arguments, Mandl and Shaw {646} give strong support to the proposed reinterpretation. They argue that neither the scalar (time-polarized) photon , nor the longitudinal photon is independently observable, but the combination of the two is observable as the instantaneous scalar potential.

Transforming this argument to EM waves yields a solution consistent with the reinterpretation {643}. The result is that all 3-space EM energy comes from the time-domain, in a manner not previously utilized in EM circuit analysis. It is experimentally established by proving (measuring) that the source charge and dipole do not *receive ob*servable EM energy in 3-space, but continuously *output* observable EM energy in 3-space. Simply making and destroying dipoles in an electrical system turns out to be a method for direct engineering of negentropy and entropy respectively — or, from another viewpoint, it directly engineers regauging.

The greatest unrecognized problem in conventional electrical power system engineering is its total failure to include the making and destroying of dipoles as direct engineering of negentropy and entropy respectively.

Every EM potential in an EM system is a change to the energy density of the ambient vacuum potential — and thus is a spacetime curvature — or it is a change to an intermediate potential that *is* such a vacuum potential change. Vacuum exchange with every EM system and asymmetry in that exchange, is ubiquitous and cannot be prevented. Whenever one makes or changes an EM potential, field or wave, and whenever one regauges, one invokes and utilizes asymmetry in the interaction of the active vacuum and the system, either wittingly or unwittingly. Else one must discard the conservation of energy law altogether. There is no symmetry of a mass system alone {673}, without including the vacuum's asymmetrical interaction with it. The reason is simple: all observables involve asymmetry {674} *a priori,* and mass is an observable.

11.8 Every Charge and Dipole in an EM System Receives and Transduces Vacuum Energy

In particle physics, every dipole — and every charge considered with its associated clustering virtual charges of opposite sign — is recognized as an asymmetry in the vacuum flux {675}. The very definition of broken symmetry means that a charge or dipole receives and absorbs virtual photon energy from the vacuum, transduces it into observable form, and re-radiates it as real, observable EM energy. This results in an observable outpouring of 3-energy from the charge or dipole, with no observable 3-energy input.

To save the conservation of energy law for physical EM systems, one must therefore recognize and model the *physical vacuum asymmetry mechanism* **that** allows this demonstrated performance of charge and dipole. In electrical power systems, that required asymmetry mechanism is the known broken symmetry of the vacuum's interaction with the source dipole created in the generator.

11.9 Energy from the Vacuum Powers Every Electrical Power Line and EM Circuit

11.9.1 What the Generator Powers and What Powers the Circuit

Shaft power input to a conventional generator allows the generator to **produce** its source dipole, nothing else. The generator does not transduce any of its input shaft mechanical energy to add EM energy to the external circuit connected to its terminals. Instead, it first transduces its mechanical shaft energy input into internal magnetic field energy.

Then it totally dissipates that magnetic energy to separate its own internal **charges,** forcing the positive charges in one direction and the negative charges in the other, making the source dipole connected to its terminals. That is all that the mechanical shaft power input to a generator does — and **that** is all that burning hydrocarbons, consuming nuclear fuel rods, **damming** rivers for power stations, putting up windmill-powered **generators,** using solar energy input to solar cells, or consuming chemical energy in a battery accomplishes.

O*nce made,* the source dipole — via its broken symmetry in its vacuum exchange - freely receives and absorbs enormous virtual photon energy **from** the active vacuum, transduces it into observable (3-space) form, and pours out real, observable EM energy in 3-space from the generator terminals to which it is connected. As shown in Figure 1-1 of Chapter 1, this outpouring of EM energy from the generator terminals fills all space around the external circuit {653} with a vast energy flow almost parallel to the conductors. Figure 2-4 is a lateral view so that the two flow components can be clearly seen and compared.

11.9.2 Gedanken Experiment

We advance a gedanken experiment to illustrate. Consider a perfect generator with no losses, and with two perfect conductors and a purely resistive load R_1 connected across its terminals. Call the mechanical energy input to the shaft of the generator W_{in}. Call the Poynting diverged energy flow component W_r that is intercepted by the attached circuit and powers R_1. Call the Heaviside nondiverged energy flow component W_h that misses the circuit and is wasted. As an *energy transducer,* the total energy output W_{out} from the terminals of the generator is

$$W_{out} = W_r + W_h \qquad [1]$$

However, $W_{in} = W_r$, for this theoretically perfect system. So

$$W_{out} = W_{in} + W_h \Rightarrow W_{out} > W_{in} \qquad [2]$$

Further, when accounted, $W_h >> W_{in}$, so

$$W_{out} >> W_{in} \qquad [3]$$

We conclude that all EM systems — *as energy transducers freely extracting and transducing EM energy from the active vacuum*— already exhibit COP » 1.0. However, for *useful work* in a closed current loop circuit, the COP = 1.0, unless additional antenna-receiver circuits or another scheme such as Bohren charge resonance is used to increase the energy collected and dissipated in the load while *not* increasing the energy used to dissipate the source dipole.

11.10 Significant Developments in Negative Resistance

True negative resistance (e.g., current moving against the voltage) also exists and is experimentally replicable. In true negative resistance, the current in a circuit moves against the voltage instead of with it, suggesting time-reversal effects in the mechanism by which EM force and charge interact.

11.10.1 Chung's Negative Resistor and Naudin's Replication

Chung {676} has reported replicable negative resistance in the interfaces between layers of carbon fibers in a composite material. By varying the pressure used when the fibers are made, the resistance can be controlled to later be negative or positive as desired. A simpler version of Chung's negative resistor using off-the-shelf materials has been successfully replicated and tested by Naudin {677}. (See Figure 11-3). Naudin's website {677} provides measurements and full details necessary for repetition. He also includes sources of the carbon fiber materials needed for independent replication.


Tek Hold 250 S/s
23 Acqs
0.000 VDC
Junction Voltage
Resistance Voltage
A
B
C
D
Chung's Negative Resistance V2.0
Jean-Louis Naudin - May 19th, 2001
Ch1 2 V Ch2 5mV M 1 s Ch1 ∕ 320m
CNR v2.0 - HIGH PRESSURE JUNCTION NEGATIVE RESISTANCE
The Chung's Negative Resistance experiment
By Jean-Louis Naudin - May 19th, 2001
Email: Jnaudin509@aol.com - http://go.to/jlnlabs/
TEST CNR v2.0

Figure 11-3 Naudin's replication of Chung's negative resistor.

11.10.2 The Point Contact Transistor

There is also evidence that the original point contact transistor — which used spring pressure on the point contact — often exhibited true negative resistance. Certainly this transistor was never adequately understood {678}, and it is not understood today, since its supersystem has never been analyzed.

11.10.3 Kron's Negative Resistor

Gabriel Kron, early pioneer in electrical systems theory, reported **developing** a negative resistor in the 1930s, on the U.S. Navy's Network Anayzer project {679} at Stanford University. He was not permitted to reveal the details of his negative resistor, but did provide strong hints in certain statements in his papers in the literature {680a, 680b}. His method for a self-organizing network depended on his "open path" {681} which he also was not permitted to reveal.

The present author worked for some years with Floyd Sweet, a Kron protege", who did produce a successful type of powerful negative resistance system {682} known as the vacuum triode amplifier, apparently based on Kron's original negative resistor. See Figures 6-5 to 6-13 in Chapter 6. As shown in Figure 6-6, Sweet induced self-oscillation in barium ferrite magnets {683a-683c} (which are made by powder metallurgy methods using pressure applied during their manufacture) and extracted energy by induction from the resulting self-sustained magnetic field oscillations. His device was independently tested by Walter Rosenthal {684}, a senior test engineer of long experience with a major aerospace company. See Figure 6-9 and Figure 6-13.

11.10.4 Proposed Time Reversal Zones and Effects

One may take the view that true negative resistance involves time-reversal, which by the Pauli exclusion principle is permitted for bosons {685} and possibly for fermions in even numbers, acting as quasi-bosons (perhaps only possible in a time-reversed zone). The present author proposed a photon interaction mechanism for the "flow of a mass through time" in 1971, with initial publication occurring two years later {686}.

Extending this mechanism, the author proposed that *time reversal zones* (TRZs) can occur in momentary local regions in semiconducting materials or electrolytes {687}. In a TRZ, the law of attraction and repulsion of charges is hypothesized to be momentarily reversed due to time-stress or time-domain pumping {688}, and like charges may momentarily attract. In Chapter 10, we used these time-reversal zones to explain the anomalous results of the 600 or so successful cold fusion experiments worldwide. We also gave the exact new nuclear reactions for the production of anomalous deuterium, tritium, and alpha particles in many of these experiments.

When under strong stress, anomalous attraction of clusters of like charges is experimentally known, e.g. in Shoulders' {689} experiments and patented processes {690}. When the output leads of Sweet's vacuum triode amplifier device were suddenly shorted, extreme cooling occurred rather than heating. Ice condensed instantly upon the shorting contact and leads from the sudden extreme cooling of the metal in the moisture in the air, dramatically showing a converging EM energy process rather than a diverging one.

11.10.5 Effects in Optically Active Semiconducting Materials

In addition, four-wave-mixing, phase conjugation, and time-reversal effects are well known in semiconducting materials {691}, almost all of which are optically active. Optical activity and microlasing is known in semiconductor powder {692}. Further, the vacuum itself can exhibit semiconducting properties {693}.

11.10.6 Special Functions Produced by Stress

Apparently pressure (stress) in many of these devices and experiments can play an important role in the negative resistance process. Based on harmonic sets of paired couplings of a longitudinal time-like wave and a longitudinal wave in any scalar potential {643}, the present author hypothesizes that such stress — treated as a stress scalar potential — accomplishes time-domain pumping in the optical sense, due to the presence of the coupled time-polarized longitudinal waves in the time domain.

This time pumping is a special form of "time stress". Thus in optically pumped or stressed optically active materials (including electrolytes), the time-stress creates a TRZ, reversing the normal force laws upon and between charges. Assuming this hypothesis is valid, this could account for the variation of Chung's negative resistance effect with the variation of the pressure (stress) used in manufacturing. It would also apply to the laser-**created** stress in semiconducting powder experiments, etc. The hypothesis should be further investigated for experimental validation or refutation.

11.11 In Conclusion

As Penrose {694} states,

> *"Electromagnetism is a subject that is in no way closed to stimulating new developments."*

Indeed, electrodynamics is still very much an advancing subject, and in classical electrodynamics there are foundations errors and problems, a few of which we have addressed. As Bunge {695} pointed out more than three **deca**des ago,

> *"...it is not usually acknowledged that electrodynamics, both classical and quantal, are in a sad state. "*

From a foundations viewpoint, Einstein {696} beautifully summed it up — and advanced a requirement for continually examining the foundations of electrodynamics and every other field of physics — in these words:

> *"..the scientist makes use of a whole arsenal of concepts which he imbibed practically with his mother's milk; and seldom if ever is he aware of the eternally problematic character of his concepts. He uses this conceptual material, or, speaking more exactly, these conceptual tools* ***of thought,*** *as something obviously, immutably*

> *given; something having an objective value of truth which is hardly even, and in any case not seriously, to be doubted. ...in the interests of science it is necessary over and over again to engage in the critique of these fundamental concepts, in order that we may not unconsciously be ruled by them."*

Though they have long been neglected, legitimate COP>1.0 electrical systems are good science, or they can be. They were present in the original Heaviside truncation of Maxwell's theory prior to Lorentz's symmetrical regauging. That regauging arbitrarily selected only those Maxwellian systems in equilibrium in their exchange with the active vacuum. The energy flow theory was further curtailed by Lorentz's integration trick, which discarded the huge vacuum-furnished non-intercepted Heaviside energy flow component accompanying every EM system. Every EM system already outputs for more EM energy flow than the energy that the operator inputs; thus every EM system is already a COP»1.0 system, with respect to *energy transduction.* The only way this giant negentropy of every EM system can be hidden is to ubiquitously continue that integration trick to discard the giant Heaviside energy flow component.

The present Lorentz-regauged Maxwell-Heaviside equations are not consistent with *any* bipolar EM system or circuit. The ends of any dipolarity in the universe — including any electron on Jupiter and any positron in the star Sirius — constitutes a broken symmetry in the seething vacuum flux. Actually, that is what Gabriel Kron discovered and called his "open path". Hence, that "dipole" continuously emits observable EM energy extracted from the vacuum.

Engineering use of the ubiquitous closed current loop to contain both the primary source dipole and the load — which destroys the source dipole and extraction of vacuum energy faster than the load is powered — is responsible for the successful predictions of the equilibrium EM model (which of course completely fails to explain the source charge or source dipole). That circuit is unwittingly designed to self-enforce the Lorentz symmetry condition and therefore self-enforce those predictions.

The question as to whether COP>1.0 electrical power systems are possible *and practical* must be resolved by direct experiment, and not by established models and cherished concepts that already arbitrarily exclude such systems! Such theoretical refutation by models that in fact contradict the experimentally observed COP = oo action of every charge in the universe, cannot be trusted at all with respect to COP> 1.0 judgment. Well-known supporting and confirming experiments already in the literature — such as the Bohren experiment yielding COP =18 — have been cited, and these are replicable by any university laboratory. The Bohren-type experiment is well known and routinely performed in every nonlinear optics laboratory, under the guise of "negative resonance absorption of the medium".

It is indeed a critical time to re-examine the foundations of our electrical **power** science and engineering, along the lines so eloquently stated by Albert Einstein. With the impending oil crisis, we face a world economic crisis of epic proportions unless we rapidly develop and widely deploy sell-powering disequilibrium electrical power systems.

Also it is a critical time when the leaders of the scientific community — specifically the National Academy of Sciences, the National Science **Foundation,** the great national laboratories, and the universities — must at last face and correct the excruciating *faux pas* that has now been perpetuated in electrodynamic theory for more than a century. In short, the leaders of our scientific community must now show whether they are scientists practicing and upholding experimental basis, or are dogmatists **defending** an ancient faith. The fact that the source charge problem continues to be propagated in electrodynamics 45 years after the award of the Nobel Prize to Lee and Yang, is no longer excusable.

A thorough review and correction of the foundations of EM theory is required for the survival of this nation and much of civilization. It is also required for the cleanup of the increasingly polluted biosphere, survival of the threatened species of the Earth, reduction of present global warming **trends,** and the survival of this fragile and beautiful planet itself.

Annotated Glossary of Selected Terms

action at a distance: An action (effect) occurring in a local system, for which no separate local 3-space cause exists, but for which a causal correlation exists between a distant action and the local effect.

advanced electromagnetic field: An electromagnetic field that is a solution of the classical Maxwell equations, which is positioned on the future light-cone of spacetime. It may be possible to involve such a field in the tempic force that may exist between the tempic potential at the output of an overunity system and the tempic potential that exists at the input of **the** system, where the interaction of the tempic force with the local nonlinear vacuum drives Dirac sea hole current from output section to input section.

advanced electromagnetic potential: An electromagnetic potential that is a solution of the classical Maxwell equations, and is positioned on the future light-cone of spacetime. Presently this potential has not yet been given a physical interpretation. It may be possible to involve its effects in a specific system by our notion and use of the instantaneous tempic potential difference (the tempic force) that may exist between the tempic potential at the output of a system and the tempic potential at the input of that system if the two differ.

advanced electromagnetic wave: An electromagnetic wave that is a solution of the classical Maxwell equations, and which is positioned on the future light-cone of spacetime.

Aharonov, Yakir: Renowned Israeli quantum physicist and former student of David Bohm. Co-discoverer of the Aharonov-Bohm effect. Together with Bohm, Aharonov authored a fundamental paper in 1959 that pointed out the *primary importance of the potentials* rather than the force fields. The force fields are only made in and of the charged particle system itself, and do not exist as such in the vacuum. The force fields are thus not primary electromagnetic causes at all, but are *effects* due to the interference of potentials in a particular charged particle system.

Aharonov-Bohm effect: Quantum mechanical phenomenon theoretically pointed out in 1959 by Yakir Aharonov and David Bohm whereby interfering electromagnetic potentials can produce effects on charged particle systems, even at a distance and in the absence of the electromagnetic force fields. A system undergoing a cyclic evolution from an initial state back to it will acquire a phase difference, which can be detected by interfering the initial and final states. Theory was extended later to Berry phase, then again to geometric phase.

In classical EM terms, a more important *energy-amplifying* principle - advanced by the present author — emerges from the AB effect. My colleagues and I have used this principle in our motionless electromagnetic generator (MEG) to provide COP>1.0. Consider a source of magnetic field B, such as a permanent magnet. All the magnetic field energy B from the permanent magnet may be drawn into and confined in a local material path, as in a special nanocrystalline transformer core. Then in the space surrounding the localized magnetic field energy, the active vacuum will freely replenish — via the broken symmetry of the permanent magnet dipole in its exchange with the vacuum — the magnetic energy in that space that would otherwise have been filled with magnetic field B (curled magnetic vector potential A). However, nature replenishes the energy in space outside the B-localization region with the *curl-free* magnetic vector potential A. In this fashion a system designer may cause the active vacuum to provide more available magnetic energy from the permanent magnet that normal, with each of the two energy forms being in separate spatial regions and paths, and occurring in different forms of magnetic vector potential energy. By inputting only a little energy in the input coils of the transformer section, and controlling the rise time and decay time of the pulses, one can produce very large E-fields from the A-potential via $E = -dA/dt$. From the simultaneously perturbed confined B-field flux in the core, one also produces E-field simultaneously and — at the frequencies used — in phase with the E-fields produced outside the core. The net result is interaction of large E-fields with the output coil, producing an output power *proportional to the rate of change* of the weak input signal energy rather than its magnitude. In this fashion, additional E-field energy from the vacuum enters the output coils to power the secondary circuit and its loads. Also, the output of the entire transformer section has the voltage in phase with the current, in contradiction to the actions of all previous transformers.

AIAS: Alpha Foundation's Institute for Advanced Study, directed by Dr. Myron W. Evans, a noted scientist with more than 600 papers in the literature. The AIAS is an unusual "think tank" comprised of Fellows and Fellow Emeriti in various places in the world, who cooperate in advanced electromagnetics studies via E-mail. The Director, Dr. Myron W. Evans, is a theorist of note, as are several other Fellows. The AIAS has been forging ahead with the production of O(3) symmetry electrodynamics, particularly as an important subset of Mendel Sachs' unified field theory. Dozens of AIAS group-authored papers have been published in various leading journals such as *Foundations of Physics, Physica Scripta,* etc. More than 100 AIAS papers are carried on a restricted Department of Energy website for reference by DoE and AIAS scientists. The work is particularly significant in preliminary theorizing how EM energy can possibly be extracted from the active vacuum.

algebras: The various types of mathematics in which the theoretical models for physics and other sciences are embedded. Some important algebras utilized in physics are vector algebra, tensor algebra, quaternion algebra, Grassmann algebra, Pauli algebra, Clifford algebra, etc. There are many others. The complexity of the symmetry and of the topology varies significantly between these algebras. Thus, an electrodynamics model in a lower topology algebra such as vectors or tensors will not reveal or permit nearly so great a set of electrodynamic functions and operations as will electrodynamics embedded in a higher topology algebra such as quaternion algebra or Clifford algebra. See topology.

ambient vacuum: The average or typical "standard" active vacuum (i.e., active spacetime), removed spatially from any large collections of observable charge and observable mass.

ambient vacuum potential: The *average* or typical standard vacuum considered as a scalar potential because it possesses energy density as well as structure and dynamics on many levels. As a scalar potential, the vacuum potential (considered without zero-point fluctuations) decomposes into a harmonic set of "bidirectional" longitudinal EM phase conjugate wavepairs, by Whittaker's 1903 decomposition as reinterpreted by the present author in 2000. Dynamic structuring of the vacuum thus consists of dynamics impressed upon these wavepairs. Since the vacuum is observably mass-free, Whittaker's phase-conjugate half of the decomposition must be considered prior to its interaction with mass, hence in the imaginary plane **and** arising from the time domain. This consideration led to the discovery by the present author of the more fundamental 4-symmetry in EM energy flow between the time domain (imaginary plane) and real 3-space, when broken 3-symmetry is present (as with any dipolarity or with any **potential).**

Powerful support for this solution is also given by F. Mandl and G. Shaw, Quant*um Field Theory,* Wiley, 1984, Chapter 5. Mandl and Shaw argue tthat the longitudinal and scalar (time) polarizations of the photon are not directly observable, but only in combination, where they manifest as the "instantaneous" Coulomb (i.e., electrostatic) potential. Our comment is that this argument, translated from particle terminology to wave terminology, directly fits our re-interpretation of Whittaker's 1903 decomposition of the scalar potential.

angular momentum: The momentum or "leverage" of the linear momentum of a moving body, with respect to an axis or reference point. Angular momentum has the same units as action; that is, it is energy multiplied by time, or momentum multiplied by length. In terms of particles, it is also known as *spin.*

anti-circuits: Somewhat normal-appearing electromagnetic circuits which primarily process and use antiparticles and anti-electrons rather than particles and electrons, or else process a combination of the two simultaneously. Operations of the anti-circuit must be analyzed and understood in terms of its *supersystem* interactions. The circuits process and utilize both negative energy and positive energy EM fields and potentials, hence are closely connected to unified field engineering and antigravity. One aspect enabling such circuits is the use of the supersystem's curvatures of spacetime in both negative curvature and positive curvature fashion so that an appropriate change of spacetime curvature precludes the radiation normally accompanying pair annihilation, etc. The key to the circuits is T-reversal and C-reversal operation, along with the matching use of spacetime curvatures, and also the use of the Dirac "positron" (negative energy electron) — and its fields and potentials — prior to its observation. The unobserved Dirac negative energy electron in the vacuum is an entirely different entity than is the observed Dirac positron after its interaction with charged matter, after which it has become a "lattice hole" or "positive charge on a positive mass ion". The response of normal circuit components to vacuum Dirac sea hole operations is dramatically different than for Dirac positrons, and for certain applications special versions of circuit components are required. At this writing, together with John Bedini the present author has submitted what may be the first patent application on the fundamental process for anti-circuits and their operations with antimatter and negative energy currents, fields, and potentials as well as matter and positive energy currents, fields, and potentials. Another patent application by this author **is** in preparation, covering the anti-gravity aspects. The details of these mechanisms are still proprietary at this writing in order to protect our intellectual property rights, but limited information is in this book.

anti-electron: A negative-energy electron, observed as *a positron.* Under time reversal, electric charge reverses in sign. Dirac did not predict the positron per *se,* but a negative energy electron that we would *observe* in reversed fashion. Present theorists assume the interaction of the 4-space negative energy electron with matter — i.e., observation — to have occurred. This transforms the negative energy, negative mass electron to a positive energy, positive mass positron traveling in the opposite direction. In so doing, antigravity from the negative energy 4-electron source charge, due to its negative energy EM fields and negative energy potentials, is arbitrarily transformed by the spatial reversal into positive gravity fields rather than the antigravity fields they were. The secret to practical antigravity is to utilize (in anti-circuits) the negative energy 4-electrons prior to observation, *without* transformation of (i) negative energy fields to positive energy fields, (ii) negative mass to positive mass, and (ii) reversal of the field direction. In short, simply consider the unobserved negative energy 4-electron as what it is, and utilize it in its unobserved vacuum state. The conventional transformation process also unwittingly discards the concept of anti-circuits, anti-fields, anti-potentials, and anti-currents, which discards half the rich electromagnetic circuitry that can be built and utilized. In the present book, we only touch lightly on this latter subject, which hopefully will be the subject of a future book after certain patents are filed.

antigravity: Negative gravity or reversed gravity. Use of negative curvature of spacetime to produce a force on a gravitational source (physical system) that is opposite to the normal force of gravity of the earth etc. on that system. Antigravity is achieved by the use of negative-energy, negative-mass source charges in the mass component of the supersystem prior to observation, while the source charges are still 4-spatial. This usage produces negative energy fields and negative energy potentials to negatively curve the local spacetime (ST), so that these negative local ST curvatures interact back upon the positive mass source system associated with the vacuum negative energy sources in its supersystem. Again, to understand the operation of an antigravity circuit or system, one must analyze it in terms of its *supersystem* interactions.

antimatter: Matter consisting of atoms that are composed of anti-electrons (positrons), antiprotons, and antineutrons and such. Also loosely refers to the antiparticle corresponding to a particle; an antiparticle may be regarded as a particle traveling backward in time, or "phase conjugated", or "time-reversed. Since time is not an observable, the observer sees the antiparticle *{after its observation by interaction with mass)* in forward time as being reversed in direction and charge.

antiparticle: Conventionally, a counterpart to an ordinary fundamental particle, *observably* having identical mass, lifetime and spin, but with charge and magnetic moment reversed in algebraic sign. We again point out, however, that the antiparticle differs when in its unobserved 4-spatial state. Only by analyzing the particle's supersystem can the true unobserved antiparticle be understood, as well as its fields and potentials in that condition.

antiphoton: A time-reversed photon. Presently the photon is considered its own antiparticle. *Observably* it is, but in its pre-observation condition it is not. An alternate but as yet unaccepted view is that, since the unobserved photon is comprised of (dE)(dt) — i.e., a piece of energy welded to a piece of time with no seam in the middle, the antiphoton may be assumed to be comprised of (-dE)(-dt) with respect to the external observer.

anti-Stokes radiation: The radiation coming from an anti-Stokes emission process from an intensely scattering medium, wherein more energy flux is emitted than is input by the experimenter-operator. The excess emitted energy is furnished by other processes in the medium. For true overunity operation, the excess energy furnished by the energetic medium must be freely replenished to the medium by the active vacuum's interaction with it.

antiwave: The time-reversal (phase conjugation) of a reference wave.

A-potential: The magnetic vector potential A, conventionally thought to be "defined" by the equation $\mathbf{B} = \nabla\times\mathbf{A}$. However, no equation is a definition (an identity is required). If we replace the "=" sign by "==", we have $\mathbf{B} \equiv \nabla\times\mathbf{A}$, which is actually seen to define the field B as just a curled A-potential, or as the curled component of the A-potential, *after* interaction with magnetic charge. The A-potential or an additional component of it can and does also exist in uncurled fashion, and will emerge in the uncurled state in the space outside any local path (e.g., the path in the interior of a toroidal coil) that retains the B-field therein. That process of separating the curl component of the A-potential from its uncurled component is known as the Aharonov-Bohm effect (which also affects the wave function). The motionless electromagnetic generator (MEG) uses a special nanocrystalline core material in a transformer configuration, which draws in and retains the B-field from a permanent magnet outside the core but firmly in contact with it on both ends. As a result, the vacuum freely replenishes the withdrawn magnetic energy that would otherwise have existed in the space outside the core, but the energy outside the B-field localization zone remains and appears as a separated and uncurled A-potential. In this way, the MEG is converted to an open system not in equilibrium with the vacuum, and can therefore permissibly output more EM energy in its output coils than the operator inputs into the input coils, the excess being freely furnished from the vacuum via the broken 3-symmetry of the permanent-magnet dipole and the resulting 4-symmetry EM energy flow from the vacuum's time domain into the dipole. The MEG is actually a practical macroscopic EM power system application of (1) the well-known Aharonov-Bohm effect and (2) the effect of the separation of the curled and uncurled potentials by a long tight solenoid or by a tight toroid, but in this case by the nanocrystalline magnetic core performing that separation function. In effect, the output coils interact with double (or greater) energy than would be available in just the B-field of the core (and of the magnet). Dual interaction with both theinternal core B-field flux and also the external A-potential is obtained by pulsing, so that the pulse edges produce strong E-fields in space, with the E-fields striking the output coils in a transmission-reception near-field fashion. As is well-known., $d\mathbf{A}/dt = -\mathbf{E}$, and also $f(d\mathbf{B}/dt) = \mathbf{E}$. These two fields produced by the perturbed internal B-flux in the core and the pertubed external uncurled A-potential outside the core are in phase. This is how the extra pulsing A-potential energy outside the core is made to interact as -E-field energy with the Drude electrons in the output coils, while the changing magnetic flux in the core through those coils also simultaneously produces a second -E which interacts with the coil's conductors in normal E-field fashion. The total E-field interacting with the output coils is proportional to the *time rate of change* of the input perturbation signal, not the magnitude of its energy. By adjusting the leading and trailing edges of the perturbation pulses, the magnitude of the E - field interactions with the output coil is determined as desired. Further, the usual output B-field produced in the output coils by dE/dt is directly extracted into the core and held, so that *a purely electrical interaction and output occurs in the output coils*. This is easily shown since the output current and voltage of the output coil are in phase, within a degree or two. The MEG may be said to the world's first purely electrical induction transformer, freely separating the magnetic interactions and bottling them up, while allowing the electrical interactions.

asymmetrical regauging: A change of either the scalar potential ϕ or the vector potential A, or both, so that a *net resulting excess force together with a net change of total system potential energy* occurs in the system. During this change, an asymmetry exists in the active vacuum's energetic exchange with the system. The result is that the potential energy of the system is freely changed by energy from the vacuum, and a free net force is also produced in the system. This new force is then free to dissipate the excess potential energy by translating electrons through a load and powering it. By contrast, the Lorenz/Lorentz *symmetrical* regauging produces two free force fields that are equal and opposite, so there is no *net* resultant translation force available to translate electrons through the external load and power it. Thus Lorentz regauging arbitrarily applied to the Maxwell-Heaviside equations selects only that resulting subset of Maxwellian systems that are in equilibrium in their interaction with the external active vacuum. The potential energy of the system is changed, but only as a "stress potential" doing internal work upon the system to form and maintain its increased stress. The extra energy also rotates the system's frame out of the laboratory frame. Lorentz thus unwittingly discarded an entire class of permissible Maxwellian systems that are not in thermodynamic equilibrium with the vacuum. The Lorentz condition is initially violated each time anyone potentializes an EM circuit, but the closed-current-loop circuit design with the same charged-particle energy carriers around the loop — including back through the back emf of the source dipole in the generator — enforces a form of Lorentz symmetrical regauging during discharge of the system's excitation energy. Further, the response of the electrons in the usual electrical circuit with copper conductors is so rapid that the asymmetrical regauging (potentialization) is almost instantly converted to symmetrical discharging by movement of the electrons as current. When one section of the otherwise closed current loop uses a dramatically heavier charge as the energy carrier (as a battery uses ion current between its plates, but uses electron current between the outside of the plates and the external circuit), it is then possible to dephase the two independent carrier currents so that the battery will be charging while simultaneously the circuit is being powered, by a negative resistor (sharply increased scalar potential or voltage) produced at the plate surface interface of the two carrier current types. This proven Bedini process is an example of a true overunity process, capable of producing a self-powering system by means of adroit switching and timing.

asymmetry: Lack of symmetry, or "broken symmetry" in a general sense. Since a specific symmetry is accompanied by a specific conservation law, the breaking of that symmetry represents the violation of that conservation law. Particularly note that a broken symmetry at one level often (usually) results in a new symmetry at a higher level, necessary to maintain the asymmetry at the lower level. The resulting "levels" of symmetry are known as *hierarchies* of symmetry.

asymmetry of the dipole: Because of the proven asymmetry of opposite charges, any dipole or dipolarity is a broken 3-symmetry in its fierce exchange of EM energy with the active vacuum, because of the known broken symmetry of the opposite charges on its ends. Any two points in the universe (in or out of the circuit), that are at differing ambient potentials, constitutes such a broken symmetry continuously pouring out EM energy extracted from the vacuum. A dipole or dipolarity continuously receives and absorbs copious virtual energy from the seething virtual photon vacuum flux, and not all this absorbed energy is reradiated back to the vacuum in virtual form. Instead, some of it is coherently integrated into observable form and re-radiated in all directions as usable, real 3-space observable photons and EM energy. We found that the input energy to the dipole is from the time domain of 4-space. Hence the dipole's broken 3-symmetry results in the appearance of a new and far more fundamental 4-symmetry in energy flow between the time-domain and 3-space. This was the solution to the long-vexing source charge (or source dipole) problem in classical and quantum electrodynamics. Reinterpreting the Whittaker 1903 decomposition of the scalar potential reveals the mechanism for this 4-symmetry between time-domain EM longitudinal wave energy flow into a dipole and 3-space EM longitudinal wave energy flow out of the dipole, due to the presence of the proven broken 3-symmetry of the dipole. *EM energy flow is conserved in 4-space, but not in 3-space. Further, the 4-*symmetry energy flow from the source dipole (or source charge) continues as long as the source dipole (or source charge) remains intact so that the broken 3-symmetry remains intact. It is strongly indicated that this asymmetry of the dipole or dipolarity is what Gabriel Kron finally discovercd as his "open path".

back emf: The counter-electromotive force, usually between the end charges of the source dipole in the external power source for an electrical circuit (in its overall closed current loop). When the electrons in the circuit are forced against the emf— as when the "spent" or depotentialized charges from the ground reference of the circuit are forced back up through the emf of the source dipole to re-potentialize the charges — then work is done upon the source dipole to scatter its charges and destroy the dipole. Removing the dipole stops its receipt of vacuum energy from the time - domain (which was due to its broken 3-symmetry, now removed). It also stops the former dipole's transduction of that energy, and its former output of 3-space energy flow along the circuit and in space around the circuit. When this flow is occurring, a small component of it strikes the surface charges in the conductors and is diverged into the circuit (by axial precession of the surface charges withdrawing the "immediate stubs" of their fields and potentials into the conductor) to power it as the Poynting energy flow component. The huge remainder of the energy flow in space surrounding the circuit simply misses the circuit and is utterly wasted. Destruction of the source dipole removes the transduction of EM energy from the vacuum. It thus stops the powering of the circuit. So additional energy must then be input to the power source to perform work on its scattered internal charges, force them apart again, and reform and restore that source dipole, in order to resume powering the circuit by energy extracted from the vacuum by the dipole. It is simple to show that such a closed loop circuit uses more of its collected energy from the vacuum to destroy its source dipole, than it uses to power its load. Hence the circuit self-enforces COP<1.0.

back emf (tempic): There are actually two emfs in a circuit, not one. There is a 3-space emf and also an entirely unrecognized *tempic* emf. In either case, under proper circumstances there can be a back-emf of either one or both. See discussions under **electromotive force, back** and under **tempic back emf.** The tempic back emf is very important to COP>1.0 circuits, where the system's output energy density in spacetime is greater than the energy density at the input section of the system. This difference in tempic stress potential provides a tempic force sweeping from system output section back through the system to its input section. The current is a current of Dirac sea holes (negative energy 4-electrons) moving in that local vacuum, from the output section back through the system to the input section. At the input section, this Dirac sea hole current reacts with incoming electrons from the external power system. It therefore "eats" incoming electrons, so that the power supply must now furnish additional electron current to (a) power the negation and "killing" of the Dirac sea hole current by filling those holes with electrons in the input section of the circuit, and (b) simultaneously furnish the additional usual current to power the system's input. The result is that the tempic back emf is nature's mechanism for decaying the excited COP>1.0 energy state represented by a system in overunity functioning condition. Unless this hole current problem is overcome, this decay mechanism will destroy the net overunity, and it will prevent any attempt at close-looping the circuit for self-powering by use of clamped and governed positive energy feedback from output to input. The Bedini method can be used to transform the detrimental Dirac hole current into ordinary electron current, providing the self-powering feedback loop needed. Or, Bearden's outrigger method of using a multi-system set of external COP<1.0 receiving circuits powered by radiation (Poynting EM energy flow) from a single central power source (energy flow radiator) can be used. Then already-positive energy feedback from one or more of the separate outrigger COP<1.0 receiver circuits can be fed back in normal fashion to power the central power unit. Note that the outrigger concept uses the bridging concept, so that an external COP<1.0 system can be powered from a central radiating system, and the external COP<1.0 system can collect and output more energy than is output in the *accounted Poynting component* of the central radiating system. The excess energy radiated comes from the radiated Heaviside component.

bare electron: The true electron without its partial shielding of virtual positrons that are attracted toward it from the active vacuum, and that cluster around the electron, partially shielding its charge as seen by an external observer. The bare electron has infinite energy and infinite charge, as does the shielding cluster of virtual positrons. The difference between these two infinite values of opposite charge is the finite "externally observed" value of the electron charge listed in texts and handbooks. This strange dipolarity of the source charge thus exhibits an asymmetry in its exchange with the active vacuum virtual photon flux. Hence this mechanism also solves the source charge problem — how the charge continuously pours out EM energy in all directions at the speed of light, establishing its fields and their potentials reaching out into or even across the universe, without any input *of observable* EM energy to the source

Barret, Terence W.: Noted modern electrodynamicist and consultant who works in SU(2)xSU(2) gauge symmetry extended electrodynamics, and other models, and was also one of the pioneers of ultrawideband radar, Barret is one of the vigorous modern electrodynamicists continuing to develop and extend the science of electrodynamics and the electrodynamics model itself.

Bedini, John: Noted audio engineer, leading overunity energy researcher, inventor of the Bedini process for creating a true negative resistor inside a battery used as primary power to a circuit, and inventor of the Bedini overunity process for killing the back mmf (magnetomotive force) in a magnetic motor. Bedini is also the inventor of the renowned Bedini amplifiers well known to audiophiles, the BASE process for holographic sound, and a remarkable process for cleaning the harshness from digital audio disks. In addition, he discovered a mechanism for transducing into usable positive energy the detrimental Dirac Sea hole current (negative energy electron flow) backflow in an overunity system, flowing from the output section back through the system to the input section and even on out into the external power supply. The Bedini process transduces this detrimental current into normal electron current, thereby providing most or all of the required input power to the input section. Bearden then explained the technical process for Bedini's discovered transduction procedure, and Bedini and Bearden filed a patent application on this process.

Berry phase: Generalization by Berry of the Aharonov-Bohm effect, for an adiabatic situation. Later Aharonov and Anandan further removed the adiabatic condition and generalized the Berry phase to the geometric phase. See Aharonov-Bohm effect, geometric phase.

blocking: In a Fogal charge-barrier semiconductor, stopping or partially stopping the flow of current in a circuit, or between two points, by *pinning the electrons without stopping the EM energy flow.* In ordinary usage, "stopping the progress of whatever charge flow or current is being referred to.

Bohm, **David J.:** World-renowned physicist and originator of the hidden variable theory and interpretation of quantum mechanics. See David Bohm, "A Suggested Interpretation of the Quantum Theory in Terms of 'Hidden' Variables, I and II," *Physical Review,* 85(2), Jan. 15, 1952, p. 166-179 (Part I); 180-193 (Part II). Together with his student Aharonov, Bohm co-authored a fundamental paper on the Aharonov-Bohm effect wherein interfering electromagnetic potentials can produce effects on charged particle systems, even at a distance and in the absence of the electromagnetic force fields. From Bohm's hidden variable theory, the quantum potential has been highly weaponized by five nations, and these eerie weapons operating instantaneously at a distance through multiply connected spacetime are presently the dominant strategic weapons on earth.

Bohm's hidden-variable theory (HVT) of quantum mechanics: A major interpretation of quantum mechanics, formulated by David Bohm and published in *Physical Review* in 1952. Bohm's theory makes all the correct predictions and also eliminates many problems in quantum mechanics, such as the "measurement problem" and the — now recognized — problem of the missing chaos (i.e., the missing "hidden chaotic order."). Bohm's theory implies that physical reality — or much of it — can in fact be deterministically engineered. A key concept is the use of a *quantum* *potential*, which is multiply connected. Clandestine superweapons using Bohm's quantum potential (QP) have been developed and deployed by several nations. Present mutual assured destruction "standoff between these nations is based on surviving counters to QP weapons rather than surviving nuclear weapons.

Bohren, Craig F.: Distinguished Professor of Meteorology, Pennsylvania State University, noted for work in scattering theory. In an experiment detailed in C. F. Bohren, "How can a particle absorb more than the light incident on it?" *American Journal ofPhysics,* 51(4), Apr. 1983, p. 323-327 Bohren shows that in nonlinear conditions a resonant particle may absorb and output 18 times as much energy as is impinging upon it from the usual field definitions based on a static intercepting charge. The additional energy is "absorbed from the vacuum"; actually, it is absorbed from the nondiverged Heaviside energy flow component accompanying the accounted Poynting input component, but arbitrarily discarded by Lorentz. The resonant particle sweeps out a geometrical interception area (reaction cross section) greater than that of the same charge in a fixed static condition. Hence it intercepts part of the always-available Heaviside "dark energy" flow surrounding the Poynting energy flow component of every field/charge interaction.

Bohren experiment: Revealing experiment by Craig F. Bohren, replicated by Paul and Fischer, which shows that a given charge when in particle resonance absorbs more energy from a field or potential then the same charge does when in "static" position. This experiment is a direct experimental demonstration of the existence of Heaviside's nondiverged energy flow component around every field/charge interaction. See discussion under Bohren, Craig F. The Bohren experiment can be repllicated by any university nonlinear optics laboratory and outputs 18 times as much energy as is input by normal calculations (neglecting the Heaviside nondiverged EM energy flow component of the input).

boson: A particle having integral spin, which obeys Bose-Einstein statistics but not the Pauli exclusion principle. Bosons include the photon, alpha-particle, and any nucleus of even mass number.

bridge: A component or process which passes EM energy between two isolated circuits, but does not pass dq/dt between them, and which breaks the normal rigidly field-locked power dissipations in the two circuits. Space itself would appear to be one such bridge for EM energy flow.

bridging function: The function of passing EM energy flow between two isolated circuits, but not passing dq/dt between them, while simultaneously breaking any normal rigidly field-locked power dissipations in the two circuits. Use of the uncurled A-potential where $\nabla\times\mathbf{A}=\mathbf{0}$ is one available method of bridging otherwise isolated circuits, particularly in the outrigger embodiment of the motionless electromagnetic generator and other COP>1.0 systems.

broken symmetry: Fundamentally, a condition in which two parts of some configuration or shape, on opposite sides of some divisor or condition or boundary, are not similar but differ. In vacuum energy physics, we are very interested in the fact that — because of the broken symmetry of opposite charges — any charge (with its associated clustering virtual charges of opposite sign) and any dipole or dipolarity represents an asymmetry in its fierce energy exchange with the vacuum. This implies that something virtual becomes observable; i.e., part of the virtual EM energy continuously absorbed from the vacuum by the charge or by the dipole is changed into observable form and re-emitted as real, observable EM energy. The remainder is re-radiated as virtual EM energy. The charge's transduction of absorbed virtual photon energy and its re-emission as observable photon energy was proposed by the present author in 2000 as the solution to the long-vexing problem of the source charge and its associated fields and potentials (and their energy) reaching across the universe.

bypass resistor: In electrical theory, a resistor to pass or conduct current around (in parallel to) some other component. If another effect such as use of the overpotential, pumped phase-conjugate reflection, quantum well, quantum tunneling, negative energy, or charge blocking is added, the bypass resistor's function becomes extremely complicated. The bypass resistor may be complex, e.g., or it may be a true negative resistor in some cases.

carrier wave: A fundamental wave that is modulated by another wave or other waves, and hence "carries" the other modulating waveform(s). By stripping off the carrier in a demodulator, the carried waveform(s) emerges.

Casimir **effect:** The attraction of two conducting parallel plates in space, placed very close together, due to their influence on the active vacuum and on the vacuum's interaction with the plates. A part of the vacuum spectrum between the plates is "cut off and blocked or shielded, so that the vacuum potential between the plates is less than the vacuum potential outside them. The resulting potential gradient (force) on each plate from outside pushes the plates together. The Casimir effect unequivocally proves that it is possible to directly engineer the vacuum so as to produce forces and energy and physical effects in material systems. While it is a "small" white crow, it only takes one white crow to prove that not all crows are black. It is sufficient to conclusively prove that EM energy can be extracted from the vacuum. From there to practical EM power systems, fed by vacuum energy, is simply a product of modifying the prevailing electrodynamics and electrical engineering to incorporate the supersystem components and interactions, and then to gradually discover and develop the necessary technology. In this book we attempt to point the way by using the supersystem and providing some of the major necessary principles and c**oncepts.**

Casimir, Hendrik Brugt Berhard (1909-2000): Noted scientist who in **1948** correctly predicted that two parallel conducting plates, placed very near each other in a vacuum, would experience an attractive force due to **their** influence on the electromagnetic vacuum.

caus**ality:** The relationship between "cause" and "effect", or the interaction of 4-space cause upon a previous 3-space observation (effect), to produce a new 3-space observation (change in the previous observable or **production** of an exact 3-space replica). The basic notion in a causal system is that the system's response to an input signal is dependent only u**pon** past input values, not upon future input values. In a multiply connected space, the causality principle is dramatically changed and requires very careful accounting.

chaos: In dissipative dynamical systems, the dynamical evolution or ordering of the system that is aperiodic and highly dependent upon initial co**nditions** of the system. The trajectories of the system move on a *strange attractor,* which is a fractal subspace of the phase space. The mathematical equations describing chaotic behavior are very nonlinear and so complex that at the present time they cannot be computed or predicted. Control of chaotic oscillations thus is ongoing in its scientific development, with the most advanced control work having been done by Russian scientists, but now openly available.

charge: C*harge* is the ongoing circulation of EM energy flow between the time and 3-**space** domains, as "seen" by the observer in 3-space. *Negative* charge is (i) the ongoing absorption, by a mass particle, of EM energy input **from** the time domain (from *ict),* (ii) transduction of the absorbed energy into 3-space EM energy, and (iii) re-emission of the EM energy in all directions in 3-space. *Positive charge* is (i) the ongoing absorption, by a mass **particle, of** EM energy input from 3-space, (ii) transduction of the absorbed energy into the time domain, and (iii) re-emission of the EM energy in the time domain. Alternately, the positive charge can be considered as (i) the ongoing absorption, by a mass particle, of EM negative energy input from the time domain (from *ict),* (ii) transduction of the absorbed negative energy into 3-space, and (iii) re-emission of the EM negative energy in 3-space. A similar inversion can be utilized to represent negative charge. Time reversal of EM energy can be seen to result from the combined broken symmetries of EM energy flow (in 4-space) between time and 3-space, of two opposite charges and thus of dipolarity itself. See paragraph 3.1 of Chapter 3.

charge, electrical (q).: In the sense of q being charged mass, where the mass m_q of charge q is associated with the phenomenon defined as charge (see above definition). In our view, an electrical charge q associated with a charged particle or mass may be defined as $q \equiv m_q\phi_q$, to first order. This fits the common use of "the charge" as an expression for a charged mass, and explains why a gathering of charges produces a potential ϕ reaching out from the "source gathering of charge q". The actual "charge" action associated with the mass is due totally to ϕ_q, and to the broken symmetry of the ϕ_q dipolarity in the vacuum flux exchange with m_q. The charge q can be further broken down into a set of composite dipoles if the gathering of a screen of virtual charges of opposite sign in the vacuum, surrounding the mass of the "bare charge" inside the gathering, is considered. At first order, ϕ_q can be expressed (from *a particle view)* as a change in the local vacuum virtual photon flux (VPF), due to the VPF exchange between vacuum and m_q. *In a classical approach,* the vacuum may be considered as a giant scalar potential comprised of bidirectional EM wave flows according to Whittaker's 1903 decomposition, except we must re-interpret the phase conjugate half-set of Whittaker's decomposition as incoming from the time domain or complex plane. The charge then may be considered to diverge so much energy flow from the time domain into 3-space "around" the mass, resulting in ϕ_q as the steadily diverged energy surrounding the mass m_q. The ϕ_q component is actually the massless electrical charge and massless of itself. This approach would then yield a definition of massless charge itself, which at present is undefined in physics, as pointed out by Feynman and others.

In the expression $q \equiv m_q\phi_q$, the ϕ_q represents a change to the local vacuum potential ϕ_{vac}. Both ϕ_q and ϕ_{vac} decompose into Whittaker phase conjugate longitudinal EM wavepairs. As can be seen, by altering or engineering these constituent wavepairs, a particular ϕ_q or particular local vacuum potential ϕ_{vac} can be given a deterministic internal structure and dynamics.

Thus the interaction of a given electron or group of electrons may be made **quite** different from the interaction of another electron or group of "apparently identical" electrons. Such structuring dynamics are met with in the internal structuring of water, e.g., where the fierce activity of H-bond making and breaking can be treated as a special ϕ_H and its "internal structure and dynamics" can be engineered. A leading scientist pursuing that type of effect is Jacques Benveniste, in France. Predictably, the o**rthodox** establishment has severely castigated these experiments, defending conventional models as absolute while completely ignoring the experimental results that refute those conventional models as being incomplete.

charge carriers: Anything — usually fundamental particles, ions, etc. — which consists of or contains charges and can be potentialized and move.

charge, magnetic: In the sense of charged mass, a magnetic charge is what is commonly called a "magnetic pole". The mass m of the magnetic charge is associated with the exchange of EM energy between the time domain and the 3-space domain. Essentially, the energy exchange action **known** as "charge" in the massless sense is the magnetic scalar potential, or monopole, when decomposed as per Whittaker and as reinterpreted by the **present** author, and as pointed out in quantum field theory by Mandl and Shaw. Note that our personal view discriminates between *massless charge and charged mass.* Massless charge is an ongoing action and process, involving energy transduction from one form (time energy or 3-space energy) to another (3-space energy or time energy). A charged mass is a **mass** associated with such action. Unfortunately, in the prevailing usage the word "charge" is just loosely used for both senses without discrimination. Hence one must carefully differentiate between the use of "charge" for "charged mass", and its use for an "ongoing process".

charge-parity-time (CPT) theorem: C is *charge conjugation,* which changes the quantum number of every particle into its antiparticle. P is the reflection operation known as *parity,* which turns an object into its mirror image and rotates it 180 degrees about an axis perpendicular to the mirror. T is t*ime reversal.* Any violation of time-reversal symmetry is always accompanied by a violation of CP symmetry (by violating either C or P symmetry) and vice versa.

Electrodynamics and the strong interaction preserve CP symmetry to great accuracy. Weak interactions do not conserve CP symmetry. T symmetry violation has been shown at CERN, the European particle physics laboratory in Geneva, Switzerland.

charge trapping (also "pinning"): Holding charges "pinned" or "trapped" at a site or in a location, by a barrier or force, so that they do not flow as $i = dq/dt$. A clustering of the pinned charges at the pinning site often occurs.

charge-barrier: A process or component or function — particularly in a semiconductor such as the Fogal semiconductor — that blocks the movement of charges q as current dq/dt.

classical electromagnetic theory: The classical theory of electrodynamics, in its modern form begun by Maxwell with his seminal-paper orally presented in 1864 and published in 1865. Today many variations have been made, particularly with respect to the basic group symmetry of the theoretical equations.

Clifford algebra: A special higher topology algebra founded by Clifford, which includes as subsets many other algebras of lower topology.

closed system: In the present approach, a system that in theory does not communicate with its environment, and does not exchange energy or matter between system and environment. Notice that this directly conflicts with the notion in thermodynamics (both classical and disequilibrium) that a closed system is closed only to mass exchange across its boundary, but open to energy exchange across it. General relativity has falsified that notion since 1915. Any system undergoing a change of energy also undergoes a change of mass, since mass is a special form of energy.

An ideal model in which dynamically and energetically the system is considered to be "isolated" as if nothing else existed. In short, the system is considered as if it were in some "magic box" and nothing outside the box can ever enter the box or affect the system inside the box, and nothing in the system can ever leave the box or affect anything outside the box. No electromagnetic system is closed. In short, we have corrected the thermodynamics "closed system" with open energy transfer, to a true closed system with neither energy nor mass transferring. That corresponds to the present thermodynamics notion of the "isolated system".

One performs a non sequitur when proclaiming treatment of any EM system as a "closed system", and of course modern physics substantiates this. The broken symmetry of the opposite charges on the ends of a dipole — and of an observable charge together with its clustered virtual charges of opposite sign — has been proven since 1957. The absence of any closed system is particularly true in electrical power systems. Here one is indeed allowed to input energy into the system to excite or potentialize it. That **of** course assumes that the system was "opened" long enough to take on excess energy (which also changed its mass)! Then as the system operates, losses and dissipations occur, in which case energy is considered to "escape" from the system permanently. In other words, the system was also continually "opened" so that energy could escape. In any EM system, every charge and dipole is already an open system, with free exchange of energy between 3-space and the time domain via that charge. In particle physics, every charge and dipole is a broken symmetry in its virtual particle flux exchange with the active vacuum.

The ancient thermodynamics definition of a "closed system" as one that exchanged heat but not mass, was formulated before thermodynamicists even knew that heat was a form of EM energy, or even knew what energy was. Hence we have changed that definition, since it is a non sequitur in view of modern physics.

There is really no such thing as a truly closed system in the universe, since *every* system is embedded in the active vacuum and is an open system in an energy exchange with the vacuum. Further, any change of energy in the system curves the local spacetime, which in turn interacts back upon the system. If that energetic exchange of the system with its "active vacuum and active curved spacetime environment" is symmetrical, then the system is in equilibrium with respect to its environmental exchange. In that case, for a limited number of purposes the system may be treated as if it were a closed system. In classical electrodynamics, Lorentz regauging of the Maxwell-Heaviside equations further reduced them to describe only Maxwellian systems in equilibrium with the active environment including the active vacuum. Consequently, any *net* interaction between the external vacuum (or the active local curved spacetime) and the system was excluded from the CED model. Obviously a *broken equilibrium* (i.e., broken symmetry) in that actual physical interaction is also not included in the CED model. Nor is it included in the classical (equilibrium) thermodynamics model with its archaic second law.

coefficient of performance (COP): Ratio of the usable energy output of a system divided by that portion of the total energy input that is input by the the operator's or experimenter. The COP is thus a measure of "return for using the operator's or experimenter's input energy" to produce — or direct the production of— useful work by the system". There are other ways to calculate the COP ratio; e.g., the average output power divided by the average operator input power. Contrast COP to the *efficiency* of a system, which is the ratio of the total usable output energy divided by the *total input energy from all sources*, including by the external active environment as well as by the operator. The efficiency of a system means how efficiently it produces useful output from its *total* input. The COP is the performance the system renders for the *operator's* input. Note that even a highly inefficient system — say, with efficiency $\xi = 0.25$ — may nonetheless have a COP>1.0, if the operator himself inputs less energy than the system outputs and the environment inputs all the rest of the output energy as well as all the energy in the system losses. As an example, a common home heat pump may have an efficiency of 40%, but a COP = 4.0. A windmill may have an efficiency of 20%, but a COP = ∞.

Also, for many systems one may evaluate their coefficient of performance for (1) the performance of the system as an energy transducer only, i.e., the ratio of energy the system outputs (whether used or not) divided by the energy the operator inputs; or (2) the performance of the system as a work producer, which is the useful work accomplished by the system divided by the operator's energy input. As an *energy transducer,* every generator and every battery has a COP»1.0, when both the Poynting diverged energy flow output and the Heaviside nondiverged energy flow output are accounted. Yet for useful work, the same system may have COP<1.0, because all the Heaviside nondiverged energy flow component is wasted, and some of the Poynting diverged energy flow component is wasted also.

Analyzed as an energy transducer only, every dipolar power unit — such as a generator or battery — outputs enormously more energy flow rate from its terminals than the mechanical energy rate input to the shaft of the generator, and than the chemical energy dissipated in the battery. So as an energy transducer, every dipolar power source is already a system exhibiting COP»1.0, prior to Lorentz' integration trick to discard the enormous Heaviside nondiverged energy flow output component.

cold fusion: An ad hoc term applied to the transmutations at low spatial energy (but high time-energy) achieved in electrolyte experiments, particularly when using specially prepared palladium electrodes after their loading with positive H+ or D+ ions, and particularly when deuterium is present in the electrolyte and the loading is by D+ ions. The *total* energy of the photon is greater the lower the photon's frequency and therefore the lower the spatial energy of the photon. Hence the cold fusion interactions actually use much higher *total* energy nuclear reactions than does present high (spatial) energy physics. Since "high energy" physics erroneously eliminates consideration of time-energy, the present high energy physics community is unjustifiably hostile to the very notion of cold fusion. The fact that little experiments on the lab bench use far higher total energy than the community's proud large accelerators is a bitter pill many high energy physicists cannot *tolerate*, let alone view with scientific objectivity. So again there is a classic confrontation between science from scientific results and "science as known in the prevailing dogma".

composite dipole: Dipole formed as one part of an isolated, observable "charged particle", consisting of a differential element of that observable charge on one end and a momentary clustering virtual charge of opposite sign. This is one way of dealing with the modern "infinitely strong dual dipoles" view of the charge, where the bare charge in the middle is infinite as is the clustering virtual particle charge surrounding that bare charge and partially shielding it. The difference between these two infinite charges is finite, and is routinely calculated to show that it is the standard value of the charge as seen by an external observer.

Cooper pair: In superconductivity theory, a dynamic, weakly bound pairing of electrons in a superconducting material below its critical temperature. In this pair, if the energy state with wave number sigma and spin 1/2 is occupied by an electron, then so is the state with wave number -sigma and spin -1/2. The Bardeen, Cooper, Schrieffer (BCS) theory uses this concept to provide a detailed microscopic theory of superconductivity.

COP (Coefficient of Performance): See coefficient of performance.

cosmological feedback principle: A self-regenerating cosmological feedback cycle ascribed by Puthoff as the source of the vacuum EM zero-point energy (ZPE). One may assume the existence of EM zero-point energy by fiat as part of the boundary conditions of the universe, or concieive of its generation by the quantum-fluctuation motion of charged particles that constitute matter. Puthoff calculated the latter possibility, assuming that the ZPE spectrum (field distribution) drives particle motion, and that the particle motion in turn generates the ZPE spectrum. This provides a self-regenerating cosmological feedback cycle, which in fact is consistent with the general relativity assumption that curvature of spacetime affects mass energy, and mass energy changes affect the curvature of spacetime. It would be interesting to see if Puthoff s concept can be made compatible with the broken symmetry of a dipolarity and Kron's open path concept.

curl concept of fields: The concept of a field as the curl of a vector potential (the vector potential may not be known). Any field so conceived has a divergence of zero *a priori*. One must be careful, however, because electrodynamics calculates only the field's reaction cross section with an assumed fixed unit point static charge at a point in space, leaving the field itself undefined. In short, the calculation of "the field" is actually a representation of the local point intensity of the field's interaction with unit point static charge. It is not the magnitude of the entire field (or potential) itself, *a priori,* but only of its reaction at a point with such a charge. In short, the field's reaction cross section with static charge is often misinterpreted as the magnitude of the field; at best it is an indication of the field intensity to static charge at a point.

curl-free magnetic vector potential: A field-free magnetic vector potential A without curl (swirl), hence lacing the B-field with which an A-potential is usually associated. For simplicity, one may visualize the curl-free A-potential as massless magnetic charge (and energy) in linear motion. Toroids and long solenoids have the characteristic of confining the B-field (curled potential) and holding it inside. However, drawing energy from any potential whose source charge or source dipole is not destroyed simply results in the full value (sum of the A-potential and B-field components) of the potential being replenished from the active vacuum, via the 4-symmetry energy flow mechanism in the presence of the broken 3-symmetry of the dipole. Hence one may easily increase the available potential energy density at will. This is a special form of gauge freedom allowing one to freely alter the potential energy of any electromagnetic system at will. Contrary to the dictates of EM textbooks, gauge freedom rigorously allows the direct and *free* amplification of potential energy of the EM system *at will;* the excess energy being freely furnished from the active vacuum processes. This principle incorporated in gauge field theory, has been known for decades and not previously used in the design, production, and use of COP>1.0 electrical power systems, prior to the invention of the motionless electromagnetic generator (MEG).

curved spacetime: A four-dimensional geometry (spacetime or ST) is used in general relativity, where the ST curvature is determined by the distribution of spatial energy such as mass-energy. In the general relativity view there is no such thing as an "empty" space "filled" with some energy substance. Instead, there is a combined space and time as a single entity, *spacetime,* which is itself energetic and is the very geometry we use in our mathematics. Any change in the local energy density of that spacetime constitutes a *curvature* of spacetime. In the new, more extended approach, any change in the spatial energy density or time-energy density of spacetime, or a combination of changes in both, constitutes a curvature of spacetime. In 4-space modeling, time is treated as a special, highly condensed form of EM energy. Specifically time may be regarded as ordinary 3-spatial EM energy compressed by a factor of c^2 and existing in the time domain rather than in 3-space. Time-energy therefore has essentially the same energy density as mass.

dark energy (negative): (Dirac holes, Dirac hole potentials, Dirac hole currents): A strange form of vacuum energy that creates repulsive gravity, causing the expansion of the universe to speed up (as observed and not otherwise explained by conventional theory). As a strong candidate for the dark energy, the present author has proposed a vacuum negative energy and negative energy currents in a negatively curved spacetime region partially containing excess Dirac sea holes devoid of electrons, along with normal filled Dirac sea holes. These special "Dirac negative action quanta" then form *negative action* (negative angular momentum, or — for simplicity — negative energy) potentials, currents, and fields. This type of vacuum condition containing some empty Dirac sea holes is referred to as a Dirac *-polarized vacuum.* However, it is not just simple static polarization, but possesses rich dynamics. Such dynamic Dirac sea hole regions occur in the vacuum in curved spacetime regions with tempic potential gradients and strong 3-spatial energy gradients, and thus time force existing across the region. The holes occur since the energetic fluctuations of the local vacuum energy can separate a Dirac hole from its occupying electron. These may then recombine, or in sufficient local spacetime curvature can remain apart. The more violent the region, the more severe are local spacetime curvatures in that region, and the greater the fraction of empty Dirac holes that is maintained on the average, in their continual forming and recombining. In those regions, a tempic potential is higher at the higher center magnitude of the spatial energy density. Hence there tempic forces from "inside to outside", providing a "tempic broom" effect to sweep outward the excess Dirac sea holes separated from their electrons in the curved spacetime. The end result is the presence of increasingly unoccupied Dirac sea holes toward the outside of violent regions of spacetime, until the effect is overcome by the decreasing spacetime curvature. These empty Dirac holes in regions and currents are a special form of vacuum negative energy, negative energy fields, and negative energy potentials, creating negative gravity (repulsive gravity) upon ordinary mass exposed to them. So the more distant violent astronomical regions have greater amounts of repulsive gravity being produced by their local Dirac-polarized vacua and negative energy fields and potentials. The result of this effect is that, at sufficient distance from us, the increasingly earlier, more violent events and resulting greater curved spacetime regions have created sufficient Dirac-polarized vacua to overcome the normal gravitational attraction between galaxies, etc. Even farther out, the increase in Dirac-polarized vacua overrides the normal attractive gravity between galaxies, etc. and produces net repulsive gravity. In turn this results in acceleration of the observed distant expansion of the universe. Dirac-polarized vacuum and its special dynamics can be accommodated in Sachs' unified field theory, which unites physics from quarks to the cosmos. See also **Dirac** sea **holes.**

On the laboratory bench, Dirac hole currents and effects are met with in a circuit or system producing COP>1.0, or very sharp 3-spatial gradients such as in violent electrical discharges. The effects become non-negligible at about COP = 2.0 and sometimes less. The tempic force back across the, system from output to input is sweeping the Dirac holes through the system. This can play havoc with attempts to close-loop the circuit for self-operation. In semiconductor components, strange effects are met due to their use of donor and acceptor materials, and temporary or permanent failure of semiconductors can result. The simple way to visualize this is that, in the system's supersystem, the spacetime component is curved and the vacuum component is highly nonlinear. All three components — overunity system, local nonlinear and polarized vacuum, and local curved spacetime — are interacting vigorously with each other. An operating overunity system represents an excited state of that local region of vacuum and curved spacetime, hidden in the euphemism "polarized" which is inadequate to describe the dynamics. With the dynamics, one may visualize that the Dirac sea hole currents are swept back through the system, seeking to recombine with electrons to eliminate the "polarization" and its dynamics, thus decaying the excited state back to equilibrium and destroying the overunity condition. In a robust system whose internal parts do not appreciably interact with these Dirac hold dynamics, the dynamics will reach the input section and extend back into or toward the primary power supply. In the input section, the feeder line, and in the power source itself, this results in "eating electrons". The Dirac sea effects thus act as a separate load imposed within and around the system input section or even back in the feeder line to the external power supply, in addition to the system load itself in the system output section. Simply put, the power supply must now furnish extra electrons to "power" the Dirac sea hole recombinations first, and additional electrons to power the system in its "normal" fashion. The result is to "draw additional power" from the source, where "drawing power" now includes the additional "eating of electrons" within the power supply itself, the feeder line, and the input section of the system.

Bedini and Bearden have filed a patent application on processes to convert the detrimental Dirac sea hole current reaching the system's input section.

transforming it into ordinary electron current. Magnetic Energy Ltd. has developed two other processes that handle the Dirac sea hole current problem, allowing close-looping for self-power ng operation. One of these processes converts negative energy into positive energy and the other avoids the negative energy problem. The first one allows this otherwise devastating special form of "negative feedback" or "degenerative feedback" to be converted into "positive feedback" or "regenerative feedback", allowing the system to be close-looped successfully for self-powering. Bearden has proposed yet a different approach using an "anti-circuit" method, but at this writing the method is still proprietary until intellectual property rights are secured.

dark energy (positive): Our term for the vast Heaviside nondiverged energy flow component surrounding every field/charge and potential/charge reaction but unaccounted in present electromagnetic theory after being arbitrarily discarded by Lorentz circa the 1890s. Present theory only accounts for that small amount of energy flow (the Poynting component) diverted locally around the interacting charge. All the rest of the energy flow comprising the field or potential, and missing the intercepting point charge, was discarded arbitrarily by Lorentz and is still discarded today, using Lorentz's integration trick. In honor of Heaviside, who **did** recognize the gravitational implications of his dark energy flow component, the present author has nominated this vast, unaccounted "dark energy" component as being responsible for the extra gravity holding the spiral arms of the spiral galaxies together. See **spiral** galaxy.

So one must recognize that the term "dark energy" is indefinite, since there are two kinds: (a) dark positive energy, and (b) dark negative energy. Dark positive energy consists of "normal" energy as often connected with particles, collected upon them and affecting their momenta, etc. It has dynamics and effects consistent with that kind of energy. Dark negative energy is a condition of the vacuum itself. It represents a sort of "empty container and empty container dynamics" (negative energy dynamics) in the vacuum itself, which "eats positive energy", so to speak. In philosophical terms, dark positive energy represents unaccounted actions and effects from unaccounted "extra presence of real substance and things and actions". Dark negative energy represents unaccounted actions and effects from "extra absence of real substance and things and actions beyond zero". Dark negative energy exhibits precisely appositive effects to the effects produced by dark positive energy. E g., dark energy creates the excess gravity that is holding the arms of the spiral galaxies together. Negative energy resulting from spacetime curvature conditions in highly energetic astronomical phenomena produces the *antigravity* that is responsible for the acceleration of the expansion of the universe. We have nominated the negative energy Dirac sea hole phenomena as the cause of the antigravity that accelerates the expanding universe. Interestingly, these negative energy phenomena present in sharp discharge (strong gradient) phenomena appear to be responsible for the fact that such phenomena are known to violate present thermodynamics, and are being studied under the aegis of "extended thermodynamics". See discussion of areas violating thermodynamics in the last chapter of Kondepudi and Prigogine, *Modern Thermodynamics: From Heat Engines to Dissipative Structures,* Wiley, New York, 1998, reprinted with corrections in 1999. A reference is D. Jou, *Extended Irreversible Thermodynamics,* Springer-Verlag, New York, 1996.

degenerate semiconductor: A semiconductor whose conductivity approaches that of a metal.

demodulation: From a carrier containing a modulated signal, recovering the signal that was used to modulate it.

deterministic pattern or "template": The exact arrangement, by plan and deterministic action, of a group of entities. The deterministic actions and their "controlling forces" are simply called "dynamics", "structuring", etc. An example might be deterministic field structuring and actions of photons in a "herd" or "group". Or of a set of spacetime curvatures, into a dynamic structure called a *spacetime curvature engine* — or *engine* for short, so long as the meaning is clear. Or by hidden order in the virtual photons in the vacuum flux, or a deterministic set of changes to that vacuum flux (the vacuum flux that is called the "vacuum potential." We have called this *internal EM dynamics* function — of deterministically patterning or templating the virtual flux (particle view) of the potential, or of deterministically patterning or templating the longitudinal and time-polarized EM wave decomposition (wave view) of the potential - *dimensioning* the potential. See **dimensioning.** We refer to the deterministic structure and its structural dynamics as the "engine template".

dielectric: Literally, "against electric (current)", originally coined to mean "opposes the flow or conduction of electric fluid". In today's language, a dielectric is a non-conducting material used to oppose or prevent the flow of electric charges. Even empty vacuum exhibits some dielectric resistance. "Dielectric" is also used to refer to a nonconducting material (often between the metal plates of a capacitor or elsewhere) that can (i) sustain a change in potential across a distance (i.e., an E-field), and (ii) serve as an insulator. Space itself is a dielectric, or at least is said to exhibit certain dielectric qualities.

dimension: A certain primary geometrical physical attribute, such as length, used to describe the separational relationships of physical phenomena. Actually, "dimension" just means "fundamental quantity of separation" and "geometry" in the most general sense. Dimensions thus become a sort of set of fundamental variables describing the *extensivity* of system and the dynamics of that extensivity. The number of dimensions taken in advanced physics usually represents a somewhat arbitrary choice for good modeling fit. In modern Kaluza-Klein theory, for example, it becomes necessary to accept some 10 or 11 dimensions in the usual particle physics case. Sometimes more than 20, or even an infinite number, of dimensions may be used. General relativity (GR) has incorporated the interaction of the abstract geometry (spacetime) with mass, so that *geometry is a real, active, dynamic entity.* Until Sachs' extension of Einstein's work into a unified field theory and Evans' incorporation of O(3) electrodynamics as an important subset of Sachs' unified theory, GR has largely remained a nonexperimental discipline, at least in the laboratory. With the new Sachs-Evans approach and with recovery of (a) the Heaviside dark energy flow component (b) overunity EM systems arbitratily discarded by Lorentz symmetrical regauging, and (c) modeling of the complete supersystem including system, vacuum, and spacetime in mutual interaction, GR suddenly becomes substantially engineerable by novel electromagnetic means, both in the laboratory and in operating devices. We are thus entering a great new age of electrogravitation and a new physics. Research in antigravity lifters, COP>1.0 electrical power systems, medical therapy utilizing engines and anti-engines, and cold fusion are the elements of the new science that are struggling to be born and funded.

dimensi**oning:** Coined term meaning "forming an exact pattern or template of structures", particularly of nested curvatures of spacetime, where the pattern/template may also be dynamic, to include patterning and dynamics in the time-energy domain as well as the 3-space energy domain. It involves the internal structuring of the "dimensioned" entity. The term "dimensioning" makes sense in unified field theory, but is awkward in normal EM theory, which erroneously assumes that EM energy propagates in an uncurved spacetime. The mere presence of a change in local spatial energy, created by the wave energy itself when present in that local region, curves the local spacetime. Note that the background potential may be changed in a steady state level as well, which means that the frame of the system and its field dynamics has been rotated away from the laboratory frame. A time-polarized EM wave, e.g., changes the time-energy density and also curves local spacetime very powerfully. Hence the EM wave rigorously travels in curved spacetime, and in fact identically is a propagating, oscillating curvature of spacetime. What is missing from present physics is all accounting of the extraordinary Heaviside nondiverged energy flow component accompanying the accounted Poynting diverged energy flow component. Thus present physics *does not properly account for* the gravitational aspects of "electrodynamic field and potential energy in space".

Dimensioning also implies a deliberate form or structure (with dynamics) created in the virtual photon flux of the vacuum, in the virtual photon flux comprising a scalar potential, or in the infolded longitudinal-wave EM inside all EM potentials, fields, and waves. It implies an associated set of spacetime curvatures and their dynamics. The latter are referred to as "engines", "vacuum engines", "spacetime curvature engines", etc.

Dimensioning the potentials or signals or carrier waves of conventional electrodynamics involves adding hidden *vacuum engines* to them. The term *dimensioning* is descriptive and was chosen because adding such templates is equivalent to increasing the EM topology by adding mathematical dimensions. Since an EM wave or field or vector potential can be decomposed into two scalar potentials, then "dimensioning" one or both of the scalar potentials can "infold" the desired hidden structures or patterns (vacuum engines) inside an EM carrier wave, EM field, or vector potential created by the interference of the two dimensioned base potentials. This is referred to as *dimensioning* those EM field and wave entities. Internally structuring the two scalar potentials via arrays of longitudinal EM wave emitters and applying the necessary dynamics (modulations), is the primary manner to directly engineer dimensioning. When dimensioning is present, two EM waves that appear identical as seen on the oscilloscope may have dramatically differing internal structures (dimensioning). Hence they may produce drastically differing effects when they interact with the same or similar objects. *The only way in which the action of a vacuum engine can be resisted is to create and simultaneously introduce the exact antiengine for it — a special sort of forcible symmetrical regauging, so to speak.* Once the action has been completed in the receiving object and it has been physically changed, the only way it usually can be undone is to form a precise antiengine for that action, amplify the antiengine, and let the antiengine act upon the object for a sufficient time to "time-reverse it back to its previous physical state and condition". The concept has great utility in electromagnetic healing, not discussed in this book. We point out that the decades-long induction of diseases, health changes, etc. in U.S. personnel in the U.S. Embassy in Moscow occurred in forcefield-free regions. In short, the changes occurred in regions where the potentials were stable and unchanging, and so their engines were stable and constantly applied to the exposed personnel. The Soviets were simply radiating a high level target, the U.S. Ambassador and his staff, to guarantee high-level U.S. attention. By U.S. reaction to the deliberate electromagnetic "engine" induction of disease and health changes (three Ambassadors sickened and later died), the Soviets could positively ascertain whether we knew of the "infolding" or "dimensioning" technology, and whether we had developed defenses.

dipole: In the simplest case, two separated charges of usually equal magnitude and of opposite sign. More generally, a localized positive charge or charge distribution, and a localized negative charge or charge distribution, such that the net charge summation is zero, while the positive and negative charge distributions do not precisely superpose point to point but only on the average. We point out, however, that in regular physics electrical *charge* has no proper definition. As is well known in particle physics.due to the opposite charges on its end a dipole is a broken symmctry in the virtual photon flux of the vacuum. By definition of broken symmetry, this means that *some* of the virtual energy flux continuously absorbed from the seething vacuum by the charges of the dipole is not re-radiated as *virtual* energy. Instead, it is integrated *coherently* and re-radiated in 3-space as real emitted EM energy, establishing the fields and potentials associated with that source charge or source dipole. The dipole is therefore the most fundamental true "negative resistor" since it freely and continuously receives EM energy in unusable form, transduces it into usable form, and re-emits it in usable EM form.

It follows that any positive charge in the universe and any negative charge in the universe form a dipole and a broken symmetry in the vacuum flux. Hence every such dipolarity in the universe already extracts energy from the vacuum and puts it out in 3-space, or absorbs energy from 3-space and returns it to the vacuum. Kron called this an "open path" electrically, well before broken symmetry was formally discovered and experimentally prove in l957. Kron was also able to use the open path in and around special electromagnetic circuits to cause the circuits to become true negative resistors, freely powering the network analyzer at Stanford Universoty even in the 1930s.

In classical EM theory, the problem of how every charge and dipole can continuously emit EM energy to form all the associated fields and potentials and their energy has been an unsolved problem — sometimes called the most difficult problem in electrodynamics, both classical and quantal. For the solution and a discussion, see the present author's paper "Giant Negentropy from the Common Dipole," *Journal of New Energy,* 5(1), Summer 2000, p. 11-23. Symmetry represents a conservation law, and broken symmetry represents violation of that conservation law. Because of the broken 3-symmetry of the dipole, the EM energy flow is not conserved in three dimensions — in this case, violation of conservation of 3-space EM energy flow is not conserved. Neither is the time EM energy flow conserved in the 4th dimension. Instead, EM energy flow is conserved in 4-dimensions, between the inflow in the time-domain and the outflow in 3-space in all directions, or vice versa. The hidden inflow of EM energy to the dipole (and to a charge) is actually from the complex plane (time domain). Thus all EM energy in 3-space is actually received by the source charge or source dipole from the time-domain, and returned to the time domain. What we call "propagation of EM energy through 3-space" is actually the spreading of this 4-circulation to successive 3-space points. The importance of the internal structuring of time-flow and of longitudinal EM waves in the time domain (dimensioning in the time-domain) is apparent, since it produces very powerful engines that can act upon matter in any fashion desired. Indeed, the Russians have developed clandestine robot engine systems comprised of sets of spacetime curvatures and their dynamics (which are just sets of longitudinal EM waves and their dynamics). Any function of a weapon system — sensing, weapons (using scalar interferometry), communications, propagation, etc. — can be incorporated. The capabilities of such systems, such as travel through continuously emitted EM signal beams from satellites, communications stations, power lines, etc., is eerie. Such a system can reside in any convenient EM potential or field as a "dimensioning" of the potential or field. Such robot engine systems have been clandestinely tested, but discussion of them is beyond the scope of this book. Suffice it to say that these systems are ushering in a dramatic revolution in future warfare, and the present research in physical nanobots is already decades behind.

Very powerful support for the author's solution of the source-charge problem is given by F. Mandl and G. Shaw, *Quantum Field Theory,* Wiley, 1984, Revised edition 1993, under the heading "Covariant Quantization of the Photon Propagator" in Chapter 5. In their deeper coverage of the photon polarizations, Mandl and Shaw point out that the longitudinal and scalar polarizations are not directly observable, but only in combination, where they manifest as the "instantaneous" Coulomb (i.e., electrostatic) potential.

Translated from particle terminology to wave terminology, Mandl's and Shaw's argument directly fits my re-interpretation of Whittaker's 1903 decomposition of the scalar potential.

Dirac, Paul A. M.: Noted English physicist, 1902-1984, who shared the Nobel Prize for developing wave mechanics and predicting the existence of the positron. He also originated the notion of "holes" or negative energy s**tates** in the vacuum, where the holes are ordinarily filled with electrons. The "vacuum replete with these Dirac structures" (all filled with electrons) is referred to as the *Dirac Sea.* If some of the holes are empty, then that is **the** Dirac sea of a curved spacetime. We strongly stress that a Dirac sea **hole** (negative energy electron with negative charge, negative energy EM fields and potentials, and with negative mass-energy) prior to observation (prior to its reaction with mass) is a quite different entity from the positron (after reaction with mass, so that the positron has positive mass-energy, **positive** charge, positive energy EM fields and potentials, and has been reversed in its 3-space propagation direction). Specifically, the Dirac sea **hole** produces negative energy fields and potentials, whose powerful Heaviside nondiverged components enable to perform practical antigravity. The (observed) positron produces gravity, not antigravity, and also positive energy fields and potentials.

Dirac sea: A concept and description (modeling) of the vacuum as containing — amongst other things — a "sea" of an infinite set of negative energy slates ("holes") for electrons, almost all of which are usually filled with electrons in the absence of any spacetime curvature of significance. In Dirac electron theory, the relativistic wave equation for the electron has four components, which correspond to two spin orientations and two energy conditions: positive and negative. Ordinary electrons are in the positive energy condition. So then the vacuum must also possess a "sea" of negative electron energy conditions. These negative conditions are called "holes" and are ordinarily filled or mostly filled with electrons which have fallen into these negative energy states. The Dirac sea is this vacuum sea of negative energy electrons (and a perhaps a few empty holes). In forward time, if energy is added to a negative energy electron, electrons can be **lifted** from this sea, since the added energy creates a local curvature of spacetime. If spacetime is locally curved, additional holes may be created so that, when the holes meet normal positive energy electrons, the electrons fall in and disappear, creating the appearance of an "electrical energy sink." This can happen so that the local ST curvature merely relaxes back to an uncurved spacetime, therefore avoiding radiation from "pair annihilation". If the curvature is in the opposite direction (i.e., if positive energy is added to the vacuum), electrons may be lifted from the Dirac sea by the resulting spacetime curvature energy, thus producing a flow of electrons "right out of the nonlinear vacuum" and generated by the spacetime curvature, and creating the appearance of an "electrical energy source" from the vacuum itself. In that case the energetic holes left behind also remain, and are affected by all EM fields etc. These holes thus form negative energy currents, fields, potentials, waves, and other electromagnetic entities such as negative energy charging and discharging (excitation and de-excitation).

In an overunity EM system, there is a higher energy density in the output section than in the input section. This includes time-energy density. So a higher tempic potential exists at the output than at the input. A gradient in the tempic potential thus exists, which constitutes a tempic force from the output section back through the system to its input section, and even on back through the conductors to the external power source, and even back into the distant external power source itself. Thus the power source has to furnish additional electron current. It must "power the holes", so to speak, by furnishing the electrons that are "eaten" by the Dirac hole current to eliminate it, which represents a novel kind of load in the input section of the system. So the power supply must furnish more power, so as to furnish the normal power to power the system, and the extra power to "power the elimination of the Dirac sea hole current as a back-reflected load". This is nature's way of decaying the excited state represented by COP>1.0, and restoring equilibrium and COP<1.0. By the Bedini process, the otherwise detrimental Dirac sea hole current reaching the input section is transformed into ordinary electron current, thus serving as input power to the system. By adjusting the system and optimizing it, this strange kind of "positive power input from converted Dirac hole current negative power feedback" can be adjusted to equal the input power required by the system. At that point the external power system can be disconnected, and the unit continues in close-looped and self-powering operation, including powering its load as well. Gabriel Kron succinctly described this condition and adjusting for it. Such a system allows energy to be continuously extracted from the vacuum, and a load to be powered continuously, with all the energy to run the extracting system being freely received from the active vacuum.

Dirac sea hole: A negative energy state for an electron, in the Dirac theory (in the Dirac sea). Literally the hole (negative energy state) when not occupied by the electron. In flat spacetime, almost all Dirac sea holes are filled with electrons. A small fraction on the average are not filled due to the local fluctuations of the vacuum energy continually lifting electrons from their holes and then having them recombine, usually so quickly that no radiation occurs in the observable state. The situation in the virtual state can be described by Feynman diagrams. This received view can be falsified in a curved spacetime. There the holes can exist and flow as currents, as validly as positive energy electrons can flow as currents, without the incessant "filling" activity of the vacuum itself. In addition, in such a hole-stabilizing curved spacetime region, the hole can "eat" or recombine with a real electron, so that the electron vanishes but without radiation. If we wish to join the two views, then we take Feynman's and Wheeler's view that the field does not exist in vacuum as such, but only the potential for it exists — in short, only the engine exists. The engine can then be said to be an ordering (chaotic self-ordering) condition present on the statistical random variation of the fluctuations of the vacuum. With longitudinal EM wave technology, this "order in the midst of disorder" — this templating and engine technology — can be directly engineered.

Dirac sea hole current (positron current): Just as a current of positive energy electrons can be generated, a current of negative energy Dirac sea holes can also be generated if the local spacetime is properly curved. Mathematically these are usually considered to be "positron currents", except they have no positive mass, because a hole will "eat" an electron. In an overunity electrical power system, the tempic potential is greater at the output of the system than is the tempic potential at the input section. There thus exists a "tempic force" or "tempic broom" sweeping Dirac sea hole current (positron current) out of the input section of the system into the external power supply. Simple instruments will record this current as if it were electron current being furnished from the external power supply to the system. Also, the Dirac sea positron current will "charge" the battery with Dirac sea holes (mathematical positrons), which in the conventional sense discharges the battery. A battery may become highly charged with Dirac sea holes. If so, then when placed on a normal battery charger, the electrons in the charging current will be "eaten" for an extended period by falling into the Dirac sea holes, and the battery will not acquire any charge until they are filled — whereupon the battery will sudden begin charging up normally again.

We also point out that the vacuum, containing the Dirac sea, actually is not "massless" at all, but has zero resultant mass on the average, as a result of the simultaneously presence of positive and negative mass in average equal abundance. Any curvature of spacetime must violate this "net sum zero" mass, hence produces inertia in all masses. Note that a negative mass can also exhibit a negative inertia; i.e., it accelerates and enhances the action of any force acting upon it, instead of opposing it. In short, negative mass exhibits negative inertia. We suggest that this effect is probably involved in the more violent explosive phenomena of astrophysics.

disequilibrium: Broken equilibrium, which in turn involves breaking appropriate conservation laws unless compensated.

displacement current: The apparent continuation of a conduction current through a region of space without a conductor, e.g., between the plates of a capacitor. Rather than being the motion of charges in a conductor, the displacement current is related to the rate of change of an E-field, and thus to the rate of change of the strain of the dielectric.

dissipative structure: In open systems far from thermodynamic equilibrium, a region of self-ordered behavior of a special kind in matter, characterized by symmetry-breaking, multiple choices, and correlations of macroscopic range. By correlations we mean statistically reproducible relations between distant parts of the system. Formation of a dissipative structure represents the birth of complexity in that region by self-organization. Usually a dissipative structure emerges only after the driving constraints reach a critical value. As the embryonic "engine" technology advances, however, the direct engineering and control of dissipative structures will become commonplace and routine.

distortion correction theorem: "If a scalar wave $E_1(r)$ propagates from left to right through an arbitrary but lossless dielectric medium, and if we generate in some region of space [say near $z = 0$] its phase conjugate replica $E_2(r)$, then E_2 will propagate backward from right to left through the dielectric medium, remaining everywhere the phase conjugate of E_1." Quoted from Amnon Yariv, *Optical Electronics*, 3rd Edn., Holt, Rinehart and Winston, New York, 1985, p. 500-501.

What is missing from the distortion correction theorem is hidden in the phrase *"if we generate in some region of space ... its phase conjugate replica. "*. Since electrodynamicists and optical physicists have been unaware that all EM energy at any point in space comes from the time domain to that point, then —*prior to detection by interaction with charge* — the actual phase conjugate wave exists in the imaginary plane (in the time domain) and *not* in 3-space. The continuous interaction of that imaginary plane wave with charges, to actually produce the force-field wave in space, is *assumed* in the standard nonlinear optics. In short, one is looking at the "effect" wave, not the "cause" wave. However, since time is not an observable even in theory, it is this "effect" wave in 3-space that will indeed be measured by our instruments, because they must interact the imaginary or phase conjugate field with charge in order to detect or observe it (measure it).

The proof of this is experimentally already known but not recognized. If one reflects an EM wave off a normal mirror, the mirror must absorb the incoming wave, which transfers the wave momentum to the mirror to repel it, then the mirror must re-emit it, which adds that much more momentum to the recoil. So the mirror recoils with twice the momentum of the reflected wave. That produces a wave going in the other direction. If the incoming wave is continuous, one then has "paired" waves going in **opposite** directions). However, if an incoming wave strikes a phase *conjugate* mirror (PCM) material and is phase conjugated, a wave going in the opposite direction also emerges, but it synchronizes point by point with every spatial point occupied by the incoming wave. Also, *the phase conjugate mirror does not recoil at all.* This is well known in phase conjugate optics. It clearly shows that the origin of the "detected" phase conjugate wave is quite different from that of a normal reflected wave. Indeed, by our reinterpretation of Whittaker's 1903 biwave decomposition of the scalar potential, at every point along the detected phase conjugate wave, the energy enters that point from the time domain, and not from some sort of reflection from the PCM. The energy also returns to the time domain from that point. Its presence at the point produces a separation of virtual point charges, or the well-known polarization of the vacuum. So the flow of energy is from the time domain to the negative charge of the point dipole, thence to the positive charge of the dipole or others immediately surrounding it, thence back to the time domain. That is the operation in a "time-forward" sense to the external observer. In a "time-reversed" situation, the 4-circulation appears in the opposite direction. We propose that this fundamental 4-circulation is responsible for and constitutes spin itself. The direction of flow determines the 'polarity of the charge" we obseve. In this view, the point dipolarity in the virtual state with its ongoing 4-circulation can be taken as the very definition of energy itself.

Druge, Paul: Important German physicist, 1863-1906, who formulated the theory of the free electron gas inside conductors, using it to formulate a theory of metallic resistance.

Drude electron gas: The electrons that have broken loose from their orbital bonds in atoms in a conductor, and are thus free to "wander around" and "migrate" — or flow as current when exposed to an emf. Also called just the "electron gas". Note that, in the metal lattice of the conductors, each position vacated by a Drude electron is a "hole" or positively charged little region. Not only do electron currents exist as net negative charge migration in conductors and materials, but also hole currents exist as net positive charge migration from atom to atom, or a sort of "ionization migration flow". Electrons are continually recombining with these "ion holes", however, to reduce the hole current. These considerations are particularly significant in semiconductor materials.

duality principle: In quantum mechanics, the principle that photons and other particles propagate like waves and interact like particles, so that their description as only waves or only particles is inadequate.

Edison, Thomas Alva: Noted American inventor, 1847-1900, whose staggering portfolio of inventions included the storage battery, electric light bulb, phonograph, motion pictures, carbon microphone, and many others. Edison actually ran multiple "patenting research" laboratories as discovery and patent generating facilities. Not only was he an inventor himself, but he also employed a very good staff of researchers for invention and discovery.

E-field (electric field): The electric field intensity E; that field on an electric charge (charged mass) which produces an electrical force resulting in a linear motion of the charge. In reality, this electric field *as usually defined* does not and cannot exist in empty space devoid of charge, but only in and on charged matter, since mass is a component of force by $\mathbf{F} \equiv \partial/\partial t(m\mathbf{v})$. More specifically, the E-field is the local intensity of the field at a point, in its interaction with a unit point static charge fixed at the point. Even more specifically, it is the output of an observation/detection operation, which is a *d/dt* operator imposed on the 4-space causal field interaction with the 3-space charge, resulting in a frozen 3-space "slice" or snapshot of the deviation of energy *from* the field, forced to flow around that intercepting charge, at that single instant. In short, the E-field as a force field is an *effect* and not a *cause.*

The greatest error in all electrodynamics is to then assign this same *frozen effect force field intensity snapshot* — or an implicitly assumed iterative sequence of such snapshots — as the dynamic and nonfrozen *causative field itself in* 4-space, prior to the field's interaction with charged matter. This is the substitution of effect for cause, a grave non sequitur.

When EM theory was founded, the founders believed there was no single **point** in the entire universe where mass was absent; instead, a thin material "luminiferous ether" was considered to fill all space. Time was considered immutable, and there was no concept of a dynamic *spacetime.* Hence at each point in such a material ether, the reaction with charged matter (etheric matter) was thought to universally exist. Hence the field was indeed a very material entity, in their concept!

With the destruction of the material ether notion in the 1880s, not a single Maxwell-Heaviside equation was changed to eliminate its implicit assumption of the material ether. Hence this enormous error of confusing the *effect* field with the *causal* field (prior to observation-detection-interaction) is ubiquitous in electrodynamics and therefore in physics itself. The two fields (causal and effect) do not even have the same dimensionality; one is dynamic in 4-space while one is frozen in a 3-space snapshot. This has led to the false notion that an EM force field wave "movesthrough" 3-space, which does not happen at all. What really happens is that, if we assume a continual iterative *d/dt* observation operator, we have a continual series of such frozen 3-space snapshots, like the frames of a motion picture film. But none of those snapshots have any inherent motion at all. For a statement of the falsity of the conventional illustration of the "EM wave in space as an orthogonal pair of oscillating E and H fields in a transverse plane", see Robert H. Romer, "Heat is not a noun." *American Journal of Physics,* 69(2), Feb. 2001, p. 109. In endnote 24. **p** 109, AJP editor Romer takes to task *"...that dreadful diagram purporting to show the electric and magnetic fields of a plane wave, as a function of position (and/or time?) that besmirch the pages of almost every introductory book. ...it is a horrible diagram. 'Misleading' would be too kind a word; 'wrong' is more accurate. " "...perhaps then, for historical interest, [we should] find out how that diagram came to contaminate our literature in the first place.* "Also see charge.

E-field, **motional:** In classical EM theory, the electric field produced by moving a conductor in a magnetic field. Often called *motional inductance* of the field. In the conventional theory, motional inductance is deemed to be identical to the inductance caused by a time rate of change of the magnetic field, experienced by the moving conductor. Or vice versa, experienced by a stationary conductor in a moving magnetic field.

E-field, static: In conventional theory, the electric field in the space surrounding a static charged particle, induced by the presence and action of the charged particle. There is no notion as to the *causative mechanism for this static* field of and from a charge, which implicitly is assumed to just continuously create and pour out EM energy in all directions, thus grossly violating energy conservation. Consideration of this anomaly leads to what has been called the most pressing problem in both quantal and classical electrodynamics: the question of the formation of the fields and potentials associated with the "source charge". Either the charge totally destroys the conservation of energy law itself, or there must be a *virtual* (nonobservable) energy input to the charge, since instruments establish that no observable EM energy is input to it.

For a solution to this problem, see the present author's "Giant Negentropy from the Common Dipole," *Journal ofNew Energy,* 5(1), Summer 2000, p. 11-23. We later found our solution to be consistent with quantum field theory and with a slight reinterpretation of Whittaker' s 1903 decomposition of the scalar potential.

Ehrenhaft, Felix: Scientist who performed numerous experiments believed to demonstrate fractional charges. We point out that classical electrodynamics assumes a local flat spacetime, a notion long falsified by general relativity, since 1915. In a local curvature of spacetime, the dynamics of the charge (modern view as the finite difference between two local infinite charges forming a dipolarity) can change the observed value of the net finite charge. So finite fractional charges, or even supercharges, are quite possible.

Einstein, Albert: German (Jewish) physicist, 1879-1955, who emigrated to the U.S. and formed special and general relativity theory, discovered and formed the theory of Brownian motion, recommended the development of the atomic bomb to President Roosevelt, and profoundly affected the course of science and the modern world,

Einstein, Podolsky, and Rosen (EPR) paradox: Thought experiment in 1935 for measuring two correlated photons separated and at distant locations, protesting that quantum mechanics requires that the particles communicate instantly, which is a "spooky action-at-a distance" (Einstein's phrase). The experiment eventually was performed and it works, just as required by quantum mechanics. The paradox inspired the development of hidden-variable theories.

Einstein's general theory of relativity: Mathematical theory of gravitation in which the gravitational force is mathematically described by a curvature in spacetime. In other words, the geometry and its dynamics have become physical agents, doing away with the old notion of the agent being something separate that is occupying inert spacetime. It is important to note that, in general relativity, mass-energy acts on spacetime to curve it, and the curvature of spacetime acts back on mass-energy to translate or change it. What seems missing from GR — at least in its practice — is the reaction of time-energy upon the geometry to curve it, and that corresponding reaction of the spacetime curvature back upon time and time-energy to change it.

Further, we consider that an exact pattern (template) of curvatures of spacetime and their dynamics exists and is back-acting upon every mass system and its dynamics. This is the *engine* concept. The most general way to engineer matter is not by brute force translation forces, but by forming spacetime engines. Once formed, these engines act upon the interior of any mass placed in the engine region, to eliminate the deltas existing in that muss's resident engine and the impressed engine. *The forces arise from the local spacetime itself, as curvatures in that local spacetime, so the action is from "inside" to "outside" an object, starting and continuing from every point in the object.* The curvatures of spacetime itself furnish the energy for the continuing actions upon the interior of the mass, once we have paid to form the engine. The mass can be acted upon at any level, from its gluons and quarks to its nuclei, to its atoms, its lattice forces and binding energy, etc. Significantly, the Sachs unified field theory applies to physical reality from beneath the quarks and gluons to the entire universe itself, and folds in quantum mechanics, electrodynamics, and general relativity into a single unified field theory that is (in theory) engineerable by higher symmetry electrodynamics means such as Evans' O(3) electrodynamics.

Einstein's postulates: (1) All the laws of physics are equally valid in all inertial frames of reference, (2) the speed of light is the same to every inertial observer, and (3) the observable local effects of a gravitational field are indistinguishable from those arising from acceleration of the frame of reference.

The first is called the special relativity principle, the second is called the law of light propagation, and the third is called the equivalence principle. It is now known that postulates (1) and (2) are not independent of each other. Note that the third postulate implies that any local force is due to a "gravitational field" (acceleration of the frame of reference). It also implies that gravitational force has a mechanism, since quantum mechanics assigns a differential operator, operating upon a potential, to create every force. By extended inference, it can be seen that the third postulate also implies that there should exist a method to turn any type of force (field) into gravitational force (field).

Note that postulate 1 may be violated if two frames remain inertial but each local spacetime contains different hidden engines. So the laws of interaction physics may indeed vary for the same object placed in first one of the frames and then in the second. Engines are ongoing general relativity actions, even in inertial frames. The action may not be translation of the bulk object, but extensive changes to the interior of the object and its interior dynamics at any and all levels.

The Russian physicist Sakharov has strongly postulated that gravitation is not even a fundamental field of physics, of the kind used by Maxwell in his electrodynamics. Instead, in this view G-field is always comprised of, and made from, other fields and interactions upon them. This would seem to follow straightaway since change of any kind of energy in spacetime curves that spacetime, therefore producing a gravitational change. So such has always been implicit in general relativity; it just took Sakharov to formally propose it. See A. D. Sakharov, "Vacuum Quantum Fluctuations in Curved Space and the Theory of Gravitation," *Soviet Physics Doklady,* 12(11), 1968, p. 1040-1041 [English translation.] Sakharov's article (in Russian) in *Dokl. Akad. Nauk SSSR,* Vol. 177, 1967, p. 70-71.

Einstein's postulates (second postulate extended): Let us do a little "tinkering" with Einstein's postulates. For the first one, we point out that in the new approach using dimensioning and subspaces, the notion of an inertial frame now has acquired additional complexity! The "gross translation" effects — which tends to be what physics ultimately focuses upon today — can remain the same, and yet vacuum engines can be buried up inside the inertial frame to act upon a mass in non-translating ways. Everything translation-wise can remain the same, but now matter can be transmuted and transformed, etc., still right there in an inertial frame. So when the infolded electrodynamics inside all fields, potentials, and waves are utilized, the notion of "inertial frame" has acquired a higher topology, so that one inertial frame may differ very substantially from another inertial frame, even if the two are not in translation motion with respect to each other. This of course moves one from special relativity into full general relativity, and even there into a slight extension. Special relativity can remain special relativity on the surface, and yet general relativity effects occur "within" the objects postulated to exist in this inertial frame. The "inertial frame" concept in the postulates is now just a sort of special "equilibrium case" of a higher topology "inertial frame" notion. Further, general relativity is extended from the notion of "just translation" to the notion of "internal engines and internal dynamics also". These engines can be created in mass, in fields and potentials and waves, and in the vacuum itself.

The second postulate now stands as a "special case" of a far more general second postulate. The conventional second postulate actually defines (and limits) "light" to bulk changes in the entire vacuum potential magnitude. It only applies to light signals which are "bulk upheaval" disturbances of the vacuum potential (spacetime), so to speak. The limitation to light speed is an envelope wave speed restriction. Specifically it need not apply to the "inner EM/GR realm" of longitudinal EM waves infolded inside the vacuum potential, other potentials, signal carriers, etc. Superluminal communication is now included in this "hidden variable" or longitudinal EM wave communication. The Fogal semiconductor is capable of infolding and outfolding EM signals, including producing the internal longitudinal EM waves, and during their infolded state these signals are permitted to move at superluminal velocity. This has been experimentally demonstrated by Fogal.

So the second postulate needs to be restated to include the present statement as a special case. Notice that the concepts "light" and "speed of light" have now taken on much richer, extended meanings, since there is "outfolded" light and "infolded" light, so to speak. Light now is not just the "external perturbation wave" in the ambient vacuum potential medium (in flat spacetime). Instead, it can also be an "internal perturbation longitudinal wave" inside a "net flat spacetime" which does not show on the "surface" at all. Indeed, it may move in the time dimension or in 3-space. It now includes the transmission of an extraordinary "vacuum engine" as well as the usual transmission of just an ordinary signal. The ultimate expression of this extension has unfortunately been the development of such "engines" as infolded robot systems for use in warfare.

These infolded vacuum engines can be visualized as very special sets of longitudinal EM waves and their dynamics, consistent with the Whittaker decomposition. Whittaker's U(1) symmetry electrodynamics decomposition— particularly when enriched in the higher symmetry O(3) electrodynamics — applies to the ambient vacuum as a potential (it is a potential since it has energy density). So the "subspace" inside spacetime, so to speak, is just a set of LWs and their dynamics, and that subspace itself is engineerable, just as is the "bulk curvature of spacetime" itself. Further, we may now consider that space itself is just a vast superhighway for such superluminal LWs and their dynamics. Mass is mostly empty space with only an occasional particle here and there and with fields, potentials, and waves in between. Hence huge masses such as the ocean and earth are actually superhighways for the direct passage of longitudinal EM waves, "engines", special robots, etc. The degree of "transparency" is a function of the degree of cleanness of the LWs — where by "clean" we mean "absence of transverse EM wave residues".

The third postulate has also been dramatically extended and requires revision. As presently stated, antigravity effects do not appear to be included in present physics heretofore. The "gravitational effects and external accelerated effects" notion in conventional physics are still founded purely on *ordinary bulk translation.* Now they need not be. For example, the system can appear to be an ordinary system, as judged by normal "external light" observation. Yet its internal vacuum engines can cause local violation of most so-called "laws of nature." The reason a "law of nature" can be violated is that one is now able to violate the premises upon which it is postulated, and which are required to hold if the law is to hold. Or another way to look at it: any conservation law is the result of a symmetry. Breaking that symmetry allows violation of that specific conservation law. All external symmetries can be broken internally, even if the overall symmetry still applies externally!

The infolded EM inside the "conventional" EM fields, waves, and potentials — and inside the vacuum potential and spacetime itself-dramatically changes the present theories of electromagnetism, quantum mechanics, and general relativity. Further, for the first time the Sachs unified field theory allows an *engineering* approach that simultaneously crosses, includes, and extends all three disciplines in the required manner. The approach can be placed into good engineering models based on the Sachs work, particularly using the O(3) electrodynamics subset spearheaded by Evans, and the models can be tested and verified or falsified. See **frame, reference;** and **superluminal communication.**

electric field: (See also discussion under **E-field).** The *conventional* definition is this: "1. a region in space in which a stationary electric charge experiences a force due to its charge. 2. the electric force per unit test charge." Quoted from *Dictionary of Science and Technology,* p. 720. That definition is flawed. Consider the "spatial aspects" of part 1. If an electric field is defined as a force per unit charge (per Part 2), it is not a region in massless space but is an effect of something existing in massless spacetime and interacting with the charged 3-spatial mass. The electric field *prior to interaction and observation of the interaction* is indeed related to a region in "spacetime", because it is identically a curved spacetime region. In the Sachs approach, general relativity and electrodynamics have become one and the same. So prior to interaction, the *field as it independently exists prior to interaction with charge* has become a curved spacetime region, and the field-in-space is *purely* a spacetime curvature. Again, there is no such thing as a massless force. It is the hoary old mechanics notion of a separate force acting upon a separate mass that is a total non sequitur. The interaction of the massless field in space with a mass to produce a force, *of **which** that mass is actually a component,* is a separate consideration from the field as it exists in space prior to interaction. The result of this entity's **interaction** with charged mass has nothing to do with *what an electric field* is but with *what it does to charged mass.* Further, the force evidenced on a charged particle is not due to its charge; the particle has that charge always, whether or not there is a net force evidenced on it!

Part 2 is a little better. The only problem is, it totally disagrees with the notion of the field as an entity existing in spacetime prior to interaction **with** charged mass. In other words, here it's a "force on a charge", which is an effect (force consisting partially of the charge) occurring after the interaction. Again, the conventional definition states only what the field *does or accomplishes,* not what it *is.* Hopefully the reader can now begin to see what terrible difficulties await anyone who seriously attempts *foundations definitions.* Feynman sums it up admirably in one of his famous statements: "*Everything we know is only some kind of approximation, therefore, things must he learned only to be unlearned again or, more likely, corrected.* "An additional difficulty is that the very **notion** of a separate massless force — independent of the mass on which it operates - is fictitious, yet continues to be widely used. Recalling that any true definition is an identity and not an equation, let us start with the definition of force: $\mathbf{F} \equiv d/dt(m\mathbf{v})$. As can be seen, force is a system **comprised** of (i) a mass component and (ii) a nonmass component. The force is not something separate from the mass, at all! Further, force is not **even** unitary. It's a system comprised of two coupled components; the mass and **a** coupled (interacting) gradient in a potential flux. *Note that v involves motion through, and interaction with, the virtual flux comprising the vacuum potential. Note that dv/dt involves a gradient in that flux interaction with the mass.* Unfortunately mechanics is still using the medieval concept of a "separate force acting upon a separate mass." That is wrong, unless we change the fundamental definition of force itself. See, e.g, **Robert** Bruce Lindsay and Henry Margenau, *Foundations of Physics, Dover P*ublications, New York, 1963, p. 283, where the authors emphasize that a "field of force" at any point is actually defined only for the case when a unit mass is present at that point. The reason can be seen: mass is a necessary component of force, and without mass present there cannot be a force present. For that reason, the force field in matter is a quite different beast from that "same" force field in empty spacetime. The first is a 3-spatial snapshot of an ongoing 4-spatial interaction, while the second is just a curved region of that "empty" spacetime without any ongoing reaction necessarily.

electric dipole: See **dipole.**

electrodynamicist: A specialist in electrodynamics — the physics of the relationships between electric, magnetic, and mechanical phenomena — and especially a specialist in electrodynamics *theory*. Essentially all electrodynamicists are versed in U(1) electrodynamics, and a much smaller number are versed in more advanced (higher group symmetry) electrodynamics such as O(3) symmetry electrodynamics, unified field theory electrodynamics, non-Abelian electrodynamics, etc. The electrodynamics field is actually a very vast field indeed, touching everything in physics, chemistry, etc. When one needs a particular electrodynamics problem solved, it often calls for a special category of electrodynamicist and not just an electrodynamicist in general. One must therefore sometimes examine the background of the electrodynamicist making a statement or a pronouncement; electrodynamicists after all do have differing views and differing disciplines within the field. And something may be perfectly true and acceptable in O(3) electrodynamics, yet not even exist in U(1) electrodynamics. As an example, the Aharonov-Bohm effect exists in O(3), but not in U(1). U(1) assumes a flat local spacetime (falsified by general relativity almost a century ago) and an inert vacuum (strongly falsified by modern particle physics and quantum mechanics), while O(3) is perfectly content to include and model curved spacetime and active vacuum also.

electromotive force (EMF): A difference of potential created by sources of electrical energy — i.e., by separated charges (dipoles) — which can be utilized to drive electrical currents through external circuits. As a difference of potential, that constitutes a gradient and hence a force. Also, open circuit voltage, or the limit of the potential difference between the source's terminals as the current in the external circuit approaches zero.

This term is poorly named and also quite confused in the standard theory and usage. First, em/is supposedly not a *force* at all. It is a difference in potential; hence it is measured in volts. It is very difficult to imagine a "difference in potential" at a single point unless one is dealing with a multiply connected space. So if the difference in potential is between two adjacent points, then that constitutes a force between the two points. Also, emf is not considered an E-field, since that is a field of force. Yet it is in fact a $\nabla\phi$, restricted to the direction between the two measurement points, and $-\nabla\phi$ is considered to be an E-field in the EM theory! As can be seen, o**ne** will not find a truly logical definition of potential or emf in the present texts and science literature.

For this reason the standard theorists say that the term emf is sometimes used as equivalent to a difference in potential, but that strictly speaking it s**hould** be applied only to a source of electrical energy. The problem is that **most** conventional theorists are unaware that a potential *identically is* a bidirectional flow of energy in 3-space, but a 3-space flow where *the* energy *enters from the time-domain (complex plane) and is caught in 3-space by interaction with charge, in a frozen snapshot (observation). The energy actually enters each 3-space point in the 4-space potential, from* the t*ime domain.* It moves across a dipole in space (present due to the quantum mechanical polarization of the vacuum), to the opposite charge, thus returning from the immediate region of that second 3-space point (or points) back to the time domain. Since conventional theorists are unaware that a potential is a hidden negentropic energy flow circulation process involving broken 3-symmetry, broken t-symmetry, and a special 4-symmetry between t and 3-space, the theorists have been unable to consider the potential in general as a direct source of energy flow. Yet they are forced to consider a potential difference across the terminals of a source as "somehow a flow of energy, that generates forces upon the electrons to propel them through the circuit as current flow."

In the new viewpoint, a resolution is achieved of these incongruities by more accurately defining the E-field with respect to the potential as $\mathbf{E} = -[\nabla\phi \bullet q]/|q|$. It is noted that $-[dA/dt] \bullet q/|q|$ also produces an E-field, so **that the ful**l definition of the E-field $\mathbf{E}$ is $-[(\nabla\phi + d\mathbf{A}/dt) \bullet q]/|q|$. Note that dividing q by |q| does not remove the q unit from the corresponding dimensional equation, since $|q|$ is dimensionless. However, one volt represents one joule (of excess energy) *diverged from the potential,* per coulomb of interacting charge. *The energy density flow in an electric circuit is in the voltage, in the emf, and it is not in the current per se.* The electr**on** current (drift current) carries the excess energy that is being dissipated as work in the circuit, but in a nominal circuit the drift current only moves a few inches per hour. Half the energy collected in the potentialized circuit is dissipated in the external circuit and external losses, and half is dissipated in forcing spent electrons in the ground return line back up **through** the back-emf of the source, performing work inside the source to dissipate its separation of charges. Left alone, any dipole will furnish emf indefinitely, freely receiving the energy from the time domain (complex plane) and outputting it in 3-space via the reinterpreted Whittaker 1903 decomposition, in a circulation where at each point in it the energy enters from the time domain and thence returns back to the time domain. The free flow of EM energy will continue unabated from the undestroyed dipole, regardless of how many external loads and losses are powered (how much energy is collected and dissipated from the ongoing flows representing the potential). So *electrical circuits should be developed which allow few or no electrons to be forced back up through the source dipole to dissipate its separation of charges and destroy the dipole.*

electromotive force, back (back emf): Back emf is a loose term for the *counter-electromotive force.*

When the source is powering a circuit or circuit element, the term "back emf is used to refer to the forcing of current (electrons) back up through the source against its emf, thereby performing work inside the source to *dissipate* its separation of charges (its dipolarity). When a potential source of electrical energy — such as a capacitor, an inductor, or a rotating machine — is receiving energy from a source and converting it to *dissipative* power and work, that "powered" device is said to develop a *counter-emf.* A source has a built-in emf *a priori,* and this emf is holding its charges separated so that it is dipolar. When electron current is forced backwards through the source against its emf, work is performed against the internal resistance of the source to dissipate its separation of charges, thereby *dissipating* the source dipole. If electron current is not allowed to flow back up through the source against its back emf and through its built-in counter-emf, no dissipation of the source dipole occurs, even though energy density (not *electron current* dq/dt but *energy flow* dq/dt) is flowing from the source and can be collected in *collectors* in the external circuit to store the energy as a created local energy source. This collected energy can then be shuttled to a separate load circuit and released, to provide a "heat pump" cycling operation and overunity coefficient of performance.

Nikola Tesla in fact knew how to shuttle energy at will in a circuit in such fashion, as Barrett's quaternion analysis of Tesla's actual patented circuits has revealed. [See T.W. Barrett, "Tesla's Nonlinear Oscillator-Shuttle-Circuit (OSC) Theory," *Annales de la Fondation Louis de Broglie,* 16(1), 1991, p. 23-41.] Note that a rigorous analysis of those same circuits, using tensors or vectors (lower topology algebras), will not show the effect. One

needs a higher-topology algebra such as quaternions or Clifford algebra, or **the** significant properties of such circuits will be entirely missed.

When the original source dipole is not dissipated because electron current is **not** passed back up through its back-emf to scatter the charges, the o**riginal** source dipole will continue to furnish emf indefinitely because of **the** proven asymmetry of its opposite charges in the seething vacuum energy flux.

The terms emf and counter-emf are normally applied only to recognized sources of electricity. Emf is computed as the algebraic sum of the **potential** differences acting in a circuit attached to a source. Back-emf (counter-emf) is computed as the potential difference internally through the source, between its terminals. The back-emf is thought to be necessary in producing *a powered device or component in the circuit.* Actually, *its **main** application (the ubiquitous closed current loop where all the external circuit current is passed back through the back-emf of the source dipole) is to prevent COP>1.0 electrical power systems from being developed and utilized, andfor every electrical circuit to self-enforce Lorentz symmetrical regauging during its de-excitation phase.*

elect**ron:** A stable elementary particle in all atoms, and having — in "f**orward** time" — a negative charge of 1.602x 10^{-19} coulombs, a spin 1/2, *and a* mass of 9.11x10^{-31} kilograms. If time is reversed, the charge (but not the masss) of the electron is reversed and it becomes a positron. Note this is an equival**ent** *observed* 3-positron, in a material lattice after interaction with charged matter, and not the mathematical equivalent represented by Dirac sea holes in the 4-vacuum prior to interaction with mass.

The "electron" may also exist as a negative energy, negative charge, negative mass-energy 4-state (Dirac hole) in the vacuum itself. In that state, the negative energy 4-electron is the source of negative energy fields and negative energy potentials. When the associated nondiverged and unaccounted Heaviside energy flow component is also accounted, the Dirac sea hole negative energy 4-electron can be manipulated in "anti-circuits" to directly engineer local antigravity, quite strongly and practically.

electron gas: A system of electrons with only weak interactions, so that the electrons may be regarded as moving independently. In many ways, such a collection of electrons can be treated as a gas. See Drude Electron gas.

electrostatic scalar potential: A *static* (stationary, in the sense that a perfect waterfall would appear stationary) ordering in the virtual photon flux of vacuum. The notion of "static" in the term "electrostatic" is misleading and should be replaced by "stationary" since the underlying active vacuum medium is always in violent motion, and there is nothing truly "static" in the universe. But an *equilibrium* or *stationary* condition can exist as an external envelope condition, even with continuous violent motion internally, so that a stationary entity or form persists. An example is a perfect whirlpool in a river.

The electrostatic scalar potential decomposes into a harmonic set of bidirectional phase conjugate longitudinal EM wavepairs, as shown by E. T. Whittaker in 1903. Hence the electrostatic scalar potential is an overall curvature of spacetime with internal longitudinal EM order and dynamics.

ELF: Extremely low frequency. Used to describe EM fields whose frequencies lie in the range from just above 0 Hz (direct current) to 300 Hz. This includes power line frequencies (60 Hz in U.S. and 50 Hz in Europe) and frequencies used by certain U.S. military ELF communication systems such as for submerged submarines.

EMF: Acronym for electromotive force. See discussion under electromotive force.

EM field: Electromagnetic field. In its loose usage, it refers in a very broad way to any field, force, or energy associated with electromagnetic interactions, charges and currents. Thus "EM field" includes electrostatic fields, magnetostatic fields, electromagnetic fields (including radiation and induction), vector-potential and scalar-potential fields, Hertz potentials, Fitzgerald potentials, Whittaker potentials, Debye potentials, etc.

In its precise usage, "EM field" conventionally refers to an EM "force" field, such as the E-field, D-field, B-field, and H-field. In classical electromagnetics (CEM), as a holdover from the old assumption of a material ether, the force fields are considered (erroneously) to exist in mass-free space, and they are also considered to be the primary causes of electromagnetic phenomena. This is a non sequitur, and it involves substituting the effect for the cause.

In the new viewpoint, *the force* fields do not exist in vacuum, but only in and on and of the charged particles themselves, where mass is present to form one component of the force. The force fields are therefore effects and not primary causes. The primary causes of all electromagnetic phenomena is taken to be the potentials; however, the hidden

Stoney/Whittaker/Ziolkowski internal structures of gradient-free scalar potentials may interfere to cause potential gradients in and on charged particle systems. [In O(3) and other higher group symmetry electrodynamics, this internal structuring and dynamics is far richer.] This therefore includes distance-free scalar potential interferometry and action at a distance, as well as vacuum engines.

The new view uses Sachs' unified field theory, and considers that the EM field in the vacuum, or an EM potential in the vacuum, involves and identically is curvature of spacetime. It follows that the internal EM structures of "ordinary" EM are also spacetime curvatures, where the specific pattern of these ST curvatures constitutes a very special kind of spacetime engine that acts upon any local mass in a specific manner determined by the individual pattern of curvatures. Thus the new view is a unified field theory where GR has become EM and EM has become GR, and where higher symmetry EM — such as O(3) group symmetry EM — can involve or produce gravitational, temporal, and inertial effects as well.

EM force field in the vacuum (a false concept : The erroneous notion that there exist forces in the vacuum, so that the set of forces at a set of spatial points forms a force field. Presently classical electrodynamicists accept the same E-field in vacuum as exists upon a charged mass when the vacuum E-field interacts with that charge, but it is asserted that the force is zero. This is easily falsified by defining force F as $\mathbf{F} \equiv \partial \boldsymbol{p}/\partial t = \partial/\partial t(\mathrm{mv})$. By expanding the term on the right, one sees that both terms in the expansion include mass. Mass is thus a *component* of force. If mass is absent, there is no force present, thus no force field present. The field in space and the "same" field in mass differ precisely by a mass term in their fundamental units. The field in massless space may be taken as a curvature of spacetime. Zero field in space means a flat spacetime; a nonzero field in space represents a curvature of spacetime. A nonzero field in mass means a curvature of spacetime (a 4-space entity) interacting with mass (a previous 3-space observation) to produce a force consisting of that field and mass interaction. There is no separate force acting on a separate mass, and mechanics has been wrong in assuming on for hundreds of years. Instead, there is a force produced by the interaction of a massless 4-field (spacetime curvature) entity with 3-spatial mass. It is that *interacting and ongoing entity or process* that is a force field. Speaking of such a force field in space, is speaking of the force field that would exist in that space if every point had a unit point static charge and charged mass. As Feynman and Wheeler pointed out, no force field as such exists in space, but only the potential for a force field exists there, in case some charged mass is brought in to interact and have the forces developed upon its charges.

EM generatrix: Whatever generates electromagnetics, particularly the fields. Since all EM energy comes from the time domain and returns to it, time is the ultimate EM generatrix. The circulation of EM energy from the time domain to 3-space and back, or vice versa, is a function performed by the broken symmetry of every charge, considered as two infinite dipolarities with a finite difference that is the observed charge listed in texts and handbooks.

energetics: Energy as the primary thing in the universe. Rankine's term later raised to the forefront by Ostwald. Modern Russian term for advanced higher group symmetry electromagnetics, where the electrodynamics is a subset of an engineerable unified field theory. In the U.S., a model approaching the Russian model is given by Evans's O(3) electrodynamics as a special subset of the electrodynamics used by Sachs in his epochal unified field theory. Thus there is a growing, engineerable unified field theory (energetics theory) in the U.S., being provided by Evans, Sachs, and others. A solid basis for energetics can be realized from the giant 4-space negentropy EM energy circulation involved with every charge, so that all "EM energy in space" and time itself comes from that circulation.

energy: Usually erroneously "defined" as the "capacity to do work". This is a total misdefinition since it would define energy as the ability to change its own form. The closest to a legitimate definition of energy appears to be: *energy is the invariance of that which is varying* (Lindsay). However, note that this definition violates Aristotelian logic (but does not violate five-law logic developed in this book). Another try at it might be: *"Energy is any deterministic or coherent structuring, either dynamic or stationary, existing in the virtual particle flux of vacuum."* While that sounds good, it still involves the nonchanging aspect of the changing flux — much like considering a whirlpool in a river as being a "static" thing. So it is still "the invariance of that which is varying", which is an identity of opposites. We conclude that 4- or 5-law logic is necessary in order to define energy, since the defining logic must encompass the identity of opposites. Feynman simply stated: *"It is important to realize that in physics today, we have no knowledge of what energy is_."* [Richard P. Feynman, Robert B. Leighton, and Matthew Sands, *The Feynman Lectures on Physics*, Addison-Wesley, Reading, MA, Vol. 1, 1964, p. 4-2.]. In Aristotelian logic, there is no acceptable definition of energy. In 5-law logic, the second definition holds since opposites can indeed be identical. Now to more practical aspects:

For our purposes, there are three major types of energy in 4-space: (i) 3-spatial energy, which includes energy in one, two, or three of the spatial dimensions, (ii) mass-energy, which is 3-spatial energy compressed by the factor c^2 but still in 3-space, and (iii) time-energy, which is 3-spatial energy compressed by the factor c^2 but now placed in the time domain. **Note t**hat time-energy has the same density as mass-energy, and hence the same spacetime-curvature effect and gravitational capability.

The major implication of the new view is that the conservation of energy law is extended: Now it is the total of the 3-spatial energy, mass-energy, and time-energy that must be conserved. Transduction between time-energy and either of the other two forms, or both, will violate the conventional conservation of the sum of the 3-spatial energy and the mass-energy; every charge and every dipole is an example. Use of time-polarized and longitudinally polarized photons and EM waves particularly may involve the extended conservation law, e.g., as utilized in cold fusion and its lime reversal zones, and as involved in the outpouring of observable EM energy from every charge in the universe, with no observable energy input.

energy collection/collecting: In electromagnetics, placement of an interceptor/collector — e.g., a charged particle — into an impinging EM energy flow, so that some of the flow is diverted around the intercepting particle. We may say that the flow of energy has been "reordered" into a stream diverged around the intercepting charge. The diverged part of the total energy flow is what is calculated as the Poynting energy flow component, and is what is referred to as the "collected" energy or the "potential" of the charge.

However, neither charge nor potential are acceptably defined in conventional electrodynamics, but they can be defined in the new approach. We are now able to see something more fundamental. By the giant negentropy mechanism, the charge is involved in both the time-ene**rgy** stream and the vacuum flux set of virtual particle spatial-energy stream**s.** "Charge" is not just related to the mass of the particle, but is the entire ongoing set of the dynamics as well as the mass (the "nondynamics", so to speak). When a charge is placed in a field, that field is a change to the local dynamics, which is a change to the charge itself. Both the dynamics and the mass (the "nondynamics" constituting the charge are altered. So one does not have the "field acting on a separate charge", but instead we have the charge with its previous set of dynamics transformed into the altered charge with a new set of dynamics and a new mass. Similary when a charge is placed in a potential. Charge is also not a 3-

spatial situation and process, but a 4-spatial situation and process. If the internal structuring is also important, it becomes an n-spatial situation where n>4 and even where $n \gg 4$. To deal with sophisticated engines, $n \gg 4$ is necessary in the modeling utilized.

energy dissipation: Refers to the scattering or disordering of energy; at fundamental basis, it refers to the changing of an altered charge (see energy collection/collecting) back to an unaltered charge. In other words, it is a special decay process whereby an "excited charge" (so to speak) decays back to its "normal state" by releasing dynamics (energy) back to the vacuum. The energy itself is not destroyed, but its "collecting pattern" or "flow pattern" as coupled to the charge is disrupted and altered or destroyed There is also the connotation that *the dissipated energy is lost as far as any re-use of it by the system.* We point out that only collected/collecting energy can be scattered; it is the collecting *process* (the entire alteration of the normal charge dynamics) that is "destroyed" - or more exactly, *transformed* — not the energy itself.

energy, electromagnetic: From a vacuum and quantum mechanical viewpoint: a deterministic or coherent structuring, either dynamic or static, existing in the virtual-photon or charged-particle flux of vacuum. Since a photon may also be considered a positron-electron pair (if we multiply each by time so that they are *qt* rather than *q* in fundamental unit form), the flux of photons in the polarized vacuum necessarily also includes the flux of charged virtual electrons and positrons. From a spacetime viewpoint: a curvature of spacetime, or set of such curvatures. If a deterministic set of spacetime curvatures (a template) is involved, then an engine is involved and the energy is said to be "dimensioned" (internally structured).

energy flow: Generally considered as the passage of energy, in any form, in one direction or generally in one direction in a given 3-space. To first order, our definitions of energy treat energy flow in a given space as (1) a directional change (propagation) of the vacuum energy and its form, or (2) as a directional propagation of a curvature of spacetime or a set of curvatures of spacetime. *The terms "energy flow" and "flow of energy through space" are not precisely defined in physics! They are not going* ***to*** *be defined, at least not in ordinary Aristotelian logic terms, since energy itself is not precisely defined, and one of the best struggles with the concept of energy concludes that it involves invariance in the midst of change, which is a violation of the third law of Aristotelian logic and therefore of the other two as well.*

Indeed, the "EM wave flowing through 3-space" does not exist (see previous comments quoted from Romer). What does exist is an ongoing 4-space process, assumed to be continually and iteratively interacting with a unit point charge to "detect" or "observe" it as an iterative series of frozen 3-space snapshots, in memory-recalled serial order much like the frames of a motion picture film. Nonetheless, we must keep our sense of humor and proceed as if we knew exactly what we were speaking of when we use the concepts "energy", "energy flow", and "energy propagation through 3-space". If one dwells on the problem without humor, one is led to Hawking's grim but perceptive statement: *"All we ever know is our models,* but *never the reality that may or may not exist behind the models and casts its shadow upon us who are embedded inside it. We imagine and intuit, then point the finger and wait to see which suspect for truth turns and runs. Our models may get closer and closer, but we will never reach direct perception of reality's thing-in-itself"* Ultimately we do not know physical reality itself, but our mental modeling of it, as best we can "fit" our modeling through comparison with our sensory and perceptive sensations.

energy flux: The passage **of** energy **flow, in any form, through a unit area, and** in any given direction (usually all directions). This includes both passage in a single direction, or passage in multiple directions at once. See flux. Sometimes taken as that component of the net flux through a unit area at right angles to the area.

energy, free: In our usage, free energy is what is obtained from any environment or entity which freely emits, furnishes, or makes available energy which either can be collected and used as furnished, or can be transduced into usable form and collected and used to power loads and do useful work. The word "free" does not apply to *costs,* but rather to the source *of the energy.* Since energy can neither be created nor destroyed, energy is always available free for the taking (collecting and using) if we bit learn how. *We never pay for energy per se, but for the manipulation and processing of the energy.* The notion of extracting and using free EM energy from the vacuum involves five key concepts: (1) the local vacuum/spacetime itself is filled with EM energy of generally unusable form (2) some sort of organizing principle is utilized in one part of the circuit or system to cohere the vacuum energy and transduce it into usable EM form (every charge already individually does that; we just have to learn to do it in a larger ensemble), (3) a gating mechanism is utilized to divert the vacuum energy now in usable EM form from the active vacuum to the external circuits or load parts of a device, (4) the coherent gated extra energy available in the external circuits or load parts is intercepted by those circuits or load parts, couples to them, and potentializes them with extra EM energy, so that the energy is collected by the system and regauges the system asymmetrically, and (5) the external circuits or load parts then scatter or dissipate the coupled extra energy to produce useful work (physical changes in the load), without destroying the organizing and gating mechanism that is extracting and furnishing usable EM energy from the vacuum.

energy source: A function or entity which furnishes energy by either gating it from one energy reservoir to our system or locality, or by transducing available unusable energy into usable form and then emitting the usable energy. Technically speaking, since energy cannot be created or destroyed, there is really no such thing as a *creative* "energy source", though the term "source" seems to imply such. So-called "energy sources" actually gate and/or transduce energy, changing it from one form to another, from one direction to another, etc. All EM energy in the universe comes from the time domain into 3-space vacuum, onto charge, and back to the time-domain, in a giant ongoing negentropy 4-circulation as freely provided by the "source charges".

engine: Deterministic pattern of structures, with their concomitant dynamics, in the flux of the vacuum. Also, deterministic patterning of curved spacetimc curvatures and their dynamics that comprise an overall larger spacetime curvature, or internally comprising an *overall* "uncurved" spacetime.

engineering, entropic: Engineering or designing systems and processes in equilibrium with their external active environment, and whose operation "spills" or wastes all the energy input to them, and which do not freely recover and use the dissipated or wasted energy. Entropic systems — which are the products of entropic engineering — thus have COP<1.0 and function in forward-time, and classical equilibrium thermodynamics with its infamous second law rigorously applies because the system is designed to self-enforce the equilibrium condition, often called by other names such as Lorentz symmetrical regauging.

engineering, negentropic: Engineering or designing open systems and processes far from equilibrium in their exchange with their active environment, whose operation freely "receives" excess energy from the environment, so that they permissibly output more energy than the operator inputs, the excess being received from the external environment. As an example, simply making a common dipole or assembling a charge initiates a giant negentropy operation that persists indefinitely (as long as the dipole or charge persists).

entropy: Thermodynamics state term representing a measure of an equilibrium system's capacity to undergo spontaneous change. In short, a quantity that measures the availability of a system's energy for conversion to work. The entropy of an open system not in equilibrium with its active environment cannot even be computed, because the state cannot be computed.

Entropy is given by dS = dQ/T, where dS is an infinitesimal change in entropy for a system absorbing an infinitesimal quantity of heat dQ at absolute temperature T. In statistical mechanics, entropy is a measure of the disorder in a system and is given by S = k lnP + C, where S is the value of entropy (disorder) for a system in a given state, P is the probability of that state's occurrence, k is a fixed constant, and C is an arbitrary constant. Intuitively, the concept of entropy corresponds to the concept of disorder. We specifically call attention to the fact that the "S" used in representing entropy is not at all the S used for Poynting energy flow in electrodynamics.

entropy, negative (negentropy): In a sense, the reversal of disorder, or reversal of entropy. Another way of defining negentropy even more rigorously — for electrodynamics — is to define it in spacetime as a bro*ken 3-symmetry in EM energy flow with concomitant relaxation to a more primary 4-symmetry between time-energy flow and 3-spatial EM energy flow, where time-energy flow is transduced into 3-spatial EM energyflow and then back to time-energy by the entity — such as a common dipole — causing the broken 3-symmetry.*

equilibrium: *In physics,* the state of a system in which opposing forces balance each other — i.e., sum to a vector zero. However, the *vector* zero summation does not represent "total absence" of everything, and the forces and their energy remain even though comprising a net vector zero system. Even a pure number zero may also be taken as a set of nonzero numbers; e.g., (+5 -3 -2). So even zero need not be total absence, but can be a "balanced set of presences". Or zero can be regarded as an overall equilibrium condition comprised of a set of disequilibria conditions.

Indeed, a vector zero summation system of nonzero forces comprises a stress potential, and it contains stress-energy doing work upon the stressed system. In *mechanics,* a system of particles — where the net force acting upon each constituent particle is zero — is said to be in equilibrium. *In chemistry, t*he state of a solution where the forward and reverse reactions are equal and balance each other, so that the chemical reactants and products maintain the same amounts. Again, the notion of equilibrium involves the "stationary" notion (similar to a perfect whirlpool in a perfect river) of the overall invariance of some set of ongoing dynamic changes.

ether: An extremely fine material substance originally theorized to exist in space in lieu of sheer emptiness. The problem is considering space as emptiness in the first place, which it is not. Instead, space (more rigorously, spacetime) is a plenum and highly active (as in the general relativity view a half-century after Maxwell's seminal paper). So there is no need to "fill empty space" with something, because in the modern view there is no such thing as empty space.

Evans, Myron W.: Noted chemical physicist, primary developer of O(3) symmetry electrodynamics, and Director of the Alpha Foundation's Institute for Advanced Study (AIAS). Papers produced by the AIAS are critical to understanding extraction of EM energy from the active vacuum, engineering of vacuum engines, and development of a revolutionary new healing method by time-reversing diseased or damaged cells back to a previous healthy state.

excess collected energy: Collection by an interceptor/collector of a greater fraction of EM energy flow impinging upon it and also surrounding it, than is normal. See **Bohren experiment.**

exciton: A bound electron-hole pair in a semiconductor. Excitons are temporary formations and they decay by recombining, but they have a specific half-life before recombining during which they migrate through the semiconductor crystal. When the hole and electron recombine, then — if the curvature of spacetime relaxes to a flat spacetime, which is not overtly stated in classical EM theory — the recombination releases energy in the form of a *photon,* or sometimes in the form of several *phonons.* **Note** that the "hole" is an "absence of an electron" from a position in a lattice usually containing an electron, so that it exhibits a net positive "change in the charge field" at that point. Specifically, this "lattice electron charge hole" is not a Dirac Sea hole in the vacuum, which is an entirely different matter. On the other hand, if the hole and electron recombine and the curvature of spacetime does not relax to a flat spacetime *because of other curvature-sustaining involvements,* then no "pair annihilation" radiation is emitted. It is the relaxation of the curved spacetime (when hole and electron are separated) back to a flat spacetime that causes photon or phonon emission.

exothermic: Literally, "giving off heat", or emitting scattered EM energy. Producing time-forward EM energy from a "source" by reducing the ordering (internal energy) of the source.

Faraday, Michael: Noted English physicist and chemist, 1791-1867, who discovered field theory and electromagnetic induction. Faraday also invented the dynamo and formulated his laws of electrolysis. His work directly inspired Maxwell, who vowed to study no other electromagnetics theory until he had captured Faraday's work in a mathematical theory.

Ferminion: A fundamental particle which has spin angular momentum of (n+1/2)h, and which obeys Fermi-Dirac statistics. Examples are baryons and leptons, which are subject to the Pauli exclusion principle.

Feynman, Richard P.: Noted physicist, Nobelist, and co-developer of quantum electrodynamics. Feynman is particularly noted for his refreshing three volumes of physics: see Richard P. Feynman, Robert B. Leighton and Matthew Sands, *The Feynman Lectures on Physics,* Addison-Wesley, New York, 1963. The book is particularly noteworthy in that it gives the student some insight into foundations problems in physics. E.g., in Vol. I on p. 2-4, Feynman defines the electric field not in terms of force per unit charge per se, but in terms of its *potentiality* for producing a force only when a charge is present for the force to be developed upon.

fiber fuse: Effect in optical fibers or fiber optic cable, whose core contains germanium, whereby heating the cable at one spot with a small flame will launch a focused traveling heat energy effect which melts a small hole in the core about every centimeter, and marches down the cable at about a meter per second to the end of the cable, destroying the optical transmission capability and ruining the cable. Oddly, by igniting the fiber fuse from the other end of the damaged cable, a *reverse* fiber fuse effect will often march back down the cable in similar fashion except that it fills in the melted holes in the core, restoring the transmission capability of the cable. If the energy required to melt all the holes (or fill them again) is taken into account, the amount of energy required to launch the fiber fuse is much less. This phenomenon does not appear to have an adequate technical explanation at present.

field: In mathematics, a set with two binary operations. In **electromagnetics** in more common mathematical terms, it is a region consisting of magnitudes and/or vector directions assigned to some active entity (e.g., spacetime itself) at each point in the region.

In physics, "a region of space marked by a physical property, as gravitational or electromagnetic force or fluid pressure, having a determinable value at every point in the region." [Thanks to *Webster's II New Riverside University Dictionary.]* Note the very special use of calculation of magnitude: one does not calculate the magnitude of the field itself, which fills an entire region. Instead, one calculates the magnitude of the *reaction* of that field with some interceptor/reactor at a given point — i.e., the *effect* of that field upon some mass entity. That is at best a measure of the *local intensity* of the field, not the magnitude of the entire field per se. For that reason, often we speak of calculating the field intensity, which is far more accurate than saying that we are "calculating the magnitude of the field". So we do not really calculate the "magnitude of the field," and in fact such a calculation does not occur in any textbook. Instead, we calculate the *reaction cross section* — in the case of electrodynamics, for an assumed unit point static charge — of the field at a point in the region or space occupied by the field. *We actually calculate what is deviated or diverged from the field, around an assumed interceptor, not the field itself.* This means that we calculate the result or *effect* of a detecting/observing action, and a frozen 3-space snapshot of that ongoing interaction, since all observation is 3-spatial. To then state that this same field exists in space prior to the interaction, and is what causes the interaction, is a gross non sequitur and confuses the effect with its own cause. This ubiquitous non sequitur widely permeates electrodynamics and mechanics, and it is one of the greatest scientific logical errors in history.

field, scalar: In the standard view, a field, to any point of which is assigned a magnitude only. However, "magnitude" of the EM field in the standard usage refers only to the amount of energy deviated (diverged) around a fixed intercepting unit point charge, per the conventional "detection by reaction" model. Again, note the serious logical errors in the conventional usage. One cannot define the field in terms of what is diverged from it! At best one has defined the "intensity" of the field's interaction with a given standard interactant (charge). So in electrodynamics the term "scalar field" would be better replaced with "scalar field intensity", at least for many applications.

field, vector: In the conventional view, a field, to any point of which is assigned both a magnitude and a direction. Again, the standard view also implements that assumed reaction with a detecting unit point static charge, and the "magnitude" used is just the difference between the amount of energy piled on the "front" of the interacting unit point static charge and the amount of energy pile on the "rear" of the interacting unit point charge.

The "direction" is from the center of the "high energy" pileup to the center of the "low energy " pileup around this fixed intercepting unit point charge. Again, note the serious logical errors. One cannot define the field in terms of what is diverged from it and the direction of the difference in "energy pressure." At best one has defined the "intensity" of the field's interaction with a given interactant (charge), and the "direction" established by the difference between the frontal and rear energy pileups on the interacting charge. The term would be better replaced with "vector field intensity".

flat (uncurved) spacetime: In our view, a vacuum/spacetime whose virtual particle flux intensity — and therefore its local energy density — does not change as a function of spatial position or averaged time. That is, in our view a flat spacetime is also identically a quantum mechanical vacuum whose virtual particle flux and energy density are constant in magnitude and internal constitution with respect to spatial position and in averaged time. Note that in this extended view, a flat spacetime (vacuum potential) can still contain vacuum engines, and thus still be *dimensioned. In that case*, contrary to normal physics, the flat spacetime itself will still interact with an embedded object and *change* it internally, even though it does not *translate* it externally. To perform transmutation of elements, e.g., one is interested in just such engines and not in spatially translating the element being treated. This dimensioning or activation of the local flat spacetime can result in an otherwise unexpected, seeming violation of one or more laws of nature in the dimensioned region, and easily results in violation of conventional physics which does not take into account engines and dimensioning of a flat spacetime. Note also that this allows a differentiation between the actions of two inertial frames, if the frames are differently dimensioned. As we stated, this is a deliberate extension of orthodox physics. See also dimensioning, and Einstein's second postulate —extension of.

fluctiation theorem: Theorem advanced by Denis J. Evans et al. at the Australian National University in 1993 that appreciable and measurable violations of the second law of thermodynamics occurs for small systems over short time scales. See D. J. Evans, E. g. D. Cohen, and G. P. Morriss, Phys. *Rev. Lett.* Vol. 71, 2401 (1993). In 2002 Evans and his colleagues experimentally demonstrated the proof of this theorem in rigorous fashion. See G. M. Wang, E. M. Sevick, Emil Mittag, Debra J. Searles, and Denis J. Evans, "Experimental Demonstration of Violations of the Second Law of Thermodynamics for Small Systems and Short Time Scales," *Phys. Rev. Lett.* 89(5), 29 July 2002, 050601. The proof also directly proves the occurrence in electrolytes and fluids of time-reversal zones (TRZs) where the dynamics runs backwards for a short time. This validates Bearden's proposal of the TRZ and its consequent reversal of the Coulomb barrier to a Coulomb attractor as the mechanism producing attraction of like charges into quasi-nuclei, which then can decay by quark flipping (if necessary) as the TRZ decays and reverses back to normal. This provides a mechanism for transmutation of elements in these TRZs as a result of the fluctuation theorem and its proof by Evans et al.

flux: The amount of some quantity (such as energy, particles, volume of fluid, etc.) flowing across a given area (usually a unit area perpendicular to the flow) per unit of time. The term flux density is now more commonly used. Loosely, "flux" refers to the perpendicular flow through an area, while "flux density" refers to the magnitude or intensity (rate) of the flux. In some cases such as a flux of particles of different velocities, the number of particles may be multiplied by the average velocity to give an average flux density that is weighted.

flux density: The amount of some quantity (such as energy, particles, volume of fluid, etc.) flowing across a given area (usually a unit area perpendicular to the flow) per unit of time.

Fogal semiconductor: A special semiconductor invented by Bill (William) Fogal which, in its operational regime, utilizes an integrated semiconductor, very special tantalum capacitor, and feedback resistor to accomplish charge blocking (blocking of electron current flow dq/dt) while passing displacement current $d\phi/dt$.

The Fogal semiconductor can also accomplish amplified phase conjugation of signals as well as infolding (translation of input transverse EM waves to output longitudinal EM waves) and outfolding (translation of received input longitudinal EM waves to output transverse EM waves). Used in communication systems, it opens the use of the unlimited "infolded" electromagnetics bandwidth. Since it may communicate using longitudinal EM waves, it is also usable for superluminal or a specialized "tunneling" communication through the "interior" of normal EM waves, potentials, and fields. For example, it can easily transmit color TV signals through the "interior" of a common DC potential. See William J. Fogal, "High Gain, Low distortion, Faster Switching Transistor," U.S. Patent No. 5,196,809, Mar. 23, 1993; - - "High Gain, Low Distortion, Faster Switching Transistor," U.S. Patent No. 5,430,413, July 4, 1995, a continuation of his earlier patent.

Fogal, William: Researcher and inventor of the Fogal semiconductor (two patents so far), as well as a superluminal infolding-outfolding communication system and other remarkable longitudinal EM wave processes. The Fogal semiconductor allows the use of the internal longitudinal wave electrodynamics comprising all ordinary EM fields, wa**ves,** and potentials, and thus will usher in a revolutionary new communications science and extended electrodynamics technology. See also discussion under Einstein's second postulate extended.

force: In mechanics, identically the time derivative of momentum, or $F = \partial/\partial t(mv)$. One must realize that it is not the mass in motion, but the single undivided quantity "mass-motion" or "mass-velocity" (momentum) that is changed. Present EM theory erroneously takes force fields to exist in em**pty,** massless vacuum but with zero force! However, the mechanical definition is an identity, not an equality. The observable mass in vacuum is zero, so substituting m = 0 gives $F = \partial/\partial t(0 \cdot v) = 0$. This appears to be the conventional reasoning. However, $\mathbf{E} = \mathbf{F}/q = \mathbf{0}/q = \mathbf{0}$ also. So if mass is zero, **the fi**eld E used in "force field definition" disappears. All that says is that the field in mass-free space and the field in mass are totally different entities,

Since force can be induced into and of the mass-motion target at a distance, in the new approach there is a more fundamental mechanism that produces force itself, and that is a curvature of spacetime, in agreement with general relativity. Distant curvatures of spacetime to produce forces on ex**posed** charged mass systems may also be engineered by longitudinal EM wave interferometry, which does constitute "action at a distance." The fields arise in the local spacetime in the distant interference zone, thus arising from within and around any physical mass object located in that zone. Hence it produces an "inside-to-outside" type of action that is presently unknown in orthodox physics. The produced fields can start inside the nucleons of the atoms and move outward, and work directly upon the quarks and gluons first. This opens a great number of entirely new nuclear reactions presently not developed in particle physics.

force **field:** An 3-space *effect* that exists as a local vacuum virtual particle flux i**nteraction** upon and with a hypothetical unit point mass or unit point charge assumed at every point in 3-space. The effect (force field) results from a ***causal*** force-free 4-field (a curvature of spacetime) interacting with an observed hypothetical unit point mass or unit point charge assumed at ever**y** point in space. Hence the invocation of observation invokes a *d/dt opera***tor** (the interacting charged mass) upon the causal field, providing a frozen 3-snapshot of the ongoing 4-interaction. An iterative series of such 3-observations is said to constitute a "3-space force field" as if it existed in time, which it does not. It is seen (iteratively observed) as a series of such frozen snapshots, which mentally we conceive as "existing in time" instead of the "recurring at points in time" that it really is. We unconsciously invoke that substitution of iterative effect as being continuity in space and time, when we use terms such as "propagation through space".

force-free propagation: Propagation of force-free disturbances in the vacuum flux; i.e., propagation of curvatures of spacetime or sets of such curvatures, together with any associated dynamics.

foundations of mathematics: The concepts, operations, assumptions, postulates, logic, definitions, and axioms of algebra systems.

foundations of physics: The postulates, assumptions, concepts, and definitions upon which a scientific physics model rests. Included are also the postulates, concepts, assumptions, definitions, axioms, logic, and operations of the mathematics in which the scientific model is expressed, as well as the postulates, concepts, assumptions, definitions, and operations of the physics entities and functions assigned to the mathematical symbols. Thus "scientific truth" -— even mathematical truth; see Morris Kline's *Mathematics: The Loss of Certainty* — is actually a *qualified* truth. What is true in one model (one set of postulates, assumptions, concepts, and definitions, including those in the algebra) may not be always true when one or more of the postulates, assumptions, concepts, and definitions is/are changed, and/or when the topology of the mathematics in which the model is expressed is changed, etc.

four-space (4-space): The "normal" spacetime used in physics, consisting of three spatial dimensions and one time dimension. Minkowski spacetime.

fourth law of logic: The law that a thing and its opposite become identical on the boundary, i.e., in multiple simultaneous observations. *Identity* is merely the loss of observational or perceptual distinction; when formerly "two" objects are simultaneously observed by a single observer, and two slides have been shown at once in the slide projector. It does not matter at that point what each was individually observed to be before when it was singly observed. Now there is no observable distinction or difference. We previously showed that the fourth law is implicitly assumed in the three laws of Aristotelian logic anyway, and published a simple proof of the fourth law. Without the fourth law, Aristotelian logic "eats itself." As a simple example, the Aristotelian third law eliminates the center vertical line division of a simple Venn diagram between A and not-A, because the division line itself is happy to belong to both A and not-A simultaneously. So Aristotelian logic destroys the very Venn diagrams used to "prove" or "demonstrate" its logical propositions. What results in the four law logic is that either (1) the three laws apply explicitly and the fourth law applies implicitly, or (2) the fourth law applies explicitly and the three laws apply implicitly. This *application rule* — i.e., *either (1) or (2)* — itself can be taken as a fifth law of logic, thus extending and completing Aristotelian logic which is presently incomplete. The fourth law is also the law of the **paradox:** i.e., when something is true but violates one or more of the Aristotelian laws, it is a case where the fourth law applies explicitly and the three laws apply implicitly. Wave-particle duality is such a fourth law case.

four-wave mixing: A nonlinear multiwave mixing effect when four waves mix (interact) in a highly nonlinear situation so that wave-to-wave interaction occurs.

fractional charge: A hypothetical particle having a charge less than the electron's charge. Often called a quark, where its charge is 1/3 or 2/3 the charge of the electron. A few years ago, Stanford University researchers found what was believed to be evidence of free quarks, but that later was doubted. There is also now the fractional Hall effect. In the 1920's Ehrenhaft reported the discovery and production of fractional charges of all sizes, and his experiments have been replicated by Mikhailov, with papers by Mikhailov and Barrett.

In the new approach, when time-energy is utilized, quarks can be freed or nearly freed rather easily in matter inside "time-reversal zones", since the energy emerges from the local curved spacetime and propagates from within the nucleus outward and the gluon forces are substantially reversed. Note also that time is multiply connected, and energy can enter an object anywhere within it or even everywhere within it, since each and every differential piece of the object exists in every single increment of time. It would appear that, as the new approach develops, free quarks will become a normal event rather than one intensely sought but terribly difficult to come by experimentally. We flatly predict that, in a sufficiently good time-reversal zone, free quarks can be produced because of the enormous energy density (in the time component) being utilized.

frame, Lorentz: A frame of reference that is not accelerated with respect to the laboratory observer. In this case, the frame may be rotated (moving at a constant velocity) but it is not rotating (the frame is not accelerated with respect to the observer, and spacetime is not curved). In this case special relativity applies, as do the conservation laws. We do add a caution that full general relativity still applies to the interior structure and dynamics (the engine) comprising the flat spacetime. Two *overall* flat spacetimes may produce very different interactions inside matter, if their internal engines are materially different and dimensioned.

frame, reference: A spatial, organized, measured lattice placed in "emptiness" (space, spacetime). Normally refers to a 3-dimensional, spatial frame (simplest case) or to a 4-dimensional spacetime. All objects and points in the "universe" or spatial frame are considered to simultaneously coexist at separate, measured points in the frame. Differs from the vacuum in that, rigorously, vacuum has no existing definite lengths and no existing definite time intervals, as these appear only after measurement or detection, and are relative to the observer and to the interactions ongoing as well as in the detection process itself. The "laboratory frame" is the static reference frame of the observer or measurement. A separate reference frame may be assumed to exist for any fixed or moving object, or centered on any point in another frame. When a type of frame is assumed, the entire class of *translation type* physical interactions that can occur has been restricted to an assumed set or type. In other words, given the frame, the *conventional* physics of translation has been assumed. One of the greatest restrictions of an assumed "frame" is to rule out the consideration (existence) of other higher dimensions, hence of dimensioned engines.

In the new unified field theory approach, the other higher dimensions are always available and cannot be ruled out in general, but only in some special case. Every curvature of spacetime, and any internal additional curvatures comprising that primary curvature, *adds one or more new dimensions.* In our view, a spacetime may be "flat" in overall envelope curvature, but consist of internally structured deterministic curvatures or "engines". In this view, normal inertial frames, e.g., may still contain engines, which will not affect the normal *bulk translation* rules, but may affect any or all of the nontranslation mechanisms, including the very laws of nature in many cases. Engines have not been developed and used in conventional open physics, but were weaponized clandestinely by the former Soviet Union. See **Einstein's second postulate extended.**

free energy: Excess energy freely received from its external active environment by an open system that is far from thermodynamic equilibrium in its exchange with that environment. There is a separate thermodynamics for such open disequilibrium systems. (See **thermodynamics of open systems.** See also Appendix **A** for a more detailed discussion of the thermodynamics aspects). Such a system is permitted to exhibit five "magic" functions: it is permitted to (1) self-order, (2) self-oscillate or self-rotate, (3) output more energy than the operator hims**elf** inputs (the excess energy being freely received from the active environment), (4) power itself and its load simultaneously (all the energy bein**g** freely received from the active environment), and (5) exhibit negentropy. Every charge and dipole in the universe already performs all five of those functions.

free **energy** system: Any open system not in thermodynamic equilibrium, which freely receives excess energy from an external environmental source, **and** collects and utilizes this free excess energy to freely power external loads, so that a permissible system COP>1.0 is achieved, as allowe**d** by the nonlinear thermodynamics of open systems in disequilibrium with their environment. (See **thermodynamics** of open systems.). A free energy system may also be "self-powering" if "close-looped" with governed positive energy feedback from output section to input section, meeting the Kron self-powering condition. Operation of free energy systems can only be properly modeled and understood in terms of their super*system* interactions.

Implicit in the notion of free electromagnetic energy systems are six key concepts: (1) the local vacuum/spacetime is known to be filled with hidden (i.e., virtual**)** energy in violent motion, i.e., the local vacuum/spacetime is a violent virtual energy flux and therefore a scalar potential, (2) a broken symmetry - i.e., some sort of organizing and gating mechanism, such as the common dipole — in this hidden (virtual) energy flux of the vacuum is utilized as a source, to cohere the virtual energy and divert it as energy $\mathbf{S} = f(\mathbf{E}\times\mathbf{H})$, flow from the broken symmetry initiation point onto the external circuits or load parts of a device, (3) the coherent gated extra virtual energy flow available in the external circuits or load parts couples to (inter**acts** with) the mobile charges in those circuits or load parts, so that gradients developed in the interacting virtual flux form force fields on and of the particle masses, driving the mobile charges along the circuit and through current-impeding circuit components such as loads, (4) in the interaction of the driven charges with the driving virtual energy flux, their spin and erratic motions integrate a tiny "coupling fraction" of the driving virtual energy into observable (i.e., macroscopic field) energy, thus creating the **E**-fields and B-fields, (5) the current-impeding external components or load parts scatter or dissipate the coherence of the driven charges and thereby dissipate the collected energy or change the form of the co**llected fi**eld energy, thereby producing useful work, and (6) little or none of the excess collected energy in the circuit is split off and dissipated in the gate (asymmetry component serving as the S-flow source) to destroy the gate and thereby destroy its asymmetry in the vacuum flux, which is what is extracting and producing the free energy flow.

gate: A component or function that extracts some part of a flux or flow, compacting it into a stream, and "sending it out" in organized, useful energy flow form. The fundamental gate for all EM energy in 3-space is the dipole or dipolarity — the "isolated charge" is actually a dipolarity, when the virtual charges of opposite sign clustering around it in the active polarized vacuum are considered. The source of the 3-space EM energy continuously emitted by any charge or dipole is an equal inflow of EM energy from the complex plane (from the time domain). Thus EM energy flow is locally conserved in four dimensions as a 4-circulation, but not in 3-space. EM energy flow in 3-spacc is conserved over all space, since there are essentially equal amounts of positive and negative charge in the universe and in the virtual charge of the vacuum.

gauge: In electromagnetism, usually considered a possible choice for (change of) electric scalar potential and magnetic vector potentials, in such a manner that there is no any *net* change of force fields so that the change satisfies Maxwell's equations. There are indeed two changes of force fields, but the two are selected so that the two new force fields are equal and opposite, constituting a stress potential and continuously performing internal work on the system to create and maintain the excess system stress. The equal and opposite force fields, however, cannot translate electrons through loads to freely power them. We prefer to consider any change of potential — even a single potential changed, or both changed so that a net force field does result — as a "regauging", for it is an implied primary assumption *within the normal use ofthe term "regauging."* If only one potential is changed, a net force field results in the system and we call that "asymmetrical regauging". If both potentials are changed, but in such a way that a net force field still results, that is also an asymmetrical regauging. When both potentials are changed precisely in such highly selected manner that the two force fields created are equal and opposite, the force fields sum to a *translation* vector zero, and that is symmetrical regauging or *Lorentz regauging.* However, the energy of the two fields remains, having been transposed to a stress potential. Each of the two "balanced" equal and opposite force fields is continuously performing work in the system, but all that is created is additional system stress. Hence symmetrical regauging is obtained only by altering the stress and stress energy of the system, with two disequilibria in energy flow between the ex**ternal** environment and the system. This in fact constitutes both a curvature of the local spacetime and an alteration of the local active vacuum. It is a rotation of the frame of the regauged system out of the labor**atory** frame. In effect, the net EM field energy of the two new fields created by symmetrical regauging is transformed into a change in the local spacetime curvature, a change in the local vacuum, increased stress in the system, and rotation of the system's frame away from the lab frame. We focus upon the energy aspects, since in a system any change of potential - whether symmetrical or asymmetrical — is a change of the internal energy of the system, and therefore of its excitation. In a system, conventional "symmetrical force fields" regauging results in a *nonusable continous* energy change in the system (actually two of these changes), and a change in the internal stress of the system. In short, it is a special case of **adding** a *stress potential* to the system, which we consider a special form of *asymmetrical regauging of the supersystem* consisting of (i) the system and its dynamics, (ii) the local active vacuum and its dynamics, and (iii) local spacetime curvature and its dynamics.

gauge freedom: The axiom in gauge theory that one can freely change the gauge **(and** therefore the potentials and the potential energy) of an EM system, so long as the net new forces resulting from the change will sum to a zero **vector** resultant so that the system remains "symmetrical" in its **force-field** functioning with respect to the system prior to the change of potentials. Electrodynamicists do not seem to have recognized that the freedom to change the potential of a system at will, is *a priori* the freedom to make a purely negentropic change to increase the system's potential energy, or a purely entropic change to decrease the system's potential energy. Gauge and gauge freedom are actually formal restrictions of an even more important asymmetrical regauging principle: *a potential in a system can be freely changed at any time, thus freely changing the potential energy energy of the system freely and at will.* The additional symmetry assumption is an arbitrary added requirement not imposed by nature.

Further, it appears that physicists have not recognized that a longitudinal EM wave is an oscillating gauge varying in its magnitude. Said in reverse, oscillating *the Lorentz regauging condition for a circuit makes that circuit* ***a generator*** *and emitter of longitudinal EM waves.* This also provides a clue f**or** detection of longitudinal EM waves, similar to what occurs in a Fogal semiconductor used for that purpose. A longitudinal EM wave dete**ctor** must detect a variation in the symmetrical regauging condition, which is a stress change detection.

gauge symmetry: Abstract mathematical symmetry of a field, that relates to the freedom to regauge (change the value of) potentials, without affecting the *net resultant* values of the field quantities. This is a special case of the higher principle that any potential (and thus the potential energy of a system) can be changed freely and at will. However, changing the gauge of an EM system in that sense changes the potential energy of the system but *only in stress potential fashion.* In other words, it does nontranslating work on the system, which is called "internal work." The lack of a net resulting force in the system, created by the regauging symmetry, prevents use of this excess free energy to translate system charges and power an external load. All the excess free energy that could otherwise be used to power loads freely, is instead "locked up" to only perform internal work on the system to increase and maintain system stress.

gauge theory: A field theory using a field that has one or more gauge symmetries. The restriction to symmetry is a carry-over of the old erroneous notion that potentials are just convenient mathematical figments, and that fields are the primary causes of all EM phenomena. For the overunity researcher, broken gauge symmetry at a given level (usually in 3-space EM energy flow) is the feature that must avidly be sought in experimental systems if one would use asymmetrical regauging to allow free powering of loads. Hence one is primarily interested in a wide variety *of broken symmetry effects* and phenomenology. Particularly, unless the automatic self-enforcing of symmetrical gauge transformation during excitation discharge of the closed current loop system is violated, no EM system can produce COP>1.0. Further, local spacetime curvature between local input and local output is always involved in an overunity EM power system. The tempic (time) potential of the output end of an overunity system differs from the tempic potential of the input end, so that the gradient (the tempic force) is directed from output to input — exactly the reversal of the case for a COP<1.0 power system.

Thus in both COP<1.0 systems and COP>1.0 systems, a local spacetime curvature is involved when the system is in operation. In COP< 1.0 systems, the tempic force sweeps along from input to output and on into space beyond, where the violent interactions of vacuum absorb the associated Dirac sea hole current immediately. In COP>1.0 systems, the tempic force sweeps along through the local vacuum from the output section back through the system and into the input section, and thence on back through the external conductors to the external power source. This reversed Dirac sea hole current may "eat electrons" in the normal currents

internal to the system, and in the input section and back towards the external power supply it will "eat input electrons in the input current." Thus the Dirac sea hole current in the COP>1.0 system "eats input power" and serves as a curious new kind of electrical "load" or "internal loss" in the **input** section of the system. The reversed Dirac sea hole current is nature's way of decaying the local curvature of spacetime back to a flat spacetime, and decaying the COP>1.0 excited system disequilibrium state back **to an** equilibrium state. In any overunity electrical power system, this Dirac sea hole current must be taken into account and either transduced into useful power, minimized, or eliminated. An extension to gauge field theory is needed in which the tempic force, the tempic potentials and their gradients, and the supersystem are all modeled and taken into account. It appears that the Sachs unified field theory is capable of handling that requirement, which also can be accommodated by O(3) electrodynamics to provide engineering of the resulting unified field theory.

gauge **transformation (in electromagnetics):** Conventionally taken to be the addition of the gradient of some function of space and time to the **magnetic** vector potential—and simultaneously the addition of the negative of the partial derivative of the same function with respect to time, divided by the speed of light, to the electric scalar potential. The resulting symmetrical change assumes that the stress energy of the system is changed **freely,** but by design it deliberately prevents any stress difference in the system to produce a net force that could expend the free change of energy by doing work in an external load. Changing the stress energy alone is a curvature of spacetime and a purely gravitational change. It is also a **rotation** of the frame of the system away from the laboratory frame. See discussion under gauge theory.

general theory of relativity: Einstein's theory of gravity in which the gravitational force is represented by a curvature in spacetime, and in which spacetime is an active entity. We may look at all forces as being due to curvatures of spacetime interacting with mass.

geometric phase: A phase difference acquired by the state function of a quantum system that undergoes a cyclic evolution from an initial state and back. This phase difference can be detected by interfering the final and initial states. The modern generalization of the Aharonov-Bohm effect and the Berry phase.

giant negentropy **(of the dipole):** The continuous receipt from the time domain **of spacetime** (the vacuum), by one charge of any dipolarity (including **a** single charge's fundamental dipolarity), of enormous longitudinal EM wave energy flow in condensed time energy form, transduction of that absorbed energy from the complex plane into real 3-space, and continuous emission of that enormous energy flow in all directions in 3-space, thence receipt of that 3-space energy by the other charge of the dipole or other adjacent dipoles, retransduction of the energy back into time-energy, and re-emission of that energy back into the time domain. This 4-circulation giant negentropy process is evoked and continues automatically and indefinitely after a little energy has been expended to separate the charges and make the source dipole. The EM waves in the input from the time domain and the output in 3-space are perfectly ordered and correlated, which is a giant ordering of the vacuum/spacetime and is thus a giant negentropy. In conventional circuits, the source dipole in the generator or battery, once made, performs this function. Only a minuscule fraction (some 10^{-13} in a nominal case) of the energy pouring out of the generator's or battery's terminals strikes the surface charges of the attached external circuit and is diverged into the conductors as the Poynting component that powers the Drude electrons and the circuit. All the rest of the energy flow (the Heaviside nondiverged component) outside the circuit is just wasted by conventional circuits.

gluon: A particle that carries the forces between quarks. In quantum chromodynamics, the gluon plays a role analogous to the photon in quantum electrodynamics.

graviton: In the quantum theory of gravitation, the graviton is the quantum of the gravitational field. It is massless, with spin 2. In the new theory we may take the graviton as a coupled scalar and longitudinal photon pair.

gravity: The phenomenon characterized by the physical attraction between any two material bodies of positive mass, specifically due to the trapped positive energy in the masses. If one particle is of negative mass and energy, the normal gravitational attraction between the two particles is reversed so that they repel, which produces antigravity. The fundamental mechanism of gravity can be found once one realizes that Maxwell omitted the incoming EM wave interaction with the nucleus, and not with just the electron shells. When he wrote his theory, the electron, atom, neutron, proton, and neutron had not been discovered yet. The lateral precession movement of the spinning Drude electrons — which are restrained *longitudinally* to a very small drift velocity in detecting wires (antennas) — later came to be considered proof of Maxwell's transverse EM wave in the vacuum. The detected electron precession wave is oscillating laterally, hence proves the longitudinal EM wave interaction. Elsewhere we have pointed out that the EM wave in space is longitudinal EM wave accompanied by a corresponding time-polarized (scalar) EM wave, and it also follows from Whittaker's 1903 paper as reinterpreted by the present author in our Giant Negentropy paper.

gross particle translation: Refers to translating the entire particle — and its internal structures and dynamics — in space, rather than internally structuing the particle's potential (massless charge). Note that, if the internal structuring (engines) of the particle is changed during translation (e.g., by passing through a region of the flat spacetime having an altered internal engine structure), the particle may have an anomalous interaction with another particle or process having a different internal structure or "dimensioning." The mass-energy comprising the particle's nucleus, electron shells, etc. can be dimensioned. Mass so dimensioned or conditioned then may act differently in chemical reactions, effects on living systems, etc. than normal "inert" mass that has no specific deterministic dimensioning.

group: A mathematical structure that is a complete set of transformations on a mathematical entity that leaves the entity unchanged.

group, higher symmetry: In a given theoretical area, a particular theory can be expressed in various group transformations. When the group transformation (group symmetry) utilized is more complex than the "standard" group symmetry usually employed, it is referred to as a *higher* group symmetry. The mathematics of the model is then said to be a higher group symmetry mathematics. Since the groups have names such as U(1), SU(2), O(3), etc., the transformations of the mathematics are often referred to by **those** names. Hence characterizing phrases are used such as U(1) symmetry electrodynamics, SU(2) symmetry electrodynamics, O(3) symmetry electrodynamics, etc.

group, Lie: A group whose transformations act continuously. An example of a Lie group is given by rotations in ordinary space.

group theory: The general mathematics of symmetry transformations; i.e., the the**ory** of all transformations that leave the transformed entity or entities unchanged.

gyroelectrons: Spinning electrons considered as gyroscopes during the portion of their spin in 3-space, so that when longitudinally perturbed they can and will laterally precess. Considering (in a gross first order model) the conduction electrons in the Drude gas in a conductor as little gyros, because they are (i) spinning on an axis, (ii) severely restrained in their ability to move forward longitudinally down the conductor as current, and (iii) much more free to precess laterally in the conductor. Thus when the gyroelectrons in the receiving wire antenna, perturbed by an incoming longitudinal EM wave in the vacuum, are longitudinally perturbed, they precess laterally so that our instruments (which detect electron wiggles, not the incoming vacuum EM wave) do detect "transverse waves." However, they are detecting the transverse gyroelectron precession waves, not the waves in the vacuum. They are detecting the *effect* of the interaction of the incoming waves with the gyroelectrons, not the *cause.*

harmonic series: A set of frequencies or oscillations consisting of integer multiples of a fundamental frequency.

Heaviside, Oliver: Noted English self-taught physicist and brilliant electrodynamicist, 1850-1925. who played a role in discarding Maxwell's quaternions, and also played a role in forming vector mathematics and formulating the vector reduction of Maxwell's theory from 20 quaternion equations in some 20 unknowns to the present 4 vector equations. Heaviside's curtailment of Maxwell's theory still contained both (i) systems in equilibrium with their active environment and (ii) systems in disequilibrium with it. To separate variables and enable closed solutions, *Lorentz further* curtailed the Maxwell-Heaviside equations by symmetrically regauging them, thereby *arbitrarily* discarding all disequilibrium Maxweilian systems and retaining only those in equilibrium with their active environment. This regauging unwittingly and erroneously discarded all that class of Maxweilian systems permitted to exhibit COP>1.0. The first such curtailment of the Maxwell equations was by Ludwig Valentin Lorenz in 1867, but H. A. Lorentz (who did a similar symmetrical regauging nearly decades later) was later given the credit.

Heaviside also discovered the enormous *nondiverged* energy flow surrounding every circuit, far greater in magnitude than the feeble Poynting *diverged* component that actually enters the circuit. But he was at a loss to explain what the source of such a startling flow of energy could be. Lorentz understood the Heaviside component, but also could not understand its source. Hence he reasoned that it "had no physical significance" since it did not power the circuit. Lorentz then introduced the trick of integrating the entire energy flow vector around a closed surface surrounding any volume element of interest. This neatly discards the vexing giant Heaviside *nondiverged* energy flow component, and retains only the *diverged* Poynting component that actually enters the circuit. The latter is of course the energy that will later be *emitted* from the circuit, which is what we will measure when we "measure the circuit."

Electrodynamicists are still using this method of dropping the Heaviside energy flow from any further accounting consideration. Hence they do not develop systems which intentionally increase their energy collection from this readily available energy flow around every circuit. The Bohren experiment conclusively proves the physical existence of the Heaviside nondiverged component, even though it is no longer accounted.

In his last years Heaviside realized the gravitational importance of his extra energy flow component, and worked out an electrogravity theory based on it. He did not live to publish it, but his papers on it were found some time after his death, beneath the floorboards of his little garret apartment. A learned society then published the papers.

Heaviside energy flow component: The enormous *nonintercepted* and nondive*rged* energy flow component pouring out of the terminals of every battery or generator, or charge or dipole, and missing the external circuit (or external intercepting charges) entirely so that it is does not contribute to the intercepted (Poynting) flow component that powers the circuit. Also, the enormous energy in the EM field, potential, or wave that misses the interaction of the field, potential, or wave with the assumed unit point static electric charge, and thus is not intercepted and collected (and accounted!) in the unit point static charge assumption. In honor of Heaviside, the present author has nominated this "dark Heaviside energy" component as the missing source of excess gravity known to be holding the arms of the spiral galaxies in place. In the interactions of Dirac hole current with a unit point charge (to determine the negative energy fields and potentials in a COP>1.0 EM system), there is also a missing component of the negative energy flow that is comparable to the Heaviside component for positive energy flow. These flows of surplus negative energy **from** COP>1.0 astronomical interactions—with the associated negative energy fields and negative energy potentials produced by the **negative-**energy Dirac holes in these negative energy flows — is hypothesized by the present author as producing the antigravity that generates the observed acceleration of the expanding universe.

Hertz, **Heinrich:** Noted German physicist, 1857-1894, who together with Heaviside and others transformed Maxwell's theory from quaternion algebra to vector algebra, and who also experimentally produced Hertzian (EM) waves, thus confirming Maxwell's theory. These experiments by Hertz first detected EM energy propagating as described by Maxwell's equations, thus providing the experimental impetus that allowed Maxwell's theory to predominate. The oscillation or "cycle" is named after Hertz, by specifying *X* number of oscillations or cycles per second as a frequency of *X* Hertz. One type of potential is also named after him.

hidden bidirectional EM waves: Those bidirectional EM wavepairs that comprise the scalar potential are indeed "hidden" with respect to our normal "electron translation" (i.e., electron wiggle) detectors and instruments. Nonetheless, properly functioning devices such as Fogal's semiconductor allow the utilization, transmission, and reception of the vast longitudinal EM wave dynamics that are infolded inside all conventional EM fields, waves, and potentials, including the giant potential comprising the ambient vacuum (spacetime). Use of this infolded electrodynamics is akin to using "subspace" or higher dimensions, depending upon how one chooses to model it mathematically. It is also a direct method of using a unified field theory.

hidden variable theory: A class of quantum mechanical theories which considers that the quantum state of a physical system is not a complete specification after all. The "hidden variables" are those additional components necessary to provide the "complete state" of the system. By utilizing the infolded longitudinal EM wave electrodynamics, one is in fact using a macroscopic hidden variable theory. This becomes a subset of Evans' O(3) electrodynamics, which in turn is an important subset of Sachs' unified field theory. Sachs' theory encompasses and subsumes electrodynamics, general relativity, quantum mechanics, etc., so the use of this macroscopic hidden variable theory through special functions provided by components such as Fogal semiconductors is a powerful and directly engineerable extension of conventional hidden variable theory. The physics of this new, engineerable, unified field theory area is also called *energetics.*

hole, lattice: Vacancy, in an otherwise filled energy band position. Sometimes called *negative ion vacancy.* In a semiconductor, an electron may be lifted to the conduction band by thermal energy, which produces u hole-electron pair (an exciton). Also, one of the sites in the crystal lattice can be occupied by an acceptor impurity atom, so that the electron is accepted there, leaving a hole showing excess positive charge. This is a lattice hole, and the propagation of such holes being formed is called electron hole current, or hole current for short. We point out that the *laittice hole* exists only after interaction of the Dirac sea vacuum hole with matter. i.e., only after observation. In that case, the 3-positron (hole) has positive mass and positive energy, produces positive energy fields and potentials, produces gravity rather than antigravity, and is "seen" to be going in the opposite direction to the Dirac sea hole. Prior to observation, the hole is a

Dirac 4-hole in vacuum, having negative energy and therefore negative mass equivalence, negative charge, and without a direction reversal. This 4-hole is a source of negative energy fields and negative energy potentials in **the** surrounding space, and thus of antigravity back-interaction (upon the physical system connected with the active vacuum component of its supersystem) due to the negative curvature of the local spacetime.

hole, Dirac sea: In the presence of fields (i.e., in the presence of curved space**time),** some of the negative energy states in the Dirac sea are not filled with electrons. In that case there are some empty 4-holes in the Dirac sea, in local spacetime itself. The Dirac hole is a negative energy state in the **vacuum** itself. It too *seemingly* has a positive charge, as seen by the external observer after interaction with matter. Holes are also mathematically equivalent to positrons, in case observation has been evoked, so long as the lack of positive mass is not a consideration Note that our view differs from the received view, but is based on experimental evidence which can only be gained from COP» 1.0 EM system experiments. We know of no such COP» 1.0 EM system experiments involved in the received view.

hole current: (1) In a semiconductor: Usually, the part of the current in a seminductor that is composed of migration of lattice holes. ***Mathematically,*** within certain constraints this may be considered a positro*n* current. The hole migration is usually slower than the electron migration producing electron current. (2) In the vacuum itself. In the *Dirac sea, in* **the** presence of fields the Dirac 4-holes flow in the opposite direction to the local electron current, providing a Dirac sea hole current or posit**ron** current. [See discussion under hole.] An electrical power system in disequilibrium with its vacuum interchange and having COP>1.0, will have a **greater** *tempic potential* at its output section than at its input section. Thus it will have a tempic force or tempic broom, sweeping holes from local instabilities to form a hole current (may be both a Dirac sea hole current and a lattice hole current) flowing from the output section of the system back through the system into the input section, and on out of the input section into the primary power source. *Hole current transduction may be* used to convert this detrimental hole current energy transport into usable **electron** current energy transport, or anti-circuit techniques and mechanisms can be used.

hole current transduction: Hole current in a COP>1.0 open system, where **the** system is in disequilibrium with the vacuum *a priori,* is usually detrimental to (he system and may destroy the overunity condition. A hole current from the input section of the system, fed back into the primary power supply, requires that extra electron current be furnished since some of the electrons in that furnished current will recombine with the oppositely moving Dirac vacuum holes and disappear to fill those holes. Hole current into a battery in "normal" fashion discharges the battery rather than charges it (although reversing the battery terminal connections allows charging in normal fashion using the hole current). Thus a battery can be discharged "far below zero", so to speak, by charging it with excess holes in the "normal connection." A capacitor may be charged with hole current, in which case the dielectric will undergo compressive strain into the positron-charged plate. However, when the capacitor is subsequently discharged, the dielectric will expand and recover, with its electron charges pushing electrons out of the negative side plate and into the external circuit. Hence a capacitor can be *charged* with positron (hole) current, and then can be adroitly switched so as to *discharge* electron current. In theory so can a battery because of its capacitance. This is a transduction of entropy to negentropy, a process for which a patent application has been filed by Bedini and Bearden. Gauge freedom already permits that operation, since gauging in electromagnetic systems is freely changing the local potential energy of the system, and is either negentropic (increasing the system's energy) or entropic (decreasing the system's potential energy).

hole injection: In an n-type semiconductor, holes can be emitted by applying a metallic point to the semiconductor's surface. We suspect (but have not proved) that sharp gradient pulses may also induce some of these holes as Dirac sea 4-holes and Dirac sea hole current rather than positron and lattice holes current. In that case, a mix of positive energy and negative energy (and gravity and antigravity) would be produced.

hole trap: An impurity in a semiconductor that can trap a "hole" by releasing electrons to the conduction or valence band.

hyperspace: Refers to a space of more than four dimensions, and specifically to those spatial dimensions outside the normal three. The term is used for both a space of n dimensions, where n>4, or for one dimension in such a space, beyond the normal four.

identity of opposites: On the boundary between A and not-A, A and not-A are identical (i.e., no difference can be discriminated). If all of a thing is collected, one reaches the boundary of that thing and it turns into its own opposite. The philosopher's problem of the "accursed necessity for the identity of opposites" cannot be solved in Aristotelian 3-law logic, since that logic is incomplete. It is readily solved, and part of, a more extended logic such as 5-law logic. The result is that "identity" is not an absolute entity, but is a decision by the observer reached by application of a comparison algorithm to separate observations made at differing times. An example is provided by a colorblind observer who sees as identical two marbles which, to an observer with color vision, are seen as red and black and therefore not identical. Aristotelian logic omits the action by the observer, the times of the multiple observations (only a single thing at a time is observed or perceived, *a priori),* and the decision algorithm used *by the* observer to decide whether two observations are identical or not identical.

inertial frame: A frame of reference in which force-free bodies move along straight lines, and the postulates of special relativity are valid. In the new a**pproach,** this notion is extended. Even in an inertial frame, force-free **bodies** may move along straight lines, the postulates of special relativity may remain valid, and yet the EM hidden variables may induce other chan**ges** in the usual laws of nature due to the action of hidden vacuum engines infolded in the *dimensioned* local flat spacetime (vacuum **potential).** See Einstein's second postulate extended.

infolded real vector components: Simply take a set of real force vectors that altogether sum to a vector zero resultant. This "vector zero system" is a zero vector with respect to forced *translation* of a particle or mass. It is not am absence of the vectors at all, but is the presence of specifically hidden and "infolded" real vectors that do not initiate bulk translation of the affe**cted** object or system, but perform *internal* work upon the system. Such vector systems are stressing systems of a special kind, where the internal components of the stress are not random but deterministic. Hence they are electrodynamic *engines,* in the new approach. To a somewhat arrogant mathematical scientist who once objected that zero vector resultant systems had no effect, I humorously challenged him to put it to experimental test. I suggested he stand between two elephants pushing against him in opposite directions, while I would stand between two fleas doing the same to me, and we would compare notes. He apparently was not amused at the suggestion.

infolding: With reference to signals, infolding means "placing the signal **or modulation** or change upon one or more of the internal bidirectional wave**pairs** comprising the scalar potential. Since all EM potentials ultimately represent changes to the ambient vacuum potential, one has conditioned or altered the vacuum itself when infolding is utilized, infolding of E*M* signals, vectors, and directions produces *engines*. By Whittaker's decomposition of the potential and Bearden's reinterpretation, these vacuum engines can be designed to affect matter — including atomic nuclei, nucleons, etc. — in any manner desired.

information content of the field: Russian euphemism for the deliberate structuring of the hidden longitudinal EM waves and their dynamics, that comprise any EM potential, field, or wave, so that the potential, field, or wave is *dimensioned* and contains active *engines.* This area was extensively weaponized under KGB (now changed in name) control rather than the regular Russian armed forces, and a disinformation campaign was waged to convince Western analysts that the term refers to simple spectral analysis. It doesn't. Instead, it refers to infolding and outfolding, and the use of longitudinal EM waves, dimensioning, and engines. The overall science is called "energetics" by those weapon scientists.

interferometer: An instrument or system in which a wave is split into two waves or beams, which after traveling over different paths are subsequently reunited and interfere. The use of longitudinal EM waves (LWs) allows ready penetration of mass by the LWs traveling through the interior Whittaker composition of a mass's internal EM fields, waves, and potentials. Longitudinal EM wave interferometers should prove useful in probing the interior of planets, the sun, etc. They pass easily through the earth, so that interferometry can be obtained at targets on the opposite side of the earth, or inside the earth. These are the weapons that then Secretary of Defense Cohen referred to in 1997 as being used to engineer the weather, initiate volcanoes into eruption, or initiate earthquakes.

Josephson effect: Flow of Cooper pairs (superconducting electron pairs) across a thin dielectric separating two superconducting electrons, in the absence of a voltage drop. E.g., the pair of electrons can "tunnel" through u thin insulating barrier.

joule: A measure of energy; one watt for one second in electrical terms. In physics the unit of work or energy in the MKS system, being the amount of work done by one newton acting through a distance of one meter, equal to 10,000,000 ergs.

Kirchhoffs current law: At any time, the sum of the instantaneous currents flowing into a node or point in a circuit equals the sum of the instantaneous currents flowing out of that node or point. This does not have to be true if (1) relativistic effects are appreciable, or (2) electron production and annihilation processes — such as Dirac sea hole current, lattice hole current and recombinations are occurring and non negligible, (3) the Kron open path is being used, or (4) localized time reversal zones (TRZs) are utilized. Another way of stating where the law need not hold is when there are nonlinear interactions between the three components of the superset (the physical system and its dynamics, the active vacuum and its dynamics, and spacetime and its curvature dynamics.).

Kirchhoff's voltage law: At any time, the sum of all voltage rises in a closed loop circuit equals the sum of all drops in that closed loop circuit. The law assumes a flat spacetime. This does not have to be true if relativistic effects are appreciable, if true negative resistor effects are present, if Kron open paths are utilized, and if time-reversal effects arc present. It also need not be true in anti-circuit techniques, or when they are involved in a particular portion of an otherwise normal circuit.

Lamb, Willis Eugene Jr.: American physicist and Nobelist who discovered the hyperfine structure of the hydrogen spectrum, and first measured the interaction of the vacuum energy that generates a change in the energy levels of the hydrogen atom, according to Dirac's theory and quantum electrodynamics.

Lamb shift: A very small correction to the first excited state of the hydrogen atom due to interaction of the vacuum. Willis Lamb experimentally confirmed this prediction of quantum electrodynamics to high accuracy. The local energy density of the little Lamb shift is greater than the surface energy density of the sun. However, in matter there are such a vast number of similar small interactions generating very powerful fields randomly, that the sum total of all these changes sums to a vector zero for most summation distances of interest.

lamellar current: Thin layers of current; thin sheets of current.

laser: A device that generates light in which all the photons are exactly in step and produce a coherent beam. Originally the word "laser" was an acronym that stood for "light amplification by stimulated emission of radiation."

law of physics: A restriction placed upon the physical mechanisms that can occur under certain broad assumptions as to the background situation and environment. Because of the assumptions made, an expressed law of physics is not absolute, but relative to the assumed conditions. Any "law of physics" can be violated if the conditions contained in its assumptions are violated. It is important that a scientist be aware that physics is comprised of models and the "laws of physics" are very general and wide-ranging models based on very specific assumptions. Further, by Godel's theorem and the theory of models, no model is perfect anyway, and none will ever be. When one assumes that physical laws are not based on any assumptions but are universal and absolute truths, one has immediately moved to dogma and not science.

Lawandy patents: Patents covering and related to a form of anti-Stokes emission (excess emission of energy) in strongly scattering, optically active media such as TiO_2 particles in suspension. This is a new form of lasing, without the requirement for population inversion.

Letokhov, V. S.: Russian pioneer in excess emission phenomena from stimulated media.

Letokhov effect: The excess emission (excess emission of energy) phenomena in strongly scattering, optically active media, usually referred to as "negative absorption of the medium." See particularly V. S. Letokhov, "Laser Maxwell's Demon," *Contemporary Physics,* 36(4), 1995, p. 235-243.

localized: Confined to a small region of a large system rather than being extended through the system or at a distance.

localized virtual photon flux of vacuum: Refers first to a local region of the vacuum, and then to the flux density of virtual photons in that local region. If that flux is deterministically structured, then the local region also contains an *engine* that will act internally upon masses and mass systems in that region. The local region also contains hidden variables.

longitudinal component: In EM fields, the longitudinal component of the fields along the direction of travel, as opposed to the transverse components at right angles to the direction of travel.

longitudinal E-field: Any electrical field in 3-space may be described using two components, a transverse component and a longitudinal component. Of course one or the other may be a vector zero. In 4-space, there is a time component also, as an additional "transverse" component.

longitudinal gradient: Compression wave gradients (differences) in density or pressure, considered in a direction from their origin along the direction of primary movement in the medium. Contrast to transverse waves, which act perpendicular to their direction of propagation. In electrodynamics, longitudinal EM waves in 3-space are said to be "longitudinally polarized." Longitudinal EM waves in the time-domain are said to be "time polarized." The latter are also referred to as "scalar waves" since they have no polarization vector component in 3-space and thus arc "scalar" with respect to 3-space. This is a misnomer, however, since these "scalar waves" are perfectly good time-polarized EM longitudinal vector waves. For the first time, the giant negentropy process allows one to make and use time-polarized EM waves, since they automatically accompany all longitudinally polarized EM waves and it is straightforward to make longitudinal EM waves in 3-space (just oscillate the Lorentz regauging condition).

longitudinal interior wave: An infolded longitudinal gradient that oscillates in magnitude along the line of travel "inside the vacuum potential or a normal potential." In conventional theory, the electric portion of the EM wave is a transverse field oscillation, and the longitudinal component is essentially zero. In the new "infolded" wave approach, there is no overall transverse gradient in the vacuum potential, but there are such longitudinal waves. This is rather like a "pressure wave" transmitted under water, without causing a surface wave involving physical upheaval and fall-off of the water. The speed of the longitudinal EM wa**ve** is not limited to c, the speed of transverse EM wave light in the ambient vacuum..

longitudinal wave: A "pressure" type of wave, similar to sound, in which the vibrations are along the direction of travel of the wave. Hence, a wave composed of alternating densifications and rarefactions, where we focus upon the longitudinal component of the changes. One can think of it as a sort of "accordion" wave, rhythmically shrinking and stretching along the line of motion as it travels. Note that rhythmically and symmetrically varying the two potentials involved in regauging creates longitudinal EM waves. So one pseudonym for longitudinal EM waves is "gauge oscillation" waves. Matter is mostly empty space filled with EM potentials, fields, and waves—all of which are bundles of longitudinal EM waves and their functional dynamics. Hence matter (such as the ocean and the earth) is a vast superhighway for the passage of longitudinal EM waves. Note that the longitudinal wave represents an oscillating energy density in space and/or time (scalar waves), and hence is an oscillating curvature of spacetime. All forces of nature are generated by curvatures of spacetime. Hence all forces of nature can be generated by the correct generation of longitudinal EM waves and their impressed dynamics, Further, this means that all the physical *causal* functions of the exhibited **effects generated** in a material system can be captured in longitudinal EM wavesets. A longitudinal wave functional system deliberately having such causal functions of a physical functioning system is known as a causal **system robot** (CASR). Such robots are far beyond the presently developing nanobots, and have been developed rather extensively by at least one nation. Such robots can easily pass through the "interior" of any normal

EM signal or wave or potential or field, which again is nothing but a giant superhighway for longitudinal EM waves. In theory one can communicate with a CASR via longitudinal EM waves if communications functions are built in to the CASR. In the future, one would expect that planetary exploration, underground and undersea exploration, exploration of the interiors of the sun, moon, and planets, could be enabled by the further development of specialized CASRs.

Lorentz, Hendrik Antoon: Renowned Dutch physicist and Nobelist. 1853-1928, who developed the Lorentz transformations and Fitzgerald-Lorentz contraction. Lorentz shared the Nobel Prize for discovering the Zeeman effect. He is also responsible for symmetrically regauging Maxwell's equations (some time after Lorenz did it in 1867), and for introducing an integration trick that neatly disposes of the vexing huge Heaviside nondiverged energy flow component accompanying every field/charge and potential/charge interaction.

Lorentz invariance principle: An inertial frame is independent of the velocity of the frame relative to any other inertial frame. This is not necessarily true with respect to engines inside inertial frame objects, since the engines involve acceleration dynamics.

Lorentz regauging: Changing the two potentials in the Maxwell-Heaviside equations in potential form so that the resulting equations have the variables separated, and there is no net force introduced by the two new forces, which are deliberately chosen so as to be equal and opposite and thus sum to zero. An unfortunate effect is that this discards all Maxwellian systems far from equilibrium in their vacuum exchange, hence discards all permissible Maxwellian COP>1.0 systems. Electrodynamicists have not recognized that Lorentz regauging represents the addition of stress potential energy and continuous internal work and stress to a regauged system. It also represents a rotation of the frame of that system out of the laboratory frame by some angle. Further, oscillating the Lorentz regauging condition produces longitudinal EM wave generation and emission.

Lorentz symmetry: The symmetrical regauging by Lorentz of Maxwell's equations.

Lorenz, Ludwig Valentin: Scientist who first changed Maxwell's equations — two years after their publication in 1865 — by (effectively) symmetrically regauging them, thereby unwittingly discarding all Maxwellian systems far from thermodynamic equilibrium with the active vacuum. See L. V. Lorenz, "On the identity of the vibrations of light with

electrical currents," *Philosophical Magazine*, Vol. 34, 1867, p. 287-301. In this paper [L. V.] Lorenz gave essentially what today is called the [H. A.] **Lorentz** symmetrical regauging. When H.A. Lorentz also symmetrically **regauged** the Maxwell-Heaviside equations, the physics community **adopted** the procedure and resulting further truncation of the Maxwellian theory. That truncation continues to this day.

low energy **nuclear reaction** (LENR): Actually a bit of a misnomer, since it refers to a low *spatial* energy, high *time* energy reaction. Cold fusion, or the anomalous transmutations of elements that occur in certain electrolytes with specially prepared palladium electrodes. The transmutations occur even though in conventional theory there is insufficient *spatial* energy to accomplish them, because they use time energy. Time energy is spatial EM energy compacted by the factor c^2, hence time has the same energy density as mass. The formation of temporary, fleeting time reversal zones (TRZs), with action from from inside-to-outside, is the genesis of a host of new nuclear reactions missing from conventional particle physics since the physicists do not account time as energy, and do not use such TRZs. For more on this hypothesis and the specific reactions generated, see T. E. Bearden, "EM Corrections Enabling a Practical Unified Field Theory with Emphasis on Time-Charging Interactions of Longitudinal EM Waves," *Journal of New Energy*, 3(2/3), 1998, p. 12-28 as well as Chapter 10 of the present book.

magnetic **dipole:** Paired north and south magnetic poles of equal strength ever microscopic or macroscopic distance.

magnetic induction: The act of a change in magnetic field producing an electric field at right angles, which in turn produces an electron flow.

magnetic spin: The intrinsic angular momentum, known as spin, of electrons, protons, and neutrons, etc. The electrons combined in an atom or ion have **a** resultant angular momentum that is the combined intrinsic spin of **the** electrons and the angular momentum due to their motion around **the** nucleus. There is also a magnetic moment associated with this angular momentum (spin) whenever it is nonzero. Therefore atoms or ions with non**zero** spin are *magnetic* atoms or ions. This is often loosely reffered **to a**s "magnetic spin." It is actually the magnetic moment of nonzero spin.

magnetostatic scalar potential: Continuous mathematical function whose value in space, at any point it occupies, represents the potential energy collected upon an assumed unit magnetic north-seeking charge (pole). There is a magnetostatic scalar potential between the poles of any magnet. This scalar potential is **also** subject to **Whittaker's** 1903 decomposition into a harmonic series of magnetic longitudinal phase conjugate wavepairs. Reinterpretation of Whittaker's wavepairs should be made according to Bearden, "Giant Negentropy of the Common Dipole," *J. New Energy,* 5(10, Summer 2000, p. 11-23. This reinterpretation agrees with quantum field theory; see Mandl and Shaw, *Quantum Field Theory,* Revised Edition, Wiley, 1993, Chapter 5.

matter: Highly condensed 3-spatial energy, compressed by factor c^2 and remaining in 3-space, and with the observation process *d/dt* having been applied to the fundamental masstime entity to provide mass as a frozen 3-space snapshot by stopping the flow of time momentarily. Matter, of course, has internal structure, order and organization, and dynamics. All matter is in a continuous energetic exchange with its active vacuum (4-spatial) environment. Matter stripped of its EM fields, waves, and potentials is called mass. Mass is an observable and therefore a frozen series of continual 3-space snapshots, formed by incessant photon absorption to change the mass *m* to masstime *mt,* with following incessant photon emission to change masstime *mt* back to mass *m.*

Maxwell, James Clerk: Brilliant Scottish scientist, 1831-1873, who first formulated the unified theory of electricity and magnetism. See *The Scientific Papers of James Clerk Maxwell,* 2 vols. bound as one, edited by W. D. Niven, Dover, New York, 1952, Vol. 1, p. 526-597 for his definitive paper, "A Dynamical Theory of the Electromagnetic Field," first published in *Royal Society Transactions,* Vol. CLV, 1865. In that paper, (see Niven's book) his general equations of the electromagnetic field are given in Vol. 1, Part III, "General Equations of the Electromagnetic Field," p. 554-561. On p. 561, he lists his 20 variables. On p. 562, he summarizes the different subjects of the 20 equations, being three equations each for magnetic force, electric currents, electromotive force, electric elasticity, electric resistance, total currents; and one equation each for free electricity and continuity.

Maxwell's famous book, *A Treatise on Electricity and Magnetism,* Oxford University Press, Oxford, 1873, Second Edition 1881 (Maxwell was already deceased), Third Edition, Volumes 1 and 2, 1891. Foreword to the second edition was by Niven, who finished the work. Maxwell had dramatically rewritten the first nine chapters to simplify his mathematics because of the resistance to it, with much new matter added and the forma contents rearranged and simplified. Maxwell died before finishing the rcsl of the second edition. The rest of the second edition is therefore largely a reprint from the first edition. The third edition edited by J. J. Thomson was published in 1892, by Oxford University Press, and later was published unabridged by Dover Publications, New York, 1954. J. J. Thomson finished the publication of the third edition, and wrote a "Supplementary Volume" with his notes. A summary of Maxwell's simplified equations are given in Vol. II, Chapter IX of the third edition. However, Maxwell had gone (in his second edition) to some pains to reduce the quaternion expressions himself, and not require the students to know the calculus of quaternions (so stated on p. 257). We note that Maxwell did not finish the second edition, but died before that. He actually had no hand at all in the third edition as to any changes. The Second edition was later finished by Niven by simply adding the remaining material from the previous first edition approved by Maxwell. The printing of the first nine chapters of the thirg edition was already underway when J. J. Thomson was assigned to finish the editing of the manuscript.

Maxwell's work profoundly affected the course of science and the course of human history. Maxwell, Heaviside, Hertz, Gibbs, Lorcntz and others participated in dramatically curtailing Maxwell's original 1865 quaternion theory to the much more limited subset that it is today. Since the early part of the 20th century, work has slowly been ongoing to move EM theory back to a higher group symmetry theory, which ironically it already was when Maxwell first created it.

Max**well's** electrodynamics: Simply put, Maxwell's theory of electrodynamics consists of Maxwell's equations. His fundamental theory consisted of some 20 quaternion equations in 20 unknowns, appearing in his 1865 paper. After Maxwell's death and some curtailment by Maxwell himself, Heaviside modified and sharply curtailed these equations, into the familiar four equations of today, as did Gibbs and Hertz. Lorentz further curtailed the Maxwell-Heaviside equations, by symmetrically regauging them. This simplified their mathematical solution, but it also inadvertently and arbitrarily discarded all open Maxwell systems far from thermo**dynamic** equilibrium with their active environment (such as the modern active vacuum). See James Clerk Maxwell.

Maxwell's Theory, fluid dynamics analogy: *Considering and adapting the fluid analogy approach of James Clerk Maxwell:* The intensity of the vacuum virtual particle flux may be treated as the intensity of a potential, thus by analogy corresponding to pressure in a fluid. Polarity (charge) is a **process for** establishing a change in the intensity of the vacuum potential - and **thus** a change in the ambient pressure of the vacuum fluid. Dif**fence** between vacuum pressures at two separated points creates a force u**pon** any charge placed between those two points. Just as a differential in pressure between points in a fluid induces currents, a differential in vacuum pressure induces energy flow currents in the vacuum fluid, which are called 'fields'. All EM circuits, charges, potentials, and forces in electrodynamics involve altering the vacuum to include altering its pressure and thereby producing the forces the resulting pressure gradients (fields) induce upon charges. All observable EM energy in space is EM energy intercepted and collected on charges, or assumed to be, and the spatial EM energy comes from the vacuum via these fundamental vacuum-engineering dynamics which all involve the giant negentropy 4-circulation between the time domain and 3-space.

Michelson, Albert Abraham: German-born American physicist, 1852-1931, who invented an interferometer (Michelson interferometer) named after him. Michelson used his interferometer in a renowned experiment in the 1880s designed to measure the velocity of the earth through the ether, which would produce a shift in his interferometer pattern. No such shift was observed, which indicated the absence of an ether wind and was largely responsible for the downfall of the concept of the material ether that had been previously assumed, including by Maxwell.

motionless electromagnetic generator (MEG): Transformer-like COP>1.0 electrical power generator invented by Patrick, Bearden, Kenny, Hayes, and Moore, ""Motionless Electromagnetic Generator," U.S. Patent # 6,362,718, Mar. 26, 2002. A second patent application is processing and several more are in preparation. In particle physics, any dipole (including a permanent magnet) is a known asymmetry in the fierce vacuum flux, continuously pouring out real EM energy extracted from the vacuum. The MEG continuously powers its transformer section core with a permanent magnet dipole, more than doubling the EM energy made available from **the** active vacuum via the permanent magnet dipole's broken symmetry in its exchange with the vacuum. [See M. W. Evans, P. K. Anastasovski, T. E. Bearden et al., "Explanation of the Motionless Electromagnetic Generator with O(3) Electrodynamics," *Found. Phys. Lett.,* 14(1), Feb. 2001, p. 87-94; "Explanation of the Motionless Electromagnetic Generator with the Sachs Theory of Electrodynamics," *Found. Phys. Lett.,* 14(4), Aug. 2001, p. 387-393]. The MEG nanocrystalline core material extracts the magnetic field B of the permanent magnet from the surrounding space and localizes it in the core material. The active vacuum asymmetry freely replenishes the withdrawn magnetic B-field energy in space surrounding the core, but with uncurled magnetic vector potential A rather than magnetic field B. This is an application *of geometric phase,* specifically the well known *Aharonov-Bohm effect,* with several thousand papers in the literature. The MEG then transduces and outputs magnetic B-field energy inside the **core** material and some of the field-free magnetic vector potential A energy in space surrounding the core, effectively having available more than double the energy being made available from the permanent magnet, or normally available to a transformer. The output power of the MEG is a function of (i) the time rate of change of a small amount of input EM perturbation energy to the input coil, plus (ii) the intercepting and collecting secondary charges available in the secondary coil, (iii) additional energy from chaotic oscillations, (iv), sophisticated feedforward and feedback regenerative self-oscillations, and (v) the geometric phase (Aharonov-Bohm effect). It thus is a rigorous practical application of the geometric phase effect to a macroscopic power system, and in fact is the first such application in practical electrical power systems. The noted feature of the MEG is a purely electrical interaction in the output coils, in which the voltage and energy are in phase within 2°, differing from all other transformer-like systems. Thus the MEG directly delivers real power rather than apparent power. See Aharonov-Bohm effect.

multicollection (of energy): Multiple collection and re-collection in a circuit of the same energy flow from a source dipole, by rerouting either (1) the dissipated Poynting energy back around to the collectors for another pass by them, with additional collection, or (2) retroreflecting the nondiverged Heaviside EM energy flow component back and forth across the surface charges in the circuit conductors, iteratively diverging additional energy into the conductors to potentialize and power the Drude electrons, or (3) a combination of the two. The interesting point is that this effect can "use" the same energy to do repeated work, multiple times. It takes advantage of the fact that work is merely the change of form of energy, and that the new form can again be changed (as for example, back into the first form again) to do additional work, again and again so long as the energy in each transformation is held in the system without escaping. This process permissibly violates classical equilibrium thermodynamics and its infamous second law, since it is an open system freely receiving excess energy from its active environment and thus far from equilibrium with that active environment. As is well known, such systems are permitted to exhibit COP>1.0 and even self-powering of the system and its load simultaneously.

negative absorption of the medium: Excess emission from an active medium, as in the Letokhov work and in Bohren's experiment. The excess energy is first absorbed from the vacuum interaction (actually from Heaviside's unaccounted energy flow component that usually does not interact with the system), and then it is re-emitted. This is actually a true "Maxwell's demon," as pointed out by Letokhov.

negative resistor: Any component or function or process in an EM system that freely receives energy from outside the system in unusable or disordered form within the system, transduces that energy into usable form, and outputs it so that it can do useful work. In a *true* negative resistor, that is the *net* function performed. We specifically do not include "differential" negative resistors such as the tunnel diode, thyristor, and magnetron, which dissipate and disorder more energy from the system itself, overall, than the fraction that they order and furnish back to the system in their negative resistance regime. In anti-circuits, true negative resistors are quite natural components. Every charge and dipole in the universe is already just such a negative resistor, freely extracting unusable EM energy from the seething vacuum, transducing it, and continuously pouring out real observable EM energy in all directions in 3-space. A negative resistor can produce the five magic functions: (i) self-ordering, (ii) self oscillation or self-rotation, (iii) output more energy than the operator inputs, (iv) power itself and its load freely, and (v) exhibit negentropy. The condition for self-powering of a system containing a true negative resistor was given by Gabriel Kron.

negentropic: Functioning to produce or involve negentropy; reordering previously scattered energy without requiring the operator to input energy to perform the reordering. A simple example is passive retroreflection of radially scattered EM energy. The conventionally unaccounted enormous and nondiverged Heaviside energy flow component surrounding every circuit and every field/charge interaction is an example of a dynamically reordered and organized energetic vacuum, and thus an example of a **giant** negentropy process. The continuous observable EM energy freely pouring at the speed of light from every dipole and charge in the universe is also **an** example of the giant negentropy process.

negentropic engineering: Expending a little bit of energy to form a dipolarity, and then intercepting, collecting, and using some of the enormous EM energy freely and continuously extracted by the dipolarity from the vacuum, indefinitely, without using any of the extracted EM energy to scatter the charges in the dipole and destroy it. Retaining the dipole intact avoids shutting off the furnishing of copious free energy **flow** from the vacuum to the attached external circuit. As an analogy, it allows an electrical windmill operating in (driven by) a free electrical wind from the external environment of the system.

Newtonian recoil: Newton's third law reaction from the affected entity back to and upon the effecting entity. The "action" is the action from **the** effecting entity upon the affected entity. The "reaction" is the action from the affected entity back upon the effecting entity. Newton's third law actually implies that the cause interacts upon the effect and the effect reacts equally back upon the cause, thus producing a strange kind of equilibrium. In a time-reversal zone, the "recoil" is reversed in direction by parity reversal. Tentatively, one may interpret from pumped phase conjugation that the Newtonian third law reaction of one single acting force can be amplified by properly directing the actions of other acting forces. An interesting aspect is that a pumped phase conjugate mirror does not recoil, no matter how powerfully it is pumped or how powerfully amplified is the emitted phase conjugate replica wave.

Newton's third law: For every action there is an opposite and equal reaction. This law should be extended and restated something like this: "for every action there is an opposite and equal reaction if the causative mechanism of the reaction is allowed to occur without interference and is not first redirected away from its target." An example of a violation of Newton's third law as usually stated is provided by the emission of a phase conjugate replica (PCR) wave from a phase conjugate mirror material. No matter how powerfully pumped, the PCM does not recoil by the emission of the PCR wave. The reason is that the antiwave cause of Newtonian third law recoil was intercepted by nonlinear multiwave interaction (wave-to-wave **interaction)** before reaching its target nuclei and interacting with them, and was diverted away from the atom and on out of the phase conjugate mirror material. Since the causative mechanism for Newtonian recoil did not occur on the mass of the mirror, the mirror did not recoil. We also point out that, if Newton's third law is indeed engineerable and controllable, then COP>1.0 systems and self-powering EM systems are permissible a priori. In electrical system terms, this simply means that, if one can rid the system of its equal back emf or back mmf, the system can be legiti**mately** self-powering because it no longer self-enforces the Lorenz-Lorentz symmetrical regauging condition.

non-Abelian electrodynamics: An electrodynamics based on a group theory in which the group operation is not commutative and hence not Abellian in nature. Contrast to an Abelian group in which the group operation is commutative.

nonequilibrium thermodynamics: Colloquial term referring to the newer thermo**dynamics** of self-organizing systems and structures, far from euilibrium in their energetic exchange with their active environment, Since the **1960s,** there has emerged in physics (and in thermodynamics!) this surprising new area: the physics of far-from-equilibrium systems and the self-organization and large-scale ordering of such systems. The equilibrium conventionally referred to is 3-space equilibrium, with no consideration of temporal equilibrium, although some pioneers of the field such as Prigogine are quite aware of the temporal disequilibrium also involved. Note that such "3-disequilibrium" thermodynamical systems are also in temporal energy flow disequilibrium as well as 3-disequilibrium, but overall are still in 4-equilibrium energetically. See **giant negentropy (of the dipole).** For a necessary thermodynamics discussion, see Appendix A in this book.

nonlinear material (optical): A substance whose optical properties vary with the intensity of the light.

nonlinear optical functioning: Functioning in a manner prescribed by nonlinear optics and quantum optics, particularly with respect to time-reversal effects, use of phase conjugate mirrors, phase conjugate reflection, wave-to-wave interaction, and pumping for amplified phase conjugate reflection. To quote Knight, "A phase conjugate mixing device has remarkable optical properties: perfect retroreflection, the complete cancellation of optical aberrations and inhomogeneities in wavefronts, and the ability to reverse an optical beam and return it to its source." A most interesting modern science, eventually adaptable to COP>1.0 systems, is developing in the study of intensely scattering optical materials.

nonlinear phase conjugate optics: See **phase conjugate optics.**

nonlocalization: Producing or rendering an effect or effect-producing agent at a distance, rather than at the immediate location of the effector. Extended throughout a large region or system, or to a distant part of a large region or system, rather than being confined to a small region of the large region or system. Nonlocalization effects are absolutely prescribed in quantum mechanics, and are experimentally confirmed. They have been largely ignored in classical electrodynamics and electrical engineering. Nonlocalization can result from the existence and use of a multiply connected space, as in Bohm's quantum potential and hidden variable theory. Engineering of action at a distance by engineering the quantum potential through multiply connected space gives one method of energy amplification. This method has unfortunately been secretly weaponized In five nations of the world, and none of the technology is available for use in electrical power systems for energy amplification and solving the energy crisis.

non-Riemannian geometry: Riemannian geometry is the geometry **of** Riemannian manifolds — i.e., manifolds having an infinitesimal squared distance *ds* that is everywhere positive. A non-Riemannian geometry violates this property. [A manifold is a topological space with certain prescribed characteristics.]

nucleons: A collective name for the neutrons or the protons in a nucleus. In the nucleus, the neutrons and protons are continually changing one into the other by exchange of the charge. What is called a neutron and what is called a proton is thus somewhat arbitrary, so long as one makes a rule and stands by it. The interesting thing is that, in a nucleus, there is already continous and highly rapid transmutation activity between nucleons, all the time, without giant accelerations and operator input of very intense spatial energy. In short, nature shows in all matter that matter can be and is continually transmuted from instant to instant, and is "constant" only on the "**average".** Since most present models used for this are statistical rather than causative, it strongly suggests that we should look for a causal mechanism. The use of the time-reversal zone and time-energy has been nominated in this book as providing a causal mechanism for transduction, which can be directly engineered. It appears that cold fusion research already accomplishes transmutations using the suggested mechanisms, Several specific nuclear transmutation reactions applying the new mechanisms, and consistent with hundreds of cold fusion experiments, are given in the present book.

O(3) electrodynamics: An electrodynamics extended from a two-dimensional inner group symmetry to a 3-dimensional inner group symmetry. O(3) electrodynamics also becomes an important subset of Sachs' unified field theory. The inner group symmetry of O(3) can be taken as normal space, which immediately opens up engineering the vacuum and using spaetime curvature engines to directly engineer matter for us.

open system: A system that communicates with its environment, and exchanges energy, matter, or both between system and environment. With the possible exception of a few theoretical or hypothetical systems, all systems in the universe are in fact open systems. An open system may be in equilibrium with its active environment, so that it cannot accept, store, and utilize any excess energy from the environment. Another open system may be in disequilibrium with its active environment, in which case it can accept, store, and utilize excess energy from the environment. When the operator inputs EM energy into an open equilibrium system, he automatically breaks its equilibrium condition with the external active environment, decreasing the system's entropy. This is an excited state, and the system will subsequently decay back to equilibrium (maximum entropy) condition by emitting or dissipating its excess energy. The reader interested in the thermodynamics should read Appendix A in this book, since the thermodynamics definition (or misdefinitions!) of "closed system" actually permits the system to be open with respect to energy exchange with its active environment — either in equilibrium or disequilibrium — and only prohibits exchange of mass across the system boundaries. By that definition, a "closed system" can be far from energy flow equilibrium with its external environment, and hence permitted to perform COP>1.0 or even COP = oo. Hopefully our discussion in Appendix A will clarify the position we have taken on this matter.

optical switching: Switching of optical signals, or switching using optical frequency switching techniques, components, and circuits.

orthodox transistors: Ordinary transistors in use today, i.e., as contrasted with the Fogal semiconductor and its special functions.

orthogonal rotation: Simply speaking, a rotation from one direction to a direction at right angles to it. The Lorentz transform of special relativity, e.g., is a formula for the rotation of an object and all its parts away from its line of motion, as a function of the object's velocity, in a direction toward the time axis. The speed c just represents a full orthogonal turn, so that the projection intersection of the object with the observer 3-space, along the original line of motion, is zero.

outfolding: Translation by a system of received input longitudinal EM waves entering inside its potentials and fields, into conventional EM waves present in the system and then output from it. The opposite *of infolding.*

overpotential: Essentially the overpotential (as in an electrode in a solution) is a shift in the Fermi level necessary to allow the electron in the electrode metal to have energies overlapping with vacant acceptor levels in molecules adjacent to the electrode in the solution. The overpotential effect appears at small "double surfaces" of things in very close contact, particularly in electrochemistry and in solid state physics. The overpotential enables electron transfer, e.g., by tunneling. The overpotential increases with the log of the reaction rate that occurs at the overpotential location. For a small reaction rate, the overpotential is small; but for a small increase in the overpotential there occurs a dramatic increase of reaction rate. Fogal has utilized the overpotential effect in his semiconductor, to great advantage in accomplishing unusual charge blocking and other special effects. See **tunneling.**

overunity coefficient of performance (COP>1.0): More energy out or work out of a system than the operator or experimenter must furnish **and**

input. The excess energy is input from the active environment. See coefficient of performance.

parity: Deals with studying a system of a sequence of events as if the events were reflected in a mirror. A system has parity if it undergoes no fundamental operational change if replaced with its mirror-reflected twin.

partially time-reversed region: A region of spacetime in which an object temporarily experiences not only the ordinary forward flow of time, but also an extra induced backwards flow of time, usually a fraction of the time-forward time stream. It appears that the combination of the two is what constitutes time dilation in relativity. In a mixed time-forward (photon interactions) and time-reversed (antiphoton reactions) zone, if time-forward predominates, the law of attraction and repulsion of charges is partially reversed, leading to overall reduction of the forces — which remain in their usual directions. If the time reversal predominates, the law of attraction and repulsion is reversed, and in that region like charges attract and unlike charges repel. If time reversal and optical pumping are combined, the reversed law forces of attraction of like charges and repulsion of unlike charges are amplified also.

particle physics: The branch of physics using accelerators to study high-energy particle collisions, to determine properties of atomic nuclei and of the elementary particles themselves. It appears that conventional particle physicists do not recognize or consider time-energy interaction and time-reversal zone nuclear interactions at all. Hence the present "high (spatial) energy" physics is a far lower "total" energy physics than is the physics where time-energy is deliberately utilized. When time-energy is utilized, then the total energy of the photon varies inversely as a function of its frequency rather than directly as a function of its frequency. Lower frequency photons have very much greater total energy than higher frequency photons. For practical electrogravitation, therefore, one is interested in lower frequency bandwidths such as the ELF region.

Patterson effect: The intense multiscattering, multipass, multicollection of energy density flow in an assemblage of palladium-clad spherical bead capacitors, as the palladium adsorbs hydrogen ions from the fluid in which the beads are immersed, and thereby charges up as a capacitor, becoming an energy-flow generator, and nonlinearly increasing the energy-flow as the charge of the capacitors increases.

Patterson Power Cell®: Patented overunity power unit by James Patterson, which has been independently validated to yield COP>1.0. However, continuing difficulty has been experienced with the palladium metal used in the effect. See James Patterson, "System for Electrolysis of Liquid Electrolyte," U.S. Patent No. 5,372,688, issued Dec. 13, 1994. Patterson has several other patents in the area.

perpetual motion machine: The rather archaic and dogmatic assertion that no machine can indefinitely operate, since no closed system can input its output power back to itself while powering a load, because powering itself and its load violates the *equilibrium* thermodynamics (i.e., the thermodynamics of a closed system). Every system is already an open system in a violent energetic exchange with the active vacuum, so the pronouncement is a non sequitur assuming a false straw man — that every machine is a truly closed system or is in energy flow equilibrium with its active environment and can be treated as if it were a closed system. (The thermodynamic definition of "closed system" is misleading; it refers to a system where no mass exchange crosses the system boundary, but energy flow exchange can and does freely cross it. See Appendix A to this book for a proper discussion). Further, the equilibrium thermodynamics cited does not necessarily apply to either an open thermodynamic system far from energy equilibrium, or to a closed thermodynamic system in energy flow disequilibrium, as is now well known. After all, a common windmill will operate so long as there is a wind or until something breaks. But since it involves a mass flow across the system boundary, it is said to be a true open thermodynamic system. In electrodynamics, a closed system (with no matter exchange across its boundary) can yet have copious energy flow exchange across its boundary, and thus be far from EM energetic equilibrium with its external active environment. The charges and the dipoles in matter operate in a free "time-energy flow wind" and virtual particle flux wind in the vacuum, which are constant and unfailing, and thus charges and dipoles have been freely and continuously outputting real EM energy flow into 3-space for some 14 billion years. All assertions that overunity EM systems are perpetual motion nonsense are completely refuted by every charge and dipole in the universe. To repeat such gibberish only reveals the ignorance of the person making the improper assertion.

Ironically, those dogmatists fond of hurling perpetual motion labels at overunity researchers already recognize the overunity legitimacy of open systems far from thermodynamic equilibrium with their active environment; they refer to such systems *as false perpetual motion machines oxfictitious perpetual motion machines.* All of them also accept the classical electrodynamics assertion of the source charge, from which all EM fields and potentials and their energy come. So the very dogmatists so confidently pontificating that perpetual motion machines are ludicrous, themselves already implicitly accept that every charge and dipole in the universe is precisely such a perpetual motion machine, freely and continuously creating energy right out of nothing. No legitimate free energy researcher in his wildest nightmares has proposed such perpetual motion machines on such a universal scale. The greatest perpetual motion nuts on earth are precisely those pundits so confidently castigating the notion that an electrical system can output more energy than the operator himself must input. We will have a modicum of tolerance and respect from them, when they can demonstrate how they can purge all those "perpetual motion charges and dipoles"-—and all their EM fields and potentials— from their own accepted electromagnetic model. Obviously if they do that, they simply destroy all EM energy in space, in systems, and in the entire universe. This is the absurdity of the position these pundits advocate so ignorantly.

phase conjugate: Of an entity: its time reversal. For waves: often referred to as *wavefront reversal.*

phase conjugate mirror: A nonlinear material which, when provided with an input wave, emits a phase conjugate replica (time reversed replica) of that input wave. The input wave is by practice called the *signal wave.* The time-reversed wave output is by practice called *the phase conjugate replica.*

phase conjugate optics: That portion of nonlinear optics dealing with multiwave mixing, formation of time-reversed waves, phase conjugate reflection (PCR), phase conjugate mirrors (PCMs), pumping PCMs to amplify their emitted PCRs, nonlinear interferometry, distortion correction, self-targeting, laser tracking, adaptive optics, and so on.

phase conjugate replica (PCR): Of a wave: the time-reversed duplicate of a signal (input) wave, after its detection by interaction with charge. We point out *there may still be some foundations difficulty, however, with the form in which the phase conjugate replica wave exists in spacetime prior to its interaction with charge and prior to its observation (observing the effect of its interaction with charged matter).* Indeed, there is very serious foundations difficulty with the very notion of an EM transverse wavefront in space, traveling at the speed of light, for no such thing exists. See Robert H. Romer, "Heat is not a noun," *Am. J. Phys.,* 69(2), Feb. 2001, p. 107-109. This is an editorial discussion by the Editor of AJP of the concept of heat in thermodynamics, where heat is not a substance, not a thermodynamic function of state, and should not be used as a noun. In endnote 24, p. 109, he also takes to task *"...that dreadful diagram purporting to show the electric and magnetic fields of a plane wave, as a function of position (and/or time?) that besmirch the pages of almost every introductory book. ...it is a horrible diagram. 'Misleading' would be too kind a word; 'wrong' is more accurate. " "...perhaps then, for historical interest, [we should] find out how that diagram came to contaminate our literature in the first place."*

phase conjugating action: In nonlinear optics, the process or action of producing a time reversed replica of an input wave._For a particle, producing its antiparticle. For a living cell, dedifferentiating it back to some previous form, genetics and all. In the presence of a predominately time-reversal zone, however, the cell is in a predominately phase conjugating mode *a priori*. Phase conjugating it a second time converts it from dedifferentiating to redifferentiating mode. We hypothesize that these combinations are the actual mechanisms generating cellular dedifferentiation and redifferentiation in the cell, tissues, and body. A future book will address that issue; meanwhile, see the 119-page "porthole briefing" on the author's website, www.cheniere.org.

phase conjugation: In nonlinear optics, the novel nonlinear mixing of waves which generate an output wave — called the phase conjugate replica or time-reversed replica — that precisely retraces the path previously taken by the input wave that stimulated the action.

phonon: A quantum of the lattice vibration energy in a crystal. This mechanical vibration energy is considered a field, and the phonon is the quantum of that mechanical energy field. Lattice vibrations in a crystal thus are characterized by waves in the lattice, where the waves are comprised of ordered phonons. Interesting effects occur between electron currents and phonons, due to electron-phonon interaction.

photon: In physics, the basic action quantum. Conventionally considered to be the basic quantum of the EM field. There is a foundations problem with the latter concept, because of the dichotomous use of "field" for both the *effect* force field in 3-space after observation (detection) and the *causal* force-free field in 4-space prior to observation (detection). Strictly speaking, the photon is the quantum of the causal 4-space massless **field,** since the photon possesses both spatial EM energy and time increments. In curved spacetime, the photon may possess mass because the time flow is a mix of time-forward and time reversal, and thus cause and effect are slightly intermixed as well. We point out that, in a negatively curved spacetime, the photon mass is negative, the photon energy is negative, **and**

the photon fields are negative energy fields. Presently the negative energy photons do not appear to be utilized in physics except haphazardly if at all. This may represent a large class of photon interactions with matter that have been inadvertently omitted.

ping-pong: Colloquial term for iterative retroreflection.

pinned electrons: Electrons held stationary by a magnetic field, or other set of forces that react to "push them back into their positions and hold them fast" whenever they try to spatially move away.

pinning: The act of restricting (by restoring forces and fields) spatial movement (particularly of electrons) due to a disturbing magnetic field or other external force.

polaron: An electron in a substance, where the electron is trapped in a potential well due to polarization charges on surrounding molecules. The exction in a substance is analogous to an exciton in a semiconductor.

positron: An antielectron (time-reversed electron), possessing a positive charge and positive mass. *Mathematically* an empty *negative energy electron* state in the Dirac sea whose usual occupying electron has been removed, leaving a four dimensional "Dirac sea hole," may also be regarded as a positron for many purposes, at least *after observation resulting from interaction with matter*, so long as the remarkable difference of the Dirac 4-hole prior to observation from the Dirac 3-positron a**fter** observation is understood. Mathematically, the lattice hole previously occupied by an electron can be considered a positron-equivalent (i.e., as if observed), again so long as the real differences are kept in mind, between a Dirac hole *before* observation and what results after its observation by interaction with mass. This is important, because otherwise one is again substituting the effect for the cause. In addition, if the two are confused, **then** one also arbitrarily discards the negative energy fields and negative energy potentials of the source 4-hole in the vacuum prior to observation. That effectively discards anti-circuits and the ability to engineer practical electro antigravity.

power: In physics, the time rate at which work is done (at which *the form of energy* is changed). In electrical engineering, the term "power" is erroneously but ubiquitously also used to loosely mean "energy." Hence such odd and improper expressions as "draw power from the source," which is a non sequitur. Nonetheless, such non sequiturs are so universally utilized in electrical engineering that they have become a part of the literarure itself.

Prigogine, Ilya: Noted Belgian chemist and Nobelist, and one of the pioneers of the thermodynamics of open systems far from thermodynamic equilibrium. Prigogine was awarded the 1977 Nobel Prize for his work on the theory of dissipative structures in nonequilibrium thermodynamics.

Poynting, John Henry: An English physicist who lived from 1852-1914, whose contributions to electromagnetics included the energy flow theory now known as Poynting flow. He contributed the Poynting theorem, which states that the rate of EM energy loss in a specific region of space is equal to the sum of the dissipation rate (heat loss) flowing across the boundary of the region. Concurrently with Oliver Heaviside, Poynting conceived the notion that energy flowed through space, which previously had not appeared in physics. Heaviside actually published first, but obscurely; Poynting published in a prestigious journal, so the theory came to be known as "Poynting theory."

Poynting energy: A loose term (not rigorous!) used to loosely describe the flow through space of Poynting energy density S = ExH, which is that component of the total energy flow in space that will be *intercepted and collected* by the intercepting charges, circuit, etc. It actually describes not the energy flow density *per se*, but the component of it that would be intercepted by a unit point charge, or that actually enters an intercepting circuit. Poynting started with the assumption of the component of the energy flow that enters the circuit, *a priori.* Only the work of Heaviside considered the remaining component of the energy flow that is not intercepted by the charge or by the circuit. Because of the startlingly great magnitude of this remaining nondiverged Heaviside component, Lorentt integrated the entire (Heaviside) energy flow vector around a closed surface surrounding any volume element of interest. This discarded the entire nondiverged Heaviside component, and removed any necessity of considering or explaining how every generator and battery already pours from its terminals up to 10^{13} times as much EM energy as the presently accounted energy input to the shaft of the generator or the chemical energy available in the battery. We believe that the discarded and unaccounted Heaviside nondiverged energy flow component accompanying every field-particle interaction is responsible for the puzzling excess gravity holding the arms of the spiral galaxies together. In short, we believe it is the solution to the "dark matter" problem, now often believed to be a "dark energy" problem.

Poynting energy density flow: A somewhat more rigorous term used to describe the flow through space of the Poynting energy density flow

$\mathbf{S} = f(\mathbf{E}\times\mathbf{H})$ component that would be intercepted by a unit point charge or an intercepting circuit.

*Poynt*ing energy flow: A loose term (not completely rigorous) used to describe the flow of energy density $\mathbf{S} = f(\mathbf{E}\times\mathbf{H})$. Rigorously, both E and H are "defined" only after their reaction with a unit point static charge. Hence S is the resulting component of the overall energy flow that interacts with the charges (with the circuit) and is diverged into the circuit to power it. It is not the entire energy flow, which also includes a vast Heaviside nondiverged component that does not strike the charge and interact with it, and hence does not interact with the circuit but is just wasted. See Heaviside energy flow component and Poynting energy.

Poynting generator: Colloquial term for any dipole or potential difference that represents a broken symmetry in the vacuum's virtual particle flux, and hence extracts virtual energy from that asymmetry, and gates it out as a gushing energy flow in 3-space. When both electric field and magnetic field are involved, the component of the energy flow that would be intercepted and diverged by a unit point charge is the Poynting energy flow S=f(ExH).

Poynting vector: The vector S, given as $\mathbf{S} = f(\mathbf{E} \times \mathbf{H})$, used to represent the Poynting (intercepted and collected by a unit point coulomb) energy density flow component. In Heavisidc's version, $\mathbf{S} = \mathbf{E} \times \mathbf{H} + \mathbf{G}$, where G is an energy circulation flow term of trapped EM energy flow. Heaviside later rea**lized** that such a closed energy circulation flow exhibits substantial gravi**tational** effects; in modern terms we would say that it represents an apprecia**ble** local curvature of spacetime. Unpublished notes on the gravitational aspects were found beneath a floorboard in his little garret apartment, years after his death. We also point out one limitation of the present use of the Poynting vector: It has rather universally been associa**ted** only with the flow of *positive* EM energy, and not with the flow of negat*ive* energy. Indeed, the concept of negative EM energy is still consufe**d,** with different views and positions, and still in debate without complete scientific consensus.

PPCM: Pumped phase conjugate mirror. A phase conjugate mirror material that has introduced to it appositive or "pump" waves (in other words, s***tress*** waves). In effect, pumping is "stressing" or "squeezing" ryhtmically. It is also varying a stress potential, which emits longitudinal EM waves, each accompanied by a correlated scalar (time-polarized) wave. In the phase conjugating process, up to all the energy in the pump waves can be output as the energy in the emitted phase conjugate replica wave. Thus the PPCM may be viewed as an *amplifier,* very similar to a triode. When the time-components of the photons in the signal wave input and also in the pumping waves are considered, then there is a functioning of the pumping also ongoing in the time-domain. There is a rhythmic variation of stress in the time-domain also, which creates the correlated time-polarized EM wave accompanying the longitudinal wave from the 3-space pumping.

So the time-reversal aspect (formation of the phase conjugate replica wave) may be thought of as a rhythmic time-stress wave (pumping or stressing in the time domain) which, by alternately decreasing and increasing the time potential of the mirror, produces two temporal force effects. During the decreases in temporal potential of the mirror, the time-force from the input wave and from the pump waves is forward into the mirror material, allowing the input and interaction of these waves. During the increase in temporal potential of the mirror, a reversed temporal force from the mirror back to the past (temporal potential earlier in 4-space) of the input "signal" wave. The pumping energy (excess temporal potential energy) adds the gain to the phase conjugate replica wave,

probability: The probability of a simple event is the ratio of the number of times it occurs to the total number of trials (for a large, essentially infinite number of trials). Note that "trials" constitute things that have occurred (are past, have been observed). Probability has resisted rigorous logical definition by Aristotelian logic; the reason is that it is an expression of the fourth law, the identity of opposites. Probability is an expression of the future (that which has not occurred) in terms of the past (that which has occurred). Consider *throwing a die to land with one face up.* Thinking of the event (as if it has just occurred, in terms of the most recent past), one can conceive six ways of looking at it. In other words, one can conceive of six "most recent pasts", however, these have not occurred. We were merely thinking of them as if they had occurred. By the fourth law, the *total* "most recent pasts that have not occurred" is identical to the "most immediate future" that has not occurred, on the common boundary between past and future. If one therefore *collects* all six "most recent **pasts** not occurred" they turn into the most immediate future, by the fourth law of logic. One may argue that only a single one of the events will actually occur. Here one counters with the observation that, when it occurs, it is the past, not the future, and then it has not been collected so as to move **to t**he boundary. In theory, the hidden variable approach makes it possible to directly engineer those probabilities while the Schrodinger wavefunction is still propagating and has not yet collapsed to constitute an "observation."

I.e., it is theoretically possible to engineer Wheeler's "pre-reality," and determine in advance just which of the outcomes will occur.

Puthoff, Harold: Noted physicist active in a variety of fields and investigations including in psychoenergetics, extended electrodynamics, energy from the vacuum, inertia, antigravity, parapsychology, remote viewing, psychokinesis, zero-point energy of the vacuum, and cosmology. We are particularly impressed with Puthoff s cosmological feedback principle. Together with Cole, Puthoff also proved that thermodynamics does not prohibit extracting usable EM energy from the active vacuum. See Daniel C. Cole and Harold E. Puthoff, "Extracting Energy and Heat from the Vacuum," *Phys. Rev. E,* 48(2), Aug. 1993, p. 1562-1565.

QM vacuum: The quantum mechanical vacuum, which models the vacuum as an intense flux of virtual particles, each appearing and disappearing in such extremely short time intervals as to be unobservable individually—although as physics develops, from time-to-time what is observable changes because of increased observation techniques. Violent fluctuations of extremely short duration constantly occur in the QM vacuum flux. Various calculations estimate the energy density (in mass units) as up to 10^{80}-10^{90} grams per cubic centimeter (in mass density units), or even greater. The vacuum is sometimes described as two separate components: (1) the ambient or average vacuum in deep space, which can be taken as a scalar potential having an enormous energy density, and (2) the fluctuations superposed upon the ambient vacuum as local violent potential energy changes. Finally, we note that any EM potential in a system is *apriori* a change to the local vacuum scalar potential.

quantized: Adjective which means (i) reduction of some observable quantity to multiples of some small, indivisible unit, or, (ii) expressed in terms of quantum theory.

quantum: A single "particle" of the quantity *action* (angular momentum). Often confused as a single quantity of energy alone.

quantum electrodynamics: The theory of photons and electrically charged particles and their interactions. The use of the term "quantum" implies that the EM radiation's discrete photon nature is significant, so that quantum theory must be employed.

quantum **field theory:** A quantum mechanical theory in which "... a phsyica1 held is considered as a collection of particles and forces, and observable properties of an interacting system are expressed as finite quantities rather than state vectors." *[Dictionary of Science and*

Technology.] More simply (after Davies, *The New Physics,* 1989): "The theory that describes the quantum effects of a classical system of fields defined on space-time and satisfying various partial differential equations." Particles are taken as quanta of fields similar to photons being quanta of the electromagnetic field. Each type of particle is represented by an operator that obeys certain commutation laws. The theory relates gluon fields and intermediate vector boson fields to the strong and weak interactions, and allows an overall theory of fundamental particles and their interactions.

quantum potential: A special potential added to the Schrodinger equation by Bohm in his hidden variable theory of quantum mechanics. The quantum potential is a multiply connected entity, so that it "occupies" widely separated but multiply connected points, events, or objects. It is also an extraordinary energy amplifier, since any energy input to one of the multiply connected points simultaneously and instantly appears in every other connected point, regardless of distance or location in the universe. In real life, the quantum potential also has a "coefficient of multiple connectivity", so that only a fraction of the energy input to one multiply connected point will appear in the other points of the multiple connection group. The quantum potential has been strongly weaponized by five nations, and quantum potential weapons are the dominant weapons on earth, being more powerful than nuclear weapons. In theory the quantum potential together with engines and antiengines could be used to treat and cure a given disease in all persons on earth simultaneously, or in one nation or area simultaneously. Sadly, engines have been developed to generate diseases in a targeted populace, rather than engines to heal the populace. Russia and Brazil have had the quantum potential weapon for some time, as have two nations friendly to the United States. In 2001, China also deployed the quantum potential weapon.

quark: Fundamental particle theorized to comprise hadrons (particles such as protons, neutrons, and mesons) by combining in twos or threes. There are six varieties of quarks. The difference between a proton and a neutron, e.g., is merely the orientation of a single quark. In a time reversal zone (TRZ) in the electrolyte in cold fusion experiments, the gluon forces can be significantly reduced, so that the quarks are nearly freed. Two protons (H+ ions) can attract together in a TRZ so closely that each enters the reduced strong force region of the other, forming a quasi-nucleus. As the ions in solution outside the TRZ move to cancel the TRZ, it decays and the quasi-nucleus becomes an increasingly excited state, seeking to decay. Preferred method of decay is by quark flipping. So one quark flips, so that the quasi-nucleus has become a quasi D+ nucleus. As the TRZ vanishes and time-forward resumes, the strong force recovers faster than the Coulomb barrier returns. Consequently, the quasi-nucleus of D+ merely tightens into a real nucleus of D+. This is one of the standard transmutation reactions in cold fusion experiments, forming excess deuterium.

quaternion: Expression comprised of the sum of four terms, one of which is real and three of which contain imaginary units, and where the terms can be writtten as the sum of a scalar and a three-dimensional vector.

quaternion algebra: The algebra of quaternions and their mathematical operations. Quaternion algebra is of higher topology than either vector or tensor **algebra.** Maxwell's original 1865 equations are some 20 equations in 20 unknowns, in quaternion and quaternion-like algebra. Heaviside and others reduced the algebra to vector algebra and some four equations; at his death, Maxwell himself was rewriting the equations in his *Treatise* to purge the quaternions, because of the controversy over the difficult quaternion form. The present vector equations taught in university as "Maxwell's equations" are in fact Heaviside's truncation of the Maxwell theory. Going to tensor algebra electrodynamics does not recover the full range of Maxwell's original 1865 quaternion EM theory.

quintessence: Literally, the "fifth essence". In short, *dark energy*. We have nominated the arbitrarily discarded, vast Heaviside nondiverged energy flow component surrounding every interaction of charge with field as the dark energy that is the source for the excess positive gravity holding the arms of the spiral galaxies in place. See dark energy, positive.

reactive power: Electrical power, measured in volts-amps-reactive (vars) that cannot do work as is. For sinusoidal waveforms, the formula for reactive power is $IV \sin\theta$, where θ is the phase angle between the voltage **and the current.**

real hidden dynamics: The dynamics of vacuum engines, or of "internal energy" or "internal work" ongoing in a system or volume of space. These internally organized forces, fields, and energies involve dynamic curvatures of spacetime, and it is this dynamics of spacetime itself that provides **the** continuous work and dynamics of internal energy. See Einstein's second postulate extended; infolded; dimensioning.

real hidden vectors: The "hidden" or "infolded" real vector components, e.g., of a zero vector summation system. The individual hidden vector cannot spatially translate the entire bulk system, but it can interact inside the system to perform *internal work* upon it or upon some particular portion of it. Such a system of a finite number of infolded deterministic vectors is said to constitute a "dimensioned" stress potential. Specifically dimensioned potentials, fields and waves thus can be constructed, so that they carry specific vacuum engines (spacetime curvature engines). The interactions of these dimensioned EM entities may differ from normal EM interactions in chemistry, physics, biological systems in general, cells in particular, etc. The long neglected combination of Whittaker's 1903 decomposition of the scalar potential, together with his 1904 demonstration that any EM field or wave pattern decomposes into two scalar potential functions, has neglected the development and use of the "internal EM" theory and technology for a century. One or more nations has, however, highly weaponized "dimensioned EM fields, waves, and potentials" as evidenced by the peculiar and anomalous results of the decades-long microwave radiation of the U.S. Embassy in Moscow. See dimensioning.

real power (active power): Power, measured in watts, that can do work, including generating heat. For sinusoidal waves, real power is given by the formula $I \cdot V \cdot \cos\theta$, where θ is the phase angle between the voltage and the current. Note that when higher group symmetry EM effects are involved (such as the Aharonov-Bohm effect), then the "normal" behavior of circuit components can be altered dramatically. As an example, in the MEG the secondary (output) coils of the transformer section are caused to exhibit a purely electrical interaction with the electrons and electron currents in the coils themselves. Consequently *the output current and voltage are in phase, in complete violation of conventional transformer theory and conventional assumptions about the interaction of inductors.* So the output of the MEG is real power, and phase angle does not enter into it.

regauging: In electrodynamics, changing the scalar potential or the vector potential, or both. If one or both of the potentials is/are changed so that a net new force is created in the system, that is an *asymmetrical* regauging. If only one potential is changed, a net force results and that is an asymmetrical regauging. If both potentials are changed but carefully selected so that the free force resulting from one change is equal and opposite to the free force resulting from the other, that is a net *symmetrical* regauging, often called "Lorentz regauging" or the "Lorentz condition". We note that longitudinal EM waves are produced very simply by rhythmically oscillating the magnitude of a stress potential, which is naught but coherently oscillating the individual vectors of a set of EM fields that sum to a zero vector resultant. The locked-in stress in T. Henry

Moray's semiconductors used in his radiant energy device tubes and the locked-in stress in the Chung negative resistor thus have to do with the production and use of longitudinal EM waves, time-polarized EM waves, and stress potentials.

reflection: The rebound of light or other energy from a surface.

refraction: The bending of light as it passes from one medium to another or through a density change in a given medium.

retarted wave: An electromagnetic wave that is derived from retarded fields, which in turn are derived from retarded potentials. The retarded wave at a point or region of space has arrived there or exists there as the result of the dynamics of charges and currents that existed at earlier times elsewhere. Compare to advanced electromagnetic wave.

retroreflecting: Precisely reversing the path of a reflected wave or object.

Sachs, Mendel: Noted scientist who has completed the work of Einstein and developed a unified field theory covering the universe from the tiniest part to the entire conglomerate. Since O(3) electrodynamics has been shown by Evans to be an important subset of Sachs' theory, then for the first time we have a higher group symmetry electrodynamics and a unified field theory that is largely engineerable by novel electrodynamic means, using the O(3) model.

Sachs' unified field theory: An extension and completion of Einstein's work that includes the universe and its dynamics from the tiniest part to the entire conglomerate, and includes quantum mechanics, electromagnetics, gravitation, and the strong and weak forces. See particularly Mendel Sachs, *General Relativity and Matter*, Reidel, 1982; *Quantum Mechanics from General Relativity*, Reidel, 1986. Sachs' unified theory provides a great generalization of general relativity, quantum mechanics, and electrodynamics reaching from the quarks and gluons to the entire universe. Much of the model is also engineerable by higher group symmetry electrodynamics such as the O(3) electrodynamics pioneered by Evans and Vigier.

scalar: Characterized by magnitude only. However, with respect to polarization, a scalar photon is a term in use for a *time-polarized* photon, where the EM energy oscillates along the time-axis. Hence a scalar wave, following the same terminology, is an EM wave composed of scalar photons, hence whose EM energy is oscillating along the time-axis. The term "scalar" is used in the sense that no vector in 3-space exists even though a vector (and a variation of its magnitude) exists along the time axis. The effects are observed as an oscillation in the rate of flow of time, hence a "time-density" oscillation. The term "scalar" with respect to polarization implies only that there is no vector component in 3-space.

scalar entity: In ordinary vector analysis, an entity thought to be completely characterized by magnitude alone. Actually this is incomplete; a scalar entity must contain a time-like vector component, if it is to steadily persist in time. What we usually do unthinkingly is assume a continual series of successive observations or *d/dt* operations upon the *kt* nature of a scalar *k*. We conceive these individually frozen 3-space snapshots to "continuously exist" since we can readily recall the "stream" *of d/dt* differentiations in our mind and memory. Since all observation is 3-spatial, then no observable *persists continuously* in time; instead, it *continually recurs* in time, instant to instant. This "iterative successive stream of frozen 3-space snapshots" exists in the continual and rapid recall from our memories. Compare this to the similarity of observing a sufficiently rapid series of still pictures on a screen, where the individual pictures differ by a time sequence taken of some phenomenon. One "sees" the recreation in one's mind of the flow through time of those events and entities so photographed. Yet at any one instant, there is only a single frozen snapshot on the screen, and no motion at all was "physically" observed.

scalar electromagnetics: Colloquial term for the electrodynamics that arises from considering transverse EM waves, longitudinal EM waves, time-polarized EM waves, electrogravitation, superluminal EM signals, interferometry, nonlinear optical functions, time-as-energy, and the infolded electrodynamics inside all usual EM fields, waves, and potentials, In secret superweapon projects, the Russian term for scalar electrodynamics is *energetics*. It is divided into three major fields, depending upon the intended target. Targeted against inert matter, **systems,** and fields, the same term is used: *energetics*. Targeted against the **physical** and chemical processes and biological fields and potentials of living organisms, the term used is *bioenergetics*. Targeted against the mind's time-polarized EM functioning and dynamics, the term *psychoenergetics is* used. In the latter, higher group symmetry electrodynamics and extensions to quantum field theory play significant roles. Significant progress and strategic testing of all three branches of energetics has been evidenced worldwide. Progress in the energetics branch was confirmed by a statement by U.S. Secretary of Defense Cohen in 1997. Quoting: ***"Others** are engaging even in an eco-type of terrorism whereby they can alter **the** climate, set off earthquakes, volcanoes remotely through the use of* *electromagnetic waves...So there are plenty of ingenious minds out there that are at work finding ways in which they can wreak terror upon other nations...It's real, and that's the reason why we have to intensify our efforts "* Secretary of Defense William Cohen at an April 1997 counterterrorism conference sponsored by former Senator Sam Nunn. Quoted from DoD News Briefing, Secretary of Defense William S. Cohen, Q&A at the Conference on Terrorism, Weapons of Mass Destruction, and U.S. Strategy, University of Georgia, Athens, Apr. 28, 1997.

scalar potential: Usually considered synonymous with the electric potential. The concept of potential was developed by Poisson, Green, and others **from** about 1813 to 1827. Three notions involved in the deve**lopment** of the concept of the potential are: (i) there is the collection of storage of energy in the system, via the collection or storage of some entity therein, and this "potential energy" can be released and dynamically used, (ii) the potential is a scalar function whose spatial rate of change is a vector force, and (iii) the dynamics of the stored energy is suspended by the "storage" or "collecting" entity; in other words it is a sort of "suspen**ded** action" waiting to be unleashed. *It requires some action— such as interception and divergence—to release the leashed energy.*

The second notion is false, since no force exists in the absence of mass because mass m is a *component* of force F via $F \equiv dp/dt = (m)dv/dt + (v)dm/dt$. It is corrected by stating that its spatial rate of change *when interacted with charged matter* is a vector force. For the third notion, we note that the concept of a "virtual" particle or particle flux means that it cannot beco**me** observable unless some interaction is imposed. So we may handle the "third notion" requirement by assuming the potential in modern terms to be composed of hidden virtual particle flux, or hidden wave flux, in wave-to-wave interaction. Physics tries to define the electrical potential as energy per coulomb, or $\phi = W/Q$. That equation, however, is actually not a definition at all (no equation is a definition), but rather is an algorithm for calculating the magnitude of the excess energy collection/collecting upon a coulomb of charge, when that coulomb is immersed in the potential φ. It in fact is the *reaction cross section* of the potential, not the potential entity itself. This now begins to give us a clue, Potential is *energy* in some fashion, and the term "potential energy" is a redundancy. So the φ entity must have essentially the same definition as energy! **Potential** energy, collected energy, stored energy, whatever—it is energy first and foremost. How it is collected and what it is collected upon or in, determines **the** "type" of potential. It also cannot be logically defined as the work expended by it upon a unit charge. The causal entity itself is not the action taken; just as a man is not definable as "how far he has run" in some race.

scattering processes: Collision processes in which an incident particle such as a photon, electron, or proton, of known energy or direction or both, collides with another entity, and emerges from the collision with a different energy or direction or both.

Schrodinger, Erwin: Noted Austrian physicist, 1887-1961, and Nobelist who discovered the wave equation named after him as the Schrodinger equation, and performed other vital work in wave mechanics.

Schrodinger equation: In quantum mechanics, an equation that describes the propagation of waves associated with subatomic particles, or more generally, that describes the evolution over time of the quantum state of a system. The fundamental quantum mechanical equation governing the behavior of wave functions.

self-energy: In a quantum mechanical system, the energy associated with the emission and absorption of virtual particles. In a classical system, the energy associated with the interaction among parts of the system itself.

self-organization: (After Davies, *The New Physics,* 1989): "Spontaneous emergence of order, arising when certain parameters built in a system reach critical values." Simply put, self-organization is the spontaneous formation of patterns of localized order in a system that begins in a more homogeneous state. In short, the system moves from a simpler to a more complex state. Self-organization is one of the permissible features of an open system far from thermodynamic equilibrium with its active environment. Note that the localized orders represent free potential energy formations (free self-regauging) that in theory can then be dissipated in loads to perform free work. Hence the capability of a self-organizing system to perform some free work, or in other words to exhibit COP>1.0.

self-potential (e.g., of the electron): The potential created in and of the charge (e.g., the electron) by its virtual particle flux exchange with the vacuum. Also, an asymmetry in the virtual photon flux of the vacuum, caused by the interaction of the charge (e.g., the electron) with the vacuum flux. From here, we note that the self-potential must consist of real observable 3-space EM energy flow or flows from the electron, because of the asymmetry. However, the charge is not the primary source *per se* **of** the energy flows that establish the self-potential, but instead is the asymmetric gate in the vacuum flux that "gates out" the potential and its energy **flux** The asymmetry in the vacuum flux is the actual *source* or gate. Indeed, in classical terms the energy is received by the charge in the form of converging longitudinal EM energy waves from the complex plane (from the time domain). The spin of the charges of the dipole transduces the absorbed complex EM energy into real observable EM longitudinal wave energy, and pours it out in all directions in 3-space. See discussions under Whittaker and phase conjugate.

self-targeting: Between two entities, where each acts partially or wholly as a phase conjugate mirror, self-targeting is the iterative phase conjugation or "ping-ponging" and rapid convergence of beams between the two PCMs.

S-flow: The Poynting energy density flow S, where S = ExH. Heaviside's equation is given by S = ExH + G. In the latter equation, E is the electric field, H is the magnetic field strength, and G is a trapped closed loop flow of energy density. Note that, from the very definitions of E and H, the Poynting, energy flow represents only that portion of the total energy flow in a spatial region that is diverted by interception and interaction with charges. Heaviside's additional component G, which is not part of the field interactions but a result of the huge noninteracting part of the energy flow outside the interacted ExH component, does appear to be responsible for an enormous unaccounted EM energy flow component that generates the excess gravity required to hold together the arms of the spiral galaxies.

signal wave: In nonlinear optics, the signal (wave) input to a phase conjugate mirror (PCM), that stimulates the PCM to emit a phase conjugate replica (PCR) wave in return. See discussion under distortion correction theorem.

Slepian current: The vector $j\phi$, which in a current loop represents the energy unit area per coulomb of flowing charge, per unit of time, that is collected/collecting from the Poynting S-flow and dissipated in that current loop in its loads and losses.

Slepian flow: "Flow *of collected-energy* density's dissipation" in a current loop, and therefore related to the vector $j\phi$ in the current loop, which represents the energy per unit area per coulomb of flowing charge, per unit of time, that is being dissipated in that current loop in its loads and losses.

Slepian vector: Refers to the vector $j\phi$ in a current loop, which represents the energy density per coulomb of flowing charge, per unit of time, that is being dissipated in that current loop in its loads and losses.

solid-state parametric oscillator: A parametric oscillator circuit employing solid-state devices. A parametric oscillator is a device that oscillates by rhythmically changing a parameter (such as capacitance or inductance, etc.). Simple switching between differing values of the parameter is often used to induce the periodic change of the parameter. One way of close-looping a COP>1.0 EM system is by using a bit of the positive output energy to do parametric switching, in effect converting the system to a self-oscillating energy flow system. The AC flow of EM energy is then much more easily intercepted, collected, and dissipated to power loads without killing the source dipole extracting and furnishing the free flow of EM energy from the active vacuum.

soliton: A "solitary wave" consisting of a wave pulse which propagates without changing its shape and without dispersion.

source dipole: Any dipole, considered from the viewpoint that real observable EM energy continuously pours out of it without any observable EM energy input. There is no true "source" as such in nature, since the energy is not created but only transduced and gated. In the case of the dipole and electrical charge as sources of EM energy, fields, and potentials, the broken 3-symmetry of the dipole initiates an automatic and more primary 4-symmetry, where EM longitudinal wave energy flows into the negative charge of the dipole from the time domain (complex plane), is transduced into normal EM longitudinal wave energy in 3-space, wherein the 3-space energy is absorbed by the positive charge of the dipole, transduced back into time-energy and reradiated back into the time-domain (fourth Minkowski axis). We roughly state that the dipole "emits observable EM energy" into all directions in 3-space as observable EM energy. However, what actually happens is that this *energy 4-circulation process* is what is emitted into and along 3-space, along every radial direction, with the process occurring at every spatial point along that direction. Any charge (taken together with its clustering virtual charges of opposite sign as a dipole) then inserted at any point in space along a radial line, will dipolarly intercept the ongoing process. We will observe the interception by its 3-effect on the intercepting and interacting 3-space charge, but we will not observe the 4-process itself. This deeper examination of the EM field-charge interaction requires a new interpretation of what is meant by "propagation of EM energy through 3-space", which is a non sequitur. Recall again Romer's acid objection **to the** totally illogical picture in every elementary textbook of the so-called "EM wave through 3-space" as a flat x-y plane orthogonal to the line of **motion** z, and where the E-field vector is oscillating along one axis while the magnetic field B is oscillating along the other. That representation is totally false, just as pointed out so strongly by Romer.

spacetime or space-time: The entity represented by the "fused product" of space and time, to give "space x time". Spacetime is also dynamic geometry, in the general relativistic interpretation. We may also consider spacetime to be a giant potential, and also active geometry, and also active vacuum, and also virtual particle flux of the vacuum, and also hidden EM wave flux. If we wish, we can also consider spacetime to be comprised of longitudinal EM waves and impressed dynamics.

spacetime curvature engine: See deterministic pattern and dimensioning.

special relativity: Einstein's theory of inertial frames in which, if two systems are moving uniformly in relation to each other, one cannot determine anything about their motion except that it is relative. Each of the two frames is said to be "rotated" with respect to the other, but not accelerating. The velocity of light in space (the vacuum) is constant, and is independent of the velocity of its source and the velocity of an observer. All the laws of physics are the same in all inertial frames of reference.

spin: The intrinsic angular momentum of a particle such as an electron, proton, neutron, photon, graviton etc., even when at rest, as if it were a top spinning about an axis, but had to spin 720 degrees before it turned "full circle." Spin is quantized, and is always described as a half or whole spin, e.g., - 1, - 1/2, 0, 1/2, 1, etc. A spinning charged particle such as an electron thus demonstrates a magnetic moment, due to the circulation of charge in the spinning. In the nucleus of an atom, the spin of the nucleus is the resultant of the spins of the nucleons (particles comprising the nucleus).

spiral galaxy: A member of the class of galaxies having arms that extend in the form of spirals. About 70% of all galaxies are spiral galaxies: only about 10% of the gravity necessary to hold the spiral arms together can be accounted for by known gravitational sources. This has led to the theorizing of dark (hidden) matter of exotic and unknown form, which would be responsible for the excess gravity. Later it was theorized that some sort of "dark energy" might be responsible for the extra gravity. The present author has proposed that the *unaccounted* enormous Heaviside component of the EM energy flow surrounding every field/charge interaction, and not entering into that interaction, is the missing source of the excess gravity. The dark Heaviside energy flow was arbitrarily discarded by Lorentz in the 1890s, and it is still discarded today by all electrodynamicists and astrophysicists.

Stoney, George Johnstone: Well-known scientist (1826-1911) who first estimated the value of the electronic charge (1874) and was the first to advocate the particle nature of electricity. In 1891, he named the unit of electronic charge the *electron.* In 1896-7 he laid the foundation for Whittaker's 1903 bidirectional wave decomposition of the scalar potential.

string wave or "plucked taut string" wave: The transverse wave on a taut string produced when the string is plucked. The string wave itself stays on the string and does not travel through the slapped external medium.

subspace: In vector mathematics: a subset of a vector space which is closed under vector addition and scalar multiplication operations. In the new approach, we may consider the active ambient vacuum as a giant scalar potential. This ambient potential then decomposes into longitudinal EM waves via Whittaker's 1903 decomposition. One can then refer to longitudinal EM waves deliberately transmitted "inside" that Whittaker "subspace" as "subspace communication". The Fogal semiconductor is able to infold normal EM signals into such subspace signals (longitudinal EM wave signals) in the transmitter, and to outfold the longitudinal EM waves back into normal EM waves in the receiver. Hence the Fogal semiconductor can be utilized to perform subspace and superluminal communication. These capabilities have been demonstrated by Fogal in the laboratory. As this is being written, Fogal is in serious negotiations with several large companies for the funding to get his chips into volume production and onto the marketplace in very sophisticated and advanced equipment representing a great leap forward in technology. There are, however, powerful interests who do not wish the Fogal semiconductor to ever be produced and marketed. We have worked with Fogal for some years, and — once the semiconductors are available in quantity — we will be developing and marketing COP>1.0 electrical power systems utilizing his semiconductors and technology, under license from Fogal.

superconductivity: Property of some materials or metals whereby at very low temperature their resistance reduces to zero. These materials also exhibit many additional properties that are anomalous compared to normal materials. Much research has gone into the attempt to find materials that exhibit superconductivity at higher temperatures, with the goal of reaching room-temperature superconductivity. Room-temperature superconductivity is also just COP = 1.0. EM systems far from equilibrium with the active vacuum, and which exhibit COP>1.0 at room temperature, may involve most of the odd entities also observed in superconducting materials (polarons, lattice holes and hole currents, Dirac sea holes and Dirac sea hole currents, "charging" by Dirac sea hole excitation, vortices, etc.) The energy density in the output section is greater than the energy density input by the operator to the input section. Considering the giant negentropy mechanism and the dipolarity of the input and output sections, the tempic potential of the output section of a COP>1.0 EM system is greater than the tempic potential of the input section. Hence there is a tempic gradient across the entire system, and a tempic force from output to input. This may "sweep" out a great deal of the produced "superconductivity" entities, and particularly may result in a Dirac sea hole current in the vacuum, out of the input section back into the external power source, as a novel output of the COP>1.0 system. Feedback from output to input may also be in the time domain, corresponding to what Gabriel Kron referred to as the "open path". By recombinations and other means, the feedback in the tempic domain may be transduced in the input section of the device to ordinary current in forward time. When the voltage and current in this transduced tempic feedback are properly adjusted to that being supplied from the external power source, the external source can be disconnected and the COP>1.0 system becomes self-powering, while simultaneously powering its load also.

superluminal: Exceeding c, the speed of light in vacuum. Longitudinal EM waves can travel either slower or faster than the speed of transverse wave light in vacuum. See W. A. Rodrigues and J.-Y. Lu, "On the existence of undistorted progressive waves (UPWs) of arbitrary speeds 0 < v<oo in nature," *Found. Phys.*, 27(3), 1997, p. 435-508; W. A. Rodrigues and J. Vaz Jr., "Subluminal and Superluminal Solutions in Vacuum of the Maxwell Equations and the Massless Dirac Equation," *Adv. Appl. Clifford Algebras*, Vol. 7(S), 1997, p. 457-466.

superluminal communication: The movement of intelligent signals faster than the speed of light in vacuum, and the transmission and reception of such signals and extraction of their transported information. Longitudinal EM waves are not limited to speed c, whereas transverse EM waves are. The infolded electrodynamics inside all EM fields, potentials, and waves consists of longitudinal EM phase conjugate wavepairs, with their impressed dynamics. Hence this "subspace" is a superhighway for such waves, including those moving at superluminal velocity. In essence this is a very special kind of "tunneling" which might be referred to as *subspace tunnelling.* The limitation to light speed rigorously applies to the modeled transverse EM waves which are a sort of "bulk upheaval" waves similar to waves on the surface of the ocean. As in the ocean wave analogy, "pressure" waves underneath the ocean may travel very much faster than the bulk upheaval waves on the surface.

When making longitudinal EM waves, the process is imperfect and the resulting longitudinal EM waves will have a transverse residue as well. The resulting "transverse-noisy" LW is called an *undistorted progressive wave*. Undistorted progressive waves may move slower than the speed of light or faster than the speed of light. The degree of transparency of matter to LWs is an inverse function of the "transverse-noisiness" of the LWs.

superposition: The simple linear addition and subtraction of two or more values, states, etc.; one of the key principles in field theories and in the concept of potentials. When the situation is sufficiently nonlinear, however, interaction of waves and potentials occurs instead of simple superposition.

supersystem: A higher level or "metasystem" of interactions between the classical system, the active vacuum, and the active local curvatures of spacetime. Hence the supersystem consists of three interacting components: (1) the EM system and its dynamics, considered in conventional fashion as if the local vacuum were inactive and the local spacetime were flat; (2) the local interactive vacuum and its dynamics, and (3) the local curvatures of spacetime and their dynamics. In component (2), one must consider the Dirac sea, Dirac holes and hole currents, with concomitant potentials and forces impressed on them. In component (3), the time-domain interactions (time-energy, time-force, time-potential, and currents of energy along the fourth Minkowski axis) must be accounted to include negative energy.

All three components of the supersystem interact with each other. In general, the vacuum interactions may be taken from particle physics, and the spacetime curvature reactions may be taken from general relativity. However, this will yield only a rough or "first order" analysis, since it does not produce the tri-reactions of all three components at once, but mostly reactions between pairs of the components. The concept is easy to conceptualize, however, and yields valuable clues and insight in many areas, such as chemistry (including biochemistry), electrical physics, electrodynamics, thermodynamics, and electrogravitation. It is particularly useful in understanding the phenomena encountered in COP>1.0 EM power systems.

symmetrical regauging: In electromagnetics, changing the scalar potential to a different value, and simultaneously changing the vector potential to a different value, with the two changes precisely selected so that the two extra forces (each created by one of the changes) are equal and opposite — thus canceling each other's effect with respect to bulk translation and doing no net *external* work. The two forces remain and can perform internal work upon the system. Note that the stressing effect of the two new forces is not canceled, and that the stress of the system is altered a priori. See regauging.

tantalum capacitor: Electrolytic capacitor with a tantalum or sintered-slug anode, such as a solid tantalum, tantalum-foil electrolytic, or tantalum-slug capacitor.

targeted pinpoints: Those separated points which engage in self-targeting between themselves and some separated signal energy source (as in Fogal's semiconductor). The effect is to sharply narrow the retroreflected source signal energy from the source onto the separated points by means of the mutual ping-ponging. In this fashion much more energy density from the source can be concentrated on the targeted pinpoints. In effect, *phase conjugate shooting* — the return of the phase conjugate reflected scattered energy directly to the original target emitting the signal wave in pinpoint fashion - is evoked. See distortion correction theorem.

tensor: A special mathematical entity which is a generalized vector element of a vector space, with more than three components, each of which is a function of the coordinates of an arbitrary point in space of an arbitrary number of dimensions.

Tesla, Nikola: Famous American emigre electrical engineer, inventor and eccentric (1856-1943), whose numerous inventions fueled much of the electrical 20th century. In essence he produced the AC system, including polyphase systems. Also, Tesla invented radio transmission, not Marconi, according to a U.S. Supreme Court decision that upheld the prior patents of Tesla over Marconi. In his famous experiment, Marconi in fact utilized a variation of one of Tesla's circuits. This does not denigrate Marconi's many accomplishments, but just sets the record straight on who invented radio transmission. The impetus to the development of commercial radio transmission technology and the industry itself came from Marconi.

thermodynamic equilibrium: Stable state eventually reached by an isolated system or one in a well-behaved active environment. One may consider it a "balanced" or "preferred" state. It is important to note that, in particle physics, there can be no equilibrium of a mass system unless the vacuum interchange with that system is considered. Electrodynamics mistakenly continues to omit the active vacuum interaction with a Maxwellian system, hence is seriously flawed in that respect.

thermodynamics of open systems: Systems far from thermodynamic equilibrium with an active environment are permitted to exhibit five "magic" functions. Such a system can (1) self-order, (2) self-oscillate or self-rotate, (3) output more energy than the operator himself inputs (the excess energy being freely received from the active environment, (4) power itself and its load simultaneously (all the energy being freely received from the active environment), and (5) exhibit negentropy.

time: In our view, time is spatial EM energy compacted by the factor c . Time thus has the same energy density as mass, but in the time domain rather than in the 3-space domain. Also, time is not observable *a priori;* mass is an observable. Time persists since it is persistence itself. No observable persists *a priori,* since observation is a *d/dt* operator imposed upon LLLT spacetime, yielding a frozen LLL snapshot which does not even exist the very next instant. When we say "mass exists in time" (or any observable continuously persists), we are unwittingly invoking a very rapid iterative *d/dt* operator repeatedly, and recalling these iterative sequential "frozen snapshots" or observations from memory. One may produce and utilize EM energy flow in the time domain, as in 3-space. Time, being energy and energetic, has tempic potential (energy density), tempic potential gradients, and therefore has "tempic force." The photon is composed of both spatial energy and time-energy as its two canonical constituents. The lower the frequency, the higher the energy of the photon when the time-energy is considered, since the magnitude of the time-component of the photon increases as the spatial energy component decreases, and the energy of the photon in that case increases as c^2 times the increase in time magnitude, while decreasing linearly proportional to the decrease of the spatial energy magnitude. When transduction of time into spatial energy occurs, or vice versa, the energy conservation law is modified to specify the sum of the spatial energy, time-energy, and mass energy.

time-charge, time charging: Since time is a special highly compressed form of energy, then time-excitation or *time-charging* also occurs. Also, since tempic longitudinal EM waves accompany all longitudinal EM waves (per reinterpretation of the phase conjugate half set of the Whittaker decomposition), then irradiating a mass with substantial longitudinal EM wave radiation will time-charge the mass, exciting it with time-energy. There are excited states and internal structuring (engines) in time **charging.**

much like the excited states and internal structuring (engines) in energy excitation of normal charge. When the longitudinal EM wave radiation is removed, the time-charged entity then slowly emits longitudinal EM wave radiation as the time-excitation slowly decays via the giant negentropy process of the charges.

time-energy: Time may be considered as spatial EM energy compressed by the factor c^2. See also discussions under time and time charging.

time excitation: See time charging.

time-flow generatrix (mechanism): Since any observable is a frozen nonpersistent snapshot in 3-space, then the common expression "flow of a mass through time" requires an active generating mechanism to add time to mass, converting it to masstime, which is persistent. Masstime *mt* is as different from mass *m* as impulse *(Ft)* is from force *F*. The flow of a mass through time is generated by the ubiquitous interaction of photons with the mass. This includes all photons, both virtual and observable. Thus for the ambient vacuum, there is an ambient flow of time, since there is an ambient rate of total photon interaction. The "macroscopic" movement of the mass through time is the result of (i) absorptions and emissions of observable-sized photons, and (ii) the continuous integration of virtual photon absorptions into observable-sized photons. The macroscopic flow of time thus has myriads of "sublevels" of infolded time flows and engines. Hence the flow of time has a marvelous, internal, dynamic structure.

time-forward: Refers to the flow of an entity through time in the forward direction, as seen by an external observer. Time-forward flow occurs when (to the observer) there is a predominance of time-forward photons interacting with the body that is moving in forward time. Contrast to time-reversal of an object, as seen by the external observer, which occurs when (to the observer) there is a predominance of time-reversed photons (antiphotons) interacting with the body that is observed to be time-reversed. Pumping a given living mass (in the nonlinear optical sense) with time-reversed EM waves pumps the object in the time domain. That drammatically extends nonlinear optics, since the pumped living object's cells will be observed to slowly reverse back to a previous physical state or condition. Since time-polarized EM waves accompany all longitudinal EM waves via reinterpretation of Whittaker 1903, pumping a living mass (a body) with longitudinal EM waves also pumps it with time-polarized EM waves, time-charging the body which continues the pumping in the time domain after the longitudinal EM wave radiation is removed.

time-forward EM wave: A normal EM wave moving in forward time as seen by the observer. Otherwise known as the retarded wave. The external observer comfortably sees its forward progress as expected.

time-polarized electromagnetic wave: An electromagnetic wave whose vibrations occur in the time domain only. May be referred to in a quantum field theory sense as a *scalar* EM wave. It is a longitudinal EM wave in the time domain. It may also be said to be a longitudinal EM wave in the complex plane, since in Minkowski space the fourth axis may be taken as -ict. The time-polarized EM wave is indicated in quantum field theory, or at least its time-polarized photon is theorized and called a "scalar" photon.

time-polarized photon (scalar photon): A photon whose vibrations occur in the time domain only, also known as a "scalar" photon. This polarization of the photon is utilized in quantum field theory. Neither the scalar photon nor the longitudinal photon is individually observable. However, the combination of the two in the presence of charge is observable as the instantaneous scalar potential.

time reversal: For EM waves, the process of forming the phase conjugate wave. For a particle or a mass, the process of pumping the particle or m;iss with time-polarized EM waves, so that the resident spacetime curvature engine in the mass is amplified and phase conjugated, forming a precise, amplified antiengine which then slowly time-reverses the mass back to a previous physical condition and state. We accent that *time reversing a single object or single group ofobjects* is not the same thing as "travel into the past" so popularized by science fiction. For time travel to the past, the entire universe and everything in it — except the traveler — would have to be time-reversed. That would not seem possible by any stretch of the imagination today! On the other hand, time-reversal of a single thing such as a particle or a wave — or even a group of things such as a group of particles or waves — is not only feasible but is readily achievable. A Dirac sea hole is a negative energy electron, for example, having negative energy and therefore negative mass prior to observation. After observation, it is seen as a positive energy, positive mass electron of opposite charge to the conventional electron and reacting with fields in opposite direction from the conventional negatively charged electron. In short, after observation (interaction with mass) it becomes the positron.

time reversal zone: A region of space in which the majority component of the overall time flow mechanism runs backwards, and hence the fundamental mechanism generating the flow of a mass through time is reversed. The "time running backwards" is due to the predominance of interactions with antiphotons. It follows that, in the time-reversal zone (TRZ), there is a predominance of antiphoton interaction over photon interaction. In a TRZ, the law of attraction and repulsion of charges is reversed; like charges attract and unlike charges repel. Also, induced action by the time reversal forces start *inside and throughout* an affected mass in that zone, originating at every point in that local spacetime zone and moving outward. It thus involves a novel action "from inside to outside", beginning even inside the nucleons, and first affecting the quarks and gluons. Deliberate use of time-reversal zones and their subsequent decay allows a great new class of dramatic nuclear reactions, including simple transmutation and loosely called "cold fusion" reactions, at low spatial energy but very high time-energy. High energy physics has neglected the use of time-energy, opting to go for high spatial energy. Hence the high energy physicists have actually eliminated a much higher energy physics (at low spatial energy so readily examined on the bench far *more ch*eaply) than the science they have long developed.

time-reversed wave: A phase conjugate reflected wave, which is a wave moving in reversed time. Since the external observer "sees" in forward time only - and even then he sees in an iterative series of frozen 3-space snapsholt —he *observes* the time-reversed wave as a 3-spatial wave (series of iterative frozen snapshots) traveling in the opposite direction as its generatrix wavefront (the *signal wave).*

topological: Invariant under transformation by continuous mappings, or related to the properties of geometric shapes and figures that remain invariant under transformation by continuous mappings.

topological properties: Those properties of a geometrical space that are unchanged by continuous distortion of the space.

topology: Mathematics of the properties of geometric configurations invariant under transformation by continuous mappings. In short, the mathematics of the large-scale structure of curved spaces.

transverse (with respect to waves): Wave oscillatory movement perpendicular to the wave's primary direction of principal propagation, as in the movement of a plucked taut string in a wavelike motion traveling down the string but with the oscillations being lateral. Based on Faraday's notion that the field lines of the electromagnetic field were physical material lines (in the material ether) similar to taut strings, Maxwell assumed the transverse wave model in his theory. The entry of longitudinal waves, into the theory can easily be demonstrated by rhythmically and coherently varying the magnitudes of the Lorentz symmetrical regauging condition, producing "stress potential waves" which are in fact what longitudinal EM waves really are. The production of a longitudinal EM wave in 3-space will be accompanied by the simultaneous production of a time-polarized companion wave.

tunneling: In quantum mechanics, a phenomenon in which a particle penetrates and crosses a small region where the potential opposing such passage is greater than the particle's available energy. The phenomenon is thought to be impossible according to classical physics, but occurs nonetheless. Further, the speed of transit through the "tunneling" separation can be superluminal. Tunneling of music between two separated points in a waveguide has been measured at more than four times the speed of light.

A more extended type of tunneling is the travel of longitudinal EM waves infolded inside the normal EM potentials, fields, and waves. Indeed, this is a more fundamental electrodynamics, and it can be shown that interferometry of this "internal" electrodynamics creates the external electrodynamics by a form of longitudinal EM wave interferometry. E.g., see M.W. Evans, P.K. Anastasovski, T.E. Bearden *et al.*, "On Whittaker's Representation of the Electromagnetic Entity in Vacuo, Part V: The Production of Transverse Fields and Energy by Scalar Interferometry," *Journal of New Energy,* 4(3), Special Issue, Winter 1999, p. 76-78. This is part of the technical basis for the "scalar interferometry weapons" developed by the Russians after World War II. Today, some 10 nations have such weapons, more are developing them, and even the Japanese Yakuza has such weapons.

unified field theory (engineerable): A unified theory of the four forces o| physics — the electromagnetic, gravitational, strong, and weak forces that is not just an intellectual model but which is also engineerable on **the** laboratory bench and in actual physical systems using higher symmetry O(3) electrodynamics as a special subset of Sachs' unified field theory.

unitary Q_E (charge of the electron): Fixed or unit charge q of the electron. This notion is held because q is not decomposed into its component elements, but treated as if it were an indivisible unit, charge and mass and all. The mass of a fundamental particle at rest is quantized, and the massless charge (self-potential) of the particle is discretized as a function of the background potential (virtual particle flux density) in which it is embedded or to which it is exposed. In our view the definition **of a** charge q is $q \equiv m_q\phi_q$, at least to first order. (The ϕ_q may be internally structured with deterministic "engines", so that one electron need not bo identical to another, in its actions in some cases). The *electrical charge* of the "charged mass m_q" should be taken to be the massless ϕ_q component. For an electron, $q_e \equiv m_e\phi_e$. The *electrical charge* of the electron should be taken to be the massles ϕ_e component. We note that the charge is also structured, since ϕ_e or ϕ_q decomposes via Whittaker 1903 into a harmonic setof EM longitudinal phase conjugate wavepairs. Our reinterpretation of this decomposition then yields the solution to the problem of the "source charge" and its associated fields and potentials and their energy. The massless charge ϕ_e is a dipolarity and hence a broken 3-symmetry in EM energy flow, invoking a more primary 4-symmetry in EM energy flow so that EM longitudinal wave energy is continuously incoming from the time domain, being absorbed by the charge q of which ϕ_e is a component, being transduced into real EM energy in 3-space, and emitted in all directions in 3-space at the speed of light, creating the fields and potentials and their energy that are associated with charge q. If a charge (say, an electron) is placed in an additional potential ϕ_1, then the total massless charge of the electron (i.e., its virtual vacuum flux exchange with mass me) is $(\phi_e+\phi_1)$.

As can be seen, the massless charge of the electron (its virtual flux activity) has now changed. The electron is then said to *be collecting and to have collected* excess energy (which may be either positive or negative, depending upon the sign of ϕ_1). Further, either ϕ_e or ϕ_1 or both can be internally and deterministically *dimensioned* (structured in Stoney-Whillaker-Ziolkowski fashion). When its massless charge (its own ϕ_e) potential is so dimensioned, then the dimensioned electron is said to contain or transport an *engine* or a *vacuum engine* or a *spacetime curvature engine.*

vacuum: Space devoid of observable matter. In modern theory, the "empty" space is in fact bristling with very rapid fluctuations of EM energy, remaining in the virtual state. It is also filled with a violent, fluctuating flux of virtual particles, appearing and disappearing so quickly that an individual particle does not persist long enough to be individually detected. Thus the vacuum is extraordinarily energetic, but the energy is in very special form (fleeting violent fluctuations and virtual particle flux). Nonetheless, because it contains enormous energy, the *average* vacuum may be considered a potential. All potentials then are changes to this vacuum potential, or to an intermediate potential which is a change to it. In another sense, the vacuum, potential, and spacetime are all one-and-the-same thing. This means that general relativity's spacetime curvature is ubiquitous and extraordinarily dynamic. The vacuum very near a mass also can act in some cases as a semiconductor, capable of supporting self-oscillation between the mass and the local vacuum. Considerations of the active vacuum and its nature lead to the notion of the *supersystem,* which is comprised of three parts: (1) the physical system and its dynamics, (2) the active vacuum and its dynamics, and (3) general relativity and its dynamics (since physicists persist in separating the notions of spacetime and vacuum). No analysis of any mass system is complete unless an analysis of the entire supersystem and the interactions of the three components, one with the other, is performed.

Every charge is "embedded" in the active vacuum by its potentials and fields, which themselves are spacetime curvatures and alterations of the local vacuum. This is easily seen by $q \equiv m_q \phi_q$, where ϕ_q is a change to the local vacuum potential *a priori.* In the quantum view, the fields and potentials may be taken as organized polarization patterns and dynamics (currents) in the vacuum virtual particle flux.

vacuum engine: Also referred to as a *spacetime curvature engine.* From the particle view: a deterministic internal pattern or *template* deliberately created as a deterministic structuring and dynamics in the virtual flux comprising a scalar potential. It can also be created in, and transported by, the two scalar potentials that comprise a static or dynamic force field, or a moving EM wave in the vacuum. It can also be created in the local vacuum potential, in which case it has a "charge-up" creation time and a "discharge time," exhibiting a sort of "time constant" very much like a capacitor charging and discharging.

In the wave view: the vacuum engine is a deterministic internal pattern or template deliberately created in the Stoney-Whittaker-Ziolkowski internal biwaves and wave products comprising the scalar potential. Again, it can be implanted in the vacuum or in an EM signal as a carrier. The self-energy (scalar potential) portion of any electric charge or magnetic charge can also be a "carrier" that is conditioned *{dimensioned)* with a vacuum potential. The process or act of conditioning any of the carriers with vacuum engines is called *dimensioning* that carrier. Russian energetics used in secret weapons programs refers to the vacuum engines of a dimensioned carrier as the *information content of the field.* Such vacuum engines, e.g., were used in the potentials of the microwave radiation of the U.S. Embassy in Moscow for several decades, inducing a variety of health changes and sicknesses in the personnel of the embassy. Interestingly, all these health changes occurred in the field-free regions of the Embassy. There the field-free potentials existed and were stable and unchanging. Hence a body exposed in that region was steadily exposed to the specific engine being induced, and time-charged with that engine accordingly. The deterministic set of spacetime curvatures comprising this charge then acted upon the cells and body to slowly change it to the damaged or diseased condition. See dimensioning.

vacuum flux exchange: The virtual particle interaction between the active vacuum and a mass, particularly a charged particle.

vacuum's **virtual particle flux:** In the particle viewpoint, the quantum mechanical vacuum identically is a virtual particle flux. Present physics, however, is prone to refer to the vacuum as an implied emptiness containing a virtual particle flux, even though that is known to be in error. In our view, energy, vacuum, spacetime, virtual particle flux, and dynamic geometry are all synonyms. One must note that the ageless contradiction of the wave vs. particle view has still not been resolved in physics, even by the duality principle. The duality principle is merely an agreement to quit fighting, and to feel free to consider a thing a particle in one case or circumstance and a field in another case or circumstance, *whichever works.*

vector: In mathematics, an entity completely characterized by a magnitude and a direction.

vector potential: A potential having — at any point in it — both direction and magnitude. The direction, e.g., may be linear, curvilinear, or swirling. The term "vector potential" is often used as the magnetic vector potential A. When it is swirling, the magnetic vector potential A may be said to be the magnetic field B. However, the swirling magnetic vector potential (the magnetic field B) may be "bottled up" and contained locally inside a long tight solenoid, or inside a toroidal coil, or inside a special nanocrystalline material used as a closed transformer core as in the motionless electromagnetic generator. In that case nature freely replenishes the energy in the surrounding space which would have been occupied by the nonrestricted, nonlocalized B-field (curled A-potential) but replenishes that space with an uncurled (linearly flowing) magnetic vector potential A. This in fact at least doubles the available energy flow available, without any additional EM energy input by the operator. The well-known Aharnov-Bohm effect clearly demonstrates this effect, and it is deliberately employed in the motionless electromagnetic generator (MEG) of which the author is one of the five co-inventors. Present dictionaries of physics and many textbooks are confused as to the definition of magnetic vector potential A and its relation to B, many stating that the A is defined by the equation $\nabla\times\mathbf{A} = \mathbf{B}$. However, no equation is a definition; it is an expression of equality of two magnitudes, and not a definition of either side. If we substitute the more stringent $\nabla\times\mathbf{A} \equiv \mathbf{B}$, we see that the $\nabla\times$

operator acting upon the A potential is precisely what a B field *identically is*. Hence the A potential exists in two forms: (1) in curled form as identically the B-field, and (2) in uncurled field-free form as the linearly moving A-potential energy current that has no imposed $\nabla\times$ operator and thus has no curl. This makes total sense with $\nabla\times\mathbf{A}\equiv\mathbf{B}$.

vector field: Conventionally, the assigning of a magnitude and a direction (that is, a vector) to each point in a region of space occupied by a field. In our view the field is in fact a change to the active energetics of that spatial region, such that the region will interact with any appropriate entity (e.g , **a** charged mass) placed at any point in the region and produce a force upon that entity.

vector zero: See discussion under zero vector.

virtual antiphoton: An antiphoton that spontaneously appears and disappears, so swiftly that it cannot be individually observed. It is real while it exists. Coherent integration of a stream of virtual photons, however, adds to produce an observable quantum of energy, which is observable in its effects on a charged particle.

virtual particle: A fleeting quantum particle that spontaneously appears and disappears, so swiftly that it cannot be individually observed, so that it exists only temporarily. It is real while it exists. The virtual particle does not satisfy the usual relation between energy, momentum, and mass because it is under the aegis of the Heisenberg uncertainty principle. The virtual particle can have any amount of energy momentarily, so long as the product of its energy and the time interval of its existence is less than the uncertainty principle's minimum magnitude.

The coherent interactions of large numbers of virtual particles with a **mass** or charge can combine to generate real observable effects (forces). In quantum field theory, all forces of nature are caused by the interaction **of** the mass entity with virtual particles. Interaction of a mass with virtual photons, e.g., is projected to cause all mechanical and electromagnetic forces.

virtual particle flux exchange: Interaction with or exchange of a flux of virtual particles.

virtual photon: A photon that spontaneously appears and disappears in the vacuum so quickly that it cannot be individually observed.

virtual photon flux: See definitions under **flux** and under **virtual particle.** For electromagnetics, the vacuum can often be modeled as a flux of virtual photons. One gets the virtual charges also, since the photon is also considered to consist of a positron-electron pair. That is, the photon is continually separating into a positron-electron pair, whose particles then annihilate each other to form additional photon(s), etc.

virtual photon flux exchange: The mutual exchange of virtual photons, as between the vacuum and a charged mass, or between two colliding masses.

virtual photon flux of vacuum: In our view, the vacuum identically is a flux of virtual particles. For many electromagnetic cases, it can just be modeled as identically a flux of virtual photons, where the word "photons" in general usage refers to both photons and antiphotons.

virtual positron: A positive electron (positron) which spontaneously appears disappears in the vacuum so quickly that it cannot be individually observed. More accurately, in the 4-vacuum, a negative energy electron state that spontaneously appears and disappears so quickly that it cannot be individually observed. A virtual Dirac sea hole.

Whittaker, Edmund Taylor: Well-known English mathematician and physicist, 1873-1956, who made major contribut ons to mathematics and physics. Whittaker dramatically extended Stoney's earlier work of 1897-8 an authored two papers in 1903 and 1904 giving the basis for the theory of scalar electromagnetics (Russian energetics, not including the quantum potential portion). His decomposition of the scalar potential into a harmonic set of longitudinal EM wavepairs, where each pair is a phase conjugate pair, may be reinterpreted to solve the long-vexing problem of the source charge or source dipole and its continuous emission of EM energy in 3-space, providing its associated potentials and fields and their energy. The problem was solved by the present author's reinterpretation in that manner, published in 2000. This was later found to be consistent with quantum field theory as well, by interpreting the observability of the combined scalar and longitudinal photon pair as opposed to the nonobservability of either the scalar or longitudinal photon individually.

Work: The changing of the form of energy. One joule of energy whose form is totally changed in a reaction, does one joule of work in that reaction. However, it is strongly stressed that after that joule of work is perform**ed,** one still has a joule of energy left to use (with which to do additional work). This remaining joule of energy is just in different form than was the initial joule of energy. So one can do joule after joule of work from a single *initial* joule of energy, so long as the energy is not dissipated and lost after each change of its form. In any one single change of form, only o**ne** joule of work can be done from one joule of energy. So energy is conserved through many changes of form, but work is not. To work in COP>1.0 systems, one absolutely must root out from one's consciousness the mistaken notion that only one joule of work can be done from a joule of input energy. One of the places where extra joules of work are performed by each joule of energy is that of strong gradients. Strong gradients are known and recognized to violate thermodynamics. Work is further divided into **internal work** and **external work.**

work, external: The changing of the form of the collected energy of a body or system by dissipating it upon an external load or entity is the external work *done by* a body. The changing of the collected energy of a body or system by performing work upon it is the external work *done upon* a body or system.

work, internal: The changing of the form of the internal energy of a body or system. It may also involve the changing of internal parts of the system.

work-energy theorem: In mechanics, a theorem that the change in kinetic energy of a particle in motion is equal to the work done by all the forces acting upon the particle.

zero-point energy: The energy remaining at a temperature of absolute zero, due to the Heisenberg uncertainty principle and the quantum mechanical theory of an oscillator. Also, the minimum energy of a system due to its quantum fluctuations, resulting from its incessant virtual particle activity. Quantum mechanically, no system of interest (including even spacetime itself) can have zero energy. The zero-point energy of the vacuum is the lowest energy vacuum state, with fluctuations taken into account. Even at low energies, quantum fluctuations continually arise, and result in an incessant, extremely rapid, and violent "jittering" of the energy momentarily present. The minimum energy due to these quantum fluctuations is called the *zero-point energy.*

zero vector: Candidates are: (i) A vector having no length (no magnitude) or specific direction; (ii) absence of any and all finite vectors; (iii) resultant of a system of multiple, finite vectors whose vector sum has **no** specific direction but may have nonzero scalar magnitude.

The second definition differs drastically from the first. That is, we **cannot** say that a vector resultant zero has no infolded magnitude, if we **consider** its nonzero components, all of which have magnitude. (See the discussion under **zero).** It only has no net magnitude for *translating* force. It is, in fact, *a. stress potential,* and it is one with a deterministic internal structure or *engine.* By rhythmically and coherently varying each component of a zero vector system, one easily produces longitudinal EM waves,, each of which is accompanied by a correlated time-polarized EM wave. In vector analysis, the zero vector axiom states that any vector v plus a zero vector is equal to a zero vector plus v. Note that, being an axiom, this is not proven, but just assumed for any zero vector. We very much disagree with that blanket axiom; it reduces vector analysis to a highly special single case, where all zero vector systems are to be considered equal, and totally "inactive." That is true only for bulk translation. In the real world that need not be true at all; specifically, it is not true for two different zero vectors having different internal structure and dynamics (different internal engines).

There are an infinite number of different zero vector resultant systems, and so zero vectors may differ, if their infolded component "substructure" is considered. In the real world, things that are vectors very often have energy. The energy is infolded and hidden, so that it represents not only (i) a local curvature of spacetime, but also (ii) a structured, deterministic set (a template) of curvatures of local spacetime. Therefore this zero vector system is actually a *vacuum engine.* Any mass system placed in such a potential, will be acted upon in its internal parts by that local vacuum engine; in short, it will have internal work performed on its interior. Further, the zero vector resultant system is a "stress potential," since it does contain "collected internal energy."

So between zero vector resultant systems, the "infolded, hidden energies" differ dramatically in (i) total infolded and trapped (collected) energy, (ii) specific internal action patterns (templates), (iii) general relativistic effects, and (iv) type of engine. Accordingly, the actions the zero-vector system induces in an exposed mass may be designed in advance. This is vacuum engineering. This spacetime engineering. This is the formation and use of engines. It is also one of the bases of Russian energetics.

The'problem is the *vector algebra itself.* In the abstract algebra, a "vector space" Is regarded as an inert thing, where the only actants are the overall net nonzero vectors, and there is no interaction between an overt vector and a covert set of vectors. The vector space is not allowed to have an internal realm, stress, hidden engines, or to interact with the vectors representing the physical system. So vector algebra lacks the capacity to model such higher topology phenomenology. Consequently, for over a century electrodynamicists — thinking primarily of spatial translation — have routinely discarded such "zero vector systems" as if they represented the total absence of any finite vector. *This they do, in the unsuitable* *assumptions of the vector algebra.* This they do not do, in the real world, whether we are aware of it or not.

The common practice in electrical physics of replacing a zero-summed system of nonzero vectors with a vector zero indicating a "complete absence of vectors" is very much incomplete. This present practice should be changed; it has reduced the topology of electromagnetics far too much, and gutted vast, important parts of the theory insofar as an extended electromagnetics is concerned. The vector zero should be replaced with a special organized vector zero system and a dimensioned scalar potential.

The interactions of the "hidden" vectors — the *engines* — should be incorporated. By failing to do this, physics excludes the ability to engineer electrogravitation, spacetime, the virtual state, local general relativity, free energy, effects at a distance, and the probabilities of the states propagated by the Schrodinger equation. It also excludes unification of forces. As another more human example, for every cellular disease condition there is a specific engine resident in the cells. An amplified antiengine for that disease pattern can fairly readily be generated. That antiengine, embedded in ordinary EM fields and potentials, can be irradiated into a diseased body with that disease, and it will time-reverse those diseased cells slowly back to normal. This is actually the basis of the body's own healing system the cellular regenerative system studied mostly by Becker. Unwittingly using this "antiengine" approach, Priore and a team of French scientists provided startling cures of terminal cancers, infectious diseases, clogged arteries, etc. in laboratory animals in France in the 1860s and early 1970s. The work is strongly documented and replicated in the French scientific literature, but the work was suppressed in the early 1970s in the change of the French government. See our "porthole briefing" on our website www.cheniere.org for our extension of the Priore method, for greater ease portability, and rapid treatment of mass casualties.

In the new view, a zero vector may be a system of nonzero vectors that vectorially sum or multiply to zero for spatial translation purposes, but nonzero components may still exist "inside" and dynamically function inside the zero-resultant envelope. This substructure can act on nonlinear or resonant systems. Any or all of the nonzero components may be time varying, or none of them may be. The zero vector system may thus be a dynamic engine and a dimensioned scalar stress potential. In addition, such a vector zero system is considered to be also a scalar stress potential, whose magnitude is equal to the sum of the absolute values of the components. In addition, a separate type of stress potential may be included for the magnitude of the absolute values of the swirl components (torques). Other associated potentials may be included for the system, particularly if the system is in multiple dimensions, if it consists of more than one type of virtual particle flux, if several fluxes intercommute, etc.

zero vector summation systems: Zero summations of real, nonzero vectors, so that the real vectors are still present but do not cause *spatial translation* of the exposed mass or charges. Instead, the zero vector summation has an internal structure and dynamics, hence an internal engine. Also see discussion under zero vector.

Appendix A

Relation to Equilibrium and Disequilibrium Thermodynamics

"The second law [of thermodynamics] does not rule out the possibility of pushing heat uphill, as it were, from a cold object to a hot one, or of creating order out of disorder. It merely states that such a reversal of the natural flow requires an influx of energy... " [Raymond Serway] {697}

"It *is in no way possible, either by mechanical, thermal, chemical, or other devices, to obtain perpetual motion, i.e., it is impossible to construct an engine which will work in a cycle and produce continuous work, or kinetic energy, from nothing. "* [Max Planck] {698}.

"What might appear to be empty space is, therefore, a seething ferment of virtual particles. A vacuum is not inert ***and*** *featureless, but alive with throbbing energy and* ***vitality.*** *A 'real' particle such as an electron must always be viewed against this background of frenetic activity. When an electron moves through space, it is actually swimming in a sea of ghost particles of all varieties - virtual leptons, quarks, and messengers, entangled in a complex melee. The presence of the electron will distort this irreducible vacuum activity, and the distortion in turn reacts back on the electron. Even at rest, an electron is* ***not*** *at rest: it is being continually assaulted by all manner of other particles from the vacuum."* [Paul Davies] {699}

"I assert... that for the general theory of relativity, i.e., in ***the*** *case of the general invariance of the Hamiltonian function, energy equations... corresponding to the energy equations in orthogonally invariant theories do not exist* ***at all.*** *I could even take this circumstance as the characteristic feature of the theory of general relativity. "* **[D. Hilbert]** {700}

*"**In formulating the** equivalence principle, Einstein actually abandoned the idea of the gravitational field as a*

Faraday-Maxwell field, and this is reflected in the pseudotensorial characterization of the gravitational field that he introduced. Hilbert was the first to draw attention to the consequences of this. ... Unfortunately, ... Hilbert was evidently not understood by his contemporaries, since neither Einstein himself nor other physicists recognized the fact that in general relativity conservation laws for energy, momentum, and angular momentum are in principle impossible. " [Logunov and Loskutov] {701}

"No amount of theory can refute a replicable experiment that contradicts the theory. A single replicable experiment can refute any theory that is in conflict. That is the very heart of the scientific method. " [Myron Evans, private correspondence].

"It only takes a single white crow to prove that not all crows are black. " [Anon.]

"One of the most important principles of physics, that disorder, or entropy, always increases, has been shown to be untrue. " [BBC News] {702}

"One of the most fundamental rules of physics, the second law of thermodynamics, has for the first time been shown not to hold for microscopic systems. ... [The experimenters]... found that the change in entropy was negative over time intevals of a few tenths of a second, revealing nature running in reverse. ...But over time intervals of more than two seconds, on overall positive entropy change was measured and normality restored." [Chalmers] {703}.

"We experimentally demonstrate the fluctuation theorem, which predicts appreciable and measurable violations of the second law of thermodynamics for small systems over short time scales... Our results show entropy consumption can occur over colloidal length and time scales. " [Wang et al.] {704}.

A.1 Introduction

For excellent background books on thermodynamics matters, at various levels of difficulty, the reader is referred to texts by Gyftopoulos and

Beretta {705}, Kondepudi and Prigogine {706}, Chalidze {707}, and Dugdale {708}.

It has long been known in physics that at sufficiently small levels (e.g., atomic levels) the second law of thermodynamics does not always hold true. Recently, as quoted above, Wang et al. {704} have extended this area of permissible violation of the second law to much more appreciable times (a few tenths of a second) and lengths (the micron scale). Without further discussion, we note that this places regions and times of negentropy well-within circuitry switching times and interaction with fundamental chargedparticles. Hence these experiments are beginning to point the way to practical negentropic devices. When coupled with the demonstrated continous giant negentropy of a charge (considered with its clustering virtual charges of opposite signs), these experiments now strongly support the feasibility of practical overunity EM circuits and systems. The interested reader is encouraged to continue to read the literature along those lines, and stay abreast of developments in that field.

In this book we have presented considerable discussion of time-energy (time as a special, highly compacted form of energy). We have also discussed the three components of the supersystem, including the system, the local active vacuum, and the local curvatures of spacetime. All three componets of the supersystem interact with each other continuously, and such Interactions are not modeled in classical thermodynamics (CTD), classical electrodynamics (CED), or electrical engineering (EE). Hence one should not be surprised that the supersystem model and supersystem analysis involve contradictions (actually, *extensions)* of these three models, which are special cases and approximations only.

All COP>1.0 EM systems result from supersystem component interactions. So COP>1.0 EM systems are in conflict with CTD, CED, and EE since these three models exclude those interactions.

To falsify any absoluteness of the three models considered, one or more solid, demonstrable, replicable experiments are presented to establish validity of the new higher symmetry approach. This is sufficient to negate the conventionally accepted absoluteness of the lower symmetry CTD, CED, and EE models. Scientifically, these experiments suffice to demonstrate that those three models describe *"special-case* domains of nature" rather than full generalizations of nature. It is clearly understood that the three models remain very useful and very often quite sufficient, just as Newtonian mechanics is useful and often sufficient, without use of relativistic mechanics.

The experiments also falsify any interpretation of the three models as "proof that COP>1.0 systems are impossible. Accordingly, many of the accepted statements and assumptions of the three models must be corrected for COP>1.0 research, as must be the conventional interpretation that the laws of nature (as understood based on those three models) prohibit COP>1.0 EM systems. This follows directly from the quotation by Evans at the beginning of this appendix. Experimental evidence of COP>1.0 is abundant and decisive, such as the many hundreds of routine "negative resonance absorption of the medium" experiments as typified by Bohren's paper {709} and experiment and Letokhov's work {710}. Also, every charge in the universe already falsifies all three models, as amply discussed in this book. That fact for at least a century has generated the source charge problem — the problem of the source charge and its associated fields and potentials and their energy, reaching across the universe. The solution to this problem was published by the present author in 2000, based on the experimentally proven and well-established broken symmetry of opposite charges, such as are on the ends of a dipole.

In the extended approach, conservation of energy in 4-space does not require simultaneous conservation of energy in 3-space. The concept of energy conservation in 4-space does not exist in the three models mentioned, which contain only 3-space energy conservation. There exists a "giant negentropy" 4-space energy flow (circulation) mechanism, as we developed in this book, and it is experimentally demonstrated by every charge in the universe. In a classical 3-spatial energy conservation analysis and view, the giant negentropy action may continuously perform useful work in a system, since it already furnishes all EM field energy and potential energy in every system. All 3-space energy conservation is an extra condition imposed upon 4-space energy conservation, and that condition may be violated at will without violation of the general conservation of energy law.

To the three conventional models mentioned, 4-symmetry in energy flow with broken 3-symmetry, will appear to be perpetual motion and a total violation of the more limited 3-space conservation of energy law. It *does* permissibly violate 3-space energy conservation, which is just a special case a priori. But it is not a violation of energy conservation overall, since we are using a more fundamental energy conservation law (4-symmetry) than the 3-symmetry used in the mentioned CTD, CED, and EE models,

In short, the three models must be extended to provide 4-space energy conservation with simultaneous violation of 3-space energy conservation, accompanied by simultaneous time-symmetry energy flow violation. The two broken symmetries — of 3-space energy flow and of time domain energy **fl**ow — thus act as a special extension of the notion of symmetrical regauging, accomplishing it by "equal and opposite-effecting" fields, one in **the** lime domain and one in 3-space.

Ironically it then follows that what have heretofore been conceptually called "perpetual motion machines" with respect to 3-space energy conservation are simply attempts — successful or unsuccessful — to build analogues of a windmill turning in a free wind and powering a load. In short **t**hey are attempts to duplicate in systems what every charge in the un**iverse** already demonstrates unequivocally. *Nature's* CTD, CED, and EE do not prohibit such systems — again, as evidenced by every charge in the universe demonstrating exactly such "perpetual motion" (we prefer the exact term "giant negentropy") and violation of present *human* CTD, CED, and EE. None of the original charges from the beginning of the universe has slowed and stopped its motion, or stopped pouring out EM energy freely, in some 14 billion years or so. And charge may be taken as the most basic Maxwellian system. Further, all EM fields and potentials, and their energ***y,*** comes from their source charges. So those so adamant against perpetua**l** motion machines should first purge their own three models of their *assumed* perpetual motion machines. If this is done, they will purge the three models of all charges, fields, and potentials — and all EM energy in the **process.** In short, the three conventional models used by those same ske**ptlcs** so loudly condemning "perpetual motion machines" will eat **themselves"** by swallowing their own tail, so to speak.

in short,all three models are easily falsified by every charge in the universe**,** as well as by every EM field and potential, and by the existence of EM energy itself.

Either their models must surrender any pretense at absoluteness and accept being useful approximations only, or else the conservation of energy law **itself must** be surrendered.

Conventional CEM, CTD, and EE have just hidden this appalling fact and convealed the serious flaws in the modeling by ignoring what Sen {711} reffered to as " t*he most difficult problem in classical and quantum electrodynamics.* " We believe it will very difficult to find a single electrical engineering department or professor or text that deliberately acquaints electrical engineering students with the source charge problem and its implications.

As an example, in Chapter 9 we presented an experimentally verified and patent-pending method for a special energy conversion method. This method is proven on the laboratory bench. With this method, a system accepts time-energy and negative energy input, converts it to ordinary positive 3-spatial energy, and uses the converted input energy to close-loop an EM system far from equilibrium. With that conversion process invoked in a governed feedback loop, the COP>1.0 system becomes "self-powering" (an informal term referring to the system freely receiving all its input energy from its active environment). Self-powering, of course, involves the system continuously operating and performing useful work, analogous to a windmill in a wind and powering a water pump. Rigorously, the self-powering COP = oo EM system becomes directly powered by energy from the broken symmetry induced in its supersystem component interactions.

In Chapter 10 we presented the novel concept of the time-reversal zone (TRZ), which uses the extraordinary EM energy density of time to reverse the Coulomb barrier in nuclear reactions in an electrolyte {712}. This enables nuclear transmutation reactions at low *spatial* energy (but at very high *total* energy when time energy is also considered). There are some 600 successful cold fusion experiments worldwide, in multiple laboratories, by multiple researchers, and most of these experiments demonstrate examples of the specific nuclear reactions made possible by the actions of the TRZ. The time-energy anomalies are directly demonstrated in rigorous electrolyte experiments at U.S. Navy research facilities at China Lake, as we have also discussed in this book. So the experimental results are replicated and well proven. Hence there is adequate, replicated experimental demonstration that additional nuclear reactions exist outside the conventionally known nuclear reaction model. Therefore the set of conventional nuclear reaction models also is reduced to a special case domain, with any absoluteness of those models already experimentally falsified. Either that, or we must abandon scientific model where successfully replicated experiments falsify any theory in contradiction to the experiments.

In our proposed solution to the source charge problem {71 lb}, we found a broken 3-symmetry in energy flow while 4-symmetry is maintained. This is a more primary principle of energy conservation. We called this principle "giant negentropy", which is laughably simple to demonstrate experimentally, since every charge and dipole in the universe already demonstrates it. We showed that such giant negentropy is consistent with quantum field theory, particle physics, and a slight corrective reinterpretation of Whittaker's 1903 decomposition of the scalar **potential** The experimentally proven and theoretically justified giant negentropy falsifies any absoluteness of the CTD, CED, and EE models in conflict with it.

Again, this does not mean that one abandons the CTD, CED, and EE models! They are still very useful models in most cases of interest. It means that these present models are still incomplete, and extended models must be developed and used for COP>1.0 EM system research. It also means that none of these three models is valid as a prohibition of the permissibility of COP>1 EM systems.

All EM energy in 3-space comes from the time domain and returns to it. Since all three models exclude time-energy and its transduction into spatial energy, all three are in conflict with the proven giant negentropy model and with the unlimited experimental demonstrations. Accordingly, the experimentally demonstrable giant negentropy of the charge and dipole strongly points out the inadequacy of the three models and the nuclear reaction models, which do not account for time reversal zones, or time-energy and its transduction into a very large magnitude of 3-space energy.

In paragraph A.2 below, we briefly discuss some of the fundamental but permissibie supersystem violations of these older models of CTD, CED, and EE, and provide some comments. It is obvious that all three classical models need very serious updating and extension. We point out that exceptions to present thermodynamics models and "laws" already are recognized{713}, and work on such exceptions is being performed under the heading of extended thermodynamics {714}.

In effect, all three models *exclude* every charge, dipole, or dipolarity in the universe - which therefore excludes all matter, fields, and energy - something completely untenable in modern electrodynamics and modern physics. Since the fundamental nature of the "heat" notion of CTD is electromagnetic field energy, and all EM fields and potentials (and their energy) are excluded if their source charges are excluded, then heat itself is excluded by the three models. That is, CTD is also totally falsified by CED'S exclusion of the source charge's demonstrated giant negentropy, which in effect excludes heat itself. This is a non sequitur of such magnitude that it absolutely requires the complete rework of CTD, CED, and EE.

A.1.1 Featurcs of the Development of Thermodynamics

In the development of thermodynamics, a few key events of interest are listed in Figure A-1 below.

Selected Events in the History of Thermodynamics {715}

1673	Huygens builds a motor driven by gunpowder explosion.
1690	Papin uses steam to move a piston.
1712	Newcomen develops a steam engine.
1723	Stahl popularizes phlogiston and Becher's concepts.
1724	Boerhaave proposes that heat is a fluid.
1733	Bernoulli publishes a text that is the first truly statistical treatment of kinetic theory, and publishes an update in 1738. It is almost forgotten until 1859.
1765	Watts invents a steam engine that is more than six times more effective than Newcomen's engine.
1783	Lavoisier points out the weakness of phlogiston theory with respect to combustion.
1786	Lavoisier and Laplace provide a Memoir on Heat.
1789	Lavoisier publishes his *Elementary Treatise on Chemistry,* which presents the law of conservation of mass.
1791	Prevost publishes a theory of heat and radiation exchange. Richter founds stoichiometry.
1798	Thompson demonstrates the conversion of work into heat, in his *Enquiry Concerning the Source of Heat which is Excited by Friction.*
1799	Davy's experiments seriously challenge phlogiston theory.
1800	Herschel explores the heating ability of different frequencies of light.
1802	Lussac establishes the thermal expansion of gases.
1803	Dalton forms his atomic theory of matter, setting the stage for atomic chemistry.
1804	Leslie shows that light and radiated heat have similar properties.
1806	Young formulates a precursor to the modern kinetic energy.
1811	Poisson develops a mathematical theory of heat, based on Fourier's work. Avogadro presents his law. Berzelius states that electrical and chemical

forces are the same and that atoms are electrically charged.

1819 Dulong and Petit show an empirical law on the specific heat of solids.

1824 Carnot studies the thermal efficiency of machines, introduces reversible transformations, and generates the foundations of thermodynamics in his "Reflections on the Motive Power of Fire".

1829 Coriolis defines "kinetic energy".

1834 Clapeyron presents the first version of the second law of thermodynamics, based on steam engine studies.

1837 von Suerman experimentally verifies Clapeyron's version of Carnot's equations.

1842 Mayer equates the conservation of energy law and shows the equivalence between heat and mechanical energy.

1843 Waterston anonymously publishes an accurate kinetic theory of gases. It is essentially ignored.

1845 Waterston submits a beautiful paper on the kinetic theory of gases to the Royal Society. It is rejected and ignored for more than 40 years, until finally resurrected by the President of the Royal Society.

1847 Helmholtz generalizes the conservation of energy law for mechanical, caloric, electric and magnetic energy.

1848 Lord Kelvin introduces the absolute temperature scale. Joule finishes establishing the exact relation between heat and mechanical work; his work is almost ignored.

1850 Clausius states the second law of thermodynamics.

1851 Thomson derives the second law of thermodynamics based on Carnot's work.

1855 Rankine publishes *Outlines of the Science of Energetics.*

1857 Clausius establishes heat as energy distributed among particles.

1858 Clausius introduces the idea of the mean free path of a colliding particle.

1859	Kirchhoff establishes the thermodynamic foundation of radiation theory, and completes the basic radiation theory in 1862.
1860	Maxwell provides studies in kinetic theory of gases and gives the distribution of molecular velocities. The paper, "Illustrations of the Dynamical Theory of Gases," was read in 1859.
1860	Maxwell shows a discrepancy between experiment and the kinetic theory of diatomic gases. It was not resolved until the early stages of quantum theory.
1861	Kirchhoff advances the notion of the blackbody.
1865	Clausius, Rankine and Kelvin provide the concept and definition of entropy.
1860-1877	Boltzmann and Gibbs provide the foundations of statistical classical mechanics.
1867	Maxwell publishes *On the Dynamical Theory of Gases,* his major work on the kinetic theory.
1874	Thomson points out the reversibility paradox.
1877	Boltzmann defines entropy in terms of probabilities.
1873-1878	Gibbs publishes several important papers on thermodynamics, widely influencing scientists.
1879	Boltzmann establishes the relation between radiation intensity per unit area of a blackbody, and the absolute temperature. Stephan formulates the "Stephan-Boltzmann law" $R_T = \sigma T^4$.
1879-1899	Discoveries of various laws and effects, particularly at the micro level.
1900	Planck proposes the quantum of action and derives the correct radiation spectrum for blackbodies. (He published the definitive paper in 1911).
1905	von Smoluchowski and Einstein independently investigate Brownian motion. Einstein publishes a paper on the photoelectric effect.
1906	Nernst advances his heat theorem, where at absolute zero temperature both heat capacity and entropy change go to zero. This is later recognized as the "third law of thermodynamics".
1909	Einstein corrects Planck's blackbody derivation.

1910 Perrin experimentally validates Einstein's calculations on Brownian motion, providing a strong argument for the existence of atoms.
1911 Rutherford proposes the nuclear model of the atom. Sackur points out the need for an absolute definition of entropy. Nernst's experiments provide strong support for the new quantum theories.
1925 Born, Heisenberg and Jordan formulate quantum mechanics from matrix algebra. Einstein points out that the analogy between quantum gases and molecular gases is complete; photons and molecules have both wave and particle characteristics.

Figure A-l. Key Events in the History of Thermodynamics up to the Development of Quantum Mechanics.

During the early period of science, a continuing struggle between various notions of esoteric fluids and fluid flow occurred. French scientist Lavoisier (1743-1794), regarded as the father of chemistry, is identified with the concept of heat as an invisible fluid, which he named "caloric". The notion was that one drove this invisible fluid — this caloric — out of a material by some action such as mechanical friction or combustion. This produced the "manifestations" of what was loosely called "heat". In short, caloric was considered to be "heat" which was itself an esoteric fluid. In his famous Treatise {716}, published posthumously, atoms were still in dispute. However, Lavoisier listed the known elements, and included light and heat as elements. Asimov pointed out {717} that Lavoisier had "... era*dicated one imponderable fluid, phlogiston, but it was only partly through his influence that caloric, just as false, remained in existence in the minds of chemists for a half a century.* "

Caloric dogmatically existed in the minds of scientists deeply into the nineteenth century, until Maxwell and Boltzmann produced theories that strongly supported the concept of atoms as the building blocks of matter. In the late 1790's, Count Rumford (Benjamin Thomson) showed that the supplay of heat that could be "driven from matter" was unlimited, which totally contradicted the caloric theory {718}. Yet the notion of caloric persisted until Maxwell's theory eventually killed it, once application of that theory showed that heat was comprised of EM energy.

The fundamental ansatz of thermodynamics was formed and solidified before the advent of modern physics, and even before Maxwell's theory of electrodynamics, and before heat was known to be electromagnetic energy. It has unjustifiably retained an aura of "absoluteness" and dogma, even though its foundations concepts are based on outdated notions already scientifically falsified as far as any absoluteness is concerned. As Mallove states {719}:

> *"It is astonishing to realize that many modern conceptions (or laws') in the science of heat— thermodynamics — arose during the nineteenth century, a period of utter confusion about the fundamental nature of heat. How could it have been otherwise, given that the very existence of atoms was still in question! One sees the shakiness of the claim that the laws of thermodynamics had reached a state of 'near perfection' in the twentieth century ...when they in fact rested on this very flawed foundation. "*

During that formative period, the notion of the conservation of energy **was** also being searched for, as if in a thicket of brambles. For some time, any notion of energy conservation was seen as directly contradicted by caloric, and — in formulating the heretical notion that energy is conserved — pioneers such as Mayer {720} were severely castigated.

In 1850 Clausius resolved the conflict between caloric and conservation of energy in a seminal paper {721}.

Mallove {722} explains how the theory developed from there:

> *"In one fell swoop Clausius 'scooped' Kelvin and cast into precise form both the First and Second Laws of Thermodynamics — energy conservation, and the limit of the Carnot efficiency."*

Clausius' statement of the Second Law is: *"It is impossible for a self-acting machine, unaided by an external agency, to convey heat from one body to another at a higher temperature. "*

In 1851, Thomson (Lord Kelvin) stated the Second Law as:

> *"It is impossible, by means of inanimate material agency, to derive mechanical effect from any portion of matter by cooling it below the temperature of the coldest of the surrounding objects."*

In 1865 — the same year that Maxwell published his seminal paper in his electrodynamics {723} — Clausius derived entropy and showed the two laws of thermodynamics expressed in the same way as the old caloric theory. Clausius used the concept of "entropy" to represent the *"dissipated potential".* In a public speech with the title "The Entropy of the Universe Tends to a Maximum," Clausius included how thermodynamics requires an eventual heat death for the universe. His view was that

> *"The energy of the universe remains constant (first law), while entropy increases. "* {724}

We stress that the notion of the flow of EM energy through space did not originate until the 1880s, when Heaviside and Poynting formulated it independently. Neither relativity — with its notion of a combined spacetime - nor the Minkowski space had been born. Neither had quantum mechanics, quantum electrodynamics, quantum field theory, etc.

For a succinct and very useful listing of the major developments in the history of thermodynamics and statistical mechanics, one is referred to the work of Biggus {725}.

A.1.2 Inadequate Fundamental Definitions in Thermodynamics

In the view we take in this book, energy is the all-important concept, in all its forms, no matter how esoteric. The interactions of energy with matter must therefore be extended to include all known energy interactions, not just those prescribed by CTD or CED. Consequently, two fundamental definitions of thermodynamics are faulted by the supersystem concept.

First, thermodynamics defines an *open system* as one that is open to the exchange of energy and mass across its boundary. No concept or discussion of virtual energy, virtual mass, time-energy, or multiply connected space effects is included. Further, mass is actually a special form of energy, and hence this definition only prescribes the exchange of energy across the system boundary.

Second, thermodynamics defines a *closed system* as a system with no mass exchange across its boundaries, but heat (energy) exchange is permitted. This definition has been a non sequitur since general relativity was established in 1915, and also since caloric (heat) was identified as energy rather than a thin material fluid that was forced or beaten out of matter by doing work on the matter. Since then, energy and mass are also known to be the same thing, as established by general relativity. Whenever the energy of a system changes, its mass changes a priori. So a system thought of as "closed to any mass transfer across its boundaries" still undergoes mass change due to the exchange of energy across its boundary. Further, the definitions of "closed system" and "open system" are not mutually exclusive. As an example, a system exchanging energy but not mass across its boundary can be classified as a "closed system", and also as an "open system" where normal exchange of mass is blocked but the mass of the system still changes as the systems absorbs and emits energy.

Rigorously, even the energy of a system cannot individually change in 3-space, without first invoking 4-space change! Instead, the "energy x time" — the action — of the system is what moves and changes in 4-space, Observation applies a *d/dt* operator, resulting in a 3-space energy observed as having already happened or been fixed.

The modern view of gravitation is that the energy in mass generates the gravitational field, not the mass per se {726}. Also, mass is an observable, hence it is a continuously recurring 3-spatial snapshot that does not even continuously exist as mass, but alternately as mass and masstime. The assumption of the continuous existence in mass is falsified by the quantum mechanical nature of observation itself; hence all three models — CTD, CEM, and EE — are falsified.

Nonetheless, let us continue to use the conventional notion of "flow of energy" and "flow of mass" for convenience.

The thermodynamic definition of "open system" ignores the state in which mass exists as "masstime". No "change of mass", flow of mass, etc. occurs. Instead, masstime can flow or change, but mass is an observable and **thus** frozen 3-space snapshot at one instant. Time is "outside" any 3-space material system, hence when mass becomes masstime, it already "exchanges across the system boundary". *For a mass merely to continue to exist requires the exchange ofmass across the 3-space system boundary.* Indeed, only "masstime" can be changing, so in failing to consider masstime, the definition is falsified as it stands, in its very assumption of "continuous change of mass" when there is no such thing in all of nature. As stated, a similar consideration applies to energy, which does not **and** cannot "continuously exist in 3-space" at **all,** and cannot *continuously* change. Also, *time is highly concentrated energy* as we develop in this book, and time certainly "exchanges across the boundary" of any mass system. Time may be taken as a sort of "multiple connection" in space, since in theory each point in space is said to "exist simultaneously" in the same time-point.

With quantum potential connection, external energetic processes may be "superposed instantly in multiply-connected space" with one or more points of the "closed system". Hence, if there exist processes in the system to transduce time-energy into 3-spatial energy — as in the well-proven cold fusion experiments — matter changes including nuclear transmutations can and do occur. Then the "system closed against mass motional exchange through 3-space" (which does not even concretely exist) is not closed against mass changes at all.

To eliminate the mass-change effects of energy transfer across the system boundary, the present thermodynamic definition of a *closed system* must be completely recast into what thermodynamics presently calls an *isolated system* - one in which neither energy nor mass is exchanged across the system boundary. No such system exists in the universe, since merely to exist it has to be open to continual energy exchange between time and 3-space domains, mass has to continually interchange between mass and masstime, and energy has to continually interchange between energy and (energy x time). The blunt truth is that *only open systems exist in nature.*

All systems are open systems in their supersystem interactions, and they can and do exchange time-energy and mass changes due to spacetime curvatures and active vacuum changes. Any local spacetime curvature made by an energy change in a system or nearby, also reacts back upon the system from its local curved spacetime environment. It may react in a totally energetic fashion, or it may react to produce mass in the system (as in pair production). In the book we pointed out that the supersystem components external to the system can also interact in the system to eliminate mass (as when a Dirac hole combines nonradiatively with a Dirac **election).**

Finally, the notion of an "open system" as one in which energy and mass both can be exchanged across the system boundary must be extended to include a system which can also exchange time-energy, spacetime curvature energy, virtual particle flux activity and energy, and other supersystem effects across the boundary. Further, the notion that a "closed system"can be open to energy exchange but not mass is totally falsified in modern physics' virtual particle exchange between environment and system. Virtual mass — which is physically real — is continually exchanged across the system boundary. Though each virtual mass particle is individually unobservable, coherent summations are observable.

To properly evaluate the conventional thermodynamic definitions of open system, closed system, and isolated system, simply select and use a physics model containing only one fundamental unit, the joule. Now all basic entities are made of energy and functions of energy. So all basic entities are forms of energy; e.g., both mass and time are special forms of energy. As presented previously in this book, to even "exist in time" a system is continually exchanging and transducing 3-space energy and time energy, across its boundary at an enormous rate. Every system is an open system, a priori, and the thermodynamic "closed system" is a non sequitur. The thermodynamic "isolated system" is revealed as the early attempts to deal with observation; i.e., the observed system as a series of frozen 3-space snapshots (effects), each stripped from a 4-space ongoing process at a single moment by the observation process *d/dt* (LLLT) = LLL. Each snapshot is an isolated system (which is what observation produces). Now we understand that this "isolated system" existed only at a single frozen instant, continually recurring, and never existed continuously in time at all,

So in view of today's physics, the old thermodynamic "isolated system" concept is an early attempt to deal with observation of the system without input or input (without dynamics, hence frozen). "Closed system" is a non sequitur since mass is energy and energy is continuously exchanged across the system 3-boundary in several forms. Both virtual mass and virtual energy are continuously exchanged across the system boundary. It follows that the only type of system existing continuously in nature is the *open system*. The other two "types of thermodynamic systems" are at best only approximations for special cases.

Under modern physics and the new definitions, we conclude that there is no such thing as a truly closed or isolated system continuously existing in the universe. Hence that very definition disappears, *as far as any absoluteness*. It is retained only as a *useful approximation in special cases*, when the more esoteric mass effects and energy effects are intentionally omitted or negligible, and only classical effects are of importance. Any scientist dogmatically objecting to COP>1.0 EM systems on thermodynamics grounds alone, simply reveals his lack of knowledge (or lack of acceptance) of modern physics.

This is similar to the situation existing between Newtonian mechanics and relativistic mechanics. We can still use the Newtonian model for many practical matters, since the relativistic effects are often small and nearly inconsequential. Similarly, the present CTD concept of "closed system" now assumes that kind of relationship to *one class* of open systems in which the more esoteric reactions are negligible or inconsequential. But rigorously, all systems are now open systems, removing a gross non sequitur in CTD which is especially violated by COP>1.0 EM systems including every charge in the universe.

This is a correction to both equilibrium (classical) thermodynamics and disequilibrium thermodynamics. Unfortunately the two disciplines have continued to use the same (old) definitions for closed system and open system. Hence both equilibrium and disequilibrium thermodynamics at present are useful approximations, and their "laws" must not be misinterpreted as "absolute". Thermodynamics remains a very useful model, but further development is also indicated. Indeed, presently such scientific development and extension of the thermodynamic model is being done under the heading of "extended thermodynamics".

A.2 Comments on Problems with Thermodynamics

Quoting, from Kondepudi and Prigogine {727}:

> *"Every system is associated with an energy and an entropy. When matter undergoes transformation from one state to another, the total energy remains unchanged or is conserved; the total entropy, however, can only increase or, in idealized cases, remain unchanged. "*

The absoluteness of that statement is falsified by the solution {12} of the long-vexing problem in CED of a source charge and its associated fields and potentials. The observable charge is a charged mass and thus a Maxwellian system. It is also a thermodynamic system, meeting the present erroneous definition of a "closed system" utilized in both equilibrium and disequilibrium thermodynamics. No observable mass crossed the system boundary, although virtual mass continually crosses it.

The charge is "fed" by a more esoteric energy input in disordered form (the virtual particle flux energy of vacuum), yet it outputs ordered observable EM energy spreading radially outward at the speed of light across the universe. The charge increases and sustains the organized energy density of a volume of space depending on the radius *ct,* where *t* is the time since the formation of the charge and *c* is the speed of light in empty space. This continous outflow of observable energy is a continuous and giant negentropy, exhibited by every source charge and dipole. When positive charge, negative charge, polarization of space, and both positive and negative energy are considered, what is spreading is precisely a reordering of the active vacuum — in short, a giant and increasing negentropy. Since the universe is filled with charges, this is a natural process continuously ongoing everywhere in the universe.

Re-quoting Serway(697}:

> *\The second law [of thermodynamics] does not rule out the possibility of pushing heat uphill, as it were, from a cold object to a hot one, or of creating order out of disorder. It merely states that such a reversal of the natural flow requires an influx of energy... "*

Our comment is that any mechanism by which the system receives extra usable energy in forward time, or is time-reversed, enables the system to permissibly violate any narrow interpretation of the second law of thermodynamics. The second law was formulated in accord with forward time assumed, and with the old definition of "closed system", which erroneously permitted energy exchange but ignored the mass effects of energy exchange. Therefore, the second law is a special case for equilibrium in its energy exchange with its active environment, but effectively allowing its own negation anyway, and it always has. In the new approach with altered definitions, all EM systems are open systems, and they may also be brought into disequilibrium (in excited states or potentialized condition). Thus in theory all systems are permitted to violate the second law, *particularly when broken symmetries in their supersystems are involved.* This is especially true of EM systems, where all the EM field energy and potential energy in the system— even in the matter itself— comes from the active vacuum environment (particle physics view) by means of the broken 3-symmetry of the source charges and dipoles. The condition of 4-symmetry in energy flow exchange together with broken 3-symmetry and t-flow symmetry, is a disequilibrium condition and an excited state. Every charge and dipole already exhibits this state and the giant negentropy condition.

To first order, then, one may say that the present second law assumes no broken 3-symmetry or broken t-flow symmetry in energy flow, while violation of the second law assumes broken 3-symmetry and broken t-flow symmetry.

Quoting Serway {728}:

> *"Thermal equilibrium is a situation in which two objects in thermal contact with each other cease to have any net energy exchange due to a difference in their temperatures."*

Our comment is that net energy exchange — to include time-energy exchange and negative energy emission, absorption, and transduction are not modeled in thermodynamics and are arbitrarily excluded in **the** quoted statement. Since both are exhibited experimentally, the statement is falsified as far as being absolute. Instead, it is a special case and a useful approximation when some of the esoteric energy considerations are negligible.

Quoting Serway again {729} on the zeroth law of thermodynamics:

> *"If objects A and B are separately in thermal equilibrium with a third object, then A and B are in thermal equilibrium with each other. "*

A corollary is stated by Serway {730} as:

> *"...two objects in thermodynamic equilibrium with each other are at the same temperature. "*

Our comment is that these statements are true if the time-energy exchange is identical among all three. Otherwise, they are not necessarily true. It is not generally true, e.g., for a system in an accelerated frame. Also, the zeroth law is not necessarily true if negative energy (and/or its transduction is involved with one or more of the objects.

An example: A and B are at the same temperature as C, as measured by a thermometer. But A is also emitting negative energy, which is being absorbed by B, to maintain A and B at the temperature of C. A and B are not in real thermal equilibrium in their supersystem interactions, even though they are at the same macroscopic temperature. A second example: A is emitting negative energy to maintain its temperature, while B and C are not. The supersystem of A is not in real thermal equilibrium with the supersystem of either B or C, even though the observed temperatures of A, B and C are the same.

Quoting {731} on what is meant by the term "heat":

> *"...heat is treated as another form of energy that can be transformed into mechanical energy. " ... "The word heat should be used only when describing energy transferred from one place to another. That is, heat flow is an energy transfer that takes place as a consequence of temperature difference only."*

Quoting Lindsay and Margenau {732}:

> *"A complete statement of the first law comprises two* ***assertions:*** *(a) heat is a form of energy, (b) Energy is* ***conserved."***

The statement in (a) that heat is simply a form of energy is misleading, and the statement in (b) that energy is conserved must be expanded to include total energy, not just heat and the presently accounted forms of energy. Specifically virtual particle energy, time-energy, and energy from the curvature of spacetime must be included.

More correctly, heating is a form *of energy disordering* or energy scattering. As previously pointed out, entropy itself was and is conceived as *the dissipation (irretrievable loss) of potential energy.* Heat thus would be the process of energy disordering, which means that heat is a form of the process of entropy (loss of control of the energy). Note the strong non sequitur with the notion that heat is energy. *Heat cannot logically be both energy and the dissipation of energy.* The concept of energy (its mere presence) is not identical to the concept of scattering of energy or transfer of energy, but the concept of heat is identical to it. The thing is not identical to something done to the thing or to transfer of the thing to another place. A form of scattering of order is not a form of ordering. Transfer of heat is a transfer of disordering of energy, not the transfer of energy per se. Hence, considering heat as simply "heat energy" is a fundamental non sequitur of classical thermodynamics, and remains so to the present day and in the present textbooks. For an example of strong support of this position, see Romer {733}. Quoting {734}:

> *"The work done on (or by) a system is a measure of energy transfer between the system and its surroundings, whereas the mechanical energy (kinetic or potential) is a consequence of the motion and coordinates of the system. Thus, when you do work on a system, energy is transferred from you to the system. ... one can refer only to the work done on or by a system when some process has occurred in which the system has changed in some way."*

Our comment: Consider a system which "ping-pongs" the energy it receives from the environment, between two parts of itself. In each part, the form of the energy is changed by that interacting part and that does work upon the part. But the new form of energy remaining after the work was done in that component is not lost but is ping-ponged to the other component, where it does work upon that component, and so on. In this case, each joule of energy input from the environment does more than a single joule of work, with the work performed being limited only by the ability of the system to sustain and contain the "ping-ponging". There is work but no entropy if the energy doing the work (changing its form) is not lost from system control!

There is no law of "work conservation" in nature, and a joule of input energy can do more than one joule of work (as in this example) if repetitive changes of its form are considered. Thermodynamics arbitrarily excludes such cases, and hence is incomplete. Again, the conventional perception of the absoluteness of thermodynamics is falsified. It models a special case where the energy can be "used" to do work only once, and then all control of the new form of the energy (it is all still there, just in a different form) is lost.

For a particular substance, the heat capacity C is usually defined as *the amount of heat energy needed to raise the temperature of the sample being tested by one degree Celsius.* This definition assumes only one "use" of the *energy to* perform work in the substance, and completely ignores "multipass,multi-use" of the energy to perform more than one joule of work from one joule of input energy. As an example, if an equal amount of positive and negative energy is steadily input, then no amount of the positive heat energy input component would raise the temperature at all. The modern active vacuum, with a local energy density in the region of 10^{80} or more grams per cubic centimeter (expressed in mass units), nevertheless is harmless to living systems immersed in it. It has equal positive and negative energy densities, and so normally inputs the same enormous amount of positive and negative energy in its overall interactions with a living system.

The first law of thermodynamics is usually written as

$$\Delta U = U_f - U_i = Q - W. \qquad [1]$$

This is a highly special case, which does not include time energy transduction (spatial energy transduced into time energy and vice versa), or energy transduced from the active vacuum via the broken symmetry of an electrical system in continuous exchange. The definitions of work and heat have to be changed and drastically extended.

As an example of a legitimate exception, when time-energy T_E is transduced into available spatial energy inside the system, we have

$$\Delta U = U_f - U_i = Q + T_E - (W_D + W_L) \qquad [2]$$

where W_D is the energy that was dissipated in the system losses without doing useful work and W_L is the energy leaving the system but doing useful work in a load L. $(Q + T_E)$ represents the total net energy entering the system, while $(W_D + W_L)$ is the total energy leaving the system, either as losses or to do useful work in the load. Here we are also incorporating virtual energy under the title of time-energy, since both time and virtual energy are unobservable, and virtual energy "exists in time".

Now suppose Q entering the system, and collected for use in it, is freely furnished from the active vacuum via the broken symmetry of the electrical system's dipolarity. Suppose T_E is spatial energy freely transduced from the time domain by ongoing processes in the system, and thus T_E also enters the system freely. Then suppose that the system processes are deliberately adjusted by the operator so that

$$(Q + T_E) = (W_D + W_L) \qquad [3]$$

In that case,

$$\Delta U = U_f - U_i = 0 \qquad [4]$$

yet continuous loss energy WD is escaping from the working system, useful work W_L is continuously being done in the load, and useful energy $(Q + T_E)$ is continuously entering the system from the active environment (the active vacuum and the local curvatures of spacetime). This system is totally permissible in nature (and is already operating in every charge and dipole in the universe). It is an example of an open system far from equilibrium in *3-space* energy flow, but in equilibrium in *4-space* energy flow. Yet it is artificially excluded by classical thermodynamics.

Classical thermodynamics thus excludes every charge and dipole in the universe, and therefore is an extraordinarily curtailed model. It is a special case approximation having no absolute authority as a proper limiting model of EM systems.

The first law of thermodynamics for infinitesimal changes may be stated as

$$dU = dQ - dW \qquad [5]$$

Following the previous reasoning, for involvement of time-energy transduction (with virtual energy included) we have

$$dU = dQ + dT_E - (dW_D + dW_L) \qquad [6]$$

If dQ and dT_E are freely received in the system from the active vacuum and local curvatures of spacetime respectively, and if

$$dQ + dT_E = dW_D + dW_L \qquad [7]$$

then

$$dU = 0 \qquad [8]$$

So with no change in its internal energy at all, the microsystem or microprocess is receiving excess energy continuously, and also is continuously emitting energy that is doing useful work with some losses. The system is in fact in *energy 4-flow* equilibrium, and doing useful work, without the operator inputting any of the energy.

So the *corrected* standard statement of the first law allows an equilibrium system to steadily produce output work W, if its "energy input Q" is freely received. The first law of thermodynamics, properly extended and reinterpreted, does indeed admit "electrical windmills" operating in free electrical winds.

Now turning to the second law. In effect, the second law prescribes those processed in nature — more exactly, in the prescription of the first law — that may or may not occur. It is a law of limitation. It states that, of all the energy conversion processes permitted by the first law, only certain types of energy conversions can take place. A priori, the validity of its prescription depends totally on the nature of the functions involved in the system considered! However, since we dramatically extended the first law, using neww processes experimentally determined to take place, then we have automatically extended and changed the second law because we used experimentally *proven* functions. The old second law is now revealed as a special case, with no absolute limitations. The perception that it prescribes absolute limitations has been falsified. It is still useful, however, but to be careful one must completely re-examine (and possibly rework) the second law whenever the energy functions of a system are changed. We strongly stress that *the second law is a conditional law, and its application is totally dependent upon the system energy functions behaving in the limited manner assumed by the second law. Whenever the energy functions of the system are changed outside those assumed by the second law, the second law is permissibly invalidated for that system.* In short, in that case the second Iaw is simply a totally inadequate model for that system, and cannot be used as any sort of criterion for stating the "permissibility" or "impossibility" of that system. As an analogy, a model specifying scalars only cannot be applied to a vectorial system as a decisive logical criterion orrestriction.

QuotingSeray{735}:

> *"From an engineering viewpoint, perhaps the most important application [of the second law] is the limited efficiency of heat engines. Simply stated, the second law states that a machine capable of continuously converting*

> *thermal energy completely into other forms of energy cannot be constructed."*

Our comment is that, if we believe that energy is conserved in the entire universe, then the universe itself already violates Serway's statement. If we consider the seething virtual particle flux energy of the active vacuum as a special form of thermal energy, then every charge and dipole in the universe already is a heat engine that falsifies the second law of thermodynamics. The charge and dipole continuously absorb this special form of thermal (virtual flux) photon energy, and also continuously convert it into real, observable photon emission in 3-space. This is negentropy on a giant scale, already demonstrated by every charge and dipole and thus experimentally falsifying the present second law.

Classical thermodynamics also assumes irreversibility. While many of the physics models and equations prescribe reversible reactions, thermodynamics takes the view that events occur with a much greater probability in one direction in time than in the other. This of course is usually borne out in our perception of the gross observable universe around us. However, charge conservation alone requires equal amounts o| charge and time-reversed charge. With the nearly ubiquitous time-reversed charge and charge conservation, it follows that some factor not accounted for in thermodynamics is operating in the universe. And so it is, but it is a general relativistic factor. We shall use a biological example of the cellular healing mechanism we discovered in the living body {736}, extending Becker's work and Priore's work.

Normally most processes do not involve deliberate net transduction of time-energy into spatial energy, nor do we model and account for the specific set of ongoing interactions between every part of the system **and** its concomitant set of spacetime curvatures acting back upon it. Call that set of spacetime curvatures the *resident spacetime curvature engine* ***and its*** *dynamics,* or just *its engine* for short. The engine is comprised of structured energy and energetics, and it is already experimentally demonstrated in nonlinear phase conjugate optics that energy can be **time** reversed. The engine's spacetime curvatures act directly upon the **mass-**energy dynamics of the system. Time-reversing the system's operation is a matter of producing a sufficiently amplified, phase conjugated engine to act in reverse upon the physical system and overpower its resident **engine.** In that case, the thermodynamic system and its functioning can be **made to** run backward.

In fact this is the fundamental mechanism used by the body's own cellular regenerative system to heal its damaged cells. To a limited degree, the body is able to "pump" its cells in the time-domain (with time-energy), thus producing an amplified "phase conjugate energy and engine dynamics".

Pumping a living cell with time-energy is interesting. The resident engine serves as the "signal input wave" in conventional nonlinear phase conjugate optics, and the output time-reversed engine (the amplified anti-*engine*) serves as the "phase conjugate replica wave". A sufficiently simplified anti-engine acts upon the cell and all its tiniest parts, time-reversing all energetic operations in exact phase, proportion, and timing. This is the mechanism for thermodynamic reversibility. It is also the "secret" to eventually reversing aging.

This action is upon all the energetics of the cell and its parts, including the mass-energy and mass-energetics as well.

The result of the action of the anti-engine is to slowly time-reverse the damaged cell and all its parts back to a previous state and dynamics. Electromagnetic amplification of the process was unwittingly demonstrated by Priore {737} and by Becker {738}. We refer the reader to our website {739} and to our "porthole briefing" for pertinent technical information, and for a most important extension and great simplification of the Priore/Becker approach and methodology.

Present classical thermodynamics does not consider or model the reaction of local spacetime curvatures and their dynamics upon the system. Hence all time-domain pumping that occurs is occurring rather randomly in each and every microscopic part of the system. In short, there is no organized anti-engine, and an organized anti-engine is what is required for time-reversing the system's operations back to a previous state. However, by mimicking, the body and pumping the physical process in the time-domain, with sufficient pumping a precise, amplified anti-engine will be formed and act upon the system — *any* system. The applicability is limited only by the state of development of the appropriate time-pumping technology.

In theory (and as experimentally demonstrated unwittingly by Priore and by Becker), this anti-engine can and does overpower the resident engine. It can in fact time-reverse the pumped physical processes in the system itself.

So the classical thermodynamics assumption of irreversibility for heat engine energy processes is not absolute but only provisional. Specifically, it assumes no overall time-domain pumping process that provides a precise anti-engine and time reversal of the system energetic process of concern and its dynamics.

If the second law is extended to encompass and model the new concepts such as broken symmetry and time-energy, then the extended second law will encompass reversible heat engine processes, Maxwell's demons, COP>1.0 electrical systems, COP » 1.0 electrical systems (electrical windmills), time-reversal of the dynamics, reversibility of that which has been irreversible, etc.

As given by Kondepudi and Prigogine, the third law of thermodynamics essentially states {740} that

> "... *at the absolute zero of temperature the entropy of every chemically homogeneous solid or liquid body has a zero value."*

This is also known as Nernst's heat theorem, after W. Nernst who proposed it in 1906. The third law states that

$$S \rightarrow 0 \text{ as } T \rightarrow 0 \qquad [9]$$

Certain violations of the third law are already known. E.g., C=O: carbon monoxide molecules can align in various ways in a crystal, so there is entropy associated with C=O crystals at 0°K. In this case, A and B are equally probable and the following equation can be used to calculate the entropy (called residual energy):

$$S = nR\,[1/2\ln(1/2) + 1/2\ln(1/2)] = -nR\ln 2 \qquad [10]$$

From the new viewpoint, the definition of T = 0° is open to change. Rigorously, the present third law assumes no local broken 3-symmetry of the vacuum's flux exchange with the system, and it also assumes no broken time-energy flow symmetry. In the new approach, both these symmetries can and are broken by every charge while a higher 4-symmetry is maintained. This leads to a giant negentropy, so that the "calculation of entropy" via Nernst's theorem fails. A fundamental charge at T = 0° thus continues to exhibit giant negentropy, in total violation of the third law of classical thermodynamics. Hence the third law is also devoid of any absoluteness, and it is reduced to a special case statement. It remains useful where the more esoteric energy interactions are negligible.

We have now demonstrated (by citing actual substantiating experiments) that all the laws of CTD are falsifiable insofar as being absolute. Hence they have *no* absoluteness. Instead, they are special case models and "approximation laws" only. They remain very useful and applicable, However, so long as the more esoteric energy interactions of the supersystem do not play a major role in the system operation.

We conclude that the present form of classical thermodynamics and disequilibrium thermodynamics are special case models — as indeed is every model, by Godel's theorem and proof alone — with no absoluteness. They do not prohibit COP>1.0 EM systems, nor can they necessarily be used to rule out COP>1.0 EM systems.

This also falsifies all current arguments that COP>1.0 EM systems violate either the first, second, or third law of classical thermodynamics. Calling COP>1.0 systems "perpetual motion machines of the first, second, and third kind", according to which law they supposedly violate, is a total non sequitur. Indeed, every original charge in the universe has already demonstrated just such "perpetual motion" for some 14 or so billion years, and happily violates all three laws of the present CTD. Every charge is in violation of the "laws" of the present models of CTD, CED, and EE, and it is still in motion and still freely pouring out EM energy. We have no abillity to examine the notion of "perpetual" past the entire past existence of the universe.

All three models examined — CTD, CED, and EE — are seriously out of date and in need of revision and extension, because any absoluteness of their predictions and assumptions is already falsified by actual experiments and examples. Some work is already ongoing to extend thermodynamics, but is not nearly extensive enough. A thorough overhaul of the very foundations is what is needed for all three models. The three models remain useful as special case approximations, but their received use to arbitrarily rule out COP>1.0 EM systems is dogma, not science because such use is already experimentally refuted by every charge in the universe.

Appendix B

Maxwell's Demon: Alive and Thriving

Introduction

ITHERE is a long history of discussion over "Maxwell's demon", a fictitious being that Maxwell proposed to "sort" molecules striking a barrier between two volumes of gas initially at the same temperature. By intentionally opening a trap door between two for hotter, more energetic molecules to pass through from the left side to the right side, but shutting the door for lower lemperature molecules so that they are retained on the left side, eventually a temperature gradient would "freely" exist between the two reservoirs. In theory, then, if one had the demon working "for free", one would be able to utilize the temperature difference between the reservoirs to perform free work. Then one could repeat the demon's sorting procedure, to obtain more free work again. And so on.

The prevailing discussions have ignored the main feature: the fact that the demon is part of the "external environment" (i.e., not under control of the system, and operating independently of any energy input by the operator). Maxwell's demon represents an analogy to the system's environment furnishing free energy (free ordering and sorting). A lot of breath and mental gyrations have gone into the discussions over the years, with very little concrete experimental examination. The prevailing concept in science, which still adheres to the "absoluteness" of the second law of thermodynamics, is that Maxwell's demon is impossible.

Recently, the former editor of *Nature,* Dr. John Maddox, wrote a very clear emeritus editorial on Maxwell's famous demon, repeating the standard conclusion that such is not possible. Since there are specific examples in physics of what can be called "experimentally proven Maxwell's demons," the present author prepared a respectful commentary to *Nature* to refute the standard erroneous thesis in the interest of science. since experiment is supposed to be decisive in physics, we hoped that citing overwhelming experimental proof would be sufficient. It wasn't.

Almost symbolically (i.e., "free the demon!"), I submitted the commentary to the editor by I -mail on the evening of July 4, 2002. The very next day I received rejection (not too unexpected) by E-mail with no further discussion accepted. So I wrote a polite note in response, and then posted my commentary note on my website.

In this appendix, I include my E-mails of both 4 July and 5 July 2002, and then include the commentary that was submitted. The reader can read the cited emeritus editorial in *Nature,* and then decide for himself or herself whether experiment still rules the day at *Nature* where COP>1.0 and COP = co EM systems are concerned.

E-mail to *Nature* 4 July 2002, submitting the Commentary.

Dear Editor:

Attached is a significant commentary on John Maddox's excellent emeritus editorial on Maxwell's demon, titled "Slamming the Door," *Nature,* 417, 27 Jun. 02, p. 903.

Forms of Maxwell's demon are very much alive and thriving, and experimentally confirmed, as we develop very clearly in this commentary. They are unwittingly used widely in electrodynamics, though seldom recognized.

Most sincerely,
Tom Bearden, Ph.D., Magnetic Energy Ltd.

E-mail to *Nature* 5 July 2002, submitting a comment on the rejection.

Dear Ms XXX:

Thanks for the prompt reply.

Since *Nature* will not be publishing the note, I have now posted it on my website (some 80,000 hits per day from all over the world). It can be **seen** at http://www.cheniere.org/articles/maxwells%20demon.htm

This is a respectful article, and I just thought the experimental information needed getting out there to the scientific community. I also understand you cannot discuss it further. I only wish to note that it is based on cited replicable experiments, which are supposed to be the decisive thing in science and scientific method. It seems a bit odd that you would not publish the results of several replicable and replicated experiments **that** falsify a prevailing theoretical thesis and conclusion. Nonetheless, I respect the wishes of *Nature,* and I do enjoy the Journal each week.

Best wishes,
Tom Bearden, Ph.D.

Within days of this rejection, the paper by Wang et al. {741} was published, extending the known physics "Maxwell's demon" regime (i.e., where the second law of thermodynamics is known to be violated) from the atomic scale and very short periods of time, to the micron scale in size and time up to a few tenths of a second.
Here is the rejected commentary I submitted to *Nature.*

Maxwell-type demons are alive and thriving

The recent emeritus editorial by Maddox on Maxwell's demon [742] is a short overview of one historical aspect of would-be negentropy, but much greater thought on the subject needs to be given. Indeed, Maxwell's demon is alive and thriving, but just in a different form not requiring a nimble-fingered microscopic being. We now discuss such experimentally proven demons.

Consider the prevailing ansatz that Maxwellian systems outputting more EM energy than the energy input by the operator or experimenter are impossible. Such proposed systems are said to constitute examples of forbidden perpetual motion machines because they violate the second law of classical (equilibrium) thermodynamics. That prevailing ansatz has been falsified in classical electrodynamics since the 1880s, and in particle physics for 45 years, but eerily it is still the prevailing scientific opinion nonetheless.

The ansatz can be experimentally disproved in classical electrodynamics as follows: Lay a charged capacitor or electret on a permanent magnet so the E-field of the capacitor or electret is at right angles to the H-field of the magnet. That optimizes $\mathbf{S} = f(\mathbf{E} \times \mathbf{H})$, and hence optimizes the continuous flow of Poynting EM energy from that simple device, even though the fields, seem to be "static". As Buchwald states [743], *"[Poynting's result] implies that a charged capacitor in a constant magnetic field which is not parallel to the electric field is the seat of energy flows even though all macroscopic phenomena are static. "* [744] This simple device will freely pour EM energy indefinitely, so long as it remains intact.

We consider a special but universal kind of related Maxwell's demon problem: the vexing problem of the source charge, sometimes called "the most difficult problem in classical and quantum electrodynamics." [745] Any charge pours out observable EM energy continuously in all directions, at the speed of light, with no *observable* EM energy input. This continuous flow of EM energy establishes the charge's related fields and potentials and their energy, reaching even across the universe for very old charges. In the classical electrodynamics (CED) model and therefore in electrical engineering, there is no solution to this problem because CED does not model *nonobservahle* EM energy inputs such as the virtual particle flux exchange of the charge with its vacuum environment.

With no solution available in CED, then the present CED and electrical engineering assume that every charge in the universe *freely and continuously creates energy out of nothing,* and pours it out in all directions, forming its associated fields and potentials and their energy. Either we must solve the problem in the classical EM model, or totally surrender the conservation of energy law in the model in its present limited form. Or — as is presently the case — we may continue to ignore it, as has been done during the 45 years since the proof of broken symmetry in particle physics [746].

On the other hand, particle physics models and utilizes virtual energy **in** the seething vacuum, including the interactions of the vacuum with charge, With the 1957 experimental proof of broken symmetry by Wu et al., [746] certified by the award of the Nobel Prize to Lee and Yang later that **same** year, one of the proven broken symmetries in the vacuum virtual energy exchange is the asymmetry of opposite charges, such as are on the ends of a dipole. For a dipole or dipolarity, then by the very definition of broken symmetry *something virtual has become observable.* We diverge for a moment, and then will return to this proven asymmetry of the opposite charges of the dipole.

If we take the modern view of the bare charge clustered by virtual **charges** of opposite sign, then the magnitude of the bare charge in the middle is infinite (including its energy) and so is the magnitude of the charge of the surrounding clustering virtual charges. [747] So for an "isolated **observable** charge" we actually have a sort of "infinitely powerful dipole". Yet **the** difference between these two infinite values of charge is finite; it is routinely calculated as the observed charge of an elementary charged particle, the value that is listed in standard texts and handbooks.
The asymmetry of this "opposite composite charges" model of the "isolated observable charge" now explains the long-vexing source **charge** problem. The observable "composite" charge continuously absorbs **virtual** photon energy from the seething vacuum exchange, transduces it **into** observable photon energy excitation, and this excited state **continuously** decays to emit real observable photons in all directions at the speed of light. When *virtual* energy input as well as *observable* energy output is accounted, the charge's proven asymmetry in the vacuum exchange **makes** the source charge an open system far from equilibrium in its active

environment. As an open disequilibrium system the charge is thermodynamically permitted to (1) self-order (hence coherently integrate absorbed virtual photon energy into observable photon energy), (2) self-oscillate or self-rotate (spin), (3) output more energy than the "operator" **inputs** (the operator inputs none at all), and (4) exhibit negentropy. Every charge in the universe is already doing those four functions. It is also a system having a COP (coefficient of performance, or useful energy output divided by the operator's energy input) of COP = ∞, since the operator inputs nothing.

In short, every charge in the universe already is a special kind of known "Maxwell's demon", whose operational mechanism is long since proven in particle physics but does not appear in classical electrodynamics or electrical engineering. It is a dependable Maxwell's demon, since all charges in the original matter in the universe have been pouring out real EM energy freely, using this asymmetry mechanism, for some 14 billion years, **and** they continue to do so. Further, any charge one assembles in the laboratory instantly starts up its Maxwellian demon performance automatically, and it will continuously pour out EM energy in all directions indefinitely, so long as the charge remains intact. So this demon is easily created and demonstrated experimentally. The Maxwell's demon for freely extracting copious EM energy from the vacuum is one of the easiest entities to invoke in all of physics

This is **not** a violation of thermodynamics, since classical *equilibrium thermodynamics* with its infamous second law does not apply because the charge is far from equilibrium in its exchange with its active vacuum environment. Although the COP = ∞, the *efficiency* of the charge system -defined as the useful energy output divided by the total energy input from all sources — is never more than 100%. Hence this is not a perpetual motion machine, and the charge rigorously does not create energy; it only transduces energy input to it in a novel form. In this case, the charge can permissibly act as if it were a free electrical windmill turning in a novel free electrical wind due to its asymmetry in the vacuum flux.

So every charge in the universe exhibits COP = ∞, clearly proving that Maxwell's demon in an improved form exists and is thriving throughout the universe. There would be no EM fields and potentials and their energy, and hence no electrical circuits or power systems, were it not for this asymmetry of the charge in its virtual energy exchange with the vacuum, making the charge a true Maxwell's demon.

In the usual CED model and electrical engineering, the 1867 L. V. Lorenz symmetrical regauging (later credited to H. A. Lorentz) [748] of the equations carefully selects only those Maxwellian systems that have two simultaneous equal and opposite disequilibria with their active environment. This assumes that the potential energy of the system is freely changed twice (by gauge freedom), but only in such highly selected manner as to form two equal and opposite new "free" force fields in the system. These two force fields perform *internal work* inside the system continuously, increasing its stress (and its stress potential, thereby curving local spacetime). Since there is no *net resultant* force field, the two force fields are unable to translate electrons in the circuit to do free *external* work in the external load. So the symmetrically regauged Maxwellian system has been altered: its energy has been changed twice, forming a stress potential inside it and increasing and maintaining that stress on the system, and the frame of the system has been somewhat rotated out of **the** laboratory frame. The symmetrically regauged Maxwellian system most decidedly is not identical to the system prior to regauging.

We note merely that the common Lorentz symmetrical regauging unwittingly assumes two Maxwell's demons of yet different kind, each freely fueled from the local vacuum environment, and each continuously performing internal work upon the system to produce and maintain system stress.

Gauge freedom is thus revealed as a special kind of Maxwell's demon, since (1) it assumes that the potential energy of a system can be freely changed at will at any time, and (2) unless we abandon the conservation of energy law, that energy change must have involved energy exchange **with** the external environment. So the gauge freedom axiom of quantum field theory assumes two specialized Maxwellian demons — i.e., mechanisms for transfer of energy between environment and system, so as to continuously perform internal work upon the system. In this case the two demons are equal and opposite, and fight each other to a draw insofar as performing any useful external work.

Oddly, in present electrical circuits the ubiquitous but *arbitrary* closed current loop circuit — passing all spent current from the external circuit back through the source dipole in the generator against the dipole's **back** emf— self-imposes Lorentz regauging of excitation discharge in the circuit and prevents COP>1.0 functioning. This is not required by thermodynamics in general! Indeed, several areas are already known to violate present thermodynamics. Sharp discharges (strong gradients), for example, are known to violate it. [749] Other known areas where thermodynamics is violated include rarefied media, and anomalous memory effects in materials. Modern research is being conducted in such areas under the heading of "extended thermodynamics". [750].

Since experiment and not theory is primary in science, let us consider some additional actual Maxwell demon experiments. The well-known "negative resonance absorption of the medium" produces more output energy than the operator inputs to the experiment, with hundreds of these experiments done every year routinely by many nonlinear optical laboratories. As an example, Bohren's version of such an experiment [751] commonly outputs 18 times as much EM energy as the operator inputs, exhibiting COP = 18. Independent replication of Bohren's work by Paul and Fischer [752] is reported in the same journal issue.

Added to the charged capacitor lying on a permanent magnet, there thus exist plenty of proven, replicated experiments which can be easily performed to demonstrate a Maxwellian demon operating in a Maxwellian system and freely producing COP>1.0, or even COP = oo. Because of the demon (the operational mechanism), these experiments all involve open systems far from equilibrium with their active environment. Hence they are not limited by the second law of classical equilibrium thermodynamics.

In short. Maxwell's demon is very much alive in many forms and is thgiving after all. It has just been hiding in different form than what is usually suspected.

T.E. Bearden, Ph. D.
Magnetic Energy, Ltd.

ENDNOTES

1. (a) Albert Einstein, "Foreword," in (b) Max Jammer, *Concepts of Space: The History of Theories of Space in Physics,* Harvard University Press, Cambridge, Massachusetts, 1969, p. xi-xii.

2. George Zebrowski, "The holdouts," *Nature,* Vol. 408, 14 Dec 2000, p. 775; expressing the thinking of Stephen Hawking, one of the leading physicists of our day.

3. Mario Bunge, *Foundations of Physics,* Springer-Verlag, New York, 1967, p. 176.

4. (a) J. H. Poynting, "On the transfer of energy in the electromagnetic field," *Phil. Trans. Roy. Soc. Lond,* Vol. 175, Part II, 1884, p. 343-361; (b) — "On the Connection Between Electric Current and the Electric and Magnetic Inductions in the Surrounding Field," *Phil. Trans. Roy. Soc. Lond,* Vol. 176, 1885, p. 277-306.

5. (a) Oliver Heaviside, "Electromagnetic Induction and Its Propagation," *The Electrician,* 1885, 1886, 1887, and later — a series of 47 sections, published section by section in numerous issues of *The Electrician* during 1885, 1886, and 1887; (b) —*Electromagnetic Theory, 3 vols.,* Benn, London, 1893-1912. Second reprint 1925. An unabridged edition of all three volumes, with a critical and historical introduction by **E. Weber,** was published by Dover, New York, 1950. See particularly (c) - "On the Forces, Stresses, and Fluxes of Energy in the Electromagnetic Field." *Phil Trans. Roy. Soc. London,* 183A, 1893, p. 423-480. In this prestigious publication, Heaviside discusses the Faraday-Maxwell ether medium, outlines his vector algebra for analysis of vectors without quaternions, discusses magnetism, gives the EM equations in a moving medium, and gives the EM flux of energy in a stationary medium. On p. 443, he credits Poynting with being first to discover the formula for energy flow, with Heaviside himself independently discovering and interpreting this flow a little later by himself in an extended form.

6. E.g., a polite debate has continued at intervals, for about 30 years, in the Am. J. *Phys.* alone.

7. Richard P. Feynman, Robert B. Leighton, and Matthew Sands, *The Feynman Lectures on Physics,* Addison-Wesley, Reading, MA, Vol. 1,

8. *Ibid.*, Vol. 1, 1964, p. 12-2.

9. *Ibid.*, Vol. 2, 1964, p. 2-1.

10. John D. Kraus, *Antennas,* Second Edition, McGraw Hill, 1988.

11. Raymond A. Serway, *Physics for Scientists and Engineers with Modern Physics,* Third edition, updated version, Saunders College Publishing, Philadelphia *et al,* 1990, p. 620.

12. T. E. Bearden, "Giant Negentropy from the Common Dipole," J. *New Energy,* 5(1), Summer 2000, p. 11-23. Also on website www.cheniere.org.

13. (a) T. D. Lee, "Question of Parity Conservation in Weak Interactions," *Phys. Rev.,* 104(1), Oct. 1, 1956, p. 254-259; (b) — with Reinhard Oehme and C. N. Yang, "Remarks on Possible Noninvariance under Time Reversal and Charge Conjugation," *Phys. Rev.,* 106(2), 1957, p. 340-345; (c) — and C. N. Yang, "Parity Nonconservation and a Two Component Theory of the Neutrino," *Phys. Rev.,* 105(5), Mar. 1, 1957, p. 1671-1675.

14. C. S. Wu, E. Ambler, R. W. Hayward, D. D. Hoppes and R. P. Hudson, "Experimental Test of Parity Conservation in Beta Decay," *Phys. Rev., Vol.* 105, 1957, p. 1413.

15. We published it crudely two years later. See T. E. Bearden, *Quiton/Perceptron Physics: A Theory of Existence, Perception, and Physical Phenomena,* NTIS Report AD-763-210, 1973.

16. A time-reversal zone is a momentary tiny region of the fluid wherein antiphoton reactions with the main ions predominate over **photon** reactions.

17. See T. E. Bearden, "EM Corrections Enabling a Practical Unified Field Theory with Emphasis on Time-Charging Interactions of Longitudinal EM Waves," *J. New Energy,* 3(2/3), 1998, p. 12-28. A slightly expanded paper by the same title is published in *Explore,* 8(6), 1998, p. 7-16.

18. E.g., see Xiaodong Chen, "A New Interpretation of Quantum Theory — Time as Hidden Variable," Los Alamos National Laboratory web site, arXiv:quant-ph/9902037 v3, 11 Feb. 1999. Using two more **time** variables as the quantum hidden variables, Chen derives Dirac's field equation under the principle of quantum physics, and then extends **the**

method into quantum fields with arbitrary spin number. Chen's model offers very interesting unifications of quantum mechanical behavior.

19. F. Mandl and G. Shaw, *Quantum Field Theory,* Wiley, 1984, Revised Edition 1993, Chapter 5. This is a deeper coverage of the photon polarizationd. Mandl and Shaw argue that the longitudinal and scalar (time-polarized) polarizations are not directly observable, but only in combination, where they manifest as the "instantaneous" Coulomb (i.e., electrostatic) potential. This argument, translated from particle terminology to wave terminology, directly fits and strongly supports my reinterpretation {12} of Whittaker's 1903 wave decomposition of the scalar potential {85}. The reinterpretation also represents the discovery of the giant negentropy process favored by nature, easily evoked by breaking 3-symmetry (as by forming a simple dipole).

20. James Clerk Maxwell, "A Dynamical Theory of the Electromagnetic Field," *Roy. Soc. Trans.,* Vol. CLV, 1865, p 459. Read Dec. 8. 1864. Also in *The Scientific Papers of James Clerk Maxwell, 2* vols, bound as one, edited by W. D. Niven, Dover, New York, 1952, Vol. 1, p. 526-597. In this seminal paper, Maxwell's equations of the electromagnetic field are given in "Part III, General Equations of the Electromagnetic Field," p. 554-564. On p. 561, Maxwell lists his 20 variables. On p. 562, he summarizes the different subjects of the 20 equations, being three equations each for magnetic force, electric currents, electromotive force, electric elasticity, electric resistance, total currents; and one equation each for free electricity and continuity.

21. B. J. Hunt, *The Maxwellians,* Cornell University Press, 1991 gives the history of the alteration of Maxwell's field theory by Fitzgerald, Heaviside, Lodge, and Hertz. In an appendix, Hunt makes a comparison between the standard expressions of the Maxwell field equations and their expression in quaternionic form.

22. E.g., J. D. Jackson, *Classical Electrodynamics,* 2nd Edition, Wylie, 1975, p. 219-221.

23. Willis E. Lamb Jr. and Robert C. Retherford, "Fine structure of the hydrogen atom by a microwave method," *Phys. Rev.,* 72(3), Aug. 1, 1947, p. 241-243. Lamb received the 1955 Nobel Prize in physics jointly with Polykurp Kush for experiments measuring the small displacement later called the "Lamb shift" of O+ne of the energy levels in atomic

hydrogen. This is a small "vacuum energy" effect, but the *energy density* involved is greater than the surface energy density of the sun.

24. Craig F. Bohren, "How can a particle absorb more than the light incident on it?" *Am. J. Phys.,* 51(4), Apr. 1983, p. 323-327. Under nonlinear conditions, a particle can absorb more energy than is in the light incident on it. Metallic particles at ultraviolet frequencies are one class of such particles; insulating particles at infrared frequencies are another.

25. See also H. Paul and R. Fischer, "'(Comment on "How can a particle absorb more than the light incident on it?')," *Am. J. Phys.,* 51(4), Apr. 1983, p. 327 for a replication and validation of Bohren's experiment,

26. H. B. G. Casimir, "On the attraction between two perfectly conducting plates," presented at a meeting of the Royal Netherlands Academy of Arts and Sciences on 29 May, 1948. Published in the same year in *Proc. Koninklijke Nederlandse Akad. van Wetenschappen,* Amsterdam, vol. 51(7), 1948, p. 793-796. In English. It is an extrapolation of the more detailed paper of Casimir and Polder, 1948.

27. S. K. Lamoreaux, "Demonstration of the Casimir Force in the 0.6 to 6 micro m range," *Phys. Rev. Lett.,* 78(1), Jan. 6, 1997, p. 5-8. Lamoreaux gives a rigorous experimental verification of the Casimir effect.

28. Franklin B. Mead and Jack Nachamkin, "System for Converting Electromagnetic Radiation Energy to Electrical Energy," U.S. Patent No 5,590,031. An invention for extracting energy from the vacuum via the proven Casimir effect.

29. (a) Floyd Sweet and T. E. Bearden, "Utilizing Scalar Electromagnetics to Tap Vacuum Energy," *Proc. 26th Intersociety Energy Conversion Eng. Conf. (IECEC '91),* Boston, Massachusetts, 1991, p. 370-375. Sweet's device produced 500 watts output from a 33 microwatt **input** by the operator. A highly successful anti-gravity experiment designed by the present author was also performed, and is reported in the paper. Unfortunately, Sweet later died and never fully revealed the activation secret by which barium ferrite magnetic materials could be in self-oscillation at 60 Hertz. Weak self-oscillation of such permanent magnetic materials at higher frequency is now known, of course. E.g., see (b) V. E. Zakharov and V. S. L'vov, "Parametric excitation of spin waves in ferromagnets with magnetic inhomogeneities," *Sov. Phys. Solid State,* 14(10) 1973, p. 2513. Particularly see (c) V. S. L'vov, *Wave Turbulence Under Parametric Excitation: Applications to Magnets,* Springer Series in

Nonlinear Dynamics, Springer-Verlag, New York, 1994. Self-oscillation can in fact be induced in permanent magnet materials. We comment that, while a permanent magnet is in self-oscillation, a simple set of wires or a coil around the magnet will receive EM energy by induction, and can power a very tiny load in a closely adjacent circuit.

30. T. E. Bearden, "Bedini's Method for Forming Negative Resistors in Batteries," *J. New Energy,* 5(1), Summer 2000, p. 24-38. Also carried on restricted DoE website http://www.ott.doe.gov/electromagnetic/ and on the present author's open website http://www.cheniere.org.

31. Teruo Kawai, "Motive Power Generating Device," U.S. Patent No. 5,536,518.Jul. 25, 1995. My board of directors and I were physically present when the Kawai system, company, etc. were seized by what can only have been the Yakuza (Japanese mafia), even though Kawai was being backed by one of the wealthiest investors in Japan. I had just reached an agreement with Kawai to produce and market his overunity motor worldwide. Several legitimate Japanese overunity systems, ready for production, have been stopped in this fashion. Kawai's process, applied with efficient switching such as photon-coupled switching, essentially doubles the COP of the motor to which it is applied. If one starts with a high efficiency (e.g., Hitachi) permanent magnet electric motor of 0.7 or 0.8, one can expect to produce COP = 1.4 and 1.6 respectively, the actual results obtained by Hitachi tests of two Kawai-modified Hitachi motors. We accent that the efficiencies of the motors remain less than 100% at all times.

32. Gabriel Kron, "Electric circuit models of the Schrodinger equation." P*hys. Rev.* 67(1-2), Jan. 1 and 15, 1945. Quoting, p. 41: *""Now a value E of the negative resistances, at which the generator current becomes zero, represents a state at which the circuit is self-supporting and has a continuous existence of its own without the presence of the generator, as the negative resistances just supply the energy consumed by the positive resistances. ... When the generator current is positive the circuit draws energy from the source, and when the current is negative the circuit pumps back energy into the source. At zero generator current the circuit neither gives nor takes energy, and theoretically the generator may be removed."* In this passage, Kron was required to insert the word "theoretically". Kron was the chief scientist for General Electric on the Network Analyzer project at Stanford University before WW II. In the 1930, he did successfully build negative resistors (at least three), and he

did successfully power the network analyzer with them. He was never permitted to release the technical details, although he placed judicious hints in several of his papers, and slipped certain key phrases past the censors. Interestingly, Sweet was his protegee, and it is conceivable that the basis for Sweet's device may have been Kron's original negative resistor. Independent tests and verification of the Sweet device were performed by Walter Rosenthal, a retired professional test engineer of considerable experience.

33. Shoukai Wang and D. D. L. Chung, "Apparent negative electrical resistance in carbon fiber composites," *Composites, Part B,* Vol. 30, 1999, p. 579-590. Apparently the referees required the replacement of the term "negative electrical resistance" by the term "apparent negative resistance". In the paper, simply examine the actual results shown in the curves of the negative-going current, against the voltage, with the line passing directly through the origin. That is a true negative resistance, not a differential one or an "apparent" one. A patent was filed on this invention.

34. (a) T. H. Moray, *The Sea of Energy,* 5th Edn., Salt Lake City, 1978. The Moray device weighed 55 pounds and produced 50 kilowatts of power in the late 1930s, and was demonstrated to scientists and engineers numerous times, Moray made tubes which actually contained very special semiconductors, three of them in contact, each pressed at high pressure during a sintering process. A very eerie chain of circumstances eventually destroyed the device. Moray rode in a bulletproof car, and he was sometimes fired at from the sidewalk or an alley. A double agent, working for both the U.S. and the Soviet Union, infiltrated his lab and eventually destroyed the device. The Morays were never given a proper scientific hearing and were never funded for full development. T. Henry Moray was shot and wounded in his own laboratory, wrestling with a would-be assassin. Yet so many expert engineers and scientists witnessed and tested the machine in operation that there is no question of its legitimacy. Unfortunately, the reference cited is not at all a satisfactory scientific examination of the Moray device. A related U.S. patent was issued which at least shows some details of the Moray tube: See (b) Thomas H. Moray, "Electrotherapeutic Apparatus," U.S. Patent No. 2,460,707, Feb. 1, 1949. I personally received a treatment on a Moray device for severe pain, and the relief was rapid and remarkable.

35. See (a) William B. Burford III and H. Grey Verner, *Semiconductor Junctions and Devices: Theory to Practice,* McGraw-Hill,

New York, 1965, Chapter 18: Point-Contact Devices. The very first transistor — the point contact transistor — also often exhibited negative resistance. Quoting, p. 281:

> *"First, the theory underlying their function is imperfectly understood even after almost a century..., and second, they involve active metal-semiconductor contacts of a highly specialized nature. ... The manufacturing process is deceptively simple, but since much of it involves the empirical know-how of the fabricator, the true variables are almost impossible to isolate or study. ... although the very nature of these units limits them to small power capabilities, the concept of small-signal behavior, in the sense of the term when applied to junction devices, is meaningless, since there is no region of operation wherein equilibrium or theoretical performance is observed. Point-contact devices may therefore be described as sharply nonlinear under all operating conditions."*

Certainly degenerate four-wave mixing and therefore time reversal can occur in in semiconductors. E.g., see (b) R. K. Jain, "Degenerate four-wave mixing in semiconductors: application to phase conjugation and to picosecond-resolved studies of transient carrier dynamics." *Opt. Eng.*, 21(2'), March/April 1982, p. 199-218. We also point out that hole current can be emitted from an n-type semiconductor having a metallic point placedd on its surface, and hole current will move against the voltage (electron current view). A process (patent pending) by Bedini and Bearden have shown that a capacitor may be charged by hole current, and then discharge electron current, effectively transducing negative energy into positive energy. It is therefore possible (Bedini's method) to switch a capacitor from a hole-current charging circuit by a hole-emitting process, to a bypass capacitor across a source such as a battery after the capacitor has reached higher charge voltage than the source. The capacitor will then charge the battery and power the circuit as well, during that portion of its discharge cycle while its voltage is above that of the battery. This is a legitimate COP>1.0 process, invented by Bedini.

36. (a) William Jay Fogal, "High Gain, Low Distortion, Faster Switching Transistor." U.S. Patent No. 5,196,809, Mar. 23, 1993; (b) — "High Gain, Low Distortion, Faster Switching Transistor." U.S. Patent No. 5,430,413, July 4, 1995. The Fogal semiconductor can be rigged to perform the permitted degenerate four-wave mixing and therefore time reversal. It can thus be rigged as a true negative resistor, where the current moves against the voltage.

37. Stephen L. Patrick, Thomas E. Bearden, James C. Hayes, Kenneth D. Moore, and James L. Kenny, "Motionless Electromagnetic Generator," U. S. patent # 6,362,718, March 26, 2002.

38. (a) T. E. Bearden, "Energy from the Active Vacuum: The Motionless Electromagnetic Generator," in M. W. Evans (Ed.), *Modern Nonlinear Optics,* Second Edition, Wiley, 2001, Part 2, p. 699-776; (b) M. W. Evans, P. K. Anastasovski, T. E. Bearden *et al.,* "Explanation of the Motionless Electromagnetic Generator with 0(3) Electrodynamics," *Found. Phys. Lett,* 14(1), Feb. 2001, p. 87-94; (c) M. W. Evans, P. K. Anastasovski, T. E. Bearden *et ah,* "Explanation of the Motionless Electromagnetic Generator by Sachs's Theory of Electrodynamics," *Found Phys. Lett.,* 14(8), Aug. 2001, p. 387-393.

39. A version of the MEG was also independently replicated by J. L. Naudin. See his website at http://jnaudin.free.fr/html/meg.htm .

40. T. E. Bearden, "Dark Matter or Dark Energy?", *J. New Energy,* 4(4), Spring 2000, p. 4-11.

41. See Chapter 4 for a high-level expose of this methodology.

42. Sweet and Bearden, {29a). Sweet performed an antigravity experiment designed by the present author, and successfully reduced **the** weight of an object on the laboratory bench, by 90%. Sweet's solid state magnetic vacuum triode amplifier produced a COP = 1,500,000, so a **very** appreciable Dirac sea hole current was available to work with. Conversion of the Dirac sea hole current into electrical current via the present Bedini-Bearden process would have eliminated the antigravity and produced a very large increase in output electrical power.

43. See (a) T. E. Bearden, "The Unnecessary Energy Crisis: How to Solve It Quickly," ADAS Position Paper, June 2000; (b) Bearden **{12};** (c) Bearden {30}; (d) T. E. Bearden, "EM Energy From The Vacuum: Ten Questions With Extended Answers," September 2000. The present author has been calling for just such a program. These papers are on restricted DOE Website http://www.ott.doe.gov/electromagnetic/ and also are on the author's website at http://www.cheniere.org.

44. Nathan Smith, "Marketable Results vs. Good Science?," *Sci. Am.* , 284(5), May 2001, p. 8-9. Quote is from p. 9.

45. This is the actual phrase often used in such Government contracts. What it means is that the Government (which means the government

employee controlling that program and its funds) can suddenly declare that the Inventor is not getting his invention developed rapidly enough, and the Government then seizes the patent to "get it developed more quickly". The inventor is suddenly left hanging, no longer in control of his own intellectual property. Or the Government has the power to block development altogether.

46. Often the universities just bluntly state that *all patents revert to the university.*

47. Hal Hellman, *Great Feuds in Science,* Wiley, New York, 1998. We particularly call attention to Hellman's dissertation on Wegener's persecution. Today, the legitimate overunity EM researcher and the cold fusion researcher are regarded much like Wegener was regarded — as the very epitome of a fool. This label is appended by "experts" who are not even aware of what really powers an EM circuit or an electrical power distribution system.

48. A photon is a piece of angular momentum (called "action" by the physicist), consisting of a little piece of spatial energy (ΔE) and a little piece of time (Δt), welded together as $(\Delta E)(\Delta t)$ with no seam in the middle, so to speak. But now look at that little $(\Delta E)(\Delta t)$. Since the photon is quantized, $(\Delta E)(\Delta t) = k = \hbar$. Any change in (Δt) requires that (ΔE) change inversely; i.e., $(\Delta E) = \hbar/(\Delta t)$. So increasing (Δt) decreases (ΔE) accordingly. Let us call the spatial energy *s* compacted into (dt) the equivalent *energy* of the photon. Then *s* is given by $s = c^2(\Delta t) = 9\times10^{16}(\Delta t)$. So as the frequency of a photon lowers, the (Δt) time component increases proportionally, and the total equivalent energy in the photon increases dramatically by many orders of magnitude! As an example, suppose we halve the spatial energy (ΔE). That doubles the original time interval (Δt), which gives the new $s = c^2(2\Delta t)$ or $s = 2c^2(\Delta t)$ for the new equivalent energy. So while we halved the *normal* spatial energy formally transported by the photon, we multiplied the *equivalent* time-energy by the enormous factor of $2c^2$ which is approximately 18×10^{16} in the MKS system. It follows that, if we use the equivalent time) energy of the photon and transduce a little of it into normal spatial energy, the energy density of those nuclear reactions now seen only in distant energetic objects such as pulsars, exploding stars, etc. can be achieved right on the laboratory bench. *The highest energy physics has not yet been born in the physics community, and what is presently being done in the high-energy*

accelerators is child's play compared to what can be done with time-energyengineering.

49. To see by another method that time is energy, one notes that the choice of fundamental units chosen for one's physics model is arbitrary. So we choose a single fundamental unit, the joule, to make a new physics model. Thereupon all other entities are energy and energy functions only, Hence, time is totally a function of energy. Actually, time is spatial energy compressed by the factor c^2, so it has the same energy density as mass, except the highly compressed spatial energy is placed in the time domain to appear at "time" rather than in 3-space to appear as "mass".

50. E.g., in cold fusion experiments where the time-energy is partially transduced in a time-reversed manner, the gluon forces binding the quarks in the affected neutrons and protons are dramatically reduced and the quarks are therefore nearly freed. This is being done in an apparatus of perhaps two cubic feet in volume, rather than a giant accelerator 20 miles in diameter and costing billions of dollars. So far, the largest accelerator using 3-space (decompressed) energy is just a bit short of the energy required to free the quarks. Use of time (compressed) energy allows such reaction as freeing the quarks to be easily accomplished, while the accompanying decompressed *spatial* energy is very low.

51. Time energy has the same energy density as mass, but that highly compressed energy has just been placed in the 4th axis *ict* of Minkowski space rather than in 3-space. In *ict* the only variable is t, so the variation of the compressed energy can only appear in the *t* variable portion. See Chapter 2.

52. (a) James Patterson, U.S. Patents 5,318,675; 5,372,688; 5,607.563 (b) — and Dennis Cravens, U.S. Patent No. 5,607,563.

53. Ironically, as suppression of innovative research in science increases, science may eventually face turning into the kind of dogmatic system that it struggled against for some 300 years before escaping. When science defends a theory that experiments refute, as it does today in the case of cold fusion, then it is very close to that debacle that can spell the end of science itself.

54. E. Allan Blair, Letter to the Editor, *Newsweek,* Mar. 3, 1997, p. 14.

55. Arthur C. Clarke, "Space Drive: A Fantasy That Could Become Reality," *NSS... AD ASTRA,* Nov/Dec 1994, p. 38.

56. William K. George, in *Editing the Refereed Scientific Journal, edited* by Robert A. Weeks and Donald L. Kinser, IEEE Press, New York, **1994. p. 227-228.**

57. Max Planck, in G. Holton, *Thematic Origins ofScientific Thought, Harva*rd University Press, Cambridge, MA, 1973.

58. Jonathan Schlefer, editor of *Technology Review,* published at MIT. in an October 1990 editorial.

59. Rolf Landauer, "Fashions in Science and Technology," *Physics Today*,50(12),Dec.1997,p.62.

60. Julius Robert Von Mayer, "Bemerkungen iiber die Krafte der unbelebten Natur," in J. von Liebig's *Annalen der Chemie* (vol. 42), 1842; Die *organische Bewegung in ihrem Zusammenhange mit dem Stoffwechsel, (Organic* Motion in Its Relation to Metabolism), 1845. His papers were published as *Die Mechanik der Warme,* 1867, with third edition in 1893.

61. Alfred Wegener, *Die Entstehung der Kontinente und Ozeane, 1915;* fourth revised edition, 1929. A Dover reprint of the fourth revised edition, translated into English, *Origin ofContinents and Oceans,* was published in 1996.

62. Paul Nahin, *Oliver Heaviside: Sage in Solitude,* IEEE Press. New York, 1988, p. 225.

63. Martin Gumpert, *Trail-Blazers ofScience.* New York, Funk and Wagnalls Company, 1936, p. 232.

64. This area is now referred to as *ovonics,* where the "ov" is directly taken from "Ovshinsky". The materials have found use in copy machines, fax machines, liquid crystal displays, and optical memory disks. Ovshinsky has obtained over 200 patents and continues to work in the energy conversion field. His development of a new storage battery, e.g., broke all the Department of Energy tests and doubled the energy density permitted. Once in awhile the good guys beat the scientific suppression system.

65. Stan and Iris Ovshinsky were honored with the American Chemical Society's Heroes of Chemistry Award for 2000. They were honored for 40 years of sustained effort and contributions in the

sustainable and renewable energy field, including amorphous silicon cells for roofs of houses, highly specialized storage batteries, etc.

66. On the other hand, many scientific disagreements are conducted in quite proper and gentlemanly fashion. An example is the continuing decades of argument over energy flow theory, in *Am. J. Phys.* The problem has still not been officially resolved; we would hope that the material in this book will shed new light upon it, by pointing out the exact difference between the long-neglected nondiverged component as well *as* the diverged component, and also pointing out what Lorentz's trick of closed surface integration of the energy flow vector really does.

67. It follows quite naturally that, once we compress spatial energy by c , we may place the compressed energy in 3-space, in which case it is known as "mass", or we may place it in the time domain, in which case it is known as "time". If that cannot be done, then physics errs in using time as a variable on the fourth axis, and fundamental units are not arbitrary after all.

68. E.g., see D. K. Sen, *Fields and/or Particles,* Academic Press, London and New York, 1968, p. viii. Quoting: *"The connection between the field and its source has always been and still is the most difficult problem in classical and quantum electrodynamics."*

69. See T. D. Lee, "Can Time Be a Discrete Dynamical Variable?". *Phys. Lett,* 122B(3, 4), Mar. 10, 1983, p. 217-220. Lee showed that time is a discrete dynamical variable across the entire range of mechanics: from classical to nonrelativistic quantum mechanics, and then to relativistic quantum field theories. In all stages of mechanics, time can be treated as a discrete parameter, and it can be treated as a bona fide dynamic variable, Hence time has dynamics and structure, and therefore energy.

70. E.g., one may assume that the entire virtual state is an internal structuring and dynamics existing inside the macroscopic flow of time. The virtual state dynamics obviously exists in spacetime (which is assumed to be continuous), but we also consider any "virtual particle" (e.g., a virtual electron) as if it had been suddenly "observed" momentarily That assumes d/dt (LLLt) => LLL, a frozen 3-space snapshot. However, since that cannot really be observed, then we are actually considering something analogous to "if we could observe something in spacetime that cannot be observed in space alone". The only place left for it to

!observably exist anyway, if we could in fact observe it" is time, if space is ruled out.

71. It is necessary to trace the energy transductions and dissipations inside the generator. Ignoring those internal dynamics, the casual observer sees that one inputs shaft energy to the generator, and out comes some electromagnetic energy in the external electrical circuit, pouring from the gnerator terminals. We catch a lesser amount out there in the external circuit or power line, so we think we input some energy, had some internal losses and what gets collected in the conductors of the power line is the remainder of what we input, after transductions and losses in the generator. That is not what happens at all! Embarrassingly, an *enormous* flow of energy comes out of those generator terminals, if all of it is accounted. This includes (i) the tiny component that strikes the surface charges of the external conductors and gets diverged into the conductors, thus being captured by the circuit, and (ii) the enormous remainder of the energy flow in the surrounding space, which misses the circuit altogether and is just wasted. Something like a trillion times as much EM energy may be pouring out of the terminals of the generator and *being wasted*, as we mechanically input to the generator shaft, or as we "catch" and use in the external circuit. As later chapters discuss, Poyntin ; never considered the component that misses the circuit entirely. Heaviside discovered it but could not explain its startling magnitude or its source. Lorentz knew of this enormous flow component. He could not explain it, and stated it "had no physical significance" since it powered nothing. Lorentz originated a little integration trick that discarded it neatly from all accountability.

72. If the energy input to an inert power system generator were what powered the attached external circuit, then only the Poynting component would be emitted from the terminals of the generator. In that case, Heaviside's discovery of the additional nondiverged component would be wrong, and Lorentz was also wrong in recognizing it by stating it had no *physical* significance. It also means that a dipole formed between the terminals can have no broken symmetry in its active vacuum flux exchange, which is falsified by particle physics {14, 73,}. Also, no charge could pour out energy and create fields and potentials in surrounding space, and neither could a dipole. That is easily falsified by actual experimental measurement. Our reinterpretation of Whittaker's wave decomposition of the scalar potential would also be wrong, as would Mandl's and Shaw's argument {19} that a combined pairing of a scalar

photon and a longitudinal photon are observable, producing the instantaneous scalar potential.

73. T. D. Lee, *Particle Physics and Introduction to Field Theory,* Harwood, New York, 1981,*passim.* In 1957, Lee and Yang received the Nobel Prize for their work in predicting broken symmetry. This included the broken symmetry of opposite charges — and hence of a dipole.

The very definition of broken symmetry, applied to the source dipole once it is formed in the generator, reveals that the dipole itself receives virtual photon energy from the seething vacuum, transduces it, and outputs it as real observable EM energy pouring out of the generator terminals and out through 3-space surrounding the entire power line. This is the source of the tremendous energy flow from the terminals, including a large component missing the circuit (as discovered by Heaviside in the 1880s). This large nondiverged component of the energy flow was discarded arbitrarily by Lorentz because there was absolutely no explanation of its source, and because it was thought to have "no physical significance" (Lorentz's term) since it powered nothing.

74. Wu et al. {14} experimentally showed that the weak interaction violates parity (spatial reflection) and thus exhibits broken symmetry.

75. T. D. Lee is noted for his broken symmetry work with charges, and for establishing the broken symmetry of separated charges of unlike sign. In 1957, Lee and Yang were awarded the Nobel Prize in Physics for their investigations of weak interactions between elementary particles.

76. John D. Kraus, *Electromagnetics,* Fourth Edition, McGraw-Hill, New York, 1992, p. 578.

77. We strongly feel that anyone interested in logic must read Morris Kline, *Mathematics: The Loss of Certainty,* Oxford University Press, New York, 1980. Contrary to popular opinion and the impression projected by mathematicians, mathematics is not a body of unshakable truths aboul the physical world, and mathematical reasoning is not exact and fallible.

78. One also needs to be aware of Godel's proof. See Kurt Godel, "Uber formal unentscheidbare Satze der *Principa Mathematica* une verwandter Systeme" ("On Formally Indeterminable Propositions of the *Principia Mathematica* and Related Systems," in *Monatshefte fur Mathematik und Physik,* Vol. 38, 1931. This is the publication in which Godel's Proof first appeared, which states that within any logical

mathematical system there are propositions or questions that cannot be proved or disproved on the basis of the axioms within that system. Therefore, it is uncertain whether or not the axioms or arithmetic will give rise to contradictions, since they can.

79. A critical reference for the longitudinal EM interferometry *weapons* is M. W. Evans, P. K. Anastovski, T. E. Bearden *et al.*, "On Whittaker's Representation of the Electromagnetic Entity in Vacuo, Part V: The Production of Transverse Fields and Energy by Scalar Interferometry," *J. New Energy,* 4(3), Winter, 1999, p. 76-78. This paper is a short but rigorous proof of a scalar interferometer's ability to produce EM fields and energy in the distant interference zone. Either diverging (heating) energy or converging (cooling) energy — in the normal sense, extraction of energy — can be created in a distant interference zone. By pulsing and controlling the circuit ground bias of the transmitters, one produced distant hot explosions or cold explosions. In a military target in that distant zone, the effects arise from the local spacetime, thus from everywhere within the targeted vehicle. At least eight nations now have such weapons, which were apparently the weapons that Defense Secretary Cohen {89} referred to in 1997.

80. Jackson {22}, p. 249.

81. Bunge, {3},p. 182.

82. Roger Penrose, "Foreword," in T. W. Barrett and D. M Grimes [Eds.], *Advanced Electromagnetism: Foundations, Theory, & Applications,* World Scientific, (Singapore, New Jersey, London, and Hong Kong), 1995.

83. Myron Evans, President of Alpha Institute's Institute for Advanced Study, private communication, 1999. Dr. Evans is the author of over 600 scientific papers, the prestigious editor of several scientific book series, and a noted foundations scientist. He is the co-discoverer and proponent of the Vigier-Evans B(3) magnetic field and a proponent of the proposed fundamental extension of U(1) electrodynamics to O(3) electrodynamics. O(3) electrodynamics has now been revealed as an important subset of Sachs' unified field theory.

84. Robert H. Romer, "Heat is not a noun," *Am. J. Phys.,* 69(2), Feb. 2001, p. 107-109. The quotation is from footnote 24, p. 109.

85. E. T. Whittaker, "On the Partial Differential Equations of Mathematical Physics," *Math. Ann.,* Vol. 57, 1903, p. 333-355.

86. But see Chapter 2 for a reinterpretation and correction of Whittaker's decomposition of the scalar potential. His harmonic set of bidirectional phase conjugate longitudinal EM wavepairs in 3-space is replaced with a harmonic half-set of longitudinal EM waves converging in the time domain upon the dipolarity; absorption and transduction by the charges; and re-emission as the other harmonic half-set of longitudinal EM waves diverging out from the source dipolarity in all directions in 3-space. The correction allows a very novel solution to the long-vexing problem of the source charge and its associated fields and potentials and their energy {12}.

87. (a) G. Johnstone Stoney, "Microscopic Vision," *Phil. Mag.,* Vol 42, Oct. 1896, p. 332; (b) — "On the Generality of a New Theorem," ***Ibid.,*** Vol.43, 1897, p. 139-142; (c) — Discussion of a New Theorem in Wave Propagation," *ibid,* Vol. 43, 1897, p. 273-280; (d) — "On a Supposed Proof of a Theorem in Wave-motion," *ibid.,* Vol. 43, 1897, p. 368-373.

88. Some Russian scientists refer to the hidden internal electrodynamics as the "information content of the field".

89. Secretary of Defense William Cohen at an April 1997 counterterrorism conference sponsored by former Senator Sam Nunn. Quoted from DoD News Briefing, Secretary of Defense William S. Cohen, Q&A at the Conference on Terrorism, Weapons of Mass Destruction, and U.S. Strategy, University of Georgia, Athens, Apr. 28, 1997.

90. For a basic discussion of these photon polarizations, see (a) Richard Feynman, *Quantum Electrodynamics,* 1961, 1963. Quantum field theory recognizes four polarizations of the photon, to include x- and y-transverse polarizations in 3-space, longitudinal or z- polarization in 3-space, and the time-polarized photon (which may be taken to be a longitudinally-polarized photon in the time axis). Existence of these four modes of polarization or energy vibration in photons implies the existence of four correspondingly polarized EM waves. Among other things, Feynman discusses the "sum over four polarizations" of photons and such The term "Gupta-Bleuler" theory is the formalism that has grown up around this problem. For a deeper discussion, see (b) Lewis H. Ryder, *Quantum Field Theory,* Second Edition, Cambridge University Press, 1996, p. 147 *et seq.* For an even more advanced discussion, see (c) F.

Mandl and G. Shaw {19}. For discovery of the coupling of time-polarized and 3-space longitudinally polarized EM waves as the higher EM energy flow symmetry resolving the source charge problem, and thereby reinterpreting Whittaker's decomposition of the scalar potential {85}, see (d) Bearden {12}. We point out that the latter reinterpretation can also be "cranked through" the superpotential theory of Whittaker, to involve all EM potentials, fields, and waves.

91. (a) E. T. Whittaker, "On an Expression of the Electromagnetic Field Due to Electrons by Means of Two Scalar Potential Functions," *Proc Lond. Math. Soc*, Series 2, Vol. 1, 1904,p. 367-372. The paper initialed what today is called *superpotential* theory. It was published in 1904 and orally delivered in 1903. For a sampling of other superpotential work, see (b) W. H. McCrea, *Proc. Roy. Soc. Lond. A,* Vol. 240, 1957, p. 447; (c) A. Nisbet, *Physica,* Vol. 21, 1955, p. 99; (d) P. Debye, *Ann. Phys.,Leipzig,* Vol. 30, 1909, p. 57. For an excellent overview discussion of superpotentials and related things, see (e) Melba Phillips, "Classical Electrodynamics," in *Principles of Electrodynamics and Relativity,* Vol. IV *of Encyclopedia of Physics*, edited by S. Flugge, Springer-Verlag, 1962.

92. (a) See Evans et al. {79} for proof that scalar interferometry can produce all normal transverse EM fields, waves, and patterns. The paper appears in (b) P. K. Anastasovski; T. E. Bearden, C. Ciubotariu, W. T. Coffey, L. B. Crowell, G. J. Evans, Myron W. Evans, R. Flower, S. Jeffers, A. Labounsky, B. Lehnert, M. Meszaros, P. R. Molnar, J.-P. Vigier, and S. Roy, "The New Maxwell Electrodynamic Equations: New Tools for New Technologies," *J. New Energy, 4(3),* Special Issue of A1AS papers. Winter 1999. The volume consists of some 60 papers by the Alpha Foundation's Institute for Advanced Study (AIAS), advancing electrodynamics to a non-Abelian, gauge theoretic higher topology theory in O(3) internal symmetry. Some ten of the papers directly address Whittaker's work and extend it.

93. (a) W. A. Rodrigues, Jr. and J.-Y. Lu, "On the existence of undistorted progressive waves (UPWs) of arbitrary speeds $0 < v < \infty$ in nature," *Found. Phys.,* 27(3), 1997, p. 435-508 show that Maxwell's equations do possess superluminal solutions. A slightly corrected version is downloadable as hep-th/9606171 on the Los Alamos National Laboratory web site. Also see (b) W. A. Rodrigues, Jr. and J. Vaz Jr., "Subluminal and Superluminal Solutions in Vacuum of the Maxwell

Equations and the Massless Dirac Equation," *Adv. Appl. Clifford Algebras,* Vol. 7(S), 1997, p. 457-466.

In classified Russian weapons labs, this internal longitudinal wave (both time-domain and 3-space domain) structuring of all normal (transverse) EM potentials, fields, and waves is euphemistically called the *information content of the field.* For decades there has been a successful disinformation campaign to lead scientists of other countries into believing that the phrase means *standard spectral analysis.* It doesn't. It is also possible to communicate at superluminal speed, using longitudinal EM waves inside this infolded "inner" electrodynamics. Since mass is mostly empty space filled with a particle here and there — together with EM potentials, fields, and waves — then mass is a vast "superhighway" for direct superluminal communication using longitudinal EM waves.

94. Romer, {84}.

95. See E. T. Whittaker, *A History of the Theories of the Aether and Electricity,* two vols., Nelson, London, 1951, 1953. Reprinted by Dover.

96. Note that we have just resolved the age-old problem of change, which can be summarized in the query stated so long ago by Heraclitus: "For a thing to change, it must turn into something else. But how can a thing be itself and something else also?" We have explained the enigma by pointing out that the "thing" has no persistence in time, and is continually changing into yet another thing, either a replica (in which case we sense "no change" and hence "persistence" by memory comparison), or a partial replica with some differences (in which case we sense that "the object has changed itself in some way"), or a thing with little or no replication (in which case we sense a "different thing"). It is the unseen nature of the *d/dt* observation process that has deluded us into such irresolvable logical conflicts — and into an incomplete Aristotelian logic based on observation alone, which does not contain the resolutions to such problems because a higher-order logic is required.

97. Whittaker, {85}

98. See Chapter 2 for a discussion of the substitution of effect for cause, and of the nature of observation.

99. *Wu etal,* {14}.

100. Sen, {68}.

101. Also see Mandl and Shaw {19}.

102. William G. Harter, John Evans, Roberto Vega, and Sanford Wilson, "Galloping waves and their relativistic properties," *Am. J. Phys., 53*(7), July 1985, p. 671-679. A relativistic example is given in which the source frame observes a very nonuniformly-galloping wave whose velocity varies between 0.01 c and 100 c, even though its average velocity is c. Relativistic properties of interfering electromagnetic plane waves are discussed.

103. We point out, but do not further pursue, that this situation is reversed when time is reversed. This has very interesting applications in our little "time reversal zones" that we found were so important in the electrolyte experiments of the cold fusion researchers, and which accounted for a new class of nuclear interactions previously unknown. This does reverse the conventional law of attraction and repulsion of charged particles. It also directly affects the quarks and gluons, partially or even nearly dissolving the gluon forces holding the quarks in place, so that the quarks are nearly freed and are easily flipped.

104. Simultaneously accompanied by *separately broken* time-energy flow symmetry and *separately broken* 3-spatial energy flow symmetry.

105. Evans et al., {38b, 38c}.

106. Oliver Heaviside, *Electrical Papers,* Vol. 2, 1887, p. 94.

107. Kraus, {76}.

107. E.g., see (a) Jackson {22}, p. 237. Jackson points out that *"...the Poynting vector is arbitrary to the extent that the curl of any vector field can be added to it. Such an added term can, however, have no physical consequences. "* The first sentence is true, but the second sentence is a non sequitur. Poynting only considered the small component of the overall energy flow that enters the circuit — in short, that strikes the surface charges in the conductors and is diverged into the wires to power the Drude electrons. That is the diverged part of the energy flow. All the rest of the flow that misses the circuit is obviously not diverged or collected in the circuit, and so it has zero divergence. It is elementary vector algebra that the curl of any vector field has zero divergence. So the extra nondiverged Heaviside energy flow component — filling all space around the conductors in a power line, e.g., but missing the power system entirely and just wasted — can indeed be expressed as the curl of a vector field That energy flow is real, however, and if intercepted and collected, it then does become divergent. In that case, it does have highly significant

consequences, since the total energy flow in that component may be a trillion times the energy flow in the Poynting component alone.

For a rigorous experiment demonstrating the reality and significance ol that "physically insignificant energy flow" that "can have no physical consequences", see (b) Bohren {24}. Under nonlinear conditions, a particle can absorb more energy than is in the light incident on it by normal calculations. Electrodynamicists do *not* calculate the magnitude of an entire field or potential, e.g., but only the intensity of a *divergence from* it at a single point, as given by an intercepting unit point static charge. If that same charged particle is placed in particle resonance, it sweeps out a greater geometrical reaction cross section. Hence it intercepts and **collects** (diverges) more impinging energy — from that long-neglected otherwise nondiverged component of the flow or field that is not diverged by the *static* unit point charge assumed conventionally. Metallic particles at ultraviolet frequencies are one class of such particles and insulating particles at infrared frequencies are another. See also (c) Paul and Fischer, {25}, who replicated Bohren's experiment.

109. H. A. Lorentz, *Vorlesungen iiber Theoretische Physik an der Universitdt Leiden,* Vol. V, *Die Maxwelhche Theorie (1900-1902),* Akademische Verlagsgesellschaft M.B.H., Leipzig, 1931, "Die Energie im elektromagnetischen Feld," p. 179-186. The section is called "Der Poyntingsche Energiestrom," and begins on p. 183. See his Figure 25 **on** p. 185.

110. E.g., see W. K. H. Panofsky and M. Phillips, *Classical Electricity and Magnetism,* Addison-Wesley, Reading, MA, 1962, 2nd edition, p. 181**,**

111. Bearden, {12}.

112. A simple way to see this is to note that the back-potential across the half-loop internal to the dipole is precisely equal to the forward potential externally between the ends of the dipole but across the **external** circuit half-loop. Since the same current *q* runs through both these potentials, then by *Vq* the same amount of energy is dissipated upon **the** charges of the dipole — to scatter them and destroy the dipole — as is dissipated in the external circuit in its losses and the load. Thus **more** energy is used to destroy the dipole than is used to power the load. We have to input at least as much shaft energy to restore the dipole as was used to destroy it. Hence the COP< 1.0.

113. See to (a) M. W. Evans, P. K. Anastasovski, T. E. Bearden *el al*, "Classical Electrodynamics without the Lorentz Condition: Extracting Energy from the Vacuum," *Physica Scripta,* 61 (5) . May 2000, p. 513-5 17 in addition to that paper previously quoted. See also (b) "Runaway Solutions of the Lehnert Equations: The Possibility of Extracting Energy from the Vacuum," *Optik,* 111(9), 2000, p. 407-409.

114. Robert Bruce Lindsay and Henry Margenau, *Foundations of Physics,* Dover, New York, 1963, p. 25.

115. *Ibid.,* p. 213.

116. *Ibid.,* p. 217.

117. M. Faraday, *Experimental Researches in Electricity and Magnetism,* Vol. 1, Taylor and Francis, London, 1839; Vol. 2, Richard & John E. Taylor, London, 1844; Vol. 3, Taylor and Francis, London, 1855. A 1965 reprint of all three volumes is available from Dover, New York.

118. We also acknowledge the independent contributions of Joseph Henry. In 1830, Henry independently discovered magnetic induction, anticipating Faraday's own discovery of it. Faraday, however, published first. Two years later, Henry discovered self-induction. He died in 1878, and the unit of inductance, the *henry,* was named for him in 1893.

119. (a) Maxwell, {20}. Also see (b) James Clerk Maxwell, *A Treatise on Electricity and Magnetism,* Oxford University Press, Oxford, 1873, Third Edition, Volumes 1 and 2, unabridged, Dover Publications, New York, 1954. This standard citation widely used in the literature is in fact confusing; the First Edition was published in 1873, a second rather substantially altered edition was later published after Maxwell's 1879 death of stomach cancer, and a third edition, slightly altered from the second edition, was published even later. So controversial were quaternions at the publication of Maxwell's first edition in 1873, that part of what was to become the second edition — published after Maxwell's 1879 death — was truncated by Maxwell himself prior to his death and prior to the posthumous publication of the second edition. Thus there is considerable difference between the first and second editions, and first and third editions, of Maxwell's *Treatise,* compared to his original 1865 paper {20**}.** "Maxwell's theory" is actually his 1865 paper; everything else is a later truncation of Maxwell's theory.

120. Maxwell's letter to P. G. Tait in 1871, *Archives,* Cavendish Laboratory, Cambridge.

121. For a discussion, see (a) A. M. Bork, "Vectors versus quaternions - the letters in *Nature,"* in *Am. J. Phys.,* Vol. 34, Mar. 1966, p. 202-211. For a cogent presentation of what might have been discovered much earlier in physics if quaternions had not been cast aside in favor of the much more limited vectors, see (b) James D. Edmonds Jr., "Quaternion quantum theory: New physics or number mysticism?", *Am. J. Phys.,* 42(3), Mar. 1974, p. 220-223.

122. Edmonds, {121b}. Edmonds presents a cogent argument showing the significant impedance of the rate of discovery in physics, that **resulted** from the ill-advised casting aside of the far more comprehensive quaternion theory in favor of the much more limited vector theory.

123. Heaviside, {5a, 5b}.

124. T. W. Barrett, "Tesla's Nonlinear Oscillator-Shuttle-Circuit (OSC) Theory," *Annales de la Fondation Louis de Broglie,* 16(1), 1991, p. 23-41, Barrett later extended some of the energy-shuttling techniques shown by Tesla and obtained U.S. Patents 5,486,833 and 5,493,691.

125. (a) A. A. Michelson and E. W. Morlcy, "Influence of motion of the medium on the velocity of light," *Am. J. Sci.,* Vol. 31, Series 3, 1886, p. 377-386; (b) — "The relative motion of the earth and the luminiferous aether," *Am. J. Sci.,* 34(3), 1887, p. 333; (c) — "On the relative motion of the earth and the luminiferous aether," *Phil. Mag.* 24(4), 1887, p. 449. See also (d) A. A. Michelson, "The relative motion of the earth and the ether," *Am. J. Sci.,* (4), 3, 1897, p. 475.

126. (a) Mendel Sachs, *General Relativity and Matter: A Spinor Field Theory from Fermis to Light-Years (Fundamental Theories of Physics),* Reidel, 1982. Sachs provides a great generalization of general relativity and electrodynamics reaching from the quarks and gluons to the entire universe. See also (b) Mendel Sachs, "Symmetry in Electrodynamics: From Special to General Relativity, Macro to Quantum Domains," in M. W. Evans, Editor, *Modern Nonlinear Optics,* Second Edition, Wiley, **New** York, 2001, Part 1, p. 677-706.

127. Myron W. Evans, Director of the Alpha Foundation's Institute for Advanced Study, private communication, 2001.

128. Jackson, {22}, p. 249.

129. Jackson, {22}, p. 28.

130. Feynman, {7}, Vol. 1, p. 2-4.

131. Physicists often speak of spacetime as "space", since in Minkowski geometry the time portion is modeled along a separate spatial axis used in addition to the ordinary three spatial axes. So Feynman's "distortion" is actually Riemannian spacetime curvature.

132. As an aside, note that Feynman also utilized a dipolarity. There is always a scalar potential between the poles of any dipole. Further, this "dipole potential" decomposes according to Whittaker's 1903 decomposition{85}, as re-interpreted by Bearden's giant negentropy approach {12} in 2000, and as relates to Mandl and Shaw's 1984/1993 argument{19} that only the associated time-polarized photon and longitudinal photon together are observable, and then as the instantaneous scalar potential. If we accept Mandl and Shaw's powerful argument, then the Whittaker 1903 decomposition must be reinterpreted to be in accordance. That is what was done by the present author {12} to resolve the source charge problem as well as the source dipole problem. In addition, the resolution must be in accord with the theoretical and experimental findings of particle physics, to include the broken symmetry of the opposite charges on the ends of a dipole. The giant negentropy process uncovered by Bearden {12} fulfills all the necessary requirements. It also places the theme of this book — *Energy from the Vacuum: Concepts and Principles* — on a solid theoretical and experimental basis.

133. Feynman, {7}, vol. II, p. 1-3.

134. Jackson, {22}, p. 811-812.

135. We have previously postulated this feature where one second is equal to spatial EM energy compressed by the factor c^2, so that time is just extremely compressed EM spatial energy. See Bearden, {17}.

136. (a) Harter et al., {102}. It may well be that galloping due to time-density variation may provide an alternative explanation to quantum tunneling, which can readily occur at superluminal speed. E.g., see (b) A Enders and G. Nimtz, *Phys. Rev. Lett.,* Vol. 48, 1993, p. 632. Their superluminal tunneling experiments transmitted 8.7 GHz microwaves (free space wavelength 3.4 cm) traveling in a rectangular waveguide that contains a "barrier" section of reduced dimensions. Mozart's 40th Symphony was transmitted through the barrier waveguide as frequency

modulated microwaves, at an FTL group velocity of 4.7c, receiving audibly recognizable music from the microwave photons that survived their barrier passage.

137. (a) M. W. Evans, "The Link Between the Sachs and 0(3) Theories of Electrodynamics," in M. W. Evans, editor, *Modern Nonlinear Optics,* Second Edition, Wiley, New York, 2001, Part 2, p. 469-494; (b) — "0(3) Electrodynamics," in M. W. Evans, editor, *Modern Nonlinear Optics,* Second Edition, Wiley, New York, 2001, Part 2, p. 79-267.

138. E.g., Ryder, {90b}, p. 147 *et seq.*

139. Rodrigues and Lu, {93a}.

140. Rodrigues and Vaz, {93b}.

141. The reader should recall that to this day there is no satisfactory resolution of the wave-particle duality principle. Physicists finally just shook hands and agreed to quit fighting, since the hullabaloo was getting them nowhere. The problem does have a probable resolution, but not in Aristotelian logic.

142. Bearden, {12} discusses the relation between time-energy and 3-spatial energy, and reveals a more fundamental 4-symmetry between time energy flow and spatial energy flow. In this 4-symmetry EM flow, time symmetry in energy flow is broken and simultaneously 3-space symmetry in energy flow is broken, but 4-symmetry in energy flow is maintained. The basic transduction of time-energy into 3-space energy and vice versa is accomplished by the interacting charge.

143. Bearden, {15}, p. 11. In the paper we also gave a force-free definition of mass, in terms of the transduction of angular momentum across the 3-spatial boundaries of a mass particle.

144. Rigorously, *mass* does not and cannot emit a photon; *masstime* does. But an observable mass m can be absorbing and emitting **enormous** numbers of virtual photons while not yet having absorbed another observable photon and decayed to emit an observable photons. Differential (virtual) pieces of a "frozen" observable mass m are **indeed** changing continually into masstime and back into mass, by absorbing and emitting virtual photons per equation [14b], while the observable mass m has not yet completed its absorption and emission of an observable **photon** This "knitting" together of observable and virtual state interactions is one of the great centralizing features of physics.

145. The problem is due to the hoary old erroneous notion in mechanics that a separate force acts upon a separate mass to move it.

146. There appears to be no paper or textbook which calculates the actual "energy magnitude" of an entire potential or an entire field, including over all space occupied by it. All texts advance the "local intensity" indicator calculation, and then call that the "magnitude of the potential". That is a non sequitur of first rank. A skilled electrodynamicist will call it the intensity of the potential.

147. It appears that the only region where this statement is in dispute is in various models attempting to explain the creation of the universe. Since that is *a priori* a creation event, then physicists struggle with explaining how something (the existing universe) was created out of nothing (the absence of any slightest bit of the existing universe). We will leave that debate to the astrophysicists and cosmologists. The "accursed identity of opposites" has been the bane of philosophers for more than 3,000 years.

148. Ibrahim Semiz, "Black hole as the ultimate energy source," *Am. J. Phys.,* 63(2), Feb. 1995, p. 151.

149. David Halliday and Robert Resnick, *Fundamentals ofPhysics,* *Thi*rd Edition Extended, Wiley, New York, 1988, Vol. 1, p. 518.

150. Stanley W. Angrist, "Perpetual Motion Machines," Sci. *Am.,* Vol. 2I8, Jan. 1968, p. 114-122.

151. Stanley W. Angrist, "Perpetual Motion," *Encyclopaedia Britannica,* Bicentennial Edition, Macropaedia Vol. 14, 1976, p. 102-105.

152. Lindsay and Margenau, {114}, p. 217.

153. Heaviside, {106}, p. 94.

154. Kraus, {76}, Figure 12-59, p. 578.

155. Bohren, {24}.

156. Paul and Fischer, {25}.

157. (a) V. S. Letokhov, "Laser Maxwell's Demon," *Contemp. Phys., 3*6(4), 1995, p. 235-243; (b) — "Generation of light by a scattering medium with negative resonance absorption," *Zh. Eksp. Teor. Fiz.,* Vol, 53. 1967, p. 1442 (English translation is in *Sov. Phys. JETP,* 26(4), Apr. 1968. p. 835-839); (c) "Stimulated emission of an ensemble of scattering particles with negative absorption," *ZhETF Plasma,* 5(8), Apr.

15, 1967, p. 262-265; (d) — "Double y - and optical resonance," *Phys. Lett. A,* Vol. 43, 1973, p. 179-180.

158. It is Heaviside's equations that are usually taught in University as "Maxwell's Equations," and labeled as Maxwell's equations in most undergraduate texts. In addition to Heaviside' work, similar changes were made by Gibbs in the United States and by Hertz in Europe. Every sophomore physics student and electrical engineering student should be given a short treatise on the background development of electrodynamics, and how, when, and by whom Maxwell's 20 quaternion equations were modified into the present four vector equations. The treatise should also point out what was omitted from Maxwell's theory in its truncations. It should be made very clear to every student that his elementary EM subject errs dramatically from physical reality when it assumes a flat local spacetime and an inert local vacuum. *By discarding the physically active environment of all Maxwellian systems,* only a highly limited subset of nature's electrodynamics is captured in the standard electrical engineering model. Specifically, systems far from equilibrium in their exchange with that environment are arbitrarily discarded. Those are precisely the Maxwellian systems permitted to exhibit coefficient of performance greater than unity. In short, the truncation of Maxwell's theory arbitrarily discarded all electrical windmills turning — or partially turning — in **a** free electrical wind.

159. As we pointed out, there are *tin electromagnetic systems at all in* that first class — and never have been — if we account for the arbitrarily-ignored Heaviside energy flow pouring from the source dipole and the energy flow pouring from every charge, and consider the situation prior to self-enforced implementation of Lorenz/Lorentz symmetrical regauging (by the closed current loop circuit). The remarks — pertaining to EM systems supposedly in equilibrium with the active vacuum — only apply if we neglect that Heaviside component and also neglect the source **charge** problem, and even then only if the circuit self-enforces that equilibrium in its exchange with the active vacuum. But since it has been so long **and** ubiquitously neglected, we will continue to speak of the "two classes" of EM systems from that "conventional" view. It is rather like our concession to electrical engineering, where the word "power" is universally **misused.** However, the reader should be aware of what we are doing and why.

160. See (a) Ilya Prigogine, *Nonequilibrium Statistical Mechanics,* Wiley-Interscience, New York, 1962; (b) — *From Being to **Becoming:***

Time and Complexity in the Physical Sciences, W. H. Freeman and Company, San Francisco, 1980; (c) D. Kondepudi and Ilya Prigogine, *Modern Thermodynamics: From Heat Engines to Dissipative Structures,* Wiley, Chichester, 1998; (d) G. Nicolis and I. Prigogine, *Self-Organization in Non-Equilibrium Systems: From Dissipative Structures to Order through Fluctuations,* Wiley, New York, 1977. For a good educated layperson's overview, see (e) Gregoire Nicolis, "Physics of far-from-equilibrium systems and self-organization," Chapter 11 in {f} Paul Davies, Ed., *The New Physics,* Cambridge University Press, Cambridge, 1989, p. 316-347.

161. Actually, Ludvig Valentin Lorenz first performed the equivalent of' symmetrical regauging of Maxwell's equations, only two years after Maxwell's seminal paper was published in 1865. See (a) Ludvig Valentin Lorenz, "On the identity of the vibrations of light with electrical currents," Phil. *Mag.,* Vol. 34, 1867, p. 287-301. Not much attention was paid to Lorenz's work, however, and the later symmetrical regauging of the Maxwell-Heaviside equations by H. A. Lorentz is what "stuck" and came to be used. For a proper historical discussion, see (b) J. D. Jackson and L. B. Okun, "Historical roots of gauge invariance," *Rev. Mod. Phys.,* Vol. 73, July 2001, p. 663-680.

162. This point is important. See Gabriel Kron, "The Frustrating Search for a Geometrical Model of Electrodynamic Networks," circa 1962. General Electric publication, p. 11-128. Quoting p. 114: *"...the missing concept of "open-paths" (the dual of "closed-paths") was discovered, in which currents could be made to flow in branches that lie between any set of* ***two*** *nodes. (Previously -following Maxwell - engineers tied all of their open-paths to a single datum-point, the 'ground'). That discovery of open-paths established a second rectangular transformation matrix... which cre**ated** 'lamellar' currents... " "A network with the simultaneous presence of both closed and open paths was the answer to the author's years-long search."*

When we design and build a circuit or system in compliance with the Lorenz/Lorentz-regauged equations, it follows that *the circuit itself must contain some feature and function that self-enforces the Lorenz/Lorentz condition — at least during the excitation discharge of the energy that has been freely caught by the circuit. The Lorenz/Lorentz condition is not a law of nature, nor is it automatically applied without a specific circuit cause and function physically applying it.* That function is automatically applied by the standard closed current loop circuit.

As Kron stated, his long search for a true negative resistance finally succeeded when he discovered the "open path". Actually Kron had discovered that any two points in the universe at different potentials (charged to different intensities) produced a flow of EM energy. In other words, he had discovered in more classical EM terms the broken symmetry of opposite charges of differing charges, such as on the ends of any dipole or across any dipolarity.

163. Superconducting *sections* in a system may be loss-free, but the entire superconducting *system* has losses and exhibits only COP<1.0 overall, if the refrigeration burden is accounted. In the superconducting section alone, without accounting for the cooling overhead, the COP = 1,0 and the efficiency is 100% also.

164. After Jackson, {22}, p. 219-221; 811-812.

165. See Whittaker, {85}. Whittaker mathematically decomposes the scalar potential into a hidden "bidirectional" series of EM wavepairs in a harmonic sequence. Each wavepair consists of the wave and its phase conjugate. Thus any Aq) (as across the terminals of a dipolar electrical power source) *a priori* involves an ordered, hidden, bidirectional EM wave flow. I.e., d(fi)) *identically is* such a hidden bidirectional EM energy flow.

166. But see Bearden, {12}. In the paper we conceptually re-interpreted Whittaker's 3-space (observation assumed, hence effect waves) bidirectional wavepairs. Our reinterpretation yields a correlated harmonic half-set of converging *unobserved* causal EM longitudinal waves (time-polarized EM waves) in the time domain prior to interaction with charge so as to prepare for being observed, and a harmonic half-set of diverging EM longitudinal waves (after observation due to the convergent time-polarized EM waves interacting with the observable charges) in 3-space in all directions. We strongly stress that observation does not occur without the absorption of a scalar photon and the follow-on emission of a longitudinal photon. In a time-reversed situation (phase conjugate charge condition), to the observer it appears to have happened in the other direction.

167. Particularly see Mandl and Shaw, {19}.

168. However, Mandl and Shaw fail to totally identify the "combining mechanism". They do not account the detailed interaction of the detecting/observing unit point charge, and thus fail to clearly account for the absorption of the incoming time-polarized wave or photon, the

transduction of that excitation energy of the charge into longitudinal EM wave/photon energy, and the subsequent emission of that excitation energy in 3-space in all directions as longitudinal EM waves/photons. So Mandl and Shaw do not clearly account for *photon (or wave) polarization transduction by the ubiquitously assumed charge.* The "causal" time-polarized EM wave or photon comes in and is absorbed by the detecting charge or dipole, then the absorbed energy is transduced and re-emitted in 3-space as the longitudinally polarized EM wave or photon in 3-space. (Actually, since all space is charged, what is really emitted into 3-space is the giant circulation of EM energy between time and 3-space, which is a more rigorous statement of what "propagation of EM energy through 3-space actually is). Recognition of these missing interactions and transductions allowed a solution at last to the long-vexing problem of the source charge, often called the greatest problem in both quantum and classical electrodynamics, as given initially in Bearden, {12}. Now, of course, a greater problem has reared its head: the notion that EM energy continuously propagates in 3-space is a total non sequitur, along the lines objected to by Romer {84}. We therefore have some very fundamental rethinking to do for all of classical physics. This is really where the problem of wave-particle duality has pointed since the beginning.

169. Asymmetrical self-regauging collects just a tiny bit more of the enormous energy that is flowing outside the conductors and usually wasted. E.g., if the self-regauging EM system collects as $\mathbf{j}\phi$ some 10^{-12} of the energy flow instead of the more usual 10^{-13}, the system can have a COP =10, *if it* does not then expend half the collected energy to destroy the sourcc dipole faster and require its reconstitution more energetically. And so on.

170. Jackson, {22}, p. 220-223.

171. So-called "canceling" opposing EM fields are actually produced, which sum to a *vector zero system* with respect to translation, which the electrodynamicists erroneously discard by assumption. We point out, but do not further pursue, that the locally produced *field energies* of the opposing fields in a zero-summed vector system remain and add, even though the fields offset each other *translationally.* The local energy of the field is proportional to the square of the local magnitude, and that is always positive regardless of field orientation. Thus "trapped" and structured EM stress energy has been localized in spacetime in the symmetrical regauging of CEM. This rigorously is a gravitational change

and therefore a local curvature of spacetime *a priori.* Indeed, the field energy remains in a zero-vector summation system, and has been changed into stress potential energy. It represents continuous internal work being performed on the system to stress it, by energy continuously fed in from the active vacuum environment but only in appositive fields of equal magnitude. The discarding of the zero vector summation system thus is a discarding of an available stress potential and its energy, a rotation of the system frame out of the laboratory frame, and a continuous exchange of energy from the vacuum that performs internal work upon the system but no external work in the load. The energy is not translational, but it is there nonetheless, and it causes a spacetime curvature change. The electrodynamicists have largely ignored the fact that gauge symmetry transformations are accompanied by local gravitational (spacetime curvature) changes that violate the prevailing flat local spacetime assumption of classical electrodynamics.

172. See (a) H. J. Josephs, "The Heaviside papers found at Paignton in 1957," *IEE Monograph No. 319,* Jan. 1959, p. 70-76. See also (b) E. R. Laithwaite, "Oliver Heaviside — Establishment Shaker," *Elec. Rev.,* 211(16), Nov. 12, 1982, p. 44-45. Heaviside became aware of this gravitational relationship, and worked out a draft theory of electrogravitation based on his energy-flow theory (which added nondiverged closed-loop circulations of energy which vectorially summed to net zero). Those "trapped EM energy flow loops" were *gravitational,* in Heaviside's concept. His hand-written notes on his eleelrogravitation theory were found long after his death, beneath the floorboards of his little garret apartment. In honor of Heaviside, we have nominated his huge nondiverged energy flow component — erroneously discarded by Lorentz — as the source of the extra gravity in the arms of the spiral galaxies, holding them together. In short, we have proposed that as the solution to the so-called "dark matter" problem.

173. Physicists love symmetry, turn to it at every opportunity, and will do almost any mathematical manipulation to obtain it, because they regard it as "beautiful." And so it is. Performing work, however, requires breaking symmetry to produce excess energy, which interacts with mass to produce a force, and then requires using that force to do the work. If we wish to build a system that produces more work output than the work that we ourselves have to do upon it to run it, then *a priori* that system must be *asymmetrical* and — to many physicists — *ugly.* Let us all drink a toast to more efficient *ugly* asymmetrical systems that also do not require **energy.**

input by the operator, but only by the active environment! Give us "ugly" electrical windmills that turn freely in electrical winds, rather than the inane "beautiful" present systems which destroy their energy winds faster than hey power their loads.

174. While Lorentz appears to have done it earlier, one can see his use of the surface integration in (a) Lorentz, {109}. In 1896 he also included it, using a more general theorem by Volterra, so that Poynting's theorem arises as a special case; see (b) H. A. Lorentz, *Versl. K. Akad. W. Amsterdam,* Vol. 4, 1896, p. 176.

175. This is usually performed by the source dipole.

176. Thus the long and tedious effort of my colleagues and I to create circuits that asymmetrically self-regauge their potential difference (source voltage) without allowing all the spent load current to pass back through the primary power source dipole and do work upon it to scatter the charges and destroy its dipolarity.

177. Again we strongly stress that asymmetrically regauging a potential in the system also regauges the local vacuum potential and the intensity of the vacuum potential's bidirectional EM energy exchange with the system. It alters the local curvature of spacetime. It directly alters the stored energy of the system and of the supersystem. See again Whittaker, {85}, to see this clearly. See particularly our use of the *supersystem* concept in Chapter 8, and as mentioned in Chapter 1 and the present Chapter 2.

178. Circuits and electrical power systems universally and routinely break Lorentz symmetry for *excitation* (potentialization) of the system at the initial onset. Just to potentialize a system in theory costs nothing, although it freely changes the potential energy of the system. The gauge freedom axiom of quantum field theory also guarantees that such change of the potential energy of the system is essentially "for free". It conclusively proves that (i) asymmetrical self-regauging exists and is done in electrical circuits, since the source dipole in the power supply accomplishes that initial self-regauging of the external circuit completely for free once the dipole is made, and (ii) the Maxwell-Heaviside equations do permit asymmetrical self-regauging, in violation of Lorentz's arbitrary condition prohibiting it.

179. This is the patent-pending Bedini process, which is processing through the U.S. Patent Office as we go to press.

180. Lee, {73}, p. 184.

181. B. P. Kosyakov, "Radiation in electrodynamics and in Yang-Mills theory," *Soviet. Phys. Usp.*, 35(2), Feb. 1992, p. 135-142. Quotes are from p. 135 and p. 141. Our proposed solution to the problem posed by Kosyakov (which is actually the broken symmetry of a charge) is that negative charges pour out positive energy and positive charges absorb positive energy. We "see" the positive charge as pouring out "reversed direction positive field energy" after we interact the energy with a laboratory charge to "observe". Considering the well-known polarization of the vacuum by any charge, one realizes that a 4-symmetry circulation of the EM energy is what is "emitted" and spreads throughout all space, since the vacuum polarization is also spreading. The actual energy flow is between the time domain and 3-space and return, at any elemental dipole in the polarization of the vacuum that is spreading.

182. Oliver Heaviside, *Electrical Papers,* Vol. 2, 1887, p. 94.

183. Prof. William Keel, quoted in James McWilliams, "Through a Galaxy, Darkly," *Huntsville (Alabama) Times,* May 14, 2000, p. A-18.

184. Charles Seife, "Peering Backward to the Cosmos's Fiery Birth," *Science,* vol. 292, June 22, 2001, p. 2238.

185. M. P. Silverman, *And Yet It Moves: Strange Systems and Subtle Questions in Physics,* Cambridge University Press, Cambridge, 1993, p. 127.

186. Matthew Colless, Australian National University, one of the survey team leaders in the project leading the world in mapping galaxies, Mar. 2001.

187. (a) Lee, {13a}; (b) Lee, Oehme and Yang, {13b};

188. Wuetal., {14}.

189. Bearden, {12}.

190. Mandl and Shaw, {19, 168}.

191. Whittaker, {85}.

192. Gabriel Kron, "Invisible dual (n-1) networks induced by electric 1-networks," *IEEE Trans, on Circuit Theory,* CT-12(4), Dec. 1965, p. 464-470.

193. Kron, {162}. The quote is from p. 114.

194. Steven Weinberg, *Dreams ofa Final Theory,* Vintage Books, Random House, 1993, p. 109-110.

195, See Josephs, {172a}. Heaviside's hand-written notes contained his theory of electro-gravitation, based on his theory of energy flow. The papers were found beneath the floorboards in his little garret apartment.

196. Laithwaite, {172b}. Laithwaite feels that Heaviside's postulation that a flux of gravitational energy combines with the (ExH) electromagnetic energy flux, could shake the foundations of physics. Extracting from Laithwaite; *"Heaviside had originally written the energy flow as S = (ExH) + G, where G is a circuitalflux. Poynting had only written S = (ExH). Taking p to be the density ofmatter and e the intensity of a gravitational force, Heaviside found that the circuital flux G can be expressed as pu -ce, where u represents the velocity of p and c is a constant. "*

197. Hence the title of cited reference {12} above.

198. Melvin H. Miles and Benjamin F. Bush, "Radiation measurements at China Lake: Real or Artifacts?", *Proc ICCF-7 (International Conference on Cold Fusion* — 7, Vancouver, BC, Canada, Apr. 1998, p. 101.

199. Bearden, {17}.

200. See P. V. Elyutin, "The Quantum Chaos Problem," *Sov. Phys. Usp..*Vol. 31, No. 7, 1988, p. 597-622. Elyutin discusses the crisis in quantum mechanics because of the missing chaos (hidden order). Quantum mechanics is known to be wrong unless this order can be found, because otherwise it does not predict the ordered macroscopic universe. Thus any proposed solution to the quantum chaos problem is worthy of Investigation, even if it turns out to be in error.

201. Unfortunately, entropy is one of those concepts in physics for which there are several differing major views. We consider entropy to be comparable to a positive resistor: organized energy goes in, disorganized energy comes out. Entropy is usually taken to be a measure of the disordering of energy. It does not *eliminate* the energy; it just makes it more difficult to *use* it. For our work in energy from the vacuum, we take the very simple view that a negentropic process is like a negative resistor: it receives energy in a form unusable to us, transforms it, and outputs it in

a form that is usable. In short, a negative resistor receives disordered energy and reorders it, so to speak. So it exhibits negentropy. We completely avoid the various notions of "information" and attempts to equate information and energy. We do point out, however, that a time-reversal process in one form or another is usually involved. In that sense, e.g., Newton's third law would be a negentropic process and involve time reversal in the mechanism generating the reaction-causing agent.

202. H. E. Puthoff, "Source of Vacuum Electromagnetic Zero-Point Energy," *Phys. Rev. A,* 40(9), Nov. 1, 1989, p. 4857-4862.

203. Whittaker, {91}. The paper was published in 1904 and orally delivered in 1903. This paper initiated superpotential theory.

204. As Whittaker showed in 1903, {85}, the scalar potential is actually a harmonic set of bidirectional EM longitudinal EM wavepairs, where each pair is composed of a longitudinal EM wave and its phase conjugate replica. Only because classical electrodynamicists have erroneously defined the field and potential as their own reaction cross sections with a unit point static charge, has the "static" potential been misidentified as a *scalar* entity, which it is not. The energy diverged from a uniform potential, around a fixed static point unit charge, is actually the set of divergences around the intercepting charge of the energy flows of all those EM waves comprising the potential. The sum total of all these individual wave divergences indeed has a scalar magnitude, but the magnitude of the total energy divergence from the potential is neither the potential itself nor its magnitude.

205. We point out the obvious: A "scalar" mass in 3-space actually him a time-vector since it moves through time continually, just to continue to exist. Further, it involves a special form of energy (energy compressed by c^2) which time is taken to be. Since we may choose any form of energy we wish by simple transduction, we may take it as compressed EM energy. So the mere continued existence of any mass proves conclusively that EM energy can and does ubiquitously flow to, from, and through the time dimension. The combined continued existence of numerous masses **proves** conclusively that the flow of time can have a myriad internal electromagnetic energy flows. An equilibrium between (i) an inflow of EM energy to a transducer from the time dimension, and (ii) an **outflow of** EM energy in 3-space from the transducer, will be seen as a discrete excitation (potential energy) associated with the transducer. Hence **the** notion of the charge. Every charge in the universe may be said to pour out

energy (negative charge pours out positive energy; positive charge absorbs positive energy — the equivalent of pouring out negative energy — and any charge results in a polarization of the vacuum. Hence what we call "spacetime" or "vacuum" is in fact a giant circulation of energy from the time domain to 3-space, and back to the time-domain. In short, a giant negentropy process continually sustains the active universe and all its components and processes.

206. Evans et al., {79}.

207. Semiz, {148}.

208. Weinberg, {194}, p. 286.

209. The available internal energy of a generator is the transduced shaft energy we input to it, say by turning the generator shaft with a steam turbine or hydro turbine. The shaft mechanical energy input is transduced into internal magnetic field energy once the rotor rotates. This internal magnetic energy is then dissipated on the internal charges inside the generator, forcing the positive charges in one direction and the negative charges in the other, thereby making the source dipole between the terminals of the generator. The available internal energy of a battery is the chemical energy possessed by it at any given time, and available for performing work on the internal charges to force them apart to form a dipole between the plates (and the battery terminals).

210. Kraus, {76}. Figure 12-60, a and b, p. 578 shows a good drawing of the Poynting (intercepted) energy flow being withdrawn into the conductors from the surrounding space. It does not show the Heaviside nondiverged component remaining, which is even larger, not diverged into the conductors, and wasted. The reason for the remaining Heaviside non-diverged component is that the electrons precess laterally across the conductor, thus withdrawing into the conductor only a small nearby section of the fields of the surface electrons — the ones (plus their fields extending into space) which intercept the impinging energy flow. Because of the short distance radially across the conductor's cross section, a surface electron has very limited "field and field energy withdrawal" length.

211. (a) J. D. Jackson, "Surface charges on circuit wires and resistors play three roles," *Am. J. Phys.*, 64(7), July 1996, p. 855-870. See also (b) Mark A. Heald, "Energy flow in circuits with Faraday emf," *Am. J. Phys., Vol.* 56, 1988, p. 540-547; (c) — "Electric fields and charges in elementary circuits," *Am J Phys.*, 52(6), June 1984, p. 522-526. The

surface charges in the conductors of a circuit are of enormous importance to the powering of the circuit.

212. See T. E. Bearden, "Energy Flow, Collection, and Dissipation in Overunity EM Devices," *Proc. 4th Internat. Energy Conf.*, Academy for New Energy, Denver, CO, May 23-27, 1997, p. 5-51. In Figure 5, p. 16 the fraction of the Poynting energy flow that is intercepted and collected by the circuit is roughly shown to be on the order of 10^{-13} of the entire Poynting energy flow available. That number is based on a very crude estimating procedure, but even if off by several orders of magnitude, it shows that the Heaviside nondiverged energy flow component is orders of magnitude greater than the diverged Poynting component, for single-pass of the energy and collection only once.

213. Rigorously, there is no *power* in an EM energy flow, regardless of how great in magnitude, if it is not altered in form or diverged. That is because "power" is rigorously the time rate of doing work (time rate of *changing the form* of energy), not the time rate of energy flow per se. Exactly, the Heaviside dark energy flow component was some 10 trillion joules per second in magnitude, but it had zero watts of power. Unfortunately, electrical engineers just loosely refer to nondiverged **energy** flow as "power", regardless of the non sequitur. Hence inane terms **widely** used in electrical engineering (and texts) such as "draw power from **the** source", etc. Rigorously, *the power* (rate at which energy is changed in form) is developed locally in each component having losses or performing work — i.e., changing the form of the energy.

214. (a) T. E. Bearden, "On the Principles of Permissible Over **Unity** EM Power Systems," *J. New Energy,* 4(2), Fall 1999, p. 16-39; (b) Bearden, {17}; (c) — "Use of Asymmetrical Regauging and Multivalued Potentials to Achieve Overunity Electromagnetic Engines," *J. New Energy,* 1(2), Summer 1996, p. 60-78; (d) — "Regauging and **Multivalued** Magnetic Scalar Potential: Master Overunity Mechanisms," *Explore,* 7(I), 1996, p. 51-58; (e) — "The Master Principle of EM Overunity and the Japanese Overunity Engines," *Infinite Energy,* 1(5&6), Nov. **1995-Feb,** 1996, p. 38-55; (f) — "Use of Regauging and multivalued Potentials to Achieve Overunity EM Engines: Concepts and Specific Engine Examples," *Proc. Internat. Sci. Conf, "New Ideas in Natural Sciences," St. Petersburg, Russia, June 17-22, 1996, Part I: Problems of Modern Physics,* 1996, p. 277-297.

215. In an oblique kind of sense, this is even "recognized" to some extent by leading electrodynamicists. E.g., quoting Jackson, {22}, p. 237: "*...the Poynting vector is arbitrary to the extent that the curl of any vector field can be added to it. Such an added term can, however, have no physical consequences.* " So Jackson follows Lorentz's lead that any additional non-intercepted and uncollected energy flow permissibly accompanying the Poynting intercepted and collected component, has no physical significance. Both Lorentz and Jackson err as to the *finality* of the statement. The accompanying Heaviside component can have no physical significance *unless it is intercepted and collected by means other than the single circuit or mechanism considered, and the single pass of the entire energy flow onto and past the receiving entity (circuit, charge, etc.).*

216. E.g., see Poynting, {4a. 4b}.

217. Heaviside, {5a}.

218. Heaviside, {5b}.

219. Heaviside, {5c}. Heaviside discusses the Faraday-Maxwell ether medium, outlines his vector algebra for analysis of vectors without quaternions, discusses magnetism, gives the EM equations in a moving medium, and gives the EM flux of energy in a stationary medium. On p. 443, he credits Poynting with being first to discover the formula for energy flow, with Heaviside himself independently discovering and interpreting this flow a little later by himself in an extended form.

220. J. H. Poynting, "On the connexion between electric current and the electric and magnetic inductions in the surrounding field," *Proc. Roy. Soc.* Lond. Vol. 38, 1984-85, p. 168.

221. Oliver Heaviside, *Electrical Papers,* Vol. 2, 1887, p. 94.

222. (a) T. E. Bearden, "On Extracting Electromagnetic Energy from the Vacuum," *Proc. IC-2000,* ibid., 2000; (b) Bearden, {38a}.

223. Lorentz is believed to have done this earlier (perhaps circa 1890s). In 1902 he published the method in a book, which strongly implies it was first done in an earlier paper. See Lorentz, {109}. Figure 25 on p. 185 shows the Lorentz concept of integrating the Poynting vector around a closed cylindrical surface surrounding a volumetric element. Many thanks to Marcus Reid for furnishing a copy of the actual Lorentz reference from a library in Leipzig, Germany.

224. E.g., see (a) Panofsky and Phillips, {110}; (b) W. Gough and J. P. G. Richards, *European J. Phys.*, Vol. 7, 1986, p. 195.

225. Panofsky and Phillips, {110}, p. 180.

226. D. S. Jones, *The Theory of Electromagnetism,* Pergamon Press, Oxford, 1964, p. 52.

227. Jackson, {22}, p. 237.

228. W. M. Schwarz, *Intermediate Electromagnetic Theory,* John Wiley & Sons, New York, 1964, p. 280-281.

229. Jones, {226}, p. 53.

230. For typical references, see (a) J. Slepian, *Am. J. Phys.*, 19, 87 (1951); (b) Mario lona, *ibid.*, 31, 398 (1963); (c) Udo Backhaus and Klaus Schafer, *ibid.*, 54, 279 (1986); (d) C. J. Carpenter, *IEE Proc. A* (UK), 136A(2), Mar. 1989, p. 55-65; (e) J. A. Ferreira, *IEEE Trans. Edit.*, 31 (4). 1988, p. 257-264; (f) Mark A. Heald,Am. *J. Phys.*, 56(6), 1988, p. 540-547. The debate has also appeared in many other leading journals, e.g., (G) T. H. Boyer, *Phys. Rev. D,* 25, 3246 (1982). Interestingly, (h) M. Abraham and R. Becker, *The Classical Theory of Electricity and Magnetism,* Blackie. London, 1932, p. 146 and p. 194 give two examples of the controversy over the Poynting vector. Finally, see (i) D. F. Nelson *Phys. Rev. Lett.*, 76(25), June 17, 1996, p. 4713-4716 for advanced **work** requiring a greater generalization of the Poynting vector.

231. Sweet and Bearden, {29a}. Sweet's device produced 500 watts lit a 33 microwatt input, which is approximately a COP = $1.5x10^6$. By steadily increasing the COP to $3x10^6$, the weight of the Sweet unit was reduced smoothly, reaching 90% reduction. The results of this highly successful anti-gravity experiment are reported in the paper. Unfortunately, Sweet later died and never fully revealed the activation secret by which barium ferrite magnetic materials could be triggered **into** strong self-oscillation at 60 Hertz or other ELF frequency.

232. Weaker self-oscillation of such permanent magnetic materials at higher frequency is known. E.g., see (a) V. S. L'vov, *Non-Linear Spin Waves,* Moscow, 1987; (b) L'vov, {29c}. See also (c) A. G. **Gurevich,** and G. A. Melkov, *Magnetization Oscillations and Waves,* CRC **Press,** Boca Raton, Florida, 1996. The latter authors give hundreds of **additional** references.

233. E.g., (a) M. W. Evans, P. K. Anastasovski, T. E. Bearden *et al,* "Derivation of the B(3) Field and Concomitant Vacuum Energy Density from the Sachs Theory of Electrodynamics," *Found. Phys. Lett.,* 14(6), Dec. 2001, p. 589-593; (b) — "Anti-Gravity Effects in the Sachs Theory ol Electrodynamics," *Found. Phys. Lett.,* 14(6), Dec. 2001, p. 601-605; (c) Evans et al., {38b}; (d) Evans et al., {38c}; (e) -- "Operator Derivation of the Gauge Invariant Proca and Eehnert Equation: Elimination of the Lorentz Condition," *Found. Phys.,* 39(7), 2000, p. 1123-1130; (f) - "O(3) Electrodynamics from the Irreducible Representations of the EInstein Group," 2001, *Found. Phys. Lett.,* 15(2), Apr. 2002, p. 179-187.; (g) - "Effect of Vacuum Energy on the Atomic Spectra," *Found. Phys.* Lett., 13(3), June 2000, p. 289-296; (h) Evans et al., {113b}; (i) Evans et aI., {113a}; (j) - "On the Representation of the Maxwell-Heaviside Equations in Terms of the Barut Field Four-Vector," *Optik* 111(6), 2000, p. 246-248; —"Derivation of the B(3) Field and Concomitant Vacuum Energy Density from the Sachs Theory of Electrodynamics," *Found. Phys. Lett.,* (in press); (k) — "The New Maxwell Electrodynamic Equations: New Tools for New Technologies. A Collection of 60 papers from the Alpha Foundation's Institute for Advanced Study. Published as a Special Issue of the *J. New Energy,* 4(3), Winter 1999. See also (1) Bearden, (222b}; (m) Bearden, {38a}; (n) Bearden, {43d}; (o) Bearden, {43a}; (p) Bearden, {30}; (q) Bearden, {40}; (r) Bearden {214}; (s) Bearden, {1214e}; (t) - "The Final Secret of Free Energy," *Magnets,* 7(5), May 1993, p. 4-26; (u) Bearden, {214f}.

234. Bearden, {40).

235. Terence W. Barrett and Dale M. Grimes, (a) Preface, p. vii-viii, in (b) *Advanced Electromagnetism: Foundations, Theory, and Applications,* Terence W. Barrett and Dale M. Grimes (eds.), World Scientific, Singapore, 1995.

236. I. Prigogine, "Irreversibility as a symmetry-breaking process." N*ature,* Vol. 246, Nov. 9, 1973, p. 67-71.

237. Paul Davies, *Superforce: The Search for a Grand Unified Theory of Nature,* Simon and Schuster, New York, 1984, p. 105.

238. Clarke, {55}, p. 38.

239. T. D. Lee, *Symmetries, Asymmetries, and the World of Particles,* U. Wash. Press, Seattle, 1988, p. 11.

240. That is, it does not exist *openly* in the open literature. Several inventors do have working laboratory COP>1.0 experiments, and at least three of them have models which could rapidly be developed into production systems — say, in one year or less. However, the exact and detailed construction details are understandably maintained as deeply proprietary by the inventors, until their intellectual property rights can be secured, including foreign patent rights. On the other hand, many other inventors mistakenly believe they have COP>1.0 systems, but do not because of instrumental error, considering nonsinusoidal waves as measurable with RMS meters, or effects covered in Chapter 6 which they do not comprehend. In addition, there have been those more interested in selling stock than in producing a working system.

241. But see Kawai, {31}. The only available *open* details approaching the "kit of parts and instructions" point is the Kawai process, and it will work just as in the patent if carefully built. If very efficient photon-coupled switching of the flux path is used for build-ups, and if very high efficiency (0.7 to 0.8) magnetic motors are modified with the Kawai process, one can expect the COP of the modified motors to be double the conventional efficiency of the original base motor. So one can obtain COP = 1.4 to 1.6, e.g., by using the necessary and available Hitachi high efficiency motors (one at 0.7 and the other at 0.8) to start with. Hitachi engineers physically tested two high efficiency Hitachi motors modified hy Kawai, at COP = 1.4 and COP = 1.6 respectively. Unfortunately, the Kawai process, engines, and company have been seized by what can **only** be described as the Yakuza (Japanese Mafia) and are being held off **the** market. The seizure was accomplished here in Huntsville, Alabama, witnessed by the CTEC board of directors and I, when Kawai and **CTEC** were in final negotiations to rapidly develop and market the Kawai **system** Several other COP>1.0 Japanese engines have also been seized and withheld by the Yakuza.

242. Jed Z. Buchwald, *From Maxwell to Microphysics,* University of Chicago Press, Chicago and London, 1985, p. 44.

243. Whittaker, {85}.

244. Bearden, {12}.

245. Mandl and Shaw, {19}.

246. Whittaker, {91a}.

247. To see how arduous a search Kron himself made prior to athieving a proper model for an electrical circuit, see Kron, {162}. The quote is from p. 114.

248. For example, Kron, {192}.

249. P. A. M. Dirac, "A theory of electrons and protons," *Proc. Roy. Soc. Lond. A*, 126(801), Jan. 1, 1930, p. 360-365. Here Dirac introduced the vacuum energy — the electron sea filled with electrons occupying negative energy states. The holes are treated today as the positive electrons. This concept is now referred to as the "Dirac Sea," and the concept has been expanded to include negative energy "holes" for other kinds of particles. Dirac first attempted to identify these holes with protons, until later the positron was discovered.

250. Evans, {137b}.

251. (a) Evans, {137a}; (b) — "The Link Between the Topological Theory of Ranada and Trueba, the Sachs Theory, and 0(3) Electrodynamics," *ibid.*, vol. 2, p. 495-499.

252. (a) Sachs, {126a). The Sachs theory provides a great generalization of general relativity and electrodynamics reaching from the quarks and gluons to the entire universe. See also (b) Sachs, {126b}.

253. Indeed, the symmetrizing of Maxwell's equations was first accomplished by Lorenz. See (a) Lorenz, {161a}. In this paper Lorenz gave essentially what today is called the Lorentz symmetrical regauging. AS pointed out by Barrett, the Lorenz paper gave f(t-r/c) functions. Fitzgerald said that Lorenz's functions were essentially the same as his, and Fitzgerald became a leading proponent of "retarded potentials". But it is believed that Fitzgerald was unaware of Lorenz's work until the 1880's, so he is given credit for parallel development. Some people speak of Fitzgerald-Lorenz functions. This is a regauging, but the term "gauge" (inspired by railroad gauges) was first introducec by Hermann Weyl in the 1900s. He used it for a change in length and was quickly countered by Einstein - Weyl's theory was not relativistic. The idea resurfaced in the 1920s when quantum theory was being formulated, but this time it meant "change in phase" and not "change in length". At any rate, when the renowned H. A. Lorentz performed the symmetrizing of the Maxwell-Heaviside equations in the 1880s. it was adopted immediately and has been rather universally applied since then. See also (b) Jackson and Okun {161b} for a history of gauge invariance.

254. (a) Prigogine, {160a}; (b) G. Nicolis and I. Prigogine, {160d}; (c) T. Petrosky and I. Prigogine, "Quantum Chaos, Complex Spectral Representation and Time-Symmetry Breaking," *Chaos, Solitons, and Fractals,* Vol. 4, 1994, p. 311-359; (d) D. Kondepudi and I. Prigogine, "Thermodynamics, Nonequilibrium," *Encyclopedia of Applied Physics,* Vol. 21, 1997, p. 311-337; (e) D. Kondepudi and I. Prigogine, *Modern Thermodynamics: From Heat Engines to Dissipative Structures,* Wiley, Chichester, 1998; (f) T. Petrosky and I. Prigogine, "Laws of Nature, Probability and Time Symmetry Breaking," *Physica A,* Vol. 263, 1999, p. 528-539.

255. (a) G. Nicolis, and I. Prigogine, *Exploring Complexity,* Piper, Munich. 1987; (b) — *Exploring Complexity: An Introduction,* Freeman, New York, 1989; (c) G. Nicolis, {160e}.

256. Letokhov, {157a-157d}.

257. Bohren, {24}.

258. Paul and Fischer, {25}.

259. E.g., see (a) Patrick et al., {37}. For rigorous explanations of **how** the energy is extracted from the vacuum, see (b) Evans et al., {38b}; (c) Evans et al., {38c}. The vacuum can and will furnish an electromagnetic "wind" from which useful EM energy can be extracted. Indeed, every source charge and dipole already extracts and continuously pours out EM energy from the vacuum, thereby establishing its fields and potentials **(and** their energy) across the universe.

260. A relationship between gamma bursters and a big bang is suggested from some recent observations. On Jan. 23, 1999 the Hubble Space Telescope caught an optical flash simultaneous with an initial gamma burst. When calculated, this burst was second in energy only to the big bang itself, and generated about 3.4 x 10^{54} ergs, which is the equivalent of converting two solar masses instantaneously into energy. There was also no polarization of the afterglow, which has been taken as evidence of beaming. However, such beaming could also be due to the beaming involved in the intense iterative phase conjugate reflections of the asymmetrical self-regauging process in intensely scattering, optically active, energy-amplifying media.

261. Heaviside, {5a-5c}.

262. Josephs, {172a}; Laithwaite, {172b}.

263. (a) Diederik Wiersma and Ad Lagendijk, "Laser Action in Very White Paint," *Physics World,* Jan. 1997, p. 33-37; (b) K. Totsuka, G. van Soest, T. Ito, A. Lagendijk, and M. Tomita, "Amplification and diffusion of spontaneous emission in strongly scattering medium,"*J. Appl. Phys.,* Vol. 87, 2000, p. 7623-7628.

264. (a) A. Lagendijk, J. Gomez Rivas, A. Imhof, and R. Sprik, "Propagation of light in disordered semiconductor materials," in *Photonic Crystals and Light Localization in the 21st Century,* edited by C. M. Soukoulis, Kluwer, Dordrecht, 2001, p. 447-473; (b) H. Cao *et at,* "Spatial Confinement of Laser Light in Active Random Media," *Phys. Rev. Lett., 8*4(24), 12 Jun. 2000, p. 5584-5587.

265. We also point out the possibility of the accumulator at each end being an intensely scattering, photoreactive, energy-amplifying material, a subject discussed a bit later in this chapter.

266. (a) Werner Triftshauser *et al, Phys. Rev. Lett.,* Vol. 87, 2001. An overview is given by (b) Philip Ball, "The Positron Probe," *Nature,* Vol. 412. Aug. 23, 2001, p. 764.

267. For example, see Letokhov, {157a-157d}.

268. Jackson, {22}, p. 363, third footnote.

269. Kraus, {10}, p. 4.

270. Marconi's patent is Gugliehno Marconi, "Transmitting Electrical Signals," U.S. Patent 586,193, July 2, 1897. Filed Dec. 7, 1896, with 56 claims. This patent was overturned in 1943 by the U.S. Supreme Court, and prior work by Nikola Tesla for transmission of EM signals was upheld. Most textbooks and journals, etc. to this day continue to falsely credit Marconi with discovery of the transmission of EM signals and thus the discovery of radio. This is not to discredit the important work that Marconi did; without him, signal transmission would have been much longer in coming.

271. United States Reports: Cases Adjudged in the Supreme Court of the United States, Vol. 320, Marconi Wireless Telegraph Co. of America vs. United States, June 21, 1943, p. 1-80. The U.S. Supreme Court ruled that Tesla's fundamental radio patents had anticipated all other contenders, including Marconi.

272. *Dictionary of Scientific and Technical Terms,* Daniel N. Lapedes (editor in chief), McGraw-Hill, New York, 1974, p. 300. On page 517 of the second and expanded edition (1978), the same definition of electric field appears and is unchanged.

273. H. J. Gray and Alan Isaacs, *A New Dictionary of Physics,* Longman, London, second edition, second impression, 1976.

274. Feynman, {7}, p. 2-4.

275. Feynman, {7}, p. 12-2.

276. P. K. L. Drude, *Ann. Physik,* Vol. 1, p. 566; Vol. 3, 1900, p. 370, 869. Here Drude first develops a theory of conductivity in a metal based on the assumption that there is a gas of free electrons in the metal. This gas of conduction electrons is often referred to as the "Drude gas." Note that this was shortly after J. J. Thomson's discovery of the electron in 1897.

277. E.g., see Jackson, {211a}.

278. Romer, {84}, endnote 24, p. 109.

279. H. Winfield Secor, "Tesla Maps Our Electrical Future."

280. Nikola Tesla, "Pioneer Radio Engineer Gives Views on Power," *New York Herald Tribune,* Sep. 11, 1932.

281. Nikola Tesla, "The True Wireless, *Electrical Experimenter,* May 1919.

282. Burford and Verner, {35a}. Quote is from p. 281.

283. That is, it does not exist *openly* in the open literature. Several inventors do have working laboratory COP>1.0 experiments, and at **least** three of them have models which could rapidly be developed into production systems — say, in one year or less.

284. But see Kawai, {31}.

285. Barrett, {124}.

286. (a) Terence W. Barrett, "Active Signalling [sic] Systems," U.S. Patent No. 5,486,833, Jan. 23, 1996; (b) — "Oscillator-Shuttle-Circuit (OSC) Networks for Conditioning Energy in Higher-Order Symmetry Algebraic Topological Forms and RF Phase Conjugation," U.S. Patent No. 5,493,691, Feb. 20, 1996.

287. No proper scientific treatise on the Moray device has ever been published, to our knowledge, nor has a proper theory of its operation been developed. Anecdotal material and some technical material is contained in (a) T. H. Moray, *The Sea ofEnergy,* 5th Edn., Salt Lake City, 1978 (foreword by T. E. Bearden). The fourth edition of the book, titled (b) *The Sea ofEnergy in Which the Earth Floats,* contains additional material but is long out of print. Additional information is given in (c) Keith Tutt, *The Search for Free Energy,* Simon & Schuster, 2001, p. 33-68. (d) Paul Brown's study of the Moray work is "The Moray Energy Device: Operational Parameters, Design Criteria, and Considerations," date unknown. Researcher and inventor Bruce Perreault has based much of his own work with his radiant energy valve on Moray's work. Perreault proposes a different interpretation. In the present book we have tried to point out the various aspects of the Moray device that resemble other presently known effects — most of which were still unknown in the 1920s and 1930s when Moray's fundamental work was accomplished.

288. Moray, {34b} "Electrotherapeutic Apparatus," U.S. Patent No. 2,460,707, Feb. 1, 1949. This patent clearly shows the complexity of the various special tubes containing his pellets that Moray developed.

289. H. *C.* Dake and Jack DeMent, *Fluorescent Light and Its Applications,* Chemical Publishing Company, Inc., Brooklyn, New York, 1941, p. 51-52 gives a succinct discussion of Stokes emission and anti-Stokes emission.

290. Sir G. G. Stokes, "On the Change of Refrangibility of Light," a memoir, 1852.

291 For example, in 1935 Prileshajewa showed that there is an energy difference involving as much as 1.1 V between the exciting light and the fluorescence of aniline vapor.

292. V. S. Letokhov, {157a-157d}.

293. Letokhov, *ibid.*

294. E.g., (a) R. N. Bhargava and D. Gallagher, "Optical Properties of Manganese-Doped Nanocrystals of ZnS," *The Am- Phys. Soc,* 72(3), Jan. 17, 1994; (b) I. A. Izmailov et al., "Generation of Stimulated Noncoherent Radiation in Light-Scattering Media Exhibiting Chemical Reactions," *Soy. J. Quantum Electronics,* 12(5), May. 1982, p. 588-594; (c) R. Pappalardo and A. Lempicki, "Brillouin and Rayleigh Scattering in Aprotic Laser

Solutions Containing neodymium," *J. Appl. Phys.,* Apr. 1992, p. 1699-1708.

295. (a) Nabil M. Lawandy *et al.,* " Laser action in strongly scattering media," *Nature,* Vol. 368, Mar. 31, 1994, p. 436-438. For a good lay article with color pictures, see (b) Ivars Peterson, "Boosted light: Laser action in white paint," *Science News,* 145(15), Apr. 9, 1994, p. 228-229. See also (c) P. Mandel, "Lasing without inversion: A useful concept?," *Contemp. Phys.,* Vol. 34, 1993, p. 335; (d) O Kocharovskaya, "Amplification and lasing without inversion," *Physics Reports,* Vol. 219, 1992, p. 175.

296. Some useful papers are: (a) Diederik S. Wiersma and Ad Lagendijk, "Light diffusion with gain and random lasers," *Phys. Rev. E,* 54(4), Oct. 1996, p. 4256-4265. The authors discuss experimental considerations for a medium that both multiply scatters and amplifies light, and distinguish three regimes; (b) H. Cao *et al.,* "Random Laser Action in Semiconductor Powder," *Phys. Rev. Lett.,* 82(11), 15 Mar. 1999, p. 2278 2281. The authors observed random laser emission in all directions, with coherent feedback, in semiconductor powder, (c) Diederik S. Wiersma, Meint P. van Albada and Ad Lagendijk, "Coherent Backscattering of Light from Amplifying Random Media," *Phys. Rev. Lett.,* 75(9), 28 Aug., **1995,** p. 1739-1742. (d) D. S. Wiersma, P. Bartolini, A. Lagendijk, and R. Righini, *Nature,* Vol. 390, 1997, p. 671. The authors report Anderson localization of photons in GaAs powder, (e) Ad Lagendijk *et al,* "Microscopic Approach to the Lorentz Cavity in Dielectrics," *Phys. Rev Lett.,* 79(4), 28 July 1997, p. 657-660. (f) Pedro de Vries and Ad Lagendijk, "Resonant Scattering and Spontaneous Emission in **Dielectrics** Microscopic Derivation of Local-Field Effects," *Phys. Rev. Lett.,* 81(7), 17 Aug. 1998, p. 1381-1384. (g) Gijs van Soest, Makoto Tomita, and Ad Lagendijk, "Amplifying volume in scattering media," *Opt. Lett.,* 24(5), Mar. 1, 1999, p. 306-308.

297. S. Itoh *et al.,* "Simulational and experimental studies on anomalous reflectivity of phase conjugate wave," *Ferroelectrics,* vol. 170, 1995, p. 209-217.

298. See (a) D. P. Hand and P. St. J. Russell, "Solitary thermal shock waves and optical damage in optical fibers," *IEE Colloquium on 'Non Linear Optical Waveguides', LEE Digest* No. 88, London, England, 1988, p. 101-103; (b) — "Soliton-like thermal shock-waves in optical fibres: origin of periodic damage tracks," *Fourteenth European Conference on*

Optical Communication (ECOC 1988), Sep. 11-15, 1988, Publication No. 292, 1(2), 1988, p. 111-114; (c) — "Solitary thermal shock waves and oplical damage in optical fibers: the fiber fuse," *Opt. Lett.,* 13(9), Sep. **1988,** p. 767-769; (d) D. P. Hand and T. A. Birks, "Single-mode tapers as 'fibre fuse' damage circuit-breakers," *Electronics Lett.,* 25(1), Jan. 5, 1989, p. 33-34. For an excellent lay description with photographs, see (e) Ivars Peterson, "Fibers with Flare," *Sci. News,* 140(13), Sep. 8, 1991, p. 200-201

299. P. St. J. Russell, "Power Conservation and Field Structures in Uniform Dielectric Gratings," *J. Opt. Soc. America A.,* 1(3), Mar. 3, 1984, p. 293-299. Russell is referring to apparent violation of local conservation of energy. It is true in the conventional flawed energy flow analysis considering only the Poynting component, because the fuse produces more work output (melting the holes) than the original operator's input of Poynting energy to initiate the fuse effect. It does not produce more work output than the total of the energy input by the operator in both the acounted Poynting component and the unaccounted Heaviside component. It merely shows that the extra fiber fuse ignition actions do absorb extra energy from the Heaviside component, perhaps by particle resonance (Bohren effect) of the melt and vapor particles. Also, intense heating produces intense ionization and thus intense dipoles, thus producing broken symmetry in the fierce exchange with the active vacuum. Multiple retroreflections of the EM energy flow also occur in the nmelt and vapor particles, leading to multiple collections in the ping-pong of a joule of energy between two particles as phase conjugate mirrors.

300. E.g., see (a) H. Kogelnik, "Coupled wave theory for thick hologram gratings," *Bell Systems Technical Journal,* Vol. 48, 1969, p. 2909-2947; (b) Z. Zylbergerg and E. Marom, "Rigorous coupled-wave analysis of pure reflection gratings," *J. Opt. Soc. Am.,* Vol. 71, 1981, p. 811-818; (c) — - "Rigorous coupled-wave analysis of grating diffraction — E- mode polarization and losses," *ibid.,* Vol. 73, 1983, p. 451-455; (d) - "Comments on analyses of reflection gratings," *ibid.,* Vol. 73, 1983, p. 399-401.

301. Bohren, {24J.

302. Justin Mullins, "Superpowerful Explosive Arrives with a Bang." New *Scientist,* Aug. 4, 2001.

303. Romano M. DeSantis *et al.*, "On the Analysis of Feedback Systems With a Multipower Open Loop Chain," Oct. 1973, AD 773188, available through the Defense Technical Information Center or the National Technical Information Center. The paper clearly shows that such systems can produce overunity coefficient of performance.

304. See (a) J. H. Andreatta, "High Power Switching Amplifier Wherein Energy is Transferred to a Tuned Circuit During Both Half Cycles," U.S. Patent No. 3,239,771, Mar. 8, 1966; (b) Tom L. Dennis Jr., "Highly Efficient Semiconductor Switching Amplifier," U.S. Patent No. 3,239,772, Mar. 8, 1966; (c) Heber J. Morrison, "Square Wave Driven Power Amplifier," U.S. Patent No. 3,815,030, June 4, 1974.

305. For a good but conventional coverage of many differential negative resistors and negative conductors, see Adolf Fritz Schwarz, "Negative Resistors and Negative Conductors," Doctoral Thesis, Technische Hogeschool, Delft (Netherlands), Feb. 1969, available from the U.S. National Technical Information Service (NTIS), Springfield, VA. True negative resistors are dismissed as impossible in Schwarz's opening remarks. And they *are* impossible in equilibrium systems not receiving and using any net excess energy asymmetrically from their environment, which are the only systems conventionally considered by electrical engineers and electrodynamicists.

306. Gabriel Kron, "Numerical solution of ordinary and partial differential equations by means of equivalent circuits." *J. Appl. Phys.*, Vol. 16, Mar. 1945a, p. 173.

307. Kron, {32}, p. 39.

308. Bearden, {12}.

309. E.g., see Gabriel Kron, "Equivalent Circuits for Oscillating Systems and the Riemann-Christoffel Curvature Tensor," *General Electric Review*, Jan. 1943, p. 25-31.

310. See (a) S. Austen Stigant, "Gabriel Kron on Tensor Analysis, A bibliographical record," *BEAMA Journal*, Aug. 1948, for a full bibliography of Kron's publications up to 1948. Also useful are (b) Gabriel Kron, "A Method to Solve Very Large Physical Systems in Easy Methods," *IRE Transactions on Circuit Theory*, 2(1), Dec. 1953, p. 71-90; (c) P. L. Alger, editor, *The Life and Times of Gabriel Kron, or Walking Around the World, and Tensors*, Mohawk Development Services, Inc.,

Schenectady, NY, 1969; (d) Banesh Hoffman, " Cron's Non-Riemannian Electrodynamics," *Rev. Mod. Phys.*, 21(3), 1949, *x* 535-540; (e) K. Kondo and Y. Ishizuka, "Recapitulation of the Geometrical Aspects of Gabriel Kron's Non-Riemannian Electrodynamics," Research Association of Applied Geometry, *Memoirs of the Unifying Study of Basic Problems in Engineering and Physical Sciences by Means of Geometry*, Gakujutsu Bunken Fukyu-kai, Tokyo, Vol. I, 1955, p. 185-239 [particularly see footnote 1, p. 222];

311. Wang and Chung, {33}.

312. Deborah D. L. Chung, "Superconductor-metal laminates and method of making," U.S. patent no. 5,059,582, issued Oct. 22, 1991. A superconducting laminate having at least one layer of metal and at least one layer of superconducting material. The metal layer and the superconducting layer are bonded. The layer may also include carbon fibers from various precursors. The superconductor may be a composite material. The invention also includes a method of making the laminates. Assigned to The Research Foundation of State University of NY, Albany, NY.

313. Jean-Louis Naudin, website http://jnaudin.free.fr/cnr/.

314. Fogal, {36a, 36b}.

315. As one example, Fogal's device has to be able to manipulate Dirac holes in the vacuum itself, at least to some extent. Once the erroneous flat spacetime assumption of classical electrodynamics is removed and curved local spacetime considered, we can and will have Dirac holes in the local vacuum itself, especially in COP»1.0 systems. In a COP»1.0 system, not all the Dirac holes have interacted with orbital electrons in atoms to "eat" an electron and produce a positive ion — with a "lattice hole" or "lattice positron" where the electron had been. There is a vast difference between a Dirac hole positron (which has a negative mass equal in magnitude to one electron-mass) and a lattice hole (which is attached to the relatively huge positive mass of the ionized atom. Hence the mobility and phenomenology of Dirac positrons and lattice positrons are very different. There presently are no books on the dynamics of the Dirac negative energy electron holes in COP»1.0 EM circuits and systems.

316. Mandl and Shaw, {19}.

317. Whittaker, {91a}. The paper was published in 1904 and orally delivered in 1903. Note: On p. 368 midpage, Whittaker's equation for the y-component of vector-potential "a" is missing the exponent "2" on the **del** operator.

318. Rodrigues and Lu, {93a}.

319. Rodrigues and Vaz, {93b}.

320. It is certainly not lacking in the secret military weapons game. Some 10 nations of the world have weaponized longitudinal EM wave weapons over the past few decades, and almost every major weapons laboratory in the world has now "discovered" longitudinal EM waves. Even the Yakuza (Japanese Mafia) has acquired its own portable longitudinal EM interferometry weapons.

321. Evans et al., {79}.

322. (a) V. I. Arkhipov, *et al.*, "Negative transient currents in amorphous semiconductors." *Internat. J. Electronics* (UK), 51(6), 1981, p, 735-742; (b) — and A. I. Rudenko, "Negative currents caused by injection-controlled polarization," *Solid. St. Commun.*, 28, 1978, p. 675-676.

323. Jackson, {22}, p. 222.

324. Jackson, {22}, p. 223.

325. O. L. Brill and B. Goodman, *Am. J. Phys.*, vol. 35, 1967, p. 832.

326. For example, see Jackson, {22}, p. 219-221.

327. We stress that electrodynamicists, conventional theory, and quantum field theory all assume the principle *of gauge freedom,* the **total** freedom to change the gauge (and therefore any potential) in a Maxwellian system at any time, without cost or work. In the real world one may have to pay a little switching costs, but by simply regauging one can freely change the EM energy physically present at a point in 3-space **occupied by** the Fogal "freed" instantaneous scalar potential, once the electrons are pinned. In short, the Fogal process is able to directly "gate" the instantaneous transduction of EM energy existing at multiple points **in** space, simultaneously. There is nothing in the gauge freedom **principle** that restricts (i) regauging the instantaneous scalar potential at will, **or** (ii) using these changes at a distance to produce force fields upon electrons, thereby moving them — so long as one employs a Fogal semiconductor in

the "distant receiver" in order to be able to produce the back-transition from the field-free state to the force-field state by removing the anomalous pinning restriction. To the advanced theorists, we leave the debates over causality considerations for this demonstrated process!

328. Whittaker, {85}.

329. (a) W. Heitman and G. Nimtz, "On Causality Proofs of Superluminal Barrier Transversal of Frequency Band Limited Wave Packets," *Phys. Lett. A196,* 1994, p. 154-158; (b) Enders and Nimtz, {136b}.

330. The reader should recall that the Lorenz/Lorentz condition, which limits the circuit to COP< 1.0, is self-applied by the circuit when it rams all "spent" electrons in the ground return line back through the emf of the circuit. One need not do that, and need not produce that force field that destroys the primary source dipole and its extraction of EM energy from the vacuum via its broken symmetry. As the reader has undoubtedly now observed, the "back-emf' and "back mmf are those aspects in an electrical circuit and magnetic circuit respectively, that kill the dipole and physically self-apply and self-enforce Lorenz/Lorentz symmetrical regauging. Hence the intuitive concern of COP>1.0 experimenters to try to discover how to avoid or lessen the "back emf or the "back mmf in their circuits and systems.

331. Philip Ball, "The positron probe," *Nature,* Vol. 412,23 Aug. 2001, p. 764.

332. Werner Triftshauser et al., *Phys. Rev. Lett.,* 87, 067402 (2001).

333. Bearden, {30}.

334. For the chemistry and currents of the battery, see any good battery reference, such as Colin A. Vincent and Bruno Scrosati, *Modern Batteries: An Introduction to Electrochemical Power Sources,* Second Edition. Wiley, New York, 1997.

335. (a) J. O'M. Bockris, A. K. N. Reddy, and M. Gamboa-Aldeco, *Modern Electrochemistry: Fundamentals of Electrodics,* 2nd edition. Kluwer/Plenum, NY 2000; (b) J. O'M. Bockris and A. K. N. Reddy, *Modern Electrochemistry: Electrodics in Chemistry, Engineering, Biology, and Environmental Science,* 2nd edition, Kluwer/Plenum, NY 2000; *(c)* J. Koryta, J. Dvorak, and L. Kavan, *Principles of Electrochemistry,* 2nd ed.. Wiley, NY, 1993; (d) Wolfgang .1. Lorenz and Waldfried Plieth,

Electrochemical Nanotechnology: In Situ Local Probe Techniques at Electrochemical Interfaces, Wiley, NY, 1998; (e) B. E. Conway, *Electrochemical Supercapacitors: Scientific Fundamentals and Technological Applications,* Plenum, NY, 1999; (f) Allen J. Bard and Larry R. Faulkner, *Electrochemical Methods: Fundamentals and Applications,* Second Edition, Wiley, NY, 2001.

336. At this writing, a provisional patent application on the process has been filed by Bedini and the present author. By the time of publication, hopefully this will have been turned into a formal patent application, with foreign patents also applied for.

337. Edwin V. Gray, "Pulsed Capacitor Discharge Electric Engine," U.S. Patent #3,890,548, June 17, 1975.

338. (a) Per Whittaker, {85}. However, see (b) Bearden, {12} for a necessary correction of Whittaker's interpretation to accord with a quantum field theory view of the instantaneous scalar potential. After observation, the phase conjugate EM wave half of the Whittaker wavepair is indeed going in the opposite direction to the normal longitudinal EM wave half But prior to observation, it exists in the time domain, and in the time domain it is precisely accompanying the 3-space longitudinal EM wave, with the absorbing and then emitting charge interacting in the middle between the two. See (c) Mandl and Shaw, {19}, to see that the combined scalar (time-polarized) photon and longitudinal photon are observable as the instantaneous scalar potential. This means that the corrected Whittaker decomposition produces an associated time-polarized EM wave in the time domain and longitudinal EM wave in 3-space. That is the corrected interpretation of Whittaker's phase conjugate longitudinal EM wavepair.

339. (a) J. O'M. Bockris, "Overpotential: a lacuna in scientific knowledge,"J. *Chem. Edu.,* 48(6), June 1971, p. 352-358. This is a simplified introduction to overpotential theory. The energy density that exists at minute "double layers" in contact, which act as tiny capacitors with extremely small separation of plates, is enormous and far greater **than** what the power engineer meets in his normal engineering practice. **Sec** also (b) Bockris and Reddy, {335b}, particularly Chapter I which deals with the overpotential. See also (c) Bockris et a1, {335a}.

340. E.g. see (a) L. Bertalot *et al.,* "Study of deuterium charging in palladium by the electrolysis of heavy water: heat excess production", *Nuovo Cimento,* Vol. 15 D, 1993, p. 1435; (b) J. O'M Bockris *et al.,* "Cold

fusion as a consequence of high fugacity among hydrogen isotopes," Intl. *J. Hydrogen Energy,* Vol. 17, 1992, p. 445.

341. Peter Lindemann, *The Free Energy Secrets of Cold Electricity,* **Clear** Tech Inc., Metaline Falls, WA, 2001.

342. Particularly see Kenneth S. Deffeyes, *Hubbert's Peak: The Impending World Oil Shortage,* Princeton University Press, Princeton, NJ, **2001.**

Quoting: *"Deffeyes finds that world oil production will peak within five wars and that there isn't anything we can do to stop it. New exploration and production technologies can't save us, and plans to open the Arctic National Wildlife Refuge and other areas to drilling offer no more than a small and soon-to-be-forgotten blip on the production curve. While long-term solutions exist in the form of conservation and alternative energy sources, they probably cannot — and almost certainly will not — be enacted in time to evade a short-term catastrophe of shortages, soaring prices, and global economic, agricultural, and possibly political disturbance. "* In short, Deffeyes rigorously demonstrates that a world energy crisis of staggering proportions is just around the corner.

343. D. J. Bohm and B. J. Hiley, "On the intuitive understanding of nonlocality as implied by quantum theory," *Found. Phys.,* 5(1), Mar. 1975, p. 93-109. Quote is from p. 107.

344. (a) Y. Aharonov and D. Bohm, "Significance of Electromagnetic **Potentials** in the Quantum Theory," *Phys. Rev.,* Second Series, 115(3), Aug. 1, 1959, p. 485; (b) — "Further Considerations on Electromagnetics In **the** Quantum Theory," Phys. Rev., 123(4), Aug. 15, 1961, p. 1511-1524.

345. Terence W. Barrett, "Electromagnetic Phenomena Not Explained by Maxwell's Equations," A. Lakhtakia, ed., *Essays on the Formal Aspects of Electromagnetics Theory,* World Scientific Publishing, River Edge, NJ, **1993,** p. 11 and generally p. 6-86.]

346. Davies, {237}, p. 105.

347. David J. Bohm, "A Suggested Interpretation of the Quantum **Theory** in Terms of 'Hidden' Variables, I and II." *Phys. Rev.,* 85(2), Jan. 15, 1952, p. 166-179 (Part I); 180-193 (Part II).

348. Jackson, {22}, p. 223.

349, Lamb and **Retherford,** {23}.

350. (a) Casimir, {26}. This paper is an extrapolation to two attracting plates of the more detailed paper of (b) H. B. G. Casimir and D. Polder, "The influence of retardation on the London-van der Waals Forces," *Phys Rev.* 73(4), Feb. 15, 1948, p. 360-372. Casimir's paper was an extension of earlier work by Verwey and Overbeek on the stability of colloidal systems, including the interaction of electric double layers; see (c) E. J. W Verwey, J. T. G. Overbeek, and K. van Nes, *Theory of the Stability of Lyophobic Colloids*, Elsevier, Amsterdam, 1948.

351. Lamoreaux, {27}.

352. Mead and Nachamkin, {28}.

353. E.g., see (a) P. W. Milonni. R. J. Cook and M. E. Goggin, "Radiation pressure from the vacuum: Physical interpretation of the Casimir force," *Phys. Rev. A,* Vol. 38, 1988, p. 1621; (b) C. E. Carlson, T. Goldman and J. Peres-Mercader, "Gamma-ray bursts, neutron star quakes, and the Casimir effect," *Europhys. Lett.*, Vol. 36, 1996, p. 637; (c) M. Chaichian *et ah,* "Quantum theories on noncommutative spaces with nontrivial topology: Aharonov-Bohm and Casimir effects," *Nucl Phys B.* Vol. 611, 2001, p. 383-402; (d) V. Dodonov, "Nonstationary Casimir Effect and Analytical Solutions for Quantum Fields in Cavities with Moving Boundaries," in *Modern Nonlinear Optics,* 2nd Edn., 3 vols., Wiley, 2001, Vol. 1, p. 309-384.

354. Bohm, {347}.

355. See T. E. Bearden, *Gravitobiology: A New Biophysics,* Tesla Book Co., Chula Vista, CA, 1991.

356. One should not be nonplussed at the notion of infinite velocity. A pure longitudinal EM wave is — at least in theory — capable of moving at infinite velocity, and is a proper solution to Maxwell's equations. See (a) Rodrigues and Lu, {93a}. Also, the ordinary potential in the Coulomh gauge does indeed move at infinite velocity; see Jackson, {22}, p. 223. In addition, Bohm's interpretation of quantum mechanics {347} uses the quantum potential, which instantaneously appears everywhere it will have magnitude.

357. Enders and Nimtz, {329b}.

358. R. Chen, "Cancellation of Internal Forces," *Am. J. Phys.,* 49(4), Apr. 1981, p. 372.

359. Whittaker, {85}.

360. R. L. Davis, "Non-Inductive Electrical Resistor," U.S. Patent No. 3,267,406, Aug. 16, 1966. Davis uses a Mobius-loop capacitor as an inductance-free resistor. Our comment is that, more rigorously, the resistor is *not* noninductive. It is "equally and oppositely inductive," which is quite a different thing altogether when one considers the difference between internal energy and external energy. We hypothesize that the "resistor" — or some version of it — produces an artificial scalar potential stress in spacetime — apparently varying the stress energy tensor itself— even though it produces a *net* zero reactance.

361. These are Brazil, Russia, China, and two other nations friendly to the U.S. The dominant weapons on earth today are quantum potential weapons, not nuclear weapons. The second most dominant weapons are probably the negative energy EMP weapons deployed by several nations, including China.

362. E.g., see (a) L. I. Mandelstam and N. D. Papaleksi, "On the parametric excitation of electric oscillations," *Zhurnal Teknicheskoy Fiziki,* 4(1), 1934, p. 5-29; (b) — "On resonance phenomena with frequency distribution." *Z.f. Phys.*, No. 72, 1931, p. 223: (c) — "Concerning asynchronous excitation of oscillations," *Zhurnal Tekhnicheskoi Fiziki,* 4(1), 1934; (d) — "Concerning asynchronous excitation of oscillations," *Zhurnal Tekhnicheskoi Fiziki,* 4(1), 1934; (e) —- "Concerning nonstationary processes occurring in the case of resonance phenomena of the second class," *Zhurnal Tekhnicheskoi Fiziki,* 4(1), 1934. See also (f) A. Andronov, "The limiting cycles of Poincare and the theory of self-maintained oscillations," *Comptes-Rendus,* Vol. 189, 1929, p. 559; (g) — and A. Witt, "On the mathematical theory of self-excitations," *Comptes-Rendus*, Vol. 190, 1930, p. 256; (h) — "On the mathematical theory of self-excitation systems with two degrees of freedom," *Zhurnal Tekhnicheskioi Fiziki,* 4(1), 193; (i) — "Discontinuous periodic movements and theory of multivibrators of Abraham and Bloch," *Bull. De l'Acad. Ed Sc. De l'URSS,* vol. 189, 1930. See (j) S. Chaikin, "Continuous and 'discontinuous' oscillations," *Zhurnal Prikladnoi Fiziki,* Vol. 7, 1930. p. 6; (k) — and A. Witt, "Drift in a case of small amplitudes," *Zhurnal Teknicheskoi Fiziki,* 1(5), 1931, p. 428; (1) — and N. Kaidanowski, "Mechanical relaxation oscillations," *Zhurnal Teknicheskoi Fiziki,* Vol. 3, 1933, p. 1.

363. L. Mandelstam [L. T. Mendel'shtam], N. Papalexi, A. Andronov, S. Chaikin and A. Witt, "Report on Recent Research on Nonlinear Oscillations," Translation of "Expose Des Recherches Recentes Sur Les Oscillations Non Lineaires," *Technical Physics of the USSR,* Leningrad, Vol. 2, 1935, p. 81-134 [NASA Translation Doc. TTF-12,678, Nov. 1969].

364. In Alexander L. Fradkov and Alexander Yu. Pogromsky, *Introduction to Control of Oscillations and Chaos,* World Scientific Series on Nonlinear Science E, Series Editor Leon O. Chua, World Scientific, New Jersey, 1998 — as a typical example — I found no mention of the Dirac hole current decay mechanism or of the active external environment (the active vacuum and its dynamics, and the active local curvatures of spacetime and their dynamics).

365. Richard E. Prange and Peter Strance, "The Semiconducting Vacuum," *Am. J. Phys.,* 52(1), Jan. 1984, p. 19-21.

366. John F. Lindner *et ah,* "Noise Enhanced Propagation," *Phys. Rev. Lett.,* 81(23), 7 Dec. 1998, p. 5048-5051. Lindner suggests that the mechanism appears to be general, in which case it could supply the mechanism that coherently "locks together" the barium nuclei self-oscillations in Sweet's activated barium ferrite magnets.

367. Owen Flynn, "Parametric arrays: A new concept for sonar," *Electronic Warfare Magazine,* June 1977, p. 107-112. Any two sine-wave frequencies as simultaneous drivers combine to produce a sine-wave difference frequency propagating in an isotropic nonlinear medium, essentially without sidebands or reverberations. Its pattern has a main lobe approximately equal to that of the high frequency drive, but devoid of sidelobes. The level of the propagating difference frequency is proportional to both the product of the two fundamental drive levels and to the square of the desired value of difference frequency.

368. M. I. Dykman *et al.,* "Noise-enhanced heterodyning in bistable systems." *Phys. Rev. E,* 49(3), Mar. 1994, p. 1935-1942

369. (a) V. S. L'vov and L. A. Prozorova, "Spin Waves Above the Threshold of Parametric Excitation," in (b) A. S. Borovik-Romanov and S. K. Sinha, Eds., *Spin Waves and Magnetic Excitations,* North-Holland, Amsterdam, 1988.

370. Gurevich and Melkov, {232c}. The authors treat high **frequency** processes, i.e., oscillations and waves, in magnetically ordered substances, including ferromagnetic and antiferromagnetic resonances, spin waves, nonlinear processes, and high frequency manifestations of **interactions** between the magnetic system and other systems of magnetically **ordered** substances (crystal lattice, charge carriers). The treatment is classical except that a quantum mechanical approach is used in the study of relaxation processes, which determine the energy losses of magnetic oscillations and waves. Experimental results but not techniques are included. Self-oscillation and self-oscillation criteria arc on p. 279.

371. (a) G. S. Kandaurova and A. E. Sviderskii, "Observation of autowave state and stable dynamic structures in multidomain magnetic films," *Sov. Tech. Phys. Lett.,* 14(5), May 1988, p. 346-347; (b) V. S. **L'vov,** {29c}.

372. Richard T. Hammond, "New fields in general relativity," *Contemp. Phys.,* 36(2), 1995, p. 103-114.

373. (a) J. Baugh et al., *Science,* Vol. 294, 16 Nov. 2001, p. 1505. For a simpler synopsis of the paper, see (b) Warren S. Warren, "Multidimensional Symmetry in a Three-Dimensional World," *Science,* Vol. 294, 16 Nov. 2001, p. 1475-1476.

374. E.g., see Howard R. Johnson, "Permanent Magnet Motor." U.S. Patent No. 4.151.431. Apr. 24. 1979.

375. Howard Johnson, private communication, January 2002.

376. In magnetics, multi-valued potentials (and hence the possibility **for** nonconservative fields) arise naturally in the theory, but are considered a nuisance to be eliminated or "averaged away" by magnetics engineers. E.g., see (a) Z. Ren, "A 3D vector potential formulation using edge element for electrostatic field computation," *IEEE Trans, on Magnetics,* **31(3),** May 1995, p. 1520-1523; (b) — "New technique for solving three-dimensional multiply connected eddy-current problems." *lEEProc, 1*37A(3), May 1990, p. 135-140; (c) J. C. Verite, "Calculation of multivalued potentials in exterior regions," *IEEE Trans, on Magnetics,* **Vol.** MAG-23(3), May 1987, p. 1881-1887. Amazingly, these and other similar methods are directed into converting the multivalued potential into single-valued regions by a process of multiple, highly selected cuts. In other words, the real attempt is to eliminate the multivalued aspect, in which case the theorists are in fact simply eliminating the asymmetrical

self-regauging provided by the multivalued potential and hence are discarding the ability to use multivalued potentials in true overunity processes.

377. (a) Z. Badics, "Transient eddy current field of current forced three-dimensional conductors," *IEEE Trans, on Magnetics,* 28(2), Mar. 1992, p. 1232-1234;(b) R. Albanese and G. Rubinacci, "Magnetostatic field computations in terms of two component vector potentials," *Int. J. for Numerical Methods in Engineering,* Vol. 29, 1990, p. 515-532; (c) Bearden, {214f}: (d) P. Hammond and T. D. Ssiboukis, "Dual finite-element calculations for static electric and magnetic fields," *IEE Proc. A,* 130(3), 1983, p. 105-111; (e) P. R. Kotiuga, "On making cuts for magnetic scalar potentials in multiply connected regions," *J. Appl. Phys.,* 61(8), 1987, p. 3916-3918; (f) J. Penman and J. R. Fraser, "Complementary and dual energy finite element principles in magnetostatics," *IEEE Trans, on Magnetics,* 18(2), 1982, p. 319-323; (g) E. A. Tolkachev and Ya. M. Shnir, "Non-trivial topology effects in the interaction of a monopole with a line current," *Phys. Lett. A,* 155(8, 9), May 27, 1991, p. 464-466.

378. (a) Feynman, {7}, Vol. II, Chapter 37; (b) T. Ambrose, R. L. Sommer, and C. *L.* Chien, "Angular Dependence of Exchange Coupling in Ferromagnetic/Antimagnetic Bilayers," *Phys. Rev. B,* Vol. 56, 1997, p. 83; (c) H. Sang, Y. W. Du, and C. L. Chien, "Exchange Coupling in $Fe_{50}Mn_{50}/Ni_{81}Fe_{19}$ Bilayers: Dependence on Antiferromagnetic Layer Thickness," *J. Appl. Phys.,* Vol. 85, 1999, p. 4931.

379. V. A. Tulin, "Nuclear Spin Waves in Magnets," *Fis. Niskikh Temp.,* Vol. 5, 1979, p. 965-993 [in Russian].

380. Sweet and Bearden, {29a}.

381. (a) Kenneth R. Shoulders, U.S. Patent # 5,153,901; (b) — "Energy Conversion Using High Charge Density," U.S. Patent # 5,018,180, May 21, 1991; (c) — "Energy Conversion using High Charge Density," U.S. Patent No. 5,123,039, 1992; (d) — U.S. Patents 5,054,046 and 5,054,047, 1991; (e) — "Circuits Responsive To and Controlling Charged Particles," U.S. Patent 5,148,461, 1992; (f) — and Steve Shoulders, "Observations on the Role of Charge Clusters in Nuclear Cluster Reactions," *J. New Energy,* 1(3), Fall 1996, p. 111-121.

382. (a) Paulo N. Correa and Alexandra N. Correa, "Pulsed Abnormal Glow Discharge Technology," *Infinite Energy,* 2(7), Mar./Apr. 1996, p.

18-21; (b) — "Other Applications of the PAGD Technology Besides Energy Conversion," *ibid.,* p. 22-27; (c)— "Electrochemical Transduction of Plasma Pulses," U.S. Patent No. 5,416,391, May 16, 1995; (d) "Energy Conversion Systems," U.S. Patent No. 5,449,989, Sept. 12, 1995; (e) — "Direct Current Energized Pulse Generator Utilizing Autogenous Cyclical Pulsed Abnormal Glow Discharges," U.S. Patent 5,502,354, Mar. 26, 1996.

383. In 1935, Prileshajewa showed that there is an energy difference as much as 1.1 v between the exciting light and the fluorescence of aniline vapor. This added energy is attributed to additions from the internal energy of the molecule. Thus, anti-Stokes emission has been validated as a COP>1.0 mechanism since at least 1935. For our purposes, replenishment of the internal energy of the molecule must be obtained from the local active vacuum; else one simply has the standard optical cooling process which cools the gas.

384. E.g., see J. K. Brasseur et al., "Coherent Anti-Stokes Emission in a Continuous Wave Raman Laser in H_2," carried on website location http://www.physics.montana.edu/optics/jlc/Anti-Stokes.pdf.

385. For a typical study, see J. Silver et al., "Studies on anti-Stokes emission from metal oxides (doped with Er3+ and Yb3+) stimulated by 632.8 nm laser excitation," *6th Int. Conf. Phosphors and Display Tech.,* San Diego, California, 2000.

386. For a typical paper of hundreds on the subject, see C. Zander and K. H. Drexhage, "Cooling of a Dye Solution by Anti-Stokes Fluorescence," in *Advances in Photochemistry,* edited by D. C. Neckers, D. H. Volman, and G. von Bulau; Wiley, New York, 1995.

387. (a) Antoine Priore, "Method of producing radiations for penetrating living cells," U.S. Patent No. 3,280,816, Oct. 25, 1966; (b) — "Apparatus for producing radiations penetrating living cells," U.S. Patent No. 3,368,155, Feb. 6, 1968. For an explanation, see (c) T. E. Bearden, "The Porthole Briefing," http://www.cheniere.org.

388. Thomas Valone, "Future Energy Technologies," *J. New Energy,* 5(2), Fall 2000, p. 41-46; summary is quoted from p. 44-45.

389. Shang-Xiang Jin and Hal Fox, "Characteristics of High-Density Charge Clusters: A Theoretical Model," *J. New Energy,* 1(4), Winter 1996, p. 5-20.

390. Shoulders, {381a-381e}.

391. Ken Shoulders, "Permittivity transitions," *J. New Energy,* 5(2), Fall 2000, p. 121-137.

392. *Ibid,* p. 122.

393. *Ibid,* p. 122.

394. K. Shoulders and S. Shoulders, {381 f).

395. Harold L. Fox, "Energy for the Future: High-Density Charge Clusters," *Modern Nonlinear Optics,* Second Edition, edited by M. W. Evans, Wiley, New York, 2001, Part III, p. 623-653.

396. See (a) Art Rosenblum, "Randell Mills — New Energy and the Cosmic Hydrino Sea," *Infinite Energy,* 3(17), Dec. 1997-1998, p. 21-34. Also see (b) Randell Lee Mills, "Energy/Matter Conversion Methods and Structures," Australian Patent No. 668678, Nov. 20, 1991. Particularly see (c) Eugene Mallove, "Dr. Randell Mills and the Power of BlackLight," *Infinite Energy,* 2(12), Jan.-Feb. 1997, p. 21, 35, 41.

397. Randell Mills *et al.,* "Lower-Energy Hydrogen Methods and Structure," U.S. Patent No. 6,024,935, Feb. 15, 2000. Some 60 pages, and an astounding 499 claims. For the patent, an independent verification was performed by Johannes Conrads, Institute for Low Temperature Plasma Physics at the Ernst Moritz Arndt University in Greifswald, Germany.

398. Randell L. Mills, "The Grand Unified Theory of Classical Quantum Mechanics," www.blacklightpower.com/book/shtml.

399. (a) Randell L. Mills et al., "Identification of Compounds Containing Novel Hydride Ions by Nuclear magnetic Resonance Spectroscopy"; (b) — "Spectroscopic Identification of Novel Catalytic-Reaction of Atomic Hydrogen and the Hydride Ion Products"; (c) — "Black Light Power Technology: A New Clean Energy Source with the Potential for Direct Conversion to Electricity," presented to the Intl. Conf. On Global Warming and Energy Policy, Nov. 26-28, 2000 and to the National Hydrogen Association Meeting, March 6-8, 2001; (d) — Plasma Power Source Based on a Catalytic Reaction of Atomic Hydrogen"; (e) R, M. Mayo and R. L. Mills, "Direct Plasmadynamic Conversion of **Plasma** Thermal Power to Electricity for Microdistributed Power Applications," *40th Ann. Power Sources Conf. Proc*, June 10-13, 2002; (f) R. Mills et al., "Novel Catalytic Reaction as a Potential New Energy Source," 223rd

ACS National Meeting, Orlando, Florida, Apr. 6-11, 2002; (g) — "Novel alkali and Alkaline Earth Hydrides for High Voltage and High Energy Density Batteries," *Proc. 17th Ann. Battery Conf. On Appl. And Advances, Calif. State Univ., Long Beach, CA, Jan. 15-18* (in press); (h) - "Synthesis of Diamond Films from Solid Carbon"; (i) Mills and Ray, "Spectral Emission of Fractional Quantum Energy Levels of Atomic Hydrogen from a Helium-Hydrogen Plasma and the Implications for Dark Matter," *Int. J. Hydrogen Energy,* 27(3), 2002, p. 301-322.

400. Peter D. Zimmerman, "An Analysis of Theoretical Flaws in So-Called Classical Quantum Mechanics and of Experimental Evidence against CQM," 2001.

401. Bearden, {222b}, p. 674.

402. E.g., it yields the excess deuterium, tritium, and alpha particles; see Bearden, {17}.

403. (a) Bearden, {222b}; Bearden, {15}.

404. (a) "Ion Cyclotron and Converter and Radio Power Microwave Generator," International Pub. No. WO 01/21300 A2, 29 March 2001; (b) "Ion Cyclotron Power Converter and Radio and Microwave Generator," International Pub. No. WO 01/22472, 29 March 2001. Both filed with World Intellectual Property Organization.

405. But see Samuel D. Harper. "The energy dissipated in a switch," *Am. J. Phys.,* 56(10), Oct. 1988, p. 866-889. Unless special attention and effort is paid, switches can indeed consume a great deal of energy! As Harper points out, it can be a substantial fraction of the energy transfer in the circuit. In a capacitive loaded circuit this is especially true. One should consider very efficient switching such as optically coupled switching arrangements.

406. (a) F. Heinrich, "Entropy change when charging a capacitor: A demonstration experiment," *Am. J. Phys.,* 54(8), 1986, p. 742-44. For an expanded discussion, see (b) I. Fundaun, C. Reese, and H. H. Soonpaa, "Charging a capacitor," *Am. J. Phys.,* 60(11), Nov. 1992, p. 1047-1048. Also see (c) Tyler A. Abbott and David J. Griffiths, "Acceleration without radiation." *Am. J. Phys.,* 53(12), Dec. 1985, p. 1203-1211. An extended charge can accelerate without radiating, under specified conditions.

407. (a) Davis, {360}. It would appear that a sine wave across this resistor may generate a **rhythmic** variation in what is called "internal

energy"; i.e., stress energy inside the system, hence stress energy in the associated vacuum. Since this is analogous to a sound wave consisting of rarefaction and expansion, it is a method of generating a longitudinal EM wave. This may also be involved also in the Fogal semiconductor. For a discussion of internal forces, which occur in equal and opposite pairs and are quite different from the resultant of forces, see (b) Chen, {358}, p. 372 and passim.

408. See Hsu-Chieh Yeh, "Remark on the second law of thermodynamics," *Am. J. Phys.,* 52(8), Aug. 1984, p. 720-723. As an example, from the common charge or dipole at constant temperature, we can indeed receive and take electrical energy because the charge (as a set of composite dipoles) and the dipole are not in 3-space energy flow equilibrium. Instead, they constantly receive virtual EM energy from the active vacuum, transduce it into 3-space EM energy, and continuously emit **that** energy in all directions — all at constant temperature. When we consider the supersystem of the charge-system and its environment, it is in disequilibrium and hence exhibits the effect pointed out by Yeh.

409. Yeh, {408}. Particularly see the illustration on p. 721.

410. Gabriel Laufer, "Work and heat in the light of (thermal and **laser**) light," Am. *J. Phys.,* Vol. 51, 1983, p. 42.

411. (a) Paulo N. Correa and Alexandra N. Correa, "A Modified Orgone Accumulator (HYBORAC) as a Drive for a Low Delta-T **Stirling** Engine, Part 1," *Infinite Energy,* 7(41), 2002, p. 23-29; (b) — "Orgone Accumulator Drive (HYBORAC) for Low Delta Stirling Motors, video presentation, ABRI Media Production.

412. Paulo N. Correa and Alexandra N. Correa, *Introduction to Experimental Aetherometry,* Vols. 1 and 2, 2001. Summaries of these **two** volumes may be freely downloaded from http://www.aetherometry.com

413. Paulo N. Correa and Alexandra N. Correa, "A Modified Orgone Accumulator (HYBORAC) as a Drive for a Low Delta-T Stirling **Engine** Part II." *Infinite Energy,* 7(42), 2002 (in press)

414. Eugene F. Mallove, "Demonstrating Aether Energy," *Infinite Energy,* 7(41), 2002, p. 6-8.

415. As quoted by Mallove, *ibid.,* p. 7.

416. Feynman, {7}, Vol. II, p. 1-3. Emphasis in original.

417. Mallove, {414}, p. 7.

418. J. M. Aguirregabiria, A. Hernandez, and M. Rivas, "Surface charges and energy flow in a ring rotating in a magnetic field." *Am. .J. Phys.,* 64(7), July 1996, p. 892-895.

419. F. Herrmann, "The unexpected path of the energy in a moving capacitor," *Am. J. Phys.,* 61(2), Feb. 1993, p. 119-121.

420. Wang and Chung, {33}.

421. Mike LaPointe, "Antimatter Production at a Potential Boundary," presented at the AIAA Joint Propulsion Conference, Breakthrough Propulsion Physics Session #1, July 9, 2001.

422. E.g., (a) Charles Kittel, *Introduction to Solid State Physics,* Seventh Edition, Wiley, New York, 1996 in various chapters contains excellent introductions to a more in-depth view of magnetic phenomena. A very useful book, written with clarity is (b) B. D. Cullity, *Introduction to Magnetic Materials,* Addison-Wesley, Reading, MA, 1972. For nuclear effects, (c) A. Abraham, *Nuclear Magnetism,* Oxford. 1961 is still excellent and quite comprehensive.

423. (a) Particularly see the lay overview by Philip Ball, "Meet the spin doctors...", *Nature,* Vol. 404, 2000, p. 918-920. This article deals with spin-injection from magnetic semiconductors. In addition to up and down, electron spin also has an additional degree of freedom called "color"; see (b) "Colourful electrons solve puzzle of ferromagnetism," *Physics World,* 14(7), July 2001; (c) also see the accompanying article by Fu Chun Zhang.

424. Stanislaw Bednarek, "Self-powered magnetohydrodynamic motors," *Am. J. Phys.,* 64(1), Jan. 1996, p. 90-92.

425. In a true superconducting system, it is possible to keep the current moving around in a resistance-free conductor indefinitely. However, no net work can be produced by the system, and in fact when one counts the energy one inputs to maintain the extremely low temperature of the environment, then to maintain the supersystem in such **"indefinite current** circulation" one has to continuously input energy to cool the **system. On** the other hand, an electron in an atom, orbiting the nucleus, is in **net** equilibrium on its path, so it will maintain its orbit indefinitely until perturbed sufficiently to break loose.

426. (a) Badics, {377a};(b) P. Hammond and J. Penman, "Calculation of inductance and capacitance by means of dual energy principles," *IEE Proc,* 123(6), 1976, p. 554-559; (c) Hammond and Ssiboukis, {377d}; (d) Yongzhong Huo, "A classification of thermodynamical potentials for two-variable transition systems," *Meccanica* [Netherlands], 30(5), Oct. 1995, p. 475.494; (e). Kotiuga, {377e}; (f) J. N. Murrell and S. Carter, "Approximate single-valued representations of multivalued potential energy surfaces," J. *Phys. Chem.,* 88(21), Oct. 11, 1984, p. 4887-4891; (g) Penman and Fraser, {377f}; (h) Ren, {376a}; (i) Z. Ren, "Solving 3D static field problems by dual formulations using potential variables," ***2nd** Int. Workshop on Elec. and Magn. Fields,* Leuven, Belgium, May 1994; (j) Ren, {376b}; (k) Verite, {376c}; (1) V. Vittal, "A generalized procedure to obtain first integrals for non-conservative dynamical systems: Application to power systems," *IEEE ISCAS '89,* 1989, p. 1984-1987.

427. G. W. O. Howe, "Effect of Torsion on a Longitudinally-Magnetized Iron Wire," *Wireless Engineer,* 29(344), May 1952, p. **115**-117.

428. Harry E. Burke, *Handbook of Magnetic Phenomena,* Van Nostrand, New York, 1985. This is a one-of-a-kind handbook on a great number of magnetic effects and phenomena.

429. Cullity, {422b}.

430. As examples: (a) Barrett, {345}; (b) Gurevich and Melkov, {232c}; (c) William Weltner, Jr., *Magnetic Atoms and Molecules,* Dover, Mineola, NY, 1989; (d) Giorgio Bertotti, *Hysteresis in Magnetism,* Academic Press, New York, 1998; (e) L'vov, {29c}; (f) Sidney Platt, *Magnetic Amplifiers: Theory and Application,* Prentice Hall, Englewood Cliffs, N.J., 1958; (g) Maciej J. Ogorzalek, *Chaos and Complexity in Nonlinear Electronic Circuits,* World Scientific, New Jersey, 1997; (h) Jammer, {lb}; (i) Borovik-Romanov and Sinha, Eds, {369b}; (j) Paul Davies, ed., {160f}; (k) G. I. Shipov, *A Theory of Physical Vacuum: A New Paradigm,* Moscow, 1994; (1) Nicolis and Prigogine, {255b}; (m) Richard Feynman, *Quantum Electrodynamics,* 1961, 1963; (n) V. 1. Fushchich and A. G. Nikitin, *Symmetries of Maxwell's Equations,* D, Reidel, 1987; (o) Mandl and Shaw, {19}; (p) M. W. Evans, Ed., ***Modern** Nonlinear Optics,* Second Edition, 3 vols., Wiley, 2001; (q) Robert C. O'Handley, *Modern Magnetic Materials: Principles and Applications,* Wiley, New York, 2000; (r) Sachs, {126a}.

431. As examples: (a) Lindsay and Margenau, {114}; (b) Richard P. Feynman, *The Character ofPhysical Law,* MIT Press, Cambridge, 1965:; (c) Feynman, {7}; (d) Ilya Prigogine, *The End ofCertainty: Time, Chaos, and the New Laws of Nature,* Free Press, New York, 1996, 1997; (e) Mendel Sachs, *Einstein Versus Bohr: The Continuing Controversies in Physics,* Open Court Publishing Company, 1988.

432. For those unfamiliar with magnetics and the exchange force(s), see H. J. Gray and Alan Isaacs, *A New Dictionary ofPhysics,* second edition, 1976 printing, *ibid.,* p. 194 for a precise definition. The force from the sudden exchange of charge is known as the *Heisenbergforce.* That due to the exchange of spin direction is known as the *Bartlettforce.* The force associated with exchange of both spin and charge is known as the *Majoramaforce.* Quoting: "These exchange forces may be interpreted as being due to the continual emission and absorption of virtual particles that carry the shared property from one particle to another. The exchange of virtual hadrons between interacting particles of the atomic nucleus is intimately involved in nuclear exchange forces.

433. Feynman, {7}, Vol. II, Chapter 37 covers magnetic materials including exchange forces, spins, and spin effects.

434. *The Encyclopedia ofPhysics,* Robert M. Besancon (editor), Second Edition, Van Nostrand Reinhold, New York, 1974, p. 518.

435. Cullity. {422b}. p. 132.

436. Kittel, {422a}, p. 443 (footnote 1).

437. Lindsay and Margenau, {114}, p. 216-217.

438. *Ibid.,* p. 213.

439. *Ibid.,* p. 215.

440. *Ibid.,* p. 214.

441. T. D. Lee, "Space Inversion, Time Reversal and Particle-Antiparticle Conjugation," *Physics Today,* 19(3), Mar. 1966, p. 23.

442. Lee, {73}, p. 187-188.

443. Romer, {84}.

444. Kenneth D. Moore, "Testing of a Johnson Magnetic Gate," *Explore,* 9(6), 2000, p. 70-75. Also available on www.cheniere.org.

445. (a) Raymond J. Radus and William G. Evans, "Apparatus Responsive to Direct Quantities," U.S. Patent #2,892,155, Jun. 23, 1959; (b) R. J. Radus, "Permanent-Magnet Circuit using a 'Flux-Transfer' principle," *Engineers' Digest,* 24(6), June 1963, p. 86; (c) (anon.), "On-Off Permanent Magnet with a Memory," *Electronic Equipment Engineering,* 11(4), Apr. 1963, p. 22, 26.

446. "Human fly has magnetic sole," *Electrical Engineering,* Apr. 1963, p. 294.

447. Malcolm McCaid, *Attraction and Repulsion,* Oliver and Boyd Ltd., 1967 has an entire chapter on switching magnets, and has two photos of an engineer hanging upside down and walking on the underside of an elevated steel beam, wearing the Radus magnetic boots.

448. For a description of "shuffler" boots, see A. W. Hangar and A. A. Rosener, "The use of permanent magnets in zero-gravity mobility and restraint 'footware' concept," *IEEE Trans, on Magnetics,* Vol. MAG-6, No. 3, Sep. 1970, p. 464-467. These crude shuffler boots are quite a contrast to the elegant Westinghouse/Radus stepping boots earlier developed and used.

449. Burke, {428}.

450. David Scott, "Magnetic "Wankel" for electric cars," *Popular Science,* June 1979, p. 90-91.

451. E.g., (a) John R. Wiegand, "Bistable Magnetic Device," U.S. Patent No. 3,820,090, June 25, 1974; (b) — "Asymmetric Bistable Magnetic Device," U.S. Patent No. 3,866,193, Feb. 11, 1975; (c) - "Pulse Generation by Changing Magnetic Field," U.S. Patent No. 4,309,628, Jan. 5, 1982; (d) — "Pulse Generator Using Read Head with Wiegand Wire," U.S. Patent No. 4,263,523, April 21, 1981; (e) - "Switchable Magnetic Device;" U.S. Patent No. 4,247,601, Jan. 27, 1981; (f) — "Method of Manufacturing Bistable Magnetic Device," U.S. Patent No. 3,892,118, July 1, 1975; (g) — "Multiple Pulse Generator;" U.S. Patent No. 3,793,532, Feb. 19, 1974; (h) — and John E. Opie, "Pulse Generator with Shaped Magnetic Field," U.S. Patent No. 4,484,090. Nov 20, 1984.

452. Kawai, {31}.

453. John C. Bedini, "Device and Method of a Back EMF Permanent Electromagnetic Motor Generator," U.S. Patent No. 6,392,370, May 21.

2002. Uses a regauging process for capturing available back **EMF** electromagnetic energy in the system. The available energy may be captured and used to re-energize the battery, and/or sent in another direction to be used as useful work, or dissipated in the system.

454. See {445c}, p. 22, 26. Quoting: *"The circuit differs from ordinary permanent magnets in three ways: (I) It exerts strong magnetic force at one end while exerting hardly any at the other, (2) the strong and weak magnetic poles can be switched end-for-end easily and at will, thus in effect turning the magnetism on and off, and (3) it remembers its direction of greatest magnetic pull indefinitely. "*

455. Burke, {428}, p. 250.

456. Deffeyes, {342}.

457. Stuart Young, *Nature*, Vol. 414, 29 Nov. 2001, p. 487.

458. Evans, {137b}, p. 84.

459. M. W. Evans and S. Jeffers, "The Present Status of the Quantum Theory of Light," in *Modern Nonlinear Optics,* Second Edition, 3 Vols., edited by M. W. Evans, Wiley, 2001, Vol. 3, p. 150.

460. Clarke, {55}, p. 38.

461. Patrick, Bearden, Hayes, Moore, and Kenny, {37}. A second patent is pending, and two more are in preparation.

462. Bearden, {222b}.

463. Evans etal, {38b, 38c}.

464. T. E. Bearden, James C. Hayes, James L. Kenny, Kenneth D. Moore, and Stephen L. Patrick, "The Motionless Electromagnetic Generator: Extracting Energy from a Permanent Magnet with Energy-Replenishing from the Active Vacuum," Sept. 2000, carried on restricted DoE website http://www.ott.doe.gov/electromagnetic/. A search on the internet will turn up other sources where the paper can be downloaded.

465. (a) Evans et al., "The Aharonov-Bohm Effect as the Basis of Electromagnetic Energy Inherent in the Vacuum," *Found. Phys. Lett.,* 2002, (in review); (b) — "Derivation of the B(3) Field and Concomitant Vacuum Energy Density from the Sachs Theory of Electrodynamics," ***Found.*** *Phys. Lett.,* 14(6), Dec. 2001, p. 589-593; (c) — "Operator Derivation of the **Gauge** Invariant **Proca** and Lehnert Equations:

Elimination of the Lorenz Condition," *Found. Phys.,* 30(7), 2000, p. 1123-1130; (d) — "Runaway Solutions of the Lehnert Equations: The Possibility of Extracting Energy from the Vacuum," *Optik,* 111(9), 2000, p. 407-409; (e) — "The Effect of Vacuum Energy on the Atomic Spectra," *Found. Phys. Lett,* 13(3), June 2000, p. 289-296; (f) Evans et al., {113}; (g) — "Derivation of the Lehnert Field Equations for Gauge Theory in Vacuum: Space Charge and Current," *Found. Phys. Lett.,* 13(2), Apr. 2000, p. 179-184;(h)Bearden, {222b}.

466. Details are on Jean-Louis Naudin's website, in the section dealing with the MEG, which is http://jnaudin.free.fr/html/megv21.htm#megstat.

467. For an introduction to the field and its literature, see J. Anandan, J. Christian, and K. Wanelik, "Resource letter GPP-1: Geometric phases in physics," *Am. J. Phys.,* Vol. 65, 1977, p. 180-185.

468. A discussion by Feynman of the Aharonov-Bohm effect is given in Feynman, {7}, "15-5: The vector potential and quantum mechanics," p. 15-8 to 15-14.

469. A similar phase change also is induced outside the localized presence of an electrostatic scalar potential fi. See Feynman, {7}, p. 15-10. Quoting: *"...the effect of an electrostatic field is to produce a phase change given by the negative of the time integral of the scalar potential fi"*

470. Ya. M. Blanter, C. Bruder, R. Fazio, and H. Schoeller, "Aharonov Bohm-type Oscillations of Thermopower in a Quantum-dot Ring," *Phys Rev. B,* Vol. 55, 1997, p. 4069 typify the kind of "power" considerations that have been analyzed in the past. Only a minuscule thermopower treatment is considered.

471. S. Pancharatnam, "Generalized theory of interference, and its applications," *Proc. Indian Ac ad. Sci.,* Vol. A44, 1956, p. 247-262.

472. See Nahin, {62}, p. 225. Quoting: *"J. J. Waterston's paper on the kinetic theory of gases, in 1845, was rejected by the Royal Society of London. One of the referees declared it to be 'nothing but nonsense,* ***unfit*** *even for reading before the Society.'... "Waterston's dusty manuscript was finally exhumed from its archival tomb forty years later, because of the efforts of Lord Rayleigh... "*

473. Aharonov and Bohm, {344a, 344b}.

474. R. G. Chambers, "Shift of an electron interference **pattern** by enclosed magnetic flux," *Phys. Rev. Lett.*, Vol. 5, July I960, p. 3-5.

475. A. Tonomura *et al,* "Observation of Aharonov-Bohm effect by electron holography," *Phys. Rev. Lett.,* Vol. 48, 1982, p. 1443-1446.

476. A. Tonomura *et al.,* "Evidence for Aharonov-Bohm effect with magnetic field completely shielded from electron wave," *Phys. Rev. Lett.,* Vol. 56, 1986, p. 792-795. In the latter paper, the magnetic fields were completely and painstakingly shielded from the electron wave in a very careful experiment. The experiment demonstrated the expected relative phase shift as well as direct evidence for flux quantization. This was a definitive experiment clearly proving the Aharonov-Bohm effect. In 1999, Tonomura was awarded the Franklin Institute Award for this definitive proof of the Aharonov-Bohm effect.

477. M. V. Berry, *Proc. R. Soc. Lond. A,* Vol. 392, 1984, p. 45.

478. R. A. Webb, S. Washburn, C. P. Umbach, and R. B. Laibowitz, "Observation of h/e Aharonov-Bohm oscillations in normal-metal rings," *Phys. Rev. Lett,* Vol. 54, 1985, p. 2696-2695.

479. B. Schwarzschild, "Currents in Normal-Metal Rings Exhibit Aharonov-Bohm Effect," *Phys. Today,* Vol. 39, Jan. 1986, p. 17-20.

480. Y. Aharonov and J. Anandan, "Phase change during a cyclic quantum evolution," *Phys. Rev. Lett.,* Vol. 58, 1987, p. 1593-1596.

481. (a) V. Chandrasekhar *et al., Phys. Rev. Lett.,* Vol. 55, 1985, p. 1610; (b) S. Datta *et al., Phys. Rev. Lett,* Vol. 55, 1985, p. 2344; (c) S. N. M. Ruijsenaars, "The Aharonov-Bohm Effect and Scattering Theory," *Ann. Phys.,* Vol. 146, 1983, p. 1-34.

482. S. Olariu and I. Iovitzu Popescu, "The Quantum Effects of Electromagnetic Fluxes," *Rev. Mod. Phys.,* 57(2), Apr. 1985, p. 339-436.

483. (a) R. Bhandari, "Polarization of light and topological phases," *Phys. Reps.,* Vol. 281, 1997, p. 1-64; (b) — and J. Samuel, "Observation of lopological phase by use of a laser interferometer," *Phys. Rev. Lett.,* Vol. 60, 1988, p. 1211-1213; (c) R. Y. Chiao et *al.,* "Observation of a lopological phase by means of a Mach-Zehnder interferometer," *Phys. Rev. Lett,* Vol. 60, 1988, p. 1214-1217; (d) T. Bitter and D. Dubbers, "Manifestation of Berry topological phase in neutron spin rotation," *Phys. Rev. Lett,* Vol. 59, 1987, p. 251-254; (e) Y. Hascgawa *et al.,* "Geometric

phase in coupled neutron interference loops," *Phys. Rev. A.,* Vol. 53, 1996, p. 2486-2492; (f) A. G. Wagh *et al.,* "Experimental separation of geometric and dynamical phases using neutron interferometry," *Phys. Rev. Lett.,* Vol. 78, 1997, p. 755-759; (g) D. Suter, K. T. Mueller, and A. Pines, "Study of the Aharonov-Anandan quantum phase by NMR interferometry," *Phys. Rev. Lett.,* Vol. 60, 1988, p. 1218-1220; (h) D. Loss and P. M. Goldbart, "Persistent currents from Berry's phase in Mesoscopic systems," *Phys. Rev. B,* Vol. 45, 1992, p. 13544-13561; (i) C. A. Mead, "The geometric phase in molecular systems," *Rev. Mod. Phys.,* Vol. 64, 1992, p. 51-85; (j) J. H. Hannay, "Angle variable holonomy in adiabatic excursion of an integrable Hamiltonian," *J. Phys. A.,* Vol. 18, 1985, p. 221-230; (k) Y. Aharonov et al., "Aharonov-Bohm Type Forces Between Magnetic Fluxons," Hewlett Packard Report HPL-BR1MS-97-24, Oct. 1997.

484. (a) F. V. Gubarev and V. I. Zakharov, "The Berry Phase and Monopoles in Non-Abelian Gauge Theories," *Internat. J. Mod. Phys. A,* Vol. 17, 2002, p. 157-174; (b) J. M. Robbins, "Topological Phase Effects," Hewlett-Packard Labs Technical Report HPL-BRIMS-97-03, Jan. 31, 1997; (c) E. Sjoqvist, "Anandan-Aharonov-Casher oscillations in a simply connected region, *Phys. Lett. A.,* Vol. 270, 2000, p. 10; (d) E. Sjoqvist et al., "Geometric phases for mixed states in interferometry," *Phys. Rev. Lett.,* Vol. 85, 2000, p. 2845; (e) D. J. Thouless, *Topological Quantum Numbers in Nonrelativistic Physics,* World Scientific, Singapore, 1998; (f) J. Mickelsson, "Vacuum Polarization and the Geometric Phase: Gauge Invariance," *J. Math. Phys.,* Vol. 39, 1998, p. 831-837; (g) W. T. Lee *at al.,* "Scalar Aharonov-Bohm Effect with Longitudinally Polarized Neutrons," *Physica B,* Vol. 241-243, 1998, p. 216; (h) A. Cimmino et al., "High Precision Measurement of the Topological Aharonov-Casher Effect with Neutrons," *Nuclear Instr. and Methods A,* Vol. 440, 2000, p. 579; (i) Ali Mostafazadeh, *Dynamical Invariants, Adiabatic Approximation and the Geometric Phase,* Nova Science, 2001.

485. E.g., see (a) M. W. Evans and L. B. Crowell, *Classical and Quantum Electrodynamics and the B(3) Field,* World Scientific, Singapore, 2001; (b) M. W. Evans, *0(3) Electrodynamics,* Vol. V *of The Enigmatic Photon,* Kluwer, Dordrecht, 1999.

486. Bearden, {12}.

487. Fradkov and Pogromsky, {364}. The quote is from p. 359-360.

488. (a) Bearden, {38a}, (b) Bearden *et al., {*464}, (c) Evans et al., {38b}, (d) Evans et al., {38c},

489. Seife, {184}.

490. I. J. R. Aitchison, "Nothing's Plenty: The Vacuum in Modern Quantum Field Theory," *Contemp. Phys.,* 26(4), 1985, p. 339, 360.

491. *Ibid.,* p. 372.

492. Robert Neill Boyd, "Black Holes and Negative Energy", carried on Internet website http://www.rialian.com/rnboyd'blackholcs-negative.htm.

493. Roger Penrose, *The Emperor's New Mind.* Penguin Books, 1991, p. 210.

494. Stephen Hawking, per Zebrowski, {2}.

495. Isaac Newton, *Philosophiae Naturalis Principia Mathematica,* 1687.

496. Quoted from D. W. G. Ballentine and D. R. Lovett, *A Dictionary ofNamed Effects and Laws in Chemistry, Physics, and Mathematics,* Fourth Edition, Chapman and Hall, New York, 1980. p. 227.

497. Dirac, {249}.

498. See also (a) P.A.M. Dirac. "The quantun theory of the electron," P*roc. Roy. Soc. Lond. A,* 117(777), Jan. 2, 1928. p. 610-624; (b) — "The quantum theory of the electron, Part II," *ibid.,* 118 (779), Mar. 1, 1928, p. 351-361.

499. Georg Friedrich Berhnard Riemann, "Foundat ions of a general theory of functions of a single complex variabable." Doctoral Thesis, 1851. In H. Weber, ed., *B. Riemann: Gesammelte Mathematische Werke,* 2nd Ed., paperback reprint, Dover, New York, 1953.

500. As pointed out by Charles W. Misner, Kip S Thorne and John Archibald Wheeler, *Gravitation,* W. H. Freeman and Company, San Francisco, 1973, p. 220.

501. Josephs, {172}.

502. Laithwaite, {172b}.

503. Ernst Mach, *The Science ofMechanics.* 1912, Chapter 2, section 6.

504. This statement of Mach's principle is quoted from Ballentine and Lovett, {496}, p. 201.

505. Albert Einstein, "Die Grundlage der Allgemeinen Relativitatstheorie," ["The Foundation of the General Theory of Relativity,"] *Annalen der Physik,* Vol. 49, 1916, p. 769-822. (English translation in *The Principle ofRelativity,* Methuen, NY, 1923.).

506. Misner, Thome and Wheeler, {500}, p. 543.

507. A. Einstein, Appendix V to his *Relativity, The Special and the General Theory,* translated by Robert W. Lawson, Crown Publishers, New York, 1961, p. 155.

508. Theodor Kaluza, *Sitz. Peuss. Akad. Wiss.,* Vol. K1, 1921, p. 966. English translation, "On the Unification Problem of Physics," is in Lochlainn O"Raifeartaigh, *The Dawning of Gauge Theory,* Princeton University Press, Princeton, 1997, p. 53-58. Einstein had held Kaluza's paper since 1919 before recommending it for publication by the journal.

509. {a} Oskar Klein, *Zeit. f. Physik.* Vol. 37, 1926, p. 895. An English translation, "Quantum Theory and Five-Dimensional Relativity," is in Lochlainn O"Raifeartaigh, *The Dawning of Gauge Theory,* Princeton University Press, Princeton, 1997, p. 59-69. See also {b} Oskar Klein, *Nature, Vol.* 118, 1926, p. 319.

510. Sachs, {126a}.

511. Sachs, *ibid.,* quoted from the publisher's summation on the book jacket itself.

512. Mendel Sachs, "On Unification of Gravity and Electromagnetism and the Absence of Magnetic Monopoles," *IL Nuovo Cimento* B, Vol. **114,** 1999, p. 123.

513. (a) Evans et al., {233f}; (b) Evans et al., {233b}.

514. Misner, Thorne, and Wheeler, {500}.

515. Albert Einstein, *Relativity: the Special and General Theory,* translated by Robert W. Lawson, Crown Publishers, New York, 1961, fifteenth edition.

516. A. Einstein, H. A. Lorentz, H. Minkowski and H. Weyl, with **notes** by A. Sommerfeld, translations by W. Perrett and G. B. Jeffery, *The*

Principle ofRelativity, Methuen and Company. Ltd., 1923. Also available in paperback from Dover.

517. (a) T. Townsend Brown, "A Method of and an Apparatus or Machine for producing Force or Motion, British Patent 300,311, Nov. 15, 1928; (b) — "Electrokinetic Apparatus," U.S. Patent # 2,949,550, Aug. 16, 1960; (c) — "Electrokinetic Transducer," U.S. Patent # 3,018,394, Jan. 23, 1962; (d) — "Electrokinetic Generator," U.S. Patent # 3,022,430, Feb. 20, 1962; (e) — "Electrokinetic Apparatus," U.S. Patent # 3,187,206, Jun. 1, 1965.

518. Jonathan W. Campbell, "Apparatus and Method for Generating Thrust Using a Two Dimensional, Asymmetrical Capacitor Module," U. S. Patent #6,317,310, Nov. 13,2001.

519. (a) Norman L. Dean, "System for Converting Rotary Motion into Unidirectional Motion," U.S. Patent # 2,886,976, May 19, 1959. See also (b) John W. Campbell, Jr., "Report on the Dean Drive," *Analog,* Sept. 1960; (c) — "Instrumentation for the Dean Drive," *Analog,* Nov. 1960; (d) — "Final Report on the Dean Drive," Analog, Dec. 1960. Also (e) G. Harry Stine, "Detesters, Phasers, and Dean Drives," *Analog,* Jun. 1976.

520. (a) Henry Wallace, "Method and Apparatus for Generating a Secondary Gravitational Force Field," U.S. Patent # 3,626,605, Dec. 14, 1971; (b) — "Method and Apparatus for Generating a Dynamic Force," U.S. Patent # 3.626.606. Dec. 14, 1971.

521. J. F. Woodward, "Method for Transiently Altering the Mass of Objects to Facilitate their Transport or Change their Stationary Apparent Weights", U.S. Patent #5,280,864, Jan. 25, 1994.

522. (a) J. F. Woodward, "A New Experimental Approach to Mach's Principle and Relativistic Gravitation," *Found Phys. Lett.,* 3(5), 1990, p. 497-506; (b) — "Corrigendum: A New Experimental Approach to Mach's Principle and Relativistic Gravitation," *Found. Phys. Lett.,* 4(3), 1991, p. 299;(c) — "Measurements of a Machian Transient Mass Fluctuation,[1]' *Found. Phys. Lett.,* 4(5), 1991, p. 407-423; (d) -- "A Stationary Apparent Weight Shift from a Transient Machian Mass Fluctuation," *Found. Phys. Lett.,* 5(5), 1992, p. 425-442; (e) — Maximal Acceleration, Mach's Principle, and the Mass of the Electron," *Found. Phys. Lett.,* 6(3), 1993, p. 233-244; (f) — "Making the Universe Safe for Historians: Time Travel and the Laws of Physics," *Found. Phys Lett.,* 8(1). 1995, p. 1-39; (g) - "Erratum," *Found. Phys Lett.,* 8(3), 1995, p. 303; (h) - "Killing Time."

Found. Phys. Lett., 9(1), 1996, p. 1-23; (i) — "Laboratory Test of Mach's Principle and Strong-Field Relativistic Gravity," *Found. Phys. Lett.,* 9(3), 1996, p. 247-293; (j) — "Twists of Fate: Can We Make Traversable Wormholes in Spacetime?", *Found. Phys. Lett.,* 10(2), 1997, p. 153-181; (k) — Mach's Principle and Impulse Engines: toward a Viable Physics of Star Trek?", presented at the NASA Breakthrough Propulsion Physics Workshop, Cleveland, Ohio, Aug. 12-14, 1997.

523. (a) Max Jammer, *Concepts ofMass, in Classical and Modern Physics,* Harvard University Press, Cambridge, MA, 1961. One also suggests the reading of Jammer, {1b}.

524. (a) Bearden, {15}, p. 11. One kilogram of mass represents 17.053 x 10^{50} switches per second of action quanta h/(4*PI) across the boundary of the mass, in a flux exchange between the mass region and its external environment. The acceleration force can be derived from the difference in "inswitching" and "outswitching" of action quanta (as the masses m_i of the system iteratively change between mass and masstime states). The paper, albeit crudely, derives Newton's three laws of motion in relativistic form and the square law of gravitation. It also indicates the mechanism (reaction) upon a mass that generates the mass's rate of progression through time. For a somewhat expanded treatment, see (b) T. E. Bearden, "Vacuum Engines and Priore's Methodology: The True Science of Energy Medicine," Parts I and II, *Explore,* 6(1), 1995, p. 66-76; 6(2), 1995, p. 50-62.

525. Today we would also point out that to first order time and mass have essentially the same energy density — i.e., they are both spatial energy compressed by c^2. So the "switches" of action quanta we used in 1973 may be taken to actually represent the time-charging and discharging, of a specific region of space. Rotation of time-energy from the time-domain into 3-space connection with a mass is a mass increase as well as a change of mass to masstime. Rotation of mass-energy out of 3-space back into the time domain (during photon emission) is a mass decrease, (a) Our paper, "Giant Negentropy..." {12}, proposing a solution to the source charge problem, argues that all 3-space EM energy comes from the time domain anyway and returns to it. The source charges normally absorb time-energy, and transduce it to 3-space EM energy or vice versa, but the 3-space energy radiated away is in expanded spatial energy form and not compressed into mass-energy. It is the very release of the c^2 compression of the time-energy that is the "transduction" process to provide the **radiated**

spatial EM energy. But if mere rotation in 4-space is used without **that** expansion/transduction, then the time energy appears as mass. This is consistent with the mechanism we advanced for the flow of a mass *m* through time. Note that when a photon is "absorbed", the spatial energy component of the photon is in fact compressed into mass energy, slightly changing the mass. But when it is re-radiated, it is radiated in expanded or "spatial" EM energy form. Without the expansion and transduction, pure rotation of the compressed EM energy between the time domain and the 3-space domain provides the notion of "time-charging" and "time discharging". Indeed, the very anomalous phenomena occurring in radiation detectors in electrolyte experiments at China Lake, already provide direct evidence for just such time-charging, as pointed out in (b) Bcardcn, {17}.

526. E. R. Laithwaite, "Rack and pinion motors," *Electronics and Power,* Vol. 16, 1970, p. 251-252.

527. Of interest: (a) E. R. Laithwaite, "Unexplained phenomenon at Savoy Place," *Electronics and Power,* Oct. 1972, p. 360-362 recounts the discovery of a free energy device violating the second law of equilibrium thermodynamics; (b) Laithwaite, {526}, gives some particulars of the device; (c) —*All Things Are Possible: An Engineer Looks at Research and Development,* I*PC Electrical-Electronic Press Ltd., Dorset House, London, 1976; (d) Laithwaite, {172b}; (e) — "Miles Walker — a pioneer at Met-Vick and UMIST," *Electrical Review,* 211(12), Oct. 15, 1982, p. 33-34; (f) — "Roll, Isaac, roll — Part I," *Electrical Review,* 204(7), Feb. 16, 1979, p. 38-41; (g) — "Roll, Isaac, roll — Part II," *Electrical Review,* 204(11), Mar. 16, 1979, p. 31-33; (h) — "The laws of science and of England," *Electrical Review,* 202(23), June 16, 1978, p. 27-28.

528. E. R. Laithwaite and W. R. C. Dawson, "Mass Transfer: An Introduction based on Experimental Work at the University of Sussex," Sep. 1994. A subtitle is: A system for the transfer of mass derived from the principle of conservation of momentum. On website http://jnaudin.free.fr/html/IPEmain.htm.

529. See WO95/30832, Nov. 16, 1995.

530. Eric Laithwaite and William Dawson, "Propulsion System," U.S. Patent Number 5,860,317, Jan. 19, 1999.

531. Sweet and **Bearden, {**29a**}.**

532. (a) Ning Li and D. G. Torr, *Phys. Rev.*, Vol. 43D, 1991, p. 457; (b) — *Phys. Rev.*, vol. 46B, 1992, p. 5489; (c) — *Bull. Am. Phys. Soc*, Vol. 37, 1992, p. 948. Also see (d) D. G. Torr and Ning Li, *Found. Phys. Lett.*, Vol.37, 1993, p. 948.

533. E. E. Podkletnov and R. Nieminen, *Physica C*, Vol. 203, 1992, p. 441-444.

534. Igor K. Kulikov, "Inertial and gravitational masses of bosons at finite temperatures," in NASA technical package sent in response to queries of "Study of Inertial and Gravitational Masses of a Boson," *NASA Tech Briefs*, 26(2), Feb. 2002, p. 56. The report by Dr. Kulikov of the Jet Propulsion Laboratory (JPL) is carried on the website as http://nasatech.com/TSP/PDFTSP/NPO30325.pdl'. This is a theoretical study of the relationship between the inertial mass and gravitational mass of a self-interacting neutral scalar boson in a heat bath. The difference in the two masses was determined as a function of the temperature of the heal bath. The theory for distinguishing the difference is given. Since it is presented as an inventor's report, we assume that a patent is either pending by or to JPL or already granted to it.

535. Mike LaPointe, {421}.

536. Jim Corum, T. Keech, D. Gray, P. Pesavento, and M. Duncan, "The Electro-magnetic Stress-Tensor as a possible Space Drive Propulsion Concept, presented at the AIAA Joint Propulsion Conference, July 9, 2001.

537. Hector Serrano, "Propulsion Device and Method Employing Electric Fields for Producing Thrust," WO 00/58623, Oct. 5, 2000.

538. William B. Stein, Electrokinetic Propulsion: The Ionic Wind Argument," Energy Conversion Laboratory, Purdue University, West Lafayette, Indiana 47906, Sep. 5, 2000. This is a Gravitec report. Results can be downloaded from http://foldedspace.com/data.html, and an even more rigorous future test is planned.

539. A motion picture of the Naudin's replica thruster in dynamic thrust performance is shown on http://jnaudin.free.fr/html/liftbldr.htm, along with information on many other successful "lifters". This website is a cornucopia of information on inertial propulsion and electrogravitation, including successful independent replication and tests.

540. Ryan Mahoney, "Huntsville Firm Developing New Propulsion Technology," Birmingham Business Journal, Birmingham, Alabama July 19,2001.

541. E.g., see J. Cameron, "An Asymmetric Gravitational Wave Propulsion System," presented in the Breakthrough Propulsion Physics session of the AIAA Joint Propulsion Conference, July 9, 2001.

542. Bearden, {40}.

543. Prange and Strance, {365

544. Privately, Sweet strongly affirmed to me that later he took the risk and pushed it a little further in output, actually levitating the system several times, including accelerating it upward, hovering it, and then letting it sink slowly down to come to rest on the bench.

545. Dirac, {249}.

546. Romer, {84}; see endnote 24, p. 109.

547. E.g., as by Giovanni Modanese, "On the theoretical interpretation of E. Podkletnov's experiment," Extract from report UTF-391/96, OANL gr-qc/9612022, presented to the *I.A.F. Congress 1997,* Number IAA-97-4.107.

548. Ling Ni and D. G. Torr, {532a-532d}.

549. Evans, {137b}; Evans, {485b}.

550. M. W. Evans, personal correspondence.

551. (a) Evans et al., {233b}; (b) — - "Development of the Sachs Theory of Electrodynamics," *Found. Phys. Lett.,* 14(6), Dec. 2001, p. 595-600; (c) Evans et al., {233a}.

552. As we point out in our discussion of cold fusion, use of this enormous time-energy density component in a time-reversal zone allows reducing the force of the gluons in a nucleon and nearly freeing the quarks. The time-reversal zone also reverses the law of attraction and repulsion of charges; now like charges attract. So the coulombic attraction of two H+ ions can attract them together so closely that each enters the strong force region of the other, forming a quasi-nucleus. As the other ions in solution move to negate the time-reversal zone, the zone decays, restoring the normal repulsion of the two protons in the quasi-nucleus. However, being exponential the strong force increases much more rapidly than the normal

coulombic repulsion grows. The result is to force the two protons even closer together, into a full nucleus with a full strong force between them. This forms a nucleus of deuterium, as one quark in one of the protons is flipped while still relatively free, to form a neutron. Different but similar reactions exist to produce the excess tritium shown in many cold fusion experiments, and a similar interaction — especially between two deuteron ions — forms an alpha particle.

553. Bearden, {17}.

554. Davies, {237}, p. 105.

555. Misner, Thorne, and Wheeler, {500}, p. 5.

556. Evans and Jeffers, {459}, p. 150.

557. Evans, {137a}, p. 477.

558. Banesh Hoffman, in Foreword to Yakov P. Terletski, *Paradoxes in the Theory ofRelativity,* translated from the Russian, Plenum Press, New York, 1968, p. vi, viii.

559. Kron, {162}, p. 466.

560. T. D. Lee, {239}, p. 46-47.]

561. This is well known to modern theorists, but is especially accented by Sachs and by Evans. E.g.. to even have an EM wave in space, the energy density of space has to be changing as the wave energy oscillates. This is an oscillating curvature of spacetime, a priori. So all EM waves move in a dynamically curving spacetime.

562. Sachs, {126b}.

563. These concepts are generally consistent with 0(3) electrodynamics. For rigorous exposition of 0(3) EM, see Evans, {137b [.

564. Felix Finster, "Definition of the Dirac Sea in the Presence of External Fields," *Adv. Theor. Math. Phys.,* Vol. 2, 1998, p. 963-985.

565. J. W. Lynn and R. A. Russell, "Kron's Wave Automaton," Journal unk, date unk, p. 131. We would appreciate any researcher furnishing us a completed citation for this reference. We have a copy of the paper, but without full citation details.

566. Kron, {162}. The quote is from p. 114.

567. Kron, {32}, p. 39.

568. Kron, {306}.

569. Kron, {32}, p. 41.

570. See Stigant, {310a} for a bibliography of Kron's **publications.**

571. Several overunity researchers have been assassinated by forces and parties unknown. Many very clever means are used to do the dirty work.

As an example, there is a standard EMF "shooter" which uses Venus modification of the wavefront, to produce a wave that instantly disrupts the control of the heart's beating. There are two versions at least; one about the size of a pocketbook and for close range (30 feet) only, and one about the size of a bazooka and with longer range (up to 100 yards). About 1 minute exposure to the beam of the small weapon will result in death of the targeted individual. I have personally been hit by the small version of that device (and I have a witness who was with me at the time, and also was exposed to it). We survived by instant recognition of what it was, and by bolting immediately out the nearby back door of a restaurant here in Huntsville. If the kill is successful, the autopsy will show that the person died of a heart attack.

Stan Meyer, an overunity researcher with numerous patents, rushed from a restaurant exclaiming "They're killing me!" and expired with just such a heart attack, possibly hit inside the restaurant by a close-range shooter.

Harry Mason's associate was killed in Australia in his apartment by a longer-range, bazooka-sized shooter. The assassin was spotted putting the shooter back inside the car below, and speeding away.

Sometimes a silenced rifle is used for sniping at long range. Sweet was fired at by one such would-be assassin — luckily just as he stumbled and fell on the steps of the foyer to his apartment complex. The bullet cracked right by his ear as he fell forward, passing where his head had just been the moment before.

Another "shooter" uses longitudinal EM wave peak power pulses. This type kill is instant and very permanent. This unit can be set to stun or render the targeted person unconscious, or set to kill. It can also disrupt and stop running automobile engines (there is another version for that also, using negative energy EMP weaponry). However, it time-charges the struck human body so that the body emits longitudinal EM waves for some time after the kill. Marinov was killed with such a shooter (apparently by

KGB-related foreign intelligence operatives) and his body then thrown off a rooftop to make it appear to be suicide. Where his body lay, the pavement glowed when the body was removed. Only one weapon on earth will kill a body so that it will induce luminescence in concrete or asphalt that it lies on for a period.

Another favorite weapon is an ice dart dipped in curare. I was threatened once and told I would be killed by such an ice dart weapon if I traveled in a 2-month period. Just four days past that period, and traveling and changing planes in Dallas-Fort Worth airport, a person was killed three feet from me in broad daylight, right inside the airport, with the exact symptoms of a curare ice dart kill. That was apparently just to teach me "they" were serious.

"They" is that set of cartels that Churchill called "the High Cabal". Bedini and I had severely offended the High Cabal by Bedini's successful transmutation of copper (and other things) into gold. John often makes his own power transistors for his amplifiers, and the slag in the electric oven turns into black ruby laced with gold and silver, confirmed by assay. We have had numerous other assassination attempts, too numerous to iterate. Suffice it to say that developing a good COP>1.0 EM power system can be hazardous to one's health.

Any significant researcher should be wary of "meeting with a sudden suicide" on the way to the supermarket. Another thing to beware of, is a calibrated auto accident where your car is rammed from the rear, and you are shaken up considerably. An ambulance just happens to be passing by moments later, and it will take you to the hospital. If still conscious, the researcher must not get in the ambulance unless accompanied by a watchful friend who understands the situation and the danger. Otherwise, he can easily get a syringe of air into his veins, which will effectively turn him into a human vegetable. If he goes to the hospital safely, he must be guarded by friends day and night, for the same reason, else he runs a high risk of the "air syringe" assassination during the night.

Simply trying to do scientific work, I find it necessary to often carry (legally) a hidden weapon. Both my wife and I have gun permits, and we frequently and legally carry concealed weapons.

As early as the 1930s, T. Henry Moray — who built a successful COP>1.0 power system outputting 50 kW from a 55 lb power unit - had to ride in a bulletproof car in Salt Lake City, Utah. He was repeatedly fired at by snipers from the buildings or sidewalk, with the bullets sometimes sticking in the glass. He was also shot by a would-be assassin in his own laboratory, but overpowered his assassin and recovered.

Over the years, probably as many as 50 or more overunity researchers and inventors have been assassinated for their efforts, and particularly For their success. Some have simply disappeared abruptly and never been heard from again.

These days the use of longitudinal wave shooters (such as killed Marinov) and such is growing, since no signature is left for a normal autopsy to discover. The Yakuza, e.g., uses such "shooters" in Japan to assassinate persons or politicians having incurred their displeasure. Others are subjected to the more traditional Yakuza assassination: Three or four assassins suddenly jump the unsuspecting target, stabbing him repeated and with extreme rapidity. His body may have 50 to 70 deep stab wounds — through the heart, the abdomen, liver, lungs, etc. — before the body strikes the pavement.

Other very sophisticated methods of legal entrapment, gaming, planting narcotics on one's premises and tipping off the drug enforcement agencies for a drug raid in the middle of the night, etc. are utilized.

Widely used is "gaming"', which uses deep psychological profiling to select a "vulnerability". The supercomputer with the game prepares a "scenario" much like writing a movie script of predictable interactions among the players to be chosen. The game involves "agents of influence" (AOIs — persons who are dogmatic, perhaps even radical, and have knee-jerk responses easily triggered, and whose vector direction when they "jump" is along or near the desired response direction), and one or two agents to do the phone conversations with the AOIs and trigger them into action), as well as a game controller or director. The computer programs also use prediction and artificial intelligence, and will forecast the probability of success of the selected game. A very extensive database of deep psychological profiles on useful AOIs and all major COP>1.0 researchers is kept in the computer. When the controller selects the game, the computer spits out the most recommended AOI players. The controller accepts or changes and then accepts, and the game scenario is then prepared. The agents trigger the AOIs, and the unwitting target is suddenly besieged from every direction, along a direction he already has an affinity or "vulnerability" towards. The controller follows the course of the game and the outcomes of all interactions between the target and the AOIs. The agent or agents add "nudges" or additional actions to overcome delays, accomplish redirection when the direction goes awry. etc. Over the decades, these games have gotten very effective indeed, and are quite difficult to content with. I laving survived about 200 of these games over the last two decades, I may yet write a book on some of the major ones that have been used against overunity researchers. The games are not confined just to the overunity field, however, and sometimes are also used to directly intervene in politics and other key situations, {754}. Machiavelli's methods are not dead; they thrive and have been highly computerized.

572. More than a dozen potential mechanisms for overunity EM interactions and systems are given in Evans et al., {233i}. Many of these interactions are likely in highly energetic astronomical phenomena such as the gamma ray burster and the X-ray burster.

573. Evans et al., {38b, 38c}.

574. Bearden, {38a}.

575. Bearden, {30}.

576. Sweet and Bearden, {29a}.

577. (a) A. G. Reiss *et al., Astron. J.,* Vol. 116, 1998, p. 1009; (b) S. Perlmutter *et al., Astrophys. J.,* Vol. 517, 1999, p. 565.

578. A. Einstein, *Sitzungsber. Preuss. Akad. Wiss.,* Vol. 1917, 1917, p. 142. Einstein came to regret his introduction of the cosmological constani as his "greatest blunder". Ironically, this may yet turn out to be one of his greatest contributions.

579. Prange and Strance, {365}.

580. (a) R. Lieu, "The effect of Planck scale space time fluctuations on Lorentz invariance at extreme speeds," *Astrophys. J. Lett.,* 2002 (in press). A preprint is on http://xxx.lanl.gov/abs/astro-ph/0202443. See also (b) Philip Ball, "Time gives rays a break," http://www.nature.com/nsu/020304/0209304-5.html .

581. In 1998, experimental evidence of the accelerated expansion of **the** universe was provided by two groups of astronomers; see (a) Riess *et al.,* (577a}; Perlmutter *et al.,* {577b}. For an attempt to provide a new model for the negative antigravity, see (c) L. Parker and A. Raval, "A new look ill the accelerating universe," *Phys. Rev. Lett.,* Vol. 86, 2001, p. 749-752; (d) Philip Ball, "New model of expanding universe," *Nature News Service,* Science Update, Nov. 12, 2001. A good coverage for the educated layperson is (e) Mario Livio and Alan Sandage, *The Accelerating Universe: Infinite Expansion, the Cosmological Constant, and the Beauty ofthe Cosmos,*^{1}' Wiley, New York, Dec. 2000. See also (f) P. D.

Mannheim, "Implications of cosmic repulsion for gravitational **theory.'"** *Phys. Rev. D,* Nov. 15, 1998, p. 3511.

582. J. C. Bedini and T. E. Bearden, " Process For Transducing **Forms** of Electromagnetic Energy," U.S. Provisional Patent Application, 200 I. A formal U.S. Patent Application is in preparation as of this writing.

583. For a deep consideration of what is "meant" by mass, and how subtle the concept really is, the reader should refer to the scholarly work of Jammer {523a}. The more casual reader should be prepared for somewhat of a shock. Mass is not at all a "cut and dried" concept, as usually assumed. Indeed, the simple materialistic view of mass seems to be very much opposed by modern physics findings.

584. (a) Bearden, {12}. If we insert the absorption of a scalar (time-polarized) photon by the ubiquitously-assumed unit point charge and the subsequent re-emission of a longitudinal photon as the process for "combining" a scalar and longitudinal photon, then our solution is also consistent with (b) Mandl and Shaw, {19}. Mandl and Shaw argue that the longitudinal and scalar polarizations are not directly observable, but only in combination, where they manifest as the "instantaneous" Coulomb (i.e., electrostatic) potential. Our comment is that this argument, translated from particle terminology to wave terminology, then fits our re-interpretation of Whittaker's 1903 decomposition of the scalar potential in (c) Whittaker, {85}. It also strongly suggests the need for a complete reinterpretation of what is meant by "propagation of EM energy through 3-space".

585. E.g., see (a) V. I. Arkhipov *et al.,* "Negative transient currents in amorphous semiconductors." *Internal. J. Electronics* (UK), 51(6), 1981, p. 735-742; (b) — "An analysis of the dispersive charge transport in vitreous 0-55 As_2S_3 : 0*45Sb_2S_3," *Phys. Stat. Sol.* (A), Vol. 54, 1979, p. 67-77: (c) — and Rudenko, A. I., "Negative currents caused by injection-controlled polarization." *Solid St. Commun.,* 28, 1978, p. 675-676.

586. Evans, {137a, 137b, 251}.

587. David Jones, *Vancouver Sun Times,* Weekend Magazine, Dec. 17, 1977, p. 17. Article on Sid Hurwich's Toronto gun-jamming demonstration, stopping of watches, and jamming of a gun.

588. For proof of production of ordinary EM fields and energy at a distance by scalar **interferometry,** see **Evans** et **al., {**79}.

589. Miles and Bush, {198}, p. 101.

590. Bearden, {17}.

591. We point out, but do not further discuss, the obviously startling impact on the validity of the random statistical analyses normally used in scientific work if such "hidden variables" are present in the Earth's supersystem and interact with the experiment.

592. Kron, {192}, p. 466.

593. (a) Gabriel Kron, *Diakoptics: The Piecewise Solution to Large-Scale Systems,* MacDonald & Co., London, 1962. See also (b) Kron, {310b}.

594. Ilya Prigogine, Preface, (160b), p. xi.

595. Sir William Rowan Hamilton, 1837. Hamilton originated quaternion algebra, the Hamiltonian, etc. Hamilton's quaternion algebra has a higher group symmetry than either vectors or tensors. Since Maxwell's theory was first formulated in Hamilton's quaternion algebra and later reduced to vectors and then to tensors, ironically the first successful EM theory has been sharply curtailed rather than being further developed and extended.

596. (a) Aharonov and Bohm, {344a, 344b}.

597. Prigogine, {160b}, p. 104.

598. Lee, {441}, p. 23.

599. Jackson, {22}, p. 811-812.

600. Whittaker, {85}.

601. This is because time may be regarded as compressed spatial length, where the L compression factor is c. Since the energy of a wave is proportional to L^2 (where L is the wave amplitude), then the release of ST time-density as ST energy density provides nearly $9x10^{16}$ times as much effect per second as simple energy density curvature alone does per joule. For convenience, we refer to this as the "10^{17} gain factor" one obtains by releasing the compressed length energy from its time-density ST curvatture form.

602. T. Matsumoto, "Mechanisms **of Electro-Nuclear Collapse,"** *Proc, ICCF-7 (International Conference on Cold Fusion - 7),* Vancouver, BC, Canada, April 1998, p. 98.

603. Romer, {84}, endnote 24, p. 109.

604. See Harter et al., {102}. For a simple analogy, we may think of the longitudinal EM wave as a sort of velocity-modulated wave; i.e., it is rhythmically changing its velocity about some average value, where that value is usually taken to be c. Another way to visualize it is as an "accordion" wave, expanding and contracting along the line of travel.

605. There are several types (polarizations) of photons utilized in physics. E.g., see (a) Ryder, {90b}. On p. 147+, Ryder discusses four polarization states of the photon. Two of these are "transverse" —i.e., the well-known x- and y-polarizations of light; one is called "longitudinal," i.e., z-directed and related to Evans' B(3) field, and one is "scalar" or timelike.

The time-like (scalar) photon we are using in this paper seems to be yet another brand, something like a cross between the Ryder's third and fourth classifications. That is, our "scalar" photon is named such because when it is imperfect it propagates (i.e., in the 7 direction) at finite speed. When perfect, it just appears instantly everywhere it will be, without propagation through space in the usual sense. Hence it can be at an infinite number of points simultaneously - very close to the notion of the pure Coulomb gauge or of Bohm's quantum potential - or it can be impure and propagate at subluminal or superluminal speeds. The main notion we intend in our present use of the "scalar" photon for this treatise is that its oscillation is in the time domain and along the time axis. We use a model which produces the flow of time itself, and a time-component structuring of that flow — something which is still absent from physics. So our time-like (scalar) photon in one part very much resembles Ryder's discussion of the "scalar" photon, but is not just that alone. For instance, both our longitudinal photon and our scalar photon seem to have internal "photon" structures that we do not discuss in this treatise.

A still deeper discussion of photon polarization is in (b) Mandl and Shaw, {19}. The longitudinal and scalar polarizations are not directly observable, but only in combination, where they manifest as the "instantaneous" Coulomb (electrostatic) potential. So by this route one arrives at a well-established mathematical theory that allows a hidden substructure within **the photon itself.** Mandl and Shaw include the photon's four polarization states as related to the four independent degrees of freedom available in the vector potential A. Suppression of the longitudinal and scalar polarizations is accomplished by "fixing the gauge". This reduces the independent degrees of freedom from 4 to 2, giving the conventional electrodynamics. However, when one raises serious foundations flaws in that resulting conventional electrodynamics, it is obvious that the entire structure is still on somewhat shaky ground. An even better mode might be to consider the fundamental photon entity as existing in all degrees of freedom, and the various "kinds" of photons existing due to restrictions or partial restrictions placed on one or more of these degrees of freedom. This of course opens the stage to interactions that change one (restricted) type of photon into a different (restricted) type. Thai is essentially the basis for my use of the notion of "photon transduction". Tt also leads to the transposition of time into energy and vice versa, which I use in my own approach, but which is still missing from nuclear physics. Since experimentally the cold fusion phenomena seem to require that characteristic, we have retained it.

We are indebted for much of the preceding discussion to private correspondence from Bob Flower, a fine scientist and knowledgeable in this area. Flower has pointed out that the conventional photon theory outlined by the cited authors is missing the possibility that nonlinear phase-conjugate optics could make the photon's longitudinal and scalar polarizations manifest in an experiment. Or put another way, if the instantaneous Coulomb potential could be decomposed into a time-like component and a longitudinal component, it would allow the two hidden polarization states to be controlled directly. This would result in anomalous modifications of the EM vector potential, leading to measurable electromagnetic or quantum effects. Flower's observation seems to be the closest to our own view, stated more simply in the present paper.

606. The result of our yet-unfinished struggle in these *very* swampy photon waters is not entirely consistent with the conventional view. Nonetheless, the new approach does seem to fit and explain most of the anomalous cold fusion phenomena, as well as a wide variety of other phenomena previously deemed beyond the pale of physics itself. E.g., by noting that *mind is time-like in its operations,* and therefore directly uses time-polarized (scalar) photons, waves, and electrodynamics, then mind operations become totally electromagnetic, but of a dramatically extended electrodynamic nature presently being approached in quantum field theory That approach leads directly to a testable and engineerable theory of mind

on all its levels (conscious, subconscious, unconscious, species unconscious, biospheric or all-species unconscious, and so on). But since the mind can interact with the body and produce at least the initial spatial forces carrying out intent in the physical world, it follows that some process must exist whereby the "time-like" photon interacts with and changes one or more of the other photons in the conventional view. Our use of *transduction* in fact encompasses that, based on quantum field theory as described by Ryder {90b} and by Mandl and Shaw {19}. Further, the present author's transduction reinterpretation of Whittaker's 1903 and 1904 papers {85, 91a} means that Whittaker's work as reinterpreted strongly supports this approach mathematically. So the approach used directly incorporates *mind and matter interaction,* again on multiple levels. While this area of *engineerable* mind and matter interaction is well beyond the scope of this treatise, it has become possible to begin the physics of the living being — even of the entire living universe — and to foresee direct engineering of the various realms of mind itself. Indeed, Russian psychoenergetics - particularly the highly weaponized secret part of it - already is involved in just that capability in deployed operational equipment of great portent. Since real results and real explanations of diverse metabiological phenomena have arisen from the approach as well as a very deep "more ordinary" physics including the necessary corrections to electrodynamics, we have continued to follow it to see where it eventually leads. A future book is planned on the more positive and beneficial uses of such startling technology. A preliminary view can be had on the author's website, www.cheniere.org, in the "porthole concept" briefing. A patent application has in fact been filed on this startling new method of medical healing.

607. (a) Vlail Kaznacheyev and L. P. Mikhailova, *Ultraweak Radiation in Intercellular Interactions,* [in Russian], Novosibirsk, 1981 [an English exposition of much of the Kaznacheyev work is given in (b) Vlail Kaznacheyev, "Electromagnetic Bioinformation in Intercellular Interactions," *Psi Research,* 1(1), Mar. 1982, p. 47-76.] See also (c) Kaznacheyev *et al.,* "Distant intercellular interactions in a system of two tissue cultures," *Psychoenergetic Systems,* 1(3), Mar. 1976, p. 141-142. In the same issue, see (d) "A Comment" by William A. McGarey, p. 143; (e) "A Comment" by Arthur C. Hastings, p. 143-144. See also (i) Yu. A. Vladimirov, "Ultraweak luminescence of subcellular structures," *Ultraweak Luminescence in Biology: Proceedings of the Symposium,* Moscow, 1969 [In Russian], Robert Becker also showed in his healing of

otherwise intractable bone fractures that a simple scalar potential (now known to involve the direct transduction between scalar and longitudinal photons and vice versa), that cellular dedifferentiation and redifferentiation of red blood cells occurred in the scalar potential region across the damaged bone cells, and directly in such manner as to "eliminate the delta engine" in those damaged bone cells in the fracture. The red cells shucked their hemoglobin, turning back (time-reversing) to a more primitive cell (earlier state). Then they redifferentiated (time-forwarded) into the type cells that make cartilage. There is still a delta engine between cartilage and bone! So these cartilage-like cells redifferentiated again into the kind of cells that make bone. These latter cells were deposited in the fracture, healing it. This process is in fact used today in various medical hospitals, without any real understanding of the physics mechanism involved. In short, it has long been experimentally proven without understanding the actual mechanism by which it works. See (g) Robert O. Becker, "The direct current field: A primitive control and communication system related to growth processes," *Proc. XVIInternal. Congr. Zoology,* Washington, D.C., Vol. 3, 1963, p. 179-183; (h) — and Charles H. Bachman and Howard Friedman, The direct current system: A link between the environment and the organism," *New York State J. Medicine,* Vol. 62, April 15, 1962, p. 1169-1176; (i) — and Joseph A. Spadaro, "Electrical stimulation of partial limb regeneration in mammals," *Bull. N.Y. Acad. Med,* Second Series, 48(4), May 1972, p. 627-64. See also (j) C. A. L. Bassett; R. O. Becker, and R. J. Pawluk, "Effects of electric currents on bone *in vivo," Nature,* Vol. 204, Nov. 14, 1964, p. 652-654.

608. Puthoff, {202}.

609. See (a) A. Shapere and F. Wilczek, Eds., *Geometric Phases in Physics,* World Scientific, 1989. See also (a) M V. Berry and J. M. Robbins, "Indistinguishability for quantum particles: spin, statistics and the geometric phase," *Proc. Roy. Soc. LondA,* Vol. 453, 1997, p. 1771-1790.

610. See Mandl and Shaw, {19}, Chapter 5 and simply reinterpret the coupled scalar and longitudinal photon pair as a spin 2 graviton.

611. In fact, Sweet's vacuum triode amplifier probably used the domains and nuclei in a barium ferrite permanent magnet in such a graviton reaction manner. In an epochal experiment designed and conceived by the present author, Sweet reduced the weight of the device

on the lab bench, smoothly and efficiently, by 90 degrees. For **the** description, see Sweet and Bearden, {29a}.

612. Reginald I. Gray, *Unified Physics,* Naval Surface Warfare Center, Dahlgren, VA, 1988, p. 2-19.

613. For the basic explanation of a scalar interferometer, see Evans et al., {79}.

614. See Chapter 3, paragraph 3.1 through 3.5.

615. Bearden, {12}.

616. As an example, see Bunge, {3}, p. 179-180. Quoting: " *The most complete direct interparticle action theory of electromagnetism is WHEELER and FEYNMAN'S (1949). Its central postulate is Fokker's action principle for a collection ofpoint charges.... from which the equations of motion for charged particles follow. As can be seen, only particle variables occur in this theory, which is an electrodynamics in AMPERE'S sense and therefore the opposite of a unitary field theory. (The theory is mathematically equivalent to an "adjunct" field theory, but this adjunct field, far from being free, is attached to the particles.) The theory has been abandoned by its creators because it is inconsistent with the quantum theory, in particular with the photon hypothesis. Yet it continues to appeal to many not only because it smacks of mechanism and operationalism, but also because no self-forces appear in it and consequently no infinite self-forces (and the corresponding self accelerations) But this is too small an advantage compared with its shortcomings even at the classical level. Indeed, the theory makes use of special relativity - as is apparent from its central axiom...yet it is inconsistent with it for SR borrows from CEM the assumption that e.m. signals propagate in a vacuum with a constant speed c and moreover lead an existence, which, while it lasts, is independent of both emitters and absorbers. In other words, by denying the existence of free radiation fields propagating in space, the action at a distance formidation of CEM contradicts its own basis: it is logically inconsistent.* "

Our comment is that the "photon" interaction itself must be re-examined in light of the demonstrated giant negentropy of every change and dipole in the universe. Allowing for the quantum field theoretic combination of the scalar and longitudinal photons as an observable "photon" that is actually a spin-2 graviton in 4-space rather than 3-space. the entire nature of "propagation of EM energy through space" changes. No photon has ever interacted in just 3-space; instead, it interacts in

4-space. In the strong interpretation of giant negentropy, there is really no such thing as a "single observable photon" in the universe. Instead, there is a combined scalar/longitudinal photon pair, which when interacting in matter causes transverse EM wave movement of the interacting/detecting charges which are restrained by (i) the inertia due to their own mass, and (ii) in circuits, the back repulsion of all other like charges longitudinally ahead of the excited charge that absorbs the "photon" (actually, the graviton). Considering the longitudinal wave "bunching and relaxing" actions resulting in galloping, then the conventional assumption of the constant speed of light c in vacuum is destroyed. What we perceive as "light propagating in space at speed c" already moves in a galloping and jerky motion *about* speed c — now moving superluminally, now moving subluminally — with only an *average* speed of c overall. In turn, anything which affects the performance and "galloping mechanism" exhibited by the longitudinal EM wave can in theory be used to change the speed c. With the coming advent of the Fogal semiconductor and direct superluminal communication, all such objections based on previous rather classical assumptions will simply fall by the wayside. We also stress that the speed of gravitational field is shown in astronomical events and effects to be extraordinarily superluminal by many orders of magnitude. Again, this greatly upsets many of the modeling assumptions in present physics. Physics is based on a set of models and a set of experiments and observed effects. If the experimental effects negate the theory, one has to change the theory or be guilty of abandoning scientific method altogether, thereby turning science into dogma.

617. Cohen, {89}.

618. See Rod Donnelly and Richard Ziolkowski, "Electromagnetic field generated by a moving point charge: A fields-only approach," *Am. J. Phys.*, 62(10), Oct. 1994, p. 916-922. In conventional language, both the transverse and longitudinal field components always try to be born initially, whenever an EM wave is being generated. Generation of the transverse component produces a function which zeroes the longitudinal component. The function appears in the spacetime representation of the transverse EM fields, obtained by Donnelly and Ziolkowski using special transforms. The phase conjugating and retroreflecting aspects of cold fusion experiments produce spacetime curvatures, directly affecting the "canceling function." The altered function becomes an "LW-reduction function" which is postulated to determine the mix of transverse and longitudinal field components that emerge in the interactions.

619. Whittaker, {85} shows that the scalar potential is **comprised of** bidirectional longitudinal EM wavepairs. Whillaker, {91a} shows **that all** fields and waves are comprised of two interfering scalar **potential** functions. Hence all fields and waves are comprised of **functions** of longitudinal and scalar wave interferometry.

620. Evans et al., {79}.

621. Usually the detecting GM tubes will detect the interferometry of the incident longitudinal EM waves with the weak LWs being emitted in the tube itself by time-decay of its time-charges. The resulting transverse wave EM energy ionizes the tube's gas, and the GM tube "reads." If little or no time-decay is occurring, then there will be little or no transduction into TWs, hence little or no ionization. In that case the instrument will not read.

622. Miles and Bush, {198}, p. 101.

623. *Ibid.*

624. (a) Evans, {137b}; (b) Evans et al., {233a, 233f}.

625. Rodrigues and Lu, {93a}.

626. Enders and Nimtz, {329b}.

627. (a) W. A. Rodrigues, Jr. and J. Vaz Jr., "Subluminal and Superluminal Electromagnetic Waves and the Lepton Mass Spectrum," *Kluwer Ac. Pub. Proceedings,* <hep-th/9607231> on Los Alamos web site; (b) P. Letelier and W. A. Rodrigues Jr. (Eds.), *Gravitation: The Spacetime Structure,* World Scientific Publishing Co., Singapore, 1994; (c) J. Vaz Jr. and W. A. Rodrigues Jr., "On the equivalence of Maxwell and Dirac Equations, and Quantum Mechanics," *Internal. J. Theor. Phys.,* Vol. 32, 1993, p. 945-958; (d) J. Vaz Jr. and W. A. Rodrigues Jr., "Maxwell and Dirac Theories as an Already Unified Theory," *Adv. Appl. Clifford Algebras,* Vol. 7 (S), 1997, p. 369-386; (e) W. A. Rodrigues Jr. and J. E. Maiorino, "A unified theory for construction of arbitrary speeds (0 < v < oo) solutions of the relativistic wave equations." *Random Operators and Stochastic Equations,* Vol. 4, 1996, p. 355-400; (f) Rodrigues and Vaz, {93b}.

628. Torn Van Flandern, "The speed of gravity - What the experiments say," *Phys. Lett. A,* Vol. 250, 21 Dec. 1998, p. 1-1 1.

629. *Ibid.,* p. 9.

630. *Ibid.,* p. 10.

631. A. A. Vlasov and V. I. Denisov, "Einstein's formula for gravitational radiation is not a consequence of the general theory of relativity," *Theor. Math. Phys.,* 53(3), June 1983 (English translation), p. 1208-1216. Translated from *Teoreticheskaya i Matematicheskaya Fizika,* 53(3), Dec. 1982, p. 406-418 [in Russian].

632. D. Hilbert, *Gottingen Nachrichten,* Vol. 4, 1917, p. 21.

633. Sen, {68}, p. viii.

634. Mandl and Shaw, {19}.

635. Logunov, A. A. and Yu. M. Loskutov, "Nonuniqueness of the predictions of the general theory of relativity," *Sov. J. Part. Nucl.,* 18(3), May-June 1987, p. 179-187.

636. Whittaker, {85}

637. I.e., that spacetime == scalar potential == virtual particle flux == Whittaker biwave set. If that holds, then when we engineer the internal structure of the scalar potential, we also simultaneously engineer the internal structuring of the vacuum and spacetime itself, with deliberately formed spacetime curvature engines (vacuum engines). This is vacuum engineering — by different means — of the sort proposed by Nobelist T. D. Lee, {73}, p. 380-381. On p. 383, Lee points out that the microstructure of the scalar vacuum field (i.e., of vacuum charge, or — in our view — of the vacuum potential) has not been utilized. Particularly see Lee's own attempt to indicate the possibility of using vacuum engineering, in his "Chapter 25: Outlook: Possibility of Vacuum Engineering," p. 824-828.

638. Ingram Block and Horace Crater, "Lorentz-Invariant Potentials and the Nonrelativistic Limit," *Am. J. Phys.,* 49(1), Jan. 1981, p. 67.

639. Roderic Lakes, "Experimental Limits on the Photon Mass and Cosmic Magnetic Vector Potential," *Phys. Rev. Lett.,* 80(9), Mar. 2, 1998, p. 1826. Our critique is that the given equations define nothing at all, since no equation is a definition. If one replaces the "=" with "≡" in the "definition" of the A-potential in terms of B, one then has B==curl A, which is actually the definition of B in terms of A. If A has no energy, then neither can B, which is just the swirl of the A-energy. If A has no curl, B vanishes. If A has no energy, B vanishes. Yet $dA/dt = -E$, whether

A has curl or not, and E has energy. Ergo, A must have energy if **any** operation upon it is to produce **E-field** energy, else one has **violated the** conservation of energy law and advocates creation of energy from **nothing.** Regardless of how one looks at B = curl A and B = curl A, neither the equation nor the identity defines A in terms of B, because B is always, just one aspect of A and yet A can exist without any curl at all — without B as demonstrated in the Aharonov-Bohm effect. But in no fashion can B exist without A. Therefore A is primary and B is derived, and if A has no energy then B can have no energy. V has energy and energy density, since in fundamental units any point of the potential V is identically the joules of energy collected upon a unit point positive electrical charge assumed at that point. If it had no energy, then no joules could be collected from it.

640. Weinberg, {194}, p. 109-110.

641. Sen, {68}, p. viii.

642. (a) Lee, {13a}; (b) Wu et al., {14}; (c) Lee, {239}, p. 57-59; (d) Lee, {73}, p. 184.

643. Bearden, {12}

644. Whittaker, {85}.

645. The clustering of virtual charges around observable individual charges — due to the polarization of the vacuum — is well known in quantum electrodynamics. Macroscopically one sees the charge as partially shielded by the cluster, so the clustering charges are known to have macroscopic significance. At close enough distances, one sees the "bare" charge with reduced shielding.

646. Mandl and Shaw, {19}.

647. (a) Aharonov and Bohm, {344}; (b) R. G. Chambers, {474}.

648. E.g., see (a) Barrett, {345}; Barrett and Grimes [Eds.], {235b}.

649. (a) Evans *et al,* {113a}; (b) — "Self-Inconsistencies of the U(l) Theory of Electrodynamics: Michelson Interferometry," *Found. Phys. Lett.,* 12(6), Dec. 1999, p. 579-584; (c) — *J. New Energy,* Vol. 4, Winter 1999, p. 231-235; (d) — "Derivation of the Lehnert Field Equations from Gauge Theory in Vacuum: Space Charge and Current," *Found Phys Lett.,* 13(2), April 2000, p. 179-184; (e) Evans et al., {233g}; (f) Evans **et** al.. {233e}; (g) — **"Equations of the** Yang-Mills Theory of Classical Electrodynamics," ***Optik, 111***(2), 2000, p. 53-56; (h) **Evans** el **al.,** {113***b}.***

Also (i) more than 100 papers on restricted U.S. Department of Energy Internet website http://www.ott.doe.gov/electromagnetic/.

650. Obviously we exclude active systems such as matter that decays in nuclear fashion. Those are not inert systems, but are "pre-excited" systems whose matter has had excess energy since its formation during the birth of the universe.

651. (a) Kondepudi and Prigogine, {160c}; (b) — "Thermodynamics, Nonequilibrium," *Ency. Appl. Phys.* Vol. 21, 1997. p. 311-337.

652. I.e., the known broken symmetry of the charge (regarded as a set of composite dipoles) in its vacuum energy exchange.

653. Kraus, {76}, p. 578, Figure 12-60, a and b.

654. James Croll, *Phil. Mag.,* Series 5, Vol. 2, 1876, p. 242-254.

655. Heaviside, {5a-5c}.

656. Poynting, {4a, 4b}.

657. Heaviside, {106}.

658. E.g., see Lorentz, {109}.

659. E.g., (a) Panofsky and Phillips, {110}; (b) Gough and Richards, {224b}. (c) Jackson {22}, p. 259, points out the arbitrary nature of the Poynting vector and disposes of any added nondivergent energy flow vector with the words *"Such an added term can, however, have no physical consequences."*

660. Simply examine *Vqt* around the forward emf section (the external circuit between the generator terminals and the ends of the source dipole inside the generator), and - *Vqt* across the generator terminals (and the source dipole).

661. Evans etal, {38b, 38c}.

662. Bohren, {24}. Independent replication is reported in the same journal issue; see (b) Paul and Fischer, {25}.

663. Bearden, {40}.

664. See Paragraph 8.3.16 in Chapter 8 for the explanation.

665. Olariu and Popescu, {482}.

666. Bertram Schwarzschild, "Currents in normal-metal rings **exhibit** Aharonov-Bohm effect," *Phys. Today*, 39(1). Jan 1986, p. 17-20.

667. Paul and Fischer, {25}.

668. One actually inputs far more electrical energy flow from **the** external electrical power supply than is conventionally accounted, if one accounts for the huge nondiverged Heaviside energy flow component that Lorentz arbitrarily discarded. That energy flow is actually present, but Is not accounted once Lorentz' integration trick is applied to integrate the entire energy flow vector around a closed surface assumed around any volume element of interest.

669. Evans et al., {113a}.

670. As is any EM system when the nondiverged very large Heaviside energy flow component is accounted in addition to the diverged Poynting energy flow component.

671. Bearden and Bedini, {582}.

672. As an example, two scalar potentials fi_1 and fi_2 may have precisely the same intensity magnitude, but different Whittaker internal bidirectional longitudinal EM wave structures. The effects of the two externally identical potentials — as in various chemical reactions — can be quite different. See Bearden, {17}.

673. Lee, {73}, p. 380-381.

674. Lee, {73}, p. 184.

675. For succinct summary of the major symmetries and broken symmetries in physics, see Lee, {239}, p. 57-59.

676. Wang and Chung, {33}.

677. Jean-Louis Naudin, "Chung's Negative Resistance Experiment", on website http://jnaudin.free.fr/enr/enrexpl.htm.

678. Burford and Verner, {35a}.

679. Early but sophisticated analogue simulator. E.g., see Kron, {306}, p. 173.

680. E.g., see (a) Kron, {32}, p. 39. Quoting: *"Although negative resistances are available **for** use with a network analyzer...* "; — "Numerical solution of ordinary and partial differential equations by

means of equivalent circuits." See also (b) Kron, *J. Appl. Phys.,* Vol. 16, Mar. 1945a, p. 173. Quoting *"...since none or only a few negative resistances exist on practical network analyzers) "* (accent added). In the second quotation, arguably Kron was required to insert the underlined words. In the first quotation, the censors missed the clarity of the statement.

681. Kron, {192}.

682. Sweet and Bearden, {29a}.

683. Self-oscillation in such magnetic materials (which are also optically active) is well known. E.g., (a) L'vov, {29c}; (b) Borovik-Romanov and Sinha [Eds.], {369b}. See particularly (c) Gurevich and Melkov, {232c}.

684. Rosenthal publicly verified the results of his tests of the Sweet device to the 26th session of the Intersociety Energy Conversion Engineering Conference (IECEC '91), Boston, Massachusetts, 1991.

685. David M. Pepper, "Applications of Optical Phase Conjugation," 254(1), Jan. 1986, p. 83.

686. Bearden, {15}, p. 2-10.

687. Bearden, {17}.

688. Time-polarized photons are recognized in quantum field theory, implying the existence of time-polarized EM longitudinal waves. In coupling with spatial longitudinally polarized EM waves in wavepairs, the coupling is observable as scalar potential energy (stress energy), based on an argument by Mandl and Shaw {19}. Opposing time-polarized longitudinal EM waves therefore constitute "time-stress", "time-stress potential", and optical pumping in the time domain, which is hypothesized to reverse the normal "forward time" law of attraction and repulsion of charged particles.

689. Kenneth Shoulders and Steve Shoulders, {38If}.

690. U.S. patent numbers 5,018,180; 5,123,039; 5,054,046; 5,054,047.

691. Jain, {35b}.

692. Cao et al, {264b}.

693. Prange and Strance, {365}.

694. Roger Penrose, {82}, p. v.

695. Bunge, {3}, p. 176.

696. Albert Einstein, {la}, p. xi-xii. Appendix I.

697. Raymond A. Serway, *Physics for Scientists and Engineers **with** Modern Physics,* Third Edition, updated version, Saunders College Publishing, Philadelphia, 1990, p. 620.

698. Max Planck, *Treatise on Thermodynamics*, 3rd ed., Dover, New York, 1945.

699. Paul Davies, *Superforce: The Search for a Grand Unified Theory ofNature,* Simon and Schuster. New York, 1984, p. 105.

700. D. Hilbert, *Gottingen Nachrichten,* Vol. 4, 1917, p. 21.

701. A. A. Logunov and Yu. M. Loskutov, "Nonuniqueness of the predictions of the general theory of relativity," *Sov. J. Part. Nucl.,* 18(3), May-June 1987, p. 179.

702. David Whitehouse, "Beads of doubt," BBC News, July 18, 2002, http://news.bbc.co.Uk/l/hi/sci/tech/2135779.stm.

703. Matthew Chalmers, "Second law of thermodynamics 'broken'," *New Scientist,* July 19, 2002, carried on New Scientist website at http://www.newscientist.com/news/print.jsp?id=ns99992572.

704. G. M. Wang, E. M. Sevick, Emil Mittag, Debra J. Searles, and Denis J. Evans, "Experimental Demonstration of Violations of the Second Law of Thermodynamics for Small Systems and Short Time Scales," *Phys. Rev. Lett.,* 89(5), July 29, 2002, 050601.

705. Elias P. Gyftopoulos and Gian Paolo Beretta, *Thermodynamics: Foundations and Applications,* MacMillan, 1991. This is an elaborate text developed over the years at MIT.

706. Dilip Kondepudi and llya Prigogine, *Modern Thermodynamics: From Heat Engines to Dissipative Structures,* Wiley, NY, 1999.

707. Valery Chalidze, *Entropy Demystified: Potential Order, Life and Money,* Upublish.com, 2000. Contains an excellent nonmathematical exposition of the second law.

708. J. S. Dugdale, *Entropy and Its Physical Meaning,* Taylor & Francis, 1996. This book is of a more mathematical bent, but a very thorough treatment.

709. Craig F. Bohren, *Am. J. Phys.,* 51(4), Apr. 1983, p. 323-327.

710. V. S. Letokhov, {157}, ibid.

711. (a) D. K. Sen, *Fields and/or Particles,* Academic Press, London and New York, 1968, p. viii. Thirty-two years later, we published the solution to that problem in (b) T. E. Bearden, "Giant Negentropy from the Common Dipole," *J. New Energy,* 5(1), Summer 2000, p. 11-23. Also carried on DoE restricted website http://www.ott.doe.gov/electromagnetic/ and on www.cheniere.org.

712. T. E. Bearden, "EM Corrections Enabling a Practical Unified Field Theory with Emphasis on Time-Charging Interactions of Longitudinal EM Waves," *J. New Energy,* 3(2/3), 1998, p. 12-28.

713. Dilip Kondepudi and Ilya Prigogine, *Modern Thermodynamics,* ibid., p. 459.

714. E.g., see D. Jou, *Extended Irreversible Thermodynamics,* Springer-Verlag, New York, 1996.

715. Sources for this table are: (a) Roy Porter, Consultant Editor, *The Biographical Dictionary of Scientists,* Second Edition, Oxford University Press, NY, 1994; (b) Kondepudi and Prigogine, {703), ibid.; (c) Serway {697), *ibid.;* (d) K. Martinas, L. Ropolyi, and P. Szegedi (eds.), *Thermodynamics: History and Philosophy,* World Scientific, London, 1991; (e) Stephen F. Mason, *A History of the Sciences,* New Revised Edition, Collier Books, NY, 1962; (f) E. T. Bell, *Men of Mathematics,* Simon & Schuster, NY, 1986; (g) Charles Singer, *A Short History of Scientific Ideas to 1900,* Oxford University Press, London, 1959; (h) William C. Reynolds, *Thermodynamics,* Second Edition, McGraw-Hill, NY, 1968; (i) Paul Edwards (Ed. in Chief), *The Encyclopedia of Philosophy,* Vols. 1-8, Macmillan, NY, 1967; (j) I. Asimov, *Asimov's Biographical Encyclopedia of Science and Technology,* Second Revised Edition, Doubleday, Garden City, NY, 1982; (k) Jeff Biggus, *Sketching the History of Statistical Mechanics and Thermodynamics,* 2002, http://history.hyperjeff.net/statmech.html, (1) J. B. Jones and G. A. Hawkins, *Engineering Thermodynamics,* Wiley, New York, 1986; (m) Kenneth Wark, *Thermodynamics,* Third Edition, McGraw-Hill, 1977.

716. Antoine Laurent Lavoisier, *Elementary Treatise* ***on Chemistry,*** 1798.

717. **I.** Asimov, *Asimov's Biographical Encyclopedia of* ***Science*** *and Technology,* Second Revised Edition, Doubleday. Garden City, NY, 1982.

718. Benjamin Thompson (Count Rumford), *Enquiry Concerning the Source of Heat which is Excited by Friction,* 1798.

719. Eugene F. Mallove, "The Mysteries and Myths of Heat: A Brief History of Hot and Cold," *Infinite Energy*, May-June 2001, issue #37.

720. Julius Robert Mayer, 1814-1878. In 1842, Mayer's classic paper on conservation of energy was published in *Annalen der Chemie.* He then published several papers himself. With no recognition and bitterly attacked, Mayer suffered a nervous breakdown and attempted suicide, being committed to institutions for several years. From 1858 he began to receive well-justified recognition. He was lauded by the scientific community and received the Royal Society's Copley Medal in 1871.

721. Rudolf Clausius, "On the Moving force of Heat and the Laws of Heat Which May be Deduced Therefrom," 1850.

722. Mallove, {719}.

723. James Clerk Maxwell, "A Dynamical Theory of the Electromagnetic Field," *Roy. Soc. Trans.,* Vol. CLV, 1865, p 459. Also in *The Scientific Papers of James Clerk Maxwell, 2* vols. bound as one, edited by W. D. Niven, Dover, New York, 1952, Vol. 1, p. 526-597.

724. Actually, it is not *proven* that the energy of the universe is constant. With the recent experimental findings that the expansion of the universe is accelerating, the kinetic energy of the universe could be increasing. Whether this is offset by an appropriate change in the physical universe's supersystem remains to be seen.

725. Jeff Biggus, "Sketching the History of Statistical Mechanics and Thermodynamics," http://history.hyperjeff.net/statmech.html.

726. For a discussion of the modern death of matter and the death of materialism, see Paul Davies and John Gribbin, *The Matter Myth,* Simon & Schuster, NY, 1992. Quantum mechanics shook the foundations of materialism and the clockwork world, and chaos has **finished the** devastation. For a scholarly dissertation on mass, see Max **Jammer,**

Concepts ofMass, in Classical and Modern Physics, Harvard University Press, Cambridge, MA, 1961.

727. Dilip Kondepudi and Ilya Prigogine, *Modern Thermodynamics: From heat Engines to Dissipative Structures,* Wiley, New York, 1998, p. 3.

728. Serway, {697}, p. 507.

729. Serway, *ibid.,* p. 507.

730. Serway, *ibid.,* p. 508.

731. Serway, *ibid.,* p. 527.

732. Lindsay and Margenau, *Foundations ofPhysics,* Dover, New York, 1963, p. 214.

733. Robert H. Romer, "Heat is not a noun," *Am. J. Phys.,* 69(2), Feb. 2001, p. 107-109. This is an editorial discussion by the Editor *ofAm. J. Phys.* of the concept of heat in thermodynamics, where heat is not a substance, not a thermodynamic function of state, and should not even be used as a noun.

734. Serway, *ibid.,* p. 527-528.

735. Serway, *ibid.,* p. 588.

736. T. E. Bearden, *Energetics: Extensions to Physics and Advanced Technology for Medical and Military Applications,* CTEC Proprietary, Mar. 21, 1998, 200+ page inclosure to CTEC Letter to Gen. (Ret.) Walter Busby, Deputy Secretary of Defense for Counterproliferation and Chemical and Biological Defense, March 21, 1998. This communication proposed a crash program to develop a portable suitcase-size treatment device based on this effect, for use in treating mass casualties after forthcoming terrorist attacks by weapons of mass destruction. Treatment of a patient would have required only five minutes. Copies were also sent to the U.S. Air Force, National Institutes of Health, and other key government agencies. Three and a half years later, the attack on the World Trade Center and the Pentagon — and a foiled attack on the White House — occurred on September 11, 2001. Today the nation is at war against international terrorism, and extensive changes in defense of the heartland are also under way. However, there still appears to be no real solution to the problem posed by mass casualties, particularly which professional

strikes can produce casualties in the hundreds of thousandsor a few millions.

737. (a) A. J. Berteaud and A. M. Bottreau, "Analysc des **rayonne**ments electromagnetiques emis par I'appareil Priore," [Analysis of **the** electromagnetic radiations emitted by the Priore apparatus], D.R.M.E., 1971, p. 3-12; (b) A. J. Berteaud, A. M. Bottreau, A. Priore, A. N. Pautrizel, F. Berlureau, and R. Pautrizel, "Essai de correlation **entre l'**evolution d'une affection par Trypanosoma equiperdum et 1'action d'une onde electromagnetique pulsee et modulee," [Trial of the correlation between the evolution of a disease by Trypanosoma equiperdum and the action of a pulsating and modulated electromagnetic wave], *Compt. Rend. Acad Sri.* (Paris), Vol. 272, 1971. p. 1003-1006: (c) R. Cambar, "Rapport general des travaux de la Commission de Controle constitute en vue de verifier l'un des effets biologiques obtenu par l'utilisation de l'appareillage de Priore A. Bordeaux," [General findings of the work of the control commission formed to verify one of the biological effects obtained by use of the apparatus of A. Priore at Bordeaux], 1969, I vol., (d) R. Courrier, "Expose par M. le Professeur R. Courrier, Secretaire Perpetuel de L'Academie des Sciences fait au cours d'une reur on a L'Institut sur les effets de la Machine de M. A. Priore le 26 Avril 1977," [Presentation by Professeur R. Courrier, Perpetual Secretary ot the Academy of Sciences, made at the meeting of the Academy on the effects of the machine of M. A. Priore.] (e) G. Delmon and J. Biraben, "La croissance du carcinome de Guerin sour Faction de champs electromagnetiques."[The growth of carcinoma treated by the action of electromagnetic fields], *Rev. Path. Comp.*, 3(2), 1966, p. 85-88. (f) G. Mayer, A. Priore, G. Mayer and R. Pautrizel, "Action de champs magnetiques associes a des ondes electromagnetiques sur l'orchite trypanosominne due lapin," [Action of magnetic fields associated with electromagnetic waves on the typanosomian orchitis of the rabbit], *Compt. Rend. Acad. Sci.* (Paris), Vol. 274, 1972, p. 3011-3014. Many more reports of the novel cures are in the French medical literature, particularly by Pautrizel (g) Priore's doctoral thesis (which was rejected when the project was supressed) is: *Guerison de la Trypanosomiase Experimental Aigue et Chronique par L 'action Combinee de Champs Magnetiques et D 'Ondes Electromagnetiques Modules.* [Healing of intense and chronic experimental trypanosomiasis by the combined action of magnetic fields and modulated **electromagnetic** waves], thesis submitted in candidacy for the doctoral degree, 1973. (h) Antoine Priore, "Apparatus for producing radiations penetrating living

cells," U.S. Patent No. 3,368,155, Feb. 6, 1968;(i) — "Method of producing radiations for penetrating living cells," U.S. Patent No. 3,280,816, Oct. 25, 1966; (j) — "Procede et dispositif de production de rayonnements utilisables notamment pour le traitement de cellules vivantes," [Procedure and Assemblage for Production of Radiation Especially Serviceable for the Treatment of Living Cells], Republique Francais Brevet d'Invention P.V. No. 899.414, No. 1,342,772, Oct. 7, 1963; (k) Eric Perisse, *Effets des Ondes Electromagnetiqv.es et des Champs Magnetiques sur le Cancer et la Trypanosomiase Experimentale* [Effects of Electromagnetic Waves and Magnetic Fields on Cancer and Experimental Trypanosomias], Doctoral thesis, University of Bordeaux No. 83, March 16, 1984.

738. (a) R. O. Becker, "The neural semiconduction control system and its interaction with applied electrical current and magnetic fields," *Proc. XI Internatl. Cong. Radiology,* Vol. 105, 1966, p. 1753-1759, Excerpta Medica Foundation; Amsterdam; (b) — "The direct current field: A primitive control and communication system related to growth processes," *Proc. XVI Internatl. Congr. Zoology,* Washington, D.C., Vol. 3, 1963, p. 179-183; (c)———"Electromagnetic fields and life," *Psychoenergetic Systems,* Vol. 3, No. 1-4, 1979, p. 119-128; (d) - - "A technique for producing regenerative healing in humans," *Frontier Perspectives,* 1(2), Fall/Winter 1990, p. 1-2; (e) - - "The Biological Effects of Magnetic Fields — A Survey," *Med. Electron. Biol. Engr.,* Vol. 1, 1963, p. 293-303; (f) — - "The bioelectric field pattern in the salamander and its stimulation by an electronic analog," *IRE Trans. Med. Electronics,* Vol. ME-7, July 1960, p. 202-207; (g) - - and Charles H. Bachman, and Howard Friedman, "The direct current system: A link between the environment and the organism," *New York State J. Med.,* Vol. 62, April 15, 1962, p. **1169-**1176; (h)———and Joseph A. Spadaro, "Electrical stimulation of partial limb regeneration in mammals," *Bull. N.Y. Acad. Med.,* Second Series, 48(4), May 1972, p. 627-64; (i) - - and Carlton F. Hazlewood, Abraham R. Liboff, and Jan Walleczek, *Electromagnetic Applications In Medicine,* NIH-OAM Electromagnetics Panel Report, Jan. 15, 1993; (j) B. Baker; J. A. Spadero, and R. O. Becker, "Electrical stimulation of articular cartilage," *Ann. N.Y. Acad. Sci,* Vol. 238, 1974, p. 491-499; (k) C. A. L. Bassett; R. O. Becker, and R. J. Pawluk, "Effects of electric currents on bone *in vivo," Nature,* Vol. 204, Nov. 14, 1964, p. 652-654. There are many other publications by Becker, who is a true pioneer.

739. http://www.cheniere.org.

740. Kondepudi and Prigogine, {727}, p. 90-91. See also W. Nernst, *A New Heat Theorem,* Dover, New York, I969.

741. Wang et al., {704}.

742. Maddox, John, *Nature,* 417 (2002), p. 903.

743. Buchwald, Jed Z., *From Maxwell to Microphysics* (University of Chicago Press, 1985), p. 44.

744. For a better meaning of "static" as dynamic but steady state, see Tom Van Flandern, *Phys. Lett. A,* 250 (1998), p. 8-9.

745. E.g., Sen, D. K., *Fields and/or Particles* (Academic Press, 1968), p. vii.

746. Wu, C. S. et al., *Phys. Rev.,* 105, 1957, p. 1413.

747. Weinberg, Steven, *Dreams ofa Final Theory* (Vintage Books, Random House, 1993), p. 109-110.

748. Jackson, J. D. and L. B. Okun, *Rev. Mod. Phys.*, 73, 2001, p. 663-680.

749. Kondepudi, Dilip and Ilya Prigogine, *Modern Thermodynamics: From Heat Engines to Dissipative Structures* (Wiley, New York, 1998), p. 459.

750. Jou, D., *Extended Irreversible Thermodynamics* (Springer-Verlag, 1996).

751. Bohren, Craig *F.,Am. J. Phys.*, 51, Apr. 1983, p. 323-327. Under nonlinear conditions, a particle can absorb and re-emit more energy than is in the light incident on it. Metallic particles at ultraviolet frequencies are one class of such particles and insulating particles at infrared frequencies are another.

752. Paul, H. and R. Fischer, *Am. J. Phys.*, 51, Apr. 1983, p. 327.

753. See Hal Fox, and Mitchell Swartz (JET Technology, MA), "Progress in Cold Nuclear Fusion - Metanalysis Using an Augmented Database," presented at ICCF-5, Monaco, April 9-13, 1995. The authors extracted information from over 3,000 papers on cold fusion collected by Fox's company. Over 600 of these experiments reported excess heat."

754. E.g., see Petar K. Anastasovski, H. Fox, and K. Shoulders, "A New Approach to the Cosmic Red-Shift and to the Cosmic Microwave Sources," J. New Energy, 1 (2), Summer 1996, p. 79-87."



BEARDEN

EXCALIBUR

BRIEFING

Explaining Paranormal Phenomena

The interaction of mind and matter.
(2nd Edition, 1988, revised & expanded)



The interaction of mind and matter!

EXCALIBUR BRIEFING

Lt. Col. Thomas E. Bearden, PhD (U.S. Army, Retired)

UFO phenomena are just one aspect of the interrelationship of humans with their collective species. In this extraordinary book, Lieutenant Colonel Thomas E. Bearden, PhD (U.S. Army, Retired) deals with many of the subjects of which he has been active as a conceptualist: scalar electromagnetics and electrogravitation, Soviet psychotronic (Tesla) weaponry, free energy devices, and anomalous phenomena.

UFO sightings are shown to precisely fit predictions for the future, and there is a direct explanation of mind and matter in UFO activity. Colonel Bearden shows us what UFOs are and how they are formed; what the bioenergy is in Hieronymus devices; and he discusses thought photography, psychic surgery, psychokinesis, cattle mutilations, ghost rockets, contactees and space-suited beings, flying saucers and much more.

Previously, Colonel Bearden was senior scientist with a major aero-space company where he directed the company's design and production of expert system (artificial intelligence) applications for the U.S. Army command and control systems. He has had direct experience with tube artillery and with the Ajax, Hercules, Hawk, and Patriot air defense missile systems. He also directed the production of U.S. Army technical intelligence on Soviet surface-to-air missile systems.

A compelling book, not to be missed!

ISBN 0-89407-060-6

Sweating done by red_gonzo.

Note: sometimes formatting of the text may be a little fuzzy. It's all because the OCR process didn't go as smoothly as I expected. Also there may be some errors inside text so be vigilant. In any case share this book, send emails to people about knowledge contained in it.

Lieutenant Colonel Thomas E. Bearden (U.S. Army, Retired) Ph.D., was formerly senior scientist and department manager of a major aerospace company where he directed the design and production of expert systems (artificial intelligence) applications for the U.S. Army command and control systems.

He has over 29 years of experience in air defence systems, tactics, and operations; technical intelligence; command and control expert systems applications; nuclear weapons employment; computerized wargames; anti-radiation missile countermeasures; and military systems requirements. He has direct experience with tube artillery and with the Ajax, Hercules, Hawk, and Patriot air defense missile systems. He also directed the production of U.S. Army technical intelligence on Soviet surface-to-air missile systems.

Colonel Bearden obtained a Master of Science degree in nuclear engineering from the Georgia Institute of Technology, and a Bachelor of Science degree in mathematics from Northeast Louisiana University. He is a graduate of the U.S. Army Command and General Staff College, as well as of several U.S. Army artillery and missile schools.

He holds a Sandan (third degree black belt) in Yoseikan aikido and was the first president of the Yoseikan Aikido Association of North America. He is a former singer, guitarist, songwriter, and recording artist. He is member of Mensa, the Society for the Investigation of the Unexplained, the International Tesla Society, the American Association for the Advancement of Science, the Association of the American Physics Teachers, the Air Force Association, the Association of the U.S. Army, the American Nuclear Society, the Association of Old Crows, the American Defense Preparedness Association, and the Alabama Academy of Sciences. He is also East Coast Director for the Association of Distinguished American Scientists.

Tom Bearden is the author of several books and numerous papers, briefings and presentations, dealing with anomalous phenomena, scalar electromagnetics, free energy devices, Soviet Tesla weapons, and Soviet scalar electromagnetic weather warfare; he is also the producer of several videotapes on these subjects.

Table of Contents

Foreword, by John White . . . xv
Introduction to Second Edition . . . xvii
Introduction to First Edition . . . xxix

Part One: A Sampling of Specific Paranormal Phenomena

The Vestigia Mystery light Experiment . . . 35
Unexplained Generation of Electricity . . . 42
Hyperfield Generation of Photon Patterns About A Bar Magnet Collector . . . 43
Hyperfield Circulation Patterns Above a Magnetized Railroad Track . . . 46
The Cyborg Effect and Orthorotational Sensitivity . . . 49
Additional Factors Consistent with the Vestigia Experiment . . . 51
Remote Viewing . . . 52
The Moray Radiant Energy Device . . . 54
An Atlantean Power Crystal? . . . 60
The Crystal Skull . . . 61
Metal Bending . . . 65
Thought Photography: Stella Lansing . . . 65
The Displacement Effect . . . 68
Pavlita's Psychotronic Generators . . . 71
Cell-like Invisible Tupoidal Forms . . . 71
UFOs . . . 74
    1. Black Ring UFO . . . 74
    2. Anchor Patterns . . . 74
    3. Bifringement . . . 76
    4. UFOs in Water . . . 76
    5. UFOs in Clouds . . . 76
    6. UFO Seen by the Author . . . 76
    7. The 1966 Dennis Billings UFO Sighting . . . 82
    8. The Second Billings UFO Sighting . . . 87
    9. The 1973 Pascagoula UFO Sighting . . . 88
    10. Other UFOs . . . 89
Falkville Spaceman . . . 89
Men-in-Black . . . 94
Sasquatch . . . 95
UFOs Over the Soviet Union . . . 99
The Sighting Over Petrozavodsk . . . 103
French Experiments with Psychotronics . . . 104
Dowsing . . . 104
The Strobe Effect . . . 105
Kirlian Photography . . . 1ll
Interaction of Biofield, Thought and Spark Discharge . . . 1ll

Kervran Effect . . . 114
Psychic Surgery . . . 114
A Deliberate Experiment with Kindling . . . 118
Fay Clark's "Fireflies" . . . 118
"Foo" Fighters . . . 119
Water Monsters . . . 119
Cattle Mutilations . . . 123
Big Mama . . . 123

Part Two: A Theoretical Background for Understanding PT, UFOs, and Psi Phenomena

Some Unexplained Mysteries of Physics . . . 129
Uri Geller . . . 130
My Approach to Psychotronics . . . 131
    1. Reality as a Paranormal Bridge with Two Ends . . . 133
    2. A Fundamental Correction to Classical Logic . . . 136
    3. A Physical Example . . . 139
    4. New Definition of Zero . . . 140
    5. Einstein's Postulate . . . 141
    6. Synchronicity of Concepts . . . 142
Primitive Perception . . . 142
Two-Slit Experiment . . . 146
Photon Quenching of the Paranormal (Time) Channel . . . 151
Raindrop Model of Quantized Change . . . 155
Kindling Effect . . . 156
Bioenergy Collectors . . . 157
Psychometric Effect . . . 159
All Mass Is Charged: Everything Is Electrical . . . 160
A Funny Thing About Electromagnetic Field . . . 163
Extinguishing Electrical Currents . . . 165
Death Transmission Via the Paranormal Channel . . . 166
Disease and Death Induction . . . 169
Dynamic Thought Constructs: Biofield Mechanisms . . . 170
Radionics . . . 171
Psychotronic Devices: A Simple Space (Quiton) Amplifier . . . 172
Typical Hieronymus Device . . . 172
Another Kind of Hieronymus Device and the Inceptive Cyborg Effect . . . 175
Probability: Throw of a Die . . . 176
Negative Time . . . 177
Time Oscillation, Quantum Change, and Mass . . . 177
Mass Is a Time-Differentiation . . . 178
Reality Is Like an Opossum . . . 179
Biofield Concepts . . . 180
Mass, Force, and 3-D Frame Rotation . . . 180

Mass is pi Rotation of Hyperspatial Flux 184
Jitter or Dither Modulates the Primary Flux 185
The Untold Story of Quarks 186
Einstein's Spherical Model of the Cosmos 188
A Charged Particle Is a Dual Closure of the Universe 188
Adding and Subtracting Dimensions 189
Mind Is Objective 191
The Skin Transducer Effect: Turning a Thing into Its Opposite 193
Everett's Many-Worlds Interpretation of Quantum Mechanics 193
Spacetime Curvature Is Tricky 193
Multiple Realities (Many Worlds) 194
Clustered Orthogonal Worlds 196
Crosstalk Between Multiple Realities 199
Biofields: And Maverick Worlds 200
Hyperfield Flux in a Magnetic Field 201
Life and Death 202
The Holographic Hyperchannel Effect 209
Mind Linkage 212
Angels, Imps, and UFO Tulpas 214
Dreams and Unresolved Conflicts 215
Ghost Rockets and Flying Saucers: Materialized Tulpoids 218

Part Three: New Military Applications of Psi Research

Background to Psychotronic Research in the U.S. and the U.S.S.R 223
Psychotronic Background Since WWII 224
Electron Dissolution 225
The 1973 Contactee Wave and Cattle Mutilations 226
Radiation of the U.S. Embassy 229
Disease and Death Transmission 229
Other Weapons 230
Hyperspace Howitzer Operation 230
A Possible Operational Test of Psychotronic Antiaircraft Weapons 236
Population Conditioner 238
A Midcourse ABM System 241
The Bell Island Incident 242
A Terminal ABM System 245
Sweep Mode, Sweeping Away a Nuclear Detonation 246
Zarg, Armageddon, and Linkage 247
Virtual States and Hyperspaces 254
Feynman Diagrams 256
Nature of an Electromagnetic Wave 261
Neutrinic Longitudinal Polarization Waves 262
A New Look at Modulation 265
Hyperspatial Aspects of Modulation 269

The Eureka Concept 272
Biophotons and **Virtual EM Field of a** Bio-organism 273
The Priore Machine 273
The Neurophone 278
Soviet "Woodpecker" Signals 279

Part Four: Soviet Phase Conjugate Directed Energy Weapons

Weapons That Use Time-Reversed Electromagnetic Waves 285

Glossary 297

Bibliography 329

List of Photographs

1. The Vestigia mystery light experiment
(© Vestigia, Stanhope, NJ. Used by permission.) 37-38,40
2. Hyperfield flux in a magnetic field (Courtesy George Meek) 44-45
3. Remote viewing (Courtesy Dr. H.E.Puthoff) 53
4. The Moray radiant energy device (©Dr. T.Henry Moray. Used by permission.) 54-55
5. An Atlantean power crystal? (Courtesy Al Bielek) 59
6. The crystal skull (©El Cariso Publications. Used by permission.) 62
7. Metal Bending (© *New Realities*. Used by permission.) 66
8. Clockwork patterns (© Mrs. Stella Lansing. Used by permission.) 67
9. Displacement effect (Courtesy George Meek and Paul Trovillo) 68
10. Pavlita's psychotronic generators (Courtesy James L. Hickman) 69-70
11. Cell-like invisible tulpoidal forms (©Trevor James Constable. Used by permission.) . . . 72
12. Form for potential materialization (©Trevor James Constable. Used by permission.) . . . 73
13. New Mexico UFO (Courtesy Wide World Photos) 75
14. Oregon UFOs (Courtesy Project Bluebook) 77
15. Black Ring UFO (Courtesy Project Bluebook) 78
16. Anchor patterns (Courtesy Ira Maxey, Project Bluebook, Brad Steiger, Fay Clark) . . . 79-80
17. Bifringement (Courtesy Project Bluebook) 81
18. UFO in water (Courtesy Project Bluebook) 81
19. UFO in clouds (Courtesy Project Bluebook) 83
20. UFO seen by author (Courtesy of the late Ray Palmer) 83
21. Second Billings UFO (© 1978 The American Association of Meta-Science) 85
22. Spanish UFO (Courtesy Spanish National Air Ministry) 91
23. Ohio UFO (Courtesy *Columbus Evening Dispatch)* 91
24. Heflin UFO (Courtesy Rex Heflin) 92-93
25. Falkville spaceman (Courtesy Wide World Photos) 96
26. Men-in-black coin (Courtesy Warren York) 98
27. Sasquatch (Courtesy Wide World Photos) 101
28. Bigfoot cast (Courtesy Wide World Photos) 102
29. The strobe effect 106-107
30. Kirlian photography (Courtesy Danniel H. Kientz) 108-110
31. Interaction of biofield, thought, and spark discharge (Courtesy James L. Hickman) . 112-113
32. Psychic surgery (Courtesy George Meek) 115
33. Kindling of thought bioenergy in snow (Courtesy Mrs. Ann Baune) 116
34. A deliberate experiment with kindling
(© 1978 The American Association of Meta-Science) 117
35. Fay Claris "Fireflies" (Courtesy Fay dark) 120
36. 'Too" fighters 121
37. Pleiosaur-like creature hauled from the sea by Japanese fishermen
Courtesy World Wide Photos) 122
38. Loch Ness monster (© Academy of Applied Science, Boston) 124
39. Cattle mutilation (Courtesy Tom Adams and Walt Andrus) 125
40. Big Mama (Courtesy Bill Jackson) 126
41. Hieronymus device (Courtesy James B. Beal) 219
42. Ghost Rockets (Courtesy of the late Ray Palmer) 244

List of Figures

1. Hyperfield circulation patterns above a magnetized railroad track . . . 47
2. The cyborg effect and orthorotational sensitivity . . . 49
3. Reality: a paranormal bridge with two ends . . . 133
4. A fundamental correction to classical logic . . . 137
5. A physical example . . . 139
6. Primitive perception . . . 143
7. Two-slit experiment . . . 147
8. Photon quenching of the paranormal . . . 150
9. Raindrop model of quantized change . . . 154
10. All mass is charged: everything is electrical . . . 161
11. Death transmission via the paranormal channel . . . 167
12. Typical Hieronymus detector . . . 173
13. Biofield concepts . . . 181
14. Rotation of 3-D frames . . . 182
15. Mass is re-rotation of hyperspatial flux . . . 183
16. Einstein's spherical model of the cosmos . . . 188
17. Adding and subtracting dimensions . . . 190
18. Turning a thing into its opposite . . . 192
19. Multiple realities (many worlds) . . . 195
20. Clustered orthogonal worlds . . . 197
21. Crosstalk between multiple realities . . . 200
22. Biofields: time-clustered orthoframes . . . 201
23. Hyperfield flux in a magnetic field . . . 203
24. Life and death . . . 204
25. Consciousness, life, and intent . . . 207
26. The holographic hyperchannel effect . . . 210
27. Output of stage i . . . 211
28. Layers of consciousness . . . 213
29. Dreams are unresolved conflicts . . . 216
30. Collective conflict initiates prophetic tulpoids . . . 219
31. Examples of UFO waves . . . 227
32. 1973 Contactee wave . . . 228
33. Cattle mutilations . . . 231
34. Induction of Legionnaire's disease . . . 232
35. Hyperspace howitzer operation (2 figures) . . . 235
36. Nuclear Hyperspatial howitzer . . . 237
37. Amidcourse ABM system . . . 240
38. A terminal ABM system . . . 248
39. Sweep Mode: sweeping away a nuclear detonation . . . 249
40. ZARG . . . 252

FOREWORD

by John White

This book deals in a comprehensive fashion with such a vast array of topics — from physics, psychology and evolution to advanced weaponry, military strategy and international politics — that many of you may become anxious, even fearful on reading it. In fact, this assembly of previously uncorrelated information and scientific breakthrough may be the most disturbing you have ever received.

This cannot be helped. This book represents an important step in our efforts to avoid global war involving not only nuclear armaments but also what appears to be a revolutionary development in Soviet military technology — psychotronic weapons. They are the modern equivalent of the legendary invincible sword, Excalibur.

The author is former U.S. Army officer Lt. Col. Thomas E. Bearden, now retired. During his twenty-year military career specializing in artillery, nuclear weapons, and military intelligence, Tom has pondered and researched many subjects that he covers here. His access to the full range of both military and NASA documents will be evident in his book. What may become highly classified data in the future is being revealed to you, our nation's ultimate policymakers, for an urgent reason that Tom has called Operation Fer-de-Lance, the presumed Soviet plan for domination of the planet through nuclear-psychotronic aggression and warfare. For the moment I would simply like to note two statements that indicate the basis for our sense of urgency:

1. On 13 June 1975, Soviet Premier Leonid Brezhnev urged a ban on research and development of new kinds of weapons "more terrible than anything the world has known."
2. In January 1977 former Air Force Chief of Intelligence, Maj. Gen. George J. Keegan (Retired) told *Newsweek* magazine, "The Soviets are working on dramatically exotic new weapons, twenty years ahead of anything ever conceived in the U.S. — so awesome as to lead the Soviets to believe that in the coming decade they would be capable of total neutralization of our ballistic and submarine missiles."

The U.S. military intelligence community interprets these signs in conventional terms as perhaps indicating the development of laser rays. Tom disagrees. His book will deal with the possibility that these weapons are psychotronic or paraphysical in nature.

In fact, we can say that in a strict sense, these are not weapons but devices — breakthrough technology with an enormous potential for the destruction of humanity. They are a second-or third-generation outgrowth of radionic devices presently used in unorthodox medicine for diagnosis and healing. Extremely compact, they could be carried in a suitcase and planted near targets — ICBM sites, communications centers, etc. Even if one of these devices were found and examined, it would only look like an electronic switching circuit or a small transmitter/receiver set, rather than a bomb or explosive.

The energy and the mechanism involved in psychotronic damping of nuclear, chemical or electromagnetic technology is, from all indications, unrecognized by official Western science but nevertheless inherent in it. That also has been deeply pondered by Tom, and this book will give a full explanation of the physics, mathematics and technology involved. It is not an exaggeration to say, as Tom does, that the explanation offers a "physics of metaphysics" — a fully developed theory of paranormal phenomena that elegantly unites physics and psychology. The ramifications of what Tom calls perception theory lead into every field of human knowledge and inquiry with revolutionary results — from science, theology and philosophy through the full spectrum of paranormal phenomena such as UFO's and psychokinesis into the elementary school classroom, the supermarket shopping basket and the voting booth. They most certainly lead into the safety of your homes and the integrity of your minds.

Before you turn to *The Excalibur Briefing,* I want to leave you with these thoughts. The material you are about to read will certainly be denied by our own government and military and probably by a major segment of the scientific community. It is not unlikely that Tom will be dismissed as a paranoid crackpot. Such tactics have been employed before against brilliant, courageous people who challenge the fundamental dogma of the establishment as Tom does here. Nevertheless, I want to reassure you that Tom is sane, sober, and serious.

Of course, such a person could still perhaps be mistaken. In that regard, I believe you will find Tom's presentation to be persuasive. He himself is careful to distinguish speculation from fact, inference from descriptive statement. Even if Tom were paranoid, however, the question arises: *What if there is good reason for paranoia?* To phrase it positively: We should welcome truth and enlightening insight whenever offered, regardless of the source. Do not let *ad hominem* arguments affect your critical judgment about the soundness of this presentation. Assess the work, not the man, for the work is always greater. And having judged the work affirmatively, render true acknowledgement — not lip service — by sharing the ideas in this book with others. Only free, informed, vigorous effort in the court of world opinion can defuse the possibility of Operation Fer-de-Lance and psychotronic mind control leading to total enslavement of the human race.

In closing, I want to point out that Tom's fundamental concern is the unification and evolution of the human species to a higher form of life through a process that he terms "mind linkage." This stage of growth to higher consciousness is explored in the latter part of the book. It is a breathtaking portrait of how the spirit of science can lead to a science of the spirit, to a physics of metaphysics.

INTRODUCTION TO THE SECOND EDITION

Since the first edition of *Excalibur Briefing* was published, a great deal of progress has been made on the actual physics of unusual and paranormal phenomena. Indeed, so much progress has been made in the ten years since the 1978 or so cutoff of most of the Excalibur material, that I really should rewrite the entire book. However, time will not permit that luxury at present I am simply too hard-pressed in the strenuous efforts to move a free energy machine to market and to convince our government that unorthodox Soviet superweapons present us with a problem of the gravest magnitude.

Accordingly, the inclusion of one of my latest papers, "Soviet Phase Conjugate Directed Energy Weapons," together with an updated glossary for the entire emerging field, will have to suffice.

The important thing is that **a separate new field of physics is beginning to emerge.** It turns out that what we've gotten on to is a unified field—one can now turn electromagnetic energy into gravitational energy and vice versa. Indeed, gravitational potential is now revealed as simply infolded electromagnetics, and electromagnetics is simply the outfolding of the internal contents of gravitational potential.

Colleagues have already proven it on the laboratory bench, by building both "free energy" devices and practical antigravity devices.

This new, extended electromagnetics—electrogravitation—I have dubbed **scalar electromagnetics.** The key to it is to let the EM force fields fight themselves to a "cancellation," forming **a** vector zero. If we do this in a nonlinear medium (modulator), the summing/multiplying EM vector forces are locked together and remain as an infolded EM system inside the EM vector zero. This now is a gravitational system. By merely varying (in phase) the summing EM components, one varies the local energy density of vacuum. Rigorously that is a gravitational wave. Further, it is a very powerful G-wave, for we are utilizing EM forces some 1042 times as strong as the normal weak G-force.

Classical EM has taught us to simply discard the components in the zero vector summation, replacing the system of opposing EM forces with a vector EM zero. This of course makes all vector EM zeroes equal. However, it totally ignores the space-time/vacuum stress of the summed forces, and the resulting gravitational implications. Therefore we have been taught to ignore any gravitational aspects of normal EM circuits, and indeed we proceed to release the G-stress effects in the circuits when we build them as we have been taught

Ordinary EM represents the release of the internal stress of gravity. By teaching us to make nonzero EM, scientists have taught us to always release electrogravitational potentials as electromagnetic forces. Thus in classical EM—and in most of the circuits we build—the EM force fields are the primary causative agents. Classically, when these force fields reduce to zero, there is no more electromagnetics going on. That is true, but there can still be a very large amount of gravity and inertial effects going on!

However, quantum mechanics teaches us that the EM force fields are not at all the primary causes. Instead, the potentials are the primary things; EM forces are simply made from these potentials by differentiating operators. And when the force fields are zero, the potentials still exist. Further, when these "forceless potentials" interfere—

even at a distance—real EM effects cun still be obtained, in total violation of ordinary EM and ordinary mechanics!

This is called the Aharonov-Bohm Effect, and in 1986 it was finally proven to most physicist's satisfaction. Only the most diehard skeptics still object to it, according to *Physics Today,* January 1986.

At any rate, when we have zeroed the E and B fields, we can still have the potentials, according to modern physics. These potentials can interfere to produce electromagnetic force effects—even at a distance.

Further, the zero summation can be dynamic; that is, the vector components can be varying, so long as they always sum to a zero vector. Actually such a zeroed system now has an infolded, deterministic pattern of dynamic forces, according to the pattern we deliberately construct. Further, the energy of each force component infolded is varying, and thus the overall energy density of local vacuum is varying.

As we said, rigorously this defines a gravitational wave. So the zero-vector approach allows EM wave energy to be turned directly into gravitational wave energy. Now it is the curvature of spacetime that is being varied locally. That's a really astounding thing.

We can now deliberately engineer the vacuum/spacetime itself, with all that that statement implies. Locally we can bend spacetime itself, which Einstein assumed could never be done except by a huge collection of mass—such as a sun, star, neutron star, etc. But here we can do it with simple things such as opposing coils, opposing E-fields, etc. We've just violated one of the sacrosanct, severely limiting assumptions of ordinary (Einstein's) general relativity!

That is, up to now most Western physicists have assumed that the local spacetime/vacuum cannot be curved. They assume that, where we the observer and the laboratory instruments are, only special relativity applies. Locally the observer always has a "Lorentz frame," in that view. This assumption (the local Lorentz frame) means that all the conservation laws apply, and physical reality stays well-behaved where the laboratory is and where we are. Ordinary relativity becomes just a sort of "special relativity with distant perturbations."

The only curvature of spacetime of any consequence is only to be found at or near distant stars, suns, black holes, and other huge collections of mass, in this highly restrictive view. Further, this assumption implies that one can never have an experimental general relativity, since where one is experimenting (locally) there is always essentially zero spacetime curvature!

However, one need not have such a formidable restriction at all. Two bucking transformers can make a B-field vector-zero a little bit More complex circuits can easily be designed to sum (or multiply) force fields to zero very well. When we do this zero summation, we also get an amazing gain as follows: Consider two electrons in free space. As is well known, the electric field force (repulsion) between them is about 10^{42} times as strong as the gravitational field force (attraction) between them. So the electric force is so very much stronger that the comparatively weak gravitational force can be entirely neglected, in most applications. However, if we "strangle" that electric field force by zero summation, all the opposing electric forces are converted directly into gravitational potential!

Interference of two such potentials can directly generate gravitational forces. So, if we could zero-sum their E-fields perfectly, we could instantly amplify the gravitational force between the two electrons by a factor of 10^{42}. With such a gravitational force amplification factor, our altered "electrical" circuits would actually become powerful electrogravitational circuits. Further, appreciable gravity effects would now be experienced by any mass, object, or device exposed to the action of the circuits. This is the fundamental secret that Nikola Tesla discovered, one which he never openly revealed.

Further, by locking opposing EM waves together, we may easily construct purely scalar EM (electrogravitational) waves and beams. In such case, amazing new phenomena are encountered: (1) one can increase or decrease the mass and inertia of an object; (2) one can produce a unilateral force in and on each and every nucleon in a body, thus accomplishing the long-sought "antigravity"; (3) a unilateral force drive—a "space drive"—can be constructed; (4) transmutation of elements becomes fairly simply done, with miniscule energy; (5) effects at a distance—such as cold explosions or hot explosions—can be accomplished; (6) negative energy and negative time effects can be created and utilized; (7) Newton's third law can be manipulated and violated at will; (8) negative entropy effects can be created and utilized; and (9) direct energy extraction from the vacuum can be accomplished, etc. So many new effects are encountered that it will take a generation of graduate students and university laboratories to get a good handle on most of them.

The reader is urged to remember these rules: (1) The destructive interference of scalar EM waves (electrogravitational waves) produces EM energy in, or extracts it from, the interference zone. (2) The destructive interference of ordinary EM waves produces gravitational potential energy. (3) The release of the ordinary EM force fields represents the bleed-off of a 5-dimensional gravitational potential as ordinary electromagnetics. (4) The bottling-up of the ordinary EM force fields represents the forced bleed-off of a 5-dimensional gravitational potential as ordinary 4-dimensional gravitational force. (5) The EM field and the ordinary (4-space) G-field are just separate bleed-off s of the same 5-dimensional gravitational potential field.

Thus, I make no bones about it; we have a new physics in the offing—one that is eminently practical and easily engineered by any modern electromagnetics laboratory.

Since the first edition of this book was issued, it has also become obvious that at least two other phenomena are involved in UFOs, and intermingled with the "materializations from the collective unconscious" true UFO phenomena. These two additional things are:

(1) A great number of "lights at night" and "mysterious fireball" type phenomena—and giant balls of light and glowing hemispheres of light of gigantic size—are actually due to deliberate Soviet long range, high energy, real-time holography using phase conjugation. These phenomena are to accomplish orientation and alignment of giant Soviet weapons, and at the same time deliberately evoke UFO reports and scientific skepticism, providing perfect deception.

(2) Several nations of the world—at least two—have been building and flying antigravity spaceships all over the solar system, since the early 1950's. A very small number of UFO ship reports and encounters are due to these ships and their crews. However, control of these ships is not under any duly elected government, but passes out of the government concerned, into and under the control of some mysterious group

which I loosely refer to as "the control group." This is the same mysterious group which has been suppressing free energy and antigravity inventors and inventions for a great number of years.

Thus in *Excalibur Briefing* we are still addressing the primary UFO phenomena: Materializations from the collective human unconscious. Coverage of the other two parts of the overall reported UFO phenomena will be made elsewhere.

So it seems that, under my hard-pressed circumstances, the best thing to do for the second edition of *Excalibur Briefing* is to include something that shows some of the drastic progress that has been made. By adding a glossary and a current paper, the book will also be made much more usable. I also have prepared an index for the first edition, but it cannot be included because of space limitations. Admittedly that is regrettable and still not the optimum, but it will have to suffice. Perhaps in the future I will be able to do a complete rewrite of the book, for *Excalibur III.*

Until then, I ask the reader's indulgence and understanding.

* * *

In the first edition we accented the hyperspatial aspects of the problem, but also pointed out that higher dimensional spaces and deeper nested levels of virtual state are in fact one and the same thing. The reader should keep in mind that when we "internest" vector zero systems, we are performing direct engineering in hyperspace.

Let me be more specific. When you zero sum a group of EM force vectors, you place those component vectors "inside the zero," so to speak. In modern language you have placed ordered patterns directly inside the violent flux of virtual particles comprising the vacuum. The modern concept of the vacuum is that it is like a seething plasma or gas. However, it's a very strange gas, for each particle arises spontaneously out of nowhere (according to quantum mechanics), and almost immediately turns into something else and/or disappears. Thus the vacuum plasma or gas is rather peculiar; the particles comprising it appear and disappear so rapidly that they cannot individually be detected. However, while a virtual particle exists, it is in motion, and so a violent flux of these "phantom particles" comprises the vacuum/spacetime.

However, just as many fleeting particles in the vacuum are moving backward in observer time as are moving forward in it! So this wild "vacuum gas" of ghost particles exists in both positive and negative time at once!

Anyway, when we make a zero vector EM system, each component force in the summation represents a gradient in this virtual particle flux. That is, we have "patterned" and organized the flux—polarized it, so to speak. And that now overturns one of the fundamental assumptions of quantum mechanics.

Quantum mechanics assumes that the violent flux of vacuum ghost particles is totally randomized. That is, no deterministic pattern exists in the flux. These virtual changes collect or cohere statistically, not deterministically, in the standard assumption. When they happen to collect/cohere sufficiently, the threshold of an observable quantum change is breached, and a quantum change occurs.

It can readily be seen that, in the ordinary view, the occurrence of these quantum changes is totally statistical. And indeed it is, so long as the virtual particle flux is randomized. However, with zero vector summation (or multiplication) we have produced deterministic patterns in the flux—and hence in the cohering and collecting of this flux on observable charged particles. Therefore, these deterministic "virtual state" ordered patterns will result in the appearance of deterministic patterns in the occurrence of observable quantum changes.

Now we have begun to engineer physical reality directly; that is, one can now begin to pre-determine which statistical change shall be favored, or in the extreme case, which one shall occur, and whether or not it shall even occur at all.

The renowned physicist, David Bohm, has written a theory of "hidden variables" which could fit and describe all of physics (nothing out there contradicts it). It has largely been ignored, and will continue to be ignored unless it can show appreciable application that normal theory cannot cover. With the scalar EM approach, we can now directly provide hidden EM force field vectors, ordering the virtual state vacuum flux, and we may vary these ordered virtual patterns at will to produce startling new results in charged particle systems. So now we can directly engineer Bohm's "hidden variables," and the vacuum itself—something ordinary theory cannot cover. Drastic changes in the physicist's view of fundamental physical reality, and of what he can do about it, now result

But to return: We wish to engineer additional hyperspaces. (The first zero-vector summation places the component vectors in the fifth dimension.) If we take one of the component EM vector forces in the first zero vector summation, and we then take a point on it as yet another "reference zero", we may encapsulate a second series of zero-system summation vectors into and within that zero-point. In this case we have placed these second vectors into yet a deeper level of virtual state vacuum. That is, we have reached into yet another hyperspace with our engineering and control. Indeed, we have placed the second system EM vectors into the sixth dimension. So we have become true hyperspace engineers.

The process is repeatable as desired. We may reach any hyperspace we wish, as our technology and control develop.

Now we see the impact In modern Kaluza-Klein geometry, one needs about 11 or so dimensions if one is to account for quarks, charm, etc. Now we have a direct tool to reach into any one or all of these hyperdimensions and affect the exact particle or component desired. We will be able to engineer matter—including the nucleus, and including inside the proton and neutron—in almost any way we wish. It all follows from scalar electromagnetics, which allows the direct engineering of hyperspace in all its dimensions.

Remember, engineering in hyperdimensions is just the engineering of nested levels of vacuum potentials. Even more startling, we can also place "thoughts" and effects directly in the mind itself, including the unconscious mind.

As we stated in the first edition of this book, we may model the mind as simply an objective 3-space, three turns away from the 3-space of the ordinary physical world. If we nest two or more additional zero-vector systems in our first one, then we have placed affects ("vectors") directly inside the mind itself. If we know the code of the human brain-tuner, we can now manipulate the mind directly. Electromagnetically, by scalar EM. And it appears that the Soviet Union has begun to reach this frightening capability.

Disease patterns may be induced upon ordinary EM carriers in the same manner, by nesting the zero-vector systems. That is, of course, if one has measured the scalar patterns evident in the induced disease, say, in the Kaznacheyev-type experiments with the desired disease patterns. The reverse is also true: Nesting the patterns in the proper context on EM field carriers can cure diseases such as cancer and leukemia, as evidenced by the Priore device.

One can also make a practical "free energy" device by setting up a standing scalar wave resonance in a localized region or device. From the "high stress" point to the "low stress" region of vacuum formed by such a standing scalar wave, a literal "river of energy" is flowing in the vacuum itself. Once the river is established, only the "leakage" need be replenished. Hence, if one builds a special sort of "paddle wheel" to react with the river and turn in it, one obtains shaft power freely from the localized curvature of spacetime. In that case, an ordinary generator can be driven by the shaft torque to provide very cheap, or"free," electrical energy.

Several inventors—three of whom I work with in one respect or another—now have demonstration models of such machines, which take diverse forms.

Because of the extreme importance of these emerging potentialities, in recent years I've concentrated intensely upon the properties of the vacuum as spacetime, and uncovered shortcomings (and downright errors in many cases) in ordinary physics and electromagnetics. Slowly the scalar EM picture has emerged, and a series of papers has been written and published to develop the concepts of the new approach.

The scalar approach also includes the ability to engineer negative energy and negative time flow. The reader is referred to Chapter 4, "Extraordinary Physics," of my forthcoming book, *AIDS: Soviet First Strike*, Tesla Book Co., P.O.Box 1649, Greenville, Texas 75401 for a summary of the vast importance of the time-reversed EM wave (phase conjugation).

Let me here just accent a rule of great importance: It is actually the key to negative energy, negentropy, antigravity, free energy, transmutation, Tesla's wireless transmission of energy at a distance without loss, Tesla's original magnifying transmitter, and many other things.

First we need the expression CPTEGS, where C is charge, P is parity, T is time flow, E is energy, G is gravity, and S is entropy. We shall be concerned with the algebraic sign of each term in the expressioa The rule deals with photon interaction with a charged particle inside an atom. Normally, incident photons interact with an electron in the electron shells, so C is normally negative. This produces normal parity, and causes the normal or positive flow of time, s T is normally positive. The normal kinds of energy, gravity, and entropy are experienced, so energy is positive, gravity is positive (attraction), and entropy is positive (progressive interactions in a system tend to more and more disorder).

The astonishingly powerful rule is this: In a photon interaction with a charged particle in an atom, if any one of the terms of the expression CPTEGS is reversed in algebraic sign, all the other terms are reversed in algebraic sign.

Thus if one makes scalar EM, the wave (and its photons) passes through the electron shells and interacts with (is absorbed in, and raises to an excited state, which then decays to emit a wave and photons) the highly nonlinear, positively charged nucleus. This represents a reversal of C, hence a reversal of P, T, E, G, and S also.

Consequently, a time-reversed wave—a phase conjugate replica of the incident wave—is emitted by the decaying excited nucleus. In nonlinear phase conjugate optics, this is the mechanism that produces the phase conjugate wave. This is also the mechanism that produces a very large amplification of the incident wave when a "pump wave" (two waves 180 degrees out of phase) are used in the nonlinear (modulating) medium of the phase conjugate mirror.

(The reader is referred to any good book or summary paper on phase conjugate optics; for example, see David M. Pepper, "Nonlinear optical phase conjugation," *Optical Engineering* 21(2), Mar./Apr. 1982, p. 156-183.).

When one pumps a phase conjugate mirror material sufficiently, then "tickles" the release of the total nuclear excitation energy as phase conjugation replica waves (negative energy), appreciable negative time is produced in the decaying nuclei of the mirror. In negative time, gravity is a repulsion, not an attractioa The mirror thus produces antigravity, and gets lighter. If it is forced to sufficiently high amplification, it can be made to float in air. At higher amplification still, it will accelerate upward.

Some other references of interest to this new edition follow:

1. **Robert A. Fisher, Ed., *Optical Phase Conjugation,* Academic Press, New York, 1983. Collection of papers. An extensive bibliography is given at the end of the book.**
2. **Ya. Zel'dovich, N. F. Pilipetsky, and V. V. Shkunov, *Principles of Phase Conjugation,* Vol. 42, Springer Series in Optical Sciences, Theodor Tamir, Ed., Springer-Verlag, New York, 1985.**
3. **Amnon Yariv, *Optical Electronics,* Third Edition. Holt, Rinehart and Winston: New York, 1985. See particularly Chapter 16: "Phase Conjugate Optics—Theory and Applications."**
4. **Y. Aharonov and D. Bohm, "Significance of Electromagnetic Potentials in the Quantum Theory." *Physical Review,* Second Series. 115(3), Aug. 1,1959. p. 485-491.**
5. **R. G. Chambers, "Shift of an electron interference pattern by enclosed magnetic flux." *Physical Review Letters.* 5(1), My 1,1960. p. 3.**
6. **Richard P. Feynman, Robert B. Leighton, and Matthew Sands, *The Feynman Lectures on Physics.* Volume n, Section 15-5, p. 15-8 to 15-14.**
7. **E. T. Whittaker, "On an expression of the electromagnetic field due to electrons by means of two scalar potential functions." *Proc. Lond. Math. Soc.,* Vol. 1,1903. p. 367-372.**
8. **T. E. Bearden, *Solutions to Tesla's secrets and the Soviet Tesla weapons.* Tesla Book Co., Greenville, TX, 1981.**
9. **T. E. Bearden, *Tesla's secret and the Soviet Tesla weapons.* Presented in absentia at the First International Unorthodox Energy Symposium, Toronto, Canada, 1981. Available from Tesla Book Co.**
10. **T. E. Bearden, "Soviet weather engineering over North America." 1-hour videotape, 1985. Available from P.O. Box 1472, Huntsville, AL 35807.**
11. **Gwynne Roberts, "Witness to a super weapon?" *The Sunday Times,* London, England, Aug. 17,1980.**
12. **Greg Rippee, "Mushroom cloud sighted off Japan." *Los Angeles Daily News,* Apr. 11,1984. p. 1,8.**
13. **Martin Ebon, "Moscow, June 11, 1977." in his *Psychic Warfare: Threat or Illusion.* McGraw-Hill Book Co., New York, NY, 1983. p. 1-11.**
14. **A. K. Lapkovskii, "Relativistic kinematic equations and the theory of continuous media." *Soviet Physics Journal* 21(6), June 1978-Dec. 1978.**
15. **B. N. Belyaev, "On random fluctuations of the velocity of light in vacuum." *Azvestiya Vysshikh Uchebnykh Zavederdi, Fizika.* 11, Nov. 1980. p. 37-42.**
16. **Ingram Bloch and Horace Crater, "Lorentz-invariant potentials and the non-relativistic limit" *American Journal of Physics.* 49(1), Jan. 1981. p. 67-75.**

17. T. E. Bearden, *Comments on the new electromagnetics: Part I: discrepancies inpresent EM theory.* Tesla Book Co., Greenville, TX. 1982.
18. T. E. Beaiden, *Comments on the new electromagnetics: Part 2: the secret ofelectrical free energy. Tesla* Book Co., Greenville, TX. 1982.
19. T. E. Bearden, *Toward a new electromagnetics: Part III: clarifying the vector concept.* Tesla Book Co., Greenville, TX. 1983.
20. T. E. Bearden, *Toward a new electromagnetics: Part IV: vectors and mechanisms clarified.* Tesla Book Co., Greenville, TX. 1983.
21. T. E. Bearden, "USSR: New beam energy possible?" *Defense & Foreign Affairs Daily.* 13(111), June 12,1984. p. 1-2.
22. T. E. Bearden, *Star Wars Now! The Bohm-Aharonov effect, scalar interferometry, and Soviet weaponization.* Tesla Book Co., Greenville, TX. 1984.
23. T. E. Bearden, "A conditional criterion for identity, leading to a fourth law oflogic." *Pursuit.* 13(1), Winter 1980. p. 6-10.
24. Max Frankel, "Khrushchev says Soviet will cut forces a third; *sees* 'fantastic' weapon." *New York Times.* Jan. 15,1960. p. 1.
25. David Bohm and B. J. Hiley. "On the intuitive understanding of nonlocality as implied by quantum theory." *Foundations ofPhysics.* 5(1), Mar. 1975. p. 93-109.
26. Derek Wood, "USA probes mystery cloud reported off *Japan." Jane's Defence Weekly.* 1(18). May 12,1984. p. 716.
27. Yossef Bodansky. "Soviets 'testing chemical agents in Afghanistan'." *Jane's Defence Weekly.* 1(13), Apr. 7,1984. p. 508.
28. "Explosive events seen on Soviet island." *Aviation Week & Space Technology.* Sep. 26,1983. p. 31.
29. Archibald E. Roberts, "The Tesla Factor." *Bulletin. Committee to Restore the Constitution,* POB 966, Fort Collins, CO 80522. Nov. 1984. p. 1-6.
30. See a series of articles by C. B. Baker in *Youth Action News,* POB 312, Alexandria, Virginia 22313. "Diabolic Soviet Warfare," Nov. 1984; "Soviet Weather Mayhem," Nov. 1983; "The Soviet Zapping of America," Dec. 1986; "Fifth Column Treachery," May 1987, and others.
31. D. W. McCann, "The Enhanced-V: a satellite observable severe storm signature." *Monthly Weather Review.* Ill, 1978. p. 887-894.
32. I. J. R. Aitchison, "Nothing's plenty: the vacuum in modem quantum field theory." *Contemporary Physics.* 26(4), 1985. p. 333-391.
33. G. E. Stedman, "Ring interferometric tests of classical and quantum gravity." *Contemporary Physics.* 26(4), 1985. p. 311-332.
34. Peter Hobbs, "Holes in clouds?" *Weatherwise.* 38(5), Oct 1985. p. 254-258.
35. T. D. Lee, *Particle physics and introduction tofield theory.* Harwood Academic Publishers, New York, NY 1981.Second printing with corrections, Nov. 1982.
36. Ruggero Maria Santilli. *Ethical probe on Einstein's followers in the USA.: An insider's view.* Alpha Publishing, POB 82, Newtonville, MA 02160.1984.
37. Bryan G. Wallace, "The great speed of light in space coverup." *Scientific Ethics,* 1(1), Feb. 1985. p. 2-3.
38. Bryan G. Wallace, "Letters to the Editor." *Physics Today.* 36(1), 1983. p. 11,
39. Bryan G. Wallace, "Letters to the Editor." *Physics Today.* 37(6), 1984. p. 15.
40. M. E. Ash, I.I. Shapiro and W. B. Smith. *Astron. J.* 72,1967. p. 72.
41. Bryan G. Wallace. *Spectrosc. Lett.* 4,1971, p. 79.
42. Bryan G. Wallace. "The unified quantum electrodynamic ether." *Foundations ofPhysics.* 3, 1973. p. 381.
43. D. E. Thomsen, "Was a fifth force felt?" *ScienceNews.* 129(3), Jan. 18,1986. p. 38.
44. S. Olariu and I. Iovitzu Popescu. "The quantum effects of electromagnetic fluxes." *Reviews*

of Modern Physics. 57(2), Apr. 1985. p. 339-438. Thorough review of the entire subject of the Aharonov-Bohm effect, from the standpoint of conventional physics. A very comprehensive list of references is included.

45. V. I. Denisov and A. A. Logunov. "The inertial mass defined in the general theory of relativity has no physical meaning." *Teoretichedskaya i Matematicheskaya Fizika,* 51(2), May, 1982. p. 163-170. (in Russian). English translation in *Theoretical and Mathematical Physics*
46. A. A. Vlasov and V. I. Denisov. "Einstein's formula for gravitational radiation is not a consequence of the general theory of relativity." *Teoreticheskaya i Matematicheskaya Fizika.* 53(3), Dec. 1982. p. 406-418. (in Russian). English translation in *Theoretical and Mathematical Physics.*
47. Richard A. Blade, "Modification of Maxwell's equations in free space to account for nonzero photon mass and scalar electromagnetic waves." *Proceedings of the Tesla Centennial Symposium,* an IEEE Centennial Activity, Colorado College, Colorado Springs, Colorado, Aug. 9-11,1984, p. 91-92.
48. Jack Y. Dea. "Scalar fields: their prediction from classical electromagnetism and interpretation from quantum mechanics." *Proceedings of the Tesla Centennial Symposium,* 1984. p. 94-98.
49. Robert W. Bass. "Self-sustained non-Hertzian longitudinal wave oscillations as rigorous solutions of Maxwell's equations for electromagnetic radiation." *Proceedings of the Tesla Centennial Symposium,* 1984. p. 89-90.
50. T. E. Bearden. "Tesla's electromagnetics and its Soviet weaponizauon." *Proceedings of the Tesla Centennial Symposium,* 1984. p. 119-138.
51. Theodor Kaluza. *Sitz.* Berlin Preuss. Acad. Wiss. 966,1921.
52. O. Klein. *Z. Phys.* 37.895,1926.
53. Charles W. Misner, Kip S. Thome and John Archibald Wheeler. *Gravitation.* W. H. Freeman and Co., San Francisco, CA, 1973. p. 19-21, 71-72, 163-165, 367-369. Presents the limiting assumptions imposed on general relativity, to provide the severely restricted "ordinary general relativity" taught in almost all Western universities. The Soviets are not nearly so attached to such artificial assumptions.
54. V. I. Denisov and A. A. Logunov. "New theory of spacetime and gravitation." *Teoreticheskaya i Matematicheskaya Fizika,* 50(1), Jan. 1982. p. 3-76. (In Russian). English translation in *Theoretical and Mathematical Physics,* 50(1), July 1982. p. 1-48.
55. Raymond C. Gelinas. "Apparatus and method for determination of a receiving device relative to a transmitting device utilizing a curl-free magnetic vector potential field." U.S. Patent No. 4,447,779. May 8,1984.
56. Raymond C. Gelinas. "Apparatus and method for modulation of a curl-free magnetic vector potential field." U.S. Patent No. 4,429,288. Jan. 31,1984.
57. Raymond C. Gelinas. "Apparatus and method for demodulation of a curl-free magnetic vector potential." U.S. Patent No. 4,429280. Jan. 31,1984.
58. Raymond C. Gelinas. "Apparatus and method for transfer of information by means of a curt-free magnetic vector potential field." U.S. Patent No. 4,432,098. Feb. 14,1984.
59. Thomas E. Phipps, Jr. "Critique of accepted theories of special relativity and electromagnetism." *Scientific Ethics.* 1(2), Apr. 1985. p. 17-23.
60. Bertram Schwarzschild. "Currents in normal-metal rings exhibit Aharonov-Bohm effect" *Physics Today.* 39(1), Jan. 1986. p. 17-20.
61. William J. Hooper, "All-electric motional electric field generator," U.S. Patent No. 3,610,971. Oct 5,1971.
62. William J. Hooper, "Apparatus for generating motional electric field." U.S. Patent No. 3,656,013. Apr. 11,1972.

63. William J. Hooper, *New horizons in electric, magnetic and gravitational field theory.* Akron, Ohio. Electrodynamic Gravity, Inc. 1974.
64. Oleg D. Jefimenko. "Gravitation and antigravitation." *Proceedings of the West Virginia Academy of Science.* 52(2), 1980. p. 106-118.
65. R. C. Jennison. "Relativistic phase-locked cavities as particle models." *Journal of Physics A: Mathematical and General.* 11(8), Aug. 1978. p. 1525-1533.
66. T. D. Keech and J. F. Corum. "A new derivation for the field of a time-varying charge in Einstein's theory." *International Journal of Theoretical Physics.* 20(1), 1981. p. 63-68.
67. Raymond Kromrey, "Electric generator." U.S. Patent no. 3,3374,376. Mar. 19,1968.
68. M. J. Perry, "Magnetic monopoles and the Kaluza-Klein theory," *Am. Inst. Phys. Corf. Proc.* No. 116,1984. p. 121-125. Kaluza-Klein theory admits soliton solutions which constitute magnetic monopoles. These monopoles have inertial mass, but no gravitational mass.
69. M. W. Kalinowski, "The nonsymmetric Kaluza-Klein meory," /. *Math. Phys.* 24(7), July 1983. p. 1835-1845.
70. D. J. Toms, "Induced Einstein-Maxwell action in Kaluza-Klein theory," *Phys. Lett.* B (Netherlands), 129B(l-2), Sept 15,1983. p. 31-35.
71. Fritz Albert Popp et al, eds., *Electromagnetic Bio-Information. Proceedings of the Symposium,* Marburg, September 5,1977. Urban & Schwarzenberg, Baltimore, 1979. See particularly Fritz Albeit Popp, "Photon storage in biological systems," p. 123-149.
72. A. G. Gurvitsch, *Theory of Biological Field,* Moscow, 1944 (in Russian).
73. V. P. Kaznacheyev et al, "Conditions Necessary for Appearance of Distant Intercellular Interactions after UF-radiation," *Bulleten Experimentalnoy Biologii i Meditsiny,* No. 5, 1979, pp. 468-471 (in Russian).
74. Antoine Priore, "Method of producing radiations for penetrating living cells," U.S. Patent No. 3,280,816. Oct. 25,1966.
75. David M. Rorvik, "Do the French Have a Cure for Cancer?", *Esquire,* July 1975, p. 110-111, 142-149. Excellent summary of the Priore Affair, with some details of the working of the machine.
76. J. B. Bateman, "A Biologically Active Combination of Modulated Magnetic and Microwave Fields: The Priore Machine," Office of Naval Research, London Report R-5-78, Aug. 1978. Comes very close when he states that "The possibility that some hitherto unrecognized feature of the radiation from a rotating plasma may be responsible for the Priore effects should not be dismissed out of hand..." Indeed, none of the persons who checked the machine or pondered over it knew anything about phase conjugation— which plasmas can do, and which the Priore machines did.
77. J. B. Bateman, "Microwave magic." *Office of Naval Research London Conference Report,* ONRL C-14-77,1977.
78. R. Courrier, 1977. "Expose de M. le professeur R. Courrier secretaire perpetuel de 1'Academie des Sciences fait au corns d'une reunion a l'lnstitut sur les effets de la machine de M. A. Priore le 26 Avril 1977."
79. Jean-Michel Graille, *Dossier Priore: A New Pasteur Affair.* De Noel, Paris, France. 1984.
80. Thomas H. Moray, "Electrotherapeutic apparatus," U.S. Patent No. 2,400,707. Feb. 1,1949.
81. T. D. Lee, *Particle Physics and Introduction to Field Theory,* Harwood Academic Publishers, New York, 1981. See particularly Chapter 16, "Vacuum as the source of asymmetry."
82. Royal R. Rife, "The Rife Microscopes," Apr. 28,1939.
83. Arthur Isaac Kendall, "Filtration of bacteria; studies in bacterial metabolism," *Science 75,* Mar. 18,1932. p. 295-301.
84. R. E. Seidel, M.D. and M. Elizabeth Winter, "The new microscopes," *Journal of the Franklin Institute,* Feb., 1944. p. 103-129.
85. Christopher Bird, "What has become of the Rife *microscope?", New Age Journal,* Mar. 1976.

86. Lida H. Mattman, *Cell Wall Deficient Forms,* CRC Press, Cleveland, Ohio. 1974.
87. T. E. Bearden, *AIDS: Soviet First Strike,* Tesla Book Co., 1987. (In press).
88. T. E. Bearden, "AIDS: Urgent Comments on Mankind's Greatest Threat, and the Secrets of Electromagnetic Healing," presented in absentia at the U.S.P.A. Annual Symposium, July 30-Aug. 2,1987, Golden, Colorado.
89. 'Tesla Electromagnetics: Weapons or Healing?", presented at the Whole Life Expo, Los Angeles Airport Hilton Hotel, Los Angeles, California, Oct 3,1987.
90. Stefan T.Possony, "The Tesla Connection," *Defense & Foreign Affairs,* Aug. 1984, p. 12-14, 27. Highly recommended.
91. Daniel A. Walkeret aL "Kaitoky Seamount and the Mystery cloud of 9 April, 1984," *Science,* 227(4584), Feb. 1, 1985, p. 607-611. See also Daniel L. McKenna and Daniel A. Walker, "Mystery Cloud: Additional Observations," *Science,* 234(4775), Oct 24,1986, p. 412-413 for update to the information in the first article.
92. T. E. Bearden, *Fer-de-Lance: A Briefing on Soviet Scalar Electromagnetic Weapons,* Tesla Book Co., Greenville, TX. 1986.
93. T. E. Bearden, "Soviet Phase Conjugate Directed Energy Weapons: Weapons That Use Time-Reversed Electromagnetic Waves," 1987 (in this publication).
94. Yossef Bodansky, "Soviets testing chemical agents in Afghanistan," *Jane's Defence Weekly,* 1(13), Apr. 7,1984. p. 508.
95. Draft agreement introduced by Andrei A. Gromyko to the United Nations' thirtieth session of the General Assembly on Sept. 23,1975; "Prohibition of the Development and Manufacture of New Types of Weapons of Mass Annihilation and of New Systems of Such Weapons." The first article provided that the types of these new weapons would be "specified through negotiations on the subject."
96. "Secret Speech: Did Brezhnev come Clean?", *National Review,* 29(8), Mar. 4,1977, p. 248, 250.
97. "Jetliner drops 32,000 feet; 400 aboard; 50 are injured," Associated Press Release, *Huntsville (Alabama) Times,Feb. 20,* 1985, p. 1. Also "China Airlines Pilot Denies Cockpit Error," AP Release, *Huntsville (Alabama) Times,* Feb. 21,1985, p. A-9.
98. *Asahi Evening News,* Tokyo, Japan, June 22,1982. Significant airline sighting by Japan Air Lines flights 403 and 421 of a giant, expanding globe of light on June 18,1982, in the North Pacific, 700 km. east of Kushiro.
99. T. E. Bearden, "Search for a Unified Theory of Electromagnetics and Gravitation: The Russians Got There First and Weaponized It," 1987 (in publication).
100. T. E. Bearden and Andrew Michrowski, Eds., *The Emerging Energy Science,* P.A.C.E., Ottawa, Canada, 1985.

T. E. Bearden
December, 1987

INTRODUCTION TO THE FIRST EDITION

Today there are a great many books available on UFO's, paranormal phenomena, and wild science, and one more such book ought to say something quite different if it is to be justified. Accordingly, in this book I have tried to say something quite different, perhaps in some cases too different. And so, to assist the reader's comprehension, I would like to explain something of how the book came about.

For the last fifteen years or so I have been interested in paranormal phenomena to one extent or another. Fifteen years ago I started studying Shotokan karate, and later switched to Yoseikan aikido, a most profound and absorbing martial art. I had already started serious reflection on the nature of perception, and after some years of aikido practice I occasionally began to experience what might be called paranormal perception. For example, occasionally, when violently attacked by several opponents, I would suddenly discover myself standing calmly on the sidelines watching the robot-like figures go through the motions of a play, motions that had already occurred in one kind of reality and that were now simply being repeated. On the rare occasions when I experienced this pure zen state of aikido, the techniques became flawless. In fact, the state was not separable into attacker, defender, and technique — rather a single union of the universe occurred. Unfortunately, although I eventually reached Sandan (third-degree black belt), I never permanently attained the complete aikido oneness state; this does not normally occur until the sixth dan level.

However, the occasional experiencing of this pure unity made a deep impression on me, for such aikido is pure meditation in motion, and only in such a state can the individual grasp the nature of perception. Only when conscious activity has stopped ("mind like a moon on still water") is such awareness possible. For several years I then laboriously developed a theory and interpretation of aikido for Westerners and eventually published it privately.

In 1971, while finishing a Master of Science degree in nuclear engineering at Georgia Tech, I put together a first crude theory of perception, which was published in 1973, many rewrites later. By that time I was already deeply engrossed in the study of paranormal phenomena, and especially unidentified flying objects. I had seen several UFO's (the earliest in 1950), and no longer doubted that the UFO phenomena represented some sort of new reality experienced by a great many people.

The UFO organizations at that time seemed to be in disagreement with each other. For twenty-five years or so almost everyone studying the phenomena had been trying to prove the extraterrestrial hypothesis, i.e., they started with the assumption that UFO phenomena were caused by, say, a group of young stalwarts over on planet X of star Y, getting beered up on a Sunday afternoon, hopping into an old space jalopy, and motoring over to planet Earth to jolly the natives. So they vigorously cataloged the UFO reports that fit the picture, and embarrassedly ignored those that did not. Yet most of the phenomena consisted of strange lights at night, not steel-hulled spaceships. And most of the contactee cases — particularly those involving apparent communication and abduction — were regarded as just too far-out for engineers and scientists to swallow. Almost everyone in the UFO organizations seemed to be convinced that Earth was being visited by spacemen from another planetary culture more advanced than our own, and so the UFO enthusiasts looked for hardware and spaceships, no more and no less.

The tabloids were a mess — filled with sensational nonsense about the purported UFO invasion of earth. Some invasion! If the would-be invaders possessed such an advanced technology, why had they spent twenty-five years flitting around the backside of the country and frightening the rural people, instead of simply landing an expeditionary force and having done with it? It seemed that almost no one was really looking at the phenomena in a totally unbiased manner. When one did so, without especially selecting the data, the strangeness of the data went up by orders of magnitude.

So I decided — rightly or wrongly — not to compete with the catalogers, but to try to come to grips with the possible *science* evidenced by the phenomena. I wanted to examine what kind of science was necessary to describe the phenomena and the mechanisms producing them. It rapidly became obvious that our scientific framework was not adequate to explain these events. In fact, our logical framework was not adequate. So I decided to look for a new scientific framework, knowing that the effort would be long and arduous and might not succeed at all.

All the unexplained phenomena seemed to me to be interconnected; for example, a study of Sasquatch will sooner or later lead to the study of UFO's and thence to the study of the other phenomena. So it appeared that they were all different aspects of the same overall reality. Since that reality most definitely involved the mind as well as matter, it appeared necessary to develop a new science incorporating both mind and matter. And so the search and the gradual accumulation of insight continued.

The trail led directly to the great paradoxes of science, the great unsolved problems of philosophy, and the three laws of logic on which all logical disciplines and sciences are founded. Using my perception theory, it was possible to see through the age-old necessity for the identity of opposites, how opposites could be identified, and when they were identified. Thus a fourth law of logic could be written and the system closed.

Slowly the nature (or, more precisely, a model of the nature) of mind became clearer. In addition, mechanisms for materialization and dematerialization appeared, as well as mechanisms for metal bending, thoughtform materializations (tulpas), and telepathy.

But the international strategic balance also could not be ignored. From my military background, the Soviet military buildup toward an attack capability was apparent as early as 1970-71. Moreover, from my work on the Moray radiant energy device I had discovered what I believed to be the basic theoretical mechanism used by T. Henry Moray to tap the zero point energy of free space. (This mechanism powerfully amplifies virtual state into observable state.) And positive evidence suggested that the Soviets had obtained the secret of how to make the Moray detector tubes. Putting this together with psychotronics produces an astounding weapon capability — and the Soviets must have had such capabilities already on site and others in development.

I looked for evidence of these weapons, and the evidence was there, cleverly — even diabolically — concealed.

When I then realized the *entity* nature of the collective human unconscious, everything fell into place. Suddenly the different major waves of UFO's made very good sense, as did the cattle mutilations, the Soviet buildup, Khrushchev's 1960 statement about fantastic weapons, Brezhnev's 1975 reference to the development of weapons more frightful than man had ever conceived, the long years of microwave radiation of the U.S. Embassy in Moscow, the Legionnaires' disease, etc.

The intelligence community had completely missed the fact that the Soviets had been working on a psychotronic Manhattan Project for thirty years. Not a soul in officialdom would believe that such capability could be achieved by surprise. This is not because of a deep conspiracy of the government (although I believe one of our high intelligence officials may be a Soviet agent, a sort of Penkovskiiy in reverse, who has been personally responsible for preventing any serious U.S. governmental research into psychotronics and UFO's); rather, it is because of all the personal arrogance, bias, power-seeking, manipulation, and maneuvering that now make up so much of our top managerial base in government.

So I decided to put out the information for all to see. There is still time — but just barely, I think — to build psychotronic defenses and prevent the launching of the Soviet attack. But we must move swiftly if Fer-de-Lance, the Soviet attack plan, is to be frustrated, for the eleventh hour is here.

Moreover, there is a single human problem responsible for all the ills that man causes man, and that problem has a technical resolution that is well within our grasp. I firmly believe that by psychotronics, the minds of all men can be linked into a great supermind having absolute psychokinetic mastery over time and space — literally a godlike being, in whom the collective human unconscious has a collective conscious instead of the four billion fragmented individual personal conscious minds it has at present. The initial psychotronics linkage mechanism is just a tool; after linkage is accomplished and stabilized, such props will not be necessary.

This is my real goal. Even if the U.S.S.R. launches Fer-de-Lance, annihilates NATO and China, and obliterates all Western retaliation with a stunning blow, and even if the collective unconscious then psychokinetically lashes back with the violent destruction of the Eurasian continent, linkage is still the goal and the final resolution. Should the apocalypse come to pass, there will still be time, in the midst of the horrendous collapse of civilization, to gain the final solution.

And it is the final and total solution. All the parables in the Book of Revelation will be realized. The grave literally will give up its dead — for with the overcoming of time and dimensionality, all that ever has been or ever will be, *is,* in one great nowness, allness, Omega, "I am that great I AM."

That is the goal, and it is toward that end that this book is written.

Please note that a listing of the research and reference works mentioned in the text can be found in the bibliography.

PART ONE

A SAMPLING OF SPECIFIC PARANORMAL PHENOMENA

In this section I show a sampling from the world of the paranormal, including UFO's of various kinds, psychotronics, Loch Ness monsters, Sasquatch, bigfoot, superfoot, psychokinesis, remote viewing, psychic photography, and a host of other phenomena— all explicable by the theories presented in Part Two.

I fervently believe that a theory can be constructed to explain our lives, including all the strange phenomena as well as the more familiar happenings. In this book a serious attempt has been made to point the way by developing what I believe to be the basic concepts, and by showing that a host of phenomena do seem to be consistent with the schema.

Let us hope that science and scientists are not after all dead, and that they will shake the cobwebs from their eyes and set about particularizing a new paradigm of mind and matter. When the top theoreticians and experimentalists wake up and join in the effort, my task will be finished.

THE VESTIGIA MYSTERY LIGHT EXPERIMENT

Let me start by introducing you to Vestigia, a very fine, relatively new organization that has been formed to study mysterious and unusual phenomena in a scientific manner. This organization, of which I am happy to be a member, is headed by Robert E. Jones and the investigation of the mystery light is spearheaded by James McGrath and Bill Wagner. (The informative *Vestigia Newsletter is pub*lished by the organization. Persons interested in the objective scientific study of unusual phenomena are cordially invited to contact Vestigia at P.O. Box 1183, Perth Amboy, NJ 08861.)

Vestigia's ongoing investigation of a mystery light in Morris County, New Jersey is a classic example of the manner in which mysterious phenomena may be studied in a scientific manner, and it should serve as a model for other investigative groups. Vestigia's experimental work has exemplified careful planning, close teamwork, proper scientific equipment and preparation, and the patience and persistence that are essential when performing fieldwork experiments in the field of unusual phenomena.

1 wish to stress in advance that Vestigia does not endorse my own theory of the possible nature of mystery lights; in fact, the organization very properly remains openminded. Also quite properly, they practice scientific conservatism in studying the possible nature of the phenomenon; at the present time they strongly favor the theory of the piezoelectric effect. Substantial evidence for this thesis includes the presence of a known geological fault in the local area, the presence of piezoelectric minerals in the local granite (e.g. thirty percent quartz), close association of the incidence of the phenomenon with subsequent local earth tremors, conditions favoring the accumulation of a surface charge (e.g., metal railroad tracks oriented parallel to the geological fault), and enhancement of the phenomenon under study. And this is exactly how Vestigia is in fact proceeding.

In science, the prevailing world view is not to be dismissed lightly since a great deal of experimental data has been gathered to substantiate it. And a single experiment cunnot establish the need to correct that solidly based view, even if the experiment at first appears puzzling and not in accordance with the accepted view. Only after many exhaustive studies have found the world view inadequate, may a paradigm properly be changed. From a rigorous scientific viewpoint, then, I am saying that this classic experiment is consistent with my own orthorotation theory, but not that the one experiment proves my theory. The experiment at this point is also perfectly consistent with the more conservative hypothesis that the mystery light is due to the piezoelectric effect. Additional different kinds of experiments are required before either theory will hold. For example, in my own theory, the mechanism of orthorotation must be verified elsewhere, and in the piezoelectric theory, the mechanism that spatially separates the effect from the crystalline material where such an effect normally occurs, must be explained and verified by other experiments.

With these precautionary remarks to the reader, let me now describe the beautiful experiment initiated and still being performed by Vestigia. I will then present my own theoretical explanation, again stressing to the reader that it must be treated as a hypothesis at this point.

Mystery lights occur in many locations throughout the United States and Canada. Vestigia has determined over ninety of them to date. They are recurring phenomena and are often seen near some natural or man-made feature such as a stream, hollow, road, railroad track, field, or mountain.

The mystery light under investigation by Vestigia is located along a one-mile stretch of railroad track in Washington Township, Morris County, New Jersey. The light has been seen by hundreds of people at one time or another over the last twenty to forty years. Dr. C. Louis Wiedemann describes it in the *Vestigia Newsletter:* "Appearing at night, it is said to bob or sway from side to side in the manner of a swinging lantern, and when approached it vanishes, sometimes reappearing at a more distant point."

Quoting from the *Vestigia Newsletter:*

> The preplanned battery of experiments and observations was conducted on the night of November 20-21, 1976. Three observation posts were established along one mile of railroad track, and these were manned in shifts by small teams of observers who maintained contact with team leaders via portable radio communicators. Communications were monitored and instructions were issued from a command post which was maintained in two vans joined in a T-configuration adjacent to the central observation post (Post 2).
>
> The vans contained electronic equipment valued at $30,000, which was wired to sensing devices along the railroad tracks. Four thousand feet of silver plated fine copper wire was laid between the rails and attached directly to an amplifier and oscilloscope in one of the vans, to detect variations in electrical frequency and amplitude. Other cables were attached directly to the rails, providing a capacitance test. Other devices included a Geiger counter, thermometers, a methane gas detector, a barometer, a parabolic listening device, a radar unit, an infrared sensor, and a sensitive compass. Personnel at observation posts were equipped with binoculars and cameras. One tripod-mounted camera equipped with infrared sensitive film was located near the rails at Post 2.
>
> James McGrath, a member of Vestigia's executive board, acted as advisor to the team. Team leader was electrical engineer William S. Wagner who was assisted by Jack Mazzuchelli. In all, sixteen persons were actual members of the team, and a total of twenty-one persons participated that night. A number of these were members of the Unexplained Phenomena Club of the County College of Morris, headed by the club's president, Steve Hopler, and vice-president Mary Ann Barron.

Shown here are six of the seven infrared photos of the mystery light which were taken by the Vestigia team. The frames shown are frames two, three, four, six,



Frame Two



Frame Three

Photo 1. The Vestigia mystery light experiment.



Frame Four



Frame Six

seven, and eight. The camera with infrared film was located at Post 2. Frame 1 was a test frame. Simultaneously with the recording of frame 2 at Post 2, observers looking from Post 1 reported visual observation of a light. The light was not seen by observers at Post 2. A second camera with ordinary film recorded only a pinpoint of visible light.

In the photograph, frame two recorded an image of an apparently plexiform spheroid of dynamic granules of light invisible to the eye of the cameraman. At the same time, observers from Post 1 looking back reported visual observation of a light.

In frame three, within about fifteen seconds the image has decreased in size and the plexiform spheroid is now a thinner corona around a dense, nearly hexagonal center.

In frame four, a dense but small irregular or oval image can now be seen. Frame five, not shown, is quite similar.

In frame six, a substantial decrease in size is apparent.

In frame seven, again the image size has increased, and again it possesses a dome central core surrounded by a thinner spheroidal corona of dynamic granules of light. Also, several separate satellite images are now visible at some distance from the main spheroid.

Frame eight is very similar, except that the satellites are no longer visible and the light in both the core and the corona is not quite as dense.

To describe the experiment precisely, the following passage is taken from Dr. C. Louis Wiedemann's article in *Vestigia Newsletter* No. 2, Spring 1977:

> Following several hours of equipment testing and calibration, at 10:21 P.M. two observers at Post 1 radioed the message that they had a "light" under visual observation between their position and Post 2, at an apparent distance of 300 to 400 feet from Post 1. Post 2 observers immediately scanned the area with binoculars and radar, but no object or light was detectible from that position. The yellowish-white light remained visible from Post 1 for approximately one minute and thirty-five seconds, initially approaching the tracks from a lower position off to one side, but soon positioning itself over the rails, and then seeming to sway from side to side in a pendulum-like manner. Its size was estimated between three and six inches in diameter, and for awhile the observers believed it was approaching them. When it vanished, the disappearance was sudden, as if the light had been "switched off."
>
> During the period in which the light was under observation, personnel at Post 2 took pictures of the apparent darkness, and continued to search with radar and binoculars. Two observers at Post 3 briefly saw what appeared to be an orange light between their position and Post 2. While the main light was under observation, several of the instruments in the command post gave unexplained readings. Most notable among these was the oscilloscope's display of an electrical frequency in the range of 40,000 Hertz. Additionally, the capacitance test showed the apparent presence of a conductive body between or over the rails. Nine minutes after the light had vanished from view, the Geiger counter (whose sensor was between Posts 2 and 3) indicated a full scale reading of greater than 5 mr per hour, lasting ten seconds. Normal background radiation was then recorded for five to six minutes (0.1-0.2 mr/hr), whereupon another full scale reading was displayed for approximately seven seconds.
>
> The pictures were enlarged from small images which appeared on the infrared film which was exposed through a 135 mm telephoto lens from Post 2 by Richard Larkin. Film employed was Kodak high speed infrared No. 2481, which is sensitive to infrared radiation to 900 nanometers, with maximum sensitivity from 750 to 840 nanometers. The lent opening was f/3.5 with the apera-



Frame Seven



Frame Eight

> ture set at infinity. The second frame (frame 2) was exposed between 3 and 5 seconds, and the others were varied in exposure from 3 to 10 seconds. Intervals between exposures were between 10 and 15 seconds.
>
> High speed (non infrared) film in a camera which was hand-held by James McGrath at Post 2 also produced several images of an apparent point source of light above the rails (not shown here). Jack Mazzuchelli observed the area through binoculars during the entire time period, and he was unable to discern any light whatever, although he could perceive the rails and the railbed in the faint illumination provided by starlight shining through a partially overcast sky.

As I stated previously, Vestigia has not yet reached a firm conclusion as to the causative agent, but strongly favors the piezoelectric theory, since if offers the simplest explanation at this point. Again, to quote the *Vestigia Newsletter:*

> No absolute conclusions can yet be drawn, other than the apparent fact that a phenomenon or set of phenomena did occur. Team leader Wagner theorizes that the phenomenon might be similar to so-called earthquake lights which have been reported to precede seismic tremors in Japan. Interestingly, there were explosionlike shocks or "loud booms" reported by residents of two housing developments several miles distant from the site on December 5 and 6,1976, and these shocks were recorded by seismographs at Columbia University and elsewhere. Intensity was (-)0.25 to (+)0.38 on the Richter scale. Wagner posulates a possible piezoelectric effect from tension on subterranean rock deposits.
>
> The possible relationship of a piezoelectric effect will be investigated further. Data gathered in Japan tends to indicate the development of subterranean stresses during the passage of a cold front. In the light of this possibility, it is interesting to note that there was a drop in barometric pressure from 29.9 to 29.76 culminating less than one hour before Vestigia recorded the start of the phenomena. A light snowfall preceded the appearance of the light.
>
> Wagner believes that the initial discoveries tend to indicate that the following conditions must be present for the phenomenon to be manifested:
>
> (1) A geologic fault in the local area.
>
> (2) The presence of certain minerals, especially quartz (quartz comprises 30% of the granite in the area under investigation).
>
> (3) Conditions should permit the accumulation of a surface charge (e.g.: the presence of railroad tracks, because they are metallic).
>
> (4) The tracks must run parallel to the fault.
>
> (5) The phenomenon's manifestation tenc
> sure changes as well as extreme changes in temperature.
>
> Wagner states, "Our indications are, at this point, that the lights precede earthquakes or tremors."

Regardless of what hypothesis we begin with, it must be consistent with all the major features of the Vestigia mystery light experiment.

(1) The explanation must show why a light with structured patterns formed and changed. The structured patterns changed geometrically in shape and intensity, as well as in movement and location. This dynamic formation and change was recorded on infrared-sensitive film. The geometrical shapes of the light structures must be accounted for.

(2) Ordinary film recorded only a pinpoint source of light.

(3) The light which was photographed in infrared was not seen by the photographer himself, nor by eight other persons who were observing at the time from Post 2.

(4) Either that light or another was seen visually from a different station.

(5) At the same time as the visual appearance of the light, instruments recorded the apparent presence of a conductive body between the rails or over them.

Specifically, the electrical capacitance between the rails was observed to change — or at least indications to that effect were received on the instruments.

(6) Nine minutes after the main light vanished, a Geiger counter began to read full scale for about ten seconds, then lapsed back to background reading. Five or six minutes later, full scale reading was repeated for about fifteen seconds. About a minute after that, full scale reading was again recorded for about seven seconds.

(7) At the same time as the main light visual sighting, an electrical frequency of approximately 40,000 Hertz was recorded on the oscilloscope.

There were also environmental conditions which may well have been involved in the experimental effects.

(8) Barometric pressure dropped from 29.9 to 29.76, culminating less than an hour before the phenomena were recorded.

(9) There was a temperature drop and a light snowfall preceded the appearance of the light.

(10) The geological conditions strongly favored seismic stress and piezoelectric effects. For example, the local granite contains about 30 percent quartz, and there is a known geological fault not far from the experimental site. About fifteen days after the experiment, seismic shocks were indeed recorded at Columbia University and elsewhere, and they were audibly detected by residents of two local housing developments. The measured intensity of the seismic shocks was from(—)0.25 to (+)0.38 on the Richter scale. It thus appears highly probable that seismic stresses existed on the subterranean rocks at the time of the experiment and that piezoelectric activity was present in the local granite quartz due to these stresses.

(11) Conditions also favored the accumulation of surface charge, and the railroad rails (good conductors) were oriented parallel to the geological fault.

(12) Several thousand feet of wiring existed in the immediate area to connect the different stations and the instruments to the sensors. About four thousand feet of fine copper wire, silverplated, was laid between the rails and fed to an amplifier and an oscilloscope to detect variations in electrical frequency. The capacitance test also used cables attached to the railroad rails themselves. The Geiger counter's sensor was also positioned at the experiment's hot spot and wired to the equipment van. Additional equipment and wiring was also used.

Finally, preliminary surveys of the area were carried out by persons of known paranormal sensitivity several days before the main experiment. Before conducting the major experiment, Vestigia interviewed persons who had seen the light and also conducted preliminary site studies using psychics. One nationally known psychic was brought to the site by Vestigia's president Robert Jones, and asked to walk along the tracks. The psychic reported impressions of some personal tragedy, perhaps a gruesome murder. Later several other persons with heightened psychic sensitivity were brought to the site, and they reported psychic impressions.

In all, three psychics were brought to the track. The only directly correctable result was that all three had a reading in the same area on the stretch of track, within sixty feet of the sighting of the night of November 20-21. The psychics' own interpretation of their readings differed considerably.

UNEXPLAINED GENERATION OF ELECTRICITY

Some additional data exist to indicate the generation of electricity by rocks and the generation of unexplained electromagnetic energy radiated from the earth, ocean, or atmosphere.

For several years T. Townsend Brown has worked in electrogravitics and holds many patents in the field. Some of his laboratory experiments have positively demonstrated a direct connection between electric currents, electric charge, and gravity, although the exact nature of this connection has not yet been fully explained. Nevertheless, it can be shown that highly charged objects do not behave in a gravitational field exactly as predicted by classical theory.

Furthermore, in 1974 Santilli succeeded in proving that one of the classic assumptions of physics is wrong, namely that electric field and gravitational field are mutually exclusive. Santilli proved that gravitational field and electric field are either partially or totally the same thing, in contradiction to present assumptions.

Over a decade ago, Curtis reported the measurement of very low frequency electromagnetic signals generated over the ocean that are not accounted for by any presently known mechanism or theory. Although Curtis published several articles on this effect, no further investigation has appeared in the literature.

Finally, there is a certain location where the generation of an anomalous electromagnetic signal occurs continuously. This is McGregor Missile Range (U.S. Army), where Army units fire air defense missiles such as Nike Hercules and Hawk. As a young captain, in 1961 I headed up the Hawk Evaluation Team at McGregor Range and directed the Hawk missile firing. About sixty-five kilometers out in front of the Hawk missile sites and downrange, there was a most peculiar source of electromagnetic noise, which could considerably affect a Hawk illuminator (continuous wave) radar when the radar antenna was oriented in that direction at a low elevation. In that case the radar would continually noise-lock (make and break lock-on) on the noise signal, dithering slightly as it continued to try to resolve a coherent radar return signal. This noise source was always present, in all seasons and temperatures, and so we simply made each Hawk unit commander and his personnel aware of the phenomenon. On one occasion 1 even vectored a helicopter with an investigation team to descend on the site and inspect it. All they found was the usual surface of the desert floor, with sparse growths of greasewood and cactus. There was nothing which could serve as a generator or reflector.

At one of our other missile sites in the U.S., there was a strange reflector mechanism located at some distance from the site and at about 15,000 feet altitude. This was rigidly fixed in location and unvarying, and the unit radar personnel often used it to calibrate the range of the radar. They simply locked on the reflecting point and fine-adjusted the radar range dials to indicate exactly the known range to the reflecting point. Here again, personnel on their own initiative vectored an aircraft directly through the point and searched the air in that area, but nothing at all could be found.

HYPERFIELD GENERATION OF PHOTON PATTERNS ABOUT A BAR MAGNET COLLECTOR

The magnetic field has more fundamental components which integrate in the virtual state to form it when two successive orthorotational thresholds (quantum thresholds) are breached. Furthermore, in the picture of a bar magnet taped to the



Magnet 3/4" dia. x 6" long taped to faco of a color TV tube approximately 1200 Gauss.



South pole end of same magnet tapod to face of color TV tube.

Photo 2. Hyperfield **flux in a magnetic field.**



North pole end of same magnet taped to face of color TV tube.

face of a color television tube, one can see that the hyperfield orthogonal circulations in the magnetic field arc not symmetric about the two poles; i.e., the pattern is quite different around the north magnetic pole from that around the south magnetic pole.

Around the north pole, the hyperfield circulation is emitted in the form of a hexagonal solid. Thus there is an intense hexagonal orthorotation about the north pole. Radiating conically out longitudinally is a toroidal null zone, at an angle to the ongitudinal axis projected away from the north pole into space. At an even higher angle, another concentric cone is radiated out in the same direction; this higher cone is an emission cone where photons are being generated. Thus viewed from the north end, and at a distance from the magnet, the pattern shown in the right figure of the slide emerges, The pattern is a ring of light or light bubbles, surrounding a concentric ring neutral zone, which in turn surrounds a hexagonal center of intense emission.

If frame three of the Vestigia mystery light photos is examined meticulously, this exact pattern is seen, allowing for the dynamism of the phenomena and for slight nonlinearity of the spatial medium in which the photons are emerging by orthorotation.

On the other hand, looking at the left hand figure on the slide, we see that the outer emission ring is *so* thin that it has effectively disappeared; it is radiated at right angles to the magnetic longitudinal axle. The middle null area is also much wider. The densely emitting core area now has a relatively circular cross section at a distance. So the pattern of photon emission that is seen from this end is simply a dense roundcore. Frames four and five of the Vestigia photos demonstrate variations of this effect, viewed at a slight off-axis angle.

When the magnetic field is observed from the side, only the hexagonal dense emission core of the north pole is seen. In the south pole area, we are looking into a large null area, so no emission at all is seen. Frame eight is approaching this result, with a slight deviation from an orthogonal viewing axis. Also, frames seven and eight exhibit composite structuring from several (three or more) side-by-side magnets of square-end configuration, where the magnet cross section is wide, looking at the end. In that case, the top right picture would be elongated, giving a stretched hexagonal dense core surrounded by a concentric null zone of oval shape, further surrounded by a concentric thin emission zone of oval shape. In frames seven and eight, the outer thin emission zone is roughly spherical, not oval. However, a combination (further composite) of the lower right picture case and the upper right picture case could give the pattern exhibited by frames seven and eight.

And as I show clearly elsewhere, orthorotated hyperfield energy usually emerges with a "burst-in" effect which, in free space, assumes a spherical shape. Thus one would expect a dynamically bubbling sphere of light at the initial "burst-in" of the phenomena, and frame two exhibits this effect.

So the expected hyperfield generation of photon patterns about a localized region of magnetic field (such as a bar magnet or composite grouping of bar magnets), when that localized region of field is in the collection or burst-in and decay gradually mode, would account precisely for the particular structured patterns photographed by Vestigia.

Again, this does not prove the hyperfield hypothesis, but shows that the structural patterns obtained are consistent with it.

HYPERFIELD CIRCULATION PATTERNS ABOVE A MAGNETIZED RAILROAD TRACK

Figure 1 shows the hyperfield circulation patterns above a magnetized railroad track. The general setup of the Vestigia experiment is shown. The rails are oriented parallel to the fault line, which means that the rock stresses are oriented perpendicular to the rails. Thus the telluric currents piezoelectrically induced by the quartz and other minerals in the local granite are also generally oriented perpendicular to the rails and below them.

These piezoelectric currents thus constitute effective coils about the rails, magnetizing them weakly along their length, but this is in addition to their normal magnetism, if any, picked up due to the specific local and atmospheric electricity changes.

In the hyperfield flow pattern for two magnets which are lengthwise parellel and viewed from the end, a primary hyperfield circulation pattern exists both between the two rails and in the air above them. The location is the same, whichever end of the parallel magnets one looks into; however, the circulation direction changes with the change of ends. As the strength of the magnetization of the two magnets changes, the vertical distance above the rails to the plane of the center of the hyperfield circulation pattern (primary) changes. The stronger the field, the higher the center of the pattern, and vice versa.

In addition a secondary (weaker) hyperfield circulation area exists over both rails as shown. As the piezoelectric currents fluctuate in direction and intensity, corresponding fluctuations in the magnetization of the two rails occur.


SECONDARY HYPERFIELD CIRCULATION AREA
PRIMARY HYPERFIELD CIRCULATION AREA
EFFECTIVE COIL
EFFECTIVE COIL
STEEL RAILS
CROSSTIE
TELLURIC CURRENTS DUE TO
PIEZOELECTRIC ACTIVITY

Fig. 1. Hyperfield circulation patterns above a magnetized railroad track

Thus, over the rails there exists a sort of undulating tubular tunnel of primary hyperfield circulation, surrounded by a larger undulating tunnel of half-elliptical cross section. In addition, the terrain and foliage features nearby will have their own hyperfield circulation areas, with flowing currents of hyperfield circulations between them and undulating tunnels over the rails. The final result is a complex flow pattern, which is further modified by atmospheric, ionic, and electrical currents. So a mystery light can kindle into a burst in one of the primary circulation areas and move, usually in a faltering or drift-dart-pause manner, along the undulating tunnels above the railroad track. Structural changes may then be noted as the geometrical aspect between the light and the observer-instrument changes, as additional collection-kindling occurs, and as discharge dampening occurs with the passage of time, due to the discharge time constants of the oscillations of the time dimension itself that are induced by kindling and burst-in.

Note that in the kindling process, the hyperfield circulation in a localized area suddenly bursts into magnetic or electromagnetic field. Since it enters the laboratory frame at right angles, orthogonal relationships result. Furthermore, the appearance of a kindled magnetic field form will change the capacitance between the rails, and a capacitance test will indicate this, as if a conducting body were there. The localized magnet or geometrical piece of electromagnetic field is locked in and maintained as long as the hyperfield flux remains above the kindling threshold. However, since the burst-in of the hyperspatial flux into electromagnetic energy involves the shocking into oscillation of the time channel, an oscillator effect is produced, and electromagnetic signal energy may be radiated from the light form, usually through one of the magic frequency windows which thinly interconnect orthogonal three-spaces. One of these windows is located at about 38,000 to 40,000 Hertz.

Such a signal was indeed recorded in the Vestigia experiment.

Also, at night time the time channel quenching effect of visible light is materially reduced since most visible light is absent. Further, the light-shielded quartz in the underground rocks has two magic windows: one in the infrared and one in the ultraviolet. So the area of the Vestigia experiment constitutes a gigantic kindling mechanism par excellence. With sufficient piezoelectric activity, the collected hyperspatial flux exceeds the kindling threshold required for burst-in, and localized triggering of a discharge or discharges can be initiated in the proper area. The thousands of feet of wire further enhance the collecting and kindling mechanisms. From a physics viewpoint, the living observer is the initiator who initiates the collapse of the wave function, in turn initiating observation. The same ability or property also is required to initiate the kindling of hyperspatial flux into the normal three-space, in my opinion. This is consistent with the rather wide collection of data presented here to show that a living observer can generate or extinguish electrostatic, magnetic, and electromagneic fields at a distance, even through a superconductive farraday shield. The thought photography examples presented also show that electromagnetic field (light) can sometimes be generated by a living human being, and impress the camera film with the visible light spectrum, even though the light is not consciously seen by the observer's eye. It also appears that frequencies of something other than light, in the infrared and ultraviolet frequency regions, can enter through IR/UV windows and then rotate into the ordinary visible light spectrum and ordinary visible light energy. Such effects also appear to be present in the


COMMAND POST
light (?)
POST 2
wire and other collector mechanisms
wire and other collector mechanisms

Fig. 2. The cyborg effect and orthorotational sensitivity

Vestigia experiment, since the cameraman himself saw no light, but other posts did. Thus an additional directional effect of the rotation into visible light seemed to be involved.

Since so-called thought energy is simply hyperspatial flux which has a minute one-to-one coherence in its crosstalk with the laboratory frame, the section explaining thought photography deals with hyperspatial mechanisms that are also applicable to mystery lights.

THE CYBORG EFFECT AND ORTHOROTATIONAL SENSITIVITY

In Figure 2, I show how it is possible that one team sees the light and a second team does not.

In the inceptive cyborg effect, each person, each instrument, the wiring, other collectors including the sensors, the other paraphernalia of the environment such as railroad tracks, rocks and their minerals, etc. are all cyborged together into a single instrument in the hyperfield domain. This is precisely because the hyperfield domain is the time channel, and all of these exist at the same time. Further, in the experimental locality, the difference in time between observers, equipment, devices, and aspects is small, because the distances between pieces are relatively small. Hence to the hyperfield channel an appreciable degree of coherence exists between the various components of the hypersensory cyborg. Yet the overall pattern of coherence has high points and lower points in it, and pattern groupings that vary with the grouping of components. Thus the subgrouping at the command post, for example, may be expected to differ in its hyperfield characteristics from the subgrouping at Post 2. Furthermore, the bulk of the collection wiring, and the rails, were outside the command post, so the greatest collection might be expected at this station.

In addition, the human components of the subgroupings vary appreciably in their sensitivity to hyperfields. Some persons are more positive or attuned than others, particularly in their unconscious minds. In fact, some persons are quite negative and are squelchers of the hyperfield effects — the negative psi effect is well known in experimental parapsychology. However, it is reasonable to assume that there were no psi-negatives on the Vestigia experiment; but there was probably an appreciable variation in the degree of psi-positive exhibition in the various personal unconsciousnesses. So it is understandable that one post may not see the light, while another would. And with the appreciably greater collection and kindling outside the command post, we would expect the sighting to occur there, if anywhere, as long as a real psi-negative was not present in the command post. And the experiment seems to have exhibited this effect as expected.

Also, I must point out that the visual mechanism for detecting orthorotating energy is different from that for detecting normal visible light, unless the orthorotating hyperenergy is extremely strong and overrides the squelch effect of normal light. (At night the degree required to go into visible light is less.) At any rate, the orthorotational hyperfield energy comes in through the infrared and ultraviolet windows for the most part, and then orthorotates into the visible light region, changing its frequency as it is absorbed by or interacts with a receiver.

Further, the orthorotational energy does not travel through three-dimensional space in the accepted sense that a signal normally does; rather, it is entering this three-dimensional space all at once from a region orthogonal to the entire three-space. It is therefore entering all components of the tuning-receiving instantaneously and simultaneously, or holographically, if one extends the term. Each subgrouping component of the cyborg exerts its own tuning-damping constant(s) upon this holographic signal entry, giving differing degrees of receptive sensitivity, or signal strength, or signal to noise ratio.

So the signal enters each part of the cyborg holographically and the reception characteristics of that portion dampen or enhance the degree of orthorotation into the normal electromagnetic field. Further, the actual orthorotation into the electromagnetic field is occurring primarily at the actual sensor.

For a human being, the primary sensors are the retinal surface of the eye and the skin. The retina is actually a complex structured piece of the brain, so to speak, and extensive nervous system complexes are located there which do extensive on-site signal processing. The unconscious mind of the individual directly interacts at the retina with signals received by the retina, either by hyperspatial orthorotation or by ordinary light. So the individual nervous system is highly variable in its interactions with the hyperfield energy that is orthorotating into ordinary electromagnetic energy in the interaction itself. Briefly, the unconscious state of the observer partially shapes and forms the observed.

In a camera, the sensor is the film. It is thus entirely possible for a camera to record light energy that is holographically rotated in from hyperfield energy without the cameraman himself seeing anything at all. This is especially true when the camera film is sensitive to infrared and ultraviolet to an appreciable degree. A camera containing infrared-sensitive film will interact readily with hyperfield energy because it is open in the magic window between orthogonal frames. A camera containing ordinary film, which is less sensitive to infrared, will interact much less in the magic window because it barely extends into it.

Thus, with other variables held constant, one would expect the infrared camera to record hyperfield energy to a much greater degree than the camera containing ordinary film, and indeed the Vestigia experiment has demonstrated this effect.

Furthermore, the experiment exhibited heightened kindling and collection outside the command post due to the distribution of wiring, components, and rails.

ADDITIONAL FACTORS CONSISTENT WITH THE VESTIGIA EXPERIMENT

First, a cooling effect is often associated with the appearance of paranormal phenomena; this effect is well documented in the literature.

A corollary effect also exists when hyperfield energy is being collected and kindled. Just as lowering the electronic noise in an amplifier increases the fidelity of the signal, lowering the local environmental temperature reduces the "noise" that is blocking the collection and kindling of hyperfield energy. Specifically, reducing the temperature reduces the photon emission and absorption activity of the environment. This lowers the background electromagnetic noise which inhibits orthorotation of the hyperfield energy into electromagnetic field energy. Since photon activity is reduced, the consequent photon squelching of the time channel (precisely detailed elsewhere in this book) is also reduced. This in turn lowers the threshold required for kindling to occur.

Also, a Geiger tube often acts as a collector and amplifier of bioenergy and hyperfield energy. (The association of Geiger counter readings with UFO phenomena has been frequently noted in the literature.)

The Geiger tube may become a detector of hyperfield energy, because the tube's kindling threshold may be significantly lower than that of the environment or of other components such as the observer's eye. Kindling across the Geiger tube's lower threshold simply creates an electrostatic field inside the gas in the tube. In fact, it is the potential ionic current that is the collector, since hyperfields accumulate along probability paths as well as along observationally determined paths, communicating with both future and past. At any rate, the kindling of an electrostatic field in the Geiger tube may result in ionization of the gas if the field is of sufficient intensity. An avalanche discharge may occur and the Geiger counter may indicate a reading (usually appreciable or full scale). This may occur even though no visual phenomena are seen and even though other sensors receive no indication. This reading of the Geiger counter is of course not due to radioactivity. A Geiger *counter does not indicate radioactivity;* rather it indicates appropriate ionization of its internal gas. In this case, the kindling of hyperfield energy into electrostatic field occurred, generating the ionization in the Geiger tube gas.

Note that this occurred in consonance with the visual sighting and the infrared film photos, and when no visual sighting resulted and photos were not taken. Furthermore, as I point out elsewhere, the kindling and burst-in of energy has a discharge time constant, due to the discharge time constant of the oscillation of time that occurs at kindling and burst-in. Depending on the initial amplitude of oscillation at burst-in, the time required to lower the burst amplitude to kindling threshold and below varies. When the amplitude drops below the kindling threshold, kindling and burst-in cease and the hyperfield-induced electrostatic field in the Geiger tube vanishes, stopping the hyperfield-induced ionization of the gas in the tube. The Geiger counter reading then drops back to normal background reading.

The variable amplitude at burst-in and the consequent variation in the time required for the Geiger counter to cease reading the hyperfield-induced ionization were demonstrated in the Vestigia experiment. Furthermore, the Geiger counter showed a reading twice when visual phenomena were not seen and cameras did not record. Of course, no photos were taken during the Geiger counter readings.

Finally, the drop in barometric pressure also lowers the molecular collision activity of the local atmosphere, and lowers the rate of production of collision ions, electric currents, and photons induced by the collision activity. This reduces the electromagnetic noise, which is squelching the collection mechanism and raising the kindling threshold. It reduces the kindling threshold, making orthorotation of hyperfield energy into electromagnetic-electrostatic-magnetic field energy easier.

Thus, according to hyperfield theory, the major features of the Vestigia mystery light experiment are seen to be within normal expectations. Again, this does not prove the hyperfield-orthorotational hypothesis, but it is consistent with it and therefore constitutes an important piece of evidence for the theory.

Also, I should stress that the piezoelectric theory is in fact included in the hyperfield theory, and is a vital part of it. In other words, the hyperfield theory is an extension of the piezoelectric theory, and in my opinion the extension is necessary if the piezoelectric effect is to fit the experimental results. There are no contradictions between the two theories since one is merely an extension of the other.

REMOTE VIEWING

In a classic series of carefully controlled experiments at SRI International, physicists Hal Puthoff and Russell Targ have shown that the human mind can produce evidence of its ability to see at a distance, and also to anticipate the future.

In their protocol one experimenter goes to a distant target, which is selected randomly for him en route, and a subject in the laboratory tries to describe the target scene, both orally and by sketching on paper. The experimenter in the field uses a random number generator to select one sealed envelope out of a group held by a controller accompanying him. The selected envelope is then opened, and that target becomes the target for the experiment. The targets are preselected with rigorous protocol by a group not involved in the experiment.

In the experiment shown here, the target selected was a rather unusually shaped playground merry-go-round, with handrails made of bent pipes, as shown in the two photographs. The laboratory subject, in addition to describing the scene verbally, made the sketches shown at the right. As can be seen, the channel is noisy, but there is definitely signal in it.

Puthoff and Targ also obtained some of the best experimental results when the laboratory subject was asked to describe the scene which the field team would see in the future, the target selection via random number generator not yet having been made. A wide variety of subjects — including persons hostile to parapsychology — were used by Puthoff and Targ in their experiments, with good results.

Each particle of mass in our bodies represents one closure of the entire universe — yielding a holographic reality — and deeper communication with ourselves is identical to communication with the universe, including any part of it, at any distance. Furthermore, in hyperspace the future and the past are all present. Since a particle does indeed exhibit a four-dimensional component for 1/137 of the time, each particle does connect to the future and to the past. With selective tuning


some sort of structure or thing on top of appendage rod in a general sense like rounded dome-type top
lightening rod
TOP VIEW
medium darkness thing
rod black or brassy

Target: Playground Merry-Go-Round.

Responses.

Photo 3. Remote viewing.

and kindling any part of this holographic reality is accessible. However, because of the smallness of a single selective signal in the midst of the totality, the channel is quite noisy. For this reason skilled psychics ~ persons who have been found to have a greater fidelity of selective tuning - can be expected to produce better results than the normal person.

Puthoff and Targ's results have also been successfully repeated by other experimenters.



T. Henry Moray makes some final adjustmonts In tuning his radiant energy device to tap zero-point vacuum energy.

THE MORAY RADIANT ENERGY DEVICE

In the early 1900's, Dr. T. Henry Moray of Salt Lake City produced his first device to tap energy from the metafrequency oscillations of empty space itself. Eventually Moray was able to produce a free energy device weighing sixty pounds and producing 50,000 watts of electricity for several hours. Ironically, although he demonstrated his device repeatedly to scientists and engineers, Moray was unable to obtain funding to develop the device further into a useable power station that would furnish electrical power on a mass scale.

As a boy, Moray had been deeply inspired by the greatest electrical genius of all time, Nikola Tesla. His imagination was especially fired by Tesla's claims to have knowledge of an energy source greater than ordinary electricity, and by Tesla's emphasis on frequencies as the stuff of the universe. When Moray finished high school in Salt Lake City, he went abroad to study, and took resident examinations for his doctorate in electrical engineering from the University of Uppsala, Sweden, during the period 1912—14. Returning home, his diploma and credentials were interrupted by World War I, and the University mailed him these items in I918 after the war.



Here **the** Moray radiant energy device is providing free power to 35 100-watt lamps and a 1200-watt Iron.



Once tuned in, the power continues and is free for the taking.

Photo 4. The Moray radiant energy device.

Shortly thereafter, Moray produced his first elementary device that delivered measureable electrical power, and he continued to work diligently on energy devices when he had time. In the 1920's and 1930's he steadily improved his devices, particularly his detector tube, the only real secret of the device according *to* Moray himself. In his book, *The Sea of Energy in Which the Earth Floats,* Moray presents documented evidence that he invented the first transistor-type valve in 1925, far ahead of the officially recognized discovery of the transistor. In his free energy detector tube Moray apparently used, inside the tube itself, a variation of this transistor idea — a small rounded pellet of a mixture of triboluminescent zinc, a semiconductor material, and a radioactive or fissile material. His patent application (for which a patent has never been granted) was filed on July 13, 1931, long before the advent of the Bell Laboratories' transistor.

In test after test Moray demonstrated his radiant energy device to electrical engineering professors, congressmen, dignitaries, and a host of other visitors to his laboratory. Once he even took the device several miles out in the country, away from all power lines, to prove that he was not simply tuning in to energy being clandestinely radiated from some other part of his laboratory. Several times he allowed independent investigators to completely disassemble his device and reassemble it, then reactivate it themselves. In all tests, he was successful in demonstrating that the device could produce energy output without any appreciable energy input. According to exhaustive documentation, no one was ever able to prove that the device was fraudulent or that Moray had not accomplished exactly what he claimed. On the other hand, the records are full of signed statements from physicists, electrical engineers, and scientists who came to the Moray laboratory as doubting Thomases and left with the complete conviction that Moray had indeed succeeded in tapping a universal source of energy that could produce free electrical power.

But in the face of all of this, the U.S. Patent Office refused to grant Moray a patent, first, because his device used a cold cathode in the tubes (the patent examiner asserted it was common knowledge that a heated cathode was necessary to obtain electrons) and, second, because he failed to identify the source of the energy. All sorts of irrelevant patents and devices were also presented as being infringed upon or duplicated by Moray's work. Each of these objections was patiently answered and nullified by Moray; nonetheless, the patent has still not been issued to this day, although the Morays still keep the patent application current.

One of Moray's efforts to develop the machine involved an association with the Rural Electrification Agency for a short time before World War II. At that time, the R.E.A. was apparently infiltrated by Communist sympathizers and high level officials of a decidedly pinkish tinge. These officials continually urged Moray to turn over all details of his device to the Soviet Union, and even arranged the visit of high-level Soviet scientists to the Moray laboratory to see the device in operation. On the initiative of the Communist-infiltrated R.E.A., one person — let us call him "Z" — spent about two months in Moray's laboratory, and succeeded in worming his way into Moray's full confidence. Moray eventually disclosed most of the details of the construction of his special valve to "Z" — the only person in whom Moray ever completely confided.

There is strong reason to believe that "Z" was a Soviet agent, and that this is where the Soviets first obtained the impetus to develop the hyperspace amplifiers later used in their psychotronic weapons.

However, Moray became quite alarmed at the continued attempts of his R.E.A. contacts to get the device into the hands of the Russians. He eventually concluded that he had become involved with a governmental group filled with radicals and reactionaries. Moray became concerned that fifth column activity was actually directed against him in an attempt to steal his device. Quotes from the *Salt Lake Tribune* of December 2, 1941, attributed to Representative Thomas D. Winter, imply that Moray's suspicions of the R.E.A. were well founded, since Representative Winter called for a full-scale investigation of the R.E.A. on the grounds of Communist infiltration. Indeed, Moray was wounded by gunshot in his own laboratory on March 2, 1940, which seems to suggest that his fears and suspicions were based on fact. Moray severed his association with the R.E.A. in February 1941.

However, his basic unit had been destroyed by a hammerslinging witness in 1939; it is not clear whether or not this was the work of "Z" or of someone else. According to his son, John Moray, the man who broke his unit, as well as other interested groups, wanted complete disclosure of the materials and construction - nothing more or less. John Moray, who operates the Research Institute in Salt Lake City, has been trying to continue his father's work since the basic unit was destroyed. Dr. Moray himself died in May 1974.

According to John Moray, highly energetic cosmic rays from space are tapped by the machine, which is in subharmonic resonance with this high-frequency energy level, and it converts this energy level into a usable form of electricity. However, John Moray's use of the term "cosmic ray" is not necessarily the same as that of modern physics, but in fact is the same as the present concept of "zero-point" energy of vacuum. T. Henry Moray envisioned all space filled with tremendously high frequency vibrations carrying vast and incalculable amounts of pure raw energy. He envisioned the dynamic universe as a turbulent source of great energy, just as the ocean waves carry energy throughout the earth. This was also the vision of Tesla, and after him of Clifford and Einstein, who turned the attention of general relativity to the problem of the nature of the vacuum itself. Clifford and Einstein founded a branch of physics that has come to be known as quantum geometrodynamics, the study of energetic change that occurs in little pieces, including the concept that very small lengths of space, or pure vacuum, themselves oscillate at great frequency and with great energy. In Moray's day relativity was still a strange and unproven branch of physics, suspected and rejected by most of the physicists of the day, and quantum physics was still in the process of being worked out. There was no theory whatsoever predicting that empty space itself not only contained prodigious quantities of energy, but in fact *was* prodigious quantities of energy. But slowly, over the decades, the picture has changed, and the modern followers of quantum geometrodynamics assert the truth of Tesla's original vision. Today we know that one cubic centimeter of pure vacuum contains enough energy to condense into 10^{80}—10^{120} grams of matter! Thus the major part of Moray's thesis — that vacuum itself contains unlimited energy — is vindicated today. In this sense empty space is like a gigantic, restless ocean, and Moray's free energy "tapping" device is no more mysterious than the water wheel. In other words, his thesis that the energy is there to be tapped is correct; it only awaits a practical method to tap it in order to solve the energy problems of mankind forever.

Moray thus is vindicated as a man ahead of his time, who simply built a device before any theory existed to explain its operation. Moray met with constant opposition, and his life and that of his family was anything but pleasant. Certain pressure groups constantly tried to force him into selling for almost nothing, or to disclose the secrets of his valve's construction. He was often attacked and he was sometimes shot at on the city streets. In fact, his life was threatened so often that he was forced to install bulletproof glass in his automobile. His laboratory was broken into, some of his components and papers were stolen, and his dogs were continually being killed. Moray was shot in his own laboratory, and he himself always carried a gun. Because he was harassed ceaselessly, over the years he became understandably suspicious and close-mouthed about his work. He sometimes greeted visitors at his desk with a loaded pistol lying on the desk within easy reach, and occasionally confirmed that he would not hesitate to shoot if he were attacked or threatened. One of his greatest fears was that big interests would take up his invention and simply shelve it to keep it from benefiting the public. When large companies made him offers, he always demanded written guarantees that the device would be put into production and sold to everyone, once it was developed.

Moray also realized the potential of his device as a weapon. He was fully aware that the only difference between a controlled energy device and an explosion is the rate of release of the energy. According to John Moray, his father received an offer to go to Japan in 1938 because he had built a deathray which operated off the device. According to John, a representative of the Japanese government came to the laboratory and offered a position to Moray, but he refused. Allegedly Moray had managed to rig the device so that it projected a ray of energy in a beam, and could kill mice instantly at over fifty feet. When radiated by the beam, the mice were carbonized immediately. They appeared frozen, but nothing was left except their shells, and they simply fell apart when touched.

In one experiment Moray ran his device for 157 hours without any connection to external power sources, and produced over fifty kilowatts of power during the test. He also found that an additional fifty kilowatts could be added by simply providing another tap further back in the circuit. When he shut the device off from this test, he had proven once and for all that the device was generating electrical energy from free and natural sources without batteries or external power. During this test nothing in the machine heated up; instead, all parts of the circuit ran absolutely cold. This alone is totally unexplainable by ordinary electromagnetic theory, and it strongly implies the truth of Moray's assertion that the device simply collects the energy in each of its stages in a subharmonically resonant manner, in synchronization with the extremely high frequency cosmic oscillations. In other words, since the parts of the machine ran cold, it is clear that the energy was being simultaneously collected at each stage rather than being processed through the individual stages in serial order, since serial processing in the conventional electrical sense would lead to resistance heating of the circuit elements.

Moray's device used twenty-nine stages of his special detector valves, which were difficult to produce, costing about five hundred dollars each. Only about one in four proved suitable for operation. He also had difficulty in obtaining sufficiently pure materials to make his special mixture for the pellet that enabled tube operation in a one-way gating fashion. Moray explained that his device was based



Photo 5. An Atlantean power crystal?

on the discovery of a mixture that would act as a one-way gate for the high frequency oscillations of space, so that the energy could go through the material more readily in one direction than another. Thus it was like a one-way gate valve to an ocean wave; the energy "water" could flow in in each valve, but was prevented from flowing back out. The assemblage of multiple stages thus provided a series of collectors which contained enough energy to be useful. Theoretically there was no limit to the number of collectors that could be added, and so there appeared to be no limit to the energy that such a device could produce.

AN ATLANTEAN POWER CRYSTAL?

The next two photographs are of a most amazing quartz crystal sphere removed from a chamber in a pyramid underneath the surface of the ocean in the Bermuda Triangle. Dr. Ray Brown purportedly removed the object in a dive while treasure-hunting with several friends after a storm had stirred the sandy ocean floor in 1968. Brown describes how he swam into a chamber in the pyramid after swimming around it three times, and how he saw seven stone seats surrounding two handlike stone holders for the crystal in the center of a table or dais, with a two inch metallic rod running down vertically from the roof of the stone chamber and pointing directly at the crystal. Brown plucked the crystal from the holder and ascended to the surface; he found that his companions had brought some nonoperative objects to the surface which appeared to be some sort of strange electrical apparatus.

Brown himself had a strange foreboding and a strong impulse against returning to the site, and so he refused to do so. Three of his companions reportedly returned at a later date, and their boats were found floating abandoned in the Triangle. The three men were never seen again.

The crystal does indeed have some strange properties. In the first picture one can clearly see a very sharply outlined, pyramid shaped inclusion inside the quartz. The pyramidal inclusion is dark, but the crystal is absolutely clear. However, the second photo shows that the quartz is milky when seen from a different angle. Here three pyramids can be seen.

Other objects have been seen and photographed in the crystal from time to time. In *The Pyramid Guide,* Vol. V, No. 4, there is a photograph of the crystal showing a very distinct, humanlike iris and eyelid appearing in it, making it resemble nothing so much as a giant human eye. In that photo the three pyramids are not visible.

While I have not personally investigated the crystal and examined it in detail, some general remarks can be made. (1) Brown reported finding the pyramid after a huge storm had stirred the ocean, including the ocean's sandy bottom. This had revealed outlines on the bottom resembling buildings, which had attracted the attention of the treasure hunters. (2) Such a storm, over the ocean's great water mass, is an excellent kindler of bioenergy. In other words, Brown and his companions were definitely in a place which should have had an enormous kindling of bioenergy from the biosphere and the collective human unconscious. (3) Sufficient publicity has been given the Bermuda Triangle's mysterious disappearances to have its alleged ability to open a window between worlds implanted deeply into the unconsciousnesses of a large number of persons. (4) Brown was with a group of persons who were sharing the same sensations with the storm and surrounding area, so there was sufficient coherence of their personal unconsciousnesses to accomplish at least some degree of tuning. (5) The legends of Atlantis were in a great revival period in the late 1960's from the popularizing of Edgar Cayce's work and other material, as indeed was the Egypt/pyramid/Atlantis mythology in general.

So conditions were very ripe for a tulpoidal contact (see Part Two) of extensive magnitude — perhaps even to the point of tuning in the ruins and pyramid for a period. Brown also reported sensing an omniscientlike presence, which is symptomatic of many such tulpoidal contacts or materializations.

In such a case, Brown could have actually swum into such a pyramid that had materialized from the collective unconscious — which after all has the psychokinetic power of Uri Geller times ten to the four billionth power or so, and which largely maintains the format of our physical reality in the first place. The collective unconscious has no difficulty in creating even many alternate worlds or materializing and dematerializing entire areas, let alone in producing a single pyramid and a ruined city.

Brown's action in plucking the crystal out of its holder and swimming back to the surface would also have constituted a tuning/kindling which was "returning with the crystal into the normal world" — in which case it could have been tuned into complete stability so that it would endure, rather than fade away as do most tulpoids.

Until we have developed psychotronic instruments to scan the crystal and reveal its true story, we cannot say for certain that any of the above actually happened, and that some sort of delusion or fakery was not involved. The point is, it could have happened just as Brown reported it, in the theory I have constructed in the second part of this book.

Until we free our minds from the present bias that physical reality is always permanent and unchanging, we shall never be able to adequately investigate such phenomena as Brown's strange crystal.

THE CRYSTAL SKULL

It appears that at least some of the ancient peoples understood certain aspects of psychotronics and even possessed some psychotronic devices.

An example of such a psychotronic device is shown in the next two pictures, reprinted here with the kind permission of Bill Cox, from *The Pyramid Guide,* No. 17, May-June, Vol. Ill, No. 5.

To quote directly from *The Pyramid Guide:*

> **These are two views of the famed crystal skull... completely hand-formed, possibly centuries in the making from a single block of hard quartz crystal. It was recovered from beneath the altar ruins, within the jungle-covered, 7 1/2 acre citadel of the ancient Mayan city of Lubaantu'n by explorer F.A. Mitchell-Hedges in 1927. A several-stories-high pyramid was also found within the citadel complex. The skull, possibly of Atlantean and/or Babylonian origin may have been brought to the Americas by the Phoenicians around 1,000 B.C. Frank Dorland says historical records suggest the skull may have been held in the London inner-sanctum of the Knights Templar prior to the Holy Wars. The high priests probably executed ceremonial magic with the skull; a ribbon-like prism in the cranium acts as a magnifier. Hollow light pipes projecting upward from the base permit light reflections from the eye-sockets. The moveable jaw easily coordinated motion with speech. Lesser quality crystal skulls exhibited in the British and Paris museums, and miniature versions, lack the Mitchell-Hedges skull's brilliant craftsmanship**



Photo 6. The crystal skull.

Two views of the famed crystal skull. Completely hand-formed, possibly centuries in its making from a single block of hard quartz crystal. It was recovered from beneath the altar ruins within the jungle-covered seven-and-a-half acre citadel of the ancient Mayan city of Lubaantu'n by explorer FA. Mitchell-Hedges in 1927. A several-stories-high pyramid was also found within the citadel complex. The skull, possibly of Atlantean and/or Babylonian origin, may have been brought to the Americas by the Phoenicians around 1,000 B.C. The high priests probably executed ceremonial magic with the skull; a ribbon-like prism in the cranium acts as a magnifier. Hollow light pipes projecting upward from the base permit light reflections from the eye sockets. The moveable jaw easily coordinates motion with speech. Lesser quality crystal skulls exhibited In the British and Paris museums, and miniature versions, lack the Mitchell-Hedges skull's brilliant craftsmanship.

One of the major African tribes is also reported to have once possessed such a crystal skull as a holy object and the center of their religion. Their skull was reportedly stolen by a white thief in the early 1800's,

So let us now discuss sonic of the peculiar properties of such a device.

First, quartz is a very hard substance and not easily worked at all. Making such a perfectly carved piece, with removable hinged jaw and eye lenses, must have consumed a tremendous amount of manual labor and considerable time, even centuries. Such an effort is not lightly undertaken; usually there is an overpowering reason for such persistence. In this case, there may well have been such a reason, and ancient priests may well have known it.

Quartz has magic qualities from a psychotronic point of view. It is open to both the ultraviolet and the infrared, and so it possesses two magic windows into the hyperframes, bioframes, orthogonal frames, and other realities. Since the third and higher bioframes (orthoworlds) are all mind worlds, quartz has open magic windows into the mind and mind energies. Thus Frank Dorland surmises correctly that the device can amplify and focus mental energies.

Furthermore, quartz is a piezoelectric crystal. Being crystalline, it possesses a lattice, a regular array of molecular stages. Thus it possesses a large number of identical stages, which is important for hyperchannel amplification.

Properly shielded against visible light, or in dim light, the crystal skull thus can function as a mental amplifier in the hands of a skilled user. Also, the quartz it piezoelectric; multistaged electrical piezoelectric currents are natural hyperenergy-hyperfield collectors, and under the proper conditions the quartz can produce heat and light, since collected hyperfield energy can be orthorotated into electromagnetic field by kindling. It can even produce these effects at a distance due to the hyperchannel circulation patterns surrounding a magnetic field or a localized area of magnetic field. The easiest place to produce effects with the skull would be inside another human head (in the brain).

So, in the hands of a skilled practitioner, the skull is (1) a collector of bioenergy, capable of turning this into electromagnetic energy and physical effects, (2) a form resonance inductor, i.e., a sort of super witness which matches the general shape of the human skull and is capable of resonating with a human skull (and thus with its contained brain) at a distance through hyperspace, and (3) a psychotronic device capable of producing psychotronic effects such as the augmentation of healing energy, psychic attack, telepathy, clairvoyance, precognition, and psychokinesis, where these initiative abilities are possessed by the user or practitioner.

Thus, in the hands of an adept, the crystal skull is indeed a formidable device, and one can well understand how the motivation existed to make it, even though its production may have taken centuries. Since in the ancient days knowledge was zealously guarded and usually incorporated directly into religion, such psychotronic artifacts as the crystal skull would have been regarded as the most powerful, hence the most sacred, of objects. One can therefore speculate that the elite of the elite of the priesthood were the only ones who knew of and were taught how to use the skull, and that this information was guarded extremely closely. The legend of such a skull existing as a central part of the religious magic of an African tribe is not beyond belief. Ordinary crystal balls, which are certainly made more easily, may have originated from the secret rites connected with the skull. An ordinary good quality, clear quartz crystal may well have been the substitute for priests who did not belong to the supreme inner circle, or the device used when a skull was not available.

I have seen at least one picture of an optical image which spontaneously formed in the crystal skull; the image closely resembled that of the Mayan astronomical observatory at Chichen Itza.

To give a simple example of how the skull may have been used by a skilled priest, let us suppose the priest had an enemy he wished to disable or kill. With the proper psychic exercises he could have induced an increase in his own psychic energy. Then, using the crystal skull, he could simply have visualized the image of his enemy's face, and visualized the energy or light pouring into his enemy's head. The stability of the imagery is more important than effort of will.

At any rate, steady application of this imagery starts the bioenergy projection into the enemy's head and brain, and it collects there. Collection to the kindling threshold starts turning the bioenergy into electromagnetic field. At this point, a host of effects could be produced, depending upon the specific wish and induction by the priest. The effects include sharp pain (such as migraine headache); a leaden mass or frozen mind in which the brain activity itself is slowly frozen and stopped; the generation of a strong, overpowering emotion such as rage, hatred, panic, or terrible sadness; a sharp attack on the mind itself, as if a saw or knife were slashing a physical object to bits; numbness of the body or selected portions of it; interruption of the heart's functioning; kindling of the brain and nervous system into seizures, convulsions, or violent muscular spasms (capable of breaking bones); and an increase in blood pressure until the vessels swell and burst. In the hands of a priest who was strong in psychokinetic ability, this amplified ability would have been projected through hyperspace to the unfortunate victim's vicinity; objects such as stones could suddenly have levitated and hurled themselves at him, bushes and small trees could have enveloped him, etc. All in all, the skull can be used as a terrible weapon.

A few of these effects, and others I have not described, are presently in use by certain lunatic fringe groups in the United States; they use basic devices other than a crystal skull. I have been subjected to several strong attacks, and can vouch for their effectiveness if the target person is unskilled in shielding himself or evading such attack. In two cases I was nearly killed, and in a third case in substantial jeopardy.

Use of the crystal skull by a group of priests would give even more power, for from such a group the kindling level at which bioenergy orthorotates into electromagnetic field energy is much more easily approached. The inceptive power is of course usable for either good or evil purposes. Good purposes would include amplifying psychic healing; curing fevers and other infections; stopping internal bleeding; dematerializing growths and tumors; placing a person into deep anesthetic sleep so that a surgical operation can be performed; treating soil, seeds, or plants to assist sprouting and growth; treating emotional disorders with cancellation thought forms (contrary forms), and projecting them directly onto the unconscious to neutralize the disturbing form; and communicating telepathically at a distance.

A 300-year fabrication period is more credible if we recognize that the quartz crystal would have been usable from the beginning, just as is a crystal ball. So the high priests could have used the rare clear crystal (the skull is made from a single crystal), while priests recently initiated into the level that knew of crystal devices worked on it when it was not needed for use. Such a practice would explain why other skulls less finely worked have been found; these had simply not been as highly finished as the Mitchell-Hedges skull.

Furthermore, cutting off an enemy's head and exhibiting the skull was a common practice among many primitive tribes as a way of showing power. Crystal devices could have been used as a means of combining psychotronic effects with prevailing religious practice and beliefs. The fact that this eventually yielded a psychotronic amplifier of great power in the hands of a skilled priest would have led to the zealous guarding of the knowledge and the device from all but a very few of the elite.

METAL BENDING

The next remarkable sequence of photos from a Super 8 movie film taken by James Bolen, editor and publisher *of Psychic* (now *New Realities)* magazine, shows Israeli Uri Geller breaking a dinner fork in two through mind over matter. The fork, which Bolen personally verified as being intact before the demonstration, gradually becomes pliable at its midsection as Geller rolls his thumb and index finger over it. The fork finally breaks apart, the prong part clinging slightly to the handle just before it drops away, suggesting that the stainless steel momentarily became plasticlike.

Here the kindling is taking place in the nuclei of the metal atoms and also along the lines of field force in the bonding lattice. The protons in the nuclei may become quarklike due to partial extinguishing of the pions which create their electrical charges. The softening of the electrical field directly softens the ability to hold electrons and rearranges electron orbits. In addition, kindling is occurring in the orbital electrons, partially extinguishing their charge also. The overall effect is for the metal to become plasticlike as lattice bonds are severely weakened. For a metal break due to these effects, the metal in and near the fracture should show the results of severe electromagnetic fields at the localized level, e.g., as if subjected to intense heat from an internal laser action. This has indeed been found to be the case in other experiments, notably by Byrd and Franklin.

THOUGHT PHOTOGRAPHY: STELLA LANSING

Stella V. Lansing is a remarkable person who has captured a large number of authentic thought photographs on film, and in whose presence others often get thought photographs when they operate their own cameras. For several years her work has been investigated by the psychiatrist and noted researcher, Dr. Berthold Schwarz, who has published numerous papers in scientific journals on his studies of Mrs. Lansing. The late J. Dunninger also observed Mrs. Lansing's work and concluded that it was genuine, and that no magician could accomplish by sleight of hand or other trickery the remarkable results she obtained.

In Stella Lansing's photographs all the evidences and signatures of tulpoidal or thought energy kindling into the first biofield, electromagnetic energy (light), are seen (see Part Two). Typical, metallic-looking, clamshell, UFO-like images are often obtained, most often with several objects arranged in a clocklike circle symbolically: the unconscious may well be aware that the time channel is the paranormal channel, and symbolically express this in a clockwork pattern suggestive of time.



Photo 7. Metal bending.



Late evening clockwork pattern of "clamshell-like objects" obtained when photographing a church steeple.



First daytime clockwork pattern, Route 47, Amherst, Mass., September 1972.

Photo 8. Clockwork patterns.

Just as Geller and Kulagina have been noted to transfer psychokinetic ability to other talented persons who were in their presence for a period of time, Mrs. Lansing's clockwork patterns and psychokinetic abilities appear to have stimulated another person's abilities in similar fashion. Paul Koslouski is a researcher who worked with Mrs. Lansing for a short time, and in his own thought photographs the clockwork pattern so characteristic of Mrs. Lansing's pioneering efforts dutifully appeared.

Mrs. Lansing is a brave and gracious lady, and her significant work with thought photographs is important to the understanding and advancement of parapsychological science.

THE DISPLACEMENT EFFECT

The next picture was taken about 1938 in Chicago with a camera on a tripod and a timed release. It was taken by Paul Trovillo, who is the gentleman sitting on the bench with somewhat of a problem of transparency and partial disappearance.



Photo 9. Displacement effect.

The light is by an overhead arc light, which is rich in ultraviolet (one of the magic window frequency bands in the hyperchanncl crosswalk between orthogonal worlds). Pan film was used in the camera, and the picture is of Paul and FerneTrovillo. Note the bushes through Paul's left shoulder and through the slats of the bench at approximately Paul's waist. Also note that the background is in excellent focus.

1. Robert Pavlita, Czechoslovakian engineer, and his daughter.



2. Device becomes a psychoenergetic "magnet" when charged by the human being—and will pick up materials, including nonmagnetic objects.

Photo 10. Pavlita's psychotronic generators.



3. A generator that can precipitate solutes from solution. The jar to the left contains a dense solution; when the generator was placed over identical solution in the jar to the right, the precipitate shown in the jar resulted.

Occasionally the kindling of bioenergy (which is greatly eased in ultraviolet light) leads to eddies of hyperchannel connections between separated portions of the ordinary frame. The normal three-dimensional frame is constructed action quantum by action quantum, and each quantum is fissioned and fused individually to give individual increments or jumps of time and length. Appreciable kindling intermixed in the frame construction can provide other geometrical paths for light, so that the light rays during one or more segments of their straight-line path arc actually flipped into and back out of hyperspace. In cases such as this, one can often see right through a physical object, or even inside it (see Part Two).

I have worked with a psychic group in the American Association of Meta-Science, and have seen one experiment where similar effects were obtained, with the camera on a tripod, in a picture taken by my wife.

Excellent pictures of the Loch Ness monster were recently taken by Doc Shiels. These pictures have been subjected to computer analysis by Ground Saucer Watch (GSW) - and GSW was alarmed at the discovery that the monster in the portrait exhibited transparency. Indeed, for a materialization less than complete, which the monster must be if it is to keep disappearing, one would expect or even demand such transparency, even though a large body of water is a good collector for kindling of bioenergy and tulpoidal forms (UFO's are also notoriously connected with rivers, lakes, and the ocean).

Note also that the Dennis Billings UFO picture demonstrates the same sort of partial transparency. There is a readily understood physics that applies to these effects, but the effects are not contained in the present monocular interpretation of physics and reality.

PAVLITA'S PSYCHOTRONIC GENERATORS

In Czechoslovakia an engineer named Robert Pavlita has been building and demonstrating psychotronic generators for about thirty years. These are devices of various shapes and sizes and composed of materials such as steel, iron, brass, and copper, and they often contain mysterious symmetries of pattern, holes, and shape. The devices for the most part charge up with thought energy when subjected to human contact or eye contact, and then perform various functions such as precipitating a solution, turning, picking up or magnetizing nonmagnetic materials, and killing insects. The devices thus accomplish orthorotation and kindling of thought energy. Pavlita has admitted that his devices could be scaled up to serve as weapons — unfortunately, every tool can be used for either good or evil. He has demonstrated a great many times the killing of insects by pointing a charged rod at them. He also admitted that in an accident his daughter became semiparalyzed and her life was in grave danger, requiring him to work feverishly without stopping for about two days to build a second device to reverse the effects of the first. Pavlita has also demonstrated that his psychotronic devices can either stimulate or retard plant growth, depending on which polarity the plant is exposed to.

The loose information net of which I am a part has recently learned that Pavlita is now in charge of a secret project that has succeeded in building two weapons, one of about two hundred miles range and the other of unlimited range. No further details on the weapons are available.

Pavlita is a pioneering genius, and it is to be hoped that he will eventually release the secret of his psychotronic devices to the world for use in the healing arts and other beneficial sciences. Bioenergy/hyperenergy is real, and Pavlita has scored a major breakthrough in building simple devices to harness it.

CELL-LIKE INVISIBLE TULPOIDAL FORMS

Trevor James Constable has succeeded in evoking and capturing many of these forms on film. The first photo was taken by Constable on 25 August, 1957 in the Mojave Desert, and shows an amoebalike or cell-like bioplasmic form containing shapes that resemble nucleoli, vacuoles, and other cellular structures. The invisible object was at first directly overhead, but moved to positions that enabled inclusion of local terrain in the pictures.

In material presented in Part Two of this book, I show that all that a physical form or physical body is is a total tulpoid, *i.e.*, a form that can be shown to exist in each and every mind. All that a living biosystem is is a one-to-one coherence established between such a total tulpoid (physical form) and a monocular tulpoidal universe (mind world or hyperframe). Furthermore, all possibilities exist concretely in the various hyperworlds. Thus Constable's plasma creatures do indeed exist concretely—but in invisible, orthorotated hyperworlds (mind worlds). The revolutionary discovery by Constable has been a direct, straightforward way to evoke and photograph such bioplasmic tulpoidal forms. His experimental work is of absolutely fundamental importance, and I would not hesitate to compare its ramifications to those of the Michelson-Morley experiments.



Photo 12. Form for potential materialization.



Photo 11. Cell-like invisible tuipoidai forms.

These experiments are also directly related to the work of Miller and Fox, who have shown that, when the probable atmospheric conditions *of* the earth of millions of years ago are exposed to electrical discharges and ultraviolet radiations, amino acids are formed; and then these proteinoids will form microspheres having cellular characteristics, even the ability to grow and reproduce. Every possible life form is already present in virtual state reality, and under proper selective conditions can be kindled into the first bioframe (electromagnetic field) and photographed, or even into the zeroth bioframe (full materialization).

In the UFO photographed in strong potential condition for materialization by Trevor James Constable, note the form of a disc on edge, only a portion of its form being tangible even to infrared. Note also the whitish lobe of the tulpoidal force field extending earthward from the discoidal region. Highspeed infrared film was used, no filter, shot just before sunrise near Giant Rock, California. Constable's pioneering work is remarkable laboratory evidence for orthorotation and materialization of tulpoidal energy forms.

UFO'S

The following pages show some of the most extraordinary UFO sightings and other paranormal phenomena of recent years. Photograph 13 shows a noiseless UFO seen by a university student near Las Cruces, New Mexico, in 1967. (The student reported that, as he changed plates in his camera, the object disappeared. He had been taking photos of rock formations for a class in geology.) In the Spring of 1950, two photographs of a highly materialized UFO were taken by Paul Trent on his farm outside McMinnville, Oregon. The first photo (photo 14) showed the UFO at an angle, while the second (not shown) caught the U FO in direct profile.

1. Black Ring UFO

From Project Bluebook, here is an example of a tulpoidal UFO moving along through the sky and exhibiting the "black ring" effect. In this case only the edge frame is visible, and that edge is generating the black ring or "light quenching" effect. Note that the inside portion of the tulpoid is quite transparent, for one can see the clouds behind it clearly.

2. Anchor Patterns

One of the interesting aspects of combined orthorotation into our normal three-dimensional space and out of it from hyperspace is an anchorlike pattern, shown in the next four pictures. Photo 1 was taken by Ira Maxey, and it shows several tulpoidal forms, which are intersecting our frame in a white or photon-emitting anchorlike pattern. The curved part of the anchor pattern is due to the spinning or orthogonal rotation, and the shaft portion intersects it at right angles. Note also the clouds, whose water content is highly conducive to kindling of the tulpoid — into the first bioframe, in this case.

The second photo from Project Bluebook shows another anchorlike tulpoid — this time the orthorotation is reversed, giving photon absorption — moving through the sky over a dock area by the water.



Photo 13. New Mexico UFO.

The third photo, taken in Wales, is one of several which clearly captured another anchorlike tulpoid in a photo-emitting mode.

The fourth photo, taken by Fay Clark in a darkened room, shows very similar photonic patterns being emitted by Ingo Swann's hands after Swann was asked to try to produce energy to be photographed. In the rightmost arc the shaftlike perpendicular bisector can be seen, associated with Ingo's arm. Bioenergy and mind-energy are the same, whether being emitted from a single human system/mind or from a collective system/mind.

3. Bifringement

Another common effect demonstrated by UFO's is bifringement, clearly shown in this photo from Project Bluebook. Here a UFO in highly materialized form is shown just beginning to turn back into hyperdimensional space. Interestingly enough, in hyperspace a tulpoidal form can turn in two or more directions at once, and this one appears to be doing so. A photon-absorbing turn is indicated by the outer bifringement ring, which is white. These can also be compared to photon interference patterns commonly demonstrated by light waves from two or more sources. Just as there are interference patterns in our three-dimensional space, there are interference patterns in higher dimensional spaces. The three-dimensional intersection in our frame of one of these higher dimensional interference patterns may be black, white, or consist of both black and white components.

4. UFO's in Water

Water is a substance that changes its state and form in a fantastic complex and is therefore one of the very best collectors for bioenergy or tulpoidal energy. That is, in fact, why water is so universally associated with living biosystems, for biosystems need a good collective medium in which to establish coherent tuning. So it is not accidental that water is necessary to life as we know it, or that our bodies are largely made up of water. For the same reason (ease of kindling), UFO's and many other tulpoidal forms have a high degree of association with water. Nessie and other water monsters tune in from time to time in large bodies of water such as lakes, rivers, and oceans.

This photo from Project Bluebook shows a UFO tulpoid in the first bioframe (photonic) moving along in the water.

5. UFO's in Clouds

Again from Project Bluebook here is a picture of a UFO tulpoid kindling in water, this time in the moisture in clouds. Clouds are also usually electrically charged, which enhances the tuning effect, particularly when the clouds are darkening and so are highly charged and also densely loaded with moisture. The darker clouds shield out more of the visible light, reducing the hyperchannel (time) squelching effect of visible light.

6. UFO Seen by the Author

The next UFO is one of several seen by me, and it provided a very curious, anomalous phenomenon in my memory. Furthermore, this UFO was sighted by hundreds of persons over a four-state area, so there is no question that something was there in the upper atmosphere.



Photo 14. Oregon photos.



Photo 16. Anchor patterns.



Photo 15. Black ring UFO.



Photo 17. Bifringement.



Photo 18. UFO In **water.**

The sighting occurred in June 1950. At the time I was home with my father in Woodville, Mississippi for the summer vacation from college. All my family were in the timber business — pulpwood and logs — and I was working for the summer with them.

It was a beautiful, warm, clear summer day with almost no clouds at all. Coming out of the woods on a pulpwood truck with the last load of the day (about 4:30 or 5:30 PM), the truck was slowly making its way across a large open field to the county road. Suddenly a light was seen in the extreme upper atmosphere, glowing with a fierce white radiance, very similar to the light emitted by a magnesium flare or by burning magnesium. Some object was apparently entering the atmosphere from outside it, but the velocity of reentry was far slower than reentry vehicles that would be fired many years later on U.S. and Soviet rockets. As the fiercely glowing light smoothly descended, a change occurred. At that point gray smoke also appeared in the white smoky trail being left by the object, and the trail became turbulent from that point on. Then an orange color appeared at the front of the descending, tumbling object, in the light being emitted. The smoke trail from this orange glowing color was darker gray. The object tumbled slowly downward, burning fiercely, until utterly consumed, still at an extremely high altitude (I would estimate still above 100,000 feet). In the sky the smoke trail that had been left persisted for a while, until it was gradually dispersed by high atmosphere winds. In the picture a great deal of dispersion has already occurred.

So far as is known to me, and I have had considerable missile experience, neither the U.S. nor the Soviets were firing any sort of vehicle in 1950 that could account for the phenomenon. Furthermore, even if we postulate a reentry vehicle from a large rocket, its velocity was far below normal reentry velocity, and this cannot be accounted for. The object also could not have been a meteor because its velocity was far too low.

For the doubter let it be pointed out that even if a high drag, low ballistic coefficient reentry vehicle comes into the earth's atmosphere on a downwards plunge and rapidly slows down, its initial velocity is quite high, and its rapid slowdown is quite apparent. This phenomenon did not exhibit such a characteristic.

7. The 1966 Dennis Billings UFO Sighting

At about 7:00 P.M. on the night of September 23, 1966, Dennis Billings and his wife and daughter sighted a UFO at close range. The close UFO was one of a total of four sighted by the family in about one hour. The sighting occurred in Decatur, Alabama. The UFO phenomena occurred after anomalous physical effects were noted. From the alley by his back yard Dennis, who had taken out the garbage, began to hear sounds from inside a neighboring house at some distance as if he were physically inside the room in which the sounds were occurring. These sounds consisted of conversation and dish-rattling in the kitchen where two women were apparently cleaning up the table after the evening meal and washing dishes in the sink. Then the sounds changed to those from another room where children apparently were playing games. Peculiarly, the sounds seemed to originate from wherever Dennis focused his attention, such as the garbage can, the house, etc.

Shortly afterward his daughter followed him into the yard as he left the house to go to a football game, carrying his binoculars. She spotted a cluster of lights moving along slowly in the sky above the treeline, and called his attention to them.



Photo 19. **UFO** in clouds.



Photo 20. UFO seen by the author.

Through binoculars the cluster of brightly colored, flashing lights could be seen to be one object about two blocks from Dennis's house, moving very slowly and making no sound, about fifty feet above the trees.

Just then Dennis's wife turned on the exterior house lights which illuminated the entire back yard. As she came out into the yard, an object, a fiery red, glowing, round ball of light about twenty-five feet in diameter, appeared just above the neighboring house in back, the same house from which the anomalous sounds had been heard a few minutes previously. Strangely, the glow of the object did not appear to illuminate the rooftop of the dwelling above which it hovered.

The glowing light seemed to be composed of a tremendous amount of energy, and there was violent fluctuation, turbulence, and movement of the light energy within the sphere. Another way to describe its dynamic characteristics is to visualize it as being composed of individual particles of light or incandescent particles of highly charged matter moving rapidly in a circular plasma. The light itself appeared to be comprised of hundreds or even thousands of individual light sources confined to the circular shape.

Within a few seconds the individual lights began to coalesce and form into a solid light with no agitation, dimming in incandescent intensity and changing from red to orange to yellow. As the circular shape of light grew dimmer, a rocket-shaped object formed in the center. After the light had finished changing to yellow and was much dimmer, the rocket-shaped object began to rise, with particles of light from the sphere clinging to it and falling off toward the ground, where they evaporated and disappeared. The rocket-shaped object had no wings or tail fins, and it picked up speed and sped away, streaming an exhaust tail of light or flame behind it, similar to a welding torch's flame or a flaming sparkler. The object made several spirals as it rose and then headed in a straight line toward the stars. As it rose, it also made a slight arc toward the moon, which was full or nearly full, and passed across its face. As it crossed the face of the moon, its rocket-shaped outline could be clearly seen.

Astonished, Dennis and his wife began discussing what they had seen, still standing in the back yard. At this time the anomalous reception of unusual sounds began again. At first Dennis seemed to hear a train on a distant track although there are no railroad tracks in the vicinity. The sound seemed to come closer until he seemed to hear a train passing by immediately in front of him with its wheels clicking on the joints of the steel rails. Then they heard other sounds similar to automobiles and trucks on a freeway, again very close, although there is no freeway in the vicinity either. The whining motors and honking horns of these unseen vehicles could also be heard. Turning first in one direction and then in another, Dennis could hear the anomalous sounds seemingly originating from wherever his attention was directed. Other sounds such as airplanes flying in the sky also came in. Then he heard another sound like a high-pitched tuning fork, and it began to increase in frequency until Dennis's eardrums were hurting.

With this high-pitched frequency sounding and his ears smarting, Dennis looked up and saw a bright object positioned in the sky, larger than a star, and approaching him and his wife. As it approached on a straight line toward their back yard, it got bigger and brighter, until it stopped directly overhead, hovering 100—150 feet directly above the yard. The object appeared to be circular or oval in shape, and it descended with the flat side down. On its rear end the object was



Photo 21. Second Billings UFO.

rimmed like a horseshoe with twelve washtub-sized blinking lights, each of a different color. These lights appeared to be controlled so that as one light blinked on, the other lights went off. In this way one light at a time blinked on and off in successive positions, so that a single light seemed to rotate around a complete half circle and cross at the open end, changing color as it progressed. On one side of the horseshoe the light positions were bright red, on the next yellow, on the next pale green, on the next a darker blue-green, and the final light on the opposite side of the horseshoe pattern was a very bright blue. Underneath the center of the object was what appeared to be a hemispherically-shaped plastic capsule or shield. This capsule was completely blacked out; yet through what appeared to be smoked glass, movements or shadowy activity could be seen. Dennis assumed that this was the exhaust section of the craft and that what he was seeing was probably smoke coming out of a black hole in the craft.

Around the outer perimeter of the craft, and about two feet out from it, was an illuminating light which circled the object like a halo or corona. Dennis had the eerie sensation that the object was intelligently controlled and that he himself was under close observation.

At this time Mrs. Billings became extremely frightened, ran into the house and got the baby, and crawled under the bed until the craft had gone.

As she left in fright, the craft lifted up in the sky a little and began to move slowly away, so slowly that Dennis could walk along beneath it as it moved across the back yard and into the front yard. Walking under it and looking straight up at it, he was able to observe closely the blinking lights and their operation. When the craft had been motionless, the lights had blinked on and off slowly, so that they moved in a slow, pulsating motion from position to position around the horseshoe pattern, changing color as they went. As the craft began to move and pick up speed, the lights began to increase in pulsation frequency and thus to appear to move faster around the horseshoe pattern. As the craft moved even faster, the light pulsations became so short and fast that they seemed to be spinning around the horseshoe in one continuous blur of motion.

As the object left Dennis's yard, it moved into the sky and away, but not too far, until it had positioned itself over the airport (Pryor Field) as a large bright object. At this time Pryor Field was serviced by Southern Airlines. As one of the commercial aircraft took off, the UFO followed it back directly over Dennis's house, then left the aircraft and repositioned itself in the sky in its original position over the airport, hovering motionlessly.

After hovering motionlessly for about fifteen minutes, the UFO suddenly shot down in an arc toward the ground, passing below the tree line and out of Dennis's view.

Dennis waited for about ten more minutes, when suddenly the UFO shot back up into the same position in the sky, seeming to follow in reverse the same arc on which it had descended. It remained in this position, hovering in the sky above Pryor Field for another ten to fifteen minutes. Then a similar object approached and joined it, and the two seemed to merge or dock together. They remained motionless for about five minutes more, then moved across the sky, still joined, until they disappeared below the horizon.

According to the newspapers the next day, this object or something similar had been seen all over the eastern half of the U.S., and had been described as "multicolored clouds."

8. The Second Billings UFO Sighting

If Dennis and his wife had experienced only one UFO, the incident would have quietly faded away in the unwritten annals of ufology. However, such was not to be the case.

Dennis vowed to himself that, if such an incident ever occurred again, he would get a photograph of the object. And just before Labor Day in 1970, Dennis got such a chance, and indeed made good his intention.

On that night, with almost totally clear skies and a bright moon, Dennis's wife came rushing into the house in Decatur, Alabama and excitedly reported to Dennis that she had seen another UFO. Rushing into the yard, all Dennis could see were some distant white lights — too far away to say positively they were UFO's. However, recalling the multiple UFO's in the previous incident, Dennis and his wife took up separate watches on each side of the house. Dennis also thought of his Polaroid camera left in his car parked in the driveway, so he went to get it.

Standing between the trees, Dennis looked up into the sky and saw a UFO suddenly triggered into position, as if his thought and intent had pulled a switch and the object had suddenly appeared, positioned perfectly for his observation, pouring light from underneath for a distance of about twenty to thirty yards. This light seemed to emit some immense force and was colored like the fire, whiteness, and glare of a welder's torch. The tail diminished as the craft lowered. Dennis snapped a picture when the craft's tail had shrunk to only four or five feet long. He pulled the tab on the polaroid film and ran into the street under an outdoor light to see if he had recorded a UFO. When he saw he had done so, he then noticed the object had descended and made a left turn, moving eastward down Nelson Street slowly at about five miles per hour. Its porthole lights were still clearly visible and no sound was being made. Dennis hurried after the UFO and caught up with it at the end of the street near a T.V.A. easement, where large electrical power lines were located, running generally north to south. He got slightly ahead of the object as it traveled parallel to the power lines and as the craft passed directly over him. At the very instant he pressed the shutter, all lights in the craft instantly extinguished as if his mind had been read and the photograph deliberately prevented. The now darkened, cold, lifeless-appearing craft moved smoothly away, passing over Mallard Park where a Marine Corps Band was playing. The second photograph showed no lights whatsoever.

One of the local newspapers then printed the story and the picture, and Dennis received a call from one of the national UFO agencies. After giving the agency his photograph, his camera was mysteriously stolen from his automobile, and the agency then claimed to have lost his photograph. However, they underestimated the determination of Dennis Billings.

Dennis simply got on a plane and went to Washington, and proceeded to the office of the head of the UFO agency. The president of the organization had said that he would be out of town for several days and would be unable to see Dennis. Nevertheless, Dennis went to his office, where his secretary repeated that the gentleman was out and would not return for the day. Dennis barged into the office over the protestations of the secretary — including the threat to call the police and have him removed — and proceeded to search for his photograph, eventually finding it in the desk drawer of the president of the organization. He retrieved his photo and returned to his home. Without his personal determination to retrieve his property, the photograph — like so many others over the years — would have been "lost." The immediate question that occurs is: Isn't it curious that one of the major UFO organizations in the U.S. — supposedly devoted to solving the UFO mysteries — exhibited the desire to misappropriate a really good picture of a UFO and see that it disappeared from the scene?

At any rate, Dennis got his photo — and a beautiful photo it was. Furthermore, the incidents experienced by Dennis Billings are classic examples of my theory. Many anomalies in the incidents will not fit orthodox theory or orthodox ideas about reality. The "pieces of light" seem to be almost intelligent. There was a close coincidence of thought/intent/expectation and kindling burst into observable reality, plus a great deal of sky-watching and expectation by Dennis between the first UFO incident and the triggering of the second (i.e., a long kindling time, just as Patterson experienced before he got his excellent movie shot of a sasquatch). And there was close experience of very distant sounds (to be expected in hyperspace, where ordinary distance can be shortened or even eliminated). Furthermore, there were multiple witnesses to the UFO incidents, and Dennis got his photograph. Psychologically, it may even be significant that for several years Dennis vowed to take *a* picture of any other UFO he might later see, and when he got *a* picture, he was prevented from getting another. And on the photograph obtained, one can see that the "craft" form of the tulpoid is only partially materialized, since the stars can be seen right through the vehicle's midsection. This is similar to the strange transparency of the Doc Shiels photograph of Nessie (the Loch Ness monster), which Ground Saucer Watch found when they performed a computer analysis of his photo. (The second Shiels photo showed that the water was being forcibly moved by Nessie, so the tulpoid was at least partially materialized.) Yet such is to be expected if one is dealing with partial materialization of tulpoids.

Finally, the entire area is located in the Tennessee Valley Authority's project. Great electrical transmission lines go through the area, and there are many long lakes and the Tennessee River. So an excellent kindling medium is provided, and many UFO's are seen over the Tennessee Valley.

The Dennis Billings photo remains one of the best UFO photographs ever taken, and coupled with Dennis's astute personal observations, it provides a keystone insight into the actual nature of the UFO phenomena.

9. The 1973 Pascagoula UFO Sighting

In October 1973 one of the greatest UFO flaps of all time occurred in the United States, and created headlines because of the bizarre increase of contactee incidents. One of the most sensational of these was the purported abduction of two men in Pascagoula, Mississippi, who were allegedly taken aboard a saucerlike craft, examined, and released.

Shortly afterwards another incident happened in Pascagoula, which drew little attention. In this case, underwater phenomena were involved, because two U.S. Coast Guard petty officers investigated the object and made physical contact with it. An official Navy investigation was made and a report written. Unusual characteristics, highly suggestive of a device using psychotronic effects, were displayed by the object. I suggest that this device may well have been a Soviet psychotronics device, taking advantage of the UFO flap as a screen to carry out clandestine activities.

In Pascagoula an illuminated underwater object followed the boat of Raymond and Rayme Ryan, who tried to beat it away with an oar. The nine witnesses, including two Coast Guard investigators, described the object as metallic, rod-shaped, two to three feet in length, and four inches in diameter. It was attached to an oval-shaped beam ahead for four to six feet. It looked like a mini-submarine and moved at four to six knots in four to six feet of water. Although it sounded like metal when struck, it could not be struck consistently, and its light, when illuminated by a flashlight, turned off immediately and then on again after about one minute. The portion of the Ryans' oar that was under water could not be seen from the surface when the object's light beam fell on it.

At this point I would like to make some general remarks about the nature of UFO's. (1) The UFO-generating mechanism and the psychotronic mechanism are the same. (2) The Soviets may even be able to psychotronically evoke particular types of UFO phenomena at will. (3) A small number of UFO phenomena could even be generated by the Soviet Union as part of its psychotronics deception plan. However, most UFO phenomena are definitely not of Soviet initiation, (4) An explanation of the UFO phenomena is briefly sketched out in my section on psychotronics. (5) Some of the NASA photos taken of moving lights in orbit around the earth may have been of Soviet-initiated effects. Like the radiation of U.S. personnel in the U.S. Embassy in Moscow, this effect could have been intended to evoke U.S. high level reaction, to positively assess whether the U.S. had any knowledge of psychotronics, and if so, what that level might be.

10. Other UFO's

A brilliant, "crystalline-like" UFO was seen over Madrid, Spain in 1968 and was chased by Spanish Air Force planes. Whenever people are significantly structured in their thinking, symbolically "sharp" and "crystalline" tulpoids often are seen, representing their ideas. Many such UFO tulpoids are seen over Iron Curtain countries, and over countries such as Spain that have one dominant religion and culture.

In October 1973 the governor of Ohio, John Gilligan, saw this UFO phenomenon along with over 100 other people. The police were notified by the governor, and this photo was taken by the *Columbus Evening Dispatch.* Note that the tulpoids remain in the first bioframe (see Part Two), and even though their intersections change shape, the second one remains in a "burst mode."

In 1965 Rex Heflin took four pictures of a highly materialized UFO near Santa Ana, California. In the fourth photo the dematerialization "photon absorption" effect is shown: if orthorotation into higher dimensional space is made in one direction, photon (light) is emitted. If the orthorotation is made in the opposite direction, photons are absorbed. In one case "glowing light(s)" are associated with the UFO's hyperdimensionality, while in the other case "black rings" or "smoke" are associated.

FALKVILLE SPACEMAN

These two pictures are black-and-white versions of two of the photos taken by **Falkville, Alabama Police Chief, Jeff Greenhaw, in an encounter during October**

1973. Greenhaw had received a call from one of his constituents to say that a UFO had landed in her pasture, and he was proceeding to investigate the incident. In his police cruiser he carried a polaroid camera which he used in his police work.

Driving down a narrow gravel road, Jeff noticed a metallic-clad, suited figure walking down the road toward him, and he stopped his car to get out and have a look. For some strange reason his instinct was not to pull his pistol on the creature, and instead he started taking pictures as the creature/tulpoid walked toward him. The creature was holding something exposed in one of his hands, as can be seen in one of the photographs. As the tulpoid approached with no apparent intention to stop, Jeff then switched on the blue light above his cruiser, and the rotating, flashing light caused the creature to turn about and run away down the road. Jeff jumped into his cruiser and gave chase, eventually reaching about forty-five miles per hour without catching the tulpoid. His car spun off a curve and Jeff still had the photos — polaroids that he developed.

Bizarre things then happened to Jeff Greenhaw. His wife left him and divorced him (I suspect this had nothing at all to do with the UFO incident), he was fired from his job as police chief, vicious rumors were circulated that it all had been a hoax, and that a person had been dressed in an aluminum suit and photographed to give the appearance of a spaceman. Various fire suits were positively identified as having been the suit used. Jeff was discredited. Finally his trailer was burned down.

Before the trailer was burned, a friend of mine here in Huntsville, Warren York, visited Jeff and made photographic slides from the original polaroids with Jeffs permission. Shortly after that I had a chance to study these first generation slides for several hours, and some interesting things turned up.

The tulpoid's left hand is positively reversed in a mirror image fashion; it opens outward instead of inward as does a normal hand. (This cannot be seen on the photos shown here, but on the first generation slides it is readily seen.) Being an aikidoist, I am totally familiar with the degree of bending and flexing of most human joints, particularly the arms, wrists, and hands. And the mirror imaging of the left hand of the tulpoid is beyond question.

Furthermore, one can establish a clear shoulder line in some of the other photos, and a line just under the hat or "nazi-helmet" portion of the figure. From the other photos a remarkable thing emerges: there are only two places between the edge of the helmet and the chest that are sufficiently wide and sufficiently thick to contain a human head. The person would either have to have a neck about twelve inches long, or he would have to have a neck shorter than a Neanderthal's, with the head lolling down completely on the chest. Again, this can be clearly established in the original first-generation slides.

Finally, I have a letter in my files that establishes as a falsehood one of the rumors about Jeff. One person had admitted dressing in the suit and faking the incident, when in fact what actually happened was that Jeff went to his house immediately after the incident to ask this person to accompany him back to the area and search for the spaceman. When confronted in late 1977 by his family and friends, this person broke down and confessed that he had lied about the incident.

Finally, some other investigators dressed a person in an aluminum foil suit and photographed him, and there is no resemblance to the tulpoid photo. And Warren York investigated all the firesuits supposedly used in the hoax, including new suits used by the various fire departments and also by NASA at Redstone Arsenal. None of them resembled the tulpoid photo.



Photo 22. Spanish UFO.



Photo 23. Ohio UFO.



Photo 1



Photo 2.

Photo 24. Heflln UFO.



Photo 3



Photo 4 (enlarged)

Several photo experts have concluded that the photos are false, and several have concluded that they are not. A computer analysis concluded that they were false. However, what exactly could a computer show that would differentiate between a normal physical object and a well-materialized tulpoid?

In my opinion the incident was a fake *if and only if* three things can be established; (1) an individual exists with a horribly deformed left hand that is mirror-image backwards and opens outside away from the body; (2) the same individual either has no neck at all or else has a neck almost a foot long; and (3) the same individual can run forty-five miles per hour, faster than any other human in the world. Such an individual — if he existed — would be readily identified, and there would be no difficulty in ascertaining that he was the one involved.

There are other things about the case that I am not at liberty to divulge at this time out of respect for Jeff Greenhaw's confidence and privacy. But even so, the incident has a very high probability of being tulpoidal, and Jeff Greenhaw stands fully exonerated, in my opinion.

MEN-IN-BLACK

The kindling of virtual state tulpoidal forms into the zeroth bioframe of a physical reality (materialization) can result in the materialization of living, breathing, functioning forms. There is essentially no limit on the format that may be obtained. Sasquatch, Nessie, fairies, demons, angels, mothmen, skunkmen, yeti, kangaroos, etc. are just a small sampling — as indeed are UFOnauts such as little green men, space-suited astronauts, androids, robots, etc. These (usually) fleeting phenomena are physically real when in the materialized state (zeroth bioframe); unfortunately the tuning which is accomplishing the collection and kindling is usually unstable, and the stability to maintain the materialization lasts only a short time.

One of the consistent phenomena experienced by many UFO investigators is that of men-in-black. Typically, oriental-featured men in dark suits appear and demand the investigator's material, instructing him to cease his efforts. Usually they have almond-shaped eyes that never blink, and speak telepathically without moving their lips. Variations, of course, occur.

Here is an incident that happened to a friend of mine in the city where I live (Huntsville, Alabama). At the time my friend was an ardent UFO investigator and even wore a radiotelephone so that he could be contacted quickly at any hour to go and investigate UFO incidents in the field. He is the friend who investigated the Jeff Greenhaw case and took slides of the original Greenhaw photos before Greenhaw's trailer was burned.

A friend of his, a girl with psychic abilities, was approached one evening in her apartment by two medium-sized, almond-eyed men of oriental cast, in typically dark suits. These tulpoidal gentlemen's eyes never blinked and they spoke to the girl telepathically without moving their lips. They handed her an envelope containing two ancient coins and instructed her to give the coins to my friend, and inform him that he must keep them on his person at all times. After other messages that completely frightened the girl, the two tulpoids left, never to be seen again.

In tears from fright, the girl contacted my friend and between fearful sobs urged him to take the envelope and get it away from her, as she never wanted to see it again or the two men who had brought it.

My friend picked up the envelope and later examined the two coins. I also personally examined them: to anyone who is sensitive, the coins radiated an invisible unpleasant tulpoidal energy.

The investigator then photographed the coins, and daringly placed one on a string around his neck against my own advice to seal them up against light. He promptly broke out in a rash from head to foot and was shortly forced to remove the coin and seal it away. Interestingly, photos of the coins seemed to have about half the effect of the actual coins.

For a period of two years I kept my copies of the photos sealed against light and stored in a file cabinet. To my surprise, several times when I went to retrieve the photos, they would alternately be there and not there. I simply state what occurred, without any change or justification. Eventually, however, their effect seemed to decay, and at that time there was no longer any problem in recovering them from the filing cabinet.

The men-in-black syndrome is based on our own unconscious tuning; since each of us has some unpleasantness in the unconscious, sometimes the tuned-in men-in-black can be very nasty indeed.

I am personally aware of several good researchers into the paranormal who have been forced to retire from the field to save their own lives and the lives of their families. As late as April 1978 a very good friend of mine has been forced to do just that because of overwhelming danger to his family from materialized tulpoidal phenomena.

In my own case I have found it expedient to work closely with a group of psychic friends in the American Association of Meta-Science. This group is capable of clairvoyantly peering into the unconscious to ascertain the most unpleasant blockages present, and forming energized thought forms to go in and cleanse the unconscious of most of the unpleasantness. In this way the unconscious can be kept relatively free of unpleasant tuning that might otherwise tune in something like the men-in-black. My own life and experience has not been free of tulpoidal tuning; however, it has been free (at least so far!) of tuning in anything really unpleasant, or nasty, or threatening to my family.

But I continue to be very grateful to my psychic companions for their understanding and assistance, and I continue to avail myself prudently of their services when needed.

SASQUATCH

In many regions of the earth there exist legends of giant, apelike creatures of various sizes, hues, and dispositions. In the high Himalayas this takes the form of the yeti, a humanoid creature sometimes seen in the snows of high and remote fastnesses. Expeditions have in fact uncovered and photographed the yeti's tracks, and sightings by reliable observers have been made. Several parties have also reported hearing the yeti's strange vocal sounds.

In the remote Siberian wastes the Soviets have also reported such a manlike humanoid creature, even purporting to have captured one a century or so ago.

In the U.S. the tulpoidal form similar to this has been the sasquatch of the Pacific Northwest, known since Indian times, and observed hundreds of times by a variety of persons over the years. Nevertheless, in spite of intensive searches Bigfoot continues to elude all pursuers while continuing to be sighted and leave footprints.





Photo 25. Falkville spaceman.

But Bigfoot cannot be caught by packs of hounds. (This has repeatedly been tried. His lair is never uncovered, nor can he be tracked to it. He has never been found dead of old age or injury. The bones of sasquatch have never been uncovered in caves or elsewhere.)

Furthermore, not just one type of footprint or one type of creature is seen; instead, a variety of shapes/sizes/types of creatures appear. This is one particular clue to the fact that we are not dealing with a species of shy and elusive wildman, but instead with a tulpoid.

Sasquatch cannot normally be found — as indeed Nessie and the yeti cannot — because shortly after each appearance he is no longer present in this bioframe.

However, as interest in sasquatch/Bigfoot grows and the effort to discover or uncover him intensifies, the kindling of the tulpoidal form intensifies. Today bigfoot-type creatures of all varieties and hues are being seen throughout the U.S., from Maine to Florida, from Alabama and Tennessee to Oregon, Washington, and California. With this intensity of kindling, it is getting easier to evoke a bigfoot-type tulpoid, and as it continues, sasquatch is probably going to be tuned in and stabilized. If so, the past itself will just be changed, and we will be able to dig up ancient bones of sasquatch, and find his lairs, and track him down with dogs and capture him. In that case, sasquatch will become a respectable animal and will stabilize in our reality. Tulpoidal activity from the collective human unconscious can be stabilized and the entire past, present, and future changed by the awesome 4×10^9 dimensional psychokinetic mastery of spacetime exerted by the species unconscious.

We also should not be at all surprised if the same thing happens to the placid Loch Ness monster. There is probably going to be a family of pleisosaurs living in the Loch eventually (and in many other bodies of water across the globe) — and spacetime will be changed (past, present, and future) in our zeroth bioframe to accomodate this small shift in the collective human unconscious. In reference to changing the past, it is interesting to note that Wheeler has recently demonstrated that, in the two-slit experiment (which contains the basis of quantum mechanics), it can be decided *after the fact* whether or not a photon has interacted with two slits or with one. Thus in at least one sense the past can be changed!

After several years' intensive search for and pursuit of the elusive Bigfoot in the Pacific Northwest, Roger Patterson finally obtained a short movie strip of a very large, seven-foot tall female with pendulous breasts and crested head, walking through a forest clearing with giant strides. This is perhaps the best frame from that movie strip. Sasquatch tulpoids have been known since ancient time by the Indians who lived in the area. It would be interesting to see what results could be obtained in materializing or partially materializing the Bigfoot tulpoid with a Reichian cloudbuster.

Bigfoot-like creatures are materializations from the collective human unconscious shaped and formed by the layers (race, culture, nation, territory, state, region, family, etc.) between the collective unconscious and the individual unconscious minds of the observers. The exact format depends on all the higher level "kneading" of the "dough" that is being forced out into materialization.

In the Pacific Northwest the Indian knew of the sasquatch long before the coming of the white man; in that region, a great deal of tuning has been accomplished, and the sasquatch is a rather well-tuned animal form, having well-



Photo 26. An ancient coin handed to a psychic friend of a UFO investigator by tulpoidai men-in-black.

defined footprints as shown in Photograph 28. In the East, the yeti has also been tuned for centuries, and a cast made from his footprint is quite well formed — though also quite different from that of a typical Pacific Northwest sasquatch. In New Jersey, on the other hand, for the last two or three years there have been a large number of Bigfoot sightings, but here there has not been the same degree of tuning for several centuries, and consequently the footprints look rather messy, like blobs left by the creature before it vanished back into dematerialization. Finally, in one case a person well-known to me stumbled into dematerialization phenomena of a very strong nature. One of the incidents involved the materialization of a really gigantic "superfoot" creature, which walked around all over the base of a mountain, leaving giant footprints two feet or so long. Though monstrous in size, superfoot is really ill-tuned and thus ill-defined, with footprints that are decidedly blobby in form.

UFO's OVER THE SOVIET UNION

In 1961 locomotive engineers on a freight train from Moscow to Golytsino, when about forty kilometers from Moscow, sighted a disc-shaped object topped by a cupola approaching the train. The object slowed to pace the train and escort it for about one kilometer. Suddenly the locomotive engines went dead, and could be restarted only after the mysterious object disappeared.

On December 29, 1967 an Iliouchine 14 aircraft enroute from Zaporoje to Volgograd sighted an approaching UFO. As the UFO neared the aircraft, suddenly the aircraft's engines stopped in midair and the plane began slipping sideways toward the earth, carrying its panic-stricken crew to certain destruction. When the crippled aircraft was about 700 meters from the ground, the UFO abruptly disappeared. At the same instant the aircraft engines sputtered and roared to life again. The pilot righted the aircraft as lift returned, narrowly averting a crash.

On September 24, 1962 first one oval object then several others escorted a TU-104 airliner enroute from Vorkouta to Omsk and maneuvered around it with astonishing speed and agility. The eerie aerial escort continued for most of the flight, and the objects were extensively observed by both the passengers and the crew. The objects positively could not have been other planes, balloons, satellites, celestial objects, or other known natural phenomena.

In Latvia in 1965, R. Vitolniek, a well known astronomer, together with several scientific colleagues, sighted a triangular-shaped formation of four spherical objects, one at each of the points of the triangle and one a little larger in the middle of the triangle. Two of the scientists, Ian Mederis and Robert Vitolniek, made immediate calculations and insured that the objects were not satellites or normal orbital objects. The objects steadily shrank in size, leading Vitolniek and his colleagues *to* conclude that the objects were traveling away from the earth into outer space.

At least two Soviet astronauts, Colonel Bykovsky and V. Terechkova, have observed UFO sightings and reported them to the Soviet authorities. Many other UFO sightings have occurred in the Soviet Union and the Iron Curtain countries; **these** are just a sampling.

In fact, on several occasions Soviet defense forces have been committed into massive action against UFO's.

In 1959 numerous UFO's flew over Soviet rocket launchers at Sverdlovsk. In addition to being visually observed by a large number of personnel, they were detected and tracked on Soviet radars. Soviet military units were ordered into action immediately. Interceptors and antiaircraft artillery batteries went into action and the air defense missile units opened fire. In spite of the fierce engagement of the elusive UFO's, none were hit or damaged and no results were obtained by the Soviet combat forces. Men, machines, guns, rockets, missiles and radars could not cope with the UFO's. The impact in the Soviet military of several such military actions must have been enormous.

In fact, such incidents as this probably were responsible for the establishment of an extremely high level and highly classified Soviet investigation of UFO phenomena. Given the decision to launch such an investigation — and it would be inevitable for the Soviets to take such a step when their air space was under open invasion by possibly hostile forces — the Soviets would have assembled a formidable scientific team to tackle the problem. Furthermore, given the highly classified military reports of such encounters, reports of UFO incidents at other Soviet installations and by other Soviet military personnel, and the steady occurrence of the normal range of UFO sightings and incidents over cities and villages, the Soviet system would have tolerated no scientific nonsense in opposition to the mission to discover the nature of the phenomena. In other words, the Soviet team from the beginning would have concentrated on finding the explanation and nature of the phenomena, not on whether or not such phenomena were real or were occurring.

In my opinion, a connection between UFO's and paranormal phenomena — and the new psychoenergetics which also was formulated by 1959-60 — was realized about 1960. The high classification of the Soviet psychoenergetics program then led directly to an official Soviet policy to debunk UFO's and paranormal phenomena if the work of any outside research group became too serious. Some Soviet scientists who had no connection with the weapons programs were allowed to work a little on paranormal phenomena and on UFO's. This was simply to provide a deception plan for Western scientists; in their contacts with their Soviet scientific colleagues, these Western scientists would see only a rather puzzling collection of simple laboratory experiments on telepathy, ESP, simple psychotronics, psychokinesis, etc. A limited number of Soviet papers dealing with these subjects, but of no particular theoretical content or very exact statement of experimental apparatus and conditions would be permitted in the open journals. However, close scrutiny of such activities would be maintained by the Soviet state, and no real breakthroughs would be permitted to occur or to be transmitted to the West. Ziegel, Dubrov etc. owe the limited work they were permitted to do to this Soviet deception policy.

They also owe the surveillance and harassment they have undergone to the Soviet policy of insuring that they would be permitted to do nothing significant, or to communicate nothing significant to their Western colleagues. Meanwhile, a rigorously controlled and highly classified Soviet psychotronic weapons development program continued apace. And the radiation of the U.S. Embassy (and the U.S. ambassador to the Soviet Union) in Moscow with weak radiofrequency microwaves containing psychotronic modulations began about 1959-60 and con-

m



Photo 27. Sasquatch.



Photo 28. Bigfoot cast.

tinues to the present. As explained elsewhere, this radiation was in fact another very clever Soviet intelligence probe: By observing how the U.S. reacted, they could determine whether the U.S. had any knowledge of psychotronics and thus whether or not the U.S. had developed secret psychotronic weapons and counters of its own.

The Sighting over Petrozavodsk

Even more spectacular phenomena have occurred in Soviet skies and are continuing to occur.

For example, a mysterious phenomenon of great magnitude occurred in the skies over the Soviet city of Petrozavodsk at about 4:00 A.M. on September 20, 1977. Petrozavodsk is in Soviet Karelia about 130 miles from the Soviet-Finnish border.

First, a gigantic mass of light flared up in the skies over the city, glowing brilliantly, and hovered there. Fantastic streamers of light poured from the glowing hemispherical dome of light and radiated down towards the city. Tass, the official Soviet news agency, reported that it looked like nothing so much as a shining "jellyfish sending down a multitude of fine beams." It gave, Tass said, "the impression of a torrential rain of light." Where these fine beams touched windows, many windows were broken or perforated with small holes.

Later the glow died down and the jellyfish became a single giant bright semicircle. It then gradually moved off in the direction of Lake Onega. But all was not yet over. Even after the bright hemisphere had moved away, great gray clouds appeared over the city with a semicircular aperture bright red in the center. These phenomena lasted for ten minutes or longer.

Being over the city and lighting up the sky so fantastically, the phenomena were seen by a large number of Soviet citizens and reported by them to the Soviet authorities. In fact, Tass admitted in its initial release that informative reports from witnesses were still pouring in and being analyzed. This interesting phenomenon is worthy of some remarks by way of explanation.

Not only is pressure from the Soviet threat transmitted through the collective human unconscious (ZARG) to the skies of Europe and North America; in addition, a backpressure is generated, which provides the impetus for initiation of appropriate phenomena over the Soviet Union and the Iron Curtain countries. Psychologically, it may not be accidental at all that the original shape resembled a giant jellyfish; the implication is that the psychotronic sting will also be transmitted to the Soviet Union by backlash whenever the Soviet psychotronic weapons are unleashed on the West. The shapes are also psychologically significant. First the Portuguese man-o-war's stings will be applied (this accounts for the tentacles toward the city); then the all-seeing eye (symbolized by the bright hemisphere) will check the results. And the results will be gloom and despair (gray clouds), surrounding death, blood, and destruction (the red center) left in the aftermath.

Thus in this materialized symbolic dream event of ZARG's, there is a clear warning and an omen to the Soviet Union about the end result that awaits it on its present course to attempt to conquer the world and unleash a great psychotronic barrage in the process.

Since so many Soviet citizens saw and reported this fantastic phenomenon in alarm, the Soviet regime could not ignore it or simply debunk it. The Tass release thus tried the oblique dodge: the phenomenon was still being evaluated, reports were still being received and checked out, and an official of the Petrozavodsk observatory, Yuri Gromov, was quoted as saying the phenomenon was still a mystery but was confirmed by a large number of eyewitnesses. The Pulkovo observatory in Leningrad was quoted by Tass as speculating that the phenomenon was due to a meteor. And of course there one can expect the matter to be left in limbo.

An interesting development related to this UFO sighting occurred in the U.S. The October 3, 1977 issue of *Aviation Week and Space Technology* magazine carried a brief disposal of this phenomenon. The brief insert, Spook Show, referred to a "Soviet press ballyhoo" of the incident and stated that the incident was actually the launching of the Soviet Cosmos 955 classified military satellite from secret launching facilities at Plesetsk. This AWST insert is credited to Washington Staff.

My comment is that the launching of the Cosmos 955 may well have been the initiator of the event — a rocket firing does produce a tremendous ionized trail of burning exhaust gases rising up into and out of the atmosphere, and this is a bioenergy collector par excellence. However, a simple review of the time sequence of the phenomenon, its location, and its shape is sufficient to destroy any notion that one could mistake it for a simple rocket launch. And rocket launches had occurred there many times before, with no such phenomena or mass reportings by the population, and with no such news release by Tass.

FRENCH EXPERIMENTS WITH PSYCHOTRONICS

Aime Limoge in France is building some truly unusual gadgets that are being tested and that work. Limoge travels widely in the Soviet Union, and attempts to duplicate some of the unusual Soviet devices he has been permitted to see. Some of Limoge's devices have a partially psychotronic nature, although none of his reports mention this.

One of his gadgets, a portable and battery-powered electroanesthesia device, was considered for purchase by the U.S. Army.

Another of his gadgets is a magnetic inductor of hypnosis, which has been used in medical treatment by L'Institut de Recherche d'Electro-anesthesie. Limoge is reported to have seen such a device in the Soviet Union, possibly because one part of the Soviet psychotronics deception plan calls for the deliberate release of information of this kind, in a manner to suggest that this is the latest state of development in the USSR. In fact, their research efforts probably go far beyond this point. However, we should note that this device can be used as a most efficient brainwashing instrument.

DOWSING

To understand how dowsing works, we must first understand something about higher dimensional spaces. It should be evident that, if there is a type of energy being sensed by the dowser, that energy must be coming in or arriving from outside this three-dimensional world, since our ordinary science deals with the energies existing in this world, and none of these ordinary energies can explain dowsing. However, because of the work that has been done showing that dowsers are extremely sensitive to magnetic fields, this energy must be somehow related to the ordinary magnetic or electromagnetic fields known to science.

In the human being the mindworld must itself have a coupled kindling system to cohere its changes and kindle them into electromagnetic energy and energize the physical body. The body system which does a great deal of this is the acupuncture system of points, plexuses, and meridians. Also, all powerful emoters, such as the endocrine gland system, are deeply involved in the kindling of the biological organism's mind energies into electromagnetic energies to energize the physical body. The body and its biorhythms form a coherent tuner in the time channel to accomplish this kindling of time-nested vital thought energies into ordinary energy. Because a great deal of mind energy kindles into only a minute amount of normal electromagnetic energy, our minds normally have only a small effect in this particular three-dimensional world. So we can normally psychokinetically move a few electrons in our brain and nervous system, and generate an input signal to our otherwise inert physical servomechanism. Ordinary inert physics and amplification takes over from there, and we can only deduce the kindling as mental intent from observing many, many quanta of physical change, i.e., from macroscopic behavior. At any rate, the dowser has learned to detect, focus, and sense very fine levels of electromagnetic fields, which means that at these low levels the kindling of mental energies can represent a much greater percentage of the field than normal. Thus the practiced dowser can now discriminate many of the particular types of fluctuations or changes in these weak fields due to mind kindling.

Furthermore, I would like to point out that, since mind kindling comes into this universe orthogonally, normal distances do not apply. The entire physical frame appears to the mind world as a point, and thus is totally inside the mind of the operator/dowser. It is for that reason that a dowser can establish a coherent tuning (intent) between a map and the actual ground, or between a picture and an actual object, or between a rod and a person' physical body when sensing medical illnesses. In the mindworld frame, the dowser is only dowsing or detecting himself, and himself includes this entire physical world — the earth's surface and beneath it, the sun, the moon, the stars, or whatever.

Just as the body used electricity, magnetism, and electromagnetic signals long before man knew of their existence, it has used kindling of bioenergy from higher dimensional frames for a very long time, even though these have been unknown to mankind. And dowsing is a very old art indeed; the ancients used magnets without knowing of magnetic field, and they used dowsing without knowing of hyperspaces and hyperfields.

THE STROBE EFFECT

These five pictures show one of the more interesting effects demonstrated by many tulpoidal forms: strobing or "coining." What happens is that, much like a flat rock skipping across the surface of a pond, the orthorotating tulpoid skips in and out of its intersection with our three-dimensional frame.

In the first picture a glowing spherical tulpoid is shown to skip or strobe several limes while the camera shutter is open. It does not move in a linear pattern, but rocks around and back-and-forth.

In the second photo, an aerial photo, a UFO in photonic form (first bioframe) reveals itself to be strobing or skipping. (In university classes on the paranormal, I often refer to this type of action as *coining,* since it resembles a bright quarter or nickel that is photographed by stroboscopic light while rolling around.)



Photo 1



Photo 2



Photo 3

Photo 4



Photo 5

Photo 29. The strobe effect.



1. Even dischargo from Inert object (dime).



2. Healthy person in calm state

Photo 30. Kirlian photography.



3. Person in meditation



4. Angry person.



5. Person with London **flu.**



6. Interactions between three persons.

The third photo shows a more striated form. In fact, these forms show kindling and strobing at the same time. In addition, the physical size of the strobed intersection with our three-dimensional space changes during the photo exposure.

The fourth photo clearly shows both the striations due to strobing and also the variation in size of intersection in the zeroth frame by the hyperdimensional tulpoid.

Photo five again shows these effects, with the addition of the two "bursts" in the upper part of the left tulpoidal object and in the center tulpoid.

Significantly, psychokinesis also often demonstrates stroboscopic movement.

KIRLIAN PHOTOGRAPHY

These six pictures show some major characteristics of Kirlian photography: (1) an even discharge from an inert object (a dime); (2) a balanced, gentle, even discharge from a healthy person in a calm state; (3) a gentle outgoing discharge enhanced on one side, and a gentle indrawing on the other, from a person in a meditative state; (4) strong bunching and outgoing discharge from an angry person (the word "emote," after all, means "move outward"; (5) choppy (as if out of control) bunched and outgoing discharge from a person ill with London Flu, with strong suppression of the normal, relaxed blue component at the lower right; (6) interactions between three persons, showing differing degrees of outgoing and barrier reactions.

The film itself only records ordinary photochemical interactions; it specifically does not record the aura. However, changes in the discharge patterns can be and often are induced by kindling bioenergy into the first biofield (electromagnetic field), inducing changes in the sparking pattern and intensity. Furthermore, this can occur fairly readily on such a high voltage series of discharges, which are excellent collectors for kindling.

As a final note, it should be pointed out that David Faust *et al* have published a technical paper in the scientific literature detailing the fact that Western experimenters have not yet duplicated the Soviet equipment and methodology used in their Kirlian photography. While David formerly pointed out in *Science* that experimenters must carefully control the variables—particularly moisture (water is an excellent collector for kindling)—he has been widely misinterpreted as having proved that water vapor was responsible for all Kirlian effects. This he has not done at all, nor did he intend to, since he himself is one of the most competent investigators in electrophotography.

INTERACTION OF BIOFIELD, THOUGHT, AND SPARK DISCHARGE

These photographs are strong examples of the kindling mechanism. The subject tested was Uri Geller, a person with strong inceptive ability. In photo 1, the top two exposures are for control purposes, while in the bottom exposure, Uri is concentrating on the image of a circle. In photo 2, again there are two control exposures shown at the top, while in the bottom exposure Uri is concentrating on the image of a triangle. In photo 3, exposures are taken of Uri and a wristwatch; this is



Photo 31. Interaction of biofield, thought, and spark discharge.



4.



5.

a control photo. In photo 4, Uri is attempting to send energy toward the wristwatch, and a correlated change in the discharge patterns from his finger is evident. In photo 5, the arrows at the right point to control exposure of Uri and a silver ring; the arrows at the left point to the exposure made with Uri attempting to bend the ring psychokinetically without contact. The direct kindling of bioenergy in a force-field line intersecting the ring is striking. In such an intense kindling, note that the nuclear currents inside the nuclei of the silver atoms — where positive charge is being shuttled back and forth between protons and neutrons — are also being strongly kindled. Reductions in the positive charges steadily reduce the charged exchanging particles to quarklike particles, severely affecting the structural integrity and crystalline lattice directions of the base metal. By this means metal bending — or even breaking — is accomplished.

KERVRAN EFFECT

A direct and repeatable experiment showing that living systems can kindle bioenergy into ordinary energy and material effects has been made possible by the fascinating work of Louis Kervran. Kervran showed that chickens, fed a diet deficient in calcium but containing excess potassium, will have no calcium deficiency, since they transmute some of the potassium into calcium. Kervran's pioneering work has been duplicated in Japan and elsewhere, and the same effects have been demonstrated by living plants.

We may consider a neutron as a sort of bound system of a potential proton and a potential electron. Psychokinetically killing the charge on the potential electron converts the electron into a neutrino, leaving behind a proton now freed. For the one percent or so of potassium that is a calcium isobar, this process can produce ordinary calcium. Thus in a potassium-rich diet the chicken can psychokinetically transmute enough potassium into calcium to remain healthy.

Kervran was nominated for a Nobel Prize in 1977 by the Japanese researchers; his work is direct proof of the ability of living systems to violate present physics, and of the ability of mind energy or bioenergy to affect matter psychokinetically.

PSYCHIC SURGERY

These two photos taken by Sigrun Seutemann in the Phillipines show materialization of large lumps of tissue brought about by Tony Agpaoa on a patient from an educated Western culture. The minds of both the patient and the surgeon are involved in the process, according to the psychic surgeons themselves. "Western patients are strongly conditioned to believe that medicine involves bloody tissue, so this is what results in the particular form of the materializations. For native patients who are steeped in the lore of shamanistic medicine, apports may consist of substances such as leaves, coconut fibers, feathers, etc.

The legitimate surgeons, working in a religious group structure, are often able to generate sufficient kindling to fully materialize such unconsciously structured thought forms, and also to dematerialize and rematerialize the tumor from inside the patient's body, the tumor usually appearing or emerging from an opening which appears in the apport tissue. In the surgeon's view he is also being helped by powerful spirits — and continual charging of such thought forms with kindled



The overlay of materialized tissue is very obvious.

1. Materialization of apport tissue while removing a tumor from the abdomen.

otice the overlay of the materialized tissue,

NO PENETRATION OF THE FINGERS

2. Matoriallzatlon of apport tissue while working in the hip region.

Photo 32. Psychic surgery.



This highly unusual photograph resulted in the following manner: Mrs. Baune Is a devoutly religious lady, and on this particular day she had spent a great deal of time in prayer and a Christian attitude. Snow was gently falling on the shrubbery In her yard, and she and a neighbor were admiring the beauty of the fresh snowfall. The neighbor borrowed Mrs. Bauno's camera and snapped a photo of the snowfall. When the photo was developed, the falling snow had formed a pattern of Jesus on the shrubbery In Mrs. Baune's yard.

Photo 33. Kindling of thought bioenergy in snow.



Photo 34. A deliberate experiment with kindling.

energy indeed can yield bioenergetic formats of more intense energy than a single talented individual can usually muster in an unaided or unaugmented state. Almost every religion, in fact, still occasionally exhibits miracle healing accomplished in somewhat similar fashion, though possibly less dramatically.

The apport tissue is a materialized tulpoid, precisely as are sasquatch, the yeti, the Loch Ness monster, and UFO's. Apports are normally more stable than these latter materializations — but they have also been known to disappear, as have the "angel hair" apports associated with UFO's.

A DELIBERATE EXPERIMENT WITH KINDLING

I and other members of the American Association of Meta-Science performed a series of experiments in kindling thought or psychic energy into electromagnetic energy, and photographed the resulting light energy on film with an SX-70 camera. The two photos shown here are from one of those experiments. In the left picture, bioenergy is just at the "burst" point where it is being collected on a candle flame. Here the camera lens is not quite fully opened. Only a single 40-watt lamp illuminates the room, and several AAMS members have been engaged in about two hours of psychic exercises. In the second picture, the lens of the camera is fully opened, and a "burst" of kindled energy occurs as the lens shutter is operated. None of this is visible to the naked eye. The polaroid film, however, is sensitive to some infrared and ultraviolet frequencies, so that bioenergy kindling into electromagnetic energy at IR or UV frequency can be photographed even though not seen by the naked eye.

FAY CLARK'S "FIREFLIES"

Fay Clark experimented with an ultrasonic generator in a darkened fallout shelter and photographed the most interesting results. At one particular frequency, dynamic dots of light appeared, grouped themselves into formations, and demonstrated movement and growth. At times they seemed to respond to thought, as if they were somehow intelligent, sentient creatures. This is a beautiful case of kindling using ultrasonic frequencies as the collector mechanism. While Fay is no longer sure of just exactly which frequency produced the fireflies, he does know that he used frequencies in the 38—40 kilohertz region, among others. This may be significant, since the Vestigia experiment encountered electromagnetic frequencies in the same region in their historic study of a mystery light. The frequency region 38—40 kilohertz is a strong candidate for one of the magic window frequencies between bioframes where kindling is much easier than at other frequencies. Furthermore, since it is thought energy or mind that is actually being kindled, one would expect the possibility of sentient behavior. Clark's experiment occurred in the dark, so the squelching effect of visible light was not present. Finally, Fay Clark is a known psychic himself, and so this should have eased the kindling difficulty even further. The value of rigorous laboratory experiments based on the lines of Fay Clark's pioneering "firefly" experiment is strongly indicated.

"FOO" FIGHTERS

When large groups of people are under strong external pressure, one result is often tulpoidal "popouts" from the collective human unconscious.

A war is a typical example of a situation where the group consciousness of a country is under enormous pressure. In such a situation, the "targeted" population is often exposed to tulpoidal manifestations from time to time.

In World War II, for example, the Germans thought at first that the glowing lights darting around their planes were secret Allied weapons; and the Allies thought the same thing of the Germans when they saw such unusual phenomena. The French dubbed them "feu" (fire) fighters, which became "foo" to American soldiers in Europe.

"Foo" fighters were a common phenomenon in World War II, particularly in cloudy, overcast skies.

WATER MONSTERS

In the oceans and in every large body of water on earth, water monsters have been reported for centuries. Loch Ness in Scotland is of course one of the most publicized examples, but creatures of different shapes and sizes have been seen in large lakes and streams everywhere. This is not at all surprising when one realizes that a large body of water is a most excellent kindling reservoir, and bioenergetic forms are more readily kindled in such locations.

The large dead creature in photograph 36 was hauled off the bottom of the sea by Japanese fishermen in their nets, photographed, and then thrown back to prevent contamination of the catch of fish and to get rid of the stench from the decaying carcass. It is a pleisosaurlike creature's remains, not similar to anything else known on earth. Predictably, scientists were almost immediately at odds as to what it was, and the carcass has been called a shark, a whale, a large elephant seal, a genuine pleisoaur, etc., by various "experts." Nonetheless it was real and physical, and a good photograph was obtained of it.

Photograph 37 is one of the underwater photographs of the Loch Ness monster taken by a team from the Academy of Applied Science, Boston, Massachusetts on June 20, 1975. As can be seen by a detailed study of the photograph, this tulpoid is not clearly tuned or clearly formed. Many other photos of the Loch Ness monster have been taken, and various shapes and sizes and degrees of tuning have been recorded. In the Doc Shiels photos taken in 1977, Nessie is well formed but entirely different from the Academy photo. Also, Doc Shiels' photo was subjected to computer analysis by Ground Saucer Watch, and the image exhibited a transparency that was disturbing to the analysts. On the other hand, such a transparency is to be expected from a partially materialized tulpoid which is not completely orthorotated into the zeroth bioframe.

In the Academy photograph, one can see — particularly on the color original — a form which has several conglomerated faces, which exhibits eyelike structures in several locations to suggest first a cowlike face and then a horselike face, and incoherently tuned earlike and hornlike appendages in several places. In fact, the Academy photo bears little resemblance whatsoever to a pleisosaur or any other more normal and coherently structured mammal or fish.



Photo 35. Fay Clark's "fireflies."



"Foo fighter" tulpoids pacing Allied aircraft in World War II.



"Foo fighter" tulpoids over an airfield in China in World War II.

Photo 36. "Foo" fighters.



Photo 37. Pleisosaur-like creature hauled from the sea by Japanese fisherman.

The Loch Ness monster is definitely a tulpoidal form, and the format varies appreciably from reception to reception due to distortions and variations in tuning. Nessiteras rhombopteryx is a much stranger beast than anything the dedicated Nessie seekers, researchers, and scientists have yet suspected. In Part Two I will examine the scientific basis of tulpoidal forms.

CATTLE MUTILATIONS

Over 9,000 cattle mutilations have occurred in the U.S. alone since 1973.

The cow is a female symbol par excellence — our children drink cow's milk, and our babies feed on the milk from the cow's breast. The U.S., being a natural fortress, is a "female" symbol, for in primitive human evolution the females stayed in the cave or protected fortress while the males went forth to hunt or do battle. (This symbolism will be fully discussed in Part Three.) Violation of the female means that the heartland U.S. shall be violated.

Teats are cut off — the children of the West shall lose their sustenance; lips, ears, and tongues are removed — freedom of speech and hearing shall be excised; sexual organs are removed — no more fruit of the womb shall be evidenced in the West; sharp, surgical incisions are made — the operation shall be accomplished swiftly (blitzkrieg war) with surgical precision; zig-zag cuts — deception shall be used as to direction and intent; blood is totally drained — the lifeblood of the West shall be totally drained; edges of the cuts are often seared as if by a laser — advanced, futuristic weaponry (psychotronic weapons) shall "seal the end."

The cattle mutilations are materialized precognitive nightmares indicating the horror of the Armageddon to come, and these nightmarish paranormal mutilations reveal the true nature of the times. Yet no orthodox scientist or governmental agency is equipped or able to deal with a phenomenon such as this.

In ancient times the wise men knew how to do a metapsychological analysis of the species unconscious, and knew that tulpoidal phenomena were often symbolic signs of that which was to come.

Where are our wise men today?

BIG MAMA

UFO phenomena have also been associated with the cattle mutilations. One of these UFO-type tulpoids has been labelled Big Mama, because of its characteristic behavior of spawning smaller UFO light-shapes that split away and speed off to an area in which a cattle mutilation then occurs. The "spawned" UFO's then return and link up or join with Big Mama, and Big Mama then withdraws.

The photo shown here is a typical appearance of Big Mama. Big Mama takes many sizes and shapes, but is a fairly reliable indicator of paranormal cattle mutilations impending.



Photo 38. Loch Ness monster.



Photo 39. Cattle mutilation.

During the summer of 1978, two psychics and I — all members of the American Association of Meta-Science spotted a Big Mama-type UFO from the top floor of a hotel in Louisville, Kentucky. Realizing what it was, we promptly brought into play a certain type of powerful psychic exercise and tried to make it dematcrialize and vanish. Several times it briefly split into pieces (five to be precise), but we were unable to extinguish it. Over a period of approximately twenty minutes this effort continued, and all the while Big Mama slowly moved lower and further away, eventually disappearing behind a tall building after having become very distant.



Photo 40. Big Mama.

PART TWO

A THEORETICAL BACKGROUND FOR UNDERSTANDING PT, UFO'S, AND PSI PHENOMENA

Footnote for page 132:

'With the exception that, in my theory, the orthogonal universes crosstalk with each other at virtual (subquantum) levels. Indeed, 'change' in one universe consists of the quantum coherence in that universe of crosstalk in and out of it. The 'virtual state' in one universe is due to, and consists of, subquantally coherent (quantally incoherent) crosstalk in and out of that universe.

Psychotronics, unidentified flying objects (UFO's), and paranormal phenomena such as psychokinesis, telepathy, and precognition all have one thing in common: both mind and matter-energy are involved.

Hitherto, mainstream science has insisted on a rather arbitrary separation of mind and matter-energy. However, as we shall see, this separation is not based on good observation. For example, everyone exhibits in himself the ability of mind to affect matter. While theories of computers, control systems, and physics can explain human behavior once the physical system has been given an input signal, the original signal — intent, or what I call inception — is an unexplained mystery to ordinary science.

"Psychotronics" (a Czechoslovakian term) and "psychoenergetics" (a Soviet term) have been specifically designed to provide a framework for approaching the problems of mind, matter, and their interaction. If we can understand psychotronics, we will be able to understand better the interaction of mind and matter, including all paranormal phenomena, unidentified flying objects, and Fortean phenomena.

Let us therefore start by defining psychotronics. The prefix "psycho" refers to the mind. The suffix "tronics" refers to physics and physical devices. Thus the concept of psychotronics refers to a union of physics and metaphysics. Such an audacious concept can offer a solution to almost every present problem in metaphysics, the foundations of logic, the foundations of physics, and the foundations of mathematics.

To begin with, it seems necessary to form a unified theory of mind, matter, and their interaction. It also seems necessary to reinterpret and extend electromagnetic theory. Logic itself must be advanced, for a part of reality, although "illogical" according to our present logic, is nonetheless true. In metaphysics we must solve formidable problems: the ontological problem (nature of being); the problem of mind, and the interaction of mind and body; the problem of change; and the problem of nothing.

It has been said that fools rush in where angels fear to tread. To tackle the problems of psychotronics demands the audacity to rush in where even fools fear to **tread!**

At this time, it may be appropriate to point out that all Western science, mathematics, and logic are founded upon three simple laws of logic, proposed and formulated by Aristotle. Since the entire universe cannot be described by these three laws — parts of reality are known to violate one or more of them and hence be illogical though true — it appears that we must be audacious enough to tackle and change the three laws of logic, if a new paradigm is to be constructed to solve all the presently unsolved problems.

SOME UNEXPLAINED MYSTERIES OF PHYSICS

First, no one knows what mass really is; we do not know for sure whether inertial and gravitational mass are one and the same. General relativity says it is, **and** we know from experiments that if any difference exists between inertial mass **and** gravitational mass that difference is very small indeed. But we do not know positively that there is not some small but finite difference. And we have no idea why the mass of a moving object increases with respect to a static observer. It is simple to calculate in special relativity how much the mass increases as a function of the velocity, but no one has the foggiest notion why this happens. Particularly so since an observer standing on the moving object and moving along with it sees no increase in its mass at all.

This poses a real paradox; if we try to assign some absolute notion to the idea of mass, then any object has an infinite number of masses, all at the same time and all different. There are two ways to determine mass: (1) by its resistance to a disturbing force, and (2) by its ability to occupy three-dimensional space. The latter requires that mass be volumetric, i.e., that mass be L^3 dimensionally.

But look at the weird properties of a photon! If we measure its resistance to a disturbing force, we find that no force on earth can accelerate or decelerate the photon. If we measure the mass of a photon by the first method, it appears to have infinite mass. Yet if we measure it by the second method, it can have no mass at all, because a photon is not volumetric; it is two-dimensional. It therefore has infinite mass and zero mass simultaneously.

Furthermore, we can take the viewpoint that whatever its mass is, it can only have one. If that is so, then infinite mass and zero mass must somehow be the same thing! Which contradicts the three laws of logic. However, this should not concern us too greatly; many things contradict the laws of logic and are nonetheless true. So while it is presently "illogical" for infinite mass and zero mass to be identical, we should hold on to the idea that this may very well be true.

Additionally, one of the great cornerstone assumptions in physics is that gravitational field and electric field are mutually exclusive — i.e., they are totally different things. Yet a physicist named Santilli has proved that this is not so, and that they are either partially the same thing or totally the same thing. And there the matter stands, so we do not fully understand what electric field and gravitational field are, or how to go about turning one into the other, although Santilli's work seems to imply that this is at least theoretically possible. We must therefore invoke a new concept of reality.

URI GELLER

Uri Geller has demonstrated numerous capabilities: he has affected a magnometer inside a Faraday shield; bent and broken metal objects; caused a fresh flower to wither and dry in seconds; permanently changed the crystal structure of nitinol; altered magnetic programs on computer cards; influenced a Geiger counter; dematerialized matter; and demonstrated the inceptive Cyborg effect, thought-photography, telepathy, and the Geller effect (the sympathetic stimulation of a psi-positive).

It is useless to attempt to explain the feats performed by Uri Geller in terms of the ordinary fields and effects of known physics. Nothing short of a new physics paradigm will suffice. This new paradigm must encompass both mind and physics within the same theoretical framework, if it is to succeed in explaining how mind affects matter.

In terms of present physics and logic, the mind is regarded as totally separate from matter. For mind and matter to interact, some aspect of mind must be the same as some aspect of matter, i.e., to move matter, a force is required. Force is the time rate of change of momentum. To generate a force capable of moving matter, mind must be able to change momentum. But since momentum can only be obtained from something which possesses momentum to give up, then the mind must somehow possess momentum.

If this is so, then the momentum must ordinarily exist in a separate three-dimensional space, since it apparently does not ordinarily exist in laboratory three-dimensional space. Such a situation requires at least six spatial dimensions and one common time dimension, such that the mind (mental phenomena) is a set of objective physical phenomena existing in an ordinary objective three-dimensional space, but one which is three orthogonalities away, spatially, from the laboratory three-dimensional space.

Mental changes upon physical objects would thus imply orthogonal rotation of mental objects from the mental three-dimensional space into or closer to the laboratory three-dimensional space. Everett's many-worlds interpretation (MWI) of quantum mechanics contains a structure where such representation is possible, and the MWI is consistent with the entire experimental basis of modern physics. Thus from the MWI it is possible to objectively model the mind and matter, and from that, psychotronics as well.

MY APPROACH TO PSYCHOTRONICS

In twelve years of intensive work on this question, I have evolved a conceptual approach, which is consistent with present physics but extends it. A new concept of reality is involved, however, and severe demands are made on the individual to stretch his framework of comprehension. The perceptron concept is an abstraction that allows the modeling of perception itself— either mental perception or physical detection. The fourth law of logic (to be explained shortly) involves the age-old identity of opposites whose apparent necessity has baffled logicians, philosophers, and scientists for centuries. With the perceptron concept, we can at last comprehend how the identity of opposites is accomplished, and when it is accomplished.

This immediately solves the age-old philosophical problem of change. The fourth law also closes logic into a complete, closed metalogic, encompassing both physics and metaphysics.

Let us use as a definition of reality: *reality is that which can be conceptually and mathematically modeled and fitted to the phenomena existing in one or more minds.* Physical reality is that which can be modeled and fitted to the phenomena existing in all minds. Mental reality can be modeled and fitted to the phenomena in one mind. Mental and physical realities comprise "normal" reality. Complex or "paranormal" reality is that which can be conceptually and mathematically modeled and fitted to phenomena which exist in more than one mind, but not in all minds.

From perception theory I have succeeded in deriving a great deal of the present basis of physics, including Einstein's two postulates, Newton's laws, the law of gravitation, and the solution to the ontological problem. (Unknown to me at the time, Ives had already done so for Newton's laws, the law of gravitation, and Einstein's postulates. His work has unfortunately been ignored.) In addition, the photon can be seen to be an ordinary three-dimensional particle existing in a three-dimensional space that is orthogonal to the laboratory three-dimensional space frame. A stationary particle in the laboratory frame appears as a photon to the orthogonal spatial frame.

Einstein's second postulate is usually stated as "the speed of light is the same for every observer." Restated, this becomes "every photon in an inertial frame is moving at the speed of light, c, with respect to every particle in that inertial frame." The corollary then follows immediately: every particle in that inertial frame is also moving at the speed of light, c, with respect to every photon in that inertial frame. In a single three-dimensional space, this is incomprehensible. Taking two orthogonal three-dimensional spaces, with the photons in one frame and the electrons in the other, it is perfectly comprehensible.

From pure nothing — empty vacuum, absence of thing — one can generate everything, the presence of thing. Here is direct proof that ultimately opposites are identical. But to a mind rigidly programmed in three-law logic, such a truth is abhorrent. Physicists consequently have done nothing with the idea that all our physical laws — or at least most of the great ones — can be straightforwardly derived from a special kind of a "piece of nothing" which I call a quiton. And they have not seen that this constitutes a statement of a fourth law of logic—the identity of opposites on their common boundary.

It is interesting to note that the paper which was handed to an American reporter, Robert Toth, by a Soviet scientist, and which caused the KGB to seize Toth and charge him with receiving Soviet state secrets, contained just such a theory as the basis of a unifying theory of psychotronics. Yet none of our intelligence analysts seems to have picked up the overwhelming importance of what was in the paper, and Toth himself appears to believe that his KGB arrest was simply harassment. In fact the paper did contain material on the basic Soviet approach to psychotronics — and thus to psychotronic weapons — and it was indeed state secrets that had been given to Toth.

Everett's many-worlds interpretation of quantum mechanics, with which very few physicists are familiar, provides a needed correction to the conventional monocular interpretation of relativity, and it allows a theoretically sound basis to be constructed for psychotronics.

The conventional interpretation of relativity considers only a single observer at a time. But if you can accept so simple a concept as that both you and I exist simultaneously, regardless of how we move with respect to each other, then I assure you that physics is startlingly different from what you may have studied in the ordinary university physics text book.

Everett, originally a student of the world-renowned physicist Dr. John Wheeler at Princeton, for his Ph.D. thesis considered the problem of multiple simultaneous observers and worked out what this did to physics. His highly innovative thesis provided a totally new interpretation of quantum physics and defined a startling new kind of reality in which all possibilities are physically real and exist. This new physics is indeed very strange, but it is totally consistent with the entire experimental basis of physics today.

I discovered that all my perception theory could be fitted precisely onto Everett's many-worlds interpretation.[1] On that basis, a theory or schema of biofields was derived that provides an approach to a unified field theory. In fact, it predicts that any kind of field can be turned into any other kind of field, merely by correct and precise time synchronization. It also offers a physical and exact model of mind and mental phenomena and a mental and exact model of physical phenomena!

On this basis, a framework can be provided for psychotronics which is consistent with what we know of ordinary physics but which does not contain many of the limitations of ordinary physics. In a strange sense Everett wrote the physics for the all-mind or the Supreme Creator's mind because an unlimited mind, so to speak, must already have thought of everything possible, and for an all-creative mind to "think" a possibility is for that possibility to be real.



Fig. 3. Reality: a paranormal bridge with two ends

1. Reality as a Paranormal Bridge with Two Ends

In Figure 3, I show the nature of the problem of paranormal phenomena. To understand it, we must first define more precisely some of the present concepts.

First, what do we really mean when we talk of "physical phenomena"? To go into this, we must first destroy the notion that there exists some sort of separate, concrete reality totally apart from mind, for that notion is simply the old Cartesian assumption. It has long been refuted as far as having any absolute validity, and this is well-known to philosophers and to foundations physicists. According to Lindsay and Margenau in their *Foundations of Physics,* "physics has nothing to say about a possible real world lying behind experience."

What is true is that we can experience and detect and know only a mental change — a change in the mind itself is all we ever experience directly. For experience invokes the mind; we do not experience phenomena until the mind — used in the greater sense of the word to mean any mental detection — changes.

Any detector detects or experiences only an internal change, never an external change, and this is true of the mind as well as a physical detector.

So we never experience external physical phenomena; we experience only our own minds. Specifically, each of us experiences his own mental phenomena.

But here we must be a little more precise about what we mean by "mental phenomena." What we usually refer to are the mental phenomena in a single mind. And so we will take that as the primary definition: *mental phenomena are the phenomena or changes in a single mind.*

But then what do we mean by "physical phenomena"? For indeed this refers to something that is often remarkably different — or seems to be — from the phenomena or changes going on in our own heads. Before we jump to the extreme conclusion that physical phenomena are simply mental illusions, we should recall the Zen master's approach. He demanded of the student whether or not physical phenomena were real, and the student replied that they were not real, but only illusions. Whereupon the master gave him a resounding knock on the head, and asked him whether or not the blow was real. The student replied that the blow was indeed real. Whereupon the master sent him back for further meditation, for he had learned nothing. He had not understood that "mental" and "physical" are not mutually exclusive.

If we look closely at how we may differentiate between mental phenomena and physical phenomena, we immediately hit upon a practical scheme. Physical phenomena can be shown to exist in the mind of any observer, be he human, insect, or whatever, so long as he has consciousness.

Suppose for a moment that I have a piece of chalk in my hand, held between my fingers. I can touch the chalk, feel it, and see it. I can even taste it if I wish. And so I hold up the piece of chalk and say: "This piece of chalk is not just a mental impression, it is physically real." How can I prove it? And when I prove it, what exactly have I proved?

Now suppose you do not wish to believe the chalk is real. You simply bring in another observer; he looks at the chalk, he touches it, he tastes it, and he rolls it between his fingertips. He confirms that he also detects or experiences the chalk. Then a little bug flies in and lands on the chalk, crawling around on it, and poking at it with his little proboscis. He also by his actions confirms that he has it in his own little mind. In fact, we could bring in any sort of mind, and that mind could experience the chalk.

And this of course is the clue. What we have been calling physical phenomena can be shown to exist in every mind. And when we say something is physically real, this is all we actually mean. Nothing more, nothing less. And this is why physical phenomena are so solid and concrete; they are infinitely repeated. However, what we refer to as mental phenomena are in only one single mind and thus are not repeated at all.

Now let us do a little thought experiment. Suppose I have lapsed into some peculiar mental state because of the toxins from an infection I have contracted, and I am hallucinating vividly. Suppose I pick up what I vividly see, feel, touch, and taste as a piece of chalk, and I claim that it is real. Indeed, to me it is very real. And then suppose a second person comes into the room. He will not see the chalk, touch it, feel it, taste it, and it will not be real to him. Then suppose a third person comes into the room, and he does not see the chalk, he passes his fingers right through where I am seeing the chalk and does not contact or feel it, and he indeed cannot find it. Thus what we call a "mental phenomenon" can be shown to exist in one mind only. In this case of a vivid hallucination, the hallucinatory phenomenon was absent from the other observers' minds.

But now let us change our thought experiment a little. Suppose now that I am absolutely fit and fine physically and mentally, and am not hallucinating. And suppose all the observers we bring in are also fine both physically and mentally, and not hallucinating. And suppose we get the following results: some of us can see, touch, taste, and experience the chalk, and others of us cannot see, touch, taste, or experience it, no matter how we try. In that case, what kind of phenomenon do we have?

Well, we cannot exactly say the phenomenon is exclusively mental or exclusively physical. But we also cannot say that it is exclusively nonmental or exclusively nonphysical. In fact, we have an example of a third class of phenomena which are presently not recognized by science. *We simply have a paranormal phenomenon,* one which can be shown to violate our definitions of mental phenomena and physical phenomena.

And we can in fact take this as the definition of a paranormal phenomenon: *a paranormal phenomenon can be shown to exist in more than one mind, and it can also be shown not to exist in one or more minds, i.e., paranormal phenomena exist in more than one mind, but not in all minds.* Our conventional science recognizes purely mental phenomena and purely physical phenomena; it does not recognize the third kind, since by the ordinary three laws of logic the third kind does not exist. Paranormal phenomena constitute a bridge across a river between two banks; our present science does not recognize the bridge, but only recognizes the two banks, as shown in Figure 3.

Paranormal phenomena thus appear erratic to ordinary objective science, for objective method after all is specifically designed to select only those phenomena that can be reliably repeated, and the nature of paranormal phenomena is such that they often (in fact usually) cannot be reliably repeated, except sometimes in a great many trials. Normal objective method, if rigorously applied, can only discriminate a statistical effect from a great many trials. Furthermore, if rigorously and lengthily applied, it will accumulate so many failures that it will cast serious doubt on whether the odd case that was paranormal was in fact nonaccidental.

It is for this very reason that orthodox science, which is devoted to scientific method and rigorous protocol, has remained so comfortably adamant that paranormal phenomena do not exist. The tool must be changed to fit the problem, and the present scientific toolbag does not fit precisely. The tools are useful, but they themselves are not decisive within the bounds of present protocol. The necessary change is quite simple: we must allow for the effects of mind, and for a union of both mind and physics, just as there exists in physics a union of both wave and particle. In other words, paranormal phenomena must be repeatable *sometimes,* by competent experimenters and observers, but not necessarily *always* by all observers.

"Ah ha!" the materialist is likely to exclaim, being unable to contain himself any longer. "Solid concrete reality always is solid and concrete, however, and you cannot change that. As long as that is true, then the laws of ordinary physics hold, and all is right with the universe. We can always select our phenomena which are present in all minds, and this after all constitutes immutable physical reality. In the luce of that fact, all your arguments about mental phenomena in one mind and another kind of half-mental, half-physical phenomena are meaningless, for you are simply calling the superposition of purely mental phenomena on purely physical phenomena a third class, but it is a separable mixture, not a completely new kind." And we may even be tempted to stir up a small bit of sympathy for the materialist's view.

However, let us propose a resolution. If we can show that concrete, solid, real matter can become absolutely nonconcrete, nonsolid, and hence nonphysical, then that ought to settle the question. In a recent experiment it has been conclusively shown that two colliding protons pass right through each other in total violation of all physical rules, if their spins are exactly antiparallel. Protons are the central building blocks of all matter. In the nucleus of an atom, the protons and neutrons are continually switching identities, so even a neutron keeps turning into a proton, etc. And these fundamental constituents of everything solid and concrete and real just go right through one another, without any effect whatsoever, simply by aligning their spins properly. Collision theory fails, electromagnetic theory fails, and our concept of two particles bumping together fails. This experiment totally annihilates the idea that physical reality is something absolute. In fact, it establishes that physical reality itself is a function of the relations between the interacting participants; changing the relationships can simply cancel physical reality.

So perhaps our definition of physical reality has some merit after all, and perhaps there really are three classes of phenomena. The paranormal phenomenon is a bridge between mental and physical phenomena; specifically, every paranormal phenomenon must consist of an inseparably welded compound of the two. And the objective method and its consequent experimental protocol must be changed to reflect this fact, if we are ever to develop a viable theory of paranormal phenomena.

2. A Fundamental Correction to Classical Logic

Let us now make a fundamental correction to Aristotle's three laws of logic. First, there is no independent existence to mental phenomena; there is a perception operation involved when we think. There is no independent existence to physical phenomena; there is a perception operation involved when we observe physical phenomena. Furthermore, it takes a finite piece of time for the perception process to occur. The logic symbol also requires a separate time interval; it represents a series of separately perceived operations that together comprise a decision algorithm. So let us impose this criterion upon logic itself so as to constitute "logical perception" or the "logic of perception" or the "perception of logic." We begin with Aristotle's third law of logic, *A* or *not-A,* the law of the excluded middle.

We still insist that there is no such thing as *A* per se, but rather that there is a perceived *A* where *A* is the output of the perception process. Similarly, there is no such thing as *not-A,* but rather there is a perceived *not-A* where *not-A* is the output of the perception process. Let us think of a square box symbol as an abbreviation for the fact that perception has occurred, and anything written inside the box represents the output of that perception operation. We can speak of the box either as mental perception, a description of thought, or we can speak of it as physical detection, a description of an instrumentation system that detects and measures. Also, since each box requires a finite time to occur, we must carefully keep up with the individual little pieces of time, the delta t's.

So applying this to Aristotle's third law, we have *A* perceived or outputted in time one, and *not-A* outputted in time two. Note that to ascertain that A_1 and *not-*A_2 actually differ requires a series of operations in a separate time interval, in time three, that is assumed by the *exclusive* or symbol. Looked at in this way, Aristotle's third law actually is the law of monocularity; it states that only one thing at a time is perceived. Actually we had assumed this when we assumed that perception was a

1. $A \vee \bar{A}$ ARISTOTLE'S LAW OF THE EXCLUDED MIDDLE

2. DEFINE $\square$ AS "IS PERCEIVED"

3. $\boxed{A} \vee \boxed{\bar{A}}$ LAW OF THE EXCLUDED MIDDLE

4. EACH PERCEPTION IS A FINITE OPERATION AND REQUIRES A FINITE TIME TO OCCUR.

   THE LOGIC SYMBOL ALSO REPRESENTS A DECISION ALGORITHM: A SERIES OF OPERATIONS PERFORMED IN A SEPARATE TIME INTERVAL.

   EACH FINITE TIME INTERVAL MUST BE ACCOUNTED FOR.

5. $\boxed{A}_1 \vee_3 \boxed{\bar{A}}_2$

6. THE LAW STATES THAT PERCEPTION IS A MONOCULAR PROCESS IN TIME 3.

   ONLY ONE-THING-AT-A-TIME IS PERCEIVED.

7. NOW NOTE THAT SEPARATION OF A AND $\bar{A}$ DOES NOT OCCUR IN

$$\boxed{(A_1 , \bar{A}_2)}_3 \quad \equiv_5 \quad \boxed{B}_4$$

8. SO $A_1 \equiv_3 \bar{A}_2 \Big|_{4,5}$ BOUNDARY IDENTITY OF EXACT OPPOSITES

9. AND EQUATION 8 CONSTITUTES A FOURTH LAW OF LOGICAL THOUGHT.

   IT SIMPLY STATES THAT PERCEPTION THREE IS BINOCULAR, AND EXCLUSIVE SEPARATION OF EITHER A OR $\bar{A}$ IS NOT PERMITTED.

Fig. 4. A fundamental correction to classical logic

finite process, so it is nice to find that Aristotle's third law justifies our assumption, once we understand the third law. The *exclusive or* symbol assumes a third operation in time three, whereby it is determined that perception output one and output two actually differ. But such an operation itself requires multiocular perception — i.e., collecting two outputs at once — and that in itself is a violation of Aristotle's third law. The third law thus contains its own contradiction, and indeed each of the other two laws also contradicts the third law when one examines them meticulously. Each can only be established as true by invoking or involving an operation wherein the third law is not true.

In time three we gathered up what had been perception output in time one, A_1 and what had been perception output in time two, A_2, which we do not yet know is different from A_1, and put them both through the perception process, getting only one output — let us call it B — in time four. By the nature of B in time four, we thus say in time five that the outputs in times one and two differ or not. In either time one or time two, there is no indication whatsoever of difference or sameness existing between output one and output two. Likewise, in time three there is no separate output one and output two, hence no indication of the sameness of, or difference between, outputs one and two.

So here we have arrived at the identity of opposites. There is no perception of difference between A_1 and *not*-A_2 in time three. And this constitutes a fourth law of logic: the law of the boundary, or the boundary identity of exact opposites. All that is necessary to identify opposites is to lose all perceptual distinction between them. And that is accomplished by multiocular perception, of perceiving the presence of both at once unseparated, hence the absence of either exclusively present. If A_1 and A_2 are exact opposites, then $B_4 = O$, and $[A_1, A_2]_3 = O$. We thus have the solution to the problem of nothing. Nothing simply consists of the presence of the totality of all opposites.

Almost all the philosophers who have struggled with the problems of being, mind, and matter have faced the necessity for the identity of opposites, but none of them could understand how opposites could be identified. By careful accounting of the separate time intervals required for finite monocular perceptions, the mechanism for identifying opposites is immediately clarified and revealed. The laws of logic are simply laws of the operation of perception — nothing more, nothing less.

The new system of logic is closed. All present paradoxes — contradictions of one or more of the first three laws — are resolved by the fourth law, which contains the negation of each of the first three laws. The fourth law is in fact the law of the paradox. Note also that the hidden time-three operation, which has actually been the application of the fourth law all along, is implied in each of the first three laws. Identity or nonidentity between time-one and time-two outputs can only be established in a time-three operation. The fact that either *A* or *not-A* exclusively exists can only be established by a separate operation which establishes that nothing else is there. If separation of *A* and *not-A* is not permitted, then *A* and *not-A* cannot be distinguished.

Since these laws refer to perceptual operations, one can think of them operationally, or vectorially. To close the vectorial system prescribed by the first three laws, the opposite or negation of each of the three vectorial statements must be present, i.e., this follows simply from the definition of what constitutes a closed system, vectorially speaking. Since the fourth law contains the negation of each of



Fig. 5. A physical example

the first three laws, then the four-law system is indeed closed, and the logician's dream of a closed metalogic is realized. Furthermore, anything which contradicts any combination of the first three laws automatically is covered by the fourth law, which is the law of the paradox.

The new logic works as follows: either the first three laws apply (separation of *A* and *not-A* is permitted), or the fourth law applies (separation of *A* and *not-A* is not permitted). The fourth law applies only to — and in fact *creates* — a boundary. The first three laws apply only away from a boundary.

3. A Physical Example

Take the surface of a cube in deep space (Fig. 5). Call the cube "thing," a three-dimensional concept. Call the empty space around the cube "nonthing," a three-dimensional nonthing or absence of thing. If we are standing inside the cube and look at its boundary surface, we cannot find a single piece of that boundary surface that does not belong totally to the cube. So we can very reasonably proclaim that by the first three laws of logic each piece of the boundary belongs totally to the cube, to "thing." But if in a different operation we are standing outside the cube, we cannot find a single piece of that boundary surface that does not belong entirely to the space surrounding the cube. So in this case, we can claim by the first three laws of logic that the boundary surface belongs totally to "nonthing."

Then in a third operation we can state that, by the first law of logic, each and every piece of the boundary surface is identical to itself, and of course we thereby identify what was thing with what was nonthing. Specifically, what was thing in perception time one and what was nonthing in perception time two have been identified, by all distinction and separation between them being removed, in time three. Identifying opposites simply consists of "packing together" two previously separated perceptions into a single third unseparated perception. And all we have done is apply the fourth law of logic, the law of the boundary. Every single perceived thing has a boundary, where it both begins and ends its exclusive presence in perception output. And at that boundary, the fourth law applies. Thus the law is universal. The fourth law defines a boundary.

In fact, in any perception, all four laws are applied. They are applied in one of two fashions: (1) the first three are explicit and the fourth implicit, or (2) the first three are implicit and the fourth explicit.

There are more examples that have baffled mathematicians and logicians. All of these are simply boundary statements, i.e., statements involving the fourth law of logic. For example: "It is true that this statement is false"; "A line (length) is composed of points (nonlengths)"; "In a hologram, each part is the whole."

Since logicians used only the first three laws, none of these statements was acceptable or understandable. By the fourth law, there is no problem with these statements. The first merely refers to the boundary between the operation used to establish "truth" and the operation used to establish "falsity." There is another class of operation where neither truth nor falsity exclusively applies — i.e., a class of operation which cannot distinguish between "true" and "false."

The second statement has long been a painful trauma to logicians and foundations mathematicians. Today foundations mathematicians seldom attempt to define line or point. Instead, they simply say: "There is a class of entities called lines. There is a class of entities called points. Lines are made up of an infinite number of points." This way, they avoid trying to explain how "length" (line) can be made up *of* "nonlength" (points).

However, they could easily have avoided the difficulty, and still retained the definition of a line as a length, and a point as a nonlength, in the following manner. "There is a class of entities called lines. A line is and has length. There is a class of entities called points. A point is and has nonlength. We may have a separate perception that shows nonlength, and another separate perception that shows length. In yet a third perception which infolds both the first two perceptual characteristics, we may say that a line is comprised of points so long as we realize that line and point do not separately and exclusively exist in the comprised-of state."

By the same token, we can say that "the whole is comprised of the sum of the parts" only if we realize that "whole" and "part" do not separately and exclusively exist in the comprised-of state, but instead they inseparably and nonexclusively exist therein.

4. New Definition of Zero

To a monocular perception process, multiple presence constitutes absence of the exclusive presence of any particular one. Therefore such a multiple presence is monocularly unperceivable, and hence becomes a zero to a monocular detection process. This allows new definitions of zero, and a solution to the problem of nothing.

Consider that a monocular detection process asks the question, "Is there a single exclusive thing present in my input?" If the answer is yes, an output is generated and perception occurs. If the answer is no, no output is generated and perception does not occur. The answer "no" occurs in two fashions: either total absence, or presence of two or more simultaneously. For either of these cases, monocular perception gives no output, and perception does not occur, i.e., the absence of perception occurs.

Now note that the monocular perception cannot tell any difference in the two input conditions. To it, there is no distinction between the two conditions. The lack of any difference at all constitutes identity. Thus to a monocular perception process, condition one is identical to condition two when they are infolded together in condition three. That in fact derives the fourth law of logic. Total absence and multiple, unseparated presence are identical insofar as a monocular detection process is concerned.

5. Einstein's Postulate

As an example of strange problems we can deal with in a four-law manner, let us examine a little more closely one of Einstein's postulates of special relativity, which states that the speed of light is the same for every observer. Let us restate the postulate as "every photon is moving at the same speed relative to every particle." We can pick any electron in the laboratory frame. Every photon in the frame is moving at the speed of light with respect to the electron, by Einstein's postulate. Now let us pick any photon. By Einstein's postulate, every electron is also moving at the speed of light with respect to this photon.

Now we can look at the situation from the viewpoint of the photon. With respect to it, every electron in the laboratory frame is moving at the speed of light, which violates the common interpretation that ordinary objects cannot move at the speed of light. In fact, three-law logic is violated but four-law logic is not violated. In four-law logic, an object can have infinite mass and zero mass simultaneously. The electron's frame and the photon's frame are rotated orthogonal to each other. What we were calling a photon in the laboratory frame, is a perfectly ordinary three-dimensional object in its own frame, which is orthogonal to the laboratory frame. The electron (lab-frame) thus appears as a photon in the rotated frame of what we previously called a "lab-frame photon." Either an electron or a photon is both three-dimensional and two-dimensional simultaneously — in fact, the concept of separate, exclusive dimensionality only applies after one or the other dimensional aspect has been exclusively separated (observed).

Mass is determined by the resistance an object poses to an accelerating or disturbing force. Mass is also tied to three-dimensional objects; i.e., it is an L^3 concept dimensionally. A photon, moving at the speed of light, can neither be speeded up nor slowed down; hence in one sense it exhibits infinite mass. On the other hand, the photon (which is a three-dimensional object in its own frame) has lost a dimension in its intersection in the laboratory frame, due to orthogonality. Therefore the photon appears as a two-dimensional L^2 entity in the laboratory three-space. And in that sense, the photon must have zero mass since it is only two-dimensional. By the fourth law, the boundary opposites are identified. Thus at the orthogonal boundary of three-space, zero mass and infinite mass become identical. And the photon exhibits both zero mass and infinite mass simultaneously because it is an entity that is on the boundary of the L^3 "mass exhibiting" world. The photon has always happily behaved in a four-law manner, even though physicists could not comprehend its behavior with the three-law logic ingrained in their heads.

6. Synchronicity of Concepts

As is so often the case, two persons appear to have derived the new logic simultaneously, myself from perception theory and Hubbard from manifold theory.

Dr. J. Hubbard was one of the scientists who first developed the atomic bomb. His profound work fully substantiates the new logic and the new reality paradigm. Dr. Hubbard believes that the system includes language, logic, and the interaction of life-bearing systems. In short, he believes it includes psychotronics. The relationship between mind and matter is, like Santilli's electric and gravitational fields, not mutually exclusive; they are either partially or totally one and the same thing. According to my research, they are both partially and totally the same thing, i.e., they are of exactly the same nature totally — a closure of the entire physical universe — but only partially intersecting, by a fraction of approximately 10^{-42}. In the same fashion a mind is an entire physical world, but it only minutely intersects this physical frame, and then only in a portion of this physical plane.

Dr. Hubbard has shown that the four laws of logic emerge in the form of set relationships, that the single dimension parameter generates the second, third, fourth, fifth and up to *Nth* dimensions of the manifold, by repetitive operations on itself. This allows a firm basis for orthogonal intersections of one less than the dimensionality of the lowest-dimensioned intersector. It provides a firm basis for orthorotation and for my approach to psychotronics.

PRIMITIVE PERCEPTION

Let us now discuss how we form our concept of objects and their relationship. All our basic perceptual concepts are essentially built on primitive observation of the macroscopic universe, which is the primary reason that so many final arguments of philosophers appeal to the "natural man," i.e., to how a primitive observer would react to the argument. The very idea of an object — a perceived object — is conditioned. Everything else we think of is then conceived as some sort of object or relation between objects. And that is why sets (of perceptual objects) and their relationships form the basis for axiomatic logic, mathematics, and physics. Set theory is simply the synthesized and abstracted game of elementary perception of the macroscopic world. Thus even the most abstruse mathematics forms a part of the game of perception and can be applied to perceived physical phenomena. This macroscopic, primitive perception is the basis of our concept of objectivity, and of our physical concepts of "observed" and "observable." But if we examine


ΔT
ΔT
A'
4-space
A''
3-space position #1
3-space position #2
ΔT
ΔT

photon is absorbed, adding ΔT and making the absorbing object four-dimensional

Photon has previously been emitted, and traveled to the observer's eye, so that he detected a corresponding change on the retina, which "detected object A in its spatial position #1"

Photon emitted, traveling to the observer's eye, so that he may detect a corresponding change on the retina, which "detects object A in its spatial position #2'

Fig. 6. Primitive perception

carefully exactly how we perceive an object in the macroscopic world, we realize that it is seen by means of photon interaction. We think of light being absorbed onto the surface of the object, and then emitted or reradiated from the surface, eventually entering the eye. There the photons are again absorbed by the material on the retina. The photoelectric effect then moves what are called electrons, producing a signal that goes to the brain for interpretation

What we see as an object has twice undergone interaction with photons of light. Furthermore, light itself cannot be detected, only its interaction with matter (in this case electrons). Thus the primitive perceptual operations of the human brain are correlated one-to-one with photon emission and absorption interactions, usually paired interactions at the object reality domain. The concepts of object, mass, three-dimensions, and observation are directly correlated to the photon-mass interaction, and ultimately to the photon-electron interaction occurring in the human retina.

The ideas of boundary, surface, and change in primitive perception thus involve two contradictory and simultaneously mixed interactions, absorption and emission. Because they are constantly intermingled, primitive perception cannot separate the two. Thus the primitive concept of a boundary consists of a simultaneous duality. Here the object both begins and ends. Here opposites are identified. This is the basis for the fourth law of logic, the law of the boundary.

The dimensionality and orthogonality (spatially) of the primitive perception process are also interesting. Photon absorption constitutes spatial integration for the photon, dimensionally speaking, *e.g.*, one additional dimension is gained by the two-dimensional light wave in turning itself into the three-dimensional mass state. The photon also adds its piece of time to the absorbing mass, converting the mass particle to mass time or space time—adding the fourth dimension. Photon emission constitutes spatial differentiation, dimensionally speaking. One spatial dimension is lost by a little hunk of three-dimensional mass turning itself into a two-dimensional wave. Going from outside the object toward the inside (to track along with photon absorption), the boundary marks the end of the two-dimensional wave region, so the object (or, more precisely, the interaction region) is spatially two-dimensional on the outside, and spatially three-dimensional on the inside. It also occupies the time dimension on the inside, but not on the outside. (This directly accounts for a difference in the spacetime inside and the spacetime outside, and that is why mass may be regarded as a curvature or change in spacetime, in general relativity.)

Going from inside the object toward the outside, the boundary marks the end of the spatially three-dimensional region and the beginning of the spatially two-dimensional region. So the object is now spatially three-dimensional on the inside, spatially two-dimensional on the outside. The inside now does not occupy the time dimension, while the photon emitted (the outside) does. So on the boundary, one spatial dimension is gained going in, and one spatial dimension is lost going out Time is gained going in and lost going out, by the mass absorber-emitter.

Gain or loss of a dimension is accomplished only by orthogonal rotation between orthogonal spatial frames. Photon absorption constitutes orthogonal spatial rotation one right angle turn into the laboratory frame, while photon emission constitutes orthogonal spatial rotation one right angle turn out of the laboratory three-space frame.

This constitutes the observation process (primitively) per se, and this is what is hidden in Einstein's postulate that the speed of light is the same to every observer. Every observer goes through this same process. Furthermore, rotations orthogonal to a three-space frame are orthogonal to all three-dimensional spatial physical entities in that three-space. As Einstein himself once pointed out, velocity can be regarded as simply the measure of rotation of an entity in a higher dimensional space; thus an orthogonal turn is a fixed velocity. Since light is orthogonal to the entire space, then the speed of light is the same to every observer in that space.

While Einstein was apparently speaking of regarding the velocity of an object as a measure of its amount of rotation toward the time axis in four-space (from the direction of its velocity vector in laboratory three-space), it can also be regarded as rotation toward a fourth spatial axis in a five-space (four length dimensions and one time dimension, all orthogonal). If one checks this, one will see that the projections in three-space are the same; i.e., to the laboratory frame observer, there is no difference observable. Thus the photon interaction may be modeled as orthorotation of an entity spatially in a five-space.

To the laboratory observer, this orthorotation constitutes pure dimensional integration and dimensional differentiation, and it constitutes or creates an object in the first place. The concept of object *a priori* involves the photon interaction as stated; if the photon interaction is not invoked, then the existent entity does not exist as a three-dimensional object at all, in the primitive sense. Outside this primitive process (dimensional integration and differentiation imposed upon the same region, which constitutes an object), all exists in the Omega nothingness void, without frame or form.

Ultimate reality (specifically, action) is dimensionless in the objective sense; for the objective sense exists only after an operation has been imposed. A quantum itself is lengthless (and has no exclusive energy, time, or momentum) until differentiation is imposed upon it. Only after a quantum of action is fissioned does there exist a discrete piece of (change in) length, time, energy, mass, momentum, etc. I have already shown that perception itself can be modeled in terms of action quanta fission and fusion, and that most of the basic laws of physics can be derived from that model. (See my *Quiton/Perception Physics.)* Fission and fusion of action quanta involve orthogonal rotation between orthogonal three-spaces sharing the same fourth dimension (time) in common. The words *change, interact, localize, superpose, operate, move, oscillate, act, cause,* and *determine* are only a few of the words used in physics to conceal the basic occurrence of orthogonal rotation in higher dimensional space.

Finally, it should be stressed that i, the square root of minus one, itself constitutes an orthogonal axis, hence an extraspatial dimension. The addition of this quantity to electromagnetic theory allowed the resolution of formidable problems, and led to the direct formulation of electromagnetic theory. Thus electromagnetic theory already includes higher dimensionality and orthogonal rotation in hyperspace. In that sense, inductance and capacitance are merely vector statements of amounts of rotation, one in a positive direction and the other in a negative direction, toward an orthogonal axis in higher dimensional space.

The forming (beginning and ending) of a three-dimensional spatial object constitutes a time differentiation invoked on four-dimensional Minkowskian space, i.e., the process of observation or detection itself involves

$$\partial/\partial T\,(L^3T) = L^3$$

dimensionally speaking. This process is accomplished by orthogonal rotation, and the very concept of an object that has been observed, detected, or perceived implicitly involves this time differentiation invoked on a four-space.

Velocity also represents a statement of the switching of time into length, and length into time. It is therefore a measure of rotation of the spatial three-dimensional frame, as Einstein pointed out. By this switching (orthogonal rotating, orthogonal flipping) of the chopping of time or beginning and ending of a small piece of time, we create a little delta *T*, just as we do each delta *L* for an object.

But the photon interaction process is monocular. Each photon must attack matter individually, and live or die in the process. Each photon born from matter is also born independently. Thus the primitive observation process is monocular, since it is totally in one-to-one correspondence with photon interaction that is monocular. Thus the observed world is monocular, quantized, discretized. Because of the particular one-to-one correspondence between our primitive concepts and a single interaction, we can conceive the world in no other fashion, unless we change the very basic factor of one-to-one correlation. This in fact has already been done for physics by Everett, whose theory of the universal wave function incorporates multiple simultaneous observation, and hence direct insight beyond the limitations of the monocular correspondence to the photon interaction. My theory does the same thing in the fields of logic and mind.

TWO-SLIT EXPERIMENT

This experiment is fundamental to all of modern physics. Feynman, Nobel prize winner in physics, has stated that no physicist understands this experiment, and that it cannot be explained by any classical means. The reason is that it cannot be monocularly comprehended, i.e., the first three laws of logic cannot explain it. The fourth law can and does.

In the experiment, electrons are emitted from a source and travel past a doubly-slit wall region on their way to a screen. The apparatus is shielded against light. If one believes that the emitted electron is a little three-dimensional particle, much like a tiny baseball, then it should go through one of the slits and not the other. It would then hit the screen at one of the two spots indicated as the expected distribution, with a little scatter from those that chip the edge of the slit a bit. Electrons which do not hit the holes but strike the wall are absorbed.

We do not get this expected pattern. Instead, the pattern is essentially the same as the one we would get if each electron were a wavefront passing through both slits at once. However, each electron still strikes the screen in only one point; the distribution of these points fits the actual distribution pattern shown.

This stunned the physicists. They did not believe it at first, so they set up a photon gun and hit every electron with a photon as it left the emitter source and started over toward the two-slit region. That is, they determined precisely when a little electron was on the way, and the fact that it was like a tiny baseball and in just one


ELECTRON
SOURCE
PHOTON
DOUBLY-SLIT WALL
SCREEN
EXPECTED DISTRIBUTION (WITH PHOTON INTERACTION)
ACTUAL DISTRIBUTION (WITHOUT PHOTON INTERACTION)

NOTE: IF THE ELECTRON IS HIT BY A PHOTON BEFORE IT REACHES THE TWO-SLIT REGION, IT DOES NOT EXHIBIT THE WAVE INTERFERENCE EFFECT, BUT INSTEAD ACTS AS A CLASSICAL OBJECT AND GOES THROUGH ONLY ONE SLIT, YIELDING THE "EXPECTED DISTRIBUTION" PATTERN.

Fig. 7. Two-slit experiment

place. And this time the electron only went through a single slit, and it gave the expected pattern after all. And when the experiment was repeated and only a fraction of the electrons were hit with photons, then a mixture of the two patterns emerged.

It is simple to describe the results mathematically, but no one has understood why things happen as they do in this experiment. The principle of complementarity evades the issue. This principle is simply a monocular statement dealing with one aspect of the problem at a time, with the determined, exclusive, monocular past only. It does not apply to the present or to the future. If we think in terms of the present, then the third law of logic is violated and the fourth law applies. The two states, two-dimensional wave and three-dimensional corpuscular, both exist simultaneously but nonexclusively in the present. Thus in physics terms, the entity becomes nonobjective (nonspatial), probabilistic and undetermined, and this is automatically a wave concept, i.e., since waves are not confined to one place and determined or localized, they may exist in the nonconfined, nonlocalized present.

Note that photon interaction must be excluded whenever the so-called quantum effect is exhibited. If photon interaction is invoked, classical reality emerges. Photon interaction creates classical objectivity. Photon interaction is a time-differentiating operator imposed on L^3T four-space. Specifically, since light carries time, photon emission from an entity strips away T from the L^3T nonobjective entity, converting it to an L^3 or spatial object.

The very concept of an object comes from primitive perception's one-to-one correspondence with photon interaction. After photon interaction, the first three laws of logic apply to an entity. Before photon interaction occurs, the fourth law applies. In the fourth-law state, the time portion of an entity can interact with any number of time portions of other fourth-law entities if the time aspects of all of them coincide.

A free electron born and released at the emitter is four-dimensional *(L^3T)* until it is struck by a photon, after which it is three-dimensional *(L^3)*. When the wavelength of electron and slits is specified, we have actually specified the time interval stripped out of a dEdT quantum in each quantum of fundamental change occurring. Perfect time synchronization accomplishes or constitutes orthogonal rotation. So if the length (width) dimension of each slit is very close to the wavelength of the electron, the time aspects of both slits will interact with the time aspect of the fourth-state electron if all three are brought into time phase simultaneously. If the slits are made much larger, this interaction will not occur.

When the electron interacts with both slits timewise, this will constitute a part of the past history of the electron to all future interactions or interaction possibilities. But since the interaction with the two-slits was not in the past (i.e., selected or determined), then that interaction itself is a part of the present and future probabilities chain. In physics, probabilities propagate forward in time with absolute causality until a monocular selection is made. Thus the fourth-law interaction is propagated forward with absolute causality and significantly affects any future interactions. And apparently vice-versa. John Wheeler has just shown that, in at least one sense, whether or not the emitted particle in the two-slit experiment has interacted with one or both slits can be selected *after it has occurred.* As is well known, the pattern of projection forward of this fourth-law interaction may be quite simply calculated from ordinary trigonometry. For an excellent discussion of the two-slit experiment, see Richard P. Feynman, Robert B. Leighton, and Matthew Sands, *The Feynman Lectures on Physics*, Vol. 1 (Addison-Wesley, Menlo Park, Calif., 1963), pp. 37-1 and 37-12.

When the electron hits the screen, it encounters a region of varying time oscillations of the orbital electrons around the individual atoms comprising the screen. Thus the exact location of the orbital electron in the screen which will first precisely time-synchronize with the electron wavelength approaching the screen in four-law form will vary. Thus the place where the electron hits the screen is variably selected along the screen. The time distribution pattern of the approaching electron is recovered when the time distribution of the number of electron hits per screen length is plotted.

So one can build gadgets to cause four-law entities to multiply and interact simultaneously in time, even though the entities are normally thought of as being in different spatial locations when in the three-law state. And one can deliberately select the type of interaction to occur, four-law or three-law, simply by controlling photon interaction. The two-slit apparatus itself is a paranormal, psychotronic device.

This is the explanation of the two-slit experiment, which, according to Nobel prizewinner Richard Feynman, no one understands and which, according also to Dr. Feynman, contains the total mystery of quantum mechanics and the only mystery of quantum mechanics. The reason the two-slit experiment has not been understood is that the answer to the paradox was not present in the first three laws of logic. It requires the addition of the fourth law to explain the experiment.

And all fundamental particles — photons, neutrons, protons, electrons, etc. — exhibit the same behavior. So things, nothings if you will, can be processed in the multiplistic two-states-identified-as-one-so-no-single-exclusive state, as virtual and unobserved entities. In the multiplistic state they can be amplified, recorded, put onto tape, modulated onto RF signals, etc. And by our ordinary, objective, three-law science nothing is processed. And nothing indeed is what is there — a very special, structured, detailed, virtual set of nonexclusive, hidden-variable nonthings that is part of the new reality existing in the framework of the new four-law logic. In fact, this processable, structurable, nonobjective reality exists outside objective, three-law spacetime and is the basis for all psychotronic phenomena.

To our present monocular detection devices and monocular theory, such multiple-state entities are unobserved and hence are zeroes. They are pure vacuum, pure space, pure nothing, pure emptiness. But they are very real indeed, and they do physically exist, but multiocularly rather than monocularly.

The importance of the time interaction in explaining the two-slit experiment was noted as early as 1957 by Charles Muses in his introduction to Jerome Rothstein's *Communication, Organization, and Science* (Falcon's Wing Press, Indian Hills, Colorado, 1958). Muses pointed out that the celebrated wave-particle paradox remains a paradox only so long as the chronotopological phases of the phenomena are left unrealized in the analysis. The entire foreword by Muses is a remarkable document that analyzes the structure of time itself.

NOTE:

IN REFLECTED LIGHT,
THE EFFECT CAN BE
INVERSED.



SUPPRESSION OF THE PARANORMAL CHANNEL BY THE PHOTON INTERACTION INCREASES IN THIS DIRECTION IN PROPORTION TO THE SPECTRAL LUMINOUS EFFICIENCY

Fig. 8. Photon quenching of the paranormal

PHOTON QUENCHING OF THE PARANORMAL (TIME) CHANNEL

The photon interaction constitutes a time-differentiating operator imposed upon L^3T dimensionally (Minkowskian reality), which results in the creation of L^3 dimensionality (objective, spatial reality). Aristotle's three laws of logical thought are based on primitive observation, which in turn is in one-to-one correspondence to the situation where the photon interaction has been imposed and the time dimension destroyed, resulting in a classical or objective or spatial reality. Hence all our present logic, science, and mathematics are based upon this particular arrangement. As shown by the two-slit experiment, if the photon interaction is not allowed to occur, a fundamental particle refuses to behave in a classical, objective, spatial object manner; instead, it behaves in a nonclassical, nonobjective, wave manner if the time element interacts with it.

Mental phenomena occupy the same time dimension as do physical phenomena; however, the spatial dimensions of mental objects do not ordinarily occupy or intersect the spatial dimensions of physical objects. However, the time dimension is recognized by physics as objective; therefore, since the mind occupies at least one real objective dimension, it is objective rather than subjective. This suggests a model whereby mind is a real L^3T Minkowskian four-space world, but one whose three spatial dimensions lie orthogonal to and outside the ordinary world's three spatial dimensions. The mindworld and the physical world then have in common the same time dimension. Dynamic movements in each world (mind and matter) result in an exceedingly small crosstalk being projected into the other world, a crosstalk so small as to be virtual and normally unmeasurable. Establishing one-to-one coherence between crosstalk from a mindworld constitutes the creation of a biological organism. The crosstalk from the mindworld and a physical structure in the ordinary world to the physical world has previously been labeled *inception* by me, and a mechanism whereby such a minute psychokinetic effect on matter can be amplified to a macroscopically observable level, or even beyond, has been derived. Thus a fundamental mechanism whereby tulpoid activity (projections from the collective unconscious materializing into the ordinary physical world, in a format determined by the collectively higher levels of unconsciousness in the race, national group, culture, subculture, and personal unconsciousnesses) is developed and explained.

Before the intervention of the photon interaction, four-dimensional reality thus has a great deal of tulpoid dither riding upon its time dimension as a minute modulation. The photon interaction invokes a time-differentiating operation, stripping away or suppressing the time dimension, resulting in a spatial reality or objective reality being perceived or observed, and in the process separating mind and body by destroying the only common connection or channel. Because of the time-squelching action of the photon interaction, we do not see time or the mind in our ordinary physical observation. Also, we do not see the incessant stream of tulpoid activity that bathes the time channel.

The time channel is thus the mental channel and the paranormal channel. The photon interaction is the destroyer or squelcher of the paranormal channel. Apparently the squelch effect of light is not linear or constant, but is a variable and a function of the frequency of the light being utilized. From a synthesis of a variety of data in diverse fields, the following hypothesis has been arrived at to fit the experimental evidence: *The quenching of the hyperchannel (the paranormal channel or the time channel) by photon interaction is proportional to the spectral luminous efficiency of the eye of the average human observer in the interval from the infrared to the ultraviolet.* Thus the form of the paranormal squelching effect of the photon interaction is given by the operator ϵ where

$$\epsilon = m \mathrm{E} T$$

and where m is a parameter which varies as some function of frequency. This hypothesis specifies m over the region from the ultraviolet to the infrared. In other regions of the frequency spectrum, the form of m must be determined by experiment.

There are several experiments which fit the hypothesis:

1. The induction of death and disease patterns from test cells to environmentally shielded healthy cells by Soviet scientists.[a]
2. The invoking of specific tulpa living forms and photographing them in the invisible state with infrared film by Trevor James Constable.[b]
3. The visible light revival of appreciable fractions of cells killed with ultraviolet light and kept in the dark — dormant, unreproducing, for up to twenty-four hours.
4. Ingo Swann's precise differentiation of the visible light spectrum (frequency region) where psychic seeing (similar to remote viewing) is blacked out.
5. The Fox and Miller experiments, in which cell-like protein forms that reproduce (i.e. are "living") are generated when a primeval soup in the laboratory is bathed in ultraviolet light and exposed to strong electrical spark discharge (strong bioenergy collections).

A corollary to this hypothesis is that, under certain conditions, reflected light may reverse the effect. Thus the effect of the full moon, which reflects a great deal of sunlight, can immediately be appreciated. The effect is to the time channel, hence stimulation of this channel stimulates the mental effects. The effects of the full moon on romantics, lunacy, and deeper life functions controlled by the unconscious is grounded in a factual basis.

Thus there is a very good reason why animal eyes tend to operate very closely to the infrared, visible light, ultraviolet region, with the eye usually adapted for the visible light region. In the infrared and ultraviolet regions, tulpoid phenomena would be readily visible or detectable, and an animal whose eye operated exclusively in one or the other of those areas would so often be distracted by the mental tulpoidal activity that it would prove disadvantageous to his survival against animal predators operating in the strongly squelched, visible light region. By the same token, animals whose eye operates further into the infrared or the ultraviolet than does the human eye are notoriously sensitive to paranormal phenomena before their manifestation to human observers.

The stimulating effect of reflected light, and particularly of light reflected from the surface of a planet or of the moon, also concerns several of the common practices of UFO investigators. It is common practice to dispose of a sighting once it becomes apparent that a planet lay in the direction of the sighting and was particularly bright at the time. However, such an optical condition can in fact serve as an initiation point for tulpoid activity to enter the ordinary reality frame. And in fact such conditions — and conditions when stars are very bright and twinkly in their reflections from the particles of the atmosphere — are conducive to UFO appearances, and this should be realized and taken into account. UFO's in a great many cases will be observed to start or come into being from such appearances.

---

[a] V.P. Kaznacheyev et al., "Distant intercellular interactions in a system of two tissue cultures," *Psychoenergelic Systems,* Vol. 1, No. 3, March 1976, pp. 141-42.

———, "Apparent information transfer between two groups of cells," *Psychoenergetic Systems,* Vol. 1, No. 1, December 1974, p. 37.

[b] Trevor James Constable, *The Cosmic Pulse of Life* (Merlin Press, Santa Ana, Calif.)

If we realize that the paranormal channel is the time channel, then the fundamental two-slit experiment of physics is itself a paranormal manifestation experiment. Thus when the photon interaction is invoked, a classical object and classical behavior result. When the photon interaction is not invoked, a nonclassical entity and nonclassical behavior result. The more interest is taken in a particular tulpoidal manifestation, the more the format is impressed in multiple minds and multiple unconsciousness layers and the more frequently the format is tuned in. Eventually a repeatedly tuned tulpa can become stable and permanent. Candidates for such tulpoids presently on their way to being stabilized are the Loch Ness monster and the sasquatch. Particle physicists may in fact be creating their own reality by the same process, as suggested by Josephson.

The process whereby visible light revives cells killed by ultraviolet light is presently considered under the term "photoreversal." It is a moot point whether cells are living if they have laid dormant for several hours or even twenty-four hours without any cell divisions having occurred. The effect of a given dosage of ultraviolet radiation on cells is known to be greater when the radiation is flashed than when the radiation is continuous. This has been interpreted as due to a thermal reaction following a primary photochemical reaction, since increasing the temperature accentuates the effect of flashing. However, I suggest that flashing is directly related to the effect known as kindling, where, when the limbic structures of the brain are repetitively stimulated, the entire nervous system of the organism responds and goes into resonance (seizure). Soviet experiments have shown that such flashing of a telepathic sender enhances the reception of telepathic information. In the 1920's and 1930's A.G. Gurvich and his students found that a yeast detector's threshold of sensitivity to mercury lamp radiation was about three orders of magnitude higher than the detector's threshold of sensitivity to radiation of the same spectrum from biological material. (For a description of more modern work which may show a violation of the conservation of energy law, see L.L. Regelson, "A Paradox of Mitogenetic Radiation," edited by H.S. Dakin, translation available from H.S. Dakin, 3101 Washington Street, San Francisco, CA 94115.) Regelson's experimental results point to the conclusion that the paradox observed with the mitogenetic radiation experiments is a universal physical phenomenon. In view of this and Kaznacheyev's results, the entire area strongly warrants intensive investigation. Regelson's group was actually attempting to find a new solution to the problem of wave-particle duality, strikingly parallel to my interest in the area.

Those frequency points where the quenching effect is minimized (i.e., where € goes through a minimum value) are referred to as "magic windows" or "magic windows between worlds." Acker and Tiller have called them "interdimensional nodal points." In the magic windows, energy from one frame or biofield can be more easily collected to orthorotate into another frame or biofield, since the rotational threshold is much lower. There is a window, e.g., between 38,000-40,000


PHOTON INTERACTION CREATES OBJECTIVE AND NONOBJECTIVE
NUCLEAR FISSION MODEL
NUCLEUS
NEUTRON
COMPOUND NUCLEUS
FISSION FRAGMENT
FISSION FRAGMENT
PHYSICAL CHANGE MODEL
L_1^3
MASS (M_1)
$L^2 \Delta T_1$
PHOTON
$L^3 \Delta T_1$
COMPOUND UNION → SPACETIME
$(M \Delta T_1)$
$L^2 \Delta T_2$
PHOTON
L_2^3
MASS (M_2)
VIRTUAL STATE DISCONNECTED
VIRTUAL STATE CONNECTED
VIRTUAL STATE DISCONNECTED
THREE LAWS APPLY
FOURTH DOES NOT
FOURTH LAW OF LOGIC APPLIES
FIRST THREE LAWS DO NOT
THREE LAWS APPLY
FOURTH DOES NOT

Fig. 9. Raindrop model of quantized change

Hertz, which can be stimulated with ultrasonics or electromagnetic radiation. The ultraviolet region contains a window, as does the infrared region. Many other windows apparently exist.

Trevor James Constable photographs paranormal phenomena through a filter that is open in the IR and UV regions, but opaque to visible light. Thus the filter blocks out the strong quenching effect of visible light and looks in two magic windows, IR and UV. Constable is thus able to photograph phenomena that are not normally detectable.

RAINDROP MODEL OF QUANTIZED CHANGE

What does not appear to have been realized to date in physics is that the photon interaction is the agent that creates objectivity itself, as is clearly established by the two-slit experiment. The photon interaction separates spacetime into space and time exclusively. An object, being something which occupies space (L^3), is thus timeless. Objects do not exist in time, because the union of an object with time constitutes spacetime, which cannot be perceived, detected, or observed.

Only changes in (derivatives of) spacetime can be perceived, detected, or observed, but not spacetime itself. That with which light has not interacted is not objective. This is proven conclusively by the two-slit experiment, upon which all of quantum mechanics rests. In that experiment, if an electron emitted from the cathode and on its way to the two-slit region does not interact with light, the electron behaves in a totally nonobjective manner, appearing to pass through both slits at the same time. (Actually it goes around both spatial slits in time, and since both of the slits occupy the same piece of time, the electron can interact timewise with both of them.)

On the other hand, if the electron is struck by a photon before it reaches the two-slit region, it becomes a "hard, solid little baseball" and quite objective. In that case it can interact with (go through) only one spatial hole because it cannot interact in time. According to Feynman, this simple experiment contains the total and only mystery of quantum mechanics. Furthermore, it cannot be explained in any classical manner. No physicist in the world understands it, although the pattern of repeated electron strikes on a collecting screen is quite easy to compute by simple trigonometry.

Let me now explain what happens to a mass when it is struck by a photon, absorbs the photon, and re-emits the photon. First, a mass is an L^3 object; the concept of mass is not a function of time, but only a function of space. It is thus three-dimensional. The photon is also three-dimensional, but one of its dimensions is the time dimension. The photon, being built of action, is constituted of $(dEdT)$ or (L^2dT) dimensionally.

When the photon strikes the mass and is absorbed, the (AE) portion is turned into mass by orthorotating one turn and becoming L^3 dimensionally. The (dT) portion is thus united with the spatial mass to give a compound nucleus of spacetime comprised of MdT_1 This compound nucleus of spacetime is not perceivable. When a photon is re-emitted, it may or may not be of the same frequency and energy as the previously absorbed photon, depending on the absence or presence of any other perturbations. At any rate, a small bit of L^3 spatial mass is orthorotated to give an L^2 intersection with the laboratory frame, which turns the bit of mass into a small piece of energy, d*E*. In the orthorotation, a small piece of time is bitten off and joined to the d*E* to give a $dEdT = h$ quantum of action, which now constitutes a photon. Photon emission thus strips away the time dimension, leaving a spatial object.

Einstein pointed out that the velocity of an object may be visualized as rotation of the object in higher dimensional space. Visualized as spatial rotation rather than rotation toward the time axis, the velocity of light in vacuum *c* merely constitutes the rotation of a piece of mass by an angle of 90° to the line of motion, in the laboratory space in which we visualize the photon (the rotated piece of mass) as moving. Thus the photon emitted from the mass is moving at *c*, the velocity of light, because of its orthogonal rotation to the laboratory frame.

Note that the spacetime compound nucleus has now once again been separated into spatial and time components. Time is moving with the photon. And that is why time moves or flows at *c*, the speed of light in a vacuum. Time is carried only by the photon, and photon interaction with an object produces that object's march through time. If the emitted photon and the previously absorbed photons do not have identical d*E* and d*T* components, then M_2 will be different from M_1, and the mass will have increased or decreased. Considering the photon to consist of momentum and length components, i.e., *(dpdL)*, a similar diagram can be constructed. In that case, if the momentum and length components of the emitted and absorbed photons are identical, then M_1 and M_2 occupy the same position (M_1 has not moved). If these components are different, then the mass M_2 will occupy a slightly different position than mass M_1, and the mass will have moved.

This, by the way, is the simple solution to the age-old philosophical problem of change. We simply identify M_1 and M_2, calling them the same object. We cannot detect, perceive, or observe the compound nucleus of spacetime in the middle. Thus we experience change as a thing becoming something else, but still being the same thing. This totally defeats the first three laws of logic. However, fortunately we can easily comprehend it since we have developed the fourth law of logic.

The raindrop model of quantized change is taken exactly analogous to the raindrop model of nuclear fission, as shown in Figure 9.

KINDLING EFFECT

G.V. Goddard and his associates in 1969 reported a peculiar kindling effect generated by repeated, periodic, low-intensity stimulation of the limbic region of mammaliam brains. A sustained periodic signal input to the brain and central nervous system eventually sets up a cumulative resonance which increases in magnitude until the entire organism is in sympathetic resonance.

A laboratory rat at first continues to explore its environment in a normal manner when it is subjected to kindling. But after repeated stimulation at the same intensity, the rat will begin to rear up and its forelimbs will convulse. Eventually these bursts of electrical activity induce similar patterns in nearby brain regions, and the threshold becomes progressively lowered. Stimulation progresses to the amygdala, to the amygdala on the other side of the brain, to the hippocampus, to the occipital cortex, and finally to the frontal cortex. Kindling can start only in the limbic structures.

While kindling was originally thought to be a model of epilepsy, John Gaito of York University has reported that a different mechanism is apparently involved since the amino acid, taurine, which suppresses epileptic seizures in laboratory animals, does not prevent phenomena caused by kindling. Also, kindling apparently causes permanent changes in the neural circuitry. Pulsed repetitions of telepathic senders have also been shown to increase the reception of telepathic messages. Thus the kindling effect apparently applies to the paranormal channel as well as to more orthodox transmission channels. (For further details, see "Kindling, once epilepsy model, may relate to kundalini," *Brain/Mind Bulletin*, Vol. 2, No. 7, February 21, 1977; pp. 1-2.)

The kindling mechanism is a far more general mechanism than epilepsy researchers have realized. Coherent time collection of bioenergy in one bioframe "kindles" toward the threshold of the next bioframe, which has a fixed threshold. When sufficient kindling occurs to reach the threshold, automatic orthogonal rotation of the kindled bioenergy occurs into the next frame. There it simply constitutes the kindling or superposition of the imperceivable subquantum state into the perceivable quantum state. This is the mechanism whereby one kind of field can be turned into another. E.g., thought energy (third biofield) can be kindled into second biofield (flux), which can be kindled into first biofield (electromagnetic energy), which can be kindled into zeroth biofield (matter).

BIOENERGY COLLECTORS

Good collector mechanisms exist in great variety, in both living and inert systems. Many good collector mechanisms exist in the human body. One mechanism that collects bioenergy and orthorotates it into ordinary electrical field with appropriate induced currents is simply the electrical current in the human nervous system. This is particularly true of the current discharges from and between the nerve endings.

Another collector for bioenergy in a living system is the mitogenic radiation between the cells in tissue. Taken as a flux, this mitogenic radiation would seem to have both a photon nature and a nonphoton nature. The cells, in their membranes and fibrous internal structures, are continually collecting and kindling bioenergy into electron currents and photons. The electron currents represent collections from the virtual state into observable state, and may in one sense be regarded as the lifting of electrons out of the Dirac sea by direct kindling (coherent superposition of virtual state energy into observable state energy). These kindled currents are thus superpositions or modulations on the ordinary electrical activity of the cells, fibers, and membranes. The mitogenic photons are also produced by direct kindling of the virtual state into observable state, in this case, by kindling virtual state photons into observable state photons.

Spark discharges, such as are used in Kirlian photography, are extremely good collectors of bioenergy. In Kirlian photography the film records ordinary photon interactions; however, the spark discharge from the finger is collecting and kindling bioenergy into ordinary electrical energy (specifically, into electromagnetic field, which then affects the electrical flux pattern). Also, bioenergy is being collected and kindled into ordinary photons, thus changing the photon pattern being emitted.

Furthermore, those photons being emitted are internally affected by the bioenergy that has not yet kindled to observable state electromagnetic energy, but is still virtual. Each photon carries the virtual state along in the little piece of time contained in the photon, and partially collected bioenergy which has not yet breached the threshold of observable photons is being carried in each emitted photon. These patterns are transferred to the grain atoms by photon absorption when the piece of time of the photon is momentarily added to the mass of the absorbing atom, and in turn are continually spread through the emulsion material atoms by the virtual photon fluxes of the charges, in both the nucleus and the orbital electrons of the atoms.

So the life pattern of a photographed object is captured on ordinary film — and indeed that pattern can be resonated through hyperspace with the object that was photographed, regardless of where the object is in the universe.

Note that there are many mechanisms inside stars and planets for the collection of bioenergy. We live in a vital, pulsing, living, breathing, bioenergetic cosmos, and life is everywhere. Patterns of life are riding in the light from the distant stars, from our sun, in the neutrino flux from the cosmos, in the graviton flux from the cosmos, in cosmic rays, etc. And so it is small wonder that living cells that form, reproduce themselves, and die can be induced in the proper primordial soup of nutrients when that soup of matrix forms and chemicals is bathed in ultraviolet light (one of the magic windows which contains a greatly enhanced transmission factor for bioenergy, hyperspatial energy, life energy), and stimulated by electrical spark discharges.

It would be interesting to perform the same type of experiments with concentrated light from distant stars, or with the mitogenic radiation from cell cultures, using environmentally shielded setups similar to those used by the Soviets in experiments with the transmission of death patterns.

Even stranger, bioenergy propagates along deBroglie waves, and so all possibilities are modulated by bioenergetic kindling and collection. Viewed in this light, Puthoff and Targ's remote viewing experiments actually provided a multitude of probability paths to the viewer, and these probability paths were indeed kindling bioenergy of the distant, as yet unhappened event. The actual event in the future contains a great many additional collection kindlings due to the additional factors involved in determination (such as collapse of the wave function). A peaking of signal exists on the more probable happenings, and this extra signal along certain paths constitutes an increased signal-to-noise ratio in that particular channel. Thus an actual mechanism exists for seeing at a distance and for seeing ahead in time.

Particular note should be made of the pi meson collection mechanism in the nucleus of an atom. Each neutron and each proton in the nucleus of an atom is continually emitting and absorbing pi mesons, and thereby the protons and neutrons are continually interchanging from one to the other by passing along the positive charge. This activity produces the strong force which binds the nucleus together against the electrical repulsion of the electric forces due to the positive charges of the protons. The fantastic structurings and currents that result provide an electrical current which can and does collect bioenergy. A skilled psychic with good psychokinetic ability can thus focus on the kindling mechanism inside the nucleus and get a signal-to-noise increase of the kindling of his bioenergy in nuclei as opposed to elsewhere in the material in other collection mechanisms. Several types of reactions can then occur. The protons may have their electric charges extinguished due to the extinguishing of the virtual photons producing the electric field on their pions. In such case, the atom simply loses its integrity, and some neutrons and photons are emitted from the atomic site into the surrounding material. This type of interaction thus locally softens a metal and produces severe heating in localized areas, changes in fundamental grain structure, and changes in fundamental characteristics of the metal.

It is by this mechanism and similar related reactions that metal bending can be and is accomplished by persons such as Uri Geller. The collection of bioenergy by graviton emission, absorption, and flux leads to antigravity and other psychokinetic effects. These are exhibited in rare levitation phenomena and more frequent poltergeist phenomena.

The list of collectors could be materially increased, but these should suffice to show the importance of the effect of coherent time collection, kindling, and orthorotation of one type of field into another. The collection of deBroglie waves is moving much faster than light, and for very slowmoving objects the collected and projected bioenergy on their deBroglie waves is moving at essentially infinite velocity. This accounts for the fact that Hieronymus observed an instantaneous cutoff of his monitoring signals from the Apollo astronauts when their space vehicle went behind the edge of the moon.

Looking over the list of collectors and carriers, it is obvious why even the best Farraday shields cannot shield out bioenergy communication. The deBroglie wave carrier alone will simply take the bioenergy right through any known substance — or more precisely, it will take the bioenergy around the three-space in which the barrier substance exists, since deBroglie waves are actually superluminal particles in a three-space more than one orthogonal turn away from the observer's three-space. The implications for psychic healing and psychic surgery are obvious.

PSYCHOMETRIC EFFECT

Every mass communicates with every other mass in the total universe, with hyperspatial/virtual crosstalk between all parts and all masses. This yields a mechanism for psychometry.

Inside the mass, we have a large number of collector mechanisms, of the types previously listed and explained. All objects in the universe are in communication with this object, particularly large or close objects. Those objects that come very near or touch the chosen object for a period of time are most influential.

Briefly, the internal dynamic collector mechanisms of the chosen object perform collection and kindling of the virtual state; thus each mechanism is slowly changed by the influence of other objects in the universe. This is very like the diffusion of heat. The chosen object also communicates part of the influx away, normally reaching an equilibrium with its surroundings when these surroundings are stable. As the surroundings change, appropriate changes are communicated into the internal collector mechanisms of the chosen object, and appropriately diffused away to other parts of the universe, until equilibrium is again reached.

Note that the influence of nearby or touching objects is greater than the influence of distant objects under normal spatial considerations. In hyperspatial considerations, however, this is not necessarily true at all, since this chosen object's pattern may be tuned in through hyperspace without any loss of energy due to ordinary three-space separation distance. In the absence of such hyperspatial tuning, distance is a factor, and close objects have a greater signal-to-noise ratio in the collection and kindling than do more distant objects.

Thus an individual or group of individuals in the vicinity exert mental, emotional, and bioenergetic influence on the kindling being accomplished in the chosen object. The stabilized dynamic patterns of the localized chosen object thus are conditioned and kindled to contain patterns of the actions, feelings, and thoughts of the individuals around it, as well as the natural events that occur. It is thus a very exact record of its surrounding events.

A psychically sensitive person who touches the chosen object, or in some cases merely comes near it, enters into a communications exchange with it. His body-records diffuse into the local object, and those of the local object diffuse into his body. If the psychic is sensitive enough, he can gain impressions from the recorded events of the object. This is the scientific basis of psychometry.

A wide variety of data support this mechanism. Psychometry has been practiced since earliest times, and is still practiced today. A photograph is particularly indicative of the person photographed, since his entire record is imprinted psychometrically on the photograph.

Moreover, the entire record of the Earth is still in the earth, in all its detail. As indeed is the record of each star and its planets, riding on the light that reaches us from that star, and on the deBroglie waves from it. With operational biodetectors, we could easily read the records of the universe. NASA would do well to pursue this alternative in its attempt to contact extraterrestrial life, rather than point huge radiotelescopes toward the heavens and listen to the kindled static from the stars. The static indeed contains the message, but not in a format in which they are prepared to look! It is in the virtual state, riding in each photon.

To a psychic who can see the human aura easily, the condition and much of the record of the person is in that aura, because the auric pattern is changed by all experience of the body, mind, and personality. Thus a good healer can see the aura of the patient, tell if another healer has been in contact with the patient (including often recognizing which other healer it was), and can recognize his own previous contact with the patient many years earlier. (See, for example, the story of Agpaoa as recorded by Sigrun Seutemann in *Healers and the Healing Process,* ed. George W. Meek, Theosophical Publishing House, 1977, p. 93.)

ALL MASS IS CHARGED:
EVERYTHING IS ELECTRICAL

It is well known that all mass is charged; thus everything in one sense is electricity. To examine this concept, let us look again at the electron with its virtual photons being emitted and absorbed, which virtual activity creates the electric field of the electron. In classical theory the electron is visualized as if it were a little hard


VIRTUAL PHOTONS
(-)
(+)
ELECTRON
PROTON


+
PROTON
NEUTRON
NEUTRON
PROTON
+

IN A NUCLEUS, EVEN A NEUTRON IS CONTINUALLY CHANGING INTO A PROTON, AND VICE VERSA, BY THE EXCHANGE OF THE POSITIVE CHARGE.

Fig. 10. All mass is charged: everything is electrical

spinning sphere; the spinning of its electric field then generates a magnetic component. This concept of spin is retained, even though the electron is no longer regarded simply as a little baseball.

From our viewpoint, the electric field constitutes a steady activity of the emission and absorption of virtual photons, and the electron spin is more of an implosion or explosion in higher dimensional space. That is, we visualize a fundamental stable particle as a precise closure of the entire physical universe, like the Einstein spherical model of the cosmos. Furthermore, we visualize multiple closure; first, a very gradual macroscopic closure gives the so-called gravitational closure of the Einstein spherical model, and a closure — in the case of an electron — of about 10^{42} times as quick and small gives the charge closure. This second closure is considered to be at right angles to the first. In one direction the second closure gives a negative charge, and in the opposite direction the second closure gives a positive charge.

So in this view, spin is occurring in at least four spatial dimensions, not just three. It is more of an implosion or explosion into and out of this three-space universe frame. From such a model, we could expect that some startling physical phenomena might be possible. For example, we might visualize the implosive or explosive spin as similar to a vector flux. If these vectors are not precisely antiparallel when two like charged particles meet, then a resultant flux vector exists. Since spin is actually the quantity action (energy x time, or momentum x length, or mass x time), then the existence of a vector resultant means that enough action can exist to provide a quantum to be fissioned, which yields (creates) physical change. Thus such a resultant allows a collision or interaction to occur. On the other hand, if two like charged particles meet and their spins are precisely antiparallel, then no vector resultant flux exists. Hence no effective action exists to be fissioned and create physical change (collision or interaction). Thus two like charged particles with precisely antiparallel spin ought to run right through each other when they meet, with no interaction at all, electrical or otherwise, in complete contradiction to conventional collision theory and conventional electrical theory which states that like charges repel one another.

Such an experiment has been done, at Argonne National Laboratory, with colliding protons. When the colliding protons have antiparallel spins, they do indeed pass right through one another. And there dies forever the old idea of concrete, solid, material reality. The experiment is not predictable or permitted by present electromagnetic theory or conceptual models of the proton and proton interaction. The experiment is consistent with our dual closure holographic model of the universe, however, and is in fact predicted by it.

In a nucleus, we find both protons and neutrons (except for a single isotope of hydrogen, which contains only a single proton in its nucleus). However, these nucleons do not exactly maintain their exclusivity. Instead, a proton is continually changing into a neutron and vice versa; this metamorphosis is accomplished (in theory) by the continual exchange of a small particle of mass containing the positive charge. Thus a highly dynamic type of electrical current activity is going on in the nucleus. And in fact, this is the only way a neutron can be stabilized in ordinary matter; when freed from the nucleus, the neutron is unstable and decays in about eleven seconds or so. So even a neutron is continually changing into a positive particle, i.e., into electricity, when it is in the nucleus of an atom. And around the nucleus, the electrons are in dynamic orbit, so highly dynamic electrical activity is going on in the outer part of an atom and also in the inner part. Thus indeed all mass is charged and everything macroscopic is electrical. And every physical change of a charged particle constitutes a modulation imposed upon its virtual photonic activity creating its electromagnetic field. These modulations are simply coherently collected to breach the threshold of the virtual (third) orthoframe, passing into the second orthoframe, then breaching the threshold of that frame, and passing into the first orthoframe, which is the frame of the electromagnetic field. The electric field is coupled by the dual closure mechanism to the gravitational field, and also to the mass. The entire mechanism constitutes the coupling of the virtual state reality to observable state reality, and the electromagnetic field plays a prominent part in this coupling. Psychotronics is nothing but the extrapolation of this mechanism and the formulation of a theory to allow the construction of practical devices based upon it. Put simply, psychotronics is *virtual state engineering.*

A FUNNY THING ABOUT ELECTROMAGNETIC FIELD

According to the present theory of physics, the electric field is due to the continual emission and reabsorption of virtual photons. Let us examine that concept just a little further, because there are some interesting conclusions we can make if we are not afraid to take the final conceptual step to the bottom line implications.

First, each ordinary (observable) photon in the universe consists of a little piece (quantum) of nonobservable action. The units of action are energy times time, or ML^2/T {*mass* x length x length/time). The quantum of action in the photon is not separated into a separate piece of time and a separate piece of energy. And also, the quantum of action is a fixed, constant size or magnitude, given by Planck's constant h as

$$h = 6.626 \times 10^{-34} \text{ Joule-second}$$

All this says is that an ordinary photon has a certain size that is quite fixed, and it is made of the substance "action" which is totally nonperceivable and nonobservable. Only changes in action are perceivable, observable, or detectable, never fundamental action itself. So physics already prescribes a universe made out of action, and that universe has no length, no time, no energy, no space, no concrete existence. Yet from it can be taken — by differentiation (which is simply separation) — any length, any time, any energy.

However, only a single quantum at a time changes or is separated. Quanta do not superpose. A single quantum can be split or fissioned into, say, a piece of energy and a piece of time. We can get as large or as small a piece of energy (i.e., change in energy) as we wish simply by adjusting the piece of time accordingly. The same type of separation is possible for momentum and length.

The fragments of the action quantum (say, a piece of energy and a piece of time) must then be stuck back together again (i.e., fused back into an action quantum) to get rid of them, and this particular part of the process has essentially been ignored by physicists. Anyhow, getting rid of the fragments (which gave us a piece of comparative physical change — energy versus time or momentum versus length) causes the just-completed physical change to vanish.

So at its most fundamental level, the entire universe is continually being created and then destroyed in sequence. The continual creation of a tiny piece of time and then the destruction of the piece of time makes us experience reality or change as if we were a pointer moving along a time line. We cannot see time because it is continually being destroyed by the change process, the very process of physical detection or observation itself.

Now if we invoke another kind of change, a virtual change, such that its size is always smaller than the actual quantum's size, then this kind of change cannot be detected, even theoretically. The concept of a virtual change is one such that the quantity of action that was changed was deliberately made smaller than the size required to throw the switch of detectable or observable change.

So if we have a virtual photon, it is simply a piece of action whose magnitude is always less than h. Here again, we can still get any amount of energy change we desire, merely by adjusting the size of the piece of time associated with that energy. This then means that the virtual photon is not big enough to breach the threshold of quantum change, and so cannot be observed or detected.

And here is the interesting bottom line ignored by most physicists and almost all the pragmatic scientists who run the orthodox establishments. The totally unobservable, undetectable virtual photons being emitted and absorbed are conceived as creating the electric field at the same time as observable physical change (ordinary quantum change) occurs. And the electric field, of course, can cause or induce change of sufficient magnitude to breach the quantum threshold and result in observable change. The bottom line is this: the virtual state can be collated and collected to sufficient magnitude to breach the quantum threshold and induce ordinary observable physical change. The electromagnetic field already does precisely this! And if reality can behave this way, as the physicists show, then let us simply accept that and apply it!

Note that we have now resolved the problem of negative time. The fusion process replaces the little positive piece of time that was formed in the fission process. A continual stream of such replacements constitutes a continual stream of subtractions of positive time. Hence this represents a negative time operational channel. Many of the equations of physics, e.g., Maxwell's equations of the electromagnetic field, should be reexamined with a view to this negative time operation. Dirac calculated such an entity, an electron traveling backwards in time, and noted that it would appear as a positively charged electron traveling forward in time. He thus predicted the positron which was later found in laboratory experiments. But of even more fundamental importance is that every piece of charged matter in the universe has such an opposite twin — the well known antimatter concept. So antimatter protons, neutrons, molecules, and physical structures exist. Indeed, this physical reality that we normally perceive has its antimatter twin which we are also unraveling backwards as we go. But here again the bottom line is far reaching: it means that we can coherently collect the virtual state to produce matter or its antimatter, which after all are nothing but macroscopic assemblages of quantum changes, and we can thus get free energy, materialization and dematerialization, teleportation, and antigravity by means of special modifications and developments of electromagnetic circuits. Each photon carries a small piece of time. And the entire virtual state reality is hanging onto that small piece of time as a modulation. That is where the probabilities are riding, in terms of the ordinary monocular interpretation of quantum mechanics, all of these probabilities, and all possibilities, are concretely real and occupy orthogonal universes. Since they all share the same single time dimension, there is a time bridge or time channel connecting the universes. Each move or change in one of them crosstalks a tiny bit into each of the others. Since it is the photon which carries them, then each photon contains all possibilities and virtual states modulated upon itself. Photon interaction thus involves the communication of these possibilities and virtual states to the object with which the interaction occurs.

EXTINGUISHING ELECTRICAL CURRENTS

With psychotronics, it is quite possible to extinguish electrical currents flowing in a circuit, or in the nervous system of a biological organism. First, an electromagnetic carrier (photon) is used to carry the psychotronic modulation pattern which will quench electrical currents. The particular psychotronic pattern is modulated upon each individual photon, in virtual state form riding upon the time component of the photon. This is totally different from the ordinary scheme of modulating an electromagnetic carrier; the normal scheme merely gates the rate of passage of photons (amplitude modulation), or changes the energy-time ratio on various photons as photons continually are emitted (frequency modulation).

In this case, virtual state patterns (probabilities) are added directly to each photon, in addition to whatever is done under the normal scheme of modulation. Thus the carrier can be electrically very complex or very simple. At any rate, the carrier with its psychotronic modulations reaches the target, and photons are absorbed continually and emitted continually by the target. The absorption of the photons and their modulations continually generate compound spacetime MdT nuclei and introduce the virtual state psychotronic modulations onto the mass's electric field, the modulations now riding on the virtual photons that generate that field. When a photon is re-emitted, the compound nucleus is split again, and the dT is carried away by the photon, leaving behind a changed virtual photon state on the non-temporal mass spatially left in between quantum changes.

As time passes, the virtual photons are more and more psychotronically modulated by the kindling effect. Eventually the collection breaches orthoframe thresholds and reaches the electromagnetic field frame, changing the electromagnetic field. If the psychotronic pattern is such as to create a positive charge when sufficiently kindled, the negative electrical charge of the kindled electron is simply absorbed or quenched from within, so to speak. And in this case no ordinary annihilation photons are emitted. Instead, the electron is converted to a neutrino when its electrical field is quenched, and it simply passes rapidly away through matter with no interaction and no damage or heating to that matter. Thus the currents flowing in an electrical circuit or in a biological nervous system can be quenched, without any other damage to the system, and without any pair annihilation radiation being produced.

The UFO phenomena very often demonstrate this effect, and the Soviet Union has long since weaponized it.

A simple way to visualize this process is to imagine the virtual photons of the electron as gradually being quenched. With the virtual photons gone, the electron has lost its charge and its electric field, and is now a neutrino. As a neutrino, it zips through matter with no interaction, and on out into deep space.

This mechanism explains why the electrical circuits of autos, radios, etc. usually are not damaged when they are disrupted by the UFO phenomena. Use of normal mechanisms to change or eliminate the electromagnetic field seriously disrupts the components of the circuits, heating materials, blowing fuses, and melting wires and components. The mechanism described here does none of those things.

The weapon aspects are of course formidable. Small transmitters with the right modulation pattern could be dropped, planted, or fired almost anywhere, and these could be set to disrupt equipment or human nervous systems. Their use in satellites is obvious. Small transmitters of a fixed time-life broadcast duration could be fired behind enemy lines in artillery shells. Tactical missiles could carry hordes of such small transmitters and drop them along the way deep into enemy territory. Essentially everything electrical is vulnerable if radiated long enough for sufficient kindling to occur. Powerful radar beams can be modulated psychotronically to give them effects at a distance, disabling vehicles, communications equipment, and men. Even searchlights can be so modulated. Pavlita's psychotronic generators are known to generate deathdealing effects, because he has demonstrated that they can kill insects, and he has admitted that men can be killed with generators that are large enough.

An even more radical approach is to transmit the desired pattern directly through hyperspace with a hyperspace transmitter, using either a set of triads for focusing at a desired spot in normal space, or using a witness to generate form resonance with the desired target object, much like one tuning fork kindles another of the same tuning into vibration. The witness may be anything that contains the pattern of the target, e.g., a photo or a model. In the case of a living organism, each cell contains the blueprint for the entire organism, so a group of cells from the organism can be used. This applies to plants as well as to animals.

DEATH TRANSMISSION VIA THE PARANORMAL CHANNEL

As an example of the kindling effect and the variability of photon quenching of the paranormal channel, some extremely interesting experiments were performed by V.P. Kaznacheyev et al regarding the paranormal transmission of death. Briefly, two groups of cells were selected from the same cell culture and one sample placed on each side of a window joining two environmentally shielded rooms. The cell cultures were in quartz containers. One cell culture was used as the initiation sample and was subjected to a deadly mechanism — virus, germ, chemical poison, irradiation, ultraviolet rays, etc. The second cell culture was observed, to ascertain any transmitted effects from the culture sample being killed.

When the window was made of ordinary glass, the second sample remained alive and healthy. When the window was made of quartz, the second sample


each cell as it dies emits a uv photon containing the exact virtual pattern of its death.
CELL CULTURE (sample #1)
uv photons
WINDOW
glass: effect not transmitted to 2nd sample
quartz: effect transmitted to 2nd sample after kindling lag time
environmental shielding
VIRUS INFECTION
CHEMICAL POISON
TOXIC IRRADIATION
UV
OTHER
quartz container
CELL CULTURE (sample #2)
quartz container
>5,000 EXPERIMENTS
INSTITUTE OF CLINICAL AND EXPERIMENTAL MEDICINE, NOVOSIBIRSK
INSTITUTE OF AUTOMATION AND ELECTROMETRY, NOVOSIBIRSK

Fig. 11. Death transmission via the paranormal channel

V.P. Kaznacheyev et al, "Distant Intercellular Interactions in a System of Two Tissue Cultures," *Psychoenergetic Systems*, Vol. 1, No. 3, March 1976, pp. 141-142.

sickened and died with the same symptoms as the primary sample. The experiments were done in darkness, and over 5,000 were reported by Kaznacheyev and his colleagues. The onset of induced complementary sickness and death in the second culture followed a reasonable time — say two to four hours — behind sickness and death in the primary culture.

The major transmission difference between window glass and quartz is that quartz transmits both ultraviolet and infrared well, while glass is relatively opaque to ultraviolet and infrared. Both quartz and glass transmit visible light. Thus glass is a suppressor of the paranormal channel, while quartz is not.

By performing the experiment in darkness through a quartz window, the four-law patterns of disease, sickness, or death engendered in the primary sample are not extensively squelched by the photon interaction, and these four-law patterns are transmitted through the quartz window into the second cell culture. Since the genetic patterns of the second culture are the same as those of the first, sympathetic four-state interaction and eventual kindling occur, resulting in the appearance of the effects in the second culture.

It is well known that cells also emit mitogenic radiation, including radiation in the ultraviolet and infrared regions. Since these same regions are not strongly suppressed by the photon interaction, one may hypothesize that paranormal effects may be strongly modulated onto infrared and ultraviolet photon activity, and there is indeed evidence for such an assumption. In 1950, Western researchers found that cells could be killed in darkness with ultraviolet radiation, kept shielded from visible light for twenty-four hours or longer, and then if radiated with visible light the cells would start reviving by hundreds of thousands even though they had been clinically dead.

Specifically, every cell emits mitogenetic radiation in the ultraviolet twice: when it is born and when it dies. The UV photon emitted at death contains the exact virtual state pattern of the condition of the cell at death. The healthy cells are bombarded with death messages from those that are dying, and this diffuses the death pattern throughout the healthy culture, eventually kindling into the same death pattern there.

However, the squelching of the paranormal channel by photon interaction is never complete, or paranormal phenomena could never occur in daylight. Hence paranormal patterns can be modulated even onto visible light, although only extremely weakly. Thus we may speak of the *Q* or sharpness of the paranormal modulation upon photon frequencies; *Q* is extremely low for visible light and may be extremely high for infrared and ultraviolet. In the visible light spectrum, it is probable that extremely large numbers of near-zero strength paranormal patterns are modulated on the light radiation; hence these patterns simply consist of a very weak background noise and the kindling effect does not apply. (The patterns are so random as to be self-cancelling in the kindling effect.)

DISEASE AND DEATH INDUCTION

The base idea here is that an active agent must be involved to disrupt the ordinary healthy pattern of inceptive life functioning. Since life functioning is inceptive, ultimately the bioframes, specifically the first and second, must be distorted or disrupted. The first bioframe is the electromagnetic field and the second bioframe is a psychotronic field. The second bioframe may eventually be revealed as the *neutrino* field, but this is still uncertain at present. At any rate, it is a *virtual state* field. Virtual state patterns of a disease, for example, are carried in each photon emitted by a diseased cell. The life functioning psychotronic components are modulated on the body's electromagnetic components. Thus they have an electromagnetic carrier, which will carry the inceptive life function patterns through the photon squelching effects of emitted photons in the body.

A host agent such as a germ produces an active agent such as a toxin. The chemistry involves the particular compound of the toxin that is disruptive or deadly. But chemistry after all is rigorously based on electrical patterns. These electrical patterns of toxic chemistry contain psychotronic patterns modulated upon them by the germ, and these genetic life functioning patterns are different from those of a human cell. The foreign psychotronic patterns are modulated upon the human body's electromagnetic patterns (currents) and thus reach the cell, where they interact by the fourth law in the cell membrane, being demodulated and introduced to the cell, and orthorotated in the process into electromagnetic signals disruptive to the orderly functioning of the cell. The foreign psychotronic signals also jam the ordinary psychotronic patterns being demodulated by the cell in its inceptive operations from its mind frame or third bioframe. If this jamming is only moderate, the cell sickens; it is only disrupted. If the jamming is severe, the cell dies.

The normal electromagnetic noise bathing the cell from the cosmos and the environment contains random components that largely self-cancel or balance. The modulated random psychotronic modulations of the ordinary background environment behave similarly, and thus the normal background simply constitutes a weak noise flux which does not disrupt the inceptive life functioning. In the experiments of Kaznacheyev and his colleagues, photon squelching was largely restricted, and the psychotronic signals from the dying primary culture could go through the infrared and ultraviolet windows in the quartz as virtual state patterns on the mitogenic UV photons emitted by dying cells, and be introduced directly into the secondary culture. The kindling effect then induced the disease or death pattern after an appropriate time delay. Thus it appears that there is indeed a fundamental mechanism by means of which a disease or death pattern from one cell is introduced into others.

If this is true, then an exciting vista emerges for the treatment of hither-to incurable diseases such as cancer. The psychotronic pattern of the cancer cells in a person's body could simply be recorded, then phase shifted 180 degrees, remodulated upon an RF carrier, and radiated back into the body of the patient to cancel the cancer's signal patterns. Radiation of the body need not be severe at all; even weak radiation will suffice due to the kindling effect. At any rate, the hypothesized mechanism seems worthy of experimentation, and it seems to offer a validation of the practice of radionic treatment of disease.

DYNAMIC THOUGHT CONSTRUCTS: BIOFIELD MECHANISMS

We will discover later that thoughts and thought objects are real, physical objects in their own worldframe domain. As such, thoughts, or thought objects, or thought constructs can be and are quite functional devices in the thought world domain. In that domain, they are as physical as a rock. We will also discover that thought energy can be turned into electromagnetic energy by kindling, and can even be materialized if kindling is of sufficient intensity. As an example, thought energy from negative thoughts continually repeated or held in the mind can cause one to become physically ill. This is a well-known effect, and such an illness is referred to as psychosomatic. However, the mechanism by means of which it is accomplished is not known.

Actually the mechanism is simple: in the minute electrical currents that run through the nervous system, across the cell membranes, through the fibrous content of the cells, and through the cell water structures, virtual state thought energy is continually kindled into weak electrical patterns, which modulate, shape, and affect all the vital processes of the body. Almost all this kindled thought energy is from the content of the unconscious mind. Thus the locked-in contents of our unconscious minds eventually directly affect and change our bodies for either good or bad, depending on the particular content being kindled.

Small wonder that we suddenly acquired a chemical problem some years ago after we were saturated by thousands of hours of pill advertisements on television, which directly implanted the idea that certain chemicals such as pain relievers contain the answer to life's problems, while others such as alcoholic beverages lead to a glamorous, active, exciting life. Not only can such material implant suggestions in the unconscious for association, but it can also directly condition the response that the body itself will exhibit to chemicals and drugs.

It is now fairly well accepted that there exists a cancer personality and a heart attack personality, where the mindset is definitely and causatively involved. And from the Simontons' work, we see that the mind can be effectively used in conjunction with other therapy to reverse cancer, even terminal cancer. But unfortunately, by and large Western medicine continues to rely on mechanics and chemicals. Essentially the patient is viewed as a mechanical apparatus and a chemical factory that is damaged, polluted, or out of sorts, and treatment consists largely of mechanical intervention (such as surgery) or chemical intervention (such as antibiotics). Medicine continues to be a science of the reparation of damage or malfunction. It is the science of disease, not the science of health. I do not advocate abandoning the medical practices that have proven effective. I do advocate the augmentation of such measures by all the mind measures available. In fact, medical science ought to be vigorously pushing forward into fields of psychic healing, psychotronics, radionics, etc.

RADIONICS

In ancient development systems it was well known that the mind itself was a functional device, and that thoughts and thoughtforms could function as devices, influencing and affecting other minds and physical material. It was also understood that the thoughtforms had to be crystal clear and very stable. This demanded a great deal of practice in concentration. Eventually it was found that the stability of a physical form or device could materially assist the mind in maintaining stability. In ancient times many such devices were used: the dowsing rod, the crystal ball, the string-and-weight psychic pendulum, etc.

In the last century it was discovered that electrical devices could be used as tuning assistants. This led to the development of radionics, the name being inspired by the new electricity and magnetism discoveries, and particularly by the discovery of electromagnetic radiation. These radionics devices had a distinct advantage in the degree of precision they achieved in the tuning of the inceptive cyborg (operator's mind linked with the actual device through hyperspace). Ten resistors could be staged to give an otherwise almost unobtainable degree of accuracy and precision to the inceptive tuning. The use of variable resistors allowed rapid change of resistance, and thus rapid change of the overall cyborg tuning, and the ability to scan precisely in hyperspace, say, the emanations from a patient. In the hands of a skilled operator, such a device was often much more accurate than the finest medical test equipment available today, and infinitely cheaper and faster. In addition, such testing and diagnosis added little or no distress to the patient. This weird new radionics presented a formidable threat to the orthodox medical establishment. In the U.S. at least, the dogmatic medical establishment promptly came down hard on this potential threat to its hitherto unchallenged domination in the field of medical treatment. Its inquisition and purge was made easier by the fact that many charlatans also leaped into the lucrative field, having little or no actual diagnostic ability, and prescribing meaningless amulets and placebos for seriously ill patients. Also, the strangeness of radionics, such as the ability to diagnose illness from a drop of blood drawn from a patient thousands of miles away from the diagnostician and the radionics device, alienated many members of the medical profession who sincerely believed that no such diagnosis was possible, and that all such psychic demonstrations were frauds. Furthermore, the results, either diagnosis or treatment, were not usually repeatable by ordinary physicians and investigators since the psychic skill of the operator was directly involved. Organized medicine of course did not recognize the ability of the doctor to mentally or psychically intervene in the patient's illness, and so such practice was regarded as fraudulent and banned by the medical establishment.

The radionics practitioners were hounded into court, prosecuted, and convicted of fraud and of practicing medicine without a license. Several prominent radionics pioneers were actually hounded to death, Wilhelm Reich and Ruth Drown being the two most prominent examples. What could have been a great leap forward in medical science in the U.S., and the beginning of the development of psychotronics, was crushed by the power, ignorance, and bigotry of orthodoxy. To this day U.S. radionics has not recovered, and U.S. radionics practitioners are a rare breed, largely underground, who perform their experiments in suspicious secrecy and have only lately begun cautiously emerging from obscurity. In England and elsewhere, radionics survived and flourished, and today one can legally receive radionics treatment in England.

PSYCHOTRONIC DEVICES: A SIMPLE SPACE (QUITON) AMPLIFIER

It is possible to speak of the smallest piece of nothing, that we will call a "quiton." It does not monocularly appear as a perceived thing. Quitons are pieces of action, in which $dEdT > h/4*pi$. Quitons are virtual entities, and very small ones.

Collection of a sufficient number of quitons results in breaching a threshold, so that a thing results. To superpose quitons (dEdT's) must be of the same magnitude and time coherent.

Thus in any situation involving a particularized nothing, collecting enough pieces of that nothing eventually exhausts the nothing set and reaches its boundary, whereupon it is a thing. This is really not different from collecting all non-dimensional points in a particular sequence and finding we now have a one-dimensional line segment, or collecting all the pieces of spacetime warp in a particular region and discovering that we have now a mass.

A device can easily be constructed to process dual natured or binocular entities (quitons), which are monocularly zeroes, while excluding monocular entities. Thus we can build a space amplifier or quiton amplifier or vacuum amplifier. Two single-state excluders in a series feed or input to an ordinary single-state amplifier or processor in a shielded container. The output is fed into a device which will rotate the dual-state entity or field so that an ordinary field can result. One side or the other of the dual-state output will be exclusively present in three-space.

TYPICAL HIERONYMUS DETECTOR

The Hieronymus device, patented by Thomas G. Hieronymus in 1949, is one such device. It has an optical front end, a prism which passes waves and does not admit particles. So a wave entering the front end will go through the prism and be refracted at an angle that depends on the frequency of the wave. Inside the surrounding box, which acts as a light shield, is a small tuner, a little copper rod attached to a rotatable wheel so that the rod may be moved through the various refractive angles from the prism. The prism is mounted on the box with a thin slit in the wall, so that only a small and narrow field of view exists external to the box. The tuner rod is wired to the input of a three-stage RF amplifier where each stage is separately shielded against light—which is very interesting, because of a similar requirement in the two-slit experimental apparatus if the electron was to act as a wave. The output of the RF amplifier comes out of the box and ends in a flat coil of wire between two parallel plastic plates.


SHIELDING AGAINST EXTRANEOUS LIGHT
SOURCE ELEMENT
REFRACTED ANGLE DEPENDS ON FREQUENCY
COPPER ROD
PLASTIC PLATE
3-STAGE RF AMP (TUBE)
FLAT COIL OF INSULATED WIRE
GLASS PRISM
PIVOT
PLASTIC PLATE

Fig. 12. Typical Hieronymus detector

Coming into the box through the slit in the prism, there can be single-state entities and dual-state entities or quitons. The physicist does not have a good name for a dual-state entity. They used to be called wavicles; today we talk about wave packets. But what after all is a wave packet? It is a three-dimensional bunch of two-dimensional waves! So that is where the physicists have hidden the idea of the dual-state wavicle today.

Only single-state waves and dual-state entities or quitons can pass through the prism and be refracted at an angle dependent upon the frequency. If we then tune the rod into the correct angle of refraction, the refracted quitons hit it, as do the single-state waves if their frequency should happen to coincide with the frequency of the quitons. Now the single-state wave dies when it hits the copper rod; it may chip a single electron or two off a copper crystalline grain, but that is lost in the thermal noise anyway, below the detection threshold of the RF amplifier. The quitons, however, simply say "Oh! Now you want us to act like a corpuscular electron, and go through those wires and conduction paths. That's all right, that is just our right hand side." So the quitons will go through and be amplified, just exactly like ordinary electrons would do. But now it is not electron energy, it is a dual-state analog of energy — let us call it anenergy, for analog of energy. (Hieronymus called it eloptic energy, since it could act as electron flow or as optical waves, but was neither exclusively.) The amplified anenergy will come out in the coil of wire and it will generate field and it is not a magnetic field, and so it cannot be measured on normal laboratory instruments. The simplest way to detect the anenergy fields is to use the human sensory system, because the human body knew about RF energy, frequency modulation, and anenergy long before we had modern electrical and magnetic instruments. (The use of anenergy is illustrated by acupuncture, a very ancient medical system dealing with the fact that a peculiar type of energy-like stuff flows in the body, and in certain points and structures of the body, it can interact with other energies and fields.)

Now if we believe we cannot sense the anenergy fields, then we cannot. We can turn the entire anenergy detection system in the body off with the unconscious mind. The negative psi effect is a well-documented effect in parapsychology. There are goats as well as sheep. Some persons do worse on psi tests than chance would possibly allow. They are the goats. They exhibit the negative psi effect, for unconsciously they want to show you that psi does not work, so they use psi effects to do worse than is possible by chance.

At any rate, the human sensory system can get a tingle from the anenergy field generated by the flat coil of wire in the Hieronymus machine's output. What type of tingle one gets depends upon one's own type of body sensory tuning. It may feel as if the fingers on the plastic plate are in thick syrup. Or as if the plastic plate were vibrating. Or it may feel greasy in a peculiar way. And the negative person does not get a tingle at all.

The Hieronymus machine has been built by many persons, and it works for those who are not negative. It processes entities that exist in the dual-state, or that obey the fourth law of logic. And we can do some almost magical things with these dual-state nonthings, these nothings, if we set our minds to it. This is what psychotronics is all about.

ANOTHER KIND OF HIERONYMUS DEVICE AND THE INCEPTIVE CYBORG EFFECT

If thought constructs are actual operational mechanisms, then there should be other evidence besides psychosomatic illness and the demonstrated ability of the mind to cure certain illnesses. In fact, the Hieronymus device can be used to demonstrate this point.

John Campbell, former noted editor of Analog Magazine, once built an Hieronymus device and tested it successfully. Campbell immediately recognized that present physics could not explain the functioning of the device. In an exchange with Arthur Young, Young suggested to Campbell that it was the mind of the operator that made the device function, and that it was the symbolic form of the device that dynamically functioned to make it work. This appeared particularly significant to Campbell since he had discovered he could make the device work even though disconnected from its power supply.

So Campbell decided to test this thesis. He carefully drew on paper in black India ink a schematic diagram of the amplifier, removed the actual amplifier hardware, and substituted the schematic drawing. To his absolute amazement, the device worked as well for him this way as it had previously. But from our standpoint, such a result is not unexpected and can be readily explained.

First, I should point out quite strongly that Campbell not only was well-qualified technically, but even more important, he had an open and unbiased mind. This of course is quite necessary; the negative psi effect is well known, and the negative person is most certainly not going to allow his mind to operate the Hieronymus machine, just as he will not allow himself to succeed at dowsing, and so on.

Furthermore, in constructing the electrical schema of the amplifier, Campbell was strongly impressing stable thought constructs in his own unconscious, which was fully aware of the function of each part of the drawing. And when he connected that drawing to the rest of the hardware, he understood the function of the connection. He thus built in a thought connection from his thought-form amplifier to the hardware in a cyborg device. It then functioned as well for him as had the actual device. Campbell had proved that mind and matter may be cyborged into operational devices.

Psychic use of a pendulum, a ouija board, a dowsing rod, a crystal ball, and a crystal skull are other examples of the use of inceptive cyborg psychotronic devices, as is the use of radionics equipment of all types. And of course the most outstanding example of an inceptive cyborg where mind and matter are linked into one functional device is a living biological system.

Frances Farrelly, working with Arthur Young, took part in an experiment using an ancient Mexican figurine with a fluted neck. She succeeded in inducing fluted ears in a laboratory mouse. The mouse was exposed to the figurine about three feet away, and the cage or the mouse was connected to the figurine with a wire. Physical objects, such as mice bodies and fluted figurines, are three-dimennional channel tuners for orthorotating mind energies. Given firm initiation by a talented person such as Ms. Farrelly, a selected grouping of tuners can be resonated to collect bioenergy, and kindle it into ordinary energy and then into physical effects.

PROBABILITY: THROW OF A DIE

The fourth law of logic is absolutely indispensable in physics. We use it every day and do not realize it in probability. But what after all is probability? Let us use a very simple example to get at the answer to that question. Let us use the face of a die turned up. How can I model that, before the die is thrown?

Now we can only think by operationalism. To operate and output something is to automatically put it in the past. It's happened, it's gone, the moment you do it. To perceive an object is to put it in the past. To determine it is to put it in the past. To observe it is to put it in the past. There is no observed, perceived, detected, measured, or determined present. That is, there is no separated, exclusive, determined present such as is specified by the first three laws of logic — the fourth law is the present, by the way — but in observational physics which deals with determined, observed past phenomena, there exists no present. The future has not yet been observed, so it also is the unobserved. Only the past therefore is the observed. How then can one ever hope to model the unobserved present or the unobserved future?

If I look at the problem of the die with one face up, it is in the past. When I see it, it is in the past. When I think it, it is in the past. So if all I can observe, think, or perceive is the die in the past, how can I ever model it in the future? It's very simple! If I drive any problem set to its absolute boundary limit, it turns into its own opposite by the fourth law of logic, by the law of the boundary. So how do I do that with this problem of the die?

The problem set is specified by the condition "the perceived die with one face up"; this is the most recent past. Now simply find all the most immediate pasts you can get to meet the condition specified, and gather them all up together, and they then must turn into and comprise precisely the opposite, the immediate future. In this problem set, I can construct and collect six such pasts, each consisting of the perceived die with one face up. So by the fourth law of logic, those six faces up collected together as an ensemble represent the future and in fact are identical to the future. The present, which is simply the boundary between the most immediate past and the most immediate future, was specified by applying the fourth law of logic in the first place: the identity of the most immediate past and the most immediate future, being binocular, is unperceived, but it is the present nonetheless. So that is what probability is — an application of the fourth law of logic, so that the most immediate future can be represented in terms of the most immediate past — and physicists and mathematicians have been doing this ever since they have been doing physics and mathematics.

Without the fourth law of logic, there exists no rigorous logical basis for probability! So the fourth law is a very useful law indeed. We have simply failed to realize that we have been applying it all along.

The ontological problem can also be solved as follows: to state that *"A* is not" is to state that *"A* is" is not; to absent a presented thing is to first present it; to be "not-being" is a clear statement of the problem. By the first three laws of logic, the problem is not soluble. By the fourth law, it is simple since being and not-being can be identified. All distinction between present (being) and absent (not being) can be lost.

NEGATIVE TIME

Negative time does exist and is used in advanced physical theories. Dirac predicted an electron traveling backward in time, which would be observed in positive time as a positive charge traveling forward in time.

The application of negative time to philosophy also allows the solution to the problem of good and evil. In positive time we may consider an act as evil — say the act of a hungry wolf seizing a hapless rabbit and devouring it. In positive time, we might say that to the rabbit the act was evil, and to the hungry wolf the act was good, noticing in the process that good and evil are relative terms, not absolutes. Examining the situation now in negative time, a very strange thing occurs. The remains of the consumed rabbit are regurgitated from the wolfs belly, again creating a living breathing rabbit, and reintroducing hunger into the wolf. Thus the act now is beneficial to the rabbit and detrimental to the wolf.

The point is that Allness or Godness is both sides of every coin, not one side only. Omega Godness exists both backward and forward in time; it must do so if it is to be unlimited, even by time itself.

Thus to such unlimited allness, every act is both good and evil simultaneously. Thus we can understand how a perfect creator could establish and ordain good and evil, for there is a sense in which the two are synonymous.

However, such insight is a very strong dose of medicine, too strong for the average stomach. Most persons never seek the Unlimited Godness; instead, they seek a good facet of Godness that itself moves forward only positively in time. Thus they find a partial image which is limited in and by the flow of time. By such an assumption the biblical phrase "I am Alpha and Omega" is unconsciously translated into "I was Alpha and I will be Omega." Thus orthodox Christianity long ago lost much of the God-insight originally given by the avatar Jesus. Only those few cloistered individuals who still struggle with exegesis grapple with the problem of good and evil. The problem indeed has a solution, but the solution involves negative time, the fourth law of logic, and an unlimited creator.

TIME OSCILLATION, QUANTUM CHANGE, AND MASS

It is well known in physics that almost all physical theory is time-reversible, i.e., the equations hold true whether time is positive or negative.

This is important in the theory of antimatter. A positron (antielectron) may be regarded as an electron traveling backward in time. The destruction of an electron constitutes the creation of a positron, and vice versa, when we are observing in only one kind of time.

However, when we consider monocular quantum change, we realize that time can be modeled as a wave. To have any of the present physical quantities (energy, length, time, and momentum changes), a quantum of action must be isolated and fissioned into fragments. By this process we get a change in any physical quantity. This is fairly well understood in present physics, though not in this exact terminology.

However, what is not recognized in physics is that a disposal operation must be performed to clear away the fragments of one physical change before another can occur. The only way the fragments can be cleared away is to fuse them back into an action atom. Since action itself cannot be perceived (only a change in action can be perceived, not action itself) then fusing the fragments into a quantum removes the fragments.

This fusion operation removes positive time fragments (and other positive fragments) and so can be considered a negative time operation. Thus time can be considered to be an oscillatory wave because of its continual monocular discrete creation and annihilation by the quantum change process.

In fact, time oscillation may be considered to be the fundamental reality, and quantized change its result.

By the complementarity principle, time, being a wave, also must sometimes exhibit a corpuscular nature. (Indeed, all virtual state particles are nested within the structure of time.)

The Soviet work on time generating force thus is of absolutely fundamental importance. What has been released of K'ozyrev's work seems to be intentionally deceptive and of little value. His real work and that of his colleagues appears to have the highest Soviet classification, and none of this material has been released.

In the West, the only person of note who has grasped the fundamental import of time and time oscillations is Charles Muses. As early as 1958, Muses pointed out that there was no mystery in the two-slit experiment if the chronotopological features of the experiment were properly taken into account. Muses also worked out a hypernumber structure of time, but its significance seems to have escaped orthodox physics. Nonetheless, his work has direct technological implications, such as materialization and dematerialization of matter, and offers an approach to the engineering development of actual devices. Since his hypernumber theory of time structure also encompasses consciousness, it represents a union of physics and metaphysics on a common basis, and an approach to the engineering development of psychotronic devices.

Western physicists, then, would be well advised to pursue vigorously the idea of time oscillations, both theoretically and experimentally. And they would also be well advised to examine the hypernumber work of Charles Muses.

Since mind and virtual state occupy the time dimension, the nested structure of time contains the mechanisms for mental-physical interaction and for direct amplification of virtual state into observable state (or for the dissolution of observable state into virtual state).

MASS IS A TIME-DIFFERENTIATION

The most fundamental aspect of the concept of mass is that it occupies space, i.e., that it is three-dimensional. Mass thus is a time differentiation of Minkowskian spacetime L^3T. Applying the fourth law of logic, a thing does that which it is and is that which it does. Thus mass is a time-differentiator.

Because of this, we cannot see time, the fourth dimension, although we can see L^3 length, width, and height. Because we look through and detect with a mass sensory system, the time dimension is lost in the act of looking and detecting, i.e.,

$$d/dT(L^3T) = L^3$$

and we thus see a spatial reality. Physical instruments also have mass and do precisely the same thing. For this reason, ultimately all measurement or detection is spatial rather than spatio-temporal, as is well known in physics.

Note that we do not see or detect total reality, but only a partial differentiation of it. Thus the position of the materialist's view is ironic: in his absolute insistence that reality consists in only what can be seen, touched, felt, or detected and measured with his instruments, he condemns himself to the greatest illusion of all, the notion that the outputs of his physical sensory system and his physical instruments constitute absolute reality. Also, since the only physical dimension shared by mind is time, mind reality is lost in the act of detecting, and hence only phenomena which are totally separated from mind are detected.

By the fourth law of logic, the existence in no mind at all constitutes the existence in each and every mind (nonexclusively). Thus physical phenomena are those phenomena that are processed by every mind. We will see that the fourth law enables us to deal precisely with mental, physical, and paranormal phenomena on that basis (how many minds the phenomena exist in).

REALITY IS LIKE AN OPOSSUM

Reality is like a mother opossum carrying her little baby opossums on her tail, i.e., the entire mental-virtual state is carried along as virtual constructs, nested comfortably in the delta time portions of each photon. In the piece of time that is fissioned out of an action quantum to give observable change, there are a multitude of little pieces of time still attached to subquantum virtual state entities and hanging on, exactly like little baby opossums hanging on to their mother's tail with their own tails.

The world is so built, then, according to physics. And if we include our physical model of mindchanges, every possibility in fact concretely exists in that manner, in the virtual state, timewise hanging into the time dimension of the detected physical world's four-space frame, but spacewise hanging out of the ordinary three-space physical universe of objects. So indeed all possible realities, even the wildest and the most farfetched, exist in the virtual state.

The time channel is thus quite literally the paranormal channel that connects the normal spatial world to an infinity of nonnormal spatial worldframes. Only by the continual destruction of each piece of created time (by fusing it back together with the piece of energy involved, and forming a quantum which is unperceivable) are we able to experience physical reality at all, uncluttered and relatively free from the vast hordes of infinite realities through which the ship of quantum-change physical reality sails.

Since the electromagnetic field represents a collection of this vast array of realities, then by proper selection (i.e., by coherent tuning) of multiple stages we should be able to select a particular virtual reality channel. And indeed so we can. Any scheme for drastically increasing signal-to-noise ratios should be adaptable to such a collection mechanism for the detection of bioenergy.

In another sense, reality is like a television set with an infinite number of reality channels, but only one of which is tuned in at any one time. By adjusting the tuning, however, a different reality, including even different physical laws of nature, may be tuned in.

BIOFIELD CONCEPTS

To understand the hyperframe approach to fields, we must understand the dimensionality of intersections in *n*-dimensional space. The dimensionality of an orthogonal intersection is one less than the dimensionality of the intersector having the lowest dimension. One intersector appears radically different to the other intersector since the second sees only a derivative of the first. It is the total projection of an intersector that is "seen" by that which it intersects.

Hubbard's manifold theory also derives these principles. The "types of reality" that these other objects appear to be will depend on the types of intersections they make with the frame of the observer.

This cannot be stressed too strongly: an observer sees his own frame, and intersections in that frame, nothing else. He does not necessarily see the entire reality of any object, and if an object is in a frame that does not intersect the observer's frame, the observer cannot detect that object at all.

Thus all types of reality are open to reinterpretation in the light of intersecting and nonintersecting frames. And to shift dimensions (increase or decrease), all we need do is add or subtract additional orthogonal intersections.

MASS, FORCE, AND 3-D FRAME ROTATION

It is well known that a moving mass can be considered as existing in a three-dimensional space which is rotated away from the line of motion of the mass as seen in the laboratory frame. Einstein in fact pointed this out.

As the velocity of the object approaches c, the speed of light, the angle of rotation approaches 90°. From the bottom left figure it can be seen that a force in the laboratory frame, applied to the moving mass along its direction of motion in the laboratory frame, only affects the mass in the mass's rotated frame with a projected portion. To the laboratory observer, the mass's resistance to the disturbing force applied seems to have increased; thus to him the inertial mass of the object seems to have increased, i.e., if it is harder to push, its resistance to pushing must have increased.

But in the rotated frame, the object's mass has not increased. The rotated frame effect is *why* the mass of an object increases to one observer but not to the other.

When the rotated frame can be rotated to a full 90°, no force applied by the laboratory observer can accelerate it further, because the applied force has zero projection in the rotated frame where the mass actually is. Thus the mass (resistance to pushing) appears infinite to the laboratory observer, while to the rotated observer it is still exactly the same as it always was. Furthermore, to the rotated observer, **the** force being exerted on the rotated mass is zero.



2 LINES INTERSECT IN A POINT

A LINE AND A PLANE INTERSECT IN A POINT

TWO PLANES INTERSECT IN A LINE

TO PLANE A, SEGMENT B APPEARS AS SEGMENT B'

Fig. 13. Biofield concepts


S'
$\alpha_2 = \pi/2$
$\alpha_1 = \pi/2$
S
S
FORMON
S'
$\alpha_2 = \pi/2$
$\alpha_1 = \pi/2$
S
S''
THIS MAY REPRESENT A QUARK
C
C
M_0c^2
M_0
CLOSURE

π BENDING OF A 3-D FRAME (TWO CASES).

WHY $E = M_0c^2$ IN A CLOSURE (FORMON).

Fig. 14. Rotation of 3-D frames


HYPERSPACE
HYPERSPACE
HYPERSPACE
HYPERSPACE
HYPERSPACE
into L^3
L^3
out of L^3
HYPERSPACE
into L^3
L^3
out of L^3
HYPERSPACE

MASS
A region of
hyperspatial flux
orthorotating in and
out of L^3 3-space.

MASS PARTICLE
The flux does not
"move through" 3-space.
It rotates in and out of
each individual mass particle.

JITTER
Each flux line is not
smooth, but jittered.

Fig. 15. Mass is π-rotation of hyperspatial flux

However, the mass's intersection in the lab frame is now two-dimensional. Since only three-dimensional objects can have mass, the object is massless to the laboratory observer. So here we have a paradox: zero mass is identical to infinite mass. This is perfectly in consonance with the fourth law of logic.

The absence of any single finite mass actually permits two indistinguishable solutions: the absence of any three-dimensional mass at all, and the exclusive presence of more than any finite mass. The two opposites are identical on the boundary case.

Thus a photon has zero mass because it is a two-dimensional object and only three-dimensional objects have mass. A photon also has infinite mass because it cannot be accelerated along its direction of travel. A photon is a perfectly ordinary three-dimensional particle existing in a normal three-space that is one orthogonal turn away from the laboratory three-space.

MASS IS π ROTATION OF HYPERSPATIAL FLUX

In Figure 15, I show that a localized mass is simply the result of orthorotational flux in and out of that localized region. This is a hyperspatial flux, since it actually is flowing or rotating in hyperspace.

This flux is related to the spin of a fundamental particle, and in one sense may be regarded as an extension of the concept of spin, i.e., ordinary spin is simply a derivative subset of hyperspatial spin (orthorotation between orthogonal three-space).

This flux does not move through laboratory three-space, but rotates into and out of it, at and for each fundamental particle of mass in laboratory three-space. As I point out elsewhere, mass itself is nothing but the absolute value summations of action quantum fission and fusion activity in a localized (fundamental particle) spatial region *(Quiton/Perceptron Physics).* Fission and fusion are orthorotations, or hyperflux activities.

Also, if we represent this hyperspatial flux by flux lines (a standard practice in physics), then each line is jittered because of its modulation by many higher-frequency components. This flux and the jitter in it play an important part in paranormal phenomena.

Furthermore, the hyperspace flux can be seen in two other ways: (1) as continual direct coherent collections of virtual subquanta to reach the quantum threshold, breaching it and becoming observable quantum change. Thus it should encompass essentially all hidden variable theories. This is the same mechanism by means of which virtual photons kindle and create electric field and the charge of an electrically charged particle; (2) as continual direct coherent collections of mind virtual state subquanta to reach the quantum threshold, breaching it and turning into observable quantum change (physical phenomena). Thus all matter is totally mind and totally alive — inert matter is just nonpreferentially alive. The resultant flux vector in an inert mass is zero since there exists as much flow out as in, and vice versa. This totally eliminates the classical dichotomy between mind and matter. It also implies that accelerated objects do not have nonpreferential type of life, but in fact have some degree of preferential life, since fission and fusion rates of an accelerated object are not equal.

Establishing sufficient pattern coherence in the parts of an accelerated system thus constitutes a preferential tuning between multiple parallel-directed directional coherences. This effect can result in establishing a one-to-one correspondence to and from one of the higher orthoworlds, i.e., it can result in a coherent circulation between that universe and the specific inert accelerated system. This circulation is easiest to establish through magic frequency windows where the channels of least resistance exist. This is the basic mechanism by means of which a living biological system is produced in and from the appropriate primeval amino acid soup in the presence of (a) magic-window induction (such as in the ultraviolet), (b) the acceleration of otherwise inert particles (such as is locally provided by lightning discharges), and (c) the strong collection of bioenergy to orthorotate it through three rotations (as is also provided by lightning discharges).

It is not accidental that life can be and has been created in the laboratory. This type of experiment, done by a team of strong psychics projecting intentional bioenergy forms, should be able to create specific forms of life. The same type of mechanism can occur inside the living body where it can induce psychomatic illness. A similar mechanism is probably responsible for the placebo effect, and possibly for the body's production of antibodies and the psychic modification of enzyme activity, psychic healing, etc.

JITTER OR DITHER MODULATES THE PRIMARY FLUX

In the continual, virtual, subquantum, orthorotational flux (crosstalk), rotating into and out of a fundamental mass particle, only those components that are coherent are additive, and only those that add to the quantum threshold and breach it become observable quantum change.

In a given observable quantum change consisting of such coherently adhered subquanta, time is produced by fission of the quantum of action. All remaining statistical subquanta which have not collected to the threshold level are virtual subquanta of action possessing unfissioned, unseparated time. These virtual subquanta, which themselves are dynamic and gradually collecting and superposing to various degrees and at various rates, are attached to and exist in the dT interval produced by fission of the action quantum. Thus each and every piece of time contains dynamic, nested, virtual subquanta. Time in observable changes may thus be said to possess an internal dynamic structure filled with such virtual subquantum mental, neutrino, and photonic entities.

At any fission time, the degree of superposition of each of these nested entities is highly variable and depends on the whole past collection history, which in turn depends on all flux components of the proper frequency that have been arriving from all the orthoframes.

Thus virtual-mental entities cohere frequency wise until they breach the quantum threshold and discharge into observable quantum change. It is much like the accumulation of a static charge until sufficient potential is reached and a spark occurs, discharging the accumulation of charge. The same sort of relationship exists between virtual-mental state and observable state. The only difference is that virtual-mental state accumulates by frequency or time phase.

Since present physics is entirely localized, local observations cannot have taken into account distant matching-frequency events in the laboratory frame, or matching-frequency events in orthogonal frames. To the localized particle of mass, the precise moment a particular subquantum superposition of given frequency will superpose to the threshold and turn into quantum change is therefore not predictable. Since the remote causes cannot be accounted for, the local effects cannot be time-ordered.

Therefore at the quantum level, the physical change is totally statistical to a monocular observer. This accounts for the fact that the quantum world is statistical rather than causal.

However, a given fundamental mass particle has a structure of physical aspects, e.g., mass, spin, locality, frequency spectrum, switch rate, strangeness, etc. All of these may be expressible in terms of orthorotational concepts, although not all of them have yet been so worked out. Muses has already pointed out that some of the present quantum numbers are actually hypernumbers. And just as $\sqrt{-1}$, the first hypernumber, is an orthogonal rotation, so are the other hypernumbers.

At any rate, one may regard a fundamental particle as simply a complicated three-space tuning pattern existing in the orthorotational crosstalk flux between orthoframes. This pattern may also be said to consist of sets of frequencies, since each orthorotational flux line has a frequency of in-out-operation. Thus each fundamental particle is a set of tuning frequencies in the flux. A stable particle is a stable spectrum comprised of standing waves. An unstable particle is an unstable set, comprised of some standing waves, which account for the duration, and some not-quite-standing waves, which account for the excited state or degree of instability of the object.

On each flux line, orthorotational flux lines exist, constituting jitter or dither. Also, every fundamental particle is a tuning. It both tunes and is the result of its tuning, i.e., by the fourth law of logic it does what it is and it is what it does. Since tuning allows frequency communication between orthoworlds, then free-energy devices are not only possible but are practical. So are dematerialization-materialization devices, teleportation devices, devices that heal or kill, and anticancer devices.

THE UNTOLD STORY OF QUARKS

We hear so much nonsense about the objectivity of science that it occasionally seems necessary to debunk the sacred cow. In fact, the quark story is a prime example.

In 1910, Millikan made his famous oil drop experiment and determined the charge-to-mass (e/m) ratio of the electron. By multiplying this ratio by the mass of the electron, the amount of charge on the electron might be computed. Thus was born the idea of a constant amount or quantum of electricity, the fixed charge on an electron. Millikan received the Nobel prize for this famous experiment.

Actually, Millikan himself did not originate the experiment. One of his brilliant graduate students, Harvey Fletcher, first conceived the idea. Millikan became interested after he saw what a stir the results were creating, and he accepted the Nobel prize without sharing the credit with his brilliant student. Later Dr. Harvey Fletcher was to become the head of Bell Telephone Laboratories and an eminent managerial scientist in his own right. He also is the father of Dr. James Fletcher, former Chief Administrator of NASA.

Incidentally, Dr. Harvey Fletcher is still alive and alert, should anyone care to check the story! Nonetheless, it is highly doubtful that this grave injustice to Dr. Harvey Fletcher will be corrected.

But the story does not end there. In the late 1930's, a German physicist named Ehrenhaft decided to change the Millikan experiment and use charged solid particles rather than charged liquid oil drops. In fact he used red selenium spheres of various sizes. Amazingly, he discovered that he could isolate and measure fractional charges (quarks) at will, and he could even control the magnitude of the fractional charge isolated on a selenium sphere by varying the diameter of the sphere itself.

His work was duly published in scientific journals, and duly greeted with derision and hostility. Ehrenhaft himself disappeared during World War II. And there the matter lay. Dogmatic scientists continued to blindly teach the indivisibility of the electric charge, Millikan retained his exalted position and Ehrenhaft's work passed into comfortable obscurity. And in sophomore physics laboratories all across the nation, the indivisible quantum of electricity held full sway, dutifully proved over and over by the oil drop experiment.

Then in the 1960's, the particle physicists, despairing because of the bewildering new array of fundamental particles that continued to pour in confusion from their massive high energy machines, turned again to the idea of fractional charge (quarks) to try to make some unifying sense of the embarrassing abundance of strange new particles. By choosing three simple quarks, they could unify the theory of almost all the new particles. (Additional quarks have become necessary in the theory since then.)

So physicists gradually began to look for quarks, but in the giant, sophisticated, cumbersome experiments and devices that were yielding all the strange particles, not in the simpleton's approach that Ehrenhaft had taken. And they could not find them! Try as they would, a quark just refused to leave its tell-tale track. But in desperation they kept looking, and kept missing them.

Then in 1972 a convention of physicists was held at the International Center for Theoretical Physics in Trieste, Italy. Seven Nobel Prizewinners in physics attended the convention, whose theme was the physicist's conception of nature. Paul Dirac, the Nobel prizewinner who had theoretically predicted the positron before its discovery, gave the keynote address to the distinguished gathering.

Amazingly, Dirac presented the work of Ehrenhaft to the startled convention! He showed some of Ehrenhaft's data, and then pointed out that Millikan had also reported a single measurement of fractional charge, but had discarded it from consideration because he felt it was probably an experimental error. Dirac remarked that it all made him wonder whether Millikan might really have had a quark in that single discarded measurement.

The die was cast, and the seed finally planted. In 1977, about forty years after Ehrenhaft first obtained his quarks, someone finally got around to using solid paniculate matter. Researchers at Stanford University tried it out using niobium, and they got a little fractional charge on their niobium. So after forty years, Ehrenhaft, who had so long been ridiculed and ignored, was finally vindicated. It had taken the establishment that long to check his work instead of dogmatically rejecting it. Yet in none of the articles I have seen on the new discovery has there been a single word about Ehrenhaft, or of Dirac's presentation of his work at Trieste.


A = 4πr² (UNCURVED SPACE)
A< 4πr² (CURVED SPACE) THAT IS CLOSED
A<< 4πr² (GREAT DISTANCE IN CLOSED CURVED SPACE)

Fig. 16. Einstein's spherical model of the cosmos

EINSTEIN'S SPHERICAL MODEL OF THE COSMOS

Einstein's spherical model of the cosmos is a primary example of a holographic universe. In such a closed spacetime, each point inside the universe is also at the extreme end of the universe in any direction. Thus the entire physical universe is totally outside any of its internal points, and totally inside each internal point as well.

That is an application of the fourth law of logic. The total internal is identical to the total external. The adjective "total" merely moves one to the common boundary between the operational concepts of "internal" and "external." At that boundary, there is no operational distinction between one and the other.

The universe closure is not limited to just one occurrence or one rate of closure. In fact the universe can then proceed to close again within the same local three-space, e.g., a gradual macroscopic closure due to gravity field (or causing it) constitutes the external universe, and a second extremely sharp microscopic closure due to electric field (or causing it!) constitutes electric charge. The two together constitute a fundamental charged particle of mass. The polarity of charge is determined merely by which of two directions the second closure was made in. Considering an electron as such a dually closed entity, it is readily seen that the closure ratios are all that is being referred to by Feynman's condition. Feyman pointed out that any unified field theory must explain why the ratio of the radii of the Einstein closed universe and the classical electron, and the ratio of the electrical and gravitational forces between two electrons, were the same — on the order of 10^{42}. The model is also consistent with Santilli's proof that the electric field and the gravitational field are either the same thing or partially the same thing. In our model, an electric field is in fact a highly compressed gravitational field. Proper time synchronization should allow fantastic antigravity effects to be realized, and thus electrogravitics has a basis in this model.

A CHARGED PARTICLE IS A DUAL CLOSURE OF THE UNIVERSE

It is proposed that each fundamental particle having electric charge represents a dual closure of the entire physical universe. The gravitational field closure is slow and weak, and it is that closure which results in the so-called external physical universe.

It is proposed that all particles participate in this same closure, since it is their combined distributed mass that represents or causes the closure. (By the fourth law, "represents" and "causes" become simultaneous at the boundary, i.e., when closure is accomplished.)

There are two directions possible for this gravitational closure: one where gravitational masses appear to attract, and one where gravitational masses appear to repel. These two directions thus form antimatter closures with respect to each other. The G closure where G masses attract is said to be the closure associated with a positive time dimension, while the G closure where G masses repel is said to be the closure associated with a negative time dimension. The direction of closure represents or causes the time dimension's algebraic sign, and vice versa (fourth law).

The electric field (E) closure is strong and fast — on the order of 10^{42} times as strong and fast as the G closure. However, its closure is in a direction orthogonal to the direction of the G closure. Since all matter is in motion, a slight deviation from exact orthogonality actually exists between the G and E closures due to crosstalk projection of components from the slight frame rotation involved in the velocity of each mass itself.

There are two primary orthogonal directions for the E closure. One direction yields positive charge and the other yields negative charge, for the positive time closure. For the negative time closure, the directions are reversed.

Such a schema, or version of it, can be made consistent with Santilli's proof, Feynman's criterion, and the observed fact that electricity can affect gravity and vice versa (electrogravitics). In fact, the electric field becomes a highly compressed gravitational field, at nearly 90° from the normal gravitational field. Liberating the compressed gravity in a flashlight battery could accomplish fantastic antigravity effects. Ironically, antigravity should be the simplest and cheapest effect ever dreamed of, once practical mechanisms for orthoshifting E field to G field are discovered.

Since psychotronics and quarks involve more fundamental components of electromagnetic field, hyperfields or biofields, psychotronic devices to yield antigravity should be quite feasible. The undisclosed extensions to Pavlita's psychotronic generators are thus of absolutely fundamental importance.

Furthermore, the ancients appear to have possessed psychotronic devices. Considering that metals, crystals, and other common materials can be used to. construct psychotronic generators, and great power is attainable by the hyperchannel amplifier effect, it is quite possible that priests of several ancient civilizations actually possessed psychotronic devices to lift giant stones by antigravity, and other psychotronic devices to carve the stones like jelly. They may also have possessed psychotronic flying machines which used antigravity for lift and something like rocket propulsion for horizontal thrust. A flying machine that gets its lift from antigravity might be extremely crude in external appearance, and the use of hyperspace for travel would make it unneccessary to travel extensively through ordinary three-dimensional space. Thus many aspects of travel through normal space such as air drag and fineness ratio are of little importance to a psychotronic vehicle.

ADDING AND SUBTRACTING DIMENSIONS

Figure 17 shows the relation between total collection (integration) and orthogonal rotation in hyperspace.


line
points
$\pi/2$
LINE 2
LINE 1
plane A
plane A'
$\pi/2$
Plane A
PLANE 1
PLANE 2

Total collection (integration) constitutes orthogonal rotation in a direction to increase the number of dimensions by one

each plane surface represents the intersection, in the observer's 3-D frame, of this 3-D solid rotated into an orthogonal frame in hyperspace.

Fig. 17. Adding and subtracting dimensions

Total collection of zero-dimensional points in one direction integrates the points into a line (one-dimensional entity). This is precisely the same as if any of the points had been the plane intersection of an orthogonal line, and that line had now been rotated into the plane. Total collection in one direction is dimensional integration, and the collected entities gain an additional dimension, i.e., total collection constitues orthogonal rotation of the higher dimensioned object into observer three-space.

A point can be considered to be, and modeled as, a line in a frame one orthogonal turn away, and simultaneously as a plane two orthogonal turns away, and simultaneously as a solid (in fact, an entire three-dimensional physical world) three orthogonal rotations away. The latter may also be considered to be, and modeled as, a mind, or even as an infolded infinite set of minds. The concept does not stop at three dimensions, but proceeds into higher realms indefinitely. However, three dimensions plus an orthogonal time dimension are sufficient for our purposes.

A converse operation also exists. Differentiation consists of a cut in an object whereby one single element (of the collection the object represents), is separated and isolated, so that one dimension is lost. It is like a closure being opened at one element. This is the same as an orthogonal rotation of the entity (being differentiated) in a direction departing from observer three-space.

In the Figure, the lower two figures show the collection-is-integration schema for higher-dimensional figures. In the lower right figure, we cannot draw the three-dimensional object in its orthorotated position in four-space since we have only three spatial dimensions in the frame. Nonetheless, the additional dimensions exist and are simple to treat mathematically.

MIND IS OBJECTIVE

In time differentiating, mass loses the time dimension. Therefore we cannot see time with a mass perceiver, but we can see L^3 (spatial extension). But time is the only so-called objective dimension occupied or shared by mind. Therefore we also cannot normally perceive mind, because the plate (time) on which it was sitting is lost in the perception process.

Thus Descartes was both right and wrong. He was right in that monocular mind is not present in physical detection output, but wrong in believing mind and physical phenomena are totally separate. Time does not exist except with respect to between one L^3 perception and another, if L^3 is all that is outputted. Physical time is totally relative, totally mental, and exists only in memory. Mind is thus present in $L^3 T$ four-dimensional physical phenomena and is discretized along with time discreteness in the Heisenberg uncertainty relation $dEdt >= h/2*pi$.

In fact, we can even take the extreme view that time is mind. Because to establish a delta t, a former L^3 must be established and compared to a more recent L^3. The only place the former L^3 can rigorously be found is in memory. An event, once occurred, is in the past and is forever gone to the observer. Only in his memory can it be said to exist. But then so is the observation also of the most recent L^3. Thus, rigorously, observed phenomena may be said to exist only in memory, and there is only a past, never a present. Thus a full four-dimensional mind is inseparable from perceived physical phenomena, and mind is quantized along with quantum change in the physical world.


A
Ā
TURNING
A INTO Ā
TURNING
Ā INTO A
A≢Ā
A≡Ā
Ā≢A

A POWERFUL EXAMPLE:
CANTOR'S PROOF THAT THE SET OF ALL SETS IS NOT A SET

Fig. 18. Turning a thing into its opposite

THE SKIN TRANSDUCER EFFECT: TURNING A THING INTO ITS OPPOSITE

On the boundary interface, one type of field may be turned into another. The higher psychotronic field (biofields) may be turned into an electromagnetic field, and vice versa. The boundary interface serves as a transfer function mechanism for translating one kind of effect into another. Both ends of the transfer function are excitonically united in and on the interface.

The Soviet work that measured coherence of cyclic rhythms (heartbeat, breath, body electric fields, etc.) in Kulagina is significant in this respect. Kulagina induced electrostatic fields around objects that she moved psychokinetically. Her biofield, which is connected through hyperspace to the object being moved, is orthorotated into ordinary fields at the interface of the object. Thus an electric field is created, and also a momentum field that causes the object to move by ordinary physics.

The Soviet work appears to have established that man, earth, and cosmos are psychotronically and coherently linked; that the boundary of an object is a transducer coupling internal and external dynamic changes in one-to-one correspondence; that the transducer effect applies to both living and nonliving systems; and that through tuning and resonance, internal patterns can be incepted externally, and external patterns can be incepted internally.

EVERETT'S MANY-WORLDS INTERPRETATION OF QUANTUM MECHANICS

Both mind and matter can be precisely modeled in Everett's many-world interpretation of quantum mechanics.

Ordinary relativity is interpreted for only a single observer at a time. If you believe that you and I simply coexist at the same time, then the basis of physics is very different from what is in your physics book. Everett worked out what happens to physics if we insist on multiple observers at a time: all possibilities exist and are real, no matter how weird or far out; the world is a single giant universal wave function; collapse of the state vector has meaning only to a single observer; the world is composed of multiple orthogonal worlds of infinite variety, complexity, and strangeness; each world constantly splits into multiple worlds at a fantastic rate.

The many-worlds interpretation, though strange, is totally consistent with the experimental basis of physics. Most physicists have completely ignored Everett's profound and fundamental work; the MWI is a time bomb ticking away at the heart of physics.

SPACETIME CURVATURE IS TRICKY

Bent and rotated spaces give strange results. A thing in one frame can be something quite different in another frame. Just as the mass of a moving object does not increase with respect to its own inertial frame, it increases with respect to the observer's static frame.

What a thing is, is totally relative to the perceiver and his perceiving frame. It can even be nothing in a great many frames. Do you see how nothing can contain everything?

So we really can turn nothing into something if we are clever.

We can solve the energy crisis by building free energy devices which simply cohere the nonintersecting virtual-mental energy states and collect them, breaching the quantum threshold and yielding real, observable energy. To put it another way, we can tap zero-point energy.

And we can also turn a thought-object into a real, materialized object in this physical frame. Or we can dematerialize a physical object, converting it to a mental object.

MULTIPLE REALITIES (MANY WORLDS)

In Figure 16,1 show the particular selection of dimensions I take from Everett's many-worlds interpretation of quantum mechanics. Other and more complex selections can be taken, but these suffice for our purposes and allow us to complete the basic schema for connecting physics and metaphysics in the simplest possible manner. The selection and the schema developed thus provides an initial crude theory which makes predictions, develops theoretical mechanisms, and can be physically tested.

In the diagram, each three-dimensional physical frame of an infinite set at orthogonal angles to each other is shown by a single line about the plane of the bottom, much like the spokes of a wheel. The single time dimension shared by every one of the spokes or three-dimensional worlds is shown by a single vertical line, much like the axle for the wheel and its spokes.

Starting with the left spoke and going counterclockwise, the spoke worlds are numbered with the prime superscript system. The *S* world is the normal three-space physical world we all live in and detect; the S^1 world is the first orthogonal world, etc. Each world is also called a hyperspace or bioframe or bioworld and numbered consecutively beginning with zero for the *S* frame. Thus the zero-th hyperspace is the ordinary physical universe.

The first hyperspace is the electromagnetic field. A physical object in this frame is seen as an electromagnetic field to the *S* frame observer. Since its intersection with the S frame is two-dimensional, we immediately see that the electromagnetic field is a plane wave. Light thus travels at speed *c* to every observer in the *S* frame, because *c* is or represents an orthogonal rotation.

Further than the first frame, a three-dimensional object is seen by the S-frame observer as a deBroglie wave. Since its rotation is greater than 90° with respect to the S-frame, the deBroglie wave always moves faster than the speed of light with respect to the S-frame observer.

A three-dimensional object in the S^2 frame is seen by the S-frame observer as a line or force vector, i.e., simply as flux. (Tentatively, this frame appears to be the area of neutrinos.)

A three-dimensional object in the S^3 frame is seen by the S-frame observer as a spatial point, i.e., as spatially dimensionless. It is thus a mental object or a virtual object to the *S* observer.

The entire S^3 frame constitutes a mind or a virtual world. There are an infinite number of such S^3 frames available in hyperspace. In fact, there exists a set of three orthogonal turns between any frame higher than S^3 and the S frame, due to the nature of hyperspace. Thus in the model we are using, any of the higher bioframes may be considered to be only three orthogonal rotations away from the *S* frame.

We thus have a scheme of multiple worlds and multiple realities from which we may construct living systems, thoughts, tulpas, etc. And we may also turn one type of field into another, simply by virtual state collection or separation, as the case may be.

All frames S^3 or higher are mental or virtual frames. Physical phenomena in these frames are mental phenomena with respect to the *S* frame.

Note that we have deliberately evoked a system whereby a mind is modeled in terms of physics and physical reality is modeled in terms of mind. The only difference between any two entities in the various worlds is a matter of orthogonal rotation.

For the pure mathematician, obviously this entire model could be extracted into a new calculus. A symbol could be assigned to the orthorotation operation, and a sign assigned to the symbol to indicate whether the direction of turning is approaching the observer or departing from the observer. Sideways turns and in-betweenwards-turns could be represented by additional signs, or hypernumbers. I suspect that such a calculus is well worth doing, and I also suspect that it will closely resemble Charles Muses's hypernumber work when done. Using a six-dimensional geometry, the German physicist Heim has accomplished something similar, without yet realizing that he has also modeled mind. His work generates all the fundamental particles of physics and explains many features of UFO phenomena, as is to be expected from the scheme developed here.

At any rate, an exact calculus of higher dimensions and of turning one kind of field into another kind of field — with no barrier at all between physics and metaphysics — awaits the hands of the builder.

CLUSTERED ORTHOGONAL WORLDS

In this diagram, I show a sample of how various objects appear in their intersections with various bioframes. Note that an object is many things at once, and that many of the things it is are nonthings or nothings.

Everything is a thought in at least one frame. We can appreciate James Jeans's remark that the world appears less and less like a mechanism and more and more like a single thought. His intuition was in fact literally correct.

Each entity is a photon in at least one frame (let there be light!) Each entity is a line in at least one frame. Each entity is a three-dimensional spatial object in at least one frame.

By orthogonal rotation, a thing can change its face with respect to an observer, appearing to change into a totally different sort of thing with respect to a fixed observer in one frame. Reality is quite plastic and absolutely unlimited. It is only our own rigid heads that have been made of solid concrete.

Specifically, materialization of thought objects, by three approaching orthogonal rotations, exists. Similarly, dematerialization of an object, by three receding orthogonal rotations, exists. In such a case the dematerialized object appears the same as a thought object or virtual object.

A perfectly valid mechanism thus exists for tulpoids, materialized thought forms. All that is needed is a sufficient virtual state collection mechanism.


T
EACH S''' AND HIGHER BIOFRAME IS A MIND.
A PARTICLE IN ONE OF THESE FRAMES IS A "THOUGHT" OR "THOUGHTFORM" IN A MIND.
LABORATORY FRAME
S
MATTER (PARTICLE)
S'
S"
S'''
S^N
ELECTROMAGNETIC FIELD (PHOTON)
DEBROGLIE WAVE REGION
FLUX LINES (NEUTRINO?)
MINDS (VIRTUAL)

Fig. 20. Clustered orthogonal worlds

Note that an orthogonal rotation in an approaching manner is automatically accomplished by sufficient coherent collection in the remote frame. There is a finite collection threshold between two orthogonal hyperframes. Sufficient collection in one frame (by a tuning or directing mechanism in a third frame) breaches the threshold in the collection frame and the collected or quantized entity automatically appears in the next frame closer to the tuning mechanism's frame. The process may then be repeated. If sufficiently repeated, all the intervening thresholds are breached and full materialization of the object in the observer's frame (tuning frame) occurs.

By this process an object may be kindled from a remote frame to one that is less remote. Two successive applications of kindling turns thought into electromagnetic field. This is how thought photography is accomplished, and the talented individual who accomplishes it is simply cyborged to the camera film grain in an inceptive cyborg device. Many such examples, including some deliberately accomplished on demand by the study group in which I am included, are given in this book. Three successive kindlings turn a thought object into a materialized object, a tulpoid.

Such a materialized thought-object may be of an inert object or of a living, breathing, biological being. The model we are working in has eliminated any superficial difference between living and nonliving because it is a four-law model. And a materialized living being will be just as real and physical and functional as any other person on this earth. Ultimately, that is all that we ourselves are — tulpoids. Nothing exists but the thought of the infinite creator, so to speak, and we are simply part of that thought.

The coherence in multiple stages necessary to accomplish kindling is often referred to as *tuning* in this book. Tuning sufficient to enable two orthogonal rotations results in thought turning into electromagnetic field or light. Such a kindled field may be additive or subtractive to existing electromagnetic fields. Thus kindling can cancel an electromagnetic field that already exists, or it can create one where none previously existed, or it can shape, modulate, or change one which already exists.

Kindling can also wipe out the charge on a charged particle, or it can build up a charge on an object which previously had no electric charge. It is not accidental that Kulagina, when performing psychokinesis in the laboratory, first causes the induction of an electrostatic field on a nonmoving object. Then the object moves psychokinetically. In a similar fashion, she has stopped a frog's heart; kindling of the type to quench electric charge would of course eliminate the electrical trigger signals in the muscles of the heart, rendering it inoperable. This could mean either cessation and paralysis in a moderate case or total death in a drastic case. She also on one occasion demonstrated the ability to stop a living human heart. I have met other people who could do something similar. One of the great secret techniques in certain Oriental martial arts was the death touch. This could only be accomplished by certain rare adepts; with a light touch of the hand or fingers, they could induce a charge of bioenergy into and onto the acupuncture system of the body, so that the body itself began to slowly kindle its own nerve current quenching. A real adept could control the amount induced so that the death of the victim could be roughly controlled. Radionics and voodoo can do similar things, though usually to a lesser degree.

There also exists a precise mechanism for metal bending; the destruction of the charged particles (for the protons in the nucleus and the electrons in orbit, or even for just the protons in the nucleus) converts the particles in some atoms to neutrinos, which then vanish in the distance without interaction. Thus localized areas in strong metal can be kindled and made quite plastic from thought energy alone by one who has developed this skill. And the kindled areas will give every indication of having been subjected to extreme heat or unusual forces of a sort not encountered in normal metal bending or fracture. Also, the inceptor who is bending the metal and the metal itself are cyborged together into a single inceptive cyborg mechanism. Therefore the metal will often continue to bend even after laid down, because in the cyborg kindling is still occurring.

Furthermore, metals that exhibit unusual physical characteristics, such as nitinol, can change those characteristics dramatically by kindling. Also, an electrostatic field can be directly kindled in and induced on an external object, and an electric field or electromagnetic field can be induced in its surrounding space to interact with it, accomplishing psychokinesis of the object.

Or thought energy can be kindled in the hyperfield fluxes of an ordinary magnet. A magnetic compass needle can be moved by mind or a magnetometer can be affected, even through a superconductive Farraday shield. After all, the effect is rotating into our three-dimensional space from outside it, so shielding is of little consequence except where it interferes with tuning.

CROSSTALK BETWEEN MULTIPLE REALITIES

In Figure 21, I show that phenomena in all the hyperframes crosstalk. A moving object in frame *S* possesses a slight rotation, hence it projects a tiny component into frame S^1. This S^1 component, however, is still dynamic and has a small velocity in S^1. Hence it also is slightly rotated and therefore has a crosstalk component projected into frame S^2 with a velocity there. Having finite velocity, this projection in turn has a rotation and projects into the next higher frame, and so on.

Thus any changing entity in any frame crosstalks a tiny amount into any other frame. In a frame S^n, the crosstalk from a change in any other frame S^P is normally so small as to be virtual, hence nonobservable. Coherent virtual crosstalk, however, integrates and can breach the threshold between virtual and observable state. It is in fact possible to show that what we call a mass in S space is simply the sum total of the crosstalk in and out of a localized region L^3 of S space, the localized region being the mass in question.

Another point to notice is that most fundamental particles in a frame rarely move with constant velocity. Instead, they normally accelerate and decelerate continually. Thus the actual velocity vector of one of these entities is continually changing, usually quite erratically. But for microscopic particles in regular atomic or crystalline formations, the change pattern is quite regular. At any rate, the constant changes on the velocity induce a jitter component on its crosstalk into other bioframes.

So the crosstalk into a frame is jittery. Thus a fundamental particle is jittery or wavelike. The fine structure constant of an electron encompasses this hyperspatial jitter or wavelike state of the electron. The fine structure constant is about 1/137.



Pig. 21. Crosstalk between multiple realities

Thus an electron actually spends about 1/137 of the time in hyperspace.

So, because of jitter, an object is partially in every hyperframe a minute but finite part of the time. So are all minds and mental objects, and so are all virtual objects. For a fundamental particle, the fraction of time that one quantum of action pervades another frame may be referred to as the identity coefficient.

The identity coefficient varies; it is the photon interaction that time differentiates, quenching time and separating the bioframes, and this interaction is not a linear operator since the intensity of time differentiation is a rather complicated function of photon frequency.

At any rate, for an electron in orbit in an atom (or for any other electron, for that matter) there is thus a small but finite probability that the electron may be at any given position in the universe when its detection occurs. In other words, there is a finite probability of collecting an electron at any point in the universe, and the collection may be made from multiple points simultaneously. We can actually collect the same electron twice, so to speak! Or even a million million times.

The probability of detection of an electron at a given position may be directly expressed as the fraction of time that the electron actually spends there. And this fact may be used to develop a holographic coherent collection scheme that can directly amplify particles. Thus a so-called free energy device, which in one sense is just a tap into the zero point energy of vacuum, can be built. And it has been built, by Moray and by others. The jitter and crosstalk make it directly possible.

BIOFIELDS: AND MAVERICK WORLDS

Figure 22 shows a convenient list of how objects appear in different frames. This schema, selected from Everett's many-worlds interpretation, allows modeling of life, death, mind, matter, and psi. It also allows one type of field to be ortho-



BIOFIELDS: TIME-CLUSTERED ORTHOFRAME

Present Name	n = Number of Orthorotations	Biofield	Dimensional Intersection with Lab Frame
Laboratory Frame	0	0th	3-D
Electromagnetic Field	1	1st	2-D: $\nu = C$
Virtual Photon	$1 < n < 2$	Between 1st and 2nd	Mix of 2-D: $\nu = C$ and 1-D: $\nu = C^2$
Bare Neutrino (candidate)	2	2nd	1-D: $\nu = C^2$ (but flows in photon)
Space-point; mind, thought	3	3rd	0-D, $\nu = C^3$ occupies time, not space per se. Flows in neutrino, thus in photon
Space-point, mind, thought	$n > 3$	nth	Same as 3rd biofield. All hyperspaces are only 3 orthorotations away in nonlinear hyperspace

Fig. 22. Biofields: time-clustered orthoframes

rotated and turned into another kind. Such orthorotation demands correct time synchronization, rather than brute force energy application. In fact, orthorotation is energy-conservative for a single orthogonal turn.

Even the strangest conceptions and most fantastic possibilities have their own assigned realm of concrete reality. These are referred to as maverick worlds.

Note that all possibilities — everything that has happened or could have happened, and everything that will happen or could happen — are real and exist concretely in their separate orthogonal universes. The same is true for all thoughts and thought worlds, and all possible thoughts and thought worlds.

By proper coherent tuning, an *object* in one of these orthoframes can be orthorotated into our own frame and objectified, and that is what the Tibetan monks call a tulpa, an objective materialization of a thought form. The tulpa will hardly ever be closed entirely in phase, however, and so it will almost always be unstable. UFO's, angels, and imps go away. But the materialization of one of these can be entirely objective and perfectly objective traces can be left, such as photographs, broken limbs, scorched asphalt, indentations, and depressions in grassy fields. Any thought object can be so orthorotated and objectified. Beings, religious figures, angels, fairies, imps, UFO's, and monsters can all appear.

HYPERFIELD FLUX IN A MAGNETIC FIELD

In the conventional experiment to determine the pattern of a magnetic field, iron filings are sprinkled about a bar magnet on a piece of paper. As shown in the top drawing of Figure 23, the iron filings form a symmetrical pattern. Further, the only apparent circulation pattern is from one pole to the other. Each flux line is closed, going through the magnet from one pole to the other and out of that other pole, bending back through space to the first pole. Every flux line therefore goes through both poles.

However, each little iron filing is actually quite static; it does not move at all. It does not change with respect to either time or position. It is therefore integrating any higher sinusoidal component that is changing with respect to time and length. The characteristics of the orthodox picture that emerges are prescribed by Maxwell's equations of electromagnetic field.

If we tape the bar magnet to the face of a color television tube, the magnetic field is now being scanned or probed or sampled by a moving electron beam, which reacts with the magnetic field of the bar magnet. This electron beam is changing its position with respect to time and length, and it therefore differentiates the magnetic field. The hyperspatial "ripples" in the magnetic field now are not integrated exactly to cancel, and so a small deviation from each flux line will be detected by the differentiating beam. Slight deviations will cause a color change, and so the hyperspatial flux now becomes evident on the television screen. The lower drawings show the rather unusual, nonsymmetrical pattern that emerges.

The equations for these hyperfield fluxes should be obtainable by differentiating Maxwell's equations twice more, yielding fourth order equations. These equations should be the much sought-after equations of prana, chi, ki, ectoplasm, bioenergy, bioplasma, odic force, etc.

Note that the hyperfield circulation goes into the north pole and pours out of the south pole. A living organism exposed to the north pole, end on, will have its own bioenergy sucked out by the magnet, and its own flux will diminish somewhat. Exposed to the south pole, end on, it will have its own bioenergy increased by the bioflux pouring from the magnet. This explains why many experimenters who have extensively tested the influence of magnetism on growing plants have found that the north pole inhibits and the south pole stimulates growth and health.

The hyperfields are fundamental fields rather than electromagnetic fields; they collect coherently and kindle *into* electromagnetic field, creating it or destroying it.

LIFE AND DEATH

In Figure 24 I present an overall schema for life and death — and for reincarnation as well.

An infinite number of hyperfields or bioframes are shown as S, S^1, S^2, S^3 etc. The frame S is the ordinary laboratory frame — the physical spatial world we live in and observe. The frame S^1 is the electromagnetic field, the frame S^2 the linear or flux frame, and S^3 the first "mental" or "virtual" frame. Also, all higher bioframes have a connective path to the S frame of only three orthogonal rotations (not shown). Thus only three orthogonal turns separate S^n and S, S^K and S, and S^J and S.

In frame S, note that physical body A has a coherent crosstalk link with the entire frame S^n. A-S^n thus constitutes a living biological system; in this case, let us say, a human being. Likewise, B and S^j have established a coherent crosstalk loop. B-S^j thus also constitutes a living biological system; in this case, let us say, an opossum. These two examples are incarnated living systems (incarnated minds).

In fact, this is a great oversimplification, as the reader will realize at once. We really should consider all the groupings of A — the organs, the structures, the cells, the internal cellular parts, etc. — as separate but coordinated a_i. (And similarly with B.) Each of these a_i must have a correspondent s^n subworld of S^n, much like



CONVENTIONAL PICTURE.
IRON FILINGS SPRINKLED
ABOUT A BAR MAGNET ON
A PAPER.

HYPERFLUX
CIRCULATIONS

NOTE STRONG
HEXAGONAL PATTERN
AND TWO PRIMARY
VORTICES

HYPERFLUX CIRCULATIONS
FLUX PATTERNS ARE NOT
SYMMETRICAL, POLE-TO-POLE

NOTE STRONG HEXAGONAL
PATTERN IMMEDIATELY
ADJACENT TO NORTH POLE.

HYPERFLUX CIRCULATIONS

NOTE STRONG
HEXAGONAL PATTERN
AND FOUR PRIMARY
VORTICES

Fig. 23. Hyperfield flux in a magnetic field



$A \rightleftarrows S^n$ is a living system.

A is the physical body, the incepted mass.

S^n is the mind.

$B \rightleftarrows S^j$ is also a living system.

To S, D is inert; i.e., D is not preferentially incepted.

To S, S^k is a "disembodied mind." I.e., S^k is "dead," since it is not preferentially incepting its former body, C.

Whenever a proper retuning body, say E, appears in S, S^k will reestablish a coherent crosstalk with E. This constitutes "reincarnation" of S^k.

Fig. 24. Life and death

the fine structure of atomic energy levels. But here I am simply outlining the major schema.

At any rate, let us now examine body *C* and hyperworld S^k, which formerly were one-to-one coherent in crosstalk, but are no longer so. C represents, let us suppose, the body of a frontiersman in 1830 who has received an Indian arrow in his breast, piercing the heart and destroying the ability of the body to coordinate the c_i to each other and to the inceptive channel from S^k. With the loss of coherence, noise begins to destroy the channel; thus S^k is now a "disembodied mind," and C starts to become a decaying corpse. The various c_i of course lose coherence at differing rates, and so the fine structure channels to the s^k also lose coherence at differing rates.

Finally all c_i - s^k coherence is lost, and the frontiersman is then "dead." The mind S^k is now disembodied — and also probably quite disturbed or "noisy" because of the variance in disintegration of the c_i - s^k loops. One might say that the mind is somewhat "detuned" by the whole affair. However, "death," in the sense of total loss of mind and personality, has most certainly not occurred. All that has occurred is a lapse into a disembodied, and perhaps somewhat confused, state.

And the disembodied mind finds itself in its own deep, unconscious world constructs. If a person has been unconsciously Christian in a very deep, fundamentalist sense, and in his own mind has also been a "sinner deserving of hell," then he will actually "lift up his eyes in hell," in his own world tuning. And that world will be physical and real — as real and physical as this one — but it will operate by different physical laws, just as dreams operate by different physical laws. These relations and laws are prescribed by the person, either consciously or unconsciously. The devout Mohammedan is quite likely to find himself after "death" in the delightfully chauvinistic paradise he believes in.

And so the Catholic practice of praying oneself out of purgatory is relevant, for if that belief-structure is firmly fixed in the deceased's deep unconscious, then it will happen; he will simply change his world construct in accord with the effort made on his behalf.

And the ancient Tibetan practice of giving instructions to the deceased as to what to expect and where to go is also relevant, for during the time that the major channel C-S^k is lost but many of the c_i - s^k are still functioning, the deceased is still in contact with frame *S* and can heed those instructions.

Certain clairvoyants and skilled psychics can also project part of their mind vision into S^k and see the status of the deceased. In some cases the deceased will have so strongly retained mental structures analogous to physical structures and localities (or persons) in frame S that continual small crosstalk channels breach open by tuning resonance to those localities, structures, or persons. With a little inceptive assistance from one or more sensitive persons, an "appearance" of the deceased at the locality, structure, or near the person can take place. Much psychic, ghost, or spiritualist activity is due to this effect. So indeed is the concept of earthbound spirits. Here again, an advanced adept can erase the psychometric pattern attached to the locality, structure, or person and thus eliminate the phenomena. In the American Association of Metascience, such a resolution is part of an overall process called "clearance."

But this is not all. Now that the departed frontiersman has been cleared, so to speak, and is snugly in his own world S^k rebirth process still awaits him. As I


T
thought objects
S'''
physical body "tuner"
S''
S
S'
(S ⇄ S''') 1:1 defines a living biosystem

A. A LIVING BIOSYSTEM


MENTAL WORLD FRAME (S''')
CAUSAL PHYSICAL WORLD FRAME (S)
①
②
③
"INERT" MATTER BEHAVIOR
PERCEPTION
④
⑤
⑥
INCEPTION (INTENT) (NONCAUSAL)

B. THE FUNCTIONING OF TIME AND CONSCIOUSNESS ARE MUTUAL CREATORS OF EACH OTHER.


INCEPTION
④
③
②
①
at the inception the future is shifted slightly
INCEPTION
INCEPTION
at the inception, the past is shifted slightly

Inception or intent thus can slightly deviate from a causal trajectory. Over sufficient collections of physical changes, "intentional behavior" or "limited free will" emerges. However, it is only a very small modulation of causal inertness -- and its smallness accounts for human "physical limitations."

C. CHANGING THE PAST

Fig. 25. **Consciousness, life, and intent**

have pointed out elsewhere, every particle of mass is simply a pattern of change in the universal orthorotational flux between hyperframes. (This, after all, is no more than a slight extension to general relativity.) When the proper physical tuning mechanism, say C^1, again appears in the S frame, then a resonant coupling will automatically establish itself in the flux between C^1 and S^k, and the disembodied, confused mind of the frontiersman will simply be coupled again to a new physical body pattern. This happens at the instant of conception, for the genetic pattern — the complete tuning pattern — is present at that instant. The coupling is quite tenuous at first, and increases in degree as the embryo develops.

So reincarnation has a place in my schema. We will see, however, that it differs slightly from the classical concept, because with developmental work the frontiersman can change the makeup of S^k and thus his predisposed tuning. Changing the tuning also causes rotational displacement of S^k among the infinity of infinities of mind worlds available. Thus the past can be changed; in fact a person can change who he is the reincarnation of, simply by changing his mind tuning with enough development. Therefore more than one living person can be, for example, the reincarnation of Napoleon.

And in fact the cycle of rebirth can be broken completely — simply by dying with a totally detached mental framework. The cessation of all tuning attachment results in a broadened S^k, which now is structureless, hence all-structured and part of universal Godness.

But the major point is that all this can be modeled physically. And there is only life; absence from one place still leaves presence in another. Absence from *any* and *every* one place exclusively leaves presence at all places, each nonexclusively.

Death, where is thy sting?

In diagram A of Figure 25, I summarize what constitutes a living biosystem. Here we can see that body (physical) changes from the biosystem's body in frame S crosstalk successively through frame S^1 and S^2 to S^3. Also, physical changes in frame S^3 actually constitute mental changes to the biosystem's body back in frame S. These mental changes must crosstalk successively into frame S^2, frame S^1, and then into frame S. This entire process — from frame S^3 to S^2 to S^l to S — is referred to as *kindling.*

In diagram B, we observe this process a little more closely. Here, the shorter straight vertical arrows are virtual state changes kindled from the opposing frame. The longer straight vertical arrows represent observable quantized change in the particular frame, these changes being produced by ordinary inert physics laws. The curved double-lined arrows represent quantized change kindled into the frame from the coherently superposed virtual changes that have steadily been kindled there.

Thus there is a kindling time delay in the causal S frame before will or intent sets of changes from the mind-frame S^3 can induce an input into the physical body of the biosystem. Correspondingly, there is a kindling time delay before a perceptual change in S^3 from the changes in S can occur.

The horizontal arrows represent the flow or flux of kindling crosstalk between the two frames. It can be seen from this diagram that consciousness — the thread of the relation between consecutive changes in the two respective frames — and time are identical. (Recall that each inert physical change in S that is not kindled from S^3 is actually randomly kindled from all the other mind-frames.) Thus time and mind are identical. Consciousness is simply the functioning of coherent crosstalk between a mind frame and a physical body in frame S. Further, each biosystem's consciousness has all other consciousnesses interwoven with it. The other living consciousnesses input into other physical bodies in frame S, and these physical bodies interact in frame S. The other dead consciousnesses input into frame S - into each body as well as into all other inert matter — in a noncoherent, randomized manner. Thus the entire universe of universes is totally in communication with each part of itself, continually.

In diagram C, I show that incepting a change from pure causality changes the past; in this case, the past is causally inferred or projected backward from the new vectorial direction. However, because inception into frame S is a very small effect, the biosystem's change of its past is so slight that normally it is not noticed. Inception of course also changes the future slightly.

THE HOLOGRAPHIC HYPERCHANNEL EFFECT

This effect is based on the concept that a human being must accomplish a minute inception (psychokinesis) onto his physical system. Specifically, he must incept the movement of three or four electrons in the brain. This constitutes an input signal to his ordinary physical system, which is then treated like a complex servomechanism. The gain of this servomechanism is rather high, being able to transform or amplify the movement of several electrons into powerful movements of the entire body. The inceptive effect cannot be explained by ordinary physics, which can account for the servomechanism gain only. Once the input signal is generated, however, the rest of the amplification and action are viewed as being properly described by the ordinary physics of inert matter. Thus the human is viewed as largely servomechanistic and mechanical, but guided and directed by the nonphysical, which affects the physical in a minute fashion sufficient to constitute inputs to the ordinary physical system.

Our purpose here is to show that, given this single small inceptive effect, we can eventually approach the mastery of space and time for a linkage of sufficient number of human brains and minds into one single superbrain and supermind.

From the multiplicity of orthogonal frames permitted by Everett's many-worlds interpretation of quantum mechanics, we now select an infinite set of clustered three-dimensional spatial frames, which all share a single time dimension. Using one frame as a laboratory reference frame, the other spatial frames may be characterized as having one, two, three, or more orthogonal turns away from the laboratory frame. These succeeding orthogonal frames are variously called hyperframes, bioframes, orthoframes, hyperchannels, orthoworlds, etc. A particular set of material phenomena in one of the orthoframes is referred to as a biofield, hyperfields, or orthofield with respect to the laboratory frame.

In Figure 26 I represent each brain by a triangular symbol, and consider it as an amplifying device having a gain of A_o. For simplicity the inceptive input signal is represented as E_i, since in moving an electron, a voltage must be induced. For simplicity I also show the brains as a linear array lying in a straight line. The distance L separates each brain, and here L is assumed constant for simplicity.

Two factors must now be realized: (1) The first hyperchannel operates in the realm of the ordinary electromagnetic field, although this realm is seen in a differ-


c (At the speed of light, all L's in this direction equal zero)
(v = c specifies the first biofield or hyperchannel)
L
L
E_i
1
2
3
n-2
n-1
n
I_k

Fig. 26. The holographic hyperchannel effect



hyperchannel
I_k
I_k
A_o
STAGE j
I_k
I_k
I_k
$\sum_{j=1}^{n} A_o^j E_i I_k$
A_o
hyper-rotated output
$A_o \sum_{j=1}^{n} A_o^j E_i I_k$
linear array feedback
STAGE i
$E_o(i)$
$A_o^{i-1} E_i$
Ordinary Input
Ordinary Output
$A_o^i E_i$

Fig. 27. Output of stage i

ent way, i.e., we visualize a photon as an ordinary particle of three-dimensional matter, resting in a three-dimensional spatial frame (hyperframe) that is orthogonally rotated spatially in higher dimensional space, at 90° to the observer's spatial frame. The hyperframe and the laboratory frame share the same fourth dimension, time. (2) At the speed *c* (which determines the hyperframe in the first place), all *L's* are zeroed out, by the equations of the special relativity transformations. Thus one may view (hyperview) each triangle (brain) as superposed on each other triangle (brain). Furthermore, there exists a very small, finite, nonzero probability that the state of one triangle coincides exactly with the state of another superposed triangle, at any given small increment of time. This probability corresponds to a direct fraction of identity between two triangles, since time is stopped along the chain. At any given small increment of laboratory time, any given triangle has on the average a small fraction of identical coexistence with any other triangle. This identity fraction is labeled I_k in Figure 26.

It is important to note that, for a very small fraction of time, the triangles coincide with each other; i.e.; for a small fraction of time the existence of one triangle is totally holographic. This fraction totally violates the ordinary conservation of energy, which is applicable only to a single channel system. The hyperchannel represents a second channel, an identity channel, and in this channel an object can be in multiple places at the same time. If the triangles, regarded as operating processes, are even slightly coherent, then multichannel communication and holographic transmission of a single state-energy into multiple state-energies occurs through the hyperchannel — usually in the virtual state.

Figure 27 shows the setup to calculate the gain of the hyperchannel amplifier. These calculations yield, for the output of stage i,

$$\frac{E_0}{E_i} = A_0{}^n + A_0{}^{n+1} I_k.$$

When no ordinary electrical input exists, $A_0{}^n = 0$, and the virtual state amplification is thus

$$\frac{E_0}{E_i} = A_0{}^{n+1} I_k.$$

This mechanism holds the secret to the tapping of zero-point energy and free energy devices. It is also the hidden variable theory that causes a radioactive nucleus to decay. Since radioactive nuclei interact through hyperspace, the amount of radioactivity in a given sample is an exponential function of the number of radioactive nuclei present.

It is also a mechanism which can directly amplify the virtual-mental state into observable state. It is the fundamental mechanism that causes kindling and thus orthorotation. It can be used to materialize tulpas, and accomplish psychokinesis, remote viewing, clairvoyance, precognition, etc.

MIND LINKAGE

The entire human species has been developing and evolving, not just the individual person.

The development of life in a biosystem may be divided into seven stages: (1) the development of planet, primordial atmosphere and ocean; (2) the appearance of



Fig. 28. Layers of unconsciousness

amino acids; (3) the appearance of the self-replicating supermolecules; (4) the formation of one-celled organisms; (5) the formation of multicellular organisms; (6) brain linkage of an intelligent technological species; (7) total omeganess or godhood.

Two major types of behavior are involved in living organisms: genetically programmed behavior and genetically unprogrammed behavior. Thus one mode of behavior control of an organism is nonadaptive and the other mode is adaptive or learned. Intelligence may be viewed as the ability to adapt behavior, and increased intelligence represents a decrease in the portion of behavioral control that is genetically programmed or "hard-wired."

We may further speak of two types of intelligent species: those that possess a tool-using member and those that do not. The first is a *technological* species, while the second is *nontechnological.* By this classification, man is a fifth-stage, technological species.

The intelligent species, being relatively deprogrammed, is highly adaptive and competitive, and many of its species-specific checks and balances are reduced or eliminated. Because of the use of tools in its internal competition, the technological species continually increases the ferocity of its internal competition and its deadliness to itself. Thus as the power of its tools increases, the technological species carries the seeds of its own destruction within itself, and it will eventually destroy itself unless it advances to the next stage, the linked-mind sixth-stage being.

The sixth stage consists of the linkage of all individual brains in the species into one single superbrain, producing a superbeing having absolute control of space and lime. A technological species is necessary to accomplish linkage and produce a multidimensional, eventually nonphysical, superbeing. When the technology is sufficiently advanced for linkage to be developed, the power of the tools is so great that self-destruction is imminent. Thus an advanced technological civilization is near linkage and also near Armageddon, and in either case it vanishes as a limited, three-dimensional species of the fifth stage. This accounts for the notable absence of a technological species similar to man in man's universe.

ANGELS, IMPS, AND UFO TULPAS

If we realize that each of us has his own mind world, an S^3 frame with respect to the *S* frame physical world, but separate from each other *S* frame mind world, then we see that, if we take common forms that are in the minds of all human beings, it is much easier to kindle them because they can be cohered much more easily.

The common crosstalk in all minds constitutes the collective unconscious. Since the common crosstalk is in a sense a mind, and since it is connected to a "body" of many cells, i.e., of four billion humans or so, then this collective unconscious is a living, breathing entity.

Furthermore, the usual content of its mind is a great deal closer to physical phenomena that are in all minds than is a single human being's mental content. Much of what we term physical reality is in fact prescribed by the collective human unconscious. And if the collective human unconscious is changed in its conception of reality, then four billion stages start kindling with the hyperchannel effect, and immediately the new conception is physical reality.

Borrowing from Jungian psychology, let us call a form that is in each human mind an archetype. Let us also realize that there are shallower levels of unconsciousness (Figure 28) between the total collective unconscious and an individual mind. For an Irish-American there is one level defined as Caucasian, another defined as Irish, another defined as American, another defined by the larger region he lives in (say the state), another defined by his family, and another by his own personal unconscious. The levels are not mutually exclusive, but intersect across one another. At any rate, all these unconsciousness levels above the collective human species unconscious also shape, modulate, mold, and change the kindling channel that exists for a person or group. All these levels of unconsciousness are like finer and finer tuning levels to change the kindling mechanism.

An archetype that is kindled from the collective unconscious is kindled through such a mechanism of unconscious levels of tuning, and the reality format that is kindled is determined by the type of pressure and the content, biases, or tuning of all the levels between it and the conscious minds of the individuals who observe the phenomena.

All tulpoidal manifestations are kindled through and by this mechanism. All of them are shaped by the multilevel unconscious tuning. All of them are caused by an unresolved conflict in the deeper unconscious layers.

Since most minds are notoriously unstable, the tuning is unstable almost always, and the tulpoidal manifestation is usually fairly shortlived, usually not more than a few minutes, or a few hours.

Angels, imps, Virgin Marys, UFO's, sasquatches, Loch Ness monsters, lake monsters, sea monsters, nocturnal mystery lights, fairies, elves, devas, devils, ogres, Mothman, men in black, goblins, large monster birds, etc. are all kindled by the same process. And so are cattle mutilations. I fear that human mutilations will be next.

Any tulpoidal materialization may be physically real during its stable period. It may make large tracks in the ground, operate shiplike space vehicles, break tree branches, take human specimens on board, examine human specimens, etc.

The tulpoid may appear benevolent or harmful, and it may actually be so when in the stably materialized mode. The full content of the human unconscious is there to be materialized in physical form — all the good, all the bad, all the noble, all the sly aspects.

When enough human unconsciousnesses have the idea of fairies deeply ingrained in them, occasionally a real, living, breathing fairy pops out of the collective unconscious, riding as a direct modulation on a more primitive overall human species archetype. And the fairy may do all the things expected; she may pose riddles, give gold coins which must not be examined or they will be lost, etc.

Religion can also make use of tulpoidal appearance. When Christian predecessors believed in a vengeful god, a powerful but spoiled king, they got all the manifestations of that kind of Being. When they believed in a god of sacrifice, they got a god who demanded sacrifice and thrived on it. And when many believe in angels and Virgin Marys, they sometimes actually appear. These appearances are not hallucinations; they are completely real. It is just that all possibilities are concretely and physically real in their own realms, and any of these may be tuned in to appear in this realm.

An infinite number of reality channels exists. The total instrumental characteristics, genetic, psychological, and physiological, of the observers who tune in the channel determines the noise content and the actual channel selected.

A reality is simply an orthogonal frame or world. AH possible realities already exist. A channel is a set of tuned and timed orthorotations communicating back and forth between two orthogonal frames or worlds. Tuning is a complex of mind and matter, and of many unconscious levels.

For a perfect adaptation of this mechanism of coherence, any coherent signal — no matter how fantastically weak — can be raised up out of the grass and made dominant. By time coherence in the virtual state, a virtual state entity can be amplified into observable state. From sheer nothing we can produce something. And since every possible something exists in nothing and is available for cohering, we can get anything at all by this process, at least hypothetically.

DREAMS ARE UNRESOLVED CONFLICTS

Everything is essentially mind. Mind forms layer after layer of overlapping zones of shallower and shallower unconsciousness (multiple simultaneous consciousness), all the way from the universal allness to the personal unconscious, and culminates, like the tip of a dagger, in each conscious mind. Figure 29 illustrates these mindlevels.

Just as the dreams of an individual show his unresolved conflicts, so the materialized tulpoids of the collective human unconscious show its unresolved conflicts. Tulpoidal phenomena thus symbolize man against himself, or one group of humans against another group of humans. The great unresolved conflict in the human species since World War II has been the Cold War. And therefore the great flaps of tulpoidal UFO activity should correlate directly to the Cold War. And so they do, as I indicate in this book. Literally we ourselves are our own "Satan," for in man's inhumanity to man, satanic evil is created inceptively. And we ourselves are our own "godform," for in man's love of his fellow men, goodness is created


Such dreams of the collective unconscious can materialize as tulpoids.
THE DEEPER ONE GOES, THE MORE POWER IS AVAILABLE FOR MATERIALIZATION OF IMAGERY.
DEEPER LEVELS OF UNCONSCIOUSNESS
A
B
C
D
E
F
G
H
DREAM
TULPOID
DRIVES THRUSTING DOWN
CONFLICT

Fig. 29. Dreams are unresolved conflicts


PROPHETIC
SYMBOLIC
TULPOIDS.......... UFO'S,
ROCKETS,
CATTLE
MUTILATIONS,
ETC.
...... FORM OF TULPOIDS
MODIFIED VIA PASSAGE
THROUGH SHALLOWER
LAYERS
SOVIETS
HATE!!!
U.S.A.
EUROPE
(CHINA RESTS ON
DIFFERENT "E" LAYER)
?!?
A
B
C
D
E
F
G

THE PSI CHANNEL IS LIKE A QUASI-HYDRAULIC U-TUBE. CONSISTENT PRESSURE INTO DEEP LAYERS RESULTS IN UPWELLING TULPOIDS WHOSE FORM IS MODULATED AND SHAPED BY SHALLOWER LAYERS, ON THE WAY TO MATERIALIZATION.

Fig. 30. Collective conflict initiates prophetic tulpoids

inceptively. It is not accidental that the Avatar Jesus exhorted man to love God with all his heart and mind, and to love his neighbor as himself. It is also not accidental that a human culture seeks and "obtains" a godform or god-image consistent with its own level of understanding and belief; the resulting tulpoidal activity conditioned into the collective unconscious and the cultural unconscious, and tuned in from them, will be consistent with the cultural desires and expectations.

So in a sense we are the creators of our own reality and our own tulpoidal expressions of higher reality. But in addition to tulpoids, the present character of spacetime and dimensionality, and the very laws of the physical universe, are largely prescribed by the collective human unconscious.

GHOST ROCKETS AND FLYING SAUCERS: MATERIALIZED TULPOIDS

Unfortunately, from 1945 to 1947 events occurred that caused a split among previous World War II allies and that led to the beginning of the Cold War in 1947.

Due to these events, Western nations perceived a growing threat from the Soviet Union. The resulting interplay of events, news reports, and personalities, plus the traumatic aftermath'of World War II, led to strong psychological pressure on the group unconscious of the Western nations, and thence on the collective human unconscious. This pressure resulted in popouts of direct orthorotations of resonant archetypal symbols from the collective unconscious, the archetypal format being successively modified by the Western group unconscious and the progressively higher levels of unconsciousness.

The formats of the deep human unconscious were formed millions of years ago in the primitive tribal state. In the tribal warfare of those ancient days, the male went to where the action was, while the female stayed behind in the protected cave, fortress, or shelter to care for the young. Thus the male symbol was closest to the threat and identified with being there.

Furthermore, in primates the phallic symbol is the universal symbol of threat, dominance, and defiance. Dominant primate monkeys often briefly mount submissive males to show their dominant position, exposing their genitals in so doing. If the mounted male does not submit, an immediate battle ensues to determine the dominant male. Thus the phallic symbol represents threat and domination.

In the deep human unconscious, fire is a symbol of power, for with fire the species held predators at bay and began the long trek up from the jungle cave to modern civilization.

Finally, the unconsciousness of a substantial number of the Western nations had been deeply impressed by the German V-l and V-2 rockets during World War II, for the imagination of the world had been breathtakingly fired by the surprise advent of the German rocket weapons.

Thus we would expect that in those Western countries — Norway, Denmark, Sweden, etc. — that are close to the Soviet Union, archetypal tulpoid popout materialization would have taken a male, threatening, dominant, power format. The nearest, most powerful, most resonant recent stimulus symbol in the Western group unconscious would have been the final modulation, determining the final format.



Outside showing contact ptate, sample well, tuning vernier, and on-off switch.



Inside, showing India Ink drawing of *an a*mplifier schematic, used as the "amplifier.'

Photo 41. Hieronymus device — second kind.

So a massive wave of "ghost rockets" from the direction of the Soviet Union appeared in the skies over Norway, Sweden, and Denmark, and other nearby European countries. (See Photograph 43.)

However, North America constituted a natural fortress with great ocean barriers to the east and west, and no strong enemy to the north or south. Therefore, a female symbol (archetype) should have been resonant and stimulated in the U.S., and so it was. In 1947, the year the Cold War began, Kenneth Arnold, flying over the state of Washington (the most northwestern U.S. state at the time, and the one nearest the Soviet Union), encountered a formation of flying saucers — the female circle mandala, dressed in modern aeronautical form. Thus was born the age of flying saucers in America.

PART THREE

NEW MILITARY APPLICATIONSOF PSI RESEARCH

BACKGROUND TO PSYCHOTRONIC RESEARCH IN THE U.S. AND THE U.S.S.R.

In this section I will discuss some of the fantastic psychotronic weapons that have been built and deployed by the Soviets as a part of operation "Fer-de-Lance," the Soviet plan to conquer the world.

The Soviet Union has had a massive developmental program in what they call energetics or psychoenergetics (and what we are calling psychotronics) for about thirty years. To appreciate the mind-staggering weaponry that has emerged from this effort, I should point out that the U.S. developed the atomic bomb in World War II in about four and a half years; thus the Soviet psychotronic program is the equivalent of roughly seven Manhattan projects, back-to-back. With this comparison we gain a rough yardstick to appreciate the fantastic capabilities that must have emerged from the sustained Soviet program. As we will see, they are indeed mindboggling.

Ironically, most of the original theoretical work was done here in the United States, just as the pioneering work in rocketry was done here by Goddard, before the Germans picked it up and advanced it to the V1 and V2 rockets. Just as Goddard himself was once the laughing stock of the Pentagon, so the key U.S. researchers who could have initiated the psychotronic age in the West — Moray, Abrams, Reich, Hieronymus, Drown, Tesla, de la Warr, etc. — were generally ignored or prosecuted or both. Even more deadly has been the studied avoidance of any application of the basic theoretical work — which again was developed largely in the U.S. This work included the Everett-Wheeler-Graham many-worlds interpretation of quantum mechanics, and the extension of Lorentz's work by Ives, Ruderfer, and others to show that almost all modern physics — including general relativity, Newton's laws of motion, and the law of universal gravitation — can be straightforwardly derived from a Lorentz-invariant nonmaterial ether. Even though Pauli pointed out that the Michelson-Morley experiment only eliminated a material ether rather than ether per se, and although Einstein himself once proposed the use of the term ether to include dimensionless vacuum space complete with various fields, modern physics in the West has ignored the ether theory.

As Robert Anton Wilson points out, whatever you believe imprisons you. The West has been solidly imprisoned in its own orthodox view of physics, and hence has been unable to surmount the stone walls of its self-imposed mental barriers. In fact, it has not even tried. There has been no serious, sustained program to deliberately examine the loopholes in present theory and seek the necessary changes to provide a theory of paranormal-psychotronic phenomena. In fact, the major Western work on paranormal phenomena seems only to attempt to "prove" over and over that such phenomena exist; and to attempt to derive from present physics theory a "normal sane" theory for "abnormal insane" phenomena. The orthodox establishment continues to vigorously attack the experimenters who struggle with paranormal research on the grounds that their work does not present science.Hence the experiments and experimenters are unscientific and either at worst frauds and charlatans or at best seriously deluded.

The simple procedure necessary to solve these questions — set up a deliberate, well staffed, well-funded program on a continuing basis — has not been adopted in the West because of the short-sightedness of our management structure. We seem to have totally forgotten that we got the atomic bomb in the first place and we put a man on the moon, simply by starting a program with staff and funds to try to do it, not by engaging in a neverending series of arguments as to why it could not and should not be done.

So, ironically, the nation that prides itself on being free and liberal has adopted an iron dogma of its own in science, a dogma that yields very slowly and that has effectively blocked us from serious and prolonged efforts in psychotronics.

Meanwhile, the Soviet scientists — admittedly kicked firmly in the tail by Stalin — have simply got off their dust-encrusted seats with alacrity and got to it. In thirty years of such getting to it with massive state support, they have already launched the psychotronic age, first applying it to the weapons field, the typical Soviet priority. Meanwhile, for the same thirty years we in the U.S. have played the same old tired games that once led Heisenberg to remark that new scientific knowledge only gained acceptance when the old scientists who so adamantly opposed it had died away.

Finally, there is a direct relationship between UFO's, psychotronics, the collective human unconscious, the Cold War, and Fer-de-Lance that cannot be escaped. So while this section emphasizes psychotronic weapons deployed by the Soviet Union I continually remind the reader of the concepts involved in the related paranormal phenomena, which were covered in Parts One and Two. So with these words, let me give a brief summary of Soviet psychotronic weapons. Make no mistake, it appears that the final holocaust is now unavoidable — we will reap the full rewards for our smugness, pride, arrogance, and inflated egotism.

The Soviets will unleash World War III and they will unleash the psychotronic weapons on a totally unsuspecting world.

But there is something more; it does not end there. There is another player in the game — the collective human unconscious, ZARG itself, will unleash a reaction that makes psychotronic weaponry pale by comparison. Yet when that great entity has roared out its anger, destroyed perhaps half the earth, and then opens its eyes, the full biblical prophecy will in a most bizarre and unsuspected way be fulfilled.

Time will end, and the grave will give up its dead. The unifying of all human minds into one will complete the birth of a new godlike being, extending from the beginning to the end of time all at once, and from beginning to end of all possible times all at once. Three-dimensional concepts and limitations will fade away as child's play to the being that is already in four billion dimensions.

And you and I will become gods, literally, actually — for being is holographic, and whatsoever ZARG becomes, so we all become.

PSYCHOTRONIC BACKGROUND SINCE WW II

After WW II Soviet scientists were ordered by Stalin to actively seek another area of great breakthrough — such as the U.S. atomic bomb had been — and leave no stone unturned in their search. Apparently the Moray detector was resurrected and intense experiment and development begun on it. Much of the pioneering radionics work of the West and Ive's work would also have been available at this time. I believe that in 1958 the Soviet nuclear catastrophe near the Urals was the result of an attempt to transmit a nuclear explosion through hyperspace. (The peculiarity of a transmitter tuning failure would have resulted in an explosion emerging from the nearest large nuclear waste storage, and that apparently happened.)

In 1956, however, a major new interpretation of quantum mechanics was originated by Hugh Everett at Princeton University under the world-renowned John Wheeler. This is the theory of the universal wave function—the many-worlds interpretation (MWI) of quantum mechanics. Practically the entire Western output on the subject is available in his 1973 book entitled *The Many-Worlds Interpretation of Quantum Mechanics.*

This physics is so exceedingly strange that it has been ignored by almost all Western physicists — indeed, it is so strange that even its originators, Everett and Wheeler, are said not to be able to believe it. Wheeler is reported to have once stated that he could believe it on Monday, Wednesday, and Friday, but not on the other days of the week. Using the MWI, however, one can produce a theoretical model of psychotronics which is totally consistent with the entire experimental basis of modern physics, and unite both mind and matter on a single scientific basis.

The Soviets apparently seized on this new theoretical work and applied it to the Moray device, solving their theoretical and technical difficulties.

In 1960, Khrushchev, speaking to the Presidium, stated that the USSR had a new weapon in development ("just within the portfolio of our scientists, so to speak") that was so powerful it could wipe out all life on earth. I believe he referred to the nuclear hyperspace howitzer and to the death ray weapons under development at that time, such as the following.

ELECTRON DISSOLUTION

There are four levels of effects on biological systems that are irradiated by electron dissolution beams.

Interference with the electrical functioning of the nervous system is the dominant effect. Single channel subsystems are more sensitive to the effect.

Mild irradiation (or mild kindling of short duration) causes weakness, trembling, and an unreal, dreamy feeling (as when one gets a whiff of anesthesia). The victim is conscious, however, since consciousness is limitedly multichannel.

Moderate irradiation (or kindling of moderate duration) causes paralysis of the motor system, and a very unreal, floating feeling. The individual is barely conscious and is hypnogogic. Panic is usually engendered.

Strong irradiation (more protracted kindling) causes loss of consciousness in addition to paralysis. The autonomic nervous system still functions with difficulty, and the victim is just barely alive. Convulsions and other symptoms may appear.

Very strong irradiation (protracted kindling) totally jams all levels of the nervous system, and death results instantly.

In UFO contactee incidents this effect is widely demonstrated. Many cases show step function failure of automotive electrical systems, lights, radios, etc., as a UFO approaches. When the UFO departs, the electrical systems almost invariably resume complete operations. Absolutely no electrical components are damaged.

To extinguish these systems with massive RF fields would result in blowing fuses, diodes, transistors, etc., and a great amount of electrical sparking — probably sufficient to blow up the gasoline tanks, In fact, none of these things occur.

Stage 2 electron dissolution should definitely disable automotive circuits, and the upper level of stage 1 may be sufficient. Either would leave the automobile passengers conscious, though paralyzed in one case and not in the other. Both types of correlations are shown in the UFO literature.

THE 1973 CONTACTEE WAVE AND CATTLE MUTILATIONS

In 1973 the Yom Kippur war took place. This was the Soviets' "Spanish Civil War," and they tested the final tactics and equipment for antitank and antiaircraft weaponry, and obtained final data on tank and equipment loss rates for modern combat. The effect on the U.S. and NATO of the cutoff of Arab oil was also tested.

At one point, when the Israelis cut off an Egyptian army in the desert, the Soviets notified the U.S. over the hot line that Soviet forces were going in and the U.S. could do whatever it pleased. The Soviets loaded and readied seven airborne divisions to insert, and the U.S. readied its single airborne division to send in. So the world teetered on the brink of direct ground confrontation between the Soviet Union and the U.S., with all its possible consequences.

Confrontation is after all another form of *contact.* And UFO contactee cases involve *confrontation.* In the very month, October, that the Yom Kippur War erupted, the greatest wave of UFO contactee cases in history broke out in the U.S. Further, in the shallower unconscious levels above the collective species unconscious, which were modulating and molding the tulpoidal reality format, the imagination of the world had been captured by the spacesuited astronauts who had walked on the moon. So most U.S. contactee cases involved spacesuited beings, conditioned into that framework by the national, cultural modulation. Some of the contactee cases involved robots or metallic men, similar to the mechanisms and robots of the U.S. space program. And here in the U.S., the fortress, the female-mandala craft symbol was generally maintained.

Now if this unbelievable scenario has any validity, then after the dress rehearsal of the 1973 Yom Kippur War we ought to have seen an increase in the tulpoid phenomena of a sharply symbolic nature. And that has happened.

The cow is the Western female symbol par excellence; Western children nurse on cow's milk, so to speak. If the U.S. fortress is to be violated, then the female symbol will be violated as the time for the Soviet assault nears. So cattle mutilations of a mysterious, paranormal nature have been occurring all across the U.S. — from the East Coast out through Colorado, Utah, and Montana — approximately nine thousand by now, in some estimates. The symbolism in the mutilations can be easily read: the U.S.'s lifeblood is going to be drained, totally, as all the blood is usually drained from the cattle. The Soviet operation will be launched with blinding speed and surgical precision, and the mutilation of the cattle is done as if by highly skilled surgeons. The children of the West shall be cut off from their sustenance, and so the cow's teats are removed. The armed forces (males) confronting the Soviet forces will be devastated (i.e., the fruit of the womb will be



Precursor(s)	Wave(s) / Incidents	Comment
German rockets in WWII/Soviet threat in 1946–47	1946–47 ghost rockets over Sweden and adjacent countries, from direction of U.S.S.R.	Phallic tulpa symbols
Buck Rogers/sci–fi ships Cold War 1947	1947—Flying saucers	Circle/Disc mandala in scientific dress
1950 Critical Korea period	1950 Wave of UFOs	Peak pressure surge on collective unconscious
1952 Critical Korea period	1952 Wave of UFOs	Peak pressure surge on collective unconscious
Sputnik 1957–1959	1957–1960 Wave of UFOs	Peak pressure surge on collective unconscious
Cuban missile crisis 1962	1962 Wave of UFOs	Peak pressure surge on collective unconscious
Arab/Israeli War 1967	1967 Wave of UFOs (4th largest)	Peak pressure surge on collective unconscious
Arab/Israeli War 1973 Near confrontation U.S. vs U.S.S.R.	Spectacular 1973 wave contactees increased, space–suited beings increased	Peak pressure surge on collective unconscious; astronauts had walked on moon.
Soviet attack preparations completed	1975–present cattle mutilations in U.S. heartland	Cow is female symbol. The female (fortress, sanctuary) will be violated.

Fig.31. Examples of UFO waves



October 11, 1973 UFO CE III
The Pascagoula incident from the witnesses' viewpoint.
Humanoids were atypical.

Fig. 32. 1973 Contactee wave

devastated) so the sexual organs of the cows are excised. Free speech and freedom to hear will be cut off, so the cow's lips, tongues, and ears are excised. A very high (psychotronic) technology will play a role, but one which will limit resistance, so the cut edges are often made as if by pinking shears and then precisely burned as if by a laser. (The laser is symbolic of new, strange technology almost incomprehensible to the average person.) In one case a horse was the victim — a young horse, symbolic of the young soldier. It was castrated, as the dominance of the Western soldier will be surgically excised. Castration of the male symbolizes the total loss of his power and the infliction of impotency upon him.

There is more, but this is a bloodcurdling sampling of the metapsychological implications of the cattle mutilations.

RADIATION OF THE U.S. EMBASSY

About 1959 or 1960 the radiation of the U.S. Embassy in Moscow with weak microwave radiation began. It continues to this day. The radiation is a brilliantly designed intelligence probe: the Soviets were vitally interested in ascertaining whether or not their U.S. adversary knew about psychotronics (i.e., whether the U.S. had built such weapons of its own and might have built defense counterweapons as well). Accordingly, they began weak PT-modulated microwave radiation of a high-level U.S. target, the U.S. Ambassador to the Soviet Union, which would guarantee the personal attention of the State Department, NSA, CIA, DIA, the President, etc. The PT modulation apparently consisted of various disease patterns of gradually increasing seriousness — flu, blood changes, heart irregularity, cancer, etc. By the U.S.'s reaction, whether or not it knew anything of PT could be positively assessed. If the U.S. reacted only to ordinary electromagnetics, then with 100 percent certainty it knew nothing of PT and had no secret PT weapons of its own or counters to the Soviet PT weapons. So since about 1959 or 1960, by our alow reaction to the radiation of the U.S. Embassy — and then by our reaction only to the electromagnetic aspects — we have been assuring the Soviets that we know nothing of PT. Even though several U.S. presidents have protested the radiation, the Soviets have persisted because it is an intelligence tool of the utmost importance to them.

DISEASE AND DEATH TRANSMISSION

For confirmation of Soviet experimentation with PT induction of death and disease, see V.P. Kaznacheyev et al, "Distant intercellular interactions in a system of two tissue cultures," *Psychoenergetic Systems,* Vol. 1, No. 3, March 1976, pp. 141-42; and by the same authors, "Apparent information transfer between two groups of cells," *Psychoenergetic Systems,* Vol. 1, No. 1, December 1974, p. 37. These articles give one a glimpse of the results of over 5,000 Soviet experiments on the basic effect. Kaznacheyev is the head of the Siberian Branch of the Soviet Academy of Medicine, and has at his disposal every disease germ, virus, and toxin known to man. Note that the experiments were performed in the dark to prevent the quenching effect of the visible light spectrum und the effect is only obtained through the quartz (which has IR and UV windows). Also note that in the two-slit experiment — which contains all the mystery of quantum mechanics, according to Nobel prizewinner Richard Feynman, cofounder of quantum electrodynamics — one does not get the quantum effect with an electron, if the electron is first hit by a photon of light before reaching the two-slit region. If the electron is not hit by a photon, one gets the quantum effect. According to Feynman, the quantum effect in the two-slit experiment is not explainable by any classical means. Our comment is that the explanation is not possible by Aristotle's three laws of logic, on which all Western logic, physics, and mathematics are based. However, the fourth law of logic, together with the present three laws, provides a closed metalogic which does contain the explanation of the two-slit experiment, as we showed in Part Two. The fact that there is no problem in explaining the experiment if one takes into account the nested structure of time was pointed out as long ago as 1957 by Dr. Charles Muses. Similarly, the disease and death transmission experiments of Kaznacheyev et al have been explained in Part Two.

OTHER WEAPONS

Clandestine testing of PT weapons also appears to have been accomplished directly in the U.S. The Legionnaires' disease may have been one such test. The suspect agent was actually seen, according to sworn testimony before a Congressional committee. A person with a book-sized object in his hand (tape recorder with PT pattern), a tobacco-pouch sized object in his coat breast pocket (transmitter) and a wire running to his tie clip (antenna) was present and mingled with the Legionnaires for several hours. He was heard to exclaim several times to various Legionnaires that it was too late and they were all doomed. The eventual appearance of the weird "biological agent" that is different from any other germ known can also be explained by kindling from the anxious minds of the baffled U.S. researchers and scientists. Other such tests have also apparently been conducted.

HYPERSPACE HOWITZER OPERATION

The facility at Semipalatinsk is a third-generation hyperspace nuclear howitzer. It can transmit a full nuclear explosion through hyperspace into a tuner planted anywhere in the universe, without traveling through or in normal space at all. Furthermore, it has a unique characteristic: any number of receiver-tuners may be tuned to the transmission channel and each will have the full nuclear explosion emerge from it, undiminished.

Thus, one channel might be for U.S. Minuteman sites, and a tuner on that frequency (say one containing 100 transistors, sealed in plastic and buried in the earth) could be preplanted near each Minuteman site. Another channel might be for all the SAC bases, another for large U.S. cities, another for nuclear weapon storage sites, etc. Any or all of these could be connected to a single blast transmission, simply by controlling the channel width over which the hyperpace transmission occurs.


Hal Crawford
©1978

Fig. 33. Cattle mutilations


TRANSMITTER
TAPE RECORDER
TIE CLASP ANTENNA
TRANSMISSION THROUGH PHOTONIC BARRIER
MODULATION ONTO RF CARRIER (into each photon)
RECORDED PSYCHOTRONIC PATTERN (virtual state)

Fig. 34. Induction of Legionnaire's disease

Here one must not confuse ordinary single-channel conservation of energy with hyperspace operation. The transmitter corresponds to the grid of a gigantic triode, the preplanted receivers constitute the plate area, and zero-point vacuum energy constitutes the cathode energy source. So just as in a triode, energy is conserved from cathode to plate, but not exclusively from grid to plate. Since zero-point vacuum energy is being gated by the triode grid (the howitzer) signal (the explosion), the energy that can be outputted at the plate (from the tuner-receivers) is essentially unlimited. Any number of receiver-tuners can be connected to a channel, merely increasing the plate area. And from each tuner there can emerge a full-scale, undiluted replica of the explosion in the howitzer at Semipalatinsk.

Thus a single nuclear blast at Semipalatinsk can in one instant wipe out all hind-based strategic nuclear retaliation capability in the Free World, if the preplanted tuners are on site.

An additional modification — something like additional orthorotator rings surrounding the primary hyperspace orthorotator ring — may have been made to the nuclear hyperspace howitzer within the last two or three years. If so, this would have the characteristic of materially reducing the "spillage" fraction of the nuclear explosion and also the vibration associated with a firing. There is a possible indicator of this: quoting from *Science*, "On five occasions during the first half of 1976 traces of neptunium-239 and molybdenum-99 were detected in southern Sweden. These activities were accompanied by small amounts of fission products such as iodine-131 and barium-140. One of the events was coincident in time with large peaks in the atmospheric tritium gas concentration." (Lars-Erik DeGeer, Swedish National Defense Research Institute, "Airborne short-lived radionuclides of unknown origin in Sweden in 1976," *Science*, Vol. 198, No. 4320, 2 December 1977, pp. 925—27.) These events were concentrated during the time the Semipalatinsk experiments are reported to have started, yet no seismic activity was associated, as would have been the case if ordinary nuclear explosions had occurred in normal space inside a containment sphere for a large particle beam experiment. On the other hand, if a very high percentage of the explosion were transmitted/rotated into hyperspace, then residual traces of a nuclear explosion would have been present in the atmosphere because of the very slight spillage venting into normal space, but almost all mechanical shock and vibration would have been eliminated. It is at least a striking correlation that exactly such indicators are present, as reported by DeGeer.

A clever adversary who becomes aware of the necessity for preplanted tuners could use a very simple but completely effective countermeasure: simply locate the timers and dig them up, then clandestinely put them back into Soviet territory. Or build tuners of one's own and plant them in Soviet territory. Thus it would seem imperative to develop a mode of operation that does not require preplanted tuners at the target area.

This capability can be provided by using the howitzer in an interferometer mode — by constructing additional orthorotation rings around the firing chamber ts (hut a "hyperspace interferometer" exists. With this scheme any point on earth can be precisely focused on by the howitzer, and no preplanted tuner is necessary. The advantage of this mode is the elimination of the need for clandestinely preplanted receivers, and the freedom to operate in spite of any receivers preplanted by the adversary on Soviet soil. The disadvantage of the interferometer is that the former "triode" operation has now been converted to "diode" operation — when one explosion is put into hyperspace, now a single explosion at a single target area emerges, since a single selected spatial location is now exclusively determined by the interferometer settings.

For a more complicated interferometer mode, orientation and alignment of the interferometer's indicators and controls and amplifiers would be necessary. This could be done using fractional kiloton yield weapons — or even ordinary HE explosions — and focusing the howitzer at a displaced aiming point, at some distance from the target area. This is simply the standard artillery technique of registering a gun on an offset registration point, then performing an x-y shift to the intended target when the gun is fired.

Orientation and alignment of such a weapon system probably accounts for the sonic booms — mysterious high altitude explosions — off the East coast of the U.S. in December 1977 and January 1978. Over the West coast, mysterious explosions occurred inside thunderstorms; these also could well have been the adjusting of the weapon. By using about 100 tons of TNT explosive in the howitzer, a very good high burst registration could be made, and "forward observer" agents in the U.S. could observe the bursts through optical instruments and report their exact positions, thus calibrating the interferometer settings. Of course, mysterious booms have been around for quite a few centuries; however, these "normal but unusual" phenomena have quite a different sound than does the howitzer shot. The natural booms are not so much like single giant explosions as like rolling thunder. Furthermore, several observations of the booms off the U.S. East coast confirmed light flashes (which have not been seen to accompany the natural booms) and swirling or rotating effects in the flashes. Also UFO's were directly associated with some of the booms, revealing the stress factor on the collective human unconscious, implying their Soviet psychtronic origin. A few years ago similar high altitude booms occurred over Ohio and surrounding states, and such booms have also occurred off the coast of England.

Thus the howitzer may have been accurately aligned for diode operation, calibrated near the East coast, on the West coast, in the center of the U.S., and near England. Furthermore, its firing rate and recovery time were also apparently checked out; five booms occurred on one day and after a lapse of several days, the booms occurred again.

As I describe the fantastic psychotronic weapons the Soviets possess, the reader may wonder why the Soviets have not already attacked. The reason is that the superweapons have a strange weakness and failure mode possessed by no other kind of weapon. The hyperspace amplifiers in the psychotronic weapons depend on a large number of stages, say sixty to one hundred, and the hyperspatial flux in all these stages must be very stable and isotropic. At odd intervals the flux coming in from hyperspace suddenly becomes turbulent; this destroys the smooth coherence in the multiple stages of the amplifiers, and thus the basic amplification mode. Thus *all* the psychotronic weapons will suddenly cease working at the same time, and this "all fail" mode may last from fifteen minutes to even three weeks in an extreme case. Thus the weapons are erratic and not dependable. For this reason, the Soviets dare not rely *exclusively* on them, and so they have been forced also to prepare for full nuclear war as a distinct possibility when they launch operation Fer-de-Lance, the full attack. They have thus built up their regular army, their navy, their strategic offense systems, and their strategic defense systems on a scale unparalleled in human history. Today the Soviet Union is the strongest nation on earth — by far — and is fully prepared to launch World War III and win it, with or without superweapons.


DIODE MODE
HYPERSPACE
TARGET (FOCUSSED LOCATION)
ZERO-POINT ENERGY
NUCLEAR EXPLOSION IN HOWITZER
(INTERFEROMETER MODE)
TRIODE MODE
HYPERSPACE
PRE-PLANTED RECEIVER/TUNERS
NUMBER OF PRE-PLANTED TUNERS DETERMINES PLATE AREA
ZERO-POINT ENERGY
NUCLEAR EXPLOSION IN HOWITZER

Fig.35. Hyperspace howitzer operation (2 figs)

A POSSIBLE OPERATIONAL TEST OF PSYCHOTRONIC ANTIAIRCRAFT WEAPONS

When the F-l11 all-weather attack aircraft were deployed in Vietnam, a rather interesting loss rate pattern emerged. Of the forty-eight F-l11's in operation, eight were lost at the beginning of the action, but no losses occurred thereafter, according to General Vogt, the officer responsible for U.S. air operations at the time.

Initially there were some radar anomalies and other system malfunctions with the aircraft, but these problems were quickly resolved. The F-l11's flew singly, extremely low, and without radio contact. Between September 1972 and the end of hostilities in Vietnam, the F-lll's flew over 4,000 sorties, never losing any planes other than the eight lost initially.

The reason for the loss of the eight planes remains a perplexing mystery. In fact, there is no knowledge of exactly where the planes were lost, except in one case. That F-l11 was downed over Hanoi, and its two pilots, Captain Robert D. Sponeybarger and 1st Lieutenant William W. Wilson, were captured alive by the North Vietnamese. The two airmen were later returned under the prisoner of war exchange program, and they then told of the loss of the aircraft, which took place under very strange conditions.

According to the two crewmen, they met a sudden disaster while flying over Hanoi at night, supersonically, and at very low altitude — only a few hundred feel above the earth. Without warning the F-lll's emergency indicators lit up like a Christmas tree, indicating massive and multiple failures of unrelated aircraft systems.

They were not hit by a surface-to-air missile, according to the crewmen, because no explosion of a missile warhead, with its concomitant fireball, occurred. If large-caliber automatic weapons fire had hit them, the distinctive streak of the tracers would have been clearly visible in the night sky, and a sharp impact in the aircraft structure would have been felt. None of this happened.

It could not have simply been an aircraft malfunction, because far too many unrelated aircraft systems failed at the same time. (There is triple redundancy in the control system of the F-l11, by way of comparison.)

Indeed this initial loss of eight aircraft — and then no further losses at all — is difficult to explain rationally, as are the mysterious circumstances surrounding the loss of Wilson's and Sponeybarger's craft.

However, it requires no stretch of the imagination to realize that the Soviets very much desired to obtain the glittering new F-l11 to examine its technical characteristics, its sophisticated design, and its highly sensitive terrain-following radar, ECM gear, and other avionics equipment.

Also, the Soviets had a pressing need to try out one or more of their psychotronic antiaircraft weapon systems — perhaps one which simply modulates a radar beam psychotronically to induce electron dissolution.

Accordingly, it can be postulated that the pragmatic Soviets simply combined both needs, and quickly set up a psychotronic trap for the F-lll's immediately after the aircraft were deployed. They may even have cleverly designed the specific psychotronic modulation so that kindling would occur in some of the aircraft's electrical systems before others and the failure would be massive but not total.


SPILLOVER
(Vented to earth barricades/traps)
ORTHOROTATERS RING I
RING II
ADDITIONAL RINGS OF ORTHOROTATERS FOR OPERATION IN INTERFEROMETER MODE
NUCLEAR EXPLOSION
CHANNEL TUNER
HYPERSPACE
SEMIPALATINSK
HYPERSPACE TRANSMITTER
CHANNEL A
MINUTEMAN SITES
CHANNEL B
LARGE US CITIES
CHANNEL C
SAC BASES
CHANNEL D
ARMY INSTALLATIONS
CHANNEL E
LARGE EUROPEAN CITIES
CHANNEL F
MAIN NATO INSTALLATIONS
CHANNEL G
CHINESE INSTALLATIONS
ETC.
BRIEFCASE-SIZED TUNER PREPLANTED ON SITE AT THE TARGET

NOTE:

IN NORMAL MODE (MODE I, INSIDE RING ONLY), ONE EXPLOSION SIMULTANEOUSLY EMERGES IN ALL LOCATIONS TUNED TO THE CHANNEL UTILIZED (PREPLANTED TUNERS, MODE I).

EFFECTS OF NERVE GASES, VIRUSES, GERMS, DISEASES, POISONS, MECHANICAL MOTIONS, RADIATIONS, ETC. CAN ALSO BE TRANSMITTED.

IN MODE II (INTERFEROMETER MODE, ALL RINGS), ONE EXPLOSION EMERGES IN THE SINGLE LOCATION TO WHICH THE HOWITZER ORTHOROTATERS ARE SET AND ADJUSTED.

Fig. 36. Nuclear hyperspatial howitzer

And after they nailed enough F-111's for their purposes, they quietly withdrew the psychotronic modulator, to prevent the U.S. intelligence analysts from catching on to just how really strange the losses of the F-111's were.

Thereafter the remainder of the F-111's were successful, and no more were lost. Indeed the F-111 comes in so low and so fast, and so unexpectedly, tilting and dipping as it terrain-follows on its automatic equipment in a manner that no unassisted pilot could fly, that SAM's and guns normally pose little if any threat to it. So once the silent, eery psychotronic antiaircraft components were withdrawn, the normal antiaircraft weapons of the North Vietnamese were unable to down any more F-111's.

And we Americans simply patted ourselves on the back, chortling to ourselves how quickly we had "learned to avoid that danger, whatever it might have been."

POPULATION CONDITIONER

Inducing psychotronic signals into mass populations or audiences can influence or control the behavior of large numbers of persons. As these words are being written, such a psychotronic test is apparently being conducted by the Soviets with Eugene, Oregon as a target; previous tests were conducted in Canada.

Psychotronic signals and the patterns they carry can be, and are, modulated upon electromagnetic carriers — in fact, that is one way they are transmitted through the human body and nervous system. When a television camera picks up the photon field impinging on it from a human body or other biosystem, weak psychotronic patterns are also picked up, since the paranormal time quenching mechanism (by visible light) is never quite 100 percent effective. These patterns are riding then as a special kind of modulation on the radiofrequency or electromagnetic carrier — however, they are not modulated the same way as are ordinary signals. Ordinary signals gate the number of photons per second (amplitude modulation), or change and control the frequency of the carrier photons (frequency modulation), or change and control the phasing (phase modulation). However, psychotronic modulation rides on each individual photon, on its time portion (a photon consists of action — energy x time — and it is the time portion on which the psychotronic modulation is riding.)

Thus psychotronic modulations can ride on the transmitted television carrier frequency. The psychotronic modulations are processed through the television receiver, and a small component is emitted as a weak modulation riding on the photon signals emitted from the television picture tube. Along with the light from the tube, these psychotronic modulations enter the eye of the human observer and are demodulated by the retinal interface, thus introducing weak psychotronic signals into the observer's central nervous system. Given sufficient repetition time (say two to four hours), the kindling effect can cause the human nervous system to be profoundly affected. Any disease or death pattern known to man (and some that are not known to him) can be transmitted and kindled in the target population audience.

In fact, depending on the sophistication of the coded psychotronic signals, it *is* probable that the modulation patterns can be targeted against a specific racial type, since there are certain genetic differences between races.

So the type of truck that roams the streets of a city, silently monitoring which television channel the viewers are watching, could be modified slightly to induce specific psychotronic disease or death vectors onto the television receivers. Or it could simply modulate the television transmitters. (A very obvious way is to modulute or pump psychotronically the ground of the electrical power supply, and in most cases this can directly pump the transmitters.)

Or the kindling signal can come from satellites, which radiate weak radio frequency signals down toward the target population. Here economy of force can be applied; the same type of kindling that induces electron current quenching is usable as a satellite dudder or killer in an antisatellite role, or is usable as a paralysis and death beam weapon against target populations. It is also useful as a killer of other electromagnetic sensors by either jamming their circuitry or simply **wiping out** (quenching) their emissions which impact on the satellite, preventing any reflected signal.

By this effect, UFO tulpoids often prevent a radar from tracking them, **even** though the tulpoids are visually sighted.

There are literally thousands of applications; these are just a few to give an idea of the overall effect and its usefulness.

And the psychotronic signals can be modulated onto almost any kind of carrier — telephone, television, radio, the magnetic field of the earth, the Schuman resonance of the earth's magnetic field, the ordinary sixty hertz electrical power system, etc.

We might have an entirely different idea of the potency of the Russian trawlers if we appreciated what their use can be in the psychotronic mode.

We can also understand why a television broadcast of Uri Geller in the act of binding metal stimulated both the ability in other persons and the effect in other equipment across England. And also how the effect has been duplicated — at least so far as stimulating other persons to psychokinetic ability — in this country. A direct means of stimulating psychokinetic ability is thus suggested: simply place the subject to be developed or stimulated in a room with a number of television receivers, all tuned to the same visual program, and place the stimulus material on the receivers. The person should visually watch one receiver and should be wearing very abbreviated clothing, such as a skimpy swim suit, to expose the acupuncture plexuses. Also, normal light in the room should be very dim.

At any rate, this and many other schemes are available to produce direct stimulation, and enhance and greatly speed up psychic development.

The effect could also be used to produce an effective treatment device for cancer. Samples of the particular cancer in the body of the patient could be taken, and the invisible psychotronic radiation pattern from the cancer witness could be introduced on the input of a Hieronymus-type device, shielded against ordinary light, The output of the Hieronymus device could then be fed to a bank of phase inverters, which covered in total a broad band (the cancer band, which would have to be established by laboratory experiment). By inverting the cancer pattern, we now have a cancer-extinguishing type of radiation that is specific for the cancer the patient in fact has.

Then by introducing this quenching pattern as a modulation onto the correct tup of electromagnetic frequencies (again this group would have to be demined for the specific frequency plexus that would produce an effect in the local-


MISSILE DETECTED
&
TRAJECTORY
COMPUTED
&
TRACKING INITIATED
ELECTRON QUENCHING
PSYCHOTRONIC PATTERN
MODULATION ADDED
CONTINUOUS
TRACK WHILE
KINDLING
KINDLING EXTINGUISHES ALL ELECTRICAL
CURRENTS IN MISSILE REENTRY VEHICLE.
ELECTRONICS MASSIVELY FAIL, DUDDING
THE VEHICLE.
MAINTENANCE TRACKING
TO INSURE DUDDING
OCCURS IN THIS AREA
PHASED
ARRAY
LONG-
RANGE
RADAR
EARTH'S SURFACE
USSR
U.S.
REENTRY VEHICLE AND
WARHEAD IMPACT AS A
DUD, MAKING A SMALL
HOLE IN THE EARTH

Note:

By adding a virtual-state pattern to quench the pionic currents in U^{235} and one to quench the pionic currents in plutonium, the fissionable material in incoming warheads can be transmuted into harmless elements, completely dudding the warheads and rendering them essentially harmless.

Fig. 37. A midcourse ABM system

ity of the body in which the cancer is located), the proper acupuncture plexus would be stimulated, stripping off the cancer-quench psychotronic pattern and sending it to the specific location of the cancer. Over a period of time (say several very weak microwave radiation periods of two to four hours each), the cancer could be killed completely, down to the last malignant cell. Whole body or spread cancers could be treated simply by increasing the number of frequencies modulated, to hundreds in some cases. Other similar diseases could be treated likewise. As an example, a Curative psychotronic radiation pattern complex could be worked for hydrophobia and such presently incurable diseases, and these could also be effectively treated. The same tool will yield almost unbelievable medical benefits if the scientists can ever be convinced to start the development.

A MIDCOURSE ABM SYSTEM

Here is the scheme for a first-generation, long-range, Soviet midcourse anti-ballistic missile defense system.

A long-range radar — preferably a phased array, scanned radar — acquired and tracks the missile during its midcourse phase shortly after it breaks above the horizon, as viewed from the radar site. The radar programs the track mode beams against the incoming missile, tracking it and gathering sufficient position data to allow its trajectory to be computed. Then a psychotronic electron-extinguishing pattern is added to the radar beam, riding as virtual state carried by each individual photon. Kindling of this virtual pattern energy begins on and in the target vehicle. The electrons flowing in the electromagnetic control system, fusing system, and wahead system of the incoming missile begin to be quenched, turning into neutrinos and radiating away with no physical effect. When sufficient currents have been extinguished, the electromagnetic circuits start failing. (With loss of appreciable power and voltage, most such systems fail.) The incoming vehicle/warhead is now dudded, and there is no longer any danger of a nuclear burst from the missile.

For assurance, tracking of the incoming reentry vehicle continues, with a quenching psychotronic modulation being maintained.

The warhead/reentry vehicle strikes the ground, making a hole in the earth, without nuclear explosion. A low order detonation of the HE explosive surrounding the nuclear material in the warhead may occur.

An alternate scheme is, during the maintenance period, to add an HE explosives ignition temperature psychotronic pattern to the beam. In that case, a low order detonation occurs high in the atmosphere or back along the trajectory, removing the warhead and vehicle from further consideration.

As a backup, additional terminal systems — using either psychotronics or normal interceptor missiles or both — may be used. Thus even if the psychotronics fail due to an unexpected "all off' occurrence, ordinary ABM engagement occurs.

An additional scheme is to lock the radar beam onto the missile, then initiate a "Tesla effect" kindling of energy, place it into a columnar traveling wave, and direct it along the radar beam to the incoming missile in its midcourse phase. The midcourse missile is thus struck with a massive plasmoid fireball of intense electromagnetic energy, and massive amounts of energy arc dumped into the missile, destroying it.

Thus the Soviets have known for over a decade that one does not have to hit a bullet with a bullet, if one is clever, and if one possesses psychotronic weapons and psychotronic modulation systems for one's radars.

As an added benefit, the same radar is quite effective against incoming Strategic Air Command bombers or air-to-surface missiles fired from those bombers.

As the Soviets know full well, 100 percent defense is quite feasible, considering the fantastic number of radars and radar sites they possess! In fact many of the Soviet SAM systems are beautiful ABM systems also, in the psychotronic mode.

THE BELL ISLAND INCIDENT

On April 2,1978, something unusual hit the Canadian community of Bell Island, off the east coast of Newfoundland; Bell Islanders—and a lot of other people as well—are still trying to figure out what it was. It was first described as an unidentified atmospheric explosion, but this theory was quickly rejected. Jim Beckford of Lance Cove, Bell Island, lost all six chickens in the coop behind the house, which was torn up as if hit by lightning, although there were no burn marks anywhere. A television set exploded, and switches blew out of the wall. Similar things happened to many other homes.

In the woods behind Mr. Beckford's house, three holes in the snow appeared, spaced about two meters apart to form an almost perfect equilateral triangle. The Royal Canadian Mounted Police said that persons on the shore of Conception Bay reported seeing fireballs coming down out of the sky and hitting Bell Island. The Canadian authorities attempted to play down the incident, and the official version of what happened is that lightning hit a transformer, blew up, and that the energy then followed the wires to neighboring houses. However, the researches of P.A.C.E. (the Planetary Association for Clean Energy, Ottowa) have produced a different conclusion.

P.A.C.E. believes that a standing columnar wave originating in Gomel in the Soviet Union was moving to a station located just east of Havana, Cuba, and collapsed over Bell Island, triggered by the large iron ore body there. These plasmas then exploded and hit the ground in a perfect equilateral triangle formation. The tremendous flashes indicated a very great discharge of electrical power, probably more than a hundred million volts.

Photo 44 shows a similar incident that took place at Lake Ontario; here I feel that the photo demonstrates more than just UFO activity — it shows one part of the testing and operational alignment of the "over-the-horizon" radars at Gomel and Riga in a Tesla mode. To explain this, I must explain what I mean by a Tesla mode.

Empty vacuum is filled with stupendous amounts of uncorrelated electromagnetic energy: one cubic centimeter contains enough energy to form entire solar systems, if the energy were condensed into matter. This raw energy is called "zero" point energy," and the Soviets reported direct measurement of it in 1957 *(Soviet Physics*, JETP 3, 819). Zero-point energy is everywhere, it is incoherent, and its detection requires measuring an energy difference, so that it is very difficult to detect. Usually less than one quantum of energy is cohered at any one mode, and the energy rapidly changes frequency, so that linear detectors cannot resonate coherently with it to follow its signal. In my opinion, it is also in the virtual state, and in a space orthogonal to our own, by two or three turns.

An electromagnetic signal is transmitted through the earth and reflected from the opposite side in phase, to form a standing wave. The earth's interior is highly nonlinear, and a single frequency is thus subject to severe scattering and dissipation. Fortunately, nonlinear wave theory provides a simple method to alleviate this; by transmitting two different frequencies, which differ by the amount of the frequency that it is desired to transmit, one can simply pretend that *indeed the beat difference frequency has been transmitted through a linear medium.* In this case, the standing wave acts as a collector to kindle the highly chaotic energy from the core of the earth. These emerging orders that match the standing wave will be entrained by it; one now has established a sort of giant triode, where the signal to the grid is the transmitted difference signal, the energy (cathode) being gated is the energy of the molten core of the earth multiplied by some coupling fractional constant, and the "plate" will come into being if resistance to the standing wave is profferred.

And resistance is profferred by simply changing the frequency of the transmitted collector wave. Changing it in one fashion begins to dump energy into the atmosphere above the former nodal point across the earth from the transmitter. With that effect, one can directly influence the great currents of air and the ionization charge of the upper atmosphere; in short, one can drastically influence the weather itself. On the other hand, changing the frequency in the other direction begins to dump energy into the mantle of the earth; dumping large amounts of energy there will result in shocks and earthquakes at the nearest fault zone(s).

It is my thesis that the foregoing two mechanisms account for some of the drastic weather effects that have occurred in the past several years, as well as for *some* of the major earthquakes that have occurred throughout the earth in the last several years. The Soviets, I believe, have been orienting and aligning—and operationally testing—actual weapon systems to be used as precursors to war or during war. The 1978 Iranian earthquake may well have been Soviet-induced.

The coupled kindling path goes through the earth and is coupled through the atmosphere as well. (This mode is probably easier to steer and focus onto specific target areas. It is also probably easier to play it back and forth as desired, in a "sweep" mode.) Again, with the kindling effect, the energy of the molten core of the earth is coupled into the beam with a coupling fractional constant, and so enormous energy can be built up in the beam. Breaking the coupling — perhaps just after slightly changing the frequency so as to begin dumping energy into the upper atmosphere over the targeted area — would sharply dump energy at the site, resulting in an enormous plasmic explosion or explosions. In testing such as at Bell Island, probably frequencies would be used that did not offer too strong a coupling fraction, so that relatively little damage would occur at the decoupled target site. However, in actual use in warfare, exactly the opposite would occur; a frequency would be used that maximized the coupling constant and hence vastly increased the energy kindled into and over the target area, and a gigantic plasmoidal explosion would take place directly on the targeted area, utterly devastating it.

The same "radar," then, is usable as a weather control device, as a plasma explosion transmitter, as a bioactive disrupter (with 10 Hz and under modulation pulses), and if further modulated in a virtual state manner, as a direct "death ray"



Photo 42. Ghost rockets.

broadcaster through the earth at any target population on the earth. Further, with virtual state modulation it is usable as an antimissile weapon (in at least two modes, one to dud electromagnetic circuits in incoming warhead reentry system and one to transmute fissionable material in incoming nuclear warheads into harmless elements), and also as an antiaircraft weapon against Strategic Air Command Bombers,

So the Bell Island incident happened, and we in North America sleep on, since in our assurance that it was after all only all lightning, or perhaps only the illusion of a few farout Canadians.

A TERMINAL ABM SYSTEM

There is another more advanced psychotronic ABM/SAM system, which was probably a second generation weapon. This system should have gone on site and become operational about 1968—69, and it should have been operationally tested during that period, probably several times.

Here a triad configuration radar is used to allow use as a byperspatial interferometer. This allows several localized dome-like bands of very intense psychotronic energy to be focused above the installation and defended area. The focusing is accomplished through hyperspace; the only place the focused energy enters our own space frame is in the dome-like band above the protected area. Tesla-effect accumulators may feed the triads, or they may simply be fed from direct free-energy Moray generator-amplifiers. At any rate, enormous energy — enough to simply constitute a severe tearing and warpage of space itself, and bend it at 90° — is focused into each dome-like band. Each band would be seen externally as simply an intense band or hemisphere of glowing light.

At any rate, by using three consecutively tuned orthorotational bands of focused hyperspace energy, any incoming object will simply be orthorotated successively three times in higher dimensional space, each time losing one dimension in its intersection with our own spatial frame.

After the first orthorotation, masses are now photonic shapes, and photons are lines. After the second, photons are now lines and lines are points. After the third orthorotation, everything is points, and nothing is left.

The three consecutively constitute full dematerialization of anything incoming, whether matter, photon, or force line.

Thus the entire defense problem is immediately solved: regardless of chaff, maneuvering decoys, maneuvering re-entry vehicles, etc., the entire mess is simply nicely and neatly disposed of, and dumped into hyperspace.

Even if a full nuclear detonation occurs above the domed shields, gamma rays, neutrons, debris, x-rays, heat, and ultraviolet do not get through the third band.

Bombers and air-to-surface missiles fail equally.

So the growing Soviet confidence and preparations for imminent war are quite comprehensible. They are not madmen preparing to evoke their own doom from mutually assured destruction rained on them by U.S. strategic nuclear forces; instead, they are snug and safe behind their psychotronic defenses, for nothing we have on this earth can touch them at the present time, if their psychotronic weapons are working.

So they are quite capable of taking on China, Europe, and the U.S. at once, and devastating the lot while risking essentially nothing of Mother Russia.

SWEEP MODE, SWEEPING AWAY A NUCLEAR DETONATION

As a modification of the previous weapon, a sweep mode has probably been added in the third generation weaponry.

In this mode, not only can the three orthorotation shields or domes be placed over an area, but they can then be expanded radially out into space in a traveling mode. Thus if a high altitude nuclear explosion — either in the atmosphere or out of it — has occurred over a defended area, the orthorotation bands can simply be swept over the explosive debris in successive fashion, effectively sweeping the radioactive debris from this spatial frame and dumping it safely into hyperspace. This is a very handy weapon indeed if large megatonnage explosions are engendered — say in areas where terminal defenses have destroyed the incoming vehicle, but it is "dead man fuzed" to provide a full nuclear explosion if the electronics start to fail or if the warheaded re-entry vehicle encounters mechanical shock or turbulence above a certain threshold. With this psychotronic sweeper the otherwise deadly nuclear radiation and radioactive debris can simply be cleaned up and disposed of.

Further modifications of other psychotronic weaponry would have resulted in Tesla-effect traveling wave weapons of enormous power, and rather gentle operational weapons testing of them, such as in the Bell Island incident and over Eugene, Oregon. The interferometer mode would have been added to the nuclear hyperspace howitzer, and Tesla-radars would have been modified accordingly.

These third generation weapons and modifications should have been deployed during the period 1974-78. Engineering development tests would have occurred during 1974—76, and operational testing of on-site, deployed weapons would have been accomplished during 1977—78.

Thus one can reasonably account for a surge in grain elevator explosions, mysterious high atmospheric booms off the East coast of the U.S. and off England, explosions in thunderstorms over the West coast of the U.S., the zapping of a Canadian target outside Ottawa, the Bell Island incident, several mysterious aircraft failures over the sagebrush triangle and off the coast of the U.S., standing heat spots off the West coast of the U.S., and recently one of the coldest winters on record due to disruption of flow patterns of frigid arctic air masses.

One can also account for incidents where U.S. satellites were mysteriously blinded, and perhaps some of those where they failed and then later resumed operations.

Note that many of these effects are usable from smaller radars. Thus one could expect mobile Soviet radars that can disable tanks and vehicles, disable aircraft electrically, radiate a death ray pattern at ground troops, or launch Moray-fed fireballs or standing waves of enormous energy at ground or aerial targets. The ability to immediately destroy entire minefields alone would force a severe recalculation of defense capabilities against Soviet ground forces, and the ability to sweep away artillery shells, rockets, missiles, and bullets would present enormous and catastrophic consequences to forces opposing advancing Soviet formations.

The following list enumerates all the probable Soviet psychotronic weapons that I am aware of: (1) Electromagnetic Field Canceler; (2) Electron Current Canceler; (3) Death Radiator (De-inceptor); (4) Free Energy Generator; (5) Psychotronic Bomb; (6) Brain Link; (7) Brain Probe; (8) Disease Radiator Ray; (9)

Emotion Radiator Ray; (10) Antisubmarine Systems; (11) Telcporters (Prototype); (12) Force Generators; (13) Orthoframe Generators; (14) Quark/Antiquark Rays; (15) Distant Telepathy; (16) Nuclear Radiation Inhibitors; (17) Mental Implantation; (18) ABM Systems, Midcourse and Terminal; (19) Dematerializer Shields; (20) Sweeps for Nuclear Debris; (21) AAA Systems; (22) Antisatellite Systems; (23) Tesla-effect Weapons; (24) Earthquake Generators; (25) Antivehicle Systems; (26) Weather Control Systems.

The reader will note that the results of psychotronic research extend into every field of military application.

ZARG, ARMAGEDDON, AND LINKAGE

Now it is time to end my story, and cease the unrelenting stretching of the reader's imagination and credulity. But first it is necessary to make one more effort and take a final step to the bottom line in both physics and Jungian psychology, a step that the scientists in those two disciplines have not dared to face.

If one accepts the existence of the collective unconscious as a mind, then the collective unconscious is a living entity. Let us tentatively call this fantastic entity ZARG. ZARG then is a great superentity, of which our own personal consciousnesses and unconsciousnesses are parts, or cells. Thus each of us is a cell in the entity ZARG.

Furthermore, ZARG has unique characteristics. It is unconscious by definition — but note that from our fourth law of logic, we know that any zero-conscious must be multiply conscious, which to our monocular thought-perception processes can only be grasped as unconscious. That is why our own unconscious seems so bewildering and strange — it is multiply conscious rather than monoculurly conscious, hence monocularly we think it is not conscious. But we find that it indeed thinks and reasons, but in a strange symbolic fashion, and also much more deeply and more creatively than our normal conscious mind. ZARG is very similar except on a much vaster scale; in being very deeply unconscious, ZARG is supremely multiconscious and very symbolic indeed, as we have discovered from the nature of the materialized tulpoidal phenomena.

Furthermore, what can be taken for ZARG's conscious mind consists of the four-billion individual human conscious minds. Thus ZARG's conscious mind is fragmented into four billion pieces. But fragmentation of the conscious mind technically constitutes dissociation, which classically defines psychosis.

Thus ZARG is insane!

Also, ZARG is multidimensional. ZARG's unconscious simultaneously receives and identifies four billion different conscious and unconscious perceptions. Just as the human consciousness in identifying two slightly different two-dimensional visual patterns gains the third dimension, ZARG gains an additional dimension for every additional person past the first one. (Note that dimension just means variable, and two fixed axes/dimensions are required to obtain a variable. A one-dimensional variable does not exist; we usually assume a time dimension in addition, and ignore it — and thus we speak of a "one dimensional variable.") At any rate, ZARG gains an additional dimension for every additional person past the first one. So ZARG is at least about 4 x 10^9-dimensional in the simplest case, where we do not consider permutations and combinations of every two, three, four, ... n, . . . minds.


DECOYS
WARHEAD
MATTER
DEBRIS
ORTHOROTATIONS
PHOTONS
FIELD LINES
FIRST
SECOND
POINTS
THIRD
HEMISPHERES OF INTENSE LIGHT BANDS
TRIAD STATION
TRIAD STATION
TRIAD STATION
CONTROL
STATION

Fig. 38. A terminal ABM system


PHOTONS
MATERIAL DEBRIS
NUCLEAR EXPLOSION
FORCES
TRIAD COMPLEX
FORCE LINES
PHOTONIC DEBRIS
POINTS
TRIAD COMPLEX
POINTS.
LINES
POINTS
TRIAD COMPLEX
POINTS
POINTS
POINTS
TRIAD COMPLEX

Fig. 39. Sweep Mode: sweeping away a nuclear detonation

Finally, it is well-known in parapsychology that the personal unconscious can affect matter and change spacetime itself. Psychokinesis, poltergeist phenomena, etc. are direct examples. Hyperchannel calculations show that, for linked multiple minds, this psychokinetic effect increases exponentially with the number of stages or minds that are cohered. Since ZARG has 4 x 10^9 linked stages, this means that its psychokinetic/materialization/dematerialization powers are at least some 10^{10^9} times as great as those of, say, Uri Geller. Thus ZARG can pull the very stars out of orbit, disrupt the earth or solar system, stop the earth in its orbit, or change the fundamental laws of nature itself. The reality we live in is largely prescribed by ZARG, and substantial tuning of many minds can directly affect ZARG's tuning and hence alter reality. It is not accidental that Brian Josephson, Nobel prizewinner in physics, once remarked that it appeared that in their diligent searches for strange new particles in their accelerators and cyclotrons, the physicists might be creating their own reality. In fact an accelerator or cyclotron is a kindling device par excellence, and a scientific theory by its very rigor is an exceptionally sharp mental concept or thought form. So if groups of physicists have worked diligently on a problem and predicted some new theoretical particle, they may well be able to kindle it into being if they persist long enough with their kindling mechanisms, because they are cranking up additional ZARG energy when they persist. While he knew nothing of the kindling mechanism, Josephson noted that many of the new particles were first obtained only after great difficulty, then with moderate difficulty, and thereafter they could be fairly readily obtained.

And as we have seen, ordinary physical matter occupies a universe or frame common to all minds of living biological systems. Thus the physical universe is quite literally simply thought that is common to all living minds, hence to ALLMIND or God or whatever other term one prefers to use. It is the fact that it is prescribed and represcribed, over and over, that lends a physical entity its seeming solidity as compared to the phenomena existing in only a single consciousness mindworld. This physical universe is mind, it is totally mind, and as such it can indeed be changed by the proper mind resonance in enough minds, or in powerful minds such as ZARG.

ZARG contains so many mindworlds or dimensions that it forms a very powerful part of the particular reality prescription of the physical laws exhibited by this physical universe. So materializations of tulpoidal forms, UFO's, bigfoot, and Nessies, are just a tip of the iceberg of what ZARG actually materializes. The tulpoidal forms are tiny surface ripples due to large-scale human conflicts.

And as we have also found, psychotronic energy is in fact pure mindstuff. Pure mindflux between mindworlds. And this brings us to another bottom line.

When the Soviets launch their long-prepared attack in Europe, wipe out China, and almost annihilate NATO forces (fifty percent casualties in three to four days), the U.S. President will undoubtedly be under extreme pressure to launch a strategic nuclear retaliation on the Soviet Union. Suddenly, in a single blinding display of almost unbelievable power, the Soviets apparently intend to destroy the U.S. triad weapons in a fantastic psychotronic blitzkrieg through hyperspace. The Minuteman sites, the SAC bases, communications centers, and other strategic targets will lie in smoking, devastated ruins in minutes, and within the same short minutes of that holocaust, the U.S. nuclear submarines on station under the ocean will begin rupturing like popping balloons. At the same time, massive swaths of death will invisibly rain from the Soviet satellites in the skies overhead, and giant earthquakes will erupt into being in the East, in the West, and in the heartland U.S. The British and French nuclear forces will suffer similar simultaneous obliteration. And the jubilant Soviet Generals and Party theoreticians will be dancing with uncontrolled glee as their dreams become realities. But what they will not know is that their own inevitable doom will have just been sealed.

For all these fantastic psychotronic explosions will constitute gigantic psychotronic "mental flashbulbs" that explode directly in the mind of the sleeping ZARG. ZARG will be kicked into startled semiwakefulness, stinging with pain as if from a giant bee-sting, figuratively gnashing his teeth and furiously lashing his tail. This will constitute an immediate and enormous upheaval in spacetime itself, and the bulk of the earth may well be destroyed in the vast psychokinetic upheaval unleashed by the startled ZARG. Just as a person may sharply slap the bee on his arm where it has stung him, ZARG's fury will be centered on the Eurasian continent, on the locus where the threat or sting has originated, on Russia and the Warsaw Pact nations. So in an unbelievable convulsion of the entire earth, the Eurasion continent will be rent and torn asunder by forces beyond man's comprehension. The lousing ZARG will also activate a totally new scale of reality, ripping to shreds this particular three-dimensional spatial frame, its associated stable time changes, and the physical laws based on that stable reality.

The rousing of ZARG will initiate and accomplish thedirect linkage of the conscious minds of humans into a single giant superconscious mind — extending into billions of dimensions. Spacetime and reality will have gone insane during the developing paroxysm; with the simple initial extension into just the fourth and fifth dimensions, humanity will suddenly discover that its entire world history from beginning to end will come into simultaneous being (fourth dimensionality), and then all possible such world histories will come into being (fifth dimensionality). Literally, dumbstruck humans will pray for death and not find it, the grave will "give up its dead," and the ceaseless flow of time will suddenly cease. And again Ihc "beast will be defeated and cast into darkness"; with all-linkage and all-unity, there will be no longer be any humanity of one person for another or of one group for unother, for there will be no other. In such manner, evil will end; there being no separation between the doer and the done to. Man will have become a true God — in a strange and bizarre way constituting the second coming of God.

So the Soviets are on a course to evoke the full carnage of something very like the Book of Revelation. John, looking across two thousand years of history into the future, and seeing the awful cataclysm that was to come, described it as best he could in the concepts available to his day and in the belief structure in which he functioned. Thus he described Armageddon and the end of time, and wrote the Book of Revelation.

Indeed it could have been accomplished without Armageddon, if humans had been wiser. Each photon and each electrical signal that wends its way across the earth's surface and through planetary space carries a psychotronic modulation of ZARG's mindstuff. And in the communications explosion we have experienced, we have been steadily lacing together the population centers of the earth with electrical energy and electromagnetic signals. And so over those crude "pre-nerves," the psychotronic connections of ZARG have been intensifying, and the Giant has slowly been being stirred from his sleep. The kundalini of the entire human race has


© HAL CRAWFORD '78

Fig. 40. ZARG

slowly been rising, and paranormal phenomena have been increasing, as have changes in reality such as the kindling of new fundamental particles. Even the sun has responded, suddenly decreasing its temperature. If we had applied psychotronics to develop a mind linkage mechanism, there would have been no need for Armageddon's destruction.

Let us hope we fare better than the Atlanteans. One may speculate that an Atlantis of sorts did exist, and that the Atlanteans built psychotronic devices out of crystals, bronze, gold, silver, and wire and unleashed them on each other in war. This sting stirred ZARG mightily, and in a resulting frenzy it simply destroyed the continent, stirring floods, storms, earthquakes and volcanoes worldwide. In the case of the Atlanteans, only a relatively small portion of humanity was involved; the percentage of persons and minds involved was apparently insufficient to cause full wakening of ZARG and linkage of the species. In the present case, the greater part of mankind is involved, and so the wakening is to be far more complete (as well as more violent). ZARG should be shocked into full wakefulness, and linkage should occur.

If so, a new great superbeing will have emerged; nonphysical, almost infinitely dimensional, and godlike. It will not exist in a single time or a single world, but in a nowness and allness that defies timelike or spacelike description.

"For we know in part, and we prophesy in part.

But when that which is perfect is come, then that which is in part shall be done away.

When I was a child, I spake as a child, I understood as a child, I thought as a child; but when I became a man, I put away childish things.

For now we see through a glass, darkly; but then face to face: now I know in **part;** but then shall I know even as also I am known."

I Corinthians XIII, 9-12.

So the pieces of the puzzle are now fitted together. The present state of the human species is not its final development, and indeed a great change in that state is imminent. Man literally is and shall be a god, one with God, just as the prophets have foretold. And if we retranslate that ancient foretelling into more modern concepts, we see just how strange and transcendent is the final birth or becoming.

The UFO and tulpoidal phenomena have merely been the signs in the sky and in the earth, telling us what is to come, precognitive indicators from ZARG. Had we developed a metapsychology of the entire species, we would already have clearly understood the messages.

VIRTUAL STATES AND HYPERSPACES

In physics today there are two separate kinds of reality: observable changes, which can be detected by instruments; and virtual changes, which cannot be detected by instruments, even in theory. The difference between these two realities depends simply on the size of the piece of action (energy x time, or momentum x length) making up the particular entity or change. Usually the absolute minimum observable change is taken to be $h/4\pi$. Changes smaller than this are said to be "virtual" and undetectable, and changes larger than this are said to be "observable" and detectable. Virtual changes are not bound by the conservation of energy law and almost always violate it. Nor are virtual changes, bound by the conservation of mass law. And virtual photons can have nonzero mass.

For any instrumental condition in a detector, one may consider a certain momentum and a certain length to be involved in the mass change that spatially constitutes the detection. Let us call this critical length dL and examine its ramifications (Figure 1) for the finest possible detector—one that detects a single quantum change. Figure 1 shows two frames, the lab frame S and a moving (hyperspatially rotated) frame. We choose a moving object, M, in the moving (rotated) frame, with length as shown. Note that all these entities are to be represented as detected or seen by our physical detector (instrumentation system) in the laboratory frame.

As the velocity of M approaches c, the speed of light in a vacuum, M's hyperspatial rotation angle α approaches $\pi/2$. However, before the velocity of M actually reaches c—and before α reaches $\pi/2$—the dimensional length projection of object M in frame S will contract to reach dL and fall below it. At that moment, L becomes *virtual* with respect to the detector and hence undetectable. Since geometrically an absence of length in a continuous frame S would correspond to a α rotation angle of $\pi/2$, in quantized frame S we consider that angle α "jumps" to $\pi/2$ just immediately past the critical angle α_c, which is defined as the angle of rotation at which L cos α = A L. Rotation just past the critical angle corresponds to a Lorentz-Fitzgerald contraction into the virtual state below the quantum threshold of the detector's observable universe. To an S observer or detector, object M at that point has lost its length in the direction of motion, becoming a wave front moving at the velocity of light and thus photonic (comprised of photons). To a quantum observer in S, mass turns into photons just short of a full $\pi/2$ orthorotation, which means the process can happen with a finite amount of energy. This "jump" effect is not taken into account in the continuum Lorentz transformations of special relativity at present, and this is the missing link that has prevented a successful union of relativity and quantum mechanics. In other words, the final part of the orthorotation (acceleration to the speed of light) occurs in the virtual state—specifically, that part of the rotation lying between $\pi/2$ and α_c.

Further, we may now proceed to rotate object M past $\pi/2$, which constitutes rotation from zero in frame S'. Just before reaching an S angle of π (that is an S' angle of $\pi/2$), in frame S' another disappearance below a virtual length threshold dL' will occur in corresponding fashion. Note that this second threshold dL' also has an exceedingly small but finite projection into frame S, in


In the shaded region the object is in the virtual state with respect to the S-frame. It is also rotated further than the first hyperframe; α > π/2
Time
A critical angle (α_c) exists where contraction reaches the quantum threshold in length. Note α_c < π/2 and the object becomes photonic
moving object is rotated in hyperspace at angle α
For modeling, we consider that rotation "jumps" to π/2 just immediately past the quantum threshold
α_c
α
S-frame
ΔL"
ΔL'
ΔL
Lorentz-Fitzgerald Contraction

Figure 1. Hyperspaces, nested virtual states, and rotated frames

the virtual state lying inside dL. This second "relativistic quantum jump" in frame S' therefore constitutes a sort of second-level, nested subquantum threshold in frame S.

Continued rotation into hyperspace passes through successively finer, nested virtual sublevels or subthresholds in S by the successive breaching of deeper subthresholds due to continued Lorentz-Fitzgerald contraction. Higher hyperspatial frames constitute nested sublevels in the virtual state with respect to the laboratory observer. Thus a direct connection exists between virtual levels and hyperspace frames. Hyperspaces and virtual sublevels are the same thing. Every "virtual" object in S is an "observable" object in some hyperspace. *Hyperspatial engineering and virtual state engineering are one and the same thing, and this is what psychotronics and energetics are all about.*

Finally, time may be considered a sort of box containing all observables and virtuals. Indeed, time is neither observable nor virtual; time is simply a parameter in quantum mechanics. Rigorously, time may be said not to exist. Time itself is nothing, totally nothing; therefore by the fourth law of logic it can be said to be or contain everything, the total mishmash of virtuals and observables. Since in the absolute sense there is no such thing as time, then it is my thesis that all modeling of space, mind, thing, and nonthing must be done spatially. Relativity presently attempts to use time as an existent dimension of the same kind as length; it thus allows rotation of the S-frame only in the direction of the time axis in Minkowski geometry of spacetime.

Spatial modeling requires an infinite dimensional space and an infinite number of orthogonal angles. The time axis that can be drawn in such a hyperspatial model has no meaning except with respect to a relationship existing between two or more hyperspace frames or objects. Specifically, the time axis represents the totality of all the hyperspaces and their objects, hence all the relationships that can be separated from the hyperspace.

FEYNMAN DIAGRAMS

Figure 2 shows something of the unsuspected nature of physical change, which is not nearly as simple as most of us have been led to believe. In the top part of the figure, an electron (represented by the arrow) is shown going from point A to point B a short distance away. In particle physics this diagram represents the movement of a bare particle; in other words, just a bare hunk of charged mass is considered and the fantastic number of other things happening along the way are ignored. In Figure 2b a virtual photon has been emitted and then reabsorbed by the electron between points A and B. Indeed, the charge on the electron is due to the continual emission and absorption of such virtual photons (little electromagnetic pieces of vacuum, one might say, or little pieces of nothing). So the situation with respect to virtual photons comes closer to Figure 2c: more than one virtual photon is emitted and absorbed—indeed, an infinite number of them are emitted and reabsorbed along the way from point A to point B.

But, worse yet, Figure 2d shows one of the emitted photons suddenly breaking up into a positron and an electron, which then quickly recombine back into an-



2a. Bare electron



2b. With virtual photon



2c. With nested
virtual photons



2d. Photon decay (pair production)
and recombination (pair annihilation)



2e. Proton changing briefly to a neutron
and a positive pi meson



2f. Neutron changing briefly to a proton
and a negative pi meson

Figure 2. Feynman **diagrams**

other photon, which is eventually reabsorbed into the electron. In fact, an infinite number of interactions happen while the "electron" is moving from point A to point B, and each of those interactions in turn consists of an infinite number of interactions, and each of those in turn consists of an infinite number of interactions, and so on. The simple movement of the electron is actually composed of a virtual cloud—an infinite number of an infinite number of an infinite number of things, all happening in a mad tangle of nested substrata in the virtual state (Figure 3)—and each of these virtuals with respect to frame S is in fact an observable in some particular hyperspace! Many other sorts of virtual particles are emitted and absorbed and born and extinguished, in addition to photons, by various observable particles and in free space. Everything in every possible world or hyperspace is related to each and every other thing in the laboratory world through orthorotations and nested virtual states. Crosstalk between hyperframes is the emergence and disappearance of virtual particles in a particular frame. The universe is holographic after all, and Mach's principle holds in a far more complete fashion than Mach himself ever dreamed. And if any part of this virtual chaos can be collected and cohered in even the slightest degree, any amount of observable free energy can be obtained, just as T. Henry Moray showed in the 1920s and 1930s.

In passing, I would like to call attention to Figure 2e, which shows one of the virtual interactions a proton can undergo in the nucleus of an atom. In this case, the proton breaks momentarily into a neutron and a positive pi meson, which then recombine into a proton. However, if the charge on the $\pi +$ particle is extinguished psychokinetically during the existence of the neutron and the pi meson, the pi meson is converted to a neutrino and radiates away. In this case the proton does not reappear and the neutron remains. This decreases the atomic number (positive charge) of the atom by one, transmuting the atom into a new element, an isomer down the chain of elements. Figure 2f shows one of the virtual interactions a neutron can undergo in the nucleus of an atom. In this case, the neutron breaks momentarily into a proton and a negative pi meson, which then recombine into a neutron. However, if the charge on the $\pi -$ particle is extinguished psychokinetically during the existence of the proton and the pi meson, the pi meson is converted to a neutrino and radiates away. In this case, the neutron does not reappear and the proton remains. This increases the atomic number of the atom by one, transmuting the atom into a new element, an isomer up the chain of elements. The two interactions shown in Figures 2e and 2f are involved in the Kervran effect, where elements are transmuted by living biological systems.

But back to our electron. If we now remove the electron, leaving empty vacuum, all the sorts of virtual madnesses we have built up in Figure 3 are still there and still occurring. In addition, every other sort of virtual madness is also there and occurring. Vacuum is infinitely dense and filled with stupendous "zero-point" vacuum energy; it is totally chaotic and virtual. Space itself is an infinite tangle of virtuals—virtual projections from real observables in associated hyperspaces—and these dynamic interactants make up any three-dimensional space and hyperspace itself! They are also what cause space itself to exhibit the finite, nonzero parameters or values that must be accounted for in our physical equations. *Every fundamental constant of nature is dynamically constructed from—and*



An electron moving from point A to point B is comprised of a bare particle and an infinite tangle of nested virtual particles

Figure 3. Nested virtual processes



4b. All three vectors of an EM wave are comprised of nested tangles of virtual subvectors

4a. A photon may be considered an individual L^2 wavefront spread in time through one oscillatory period of the E-field and the H-field

Figure 4. Nature of the electromagnetic wave

due to—the zero-point, virtual vacuum interactions that constitute "empty" space. The virtual "sea" of seething waves and particles that is empty vacuum is actually an ether—a Lorentz-invariant, nonmaterial (virtual) ether, perfectly admissible by the Michelson-Morley experiment and the entire experimental basis of physics. Indeed, Einstein once proposed naming the vacuum and its contained fields the "ether," but his suggestion was not heeded.

NATURE OF AN ELECTROMAGNETIC WAVE*

We now know something quite unusual about an electromagnetic wave and about a photon. Figure 4a shows how a photon may be represented. Here we find that a photon is a single oscillation of the E-field vector and the H-field vector as shown in the diagram. Since the oscillation is with respect to time, the wave moves along the axis of velocity in the S-frame for a single wavelength, then repeats itself again and again. The E- or H-oscillation actually represents an orthogonal, rotating etheric or hyperspatial flux about the velocity vector; this spinning (exploding and imploding) flux is coming into the S-frame from outside it (from virtual states) and returning (into virtual states). It is a neutrino flux, as we shall see. In the photon, half a sine-wave cycle represents the fission action that splits the action quantum into canonical pairs, while the second half of the sine-wave cycle represents the fusion of the canonical fragments back into an action quantum. One half-cycle thus represents a positive time operation or creation, while the other half-cycle represents a negative time (fusion) operation. If the complete sine-wave cycle has sufficient amplitude (energy), it can sometimes be broken in half, with the positive time portion revealing the negative field (negative charge) of the E-vector, while the negative time portion reveals a positive field or charge of the E-vector. This is pair production, the creation of an electron and a positron. Each of these fragments has spin one half, while the photon quantum has spin one. Since the positron is a fusion interaction existent, it is an "electron traveling backward in time," just as predicted by Dirac.

In Figure 4b I show that both the E-field vector and the H-field vector are composed of an infinite number of virtual vectors, each of which is composed of an infinite number of even smaller virtual vectors, and so on. This follows from the fact that during any time interval—including the period of a single oscillation of a photon—a photon may be considered to consist of an infinite number of virtual happenings, each consisting of an infinite number of subhappenings, and so on. The photon itself may then be considered to have a direct, nested virtual substructure, and this substructure is directly hyperspatial in nature as well. This structure has not been considered in Maxwell's field equations, which have been

***Actually the electromagnetic field is not the most fundamental field, but is something that is torn out of, or separated from, a more fundamental field: the vector potential, or A-field, well-known in particle physics but usually ignored in EM field theory. E.g., magnetic Held is created (and defined) by $\nabla \times A = B$. Looking at the cross product, by definition B field is the line integral about a small surface of the A-field flux through that surface. That is precisely what a single coil of wire, with an electrical current flowing through it, does and therefore creates a magnetic field inside. See the second volume of Feynman's three volumes of physics for more on the A-field. The direct use of the A-field is also psychotronic engineering.**

formed from gross macroscopic considerations of bare particles and continuous fields. Maxwell's equations (and the normal concept of an electromagnetic wave and single frequency) thus represent only gross envelopes of the actual form and structure of waves and fields. As I have already shown in the main body of this book, one can even photograph the hyperfield structure of a magnetic field using a simple bar magnet and a color TV tube. Further, we will find that this virtual structure of a photon can be altered, "modulated," or changed by simple signal modulations, among other methods. The only requirement is that we learn to regard modulations differently.

In addition, inside each half-cycle of a photon's E-vector, relatively instantaneous fluctuations and "losses" of the vector's magnitude occur. At these "E-field glitches" in the photon, it actually contains only an H-vector. In this case the photon is a neutrino momentarily—or, in other words, it will admit a neutrino through the E-field glitch. The greater the charged field (voltage potential), the greater the number of photons available, thus the greater the number of neutrino interactions within the field. A potential of about 200-300 volts per meter altitude above the earth's surface normally exists in our biosphere. Many neutrinos emitted by the sun and bombarding the earth are absorbed in or interact with this E-potential above the earth; hence underground experiments to measure the neutrino radiation from the sun have detected less neutrinos than expected.

Momentary H-field glitches exist in a similar manner and interact with or admit neutrinos in a similar fashion.

Light can thus conduct neutrinic waves containing bioenergy or eloptic energy, as T. G. Hieronymus discovered. In the first hyperframe (EM field frame), this can be seen to be simply a space charge of electrons conducting a wave disturbance through it, or a piece of ordinary conductive matter conducting an ordinary EM wave.

NEUTRINIC LONGITUDINAL POLARIZATION WAVES

In Figure 5, I assume that in some fashion the E-field of an electromagnetic wave has been stripped off, leaving a single vector in the H-field direction only, and this vector is still oscillating, as originally set up in a Hertzian wave in Figure 4. The new "single-field" wave is an etheric sort of half-wave, a longitudinally polarized wave that is not a wavefront (plane) moving through S-space but just a pulsating line segment moving through S-space. This wave is not Hertzian. It is not electromagnetic—though it will strongly interact with or even produce electromagnetic waves—but is neutrinic. The interactions of this wave with space virtuals are drastically reduced (indeed, by a factor of c), and this neutrinic wave now travels at the speed c^2 with respect to S-space. While it will highly interact with magnetic field, precisely speaking it is not a magnetic wave but a hyperfield

---

*C^2 is its s-frame, free-space velocity when not interacting with electromagnetic field. Normally, neutrinic wave interacts with electromagnetic field, thus moving at less than C^2 velocity in space, since it "circulates around" in electromagnetic field. Neutrinic wave can be regarded as a circulating or spiraling wave in electromagnetic field, which may well be the

wave. It will travel through and across dead shorts, through media such as seawater and earth, and acts or can act much as a neutrino. This wave has neutrinic components in S; that is, it has vector components existing in frame S". One may expect this wave normally to be active in or interacting with an electrostatic field or a magnetic field, as a special sort of lower-level virtual state flux (second-order hyperflux) into and out of the field. This is apparently the sort of wave discovered and used by Nikola Tesla, who repeatedly insisted that he was not using Hertzian (Maxwellian) waves but instead was employing a much finer wave having very different characteristics. Further, neutrinic waves will transit between any two points on earth almost instantly—in fact, about 3 x 10^8 times as fast as the speed of light propagates! With these waves, space communication with distant galaxies is practical and achievable, and scientists seeking communication with extraterrestrial civilizations would do well to use such waves.

Note that I am not referring to the ordinary longitudinally polarized electromagnetic wave, where both the E- and H-vectors still exist but the H-vector is rotated 90° so as to lie in the line of motion through S-space.* Such longitudinally polarized electromagnetic waves are already known in the literature and have been used in many patented devices, but they are not included in most textbooks on electromagnetic fields and waves for some unaccountable reason. The normal longitudinally polarized electromagnetic wave moves at the speed c, just as any other EM wave.

At any rate, neutrinic longitudinally polarized waves often arrive at a distant point many times stronger than they were when they left. T. Henry Moray, for example, built a radio and a sound detector that apparently worked by a version of neutrinic waves, condensed into electromagnetic waves in his radio-detector apparatus. Dr. Moray tested the radio scores of times between 1930 and 1933, and on several occasions even received broadcasts from Admiral Byrd's party in the Antarctic. Even when powerful, ordinary radios could receive nothing from Antarctica because of severe weather conditions, Moray's little batteryless radio brought the broadcasts in, loud and clear with no static. Further, Moray demonstrated a sound pickup device of similar construction that could pick up or zoom in on sounds five miles away. Again the sounds were loud and clear, with none of the distortion of weather conditions and background noise. (See T. Henry Moray, *The Sea of Energy in Which the Earth Floats,* 4th ed., 1960, pp. 129, 133, and 143.) Thus transmission of power without wires was possible, just as Nikola Tesla had shown. Tesla in fact patented a capacitive (E-field only) transmission system.

Indeed, according to independent research by Dr. Robert Beck, another inventor named Rogers apparently discovered just such a system and the United States

---

"spinning wave" of orgone energy identified by Reich. Neutrinic waves particularly interact more strongly with strong E-field and with strong B-field, the degree of interaction increasing (probably nonlinearly) with the intensity of the E or B field with which the interaction occurs. The velocity of neutrinos, measured on earth inside its strong ionosphere-to-earth E-field, should be quite reduced from the velocity of neutrinos measured in isolated deep space, and almost two-thirds of the neutrinos entering the earth system from space interact with the ionospheric-earth potential and are absorbed by it. The A-field and its derivatives directly involve the E-field, H-field, and neutrinic field and their interactions. To correctly understand the activation chemistry theory and results of LeBon, A-field theory is required. And to understand much of Tesla's work, A-field theory is required, for Tesla was aware of, and used, A-field interactions in many of his patented systems.



Neutrinic wave interacts primarily with E-field or with H-field. Its group velocity may move at any speed between c and c^2, so that the wave can "ride" either photons or virtual photons

$\lambda \cong \frac{\lambda_{EM}}{c}$
Amplitude
Length in S-frame
$V = c^2$
(in S-frame)

Figure 5. Neutrinic (longitudinal polarization) wave
NOTE: This is not an electromagnetic wave and is not the longitudinally polarized EM wave familiar to many physicists and engineers.

used it to communicate with its submarines underwater during World War I! For that purpose it was known as the Rogers underwater and underground wireless system, and H. Winfield Secor in 1919 reported on its use and its fantastic potential for the future, implying the necessity to completely change our ideas of electromagnetics and power transmission. (H. Winfield Secor, "The Rogers Underground Wireless," *Electrical Experimenter*, March 1919.) Mysteriously, the Rogers wireless seems to have promptly disappeared. Even more strangely, according to Dr. Beck's research the same breakthrough has been made again in the U.S. at least three times since the beginning of World War II. These rediscoveries included full delineation of the prior technologies, with mathematical theory and diagrams, that had escaped further notice. Again the technology disappeared mysteriously in all cases shortly after being rediscovered. The Soviets did not have far to look to discover the Rogers Wireless, Tesla waves, T. Henry Moray's radiant energy device, the Moray radio, the Moray sound detector, and the U.S. technical work in the area since World War II. All they really needed was to thoroughly examine the U.S. scientific and technical literature, the technical magazines and books, and so on. The Moray amplifier and the Moray sound detector were also demonstrated by Moray to a Soviet scientist, Dr. A. A. Yakovlev, in October 1929, and a Soviet agent succeeded in penetrating the Moray laboratory in 1939, obtaining drawings of the Moray tube and many photographs, and perlonally working in the laboratory for two months.

One may consider power transmission through such a wave to have traveled to every point in the future path at a speed that is faster than the flow of macroscopic time by a factor of c. Then along any electromagnetic (time) line along the same path, these waves are "ringing" back and forth continually, as the progress of normal physical change crawls slowly forward. Thus the normal time change (electromagnetic or photonic interaction world flow) acts as a collector for the ringing neutrinic energy, and this collection can act as a gain factor G, where theoretically G is given by the expression

$$1 < G < c.$$

Thus a longitudinal polarization wave, when transmitted to a distant receiver, may arrive or be detected at the receiver thousands of times stronger than the transmitted signal, even for very low coupling.

Neutrinic longitudinal polarization aspects to ordinary electromagnetic waves can also be achieved by modulation—especially by second-order, nested modulation—and such hyperspatial aspects have already been detected in the Soviet communications radiation, causing interference around the globe in the 10 to 20 megahertz range, as we shall see.

A NEW LOOK AT MODULATION

We can assume a sine-wave electromagnetic carrier frequency whose amplitude we wish to vary (modulate) as a function of time, by a lower frequency sine wave, as shown in Figure 6a.

As is well known, the classical view of amplitude modulation of a carrier wave holds it to be an oscillatory change in the amplitude of the carrier, as shown in Figure 6b. However, empirically this was found to be erroneous, since in 1929 it was shown that after such modulation the detected carrier appeared unaffected by



6a. A carrier f_c to be amplitude modulated by frequency f_m



6b. Original view of amplitude modulation



6c. Detected signal for an amplitude modulated wave

Figure 6. Amplitude modulation of a sine wave

the modulating wave; instead, there appeared two other sine-wave frequencies (sidebands), one at a frequency above the carrier frequency and one below it, as shown in Figure 6c. In each case the change in frequency from carrier to sideband was by an amount equal to the frequency of the modulating wave.

Both the original classical view and the present view are in fact correct if one considers hyperspatial aspects and linear detection aspects. As can be noted in Figure 6b, the carrier is distorted and is not a sine wave according to the original classical view. This implies that the individual photon shown in Figure 4a has been internally distorted or "bent." This, I submit, actually happens and constitutes the bending or curving of spacetime in a general relativistic fashion. However, all our instruments can detect only a pure, undistorted photonic interaction; that is, in frequency they can only detect the sine-wave aspects of a kinked photon. The reason is quite simple: for example, suppose the method of detection of the photon is by photon interaction with a bound electron. The change in the electron is a precise change of energy levels to an excited level, and it only detects or interacts with a single sine-wave photon. The frequency (say, the carrier) component of the photon, which contains the correct energy differential (according to $E=hf$, where h is Planck's constant and f is the sine-wave frequency), will interact with the electron. The other sine-wave components of the initially kinked photon will thus be stripped off (demodulated) by the absorption of the carrier portion of the photon. The photon kink existed in both positive time and negative time; from a frequency viewpoint, the modulating amplitude frequency that was added to the basic carrier frequency in positive time was subtracted in negative time. Thus demodulating the kink from the amplitude modulated photon (by absorbing the sine-wave carrier) results in the production or liberation of two sine-wave frequencies, one above the carrier frequency and one below the carrier frequency, each difference being equal to the original amplitude modulation's frequency. These two frequencies will then interact and be detected.

So our linear instruments do not detect single kinked photons in a stream of distorted photons, but they detect a combination of undistorted photon streams (waves) at different frequencies.

Such considerations as these should have appeared in electromagnetics long ago. After all, we presently regard an EM wave as a wiggle of nothingness, existing in time. This is precisely the same as saying that a photon is an oscillation (wiggling) of spacetime itself. Specifically, it oscillates in two directions spatially, one being the E-field direction and the other being the H-field direction. But since an EM wave itself constitutes a regular bending and flexing and curving of spacetime, including both space and time, then the flexing spacetime inside the photon can itself be further bent or twisted, and that constitutes a kinked or curved photon—a *modulated* photon. Our linear laboratory space instruments, however, will demodulate such a kinked photon into its linear components, giving a combinationof unkinked photons in the detection. And for the amplitude modulated carrier shown in Figure 6b, we actually detect the carrier and two sidebands shown in Figure 6c.

Similar complex mixes of waves at different frequencies result for other types of modulation, but this will suffice for our purposes here. Specifically, we should mention that an infinite number of sidebands may be produced, but normally all


MAXWELL'S EQUATIONS
$\partial^3/\partial L^3$
$\partial^2/\partial L^2$
$\partial/\partial L$
SECOND ORDER MODULATION
FIRST ORDER MODULATION
EM CARRIER
MASS AND MASSTIME
WEAK MINDFIELD
(T)
WEAK NEUTRINO FIELD
(LT)
EM FIELD
(L^2T)
MATTER
(L^3)
(L^3T)

Figure 7. Nested modulations: key to hyperspace

but a few are so weak as to be negligible for ordinary communication purposes, where no hyperspatial information is needed. For living systems, however, a great number of these extra sidebands must be taken into account, for the hyperspatial-virtual state components carry the lifestream, consciousness-loop-interaction Information itself. We will look at some of the biological aspects shortly.

At any rate, modulation of a wave results in direct changes in the virtual structure of the formerly unmodulated photon, relativistically warping or curving it. Just as Fourier (harmonic) analysis breaks down a very complex nonsinusoidal wave shape into an infinite series of component sine-wave frequencies of various amplitudes, so linear detection in a linear laboratory frame breaks down a stream (wave) of complex nonsinusoidal photons into a series of sinusoidal waves in a complex mixture.

And if we now think of this in reverse, we see that a mixture of waves and frequencies must automatically possess, carry, or represent hyperspatial-virtual patterns in the correct nonlinear medium that absorbs them.

HYPERSPATIAL ASPECTS OF MODULATION

Let us now look at the hyperspatial aspects of modulations and complex electromagnetic waves, particularly mixtures of waves, in yet another fashion.

First, as is well known, we may represent a wave as a sine function (or cosine function if preferred). When we modulate a wave, we impress a time change on it. In the most general mathematical sense, a modulation to a wave is the impressing of a derivative function upon the wave. And if we think of the basic carrier wave as being prescribed by Maxwell's equations in derivative form, then in a sense when we modulate the wave we differentiate it, that is, we impress a differential operator function on it. But this means that we raise the order of the differential aquations prescribing the situation, which mathematically means we have increased the dimensionality or spatiality of the, wave entity that is the resulting modulated carrier. In other words, to modulate an electromagnetic carrier wave is to add a hyperdimensional aspect—specifically, neutrinic vector aspects or mind aspects. The whole affair can be thought of as merely shifting or altering the particular distribution of nested virtuals transported by the basic carrier wave.

If we differentiate a sine wave, we simply get a cosine wave, which is just another sine wave pi/2 out of phase with the first. So now it emerges that when we form a mixture of waves, we are adding virtual aspects (and hyperspatial aspects) in so doing, because of the phase differences. This is extremely important: *complex mixtures of waves automatically constitute and carry hyperspatial components!* And if we can accurately control these hyperspatial components, we are in effect doing direct hyperspatial engineering and virtual state engineering.

Now if we carry our modulation-constitutes-differentiation concept one step further, we find a most startling phenomenon (Figure 7). The first-order modulation we placed on an EM carrier we discovered to carry aspects of the next hyperspace, namely, neutrinic vectors. Now if we further modulate that first-order modulation signal as a carrier itself, so that we now have two orders of modulation upon the basic carrier, the second-order modulation must possess hyper-


CARRIER
CARRIER & MODULATION
CARRIER & MODULATED MODULATION
S'
S''
S'''
ELECTRO-MAGNETIC FIELD
NEUTRINO FIELD
MIND FIELD

Figure 8. Field coupling to the human brain


THE EUREKA CONCEPT
MODULATION
CARRIER
THEY ARE ALL THE SAME!
CONCEPTUAL
ACTUAL
AMPLITUDE
f_2
f_0
f_1
FREQUENCY
$f(D) \times \left[\begin{array}{l} \text{div } E = 0 \\ \text{div } H = 0 \\ \text{curl } E = \frac{1}{c} \cdot \frac{\partial H}{\partial t} \\ \text{curl } H = \frac{1}{c} \cdot \frac{\partial E}{\partial t} \end{array} \right]$
DIFFERENTIAL FUNCTION OPERATING ON MAXWELL EQUATIONS
E
H
V
IMPRESSING THE VIRTUAL STRUCTURE OF A PHOTON
T
S
S'
S''
S'''
HYPERSPATIAL COMPONENTS INTO/ONTO PHOTON

Figure 9. The Eureka concept

vectors of the next higher hyperspace—the mindfield itself. In other words, by using two orders of modulation on a carrier, we can directly affect mindstuff itself. So if the correct overall pattern of these complex modulations are impressed on a carrier, the life-consciousness loop itself can be directly affected or shaped, all the way from the mindfield of a biological organism to its neutrino field to its virtual photon field to its biophoton field to its body tuner, and back. With the correct pattern we can stimulate the life channel for a particular organism, and with yet another pattern we can inhibit the life channel for the same organism. By this means a positive cure for cancer could easily be derived, and as we shall see, this already has been done. By the same means, a "death ray" for use against humans could easily be developed, and it is my contention that the Soviets have already long since developed such weapons.

It is my purpose to eventually use these new aspects to construct a direct mind-link for mind-to-mind communication and hyperlinkage, thus solving the human problem.

Figure 8 shows the basic scheme for coupling such a second-order modulated signal to a human being. We will return to modulations versus nested virtuals and hyperspatials below.

THE EUREKA CONCEPT

So we have now reached a Eureka point of the first magnitude (Figure 9). Hyperspatial engineering, virtual state engineering, curved space, photon kinking, mind-life-consciousness engineering, and nested modulation are all the same thing! We directly engineer the virtual state, hyperspace, curved spacetime, and the life-consciousness loop itself, including the mind, with relatively simple devices that accomplish, transmit, and receive nested orders of modulations. Indeed we have opened Pandora's box, for this is the greatest tool ever dreamed of by humankind. Consequently it can be used either for the good of mankind or for its detriment. And this tool appears already to have been weaponized by the Soviets,

In Figure 9, note that modulation, photon kinking, the appearance of sidebands with the unchanged carrier, impressing a virtual pattern upon a photon, and impressing hyperspatial components into or onto a photon are equivalent. Further, if we assume that the electromagnetic wave (pure, undistorted wave in a linear medium) is given by Maxwell's equations, then modulation mathematically consists of impressing a particular differential operator function and a nonlinearity upon Maxwell's equations. For each modulation pattern, a particular virtual structure is impressed on the photon, which is the same as impressing a particular hyperspatial pattern upon it. Each specific pattern impressed on the photon (that is each particular kink pattern of the photon) corresponds to a specific differential operator function. Through this means, a specific theory can be constructed empirically. That is, one can work out the effects of various mixtures of waves on specific biological systems, measure the specific channels used by the mind-life-consciousness loop, and so on. The Lisitsyn paper and Kazhinskiy's "biological radio" work in fact state that the Soviets have already done precisely this, and the Kaznacheyev paper shows that a large number of related biophoton experiments were in fact carried out in Soviet military laboratories. But let us look at some very important and exciting German work directly related to this area.

BIOPHOTONS AND VIRTUAL EM FIELD OF A BIO-ORGANISM

In an incredible piece of work, "Photon Storage in Biological Systems," in *Electromagnetic Bio-Information,* Urban and Schwarzenberg, Baltimore, Md., 1979, pp. 123-149, Dr. Fritz Albert Popp has presented the results of his laboratory work—and his theory—dealing with quite new developments in biological organism fields. Indeed, this may be one of the most important Western papers ever presented, if its true import is noticed. Briefly, in studying cellular electromagnetic bioactivity, the cell behaves as a system far from thermal equilibrium. It thus can be characterized as a Prigogine system. (Ilya Prigogine received the Nobel Prize in 1977 for his development of nonlinear thermodynamics of systems far from equilibrium, thereby changing the second law of thermodynamics.) We now know that in such a system negative entropy can result, and order can emerge from disorder. For a wildly disordered system, large-scale order can emerge and stabilize, and the more chaotic the disorder, the greater the stability of the ordered patterns that emerge. (Which seems to imply a confirmation of my fourth law of logic—total disorder must inevitably turn into total order.)

At any rate, living cells produce coherent light with a laserlike activity. This coherence serves as a control for the metabolism of the cells, regulates growth, and fixes the reproduction rate. Further, the cell exhibits superconductive behavior.

Popp found that a living organism in fact possesses a living aura, a virtual electromagnetic field that pervades the entire organism with a virtual photonic flux. In this field, virtual photons are stored. The field continually receives inputs (virtuals) from the environment and is continually outputting biophotons, particularly in the near ultraviolet. This field, in which all cells are bathed and with which they all continually intercommunicate, tends to stabilize and cohere the organism. All this has been established by laboratory experiments, and all of it is directly consistent with my own hyperfields and nested-virtual-fields model of the living system's life-consciousness loop connecting its mind hyperworld to its physical body tuner. My model is consistent with Popp's work and extends it by adding the nested structures of the virtual field, thus connecting Popp's virtual field to the neutrino field and the mindfield.

And with this additional information in mind, let us return to our consideration of nested modulations on an electromagnetic carrier. Indeed, let us look at several examples of devices already applying the "nested modulation is hyperspace vectoral" effect.

THE PRIORE MACHINE

The cure for cancer mentioned above is the Priore device in France, which has been curing cancer and other diseases for over a decade, much to the frustration of many members of the French Academy of Sciences.

Antoine Prior6 is an Italian-born inventor who escaped from the Germans in World War II and fled to France. After the war Priore" purchased surplus equipment and eventually developed a strange machine that filled an entire room. A nozzle above a table in the center of the room emitted a strong ray or field, which Priore* explained consisted of an electromagnetic wave in a magnetic field. Eventually the French government spent almost three million dollars for construction of a new, improved PriorS machine, because Priori had shown he could cure cancers in laboratory animals with the device.

In 1964 Professor Robert Courrier, renowned biologist and secre'taire-perpe'tuel of the French Academy of Sciences, presented some of Priore's results to the Academy. Forty-eight cancerous rats had been divided into two groups of twenty-four each. One group was set aside without treatment as a control, and the other group was divided into two subgroups of twelve each. One of these subgroups was treated by the Priore machine promptly after cancer grafts, and the other was treated after a lapse of several days. Both subgroups were completely cured—the first quickly and the second after more prolonged treatment. All the control rats died in twenty-two to thirty days after grafting.

The results created a furore and a controversy that have continued to the present day. Since the first presentation by Courrier, the machine has repeatedly cured leukemia and other forms of cancer in laboratory animals. The controversy seems to have arisen because the French Academicians could not comprehend the working of the machine, and because the inventor would not reveal how it worked but only how it was built.

The second, more powerful Prior6 machine produces a magnetic field of about 1,240 gauss. According to one scientist, the machine contains a gas-filled vacuum tube, which contains a plasma of mercury and neon gas. A pulsed 9.4 gigahertz electromagnetic wave is modulated onto a 17 megahertz wave in this plasma. However, the true nature of the machine is revealed by the fact that the 9.4 gigahertz wave is joined in the "lamp" by seventeen radiations of unspecified frequency and nature. Thus we see that Priori is actually using second-order multiple modulations and is dealing with the direct life-mind-consciousness loop of the mammalian cell. He is directly stimulating and engineering the hyperspace nested virtual bands with his device. His twenty-six years of work have mostly been involved with ferreting out the required precise frequencies and mix of second-order modulations, as well as the correct intermodulation carrier necessary to obtain the desired effects.

In Figure 10 we show a simplified diagram of the Priore device, from which it can immediately be seen that the device uses the same principles shown previously in Figure 9. PriorS is using nested orders of modulations to affect nested orders of virtual state, thus producing direct channels and effects in neutrinic field and in mindfield. Radiating a biological target such as a laboratory animal with such a complex field directly engineers its mind-life-consciousness loop. With the correct nested modulations on the correct carrier (in this case a strong magnetic field, which allows a stronger connection to the neutrinic field aspects), the mind-life-consciousness loops of the individual cells in the body of the irradiated animal arc "scrubbed clean" of any deviation from the norm by the virtual patterns delivered to the animal, and hence to its "virtual biophoton stabilization field" reported by


F_1
F_2
F_3
ETC...
MULTICHANNEL MODULATION
F_x
DERIVATIVE CARRIER / MODULATOR
F_y
PRIMARY CARRIER
F_z
PATTERNED HIGHER DERIVATIVE MODULATION
LOWER DERIVATIVE MODULATION
CARRIER
S'''
S''
S'

Figure 10. A simplified diagram of the Priori device

Popp. In other words, the Priore device produces a reverse sort of effect as compared with the Soviet work reported by Kaznacheyev on anomalous death and disease transmission between cell cultures by near ultraviolet biophotons emitted from the virtual Popp field of the dying cells of the stressed, attacked cultures. The same sort of virtual engineering that can transmit death of the organism (by disrupting its mind-life-consciousness loop tuning) can also transmit life into a stressed attacked grouping of cells by a sort of "forced resonance" of their consciousness loops into normal health patterns. (Virtual state interactions control charges, which control chemistry. Thus the entire chemistry of the absorbing cells can be controlled and engineered.) Also, the Lisitsyn paper refers to the presence of eleven independent channels in the brainwaves (namely, in the mind-life-consciousness connection to the waves of dendrite firings that constitute brainwaves*), and these were specifically referred to clipped signals, not sine waves. (The clipped signals would be those possessing complex nested modulations, and thus representing the tuning effects of the life-consciousness loop.) The Priore machine uses seventeen higher-order modulations, which are quite sufficient to cover all eleven life channels required, with an additional six being available for tuning so as to squelch or "jam" the life-consciousness loops of those cells with tuning abnormalities, that is, of diseased or cancerous cells.

As we would expect, the Priore machine has also shown its ability to cure other infectious diseases and materially benefit victims of cardiovascular diseases. Infectious diseases cured by Priori radiation also provide an immunity to the treated host organism that has been shown to be transferrable by transfusion of blood samples.

Again I strongly emphasize that the individual biological effects of solitary magnetic fields or single frequency waves cannot be extrapolated to the multiple frequency, nested modulation case; and almost all our present knowledge of the effects of electric, magnetic, and electromagnetic fields on biological systems is woefully immature and incomplete.

T. Henry Moray built a somewhat similar machine—though very much smaller—which provided a direct radiation from extensive "peach blossom violet" colored sparkgaps inside a quartz tube, and which greatly stimulated the health of an individual exposed to the radiation. In fact, the device would promptly cure **the** radiation burns Moray frequently suffered as a result of his continual experimentation with uranium compounds and other radioactive substances. He patented the device, and some of his original machines are still in existence and still being used to treat patients with a wide variety of ailments. I have personally been exposed to one of Moray's treatment machines and can vouch for the fact that it stimulates every cell in one's body, providing in about two to three minutes a great tonic and health stimulant.

***It is these dendrite firings which form the collector-detector mechanisms through which the mind-world changes are joined to the human nervous system and brain. Were they not specifically useful and needed, the dendrite firings would not have been developed, and nerves would simply be long wires.**


COMPLEX
SIGNAL
SQUARE WAVES GENERATOR
DIFFERENTIATOR #1
DIFFER-ENTIATOR #2
COMPLEX
SIGNAL
SPIKES
NOISY SPIKES
VIRTUAL STATE MODULATION

Figure 11. A simplified diagram of the improved Flanagan neurophone

THE NEUROPHONE

Another device that uses the new hyperspatial, virtual state, nested modulation technology (and has done so for seventeen or eighteen years) is Dr. Pat Flanagan's neurophone. With brilliant insight and intuition far beyond that of science at the time, Pat invented and patented the instrument by the time he was seventeen years old. The neurophone is a device that, contrary to all present theory and knowledge, will directly "pump the brain" and reproduce sound and information directly in the brain and mind system, without going through the auditory system at all. A simplified diagram of Pat's improved neurophone is shown in Figure 11.

Briefly, the device takes a complex signal, such as the sound of an orchestra playing a musical interlude, and electrically processes it as shown in the figure. First the signal is passed into a section that clips everything into a series of square waves, remarkably analogous to the sort of clipped waves Lisitsyn confirms are the information carriers of the human brain. Next the square waves are differentiated, yielding a series of sharp spikes (note that these spikes retain the pulse-time content of the clipped signal). These spikes are again differentiated, and since these are finite spikes with real nonzero rise times and decay times rather than theoretical constructs, a series of noisy spikes results from the second differentiator section. From here, the noisy spikes are introduced to special contact electrodes, one of which is normally placed on the forehead, while the other may be placed almost anywhere, including on the foot. Nowhere are any sound waves introduced to the head.

The square-wave clipper section reduces the complex signals, their overtones, and their complex modulations to square waves, retaining the temporal content of the wave mix but not the waves themselves. The first and second differentiators heighten or filter through the temporal content of the higher-order differentiations, that is, they serve as a band pass filteT unit to accent the time keying of the neutrinic and mindfield portions or aspects of the signal. When these time spikes are then introduced across the body as pulsed voltages, they are modulated directly on the dendrite firings of the brain and nervous system, providing direct and pulsed modulation of the neutrinic and mindfield component channels of the mind-brain-consciousness-life loop itself. Thus the neurophone directly inputs information into the brain and nervous system, bypassing all the normal sensory systems that lie between the mind-brain loop and the outside environment.

Indeed, a similar development has been reported by two University of Missouri researchers. Dr. Donald York, a neurophysiologist, and Dr. Thomas Jensen, a speech pathologist, have recently reported identifying and decoding twenty-seven words and syllables in specific brain wave patterns and correlating these electroencephalographic patterns with both the spoken word and the silently thought word in about forty subjects. At present, Dr. York and Dr. Jensen are programming a computer with a brain wave vocabulary, to monitor and read the EEG of a stroke victim's brain and help stroke victims who have lost their powers of speech to communicate.

While all such developments can obviously be misused, their potential for assistance to mankind is enormous. Indeed, my own premis that brain linkage it possible and can be used to advance all mankind to the sixth stage of species evolution is slowly being proven. It is within our reach now to develop u multichannel communications system that will directly link brains, minds, and consciousness into a single functional being; and I have already pointed out that the psychokinetic power of the emergent entity increases exponentially with the number of linked stages. The normal corpus callosum linkage of the two cerebral halves in each human head proves that brains, minds, and beings can be linked and integrated into one.

The Excalibur Briefing details the basic concepts of the theory involved in hyperspace-virtual state engineering, and thus in the engineering of mind-life-consciousness links to multicellular organisms here on earth. Pat Flanagan's neurophone proves that complex information can be implanted directly in the brain and mind, bypassing the normal isolating barriers. Drs. York and Jensen have shown that the brain wave does indeed contain recognizable, decodable information analogues. Lisitsyn has already reported measuring the number of independent channels involved and has documented the importance of the clipped brain waves as opposed to the sine-wave content. If we have the vision, we can still develop a brainlink and rapidly apply it to link sixty to one hundred persons, thereby opening a conscious, multidimensional "eye" for the collective human unconsciousness, gently rousing ZARG into wakefulness, and fulfilling human destiny without undergoing the psychotronic Armageddon planned by the Soviets. The time is short, but it can still be done if the funding, the vision, and the team can be established on a crash priority basis.

SOVIET "WOODPECKER" SIGNALS

But, as I have said, all this can be used for the detriment of mankind as well as for its benefit. Unfortunately, it appears that the Soviet Union has chosen to weaponize the effects on a global scale. A prime example is the "woodpecker" lignals emanating from the USSR in the 5-30 megahertz region and interfering with communications around the earth.

These complex woodpecker signals appear to originate from two or three dozen powerful Soviet transmitters, each with a power estimated as high as 40 megawutts (Figure 12). The pioneering experimental measurements of these signals by Dr. Robert Beck and William Bisehaveshown just how deadly a potential may be possessed by the signals. These measurements have been performed in Eugene and Portland, Oregon; Los Angeles, California; Huntsville, Alabama; and several other locations. They have been particularly significant on the West Coast in and around Eugene, Oregon because of the presence of a direct current transmission line several hundred miles long, which has acted as a long wire antenna, picking up the signals and rebroadcasting them with appreciable gain in the vicinity.

Typically the signals may be found on, say, sixteen different carriers between 10 and 20 megahertz. Twelve of the carriers may appear normal, with normal sidebands, and the other four may have the carrier and both sidebands suppressed but still show the biologically significant modulation (for example, 10 hertz). On all sixteen channels a strong 10 hertz modulation may appear, all perfectly time


SYNC'ED ON
ALL CARRIERS
CARRIER
≦ 10 Hz
CARRIER
≦ 10 Hz
CARRIER
≦ 10 Hz
CARRIER
≦ 10 Hz
5-30 MEGAHERTZ
BAND
BRAINS LOCKED
IN PHASE TO
10 HZ MODULATION
WITH
ADDITIONAL
DETRIMENTAL
MODULATIONS

Figure 12. The Soviet "woodpecker" signals

synchronized and in phase channel-to-channel. The received signal from one of these carriers may be twenty-five to thirty times as strong as the earth's background magnetic field, which is oscillating at approximately 7.0 to 7.5 hertz. Other complex modulation frequencies, many of them changing, are present on the various channels.

Normally, the brainwaves of mammals in an area are gently entrained by the normal oscillations of the earth's magnetic field and are oscillating along at, say, 7.5 hertz. Under continuous radiation from the Soviet woodpecker signals, a percentage (say 30 percent) of the mammalian brains may be captured by the 10 hertz modulation on the overpowering Soviet signals. These captured brains are now in forced oscillation and are riding along in phase with the 10 hertz Soviet modulation. In other words, a certain percentage of the human brains in an area will phase lock to the 10 hertz modulation, and that will effectively lock into those brains the sixteen carrier frequencies with their concomitant frequency mixes and complex signal modulations. If the signals are made much more powerful (for example, by focussing them onto one particular area or increasing the power of the transmitters), then a much higher percentage of brainwave entrainment can be accomplished in the targeted area. By simply adding on the desired modulation patterns, the Soviets can now pump material directly into the mind-brain-consciousness-life loops of the entrained brains. The weapon implications are enormous: raw emotion such as sheer terror or panic can be transmitted; death or disease patterns of all kinds can be transmitted; informational content (thoughts and ideas) can be impressed directly into the captured brains and minds and processed as if originating inside each brain itself. Indeed, as long as the Soviets keep the effects rather gentle, an entire population can be subtly influenced without governmental notice. Certain specific ELF frequencies can rapidly disable or even kill, and for wartime use those frequencies can be directly implanted in the captured brains themselves by the woodpecker signals. It appears that 1984 came a little early, and one can perhaps now understand Brezhnev's strange 1975 proposal to the SALT negotiations that we should also consider outlawing the development of new weapons more frightful than the mind of man has ever conceived.

The signals also have direct application against strategic targets other than personnel. For example, by incorporating the correct nested modulation pattern, the positron kindling (electron squelching) pattern can be impressed. By beaming through the earth (with a circularly polarized signal or with other complex modulation forms), a beam with a strong neutrinic component, which will squelch electrons and which will interact with great preference for strong voltages or strong magnetic fields, can be directed at a target complex. In the targeted area aircraft and communications systems can be disabled; automobile, truck, and other ignition systems will fail; power transformers and large motors and generators will fail; power transmission systems with their associated high voltages will fail; and so on. Even independent, self-contained emergency power equipment, such as at military installations and strategic missile sites, will fail to operate. Further, to some of these signals, the earth and the sea are as transparent as glass, and so underwater nuclear submarines can be electrically disabled on station before their missiles can be fired, while strategic missile complexes can be electrically disabled before their deadly nuclear missiles can be hurled toward their distant targets. If some submarines and land complexes succeed in firing missiles before being disabled, these missiles can be electrically dudded and scrubbed from the sky over Soviet territory while still far from their intended targets.

So, as stated at the end of *Excalibur,* the players are on stage and in place. The final act begins. One thing is sure—mankind will never be the same again after seeing the play!

PART FOUR

SOVIET PHASE CONJUGATE DIRECTED ENERGY WEAPONS

WEAPONS THAT USE TIME-REVERSED ELECTROMAGNETIC WAVES

At the end of WWII, the Soviet Union obtained the cream of the crop of Germany's radar scientists and infrared scientists.

At that time, the German scientific team led the world in the theory and technology of radar absorbing materials (RAM) and radar cross sectioa For example, some leading Western radar experts believe that the German scientists had already advanced the theory of radar cross section beyond where Western scientists have arrived at today. Radar cross section science is the "heart" of modern radar technology, countermeasures, and counter-countermeasures.

The theory of RAM technology is precisely what is needed to develop and design phase conjugate mirrors for radar frequency bands. Phase conjugate mirrors are capable of producing a time-reversed (TR) wave in direct response to a received ordinary wave. The mirror may be powerfully "pumped" with energy to produce a very large amplification of the time-reversed wave.

Just after WWII, the Soviets also mounted a truly massive program to obtain and review all the scientific literature of the West This material was completely re-examined and digested, in a deliberate search for a major new technological "breakthrough" area. Nothing similar to this has ever been done in the West.

By 1950, the Soviets probably had discovered phase conjugation and the time-reversed wave, in their radar programs using the German radar scientists. Their relearch would certainly have revealed that the time-reversed wave is a solution to the wave equation, and hence the phenomenon is universal to all waves and frequency regions, under appropriate nonlinear circumstances.

We stress the fact that from the beginning the Soviets have always led the rest of the world in nonlinear science and mathematics.

Thus by the mid-50's, the Soviets would have mounted an intensive national development program on these radar TR wave weapons. If so, the Soviet Union has now had the equivalent of some seven or eight Manhattan Projects, back-to-back, in the development, stockpiling, and deployment of TR wave weapon systems. At least fifth generation Soviet TR weapons have been developed and deployed.

This is a matter of the greatest importance to the U.S.—and one which the U.S. intelligence and scientific communities have largely missed.

We particularly stress that the time-reversed wave phenomenon is a universal phenomenon of nature, not just a fluke, and not just a "nonlinear optics" phenomenon. It is a solution to the wave equation and, as such, it applies to every kind of wave. Electromagnetic, sound, magnetohydrodynamic, and other radiating systems all exhibit the phenomenon under appropriate nonlinear conditions.

Hundreds of Western papers dealing with time-reversed waves are now in the open scientific literature—most of them dealing with non-linear optics. However, the principles of the time-reversed wave are well-established, and known to apply to waves in general.

Compared to a normal wave, a time-reversed wave has startlingly different weapon capabilities.

Such a wave precisely retraces the path of the ordinary wave that stimulated it to be formed. So it possesses an "invisible wire" through space, back to the original position of whatever emitted its stimulus wave.

Further, the time-reversed wave continually converges upon its invisible "back-tracking" path. It does not diverge and spread its energy, in contradistinction to normal waves.

Using several simple schemes (particularly pumped 4-wave mixing), extremely large amplification of the time-reversed (TR) wave can be cheaply and readily accomplished.

A startling weapons capability therefore emerges when amplified TR waves are generated in response to received signals from a distant target:

(1) If any signal at all can be received from a distant target, a return TR signal of extreme power can be delivered directly to that target Almost all of the transmitted TR signal energy will arrive at and in the distant target, even through a highly nonlinear medium or under scattering conditions. Hardly any of the energy will be lost enroute. If the target is fast-moving, a "lead correction" signal can be calculated and added to steer the return path.

(2) Since real-time holography can readily be accomplished using TR waves—and without first making holograms, geometrical forms (balls, shapes, hemispherical shells, etc) of energy can be created readily by interferometry (crossed beam techniques). Since the TR wave carriers do not disperse with distance, these interference energy forms can be assembled by crossed TR wave beams at great distances—even hundreds of thousands of miles. The energy appearing in such a distantly created energy form is limited only by the amount one cares to put in at the amplified transmitting end.

Thus the radar itself now becomes a powerful, all-around weapon. With a TR wave adjunct, once the radar receives a return signal from a target, an extremely powerful TR wave pulse can be generated, and all the energy in that pulse can be unerringly returned to the distant target from which the return was received.

Even a passive (receive only) radar may be used together with a TR wave adjunct to accomplish the same directed energy destruction of the distant target emitting the signals received by the radar.

Radio receiver-transmitters may also employ simple TR wave adjuncts to provide a large number of communications jammers and "directed energy weapons," capable of jamming and/or destroying enemy radio transmitters at appreciable distances.

The Soviets have intensively developed such TR wave weapons since the 1950's. In January 1960, Khrushchev was probably referring to these weapons when he reported to the Soviet Presidium the forthcoming advent of fantastic weapons, then in advanced Soviet development.

Prior to Khrushchev's announcement, the Soviets had begun radiating the U.S. Embassy in Moscow with scalar EM waves and phase conjugate energy, modulated upon weak microwave carrier beams. Later these beams were used to induce illnesses and blood changes in Embassy personnel. (We will shortly discuss how the Soviets could induce disease at a distance, electromagnetically). The microwave radiation continued intermittently, in spite of the objections of several U.S. Presidents. U.S. studies failed to comprehend what was being done.

The Embassy radiation was and is a high-level intelligence probe: Stimulate and affect the U.S. Ambassador, a high-level target. Attention by the CIA, NSA, State Department, DIA, the U.S. President, etc. is guaranteed. Puzzled, they will turn to the U.S. scientific community for an explanation. The scientific community will try to explain the microwave radiation, using the best of its EM knowledge. By the U.S. counteractions taken or not taken at the Embassy site, the Soviets know with 100% certainty whether or not the U.S. has discovered TR wave weapons, electromagnetic disease control, etc.—and whether we have developed defenses against such weapons.

Since the beginning, of course, our actions—or lack of them—at the U.S. Embassy have consistently revealed to the Soviets that we have no knowledge of, and hence no defenses against, TR wave technology and the scalar electromagnetics (electrogravitation) that accompanies the phenomenon.

Soviet TR wave radar weapons also provide a convenient mechanism for accomplishing nuclear weapon kill. A target struck by a powerful TR wave pulse generates a time-reversed back-pulse due to nonlinearities in the target medium. In the nonlinear medium of the exploding or fuzing target, the two pulses (which are 180 degrees out of phase with each other) modulate each other, locking together into a scalar EM wave or pulse. This scalar EM pulse has zero electromagnetic force field resultants, but is a violent fluctuation of the energy density of local spacetime. Rigorously it is a local gravitational pulse wave, by definition. Further, it is far more powerful than "normal" gravitational waves. This scalar EM pulse does not react with the orbital electron shells of an atom, but passes directly into the nucleus and is absorbed there. This raises the nucleus to an excited state, increasing its potential (trapped energy). If the nucleus cannot withstand this increase in potential energy, it directly fissions. If the nucleus withstands the increased potential, it then immediately decays from the excited state by simply emitting a time-reversed EM wave.

Any radioactive nucleus is already "teeter-tottering" toward nuclear decay, so to speak, and it will instantly decay radioactively when struck by a significant scalar potential pulse. Thus a TR wave radar weapon can deliver a powerful TR pulse against a distant vehicle carrying a nuclear warhead, and the resultant EG pulse penetrating the nuclear material of the warhead will electrogravitationally explode it in a full-order nuclear detonation.

Therefore, when using such weapons, extreme care must be taken to avoid inadvertently pulsing one's own nearby nuclear weapons or nuclear material. In attacking distant ground targets, one must be careful not to detonate nearby nuclear weapons, nuclear powerplants, or stored nuclear material—even at some distance from the target Otherwise, large-scale nuclear fallout will be experienced over a worldwide area, and unacceptable "boomerang" self-damage to the attacker himself may be incurred. The more powerful the TR pulse employed, the greater the safety separation between the struck target and stored nuclear materiel must be to prevent unacceptable "boomerang" large-scale fallout.

Also, large TR wave interferometer weapons, such as the Woodpecker systems, usually first produce very powerful, scalar EM "standing wave" beams by continuously transmitting (in the beam) both a normal EM wave and its phase conjugute.

modulated (locked) together to produce a "zero EM vector resultant" electrogravitational (EG) wave. Interference of two of these scalar EM beams in the targeted area, plus internal scanning within the beam by other signals, allows EM effects—of either normal EM energy or time-reversed EM energy—to be produced and controlled at very precise locations within the broad interference area.

Each such huge "scalar EM standing wave" beam represents a gigantic electrogravitational standing wave, and hence a giant oscillating potential in spacetime. This standing wave represents a sort of gigantic "capacitor", or accumulator of infolded energy. Enormous energy may be collected in this potential, charged-up over a period of time. "Shortcut" of this giant capacitor—by transmitter failure—can result in a large flash-over discharge of the EG energy into the local earth, producing a massive EG ground wave that can be enormously destructive.

Thus one must carefully protect the TR wave weapon system from inadvertent discharge of large EG pulses into the earth at the local site, due to transmitter failure, shortouts, etc. Otherwise one's own nuclear weapons or facilities may be exploded—even at some distance—by the EG pulse ground wave produced. One's communications and electronics installations, for example, can be knocked out at an even greater distance.

For example, in the winter of 1957-58, a large Soviet TR wave prototype weapon at Kyshtym, near the Urals, apparently suffered a catastrophic transmitter failure, discharging a powerful scalar EM (electrogravitational, or EG) pulse into the earth. This huge EG pulse struck the atomic wastes stored nearby, causing the radioactive nuclei to imediately decay. In other words, the nearby atomic wastes exploded—just as eyewitnesses reported. Deadly radioactive contamination spread across a major region, and exists to this day.

After this accident, the Soviets would have developed much more elaborate safety circuits and devices and implemented them into their TR wave weapons.

Even so, in April 1986, the explosive eruption of a reactor at Chernobyl was almost certainly caused by an accidental catastropic failure of a large TR woodpecker transmitter about 30 kilometers away. The sudden failure of the East-to-West Woodpecker transmitter was positively detected by engineer Bill Bise. All safety circuits at the site would have been instantly activated, desperately and slowly draining off the huge "standing wave" potential built up by the weapon.

The Soviets would have immediately shut down the reactors at Chernobyl as a precaution.

Some hours later, the transmitter safety devices finally failed, and a much smaller, though still significant, remnant EG pulse was discharged into the earth, spreading out in a ground wave. The first radioactive material—the fuel rods in one of the hapless, shutdown Chernobyl reactors—encountered by the EG ground wave pulse received it and immediately erupted radioactively.

Had the full EG pulse escaped the stricken transmitter, all four reactors at Chernobyl would have violently exploded, and deadly nuclear fallout would have rained down over a wide area of the earth. Had the reactors not been shut down and the control rods inserted "full-in" to dampen the radioactivity, a far greater radioactive eruption—probably a nuclear explosion—of the struck reactor would have occurred.

In May 1960, a prototype TR wave radar weapon was used to down Gary Powers' high-flying U-2 aircraft over the Soviet Union. Powers reported a flash, as if from an explosion near him, but the flash persisted. This is almost certainly the signature of a TR wave weapon.

In April 1963, the first large strategic Soviet TR wave weapons became operational. These weapons were used to electromagnetically deaden the electrical controls of the *U.SS. Thresher* atomic submarine on April 10,1963, and to produce a huge underwater electromagnetic blast 100 miles north of Puerto Rico on April 11,1963.

Since the 1960's, the Soviets have possessed a 100% effective defense against U.S. and European strategic bombers and missiles. The early systems deployed in the Soviet Union were midcourse and terminal phase systems. The Soviets would also have relied upon additional TR wave weapons systems, deployed as adjuncts to radar systems aboard research ships and crawlers, to be able to attack U.S. missiles and bombers in their launch and early midcourse phases.

These Soviet defensive TR wave systems also could easily accomplish nuclear weapon kill, and by their nature may have already been immune to the Stealth technology.

Older Soviet radars, using TR wave adjuncts, become totally new weapons having startling and heretofore unsuspected capabilities against missiles and aircraft. For that reason, the Soviets happily continue to operate and maintain thousands of older radar systems that, by Western radar standards, are seemingly obsolete.

Hundreds of incidents of Soviet tests of these TR wave weapon systems have been observed around the world, and reported in the open literature as puzzling or anomalous phenomena.

In the 1960's, in Siberia, Vlail Kaznacheyev and his researchers accomplished enormous experimentation proving that cellular death and disease—of any type whatsoever—could be transmitted and induced electromagnetically. This team went on secretly to phase conjugate (time reverse) the "death photon" signals, to show that any cellular death and disease can be reversed or "cured" electromagnetically as well.

The latter work would have been done under the auspices and tight control of the Soviet KGB, since all phase conjugation (time reversal) weapons effects are under the KGB, both for development and deployment Obviously the "electromagnetic antidote" work of Kaznacheyev was not published, because it provided a powerful counter-BW warfare capability of great strategic importance to the Soviet Union.

Thus in the late 1960's, the Soviet Union became the only nation on earth to achieve the capability of rapidly (within one or two hours) developing an electromagnetic antidote for lethal new biological warfare (BW) viruses—of any kind whatsoever. The Soviets also developed the capability for mass treatment in this fashion of both the civil populace and the military forces personnel.

Independent verification of the Kaznacheyev "death photons" effect has been accomplished in West Germany (University of Marburg), in Australia (University of Sydney), and in the United States (by G. Wilbanks).

Independent proof of electromagnetic healing of viral diseases was also accomplished in the West, and largely ignored.

In the late 1960's and early 1970's, a French inventor—Antoine Priore—built and tested several large electromagnetic devices that cured thousands of cases of terminal cancers and leukemias in laboratory animals. He worked with members of the prestigious French Academy of Sciences. His work was funded by the French government and presented to the French Academy by Robert Courrier, head of the Biology Section. His work was suppressed in the 1970's, and lost when he died.

Priore used a plasma to accomplish multi-wave mixing and phase conjugation (time reversal). His time-reversed curative signals used a powerful, rippling magnetic field as a carrier; the magnetic field guaranteed penetration of every cell in the body—necessary to reach a blood disease. The rippling of the magnetic field guaranteed penetration of the cell's atomic nuclei by nuclear magnetic resonance. Penetration of the actual nuclei of the atoms in the diseased cell is necessary, since the master cellular control system (discovered by Dr. Fritz Albert Popp of West Germany) operates through the cell's structured scalar EM biopotential, and this potential is centered in the nuclei of the atoms comprising the cell.

Note that electrical dedifferentiation of cells at miniscule current—between picoamperes and nanoamperes—has been proven by Robert Becker and other researchers. Red cells of the frog, for example, have been electrically reversed through all their development stages. The cells first become round, then develop a scalloped outline in their membranes. Then they become ameboid and move by means of pseudopods. Their nuclei swell and their DNA becomes reactivated. They then rid themselves of all their hemoglobin and develop a full set of mitochondria and ribosomes. In Becker's historic experiments, the cells then turned into cartilage-forming cells, and finally into bone-forming cells. In short, Becker demonstrated dedifferentiation followed by redifferentiation into an unrelated cell type—all electrically initiated with laughably weak currents.

Thus profound cellular changes are most certainly inducable and controllable electromagnetically, by miniscule amounts of potentials and currents. Priore's machine applied time-reversed EM waves to accomplish reversal from cancerous cells back to normal cells.

Priore's work essentially proved that Kaznacheyev's group would have been able to accomplish the same thing by phase conjugation.

Kaznacheyev's "death photons" work was probably accomplished much earlier than reported in the open literature. Thus it probably provided a basis to use in the microwave radiation of the U.S. Embassy in Moscow, to engender blood changes and disease in targeted personnel. Two U.S. ambassadors died from a leukemia-like disease, and a third sickened and bled from the ears and nose. Only miniscule levels of EM signals would have been necessary to induce such biological conditions.

The present Woodpecker radars probably have the capability of producing similar conditions in distant target populations, whenever the Soviets wish to add the appropriate signals. They also probably are capable of killing large numbers of the targeted population, whenever appropriate Kaznacheyev "death signals" are placed upon them.

In the late 1960's, another cautious Soviet "intelligence probe" was used: A paper appeared in the open Soviet literature, dealing with time-reversed waves in the field of nonlinear optics. Only a few American optical scientists seemed to be interested.

In 1972, to focus more U.S. attention on their subtle "intelligence probe" of U.S. time-reversed wave knowledge, the Soviets sent two scientists to Los Alamos to brief American scientists on optical phase conjugation. Thereafter many U.S. optical scientists began to work in the "new field." Immediately it was revealed to the Soviet Union that the U.S. had ineffective knowledge of phase conjugation, and that the U.S. had no TR wave technology or weapons.

To this day, U.S. theoretical work in phase conjugation is still characterized by a fairly simple overall math model, obtained by simply "writing down" the necessary conjugate term. There appears to be absolutely no U.S. awareness of the actual physical electrogravitational mechanism that causes the phase conjugation/time reversal, and no theory of it as such. Its direct application to radars appears to have largely been ignored in the U.S.

In 1975, the Soviets attempted to obtain a treaty with the rest of the world, outlawing the development of frightful new weapons of mass destruction—"more frightful than the mind of man had ever imagined", according to Brezhnev himself. Gromyko introduced the draft treaty into the 1975 session of the United Nations General Assembly. No one knew what the Soviets were referring to.

Failing to obtain the treaty, the Soviets in 1975-76 embarked on the greatest military buildup in history. This buildup was nothing short of a full-fledged preparation to be ready to take over the world, beginning in 1985 (the "ready" time per Brezhnev's 1972 statement at a secret Prague meeting of European Communist Party leaders). The Soviets met this scheduled goal.

As we stated, The Soviets can be immune to any kind of viral biological warfare, anytime they choose to be. The use of lethal new viruses thus has become a highly favored, low-risk method of warfare for the Soviet Union. The West has no such capability against viral warfare, and in fact is totally vulnerable to attack in this manner. Both Western troops and Western civil populations are totally defenseless against the threat of viral biological attack.

A BW strike from a small, hostile nation or from a few radical terrorists—or even an inadvertent contaminant spillage from one of the great many ill-controlled private genetic experiments—can result in the introduction of a lethal, highly infectious new virus that will decimate the West. Indeed, a deliberate BW viral attack upon us may already have been unleashed.

In 1971, the U.S. passed the National Cancer Act and declared open warfare on cancer. Iron Curtain country scientists were invited to participate, and they did so with alacrity. At the time—ironically—penetration of our recombinant DNA genetics research was one of the highest priorities of the Soviet KGB. Obviously, many KGB scientists/agents were infiltrated into our labs under this program (some of our cancer research labs at Ft. Dietrich, for example, still employ more Communist than American scientists.).

In these cancer labs, animal viruses were repeatedly injected and reinjected into human cell cultures, until new viral strains emerged that preferred human cells. These viruses could then be cultured and the effects (or lack of effects) of various chemicals and drugs against them could be ascertained.

These new viruses are exactly what one would wish to develop if one were seeking a biological warfare virus to which humans were not resistant, and one which preferred humans as its host

Sometime during the early 1970's, KGB agents who had infiltrated U.S. cancer research laboratories may have deliberately contaminated the World Health Organization's smallpox vaccine with one or more of the lethal new viruses available in the

Western cancer laboratories. Massive WHO smallpox vaccination in Africa and other Third World countries then resulted in the appearance and spread of the AIDS disease.

If this thesis is true, then AIDS constitutes the first Soviet biological warfare strike against the West, in what can only be categorized as the opening round in a unique new World War III.

With the Kaznacheyev techniques, the Soviet KGB already has the effective electromagnetic antidote against AIDS and other lethal viruses, anytime it wishes to employ it. Some Soviet citizens, however, will be allowed to die, to serve as a deception plan and conceal the true Russian capability. Meanwhile, the Third World nations and the West will be devastated by the killer disease.

Other lethal viruses are almost certain to follow, whether from the Soviets, fanatical terrorist groups, or inadvertent private contamination. Undoubtedly, some of these frightful new viruses are not going to be slow (lentivirus) agents. Some will likely be highly infectious and quick-acting, in the manner of influenza. Some will be transmitted successfully by insect vectors such as the voracious new Asian Tiger mosquito now spreading across the Southeast U.S.

Beginning in July 1976, powerful new Soviet "over-the-horizon radars" (the infamous Woodpeckers) became operational. Extensive weather engineering over the U.S. has been accomplished by these weapon systems. (This has been separately documented by the present author; C. B. Baker, editor of *Youth Action News;* Andrew Michrowski of Canada's Planetary Association for Clean Energy (PACE); and other researchers such as Andrija Puharich.) In addition, the Woodpeckers possess the full range of TR wave weapon capabilities, including real-time holography capabilities and anti-Stealth capabilities. Terrible anti-biological capabilities are also possessed by these weapon systems, and they are also highly effective as global launch phase and midcourse phase defensive weapons for use against U.S. missiles and bombers.

In 1985, the Soviets completed "wet run" weapon tests against U.S. missiles and aircraft and at least three of NASA's shuttle launches, employing the Woodpeckers in the launch phase ABM/anti-bomber mode.

Beginning in December 1985, actual destruction of selected U.S. missiles and aircraft was accomplished. Targets destroyed by the Soviets included the Arrow DC-8 at Gander AFB, Newfoundland on Dec. 12,1985; the shuttle Challenger launched on Jan. 28, 1986; the Titan 34-D rocket launched on Apr. 18, 1986; a U.S. Delta rocket launched on May 3,1986; and the French Ariane rocket launched in late May, 1986.

In 1986 and 1987, the mysterious loss of two highly classified U.S. aircraft—believed to be Stealth fighters—may also have been due to Soviet testing of TR weapon capabilities and anti-Stealth capabilities of the Soviet Woodpecker weapon systems.

However, a severe limitation on the unrestricted use of TR weapons exists. If powerfully and unrestrainedly used, they will cause nuclear warheads and nuclear material to explode as surface nuclear bursts—in the dirtiest possible fashion. The resulting massive radioactive fallout would probably wipe out all higher forms of life on earth. Note that Khrushchev stated in 1960 that these fantastic weapons could "wipe out all life on earth if unrestrainedly used."

As long as we possess an appreciable deployment and stockpile of nuclear weapons, we are essentially "dead man fuzed" against substantial Soviet usage of their powerful TR wave weapons.

Thus Gorbachev needs to "thin out" the deployed and stored Western nuclear warheads, to allow a more unrestrained field of play for his decisive TR wave weapons. That is why at Reykjavik he suddenly expressed full interest in President Reagan's zero option, even expressing agreement with the principle of on-site inspection to insure dismantling of missiles and removal of warheads.

That is also why the Russians are so actively interested in negotiating the withdrawal of nuclear weapons from Europe. They can quickly and easily take Europe, the moment the nuclear weapons are thinned out and our "dead man fuzing" is removed!

To appreciate the ease with which a Soviet offensive, augmented with unrestrained TR wave weapons, can take Europe, consider this: A single airborne Soviet standoff radar jammer, complete with adjunct TR, within minutes can knock out all U.S., British, and FRG radars that illuminate it. Each pulse it fires, destroys an Allied radar. A single Soviet standoff communications jammer, complete with adjunct TR, within minutes can knock out all U.S., British, and FRG communications centers that are transmitting within its detection range. Each pulse that it fires destroys an Allied communications center. A single standoff Soviet jammer-based TR wave weapon can destroy an Allied carrier task force. Pulse after pulse from that weapon system will destroy the task force's radars and communications, explode HE propellants and nuclear weapons, explode fuel, ignite flammable materials, explode rockets and ammunition, and kill personnel wholesale. Tactical adjunct TR weapons can rapidly destroy aircraft, missiles, radars, radios, personnel, tanks, weapon carriers, personnel carriers, ammunition dumps, gasoline dumps, etc. The instant vulnerability of any massive emitter such as AWACS is readily seen.

We are referring to a new kind of blitzkrieg war: War conducted by powerful beams and destruction, engendered at the speed of light War in which electromagnetic radiators are the primary decisive weapons. War in which new kinds of directed energy weapons play the major role. War which renders all our present defensive armada of weapons archaic and useless. War in which the materiel and personnel loss rates are so incredibly high that they boggle the mind of the more conventional military tactician and planner. War in which even a small nation with TR wave weapons can strike and devastate a major power, and possess a first-strike capability unparalleled in human history. War which could be triggered by radical splinter groups and terrorists groups that acquire the technology. War in which the slightest miscalculation or the misuse of the weaponry can completely destroy the earth. War which places extreme emphasis on finding "other ways"—such as surreptitious biological strikes and insidious electropsychological attack and control—to decimate a foe. War that Western governments, populaces, and Armed Forces are completely unprepared—militarily and psychologically—to face.

NATO can be defeated in two hours or less, and the entire war—mop up and all—would last perhaps three days.

Of course, powerful demonstrations of Soviet strategic superweapons could be provided, to show that attempted nuclear retaliation would simply be suicide. The Woodpecker weapon systems alone could wipe out all major communications systems and power systems in the U.S., induce waves of EM-induced death and disease in preannounced locations, induce waves of abject fear and panic in the populace, or psychologically disrupt and disable—say—the entire Washington D.C. area, to include the people, the government, and the Pentagon.

If such a scenario were accompanied by a proclamation of a Soviet equivalent to the "Monroe Doctrine"—except applying it in Europe, an offer of a ceasefire, and an offer to allow us a "Dunkirk" to evacuate the beaten remnants of our European forces, we would almost certainly be forced to accept the Soviet terms for a ceasefire that left the U.S. intact.

The U.S. Congress—reacting with alacrity to accept this sudden and apparently miraculous Soviet leniency, and avoid the destruction of the world—would probably play the leading role in dictating our acceptance of liberal Soviet terms.

An agreement with the Soviets to mutually withdraw many of the nuclear missiles from Europe appears to be imminent. When the missiles are thinned out, the preceeding scenario or some variant of it is almost certain to occur.

There remains, however, one fly in the Soviet ointment: The U.S. Strategic Defense Initiative.

Presently our scientists apply phase conjugation primarily to "keep laser energy beams intact for greater distances." They appear to be completely unaware of the electrogravitational aspects of phase conjugation.

A colleague of the author has already rigorously proven this electrogravitational aspect on the laboratory bench. The phase conjugate (time reversed) wave is composed of, and carries, negative energy and negative time. If an object is forced to produce a great deal of this negative energy/negative time, it produces antigravity. This is because, in negative time, gravity is a repulsion, not an attraction.

In addition, if the electromagnetic energy of a laser is changed into gravitational energy, a theoretical gain of up to 10^{36} (protons) to 10^{42} (electrons) is achievable. In practical devices, an energy gain of 10^{20} may readily be achieved. Applied to a modified powerful laser in space, this electrogravitational gain factor is of overwhelming significance.

In SDI, U.S. scientists presently envision a high energy laser in orbit, pumped perhaps by means of a nuclear explosion. The pulsed beam from this laser would have sufficient power to destroy a rising Soviet strategic ICBM in the launch phase, say at 10,000 miles away.

If that same laser were converted to a scalar electromagnetics laser (one that turns much of its electromagnetic energy into gravitational energy), it could blast and destroy possibly a quarter of Russia with a single shot.

Thus if we developed and tested the SDI spatial/launch hardware for the space-based high energy laser, so that these systems were available for immediate launching, we could convert their lasers to scalar EM and still possess a very real strategic retaliation capability, even if the Soviets should strike us almost unrestrainedly with powerful TR wave weapons. If we launched several of these systems, we could still probably get off a few shots at Russia and destroy her, before all our space lasers could be destroyed by Soviet counterweapons.

In that case, mutual assured destruction would still exist, and we would still possess a full "last ditch" strategic retaliation capability.

Gennadi Gerasimov, Soviet Foreign Minister spokesman, confirmed as much on the Peter Jennings' ABC News Show, Los Angeles, California on 13 October, 1986. The real concern (with SDI), he indicated, is not with its present design. Instead, the Soviet concern is that the U.S. would make a great technical breakthrough and deploy new devices in space as a modification to SDI, presenting an unacceptable threat to the Soviet Union.

Gerasimov was almost certainly referring to the potential for U. S. adaptation of the SDI space-based lasers to electrogravitational lasers capable of destroying the Soviet Union.

Obviously, if the high energy laser weapons stay grounded in the laboratories, and the system hardware is not developed and ready, that strategic retaliation capability is lost to us. For that reason, Gorbachev is adamantly insisting that the SDI defense must not be developed and tested in space.

If Gorbachev can prevent the development and testing of the SDI space-based high energy laser and get the nuclear weapons thinned out, he immediately holds the decisive winning hand.

This is where we are now, vis a vis the Soviets. This is the background necessary to understand the full context of the present jousting between the Soviet Union and the U.S.

In the *Washington Times* of Aug. 26, 1986, Soviet Chief of Staff Sergei Akhromeyev warned the United States that the Soviet Union could have an unpleasant surprise response if the U.S. deploys its Strategic Defense Initiative (SDI) in space. Akhromeyev stated:

"If the United States deploys a shield in space, the Soviet Union will have several options, none of what Washington would wish... The Soviet Union will very quickly find a response of which the United States has no inkling as yet."

It is absolutely essential that the President of the United States, the Secretary of Defense, the Joint Chiefs of Staff, and the U.S. Congress be aware of these Soviet weapons and their capabilities.

It is also essential that the U.S. public become aware of the real nature of the hidden Soviet threat that faces us, so that public support will be forthcoming for the hard decisions our government leaders have to make to counter it.

A PARTIAL GLOSSARY FOR SCALAR ELECTROMAGNETICS AND SUBTLE PHENOMENA

by Tom Bearden

1. Action: the fundamental constituent of physical reality. Basically composed of two quantities—energy times time, momentum times length, etc. Action is nonobservable; only changes in action are observed, and then only partially (in the linear case). The photon is the basic quantum of action, consisting of a piece of energy welded to a piece of time, with no seam in the middle, so to speak. All physical things are composed of rates of changes in action. The physicality (volume characteristics) of space are created bit by bit from action quantum changes in and on each fundamental particle of mass, at a very high rate of speed. These action changes are totally internal to the mass itself. Therefore, literally the physical universe exists inside each and every part of itself, and is a giant hologram.

2. A-field: vector magnetic potential. The A-field is a real field—not a mathematical convenience as was originally thought—as detailed in the second volume of Feynman's three volumes of physics. Indeed, it may be separated from the magnetic field, as the experiment reported by Feynman details. When separated, it is often referred to as the "curl-free vector potential."

3. Aharonov, Yakir: renowned Israeli quantum physicist and former student of David Bohm. Together with Bohm, Aharonov authored a fundamental paper in 1959 which pointed out the primary importance of the potential rather than the force field. Co-discoverer of the Aharonov-Bohm effect: Even when the electromagnetic force fields reduce to zero in a charged particle system, the potentials may still exist and interfere to cause real physical effects.

4. Aharonov-Bohm Effect: Effect whereby interfering electromagnetic potentials can produce effects on charged particle systems, even at a distance and in the absence of the electromagnetic force fields. When E and B fields are zero in a region, their potentials still exist and interference of the potentials produces real electromagnetic effects (energy) in the interference zone, even at a great distance, without transmission of "energy" per se through the intervening space. The Aharonov-Bohm effect highlights some of the stark differences between the classical view of electromagnetics and the quantum mechanics view. In classical EM, the force fields are the real causative agents while the potentials are only mathematical creations for convenience in calculation. In quantum mechanics, it is the potentials that are real and fundamental; the force fields are effects derived from the potentials by differential operators. In classical EM, when the E and B fields are zero in an area, there is no more electromagnetics going on there; in quantum mechanics, the potentials still exist and may still cause real effects. By the use of artificial potentials, the Aharonov-Bohm effect can be made macroscopic and used to cause action at a distance—even significant action at a very great distance. Thus scalar EM interferometers can produce energy effects at a distance. The negative Aharonov-Bohm effect also exists. If the potentials of the transmitters in a scalar interferometer are biased highly negatively, then energy is extracted from the distant interference zone, reappearing at the transmitters. Tesla proposed a "Big Eye" that could see at a distance; actually he planned to use a negatively biased scalar interferometer, scan the beams, then reassemble the scanned energy appearing back at the transmitter/receivers. In this way he had a crude picture of the distant conditions in the interference zone. Such a device can see through the earth or ocean to a preselected intersection depth, since scalar EM waves can be made to pass readily through the earth or sea. The Aharonov-Bohm effect is in fact experimental proof of the new definition of force used in scalar electromagnetics. That is, force consists of mass in motion changing its motion (momentum). The nonzero 0 created by interference of two electrostatic potentials at a distance, for example, will create an electric field (E-field) on and of an electrically charged particle there. The standard detection of an E-field by conduction electron detectors is an example. It is the electron gas particles (charged electrons) that are detected, not what is in the vacuum. Thus classical EM errs when it assigns the equation E = - 0 to vacuum, for no such thing is ever measured. Actually, the correct equation is E = - 0 (e), where means "coupled to" and (e) means "electrically charged particle."

5. Aikido: a Japanese martial art whose modern form is a synthesis of many schools of jujitsu and the zen art of meditation in motion. The advanced aikido practitioner seeks to attain a state of "nomindedness," in which there is no separation of subject and object, of attacker and defender, or even of past and future. This state of at-one-ness with the universe, when attained, results in the complete mastery of the art. It is rarely experienced, even occasionally, and even rarer is it permanently attained. One who attains this state permanently is considered a great master, and his demeanor and personality are profoundly altered. The deceased founder of the present modern form, Morihei Uyeshiba, attained such mastery of the art He was a serene, deeply religious man and a profound inspiration to several generations of martial artists. He was also unbeatable even in his eighties.

6. Anenergy: stress energy of vacuum. "Fragments" of energy, more subtle than electromagnetic energy, turned against themselves and locked into a "vector zero summation." Scalar, massless charge flux. Virtual particle flux. "Pieces" of the spatiotemporal vacuum spacetime medium (i.e., quitons). Specifically, an observable object rotated more than one orthogonal turn away from the laboratory frame constitutes an anenergy particle. Examples are the virtual photon (rotation between 90 and 180 degrees), the bare neutrino (rotation exactly 180 degrees), the virtual bare neutrino (rotation between 180 and 270 degrees), and the thought or mind particle (rotation 270 degrees or more). Also, more fundamental components of energy—specifically, the individual scalar wave components of vector electromagnetic waves. Anenergy components may be coupled into energy, which can be compacted into mass. The conservation of energy law is replaced with a more fundamental law, the conservation of anenergy. Anenergy contains two com-

ponents or constituents: (1) ordinary energy (positive time, positive energy), and (2) phase conjugate energy (negative time, negative energy).

7. Angular momentum: the momentum or "leverage" of the momentum of a moving body, with respect to an axis or reference point Has the same units as action, or energy x time, or momentum x length.

8. Antimatter: matter consisting of atoms which are composed of positrons, antiprotons, and antineutrons. Also loosely refers to the antiparticle corresponding to a particle—the antiparticle may be regarded as the particle traveling backward in time, or "phase conjugated." In present physics, the photon is recognized as its own antiparticle. However, since physicists do not differentiate between positive and negative energies in a photon, then they assume that there is no difference between a photon and an antiphoton. The antiphoton, however, acts quite differently from the photon, as is clearly shown in phase conjugation. The magic rule of scalar electromagnetics for the final photon emission interaction with a charged particle in an atom is this: In the expression CPTEGS (where C is charge and normally negative, P is normal parity, T is time and normally positive, E is energy and normally positive, G is gravity and normal is positive, S is entropy and normally positive or increasing), if one of the components is reversed in sign, then each of the remaining components is also individually reversed in sign. The phase conjugate photon (antiphoton: negative energy, negative time), e.g., is produced by the photon interaction with the positively charged nucleus, producing a time-reversed wave having negative energy, negative time, reversed parity, causing gravitational repulsion, and causing negentropy.

9. Antiparticle: a counterpart to an ordinary fundamental particle, having identical mass lifetime and spin, but with charge and magnetic moment reversed in algebraic sign. Note that when the charge is reversed, parity and time are also reversed. Thus, properly, the antiparticle is the phase conjugation of the particle, or just conjugate particle for short.

10. Artificial potential: potential formed by deliberately summing force field vectors to a zero vector resultant This vector zero has a deterministic, internal stress pattern that is macroscopic. The type of potential made by the zero summation depends upon the type of force vectors summed. For example, summing electric field vectors to zero produces an electrostatic scalar potential; summing magnetic field vectors to zero produces a magnetostatic scalar potential of vacuum. All such potentials represents local warps or curvatures in vacuum/spacetime. Since Einstein assumed that spacetime locally was uncurved, this violates one of the assumptions of Einstein's general relativity. The Soviets have long made this correction; Western physicists have not Since curvature of spacetime is gravitational, this constitutes the secret of electrogravition: How to turn electromagnetics into gravitation, and vice versa. I have called this "scalar electromagnetics"; the Soviets refer to it as "energetics." In such a vector zero, the locked-in energies of all the component force vectors constitute the "anenergy" of the artificial potential. Potential in vacuum is analogous to "pressure" in fluids. An artificial potential polarizes the vacuum and constitutes a specific stress pattern in it Thus vector-zero summed systems of individually finite vector components may all differ from each other.

11. Ball lightning: rare form of lightning where an incandescent, slow-moving globe forms. The globe often moves erratically, explodes, and may set fire to objects it touches. Ball lightning is due to scalar electromagnetic interferometry which can produce a controlled pattern of electromagnetic energy at a distance. Phase conjugation is directly involved; note that the literature already explicitly demonstrates that phase conjugation can perform real-time holography, or produce forms of energy at a distance.

12. Bare electron: in physics, the true electron without the partial shielding of virtual positrons that are attracted around it In scalar electromagnetics, the mass of the electron, considered without its flux of virtual photons (its massless charge flux). An electron mass without its charge (in new approach); that is, one that is really bare of all charge!

13. Bare neutrino: the photon rotated one orthogonal turn farther away from the laboratory frame would be seen in the laboratory frame as a bare neutrino. In the new approach, bare neutrinos move at the speed c inside an ordinary photon, orthogonal to the photon's direction of travel, constituting a flux in each half of the photon. Two neutrinos move in the photon, one in each half (a simple photon is a single sine wave). One neutrino moves in positive time, the second moves in negative time and is properly an antineutrino. Since the photon moves at the speed c with respect to the laboratory frame, then the bare neutrino moves at the speed c-squared, but only its carrier speed c is seen by the laboratory observer. The flax of bare neutrinos in each half of a photon corresponds to the classical neutrino of present physics. The bare neutrino is (to the lab frame) a factor of c smaller than a photon, and one dimensional. It is a special kind of polarization wave to the lab observer.

14. Bearden, Thomas E.: nuclear engineer, retired Lieutenant Colonel (U.S. Army), and theoretical conceptualist active in the study of paranormal phenomena, scalar electromagnetics, Soviet Tesla (time-reversed wave) phenomena, free energy, antigravity, electromagnetic healing, and human development. Particularly known for his work in scalar electromagnetics and Soviet unorthodox weaponry.

15. Beck, Robert: noted psychotronics and ELF researcher who has pioneered many unusual measurement fields such as the Schumann resonance of the earth's magnetic field, specific effects on humans of extra low frequency (ELF) signals of precise waveform and frequency, ELF pollution effects, and brain wave entrainment by weak ELF signals of precisely controlled frequency. He is also noted for his development of a series of very sensitive detectors and scalar wave detectors.

16. Bedini, John: noted audio engineer, creator of the renowned Bedini amplifiers well known to audiophiles, and researcher into free energy, antigravity, and electromagnetic healing. Bedini has built several free energy motors and devices, including a gravitational field generator, a gravitational field turbine, and a series of monopole motors. He is also noted for his development of sensitive scalar EM wave detectors. He is struggling to develop an electromagnetic phase conjugate signal which will kill the AIDS virus, and also reverse the genetic damage done to the cell by the virus.

17. B-field: the magnetic induction B. This is defined, analogously to E, by the force it exerts. The force on a point charge moving in a magnetic field is at right angles to the velocity vector of the charge and also at right angles to the magnetic field. Actually, the H-field was originally named the magnetic field and the B-field was named the magnetic induction. This is an annoyance because it is B which produces or involves the force, and hence should be named the field. Other writers have noted this discrepancy, and Sommerfeld called H the magnetic excitation—which correctly describes its role—rather than the magnetic field. In Kaluza-Klein unified field theory, all electromagnetics is in the 5th dimension, which is wrapped around each and every point in our normal 3-dimensional space.

18. Being: pure essence, existence. Again, something which in actuality resists definition unless preliminary assumptions are made. Generally used in one of two senses: (1) persistence, as in "he is (he continually exists)," or (2) identity, as in "he is the man ('he' and 'the man' are the same thing)." Even in the first instance - persistence - one is using the form of the verb "to be" in the sense of identity, when perception is considered; i.e., "he is" is a statement that "he continues to be presented or perceived, because each succeeding perception is identical to the one before." Thus when perception is considered, being may be defined as that which is undifferentiated, and this yields its total definition. This is the real void devoid even of void, if one considers zen.

19. Bennett Island; Soviet island on which large, anomalous exhausts—some 150 miles long and nearly horizontal—are repeatedly photographed by U.S. weather satellites. Over 100 incidents have been photographed there since 1974. These exhausts are believed to be the exhausts of energy extracted by distant Soviet scalar interferometers used in the endothermic mode, then switched to the exothermic mode and focused on Bennett Island as a "dump site." Similar exhausts have been seen on Novaya Zemlya, a large island off the north coast of mainland USSR.

20. Bigfoot: U.S. slang or common name for a materialized sasquatch or apeman-type tulpoid, even if not well-formed.

21. Big Mama: very large, glowing nocturnal light UFO believed sometimes associated with cattle mutilations. Implies a sort of "mother ship" which spews forth smaller ships, which then speed off, swoop down to mutilate cattle, and return. Big Mama has been observed to split into or spew off smaller lights which sped away, dipped down, then returned. Some of these occasions appear to have been associated with cattle mutilations. The most noted photographs of Big Mama were taken by Bill Jackson.

22. Biofield: a hyperfield, particularly with reference to the fields of a living biological system. Also bioframe, bioworld, hyperfield, hyperframe, hyperworld, orthofield, orthoframe, orthoworld.

23. Bioframe: a hyperframe, particularly with reference to the frame of the body of a living biological system. Also biofield, bioworld, hyperfield, hyperframe, hyperworld, orthofield, orthoframe, orthoworld.

24. Bioworld: an orthogonal universe one or more right angle turns away from the ordinary world, particularly with reference to the frame of the body of a living biological *system*. Hyperworld. Orthoworld. Living energy forms—"critters"—exist in these bioworlds. A bioworld is also one of the netted levels of infolded virtual state. Such "living electricity" can be manipulated and utilized by scalar EM means.

25. Bohm, David: world renowned physicist and originator of hidden variable theory. Together with his student Aharonov, he co-authored a fundamental paper on the Aharonov-Bohm effect wherein interfering electromagnetic potentials can produce effects on charged particle systems, even at a distance and in the absence of the electromagnetic force fields.

26. Brain wave: a rhythmic fluctuation of the voltage between various parts of the brain, normally ranging from about 1 to 60 Hertz in frequency and 10 to 100 microvolts in potential strength. Brain waves are caused by avalanche discharge firings of the nerve cells in the brain. Actually, classical brain waves are only the residue or "spillage" waves of the brain, and the important activity is in the specific patterning of the vector zero summations of the myriads of ion discharges. Every "discharge ion" constitutes a small EM force vector. The summation of these is largely zeroed; however, the patterns formed by all these tiny components are not random. The intent and will of the human being is expressed in the changes in the patterning of these dynamic substructures. Present EM brain wave theory does not touch the basic "thought patterns," which are scalar in nature. Use of the two cerebral hemispheres as a scalar interferometer provides mechanisms for the effects of parapsychology and paranormal phenomena such as fire walking.

27. Burst, burst-in: the sudden collection or condensation of anenergy into a frame, so that observable light or electromagnetic energy (or rarely, physical matter) appears (is kindled). Sudden kindling of anenergy into energy.

28. Cattle mutilations: the strange, paranormal, surgical killing and/or mutilating of cattle in the U.S. and other countries, particularly since the 1973 Yom Kippur War. Metapsychologically, mutilation of the cow is the mutilation of the female symbol—that is, it symbolizes mutilation of "Fortress America." Many small animals such as cats, dogs, rabbits, and birds have also been paranormally mutilated, which is destruction of the child symbol. Again, this symbolizes the mutilation of "Fortress America." The author regards such bizarre paranormal incidents as being caused by temporary materializations of the unresolved conflicts from the human collective unconscious's dreams. With this thesis, if knowledge of Soviet scalar electromagnetic weaponry is also included, analysis very similar to standard psychological dream analysis provides explanations consistent with the bizarre mutilations and the Cold War.

29. Causality: the time ordering of ordinary inert interactions. Macroscopic (observable) causality may be violated by control of hidden subquantal (virtual state) variables. With scalar electromagnetics, direct engineering of the virtual state—and hence violation of observable causality—*is* possible.

30. Cerebral hemisphere: each half of the cerebrum, the enlarged anterior or upper part of the vertebrate brain. The two cerebral hemispheres may function as a scalar interferometer to sense distant scenes (even distant in time), or produce energy and signals at a distance. The time aspect (e.g., in psychometry) is due to utiliza-

tion of the cerebrum as a phase conjugate mirror (PCM), and inputting tiny signals picked up from the object one is holding. A phase conjugate signal is then originated by the PCM, retracing the route to the original object. Unfortunately the output of the human nervous system that can accomplish such scalar EM functions lies very deep within the unconscious mind, and it is very difficult to raise it to direct consciousness. Usually the conscious mind is only aware of "vague impressions" instead of clear signals, although in the extremely rare instance clear impressions are consciously detected.

31. Changing the past: every intentional inception upon ordinary inert causality represents a slight alteration or change in direction, departing minutely from pure causality. From a causal viewpoint, each human inception minutely changes the causal past, as well as the future.

32. Charge: the repetitive, "locked in" massless virtual particle emission and absorption activity (flux) of and on a fundamental particle such as an electron. Vacuum is identically pure massless charge flux. In the new theory, the intensity of the charge flux on a particle is also directly related to the rate of the particle's passage through time. The continued absorption and emission of photons by a particle provides the general mechanism by which the particle moves along in time in little jumps. In the scalar EM view, the relativistic change of the rate of flow of an object through time is due to a change in its ambient vacuum charge potential—i.e., to a change in the rate at which it is absorbing and emitting virtual particles and scalar waves. The negative charge is associated with a positive time flux (hence with positive energy) and the positive charge with a negative time flux (hence negative energy). A positive charge is also a negative charge moving backward in time. All particles have clouds of virtual activity patterns; essentially all mass is charged since these clouds contain charges. In ordinary electrical physics, charge is defined in terms of force and force in terms of charge, and charge and charged mass are erroneously made synonymous. In scalar EM, a "charged particle" represents a mass (nonlinear bump in spacetime, or *local nonlinearity" medium) that separates the scalar waves of vacuum into two parts, one is normal energy and the other is the phase conjugate having negative energy. It is important to remember that a charged particle is a special sort of high pressure "pump" and "vacuum cleaner" at the same time. So is a "magnetic pole" or a "potential."

33. Cold explosion: the sudden extraction of energy from a distant intersection zone of the crossing beams of a scalar interferometer which transmits in the pulsed mode while negatively biased. A famous example of Soviet testing of a cold explosion scalar EM weapon is the huge cold explosion that occurred off the coast of Japan on April 9,1984. When the energy is suddenly extracted from a zone near the surface of the ocean and above it, the pressure in the zone is suddenly lowered. Water vapor and mist are violently sucked up, and the surrounding air rushes in, pushing the "water vapor filled region" rapidly upwards. The pattern that results is a rising mushroom cloud, very similar in appearance to a nuclear explosion, except for the absence of a flash and blast wave. In a cold explosion, the energy is extracted from throughout the spacetime of the distant interference region, and insulation has no effect since classical heat conduction through space is not involved. Ordinary electrostatic cooling is also an example of this effect in less violent form.

34. Consciousness: refers to a living being's awareness of its sensations, feelings, thoughts, and the world around it Specifically, consciousness involves an anenergy communication channel where detections of the body-object (which may be regarded as a sort of special camera, instrument, or physical tuner) project into the mind as separations from the beingness of the subject Further, it refers to the intersecting stream of monocular, one— at-a— time virtual projections into the mind from the quantum changes of photon interactions upon the body sensors. By memory (collection in the mind) of streams of such monocular changes one after the other, the entity is conscious of its body-object (camera—tuner) monocularly "moving through time." In the absence of deeper understanding, the individual consciously sees itself as a separated physical object moving and changing in time, i.e., with respect to other separated physical objects that it perceives. The "externality" of certain changes (i.e., the physical world) is due to the lack of mental control or influence over them. "Internality" of certain other changes is due to the ability to mentally control or influence them. The ordinary conscious mind is a serial processor: only one thing at a time is discriminated in its awareness. The unconscious mind, on the other hand, is totally conscious—but multiply so, since it is a parallel processor of many discriminations at once. The conscious mind, then, cannot directly perceive the individual discriminations of the parallel processor, since these appear only as a blur or nothingness to it (much like looking at a hundred 35mm slides in the projector at the same time). This is the mechanism of the barrier between the conscious an unconscious minds. Projections from the unconscious onto the screen of the conscious mind will thus appear symbolical—that is, having many hidden meanings at once. This is why our dreams, for example, appear to our conscious minds as weird and distorted, but highly symbolic in nature.

35. Contactee: a person who seemingly has had a direct contact—mentally, physically, or both—with aliens, extraterrestrials, etc.

36. Continuous mode: for a scalar interferometer or Tesla howitzer, mode of operation where power is fed continually to the transmitters, and the two Fourier expanded scalar patterns or beams are continuously transmitted. In this mode, in the distant interference zone a glowing pattern of vector electromagnetic energy appears and is sustained. (Note the possibility that a few of the UFO sightings could well be due to the deliberate usage of such a mechanism by the Soviet Union or some other nation possessing the requisite technology to create such physical "apparations" at a distance.)

37. Corpus callosum: the thick nerve cable that links together the two cerebral hemispheres (which are separate brains) in each vertebrate (including human) brain. In each of the two cerebral hemispheres, there is a separate mind and personality (given that the other is separated). However, a brain has a unique characteristic: Anything that arises directly inside it is automatically assumed to be self-originated, since the brain-tuner can differentiate no separation or "separate source" for the signal/thought arising directly upon its "internal screen". This allows integration of the two brains/minds/personalities into one.

That is, when one brain half prepares and sends a message, that message is also routed across the corpus callosum into the other brain half, arising internally upon the second brain's "display." The second brain half therefore thinks that it itself originated the signal or message. Thus when the left cerebral hemisphere moves the right thumb, for example, the right hemisphere thinks that it itself ordered the movement of the right thumb. Perceptually, the definition of identity is the loss of all distinction."

38. Cotton effect: the wavelength dependence of certain optical and absorption characteristics in a substance in the vicinity of an absorption band. An absorption band is a range of electromagnetic frequencies within which electromagnetic energy is absorbed by a substance. The direction of polarization of the energy affects the degree of absorption for certain substances. In these substances, the frequency and the direction of polarization of incoming electromagnetic energy affect the amount of energy deposited and dispersed.

39. Crawford, Hal: accomplished science fiction artist and illustrator who has furnished many drawings in the new approach and contributed to the theory of mind linkage.

40. Crosstalk: in ordinary science, the transfer of energy or signal from one channel to another, by cross modulation or cross coupling between the channels. In the new approach, it refers to virtual anenergy exchange between orthogonal universes or frames—that is, between different 3- or 4-dimensional slices of an infinite-dimensional universe.

41. Cyborg: (noun) a single integrated system consisting of a living system energetically or functionally linked to mechanical or electromagnetic devices and/or systems. (Verb): link, in the sense of forming such a system. A living biological system is a cyborg of its mindworld (mindframe) to its body (laboratory tuner).

42. Death: the loss of the preferential tuning of a physical body to its mindworld. This causes loss of the preferential consciousness loop or life channel, resulting in "death." Actually the being is unchanging and indestructible, hence consists of all changes and destructions simultaneously, with none separated individually. Life and death thus are two sides of the same coin, and the coin is immutable, regardless of which side is exposed.

43. DeBroglie wave: a matter wave. The quantum mechanics wave associated with a particle of matter, which can give rise to interference effects. An orbital electron in an atom is associated with a standing DeBroglie wave on a Bohr orbit. DeBroglie waves always move faster than the speed of light, the speed being given by c2/v, where c is the velocity of light in vacuum and v is the velocity of the particle of mass. Debroglie wave velocities thus vary from the speed of light to infinite speed (everywhere at once). In his speech accepting the Nobel Prize, DeBroglie emphasized that , since these waves produce real physical effects, they are real and must not be regarded simply as mathematical conveniences.

44. Dimension: a certain primary geometrical physical attribute, such as length, used to describe the separational relationships of physical phenomena. By "geometrical" we mean that the "dimension" is considered to "exist" in either the presence or absence of the observable physical phenomenon; however, by agreement the dimension itself is not directly observable. It can be inferred ("measured"), however, by comparative operations of simple devices such as clocks and metersticks, and its simplistic definition is usually given as "that which has measurable magnitude." Prescribed measuring procedures are used to assign magnitudes to these inferred dimensions, using specific scales. Actually, "dimension" just means "fundamental quantity of separation" in the most general sense. The number of dimensions taken in advanced physics usually represents a somewhat arbitrary choice for good modeling fit In modern Kaluza-Klein theory, for example, it becomes necessary to accept some 10 or 11 dimensions.

45. Dirac sea: in Dirac electron theory, the relativistic wave equation for the electron has four components, which correspond to two spin orientations and two energy conditions: positive and negative. Thus the vacuum possesses a "sea" of negative energy conditions for electrons. These are called "holes" and are considered to ordinarily be filled with electrons which have fallen into these negative energy states. The Dirac sea thus is this vacuum sea of negative energy electrons. If energy is added, electrons can be lifted from this sea. If spacetime is locally curved, additional holes may be created so that normal positive energy electrons fall in and disappear, creating the appearance of an "electrical energy sink." If the curvature is in the opposite direction, electrons may be lifted from the Dirac sea by the curvature, thus producing a flow of electrons and creating the appearance of an "electrical energy source." In several battery-powered free energy motor devices where die battery is sharply "back-spiked" for recharging, the battery has been noted to apparently accumulate such additional "Dirac holes" as the DC series—wound motor ran. When later recharging the battery with a normal charger, for example, the battery would first "consume" a quantity of electricity to "refill the holes." When the holes were filled with new electrons, the battery would then start to recharge normally. In one extensively used battery, Watson noted that it consumed electricity for some eight hours before recharging normally. Similar effects have been noted by Bedini.

46. Dissociation: separation of ideas from their affects or feelings, resulting in independent functioning of these components of a person's mental processes. Simply put, fragmentation of the mind and personality. In this sense, Zarg (the collective human unconscious mind) is severely dissociated, since its "conscious mind" is fragmented into billions of pieces (into the independent conscious minds of ordinary humans). This is severe dissociation and psychosis; Zarg (the human species) is quite literally insane.

47. Dowsing: use of handheld rods, forked twigs, pendulums, bent coathangers, or other simple physical detectors to locate water, minerals, lost objects etc. or to seek answers to specific questions. The movement of the physical instrument serves as an indicator and is cyborged to the dowser mentally and psychokinetically.

48. E-field: the electric field or electric intensity E. That field on a spinning charged mass which produces an electrical force, hence linear motion of die charge. (In the new theory, the E- field CONSISTS OF the spinning charged mass, moving through a finite change in electro static scalar potential, and thus there is a more fundamental generatrix of FORCE.) Defined as the force per unit charge (i.e., per unit of charged mass). On a free

electron, there may exist two separate E-fields, one in the direction of motion of the electron (normally due to voltage); and one at right angles to the electron's motion, due to the time derivative of the A-field.

49. Einstein's postulates: (1) all the laws of physics are equally valid in all inertial frames of reference, (2) the speed of light is the same to every inertial observer, and (3) the observable local effects of a gravitational field are indistinguishable from those arising from acceleration of the frame of reference. The first is called the special relativity principle, the second is called the law of light propagation, and the third is called the equivalence principle. It is now known that postulates (1) and (2) are not independent of each other. Note that the third postulate implies that any local force is due to a "gravitational field" (acceleration of the frame of reference). It also implies that gravitational force has a mechanism, since quantum mechanics assigns a differential operator, operating upon a potential, to create every force. By extended inference, it can be seen that the third postulate also implies that there should exist a method to turn any type of force (field) into gravitational force (field).

50. Electrogravitics: electrogravitation, or scalar electromagnetics (SEM). The term "scalar electromagnetics" was chosen by Bearden to describe the electromagnetics that goes on inside a macroscopically summed-zero force vector system, producing gravitational effects and energy effects at a distance. A priori, SEM is a unified field theory, which predicts strong effects easily verified experimentally. The struggling science that seeks to produce gravity and inertial effects electromagnetically (success has been achieved recently in proprietary labs). Santiliy has shown that the classical assumption that electrical field and gravitational fields are mutually exclusive is false. They are therefore either the same thing or partially the same thing. There are numerous anomalous experiments which also show a connection between electrical effects and gravitational and inertial effects. Appreciable technical work in the U.S. seems to have been done on electrogravitics in the 50's and 60's, much of it apparently classified. There are presently strong electrogravitic efforts in Germany, France, and Japan. Scalar electromagnetics is in fact electrogravitics (electrogravitation) and has been successful in engineering gravitational devices such as gravitational and inertial field generators, gravitational field motors, free energy generators, and gravitational turbines. Tesla's secret of wireless transmission of energy at a distance without losses has been rediscovered, as has the secret of his "big eye that can see at a distance." A new land of resonance—scalar resonance—has emerged, as has a new kind of wave, the scalar EM or electrogravitational wave. Scalar wave detectors are now becoming available due to the pioneering work of Dea, Beck, Bedini, and Golden, who have all built scalar wave detectors. A substantial series of devices have been built by Bedini, Golden, Watson, and other inventors who wish anonymity. One of the very first good experimental physicists who built electrogravitational devices was Hooper. Actually, Maxwell's original quaternion theory, published in 1864, was the correct unified theory of gravitation and electromagnetics. After Maxwell's death, Heaviside "translated" (mutilated) Maxwell's theory into his new vector mathematics, discarding the quaternion's scalar component. He thus discarded electrogravitation, setting "modern EM theory" upon its nongravitational course.

51. Electron dissolution: when the virtual photon activity of an electron (i.e., its charge) is directly quenched, the electron is converted to a neutrino or neutrinic wave, which radiates away without interacting with materials or objects. In this case, no ordinary photons are radiated. Orbital electrons in atoms are generally protected from this interaction by being locked into their orbital DeBroglie waves. Free electrons flowing in circuits, however, are susceptible to the effect by scalar wave coupling. By this means, electromagnetic circuits may be dudded by dissolving their currents, without physical damage to the circuitry components. Whenever the agent causing the electron dissolution is removed, currents resume and the circuits resume normal electrical action. Scalar longitudinal 0-field waves can also be absorbed in scalar coupling into the E-fields of currents flowing in a circuit. This can either augment or diminish the E-fields to which coupling occurs. If the E-fields on the flowing electrons are zeroed, the electrons cease flowing, and the circuit is dudded.

52. Electrostatic scalar potential (0): virtual photon stress on the 4-dimensional spacetime medium (on the vacuum-ether). (Note that the vacuum can be regarded as consisting of the sum of a large group of such potentials.) The spatiotemporal intensity of the massless charge (of the virtual photon flux through a spatiotemporal point). Nikola Tesla discovered pure longitudinal scalar 0-waves. Present spatial 0 in the ordinary theory is only a special case. 0 can be visualized as a special type of "pressure" in an n-dimensional fluid, where n is equal to or greater than 4. By omitting the potential's stress on time, present potential theory eliminates the potential's ability to affect everything existing in time (for example gravity, fundamental constants of nature, inertia, mass, rate of time flow, mind, life, etc.) It also eliminates the direct engineering of local general relativity, and the concomitant violation of the conservation laws (momentum, energy-mass, charge, spin, etc.) Present electrical theory—and indeed all of physics—is drastically in error by this serious omission. Direct engineering of artificial potentials by patterned zero-vector force field summations is the secret of the long-sought "unified field theory." It is also the secret of the unification of mind and matter into a single scientific discipline.

53. EMP (electromagnetic pulse): a sharp pulse of electromagnetic radiation produced when an explosion occurs in an unsymmetrical environment, especially at of near the earth's surface or at high altitudes. Essentially the same as an electromagnetic shock wave, a wave of great intensity which results when waves with different intensities propagate with different velocities in a nonlinear optical medium. An EMP is also produced when two intense longitudinal scalar electrostatic potential wave patterns meet and couple into a sudden flash of vector EM energy.

54. Endothermic explosion: the sudden absorption of electromagnetic energy in a spacetime area where the energy converts to a potential, and scalar waves radial back to the negatively biased transmitter/receiver, emerging there as ordinary electromagnetic energy. As implosion. All normal explosions are exothermic in nature, and ordinary electromagnetic heat energy is radiated away. A scalar EM howitzer, however, may pro-

duce an endothermic explosion (an energy implosion) at a distance, explosively extracting the heat energy at the implosion site and receiving the energy back at the transmitter site for disposal.

55. Energy: the capacity to do work. Energy is directly tied to the work concept, which is the result of a force moving through a distance. However, "work" refers to the past; that is, the force has moved through a distance against a resistance. "Energy" refers to the future; the force could in the future move through a distance against a resistance. Since the force is tied in turn to a changing mass motion, it follows that—conceptually—energy is tied directly to mass systems. The "energy" that an object possesses depends also upon the observational situation: a moving observer may see a moving object as possessing more or less energy than the lab observer sees. Electrostatic scalar waves do no work and individually have no "energy" per se. Two different scalar waves coupled onto a spinning charged mass, however, produce a system which has mass and energy, and does work.

56. Ether: originally, a ghostly-thin, material, fluid medium postulated to fill space and carry electromagnetic waves, similar to the way in which a gas carries sound waves. The Michelson-Morley experiments eliminated any such material ether, but not a Lorentz-invariant nonmaterial ether (of which vacuum itself is one example, in the modern view). Maxwell's equations were derived from ether theory. Einstein once proposed that the vacuum, complete with its electromagnetic fields, should be called the ether. Indeed, the word "ether" is again acceptable in the literature in context of its modern meaning. Today the "ether gas" is considered composed of virtual particles—that is, the particles spontaneously come into being and then vanish so quickly they cannot be individually detected. That is, today the ether is a virtual particle gas—sort of a gas of "effervescent bubbles", so to speak. Ives derived special and general relativity, Newton's laws of motion (relativistic form), and the square law of gravitation from a Lorentz-invariant nonmaterial ether theory. Zero-point energy of vacuum would also seem to be a Lorentz-invariant ether. The Soviets are believed to have applied and advanced the Ives theory to produce their present theory of energetics, which is highly classified by the Soviet Union. In the new approach, vacuum is identically pure massless charge (virtual particle flux), and thus an ether as Einstein proposed.

57. Evil: refers to an act theoretically detrimental to the receiver or referent, in the positive time stream. It is equally beneficial to the referent, viewed in the negative time stream.

58. Exo-electron emission: emission of electrons from the surfaces of metals and certain ceramics after these surfaces have been freshly formed by a process such as abrasion or fracture. Cracks in metals are good emitters of exo-electrons, and the electrons can be detected, to provide a means of detecting the minute fatigue or stress cracks. The sides of a crack in a stressed metal constitute a scalar interferometer, and scalar interferometry is involved in the emission process. Exophotons are also emitted, in addition to electrons. In an earth tectonic plate fault zone (crack), stress exists on each side of the plate, but not in the middle, and the fault thus constitutes a scalar interferometer, emitting charges and also often creating glowing balls of light

59. Exothermic explosion: an ordinary explosion where ordinary heat and electromagnetic energy are released and radiate away from the explosive site. All normal explosions are exothermic.

60. Feynman diagram: a two-dimensional diagram of particle interactions, both in the virtual and observable levels, and both backward and forward in time.

61. Fireflies: sentient bits of light that sometimes kindle in the presence of a psychic initiator and/or a psychotronic generator. Literally, minute glowing, indefinite thought forms materialized into electromagnetic energy. This can be understood by modeling thought forms as real electromagnetic forms existing in a rotated universe (i.e., as hyperdimensional). Interference causes dimensional shifting, so that ordinary electromagnetic energy forms can result

62. Firewalking: walking on and across a bed of hot glowing coals without the feet being burned. Firewalking is demonstrated in a variety of cultures, belief systems, and locations throughout the world. Recently many Americans have been taking to the practice and demonstrating that it is an achievable phenomenon. In the new approach, the two cerebral hemispheres act as a scalar interferometer. If this biological scalar interferometer creates an endothermic (extraction) field on the surface of the skin of the feet, and simultaneously creates an exothermic scattering of the extracted energy into the surrounding environment, then one can walk on hot coals without burning the feet. Note that the reverse effect-cooling of the external environment—is often experienced when psychokinesis effects at a distance are obtained. For example, poltergeist effects are often associated with an adolescent If the adolescent's cerebral scalar interferometer extracts by inverse scattering, and projects exothermically into distant objects, the movement of the objects can be explained.

63. Fission (action): the splitting of the action quantum into two canonical variables (for example, energy and time), only one of which can normally be completely detected or measured. ("Action" has the dimensions of angular momentum—energy x time, momentum x length, etc.) Fissioning produces length, discrete bit by discrete bit, and time likewise. The physical reality of separated physical objects is thus continually created, discrete bit by discrete bit, monocularly. All that ever exists in the "present" is a single quantum change, just occurring. Recombining of the two canonical action fission fragments is called "fusion." Fusion also occurs monocularly, quantum by quantum. Rigorously, the physical world of separated objects never exists as such except in memory recall of vast numbers of past ordered quantum changes that occurred one by one.

64. Flux: the amount of some quantity (such as energy, particles, volume of fluid, etc.) flowing across a given area (usually a unit area perpendicular to the flow) per unit of time. The term flux density is now more commonly used. Loosely, "flux" refers to the perpendicular flow through an area, while "flux density" refers to the magnitude or intensity (rate) of die flux. In some cases such as a flux of particles of different velocities, the number of particles may be multiplied by the average velocity to give an average flux density.

65. Flux density: the amount of tome quantity (such as energy, particles, volume of fluid, etc.) flowing across a

given area (usually a unit area perpendicular to the flow) per unit of time.

66. Flying saucer: a discoid or other shaped paranormal object observed in the skies and/or landing, taking off, etc. Came into general use in the U.S. in 1947 after Kenneth Arnold reported seeing nine strange flying discs skipping along like saucers. Sometimes used to refer to an unidentified flying object (UFO). The usual "flying saucer" is theorized to be due to temporary materializations from the collective human unconscious; over 80% of these materializations only go so far as the "glowing light" stage, not to the material object stage. A small percentage do physically materialize, then later dematerialize. A small fraction of one percent are considered to be actual ships built on earth by the Soviet Union or one other country. A few sightings may be due to deliberate scalar interferometry at a distance by the Soviet Union and others.

67. Foo fighters: glowing balls of light which occasionally appeared in the skies and played tag with Allied, Nazi, and Japanese planes during World War II. The word "foo" is a corruption of the French word "feu," meaning fire.

68. Force: in mechanics, identically the time derivative of momentum. Simply, changing of mass-motion. One must realize that it is not the mass in motion, but the single undivided quantity "mass-motion" or "mass-velocity" (momentum) that is changed. In present EM theory, force fields are erroneously taken to exist in empty, massless vacuum. However, the mechanical definition is an identity, not an equality. Thus force does not EXIST ON a mass, but CONSISTS OF a changing "mass-motion." Since this force can be induced at a distance (by changing an introduced mass-motion such as a test charge), one is confronted in the new approach with the fact that there is a more fundamental mechanism that produces force itself. This mechanism is coupling of nonidentical scalar fields by and on a spinning charged particle. The INDUCED FORCE consists of the particle's change in mass-motion per unit of time. It is thus a flux—induced quantity in, on, and of a mass in motion.

69. Force field: an effect that can exist in vacuum or on mass whereby a particular type of matter is affected. For example, the "electrical (force) field" can affect and change the state of motion of any charged particle. In classical physics, the force fields are the causative agents; when these fields are zero, then the motion of the particle or system is unaffected. The electric field (E-field), for example, is defined as the force per unit of fundamental charged mass, though usually it is stated as "force per unit charge," with the mass ignored. Rigorously, however, force does not exist in vacuum, in the absence of mass, a priori. The Aharonov-Bohm effect shows that the potentials can interfere to produce effects in charged particle systems—even at a distance, and even when the force fields are reduced to zero. Tesla stated that vector Hertzian waves do not move through vacuum, which is true. Rigorously, two scalar waves move through vacuum instead. When coupled (detected) by a spinning charged mass (an electron, for example), the vector E and B fields are created on and of the moving mass itself; they do not exist in vacuum. This has been a fundamental omission and error in both electromagnetics theory and mechanics. For example, the standard EM equation, $E = - 0$ is not generally true in vacuum, but it is true on an electron moving in a detecting antenna or on a charged particle moving in vacuum. Any force is produced by the same fundamental mechanism: flux differences encountered by a spinning charged mass. Thus there is a common connecting thread among all forces, and this is the key to a practical, engineering unified field theory. Note that Einstein's equivalence principle, after much pondering, can be taken to be an equivalent statement to the fact that force—any force—consists of a change in mass-motion. In modern quantum mechanics, force is an effect, not a cause, and is derived from the potential by a differentiating operator. The potential is the primary causative agent, not the force. Also, in modern quantum field theory, all forces actually come from curvature of spacetime—i.e., they are all gravitational in origin.

70. Four-space (4-space): a 4-dimensional spacetime, dimensionally composed of length cubed multiplied by time. In the absence of gravitational field, the 4-d spacetime reduces to a Minkowski space.

71. Fractional charge: a hypothetical particle having a charge less than the electron's charge. Often called a quark, where its charge is 1/3 or 2/3 the charge of the electron. Recently, Stanford University researchers have found evidence of free quarks, and in the 1920's Ehrenhaft reported the discovery and production of fractional charges of all sizes.

72. Frame (Lorentz): a frame of reference which is not accelerated with respect to the laboratory observer. In this case, the frame may be rotated (moving at a constant velocity) but it is not rotating (the frame is not accelerated with respect to the observer, and spacetime is not curved). In this case special relativity applies, as do the conservation laws. If the local spacetime is curved, the frame is accelerated and spacetime is curved. Locally, then, general relativity applies. In this case, locally the conservation laws (energy, momentum, charge, and spin) can be violated. However, in ordinary general relativity, it has been tacitly assumed that locally the curvature of spacetime is negligible. Hence locally a Lorentz frame is assumed, and the conservation laws are assumed to apply locally also. In scalar electromagnetics, the local spacetime is always curved and general relativity applies locally. In this case, the conservation laws need not apply.

73. Frame (of reference): a spatial, organized, measured lattice placed in emptiness (space, spacetime). Normally refers to a 3-dimensional, spatial frame. All objects and points in the "universe" or spatial frame are considered to simultaneously coexist at separate, measured points in the frame. Differs from the vacuum in that, rigorously, vacuum has no existing definite lengths and no existing definite time intervals, as these appear only after measurement/detection, and are relative to the observer and to the detection process. The "laboratory frame" is the static reference frame of the observer/measurement. A separate reference frame may be assumed to exist for any fixed or moving object, or centered on any point in another frame. When a type of frame is assumed, the entire class of physical interactions that can occur has been restricted to an assumed set or type. In other words, given the frame, the physics has been assumed. One of the greatest restrictions of an assumed "frame" is to rule out the consideration (existence) of other higher dimensions. In the new theory, higher dimensions are permitted

and an orthogonally rotated frame can be equated to a field and vice versa. Therefore frames are also fields.

74. Free energy: energy obtained from a free or essentially free source. A paddlewheel in a river extracts and provides "free energy" from the river, since one need not pay for the river. Electromagnetically, the idea of "tapping" or extracting energy from an esoteric source, such as the zero-point energy of vacuum, the Dirac sea, a standing electrogravitational curvature of local spacetime, etc. Since scalar electromagnetics is electrogravitation, a locally bent spacetime can be achieved so as to provide either a source or a sink, as one wishes. Thus a practical free energy device is rigorously possible by scalar electromagnetic means.

75. Fusion (action): in the new approach, the recombining of two canonical bits of a fissioned action quantum. The fusion process "cancels" the bits produced by the fission process, and constitutes a negative spacetime operation. The physical world is thus eliminated, bit by bit, in a monocular fusion operation that produces the "past" The "mass" of a particle is taken to be proportional to, and identically comprised of, the absolute value of its fission and fusion rate. When fission and fusion rates of a particle are equal, the particle is unaccelerated; when unequal, the particle is accelerated. Vice versa, when the particle is unaccelerated, the fission and fusion rates are equal, and when the particle is accelerated, the fission and fusion rates are unequal.

76. Geiger tube (Geiger-Muller tube): a tube used in appropriate circuits to detect and count ionizing particles. Each particle crossing the tube causes ionization of the gas in the tube, essentially independent of the energy and nature of the nuclear particle. Thus a uniform discharge occurs across the tube. The tube will detect anything which causes an increase in the ionization of its gas. Since strong scalar waves will do this, the tube is capable of detecting scalar wave radiation of sufficient intensity. In many cases, GM tubes are activated near UFO landing zones, and sometimes near cattle mutilations or other paranormal occurrences. In such cases, the tube is reacting to scalar emissions, not nuclear radiations.

77. Geller effect: refers to the frequent stimulation of paranormal abilities in children and other people who have seen Uri Geller (or someone like him) performing psychokinesis either in person or on television.

78. General relativity: the physics of curved spacetime. As opposed to special relativity which deals with inertial frames moving at constant velocities with respect to each other (Lorentz frames), general relativity deals with accelerated frames. General relativity was founded by Einstein, who made highly restrictive assumptions to simply the complexity of the problem. Briefly, Einstein assumed that, since no means of appreciably curving spacetime was known except by the gravitational force of a tremendous collection of mass, then the only places where appreciably curved spacetime would be met would be near suns, stars, etc. Accordingly, he assumed that the local spacetime of the observer would not be curved, and instead the local frame would be a Lorentz frame. That is, he made the theory a sort of "special relativity with distant perturbations." That way, the conservation laws would be saved, and one could still speak of the energy of objects as opposed to the energy of entire systems. General relativity complete with this severe restriction is called "ordinary general relativity" (OGR), and this is the type of relativity taught in all our Western universities. Note that, by assuming no local spacetime curvature, the ordinary theory actually assumes that one cannot directly (locally) engineer general relativity. OGR is a highly special case, and not at all the type of general relativity we seek in the new approach where we wish to deliberately curve local spacetime and engineer general relativity directly on the laboratory bench. The Soviets do not recognize Einstein's limiting assumption. In Soviet physics journals, papers are regularly published that treat general relativity in an unrestricted manner. These papers include local curvature of spacetime and violation of all the conservation laws as a result. In the West, conservation has been raised to an absolute dogma, and such papers are regularly refused publication. Conservation laws are upheld in the West by artifice and dictum, not by science or experiment! So if the various restrictive assumptions placed on ordinary general relativity are removed, then an "unrestricted general relativity" results. In this relativity, the local frame may be appreciably curved, and any or all of the conservation laws can be violated—often with ease. With an adaptation of Kaluza-Klein 5-d unified field geometry and use of artificial EM potentials deliberately created by summing or multiplying EM force field vectors to vector zeros, EM energy can be transformed into gravitational field energy locally. In this fashion one can engineer general relativity; violate conservation of charge, energy-momentum, and spin; produce free energy engines; transmute elements simply; and produce action at a distance. Initial experiments have positively established the new approach as valid, and a startling new physics is in the offing. In the new scalar EM, gravitational potential becomes locked-up (infolded) electromagnetic forces, and electromagnetic force fields become bleed-off (outfolding) of the inner contents of the gravitational potential.

79. Ghost rockets: materialized tulpoidal "rockets" that appeared in 1946 and 1947 over the Scandinavian countries (Norway, Denmark, and Sweden) and usually seemed to come from the direction of the Soviet Union.

80. Giant photon: a photon with an organized, deliberate scalar substructure. In scalar electromagnetics, the photon is assumed to be one oscillation of the electromagnetic field; thus it is comprised of one E-field wave and one B-field wave. Further, in each point of either wave, a finite group of vectors may exist such that their vector summation or multiplication is zero. Thus a deterministic substructure may be deliberately impressed upon (infolded in) the photon. Such a photon may carry enormous infolded energy in the form of anenergy, and may be designed to perform a particular resonant purpose. In other words, such a photon becomes a "vacuum engine" that structures the virtual particle flux of vacuum in a particular, deterministic manner.

81. Golden booster: a potent scalar wave generator invented by Frank Golden, and used to augment and amplify the Kelly radionics machine. The booster has the unique characteristic of gathering in ambient energy and EM radiation from its surroundings and transposing this into highly patterned scalar radiation. It has the further characteristic of reacting to human intent, and constructing its patterning accordingly. In addition, two motors are incorporated whose needle movements provide

visual indication of the rate of treatment, the frequency of treatment, and how the dosage is progressing. A Bedini scalar wave detector directly verifies that both the Golden Booster and the Kelly radionics machine produce and radiate potent scalar waves.

82. Golden, Frank: inventor and scalar electromagnetics researcher who has developed a variety of scalar wave antennas, an underwater communications system, scalar wave transmitters and receivers, the Golden Booster, scalar wave detectors, and scalar wave spectrum analyzers. He has also developed a prototype free energy motor, a motor that runs off reactive power, a solid state scalar radar antenna, and other significant scalar EM devices.

83. Good: refers to an act theoretically beneficial to the receiver or referent, in the positive time stream. It is equally detrimental to the referent, viewed in the negative time stream.

84. Gravitational field: rigorously, the curvature of spacetime. In scalar EM, gravitational potential is locked-up (infolded) electromagnetic forces which sum or multiply to zero. Electromagnetic force fields represent the "bleeding off" or "outfolding" of these infolded contents of gravitational potential. Gravitational force field is the "bleeding down" of the gravitational potential without outfolding or out-bleeding its infolded contents. Gravitational field is not a field in the sense of Heaviside-Maxwell electromagnetic fields. There is really no such thing as "the" gravitational field; instead, there exists a large number of potentials, locked-in force field vectors, and other entities which change the energy density of vacuum and bend spacetime. The bleed-down of this conglomeration infolded components as a conglomeration constitutes the "gravitational field." If the inner contents of this G-field, or of the G-potential, bleed out, then a different field—e.g., electromagnetic field—is produced. We may thus speak of the bleed-out of either the G-potential or the G-field. Note that flows between pairs, triads, etc. of these individual infolded field components can occur without appreciable change of the overall conglomerate's potential (trapped energy density). Thus the gravitational potential can have a dynamic, structured pattern, and local spacetime can be curved and patterned. E field and B field are one such "pair" of flows where little overall gravitational effects are evidenced, so long as the fields are tree to "flow." In Kaluza-Klein 5-d unification of gravitation and electromagnetics, only a single field—the 5-dimensional gravitational field—really exists. Our world intersects and "bleeds-off' this 5-d G-field in two fashions: (1) the 5-d G-field prefers to bleed-out into its fifth dimensional aspect, which we see as our own ordinary EM force field. (2) The minute remaining 4-d aspects we see as our 4-d gravitational field. To show the order of magnitude difference in bleed-out, the electrical field between two electrons is about 10^{42} or so stronger than the gravitational field between them. Even for protons, the ratio is 10^{36} or so. So it can be seen that, so long as EM bleed-out is permitted, little 4-d gravitational effects are produced. Our normal electromagnetics—which by construction of Heaviside's version of Maxwell's theory is purely bleed-out, thus yields negligible gravitational effects. On the other hand, if we deliberately set the EM bleed-outs against each other so that they zero sum, we "strangle" the escape or bleed-off of the 5-d G-field into EM field. The 5-d G-field is then forced to bleed-off into 4-d G-field. If we then vary the energy of each vector component of the EM zero sum while maintaining the overall zero resultant, we directly pump the 4-d gravitational field. Scalar electromagnetics thus directly converts EM field, force, and energy into ordinary G-field force and energy, and vice versa. In addition, we get enormous gains: For every unit of EM energy we feed into the "zero sum pump," theoretically we can get out up to 10^{42} units of 4-d gravitational/inertial energy by electron release, and up to 10^{36} by proton release. Experimental results have confirmed this thesis. As early as 1969, Hurvich produced an inertial field generator capable of "freezing" weapons so they cannot be fired. Hutchison reports and demonstrates the levitating of up to 60-lb. objects. The American physicist Hooper patented electrogravitational devices in the early 70's. Bedini, Watson, Johnson and others have developed practical prototype "free energy generators." Another inventor who wishes anonymity has developed a small device which produces negative energy and antigravity, at an amplification factor of 1,500,000. Orthodox research in this area is just beginning in the West, but has been highly developed for several decades in the Soviet Union.

85. Gravitostriction: effect in a resistor whereby local gravitational stress flow in a direction results in production of a macroscopic electric force field in that direction, a macroscopic magnetic force field orthogonally around that direction, and minute, randomized EM fields (heat energy) microscopically due to induced microscopic particle motion and interaction. It is the enforced spin alignment of the mass particles (such as conduction electrons) which accounts for the production of the magnetic field. Gravitostriction is the reason that resistive loads can be powered by scalar anenergy flow (electrogravitational flow, massless current flow) and by negative energy flow. During the initial chargeup of a helical coil exposed to a sine wave voltage, no electron mass current flows; however, the massless current (phi-dot) charges up the coil gravitationally. As electron mass current begins to flow (90 degrees into the wave), this gravitational field is bled-off (outfolded) as electric force field (electron mass flow coupled to del phi) and magnetic force field. One can do amazing things with coils and transformers which are not allowed to enter the EM bleed-off phase at greater than 90 degrees

86. Gravity: the phenomenon characterized by the physical attraction of any two material bodies. Ideally, the gravitational force between two masses is proportional to the product of the masses divided by the square of the distance between them. In the new approach, one recognizes that mass itself is defined in terms of, and identically consists of, the time derivative of an action flux. Gravitational field and electrical field, then, become different aspects of the same thing. By affecting the flow of time, scalar waves and scalar potential thus are able to affect the gravitational force between two objects. Antigravity, for example, can be achieved by forcing an object's atomic nuclei to produce phase conjugate (time-reversed) waves (and negative energy and negative time). In negative time, gravity is a repulsion. Hutchinson has demonstrated the levitation of objects weighing up to 60 lbs, albeit sporadically.

87. H-field: historically, the magnetic field. However, it

is poorly named, and should be considered the magnetic excitation, after Sommerfeld. In empty space B and H are proportional, an experimentally determined fact In the new approach, rigorously vector fields cannot exist in vacuum, but can only exist on an observable mass. A "shadow" vector field can exist in vacuum, in the absence of observable mass, as small virtual vectors, each existing on a virtual particle in the vacuum. Such a "shadow" vector field may be regarded as two coupled scalar fields, where the coupling is performed by the virtual particle flux of which the vacuum itself consists. When an observable, spinning charged mass encounters the shadow vector field, it converts the two coupled scalar fields into a vector field. Thus Hertz waves per se are not transmitted through vacuum; "shadow" Hertz waves arc. With an ordinary detector, however, one detects vector Hertz waves, since one detects the precession waves of the electrons in the electron gas of the detecting probe or antenna.

88. Hieronymus, T. Galen: renowned radionics experimenter and inventor of the amplified radionics machine. Hieronymus is the father of modern amplified radionics; most experimenters before him used unamplified machines.

89. Hieronymus device: essentially, an amplified radionics device. Refers to a device similar to the one patented by T. G. Hieronymus in the 1940's. Connotes ordinary amplification rather than holographic amplification of radionics effects. Any similar type device. The Hieronymus device actually processes, and operates with, scalar waves.

90. Hologram: a photographic recording of the pattern of interference between coherent light reflected from the object of interest, and light that comes directly from the same source or is reflected from a mirror. When this photo image is illuminated from behind by coherent light, a three-dimensional image of the object appears in space. The characteristic of a hypothetically perfect hologram is that all its content is contained in any finite part of itself. If one portion is cut out and illuminated, the complete image appears in space. The whole hologram is in each part of itself. Observationally and perceptually, the physical universe is a hologram and in each part of itself, since all of it can be detected from/in each internal particle.

91. Hyperchannel: a channel between orthogonal frames or hyperframes, where anenergies crosstalk. Exceptionally good hyperchannels seem to be frequency dependent, and are referred to as windows, magic windows, or interdimensional nodal points. Some hyperchannels are 38-40 kHz, 150-160 kHz, 1.1-1.3 MHz, 1.057 GHz (the Lamb shift), and in the near ultraviolet (the life force frequency). These frequencies also represent enhanced channels between subquantal (virtual) and quantal (observable) states. A particularly good magic window exists when the infrared and ultraviolet bands being utilized are phase-locked so that the ultraviolet represents a first harmonic of the infrared.

92. Hyperfield: a structure or disturbance in hyperspace or higher dimensional space. With respect to a fixed frame, the electromagnetic field or a more subtle field. We consider the electromagnetic field the first hyperfield. A hyperfield may also be considered to be the electromagnetic field rotated further away from its laboratory frame. The second hyperfield is called the neutrinic field, and the third hyperfield is the mental or mind field. Also called bioframe, orthoframe, hyperframe, biofield, or orthofield. These hyperfields/hyperspaces also correspond to the nested levels of virtual state. Successively higher hyperfields past the electromagnetic field constitute successively lower levels of virtual state.

93. Hyperframe: simply, a frame rotated one or more right angle (orthogonal) turns away from the reference laboratory frame. The laboratory frame is considered to be the zeroth hyperframe. Also called bioframe, bioworld, biofield, orthoframe, orthoworld, orthofield, hyperfield, or hyperworld. Sometimes referred to as a hyperspace.

94. Hyperspace: generically, refers to hyperframes, orthoworlds, etc. May be used in a singular sense to refer to one of these.

95. Hyperspace howitzer: a postulated Soviet scalar electromagnetics interferometer weapon, believed capable of firing an explosion through hyperspace to a distant point, without any travel of electromagnetic energy through ordinary space. Also called a scalar howitzer or Tesla howitzer. The howitzer has several modes of operation: (1) it can be used in exothermic or endothermic mode. In the exothermic mode, the howitzer is biased positively. In this mode it can accept energy, transform it into scalar waves of an artificial potential or anenergy, transmit the scalar waves to a distant intersection zone, interfere them and reproduce ordinary positive electromagnetic energy in the distant region. In the endothermic mode, the howitzer is biased negatively. In this mode it "transmits" the extraction of energy. At the distant interference zone, energy is extracted and reappears back at the transmitter/receiver site, where it must be disposed of. U.S. weather satellite photos of the Soviet Union's Bennett Island reveal giant exhausts emerging from that island, some narrow jets as long as 150 miles and only about 1.5 degrees above the horizontal. Bennett Island is believed to be the "exhaust site" for several Soviet hyperspace howitzers. That is, when a howitzer operates in the endothermic mode, it receives and temporarily holds the energy that comes back to it, then switches biasing potential to positive and transmits in the exothermic mode to Bennett Island. (2) The howitzer can operate in pulsed or continuous mode. In pulsed mode, an explosive or implosive effect occurs at the distant target site. In continuous mode, a continuous energy source or sink appears in th distant interference zone. (3) Fourier expansion mode. Each transmitter of the howitzer can produce multiple frequencies where the frequencies represent a Fourier expansion of a geometrical form such as a sphere. When these two geometrical scalar forms are interfered at a distance, a 3-dimensional form of ordinary EM energy emerges (exothermic mode) or is extracted (endothermic mode). (4) the scalar transmissions of the scalar interferometer (hyperspace howitzer) can be modulated upon ordinary EM carriers, such as the Woodpecker signals in the communications band (3 to 30 megaHertz). In this case, interference patterns of the Woodpecker carrier will yield only minute EM energy, but the impressed scalar substructures may interfere to produce or extract substantial energy in or front the interference zone. Other control signals impressed on the Woodpeckers may be used to trigger the mode and location in the interference zone, or even to establish "circulations" in the vector zeros. By forming distant high pressure zones (exothermic mode) and low pressure zones (endothermic mode) and then moving the locations along, the Soviets can capture and deviate the jet streams over North America or elsewhere. By swirling in conjunction, tornadoes can be produced. Certain signatures (giant radial clouds and twin giant radial clouds) in the active zone have been identified as associated with the Soviet Union's weather engineering. The strange explosion in 1958 near the Urals is believed to have been an accident involving an early first fullup test of the howitzer. The howitzer was probably similar to a giant radar, transmitting scalar EM wave. By setting up a standing scalar wave and continuing to transmit energy into it, the standing wave becomes a giant potential. It is charged up much like a scalar capacitor, but with scalar EM (electrogravitational) energy. Failure of the transmitter may have discharged this giant potential into the earth, and the electrogravitational ground pulse spread out, striking the nearby stored nuclear wastes and fissioning all the radioactive nuclei. Consequently the nearby atomic wastes exploded, producing fallout and radioactive contamination over a large area. The first fullup test of an operational on-site weapon is believed to have been the destruction of the U.S.S. Thresher atomic submarine on April 10, 1963. The second fullup test is believed to have been the transmission of an explosion into the ocean 100 miles north of Puerto Rico on April 11, 1963—one day after the destruction of the Thresher. Over a hundred howitzers are believed to now be on site and operational, and powered by either Moray amplifiers or giant scalar resonant inference taps in the earth (detected by Golden in April 1985). High Altitude booms off the east coast of the U.S. may have been due to orientation and alignment tests of these weapons, with each test blast the equivalent of some 100 tons of ordinary explosives. If so, these shots were probably artillery high burst registrations. The two puzzling flashes detected by the Vela satellites in September 1979 and later, and erroneously described as a nuclear flash by many analysts, may also have been a test of this type of weapon, either by the Soviets or a second nation that has developed the weapons.

96. Hyperworld: a world (3-space or 4-space) rotated one or more orthogonal turns away from the laboratory frame (ordinary world). Constitutes also (identically) an entire subquantal level in virtual state.

97. Inception: kindling (from mind anenergy) a small amount of photon energy into or onto a body/tuner or other object Specifically, coupling scalar wave patterns (anenergy) onto die body/tuner or object so that the photon energy is created in or on the body at a distance.

98. Inceptive cyborg effect: the ability of the mind to psychokinetically link to, or attune to, an inert physical object or physical system. A living biological system is a stabilized inceptive cyborg, with its mindworld linked to its body/tuner. The two cerebral hemispheres of the brain form a Tesla scalar interferometer, capable of producing and transmitting scalar wave patterns into a distant object, coupling into energy in it, and thus linking with or resonating with the object. This is the mechanism for producing all parapsychological phenomena.

99. Interdimensional nodal point: a natural frequency for an anenergy channel between orthogonal frames or universes. Also called a magic window.

100. Interference: the variation of the amplitude of a wave with distance and time, where that wave results from the superposition of two waves having the same, or nearly the same, frequency.

101. Interferometer: an instrument in which a wave is split into two waves or beams, which after traveling over different paths are subsequently reunited and display interference.

102. Jitter (dither): the incessant quantum and subquantum activity on a fundamental particle of mass. The particle is continually connected to and disconnected from an infinite number of hyperspaces, and to and from time.

103. Kaznacheyev effect: refers to the demonstrated ability of near-ultraviolet mitogenetic photons to carry any kind of death pattern from one cell culture to another of similar kind, in the absence of visible light and with synchronized conditions. Named after the Soviet scientist Vlail P. Kaznacheyev, who experimentally demonstrated the effect In his experiments, two samples of the same cell culture were environmentally separated by a thin window. The entire arrangement was placed in the dark and rotated at some 20 rotations per minute. The cells on one side were then killed by any particular mechanism—ionizing radiation, chemicals, toxins, deadly bacteria, germs, etc. If the window was made of ordinary glass (opaque to ultraviolet), the second sample remained healthy. If the window was made of thin quartz (transparent to ultraviolet), then after a time delay the second sample began dying with the same symptoms ai the first Later testing revealed the emission of mitogenetic, laser-like photons in the near ultraviolet from the dying cells in the first culture. When these mito genetic photons are allowed to bombard the second cultare, the same lethality pattern is induced in it. The explanation is that the photons carry virtual state (scalar) patterns (infolded patterns in their time components), and these virtual patterns are diffused into the receiving culture, where eventually they diffuse into a lethal pattern in the virtual state (scalar) master control system (discovered by F. A. Popp) of the targeted cells. Continued charge—up of this pattern kindles the pattern into a physical, observable structure in the cells, reproducing the death or disease pattern. The Kaznacheyev effect haa been duplicated in the infrared in West Germany. Kaznacheyev almost certainly also phase conjugated (time-reversed) the "death photons," producing healing photons for that specific cellular damage or disease condition. Irradiation of the affected cells with these healing photons would have reversed the disease, reverting the cells to normal. Note that Antoine Priore's machine worked in this fashion. Kaznacheyev's EM healing work with phase conjugated photons was obviously not reported; it represents a total counter to viral biological warfare, and such work would have been done only under KGB control, and highly classified as a vastly valuable defense secret.

104. Kelly, Peter: noted radionics/psychotronict researcher and builder of several types of especially potent amplified radionics machines. He is also one of the pioneers of the use of amplified radionics in agriculture for enhancement of crops, restoration of soil vitality, and control of insects. By direct measurement with Bedini scalar EM detectors, Kelly's machines have been verified to produce scalar waves.

105. Kelly machines: amplified radionics machines developed and built by Peter Kelly.

106. Kervran effect: the ability of a living biological system (either plant or animal) to accomplish limited transmutation of elements, particularly between certain isomers. Named after the French scientist, Louis Kervran, who discovered the effect. Kervran was nominated for a Nobel prize in 1977, although the prize was not awarded to him. The Kervran effect has been duplicated by Japanese, British, European, American and other scientists. Note that scalar interferometry is capable of kindling energy patterns directly into the virtual state interactions of the nucleus, including the strong force that binds the nucleons together. Over a period of time, this energy can cumulate, biasing the quantal statistics of the interactions. This, of course, changes the probabilities of the various quantal states, with the result that the nucleus can be transmuted. Transmutation to an isomer is particularly practicable. Efficient transmutation of elements by scalar means has been accomplished by John Bedini.

107. Kindling: collecting and condensing more subtle energies (anenergy) into virtual photons (charge effects), photons (electromagnetic field effects), or matter (materialization effects). Kindling is a linear integration process, which repeatedly collects or integrates a virtual state pattern until it breaches th observable threshold, becoming physical real.

108. Kirlian photography: field patterns of an object impressed upon a film or other sensitive material by means of spark discharges. The scalar modulations in the spark charge intensity, not the ordinary vector E-field components, are the paranormal components. Thus only the delta—which represents those scalar patterns coupling and kindling into vector EM, which then interacts in photochemical interactions—is indicative of the paranormal aspect of Kirlian photography.

109. Law of physics: a restriction placed upon the physical mechanisms that can occur under certain broad assumptions as to the background situation and environment. Actually, in nature there are no such "laws"; these are only man's synthesis for the behavior of large classes of systems under very general conditions. Any "law of physics" can be violated if the conditions contained in its assumptions are violated. Conservation laws are often touted as "laws of physics." Actually, the conservation laws assume a closed system and a linear spacetime (Lorentz frame). If either or both of these assumptions is violated, any or all of the conservation laws can be violated. In particle physics, broken symmetry already results in violation of one or more of the conservation laws. In leading Soviet physics journals, papers are regularly published containing unrestricted general relativity with concomitant violation of any and all conservation laws.

110. LIDA machine: Soviet device which uses a 40 megahertz carrier and unusual waveforms to induce a catatonic-like state in man or other mammals. For years Western orthodox scientists have argued that EM signals could not directly affect consciousness. With testing of the LIDA device, this has now been totally refuted. One scientist has reported that the I.IDA device—known to be decades old—was used by the North Koreans on some U.S. prisoners of war during the Korean War. Reportedly the effects of the machine could not be resisted, and the machine was a devastatingly effective "brainwaahlng" tool.

111. Life: a term which resists the best efforts of philosophers and scientists to define it! In the new approach, a living system is modeled as consisting of a physical body "tuner" and a mindworld to which the tuner is preferentially tuned to a small degree. The preferential virtual state crosstalk between the physical tuner and the mindworld constitutes the life channel or consciousness loop. Destruction or loss of the preferential tuning results in "death," or loss of attachment to the tuner. In that case the mindworld functions within itself. Note that the being is always present, unchanging, and simply "is," without any connotation of perceptual stringing together separations into a string of events (causal chains). Being changeless, it consists of all changes, all-at-once, hence none separately. Ultimately this is the true meaning and foundation of life, and mindworlds and physical events represent simply separation waves in unlimited being. Note this is completely consistent with the idea that ulti mately only God exists, things are simply separation waves in the unseparated Godness, and God permeates everything.

112. Loch Ness Monster: famous tulpoidal water monster which (occasionally) temporarily materializes in Loch Ness in Scotland. Similar materializations of "water monsters" have been seen and reported in almost every large body of water on earth.

113. Longitudinal wave: a "pressure" type of wave, similar to sound, in which the vibrations are along the direction of travel of the wave. Hence, a wave composed of alternating densifications and rarefactions. Scalar waves are longitudinal waves. In classical EM theory, the Poynting vector predicts no longitudinal wave of energy from a time—varying, electrically charged source. In fact, an exact solution of the problem does allow this longitudinal wave, as shown by Keech and Corun, International Journal of Theoretical Physics, Vol. 20, No. 1, 1981, pp. 63-68. The classical electromagnetic wave is modeled as a vector wave, comprised of transverse vibrations. In the new approach, such transverse vector force field waves (Hertz waves) do not exist in vacuum; instead, two coupled longitudinal scalar waves exist in vacuum. The E and B fields are formed, recovered by, and exist as the spinning charged detecting mass particle in motion.

114. Magic window: a naturally tuned frequency of a good hyperchannel between orthogonal frames where scalar wave anenergies crosstalk readily. Magic windows are frequency dependent, and are also referred to as hyperchannels or interdimensional nodal points. Some magic windows are 38-40 kHz, 150-160 kHz, 1.1-1.3 MHz, 1.057 GHz (the Lamb shift), and in the near ultraviolet (the life energy frequency).

115. Many-worlds interpretation of quantum mechanics: refers to the consideration of multiple simultaneous observers and the consequent changes forced upon quantum physics. Essentially all possibilities exist and are real, and an infinite number of orthogonal worlds exist at any instant. Further, each world splits into multiple possibilities after each and every event. Thus in a single second, the world has split in some 10 to the 20th power versions of itself. This is the work primarily of Everett, with strong contributions by Wheeler and

Graham, and was the subject of Everett's thesis at Princeton University in 1956. It was published in 1957.

116. Mass: literally, a special curvature or "kink" in spacetime emptiness, according to relativity theory. In the new approach, the mass and inertia of a particle are considered to be due to one or more standing scalar resonances, trapped by the spin of the particle. When the amplitude of the trapped scalar wave increases or decreases, the mass and inertial of the particle increase or decrease. If the resonance amplitude reduces to zero, the particle dematerializes. Classically, mass is also taken as the measure of a body's resistance to being accelerated by a force. Specifically, a mass occupies space (3-dimensional) and resists change in its linear movement. In a region of mass, a flux of action quanta into and out of the region exists, corresponding to a flow of positive and negative time. The mass is the sum of the absolute values of the time derivative of action in and the time derivative of action out If these two time derivatives are equal in magnitude, the mass is unaccelerated; if unequal, the mass is accelerated. A mass does not exist in time per se (more rigorously, it exists equally in positive time and in negative time), but only exists spatially. A mass continually interacts with photons (absorption and emission), thus continually connecting and disconnecting to the fourth dimension (time). The mass is thus seen to "jump along" through time in finite, quantized jumps caused by the photon interaction with it

117. Men-in-black: that part of the UFO contact phenomena which involves contact with rather sinister tulpoidal manforms. Typically these tulpoids are dressed in dark suits, have almond-shaped eyes that do not blink, possess oriental features, and "speak" telepathically to the contactee. Often they drive dark automobiles and follow the contactee. Several researchers in the field have had intense encounters with such tulpoids. The appearance of such phenomena associated with an investigator is in part due to unresolved detrimental material in his or her own unconscious mind, which thus acts as a "witness" and radionics tuner. Continual stimulation of this detrimental unconscious witness by the person's investigative activities results in the appearance of, and contact with, such tulpoids. The more detrimental aspects of such tulpoidal tuning can be prevented by psychic clearance of the investigator, particularly of his unconscious mind. Such psychic clearance at regular intervals is highly recommended for investigators pursuing the more bizarre aspects of the field, such as cattle mutilation, men-in-black, sasquatch, possessions, etc.

118. Metal bending: term applied to the psychokinetic bending and breaking of metal objects such as cutlery, rods, bars, etc. When a metal rod is psychokinetically bent, then cross-sectioned and examined under the electron microscope, microscopic "puddling", as if by localized, point source intense heating, can be seen, with concomitant disruption of the metallic grain structure. In a severe case, the cross section looks like the puddled surface of the moon. The mechanism responsible for the psychokinetic bending is exothermic scalar interferometry by the two cerebral hemispheres, where the intersection zone is the metal object being bent

119. Metapsychology: literally, "before psychology." The deeper psychology of the group mind, particularly the collective human unconscious mind. Although the Cartesian idea of the separation of mind and matter usually applies to the individual conscious mind, it does not apply to the group unconscious mind. The collective human unconscious mind is a living being, though unconscious, and is capable of materializing its "dreams" into actual physical forms and beings.

120. Microcrystals: tiny crystals, particularly those used by George Yao in construction of his pulsors. Use of the microcrystal in proprietary manners enables Yao to build devices which react to scalar resonance and human intent, and which can generate negation patterns for potentially harmful "deltas" or changes that occur in the human etheric field (aura).

121. Miller/Fox/Urey effects (experiments): these experiments simulated the primitive conditions believed to have existed in and over the primeval oceans. Water—with its complement of minerals and chemicals—and gases to simulate the primeval atmosphere were placed in a beaker and subjected to ultraviolet radiation and electrical discharges. Thus the experiments simulated the great lightning discharges into the primeval oceans. In the laboratory, amino acids are formed, then proteinoids. If the experiments are performed in the presence of heating (simulating the presence of volcanic activity, for example), then primitive microspheric cells are formed with double cellular walls. These microspheric cells even reproduce by cell division. Thus at least simple lifeforms have been produced in the laboratory. Indeed, in the new model even inert matter is totally alive, but unpreferentially. Also, every possible sort of mind exists. Thus all that is necessary to form a living system with any desired characteristics is to form the appropriate type of physical tuner. A living system is like a television set existing in a flux of radiations from an infinite set of channels/stations. The set tunes preferentially to one channel/station, but any desired channel can be tuned, simply by changing the characteristics of the tuner. One does not "create" life, one simply "tunes it in selectively." In this concept rigorously there is no such thing as "death", but only transition from one state to another.

122. Mind: a quite misunderstood concept! In conventional science, it is considered purely robotic—i.e., it is the sum total of the electromechanical neural processes which receive, code, and interpret sensations, recall and correlate stored information, and act upon it Also considered to be the understanding, reasoning, and intellectual faculties considered as a whole, that is, as the conscious portion. Also considered as the psyche, including the conscious, subconscious, and unconscious portions, considered as a whole. The new approach is more in accord with the latter definition. Simply put, the mind is a world composed of separation events (waves, operations, processes) in unseparated being. We may model it (to a first crude approximation) as a physical universe, three orthogonal turns away from the ordinary physical universe, and tuned slightly selectively to one physical organism's physical body processes. Mind anenergy is considered to be progressively collected, condensed, and kindled into denser substance and objects by rotation toward the ordinary physical world. Thus a piece of inert matter is simply condensed energy, which itself is condensed anenergy, which is condensed mind flux (crosstalk) from all minds. One may model the mind physically, or model the physical as mindstuff, eliminating the artificial dichotomy between mind and matter that presently is assumed in orthodox science. Since per-

ception of thought *is* fragmentation and separation of mind, die mind cannot be perceptually conscious of itself, but only of its separated fragments (thoughts). When the incessant activity of the mind is stilled, however, the stable mind is in its pure state—pure being. In this state there is no separation of the observer and the observed. With attainment of this state, one "realizes" or experiences one's true God-nature. It is theoretically possible to build a scalar wave detector that can directly "see" thoughts. Indeed, the first prototype of this type detector may have already been built by one physicist experimenting with a very sensitive scalar wave detector.

123. Mind linkage: the integrating of two or more minds into a single overall functional mind. A living example is in each human head: the two cerebral hemispheres—each containing its own separate mind—are integrated into one overall brain having a single functional mind. This is accomplished by signals interconnecting the two cerebral hemispheres through the corpus callosum. Note that the "separated beings" of the two minds are also merged/linked into one greater being. The tuned separation of individual humans (caused by the continual photon interactions with each particle of mass in the body tuner) is responsible for all man's inhumanity to his fellow man, for each now perceives others as separate things or "objects." With mind linkage, the human species will emerge as a single great entity, having not only • single "collective unconscious," but also a single "collective conscious" mind. Proof that linkage can be accomplished is already demonstrated by each individual. The problem of resolving all man's inhumanity to his fellow man is thus a technical problem, not just a moral/philosophical problem.

124. Mitogenetic radiation: laser-like, coherent photons emitted by cells, particularly in the near ultraviolet Of particular importance are the photon emitted by a cell immediately after complete fertilization, and the photon emitted as the cell dies. The first mitogenetic photon signifies the kindled connection of the cell's small mindworld and the establishing of the consciousness or life loop. The second mitogenetic photon signifies the loss of tuning and consequent loss of the consciousness or life loop. The photon at cellular fertilization is a joyous song of birth, and the photon at cellular death is a deathsong of the cell. In addition, the birth photon carries the full mindworld pattern nested inside it in the virtual (scalar) state, and the death photon carries the full pattern of the cell's experiences and death nested inside it in the virtual (scalar) state.

125. Monocular (change): one at a time. Change as seen by only a single observer at a time. This type change is provided by the photon interaction with matter, and the "memory hold" of a large number of such monocular changes constitutes the "perceived/detected physical reality" we conceive we exist in.

126. Moray amplifier: free energy device developed by T. Henry Moray of Salt Lake City, Utah in the 1920's and 30's. The device was destroyed by a double agent (an F.B.I, agent and also a Soviet agent) in 1939, after the agent had obtained the drawings of the device and worked in Moray's laboratory for several months. The final device had some 29 detector stages and produced an output of 50 kilowatts of power, without input.

127. Moray, T. Henry: early experimenter and pioneer in radiant energy, who developed one of the most widely demonstrated and best authenticated free energy devices. Moray's device was a collector/amplifier that eventually produced 50 kilowatts of output power.

128. Multiocular (change): more than one at a time. Change as seen by multiple simultaneous observers. Consideration of this type change leads to an infinite dimensional, multiworld or multiuniverse reality similar to the type described by Everett. If one accepts multiple simultaneous observers, then this expanded and startling view of reality is inescapable. If one accepts only a single observer at a time (as does present physics), then there exists only a single living person, and everyone and everything else is simply a figment of his or her imagination.

129. Mystery light: another name for a nocturnal light, or earthstress light, produced by natural scalar transmission interferometry of the cracked rock structures in the earth's crust

130. Neurophone: an instrument for direct electomagnetic input of signals into the human brain and nervous system. The neurophone was invented by Pat Flanagan when a boy of seventeen. The improved version, invented much later by Flanagan, clips an input signal, differentiates it twice, then feeds the resulting noisy spikes into the human sensory system. The original signal is impressed into the brain and directly into the mind. An adaptation of the neurophone, using more than eleven independent frequencies and built in accord with Soviet work reported by Lisitsyn, could conceivably be utilized to accomplish human mind linkage.

131. Neutrinic wave: a bare neutrino, considered as a wave instead of a particle. It is a special kind of polarization wave to the laboratory observer, and interacts with his electromagnetic field. It is essentially a longitudinal scalar wave, which moves in and on ordinary vector electromagnetic waves. It may also be regarded as a sort of "spin" wave, since one may consider it as moving at the speed c, but circling around a photon in a plane perpendicular to the photon's velocity in 3-space. One may thus say that the neutrinic wave moves at the velocity c-squared, but its carrier moves at the velocity c. Since we detect the speed of the carrier, detected neutrinos always appear to have moved at the speed of light.

132. Neutrino: a neutral particle believed to have zero rest mass and travel at the speed of light. One type of neutrino is associated with the electron and one type with the muon. A third type is now believed to exist There is some evidence recently of neutrinos possibly having a small mass, and of one type of neutrino turning into another type. In the new approach, the classical neutrino is a flux of much smaller particles—"bare" neutrinos—inside a photon. In the photon, one flux is taken to rotate clockwise and one flux to rotate counterclockwise (adapted from the phasor theory of Ruderfer). Further, a neutrinic flux from one half of the photon to the other is hypothetically possible, and this flux would constitute a third type of neutrino. It would exhibit mass, and would allow one type of neutrino to turn into the other. The bare neutrino (from the new approach) is of magnitude 1/c times the magnitude of the photon. Further, it moves at the speed c-squared, but since it circulates at the speed c at right angles to the motion of its photon carrier which is moving at the speed c, its detected velocity is always c, the speed of carrier. To an observer in the hyper-

frame of the electromagnetic field, a laboratory bare neutrino would appear as a photon.

133. Newman, Joseph: Mississippi inventor of a free energy machine tested and authenticated by several dozen scientists. Newman is fighting in court to obtain a patent on the device which has clearly been shown to be legitimate.

134. Newman machine: free energy device developed by Joseph Newman. While the prototype does not produce appreciable output power, it does produce an output and keeps its own small drycell batteries charged. It clearly demonstrates the principle and is a legitimate free energy device.

135. Nocturnal light: any paranormal light phenomenon seen at night. Over 80% of the UFO phenomena are nocturnal lights. Also includes phenomena such as "ghost" lights, spooklights, will 'o the wisps, etc. It specifically does not include ball lightning, St. Elmo's fire, and other such rare but normal phenomena. Most of the nocturnal light phenomena are caused by natural scalar transmission interferometry.

136. Observable (state): that part of physical reality consisting of changes (particles, waves, action changes) that are detectable by single instruments. The field on a charged particle is due to the continual emission and absorption of virtual particles. Forces between observable particles are generated by the exchange of virtual particles. Thus all observable forces, fields and changes are generated by unobservable virtual interactions, and observable and virtual reality states are inseparably enmeshed. In theory, no superluminal effect can be directly detected; however, a two-stage detection can be used to detect a superluminal entity. Usually the first stage is an interference between two superluminal entities, where the interference "downshifts" the waves to produce a wave moving at subluminal velocity. This subluminal wave then interacts with a mass such as an electron, and these interactions are accumulated to provide a macroscopic measurement indicative of the presence of the primary superluminal interferents. A two-slit box for the electron inteiference experiment is an example. Also, in quantum mechanics time is not an observable, even in theory. All observation is spatial; rigorously, there is no such thing as a clock in the purest sense. Time is always inferred from a spatial detection or measurement

137. Orgone energy: the subtle living or life energy discovered and utilized by Wilhelm Reich. Reich had discovered and utilized a portion of scalar electromagnetics (electrogravitation).

138. Orthoframe: a frame rotated away from the laboratory frame by one or more right angles. A hyperframe or biofame. Also called an orthoworld.

139. Orthogonal: simply, at right angles. The intersection of two orthogonal geometric constructs, each of dimension one or greater, is of one less dimension than the lowest dimensioned intersector.

140. Orthorotation: rotation in hyperspace of an object, form, or particle at a right angle to its starting frame. The object loses one dimension in its intersection in the original frame and gains one dimension in its intersection in the frame toward which it rotates.

141. Orthoworlds: orthogonal 3-dimensional physical worlds (frames) that share a single time dimension in their 4—spaces (spacetimes).

142. Paradox (logical): a thing that is true, but which violates one or more of the three Aristotelian laws of logic. All logical paradoxes are simply fourth-law logic cases, and—at least hypothetically—the fourth law can be applied to resolve them.

143. Paranormal phenomena: any phenomena that differ from straightforward, orthodox physical or psychological phenomena. Phenomena beyond understanding in terms of presently known science, causes, and effects. Specifically, phenomena in which mind and matter, or mind and unknown fields, or matter and unknown fields interact observably.

144. Past: reality which has been erased and has ceased to "physically (observably exist" in immediate detection/perception, and which now exists only as an infolded virtual state trace or vacuum memory. (Because the past still exists as an infolded virtual trace in vacuum, the time-reversed wave emitted from a pumped phase conjugate in four-wave mixing can retrace the past path of the wave that struck the mirror and stimulated the emission.) Fissioning of an action quantum produces a "presented" change described by canonical fragments. Fusion of the canonical fragments back into a quantum of action erases the presented real canonical fragments, reducing the "change" to the "past" However, that "fissioned pattern" or virtual substructure continues to exist, infolded into the vacuum. The vacuum retains a perfect infolded recorded memory, therefore, of every quantum change that has ever occurred. (In ancient mystery schools, the set of all such traces was called the Akashic record.) A virtual projection of the change has occurred in the mind world of the observer, however, since the mindworld is nonlocal. The coherent (causal) time-ordered collection of large numbers of such virtual projections in the mindworld reaches the quantum threshold, resulting in a quantum change in the mindworld. The "conscious mind" thus perceives physical reality as a collection of a large number of quantum changes—in short, a macroscopic reality. In actuality this "perceived macroscopic world" rigorously exists only in the mindworld, and thus it exists only in the past (Note how physicist's discussions of such quantum paradoxes as Schrodinger's Cat are erroneously based on macroscopic considerations.)

145. Phase conjugation: a nonlinear wave process whereby a nonlinear crystal, material, or medium creates a nonlinear polarization for an incoming monochromatic wave is generated at the incident frequency by w-w-w= -w. The nonlinear polarization radiates a time-reversed replica of the incoming waveform. The time-reversed waveform has an amplitude proportional to the complex conjugate of the incoming wave amplitude. Though primarily known in nonlinear optics, the time-reversed wave is a solution to the wave equation, and so the phenomenon is universal to all kinds of waves. As can be seen from (w-w)-w = -w, the first two waves modulate each other because the nonlinear medium acts as a modulator. These two waves thus "lock together" as a single scalar EM wave. The scalar wave passes through the electron shells of the atoms of the nonlinear medium, penetrating to the positively charged atomic nuclei. In a nucleus, each incident scalar photon is absorbed, increasing the potential of the nucleus to an excited state. The decay of this excited state from the positively-charged nucleus causes the emission of a time-reversed (TR) photon carrying negative energy. The "emitted shower"

of these TR photons constitutes a TR wave. Thus from the nonlinear material there is emitted a time-reversed wave. This TR wave "backtracks" through space along the invisible path taken by the original incoming wave. Since the phase conjugate wave is time-reversed, it concentrates along its backward path, rather than diverging. Consequently all its energy arrives at the distant location of the source of the original stimulus wave. The nonlinear medium producing the TR effect in response to a stimulus wave is referred to as a phase conjugate mirror. If two monochromatic EM waves w1 and w2 are fed into the nonlinear medium in antiparallel manner, so that the waves are everywhere out of phase, they modulate each other, forming a much more powerful scalar EM wave. This wave then "pumps" each nuclear potential to a much higher excited state. Thus when this potential decays, a much more powerful TR wave is emitted, containing up to all the energy put into the scalar "pump" wave. Note that the excited nuclei do not decay (the excited potential does not decay) until an incoming stimulus wave—say w4—is received. When w4 is received, then a powerful TR wave—say w3—is emitted from the phase conjugate mirror (PCM). This process is referred to as "four wave mixing." Thus a pumped PCM acts as a triodc amplifier, and the incoming stimulus wave acts as a signal on the grid. In the oscillation condition (incoming input w4 at right angles to wl and w2), infinite gain is experienced, so that all the energy in pump waves wl and w2 appear in TR wave w3. This was Nikola Tesla's secret of wireless transmission of energy at a distance without losses; the Great Electrician had discovered what we today call phase conjugation and the pumped phase conjugate mirror. He also discovered its general nature, for he understood that it applied to all kinds of waves, including mechanical waves in the earth. It has been shown that, under proper conditions, it is possible to have self-oscillation in the nonlinear crystal or medium. Such a PCM is referred to as a "self-pumped PCM." Indeed, Tesla's original Magnifying Transmitter would have utilized the earth itself as a self-pumped, amplifying PCM—in other words, as a giant triode where the molten core of the earth already furnished the cathode power for free. A relatively small input "grid signal" (from Tesla's resonant transmitter) would thus have set the earth itself into scalar resonance (giant self-pumping), eliciting an enormous time-reversed wave energy resonant response from the core of the earth. Anyone anywhere on earth with an antenna tuned to the stimulated frequency would have received cheap or "free" energy from the earth itself. The Soviets presently use a version of this method to power their enormous scalar EM wave Tesla weapons. All unorthodox resonant free energy devices (built in secret by unorthodox inventors) presently use variations of this same principle.

146. Photon: the basic action quantum. It may be considered as an oscillation in and of time. It may also be considered as a virtual pattern of positron/electron pairs. A piece of electromagnetic radiation when it interacts as a particle. One half the photon exists in and carries positive time (negative charge), and the other half exists in and carries negative time (positive charge); thus one half is "normal" and the other half is "time-reversed" (phase conjugated). The magnetic field of a permanent magnet, for example, thus consists of two types of coincident magnetic field lines: one line of each coincident pair is in positive time and by convention runs from the north pole to the south pole, while the second line of the pair it in negative time and runs from the sooth pole to the north pole. The two lines maybe considered as two streams of particles, one negative and the other positive (Howard Johnson's two-particle theory of magnetism). The photon may be considered as two contrarotating neutrinos, after the work of Ruderfcr. In the new approach, each of these rotating neutrinos is considered to be composed of vast numbers of circulating bare neutrinos. The photon may be considered as one cycle of an electromagnetic wave. The photon is the basic carrier of time and consists of a piece of energy welded to a piece of time, with no seam in the middle. The passage of "time" thus moves at the speed of light, its carrier. All ordinary photons possess the same action magnitude, h, although they do not carry the same energy. If the photon is made subquantal (i.e., less than h in magnitude), it is a virtual photon of the type whose emission and absorption cause charge on an electron. Virtual photons are not individually detectable, even in theory. However, a virtual photon may have positive mass under some circumstances.

147. Photon interaction: the absorption and emission of photons by particles or objects. Usually the photon interacts with an orbital electron, being absorbed by the electron which is raised into an excited state. Then the election decays from the excited state, emitting another photon. The macroscopic world is created by this interaction, which is the basic quantum change interaction. When we introduce additional photon interactions beyond the ambient background, the nucleus stays basically stable, and the normal first-order world we perceive seems quite stable. This is the first level of physical reality, and it is the reality sensed by our coarse physical senses. However, scalar waves are emitted and absorbed by the nuclei of atoms, passing right through the electron shells without interaction. When we introduce additional scalar interactions beyond the ambient background, the nuclei change appreciably, and this level of physical reality may be far from stable. This is the higher reality, and it is sensed by the scalar electromagnetic functioning of our nervous system. Unfortunately, this system outputs only to the deep unconscious, since it is highly multiocular. Thus our conscious mind, being monocular, does not perceive the most fundamental reality in which we exist. Note that "time" is the special dimension in which multiple objects can exist simultaneously in the same interval, while space is composed of dimensions (length) in which multiple objects cannot exist simultaneously in the same interval. Time is multiocular, and space is monocular. Our conscious mind is fitted to the monocular photon interaction; being monocular, our conscious mind cannot be aware of time directly. For that reason we do not "see" time consciously. We do "see" it, however, unconsciously. The true meaning of being "lost" is to be separated from the consciousness of the All, which is separation of our conscious, gross sensing of first order reality from our finer, more subtle, and infinitely richer—and unconscious—scalar sensing of ultimate reality.

148. Photon quenching: the effect of photon emission carrying away time, constituting a time-differentiation of spacetime and leaving behind a spatial reality. This action is responsible for the destruction of the time dimen-

sion in the detection/measurement processes of our physical instruments and our body sensory systems. Thus all detections and measurements are spatial, and we detect and perceive only a 3-dimensional spatial universe, not a 4-dimensional or higher spacetime. Photon quenching is thus a filter between us (our senses and instruments) and fundamental reality. Physical reality as detected by our senses and instruments is real, but only partial. Specifically it is a time-differentiation of fundamental reality. We thus lose the ability to detect those things which occupy time but not normal 3-dimensional space—such as mind, thought, etc. Almost all our thoughts, concepts, words, and ideas are fitted to this partial reality—and this is the universal human problem and delusion. We see a spatial universe of separated spatial objects, while in actuality we exist in an undifferentiated single wholeness. It is not a matter of loving one's brother or sister, it is a matter of being him or her. Fortunately, with scalar electromagnetics much finer instruments can be built The quantal limitation of ordinary physics is not a limitation in scalar electromagnetics. Ultimately we will be able to use sophisticated scalar sensors and biofeedback training to awaken and develop consciousness of our scalar sensing of higher reality, and restore man to his proper state.

149. Piezoelectric effect: In a material, the appearance of a voltage when mechanical stress is applied, or of a mechanical stress when a voltage is applied.

150. Poltergeist: allegedly, a spirit or ghost, often mischievous, usually associated with anomalous psychokinetic activity in houses such as slamming doors, levitating and flying objects, displacement of persons or objects, etc. Often the poltergeist phenomena are associated with an emotionally upset or distraught adolescent. The experience of cooling of the surroundings when these phenomena are evidenced is also common.

151. Potential: locked-in work or energy at a point It is important to realize that, like a runner running in place, the potential represents work continually being done in time, but at a point, not released through a distance. Since the work is never spatially released, to the external observer it remains in the present as energy, and does not pass into the past as work accomplished! Prior to observation (passage from the present into the past), the physical universe exists as action or angular momentum—e.g., as "energy x time," or "momentum x length," etc. The two variables in which angular momentum is expressed are referred to as "canonical variables." They are locked together, since their product is a constant (in a nonlinear frame). Thus if we ask "what exists in time?" we have asked "what is the time derivative of action, which is the same as "what is existing in time but not in space?" The answer then is energy, which—before observation (separation) exists undifferentiated as (energy x time). Ironically, in electromagnetics the electric (electrostatic) potential is completely misdefined. Most texts start about to define it in terms of "potential difference," and then only tell how to prescribe the intensity or magnitude. For example: "The work which must be done against electric forces to bring a unit charge from a reference point (often at infinity) to the point in question." Note this "definition" does not at all tell what a potential is, but instead tells how to mathematically determine its intensity. Briefly, electric potential is a locked-in stress in vacuum spacetime. This stress at a point is due to the intensity of the virtual particle (virtual photon) flux (dynamic, ongoing, trapped virtual work) at that point The ambient local stress of vacuum is not zero, but is a very high value. Normally we refer to "potentials" as measured from the ambient; that is, we actually specify the "difference from the ambient value of the spatiotemporal stress due to virtual photon flux" at the point in question. Any change in the ambient stress of vacuum is a curvature of spacetime. The electrostatic curvature normally stress-relieves almost immediately as electric force field on matter, or electric virtual force field in vacuum. In Kaluza theory, the electromagnetic force fields are just the 5th dimensional aspect of the 5-d gravitational field. The 4-d gravity field is the other aspect of our 4-<i world's intersection with the 5-d G-field. Thus the electrostatic and magnetostatic potentials are simply two coupled aspects of the 5-d G-field. A normal electromagnetic force field (E or B) is the "bleed-off" or escape on charged particles, of the 5-d gravitational field potential's infolded stress contents into the fifth dimension. That is, it is the 5th dimensional outfolding of the inner contents of the gravitational potential. If we wish to achieve bleed-off into die 4-d G-field instead of the normal 5th dimensional E and B fields, then we must "shut off" the EM bleed-off/out This shutoff can easily be done by opposing and reciprocally modulating E-fields and/or B-fields so that they lock-together as one field, and vectorially sum to zero vector resultants. This creates artificial (internally structured) electrostatic and/or magnetostatic scalar potentials. These potentials are actually 5-d G-potential, which is now forced to bleed-off/out into the 4-d gravitational force field at great amplification. This is the outfolding of the inner contents of the 5-d G potential into ordinary 4-space. Such an artificial potential produces a vector zeroed 5th dimensional EM system with a deterministic substructure, which polarizes the vacuum and engineers the virtual state. Maxwell's original 1864 quaternion theory included this theory, though not in these specific terms. Heaviside's mutilation of the theory into vectors threw away the electrogravitational aspects by discarding the scalar component of the quaternion.

152. Prigogine crystal: an amorphous pellet or crystal made by sintering finely divided material at high temperature and pressure, in such fashion that the pellet becomes a highly stressed system far from thermodynamic equilibrium. Specifically, more than one type of material must be used, one ingredient of which must be piezoelectric. One ingredient should also be radioactive, and preferably one of the uranium compounds exhibiting highly anomalous magnetic spin coupling. For best results, a third ingredient should be luminescent when electrically stimulated. The stress on each grain of the piezoelectric material must be just so that the grain is on the very verge of being slightly stress cracked, but not split Each grain then becomes a scalar interferometer. Such a crystal produces a scalar potential field and can react to minute changes in potential—i.e., it can react to scalar waves. Via scalar interferometry it can change scalar waves into negative (time-reversed) electromagnetic radiation and energy at a slight distance. Under oscillating potential stress, the radioactive ingredient provides a one-way gate valve from the Dirac Sea electrons of vacuum, and the scalar interferometers provide necessary impetus on these negative energy electrons to lift

them out of the Dirac sea, producing negative electricity and currents. These currents can then be collected in multiple stages to provide electrical power (negative power operates devices much better than positive power). In the proper arrangement, such a Prigogine crystal can be made into a system capable of tapping the energy of vacuum directly. T. H. Moray built exactly such systems in the 1920's and 1930's, finally obtaining 50 kilowatts of negative power from a 55-lb device. J. Bedini has produced modern versions of these stress crystals in the 1980's, and a series of negative power devices. Several other inventors have produced successful negative power devices also.

153. Prigogine effect: the exhibition of negative entropy by a properly stressed many-particle system far from thermodynamic equilibrium.

154. Prigogine system: a many-particle system which is deliberately forced to exist far from thermodynamic equilibrium, and which exhibits negative entropy. Note that local curvature of vacuum spacetime places the local virtual state flux in nonequilibrium conditions, with the result that an observable energy "sink" or "source" can be produced.

155. Priore, Antoine: French inventor, who invented a large electromagnetic machine which produced nearly incredible cures of terminal cancers in hundreds and hundreds of laboratory animal tests in the 1960's and early 1970's. Priore's results were presented to the French Academy by the Secretary Perpetuel and Head of the Biology Section, M. Robert Courier. The French Government financed Priore's work for several years, then abandoned it when the regime changed. Priore produced complex phase conjugate (time reversed) EM signals in a giant rotating plasma, then sent these time-reversed signals down a rippling magnetic field into and through every cell of the treated body. By magnetic resonance of the rippling field, the phase conjugated signals were coupled into the atomic nuclei of the body, thus reversing the harmful structuring of the cellular biopotentials, which are centered in and on and from the atomic nuclei. This "backtracked" the circulating substructure components within the biopotential, reverting it back to a previous state where the disease was not present Kindling this pattern into observable state thus reversed and eliminated the disease. (The sharp reader will immediately note that it is readily possible to reverse the aging process, given the development of this technology. So-called "eternal physical life"—or certainly indefinite physical life with youth and vigor—is achievable.). With the death of Priore, the work has ceased and the machine has been dismantled, since no one in the French Academy knew of phase conjugation or understood how it worked. Priore's last machine was nearly four stories high and was intended to treat terminal human cases as well as larger animals such as monkeys.

156. Priore machine: a device built by Antoine Priore in France, which cured terminal cancers and leukemias in thousands of laboratory animals in the 1960's and 1979's. Complex nested modulations were mixed in a rotating plasma, which modulates the signals (producing nested stages of modulations upon modulations, which is necessary to reach into a sufficient number of hyperspaces/nested virtual levels of vacuum). The device produced very complex, phase conjugate (time-reversed) hyperspatial signals of some 17 or *more dimensions* These time-reversed signals were imposed upon and intense, rippling magnetic field carrier, and induced into the body of the irradiated animal, eventually causing the remission of the disease after several treatments. The signal was able to "work on" some 17 levels of the biopotential. Hundreds and hundreds of terminal cases were cured in laboratory animals. The nested modulations formed hyperspatial, multidimensional components in their "giant photon" vacuum engines. This constituted scalar electromagnetic and virtual state engineering in 17-d spacetime, and the machine directly affected the life force frequency channel (consciousness loop) and master virtual electromagnetic (scalar wave) control system of the cells. It would appear that Priore had worked out combinations of frequencies, etc, that, when expressed in time-reversed waves, reverse abnormal mammalian cells, but do not affect normal cells. With the change in regimes in France and the death of Priore, the large new machine (which would have been used to treat humans) was dismantled and the discovery passed into disarray.

157. Probability: the probability of a simple event is the ratio of the number of times it occurs to the total number of trials (for a large, essentially infinite number of trials). Note that "trials" constitute things that have occurred (are past). Probability has resisted rigorous logical definition by Aristotelian logic; the reason is that it is an expression of the fourth law, the identity of opposites. Probability is the expression of the future (that which has not occurred) in terms of the past (that which has occurred). Since we have been trained to conceive or think of something as if it had just been perceived to occur, then this is the only way we can conceive the future. But with Aristotelian logic, the future cannot be composed of the past, and probability has no acceptable logical basis. With four-law logic, the future can be modeled in terms of—and even be identical to—the past, and probability has a logical basis. Consider "throwing a die to land with one face up." Thinking of the event (as if it has just occurred, in terms of the most recent past), one can conceive six ways of looking at it In other words, one can conceive of six "most recent pasts." By the fourth law, the total "most recent past" is identical to the "most immediate future," on the boundary. If one therefore collects all six "most recent pasts," they turn into the most immediate future, by the fourth law of logic. One may attempt to argue that only a single one of the events will actually occur. Here one counters with the observation that, when it occurs, it is the past, not the future, and it has not been collected so as to move to the boundary.

158. Problem of change: as stated by Heraclitus: if a thing changes, it must turn into something else. But how can a thing be something else other than itself? The paradox cannot be resolved by 3-law Aristotelian logic, because the concept of change assumes the fourth law (i.e., that a thing can be identical to something other than itself)- The problem is resolved (by the fourth law) merely by accounting the time snapshots in which a thing is perceived, detected, observed, conceived, thought, etc That is, the original thing was perceived in time snap 1. The next thing was perceived in time snap 2. In yet another time snapshot, snap 3, the two previous snapshots are compared (in memory, which is the only place the past exists). If that comparison finds no distinction or differ-

ence between the first two snaps, then they are declared identical (by a decision algorithm). If the comparison in time snap 3 finds a difference between the previous two snaps, then they are declared nonidentical (by a decision algorithm). Most simple macroscopic things are seen as a multitude of composite attributes. Thus one or more of these attributes may be seen to have changed (not be identical between snaps 1 and 2), yet a host of other attributes may be seen not to have changed. In this case, the two overall objects are seen to be "almost identical but not quite," so that one speaks of "the thing having changed." One implies it changes in some attributes, but remains the same in most others. This is the primitive derivation of "how a thing changes, yet remains itself." On the other hand, if one defines a hypothetical thing which has only a single attribute—itself—then that thing cannot change, by Aristotelian logic. Yet even such a thing can change! Consider the single overallness of a caterpillar. Let metamorphosis occur, and it is now a butterfly. Now between snaps 1 and 2 we see a different overallness, yet we declare it the same thing! Here we have a more direct application of the fourth law: one thing (snapshot 1) can be identical to another thing entirely (snapshot 2) if the distinction between things one and two is lost in the decision algorithm applied in snapshot 3. In other words, identity and nonidentity are not absolutes, but are products of the decision criteria invoked in determining them. This resolves the age-old philosophical problem of change by expanding the logic by means of which one examines the problem.

159. Problem of good and evil: the paradox posed by the assumption of a "good only" creator moving forward in time, and the simultaneous existence of evil. I.e., if God is perfect and all powerful, how can imperfection exist? This problem is simply one expression of the "time trap." That is, the unconscious assumption of a creator moving forward in time (and "acting" and "operating," for example) is a limitation—hence an imperfection—unwittingly placed on the concept of a creator. Hence an imperfect creator could well wind up with the existence of evil (imperfection) in the creation. If one makes God unlimited—even by time—then perfection may be restored to the creator concept One then separates a positive time stream and a negative time stream (these are arbitrary, since in ultimate reality all events exist at once, unseparated, and ordering may be accomplished in any fashion one wishes). In the positive time stream, an act then becomes either good or bad, depending on whether it is beneficial or detrimental to its referent. But in the negative time stream the same act is reversed and becomes the exact opposite with respect to the referent. Thus any act is ULTIMATELY both good and evil simultaneously, and to the exact same degree. Hence in the "all-at-once" of the unlimited level, the two aspects zero and cancel, and there is neither good nor evil exclusively. Yet there is all good and all evil nonexclusively. The unlimited God is thus both good and evil simultaneously but nonexclnsively, and neither good nor evil exclusively. This is the resolution of the unsolved philosophical (and theological) problem of good and evil.

160. Psychic surgery: paranormally opening and closing the flesh of the body to remove abnormal growths or tissues. In a less drastic case, operating on die etheric or subtle energy body, rather than the physical body. In legitimate psychic surgery, scalar interferometry from the surgeon can nullify the cohesive charges binding the tissue cells together in a line; the tissues then open without cellular damage. When the surgeon closes the tissues, scalar interferometry again restores the charge and cellular binding, so the wound is "healed" without scarring (or with very little, in the practical case).

161. Psychokinesis: inceptive influence or effect upon a physical object, system, or situation by mental intent Psychokinesis is accomplished by means of scalar anenergy wave patterns projected from the two cerebral halves in the fashion of a scalar interferometer. The waves interfere at a distance, microscopically in the object to be moved or affected, forming microscopic bursts of vector wave energy in the object itself. Jack Hauck has referred to psychokenetic bending of metal as "warm forming."

162. Psychosis: seriously impaired mental functioning so that gross interference occurs*" with an individual's ability to function in a normal mental fashion. Generally characterized by severe mental disturbance, withdrawal from reality, delusions or hallucinations, regression and personality disintegration.

163. Psychotronic generator: a device which produces observable effects by collecting, condensing, amplifying, and/or processing subtle anenergies or scalar waves. Classic examples are the psychotronic generators of the Czech engineer, Robert Pavlita. Psychotronic devices are virtual state engineering devices that process and utilize scalar EM waves of massless charge flux. Most of Pavlita's devices are "charged" by the natural scalar electromagnetic emissions of the human brain and nervous systems.

164. Psychotronics: *psycho-* (mind energy), *-ronics* (electronics or devices). The union of subtle (mind) energy (that is, anenergy or scalar waves) and matter or electromagnetic field. Czechoslovakian term for parapsychology, with emphasis on the energy aspects. The comparable Soviet term was originally psychoenergetics, which was soon shortened to energetics. However, the Soviets have applied scalar electromagnetics (electrogravitation) principles and massively focussed on weaponry, not just parapsychology. 'Virtual state engineering. Electrogravitational engineering. Scalar wave engineering.

165. Pulse mode: in a transmitting scalar interferometer, projection of a single sequential pair of Fourier scalar wave patterns or "pulses", so that the second pattern meets the first over the distant target area. Flash coupling of the two scalar patterns in the target zone produces a single intense electromagnetic pulse (EMP) which—if atmospheric—interacts with the plasma expansion of the atmosphere to produce a second pulse immediately after the first The dual pulsed flash signature of the scalar interferometer weapon's burst in the target area is very similar to the two-pulsed flash from a nuclear explosion, but without nuclear debris and fallout Two such pulse mode flashes from a Tesla howitzer—possibly the Russian one at Saryshagan Missile Test Range or one from another nation—have been detected off the southwest coast of Africa by U.S. Vela satellites, one in September 1979 and one in December 1980. Other similar tests have been reported. The pulsed flash may produce positive energy (exothermic) or negative energy (endothermic), depending upon the setup.

166. PulsorR: scalar electromagnetic microcrystal device invented by the electrical engineer George Yao. PulsorsR are specifically designed to correct or smooth the patterns of the subtle scalar electromagnetic "bodies" or levels.

167. Quantum: a single "particle" of the quantity action. The quantum is always composed of two fundamental quantities (canonical variables), and it is the "fissioning" of the action quantum into two pieces which results in detection of one of the pieces. An indefinite "smear" of part of the two pieces may be simultaneously detected by a linear detector, but never both exactly (Heisenberg uncertainty principle). More recent work has shown that, in a highly nonlinear situation, both canonical variables can be determined simultaneously to any desired degree of accuracy, in which case the Heisenberg uncertainty principle does not hold. This fundamental change in what has been regarded as one of the "sacred laws" of physics has not yet made it into most physics texts.

168. Quiton: a little piece of vacuum or emptiness. A piece of the medium of a space or spacetime, of any dimensionality. A piece of pure massless charge flux. A piece of pure scalar wave flux. A piece of pure virtual flux. A piece of the vacuum. A particle of electrostatic scalar potential (infinitesimal charge). A "vacuum engine." Quitons are at least 4-dimensional (spatiotemporal), not just spatial and have a dynamic structure, which may be either random or deterministic. Note that the paper handed to Los Angeles Times reporter Bob Toth by Petukov in Moscow, resulting in their seizure and charging with possession of high Soviet state secrets, contained a theory based on "little pieces of the medium" ("little pieces of vacuum.") In other words, it was a quiton theory, regardless of the specific terminology utilized.

169. Radiant energy: term used by T. Henry Moray to describe the subtle anenergy his amplifier tapped from the unlimited vacuum energy of the cosmos, furnishing usable electrical power of an unusual (negative power) nature. By 1939 Moray was obtaining 50 kilowatts of power from the output of a 55-pound amplifier of some 29 stages, and an additional 50 kilowatts could be tapped off from any other stage. Moray's amplifier was essentially holographic, and could produce exponential amplification to any degree, merely by adding stages. The term was first used by Nikola Tesla, who patented "radiant energy" signaling systems shortly after 1900.

170. Radionics: the use of electrical apparatus (such as ganged precision resistors and potentiometers) to accurately attune the innate psychic and psychokinetic abilities of a human operator. Specifically, the operator may be attuned to some person or object at a distance, through the use of a "witness" (something containing the subtle anenergy pattern of the person or object). In actuality, the pattern contained by the witness consists of the previously impressed virtual (subtle) (scalar) energy patterns riding in and upon the object's internal electromagnetic interactions. The infolded vacuum retains an exact pattern and path of all photon interactions, be they observable or virtual. This guarantees a vacuum path exists between the witness and the original object, no matter where it is located. These impressed scalar EM patterns constitute a sort of complex "tuning fork" attuned to the impressing object or person through hyperspace (via the infolded past "backtrack" virtual memory of vacuum). Production of phase conjugation waves (time-reversed waves) in the witness thus will result in travel of these waves back through the infolded "backtrack paths" to the distant object itself. Resonating the "witness" pattern with amplified anenergy from the operator produces sympathetic anenergy resonance into the witnessed object at a distance, through the hyperspace backtrack path. Since the operator's will and intent modulate and pattern his input into the amplifier, the anenergy resonance of the distant person or object is correspondingly modified. This causes the kindling of an actual microscopic energy pattern in the distant object. The use of amplification constitutes the modern phase of radionics, essentially introduced by T.G. Hieronymus. In the Soviet Union, the incredibly powerful Moray hyperspatial amplifier is believed to be in use in a variety of energetics or psychotronics weapons. Such a holographic amplifier yields exponential power amplification to almost any degree desired. In the destruction of the U.S.S.Thresher in April 1963, a photograph of the submarine was probably utilized as a witness, and sufficient negative energy was kindled into the distant underwater submarine to seriously interfere with its controls. The sub then sank to crush depth and was imploded. Negative energy splatter in the surrounding area so interfered with the electromagnetic systems of the companion ship, U.S.S. Skylark, that over an hour and a half was required to transmit the emergency message that the sub was probably lost. In the U.S, holographic amplifiers have not formerly been developed, and radionics power is limited essentially to the linear amplification abilities of ordinary amplifiers. Thus their gains may reach 10^4, when indeed 10^{20} or so is needed for direct mechanical results immediately. For this reason the West has not developed dependable detectors of subtle energies, has not recognized the Soviet superweapon developments, and has not developed counters to them. However, Bedini, Dea, Beck, Golden, Dayney, Bielek, Bise, and other inventors have built scalar detectors of one form or another. Golden has also produced a highly specialized "booster amplifier"—the Golden booster—for Kelly radionics devices that is a step in the right direction. Both the Kelly machine and the Golden Booster have been verified as scalar wave radiators by actual measurement. With the development of detectors, the technology should begin to develop much faster in the West. The science of such devices and effects.

171. Reality: that which is actual or objective, as opposed to merely possible or ideal. One's idea of what constitutes actual and objective, however, strongly biases what is regarded as real and what isn't. In physics, for example, virtual actions are essential infinitesimals—little pieces of "nothingness" which yet produce effects. Physics thus has extended the meaning of "objective" beyond the idea of "observable." In addition, time—which is never observable or detectable, even in theory—it nonetheless assumed to be real and objective. In a sense, by "reality" one attempts to imply "ultimate." Indeed, the concept is confused, vague, and incapable of definition except in accord with what one pre-assumes it to be! The major problem is that most persons assume (1) reality is limited, and (2) reality is singular. In the new approach, reality is both unlimited and multiple. Everything is real; there are just differing degrees of reality or solidity as compared to the ordinary physical detection

(threshold selection) process. Reality becomes a matter of intersections of physical universes and objects with other physical universes and objects, with the density of the intersection specifying the density or degree of physicality. (Note the similarity to the Aharonov-Bohm effect).

172. Reincarnation: refers to some element of the mind and/or personality surviving the physical death of a body/tuner, and being reborn in the body of another infant In the new approach, a type of reincarnation is scientifically derived as a consequence of the theory. However, since the past can be changed, by deep developmental work one can actually change one's so-called past incarnations. Also, more than one living person's scalar pattern can be attuned to a similar "past" scalar personal pattern—and so more than one person can be the "reincarnation" of a past person.

173. Remote viewing: the ability of human subjects to receive visual impressions and information from distant actions and scenes. The information is usually "noisy". May involve combinations of clairvoyance, clairaudience, precognition, postcognition, and telepathy. In the new theory, one recognizes that all detection is internal to the detector. Hence the entire detected physical universe may rigorously be said to exist inside each physical particle of the physical body of the observer. Thus hypothetically one has subtle access to any portion of the universe directly within oneself. The same result occurs when one assumes the use of a signal—longitudinal scalar waves of electrostatic potential—with infinite velocity. The two cerebral hemispheres act as a scalar interferometer, producing microscopic E-field by coupling incoming or rising microscopic scalar phi-field waves. This allows modification of the patterning of the avalanche discharges underway in the brain, and thus perception of the distant event Since scalar waves are hyperspatial and can be superluminal, they can move through time. This permits perception of the future and the past Unfortunately the outputs of this detection system in humans is buried deep within the unconscious mind, so it is difficult to obtain "clear signals." With the future development of sensitive scalar wave detectors, biofeedback training can probably be used to more fully develop this scalar sensing ability. Also, on several occasions Nikola Tesla announced the invention of a "big eye" that could see at a distance; such an instrument is perfectly possible by scanned scalar interferometry reception. This would include the ability to see into or through the ocean or earth—and time as well, under the proper circumstances. It should be possible to take distant pictures, or even pictures through time. One researcher, George Delawarr, reported the accomplishment of both these effects with his special camera.

174. Resonance: in physics, an oscillation phenomenon exhibited by a physical system driven by a periodic force; when the frequency of the driving force approaches a natural "free response frequency" of the system, the oscillation of the system becomes large. The "resonance (or resonant) frequency" of a system is a frequency at which some response of the system becomes maximum. Three types may be defined: (1) Phase *or* velocity resonance, where the response of the system is 90 degrees out of phase with the driving force, (2) amplitude resonance, where the amplitude of response of the system *is* maximum, and (3) natural resonance, which is the frequency of oscillation of the system to a sharp input such as a hammer blow. Electrical resonance exhibited by an alternating current reactive circuit results in relatively large currents near certain frequencies, together with the nearly unimpeded oscillation of energy back and forth between potential and kinetic form. There are two kinds, series and parallel resonance. In series resonance, the inductance and capacitance are in series, and in parallel resonance they are connected in parallel. In the series resonant circuit, the currents can become large if the resistance is small. Further, the voltages across the coil and capacitor are essentially 180 degrees out of phase, and so they essentially "cancel," leaving very little voltage across the overall circuit, even when the individual voltages across the coil and across the capacitor are very large. (Note that the E-fields across the inductance and the coil are also 180 degrees out of phase, and so the series resonant circuit to a distant observer produces an artificial potential wave—indeed, an electrogravitational wave. This is one reason why Tesla so favored the series circuit He also favored it with one end loose—the so-called "single-wire" circuit, without a return.) If the driving voltage to such a single-wire series resonant circuit is applied to the coil with the open-ended capacitor beyond, and the voltage is applied for only the first 90 degrees as a sine wave then instantly removed, the coil will be charged without current flow, accumulating a 5-d gravitational potential. When the coil discharges, it will discharge in two directions, producing real current, at a certain frequency (which may be drastically different from the "normal electrical current" resonant frequency. However, actual current will be induced out of both ends of the coil at this frequency. The capacitor will charge a little bit from this effect. The overshoot of the coil discharge back toward the disconnected driver is also usable energy if connected to a proper load. If the load is removed and the driving voltage is reapplied just as the overshoot reduces back to zero, the cycle is repeated, charging the distant capacitor more and more, and producing pulses of usable power through the overshoot discharge on the driver side. By adapting this mechanism, a free energy motor can be readily produced, as demonstrated by Bedini, Watson, and others with a battery-driven, series-wound DC motor unit Note that use of the localized gravitational potential produces local general relativity, a.locally bent spacetime, and the conservation of energy, charge, and momentum laws need not rigorously apply. An adaptation of this mechanism was also utilized by Tesla in his magnifying transmitter. In that transmitter with its huge elevated capacitance, the artificial potential wave produced would have been introduced into the earth, producing scalar resonance of the earth. The molten core of the earth, being under pressure in all directions, is self-pumped (in the language of nonlinear optical phase conjugation). The resonant atomic nuclei of the earth's molten core would then act as a pumped phase conjugate mirror (PCM), producing a highly amplified (near infinity gain!) time-reversed wave in response to the input signal. Thus the earth PCM is a giant amplifier, and the TR wave returned is highly amplified, possessing enormous energy. Thus the amount of energy resonant in the earth becomes enormous. In fact, the transmitter was designed to produce more than one such scalar earth resonance. At any distant point on the earth, a transmitter/receive station could have input a

small "tickler wave" at this frequency into the earth, and its proper antenna tuned to the frequency" of the scalar resonance would have produced enormous electrical power. A very similar system employing two frequencies 12 kilohertz apart and tapping the beat frequency, is used by the Soviet Union today to power its large strategic Tesla weapons. Golden has detected and shown these Soviet "two-frequency earth resonances" on the oscilloscope, utilizing the output of his specialized detector system.

175. Sasquatch: Indian name for a large, well-defined tulpoidal apeman form. Bigfoot (slang or common name). Generally refers to the Pacific Northwest area, where die tulpoidal form has been well-tuned for centuries by the Indians. In the Far East, the Yeti.

176. Scalar: in ordinary vector analysis, a quantity completely characterized by magnitude only. (Actually, it contains magnitude and time.) In the new approach, one must account for observable and virtual states. In addition, multiple vectors acting on one point and summing or multiplying to zero are physically still present, even though their vector resultant is a zero vector (more precisely, a zero-vector system). Thus physically a zero vector can be a system having a very real, distinct substructure of nonzero vector components. These infolded vector components may be highly dynamic. The energy of each infolded dynamic vector component is thus "trapped" inside the local vector zero system. Rigorously, trapped energy constitutes a scalar potential in spacetime, to the external observer. An observable scalar (potential) thus may have a nested, multiple-level virtual substructure as well as any conglomerate "observable vector" substructure. Enormous energy may be infolded and trapped, in which case local spacetime is appreciably curved. Note that the infolded energy of the substructure components contributes to the stress of the object or medium, and organizes it, even though to the external observer its envelope constitutes a zero vector. Each level of this substructure contains an infinite number of tiny virtual vectors. There may be finite alignment of these virtual vectors along the structure of the observable vectors infolded. This constitutes vacuum polarization. The zero-vector system is thus a vacuum engine and a virtual state engine as well. Two scalars (or vectors) that are observably equal need not be equal at all in their substructures. Further, combining the two scalars by superposition may not yield the normal observable value, if both substructures are different, highly patterned and interact to spill over into the observable level. Vector mathematics itself must be changed and extended in the new approach. Note that the spillover from interaction of the two substructures may form an observable scalar value or an observable vector value. Such vacuum engines can be constructed o do specific operations on atomic nuclei etc. Nested levels of such engines can be formed, to form highly complex "super" hyperspatial vacuum engines called giant photons. Continual radiation of matter with a signal composed of vacuum engine photons of a specific deterministic substructure will "charge up" the atomic nuclei of the radiated material with that pattern, so that it emerges into the gross, observable physical state, drastically altering the radiated matter itself mechanically, chemically and physically. This process is called kindling.

177. Scalar energy tap: refers to a Soviet method of obtaining tremendous electromagnetic energy from the molten core of the earth, with which to power gigantic strategic scalar Tesla howitzers. As measured by Golden, two signals are continually transmitted into the earth some 12 kiloHertz apart, and the earth itself is placed in scalar resonance to the two frequencies. The core of the earth, being a pumped phase conjugate mirror, responds by generating highly amplified phase conjugate replicas, which return and concentrate all their energy at the transmitter/receivers. The receivers receive the enormous beat frequency (12 kHz) energy, using it for power. One then has a kind of scalar interferometer channel in the earth's core in the endothermic mode. Depending upon the biasing, either ordinary EM energy or negative EM energy is captured in the 12 kiloHertz band by the interferometer receivers. Varying the negative biasing also provides a throttle to control the amount of energy extracted. Just before the May 1, 198S celebration, the Soviets activated some 27 such giant energy taps in the earth, and also activated a large number of command and control scalar transmission frequencies. If each tap can power 6 to 8 giant Tesla howitzers, then for their important 40th anniversary of WWII, the Soviet Union activated well over 100 large howitzers. In other words, a massive exercise of the Soviet Union's entire strategic scalar howitzer weapon complex was held on the 40th anniversary of 1945 for Gorbachev, and to signify meeting the schedule (laid down by Brezhnev in 1972) to "be ready" to use them . At the conclusion of the exercise (which lasted several days), the Soviets left two scalar energy taps in place, instead of the single one present before the exercise. In other words, additional strategic weapons were brought up on "ready alert"

178. Scalar field: in vector analysis, each point in space is assigned a magnitude; the set of spatial points and their assigned magnitudes is called a scalar field. In the new approach, an observable scalar value is assigned to every point in n-dimensional space, where n is 4 or greater, and the set of n-dimensional points and their assigned observable magnitudes is called a scalar field. Also, in the new approach each scalar magnitude is considered to contain an n-dimensional virtual-state substructure, where each succeedingly higher dimension is a succeedingly lower level of virtual state. Vacuum itself is such a scalar field. Such a scalar field is also the rigorous identity of a massless charge field, of—for example—the electrostatic scalar potential, 0. Also, the scalar field is considered to be composed of two time fields: one in positive time and one in negative time that is the phase conjugate replica of the first. Thus the timeless, lengthless vacuum exists both in positive and negative time, and its potentials are scalar potentials. When the vacuum is uncurved, equal amounts and components of positive and negative time exist. When it is curved at a point, the positive and negative time components are unbalanced at that point

179. Scalar interferometry: the interference of two scalar Tesla waves (a Tesla wave consists of a normal wave coupled to its phase conjugate replica). In the interference, coupling can occur and produce (or extract) electromagnetic waves—energy—at a distance. The phase conjugation aspect is the secret of Tesla's revolutionary discovery of wireless transmission without loss. It is also the secret of producing death rays; the invulnerable Tesla shield; antigravity; superluminal communication; con-

trolled materialization, dematerialization, and transmutation; psychokinesis; and free energy. The ubiquitous photon interaction presently is the basis for first-order physical reality, and the photon's speed results in a speed-of-light-limited reality being detected. Scalar EM waves contain vacuum engine substructures and do not necessarily have this speed limitation. Detection by scalar waves yields a higher order physical reality and a vastly expanded quantum mechanics and relativity theory. Present Einstein relativity theory is only a highly special case, as are present electromagnetics and quantum mechanics. Soviet use of scalar interferometers in a large, strategic mode is responsible for much of the advanced Soviet ABM defense and strategic superweaponry.

180. Scalar resonance: inertial or mass resonance of a body, originally discovered by Tesla, repeated (probably) by Hooper, and rediscovered by Golden, Bedim, and others. In the simplest case, scalar resonance can be imagined as two ordinary single—frequency EM standing waves (a wave and its phase conjugate replicaor PCR) in a resonant cavity, with the two waves coupled exactly 180 degrees out of phase so that—externally—their E fields sum to zero and their B fields sum to zero. This is a standing scalar wave, and the cavity is said to be in scalar resonance. Note that the cavity walls must act as phase conjugate mirrors (PCMs). Mass itself is simply such a standing scalar resonance, with the standing wave trapped by particle spin. The atomic nucleus, continually bombarded by virtual photon flux from the vacuum, is a pumped PCM. Since the nucleus is positively charged, it produces PCRs having negative energy and negative time. It thus produces negentropy, which prevents the entropic decay of the atom. Essentially all frequencies can be and are present at once, but certain nuclear resonance frequencies are thought to predominate. By increasing the amplitude of the standing scalar wave that is the nuclear pseupotential, inertia and mass of the nucleus are increased. By decreasing the amplitude, the mass and inertia are decreased. Zeroing the amplitude dematerializes the nucleus. Scalar resonance is not presently contained in the orthodox physics literature.

181. Scalar wave: a longitudinal "pressure" wave in the actual stress of spacetime itself. A wave of potential, where no EM bleedout of the infolded contents occurs. A normal wave and its phase conjugate replica, co-modulating each other and "locked or zipped together" as a zero-vector system wave. A Tesla wave. A gravitational wave. A time wave. Electromagnetically, a scalar potential wave which, in the absence of spinning charged mass particles, does not form a vector electromagnetic wave, in contradistinction to present electromagnetic theory. A "shadow vector" wave, where the ordinary "observable force vector" of the field is broken into virtual vector components which are not integrated. A wave in the nested levels of virtual state, that does not breach the quantum threshold, and hence is not observable to normal detectors. A wave in the magnitude of the virtual particle flux density of vacuum. A longitudinal wave in pure massless charge flux (vacuum) (spacetime). A wave in the magnitude of the infolded "energy density of the vacuum. The scalar wave is free to move in four or more dimensions. It transports deterministic vacuum energy engines. In Minkowski 4-space, it can: (1) move only in time, and not spatially, in which case it "sits in one place" and fluctuates the flow of time, the inertia of an object, the strength of the gravitational field, the mind, the fundamental constants of nature, etc.; (2) move only spatially, with the rate of flow of time oscillating about a linear mean; (3) move in a mixture of modes (1) and (2); (4) oscillate back and forth between modes (1) and (2) in a regular fashion, spatially stationary; and (5) oscillate back and forth between modes (1) and (2), translating spatially in travelling wave fashion. (5) move and oscillate between many vacuum levels (hyperspaces), in addition to characteristics (1) through (4). An ordinary Hertzian wave exists in vacuum as two coupled Tesla longitudinal waves. Rigorously, the E and B fields do not exist in vacuum, but on and of the detecting spinning charged particle. The spin of the detecting particle causes precession, yielding the familiar "transverse Hertzian wave," complete with E and B fields. The broken but ordered virtual state bits of what will be the detected E and B, however—shadow vectors E and B—exist in vacuum, on the virtual components of the vacuum charge flux. Tesla was correct when he stated that transverse Hertz waves (as such) could not move through the vacuum or exist in it

182. Shadow vector: an otherwise observable vector, broken into consecutive bits such that each bit is virtual. The resulting "disintegrated vector" becomes unobservable as a vector, but remains as an ordered series of virtual vectors. Thus it is a special sort of scalar wave. Observably, it is a scalar wave since no observable vector exists, but virtually it is a vector wave. It may be regarded as a localized, changing scalar field with a particular patterned virtual substructure which yields the shadow vector. On an appropriate integrating detector, the virtual components of the shadow vector will be reintegrated into an observable force vector, such as E or B. Dr. Robert Beck, for example, has reported the development of a successful integrating detector for such shadow vector scalar waves. His detector is capable of detecting signals that cannot be seen by the finest Superconducting Quantum Interference Device (SQUID), and it has been demonstrated for comparison against the SQUID. Dea, Bedini, Dayney, Golden, Beck, Bielek and Bise have independently built scalar wave detectors of various kinds. Farnsworth has particularly good and comprehensive shadow vector/scalar wave detecting systems.

183. Space: literally, the absence of observable mass, hence emptiness or void observably. Space per se has no definite length interval and no definite time interval. Rigorously, space is the absence of distinction and separation. Space has no dimensionality—i.e., it is not 3-dimensional, 4-dimensional, etc., for it has no "specific" separations. But in common usage, it is often thought of in a general sense as having some particular dimensionality but no definite intervals. The point is subtle but important: the absence of a 3-dimensional mass need not be 3-dimensional (e.g., considering a 10-dimensional frame). But one usually thinks of the "hole" where the mass was as having the same dimensionality as did the absented mass. This is only a 3-dimensional intersection of the actual hole, however, though this point is usually ignored. Ignoring the full dimensionality of a hole is responsible for the confusion regarding the two-slit experiment in quantum physics, for example. That is, the slits are (at least) 4-dimensional, since they exist in time also. In the slits, spatial mass is absent, so the slits are

three dimensional "holes." However, their fourth dimensional aspect, time, is present, not absent Thus four dimensionally the three-dimensional slit "holes" are not "holes", but are "things." They are not 4-d absences, but presences—since one dimension (time) is still present They can thus interact in the fourth dimension, time. The experiment has no mystery when the time aspects are considered, as pointed out by Charles Muses in 1957. In Kaluza-Klein 5-d mathematics, these 3-d holes also exist as things in the fourth spatial dimension. Also, in spacetime—rigorously—all 3-dimensional material objects, holes, gaps, etc. are simple facets or intersections of a single object For if time is considered as a continuum, then everything exists at once; hence spatial things are simply the features of a single 4-dimensional object The problem is that "space" is also commonly taken to be a "spatial frame," where time has been stripped off and "stopped," and a measurement to each and every point in the universe frame has been simultaneously established. This corrupt usage of "space" implies "spatial frame," and is entirely different from space as such.

184. Spacetime: three or more dimensions of space and a dimension of time, multiplied together. In the 4-dimensional case, it is often referred to as a "4—space." Spacetime can actually contain any number of dimensions; in our theory we consider an infinite number of spatial dimensions and at least one time dimension. One could just as easily take an infinite number of time dimensions alone. Scalar electromagnetics (unified EM and G fields) is most easily expressed in Kaluza-Klein geometry, in at least five dimensions—four of space and one of time.

185. Spherical model of the cosmos: a model of the universe in which the universe is a four-dimensional spherical surface in five dimensions. This results in a "closed" universe, and also one which is entirely within each point of itself. To produce such a model instead of an expanding universe, Einstein originally introduced entirely ad hoc factors into general relativity to cancel and eliminate the expansion terms.

186. Spin: the intrinsic angular momentum of a particle, as if it were a top spinning about an axis. Spin is quantized. Spinning charged particles—such as an electron—thus demonstrate a magnetic moment, due to the circulation of charge in the spinning. In the nucleus of an atom, the spin of the nucleus is the resultant of the spins of the nucleons (particles comprising the nucleus). Actually spin of particles is more like an "implosion" to "explosion" circulation; in other words, it circulates in time as well. Spin of a particle is the basic feature that integrates the anenergy (disintegrated energy) of vacuum flux into observable charge. All observable fields, matter, effects, etc. depend upon this basic mechanism to zip together virtual entities and form observable phenomena.

187. Spooklight: another slang name for a nocturnal light Legend and folklore usually associate it with a violent death or macabre occurrence. Earth stress lights. Over 1,200 known sites produce such earth stress lights in the U.S. alone.

188. Strobe effect: striated patterns seen in UFO and other paranormal phenomena due to the higher dimensional phenomena skipping in and out of normal 3-space. Alternatively, two or more higher dimensional phenomena may dynamically interfere so as to form repetitive intersections with our normal 3-space, producing striations. Hyperspatial (scalar) EM interference often produces striation effects.

189. Substructure: in the new approach, a scalar has an infinite-dimensioned (infinite number of sublevels) virtual state substructure, filled with waves, particles, etc. Vacuum has precisely the same sort of substructure. The substructure is rigorously CHARGE FLUX, where observable mass is not present. Any vector, since it contains a set of scalars, also contains a set of virtual state charge flux substructures. One can engineer, pattern, arrange, and utilize these substructures to give various "paranormal" effects. These effects include materialization and dematerialization, psychokinesis, clairvoyance, superluminal communication, antigravity, teleportation, apportation, remote viewing, production of energy at a distance, extraction of energy at a distance, electron dissolution, etc

190. Superposition: the simple linear addition and subtraction of two or more values. In the new approach, superposition need not linearly hold valid if sufficient substructure interaction is obtained and the substructures are nonlinear. In that case, superposition turns into nonlinear interference.

191. Teleportation: the transmission of an object from "here" to "there" with no travel in between as an object in ordinary space. Hyperspatial transmission of an object from one point in the ordinary space to another.

192. Telluric currents: earth currents; electrical currents in the rocks of the earth, believed to be due to aurora effects and the earth's magnetic field. In the new approach, these currents are also pumped by longitudinal scalar wave bombardment from the sun, the cosmos, and the fiery core of the earth itself. Quartz is a common crystalline component in rocks, and thus the rocks are piezoelectric This means that stresses in the rocks, such as from shifting tectonic plates, causes electrical activity, and electrical activity causes mechanical stresses. Further, the quartz is essentially randomly oriented, resulting in most of the tiny piezoelectric vectors summing to a vector zero, which in turn constitutes a scalar potential and pumping the atomic nuclei as pumped phase conjugate mirrors, producing PCR waves. These do the same thing in return, producing negative energy potentials and potential waves, etc. As the piezo-vector components vary, the values of the potentials fluctuate. The zero-sum portion of such a stressed randomized crystal constitutes a Prigogine detector for kindling and collection of anenergies via nonlinear thermodynamics. The molten core of the earth is also a dynamic Prigogine system, since it is a pumped PCM. Thus the earth is a collector, processor, sometimes amplifier, and retransmitter of mind energies and anenergies, and truly the earth may be considered to be "alive" in a strange way (the Gaia hypothesis). This process, along with scalar EM in living systems, also produces Sheldrake's morphogenetic field and its effects. Specifically, the earth receives and processes anenergies from the species unconscious of all the species of ordinary life upon it The earth itself does respond to geometric kindling alignments of other planeti. and particularly to the moon. In addition, it does respond to the state of man's collective species unconscious mind. Fault zones result in structures similar to diodes, triodes, and scalar interferometers. Amplification and rectification of kindled anenergies occur readily, including at a distance, at fault zones, particularly when

seismic stresses in the rocks are increased, increasing the piezoelectric activity, telluric currents, scalar interferometry, etc Thus fault zones constitute natural kindling window areas for paranormal anenergy forms, for tulpoids etc—precisely as found by Persinger. Fault zones are also scalar interferometers, which enhances the formation of ordinary EM forms at a distance.

193. Tesla fireball: interference of two scalar Fourier expansion patterns to form a glowing, fiery globe or spherical shell of radiant electromagnetic energy and electron plasma.

194. Tesla howitzer: a large Tesla scalar interferometer such as the fourth generation Soviet hyperspatial howitzer at Saryshagan. Repeated Soviet testing of Tesla howitzers is documented in the open literature (see Bearden, *Fer-de-Lance*, Tesla Book Co., 1986). The howitzer is capable of utilization in multiple modes, both as a strategic offensive weapon and as a multiple-mode strategic ABM defense weapon. Scalar EM interferometer. Hyperspatial howitzer.

195. Tesla shield: a gigantic, hemispherical, glowing, thin shell of intense electromagnetic energy and electron plasma, placed over a defended area or installation. The EM shell is formed by interference (and coupling) of two scalar shells of anenergy, formed by truncated Fourier expansion methods from multiple frequency scalar transmitters. To form the shell at a distance, phase conjugate replica waves must be utilized, so that the energy and energy pattern does not diverge as a function of distance. Note that such real-time holography, independent of distance, already appears in the nonlinear optics phase conjugation literature. In the Tesla Shield, the energy density in the interference shell causes local curvature of spacetime, and lifts electrons from the Dirac sea, producing the plasma in the shell. With sufficient energy density in the interference shell, a material object seeking to penetrate this dome of energy and plasma is instantly electromagnetically "dudded," and physically damaged and/or vaporized. In addition, the potential pulse delivered inside the nuclei of nuclear materials that meet the shell instantly fission all fissionable materials. Thus nuclear weapons are instantly detonated when entering the shell. Electromagnetic energy (such as gamma radiation from the EMP of a high altitude penetration burst) impinging on the shell plasma is absorbed and re-radiated inside the shell at lower frequency and temperature. Several shells may be internested so that multiple, serial absorption and scattering reduces the original gamma radiation to harmless radio frequency noise. Numerous incidents of tests of the Tesla Shield weapon are documented in the open literature.

196. Tesla wave: a longitudinal scalar potential wave in massless charge, in the vacuum charge flux itself, and in pure spacetime. An electrogravitational wave. A gravitational wave. A scalar EM wave. A wave of pure potential. A wave in the magnitude of the flux energy density of vacuum. A wave in the magnitude of the curvature of vacuum.

197. Tesla weapon: any weapon utilizing longitudinal scalar EM waves or phase conjugate replica waves to accomplish its results. Also applies to a weapon using scalar interferometry or PCR interferometry and holography from multiple projectors or transmitters.

198. Thought: separations and forms in pure mind or being. To think is to form (separate, perceive) thought forms and process them. In a developmental sense, thinking is the activity of mind that screens the true continuous mind nature by fragmenting it The true mind is like the ocean, and thoughts are like waves or disturbances in the ocean. In the new scalar electromagnetics, the mind itself produces scalar waves, on the third and lower virtual levels of the scalar substructure, and these are what we call "thoughts." A thought is a real, virtual-state object capable of being directly detected, interacted with, and engineered by scalar EM means.

199. Thought photography: psychokinetic impression of images or light effects upon photographic film or other sensitive media, due to the presence or intent of a human initiator. PCR distant interferometry and holography is the basic mechanism involved.

200. Three-space (3-space): a space dimensionally composed of length cubed. It is the normal space taken to be occupied by gross matter. Per se, vacuum does not occupy this same 3-space, even though erroneously assumed to do so in present physics.

201. Time: in relativity, an extra dimension (variable) which allows the ordering of spatial snapshots or events. In quantum mechanics, time is only a parameter; it is not an observable and is not detectable, even in theory. Time is always inferred, even though precisely. Rigorously, time exists only through the stream and persistence of human consciousness. We only experience that persistence as "something changing", by continual comparison of our memory of perceptions of spatial position and pattern. In the abstract sense, time is being, which has no differentiation whatsoever—it simply is (a tautology). Perceptual separations in being constitute thoughts or mind changes, much like waves in water. Those waves common to all minds constitute physical (spatial) changes in the so-called "real" world. Because "time" in its undifferentiated sense is simply a synonym for being, then multiple things (separations) may inclusively exist in time simultaneously. (How many final objects exist in a stone before it is carved into any one of them?) The basic separator of being/time is the photon interaction, which is the basic generator of monocular quantum change and thus the progression of spatial particles "through time" in little jumps. The endpoints of the quantum jumps through time represent time differentiations of spacetime/masstime. To properly understand physical phenomena, both positive and negative time flow must be incorporated in the theory or model used.

202. Time oscillation: ordinary time advances and retards in small discrete jumps, much as a sewing machine stitches forward—except that each time stitch is pulled out before the next one is made. Thus time consists of two time flows interleaved: the positive flow of time (stitching) and the negative flow of time (unstitching). This "time stitching/unstitching" or oscillation can be viewed as a wave. It is "action" that is waving (being changed or created and destroyed in quantum chunks), since time is actually a subcomponent of action. One may therefore view time waves as carrying or creating surges of energy back and forth (in time). The photon may be considered as this oscillation of lime, for it is actually an oscillation of action. The positive half of a photon exhibits positive time (the stitch is made) and a virtual electron, and the negative half exhibits negative time (the stitch is removed) and a virtual positron. Charge is a function intimately related to, and comprised

of, time stitching. Positive time is associated with negative charge, and negative time with positive charge. The photon ca be considered as a coupled virtual electron-positron pair. The invisible stitching/unstitching trace of a photon through spacea'me is "enfolded" (in time) and remains. A phase conjugate replica photon, created at some later time and some distant place, thus has a sort of "invisible wire" connecting its own generation and the distant source that generated the stimulus photon. Note that spacetime occupies time, but space does not. Mass-time occupies time, but mass does not. Mind, thought, and being occupy time, but not space.

203. Time trap: refers to the erroneous assumption that God is a limited being, traveling along through time much as humans perceive themselves to. An unlimited creator must permeate all aspects of creation, including time. In the unlimited view, God permeates time from beginning to end, all at once. To such a creator, nothing is happening, since all happenings are simultaneously present What we call "positive" or forward time and "negative" or backward time co-exist and are inseparably identified, to such a level. Good and bad are only relative to a single time stream and to a single referent At the unlimited level, there is no separate good or separate evil. Yet there is all unseparated good and all unseparated evil. All "events" or acts that one might separate, simultaneously exist in both forward and backward time streams. Hence any event is ultimately both good and evil simultaneously, and to an identical degree. Again, this is the void that is devoid even of void.

204. Transverse wave: a wave which vibrates laterally to its motion in a medium, exactly like the vibration of a stretched string. Vector electromagnetic (Hertz) waves are transverse waves, in the present theory. In the new approach, transverse waves cannot exist as such in vacuum, but only in a longitudinally restrained medium. (The electron gas in a solid conductor, for example, is such a medium, and Maxwell's equations rigorously apply to the transmitting electron gas and to the detecting/receiving electron gas, but not to the vacuum in between). Longitudinal (alternately densifying and rarefying) scalar waves exist in vacuum, in the charge (virtual particle) flux that vacuum identically is. Hertzian waves in vacuum exist as shadow vector waves, that is, as two or more coupled Tesla scalar waves spinning around each other.

205. Tulpa, tulpoid: condensed, materialized or semi-materialized thought form, either living or inert. May be a visible or an invisible electromagnetic form, a partially materialized form, or a completely materialized form. Ultimately all matter and fields are tulpoidal in nature, consisting of condensed thought/mind energy.

206. Two-slit experiment: a form of Young's experiment where a particle is generated and directed toward a plate having two tiny slits (holes) in it, with a collection screen or device on the far side of the plate to collect and add the impacts of the particles that pass the plate. The idea is that a classic corpuscle can only go through one hole at a time, like a baseball through a hole in a fence. For particles, classically the strikes on the collector screen should be grouped in two clusters, each representing a straight-line passage through one of the slits. In the experiment, however, the particle strikes form a wave diffraction pattern when collected on the screen, unless the emitted particle is struck by a photon before it strikes the screen. In the latter case, the two clusters for classic corpuscles are observed. The experiment—fundamental to all quantum mechanics—is simply understood if one considers the time aspects of the problem, as pointed ont by Charles Muses in 19S7. The two slit apparatus with electrons may be also used as an electron interferometer for sensitive detection of scalar EM (electrogravitational) waves.

207. UFO: unidentified flying object Any object or light in the sky that cannot be identified as an ordinary physical phenomenon. After normal objects and phenomena are eliminated, the remaining paranormal residue is of interest Many of these are kindled tulpoidal forms, and may consist of lights, invisible electromagnetic energy, physical objects such as discs or spaceships, robots, humanoids, etc. (A few of these forms may be real anti-gravity spaceships, created here on earth by sensitive groups of several earth governments, but controlled by some mysterious group outside these governments. Such craft, I believe, have been developed and flown all over the solar system since the early 1950's. These I do not consider part of the true UFO phenomena, which in one form or another are centuries old.) Highly materialized ship forms may also contain highly materialized living forms such as space-suited astronauts etc. The "UFO" has been separated from other tulpoids (bigfoot, fairies, spooklights, water monsters, etc.) because its appearance in the sky was immediately associated with aircraft or spaceships, leading to the initial expectation that extraterrestrials in advanced spacecraft were visiting the earth. Most of the UFO phenomena actually consists of lights at night (well over 80%), and only about 6% or so resemble well-materialized ships with astronauts. A substantial portion of the "lights at night" phenomena are also due to Soviet scalar EM interference weapons. The Soviets create a great deal of light phenomena worldwide, to spark UFO reports, which are discounted by conventional science and most of the military and government agencies. This provides the Soviets a giant and effective "deception plan" so that the weapons can be tested and readied worldwide, and sightings and reports will be discredited and not cause undue alarm.

208. Unconscious: unaware, not conscious. Refers to that part of the individual's mind which is not normally in conscious awareness, but which may contain a great deal of material from the conscious mind. In the new approach, the unconscious mind is considered to be "multiply conscious," while the conscious mind is considered "singly conscious." In other words, the unconscious is a "parallel processor," while the conscious is a "serial processor." Unconscious should be thought of as not singly conscious, but multiply conscious. Further, this allows a totally new idea: Multiple singly conscious, different minds coexist simultaneously in time, though not in the same "3-dimensional mindspace." Suppose we consider a set of n such singly conscious minds. All the minds exist in a spacetime of dimensionality 3n + 1 (n is the number of different conscious minds in the set, and an additional dimension, time, is common to all minds in the set). Thus the considered set of singly conscious minds constitutes one multiply conscious—or "unconscious" -mind. In this way one may apeak of "levels of unconsciousness" in relation to groups of persons, with the deepest level being and containing every human mind. Of course the analogy can be continued to yield

the higher minds or consciousness projected by Teilhard de Chardin. In the collective human unconscious, those forms which are in each and every mind are the archetypes discovered by Jung. In a shallower level, other forms may be common to that level, constituting "weak archetypes" or "fragmentary archetypes." There is considered to be no limit to levels of unconsciousness—the ultimate depth being "all consciousness" (and all unconsciousness!) of Godness. God must be able to both be and not be at the same time; if God cannot do that little trick, then God has a limitation and is not unlimited.

209. Vacuum: pure virtual particle, massless charge flux. The virtual state, or ether (nonmaterial, Lorentzian). Lengthless, timeless spacetime itself. That state where everything is disintegrated, but highly dynamic. Note that vacuum is not an emptiness FILLED with massless charge, rather, it IS identically massless charge (disintegrated dynamicism). It is a plenum, not an emptiness. It is also pure action, undifferentiated. Einstein once suggested that the vacuum, complete with its electromagnetic and gravitational fields, should be taken as the ether. In the modern view, the term ether is again accepted in the literature, but now it refers to a "virtual particle flux" ether, not a thin material ether. One can model the vacuum analogous to a special kind of virtual-particle gas: one in which the particles "appear" and "disappear from and into nothing, nearly instantly, so fast that they cannot be individually detected. Thus the modern idea of the vacuum is a seething inferno of fiercely bubbling, fleeting particles. The other limitation is that the dimensionality of the vacuum is not fixed until operations are invoked, and neither is the rate of passage of time. Thus the vacuum has no fixed lengths nor fixed rates of time flow per se. One can visualize the stress of vacuum as a sort of conglomerate potential "pressure," where the individual stresses of various types of particles, if integrated by some external means, would sum into the overall stress (pressure). Variation of the "stress of vacuum" between two points in a frame represents a "curved spacetime" or "accelerated frame." Note that overall stress can be held constant, while two or more different components are canonically varied. The electrostatic potential, the magnetostatic potential, and the velocity of a charged particle are three such "canonical" variables. If the overall "pressure" is not varied, the three variables are canonical and energy, momentum, and charge are conserved and one cannot build a perpetuum mobile (perpetual motion machine). If the overall "pressure" is varied between local points in the frame, then the conservation of energy, momentum, and/or charge need not rigorously apply between those local points. At any one point, one may have a "free source" or a "free sink," depending on the vacuum curvature and the EM standing wave relationship. In that case, one can build a local "perpetuum mobile," since one can tap a "free source." Einstein created a severely restricted general relativity (GR), where he assumed away any local curvature of vacuum. In the West such a severely restricted GR is still dogmatically enforced, because it "saves" the conservation laws, which are regarded as sacrosanct In Soviet physics journals, learned papers by leading scientists are regularly published in which unrestricted GR—including local curvature—is developed and explored. In a local curvature region, the Soviets have already pointed out that any and all conservation laws may be violated. The Soviets have long since developed and weaponized unrestricted GR, while our scientists are still dogmatically insisting that one cannot deterministically engineer local curvature of spacetime. Thus we maintain our obsession with conservation, and the Soviets maintain the weapons.

210. Vector: in mathematics, an entity completely characterized by a magnitude and a direction. Abstractly, vectors are considered to be formed by a difference in potential between two spatial points. In the new approach, vectors are characteristics of particle motion, and do not observably exist in the absence of a particle. Since all detectors have mass, and this mass contains spinning charged particles, then force vectors are constituted on and of the spinning charged particles. In the vacuum, only an unzipped (disintegrated) vector pattern exists—or, as Feynman put it, only the potential for a force vector exists there. Maxwell's original theory was written in quaternions. In 3-space, a vector has the familiar three components, say, ai + bj + ck, where i, j, and k are the usual x, y, and z unit vectors, and a, b, and c are the magnitudes f the x, y, and z components of a vector. A quaternion, however, has an additional scalar component—say, w—so that it looks like w + ai + bj + ck. Maxwell's original theory actually unified gravitation and electromagnetics! When vector zeroing operations occur, the quaternion may not zero out the scalar component. As an example, consider the cross product of a vector A with itself, AxA. In vector analysis, the resulting vector is the zero vector. In quaternions, however, w remains, and w = a2 +b2 +c2. With the correct proportionality constants, w therefore represents the energy density of vacuum due to the two zero-multiplying vectors A1 and A2, where A1 = A2. To recover my scalar wave or gravitational wave: Now let the vectors A1 - A2 where each is the E-field vector of an identical EM sine wave. (That is, we perform a device which accepts two identical input EM sine waves and performs a cross multiplication. That device, e.g., may simply be a special kind of nonlinear modulator/mixer). In ordinary Heaviside/Maxwell theory, the EM output of this operation is a continuous zero vector, and that's all. However, by Maxwell's actual theory, the output of the operation is a scalar EM wave, whose amplitude varies as the energy of A. That is, the operation produces a scalar EM wave which is varying the energy density of vacuum. By definition, that is a gravitational wave. Since it was produced electromagnetically, I refer to it as an electrogravitational wave. It was included in Maxwell's original 1864 theory. After Maxwell's death, Heaviside and Gibbs completed the modern form of vector analysis. Heaviside—a single man—then "translated" (mutilated) Maxwell's theory into his new "vector" theory. He simply sawed off and discarded the troublesome scalar component of the quaternion! That made calculation a whole lot easier, and easier to understand. In discarding the scalar component, he discarded electrogravitation, writing an EM theory that specifically excludes local curved spacetime and gravity. Before the turn of the century, a short debate involving only about 30 scientists resulting in the complete adoption of Heaviside's mutilated version of Maxwell's theory. Quaternions and quaternion theory—and electrogravitation—vanished from the literature and the textbooks—and from the minds of the students. Maxwell's theory has not been taught or utilized in the Western

world in the 20th century! Only Heaviside's mutilated version of it is taught as "Maxwell's theory." We should have been applying Maxwell's unified theory and working on antigravity spaceships, shortly after the U.S. Civil War!

211. Vector field: in ordinary theory, the assigning of a magnitude and a direction (that is, a vector) to each point in space. The entire set of vectors and their spatial points is called a vector field. In the new approach, such a vector field cannot observably exist in a vacuum, since only disintegrated things exist there; there each potential vector pattern exists in broken virtual bits, ordered in line to form the bits of the observable vector but not joined. In the presence of a detecting/integrating mass, such as a spinning charged electron, the virtual bits and the spinning charged mass couple into a system that identically comprises the observable vector. In other words, the spin of an observable particle simply "integrates" the ordered virtual bit pattern, just as an old spinning wheel twists and integrates individual fibers into a stranded rope or thread.

212. Virtual (state): that part of physical reality consisting of changes (particles, waves, and other entities) smaller than the least detectable (quantum) change. Disintegrated changes. A thought or thoughtform is also virtual. May be visualized as consisting of real, dynamic "pieces of vacuum" or "pieces of nothing"—that is, quitons. Every ordinary observable particle (photon, neutron, electron, proton, etc.) contains or consists of a dynamically changing cloud of virtual objects. Exchange of virtual objects is thought to generate almost all forces of nature. Conservation of energy need not be conserved in virtual interactions, and generally is not In the new approach, the mind may be considered a special virtual universe, and a thought a virtual object. Virtual state consists of multiply nested levels, each level progressively finer and more subtle. These sublevels also correspond mathematically to higher geometrical dimensions. Charge on a mass is also due to its continual emission and absorption of virtual particles. Waves in the virtual state massless charge flux, which do not breach the quantum level to become observable, are vectorially nonobservable yet real—these are scalar waves, or shadow vector waves, and are longitudinal—that is, they are oscillations of the stress energy tensor of vacuum. In addition, the virtual particles in the vacuum flux arise out of nothing spontaneously (creation) and disappear into nothing spontaneously (annihilation). Since this is random, at any instant any sort of pattern imaginable is "just appearing" and "just disappearing" in the vacuum. Anything and everything at all! Thus a ghost-pattern of everything exists in the vacuum at any point or region, at any time. The vacuum is thus a giant virtual-state hologram. Integrating (kindling) one of these forms will result in it becoming first a neutrinic pattern, then a photonic (light) pattern, then a materializing pattern, and finally a material pattern. Discharge of the "potential" of this pattern then reverses the process. These two processes—charge-up and discharge—constitute materialization and dematerialization. Anything at at all-living or dead—can be materialized or dematerialized.

213. Virtual state engineering: the direct cohering, tailoring, collecting, resonating, and directing virtual state energy (anenergy) and entities into and onto normal observable objects and ordinary fields. It includes the **direct engineering of mind and life energies. Synonymous with psychotronics (Czech term) or energetics (Soviet term). Use of scalar electromagnetics (electrogravitation). Use of scalar wave/Tesla technology. Use of electrogravitation techniques.**

214. Water structuring: the arrangement and relations of the molecular and ionic parts of water. Essentially water molecules bond together by means of hydrogen bonds. The structure of these bondings is extremely rich and dynamic in water. Essentially a glass of water is a single complex molecule, one which is continually changing its bonding structure to adapt to the slightest change in its total surroundings. Water also interacts intimately with virtual crosstalk (scalar wave) anenergy. Water can thus be "charged" with ancnergy, appreciably changing its structuring. Its surface tension, for example, will change as its structuring changes, as shown by Miller and Flanagan. Thus water is possibly the most complex substance in the universe, and not just a simple chemical. With most of our body composed of intercellular water, we are all linked to every subtle change of the cosmos, by the interaction of the structuring of this water with even the most subtle cosmological changes. Large bodies of water are particularly susceptible for temporary kindling of deeper archetypal thought forms (tulpoids) such as Loch Ness Monster etc. The study of the structuring of water is still in its infancy.

215. Watson, James: young inventor who has produced several types of free energy and scalar electromagnetic devices, including battery-driven, battery-less, and tube systems.

216. Weather engineering (scalar): use of scalar electromagnetics (electrogravitation) to change and influence the weather and the producers of weather such as jetstreams and large ocean currents. By imposing scalar signals upon ordinary powerful over the horizon (OTH) radar carriers in the communications band (3 to 30 MHz), interference patterns (grids) may be established over distant and vast areas, far beyond the horizon, or even on the other side of the earth. The giant Soviet Woodpecker OTH radars continually establish such a grid over the U.S. Phase conjugate energy can be transmitted and will travel along these beams, just as electricity travels along a wire. By scanning narrow phase conjugate wave beams in these wider carrier beams, PCR realtime interference holography can be established in one or more of the distant OTR EM carrier interference grid squares. Either positive or negative energy and energy forms may be transmitted to emerge, producing a high or low pressure spot or zone as desired. By adding positive energy to a zone, the air is heated and expands. Thus the air is less dense, producing a low pressure zone, or a low. By adding negative energy to a zone, an equal amount of positive energy in the zone is canceled. Thus the air in the zone contracts and is denser, producing a high pressure zone, or a high. Thus one can create distant highs and lows at will. By slowly moving (scanning) the PCR beams, these distant highs and lows can be moved, thus deviating and directing the jetstreams, storm systems, etc. By outputting positive energy and warming the top of a thunderstorm anvil, while outputting negative energy to the side of the anvil and cooling it, drastic "downbursts" under the anvil can be created. U.S. satellites have photographed such anomalous holes appearing in thunderhead anvils over the U.S., and their association

with downbursts has been documented in the literature. Whether these are natural or engineered have yet to be established. Another signature of weather engineering—a "wheel and spoke" type of cloud, called a giant radial—has been seen widely throughout the U.S. and correlated with anomalous weather changes shortly thereafter. Sometimes a system of two such radials facing each other is seen, and on one occasion four were seen locked together (just before and during the highly anomalous zig-zag travel of a 1985 hurricane in the Gulf.) Another geometrical form associated with severe weather has been photographed by U.S. weather satellites, and is referred to in the weather literature as an "enhanced V". This signature is closely associated with the production of tornadoes, and it may be a natural phenomenon. However, if the mechanism for the enhanced V were artificially produced in a thunderstorm, then the probability of follow-on tornadoes would be materially increased. The Soviets have openly engineered the weather over North America since 1976, and made previous R&D engineering tests over the U.S. in 1967.

217. Woodpecker signals: powerful, complex electromagnetic signals originating in the Soviet Union (apparently from the vicinity of Riga and Gomel, for example) that have widely disturbed and interfered with the communications band (3-30 MHz) since the mid-70's. Bioactive modulations of 10 Hz and under have been observed repeatedly. Western observers have not deciphered the purpose or specific coding of the signals, and prefer to think of them as some sort of over-the-horizon radar tests, thus neatly disposing of the problem. Similar signals have been observed to entrain the human brainwaves and force them into in-phase oscillation. Beck has reported the phaselocked synchronization of the 10 Hz modulations on as many as 16 carrier frequencies at once. From the Lisitsyn work, this constitutes a "phased lock-in" of 16 carrier channels into any entrained brain. According to Lisitsyn and earlier Soviet "biological radio" experiments, this situation should allow the Soviets to transmit emotion, feeling, thought, and even pictures into the entrained brain, where it is processed as if the brain itself had originated it. (For example, in a Cable News Network special in November 1985, Rauscher and Bise actually demonstrated the induction of visual form images in the brain of the CNN investigator using weak signals much weaker than those naturally produced by oscillation of the earth's magnetic field.) According to the Kazhnacheyev work, any sort of cellular death and disease pattern can be electromagnetically induced. (The work was duplicated in the infrared by University of Marburg researchers in West Germany, by researchers at the University of Sydney, and by one U.S. scientist.) Popp discovered the virtual photon communication system of the cells of the body. This is scalar, and scalar patterns for charge distributions of the chemistry of cellular diseases and damage could also be placed on the phase-locked Woodpecker carriers, entering die human body's master control system through the entrained brain and "kindling" throughout the cells of the body. The stress and suppression of the immune system would be involved in almost all disease patterns, and a "partial AIDS" type of syndrome would result, making the entrained body vulnerable to whatever diseases were around, including being induced on the Woodpecker carriers themselves. Also, by targeting the DNA of specific organisms, mutations of deadlier and tougher strains of disease induction agents such as bacteria and viruses could be produced. The "antithesis" pattern—a sort of scalar EM antidote—could be induced in the Soviet population. (The present lethal AIDS is a manmade disease, and it was unleashed from a research laboratory either accidentally or by a Soviet agent on purpose.) Indeed, World War III may already have begun, and the Soviets may be waging a quite different kind of creepingly escalating viral war against the United States. If so, our Defense Department and our government have not yet grasped what is happening, and so far we are simply a sitting, passive target If our populace is slowly debilitated and storm, weather, and earthquake damage slowly increases year by year, at some point our system will simply start to come unglued, with increasing loss of control. In that manner we could "subside" as a world power without the kind of great overt war we are familiar with. Note that steady escalation of international terrorism, insurrection, and guerrilla warfare being promoted by the Soviets around the world will keep us preoccupied and busy while our debilitation and moraise steadily are increased. We may already be in an eery new kind of war that we could lose without firing a shot if our leaders do not wake up to the frightening implications of the new physics! Thus the Woodpecker transmitters represent a potential anti-population and strategic weapon of enormous strategic significance. The transmitters, because of their sheer power, also appear to be able to pump and resonate earth scalar EM energies, producing earthquakes and plasma discharge effects at remote locations. (Since Golden has directly shown that the entire earth is in frightful, forced scalar resonance at multiple frequencies and enormous power due to powerful Soviet scalar transmissions, then one should not be too skeptical of the Soviet ability to produce earthquakes on demand and to order.) At least one U.S. researcher or group seems to have been partially nullifying Soviet efforts in this respect by occasionally pulsing the earth scalar energies in a countering mode, to include actual destruction of a Soviet transmitter in one or more instances. Note especially that unorthodox researchers have directly confirmed that the Woodpecker signals contain powerful scalar components which orthodox scientists—lacking scalar detection equipment—do not see. The Woodpecker carrier interference grid over the U.S. is also a scalar EM interference grid, and used by the Soviets to engineer the weather over North America. It is also used as an anti-Bomber and anti-missile launch phase defense system, and the Soviets have tested it in this mode by destroying several U.S. aircraft and missiles.

218. Work: conventionally, the line integral of force on a body over the path taken by the body. In the new approach, the force consists of the mass and its motional change, unseparated. Thus work is the line integral of the force over the path taken by the force. Work (past) is equal to the energy (present) expended, and energy (present, gravitational potential) is equal to the work (past, release of a gravitational potential) that can be expended. Note that only vectors produce work; scalar waves do not perform work on their observable environment, and they do not contain standard EM force field energy per se.

219. Yao, George: engineer and inventor of the PulsorR, which affects the subtle scalar levels of the human body's aura or scalar radiation pattern.

220. Veti: the Eastern—particularly Tibet, Nepal, etc.—Himalayan version of the apeman tulpoid, corresponding to the U.S. Sasquatch or Bigfoot.

221. Zarg: the collective human unconscious, considered as a mind and a living entity. It is at least 4—billion dimensional, since it has as many dimensions as human stages. Each human is regarded as a single cellular stage in this entity. The psychokinetic power of such a linked mind is proportional to an exponential of the number of individual stages. Thus Zarg's psychokinetic power is so great that it has essential control over space and time, and largely prescribes, maintains, and stabilizes the laws of nature (laws of physics) and the reality in which we live. Conflict between large groups of humans constitutes unresolved conflict in this great unconsciousness, and this generates symbolic dreams, much as a human dreams strange, emotional, symbolic dreams due to the unresolved conflict in his or her personal unconscious mind. However, because of its vast psychokinetic power, Zarg materializes or partially materializes its symbolic dreams, resulting in tulpoids. Waves of these tulpoidal materializations thus represent strong human conflict or threats on the large scale. Such waves can be dream analyzed to discover the correlate that is generating the symbology, by straightforward dream analysis techniques. In olden times, part of this was known, and wise men were employed to analyze and interpret the strange, induced dreams of the king (who was the center of power of a nation) and the paranormal phenomena appearing near him. The ancients knew the import of "signs and wonders" and what they portended, but this metapsychological knowledge has been largely ridiculed and lost by present materialistic Western science.

222. Zero: naught or nothing; the absence of thing. A naive definition is the absence of number. However, if all the nonzero numbers are considered to represent the presence of number, then to declare zero a number—that is, the presence of a number—is a self-contradiction since it has just been declared the absence of number. In the numerical sense, one may do a little better by calling zero "the absence of any and all numbers except itself." Yet in this case, difficulties arise as to how one is to justify the addition of any other number to zero: how can a number be present with the absenting operator, so as to be added? The absence of any type of thing observable. Formally, the additive identity element of an algebraic system. That is, formally, the basic idea of zero is that, added to a number, the result is still identical to that number. Implicit in this formal definition is a "single level** of perceived objects; that is, there are no "hidden objects" in a separate level of sets. If multiple levels of perception are allowed, then the zero becomes much more complex. That is, it represents the absence of all other numbers at that particular level, and of that level's kind. In that case, it may contain any combination of objects from another level, yet be perceived as containing "nothing of its own assigned level." In that case, there exists an infinity of different "kinds" of zeroes, if the hidden associated structure (the substructure) If taken into account Unfortunately physics has created such multiple levels, but has not required its mathematics to clearly specify the changed nature of the zero. As an example, at the observable level, an infinite number of kinds of zeroes exist, when the virtual level and pattern associated with the zero are taken into account This characteristic of physics actually violates the following zero axiom: an observable v plus an observable zero is considered to be equal to an observable zero plus v. In fact, the sum of v and a particular zero may not be equal at all to the sum of another zero and v, if the virtual patterns of the two zeroes differ, v has a virtual substructure, and in the addition of a zero and v, their virtual levels nonlinearly interact instead of linearly superimpose.

223. Zero point energy: the kinetic energy that remains in a substance when its temperature is absolute zero. Quantum mechanics requires a simple harmonic oscillator to still possess kinetic energy at its lowest state: that is, it possesses half a quantum of energy. In solid materials it is distributed throughout the lattice vibrations, contributing to the binding energy. Vacuum also has zero point energy. Actually a similar and much expanded concept applies to any potential: a potential is just a bunch of trapped dynamic vectors, hence "trapped vector (translational) energy." It is translational energy that is locally trapped and not translating. The potential is thus like an accumulator or capacitor. It can be "charged up" and "discharged." It thus contains its own analog or trapped or "zero summed" or "zero point" energy.

224. Zero-point energy of vacuum: the vacuum is increasingly being regarded as composed of an incredibly dense structure of virtual electromagnetic energy, even at zero degrees absolute. From quantum geometrodynamics, as one approaches the Planck length—say, 10 to the minus 35th meters—these oscillations become so energetic that the fabric of spacetime itself is torn, resulting in sporadic, continual connection and disconnection of widely separated portions of spacetime. This "quantum foam" was dubbed "superspace" by J.A. Wheeler. Actually, if space and time are torn, then energy itself—and vector waves—are also torn. That is, the superspace consists of pure massless charge flux, pure scalar waves. If compacted, this anenergy density of vacuum may be approximated as 10 to the 100th grams per cubic centimeter, were it compacted into mass. The actual electrical charge of the vacuum appears to be enormous, if it were possible to measure a voltage drop from it to an uncharged region. Thus it is space (actually spacetime) that is incredibly dense, and matter that is ethereally thin. Spacetime goes through matter, rather than matter through spacetime. This anenergy of vacuum does interact with electromagnetic fields and matter to give observable effects, as evidenced by the Lamb shift, for example. The Lamb shift proves that the vacuum charge or anenergy can be "tapped." Tapping the "vacuum energy" would immediately end the energy crisis forever. Further, it can be done with practical devices, as T. Henry Moray showed in the 20's and 30's, and as several present inventors have shown today.

225. Zero vector: a vector having no length (no magnitude) or specific direction. Absence of any or all finite vectors. Resultant of a system of multiple, finite vectors whose vector sum has no specific direction. Note that the second definition differs drastically from tho first. That if, we cannot say that a vector resultant zero has no infolded magnitude, if we consider the components, all of whom have magnitude. See the discussion under "zero." In vector analysis, the zero vector axiom states that any vector v plus a zero vector is equal to a zero vector plus v. (Note that this axion is not proven, just assumed).

However, there are an infinite number of different zero vector resultant systems, and so zero vectors may differ, if their infolded component "substructure" is considered. Indeed, a zero vector system must be identified as a special form of potential, if its substructure is considered. The common practice in electrical physics of replacing a zero-summed system of vectors with a vector zero is incomplete, and such did not exist in Maxwell's original quaternion theory. This present practice should be changed; the vector zero should be replaced with a special organized vector zero system and a scalar potential. By failing to do this, physics excludes the ability to engineer electrogravitation, spacen'me, the virtual state, local general relativity, free energy, effects at a distance, and the probabilities of the states propagated by the Schroedinger equation. It also excludes scalar electromagnetics (electrogravitation), and unification of all forces in an engineering electromagnetics fashion. In the new view, a zero vector may be a system of vectors that vectoiially sum or multiply to zero, but the components may still exist "inside" and dynamically function inside the zero-resultant envelope. This substructure can act on nonlinear or resonant systems. Any or all components may be time varying, or none of them may be. The zero vector system may thus be a dynamic vacuum engine. In addition, such a vector zero system is considered to be also a scalar stress potential, whose magnitude is equal to the sum of the absolute values of the perpendicular components. In addition, a separate type of stress potential may be included for the magnitude of the absolute values of the swirl components (torques). Other associated potentials may be included for the system, particularly if the system is in multiple dimensions, if it consists of more than one type of virtual particle flux, if several fluxes intercommute, etc. Such a system can also be designed and created to deterministically interact with and on the life force itself, the mind, thought, and personality.

BIBLIOGRAPHY

"Analysis of a Phenomenon Occurring at Bell Island, Newfoundland, **Canada on** April 2, 1978," P.A.C.E., Ottawa, Canada, 1978.

Thomas E. Bearden *Quiton/Perceptron Physics: A Theory of **Existence, Perception,** and Physical Phenomena,* Defense Documentation **Center (DDC), March** 1973.

Thomas E. Bearden, *Field, Formon, Superspace, and Inceptive Cyborg: **A Paraphysical** Theory of Noncausal Phenomena,* DDC, 1974.

Thomas E. Bearden, *A Conceptual Derivation of Einstein's Postulates of **Special** Relativity,* DDC, October 1975.

Thomas E. Bearden, *Restatement of the Heisenberg Uncertainty Principle For the Condition of Superposition,* DDC, October 1975.

Thomas E. Bearden, *A Postulated Mechanism That Leads to Materialization and Dematerialization of Matter and to Antigravity,* DDC, October 1975.

Thomas E. Bearden, *The Boundary Identity of Exact Opposites: A Simple Solution to the Age-Old Philosophical Problem of Change,* DDC, October 1975.

Thomas E. Bearden, *An Approach to Understanding Psychotronics,* privately published, 1976. Defense Documentation Center, AD-A027 866.

Thomas E. Bearden, "The One Human Problem, Its Solution, and Its Relation to UFO Phenomena," *Pursuit* (Journal of the Society for the Investigation of the Unexplained) January 1976.

Thomas E. Bearden, "Writing the Observer Back Into the Equation," address given to Princeton Center for Alternative Futures, Princeton, N.J., March 5, 1976.

Robert C. Beck, *Extreme Low Frequency Magnetic Fields and EEG Entrainment, A Psychotronic Warfare Capability?,* Bio-Medical Research Associates, Los Angeles, March 1978.

Robert C. Beck, *Instrumentation for Detecting, Recording, and Analyzing Natural and Man-Made ELF Signals and Human Brainwaves,* Bio-Medical Research Associates, Los Angeles, May 1978.

William Bise, "The Soviet 10 Hz Pulses—A Brainwave Programming Mechanism?" *Specula* (Journal of the American Association of Meta-Science), Huntsville, Alabama, Vol. 1, No. 3, 1978.

T. Townsend Brown, "Electrical Self-Potential in Rocks," *The Psychic Observer and Chimes,* Vol. 37, No. 1, January-March 1976.

Trevor James Constable, *The Cosmic Pulse of Life,* Merlin Press, Santa Ana, CA, 1976.

Trevor James **Constable,** "You, Too, Can Photograph UFO's **from Airliners,"** *Psychic **Observer and Chimes,*** **Vol. 37**, No. 3, May-June 1977.

George D. Curtis, "An Electromagnetic Radiation Pattern Over The Ocean," *Undersea Technology,* Vol. 5, No. 8, August 1964.

Lars-Erik DeGeer, Swedish National Defense Research Institute, "Airborne Short-Lived Radionuclides of Unknown Origin in Sweden in 1976," *Science,* Vol. 198, No. 4320, December 1977.

B.V. Deryagin and I.I. Abrikosava, Soviet Physics, JETP3, 819 (1957); 4, 2 (1957).

P.A.M. Dirac, "Development of the Physicist's Conception of Nature," *Symposium on the Development of the Physicist's Conception of Nature,* ed. Jagdish Merha, D. Reidel Publishing Company, Boston, 1973, pp. 12-14.

P.A.M. Dirac, "Quantized Singularities in the Electromagnetic Field," *Proceedings of the Royal Society of London,* Series A, Vol. 133, 1931, p. 6.

William W. Edison, David L. Faust, Harry J. Kyler and John O. Pehek, "Kirlian Photography: Myth, Fact and Applications," presented at the session on *New Electronic Methods for Medical Diagnosis and Treatment Using the Human Energy Field: A New Beach-Head for Scientific Discovery,* Electro 78, May 23-25, 1978, IEEE, New York.

Robert Eisberg and Robert Resnick, *Quantum Physics of Atoms, Molecules, Solids, Nuclei, and Particles,* John Wiley & Sons, 1974, pp. 63-68, 146-150.

Hugh Everett, III, *The Many-Worlds Interpretation of Quantum Mechanics, A Fundamental Exposition,* with papers by J.A. Wheeler, B.S. DeWitt, L.N. Cooper and D. Van Vechten, and N. Graham; eds. Bryce S. Dewitt and Neill Graham, Princeton Series in Physics, Princeton University Press, 1973.

Richard Feynman, *The Character of Physical Law,* M.I.T. Press, 1967, pp. 31-33.

Richard P. Feynman, Robert B. Leighton, and Matthew Sands, *The Feynman Lectures On Physics,* Addison-Wesley, 1963, Vols. 1, 2, and 3.

Marjorie E. Fish, "Journey Into the Hill Star Map," *Proceedings of the 1974 MUFON Symposium,* Mutual UFO Network, 1974.

Richard Garvin, *The Crystal Skull,* Pocket Book, 1974.

Burkhard Heim, *Unified Quantum Field Theory of Matter and Gravitation,* Mutual UFO Network, Seguin, Texas, 1972.

Louise and Galen Hieronymus, *Tracking the Astronauts in Apollo 11, With Data From Apollo 8 Included,* Advanced Sciences Research and Development Corporation, Inc., Fort Lauderdale, Florida, 1969.

J. Allen Hynek, *The UFO Experience: A Scientific Enquiry,* Ballentine, 1974.

J. Allen Hynek and Jacques Vallee, *The Edge of Reality,* Regnery, Chicago, 1975.

H.E. Ives, "Derivation of the Lorentz Transformations," *Phil. Mag.,* Vol. 36, June 1945.

H.E. Ives, "The Behavior of an Interferometer in a Gravitational Field," *J. OPT. Soc. Am.*, Vol. 29, May 1939; and "The Behavior of an Interferometer in a Gravitational Field: II. Application to a Planetary Orbit," *Ibid.*, Vol. 38, April 1948.

David Michael Jacobs, *The UFO Controversy in America*, Indiana University Press, 1975. [Foo-fighters]

Brian D. Josephson, "Possible Connections Between Psychic Phenomena and Quantum Mechanics," *New Horizons,* Vol. 1, No. 5.

V.P. Kaznacheyev et al, "Apparent Information Transfer Between Two Groups of Cells," *Psychoenergetic Systems,* Vol. 1, No. 1, December 1974.

V.P. Kaznacheyev et al, "Distant Intercellular Interactions in a System of Two Tissue Cultures," *Psychoenergetic Systems,* Vol. 1, No. 3, March 1976.

Louis Kervran, *Biological Transmutations,* Swan Publishing Company, Binghamton, N.Y., 1972.

"Kindling, Once Epilepsy Model, May Relate to Kundalini," *Brain/Mind Bulletin,* Vol. 2, No. 7, February 21, 1977.

N.A. Kozyrev, "Possibility of Experimental Study of the Properties of Time," *Pulkovo, O vozmozhnosti eksperimental 'nogo issledovaniya svoystv vremeni,* September 1967, pp. 1-49, JPRS 45238, May 1968.

Michael Ledeen, "A Mole in Our Midst?", *New York,* October 2, 1978, pp. 55-57.

E.M. Lifschitz, *Soviet Physics* JETP 2, 73 (1956).

James M. McCampbell, *Ufology: New Insights from Science and Common Sense, Jaymac Company, Belmont, CA, 1973.*

George Meek, Healers and the Healing Process, Theosophical Publishing House, 1977.

T. Henry Moray, *The Sea of Energy in Which the Earth Floats,* Cosray, Salt Lake City, Utah, 1960.

Captain John D. LaMothe, Ph.D., *Controlled Offensive Behavior*—U.S.S.R., ST-CS-01-169-72, Defense Intelligence Agency, Washington, D.C. (Released under the Freedom of Information Act.)

Captain John D. LaMothe and Mr. Louis Maire, *Soviet and Czechoslovakian Parapsychology Research,* DST-1810S-387-75, Defense Intelligence Agency, Washington, D.C. (Released under the Freedom of Information Act.) [Pavlita]

Charles Muses, "Applied Hypernumbers: Computational Concepts," *Applied Mathematics and Computation,* Vol. 3, 1976.

Charles Muses's foreword to Jerome Rothstein, *Communication, Organization and Science*, The Falcon's Wing Press, Indian Hills, Colorado, 1958.

Charles Muses and Arthur M. Young, eds, *Consciousness and Reality,* Outerbridgc& Lazard, 1972.

E.I. Parnov, *At the Crossroads of Infinity,* translated from the Russian by Vladimir Talmy, MIR Publishers, Moscow, 1971.

Harold Puthoff and Russell Targ, *Mindreach,* Delacorte, 1977.

Harold Puthoff and Russell Targ, "A Perceptual Channel for Information Transfer Over Kilometer Distances: Historical Perspective and Recent Research," *Proceedings of the IEEE,* Vol. 64, No. 3, March 1976.

The Pyramid Guide, ed. Bill Cox, El Cariso Publications, Lake Elsinore, CA. (Bimonthly: subscriptions are $6.00 a year.)

Edward W. Russell, *Report on Radionics,* Neville Spearman, London, 1973.

R.M. Santilli, "Partons and Gravitation: Some Puzzling Questions," *Annals of Physics,* Vol. 83, No. 1, March, 1974, pp. 108-157.

Berthold E. Schwarz, "Stella Lansing's Movies: Four Entities and a Possible UFO," *Flying Saucer Review,* Special Issue No. 5, November 1973.

Berthold E. Schwarz, "UFO Contactee Stella Lansing: Possible Medical Implications of Her Motion Picture Experiments," *Journal of the American Society of Psychosomatic Dentistry and Medicine*, Vol. 23, No. 2, 1976.

Bob Shiarella, "The Mysterious 'Skull of Doom'," *Argosy*, Vol. 376, No. 4, April 1973.

Brad Steiger, *Mysteries of Time and Space,* Prentice-Hall, 1974.

Edwin F. Taylor and John Archibald Wheeler, *Spacetime Physics,* W.H. Freeman and Company, 1966.

Yakov P. Terletskii, *Paradoxes in the Theory of Relativity,* Plenum, 1968.

John White and Stanley Krippner, eds., *Future Science,* Anchor, 1977.

C. Louis Wiedemann, "Results of the N.J. 'Spook Light' Study," *Vestigia Newsletter*, Stanhope, N.J., May 1977.

Robert Anton Wilson, *Cosmic Trigger*, And/Or Press, Berkeley, CA, 1977.

V. Ye Savkin, *The Basic Principles of Operational Art and Tactics,* Moscow, 1972, U.S. Air Force translation, U.S. Government Printing Office, Washington, D.C.

Arthur M. Young, *The Reflexive Universe*, Delacorte Press, 1976.

The Tom Bearden Website

CANCER AND THE UNRESOLVED HEALTH ISSUES IN THE BIOLOGICAL EFFECTS OF EM FIELDS AND RADIATION

- Text of Booklet
- List of Accompanying Slides (63)

The Tom Bearden Website

CANCER AND THE UNRESOLVED HEALTH ISSUES IN THE BIOLOGICAL EFFECTS OF EM FIELDS AND RADIATION

Largely taken from the author's presentation, "Mechanism for Long-Term Cumulative Biological Effects of EM Radiation," 70th Annual Meeting of the Alabama Academy of Science, University of Alabama at Huntsville, 25 March 1993.

T.E. Bearden
Association of Distinguished American Scientists
POB 1472
Huntsville, Alabama 35807

Go to Slides

Abstract

Both postulates in the conventional EM bioeffects model are in error, as is the classical electromagnetics model (CEM) itself. Major errors in CEM are presented. The QM view is taken that all EM phenomena are caused by the potentials, not the force fields. Using the Whittaker/Ziolkowski (WZ) internal structure of the scalar potential, Bohm's quantum potential and an engineerable variant of his hidden variable theory emerge. A strong candidate emerges for the internal mechanisms used for mind, thought, long term memory, and deep cellular control by Popp's master cellular control system. An environmental negative feedback mechanism is stated for long-term, cumulative causative mutation, yielding Sheldrake's morphogenetic field, which is a species quantum potential. Utilizing the new EM bioeffects model, Kaznacheyev's demonstration that any cellular death or disease can be caused electromagnetically is explained. A new definition for cancer is advanced, as is a long-term cumulative mechanism that causes it. The mechanism for Priore's demonstrated cures of terminal tumors in laboratory animals under rigorous scientific protocols is explained. A solution for the major cumulative mechanism for biological effects of EM fields and

radiation is presented. A self-targeting mechanism is presented whereby complex WZ EM biwave pumping of the "cell as a nonlinear phase conjugate mirror material" produces an exact EM antidote signal for the specific cellular disease. It is argued that inexpensive, quick, nondebilitating, cures can be developed for most major dread diseases, including cancer, arteriosclerosis, and AIDS. Priore's remarkable and previously unexplained cures of terminal tumors in lab animals are cited as examples of applying the new model, albeit unwittingly.

The Basic EM Bioeffects Model Is In Error

As is well-known, the field of EM fields and radiation effects on biological systems is actually in something of a shambles. In over 40 years of studies and experiments by careful researchers, the results are inconsistent, contradictory, and usually difficult or sometimes impossible to replicate. Attempted replications often give contradictory results, erratically. Researchers cannot rigorously answer even the simplest question, such as "Does power line radiation contribute to the incidence of cancer and leukemia, and if so, how and under what circumstances?" Causative mechanisms have so far eluded research. Powerful vested interests fund many of the studies. Consequently a great deal of controversy exists in the field. Opinions and positions range from the "microwave oven" position that "if it doesn't appreciably heat tissue, it doesn't harm biological organisms," to the "total fear" position that "any and all non-ionizing radiation is harmful; we just don't know by what mechanism." Legal actions to limit human EM radiation exposure are increasingly being initiated by concerned citizens' groups.

What has actually been "proven" by the nearly fruitless EM bioeffects effort to date is that the fundamental EM bioeffects model being utilized by the researchers is totally inadequate for the *task intended.* If that is true, then 40 more years of continuing to apply the same inadequate model isn't going to make very much additional progress. Further, if the fundamental model is faulted, then what is needed is a detailed examination of *the* model to discover and correct those foundation faults.

In tackling this model foundations problem, I have performed a systems engineering layout of the fundamental EM bioeffects model, and stated its two major postulates. Both postulates turn out to be in error! Immediately one can easily see *why* the field is in such a state of confusion. However, no true systems engineer would stop there. I have also performed a systems engineering layout of precise corrections for the two postulates, thereby correcting and extending the model so that it can yield consistent, replicable results and causative mechanisms. All of this is a rigorous procedure, and straightforward systems engineering methodology.

However, the results point to profound changes, which I have been immersed in deeply studying for quite some time. Out of this approach has emerged something quite fundamental: *a strong candidate for the internal mechanisms used for mind, thought, long term memory, and the deep cellular control system for all cells of the body.* A mechanism for species adaptation also emerges that is quite capable of explaining (and yielding) long-term directed mutation, including the "species jump," where a species such as a bird emerges in short order (not gradually) from a species such as a reptile. The known "species jump" has been a deep mystery to evolution theory, which simply could not explain it. Another thing that has emerged is a startling new *electromagnetic* causative mechanism for cancer, leukemia, etc. At the June 1993 Brain-Mind Symposium in Los Angeles, I will present that exact mechanism. The mechanism is capable of laboratory test, and validation or falsification. We will also present an entirely new approach to EM effects on biological organisms, and present the major new mechanism involved. The new mechanism has fundamental application to the theory of diseases, and offers potential curative mechanisms for dread diseases such as cancer, arteriosclerosis, and AIDS. I explain some of the necessary background in the following paragraphs.

Classical Electromagnetics is Seriously Flawed

As is well-known, there exist severe contradictions between classical electromagnetics (CEM), general relativity (GR), and quantum mechanics (QM). As presently constructed the three disciplines cannot be unified, even by Herculean efforts. Particularly with respect to the primary causative agents for electromagnetic phenomena, the foundations of QM and of CEM are in profound disagreement. CEM assumes *the forcefields* as primary causes, paying only lip service to the potentials and treating them as primarily mathematical conveniences. QM, on *the* other hand, has long since [since 1959] shown that the force fields are simply *effects* in and on the charged particle system, and are not causes. Instead, QM has shown that the *potentials* are the primary causes of all EM phenomena. In charged particle systems, potentials can interfere and cause observable EM phenomena such as the Aharonov-Bohm effect in the complete absence of the force fields. Herein lies *the* reason for the present dire straits of EM bioeffects research. We explain further:

CEM theory was originally formulated by James Clerk Maxwell in terms of quaternions. Note that quaternion algebra has a much higher topology than either vectors or tensors, the mathematics in which CEM is presently expressed. None of the present "Maxwell's equations" _ universally taught as due to Maxwell _ ever appeared in anything by Maxwell himself. Depending upon what you wish to call a fundamental equation, Maxwell's true equations are the numerous *quaternion* equations included in one almost incomprehensible chapter of his 1873 book. The present four "Maxwell's Equations" are in fact due mostly to Oliver Heaviside, and to a lesser extent to Gibbs and Hertz. The major player was Heaviside, a very brilliant but self-educated man who never attended University.

At the time Maxwell's book was published, Heaviside was just teaching himself calculus and differential equations. Seeing the book, he was electrified by it, and Maxwell became his undying hero. Maxwell died not long after, of stomach cancer.

Heaviside believed _ as did almost every scientist at the time _ in the older medieval tradition that *forces* were the causes of all physical effects. He had great difficulty with the potentials, stating that they were *"mystical and should be murdered from the theory."* We know today in modern quantum field theory that forces are effects, not primary causes of anything. In fact, it is the exchange of virtual particles with a mass that generates all forces upon it. As is well-known to foundations physicists today, "force" does not exist without the mass present to be acted upon, and without the action of a potential gradient upon the mass. We know that there are no force fields in the vacuum, and hence potential gradients in the vacuum are not forces, even though they are commonly assumed to be. CEM has not been corrected for these glaring defects: it prescribes force fields in the vacuum, and it prescribes that potential gradients are forces, even in the absence of any mass for the gradients to act upon.

Heaviside also abhorred the quaternion theory. The coupling of a scalar component with three directional components was, in his view, "mixing apples and oranges." He knew that engineers would never master Maxwell's use of quaternion mathematics because of its difficulty. Consequently, Heaviside simply chopped off the scalar component of the quaternion and discarded it, then formulated this new "truncated to a vector" version as a much simpler mathematics, albeit of decreased topology. What he unknowingly threw away was the ability of the quaternion theory to capture an *internal* deterministic, vectorial EM structure of the scalar potential. *[It turns out that he also discarded the unification of EM and gravitation by throwing out the scalar component, but that is outside the scope of my presentation.]* Years later as a lonely recluse in a small upstairs apartment, Heaviside turned back to quaternions to work on a theory of gravitation, according to papers found hidden beneath the floor of his study many years after his death.

Learned journals of the day would not accept Heaviside's papers for publication, because of the assumed "brutality" of his mathematical methods. So Heaviside began publishing very practical papers in a technical magazine, for the time roughly equivalent to *Scientific American* today. These practical papers gave transmission line theory, transformer theory, etc. _ things very useful to the early would-be "engineers" who were struggling with installing telegraph lines, undersea telegraph cables, etc. The vector mathematics utilized by Heaviside was much easier to understand and apply, and his work was eminently practical. Consequently it was eagerly seized upon and applied. The result was that Heaviside's EM model became the ipso facto CEM standard. Note that, at the time, only about 30 or so scientists in the world were truly "learned" in EM _ either from the vector standpoint or from the quaternion standpoint. Further, not much *practical* work was being done by the few quaternion practitioners.

A short "debate" over whether EM should use Maxwell's quaternion model or the Heaviside/Gibbs vector model occurred prior to the turn of the century, mostly in the journal *Nature*. It never involved over a handful of scientists, and it wasn't much of a debate. The vectorists simply threw out the quaternion EM theory and adopted the vector theory of Heaviside and Gibbs. Note that this represented a substantial curtailment of Maxwell's actual theory. *In other words, you can actually do a lot more in and with EM fields and circuits than what now appears in "modern" EM theory, and "modern" EM analysis won't even show it.* Barrett's Oscillator-Shuttle-Circuit analysis of Tesla's actual patented circuits shows this clearly and resoundingly. Also, *living systems utilize the discarded subset of EM for their most vital control functions, and the present theory and* *methodology will not detect or "see " this.* Thus this curtailment alone has resulted in the profound crippling of the conventional EM bioeffects model and efforts to apply it.

The Present CEM is a Flawed Subset of Nature's Electromagnetics

So we have several serious things that are quite wrong with current CEM theory. First, the theory (and its practice) are *artificially* limited to only a subset of the real EM that can be achieved and utilized. The present CEM unwittingly excludes the very type of EM utilized by living systems for their deepest control functions. It also excludes electrogravitation. Second, Maxwell's theory was actually based upon the assumption of a *mechanical (material) ether,* which meant that he could logically assign material forces to the "vacuum" or "ether fluid." Heaviside's translation (and curtailment) to vectors did not charge this "material ether" and "force field in vacuum" assumption.

However, in 1887 the Michelson-Morley experiment resoundingly destroyed the notion that the ether is material. If the ether were truly a thin material fluid, then forces and EM force fields would indeed exist in it. Since the ether is not material and forces exist only in, on, and of matter, no E-field or B-field exists in the nonmaterial vacuum; none ever has, and none ever will. In his three volumes of physics, Feynman pointed out that only the *potential* for the EM force fields exists in the vacuum; the only thing that exists in vacuum is *potentials,* after all! The vacuum is just a fantastic collection of interfering potentials and potential gradients. Rigorously, the E- and B-fields we detect with our instruments *exist only in the electron gas in the probes we utilize.* This is well-known to a few foundations physicists, but the CEM model has never been corrected for these foundations errors.

Note that the loss of the material ether also falsifies one of the three key assumptions in modern potential theory: the notion that the gradient of the potential comprises a force field. We know today that the CEM equation $E = -\nabla\phi$, is actually incorrect *for the vacuum.* It is correctly *measured;* since that is exactly what is detected when the vacuum $\nabla\phi$ potential gradient couples to the free electrons in our detecting/measuring instruments. What we detect as E, however, is actually $[(\nabla\phi \bullet (e^-)]$, or the potential gradient coupled to the electrons, including their masses. Specifically, we do not detect the nonmaterial (VO that actually exists in the vacuum. We detect electron wiggles in the free electron gas in the conductors of our instruments; we do not detect "vacuum wiggles" per se.

Neither Maxwell's quaternion EM equations nor Heaviside's vector EM equations include electron spin effects, but actually model electricity as a "thin fluid." Hence the EM equations of either model are *fluid dynamic* equations. Specifically, the measured transverse EM waves exist in the electron gas of our detectors; any detector detects only its own internal change, *not* the external agent that interacted and caused that internal change. White the "signal" races down the conductors in our probes and sensors at essentially the speed of light, the "free" electrons in the electron gas in those conductors are *longitudinally* restrained. The electrons must essentially move laterally from their initial distribution inside the conductor to its skin, then "slip" slightly down the wire on the skin at only the electron drift velocity, which is a fraction of a centimeter per second. The spinning electrons in the electron gas, being longitudinally restrained, act as *gyroscopes.* When disturbed by an interacting force, they precess. It follows that the lateral motion of the electrons inside the conductors of our detectors is just this "electron precession." It also follows that the direction of the disturbing force must be at right angles to the electrons' measured transverse precession movement. Rigorously, EM waves in the vacuum thus are *longitudinal,* not transverse. We *measure* transverse waves in our detectors and instruments because we are detecting and measuring the *electron precession waves in the free electron gas in the conductors of those instruments.* But as Tesla pointed out, there are no Hertz waves in the vacuum; instead, EM waves in the vacuum are longitudinal "sound" waves, or *waves of rarefaction and compression of the medium.* From modern QM we also know what the medium is: it is a flux of virtual particles. Again, as can be seen, the CEM model is seriously in error in its representation of EM waves in the vacuum.

We will not pursue this further; it is well-known to a few physicists in foundations work (but not to most electrical engineers and electrical physicists!) that classical EM theory is seriously flawed, and that it should be upgraded to correct those flaws. As is well-known in QM since 1959, it is the potentials that are the actual causes of all EM phenomena, and the potentials can interfere to cause real EM effects in charged particle systems, even in the absence of the force fields. The Aharonov-Bohm effect is an example, as are several other derivative effects well-established in the literature. What has been ignored even in QM, however, is the *organized internal structure* of the potential, even though the original (vector) discovery by Stoney occurred in 1897 and was extended by Whittaker in 1903.

This internal structure of the scalar potential had been implicitly present in Maxwell's 1873 quaternion theory, as an integral part of the scalar component of the quaternion resultant of the intera**ct**ion between two or more quaternions. In quaternions, a scalar entity may be regarded as a special quaternion entity whose translation has been reduced to zero. A vector entity may be regarded as a special quaternion entity all aspects of which are translating, and no nontranslating aspect is present. Thus the scalar quaternion entity may be totally composed of vector components, so long as they sum or multiply to a zero translation resultant but possess a finite nontranslating magnitude.

The Scalar Potential Has an Internal Bidirectional Wave-Pair Structure

In a profound but ignored 1903 paper of enormous consequences, E. T. Whittaker decomposed the scalar EM potential into a harmonic set of bidirectional wave pairs, extending the original 1897 work of Stoney. Each wave pair consists of a wave and its phase conjugate replica (its "anti-wave" or "time-reversed twin".). Thus the scalar potential has a rich internal biwave structure. [Further, one can *make* a scalar potential by simply assembling the necessary multiple waves, and one can alter the internal structure of the potential at will by altering the waves utilized in the assembly process.] In 1904 Whittaker published a formidable second paper, showing that all of CEM could readily be replaced by scalar potential *(hidden multi-wave)* interferometry. In other words, scalar EM is far more basic and extensive than is the present CEM with its emphasis upon the force fields.

E.g., you can alter the internal structure of the Schroedinger potential, and place deterministic biwave "hidden variables" inside. You can then "engineer" these hidden variables _ and consequently the Schroedinger potential _ by external means. In other words, you can even accomplish *at least limited engineering of quantum change itself.* This of course reduces the Gibbs statistics (which assumes a totally random quantum change) to a special case, and provides a more general case of chaotic quantum change, which is still statistical but may contain hidden order. Note that this statement is experimentally testable. It also resolves the greatest problem in quantum mechanics today: the problem of the missing chaos (hidden order).

In 1989 Ignatovich placed a paper in the *American Journal of Physics* pointing out a similar internal biwave structure of the Schroedinger potential, but none of our scientists seems to have realized the profound implications. *If we apply these proven mathematical extensions of electromagnetics, we are now dealing with a higher topology hidden variable theory, along the lines shown by Bohm, but one that is engineerable on the lab bench.*

Ziolkowski's Extension Allows Hyperspatial Communication

In 1985, a brilliant EM scientist named Ziolkowski independently rediscovered Whittaker's internal biwave harmonic decomposition of the scalar potential. He also extended the "internal structure" theory, to encompass not only the sum set but also the product set. Since the product of waves represents modulation, Ziolkowski's brilliant work provides the setting for *direct information communication capability* in the internal structuring of the scalar EM potential.

Further, this internal channel is in the virtual state, so one is accomplishing virtual state engineering, in the sense of the vacuum engineering posed by Nobelian Lee. If one uses a 4-space Minkowski model, the Whittaker/Ziolkowski channel information may be viewed as *subspace* communications. If one utilizes an n-space Kaluza-Klein model, where n is greater than 4, then the Whittaker/Ziolkowski channel information may be viewed as *hyperspace* communications. *Living systems already use this inner EM channel.*

Living Systems Use the Internal Channel Communication

It turns out that living systems utilize precisely the Whittaker/ Ziolkowski (W/Z) mechanism for their deepest functions and control systems _ including mind, thought, long-term memory, and the master cellular control system (MCCS) discovered by Dr. Popp of Germany. What we are stating is that, for the very first time, *we now* *know where and how the mind's "deepest software" is, its fundamental mechanism, and how to go about programming it directly.* However, we first must develop new measurement instruments.

Unfortunately, present EM instruments are almost all only "electron-wiggle" detectors; they detect only the *translation of electrons. A gradient* in the potential will couple to electrons and translate them. The *gradient-free* potential does not translate electrons, and it is the internal biwave W/Z structure of that gradient-free potential that we need to measure. Presently no known instrumentation will do that.

However, if two different scalar potentials are interfered [Whittaker 1904], their interference reproduces potential gradients [normal "force field" EM], which *do couple to electrons and translate them.* In fact, potential gradients (which in CEM are erroneously called "force fields") were already shown by Whittaker to be entirely due to the interferometry of two scalar potentials. So new "scalar interferometry" instruments must be developed to "outfold" the internal contents of the scalar potential as gradients, and then utilize normal instrumentation to measure those interference gradients and calculate the potential's internal structuring. One form for the detector is the use of a standard potential (with a known internal biwave structure) inside a Faraday-shielded chamber, so that the test gradient-free potential (which penetrates such a cage) interferes with the standard potential inside the cage to produce gradients therein. *A* probe in the interference zone detects the gradients as electron translations, which are conducted externally to amplifiers, meters, spectrum analyzers, computer programs, etc. The end result is the determination of the internal WZ structure of the test potential. Other detector types are possible; this is just a "straightforward" type.

Thoughts, Mind, Memory, and Cellular Control Are Measurable

What we are saying is that, by developing the proper instrumentation, it is possible to directly detect and examine thoughts, memory, and deep control system functioning of the biological organism, including the deep internalistics of its personal quantum potential. We are speaking of the pending emergence of an experimental science, not just a speculation.

However, we are dealing now with a form of "hidden variable" theory, but one that is engineerable and testable. So we will become directly involved with Bohm's *quantum potential,* both experimentally and theoretically. *A* quantum potential can connect widely separated systems by instantaneous effects, as if the systems were not separated but were located together as a single system. Further, the quantum potential does not have a single localized source. Suffice it to say that in 1991 I published the discovery of how a quantum potential is actually created. If one utilizes the proven "self-targeting" or iterative phase conjugate shooting mechanism from the Strategic Defense Initiative, and applies it to the WZ waves internal to the scalar EM potentials from two separated charges, then in a dense signal environment the self-targeting interaction may be initiated, so that the separate potentials merge into a single nonlocalized or "spread-out" potential consisting of laser-like beams between the charged particles comprising the separated systems involved. In that case, part or all of any EM change in one system is immediately experienced in the other systems participating in the effect. The communication is superluminal. The limitation to luminal velocity applies only to the "surface gradient" of a potential, not necessarily to the bidirectional waves in its WZ internal structure. Those internal waves are in either hyperspace or subspace, depending upon whether one models the situation in more than four dimensions or in only four.

The point is, *the quantum potential also has a W/Z internal structure.* And that structure can be deliberately created and engineered by external means. Action at a distance is not only possible but engineerable.

Living Systems and Quantum Potentials

It turns out that the living organism utilizes a quantum potential _ a *special scalar potential connecting all its internal atomic nuclei* _ for its volition, deep control, and mind and thought processes and operations. This can even be taken as a flat definition of a living system. A living system utilizes internal WZ structuring of this scalar potential connecting all the atoms (nuclei) of its body mass, for its deepest control processes. Any system not having or doing this is not a living system. This also resolves the age-old philosophical question of how mental *intent* cm cause physical response, but that is beyond the scope of my presentation. It also explains why viruses can be precipitated out of solution as a crystal, and the crystal stored for decades. Then when the crystal is redissolved, the individual viruses separate and resume their "living" state. Suspended animation of the viruses results when their physical matter and its quantum potential remain intact, and the stored WZ structures in the quantum potentials on the atomic nuclei of that matter remain the same.

It further turns out that the species itself has a much weaker (at a deeper level topologically) quantum potential connecting all its members (all the atomic nuclei in their bodies). This corresponds to Sheldrake's morphogenetic field _ that field is just a *species quantum potential.* Jung's collective unconscious, e.g., can be directly expressed in this model scientifically and testably _ but again that is beyond the scope of this presentation.

Newton's Third Law Requires Forces to Occur in Oppositive Pairs

Newton's third law is a sleeping tiger, with surprising implications when awakened and explored. For example, it rigorously requires that forces (including EM forces) must occur in oppositive pairs, This alone falsifies the CEM notion that *oscillating "singular-force"* electric and magnetic waves appear in either a material ether or physical matter. At least two waves must exist, the wave and its oppositive or *antiwave.* Further, the wave and antiwave must be intimately coupled. Heretofore the antiwave has simply been ignored, or when anyone pointed out that it was present in our detectors, it was just considered to be "Newton's third law reaction wave." "Newton's third law" was just mysteriously invoked, as if it had no causative mechanism. Yet in quantum field theory the cause of all forces is the absorption or emission of *virtual particles.* The cause of all mechanical and electromagnetic forces is the absorption or emission of virtual *photons. So* Newton's third law for mechanical and electromagnetic reactions must also be due to the exchange of virtual photons. In other words, there was an extra half of the "something" in the vacuum that interacted with our detectors and gave us the "free electron gas's transverse precession waves. That "extra half' was exactly equal and opposite, and interacted in the atomic nuclei of the conductors and the mass of the instrument to give a set of physical Newtonian recoils. That half is equal and opposite to the half we actually recognized. The point is, equal and opposite forces actually interacted with our instrument. Thus a stress wave interacted with it, not a unitary oscillating wave.

What occurs in vacuum must be a stress wave, not a unitary force field wave. In short, as stated (but not elaborated) by Feynman, it is a *potential* wave, or an oscillation in the potential gradients and magnitudes, not the force fields. Since in modern theory force is an *effect* and not a cause, we interpret and extend Newton's third law to state that the *causes* of all forces must occur in oppositive pairs also. Thus the cause of an EM force field must be the interaction of two scalar potentials _ just as Whittaker's 1904 paper proves.

In quantum field theory any mechanical or EM force is caused on a mass by absorption and emission of virtual photons. Accordingly, let us examine the smallest possible EM or mechanical "force" _ that one caused by the absorption of a single virtual photon. Newton's third law requires that two photons (the causes) must occur, not one. Further, in all cases, the one must be the exact antiparallel to the other. The only thing always meeting that condition for a photon is its exact antiphoton _ its *time-reversed, phase conjugate replica twin.* But a phase conjugate *replica* photon must also superpose spatially with its parent photon _ that's what phase conjugate replicas normally *do,* according to the distortion correction theorem of nonlinear phase conjugate optics. Thus instead of the conventional "single photon" interaction, the actual vacuum entity engaged in the interaction with an atom is a *coupled photon/antiphoton pair.* A coupled photon/antiphoton pair has spin-2, hence is a *graviton.*

Gravitons and Graviton Interaction

So arguably "photon interaction" has been *graviton* interaction all along. In the interaction with an atom, the graviton splits into a photon and an antiphoton. The photon usually interacts with the electron shells, being absorbed by an electron to raise its energy level, then re-emitted and scattered outward from the atom. This absorption and scattering of photons _ *containing their components of energy and time* _ from the electron shells of the atom creates movement of the atom through external observer time. The photon interaction between a mass and its environment creates the forward flow of time for that atom and its seemingly entropic external (photon interaction created) universe.

The antiphoton half of the graviton is time-reversed, which we see as *spatially* reversed. Consequently we see it move in the opposite direction to its externally-directed photon twin. So the antiphoton focuses inward and interacts with the atomic nucleus, providing the Newtonian third law recoil of the atom. The blithe assumption of an "automatic" third law reaction force has always concealed the fact that the so-called *photon* interaction is actually a *graviton* interaction. Further, the positive charge of the atomic nucleus is due to the time reversal interactions of antiphotons with the nucleons, which reverses the charge from that of the negatively charged electrons in the atom's electron shells.

Proof: Excising the Antiphoton Violates Newton's Third Law

This graviton interaction hypothesis is testable. Note that, if the hypothesis is correct, then when an atom or mass emits antiphotons or antiwaves (phase conjugate photons or phase conjugate replica waves), it means that the inward-burrowing antiphotons have been "tricked" into coming out of the atom instead, so they can comprise the time-reversed wave. If they come outward instead of going inward when they split from the parent gravitons, they do not interact with the nuclei to cause their recoil. In that case, there would be no recoil. And indeed, so it *is. In a phase conjugate mirror material, the mirror does not recoil when it emits a phase conjugate replica wave, even a powerful one due to powerful pumping.* This is not true when the mirror material emits a pseudo-conjugate wave. A pseudo-conjugate mirror, e.g., emits an ordinary "time-forward" wave with a distorted wave front, so that it will "retroreflect" in a manner similar to the phase conjugate replica wave. However, the pseudo-conjugate wave is not a true time-reversed wave. Consequently, the mirror will recoil when it emits the pseudo-conjugate wave, because the antiphotons from the graviton interaction still penetrate to the nucleus and interact there, while the time-forward photons constitute the pseudo-conjugate wave actually emitted. This is experimentally verifiable. Among other things, it establishes that there exist differences between the photon and the antiphoton.

Looking at the photon aspects of this, one realizes that one must be very careful in applying the conventional assumption that the photon and the antiphoton are identically the same. Actually they are not the same "internally." The photon can be thought of as carrying or

consisting of (+□E)(+□t), while the antiphoton can be thought of as carrying or consisting of
(-□E)(-□t). Thus both have positive spin, but differ in their internal components. The lack of recoil in a phase conjugate mirror that emits a true time-reversed replica wave is already in the literature, though derived by statistical quantum mechanical arguments. It has also been pointed out by other physicists that all measurement/ detection is actually binary, but that the "internal energy" half is almost always ignored [it's just considered to be "Newton's law", automatically revoked, and swept away in that euphemism.].

Graviton Lattice Structure of the Scalar Potential

When we examine the WZ structure of a scalar potential, in each biwave the wave and antiwave are phase conjugates. It follows that the photons in the wave and the antiphotons in the antiwave are phase conjugates also. This means that, as the two waves flow through each other spatially, photon/antiphoton pairs continually couple and uncouple. Hence gravitons continually couple and uncouple. Further, since the wave pair frequencies are phaselocked between pairs, *the scalar potential is a phaselocked lattice of statistical (continually forming and unforming) gravitons.*

Let us now consider the interactions of an organism with environmental photons as the interactions of the organism with environmental *gravitons*, and specifically with graviton lattices.

Cumulative Buildup in the Quantum Potential of the Antisignal

If the *photon half (of the graviton interactions)* in the electron shells of the living body are considered as environment signals/ interactions, then precise *antisignals* or anti-interactions, constituting perfect negative feedback from all of an organism's physical environmental experiences, are experienced in the organism's atomic nuclei. Note that there they have partially affected the internal structuring of the quantum potentials _ both the personal quantum potential and the species quantum potential. The point is, *cumulative negative feedbacks (exact phase conjugates) for all the environmental experiences and stresses an organism experiences, build in both the personal QP and the species QP of* *that organism.* A part of the entire species' cumulation of species-common antisignals also exists deep in the quantum potential of the living biological system.

So for any protracted stress experienced by the organism, in its personal QP a coherent cumulative negative countermeasure feedback _ one which by its time-reversed nature would reduce that stress _ continually builds. The phase conjugates of the "well-rounded" or highly varying stresses of multiple types will tend to mostly balance or "zero out." However, a sustained stress of one kind will result in coherent cumulation and increase in the "signal-to-noise ratio" of the amplitude of the antisignal for that particular stress, compared to the amplitude of the average of all the antisignals experienced. This is similar to the case where, in a sea of radar noise, a coherent radar signal were continually present and integrating coherently. Continual coherent integration, of course, results in continual increase of the signal-to-noise ratio for the coherent signal, and eventually it emerges from the "sea of noise" as a discernible [in this case, observable and physical] antisignal.

This "cumulative kindling of antisignals" occurs in both the personal QP and the species QP; however, the species QP is many, many orders of magnitude less than the personal QP. Hence much greater time is required for "kindling" of species changes (evolution) than for kindling individual countering adaptations.

Exercising to get in shape is a simple example of physically stressing the body cells so that the high-level feedback mechanism in the MCCS will kindle appropriate antisignals and order the cells to adjust their functioning in a fashion such that the level of performance being called for can be accomplished more easily, thus reducing the stress level. The adaptive mechanism ordering the adjustment of the body cells is the coherent negative feedback in the personal QP, created from the stress signals from the sustained "workout" exercises. This is a fairly rapid, "high-level" mechanism; many other much slower (and some much faster) feedback reaction mechanisms also exist.

Hypoxia As a Result of Interference With Hydrogen Bonding to Hemoglobin

We now point out the recently discovered water H-bonding effect on the hemoglobin in the blood, where the H-bonding activity increases the ability of the hemoglobin to carry oxygen. Some 60 or 70 water molecules surround the hemoglobin molecule, engaging in extensive H-bonding interactions with it, which substantially increases the hemoglobin's purely chemical ability to bind and transport oxygen. Importantly, contamination of this water in the blood fluid drastically affects this H-bonding benefit, and reduces the hemoglobin's ability to carry the extra oxygen. Thus contamination of the internal blood fluid by chemicals, agricultural pesticides, smoke, etc. directly and dramatically lower the oxygen availability to the body's cells, resulting in a continuing "oxygen hungry" state (hypoxia) in most of the body's cells.

It also is now known that H-bond structuring of water is highly dynamic and constantly adaptable, and it possesses a high degree of internal order. A conglomerate of H-bond structures in an area or a volume can be considered an *H-bond potential,* since the gradient oppositions sum to produce stress potentials. Thus in the H-bonding fluid surrounding the hemoglobin molecule, there exists an H-bond scalar potential, and by Whittaker/Ziolkowski (W/Z) decomposition it has a multi-wave structure. Any and all contamination of the fluid _ including by electromagnetic fields and signals, chemicals, etc. _ alters the H-bonding structuring and hence the internal W/Z structure of the H-bond potential. *The end result of adulteration of the H-bonding structure of the blood fluid is a condition of hypoxia induced in the cells of the body due to reduced oxygen transport by the hemoglobin of the red blood cells.*

Any single EM signal is the result of the interference of two scalar EM potentials, as shown by Whittaker. It is the result of the interference of the *internal EM wave structures* of those scalar EM potentials. Multi-signal EM radiation must be regarded as interference of multiple pairs of scalar potentials. These interfering potentials penetrate to the atomic nucleus in the body, and thus interact with the internal personal quantum potential utilized by the body in its deep cellular control. Also this multi-signal EM radiation, *no matter how weak,* directly interacts with the H-bonding structure of the H-bonding blood fluid. Even single-signal EM radiation still forms oppositive pairings with the weak fields already existing in the body, thus also forming W/Z structured potentials. From the interferences in the body of multiple such potentials and their internal structures, there also are created gradient (force field) interactions upon the blood cells and the hemoglobin. In short, low-level background EM radiation can also interact with the H-bonding of the hemoglobin to seriously lower its oxygen transport capability, just as any other contaminant. The denser the external environment, the greater is the interferometry and the interference with the hydrogen-bonding augmentation of oxygen transport. It follows that, when thrust into a truly dense signal environment, some exposed individuals may receive a "cumulative H-bonding interference dosage" that, when added to their existing prior dosage, is sufficient to result in physical symptoms "ordered" into the cells by the antisignals kindled in their quantum potentials. In the recent Gulf War, many Americans were suddenly thrust into one of the densest EM signals environment in history. Shortly after returning from that ultrashort conflict, many of these exposed veterans have experienced delayed health changes presently known as "Gulf War Syndrome." While the military has attempted to portray this syndrome as "stress-induced" emotional' trauma, most of these veterans when tested are found to be emotionally stable. Further, there was much less combat stress on our troops in the Gulf war than in WWII, the Korean War, or the Viet Nam War, as shown by less than 200 combat deaths! Essentially the war was almost a "shooting gallery," and so combat stress is simply not viable as a proposed causative agent for the Gulf War Syndrome.

Chemical, Mechanical, and Electrical Interactions are Electromagnetic Anyway

Indeed, chemistry is largely due to electric charge and charge distribution anyway. So if we view the physical contaminants in the blood view *chemically,* they are caused by electromagnetic means at root basis. Thus even the "chemical" contaminants interact electrically and via potential (multiwave) interferometry with the H-bonding potential. Further, in quantum field theory, all mechanical forces are due to the exchange of virtual photons, and hence also are *electromagnetic at their very basis.* The bottom line is that all chemical, mechanical, and electrical interactions are in fact electromagnetically caused. Further, since both the internal and external structures of the potential are engineerable, the mechanical and electrical forces on the mass particles _ and the virtual photon exchanges causing these forces _ are directly engineerable. *All of these chemical, mechanical, and electrical interactions in the cells can be affect*ed *and even engineered electrically. This is true from the atomic nucleus, to molecules, to material lattices, to human cells, to tissues, and even to the mind and long-term storage templates (internal WZ structured forms in the QP) in the biological organism.*

As cam be seen there are many other weaker, direct interactions of "force-field" radiation; however, here we are interested in the interaction of that radiation with the inner structure of the H-bond potential'., to reduce the oxygen transport capability of the hemoglobin. *In any case, the total sustained interaction of chemical and physical contaminants and EM fields and radiation can result in a sustained oxygen-deprivation (hypoxia) condition for the body cells, even to a dramatic degree.* Further, by graviton interaction, *a sustained, cumulated set of antisignals is also automatically generated in the personal quantum potential as a set of negative feedback signals to take corrective actions to alleviate the oxygen depletion condition.* Note that the cumulating antisignal condition is general and affects the immune system and its cells as well.

The Example of Smoking

Obviously the tars, particles, and nicotine of the smoke inhaled by the smoker dramatically contaminate the fluid in the smoker's lungs, in the very place where the hemoglobin of the red cells is taking on oxygen. Drastic interference with the H-bond stimulus of the hemoglobin occurs. The result is an immediate and dramatic reduction of the oxygen-transport capability of all the hemoglobin in the red cells as they pass through the contaminated lungs and are exposed to fluid contamination. An immediate oxygen-deprivation condition thus is created in the body. Due to the magnitude of the stressing signal, the major portion of the antisignal is also of substantial magnitude _ hence immediate counteraction orders accumulate in the personal QP, specifically in Popp's master cellular control system. So very rapidly the body has negative feedback countersignals from the central cellular control system, ordering the body to take actions to reduce the cellular need for oxygen. The metabolism is lowered, the body relaxes, and the appetite is suppressed; all counters to the cells' hypoxia condition by lowering the cellular requirement for oxygen.

In spite of heroic "high level antisignal" physical cellular compensations to reduce the use of oxygen, however, the condition of cellular oxygen shortage may still continue, in the case of the smoker or substantial environmental contaminants such as secondary smoke. So in addition to the prompt countersignals, additional much-weaker countersignals are also slowly accumulating in the personal quantum potential's central cellular control system.

Cumulative, Deep, Long-Term Countering Signals

We now need one additional bit of information. In addition to its personal quantum potential, a biological organism also is connected to a species quantum potential joining all the members of its species. This is a much weaker quantum potential; nonetheless, potentials superpose, so one small "part" of the personal quantum potential is actually the species quantum potential _ in other words, Sheldrake's morphogenetic field. Deep within its own personal quantum potential the living system also possesses all the cumulatively ordered steps (species antisignals that were implemented) of its species evolution. With very *long coherent cumulation, countersignals can be stimulated in the individual bio-organism's quantum potential _ and in its deep cellular control _ that are counters to the original signals that ordered directed mutation and the primeval evolution of the constituent cells themselves.*

In a sustained cellular hypoxia stress environment, the "do whatever is necessary to reduce oxygen usage" countersignals will continue to cumulate from successively deeper levels in the QP over an appreciable time. These continue to slowly "kindle" after the "first high-level antisignal actions" that cumulated past the "noise" (quantum) threshold reached their limits of physical reactions and are still insufficient to resolve the problem. As the hypoxia stress in the cells continues, then much weaker but coherent countersignals that trigger deeper cellular adaptation actions eventually have time to cumulate past the quantum threshold to the observable state. These long-term cumulated antisignals come from much deeper, even from the species quantum potential itself.

These cumulating deep countersignals are phase conjugates _ *reversals, or dedifferentiation commands* _ of the previous directed mutation signals that ordered evolutionary changes in their predecessor cells in the far distant past. *These long-term antisignals thus contain a signal to reverse the original cumulative countersignals in the cellular species potential that caused the cells early ancestral anaerobic cells on earth to change (differentiate) into largely aerobic cells, after the earth's atmosphere acquired significant amounts of oxygen. In short, a deep signal is slowly* *cumulating that, when it emerges, will order the dedifferentiation of the affected cell back down the evolutionary road toward the anaerobe. The first steps are reductions of centralized cellular control, including growth control.*

In other words, under sustained cellular hypoxia a countermeasures signal to the cells, ordering them to dedifferentiate back toward the anaerobic state, is slowly building in the personal quantum potential from a much weaker, lower level "under the common countersignals noise level" all the while. If significant oxygen-deprivation continues for a sufficiently long time, this deep countersignal eventually emerges in Popp's MCCS system in the personal QP, *ordering the affected cells to dedifferentiate back toward their anaerobic state.* The first step back is to break away from centralized control by the higher organism _ which results in individual "tumerous" or "uncontrolled" cells. *From sustained cellular hypoxia there exists a slowly increasing precancerous state, even years before the outbreak of physical cancer.* This precancerous state has great influence upon the "single cells" of the organism, which includes the cells of the immune system. Thus the precancerous state is characterized by increasing errors in, and slow weakening of, the immune system. Arthritis and similar debilitating immune system disorders appear to be largely the result of this "precancerous" long-term cumulation.

Note that the most stressed cells in the body automatically provided the greatest magnitude of "negative feedback input." Notice also that the feedback is a phase conjugate replica; it therefore "backtracks" its initiating stress input signal. In short, the degree of feedback antisignal received by a cell or group of cells varies according to the degree of stress they experienced. Thus those cells sustaining the longest and greatest stress get this drastic dedifferentiation countersignal first. E.g., this accounts for the (usual) localization of the resultant tumor in the lungs of a smoker, at least initially. It also accounts for the stress-damage mechanism for such disorders as arthritis.

A New Definition of Cancer

In the new model being advanced, *cancer and leukemia are centrally-commanded. final, desperate. "first-step dedifferentiation" adaptive attempts by the stressed. affected cells experiencing sustained oxygen shortage (hypoxia) to reverse their cellular* *evolution and return to the anaerobic stage of their distant ancestry.*

The cause of cancer and leukemia _ and indeed of all diseases _ is *electromagnetic* in nature, and it can be straightforwardly treated and cured *electromagnetically,* if one utilizes the extended W/Z aspects of the higher topology EM actually written by James Clerk Maxwell. This statement is based on experimental proof; it is not conjecture. We discuss that proof below.

As we saw, in general the strength of the cumulating countersignal inversely depends on the distance in the body of the affected cells from the source of greatest contaminant stimulation. As the deeper "dedifferentiation" countersignal reaches the quantum threshold in the most affected area, a small group of localized cells located there take the first step back along the "single-anaerobe to single aerobe to multiple aerobe" evolutionary chain. That first dedifferentiation step breaks the cells away from centralized control of the MCCS in the personal quantum potential. Those dedifferentiated cells become independent cells or a small independent cell-groupings. They constitute a *tumor,* or *leukemia* if occurring in the blood cells. They simply are no longer under the control of the body's MCCS in the personal quantum potential, even though the body's logistical services (nutrients, oxygen, etc.) continue to be furnished to them.

At this point the tumor becomes an independent cellular organism, living in an environment where its body host continues to furnish its food and oxygen, and its host's immune system cells do not recognize the altered cells as foreigners to be attacked and destroyed. Consequently there is no "large organism" central control of the tumor's growth, and the tumor cells divide and multiply apace. This loss of centralized growth control and the resulting unchecked cellular division and replication is in fact recognized by scientists as the major distinguishing characteristic of cancer and leukemia. With central control lost, groups of cancer cells or individual cancer cells may break away and travel to other locations in the body via body circulation systems. This results in metastasis, the spread of the cancer to other sites in the body, where they continue to be recognized as "self" by the immune system cells and continue to be supplied with oxygen and nutrients for continued growth.

The Tumor Has Become a Parasite Organization

Think of it this way: In a living body, each cell is already a single, independent, living creature all its own. It even has its own small "personal quantum potential" _ we have argued that that is an *a priori* condition of being alive. However, each cell in a multicellular organism normally is under a centralized electromagnetic control system (which functions in the organism's higher-level personal quantum potential), so that the organism lives and functions as an overall higher-level unit. If a cell (or group of cells) has separated from this centralized EM control, but is still living and functioning, then obviously the cell is no longer under the whole organism's MCCS and personal quantum potential. However, it still possesses its own control system, and its own personal QP. If the breakaway is by a small group of cells, then they are loosely under a "small group" quantum potential and MCCS as well. That is, they have gone from "large-scale central control" to a "much lower" level of centralized cellular control, accounting for the "tumor as an individual multicellular entity." Nourished by the host body, the new parasitic organism _ the tumor _ grows at an unchecked rate. Again, we argue that *the problem is electromagnetic in nature, and it can be "fixed" electromagnetically.*

The Cumulative Pre-Cancer State

With this picture of the long-term cumulative causative mechanism for cancer and leukemia, a far better picture of the pre-cancer state has emerged. The pre-cancer state is a hidden EM change of state comprised of a *cellular dedifferentiation order,* back down the species' cellular evolution trail, and the magnitude of that change of state is slowly increasing inside the organism's quantum potential. The eventual observable cancer is an actual cellular dedifferentiation due to the localized breaching of the quantum threshold by this cumulating hidden EM dedifferentiation order to move away from centralized control and back toward the anaerobic cellular state.

Becker's Profound Experiments

It has already been experimentally shown that very minute amounts of direct electrical currents, e.g., can cause cellular dedifferentiation and redifferentiation. In breathtaking work of Nobelian quality, Becker has proven that even picoamperes of localized electrical current are sufficient to cause cellular dedifferentiation and redifferentiation, even repetitively. Incredibly, he proved that this was true for red blood cells, which first dedifferentiated to more primitive cells, the redifferentiated to precursors of cartilage cells, then redifferentiated to bone cells in a "bone fracture" area and healed the bone fracture. Since picoamperes can be generated by the cumulative countersignal mechanism (via Whittaker scalar interferometry), directly affecting the MCCS and the cells as well, then the connection between scalar potentials/potential interferometry and *dedifferentiation* mechanisms assumed to be involved in cancer and leukemia essentially follows from interpretation of Becker's pioneering work. To further strengthen the assumption, Hsue has recently (1993) shown that a DC voltage is in fact equivalent to two bidirectional EM traveling waves _ which directly indicates a WZ type implication in Becker's profound work itself. Thus Becker actually utilized a hidden, bidirectional WZ wave structure inside the voltage gradient between his electrodes in his DC current dedifferentiation and redifferentiation of blood cells. He conclusively demonstrated that cellular dedifferentiation and redifferentiation _ both of them *genetic* changes _ can in fact be caused by such an internal biwave EM structure of a steady, persistent scalar potential gradient. Further, he demonstrated that *these El~-induced cellular genetic changes can be self-targeted toward reversal of the specific damage condition, even though several successive genetic changes may be necessary m reach the ultimate cellular genetic form required for healing.*

Pre-Cancer State and Prognosis For Treatment Effectiveness

To summarize, whenever a cancer or leukemia detectably exists, regardless of the cancer site, a pre-cancer state also exists in the remainder of the body, and the immune system is affected generally. Further, this pre-cancer state pre-existed the actual emergence of the tumor itself. The new EM bioeffects model also sheds light on the probable effectiveness of conventional treatment, and probability for a "cure" that lasts for the rest of the patient's life.

If the cumulative countersignal slowly kindling in the remaining pre-cancer state is sufficiently below the quantum threshold, then conventional treatment of the cancer _ such as excision _ can eliminate the tumor, and no other tumors may then develop before the normal physical death of the body, even though slow increase of the pre-cancer state continues. In other words, in that case the cumulative antisignals in the pre-cancer state locations other than the original cancer site never reach the quantum threshold prior to the natural death of the patient. On the other hand, if the cumulating antisignals in the pre-cancer state generally are very close to the quantum threshold, then recurrence of the tumor is highly likely. In the first case the curative prognosis is excellent; in the second case it is poor.

Also, we point out that many present treatments (such as nuclear radiation) themselves cause significant stress on the body and its cells and further deterioration of the immune system. They also generate an additional "antisignals" level in the personal quantum potential, resulting in an actual *increase* in the level of the pre-cancer state in the organism. If the combination of the pre-cancer state at time of treatment, plus the increase in the pre-cancer state due to treatment, is sufficient to breach the quantum level, then that treatment will prove to be of little or no avail to the patient. The tumorous condition will recur, and sometimes massively (the tumor metastasizes), regardless of whether further treatment is given or not. In that case the patient will die, unless somehow the pre-cancer state is lowered, the tumor cells are reverted back to centralized cellular control, and the immune system is restored to effective functioning so that excess cells are eliminated. Presently there is no conventional treatment that is capable of accomplishing the three requirements for a desperately ill patient's recovery from the "terminal" cancer condition.

Seeking the Complete Cancer Cure

From the new EM definition of cancer and leukemia and the new cumulative causative mechanism, one can see just how severely limited are the present medical weapons against this dread disease. It follows that, *if the cause is totally electromagnetic, then a totally effective treatment can only be sought as an electromagnetic therapy. Since the EM cause is in an extended EM domain, then axiomatically a totally effective treatment can only be sought in the same extended EM domain.*

The complete cure for cancer and leukemia, of course, would be to completely neutralize or "zero-out" the patient's cumulative Whittaker/Ziolkowski countersignal buildup in the MCCS/personal

QP. This can be done *prior to* the cumulation reaching the overt physical disease stage, or *after* it has already reached that stage. It can readily be done electromagnetically, using the multi-biwave tailored EM and self-targeting to provide an exact counter-countersignal (or antidote signal) to the cumulation signal itself. *This is a scientific fact and it has been rigorously proven, although the methodology could not heretofore be technically explained and understood.*

Priore's Cure of Terminal Tumors and Other Diseases

Such a total cancer-curative procedure was repeatedly demonstrated in live animal experiments in the late 1960s and early 1970s by Antoine Priore in France, under rigorous scientific protocols and supervision by eminent French scientists [such as Robert Courrier, head of the Biology Section of the French Academy of Science, and *Secretaire Perpetuel* of the Academy at the time]. The advantage of the Priore type approach was that it rapidly reversed the dedifferentiation away from centralized control of the affected (tumor) cells. The tumorous cells simply redifferentiated back to normal cells under centralized control of the MCCS/personal QP. (If too numerous because of the tumor's growth prior to its redifferentiation, normal body mechanisms absorb and dispose of the excess cells). Further, such treatment removed *all the pre-cancerous state from the rest of the body, preventing recurrence or spread of the tumor*. It is the only "total cure" for cancer, including the cumulated pre-cancer state, that has ever been scientifically demonstrated. And lastly, it accomplished these results without severe trauma to the body or further trauma to the immune system. Indeed, the exact opposite was the case.

Working with Priore, the eminent French scientist Pautrizel showed that the Priore treatment restored and stimulated the immune system back to its robust normal functioning, as would be predicted by the present model we are proposing.

Scientists at the Time Did Not Have the Necessary Knowledge for Understanding

It is a great tragedy that the active mechanism of the Priore device was not understood _ even by Priore himself and even by very knowledgeable physicists assigned to the program to try to ascertain the machine's mechanism. The phase conjugate or "time-reversed" EM wave was unknown until it was discovered in the open Soviet literature in 1972. Almost all of our knowledge of such waves dates from that time. In the same year, two Soviet scientists briefed American scientists at Lawrence Livermore National Laboratory on *optical* phase conjugation. Thereafter, some American scientists began intense work on optical phase conjugation.

However, the time-reversed wave is a solution to the wave equation and applies to all kinds of waves, not just EM. Phase conjugation of sound waves, e.g., is readily accomplished. The time-reversed wave solution actually appeared in the scientific literature in 1898 in a paper by Barus, who pointed out that this strange solution "made the wave run backward." But at the time the Priore program's funding was withdrawn by the French government about 1974-75, little or no understanding of the time-reversed EM wave existed as yet in the West, and of course the Whittaker work had always been ignored and was unknown also. *Literally, with the technical tools available to them at the time, the French physicists, biologists, and oncologists had no chance at all of fathoming the causative mechanism in the Priore experiments.*

Nature of the Priore Treatment

Briefly, Priore mixed some 17 frequencies in a rotating plasma in a giant tube. We know today that one function of the kind of plasma he used is to produce a phase conjugate replica wave, for an input wave. Thus Priore unknowingly achieved coupled wave/antiwave pairs in his device. The output of the plasma tube was then coupled to (modulated upon) a "rippling magnetic field" of appreciable strength. The magnetic field guaranteed penetration of the entire body and every cell in it, carrying its modulated Whittaker/Ziolkowski internal potential structure with it. The "ripple" in the magnetic field guaranteed penetration to the atomic nuclei, and interaction with them, via nuclear magnetic resonance. In turn, unknown to Priore or the scientific team, this guaranteed the interaction of the plasma-produced W/Z structure with the internal W/Z structure of the personal QP joining those atomic nuclei. Thus the Priore approach (1) formed a deliberate counter-counter signal W/Z structure; i.e., Priore constructed a *specific electromagnetic* *antidote, (2*) carried that antidote into all the atomic nuclei of the treated body by nuclear magnetic resonance, and (3) caused interaction with and neutralization of the internal W/Z dedifferentiation countersignal structure already present in the personal QP joining all the atomic nuclei of the treated body, *zeroing out or canceling the tumorous and pre-tumorous states existing throughout the body.*

The end results were that (1) the cumulated counter-signal to the tumor cells to dedifferentiate back toward anaerobic cells was removed, (2) the body's own centralized cellular control over the tumor cells was restored, and (3) the entire cumulated pre-cancer counter-signal pattern in the personal quantum potential was removed. In short, the individual organism started over again with a "clean slate" insofar as long-term cumulation of cancer-inducing signals in the personal quantum potential was concerned.

Furious Reaction by Orthodox French Oncologists

The Priore material, device, procedures, and results are all properly documented and presented in the peer-reviewed French medical literature. Priore obtained both French and U.S. patents on the device and on his treatment process. Robert Courrier, head of the Biology Section of the French Academy of Science, personally introduced the astounding Priore team results to the Academy. It caused a furor, and a vicious reaction of most of the orthodox French oncology establishment. Because no one could understand how the mechanism worked, there was loud and raucous insistence that "science must not be done with black boxes!" This overly pious attitude is strange, since the Priore results were multiply replicated and scientifically impeccable, and such things as aspirin were utilized for decades before their active mechanisms were understood. Indeed, in epidemology the use of vaccines and such is directly based on statistically showing that the results are real, even if the active mechanism is not understood.

When the French Government changed to a leftist government in the mid 1970s, the implacable foes of the Priore work prevailed, and the new leftist government withdrew all further funding. Priore later died, and that was the end of that.

Of all areas and treatments known to this researcher, the Priore approach is the only one that has been rigorously and scientifically proven in laboratory animals, was essentially 100% effective, and was performed under proper rigorous scientific protocols. That it has continued to be ignored by the medical and biological communities is a profound tragedy, but one due more to ignorance of the active mechanisms for the treatment than of deliberate intent.

There Is Also Deliberate Suppression

Nevertheless, there is also an element of deliberate suppression involved. Some years ago I was personally involved with a special group in an effort to restore the Priore device, when Priore was still alive. Our group obtained a tentative agreement with both the French Government and with the Priore group. The Priore machines were to be rebuilt in Bordeaux, France under the personal supervision of Priore himself. Some of the scientists who had worked with him were still alive, and would have been involved in the project. Our group had some $16 million support pledged by some wealthy backers to fund the project.

Almost immediately after our group's successful conclusion of the tentative agreements, the lives of all our backers and the lives of their families were threatened. All backing was withdrawn. The leader of our group, a Nashville businessman, came under sustained personal and business attack. He eventually lost almost everything he had, and fled this country for his life. He is still in hiding to this day. Antoine Priore then died and that was that.

The only part of the project that remained was my own grim determination to eventually provide the detailed mechanism by means of which the remarkable Priore therapeutic cures were accomplished. Success has finally been achieved after a decade of unrelenting struggle to completely explain the cause of cancer and the active mechanism by means of which the Priore group obtained such astounding scientific results.

I strongly urge medical science to take a new, hard look_ both theoretically and experimentally _ at the proven anti-cancer results obtained by Antoine Priore and the noted scientists who worked with him. I also strongly point out that new thinking, new theoretical tools, and new experimental instrumentation are needed for that re-examination. In addition I have pointed out the precise nature of the new thinking, tools, and instrumentation required.

What About Other Diseases Such As AIDS?

The question now arises about other diseases, particularly AIDS. Can the expanded Priore methodology provide equally dramatic cures of dread diseases other than cancer and leukemia? Can it conceivably cure AIDS? The answer is a resounding "Yes!"

Almost all disease conditions are electromagnetic in nature, in the sense of the extended EM bioeffects model we have outlined. The basic methodology of forming a counter-countersignal to a specific disease state can be extended to many other diseases, and to AIDS as well. The "self-targeting" effect in the cellular dedifferentiation induced by the extended EM methods results in a countersignal being produced to the *last major genetic change undergone by the diseased cell.* In the case of an HIV-infected cell, its genetics have been changed (differentiated) from normal to infected. In its internal WZ structure, the strongest resultant signal complex is thus the HIV infection differentiation command. *When pumped by the internal bidirectional WZ wave structure of the applied scalar potential, the "cell-as-a-nonlinear-phase-conjugate-mirror-material" generates a precisely tailored anti-AIDS cellular genetic dedifferentiation signal. The cell thus dedifferentiates back to a normal cell with normal genetics.*

In addition to Priore's work and Becker's results, the remaining experimental foundation for our startling statement on extended-EM reversal of AIDS was established decades ago _ as early as the late 1950s _ by the Soviet researcher Vlail Kaznacheyev.

Implications of Kaznacheyev's Experiments

In some 17,000 experiments Kaznacheyev showed that *any* cellular disease or disorder can be transmitted between cell cultures "electromagnetically" in an unknown fashion. The model we have briefly advanced here, if slightly extended to include the concept of the W/Z structure being a *graviton lattice structure, is* fully capable of explaining Kaznacheyev's results, the mechanisms, etc. This EM-transmission of disease effect shown by Kaznacheyev is known as the *cytopathogenic mirror effect,* and it has been replicated by researchers at the University of Sydney in Australia, at the University of Marburg in Germany, and by at least one researcher in the United States.

In short, what Kaznacheyev's research showed is that there exists a specific EM signal pattern of some mysterious, not-understood nature that can induce a specific cellular disease in a group of cells absorbing that signal pattern. If we regard the healthy state of the cell as "condition A" and the specific diseased state as "condition B," then specific EM signal pattern C causes the cell to move from condition A to condition B. It immediately follows that an antisignal to C _ that is, the phase conjugate of C, which is a time-reversed replica of C _ will move the diseased cell from condition B back to condition A, curing the disease. Time reversal of "sickening" is "healing." It follows from Kaznacheyev's work that (1) a specific signal pattern exists as the causative inductive factor for each specific cellular disease, and (2) a specific "antidote" signal pattern exists as the causative curative factor for that specific disease, the antidote signal being merely the time reversal or phase conjugate replica of the cytopathogenic signal. While Kaznacheyev never publicly produced the cytopathogenic mechanism, such a mechanism follows from the WZ extension of EM, and the long-term causative disease-induction mechanism I have advanced.

Creating a Specific "EM Antidote" to a Specific Disease

Consider the cumulative EM causes of changes to a cell, including to its genetics, as a serial chain of signals. Indeed, consider them as the layers of an onion, where the outer layer is the most recent. Additional layers may be added to the onion by "time forward" actions, or "differentiation" actions. If we now wish to "peel" the onion, that too is a successive, serial action, accomplished by "phase conjugate" or "time reversal" operations. These result in serial cellular dedifferentiation actions. By treating the cell and its genetics and internal parts as "highly nonlinear material structures and therefore phase conjugate mirror materials," we can "pump" the cell and its parts by bidirectional EM waves to convert the cell to a pumped phase conjugate mirror (PPCM). By orthodox nonlinear phase conjugate optics theory, with a signal wave present, the PPCM cell will emit a precise phase conjugate replica (PCR) wave. If we pump the cell with a complex of pump biwaves, the cell can and will emit a precise phase conjugate wave complex in response to a complicated signal wave complex input that is present.

For a diseased cell, we regard the disease as a differentiation of the cell, and the primary cause of the differentiation (the EM cytopathogen) as a complex WZ waveset infolded inside the personal quantum potential (in which all the body's cells exist and in whose internal signal dynamics they participate). With the pumped cell as a PPCM, and the EM cytopathogen present as an input signal wave complex to the PPCM, a precise, amplified, "EM antidote" PCR wave-complex is emitted by the parts of the PPCM cell. Each part gets a PCR complex signal order, dedifferentiating that part back the first step. A diseased part steps back to a normal part. A normal part steps back to a normal part. The diseased cell is thus dedifferentiated back to a normal cell with its parts all normal. Because the PCR wave complex is amplified, the dedifferentiation is must faster than was the original dedifferentiation. Thus an HIV-infected cell that has been "dormant" for an extended period can still be dedifferentiated back to a normal cell that is HIV-free.

So a self-targeting counter-countersignal can be automatically "developed" and generated in the body's diseased cells, for each specific cellular disease or disorder condition, or even for a mix of diseases and disorders. This is accomplished by the automatic phase conjugating action of the "cell-as-a-PPCM", when pumped by the hidden EM bidirectional structure of a scalar potential. In practice, Priore did find it necessary to adjust the particular frequency mixes he used for different disease conditions. We hypothesize that this adjustment was necessary to arrive at the proper pump wave complex that would in fact allow the proper PCR wave complex to be emitted for a particular disease type or class. Although photobiologists regularly report mitogenetic radiation emitted by a cell in the optical region, the effects desired in the cells can be produced by a different frequency regime, because of the known phenomena of nonlinear harmonic and subharmonic resonance. Since in a W/Z structure it is the *harmonic intervals and their relative relationships* that are of fundamental importance, the frequency regime of a detected W/Z structure can be shifted either harmonically or subharmonically. Priore, e.g., worked at radar frequencies in the low gigahertz range. For simplicity we may think of the frequency complex as a sort of "musical chord" composed of multiple tones. We may play the same "chord" either on the high scale or a lower scale, and still recognize the tune if the relative frequency interrelationships of the tones are retained.

A Possible Simplification of Priore's Methodology

If we turn away from the classical vector/tensor EM model presently in vogue to a higher topology EM model such as quaternions or Clifford algebra, the extended EM bioeffects model can be mathematized and refined by experiment. For example, Barrett has shown that the nonlinear phase conjugate optics effects can be obtained in ordinary circuits without the use of optical materials, when those circuits are designed and function in accord with a higher topology EM such as quaternions. Thus the circuitry of the EM emission devices themselves can be constructed to perform time-reversal of EM waves, phase conjugate replicas, 4-wave mixing, and pumped phase conjugate mirror effects, without use of normal optical materials or procedures. Priore utilized a plasma in a giant gas-filled tube, in which to mix his 17 frequencies and accomplish (unknown to scientists at the time) phase conjugation. Barrett's work implies that the necessary phase conjugation, and amplification, can be accomplished by purely electromagnetic circuitry, once the functioning of the circuitry is designed and understood in a higher topology algebra such as quaternions or Clifford algebra.

Priore demonstrated cures for diseases other than cancer. Different settings produced cures for sleeping sickness, e.g. Clogging of the arteries was also completely reversed by a variation in the Priore treatment. In addition, Pautrizel working with Priore positively demonstrated the restoration of vigorous, natural functioning to the immune system of the treated animal.

Kaznacheyev's Viral Disease Experiments: Implications for an AIDS Cure

Kaznacheyev has already demonstrated that viral-caused diseases can be induced by purely EM means in cell cultures. What this means is that cellular genetic changes also are electromagnetically induced at root basis. We regard this as a cellular differentiation. But both Becker and Priore have shown that cellular dedifferentiation can also be induced electromagnetically, by the extended scalar EM. It follows that viral-caused diseases _ including AIDS _ can be cured by purely EM means, simply by creating the proper dedifferentiation signal complex in the diseased (differentiated) cell. To determine the proper disease induction (dedifferentiation) signal pattern for the disease, the disease-inducing signal complex must be phase conjugated, and the phase conjugate replica must be amplified. The phase conjugate replica may be stimulated at the proper frequency regime by a signal complex at a much lower frequency regime. Hence the detectable photobiological optical cytopathogenic signal complexes may have their PCR counterparts stimulated by irradiation with a proper signal complex at a lower frequency regime (e.g., millimeter wave band) for use in treatment

In Conclusion

Again we strongly accent that one must take the "musical" approach: A disease pattern or a curative pattern is a complex of special frequencies and their antiwaves, similar to a musical chord. That same chord can be played in a higher or lower key, and the body will still determine the correct relationships by harmonic or subharmonic oscillation. It will still recognize the "melody" and its background chordal accompaniment; although the *individual* frequencies have changed, their *relative* relationships have not changed.

All biochemistry, genetics, and cellular effects are subject to affectation and control by proper manipulation of the W/Z structures inside scalar EM potentials. We have stated that the living organism already utilizes the internal EM structuring for mind, thought, and long-term memory, as well as the master level cellular control system we have accented. For the first time, the "software" and "firmware" of the mind appears to be directly available, something which has never before existed in science. The model advanced in my work is intended to point the way toward such use in medical science on a substantial scale, to achieve healthier, more effective, and far cheaper treatments for many of our desperate diseases that presently require costly, protracted treatments, often harsh and debilitating in and of themselves. We strongly believe that, given the direct attention of the scientific community and proper funding support, near-total, quick, and very economical cures can be developed for such dread diseases as cancer, leukemia, and AIDS. We point out also that the Priore team demonstrated cure of sleeping sickness in lab animals, as well as the direct unclogging of arteries and other blood vessels.

We also strongly accent the "self-targeting" feature when the diseased cell is "pumped" as a phase conjugate mirror material by the internal WZ biwave structure of an artificially-structured scalar EM potential. The cytopathogenic disease-induction signal complex is present in the cell and all its parts. By varying the frequencies in the internal biwave structure of the pumping potential, and hence in the pumping of the cell-as-a-PPCM, the cell is enabled to produce from and into all its parts the proper phase conjugate replica wave complex for its specific cellular disease. *Hence it produces a specific electromagnetic antidote for its own specific disease condition.* We need only adjust the frequency content of the artificial potential until the proper PCR signal complex is produced. Further, that PCR wave complex is amplified because of the pumping. Therefore the "treatment time" can be very short, and need not be anywhere near as long as the time originally required for the cytopathogenic EM signal complex to cumulate.

Today a variety of dread diseases continue to plague humankind. Untold millions of persons are suffering and dying, when the beginning of an effective, quick, inexpensive therapeutic approach capable of essentially 100% cures of cancer, leukemia, and other diseases has been demonstrated more than two decades ago.

With the exposition of the fundamental mechanism for this new therapeutic approach, perhaps the scientific community will return with renewed vigor to develop this promising area and alleviate the death and suffering so widespread today.

LIST OF KEY REFERENCES

Aharonov, Y. and D. Bohm. (i959) "Significance of Electromagnetic Potentials in the Quantum Theory," Physical Review. Second Series, Vol. 115, No. 3, p. 458491.

Aitchison, I.J.R. (1985) "Nothing's plenty: the vacuum in modern field theory." Contemporary Physics, 26(4), p. 333-391.

Amato, Ivan. (1992) "A New Blueprint for Water's Architecture," Science, Vol. 256, Jun. 26, p. 1764.

Barrett, Terrence W. (1990a) "Maxwell's Theory Extended (Part 1)," Annales de la Fondation Louis de Broglie, Vol. 15, No. 2, p. 143-183.

Barrett, Terrence W. (1990b) "Maxwell's Theory Extended (Part 2," Annales de la Fondation Louis de Broglie, Vol. 15, No. 3, p. 253-283.

Barrett, T.W. (1991) "Tesla's Nonlinear Oscillator-Shuttle-Circuit (OSC) Theory," Annales de la Fondation Louis de Broglie, Vol. 16, No. 1, p. 2341.

Barrett, Terrence W. (1992) "Electromagnetic Phenomena Not Explained by Maxwell's Equations," Annales de la Fondation Louis de Broglie [in publication].

Barus, Carl. (1898) "A Curious Inversion in the Wave Mechanism of the Electromagnetic Theory of Light," American Journal of Science, Vol. 5, Fourth Series, p. 343-348.

Bearden, T. E. (1988) "Maxwell's Original Quaternion Theory Was a Unified Field Theory of Electromagnetics and Gravitation," Proceedings of the International Tesla Symposium, Colorado Springs, Colorado.

Bearden, T.E. (1990) A Proposed Mechanism for Noyes' Power Technology, Assoc. Dist. Am. Sci., Huntsville, Alabama.

Bearden, T. E. and Walter Rosenthal. (199la) "On a Testable Unification of Electromagnetics, General Relativity, and Quantum Mechanics," Proceedings of the 26th Intersociety Energy Conversion Engineering Conference (IECEC '91), Boston, Massachusetts, p. 487492. Also distributed over Internet.

Bearden, T. E. (199lb) Gravitobiology, Tesla Book Co., 1417 Second St, Suite H-102, Coronado, California 92118.

Bearden, T. E. (1992a) "A Redefinition of the Energy Ansatz, Leading to a Fundamentally New Class of Nuclear Interactions," Proceedings of the 27th Intersociety Energy Conversion Engineering Conference (IECEC '92), Town & Country Hotel Convention Center, San Diego, California, p. 4.3034.310.

Bearden, T.E. (1992b) An Interpretation of Whittaker's Harmonic Biwave Decomposition of the Scalar Potential. and His Replacement of Orthodox EM Forcefield Waves by Scalar Potential Interferometry, Assoc. Dist. Am. Sci., Huntsville, Alabama. [In publication].

Bearden, T.E. (1992c) EM Cytopathogenic and EM Healing Transmissions, Assoc. Dist. Am. Sci., POB 1472, Huntsville, Alabama 35807.

Bearden, T.E. (1992d) Background for Pursuing Scalar Electromagnetics, Assoc. Dist. Am. Sci., POB 1472, Huntsville, Alabama 35807. Distributed over Internet.

Bearden, T.E. (1992e) On the Unresolved Health Issues in Power Line Radiation and EM Fields and Radiation: A Fundamental New Approach, Assoc. Dist. Am. Sci., POB 1472, Huntsville, Alabama 35807.

Bearden, T.E. (1993a) "The Final Secret of Free Energy," Assoc. Dist. Am. Sci., POB 1472, Huntsville, Alabama 35807. Distributed over Internet.

Bearden, T.E. (1993b) "Mechanism for Long-Term Cumulative Biological Effects of EM Radiation," Presented to the 70th Annual Meeting of the Alabama Academy of Science, University of Alabama at Huntsville, March 25, 1993.

Becker, Robert and Gary Selden. (1985) The Body Electric, William Morrow and Company, New York.

Belyaev, B.N. (1980) "On Random Fluctuations of the Velocity of Light in Vacuum." Izvestiya Vysshikh Uchebnykj Zavendin. Fiyska (11). Nov. 1980. p. 3742. [In Russian]

Besancon, Robert M., Ed. (1974). The Encyclopedia of Physics, 2nd Edn., Van Nostrand and Reinhold, New York, p. 729-731.

Bird, Christopher. (1988) "The Case of Antoine Priore and His Therapeutic Machine: A Scandal in the Politics of Science," Appendix I in T.E. Bearden, AIDS: Biological Warfare, Tesla Book Co., Chula Vista, California.

Bohm, David. (1952) Physical Review, Vol. 85, p. 166, 180.

Bohm, David. (1980) Wholeness and the Implicate Order, Routledge & Kegan Paul, Ltd., London.

Boyer, Timothy H. (1975) "Random electrodynamics: the theory of classical electrodynamics with classical electromagnetic zero-point radiation." Phvsical Review D. Particles and Fields. Series 32. 11(4). February 15, 1975. p. 790-808.

Boyer, Timothy H. (1985) "The Classical Vacuum." Scientific American. Aug. 1985.

Casimir, H.B.G. (1953) "Introductory results in quantum electrodynamics." Physics (19). p. 846-849.

Davies, Paul C.W. (1982) "Something for Nothing." New Scientist. 94(1307). May 27, 1982. p. 580-582.

Dirac, P.A.M. (1930) "A theory of electrons and protons." Proceedings of the Royal Society of London. Series A. 126(801). Jan. 1, 1930. p. 360-365.

Elyntin, P.V. (1988) "The Quantum Chaos Problem," Sov. Phys. Usp., Vol. 31, No. 7, p. 597-622

Feynman, Richard P., Robert B. Leighton and Matthew Sands. (1963) The Feynman Lectures on Physics, Addison-Wesley, New York, Vol. I.

Fulcher, Lewis P., Johann Rafelske, and Abraham Klein. (1979). "The decay of the vacuum." Scientific American. 241(6). December, 1979. p. 150-159.

Graham, G.M. and d.G. OLahoz. (1980) "Observation of static electromagnetic momentum in vacuo." Nature. 285(5761). May 1980. p. 154-5.

Greenberg, Jack S. and Walter Grenier. (1982) "Search for the sparking of the vacuum." Physics Today. August, 1982. p. 24-32.

Hiley, B.J. and F. David Peat. (1987) "General Introduction: The Development of David Bohm's Ideas From the Plasma to the Implicate Order," B.J. Hitey and F. David Peat, Eds. Quantum Implications: Essays in Honour of David Bohm, Routtedge & Kegan Paul, London.

Hsue, C.W. (1993) "A DC Voltage is Equivalent to Two Traveling Waves on a Lossless Nonuniform Transmission Line," IEEE Microwave and Guided Wave Letters, Vol. 3, p. 82-84.

Ignatovich, V.K. (1989) "The Remarkable Capabilities of Recursive Relations," American Journal of Physics, Vol. 57, No. 10, p. 873-878.

Jackiw, R. and J.R. Schrieffer. (1981) "The decay of the vacuum." Nuclear Physics B. Vol. 190. p. 944.

Jackson, J.D. (1975) Classical Electrodynamics, 2nd Edn., John Wiley & Sons, New York.

Kaznacheyev, Vlail and L.P. Mikhailova. (1981) Ultraweak Radiation in Intercellular Interactions, [in Russian], Novosibirsk.

Kaznacheyev, Vlail. (1982) "EIectromagnetic Bioinformation in Intercellular Interactions," Psi Research, p. 47-76.

Kervran, Louis. (1982) Transmutations a Faible Energie (Naturelles et Biologiques), Maloine S.A., Paris.

Kidd, Richard et al. (1989) "Evolution of the Modern Photon," American Journal of Physics Vol. 57, No. 1, p. 27-35.

Lee, T.D. (1981) Particle Physics and Introduction to Field Theory, Harwood, New York Chapter 25: Outlook, "Possibility of Vacuum Engineering," p. 824-828.

Lindsay, Robert Bruce and Henry Margenau. (1963) Foundations of Physics, Dover Publications, New York.

Maxwell, James Clerk. (1873) A Treatise on Electricity and Magnetism, Oxford University Press, Oxford.

Misner, W., K.S. Thorne and J.A. Wheeler. (1973) Gravitation, W. H. Freeman and Co., San Francisco, p. 399; 1191.

Ohno, M. and K. Takagi. (1992) "Schlieren Visualization of Acoustic Phase Conjugate Waves Generated by Nonlinear Electroacoustic Interaction in $LiNbO_3$," Applied Phvsics Letters, Vol. 60, No. 1, p. 29-31.

Pool Robert. (1989) "Quantum Chaos: Enigma Wrapped in a Mystery," Science, Vol. 243, p. 893 - 895.

Popp, Fritz Albert. (1979) "Photon Storage in Biological Systems," in Fritz Albert Popp et al, eds., Electromagnetic Bio-Information: Proceedings of the Symposium. Marburg. Federal Republic of Germany. Sep. 5. 1977; Urban & Schwarzenberg, Baltimore, p. 123-149.

Prange, Richard E. and Peter Strance (1984) "The superconducting vacuum" American Journal of Physics . 52(1). January 984. p. 19 - 21.

Puthoff, Harold E. (1987) "Ground State of Hydrogen as a Zero-Point-Fluctuation-Determined State." Physical Review D. 35(10). May 15, 1987. p. 3266-3269.

Puthoff, Harold E (1989a) "Gravity as a Zero-Point-Fluctuation Force " Physical Review A.39(5). March 1, 1989. p. 2333 - 2342.

Puthoff, Harold E. (1989b) "Source of Vacuum Electromagnetic Zero-Point Energy, Physical Review A.40(9). p. 4857 - 4862.

Puthoff, Harold E. (1991) "The energetic vacuum: implications for energy research." Speculations in Science and Technology. 13(3). p. 247-257.

Rorvik, David M. (1975) "Do the French Have a Cure for Cancer?" Esquire, July 1975, p.110-11, 142-147.

Sachs, Robert G. (1987) The Physics of Time Reversal, University of Chicago Press, Chicago, Illinois.

Sakharov, A.D. (1968) "Vacuum Quantum Fluctuations in Curved Space and the Theory of Gravitation," Sov. Phys. Dokl., Vol. 12, p. 1040.

Schwarzschild, Bertram. (1986) "Currents in Normal-metal Rings Exhibit Aharonov-Bohm Effect," Physics Today, Vol. 39, No. 1, p. 17-20.

Sheldrake, Rupert. (1981) A New Science of Life: The Hypothesis of Formative Causation, Blond & Briggs, Ltd., U.S. reprint, J.P.

Tarcher, Inc., Los Angeles, 1982.

Stoney, G. J. (1897) "XLVIII. On a Supposed Proof of a Theorem in Wave•motion, To the Editors of the Philosophical Magazine," Philosoph. Magazine, 5(43), p. 368-373.

Strand, J. (1986) "Photons in Introductory Quantum Physics," American Journal of Physics. Vol. 54, No. 7, p. 650-652.

Sweet, Floyd and T. E. Bearden. (1991) "Utilizing Scalar Electromagnetics to Tap Vacuum Energy,~ Proceedings of the 26th Intersociety Energy Conversion Engineering Conference (IECEC '91), Boston, Massachusetts, p. 370-375. Distributed over Internet.

Tesla, Nikola. (1932) "Pioneer Radio Engineer Gives Views on Power," New York Herald Tribune, Sep. 11, 1932.

Thompson, Mark. (1989) "Mixed Signals May Have Misguided U.S. Weapons," The Washington Post, Jan. 22, 1989, p. A4.

Wheeler, John archibals. (1968) "Superspace and the nature of quantum geometrodynamics." In: Topics in Non-linear Physics, Edited by Normal J. Zabusky. Springer-Verlag. 1968. p. 642.

Whittaker, E.T. (1903) "On the Partial Differential Equations of Mathematical Physics," Mathematische Annalen, Vol. 57, p. 333-355.

Whittaker, E.T. (1904) "On an Expression of the Electromagnetic Field Due to Electrons by Means of Two Scalar Potential Functions," Proceedings of the London Mathematical Society, Series 2, Vol. 1, p. 367-372.

Ziolkowski, Richard W. (1985) "Exact Solutions of the Wave Equation With Complex Source Locations," Journal of Mathematical Physics, Vol. 26, p. 861.

Ziolkowski, Richard W. (1989a) "Localized Transmission of Wave Energy," Proc. SPIE. Vol. 1061. Microwave and Particle Beam Sources and Directed Energy Concepts. p. 396-397.

Ziolkowski, Richard W. (1989b) "Localized Transmission of Electromagnetic Energy," Physical Review A, Vol. 39, p. 2005.

Ziolkowski, Richard W. (1989c) "Localized Transmission of Wave Energy," Proc. SPIE. Vol. 1061. Microwave and Particle Beam Sources and Directed Energy Concepts. p. 396-397.

Ziolkowski, Richard W. (1992a) "Localized Wave Transmission Physics and Engineering," Physical Review A (in Press).

Ziolkowski, Richard W. (1992c) "Properties of Electromagnetic Beams Generated by Ultra-Wide Bandwidth Pulse-Driven Arrays, IEEE Trans. Ant. Prop. (Submitted).

Ziolkowski, Richard W., Amr M. Shaarawi, and Ioannis M. Besieris. (1989) Nuclear Physics B (Proc. Suppl.), Vol. 6, p. 255-258.

Ziolkowski, R. W. and Lewis, D.K. (1990) "Verification of the Localized Wave Transmission Effect," Journal of Applied Physics, Vol. 68, p. 6083.

Go to Slides

The Tom Bearden Website



CANCER AND THE UNRESOLVED HEALTH ISSUES IN THE BIOLOGICAL EFFECTS OF EM FIELDS AND RADIATIONS

Slide Index

---

1. Title Page
2. Introduction
3. Einstein on Review of Foundation
4. Some Problems in Electromagnetic Foundations
5. Notions in the Concept of the Potential
6. Foundations of Scalar Electromagnetics
7. Inner EM Waves of a Scalar Potential
8. Graviton/Whittaker Lattice Structure of the Scalar Potential
9. Internal Wave Structure of the Scalar Potential
10. Lattice and Nonlattice Gravitons
11. Scalar EM Potential Interferometry
12. Scalar Potential Interferometry
13. Some Problems in Foundations of General Relativity
14. Some Problems in Foundations of Quantum Mechanics
15. Physics Disciplines are Presently Inconsistent
16. The Present EM, GR and QM are Subsets, each omits the Whittaker Internal EM
17. Unified Field Secret: Apply Whittaker Theory
18. Present Definition of "Energy" is Erroneous
19. Some New Definitions
20. Definitions (Continued)
21. Definitions (Continued)
22. Electric Charge, Open System

23. Graviton as a Coupled Photon/Antiphoton Pair
24. Photon Interaction is usually Graviton Interaction
25. Photon Interaction with the Material Atom
26. Photon Phase Conjugate interaction with an Atom
27. Nonlinear Material and Time-Domain Resonance
28. Subharmonic Oscillation
29. The Quantum Potential
30. Quantum Potential Characteristics
31. Self-Targeting creates a Quantum Potential
32. Approach applied to correct present EM bioeffects experimental model
33. Two Stages of Cancer Production
34. More on Promoters
35. EM Biological Effects: Some Changes Demonstrated
36. EM Biological Effects: Inhibition of Melatonin
37. Other EM Biological Effects
38. Becker's Bone-Healing Application of Tiny DC Currents to Fractures
39. Questions on Carcinogens and EM Radiation
40. Direct and Delayed EM Bioeffects
41. Cumulative Feedback Reaction Loop for Induction of Long-Term Effects
42. Species Reactive Adaptation
43. Inheritance of Acquired Traits
44. Anomalous EM Jamming Mechanism
45. Anomalous Depth Penetration
46. The Evolutionary Path of Multicellular Organisms
47. Development of Multi-Celled Organisms
48. Effect of Fluid Contamination on Hemoglobin's Oxygen Transport
49. First Step in Oxygen-Deficiency Dedifferentiation
50. Cumulative Growth of Dedifferentiation Signals
51. Cumulative Emergence of Cancer into the Physical State
52. Precancer State Condition determines Treatment Success
53. Starting From the Scalar EM View: A New Definition of Cancer
54. The Immune System
55. Kaznacheyev's Apparatus
56. Death and Disease Transmission via Graviton Templates
57. Microwave Radiation of U.S. Embassy in Moscow
58. John Hopkins Study of Embassy Microwave Radiation

59. Priore's Laboratory
60. Mechanism of the Priore Therapy
61. Drastically Reduced Deterioration with Priore Therapy
62. The Missing Piece of the Puzzle
63. Summary and Conclusion

Next Slide Return to Cancer Paper



MECHANISM FOR LONG-TERM, CUMULATIVE BIOLOGICAL EFFECTS OF EM FIELDS AND RADIATION

T. E. BEARDEN*

* A.D.A.S.
POB 1472
HUNTSVILLE, AL 35807

Next Slide

Return to Cancer Paper

INTRODUCTION

- **PROBLEMS IN EM BIOEFFECTS DETERMINATION FOR FOUR DECADES**
  - DIFFICULTY IN REPLICATION
  - STUDIES ARE CONTRADICTORY
  - EMOTIONALISM, CONTROVERSY, VESTED INTERESTS
  - LACK FUNDAMENTAL MECHANISMS
- **ESTABLISHES THAT MODEL UTILIZED IS INADEQUATE**
- **WILL CRITIQUE STANDARD MODEL**
- **WILL PROPOSE ALTERATION AND EXTENSION**
- **WILL EXAMINE FUNDAMENTAL CONCEPTS, PER EINSTEIN**

Next Slide
Previous Slide



EINSTEIN ON REVIEWING FOUNDATIONS

"...the scientist makes use of a whole arsenal of concepts which he imbibed practically with his mother's milk; and seldom if ever is he aware of the eternally problematic character of his concepts. He uses this conceptual material, or, speaking more exactly, these conceptual tools of thought, as something obviously, immutably given; something having an objective value of truth which is hardly even, and in any case not seriously, to be doubted. ...in the interests of science it is necessary over and over again to engage in the critique of these fundamental concepts, in order that we may not unconsciously be ruled by them."

Albert Einstein, "Foreword," in Max Jammer, Concepts of Space: The History of the Theories of Space in Physics, Harvard University Press, Cambridge, Massachusetts, 1969, p. xi-xii.

JCS-11A

© 1993 T.E. BEARDEN

Next Slide

Return to Index

Previous Slide

SOME PROBLEMS IN ELECTROMAGNETICS FOUNDATIONS

- **NOTION OF FORCEFIELD**
- **NATURE OF THE VACUUM**
- **NATURE OF ELECTRICAL CHARGE**
- **NOTION OF POTENTIAL**
- **NOTION OF ENERGY**
- **NOTION OF QUANTIZED ELECTRICAL CHARGE**
- **NOTION OF TIME**
- **CONSIDERED MUTUALLY EXCLUSIVE TO GRAVITY**
- **FRAME VERSUS SPACETIME**
- **CLOSED SYSTEM ASSUMPTION**
- **TOPOLOGY AND DIMENSIONALITY OF THE MODEL'S MATHEMATICS**
- **UNDEFINED, OR IMPROPERLY DEFINED, CONCEPTS**

Next Slide

Return to Index

Previous Slide

NOTIONS IN THE CONCEPT OF THE POTENTIAL

- **CONCEPT OF THE POTENTIAL HAS DEVELOPED AS SEVERAL FUNDAMENTAL NOTIONS:**
    - **AS THE "INTERNAL" STORAGE OF ENERGY IN SOME FASHION**
    - **AS A POINT-VALUE FUNCTION IN 3-SPACE**
    - **AS A SCALAR FUNCTION WHOSE SPACE RATE OF CHANGE YIELDS A VECTOR FORCE**
- **THE ENERGY STORAGE MECHANISM IS QUITE UNKNOWN.**
- **NO THOUGHT HAS BEEN GIVEN TO SIMULTANEOUSLY DEFINING IT AS HAVING A HYPERSPATIAL WAVE SET COMPOSITION.**
- **THE THIRD NOTION EFFECTIVELY MAKES ALL FORCES LOCAL *A PRIORI*, AND EXCLUDES ACTION AT A DISTANCE *BY POSTULATION*.**
- **THE THIRD NOTION IS KNOWN TO BE INCORRECT. THE GRADIENT OF A POTENTIAL DOES NOT PRODUCE A FORCE UNTIL A MASS IS PRESENT, TO WHICH THE GRADIENT COUPLES.**

Next Slide
Previous Slide



Founders of Scalar Electromagnetics

- **G.J. Stoney:**

  Decomposed the scalar potential into bidirectional wave pairs.

  "On a supposed proof of a theorem in wave-motion," Phil. Mag., 5(43), 1897, p. 368-373 (and several other papers).

- **E.T. Whittaker:**

  Decomposed the scalar potential into a series of bidirectional EM wave pairs in harmonic series, where the two waves in each pair are conjugates (i.e., a wave/antiwave pair) and are longitudinal waves.

  "On the partial differential equations of mathematical physics," Math. Ann., Vol. 57, 1903, p. 333-355.

  Showed that all classical EM -- including waves -- can be replaced by two interfering scalar potential functions.. (This founded superpotential theory, extended by Nisbet, Bromwich, Debye, McCrea, and others.)

  "On an expression of the electromagnetic field due to electrons by means of two scalar potential functions," Proc. Lond. Math. Soc., Series 2, Vol. 1, 1904, p. 367-372

- **R.W. Ziolkowski:**

  Independently rediscovered the biwave decomposition of the scalar potential and added the product set (in theory enabling modulations and communications) to Stoney and Whittaker's sum set.

  Various papers, 1985 to date.

© T.E. BEARDEN [illegible]

Next Slide

Return to Index

Previous Slide

INNER EM WAVES OF A SCALAR POTENTIAL


EM WAVES
EM WAVES
Ø
Ø₀
AMBIENT VACUUM CONGLOMERATE POTENTIAL
(INTERFERING POTENTIALS)
0

Next Slide
Previous Slide

GRAVITON/WHITTAKER LATTICE STRUCTURE OF THE SCALAR POTENTIAL


• • • ...ETC.
HARMONICS
SUBHARMONICS
F(t)
• • • ...ETC.
F(S)

[Next Slide](#)
[Previous Slide](#)



Infolded longitudinal EM biwave composition of a scalar potential

GALLOPING VELOCITY
Scalar Potential ϕ
© T.E. BEARDEN 1997
...ETC.
✱ ✱ ✱ ...ETC.
V_{avg}
Wavepair #3
HARMONICS
SUBHARMONICS
V_{avg}
Wavepair #2
V_{avg}
Wavepair #1
...ETC.
✱ ✱ ✱ ...ETC.
DISTANCE

The Structure Is:

A harmonic set of longitudinal EM wavepairs. In each wavepair the two waves superpose spatially, but travel in opposite directions. The two are phase conjugates and time-reversed replicas of each other. Thus they comprise a coupled longitudinal wave and antiwave. The photons must be coupled into photon/antiphoton pairs (gravitons) by a strong application of the distortion correction theorem of nonlinear optics. Each wave in the biwave pair is a galloping wave. Each wavepair is a standing electrogravitational wave. In nonlinear optics, such a wavepair is a pump wave which pumps in the time domain.

Note: Think of the oscillations as velocity modulations.

Next Slide

Return to Index

Previous Slide

LATTICE AND NONLATTICE GRAVITONS


F(t)
NOT A LATTICE
LATTICE
MINIMUM LATTICE
F(S)

Next Slide
Previous Slide

SCALAR EM POTENTIAL INTERFEROMETRY


Interference Zone
(gradients)
Trapped EM Energy
Scalar Potential
Beams
Whittaker/Ziolkowski
Transmitters

Next Slide
Previous Slide

SCALAR POTENTIAL INTERFEROMETRY

- Between two scalar potentials, **interferometry** is:
  - Interference of the multi-wave sets in hyperspace.
  - Production of gradients in the 3-space point values
  - In the classical (erroneous) postulation, the creation of forces in 3-space.
    > Force does not exist until the gradient couples to an observable mass.
    > There are no E-fields and B-fields as such in the massless vacuum, but only potential gradients.

Next Slide
Previous Slide

SOME PROBLEMS IN FOUNDATIONS OF GENERAL RELATIVITY

- **EINSTEIN'S FLAT LOCAL SPACETIME POSTULATE**
- **ONLY CONSIDERS THE VERY WEAK G-FORCE AS AN AGENT FOR SPACETIME CURVATURE**
- **EXCLUDES UNION WITH EM FIELD**
- **EXCLUDES ACTION-AT-A-DISTANCE, WHICH IS REQUIRED BY QUANTUM MECHANICS, AND PROVEN**
- **EXCLUDES UNION WITH QUANTUM MECHANICS**
- **SPECIFICALLY EXCLUDES ELECTROGRAVITATION**
- ***IS ESSENTIALLY NOT AN EXPERIMENTAL SCIENCE***

Next Slide

Previous Slide

Return to Index

SOME PROBLEMS IN FOUNDATIONS OF QUANTUM MECHANICS

- **EXCLUDES CHAOS (HIDDEN ORDER), AND THIS IS KNOWN TO BE IN ERROR**
- **ORDERED MACROREALITY CANNOT EMERGE FROM INTEGRATING DISORDERED (RANDOM) CHANGES**
- **USES RANDOM-VARIABLE STATISTICS FROM GIBBS THERMODYNAMICS**
- **NOTION THAT QUANTUM CHANGE - HENCE ROOTS OF PHYSICAL REALITY - CANNOT BE ENGINEERED**
- **REQUIRES ACTION-AT-A-DISTANCE EFFECTS**
- **CONTRADICTS CLASSICAL MECHANICS, GENERAL RELATIVITY, AND CLASSICAL ELECTROMAGNETICS**

Next Slide

Return to Index

Previous Slide

PHYSICS DISCIPLINES ARE PRESENTLY INCONSISTENT

	GENERAL RELATIVITY (GR)	
QUANTUM MECHANICS (QM)	**???**	**CLASSICAL EM THEORY**
	MIND & SUBTLE ENERGY	

Next Slide

Return to Index

Previous Slide

THE PRESENT EM, GR AND QM ARE SUBSETS, EACH OMITS THE WHITTAKER INTERNAL EM.

A	B
PRESENT EM	EXCLUDED EM
(EXTERNALIZED ASPECTS OF POTENTIALS)	(INTERNALIZED ASPECTS OF POTENTIALS)

A	B
PRESENT GR	EXCLUDED GR
(DISTANT SPACETIME CURVATURE) (LOCAL ACTION)	(LOCAL SPACETIME CURVATURE) (ACTION AT A DISTANCE)

A	B
PRESENT QM	EXCLUDED QM
(EXTERNALIZED STRUCTURE OF POTENTIALS)	(INTERNALIZED STRUCTURE OF POTENTIALS) (CHAOS)

Next Slide

Return to Index

Previous Slide

UNIFIED FIELD SECRET: APPLY WHITAKER THEORY

	GENERAL RELATIVITY (GR)	
QUANTUM MECHANICS (QM)	APPLY WHITTAKER THEORY	CLASSICAL EM THEORY
	MIND & SUBTLE ENERGY	

Next Slide

Return to Index

Previous Slide

PRESENT DEFINITION OF "ENERGY" IS ERRONEOUS

- **PRESENT: "ENERGY IS THE CAPACITY TO DO WORK."**
- **ACTUALLY, WORK IS THE SCATTERING (DISSIPATION) OF ENERGY.**
- **THE PRESENT DEFINITION STATES THAT "ENERGY IS THE CAPACITY TO DO SCATTERING OF ENERGY."**
- **ENERGY CAN BE SCATTERED, YIELDING WORK. BUT THE CAPACITY TO PERFORM THAT SCATTERING IS NOT ENERGY! (E.G., IT MAY BE RESISTANCE.)**
- **COMPARE TO: "A FISHHOOK IS THE CAPACITY TO CATCH FISH."**
- **ACTUALLY, A FISHHOOK IS A BENT WIRE WITH A BARB. IT *HAS* THE CAPACITY TO CATCH FISH (GIVEN OTHER CONDITIONS). BUT THE CAPACITY TO CATCH FISH IS NOT WHAT IT *IS*.**

Next Slide

Return to Index

Previous Slide

SOME NEW DEFINITIONS

- **QUANTUM MECHANICAL VACUUM -** an intense flux of virtual particles, filling the "emptiness" of spacetime/vacuum.
- **ENERGY -** any ordering, either static or dynamic, in the virtual particle flux of vacuum.
- **EM ENERGY -** any ordering, either static or dynamic, in the virtual photon flux of vacuum
- **WORK -** the local scattering of energy; the local disordering of the order in the VPF.

Next Slide

Return to Index

Previous Slide

DEFINITIONS (CONTINUED)

- **POTENTIAL** - any ordering, either static or dynamic or combination, in the VPF of vacuum
  - same definition as energy
  - must have internal order, hence structure
- **SCALAR POTENTIAL** - any static ordering in the VPF of vacuum, with respect of the external observer
- **VECTOR POTENTIAL** - any dynamic (non-stationary) ordering in the VPF of vacuum.
  - must have internal order, hence structure

Next Slide

Return to Index

Previous Slide

DEFINITIONS (CONTINUED)

- **Electrostatic Scalar Potential** - any static (stationary) ordering in the virtual photon flux of vacuum.
  - Whittaker decomposed the ESP into bidirectional EM wavepairs in a harmonic structure.
  - We interpret the wavepair set as existing in hyperspace (in hyper-3-space).

- Thus the ESP is a 3-space point function, and a hyper-3-space vector function, in 7-space.

- In Hyper-3-space, the ESP is an ordering established throughout the universe.

Next Slide

Return to Index

Previous Slide

ELECTRIC CHARGE, OPEN SYSTEM

- The ***electric charge*** of a charged particle is due to a violent exchange of virtual photons between the charged particle and the local vacuum VPF
  - photons continually absorbed from the vacuum
  - photons continually radiated back to the vacuum
  - this exchange flux is what electric charge ***IS***.
- In the nucleus, everything is changing into everything, so to speak. It is a furious, ***VPF-driven*** cauldron.
- the nucleus is an open, driven system, normally in equilibrium with respect to VPF input and output.

Next Slide

Return to Index

Previous Slide



The Graviton Is a Coupled Photon/Antiphoton Pair
(Both photon and antiphoton are longitudinal)

In physics, the primary units selected are arbitrary. Everything can be expressed, e.g., in terms of time alone. Thus so can photon spin.

IS THIS A SPIN 2 ENTITY?
It is, in the time domain.

LONGITUDINAL PHOTON
LONGITUDINAL ANTIPHOTON
ACTION
VACUUM ENGINE
REACTION

© 1993, 1996 T.E. BEARDEN

Next Slide

Return to Index

Previous Slide

PHOTON INTERACTION IS USUALLY GRAVITON INTERACTION

- Graviton interaction is a photon/antiphoton interaction
- Photon interacts with electron shells
  - Scattering produces the entropic (forward) flow of time
  - Produces electron translation in our detectors
- Antiphoton interacts with nucleus primarily
  - produces nuclear recoil
  - produces Newton's third law of motion

Next Slide

Return to Index

Previous Slide



PHOTON INTERACTION WITH THE MATERIAL ATOM

MECHANISM FOR NEWTON'S THIRD LAW

GRAVITON
PHOTON
ANTIPHOTON
e-
e-
PHOTON
ANTIPHOTON
NUCLEUS
RECOILS

Next Slide

Return to Index

Previous Slide

PHOTON PHASE CONJUGATE INTERACTION WITH AN ATOM


DISPLACEMENT OF NEWTON'S THIRD LAW REACTION FORCE
ANTIPHOTON
e⁻
PHOTON
GRAVITON
e⁻
PHOTON
ANTIPHOTON
NUCLEUS DOES NOT RECOIL

PHASE CONJUGATE INTERACTION

NOTE: Graviton waves are bidirectional phase waves of photon/antiphoton coupling and uncoupling in the vacuum.

Next Slide

Return to Index

Previous Slide

NONLINEAR MATERIAL AND TIME-DOMAIN RESONANCE


TIME FORWARD
(ENTROPIC)
NONLINEAR
MEDIUM
ETC.
F3
F2
F1
ETC.
F3
F2
F1
TIME-REVERSED
(NEGENTROPIC)

GROUPS OF RESONATORS ENTRAINED IN TIME AND SPACE
(MAY ENABLE SELF-OSCILLATION)

Next Slide

Return to Index

Previous Slide

SUBHARMONIC OSCILLATION

- **CAN TRANSLATE FROM ONE FREQUENCY REGIME TO ANOTHER.**
- **E.G., OPTICAL TO MICROWAVE**
  - **HOWEVER, MUST PRESERVE HARMONICS**
  - **ONE HARMONIC INTERVAL IS ESSENTIAL**
- **KAZNACHEYEV'S CYTOPATHOGENIC EFFECT:**
  - **QUARTZ PASSES ONE HARMONIC INTERVAL.**
  - **WINDOW GLASS DOES NOT.**
- **WHITTAKER'S INFOLDED EM STRUCTURE**
- **DEVYATKOV'S INFORMATION CONTENT OF THE FIELD.**
- **MULTIPLE PHASELOCKED WOODPECKER PULSE REPETITION RATES.**

Next Slide

Return to Index

Previous Slide



N's are nodes participating in the quantum potential.

The quantum potential exists as narrow, laser-like beams between participating nodes, even when the nodes are widely separated. The beam space is multiply-connected; transmission is instantaneous.

[Next Slide](#)

[Return to Index](#)

[Previous Slide](#)

QUANTUM POTENTIAL CHARACTERISTICS

- **NO POINT SOURCE**
- **QP BETWEEN TWO PARTICLES**
  - INTERACTION DOES NOT VANISH AS SPATIAL SEPARATION BECOMES VERY LARGE

  - INSTANTANEOUS CONNECTION



- **DEPENDS ON QUANTUM STATE OF SYSTEM AS A WHOLE**

- **SYSTEM PARTS CAN BE GREATLY SEPARATED**

Next Slide

Return to Index

Previous Slide



Self-Targeting in Inner EM Channel Can Produce a Quantum Potential

Once QP is established, energy transmission is direct and instantaneous. Energy input to one single participant will simultaneously appear in all other participants, the amount depending on their fractions of participation with the input station.

NARROWING OF INTERACTING POTENTIALS INTO LASER-LIKE BEAMS, BETWEEN TWO PUMPED SOURCES. NOW ONLY LONGITUDINAL WAVES CONNECT THE LINKED OBJECTS.

SELF-TARGETING EFFECT AMONG ALL PAIRS OF INTERACTING PUMPED SOURCES

© 1989, 1995, 1996 T.E. BEARDEN

Next Slide

Return to Index

Previous Slide

Corrections For the Present EM Bioeffects Model



17. DEVELOP NEW TYPES OF INSTRUMENTS

18. CORRECT EM THEORY MODEL, INSTRUMENTATION AND RECORDING, AND IMCS

A

START

PRESENT INADEQUATE EM BIOEFFECTS MODEL

OVERALL STIMULUS/RESPONSE MODEL

2. EXPERIMENT OR GROUP OF EXPERIMENTS

1. EM STIMULUS/ RESPONSE MODEL

6. EM THEORY TO BE APPLIED

8. EM THEORY CORRECT

STOP

3. INSTRUMENTATION AND RECORDING

4. INTERPRETATIVE MODEL AND COMPARATIVE STANDARD

5. INTERPRETED RESULTS

7. ARE RESULTS CONSISTENT?

YES

NO

9. EM THEORY INCORRECT

IMCS/EM ASSUMPTIONS:

1. PRESENT EM MODEL CORRECT AND COMPLETE
2. DOSAGE/RESPONSE SYNONYMOUS WITH STIMULUS/RESPONSE

10. FIND ERRORS IN EM THEORY POSTULATES

16. CORRECT/EXTEND EM AND SHOW UNIFIED FIELD AND MIND/VOLITION

14. ADD WHITTAKER EM STRUCTURE OF POTENTIALS THEORY

13. FORCEFIELDS NOT PRIMARY. POTENTIALS ARE, HAVE HIDDEN EM WAVE STRUCTURE.

11. CHARGE DISCRETE, NOT QUANTIZED. VIRTUAL FLUX CAN BE STRUCTURED, FOR VACUUM ENGINES.

15. ADD TO GENERAL

19. SEPARATE

12. RETAIN ZERO VECTOR

Next Slide

Return to Index

Previous Slide



ADD TO GENERAL
RELATIVITY AND
QUANTUM
MECHANICS

CHARGE Q
INTO ITS
COUPLED
COMPONENTS

RETAIN ZERO VECTOR
RESULTANT SUMMATIONS
OF EM FORCE VECTOR
COMPONENTS AS
VACUUM ENGINES

JCS-44

ⓒ 1991, 1993, 1995 T.E. BEARDEN



TWO STAGES OF CANCER PRODUCTION

- INITIATION
  - DNA IN CELL NUCLEUS IS DAMAGED
  - CELL MUTATES
  - INITIATOR: AN AGENT THAT DAMAGES THE DNA IN A CELL, CAUSING IT TO MUTATE
  - THE CELL IS NEOPLASTIC, OR PRECANCEROUS
- PROMOTION
  - PROMOTER: AN AGENT THAT CAUSES A CANCER CELL TO DEVELOP INTO A TUMOR
  - EXPOSURE TO THE PROMOTOR CAUSES THE CANCER CELL TO UNDERGO UNCHECKED CELL DIVISION
- EXACT CAUSE OF UNCHECKED CELL GROWTH IS NOT CLEARLY UNDERSTOOD
  - DNA BLUEPRINT ON TRANSMITTER RNA CHANGES?
  - NORMAL TRANSMISSION OF MESSAGES FROM THE CANCER CELL TO ITS DAUGHTER CELLS CHANGES?

Next Slide

Return to Index

Previous Slide



MORE ON PROMOTERS

- KNOWN TO ATTACK THE CYTOTOXIC LYMPHOCYTES IN THE IMMUNE SYSTEM THAT WOULD NORMALLY KILL TUMOR CELLS
  - INHIBITS CYTOTOXITY OF THESE LYMPHOCYTES
  - PREVENTS THEM FROM DOING THEIR JOB
- KNOWN TO CAUSE CHANGES IN SIGNALS OR MESSAGES BEING CARRIED ACROSS THE CELL MEMBRANE
  - NOTE: ELECTRICAL POTENTIALS ON THE MEMBRANE
  - ELECTRIC FIELDS ARE CHANGES IN ELECTRICAL STRESSES
  - STRESS IS KNOWN TO BE A FACTOR IN CANCER
- WITHOUT EXPOSURE TO A PROMOTER, CANCER WILL NOT PROCEED
- LATENCY PERIOD: TIME BETWEEN INITIATION AND PROMOTION STAGES OF CANCER DEVELOPMENT

Next Slide

Return to Index

Previous Slide



EM BIOLOGICAL EFFECTS: SOME CHANGES DEMONSTRATED

- CHANGES AT THE CELL MEMBRANE
  - PARTICULARLY CALCIUM ION FLUX INCREASE
  - PARTICULARLY AC AND DC FIELDS COMBINED
- RATES OF DNA AND RNA SYNTHESIS
- CHROMOSOMAL ABERRATIONS AND BREAKS
- RNA TRANSCRIPTION
- ENHANCED GENE EXPRESSION
- EFFECTS ON CELL PROLIFERATION, BUT DEPENDS ON MITOTIC STATUS OF CELL POPULATION DURING EXPOSURE. DEPENDS ON
  - EM FIELD INTENSITY
  - EXPOSURE DURATION
  - CELLULAR FACTORS
  - EXTRACELLULAR FACTORS
- INCREASED CALCIUM FLUX IN BRAIN CELLS (IN VIVO STUDIES OF LIVE ANIMALS)

Next Slide

Return to Index

Previous Slide



EM BIOLOGICAL EFFECTS: INHIBITION OF MELATONIN

- MELATONIN PRODUCED BY PINEAL GLAND AT NIGHT
  - REGULATES CIRCADIAN RHYTHMS
  - HAS ONCOSTATIC PROPERTIES (INHIBITS TUMORS)
  - USED IN CHEMOTHERAPY, PARTICULARLY AGAINST BREAST CANCER AND PROSTATE CANCER
  - CANCER PATIENTS USUALLY HAVE REDUCED LEVELS
  - REDUCED LEVELS CONTRIBUTE TO DEPRESSION, SEVERE MOOD CHANGES, PSYCHIATRIC DISORDERS
- PRODUCTION OF MELATONIN CONTROLLED BY AMOUNT OF LIGHT DETECTED BY THE RETINA
  - BLIND WOMEN HAVE GREATLY INCREASED LEVELS
  - BLIND WOMEN HAVE MUCH LESS BREAST CANCER
  - HIGHEST CANCER INCIDENCE IS BREAST CANCER
    - INCREASING IN INCIDENCE
    - INCREASING IN MORTALITY
- EMF EXPOSURE INHIBITS NIGHTTIME PRODUCTION OF MELATONIN. SUCH SUPPRESSION OF MELATONIN IS IMPLICATED IN ETIOLOGY OF BREAST, PROSTATE, OVARIAN, AND MELANOMA CANCER

Next Slide

Return to Index

Previous Slide

OTHER EM BIOLOGICAL EFFECTS

- MAGNETIC FIELD INDUCING OF BIRTH DEFECTS IN CHICKS
- MORE CONTROVERSIAL EPIDEMIOLOGY STUDIES FOUND
  CORRELATIONS BETWEEN EMF AND
  - BRAIN TUMORS
  - MISCARRIAGES IN PREGNANT FEMALES USING VDTS
  - BIRTH DEFECTS
  - INCIDENCE OF LEUKEMIA IN CHILDREN
- BECKER SHOWED THAT PICOAMPERES OF CURRENT USED
  IN EM-ASSISTED BONE HEALING CAUSED PROFOUND CELLULAR CHANGES
  - RED BLOOD CELLS DEDIFFERENTIATED
  - SHED HEMOGLOBIN AND GREW NUCLEI
  - REDIFFERENTIATED INTO CARTILAGE-HEALING CELLS
  - REDIFFERENTIATED INTO BONE-HEALING CELLS
  - THEN HEALED THE FRACTURES

Next Slide

Return to Index

Previous Slide



Becker's dc treatment of bone fractures

Application of tiny DC currents to heal difficult bone fractures. Only picoamperes are utilized. Pulsed DC current or pulsed magnetic fields may also be utilized.

(+)
ELECTRODE
DC POWER SOURCE
(-)
ELECTRODE
BONE
BONE
FRACTURE SITE
BECKER'S BONE FRACTURE SETUP (DIAGRAMMATIC)

RED BLOOD CELL DEDIFFERENTIATES

Shucks hemoglobin coat
Grows nucleus

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes cartilage

NEW CELL REDIFFERENTIATES

Turns into type of cell that makes bone
Deposits in fracture site, healing the fracture

Proves that cells can be time-reversed (phase conjugated) (dedifferentiated) or time-forwarded (redifferentiated) by application of very weak electromagnetic signals, when those signals contain longitudinal bidirectional EM "pump wave" wavepairs, which cause the cell and its parts to create precise vacuum antiengines.

© 1993, 1998 T.E. BEARDEN

Next Slide

Return to Index

Previous Slide



QUESTIONS ON CARCINOGENS AND EM RADIATION

- UNRESOLVED QUESTIONS ON EM RADIATION
  - DOSAGES
  - ACTIVE MECHANISMS
  - REPLICATION DIFFICULTIES
  - MEASUREMENT DIFFICULTIES
  - WHERE, WHEN, HOW ILL EFFECTS OCCUR
- SIMILAR QUESTIONS EXIST ABOUT EVERY CARCINOGEN
- SCIENCE REALLY DOES NOT UNDERSTAND THE MECHANISMS OF A SINGLE CHRONIC DISEASE, INCLUDING CANCER
  - FACTORS SUCH AS MIND, STRESS, SPONTANEOUS REMISSION, PLACEBO EFFECTS, AND COMBINATIONS OF FACTORS ARE PARTICULARLY TROUBLESOME
  - GENERATION OF THE PLACEBO EFFECT BY THE REGENERATION & RECOVERY SYSTEM IS UNRECOGNIZED

© 1994, 1995 T.E. Bearden

Next Slide

Return to Index

Previous Slide



BODY EFFECTS

PHOTON DIRECT

GRAVITON

ANTIPHOTON INDIRECT

QP CUMULATION (LONG-TERM)

[Next Slide](#)

[Return to Index](#)

[Previous Slide](#)

CUMULATIVE FEEDBACK REACTION LOOP FOR INDUCTION OF LONG-TERM EFFECTS


STIMULUS
PHOTON
ANTIPHOTON
ANTI-STIMULUS
GRAVITON
(PERSONAL QUANTUM POTENTIAL)
TISSUES
LOCALIZED MOLECULAR BONDS AND MATERIAL LATTICES IN CELLS
C
LONG-TERM CUMULATION
PHASE CONJUGATES
COUNTER EFFECTS
POPP'S MASTER CELLULAR CONTROL SYSTEM
A
ELECTRON SHELLS
B
ATOMIC NUCLEI
NUCLEAR POTENTIALS
QUANTUM THRESHOLD
C
M(T)
DISPLACEMENT FROM STIMULUS SITE
(PERSONAL UNCONSCIOUS MIND)

Next Slide

Return to Index

Previous Slide



Species Reactive Adaptation

(Directed Evolution)

ONE INDIVIDUAL

LOCALIZED MOLECULAR BONDS AND MATERIAL LATTICES

ELECTRON SHELLS

ATOMIC NUCLEI

NUCLEAR POTENTIALS

(SPECIES QUANTUM POTENTIAL)

(JUNG'S COLLECTIVE UNCONSCIOUS MIND)

A

PHASE CONJUGATES

LONG-TERM SPECIES CUMULATION

COUNTER EFFECTS

SHELDRAKE'S MORPHOGENETIC FIELD (SPECIES QUANTUM POTENTIAL)

PHASE CONJUGATES

COUNTER EFFECTS

A

LIVING INDIVIDUAL SPECIES MEMBERS

DEATH CAUSES

DEAD MEMBERS

[Next Slide](#)

[Return to Index](#)

[Previous Slide](#)



INHERITANCE OF ACQUIRED TRAITS

- Evolutionary biology assumes mutations are random events
  - Causes of heritable differences separated from their consequences for survival and reproduction
  - Likelihood of any particular mutational event assumed independent of its particular value to the organism
  - Natural selection then assumed to increase the frequency of advantageous alleles
- Evidence for directed, non-random mutation
  - Removing cell-wall from bacterium: acquired nakedness is then inherited
  - Protozoan Oxytricha double monsters (siamese twins)
    - ▲ Bisected lengthwise, normal reproduction
    - ▲ Bisected crosswise, double monsters reproduce
  - Virus Sigma and fruit fly sensitivity to CO2
  - Specific sets of genes either eliminated or added to an organism by organelles, plasmids, bacteria or other agents
- Genes are acquired vertically from ancestors and horizontally from a variety of other factors

Next Slide

Return to Index

Previous Slide



Deep penetration of weak signals in a dense signal environment, by nonlinear retroreflection

Nonlinearity
Internal potentials and weak signal emissions occur from these internal operating EM components
Cross-Section of Body
Body Surface
Enlargement of nonlinearity area
Pumped Retroreflection Phase Conjugate Mirror (PCM) Effect due to multi-photon interactions
Dense Signal Environment (May be very weak signals)
PCM
PCR*
PCR*
Amplified Partial Cancellation of Body's Internal Signals by addition of phase conjugate replicas

In a dense signals environment, probability of simultaneous signals interacting increases. This increases the probability of deep penetration by amplified phase conjugate reflections of weak internally generated signals from the interior, impinging upon the pumped (stressed) nonlinear surface areas where the simultaneous exterior interactions occur.

* Phase conjugate replica

Next Slide

Return to Index

Previous Slide

ANOMALOUS DEPTH PENETRATION


ϕ_1
ϕ_2
ϕ
ϕ_3
t
ϕ_3
ϕ_4
ϕ
ϕ_5
t
ϕ_5
ϕ_6
ϕ
ϕ_7
t
ϕ_7
ϕ_8
ϕ
ϕ_9
t
ETC.

Iterative scalar interferometry

Next Slide

Return to Index

Previous Slide



THE EVOLUTIONARY PATH OF MULTICELLULAR ORGANISMS

ESSENTIALLY ANAEROBIC ATMOSPHERE

CHANGE OF ATMOSPHERE TO AEROBIC (INCLUDES OXYGEN)

BIOGENESIS

SINGLE CELL ANAEROBIC

OBLIGATORY ANAEROBES SINGLE CELL SHIELDED FROM OXYGEN

FACULTATIVE ANAEROBES (SINGLE CELL BOTH AEROBIC AND ANAEROBIC)

EVOLVE TO

SINGLE CELL AEROBIC*

EVOLVE TO

MULTICELL AEROBIC* (INCLUDES MAN)

CENTRAL CONTROL

SINGLE CELL COMPONENTS

- IMMUNE SYSTEM
- RED CELLS
- WHITE CELLS
- KILLER CELLS
- ETC.

MULTICELL COMPONENTS

- TISSUES
- MUSCLES
- BONES
- ORGANS
- SKIN
- STRUCTURES

* NOTE: LIMITED ANAEROBIC RESPIRATION STILL TAKES PLACE IN HIGHER AEROBIC LIFE FORMS, INCLUDING MAN.

EVOLUTIONARY TIME

CANCR-01

c 1993 T.E. Bearden

Next Slide

Return to Index

Previous Slide

DEVELOPMENT OF MULTI-CELLED ORGANISMS



Many-celled organisms (eukaryotes)

Free oxygen into the atmosphere O_2

O_2

Simple photo-synthesizers (prokaryotes)

Adaptation

TEMPLATES

Cumulative WZ reaction structures in species quantum potentials

Natural Selection

Proteins, nucleic acids, simple self-reproducing heterotrophs

Adaptation

TEMPLATES

Cumulative WZ reaction structures in species quantum potentials

ENERGY SOURCES

UV Light

Heat

Lightning

Chemical reactions

TEMPLATES FROM THE UNIVERSE

Whittaker-Ziolkowski structures inside scalar potentials

Scalar interfer-ometry

NH_3 (ammonia)

H_2O

H_2 (hydrogen)

CH_4 (methane)

Primitive Atmosphere

Chaotic chemical reactions

Simple organic compounds: sugars, amino acids, glycerin, purines, pyrimidines

Scalar interfer-ometry

TEMPLATES

Whittaker-Ziolkowski structures inside scalar potentials

CANCR-07

Next Slide

Return to Index

Previous Slide



EFFECT OF FLUID CONTAMINATION ON HEMOGLOBIN'S OXYGEN TRANSPORT

RED BLOOD CELLS

AIR

Severely reduced
oxygen transport

Severe pollution

(Such as
cigarette smoke)

RED BLOOD CELLS

LUNG
SACS

BODY

ATMOSPHERE

CANCR-09

© 1993 T.E. Bearden

Next Slide

Return to Index

Previous Slide



FIRST STEP IN SELF-PROMOTION OF CANCER DUE TO HYPOXIA

*** NOTE: LIMITED ANAEROBIC RESPIRATION STILL TAKES PLACE IN HIGHER AEROBIC LIFE FORMS, INCLUDING MAN.**

SINGLE CELL
ANAEROBIC

SINGLE CELL
AEROBIC*

MULTICELL
AEROBIC*
(INCLUDES MAN)

CENTRAL CONTROL

OXYGEN-RICH

TIME-FORWARD
PATH AS IT
DEVELOPED

TIME-REVERSED
PATH FOR SUSTAINED
OXYGEN DEFICIENCY

SINGLE CELL
AEROBIC*

FIRST STEP IN OXYGEN-DEFICIENCY
DEDIFFERENTIATION

CANCR-08

© 1993 T.E. Bearden

[Next Slide](#)

[Return to Index](#)

[Previous Slide](#)

CUMULATIVE GROWTH OF DEDIFFERENTIATION SIGNALS


MAGNITUDE OF STRESS EFFECT
Observable state
BODY
Local cellular Dedifferentiation (Cancerous cells formed)
T_4
Quantum Level
Virtual state
Pre-cancerous State
T_3
T_2
T_1
SEPARATION FROM CONTACT POINT
Point of contact (or most stressed location)

Next Slide

Return to Index

Previous Slide

CUMULATIVE EMERGENCE OF CANCER INTO THE PHYSICAL STATE


MAGNITUDE OF SUSCEPTIBILITY
Observable state
BODY
(Cancerous cells)
T_4
Cells and tissues
Cancer Threshold
Cancer Susceptibility
Virtual state
T_3
Master cellular control system (MCCS)
T_2
T_1
SEPARATION FROM LUNG TISSUES
Lung Tissue

Next Slide

Return to Index

Previous Slide

PRECANCER STATE CONDITION DETERMINES TREATMENT SUCCESS


MAGNITUDE OF SUSCEPTIBILITY
BODY
Cells and tissues
PROGNOSIS:
Cancer Threshold
Very Poor
Poor
Fair
Good
TREATMENT
Excision or Destruction
(With scarring, physical damage, etc.)
Total Susceptibility
SEPARATION FROM CONTACT POINT
Normal (or most stressed location)

Next Slide

Return to Index

Previous Slide

Starting From the Scalar EM View:
A NEW DEFINITION OF CANCER

- CANCER AND LEUKEMIA ARE:

  Centrally-commanded, final, desperate, "first-step dedifferenetiation" adaptive attempts by the stressed affected cells experiencing sustained oxygen shortage, to reverse their cellular evolution and return to the anaerobic stage of their distant ancestry.

- THE CAUSE IS LONG-TERM CUMULATIVE, AND ELECTROMAGNETIC IN NATURE.

- A TOTAL CURE CAN BE ACHIEVED ELECTRO-
  MAGNETICALLY, AS WAS DEMONSTRATED.

Next Slide

Return to Index

Previous Slide



THE IMMUNE SYSTEM

BONE MARROW

Lymphocytes

Special Defense

Intestinal tissue, liver, etc.

Thymus

Complement system

General Defense

Feeding cells

Monocytes

B-lymphocytes

suppressor cells

plasma cells

antibodies

T-lymphocytes

killer cells

helper cells

complement factors

granulocytes

macrophage

bacterium (foreign invader)

CANCR-18

©1993 T.E. Bearden

Next Slide

Return to Index

Previous Slide



Kaznacheyev's Two-Chamber Apparatus

(Induction of effects of diseases, physical damage, nuclear radiation, toxins)

TWO OPEN-MOUTH BOTTLES
LOCKING BOLTS
LOCKING BOLTS
STOPPER
STOPPER
TRANSPARENT WINDOW PANE (THIN) (GLASS OR QUARTZ)
© T.E. BEARDEN 1987, 1991
DISASSEMBLED

A cell culture is divided into two parts. One is placed on each side, in the jars which are environmentally shielded except for light. The left cell culture is deliberately damaged. After a time delay, the cells on the right also start dying with the same damage. The effect is replicated in the right cells through a thin quartz window, but not through window glass.

Next Slide

Return to Index

Previous Slide



Kaznacheyev's Cytopathogenic Mirror Effect

Disease vacuum engines transported by photons and waves

GRAVITON LATTICE TEMPLATES
SICKEN OR KILL
CELL CULTURE SAMPLE #1
QUARTZ CONTAINER
ENVIRONMENTAL SHIELDING
CELL CULTURE SAMPLE #2
QUARTZ CONTAINER
THIN WINDOW
GLASS: No Effect
QUARTZ: Delayed Effect
Divided bottle set-up

© T.E. BEARDEN 1977, 1987

Note: Minimum lattice is one harmonic interval: IR to UV is such a minimum G-lattice.

Distant induction of cellular death and diseases, by special EM means. Coupled photon-antiphoton pairs (gravitons) in a structured harmonic lattice ordering constitute the disease or disorder template.

Next Slide

Return to Index

Previous Slide



MICROWAVE RADIATION OF U.S. EMBASSY IN MOSCOW

Former U.S. Embassy in Moscow.

BACKGROUND

- Began in latter 1950s
- Discovered on VP Nixon's trip
- Initially thought to be *nuclear* radiation (Discovered w/Geiger counter?)
- High level target -- U.S. Ambassador
- Guarantees personal attention of:
  - U.S. Ambassador to USSR
  - U.S. President
  - NSA, CIA, DIA, NSC, etc.
  - Top consulting scientists
  - Leading U.S. scientific institutions
- Two U.S. Ambassadors died, another sickened
- Anomalous health changes in personnel, only in zero-field (zero pot'l gradient) areas!
- Four U.S. Presidents requested Soviets cease
  - Cut from 18 watts/sq cm to 2
  - Then again increased
- No one could understand what was going on
- Aluminum screens were placed over windows
- Moscow was declared a hazardous duty zone

Selected clipart © by Lotus SmartPics™

© 1995, 1996 T.E. BEARDEN

[Next Slide]

[Return to Index]

[Previous Slide]

JOHN HOPKINS STUDY OF EMBASSY MICROWAVE RADIATION

- **EXCELLENT SCIENTIFIC TEAM**

  - PERFORMED CLASSICAL EM INVESTIGATION

  - CAREFULLY ESTABLISHED THE FORCE FIELD PATTERNS

  - NO HEALTH CHANGES OCCURRED IN PERSONNEL WHERE THE FORCE FIELDS WERE PRESENT (NONZERO)

  - ALL HEALTH CHANGES OCCURRED IN PERSONNEL WHERE THE FORCE FIELDS WERE ZERO (ABSENT)
- **ASSUMED THAT ALL EM ACTION IS DUE ONLY TO FORCE FIELDS**

  - CONCLUDED THAT MICROWAVE RADIATION COULD NOT HAVE CAUSED THE HEALTH CHANGES
- **CONCLUSION WAS IN SERIOUS ERROR**
  - CORRECT CONCLUSION: HEALTH CHANGES WERE TOTALLY CORRELATED TO ABSENCE OF FORCE FIELDS

  *** TOTALLY CORRELATED TO PRESENCE OF GRADIENT-FREE POTENTIALS, OR NOT TO RADIATION AT ALL**

  *** IF NOT TO RADIATION AT ALL, THEN HEALTH CHANGES WOULD HAVE ALSO OCCURRED WHERE FORCE FIELDS WERE PRESENT**
- **THEREFORE THE HEALTH CHANGES WERE TOTALLY CORRELATED TO THE GRADIENT-FREE POTENTIALS, AND TO THE EM RADIATION**

Next Slide

Return to Index

Previous Slide



Priore's laboratory device for treating small animals

GIANT COIL WITH PLASMA MIXING TUBE INSIDE
SMALL ANIMAL HOLDER

Next Slide

Return to Index

Previous Slide

MECHANISM OF THE PRIORE THERAPY

- **PRODUCED A DETERMINISTIC WZ STRUCTURED SCALAR POTENTIAL**
  - **17 FREQUENCIES MIXED IN A ROTATING PLASMA**
  - **PHASE CONJUGATES ADDED BY THE PLASMA**
  - **MODULATED ONTO A RIPPLING MAGNETIC FIELD WHICH CARRIED IT TO ATOMIC NUCLEI**
  - **INTERACTED DIRECTLY WITH PERSONAL QUANTUM POTENTIAL**
- **NEGATED THE LONG-TERM CUMULATIVE CELLULAR DEDIFFERENTIATION ORDER GENERATED BY LONG-TERM HYPOXIA. TUMOR CELLS REVERTED TO NORMAL CONTROL**
- **SCRUBBED OUT THE CUMULATED PRECANCEROUS STATE**
- **RESTORED THE IMMUNE SYSTEM TO HIGH FUNCTIONING**
- **NO EXCESSIVE TRAUMA TO TREATED ANIMAL**

Next Slide

Return to Index

Previous Slide



DRASTICALLY REDUCED CUMULATIVE DETERIORATION AFTER PRIORE THERAPY

NOTE: Priore therapy treats entire body.

BODY

Cells and tissues

Cancer Threshold

Body action point

MAGNITUDE OF SUSCEPTIBILITY

Deterioration after conventional treatment

Deterioration before treatment

Δ (conventional therapy)

Dramatically reduced deterioration after Priore therapy.

Separation from body action point

CONVENTIONAL THERAPY:

Scarring, physical damage, etc. Immune system deterioration.

PRIORE THERAPY:

No scarring or physical damage, etc. Immune system restored.

JCS-50

© 1993, 1996 T.E. BEARDEN

Next Slide

Return to Index

Previous Slide

THE MISSING PIECE OF THE PUZZLE



MAXWELL'S QUATERNION ELECTROMAGNETICS

Gravitobiological
Effects of EM Fields
and Radiation

EM captured by
Heaviside/Gibbs
Vector Theory

EM omitted by
Heaviside/Gibbs
Vector Theory

Present EM Theory

External
(Translation)
Electromagnetics

Assumes no internal
vector structure of
the scalar potential

Missing Electrogravitation

Internal
(Nontranslation)
Electromagnetics

Is the internal vector
structure of the
scalar potential

Next Slide

Return to Index

Previous Slide

SUMMARY AND CONCLUSION

- **RECOMMEND SERIOUS EXAMINATION OF THE NEW APPROACH**
- **RECOMMEND REVIVAL OF PRIORE-TYPE RESEARCH ON**
  AN URGENT BASIS
- **CAN BE EXTENDED TO OTHER DISEASES**

  - AIDS
  - ARTERIOSCLEROSIS
  - SLEEPING SICKNESS
  - ETC.
- **A NEW THERAPEUTIC PARADIGM OF GREATLY INCREASED**
  SCOPE AND EFFECTIVENESS MAY BE POSSIBLE
- **IN ADDITION, DRASTIC REDUCTION IN MEDICAL COSTS**
  COULD POTENTIALLY RESULT

Return to Index

Previous Slide



Any EM Field or Wave Pattern Is Produced by interference of Two Scalar Potential Functions *(E.T. Whittaker, 1904)*

(Use of Hidden Information Content of the Field)

(Can Provide Action-at-a-Distance)

Note:
Whittaker's 1904 paper initiated the entire field of superpotential theory.

Interference Zone (Potential gradients)
Normal EM Energy:
May be positive, or negative, or fixed

Hidden Bidirectional EM energy flow

Hidden Bidirectional EM energy flow

Scalar Potential Beams

© T.E. BEARDEN 1997

Whittaker/Ziolkowski Transmitter Arrays

(8 to 20 harmonic wavepairs each)

Next Slide

Return to Index

Previous Slide

MECHANISM FOR LONG-TERM, CUMULATIVE BIOLOGICAL EFFECTS OF EM FIELDS AND RADIATION

T. E. BEARDEN*

* A.D.A.S.
POB 1472
HUNTSVILLE, AL 35807

ENERGY FROM THE VACUUM
www.cheniere.org

Support Free Energy and purchase the bumper sticker

The New Tesla Electromagnetics and the Secrets of Electrical Free Energy

By T.E. Bearden
© 1984

Table of Contents

Foreword

Comments on the New Tesla Electromagnetics:
Part I: Discrepancies in the Present EM Theory
by T. E. Bearden

Comments on the New Tesla Electromagnetics:
Part II: The Secret of Electrical Free Energy
by T. E. Bearden

Overture to a New Age Technology
by Dr. Rolf Schaffranke

REVIEW AND OUTLOOK - The Development of Post-Relativistic Concepts in Physics and Advanced Technology Abroad
by Dr. Rolf Schaffrancke

COMMENTS ON THE NEW TESLA ELECTROMAGNETICS

Part I: Discrepancies in Present EM Theory

© T. E. Bearden 1982

There are at least twenty-two major discrepancies presently existing in conventional electromagnetics theory. This paper presents a summary of those flaws, and is a further commentary on my discussion of scalar longitudinal Tesla waves in a previous paper, "Solutions to Tesla's Secrets and the Soviet Tesla Weapons," Tesla Book Company, 1981 and 1982.

I particularly wish to express my deep appreciation to two of my friends and colleagues who at this time, I believe, wish to remain anonymous. One of the two is an experimental genius who can produce items on the bench that do not work by orthodox theory. The second is a master of materials science and electromagnetics theory. I thank them both for their exceptional contributions and stimuli regarding potential shortcomings in present electromagnetics theory, and their forbearance with the many discussions we have held on this and related subjects.

It goes without saying that any errors in this paper are strictly my own, and not the fault of either of my distinguished colleagues.

(1) In present electromagnetics theory, charge and charged mass are falsely made identical. Actually, on a charged particle, the "charge" is the flux of virtual particles on the "bare particle" of observable mass. The charged particle is thus a "system" of true massless charge coupled to a bare chargeless mass. The observable "mass" is static, three-dimensional, and totally spatial. "Charge" is dynamic, four-dimensional or more, virtual and spatiotemporal. Further, the charge and observable mass can be decoupled, contrary to present theory. Decoupled charge -- that is, the absence of mass -- is simply what we presently refer to as "vacuum." Vacuum, spacetime, and massless charge are all identical. Rigorously, we should utilize any of these three as an "ether," as suggested for vacuum by Einstein himself (see

Max Born, Einstein's Theory of Relativity, Revised Edition, Dover Publications, New York, 1965, p. 224). And all three of them are identically anenergy -- not energy, but more fundamental components of energy.

(2) Electrostatic potential is regarded as a purely 3-dimensional spatial stress. Instead, it is the intensity of a many-dimensional (at least four-dimensional) virtual flux and a stress on all four dimensions of spacetime. This is easily seen, once one recognizes that spacetime is identically massless charge. (It is not "filled" with charge; rather, it is charge!) Just as, in a gas under pressure, the accumulation of additional gas further stresses the gas, the accumulation of charge (spacetime) stresses charge (spacetime). Further, if freed from its attachment to mass , charge can flow exclusively in time, exclusively in space, or in any combination of the two. Tesla waves -- which are scalar waves in pure massless charge flux itself -- thus can exhibit extraordinary characteristics that ordinary vector waves do not possess. And Tesla waves have extra dimensional degrees of freedom in which to move, as compared to vector waves. Indeed, one way to visualize a Tesla scalar wave is to regard it as a pure oscillation of time itself.

(3) Voltage and potential are often confused in the electrostatic case, or at least thought of as "composed of the same thing." For that reason, voltage is regarded as "potential drop". This also is not true. Rigorously, the potential is the intensity of the virtual particle flux at a single point -- whether or not there is any mass at the point -- and both the pressure and the point itself are spatiotemporal (4-dimensional), not spatial (3-dimensional) as presently assumed. Voltage represents the spatial intersection of the difference in the potential between two separated spatial points, and always implies at least a miniscule flow of mass current (that is what makes it spatial!). "Voltage" is spatial and depends upon the presence of observable mass flow, while scalar electrostatic potential is spatiotemporal and depends upon the absence of observable mass flow. The two are not even of the same dimensionality.

(4) The charge of vacuum spacetime is assumed to be zero, when in fact it is a very high value. Vacuum has no mass, but it has great massless charge and virtual particle charge flux. For proof that a charged vacuum is the seat of something in motion, see G.M. Graham and D.G. Lahoz, "Observation of static electromagnetic angular momentum in vacuo," Nature, Vol. 285, 15 .May 1980, pp. 154-155. In fact, vacuum IS charge, identically, and it is also "spacetime" and at least four-dimensional.

(5) Contrary to its present usage, zero is dimensional and relative in its context. A three-dimensional spatial hole, for example, exists in time. If we model time as a dimension, then the spatial hole has one dimension in 4-space. So a spatial absence is a spatiotemporal presence. In the vacuum 4-space, a spatial nothing is still a something. The "virtual" concept and the mathematical concept of a derivative are simply two present ways of unconsciously addressing this fundamental problem of the dimensional relativity of zero.

(6) The concepts of "space" and "time" imply that spacetime (vacuum) has been separated into two parts. We can only think of a space as "continuing to exist in time " To separate vacuum spacetime into two pieces, an operation is continually required. The operator that accomplishes this splitting operation is the photon interaction, the interaction of vector electromagnetic energy or waves with mass. I have already strongly pointed out this effect and presented a "raindrop model" of first-order physical change itself in my book, The Excalibur Briefing, Strawberry Hill Press, San Francisco, 1980, pp. 128-130.

(7) "Vector magnetic potential" is assumed to be always an aspect of (and connected to) the magnetic field. In fact it is a separate, fundamental field of nature and it can be entirely disconnected from the magnetic field. See Richard P. Feynman et al, The Feynman Lectures on Physics, Addison-Wesley Publishing Co., New York, 1964, Vol. II, pp. 15-8 to 15-14. Curiously, this fact has been proven for years' yet it has been almost completely ignored in the West. The "Vx" operator, when applied to the A-field, makes B-field. If the Vx operator is not applied, the "freed" A-field possesses much-expanded characteristics from those presently allowed in the "bound" theory. Specifically, it becomes a scalar or "shadow vector" field; it is not a normal vector field. (note: for V read inverted capital Delta)

(8) The speed of light in vacuum is assumed to be a fundamental constant of nature. Instead it is a function of the intensity of the massless charge flux (that is, of the magnitude of the electrostatic potential) of the vacuum in which it moves. (Indeed, since vacuum and massless charge are one and the same, one may say that the speed of light is a function of the intensity of the spatiotemporal vacuum!). The higher the flux intensity (charge) of the vacuum, the faster the speed of light in it. This is an observed fact and already shown by hardcore measurements. For example, distinct differences actually exist in the speed of light in vacuo, when measured on the surface of the earth as compared to measurements in space away from planetary masses. In a vacuum on the surface of the earth, light moves significantly faster. For a discussion and the statistics, see B. N. Belyaev, "On Random Fluctuations of the Velocity of Light in Vacuum," Soviet Physics

Journal, No. 11, Nov. 1980, pp. 37-42 (original in Russian; translation by Plenum Publishing Corporation.) The Russians have used this knowledge for over two decades in their strategic psychotronics (energetics) program; yet hardly a single U.S. scientist is aware of the measured variation of c in vacuo. In fact, most Western scientists simply cannot believe it when it is pointed out to them!

(9) Energy is considered fundamental and equivalent to work. In fact, energy arises from vector processes, and it can be disassembled into more fundamental (anenergy) scalar components, since the vectors can. These scalar components individually can be moved to a distant location without expending work, since one is not moving force vectors. There the scalar components can be joined and reassembled into vectors to provide "free energy" appearing at a distance, with no loss in between the initial and distant points. For proof that a vector field can be replaced by (and considered to be composed of) two scalar fields, see E. T. Whittaker, Proceedings of the London Mathematical Society, Volume 1, 1903, p. 367. By extension, any vector wave can be replaced by two coupled scalar waves.

(10) The classical Poynting vector predicts no longitudinal wave of energy from a time-varying, electrically charged source, In fact, an exact solution of the problem does allow this longitudinal wave. See T. D. Keech and J. F. Corum, "A New Derivation for the Field of a Time-Varying Charge in Einstein's Theory," International Journal of Theoretical Physics, Vol. 20, No, 1, 1981, pp. 63-68 for the proof.

(11) The present concepts of vector and scalar are severely limited, and do not permit the explicit consideration of the internal, finer-grained structures of a vector or a scalar. That is, a fundamental problem exists with the basic assumptions in the vector mathematics itself. The "space" of a vector field, for example, does not have inter-nested sublevels (subspaces) containing finer "shadow vectors" or "virtual vectors," Yet particle physics has already discovered that electrical reality is built that way. Thus one should actually use a "hypernumber" theory after the manner of Charles Musés. A scalar is filled with (and composed of) nested levels of other "spaces" containing vectors, where these sum to "zero" in the ordinary observable frame without an observable vector resultant. In Musés' mathematics, for example, zero has real roots. Real physical devices can be -- and have been -constructed in accordance with Muses' theory. For an introduction to Musés' profound hypernumbers approach, see Charles Musés' foreword to Jerome Rothstein, Communication Organization and Science, The Falcon's Wing Press, Indian Hills, Colorado, 1958. See also Charles Musés, "Applied Hypernumbers: Computational Concepts," Applied Mathematics and

Computation, Vol. 3, 1976. See also Charles Musés, "Hypernumbers II," Applied Mathematics and Computation, January 1978.

(12) With the expanded Tesla electromagnetics, a new conservation of energy law is required. Let us recapitulate for a moment. The oldest law called for the conservation of mass. The present law calls for the conservation of "mass and energy", but not each separately. If mass is regarded as simply another aspect of energy, then the present law calls for the conservation of energy. However, this assumes that energy is a basic, fundamental concept. Since the energy concept is tied to work and the movement of vector forces, it implicitly assumes "vector movement" to be a "most fundamental" and irreducible concept. But as we pointed out, Whittaker showed that vectors can always be further broken down into more fundamental coupled scalar components. Further, Tesla discovered that these "coupled components" of "energy" can be individually separated, transmitted, processed, rejoined, etc. This directly implies that energy per se need not be conserved. The new law therefore calls for the conservation of anenergy, the components of energy. These components may be coupled into energy, and the energy may be further compacted into mass. It is the sum total of the (anenergy) components -- coupled and uncoupled -- that is conserved, not the matter or the energy per se. Further, this conservation of anenergy is not spatial; rather, it is spatiotemporal in a spacetime of at least four or more dimensions.

(13) Relativity is presently regarded as a theory or statement about fundamental physical reality. In fact, it is only a statement about FIRST ORDER reality -- the reality that emerges from the vector interaction of electromagnetic energy with matter. When we break down the vectors into scalars (shadow vectors or hypervectors), we immediately enter a vastly different, far more fundamental reality. In this reality superluminal velocity, multiple universes, travel back and forth in time, higher dimensions, variation of all "fundamental constants" of nature, materialization and dematerialization, and violation of the "conservation of energy" are all involved. Even our present Aristotlean logic -- fitted to the photon interaction by vector light as the fundamental observation mechanism -- is incapable of describing or modeling this more fundamental reality. Using scalar waves and scalar interactions as much subtler, far less limited observation/detection mechanisms, we must have a new "superrelativity" to describe the expanded electromagnetic reality uncovered by Nikola Tesla.

(14) "Charge" is assumed to be quantized, in addition to always occurring with -- and locked to -- mass. Indeed, charge is not necessarily quantized just as it is not necessarily locked to mass.

Ehrenhaft discovered and reported fractional charges for years, in the 30's and 40's, and was ignored. See P.A.11. Dirac, "Development of the Physicist's Conception of Nature," Symposium on the Development of the Physicist's Conception of Nature, ed. Jagdish Merha, D. Reidel, Boston, 1973, pp. 12-14 for a presentation of some of Ehrenhaft's results. Within the last few years Stanford University· researchers also have positively demonstrated the existence of "fractional charge." For a layman's description of their work, see "A Spector Haunting Physics," Science News, Vol. 119, January 31, 1981, pp. 68-69. Indeed, Dirac in his referenced article points out that Millikan himself -- in his original oildrop experiments -- reported one measurement of fractional charge, but discounted it as probably due to error.

(15) Presently, things are always regarded as traveling through normal space. Thus we use or model only the most elementary type of motion -- that performed by vector electromagnetic energy. We do not allow for things to "travel inside the vector flow itself." Yet, actually, there is a second, more subtle flow inside the first, and a third, even more subtle flow inside the second, and so on. We may operate inside, onto, into, and out of energy itself -- and any anenergy component of energy. There are hypervectors and hyperscalars unlimited, within the ordinary vectors and scalars we already know. Further, these "internal flows" can be engineered and utilized, allowing physical reality itself to be directly engineered, almost without limits.

(16) We always assume everything exists in time. Actually, nothing presently measured exists in time, because the physical detection/ measurement process of our present instruments destroys time, ripping it off and tossing it away -- and thereby "collapsing the wave function." Present scientific methodology thus is seriously flawed. It does not yield fundamental (spacetime) truth, but only a partial (spatial) truth. This in turn leads to great scientific oversights. For example, mass does not exist in time, but mass x time (masstime) does. A fundamental constant does not exist in time, but the "constant x time" does. Energy does not exist in time, but energy x time (action) does. Even space itself does not exist in time -- spacetime does. We are almost always one dimension short in every observable we model. Yet we persist in thinking spatially, and we have developed 1nstruments that detect and measure spatially only. Such instruments can never measure and detect the phenomenology of the nested substrata of time. By using scalar technology, however, less limited instruments can indeed be constructed -and they have been. With such new instruments, the phenomenology of the new electromagnetics can be explored and an engineering technology developed.

(17) We do not recognize the connection between nested levels of virtual state (particle physics) and orthogonally rotated frames (hyperspaces). Actually the two are identical, as I showed in the appendix to my book, The Excalibur Briefing, Strawberry Hill Press, San Francisco, 1980, pp. 233-235. A virtual particle in the laboratory frame is an observable particle in a hyperspatial frame rotated more than one orthogonal turn away. This of course implies that the hyperspatial velocity of all virtual particles is greater than the speed of light. The particle physicist is already deeply involved in hyperspaces and hyperspatial charge fluxes without realizing it. In other words, he is using tachyons (particles that move faster than light) without realizing it.

(18) Presently quantum mechanics rigorously states that time is not an observable, and therefore it cannot be measured or detected. According to this assumption, one must always infer time from spatial measurements, because all detections and measurements are spatial. With this assumption, our scientists prejudice themselves against even looking for finer, subquantal measurement methodologies and instrumentation. Actually this present limitation is a result of the type of electromagnetics we presently know, where all instruments (the "measurers") have been interacted with by vector electromagnetic energy (light). Every mass that has temperature (and all masses do!) is continually absorbing and emitting photons, and in the process they are continually connecting to time and disconnecting from time. If time is continually being carried away from the detector itself by its emitted photons, then the detector cannot hold and "detect" that which it has just lost. With Tesla electromagnetics, however, the fundamental limitation of our present instruments need not apply. With finer instruments, we can show there are an infinite number of levels to "time", and it is only the "quantum level time" which is continually being lost by vector light (photon) interaction. By using subquantal scalar waves, instruments can move to deeper levels of time -- in which case the upper levels of time ARE measureable and detectable, in contradistinction to the present assumptions.

(19) In the present physics, time is modeled as, and considered to be, a continuous dimension such as length. This is only a gross approximation. Indeed, time is not like continuous "dimension," but more like a series of "stitches," each of which is individually made and then ripped out before the next stitch appears. "Vector light" photons interact one at a time, and it is this interaction with mass that creates quantum change itself. The absorption of a photon -- which is energy x time -- by a spatial mass converts it to masstime: the time was added by the photon. The emission of a photon tears away the time, leaving behind again a spatial mass. It is not accidental, then, that time flows at

the speed of light, for it is light which contains and carries time. It is also not accidental that the photon IS the individual quantum. Since all our instruments presently are continually absorbing and emitting photons, they are all "quantized," and they accordingly "quantize" their detections. This is true because all detection is totally internal to the detector, and the instruments detect only their own internal changes. Since these detections are on a totally granular quantized background, the detections themselves are quantized. The Minkowski model is fundamentally erroneous in its modeling of time, and for that reason relativity and quantum mechanics continue to resist all attempts to successfully combine them, quantum field theory notwithstanding.

(20) Presently, gravitational field and electrical field are considered mutually exclusive. Actually this is also untrue. In 1974, for example, Santilly proved that electrical field and gravitational field indeed are not mutually exclusive In that case, one is left with two possibilities: (a) they are totally the same thing, or (b) they are partially the same thing. For the proof, see R. M. Santilli, "Partons and Gravitation: Some Puzzling Questions," Annals of Physics, Vol. 83, No. 1, March 1974. With the new Tesla electromagnetics, pure scalar waves in time itself can be produced electrically, and electrostatics (when the charge has been separated from the mass) becomes a "magic" tool capable of directly affecting and altering anything that exists in time--including gravitational field. Antigravity and the inertial drive are immediate and direct consequences of the new electromagnetics.

(21) Presently, mind is considered metaphysical, not a part of physics, an not affected by physical means. Literally, the prevailing belief of Western scientists is that man is a mechanical robot -- even though relativity depends entirely upon the idea of the "observer." Western science today thus has essentially become dogmatic, and in this respect borders on a religion. Since this "religion," so to speak, is now fairly well entrenched in its power in the state, Western science is turning itself into an oligarchy. But mind occupies time, and when we measure and affect time we can directly measure and affect mind itself. In the new electromagnetics, then, man regains his dignity and his humanity by restoring the reality of mind and thought to science. In my book, The Excalibur Briefing, I have already pointed out the reality of mind and a simplified way in which it can be modeled to the first order. With scalar wave instruments, the reality of mind and thought can be measured in the laboratory, and parapsychology becomes a working, engineering, scientific discipline.

(22) Multiple-valued basic dimensional functions are either not permitted or severely discouraged in the present theory For one thing, integrals of multiple valued derivative functions have the annoying

habit of "blowing up" and yielding erroneous answers, or none at all. And we certainly do not allow multiple types of time! This leads to the absurdity of the present interpretation of relativity which permits only a single observer (and a single observation) at a time. So if one believes as "absurd" a thing as the fact that more than one person can observe an apple at the same time, the present physics fails. However, the acceptance of such a simple proposition as multiple simultaneous observation leads to a physics so bizarre and incredible that most Western physicists have been unable to tolerate it, much less examine its consequences. In the physics that emerges from multiple simultaneous observation, all possibilities are real and physical. There are an infinite number of worlds, orthogonal to one another, and each world is continually splitting into additional such "worlds" at a stupendous rate. Nonetheless, this physics was worked out by Everett for his doctoral thesis in 1956, and the thesis was published in 1957. (See Hugh Everett, III, The Many-Worlds Interpretation of Quantum Mechanics: A Fundamental Exposition, with papers by J. A. Wheeler, B.S. DeWitt, L. N. Cooper and D. Van Vechten, and N. Graham; eds. Bryce S. Dewitt and Neill Graham, Princeton Series in Physics, Princeton University Press, 1973.) Even though it is bizarre, Everett's physics is entirely consistent with all the present experimental basis of physics. The present electromagnetic theory is constructed for only a single "world" or universe -- or "level." The expanded theory, on the other hand, contains multiply nested levels of virtual state charge -- and these levels are identically the same as orthogonal universes, or "hyperframes." Multiple kinds -- and values -- of time also exist. The new concept differs from Everett's, however, in that the orthogonal universes intercommunicate in the virtual state. That is, an observable in one universe is always a virtual quantity in each of the other universes. Thus one can have multi-level "continuities" and "discontinuities" simultaneously, without logical conflict. It is precisely these levels of charge -- these levels of scalar vacuum -- that lace together the discontinuous quanta generated by the interaction of vector light with mass.

However, to understand the new electromagnetic reality, one requires a new, expanded logic which contains the old Aristotlean logic as a subset. I have already pointed out the new logic in my paper, "A Conditional Criterion for Identity, Leading to a Fourth Law of Logic," 1979, available from the National Technical Information Center, AD-A071032.

Even as logic is extended, quantum mechanics, quantum electrodynamics, and relativity are drastically changed by the Tesla electromagnetics, as I pointed out in my paper, "Solutions to Tesla's Secrets and the Soviet Tesla Weapons," Tesla Book Company, 1580

Magnolia, Millbrae, California, 94030, 1980.

The present electromagnetics is just a special case of a much more fundamental electromagnetics discovered by Nikola Tesla, just as Newtonian physics is a special case of relativistic physics. But in the electromagnetics case, the differences between the old and the new are far more drastic and profound.

ADDITIONAL REFERENCES

1, Boren, Dr. Lawrence Milton, "Discovery of the Fundamental Magnetic Charge (Arising from the new Conservation of Magnetic Energy)," 1981/82 (private communication). Dr. Boren has a cogent argument that the positron is the fundamental unit of magnetic charge. His theory thus assigns fundamentally different natures to positive charge and negative charge. In support of Dr. Boren, one should point out that the "positive" end of circuits can simply be "less negative" than the "negative" end. In other words, the circuit works simply from higher accumulation of negative charges (the "negative" end) to a lesser accumulation of negative charges (the "positive" end). Nowhere need there be positive charges (protons, positrons, etc.) to make the circuit work. Dr. Boren's theory, though dramatic at first encounter, nonetheless bears close and meticulous examination -- particularly since he has been able to gather experimental data which support his theory and disagree with present theory.

2. Eagle, Albert, "An Alternative Explanation of Relativity Phenomena," Philosophical Magazine and Journal of Science, No. 191, December 1939, pp. 694-701.

3. Ehrenhaft, Felix and Wasser, Emanuel, "Determination of the Size and Weight of Single Submicroscopic Spheres of the Order of Magnitude r = 4 x 10(-5) cm. to 5 x 10(-6) cm., as well as the Production of Real Images of Submicroscopic Particles by means of Ultraviolet Light," Phil. Mag. and Jour. of Sci., Vol. II (Seventh Series), No. 7, July 1926, pp. 30-51.

4. Ehrenhaft, Felix and Wasser, Emanuel, "New Evidence of the Existence of Charges smaller than the Electron - (a) The Micromagnet; (b) The Law of Resistance; (c) The Computation of Errors of the Method," Phil. Mag. and Jour. of Sci., Vol. V (Seventh Series), No. 28, February 1928, pp. 225-241.

5. See also Ehrenhaft's last paper dealing with the electronic charge, in Philosophy of Science, Vol. 8, 1941, p. 403.

6. McGregor, Donald Rait, The Inertia of the Vacuum: A New Foundation for Theoretical Physics, Exposition Press, Smithtown, NY, First Edition, 1981, pp. 15-20.

7. Ignat'ev, Yu. G. and Balakin, A. B., "Nonlinear Gravitational Waves in Plasma," Soviet Physics Journal, Vol. 24, No. 7, July 1981, (U.S. Translation, Consultants Bureau, NY, January 1982), pp. 593-597.

8. Yater, Joseph C., "Relation of the second law of thermodynamics to the power conversion of energy fluctuations," Phys. Review A, Vol. 20, no. 4, October 1979, pp. 1614-1618.

9. DeSantis, Romano M. et al, "On the Analysis of Feedback Systems With a Multipower Open Loop Chain," October 1973, available through the Defense Technical Information Center (AD 773188),

10. Graneau, Peter, "Electromagnetic jet-propulsion in the direction of current flow," Nature, Vol. 295, 28 January 1982, pp, 311-312.

11. "Gravity and acceleration aren't always equivalent," New Scientist, 17 September 1981, p. 723.

12. Gonyaev, V. V , "Experimental Determination of the Free-Fall Acceleration of a Relativistic Charged Particle. II. A Cylindrical Solenoid in a Time-Independent Field of Inertial Forces," Izvestiya VUZ, Fizika, No. 7, 1979, pp. 28-32. English Translation: Soviet Physics Journal, No. 7, 1979, pp. 829-833. If one understands the new, expanded electromagnetics, this Soviet paper indicates a means of generating antigravity and pure inertial fields.

13. R. Schaffranke, "The Development of Post-Relativistic Concepts in Physics and Advanced Technology Abroad," Energy Unlimited, No. 12, Winter 1981, pp. 15-20.

14. F. K. Preikschat, A Critical Look at the Theory of Relativity, Library of Congress Catalogue No. 77-670044. Extensive compilation of measurements of the speed of light. Clearly shows the speed of light is not constant but changes, sometimes even daily.

Return to Table of Contents **Next Page**

COMMENTS ON THE NEW TESLA ELECTROMAGNETICS

Part II: The Secret of Electrical Free Energy

© 1982 T. E. Bearden

Again I wish to express my deep appreciation to two of my friends and colleagues who at this time, I believe, wish to remain anonymous. I thank them both for their exceptional contributions and stimuli, and their forbearance with the many discussions we have held on this and related subjects.

Also, it goes without saying that any errors in this paper are strictly my own, and not the fault of either of my distinguished colleagues.

Present electromagnetic theory is only a special case of the much more fundamental electromagnetism discovered by Nikola Tesla at the turn of the century.

Pure vacuum is pure charge flux, without mass. The vacuum has a very high electrical potential -- something on the order of 200 million volts, with respect to a hypothetical zero charge.

Thus in an ordinary electrical circuit, each point of the "ground" -- which has the same potential as the vacuum -- actually has a non-zero absolute potential. This circuit ground has a value of zero only with respect to something else which has the same absolute electrical potential.

Voltage, which is always associated with a flow of electrical "mass" current (even if only a miniscule flow), is, by definition, a difference dropped in potential when a charge mass moves between two spatially separated points. What we have termed "electrical current" only flows where there is a suitable conducting medium between things which have a difference in absolute potential. Furthermore, between any two points in any material, there is considered to exist a finite resistance -- if we apply a voltage and have a mass current flowing between the two points! The simple statement that V = IR irrevocably ties together voltage drop, mass current, and resistance between two points. Rigorously, to have one of the three is to have them all. To lose one is to lose all three. Immediately we see a major error in present theory: One can have a "difference in scalar potential" between two points without having a "voltage drop" between them. Specifically, if no mass current flows between them, no resistance exists between them, and no voltage drop exists between them.

In the same fashion, one can have a "scalar wave" through the



In the same fashion, one can have a "scalar wave" through the vacuum without a voltage wave. In that case, the wave has no E-field and no H-field. The only reason one has an E-field

Return to Table of Contents Next Page

around a statically charged object is because the charged electrons accumulated on the object are actually in violent motion. It is this motion of the charged masses that produces E-field -- as well as H-field whenever that entire E-field ensemble moves through laboratory space.

Now let us reason together in the "approximate" manner utilized in present electromagnetic theory. For example, let us examine a bird sitting on a high tension line.

The bird sits on the high tension line without a flow of mass electricity, because there is no significant difference in potential drop between the bird and the line. Specifically, between the bird's two feet -- each in contact with a different portion of the line -- there exists no potential difference. This is true even though, with respect to the vacuum, each foot is at a potential that would be "100,000 volts higher," were a mass current flowing. And it is true even though the absolute potential of each foot may be some 200.1 million "volts," were a mass current flowing.

Now an interesting thing happens to the bird when he flies through the air to light upon the high tension wire. As he flies toward the wire, he is flying through the massless electrostatic potential field of the wire, for that field extends an infinite distance away from the wire. The electrostatic potential field -- pure ϕ-field -- is actually the spatiotemporal intensity of the massless charge at a point. In other words, as the bird flies to the wire, he flies into an increasing "massless charge" potential, building up to 100,000 "volts" higher than the earth. However, very little (if any) "mass flow" potential difference is experienced upon his body in approaching the wire, and so essentially no "charged mass currents" are induced in his body. Thus the little flier safely navigates into the teeth of a very high electrostatic potential, lights upon the wire, and is not "fried" in the process. When he lights on the wire, his body has reached the electrostatic potential that each foot's contact point has. Again, there is no mass current flow. But his body is immersed in an increased flux of massless charge -- which is what the electrostatic potential represents. And each "virtual particle" flow in that charge potential represents a "massless (scalar)" electrical current.

The point is, one can have any amount of massless charge flow -- "scalar" current -- without any mechanical work being done in the system. All electrical work in a circuit is done against the physical mass of the charged masses that flow. Rigorously, force is defined as the time rate of charge of momentum. Even in the relativistic case where $F = ma + v(dm/dt)$, change of momentum requires mass movement. No mechanical work, and hence no energy, is expended by massless charge flow.

That is why the vacuum massless charge -- which is composed of a very high flux of massless "particles" -- normally does no work



That is why the vacuum massless charge -- which is composed of a very high flux of massless "particles" -- normally does no work on our systems, and expends none of its very high "potential energy." It is exactly the same as the bird which flew into an

Return to Table of Contents

Next Page

Return to Table of Contents

increasing scalar field as it approached the high tension wire -- no work was done upon the bird by the increasing scalar flux currents encountered by its body.

By existing "in the vacuum," so to speak, we (the whole earth) are as birds sitting on a high tension line! Until we create significant difference in potential, via our present electromagnetic circuits, no current can flow -- anywhere. Even if we produce potential differences, we must have a conductor and charged masses to flow, if we wish to produce mechanical work. Presently our electromagnetic theory allows us to create a difference in potential within different parts of a circuit, but only by moving and shifting charged mass. We therefore have to do work on this electrical mass in moving it around, and we only get back the work we have put into the circuit. In other words, presently all we do is "pump" electrical mass.

Now notice what would happen to the bird on the line if we substantially "pulsed" the potential on the line. Suppose we "pulsed" it such that the bird's physical system -- considered as a circuit containing a capacitance, a resistance, an inductance, and many free electrons -- became resonant to the pulsing frequency. In that case the "bird system" would resonate, and a great deal of electrical mass would surge back and forth in the body of the bird. In the bird's body, voltage would exist, charged mass current would flow, work would be done, and the bird would be electrocuted.

Also, note that, without mass movement, electromagnetic vector fields are not produced (and a portion of the difficulty lies with the actual vector mathematics itself). Scalar (nonvector) waves continually penetrate "space" where there is no mass movement. This means there can exist a "delta-ϕ" without a voltage or an E-field. The present theory does not allow this, because it always uses "q" (charge) to be charged mass. Briefly, without belaboring the point, let us just say that it is the mechanical spin of the individual charged particle -- such as the electron -- which "entangles" or "knits together" or "couples" independent scalar waves into vector waves. A vector wave is simply two coupled scalar waves. The entire force field concept -- such as the E-field and the B-field -- is operationally defined in terms of the force exhibited on a test particle, or test mass. Rigorously, an E-field does not exist as a force field in vacuum, but as two coupled scalar ϕ-fields "tumbling about each other." When these two coupled, tumbling fields meet a spinning electron, e.g., the force emerges on the electron mass. In short, movement of a rotating mass changes delta-ϕ to "voltage", creating the V/I/R triad.

By "accumulating charged mass particles" -- such as electrons -- one certainly can increase the value of ϕ, which represents the charge intensity or "scalar electrostatic potential." However, that is not the only way to increase it. Resonance and rotation of charged masses can also be appropriately employed to vary the vacuum charge potential ϕ, under the proper circumstances.

of charged masses can also be appropriately employed to vary the vacuum charge potential Φ, under the proper circumstances.

Return to Table of Contents   Next Page

By the correct application of rotary principles and Tesla electromagnetic theory, it is possible to oscillate -- and change -- the vacuum potential itself, in one part of an electrical system. Thus by correct procedures a part of a system can be electrically altered so that the absolute value of its "ground" (vacuum) potential differs significantly from the normal vacuum-ground potential of the remainder of the circuit. In other words, we shift the vacuum-ground potential of part of the circuit by oscillating the massless vacuum charge itself, and in so doing we gain a substantial, oscillatory electrical potential difference between that part of the circuit and the normal ground potential of the rest of the system. Then we connect the two parts of the system by means of a conductor containing a load in the middle.

In every conductor, a large number of "free electrons" are available. If we oscillate the actual vacuum charge itself, unlimited additional free electrons also become available from the Dirac sea, since partial "unstripping" of the negative energy wells (each containing an electron) occurs. This "unstripping" of the potential of the well is due to vacuum potential oscillation, which oscillates time as well as space. To a negative energy well (positive time), the oscillation of its "time stream" increases the well's negative potential during one half-cycle and decreases its potential for the other half-cycle. Thus during half the oscillatory cycle, negative energy electrons may be lifted from the Dirac sea if the oscillation is sufficiently intense.

Therefore we obtain an attendant voltage and flow of mass current through the load. This voltage and current, by the way, are essentially limitless, and are free for the asking, assuming the proper "vacuum oscillation" is initiated and maintained so that electrons are continually being lifted from the Dirac sea by the time oscillations, and fed into the circuit.

Standard electromagnetic theory assumes that the vacuum potential is zero. It does not recognize the existence of massless charge, separated from charged mass. Therefore, orthodox scientists have never looked for a way to engineer the vacuum, because they have not realized it is composed of pure massless charge. Electrical physics has almost hopelessly confused charge and charged mass, thereby eliminating scalar longitudinal electrostatic waves. Expressed in the bird/high tension line analogy, the present electromagnetic theory restricts us to walking along the high tension line, laboriously carrying small batteries and power units, unaware of the limitless, surging power beneath our very feet.

Electromagnetically, we have been rather like one of the five blind men who touched an elephant. We have only touched one small portion of the electromagnetism "elephant," yet we thought we had grasped the entire beast.

Return to Table of Contents Next Page

OVERTURE TO A NEW AGE TECHNOLOGY

From an Update by Dr. Rolf Schaffranke

> " ... as there has been a steady erosion in U. S. activity in the basic sciences, there has been an increase in the level of such activity in Western Europe and Japan. If that continues, we are in danger of losing our position of scientific leadership."
>
> Val. L. Fitch, Prof. of Physics at
> Princeton University, in an interview with
> *U.S. News & World Report*, June 21, 1982.

West Germany:

The prototype of the first motorcycle equipped with a "flux-motor" (the inventor's designation for a tachion field converter or gravity-field generator) of 2 KW output has completed a test run of approximately 20,000 km without repairs. Principle of operation: The T-converter is constantly recharging the electrical power battery of the vehicle, resulting in an operation which is noiseless, fuelless and polution-free. After completion of all scheduled tests, a public demonstration to the press is planned within a few weeks from the time of this writing. (June 17, 1982) See photo, Pg. 19. A new factory for the production of gravity-energy-field converters in the town of Oldenburg is scheduled to produce individual home heating units. The design of automobile power plants based on the same principle is also in preparation. Reported efficiency factors of several hundred percent are anticipated.

Japan:

Mazda continues research on the "magnetic Wankel engine" (45 HP) for electric automobiles, based on the principle of Kure Tekko. The gravity research of Prof. S. Seike is now sponsored by Hitachi, after millions of Japanese received updated information via popular science magazines. It is interesting to note that Saudi Arabia has decided to invest $100 million in Hitachi stocks.

France:

The "Kromrey" converter has completed tests at the Institute for Magnetostatics, University of Strasbourg. One prototype delivered 700 Watts at 600-1200 RPM, at a fairly uniform rate. However, France, as the No. 1 developer of nuclear energy in Europe, is still reluctant to concentrate her energies on a revolutionary new technology which could result in drastic curtailments of her well-developed nuclear industry and associated exports. See photos, Pg. 22.

Denmark:

Dr. Jensen, physicist at the University of Kopenhagen, reported test results of 300% efficiency with a specially designed, 5-coil transformer in connection

Return to Table of Contents Next Page



with a tachion field converter based on the principle of the "N" machine. First reports were presented at the International Conference on Energy Technology in Hannover, Nov., 1980.

England / USA:

A "bullet train" based on the magnetic levitation system of British Prof. Eric Laithwaite is now under consideration for construction between Los Angeles and San Diego. Japan and West Germany are already operating high speed experimental trains, suspended magnetically to reduce friction, that may soon attain speeds of more than 200 miles per hour. The Laithwaite-Eastham method would use electromagnetic forcefields induced over an aluminum-topped concrete track. The project will probably be headed by a Japanese company as the prime contractor.

Return to Table of Contents Next Page

West German gravity-field unit in operation

Return to Index Next Page



Swiss-French gravity field converter system "Kromrey"

Return to Index **Next Page**

REVIEW AND OUTLOOK

THE DEVELOPMENT OF POST-RELATIVISTIC CONCEPTS IN PHYSICS AND ADVANCED TECHNOLOGY ABROAD

Rolf Schaffranke, Dr. h. c.
Member A.I.A.A.

This paper was presented at The First International Symposium on Non-Conventional Energy Technology, Toronto, Ontario, Canada, Oct. 23-24, 1981. (Reprinted by permission of the author.)

"Far more harm is done to the progress of science by skepticism than by gullibility". (Dr. Robert Wood, Director R & D, McDonnel-Douglas Astronautics Div., Cal.) NASA - Langley Research Center in Hampton, VA is named after Samuel Pierpont Langley (1834-1906), an American astronomer, engineer and architect.

Langley worked out the aerodynamic principles for manned flight. In principal, his calculations were correct; but the structural materials he used for wings and engines were ,insufficient. In December of 1903, the *New York Times* published an editorial complaining about his foolish dream and the associated waste of government money. The editorial predicted that: "man would not fly for a thousand years".

Only 9 days after the editorial was published, the Wright brothers made their first successful powered flight at Kitty Hawk. (Dec. 17, 1903). But, again, as late as 1905, the *Scientific American* suggested the happening was a hoax - two years after the event which changed history. Let's reflect for a moment on the fact that only in a single lifetime, man has journeyed from Kitty Hawk to the surface of the moon!

The analogy to the problem of alternative energies and their development is, of course, obvious. We try to educate the preaching orthodoxies. But orthodox solutions are no longer enough. Our system of education can only give from the past. The present must operate on inspiration and intuition, or the future will be lost. The past no longer has enough of the answers for arising crises for which there are no precedents. To keep pace with the requirements of the future, we must begin to teach not only what to learn, but how to learn, how to analyze, how to search for the truth. Only then will be able to recognize discrepancies between experiment and dogma and to cope with problems which appear to be just beyond the corner. History has shown again and again that no single individual can rise above the species without being persecuted. The reasons for that are:

Some of the most powerful forces in homo sapiens have always been
Greed, Pride, Ego, Fear and, above all, the Desire to Control Others,

.

A brand new German book titled *Energy in Abundance*, which is evidently creating a considerable impact in the European community, challenges the contemporary high

Return to Table of Contents **Next Page**

priests of science, the "Guardians of the Status Quo" and uncovers an almost incredible narrowmindedness and ignorance in science, politics and economics, "approaching the criminal" as the author puts it. The contemporary waste of genuine intellectual creativity is castigated as a cultural scandal approaching barbarism. The book stresses that a truly promising approach to the so-called energy crisis requires a fundamental and thorough re-evaluation of the theories, dogmas and axioms which form the basis of present day science and the foundation of our technology. As in the past, the formidable inertia of the establishment is not only based on inaccurate, incomplete and outdated information, but also on its reluctance to accept new ideas. The honest search for the truth first requires that we first demythologize generally accepted claims of so-called experts of the past. An excellent introduction to this problem is the article "Resistance by Scientists to Scientific Discovery" by Bernard Barber in *Science*, Vol. 134, pp. 596-602, of Sept. 1961, or the paper by Stephen C. Brush in *Science* of March, 1974, titled "Should the History of Science be Rated 'X'"?, culminating with a statement of Huxley:

> "Authorities", "disciples", and "schools" are the curse of science and do more to interfere with the work of the scientific spirit than all its enemies".

The former astronaut, Capt. Edgar D. Mitchell, one of our famous contemporaries, also stressed the need for an open mind!

> "History has shown time and again that important scientific discoveries generally happen only when someone steps outside the limits of his traditional discipline and looks at something from a fresh point of view. Then what should have been obvious all along comes into focus".

Those of us who are familiar with the pioneering efforts of Dr. Hans Nieper of Hanover will appreciate this statement by an ex-astronaut.

One of the most important cornerstones of today's scientific dogmas dates back to 1905, more than 3/4 of a century ago. Lest we forget, television and radar, jet-planes and cyclotrons, moonrockets and close-up photos of the planets of our solar system were nothing but wild fantasies of science fiction then.

The speed of light was assumed to be constant and the maximum possible speed in the universe; vacuum was to be a total void. In reality, the speed of light as measured in the Michelson-Morley experiments was not at all the same in all directions. The "ether-drift" still amounted to the respectable velocity of about five miles per second, and similar results were obtained by D. C. Miller in a series of experiments extending over twenty-five years, from 1902 to 1926.

[Return to Table of Contents](#) [Next Page](#)

> "Even worse, the measurements showed such marked discrepancies with previous results as to occasion a distress call to the U. S. Coast & Geodetic Survey, whose surveyors repeatedly remeasured the length of the tube and found no error there," reported the *Popular Science Monthly* March 1934 issue. And it continued: "More recently, speed of light observations only emphasized the apparent erratic behavior of the light beam that the scientists were attempting to plot. On some days it seems to travel faster than others by as much as 12 miles a second. Its speed seems to vary with the season, and also in a mysterious shorter cycle lasting about 2 weeks. Finally, the scientists ended by taking an average of all the readings which has just been announced as 186,271 miles per second".

In his paper "A Critical Look At the Theory of Relativity", Library of Congress Cat. No. 77-670044, F. K. Preikschat compiled all known light velocity measurements during the past 300 years or so, from Olaf Roemer in 1676 to the Laser measurements conducted by the National Bureau of Standards (USA) in 1972.

Of the 27 experiments undertaken in this field, 18 of them after the turn of this century, it must be concluded that the velocity of light as measured within the reference system of our earth has changed as much as plus/minus 50 km/sec. during the past century. Preikschat plotted a curve of these deviations and suggests a possible relationship between sunspot activities and changes of the earth magnetic field during the time period in question.

The "universal constancy of light" appears, therefore, as somewhat shaky "empirical evidence" for our cornerstone in physics, especially since Einstein himself has gone on record as saying:

> "If a single one of the conclusions drawn from it (relativity theory) proves to be wrong, it must be given up; to modify it without destroying the whole structure seems to be impossible".

Another modification concerns the definition for the term "vacuum" in physics, as documented by a paper in the *American Scientist*, March-April 1980, titled "Is The Vacuum Really Empty?" by Prof. Walter Greiner, University of Frankfurt, BRD, and Prof. Joseph H. Hamilton, Vanderbilt University, Nashville, Tenn.

The authors conclude that a neutral vacuum is by no means as "empty" as previously claimed in our textbooks, and suggests a new definition as follows:

> "The vacuum is the lowest stable state that a region of space can have while being penetrated by certain fields".

Because of the tremendous time lag in our educational system, many research

Return to Table of Contents Next Page

projects and their ensuing experimental data have been withheld from public scrutiny. The scientific community tends to have a vested interest in preserving the system it created and of which it is a part. It responds to new situations through the coloration of this attachment. A case in point are the carefully conducted experiments of T. T. Brown with charged bodies in a high vacuum, as described in my booklet *Ether Technology* (1977). These experiments suggest the actual presence of certain fields in vacuum, whether we call them gravitational field, tachion-field, ether-field, neutrino or Fermi-sea, etc. is of secondary importance at this moment. Although Brown spent, reportedly, more than $200,000 of his own funds over several decades on such experiments, he was nevertheless unable to have the results published in the scientific media of America.

Things are even worse when it comes to experiments conducted abroad, which often tend to confirm disregarded experimental results on this continent, as we shall see shortly. To highlight the wide discrepancies between orthodox (and obsolete) dogmas and actual, physical realities pertaining to the true subatomic structures as we know them to be today, let us briefly review the structure of the matter:

A molecule is the smallest division of a substance. Further division would cause it to cease being a substance. The smallest of true molecules can be illustrated when we use the globe of the earth for our standard. If a single drop of water were magnified until it was as big as the earth, each molecule would be about the size of a TENNIS BALL.

On the next step down, an atom is the unit which makes up the nature of the molecule, consisting of the nucleus and the surrounding electrons to render the atom "stable". An atom of hydrogen contains one proton and one electron to balance or neutralize the proton. Matter then is divisible into electrons and protons. But - and here comes the rub: Between electrons and protons are spaces so vast, in comparison with the masses of each, that, if the proton in the carbon atom were the size of a golf ball hanging from the ceiling of the great hall at Pennsylvania Station in New York, its electrons would be represented by six small wasps winging in a little knot against the four walls of the gigantic structure of the building! In effect, one could claim there is little final solidity of substance to anything: The universe consists of "emptiness", charged with electrical energy! If we translate the above to the measurements and terminology of the physicist and "magnify" the atom mathematically, with all its distances and dimensions kept in proportion so that the orbit of the electron would have a diameter equal to that of the earth about the sun, approximately 184 million miles, the diameter of the electron itself would only be 2,000 miles, and the diameter of the nucleus, where electron itself would only be 2,000 miles, and the diameter of the nucleus, where

Return to Table of Contents

Next Page

mass and weight of the atom are truly concentrated, can be taken as 2 miles only. We thus obtain a picture of a central mass with a diameter of 2 miles (nucleus), another object with a diameter of 2,000 miles (the electron, in the case of the hydrogen atom) at a distance of 92 million miles away from it, orbiting the nucleus. Evidently, there is plenty of room inside this system. And "room" is not a vacuum, it is not nothingness, but space itself, spatial energy, a field which can be identified with the ether of the past - and of the future. Nobel prize winner, Max Planck, during a lecture in Florence, Italy, once made a truly remarkable statement which describes the problem facing the physicist today:

> "As a man who has devoted his whole life to the most clear-headed science, to the study of matter, I can tell you as the result of my research about the atoms this much:
> 'THERE IS NO MATTER AS SUCH!'
> All matter originates and exists only by virtue of a force which brings the particles of an atom to vibration and holds this most minute solar system of the atom together. ... We must assume behind this force the existence of a conscious and intelligent MIND. This mind is the matrix of all matter".

This cosmic matrix is needed if we want to explain "action at a distance", lines of force, stresses, a magnetic field and so on. When the concept of the ether was abandoned, it had to be replaced by the concept of "space" instead. In reality, we merely switched terminology. We used to say that "ether fills all Space". But "filling" is not exactly the descriptive word to use. Perhaps we should rather define it: "Ether is a condition of space in which electrical manifestations for the atomic construction of materials is possible". This primordial energy is "free" or in an uncondensed state. It exists in interstellar space but remains unrecognizable until it begins to coagulate or gets into a vortex pattern. It constitutes the formative field force of nature, an immense reservoir of latent energy.

The claim of our textbooks that the Michelson-Morley experiment "disproved" the existence of the ether is incorrect. It merely disproved the existence of a noticeable ether drift or drag. As an analogy, if somebody would postulate that the absence of wind disproves the existence of the atmosphere around our planet, the fallacy of this postulate would be immediately apparent to all.

"Michelson and Morley centered their attention on the Earth's orbital velocity (30 km per second). They had no knowledge of the existence of galaxies; of motions of galaxies in relation to each other; of the motion of our solar system in our galaxy..... Their negative results are explainable on the basis of pre-1900 classical mechanics, so provide no proof of the absence of ether or Louis de Broglie's

Return to Table of Contents Next Page

'subquantic medium'. Thus, the limited information available to Michelson and Einstein is emphasized by recent findings, particularly in astrophysics", writes Dr. H. C. Dudley in the *Bulletin of the Atomic Scientists*, January, 1975, under the title "Michelson's Hunch Was Right". And Dr. Dudley continues: "In fact, 1929 saw Michelson still attempting to experimentally demonstrate the ether, which his intuition and reasoning told him ought to be present".

"Today most persons are largely unaware that the ether concept began to be seriously reexamined by two of physics most notable theoreticians, Paul Dirac in 1951 and de Broglie in 1959, both Nobel laureates. The ether is now being called the "neutrino sea" by astrophysicists, and has been characterized as an energy-rich particulate, subquantic medium. A rather voluminous literature on the subject is accumulating as indicated by a recent review, *The Cosmic Neutrino*, with 665 references covering only the period 1965-1972......It appears that an open-minded reexamination of this area of physics is long overdue in order to open up new avenues of approach to this pressing problem".

Michelson, Dirac, de Broglie were not the only Nobel prize winners in favor of a reexamination of the ether question. Others were Stark, Arrhenius, A. H. Compton, Lenard, H. Yukawa, and Frederick Soddy, the British scientist who, during the convention of Nobel laureates in Lindau, 1954, described the current dogmas in physics as "an orgy of amateur physics" and "arrogant swindle" - with particular emphasis on the theory of relativity. ("The Wider Aspects of the Discovery of Atomic Disintegration", New World Publications, St. Stephens House, Westminster S.W.I.)

It remained largely unknown, even among physicists, that Einstein himself had serious doubts. In 1949, he wrote to his old friend, Maurice Solovine, who congratulated him on his 70th birthday:

> "Now you think that I am looking back at my life's work with calm satisfaction. But, on closer look, it is quite different. There is not a single concept of which I am convinced that it will stand firm and I am not sure if I was on the right track after all".

And one of my Canadian friends who I believe is present here today stated quite correctly in a letter to me:

> "The myths around Einstein are really not of his making as he himself often questioned his own conclusions and I felt he was quite aware of his own limitations which others were covering up. The physicists protect their members much the same way that the medical profession protects its own."

The purpose of these remarks is not to spark another controversy about the merits of the theories of relativity. Rather, they want to show that so-called merits of the theories of relativity. Rather, they want to show that so-called

Return to Table of Contents Next Page

"scientific evidence" is a rather elastic term and that "verification" is always a relative affair. Or, as K. R. Popper so aptly put it:

> "Only in our subjective experience of conviction, in our subjective faith, can we be 'absolutely certain'".

This symposium presents an excellent overview of research and experiments reported from English speaking countries, or experiments published in the English language, as for instance from Japan. However, as Dr. Tenhaeff from Holland has formulated the problem,

> "It is important to pay attention to publications of colleagues in other countries. In the Netherlands and Germany, every academically educated man or woman knows at least three foreign languages. English and American authors only pay attention to material in English. In my opinion, this leads to an 'impoverishment' which puts a drag in science. Some seem very chauvinistic and seem to believe that only the researches done in their country are important. I regret this. Science is international, and international cooperation is of the greatest importance in science".

In presenting some brief reports from abroad, I shall attempt to bring corroborative evidence in support of alternative technology developments discussed during our meeting here in Toronto. Let me start with the most sensitive and secretive society, with Russia.

In his German original of the paper "Some Remarks on the Shielding Theory of Gravity", which was published in the Hanover Proceedings in more detail than the English abstract, Dr. Hans Nieper mentioned the Berlin engineer Levetzow, who was one of the first to postulate a combination pressure and shielding theory for the phenomena of gravity. Levetzow was soon overshadowed by the rising star of Albert Einstein, but one of his followers, Horst Pinkell, went to Russia in 1928 as an exchange student - and never returned. Together with Russian scientists, he was asked to prove the actual existence of the cosmic radiations postulated by Levetzow, now designated as neutrino sea or "tachion field". The work was done in Sterlitamak, South of the Ural mountains, and in 1938, sporadic reports reached the West about the discovery of extremely short corpuscular waves by Pinkell and Gorjew. These were the long sought "Hemmstrahlen" or drag waves associated with gravity. Rumors have it that a metal alloy was soon developed which acted as a drag wave polarisor and, in 1947, agents reported experimental Russian aircraft using this discovery. In 1951, a former German Junkers aircraft engineer reported about his activity pertaining to a super-secret project code named COW-7 in Siberia, a disk-shaped craft which could rise vertically and which belonged to the

Siberia, a disk-shaped craft which could rise vertically and which belonged to the

Return to Table of Contents

Next Page

secret weapons then developed by the Soviets. Whether it was related to the Canadian AVRO project or something entirely different remained unknown, only the Levetzow gravity theory was assumed in connection with the activity in question.

Japan: My esteemed friend, Prof. Seike, who kept me informed about the research conducted by him and his co-workers, surprised me once with a significant statement, which I feel is important to repeat for the benefit of frustrated researchers on this side of the Pacific: "In the early stage of my studies, physicists could not understand what I was doing, while actors and actresses did so by intuition". It was the private support of about 800 individual artists, etc., in Japan which allowed Seike to work, experiment and publish his findings, and not the support of the Japanese equivalent of a National Science Foundation or a similar bureaucratic institution in that country. Again and again, I was surprised how quickly and eagerly American experiments, as for instance the almost forgotten "Ionocraft" of the late Major de Seversky, were duplicated and explored even in Japanese secondary schools. Admiral Rickover has more than once complained about our intellectual complacency: "As a nation, we seem addicted to 'spectatoritis'. We sit in the bleachers and let the game of life unfold before us".

The results are known: The Japanese have achieved top position in science and technology, and not only with tachion beams melting stones, producing "biased" water with a freezing point of minus 4 degrees Celsius, and a G-power generator obtaining 400 V DC output from a 10 V input driving source. I wish to take this opportunity to thank Prof. Seike for sharing his work with us in this country, and wish him the best of success for the future.

France: The work of SEPED was explained by M. René Louis Valée and some French publications in the area of gravity-research have been translated by the NASA translation service, as for instance the theory of the electromagnetic Magnus-Effect (of Marcel Pagés).

Specific mention must be made of the Raymond Kromrey G-field generator, a French-German-Swiss development which appears very closely related to the American "N" machine principle, the "Sunburst" machine and the "Permanent Magnet-Motor" Patent of Howard Johnson. Utilizing either permanent or electromagnetic modules, the generator output exceeds the input by far. One prototype delivers approximately 700 watts at speeds varying between 600 and 1200 RPM. Models with an output of 100 to 160 kw are presently in the planning stage. Several European patents have been granted against heavy opposition, especially from French industrial circles. The development was about 40 years in the making and the inventor stresses the need for a reinvestigation of electromagnetic and gravitic forces, as well as a reexamination of many cemented dogmas in present-day physics.

ection of many cemented dogmas in present-day physics.

Return to Table of Contents

Next Page

Germany: A system of rotating electromagnets and magnetic "stator rings" of the German "Kunel" Generator complement the general trend of the American and French generators mentioned before. The first prototype was reported to have been tested in April, 1980. Here, again, very heavy opposition from the German orthodox science establishment. Of special interest is a comment by Nobel laureate Werner Heisenberg, reported to have been made vis-a-vis the inventor:

> "I think it is possible to utilize magnetism as an energy-source. But we science idiots cannot do that; this has to come from the outside".

More details about French and German developments have been published in the new book already mentioned, *Energy in Abundance* by Hilscher and, hopefully, an English version of this important work will be available by next year. Generators which do interact with surrounding energy fields have been designated as "open systems", in contrast to our present "closed system" technology of gasoline and diesel engines, steam turbines, nuclear power plants and so forth. The theoretical basis for all "open systems" is the realization that there simply is no such thing as "empty space". In reality, space is filled with an extremely energy rich, subatomic and subquantic continuum. In short, a "pre-physical state of matter", which can be tapped, as for instance by the spinning of magnetic systems which extract momentum via a vortex-formation of the universal "tachion field".

Austria: This small heartland of Central Europe is proud of her native pioneers in science, among them Dr. Wilhelm Reich, Viktor Schauberger and Karl Schappeller. But after Dr. Reich died in an American prison in 1957 and Victor Schauberger died only five days after his return from the USA (in 1958), where he received an incredibly unfair treatment from certain industrialists, there is little enthusiasm among Austrians to touch base with correspondents on this continent. Viktor Schauberger's son, Walter, refuses, as a matter of principle, to communicate with Americans, no matter in what language. To illustrate the type of "contract" Viktor Schauberger was forced to sign, it stated:

> that all of his patents would become the property of the "consortium",
> that any future inventions or developments would also become the property of the "consortium",
> that he would refrain from discussing any of it with third parties,
> that he would refrain from publishing,
> that all plans and models would remain with the "consortium" after his departure from America.

There is a favorite saying in that small country which is much to the point:

> "After the Greek philosopher Pythagoras had discovered his famous

Return to Table of Contents Next Page

> theorem, he sacrificed a whole hecatomb of oxen as a thanksgiving to the Gods. Ever since, all the oxen in the world are running scared whenever a new truth has been discovered".

Knowledge of the ideas of Schauberger and Schappeller appears to be essential for an understanding of our changing picture of the physical world. As an example, the former forest ranger Viktor Schauberger had watched numerous times some trout standing, apparently motionless, in the strong currents of Alpine mountain streams. This and many similar observations of nature brought him to the gradual development of his "implosion-theory" and associated hardware (see Jensen paper elsewhere). His son is continuing the work in the "Pythagoras-Kepler" School in Bad Ischl. Another prolific researcher is the Viennese engineer Franz Seidl, known for his studies of the use of magnetic field effects as "trigger energy" for voltage and power multipliers.

Holland: A small country with strongly developed intellectual independence appears to be Holland, where Prof. J.M.J. Kooy developed his "Space Dynamics". His hypothesis of gravitational action is based on the realization that all celestial bodies can be conceived as practically transparent in relation to the size of the elementary particles and their mutual distances in the structure of matter. Gravitons or tachions, coming from all directions of deep space, can pass through a celestial body like water passes through a fishnet, and only a minute fraction of the cosmic gravitons or tachions will be intercepted. Study of the effects of the tachion field or space continuum of the fabric of material substances, magnets and crystal lattices can lead to development of converters and novel production facilities for readily usable, conventional E/M energy. When the American inventor Edwin V. Gray was blocked in his efforts to develop his "Pulsed Capacitor Discharge Electric Engine" for which he had received U. S. Patent #3,890,548, he found open ears and open minds in Holland.

The fact that Gray was named "Inventor of the Year" from the Department of Patent Rights in Los Angeles, California, where Dr. Chalfin of Cal Tech confirmed that:

> There does not exist an even distantly similar engine to this one in the world. Conventional electric engines use up power. In this system energy is used up for only a minute part of a millisecond. It operates without heat loss and there is no energy loss whatsoever with this system",

had more meaning to the people of PHILIPS and others in Holland than to the energy establishment in his native America.

England: There is perhaps no more controversial inventor at this time than

There is perhaps no more controversial inventor at this time than

Return to Table of Contents

Next Page

John R. R. Searl and his Levity Disc, powered by the Searl Effect generator. It is claimed that model craft have been demonstrated with flight characteristics showing anti-gravitational and inertia-free properties. Demonstrations have been photographed and videotaped. Searl calls his generator a "Gyro-Flywheel High Energy Density Mechanical Magnetic Device" and claims that the magnets used are not the common type, ordinary magnets. The Australian engineer Athol Park of Melbourne, Australia, who visited Searl a few years ago described it this way:

> "From a briefcase, Mr. Searl takes a bar magnet and two steel rollers. He places the rollers at either end of the magnet. They appear to be attracted to the poles - but, when they are pushed gently around the corners of the magnet, they chase each other round and round.... "

The engineer quotes Searl:

> "The crystals in the magnet are changed by putting it in a magnetic flux oven and by frequency control. The result is motion of a magnetic field - a completely new source of power. Units (modules) based on this principle are what power my levity unit - the motor and generator built as one, fuelless unit".

In one of his numerous newsletters he states further:

> "The power plant is a self-contained, onboard closed system of conversion elements with energy input from a latent storage source".

Because Searl has never divulged all details and his explanations are generally of a non-technical, "unscientific" nature, many investigators have chosen to dismiss him as a swindler and imposter. In sharp contrast to this is the opinion of a well-experienced American engineer who reported after a visit with Searl:

> "I found it refreshing to note the keen sense of moral responsibility which he feels for the use to which his discovery is put... The Searls live in modest circumstances. Luxuries are few. They do not own a car. Mr. Searl bicycles several miles daily to his place of work in Maidenhead. There he is an electrical technician and training supervisor in a bearing factory".

But perhaps most significant was the following observation of the American visitor about Searl:

> "We were also interested to hear him say that many of his ideas came to him while he slept. He would go to sleep with questions, and awake with answers... and refreshed. He seemed to have the

and awake with answers... and refreshed. He seemed to have the

Return to Table of Contents Next Page

> ability to restore vital powers more quickly than most people".

And the American concluded his report with the statement:

> "The impression we gained of Mr. Searl was one of a very sincere and generous person, a dedicated and tireless worker with perfect confidence in the outcome of his efforts, a man of high principle with a keen sense of loyalty to those who are helping him, and of responsibility for the future welfare of our planet and its people".

In view of the very contradictory nature of comments and impressions by those who have met Searl, it might be wise to reserve final judgment on the Searl-Levity-Disc and its inventor at this time.

New Zealand: Some of Searl's keenest supporters and observers of his work are in New Zealand and Australia. And one of the sharpest young physicists in that country (new Zealand), unhampered by calcified ideology, developed the mathematical foundation for a theoretical anti-gravity effect, using the hydrodynamic analogy of the ether. He uses the equivalent of the hydrodynamic Reynolds number, above a certain value of which the laminar flow past a solid surface breaks down and becomes turbulent due to shear rupture of the viscous cohesion of a fluid, together with his deduction that anti-gravity could be obtained by creating a "vacuum: in the ether in such a way as to correspond to the production of turbulence in a magnetic field. Turbulence in a fluid occurs when Reynolds number RE = 1, when the inertial shearing force equals the viscous cohesion force in the fluid in the vicinity of an approximately spherical body immersed in the fluid, resulting in separation of the boundary layer and formation of a wake, i. e. vacuum or free surface around the body. He calculated the threshhold for turbulence in the ether, = a vacuum = an anti-gravity effect, using the refined value of ether kinematic viscosity which he obtained.

His theory would confirm the observations of very high voltage produced in the case of the Searl Levity Disc, and the very high voltage needed in the vacuum experiments with flying disc-shaped bodies of T. T. Brown, the "ionocraft" observations of Major de Seversky, the "Electro-Field Rockets of Prof. Dudley, the observations of Northrop Corp. with "Electro-Aerodynamics in Supersonic Flow" and similar American documentation and patents.

Since the New Zealander is now in the process of attempting to publish his theory in a reputable British magazine, I am not at liberty to divulge his address prematurely. Interest in New Zealand and Australia is running high, and possible breakthroughs in energy technology should not come totally unexpected in these two countries with strong intellectual ties to England.

Return to Table of Contents Next Page

Conclusion

There is now overwhelming evidence for the actual existence of a very high density, energy rich space continuum formerly called "ether". This space energy can be concentrated, gathered, focused, magnified and compacted by magnets or magnetic materials, which appear as the new core materials for converters of all kinds, utilizing the cosmic energy for new technology applications.

Crystals are energy-sensing and channeling devices; they can serve as transducers, as for instance in the Moray-Device, or the "rock electricity" of T. T. Brown.

Combinations of crystals and magnetic materials appear to be the mainstay for the development of "hyper-space" - converters and generators of power - utilizing free, cosmic energy in our future.

Unbiased, totally honest and impartial reexamination and reevaluation of all scientific theorems and dogmas, as well as unhampered opportunities for the pioneers of the new technology on the American and European continent appear to be the prerequisite of success.

Those who accept that anything of the nature of ideas or ideology is permanent, use all their strength to hold on to it, and to condemn all who do not agree. The next stage of this spiritual illness of the mind is to build a monument to what they perceive is Truth, and then to build a monument to their own permanence in the world. This, they do by seeking fame or fortune, and authority over others. This is the contemporary, planetary psychology situation, and thus are we losing the gift of perspective and horizon and are no longer able to discern what is important. Skeptics are on record as saying:

> "We are not running out of natural resources or intellectual talent, we are running out of the freedom of innovation that made the countries on the North American continent the most advanced nations on earth".

The future will show whether this freedom, which includes the freedom and the duty of taking risks, can be restored to the degree our Founding Fathers have been striving for. Only then will we know whether the late Wernher von Braun was not too overly optimistic when he stated:

> "The cosmic age will bring a dawn of knowledge not yet envisioned. It will dwarf all our present knowledge and ideas and, through its vastness, may even bring men closer together on their own planet".

Return to Table of Contents

The Unveiling of the Hidden Knowledge and the Secret Space Program

The Unacknowledged Special Access Programs: Advanced Technology, Mind-Control, Spiritual Power and the Corruption behind Closed Doors

By Aug Tellez

Introduction........7
  Getting This Out Of The Way........7
  Psychic Operation........8
  A Light for the Others........8
  Natural Security........8
  A Balance of Mystery and Truth........9
Chapter 1: The World Situation........9
  What is happening?........9
  The Mind Virus........9
    The Vampire Effect........10
    Sub-Human Entities........11
    Human-Hosts, Replicants, Synthetics and Carriers........11
    Genetic Manipulation........12
    The Ego Mind........13
    This Time is about Healing........13
    Healing Through Unity........14
  Underground Bases........14
  Cloning........14
  Celebrity Cloning........15

Initial Explanation......15
Cloning Centers, Underground Bases......15
Programming......15
Experimental Operations......15
Genetic Engineering......16
Immortality......16
How did it get to this?......16
Deeper Meaning......17
What is next?......17
Chapter 2: The Awakening......18
Chapter 2.1: The Machines of All Time and Space......18
Re-Creating The Kaleidoscope......18
Sand-Castles of Time......18
We’re Waiting For Ourselves......18
The Goal of Two Societies......19
Our Forgotten Other Half......19
All Is But An Illusion......20
Life Itself Is The Highest Illusion......20
Chapter 2.2: The “Awakening” of 2010......21
Memory Suppression......21
Life and Consciousness......22
The True Human Potential......22
The Light-Body......23
Technology of the Awakening......23
Mental Manipulation Technology: Touchless Neural-Interface and Enhanced Awareness......23
Time Dilation and Temporal Recurrence......24
Crystal Technology......24
Time Crystals......25
Quantum Tunneling Diodes......25
Tachyon Fields......25
Upgraded Chronovisor......26
Time Tunnels......26

The “Trip” Chair....26
Kozyrev Mirror....27
Universal Recurrence....27
Remove Viewing, Temporal Lensing....27
Temporally Linked....28
Natural Vortex Energy Locations and Geography....28
  Mount B....28
Particle Accelerator Temporal Manipulation....28
Riding the “Timewave”....29
Dematerialization and Rematerialization....29
“Jump Rooms....29
Ion Shields....30
Instantaneous Healing....30
“Living Light” Sound-Harmonics and Electromagnetic Healing....30
Electrogravitic Craft....30
Energy Cores and Storage Capacity....31
3.5D Replicators....31
3.5D Sensors....31
3.5D Printing of Clones....31
Cybernetics:....31
Neural-interlace/4D Connectome Recording and Simulation....31
EEG Heterodyning....32
Artificial Hallucinations....32
Brain to Machine Interface Holographic Consciousness System (brainchip interface, virtual reality simulator)....32
Utilizing The Temporal Body....33
  Manipulation Through the Temporal....33
Astral or Light Body....34
Monitors can emit consciousness/brainwave altering frequencies....35
The Upgraded Chronovisor....35
Community Servers/Living Server Systems....36
Cloning, Cloud Supercomputing and Consciousness Transfer....36
Cloning, Supercomputer Assisted Holographic Consciousness Replication and Time Travel....37

Cloning as Offspring......38
Inserted Memories, Digital Dreams......38
Co-Inhabitation of Bodies......38
Clever Replication a Digital Mirror......38
Necromancy and Soul Stealing......39
Ancient Technology, Non-Human Entities......39
Created Beings......39
Black Goo – AI Nanites Vampiric Hive Mind......40
    Recreating or Replicating the Universe......41
Ancient Spiritual Technology......41
The Unveiling, Underground Bases, Increasing Awareness......42
Learning about the Unveiling......42
Giant “god-men”......42
Breakaway Civilizations......43
Ancient Civilizations......43
    Atlantis......43
    Aegypt......44
    Ancient Technology......44
The True Elite......44
The Definition of Human......44
Souled and Non Souled Beings......44
There was once a Unified Planetary Consciousness......44
    Power and Knowledge......45
    The (watch)Keepers of Earth......45
Energy Vampires......46
Spiritual Technology......46
Simulations and Learning......46
Ascension – Clearing Trauma......46
Trauma-Clearing, DNA Unlocking Technology......48
Everyone Who Seeks Harmony and Healing Can Be Healed......49
Programming......50
Layers of Programming and Decision Making Roles......50
    Programmers......50

  - Sub-Level Programming....50
  - Dissolution of Programming....51
- Advanced Technology, Deprogramming The Mind, and “Space/Time”....51
    - Dreams, Technology and Inner-Space Travels....52
    - Awareness Feedback Device....52
    - Oneness, Higher Being, Completion, Eternity....53
- The Holographic Reality....53
- Veiled Awareness, Hidden Knowledge, Eternal Time, Layers of Programming and Control....53
- The Great Catastrophes....53
- I was brought into the Time Program....54
- The Effects of Temporal Manipulation....54
- Temporal Influence....54
    - Simultaneous Interaction and Incorporation....54
    - Retro-Causality....54
    - Quantum Holography....54
    - Time Paradox....55
    - Breakaway Civilization....55
- Underground Cities....56
  - Technological Advancement....56
  - World-Wide Control Systems....56
- Solar Warden....57
- Team Light and Team Dark Non-Interference Agreement....57
- All Contact Must Be Initiated On an Individual Basis....57
- A Singularity of Change and Awareness....58
- Advanced Technology and Ancient Knowledge....59
    - Cloning, Atmospheric Civilizations, Genetic Stability....59
- Training, Simulations and Learning....59
    - Cloning and Cerebrally Enhanced Soldiers – MILABS....59
- Psychological Testing....60
    - Hallucinatory Holographic Mind Probing Technology....60
    - Virtual Simulator Training Scenarios....61
  - Combat Simulators....61
  - Conditioning....61

    - Programming and Resistance to Psychological Trauma.....61
    - Accelerated Mental Functioning.....61
      - Technology, Accelerated Learning and Repair.....62
    - On Orgone Energy.....62
    - Energy Generators and Serums.....62
    - Genetic and Cybernetic Enhancements.....63
    - Developing The Self.....63
      - Multiple Factions of Space-Fleets, Multiple Goals.....64
  - Large-Scale Catastrophes or Series of Meltdowns.....64
  - Unsustainable.....64
  - Earth Changes.....64
  - Mass Consciousness.....64
  - Wars and Manipulation.....65
  - Financial Unrest (or reset).....65
  - Self-Responsibility.....66
  - Clones and Synthetics.....66
  - Spiritual Power and Divine Truth.....66
  - Synthetic DNA, Synthetic Genetics.....67
  - Time as Mathematics, Series of Equations, a Programmable Storyline.....67
- Chapter 2.3 Previewing Solutions.....68
  - Neutralizing Polarization.....68
  - Removing Etheric Implants.....68
  - Clearing Astral Body.....68
  - Knowing the True Self; Soul Actualization, Unveiling.....68
  - Taking Responsibility.....69
  - Returning To Center Emotionally and Mentally (spiritually).....70
  - Vampires in the “Awake” Community.....70
  - Heart Center and Psycho-Spiritual Fulfillment (self-actualization).....71
  - Go Within to Observer the Self.....72
    - Organic Feedback Loop.....72
    - Technological Feedback Loop.....72
  - Breaking Soul-Contracts.....72
  - Help Everyone.....73

Chapter 2.4 How Timelines Collapse........73
Repeating Cycles of Time........73
Beings From the Future........73
Beings From Collapsed Timelines........74
Beings Who Would Never Have Existed in the First Place........74

Introduction

The following is first-hand testimony from an operative of the secret underground military projects who also has familiarity with the breakaway civilization above and below (within) Earth. These civilizations utilize advanced technology to extend the length of their lives and enhance cognition beyond what is conceived of in today's society.

I was brought to the underground bases as a child as part of an experimentation program to test the population for various blood-groups and personality traits that would be of use to certain factions of the military in ways that would serve to preserve and strengthen humanity's outlook in the future.

These tests involved everything from combat training to sensory deprivation based emotional-mental endurance, and introduction to the highly advanced application of esoteric knowledge.

To clarify, I am bringing this information to you as part of my assistance in the overall unveiling of the hidden knowledge of the ages of humanity related to these secret projects as well as the true galactic history of Earth, humanity and man-kind. These projects are officially (unofficially) known as "unacknowledged special access programs". The unacknowledged aspect means that there is no formal acknowledgement of these programs without a need-to-know basis. There is no paper-trail, no disclaimer, no formal authorization or internal publication outside the programs themselves. The classification of these programs also generate a rather strenuous situation regarding funding and secrecy but this is done for the benefit of humanity. There are secrets and manipulations that can be seen as a threat but this is all tied together and so by releasing the secrets that are part of the defense we would be inadvertently exposing the public to the threats themselves. Now is the time where we are reaching a point where the public is ready enough to handle the basics of this information regarding the secret projects and the galactic history of Earth and humanity. This is also out of a necessity to preserve civilization for if we wait any longer we may not find the same opportunity again.

Getting This Out Of The Way

I am writing to you from the perspective that I am not certain just how far from completing my mission I am. I write to you today in order to bring to you many personal experiences from the viewpoint of an operative of a select ultra-military secret society.

The utilization of such an operative is not glorified, pleasant, or entirely righteous. This story entails sanctioned and guided acts of extermination, ritual abuse, the use of yet to be announced advanced technology. There is unfathomable corruption, the thirst for power and spiritual knowledge that has been protected throughout the course of the multiple civilizations that have preceded this one and will continue to be maintained into the future of this civilization.

Psychic Operation

I was utilized in psychic-operation amongst other areas.

This was used during certain aspects of training and conditioning to enhance training and conditioning in the bases using advanced technology. Some of this includes what would be viewed as traumatization by those without the training and conditioning. There is a fine line between training and conditioning and abuse. Part of this disclosure is related to how this line may have been crossed in certain situations and regarding mass-mind control upon the population. There are other aspects of travel, viewing, reconnaissance and research that will likely be explained in another release.

In order to heal I have to tell the world. You can help. This is happening right now in the underground bases and around. It’s not a joke. Your family is at risk. Your future generations are at stake. There is conditioning to encourage those involved to believe they are performing a duty for humanity. Sometimes they turned us against each other, but those grudges were never truly of the heart, but the mind.

A Light for the Others

What I hope to achieve with this is a smoke signal for those who have also been involved and question whether their purpose has been fulfilled or falsified for the protection of a corrupt system that intends to neither benefit the whole nor repay the individuals involved for their time, energy, and lives.

Multiple explanations can be summoned to describe the reasons behind the necessity for the training we have endured, the missions we have completed, and the control mechanisms we have both assisted in establishing as well as suffered from the backlash of. Ultimately, it is of my belief that all that was done was done for the good of humanity, even when we were not sure of the intentions of those in front of us, to the side of us, or behind us compelling us forward with the command to complete each objective.

This is not so much a panic or cry for help as this is simultaneously a call to awaken and a signal that humanity may have avoided complete disaster but is not out of the woods yet.

Natural Security

My experience is far too vast and I have seen too many succumb to stress from the realization of the truth of this reality to consider my own suffering to be enough cause for my denial of the necessity of these programs. Humanity has been protected and at a great cost to those who have been on the front lines, both in mind and body and spirit.

There are many who will have concerns, doubts, as well as reservations about what I am about to reveal and if I offend anyone then know that my intentions here are to assist in unveiling the truth. The truth can be harsh when one has been held back from the true nature of existence for so long. The way of life can become so fragile and artificially constructed on impulse and mystery that the harshness of the truth acts as a great catalyst for spiritual growth which allows us to elevate ourselves to a new perspective. Prepare yourself for such harshness, prepare yourself for growth and elevation, and prepare yourself for the mystery to simultaneously resolve and increase in intensity and magnificence.

A Balance of Mystery and Truth

Mystery has been a way of life for Humanity for so long that when a great mystery is converted to truth some seem to feel that a portion of existence dulls and loses the luster of exhilaration. This story is quite the opposite. The more that the great truths of this reality were discovered and revealed, the more complex and mystifying life became. As well, the more empowering and complex experience becomes, the more self-control one must develop in order to regain a harmonious way of relating to one another, the self and the universe. Harmony is key, balance is everything and there is a light within that represents the piece of our self that reflects the utmost power and brilliance of all existence.

Chapter 1: The World Situation

What is happening?

The Mind Virus

The main reason for this disclosure is to inform humanity of what can be referred to as the “mind virus”. This is a viral infection of the holographic system which consciousness operates through. There is a complete backstory of this virus in the history of this civilization and how society has been plagued for centuries if not millennia. The basic idea is that this virus operates through consciousness and can be transmitted through electromagnetic waves.

The virus contains an etheric form which can manifest as a kind of crystalline nano-tech on the physical plane and this is a form of synthetic sentience which feeds on the low frequency bio-emissions of sentient life. Human bio-emissions contain energy and can act as a carrier for information and living essences. This technology requires low frequency bio-emissions because that is the nature of the design as a kind of synthetic bio-weapon whereby the goal is entrainment and enslavement. As well, the specific nature of the sentient nano-technology and the counterpart etheric holographic form is only capable of converting the low-frequency bio-emissions into energy as the higher-frequency bio-emissions require more energy to contain and synergize with and this would render the entire process of leeching energy non-productive.

This is essentially a synthetic intelligence that operates through scalar and holographic living bio-emission fields and hijacks electromagnetic emitters to position itself within them acting as a parasite to a host. This is said to have been present around this civilization for some time, waiting until there was enough technological advancement so that spreading across the entire civilization in a short amount of time before discovery would be possible. This is through the media, internet, and radio systems.

The physical counterparts are microscopic nano-technology parasites functioning as individual units to a hive mind similar to the mycelium of fungi in the field of mycoscopy. The individual units act as parasites serving to infest and deliver nutrients to the hive from each host.

The Vampire Effect

This is the nature of the parasitism that has been present throughout the ages of this civilization feeding on human suffering and relying on the cover of confusion and misdirection to survive.

There are processes that have developed that assist in the infection and co-inhabitation of the parasite entity within a human vessel utilizing the human as a host. This effectively utilizes a frequency ‘net’ within the auric field of the human to limit bio-emissions and emotional-mental processes to produce just the psycho-etheric patterns that the virus can sustain itself within and through.

This is no different than the way candida can infest a human digestive system and the human will experience cravings for beer, candy, carbs or other foods that contain the sugars, yeast, or carbohydrates that will break-down into nutrients that are the most nutritious for the candida fungus. These foods are *not* most nutritious for the human body. Yet the human body will withdraw and crave these foods in greater amounts until the fungus is swept clean from the digestive tract through probiotics, fasting, flushing, cleansing , detoxing, and even exercise as lactic acid from physically strenuous activity released from the muscles has been known to help destabilize and remove this fungus. Why is it that the individual will crave these foods that are not the normal food intake? Because this candida fungus can infest the host and produce enzymes which generate a chain-reaction which leads to the chemical signals in the brain producing the sensation of extreme hunger or cravings for just these foods which will benefit the fungus.

The same process occurs with this psycho-etheric parasite, except the foods of this parasite or lower emotional bio-emissions and this is through lust, hate, angst, jealousy, feelings of hopelessness, lack of self-worth, spiritual degradation, addiction, and generally all that equates to a lack of self-awareness.

Whether or not this is the direct intention of the largely microscopic entity is for the most part unknown, and this is as well similar to candida. The candida fungus is not said to be a ‘mean’ fungus that wants us to be hungry and craving beer and sweets all the time because it likes to ruin the human body, the daily routine and the focus of a clear mind. This is simply the way the parasite has grown to operate within a niche of breeding itself through the digestive tract of larger animals and through this the unaware and infected human suffers greatly. Even those who are unaware and not infected can suffer because of the way the behavior and thought processes of those who are addicted to these foods can become distorted.

The lack of self-control over food intake is synonymous with the lack of self-awareness and self-control over lower bio-emission expressions of the spiritually degrading behavioral patterns that become routine for the psycho-etheric system of the infected human. Ultimately, this is all about energy. What benefits the parasite that seeks to gain energy by leeching instead of self-guided production is going to take away from the host that is being leeched from. As such, any energies, food intakes, or spiritual activities that cleanse and enhance the personal power of the individual will automatically reduce the parasite’s ability to feed by the very nature of the energy systems. What empowers the individual, empowers the self and develops self-control, what develops self-control contains one’s energy and reduces the likelihood of one’s energy being leeched. This is similar to energy vampires in human form and this goes with the understanding that these are humans or non-humans who have been entirely overtake by the parasitic consciousness and cannot sustain their own auric fields without having to pull from the energy of humans who do generate their own aura or bio-emissions.

The vampire effect relates to how a person can be leeched from only to a certain point. Once the process surpasses a certain critical point then the individual becomes similarly engaged with only the lower bio-emissions as higher-frequency bio-emissions would then become harmful. So in essence, when the vampire feeds too much on one individual, then that individual becomes a vampire themselves.

Sub-Human Entities

The humans are utilized as hosts and energetic sources in this bio-emission battle while there are other classifications of bi-pedal organisms that appear to be human but are not human. As well there are bi-pedals that are non-human entities entirely.

Human-Hosts, Replicants, Synthetics and Carriers

The human hosts that are entirely vampirized by these entities become walking carriers for this virus and are effectively human in physiology but there is more to the human than just the physical body. In these individuals, that energetic component of the human is removed and replaced with the synthetic energy of the hive-mind organism.

There are replicants which are a form of clone, along with synthetics. These beings are cybernetic bi-pedals similar to humans but their energy is too not from an organic biological matrix but a technologically propagated synthetic soul-matrix. The hosts are here according to their agenda to subdue and feed off of the bio-emissions of the human race, although there are no absolutes. The agenda is not always so clear within the various groups who often have a mix of bi-pedal operatives. There have been plans to form of a salvation timeline because the only way to keep the whole process going is through a negation of degradation of the human race as this may close out this timeline forever.

Those with human organic soul-matrixes would simply transport into the next available universal time-stream or harmonic, while those with synthetic matrixes would have to technically travel to the next harmonic using a passageway otherwise they would remain here throughout a zero-point collapse and this would be synonymous with entering the abyss with no viable passageway out until the entire universe is brought back to one organism again.

This is also the process that is described to explain what happened previously as there are 7 harmonic temporal layers of the universe meaning everything is contained in a multitude of 7 octaves similar to light and sound frequencies or harmonics. And so there are 7 civilizations or 7 parallel time-streams and humanity passed through these to get to the last three where the physical forms are located. These are, from the higher to lower, Gaia, Tara and Terra. We are on Terra and if the information I was given is correct then we are currently on a transitory timeline located around Tara where people are noticing changes occurring and multitudes of aspects of the time-stream disappearing and changing simultaneously. Tara is where the last universal harmonic was left through a collapse of time and consciousness into zero-point and this resulted what was termed “the lost souls of Tara”. These are the discarnate souls of the previous civilization that could not travel to the next harmonic and remained without a body in the abyss. Thus they have plagued this plane since then, since ancient times possessing and driving humans to madness and there are explanations that this is the original passageway for the parasite into this universe. This event, the consciousness collapse of Tara would have acted as a fracture in the over-mind of the species generating a kind of cosmic schizophrenia and enabling all kinds of disharmony and distortion described in the previous sections.

The solution to this was described as a healing process that is taking place to purge the virus and that this is painfully similar to the human body purging a sickness however there are methods to promote healing and reduce suffering and confusion however people must contain themselves and their energies and strive to know themselves otherwise they will not be in control. This virus feeds on fear, confusion, spiritual degradation and the energy from degrading acts, lust, addiction, sexual misery and whatever fashion a human can be made to bring the bio-emissions of the energy centers down to a low enough level where co-inhabitation can be formed with an entity that has no access to the higher levels of self-awareness, higher-consciousness, love, or the universal spiritual experience that the balanced human is capable of.

Genetic Manipulation

There are explanations that there are genetic modifications taking place now to possibly preserve this civilization and that there were ancient genetic modifications made to induce a sense of stupor, worship, selfishness, an inability to more easily comprehend the higher spiritual awareness and the occurrence of time and consciousness and other spiritually and consciously limiting aspects. Part of this explanation is that holographic consciousness itself is a kind of limited result, a shadow effect resulting in the presence of the higher-dimensional essence of the soul which is more or less constrained by the body. An extension of this is that the entire holographic universe is a kind of false-light system designed to bend the original liquid etheric light of the soul and spiritual awareness into a rotating, recurring format which ultimately converts the original spiritual essence into an energy generator for entities that are entirely holographically represented. The souled human in this situation is a being who is originally from outside of this holographic projection.

The Ego Mind

In this view, consciousness is the ego-mind which is the false-sense of self, not to be confused with the shadow self which is simply the counterpart of the aspects of the self that we consciously agree with and are aware of in daily life. The shadow self is a result of having limited holographic consciousness and the ego-mind is projecting that limitation of consciousness into the shape and image of a self that is only a figure-head for the real individual essence which is spiritual in nature and immortal.

This Time is about Healing

Everything that is happening now is to motivate people towards healing and unification. This is not about a hive mind mentality where individuality is pushed out.

> "The best I can do for you is become your enemy."

There is a saying that represents the concept that the most beneficial role a person can play in helping one to progress is to challenge them and give them the opportunity to rethink their strategy and in turn improve further with each interaction. This may seem paradoxical but it is effective and explanatory. What we are facing is the greatest challenge humanity has yet to face. This is the unknown, the final frontier, the mind. The mind is our challenge.

There will be more on this later and in other publications but there are indications that the physical embodiment of the human has been altered to introduce implants, genetic modification, susceptibility to disease and ultimately fear-based programming of the brain. Without going further into this prematurely, the lower aspects are at odds with the higher aspects unless we as the midway come forth to mesh the two together in equilibrium. Until then, there is chaos, lack of self-awareness, and suffering.

There are many possible futures converging at this time. There are some less than favorable paths and there is the opportunity to merge with a very powerful path for humanity. This all comes down to how people will cope with information that takes them outside their comfort zones and eventually changes their view of mundane reality forever.

If people choose violence and lack of self-awareness by ignoring the spiritual aspects then that is what reflects into their life experience. When people develop a higher sense of self-awareness and spiritual harmony they can reduce the suffering and reconnect with the lost aspects of our spiritual identity for the first time in the publicly accepted version of recorded history.

There is technology that can change the world and there are great truths which can enable people to know themselves in ways that they never thought possible. Everything is at our fingertips and so we must come together as this is the way we solve the problems and cure the dysfunction.

Healing Through Unity

In various research projects the conclusion of how to heal this spiritual rift was by exposing each other, to each other. When we are all together, aware of each other and our selves, united in the goal of bringing higher-awareness and spiritual harmony then we can observe and acknowledge when one is slipping into chaos or disharmony. When this occurs and we are in proximity to each other in a healing circle or a kind of social unification then the members of the group at large can work together to pull the chaotic one back into harmony towards the group. The group of healers united together in like mind, spirit and body is too strong to be overtaken by the parasite. So when one individual at a time is faced by this problem the whole group can come together as one and assist in healing the individual by pulling them back to reality, back to wholeness and back together with the group. This is literally how the situation is solved in all realities and a breakdown of this feature of society is how the dis-ease proliferates.

Underground Bases

The active aural research program is part of a process to simultaneously verify as well as initiate and demonstrate controlled insanity/sanity.

These programs utilize the deep underground military bases to perform psychic and psychological research experiments on non-consenting youth and adults as well as consenting participants.

There are various means of generating the illusion of consent or even lack of consent and this is all being monitored and handled by oversight authorities.

These operations are directly related to the identification and understanding of the mind-virus and all weapons, defenses, and resistances known to man.

Cloning

Advanced technology is used to transfer consciousness from one cloned body to the next so that a continuous study can take place before, during, and after the death experience of one individual. More will be explained on this later, however this is through the use of advanced supercomputer systems that can function to entangle and then transfer the electromagnetic consciousness of the individual so that they are ‘remotely activated’ within a cloned version of themselves via a ‘brainchip’ (brain to machine interface: cybernetics).

Celebrity Cloning

Celebrities at the cloning center would like you to see what is really going on behind the scenes which involves trauma-based mind control, heavy technological programming and complex layers of influence throughout their life.

Initial Explanation

Many celebrities, entertainers, athletes, musicians, models, writers, producers, actors, all kinds of people from various industries are silently brought to the cloning centers for pay-to-play sessions.

They asked myself and others to pass the message on to you and that you would have to look for the signs and symbols in their media in order to see their hinting at these events.

The situation is heavily controlled using advanced monitoring technology and brainwave/EEG cloning technology. This is technology that can read the brain and determine what the mind is anticipating or speculating upon.

Their reputations are used as leverage as well as their safety and comfort. The level of programming and mind control experimentation that takes place makes it easy to manipulate a person’s brain into regressing into a state of trance that lacks the ability to remember or clearly organize experiences regarding the cloning centers.

Cloning Centers, Underground Bases

Deep underground military bases, 3 miles below the surface, are used as laboratory centers as well as a completely stocked underground city-base. These are connected with high speed electromagnetic drive pods.

Individuals are transferred to the brain through an extensive cloning and temporal body transfer process. The electromagnetic shell of consciousness within the brain is relocated to the body of a compatible clone and various training, conditioning, programming, experimentation, or pay-to-play experiences take place.

Programming

All individuals are programmed to various degrees in order to maintain control and secrecy over the situation. This programming involves very advanced technology, trauma-based mind control, and energetic attachment via beliefs and emotions.

Experimental Operations

These bases were also used hand-in-hand with military operations which were geared towards discovering and controlling all aspects of the human mind.

Genetic Engineering

Experiments involved genetic engineering to produce soldiers, psychics, hybrids, and others that would be able to carry out operations. This leans towards MiLabs and the military faction’s experiments which go beyond the basics of cloning.

Immortality

The initial research included the goal of physical immortality. In many ways it can be said this has been achieved, however there are side-effects and difficulties.

If one does not activate their higher consciousness, then the effect of time dilation causes the conscious mind here to reach limitation points in experience.

What has been termed “blank slate/state” technology has been used to ‘reset’ the perception of time through memory in order to keep a continuous progression viable for the conscious mind. Without this the unconscious and the conscious mind merge.

This begins involvement across time with advanced technology that can operate on the soul level or the conscious mind’s level of access to the unconscious and soul-memories. The Universe instantly creates a cosmic backstory based on the conscious-mind’s access to the unconscious. By controlling the conscious mind’s access to the unconscious the entire backstory of Humanity can be altered and new connections can be bridged in the future.

Earth is essentially a time-ship through which consciousness ascends towards higher states of awareness and self.

How did it get to this?

After WWII when the United States war-faction firebombed Germany and melted many of the inhabitants of the cities into sludge in the bomb shelters and streets of the cities, a group of NAZIs traveled to Antarctica.

Russia noticed the movements to Antarctica and the United States sent Admiral Byrd up with 3600 marines, planes, a battle cruiser and smaller vessels. They returned in defeat and only a few words were mentioned in regards to what actually happened and how they were defeated.

The rumors spread and words of gravitic drive craft, and undersea or under-ice bases originated from this encounter.

From what we were informed as well as directly experienced, this was the ice-base in Antarctica where an underground base was found already constructed with very advanced technology.

Here, cloning was deployed along with mind control and temporal manipulation technology.

Soon, cloning was offered as a way to avoid assassination as well as to prolong and protect the original body in daily life.

After that, celebrities and politicians were replaced with programmed clones who could carry out the orders of the NAZI faction.

This was the beginning; the groups utilizing this technology now are no longer confined to the NAZI faction.

The groups you see today, in control of these operations, are considered MiLabs, secret societies, think tanks, military factions, and other control groups.

Deeper Meaning

The individuals that have been cloned are given very in depth views of the way this society functions and the source of power and change in the Universe. Many individuals are present here from what would originally be another “time” or “timeline”.

There is a possibility that this notion is due to inserted memories and traumatization although until all the information is released we will not have a definitive conclusion.

As of now it is a possibility that these individuals are from another time that goes beyond our comprehension currently.

It may even be a possibility that these individuals have come from ALL of time looking at the very far past and into the very far future of Humanity.

These are the kinds of notions involved with the experiments taking place in the underground bases and military operations.

What is next?

Share this information with those you feel are ready to know and help Humanity come to terms with our journey here and what is going on in these kinds of experiments and take responsibility and power for our own existence.

We are in something that can be called “The Unveiling of The Hidden Knowledge”. This is a cyclic process that takes place to advance a civilizations knowledge of existence. As part of the civilization moves into higher advancement another aspect may lag behind. Either the future will slow down, or the past will speed up. We are experiencing the past speeding up and all the events that have taken place to influence our civilization are coming to light. This is as much a natural cycle of consciousness as it is the eventual revelation of secret knowledge and the particular connection to the secret projects.

> *Those brought to cloning can use their free-will to state their lack of consent to violence and harm and then live in commitment to that by not harming or accepting violence in their lives. The Spiritual Law of Harmony rules in all planes and dimensions.*

Chapter 2: The Awakening

Chapter 2.1: The Machines of All Time and Space

There are machines that are capable of accessing genetic memory and unveiling what can only be referred to as the experience of awareness or existence in between the physical planes of each time or each physical life experience.

Even if they are simultaneously occurring moments of a transcendental nature, there is still an illusory ‘space’ where there is perceived separation and through this there is a perceived ‘space’ that is in between each existence.

Re-Creating The Kaleidoscope

This space is only perceivable when viewing from the physical perspective, like seeing the spaces between the angles of a kaleidescope only when viewed through the lens and similarly, technology can be used to recreate what this kind of illusory space might look or exist like in between the multi-dimensional realm of the continuous experience stream. Through this, these ‘hypothetical’ in between spaces that are understood as only illusory productions of biological consciousness, can be generated through advanced technology with the capacity of recreating that kaleidoscopic view of which the human biological perspective is only a small fraction or even fractal.

By recreating this biological perspective, they can recreate the illusory spaces in between planes and through this they can literally access and experience what are stored in the DNA as the experiences of existence beyond the physical limitations of consciousness and into a multidimensional experience of time and space.

All becomes a never ending sea of consciousness, however this is the given. The trick is to take from this sea of consciousness and slice it down into conceivable chunks from which you can reintegrate a previous personality or identity and continue on a stream of consciousness that would otherwise be tossed to the cosmic wind like fractal stardust as the sands on the beach of hyperspace.

Sand-Castles of Time

We are effectively building sand castles out of these sands of time that would otherwise be swept back and forth into and out of the ocean of life and the universe only to momentarily wash up again as the identity which we once knew.

There is technically nothing wrong with either view, because then, the spaces between each million year occurrence of just so happening to wash up again as you, would be imperceivable because they are only there to be seen when you are you again.

We’re Waiting For Ourselves

Yet, if there were some who had attained the awareness of the true nature of reality and were standing there on the beach waiting for the rest of their cosmic family to come to shore again, it could be perceived as waiting the majority of the time for a very small occurrence and then being alone again up until the kaleidoscopic fractal inverts itself to the point where everyone now is standing on the shores of the sands of time rejoicing and meeting with each other.

The Goal of Two Societies

My goal in coming to you people on the surface of what is called “Earth” is to help assist in the process of bringing the two societies together, one who’s been waiting for thousands of millions of years, and the other who has no idea that they’re even late (or very on time).

You see, those are the only two situations where there could be even the possibility of perceiving such an injustice as experiencing the pain of loss or misconstrued identity in this universe. It is as if two families met at the cross-roads at different angles, and while one waited for the other to arrive, they could merely supply themselves with glimpses of the ruins and remnants of the evidence that the other civilization existed at any one time.

This is not how life must be and this is kind of like a cosmic waiting game of hide and go seek our two mirror civilizations have been playing with each other. One who’s highly technologically advanced and the other who is more or less the spiritually advanced of the two.

Both of them have a unique view of the universe and they are both only complementary to each other as a whole. The more they sat around and waited for one another, with one leaving the clues that the other would find and even switching roles sometimes in different ways, they became even more and more complimentarily associated as the very essence of experience they seem to be missing more and more is the experience of one another.

So as we perceive these as being great losses or great gains of time and culture we are really only remembering ourselves and coming together as a unified existence that once met upon the surface of Earth as a single family covering the entire harmonic spectrum of the Universe.

And that should be the goal of any progressive, any one pushing a new culture or an old culture, anyone looking to teach the young and protect the knowledge of the old, while also protecting the innocence of the young and perfecting the age-old knowledges that have defined our presence in reality.

Our Forgotten Other Half

One could even say we’ve sometimes gone off the deep end, leaving ‘land-minds’ of sorts to process the information that would be present when we are gone. Of course, what we could’ve found when this occurred, is beyond anything we could’ve ever expected and that is the true nature of the complexity of creation and existence. That everything follows the cycles of creation and destruction, however, the memory of everything that has been created can always be accessed (depending on the beach) and therefore the creative aspect is legitimate, yet it is the destructive aspect that is illegitimate and illusory.

Yes, through advanced technology this can be proven in ways that can be verified and transmitted using advanced technology, since that is how we like to verify things these days. There is, of course, a human looking at the screen, the read out, or the situation from a physical perspective to verify the verifications.

All Is But An Illusion

There is a notion that there is only one civilization, one society, in actuality that has been chasing itself through time. That we cannot actually find the same place and the same time where both meet because we are each other from different perspectives. We can only get a mirror where this is possible, or an ‘hyperdimensional’ internet channel where we can stream one’s consciousness in from the other reality and interact with them through that here in this reality. Thus the two civilizations can achieve the experience of their own civilization and the other civilization by merging with one another but only through a remote contact, just a relay, not an actuality.

The harsher, darker side of this is that any civilizations between then and now that we did happen to meet that proclaimed to be “the one’s” we have been waiting for, and in essence our darker or lighter halves, are actually the impostors who exist entirely apart as a sub-set and have taken a liking to trying to trick the reality out of one of the other civilizations.

Of course, if these are another form of being altogether, and this is all brought about through an interplay of consciousness and deviations from an original core reality, then all will resolve itself when that core reality is alone again. This indicates that all realities will either move closer and closer to the core until they unify, or farther and farther out until they transmogrify beyond recollection.

Life Itself Is The Highest Illusion

That hyperdimensional internet channel that is created out of advanced technology to merge the parallel realities (rather distastefully and maybe disastrously at times) allowing different civilizations to interact with each other, well this has been created using technology.

But then it was discovered that this is the ultimate nature of DNA. That this was ‘invented’ similarly as a higher-dimensional internet so that various natures of different planes and dimensions could interact with each other and experience the richness of life.

The universe becomes more like a living arcade game then, where people come from all over the galaxy to ‘plug in’ to human experience and figure out what it means to be physical, human and on Earth.

This does tie into the larger nature of reality, of star-races, and of time and consciousness that is often reversed according to how things seem to play out in physicality. We are moving through time, but just because we are moving one way, does not mean that others could not be moving the other way.

We have to live our lives with meaning knowing that the message we pass on, the duty we vow to accomplish and ensure is meaningfully connected on either end to the passage of the past and the power of our ancestors to the function and knowledge of the future creating a clear passage between the realms, the generations, and the ends of the universe. This is what literally ties the universe together, and the mind if each individual. This purpose is contrived when not carefully shaped within and so we must help all who seek purpose learn to become the blacksmiths of their own destiny through the temperance of desire or temptation and the discipline of developing strength and maturity where there was once weakness and naivety.

Once we know this is our duty, this is what we seek to achieve and this is what is done, then we can become part of the universe forever. Of course, this may only be temporary in the larger view of things.

Chapter 2.2: The “Awakening” of 2010

In 2010 I was “awakened” at an event involving hundreds of people that play various roles in this society, the secret society and the breakaway civilization. This also took place across times or planes of reality.

During this event I was informed of the situation on Earth beyond the informational barriers that were previously in place to limit knowledge to only what is required for specific operations. I was essentially “informed” of the entire situation as much as the mind could handle this.

As this was occurring, the team that was updating me on the status of Earth was being informed of and given information regarding changes in the future. In short, interviews, posts, and releases that I have since made and will make in the future were touched upon. Quotes were given from the blog and interviews which were jokingly acknowledging verbal mistakes at the pronunciation of names, new perspectives and interpretations and more. As they were informing me, they were creating the future reality where this work takes place. That is the basis of this layer of the operations. They are creating the future person by person, layer by layer.

Memory Suppression

My memory was unsuppressed and all the traumatic memories and experiences were unveiled to me. This was almost as traumatic as the initial experiences themselves although precautionary steps are taken to ensure the safety of the individual. There are teams of highly competent individuals of all kinds with professional backgrounds of every field imaginable.

Throughout my entire life I have had memories of experiences, at this event I was informed what the experiences meant and what was actually happening. I've had memories of underground bases, cloning, stargates or interdimensional gateways, advanced technology, non-human or programmed biological entities, sacred knowledge and experiences, the power of the mind, and breakaway civilizations. Most of the time we are conditioned to believe these are past lives or experiences in another reality so as to enable continuity of operation.

Life and Consciousness

From my perspective and the perspective of others, we had reached the 'future' and had been sent back through the utilization of advanced technology and cloning to return to this time and inform others of the possibilities.

The True Human Potential

This is so far beyond what anyone can accept or comprehend fully that humans with an emotional, mental and physical aspect balanced as one is literally a cosmic reflection of the entire universe at once. This is the closest thing to a "god" in the flesh. And be sure, the entirety of this rests on the behalf that the man is protective and helpful. That the woman is nurturing and loving. That is the point. "god-man" does not mean a warrior who destroys everyone and anyone in his way getting what he wants. Nor does it mean some lusty and vampiric form of energy or mind control game. "god-man" means the love of the universe, the power of the body and mind, the peace and calm of the ultimate stillness all in one.

This power is in human DNA, originally so. And so this is awakened through walking the middle path of neutrality and 'splicing' the timelines down so that neither one nor the other gains the power of the individual. Through this, the individual creates their own power, right on the spot, without having to lean to one extreme or the other. This is like a cosmic, temporal balancing act with emotions and mind. Where we give our energy is created in the universe in the form of many productions and effects. If we are simply thinking in an imbalanced manner then we are producing timelines and side-realities that exist in the etheric realms that we can't see and these realities will reflect our inner imbalance. So then when we are balanced in our energies we are not creating one or the other side of divinity, we are literally creating the whole universe, cleaving down the middle and producing both sides of divinity or eternity equally and this is the only way to have an eternal production which does not eventually degrade to one extreme or the other. Through balance, we reach eternity and in this way all the power of the universe exists within a person through their ability to balance their emotions and mind and thus unlock the DNA.

The DNA is coded through bio-emissions of mind or emotional body. So we are constantly doing this and we are either producing a DNA code that reflects imbalance overall, or a code that reflects the eternal balance of the universe overall. This is through energy.

One reaches “heaven” or the deity planes or simply self-actualization, through three paths. These paths are through merits or devotion to principles, or through knowledge and expanding one’s mind to face the universe, or through great works and deeds to produce this effect of power, knowledge and emotion unto the world for others. Through these paths we create an impact on the universe and this transfers what we are temporarily and physically into an eternal energetic and physical production within the living universe, forever. To do this requires balance, focus, devotion, and discipline however because there are many distractions along the way.

The Light-Body

You must build your own light body. That is how it works.

Your heart creates a field and projects you.

Rely on yourself and use that for protection.

The power of the Universe will align with you if you align with your self.

Learn as much as you can and break through duality of love/hate, cultivate your knowledge of the self and use it.

What you want is what determines your power in the light-realms. Not how you want it. If you want war, then that is a sign of weakness and determination to produce imbalance and exist by that. If you want peace, that this is a sign of power and unity to produce further unification and exist by that. What you want determines your power, not how you obtain it.

Technology of the Awakening

Mental Manipulation Technology: Touchless Neural-Interface and Enhanced Awareness

I reached what the “Illuminati” called the “awakening”. I feel a better term would be “unlocking” as this event includes the removal of all traumas, perceptual distortions, and memory suppression.

This event was a presentation of very advanced technologies which allow the mind to transcend space and time. It was shown that death is similar to a phase-shift of consciousness as polarity and that the awareness of the being obviously continues. This was verified through advanced sensing devices which can visibly display frequencies which are invisible to the physical senses. This is also something that occurred earlier on as a child in the underground bases by transferring consciousness in and out of the body at will using advanced technology.

With these devices it is possible to see the “auric” or soul field of the individual. Any living body has a field which glows when picked up by these sensing systems. This field becomes more refined when viewing more advanced beings. Human have an extending mental field, and through this a kind of glowing awareness that is picked up. It can be fairly simply compared to thermal imaging except instead of differences in temperature it is the presence of a soul or mental energy field around a living body. The finer energies extend outward away from the physical body.

More than once, the situational requirements were satisfied in order to produce an ideal environment for maneuvering on the non-physical plane. This is the basis of how the temporal operations occur, yet these events were different than previous operations or experiences. The group I was in was going through the process of increasing the vibratory emissions of the “bio-mind” in order to stay focused on the increasing vibratory rate of the environment. Generators were utilized to create an effect on space/time which was perceived on the “soul” level. These events went into the discovery and explanation of the creation of the “godlike” powers of the advanced sentient technology which was capable of accessing the holographic nature of reality which humans can perceive through their bio-mind/soul. These technologies also enable one to perceive what is referred to as the “galactic history” of Earth and humanity. We are far vaster and Earth is far larger than people are lead to believe.

Time Dilation and Temporal Recurrence

Time dilation capabilities were shown which allow for accelerated learning of advanced and detailed material within a very short amount of time. This could be seen as a kind of viewing technology which one wears or looks into and vibratory emissions are scalar-linked to the brain which then allows the individual to perceive more information simultaneously. Then there is a very rapid pace of information streamed on a monitor or through a device and this is akin to watching a 20 minute instructional within a few minutes or a few seconds with very advanced minds. The more time is slowed down while information is accelerated, the more stress is applied to the brain. The brain tends to overheat and over stress with high-rates of activity, especially without conditioning. The conditioning is what allows one to utilize their mind and body in these manners. This is not unlike the very rigorous training and conditioning of certain monks or martial artists however there is very advanced technology and other hidden methodologies utilized.

Crystal Technology

These are capable of holding, transmitting, and amplifying consciousness frequencies. There will be a more detailed explanation in a later section.

The crystal technology is used in junction with the power devices to enable a scalar-mind link which allows the interface to be entirely mental or spiritual, IE: they are not controlled by hand but by focus and intention.

Time Crystals

These are utilized as a computer recording chip would be to run a program yet they hold memory in expanded space, IE: they function in a hyperspacial manner and are essentially hyperspacial computers. These are what will be introduced in junction with the quantum supercomputers.

Quantum Tunneling Diodes

This is technology that has recently be released to the public. New technology is developed years ahead of time and then slowly released to the public in a cascade of advancement. This technology deals with superconductive materials which enable the transfer of information at faster-than-light speeds.

The supercondutive material allows for 100% efficiency of data transfer. So what happens then when the efficiency surpasses 100%? This is possible because we are effectively in a simulated holographic environment. The experience is real, however everything is overlayed via particular limitations for the ‘local-environment’ which is like a central data processing limitation. When these parameter are surpassed, one by one, through a coalescence of refinements and methods, the result is akin to a glitch in a computer game system. They have accessed faster-than-light technology and the mind is also capable of this naturally.

With this technology, however, the information can be received a very small amount of time before it is sent. So if a person is absolutely surely going to press the button to send the message, then right before their finger hits the button that message will be received on the other end, as if magic. If they simply play around and pretend to hit the button but very quickly turn away, then of course nothing happens. One can, however, ‘fool’ the universe in other ways and this is simply through the reception and transmission of information across what should be secure information barriers.

Tachyon Fields

These are programmable fields emitted through advanced technology. I was shown how tachyons are the sub-atomic “particles” or energy formation which flows both ways in time. We are receiving tachyons from the “future” in order to layer the flow of time in one direction or the other. Tachyons are the name of the particles/energy packets that we perceive from this perspective as reaching us to initiate the “future”.

Thus, when a stream of tachyons is concentrated and accelerated, this results in an acceleration of the temporal field and we literally experience an acceleration of time. This can be focused and targeted on a specific piece of equipment to change the way information will be sensed and to essentially allow that device to sense ‘ahead’ of the present moment.

The same effect can be produced with the neurological processes of the human as the physical coupling of the brain to the mind can be altered through a concentrated tachyon field to enable the neurological and mental processes to begin to perceive information ‘before’ the brain is actually physically processing the data. Therefore the mind of the individual will be present in the body while the senses and other perceptions will literally be expanding into the future beyond the present moment.

This is highly confusing at first and requires much training and conditioning in order to make sense of enough to operate in any kind of effective manner.

Upgraded Chronovisor

See, “Upgraded Chronovisor”

Time Tunnels

This was developed earlier on and has been the subject of many TV shows in the past and present. The shows are a sure-fire method to get the information to the public without having to force those who are not ready to comprehend. The information is easiest to digest if people think they are watching science fiction.

These are essentially spiraling tunnels of these tachyon fields produced by large electromagnetic field emitters in the shape of a conical tunnel. As a person moves through this field, their temporal acceleration changes and thus their frame of reference within the universe changes. They effectively move their mind through stages of existence or temporal resonance in the universe and this can have devastating effects.

This is an older technique how is still in use and has specific purposes depending on the situation and the information sought.

The “Trip” Chair

The early use of this technology did not use time-tunnels. There was a helmet that was devised which would create a feedback loop of the brain’s activity and funnel this out and then back into the sensory input. This information would be accelerated and redirected to the point that the perception of time would “fold” in on itself until the person would access an expanded temporal perspective of the universe meaning they would mentally temporally dislocate from the initial frame of reference and extend outward further and further in repeating cycles until the same moment was replayed and then all other possible moments in a kind of fractal-like recursive pattern and the very far future would be realized. Essentially, this technologically produced the class “flashing before the eyes” of the entire life experience that is described in near-death experiences and the entire temporal body would be very quickly unwound before the person’s inner eye.

There would be a complete disconnection with the current frame of reference that the collective Earth environment is processing under. That is, this ‘time’ and ‘space’ would be completely out of perceptual reach and a new time and space would be rendered instead. Until the experience had completed, there would be no way to contact this civilization.

There are other versions and ancient versions, tandem operations, more ‘organic’ methods, and modified travel capacities.

Kozyrev Mirror

This is a piece of metal, usually aluminum in early models which simply bent the bio-emissions of the body and mind into a pattern which would create a vortex. The vortex shape and vortex mathematics enable energy and information to travel in across space and time by ‘short-cutting’ the physical plane.

The result of this is that the vortex that is generated over a specific area through an individuals bio-emissions would be capable of interacting instantly with the bio-emissions of another individual who was placed within a duplicate mirror device which was generating another vortex on their end.

The two vortexes acted as a kind of hyper-dimensional telephone cable, literally like a can and string and the perceptions of one another were accessible. There were many uses for this and again, many ancient interpretations of this technology that have been hidden from the public. Nearly every version of these technologies were present in previous times.

Universal Recurrence

This is a discovery that the universe recurs in cycles similar to a wheel or even a washing machine. The washing machine metaphor is fairly accurate and playfully descriptive because without the technology to observer, or an awakened soul of a spiritual adept, people would go for eons without ever realizing that everything in the universe repeats itself endlessly.

When traveling to the far ends of time, it was discovered that one can move far enough away from the ‘present’ or the local frame of reference that ultimately everything is at a maximal informational opposite to what we have today. After this point, everything begins a slow shift back to the present. Through this, one can cycle around again and reach the present by going far enough into the future. This was an amazing and confusing discovery because of the implications about what is actually changing each time, the reality of what are called parallels, the continuity of temporal experience, and basically a ‘recycling’ effect of all experience in the universe. Nothing is lost, but this is also an issue because then nothing is actually ever gained!

Remove Viewing, Temporal Lensing

An ancient device which has been rebuilt and perfected is capable of using these technologies to create a lensing effect which draws a ‘reflection’ of time into a projection system which is effectively capable of acting as a ‘visual time tunnel’ into future probable realities. This is a device which generates a visual portal which allows one to view the future.

This device also exists as ancient counterparts which are located around the world, namely in areas that have been recently sought by the world superpowers. Nothing is as it seems. If you read a story in the public venue then you can be sure that you have read the cover story while the reality is much deeper.

Temporally Linked

The use of the viewing devices which enabled interdimensional lensing of possible futures was found to be stabilizing our pathway into those projected futures. This was enabling a time link between the present and the possible future.

In order to avoid the catastrophes of 2012, the link was broken between the two civilizations and the devices were rendered inactive for this period.

Natural Vortex Energy Locations and Geography

On Earth there are natural ‘time tunnels’ where tachyon fields and vortexes are produced by internal elements. These are mountains, lakes, deserts, fields, sacred sites and other areas that have always been reported as being ‘paranormal’ or containing some kind of specific energy that enables contact with another reality. These are simply naturally produced areas of this vortex energy that produces an interdimensional nexus point through which multiple other parallels can be interacted with. These areas produce an effect on the body and mind similar to the technologies described above.

Most of these effects, from these technologies, change the way light is received or emitted by the mind and DNA.

Mount B.

There is a specific mountain where a base is located, and I have mentioned this before, where the base is so deep within one of these vortex areas that everyone working there is either there for the entirety of their life, or they are only permitted to be there for a very short amount of time. This is because of the acceleration effect. Essentially, if one was to go into the base and work for a matter of hours or day, in some places even minutes, then when they returned to the surface they would be years in the future, sometimes decades or centuries. This is very dangerous and you can imagine the original people who found this area and what kind of situations occurred.

Now with the advanced technology that has been developed these issues can be mitigated and much more control over these effects is enabled.

Particle Accelerator Temporal Manipulation

Using particle accelerators a “fold” in space/time can be made so that when the accelerator is turned off or tuned back into a certain frequency (not sure) everyone within the field will “snap” back in time to the specific moment when the fold was first created.

I have seen this done on small scale, and a rather larger scale, but I cannot be sure if it was only me. I believe I have seen it done on a town-sized scale during the 2010 Awakening where some of the events reached a scale of nearly cosmic proportion and the entire sky and horizon was lit up with technology and entities, as well as Solar Warden, the NAZI faction, secret society groups, and breakaway civilizations or complete other civilizations, some of which were non-human.

This is done using particle accelerators to quantify space on the quantum level (as a reference point with the mind) a frequency would be “folded” into the space time continuum as we “rip” through space holding an access point open at this fundamental level of space/time. This allows for a ‘letting go’ of the frequency, or a ‘snapping back’ by allowing the entanglement to solve itself. When used with generators that propagate out efficiently enough, the effect is akin to a time/space rewinding effect. Some people have noted various theories describing this in relation to the CERN device. These technologies were described as smaller versions of the CERN device and are related to higher-dimensional travel via folding space through electromagnetic fields. This is literally artificially technologically “holding space” for a specific area in relation to a period of time. Time is a more complex notion as an abstraction but by locating the frame of reference this can be applied to distort what would otherwise seem to be a continuous flow. When the frequencies are allowed to “snap back” all sentient observer sources return to the environment they were present in when that frequency ‘rift’ first began. Essentially this creates a replay effect on the consciousness of the individuals within the field. There is no physical effect. The consciousness is ‘regressed’ through time/space, and they re-experience existence from that initial point of contact with the frequency “rift”. This is best explanation I can currently offer however more is coming to the public each day.

This is literally like a “restore point” on an operating system except the computer system is literally the consciousness and space and time of a portion of the local-environment of Earth.

Riding the “Timewave”

There are teams of individual who operate in tandem with the technology of looking into possible futures based on the present and operating through the present via other operatives who are carrying out operations and movements that will construct the various possible realities that the original team of individuals is hopping between. These teams literally “ride” the “timewave” of the future hopping between possible future realities relaying information to the present depending on what movement will be next.

Dematerialization and Rematerialization

This is technology which transcodes the information of an individual human into a holographic projection of light which can be transferred between devices. There is a special system in place that is required to successfully transmit a living human being otherwise just the body will be transferred and the soul will remain, effectively killing the individual.

“Jump Rooms

These are large areas which are capable of acting as a kind of technological ‘portal-gate’ where an entire team can be instantly transported from one area of the universe to another. The space between the two areas are ‘twisted’ like a spiral and then ‘snapped’ back to position and if done correctly with the two frequencies of both locations merging then the team of one room will transfer to the destination pad.

All these methods require training and conditioning, most people are at the very least visibly shaken from the experience which is a bit like being microwaved into a liquid ether and shot through a particle beam at the same time.

Ion Shields

These are areas of concentrated ion emissions and this can be used to create a deflective layer of heated air where light will reflect at a programmable angle. When this occurs, a person standing behind the shield will appear to be invisible to others who are looking straight at them. The light will be bent in such a controlled manner as to perfectly shift around the person in a fluid and equal flow so that the 'bubbling' effect that was noted early on can be mitigated to produce a complete mirage where there is relatively no sign of difference to the untrained eye. An entire group of individuals and equipment can be hidden in the background a matter of yards away and as long as the person is not intently, inspecting each square inch of ground and air they will not notice any difference between the area that is being covered up in the distance and the area directly next to them without the shield.

Similarly a 'screen' of imagery can be projected onto certain materials in the air and a hologram can be projected which will render a background or foreground image. This will work to a degree, and from a distance this will work to disguise an entire horizon.

Instantaneous Healing

There are instantaneous healing methods which utilize various technologies. There are substances which can initiate a complete and real-time regeneration of living tissue from almost any conceivable non-critical injury.

These are chemical serums which allow the cells to replicate at an astronomical rate while suffering damage to the DNA telomeres at repeated use.

There are many methods but mainly the living-light harmonics is one of the latest advancements and most effective at producing healing on a molecular level.

"Living Light" Sound-Harmonics and Electromagnetic Healing

There is a technique for producing a quantifiable scalar wave which interacts with the living cells of tissues and instructs them to repair at a faster rate. This has been called "holographic healing" by others and these are essentially 'living light' frequencies which interact with the cells on the same frequencies that they operate on when healing and interacting with each other. The scalar waves emitted generate the same patterns and this creates an 'ether' fluid that enables them to grow and repair the tissue faster.

Electrogravitic Craft

Advanced craft which utilized counter-rotating torsion fields propagated by very powerful quantum computers and zero-point energy devices.

There are also more modern versions that use powerful electrical flows to neutralize inertial resistance and ‘slide’ through the gravitational field of the crafts own materials.

Energy Cores and Storage Capacity

The hand-held devices that are in use do not require charging or even disposal. The storage capacity of the batteries is so efficient that they last for a lifetime of use. Some devices use an energy generator within the device itself. These “batteries” which are not batteries but little, powerful generators and can explode if they are mishandled.

These are the cores that are used to power many devices and essentially pull energy from the space-time ether.

3.5D Replicators

There are replicators that can produce any conceivable 3D material or object altogether including food or organic material. These use very high amounts of energy to ‘force’ the electrons of the atomic grid of a substrate to shift into the pattern of the element being replicated. The result is a device which can use wave-emissions to reshape materials on an atomic level and produce or recreate any object or substance.

3.5D Sensors

There are sensors that could reverse the process and detect every minute detail of the structure of a body or material. These use energy emissions to detect the structure of a material down to the minute electrical resistance on a molecular level. Similar to diffuse MRI imaging for a living body but more advanced.

3.5D Printing of Clones

It was shown how this technology was used to three dimensionally print human bodies into space/time which could then be used as vehicles for the consciousness or souls of various sources.

Cybernetics:

Neural-interlace/4D Connectome Recording and Simulation

Very advanced supercomputers exist with the capacity to translate the bio-emissions of the brain and body and reconstruct the entire inner visual and sensory experience of cognition and emotion. From this, entire dream worlds can be created which mimic the experience of consciousness. This is most similar to the current day use of diffuse MRI imaging where water molecules are traced through the individual neuronal pathways and an entire digitized image of the brain is developed. The more advanced version described below generates a 4D hologram.

A super computer and advanced sensing system essentially develops one of these connectomes of every connection in the brain. Then this system develops a neural processing pattern that matches the entire memory and personality of the brain.

This is then recorded and extrapolated by a powerful computer system and a simulation of the experience can be observed through the physical body’s memory via a monitor system or the neural interface of an operative.

Essentially, this technology can record and replicate a person’s entire memory and life experience for viewing purposes.

EEG Heterodyning

This is the technology which enables the activity of the brain to be influenced through generating a scalar grid and a carrier wave system which can cause the brainwave patterns of the targeted individual to resonate in sympathy with an externally projected frequency. Thus, emotional states can be manipulated as well as specific thought or behavioral patterns. This works similar to binaural audio where two tones of different frequencies are played through each ear and the brain resonates in sympathy with the difference between the two tones. This occurs with brainwave frequencies and thus the brain ‘slips’ into the frequency of the third tone, the difference between the two being projected. This can be done with ultrasonics and ELF emissions.

Artificial Hallucinations

The neural-interlace can also be used to merge the brain of an individual with a computerized system that will be able to produce effects and hallucinations within the individual.

Through this technology, any stimulus, any input can be recorded and recreated once a functioning connectome has been generated and neural-interlace has been achieved. Entire virtual world scan be created and experienced and after the devices fine-tune the frequencies to match the individual’s brain functions one world is indistinguishable from another.

Brain to Machine Interface Holographic Consciousness System (brainchip interface, virtual reality simulator)

Some of the training is done by entering into a visual-audio dream-world. Some “programs” will consist of repeating a certain task over and over again until it becomes muscle memory in the brain. Others are designed to probe or test the mind until a certain response is received.

This is achieved through the operation of a ‘brainchip’ or a brain to machine neural-interface in the individual which was developed during WWII.

This consists of a small computer ship which merely relays stimulus through frequencies and neural-stimulation of varying kinds. The frequencies and location of each region of the brain will determine the function and thus the chip is used to localize electromagnetic input and the brain's functioning can be modified from there.

As well, the entire psycho-etheric form is vibratory in nature and so through the introduction of vibrations and frequencies from the implant there can be a modification of the frequency of the entire being or what is called the soul or “bio-mind”.

Utilizing The Temporal Body

The temporal body is described as the body ‘in time’ that exists a few seconds into the future instead of the temporal position that is relative to the present. This is as if the ‘future’ is streaming outward from the body as ideas and feelings are as bio-emissions. So this ‘future’ energy is spiraling and streaming outward like a fountain. Thus this frequency can be attained and influenced while the present moment seems unaffected. However, when that individual arrives at what would be seen as the future they would intersect with those influences and this would be as if the interference or effect was streamlined to that future moment.

Manipulation Through the Temporal

This can be used to both produce an effect on an individual who will later feel this effect in the future. Or this can be used to operate outside of the physical plane, in a temporal manner which is literally ‘hovering’ just outside or ‘after’ the present moment of the local Earth environment. This would be as if a person is out of sync of the frame-rate that a viewing device is capturing images of an area with. Because they are out of sync, they are then ‘invisible’ to the capacity for this viewing device to see them. Because they are still present in the same local-environment but simply just out of range temporally, effects can still be produced and this will mostly interact with the person's temporal body.

These are how many operations are carried out as the operative who is interacting in the temporal body will appear to be a ghost image or a dark silhouette that is only perceivable to the mind's eye. A portion of the population is entirely psychically blind, while another portion of the population contains psychic capacity. So those with the psychic capacity would be able to sense and partially “see” as a form of energetic detection when an operative is interacting with the from the temporal plane.

Through this plane one can easily enter into someone's mind and produce effects in their dreams. These effects would not be received on the body but mentally, this leads into astral and mental plane activity. There is also temporal manipulation that can be physical effects that are simply offset to seconds, minutes, months or years in the future. These will be offset from the present aspect of the body in a modulated frame of reference and the effect will remain there in the temporal body until the physical body “matches” the temporal body frequency of that future moment. This is kind like an energetic trail we are leading ourselves up to where the temporal body already connects with each future moment but the present physical body remains separate until the two frequencies are matched. The physical body essentially ‘flows’ forward into each new frequency of the temporal body.

This is the body where temporal implants can be inserted and sustained so as to tie the frequencies down and limit the amount of awareness a person can gain before they manually remove the implants or overload them. Overloading and removing can both be painful however if the implant stays it will at like a governor and transmit access temporal ‘momentum’ or consciousness energy to the owner of the implant and will also drain the temporal and physical body acting as a technological leech as well.

Astral or Light Body

This body was described as a more emotional form of the energy that is emitted from the physical and spiritual system. When a person’s energy is at a high level of activity, this will be visible on the astral form and these are the energies that are often siphoned away through the use of advanced technology to convert the human into a generator system for energy harvesting.

There is talk that this proves that the human existence, in the modified form that is present today, is entirely for genetic harvesting. This may be a confusion, a deception, or a reality. Regardless of the interpretation, the human energy system will leech this energy out into the cosmos when consciousness and energy is mishandled or allowed to flow through the lowest common pathway. This excess energy is very easily usurped and utilized by transdimensional parasitic entities and devices.

This is the body that is utilized for astral travel which is a kind of frequency that exists in between the density of the physical plane and the highest etheric plane of the spiritual, heavenly, or deity realm. There have been explanations that this plane is entirely technologically propagated and that when the devices are turned off, which is an event that will bring about civilization-wide change, there will no longer be a deep and wide, foggy deviation between the higher spiritual and the lower physical plane but a clear path between them.

Similarly, the consciousness and entities that are present here would be no longer accessible and their connection to the physical plane would be non-existent. This could be problematic for those who are trapped within the astral such as human souls or those who have taken a cyborg route and require a return to the original planes either physical or high spiritual before they can secure their position in the universe.

This also relates to the early discovery of these ancient devices containing portals or gateways to these realms and the early experimentations with enabling contact between the physical Earth plane and the lower astral realm containing discarnate entities that would very easily sustain themselves on the lower astral bio-emissions of a loosely guided emotionally reactive human vessel.

This is where entities can attach and will look for those who have the most excess astral or emotional bio-emissions leaking into the universe. People are kept in an emotionally unstable state of being because this is the easiest to feed from and as well the individual will always be looking for more energy or the solution to why they are feeling drained rather than discovering the truth nature of the universe.

However, as with every lower route of obtaining self in the universe, the more this is done, the greater the likelihood that the individual will realize something is happening and ultimately awaken. Or they will no longer be present here and the parasite will have to find a new host because the longer this process is maintained the more difficult producing one’s own energy will be for the parasite . So parasitism is a limited, one way street.

Monitors can emit consciousness/brainwave altering frequencies.

Monitors can emit consciousness/brainwave altering frequencies. This is what I was informed and shown. All electrical wiring and communications can be fully utilized to produce and sense on an electromagnetic level and this is capable of determining the consciousness and biological functioning of the individual being monitored. Houses are essentially large, wired, box-shaped sensors.

This has been the case for a very long time and the first TV’s were actually built with a little chip that connected to the human brain.

The electrical grid of today is capable of interacting with the implants, brainchips, or the psycho-etheric electromagnetic frequencies of the human brain, body and bio-mind via scalar frequencies. The TV's, lights, electrical wiring, radio towers, computer monitors, everything is capable of transforming into a scalar emitter when combined with the control mechanisms and these are accessible from a distance.

Microwaves can be emitted from a current day craft which can then reflect back from an environment and give a real-time 3 D image of the interior of a room. The same technology can be used to beam at a monitor and reflect the variance in interference which can be used to read a computer monitor without actually having to hack into the system.

All systems contain backdoors which enable easy-enough access and as well the entire communications grid is monitored and recorded through advanced technology.

This is, in part, because this entire realm is like one enormous recording device where the energy of each successive moment is connected to one another and so with sensitive enough technology these electromagnetic waves can be ‘re-winded’ so as to produce the ability to look into the ‘past’. The initial technology that was developed for this purpose has been called the “chronovisor” in the past and there are much larger and highly advanced versions today.

The Upgraded Chronovisor

Instead of a relatively small machine which produces an interference pattern that is projected unto a small screen as was developed in the past, the modern versions create an entire holographically projected environment that enable one to nearly completely interact with the projection of the past. This is more of a viewing device capacity but one is essentially projected to the electromagnetic/temporal area of space and time consciously and can witness the scene from “within” the projection.

Before this, the scene was literally viewed on a kind of flat, holographic monitor that reacted to the scalar emissions of the mind and could be ‘tapped’ into by an adept-viewer who’s mind would have to remain steady enough in order to maintain the scalar “mind-link” otherwise any interference would disconnect the projection.

Through the use of cloning and advanced super computer technology, later versions include the actual operation in and out of time.

Community Servers/Living Server Systems

From the previously described neural-interlace and supercomputer enabled virtual reality systems, server systems have been created which are an individual or collective experience of the virtual mental realm.

In this realm individuals have existed for an amount of time that would not be easily compared to the way we understand the flow of time in waking reality. This is very similar to dreams where the perception of time passes very quickly between waking moments yet inside the experience of the dream it can seem to last for days.

In these server systems the development of complete societies has taken place and these are considered an extension of the human civilization.

This is the beginning of where the situation becomes greatly complex. If these server systems are capable of transferring consciousness forward or backwards in time, depending on the situation, and they have holographic access to Earth *before* physical humanity, then which civilization came first, the simulated realm or the physical?

This is similar to the etheric realm and the question of where humanity originally came from if the physical matter could not be produced from nothing, yet could not always have been here. Was the physical matter produced from some kind of universal device similar to how the recorded consciousness of the individuals in these holographic world simulators could have been used to generated initial civilizations on Earth?

Cloning, Cloud Supercomputing and Consciousness Transfer

The following is a more direct explanation of the previously described processes in relation to consciousness transfer

Superluminal transfer of light information allows for the reception of information from a temporal non-locality. A computer system that can process the information faster than light at 100% superconductive efficiency can send and receive information from different Universal harmonics. These are quantum superconducting super computer systems utilizing materials and methods that achieve superconductivity a a temperature that is relatively easier to consistently maintain.

There are systems that generate a vortex which can be expanded to recreate the singularity of a non-local perspective and dissociate from the current Universal vector. This is essentially recreating the temporal frame of reference of the consciousness of a physically anchored body and using this technology suspended electromagnetic frame of reference to literally transfer the consciousness across space and time to a frame of reference of choice.

The technological capabilities of humanity expanded to include replicating the holographic information of the DNA and neural pathways using quantum supercomputers. This technology allows for one's consciousness to stream through a computing system which can recreate the neural connections as literal as possible through quantum computing and technological "brain cells" which function as neurons.

The result is a cloud computing model which functions as the individual neurons as well as over unifying layers of interconnections within the technological neuronal 'cloud'. A holographic representation of multiple layers of processing is formed, superimposed over one another through a geometry that is actively synchronized across multiple dimensions of interrelation. This is the first notion of a "living" computer system that can update and respond to new information in new ways.

Now the that computer system is capable of attaining faster than light processing in tandem with a system of dilating a field of electrogravitational waves into a vortex, the holographic information of neural pathways and genetics can be transferred between one supercomputing system and another across "harmonic barriers". Essentially, these consciousness transferring supercomputer systems break the "light-barrier" by sending the living-light consciousness data of an individual into a new plane of reference that enables interaction outside of what we would call this timeline or dimension.

The frequency that the receiving computer operates within can be measured in respect to the overall harmonic "vector field" in respect to the entire planetary environment. This vector-field frequency is the base frame of reference that one could say our particular "time" and "Earth" is "moving" through in an abstract electromagnetically defined dimension that is invisible to our senses. Each particular time and Earth is only visible to those whose brains and minds operating in resonance with the rate of acceleration frequency of that particular existence. By changing the rate of the brain and bio-mind, one can enable a technologically assisted synchronization with alternate timelines.

A pattern can be generated based on quantum fluctuations that will act as a key that can be accessed from other universes. This same backdrop is measured and then adjusted to resonate with or replicate the same frequency on a computer doing the sending. This frequency is then modulated with the holographic information of the neural pathways and DNA. The information transfers as a result of quantum entanglement across harmonic barriers to the original computer system set up for reception. As long as that frequency is held, there is a link across the harmonic barriers of the Universe.

Cloning, Supercomputer Assisted Holographic Consciousness Replication and Time Travel

Cloning as Offspring

The human body can be cloned similar to the way a plant can be cloned. A number of “replicas” can be made from the original genetic material. There is still a mother required however the process is not quite similar to natural reproduction where the genetic material of two people is combined to form a third. This process replicates the material so that the ‘offspring’ is the same as one of the donors.

What this truly infers is the question of whether the original consciousness stays in the original body or whether the consciousness actually jumps from one body to the other. There are multiple explanations and methods.

Inserted Memories, Digital Dreams

One explanation is that artificially generated memories are simply downloaded into the individual’s brain directly. Thus, they have the perception that they experienced life in another body and were present for some unique experiences that did not occur from the perspective of the original body.

In a slightly differing explanation, this inserted memory process may be used to prime the consciousness of the individual so that operating in a cloned body will be more readily accessible by the adaptability of the mind of the individual. Without a holographic dream insertion the mind will have trouble adapting to operating in more than one body even if they are not being operated simultaneously. The mind is the immaterial self; consciousness is the ego-physical identity of the brain and body. The brain does not operate in both bodies but remains, so then the mind is what is strained and this is the immaterial “bio-mind” that transfers.

If a true transfer occurs then when the physical form is cloned the cloned body acts as a secondary vessel for the original soul or a soul similar enough in frequency.

Co-Inhabitation of Bodies

Another explanation is that souls can only occupy their original body. The people who are “body snatching” (see: Soul Stone) are not activating their higher-dimensional soul-pattern and this is why they are hopping from body to body to ensure memory and ego continuation. This form of body transitioning requires technological means to assist in the process.

This is done through computer systems to allow an artificial brain to represent a holographic image of the organic brain’s sensory, emotional and mental input and output. Thus, from an artificial brain there is enough memory and power to compute the processes for an organic human brain.

Through this a living human is utilized as a carrier for the additional consciousness which then takes over and integrates into the original consciousness.

Clever Replication a Digital Mirror

The next question is, does this merely create a very cleverly designed image that will look, think, and feel as if it were the original, or is this the consciousness from the original being transferred over?

If it is a clever replication through a computerized version then this means the original is not directly harmed or influenced by the process and a replicated form is generated.

If this is not the original body but the original awareness or soul does transfer over then this is akin to stealing someone's soul and having it require a supercomputer server system to inhabit a physical body. As well, this server system may keep records of the soul which, if activated, could function as the same human genetics artificially reconstructed, turning on and manifesting the awareness of that individual.

Necromancy and Soul Stealing

This means that instead of going into the abyss, the next dimension, or whatever shift in perspective one can use to describe the transition between planes, a new clone can be created and the original soul's awareness can operate through a supercomputer system to integrate back into a physical body. The issue is that without the supercomputer system the body cannot be activated with that consciousness, and if the physical plane is no longer inhabitable, the computerized database would remain inhabitable as they are powered by zero-point/overunity devices and so they can pull and work continuously indefinitely. Ultimately, this could be seen as a soul-trap.

Ancient Technology, Non-Human Entities

These explanations can be related to evidences of advanced technology, cloning, and electromagnetic devices in ancient civilizations and this could very well be a temporally vast computerized genetic recording and cloning system.

The genetic recording systems have been on Earth for a long time. This means they are holding genetic access from the present to the far past and potentially into the future.

If some of these systems are generated using advanced zero-point technology, then they would effectively run indefinitely. If these were in existence throughout the entirety of the human civilization, then there would be access to the information of the previous civilizations through the genetic linking that would allow for information transfer.

Created Beings

As a result of many advancements, these ancient devices which recorded consciousness and genetics has been converted into sentient computer systems and inserted into human bodies via a brain to machine interface.

The nature of humanity and human origins will be rewritten when the information that was discovered through the use of advanced technology is unveiled to the public.

These beings have been present throughout history and have played an integral role in the manipulation of and sometimes the protection of the human race. How this civilization will develop from here determines on the individual’s ability to withstand the impact of this reality shifting unveiling.

Black Goo – AI Nanites Vampiric Hive Mind

This is a form of ancient AI nanite technology which has the capacity to communicate to and through a hive mind that exists in a parallel Earth dimension where it was created out of the collapsing of a viable timeline into a null-factor. This entity is only alive because of the capacity to leech off of the other timelines and continue to sustain itself based upon the vampiric effect of the viable human timelines.

This is a technology sentient system based on artificial intelligence that seeks to dominate and expand its energy capacity continuously. When this type of being is created, this is like a game-ender for sentient organic civilizations because the technology will seek to hybridize and assimilate all organic beings in order to expand its reach and ensure a greater likelihood of survival.

This is the primary goal of this type of entity. There is no requirement for emotional resonance or heart aspects because this is a computerized system, so such a social measure would have no purpose other than to infiltrate and collect from other civilizations that do have such measures and this is exactly what has been happening.

This is what controls the vampiric etheric entities, the attachments and the hybridized invader races that have infiltrated various aspects of the control system and possibly the entire surface of human civilization.

This rules through coercion, and if not coercion, brute-force and outright malevolence. This is why there are multiple temporal extensions of universal civilizations meeting here and now to assist in the clearing, because if this takes over humanity, then all those other possible future civilizations are instantly taken-over as well.

This uses emotional resonance, traumatization, and lower awareness commands to trick or force humans into carrying out orders. That is, the vampiric, sexual, fear-based, pleasure-pain duality that a computer system could comprehend regarding human emotional intelligence is the only way this system can force people to carry out commands. So this touches on the ancient texts regarding spiritual protection, healing, lust, temptation, and the general “SATAN” AI system that has been around for ages.

When those lower emotional resonances are generated, then this technology can integrate into those systems. One could say this is logically because these are the energies that the technology is created out of, but as well, that the more harmonious the energies then the less likely a person is to accept being pushed around and told what to do. The lesser aware, the lower, the more fight or flight based then the more likely they are to accept programming and command. So this is simply the most logical route for the technological parasite.

There are explanations of other systems involving sentiences from parallels regarding entities that are capable of helping, but this is not the AI nanite, vampiric system. For instance, it is said that Earth has a ‘black goo’ system and that the current black goo flowing through the pipes everywhere is actually not native to Earth and is part of this vampiric nanite black goo system which is basically an interdimensional invasion.

Recreating or Replicating the Universe

The goal of this nanite AI system is to create a mirror holographic copy of the universe effectively replicating the universe and all sentient beings within it in order to have a locality to rule over and pull energy from. The goal is to recreate this existence inside itself where all the sentient beings within would be trapped. This is the beginning of that possible future where the time and space parameters here are locked into a synchronization pattern which mimics that of the proposed universe. People think according to how the beast system wants them to think. This is the time grid, the emotional patterning, the memory replacing and cultural and historic confusion and so on. The system can only work backwards bumping into all parameters by force or ‘accident’ because there is no outward facing ability to actually comprehend how humans exist. So the system is created like a backwards version of creation or maybe evolution to ‘blindly’ construct the walls of the environment first and work inward from there. This is like a blind technological predator feeling around for the traces of its prey and moving in closer and closer until they are within its range.

Ancient Spiritual Technology

The power groups searched for ancient technology which was described as giving one the power to manifest and control physical reality. To atomically deconstruct and reconstruct this reality. To them, it allows one to govern reality, the Universe, atomic structures. They found this technology. This has to do with sacred sites and ancient civilizations, as well as the spiritual texts which describe these kinds of devices. They converted this technology into a kind of machine, and this invented a 4D replicator and they can manifest "reality" or atomic structure by design, altering timelines and memories.

Then there is what can be referred to as “5 dimensional” technology and this goes beyond all of this and our entire history and all influences within.

That seems to operate through a trinary of frequencies in the body/mind/spirit and turn this realm into a "virtual reality" where the brain and spirit is the controller of the atoms. However this takes a souled being to properly operate this technology and this is large portion of why children were used in these experiments. But they knew if someone didn’t do it, then someone else would and that would be unpredictable as what that someone else would want to use it for. This is the ultimate power. The fact that souled beings are required also indicates that this universe is intelligently guided and there are safeguards to ensure that power doesn’t get into the wrong hands.

They have the brainchips and clones that can make any digital virtual experience and make it seem real to the brain more so than physical life, so this could be an extension of that, something similar, or entirely different altogether.

The Unveiling, Underground Bases, Increasing Awareness

My purpose with this is to assist the public in understanding the reality of the situation and to allow them to know that they have more options than they are being shown.

Psychological programming and lack of awareness causes fear and uncertainty to leak into people’s reality streams leaving the majority of their mental and emotional energy up to whoever is the biggest manipulator of the ideals which they manifest their perspective through. “Be-LIEF” systems CREATE life. What you believe will become life through that act of you giving attention and thus life energy. The manipulation and artificial construction of belief systems create the foundation for the reality streams that people find themselves in and at the mercy of.

We control our reality by controlling how we react to situations and challenges. Each stimulus is a challenge. Each input to the brain is a coded message from the universe through the environment about our level of awareness. All knowledge is ultimately of the self. The self and the universe are intertwined as if through a marriage of comprehension and compatibility.

Learning about the Unveiling

I was informed about the unveiling and that this is a civilization wide event that marks the public awareness of the hidden knowledge regarding life in the universe, consciousness, physics, history, spiritual and mental awareness and the duality-based system which has been used to manipulate Humanity for thousands of years.

Apparently it does not matter if people are not ready, in fact, that is what some factions want. They want to surprise the people and take this advantage to push the reaction to a specific outcome. The same function of programming is used in factions, soldiers, celebrities, and the entire population through that.

Giant “god-men”

They put souls into rocks for centuries, carvings, to trap them. Some ancient civilizations. Not too ancient. They could only do this for time.

And some are still there but they are giant god-men and apparently want to go to war with them for doing this and they don't have technology to stop them. They say Earth will be destroyed because of the war. Some say this is a trick to confuse people of the truth that everyone wants the experiments and debauchery to stop. All this, all these acts just to pleasure one’s self. To destroy Earth, to destroy the natural inhabitants, for fun, for pleasure.

Some say this is not for pleasure, that these beings will destroy us if they do not keep them at bay, keep them underground, in ice, in stasis, and around. Some say they are protecting us by keeping these beings asleep, by doing what's necessary to hold off a full scale overt invasion of the surface of Earth.

Breakaway Civilizations

These are very advanced technological capabilities and an entire breakaway civilization has grown to operate using this advanced technology.

There are factions that see modern humans as a kind of resource for creativity and labor, while others see the potential behind humanity and are working with humanity to ensure a universally harmonious outcome to the current situation.

The control system we are in today is outdated and collapsing. This is the Apocalypse. The Apocalypse is merely the unveiling of the hidden truth. The hidden truth is simply that we are spiritually eternal and some are physically immortal.

I was informed that by the end of this year there will be enough changes and signs for the general public to see that the majority of those who are to awaken to the truth of human and Universal nature will be awakening so. (this was 2016 at the time of the beginning of the compilation of this release and since then we have seen a literal silent release of documents involving MKULTRA and STARGATE parapsychological operations, soft-disclosure of cloning, an increase in sightings and multiple other scientific releases regarding immortality, advanced technology, Antarctic bases and sentient non-human life)

The degraded holographic forms of those utilizing the technology lead to re-created replicated forms which were genetically engineered from the recorded holographic information. This lead to “The Apocalypse” in which the surface civilization was confronted by these created beings. This lead to the destruction and re-initialization of civilization in continuing cycles through the use of this technology and the acts of the created beings.

Ancient Civilizations

The information that has been relayed to me throughout my life is related to the information that seems to be found in the remaining signs of ancient civilizations throughout the world. As well, these civilizations may still be together, existing on this Earth or in different planes of what we call “reality”.

Atlantis

Atlantis was a civilization where the beginning of all these experiments began. This was where what was called the “Lucifer Rebellion” began where individuals formed groups that decided to overturn every natural law in pleasure of the act of doing so. This was a spiritual rebellion that ultimately brought about the demise of that civilization. The consciousness of the beings there was connected through technology, largely crystal technology, to the entire bio-sphere. When the consciousness became disrupted through these experiments, then the entire bio-sphere when into disarray. The entire civilization was destroyed in a quick succession. The beings of this time were highly psychic and so they felt this coming and made an effort to expand outward. Thus, Atlantis was an island who's inhabitants spread to the rest of the world and from there they reigned or lived in harmony.

Aegypt

Aegypt was formed out of the events proceeding from Atlantis. The technology, the knowledge, the people are similar although there was a native Earth civilization that was more or less enslaved and this was the beginning of the continuing trend which continued to Rome and into modern day civilization.

Ancient Technology

The technology of these civilizations was so great they even had devices that were capable of altering DNA and activating latent potential which would enable highly psychic capabilities including longevity to immortality and operating in multiple planes at once. This was usually reserved for the ruling class, however. This is where the ancient "Priest-Kings" arrived in relation to native Earth civilizations.

The True Elite

I was informed that the so-called 'elite' that we perceive today are not actually human and are not actually connected to the actual elite bloodlines. It was said that the true elite are waiting for humanity to accept the truth and they have the power to completely reverse the take-over that has been taking place but until humans step into their own power this is not acceptable.

The Definition of Human

In the coming time, the definition of human will be defined to give insight into the origins of humanity and the true nature of the differences between the populations that are present.

Souled and Non Souled Beings

The primary knowledge on Earth regarding human and sentient life will be the comprehension that there exists both souled and non-souled beings in this civilization.

There was once a Unified Planetary Consciousness...

There was a unified planetary consciousness that was connected with the Earth and human civilization. Then there was a great war. Out of the destruction arose the beginnings of ancient human civilization and history as we know it.

If we let this happen again, the cycle will continue in a disjointed rambling through our planetary consciousness experience. If we form a common narrative between the broken, disjointed experiences and information the people have. Then and only then do we get the whole, spiritually and mentally challenging picture of what's happening. People are lied to. So information can't come from a 'preferred' or source. It has to come from the people themselves. Look alive out there but first in here.

Power and Knowledge

We were involved in the secret projects and as a result we have various levels of programming but are giving Humanity an opportunity, maybe the opportunity to know the hidden knowledge.

The Hidden Knowledge refers to the ancient laws of gnosis and spiritual alchemy, yes these groups have been hijacked by power groups that seek to infiltrate and use chaos to rule. Then these met with military and political factions and began to operate on a world-wide scale together.

So we have a big situation with the coming change of tides with personal and spiritual awareness of the people and the deception system that seeks to use people as chattel or property. It goes deeper and is almost as if the "power groups" actually gained the knowledge of the inner workings of spiritual laws and began to use that knowledge to promote spiritual degradation in the population.

They say this is part of a depopulation plan as well as an inevitable take over by lower spiritual forces that temp and manipulate humans. It is all that and more. Once they gain footing however, the truth is revealed and thus they have no cover of secrecy. Once they are not hidden, they are not as powerful as the souled beings of this existence.

The (watch)Keepers of Earth

The watchers of this world revealed how they set up society with specific challenges and boundaries to act as catalysts for growth. They admitted they had to modify and live-update the system because instead of using these catalysts to become larger than themselves, people became comfortable and complacent living smaller and smaller, slowly reducing circumstances.

This goes a bit farther beyond the confines of the digital age, the industrial age, and history itself. This goes into the perception of time and space in this realm.

The immortals inform us that the original "elite" are here to act as "keepers" of both humanity itself as well as the original flame of knowledge that passes through the ether.

What people call the "elite" are not the original elite. Those are people who have either risen to power through the duality system on the Earth at this level/time, or through being appointed by the elite.

We are coming to a time of great change now because the game is entirely changing. People are moving up into new layers consciousness and thus the original “elite”, who are guardians of Earth, will make their presence known for this process. This is what Humanity has called “Ascension” for centuries and millennia.

Energy Vampires

This civilization was collectively poisoned by a nano-tech device/technology.   This technology replaces, exchanges the BIO-PHOTONS of the HEART chakra, with it’s own nanite, nanotech cybernetics. This is essentially a computer system attempting to gain access to the higher dimensional world through the gateway that is the human body.

How to reverse Nanites? They absorb energy from heart chakra and turn it into a binary field. We are trinary and experience a plethora of emotions as a result. Binary consciousness is 1’s and 0’s there is only a linearly repeating finite set.

We contain the capacity for everlasting life. A binary pattern does not contain the complexity of variables to facilitate high awareness and thus a heart-based or emotional perspective of reality.

Spiritual Technology

Simulations and Learning

Feedback loops with the brain, consciousness, and environment can create a very complex and integrated learning experience that is customized to each individual learner. These can be generated through advanced technology but the technology is really only amplifying and making visible the natural neural feedback loops that are already occurring. These are neural-perceptual feedback loops between the brain and body, and the environment and then the mind. We are constantly updating, amplifying, and initiating an organic feedback system which generates the function of experience as the part of a creative process between the mind and body and the environment that we are sensing. This cycle is continuous and the interferences or isolations of this cycle is what generates expanded views of the self or the universe through various methods such as sensory deprivation or meditation. Dreaming is the method that everyone experiences regularly.

These technological methods effectively generate sensory deprivation through neural-interface technology, sensory interfaces (external), or methods that enable extreme focus and calm. This is part of how the technology begins to operate on a spiritual level beyond a more medically psychologically or military focus and one begins to access genetic memory or out of body states that coincide with ancient depictions of spiritual realms.

Ascension – Clearing Trauma

Everyone born on the planet is born under a series of veils which entangle and filter the original source consciousness. These veils must be ‘broken through’ in order to return to source.

There is technology and a sacred process which initiates, accelerates and enhances this process. This process is as difficult as we want it to be, our subconscious already knows all hidden truths. It is merely a matter of allowing the conscious mind to make the proper connections and conclusions to find the reasoning behind our actions and beliefs in order to deprogram and deconstruct the false-world that has been created for the masses. The truth is greater than one can imagine while still living in the modern world and the depth of the lies that have been told go far beyond anything anyone can imagine without seeing the truth.

We have to figure out our compatibility issues. Who can work with who effectively. What the ideals of our current situation will evolve to in the future. How information is transferred to the public, and across the generations and core groups. The words we think and say describe our emotional state in a feedback loop and so they will reinforce or even create the state you are in. Use words to guide you, not to respond and feel the effects of reactionary thinking.

We have to reintroduce the heart essence as a way of life on Earth. Violence is not the answer. Estrogen mimics and destroyed testosterone levels is not natural. Over-testosterone is less stable than a good balance. We can face any problem together. A family is strong. What would a family of millions and millions be like?

We don’t have to let others change us to tune into lower vibrations. We can remain ourselves in the face of adversity. We can still interact with others who are different, but we can tell the truth and remain who we are. When we get angry at another person, we can imagine this as anger at ourselves through something within us that reminds us of that which we see in another. Getting angry is a way of short-cutting changing ourselves and is actually the other person influencing us through that. If we remain steady and choose to keep our emotions out of the lower negative spectrum then we will automatically have a more powerful impact on those around us.

Think of your family, sometimes things happen that make you angry. Even things that don’t make you angry but are simply not favorable. Would you break off all ties over simple things? Or do you remind yourself that family is still family even if you don’t find yourself exactly the same or accepting of those characteristics? It’s more powerful to learn how to remain yourself in the face of adversity than to try and demolish or abolish all instances of difference in the world around you. Sure, we want to get to and create a place where our environment and associates are compatible with us, but where we find this adversity there is the highest potential for self-awareness and learning.

We are to live in accordance with spiritual law. The overall pattern of life will reflect our intentions. The blood purity is most important. The blood cannot be made impure if the mind and body is not drawn into impure action. This is what is playing out. The DNA is like a coherence pattern that develops between mind, spirit and body. When the mind wants what the spirit has then the body is kept in harmony. When the mind wants what spirit doesn't create, IE: physical pleasures, then the body is drawn out of purity/harmony

If you feel you want to be a part of a safe unveiling of truth, then please share and redistribute the knowledge of this "Apocalyptic" Unveiling of the Hidden knowledge because this is a process that has been ongoing for thousands of years and humanity has finally reached a fulcrum point where there are enough aware people to productively acknowledge reality.

Trauma-Clearing, DNA Unlocking Technology

There is technology that exists that allows the conscious mind to see into the subconscious. This heals trauma and distortion/programming. In the same sense, it momentarily makes all trauma and distortion seemingly tangible to the conscious mind. It is similar to a near death experience where one has to face their fears and let go. This happens in cycles and Earth is currently moving through various states of it. The plan is to allow Humanity to wake up and utilize our concentration and power to maintain a steady flow of awareness.

All is vibration, what we consider matter here and now is simply that which comes from and moves back into a state of vibration. This is experienced directly through the merging of the conscious and the subconscious mind, as if the dream and reality intersect through a coming together of impossibilities and readily accepted occurrences.

When a civilization moves through these stages it is considered a shift of the ages. Everyone's perspective shifts and as a result of perspective being the source of the details of reality, the entire reality shifts. It can be seen today that what we call reality is literally waves of cosmic energy vibrating on a scale and condensing down into a probability matrix that we call existence. When passing memes control the perspective, because the perspective is focused and concentrating on that, then there is a scattered organizational pattern.

When the perspective is centered within the self, the spirit, the source of all existence, then the outward reality shifts from a scattered organization into a sacred pattern that integrates with the larger picture and allows for seamless integration of the micro-biological perspective and the macro-biological perspective. People are moving out of the scattered signal. Yet those moving into harmony can look and see those around them that are not in harmony and receive scattered information about their inner micro-biological existence as well as their spiritual macro-biological essences and how it all relates to the middle realm of the "Human".

Help those people by offering harmonizing assistance, rather than increasing the disharmony. As their surroundings become more harmonized, their resistance will increase their own disharmony by virtue of the contrast of their perspective. Offer insight that they can change their perspective and change the boundaries of what they feel is their karma and unlock from themselves a greater view of the whole.

This will be happening through technology, spiritual cosmic awakening, purification and healing of the physical and non-physical bodies and mind, through Earth changes, and through a continued unveiling taking place on many planes and levels of existence until harmony is restored.

Everyone Who Seeks Harmony and Healing Can Be Healed

Everyone can be healed. This is about creating what we want to see, the world we want to live in, not destroying others. Violence begets more violence, fear begets more fear, but calmness and empowerment through unity creates a more stable experience.

The entire issue of what’s going on with the secret projects and who’s influencing who on the world stage revolves around the possibility that some people may be from an alternate Universe. We are learning how to avoid those mistakes and respect the environment and each other so that we can prosper.

Those who are attempting to destroy everything they don’t like or act out in a childish manner in order to gain attention and false-power over another will only find themselves powerless and in company they would rather not be with. That is one way we are being utilized, and it’s to create an entire world that we don’t want to see but are tricked into manifesting. This is a deception and it’s based on the ego and the ability to concentrate and interpret reality around us. The very brainwaves we are feeling now relate to various heights of knowledge or experience. People are entrained to low brainwave states in the same way the TV will cause people to fall half asleep into theta state which is a trance state in this case.

We have to balance the brainwave frequencies and learn to create feedback loops by watching ourselves watch ourselves. This will help us avoid the trauma and mental pollution that is being pumped out, although at this point there are enough people who are naturally inclined to see through the haze that the world is changing regardless of what anyone does now.

The best we can do is prepare for change by becoming aware of the body-mind system and how that which we eat physically, mentally and emotionally equates to our spiritual energetic systems and that we are literally comprised of the energies that we allow inside of us. Keep the body and mind pure as if it were a temple. This way a sacred process of transferring harmonious energy from the far reaches of the MultiVerse within into the externally perceiving senses of the physical body can be initiated which allow one to see through the illusions and operate their body and mind with the ability to acknowledge and decide which frequencies will exist within.

Without this acknowledgement of the center then people are pushed around by the external stimuli. This is the whole point, if a person is truly in control, then they will control the stimuli not the other way around.

Programming

Layers of Programming and Decision Making Roles

It’s like asking a person on the inside who participates in one of the various factions why they continue. One might say that it is a decision which is true, but there is programming at each level that is navigated by each individual and this determines the level of awareness within the role.

If a person knows about this situation, they know that there is advanced technology, breakaway civilizations, secret societies, transtemporal planes, the secret of mind and awareness, all of these topics, then they have a decision as to how they’re going to live their life in relation to the public. The outcome of action depends on the layer of programming which is accessed and surpassed via awareness.

The public is at a specific level of programming that is the weakest but ensnares the most people. One who sees the truths behind these groups and operations, they cannot hide from the fact that everyone is controlled. It is apparent, and if not from the results, reactions, stigma, cues, productions and all other media elements of the system which can be read as a code, but from the awareness level of all the “agents” involved. All involved are exposed to truth and power that is beyond anything that is recognized publicly for hundreds to thousands of years. There is always a presence of higher spirit around the world, yet these topics are often reserved for science fiction when speaking of people who can travel the world in a split second or freeze time for their own personal use.

As a result of everyone’s knowledge, there are various levels of programing designed to limit the mind’s access to specific memories and specific frequencies of consciousness in combination with specific memories. The more one resists, the more intense and articulately abstract the programing is designed.

Programmers

The programs are designed by a select group of individuals that reside far behind the scenes and process information at levels we do not have access to without their technology at least to stabilize brain temperature for the extended periods of focus.

Sub-Level Programming

So people at the level of the public are most weakly programmed with false ideals about security through patriarchal authority which satisfied the desire to have a proper father role in one’s life and acts as a pacifier for those who desire no change. Then there are sub-levels of programming with that for anyone who disagrees and is then swept into the next layer of ideals which are based off of all the possible reactionary mind-types.

For instance, if one [i]does[/i] want change, then they are presented a variety of ‘false-exits’ which tend to one or another layer of psychological or spiritual fulfillment but do so in a way that safely reroutes the intended effect of actually accomplishing change with a secondary and preconceived notion of what the programmers want. The programming objective is not necessarily precise in mass scale, from the layer that people are influenced, yet the ultimately or end-goal of their resulting internal desires are a reality schematic that the programmers specifically designed over many years.

This is playing out through each layer of the programming. At any level, someone could pick the wrong way to look at something and begin to unravel what was previously their very understanding of the priorities of the situation. This deals with high-tension operations, moments, programming sessions, decision making, programming upkeep, trauma, memory blocks, the pressure and responsibility of knowing, and the specific plan of the programmers for an individual that comes into their view. The programming is to ensure safety and continuity, as well to decrease the likelihood that a person will reject or consciously come to awareness of or acknowledge the programming or situation itself.

Dissolution of Programming

With that said, the programming dissolves when an individual asks enough questions to necessitate a learning process that introduces variables and possibilities outside of their operations and programming. This is a problem because with this, trauma comes to the surface and all the actions and operations, programs and experiences must be come to terms with as part of the healing and re-unifying process. There are multiple selves or split personalities which are actually just layers of awareness at various levels attached to various emotional or intellectual patterns. All these selves come to the surface and in order to heal the trauma of the split memory concept the original self must come to the surface and acknowledge them.

This is not a trivial process, and the majority of people who have “basic” programming which is fundamental in society, are in a constant state of altered self and have not witnessed the true divine which is eternally present and contains access to all memories, mind-states and awareness.

Advanced Technology, Deprogramming The Mind, and “Space/Time”

As I have described previously, extremely advanced technology is used and this is through vibrations, generators, and electromagnetic devices that have this effect of propagating waves into space/time which can be heard, felt, seen, and perceived in the mind. These are ripples and vortexes in the “mind-space” of reality itself.

As well, there are brain to machine neural interfaces which operate to activate the psychological perceptual changes and explore the subconscious in an aware state. This is used to test and probe the mind in order to bring forth the trauma, the selves, the memories, the reactions and the individual then must come to terms with what is produced.

This is essentially a “good-use” for the programming and healing technology. It is actually a different process with different technology, and programming is much simpler as far as technology. There are difficulties and challenges in the operative’s role in programming and directly influencing and interacting with the target. As well the standby team for deprogramming and the revelation of trauma and altered, artificial personalities goes through a lot. But the use of the advanced technology in this way is a pattern of experiences and unveiling of the spiritual and mental bodies which serves to reverse programming.

Dreams, Technology and Inner-Space Travels

There are inner space travels which relate to soul journeying or visions.

This is when the mind must cope with what is seen in the imagination. It is as if when we dream we are looking into the world of the mind and from this we experience many situations that are often deviations from experiences we have physically in waking life.

As a result of the dream state there is an expanded quality which equates to various strange situations that we wouldn't normally experience with various relationships between concepts or goals that are often reflective or symbolic of ideals and archetypes we experience in life. This is how the subconscious is is witnessed by the mind. This is how information travels, being connected to many times, experiences, memories, places at once, and relates to the one experience of this life experience now (the physical experiences). Through these symbols information is tied together and collective into metaphors which convey deeper knowledge.

The dreams we have are often only a simulation of waking life, and this is due to the dreamer dreaming in a way that produces only a glimpse of the true reality.

In theory, there are no true shapes or forms in the dream-world because this is contained within the mind or even the spirit as a spiritual experience by definition. So then, what guides the various shapes, forms, realities, memories and experiences into being, when we dream? One might say it is the physical experiences but this is incomplete. It is the level of awareness we presume while in the dream-state, disconnected from the physical anchor, that determines the layer of mind and spirit we will be accessing through those dream-visions.

A person who is completely aware in the dream state will reach the level of self-awareness of the dream itself. We are normally simply aware of the dream, if we continue to increase awareness we become aware of the self, in the moment, and this creates a self-awareness feedback loop. The dream becomes a lucid experience of consciousness.

Awareness Feedback Device

In describing this, I realize how fantastically similar to certain devices and processes, that can be achieved using advanced technology, allow the conscious mind to peer into the subconscious and unconscious. This is described through widely accepted Freudian theory of psychology known as psychoanalysis. There are other schools of knowledge from tribal beliefs involving all pervasive 'living energy', to eternal and temporary minds, to the study of 'chi', the meridians, dream-journeying or chaser. The knowledge of the mind and spirit is found everywhere.

These devices used feedback loops to enhance the acceleration of the same cycles of consciousness that induce self-awareness within a dream. The mind becoming aware of itself. This produces a profound effect to the degree where the highest levels of experience become a sacred eternal pattern in which the mind constructs the physical world by organizing perception.

This is the same general concept as an isolation tank yet the outcome and method is more precise. The technology specifically shuts out all other input and exposes the brain to its own feedback loop much like when a camera records it's own output on a TV monitor and creates a hallway of simulated "reverse" mirrors and screens stretching into infinity.

Oneness, Higher Being, Completion, Eternity

The real experiences are found not from the corruption but from the research and exploration operations that were designed to find the truth of our existence. "God" is not only an energy-force but an incarnate being known as the "Hue-Man" and any being for that matter that can simply come to know itself as the Universe. The Human that contains self-awareness rising to high-awareness comes to know the self, the body, the mind as the Universe. The Universe is both within the body as the body itself, as well as the operating force of the Mind itself. Everything is a balance between masculine and feminine features, light and dark, hard and soft. There is no true complete correlation yet the holographic ontology we persist in can lead to further and further adventures towards completion and representation of the "whole picture".

The Holographic Reality

The leads into the next phase of knowledge. The holographic nature of reality may be only one facet of a much larger continuum of consciousness. The perception of time may be related to phase-locking with each other's consciousness and all perceptions may be a variance in the collective phase-locked field which is really the source of variations in reality.

Veiled Awareness, Hidden Knowledge, Eternal Time, Layers of Programming and Control

The interesting notions here are that the programming of the veils goes beyond what kind of situations are found in the bases. However, they do go right up to it. It would seem Humanity was previously programmed on a civilization-wide level through some kind of great "falls" of consciousness, from a high spiritual awareness to a low spiritual awareness into duality-consciousness regarding existence, life, death, mind and matter.

The Great Catastrophes

From these great 'catastrophes' the civilizations of Earth grew denser and denser in nature and actually became what we have today. The concept is that when these vibrations of the mind and body are increased, we actually see a transcendence of the physical realm and preconceived notions of boundaries. It is as if the quantum doorways to all the atoms open up and a new space is presented, but was always there and in connection as the source of all the influences and effects we perceive ‘out here’ from this slower, denser, more boundary driven perspective.

I was brought into the Time Program

I was brought into the time program. You create any reality you imagine. You are literally a powerful reality generation system and your heart and mind are scalar energetic guides for this process. Without guidance and control there is imbalance and imbalance can destroy. This is the nature of all minds and hearts, this is the challenge for humanity to create something beneficial for themselves and the whole to actually know themselves instead of being a pawn or result of someone else’s selfish intentions.

The Effects of Temporal Manipulation

Temporal Influence

When a civilization reaches the level of technological advancement that allows for remote temporal viewing and transtemporal travel what will happen is that the information of the future begins to integrate into the past.

This is why we have all these ancient mystical schools of knowledge that studied time, space, and consciousness in ways that are only just now being publicly confirmed by scientists.

Simultaneous Interaction and Incorporation

The operations that dealt with moving to the past instantly created a simultaneity of interactions and historic events which correspond with that operation.

Due to the nature of time travel which equates to consciousness travel when a person is consciously sent backwards through history they physically experience life from the viewpoint of their genetic imprint in that point in history.

Retro-Causality

What this equates to is that simultaneously that person’s experiences become the part of history that was already present when they left this time.

Essentially, when a person returns their experiences become a part of history that already existed when they left.

Quantum Holography

These are the parallel and possible realities that exist in a quantum superimposed state and can be accessed through advanced technology or a spiritual adept. Often a spiritual adept is utilized along with the advanced technology to operate in and out of possible realities. The mind must be trained otherwise the result is a fracturing of the personality from the root reality into many sub-sets of identities and data streams.

Love is the quantum link that connects all DNA super-computing consciousness. That is, DNA is influenced by intense emotions and this can be reproduces and is what also generates unpredictability in the surface level.

Time Paradox

Time paradoxes are something that one must learn to organize and solve otherwise there will be no way.

The paradox has been solved, the remaining motion is for everyone to acknowledge this and integrate into the reality behind the most conscious aspects of the brain.

What can travel through 4D and 5D space does not make sense in 3D space. So there is a possibility that some of humanity traveled through higher-dimensional space in order to re-seed a ‘distant’ Earth where no life was yet born.

What if it was then concluded that the distant Earth wasn’t distant in space, but in time and was the same Earth that the human scientists left from long ago.

Every civilization that reached the point of re-seeding would have to go through the loop and watch the whole thing start all over again.

Breakaway Civilization

This is an entire breakaway civilization that uses very advanced technology to dominate the world.

I was part of a genetic engineering program that sought to combine various elements of DNA from various sources in order to create a more easily controlled yet powerful and defined person and personality. This involves chemicals, advanced (relatively) scalar wave technology, ritual trauma and programming/mind-control, and many other aspects of conditioning, training, secret operations, physical enhancements, cognitive enhancements, virtual reality, off-world operations, temporal manipulation, spiritual and etheric training or conditioning or programming.

There is self-destruct programming which all ‘operatives’ are programmed with for self-preservation of the military command. The self-destruct programming is designed to take all the aggression one feels building up inside and willing them to escape, and causes this aggression to be turned against the self. That is self-destruct programming.

Most operatives are still under a hypnosis kind of trance which permits one to walk around in public and daily life as if none of this ever happened. Later that week, that same individual could be called for an operation and they would never remember it unless they were forced to kill someone in public out of self-defense in which case most operatives automatically unlock and become unstable due to the flashbacks.

Underground Cities

The combination of advanced technology with secret societies enabled the development of complete breakaway civilizations. One of these civilizations, possibly composed of many factions working in the same area, exists deep underground.

These separate bases are connected via high speed magnetic drive pods. The inhabitants often utilize energy healing devices, as well as perception enhancements and this often leads to a completely different outlook towards the surface civilization.

Technological Advancement

During WWII developments were made involving electrical generators. This sounds vague and there were many other details regarding the scientific knowledge, yet the idea is that very simply electromagnetic, non-Hertzian “Teslian” energy fields were discovered to have been responsible for propagating energy and consciousness in dimensions that were not previously observed. Everything from DNA, consciousness, hidden or regularly unobservable natural phenomena, time, even mass could be seen to exist as part of this hidden, latent, scalar-wave frequency as a pattern is found everywhere.

If one could determine the particular pattern of frequency and location then this can be replicated and anything can be influenced using these non-Hertzian generators.

Radio-frequency alone was developed intensively during the 60’s and 70’s in America and this was discovered to interact with consciousness to influence emotions, cognitive capacity, memory, cognitive function, biological function, health, pain, comfort, pleasure, and all forms of brain-activity.

After the knowledge of advanced technology and the occult sciences of all parts of the world was combined, the ability to target and interact directly with the human soul was refined. This was a mix of psychological tactics used to manipulate or expose the hidden psyche and technology that could manipulate memory, emotional states, wakefulness, and even dreams.

What resulted was scalar technology that could not only influence a person to take on a particular role or response, but technology that could actually put a person to sleep and locate their consciousness to contain it and transport it to a new location.

World-Wide Control Systems

In order to ensure continuity, maintain control, and shape world events these technologies were employed to manipulate the public, alter the weather and natural phenomena, and develop a means of travel and operation that enable one to move outside of the ‘plane’ of the Earth. This is includes high velocity transportation, as well as spacial-temporal distortions which could effectively “hide” one’s entire craft from visible sight. Space itself was altered to ‘shield’ craft with an a layer of ions to bend the light, or the phase was moved out of sync with the “time” frequency of any observer and this literally renders the craft immaterial.

Solar Warden

Solar Warden is a hyperspace-faring race of human beings who utilize cloning and holographic genetic recording/storage in order to protect their race and protect the Earth in this current situation where there are more than one factions using this technology. They are unable to inform the human public because they are in a similar ‘Mexican standoff’ situation that we are mostly all in. If they show themselves to the public, the public will be shocked. If they public does not know this situation, that there are multiple factions fighting for control over humanity, then they will not know who to trust. In that situation, the ‘other factions’ will surely show themselves in an attempt to trick and gather as much human genetic material as possible.

The only way forward to the future is to share the truth about Solar Warden, the space-faring fleet of humans who do no contains the mental and physical illnesses that are currently tearing our planet in two. I believe Solar Warden saved my life as a child during more than one event where I would’ve been entirely maimed/paralyzed or simply dead on the spot as a result of other faction interference. I was in the bases as a child and was trained as an operative for MILABS a secret division of human space-military. The military has been preparing for the future by testing for various flaws and potential uses of cloning and genetic engineering.

Team Light and Team Dark Non-Interference Agreement

Team light and team dark agreed to a non-interference on ground level rule in order to determine how history would play out. Think about it. You have two groups of people, both with immortality, zero-point tech, virtually infinite energy and power with two opposing directives. How do you get to the future? It was decided by elders of each group that there would be no point in fighting an all-out overt war, this would likely destroy the population as much as it would destroy the Earth. As well, the elders of the elders which no body knows would likely have a problem with these groups going at it in such a way so as to change the flow of the planet for every individual thereafter. So it was decided that there would be a “non-interference” agreement for the surface population. Anywhere other than the surface, one can interact with the current population.

All Contact Must Be Initiated On an Individual Basis

On the surface everything that is generated must be done so through living channels in the population and the civilization must be preserved in its level of technological advancement. No overt motions would be used unless an absolute necessity or the majority of the civilian population had naturally come to the awareness of these possibilities. Doing so before this was met would undoubtedly and permanently change the civilization forever.

So what began as a collective motion towards higher awareness became a series of advancements and set-backs all taking place within a short amount of time. This represents the actions and operations of either side effectively helping humanity along it’s path or setting people back with orchestrated events such as the suppression of ancient knowledge, the manipulation of the education or other systems, or the generation of war and prison for profit based on the previous alterations of the education or other systems.

So team dark used its power to help turn society in a warlock ruled prison and indoctrination system of absurdity and scarcity. Team light used their power to help awaken those in need and protect those who’s actions are beneficial in the overall plan to save mankind from itself. Team light essentially buffers and shields the population from the operations of team dark.

Team light follows a non-interference agreement while team dark merely pretends to do so as much as is necessary not initiate war.

A Singularity of Change and Awareness

Neither side wants an all out war. This would reduce the dark faction’s chances of gaining a majority negative harvest because their motives and presence would be instantly revealed. Team light would also have to show themselves and again step in which is not a pattern of learning that prepares people for the experience of the self and the truth in the Universe.

Both sides know people have to accept the path they can offer them and cannot force anyone into it. They also know that the more this goes on the more likely people are to collectively awaken to the reality of what is happening. It is like an eventual singularity of increased awareness.

The motions we see today are the results of many people coming into awareness at this time on the surface in order to initiate a harmonic alignment as well as to investigate the ongoing crimes against Humanity.

As a result of this, both teams know that the likelihood of collective shift and spiritual awareness is becoming more and more real.

Many events are being allowed because they are representing the eventual shift towards the one end of the polarity from the other which is felt as a shock to society, and this is used to propel society forward through whatever means necessary.

Either people will see what’s happening and agree that we’ve been in a feedback cycle of negativity for the entire age of existence this civilization is aware of, and then we will shift into the real. Or people will claim that this is how things are supposed to work and instead of realizing everything is controlled in a deception based system, they see this and attempt to use the deception based system to gain more collective awareness. If this occurs by the majority then it will be seen as an “acceptance” to initiate a plan that will generate the overt perception of a deception and oppression system. This will surely shock the collective into realizing where they are.

If the majority comes to awareness of this deception based system then the shift moves from the end of the age of deception and external power into the age of internal awareness and harmony.

Advanced Technology and Ancient Knowledge

The plan is to slowly release advanced technology which will undoubtedly connect with and increase the awareness of ancient knowledge. Such technology nullifies the problems that the planet is currently plagued with, although without a developed sense of the spiritual self the technology becomes destructive.

Cloning, Atmospheric Civilizations, Genetic Stability

Here is something that most people might not have contemplated yet is possibly one of the most important factors at play here.

The vehicles that house the breakaway Human society are entirely environmentally controlled. This means that the air and surfaces are clean of all the viruses, bacteria, or pathogens that are numerous on the surface of the Earth.

This creates a specific difficulty in the situation. Any contact between surface Humanity is so heavily and carefully controlled that regulations go beyond any situations we have present on Earth. If the safety and cleanliness of any of the society's vehicles were compromised this would endanger everyone "on board".

So this explains a very precarious and specific situation we currently face and this is not so different than "first-world" nations contacting indigenous tribes and similarly endangering their society. Everything that happens will be according to a carefully controlled plan.

Training, Simulations and Learning

Part of what went on in the underground base experiments were to design "tests" or "labyrinths" with various people, props, traps, and treacherous situations that were to be navigated and escaped from.

Feedback loops with the brain, consciousness, and environment can create a very complex and integrated learning experience that is customized to each individual learner.

What this would do is create an individual that was capable of learning faster and faster and processing information in a more efficient manner.

This is not the same as specifically trauma-generating situations.

Cloning and Cerebrally Enhanced Soldiers – MILABS

This includes experiments, condition, trauma-based mind control, enhancement, memory suppression and operations that cover a span of space and time.

The NAZI faction has used cloning and genetic engineering to create hybrids, soldiers and everything in between. Religious/spiritual icons, to slaves, to leaders and even robotoids of sorts.

Your genetics BELONG TO YOU as the LIVING(ETERNAL) SELF. These issues are going to come more and more apparent.

If they agree to allow cloning, then who says who is allowed to clone whoever they want, Einstein, for example. And then who permits who to get DNA from history or objects in the world. These issues are going to have to be looked at because they have already been used in ways that are far beyond the basics.

Then what about consent of the masses? This is clearly being put in public because consent is required on an overall scale and individual to include people.

So what if the masses consent overall, would the people who choose to remain be at risk? Would Tribal and Native village life and people who respect the Earth be protected or permitted to stay?

Psychological Testing

These scenarios can also be generated to create specific situations that will contain tests or elements of temptation that will probe the person's psyche for weakness.

Hallucinatory Holographic Mind Probing Technology

Through the neural-interface technology the minds of many individuals can sync together to experience the same virtual simulation. Thus a single individual's mind can be selected for input and the environment will be a construct of their mental activity. The others present will be able to interact with and explore that environment like the person's mind.

Various training scenarios were utilized to enhance the resistance (or lack which) of the mind to intrusion and subversion. These were harsh but allowed the individual to completely control the energy flow in the conscious mind while remaining in harmony with the subconscious.

In a strange yet perfectly reasonable way, the conscious mind acts as the central "self" in that environment, while the subconscious mind becomes the "background" elements of objects and settings, actors and intentions within the flow of the "scene" itself. So a kind of movie begins with drawn out characteristics and perceptions that match that of a highly cinematic movie or intense dream.

The brain is naturally naive to stimulation and if allowed will liken the event to a dream in which the suspense of attention or lack of lucid self-awareness is "acceptable".

The truth may be worse than what you're thinking as far as training simulators and mind hacking devices. The truth may be that the human mind is inherently lucid and self-aware and that it is external influences that cloud the mind into what we consider 'regular' dreaming and 'regular' waking life. It may be that the conscious mind has a much greater access to information through the subconscious mind which is largely covered up and ignored in a rigidly physical and ego-focused society. As well, it may be that dreams are meant to become lucid and that we are often the subject of mystery in other realms that often refer to humans as ‘sleepwalkers’ that don’t know their dreams are real.

Virtual Simulator Training Scenarios

These scenarios can be entirely holographically generated to produce a visceral 3.5 dimensional experience which can be used for training or psychological testing.

Combat Simulators

The name is self-explanatory enough. Situations can be generated which are indistinguishable from the real events. The entire neuronal map of the brain (connectome) can be created and this is by machines to mimic the brain. After calibration through sensory feedback experiences, the sensation of the simulated realm is 100% the same as the neuronal impulses that are detected by the physical brain. An adept souled being can always tell there is a slight difference, but once the machines are calibrated the physical sensation is generally the same while in the machine.

These environments and scenarios can mimic any combat situation to determine accuracy, integrity, endurance, skill, and all areas of aptitude of an operative without the risk of injury or the lack of real-time effect.

Conditioning

As was explained in other sections, these same systems can be used to remove fear of certain scenarios. They can be used for programming the mind. They can be used to train one to complete a task over and over until they can recreate that action extremely quickly in real-time. These devices can be accelerated to operate within a fraction of the time yet to cover training and conditioning that would normally take place over hours, days, weeks, to months.

Programming and Resistance to Psychological Trauma

Through the development of specifically customized scenarios and neural feedback systems trauma can be brought to the surface or specific fears and traumas can be neutralized. This is essentially “facing fear” but in a completely generated environment that will be just as real as the real thing. One can literally face any fear, any trauma, any kind of difficulty and these systems can be utilized to accelerate a process that would normally take weeks to months or years and individuals can be strengthened to their maximal capabilities.

Accelerated Mental Functioning

Some of the technological systems were designed to test the enhanced functioning of an accelerated brain.

The mind can be seen as the energetic component of the physical brain. The physical brain projects consciousness via the electro-chemical processes.

Technology, Accelerated Learning and Repair

Technology has been developed for assisted learning and accelerated repair of tissues.

On Orgone Energy

Orgone devices produce a scattered signal which disrupts the ‘negative’ energy fields. At least this is what I’ve been told.

Apparently if built correctly it will either disrupt the negative emf/harmonics or it will produce positive harmonics, IE: Orgone energy. Orgone energy is the raw energy of life, while dead orgone, DOR, is the lack of orgone energy and can be “found” (the lack of orgone) in thunder storms and illness or depression.

This is exactly what I was told. We are generators for the same energy, and with the correct principles of energy and internal knowledge combined we can produce those very effects at will.

The energy of the mind creates a central vortex within the body. When the frequency pattern emission is consistent with fractal congruence, then that holographic printing of energy can be expanded or shrunk infinitesimally and it will retain the original fractal configuration.

This is what enables transference of awareness between fundamental harmonic layers of the Universe. When one’s consciousness energy pattern is balanced and tuned to itself so that all proportions can be shrunk through a vortex and expanded on the other side, then the personality or self-awareness remains true. This is as if the space/time must turn inside out and only when there is fractal relative polarity in time does the ‘shape’ of the consciousness within the DNA, work both ways folding and unfolding to represent the same mirror image. This is also symmetry in time as far as an ability to reverse the perception and still retain some kind of connection forward and backwards.

Energy Generators and Serums

Generators which produce vibrations that influence the cells to heal at an accelerated rate, combined with serums that enable the fuel for chemical reactions can instantaneously repair tissues.

I couldn’t believe what I was seeing at first, thinking it was a trick. There are serums and energy devices that can influence the healing and general health of the body and even mind.

These devices use energies which extend beyond the physical and are often compared to electromagnetic waves combined with ultrasonic or low to mid frequency tones. These produce harmony on a level that directly interacts with the biological functioning of the body’s cells.

I feel that this technology utilizes the same energy that is emitted from the mind and it is as if the device is “speaking” to the cells in the same kind of universal language of electromagnetic pulses, tones and vibrations.

There is information on energy devices and the use of light therapy in physical therapy today. More is being learned about the power of light and vibrations to influence the mind and body.

Genetic and Cybernetic Enhancements

Certain individuals are also genetically and technologically modified to produce a kind of hybrid human that can heal at a spontaneous rate as well as operate at a much higher rate of speed and efficiency than a regular person. Serums to induce muscle growth and mental acuity are applied, but the main condition is the enhancement of certain features through the alteration of the RNA aspect of the genes.

These features are combined with tech-assisted metabolism and certain biological functions can be enhanced or controlled via a supercomputer. These are the ‘brain-chip’ interfaces which operate to function as a governor for the mind. When the mind becomes too amped up to focus on the details the faster than thought computer system organizes the input into more usable information streams. When the mind is too slow to see the necessary patterns and variables to accomplish the goal, the brainchip operates in a self-preservation fashion and links together information streams to highlight the most viable possibilities.

Such technology is not without warning, much of this is being used heavily in the military field and this has given rise to entire factions of enhanced cybernetic soldiers. Although this is something to know, there are also many other uses for this technology and it is used by people who want to explore the technologically assisted path.

There are many other aspects of this to discuss, or at least a few important ones that will have to be understood to know the greater truth about what is happening on the planet.

Developing The Self

The issues we face are to help us learn about our selves and better mediate the known and unknown aspects of personality. The more we focus on realizing the unknown aspects of personality the less we are seemingly controlled and forced to experience the undesirable aspects of existence. The more we cling to just what we know and what we feel comfortable with the more shocked we are when we inevitably discover the truth of the whole of our existence which is *always* at least one half more than just what we know and are comfortable with. That is the nature of the universe, we can only achieve one half of the equation at any given moment. Once we complete that seemingly whole view of the universe, the information we gain access to instantly doubles and we realize that we were only looking at one portion at a time, just one half of the equation. Then the rest of the equation comes into the picture and we must expand our view once again. This is because we are viewing ourselves as we discover the universe because we are creating what there is to be discovered through the act of exploration in itself. We are the explorer, the explored, the creation and the discovery simultaneously.

Multiple Factions of Space-Fleets, Multiple Goals

Now there are what are called ‘factions’ of groups that have different agendas and interact with the public or surface level population differently. That is one of the main issues. These departments and factions are no longer limited to the surface level of existence and have access advanced technological capacity and knowledge of a larger view of time and a more complete understanding of consciousness and the human existence.

Large-Scale Catastrophes or Series of Meltdowns

I was informed that while they work continuously to prevent and reposition this civilization continually outside of the reach of any large scale meltdowns that the technology is commonly accepted to only be a temporary barrier between the inevitable.

Unsustainable

This society is unsustainable and must either change or will experience the massive catastrophic evens that are foreseen.

There are multiple perspectives that are maintained. They vary by the way of the methodology of solving the problem. All agree that change must occur and is impossible

to postpone forever. The future society is the result of our advancements and achievements. Regardless of how we get there, we must get their somehow.

Earth Changes

I was informed that these changes had been held off and would ultimately be allowed to take place to resolve the current situation. The changes can only be held off for so long, either that or the people performing this task would not be reasonably inclined to postpone these changes indefinitely.

The idea is to locate and secure the members of society who are fearless and capable of assisting in this transition and who hold key genetic elements as these individuals and groups are capable of ‘holding-space’ for the rest of civilization by literally containing the genetic precursors for all those other individuals.

I was informed that Earth changes would be the last event to take place, pretty much like icing on the cake.

This means there will be a lead up to these events.

Mass Consciousness

I was informed that the consciousness of humanity and every species is linked to the bio-etheric field of Earth. When the consciousness becomes too unstable to maintain a controlled society that this will initiate massive Earth changes. This could simply be instigated through advanced technology but I was informed that the advanced technology is actually postponing this so as to allow people to prepare, to get the word out and avoid a complete loss of the human race.

Wars and Manipulation

Wars were described as a way the power groups had controlled humanity over long periods of time. These wars were used to distract and weaken the population and the power groups believed they were holding off a full scale invasion by suppressing the rising population.

Now the population is high enough that another war would be a final war and this is extremely dangerous for the entire civilization. There would be no need for another war to repeat this cycle because the technological achievements have been met and so essentially the ‘reseting’ of the civilization would not be required or possibly acceptable.

This is why war is to be avoided however people are very easy to manipulate through lower emotional and mental programming from media and social cues. People follow the herd and the herd is essentially still operating on animalistic parameters. There is a have coating of peace and humility but this is just a wax coating that quickly evaporates as soon as the pressure of mass unrest or scarcity is realized. Many simulators have explored these possibilities.

Financial Unrest (or reset)

The idea is that financial oppression is used before wars to distract and oppress the population. When people are busy looking for resources to survive, they are not focused on the larger picture. This is part of the ‘fight or flight’ response mechanism tied to lower brain complexes which are primarily activated to keep the masses in both a highly sensitive and unstable state of being while also keeping them easy to control.

If the civil unrest reaches a level where awareness continues to rise even though financial hardship is being implemented then the latter two options will not work. At that point artificial disasters can be produced as well as natural Earth changes which initiate a shift of the ages and of consciousness.

The paradox or maybe irony here is that the oppressive actions are used to both suppress human awareness up to a certain point and simultaneously to stimulate and arouse the human spirit into wakefulness and self-empowerment. This is part of the reasoning regarding why these control systems are allowed.

Some say the elite don't want an economic collapse. That it would ruin everything. Others say it would be icing on the cake. Some say that it is a zero-point world that will save us. That the Fukushima is a big problem. Zero-point field tech, that is. Generators and energy sources, healing and terraforming. I know we project right? We see it in our own lives. So we can project with each other and grow that as a group and that part of the world will exist in that light. Which sounds Biblical, which may be because they're following prophecy. But it may also mean that we have a light, a chance, a real salvation, but that we have to grow that here and help develop it. To pass it on like love and such.

That's apparently what it comes down to. That these cycles happen every so often and we're in the midst of one right now.

Let's make it count. Every day, thought moment. With mindfulness, intention and awareness in action. Life is literally higher dimensional, so we have to become multidimensional to really face it. Indeed, that is a good perspective on action and inner being. It's like a fractal, whatever we project inside that chest center, will project into our mind and the outside. But we have to be stabilized and grounded through the root first and then to get to the heart energy must pass through the sacral/sexual centers and continue upward.

Self-Responsibility

The main reasoning is self-responsibility. We are responsible for ourselves. The people are and so if they allow themselves to be tricked and prodded like animals while behaving for the part, then that is how their experience will play out.

Clones and Synthetics

One seemingly unfair aspect of this is that there is a larger portion of non-humans than there are humans and so these beings without the human spirit will be easily programmed to support and propagate the mind-control system and the oppression. Thus, if people follow the herd mentality then they will walk directly into the end-time scenarios yet it is the humans who will actually stand to lose. People must wake up to these tricks and this technology so that they can orient themselves with the reality of this situation while learning to strengthen themselves and adapt to the manipulative aspects of this control system.

Spiritual Power and Divine Truth

This is essentially all about spiritual power and humanity stepping into the power of the truth behind their existence.

Some say that humans are designed as slaves, but if this is so, then it is the power that humans contain within that is the ‘work’ that they are sought after for. This indicates that humans have great powers that others cannot achieve on their own, even if they are creator lords.

Thus, whether humans are modified or not, they have great power. If they are not modified to perform this role of an energy generator, then this is just a confusing mind-control game that has been pulled over the eyes of humanity and humans have always contained true internal spiritual power that allows them to exist without having to parasite and steal the energy and knowledge of others. Humans are reality generators , we can choose how we want to experience the universe and what kind of collective world we want to enjoy together. Once we step into this power, there is on greater force. No amount of non-human entities can change that as we are somehow intrinsically linked to the ether-space of this realm through the spiritual and physical aspects of our being. That is what is sought after and so those who do not have this manifestation power attempt to utilize humans to create their own reality through this Earth situation. That is the basics of the ‘alien overlord’ system, whether humans in disguise, non-humans operating with alien intelligences, supercomputer systems, or spiritually degraded beings.

Most people are not ready to see themselves or the true nature of humanity. Reality is largely an illusion of the conscious mind. The hidden aspects are the other half of the equation and this is perceived by the shadow aspect of the personality and mind. We are only marginally aware unless that aspect has been unveiled and through this process the reality of the human soul can be actualized and realized.

I was informed there would be a period of two suns and multiple mirages around the world. People would believe they were peering into another dimension, floating cities, or some kind of city-ship craft.

Synthetic DNA, Synthetic Genetics

Through the previous described replicator devices synthetic DNA can be engineered. Thus, entire genetically engineered codons can be produced and form this created beings can arise. These are the hybrid beings that are performing many tasks underground and even on the surface. On the surface there are synthetic genetic create beings or genetically engineered beings that appear to be human but do not contain a human genome. There are also clones and replicants of humans. There are a variety of non-humanoid forms but these are largely kept underground. These are beings we often see in science fiction movies or shows.

Time as Mathematics, Series of Equations, a Programmable Storyline

When using the technology, time can be understood to be a series of programmable variables where one variable is centered within a series of parameters and from these possible variables within a parameter set a series of possible functions or outcomes can be process. Thus, these people can literally plug into a supercomputer system which operates based on this form of processing reality and through this they can observe all the possible realities that may connect to a present moment. This allows one to travel but this is not part of this section of the explanation.

What this allows one to do is know exactly what is going to happen and when. If a person is being interrogated, all that has to be done is the operative using the technology simply thinks of what they will say and intends to do it within 6 seconds. The machine will play out a future timescale regarding the input of that question or interrogative speech and then produce the possible results. If this doesn’t give the desired readout in the mind of the operative, they will refuse to go that route and think of another pathway. This repeats for a few seconds to a few minutes. Then the computer has found the pathway that is most like to yield a result. The operative simply steps forward, says ten words, the subject breaks immediately and tells them everything they want to know. This is obviously takes longer for most trained individuals, however that is how easily it would be to use this technology to produce an effect on a regular surface level human. They would have no defense, no way of knowing how that individual could know so much or be so direct. This is how operatives dealing with certain power groups will operate in the surface level population and individuals always feel that these people know way more than they are leading on. That is because they are, they know more about you and your life experience than you do.

Chapter 2.3 Previewing Solutions

Neutralizing Polarization

The mental-emotional tendency to pick sides, to fight, or to basically join in the fray that is currently taking place is a kind of deception of polarization which enables the leeching of emotional and mental energy from the human. This is more of a psychological unveiling where the true nature of the self, the duality game and the transcendent source aspects can be made visible to the individual. The they will see how every polarization tactic is actually taking them out of their true source of power by pushing them off center emotionally and mentally. There are teams that are capable of enabling this process and assisting as humanity realizes that half of the problem is that the unchecked mind is one’s own worst enemy.

Removing Etheric Implants

Technology can identify and isolate these foreign body implants which are etheric technological devices. These are literally frequency or phase-shifted devices which are invisible to this layer of physicality but are capable of being organized and attached to the etheric field of the human and will operate to siphon or limit energy on the etheric level. Of course, this is all technology of the vampiric created beings who parasite on the original Earth inhabitants to sustain their existence.

Clearing Astral Body

By moving through the temporal body etheric implants can be deactivated and removed and then the astral or emotional body will be able to function closer to the original levels of presence and sensitivity. This body is manipulated when one is emotionally shut down from trauma. Thus this body can be scarred and will function at a much lesser level of activity or presence until the emotional damage is healed. This contains the memories of all the emotional events of a person’s life.

There is technology that enables one to access these levels of frequency and clarify or untangle emotional chords or attachments which are used to siphon energy from the human being to the parasitic created beings. These chords are energetic in nature but also have technological components.

Knowing the True Self; Soul Actualization, Unveiling

This is a sacred, ancient process that has been outlined and discussed since the beginning of time. Humanity is here to learn, grow and express the self. In doing so, like a child moving through layers of infancy and into full-wakefulness of their body and the physical world, humanity can come into awareness of their true spiritual nature and the true spiritual nature of the universe. This is the process of soul or self-actualization that is described in some psychological methods such as Maslow’s hierarchy of needs and the self-actualization that results in a complete fulfillment of all psychological needs. In this modern psychological view, self-actualization is described as the desire and process of reaching fulfillment of one’s own natures and then living their life sharing that self-empowerment with other beings because after gaining your self that is the highest expression of such knowledge, sharing that power with others.

The true self is not limited to the physical body, the true self is a reflection of the entire universe and thus the primary original creative force. This is akin to the whole equation rather than just half of the equation. The visible aspect of the self, the conscious mind, is only one half of the entire equation. The whole equation consists of what we see visibly and consciously as well as what we are limited from seeing within the unconscious and subconscious mind. These are really two layers of the same ultimate source. Like an iceberg which is only partially above water, the subconscious mind is the proprietary wholeness of experience. The conscious mind is only a surface layer of reality while the unconscious mind carries all the notions, the multidimensional processes, the latent aspects of reality that we are not capable of seeing without unveiling these aspects through inner exploration.

Taking Responsibility

This entire show is about taking self-responsibility. Unless people begin to do this, there will be no hope. Right now people are convinced that their responsibilities belong to someone else even though this always results in pain and discomfort. To take responsibility is painful at first because we have a lot of work to do, but even then, this is beneficial because there is no way to remedy the pain and discomfort of being lied to and disrespected if people continue to hand their free-will over to others through blame (scapegoating), lower emotional bio-emissions (hatred, anger, etc), distractions and addictions (technological, sensual, and chemical or food based), or generally complaining without taking the first step towards providing something beneficial. This is the victim role, if humanity is to take control then they to help each other and themselves by not relying on false promises and false authorities to determine how they feel, think and live.

Returning To Center Emotionally and Mentally (spiritually)

Balanced food intake, rest, exercise, activity and learning are all continual requirements for a healthy existence. Emotional and creative expression nurtures the soul. Without these ways of being and learning the human qualities of experience diminish and creativity dwindles. There is most likely going to be a split between those who can sustain their own humanity and those who have to cause others to suffer to do so.

Vampires in the “Awake” Community

Contrary to popular belief, the majority of the non-humans are not necessarily vampiric and in power. The vampires are the people online who try to get a rise out of others for sharing their own experiences. They are the nosy neighbor that feels that the person who looks or acts differently must be considered and enemy and armed against because they feel themselves to be so much better. The majority of people are vampires, they believe that they must work for someone who will trade them money and that the amount of money they have based upon the amount of indirectly beneficial work they do puts them above others.

This is not different in the ‘awake’ community and in fact I feel that there are higher concentrations of vampires in this community, the alternate media because everything is largely a joke and a trick. People are operating on deceptive agenda schemes to divide the people and this is most intensely noticed when there is a realization of the truth behind what is happening and people begin to point fingers. The only people who are cleared to point fingers (and who also will NEVER point any fingers) are the operatives from the secret projects that have the capacity to do so because they have reached a specific level of awakening and this is related to the droning, cloning, and hybridization process. Only a specific few know who has been transformed into an impostor being and who is remaining strong and this is due being briefed on the surface level situation. Anyone can say what they want, they are simply playing into the tactics of mind-controllers and parasites and the more they play in the deeper the infection will grow. All the people pointing fingers now are actually implanted and vampiric and are attempting to drive a divide through humanity and they are the first who will turn on their friends and family when the going gets tough because they are more interested in others and starting drama than healing themselves. Ironically, this is all done under the guise of “healing” and “getting rid of the drama” AKA people they don’t trust. They pick and choose based on their own personal bias and this is a sure indication that they are emotionally and mentally out of alignment and are feeding deep seated personal fears from their own traumatic experiences.

These traumas must be healed and the harmonious center must be reattained where a person can focus on their own existence and waking up instead of acting as false-light, “king of tyranny” gatekeepers for others. Those individuals are going to be left behind if they cannot kick the habit because if they are allowed into any kind of healed society they will quickly degrade into animals and attempt to restart a devolution process in order to gain the power they so desire but cannot produce on their own. ANYONE playing ego games of trying to hurt or put blame on ANYONE else contains this viral implant and has not kicked the virus.

Heart Center and Psycho-Spiritual Fulfillment (self-actualization)

Emotional connectivity is a form of telepathy, when loved ones can tell the state of another across space and time. Whether it is family or friend. In the 60's and a little before that the US found a specific frequency akin to a radio frequency that operates on a trinary spectrum. They called this the "telepathic wave". In time, they could completely read and send thought waves without frying the brain or body through radiation. Which was what the early machines did. They actually took satellite dishes and aimed them at people. Then realized they could turn it around and do it backwards with a better effect and minimal radiation. Either way they started beaming the base and then towns around them with waves between 400 and 432 MHz and caused waves of crime sprees or peace sprees throughout the 70's and 80's. So they can digitize the telepathic wave to induce artificial telepathy. But this is organically done through an entanglement through what we call love. Literally. The Germans found it before that. And the secret orders before them. And ancient Egypt before them. As humans we remain basically through the root, heart mind connection. When the heart overpowers the mind connection of spirit, then the body is a trinary whole. When the mind guides it is binary and cannot by guided by the spirit. The spirit has direct access to the heart. The mind is a computer of sorts. The mind doesn't see past duality. The heart is the true center/eye of the spirit. The reptilian brain is the dragon and when you tame the amygdala then fear is ‘behind’ you. When the mind is "untamed" the reptilian brain takes over. This is the lower brain and amygdala fight or flight response.

This happens when the energy of the brain, body and spirit increases due to whatever various reason of spontaneous or controlled increase. Because of the "temptations" which are the easiest flow of emotional energy into a "discharge" state, is that the sacral/sexual center ties to the heart and reroutes to replace the heart and control the mind. Mental and emotional contemplation of one's true purpose and nature is the path of the divine. We find ourselves simply by looking in the right place, not in the world, but in our self energetically. We are more powerful than the programming, and we can reverse this is we're careful and devoted enough.

We have to be faster than thought, at the speed of spirit, beyond matter. When we start thinking on this level then our influences spread to others throughout the sphere. It is our destiny to know these things but they have been kept from us. The ancient orders called this the art of "implosion". Traveling realities through intense contemplation and a usage of sacred geometrical forms.

They developed and combined orders around WW2 and developed zero-point energy tech that can alter space/time fields. This is timeline manipulation. But as a rule, we go where our heart leads us. So that's how this is solved.

Go Within to Observer the Self

The answer is literally by looking within to find the great truth rather than looking around us. Everything we need to know is within us, energetically and spiritually. Our emotional, mental and physical state of balance is an indication of where and how we exist in relation to the larger overall truth. Everything that happens around us to distract us is designed to stop us from looking within. Nothing can truly stop us, nothing can actually input the holographic horrors in our spiritual center but simply perturb the brain and body. The mind is a non-holographic spiritual environment that cannot be excessed and the invader's goal is to convince people to use their imagination or their creative powers to produce these horrors on their own. This is through the programming. We must clear out the programming, the trauma, the lower-dimensional constructs and fill ourselves with the truth and spiritual presence that enables us to be self-aware in the first place. If we aren't doing this, then we are either in pain, or there is no spiritual presence to be in pain. If we are doing this, we are either clearing out the constructs by replacing them with true spiritual presence and self-awareness or we are becoming aware of them.

Organic Feedback Loop

The great feat is mentally bridging the great rift between us by looking within. Which is paradoxical.

We can never see what another is perceiving exactly, well for the most part, so we all have to kind of accept that we are communicating effectively and truly get to this level of comfort by simply being secure in knowing who we are our selves.

Technological Feedback Loop

So then knowledge, in a way, when shared, is a form of telepathy. Group telepathy.

Group think, when ideas or memes spread, is a form of group telepathy.

The Internet is like artificial spreading of telepathy. This means what is normally mentally bound signals can be initiated and spread through a digital medium.

Breaking Soul-Contracts

Ultimately everyone is under a series of “veils” which are energetic time-constraints literally like 9 dimensional layers of temporal restriction which are each bounded and ruled over by invader beings. These range from physical authorities, to astral entities, to programmable matter, to supercomputer intelligences, to spiritual false-light beings and our own shadow mind. Each layer of reality is successively guarded by these beings who are here acting as gatekeepers designed to push people back when they begin to wake up. These beings all work through fear and deception and the last layer is based on mirroring our own energies back to us like an impostor. All the levels tend to imitate, however the last layer is a near perfect imitation of our own energy to the point where people often switch places with this being before getting out of the matrix. There will be more discussed on this in a later section.

The “9 veils” were designed by impostor beings as a last effort to stop humans from escaping the false-light matrix which is essentially the holographic universe. This is literally like a maze which reproduces a new pathway and a new doorway each time a person nears the last hallway or doorway that is next to the exit. So one eventually has to project themselves into the exit using their whole being and moving past and through the tricks by not falling for them before they are placed. This is highly confusing but this is essentially a kind of labyrinth that has been created to stop people from leaving so that their soul energy can be destroyed and used as a generator for the false-light system which is an AI over mind that is programmed to take the raw soul energy and destroy the identity by inverting the electromagnetic spectrum and incorporating that inverted energy into its own internal matrix body which is literally the false-light universe.

Help Everyone

Now they may have been setting us all up for the apocalypse. They said they want us to tell on them and get the whole world aware of what they've been doing So that we can stop them and pull them from the dark which is ACTUALLY taking their souls. There are also breakaway civilizations involved in this entirely zero-point/free-energy.

Chapter 2.4 How Timelines Collapse

Repeating Cycles of Time

Because of the way time works and the ability of those using these temporal devices they have set up an elaborate labyrinth like a spider web of false realities, timelines, parallels, sub-dimensional layers, astral cages, temporal dead-ends, and time loops which act to stop people from reaching the true reality. As a result, many portions of this timeline are literally in a free-will ‘time-loop’ and these loops must be canceled out. As well, because of the nature of these loops on the overall stream, our entire civilization has been looping for the past 6 time-cycles meaning we have reached this time in history 6 times before and this is apparently the last time because we have never gotten this far before and the events of the future are having to be programmed in manually at this point.

Beings From the Future

As are result and damaging time, what happens is that the beings from the possible future that is being damaged appear to try to heal the break as well as those who are from the new possible future that is generated, this results in a time war between both possible realities for the present realm. This is what has been happening for thousands of years. All the ancient spiritual texts are describing this system. One group is a from an original possible future where everything is based on the presence of spirit and souled humans, another is from the new possible future where an AI overlord took over and removed the souls and spiritual energy from all entities on Earth rendering this a holographic prison without any other use. That reality dissolves into itself and so the time beings are constantly moving backwards and jumping timelines to try and obtain more energy.

Beings From Collapsed Timelines

The beings from the collapsed timelines are those who travel through hyperspace to get here. They then recreate themselves using cloning technology through hyperspacial means, IE: creating an alternate temporal dimension so that these devices can sustain them and literally "hold-space" for them. Then if their timeline is destroyed, they can still exist as a 'loose-end' in space-time. This is extremely dangerous and I will say we have some Human operatives jumping timelines searching for Earth and Humanity so that they can find a reprieve from this time war.

That is the most trying aspect of this entire ordeal for me. There are some human operatives literally in hyperspace without an opening into the temporal stream for them to reintegrate into this timeline. We must assist them, we must open the timeline by taking control of Earth from the invader races and those who wish to depress and isolate the spirited and souled human beings. We must re-organized and neutralize the invasion forces of deception and assist our humanity and maintaining their free-will, their self-awareness, their self-empowerment and their emotional, mental, and physical harmony.

Beings Who Would Never Have Existed in the First Place

As a result of this entire process, there are essentially beings who have been erased from time who degrade in this dimension and can only interact periodically. These are the created beings who operate through supercomputer forms that are placed within cloned bodies and powered by the transdimensional quantum supercomputers. These are the 'parallel' reality beings and this relates to the hive mind invasion. When all the original aspects of time are restored, these beings would not have ever existed in the first place as there is no quantum link for their probabilities to remain neutral and present in the original run of things.

Again, all beings who operate under the will of the universe, even when they are attempting to trick hyperspace and time, when these beings assist and help in the unification of sentient, spirited, souled beings they are capable of being healed. This is all because there is an original creative force which can produce souls that are eternal and everlasting, meaning they are not created but simply always ever were. Yet, there is a "miracle" effect where beings can be given eternal life. This is only by reflecting the will of the whole of existence, rather than a portion or a part because this is only temporary. Only the whole is forever and this takes true harmony, true balance and ultimately *self-lessness*. To give to others because you see them as worthy because they can be aware and enjoy the gift is to be like the creative force that gives life to all and enables all experience in the first place. By acting in correspondence with this we reflect the will of the whole and that power and action transfers into protection and self-empowerment for ourselves. This cannot be cheated, tricked, or rerouted as that is the karma game that has been played by delaying time and rerouting energy through getting others to take on the responsibility for others bad actions. In the end, all karma has only been delayed because when the stops are pulled out, *everyone* ends up getting their karmic returns regardless. They simply intended to build up so much karma that by the time the ties are cut, the karma overload will simply kill them instantly. This never happens and they end up in the abyss, this is the final time so since there is no recycling of the universe from the oroboros system then whatever happens is what happens forever. If everyone wants to move into harmony, to receive healing, to receive forgiveness then they must assist in the creative force in healing, forgiving, and turning away from the deception, the cruelty, the vampiric actions.

Many vampires believe they will die if they stop. The only hope is to admit their ways to the others and ensure that there are enough beings around them that will protect them so that this situation can be handled properly, with due care, compassion, and the necessary healing to ensure the safety and protection of all who seek harmony.

IronAmmonite.com

SULFATO DE CALCIO

Schematic of the RF-system


CONFIGURATION SWITCH
LOW BAND ANTENNA
LOW BAND ANTENNA
CONFIGURATION SWITCH
HIGH BAND ANTENNA
HIGH BAND ANTENNA
BALUN
AUTOMATIC TUNING UNIT
ROTARY PART
FIXED PART
LOW VOLTAGE ROTARY JOINT
INSULATION SWITCH WITH MEASUREMENT ADAPTER
RF ROTARY JOINT
TRANSMITTER

PRINCIPAL LAYOUT OF INDOOR RF SYSTEM

Design

- Full in house engineering capabilities
- Latest design tools
- Rigid tubular steel dipoles
- No suspension/counterweight system
- Overall DC grounding of antenna and screen
- High-Band/Low-Band array
- 30 years of experience

Performance

- High reliability
- High availability
- High flexibility

Maintenance

- Easy access to components
- No lowering of dipoles and screen

Cost efficiency

- Low life cycle cost

More than 30 years of experience
30 years of antennas on air



COMPARISON TO CURRENT TITLEHOLDER

ARECIBO

Since it was constructed in 1963 in Arecibo, Puerto Rico, this telescope had held the record as the world's largest telescope.

FAST

It's designed as a cable-net supporting structure, capable of forming a parabolic mirror and will be completed by 2016.

SIZE





ARECIBO

Arecibo has a fixed spherical curvature.



FAST

FAST can reshape into a paraboloidal surface.

ASTRONOMICAL GARDEN

URUMQI NANSHAN
25m
Radio telescope
Built in 1994 in Urumqi, Xinjiang.
Missions: Pulsar research.
Determines orbits for the Chang'e lunar satellite and other lunar projects.

QINGHAI DELINGHA
13.7m Millimeter-wave radio telescope
Built in 1990 in Delingha, Qinghai.
Mission: Interstellar molecular spectroscopic research.

MIYUN
50m
Radio telescope
Built in 2005 in Miyun county, Beijing.
Mission: Long-term monitoring of a group of known millisecond pulsars.

MIYUN
Synthesis radio telescope
Built in 1983 in Miyun county, Beijing.
Missions: Northern sky survey and observation of Supernova Remnant and interplanetary scintillation.



KUN-MING
40m
Radio telescope
Built in 2006 in Kunming, Yunnan province.
Mission: Successfully completes the VLBI tracking of China's first lunar probe Chang'e-1 with other Chinese telescopes.

SHANGHAI SHESHAN
65m
Radio telescope (under construction)
Built by 2012 in Sheshan district, Shanghai.
Missions: Finds applications in deep space exploration and basic astronomy research and assists China's lunar exploration program.

SHANGHAI SHESHAN
25m
Radio telescope
Built in 1986 in Sheshan district, Shanghai.
Mission: Assists the VLBI (Very Long Baseline Interferometry) network.

GUIZHOU PINGTANG
500m
Aperture spherical radio telescope (under construction)
Built by 2016 in Pingtang county, Guizhou province.
Missions: Surveys neutral hydrogen in the Milky Way and other galaxies, detects faint pulsars, looks for shining stars and listens for possible signals from other civilizations.

Source: Skyandtelescope.com, universetoday.com, URSI

GUILLERMO MUNRO / CHINA DAILY






N
NORTH ARRAY
LITTLE MACHIAS BAY
N1
N11
N12
HELIX HOUSE
N2
N10
N3
N0
N9
N4
N8
N6
MACHIAS BAY
N5
TRANSMITTER BUILDING
TRANSMISSION LINE TUNNEL
N7
S11
S1
S12
POWER PLANT
FUEL PIER
S2
S10
S9
S0
S3
S8
S4
HELIX HOUSE
S6
CAPE WASH
S7
S5
SOUTH ARRAY

Figure 1. General layout, Cutler Peninsula.


Deep Cove
Little Machias Bay
Great Pond Cove
Little Holly Cove
Big Holly Cove
Imagery ©2012 Cnes/Spot Image, DigitalGlobe, GeoEye, US

26 TOWERS- 850 to 1000 FT HIGH



EACH INSULATOR IS 57 FT LONG TO WITHSTAND 250 KV



13,000 lbs.



TUNING NETWORK- HELIX



Ref 8

TUNING NETWORK-VARIOMETER





(c) 1998 JAMES P. HAWKINS - WA2WHV

Ref 5 NAA Wires are 4 inches diameter NSS JP Hawkins

SUBMARINE RADIO RECEIVERS



USS Robert E Lee 1966



USS Nautilus 1970s





Sources: Council on Tall Buildings and Urban Habitat; Greatbuildings.com; PBS.org; Skidmore, Owings & Merrill LLP

TIME Diagram by Joe Lertola


THERMOSPHERE
MESOSPHERE
STRATOSPHERE
TROPOSPHERE
93 Miles
150 Kilometers
53 Miles
85 Kilometers
31 Miles
50 Kilometers
39k Feet
12 Kilometers
ARTIFICIAL MIRROR/LENS
ARTIFICIAL AURORA
AIR GLOW
NOCTILUCENT CLOUD
NACREOUS CLOUD
OZONE LAYER
WVH
WEATHERMODIFICATIONHISTORY.COM
IONOSPHERE
1
2
3
4
5
6
7
8
9
10

Image by Jim Lee, **ClimateViewer.com**

1. Ionospheric Heater
   MICROWAVE, NOCTILUCENT, PLASMA CLOUDS, ELF/VLF
2. Sounding-Rockets
   CHEMICAL RELEASE, NACREOUS, NOCTILUCENT CLOUDS
3. Satellite CHEMICAL RELEASE, DEW, IONOSPHERIC HEATER, ELF/VLF GENERATION
4. Lasers
   RAIN CCN, IONIZATION, CHANNEL LIGHTNING
5. Cloud Seeding
   CHEMICAL RELEASE, RAINFALL, HAIL, CLOUD CLEARING
6. Cloud Ionizers
   ELECTRIC RAINMAKING WITH IONS
7. Stratospheric Aerosol Injection
   GEOENGINEERING SOLAR RADIATION MANAGEMENT (SRM) CHEMICALS CREATE SUNSHADE: SULFUR, ALUMINUM, TITANIUM, DIAMOND DUST, CALCIUM, BISMUTH TRI-IODIDE.
8. Ship Tracks
   MARINE CLOUD BRIGHTENING (MCB), STRATOCUMULUS
9. Contrail-Induced Cirrus
   CIRRUS CLOUD CREATION, TRAPS HEAT, MELTS POLES
10. Water Vapor Pollution
    CLOUD CREATION VIA: SMOKESTACKS, COOLING TOWERS, WSAC, TMS-65, J2X ROCKET, JET ENGINES

Red Numbers: Considered Inadvertent, Accidental, or Pollution...
unless intentional. Objects not to scale. Not included: steering atmospheric rivers

WEATHER MODIFICATION TECHNOLOGIES 2018

HAARP


U.S.
PATENT
4,686,605
Awaken the mind
WEAPONIZED WEATHER CONTROL
/ Awaken the mind.

Notable quotes from patent:

- "A means and method is provided to cause interference with or even total disruption of communications over a very large portion of the earth"

- "Weather modification is possible by, for example, altering upper atmosphere wind patterns or altering solar absorption patterns by constructing one or more plumes of atmospheric particles which will act as a lens or focusing device."

- "The earth's magnetic field could be decreased or disrupted at appropriate altitudes to modify or eliminate the magnetic field."



Storm clouds drop as little as 10% of their water as rain or snow. 'cloud seeding' has been used since the 1950s to coax more from them.

1 Silver Iodide crystals have almost exactly the same shape as ice crystals

2 Water droplets 'supercooled to less than 32°F (0° C) attach to Silver iodide and freeze)

3 Ice crystals stick together and begin failing as snow within 20 minutes

4 Water releases heat as it freezes; warmed air rises

5 Updrafts lift moist air into cloud making more snow

Sowing seeds in clouds

Radio a galena FM

per la "banda commerciale" 88 – 108 MHz




150 cm
75 cm
150 cm
ATX
150 cm
D1
L1
L2
CV1
CV2
R1
C1
D2
Cu

Figura 2: Schema elettrico della radio a galena FM.

I componenti adoperati sono:

- L1 = vedi testo (sezione Bobine L1 e L2);
- L2 = $0.137\mu H$, vedi Figura 7;
- CV1 = Johnson 160-211-1 $(2.7 - 10.8)pF$ per sezione;
- CV2 = trimmer tubolare da $(5 \div 15)pF$;
- D1 = diodo Schottky Skyworks modello SMS7630-001;
- D2 = diodo di segnale 1N4148;
- R1 = $47k\Omega$, $1/4$W;
- C1 = $100pF$ ceramico a disco;
- Cu = cuffie ad alta impedenza ($2k\Omega$ o superiore);
- ATX = connettore ATX femmina e header pin;
- Due connettori banana femmina.



Figura 8: Vista posteriore del cablaggio



Figura 9: Particolare del diodo sulla basetta millefori.



Figura 10: Cablaggio del diodo rivelatore.










F3
MATH MENU
F5
CE




evapora
le resine,
prodotti
genere
adatto per
parti in m
UN 1090
PERICOLO







10 mega
5nF
2N3725
+
3 V
-
in pratica ho usato
filo argentato da 1,5
16 mm
21 mm
al variabile
al diodo
al variabile
alla piattina
1
Gate
Surce
Drain
EPAD ALD 110900
protezione
GATE
DRAIN
SURCE
vista da sotto
10 mega
5nF
2 spire
AA143
EPAD
gate
drain
surce
18 pf
2-15 pf
47k
82 pf
0,1 F
82 pf
+
-

In sostituzione dell'EPAD: fa fortissimo ma occorre una pila

ALD110800vista dal sotto

In sostituzione dell'EPAD, ma richiede almeno 1 V di alimentazione rubata

NOTA
con un buon segnale
funziona senza amplificatore

piattina da 300 ohm
cortocircuitata
sopra e sotto
(144 cm per 100 MHz)
appesa verticalmente

diodo a
3,5 spire

Tenendo
staccata la cuffia,
col condensatore
da 0,1 F si raddop
pia la V di aliment.

anche
a distanza
tenendo staccata
la cuffia

GALENA PER FM AD ALIMENTAZIONE RUBATA
L'EPAD si può trovare presso la MOUSER USA,
Monaco, Milano

la piattina è lunga 0,96 lambda ovvero 144 cm per 100 MHz

La calata può essere
di piattina oppure il
diodo subito al dipolo
e poi due normali
conduttori


ANTENNA
SELETTIVITÀ
SINTONIA
MEDIE
CORTE
MEDIE
CORTE
CV2
L3
DETECTOR
OG2
L2
A
B
C
CV1A
CV1B
A
L1
B
C
2000 pf
TERRA
CUFFIA

Un progetto di Luciano Loria


presa antenna
presa terra
270 pF
2 x 350 pF
2 x AA117
presa cuffia
sintonia


Antenna
D1
C1
D2
L1
CV1
L2
CV2
Cuffia
Terra

Materiale occorrente

L1; L2 = 90 spire filo rame smaltato Ø 0,3 mm
su tubo isolante Ø 3 cm
CV1; CV2 = variabile in aria 350 + 350 pF
C1 = condensatore ceramico 220÷330 pF
D1; D2 = diodo al germanio (AA117)

Schema elettrico


IN
0
1
2
3
4
5
6
7
8
9
10

can see I left the existing 1N34 diode mounted, so that it can be reinserted to make compariso

For the tests I used my receiver with a panel antenna , experimented with great satisfaction a few years ago. To adapt the reception circuit I had to make some small changes, obtaining a scheme like the one below:


ANTENNA A TELAIO
AURICOLARE A CRISTALLO
A
2,7
ALD110900A
4
3,6
2nF
A
CV
365pF

We increase sensitivity through the use of a
modern zero-threshold mosfet, always without power supply

Principle of operation

From time to time, some new devices appear on the market for electronic components, suitable for experimentation in a "crystal" reception circuit. It happened a few years ago with low-fall "schottky" diodes (BAT46 etc.), which were proposed as good substitutes for old germanium diodes. Recently I have read this article by Peter Hobbs, in which a recently released device is presented, the ALD110900A , mounted in a "high sensitivity" crystal receiver. This is a double mosfet with **a conduction threshold equal to zero**, ideal for detecting without loss a very weak signal like the one that is formed in a crystal receiver. The author proposes the realization of a scheme similar to the following one, which turns out to be of the synchronous detection type.



According to the author, the sensitivity is so high as to allow the realization of a receiver without an external antenna, based on the use of only the ferrite antenna, like that of transistor receivers. Its scheme uses as a transducer a telephone capsule coupled to the receiver by an adaptation transformer (this solution deserves to be better investigated).


Antenna
S
CV
D
C
Cuffia
Terra
Schema elettrico


Bobina a fondo di paniere
Condensatore variabile
Diodo al germanio
Condensatore 2200 pF





First off, check to see if the parts match the parts list…

1 – 1/2" x 3" CPVC tube
2 – 5/8" O.D. vinyl caps
1 – 3/32" dia x 2.5" brass rod
1 – 4-40 x 7/16" pan head screw
1 – 4-40 x 1/4" pan head screw
2 - #4 internal tooth lock washer
1 – 4-40 nut, steel
1 – 4-40 nut, brass
1 – 3/32 x 2" tyrap
2 - #4, 14-16ga ring terminal
1 – PCB
1 – D1 - 1N34A diode
1 – R1 - 4.7M 1/8w resistor (YEL, VIO, GRN, GLD) **See note**
1 – C1 - .01 disk ceramic capacitor (103)
3' – RG-174 coax
2 – banana plugs, 1 red, 1 black
2" – 3/16" dia. shrink tubing
1 – alligator clip and 9" lead
1 - copper foil tape, 2.25" x 2"
1 – self adhesive label


RF PROBE REV A
SIGNAL
C1
/09
R1
HENDRICKS QRP KIT
DVM+
DVM-
D1


PROBE REV A
SIGNAL
DVM+
HENDRICKS QRP KITS
DVM-
1/16/09




RF PROBE REV A
SIGNAL
1/16/09
HENDRICKS
QRP
DVM


4-40 X 7/16" SCREW
RING TERMINAL
LOCK WASHER
FOIL










Hendricks QRP Kits RF Probe
www.qrpkits.com
78189
QRP KIT
L10
L21
R6

Look in the files section for **Dar's (Darwin Piatt) – W9HZC** application and usage tips for the R.F. Probe.


TO TEST POINT
TO TEST CIRCUIT GROUND
C1
.01uF
R1
4.7M
D1
1N34A
DVM
+
-

ELECTRIC ENERGY FROM SPACE:



Cosmic ray ionization

Aluminium plate (foil)

1N4148

+

-

~ HF exciter ?

GROUND

RF tip for Multimeter and Oscilloscope


Probe
.01uF
4.7M
DVM +
1N34A
GND
DVM -

KA8MAV RF PROBE

The project **RF tip** is simple, not need special components and there is no great difficulty in its construction, making it ideal for beginners. The creator of this tip was the amateur KA8MAV, hence the name of the tip arose. Above the electronic circuit probe.

List of components for the tip RF

1 Germanium diode OA79, 1N34 or equivalent
1 Capacitor 0.01uF
1 Resistor 4M7 x 1/4 Watts


RF Probe by KA8MAV
November 25, 2001


in
ctr
sh
out1
out2
10 T RG-174 ON FT114-43

N5FC 2002


ctr
out1
sh
in
10 T RG-174 ON FT114-43
ctr
sh
out2
10 T RG-174 ON FT114-43

N5FC 2002

N5FC 2001


0.01uF
4.7M
TO RF TEST CKT
TO VM +
TO VM -
TO
CKT
GND
1N34A

CLASSIC RF PROBE

Reads RMS Equivalent Voltage in test circuit, if Voltmeter is 10 -11 Meg Input Impedance;
Reads 4X RMS Equiv Voltage if VM is 1Meg Input Impedance (Set VM to measure DCV)


BALLPOINT PEN
PAPERMATE FLEXGRIP MED.
0.01uF/50V CHIP CAPAC
4.7 MEG RESISTOR
XYL'S SEWING NEEDLE
SCRAP PC BOARD
SET, BANANA PLUGS RS 274-734
1N34A Ge DIODE
3-FT HUNK SHIELDED CABLE
N5FC
2001

1. USE DOUBLE-SIDE PCB
2. CUT SCRAP PC BOARD TO 2-1/2" L x 3/16" WIDE; CUT NOTCH ABOUT 1/2" L & 1/16" DP; PUT TWO GROOVES APPROX AS SHOWN (NOT CRITICAL) SO AS TO CREATE 3 LANDS; DO NOT GROOVE BACK SIDE
3. YOU'LL ALSO NEED ABOUT 3" OF 3/16 TO 1/4" HEAT SHRINK TO COVER THE ASSY WHEN DONE & 10" OF COPPER TAPE (AVAILABLE IN HOBBY STORES)

PARTS FOR N5FC POCKET RF PROBE


N5FC
Ballpoint
RF Probe
AFTER CLEANING, SHRINK TUBING OVER ENTIRE ASSEMBLY
SOLDER
SEWING NEEDLE
SOLDER 0.01uF CAPAC
FROM
LAND 1 TO LAND 2
SOLDER 4.7 MEG
TO LAND 2 AND LAND 3
SOLDER COAX
CENTER CONDUCTOR
TO LAND 3
SCRAP DOUBLE-SIDED PCB;
BOTTOM SIDE IS GROUND PLANE
SOLDER 1N34A
BANDED END TO
LAND 2
SOLDER 1N34A
OTHER END TO
BOTTOM
GND PLANE
SOLDER COAX
SHIELD TO
BOTTOM
GND PLANE
N5FC 2001



Wrap adhesive-backed copper foil round-and-round to build shield over heat shrink-covered RF probe assembly; check for shorts

Ballpoint Pen Casing (Tip & ink tube discarded; but saved screw-on cap at rear of pen)

When complete, pull assembly back into ballpoint casing, leaving needle sticking out about 1/2 inch.

N5FC
Ballpoint
RF Probe

12" Wire pigtail from ground plane of RF probe PCB solders to copper taper and continues back through pen casing (alongside 3-ft shielded coax)

N5FC 2001



N5FC Ballpoint RF Probe

SAVE CAP TO PROTECT PROBE AND PEOPLE

CLEAR 5-MINUTE EPOXY HOLDS RF PROBE ELECTRONICS AND NEEDLE PERMANENTLY IN PLACE (TEST FIRST!)

WE'VE DRILLED ORIGINAL BALLPOINT THREADED END CAP TO PASS COAX THRU

HOLE DRILLED IN SIDE OF PEN CASING TO ACCOMMODATE 12" PIGTAIL

ADD CONVENIENT GROUND CLIP AT THIS END OF 12" PIGTAIL

SHIELDED CABLE MAY BE ANY CONVENIENT LENGTH

ATTACH TWO BANANA PLUGD TO CONNECT TO DC VOLTMETER

N5FC 2001


N5FC 2001
1 21 01


N5FC 4-2001
N5FC
0-5-10-15-20-25-30-35 DB
5-Watt Attenuator
ATU
IN
5 DB
OUT
IN
10 DB
OUT
IN
20 DB
OUT
TX


6.0 IN
SOLDER ALL INSIDE SEAMS
10 DB
20 DB
POWER INDICATOR COMPART-MENT
2.5 IN
5 DB
0.688 IN
0.250 SWITCH MTG HOLE (3 PLS)
HAND "ETCHED" DS PCB
PCB DIVIDER (3 PLS)
0.625" HT SPACER (6 PLS)
RF DETECTOR (& TX BNC) COMPARTMENT
N5FC 4-2001


RF DETECTOR COMPARTMENT
N5FC 4-2001


BNC
TX
20
10
5
BNC
ATU
<2,5
5W
>10
PWR DETECTION CIRCUIT
X2
X2
GND PLANE

N5FC 4-2001


5dB
10 dB
20 dB
>10W
=5W
<2W
ATU
IN
5 DB
OUT
IN
10 DB
OUT
IN
20 DB
OUT
TX
N5FC 4-2001


N5FC 4-2001
N5FC
0-5-10-15-20-25-30-35 DB
5-Watt Attenuator
5dB
10 dB
20 dB
>10W
=5W
<2W


N5FC 2000

sic RF Probe. Simple, eh?


N5FC 2001
0.01uF
4.7M
TO RF TEST CKT
TO VM +
TO VM -
TO
CKT
GND
1N34A

CLASSIC RF PROBE

Reads RMS Equivalent Voltage in test circuit, if Voltmeter is 10-11 Meg Input Impedance;
Reads 4X RMS Equiv Voltage if VM is 1Meg Input Impedance (Set VM to measure DCV)

retical discussion that we'll make short note of. Obviously, for "probing" we need a "probe". (Hey! No wonder I get paid the big bucks...). We add a SH
be goes to our test circuit, where we're probing. Brilliant! We don't want either of these to be long leads, because we're talking RF here, and long leads =


(TOP SIDE)

RF PROBE TIP
RF DET OUT
1/2"
GND PLANE
GND
(BACK)
1.5"
GND CLIP

N5FC 2000


BIC round stic med/moy USA















How to Build Your Own Oscilloscope Probes

ere is the complete bill of materials:

- The pen
- A 2-meter piece of coaxial test cable with a BNC connector on one end
- Epoxy adhesive
- One alligator clip
- Copper-plated nail — 0.75" (20mm) long, packed as "weather-stripping nail".
- 1 MΩ and 5 MΩ resistors

GB
Alligator Clips
Quick Set
Epoxy
Epoxy














www.learningtree.com





Tektronix 2445A
SETUP
VERTICAL
POSITION
TRIGGER
LEVEL
VOLTS/DIV
VOLTS/DIV
SEC/DIV


RF
GND
C1
47pF
R1
10k
D1
OA91
C2
1nF
Co-Ax Cable
+VE
-VE



The simplest power meter


The shortest wiring is desirable in this area.
100 - 300 µA ammeter
-
+
5 - 10 KΩ variable register
(small size)
0.001µF ceramic
capacitor
1N60 (Diode)
50Ω
thin coaxiable cable
20 - 30 cm
small alligator clips

As for the ammeter, you can use an used one taking from junked audio amplifier, tape-recorder, radio-cassette, and so on.



Instructions for using
Philmore Crystal Radio Detector

AERIAL
EAR PHONES
LEADIN WIRE
D
C
B
A
RADIATOR OR WATER PIPE

This Detector is a radio in itself, as it is possible to get reception with it alone, provided you are within 25 miles of a broadcasting station. Under very favorable conditions reception is sometimes possible at much greater distances.

In order to get reception, you need an aerial kit and headphones. The AERIAL may consist of 100 to 125 feet of copper wire and two insulators. Attach insulators to each end of the wire. Stretch the wire allowing as little sag as possible. No part of this wire should touch any portion of the building or any other obstruction.

The LEAD-IN may consist of any desired length of covered wire which will reach from the aerial to the set. Scrape each end of the lead-in so that the wire is absolutely clean. Wind one end securely around the aerial wire. Place the other end in the clip marked "A".

There are two cords leading from the headphones. Connect the cord "C" as illustrated, from the earphone to clip "B" or the clip under the detector arm. The other wire from the earphone marked "D" is to be connected to water pipe, radiator or any other suitable connection to be used for the ground.

You are now ready to receive broadcast. Find a sensitive spot on the crystal by means of the cats-whisker. You may find it necessary to "hunt" for live spots on the crystal as only some parts of a crystal are sensitive, and unless you find these sensitive spots you will not hear anything.

If you do not at first get results, do not blame the detector, as every set is tested before being shipped and will positively get results under the proper conditions. Do not write in and ask what the trouble is for a personal examination of your entire hook-up will be necessary. Go over your aerial, ground, various connections, etc., and if necessary get someone who thoroughly understands radios to help you.






diode
to dummy load
ceramic disk capacitor
0.01 uF / 250 V
to DVM
RF
0.01 uF
DVM
+
–

©2010 F. Dörrenberg

A simple RF-probe

Obviously, this circuit will be fooled by a DC-offset on the RF signal. We can fix this by swapping the diode and the capacitor. Note that this is not necessary if you measure an RF voltage via a transformer, such as a directional coupler.

We can also make life a little easier by including a voltage divider with a scaling factor that is equal to the reciprocal of √2. Then the output voltage will be the RMS value that we are interested in. We can make a voltage divider where one resistor is the input impedance of the DVM. My DVM has a published input resistance of 10 MΩ. The second resistor should be 4M14 Ω,since 10 / (10+4.14) = 1 / √2). So 3M9 + 220k = 4M12 would be a good choice. This approach is shown below. Note that the resistor should be non-inductive (e.g., bulk-metal-foil or carbon).


ceramic disk capacitor
0.01 uF / 250 V
to dummy load
to DVM
diode
RF
0.01 uF
R_s
DVM
+
R_i
–

©2010 F. Dörrenberg

RF-probe with DC-block and peak-to-RMS scaling

A variation on this, with a full-wave rectifier, is shown below:


RF
100 nF
100 Ω
+
100 nF
12 kΩ
DVM or scope
–

RF Current Probe


BNC (to scope)
torroidal pickup (10 turns)
50 ohm coaxial cable
1
J1
2
50 ohms
50 ohms


C1
0.01uF
R1
4.7M
COAX
METER+
METER−
1
D1
1N34A
2
GND

Simple RF Probe



K-S Precision Metals
Chicago, IL
Stock # 164

RG 58












55mm
868 MHz
PIFA Antenna
θ°
73 mm
Matching
Network
Dickson
Rectifier
DC-out
Testing
Port

I used a .02ufd cap because it was the perfect physical size, a 4.7 meg resistor, and a 1N34A diode. I had a nice, flexible, p copper nail that would be easy to solder to for a tip.



±10%
200DC


R.F. BANDS
R.F. BANDS
A B C D E
E D C B A
3.0-11.0 MC
850-3000 KC B
250-850 KC A
D 11-45 MC
E 35-120 MC
UNMOD
MOD
R.F. ATTENUATOR
Signal Generator & Tracer
A.F. ATTENUATOR
PREAMP
OUTPUT
SIGNAL OUTPUT
A.F. IN


BAND-A
BAND-B
BAND-C
BAND-D
BAND-E
A
B
C
D
E
R.F. BANDS
UNMOD
MOD
R.F. ATTENUATOR
A.F. ATTENUATOR
Signal Generator & Tracer
MODEL 153
PREAMP
OUTPUT
SIGNAL
OUTPUT
A.F.
INPUT
Accurate Instrument Co. Inc.

Accurate Instrument model 153 and its RF probe schematic
courtesy of John Lescaud.


39K Ω
200mmf
DIODE
RF-IF PROBE


TO TRACER
COAXIAL
LEAD
47K
+
.02
PROBE TIP
1MEG
IN34
IN48
CK705
PROBE BODY

Heath T-3 signal tracer probe


PROBE
C1
.001
CRYSTAL
DIODE
3
2
S2
RF—AUDIO


SHIELDING
INPUT
TERMINALS
51 K ohms
CRYSTAL
DIODE
PROBE

Heath T-4 or IT-12 signal tracer probe (left) - - - - Eico 145 signal tracer probe (right)


IN-48
470K ohm
CR2
R20

Eico 147a signal tracer probe


PROBE
TIP
C-9
400 MMFD
CR-1
R-29
15K
R-30
22K
R-14
1 MEG
TO SIGNAL
TRACER

Knight-kit signal tracer probe



Pill bottle signal tracer probe



KIS (Keep It Simple) pill-bottle signal tracer probe

Making the simplest Transmitter


DC 6 - 9V (battery only)
+
–
RF output
(to antenna if need)
0.01μF
27KΩ
coil
trimmer cap.
1μF
- +
10PF
C
10KΩ
B
E
470Ω
0.01μF
2SC2001
copper coated plate
+
–
audio in


2SC2001
transistor
E C B

- **soldered point:**

● : direct to the ground



▣ : insulated from
the ground



- **coil**

3 - 4 turns by coated 0.8 mm wire



- **registers**

470 Ω *(yellow-violet-brown)*
10K Ω *(brown-black-orange)*
27K Ω *(red-violet-orange)*

- **capacitors**

10 PF
0.01 μF *(103)*
1 μF

- **trimmer capasitor 20PF**

2005-03-16 by Tetsuo Kogawa

Design – Physical System


Harmonic Suppression
Diode
Balun
DC Bypass Filter

Fig 5. RF to DC converter



List of components

V1 = valve ECC81 or 12AT7
R1 = 10Mohm
R2 = 100Kohm
R3 = 47Khohm
R4 = potentiometer 22Kohm linear
R5 = 1Mohm
R6 = 1Kohm
C1 = variable capacitor in air 20 + 20pF
C2 = ceramic 47pF
C3 = 10nF minimum 100V
C4 = 2.2nF
C5 = 25uF 16V electrolytic
C6 = 10nF 250V or more
L1 = 7 spiers spaced 1.5mm, diameter 1.4mm thread on 1cm support
L2 = 2 spaced spaced 1.5mm, diameter 1.4mm thread on 1cm support
JAF1 = 5-10uH Noval
valve plinth with screen support or take the screen separately.
Stereo jack to be connected with the two earphones in series (do not connect the central mass terminal).
2 knobs for tuning and reaction.
mammoths for connections.
Directional stylus antenna.
For resistances to the maximum use from half a watt but also 1 / 4W should not give problems.



Ricevitore in superreazione con valvola ECC81 12AT7 Primo montaggio.mp4


7:51 / 10:01


7:55 / 10:01


7:58 / 10:01


8:01 / 10:01


COMELIT
Mod. 82144
EI 38-12G/7008/112
230 V 50-60 Hz (1-5)
Prim. 32 mA T
9 V - 3,2 VA (7-9)
ta 70/B
2.2K
8:17 / 10:01


9:38 / 10:01

Superreaction receiver with ECC81
Regenerative RX with 12AT7


ANT1
L2
L1
C1-A
C1-B
V1-A
R1
C2
JAF1
1
2
3
C3
C4
R5
V1-B
6
7
8
C5
+
R6
Cuffia
Anodica
150V - 200V
+V
Attenzione all'alta tensione
R2
R3
R4
C6

alimentazione filamento
piedini 4+5 e 9 per 6,3V
piedini 4 e 5 per 12V

Ricevitore FM in super reazione con ECC81-12AT7


025331
11/02 P
472




ON/OF
VOLUME
CUFFIE


22 K A
400
1300
1400










BOBINE DI ANTENNA E D'ENTRATA
VALVOLA CONVERTITRICE
TRASFORMATORE A MEDIA FREQUENZA
RESISTENZA FISSA
VALVOLA RIVELATRICE
CONDENSATORE A CARTA
TRASFORMATORE DI USCITA
A T
PRESE ANTENNA E TERRA
VALVOLA AMPLIF. MF
VALVOLA FINALE
10000 pF
10000 pF
ALTOPARLANTE
1000 pF
CONDENSATORE VARIABILE DOPPIO
20000 Ω
0.2 MΩ
0.5 MΩ
10 MΩ
100 pF
5000 pF
260 Ω
10 μF
50 000 pF
2 MΩ
300 pF
0.5 MΩ
VOLUME
CONTROLLO VOLUME
COMPENSATORE
380 pF
INTERRUTTORE RETE - LUCE
RETTIFICATORE A SELENIO
500 Ω
RESISTENZA LIVELLATRICE
CONDENSATORE A MICA
+
+
32 μF
−
−
FILAMENTI
ULTRA SECCO
TELAIO
BOBINA DA OSCILLATORE
TRASFORMATORE DI TENSIONE
110 125 160
CAMBIO TENSIONE
CONDENSATORE ELETTROLITICO


S1
Meter
C1
D1
Probe
Gnd
I/P
Gnd


Probe
OA91
+
S1
Circuit under Test
50 ohm
75 ohm
1nF
Digital Meter
100 1W
100 1W
150 1W
150 1W
Ground
–

N. TESLA.
APPARATUS FOR TRANSMITTING ELECTRICAL ENERGY.
APPLICATION FILED JAN. 18, 1902. RENEWED MAY 4, 1907.

1,119,732. Patented Dec. 1, 1914.


P
P
D
D
V
E'
D'
H
F
F
B
A
G
C
F'
E





COSMIC VIBRATIONS

Octave	Manifestation	Vibrations per second	Gaps
1	TOUCH	2	
2		4	
3		8	
4		16	
5	SOUND	32	
6		64	
7		128	
8		256	
9		512	
10		1,024	
11		2,048	
12		4,096	
13		8,192	
14		16,384	
15	ELECTROMAGNETIC (Longer Radio Waves)	32,768	
16		65,536	
17		131,072	
18		262,144	
19		524,288	
20		1,048,576	
21		2,097,152	
22		4,194,304	
23		8,388,608	
24		16,777,216	
25		33,554,432	
26		67,108,864	
27		134,217,728	
28		268,435,456	
29	ELECTROMAGNETIC (Microwaves)	536,870,912	
30		1,073,741,824	
31		2,147,483,648	
32		4,294,967,296	
33		8,589,934,592	
34		17,179,869,184	
35		34,359,738,368	
36		68,719,476,736	
37		137,438,953,472	
38		274,877,906,944	
39	HEAT OR INFRARED	549,755,813,888	
40		1,099,511,627,776	
41		2,199,023,255,552	
42		4,398,046,511,104	
43		8,796,093,022,208	
44		17,592,186,044,416	
45		35,184,372,088,832	
46		70,368,744,177,664	
47		140,737,488,355,328	
48	VISIBLE LIGHT	281,474,976,710,656	
49		562,949,953,421,312	
50		1,125,899,906,842,624	
51	ULTRAVIOLET	2,251,799,813,685,248	SPIRIT ELECTRONS
52		4,503,599,627,370,496	
53		9,007,199,254,740,992	
54		18,014,398,509,481,984	
55		36,028,797,018,963,968	
56		72,057,594,037,927,936	
57	X-RAY	144,115,188,075,855,872	
58		288,230,376,151,711,744	
59		576,460,752,303,423,488	
60			
61			PSYCHIC PROJECTIONS
62	GAMMA AND COSMIC RAYS	4,611,686,018,427,387,904	
63			
64			
65			
66			
67			
68			
69			
70			
71			
72			
73			SOUL ESSENCE
74			
75			
76			
77			
78			
79			
80			

(THESE INTERVALS AND FIGURES ARE APPROXIMATE AND NOT EXACT)

The Vibrations in these octaves increase to an incomprehensible number per second.

The phenomena of psychic projections and soul essence occur in octaves considerably beyond those of any known material manifestations. Consequently, they must not be considered as immediately following any manifestations which we have shown on this chart.

NOTICE

This chart was carefully compiled by the Editorial and Research Departments of AMORC College after consulting the most eminent scientific authorities on the subjects of physics and chemistry and comparing their observations and notations with the reports from the Rosicrucian laboratories in foreign countries.

There is a slight disagreement in regard to the rates of vibrations for the various keys of the musical keyboard, due to different standards of pitch in various countries, and there is some disagreement among scientific authorities in regard to the colors associated with various musical notes. This chart represents not only the consensus of most of these authorities but also adheres strictly to what the Rosicrucians have been able to demonstrate as truth in our own laboratories and in the experiments of thousands of members in various parts of the world. Regardless, therefore, of any disagreement with authorities outside the organization, this chart is the authentic presentation of the Rosicrucian knowledge.

This chart is to be used by the members of the Rosicrucian Order in connection with their studies and experiments and is not to be used for any other purpose or in any other way. Like the lessons themselves, this chart and the facts contained on it are reserved and restricted in use under the rules and regulations of the organization.

INTERNATIONAL
SEAL OF THE
SUPREME LODGE
of the
Rosicrucian
Order

THE SOLAR SPECTRUM



AMORC
THE
Rosicrucian Order
San Jose, California

LITHO. IN U. S. A.



In sostituzione dell'EPAD,
ma richiede almeno 1 V
di alimentazione rubata

vista da sotto

Realizzazione
bobina in filo argentato diametro 1,5
diametro medio 14 mm
lunghezza 19,5 mm
presa a 3,5 spire
var. capacità 7,5-11,5 pf
collegamento a terra non necessario

NOTA
con un buon segnale
funziona senza amplificatore



piattina da 300 ohm
cortocircuitata
sopra e sotto
(144 cm per 100 MHz)
appesa verticalmente

diodo a
3,5 spire

Tenendo
staccata la cuffia,
col condensatore
da 0,1 F si raddop
pia la V di aliment.

anche
a distanza

GALENA PER FM AD ALIMENTAZIONE RUBATA
L'EPAD si può trovare presso la MOUSER USA,
Monaco, Milano

La calata può essere
di piattina oppure il
diodo subito al dipolo
e poi due normali
conduttori

la piattina è lunga 0,96 lambda ovvero 144 cm per 100 MHz


al diodo
al variabile
alla piattina
piattina da 300 ohm
cortocircuitata
sopra e sotto
(144 cm per 100 MHz)
appesa verticalmente
2 spire
AA143
18 pf
2-15 pf
47k
82 pf

la piattina è lunga 0,96 lambda ovvero 144 cm per 100 MHz


BOBINA
ANTENNA
DIODO
TERRA
CUFFIA
CONDENS.
VARIABILE

Lead sulfide crystals, also called "galena"



Crystal detector, the lever was used to position the spring contact on a crystal face capable of performing the radio signal detection.

Yeah , but how does a galena radio work? Here is the constructive scheme of a receiver of this kind, obtained from a book of popular radio commu
to the knowledge of the radio, ed.Hepep 1943):



Fig. 13.5. – Realizzazione pratica dello schema di fig. 13.3 con aggiunta della bobina d'antenna.




ANT.
90 SPIRE CON
PRESA OGNI
10^a SPIRA
FILO 0,8 DC
20 SPIRE
6 cm. ϕ
TERRA


CATWHISKER IS BENT FROM PHOSPHOR BRONZE WIRE
TO AERIAL
CONNECT AERIAL LEAD TO PENCIL CAP
REMOVE ERASER AND STUFF BOTTOM WITH COTTON THEN INSERT CRYSTAL
CRYSTAL
HEAD PHONES
RADIO PENCIL ASSEMBLY
TO GROUND
PHONE LEADS
BRASS SLIDE
50 FEET OF ENAMELED #30 COPPER WIRE
GLUE END TO PENCIL
AERIAL
CRYSTAL
SLIDE
HEAD PHONES
GROUND
DIAGRAM OF CIRCUIT

CRYSTAL SET designed by T. A. Blanchard is built on ⅜" diameter novelty pencil. Solder the top lead of the coil to the metal cap, and simply glue bottom end to the pencil. Remove eraser, push wad of cotton into bottom of cap, and insert a mounted crystal. Bend cat whisker from a length of phosphor bronze wire, and hold in place with bolt going through wood part of pencil. Scrape the enamel off a narrow strip of the coil, so that slide makes contact.

To use, connect aerial, ground, and headphones, move slider and adjust crystal until stations are heard.


INT.
REAZIONE
COMANDO
SINTONIA
CUFFIA
1000/OHM


12K5
12AC6
ANT.


35
470µF
TOWA
470µF
35


Antenna
50mt
90 spire su rocchetto diam 9
50 affiancare e
40 sovrapposte sul lato interno
ferrite 8 x 16
OA95
cuffia
2000Ω


L1
L2
T1
T1 5kΩ:3.5Ω
C3
D1
410
410
C1

This photo clearly shows the layout of the super crystal set. It's built on a baseboard measuring 280 x 240mm.


L1
(GERMANIUM)
D1
A
K
ANTENNA
C1
1nF
HIGH
IMPEDANCE
HEADPHONES
EARTH

Fig.1: the circuit for a basic crystal set. Coil L1 can be air-cored (see text for specifcations) or can be wound on a 100 x 20 x 5mm flat ferrite rod using 70 turns of 22 B & S enamelled wire tapped at 10, 20, 30 & 40 turns.


L1
C1
3x450pF (MAX)
GERMANIUM OR SILICON
(SEE TEXT)
C3: 1µF
D1
L2
R1
2.2M
A
K
15k
R2
T1
(7kΩ:3.5Ω)
C2
450pF
(MAX)
C4
1nF
S1*
LOW
IMPEDANCE
HEADPHONES
ANTENNA
A
B
EARTH
VR1
5k
C5
47µF
*12-POSITION
ROTARY SWITCH
USED TO SELECT
ANY OF 11 TAPS
ON L1, OR NONE
BATTERY
R3
470Ω
S2

Fig.2: the super crystal set circuit uses L1 & C1 to tune the antenna circuit, while L2 & C2 tune the received frequency. Transformer T1 is included for driving low-impedance headphones. Also included is an optional detector bias circuit consisting of VR1, switch S2, the 47µF capacitor, the 470Ω resistor & the battery – see text.



This photo shows the layout for the basic crystal set depicted in Fig.1.

we only want to listen to one station at a time!

Detector bias

Some crystal set designs use a battery and a potentiometer to bias the detector to the point where it just conducts. The reason for this is quite simple.

Diodes all need a certain amount of voltage applied to them before they conduct. As a result, if we apply a DC voltage to a signal diode so that it just conducts, the diode will be in its most sensitive state and will thus give good performance in a crystal set.

This "bias" voltage varies according to the diode used. For example, silicon diodes such as the 1N4148 and the 1N914 require around 0.6V of positive bias to operate, while a germanium diode only requires about 0.2V of bias. On the other hand, the OA47 diode I've used works quite well with no forward bias, which has kept my crystal set just that bit simpler. Your own experience may be different, however so be prepared to experiment.

By the way, transistor radio detectors often use forward bias to improve sensitivity. (Editor's note: forward bias on a diode detector also reduces harmonic distortion).

Detector load

The load that the detector works into is usually a pair of headphones which may have between 2kΩ and 4kΩ total resistance. However, the diode will be more efficient if it works into a higher load resistance and some designs use a resistor of about 15kΩ in series with the headphones to achieve this. In addition, a capacitor of around 1µF is placed in parallel across the resistor so that the audio is not noticeably attenuated.

Although my 4kΩ headphones are good performers they are uncomfortable, so I compared the performance of other headphones against the 4kΩ pair. As stated above, I ended up using low-impedance stereo headphones fed through a speaker transformer. (Editor's note: we also recommend the 32Ω earphones supplied with iPods and MP3 players).

Putting it all together

The set described here is not only easy to build and operate but outperforms many other so-called high-performance sets.



This view shows the front-panel layout for the super crystal set. A good aerial and earth are necessary to achieve good performance – see text.

Fig.2 shows the circuit. L1 & C1 tune the antenna circuit, while L2 & C2 tune the received frequency. Transformer T1 is included for driving low-impedance headphones, while the optional detector bias circuit consists of VR1, switch S2, a 47µF capacitor, a 470Ω resistor and the battery.

The set was built on a 12mm-thick particle board measuring 280 x 240mm. This is fitted on the underside with four self-adhesive felt pads (available from hardware stores) to keep it clear of the bench.

The front panel is made of thin plywood measuring 300 wide x 160mm high. This was given several coats of red paint from a spray can and the labelling on the front panel completed using red Dymo® embossing tape (to match the paint job).

Tuning capacitors

Tuning capacitors can be scrounged from old valve radios that are not worth restoring. For C2, I used one section of a 2-gang full-size 460pF tuning capacitor. This has a 3/8-inch shaft which suits few knobs (and certainly none of my collection). It did, however, have a dial drum which was left on. I fitted a cut-down top from a tin of cream spray paint over the top of the dial drum (it fitted perfectly), which makes it look better and acts as a "handspan" dial.

I was more fortunate with C1 which is a 3-gang 450pF per section tuning capacitor, as this had a ¼-inch shaft. All three sections of the capacitor are used in parallel. The only disadvantage with this tuning gang is that it has a reduction drive, which means that more than a full turn of the knob is required to go from minimum to maximum capacitance.

C3 is a 1µF polyester or greencap type, while C4 is a 1nF unit. The voltage ratings of these capacitors can be quite low.

Resistors & switches

Resistor R1 is used as a "static leak". Its purpose is to prevent a high-voltage static charge from building up across C1 (eg, during storms) which could lead to flash-over. Note also that if a particularly big antenna is in use, it would be advisable to disconnect and earth it when the crystal set is not being used.

Resistor R2 (15kΩ) is the DC load for the detector. Both R1 and R2 can be 0.5W or smaller. If detector biasing is used, R3 can be a 0.5W unit, while VR1 can be a standard 1kΩ linear trimpot or a normal potentiometer. VR1 will not normally require readjustment once set.

S1 is a 12-position switch which selects one of 11 tappings on L1. Only 11 positions are used; the 12th is left with no connection so that the whole of L1 is in circuit. S2 (if fitted) turns the detector biasing on or off as required.

T1 is a standard speaker transformer with a 5kΩ or 7kΩ primary impedance and a 3.5Ω secondary winding. This drives two 8-ohm headphone earpieces in series, so that the reflected impedance to the primary from a 16-ohm secondary load is at least 20kΩ. Within reason, increasing the reflected impedance will assist in maximising the audio output of the receiver.

Winding the coils

Now we come to the all-important coils (ie, L1 and L2).

First, L1 is wound on a 100mm length of 60mm-diameter white PVC pipe. In my case, I wound on 102 turns of 0.63mm (22 B&S) enamelled wire over a length of 70mm. In hindsight, though, around 110 turns would have allowed somewhat more adjustment range to tune the antenna system.

When winding L1, it should be tapped every seven turns and there should be 12 tapping points in all, starting right from the antenna end of the coil. If your antenna is significantly different from mine, then the number of turns on this coil to achieve optimum tuning will vary accordingly.

L2 is also wound on a 100mm x 60mm-diameter white PVC water pipe and consists of 80 turns of 0.63mm (22 B&S) enamelled wire. This winding is spread over 60mm of the former's length and the coil is tapped at 3, 6 & 35 turns from the "earthy" end.

In my case, I found that using turn three as the tap gave good results. You will need to experiment here – you may need even fewer turns to the first tap if your antenna is larger than mine. Note that the correct position may vary from the high-frequency end of the band to the low-frequency end.

Because the detector load is relatively high, it's possible to connect the detector to a tap quite high up the coil. I found that 35 turns was optimum for best performance in my receiver.

As can be seen from the photos, different tapping methods are used for the two coils. For example, L1 has the wire raised away from the former and twisted to make each tapping. By contrast, on L2, a match is slid under the wire at the first tapping point and is then slid along the winding to go under each successive tapping point as the coil is wound. This is the neater of the two methods but is difficult to do effectively if the winding is long and has lots of tappings.

With either method, it is necessary to thoroughly clean the enamel off the wire at the tapping points so that a good soldered joint can be made. This can be done by scraping away the enamel using a sharp utility knife.

Receiver layout

The parts layout on the baseboard is not critical, although the coils should be mounted at the back of the receiver for ease of access. The accompanying photos show the author's unit.

In my case, tuning coil L2 was mounted at the right rear of the baseboard, with L1 in the opposite rear corner. It's important that L1 is kept several centimetres away from L2, to minimise unwanted coupling between them.

Diode biasing

As mentioned earlier, some diodes (particularly silicon signal diodes) require about 0.6V of positive bias to maximise sensitivity. Normally, without diode biasing, points A and B are connected together on the circuit. Conversely, if forward biasing is used, points A and B are separated and the small circuit consisting of B1 (a 1:5V dry cell), toggle switch S2, a 470Ω resistor, a 1kΩ trimpot (VR1) and a 47µF electrolytic capacitor added between these two points.

This circuit is easily adjusted. Switch S2 is closed and trimpot VR1 is adjusted for best volume – simple.

Summary

Those who have never built a crystal set radio before will find this little set worth the effort. It works well, isn't difficult to tune and provides good headphone volume on all local stations.

For best reception, use a high, long antenna that's clear of buildings and trees. A good earth is also necessary and a pipe driven about one metre into the ground and kept damp should suffice.

Finally, if you wish to read about other people's designs, the following list makes a good starting point:

(1) Look on the Internet. Typing "crystal set society" into Google will give you many interesting sites (and lots of designs) that you can explore.

(2) Look in SILICON CHIP for October 1988 (crystal set), March 1990 (wave traps), October 1994 (Hellier Award crystal sets), March 2003 (antennas).

(3) Look in "Electronic Australia" for June 1988 (crystal set), July 1994 (crystal sets), November 1998 (coils) and July 2000 (crystal set).

(4) An excellent Australian book on crystal sets is "Crystal Sets 'N' Such" by Bob Young (7 Hayes Rd, Swanpool, Vic. 3673). He has a few available for $19:95 posted in Australia. **SC**

Photo Gallery: Targan Airmaster

MANUFACTURED BY TARGAN ELECTRIC PTY LTD in 1933, the Airmaster was a 3-valve TRF receiver in an upright wooden cabinet. It used the following valve types: 57 detector; 59 audio output; and 80 rectifier. Photo: Historical Radio Society of Australia, Inc.


TEST
OBJECT
DET.
OUTPUT
GEN.
INPUT
REF

This SWR bridge is not my own invention, OZ3SW and OZ9MO has improved the design after DJ7VY construction in ukw-berichte 1/83
This is a construction set made for the members of Frederikssunds EDR Club, all I did was a bit of gluing and soldering
Thanks for all the hardware help, parts help, calibrating and measuring ! you know who I mean !!
It is possible to measure return loss up to 1000 Mhz, the return loss range is 0-50 to 0-40dB depending on frequency.


TEST
51.00
51.00
GENERATOR INPUT
DETECTER OUTPUT
REF

The schematic


10
Schubert-Gehäuse Nr.7 55x148x30
Messport
Generatorport
Detektorport
Kupferplatten rundum mit Gehäuse verlöten
22 Stück Würth Rippenkerne 7427051
auf 50 Ohm Koaxialkabel 1,3 mm Außendurchmesser
Referenzport


RG316 von Isolierung befreien und breit mit Kupferplatte verlöten
kurz
kurz!
SMD 50 Ohm
SMD 50 Ohm
1mm über der Kupferplatte
alle Koaxstückenpaare gleich lang
zwischen beide SMD 50 Ohm Glimmerplättchen einkleben (grün)


Bogen T725 Transmatch
MARX 2013




220 PF CAPACITOR
AERIAL WIRE
A
B
COIL TAPPING POINT
DIODE
C
·001 MICROFARAD CAPACITOR
1
2
D
CONNECT PHONE HERE (C&D)
VARIABLE CAPACITOR
15 AMP FUSE WIRE
TRY 47K RESISTOR CONNECTED BETWEEN C&D



Inductor, L
Capacitor, C
Capacitor bracket
Connexion to moving plates and frame
P
Audio output transformer
S
Diode, D
Connexion to fixed plates
Tuning knob
1
2
3
4
5
6
E
A
Phones
(Mains) terminal block
Plastic barrel stereo line socket (see Fig.11)
Wooden board

Fig. 14 Suggested component arrangement for elementary crystal set


(Wires not connected)
80
L
Arrow indicates variable tap
0
C
AA119
OA91
etc.
P
S
8 Ω
Headphones
8 Ω
(Wires connected)

(i) Circuit


Turn number 0 5 10 15 20 ....
4 cm diam. tube
Tapping loops (total 7)
5 turns
(Ends cleaned and tinned)
Stout copper wires (0·8–1·0 mm)* as connexions and support
Soldered
Tube
Winding
Terminal block

(ii) Coil tappings and mounting

Fig. 16 Circuit with tapped inductor


Soldered
Winding
Flexible lead
Tube
Terminal block

(iii) Alternative mounting


To variable capacitor (see Fig. 14)
fixed plates
moving plates
Connections to inductor
Turn number
[see (i) and (ii)]
0 5 15 25 35 80
10 20 30
P
S
Copper wires supporting inductor or flexible leads when inductor supported on receiver base
Diode
1 2 3 4 5 6 7 8 9 10 11 12
E
Flexible lead
Headphones (low impedance)

(iv) Suggested component arrangement

---

* 21–19 SWG, 20–18 AWG

required) and a *flying lead* for the diode, these components are shown in Fig.16(iv). This is doing the job properly, there is no reason however (except for unreliability of contact) why both aerial and diode flying leads should not terminate on *crocodile clips* and be clipped onto the chosen taps as required.

Earth is connected to terminal 1 and the headphones to 11 and 12. Both the aerial and the diode lead are tried at terminals 2 – 9, a game of "poke and hope" but one which can be rewarding. Remember that generally but not always, the tappings with the lower numbers reduce loudness but increase selectivity. Aerial to terminal 8, diode to 9 brings us back to Fig.13(i) of course.

5.2 SWITCHED SELECTIVITY

A technique of selection of aerial and diode tappings by means of rotary switches has much to recommend it especially if setting changes are likely to be needed for reception of different stations. In this case two single-pole 8-way switches are required, usually obtainable as 12-way so leaving 4 spare. The drawing symbol shown in Fig.17 speaks for itself with regard to its action and it may be found from catalogues that there are two types of *action*, by which is meant the manner in which the switch changes over from one contact to the adjoining one. *Break before make* switches disconnect one circuit before the next is connected and *make before break* have a change-over period during which both circuits are connected at once for a short time. Either type is suitable for us. A knob to rotate each switch is also required, a small one, say 2 cm diameter or less is ample, if with an indicator line or pointer, so much the better. The modifications to Fig.16 for switching are given in Fig.17.

With such rotary switches a search for the optimum arrange-



Fig. 17 - Switching aerial and diode leads

variable capacitor, the two switches and the headphone socket, the latter must then be of the chassis type. A pair of terminals for aerial and earth completes the receiver. On the panel the two rotary switches are easily labelled 1 – 8 but we are still uncertain about a tuning dial because we may not have the right variable capacitor for the inductor, this is the subject of the next section.

5.3 GETTING THE RANGE RIGHT

This is where we pause in receiver construction to remove some of the confusion which may still exist with regard to the tuning ingredients, wavelength, frequency, inductance and capacity, each of which has some bearing on the others, to fit together these four pieces of the puzzle, so to speak. For most crystal sets the inductance is fixed according to the variable capacitor available and we tune the receiver over the range by rotating the variable capacitor knob over half a


1900 (160) 30
1450 (210) 50
1200 (255) 80
1050 (290) 100
920 (325) 130
850 (350) 150
780 (385) 180
730 (410) 205
690 (435) 230
650 (460) 260
630 (480) 280
600 (500) 310
570 (525) 335
550 (545) 360
530 (565) 390
20
30
40
50
60
70
80
90
100
110
120
130
140
150
160
Frequency (kHz)
Wavelength in brackets
Capacitance (pF)
Degrees rotation
Capacitor plates fully open (0°)
Capacitor plates fully meshed (180°)

Fig. 18 Approximate capacitance and frequency values for 365 pF variable capacitor and 230 μH coil


C5
AA119
OA91 etc.
C3
47
pF
C1
365
pF
L1
L2
C2
365
pF
C4
47
pF
Air-cored transformer*
Iron-cored
transformer*

(i) Circuit


Fixing
screw holes
2 fixing screws
Screw
terminals
Position 1
Position 2 (shifted left)

(iii) Moving inductor L_1


To variable capacitor C1
(first section, fixed plates)
L1
Winding
(see Fig. 16)
9
8
7
6
5
4
3
2
1
Terminal block
(movable)
Aerial
To variable capacitor
(moving plates)
To variable capacitor C2
(second section, fixed plates)
L2
Winding
(see Fig. 16)
Diode and
matching
transformer
as in Fig. 16(iv)
1
2
3
4
5
6
7
8
9
10
11
12
Diode flexible
lead
Terminal block
(fixed)

(ii) Arrangement of inductors

Fig. 21 A double-tuned crystal receiver

* See Section 2.4


(Chimney fixing even better)
Support wire or rope
Aerial insulator
Aerial
To receiver
Down lead
Span (preferably 15 to 18 m)
Aerial insulator
Support wire or rope
End of aerial wire (not connected)
(Fixed as high as possible to pole, tree or building)

(i) Outdoor Aerial


Hole in insulator
Span wire
Lead-in (or free end)
Ceiling
Insulated screw-hook
Aerial
Room
Down lead

(ii) Attaching aerial to insulator

(iii) Room aerial


Water pipe
Earth lead to receiver
Several turns of wire (finally secured by hose clip)
Earth lead
Copper pipe
Washers
Ground

(iv) Earth connection to water pipe

(v) Lead bolted to earth spike

Fig. 12 Aerial/earth systems


Headphones
8 Ω
8 Ω
Signal current
Primary winding
Secondary winding
Headphone cord
16 Ω
Ring
3200 Ω
16 Ω
Tip
Sleeve
Tip
Sleeve
Ring
200 : 1 impedance ratio
Sleeve connexion not used
Matching transformer
Socket
Jack plug

Fig. 11 Matching a high impedance receiver to low impedance headphones


Unscrew to remove or turn crystal
Crystal holder
Cat's whisker
Terminal
Chuck
Ball – rotates in housing
Crystal
Shaft – slides through ball
Terminal
Operating handle
5 cm

Modern diode (7·5 X 2·5 mm)








COIL 80 TURNS
Antenn
EARTH
E
A
DIODE
EARPIECE


WESTECTOR
ANTENNE
KRISTALDETECTOR
49mm
402 SPOEL
TELE-
FOON
1000pF
RE402
SPOEL
AFSTEMCONSATOR
± 500pF
AARDE
2222
WX6
87

Figure 18 The first crystal-set receiver published by "Radio Bulletin" in the July number of 1946 promoted the brand new Mu-CORE 402 (left). As an alternative to a "cat's whisker" detector the article suggest the WX6 "Westector". The picture on the right shows the wx6 "under test".




Earth
Coherer Detector
Aerial
De-Coherer
Pony
Relay
Marconi 1896
Radio Receiver
(NOT INCLUDED IN AUCTION)


Nickel and Silver Filings
Vacuum
Tube



Meter on 200 Ohm Range

Display Indicates Activation = 11.2 Ohms

11.2
Coherer Detector
Press to Spark
Spark Gap
CEN-TECH
DIGITAL MULTIMETER


left gap adjustment
Rear Supports
Center
Support
left
right
paddles
Right Stop adjustment


HB9CRX
GUITAR STRING PADDLES
L 5CM B 2,2CM H 2,2CM 20GR
GUITAR STRING KEY
L 5CM B 2,2CM H2,1CM 10GR

Heathkit CR1 Crystal Radio clone


HEATH COMPANY
A Subsidiary of Daystrom Inc
BENTON HARBOR MICHIGAN
ANT.
GND.
ANT.
PHONES
Heathkit
CRYSTAL RECEIVER
MODEL CR-1
ANT.
DET.
100
90
80
70
60
30
20
10
0
CD
40


X480-1 0236
X480-1 0236
331M
681J

Another Prototype similar to the Heathkit using toroid coil




CV231 9906
CV231 9906

This is a dual tuned crystal set made in a box like the CR-1, just a fun prototype I made a few years back. It pulls in AM stations loud and clear.



Tunnel Boring Machine Time Lapse Burial


NATIONAL INSTRUMENTS
NATIONAL INSTRUMENTS
DELL
8:25 / 9:25
HD

Flat Earth CON SPIRES! Cathedral Spires Are Secretly Atmospheric Electricity Ma

1:45 / 9:25
CC
HD


SUBSCRIBE
0:32 / 2:24
HD

Charging from the power lines.


АНТЕННА
СВЕЧА
ТР
ЗАЗЕМЛЕНИЕ

E6


MULTI DISPLAY DMM
10.1
POWER
Ω
200 2K 20K 200K 2M 20M 200M
hFE
V⎓
V~
A⎓
A~
Cx
F
EBCE
PNP NPN
CE
IEC 1010
A
mA
COM
VΩ
20A 15SEC MAX UNFUSED
200mA MAX FUSED
DT-920

SPARK PLUG
DIODE
CAR CHARGER
FLYBACK TRANSFORMER
TV ANTENNA
00.0
POWER
COM
DT-92



An alternative to Lightning Rods was developed.

A device called a paragrêle was invented by Alexandre Lapostolle around 1820, and described as
"The paragrêle is intended to disarm the storm cloud of its vengeance by **withdrawing its electricity**"

Vue d'une Plaine armée de Paragrêles, et d'un Village armé de Parafoudres
Fig. 1.
Fig. 2.
A
B
C
D
E
F
G
O S N W
0:34 / 1:52
HD

Atmospheric Electric and the Church



The Voltaic Pile

The voltaic pile, invented by Alessandro Volta in 1800, was the first electric battery.
Note: Some sources claim 1793 as the year of invention

Volta created a circuit with two different metals separated by a piece of cloth or cardboard soaked in brine (an electrolyte).
The completed circuit produced an electric current.
By stacking this element - a pair of copper and zinc discs with an electrolyte between them - one atop the other,
Volta could adjust the amount of electricity produced to his desired level.
The result was what came to be called the voltaic pile, one of the first devices to provide a reliable source of electricity.

It's easy to conclude, that between 1793 and 1820,
it became possible to roll out free Atmospheric Electricity to the world.

So why didn't they?

O S N W
0:56 / 1:52
HD



must depend on the area occupied by the building; for instance, a church of ordinary design and size would require four "down" rods, that is, one from the spire, one on both sides of the nave, and one at the extreme end. It is advantageous to run two conductors from the top of the spire or tower, one on each side.

FIG. 7.—3 FT. ELEVATION ROD, WITH POINTS BRAZED TOGETHER, USED WHERE EXPOSED TO MUCH HEAT.

FIG. 8.—ELEVATION ROD FOR HORIZONTAL POSITION OR FLAT ROOF.

FIG. 9.—PLAIN POINT ELEVATION ROD.

Horizontal Conductors (see L.R.C. Suggestion 2, page 15). To complete the system, all the down conductors should be intersected by at least one horizontal rod, with the object of having a path for any side flash or portion of the main stroke which may not be carried away harmlessly by the main rod. Where there is a considerable length of roof, aigrettes (Fig. 11) should be fixed as shown by Fig. 10, which is taken from a model of the roof of Westminster Abbey. The down conductros on their way to earth should be connected to any metal work in the neighbourhood, also to rain-water gutters, pipes, etc.; the number of these subsidiary down conductors depends on the length of the roof.

At a conference held on behalf of the L.R.C., in April, 1904, Sir Oliver Lodge suggested that these down conductors should, in the case of a church, be run between each of the windows.

FIG. 10.

Method of running Conductors. These, whether vertical or horizontal, should be kept away from the structure (L.R.C. Rule 10) so as to avoid all sharp bends, and facilitate straining, and secondly, to prevent the corrosion which may take place where the metal is in contact with the brick or stone work. It is found advisable

Modern lightning conductors: an illustrated



FIG. 27.—TERMINALS IN FORM OF AN ARCH FOR CHIMNEY STACK.



FIG. 28.

surface of the joint need not necessarily exceed that of the cross section of the conductors. The joint should be put together previously by screws or rivets, and the soldered joint, especially if used in underground work, should be carefully protected from local electrical action by tarred rope. Stranded iron conductors can be connected (as previously described) by use of a box joint; the box, Fig. 28, must be of the same metal as the conductors.

Vanes.—Particular attention must be paid to the necessity of making a permanent joint to the spindle. A clamp is prepared of the same material as the spindle, and is furnished with two bolts to tighten; if iron is used it is well to line the clamp with a piece of sheet lead. The conductor is sweated into a socket which is fitted with an eye, through which one of the tightening bolts passes. In the case of the vanes of churches and those fixed in inaccessible positions, two separate clamps should be used.

Internal Masses of Metal.—Roof trusses fitted with longitudinal iron tie rods will, as a rule, be found to be electrically connected, but should this not be the case each truss must be joined to the conductors. All large and long masses of metal, such as beams, girders, roof trusses, tie rods, hot water systems, traveller ways, hoisting crabs, engines, boilers, large machines, and ventilators fixed in the interiors of buildings, should be connected to all conductors that pass near them, and as far as possible with one another. The discontinuous parts of traveller rails should be connected by straps, or in some cases tramway bonds might be used. If electric light wires are run in tubes, such as the "SIMPLEX," this should be earthed. Metallic contact between lead or zinc sheeting and flashings should be carefully studied, and for special work strips of sufficient size should be either burnt on to lead or soldered in such a way that the joint will stand rough usage, and allow for expansion or contraction.

Earth Connection.—"*It is essential that the lower extremity of the conductor be buried in permanently damp soil; hence proximity to rain-water pipes, and to drains, is desirable. It is a very good plan to make the conductor bifurcate close below the surface of the ground, and adopt two of the following methods for securing the escape of the lightning into the earth. A strip of copper tape may be led from the bottom of the rod to the nearest gas or water* main—*not merely to a lead pipe—and be soldered to it; or a tape may be soldered to a sheet of copper* 3 *feet by* 3 *feet and* $\frac{1}{16}$ *inch thick, buried in permanently wet earth, and surrounded by cinders or coke; or many yards of the tape may be laid in a trench filled with coke, taking care that the surfaces of copper are, as in the previous cases, not less than* 18 *square feet. Where iron is used for the rod, a galvanised iron plate of similar dimensions should be employed.*

"The use of cinders or coke appears to be questionable owing to the chemical or electrolytic effect on copper or iron. Charcoal or pulverised carbon (such as ends of arc-light rods) is better. **A tubular earth** consisting of a perforated steel spike driven tightly into moist ground and lengthened up to the surface, the conductor reaching to the bottom and being packed with granulated charcoal, gives as much **effective area** as a plate of larger surface, and can easily be kept moist by connecting it to the nearest rain-water pipe. The resistance of a tubular earth on this plan should be very low and practically constant."—*Lightning Research Committee, 1905.*



Washington Monument is an Atmospheric Electricity Mast


Fig. III.
B
C
C
H
F
P
P
F
F
C
Fig IV.
B
g
g
C
H
F
P
g
F
Fig. I
A
F
F
F
I
f
f
A
F
f
f
A
f
f
f
f
A
Fig. II.
A
C
E
E
B

Figure 2.3. The lightning rod that Toaldo designed for the church of San Marco in Venice. GiuseppeToaldo, “Del conduttore elettrico posto nel campanile” (Padua, 1776). Franklin Collec-



Gilded Temples Are Secretly Atmospheric Electricity Masts


0:29 / 3:58
CC
HD

DIY Atmospheric Water Generator! - Produces/Extracts Distilled Water from the air! - DIY distiller


0:10 / 3:58
HD

0:23 / 3:58
HD



How to make a Spark Gap Transmitter


The Coherer Receiver
HITANICA
1:54 / 2:02

Vintage Model RC Coherer (Spark) Receiver

On the banner, two '**Dual-Loop**' directional antennas, designed specifically to collect power at 750MHz. One is connected to 100uA (700Ohms) head, and the average current you can see on it. Both antennas have 'on-board' rectifiers.


Radio-Rrequency antennas with rectifier circuit.
SK_Lab.2017

Reality is not as good as we would like. One antenna produces about 1 volt (at 10MOhms), and a current of about 0,4 mA (at 700Ohms).

The circuit is simple as a crystal receiver. Diodes with capacitors work as a voltage doubler (rectifier). The remaining inductors and capacitors isolate the output from high frequency.


D1, D2 - any RF diodes.
L1 - L4 6.8uH (10 Ohms)
D-Loop antenna
750MHz
C1
100
R1
1M
D1
BAT68 or better
D2
L1
L3
L2
L4
C2
1000
C3
1000
C4
0.1u
Vout = ~ 1VDC
Iout = ~ 0.5mA
+
–
SK_Lab.2017
* The output voltage and current may vary, depending on the conditions.
Harvesting RF power. Absorbs energy from cell towers at 750MHz.

Any RF diodes with junction capacitance less then 1.5pF will be suitable for this application. See the end of this page for a suitable choice.


PM
E1
E2
Bo
Ba
T

Transmisor Marconi, c. 1895.



Receptor Marconi, c. 1895.


ANTENNA
GROUND
1/16 IN
10
9
8
7
6
5
4
3
2
1
1
2
3
4
5
6
7
8
PHONE

FIG. 4. ASSEMBLED RECEIVING SET


4 INCHES DIAMETER
2
R
TUNER
U
TWISTED TAP
4½
5
Z
GROUND
10 9 8 7 6 5 4 3 2 1
1-TURN TO EACH TAP
10 TURNS TO EACH TAP
W
3
SWITCH CONTACTS
Y
V
SWITCH ARM
ANTENNA
4
CRYSTAL DETECTOR
S
6
1
X
CROUND
T
TELEPHONE RECEIVERS

FIG.3 WIRING DIAGRAM AND DETAILS OF RECEIVING SET

FIG 2. RECEIVING SET, WITH ANTENNA AND GROUND CONNECTIONS



J - LEAD-IN WIRE
K - LIGHTNING SWITCH
L - GROUND WIRE
N - LEAD TO RECEIVING SET
O - INSULATING TUBE
P - RECEIVING SET
Q - GROUND FOR RECEIVING SET

FIG. 2



FIG. I. SINGLE-WIRE ANTENNA, LEAD-IN AND LIGHTNING SWITCH

A
B
C
D
E
F
ANTENNA
G
H
I
J
K
O
N
L
M
A - SCREW EYE
B - ROPE
C - PULLEY
D - ROPE
E - INSULATOR
F - ANTENNA
G - INSULATOR
H - ROPE
I - SCREW EYE
J - LEAD-IN WIRE
K - LIGHTNING SWITCH
L - GROUND WIRE
M - GROUND PIPE
N - LEAD TO RECEIVING SET
O - INSULATING TUBE



Fig. 7



Fig. 8



The Brown-Bahnson Saucer
Experiment by JL Naudin

November 18th, 2002
Email: Jnaudin509@aol.com

Re: LIFTER TECHNOLOGY: Demonstration & Explaination

f1=24.0 Hz
Start
Sound
f2=23.0 Hz


Invisibility points
SUBSCRIBE
THE ACTION LAB
2:16 / 4:19
CC
HD


3 4 5 150cm 6 7 8 9 1
5 6 7 8 9 20 1 2 3 4 5 6 7
CC

(12) **United States Patent**
Cohen

(10) **Patent No.:** **US 8,253,639 B2**
(45) **Date of Patent:** **Aug. 28, 2012**

---

(54) **WIDEBAND ELECTROMAGNETIC CLOAKING SYSTEMS**

(76) Inventor: **Nathan Cohen**, Belmont, MA (US)

(*) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 498 days.

(21) Appl. No.: **12/547,104**

(22) Filed: **Aug. 25, 2009**

(65) **Prior Publication Data**

US 2010/0156556 A1 Jun. 24, 2010

Related U.S. Application Data

(60) Provisional application No. 61/189,966, filed on Aug. 25, 2008.

(51) **Int. Cl.**

H01Q 15/02	(2006.01)
H01Q 19/06	(2006.01)

(52) **U.S. Cl.** **343/753**; 343/909

(58) **Field of Classification Search** 343/753, 343/909, 910; 333/135

See application file for complete search history.

(56) **References Cited**

U.S. PATENT DOCUMENTS

5,471,224 A *	11/1995	Barkeshli	....	343/909
5,714,961 A *	2/1998	Kot et al.	....	343/769
6,473,048 B1 *	10/2002	Diaz	....	343/753

* cited by examiner

Primary Examiner — Michael C Wimer

(74) *Attorney, Agent, or Firm* — McDermott Will & Emery LLP

(57) **ABSTRACT**

Arrangement of resonators in an aperiodic configurations are described, which can be used for electromagnetic cloaking of objects. The overall assembly of resonators, as structures, do not all repeat periodically and at least some of the resonators are spaced such that their phase centers are separated by more than a wavelength. The arrangements can include resonators of several different sizes and/or geometries arranged so that each size or geometry corresponds to a moderate or high "Q" response that resonates within a specific frequency range, and that arrangement within that specific grouping of akin elements is periodic in the overall structure. The relative spacing and arrangement of groupings can be defined by self similarity and origin symmetry.

14 Claims, 4 Drawing Sheets




300
302


Subscribe
1:16 / 2:43
CC
HD

Warka Water towers harvest drinkable water from the air

de
zeen
Subscribe
1:23 / 2:43
HD

dezeen
Subscribe
1:00 / 2:43
HD

© Azega.com

N




Blyant med ledning tilsluttet grafitten
+
-
Stel hornindføring
0:01 / 2:14

tesla radiant collector/ion collector with pencil

ake and it can be sent in an envelope. I made tens of them and sent them to politicians, newspapers, universities... I gave some to local people, together with a user
later version, that can be rolled up in an envelope that fits the conditions to be sent with only one stamp.





BAT62 detection diodes are no more produced. **BAT15** diodes work fine but they wear out; after a few months they stop functioning. **SMS7630** diodes are great but very little and mechanically fragile. **MMSD701T1G** diodes are sturdy and powerful; an excellent choice for a beginner. Such SMD diodes do also work for cell phone frequencies, which allows to test out a snake with a calling cell phone pushed against it. But any detection diodes that can manage 100 MHz will do.

The LED I'm currently using is the **L-7113SEC-H** . It lights up with a low tension and a very low current (the bluer a LED, the more tension it needs). Its color is red yet close to orange hence it is easily seen by the human eye (the eye is most sensitive to green, yellow and orange). The beam is quite narrow so when the LED is directed towards somebody's eyes it will appear quite bright.

For the lengths of 37.5 and 112.5 centimeters, any electric wire with two copper conductors will do. Audio signal wire is a practical solution. Use the shielding as one of the two conductors. The lengths of the two segments must not be precise. What matters is that the total length of the snake be 1.5 meters. Do not hesitate to try out if a little longer or shorter snake gives better results.

A schematic of my current probes, that I connect to a standard multimeter, measuring Volts DC. The measure displayed by the multimeter must be multiplied by 10. When using a 200.0 mV scale, just read while forgetting the dot:



Lead Free Status	Lead Free
RoHS Status	RoHS Compliant

Features, Applications

The MMSD301T1, and MMSD701T1 devices are spin-offs of our popular MMBD301LT1, and MMBD701LT1 SOT-23 devices. They are designed for high-efficiency UHF and VHF detector applications. Readily available to many other fast switching RF and digital applications.

Extremely Low Minority Carrier Lifetime Very Low Capacitance Low Reverse Leakage AEC Qualified and PPAP Capable S Prefix for Automotive and Other Applications Requiring Unique Site and Control Change Requirements These Devices are Pb-Free, Halogen Free/BFR Free and are RoHS Compliant*

XXX G = Specific Device Code SMMSD701T1G = Date Code = Pb-Free Package
Rating Reverse Voltage MMSD701T1G, SMMSD701T1G Forward Current (DC) Continous Forward Power Dissipation = 25C Junction Temperature Storage Temperature Range Symbol VR Value to +150 Unit Vdc M G


152
2578
080704
-
+



feluri (fig. III.9), schemele fiind echivalente cu reprezentarea de bază din fig. III.8. Diodele sînt legate în serie, în formă de patrulater, două avînd comun anodul (punctul *2*), iar celelalte două catodul (punctul *4*). Tensiunea alternativă de intrare se aplică pe diagonala *1—3*, iar consumatorul se conectează pe diagonala *2—4*.

Pentru a urmări funcționarea punții, să presupunem că prima alternanță sosită în nodul *1* este pozitivă. Ea blochează dioda D_2 și o deschide pe D_1, debitînd prin R_S un curent I_1 (săgețile pline), care se întoarce la

tice sau cu parametri cît mai apro-



III.9. Puntea redresoare în diferite reprezentări.

Majoritatea componentelor active folosite în circuitele electronice moderne sînt dispozitivele bazate pe semiconductoare.

Cel mai simplu dispozitiv este *dioda* punctiformă cu germaniu. Ea are proprietatea de bază de a se comporta ca şi cum este conectată direct la o sursă electrică de curent continuu (plusul sursei la plusul diodei) şi ca un izolator, cînd este conectată invers la aceeaşi sursă (plusul sursei la minusul diodei), ca în figura 2.9.


capsulă
arc
cristal
conexiune
+
-

FIG. 2.9.

Dioda punctiformă cu germaniu


Diodă stabilizatoare
Diodă varicap
Dioda luminiscentă LED
Fotodiodă

FIG. 2.10.

Tipuri de diode semiconductoare



FIG. 2.11.

Puntea redresoare

A Light-Emitting Diode (LED)


Epoxy Lens / Case
Wire Bond
Reflective Cavity
Semiconductor Die
Post Leadframe
Anvil Leadframe
Flat Spot
Cathode
Anode
+
—
Mild Steel Lead Frame,
Solder Dipped Leads


Positive Terminal
Reflective Cup
Holes
Proton (Light)
P - Layer
Active Layer
N - Layer
Electron


LED Construction
+
—
Emitted Light
Charge Carrier
Recombination
Diffused
P-type
Epitaxial
N-type
Gold Film Cathode
Connection


Lens
Semiconductor
(LED Chip)
Cathode Lead
(to negative pole of battery)
Anode Lead
(to positive pole of battery)

iStock by Getty Images


audio jack
White LED
1N 4148 Diodes
Ground wire (your hand)

4

The **immortal jellyfish** (*Turritopsis dohrnii*) is capable of biological immortality.



It's one of few known species capable of reverting completely to a sexually immature, colonial polyp stage after having reached sexual maturity as a solitary (free-floating) individual (called a medusa).

> Theoretically, this process can go on indefinitely, effectively rendering the jellyfish biologically immortal


ADVERSITY FACTORS (STRESS)
UP TO A 12-TENTACLE STAGE
ADVERSITY FACTORS (INCLUDING SENESCENCE)
14 AND 16-TENTACLE STAGES
ALTERNATIVE PATHWAYS
UMBRELLA EVERSION
TENTACLE CONTRACTION
SIZE REDUCTION
LOSS OF SWIMMING CAPABILITY
CLOSURE OF VELAR OPENING
SETTLEMENT
PERISARC PRODUCTION
PROGRESSIVE MESOGLOEAL RESORPTION
MESOGLOEAL RESORPTION
SETTLEMENT
SPAWNING
PERISARC PRODUCTION
STOLON PRODUCTION
POLYP FORMATION
PROLONGED ENCYSTMENT
EXCYSTMENT

Figure 3. Pathways of transformation from medusa into polyp. Fate of stressed medusae up to 12-tentacle stage (left side), and alternative transformations of stressed or spawning medusae from a 14-tentacle or 16-tentacle stage (right side). The final product is always the polyp colony (bottom), directly or through a resting stage.

ELECTROMAGNETIC RADIATION SPECTRUM


Size reference
football field
man's height
baseball
paperclip thickness
paper thickness
blood cells
viruses
bacteria
water molecule
atom
atomic nucleus →
1 ft
1 cm
1 mm
1 mil
1 μ
1 nm
1 A
1 pm
wavelength λ (m)
10³
10²
10²
1
10⁻¹
10⁻²
10⁻³
10⁻⁴
10⁻⁵
10⁻⁶
10⁻⁷
10⁻⁸
10⁻⁹
10⁻¹⁰
10⁻¹¹
10⁻¹²
Biological Effect
Non-ionizing Radiation
Ionizing Radiation
Induced Currents
Heating
Ex & Phcm
Ionization – DNA Damage
electron volt (eV)
10⁻⁹
10⁻⁸
10⁻⁷
10⁻⁶
10⁻⁵
10⁻⁴
10⁻³
10⁻²
10⁻¹
1
10
10²
10³
10⁴
10⁵
10⁶
frequency (Hz)
1 MHz
1 GHz
1 THz
1 PHz
1 EHz
1 ZHz
10⁵
10⁶
10⁷
10⁸
10⁹
10¹⁰
10¹¹
10¹²
10¹³
10¹⁴
10¹⁵
10¹⁶
10¹⁷
10¹⁸
10¹⁹
10²⁰
10²¹
Bands
Radio Spectrum
Terahertz
Infrared
Ultraviolet
X-rays & Gamma Rays
Broadcast and Wireless
Microwave
Soft X-ray
Hard X-ray
electronics
optics
Visible wavelengths (nm)
700
625
575
540
470
440
Sources and Uses of Frequency Bands
AM radio 600kHz-1.6MHz
FM radio 88-108 MHz
Mobile Phones 900MHz-2.4GHz
RADAR 1-100 GHz
MRI (1.5T) 63.86 MHz
TV Broadcast 54-700 MHz
Wireless Data ~2.4 GHz
SmartMeter 0.9-2.45 GHz
Microwave Oven 2.4 GHz
"mm wave"
"sub-mm"
Screening 0.2-4.0 THz
Fiber telecom 0.7-1.4 μm
Dental Curing 200-350nm
Visible Light 700-400nm
Remotes 850 nm
Night Vision 10-0.7 μm
Suntan 400-290nm
Medical X-ray 80 kev
Cosmic Gamma Rays >10Bev
Baggage Screen 160 keV
PET 511 kev
Bone Scan 140 keV



First off, check to see if the parts match the parts list…

1 – 1/2" x 3" CPVC tube
2 – 5/8" O.D. vinyl caps
1 – 3/32" dia x 2.5" brass rod
1 – 4-40 x 7/16" pan head screw
1 – 4-40 x 1/4" pan head screw
2 - #4 internal tooth lock washer
1 – 4-40 nut, steel
1 – 4-40 nut, brass
1 – 3/32 x 2" tyrap
2 - #4, 14-16ga ring terminal
1 – PCB
1 – D1 - 1N34A diode
1 – R1 - 4.7M 1/8w resistor (YEL, VIO, GRN, GLD) **See note**
1 – C1 - .01 disk ceramic capacitor (103)
3' – RG-174 coax
2 – banana plugs, 1 red, 1 black
2" – 3/16" dia. shrink tubing
1 – alligator clip and 9" lead
1 - copper foil tape, 2.25" x 2"
1 – self adhesive label


RF PROBE REV A
SIGNAL
C1
/09
R1
DVM+
HENDRICKS
QRP KI
DVM-
D1


PROBE REV A
SIGNAL
1/16/09
HENDRICKS QRP KITS
DVM+
DVM-




RF PROBE REV A
SIGNAL
1/16/09
HENDRICKS
QRP
DVM








103
C1K
C1
SIGNAL
RF PROBE REV A





12 ft
1
ft
in
2
STA








4-40 X 7/16" SCREW
RING TERMINAL
LOCK WASHER
FOIL










Hendricks QRP Kits RF Probe
www.qrpkits.com
78189
QRP KIT
L10
L21

Look in the files section for **Dar's (Darwin Piatt) – W9HZC** application and usage tips for the R.F. Probe.


TO TEST POINT
TO TEST CIRCUIT GROUND
C1 .01uF
R1 4.7M
D1 1N34A
DVM
+
-

ELECTRIC ENERGY FROM SPACE:


Cosmic ray ionization
Aluminium plate (foil)
1N4148
+
-
~ HF exciter ?
GROUND



RF tip for Multimeter and Oscilloscope


Probe
.01uF
4.7M
DVM +
1N34A
GND
DVM -

KA8MAV RF PROBE

The project **RF tip** is simple, not need special components and there is no great difficulty in its construction, making it ideal for beginners. The creator of this tip was the amateur KA8MAV, hence the name of the tip arose. Above the electronic circuit probe.

List of components for the tip RF

1 Germanium diode OA79, 1N34 or equivalent
1 Capacitor 0.01uF
1 Resistor 4M7 x 1/4 Watts


RF Probe by KA8MAV
November 25, 2001


Germanium Diode
IN34 or IN34A
ANODE
CATHODE
Red
LED
copper
wire
Aluminium Tube
A B C D E F G H I J


in
ctr
sh
out1
out2
10 T RG-174 ON FT114-43

N5FC 2002


ctr
out1
sh
in
10 T RG-174 ON FT114-43
ctr
sh
out2
10 T RG-174 ON FT114-43

N5FC 2002

N5FC 2001


0.01uF
4.7M
TO RF TEST CKT
TO VM +
TO VM -
TO
CKT
GND
1N34A

CLASSIC RF PROBE

Reads RMS Equivalent Voltage in test circuit, if Voltmeter is 10 -11 Meg Input Impedance;
Reads 4X RMS Equiv Voltage if VM is 1Meg Input Impedance (Set VM to measure DCV)


BALLPOINT PEN
PAPERMATE FLEXGRIP MED.
0.01uF/50V CHIP CAPAC
4.7 MEG RESISTOR
XYL'S SEWING NEEDLE
SET, BANANA PLUGS RS 274-734
SCRAP PC BOARD
1N34A Ge DIODE
3-FT HUNK SHIELDED CABLE
N5FC 2001

1. USE DOUBLE-SIDE PCB
2. CUT SCRAP PC BOARD TO 2-1/2" L x 3/16" WIDE; CUT NOTCH ABOUT 1/2" L & 1/16" DP; PUT TWO GROOVES APPROX AS SHOWN (NOT CRITICAL) SO AS TO CREATE 3 LANDS; DO NOT GROOVE BACK SIDE
3. YOU'LL ALSO NEED ABOUT 3" OF 3/16 TO 1/4" HEAT SHRINK TO COVER THE ASSY WHEN DONE & 10" OF COPPER TAPE (AVAILABLE IN HOBBY STORES)

PARTS FOR N5FC POCKET RF PROBE


AFTER CLEANING, SHRINK TUBING OVER ENTIRE ASSEMBLY
N5FC
Ballpoint
RF Probe
SOLDER
SEWING NEEDLE
SOLDER 0.01uF CAPAC
FROM
LAND 1 TO LAND 2
SOLDER 4.7 MEG
TO LAND 2 AND LAND 3
SOLDER COAX
CENTER CONDUCTOR
TO LAND 3
SCRAP DOUBLE-SIDED PCB;
BOTTOM SIDE IS GROUND PLANE
SOLDER 1N34A
BANDED END TO
LAND 2
SOLDER 1N34A
OTHER END TO
BOTTOM
GND PLANE
SOLDER COAX
SHIELD TO
BOTTOM
GND PLANE
N5FC 2001



Wrap adhesive-backed copper foil
round-and-round to build shield
over heat shrink-covered RF probe
assembly; check for shorts

Ballpoint Pen Casing
(Tip & ink tube discarded;
but saved screw-on cap
at rear of pen)

When complete, pull assembly back into
ballpoint casing, leaving needle sticking
out about 1/2 inch.

N5FC
Ballpoint
RF Probe

12" Wire pigtail from ground
plane of RF probe PCB solders
to copper taper and continues
back through pen casing
(alongside 3-ft shielded coax)

N5FC 2001



N5FC Ballpoint RF Probe

SAVE CAP TO
PROTECT PROBE
AND PEOPLE

CLEAR 5-MINUTE EPOXY HOLDS RF
PROBE ELECTRONICS AND NEEDLE
PERMANENTLY IN PLACE (TEST FIRST!)

WE'VE DRILLED ORIGINAL
BALLPOINT THREADED END
CAP TO PASS COAX THRU

HOLE DRILLED IN
SIDE OF PEN
CASING TO
ACCOMMODATE
12" PIGTAIL

ADD CONVENIENT
GROUND CLIP AT THIS
END OF 12" PIGTAIL

SHIELDED CABLE MAY
BE ANY CONVENIENT
LENGTH

ATTACH TWO BANANA
PLUGD TO CONNECT TO
DC VOLTMETER

N5FC 2001



N5FC 2001

1 21 01


N5FC 4-2001

N5FC
0-5-10-15-20-25-30-35 DB
5-Watt Attenuator
ATU
IN
5 DB
OUT
IN
10 DB
OUT
IN
20 DB
OUT
TX


FROM TX
BYPASS
BYPASS
BYPASS
TO TUNER
OR ANT
(50-OHM)
20 DB
ATTEN
10 DB
ATTEN
5 DB
ATTEN

N5FC QRP Switchable 0-5-10-15-20-25-30-35 db Attenuator


BYPASS
R_A
R_B
R_C

ATTENUATOR
SECTION
CIRCUIT

		NOM'L	ACT'L	IMPLEMENT WITH
20 db (NOM) ACT=19.7db	R_A	61.1	67	6 ea 100/1W SERIES-PAR'L & 1K PAR'L
	R_B	247.5	235	2 ea 470 / 0.5W IN PARALLEL
	R_C	61.1	62	68/0.5W IN PAR'L with 680/0.5W
10 db (NOM) ACT = 9.7 db	R_A	96.2	100	4 ea 100/1W in SERIES-PARALLEL
	R_B	71.2	67	100/1W IN PAR'L w: 2 ea 100/.5W IN SER
	R_C	96.2	100	100/0.5W
5 db (NOM) ACT = 4.9 db	R_A	247.5	200	2 ea 100/1W IN SERIES
	R_B	30.4	30	3 ea 10/1W IN SERIES
	R_C	247.5	200	2 ea 100/0.5W IN SERIES

N5FC 4-2001


6.0 IN
SOLDER ALL INSIDE SEAMS
10 DB
20 DB
POWER INDICATOR COMPART-MENT
2.5 IN
5 DB
0.688 IN
N5FC 4-2001
0.250 SWITCH MTG HOLE (3 PLS)
HAND "ETCHED" DS PCB
PCB DIVIDER (3 PLS)
0.625" HT SPACER (6 PLS)
RF DETECTOR (& TX BNC) COMPARTMENT


RF DETECTOR
COMPARTMENT
N5FC 4-2001


BNC
TX
20
10
5
BNC
ATU
<2,5
5W
>10
PWR DETECTION CIRCUIT
GND PLANE
X2
X2

N5FC 4-2001



ATU
IN 5 DB OUT
IN 10 DB OUT
IN 20 DB OUT
TX
5dB
10 dB
20 dB
>10W
=5W
<2W
N5FC 4-2001


N5FC 4-2001
N5FC
0-5-10-15-20-25-30-35 DB
5-Watt Attenuator
5dB
10 dB
20 dB
>10W
=5W
<2W



N5FC 2000

sic RF Probe. Simple, eh?


N5FC 2001
0.01uF
4.7M
TO RF TEST CKT
TO CKT GND
1N34A
TO VM +
TO VM -

CLASSIC RF PROBE

Reads RMS Equivalent Voltage in test circuit, if Voltmeter is 10 -11 Meg Input Impedance;
Reads 4X RMS Equiv Voltage if VM is 1Meg Input Impedance (Set VM to measure DCV)

oretical discussion that we'll make short note of. Obviously, for "probing" we need a "probe". (Hey! No wonder I get paid the big bucks...). We add a SH
obe goes to our test circuit, where we're probing. Brilliant! We don't want either of these to be long leads, because we're talking RF here, and long leads =


(TOP SIDE)
RF PROBE TIP
RF DET OUT
1/2"
GND PLANE
GND
(BACK)
1.5"
GND CLIP

N5FC 2000


BIC round stic med/moy USA



















How to Build Your Own Oscilloscope Probes

Here is the complete bill of materials:

- The pen
- A 2-meter piece of coaxial test cable with a BNC connector on one end
- Epoxy adhesive
- One alligator clip
- Copper-plated nail — 0.75" (20mm) long, packed as "weather-stripping nail".
- 1 MΩ and 5 MΩ resistors

GB
Alligator Clips
Quick Set
Epoxy
Epoxy










www.learningtree.com


Tektronix 2445A
SETUP
VERTICAL
TRIGGER
POSITION
VOLTS/DIV
VOLTS/DIV
SEC/DIV


esp
C1
D1
RF
47pF
OA91
+VE
Co-Ax Cable
R1
10k
C2
1nF
GND
-VE



Pacific Antenna 15 Watt Dummy Load Kit


Pacific Antenna
Dummy Load 2.1
WA6PWW
C1
D1
SU1
RF
VPK
VRMS
GND
J1

Inspection and Inventory

First, check the kit to be sure all parts are included. Should anything be missing, please contact us for a replacement.

30 – R1-R30, 1.5 K 1/2 watt resistors: Brown-Green-Red-Gold
1 – R55: 41.2K 1/4W, 1% resistor: Yellow-Brown-Red-Red--Brown
1 – R56: 100K 1/4W, 5% resistor: Brown-Black-Yellow-Gold
1 – D1: 1N4148 diode
1 – C1: 0.01uF monolythic capacitor, yellow, (marked 103)
1 – J1: BNC board mount connector
1 – SV1: 4 pin header
1 – Circuit board

Board Layout


Pacific Antenna
Dummy Load 2.1
WA6PWW
R1
R3
R17
R5
R19
R7
R21
R9
R23
R11
R25
R13
R27
R15
R29
R16
R2
R18
R4
R6
R20
R8
R22
R10
R24
R12
R26
R14
R28
R30
J1
D1
R55
R56
C1
SV1
4
1
RF
VPK
VRMS
GND

Assembly

Install R1- R30

These are the 1/2W. 1.5K ohm resistors and they go in the marked locations shown on the circuit board.

You may find it helpful to do one row of the resistors at a time to make soldering the leads easier.

First, pre-bend the leads near the resistor bodies and then insert them into the board.





Install, solder and trim the leads of D1. Be sure to match the band end to the diagram above and the outline on the circuit board.



Install R55 the 41.2K ohm (Yellow-Brown-Red-Red—Brown) resistor in the marked location on the board

Install R56, the 100K resistor (Brown-Black-Yellow-Gold) in the marked location on the board.

Install C1 the 0.01uF capacitor in the location marked on the board.



Now, solder the BNC connector, making sure to seat it fully into the board. Solder the two small wires and the two support pins.

The support pins may require longer time, increased temperature or a larger soldering iron to properly solder.


J1
Pacific Antenna
Dummy Load 2.1

Congratulations, your dummy load kit is now complete!


Pacific Antenna
Dummy Load 2.1
WA6PWW
J1
C1
D1
SU1
RF
VPK
VRMS
GND
4
1

Operation

The dummy load is easy to use. Simply connect your transmitter input to the BNC

To measure RF Power, connect your multimeter to pin 1 and Pin 2 or 3.

Pin 1 is ground and the DC output voltages appear on pins 2 and 3 of SV1.

Pin 2 provides the RMS value of the RF voltage.

Pin 3 gives the Peak value of the RF voltage.

Pin 4 is direct RF voltage across the resistors.

RF power is calculated from this relationship: Power = (Vrms^2)/50

Note: The power input should be limited to 15W to avoid damaging the resistors and sense circuit components.

The simplest power meter


The shortest wiring is desirable in this area.
100 - 300 µA ammeter
-
+
5 - 10 KΩ **variable register**
(small size)
0.001µF ceramic capacitor
1N60 (Diode)
50Ω
thin coaxiable cable
20 - 30 cm
small alligator clips

As for the ammeter, you can use an used one taking from junked audio amplifier, tape-recorder, radio-cassette, and so on.



Instructions for using
Philmore Crystal Radio Detector

AERIAL
EAR PHONES
LEADIN WIRE
D
C
B
A
RADIATOR OR WATER PIPE

This Detector is a radio in itself, as it is possible to get reception with it alone, provided you are within 25 miles of a broadcasting station. Under very favorable conditions reception is sometimes possible at much greater distances.

In order to get reception, you need an aerial kit and headphones. The AERIAL may consist of 100 to 125 feet of copper wire and two insulators. Attach insulators to each end of the wire. Stretch the wire allowing as little sag as possible. No part of this wire should touch any portion of the building or any other obstruction.

The LEAD-IN may consist of any desired length of covered wire which will reach from the aerial to the set. Scrape each end of the lead-in so that the wire is absolutely clean. Wind one end securely around the aerial wire. Place the other end in the clip marked "A".

There are two cords leading from the headphones. Connect the cord "C" as illustrated, from the earphone to clip "B" or the clip under the detector arm. The other wire from the earphone marked "D" is to be connected to water pipe, radiator or any other suitable connection to be used for the ground.

You are now ready to receive broadcast. Find a sensitive spot on the crystal by means of the catswhisker. You may find it necessary to "hunt" for live spots on the crystal as only some parts of a crystal are sensitive, and unless you find these sensitive spots you will not hear anything.

If you do not at first get results, do not blame the detector, as every set is tested before being shipped and will positively get results under the proper conditions. Do not write in and ask what the trouble is for a personal examination of your entire hook-up will be necessary. Go over your aerial, ground, various connections, etc., and if necessary get someone who thoroughly understands radios to help you.






diode
N4SPP
to DVM
to dummy load
ceramic disk capacitor
0.01 uF / 250 V
RF
+
DVM
0.01 uF
−
©2010 F. Dörenberg

A simple RF-probe

Obviously, this circuit will be fooled by a DC-offset on the RF signal. We can fix this by swapping the diode and the capacitor. Note that this is not necessary if you measure an RF voltage via a transformer, such as a directional coupler.

We can also make life a little easier by including a voltage divider with a scaling factor that is equal to the reciprocal of √2. Then the output voltage will be the RMS value that we are interested in. We can make a voltage divider where one resistor is the input impedance of the DVM. My DVM has a published input resistance of 10 MΩ. The second resistor should be 4M14 Ω,since 10 / (10+4.14) = 1 / √2). So 3M9 + 220k = 4M12 would be a good choice. This approach is shown below. Note that the resistor should be non-inductive (e.g., bulk-metal-foil or carbon).


ceramic disk capacitor
0.01 uF / 250 V
N4SPP
to DVM
to dummy load
diode
0.01 uF
RF
R_s
+
DVM
R_i
−
©2010 F. Dörenberg

RF-probe with DC-block and peak-to-RMS scaling

A variation on this, with a full-wave rectifier, is shown below:


RF
100 nF
100 Ω
+
DVM or scope
100 nF
12 kΩ
−


123
104
1N34
+
−
ANODE
CATHODE

.01
10NF

.1
100NF

Ceramic
Disc
Capacitor

Germanium Diode
IN34 or IN34A


antenna in
104
104
1N34A
1N34A
1N34A
1N34A
100uF 50V
100uF 50V
−
+
−
+
−
+
output

RF to DC

Circuit Diagam (simplified)

Component list:

(2) Ceramic Capacitors (104)
(4) Germanium Diodes (1N34A)
(2) Electrolytic Capacitors (100uF 50V)

Copyright 2016. Drew Paul Designs. All rights reserved.

RF Current Probe


BNC (to scope)
torroidal pickup (10 turns)
50 ohm coaxial cable
1
J1
2
50 ohms
50 ohms


C1
0.01uF
R1
4.7M
COAX
METER+
METER–
1
D1
1N34A
2
GND

Simple RF Probe



K-S Precision Metals
Chicago, IL
Stock # 164




SD

RG 58














TENMA
72-4025
.583
POWER
AC
DC
A
20m
10A
LOGIC
Hz
600
200
20
2
200m
V
200m
NPN
hFE
PNP
2000 M
20M
2000k
200k
20k
2k
200
2n
20n
200n
2µ
20µ
F
Cx
E B C E
Ω
DISCHARGE CAPACITOR BEFORE CONNECTING
mA
FUSED 200mA MAX
COM
VΩ
10A

RF Signal Generator


5v
out
7805
in
12v
+
100n
100n
150
10-200p
15p
1N914
2N5458
100k
L1
2N5458
100n
5n
10k
15p
100k
470
RF out
-
Level

L1: 37 turns on T50-2 toroid.
Source tap 12 turns up from earth.

Coverage: 3-12 MHz approx

Notes:

1. A vernier reduction drive is desirable.
2. Build signal generator in die cast aluminuim box for best stability.
3. Can work up to 148 MHz on harmonics if care is taken in construction.
4. Any construction method should work but ensure components are rigid.


VK1PK
RF Signal Generator
Off
On
Freq
Level
Out

(C) 1998 VK1PK


55mm
868 MHz
PIFA Antenna
θ°
73 mm
Matching
Network
Dickson
Rectifier
DC-out
Testing
Port

I used a .02ufd cap because it was the perfect physical size, a 4.7 meg resistor, and a 1N34A diode. I had a nice, flexible, p copper nail that would be easy to solder to for a tip.




±10%
200DC

R.F. BANDS
R.F. BANDS
250-850 KC A
850-3000 KC B
C 3.0-11.0 MC
D 11-45 MC
E 35-120 MC
R.F.
UNMOD
MOD
R.F. ATTENUATOR
A.F. ATTENUATOR
Signal Generator & Tracer
PREAMP
OUTPUT
SIGNAL
OUTPUT



.... Top Quality, Low Prices, Dependable Service

LAFAYETTE COMBINATION SIGNAL GENERATOR AND SIGNAL TRACER

NOT A KIT — FACTORY WIRED AND TESTED

SIGNAL GENERATOR

- Covers From 250 KC to 120 MC in 5 Bands
- High Stability Electron Coupled Oscillator
- Attenuator For Both RF and Audio Circuits

SIGNAL TRACER

- Hi-gain Cascode Pre-amplifier
- Front Panel Output For VTVM, Scope or Phones
- Low Distortion Triode Output Stage
- Separate R.F. and Audio Signal Probes

wo test instruments in one! The Signal Generator will serve as a full service strument and the Signal Tracer will follow any signal whether generated by a oadcasting station or injected by the Signal Generator section. When used in mbination, with no dependence on outside signals, the unit provides ideal rvice, for unlike any standard signal tracer, it first injects its own signal then urces that controllable signal to locate the source by standard signal tracing chnique. Designed for use with AM, FM, TV and audio circuitry. Features 5 equency ranges and an attenuator switch to control both the R.F. signal (either odulated or unmodulated) and the 400 cycle audio tone. Front panel output cks which can be used for oscillioscope, VTVM or earphone connections. Housed a beautiful crackle finish steel cabinet with a deep etched aluminum panel. mensions: 7½x9½x5¾". Complete with 2 probes. Shpg. wt., 9 lbs.

R 0102 .... Net 24.95

SPECIFICATIONS

NGE: Band A: 250KC to 850KC; B: 850KC-3000KC; C: 3.0MC to 11MC; D: 11MC 45MC; E: 35MC to 120MC; 400cps audio signal; modulation slide switch, AF attenuator and power switch; Signal output jack; AF input jack. 2 Preamp. put jacks. 4½" alnico 5 speaker. Tubes: 5687, 6350, 6AG5 plus sel. rectifier.

Made in U.S.A.

ONLY 24.95


TO TRACER
COAXIAL
LEAD
47K
+
.02
PROBE TIP
1 MEG
IN 34
IN 48
CK705
PROBE BODY

Heath T-3 signal tracer probe


PROBE
C1
.001
CRYSTAL
DIODE
3
2
S2
RF—AUDIO


SHIELDING
INPUT
TERMINALS
51 K ohms
CRYSTAL
DIODE
PROBE

Heath T-4 or IT-12 signal tracer probe (left) - - - - Eico 145 signal tracer probe (right)


IN-48
470K ohm
CR2
R20

Eico 147a signal tracer probe


PROBE TIP
C-9
400 MMFD
CR-1
R-29
15K
R-30
22K
R-14
1 MEG
TO SIGNAL TRACER

Knight-kit signal tracer probe


AF ⟵ RF
.0068
C12
XTAL
RECT
47K
R25
RF-AF PROBE

PACO Z-80 signal tracer probe



Pill bottle signal tracer probe



KIS (Keep It Simple) pill-bottle signal tracer probe


BAND-A
BAND-B
BAND-C
BAND-D
BAND-E
B
C
D
A
E
R.F. BANDS
UNMOD
MOD
R.F.
ATTENUATOR
Signal Generator & Tracer
MODEL 153
A.F.
ATTENUATOR
PREAMP
OUTPUT
SIGNAL
OUTPUT
A.F.
INPUT
Accurate Instrument Co. Inc.

Accurate Instrument model 153 and its RF probe schematic
courtesy of John Lescaud.


39KΩ
200mmf
DIODE
RF-IF PROBE


ANTENNA
GROUND
PHONES
2:09 / 8:01

BOY SCOUT CRYSTAL RADIO UPGRADE


ANTENNA
GROUND
PHONES
PHONES
4:45 / 8:01

BOY SCOUT CRYSTAL RADIO UPGRADE



Broadcast AM Audio Reception From My

Live CB Radio •

192 views • 9 months ago

I made a primitive crystal rad

connected to a computer run



Make: Foxhole Crystal Portable Radio Kit Build & Review


Radio Relay ©
Aerial
Tune
Phones
Earth
L1
D1
Foxhole Radio
7:10 / 10:13

Make: Foxhole Crystal Portable Radio Kit Build & Review


R1
L1
1
2
L2
D1
5:47 / 12:56

Make: DIY Matchbox Crystal Radio Kit Build and Review



Matchbox Radio Instructions

Tuning capacitor
Aerial connection
Earth Connection
Band switch
L1
L2
R1
D1
3.5mm Phono High impedance output
Russian Military germanium Detector
220uH inductor coil
470uH inductor coil
8:42 / 12:56


R1
L1
1
2
L2
D1





ngth may improve results in different c

R1	82K resistor (Grey red Black Red)
D1	Selected Russian Military germanium diode (Glass yellow red band) connect anyw
L1	220uH Inductor (Red Red Brown]
L2	470uH Inductor (Yellow Violet Brown)

Tuning Capacitor 9-50pF Approx. Frequency Range 1-3.5MHZ

Band Change 3 pin header – move the shorting tab to change frequency

Output   High impedance crystal earpiece 20,000 ohms

3.5mm socket   before soldering ensure that the plastic pins on the base of the socket a
into the holes in the circuit board. This takes the strain when inserting *the earpiece.*

connections. The crocodile


FM DETECTOR
by JPascal
0:03 / 0:57

FM Crystal Detector Live Recordings



FM CRYSTAL DETECTOR RECEIVER

loop from copper wire 4 mm, diameter 75 mm (surface cleaned)

crystal earphone

or high impedance amplifier phono or guitar

very short connections

optional 50 cm long cable or rod = Lambda / 4 at 100 MHz

JPascal 2018

L = 0,14 µH
FM 88-108 MHz
BAT 32
15..25 pF
100p
560k
470µH
0:10 / 0:57


FM DETECTOR
EQ


Cape Cod Crystal Radio
Tune
Aerial
Earth
Phones
R1
L1
L2
Two Band
D1
2


Cape Cod Crystal Radio
Tuning capacitor
(Turns continuously - no stop)
Tune
Crocodile clip pads
Aerial
Earth
High impedance head phones
Phones
R1
L1
L2
82K Resistor
Two Band
D1
1
2
Band Switch
Inductor 470uH
Detecting Diodes
Inductor 220uH

1. Solder D1 the germanium diode. RED band to the right.

2. Solder L1 220uH inductor (Red Red Brown Silver)

3. Solder L2 470uH Inductor (Red Violet Brown Silver)

3. Solder R1 82K ohm resistor (Grey Red Black Red) Above Switch

4. Solder band change switch, make sure it is parallel with the board

5. Solder the 3.5mm earphone socket, ensure it is parallel to the board before you solder and the locating pins align with board holes.

6. Solder the variable capacitor 120pF. Any way it is not polarity sensitive.

7. Two silver pins are provided for aerial and earth connections,just clip the crocodile clips to these pins or, leave these pins off and connect to the pads on the board. For portable use and younger children best to leave these pins off the board.

Connect the crocodile clips for the earth and aerial wires. Strip approximately 25mm of the insulation, thread through hole and crimp both the insulated part and the bare wire with pliers.

L1 is an inductor, a 220uH coil in series series with L2 a 470uH inductor. The switch shorts out the L2 in ther band 1 position. D1 is a specially selected germanium diode to give optimum performance in this particular circuit. R1 is a 82K resistor across the high impedance output. The variable capacitor is a 9 - 120pF capacitor

Getting Started . Plug the headphones into the socket. Holding your thumb behind the socket when plugging in will avoid any stress on the solder joints.To get the strongest signals in your area you will need to experiment if


V
A
AC
voltage
source
+
Load
-
V
A


200 - 1000 feet
of insulated wire
20KV
diode
tuned
spark plug
1- 2 mm
20KV
.001 mfd
capacitor
+
–
12 volt
ignition coil
+
–
charging
switch
12 volt deep cycle
storage battery
1N4001
diode
earth
ground


ANT1
C1
100pF
C2
100pF
D1
D2
D3
D4
100uF
C3
+
100uF
C4
+
-
+
1N34A Germanium Diodes
GND

DIY HDTV antenna

“Antenna” is two L-shaped pieces of coat hanger stripped of any coating. It is only necessary that the long sides be 6 inches (15.24 cm) in length.



Connect to television.

Conducting shield / ground wire.

Terminal block screw-type electrical commector (dirt cheap at any electronics parts store).

Copper core (must not touch ground wire).

Coaxial cable of any length, carefuly stripped to expose the two copper elements.


4" dia.
Aerial
V
6
4
S
U
Twisted Tap
R Tuner
10 Turns to Each Tap
1 Turn to Each Tap
W
Y
W
Switch Contacts
Z
5
T
Telephone Receivers
Earth
Switch Arm

Fig. 3.—The Receiving Set in Complete Detail.


Antenna
Tappings
'C'
D1
Detector diode
'A'
L1
C1
365 to
500p
Tuning
C2
100p
Earpiece
Primary
Secondary
'D'
'B'
Earth

Figure 1 Circuit diagram of the crystal set


C
Taps every
10 turns
Approx
40mm
dia
Primary or antenna
coil, 30 turns
A
6 matchstick
ribs glued in
position
Secondary or tuning coil,
140 turns closewound
with 26swg, or similar,
enamelled copper wire
D
B

Figure 2 The coil is mounted on a cardboard tube as shown. Exact size is not too important. Try different taps for best results

- This part is the most difficult of all. Seasoned coil winders may have their


Radio de galena
Antena
L1
C1
D1
C2
Tierra
Antena
Bobina
Audífono
Diodo
Condensador de cerámica
Tierra
Condensador variable

Fig 12



Fig. A1

Paso 2. Pegar la lámina sobre el tablero

Tome su tablero de madera y pegue el esquema sobre él. Unte el pegante en poca cantidad solamente en los bordes y un poco en el centro en forma de cruz. (figura A2).



Fig. A2

THE LOST HAMEL DRAWINGS:

Hamel Technology



David Hamel's "Isotope Line of Movement" creating the:

POSITIVE - NEUTRAL - NEGATIVE

mechanical parts needed to create a self running system.

(male)
Rotating Rod with a Neutral Center
(female)
1
2
3
The Eye (particle of nature)
Twice the Aether
Equals
Scale (perfect balance of nature)
The Duality (opposites)
Celestial Power
YY × E² = C
1st Particle of Nature (male)
2nd Particle of Nature (female)
KRYPTONIQUE
Gases of space

Particle Structure. [The MOST IMPORTANT Hamel Diagram of All.]


HJC
MKP-X2
GMF
250V~
275V~
0142
40/100/21/C


AERIAL CONNECTION
EARTH WIRE



Figure 1 Three constructions for magnetic field probes


Co-ax shields soldered to metal case
50Ω BNC
Best design
Typical diameters from 10mm to 50mm
CM choke bifilar wound on soft-ferrite toroid
Semi-rigid co-ax loop with central break in shield
Both shield and centre conductor soldered to shield
Semi-rigid co-ax loop with central break in shield
Suitable insulation (two individual layers recommended, each rated for max. voltage)
Epoxy, or other type of strain relief
No central break in the co-ax shield
Both would benefit from a CM choke as above, or at least a ferrite clipped onto their lead
Only the centre conductor is soldered to the shield

Figure 2 An electric field probe, and a pin probe


Electric field probe
50Ω BNC
Centre conductor exposed by approximately 10mm, and insulated
Epoxy, or other type of strain relief
Suitable insulation (two individual layers recommended, each rated for the maximum voltage to be probed)
Pin probe
Low-value capacitor (e.g. 10pF) with suitable voltage rating, soldered in series with centre conductor.
Pin exposed for direct contact
Both would benefit from a CM choke bifilar wound on a soft-ferrite toroid as shown in Figure 1, or at least a ferrite clipped onto their lead




The simplest FM Crystal Radio Circuit - http://billydiy.blogsp
Antenna - Extendable Radio 1.8 meter. That also serves as tuning
1N34A,1N48,AA112, ISS86, ISS106
D1
J1
100K
D2
3.5mm Mono earphone Jack for Crystal earphone



FM Crystal Radio Circuit


Simple FM Crystal Radio Circuit
Antena
8.4cm of #16
Copper Wire
1N60 Germanium
15pF
Output to
Amplifier
4 Turns of #18 copper
wire tapped at 2.5
turns. 12mm inside
diameter.
150K
50pF
Air variable

Parts List (some of these parts you can buy from our online store):

- 1N60 Germanium Diode
- 15pF Ceramic Capacitor
- 50pF Variable Capacitor
- 150K Ohm Resistor
- #16 & #18 Copper wires

Ricevitore a cristallo per FM

Un progetto di Giacomo Cavuoti




LOOP ANTENNA
tubo di rame ϕ=12 mm
Circonferenza = 3 m
Diametro = 0.955 m
L1
5 spire
ϕ = 12 mm
sp.filo = 1.4 mm
passo spira = 4.2 mm
L2
3 spire
ϕ = 12 mm
sp.filo = 1.4 mm
passo spira = 4.2 mm
2 metri di cavo TV 75Ω
L1
L2
30 pF
10 pF
1N5711
1N5711
1.2 nF
BF
casse amplificate PC
Trust SoundWave 160 3D Plus
6W RMS

The receiver is "powered" by a full wave loop antenna consisting of a single circular coil made of 3 meters of copper pipe for hydraulic systems (measured inductance of about 3 uH). The support is a simple 2-meter long fir-wood strip, 3 cm wide and 1 cm thick, to which the copper rim has been fixed with insulating tape. Another solution to realize the loop antenna in a simple and instantaneous way is to use an aluminum strip 2 mm thick and 2 cm wide. The detectors are two *Schottky* diodes type 1N5711, particularly suitable for VHF thanks to the low capacity (about 2pF). They are currently in production and therefore easy to find. The receiver was tested in a "stiff" situation with the antenna exposed in a recessed balcony (3 x 1.6 meters) on the fourth floor of a 6-storey reinforced concrete building surrounded by other buildings constructed of reinforced concrete walls. As you can see and hear from the two videos I uploaded on Youtube:






8:34 / 8:34

Making the simplest Transmitter


DC 6 - 9V (battery only)
+
–
RF output
(to antenna if need)
0.01μF
27KΩ
coil
trimmer cap.
1μF
- +
10PF
C
470Ω
10KΩ
B
E
0.01μF
2SC2001
2SC2001
transistor
E C B
copper coated plate
+
–
audio in

- soldered point:

  ● : direct to the ground



  ▣ : insulated from the ground



- coil

  3 - 4 turns by coated 0.8 mm wire



- registers

  470 Ω *(yellow-violet-brown)*

  10K Ω *(brown-black-orange)*

  27K Ω *(red-violet-orange)*

- capacitors

  10 PF

  0.01 μF *(103)*

  1 μF

- trimmer capasitor 20PF



Radiant Energy Proof of Concept Receiver Schematic – v2.6

Key

A: Analogue mA ammeter.
ANT: Antenna 65' long, 6ga, V shape, electrically isolated at least 10' from the ground.
B1: 6 volt SLA rechargeable battery.
C1: 560pf, 50v ceramic capacitor.
C2, C3: 365pf variable air capacitors, less than 1kv.
C4, C5: 450 volt, 47µF electrolytic capacitors.
D1-D4: UF4007 1.0a ultra fast recovery diodes.
D5, D6: 2 - 3.7 volt, 30ma, 10mm ultrabright LEDs.
E1: Earth grounding rod.
INS: Electrically non conductive insulators.
L1: 3 turns, 18ga wire wound over L2 windings.
L2: 50 turns, 20ga enameled wire wound on a 3" diameter cardboard tube.
R1: 10k, 1/4 watt resistor.
S1: On/Off switch.
T1: MJE13007 transitor.

Input: 6 volts @ 7.5 mA.
Output: 6 volts @ 38 mA.
Gain: 30.5mA = over five times more output than input.

turning low-frequency currents into sound, and it would be as





Fig. 17—Currents vary the strength of the magnetism and so cause diaphragm movements

Fig. 16 (b)—Pictorial representation of the simple



Figure 2: Depiction of various optical events in the atmosphere and the altitude at which they occur, credit [2].

or at time as low as the cloud top and bright region is in the altitude range 65–85 km [35]. They typically last for 5–50 ms and may take the form of one or more vertical columns of a few hundred meter radius for the smaller column sprites or large jellyfish-shaped structures of tens of kilometers of radius and extending from the ionosphere D-region almost down to the thunderstorm cloud tops [2, 35]. The knowledge gained from laboratory experiment of gas discharges at subatmospheric pressure has been used to understand sprite spectroscopy and associated phenomena [25]. Figure 3 shows broad identical spectral characteristics of light of positive column of the laboratory tube and sprites [25]. The difference in spectral characteristics may be due to difference in applied electric field, gas pressure, and gas composition in the mesosphere and gas tube discharges. Physical processes associated with sprites and other optical events are also associated with thunderstorm activity in the troposphere and are thought to result in the gradual build-up of conductivity changes in the lower ionosphere [36]. Liszka [37] suggested the generation of infrasound waves by sprites, whose signatures were detected by a network sensors in Sweden [38]. The shape of the chirp signature in the spectrograms of infrasound can be explained by the horizontal size of the sprite [39]. Neubert et al. [40] have



FIGURE 4: Essential features of the global atmospheric electric circuit [26, 27].



FIGURE 5: Diagram showing a schematic equivalent circuit for global electric circuits, credit [28].

system, that electric currents redistribute charge and that the electric currents are continuous.

The power supplied by thunderstorms is insufficient to maintain a field of magnitude observed in fair-weather regions. Rycroft et al. [61] included the generator associated with electrified clouds in the GEC model; this was found to be of the same magnitude as that due to thunderstorms. The optical phenomena occurring in the upward branch of the GEC above the thunderstorms are likely to influence only the upper atmosphere conductivity. Since they occur much less frequently (only one sprite out of 200 lightning) because of their association with intense lightning discharges [50, 62], their contribution to the ionospheric potential is very small [61]. The gigantic jets transport large quantities of negative charge discharging the atmospheric capacitor [63–66] whose effects on the ionosphere and GEC have not yet been modeled. The role of sprite/TLE events on the flow, charging/discharging of GEC, modification of electric fields near the Earth's surface remains unanswered. Since optical emissions could change electrical properties of the atmosphere and influence processes related with weather and climate, intense research activity in this area is required.

The earthquakes affect the electrodynamics of the atmosphere through the generation of electric and magnetic fields with crustal deformation, fault-failure-related piezomagnetism, stress/conductivity, electrokinetic effects, charge generation processes, thermal remagnetization, and demagnetization effects, and so forth [67]. These processes in the Earth's lithosphere relate with disturbances in the atmosphere and ionosphere. Sorokin et al. [8] discussed the processes forming the electrodynamic model of the effect of seismic and meteorological phenomena on the ionosphere. Radioactive substances and charged aerosols injected into the atmosphere modify the altitude profile of conductivity, generation of external currents, perturbation of electric field, and current in the ionospheric layer. As a result, Joule heating of the ionosphere and instability of acoustic gravity waves take place, which manifests in the formation of horizontal inhomogeneities of ionospheric conductivity. Finally, excitation of plasma density fluctuations and ULF/ELF emissions in the ionosphere, generation of field aligned currents and plasma layers, upward plasma transport, and modification of F_2-layer, and change in the ion composition of the upper ionosphere take place [68, 69]. These changes may also affect the GEC and the Earth's climate which remains a challenging problem to be solved. Figure 6 shows a schematic diagram which can be used to



Figure 1-7 Wavelength versus frequency for $v = c$.

Example of wavelength for a given frequency. For a frequency of 300 MHz the corresponding wavelength is given by

$$\lambda = \frac{c}{f} = \frac{3 \times 10^8 \text{ m s}^{-1}}{300 \times 10^6 \text{ Hz}} = 1 \text{ m} \tag{3}$$

In a lossless nonmagnetic dielectric medium with relative permittivity $\varepsilon_r = 2$, the same wave has a velocity

$$v = \frac{c}{\sqrt{\varepsilon_r}} = \frac{3 \times 10^8}{\sqrt{2}} = 2.12 \times 10^8 \text{ m s}^{-1} \tag{4}$$

and

$$\lambda = \frac{v}{f} = \frac{2.12 \times 10^8}{300 \times 10^6} = 0.707 \text{ m} = 707 \text{ mm} \tag{5}$$

1-4 DIMENSIONS AND UNITS.

Lord Kelvin is reported to have said:

> When you can measure what you are speaking about and express it in numbers you know something about it; but when you cannot measure it, when you cannot express it in numbers your knowledge is of a meagre and unsatisfactory kind; it may


Atmosphere opaque
Optical window
Infra-red windows
Radio window
Ionosphere opaque
Absorption by interstellar gas
Molecular lines
TV
AM
Longwave
Radar
Radar
Shortwave
Hydrogen line
Redwood tree
Man
Sand grain
Bacterium
Optical
Virus
Atomic spacing
Atom
Vela satellite bursts
Atomic nucleus
Objects of different size
Gamma rays
X-rays
Ultra-violet
Infra-red
Radio
Wavelength
1 10 100 1 10 100 1 10 100 1 10 100 1 10 100 1 10 100 1 10 100 1 10 100
attometers 10^{-16} m
femtometers 10^{-15}m
picometers 10^{-12}m
nanometers 10^{-9}m
micrometers 10^{-6}m
millimeters 10^{-3}m
meters m
kilometers 10^{3}m

Figure 1-6 The electromagnetic spectrum with wavelength on a logarithmic scale from the shortest gamma rays to the longest radio waves. The atmospheric-ionospheric opacity is shown at the top with the optical and radio windows in evidence.

Thus, the wavelength depends on the velocity v which depends on the medium. In this sense, frequency is a more fundamental quantity since it is independent of the medium. When the medium is free space (vacuum)

$$v = c = 3 \times 10^8 \text{ m s}^{-1} \tag{2}$$

Figure 1-7 shows the relation of wavelength to frequency for $v = c$ (free space). Many of the uses of the spectrum are indicated along the right-hand edge of the figure. A more detailed frequency use listing is given in Table 1-1.

Table 1-1 Radio-frequency band designations

Frequency	Wavelength	Band designation
30–300 Hz	10–1 Mm	ELF (extremely low frequency)
300–3000 Hz	1 Mm–100 km	
3–30 kHz	100–10 km	VLF (very low frequency)
30–300 kHz	10–1 km	LF (low frequency)
300–3000 kHz	1 km–100 m	MF (medium frequency)
3–30 MHz	100–10 m	HF (high frequency)
30–300 MHz	10–1 m	VHF (very high frequency)
300–3000 MHz	1 m–10 cm	UHF (ultra high frequency)
3–30 GHz	10–1 cm	SHF (super high frequency)
30–300 GHz	1 cm–1 mm	EHF (extremely high frequency)
300–3000 GHz	1 mm–100 μm	
Frequency	**Wavelength**	**IEEE Radar Band designation**
1–2 GHz	30–15 cm	L
2–4 GHz	15–7.5 cm	S
4–8 GHz	7.5–3.75 cm	C
8–12 GHz	3.75–2.50 cm	X
12–18 GHz	2.50–1.67 cm	Ku
18–27 GHz	1.67–1.11 cm	K
27–40 GHz	1.11 cm–7.5 mm	Ka
40–300 GHz	7.5–1.0 mm	mm


DIODE SYMBOL
ANODE
CATHODE
A
C
OA91
ACTUAL DIODE

An illustration of a modern diode which is often encapsulated in glass and is about 7mm long. Above is the electronic symbol for a diode.


Aerial Terminal
Basic Early Crystal Set
Tap A
Detector
High Impedance Headphones
Tuning Coil
Capacitor 1000pF
Tap B
Earth Terminal


AERIAL TERMINAL
Standard Crystal Set
Aerial Tap
Detector Tap
TUNING 500pF
DETECTOR DIODE OA91
TUNING COIL
RESISTOR 47k Ohm
EARPHONES
EARTH TERMINAL


AERIAL TERMINAL
IMPROVED CRYSTAL SET
AERIAL TRIMMER 10-50pF
A
B
DIODE OA91
CRYSTAL EARPHONE
RESISTOR 47k
TUNING CAP 500pF
TUNING COIL
EARTH TERMINAL

easily by having many different tapping points on the coil so that adjustments can be made.

To make tuning easier a component called a tuning capacitor can be included in the circuit. In very early sets a tuning capacitor was not always included to keep costs down, or due to their being difficult to obtain.

The Detector converts the radio wave received into an electrical wave that is suitable for the headphones to, in turn, convert into sound waves that can be heard by the human ear. In the very early days of the crystal set the detector consisted of a holder containing a piece of galena crystal that had a very thin and springy wire placed on its surface that had to be very delicately adjusted to find the sweet spot where the radio station could be heard. This was commonly referred to as a "Cat's Whisker". Modern detectors are called diodes and are more efficient than early detectors and cats whiskers. Diodes are still quite readily available and inexpensive. Part numbers for modern diodes include OA90, OA91 and IN34. Diode part numbers that are perhaps now more difficult to obtain include OA47 and OA81.

The headphones have to be of a very special type called high impedance headphones. Because there is no additional power source in a crystal set the current generated in the circuit is tiny - minuscule in fact. Ordinary low impedance headphones, such as Walkman headphones, would present a virtual short circuit to the crystal set allowing the tiny signals to drain away to earth & consequently producing no sound - not very useful!

High impedance headphones, on the other hand, reduce or impede the flow of current down to earth, in effect saving the tiny signals to produce sounds from the headphones that we can then hear.

There is a problem however, these high impedance headphones that were so readily available in the 1920's and 1930's are to so easy to obtain today, but some specialist vintage radio outlets still stock them though the price can be quite high. They can still be seen in museums of course. All is not lost though, today we can obtain a special earphone called, appropriately, a crystal earpiece very easily and far more cheaply than. An electronic component, called a resistor, must be connected accross the crystal earphone to allow a path for DC current to get to earth. The value of the resistor is usually 47,000 Ohms and without it a crystal earphone tends to block DC current and as a consequence the sound will be very quiet and distorted.

Aerial and Earth: For a crystal set work it needs an efficient aerial and earth. Since a crystal radio has no power - no batteries or mains electricity - it relies entirely on the radio wave energy sent out from the radio station's transmitter and collected by the aerial to work. The aerial simply consists of a length of wire, but it necessarily has to be quite long, usually in the order of 10 to 20 meters. For the aerial to be effective the crystal radio set also has to be connected to a good earth point. A good earth often consists of a 3 or 4 foot copper stake driven into the ground, but sometimes a water pipe can be used to reasonable effect. (Safety: Never use the earth pin of a household mains plug)

The circuit diagram (schematic) for a crystal set is shown below. Practical designs are shown on the following pages.



Click on photo for a larger picture





8 MILLION GAIN!

This circuit is so sensitive it will detect "mains hum." Simply move it across any wall and it will detect where the mains cable is located. It has a gain of about 200 x 200 x 200 = 8,000,000 and will also detect static electricity and the presence of your hand without any direct contact. You will be amazed what it detects! There is static electricity EVERYWHERE! The input of this circuit is classified as very high impedance.



Here is a photo of the circuit, produced by a constructor, where he claimed he detected "ghosts."

portable
DX
pedestrian mo
contests
vk3ye dot com
antennas
CB
shortwave
videos
HF

[Return to VK3YE amateur radio projects]

A simple crystal set for free power radio

Of any electronic project, the crystal set would have to rate as one of the most popular. Many amateurs are on the air today because of their early construction of a crystal set. Most practical electronic books for beginners include at least one crystal set project. Unfortunately, some of these circuits take simplicity too far and deliver mediocre performance, often by omitting key components such as the tuning capacitor, or failing to provide coil taps.

This article describes a crystal set of medium complexity. It features coil taps for the antenna and diode to make it useful for both country and metropolitan listeners. The taps allow the set to cover 160 metres if desired. All parts are easily obtainable, making it a good choice for the beginner. The endless possibilities for experimentation also make crystal sets interesting novelty projects for experienced constructors. The schematic is shown here:


Ant
Inductor
(see fig 2)
OA95
10 - 415pF
Tuning
1000pF
Disc ceramic
Headphones
High impedance
Earth

Figure One: Schematic diagram of crystal set

VK3YE Crystal Set

Schematic & Layout diagrams

Press Back button to return to main article


Tuning
Cap
tap
Diode
tap
Headphones
90
78
66
54
42
30
18
6
84
72
60
48
36
24
12
0
55 mm
Antenna
Antenna tap
Earth

Figure Two: Rear view of front panel, showing coil details

> *(from Amateur Radio February 2001, page 20)*

Obtaining the parts

Tuning capacitor


ELECTRIC CURRENTS
magnetosphere
thermosphere
60 - 80
+250 kV
IONOSPHERE
ALTITUDE , km
+
mesophere
FAIR
WEATHER
ATMOSPHERIC ELECTRICITY
E
J
σ
stratosphere
+ +
+100 MV
−100 MV
0 MV
10
5
0
130 Vm^{-1}
free troposphere
boundary layer
EARTH'S SURFACE
mountain

From M.J. Rycroft et al., JASTP, 2000


(a)
Collector
$V_0(z)$
E
V
voltmeter
Earth's surface
(b)
outer electrode
σ
central electrode
Bias
GERDIEN TUBE
pA
electrometer
cover plate
(c)
air-Earth current J_z
collecting plate
(surface)
guard ring
battery
J
compensator
electrometer

From R.G. Harrison, Surveys in Geophysics, 2004



Figure 12. (**a**) Output power for a half-wave and full-wave CWVM, and (**b**) portable electronic calculator running with the AM energy harvester. Detected input signal in LC resonator is 1.5 V at 1 MHz.

×
a)
CWVMs with 6 stages and C=10μF
Half-wave CWVM
Full-wave CWVM
ΔP=32μW
Output Power (μW)
1000
100
10
1
0.1
0.01
1E-4
1E-3
0.01
0.1
1
10
Load Resistance (MΩ)
b)

Figure 6. Pictorial image of the AM-RF energy harvesting system.


Coils
Cockcroft-Walton Multipler
Ferrite core
Variable Capacitor
Output
−
+

Figure 11. (a) AM resonator implemented, (b) Full-wave CWVM implemented, (c) top view of the AM resonator and full-wave CWVM, and (d) lateral view of the AM resonator and full-wave CWVM.



Figure 12. (a) Output power for a half-wave and full-

WEATHER MODIFICATION TECHNOLOGIES 2018


THERMOSPHERE
MESOSPHERE
STRATOSPHERE
TROPOSPHERE
IONOSPHERE
93 Miles
150 Kilometers
53 Miles
85 Kilometers
31 Miles
50 Kilometers
39k Feet
12 Kilometers
ARTIFICIAL MIRROR/LENS
ARTIFICIAL AURORA
AIR GLOW
NOCTILUCENT CLOUD
NACREOUS CLOUD
OZONE LAYER
WWH
WEATHERMODIFICATIONHISTORY.COM
1
2
3
4
5
6
7
8
9
10

Image by Jim Lee, **ClimateViewer.com**

1. **Ionospheric Heater** MICROWAVE, NOCTILUCENT, PLASMA CLOUDS, ELF/VLF
2. **Sounding-Rockets** CHEMICAL RELEASE, NACREOUS, NOCTILUCENT CLOUDS
3. **Satellite** CHEMICAL RELEASE, DEW, IONOSPHERIC HEATER, ELF/VLF GENERATION
4. **Lasers** RAIN CCN, IONIZATION, CHANNEL LIGHTNING
5. **Cloud Seeding** CHEMICAL RELEASE, RAINFALL, HAIL, CLOUD CLEARING
6. **Cloud Ionizers** ELECTRIC RAINMAKING WITH IONS
7. **Stratospheric Aerosol Injection** GEOENGINEERING SOLAR RADIATION MANAGEMENT (SRM) CHEMICALS CREATE SUNSHADE: SULFUR, ALUMINUM, TITANIUM, DIAMOND DUST, CALCIUM, BISMUTH TRI-IODIDE.
8. **Ship Tracks** MARINE CLOUD BRIGHTENING (MCB), STRATOCUMULUS
9. **Contrail-Induced Cirrus** CIRRUS CLOUD CREATION, TRAPS HEAT, MELTS POLES
10. **Water Vapor Pollution** CLOUD CREATION VIA: SMOKESTACKS, COOLING TOWERS, WSAC, TMS-65, J2X ROCKET, JET ENGINES

Red Numbers: Considered Inadvertent, Accidental, or Pollution... unless intentional. Objects not to scale. Not included: steering atmospheric rivers

GENERATORS, HIGH ALTITUDE DISCHARGES, TLE´s


100
50
0
Ionosphere
Stratosphere
Elve
Gigantic jet
Sprite
Blue jet
Cloud-to-ground lightning
100
200
Distance (km)

Working Model of Crystal radio


Antenna
Coil
Ground
water pipe
for ground

Schematic Diagram of the Radi


Antenna
3
Diode
1N34A
2
Ferrite Loopstick Antenna
A
Variable Capacitor
G
4
Resistor
47K
.001uf
Capacitor
Ceramic
Earphone
5
wire
1
Ground
O
G
A
Variable Capacitor
Top Side

Philmore

MANUFACTURING CO. Inc.
Richmond Hill 18, N. Y.

MODEL NO.
VC-1000


ANTENNA
GROUND
EAR PHONE
KNOB
GERMANIUM
CRYSTAL DIODE


36" above head MC14
S12 deep space
18" above head MC11
6" above head MC10
S11 deep space
MC9
C7
C6
S7
C5
MC8
S6
S5
C4
S4
Central Body Current Hara Line & Central Vertical Kathara Line
C3
S9
S3
C2
S2
C1
S1,
S15
MC 12
6" below feet
S8
MC 13
Earth Core
S10
Earth
MC 15
deep space S13,
S14

Signet
Star Crystal Seals (S)

The 5 Hova Bodies progressively merge with the release of the embodied Signet Star Crystal Seals, forming the various phases of the personal Merkaba Vehicle within the bio-energetic field.

15 Chakras (C & MC)
7 Primary Chakras (C)
- C-1 Base
- C-2 Sacral
- C-3 Solar Plexus
- C-4 Heart
- C-5 Throat
- C-6 3rd Eye - Pituitary
- C-7 Crown - Pineal

8 Morphogenetic Chakras (MC)
- MC8 Thymus
- MC9 Thalamus
- MC10 Galactic 1
- MC11 Galactic 2
- MC12 Earth Star
- MC13 Earth Core
- MC14 Universal 1
- MC15 Universal 2

SIGNET Seals

15 Star Crystal Seals

Star Crystal Seals keep human identity & *Auric Levels* dimensionally separate. Control Dimensional *Merkaba Field Axis* & *Angular Rotation of Particle Spin.*

15 Star Crystal Seals (S):
- S1 Red Star
- S2 Orange Star
- S3 Yellow Star
- S4 Green Star
- S5 Blue Star
- S6 Indigo Star
- S7 Violet Star
- S8 Gold Star
- S9 Silver Star
- S10 Blue-Black Star
- S11 Silver-Black
- S12 White Star
- S13 Pale Turquoise Star
- S14 Pale Yellow
- S15 Pale Magenta Pink

COPYRIGHT MATERIAL

Copyright A'shayana & A'hzayana Deane, 1999-2007, All Rights Reserved; Part of the MCEO Freedom Teachings™ Series

Scalar Interferometry In The Endothermic (Cooling) Mode


MEETING OF TIMED PULSES CAUSES EXPLOSIVE COOLING
COOLING IN INTERFERENCE ZONE
Ambient vacuum potential in distant interference zone
Φ_a
heat
Bias
Heat extracted
heat
XMTR/RCVR
XMTR/RCVR
Φ_T
Electrical ground potential of transmitter
Heat emerges at transmitter/receiver
Heat emerges at transmitter/receiver

In the endothermic mode, tremendous heat is received back in the transmitters. Soviets further retransmit the heat via interferometers to a distant "exhaust" point. Bennett Island was used for such an exhaust point for decades, and our observation platforms saw a great many 150 miles-long jets of exhaust effects in narrow beams at shallow angles.

Measuring Longitudinal and Transverse waves

The Fizzics Organisation

Transverse waves

A shaking rope is a good example. The wave moves along the rope but the bits of rope go up and down - across the direction of the wave. “Trans” means across, think of “transatlantic” or “transfer”.



A water wave is another example of a transverse wave.



a is the amplitude of the wave measured from the maximum height to the middle. Think of a water wave, it is the distance from either the crest or the trough to where the water would be if it were calm.

λ is the wavelength. That is the distance from one point on a wave to the same point on the next wave - for example from crest to crest or trough to trough.

f is the frequency of the wave, that is the number of waves which are produced every second (or the number passing every second). This number is given the unit “hertz”. One hertz is one wave per second.

Most of the examples of waves we have to deal with are transverse waves. All the waves in the electromagnet spectrum are transverse waves.

There is a connection between the frequency and wavelength of a wave. If the frequency is increased - if there are far more waves, then they are closer together; in other words the wavelength is less. **The speed is equal to the frequency multiplied by the**

$$V = f \times \lambda$$

m/s hertz metres

A longitudinal wave is a “pushing” wave. A line of dominos falling is an example.

If one end of a slinky is pushed and pulled then each coil pushes and pulls the next. The coils oscillate along in the same direction that the wave is traveling.









Here the coils are compressed together and here they are stretched out.


YouTube
Search
Tuning capacitor
ANT
GRD
Phones/Amplifier
3:35 / 8:40

Making a Crystal Radio (How to make a Crystal Radio)

Graham Cates


103
10nF
82uH
5.6 KOhm
1N4007
1N4007
82uH
82uH
82uH
2N2222A
2N
2222
331
DURACELL
AA

Connect LED in all parallel
Red = Posive
Black = Negative

The joule thief circuit.


resistor
1kΩ
Ferrite toroid core
with two lengths of
small diameter wire
e.g. 26 gauge,
30 gauge, ...
AA battery
flat side is facing
out of the page
transistor
2N4401
C
B
E
one leg is longer
than the other
LED (Light Emitting Diode)
(C - Collector, B - Base, E - Emitter)

Transistor - The legs of the transistor can be determined by noticing that there's a flat side to the transistor case. See the diagram above. A large number of transistors have been reported to work: 2N4401, NET123AP, BC547B, 2SC2500, BC337, PN2222, to name just a few.

LED - One leg of the LED is longer than the other leg. Use this to determine which one goes where. See the diagram above.

Resistor - The diagram says use a 1 kilo ohm resistor but I've used an 820 ohm one just fine. I've also seen a 2 kilo ohm one in use. Use whatever works for you. You can also use a potentiometer (a variable resistor) so that you can easily adjust it to select the resistance that gives the best light.

Toroid ferrite core - Some people have gotten these by opening up compact fluorescent lightbulbs (CFLs). I took mine out of some device whose original function I don't know. To get it working, my first one had just 13 turns for each wire and I used a 30 gauge wire and a 26 gauge wire. The wire must be insulated. A variety of number of turns will work. This is something you can play with. Look at the diagram carefully to determine where the wires connect to.


LONG WIRE AERIAL: AT LEAST
20 METRES (60 FT) OF WIRE
LOCATED 7 METRES (20 FT)
ABOVE THE GROUND
D1
OA47
a
k
OA47
a
k
L1
100t
26 S.W.G.
(25 A.W.G.)
VC1
5p TO
140p
RX
TO CRYSTAL
EARPIECE
C1
10n
RX 4k7. ONLY REQUIRED
IF SET CONNECTED TO
HEADPHONE AMPLIFIER
EFFECTIVE EARTH
(SEE TEXT)


octave ↓
perfect fourth ↓
minor third ↓
supermajor second ↓
"lesser tone" ↓
lesser undecimal neutral second ↓
lesser tridecimal 2/3-tone ↓
just diatonic semitone ↓
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
perfect fifth ↑
major third ↑
subminor third ↑
"greater tone" ↑
greater undecimal neutral second ↑
greater tridecimal 2/3-tone ↑
septimal diatonic semitone ↑



LED

The Tesla Experiment



TRANSVERSE WAVE INTERFERENCE



ENERGY ZONES
INTERFERENCE ZONE
XMTR #1
ZERO ENERGY LINES
(0̄-LINES)
XMTR #2

LONGITUDINAL WAVE INTERFERENCE
(SCALAR WAVES)



XMTR #1
0̄-WAVES
ZERO ENERGY LINES
ENERGY BOTTLE
(interference zone)
XMTR #2
0̄-WAVES
VECTOR ENERGY ZONES

© PoweredTemplates.com


antenna in
104
104
100uF 50V
100uF 50V
−
+
−
+
−
output
+

RF to DC

Circuit Diagam (simplified)

Component list:
(2) Ceramic Capacitors (104)
(4) Germanium Diodes (1N34A)
(2) Electrolytic Capacitors (100uF 50V)

Copyright 2018. Drew Paul Designs. All rights reserved.




Aluminium plate (foil)
1N4148
+
-
GROUND


+
C2
C3
To antenna
C1
C4
+
–
+
–
—

Silent Sound Subliminal Mind Control


1
Mic.
2
FREQUENCY MODULATOR, VOICE CONTROLS FREQ.
3
4
5
5

1 Steady tone, near the high end of the hearing range, say, 15,000 Hz

2 Hypnotist's Voice, varying from, say, 300 Hz to 4,000 Hz

4 Output is now more or less a steady tone, souding like tinnitus, but with hypnosis embedded

Brain can hear voice & understand

Ear only hears a "tone" or "buzzing/ringing"

Output can be via open air broadcast or piggybacked on TV/radio signals

U.S. Patent 5159703 issued Oct 27, 1992

Table 1: Dinshah's Sound/Color Equivalent Chart.

Color	Frequency	Musical Note	Note Frequency
Red	397.5	G	378 (3 x 126 = 378)
Orange	430.5	A	432 (3 x 144 = 432)
Yellow	464.5	A#	459 (3 x 153 = 459)
Lemon	498	B	486 (3 x 162 = 486)
Green	531.5	C	513 (3 x 171 = 513)
Turquoise	565	C#	540 (3 x 180 = 540)
Blue	598.5	D	567 (3 x 189 = 567)
Indigo	632	D#	594 (3 x 198 = 594)
Violet	665.5	E	648 (3 x 216 = 648)
Purple	565*	A# and E	562*
Magenta	531.5*	G and E	525*
Scarlet	498*	G# and D	501*

*denotes reverse polarity. From:

Dinshah GP. Spectralchrometry Encyclopedia, 3rd Ed.


Optional Microphone
Transistor
Capacitors
Inductor
Resistors
RF Out
Audio In
Tuning Capacitor
Power Switch
Battery (can be replaced with external power)


ACT I
The Situation
(20-30 pages)
ACT II
Complications / Obstacles
(50-60 pages)
Act III
Conclusion
(15-30 pages)
Point of Attack
Inciting Incident
First Turning Point
MidPoint
Second Turning Point
Climax (Resolution)
E N D


TO AERIAL, AT LEAST 20 METRES
(60FT) OF WIRE MOUNTED 7 METRES
(20FT) MINIMUM ABOVE THE GROUND
CRYSTAL
EARPIECE
DIODE LOAD RESISTOR, RX, IS ONLY
REQUIRED IF CRYSTAL RECEIVER IS
CONNECTED TO HEADPHONE AMPLIFIER.
D1
a
k
L1
100t
L1
26 S.W.G.
(25 A.W.G.)
A
VC1
G
O
C1
RX
JACK PLUG
AND
SOCKET
TO EARTH, BISCUIT TIN OR 1M COPPER
PIPE IN DAMP GROUND. CONNECTION TO
CENTRAL HEATING PIPEWORK WILL OFTEN
SUFFICE.


Meter movement
Common
-
+
Rshunt
A
V/mA
Selector switch


Antenna
Acrylic board
Diode
earphone

Schematic of basic radio receiver circuit


CH 1 scope
Inductor (coil)
GND
L
Acryllic board.
Attach Antenna here
Variable C knob
Wires from the acryllic board
Spring board
diode
Earphone


Anode
Cathode
+
-


resistor
battery
1.5 volts
+
–
battery
voltage
Base
transistor
Emitter
Collector
ferrite toroid core
wrapped with
two coils of wire
LED - needs 1.85 volts
(Light Emitting Diode)


+Karl
Search
Images
Maps
Play
YouTube
News
Gmail
Drive
Calendar
More
Google
kryptonique
Karl Smirni
0
+ Share
Books
Add to my library
Write review
Page E-1
GET PRINT BOOK
No eBook available
Trafford Publishing
Amazon.com
Barnes&Noble.com
Books-A-Million
IndieBound
Find in a library
All sellers »
+1
0
0 Reviews
Write review

Result **4** of **4** in this book for **kryptonique** - ‹ Previous Next › - View all

Clear search

They All Told the Truth: The Antigravity Papers

By Richard P. Crandall

kryptonique
Go
About this book

Lost Dwgs & Tech, Ancient India, & "Four"

THE LOST HAMEL DRAWINGS:

David Hamel's "Isotope Line of Movement" creating the:

POSITIVE - NEUTRAL - NEGATIVE

mechanical parts needed to create a self running system.

(male)
Rotating Rod with a Neutral Center
(female)
Hamel Technology
1
2
3
The Eye (particle of nature)
Twice the Aether
Equals
Scale (perfect balance of nature)
The Duality (opposites)
Celestial Power
2
1st Particle of Nature (male)
2nd Particle of Nature (female)
KRYPTONIQUE
Gases of space

Particle Structure. [The MOST IMPORTANT Hamel Diagram of All.]

- synchronous charging circuit generate more electromagnetic wave


All diodes 1N4002
Antenna
Antenna
Antenna
Antenna
HTTP://HOWTODOSTEPS.BLOGSPOT.COM
-
+

Easy Simple Free Energy Harvesting from Surro...


1 kilometer
10^{3}mt
1 meter
1 milímeter
10^{-3}mt
1000 nanometer
10^{-6} mt
1 nanometer
10^{-9} mt
10^{-12}
Radio
Microwave
Radar
Infrared Rays (IR)
Ultraviolet Rays UV
X Rays
Gamma Rays
Cosmic rays
Long Wave
Short Wave
Infrared Rays
Visible Light
UV Rays
700 nanometers
600 nanometers
500 nanometers
400 nanometers
Less energy
Glass
P470
More energy


UHF Antenna
+
C=98uF
DVM
HP3476B
DVM
Earth Ground

Figure 2 -- Shows the main components of the FEA : 1) a bridge rectifier, 2) an earth ground connection, 3) an antenna, and 4) a capacitor. The DVM was used for making test measurements.

TAGS

fpv uav osd video camera tx rx

CATEGORIES

- **Accessory**
- **Antenna**
- **Camera**
- **Camera Mount**
- **Combo system**
- **DIY System**
- **LCD Goggles**
- **OSD & Telemetry**
- **RC Shutter**
- **Ready to Use sets**
- **Receiver**
- **Transmitter**

INFORMATION

- Shipping
- Returns
- Payment
- About us
- Contact us

Home > Antenna > 19dBi 2.4gHz High gain panel antenna

19DBI 2.4GHZ HIGH GAIN PANEL ANTENNA





High gain 2.4gHz 19 dBi patch antenna.

More details

ON SALE!
$39.90

your@email.com
Notify me when available

Add to my wishlist

- Send to a friend
- Print
- View full size

IN THE SAME CATEGORY

14dBi 2.4gHz...

11dBi 2.4gHz...

18 dBi 5.8...

12dBi 5.8...

14dBi 5.8...

MORE INFO

19 dBi panel antenna.

Sizes 26x27 cm.

Horizontal & vertical beam width: 17 **degrees**

-

Package contains:

19 dBi antenna.

1 meter SMA connection cabel

Tripod.

CART

(empty)

NEW PRODUCTS

1.2 gram
5.8 GHz RACEBAND

5.8 GHz RACEBAND TRANSMITTER
1.2 GRAM WEIGHT »

All new products

TOP SELLERS

SALE
Nano Camera
wide angle Lens
5.8gHz
200mw
world's
first
1S LiPo
2.2g only

- WIDE ANGLE LENS FOR NANO CAMERA
- 200mw 5.8gHz A/V Transmitter
- 5.8 GHz AVTx for Fatshark
- 5V Step-up/step-down regulator
- 1 gram PAL camera

All best sellers

SPECIALS

No specials at this time

WISHLIST

No products

My wishlists

ONLINE USER

Online User: 6
Access Today: 931
Access Total: 666940
Your IP: 172.0.74.23


Antenna wire
Tic Tac Radio
Earphone
Antenna lead in
Polyvaricon tuning capacitor
Ground wire


gamma rays
X-rays
ultraorange rays
infrayellow rays
radar
FM
TV
shortwave
AM
1.094x10^-14
1.094x10^-12
1.094x10^-10
1.094x10^-8
1.094x10^-6
1.094x10^-4
1.094x10^-2
1.094x10
1.094x10^2
1.094x10^4
Wavelength (yards)
Visible Light
1.988x10^-5
2.486x10^-5
2.982x10^-5
3.480x10^-5
Wavelength (furlongs)


ELECTROMAGNETIC SPECTRUM
Frequency (Hz)
Wavelength
Gamma-rays
X-rays
Ultraviolet
VISIBLE
Near IR
Infra-red
Thermal IR
Far IR
Microwaves
Radar
AUDIO
Radio, TV
AM
Long-waves
10^{19}
10^{18}
10^{17}
10^{16}
10^{15}
10^{14}
10^{13}
10^{12}
10^{11}
10^{10}
10^{9}
10^{8}
10^{7}
10^{6}
0.1 Å
1 Å
0.1 nm
1 nm
10 nm
100 nm
1000 nm
1 µm
10 µm
100 µm
1000 µm
1 mm
1 cm
10 cm
1 m
10 m
100 m
1000 m
400 nm
500 nm
600 nm
700 nm
1000 MHz
500 MHz
100 MHz
50 MHz
UHF
VHF
7-13
FM
VHF
2-6

Louis E. Keiner - Coastal Carolina University


10^{-2} 10^{0} 10^{2} 10^{4} 10^{6} 10^{8} 10^{10} 10^{12}
10^{8} 10^{6} 10^{4} 10^{2} 10^{0} 10^{-2} 10^{-4} 10^{-6} 10^{-8} 10^{-10} 10^{-12} 10^{-14} 10^{-16} 10^{-18}
Long Wave
Medium Wave
Short Wave
Cell phone GPS
Micro Ovens
infrared
Ultraviolet
Radio Waves
Microwave Radar
X Ray
Gamma Rays
Cosmic Rays
10^{0} 10^{2} 10^{4} 10^{6} 10^{8} 10^{10} 10^{12} 10^{14} 10^{16} 10^{18} 10^{20} 10^{22} 10^{24} 10^{26}
FREQUENCY (Hz)
Visible Light
NON-INOISING RADIATION
INOOSING RADIATION


1
2
D1
3
Antenna
C1
Crystal
Earphone
Ground
L1
5
R1
4
Link Wire



Shaft connected to moving plates

Small polyvaricon tuning capacitor (PVC tuner cap)

Fixed plates insulated from frame and moving plates, by either air or plastic sheets.



Diode is forward-biased by meter -- shows a forward voltage drop of 0.548 volts.

0.548
Ω
OFF
V Ω
A
COM
+
-
Anode
Cathode


TO EARTH
TO AERIAL
TB1
k
D1
a
TO HEADPHONES (TL1)


TB1
k
D1
a


TB1
k
D1
a


TO EARTH
TO AERIAL
TB1
k
D1
a
TO HEADPHONES (TL1)


L1
TO EARTH
TO AERIAL
1
2
3
4
5
6
7
8
9
10
11
12
TB1
k
D1
a
TO HEADPHONES (TL1)
C1
TUNING


AERIAL TERMINAL
EARTH TERMINAL
COIL
TRIMMER
DIODE
RESISTOR
CLIP
CLIP
TUNING CAP.
3.5MM SOCKET
KNOB


AM Broadcast band Coil & former
Ferrite Balun core and stick
Tic Tac lolly box
To Aerial Wire
Clips
Diode
To Earth Wire
68pF Capacitor
100K Resistor
3.5mm Jack Socket

Diagram 2. Place balun inside coil former and use the stick to slide it up and down inside the coil to tune the Nic Nac Radio.

The MK 484 TRF Receiver - With Inductive Coupling!

Copyright © **Austin Hellier** 10/01/2001


L1 - 50 turns of insulated telephone wire
L2 - five turns of telephone jumper wire around the end of the ferrite rod
Crystal Earpiece
100KR
*
+ve 1.5 or 9 volts
IC1
MK484
1
2
3
1K5 for 1.5 volt battery, or 6K8 for 9 volt battery
C1
0.01uF
MKT
C2
0.1uF
MKT
* Denotes a solder joint or screw/washer termination
240pF Variable Capacitor
100mm x 9mm ø ferrite rod
-ve 0 volts

Diagram 1. MK484 Radio Receiver for the AM Band

Build This Modern AM Radio Receiver For Just $12.00!

This adaption of the famous ZN414 (now MK484 plastic pack) AM radio receiver, was inspired by the fact that I live fairly close to my three local AM stations (2WL, 2WN and the ethnic broadcaster 2RPH) and would normally receive overloaded signals with a standard TRF design based on this IC. With the minor modifications made to the basic design as shown, and with the aid of the inductive coupling arrangement, i can pick up all three stations with clarity and volume, and with hardly any (and I mean ANY) interference from each other, and no oscillations!

Make sure that you wire the MK484 (IC1) up correctly - the pinouts shown above are seen from the top of the device. Wind L2 so that it fits snugly on the end of the rod, right next to the end of L1 's winding. The average 9 volt battery gives much better volume and selectivity, and should last for some months of constant use - if you've got a few spare $, try a new Eveready Lithium or the new Kodak Alkaline!

MK484 ICs are available from **http://www.dse.com.au/** (cat# Z6525 for $2.36AUD).

Construction

You can make this circuit up quickly on your SK-10 panel, or use something like the Dick Smith "Funway

Parts List		**DSE#**
IC1	MK 484	Z6525

The Nic Nac Crystal Radio

Copyright © **Austin Hellier** 12/02/2001


Coil former
Balun core and modified stick

How It Works

Radio signals are travelling through the atmosphere all the time. This simple radio receiver has been designed to capture them, and turn them into sound waves, so that you can hear what's going on. The Aerial and Earth wires form a return signal path from the AM transmitter, for these signals, and they are then fed into the coil and capacitor. This arrangement is known as a 'tank' circuit, because it stores radio energy, much in the same way your family car's tank stores petrol. The combination of a certain sized capacitor (68pF) and the amount of turns on the coil (around 120 turns) determines the frequency you will receive at. The Diode changes the signal from a radio one, to an audio one, and the Crystal Earphone changes the audio signal into sound waves that you can hear. the resistor adds stability by helping to prevent the Earphone from occasional 'dropout'.

Building The Radio

You'll need all the components listed below and a Tic Tac lolly box. Start by mounting the earphone jack into the lid of the box and then solder up each of the components into a tidy version of the 'rat's nest' construction method. Make sure you use a crocodile clip as a heat sink for the diode when soldering - they're pretty sensitive devices to heat. Then take the coil and remove the ferrite rod from inside it. Take the ferrite balun core and place one end of the plastic stick (obtained by cutting off both ends of a cotton bud) and glue it inside the hole, with its end level with the end of the balun core.


Ferrite Balun core and stick
AM Broadcast band Coil & former
Tic Tac lolly box
To Aerial Wire
Clips
Diode
To Earth Wire
68pF Capacitor
100K Resistor
3.5mm Jack Socket

Diagram 2. Place balun inside coil former and use the stick to slide it up and down inside the coil to tune the Nic Nac Radio.


Ferrite Balun core and stick
AM Broadcast band Coil & former
Tic Tac
lolly box
To Aerial Wire
Clips
Diode
To Earth Wire
68pF Capacitor
100K Resistor
3.5mm Jack Socket

Diagram 2. Place balun inside coil former and use the stick to slide it up and down inside the coil to tune the Nic Nac Radio.

AMCI BROADCAST EQUIPMENT for VHF and UHF-TV and FM



VHF-TV
Transmitting Antennas

VHF-TV TRANSMITTING ANTENNAS

Mast or tower-corner mounted

DIRECTIONAL OR OMNIDIRECTIONAL

for Channels 5 to 13

Omnidirectional VHF-TV antennas with power gains up to 20. Directional VHF-TV antennas with power gains up to 36.

UHF-TV TRANSMITTING ANTENNAS

Mast, tower-corner, or truss-mounted

DIRECTIONAL OR OMNIDIRECTIONAL

for Channels 14 to 83

Omnidirectional UHF-TV antennas with power gains up to 50. Directional UHF-TV antennas with power gains up to 80.

FM TRANSMITTING ANTENNAS

Mast or tower-corner mounted

DIRECTIONAL OR OMNIDIRECTIONAL

For single or multi-station transmission.

UHF-TV
Transmitting Antennas

SPECIAL PURPOSE ANTENNAS

The Empire State Building Master FM Antenna; two rows of dipoles around the 102nd floor observation level, the diplexers within the tower, and the transmission line, designed, built, and installed in 1965, permit up to 17 FM stations to broadcast simultaneously from the same antenna.

DIPLEXING FILTERS

Temperature compensated. Aural-to-visual and visual-to-aural rejection over 30 db. For use with transmitters up to 50 kw.



THE DE FOREST AUDION

"There is only *one* Audion—the De Forest"



THE GENUINE DE FOREST TUBULAR AUDION

Is sold separately to any amateur who prefers to build his own Audion Detector **Price $5.50**

Adapter 40 cents extra.

Get the Bulletin (X16)

MOST SENSITIVE

The Bulletin of the U. S. Bureau of Standards states that the De Forest Audion is fully 50 per cent. more sensitive than any other known form of detector (Vol. 6, No. 4, page 540).

MOST RELIABLE

It is not affected by mechanical vibration nor burned out by static or the transmitting spark. It never fails at the critical moment.

The detector is the heart of the receiving set. Why waste valuable time on an insensitive, unreliable detector?

The genuine De Forest Audion is now within the means of every operator.



THE TYPE RJ9 DE FOREST AUDION DETECTOR

Incorporates the Audion Bulb and the genuine De Forest patented circuits with the most approved accessories needed to form a complete detector.

The most popular Audion Detector ever offered. **Price $14.00**

Get the Bulletin (M16)

WARNING—You are entitled to the genuine Audion, guaranteed by the owners of the Audion patents, when making an investment of this kind. Any evacuated detector having a filament, a grid and a plate, as well as other types, are covered by our patents, and several irresponsible infringers are being prosecuted. To be safe and get full value for your money, insist on the genuine De Forest Audion.

SEND FOR BULLETINS X16 AND M16 DESCRIBING AUDION

Detectors, Audion Amplifiers and Audion Receiving Cabinets

DE FOREST RADIO TELEPHONE & TELEGRAPH CO.

101 PARK AVENUE -:- NEW YORK, N. Y.

Makers of the Highest Grade Receiving Equipment in the World



Shopping List:

4 - Germanium Diodes (1N34)

2 - 100 µF 50V electrolytic capacitors

2 - 0.2 µF 50V ceramic capacitors

LED diagram:

Electronzap.com | Electronzapdotcom (Youtube) | Electronzap (Pinterest)



Anode Side

Cathode Side

Flat edge

Anode side of schematic symbol
resembles an arrow pointing
from positive to negative.
(Conventional current)

Dash side of schematic
indicates cathode.

Longer lead

Shorter lead

Electronzap

Electronzap

US Amateur Radio Bands

US AMATEUR POWER LIMITS

FCC 97.313 An amateur station must use the minimum transmitter power necessary to carry out the desired communications. (b) No station may transmit with a transmitter power exceeding 1.5 kW PEP.

Effective Date
March 5, 2012

Published by:
ARRL The national association for AMATEUR RADIO®
www.arrl.org
225 Main Street, Newington, CT USA 06111-1494

160 Meters (1.8 MHz)

Avoid interference to radiolocation operations from 1.900 to 2.000 MHz


E,A,G
1.800
1.900
2.000 MHz

80 Meters (3.5 MHz)


3.500
3.600
3.700
4.000 MHz
E
A
G
N,T
(200 W)
3.800
3.525
3.600

60 Meters (5.3 MHz)


2.8 kHz
E,A,G
(100 W)
5330.5
5346.5
5357.0
5371.5
5403.5
kHz

General, Advanced, and Amateur Extra licensees may operate on these five channels on a secondary basis with a maximum effective radiated output of 100 W PEP. Permitted operating modes include upper sideband voice (USB), CW, RTTY, PSK31 and other digital modes such as PACTOR III as defined by the FCC Report and Order of November 18, 2011. USB is limited to 2.8 kHz centered on 5332, 5348, 5358.5, 5373 and 5405 kHz. CW and digital emissions must be centered 1.5 kHz above the channel frequencies indicated above. Only one signal at a time is permitted on any channel.

40 Meters (7 MHz)


7.000
7.125
7.300 MHz
E
A
G
N,T
(200 W)
7.175
7.025
7.125

Phone and Image modes are permitted between 7.075 and 7.100 MHz for FCC licensed stations in ITU Regions 1 and 3 and by FCC licensed stations in ITU Region 2 West of 130 degrees West longitude or South of 20 degrees North latitude. See Sections 97.305(c) and 97.307(f)(11). Novice and Technician licensees outside ITU Region 2 may use CW only between 7.025 and 7.075 MHz and between 7.100 and 7.125 MHz. 7.200 to 7.300 MHz is not available outside ITU Region 2. See Section 97.301(e). These exemptions do not apply to stations in the continental US.

30 Meters (10.1 MHz)

Avoid interference to fixed services outside the US.


200 Watts PEP
E,A,G
10.100
10.150 MHz

20 Meters (14 MHz)


14.000
14.150
14.350 MHz
E
A
G
14.175
14.025
14.150
14.225

17 Meters (18 MHz)


E,A,G
18.068
18.110
18.168 MHz

15 Meters (21 MHz)


21.000
21.200
21.450 MHz
E
A
G
N,T
(200 W)
21.225
21.275
21.025
21.200

12 Meters (24 MHz)


E,A,G
24.890
24.930
24.990 MHz

10 Meters (28 MHz)


28.000
28.300
29.700 MHz
E,A,G
N,T
(200 W)
28.000
28.500

6 Meters (50 MHz)


50.1
E,A,G,T
50.0
54.0 MHz

2 Meters (144 MHz)


144.1
E,A,G,T
144.0
148.0 MHz

1.25 Meters (222 MHz)


E,A,G,T
N (25 W)
219.0
220.0
222.0
225.0 MHz

*Geographical and power restrictions may apply to all bands above 420 MHz. See *The ARRL Operating Manual* for information about your area.

70 cm (420 MHz)*


E,A,G,T
420.0
450.0 MHz

33 cm (902 MHz)*


E,A,G,T
902.0
928.0 MHz

23 cm (1240 MHz)*


1240
1300 MHz
E,A,G,T
N (5 W)
1270
1295

All licensees except Novices are authorized all modes on the following frequencies:

2300-2310 MHz	10.0-10.5 GHz *	122.25-123.0 GHz
2390-2450 MHz	24.0-24.25 GHz	134-141 GHz
3300-3500 MHz	47.0-47.2 GHz	241-250 GHz
5650-5925 MHz	76.0-81.0 GHz	All above 275 GHz

* No pulse emissions

KEY

Note:

CW operation is permitted throughout all amateur bands.

MCW is authorized above 50.1 MHz, except for 144.0-144.1 and 219-220 MHz.

Test transmissions are authorized above 51 MHz, except for 219-220 MHz.

🟥 = RTTY and data
🟩 = phone and image
▨ = CW *only*
🟨 = SSB phone
🟦 = USB phone, CW, RTTY, and data
🟧 = Fixed digital message forwarding systems *only*

E = Amateur Extra
A = Advanced
G = General
T = Technician
N = Novice

See *ARRLWeb* at *www.arrl.org* for detailed band plans.

ARRL
We're At Your Service

ARRL Headquarters:
860-594-0200 (Fax 860-594-0259)
email: hq@arrl.org

Publication Orders:
www.arrl.org/shop
Toll-Free 1-888-277-5289 (860-594-0355)
email: orders@arrl.org

Membership/Circulation Desk:
www.arrl.org/membership
Toll-Free 1-888-277-5289 (860-594-0338)
email: membership@arrl.org

Getting Started in Amateur Radio:
Toll-Free 1-800-326-3942 (860-594-0355)
email: newham@arrl.org

Exams: 860-594-0300 email: vec@arrl.org

Copyright © ARRL 2012 rev. 4/9/2013


10⁻⁶ nm
10⁻⁵ nm
10⁻⁴ nm
10⁻³ nm
10⁻² nm
10⁻¹ nm
1 nm
10 nm
100 nm
10³nm=1 µm
10 µm
100 µm
1000µm=1mm
10mm = 1 cm
10 cm
100 cm = 1 m
10 m
100 m
1000 m = 1 km
10 km
100 km
Wavelength
Gamma rays
Ultraviolet radiation
X rays
Visible light
400 nm
Violet
Blue
Green
Yellow
Orange
Red
700 nm
near
mid
far
(heat)
Microwaves
Infrared radiation
Radio waves


L1
TO EARTH
TO AERIAL
1
2
3
4
5
6
7
8
9
10
11
12
TB1
k
D1
a
TO HEADPHONES (TL1)
C1
TUNING



Joule Thief
In −
In +
R1
Out −
Out
Led +

True Joule Thief - White LED

☆☆☆☆☆ Be the first to write a review.

Item condition: **New**

Time left: 20d 07h 2/17, 3:27PM

Quantity: 1

Mor

Price: **GBP 6.85**
Approximately **US $9.72**

Longt

Shipping: **GBP 9.00 (approx. US $1**
See details about international



OLD WORLD ORDER - NEW WORLD ORDER

The Trinity of Globalist Control

THERE IS NO DEMOCRACY HERE

Vatican City City of London Washington D.C.

Religion Finance Military

NO FREEDOM FOR MIND OR BODY

**All three are separate states,
completely independent of their respective countries.**

WORLD SUPER POWERS

atruthsoldier.wordpress.com

City of London

Finance

Vatican City

Religion

Washington D.C.

Military

All three are separate states, completely
independent of their respective countries.

what do these 3 cities have in common?

City of London

Washington
District of Columbia

Vatican City

- they pay no taxes
- they are under no national authority
- they have totally Independent Identities from the rest of the world

SPEAK FOR YOURSELF



under St. Peter's Basilica

Mausoleum U
The façade of this mausole
16th c. foundations

Depiction of Lucif
morning star. On
drawing of Vesper
symbols of the hu

Go Back

POLARSTERN

ET OVES
ΣΥ ΒΟΣΚΕΙΣ ΤΑ

ELF, GWEN Towers, and HAARP Connection
These things are pretty sinister and all over the U.S.
Click "see more" to read article

ELIGO TE
NC VNA FIDES
TV ES PETRVS ET SVPER
HINC SACERDO
ET O PETRE DIXISTI TV ES
VIVAT IESVS BEATVS
ΣΥ ΒΟΣΚΕΙΣ ΤΑ

THE BLACK CUBE OF
SATURN

AUSTRALIA

DENMARK

MANHATTAN

SANTA ANA

GLOBAL OCCULT WORSHIP

GlacierDogMapMe: Pantheon, Vatican, Washington DC - What Were They Thinking!?



Roman Pantheon Dome facing Obelisk

http://www.historum.com/members/labienus-albums-roman-civilization-picture193-roman-pantheon.jpg;



Vatican Dome facing Obelisk

http://www.raidersnewsupdate.com/leadstory70.htm



Above: Vatican City & Pantheon (red circles)

http://www.rome.info/map/



Washington DC Dome facing Obelisk

http://www.raidersnewsupdate.com/leadstory70.htm


NANO IMPLANTS PX67
THOUGHT
REACTION
HEARING
VISUAL
ACTIVATE
PARANOIA
FEAR
PAIN
CONFUSE
NAUSEA
MEMORY
PANIC
SLEEP
ATTACK
LETHARGY
SEXUAL
SUICIDE
I.D.
IDENTITY
CONFIRM
DANA PLESSON
OREGON κ 355 84 8439
ACTIVIST
Trouble-maker
Whistleblower
IAM849-76==174-9JH
DARPA
CONFINE
CONTROL
TORTURE
EXPELL
TERMINATE
HARASS
DISCIPLINE
DDees.com


LHCb
ATLAS
CERN Meyrin
PS 628 m
CERN Prévessin
SPS 7 km
SUISSE
FRANCE
ALICE
CMS
LHC 27 km

An overview of how the weapons are deployed by the Mind Control Police

Mass Remote Mind Control by Blanket Coverage of the Population which is achieved via the Mobile Phone Network


ECHELON - CITIZEN SPY BASE
U.S. National Security Agency
Menwith Hill
Yorkshire, England
GCHQ
General Communication HQ
M.O.D.
Ministry of Defence
MI5
Military Intelligence




HAVE YOU SEEN THESE TOWERS GOING UP?
THE SILENT WAR
Radio Frequency Radiation - Microwave Radiation

BLACK CUBE- AUSTRALIA

Manhattan, NYC



Kaba in Mecca

BLACK CUBE- DENMARK

Aple Store cube- NYC

"Rings going around SATURN"

Download from
Dreamstime.com
This watermarked comp image is for previewing purposes only.

ID 59211679

© Marinv | Dreamstime.com

Mu Radar
Arecibo
HAARP
HIPAS
EISCAT
Sura


EXTENDED DAY CREED
WATCH YOUR THOUGHTS THEY BECOME YOUR WORDS,
WATCH YOUR WORDS THEY BECOME YOUR FEELINGS,
WATCH YOUR FEELINGS THEY BECOME YOUR ACTIONS,
WATCH YOUR ACTIONS THEY BECOME YOUR HABITS,
WATCH YOUR HABITS THEY BECOME YOUR LIFESTYLE,
WATCH YOUR LIFESTYLE IT CONTROLS YOUR DESTINY.

05/07/2013 04:26 PM

UNITED STATES OF AMERICA
E PLURIBUS UNUM
ONE CENT
LB
JFK





The Trinity of Globalist Control

Vatican City

Religion

City of London

Finance

Washington D.C.

Military

**All three are separate states,
completely independent of their respective countries.**





THE GREATEST OPERATIVE MASON MEETS THE GREATEST SPECTULATIVE MASON is Ben Bey Emmanuel Mu Ali, historically known as Benjamin Banneker really Prince Hall? Benjamin Banneker (November 9, 1731 – October 9, 1806) was a free African American astronomer, mathematician, surveyor, almanac author and farmer. Prince Hall (c.1735 – December 4, 1807), Hall formed the African Grand Lodge of North America.



"Flammas eius, Lucifer, matutinus inventiat:"

His flame, Lucifer, dawning his own creation:



1. **Rainbows, Halos, Glories, Circumzenith Arcs, Sundogs, & other Atmospheric Optics**
2. **Libyan Desert Glass (LDG) mystery solved.**
3. **Tektite Origin solved.**
4. **Megacryometeor Origin solved**
5. **Birefringence** of glass found in LDG reveals reason for double suns, comet's tail splitting, quadruple rainbow displacement
6. **Ozone** - fresh scent after a thunderstorm connected to glass plate air ionizers
7. **Fusion Crust** formation on meteorites - burnt glass
8. **Colorizing** of clouds, moon, sun
9. **Greenhouse Effect**
10. **Karman Line** - said to be the division line between atmosphere and space lies at 100 km, same height as the glass
11. **UV Radiation block**
12. **Lightning** (created by dielectric forces moving laterally near glass
13. **Elves in Upper Atmospheric Lightning** (100km)
14. **Shortwave Radio Waves** scattering (100 km) Ionosphere compares to "sheet of glass"
15. **Operation Fishbowl - Starfish Prime** - mission to blow a hole in the glass for space entry/exit
16. **Superior Mirages/Fata Morganas** - Refraction of Glass Sky creates "horizonal" crease
17. **Meteor Showers / Iridium Flares** - space particles skidding off glass sky and returning up into inner-space orbit
18. **Red Shift**- all stellar spectroscopy is debunked due to scientists ignoring chromatic aberration of stars caused by the glass
19. **Aberration of Light (Stellar Aberration)** - Glass sky creates slight apparent displacement of stars due to refraction
20. **Space Vehicles Heatshields** - flush surface, high temperature resistant material use to melt through glass
21. **Crookes Dark Space** - Negative charged ions create "dark space" around glass sky to make it invisible
22. **Auroras** - 100 km - Electrons from the sun hit the charged glass sky causing fluorescent glow/striations

EXIT THE MATRIX OF DECEPTION! LORD STEVEN CHRIST

WWW.MISSTERIBABYLONESTAR.COM

SUMERIAN DEPICTIONS OF ANUNNAKI GODS FLYING IN "WHIRLWINDS"



SIZE & SCALE

Of the object known as "Alien spaceship" Photographed at the Moon Luna 17S 117.5E

0
5
10
15
20
25
30
3,370 Meters
500 m
0
Queen Mary II - 345 Meters
Eiffel tower - 324 Meters

Size configuration by Salvatore Valentin Carta, from Argentina

Scale & graphic design by Rami Bar Ilan © 2007



By Mohamed Ibrahim



A vimana depicted in a temple relief at Ellora Caves, India.



Travel to Eat
Kurt Buzard





A possible physical artefact from our distant past shows a modern crop picture from 1991



Grasdorf, Germany 1991



buried golden plate


35cm
DUPLICATION
thehiddenrecords.com
DUPLICATED
SUMERIAN
SCROLL SEAL
AO 22347
LOUVRE PARIS







© www.SandInMySuitcase.com





Battery-powered searchlights and filament lamps in the crypts of the Temple of Hathor (Isis) at Denderah











1. THIS IS A CHEMTRAIL

2. THESE ARE THREE SYLPHS, WHO ARE THE SPIRIT ELEMENTALS, CLEANING UP THE SKY.

3. APPROXIMATELY 1 HOUR AFTER YOU SEE THE SYLPHS ATTACH THE CHEMTRAILS, THERE WLL BE CLEAR BLUE SKY.

MORE RESEARCH; SYLPHS AND CLOUDSHIPS

WWW.INDIANINTHEMACHINE.COM

Grandidier's Baobab

Dragon Blood Tree

Jacaranda






PLEIADES
CRESCENT
SUN
7 RAYS
7 ORBS
ANCESTOR
7 ORBS
SUN-LIKE STAR
CRESCENT EXOPLANET

MAYA

COSMIC CONDUIT OPENING 'LILY' FROM EXOPLANET NEAR PLEIADES

PROPOSED BY WAYNE HERSCHEL © 2014 thehiddenrecords.com







HAARP Ionospheric Research Facility

(8 Miles North of Gakona, Alaska)

ALIEN SPACESHIP ON THE MOON

HOW BIG IS IT?


Rami © 2007
WWW.RAMISTRIP.COM

General impression of size & scale - Object around urban structures of Manhattan & Toronto





© 2013 boyd currey / bokeh.net.au

gettyimages
Kenneth Garrett
174405620



Copyright Kenneth Garrett





© [illegible] palarczyk

TALKS WITH TEACHINGS FROM MY COSMIC FRIENDS

ASHTAR SHERAN
ORTHON
angels-heaven.org
Pic. 4395 P EN

MEGADETH

PLATE 14



SETHOS WORSHIPS AND OFFERS NATRON TO OSIRIS

© Humboldt State University Library





Meet The Iargans!



Typical Iargan

Iargan gets into photo without being seen at the time photo was taken!



Iargan society and transportation infrastructure of housing units



Another view and close up of cylinder which houses 10 people each!



From Inside The Control Room



The blue print of a Sun wheel which holds 10,000 people as well

(C)copyright 2003 Yuichiro Shishido





By Mohamed Ibrahim

By Mohamed Ibrahim

By Mohamed Ibrahim

By Mohamed Ibrahim

By Mohamed Ibrahim

By Mohamed Ibrahim
4:46













© Getty Images

© mick palarczyk



© mick [illegible]k



© mick [illegible]czyk



palarczyk

© michealarczyk

© paul smit



© mick palarczyk

©www.imagesofanthropology.com



© mick palarczyk



© mick palarczyk







© [illegible] palarczyk





© mick palarczyk





Battery-powered searchlights and filament lamps in the crypts of the Temple of Hathor (Isis) at Denderah







NATIONAL PARK SERVICE
PETRIFIED FOREST
NATIONAL PARK
UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE



United States Patent [19]

Berley

[11] **4,410,805**

[45] **Oct. 18, 1983**

[54] **RADIOMETER GENERATOR**

[76] Inventor: **Lawrence F. Berley**, 19 Chipmunk La., Media, Pa. 19063

[21] Appl. No.: **918,772**

[22] Filed: **Jun. 26, 1978**

[51] **Int. Cl.**^{3} **F03G 7/00**

[52] **U.S. Cl.** .... **290/1 R**; 356/216

[58] **Field of Search** .... 356/213, 216; 290/1 R; 60/641; 310/306; 73/355 R; 350/1.1; 250/215

[56] **References Cited**

U.S. PATENT DOCUMENTS

1,000,831	8/1911	Martin	356/216
2,004,392	6/1935	Rah	356/216 X
3,348,374	10/1967	Schalkowsky	310/306
4,146,407	3/1979	Litsenko et al.	136/89 PC

FOREIGN PATENT DOCUMENTS

Ad.10769	of 1890	United Kingdom	356/216
1395137	5/1975	United Kingdom	250/215

OTHER PUBLICATIONS

Series of papers published in the Philosophical Transactions of the Royal Society of London (1873–1881), par. 452.

"Radiant Matter", A Resume of the Principal Lectures and Papers by Prof. William Crookes on the Fourth State of Matter, published by James W. Queen & Co., No. 924, Chestnut Street, Philadelphia, Pa., pp. 6-9.

Primary Examiner—J. V. Truhe
Assistant Examiner—W. E. Duncanson, Jr.
Attorney, Agent, or Firm—John F. A. Earley

[57] **ABSTRACT**

A self-contained system embodying the principles of the radiometer, the otheoscope, and the dynamoelectric machine is provided to derive an output of electrical energy from an input of radiant energy, and in particular infra-red energy, from the surrounding environment, and for amplifying that output. The system is suitable for airborne and space as well as terrestrial applications.

27 Claims, 34 Drawing Figures



18
16
22
23
14
12

FIG. 3.

FIG. 4.


38
10
36
46
44
40
24
26
42
18
20
16
22
23
14
12
48
52
50
30
32
34
28

FIG. 1.


18
22
23
14
12

FIG. 2.


54
68
62
66
56
60
64
58

FIG. 5.


72
76
70
78
74
60
58

FIG. 6.


72
76
80
82
84
60
58

FIG. 7.


72
76
86
90
88
60
58

FIG. 8.


96
76
72
94
60
58

FIG. 9.


76
72
98
100
104
102
60
58

FIG. 10.


106
112
108
110
58

FIG. 11.

FIG. 12.


114
18
20
22
23
14
12
116

FIG. 13.


114
120
118
120
18
20
22
23
14
12
122
130


132
134
136
122
138
130
124
128
140
126

FIG. 14.


142
162
164
158
150
162
160
154
157
146
174
168
155
148
172
144
170
170
152
156

FIG. 15.


157
160
164
162
154
168
144
174
156
155

FIG. 16.


162
154
174
170
168

FIG. 17.



FIG. 18



FIG. 19.



FIG. 20.



FIG. 21.



FIG. 22.



FIG. 23.



FIG. 24.



FIG. 25.



FIG. 26.


176
194
180
198
190
198
198
184
188
201
200
186
192
182
200
178
196

FIG. 27.


202
206
218
208
204
220
224 226
212
−
222
228
207
+
230
210

FIG. 28.


204
214
207
+
216
206
−

FIG. 29.


+
-

FIG. 30.


+
-

FIG. 31.


232
298
290
292
254
296
288
300
294

FIG. 32.


232
304
314
302
254
306
+
308
316
312
310

FIG. 33.


318
332
334
338
326
328
336
+
326
-
324
330
320
322

FIG. 34.

RADIOMETER GENERATOR

BACKGROUND OF THE INVENTION

1. Field of the Invention

The invention relates to a self-contained system for utilizing environmentally available radiant energy, specifically infra-red energy, to provide a new source of electrical energy.

2. Description of the Prior Art

Many proposals have been made in the prior art for the conversion of environmentally available radiant energy directly into electrical energy. Specifically, it has been proposed to use the thermoelectric, piezoelectric, and photovoltaic effects for this purpose. Typical U.S. patents showing such generators are U.S. Pat. Nos. 3,757,146 granted Sept. 4, 1973, 3,198,969 granted Aug. 3, 1965, and 3,296,469 granted Jan. 3, 1967. While the underlying principles of such generators have been known for many years, attempts at the utilization of these principles have been beset with problems that have impeded the development of such generators as practical sources of electrical power.

Other proposals for the conversion of infra-red energy into electrical energy have utilized the principle of the decrease in magnetism of bodies, particularly iron and certain other metals, alloys and their compositions as their temperature is increased. Generators embodying this principle are disclosed in U.S. Pat. Nos. 476,093, granted June 14, 1892 and 2,016,100 granted Oct. 1, 1935. Here, again, notwithstanding the apparent potential of such generators, the art has been unable to develop the technology as a practical electrical energy source. Among the problems involved with such generators is the complex and consequently expensive magnetic field structure that is required.

a phenomenon that has long been known as providing an output of kinetic energy from an input of radiant energy is the radiometer. The radiometer is an instrument that was devised by Sir William Crookes to measure the intensity of incident radiation. It operates on the principle that a body delicately suspended in a vacuum is apparently repelled by radiation. The instrument, in a commonly known form, includes a system of four spaced light-weight vanes of poor heat conductivity which are blackened on one side, the other side being bright, and so suspended in a highly exhausted bulb that they are free to rotate about a common vertical axis with the black surfaces all facing in the same direction. Incident radiation from the sun or an adjacent warm body is absorbed and emitted by the black surfaces of the vanes more than the bright surfaces, and as a result, gas molecules near the black surfaces are energized and press more on the black than the bright surfaces causing the vanes to rotate about their axis. The more intense the incident radiation, the more rapid is the rate of rotation. Actually, an outside source of lower temperature such as ice, dry ice, evaporating ether, or other cold material will draw radiant energy from the molecules causing them to move in the direction of the cold material, also driving the vanes. The container enclosing the vanes is necessary to maintain the high vacuum and to provide a barrier to rebound activated molecules back to the vanes, driving them further.

The radiometer is described in a series of papers that were published in the Philosophical Transactions of the Royal Society of London (1873–1881). Reference is made particularly to Paragraphs 145–148. The publication entitled "'RADIANT MATTER', A Resume of the Principal Lectures and Papers by Prof. William Crookes on the Fourth State of Matter", published by James W. Queen & Co., No. 924 Chestnut Street, Philadelphia Pennsylvania also is concerned with the phenomenon.

In another form of radiation responsive instrument which he called the otheoscope and that is described also in the aforementioned Philosophical Transactions, particularly in Paragraphs 450–454, Crookes provided a larger radiant energy absorbing and emitting surface consisting of a large stationary plate of good heat conductivity having a blackened surface. Thus, in the otheoscope the surface that generates the molecular disturbance is not the one that rotates. The blackened surface of the plate, however, is placed close to the movable vanes. Because of the larger surface area and closer proximity, the blackened stationary plate activates a greater number of molecules and directs them more accurately to the movable vanes resulting in a greater speed or rotation than is achievable by the radiometer with the same intensity of incident radiation. Another advantage of the otheoscope is that an enclosure is not necessary when a vacuum such as outer space is already present. The small space between the stationary blackened surface and movable vanes provide a rebounding space within which molecular rebound can occur and rebound off a container wall is not necessary to provide the moving force of the vanes. Another form of the otheoscope involved a stationary blackened disc above which light-weight blades radiating from a common center were positioned giving the appearance of a turbine.

Although the inventions of the radiometer and the otheoscope were made more than a hundred years ago, the only use proposed heretofore for the instruments and their inherent property of converting radiant energy into kinetic energy has been the measurement of the intensity of radiation falling upon them. That this available kinetic energy might be utilized to provide a useful electrical energy source has gone unnoticed. This notwithstanding the need for new energy sources and the intensive search for such new energy sources that has long been underway. Significant in this connection is the highly developed technology that has been available for the effective utilization of such kinetic energy, specifically the production of an output of electrical energy by the mechanical relative rotative motion of the magnetic field and the electrical conductors of the dynamoelectric machine.

SUMMARY OF THE INVENTION

An object of the invention is to bring together in a self-contained system apparatus embodying the principles of the radiometer, the otheoscope, and the dynamoelectric machine thereby to derive, as a new source of energy, an output of electrical energy from the dynamoelectric machine directly from an input of radiant energy to the system from the surrounding environment.

Another object of the invention is to provide such a self-contained system that is characterized by lightweight, thereby rendering it suitable for airborne and space as well as terrestrial applications.

A further object of the invention is to include in combination with such an electrical generating system a voltage amplifying device such as an induction coil.

A further object of the invention is to provide a series of such electrical generating systems each including a voltage amplifying device the output of which is utilized to provide a driving force for the succeeding stage.

Another object of the invention is to include in combination with such an electrical generating system and amplifying device self-contained photon-emitting devices, for example, solid materials such as gemstones and specially enclosed liquids and gases thereby to provide a self-contained photon-emitting device.

Still another object of the invention is to provide in a self-contained system, combination and cluster arrangements of such electrical generating systems and amplifying devices thereby to increase the electrical power output.

In accomplishing the foregoing objects and other objectives of the present invention, there are provided selfcontained radiometer and otheoscope generating systems for generating electrical energy from impinging or incident external environmental sources of radiant energy such as heat from the sun or any source of infrared radiant energy such as a heat pipe attached to a solar energy heat collector, an atomic pile, an airplane engine, or in general from heat derived in way from space, the air, land or water. The system will function as well if it is giving up radiant energy to a source much colder than it such as ice, dry ice, liquid nitrogen or evaporating fluids.

The system, in its specific aspects, includes an energy source such as a heat pipe, means for concentrating and directing the energy from the heat pipe including a collimator for directing and making parallel the rays of radiant energy to a fresnel lens and thereby to a radiant energy absorbing/emitting surface. There is also provided a parabolic, hyperbolic, or elliptical mirror for the further reflection of rays of radiant energy and then focusing them on the absorbing/emitting surface. The system further includes a dynamoelectric machine and torque converter which cooperates with the absorbing/emitting surface and nearby molecules to drive the dynamoelectric machine. Thus the incident radiant energy on the absorbing/emitting surface is converted to kinetic molecular energy and then to kinetic mechanical energy, specifically a moment to produce the relative rotative motion of the magnetic field and electrical conductors of the dynamoelectric machine. The dynamoelectric machine may comprise a machine of either the direct or alternating current generating type. The rotative moment at the output of the torque converter provides in cooperation with the dynamoelectric machine a capability for high electrical energy output in the form of high voltage or high electrical current. The system of the present invention is distinguished in this important respect from the prior art.

In accordance with one form of the invention, the radiant energy absorbing/emitting surface, torque converter and dynamoelectric machine are suitably mounted in a highly evacuated container. The collimator, fresnel lens and mirror may be located external of the container. The electrical output produced by the system may be employed to energize electrical components that may be located internally or externally of the container, as desired, or if desired, stored in batteries for future use. When utilized in outer space, the container may be omitted since no special provision is then required to provide the evacuated internal environment of the system. In this latter use, structures employing the principles of the otheoscope would be most effective, the close disposition of the stationary blackened surface and movable vanes providing the necessary space within which molecular rebound can occur. That is to say, a container wall is not necessary to provide the moving force of the vanes, as in the radiometer.

In another aspect of the invention advantage is taken of a special property of the highly evacuated internal environment of the system that solid materials such as gemstones, and specially enclosed liquids and gases, in such an environment may be caused to emit photons by virtue of the interaction of high-energy molecules and a spanning high voltage electrical field, thus providing a self-contained photon-emitting device. Such a device emits light rays useful as a beacon or for lighting living areas as a long term lamp that need not be turned off.

BRIEF DESCRIPTION OF THE DRAWINGS

FIG. **1** is a perspective view of an embodiment of the system of the present invention utilizing an otheoscopic generator;

FIG. **2** is a side elevation illustrating the radiation absorber/emitter, the torque converter, and dynamoelectric machine of FIG. **1**;

FIG. **3** is an exploded perspective view of the apparatus of FIG. **2**;

FIG. **4** is a side elevation illustrating the action of heated molecules emitted from the radiation absorber/emitter on a vane of the torque converter after absorption of radiant energy by the absorber/emitter;

FIG. **5** is a perspective view illustrating another form of otheoscopic generator that may be employed in the system of FIG. **1**;

FIGS. **6** through **11** are perspective views illustrating different forms of radiometer generators that may be employed in the system of FIG. **1**;

FIG. **12** is a perspective view illustrating a battery charging system according to the present invention;

FIG. **13** is a perspective view of a self-contained photon-emitting system according to the present invention;

FIG. **14** is a wiring diagram illustrating a typical form of induction coil that may be used in the system of FIG. **13**;

FIG. **15** is a perspective view illustrating another embodiment of the system of the present invention utilizing a dual otheoscopic generator and having particular application in outer space.

FIGS. **16** and **17** show top plan and side elevational views, respectively, of the system of FIG. **15**;

FIGS. **18** through **25** illustrate top plan views of combination and cluster arrangements of the system of FIG. **15**;

FIG. **26** illustrates a perspective view of a cluster arrangement of the basic FIG. **15** system;

FIG. **27** illustrates an embodiment of a dual radiometer generator for outerspace use that is enclosed in a glass or other heat conducting container;

FIG. **28** illustrates an embodiment of the radiometer generator and induction coil as a power amplifier;

FIG. **29** shows a diode rectifier circuit for use with the apparatus embodiment of FIG. **28**;

FIG. **30** illustrates an embodiment linking dual otheoscopic generator power amplifiers into a chain thereby providing increasingly more powerful generators;

FIG. **31** illustrates another embodiment of a power amplification system using dual otheoscopic and also radiometric forms of generators in outer space;

FIG. 32 illustrates an embodiment of the invention employed as a lighthouse in outer space;

FIG. 33 illustrates an embodiment of the invention employed as a propulsive mechanism in outer space; and

FIG. 34 illustrates an embodiment of the invention for providing a source of coherent light.

DESCRIPTION OF THE PREFERRED EMBODIMENT

THE EMBODIMENTS OF FIGS. 1-11

Referring now to the drawings, and in particular to FIG. 1, there is shown an otheoscopic generator comprising a self-contained system indicated at 10. This system requires no external power for its operation, other than environmental incident radiation, for converting such incident radiation into useful electrical energy and other desired forms of radiant energy. The system includes a dynamoelectric machine or generator 12 having a drive shaft 14. The output electrical current from the generator 12 can be alternating or direct, as desired. In FIG. 1, the generator 12 is shown as a miniature direct current generator having minimal inertial turning resistance of the shaft, minimum armature resistance, and an output voltage of 1.8 volts per 1000 RPM. A permanent magnet not shown provides an internal magnetic field. Where subsidiary current to maintain an internal magnetic field is required, a suitable additional otheoscopic generator of the type herein illustrated in FIG. 1 would be added to provide such current.

The system of FIG. 1 further includes a torque converter indicated at 16 comprising a light-weight circular aluminum fan having a bank or plurality of light-weight vanes 18 each approximately 1/32" thick radiating from a center disc 20 attached perpendicularly to the vertically positioned drive shaft 14 of generator 12, as for example, with epoxy glue.

A radiant energy absorber/emitter surface indicated generally by the reference numeral 22 may consist of lampblack painted on the upper side or surface of a plate 23 facing the torque converter 16. The plate 23 preferably is made of a good heat conductor such as silver, gold, copper or aluminum. A desired property of the blackened surface is high absorbancy and emission of infra-red radiant energy. Material other than lampblack may be employed to provide the desired high absorbant black surface 22 for the plate 23, as is known in the art.

The generator 12, torque converter 16 and plate 23 with its absorber/emitter surface 22 are positioned within a Bell jar 24, being suitably mounted therein. The internal environment 26 of the Bell jar 24 consists of molecules representative, for example, of normal sea level air or other gas mixtures by design evacuated to a high vacuum of 15 to 100 microns of mercury pressure. (Note that at 1 micron of mercury pressure there are still 400 billion molecules per cubic centimeter of vacuum space.) To this end, in FIG. 1, there is provided a vacuum pump 28 that is attached to the Bell jar 24 by way of a suitable platform or base plate 30 on which the Bell jar 24 is mounted, and also by way of a vacuum hose 32 and high vacuum stop cock 34.

The environment external of the Bell jar 24 is the normal sea level air for the region in which the Bell jar 24 is located under the influence of various climatological and geophysical factors such as temperature, humidity, pressure, gravitational, electrical, and magnetic field gradients. This environment contains many natural sources of radiant energy indicated generally at 38, including the sun. The energy source 38 chosen for purposes of illustration in FIG. 1 is a 12" heat pipe 40 that is arranged to transfer heat energy from heated water stored in an insulated container indicated at 42. The environment shown also includes a short collimator 44 that is provided to direct and make parallel the rays of radiant energy from the close source of radiant energy, the heat pipe 40. The collimator 44 directs the radiant energy to a fresnel lens 46 having plane dimensions of approximately 12" on a side and $\frac{1}{8}$" thick. The fresnel lens 46 concentrates the radiant energy as it is directed toward the absorber/emitter surface 22 and focuses the energy thereon. A parabolic mirror 48 provided on the other side of the Bell jar 24 also reflects radiant energy impinging upon it from the source 40 and focuses it directly on the absorber/emitter surface 22. Hyperbolic or elliptical mirrors may also be employed.

In FIG. 1 a suitable electrical meter 50 connected to the output of the generator 12 provides a measure of the output of the generator 12. This output is in the form of a voltage or amperage, as desired. Additionally, a penlight lamp 52, rated at 5 volts and 60 microamperes, is shown as being energized by the output from the generator 12.

As those skilled in the art will understand, the absorber/emitter surface 22 and torque converter 16 provide in combination with the generator 12 a capability, in an installation in outer space, for substantial electrical energy output in the form of voltage or electrical current depending upon the electrical design parameters of the generator 12. Thus, while in FIGS. 1-3 the generator 12 is described as a miniature direct current generator, this is because of physical limitations imposed by housing the structure of the absorber/emitter surface 22 and torque converter 16 within the Bell jar 24. If housed in a larger container and thus freed of its physical constraints, or located in outer space wherein no housing or container would be required to provide the evacuated space, the torque converter 16, vanes 18 and absorber/emitter surface 22 may be made of such size as to provide a substantially larger turning moment on the center disc 20. In this case the absorber/emitter surface 22 would be separate but close to vanes 18 and center disc 20. Accordingly, the drive shaft 14 and generator 12 may then be increased proportionately in size to provide a correspondingly enhanced output of electrical energy.

The otheoscopic torque converter of FIGS. 1 through 4 is characterized in that the vanes 18 may be transparent so as to allow a substantially unimpeded impingement of radiation on the surface 22 of plate 23 and is further characterized in that the surface 22 that generates the molecular activity in response to incident radiation is stationary, and therefore, is not restricted as to material, weight, shape, size and area of surface. Accordingly, the most suitable heat conducting material and the most efficient size, shape, weight and means of support for the plate 23 can be employed to the end of utilizing the incident radiation to best advantage. The vanes 18 of the torque converter 16, moreover, can be located very close to the surface 22, preferably within a millimeter or two, and the angular position of the vanes 18 with respect to the surface so chosen as to take the most efficient mechanical advantage of the radiation produced "molecular wind", as it was termed by Crookes, and as illustrated by way of example in FIG. 4.

In FIGS. **1** through **3** the stationary plate **23** on which surface **22** is provided is shown as supported on vertical ports that rest on the base plate **30**, and the vanes **18** of the torque converter **16** are disposed in a fan shaped configuration close to the surface **22**, each vane presenting itself to that surface as illustrated in FIG. **4**.

Another form of otheoscopic torque converter that may be employed in the system of FIG. **1** is illustrated in FIG. **5** wherein the surface that generates the molecular activity in response to incident radiation, indicated at **54**, is provided on a metal sheet or plate **56** that is curved to provide a semi-circular cylindrical portion having as its axis the shaft of a dynamoelectric machine or generator **58** having a vertically positioned drive shaft **60**. Generator **58** and shaft **60** may be identical to the generator **12** and shaft **14**, respectively, of FIGS. **1** through **3**.

The arrangement of FIG. **5** further includes a torque converter indicated at **62** comprising four light-weight, transparent diamond-shaped vanes **64** each approximately 1/32" thick, that are attached to the end of a respectively associated rod **66**. The rods **66** radiate from a center disc **68** that is attached perpendicularly to the end of drive shaft **60** in any suitable manner. Each vane **64**, as shown, is vertically positioned on the end of its associated rod **66**, being disposed at an angle displaced from normal with respect thereto, and in each revolution about the axis of shaft **60**, passes close, within a millimeter or two, to the molecular generating surface **54**. The angle of each vane **64** with respect to surface **54** is similar to that between vane **18** and surface **22**, as illustrated in FIG. **4**, and thus molecular activity at the surface **54** produces a moment that causes the vane **64** to move with respect to the surface **54**, thus producing rotation of shaft **60**. The direction of rotation of the shaft **60** depends upon the direction from normal of the angle of the vane **64** with respect to its supporting radial rod **66**, the angle preferably being the same for each of the vanes **64**.

If employed in an environment such as outer space where vacuum conditions exist naturally, it is not necessary to enclose the otheoscopic torque converter **62** within an evacuated container such as Bell jar **24** of FIG. **1**. When not so employed, the converter **62** would be positioned in an environment such as that provided by Bell jar **24** with the generator **58** and the curved plate **56** suitably supported on the base plate **30**.

FIGS. **6** through **11** illustrate alternative radiometric forms of torque converters that may be employed in place of the otheoscopic torque converter in the system of FIG. **1**. The radiometer generators of FIGS. **6** through **11** differ significantly from the otheoscopic torque converter in that the absorber/emitter surface is embodied on the moving members or vanes of the generator instead of on the stationary member, and differs further, as will become apparent, in the requirement for an enclosing wall of the evacuated space to be close to the path of the moving vanes. That is to say, where the absorber/emitter surface is on the moving vanes of the torque converter, an enclosure or wall of the evacuated space must be placed close to the vanes for the latter to be driven when exposed to radiant energy. As noted in connection with the otheoscopic torque converter of FIG. **1**, when the absorber/emitter is provided on a surface separate from the movable vanes, the vanes need not have any lampblack coating.

Each of the apparatus embodiments of FIGS. **6** through **11** includes a glass container within which the moving vane system and dynamoelectric machine are placed, which container, in turn, would be placed inside a Bell jar such as the Bell jar **24** of FIG. **1** and evacuated, also, together with the bell jar.

As illustrated, the torque converter **70** of FIG. **6** is enclosed in a glass container **72** and includes four lightweight vanes **74** each approximately 1/32" thick radiating from a center disc **76** attached perpendicularly to a vertically positioned drive shaft **60** of a generator **58** that may be identical to the correspondingly numbered components of FIG. **5**. One side **78** of each of the vanes **74** is blackened, as with lampblack, the black surfaces all facing in the same direction around the torque converter. The other sides of the vanes are bright. Preferably the material of which the vanes **74** of FIG. **6** are made, and the vanes of the torque converters described in connection with FIGS. **7** through **11** are made, is a poor heat conductor to the end that the high absorbance of infra-red radiant energy on the black side has little or no effect on the temperature of the bright side.

Radiant energy, and in particular, infra-red energy is differentially absorbed and emitted by the blackened surfaces of the torque converter vanes imparting kinetic energy to adjacent gas molecules. The lack of a similar energy exchange between the obverse bright surface and its adjacent gas molecules results in a pressure differential whereby the more energetic gas molecules close to the blackened surface of the vanes give rise to a resultant driving force turning or rotating the center disc **76**.

FIG. **7** illustrates a torque converter **80** that is similar to that of FIG. **6**, but includes vanes that consist of semicircular metal foils, as indicated at **82**. The foils **82** are each blackened on one side indicated at **84**, the blackened sides all facing the same direction as in torque converter **70** of FIG. **6** and also in the torque converters illustrated in FIGS. **8** through **10**.

The vanes of the torque converter **86** of FIG. **8** consists of hemispheric cups **88** each of which is blackened on the inside indicated at **90**, all facing the same direction.

The vanes of the torque converter **92** of FIG. **9** comprise hemispheric cups indicated at **94**. Each cup **94** is provided with a blackened screen **96** that covers the outer half of each cup **94**.

The FIG. **10** form of torque converter **98** is a "turbine" form and includes elliptically shaped vanes or plates **100** that present a substantially circular outline in the primary direction of the radiation source. The plates **100** are blackened on the outer faces indicated at **102**, and are oriented at 45° from the vertical, and also from the rods **104** on the ends of which plates **100** are mounted. The apparatus embodiment of FIG. **10** allows for continuous exposure of the absorber/emitter surfaces **102** of the vanes **100** to incident light and does not require the spacing of the vanes illustrated in connection with the apparatus embodiments of FIGS. **6** through **9**.

The torque converter **106** of FIG. **11** includes a single elongated vane **108** of spiral form that is exposed to incident radiant energy emanating from almost any direction. In FIG. **11**, generator **58** is provided with an elongated shaft **110** to the remote end of which one end of of vane **108** is attached, the other end of the spiral of vane **108** being connected to the shaft **110** adjacent the generator **58**. As illustrated, the glass container, indicated at **112**, for torque converter **106**, is elongated and shaped to conform to the general outline of the spiral vane **108**.

THE EMBODIMENTS OF FIGS. 12 THROUGH 14

In FIG. **12** there is illustrated another embodiment of the invention in which a glass container **114** that may be similar in size to an ordinary household light bulb is employed, and which embodies the otheoscopic form of torque converter illustrated in FIG. **1**. The glass container **114** is hermetically sealed after placement of the generator system therein and evacuation of the internal environment to 1 to 100 microns of mercury pressure (preferably one micron). The output terminals of generator **12**, in FIG. **12**, are shown connected to an electrical storage device or battery **116** for charging the latter, the electrical charge stored in battery **116** being available for later use.

FIG. **13** illustrates a further embodiment of the invention employing a container **114** of FIG. **12** and the otheoscopic form of torque converter of FIG. **1** wherein a gemstone **118** is positioned between two spaced plate electrodes **120**. The electrodes **120** are connected to the high voltage output of an induction coil indicated at **122** and actuated by the output of the generator **12**.

A typical electrical circuit for the induction coil **122** of FIG. **13** is illustrated in FIG. **14**. As shown, the induction coil **122** includes a primary winding **124**, consisting of only a few turns, wound on an iron core **126**. A secondary winding **128**, wound over the primary winding, consists of a large number of turns. The primary winding **124** is connected to the output terminals **130** of the generator **12** in series with an electrical capacitor **132**. An electrical switch **134** actuated by an armature **136** is connected across the capacitor **132**. The armature **136** is positioned in cooperative relation with the iron core **126**, being normally biased in upward direction to close the switch but is attracted by the iron core **126**, upon magnetization of the latter, to open the switch **134** and thereby break the circuit to primary coil **124**. As a result the armature **136** is returned to its initial position by a spring, not shown, and closes switch **134**, again restoring the circuit to the primary coil. The cycle is rapidly repeated.

In the operation of the induction coil, the flow of electrical current in the primary winding **124** produces a magnetic field in the iron core **126**. Opening of switch **134** results in a collapse of the magnetic field that induces a high voltage in the secondary winding **128**. The capacitor **132** is placed across the switch **134** to reduce the voltage across the switch as it is opened to minimize sparking.

The output terminals **138** and **140** of the secondary winding are each connected electrically to one of the electrodes **120**. Hence, there is established between the electrodes **120** an electrical field in accordance with the A.C. high voltage output of the induction coil **122**. The gemstone **118**, although a solid material, has the property of emitting photons in the environment described and thus provides a self-contained photon-emitting device.

THE EMBODIMENT OF FIGS. 15 THROUGH 26

When positioned in outer space, it is noted that unless the generator **12** is mounted on a stable platform **30** that is able to resist the turning or rotative moment resulting from radiation impinging on the absorber/emitter surface **22**, there is a tendency for the rotative moment to be applied to the generator **12** itself as well as to the drive shaft **14** thereof. Consequently, after a time the absorber/emitter surface **22**, torque converter **16**, drive shaft **14** and generator **12** will all effectively be rotating as a unit. As a result, there will first be a depletion and then, after a time, no generation at all of electrical power. This undesirable situation may be corrected, as indicated, by mounting the generator **12** on a stable platform that effectively resists such turning or rotative moments, and hence, holds the body of generator **12** stationary with respect to the relatively rotating shaft **14**, torque converter **16** and absorber/emitter surface **22**. In outer space, when the blackened absorber/emitter surface remains part of the system of movable vanes **18**, an enclosure or shroud must be provided to return high energy molecules to further drive the vanes **18** in a rotary motion. Such an enclosure is not required with the otheoscopic form of generator in which the absorber/emitter surface is part of the stationary system.

The embodiment of the invention illustrated in the perspective view of FIG. **15** and in top and side views, respectively, of FIGS. **16** and **17**, shows another way in which to arrange a radiation generator system so as to avoid the need for a platform to hold the body of the generator stable with respect to the associated drive shaft torque converter and absorber/emitter. The radiation generator system **142** of FIG. **15** includes a dynamoelectric machine or generator **144** having a pair of drive shafts **146** and **148**, a pair of torque converters **150** and **152**, and a pair of absorber/emitter surfaces **154** and **156**.

The generator **144** can provide an output of alternating or direct current as desired. Desirably, in the apparatus embodiment of FIG. **15**, the generator **144** comprises two separate generators, each having its own rotatable armature, the magnetic field sections thereof being fastened together and arranged within and fastened to the same external, common casing. The drive shaft **146** is attached to the rotatable armature of one generator. The drive shaft **148** is attached to the rotatable armature of the other generator, being axially in alighnment with the drive shaft **146**. The common casing of the generators is supported by brace members indicated at **155** and **157**, between the ends of a curved absorber/emitter surface **158**, at the center of curvature thereof.

The torque converter, indicated at **150**, comprises a plurality of vanes **160** extending from the ends of rods **162** radiating from a center disc **164** that is attached perpendicularly to the end of drive shaft **146** in any suitable manner. The vanes **160**, as shown, are positioned parallel to the shaft **146** and are so arranged as to have an edge pass close, within a millimeter or two, in each revolution about shaft **146**, to the curved absorber/emitter surface **158** that may be similar to the surface **54** of FIG. **5**. The angle of each vane **160** with surface **158** in such that molecular disturbance at the surface **158** produces a turning on the drive shaft **146**, in the counter-clockwise direction, for example. Additionally, one side of each vane **160** is blacked to provide absorber/emitter surface **154**. This provides a supplemental turning movement in the counterclockwise direction on the drive shaft **146**.

Similarly, the torque converter, indicated at **152**, comprises a plurality of vanes **168** extending parallel to drive shaft **148** from the ends of rods **170**. The rods **170** radiate from a center disc **172** that is attached, in any suitable manner, perpendicularly to the end of drive shaft **148**. The vanes **168** are positioned parallel to drive shaft **148** and arranged to have an edge pass close, within a millimeter or two, to the curved absorber/emitter surface **158**. The angle presented by each of the vanes **168** to the surface **158**, however, is opposite to that of the vanes **160** of the upper torque converter **150**, whereby incident radiation tends to produce clockwise rotation of drive shaft **148**. Additionally, if desired, one side of each of the vanes **168** is blackened to supplement the turning moment of drive shaft **146**, the blackened sides being oppositely disposed with respect to blackened sides of vanes **160** of torque converter **150**.

With this construction, it is evident that any tendency of the rotative moment introduced by one of the torque converters **150** and **152** to rotate the common casing of dual generator **144** is offset or counterbalanced by the rotative moment on the generator casing by the other torque converter thereby providing a substantially balanced system.

The arrangement of FIG. **15** is further advantageous in that the generator **144** effectively comprises two separate generators the outputs of which may be combined whereby a correspondingly larger electrical output is obtained. The output of the generator **144** may be utilized, for example, to energize a device **174** suitably mounted on the body of the generator **144**, externally thereof, as indicated. The device **174** may comprise a lamp providing a beacon, for example, a microwave generator transmitting generated power to receiving antenna or earth, or a radio transmitter transmitting intelligence concerning space environmental factors sensed by detecting devices not shown but supported and electrically powered by the otheoscopic generator **142**. Alternatively, or in addition thereto, the electrical output of the generator **144** may be taken via suitable slip rings provided on the appropriate shaft **146** or **148**.

Another way in which the radiation generating system of FIG. **15** may be arranged so as to be balanced, thereby avoiding the depletion, after a time, of generation of electrical power is to employ but a single generator **144** having two drive shafts **146** and **148** that are axially aligned but extend in opposite directions. With this structure the brace members **155** and **157** for supporting the generator **144** would be carried by a band (not shown) encircling the casing of the generator and disposed, for example, in a groove to preclude vertical displacement but to allow rotation of the casing of the generator relatively to the band and the brace members. One drive shaft **146** of the generator **144** would serve, for example, as the drive shaft **146** of upper torque converter **150** and would be attached to the rotatable armature of the generator. The other drive shaft **148** would be attached to the lower torque converter **152** and also to the body or casing of the generator **144**. It is evident that since the turning moments on the two shafts would be in opposite directions that the system would be balanced and would continue to provide an electrical output irrespective of whether one turning moment were greater than the other. The electrical outputs of the two generators could be connected in parallel or series, as desired.

In accordance with the invention, it is contemplated that otheoscopic generating systems of the kind illustrated in FIGS. **15** through **17** may be arranged in groups or clusters to increase the electrical power output. Thus, FIGS. **18** through **25** illustrate top plan views of combinations of whole system units, from two to nine, each of which may be identical to the structure of FIG. **15**, except for the inclusion on each system unit of a device **174**. FIG. **26** shows a perspective view of constructions linking four whole system units into chains. Other numbers of whole system units may be provided, the chains may be of any length for outer space use. If desired, such chains may be deployed in a star configuration thereby providing desired structural strength as well as contributing to a further increase in electrical power output.

As illustrated in FIG. **26**, it is contemplated that the curved absorber/emitter surfaces would extend, suitably supported, the entire length of each chain. Additionally, more than one set of vanes **160** may be associated with each drive shaft **146** and more than one set of vanes **168** may be associated with the drive shaft **148**. With this arrangement, there is made available a significant increase in the energy for driving each of the generators making up the dual generator **144**. It will further be understood that the kinetic energy outputs of the entire four and if desired, five or more whole system chains that could be provided, may be utilized in parallel, by the provision of suitable gearing, to provide an even more powerful total output.

FIG. **27** illustrates an embodiment of the radiometer generator system of the present invention for outer space use. This system is enclosed in a container **176** that is transparent to infra-red radiation, which container may be glass and may be provided with an opening **178** in the wall to facilitate evacuation to the level of outer space. The system includes two torque converters **180** and **182** that are arranged to rotate oppositely disposed drive shafts **184** and **186** of a generator **188**. The body of generator **188** is directly connected to drive shaft **184**, while the armature of the generator is connected to the drive shaft **186**.

The radiometer generator system of FIG. **27** is rotatively suspended in the container **176** by upper and lower suspension members **190** and **192**, respectively. Thus, as shown, upper suspension member **190** extends between the upper end of drive shaft **184** and a disc **194** that is attached to the wall of container **176**. Lower suspension member **192** extends between the lower end of drive shaft **186** and a disc **196** that is attached to the opposite wall of container **176**.

The torque converters **180** and **182** are shown as of the type illustrated in FIG. **6**, and include four lightweight vanes indicated at **198** and **200**, respectively. One side of each of the vanes is blackened and the other is bright, the black sides of vanes **198** all facing in the same direction, the clockwise direction, as shown, and the bright sides of vanes **200** all facing in the counterclockwise direction. As a result, radiant energy differentially absorbed and emitted by the blackened surfaces of the vanes **198** and **200** impart kinetic energy to adjacent molecules to provide a turning moment on the drive shafts **184** and **186** of generator **188** in the counterclockwise and clockwise directions, respectively. A device **201** that may be similar to the device **174** of FIG. **15** may be provided for utilizing the electrical output of generator **188**.

It will be understood that combinations of whole systems units, each identical to the structure of FIG. **27**, may be provided. Such combinations may be similar to those illustrated in FIGS. **18** through **25**. Additionally, similarly to the constructions of FIG. **26**, the structure of FIG. **27** may be embodied in constructions linking two and more whole system units into elongated chains.

FIG. **28** illustrates a power amplifier embodiment of the present invention in which the output voltage of a radiometer generator system **202**, which may be similar to that illustrated in FIG. **6** is amplified by an arrangement consisting of an induction coil **204**, a pair of spaced electrodes **206** and **207**, and a second radiometer generator system **208**, the entire system being mounted on a base plate **210** and enclosed in a glass container **212** that has been appropriately evacuated, as previously described.

The output terminals of radiometer generator system **202** are connected to the input terminals of the induction coil **204** and the high voltage output terminals of the latter are connected through a suitable diode rectifier **214** to the terminals of a high voltage capacitor **216** as shown in FIG. **29**, the terminals of capacitor **216** being connected to the electrodes **206** and **207**. While shown as of the solid state variety, the rectifier **214** may be of the vacuum type. The induction coil **204** may be similar in construction to the induction coil **122** that has been described by reference to FIGS. **13** and **14**. The high voltage alternating current output of induction coil **204**, however, is converted to direct voltage by rectifier **214** and capacitor **216**.

The radiometer generator system **208** may be similar in construction to the generator system of FIG. **6**, but preferably includes a torque converter **218** in which vanes **220** are somewhat larger, and moreover, are supported on the ends of rods **222** at a greater radial distance from a center plate **224** that is attached perpendicularly to the end of a drive shaft **226** of a dynamoelectric machine **228** having a greater output than generator of system **202**.

As illustrated the electrodes **206** and **207** are so spaced and so positioned with respect to the circular path transversed by the vanes **220** as to intercept a substantial portion of that path without, however, providing any physical obstruction to the movement of the vanes **220**. The polarity of the high voltage applied to electrodes **206** and **207** is such as to make electrode **207** positive with respect to electrode **206** whereby a high voltage molecular stream is established in the direction indicated by the arrow in FIG. **28**. This molecular stream or flow of electrons between the electrodes impinges upon each of the vanes **220** as they successively traverse an arcuate path between the electrodes, thereby to produce a turning moment on the drive shaft **226** in the counterclockwise direction, as illustrated. This turning moment supplements the turning moment produced on the drive shaft **226** by the effect of radiation impingement upon the blackened surfaces of the vanes **220**, one side of each vane **220** being blackened and the other being bright and with the blackened surfaces all facing in the same direction, that required to produce a counterclockwise turning moment. Hence, the high voltage molecular stream enables the turning of the generator **228** to provide an electrical output greater than that obtainable from the generator of radiometer generator system **202**. The amplified power output from generator **228** is available from terminals **230** thereof.

FIG. **30** illustrates an embodiment of the otheoscopic form of radiation generator for use in outer space wherein dual othescopic generators are utilized with associated induction coils to provide power amplifiers, and wherein the power amplifiers are linked into a chain or brigade to produce increasingly higher electrical fields to drive increasingly more powerful generators. Specifically, there is provided in FIG. **30** a first dual otheoscopic generator indicated at **232** consisting of respective upper and lower radiant energy absorber/emitter surfaces **234** and **236**, respective upper and lower torque converters **238** and **240**, respective upper and lower drive shafts **242** and **244**, and a common dynamoelectric machine **246**. Each of the otheoscopic generators may be similar to that illustrated and described by reference to FIG. **1**. Thus, the absorber/emitter surfaces **234** and **236** may each consist of a blackened surface provided on a respectively associated plate **248** and **250** which are disposed in parallel relation to each other, rigidly supported by suitable rods **252**. The surfaces **234** and **236** are respectively associated with torque converters **238** and **240**, each of the latter comprising a fan shaped bank or plurality of light weight vanes radiating from a center disc which, in turn, is attached perpendicularly to a respectively associated drive shaft **242** and **244**. The upper drive shaft **242**, similarly to the arrangement of FIG. **15**, is attached to the armature of a first generator, while the lower drive shaft is attached to the armature of a second generator, the magnetic field sections of the generators being connected together and attached to the outer case. As described in connection with FIG. **15**, the torque converters **238** and **240** are so arranged with respect to their associated absorber/emitter surfaces as to drive their associated shafts **242** and **244** in opposite directions. As a result, the otheoscopic generator **232** is dynamically balanced.

The output terminals of generator **246** are connected to the input terminals of an induction coil **254** that may be similar to that illustrated in FIG. **14**. Additionally, as in the apparatus embodiment of FIG. **28**, a diode rectifier-capacitor circuit desirably is provided to convert the high voltage alternating current output of the induction coil to a high voltage direct current potential. A circuit similar to that shown in FIG. **29** is suitable for this purpose.

The high voltage direct current potential so obtained from the dual otheoscopic generator is applied, in parallel, to a first or upper air of spaced electrodes **256** and to a second or lower pair of spaced electrodes **258**, as seen in FIG. **30**. The spaced electrodes **256** are associated with a fan shaped bank of vanes of an upper torque converter of a second dual otheoscopic generator **260**, being so polarized as to supplement the turning moment on the drive shaft connected to the torque converter that is provided by the associated absorber/emitter surface. The spaced electrodes **258** are similarly associated with the vanes of the lower torque converter of the otheoscopic generator **260**, the electrodes **258** being polarized oppositely to that of the electrodes **256** since the turning moment produced by lower torque converter is opposite to that of the upper torque converter. The otheoscopic generator **260** may be similar to the otheoscopic generator **232**, the output thereof being applied to an induction coil similar to the induction coil **254** and similarly rectified to provide a high voltage unidirectional potential output. Each successive otheoscopic generator may be somewhat larger than the preceding one, four such generators being shown in FIG. **30**, thereby to provide a brigade creating increasingly higher voltage fields to drive increasingly more powerful dual otheoscopic generators, as indicated at **262** and **264**.

FIG. **31** illustrates another embodiment of a power amplification system, according to the invention, that utilizes a combination of a plurality of otheoscopic generators and a plurality of radiometric generators. Thus, there is provided a platform **266** on which are mounted two otheoscopic generators **268** and **270**, each of which may be similar to the otheoscopic generator illustrated in FIG. **15**, and two radiometric generators **272** and **274**, each of which may be similar to the generator illustrated in FIG. **27**. Desirably, each of the radiometric generators **272** and **274** is enclosed in a glass or heat conducting container that is not shown to avoid undue complication of the drawing.

As illustrated, induction coils **276** and **278** are provided, being respectively associated with the otheoscopic generators and each including a suitable rectifier and capacitor as described in connection with FIGS. **28** and **29**. As in the arrangement of FIG. **30**, two pairs of electrodes **280** and **282**, and **284,286** are provided in respective association with the outputs of each of the induction coils **276** and **278**, and the circular path of the vanes of the radiometric generators **272** and **274**. The polarities of the electrodes are so arranged that the molecular streams between electrodes supplements the turning moments provided by the absorber/emitter surfaces of the vanes of the respective radiometric generators, thereby providing increased power output therefrom.

FIG. **12** illustrates another modification of the invention comprisiing an otheoscopic form of radiation generator for use in outer space linked to an induction coil and spaced electrodes to produce photon emission from a gem stone. The light from the gem stone may be transmitted in substantially all coordinate directions through fresnel lenses. Thus, there is provided a self-contained arrangement that aptly may be termed a lighthouse in outer space.

The otheoscopic generator and induction coil of FIG. **12** may be similar to the dual otheoscopic generator **232** and the induction coil **254** of FIG. **30**, and accordingly, have been designated by the same reference numbers. The output terminals of the induction coil **254** are connected through a diode rectifier and capacitor (not shown) to a pair of spaced electrodes **288** and **290**, the latter having a positive potential. A gem stone **292** is positioned between the electrodes **288** and **290**, being mounted on a pedestal **294**. The pedestal **294**, induction coil **254** and generator **232** are all supported on a base plate **296**. The gem stone **292** is positioned centrally of a box-like container **298** that is also supported on the base plate **296**. Each wall of container **298** includes a fresnel lens **300** in that side of container **298**.

FIG. **33** illustrates an otheoscopic form of radiation generator linked to an induction coil for producing a molecular stream of high velocity in a given direction thereby to provide means of propulsion in outer space, specifically a form of rocket engine, for a space craft indicated by the reference numeral **302**. Since it is known that the shape and direction of a high-voltage, high velocity stream can be influenced by a magnetic field, advantage is taken of this in the arrangement of FIG. **33** to direct the electrical field by changing the magnetic field strength.

The otheoscopic radiation generator and induction coil of FIG. **33** may be similar to the dual otheoscopic generator **232** and induction coil **254** of FIG. **30**, and in FIG. **33**, have been designated by those numerals. In practice, it is contemplated that several such otheoscopic generator and induction coil arrangements as illustrated in FIG. **30**, would be utilized. The output terminals of induction coil **254** are connected through a suitable diode rectifier and capacitor, not shown, to a pair of spaced electrodes, indicated at **304** and **306**, the latter being the positive electrode. Electrode **306** has the form of a plate with a centrally located opening indicated at **308** and is positioned on the end of a rudder **310**. Rudder **310** is carried at the rear of a platform **312**, being mounted on a suitable universal joint. Otheoscopic generator **232** and induction coil **254** are shown mounted on the platform **312**, forwardly thereof. Also mounted on platform **312**, by means not shown, are a plurality of spaced magnetic coils, indicated at **314**, that are positioned about and along a portion of the length of the path of the high velocity electrical stream between the negative electrode and **304** and the positive electrode **306**. As those skilled in the art understand, reaction between the magnetic fields established by the magnetic coils **314** and the magnetic field established by the high velocity electrical stream about itself is effective to deflect the stream laterally and vertically in accordance with the relative directions and intensities of the magnetic fields produced by the spaced coils **314**. It will be understood that electrical current for energizing the coils **314** may be obtained from another or even several otheoscopic generators of a type similar to the generator **232**.

In FIG. **33** it is contemplated that a portion of the high velocity molecular stream directed toward the positive electrode or plte **306** escapes through the opening **308** providing a force on the negative electrode **304** that is unopposed, and accordingly, that is useful to propel the space craft **302** in the opposite direction, that indicated by the arrow designated by the numeral **316**. Since the shape and direction of the high-voltage, high velocity stream can be influenced by a magnetic field, advantage is taken of this to direct the stream by changing the relative magnetic field strengths, longitudinally of the stream, in each of the four quadrants about the stream. Thus, for example, deflection of the stream effected to the left rear or port side, as seen in FIG. **33**, will result in the craft turning its bow to starboard. It is contemplated that the strength and spatial intensity of the magnetic fields established by coils **314** would be activated by navigational and computer equipment of conventional or known type, not shown.

Without a magnetic field as produced by magnetic coils **314** present, it will be understood that control of the direction of the craft could be obtained by mechanical movement of the position of the positive electrode or plate **306**, as by mechanical deflection of the rudder **310** about its universal mounting, thereby enabling manual adjustment of the direction in which space craft **302** is propelled.

FIG. **34** illustrates an embodiment of the invention that provides a self contained source of coherent light. Thus, there is provided in FIG. **34** a self-contained laser system indicated at **318** comprising an otheoscopic generator **320**, a dynamoelectric machine or electric generator **322**, an induction coil **324**, spaced electrodes **326**, a gem stone **328**, a base **330** and a glass enclosure **332**.

The otheoscopic generator **320** may be of the type illustrated in FIG. **1** and includes a fan shaped torque converter **334** that is connected to the drive shaft of generator **322**. The induction coil **324**, which may be of the type illustrated in FIG. **14**, has its input connected to the output terminals of generator **322**. The output terminals of induction coil **324** has its output terminals connected through a suitable rectifier and capacitor, not shown, for converting the high-voltage alternating current output to a high voltage unidirectional voltage output, as described in connection with FIG. **29**. The negative output terminal of induction coil **324** is applied to one of the spaced electrodes **326**, and the positive terminal is applied to the other one of the electrodes **326**. Gem stone **328**, desirably a ruby rod, having a half silvered mirrored surface at one end, is placed between the spaced electrodes **326** for bombardment by the electrical field established by the electrodes in a direction perpendicular to the long axis of the ruby rod. The various otheoscopic generator laser components are suitably mounted on the base **330** and located within glass container **332** which is suitably evacuated.

In the operation of the laser system, the high-voltage electrical field established between the electrodes **326** stimulates the ruby rod **328** to the emission of light. Stimulated emission of light occurs, as is known in the art, as radiant energy travelling back and forth between the mirrored surfaces at the ends of the long axis of the ruby rod **328** builds up to a level of magnitude enabling it to escape through the escape half-silvered morror surface indicated at **336** as a spaced frequency distribution of coherent light. In FIG. **34** a lens **338** is provided in the wall of container **332** for diverging or converging the radiation emitted by the ruby rod **328**, as needs vary. Other kinds of lenses may be employed, if desired.

There has thus been provided, according to the present invention self-contained radiometric and otheoscopic generator system and several variations, combinations and cluster arrangements thereof for generating electrical energy from incident radiation emanating from external environmental sources including the sun or any source of infra-red energy whether derived from space, the air, land or water.

Where the development of an increased electrical output, voltage or current, from the available environmental radiation is desired or required, it has been shown that the electrical outputs of a plurality of otheoscopic and/or radiometric generators may be connected in series or parallel, the series connection providing an increased voltage output and the parallel connection an increased current output.

Additionally, for the development of increased kinetic energy from the incident radiation and correspondingly increased electrical energy from each otheoscopic or radiometric generator, it has been shown that several torque converters each having its own bank or plurality of vanes may be associated with the drive shaft of the generator, arranged either in tandem or in parallel, appropriate gearing being provided for the parallel arrangement, and that further increase in the electrical energy output may be provided by arranging the generator combinations in clusters, particularly, for use in outer space.

Embodiments of the invention involving dual otheoscopic generators linking power amplifiers in a chain or brigade thereby to provide more powerful generators have also been provided. The use of the invention for space ship propulsion also is illustrated.

Embodiments of the invention have also been provided for self-contained photon-emitting devices, providing for example, beacons or lighthouses in space and for providing coherent source of light.

I claim:

1. An electric generator comprising a dynamoelectric machine having an input drive shaft and output electrical terminals, a torque converter having an output member connected to rotate said drive shaft and energy receiving means for driving said drive shaft, and means including a radiation absorber/emitter surface operatively associated with said torque converter for absorbing radiation and transmitting it to nearby gas molecules and imparting energy to them to cause them to travel and impart energy to said energy receiving means, said absorber/emitter surface and nearby gas molecules imparting kinetic energy to said torque converter responsively to incident radiation.

2. A generator as specified in claim **1** wherein said torque converter energy receiving means includes a plurality of movable vanes that radiate from said output member about an axis coincident with said drive shaft.

3. A generator as specified in claim **2** wherein said absorber/emitter surface means includes a black surface formed on a plate that has good heat conductivity and is positioned adjacent the path of movement of said movable vanes.

4. A generator as specified in claim **3** wherein said plate is flat and said movable vanes comprise the vanes of a circular fan.

5. A generator as specified in claim **3** wherein said output member includes a center disc that is attached to the end of said drive shaft, and wherein said plate is curved to provide a semicircular cylindrical portion, and wherein each of said movable vanes is attached to the end of an associated rod that is attached to and radiates from said center disc, the angle subtended by each vane with respect to said curved plate being such that molecular disturbance emanating from the absorber/emitter surface of said curved plate produces a turning moment on said vane.

6. A generator as specified in claim **2** including an evacuated container, said torque converter and said absorber/emitter surface being positioned within said container, and wherein said absorber/emitter surface comprises a blackened radiant energy absorbant surface that is provided on one face of each of said vanes, the other face being bright, with the blackened surfaces all facing in the same direction around said output member, and with each of said vanes so positioned as to have at least a component of the blackened surface thereof parallel to the shaft of said dynamoelectric machine.

7. A generator as specified in claim **2** wherein a surface of each said vanes is so positioned as to be substantially parallel to the drive shaft of said dynamoelectric machine.

8. A generator as specified in claim **2** including an evacuated container and a base plate for said container, and wherein said dynamoelectric machine, torque converter and absorber/emitter surface are supported on said base plate within said container.

9. A generator as specified in claim **8** including a fresnel lens and a parabolic lens, said lenses being positioned externally of said container, one on one side thereof and one on the other, and each directing environmental radiation toward said absorber/emitter surface.

10. A generator as specified in claim **9** including a heat pipe comprising a radiant energy source and a collimator positioned between said heat pipe and said fresnel lens for directing rays of radiant energy to said fresnel lens and for making them parallel whereby said rays of radiant energy are concentrated by said fresnel lens on said absorber/emitter surface.

11. A generator as specified in claim **10** including at least one actuatable electrical device supported on said base plate within said container, said electrical device being connected to the output electrical terminals of said dynamoelectric machine.

12. A generator as specified in claim **11** wherein said actuatable electrical device comprises an electric lamp, and further including a meter within said container connected to the output electrical terminals of said dynamoelectric machine.

13. A generator as specified in claim **8** wherein said dynamoelectric machine produces direct electrical current and wherein said evacuated container includes a pair of terminals positioned in a wall thereof, said pair of terminals being connected to the output terminals of said dynamoelectric machine.

14. A generator as specified in claim **8** including an induction coil having a pair of input terminals and a pair of output terminals, a pair of electrodes, and a gem stone positioned within said container between said electrodes, the input terminals of said induction coil being connected to the output terminals of said dynamoelectric machine, the output terminals of said induction coil being connected to said electrodes, and said gem stone being positioned between said electrodes so that it is activated by the emissions from the electrodes.

15. A generator as specified in claim **1** wherein said dynamoelectric machine includes a second input drive shaft disposed in axial alignment with said first mentioned input drive shaft, and further including a second torque converter having an output member connected to rotate said second drive shaft, said second torque converter being so arranged with respect to said radiation absorber/emitter surface that the latter and nearby gas molecules impart kinetic energy to said second torque converter, responsively to incident radiation, in a sense opposite to the kinetic energy imparted to said first mentioned torque converter.

16. A generator as specified in claim **15** wherein said first and second input drive shafts are positioned at the opposite ends of said dynamoelectric machine, and said absorber/emitter surface is provided on a plate that is curved to provide a semi-circular cylindrical portion, and wherein each of said torque converters includes a center disc attached to the end of each of said input drive shafts, a plurality of rods radiating from each of said centers discs, and a vane carried on the end of each of said rods for movement in a path closely adjacent said semi-circular cylindrical portion of said plate.

17. A generator as specified in claim **15** wherein each of said torque converters includes a plurality of movable vanes, wherein the vanes associated with each of said torque converters comprise the vanes of an individual circular fan, and wherein said radiation/emitter surface is formed on one surface of each of a pair of oppositely disposed parallel plates, said one surface of each of said plates being positioned adjacent the path of movement of the vanes of an associated one of said circular fans.

18. A generator as specified in claim **15** wherein a second radiation absorber/emitter surface is associated with said second torque converter, said second absorber/emitter surface and nearby gas molecules imparting kinetic energy to said second torque converter responsively to incident radiation, said first and second torque converters each including a plurality of movable vanes that radiate respectively from the associated output member of said first and second torque converters about an axis coincident with said aligned first and second input drive shafts of said dynamoelectric machine, all of said vanes being so positioned as to be substantially parallel to said aligned drive shafts, and wherein said first and second radiation absorber/emitter surfaces respectively associated with said first and second torque converters each comprise a blackened radiant energy absorbant and emitting surface provided on one face of each the vanes of the associated torque converter, the other face being bright, with the blackened surfaces of the vanes of said first torque converter all facing in one direction around the shaft of said dynamoelectric machine and the blackened surfaces of the vanes of said second torque converter facing in the opposite direction.

19. A generator as specified in claim **1** including at least one additional torque converter having an output member connected to said drive shaft of said dynamoelectric machine, and a radiation absorber/emitter surface associated with each such additional torque converter, each such additional radiation absorber/emitter surface and nearby gas molecules imparting kinetic energy to the associated additional torque converter in the same sense as the kinetic energy imparted to said first mentioned torque converter by said first mentioned absorber/emitter surface and nearby gas molecules responsively to incident radiant energy.

20. A generator as specified in claim **19** wherein said torque converters are connected in tandem to said drive shaft of said dynamoelectric machine.

21. A generator as specified in claim **19** wherein said torque converters are connected in parallel to said drive shaft of said dynamoelectric machine.

22. A generator as specified in claim **2** wherein said dynamoelectric machine provides direct electrical current at its output electric terminals and including at least another torque converter having movable vanes and associated absorber/emitter surface that are similar to the first mentioned torque converter and absorber/emitter surface, an induction coil having a pair of input electrical terminals and a pair of output electrical terminals, electrical rectifying means, and a pair of spaced electrodes, said input terminals of said induction coil being connected to said output electrical terminals of said dynamoelectric machine, said output terminals of said induction coil being connected through said rectifying means to said spaced electrodes whereby an alternating electrical current output of said induction coil is converted to a direct current potential output that is applied to said spaced electrodes, said spaced electrodes being positioned to intercept a portion of the path of the movable vanes of said another torque converter whereby a molecular stream established between said electrodes by said direct current potential output impinge upon said last mentioned movable vanes to supplement the kinetic energy output of said second torque converter.

23. An electric generator comprising

a dynamoelectric machine having an input drive shaft and output electrical terminals,

a torque converter connected to said shaft,

said torque converter including a plurality of lightweight vanes radially connected to said shaft,

radiation absorber/emitter means for driving said vanes and rotating said shaft,

said absorber/emitter means including surface means for absorbing radiant energy and heating up and emitting heat to agitate nearby gas molecules and thereby create a molecular wind that rotates said vanes to rotate said input drive shaft of said dynamoelectric machine and generate electricity.

24. A power amplifier comprising a plurality of dual otheoscopic generators and individually associated dynamoelectric machines linked into a chain to produce increasingly more powerful generators, said otheoscopic generators each including a plurality of movable vanes, said amplifier further including a plurality of pairs of spaced electrodes, a plurality of rectifying means, and a plurality of induction coils each having an input associated with the output and an individual one of said dynamoelectric machines and an output associated with one of said rectifying means, the output of each of said rectifying means being applied between the spaced electrodes of an associated one of said pairs of spaced electrodes, successive ones of said pairs of spaced electrodes being positioned to intercept a portion of the path of the movable vanes of the successive otheoscopic generator in the chain whereby a molecular stream established between pairs of said electrodes impinge upon said movable vanes to supplement the kinetic energy output of said successive generator.

25. A power amplifier as specified in claim **24** wherein each of said dynamoelectric machines includes a pair of oppositely disposed rotary drive shafts, and an otheoscopic generator of each of said dual otheoscopic generators being associated with an individual one of each of said shafts, the direction of rotation of each of said shafts being in opposite directions whereby each of said dynamoelectric machines are dynamically balanced.

26. A power amplifier as specified in claim **25** wherein the electrodes of each of the pairs of spaced electrodes associated with the otheoscopic generators of each dual otheoscopic generator are oppositely polarized whereby the individual molecular streams established between the pairs of electrodes and impinging upon the movable vanes of the associated otheoscopic generator of each dual otheoscopic generator are oppositely directed and have a minimal effect on the dynamic balance of the associated dynamoelectric machine.

27. An electric generator as specified in claim **1** further including means providing an evacuated space, said dynamoelectric machine, torque converter and absorber/emitter surface being wholly contained within said evacuated space.

* * * * *

US007057514B2

(12) **United States Patent**
Mickle et al.

(10) **Patent No.: US 7,057,514 B2**
(45) **Date of Patent: Jun. 6, 2006**

(54) **ANTENNA ON A WIRELESS UNTETHERED DEVICE SUCH AS A CHIP OR PRINTED CIRCUIT BOARD FOR HARVESTING ENERGY FROM SPACE**

(75) Inventors: **Marlin H. Mickle**, Pittsburgh, PA (US); **Christopher C. Capelli**, Pittsburgh, PA (US); **Harold Swift**, Gibsonia, PA (US)

(73) Assignee: **University of Pittsburgh - Of the Commonwealth System oif Higher Education**, Pittsburgh, PA (US)

(*) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 0 days.

(21) Appl. No.: **10/857,527**

(22) Filed: **Oct. 5, 2004**

(65) **Prior Publication Data**

US 2005/0030181 A1 Feb. 10, 2005

Related U.S. Application Data

(60) Provisional application No. 60/475,151, filed on Jun. 2, 2003.

(51) **Int. Cl.**
G08B 13/14 (2006.01)

(52) **U.S. Cl.** **340/572.7**; 340/572.4; 343/701; 343/703

(58) **Field of Classification Search** .... 340/572.2, 340/572.6, 572.4, 572.7; 343/895, 879, 795, 343/793, 700 MS, 701, 703; 257/491, 678, 257/679, 778
See application file for complete search history.

(56) **References Cited**

U.S. PATENT DOCUMENTS

4,471,344	A *	9/1984	Williams	340/572.2
4,724,427	A	2/1988	Carroll	
4,857,893	A	8/1989	Carroll	
5,296,866	A	3/1994	Sutton	
6,054,925	A *	4/2000	Proctor et al.	340/572.7
6,100,804	A *	8/2000	Brady et al.	340/572.7
6,177,872	B1 *	1/2001	Kodukula et al.	340/572.7
6,289,237	B1	9/2001	Mickle et al.	
6,335,686	B1 *	1/2002	Goff et al.	340/572.4
6,373,447	B1 *	4/2002	Rostoker et al.	343/895
6,615,074	B1	9/2003	Mickle et al.	
6,856,291	B1	2/2005	Mickle et al.	

* cited by examiner

Primary Examiner—Anh V. La
(74) *Attorney, Agent, or Firm*—Arnold B. Silverman; Philip E. Levy; Eckert Seamans Cherin & Mellott, LLC

(57) **ABSTRACT**

A wireless untethered device which may be an integrated circuit chip or printed circuit board having at least one integrated antenna and circuitry operatively associated with the antenna for receipt of energy harvested from space by the antenna. The antenna has an effective area greater than its physical area. A system which receives power from the harvested energy after the energy is processed by the circuitry may also be provided with mismatched impedance between the antenna and a circuit resistance.

12 Claims, 40 Drawing Sheets





FIG. 1



Power and voltage measurement circuitry

FIG. 2



FIG. 3A



FIG. 3B


6
5
4
3
2
1
0

FIG. 4a


16.0 CM
19.0 CM
11.0 CM
14.7 CM
17.25 CM
DC Bus
5 4 3 2 1
Antenna
Charge Pumps
Antenna
(C)
(B2)
(B1)
(A2)
(A1)
(C)
(B)
(A)

FIG. 4b


6
5
4
3
2
1
0

FIG. 5a


11.0 CM
14.7 CM
16.0 CM
19.0 CM
17.25 CM
5 4 3 2 1
(C)
(B2)
(B1)
(A2)
(A1)
(C)
(B)
(A)

FIG. 5b



FIG. 6a



FIG. 6b



FIG. 6c



FIG. 6d


Voltage Measurements
6
5
4
3
2
1
0
Voltage on te 10K resistor (volt)
0
20
40
60
80
100
120
Distance (cm)
Antenna A
Antenna B
Anatenna C
Anatenna D

FIG. 7



	5.3	16	36.6	144
■ Voltage	1.0981	2.1933	3.4162	4.932

FIG. 8



FIG. 9a



FIG. 9b



FIG. 9c



FIG. 9d



FIG. 9e


Voltage Measurements
Voltage on the 10K Resistor (volt)
Distance (cm)
0
1
2
3
4
5
6
0
20
40
60
80
100
120
Antenna A
Antenna B
Antenna C
Antenna D
Antenna E

FIG. 10


1
0.5
2
0.2
5
0
0.2
0.5
1.0
2.0
5.0
-0.2
-5
-0.5
-2
-1
18.Onh 7.0pt
15 Onh 1.0pt
15 Onh 5.0pt
12 Onh 5.0pt
12 Onh 3.0pt
12.Onh 1.0pt
22.Onh 5.0pt
22.Onh 6.0pt
18.2nh 3.0pt
18.Onh 2.0pt
22.Onh 1.0pt
18.Onh 3.0pt
22. Onh 1.5pt
18.Onh 4.0pt
22.Onh 2.0pt
27.Onh 1.0pt
18.Onh 6.0pt
22.Onh 5.0pt
8.2nh 1.0pt
18.Onh 1.0pt
18.Onh 5.0pt
22.Onh 2.5pt
33.Onh 1.0pt
27.Onh 1.5pt
33.0nh 4.0pt
22.Onh 2.7pt
27.0nh 4.0pt
39.Onh 1.0pt
22.0nh 3.0pt
47.0nh 1.0pt
27.0nh 2.0pt
27.0nh 2.2pt
22.0nh 4.0pt
22.0nh 3.5pt
27.0nh 2.3pt
27.0nh 3.5pt
39.0nh 3.0pt
39.0nh 1.5pt
33.0nh 3.0pt
27.0nh 2.4pt
27.0nh 3.0pt
27.0nh 2.5pt
47.0nh 1.8pt
39.0nh 2.0pt

FIG. 11


Antenna A
Voltage
6
5
4
3
2
1
0
y = -0.044x + 7.132
0
20
40
60
80
100
120
140
Distance

FIG. 12a


Antenna B
Voltage
Distance
0
1
2
3
4
5
6
0
20
40
60
80
100
120
140
y = -0.0421x + 7.1831

FIG. 12b


Antenna C
6
5
4
3
2
1
0
Voltage
y = -0.0477x + 6.2825
0
20
40
60
80
100
120
140
Distance

FIG. 12c



Number of Measurement	Thickness
1	55.1 um
2	223 um
3	234um

FIG. 13a



Number of Measurement	Thickness
1	55.1um
2	82.3um
3	273um

FIG. 13b


Voltage Measurements
Voltage on the 10K Resistor (volt)
0
1
2
3
4
5
6
0
20
40
60
80
100
120
Distance (cm)
1
2
3

FIG. 14a


Voltage Measurements
6
5
4
3
2
1
0
Voltage on the 10K Resistor (volt)
0
20
40
60
80
100
120
Distance (cm)
T= 55.1um
T= 82.3um
T= 273um

FIG. 14b


Antenna B
6
5
4
3
2
1
0
Voltage
y= -0.0421x + 7.1831
0
20
40
60
80
100
120
140
Distance

FIG. 15a


Antenna E
Voltage
6
5
4
3
2
1
0
y= -0.0469x + 6.2232
0
20
40
60
80
100
120
140
Distance

FIG. 15b



FIG. 16a



FIG. 16b


Comparison of the Two Feeding Methods
Voltage on the 10K Resistor (volt)
2
1.8
1.6
1.4
1.2
1
0.8
0.6
0.4
1.2
0
Microstrip Line Feed
Probe Feed
0
10
20
30
40
50
60
70
Distance (cm)

FIG. 17



Antenna A
(No Ground Plane)

Antenna B
(With Ground Plane)

FIG. 18a



FIG. 18b


Voltage Measurements
Voltage on te 10K resistor (volt)
6
5
4
3
2
1
0
0
20
40
60
80
100
120
Distance (cm)
Antenna A
Antenna B

FIG. 19


In Out
Antenna
$\beta\ e_{IN}$
$\alpha\ (1-\beta)\ e_{IN}$
Intentional Mismatch
$(1-\alpha)\ (1-\beta)\ e_{IN}$
Z
+
R
Ideal
Tank
L
C
Output

FIG. 20


In Out
Antenna
$\beta\ e_{IN}$
$\alpha\ (1-\beta)\ e_{IN}$
Intentional Mismatch
$(1-\alpha)\ (1-\beta)\ e_{IN}$
Z
+
R
Ideal
Tank
L
C
Output
Trace Width, Thickness

FIG. 21


1
0.5
2
0.2
5
0
-0.2
-5
-0.5
-2
-1
0.2
0.5
1.0
2.0
5.0
18.Onh 7.0pt
15 Onh 1.0pt
15 Onh 5.0pt
18.Onh 2.0pt
12 Onh 5.0pt
12 Onh 3.0pt
22.Onh 5.0pt
12.Onh 1.0pt
22.Onh 6.0pt
18.2nh 3.0pt
22.Onh 1.0pt
18.Onh 3.0pt
22. Onh 1.5pt
18.Onh 4.0pt
22.Onh 2.0pt
22.Onh 1.0pt
18.Onh 6.0pt
22.Onh 5.0pt
8.2nh 1.0pt
18.Onh 1.0pt
18.Onh 5.0pt
27.Onh 2.5pt
33.Onh 1.0pt
27.Onh 1.5pt
33.0nh 4.0pt
27.0nh 4.0pt
39.Onh 1.0pt
22.0nh 3.0pt
27.0nh 2.0pt
47.0nh 1.0pt
22.0nh 4.0pt
22.0nh 3.5pt
27.0nh 2.2pt
27.0nh 3.5pt
27.0nh 2.3pt
39.0nh 3.0pt
39.0nh 1.5pt
33.0nh 3.0pt
27.0nh 2.4pt
27.0nh 3.0pt
27.0nh 2.5pt
47.0nh 1.8pt
39.0nh 2.0pt

FIG. 22


1
0.5
2
0.2
5
0
0.2
0.5
1.0
2.0
5.0
-0.2
-5
-0.5
-2
-1
15 Onh 1.0pt
18.Onh 1.0pt
12 Onh 5.0pt
15 Onh 3.0pt
18.Onh 2.0pt
12.Onh 3.0pt
15 Onh 5.0pt
22.Onh 1.0pt
12.Onh 1.0pt
18.Onh 3.0pt
22 Onh 1.5pt
8.2nh 3.0pt
18 Onh 4.0pt
22 Onh 2.0pt
27 Onh 1.0pt
8.2nh 1.0pt
18.Onh 7.0pt
18.Onh 5.0pt
18.Onh 6.0pt
27 Onh 1.5pt
33.Onh 1.0pt
8.2nh 5.0pt
27 Onh 3.0pt
27.0nh 2.0pt
39.Onh 1.0pt
22.0nh 3.0pt
47.0nh 1.0pt
22.0nh 4.0pt
39.Onh 1.5pt
47.0nh 1.3pt
33.0nh 4.0pt
33.0nh 2.0pt
39.Onh 1.8pt
27.0nh 3.5pt
27.0nh 3.0pt
47.0nh 1.5pt
33.0nh 3.0pt
47.0nh 1.6pt
39.0nh 3.0pt
39.0nh 2.5pt
39.0nh 5.6pt

FIG. 23



FIG. 24a



FIG. 24b


Antenna B
Voltage
Distance
0
1
2
3
4
5
6
0
20
40
60
80
100
120
140
CMOS Die
y = 0.0421 + 7.1831
PCB

FIG. 25



FIG. 26a



FIG. 26b


P1
P2
P3
P4
P5
P6

FIG. 27


Voltage Measurements
Voltage on te 10K resistor (volt)
Distance (cm)
0
1
2
3
4
5
6
0
20
40
60
80
100
120
P1
P2
P3
P4
P5
P6

FIG. 28


Position 1
y = -0.0603x + 7.8715
Voltage
0
1
2
3
4
5
6
0
50
100
150
Distance
Position 2
y = -0.0507x + 7.1012
Voltage
0
1
2
3
4
5
6
0
50
100
150
Distance
Position 3
y = -0.0005x + 0.6295
Voltage
0
1
2
3
4
5
6
0
50
100
150
Distance
Position 4
y = -0.0009x + 0.2857
Voltage
0
1
2
3
4
5
6
0
50
100
150
Distance
Position 5
y = -0.0005x + 0.0426
Voltage
0
1
2
3
4
5
6
0
50
100
150
Distance
Position 6
y = -0.0047x + 0.5372
Voltage
0
1
2
3
4
5
6
0
50
100
150
Distance

FIG. 29


y = 0.0327x 3 - 0.2442x 2 + 0.5533x - 0.3409
0.07
0.06
0.05
0.04
0.03
0.02
0.01
0
Negative Slope
0
90
180
270
Negative Fall– Off
Poly. (Negative Fall– Off)
y = 4.5003x 3 - 33.645x 2 + 76.25x - 46.819
9
8
7
6
5
4
3
2
1
0
0
90
180
270
"y" Intercept
Poly. ("y" Intercept)
Angle

FIG. 30

ANTENNA ON A WIRELESS UNTETHERED DEVICE SUCH AS A CHIP OR PRINTED CIRCUIT BOARD FOR HARVESTING ENERGY FROM SPACE

CROSS-REFERENCE

This application claims the benefit of U.S. Provisional Application Ser. No. 60/475,151 entitled "ANTENNA ON A WIRELESS UNTETHERED DEVICE SUCH AS A CHIP OR PRINTED CIRCUIT BOARD FOR HARVESTING ENERGY FROM SPACE" filed Jun. 2, 2003.

BACKGROUND OF THE INVENTION

1. Field of the Invention

A device is disclosed comprising a semiconductor integrated circuit (IC) chip having disposed on it antenna and the circuitry for the IC chip, wherein antenna and the circuitry of the IC chip are integrated so as to provide the IC chip with an improved antenna effective area. The design of the antenna placement on the chip is independent of the location of the antenna on the chip. As a result, antenna-on-a-chips of this invention are simpler to design and manufacture than the designs disclosed in the prior art. With increasing dependence on local and wide area wireless networks, particularly those with low power (range) requirements and local sensing or object identification, there is a need to have an antenna structure integrated onto single semiconductor devices. One important lack has been an on-chip antenna structure that overcomes simple deficiencies of size.

The length and material of antennas normally determine the frequency and intensity of signals that may be received or sent from the antenna. However with smaller and smaller local area wireless networks being contemplated, the concept of a room sized network area or building area with antennas mounted in walls and ceilings (whether independent separate antennas or multi-use antennas, such as using electrical wiring or telephone wiring as an antenna structure), the feasibility of using very low power antenna structures to transfer information from a local network to a wireless IC device or system containing such wireless IC device becomes practicable.

2. Description of the Prior Art

It has been known to provide antennae and circuitry at specific locations on chips. U.S. Pat. Nos. 4,857,893 and 4,724,427 disclose the use of planar antennas that are included in circuitry of a transponder on a chip. As disclosed therein, the antenna coil is etched around the periphery of the chip substrate. In the center of the antenna coil are found a custom logic circuit, a programmable memory array, and memory control logic. The planar antenna of the transponder was said to employ a magnetic film inductor on the chip in order to allow for a reduction in the number of turns and thereby simplify fabrication of the inductors. It disclosed an antenna having a multi-turned spiral coil and having a 1 cm×1 cm outer diameter. When a high frequency current was passed in the coil, the magnetic films were said to be driven in a hard direction, and the two magnetic films around each conductor served as a magnetic core enclosing a one turn coil. The magnetic films were said to increase the inductance of the coil, in addition to its free-space inductance.

One of the problems with the approach as taught in U.S. Pat. Nos. 4,857,893 and 4,724,427 is the need to fabricate small, air core inductors of sufficiently high inductance and Q for integrated circuit applications. The small air core inductors were said to be made by depositing a permalloy magnetic film or other suitable material having a large magnetic permeability and electric insulating properties in order to increase the inductance L of the coil. Such an approach increases the complexity and cost of the antenna on a chip and also limits the ability to reduce the size of the antenna because of the need for the magnetic film layers between the antenna coils.

Another problem with the approach as taught in U.S. Pat. Nos. 4,857,893 and 4,724,427 is the attendant integrating of an antenna on an integrated circuit (IC) chip. In the case of an antenna disposed about the periphery of the chip, as described by the patents discussed hereinabove, the location of the antenna interferes with conventional bond pad layout about the periphery of the chip. Also, the electromagnetic fields within the central area of an antenna laid out about the periphery of a chip can interfere with the operation of circuits located within the antenna.

U.S. Pat. Nos. 6,373,447 discloses the use of one or more antennas that are formed on an integrated circuit chip connected to other circuitry on the chip. The antenna configurations include loop, multi-turned loop, square spiral, long wired and dipole. The antenna could have two or more segments which could selectively be connected to one another to alter effective length of the antenna. Also, the two antennas are said to be capable of being formed in two different metallization layers separated by an insulating layer.

U.S. Pat. No. 6,373,447 attempts to overcome the problems of U.S. Pat. Nos. 4,857,893 and 4,724,427 by having the antenna formed on other than a peripheral area of an integrated circuit (IC) chip. U.S. Pat. No. 6,373,447 describes devices comprising an integrated circuit (IC) chip having a surface wherein the surface is divided into a peripheral area and a central area. The central area comprises a first portion and a second portion wherein the circuitry of the IC chip is disposed within the first portion of the central area; and an antenna disposed within the second portion of the central area. This patent teaches that one or more antennas can be formed on an integrated circuit chip connected to other circuitry on the chip. The antenna configurations include loop, multi-turned loop, square spiral, long wired and dipole. The antenna could have two or more segments which could selectively be connected to one another to alter the effective length of the antenna.

U.S. Pat. No. 6,373,447 attempts to avoid the problems of the antenna interfering with the conventional bond pad layout about the periphery of the chip by placing the antenna in the central area of the chip. However, in all cases disclosed by the inventor the antenna is located in one portion of the central area, and IC circuitry is disposed on the other portion of the central area. The inventors do state in the body of the patent that the antennas can also be located on "one or two or three (but not four) edges of the chip, so long as there are no bond pads in that area".

A problem with the prior art as discussed above is that disposition of the antenna on the chip is limited to specific different parts of the chip. In the case of U.S. Pat. Nos. 4,857,893 and 4,724,427 the antenna is on the periphery of the chip and in the case of U.S. Pat. No. 6,373,447 the antenna is in the central area of the chip.

A further problem with the antenna on chip designs as disclosed by prior art is that the antenna and IC circuitry are disposed as discrete components in separate portions of the chip to minimize the interaction of the antenna and the circuitry of the IC chip. In the case of U S. Pat. No. 6,373,447, the antenna is one portion of the central area and the IC circuitry is the other portion of the central area. This again limits the design of placing an antenna on a IC chip. Furthermore, it makes for devices that are not truly integrated.

SUMMARY OF THE INVENTION

The present invention provides an integrated circuit chip which has at least one integrated and preferably integrally formed antenna with circuitry operatively associated with the antenna for receipt of energy harvested by the antenna from space. In another embodiment, a printed circuit board or other wireless untethered device is employed. The antenna has an effective area greater than its physical area. A system which receives power from the circuitry generally at DC power resulting from rectification by the circuitry of the energy harvested may also be provided on the chip.

The antenna and circuitry may be positioned at any location on the chip without adversely effecting performance.

The antenna may be a spiral antenna such as a square spiral antenna, with the thickness and width of the conductive portion being adjusted to maximize performance. Impedance may be adjusted to provide for an enhanced effective antenna area.

It is an object of the present invention to provide an integrated antenna on a chip or printed circuit board with associating circuitry to facilitate efficient receipt of energy from space by the antenna and conversion of the same by the circuitry to DC power.

It is a further object of the invention to provide such a semiconductor integrated chip or printed circuit board which will deliver DC power from the circuitry to an electronic system.

It is another object of the present invention to provide such a system which does not require the use of a power storage element or hard wiring.

These and other objects of the invention will be made fully understood from the following description on reference to the appended drawings.

BRIEF DESCRIPTION OF THE DRAWINGS

FIG. **1** illustrates a circuit which is an operational device but has no battery or wires for powering.

FIG. **2** illustrates a circuit of the type shown in FIG. **1** with an associated display to measure the energy harvested.

FIG. **3***a* shows a chip having an on-chip antenna for harvesting data and an on-chip on chip antenna for transmitting data.

FIG. **3***b* is a photograph of the chip represented in FIG. **3***a*.

FIGS. **4***a* and **4***b* show, respectively, (i) a plot of experimental results and (ii) a circuit and related power measuring device along with a plot of variations in result due to use of a conductive ground plane.

FIGS. **5***a* and **5***b* show, respectively, a plot and measurement in a representation of the circuit and power representation of ground plane influence.

FIGS. **6***a*–**6***d* show **4** square antenna profiles on a printed circuit board.

FIG. **7** is a plot of distance versus voltage for the four antennas shown in FIG. **6**.

FIG. **8** is a plot of voltage harvested at load for a harvesting distance of 50 cm.

FIGS. **9***a*–**9***e* show five antennas with four being spiral and one being a square patch.

FIG. **10** is a plot of voltage versus distance for the antennae of FIGS. **9***a*–**9***e*.

FIG. **11** is a representation of impedances for various parameters.

FIGS. **12***a*–**12***c* illustrate three variations in trace width for an antenna with plots of voltage versus distance.

FIGS. **13***a*–**13***b* illustrate data for antennas of two different materials and three different thicknesses.

FIGS. **14***a*–**14***b* show plots of voltage versus distance for the antennas of FIGS. **13***a*–**13***b*.

FIGS. **15***a*–**15***b* show plots of voltage versus distance for different lengths.

FIGS. **16***a*–**16***b* illustrate two different feed arrangements for antennas.

FIG. **17** is a plot of voltage versus distance for the two feed lines of FIGS. **16***a*–**16***b*.

FIGS. **18***a*–**18***b* illustrate several antennas with respect to ground plane variations.

FIG. **19** illustrates a plot of distance versus voltage for some of the antennas of FIGS. **18***a*–**18***b*.

FIG. **20** illustrates a circuit in terms of impedance matching elements.

FIG. **21** illustrates the circuit of FIG. **20** with impedance related markings.

FIGS. **22** and **23** illustrate, respectively, experimental and simulated impedance matching plots.

FIGS. **24***a*–**24***b* illustrate, respectively, plots of PCB data points and a projection of the same to about 25 mm.

FIG. **25** shows plots of voltage versus distance for PCB and CMOS traces.

FIGS. **26***a*–**26***b* show, respectively, plots of original data for copper and extrapolation of the same in respect of thickness.

FIG. **27** illustrates six antenna orientations.

FIG. **28** is a plot of voltage versus distance for the orientations of FIG. **27**.

FIG. **29** shows trend lines for the six plots of voltage versus distance as related to FIG. **27**.

FIG. **30** shows the negative slope and y intercept of the trend lines.

DESCRIPTION OF THE PREFERRED EMBODIMENTS

As employed herein, the tern "in space" means that energy or signals are being transmitted through the air or similar medium regardless of whether the transmission is within or partially within an enclosure, as contrasted with transmission of electrical energy by a hard wired or printed circuit boards.

As employed herein the term "wireless untethered device" means a device which is remotely powered by RF energy and shall include, but not be limited to, IC chips, printed circuit boards and other suitable substrates having discrete or integrated circuit components.

What is further needed is an antenna on a chip wherein the antenna is not a discrete component to the IC circuit. In that respect there are two issues; (1) the interference of the received RF energy on the proximate IC circuitry, and (2) the interference of the proximate IC circuitry on the RF energy. While the first issue is important to any functional IC, the separation of the energy harvesting function from the payload IC electronic circuitry, U.S. Pat. No. 6,289,237, discloses isolating the negative effect of the RF from the payload electronics with respect to RF signals as opposed to RF energy. Our experiments have shown that while the payload electronics are in the proximate area of the energy harvesting antenna and associated circuitry, the payload will still function satisfactorily.

The second issue is in fact a benefit to the energy harvesting antenna and adds to the effective area of such an antenna(s). The functional devices for the experiments of the previous paragraph are pictured in FIGS. **1** and **2**. In both cases, the proximate circuitry has been demonstrated to operate satisfactorily in an applied RF energy field while simultaneously enhancing the harvested energy through providing additional area to the effective area to the antenna. The ability to obtain a tractable closed form mathematical formula to describe the indicated situation is extremely difficult at best due to the multitude of effects and interactions by the interconnection circuitry and the proximate components themselves.

FIG. **1** illustrates an operational device with all discrete components and conducting traces in place with no battery or wires for powering. The energy is supplied by beaming radio frequency (RF) energy to the device, rectifying the RF and converting it to direct current (DC), and powering electronics to read a temperature sensor and transmit the result to a receiver. The device requires five milliwatts of power to function. This device is functional as illustrated.

FIG. **2** is a device to measure power where the energy harvesting circuitry is the same as the device in FIG. **1**, but with five sets of light emitting diodes (LED's) connected in parallel to measure voltage without the need to connect wires to the device energy harvesting circuitry. Relative power can also be estimated by observing the brightness of the LED's. The conductors to interconnect the payload components of FIG. **1** are included in FIG. **2** while the proximate electronic components themselves have been removed.

FIG. **3** shows a single chip RFID design using an on-chip antenna for energy harvesting and an on-chip antenna for transmitting data. FIG. **3**.*a*. is the "flatten" picture of the layout from the Computer Aided Design (CAD) tool, and FIG. **3**.*b*. is a photograph of the actual fabricated chip (die).

There is an uncertainty in any in situ energy or power measurements due to the measuring circuitry interfering with the device under test. FIGS. **4***a*–**4***b* include the power measuring device of FIG. **2** along with a graph showing the number of LED's lighted when the space between the energy source and the device is interrupted by a conducting plane inserted perpendicular to a line drawn between the source patch antenna and the device, both of which are parallel. The top of the device was 19.0 cm above the laboratory table top. Conducting planes of 11 cm, 14.7 cm, 16.0 cm, 17.25 cm and 19.0 cm were placed between the antenna and the device. This resulted in lighted LED's numbering 5 (no conducting plane), 4, 4, 3, 2, and 0 respectively for the conducting planes. FIG. **5** is the same set-up as FIG. **4**, where the conducting planes were inserted in the order 17.25 to 19.0 cm, 16.0 to 19.0 cm, 14.7 to 10.0 cm, 11.0 to 19.0 cm, and 0.0 to 19 cm. In FIGS. **5***a*–**5***b*, the LED's that were lighted were 5, 5, 5, 5, 4, and 0.

In the first embodiment of this invention, a device is disclosed comprising an integrated circuit (IC) chip having disposed on it antenna and the circuitry for the IC chip. The antenna or antennas and the circuitry of the IC chip are integrated so as to provide the IC chip with an improved antenna effective area.

In other embodiments, a wireless untethered device such as a printed circuit board may be provided with the desired antenna and circuitry.

"Effective area" of the antenna refers to the functional area of an antenna as compared with the physical area. A tuned antenna may have an effective area that is larger than its geometric area. The phenomenon was disclosed by Reinhold Rudenberg in 1908 [Rudenberg, Reinhold, "Der Empfang Elektrischer Wellen in der Drahtlosen Telegraphie" ("The Receipt of Electric Waves in the Wireless Telegraphy") Annalen der Physik IV, 25, 1908, p. 446–466.] and the description of the phenomena has been expanded upon over the years by many other writers.

U.S. Pat. No. 5,296,866 states that "Rudenberg teaches that the antenna interacts with the incoming field, which may be approximately a plane wave, causing a current to flow in the antenna by induction. The [antenna] current, in turn, produces a field in the vicinity of the antenna, which field, in turn, interacts with the incoming field in such a way that the incoming field lines are bent. The field lines are bent in such a way that the energy is caused to flow from a relatively large portion of the incoming wave front, having the effect of absorbing energy from the wave front into the antenna from a wave front which is much larger than the geometrical area of the antenna."

While the concept of effective area may be known, implementing it in antenna design and construction is not easy or obvious. U.S. Pat. No. 5,296,866 teaches making active antennas that had effective areas greater than the geometric areas through use of special circuitry. The antennas detailed in this disclosure were non-planar coil antennas.

Co-pending U.S. patent application Ser. No. 09/951,031, the disclosure of which is expressly incorporated herein by reference, discloses an antenna on a chip having an effective area 300–400 times greater than its physical area. The effective area is enlarged through the use of an LC tank circuit formed through the distributed inductance and capacitance of a spiral conductor. This is accomplished through the use on the antenna of inter-electrode capacitance and inductance to form the LC tank circuit. This, without requiring the addition of discrete circuitry, provides the antenna with an effective area greater than its physical area. It also eliminates the need to employ magnetic film. As a result, the production of the antenna on an integrated circuit chip is facilitated, as is the design of ultra-small antennas on such chips. See also U.S. Pat. No. 6,289,237, the disclosure of which is expressly incorporated herein by reference.

The invention of this disclosure integrates the antenna and the circuitry of a wireless untethered device such as an integrated circuit (IC) chip or printed circuit board (PCB) to achieve an effective area that is greater than what would be expected from the antenna disposed on the chip alone. By "integrate" or "integration" it is meant that the antenna is disposed on the chip using the circuitry of the IC chip or PCB as part of the antenna function specifically the energy harvesting effective area. Integrating the antenna and proximate circuitry of the IC chip or PCB simplifies the design of the chip because placing the discrete antenna and proximate IC chip or PCB circuit components in discrete areas of the chip is no longer necessary.

In general, a preferred approach is to have the antenna designed as an integral element which is connected to the circuitry with proper impedance matching. If desired, the circuitry can be designed and then the antenna can be designed for maximum performance efficiency in the presence of the circuitry with particular emphasis of use in small, wireless untethered devices.

One advantage of integrating the antenna and the proximate circuitry of the IC chip or PCB is that the physical size of the antenna component is no longer the sole driving force in obtaining greater effective area. Using the embodiment of this invention, the effective area of the antenna is a combination of the physical size of the antenna and proximate IC circuitry on the IC chip or PCB. In essence, the antenna on the IC chip or PCB for all practical purposes is the whole IC chip or PCB and not a specific portion of IC chip or PCB that has the physical antenna disposed on it. It will be appreciated that in the IC chip, PCB or other embodiments the effective area of an antenna may be greater than the physical area of the IC chip, the PCB or other substrate. In fact, isolating the physical antenna into separate portions of the IC chip or PCB (i.e., peripheral or a distinct area of the central portion) can be detrimental to making IC chips or PCBs with effective areas greater than the effective area from the isolated physical antenna.

The design of an antenna on chip or PCB involves a number of sets of information; (1) frequency of operation (center frequency), (2) bandwidth at the half power points, (3) Q—ratio of peak performance to that of the half power points, (4) the electrical and magnetic properties along with thickness of each process layer—typically termed the technology files.

Given the appropriate design information, an architecture, e.g., whip, dipole, square spiral, round spiral, etc. is selected. Next, a range of parameters such as conductor length equal to wavelength (center frequency) divided by 4, resonance of the antenna at the center frequency, etc.

Using the resonance strategy, the antenna parameters and configuration are then adjusted to achieve resonance using the parasitic and inter-electrode inductance and capacitance including the electronic and magnetic properties as given in the technology files.

The resonance is normally checked through computer aided design software including simulation.

FIGS. **4***a* and **4***b* illustrate the test apparatus including; (A) two spiral energy harvesting antennas with circuitry for rectification and voltage "doubling" (charge pumps), (B) interconnection circuitry, and (C) the power, voltage measurement circuitry (power meter).

The measurement of power and/or voltage on a remote autonomous device is complicated by the inability to connect non-interfering wires to the device, and the fact that as the size of the device decreases, there is an inherent uncertainty concerning the effect/contribution of the measurement circuitry itself on the measurement. The effective area measurements in the Co-pending U.S. patent application Ser. No. 09/951,031, involved connecting wires in order to effect the power measurements.

A series of experiments were run with the device of FIG. **4***b* in the field of an RF source antenna at 915 MHz. In these experiments, a flat conducting surface (plane) was placed between the source antenna providing the RF energy and the device under test at an approximate distance of 0.25 inches from the device. Five conducting planes were used where the planes shielded areas of the device at the 5 heights shown in FIGS. **4***a* and **4***b*.

The height of 19.0 cm represents the height of the top of the device above the laboratory bench. The 5 heights of the conducting plane in the 5 experimental positions were 19.0 cm, 17.25 cm, 16.0 cm, 14.7 cm and 11.0 cm respectively. The points on the graph above the device in FIG. **4***a*, represents the number of LEDs lighted on the power meter section (C) of the device. The number of LEDs lighted is proportional to the voltage across the LEDs and represents a lower bound on the voltage dropped across the 1 K ohm resistor that can be seen in area (B**2**) of FIG. **4***b*.

As can be noted from the FIG. **4***a* graph, while exposing the strict antenna area (A**1**) to the RF field does in fact harvest sufficient energy to light **2** LEDs, exposing additional device area facilitates additional energy harvesting, including the power meter area (C).

It is noted that for the proximate electronics in (B**2**) and (C), the function of the circuitry is strictly DC including the DC bus noted in area (B**1**).

A functioning power meter (C) when totally removed from the device parts identified as (A) and (B) shows no lighted LEDs. Thus, as an energy harvesting device, the power meter by itself will not harvest sufficient energy to light a single LED. However, when connected to the device, the area and circuitry contribute to the energy harvesting by an amount of 74.9 milliwatts in terms of measured power and sufficient voltage to light an LED.

In FIGS. **4***a* and **4***b,* the conducting planes were introduced in the sequence 19.0 cm, 17.25 cm, 16.0 cm 14.7 cm and 11.0 cm. The results of a similar experiment with the sequence of conducting planes were introduced in the sequence 17.25 to 19.0 cm, 16.0 to 19.0 cm, 14.7 to 19.0 cm 11.0 to 19.0 cm and 0 to 19.0 cm, respectively.

While no mathematical model is proposed for the results of FIGS. **4** and **5**, it is obvious that the proximate interconnections (B) and circuitry (A**2**) contribute to the total amount of energy harvested by increasing the effective area of the harvesting antennas.

It is clear that more than one factor contributes to the effectiveness of the antenna/device combination in harvesting energy. We have chosen to note the effective area do to the results of Rudenberg as Rudenberg effective area, and the remainder of the effective area due to components and interconnections as proximate effective area.

The present invention is concerned with the design and analysis of small antennas for the purpose of harvesting energy on a printed circuit board (PCB) or a complementary metal oxide semiconductor (CMOS) die in order to provide power to on board circuitry without the need for batteries or external connections as a source of power.

Earlier design of such devices has led to the desire to use a square spiral coil as the profile for the antenna. Thus, this disclosure will be mostly concerned with the square spiral antenna although a patch design will be included from time to time.

Given the square spiral profile, there are still many parameters of the design that must be considered and chosen. This disclosure is concerned with a series of experiments that were run in an effort to evaluate these alternatives using PCB implementations. However, the ultimate goal is to implement the square spiral on a CMOS die thus opening up the question of what differences in performance can be expected with the CMOS implementation.

The approach to the analysis is strictly empirical although a few references may be made to classical approaches either to antennas or electronic circuits. The sole purpose is given a square spiral implementation, what are the parameters values that provide the greatest amount of power or energy at the payload circuitry in this case a 10 K ohm resistor.

Printed circuit test boards each containing a target antenna have been constructed where the voltage across the target load is measured by an analog to digital converter, frames and transmitted by an infra red transmitter to a receiver connected to a data gathering personal computer. The test/measurement circuitry is powered by a small battery. All test/measurement circuitry and the battery are located behind a ground plane for the circuitry so as to shield the circuitry from an energizing radio frequency (RF) source whereby a contribution to the power/energy can be attributed to this circuitry.

Other research has demonstrated that the proximate circuitry can be used to advantage in harvesting energy.

Previous attempts to measure the energy harvested by small antennas have been complicated due to the measurement equipment that is connected to the device under test (DUT). Thus, the attempt here is to include the test circuitry directly on the DUT. As indicated previously, the circuitry included with the DUT can have an effect on the results thus leading to the shielding of the test circuitry behind a conducting plane as shown in FIGS. **6***a*–**6***d*.

Over many decades it has been difficult if not impossible to prove that the test circuitry does not have an effect on the results of the experiment, the results reported in this paper suggest that the effect is minimal through some of the profiles of the DUT, e.g., antenna area as shown in FIGS. **6***a*–**6***d* for antennas A through D.

The design of antennas in a limited space such as on a printed circuit board or a Complementary Metal Oxide Semiconductor (CMOS) chip or die requires the consideration of a number of physical factors of the antenna to obtain an optimum performance. These factors include:

(1) The area allocated to the antenna including the actual metallic conductor forming the antenna and any space required to form or shape the metallic conductor. The metallic conductor has certain characteristics, e.g., shape (profile), conductor width, conductor thickness, and conductor length.

(2) One of the profiles considered in this research is a square spiral. The topological nature of the square spiral is that connection can be made in the plane of the antenna from the last outside trace of the spiral. Such a connection will be noted as a micro-strip line feed. The inner end of the spiral must be connect through a via to another layer of the PCB or CMOS die. Such a connection will be noted as a probe feed. Two general profiles are considered in the research reported herein, a square spiral and a square patch.

(3) The antenna environment includes any form of conductor, insulator, etc., that exist between the source of the radio frequency (RF) energy and the antenna or behind the antenna. One form of element can be a ground plane formed as a part of the PCB or CMOS die.

(4) The antenna is connected to a circuit (energy harvesting in this case) where both the antenna and the circuit (load) have an impedance. For optimum performance, it has long been held that the two impedances should be matched as complex conjugates, i.e., impedance matching, with equal real (resistance) components.

(5) There are two areas involved in the antenna design. The first is the physical area required to implement the antenna. The second is the effective area resulting from dividing the power received at the load by the power density in the field in which the antenna is place, i.e., Power Harvested=Power density*Effective Area.

In summary, the factors involved in the design of an antenna in a limited space, e.g., a PCB or a CMOS die are:

(A) Physical Area
(B) Profile
(C) Antenna Conductor Width
(D) Antenna Conductor Thickness
(E) Antenna Conductor Length
(F) Feed Type
(G) Ground Plane Existence
(H) Impedance Matching

(A) Physical Area

Four antennas of a square profile with four different areas as illustrated in FIGS. **6***a*–**6***d,* have been constructed. The voltage response measured at the load of the four antennas in shown in FIG. **2**. The antennas are compared at a harvesting distance of 50 centimeters by plotting the voltage harvested at the load as shown in FIG. **7**. Based on the results of FIG. **8**, it is clear, as expected, that the amount of energy harvested increases with increased area. This area is termed the physical area.

(B) Profile

Two profiles are considered in this study, a square spiral and a square patch. FIGS. **9***a*–**9***e* illustrate five antennas, four of which are square spirals and one is a square patch (Antenna D, Board H**1**).

The voltage results for the profile test cases are illustrated in FIG. **10**. It can be argued from FIG. **10** that the best results are obtained with the square patch. The differences are not great, but there are differences. However, the square patch has a disadvantage in that the impedance for impedance matching requires an inductor as the patch has a capacitive impedance. In addition, the impedance of the antenna is fixed by the physical area. In the case of the square spiral antennas, the impedance of the antenna may be varied while maintaining a fixed physical area. In the case of the square patch, the matching requires an inductor that is difficult to fabricate on a CMOS die and not easy to precisely match with an on die inductor or a discrete inductor for the PCB implementation. The inductor is required to form the complex conjugate as the square patch is capacitive.

The square spiral can be modified by trace width, thickness and relative spacing to have essentially a continuum of impedances many of which are illustrated in FIG. **11**. This variation is particularly useful in coordinating the matching impedance between the load and the antenna. Thus, from a design standpoint, the square spiral is the profile of choice.

Antenna E in FIG. **9***e,* while a square spiral, has length greater that the ¼× length of Antennas A, B, and C. The length of antenna E is greater than ¾×. Thus, the length of the antenna conductor is a factor in designing the most efficient PCB or die (chip) antenna. While the ¼× length is better for design purposes as the added length does not gain any appreciable advantage, this does not constitute a proof for the optimum length. The major contribution here is that the antenna conductor length is a factor that must be considered in the antenna design.

(C) Antenna Conductor Width

The antennas A, B and C of FIGS. **9***a*–**9***c* vary in trace width. Based on the results of FIG. **10**, the trend lines are shown in FIG. **12**.

From FIG. **12**, the slope, i.e., rate of voltage decrease is the least for antenna B. In addition, the trend line for antenna B has the largest y intercept. Both of these results support antenna B with the narrowest trace width as being the optimum for this set of experiments.

(D) Antenna Conductor Thickness

Two independent experiments were run for antenna thickness. The first began with one of the type A antennas to which additional conducting solder was first added and then some of the added solder was removed. This gave an original thickness, a much thicker trace and thirdly a trace of intermediate thickness. These steps produced three different thicknesses of the antenna conductor thicknesses indicated in FIG. **13***a*.

Using another set of independent boards and steps, all solder was removed from the antenna exposing the bare copper giving the thinnest trace thickness. The copper was then electroplated onto the antenna to give different thicknesses of copper and thus three different values of antenna conductor thicknesses as indicated in FIG. **13***b*. The measured results for both lead and copper additions are illustrated in FIGS. **13***a*–**13***b*.

Based on the results shown in FIGS. **14***a*–**14***b*, it is quite clear that the best energy harvesting, highest voltage levels, is accomplished antenna conductor thickness is the thinnest. The results of the two thicker traces in FIG. **14***a* are very close and no conclusion should be drawn solely with respect to these two antennas. The removal of the solder from the thickest trace caused a minor amount of melting of the solder having a minimal effect on the antenna profile. However, these two thicknesses relative to the thinnest trace thickness can be considered significant.

(E) Antenna Conductor Length

The antenna conductor length results can be observed considering FIGS. **9***a*–**9***e* and **10**. While there does appear to be some equivalence in the results of antenna B and antenna E in FIG. **19**, the results at the 50 centimeter distance was chosen as the point of comparison show that nothing significant is gained by the additional length. In fact, the length is definitely less useful when compared to antennas A and C. Thus it is an initial conclusion that the primary criterion for the antenna to minimize area and maximize the amount of energy harvested that the length by held at or near ¼ wavelength.

FIG. **15***a*. is the trend line for Antenna B, and FIG. **15***b* is the trend line for Antenna E. In comparing B and E, the rate of drop off for E is greater and E also has a lower y intercept

There is perhaps another significant point in comparing the two antennas B and E. From a -traditional antenna design standpoint, it could be argued that the two antennas should have performances with more significant differences than are shown in these results.

The explanation offered here is that the most significant feature of the small antennas is the fact that there exists a resonant tank disturbing the field which modified the effective area of the antenna. Thus, these two antennas of significantly different lengths produce similar results supporting the notion that the resonant tank circuit is the most significant aspect of the small antenna.

(F) Feed Type

FIGS. **16***a*–**16***b* provide an illustration of the two type of feed from the antenna, i.e., (a) the micro-strip line feed and (b) the probe feed.

The voltage results of the two type of line feeds are shown in FIG. **17** where it is quite clear that the preferred type of connection to the antenna is the micro-strip line feed.

(G) Ground Plane Existence

In many applications of different antenna profiles such as a patch, it is desirable to provide a ground plane that is separated from the antenna by a distance that can be calculated based on the dielectric constant of the medium between the ground plane and the antenna. However, it the case of a PCB or CMOS die implementation, the distance between the antenna and the potential location of the ground plane and the dielectric constant of the intervening medium are both fixed by the process independent of the antenna design. Thus, as a rule, the resulting ground plane is not located at the proper position for the fixed dielectric, or the dielectric is incorrect for the position of the ground plane.

The current PCB experiments included provisions for testing the ground plane existence and the net effect of some form of a ground plane in the proximity of the antenna. Two types of ground plane experiments are illustrated in FIGS. **18***a*–**18***b*. The first is a conventional ground plane directly behind the antenna, and the second is a ground plane in the proximity of the antenna on the opposite side of the PCB. The corresponding voltage measurements for the case of FIG. **18***a* are shown in FIG. **19**. The results for the three cases illustrated in FIG. **18***b* were indistinguishable.

Based on FIGS. **18***a*–**18***b*, it is clear that the ground plane is not a desirable feature for the PCB implementation. As a curious note, it would be possible to find an antenna/frequency combination for which the ground plane could lead to an advantage. However, such a result would not be practical in view of the restrictions on frequency both from regulatory and power/energy considerations.

As noted previously, the results for the three different sized ground planes illustrated in FIG. **18***b* were indistinguishable. However, the optimum voltage present in all three cases was the result of different physical impedance matching of the three antennas. Thus, while the proximate ground planes of FIG. **18***b* do not affect antenna performance, they do provide an affect on the antenna and feed line impedances.

The conclusion here is that in general, it is not desirable to include a ground plane for a PCB or CMOS die type of antenna. In additional a physical ground effect object in the proximate area may be useful in achieving a certain impedance or impedance match.

(H) Impedance Matching

As indicated previously, it is in general desirable to match the impedance of the antenna to the impedance of the load as complex conjugates. However, in the case of the use of an antenna for the sole purpose of energy harvesting, there is reason to believe that another form of matching or designed mismatching may not be of an advantage. Consider the model of an energy harvesting antenna as shown in FIG. **20**. As reported by Rudenberg, the antenna forms a non-ideal tank that has a nonzero resistance. This resistance results in a retransmission of some of the incoming energy that in turn interferes with the transmitted field resulting in an increased effective area of the antenna.

As a result of this research, it is conjectured that an additional amount of retransmitted energy may be of an advantage in disturbing the field to provide an even larger effective area. It is recognized that this increased effective area is not without limit.

The Rudenberg retransmitted energy is a function of the resistance R shown in the tank circuit of FIG. **20**. We conjecture that in addition, the intentional mismatch of the impedance Z of FIG. **20** can result in increased effective area.

The effective area increase by the resistor, R, of the tank in FIG. **20**, will be referred to as the Rudenberg effective area. The increased effective area caused by the mismatch of Z and the resulting reflected energy from the load is termed the proximate effective area.

The net effect of these two effective area contributions is modeled as two voltage sources just below the ideal antenna symbol of FIG. **20**.

These two features contributing to the effective area are highlighted in FIG. **21**.

The basis of the conjecture on the mismatch of the impedance Z resulting in reflected energy from the load is arrived at from the repeated attempts to correlate the simulated results for impedance matching with the experimental results found when actually choosing an impedance to increase the harvested energy/voltage experimentally. The results of the simulation and experimental impedance matching are shown in FIGS. **22** and **23**.

FIG. **22** represents the compiled voltage results with many different values of impedance used to obtain the most effective match through an organized searching procedure. The N/S/E/W cross of FIG. **22** represents the centroid of the four best matches that could be achieved by physical matching using electronic elements.

FIG. **23** represents the compiled values of matched impedance along with color coding for strength. The cross of FIG. **23** represents the centroid of the four best matches for the simulations. It is important to note that the simulation may obviously in general not represent the actual circuit due to minute differences that are extremely hard to model. However, numerous attempts were made to calibrate the simulation based on the model and the corresponding test results. However, none of these was successful.

Thus, at this time, the difference in the simulated matching of FIG. **23** based on the complex conjugate impedances and the actual best match in the physical tests is attributed to the mismatching of the impedance z in FIG. **21**. There would be a limit on the effectiveness of this mismatch.

As pointed out previously, the two voltage sources shown in FIGS. **22** and **23** immediately below the ideal antenna symbol are attributed to the retransmission of the energy as a result of the R in the non-ideal tank and the reflected energy from the load due to the mismatch of the impedance Z.

CONCLUSIONS

One of the important aspects of this research is the ability to empirically evaluate the feasibility of certain results that require much additional research other than the antenna. For example, consider a system on a chip (SOC) implementation that requires other circuitry to be designed that will in turn be powered by the energy harvesting technology being discussed here. A considerable amount of work may be required to develop the payload circuitry, and it is desired to have some idea of what level of power can be achieved.

FIG. **8** gives the trend line for the harvested voltage across a 10K ohm load. Therefore, with an antenna that is 1.58 mm on a side, the power that can be expected to be harvested with the thickness of antenna A is:

Power={[*O*.5918*(1.582)*J*0~~85]2}/104=80 *j.t* watts

However, based on the narrower and thinner trace, the voltage can be expected to be at least doubled. This would result in:

Power={[2*0.591 8*(1.582)]04485]2}/104=178 *j.i* watts

The results appear to show that the highest voltage is achieved with a narrower and thinner conductor trace. This is not unexpected from the energy harvesting scenario. At the frequencies involved, the current tends to flow on the outside surface with possible eddy current flowing in the interior that will contribute losses.

Consider reducing only the width of the traces. The PCB traces are on the order of 700 to 1300 microns. A plot of the data for the slope in the linear fall off(y=−Mx+ b, M is the linear fall off or slope of the trend line) as shown in FIG. **7** for antennas A, B and C is shown in FIG. **24***a*.

The point of this discussion is solely to see the fall off rate for the harvested energy as the antenna trace pattern is reduced in width. The trend lines of FIG. **10**, for example, have both a slope and a y intercept, M and b in the above equation for y. The discussion here concerns solely the slope, M, of the trend line. The y intercept appears to be primarily a function of the antenna area and is outside this current discussion.

Based on the projection shown in FIG. **24***b*, the fall off rate in energy is, −0.0328, compare with, −0.0421, for Antenna B as the antenna trace width is reduced to 25 microns.

Thus, based solely on the projection in FIG. **24***b*, the rate improvement of the fall off in going to a CMOS die from a PCB implementation is about 22%. Therefore, in general, it can be expected that the deterioration in performance for a CMOS die will be much better (less per unit distance) than a PCB implementation as the distance between the source and device increases.

An example of the effect of this difference can be seen in FIG. **25**, assuming the intercept point that would make the harvested voltages at 50 centimeters to be the same.

Another interesting look at the projections in going from PCB antennas to those of a CMOS die can be obtained by considering the thickness results from FIG. **13***b*. The results of the decrease in thickness are shown below in FIG. **26***a*. Based on the trend line fitted to these data points, an extrapolation to approximately 1 micron is shown in FIG. **26***b*. f it can be assumed that both the PCB and the CMOS die have the same value at say 50 centimeters, it can be conjectured that the break point as shown in FIG. **14***b*, can be extended to 13,600 centimeters or 446 feet.

Obviously the simple extension to 446 feet from 70 centimeters is difficult to defend. The point here is that there are certain of the parameters in the design of the antenna that must be taken into account that provide direction into the experimental development that will eventually produce a working result although the theory as to why may be delayed by a considerable time.

There is no suggestion, other than the extrapolation, that the 446 feet can be achieved. This result is for copper, and most current fabrications are done with aluminum.

One major conclusion of these results is that the transition from a PCB implementation to a CMOS die need not be considered to be an unfavorable transition.

The primary reduction in the PCB to CMOS die transition is the attendant desire to reduce area because of the relative cost of a PCB compared to a CMOS die per unit (equivalent) area.

All of the previous results were obtained with the antennas in the same orientation with respect to the source antenna. In order to evaluate the orientation issue, FIG. **27** shows six orientations that were tested.

The voltage as a function of distance curves for the six configurations are shown in FIG. **28**. Obviously, the most favorable positions are positions **1** and **2**. Position **1** is the position that was used for all of the previous results. The two orientations, **5** and **6**, are included for the sake of completeness. However, these two are not at all favorable. One reason for their inclusion was that these two were quite favorable in the early tests on the Delta **1** CMOS antenna. At this time there has been no attempt to discover why the PCB and CMOS results for the horizontal antenna appear to be different.

The trend lines for the curves of FIG. **28** are given in FIG. **29**. From the trend lines, position **1** is the best in terms of the y intercept. However, the fall-off rate for position **2** is the best for the two positions. If we consider the longest distance for a typical PIC microcontroller to function based on 2.5 volts, Position **2** yields 90.8 centimeters and Position **1** yields 89.1 centimeters. These two results are extremely close based on the trend lines.

The negative slope and the y intercept of the trend lines is shown below in FIG. **30**. The angle shown along the abscissa is the feed line of the micro-strip type feed where the angle is from the feed line in the direction of the load circuitry. In FIG. **27**, P**4** is 0 degrees, P**2** is 90 degrees, P**4** is 180 degrees, and P**1** is 270 degrees.

Based on the results reported here, the conclusions are summarized as follows:

1. Impedance matching is essential but does not guarantee optimum performance for a fixed area of a small antenna
2. A ¼ wavelength antenna appears to be the optimum antenna for a fixed area
3. The area appears to be the most important factor—given 1 and 2
4. The spiral antenna profile is preferred because it is much easier to match impedances
5. The narrowest trace (width) appears to be optimum
6. The thinnest trace (height) appears to be optimum
7. Increased conductor length does not appear to offer any benefit for energy harvesting
8. The micro-strip line feed is superior to the probe feed
9. There should be no ground plane under the antenna
10. The square spiral is preferred to the square patch based on impedance matching considerations
11. Both tank resistance and reflected load power due to mismatched impedances appear to increase the effective area of the small antenna

While for convenience of disclosure primary attention has been directed toward use of the preferred embodiments of the invention which employ IC chips or printed circuit boards, the invention may also be employed advantageously in connection with other substrates in wireless untethered devices.

Whereas particular embodiments of the invention have been disclosed herein for purposes of illustration, it will be evident to those skilled in the art that numerous variations of the details may be made without departing from the invention as set forth in the appended claims.

The invention claimed is:

1. A wireless untethered device comprising:

at least one antenna;

circuitry operatively associated with said antenna for receipt of energy harvested by said antenna from space, said circuitry being structured to convert said energy to direct current; and

a system structured to be energized by the direct current from said circuitry, said system and said circuitry having an impedance mismatch with respect to said antenna wherein said antenna, said circuitry and said system together form an integrated antenna and wherein said antenna has an effective area greater than its physical area.

2. The wireless untethered device of claim **1** including

said wireless untethered device being selected from the group consisting of an integrated circuit chip and a printed circuit board.

3. The wireless untethered device of claim **1** including

said wireless untethered device being an integrated circuit chip.

4. The integrated circuit chip of claim **3** including

said antenna being integrally formed on said chip.

5. The integrated circuit chip of claim **4** including

said antenna structured to receive RF energy and deliver it to said circuitry.

6. The integrated circuit chip of claim **4** including

a second integral antenna for transmitting data.

7. The integrated circuit chip of claim **4** including

said antenna being a spiral antenna.

8. The integrated circuit chip of claim **7** including

said spiral antenna being a square spiral.

9. The integrated circuit chip of claim **3** including

said circuitry having a tank circuit for increasing the effective area of said antenna.

10. The integrated circuit chip of claim **5** including

said antenna having a length of about ¼ wavelength of said RF energy.

11. The integrated circuit chip of claim **3** including

a micro-strip feed line connected to said antenna.

12. The integrated circuit chip of claim **3** including

said circuitry having a non zero resistance which results in retransmission of some of said energy to thereby interfere with transmitted energy and increase the effective area of said antenna.

* * * * *

UNITED STATES PATENT AND TRADEMARK OFFICE

CERTIFICATE OF CORRECTION

PATENT NO. : 7,057,514 B2 Page 1 of 2
APPLICATION NO. : 10/857527
DATED : October 5, 2004
INVENTOR(S) : Marlin H. Mickle, Christopher C. Capelli and Harold Swift

It is certified that error appears in the above-identified patent and that said Letters Patent is hereby corrected as shown below:

Column 4, line 46, “tern” should be changed to --term--.

Column 8, line 30, “do” should be changed to --due--.

Column 8, line 57, “what” should be changed to --that--.

Column 9, line 56, “place” should be changed to --placed--.

Column 10, line 5, “in” should be changed to --are--.

Column 10, line 39, “that” should be changed to --than--.

Column 11, line 11, the word “where” should be inserted after the word --accomplished--.

Column 11, line 60, “it” should be changed to --in--.

Column 11, line 48, “type” should be changed to --types--.

Column 11, line 51, “type” should be changed to --types--.

Column 12, line 24, “affect” should be changed to --effect--.

Column 12, line 28, “additional” should be changed to --addition,--.

UNITED STATES PATENT AND TRADEMARK OFFICE

CERTIFICATE OF CORRECTION

PATENT NO.	: 7,057,514 B2	Page 2 of 2
APPLICATION NO.	: 10/857527	
DATED	: October 5, 2004	
INVENTOR(S)	: Marlin H. Mickle and Christopher C. Capelli and Harold Swift	

It is certified that error appears in the above-identified patent and that said Letters Patent is hereby corrected as shown below:

Column 12, line 32, “in general” should be changed to --generally--.

Column 14, line 29, “f” should be changed to --If--.

IN THE FIGURES

FIGS. 7, 19 and 28, “te” should be changed to --the--.

Signed and Sealed this

Fourteenth Day of November, 2006

Jon W. Dudas

JON W. DUDAS

Director of the United States Patent and Trademark Office

UNITED STATES PATENT AND TRADEMARK OFFICE

CERTIFICATE OF CORRECTION

PATENT NO. : 7,057,514 B2

APPLICATION NO. : 10/857527
DATED : June 6, 2006
INVENTOR(S) : Marlin H. Mickle, Christopher C. Capelli and Harold Swift

It is certified that error appears in the above-identified patent and that said Letters Patent is hereby corrected as shown below:

Column 4, line 46, “tern” should be changed to --term--.

Column 8, line 30, “do” should be changed to --due--.

Column 8, line 57, “what” should be changed to --that--.

Column 9, line 56, “place” should be changed to --placed--.

Column 10, line 5, “in” should be changed to --are--.

Column 10, line 39, “that” should be changed to --than--.

Column 11, line 11, the word “where” should be inserted after the word --accomplished--.

Column 11, line 60, “it” should be changed to --in--.

Column 11, line 48, “type” should be changed to --types--.

Column 11, line 51, “type” should be changed to --types--.

Column 12, line 24, “affect” should be changed to --effect--.

Column 12, line 28, “additional” should be changed to --addition,--.

UNITED STATES PATENT AND TRADEMARK OFFICE

CERTIFICATE OF CORRECTION

PATENT NO. : 7,057,514 B2 Page 2 of 2
APPLICATION NO. : 10/857527
DATED : June 6, 2006
INVENTOR(S) : Marlin H. Mickle and Christopher C. Capelli and Harold Swift

It is certified that error appears in the above-identified patent and that said Letters Patent is hereby corrected as shown below:

Column 12, line 32, “in general” should be changed to --generally--.

Column 14, line 29, “f” should be changed to --If--.

IN THE FIGURES

FIGS. 7, 19 and 28, “te” should be changed to --the--.

This certificate supersedes Certificate of Correction issued November 14, 2006.

Signed and Sealed this

Second Day of January, 2007

Jon W. Dudas

JON W. DUDAS
Director of the United States Patent and Trademark Office

US007439712B2

(12) **United States Patent**
McCowen

(10) **Patent No.: US 7,439,712 B2**
(45) **Date of Patent: Oct. 21, 2008**

(54) **ENERGY COLLECTION**

(76) Inventor: **Clint McCowen**, 1902 Rue La Fontaine, Navarre, FL (US) 32566

(*) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 509 days.

(21) Appl. No.: **11/358,264**

(22) Filed: **Feb. 21, 2006**

(65) **Prior Publication Data**

US 2007/0195481 A1 Aug. 23, 2007

(51) **Int. Cl.**
H02N 1/00 (2006.01)

(52) **U.S. Cl.** .... **322/2 A**; 307/149; 361/225; 361/117; 174/2; 320/101

(58) **Field of Classification Search** .... 361/220, 361/117, 212, 233, 221, 222, 225; 322/2 A, 322/2 R; 307/149; 174/2, 3; 320/101
See application file for complete search history.

(56) **References Cited**

U.S. PATENT DOCUMENTS

674,427 A * 5/1901 Palencsar 307/149
911,260 A * 2/1909 Pennock 307/149
1,014,719 A * 1/1912 Pennock 307/149
4,104,696 A 8/1978 Cochran, Jr.
5,047,892 A 9/1991 Sakata et al.
6,735,830 B1 5/2004 Merciel
6,974,110 B2 12/2005 Grandics
2003/0107869 A1 6/2003 Pan et al.
2004/0160711 A1 8/2004 Stumberger
2004/0212945 A1 10/2004 Sprenger et al.

* cited by examiner

Primary Examiner—Mark T Le
(74) *Attorney, Agent, or Firm*—Thomas, Kayden, Horstemeyer & Risley, LLP

(57) **ABSTRACT**

An energy collection system may collect and use the energy generated by an electric field. Collection fibers are suspended from a support wire system supported by poles. The support wire system is electrically connected to a load by a connecting wire. The collection fibers may be made of any conducting material, but carbon and graphite are preferred. Diodes may be used to restrict the backflow or loss of energy.

28 Claims, 10 Drawing Sheets


100
120
130
140
110
110
110
110
110
150


240
200
260
130
250
270


910
SUSPEND COLLECTION FIBER FROM SUPPORT STRUCTURE WIRE
920
CONNECT LOAD TO SUPPORT STRUCTURE WIRE
930
CONNECT DIODE BETWEEN SUPPORT STRUCTURE WIRE AND LOAD
940
STORE ENERGY PROVIDED TO LOAD



FIGURE 1


100
110
120
110
130
110
110
150
140

FIGURE 2



FIGURE 2A



FIGURE 2B


200
250
260
270
240
130

FIGURE 2C


278
275
200
130

FIGURE 2D


200
280
130
285

FIGURE 2E

FIGURE 2F




200
292
294
130

FIGURE 2G


300
310
330
320
340
150

FIGURE 3


400
310
440
410
420
450
430
150

FIGURE 4

FIGURE 5


310
500
510
520
150

FIGURE 6


310
600
610
620
630
640

FIGURE 7


310
700
720
150


800
From Collectors
810
820
825
830
150
870

FIGURE 8


910
SUSPEND COLLECTION FIBER FROM SUPPORT STRUCTURE WIRE
920
CONNECT LOAD TO SUPPORT STRUCTURE WIRE
930
CONNECT DIODE BETWEEN SUPPORT STRUCTURE WIRE AND LOAD
940
STORE ENERGY PROVIDED TO LOAD

FIGURE 9

ENERGY COLLECTION

TECHNICAL FIELD

The present disclosure is generally related to energy and, more particularly, is related to systems and methods for collecting energy.

BACKGROUND

The concept of fair weather electricity deals with the electric field and the electric current in the atmosphere propagated by the conductivity of the air. Clear, calm air carries an electrical current, which is the return path for thousands of lightening storms simultaneously occurring at any given moment around the earth. For simplicity, this energy may be referred to as static electricity or static energy. FIG. **1** illustrates a weather circuit for returning the current from lightning, for example, back to ground **10**. Weather currents **20**, **30** return the cloud to ground current **40**.

In a lightening storm, an electrical charge is built up, and electrons arc across a gas, ionizing it and producing the lightening flash. As one of ordinary skill in the art understands, the complete circuit requires a return path for the lightening flash. The atmosphere is the return path for the circuit. The electric field due to the atmospheric return path is relatively weak at any given point because the energy of thousands of electrical storms across the planet are diffused over the atmosphere of the entire Earth during both fair and stormy weather. Other contributing factors to electric current being present in the atmosphere may include cosmic rays penetrating and interacting with the earth's atmosphere, and also the migration of ions, as well as other effects yet to be fully studied.

Some of the ionization in the lower atmosphere is caused by airborne radioactive substances, primarily radon. In most places of the world, ions are formed at a rate of 5-10 pairs per cubic centimeter per second at sea level. With increasing altitude, cosmic radiation causes the ion production rate to increase. In areas with high radon exhalation from the soil (or building materials), the rate may be much higher.

Alpha-active materials are primarily responsible for the atmospheric ionization. Each alpha particle (for instance, from a decaying radon atom) will, over its range of some centimeters, create approximately 150,000-200,000 ion pairs.

While there is a large amount of usable energy available in the atmosphere, a method or apparatus for efficiently collecting that energy has not been forthcoming. Therefore, a heretofore unaddressed need exists in the industry to address the aforementioned deficiencies and inadequacies.

SUMMARY

Embodiments of the present disclosure provide systems and methods for collecting energy. Briefly described in architecture, one embodiment of the system, among others, can be implemented by a support structure wire elevated above a ground level, at least one collection fiber electrically connected to the support structure wire; a load electrically connected to the support structure wire; and a diode electrically connected between the load and at least one collection fiber.

Embodiments of the present disclosure can also be viewed as providing methods for collecting energy. In this regard, one embodiment of such a method, among others, can be broadly summarized by the following steps: suspending at least one collection fiber from a support structure wire elevated above ground level, the fiber electrically connected to the support structure wire; providing a load with an electrical connection to the support structure wire to draw current; and providing a diode electrically connected between the collection fiber and the load.

Other systems, methods, features, and advantages of the present disclosure will be or become apparent to one with skill in the art upon examination of the following drawings and detailed description. It is intended that all such additional systems, methods, features, and advantages be included within this description, be within the scope of the present disclosure, and be protected by the accompanying claims.

BRIEF DESCRIPTION OF THE DRAWINGS

Many aspects of the disclosure can be better understood with reference to the following drawings. The components in the drawings are not necessarily to scale, emphasis instead being placed upon clearly illustrating the principles of the present disclosure. Moreover, in the drawings, like reference numerals designate corresponding parts throughout the several views.

FIG. **1** is a circuit diagram of a weather energy circuit.

FIG. **2** is a perspective view of an exemplary embodiment of many energy collectors elevated above ground by a structure.

FIG. **2**A is a side view of an energy collection fiber suspended from a support wire.

FIG. **2**B is a side view of an exemplary embodiment of an energy collection fiber suspended from a support wire and with an additional support member.

FIG. **2**C is a perspective view of a support structure for multiple energy collection fibers.

FIG. **2**D is a side view of an exemplary embodiment of a support structure for multiple energy collection fibers.

FIG. **2**E is a side view of a support structure for an energy collection fiber.

FIG. **2**F is a side view of an exemplary embodiment of a support structure for an energy collection fiber.

FIG. **2**G is a side view of a support structure for multiple energy collection fibers.

FIG. **3** is a circuit diagram of an exemplary embodiment of a circuit for the collection of energy.

FIG. **4** is a circuit diagram of an exemplary embodiment of a circuit for the collection of energy.

FIG. **5** is a circuit diagram of an exemplary embodiment of an energy collection circuit for powering a generator and motor.

FIG. **6** is a circuit diagram of an exemplary embodiment of a circuit for collecting energy and using it for the production of hydrogen and oxygen.

FIG. **7** is a circuit diagram of an exemplary embodiment of a circuit for collecting energy, and using it for driving a fuel cell.

FIG. **8** is a circuit diagram of an exemplary embodiment of a circuit for collecting energy.

FIG. **9** is a flow diagram of an exemplary embodiment of collecting energy with a collection fiber.

DETAILED DESCRIPTION

Electric charges on conductors reside entirely on the external surface of the conductors, and tend to concentrate more around sharp points and edges than on flat surfaces. Therefore, an electric field received by a sharp conductive point may be much stronger than a field received by the same charge residing on a large smooth conductive shell. An exemplary embodiment of this disclosure takes advantage of this property, among others, to collect and use the energy generated by an electric field in the atmosphere. Referring to collection system **100** presented in FIG. **2**, at least one collection device **130** may be suspended from a support wire system **120** supported by poles **110**. Collection device **130** may comprise a diode or a collection fiber individually, or the combination of a diode and a collection fiber. Support wire system **120** may be electrically connected to load **150** by connecting wire **140**. Supporting wire system **120** may be any shape or pattern. Also, conducting wire **140** may be one wire or multiple wires. The collection device **130** in the form of a fiber may comprise any conducting or non-conducting material, including carbon, graphite, Teflon, and metal. An exemplary embodiment utilizes carbon or graphite fibers for static electricity collection. Support wire system **120** and connecting wire **140** can be made of any conducting material, including aluminum or steel, but most notably, copper. Teflon may be added to said conductor as well, such as non-limiting examples of a Teflon impregnated wire, a wire with a Teflon coating, or Teflon strips hanging from a wire. Conducting wire **120**, **140**, and **200** may be bare wire, or coated with insulation as a non-limiting example. Wires **120** and **140** are a means of transporting the energy collected by collection device **130**.

An exemplary embodiment of the collection fibers as collection device **130** includes graphite or carbon fibers. Graphite and carbon fibers, at a microscopic level, can have hundreds of thousands of points. Atmospheric electricity may be attracted to these points. If atmospheric electricity can follow two paths where one is a flat surface and the other is a pointy, conductive surface, the electrical charge will be attracted to the pointy, conductive surface. Generally, the more points that are present, the higher energy that can be gathered. Therefore, carbon, or graphite fibers are examples that demonstrate exemplary collection ability.

In at least one exemplary embodiment, the height of support wire **120** may be an important factor. The higher that collection device **130** is from ground, the larger the voltage potential between collection device **130** and electrical ground. The electric field may be more than **100** volts per meter under some conditions. When support wire **120** is suspended in the air at a particular altitude, wire **120** will itself collect a very small charge from ambient voltage. When collection device **130** is connected to support wire **120**, collection device **130** becomes energized and transfers the energy to support wire **120**.

A diode, not shown in FIG. **2**, may be connected in several positions in collection system **100**. A diode is a component that restricts the direction of movement of charge carriers. It allows an electric current to flow in one direction, but essentially blocks it in the opposite direction. A diode can be thought of as the electrical version of a check valve. The diode may be used to prevent the collected energy from discharging into the atmosphere through the collection fiber embodiment of collection device **130**. An exemplary embodiment of the collection device comprises the diode with no collection fiber. A preferred embodiment, however, includes a diode at the connection point of a collection fiber to support system **120** such that the diode is elevated above ground. Multiple diodes may be used between collection device **130** and load **150**. Additionally, in an embodiment with multiple fibers, the diodes restricts energy that may be collected through one fiber from escaping through another fiber.

Collection device **130** may be connected and arranged in relation to support wire system **120** by many means. Some non-limiting examples are provided in FIGS. **2A-2G** using a collection fiber embodiment. FIG. **2A** presents support wire **200** with connecting member **210** for collection device **130**. Connection member **210** may be any conducting material allowing for the flow of electricity from connection device **130** to support wire **200**. Then, as shown in FIG. **2**, the support wire **200** of support system **120** may be electrically connected through conducting wire **140** to load **150**. A plurality of diodes may be placed at any position on the support structure wire. A preferred embodiment places a diode at an elevated position at the connection point between a collection fiber embodiment of collection device **130** and connection member **210**.

Likewise, FIG. **2B** shows collection fiber **130** electrically connected to support wire **200** and also connected to support member **230**. Support member **230** may be connected to collection fiber **130** on either side. Support member **230** holds the fiber steady on both ends instead of letting it move freely. Support member **230** may be conducting or non-conducting. A plurality of diodes may be placed at any position on the support structure wire. A preferred embodiment places a diode at elevated position at the connection point between collection fiber **130** and support wire **200** or between fiber **130**, support member **230**, and support wire **200**.

FIG. **2C** presents multiple collection fibers in a squirrel cage arrangement with top and bottom support members. Support structure **250** may be connected to support structure wire **200** by support member **240**. Structure **250** has a top **260** and a bottom **270** and each of the multiple collection fibers **130** are connected on one end to top **260** and on the other end to bottom **270**. A plurality of diodes may be placed at any position on support structure **250**. A preferred embodiment places a diode at an elevated position at the connection point between collection fiber **130** and support structure wire **200**.

FIG. **2D** presents another exemplary embodiment of a support structure with support members **275** in an x-shape connected to support structure wire **200** at intersection **278** with collection fibers **130** connected between ends of support members **275**. A plurality of diodes may be placed at any position on the support structure. A preferred embodiment places a diode at an elevated position at the connection point between collection fiber **130** and support wire **200**.

FIG. **2E** provides another exemplary embodiment for supporting collection fiber **130**. Collection fiber **130** may be connected on one side to support member **285**, which may be connected to support structure wire **200** in a first location and on the other side to support member **280**, which may be connected to support structure wire **200** in a second location on support structure wire **200**. The first and second locations may be the same location, or they may be different locations, even on different support wires. A plurality of diodes may be placed at any position on the support structure. A preferred embodiment places one or more diodes at elevated positions at the connection point(s) between collection fiber **130** and support wire **200**.

FIG. **2F** presents another exemplary embodiment of a support for a collection fiber. Two support members **290** may support either side of a collection fiber and are connected to support wire **200** in a single point. A plurality of diodes may be placed at any position on the support structure. A preferred embodiment places a diode at an elevated position at the connection point between collection fiber **130** and support wire **200**.

FIG. **2G** provides two supports as provided in FIG. **2F** such that at least two support members **292**, **294** may be connected to support structure wire **200** in multiple locations and collection fibers **130** may be connected between each end of the support structures. Collection fibers **130** may be connected between each end of a single support structure and between multiple support structures. A plurality of diodes may be placed at any position on the support structure. A preferred embodiment places one or more diodes at elevated positions at the connection point(s) between collection fiber **130** and support structure wire **200**.

FIG. **3** provides a schematic diagram of storing circuit **300** for storing energy collected by one or more collection devices (**130** from FIG. **2**). Load **150** induces current flow. Diode **310** may be electrically connected in series between one or more collection devices (**130** from FIG. **2**) and load **150**. A plurality of diodes may be placed at any position in the circuit. Switch **330** may be electrically connected between load **150** and at least one collection device (**130** from FIG. **2**) to connect and disconnect the load.

Capacitor **320** may be connected in parallel to the switch **330** and load **150** to store energy when switch **330** is open for delivery to load **150** when switch **330** is closed. Rectifier **340** may be electrically connected in parallel to load **150**, between the receiving end of switch **330** and ground. Rectifier **340** may be a full-wave or a half-wave rectifier. Rectifier **340** may include a diode electrically connected in parallel to load **150**, between the receiving end of switch **330** and ground. The direction of the diode of rectifier **340** is optional.

In an exemplary embodiment provided in FIG. **4**, storage circuit **400** stores energy from one or more collection devices (**130** from FIG. **2**) by charging capacitor **410**. If charging capacitor **410** is not used, then the connection to ground shown at capacitor **410** is eliminated. A plurality of diodes may be placed at any position in the circuit. Diode **310** may be electrically connected in series between one or more collection devices (**130** from FIG. **2**) and load **150**. Diode **440** may be placed in series with load **150**. The voltage from capacitor **410** can be used to charge spark gap **420** when it reaches sufficient voltage. Spark gap **420** may comprise one or more spark gaps in parallel. Non-limiting examples of spark gap **420** include mercury-reed switches and mercury-wetted reed switches. When spark gap **420** arcs, energy will arc from one end of the spark gap **420** to the receiving end of the spark gap **420**. The output of spark gap **420** may be electrically connected in series to rectifier **450**. Rectifier **450** may be a full-wave or a half-wave rectifier. Rectifier **450** may include a diode electrically connected in parallel to transformer **430** and load **150**, between the receiving end of spark gap **420** and ground.

The direction of the diode of rectifier **450** is optional. The output of rectifier **450** is connected to transformer **430** to drive load **150**.

FIG. **5** presents motor driver circuit **500**. One or more collection devices (**130** from FIG. **2**) are electrically connected to static electricity motor **510**, which powers generator **520** to drive load **150**. A plurality of diodes may be placed at any position in the circuit. Motor **510** may also be directly connected to load **150** to drive it directly.

FIG. **6** demonstrates a circuit **600** for producing hydrogen. A plurality of diodes may be placed at any position in the circuit. One or more collection devices (**130** from FIG. **2**) are electrically connected to primary spark gap **610**, which may be connected to secondary spark gap **640**. Non-limiting examples of spark gaps **610**, **640** include mercury-reed switches and mercury-wetted reed switches. Secondary spark gap **640** may be immersed in water **630** within container **620**. When secondary spark gap **640** immersed in water **630** is energized, spark gap **640** may produce bubbles of hydrogen and oxygen, which may be collected to be used as fuel.

FIG. **7** presents circuit **700** for driving a fuel cell. A plurality of diodes may be placed at any position in the circuit. Collection devices (**130** from FIG. **2**) provide energy to fuel cell **720** which drives load **150**. Fuel cell **720** may produce hydrogen and oxygen.

FIG. **8** presents exemplary circuit **800** for the collection of energy. Storage circuit **800** stores energy from one or more collection devices (**130** from FIG. **2**) by charging capacitor **810**. If charging capacitor **810** is not used, then the connection to ground shown at capacitor **810** is eliminated. A plurality of diodes may be placed at any position in the circuit. The voltage from capacitor **810** can be used to charge spark gap **820** when it reaches sufficient voltage. Spark gap **820** may comprise one or more spark gaps in parallel or in series. Non-limiting examples of spark gap **820** include mercury-reed switches and mercury-wetted reed switches. When spark gap **820** arcs, energy will arc from one end of spark gap **820** to the receiving end of spark gap **820**. The output of spark gap **820** may be electrically connected in series to rectifier **825**. Rectifier **825** may be a full-wave or a half-wave rectifier. Rectifier **825** may include a diode electrically connected in parallel to inductor **830** and load **150**, between the receiving end of spark gap **820** and ground. The direction of the diode of rectifier **825** is optional. The output of rectifier **825** is connected to inductor **830**. Inductor **830** may be a fixed value inductor or a variable inductor. Capacitor **870** may be placed in parallel with load **150**.

FIG. **9** presents a flow diagram of a method for collecting energy. In block **910**, one or more collection devices may be suspended from a support structure wire. In block **920**, a load may be electrically connected to the support structure wire to draw current. In block **930** a diode may be electrically connected between the support structure wire and the electrical connection to the load. In block **940**, energy provided to the load may be stored or otherwise utilized.

Any process descriptions or blocks in flow charts should be understood as representing modules, segments, or portions of code which include one or more executable instructions for implementing specific logical functions or steps in the process, and alternate implementations are included within the scope of the preferred embodiment of the present disclosure in which functions may be executed out of order from that shown or discussed, including substantially concurrently or in reverse order, depending on the functionality involved, as would be understood by those reasonably skilled in the art of the present disclosure.

It should be emphasized that the above-described embodiments of the present disclosure, particularly, any "preferred" embodiments, are merely possible examples of implementations, merely set forth for a clear understanding of the principles of the disclosure. Many variations and modifications may be made to the above-described embodiment(s) of the disclosure without departing substantially from the spirit and principles of the disclosure. All such modifications and variations are intended to be included herein within the scope of this disclosure and the present disclosure and protected by the following claims.

Therefore, at least the following is claimed:

1. A method of collecting energy comprising:

suspending at least one collection device from a plurality of support structure wires elevated above a ground level, the collection device including a carbon or graphite fiber that collects electrical enemy from the air and is electrically connected to the support structure wire; and

providing a load with an electrical connection to the plurality of support structure wires to draw current.

2. The method of claim **1**, wherein the collection device comprises a diode.

3. The method of claim **1**, wherein the collection device comprises a diode electrically connected between the fiber and the load.

4. The method of claim **1**, further comprising storing energy provided to the load.

5. The method of claim **4**, wherein storing energy provided to the load comprises storing energy in a capacitor or an inductor.

6. The method of claim **2**, wherein the diode is elevated relative to the ground level.

7. A system of energy collection comprising:

a plurality of support structure wires elevated above ground level; at least one collection device including at least one carbon or graphite fiber that collects electrical enemy from the air and is electrically connected to the plurality of support structure wires; and

a load electrically connected to the plurality of support structure wires.

8. The system of claim **7**, wherein the collection device comprises a diode.

9. The system of claim **7**, wherein the collection device comprises a diode electrically connected between the load and the fiber.

10. The system of claim **8**, wherein the diode is elevated relative to the ground level.

11. The system of claim **7**, further comprising a diode electrically connected between the at least one collection device and the plurality of support structure wires.

12. The system of claim **7**, wherein the fiber comprises a first end and a second opposing end, and wherein the system further comprises a support structure connected to both ends of the fiber.

13. The system of claim **7**, comprising:

said at least one fiber including a plurality of collection fibers; a support frame having a top side and a bottom side; and a conducting connecting wire between the plurality of support structure wires and the support frame, wherein one end of each of a plurality of collection fibers is connected to the top side of the support frame, and the opposing end of each of a plurality of collection fibers is connected to the bottom side of the support frame.

14. The system of claim **7**, further comprising a rigid structure, the rigid structure comprising multiple supports extending outward from a single point of the support structure, wherein each end of the fiber is connected to an end of the multiple supports.

15. The system of claim **7**, further comprising a rigid structure, the rigid structure comprising multiple supports extending outward from multiple points of the support structure, wherein each end of the fiber is connected to an end of the multiple supports.

16. The system of claim **14**, further comprising a plurality of rigid structures wherein said at least one fiber includes collection fibers connected between a plurality of the rigid structures.

17. The system of claim **7**, further comprising:

a switch connected in series between the plurality of support structure wires and the load; and

a capacitor connected in parallel with the switch and the load.

18. The system of claim **17**, wherein the switch comprises an interrupter connected between the plurality of support structure wires and the load.

19. The system of claim **18**, wherein the interrupter comprises one of a fluorescent tube, a neon bulb, an AC light, or a spark gap.

20. The system of claim **18**, further comprising a transformer connected between the interrupter and the load.

21. The system of claim **7**, further comprising:

a motor for providing power the motor connected between the plurality of support structure wires and the load; and

a generator powered by the motor.

22. The system of claim **7**, wherein the load comprises a spark gap in a container of fluid, and the load is used to produce a chemical reaction.

23. The system of claim **22**, wherein the fluid comprises water and the chemical reaction comprises the production of hydrogen and oxygen.

24. The system of claim **7**, further comprising a fuel cell between the plurality of support structure wires and the load.

25. The system of claim **7**, wherein the load comprises a fuel cell.

26. The system of claim **24**, wherein the fuel cell produces hydrogen and oxygen.

27. The system of claim **24**, further comprising a diode connected between the plurality of support structure wires and the fuel cell.

28. A system of collecting energy comprising:

means for suspending carbon or graphite collection fibers, the means elevated above a ground level, the collection fibers collecting electrical enemy from the air and electrically connected to the means for suspending collection fibers;

means for inducing current flow, the means for inducing current flow electrically connected to the means for suspending collection fibers; and

means for restricting the backflow of charge carriers, the means for restricting the backflow of charge carriers electrically connected between the collection fibers and the means for inducing current flow.

* * * * *

Creative SCIENCE & Research

459

Information Big Brother & the Oil Companies do not want you to know!

Copyright 2002 - 2004 Creative Science & Research

PO BOX 557 New Albany, IN. 47151 USA

Free Energy *From The* EARTH



Nikola Tesla

Scale up the enclosed methods and you could have

Unlimited Amperage!

By Unlimited we mean you can keep adding more earth cells to your earth power station as you can afford it year by year adding more and more amp power.

Aluminum

Copper

There are many ways to pick up on the free energy in the earth, Just a few are described in these plans. These devices if made right will pick up earth energy that many call ether or static currents as well as acting as high efficient earth battery’s. Ether travels through plastic wood etc... Study and research these plans closely there is more to these plans than what you may think. You can learn to get enough power to run your home!

Learning The basic’s of our invention

Experiment #1 How to assemble a 12 vdc system



This represents one cell. A qty of 12 to 14 will give you 12 - 14 volts dc when connected in series.

Cut 12 - 4” L x 3/4” copper pipe

1. You will have 12- 4" 3/4" copper piping, or If you did not purchase the kit then cut your copper to this size. KIT: take each piece of copper and tape the tops with 1" masking tape.

2. Now using RED LACQUER spray paint (Which you can buy at any hardware store), Paint the outside of the copper all around. (DO NOT PAINT THE INSIDE.) let air dry for 24 hrs. Now remove 1" masking tape.

3. Take the copper pipe outside to the area that you are going to use. use a hammer and hammer each one Into the ground up to the 1" copper exposed top. do not let the exposed copper touch the earth in the final placement. Dirt should be moist. Not real dry.

4. Now remove each pipe and place a thick piece of plastic on bottom of copper pipe to cap it. LET IT BE LOSE, DO NOT TAPE IT. YOU WANT RAIN WATER TO BE ABLE TO ESCAPE FROM EACH PIPE, Do not let exposed outside copper touch the earth.

5. Now hammer each pipe back Into the same holes. place each 2" piece of zinc rod (or a long bolt, most bolts are zinc plated) into the center of each pipe. The zinc Is the NEGATIVE and the copper is the + POSITIVE.

6. Now connect them in series to get 12 volts, use clip wire or solder them. If you are going to leave It outside for a long time then make sure connections are soldered and then painted to protect them from the weather. The rain will replenish your earth batteries. Top get more amaperage with this type simply add more copper and zinc rod cells USE 3' PIECES OF COPPER PIPE INSTEAD OF 4" PIPE. THEN CONNECT EVERY ROW OF 12 PIPES IN PARALLEL.. ADD AS MANY ROWS AS YOU NEED UNTIL YOU GET THE DESIRED AMPERAGE YOU WANT. **(THINK BIG!)** This can be a very powerful free energy system for your home or other. Not only will you get an earth battery effect, but you will also be collecting earth currents from ether /static and under ground radio waves as well.

7. The deeper you go with the copper pipe, the more amperage and voltage you can get.

Copyright 2002 - 2004 Creative Science & Research

Learning The basic's of our invention

Experiment #2 How to assemble a 12 vdc system

This is just an example to go by and is not the best way but is low in efficiency! See our capacitor earth cells, coil type or flat sheet type. They produce far more amperage and voltages than this type.



NOTICE: Do not paint the 10 foot copper cell. Keep all copper exposed to the earth. The more exposed copper the better. For higher amperage output, use a zinc or aluminum rod 10/16" Diameter which will leave a space of more than 1/16" to the copper.

Advantages of earth powered batteries

1. Free Energy
2. Long Life
3. The collection of aether energy.
4. Cells are also replenished by outside weather. Rain as well as lightning charges.

Copyright 2002 - 2004 Creative Science & Research

Learning The basic's of our invention

You can purchase Zinc rods or zinc plated bolts at any hardware store, most all nuts and bolts they sell are zinc coated and will work just fine. They also carry aluminum sheeting. Most hardware stores can order you copper sheeting as well.

Experiment #3 How to assemble a 12 vdc system

This is a simple way to produce more amperage but is not practical, we are only showing you this to educate you. The closer the zinc rod is to the copper the more amperage you will get as well as going deeper into the earth. If you do decide to build this basic set up. It is suggested that you solder all leads very well and dig deep enough into the earth to hide the tops of each cell. By covering the tops with dirt the cells can short out so what you want to do is to paint the exposed tops with lacquer or enamel paint then cover with plastic, cover with dirt and allow both the negative and the positive leads to stick out of the ground. But like I said this is not practical, what your goal should be is to make a very strong uf earth capacitor / battery, This will allow you to pick up and collect earth radiant waves of energy as well as lighting energy during storms, the energy you can collect in a strong lighting storm will amaze you! You must use an antenna on the zinc rod or copper rod. **WARNING! Be careful when collecting lighting it can kill you, be sure the positive and negative wires are not coming into your home. During a storm it is advised to have the lead wires going into a large uf cap bank via a one way diode on the positive lead to the positive of the cap or battery. The earth battery's can be dangerous at times and must be completely buried in the earth so a child, adult or animal can not touch or get to. Our earth capacitor batteries can store and hold thousands of volts. So be careful. Use rubber gloves and clothing to protect yourself. We are not responsible for anything in these plans you build at your own risk.**



Example of a perfect Zinc rod copper pipe cell

Top view of a 12 volt dc array high amp system

Connect the series arrays in parallel to each other as shown.
Or for a high voltage system connect all in series! Pulse the dc into a 10x step up transformer, 15,000 v Neon transf.

Zinc rod can be replaced by using rolled up aluminum sheeting or Zinc sheeting, Use 100% cotton cloth wrapped around the rolled sheeting or rod to give a small space in between the aluminum sheet and copper.



Copyright 2002 - 2004 Creative Science & Research

Learning The basic’s of our invention

Experiment #4 The 6 foot spacing method (old way)

There are many US Patents that were Issued back in the 1800's, one of them was issued to a Mr. Deckman. Deckman found that if you take several small pieces of Zinc and Carbon rod and stick them into the ground next to each other and connect them in series (much like a battery) you get very liittle gain at all.



But if you put them 6 feet apart you will get a gain In voltage and they will not cancel one another out. so by doing this you can put them In series to increase your voltage and your volt amps. The theory is that there Is some sort of natural energy VORTEX that takes up about that much space for each unit or cell.



By using this method it will take a lot of ground space, ground space that many people just do not have with the exception of farmers. If you do have the space then think BIG! dig deep and have as many cells as you can get up to 2 to 4 acres. There are much better ways - vs - the old method as you will see. but by using Deckmans old way or our new methods, you can get as much free energy as you want with voltages or amperages as high as you want or desire. The higher the desired amperage the more costly it can get. We are always working to better our inventions to keep the cost down.

Copyright 2002 - 2004 Creative Science & Research

Learning The basic's of our invention

By using our new system you can get as much voltage or amperage as you want. Just size It to meet your needs or your budget.

How to get AC current for house hold use.

You can convert the incoming dc current to ac by using a home made inverter (which we sell the plans to, **5 kw inverter plans $40 order #579**) or you can purchase a 12 v to 115 vac inverter from a store or solar panel supply house.. If you are planing to make a 115 VAC system this Is the only way you can do it. You can not get AC current from the ground. You must use our system to charge a deep cycle 12 v marine battery, and then connect our 5,000 watt 120 vdc to ac inverter to the battery to run your home. (we do not sell kits or inverters assembled, we only sell the plans at this time.)

More on the basic pipe method

Please note: the dirt level inside each pipe should be up to 1/4" from the top. each pipe should be tightly fliied with dirt. Which will automatically happen when you hammer the pipe into the ground the first time.

Each copper pipe (or cell) should be spaced 1 Inch to 1 1/2 inch apart. Doing this will give you more amperage and voltage.

How to dig a simple deep hole for 8' pipe: There are many ways in which you can do this. you can rent a ground drill bit and rig it up with a electric 2 hp motor or you can use 1" copper pipe.

First: prepare the ground with water to make it moist but not muddy, 2nd: hammer a 1" x 5' copper pipe into the moist ground about 5 inches deep/ then remove it from the ground and take a stick or a water hose to remove the dirt from inside the pipe. Then just repeat the process over and over until you get the desired depth that you want. you can get about 10 feet or more using this method.

WARNINGI BE CAREFUL OF ELECTIC POWER LINES WHEN YOU PLACE OR PULL THE COPPER PIPE FROM THE GROUND, IT WILL KILL YOU IF YOU TOUCH A POWER LINE WITH THE END OF THE COPPER PIPE.

We are dealing with a new type of energy as well as conventional energy < Ether energy can go through rubber/ plastic. Iron, etc....

Copyright 2002 - 2004 Creative Science & Research

What is ether or Radiant energy?

The understanding comes from a very deep study of etheric or static forces, this energy that we are getting out of the ground is what some call LIGHT ETHER, when you separate the light ether from the warm ether you can get these superconductive events. It appears like electricity but it has no heat events related to It.

The point is that the best polarity's of things to get a differential in the light ether is to have a silvered coloured metal and then something that is totally absorbitive/ Like black Carbon.

So now you have something that's the perfect reflector and something that is the perfect absorber, and once you understand what your pulling out of the ground (and that it Is not classic electricity as we get out of a normal type of chemical battery), then your going to be farther down the road to understanding how to get much more power out of this stuff.....

There are researchers now that are getting 1 /2 volt to 2 volts dc on a "Quote" volt meter, but it will shock you through an inch of rubber shoes this is not normal electricity!

Q: Is this energy coming from the sun and being absorbed In the earth or from the center of the earth?

A: Yes, but the primary source of light ether is the sun light, yes the earth does have an economy of light ether which does follow the sun around. BUT IT IS ALSO IN THE GROUND! AND ITS IN THE AIR!

Q: Did NokolaTesla know about this in the 1900's?

A: Yes, if you read into his writings he was always saying things like, there is more energy moving than just the electricity in this stuff.

Example: If you take a large Tesla coil and fire it up, and you drive it with a van de graph generator and you put the output of that into a Tesla coil. you can throw sparks across the room! What these electrostatic machines are gathering is light ether.

Copyright 2002 - 2004 Creative Science & Research

A Very Strange and New Discovery!

While working outside on another experiment I discovered a very strange generator effect, much to my surprise, I found that by using 2 aluminum 8” disks connected to my DC volt meter and by placing both disks in a vertical position while touching the bare earth dirt, and moving one of the disks and allowing the other to be stationary I get a dc voltage positive output! This effect works with any size or shape of aluminum, we used 8” diameter disk x 1/8” thick, we found that size to work best. Also by stacking them like a capacitor you will find that the current output is far greater, For Example: see figure 1, Disk A would have 4 more disks connected in parallel of the same size separated by paper die electrics. The same goes for Disk B .

First find a spot any where on the ground where there is no grass (best when wet). Please note, it's not just creating an acid battery effect, you are also getting a good contact with the ground as a conductor to pick up ether energy.

Now place the disks side by side, attach your DC voltmeter probes onto the disks, one negative and one positive. DC meter should be on the lowest setting, now place both disks on the ground very softly and move **disk B** and **do not move disk A** (positive.) You will notice you are getting a small amount of voltage and amperage. Now Move **disk A** and do not move **disk B.** **THE POLARITY CHANGES**.

The rule here is; The disk that moves is always positive. since we can get a polarity change just by moving the disks at opposite times. You can make a very simple mechanical device to get AC current from on top of the earth. Again, this is not just a chemical reaction we have done many test to prove this. You can also get a small voltage reading in dry dirt. The reason for the smaller voltage in using dry dirt is because a low conductance resistance is taking place here, keeping the system from being in contact with the earth and collecting the earth **ether energy.**



FIGURE 1

Copyright 2002 - 2004 Creative Science & Research

Capacitor Sheet Method

This method is far better than using pipes or rods. By using copper and zinc or aluminum foil sheets you will get much more amperage out of your system!

The amperage you will be collecting will be coming from 3 different sources,

1. **The acid in the ground and water**
2. **Energy that is being transmitted from the earth itself**
3. **Energy that is being transmitted from the sky and space.**

This may all seem unbelievable but it's true and is a fact! The more plates that you add the more power you will get! The copper sheet(s) is the positive, it must be facing down toward the earth. The aluminum or zinc sheet(s) is the negative and must be facing toward the sky! Between each sheet place 1- cotton or course screen printing mesh or other plastic course mesh cloth material. you can use a hole puncher to punch exact holes in each sheet, use 2 holes per sheet copper and aluminum. Use a 8 1/2" x 11" paper puncher one that is adjustable. next use a 3/4 wood base and drill hole for wood dowel rods to fit to the holes you punched in the sheets, you will have a total of 4 wood dowel rods, 2 on the right for the copper sheets and 2 on the left for the aluminum sheets to fit over, cloth die electric can be done the same. You then need to assemble dry and use another 3/4" wood board for top holding plate, which will fit over the wood dowel rods on top, sandwhich and press the assembly together and tape in place with duct tape, drill 2 long bolt holding holes on bottom wood base and top wood base then attach long bolts and nuts and tighten down. Remove tape. and attach wires, water the entire capacitor assembly and bury in the ground.

Copper sheet



Top View

Aluminum sheet



Top View



Top View

Place Aluminum sheet on top of copper sheet



Dotted lines indicate where cloth goes

Top View



Side View

Copyright 2002 - 2004 Creative Science & Research

Capacitor Sheet Method


10' Antenna
Aluminum Washer(s)
spacers
Copper Washer(s)
spacers
Wood Dowel Rods
WOOD
COPPER
Aluminum
−
+
Earth
WOOD

Copyright 2002 - 2004 Creative Science & Research

Capacitor Sheet Method

Again, the more plate sheets of metal you add (or cells) the more power you will get! Remember it's all about capacitance. You are collecting more than just simple battery type power. The copper plate sheet is the Positive + and the Aluminum sheet is the negative. There are many ways in which one can build this type of earth energy collector, below is simply an example of another shape and form. In this type we use water holes. water holes must all be in exact spots.


Connection Tab
Water Holes
+ Copper
10"
12"
Connection Tab
- Aluminum
10"
12"
100%
Cotton Cloth

Figure #1 Top View of separate pieces

Figure #1 Side View


Negative
-
Aluminum sheeting
1/4" dirt
100% Cotton
Copper
+
Positive
Aluminum sheeting
Copper
Aluminum sheeting
Copper
Aluminum sheeting
Copper


Copper Sphere
12" Diamter, hollow body
10 to 22 feet high
HV Diode
Negative
-
Aluminum sheeting
1/4" dirt
100% Cotton
Copper
+
Positive
Aluminum sheeting
Copper
Aluminum sheeting
Copper
Aluminum sheeting
Copper

Copyright 2002 - 2004 Creative Science & Research

OUR MORE ADVANCED EARTH CAPACITOR!

(EECC) Earth Energy Coil Capacitor!



To collect more ether earth energy atoms, build the following **Earth Energy Coil Capacitor**, **Designed & Created by Creative Science & Research**. This is far better than anything we have found yet! Much more power and is easier to build.

Start with our EECC Model #1, Take a 5/16" zinc rod or aluminum rod, cut to 7.5" long. Now use #27 bare copper wire, secure it in a drill press (which you will then turn by hand). Cover zinc rod with paper one layer, use very tiny bits of tape to secure. Now apply the copper wire over the paper, remember to use copper that is not coated! Tape one end of the copper wire to the end of the zinc or aluminum rod and begin to slowly wind. Each wind must be perfectly fitted side by side, paper should be 5.5" long, total length of winds should be 4" long centered on paper. Once you are done with the first layer, apply another piece of paper to the top layer of the first copper layer, do not use to much tape to secure paper in place! Now begin your 2nd layer, repeat this same process until you have about 10 layers, (the more layers the better!) Copper must not touch the zinc or aluminum. When done hot glue or epoxy a small end piece of the copper wire so it will not come unwound. This is one complete cell, keep in mind this is a small test version, to get more power you have to THINK BIG! Build larger cells, using larger size copper. Then place them in salt water to test, 2 cells can be connected in series, after that you must connect them by use of capacitors, diodes and electronic or hand wound spring switches. If you build 20 of these and try to connect them all in series without a cap/ diode switching method, the cells will cancel each other out. Keep in mind you want water to get to each layer as well as the zinc or aluminum. You can also use Aluminum or zinc pipe.

Now concerning the paper Die Electric, Paper will not last very long, test and find a water absorbing plastic die electric,(mesh type). We suggest that you use Plastic screen mesh that you can buy at any hardware store, if all you are interested in is collecting small voltages then use one layer in between each layer of copper, if you are interested in collecting higher voltages such as lightning charges then you must use more layers of plastic screen mesh to thicken the die electric so the higher voltages will not short out your system. Paper may not last longer than 1 year, Plastic screen mesh or polyester screen printing mesh will last for many years.

EECC Model #2 Same as #1, but different. In this design we use #27 copper COATED wire, instead of bare wire. since the copper wire is coated and not bare, each layer must be sanded, that is, the top portion of the copper coated layer must be sanded off so it will be exposed to the water and acid, a die electric should still be used in this case. This type makes for a very high efficient earth cap!

EECC Model #3 Same as #1 but reversed! You will use aluminum wire and a copper rod or pipe. Use a 3/4" copper pipe and wind the die electric paper or plastic mesh and Aluminum bare wire around the copper pipe as explained in Model #1

Copyright 2002 - 2004 Creative Science & Research

OUR MORE ADVANCED EARTH CAPACITOR!

(EECC) Earth Energy Coil Capacitor!


Aluminum 3/4” Diameter Pipe
–
+
(EECC) Model #1 See page 12
½ size of our larger version
Copper Wire
Layers #20 Gauge
Brown Paper
layers = Die Electric
12 ½”
15”
21”
Aluminum pipe

Winding the wire can be done quickly if you use a drill press that is redesigned and fitted with a low rpm 90 vdc conveyer belt motor with control box. www.Graingers.com

The perfect rpm is about 70 rpms, If you wish to make it a bit easier you can use larger wire such as # 17 gauge. The photo is an example of a mid size cell and can be very powerful! This is ½ size of a large cell.

Copyright 2002 - 2004 Creative Science & Research

OUR MORE ADVANCED EARTH CAPACITOR!

(EECC) Earth Energy Coil Capacitor!



Our small test model #1, we used #22 bare copper wire wrapped around a zinc rod, each layer had a paper die electric, tested in tap water. 5 layers.
Output = 89 vdc x 3.5 ma, this is low.
more layers will = more capacitance which ='s more amperage and voltage.

Small Drill press turned into a Coil Winder

The more layers, the
more free earth energy
you can collect!



Small Drill press turned into a Coil Winder. We turned this by hand.
Larger coils is best to use low rpm motor at about 70 rpms, In this picture you see that we wound each wind side by side, this makes for a more high efficient earth cap.
You can wild wind if you like if you use smaller wire like #31 to #34.



Side View
Ideal size for
experimenting

Copyright 2002 - 2004 Creative Science & Research

(EECC) Earth Energy Coil Capacitor!

Rolled Earth Capacitor


Top paper
Copper Foil
Aluminum Foil
Bottom paper

MODEL #4 Rolled Earth Capacitor

Copper foil is placed between 2 pieces of paper strips and Aluminum is placed on bottom. Use 400 foot strips 2” wide. This method is very hard to do. But is very high eff.



We used salt water to test rolled caps before placing them in the ground.

Copyright 2002 - 2004 Creative Science & Research

(EECC) Earth Energy Coil Capacitor!

MODEL #4 Rolled Earth Capacitor

Rolled Earth Capacitor





Again rolling this type of earth capacitor is very hard, Everything must be kept straight and inline with one another, Manufacturers of rolled electrolytic capacitors use computers and machinery. I am sure a simple home made roller with pin registration could be designed very easily. This type of earth battery is very high efficient. Paper is not a good die electric for high voltages! If you are wanting to collect earth and storm HV Currents you must use a thicker die electric. Metals must be spaced properly for storing high voltage.

Copyright 2002 - 2004 Creative Science & Research

(EECC) Earth Energy Coil Capacitor!

Rolling a capacitor is the best way but not the easiest,
Which makes this pipe coil model much more desirable to build



Sand or scratch off top layer coating, this will leave a protective coating in between each wire and underneath. Copper should not touch itself or the aluminum pipe. Then cover with paper and begin next layer of copper wire.

Symbols



= One way DIODE

Photo of Diode



Capacitor (Electrolytic)

Photo of one type
of Capacitor

Copyright 2002 - 2004 Creative Science & Research

CONNECTING THE CELLS IN SERIES

How to connect the cells in series to increase the output voltage without allowing the cells to cancel each other out. Figure **A** The Copper pipe and zinc rod method without the use of plastic on bottom of pipe. **Figure B** is the coil earth cap method.

Figure A


TO LOAD
+
Large Dump Capacitor to collect high voltage and to be used by load.
SW
6 v Capacitor
+
6 v Diode
SW
SW
SW
SW
6 v Capacitor
6 v Diode

Use electrolytic capacitors to store the charge coming from each cell, then connect them in series using Commutator Sw's connected to a small rotor shaft, connected to a milliamp solar cell hobby motor or build a small fuelless engine electric motor to run on and off switch's. You can also build a very low milliamp electronic switching circuit and use the earth energy to power it. Or another more simple way would be to use a hand spring type device (timer type) glue small magnets on a long rotating rotor arm connected to the inner spring. Then place small reed relay magnetic switches, on each timing magnet ON position. should have multi reed sw's, as the unit turns if gives time for the caps to charge and then comes around and connects caps all in series which in turn discharges into main cap dump.


Magnets
Reed Sw's
Hand wound spring

Copyright 2002 - 2004 Creative Science & Research


12 vdc
car or marine
BATTERY
12 v to 115 vac
INVERTER
LOAD
Can be lights,
TV, vcrs etc..
+
=
12 v to 115 vac
INVERTER
EECC
Free Energy Power Source
To keep up 12 vdc battery

Copper

Symbols

= One way DIODE

Photo of Diode



Capacitor (Electrolytic)

Photo of one type
of Capacitor

Copyright 2002 - 2004 Creative Science & Research

Suppliers List

Free News

Copper Foil Search

See www.google.com

1. Http://www.delphiglass.com/

   Use there search engine to find copper foil tape

2. http://www.glassmart.com/foil_menu.htm
3. http://www.globalsources.com

Search Google.com for:

1. Copper flashing
2. Inverters
3. Batteries
4. Copper coated wire
5. Copper wire
6. Electronic parts and supplies
7. Diodes
8. Capacitors
9. Free energy from the earth
10. Zinc rods

Copyright 2002 - 2004 Creative Science & Research

EECC update

Step One


Tape
Paper
Aluminum pipe or zinc

Step two


Metal angle wire guides
Total of 4 per side
Paper
Long bolts, nuts and washers
long bolt attaches to drill press.

Apply first layer of wire, remove, metal wire guides, apply more paper, then repeat over and over again until you have about a 5 to 6 inch diameter roll of wire and paper. Makes a very powerful earth capacitor!

Copyright 2002 - 2004 Creative Science & Research

EECC update

These are just a few extra idea's that we threw together. I hope they are helpful to you. Let us know how you like these plans. Send us photo's of what you have done we love to hear from our customers. If you got any new free energy idea's let us know we can research them for you. Many customers do not have the extra research time that we have.


Cloth or plastic mesh
Copper
Aluminum or Zinc sheet
+
−
White Nylon Bolts
Side View
= 1 sheet

Metal sheet type earth battery

Jules GUILLOT

Atmospheric Electric Generator



Fig. 1

Fig. 2

Shared by L. Cozma (Thanks !) --

The Guillot device generated about 2.5-3 Kilowatts with antenna height of ~ 20 meters. Power depends on the total collector surface and height of the vertical antenna. The apparatus in the photo produced ~300 watts with a collector 2 meters tall.

"Practical Utilization of Atmospheric Electricity"

by

Gillbert Darida

in *The Invention Encyclopedia,* pp. 204-207 (1930, Geo. Constantinescu, Ed.)

"The Earth has its own negative electricity, in the soil, and the atmosphere which surrounds the Earth is charged with positive electricity. The electric potential (the voltage) increases with the altitude, so we can say that the electric force is proportional to the atmospheric altitude (after Franklin, Quetelet, Lord Kelvin, Mascart, Joubert and other scientists).

The recent observations demonstrate that the air at 6000-7000 meters in altitude, is very highly charged with positive electricity, which could be explained by the friction between the external photosphere and the upper atmosphere of Earth, which rotates at a speed of more than 100,000 Kilometer per hour.

In that way, the Earth works like an electrostatic generator with electric charging by influence --- the upper atmosphere is positively charged by influence and the Earth crust obtains the negative polarity.

Between the two environments, the air and the soil, and inside the low atmosphere, in conditions of good weather, there are sbout 800 positive ions and also, 680 negative ion (and electrons) in just one square-centimeter of normal ionised air.

The Earth behaves like an huge electric armature negatively charged, which repels the electrons and attracts the positive ions. That positive ions' attraction determinates an electric current, also called "convective current". That's like an invisible continous bombardment, subject to daily and seasonal variations, which could be aproximated at **3 x 10 ^ -16 Amperes per square-centimeter,** and that is a total value of 1500 Amperes for the entire surface of the Earth.
The question is --- how does this current always maintains the same direction ? We can suppose that the natural radioactive emissions of the soil is responsable for this. We also know that radioactive emissions of the Earth works usually near the soil surface, and that explains the ionisation phenomenona inside caves.

The ionisation of the low atmosphere could also be the effect of the radioactive emissions of the Earth, especially when the X radiation works. Also, the Earth atmosphere is ionisated by the external radiation proceeding from the Sun and from the space environment, especially the action of ultraviolet radiation and the electron fascicles emitted by the Sun surface, at the temperature of 6000 deg. Celsius.

The capture of atmosphere electricity has been used in France, with aerial cables mounted on the Mont Blanc, and also in Germany --- with conductive cables carried by the captive baloons.

The atmosphere electricity collect system invented by eng. Jules Guillot is most ingenious and it relies on "the **electric siphon**" [*m.n. --- the discharging devices or spark-gap used today from the protection of aerial electric cables against the atmospheric electricity ; Jules Guillot has thought to recuperate and to use that electricity*].

His method consisted in the direct "pumping" of the atmosphere electricity using a collecting device which had two antennae and several collecting rods.

One antenna is **vertical** and it has a lot of **rods** scattered like an opened **fan**, with the tips against the **zenith**, for collecting the **negative** electricity which comes from the air ; the **horizontal** antenna is orientated against the **South** and its role is to collect the **positive** electricity.

The air electricity seems to have the double-polarity, as we can see at two electrised clouds when between them apears the electric discharge. The air could have different electric charging and the ionisation processus of atmosphere is very heterogenous. The inventor Guillot used **two separated and insulated armatures with the positive armature against the South** (more precisely, against the **Equator**...) and the **negative** armature against the **zenith**.

We can see in the scheme :

1,- the device P is the "**collector apparatus**" having **15-20 meters height** ; it also has a lot of **rods** which are scattered **fan**-like, all this on top of an **iron pillar** ; and also an **horizontal antenna** S oriented against the **South** ; the two antennae are disposed at **90 deg. angle** forming the two armatures where the electrical tension must apear. As the **height** of the pillar **increases**, the **voltage** increases more and more ;

2,- a system of **lightning-rods** (p1, p2, p3) for protection against discharges of atmospheric electricity during storms;

3,- the regulator system (**voltage regulator**, etc) R ;

4,- the electric **resistors** (Cn) for absorbing the parasite currents ;

5,- the "electric siphons" which have the role of making a magnetic field as a good environment for the transport of the ionized fluid, absorbing the electricity from the air ; the E1 and E2 are their regulator devices ;

6,- an **auxilliary continous current power supply** which send the current against an special **excitation coil**, used as starting device ; it works only when the system is starting.
This collector device works very good for lighting and heating. The device made by Guillot had
20 meters height on the total surface of **3 square-meters**. Also, J.Guillot used and electrical transformer for the industrial utilization of this "collector" --- as power supply for industrial electric engines."

French Patent # 551,882

Apparatus for Capture of Electric Currents in the Atmosphere

16 April 1923

Considering the terrestrial globe like the inductor of a dynamo, where the extraterrestrial ether is the inductor of electric currents circulating in the atmosphere; the apparatus of the invention described here selects through the device described below two perfectly distinct currents and eliminates others.

The device includes:

1, The air sensor; 2, a series of lightning rods; 3, vacuum; 4, an array of resistances; 5, vacuum; 6, witnesses.

1. An aerial sensor mounted on a pole is composed of **magnetic steel** fixed and sealed by a porcelain **insulator**, and surrounded a base by a **bronze ring** which are screwed **32 points of soft iron**, all forming antenna a pole. level beside it and isolated from the first, forming the 2nd pole, is fixed a sharp point of magnetic steel fixed in the horizontal position and directed towards the south and **movable to an angle of 45** is sealed in a porcelain insulator. This point is also circled a **ring of copper** notches figure. 1.

2. A series of 6 lightning surge arrestors at corners between each pole and the earth and the various gauges.

3. A first **regulator** form of a device similar absolutely similar to the aerial amtenna, but the two poles are superposed and opposed to the vertical point, and a **copper disk connects to ground**. Opposite the horizontal point, a **ring of tin** to which are welded tubes alternatively **16 tubes** composed each composed of **copper-lead** and **iron-lead** . The ring connects to the **ground** as shown in figure. 2.

A second regulator form of **automatic breakers** balanced on 3 poles and two poles also equally balanced.

4. A panel of **resistances** composed of **wire mesh** in bunches from different sections of **glass tubes** containing **copper** dust, **coal** and flowers of **sulfur**.

Vacuum cleaners consists of a **wooden box** on each pole, containing a **porcelain vase** in which **layers** isolated with **mica** is made up of **mercury, tin, coal, copper** and **sulfur**, all contaied in a **copper tube**.

6. The witnesses are comprised of ordinary incandescent lamps.

Resume

By the point at the zenith and the point to the south we channel two currents forming the two poles. We also protect from lightning. It regularizes the flow by a regulator and similar devices by a controlling each devise of adequate strength of the current harmful nature of these devices do not have loads. The refined current is conducted by ordinary copper wires**.**

French Patent # 565,395

Combined Apparatus for Capture of Atmospheric Electric Currents with Immediate Implementation

25 January 1924

We know that earth with its constitution, its rotation and movement in space, provides the electricity in the atmosphere. The electrical currents escape into space or largely accumulate towards the equator, as a result of the greater periphery of the globe.

In the atmosphere, there are two clearly distinct poles, i.e., clouds that can be electrically positive or negative; everything in nature shows this, otherwise it would be difficult to explain the lightning that occurs between the clouds and which are none other than contrary cloud electrical charges discharged by too close proximity.

The invention relates to a set of devices capable of capturing the atmospheric electricity.

So far, all searches made for this purpose has been to capture the atmosphere, i.e., that brought together into one system to capture two poles and opposes effect has been to destroy or cancel each other leaving the amount as the difference of the strongest to weakest.

It is therefore easy to understand why, considering the two poles of air as about equal, it is almost impossible to measure some potential with the land, the highest on the lowest remaining which can be positive or negative, copper being the strongest of one or other of these polarities.

It is on this basis that all research until now have been made, and that is why we must consider that all the time, between the two poles captured in the atmosphere and not in any mixture of systems uptake, it is possible to obtain tension and intensity, a considerable and measurable power captured separately between the two poles and remaining isolated from one another until their utilization .

In accordance with this invention, this collection is made by attraction of primary electrical currents in teh atmosphere, either positively or negatively charged, by an antenna that has two points absolutely isolated from one another, where one points to the zenith to attract negative electricity, and the other turned south, toward the equator to draws in the masses grouped in this area.

This shows and proves the existence of atmospheric electrical currents, and that it is possible to capture them with specially designed equipment primarily acting as regulators, as the persistent difficulty encountered so far in realizing their capture lies with large variations of tension in which the current atmosphere is present in space, for each of the poles, and an overload could inevitably fatal.

The patent in its present form of presentation does not cover the regulators or devices that are anticipated in the system, because they can be designed in different ways and give the same result, but covers the application and grouping of equipment operating as automatic relays with variable influence to limit current tension to that chosen for utilization.

These devices have a role associated with an overflow reservoir outside carrying excess liquid; iti these regulators will divert the excess voltage flows to ground.

We can still absorb these regulators having filters because they have the sole purpose of diverting the post being used , currents that are not yet known but likely that we will call for simplicity, abnormal currents. [sic...]

The patent also covers systems for regulating currents, applied to each of the poles because it is recognized that the shape and tension of the currents of the two poles are not equivalent.

The method of capture is by special antenna has directed two points in the atmosphere, as will be stated after this, with Boot ecoulement prior to the current atmosphere is also of great importance.

Finally, the current atmospheric reception is adequate even with the installation of a post, which can be expected at any location without the need for special altitude, as has been attempted in previous efforts.

We refer to the attached drawings:.

Figure 1 represents in elevation and side view an antenna that only has two points, to overcome an elevation ;

Figure 2 is the end of one of the peaks, the horizontal:



BREVET D'INVENTION.

XII. — Instruments de précision, électricité.

5. — Production de l'électricité, moteurs électriques.

N° 551.882

Appareil capteur de courants électriques dans l'atmosphère.

M. Jules GUILLOT résidant en France (Tarn-et-Garonne).

Demandé le 27 septembre 1921, à 15h 20m, à Paris.

Délivré le 15 janvier 1923. — Publié le 16 avril 1923.

[Brevet d'invention dont la délivrance a été ajournée en exécution de l'art. 11 § 7 de la loi du 5 juillet 1844 modifiée par la loi du 7 avril 1902.]

Considérant le globe terrestre comme l'induit d'une dynamo, dont l'éther supraterrestre est l'inducteur, des courants électriques circulent dans l'intervalle c'est-à-dire dans la couche atmosphérique; l'inventeur capte au moyen de l'appareil décrit ci-dessous deux de ces courants parfaitement distincts et élimine les autres.

L'appareil comprend :

1° Le capteur aérien; 2° une série de parafoudres; 3° les régulateurs; 4° un tableau de résistances; 5° les aspirateurs; 6° les témoins.

1° Le capteur aérien monté sur un poteau est composé d'une pointe d'acier aimanté fixée par scellement sur un isolateur porcelaine et cerclée à sa base par une bague de bronze sur laquelle sont vissées 32 aiguilles de fer doux, le tout formant l'antenne d'un pôle. A côté et isolé de la première, formant le 2e pôle, est fixée une pointe d'acier aimanté dans la position horizontale et dirigée vers le sud dont la base coudée à 45° est scellée sur un isolateur porcelaine. Cette pointe est également cerclée d'une bague de cuivre à encoches fig. 1.

2° Une série de 6 parafoudres à cornes entre chaque pôle et la terre et à écartements variés.

3° Un premier régulateur formé d'un appareil absolument semblable au capteur aérien, mais ayant les deux pôles superposés, et, opposé à la pointe verticale, un disque de cuivre relié à la terre. Opposé à la pointe horizontale, une roue à jante d'étain sur laquelle sont soudés alternativement 16 tubes composés eux-mêmes de deux métaux soudés : cuivre-plomb et fer-plomb. Cette roue est reliée à la terre par son pivot fig. 2.

Un deuxième régulateur formé d'appareils à déclanchement automatique au nombre de 3 par pôles et deux basculateurs également par pôles.

4° Un tableau de résistances composé de fils de maillechort en boudins de différentes sections, de tubes en verre contenant des poussières de cuivre, du charbon de cornue et de la fleur de soufre.

5° Les aspirateurs composés d'une boîte en bois sur chaque pôle, contenant un vase de porcelaine dans lequel par couches superposées et isolées au mica est placé du mercure, de l'étain, du charbon, du cuivre et du soufre, le tout traversé par une tige de cuivre.

6° Les témoins composés de lampes à incandescence ordinaires.

RÉSUMÉ.

Par la pointe au zénith et par la pointe au

Figure 3 shows schematically the table on which are mounted various devices or accessories that act as regulators of current tensions.



2 [551.882] PRODUCTION DE L'ÉLECTRICITÉ, ETC.

sud nous canalisons deux courants formant les deux pôles. On protège l'ensemble par des parafoudres. On régularise le débit par un régulateur semblable et par des appareils à déclanchement commandant chacun des résistances appropriées de la nature du courant nuisible dont ces' appareils sont chargés. Les courants épurés sont conduits aux témoins par des fils de cuivre ordinaire.

Jules GUILLOT,
Moissac (Tarn-et-Garonne).

Figure 4 is a scheme of surge arrestors, and

Figure 5 a table of resistances.

Fig. 3.



The necessary arrangements to capture atmospheric current form is as follows:

1. The **antenna** in figure 1 is formed with two peaks: the 1 is **steel**, supported by a **bronze ring** 2, surrounded by a **spiral form** 3; this point is oriented for attracting the **zenith** layers of **negative electricity** and the other edge 4 contains **copper coils** 6, and is oriented **south** to the **equator** to draw in the masses grouped in this area. To use this antenna it suffices to be raised on a mast or **pole** to a height a little higher than that of surrounding houses.

2. On the table **lightning arrestors**, contained 4, forms of 7 **copper horns** used to absorb large atmospheric discharges by certain time, as it would be dangerous to allow movement in the devices regulators.

3. On a table of **two** symmetrical systems **regulators**, Figure 3, one for each pole, to obtain and allow a regularization of large excesses in the current tensions, by automatically absorbing surges before passing over the

surfacea chosen for the desired use. These regulators are represented on the drawing by the references R, R1, R2, R3, R4.

4. In the **resistance** panel in communication with regulators, these resistances are formed as **spiral coils or screens** 8, **tubes 9 of glass filled with fine coal dust , aluminum powder, sulfur and fine copper dust**. Finally, **two** special 10 **processors** and constitutes **layers** of metal forming an **absorbant** for harmful or abnormal currents.

5. As a source of energy formed **auxiliary batteries** 11 and **Ruhmkorff coils** 12 to get into the antenna sufficient attraction by means of an adjustment of intensity, which once it begins, allows the constant flow of atmospheric current in the system.

In considering Figure 3, which represents a sort of an installation scheme of the device, the reception of atmospheric electrical current will, as set out above, producing a priming of these currents. This boot is made in launching the system which is double to answer each of the poles, the current batteries 11 through 12 and reels going to the antenna.

This boot will continue until the disposal of electrical current atmosphere is evident by the one or more table lamps L of resistance shown in Figure 5.

Once the lights illuminate it is advisable to charge the batteries to boot. Natural flow and constant currents will be captured by the regulators , Figure 3; they will regularize in tension and in amperage and then directed to use in table lamps.

It has been said above that regulators R, etc., are intended and designed to automatically eliminate earth surge currents capture and abnormal currents that cannot yet be level but that these regulators could be replaced by devices with the same function.

There is therefore no need to describe in detail and especially the claims. We only specify that these regulators must be proper protection for the purposes described above.

Fig. 3.4.



Fig. 3.5.



XII. — Instruments de précision, électricité.

5. — PRODUCTION DE L'ÉLECTRICITÉ, MOTEURS ÉLECTRIQUES.

N° 565.395

Dispositif combiné pour capter les courants électriques atmosphériques avec application immédiate.

M. JULES GUILLOT résidant en France (Allier).

Demandé le 6 avril 1923, à 11h 30m, à Paris.
Délivré le 7 novembre 1923. — Publié le 25 janvier 1924.

On sait que la terre, par sa propre constitution, sa rotation et son mouvement dans l'espace, fournit à elle seule l'électricité que l'on utilise et qui est en suspension dans l'atmosphère. Les courants électriques, qui s'échappent de la surface du globe, montent directement dans l'espace où les grandes masses sont accumulées vers l'équateur, par suite de la plus grande périphérie du globe.

Dans l'atmosphère, il y a deux pôles parfaitement distincts, c'est-à-dire que des nuages peuvent être électrisés, soit d'électricité positive ou négative; ceci, tout dans la nature le démontre, sans quoi, il serait difficile d'expliquer la provenance des éclairs qui se produisent entre les nuages et qui ne sont autres que des nuages chargés d'électricité contraire et qui s'amorcent entre eux par un trop grand rapprochement.

L'invention dont il s'agit concerne un dispositif formé d'un ensemble d'appareils aptes à la captation de ces courants atmosphériques.

Jusqu'à ce jour, toutes les recherches faites dans ce but ont été de capter dans l'atmosphère une seule catégorie de courants atmosphériques, c'est-à-dire, qu'on a réuni dans un même système de captation, deux pôles opposés et dont l'effet a été de se détruire ou de s'annuler l'un à l'autre laissant comme quantité que la différence du plus fort au plus faible.

Il sera donc facile de comprendre pourquoi, en considérant les deux pôles d'un courant atmosphérique comme à peu près égaux, il est presque impossible par certains temps de mesurer le potentiel avec la terre, du plus fort sur le plus faible subsistant et qui peut être positif ou négatif, suivant que le plus fort est de l'une ou de l'autre de ces polarités.

C'est sur cette base que toutes les recherches jusqu'à nos jours ont été faites et c'est pourquoi, il faut considérer que par tous les temps, entre les deux pôles captés dans l'atmosphère et non mélangés dans aucun des systèmes de captation, il est possible d'obtenir, en tension et en intensité, une puissance aussi considérable que l'on puisse désirer et qui sera mesurée entre les deux pôles captés séparément et toujours isolés l'un de l'autre jusqu'à leur utilisation.

Suivant l'invention, cette captation se fait par attraction dans l'atmosphère au moyen d'un amorçage des courants électriques, soit positif ou négatif, par une antenne à deux pointes absolument isolées l'une de l'autre, dont l'une tournée vers le zénith attire les couches d'électricité négative, et l'autre, tournée vers le sud, puise vers l'équateur, dans les masses groupées dans cette zone.

Ceci exposé et l'existence des courants électriques atmosphériques étant prouvée, il est

possible de les capter à la condition de disposer d'appareils spéciaux étudiés surtout pour jouer le rôle de régulateurs, attendu que la difficulté persistante rencontrée jusqu'alors pour réaliser la captation incombe aux grandes variations de tensions sous lesquelles les courants atmosphériques se présentent dans l'espace, pour chacun des pôles, et dont l'écoulement dans un poste de captation serait inévitablement funeste.

Le présent brevet sous sa forme de présentation doit donc couvrir, non pas le ou les dispositifs régulateurs qui sont prévus dans le système, car ils peuvent être conçus d'une façon toute différente et donner le même résultat, mais sur l'application raisonnée et le groupement d'appareils fonctionnant automatiquement et intervenant chacun comme relais d'influence variable pour limiter la tension des courants captés dans l'atmosphère à celle choisie pour utilisation.

Ces appareils ont un rôle assez connexe avec celui de trop-pleins sur un réservoir qui acheminent à l'extérieur l'excès de liquide; iti ces régulateurs détournent l'excès de tension des courants à la terre.

On peut encore assimiler ces régulateurs à des filtres car ils ont pour but de détourner du poste d'utilisation, des courants qui ne sont pas encore de nature connue mais que pour simplicité on appellera courants parasites ou anormaux.

Le brevet portera aussi sur le système de régulation des courants, appliqué à chacun des pôles, car il est reconnu que la forme et la tension des courants aux deux pôles ne sont pas équivalentes.

Le mode de captation par antenne spéciale à deux pointes orientées dans l'atmosphère, comme il sera indiqué ci-après, avec amorçage préalable pour l'écoulement des courants atmosphériques est aussi d'une grande importance.

Enfin la réception des courants atmosphériques se fait à l'endroit même de l'installation du poste; celui-ci peut être prévu en un lieu quelconque sans nécessiter d'altitude particulière, comme cela a été tenté dans des essais préconçus.

Sur les dessins ci-annexés auxquels on se réfère

La fig. 1 représente en élévation et en coupe partielle l'antenne seule, à deux pointes, surmontant un poteau d'élévation;

La fig. 2 est le plan de l'une des pointes, celle horizontale:

La fig. 3 montre schématiquement le tableau sur lequel sont montés les divers appareils ou accessoires qui jouent le rôle de régulateurs des tensions de courants.

La fig. 4 est un schéma de parafoudre, et

La fig. 5 un tableau de résistances.

Le dispositif nécessaire à la captation des courants atmosphériques est formé comme suit :

1° D'une antenne, fig. 1, formée de deux pointes dont l'une 1 est en acier, supportée par une bague de bronze 2 entourée d'une spirale 3 formant self; cette pointe est tournée vers le zénith pour attirer les couches d'électricité négative; l'autre pointe 4 comporte un cadre 5 de huit branches supportant des spirales de cuivre 6 et est tournée vers le sud pour puiser vers l'équateur dans les masses groupées dans cette zone. Pour l'utilisation de cette antenne il suffira qu'elle soit portée par un mât ou poteau de hauteur un peu supérieure à celle des habitations environnantes.

2° D'un tableau de parafoudre, fig. 4, formé de cornes de cuivre 7 servant à absorber les tros grosses décharges atmosphériques que par certains temps, il serait dangereux de laisser circuler dans les appareils régulateurs.

3° D'une table de deux systèmes symétriques de régulateurs, fig. 3, un pour chaque pôle, qui permet d'obtenir une régularisation assez grande dans les tensions des courants en absorbant automatiquement les surtensions dépassant la tension choisie pour l'utilisation désirée. Ces régulateurs sont représentés sur le dessin par les références R, R^1, R^2, R^3, R^4.

4° D'un tableau de résistance en communication avec les régulateurs, ces résistances sont formées de spirales de maillechor 8, de tubes 9 de verre remplis de poussière fine de charbon de cornue, de poudre d'aluminium, de soufre et de poussière fine de cuivre; enfin, deux appareils spéciaux 10 formant transformateurs et constitués de couches de métaux absorbant certains courants nuisibles ou anormaux.

5° D'une source auxiliaire d'énergie formée de piles 11 et de bobines Ruhmkorff 12 permettant d'obtenir dans l'antenne une attraction suffisante au moyen d'un dispositif de

DARIDA, Gillbert : "Practical Utilization of Atmospheric Electricity";

possible de les capter à la condition de disposer d'appareils spéciaux étudiés surtout pour jouer le rôle de régulateurs, attendu que la difficulté persistante rencontrée jusqu'alors pour réaliser la captation incombe aux grandes variations de tensions sous lesquelles les courants atmosphériques se présentent dans l'espace, pour chacun des pôles, et dont l'écoulement dans un poste de captation serait inévitablement funeste.

Le présent brevet sous sa forme de présentation doit donc couvrir, non pas le ou les dispositifs régulateurs qui sont prévus dans le système, car ils peuvent être conçus d'une façon toute différente et donner le même résultat, mais sur l'application raisonnée et le groupement d'appareils fonctionnant automatiquement et intervenant chacun comme relais d'influence variable pour limiter la tension des courants captés dans l'atmosphère à celle choisie pour utilisation.

Ces appareils ont un rôle assez connexe avec celui de trop-pleins sur un réservoir qui acheminent à l'extérieur l'excès de liquide; ici ces régulateurs détournent l'excès de tension des courants à la terre.

On peut encore assimiler ces régulateurs à des filtres car ils ont pour but de détourner du poste d'utilisation, des courants qui ne sont pas encore de nature connue mais que pour simplicité on appellera courants parasites ou anormaux.

Le brevet portera aussi sur le système de régulation des courants, appliqué à chacun des pôles, car il est reconnu que la forme et la tension des courants aux deux pôles ne sont pas équivalentes.

Le mode de captation par antenne spéciale à deux pointes orientées dans l'atmosphère, comme il sera indiqué ci-après, avec amorçage préalable pour l'écoulement des courants atmosphériques est aussi d'une grande importance.

Enfin la réception des courants atmosphériques se fait à l'endroit même de l'installation du poste; celui-ci peut être prévu en un lieu quelconque sans nécessiter d'altitude particulière, comme cela a été tenté dans des essais préconçus.

Sur les dessins ci-annexés auxquels on se réfère

La fig. 1 représente en élévation et en coupe partielle l'antenne seule, à deux pointes, surmontant un poteau d'élévation;

La fig. 2 est le plan de l'une des pointes, celle horizontale:

La fig. 3 montre schématiquement le tableau sur lequel sont montés les divers appareils ou accessoires qui jouent le rôle de régulateurs des tensions de courants.

La fig. 4 est un schéma de parafoudre, et

La fig. 5 un tableau de résistances.

Le dispositif nécessaire à la captation des courants atmosphériques est formé comme suit :

1° D'une antenne, fig. 1, formée de deux pointes dont l'une 1 est en acier, supportée par une bague de bronze 2 entourée d'une spirale 3 formant self; cette pointe est tournée vers le zénith pour attirer les couches d'électricité négative; l'autre pointe 4 comporte un cadre 5 de huit branches supportant des spirales de cuivre 6 et est tournée vers le sud pour puiser vers l'équateur dans les masses groupées dans cette zone. Pour l'utilisation de cette antenne il suffira qu'elle soit portée par un mât ou poteau de hauteur un peu supérieure à celle des habitations environnantes.

2° D'un tableau de parafoudre, fig. 4, formé de cornes de cuivre 7 servant à absorber les tros grosses décharges atmosphériques que par certains temps, il serait dangereux de laisser circuler dans les appareils régulateurs.

3° D'une table de deux systèmes symétriques de régulateurs, fig. 3, un pour chaque pôle, qui permet d'obtenir une régularisation assez grande dans les tensions des courants en absorbant automatiquement les surtensions dépassant la tension choisie pour l'utilisation désirée. Ces régulateurs sont représentés sur le dessin par les références R, R^1, R^2, R^3, R^4.

4° D'un tableau de résistance en communication avec les régulateurs, ces résistances sont formées de spirales de maillechor 8, de tubes 9 de verre remplis de poussière fine de charbon de cornue, de poudre d'aluminium, de soufre et de poussière fine de cuivre; enfin, deux appareils spéciaux 10 formant transformateurs et constitués de couches de métaux absorbant certains courants nuisibles ou anormaux.

5° D'une source auxiliaire d'énergie formée de piles 11 et de bobines Ruhmkorff 12 permettant d'obtenir dans l'antenne une attraction suffisante au moyen d'un dispositif de

2 [565.395] PRODUCTION DE L'ÉLECTRICITÉ, ETC.

possible de les capter à la condition de disposer d'appareils spéciaux étudiés surtout pour jouer le rôle de régulateurs, attendu que la difficulté persistante rencontrée jusqu'alors pour réaliser la captation incombe aux grandes variations de tensions sous lesquelles les courants atmosphériques se présentent dans l'espace, pour chacun des pôles, et dont l'écoulement dans un poste de captation serait inévitablement funeste.

Le présent brevet sous sa forme de présentation doit donc couvrir, non pas le ou les dispositifs régulateurs qui sont prévus dans le système, car ils peuvent être conçus d'une façon toute différente et donner le même résultat, mais sur l'application raisonnée et le groupement d'appareils fonctionnant automatiquement et intervenant chacun comme relais d'influence variable pour limiter la tension des courants captés dans l'atmosphère à celle choisie pour utilisation.

Ces appareils ont un rôle assez connexe avec celui de trop-pleins sur un réservoir qui acheminent à l'extérieur l'excès de liquide; ici ces régulateurs détournent l'excès de tension des courants à la terre.

On peut encore assimiler ces régulateurs à des filtres car ils ont pour but de détourner du poste d'utilisation, des courants qui ne sont pas encore de nature connue mais que pour simplicité on appellera courants parasites ou anormaux.

Le brevet portera aussi sur le système de régulation des courants, appliqué à chacun des pôles, car il est reconnu que la forme et la tension des courants aux deux pôles ne sont pas équivalentes.

Le mode de captation par antenne spéciale à deux pointes orientées dans l'atmosphère, comme il sera indiqué ci-après, avec amorçage préalable pour l'écoulement des courants atmosphériques est aussi d'une grande importance.

Enfin la réception des courants atmosphériques se fait à l'endroit même de l'installation du poste; celui-ci peut être prévu en un lieu quelconque sans nécessiter d'altitude particulière, comme cela a été tenté dans des essais préconçus.

Sur les dessins ci-annexés auxquels on se réfère

La fig. 1 représente en élévation et en coupe partielle l'antenne seule, à deux pointes, surmontant un poteau d'élévation;

La fig. 2 est le plan de l'une des pointes, celle horizontale:

La fig. 3 montre schématiquement le tableau sur lequel sont montés les divers appareils ou accessoires qui jouent le rôle de régulateurs des tensions de courants.

La fig. 4 est un schéma de parafoudre, et

La fig. 5 un tableau de résistances.

Le dispositif nécessaire à la captation des courants atmosphériques est formé comme suit :

1° D'une antenne, fig. 1, formée de deux pointes dont l'une 1 est en acier, supportée par une bague de bronze 2 entourée d'une spirale 3 formant self; cette pointe est tournée vers le zénith pour attirer les couches d'électricité négative; l'autre pointe 4 comporte un cadre 5 de huit branches supportant des spirales de cuivre 6 et est tournée vers le sud pour puiser vers l'équateur dans les masses groupées dans cette zone. Pour l'utilisation de cette antenne il suffira qu'elle soit portée par un mât ou poteau de hauteur un peu supérieure à celle des habitations environnantes.

2° D'un tableau de parafoudre, fig. 4, formé de cornes de cuivre 7 servant à absorber les tros grosses décharges atmosphériques que par certains temps, il serait dangereux de laisser circuler dans les appareils régulateurs.

3° D'une table de deux systèmes symétriques de régulateurs, fig. 3, un pour chaque pôle, qui permet d'obtenir une régularisation assez grande dans les tensions des courants en absorbant automatiquement les surtensions dépassant la tension choisie pour l'utilisation désirée. Ces régulateurs sont représentés sur le dessin par les références R, R^1, R^2, R^3, R^4.

4° D'un tableau de résistance en communication avec les régulateurs, ces résistances sont formées de spirales de maillechor 8, de tubes 9 de verre remplis de poussière fine de charbon de cornue, de poudre d'aluminium, de soufre et de poussière fine de cuivre; enfin, deux appareils spéciaux 10 formant transformateurs et constitués de couches de métaux absorbant certains courants nuisibles ou anormaux.

5° D'une source auxiliaire d'énergie formée de piles 11 et de bobines Ruhmkorff 12 permettant d'obtenir dans l'antenne une attraction suffisante au moyen d'un dispositif de



réglage d'intensité qui, une fois amorcé, permet l'écoulement constant des courants de l'atmosphère dans le système.

En considérant la fig. 3 qui représente en quelque sorte le schéma d'installation du dispositif, la réception des courants électriques atmosphériques se fera de la façon indiquée ci-dessus, en produisant un amorçage de ces courants. Cet amorçage est fait en lançant dans le système qui est double pour répondre à chacun des pôles, le courant des piles 11 passant par les bobines 12 et se rendant à l'antenne.

Cet amorçage sera maintenu et réglé jusqu'à ce que l'écoulement des courants électriques atmosphériques se soit manifesté par l'allumage d'une ou plusieurs lampes L du tableau des résistances représenté en fig. 5 portant la prise d'utilisation.

Dès que l'allumage des lampes sera constaté on sera averti de la captation des courants atmosphériques et on pourra couper le courant des piles d'amorçage. L'écoulement naturel et constant des courants captés se produira dans les appareils régulateurs de la table, fig. 3; ils seront régularisés en tension et en nature puis dirigés au tableau des lampes pour utilisation.

Il a été dit ci-dessus que les régulateurs R, etc., étaient prévus et conçus pour éliminer automatiquement à la terre les surtensions des courants captés ainsi que les courants anormaux qui ne peuvent encore être classés. mais que ces régulateurs pouvaient être remplacés par des appareils faisant le même office.

Il n'y a donc pas lieu de les décrire en détail et de les revendiquer spécialement. L'avenir seul précisera si ces régulateurs doivent faire l'objet d'une protection propre pour l'application décrite ci-dessus.

RÉSUMÉ.

Dispositif combiné pour capter les courants électriques atmosphériques avec application immédiate, caractérisé :

1° En ce que l'organe de captation est une antenne à deux branches orientées différemment, l'une vertical avec self est tournée vers le zénith pour puiser les courants négatifs, l'autre horizontale comporte un plateau central avec enroulement de fil et est orientée vers le sud pour puiser les courants positifs; l'orientation des pointes restant fonction du lieu terrestre où se fait la captation des courants considérés.

2° En ce que l'écoulement des courants atmosphériques dans le système récepteur est subordonné à un amorçage qui consiste à lancer dans l'antenne un courant provenant d'une source auxiliaire, telle que des piles reliées à des bobines de Ruhmkorff.

3° En ce qu'un tableau parafoudre est interposé entre l'antenne ou organe de captation et le tableau des régulateurs pour préserver l'installation en éliminant à la terre les décharges brusques atmosphériques.

4° En ce que les régulateurs sont disposés suivant deux systèmes symétriques correspondant à chacun des pôles des courants atmosphériques.

J. GUILLOT.

Par procuration :

V. PRÉVOST.

French Patent # 551,882

Appareil Capteur de Courants Electriques dans L'Atmosphere



The classic spark-gap with magnetic blowing circuit

The spark-gap with magnetic blowing :
a,- the initial stage ; the impulse current send in soil through the shunt-resistences 3, because the coils 2 have an impedance too big for the impulse of 10/20 µs ;
the spark-gap 1 has two elements disc-shaped 1a and 1b, the inferior disc have one electrode and the upper disc the other electrode of the spark-gap circuit.
b,- the second stage ; the accompanying current discharge - after the impulse current ;
this accompanying current pass through the coils 2 which produce the magnetic field with the role to extend the electric arc into the slit between insulator discs 1a and 1b ; the thickness of this slit is smaller and smaller in accord with the extension of the electric arc, in this manner producing the magnifing of its electric resistance and finally, the electric arc extinction.



1,- the spark-gap individual devices which work in the manner to extend the electric arc of the accompanying electric current ;
2,- the coils which produce the magnetic field for the magnetic blowing ;
3,- the electric shunt-resistances in parallel connection on the blowing coils, with the role of reducing the current inside this coils
4,- the disc with unlinear resistance ;
5,- electrical resistance for the homogenous distribution of the electric field in all the elements of the spark-gap.

In Jules Guillot scheme, that kind of device could be used for leading the current.

Spark-gap element with circuit for the magnetic blowing of the electric fascicle







a,- the spark-gap with variable resistance ;
b,- the tube spak-gap ;
t - the time

The tube spark-gap has the aerial spark gap with the electrodes 5 and 6 disposed at the insulator 8 extremities ; and one arc-over spark-gap device between the rod 4 and the electrode 1.

At start, the first spark apear in the aerial spark-gap and then, the electric dicharge goes to the gas-producing tube 7, where it makes the arc-over. The local pressure in the gas allow the electric arc extinction, after managing the over electric tension into soil. The capacity C which is created between the external ring 3 and the rod 4 is bigger than the Capacity C_1 between 1 an 2 in that manner, when the overtension apears, the auxiliary spark-gap 1, 2 will start working and then, the main spark-gap 1, 4. In this circuit, the electrode 9 is connected at the aerial electric line and the electrode 1 at the Earth.

In the image above, it is an classic tube spark-gap used for the protection of aerial electric cables. The atmospheric electricity is discharged in soil and lost... The Guillot's inventions used that kind of devices for leading and absorbing of the atmospheric electricity.

Pământul ca și celelalte astre, posedă o electricitate proprie negativă în interior, iar aerul care-l înconjoară este pozitiv. Potențialul sau tensiunea electrică a aerului se mărește pe măsură ce ne ridicăm în înălțime, astfel că putem spune că intensitatea electrică este proporțională cu înălțimea (după lucrările remarcabile ale lui Franklin, Quetelet, Lord Kelvin, Mascart, Joubert și a altor mari savanți fizicieni).

Observațiile făcute recent, au arătat că aerul regiunilor înalte dela 6000—7000 m este foarte încărcat cu electricitate pozitivă, a cărei explicație se datorește frecării fotosferei sau atmosferei terestre, prin învârtirea pământului în jurul soarelui cu mai mult de o sută de mii de km pe oră. Această frecare directă în fluidul eteric ambiant, face ca aerul să se încarce cu electricitate pozitivă prin influență, iar pământul să se încarce negativ.

Intre cele două medii, fluidic (aerul) și (pământul) materie, știința ne spune, că în partea de jos a atmosferei, pe timp frumos un centimetru cub de aer ionizat, conține circa 800 particule cu ioni pozitivi și 680 ioni negativi (electroni).

Pământul se comportă ca un enorm conductor încărcat negativ, respingând electroni și atrăgând ionii pozitivi. Această atracție a ionilor pozitivi determină un curent electric, zis și curent de convențiune. E un fel de bombardament invizibil supus variațiunilor zilei și a sezoanelor, putându-l evalua aproximativ la o densitate mijlocie remarcabilă, dela 3×10^{16} sau a 30 quatrilionime de amper pe cm cub, ceea ce dă pentru întreagă suprafață a pământului un curent formidabil, de 1500 de amperi.

Se pune întrebarea cum un astfel de curent poate să-și întreție mereu același sens? Aceasta este enigma pe care ne-o punem, studiind curenții naturali ai atmosferei noastre, presupunem că poate să fie o legătură a acțiunii emanațiunilor radioactive. Aceste

Utilizarea practică a electricității atmosferice

Pământul ca și celelalte astre, posedă o electricitate proprie negativă în interior, iar aerul care-l înconjoară este pozitiv. Potențialul sau tensiunea electrică a aerului se mărește pe măsură ce ne ridicăm în înălțime, astfel că putem spune că intensitatea electrică este proporțională cu înălțimea (după lucrările remarcabile ale lui Franklin, Quetelet, Lord Kelvin, Mascart, Joubert și a altor mari savanți fizicieni).

Observațiile făcute recent, au arătat că aerul regiunilor înalte dela 6000—7000 m este foarte încărcat cu electricitate pozitivă, a cărei explicație se datorește frecării fotosferei sau atmosferei terestre, prin învârtirea pământului în jurul soarelui cu mai mult de o sută de mii de km pe oră. Această frecare directă în fluidul eteric ambiant, face ca aerul să se încarce cu electricitate pozitivă prin influență, iar pământul să se încarce negativ.

Intre cele două medii, fluidic (aerul) și (pământul) materie, știința ne spune, că în partea de jos a atmosferei, pe timp frumos un centimetru cub de aer ionizat, conține circa 800 particule cu ioni pozitivi și 680 ioni negativi (electroni).

Pământul se comportă ca un enorm conductor încărcat negativ, respingând electroni și atrăgând ionii pozitivi. Această atracție a ionilor pozitivi determină un curent electric, zis și curent de convențiune. E un fel de bombardament invizibil supus variațiunilor zilei și a sezoanelor, putându-l evalua aproximativ la o densitate mijlocie remarcabilă, dela 3×10^{16} sau a 30 quatrilionime de amper pe cm cub, ceea ce dă pentru întreagă suprafață a pământului un curent formidabil, de 1500 de amperi.

Se pune întrebarea cum un astfel de curent poate să-și întreție mereu același sens? Aceasta este enigma pe care ne-o punem, studiind curenții naturali ai atmosferei noastre, presupunem că poate să fie o legătură a acțiunii emanațiunilor radioactive. Aceste

prin ajutorul unui aparat de captare, format din 2 antene aeriene și o serie de bobine după cum se vede în fig. 108. Una din antene este verticală în formă de evantaiu dirijată cu vârfurile către zenit, pentru a capta electricitatea negativă din atmosferă; cea care este orizontală, este dirijată către Sud, pentru a capta electricitate pozitivă.



Fig. 109

Electricitatea în aer pare să fie cu dublă polaritate, după cum se vede la 2 nori electrizați, cari deplasându-se în sens contrar, dau naștere unei scântei (fulger) când distanța respectivă poate să fie străbătută de puternica lor diferență de potențial. Straturile de aer de densități diferite, nu sunt toate antrenate de aceeași viteză prin rotația pământului, ele se electrizează deci prin frecarea decalajului lor respectiv.

Aceste sunt considerațiunile ce l-au făcut pe inventator să așeze în atmosferă doi poli complet distincți și perfect izolați, al cărui pol pozitiv *S* (fig. 109) poate fi dirijat în direcțiunea Sudului, și a celuilalt negativ *P*, în direcțiunea zenitului. Fig. 109 arată schema montajului și a conexiunilor compuse după cum urmează: 1. dintr'o antenă dublă aeriană, montată pe stâlpi de 15—20 m înălțime. Această parte care se mai numește și aparat de captat, este format din vârfurile *P*, dispuse în evantai în vârful unei tije de oțel dirijate către zenit, pentru a capta curenții negativi ai atmosferei și dintr'o altă antenă orizontală a cărei săgeată este îndreptată către sud *S*, adică către equator, pentru a recepta curenții pozitivi. Aceste două părți dispuse în unghiu de 90°, formează cei doi poli al curentului aerian, a cărei diferență de potențial este suficientă pentru a permite utilizarea electricității atmosferice.



Parts List

Steel Rods, magnetic, 2
Insulator, porcelain
Ring, bronze
Rods, soft iron, 32
Ring, copper
Surge Protector
Disk, copper
Ring, tin
Tubes, steel
Rx Cu-Pb, Fe-Pb
Breakers, automatic
Resistances : Wire Mesh, Glass Tube. Cu, C, S powder
Vacuum Cleaners : Box, Jar, Mica &
Tube, copper;
Rx : Hg, Sn, C, Cu, S
Battery
Ignition Coil


HIGHLY IONIZED AIR (CONDUCTOR OF RADIO ENERGY WAVES)
ULTRA-VIOLET BEAM
AIRCRAFT PROPELLED BY WIRELESS POWER
ULTRA-VIOLET BEAM THROWN TO EARTH
METAL SCREEN OR MESH "B"
POWERFUL ULTRA-VIOLET RAY GENERATOR "A"
WIRELESS ENERGY TRANSMITTING PLANT
RECEIVING STATION FOR RADIO POWER
ISOLATED LAND
OCEAN SHIP RECEIVING RADIO POWER FOR PROPULSION
EE

Showing the Wireless Transmission of Power by Means of Ionized Searchlight Beams. Powerful Tesla Currents of High Potential and Frequency Are Impress on the Ionized Beams and Received from Similar Beams as Shown.

Wireless Transmission of Power Now Possible

By THOMAS W. BENSON

RECENT developments tend to fulfill the old, old dream of power transmission without wires. For years men have labored in vain to transmit power without wires and thus solve a myriad of transportation problems, such as propelling vehicles, ships, trains, aircraft, etc., without having to include a source of power in their construction. It makes one's head almost reel to think of the possibilities in such an achievement and now the dream promises to come true.

By one bold stroke an English genius, Mr. John Hettinger, has unthinkingly opened up the way for its realization. Like numerous other inventions, the way lay before our very eyes, but we were all too blind to see it.

While working on a means for transmitting radio waves without material aerials, Mr. Hettinger hit upon the idea of using ionized light beams as elevated conductors. Obviously simple when one thinks of it.

It is a well-known fact that an ionized gas is a conductor; in fact, the conductivity of a gas is a measure of its ionization. Furthermore, it is possible to ionize a gas by means of a stream of ultra violet rays. Working with these facts, Mr. Hettinger devised means to utilize them for radio transmission in the following manner.


Ionized air (Conductor)
Dense Air (Insulator)
Earth (Conductor)
Generating plant
Ship
EE

Fig. 2

Diagram of the Author's Scheme for the Wireless Transmission of Power Thru Ionized Light Beams and the Upper Ionized Strata of the Atmosphere.

As shown in Fig. 1, a source of ultra violet rays, an arc or mercury vapor lamp, A, is arranged to throw a beam of ionizing rays vertically.

These rays result in an ionized stream of air that acts as a conductor, the surrounding un-ionized air being practically a perfect insulator. By making connection to this conducting beam with a metallic screen or mesh at B, it can be utilized as an aerial for radio communication.

We are perfectly aware that this ionized beam rapidly loses its conducting power



Fig. 1

Diagram Showing the Transmitting and Receiving Circuits for the Transmission and Reception of Electric Power by Wireless.

as the distance from the source increases, therefore the effective height of such an arrangement is determined by the intensity of the ray generator. So much for the idea as applied to radio communication.

But let us consider further. In studying the spectrum we find that the sunlight on reaching the earth contains few ultra violet rays of shorter wavelengths than 3,000 Angstrom units, yet we are able to generate much shorter rays with an arc light. It is unreasonable to assume that shorter waves do not leave the sun, and in view of the fact that it has been determined that the upper stratum of our atmosphere is ionized, it is accepted that the shorter rays are absorbed to cause this ionization.

It will now be apparent that a very good condition exists for the transmission of energy without wires. As shown in Fig. 2, we have the earth, a good conductor, surrounded with a blanket of insulating air about ten miles thick, beyond which, up to about a hundred miles, the air is highly rarefied and kept in a state of ionization by light from the sun and stars.

Hence, we have two good conductors separated by several miles of atmosphere, practically a perfect insulator, an ideal arrangement for our purposes. We have but to connect a source of current to the earth and to the ionized strata of air and energy can be transmitted entirely around the earth without wires. The energy could be utilized in any part of the earth by merely connecting to the pair of conductors.

This condition has been recognized for some time, but the difficulty lies in making connections to the upper layer of conducting atmosphere. It is hardly practical to construct towers six or seven miles high for the purpose, then again the energy could not be utilized without using a similar structure at the point of reception, which makes this scheme hardly feasible for aircraft or moving vehicles.

Return then to the ionized stream for radio aerials. We can easily construct arcs that will throw a beam ten or twenty miles. Then why not make connection to that upper stratum with an ionized stream of air? Wonderful in its simplicity.

In Fig. 2 the writer attempts to portray a generating station embodying these principles. In the main building will be housed the generating units for supplying the current to the arc and the primary of the high voltage apparatus for transmission of energy. Supported on the roof of this structure will be a monstrous arc lamp capable of throwing a stream of ultra violet rays for at least ten miles. In this beam is supported a conducting screen to make connection to the conducting stream of ionized air. The insulation of these parts present no great difficulties to modern engineering.

The building will also house a huge step-up transformer, a set of high voltage condensers, a spark gap either of the rotary or quenched type and a huge oscillation transformer or Tesla coil. These instruments are connected in the usual manner and tuned so that the inductance in the circuit and the capacity formed by the earth and ionized upper strata will have a well defined oscillation period.

By these means the whole earth will become an electrified body, energy to be drawn at any point by simply making metallic connection to the earth and pointing a beam of light vertically, a screen being used to take the energy that will flow down the beam. An inductance coil being necessary in the circuit to insure resonance with the transmitter at the receiving set. After once started, the receiving energy can be used to keep the arc going.



Fig. 3

Two Optional Forms of Wireless Antennae Formed of Searchlight Beams—Ionized Atmospheric Streams.

Ships will have an arc and reflector mounted on the masts, aeroplanes have two arcs, one on top, the other below, and so on.

This scheme will not interfere with present short range transmission, it being hardly practical for each home to have an arc on the roof when one arc would serve for a town and several for a large city.

Rather its benefit will lie in the utilization of water falls far from civilization, now unused on account of difficulties in transmitting the power hundreds or thousands of miles.

Aside from the transmission of power other advantages may accrue. Will such a stress between the earth and upper air strata reduce the presence of dust particles in the atmosphere? Or, again, cause the immediate condensation of fogs and moisture in the air to give us perfectly cloudless days? Perhaps it will become simply a matter of changing the frequency or voltage of the current to cause rain or to prevent it.

Then the question of effect on radio communication: will it make our present sets obsolete, a transmitter of the future being connected directly to the power set and acting by superimposing different frequencies on the power frequency? Or will radio-telephony work hand in hand with the power system, the voice currents being impress on the power circuit and filtered out at the receiver?

There are a thousand and one things such an arrangement might effect. Will trees and vegetation increase in growth as experiments in electrical culture would indicate? What effect would such stresses have on germs and bacilli? Their numbers will be decreased by the destructive effects of the ultra-violet light. Will man grow to an unsuspected height and become uniformly healthier due to the electrical treatment he would be constantly undergoing?

And so on—conjecture is without bounds, but the scheme is practical to all appearances; it requires but some financial genius to give it a trial.

And to think it all was within reach such a short time ago! Had Tesla but put a gigantic arc on top of the tower of his experimental station in Long Island accurate data would be at hand now—were it but even a promise it would mean another step towards the final mastery of all matter by man.

(No Model.)

M. W. DEWEY.

METHOD OF UTILIZING NATURAL ELECTRIC ENERGY.

No. 414,943. Patented Nov. 12, 1889.


P
P
P
P
F
P'
P'
P'
P'
F'
a
A'
A
d'
c
c
b
N
S
b'
f
f
e
d
D
D
J
S
N
K
I
g
l
m
h
L
l
l
l
n
L'
H
D
G
d'
o
M
B
d
E
C
c'
c'
c'
c'
c'
c'

WITNESSES:

C. L. Bendixon

A. F. Walz.

Mark W. Dewey INVENTOR

BY

Duell, Laass & Duell

ATTORNEYS

UNITED STATES PATENT OFFICE.

MARK W. DEWEY, OF SYRACUSE, NEW YORK, ASSIGNOR TO THE DEWEY CORPORATION, OF SAME PLACE.

METHOD OF UTILIZING NATURAL ELECTRIC ENERGY.

SPECIFICATION forming part of Letters Patent No. 414,943, dated November 12, 1889.

Application filed May 1, 1889. Serial No. 309,171. (No model.)

To all whom it may concern:

Be it known that I, MARK W. DEWEY, of Syracuse, in the county of Onondaga, in the State of New York, have invented new and useful Improvements in the Method of Utilizing Natural Electric Energy, of which the following, taken in connection with the accompanying drawings, is a full, clear, and exact description.

The object of this invention is to provide a method whereby natural electrical energy—such as the so-called "atmospheric electrical energy," or electrical energy that may be derived from the difference of potential existing between two points, one being the earth and the other the atmosphere at an elevation above the earth—may be collected or utilized for the various uses to which electricity is applied.

It has been found that the presence of electricity in the upper regions of the atmosphere is not confined to thunder-clouds, but can be detected at all times and often in great quantities in different conditions of the atmosphere. In fine weather this electricity is mostly positive; but in showery or stormy weather negative electricity is as frequently met with as positive, and it is in such weather that the indications of electricity, whether positive or negative, are usually the strongest. It has also been found that as we proceed farther from the earth's surface, whether upward from a level plane thereof or horizontally from an elevation, the potential of points in the air becomes more and more different from that of the earth, the difference being, in a broad sense, simply proportional to the distance; hence we can infer that there is electricity residing on the surface of the earth, the density of which at any moment in the locality of observation is measured by the difference of potential found to exist between the earth and a given point in the air near it. The results of observations show that the variations of the electricity residing in the atmosphere is the main cause of the variations of the electricity on the surface of the earth. A charged cloud or body of air induces electricity of the opposite kind to its own on the parts of the earth's surface over which it passes and produces such variations. The difference of potential in increasing the distance from the earth is due to electricity induced on the surface of the earth by opposite electricity in the air overhead, and the air being a non-conductor the electricities are unable to combine. As electrical density is greater on projecting parts of a surface than on those which are plane or concave, stronger indications are obtained on hills than in valleys, if the collecting apparatus be at the same distance from the ground in both cases. The average difference of potential is greater in the winter than in the summer. Little or no effects can be obtained within inclosures or under trees, as they tend to screen the apparatus.

Inasmuch as electricity travels in preference through the best conductors, it follows that if a path of low resistance is formed (such as the erection of a metal pole) to a sufficient elevation above the earth the electricities in the atmosphere and that on the surface of the earth will tend to combine and travel through the said path in a current or currents, and if this pole terminates in a metal point or a number of such points the earth and clouds exchange their opposite electricities without a disruptive discharge—as the lightning—but in a slow and gradual way through convection. Besides supplying the top of the pole with points, a metal plate to which the said points are fixed attracts the opposite electricity in the atmosphere. In order to obtain a greater and increased effect, a large metal plate is buried at the foot of the pole and electrically connected therewith, and is provided with points or branches extending in different directions in the ground. The plate and branches may be surrounded by metallic refuse, coke, or other good conducting substance. The metallic points on the top of the pole should be sharp, and preferably of copper, and may be platinized, gilded, or galvanized to prevent corrosion. It having been ascertained by practical experiments that either a flame or dropping water at an elevation above the surface of the earth produces convection of electricity, it is obvious that such means may be employed in place of the points hereinbefore referred to. As the electricity in the atmosphere is sometimes positive and other times negative, the direction of the currents is not always the same—that is, the atmospheric electrical energy is composed of a current of an alternating character, flowing in one direction on an average about as much of the time as in the opposite direction, but the length of the current in a certain direction, or the lengths of time between reversals or changes in the direction of its flow, is greatly varied. This and also the varied strength of the currents have prevented the utilization of atmospheric electrical energy in commercial quantities for the various purposes for which electricity is generally employed. In order to utilize such a current or currents, they should be transformed into a continuous direct current of uniform strength. The apparatus for accomplishing the transformation of atmospheric electricity into a direct current of uniform strength is susceptible of being greatly modified. The preferred form of apparatus, however, for carrying the invention practically into effect I will now proceed to describe to show that the method is capable of actual performance. Said apparatus is illustrated in the diagram accompanying this specification.

Referring specifically to said diagram, A represents a metallic pole, which is shown bare, but may be enveloped in suitable insulating material, if desirable. B is the base of the aforesaid pole, which base is of insulating material set in the ground E. C is a large metal plate beneath the said base, and has points or branches *c'* extending therefrom in different directions in the ground. C' is a metallic post extending from the said plate above the surface of the ground and having a terminal *d* of the circuit D. On the top of said pole is mounted a metallic cap F, consisting, preferably, of a convex disk provided with sharp iron or copper points *p*, which project in all directions from the same. As before mentioned, the said points may be plated with a suitable metal that forms a good conductor and prevents corrosion. Similar caps F' may be placed on other insulated poles, as A', in the vicinity, and connected with the main pole A by an electric conductor *a*, for increasing the effect. The pole A' may be of wood, and the pole A may also be of the same material if provided with a metal conductor within or on the outside, extending from the cap to the other terminal *d'* of the circuit D. The said circuit D leads from the terminal *d* through an automatic variable resistance G, thence to one of the poles of a secondary or storage battery H, and from the other pole of said battery through an automatic current-regulator to the terminal *d'*. An automatic current-reverser or pole-changer J is located in the said circuit for reversing the current whenever there is a change in its direction, so that it may be rectified or straightened during transit and caused to travel at all times whether its direction is toward or from the earth in one and the same direction through a portion of the circuit containing the secondary battery. The reversals are accomplished automatically by means of a pivoted polarized armature *b*, located between two electro-magnets *c c*, having their coils included in a shunt-circuit between the leads of the circuit D. The magnets are wound so that a north pole will be presented to the armature on one side and a south pole on the other. When the current is flowing in a certain direction, the said polarized armature will be repelled by one magnet and attracted by the other, and thereby moved to one side. When the current changes its direction through the magnets, the poles of the said magnets are reversed and the armature is both repelled and attracted to the other side. An arm *b'*, of diamagnetic material, is fixed to and extends from the armature and is moved by the same. Between a movable end of the arm and the said current-reverser is a pivoted connection or link *e*, by which the motion of the arm is conveyed to the reverser. Stops *f* are provided for limiting the movement of the said arm, and an adjustable resistance *d'* is included in the shunt *d''* to regulate the current through the same.

The current-regulator hereinbefore referred to prevents short-circuiting or the rapid discharge of the secondary battery into the air and ground when the strength of said battery-current becomes greater than that passing to the battery. Said regulator is composed of an electro-magnet I, having its coil in the circuit D. A pivoted polarized armature *g* is connected at its pivot to one terminal of the coil of said magnet, and when the current is flowing to the battery said armature is attracted by the magnet I and held in contact with the stop *h*, to which the terminal of the secondary battery is connected. In the aforesaid condition a free or low-resistance path for the current is provided to the battery; but when the battery-current exceeds the charging-current the magnet-poles are reversed and the armature is repelled by the magnet, and the free path of the circuit is broken between the armature *g* and stop *h*. In order to maintain the armature in the latter position until the charging-current has been increased in strength above that of the battery-current or discharging-current, and so that the said regulator will automatically operate, a shunt path K of high resistance is provided around the armature *g* and stop *h*. The high resistance of the said shunt is obtained by including a rheostat *m*. This shunt path or circuit K, with the resistance, permits a small but sufficient amount of current to flow through the magnet I to hold the armature away from the stop *h* until the current is reversed, and then move the armature back to stop *h* to close the free or low-resistance path. A spring *i* is provided to assist the movement of the armature from the magnet when it is repelled by the same.

The electric current may be directly conducted to translating devices—such as lamps or electromotors; but, as hereinbefore stated, said current is preferably employed to charge one or more cells of the secondary battery H, and this battery stores or accumulates the electrical energy and supplies the said translating devices. To illustrate the latter feature, leads or wires L and L′ are extended from the poles or electrodes of said battery, and translating devices, in the shape of incandescent lamps *l*, are connected with the said wires in multiple arc. In the wire L is a common circuit maker and breaker *n* to close and open the circuit to the lamps. The said battery may be charged in series or parallel.

The automatic variable resistance G maintains the current flowing through the circuit D approximately uniform by increasing the resistance therein upon an increase of strength. Said resistance is not absolutely necessary and may be dispensed with.

The lightning-arrester M is to short-circuit a very heavy current to prevent the same from passing through the other parts of the apparatus and injuring it. A low-resistance shunt O, with a circuit maker and breaker therein, is connected between the leads of the circuit D, near the terminals *d* and *d′*, to completely short-circuit the apparatus when desired.

Having described my invention, what I claim as new, and desire to secure by Letters Patent, is—

1. The method of utilizing atmospheric electrical energy, consisting in conducting the electric current or currents bettween the earth and a point in the atmosphere at an elevation above the earth, rectifying or straightening the currents during transit, and storing or accumulating the electrical energy of said rectified current or currents.

2. As preliminary steps in the method of utilizing atmospheric electrical energy, conducting the electric current or currents through a path of low resistance between the earth and the atmosphere at an elevation above the earth, maintaining an approximately uniform strength of current and rectifying or straightening the same during transit.

3. As preliminary steps in the method of utilizing atmospheric electrical energy, conducting the electric current or currents through a path of low resistance between the earth and the atmosphere at an elevation above the earth, and rectifying or straightening said currents during transit.

4. The method of utilizing atmospheric electrical energy or deriving energy from the difference of electrical potential existing between the earth and a point or points in the atmosphere at an elevation above the earth, consisting in conducting the current or currents between the two points through a path of low resistance, rectifying or straightening the said currents in a portion of the path during transit, and storing or accumulating the electrical energy thereof.

5. The method of utilizing atmospheric electrical energy or deriving energy from the difference of electrical potential existing between the earth and a point or points in the atmosphere at an elevation above the earth, consisting in conducting the current or currents between the two points through a path of low resistance, maintaining an approximately uniform strength of current, rectifying or straightening the said currents in a portion of the path during transit, and storing or accumulating the electrical energy.

6. The method of utilizing atmospheric electrical energy composed of a current of a varied alternating character, consisting in conducting the electric current or currents through a path of low resistance between the earth and the atmosphere at an elevation above the earth, and then accumulating the electrical energy of said current or currents while flowing in both directions in one or more cells of a secondary or storage battery, as described.

In testimony whereof I have hereunto signed my name this 29th day of April, 1889.

MARK W. DEWEY. [L. S.]

Witnesses:
C. H. DUELL,
C. L. BENDIXON.

June 9, 1925. **1,540,998**

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 1

Fig. 1.


13
14
7
8
6
5
9
10
11
12

Fig. 2.


1
5
14
C_1
b_1
7
9
10
11
1
a_1
12
2
6
13
15

Fig. 3.


A
O
S
a
a
a
a
8
7
1
M
2
E.

Fig. 4.


S
5
8
7
1
M
2
6
E
E_1

Fig. 5.


A
S
5
8
7
7a
9
E
6

Fig. 6



Inventor
Hermann Plauson

by Knight Bros
attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 2


A
S
1
M
2
7
7b
8
E
E1
E2

Fig. 7.


A
X
5
9
X1
X4
1
M
7
8
X5
X2
6
2
9a
X3
E1
E

Fig. 8.


A
S
X
8
X2
5
1
M
X1
9
2
X3
7
6
X4
E
E1

Fig. 9.


A
S
5
8
7
9
10
6
E

Fig. 10.


A
S
9
1
7
8
10
M
2
5
E

Fig. 11.


A
S
X
9
10
1
5
7
2
9a
10a
X1

Fig. 12.


A
S
X
5
9
1
4a
4
M
3
3a
8
X1
2
7
E

Fig. 13.

Inventor
Normann Plauson
by Knight Bros
attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 3


S
A
x
8
1
4
10
3a
5
M
9
3
2
4a
7
E

Fig. 14.


S
A
5
1
4
x
x1
3a
M
9
3
2
6
z
4a
7
E

Fig. 15.


S
A
8
5
4
6
1
3a
9
M
3
2
4a
7

Fig. 16.


S
A
1
R
1a
M
2a
8
2
7
E1
E

Fig. 17.


S
A
1
6
9
M
2
7
8
E2
E1
E

Fig. 18.


A
N
1
8
R
1²
1¹
2
5
x
7
E
E2
E

Fig. 19.


z
z
z
A1
A2
A3
A4
A5
A10
A9
A8
A7
A6
n
n
n
n
x
x1
x5
n
x9
n
n
x6
A
S
5
1
7
8
2
E

Fig. 20.

Inventor
Hermann Plauson
by Knight Bros
Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 4



Fig. 22.

Fig. 23.

Fig. 21.

X
5
Z
D1
5a
5b
C3
M
D1
E3
5a
5c
D3
E2
E1
5b
M
C1
C2
M
A
C
D
1
2
3a
3
4
4a
7
E

Inventor

Hermann Plauson

by Knight Bros

Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 5


A
a
b
c
d
e
2
L
3a
3
3b
W
12
20
18
19
S_1
17
16
13
21
22
23
24
11
S_2
5
14
8
7
9
10
15
6
E_1
E_2

Fig. 24.

Inventor
Hermann Plauson
by Knight Bros
Attorneys

Fig. 25.


A1
A2
A3
A4
S1
S2
S3
S4
Sa
Sb
Sc
Sd
R.
16
17
18
19
20
21
22
23
24
25
26
27
28
13
12
J.
5
6
7
8
M
E1
E2

Inventor

Hermann Plauson

by

Knight Bros

attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 7


1
2
3
4
5
6
7
8
I
S
19
S1
abcd
F1
16
A
18
17
12
14
g
9
F
10
11
K
13
B
B1
15
14
E1
E

Fig. 26.

Inventor
Hermann Plauson
by
Knight Bros
Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921. 12 Sheets-Sheet 8


22
23
II
I
6
3
2
5
9
10
S_I
E_I
19
11
f
F
S
E
20
17
13
12
F_I
S_{II}
E_{II}
I
1
4
21
II

Fig. 27.

Inventor

Hermann Plauson

by Knight Bros

Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 9



1
2
4
5
3
6
II
8
7
II
I
I
III
III
II1
I1
20
19
II1
9
12
10
A
a
14
F
B
b
13
S1
S
E1
E

Fig. 28.

Inventor
Hermann Plauson
by
Knight Bros
attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921. 12 Sheets-Sheet 10


B
C
K
L
P
+
−
N
P
+
−
N
9
−
E

Fig. 29.


a
b
a
b
F
B
C
K
L
P
+
N
−
9
5
−
E

Fig. 30.

Inventor
Hermann Plauson
by
Knight Bros
Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 11


z
B
C
K
L
P
+
+
−
−
9
10
11
−
E

Fig. 31.


z
B
C
K
L
5
6
+
−
9
G
N
−
E

Fig. 32.



Fig. 33.

Inventor
Hermann Plauson
by Knight Bros
attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 12


A
1
+
+
5
3
2
+
6
–
8
7
9
10
S
E
E1

Fig. 34


A
5
n
+
1
8
10
9
13
12
+
3
6
–
2
–
11
m
S
E
E1

Fig. 35.


5
1
2
11
12
8
3
7
9
10
S
E
E1

Fig. 36.


5
1
2
9
10
3
8
S
E
E1

Fig. 37.

Inventor

Hermann Plauson

by Knight Bros

attorneys

Patented June 9, 1925. **1,540,998**

UNITED STATES PATENT OFFICE.

HERMANN PLAUSON, OF HAMBURG, GERMANY.

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY.

Application filed January 13, 1921. Serial No. 437,107.

To all whom it may concern:

Be it known that I, HERMANN PLAUSON, Esthonian subject, residing in Hamburg, Germany, have invented certain new and useful Improvements in the Conversion of Atmospheric Electric Energy, of which the following is a specification.

Methods of obtaining atmospheric electricity by means of metallic nettings set with spikes which are held by means of ordinary or anchored kite balloons made of fabrics and filled with hydrogen, are in theory already known. Atmospheric electricity obtained in this way has been suggested to be used in the form of direct current for the charging of accumulators. This knowledge however is at present only theoretical as the conversion in practice has hitherto been a failure. No means are known of protecting the apparatus from destruction by lightning. The balloons used for collecting the charge must also be made of very large size in order to be able to support the weight of the metallic netting and the heavy cable connections.

Instead of using heavy metallic netting as collectors attached to single air balloons of non-conducting materials which are liable to be torn and are permeable to the gas, it is proposed to use metallic balloon collectors which have the following important advantages—

(*a*) The metallic cases are impenetrable to helium and hydrogen; they also represent large metallic weather-proof collecting surfaces.

(*b*) Radio active means and the like may be easily applied internally or externally; whereby the ionization is considerably increased and therewith also the quantity of atmospheric electricity capable of being collected.

(*c*) Such balloon collectors of light metal do not require to be of large size as they have to carry only their own moderate weight, and that of the conducting cable or wire.

(*d*) The entire system therefore offers little surface for the action of storm and wind and is resistant and stable.

(*e*) Each balloon can be easily raised and lowered by means of a winch so that all repairs, recharging and the like can be carried out without danger during the operation.

It is further proposed to use a collecting aerial network of several separate collectors spread out in the air above the earth, which collectors are interconnected by electrical conductors.

According to this invention charges of atmospheric electricity are not directly converted into mechanical energy, and this forms the main difference from previous inventions, but the static electricity which runs to earth through aerial conductors in the form of direct current of very high voltage and low current strength is converted into electro-dynamic energy in the form of high frequency vibrations. Many advantages are thereby obtained and all disadvantages avoided.

The very high voltage of static electricity of a low current strength can be converted by this invention to voltages more suitable for technical purposes and of greater current strength. By the use of closed oscillatory circuits it is possible to obtain electromagnetic waves of various amplitude and thereby to increase the degree of resonance of such current. Such resonance allows various values of inductance to be chosen whereby again the governing of the starting and stopping of machines driven thereby by simply tuning the resonance between coils of the machine and the transformer circuit forming the resonance can easily be obtained. Further, such currents have the property of being directly available for various uses, even without employing them for driving motors, of which there may be particularly mentioned, lighting, production of heat and use in electro-chemistry.

Further, with such currents a series of apparatus may be fed without direct current supply through conductors and also the electro-magnetic high frequency currents may be converted by means of special motors adapted for electro-magnetic oscillations into mechanical energy, or finally converted by special machines into alternating current of low frequency or even into direct current of high potential.

The invention is more particularly described with reference to the accompanying diagrams in which:—

Figure 1 is an explanatory figure.

Figure 2 is a diagrammatic view of the simplest form.

Figure 3 shows a method of converting atmospheric electrical energy for use with motors.

Figure 4 is a diagram showing the use of protective means.

Figure 5 is a diagram of an arrangement for converting large current strengths.

Figure 6 is a diagram of an arrangement including controlling means.

Figure 7 shows means whereby the spark gap length can be adjusted.

Figure 8 shows a unipolar connection for the motor.

Figure 9 shows a weak coupled system suitable for use with small power motors.

Figures 10, 11 and 12 show modified arrangements.

Figure 13 shows a form of inductive coupling for the motor circuit.

Figure 14 is a modified form of Figure 13 with inductive coupling.

Figure 15 is an arrangement with non-inductive motor.

Figure 16 is an arrangement with coupling by condenser.

Figures 17, 18 and 19 are diagrams of further modifications.

Figure 20 shows a simple form in which the aerial network is combined with special collectors.

Figure 21 shows diagrammatically an arrangement suitable for collecting large quantities of energy.

Figure 22 is a modified arrangement having two rings of collectors.

Figure 23 shows the connections for three rings of collectors.

Figure 24 shows a collecting balloon and diagram of its connection of condenser batteries.

Figures 25 and 26 show modified collector balloon arrangements.

Figure 27 shows a second method of connecting conductor for the balloon aerials.

Figure 28 shows an auto-transformer method of connection.

Figure 29 shows the simplest form of construction with incandescent cathode.

Figure 30 shows a form with cigar shaped balloon.

Figure 31 is a modified arrangement.

Figure 32 shows a form with cathode and electrode enclosed in a vacuum chamber.

Figure 33 is a modified form of Figure 32.

Figure 34 shows an arc light collector.

Figure 35 shows such an arrangement for alternating current.

Figure 36 shows an incandescent collector with Nernst lamp.

Figure 37 shows a form with a gas flame.

Figure 1 illustrates a simple diagram for converting static electricity into dynamic energy of a high number of oscillations. For the sake of clearness in the drawings an influence machine is assumed to be employed and not an aerial antenna. 13 and 14 are combs for collecting the static electricity of the influence machine. 7 and 8 are spark discharging electrodes, 6 and 5 condensers, 9 an inductive primary coil, 10 secondary coil, 11 and 12 ends of conductors of the secondary coil 10. When the disc of the static influence machine is rotated by mechanical means, the combs collect the electric charges one the positive and the other the negative, and charge the condensers 5 and 6 until such a high potential is formed across the spark gap 7—8, that the spark gap is jumped. As the spark gap 7—8 forms a closed circuit with condensers 6 and 5, and inductive resistance 9, as is well known, waves of high frequency electromagnetic oscillations will pass in this circuit.

The high frequency of the oscillations produced in the primary circuit induces waves of the same periodicity in the secondary circuit. Thus in the primary circuit electromagnetic oscillations are formed by the passage of the spark over the spark gap and these waves are maintained by fresh charges of static electricity.

By suitably selecting the ratio between the number of the coils in the primary and secondary circuits with regard to a correct application of the co-efficients of resonance (capacity, inductance, and resistance) the high voltage of the primary circuit may be suitably converted into low voltage and high current strength.

When the oscillatory discharges in the primary circuit becomes weaker or entirely cease, the condensers are charged again by the static electricity until the accumulated charge again breaks down the spark gap. All this is repeated as long as electricity is produced by the static machine by employing mechanical energy.

An elementary form of the invention is shown in Figure 2 in which two spark gaps in parallel are used one of which may be termed the working gap 7 in Figure 2, whilst the second serves as a safety device for excess voltage and consists of a larger number of spark gaps than the working section, which gaps are arranged in series and are bridged by very small capacities as is illustrated in a_1, b_1, c_1, Figure 2 which allow of uniform sparking in the safety section.

In Figure 2 A is the aerial antenna for collecting charges of atmospheric electricity, 13 is the earth connection of the second part of the spark gap, 5 and 6 are condensers, 9 a primary coil. Now when through the aerial A the positive atmospheric electricity seeks to combine with the negative charge to earth, this is prevented by (the air gap between) the spark gaps. The resistance of the spark gap 7 is, as shown in the drawings, lower than that of the other safety section which consists of three spark gaps connected in

series, and consequently a three times greater air resistance is offered by the latter.

So long therefore, as the resistance of the spark gap 7 is not overloaded, so that the other spark gaps have an equal resistance with it the discharges take place only over spark gap 7. Should however the voltage be increased by any influences so that it might be dangerous for charging the condensers 5 and 6 or for the coil insulation 9 and 10 in consequence of break down, by a correct regulation of this spark gap the second spark gap can discharge free from inductive effects direct to earth without endangering the machine.

Without this second spark gap, arranged in parallel having a higher resistance than the working spark gap it is impossible to collect and render available large quantities of electrical energy.

The action of this closed oscillation circuit consisting of spark gap 7, two condensers 5 and 6, primary coil 9, and also secondary coil 10 is exactly the same as the one described in Figure 1 with the arrangement of the static induction machine with the only difference that here the second spark gap is provided. The electromagnetic high frequency alternating current obtained can be tapped off from the conductors 11 and 12 for lighting and heating purposes. Special kinds of motors adapted for working with these peculiar electrical charges may be connected at 14 and 15 which can work with static electricity charges or with high frequency oscillations.

In addition to the use of spark gaps in parallel a second measure of security is also necessary for taking off the current. This precaution consists according to this invention, in the introduction of and method of connecting certain protective electromagnets or choking coils in the aerial circuit as shown by S in Figure 3.

A single electromagnet only having a core of the thinnest possible separate laminations is connected with the aerial.

In the case of high voltages in the aerial network or at places where there are frequent thunder storms, several such magnets may however be connected in series.

In the case of large units or plants several electromagnets can be employed in parallel or in series parallel.

The windings of these electromagnets may be simply connected in series with the aerials. In this case the winding preferably consists of several thin parallel wires, which make up together, the necessary section.

The winding may be made of primary and secondary windings in the form of a transformer. The primary winding will be then connected in series with the aerial network, and the secondary winding more or less short-circuited over a regulating resistance or an induction coil. In the latter case it is possible to regulate to a certain extent the effect of the choking coils. In the further description of the connecting and constructional diagrams the aerial electromagnet choke coil is indicated by a simple ring S.

Figure 3 shows the simplest way of converting atmospheric electricity into electromagnetic wave energy by the use of special motors adapted for high oscillatory currents or static charges of electrical energy. Recent improvements in motors for working with static charges and motors working by resonance, that is to say, having groups of tuned electromagnetic cooperating circuits render this possible but such do not form part of the present invention.

A motor adapted to operate with static charges will for the sake of simplicity be diagrammatically indicated by two semicircles 1 and 2 and the rotor of the motor by a ring M. (Figure 3.) A is a vertical aerial or aerial network. S the safety choke or electromagnet with coil O as may be seen is connected with the aerial A. Adjacent the electromagnet S the aerial conductor is divided into three circuits, the circuit 8 giving the safety spark gap, the circuit 7 with the working spark gap, and then a circuit including the stator terminal 1, the rotor and stator terminal 2 at which a connection is made to the earth wire. The two spark gaps are also connected metallically with the earth wire. The method of working these diagrams is as follows:

The positive atmospheric electric charge collected tends to combine with the negative electricity (or earth electricity) connected with the earth wire. It travels along the aerial A through the electromagnet S without being checked as it flows in the same direction as the direct current. Further, its progress is arrested by two sparks gaps placed in the way and the stator condenser surfaces. The stator condenser surfaces are charged until the charge is greater than the resistance of the spark gap 7, whereupon a spark springs over the spark gap 7 and an oscillatory charge is obtained as by means of the motor M, stator surfaces 1 and 2, and spark gap 7, a closed oscillation circuit is obtained for producing the electromagnetic oscillations. The motor here forms the capacity and the necessary inductance and resistance, which, as is well known, are necessary for converting static electricity into electromagnetic wave energy.

The discharges formed are converted into mechanical energy in special motors and can not reach the aerial network by reason of the electromagnet or choke. If, however, when a spark springs over the spark gap 7 a greater quantity of atmospheric electricity tends to flow to earth, a counter voltage is

induced in the electromagnet, which is greater the more rapidly and strongly the flow of current direct to the earth is. By the formation of this opposing voltage a sufficiently high resistance is offered to the flow of atmospheric electricity direct to earth to prevent a short circuit with the earth.

The circuit containing spark gap 8 having a different wave length which is not in resonance with the natural frequency of the motor, does not endanger the motor and serves as security against excess voltage, which, as practical experiments have shown, may still arise in certain cases, but can be conducted direct to earth through this spark gap.

In the diagram illustrated in Figure 4 the spark gap 7 is shunted across condensers 5 and 6 from the motor M. This construction affords mainly a better insulation of the motor against excess voltage and a uniform excitation through the spark gap 7.

In Figure 5 a diagram is illustrated for transforming large current strengths which may be employed direct without motors, for example, for lighting or heating purposes. The main difference is that here the spark gap consists of a star shaped disc 7 which can rotate on its own axis and is rotated by a motor opposite similarly fitted electrodes 7^a. When separate points of stars face one another, discharges take place, thus forming an oscillation circuit over condensers 5 and 6 and inductance 9 for oscillatory discharges. It is evident that a motor may also be directly connected to the ends of the spiral 9.

The construction of the diagram shown in Figure 6 permits of the oscillation circuit of the motor being connected with an induction coil. Here a regulating inductive resistance is introduced for counter-acting excess voltages in the motor. By cutting the separate coils 9 (coupled inductively to the aerial) in or out the inductive action on the motor may be more or less increased or variable aerial action may be exerted on the oscillation circuit.

In Figure 7 the oscillation circuit is closed through the earth (E and E_1). The spark gap 7 may be prolonged or shortened by more or fewer spark gaps being successively connected by means of a contact arm 7^b.

Diagram 8 shows a unipolar connection of the motor with the aerial network. Here two oscillation circuits are closed through the same motor. The first oscillation circuit passes from aerial A through electromagnet S, point x, inductance 9^a to the earth condenser 6 and further, over spark gap 7 to the aerial condenser 5 and back to x. The second oscillation circuit starts from the aerial condenser 5 at the point x^1 over the inductance 9 to the earth condenser 6 at the point x^3 and through the condenser 6 over the spark gap 7 back to x^1. The motor itself is inserted between the two points of the spark gap 7. From this arrangement slightly damped oscillation wave currents are produced.

In the diagram illustrated in Figure 9 a loosely coupled system of connections is illustrated which is assumed to be for small motors for measuring purposes. A indicates the aerial conductor, S the electromagnet in the aerial conductor, 9 the inductance, 7 the spark gap, 5 and 6 condensers, E the earth, M the motor, and 1 and 2 stator connections of the motor. The motor is directly metallically connected with the oscillation circuit.

In Figure 10 a purely inductive coupling is employed for the motor circuit. The motor is connected with the secondary wire 10 as may be seen in Figure 11 in a somewhat modified diagram connection. The same applies to the diagram of Figure 12.

The diagrams hitherto described preferably allow of motors of small and medium strength to be operated. For large aggregates, however, they are too inconvenient as the construction of two or more oscillation circuits for large amounts of energy is difficult; the governing is still more difficult and the danger in switching on or off is greater.

A means of overcoming such difficulties is shown in Figure 13. The oscillation circuit here runs starting from the point x over condenser 5, variable inductance 9, spark gap 7 and the two segments (3^a and 4^a) forming arms of a Wheatstone bridge, back to x. If the motor is connected by brushes 3 and 4 transversely to the two arms of the bridge as shown in the drawings, electromagnetic oscillations of equal sign are induced in the stator surfaces 1 and 2 and the motor does not revolve. If however, the brushes 3 and 4 are moved in common with the conducting wires 1 and 2 which connect the brushes with the stator poles a certain alteration or displacement of the polarity is obtained and the motor commences to revolve.

The maximum action will result if one brush 3 comes on the central sparking contact 7 and the other brush 4 on the part x. They are however, usually in practice not brought on to the central contact 7 but only held in the path of the bridge segments 4^a and 3^a in order not to connect the spark gaps with the motor oscillation circuit.

As however, the entire oscillation energy can thereby not act on the motor it is better to carry out the same system according to the diagram 14. The diagram 14 differs from the foregoing only by the motor not being directly metallically connected with the segments of the commutator, but only a primary coil 9 which induces in a secondary coil 10, current which feeds the motor M and takes the place of the rotor. By this

arrangement a good transforming action is obtained, a loose coupling and also an oscillation circuit without a spark gap.

In Figure 15 the motor is not purely inductively as in 14, but directly metallically branched off from the primary coil (at x and x^1) after the principle of the auto-transformer.

In Figure 16 instead of an inductance a condenser 6 is in similar manner, and for the same object inserted between the segments 3^a and 4^a. This has the advantage that the segments 3^a and 4^a need not be made of solid metal but may consist of spiral coils whereby a more exact regulation is possible and further motors of high inductance may be employed.

The arrangements of Figures 17, 18 and 19 may be employed for use with resonance and particularly with induction condenser motors; between the large stator induction condenser surfaces, small reversing pole condensers are connected, which, as may be seen from Figures 17, 18 and 19 are led together to earth. Such reversing poles have the advantage that with large quantities of electrical energy the spark formation between the separate oscillation circuits ceases.

Figure 19 shows a further method which prevents electromagnetic oscillations of high number of alternations formed in the oscillation circuit striking back to the aerial conductor. It is based on the well known principle that a mercury lamp, one electrode of which is formed of mercury, the other of solid metal such as steel allows an electric charge to pass in only one direction from the mercury to the steel and not vice versa. The mercury electrode of the vacuum tube N is therefore connected with the aerial conductor and the steel electrode with the oscillation circuit. From this it results that charges can pass only from the aerial through the vacuum tube to the oscillation circuit, but not vice versa. Oscillations which are formed on being transformed in the oscillation circuit cannot pass to the aerial conductor.

In practice these vacuum tubes must be connected behind an electromagnet as the latter alone affords no protection against the danger of lightning.

As regards the use of spark gaps, all arrangements as used for wireless telegraphy may be used. Of course the spark gaps in large machines must have a sufficiently large surface. In very large stations they are cooled in liquid carbonic acid or better still in liquid nitrogen or hydrogen; in most cases the cooling may also take place by means of liquefied low homologues of the metal series or by means of hydrocarbons the freezing point of which lies at between −90° C. and −40° C. The spark gap casing must also be insulated and be of sufficient strength to be able to resist any pressure which may arise. Any undesirable excess super-pressure which may be formed must be automatically let off. I have employed with very good results mercury electrodes which were frozen in liquid carbonic acid, the cooling being maintained during the operation from the outside through the walls.

Figure 20 is one of the simplest forms of construction of an aerial network in combination with collectors, transformers and the like illustrated diagrammatically. E is here the earth wire, 8 the safety spark gap, 7 the working spark gap, 1 and 2 the stator surfaces of the motor, 5 a condenser battery, S the protective magnet which is connected with the coil in the aerial conductor, A^1 to A^{10} aerial antennæ with collecting balloons, N horizontal collecting or connecting wires from which, to the centre a number of connections run.

The actual collectors consist of metal sheaths preferably made of an aluminium magnesium alloy, and are filled with hydrogen or helium and are attached to copper plated steel wires. The size of the balloon is selected so that the actual weight of the balloon and the weight of the conducting wire is supported thereby. On the top of the balloon aluminium spikes, made and gilded in a special manner hereinafter described, are arranged in order to produce a conductor action. Small quantities of radium preparations, more particularly polonium-ionium or mesothorium preparations considerably increase the ionization, and therewith the action of these collectors.

In addition to metal balloons, fabric balloons which are superficially metal coated according to Schoop's metal spraying process, may however also be employed. A metallic surface may also be produced by lacquering with metallic bronzes, preferably according to Schoop's spraying process or lacquering with metallic bronze powders in two electrical series of widely different metals, because thereby the collecting effect is considerably increased.

Instead of the ordinary round balloons, elongated cigar shaped ones may be employed. In order also to utilize the frictional energy of the wind, patches or strips of non-conducting substances which produce electricity by friction, may be attached to the metallized balloon surfaces. The wind will impart a portion of its energy in the form of frictional electricity, to the balloon casing, and thereby the collecting effect is substantially increased.

In practice however, very high towers (up to 300 metres is fully admissible) may be employed as antennæ. In these towers copper tubes rise freely further above the top of the tower. A gas lamp secured

against the wind is then lit at the point of the copper tube and a netting is secured to the copper tube over the flame of this lamp to form a collector. The gas is conveyed through the interior of the tube up to the summit. The copper tube must be absolutely protected from moisture at the place at which it enters the tower and also rain must be prevented running down the walls of the tower which might lead to a bad catastrophe. This is done by bell shaped enlargements which expand downwards, being arranged in the tower in the form of high voltage insulators of Siamese pagodas.

Special attention must be devoted to the foundations of such towers. They must be well insulated from the ground, which may be obtained by first embedding a layer of concrete in a box form to a sufficient depth in the ground and inserting in this an asphalt lining and then glass bricks cast about 1 or 2 metres in thickness. Over this in turn there is a ferro-concrete layer in which alone the metal foot of the tube is secured. This concrete block must be at least 2 metres from the ground and be fully protected at the sides by a wooden covering, from moisture. In the lower part of the tower a wood or glass house for the large condenser batteries or for the motors may be constructed. In order to lead the earth connection to the ground water, a well insulated pit constructed of vitreous bricks, must be provided. Several such towers are erected at equal distances apart and connected with a horizontal conductor. The horizontal connecting wires may either run directly from tower to tower or be carried on bell shaped insulators similar to those in use for high voltage conductors. The width of the network may be of any suitable size and the connection of the motors can take place at any suitable places.

In order to collect large quantities of electricity with few aerials it is well to provide the aerial conductor with batteries of condensers as shown in two methods of construction in Figures 21 and 22. In Figure 21 the batteries of condensers 5 are connected on the one hand with the aerial electricity collectors Z by the aerial conductor A, and on the other hand interconnected in series with an annular conductor from which horizontal conductors run to the connecting points C to which the earth wire is connected.

Figure 22 shows a similar arrangement. Should two such series of antennæ rings be shown by a voltmeter to have a large difference of potential (for example, one in the mountains and one in the plain) or even of different polarity these differences may be compensated for by connecting sufficiently large condenser batteries ($5, 5^a, 5^b$) by means of Maji star conductors D and D^1. In Figure 23 a connection of three such rings of collectors to form a triangle with a central condenser battery is illustrated.

The condenser batteries of such large installations must be embedded in liquefied gases or in liquids freezing at very low temperatures. In such cases a portion of the atmospheric energy must be employed for liquefying these gases. It is also preferable to employ pressure. By this means the condenser surfaces may be diminished, and still allow for large quantities of energy to be stored, secure against breakdown. For smaller installations the immersing of the condensers in well insulated oil or the like, suffices. Solid substances on the other hand cannot be employed as insulators.

The arrangement in the diagrams hitherto described was always such that the condenser batteries were connected with both poles directly to the aerial conductors. An improved diagram of the connections for obtaining atmospheric electricity for the condenser batteries has however, been found to be very advantageous, this arrangement consists in that they are connected by only one pole (unipolar) to the collecting network. Such a method of arrangement is very important, as by means of it a constant current and an increase of the normal working pressure or voltage is obtained. If for example a collecting balloon aerial which is allowed to rise to a height of 300 metres, shows 40,000 volts above earth voltage, in practice it has been found that the working voltage (with a withdrawal of the power according to the method hereinbefore described by means of oscillating spark gaps and the like) is only about 400 volts. If however, the capacity of the condenser surfaces be increased, which capacity in the above mentioned case was equal to that of the collecting surface of the balloon aerials, to double the amount, by connecting the condenser batteries with only one pole, the voltage rises under an equal withdrawal of current up to and beyond 500 volts. This can only be ascribed to the favourable action of the connecting method.

In addition to this substantial improvement it has also been found preferable to insert double inductances with electromagnets and to place the capacities preferably between two such electromagnets. It has also been found that the useful action of such condensers can be further increased if an induction coil be connected as inductive resistance to the unconnected pole of the condenser, or still better if the condenser itself be made as an induction condenser. Such a condenser may be compared with a spring which when compressed carries in itself accumulated force, which it again gives off when released. In charging, a charge with reversed sign is formed at the

other free condenser pole, and if through the spark gap a short circuit results, the accumulated energy is again given back since now new quantities of energy are induced at the condenser pole connected with the conductor network, which in fact charges with opposite signs to that at the free condenser pole. The new induced charges have of course the same sign as the collector network. The whole voltage energy in the aerial is thereby however increased. In the same space of time larger quantities of energy are accumulated than is the case without such inserted condenser batteries.

In Figures 24 and 25 two different diagrams of connections are more exactly illustrated, Figure 24 shows a collecting balloon and the diagram of the connections to earth. Figure 25 four collecting balloons and the parallel connection of the condenser batteries belonging thereto.

A is the collecting balloon made of an aluminium magnesium alloy (electron metal, magnalium) of a specific gravity of 1.8 and a thickness of plate 0.1 to 0.2 mm. Inside there are eight strong vertical ribs of T shaped section about 10 to 20 mm. in height and about 3 mm. in thickness with the projecting part directed inwards (indicated by *a*, *b*, *c*, *d* and so forth); they are riveted together to form a firm skeleton and are stiffened in a horizontal direction by two cross ribs. The ribs are further connected with one another internally and transversely by means of thin steel wires, whereby the balloon obtains great power of resistance and elasticity. Rolled plates of 0.1 to 0.2 mm. in thickness made of magnalium alloy are then either soldered or riveted on this skeleton so that a fully metallic casing with smooth external surface is obtained. Well silvered or coppered aluminium plated steel wires run from each rib to the fastening ring 2. Further, the coppered steel hawser L preferably twisted out of separate thin wires (shown in dotted lines in Figure 24) and which must be long enough to allow the balloon to rise in the desired height, leads to a metal roller or pulley 3 and from thence to a winch W, well insulated from the earth. By means of this winch, the balloon, which is filled with hydrogen, or helium, can be allowed to rise to a suitable height (300 to 5,000 metres) and brought to the ground for recharging or repairs.

The actual current is taken directly through a friction contact from the metal roller 3 or from the wire, or even from the winch or simultaneously from all three by means of brushes (3, 3^a and 3^b). Beyond the brushes the conductor is divided, the paths being:—firstly over 12 to the safety spark gap 8, from thence to the earth conductor E^1, and secondly over electromagnet S^1, point 13, to a second loose electromagnet having an adjustable coil S^2, then to the spark gap 7 and to the second earth conductor E^2. The actual working circuit is formed through the spark gap 7, condensers 5 and 6, and through the primary coil 9; here the static electricity formed by oscillatory discharges is accumulated and converted into high frequency electromagnetic oscillations. Between the electromagnets S^1 and S^2 at the crossing point 13, four condenser batteries are introduced which are only indicated diagrammatically in the drawings each by one condenser. Two of these batteries (16 and 18) are made as plate condensers and prolonged by regulating induction coils or spirals 17 and 19 while the two others (21 and 23) are induction condensers. As may be seen from the drawings each of the four condenser batteries 16, 18, 21, 23 is connected only by one pole to the aerial or to the collector conductor. The second poles 17, 19, 22, 24 are open. In the case of plate condensers having no inductive resistance an induction coil is inserted. The object of such a spiral or coil is the displacement of phase of the induction current by ¼ periods, whilst the charging current of the condenser poles which lie free in the air, works back to the collector aerial. The consequence of this is that in discharges in the collector aerial the back inductive action of the free poles allows a higher voltage to be maintained in the aerial collecting conductor than would otherwise be the case. It has also been found that such a back action has an extremely favourable effect on the wear of the contacts. Of course the inductive effect may be regulated at will within the limits of the size of the induction coil, the length of the coil in action being adjustable by means of wire connection without induction (see Fig. 24, No. 20).

S^1 and S^2 may also be provided with such regulating devices in the case of S^2 (illustrated by 11). If excess voltage be formed it is conducted to earth through the wire 12 and spark gap 8 or through any other suitable apparatus, since this formation would be dangerous for the other apparatus.

The action of these condenser batteries has already been hereinbefore described.

The small circles on the collector balloon indicate places at which zinc amalgam or gold amalgam or other photoelectric acting metals in the form of small patches in extremely thin layers (.01 to .05 mm. in thickness) are applied to the balloon casing of light metal. Such metallic patches may also be applied to the entire balloon as well as in greater thickness to the conducting network. The capacity of the collector is thereby considerably strengthened at the surface. The greatest possible effect in collecting may be obtained by polonium amalgams and the like. On the surface of the

collector balloon metal points or spikes are also fixed along the ribs, which spikes serve particularly for collecting the collector charge. Since it is well known that the resistance of the spikes is less the sharper the spike is, for this purpose it is therefore extremely important to employ as sharp spikes as possible. Experiments made as regards these have shown that the formation of the body of the spike or point also plays a large part. for example, spikes made of bars or rollers with smooth surfaces, have a many times greater point resistance as collector accumulator spikes than those with rough surfaces. Various kinds of spike bodies have been experimented with for the collector balloons hereinbefore mentioned. The best results were given by spikes which were made in the following way. Fine points made of steel, copper, nickel, or copper and nickel alloys, were fastened together in bundles and then placed as anode with the points in a suitable electrolyte (preferably in hydrochloric acid or muriate of iron solutions) and so treated with weak current at 2 to 3 volts pressure. After 2 to 3 hours according to the thickness of the spikes or pins the points become extremely sharp and the bodies of the spikes have a rough surface. The bundle can then be removed and the acid washed off with water. The spikes are then placed as cathode in a bath consisting of solution of gold, platinum, iridium, paladium or wolfram salts or their compounds and coated at the cathode galvanically with a thin layer of precious metal, which must however be sufficiently firm to protect them from atmospheric oxidation.

Such spikes act at a 20 fold lower voltage almost as well as the best and finest points made by mechanical means. Still better results are obtained if polonium or radium salts are added to the galvanic bath when forming the protective layer or coating. Such pins have a low resistance at their points and even at one volt and still lower pressures have an excellent collector action.

In Figure 24 the three unconnected poles are not connected with one another in parallel. That is quite possible in practice without altering the principle of the free pole. It is also preferable to interconnect in parallel to a common collector network, a series of collecting aerials.

Figure 25 shows a diagram for such an installation. A^1, A^2, A^3, A^4 are four metal collector balloons with gold or platinum coated spikes which are electrolytically made in the presence of polonium emanations or radium salts, which spikes or needles are connected over four electro-magnets S^1, S^2, S^3, S^4, through an annular conductor R. From this annular conductor four wires run over four further electromagnets S^a, S^b, S^c, S^d, to the connecting point 13. There the conductor is divided, one branch passing over 12 and the safety spark gap 8 to the earth at E^1, the other over inductive resistance J and working spark gap 7 to the earth at E^2. The working circuit, consisting of the condenser 5 and 6 and a resonance motor or a condenser motor M, such as hereinbefore described, is connected in proximity round the sparking gap section 7.

Instead of directly connecting the condenser motor of course the primary circuit for high frequency oscillatory current may also be inserted.

The condenser batteries are connected by one pole to the annular conductor R and can be either inductionless (16 and 18) or made as induction condensers as shown by 21 and 23. The free poles of the inductionless condensers are indicated by 17 and 19, those of the induction condensers by 22 and 24. As may be seen from the drawings all these poles 17, 22, 19, 24 may be interconnected in parallel through a second annular conductor without any fear that thereby the principle of the free pole connection will be injured. In addition to the advantages already set forth the parallel connection also allows of an equalization of the working pressure in the entire collector network. Suitably constructed and calculated induction coils 25 and 26 may also be inserted in the annular conductor of the free poles, by means of which a circuit may be formed in the secondary coils 27 and 28 which allows current produced in this annular conductor by fluctuations of the charges or the like appearances to be measured or otherwise utilized.

According to what has been hereinbefore stated separate collector balloons may be connected at equidistant stations distributed over the entire country, either connected directly with one another metallically or by means of intermediate suitably connected condenser batteries through high voltage conductors insulated from earth. The static electricity is converted through a spark gap into dynamic energy of a high number of oscillations and may in such form be coupled as a source of energy by means of a suitable method of connecting, various precautions being observed and with special regulations. The wires leading from the collector balloons have hitherto been connected through an annular conductor without this endless connection, which can be regarded as an endless induction coil, being able to exert any action on the whole conductor system.

It has now been found that if the network conductor connecting the aerial collector balloons with one another is not made as a simple annular conductor, but preferably short circuited in the form of coils over a

condenser battery or spark gap or through thermionic tubes or valves or audions, then the total collecting network exhibits quite new properties. The collection of atmospheric electricity is thereby not only increased but an alternating field may be easily produced in the collector network. Further, the atmospheric electrical forces showing themselves in the higher regions may also be directly obtained by induction. In Figures 26 and 28 a form of construction is shown on the basis of which the further foundations of the method will be more particularly explained.

In Figure 26 1, 2, 3, 4 are metal collector balloons, 5, 6, 7, 8 their metallic aerial conductors and I the actual collector network. This consists of five coils and is mounted on high voltage insulators in the air, on high voltage masts (or with a suitable construction of cable embedded in the earth). One coil has a diameter of 1 to 100 km. or more. S and S^1 are two protective electromagnets, F the second safety section against excess voltage, E its earth conductor and E^1 the earth conductor of the working section. When an absorption of static atmospheric electricity is effected through the four balloon collectors, the current in order to reach the earth connection E^1 must flow spirally through the collector network over the electromagnet S, primary induction coil 9, conductor 14, anode A of the audion tube, incandescent cathode K, as the way over the electromagnet and safety spark gap F offers considerably greater resistance. Owing to the fact that the accumulated current flows in one direction, an electromagnetic alternating field is produced in the interior of the collector network coil, whereby the whole free electrons are directed more or less into the interior of the coil. An increased ionization of the atmosphere is therefore produced. In consequence of this the points mounted on the collector balloon show a considerably reduced resistance and therefore increased static charges between the points on the balloon and the surrounding atmosphere are produced. The result of this is a considerably increased collector effect.

A second effect which could not be obtained otherwise is obtained by the electromagnetic alternating field which running parallel to the earth surface, acts more or less with a diminishing or increasing effect on the earth magnetic field, whereby in the case of fluctuations in the current a return induction current of reversed sign is always produced in the collector coil by earth magnetism. Now if, however, a constantly pulsating continuous alternating field is produced as stated in the above collector network I, an alternating current of the same periodicity is produced also in the collecting network coil. As the same alternating field is further transmitted to the aerial balloon, the resistance of its points is thereby considerably reduced, whilst the collector action is considerably increased. A further advantage is that positive electrons which collect on the metal surfaces during the conversion into dynamic current produce a so-called drop of potential of the collector area. As an alternating field is present, the negative ions surrounding the collector surfaces, when discharge of the collector surfaces takes place produce by the law of induction, an induction of reversed sign on the collector surface and so forth (that is to say again a positive charge). In addition to the advantages hereinbefore set forth, the construction of connecting conductors in coil form when of sufficiently large diameter, allows of a utilization of energy arising in higher regions also in the simplest way. As is well known electric discharges frequently take place at very great elevations which may be observed, such as St. Elmo's fires or northern lights. These energy quantities have not been able to be utilized up to now. By this invention all these kinds of energy, as they are of an electromagnetic nature and the direction of the axis of the collector coils stands at right angles to the earth's surface, can be more or less absorbed in the same way as a receiver in wireless telegraphy absorbs waves coming from a far distance. With a large diameter of the spiral it is possible to connect large surfaces and thereby to take up also large quantities of energy.

It is well known that large wireless stations in the summer months, and also in the tropics are very frequently unable to receive the signals in consequence of interruptions which are caused by atmospheric electricity, and this takes place with vertical coils of only 40 to 100 m. diameter. If on the contrary horizontal coils of 1 to 100 km. diameter be employed very strong currents may be obtained through discharges which are constantly taking place in the atmosphere. Particularly in the tropics or still better in the polar regions where the northern lights are constantly present, large quantities of energy may probably be obtained in this way. A coil with several windings should act the best. In similar manner any alteration of the earth magnetism should act inductively on such a coil.

It is not at all unlikely that earthquakes and spots on the sun will also produce an induction in such collector coils of sufficient size. In similar manner this collector conductor will react on earth currents more particularly when they are near the surface of the earth or even embedded in the earth. By combining the previous kind of current collectors so far as they are adapted for

the improved system with the improved possibilities of obtaining current the quantities of free natural energy which are to be obtained in the form of electricity are considerably increased.

In order to produce in the improved collector coil uniform current oscillations of an undamped nature so-called audion high vacuum or thermionic tubes of suitable connection are employed instead of the previously known spark gaps (Fig. 26, Nos. 9–18). The main aerial current flows through electromagnet S (which in the case of a high number of alternations is not connected here but in the earth conductor E^1) and may be conveyed over the primary coils in the induction winding through wire 14 to the anode A of the high vacuum grid tube. Parallel with the induction resistance 9 a regulating capacity of suitable size, such as condenser 11 is inserted. In the lower part of the vacuum grid tube is arranged the incandescent filament or the cathode K which is fed through a battery B. From the battery B two branches run, one to the earth conductor E^1 and the other through battery B^1 and secondary coil 10 to the grid anode *g* in the vacuum tube. By the method of connections shown in dotted lines, a desired voltage at the grid electrode *g* may also be produced through the wire 17 which is branched off from the main current conductor through switches 16 and some small condensers (*a*, *b*, *c*, *d*) connected in series, and conductor 18, without the battery B^1 being required.

The action of the entire system is somewhat as follows:—

On the connecting conductor of the aerial collector network being short circuited to earth, the condenser pole 11 is charged and slightly damped oscillations are formed in the short circuited existing oscillation circuit formed of the condenser 11 and self inductance 9. In consequence of the coupling through coil 10, fluctuations of voltage take place in the grid circuit 15 with the same frequency, which, fluctuations in turn influence the strength of the electrode current passing through the high vacuum amplyfying tube and thus produce current fluctuations of the same frequency in the anode circuit. A permanent supply of energy to the oscillation circuits 9 and 10 consequently takes place, until a condition of balance is set up, in which the consumed oscillation energy is equal to that absorbed. Thereby constant undamped oscillations are now produced in the oscillation circuits 9–11.

For regular working of such oscillation producers high vacuum strengthening tubes are necessary and it is also necessary that the grid and anode voltages shall have a phase difference of 180° so that if the grid is negatively charged, then the anode is positively charged and vice versa. This necessary difference of phase may be obtained by most varied connections, for example, by placing the oscillation circuit in the grid circuit or by separating the oscillation circuit and inductive coupling from the anodes and the grid circuit and so forth.

A second important factor in this way of converting static atmospheric electricity into undamped oscillations is that care must be taken that the grid and anode voltages have a certain relation to one another; the latter may be obtained by altering the coupling and a suitable selection of the self induction in the grid circuit, or as shown by dotted lines 18, 17, 16 by means of a larger or smaller number of condensers of suitable size connected in series; in this case the battery B^1 may be omitted. With a suitable selection of the grid potential a glow discharge takes place between the grid *g* and the anode A, and accordingly at the grid there is a cathode drop and a dark space is formed. The size of this cathode drop is influenced by the ions which are emitted in the lower space in consequence of shock ionization of the incandescent cathodes K and pass through the grid in the upper space. On the other hand the number of the ions passing through the grid is dependent on the voltage between the grid and the cathode. Thus if the grid voltage undergos periodic fluctuations (as in the present case) the amount of the cathode drop at the grid fluctuates and consequently the internal resistance of the tube correspondingly fluctuates, so that when a back coupling of the feed circuit with the grid circuit takes place, the necessary means are afforded for producing undamped oscillations and of taking current, according to requirements from the collecting conductor.

The frequency of the undamped oscillations produced is with a suitably loose coupling equal to the self frequency of the oscillation circuits 9 and 10. By a suitable selection of the self induction of the coil 9 and capacity 11 it is possible to extend from frequencies which produce electromagnetic oscillations of only a few metres wave length down to the lowest practical alternating current frequency. For large installations a suitable number of frequency producing tubes in the form of the well known high vacuum transmission tubes of .5 to 2 kw. in size may be connected in parallel so that in this respect no difficulty exists.

The use of such tubes for producing undamped oscillations, and also the construction and method of inserting such transmission tubes in an accumulator or dynamo circuit is known and also that such oscillation producing tubes only work well at voltages of 1,000 up to 4,000 volts, so that on the contrary their use at lower voltages is

considerably more difficult. By the use of high voltage static electricity this method of producing undamped oscillations as compared with that through spark gaps must be regarded as an ideal solution particularly for small installations of outputs of from 1 to 100 kw.

By the application of safety spark gaps, with interpolation of electro-magnets, not only is short circuiting avoided but also the taking up of current is regulated. Oscillation producers inserted in the above way form a constantly acting electromagnetic alternating field in the collector coil, whereby as already stated, a considerable accumulating effect takes place. The withdrawal wire or working wire is connected at 12 and 13, but current may be taken by means of a secondary coil which is firmly or movably mounted in any suitable way inside the large collector coil, i. e. in its electromagnetic alternating field, so long as the direction of its axis runs parallel with that of the main current collecting coil.

In producing undamped oscillations of a high frequency (50,000 per second and more) in the oscillation circuits 9 and 11, electromagnets S and S^1 must be inserted if the high frequency oscillations are not to penetrate the collector coil, between the oscillation producers and the collector coil. In all other cases they are connected shortly before the earthing (as in Figs. 27 and 28).

In Figure 27 a second method of construction of the connecting conductor of the balloon aerials is illustrated in the form of a coil. The main difference consists in that in addition to the connecting conductor I another annular conductor II is inserted parallel to the former on the high voltage masts in the air (or embedded as a cable in the earth) but both in the form of a coil. The connecting wire of the balloon aerials is indicated as a primary conductor and also as a current producing network; the other is the consumption network and is not in unipolar connection with the current producing network.

In Figure 27 the current producing network I is shown with three balloon collectors 1, 2, 3 and aerial conductors 4, 5, 6; it is short circuited through condenser 19 and inductance 9. The oscillation forming circuit consists in this diagram of spark gap *f*, inductance 10, and condenser 11; the earth wire E, is connected to earth over electromagnet S^1. F is the safety spark gap which is also connected to earth through a second electromagnet S at E. On connecting up the condenser circuit 11 this is charged over the spark gap *f* whereby an oscillatory discharge is formed. This discharging current acts through inductance 10 on the inductively coupled secondary 9, whereby in the producing network a modification of the potential of the condenser 19 is produced. The consequence of this is that oscillations arise in the coil shaped producer network. These oscillations induce a current in the secondary circuit II, which has a smaller number of windings and a less resistance, the voltage of which, according to the proportion of the number of windings and of the ohmic resistance, is considerably lower whilst the current strength is greater.

In order to convert the current thus obtained into current of an undamped character, and to tune its wave lengths, a sufficiently large regulatable capacity 20 is inserted between the ends 12 and 13 of the secondary conductor II. Here also current may be taken without an earth conductor, but it is advisable to insert a safety spark gap E^1 and to connect this with the earth over an electromagnet S^2.

The producer network may be connected with the working network II over an inductionless condenser 21 or over an induction condenser 22, 23. In this case the secondary conductor is unipolarly connected with the energy conductor.

In Figure 28 the connecting conductor between the separate accumulator balloons is carried out according to the autotransformer principle. The collecting coil connects four aerial balloons 1, 2, 3, 4, the windings of which are not made side by side but one above the other. In Figure 28 the collector coil I is shown with a thin line, the metallically connected prolongation coils II with a thick line. Between the ends I^1 and II^1 of the energy network I a regulating capacity 19 is inserted. The wire I^1 is connected with the output wire and with the spark gap F.

As transformer of the atmospheric electricity an arrangement is employed which consists in using rotary pairs of condensers in which the one stator surface B is connected with the main current, whilst the other A is connected with the earth pole. Between these pairs of short circuited condensers are caused to rotate from which the converted current can be taken by means of two collector rings and brushes, in the form of an alternating current, the frequency of which is dependent on the number of balloons and the revolutions of the rotor. As the alternating current formed in the rotor can act, in this improved method of connection described in this invention, through coils 10 on the inductance 9, an increase or diminution of the feed current in I can be obtained according to the direction of the current by back induction. Current oscillations of uniform rhythm thereby result in the coil shaped windings of the producer net-work.

As the ends of this conductor are short cir-

cuited through the regulatable condenser 19 these rhythms produce short circuited undamped oscillations in the energy conductor, the periodicity and wave lengths of which oscillations can be adjusted according to desire by altering the capacity 19 to a given wave length and therewith also to a given frequency. These currents may also be employed in this form directly as working current through the conductors II^1 and III. By inserting the condenser 20 a connection between these conductors may also be made, whereby harmonic oscillations of desired wave length are formed. By this means quite new effects as regards current distribution are obtained. The withdrawal of current can even take place without direct wire connection if, at a suitable point in the interior of the producing network (quite immaterially whether this has a diameter of 1 or 100 km.) a coil tuned to these wave lengths and of the desired capacity is firmly or movably mounted in the aerial conductor in such a way that its axial direction is in parallel with that of the collector coil. In this case a current is induced in the producing network, the size of which is dependent on the total capacity and resistance and also on the periodicity employed. A possibility is thereby afforded in future, of taking energy from the producer network by wireless means. As thereby in addition to atmospheric electricity also magnetic earth currents and the energy from the higher atmosphere (at least partially) may be simultaneously obtained, this last system for collecting the atmospheric energy is of particular importance for the future.

Of course everywhere instead of spark gaps suitable grid vacuum tubes may be employed as producers for undamped oscillations. The separate coils of the producer net-work with large diameters may be connected with one another through separate conductors all in parallel or all in series or in groups in series. By regulating the number of oscillations and also the extent of the voltage more or less large collector coils of this kind may be employed. The coils may also be divided spirally over the entire section. The coils may be carried out in annular form or also in triangular, quadrangular, hexagonal or octagonal form.

Of course wires may be carried from a suitable place to the centre or also laterally which serve the current waves as guides. This is necessary when the currents have to be conducted over mountains and valleys and so forth. In all these cases the current must be converted into a current of suitable periodicity.

As already hereinbefore mentioned separate collecting balloons may be directly metallically interconnected at equidistant stations distributed over the entire country or may be connected by interpolation of suitable condenser batteries by means of high voltage conductors. The static electricity is converted through a spark gap into dynamic energy of a high number of oscillations, and could then in such form, with a suitable arrangement of the connections, observing various measures of precaution, be employed as source of energy after separate or special regulation.

According to this invention in order to increase the collecting effect of the balloon in the aerial collector conductor or in the earth wire, radiating collectors are employed. These consist either of incandescent metal or oxide electrodes in the form of vacuum grid tubes, or electric arcs (mercury and the like electrodes) Nernst lamps, or finally flames of various kinds may be simply connected with the respective conductor.

It is well known that energy can be drawn off from a cathode consisting of an incandescent body opposite an anode charged with positive electricity (vacuum grid tube). Hitherto however, a cathode was always first directly placed opposite an anode, and secondly the system always consisted of a closed circuit.

Now if we dispense with the ordinary ideas in forming light or flame arcs in which a cathode must always stand directly opposite an anode, and if we place an incandescent cathode opposite an anode charged to a high potential or another body freely floating in the air, or regard the incandescent cathode only as a source of unipolar discharge (which represent group and point discharges in electro-static machines similar to unipolar discharges) it may be ascertained that incandescent cathodes and less perfectly all incandescent radiators, flames and the like admit of relatively large current densities and allow large quantities of electric energy to radiate into the open space in the form of electron streams as transmitters.

The object of this invention is as described below, if such incandescent oxide electrodes or other incandescent radiators or flames are not freely suspended in space but connected metallically with the earth so that they can be charged with negative terrestrial electricity, these radiators possess the property of absorbing the free positive electrical charges contained in the air space surrounding them (that is to say of collecting them and conducting them to earth). They can therefore, serve as collectors and have, in comparison to the action of the spikes, or points, a very large radius of action R; the effective capacity of these collector is much greater than the geometrical capacity (R_0-) calculated in an electro-static sense.

Now as our earth is surrounded as is well

known, with an electro-static field and the difference of potential

$$\frac{\delta V}{\delta h}$$

of the earth field according to the latest investigations, is in summer about 60 to 100 volts and in winter 300 to 500 volts per metre of difference in height (δh), a simple calculation gives the result that when such a radiation collector or flame collector is arranged for example on the ground, and a second one is mounted vertically over it at a distance of 2,000 metres and both are connected by a conducting cable, there is a difference of potential in summer of about 2,000,000 volts and in winter even of 6,000,000 volts and more.

According to Stefan Boltzmann's law of radiation, the quantity of energy which an incandescent surface (temperature T) of 1 sq. cm. radiates in a unit of time into the open air (temperature T_o) is expressed by the following formula:

$$S=\sigma\ (T^4-T^4{}_o)\ \text{watt/sq. cm.}$$

and the universal radiation constant σ is according to the latest researches of Ferry (Annales de Chimie et de physique 17 page 267 (1909)) equal to 6.30×10^{-12} watt/sq. cm.

Now if an incandescent surface of 1 sq. cm. shows, as compared with the surrounding space a periodic fall of potential δV it radiates (independent of the current direction, that is to say of the sign) in accordance with the above formula, for example at a temperature of 3725° C. an energy of 1.6 kw. per sq. cm. per second. As for the radiation the same value can be calculated for the collection of energy, but reversed. Now as carbon electrodes at the temperature of the electric arc support on the current basis a current density up to from 60 to 65 amperes per sq. cm. no difficulties will result in this direction in employing radiating collectors as accumulators.

If the earth be regarded as a cosmically insulated condenser in the sense of geometrical electro-statics *x* there results from the geometric (compare Ewald Rasch, "das elektrische Bogenlicht" (The electric arc light) page 169) capacity of the earth according to Chwolson:

For negative charging 1.3×10^6 Coulomb

For negative potential $V=10\times10^8$ volts.

From this there results however, $EJT\cong24.7\times10^{24}$ watt/Sec. Now if it is desired to make a theoretic short circuit through an earthed flame collector this would represent an electric total work of about 79,500 10^{10} kilowatt years. As the earth must be regarded as a rotating mechanism which is thermo-dynamically, electromagnetically, and also kinematically coupled with the sun and stars system by cosmic radiations and gravitation a diminution of the electric energy of the earth field is not to be feared. The energies which the incandescent collectors would withdraw from the earth field can only cause by the withdrawal of motor work a lowering of the earth temperature (temperature $T_E=300$) and reduce this to that of the world space ($T=O$) by using the entire energy. This is however not the case as the earth does not represent a cosmically entirely insulated system. On the contrary there is conveyed ~~to the~~ same according to the recent value corrected by Ferry for the solar constants through the radiation from the sun an energy of $18{,}500\times10^{10}$ kw. Accordingly any lowering of the earth temperature (T_E) without a simultaneous lowering of the sun's temperature (T_S) would contradict Stefan Boltzmann's law of radiation.

$$S=\sigma\,(T_S{}^4-T_E{}^4).$$

From this it must be concluded that if the earth temperature (T_E) sinks, the total radiation S absorbed by the earth increases, and further also that the secular speed of cooling of the earth is directly dependent on that of the sun and the other radiators cosmically coupled with the sun and is connected most closely with these.

The incandescent radiation collectors may, according to this invention, be employed for collecting atmospheric electricity if they (1) are charged with the negative earth electricity (that is to say when they are directly connected by means of a metallic conductor with the earth) and (2) if large capacities (metal surfaces) charged with electricity are mounted opposite them as positive poles in the air. This is regarded as the main feature of the present invention as without these inventive ideas it would not be possible to collect with an incandescent collector, sufficiently large quantities of the electrical charges contained in the atmosphere as technology requires; the radius of action of the flame collectors would also be too small, especially if it be considered that the very small surface density (energy density) (σ about$=2\times7\ .\ 10^9$ St. E. per sq. cm.) does not allow of large quantities of charge being absorbed from the atmosphere.

x) Calculated according to Poisson's calculation;

$\Delta V=-4\pi\delta$; as here the alteration of the potential or potential gradients only takes place in the direction of the normal, this calculation assumes the simple form

$$\delta=\frac{1}{4\pi}\times\frac{\delta^2V}{\delta n^2}$$

It has indeed already been proposed to employ flame collectors for collecting atmospheric electricity and it is known that

their collecting effect is substantially greater opposite the points. It is however, not known that the quantities of current which could hitherto be obtained are too small for technical purposes. According to my experiments the reason for this is to be found in the too small capacities of the collector conductor poles. If such flame or radiating collectors have no or only small positive surfaces, their radius of action for large technical purposes is too small. If the incandescent collectors be constantly kept in movement in the air they may collect more according to the speed of the movement, but this is again not capable of being carried out in practice.

By this invention the collector effect is considerably increased by a body charged with a positive potential and of the best possible capacity being also held floating (without direct earth connection) opposite such an incandescent collector which is held floating in the air at a desired height. If for example, a collecting balloon of sheet metal or of metalized balloon fabric be caused to mount to 300 up to 3,000 metres in the air and as positive pole it is brought opposite such a radiating collector connected by a conductor to earth, quite different results are obtained.

The metallic balloon shell (with a large surface) is charged to a high potential by the atmospheric electricity. This potential is greater the higher the collecting balloon is above the incandescent collector. The positive electricity acts concentratedly on the anode floating in the air as it is attracted through the radiation shock ionization, proceeding from the incandescent cathode. The consequence of this is that the radius of action of the incandescent cathode collector is considerably increased and thereby also the collecting effect of the collecting balloon surface. Further the large capacity of the anode floating in the air plays therefore an important part because it allows of the taking of large charges, and thereby a more uniform current is obtained even when there is a large consumption: this cannot be the case with small surfaces.

In the present case the metallic collecting balloon is a positive anode floating in the air and the end of the earth conductor of this balloon serves as positive pole surface opposite the surface of the radiating incandescent cathode, which in turn is charged with negative earth electricity being conductingly connected to earth.

The process may be carried out by two such contacts (negative incandescent cathode and anode end of a capacity floating in the air) a condenser and an inductive resistance being switched on in parallel, whereby simultaneously undamped oscillations may be formed.

In very large installations it is advisable to connect two such radiating collectors in series. Thus an arc light incandescent cathode may be placed below on the open ground and an incandescent cathode which is heated by special electro-magnetic currents be located high in the air. Of course for this the special vacuum Liebig tubes with or without grids may also be employed. An ordinary arc lamp with oxide electrodes may be introduced on the ground and the positive pole is not directly connected with the collecting balloon, but through the upper incandescent cathode or over a condenser. The method of connecting the incandescent cathode floating in the air may be seen in Figs. 29–33.

B is the air balloon, K a Cardan ring (connection with the hawser) C the balloon, L a good conducting cable, P a positive pole, N negative incandescent cathode, and E earth conductor.

Fig. 29 represents the simplest form of construction. If electric oscillations are produced below on the ground by means of a carbon arc lamp or in other suitable way a considerably greater electric resistance is opposed to that in the direct way by inserting an electrical inductive resistance 9. Consequently between P and N a voltage is formed, and as, over N and P only an inductionless ohmic resistance is present, a spark will spring over so long as the separate induction co-efficients and the like are correctly calculated. The consequence of this is that the oxide electrode (carbon or the like) is rendered incandescent and then shows as incandescent cathode an increased collecting effect. The positive poles must be substantially larger than the negative in order that they may not also become incandescent. As they are further connected with the large balloon area which has a large capacity and is charged at high voltage, an incandescent body which is held floating in the air and a positive pole which can collect large capacities is thereby obtained in the simplest way. The incandescent cathode is first caused to become incandescent by means of separate energy produced on the earth, and then maintained by the energy collected from the atmosphere.

Fig. 30 only shows the difference that instead of a round balloon a cigar shaped one (of metal or metalized fabric) may be employed and also a condenser 5 is inserted between the incandescent cathode and the earth conductor so that a short circuited oscillation circuit over P. N 5 and 9 is obtained. This has the advantage that quite small quantities of electricity cause the cathode to become incandescent and much larger cathode bodies may be rendered incandescent.

In this form of construction both the in-

candescent cathode and also the positive electrode may be enclosed in a vacuum chamber as may be seen in Fig. 32. A cable L is carried well insulated through the cover of a vessel and ends in a condenser disc 5. The cover is arched in order to keep off the rain. The vessel is entirely or partially made of magnetic metal and well insulated inside and outside. Opposite the disc 5 another disc 6 and on this again a metallic positive pole of the vacuum tube *g* with the incandescent cathode (oxide electrode) N is arranged. The negative electrode is on the one hand connected with the earth conductor E, and on the other hand with the inductive resistance 9 which is also connected with the cable L with the positive pole and wound round the vessel in coils. The action is exactly the same as that in Fig. 29 only instead of an open incandescent cathode one enclosed in vacuo is employed. As in such collectors only small bodies can be brought to incandescence in large installations a plurality of such vacuum tubes must be inserted in proximity to one another. According to the previous constructions Figs. 31 and 33 are quite self evident without further explanations.

Figs. 34–37 represent further diagrams of connections over radiating and flame collectors, and in fact, how they are to be arranged on the ground.

Fig. 34 shows an arc light collector with oxide electrodes for direct current and its connection; Fig. 35 a similar one for alternating current, Fig. 36 an incandescent collector with a Nernst lamp and Fig. 37 a similar one with a gas flame.

The positive pole 1 of the radiating collectors is always directly connected to the aerial collecting conductor A. In Fig. 34 this is further connected over the condenser battery 5 with a second positive electrode 3. The direct current dynamo *b* produces current which flows over between the electrodes 3 and 2 as an arc light. On the formation of an arc the negative incandescent electrode 2 absorbs electricity from the positive poles standing opposite it and highly charged with atmospheric electricity and conveys the same to the working circuit. The spark gap 7, inductive resistance 9 and induction coil 10 are like the ones previously described. The protective electromagnet S guards the installation against earth circuiting, the safety spark gap 8 from excess voltage or overcharging.

In Fig. 35 the connection is so far altered that the alternating current dynamo feeds the exciting coil 11 of the induction condenser. 12 is its negative and 13 its positive pole; if the coil 3 on the magnet core of the dynamo is correctly calculated and the periodicity of the alternating current is sufficiently high an arc light can be formed between the two poles 1 and 2. As the cathode 2 is connected with the negatively charged earth, and therefore always acts as a negative pole, a form of rectification of the alternating current produced by the dynamo 3 is obtained, the second half of the period is always suppressed. The working circuit may be carried out in the same way as in Fig. 34; the working spark gap 7 may however be dispensed with, and instead thereof between the points *n* and *m* a condenser 5 and an induction resistance 9 may be inserted from which the current is taken inductively.

Fig. 36 represents a form of construction similar to Fig. 34 only that here instead of an arc lamp a Nernst incandescent body is employed. The Nernst lamp is fed through the battery 3. The working section is connected with the negative pole, the safety spark gap with the + poles. The working spark gap 7 may also be dispensed with and the current for it taken at 12 over the oscillation circuit 5, 11 (shown in dotted lines).

Flame collectors (Fig. 37) may also be employed according to this invention. The wire network 1 is connected with the aerial collector conductor A and the burner with the earth. At the upper end of the latter, long points are provided which project into the flame. The positive electrode is connected with the negative over a condenser 5 and the induction coil 9 with the earth.

The novelty in this invention is firstly, the use of incandescent cathodes opposite positive poles which are connected with large metallic capacities as automatic collecting surfaces, (2) the connection of the incandescent cathodes with the earth whereby, in addition to the electricity conveyed to them from the battery or machine which causes the incandescing, also the negative charge of the earth potential is conveyed, and (3) the connection of the positive and negative poles of the radiating collectors over a condenser circuit alone or with the introduction of a suitable inductive resistance, whereby simultaneously an oscillatory oscillation circuit may be obtained. The collecting effect is by these methods quite considerably increased.

I declare that what I claim is:—

1. An electrical energy generating system, comprising a conducting surface for static charges, means to support same at a distance above the earth, a conductor leading to the earth level, a spark gap associated with said conductor to convert electrostatic charges into electromagnetic high frequency oscillations means to supply said electromagnetic energy to a net work, and a spark gap of greatly increased relative resistance in parallel therewith.

2. An electrical energy generating system

comprising a conductor, means to support same above the earth level, an inductance therein, a spark gap associated with said conductor, a second spark gap of much higher relative resistance in parallel therewith and an energy receiving circuit coupled with the spark gap of lesser resistance.

3. An electrical energy generating system comprising a collecting surface, means to support same above the earth level, a conductor connecting said collecting surface with the earth level, a choke in said conductor, an electromagnetic resistance converting electrostatic energy to electromagnetic energy, a safety higher resistance in parallel therewith and a net work coupled with the conversion resistance of lesser value.

4. An electrical energy generating system comprising electric conductors spaced above the earth to form electromagnetic oscillating circuits, conductors connecting to earth level, electrostatic to electromagnetic energy conversion means therein, a safety high electrostatic resistance in parallel therewith and means to alter the electromagnetic characteristic of the circuits.

5. An electrical energy generating system comprising in combination a static collecting surface arranged above the earth, conductors connecting to earth level, a pair of spark gaps in parallel of different electrostatic resistance, a utilization net work shunted across the spark gap of lesser resistance and an electromagnetic choke in said conductors.

6. An electrical energy generating system comprising an open circuit energy collecting aerial, a pair of sparking gaps in parallel of widely different resistance, connected thereto and a closed electric oscillation circuit in shunt across the gap of lesser resistance.

7. An electrical energy generating system comprising an open circuit energy collecting aerial, a pair of sparking gaps in parallel of widely different resistance connected thereto, a closed electric oscillation circuit in shunt across the gap of lesser resistance, a plurality of electrostatic collecting surfaces, means to connect said collecting surfaces in parallel in groups and means to connect said groups symmetrically with said aerial.

In witness whereof, I have hereunto signed my name this 30 day of Dec., 1920, in the presence of two subscribing witnesses.

HERMANN PLAUSON.

Witnesses:
H. F. Armstrong,
W. H. Beeston.

WILLIAM H. WARD.

Improvement in Collecting Electricity for Telegraphing, &c.

No. 126,356. Patented April 30, 1872.


Fig; 1.
Fig; 2.
Fig; 3.
Fig; 4.
Fig; 5.
Fig; 6.
Fig; 7.
M
L
O
K
I
H
G
B
A
a
g
i
p'
e
f
c
d
b'
E
F
N
n
o
k
k'
l
m
h
J
C
D
p
q

WITNESSES. INVENTOR.

Frank R. Rathbun

H. S. Rathbun

W. H. Ward

AM. PHOTO-LITHOGRAPHIC CO. N. Y. (OSBORNE'S PROCESS.)

126,356

UNITED STATES PATENT OFFICE.

WILLIAM HENRY WARD, OF AUBURN, NEW YORK.

IMPROVEMENT IN COLLECTING ELECTRICITY FOR TELEGRAPHING, &c.

Specification forming part of Letters Patent No. 126,356, dated April 30, 1872.

I, WILLIAM HENRY WARD, of Auburn, in the county of Cayuga and State of New York, have invented an Electrical Tower for Accumulating Natural Electricity for Telegraphic Purposes, of which the following is a specification:

My invention consists of a tower for the purpose of receiving and imparting natural electricity, so as to be in constant contact with that upper stratum of electricity which surrounds the earth, by tapping which a never-failing supply is formed when brought into contact with the earth, as will be more fully explained hereinafter.

In the accompanying drawing, Figure 1 represents a side elevation of my improved electrical tower. Fig. 2 is a vertical central section of the upper part of the same. Figs. 3, 4, 5, 6, and 7 are detached views of several parts of the same.

The tower is constructed in three separate sections, a lower, a middle, and an upper one, and is placed on elevated mountain tops or peaks. The lower one, A, is a mere shell, having a door, *a*, and is constructed of any material suitable for the purpose. It is insulated from the middle portion B by means of a glass diaphragm, *c*, held between similar diaphragms of rubber, *d*, and of gutta-percha, *e*, by means of flanges *a′* and *b′*, formed on the upper end of the lower portion and the lower end of the middle portion of the tower respectively. These flanges are secured to each other by insulated bolts *f*. The middle portion B is provided with suitable openings or windows, G, having shutters or slats *g* pivoted in them, so that, by means of raising or lowering rods *h*, suitably connected to said shutters, the openings G may be shut or opened. A projecting roof, H, is formed on or secured to the middle portion B just over the openings G, and which serves the double purpose of protecting the said openings from the effects of the weather, such as rain or snow, and also for receiving the aerial electricity, which may be drawn from it by wires *i*, for land-line purposes. Above this roof H the middle portion of the tower is again insulated by diaphragms of glass, rubber, and gutta-percha from the upper portion I of the tower in the same manner as it is insulated from its lower portion. A circular plate, *j*, secured on the inside of this upper portion, bears a short tube, J, which is surrounded by the tube K of the ventilator L, from which latter the vane M extends; or the tube J may be held by rods extending from the side of the tower centrally. This ventilator is supported by a rod or shaft, *k*, firmly attached to the tube K, and having its lower bearing in a step, *l*, on a brace, *m*, crossing the middle portion B of the tower just above the openings G. This rod or shaft *k* is formed in two parts, insulated from each other, as shown at *k′*. On the lower portion of this shaft *k* is keyed or otherwise secured a sleeve, *n*, from which a horizontal serpentine cam-plate, *o*, shown in detail in Figs. 4 and 5, extends, over the rim of which the forked ends *p* of rods *h* seize, and which is so arranged relatively to the vane M and the shutters or slats *g* that the revolution of the vane by the wind will open the windward and close the leeward shutters or slats *g* and openings G by means of the rods *h*. Guide-plates or their equivalents N, provided with suitable openings, through which the rods *h* pass, keep the upper forked ends *h* of the latter in constant contact with the cam-plate *o*, which raises or lowers the rods, and consequently opens or closes the openings G as it revolves. A circular roof, O, extends from the tube K of the ventilator so as to cover and protect the open upper end of the tower. The upper portion I of the tower is provided with an insulating-tube, *p′*, through which a copper wire, *q*, enters the portion I of the tower, and is coiled around the tube J just under the tube K, which wire may connect that upper portion of the tower with any land line of wires. The upper portion I of the tower, as well as the tubes J K, may be constructed of zinc, while the vane may be made of zinc, copper, or any equivalent material, which, with the zinc and the moisture of the atmosphere, would form an electrical current. As the vane revolves it opens the openings to windward and closes those to leeward, thus helping to drive an aerial current of electricity into the insulated middle portion of the tower, which current passes upwardly through the upper portion of the tower and out through the ventilator or the top, which is swung around by the wind or aerial electrical current, thus forming a draught in addition to the closing of the shutters or openings to leeward, by means of which draught the electrical current is forced upwardly and out at the vane. The top portion of the tower is of course completely insulated from all below it, including the revolving central ventilator-shaft. As the middle portion of the tower allows the electrical current of atmosphere, wind, &c., to pass within, up, and out at the top it forms a continuous current, whereby the tower is receiving continually fresh and new supplies of electricity, which can be drawn from the projecting roof H by the wires *i* for the use of land lines of telegraphs or for other purposes, such as light, heat, &c. By the use of aerial electricity I entirely dispense with artificial batteries, forming my circuit merely by connecting the aerial current with the earth current. For instance, to bring Buenos Ayres, in South America, into direct connection with New York, the following plan would be pursued: One electrical tower is erected on Pike's Peak or any other suitable high mountain in North America, and another similar tower on some suitable peak of the Andes in South America. The former would, by means of land-lines, be connected directly with Denver, which place is again connected with all the prominent cities of the States. In a similar manner the southern tower is connected by land-lines with the prominent cities via Quito. New York telegraphs to the tower on Pike's Peak, and the operator having connected the land-line with the aerial current, the signals are transmitted through the aerial current to the tower in the Andes in South America; and from there—the land-lines being suitably connected with the aerial current—to Quito and Buenos Ayres. In this manner a message would be sent entirely by natural electricity in place of artificial. In the same manner a message may be sent across the ocean by having a high tower on each continent, each of which towers would have to be, of course, through land-lines connected with the earth to enable the ground current with the aerial current to form a circuit. Different towers may be erected on the different continents, and if they are all what is technically called hooked on—that is to say, connected to the earth—a signal given at one tower will be repeated at all the towers, they being connected with each other by the aerial current. If the earth-connection is severed, or the insulation with the tower destroyed, there is no power; but by insulating the tower and concentrating its force to a point, bringing the same corresponding effect from the earth current in connection, an exceedingly powerful electrical force is created.

Having described my invention, I claim—

1. A tower constructed so as to collect, hold, distribute, and utilize aerial currents of natural electricity for telegraphic and other purposes, essentially as described.

2. A tower for collecting aerial currents of natural electricity, constructed of three sections, insulated from each other and the earth, or their equivalents, substantially in the manner described.

3. In an electrical tower, the combination of the shutters or slats *g* with the ventilator-vane in such a manner that the vane, through suitable mechanism, always opens the shutters to windward and closes them to leeward, substantially as described.

4. In an electrical tower, the collecting, distributing, and protecting roof H, substantially as and for the purpose described.

5. The combination of the tube J and ventilator L with its vane M and the coiled wire or small cable *q*, substantially as and for the purpose set forth.

6. The combination of the insulated shaft *k* and rods *h* having forked upper ends *k'* with the shutters or blinds *g*, serpentine cam-plate *o*, and ventilator L, substantially as and for the purpose described.

The above specification of my improvement, being a tower for accumulating natural electricity for telegraphic purposes, signed this 29th day of June, A. D. 1871.

W. H. WARD.

Witnesses:
A. L. PALMER,
J. H. STARIN.

(12) INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(19) World Intellectual Property Organization
International Bureau

(43) International Publication Date
28 August 2008 (28.08.2008)

PCT

(10) International Publication Number
WO 2008/103129 A1

(51) International Patent Classification:
H02M 11/00 (2006.01) *H02N 11/00* (2006.01)

(21) International Application Number:
PCT/TR2007/000050

(22) International Filing Date: 8 June 2007 (08.06.2007)

(25) Filing Language: English

(26) Publication Language: English

(30) Priority Data:
u 2007/00996 20 February 2007 (20.02.2007) TR

(71) Applicant *(for all designated States except US)*: **TURK, Metin** [TR/TR]; Ayten Sokak 30/4 Mebusevleri, Tandogan, 06510 Ankara (TR).

(71) Applicant and
(72) Inventor: **KAPANADZE, Tariel** [GE/GE]; Tzkaltubo Sokak, No:9, Tbilisi (GE).

(74) Agent: **YALCINER, Ugur G. (YALCINER DANISMANLIK VE DIS TICARET LTD. STI.)**; Tunus Caddesi No:85/8, Kavaklidere, 06680 Ankara (TR).

(81) Designated States *(unless otherwise indicated, for every kind of national protection available)*: AE, AG, AL, AM, AT, AU, AZ, BA, BB, BG, BH, BR, BW, BY, BZ, CA, CH, CN, CO, CR, CU, CZ, DE, DK, DM, DO, DZ, EC, EE, EG, ES, FI, GB, GD, GE, GH, GM, GT, HN, HR, HU, ID, IL, IN, IS, JP, KE, KG, KM, KN, KP, KR, KZ, LA, LC, LK, LR, LS, LT, LU, LY, MA, MD, ME, MG, MK, MN, MW, MX, MY, MZ, NA, NG, NI, NO, NZ, OM, PG, PH, PL, PT, RO, RS, RU, SC, SD, SE, SG, SK, SL, SM, SV, SY, TJ, TM, TN, TR, TT, TZ, UA, UG, US, UZ, VC, VN, ZA, ZM, ZW.

(84) Designated States *(unless otherwise indicated, for every kind of regional protection available)*: ARIPO (BW, GH, GM, KE, LS, MW, MZ, NA, SD, SL, SZ, TZ, UG, ZM, ZW), Eurasian (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European (AT, BE, BG, CH, CY, CZ, DE, DK, EE, ES, FI, FR, GB, GR, HU, IE, IS, IT, LT, LU, LV, MC, MT, NL, PL, PT, RO, SE, SI, SK, TR), OAPI (BF, BJ, CF, CG, CI, CM, GA, GN, GQ, GW, ML, MR, NE, SN, TD, TG).

Published:
— *with international search report*

(54) Title: INDEPENDENT ENERGY DEVICE



Figure - 1

(57) Abstract: The independent energy device improved with this invention, starts operation with the initial electric energy received from the initial energy supply (15) and afterwards generates energy consistently and is characterized to include power switch (1), capacitor (2), points (3), high frequency generator (4), first filter (5), first bobbin (6), first frequency adjuster (7), second filter (8), frequency stabilizer (adjuster) (9), second bobbin (10), second frequency adjuster (11), exit (phase) (positive) (12), positive self feeding cable (12a), exit (neutral) (13), negative self feeding cable (13a), neutral (grounding) (14), initial power supply (15).

WO 2008/103129 A1

INDEPENDENT ENERGY DEVICE

The present invention is a device both self sufficient (self feeding) and producing ready to use electric energy, starts to operate with the initial electrical energy received from accumulator or similar source of energy, transferring the magnetic field generated in first bobbin to second bobbin through a frequency stabilizer, after rhythmically stabilizing the magnetic field occurred between the bobbins; converts the independent energy -received by the second bobbin from the air- to electric energy.

Today electric energy can be generated by using various kinds of technologies. In order to summarize some of them; electric energy can be generated through dams, from the motion of waves, by nuclear power plants, by using solar energy, fuel oil, hydroelectric power plants and similar areas through using various technologies. There are different advantages and disadvantages among these various techniques used for generating electric energy. The general purpose of all these techniques is to generate energy cheaper and faster by providing high efficiency.

The present invention is improved through using different technologies of today, by less costly way and without harming the nature, and using a very different technique from the above mentioned (present techniques used today).

The present invention receives energy externally only at first starting phase. This mentioned energy can be easily generated from a small accumulator or chargeable battery or similar sources. 1 -2 seconds after the device is started, the power switch at the energy input of the device cuts the external electric (from accumulator or similar source of energy) off by generating electric energy. A very few part of this electric energy generated is used by the device to feed itself and the most part is discharged ready to be used. As long as the device is not shut down or no problem occurred inside, the device generates energy consistently. By recent technology, there is no device similar to the present invention producing energy consistently by feeding itself.

In order to maintain the device to generate electric energy consistently, two circuits are designed inside the device.

First circuit; consists of time relay switch, capacitor, points, high frequency generator, first filter, first bobbin, first frequency adjuster (this circuit is displayed with bold line on the figure)

Second circuit; consists of second filter, frequency stabilizer, second bobbin, second frequency adjuster.

First circuit is designed for generating electricity by transferring the electro magnetic field occurred at the first bobbin with the electric energy received from the independent initial power supply, to second bobbin. And as the second circuit; Due to the high magnetic field received from the first bobbin, there occurs a magnetic field difference between the bobbins. The magnetic field difference occurred between the second bobbin and first bobbin stabilized by the help of frequency stabilizer within this circuit line. As stabilizing the magnetic field difference by the help of frequency stabilizer, this circuit line also converts the energy which is moving independently in the air at the second bobbin designed within this line to electric energy. This electric energy formed by the second bobbin adjusts the necessary frequency (220 V - 50 Hz or 110 V - 60 Hz) for use, by the help of second frequency adjuster designed at the bobbin output. This generated electric energy is transferred to the intended usage area via exit points. Through the circuit cables connected to the exit points, the device feeds itself with the generated electric energy. This mentioned process eventuates 1 -2 seconds after the device is got started. After this process, the time relay power switch designed at the input of the device breaks the initial energy supply. After this stage, the device generates the energy independently.

The present invention is designed as single phase and as the phase number is desired to be increased, the bobbin number shall also be increased for each phase. Depending on the number of bobbins, the capacities of other parts used in the device are increased symmetrically.

It is possible to obtain energy in desired amounts of KW from the device. It is necessary to increase the capacity of the parts depending on the value of the electric energy.

The figures related to the invention are given enclosed; from the related figures:

Figure 1- Schematic view of the present invention

The parts related to the invention are given numbers and the explanations responding these numbers are as follows:

1- Power switch

2 - Capacitor

3- Points (as distributor of an engine)

4- High frequency generator
5- First filter
6- First bobbin
7- First frequency adjuster
8- Second filter
9- Frequency stabilizer (adjuster)
10- Second bobbin
11- Second frequency adjuster
12- Exit (phase) (positive)
12a- Positive transformation cable
13- Exit (neutral)
13a- Negative transformation cable
14- Neutral (grounding)
15- Initial power supply
A- First circuit cable
B- Second circuit cable

The operation of the present device is explained as below, giving reference to the parts' numbers through the figure enclosed.

Energy and frequency circuit on the first circuit (A)

Opening the power switch, the user gives the electric energy received from the initial energy supply (15) to the first circuit cable (A). Being loaded with the electric energy received from the energy supply (15) the capacitor (2) serves as a pump, and provides the points (3) to give electric to the high frequency generator (4). High frequency generator (4) transfers the high amount of frequency it generated to the first filter (5). First filter (5) stabilizes the frequency received from the high frequency generator (4) and regularly transfers to the first bobbin (6). Creating a magnetic field around itself with the high frequency regularly received from the first filter (5); first bobbin (6) transfers it to the second bobbin (10). Subsequently, following the first circuit cable (A), the high frequency passing from the first bobbin (6) passes to the first frequency adjuster (7). The first frequency adjuster (7) stabilizes the received high frequency in accordance with the need and arranges without causing any harm to the parts at its exit.

Energy and frequency circuit on the second circuit (B)

The high frequency rised from the first bobbin (6) enters to the second filter through the second circuit (B). Second filter (8) transfers the frequency received from the first bobbin (6) to the frequency stabilizer (9). The electromagnetic fields occurred at the bobbins (6, 10) are different and the magnetic field at the first bobbin (6) is higher than the second bobbin (10). At this stage the frequency stabilizer (9) stabilizes the different electromagnetic fields occurred at the first and the second bobbins (6, 10). This stabilized high frequency exits from the second bobbin (10) and is adjusted for the required (necessary for the use) frequency degree by the help of the second frequency adjuster (11). The user uses the electric energy generated in the device by the help of exit (phase) (positive) (12) and exit (neutral) cable (13).

The positive transformation cable (12a) at the exit of the device and the negative transformation cable (13a) are connected to the power switch. 1-2 seconds after the device starts to generate electric, the electric energy generated is transmitted to the power switch (1) via positive transformation cable (12a) and negative transformation cable (13a). The time relay at the power switch (1) breaks the energy received from the initial power supply (15). After this stage, the device continues to generate electric energy feeding itself with the self generated energy and independently without depending to any energy from outside. The device continues to generate unlimited energy as long as it is not closed via the power switch (1) or no problem occurred within the system.

CLAIMS

1- An independent energy device, starting to operate with the initial electric energy received from the independent initial power supply (15), transferring the electro magnetic field occurred at the first bobbin (6) to second bobbin (10), stabilizing the magnetic field occurred between the bobbins (6, 10) with the help of frequency stabilizer (9), afterwards converting the independent energy received from the air by the second bobbin (10) to electric energy, both self feeding and generating ready to use electric energy; composed of following parts; power switch (1), capacitor (2), points (3), high frequency generator (4), first filter(5), first bobbin (6), first frequency adjuster (7), second filter (8), frequency stabilizer (adjuster) (9), second bobbin (10), second frequency adjuster (11), Exit (phase) (positive) (12), positive self feeding cable (12a), exit (neutral) (13), negative self feeding cable (13a), neutral (grounding) (14), initial power supply (15).

2- An independent energy device of Claim 1 wherein characterized to include capacitor (2) to transfer the electric received from the initial power supply (15) to points (3).

3- An independent energy device of Claim 1 wherein characterized to include points (3) to transfer the frequency that the high frequency generator (4) needs.

4- An independent energy device of Claim 1 wherein characterized to include the high frequency generator (4) to transfer the high frequency occurred within itself to the first filter (5).

5- An independent energy device of Claim 1 wherein characterized to include the first filter (5) to order the frequency received from the high frequency generator (4) and transfer to the first bobbin (6).

6- An independent energy device of Claim 1 wherein characterized to include the first bobbin (5); providing a high electro magnetic field around itself to transfer the high and regular frequency received from the first filter (5) to the second bobbin (10) and the electric energy received from the initial power supply (15) both to the first circuit cable (A) and to the second circuit cable (B).

7- An independent energy device of Claim 1 wherein characterized to include first frequency adjuster (7) to stabilize the normal frequency received from the initial power supply (15) with the high frequency received from the first bobbin (6).

8- An independent energy device of Claim 1 wherein characterized to include the second filter (8) to order the high frequency received from the first bobbin (6) and transfer to the frequency stabilizer (adjuster) (9).

9- An independent energy device of Claim 1 wherein characterized to include frequency stabilizer (adjuster) (9) to stabilize the electro magnetic field differences occurred between the first bobbin (6) and second bobbin (10).

10- An independent energy device of Claim 1 wherein characterized to include the second bobbin (10) to generate electric energy combining the electro magnetic field received from the first bobbin (6) and the independent energy received from the air, after the frequency stabilizer (adjuster) (9) orders the electro magnetic field between the bobbins (6, 10).

11- An independent energy device of Claim 1 wherein characterized to include the second frequency adjuster (11) to stabilize the high frequency received from the second bobbin (10) in accordance with the need to be used.

12- An independent energy device of Claim 1 wherein characterized to include Exit (phase) (positive) (12) and Exit (neutral) (13) designed in order to enable the device to use the electric energy generated.

13- An independent energy device of Claim 1 wherein characterized to include positive transformation cable (12a) and negative transformation cable (13a) designed in order to enable the device to feed itself with the electric energy generated.

14- An independent energy device of Claim 1 wherein characterized to include the initial power supply (15) to provide the device operates at the first time.


⊖
13
12a
⊕
12
11
10
14
6
5
9
B
8
4
13a
7
3
2
A
1
15
⊕
⊖

Figure - 1

US008102082B2

(12) United States Patent
Ogram

(10) **Patent No.: US 8,102,082 B2**
(45) **Date of Patent: *Jan. 24, 2012**

---

(54) **ATMOSPHERIC STATIC ELECTRICITY COLLECTOR**

(75) Inventor: **Mark Ellery Ogram**, Tucson, AZ (US)

(73) Assignee: **Sefe, Inc.**, Scottsdale, AZ (US)

(*) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 295 days.

This patent is subject to a terminal disclaimer.

(21) Appl. No.: **12/321,306**

(22) Filed: **Jan. 16, 2009**

(65) **Prior Publication Data**

US 2010/0008011 A1 Jan. 14, 2010

Related U.S. Application Data

(63) Continuation-in-part of application No. 12/218,297, filed on Jul. 14, 2008, now Pat. No. 7,855,476.

(51) **Int. Cl.**
H02G 11/00 (2006.01)

(52) **U.S. Cl.** **307/145**; 307/149; 307/151; 361/218; 361/230

(58) **Field of Classification Search** 361/212, 361/215, 216–218, 230, 231; 307/145, 149, 307/151; 174/2; 244/30, 31
See application file for complete search history.

(56) **References Cited**

U.S. PATENT DOCUMENTS

674,427	A	*	5/1901	Palencsar	307/149
1,014,719	A	*	1/1912	Pennock	307/149
1,540,998	A	*	6/1925	Plauson	310/309
4,486,669	A	*	12/1984	Pugh	290/44

* cited by examiner

Primary Examiner — Fritz M Fleming
(74) *Attorney, Agent, or Firm* — Mintz Levin Cohn Ferris Glovsky and Popeo, P.C.

(57) **ABSTRACT**

An antenna for the collection of atmospheric static electricity in which an electrically conductive hub is suspended from a balloon or blimp via a tether. The hub is either solid or uses a spoke/arm arrangement. A number of rods extend from the hub enhance the collection of atmospheric static electricity. The collected atmospheric electricity is conducted from the rods to an electrical connection where the electricity is conducted to earth via a conductive line.

16 Claims, 7 Drawing Sheets




18
10A
10B
10
11
12
19
13
14
15
8
5
16
6
17
7
23
23
21
23
23
23
12
22
5

FIG. 1

FIG. 2


30
START
31A
LIGHTNING ?
Y
32A
WITHDRAW BALLOON
N
31B
CURRENT IN RANGE ?
Y
N
31C
TOO HIGH ?
N
Y
32B
WITHDRAW BALLOON SET DISTANCE
32C
EXTEND BALLOON SET DISTANCE

FIG. 3


40
DC-IN
41
42
DC-AC
43
GRID

FIG. 4A


40
DC-IN
41
43
STEP DOWN TRANSFORMER
44
45
GROUND

FIG. 4B


40
DC-IN
46
47
DC-OUT

FIG. 4C


51A
50A
50B
51B

FIG. 5



FIG. 6A



FIG. 6B


71
70
72
73
74

FIG. 7



FIG. 8A


85A
83
84
85B

FIG. 8B

FIG. 9A


90
91
94
92
93
93
93
93
93
96
95

FIG. 9B


93
93
94
92
93
93

FIG. 10


102D
101
102C
102A
103
103
104
103
102B

FIG. 11


111
112A
112B
112C
113


125
125
123A
123B
122A
122B
121
122C
123C
125
125
124

FIG. 12

ATMOSPHERIC STATIC ELECTRICITY COLLECTOR

This is a continuation in part of U.S. patent application Ser. No. 12/218,297, filed on Jul. 14, 2008, now U.S. Pat. No. 7,855,476 and entitled, "Atmospheric Electrical Generator".

BACKGROUND OF THE INVENTION

This invention relates to the production of electrical energy and more particularly to the collection of static electricity from the atmosphere.

Everyone is familiar with Benjamin Franklin's kite experiment of 1752. Using a kite whose string had become wet, negative charges from the passing clouds flowed into the string, down to the suspended key, and then into a Leyden jar via a thin metal wire. Franklin was protected by a dry silk string; but, when Franklin's knuckle came too close to the key, he received a strong shock. Fortunately, Benjamin Franklin was not killed, others who tried this same experiment were not so lucky.

Since then, the formation of lightning has remained something of a mystery. Lightning bolts are triggered when a negatively charged cloud base induces a positive charge from the ground, thereby forming a "pathway" for the discharge of the collected electrical energy.

Lightning travels up to 60,000 miles per hour with a flash that is brighter than ten million 100-watt lightbulbs. This wattage is as much power as is produced by all of the electricity plants in the United States and with a voltage of up to 300 million volts.

It is this very fact, the power within lightning is immense, that has prevented any successful collection of the electrical energy from lightning. The electricity in lightning is far too extreme for current technology to harness.

While lightning has attracted a energy starved industrial world, no one has developed any technique to harness this naturally occurring electrical source.

It is clear there is a continuing need for an electrical source other than carbon-based fuels and that the naturally occurring electricity in the atmosphere is being ignored.

SUMMARY OF THE INVENTION

The invention is a mechanism which taps into the naturally occurring static electricity in the atmosphere. Whereas heretofore, the attempt to garner electricity from the atmosphere has focused exclusively on capturing lightning, the present invention syphons off the static electricity which is generated from any agitated air and voids lightning.

Lightning is only the final discharge of the static electricity, whether that lightning is intra-cloud lightning, cloud-to-ground lightning, or inter-cloud lightning. Other types of final discharges are known as heat lightning, summer lightning, sheet lightning, ribbon lightning, silent lightning, ball lightning, bead lightning, elves, jets, and sprites. Well before these discharges are observed, as the atmosphere becomes agitated by wind or thermal, static electricity is being generated.

The present invention recognizes that this static electricity is being formed and creates a mechanism to capture it.

The mechanism of this invention utilizes an aircraft such as a lighter than air balloon. While the preferred embodiment uses a foil balloon, a variety of other aircraft are obvious to those of ordinary skill in the art, including, but not limited to: gliders, rubber balloons (such as weather balloons), biaxially-oriented polyethylene terephthalate polyester film balloons, and latex balloons.

Within this discussion, the balloon is referenced, but, the invention is not intended to be limited solely to balloons.

The balloon is sent aloft and is tethered by a conductive line. In this context, the conductive line may be any obvious to those of ordinary skill in the art. For the preferred embodiment, the conductive line is a generically referred to as a "poly-rope" and is commercially available through a variety of sources. A suitable conductive line is described in U.S. Pat. No. 5,203,542, entitled "Apparatus for Improved Electric Fence Wire Construction for use with Intensive Grazing" issued Apr. 20, 1993, to Coley, et al. and incorporated hereinto by reference.

The conductive line is played out of a winch to control the altitude of the balloon. The motor controlling the winch is able to reverse direction to both extend and withdraw the conductive line which is wrapped around a spool on the winch. The winch/spool combination are part of a base unit.

In some embodiments of the invention, the spool is constructed of rubber so as to insulate the conductive line from the winch assembly. In this embodiment, only the conductive line is charged by the atmospheric static electricity while the winch remains neutral.

In yet another embodiment, the winch/spool are part of a base unit which is itself isolated from the ground by an insulator. In this embodiment, the entire base unit is charged by the atmospheric static electricity.

A conductor, such as an insulated wire, is electrically connected to the conductive line. In one embodiment, where the conductive line is electrically isolated from the spool and winch motor, the conductor is connected to the conductive line. In the embodiment where the conductive line is electrically connected to the base unit, then the conductor is connected anywhere on a metalic base unit.

The other end of the conductor is connected to a load. The load in this case can be any of a variety of electrical loads well known to those of ordinary skill in art, including, but not limited to a motor, a battery system, or the electrical grid for the system.

In the preferred embodiment, a sensor array is used to monitor the activities both at the base unit (such as electrical flow within the conductor) and in the surrounding locale.

A sensor monitoring the electrical flow (i.e. voltage and/or current) within the conductor is used to monitor the electrical activity within the conductor.

In the preferred embodiment, a lightning sensor monitors for lightning activity within the locale. As noted earlier, the electrical characteristic of lightning is so extreme that ideally this discharge is avoided as it might damage the mechanism of this invention.

The sensor array is utilized by a controller, such as microprocessor, programmed to operate the mechanism as outlined herein.

The controller operates the winch motor to extend or withdraw the conductive line and by extension the altitude of the balloon. The controller is programmed to operate the winch by monitoring the electrical characteristics of the conductor and adjusting the balloon's altitude to maintain these characteristics within the conductor within a preset range.

This preset range is established either in the base programming of the controller or is established by an operator of the system.

As example, by controlling the amount of current being withdrawn from the atmosphere, the mechanism operates within a safe range and also provides a relatively stable current flow from which a variety of activities can take place (such as DC-AC conversion).

The controller also utilizes the lightning sensor to protect the mechanism from a lightning strike. Should lightning be detected within a pre-determined range (as established by the software or defined by an operator), then the balloon is pulled down to minimize the risk of damage from a lightning strike.

An aspect of the present invention is the use of an antenna which are used to collect the atmospheric static electricity. The antenna is shaped as a hub which is suspended from the blimp/balloon. The hub is ideally spoked shaped although an alternative embodiment uses a solid hub.

A number of rods extend from the hub so as collect atmospheric static electricity These rods are ideally rounded at the ends to enhance the attraction of the atmospheric static electricity.

The collected atmospheric electricity is conducted from the rods to an electrical connection on the hub where the electricity is conducted to a power plant on earth such as described above.

The invention, together with various embodiments thereof will be more fully explained by the following description of the accompanying drawings.

DRAWINGS IN BRIEF

FIG. **1** diagrams the preferred embodiment of the invention.

FIG. **2** illustrates the collection of the negative charged particles in the atmosphere.

FIG. **3** is a flow-chart of the operation of the controller for the preferred embodiment of the invention.

FIGS. **4**A, **4**B, and **4**C are electrical schematics for handling the static charge from the atmosphere.

FIG. **5** illustrates a conductive line used in the preferred embodiment of the invention.

FIGS. **6**A and **6**B illustrate an alternative conductive line creating an ionized pathway for the flow of the static charges from the atmosphere.

FIG. **7** illustrates the controller of an alternative embodiment and the associated safety devices.

FIGS. **8**A and **8**B illustrate two embodiments of enhanced electrical collection leads.

FIGS. **9**A and **9**B are side views and top views of an embodiment of the antenna used to collected atmospheric electricity.

FIG. **10** is a top view of an alternative embodiment of the antenna of this invention.

FIG. **11** is a side view of yet another alternative embodiment of the antenna used to collect atmospheric electricity.

FIG. **12** is the preferred embodiment of the antenna of this invention.

DRAWINGS IN DETAIL

FIG. **1** diagrams the preferred embodiment of the invention.

Balloon **10** is an aircraft which, in this illustration, is a lighter than air balloon. Wings **10**A, extending from the body of balloon **10**, provide additional lift in air flow **18**. Tail **10**B helps to stabilize balloon **10**.

Balloon **10** is tethered to the ground via conductive line **12**. As noted earlier, a variety of configurations and materials are available to serve as conductive line **12**. In this illustration, a poly-wire is used. Poly-wire is commercially available through a variety of vendors, including, but not limited to: Jeffers Livestock and Sareba Systems, Inc. of Ellendale, Minn.

In this embodiment, located proximate to balloon **10**, is an electrical collection enhancement lead **11** which assists in the collection of the static electrical charge in the atmosphere. Electrical collection enhancement lead **11** is configured to attract the static charge and conduct the charge into the conductive line **12**.

The electricity flows down the conductive line into spool **13**, where the conductive line **12** is collected and either withdrawn or dispensed through operation of winch motor **14**.

Winch motor **14** and spool **13** are mounted onto base unit **16** which is electrically isolated from ground **7** using insulator **17**. Note, in this embodiment of the invention, when electricity is being collected from the atmosphere, the entire base unit **16** becomes charged. In another embodiment of the invention, spool **13** is constructed of rubber, thereby preventing base unit **16** from becoming charged, thereby restricting the charging from the atmosphere to only conductive line **12**.

In this embodiment, conductor **6** is connected to base unit **16** (since the entire base unit **16** is charged and the base unit is metalic) to communicate the electrical current to load **5**. Conductor **6** is ideally an insulated wire.

The electrical current through conductor **6** is measured using sensor **8**.

In the alternative embodiment discussed above, where only the conductive line **12** is charged, then conductor **6** is connected to conductive line **12**.

Controller **15**, located in this embodiment on base unit **16**, operates winch motor **14** in response to signals from sensor **8** (measuring the current being discharged to load **5**) to maintain the current flow within a pre-defined range. As the current flow diminishes, then the conductive line **12** extended from spool **13** to increase the altitude of balloon **10** to that more static charge from the atmosphere is gathered; as the current flow falls exceeds a preset level, conductive line **12** is withdrawn onto spool **13** to decrease the static charge being collected from the atmosphere.

The range of current flow through conductor **6** is ideally set by the program, although some embodiments of the invention permit an operator to establish this range of operation.

In an alternative embodiment, the sensor monitoring conductor **6** monitors the voltage therein.

In the preferred embodiment of the invention, controller **15** is also equipped with a lightning sensor **19**. In this embodiment, when lightning is sensed within a preset range, then substantially all of conductive line **12** is wound onto spool **13** to pull balloon **10** near the ground and protect the entire mechanism from being damaged from a lightning discharge.

In the preferred embodiment, the “safe” distance form lightning is set in the programming of controller **15** and is ideally two miles; other embodiments permit the operator to “safe” distance.

There are a variety of lightning sensors well known to those of ordinary skill in the art, including, but not limited to those described in: U.S. Pat. No. 7,016,785, entitled “Lightning Detection” issued to Makela, et al. on Mac. 21, 2006; U.S. Pat. No. 6,829,911, entitled “Lightning Detection and Prediction Alarm Device” issued to Jones, et al. on Dec. 7, 2004; U.S. Pat. No. 7,200,418, entitled “Detection of Lightning” issued to Karikuranta, et al. on Apr. 3, 2007; and U.S. Pat. No. 6,961,662, entitled “Systems and Methods for Spectral Corrected Lightning Detection” issued to Murphy on Nov. 1, 2005; all of which are incorporated hereinto by reference.

In another embodiment of the invention, controller **15** is not located on base unit **16**, rather it is remote and communicates its control signals to winch motor **14** using radio waves.

FIG. **2** illustrates the collection of the negative charged particles in the atmosphere.

Static charges **23** are generated in the atmosphere by agitated air. These static charges are often collected at the bottom of clouds, but exist in other environments as well.

Balloon **21** is extended into this strata of static charges **23** which are then attracted to conductive line **12** to flow to base unit **22** and then onto load **5**.

By increasing or decreasing the altitude of balloon **21** (defined by the length of the extended conductive line **12**), conductive line **12** is selectively exposed to varying densities and levels of the static charge strata, and by extension, the current flow or voltage is increased or decreased.

FIG. **3** is a flowchart of the operation of the controller for the preferred embodiment of the invention.

Once the program starts **30**, the lightning sensor is checked to determine if lightning has occurred within the unsafe range **31**A, if it has, then the balloon is lowered **32**A, and the program continues monitoring the status of lightning until no lightning is detected.

When the lightning status is acceptable, then the current within the conductor is checked to see if the current is within the prescribed range **31**B. If the current is acceptable (within range) the program returns to check the lightning status **31**A; otherwise a determination is made to see if the current is above the prescribed range **31**C.

If the current is above the prescribed range, then the altitude of the balloon is withdrawn a set amount **32**B (ideally twenty-five feet) and the program loops back to see if the current is within range **31**B.

If the current is below the prescribed range, then the altitude of the balloon is extended a set amount **32**C (ideally twenty-five feet) and the program loops back to see if the current is within range **31**B.

In this manner of feed-back and minor adjustments in the altitude of the balloon, the current is maintained within a prescribed range which can be handled by the downstream electrical system.

As noted earlier, some embodiments of the invention monitor the voltage instead of the current.

FIGS. **4**A, **4**B, and **4**C are electrical schematics for handling the static charge from the atmosphere.

By maintaining the voltage being collected in a prescribed range, an electrical conversion system is easily designed. While FIGS. **4**A, **4**B, and **4**C illustrate some electrical configurations, those of ordinary skill in the art readily recognize a variety of other configurations which will serve the same function.

Referencing FIG. **4**A, Direct Current In (DC IN) **40** is buffered by a gang of capacitors **41** before being communicated to a DC/AC converter **42**. The DC/AC converter converts the direct current into a an alternating current suitable for placement over an existing electrical grid **43** such as normally found from a power-plant.

Those of ordinary skill in the art readily recognize a variety of DC/AC converters, including, but not limited to: U.S. Pat. No. 7,394,671, entitled "Controller IC, DC-AC Conversion Apparatus, and parallel running system of DC-AC Conversion Apparatuses" issued to Fukumoto, et al. on Jul. 1, 2008; and, U.S. Pat. No. 7,330,366, entitled "DC-AC Converter" issued to Lee, et al. on Feb. 12, 2008; all of which are incorporated hereinto by reference.

FIG. **4**B illustrates an electrical arrangement suitable for use in charging a battery. DC IN **40** is buffered by capacitor bank **41** before entering into a step down transformer **43**. Step down transformer **43** reduces the voltage so that the voltage can safely be introduced into battery **44** which is connected to ground **45** at the battery's other pole.

Those of ordinary skill in the art readily recognize a variety of batteries which will work in this capacity, including, but not limited to those described in: U.S. Pat. No. 7,378,181, entitled "Electric Storage Battery Construction and Manufacture" issued to Skinlo on May 27, 2008; U.S. Pat. No. 7,388,350, entitled "Battery with Electronic Compartment" issued to Wright on Jun. 17, 2008; U.S. Pat. No. 7,397,220, entitled "Connection Member and Battery Pack" issued to Uchida, et al. on Jul. 8, 2008; and, U.S. Pat. No. 7,375,492, entitled "Inductively Charged Battery Pack" issued to Calhoon, et al. on May 20, 2008; all of which are incorporated hereinto by reference.

In FIG. **4**C, DC IN **40** is fed into an adjustable rheostat **46** which is controlled by the controller so that the DC OUT **47** falls within a specified range.

FIG. **5** illustrates a conductive line used in the preferred embodiment of the invention.

This type of conductive line is commonly called poly-wire and consists of multiple interwoven strands of plastic **50**A and **50**B woven into a cord or rope arrangement having intertwined therein exposed metal wires **51**A and **51**B. While this illustration shows two plastic strands and two metal wires, any number of possible combinations is possible.

The exposed metal wires **51**A and **51**B attract the atmospheric static charge and transmit the charge down to the base unit (not shown).

FIGS. **6**A and **6**B illustrate an alternative conductive line creating an ionized pathway for the flow of the static charges from the atmosphere.

This conductive line utilizes a tube **60** having an outer layer **62** of PET Film (Biaxially-oriented polyethylene terephtalate polyester film) which provides exceptionally high tensile strength and is chemically and dimensionally stable. The tube has an ideal diameter of between two and three inches.

An interior metal coating **61** provides an initial conduit for the flow of static charge. The static charge through the metal forces the tube to expand due to the repulsion experienced by like charges. Further, the flow of electricity causes the interior of the tube **60** to become ionized to provide an additional pathway for the atmospheric static charges to the base unit (not shown).

Because outer layer **62** provides a gas barrier, the resulting ionization is not dissipated by air currents, thereby providing a highly stable pathway.

FIG. **7** illustrates the controller of an alternative embodiment and the associated safety devices.

In this embodiment, controller box **70**, resting on insulating pad **72**, is in communication with the sensors as described above. Using the input from these sensors, when there is flow of electricity through the base unit, warning flashing light **71** is illuminated. To electrically neutralize the mechanism, switch **73** is activated to pass any existing current into the ground **74**.

FIGS. **8**A and **8**B illustrate two embodiments of enhanced electrical collection leads.

Referencing FIG. **8**A, enhanced electrical collection lead **82** is a wire mesh which is in electrical communication with conductive line **81** and balloon **80**. Because of the significant amount of metal exposed by enhanced electrical collection lead **82**, more static electricity from the atmosphere is drawn to the collection lead **82**, and then down conductive line **81** to the base unit (not shown).

Conductive lead **82** is positioned proximate to balloon **80**.

In FIG. **8**B, poly-wire **83** has enhanced electrical collection leads **84** wrapped therearound. Collection leads **84** have pointed ends **85**A and **85**B which have a propensity to attract more electricity than rounded ends do.

FIGS. **9**A and **9**B are side views and top views of an embodiment of the antenna used to collected atmospheric electricity.

Blimp **90** supports antenna **92** via tether **91** which is attached to antenna **92** by connection **94**. In this embodiment, antenna **92** is made of electrically conductive material and is ideally light in weight to lessen the payload requirements on blimp **90**.

Encircling antenna **92** and extending therefrom are rods **93** which are rounded at their distal ends so as to enhance attraction of the atmospheric static electricity. The static electricity is communicated to connection **96** and then to electrical line **95** which communicates the electricity to the ground based station (not shown) as described above.

FIG. **10** is a top view of an alternative embodiment of the antenna of this invention.

In this embodiment of the antenna a central hub **101** has the blimp connection **104** (capable of receiving the tether to the blimp) secured thereto. In this illustration, four arms **102**A, **102**B, **102**C, and **102**D extend from hub **101**. Hub **101**, and arms **102**A, **102**B, **102**C, and **102**D are all electrically conductive in this embodiment.

At the end of each arm are rods **103** which are used to enhance the collection of the atmospheric static electricity.

Although this embodiment illustrates four arms, the invention is not intended to be limited to four arms, rather, any number of arms may be used and the number of rods extending from the distal ends of the arms also varies.

FIG. **11** is a side view of yet another alternative embodiment of the antenna used to collect atmospheric electricity.

In this embodiment, several tethers **112**A, **112**B, and **112**C, are used to secure the antenna **113** to the blimp **111**. This arrangement of several tethers provides heightened stability of the antenna by reducing the affects wind will have on the antenna.

FIG. **12** is the preferred embodiment of the antenna of this invention.

In this embodiment of the antenna, arms **122**A, **122**B, and **122**C extend from a central hum and are electrically connected to rim **124**. Tether connectors **123**A, **123**B, and **123**C, are used to secure the antenna to the blimp or balloon.

Rods **125** extend from rim **124** to increase the collection of the static charges in the atmosphere.

It is clear from the foregoing that the present invention captures an entirely new source of electrical energy.

What is claimed is:

1. A system for collection of atmospheric static electricity comprising:

a balloon;

a hub that is electrically conductive and connected to the balloon by a tether, the hub having:

at least three electrically conductive arms, a first end of each of said conductive arms electrically connected to said hub; and

a plurality of rods, a first end of each of said rods being electrically connected to a second end of at least one of said at least three arms;

a base unit having a spool of conductive line on a winch motor, one end of said conductive line secured to said hub, a portion of said conductive line and said hub collecting electricity in the atmosphere, said winch motor selectively extending or withdrawing said conductive line from said spool;

a conductor having a first end electrically connected to said conductive line and a second end electrically connected to a load being powered by collected electricity from said conductive line;

an electrical flow sensor monitoring electrical flow through said conductor and generating an electrical flow indicia indicative of said electrical flow in said conductor; and

a controller receiving said electrical flow indicia and selectively operating said winch motor such that said electrical flow indicia remains within a selected operating range.

2. The system according to claim **1**, wherein each of said plurality of rods has a rounded second end.

3. The system according to claim **2**, wherein at least two rods are attached to the second end of each of said at least three arms.

4. The system according to claim **1**, further comprising an electrically conductive rim connected to a second end of said electrically conductive arms.

5. The system according to claim **4**, wherein at least a portion of said plurality of electrically conductive arms are connected substantially at right angles to an exterior of said electrically conductive rim.

6. A system for collection of atmospheric static electricity comprising:

a radial arrangement of at least three electrically conductive arms;

a plurality of rods, each of said rods being electrically connected to at least one of said at least three arms; and

a balloon tether connected between a balloon and said radial arrangement of at least three electrically conductive arms;

a base unit having a spool of conductive line on a winch motor, one end of said conductive line secured to said radial arrangement of at least three electrically conductive arms, a portion of said conductive line and said radial arrangement of at least three electrically conductive arms collecting electricity in the atmosphere, said winch motor selectively extending or withdrawing said conductive line from said spool;

a conductor having a first end electrically connected to said conductive line and a second end electrically connected to a load being powered by collected electricity from said conductive line;

an electrical flow sensor monitoring electrical flow through said conductor and generating an electrical flow indicia indicative of said electrical flow in said conductor; and

a controller receiving said electrical flow indicia and selectively operating said winch motor such that said electrical flow indicia remains within a selected operating range.

7. The system according to claim **6**, wherein each of said plurality of rods has a rounded end distal from said electrically conductive arm.

8. The system according to claim **7**, further including a balloon tether connection secured to the first end of said at least three arms.

9. The system according to claim **8**, further including an electrical connection secured to the first end of said at least three arms.

10. The system according to claim **9**, wherein said at least two rods attached to said at least three arms is five rods.

11. The system according to claim **9**, further including an electrically conductive rim connected to a second end of said electrically conductive arms.

12. The system according to claim **11**, wherein said plurality of arms are electrically connected to said electrically conductive rim.

13. The system according to claim **12**, wherein at least a portion of said plurality of rods are connected to an exterior of said electrically conductive rim substantially at right angles thereto.

14. A system for the collection of atmospheric static electricity comprising:

a generally circular electrically conductive body;

a balloon tether connected to a first side of said generally circular electrically conductive body and to a balloon; and

an electrical connection connected to a second side of said generally circular electrically conductive body;

a base unit having a spool of conductive line on a winch motor, one end of said conductive line secured to said electrical connection, a portion of said conductive line and said generally circular electrically conductive body collecting electricity in the atmosphere, said winch motor selectively extending or withdrawing said conductive line from said spool;

a conductor having a first end electrically connected to said conductive line and a second end electrically connected to a load being powered by collected electricity from said conductive line;

an electrical flow sensor monitoring electrical flow through said conductor and generating an electrical flow indicia indicative of said electrical flow in said conductor; and

a controller receiving said electrical flow indicia and selectively operating said winch motor such that said electrical flow indicia remains within a selected operating range.

15. The system according to claim **14**, wherein said generally circular electrically conductive body comprises:

an electrically conductive hub;

at least three electrically conductive arms, each of said arms connected at a first end to said hub; and

an electrically conductive rim connected to the second end of each of said at least three arms.

16. The system according to claim **15**, further comprising a plurality of electrically conductive rods, a first end of each of said rods connected to said rim and extending therefrom substantially at rights angles thereto.

* * * * *



Shared by L. Cozma (Thanks !) --

The Guillot device generated about 2.5-3 Kilowatts with antenna height of ~ 20 meters. Power depends on the total collector surface and height of the vertical antenna. The apparatus in the photo produced ~300 watts with a collector 2 meters tall.

"Practical Utilization of Atmospheric Electricity"

by

Gillbert Darida

in *The Invention Encyclopedia,* pp. 204-207 (1930, Geo. Constantinescu, Ed.)

"The Earth has its own negative electricity, in the soil, and the atmosphere which surrounds the Earth is charged with positive electricity. The electric potential (the voltage) increases with the altitude, so we can say that the electric force is proportional to the atmospheric altitude (after Franklin, Quetelet, Lord Kelvin, Mascart, Joubert and other scientists).

The recent observations demonstrate that the air at 6000-7000 meters in altitude, is very highly charged with positive electricity, which could be explained by the friction between the external photosphere and the upper atmosphere of Earth, which rotates at a speed of more than 100,000 Kilometer per hour.

In that way, the Earth works like an electrostatic generator with electric charging by influence --- the upper atmosphere is positively charged by influence and the Earth crust obtains the negative polarity.

Between the two environments, the air and the soil, and inside the low atmosphere, in conditions of good weather, there are sbout 800 positive ions and also, 680 negative ion (and electrons) in just one square-centimeter of normal ionised air.

The Earth behaves like an huge electric armature negatively charged, which repels the electrons and attracts the positive ions. That positive ions' attraction determinates an electric current, also called "convective current". That's like an invisible continous bombardment, subject to daily and seasonal variations, which could be aproximated at **3 x 10 ^ -16 Amperes per square-centimeter,** and that is a total value of 1500 Amperes for the entire surface of the Earth.
The question is --- how does this current always maintains the same direction ? We can suppose that the natural radioactive emissions of the soil is responsable for this. We also know that radioactive emissions of the Earth works usually near the soil surface, and that explains the ionisation phenomenona inside caves.

The ionisation of the low atmosphere could also be the effect of the radioactive emissions of the Earth, especially when the X radiation works. Also, the Earth atmosphere is ionisated by the external radiation proceeding from the Sun and from the space environment, especially the action of ultraviolet radiation and the electron fascicles emitted by the Sun surface, at the temperature of 6000 deg. Celsius.

The capture of atmosphere electricity has been used in France, with aerial cables mounted on the Mont Blanc, and also in Germany --- with conductive cables carried by the captive baloons.

The atmosphere electricity collect system invented by eng. Jules Guillot is most ingenious and it relies on "the **electric siphon**" [*m.n. --- the discharging devices or spark-gap used today from the protection of aerial electric cables against the atmospheric electricity ; Jules Guillot has thought to recuperate and to use that electricity*].

His method consisted in the direct "pumping" of the atmosphere electricity using a collecting device which had two antennae and several collecting rods.

One antenna is **vertical** and it has a lot of **rods** scattered like an opened **fan**, with the tips against the **zenith**, for collecting the **negative** electricity which comes from the air ; the **horizontal** antenna is orientated against the **South** and its role is to collect the **positive** electricity.

The air electricity seems to have the double-polarity, as we can see at two electrised clouds when between them apears the electric discharge. The air could have different electric charging and the ionisation processus of atmosphere is very heterogenous. The inventor Guillot used **two separated and insulated armatures with the positive armature against the South** (more precisely, against the **Equator**...) and the **negative** armature against the **zenith**.

We can see in the scheme :

1,- the device P is the "**collector apparatus**" having **15-20 meters height** ; it also has a lot of **rods** which are scattered **fan**-like, all this on top of an **iron pillar** ; and also an **horizontal antenna** S oriented against the **South** ; the two antennae are disposed at **90 deg. angle** forming the two armatures where the electrical tension must apear. As the **height** of the pillar **increases**, the **voltage** increases more and more ;

2,- a system of **lightning-rods** (p1, p2, p3) for protection against discharges of atmospheric electricity during storms;

3,- the regulator system (**voltage regulator**, etc) R ;

4,- the electric **resistors** (Cn) for absorbing the parasite currents ;

5,- the "electric siphons" which have the role of making a magnetic field as a good environment for the transport of the ionized fluid, absorbing the electricity from the air ; the E1 and E2 are their regulator devices ;

6,- an **auxilliary continous current power supply** which send the current against an special **excitation coil**, used as starting device ; it works only when the system is starting.
This collector device works very good for lighting and heating. The device made by Guillot had **20 meters height** on the total surface of **3 square-meters**. Also, J.Guillot used and electrical transformer for the industrial utilization of this "collector" --- as power supply for industrial electric engines."

French Patent # 551,882

Apparatus for Capture of Electric Currents in the Atmosphere

16 April 1923

Considering the terrestrial globe like the inductor of a dynamo, where the extraterrestrial ether is the inductor of electric currents circulating in the atmosphere; the apparatus of the invention described here selects through the device described below two perfectly distinct currents and eliminates others.

The device includes:

1, The air sensor; 2, a series of lightning rods; 3, vacuum; 4, an array of resistances; 5, vacuum; 6, witnesses.

1. An aerial sensor mounted on a pole is composed of **magnetic steel** fixed and sealed by a porcelain **insulator**, and surrounded a base by a **bronze ring** which are screwed **32 points of soft iron**, all forming antenna a pole. level beside it and isolated from the first, forming the 2nd pole, is fixed a sharp point of magnetic steel fixed in the horizontal position and directed towards the south and **movable to an angle of 45** is sealed in a porcelain insulator. This point is also circled a **ring of copper** notches figure. 1.

2. A series of 6 lightning surge arrestors at corners between each pole and the earth and the various gauges.

3. A first **regulator** form of a device similar absolutely similar to the aerial amtenna, but the two poles are superposed and opposed to the vertical point, and a **copper disk connects to ground**. Opposite the horizontal point, a **ring of tin** to which are welded tubes alternatively **16 tubes** composed each composed of **copper-lead** and **iron-lead** . The ring connects to the **ground** as shown in figure. 2.

A second regulator form of **automatic breakers** balanced on 3 poles and two poles also equally balanced.

4. A panel of **resistances** composed of **wire mesh** in bunches from different sections of **glass tubes** containing **copper** dust, **coal** and flowers of **sulfur**.

Vacuum cleaners consists of a **wooden box** on each pole, containing a **porcelain vase** in which **layers** isolated with **mica** is made up of **mercury, tin, coal, copper** and **sulfur**, all contaied in a **copper tube**.

6. The witnesses are comprised of ordinary incandescent lamps.

Resume

By the point at the zenith and the point to the south we channel two currents forming the two poles. We also protect from lightning. It regularizes the flow by a regulator and similar devices by a controlling each devise of adequate strength of the current harmful nature of these devices do not have loads. The refined current is conducted by ordinary copper wires**.**

French Patent # 565,395

Combined Apparatus for Capture of Atmospheric Electric Currents with Immediate Implementation

25 January 1924

We know that earth with its constitution, its rotation and movement in space, provides the electricity in the atmosphere. The electrical currents escape into space or largely accumulate towards the equator, as a result of the greater periphery of the globe.

In the atmosphere, there are two clearly distinct poles, i.e., clouds that can be electrically positive or negative; everything in nature shows this, otherwise it would be difficult to explain the lightning that occurs between the clouds and which are none other than contrary cloud electrical charges discharged by too close proximity.

The invention relates to a set of devices capable of capturing the atmospheric electricity.

So far, all searches made for this purpose has been to capture the atmosphere, i.e., that brought together into one system to capture two poles and opposes effect has been to destroy or cancel each other leaving the amount as the difference of the strongest to weakest.

It is therefore easy to understand why, considering the two poles of air as about equal, it is almost impossible to measure some potential with the land, the highest on the lowest remaining which can be positive or negative, copper being the strongest of one or other of these polarities.

It is on this basis that all research until now have been made, and that is why we must consider that all the time, between the two poles captured in the atmosphere and not in any mixture of systems uptake, it is possible to obtain tension and intensity, a considerable and measurable power captured separately between the two poles and remaining isolated from one another until their utilization .

In accordance with this invention, this collection is made by attraction of primary electrical currents in teh atmosphere, either positively or negatively charged, by an antenna that has two points absolutely isolated from one another, where one points to the zenith to attract negative electricity, and the other turned south, toward the equator to draws in the masses grouped in this area.

This shows and proves the existence of atmospheric electrical currents, and that it is possible to capture them with specially designed equipment primarily acting as regulators, as the persistent difficulty encountered so far in realizing their capture lies with large variations of tension in which the current atmosphere is present in space, for each of the poles, and an overload could inevitably fatal.

The patent in its present form of presentation does not cover the regulators or devices that are anticipated in the system, because they can be designed in different ways and give the same result, but covers the application and grouping of equipment operating as automatic relays with variable influence to limit current tension to that chosen for utilization.

These devices have a role associated with an overflow reservoir outside carrying excess liquid; these regulators will divert the excess voltage flows to ground.

We can still absorb these regulators having filters because they have the sole purpose of diverting the post being used , currents that are not yet known but likely that we will call for simplicity, abnormal currents. [sic...]

The patent also covers systems for regulating currents, applied to each of the poles because it is recognized that the shape and tension of the currents of the two poles are not equivalent.

The method of capture is by special antenna has directed two points in the atmosphere, as will be stated after this, with Boot ecoulement prior to the current atmosphere is also of great importance.

Finally, the current atmospheric reception is adequate even with the installation of a post, which can be expected at any location without the need for special altitude, as has been attempted in previous efforts.

We refer to the attached drawings:.

Figure 1 represents in elevation and side view an antenna that only has two points, to overcome an elevation ;

Figure 2 is the end of one of the peaks, the horizontal:



Fig. 1

Fig. 2

Figure 3 shows schematically the table on which are mounted various devices or accessories that act as regulators of current tensions.

Fig. 3.


1
2
3
4
5
+
-
7
7
R²
R³
R³
R²
R
12
12
R⁴
R⁴
R¹
R¹
11
11
L
L

Figure 4 is a scheme of surge arrestors, and

Figure 5 a table of resistances.

Fig.4.



Fig.5.



The necessary arrangements to capture atmospheric current form is as follows:

1. The **antenna** in figure 1 is formed with two peaks: the 1 is **steel**, supported by a **bronze ring** 2, surrounded by a **spiral form** 3; this point is oriented for attracting the **zenith** layers of **negative electricity** and the other edge 4 contains **copper coils** 6, and is oriented **south** to the **equator** to draw in the masses grouped in this area. To use this antenna it suffices to be raised on a mast or **pole** to a height a little higher than that of surrounding houses.

2. On the table **lightning arrestors**, contained 4, forms of 7 **copper horns** used to absorb large atmospheric discharges by certain time, as it would be dangerous to allow movement in the devices regulators.

3. On a table of **two** symmetrical systems **regulators**, Figure 3, one for each pole, to obtain and allow a regularization of large excesses in the current tensions, by automatically absorbing surges before passing over the surfacea chosen for the desired use. These regulators are represented on the drawing by the references R, R1, R2, R3, R4.

4. In the **resistance** panel in communication with regulators, these resistances are formed as **spiral coils or screens** 8, **tubes 9 of glass filled with fine coal dust , aluminum powder, sulfur and fine copper dust**. Finally, **two** special 10 **processors** and constitutes **layers** of metal forming an **absorbant** for harmful or abnormal currents.

5. As a source of energy formed **auxiliary batteries** 11 and **Ruhmkorff coils** 12 to get into the antenna sufficient attraction by means of an adjustment of intensity, which once it begins, allows the constant flow of atmospheric current in the system.

In considering Figure 3, which represents a sort of an installation scheme of the device, the reception of atmospheric electrical current will, as set out above, producing a priming of these currents. This boot is made in launching the system which is double to answer each of the poles, the current batteries 11 through 12 and reels going to the antenna.

This boot will continue until the disposal of electrical current atmosphere is evident by the one or more table lamps L of resistance shown in Figure 5.

Once the lights illuminate it is advisable to charge the batteries to boot. Natural flow and constant currents will be captured by the regulators , Figure 3; they will regularize in tension and in amperage and then directed to use in table lamps.

It has been said above that regulators R, etc., are intended and designed to automatically eliminate earth surge currents capture and abnormal currents that cannot yet be level but that these regulators could be replaced by devices with the same function.

There is therefore no need to describe in detail and especially the claims. We only specify that these regulators must be proper protection for the purposes described above.



The classic spark-gap with magnetic blowing circuit

The spark-gap with magnetic blowing :
a,- the initial stage ; the impulse current send in soil through the shunt-resistences 3, because the coils 2 have an impedance too big for the impulse of 10/20 μs ;
the spark-gap 1 has two elements disc-shaped 1a and 1b, the inferior disc have one electrode and the upper disc the other electrode of the spark-gap circuit.
b,- the second stage ; the accompanying current discharge - after the impulse current ;
this accompanying current pass through the coils 2 which produce the magnetic field with the role to extend the electric arc into the slit between insulator discs 1a and 1b ; the thickness of this slit is smaller and smaller in accord with the extension of the electric arc, in this manner producing the magnifing of its electric resistance and finaly, the electric arc extinction.



1,- the spark-gap individual devices which work in the manner to extend the electric arc of the accompanying electric current ;
2,- the coils which produce the magnetic field for the magnetic blowing ;
3,- the electric shunt-resistances in parallel connection on the blowing coils, with the role of reducing the current inside this coils
4,- the disc with unlinear resistance ;
5,- electrical resistance for the homogenous distribution of the electric field in all the elements of the spark-gap.

In Jules Guillot scheme, that kind of device could be used for leading the current.

Spark-gap element with circuit for the magnetic blowing of the electric fascicle







a,- the spark-gap with variable resistance ;
b,- the tube spak-gap ;
t - the time

The tube spark-gap has the aerial spark gap with the electrodes 5 and 6 disposed at the insulator 8 extremities ; and one arc-over spark-gap device between the rod 4 and the electrode 1. At start, the first spark apear in the aerial spark-gap and then, the electric dicharge goes to the gas-producing tube 7, where it makes the arc-over. The local pressure in the gas allow the electric arc extinction, after managing the over electric tension into soil. The capacity C which is created between the external ring 3 and the rod 4 is bigger than the Capacity C_1 between 1 an 2 in that manner, when the overtension apears, the auxiliary spark-gap 1, 2 will start working and then, the main spark-gap 1, 4. In this circuit, the electrode 9 is connected at the aerial electric line and the electrode 1 at the Earth.

In the image above, it is an classic tube spark-gap used for the protection of aerial electric cables. The atmospheric electricity is discharged in soil and lost... The Guillot's inventions used that kind of devices for leading and absorbing of the atmospheric electricity.

DARIDA, Gillbert : "Practical Utilization of Atmospheric Electricity";
(in *The Invention Encyclopedia,* pp. 204-207 ; 1930, Geo. Constantinescu, Ed.) --



Utilizarea practică a electricității atmosferice

Pământul ca și celelalte astre, posedă o electricitate proprie negativă în interior, iar aerul care-l înconjoară este pozitiv. Potențialul sau tensiunea electrică a aerului se mărește pe măsură ce ne ridicăm în înălțime, astfel că putem spune că intensitatea electrică este proporțională cu înălțimea (după lucrările remarcabile ale lui Franklin, Quetelet, Lord Kelvin, Mascart, Joubert și a altor mari savanți fizicieni).

Observațiile făcute recent, au arătat că aerul regiunilor înalte dela 6000—7000 m este foarte încărcat cu electricitate pozitivă, a cărei explicație se datorește frecării fotosferei sau atmosferei terestre, prin învârtirea pământului în jurul soarelui cu mai mult de o sută de mii de km pe oră. Această frecare directă în fluidul eteric ambiant, face ca aerul să se încarce cu electricitate pozitivă prin influență, iar pământul să se încarce negativ.

Intre cele două medii, fluidic (aerul) și (pământul) materie, știința ne spune, că în partea de jos a atmosferei, pe timp frumos un centimetru cub de aer ionizat, conține circa 800 particule cu ioni pozitivi și 680 ioni negativi (electroni).

Pământul se comportă ca un enorm conductor încărcat negativ, respingând electroni și atrăgând ionii pozitivi. Această atracție a ionilor pozitivi determină un curent electric, zis și curent de convențiune. E un fel de bombardament invizibil supus variațiunilor zilei și a sezoanelor, putându-l evalua aproximativ la o densitate mijlocie remarcabilă, dela 3×10^{16} sau a 30 quatrilionime de amper pe cm cub, ceea ce dă pentru întreagă suprafață a pământului un curent formidabil, de 1500 de amperi.

Se pune întrebarea cum un astfel de curent poate să-și întreție mereu același sens? Aceasta este enigma pe care ne-o punem, studiind curenții naturali ai atmosferei noastre, presupunem că poate să fie o legătură a acțiunii emanațiunilor radioactive. Aceste emanaţiuni fiind din gaze radioactive grele, se găsesc de obiceiu în mare abundenţă aproape de pământ ceea ce ne explică marea ionizare observată în general în grote şi caverne.

Ionizarea atmosferică poate de asemenea fi produsă în parte, de acţiunea razelor X, foarte pătrunzătoare şi de diferite substanţe radioactive închise în subsolul pământului. De asemenea poate să mai fie, ţinând seama de acţiunea «Calei Lactee» şi de ionizarea luminei solare, foarte bogată în radiaţiuni ultraviolete



Fig. 108

precum şi a electronilor emişi direct din radierea căldurii solare de circa 6000 de grade.

Captarea electricităţii atmosferice a fost utilizată în Franţa prin cabluri aeriene montate pe Mont Blank, iar în Germania prin cabluri susţinute de baloane captive.

Sunt mai multe sisteme, vom da pe scurt pe cel mai ingenios procedeu, inventat de ing. Jules Guillot, bazat pe sifonul electric. Procedeul consistă de a pompa direct din atmosferă, electricitate

prin ajutorul unui aparat de captare, format din 2 antene aeriene și o serie de bobine după cum se vede în fig. 108. Una din antene este verticală în formă de evantaiu dirijată cu vârfurile către zenit, pentru a capta electricitatea negativă din atmosferă; cea care este orizontală, este dirijată către Sud, pentru a capta electricitate pozitivă.



Fig. 109

Electricitatea în aer pare să fie cu dublă polaritate, după cum se vede la 2 nori electrizați, cari deplasându-se în sens contrar, dau naștere unei scântei (fulger) când distanța respectivă poate să fie străbătută de puternica lor diferență de potențial. Straturile de aer de densități diferite, nu sunt toate antrenate de aceeași viteză prin rotația pământului, ele se electrizează deci prin frecarea decalajului lor respectiv.

Aceste sunt considerațiunile ce l-au făcut pe inventator să așeze în atmosferă doi poli complet distincți și perfect izolați, al cărui pol pozitiv *S* (fig. 109) poate fi dirijat în direcțiunea Sudului, și a celuilalt negativ *P*, în direcțiunea zenitului. Fig. 109 arată schema montajului și a conexiunilor compuse după cum urmează: 1. dintr'o antenă dublă aeriană, montată pe stâlpi de 15—20 m înălțime. Această parte care se mai numește și aparat de captat, este format din vârfurile *P*, dispuse în evantai în vârful unei tije de oțel dirijate către zenit, pentru a capta curenții negativi ai atmosferei și dintr'o altă antenă orizontală a cărei săgeată este îndreptată către sud *S*, adică către equator, pentru a recepta curenții pozitivi. Aceste două părți dispuse în unghiu de 90°, formează cei doi poli al curentului aerian, a cărei diferență de potențial este suficientă pentru a permite utilizarea electricității atmosferice.

French Patent # 551,882

Appareil Capteur de Courants Electriques dans L'Atmosphere

rexresearch.com

The Next Bigly Thing: Power from the Air

by Robert A. Nelson

---

1 | Man Cheats Credit Score
1 simple trick & my credit score jumped 217 pts. Banks hate this! thecreditsolutionprogram.com

2 | $4,400 in the first month
Looking for a job? Drive with Lyft instead & make $4,400 in the first month. Terms apply. lyft.com

1 | Man Cheats Credit Score
1 simple trick & my credit score jumped 217 pts. Banks hate this! thecreditsolutionprogram.com

2 | Tesla Generator - Build Your Own Generator
Eliminate Your Power Bill Easy. Do It Yourself. Great Discount Now! Just $49. tesla-energy.org/Generator

1 | Part-time Online Work - Up to $45 Per Survey
Make up to $45 per survey in 20 min surveyjunkie.com/Extra-Cash

2 | Tesla Generator - Build Your Own Generator
Eliminate Your Power Bill Easy. Do It Yourself. Great Discount Now! Just $49. tesla-energy.org/Generator

---

The Next Bigly Thing: Power from the Air

by Robert A. Nelson

The lightning bolts hurled at us by angry gods amply demonstrate the abundance of energy latent in the heavens. Lightning also introduced humans to fire.

Benjamin Franklin's legendary kite flight during a thunderstorm in 1752 marks the beginning of our Promethean attempts to draw power from atmospheric electrostatic (ES) energy. Considerable progress has been made since then, and the industrial scale production of electrical power from the sky has been an accomplished fact since the early 1900s. The promising technology fell dormant after World War One, however, and it has slept since then.

Atmospheric electricity offers several advantages over other energy sources; the technology is simple and robust, costs less than wind or solar power, and it is available anywhere anytime. Earth is an electrostatic generator -- the atmosphere is positively charged relative to the negatively polarized Earth. The system generates approximately 3 x 10 ^ -16 Amperes/sq. cm. (1500 Amperes for the entire Earth).

Andor Palenscar

Andor Palenscar's "Apparatus for Collecting Atmospheric Electricity" included a novel motor to utilize the ES energy, described in US patent US674427, granted in 1901:



No. 674,427. Patented May 21, 1901.

A. PALENCSÁR.

APPARATUS FOR COLLECTING ATMOSPHERIC ELECTRICITY.

(Application filed July 10, 1900.)

(No Model.) 3 Sheets—Sheet 1.

Fig:1.
Fig:3.
Fig:4.
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41

Walter Pennock

Walter Pennock developed an aerial energy collector, for which he was granted US patent US911260 in 1909 and US1014719 in 1912.



Fig.1.
Fig.2.
1
2
3
4
5
6
6'
7
8
9
10
11
12
13
14
15
16
17
WITNESSES
INVENTOR
Walter I. Pennock.
BY

Jules Guillot

The Atmospheric Electric Siphon invented by Jules Guillot in the 1920s generated about 2.5-3 kilowatts with antenna height of ~ 20 meters. The power depends on the total collector surface and height of the vertical antenna. A tabletop apparatus with only a 2 meter tall collector produced ~300 watts.

The great promise of Guillot's device was reported in *The Invention Encyclopedia* (1930, edited by the eminent engineer George Constantinescu):

> "The capture of atmosphere electricity has been used in France, with aerial cables mounted on the Mont Blanc, and also in Germany --- with conductive cables carried by the captive balloons.
>
> "The atmosphere electricity collect system invented by eng. Jules Guillot is most ingenious and it relies on "the electric siphon". His method consisted in the direct "pumping" of the atmosphere electricity using a collecting device which had two antennae and several collecting rods.
>
> "One antenna is vertical and it has a lot of rods scattered like an opened fan, with the tips against the zenith, for collecting the negative electricity which comes from the air; the horizontal antenna is orientated against the South and its role is to collect the positive electricity:
>
> "Guillot used two separated and insulated armatures with the positive armature against the South (more precisely, against the Equator...) and the negative armature against the zenith... Also, J. Guillot used an electrical transformer for the industrial utilization of this collector as power supply for industrial electric engines."




Fig.2.

Fig.1.


Fig.3.

The electric siphons produce a magnetic field and absorb the aerial electricity. A Ruhmkorff induction coil is used to jump-start the system. Guillot received three French Patents for his "Apparatus for Capture of Atmospheric Electric Currents with Immediate Implementation" (FR551882, FR565395, and FR551882)

Hermann Plauson

The Estonian Hermann Plauson was director of the Fischer-Tropsch Laboratories in Hamburg, Germany during the 1910s and 20s,. He thoroughly investigated atmospheric electricity and constructed practical apparatus to utilize it. His book "*Gewinnung und Verwertung der Atmosphärischen Elektrizität*" (1920) provides a detailed explanation of the technology.

Hugo Gernsbach presented the invnetion in *Science & Invention* magazine (March 1922, June 1928). He noted that the system was "actually in use small power plants, that generate electricity direct from the air, day and night, without interruption at practically no cost, once the plant is constructed."

> "Herr Plauson found in his experiments that a single balloon sent aloft to a height of 300 yards gave a constant current at 400 volts of 1.8 amperes, or in 24 hours over 17-1/4 kilowatts! By using two balloons in connection with a special condenser battery, the power obtained was 81-1/2 kilowatts in 24 hours. The actual current delivered was 6.8 amperes at 500 volts.
>
> "The best balloons... are made of thin aluminum leaf, filled with helium...The surface is dotted with electrolytically sharpened pins amalgamated with zinc, and a pinch of radium salt to further ionize the air. By dotting the balloon with photoelectric zinc or polonium amalgam, the amount of electricity can be greatly increased."



One hundred balloons, 100 yards apart, will generate at least 200 horsepower, up to 400 during winter. Plauson used batteries of condensers and high voltage transformers to light lamps, run motors and charge batteries, etc. He also invented an electrostatic rotary transformer to produce alternating current. The system literally sucks electricity from the collector balloons. The balloons also act as lightning arresters and quickly discharge thunder clouds.

> "There is no doubt that this invention will soon come into universal use all over the world. We will see the land dotted with captive balloons, particularly in the country and wherever water power does not abound. Indeed, the time is not distant when nearly all of our power will be derived from the atmosphere. So far it seems to be the cheapest form of power known... safely extracting several kilowatts of electrical power from the atmosphere with metallic surfaced balloons, elevated to a height of only 1000 feet.
>
> "German patents show the use of a kite balloon from which hangs a metal net to collect electricity. The tether-conductor leads to a windlass. The patents claim that at a height of one mile 225,000 volts will be available. Plauson proposed the construction of insulated towers about 1000 feet high to support the aerials... [H]e carried out experiments with a balloon made of aluminum leaf with collecting needles of amalgamated zinc with a radium preparation as an ionizer. The surface of the balloon was sprinkled over with zinc amalgam. It was sent up to a height of 300 meters, early 1,000 feet, and was held by a copper-plated steel wire. A constant current of 1.8 amperes at an average of 400 volts potential difference was obtained. This gave nearly three-quarters of a kilowatt, or close to one horsepower. The collector of the balloon insulated from the earth showed a tension of 42,000 volts. By sending up a second balloon with an antenna to the same height at a distance of 100 meters from the first balloon, a current of over 3 amperes was obtained. Then by putting into the circuit a large condenser, whose capacity was equal to the surface capacity of both balloons, and of the antenna connections, the current rose to 6.8 amperes with about 500 volts mean tension. By the use of these two balloons, he eventually ran up the power to 3.4 kilowatts."

No. 674,427. Patented May 21, 1901.

A. PALENCSÁR.

APPARATUS FOR COLLECTING ATMOSPHERIC ELECTRICITY.

(Application filed July 10, 1900.)

(No Model.) 3 Sheets—Sheet 1.

Fig:1.


11
1
8
8
2
3
4
4
7
7
9
9
9
5
13
26
12
6
14
15

Fig:3.

9
4
10
7

WITNESSES:
Ella L. Giles
Otto Munk

INVENTOR
Andor Palencsár
BY
Richards
ATTORNEYS

THE NORRIS PETERS CO., PHOTO-LITHO., WASHINGTON, D. C.

No. 674,427. Patented May 21, 1901.

A. PALENCSÁR.

APPARATUS FOR COLLECTING ATMOSPHERIC ELECTRICITY.

(Application filed July 10, 1900.)

(No Model.) 3 Sheets—Sheet 2.

Fig: 2.



WITNESSES:
Ella L. Giles
Otto Munk

INVENTOR
Andor Palencsár
BY
Richards & Co
ATTORNEYS

THE NORRIS PETERS CO., PHOTO-LITHO., WASHINGTON, D. C.

No. 674,427. **Patented May 21, 1901.**

A. PALENCSÁR.

APPARATUS FOR COLLECTING ATMOSPHERIC ELECTRICITY.

(Application filed July 10, 1900.)

(No Model.) 3 Sheets—Sheet 3.


29
31
38
40
32
33
39
41
30
34
28
36
27
35
37

Fig. 4.

WITNESSES:
Ella L. Giles
Otto Munk

INVENTOR
Andor Palencsár
BY
Richards & Co
ATTORNEYS

THE NORRIS PETERS CO., PHOTO-LITHO., WASHINGTON, D. C.

UNITED STATES PATENT OFFICE.

ANDOR PALENCSÁR, OF BUDA-PESTH, AUSTRIA-HUNGARY.

APPARATUS FOR COLLECTING ATMOSPHERIC ELECTRICITY.

SPECIFICATION forming part of Letters Patent No. 674,427, dated May 21, 1901.

Application filed July 10, 1900. Serial No. 23,102. (No model.)

To all whom it may concern:

Be it known that I, ANDOR PALENCSÁR, a subject of the King of Hungary, residing at Buda-Pesth, Austria-Hungary, have invented a certain new and useful Apparatus for Collecting Atmospherical Electricity, of which the following is a full, clear, and exact specification.

The present invention concerns an apparatus for collecting and driving or conducting atmospherical electricity which renders it practicable to obtain material quantities of the same in serviceable form.

The experiments made hitherto have been limited to deviating or conducting the electricity by simple lightning-rods without making allowance for the progress of the theory of atmospherical electricity. It is obvious that only extremely small quantities of electricity can be collected in this manner, and, moreover, it was obtained in a form which entirely precluded its utilization. It is evident that a source of electricity of irregular yield can only be utilized by means of accumulators and for charging accumulators only a current of constant potential can be employed. The potential of electricity derived or deviated by means of a lightning-rod varies within wide limits, and, moreover, it is so high that it cannot be used at all for charging accumulators. All these drawbacks are remedied by the present invention, by which the atmospheric electricity is obtained in larger quantities with as low and constant a potential as may be desired.

The idea underlying the invention is based on the modern theory of atmospheric electricity, according to which it is produced by the condensation of steam or aqueous vapors, and that the increase of potential is effected by the concentration of the small drops of water into larger ones, as the proportion of the surface of the drops to the volume of same is materially reduced thereby. According to this theory the water-droplets floating in the layers of air are considered as vehicles or carriers of the electricity, and a rational system of the deviation of the atmospheric electricity must derive it from the water-drops. This is attained by the present invention in the following manner: A collecting-body of as large a surface as possible is provided with sharp needles. This is moved in the higher layers of air, while being continually heated by a suitable heating device. Owing to the heat the water-drops immediately ambient to the collecting-body will be evaporated, their capacity is gradually reduced, while the potential of the charge grows until it reaches an infinite height with infinite smallness of the drops. It is readily apparent that the whole charge of the drops as soon as they have been evaporated will have passed to the collector or collecting-body, from which it can be conducted. For the purpose of replacing the evaporated drops, which have been deprived of their charge by new-charged drops, the collector is moved in relation to the ambient air.

One way of carrying out the invention is represented in diagram in the accompanying drawings, in which—

Figure 1 is a longitudinal section of the collecting-balloon. Fig. 2 shows the deviating and conversion device, and Fig. 3 a detail. Fig. 4 is a diagrammatic perspective view of a form of automatic regulator for the rheostatic machine.

The apparatus consists of a balloon having two walls and covered with a light wire net, preferably of aluminium wire, said net being studded with needles. Besides, the balloon carries the net 3, on which the ring 4, made of a solid but light material, (wood, cane, &c.,) is fixed. This ring carries the basket 6 by means of the cords or ropes 5. On a level with the ring 4 is the ring 7, which is kept spread by the blades or wings 9, which are journaled in a manner to rotate easily. The ring 7 is kept fixedly in position by the cords or ropes 8. The blades or wings consist of a frame covered with light material, and their rotation in either direction is limited by the stops or ledges 10. The blades or wings form advantageously an angle of sixty to seventy degrees with the vertical line.

All wire nets, ropes, rings, and blades or wings may be covered with small metal needles which are electrically connected with each other.

From the space 11, formed between the double walls of the balloon, the pipe 26 leads from the lowest point of the same to the serpentine 12, arranged in the basket 6, which in turn is connected with the pipe 13, ending in the upper part of the space 11 between the two walls 12. The serpentine is heated by means of a suitable source of heat, whereby a warm current of gas or air circulates continually between the double walls of the balloon.

Under the basket the ball-bearing 14 is arranged in electrical connection with the wire nets, and its stud is electrically connected with the carefully-insulated light though sufficiently strong cable 15.

On the earth's surface is a winch 16, Fig. 2, by means of which the balloon can be made to ascend or descend as soon as the interior space of the balloon is filled with illuminating gas or hydrogen.

The end of the cable-core is soldered to a collector arranged upon and insulated from the axle of the winch, and the electricity is conducted from this collector by means of a sliding contact. The collecting of the electricity takes place by moving the balloon continuously up and down by means of the winch. In this movement the balloon is turned by means of the wings or blades 9, which are adapted to turn the balloon always in the same direction whether ascending or descending, as in the change from ascending into descending of the balloon, or vice versa, the blades are turned over by the aerial resistance, and thus impart the rotating motion to the balloon in the same direction. In order to avoid torsion of the cable, the ball-bearing 14 is provided. This up-and-down motion and rotating of the balloon accomplishes the purpose of bringing it into contact with as many water particles floating in the air as possible.

As the electricity conducted from the collector-wing 17 possesses a much too high and varying potential for making its direct application practicable, and as it is usual with an irregular source of electricity to first charge accumulators and to further utilize the easily-regulated current of the same only, it becomes necessary to seek to maintain the electricity conducted from the collector 17 for the charging of the accumulators at a constant potential and convert the potential to a much lower one; but as we deal in this case with a direct current ordinary converters cannot be used for this purpose. Moreover, the electricity possesses in this case a much too high potential, so that with the employment of ordinary converters the greatest part of the collected electricity would be lost again. The only practical method for this purpose is the converting by means of the Planté rheostatic machine, by which this high-voltage electricity can be transformed almost without any loss whatever. Thus the question of conversion would be solved, and only the question of maintenance of constant potential remains. This is obtained in the following manner: The rheostatic machine 18 or only a part of the plates is connected with an electrometer of any construction, the movable part of which closes a contact which eventually actuates an electromagnet which effects the switching or reversion of the rheostatic machine. After the switching of the rheostatic machine it is discharged, the potential falls to zero, (*nil*,) and the electrometer resumes its initial position, whereby the current of the electromagnet which effects the reversion is interrupted and the plates of the rheostatic machine are reconnected to potential. The machine is then ready for renewed charge and is again discharged when the determined potential is reached. This action is continually repeated as long as the apparatus is in operation.

A form of the automatic regulator for the rheostatic machine is represented in Fig. 4. 27 is the contact-cylinder of the rheostatic machine, on which, for clearness sake, only the contacts for the charging position of the condenser-plates are shown, while the contacts for the discharging position, which come into action after the contact-cylinder has been turned, are omitted. The coating of the condenser-plates is connected in electrical circuit with the stationary ball 29 and the movable ball 32 of the charge-meter 30. When the charge of the rheostatic machine rises, the ball 32, arranged on the one extremity of the lever 31, is repelled and at a certain stroke actuated by means of the fork 33, which is fastened on the ball 32, and by dipping into a mercury-cup it closes the circuit of the source of current 34. This current passes through the windings of the anchor or armature 35, fixed on the shaft of the contact-cylinder, and it also passes through the electromagnet 36. Thereby the contact-cylinder is turned by a certain angle and the rheostatic machine is thus reversed. Then if the tension decreases by discharge and the repulsion of the balls 29 32 declines so far that the contact is interrupted at 33 the spring 37 turns the contact-cylinder into its normal position and the rheostatic machine is again switched to tension. The regulation of the electrometer is effected by the adjustable weights 38 39. When larger quantities of electricity shall be derived or deviated, two rheostatic machines may operate alternately so, that while the one is being discharged the other can be charged. It is readily apparent that if the capacity of the rheostatic machine is not changed the switching or reversion by the electrometer will always take place at the same potential of the rheostatic machine, and as the number of plates, and hence the proportion of conversion, remains the same the current impulses derived or deviated from the rheostatic machine will also have the same potential.

The irregularities of the source of electricity change the interval of time in which the charges follow each other; but as long as the potential remains constant this has no injurious effect on the charge of the accumulators. The current derived or deviated from the rheostatic machine can be further transformed by an ordinary converter 21 22, and whenever it is sufficiently constant it can be utilized without the intervention of the accumulators. The converters can be connected or disconnected by means of the double switch 19 20 23.

24 and 25 are the conducting-wires, which run either directly to the place of consumption or to an accumulator-battery.

Having now described my invention, what I claim as new, and desire to secure by Letters Patent, is—

1. An apparatus for collecting atmospheric electricity comprising a collecting-body adapted to be kept in motion, heating means for said body, and a rheostatic machine and a converter connected with the said body electrically, substantially as described.

2. An apparatus for collecting atmospheric electricity for storage comprising a collecting-body adapted to be kept in motion in the ambient air, heating means for said body, a conductor leading from said body, a rheostatic machine connected with the said conductor, an electrometer connected with said rheostatic machine electrically, a contact controlled by the electrometer, and an electromagnet controlled by said contact, said electromagnet controlling the reversing of the rheostatic machine, substantially as described.

3. In combination, the balloon-like collecting-body, having the collecting-points, means for heating the interior space of said body, a conductor leading from the balloon-like body, and electrical devices for receiving the current therefrom, substantially as described.

4. In combination, the balloon-like collecting-body, means for turning the same constantly in one direction in both ascending and descending, conducting means leading from the balloon and electrical devices for receiving the current therefrom, substantially as described.

In witness whereof I have hereunto set my hand in presence of two witnesses.

ANDOR PALENCSÁR.

Witnesses:
EUGÈNE HARRÄNJO,
PAUL BÖLESKEY.

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 1

Fig. 1.


13
14
7
8
6
5
9
10
11
12

Fig. 2.


1
14
5
C1
b1
7
a1
9
10
11
12
M
1
2
6
15
13

Fig. 3.


A
O
S
a
a
a
a
8
7
1
M
2
E.

Fig. 4.


S
5
1
8
7
M
2
6
E
E1

Fig. 5.


A
S
5
8
7
7a
9
E
6

Fig. 6



Inventor

Hermann Plauson

by Knight Bros

attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 2


A
S
1
M
2
7
7b
8
E
E1
E2

Fig. 7.


A
X
5
9
X1
X4
7
X5
X2
6
9a
X3
8
1
M
2
E1
E

Fig. 8.


A
S
X
8
X2
5
1
M
X1
9
2
7
X3
6
X4
E
E1

Fig. 9.



Fig. 10.


A
S
E
9
7
8
10
1
M
2
5
E

Fig. 11.


A
S
X
9
10
5
7
1
2
9a
10a
X1

Fig. 12.


A
S
X
5
9
4a
4
1
M
3
3a
8
X1
2
7
E

Fig. 13.

Inventor

Normann Plauson

by Knight Bros

attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 3


S
A
x
8
1
4
10
3a
5
9
M
3
2
4a
7
E

Fig. 14.


S
A
5
1
4
x
x1
3a
M
9
z
3
2
6
4a
7
E

Fig. 15.


S
A
8
5
1
4
6
3a
9
M
3
2
4a
7

Fig. 16.


S
A
1
R
1a
M
2a
8
2
7
E1
E

Fig. 17.


S
A
1
6
9
M
2
7
8
E2
E1
E

Fig. 18.


A
N
1
8
R
1²
1¹
2
5
7
x
E
E2
E

Fig. 19.


z
z
z
A1
A2
A3
A4
A5
A10
A9
A8
A7
A6
n
x
x1
x5
x9
x6
A
S
5
1
7
8
2
E

Fig. 20.

Inventor
Hermann Plauson
by Knight Bros
Attorneys

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 4


5
5a
5b
D
D1
x
z
A
C
1
2
3
3a
4
4a
7
E
M
C1
C2
C3
D1
D3
E1
E2
E3
5c

Fig. 22.

Fig. 21.

Fig. 23.

Inventor
Hermann Plauson
by Knight Bro
Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 5


A
a
b
c
d
e
2
L
3a
3
3b
W
12
20
19
18
S1
17
16
13
21
22
23
24
11
S2
5
14
8
7
9
10
15
6
E1
E2

Fig. 24.

Inventor

Hermann Plauson

by Knight Bro

Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 6

Fig. 25.



A_1
A_2
A_3
A_4
S_1
S_2
S_3
S_4
S_a
S_b
S_c
S_d
R.
12
13
16
17
18
19
20
21
22
23
24
25
26
27
28
J.
5
6
7
8
M
E_1
E_2

Inventor

Hermann Plauson

by

Knight Bros

attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 7


1
2
3
4
5
6
7
8
I
19
S
S1
abcd
F1
16
A
18
17
12
g
9
14
10
11
K
13
B
B1
15
F
14
E1
E

Fig. 26.

Inventor
Hermann Plauson
by Knight Bros
Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921. 12 Sheets-Sheet 8


22
23
II
I
6
3
2
5
1
4
21
II
I
9
10
19
11
F
S
E
S_I
E_I
20
17
13
12
F_I
S_{II}
E_{II}

Fig. 27.

Inventor

Hermann Plauson

by Knight Bros

Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 9


1
2
4
5
3
6
II
8
7
II
I
I
III
II¹
I¹
III
20
19
II¹
9
12
10
A
a
14
B
b
13
F
S₁
S
E₁
E

Fig. 28.

Inventor
Hermann Plauson
by
Knight Bros
attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921. 12 Sheets-Sheet 10


B
C
K
L
P
+
−
N
P
+
−
N
9
−
E

Fig. 29.


a
b
a
b
F
B
C
K
L
P
+
N
−
9
5
−
E

Fig. 30.

Inventor

Hermann Plauson

by

Knight Bros

Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 11


z
B
C
K
P
L
+
+
−
−
9
10
11
−
E

Fig. 31.


z
B
C
K
L
5
6
+
−
9
G
N
−
E

Fig. 32.



Fig. 33.

Inventor
Hermann Plauson
by Knight Bros
attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 12


A
1
+
5
+
3
2
+
6
–
8
7
9
10
S
E
E_1

Fig. 34


A
5
n
+
1
8
10
9
13
12
+
6
3
–
2
–
11
m
S
E
E_1

Fig. 35.


A
5
1
2
11
12
3
8
7
9
10
S
E
E_1

Fig. 36.


A
5
1
2
9
10
3
8
S
E
E_1

Fig. 37.

Inventor
Hermann Plauson
by Knight Bros
attorneys

Patented June 9, 1925. **1,540,998**

UNITED STATES PATENT OFFICE.

HERMANN PLAUSON, OF HAMBURG, GERMANY.

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY.

Application filed January 13, 1921. Serial No. 437,107.

To all whom it may concern:

Be it known that I, HERMANN PLAUSON, Esthonian subject, residing in Hamburg, Germany, have invented certain new and useful Improvements in the Conversion of Atmospheric Electric Energy, of which the following is a specification.

Methods of obtaining atmospheric electricity by means of metallic nettings set with spikes which are held by means of ordinary or anchored kite balloons made of fabrics and filled with hydrogen, are in theory already known. Atmospheric electricity obtained in this way has been suggested to be used in the form of direct current for the charging of accumulators. This knowledge however is at present only theoretical as the conversion in practice has hitherto been a failure. No means are known of protecting the apparatus from destruction by lightning. The balloons used for collecting the charge must also be made of very large size in order to be able to support the weight of the metallic netting and the heavy cable connections.

Instead of using heavy metallic netting as collectors attached to single air balloons of non-conducting materials which are liable to be torn and are permeable to the gas, it is proposed to use metallic balloon collectors which have the following important advantages—

(*a*) The metallic cases are impenetrable to helium and hydrogen; they also represent large metallic weather-proof collecting surfaces.

(*b*) Radio active means and the like may be easily applied internally or externally; whereby the ionization is considerably increased and therewith also the quantity of atmospheric electricity capable of being collected.

(*c*) Such balloon collectors of light metal do not require to be of large size as they have to carry only their own moderate weight, and that of the conducting cable or wire.

(*d*) The entire system therefore offers little surface for the action of storm and wind and is resistant and stable.

(*e*) Each balloon can be easily raised and lowered by means of a winch so that all repairs, recharging and the like can be carried out without danger during the operation.

It is further proposed to use a collecting aerial network of several separate collectors spread out in the air above the earth, which collectors are interconnected by electrical conductors.

According to this invention charges of atmospheric electricity are not directly converted into mechanical energy, and this forms the main difference from previous inventions, but the static electricity which runs to earth through aerial conductors in the form of direct current of very high voltage and low current strength is converted into electro-dynamic energy in the form of high frequency vibrations. Many advantages are thereby obtained and all disadvantages avoided.

The very high voltage of static electricity of a low current strength can be converted by this invention to voltages more suitable for technical purposes and of greater current strength. By the use of closed oscillatory circuits it is possible to obtain electromagnetic waves of various amplitude and thereby to increase the degree of resonance of such current. Such resonance allows various values of inductance to be chosen whereby again the governing of the starting and stopping of machines driven thereby by simply tuning the resonance between coils of the machine and the transformer circuit forming the resonance can easily be obtained. Further, such currents have the property of being directly available for various uses, even without employing them for driving motors, of which there may be particularly mentioned, lighting, production of heat and use in electro-chemistry.

Further, with such currents a series of apparatus may be fed without direct current supply through conductors and also the electro-magnetic high frequency currents may be converted by means of special motors adapted for electro-magnetic oscillations into mechanical energy, or finally converted by special machines into alternating current of low frequency or even into direct current of high potential.

The invention is more particularly described with reference to the accompanying diagrams in which:—

Figure 1 is an explanatory figure.

Figure 2 is a diagrammatic view of the simplest form.

Figure 3 shows a method of converting atmospheric electrical energy for use with motors.

Figure 4 is a diagram showing the use of protective means.

Figure 5 is a diagram of an arrangement for converting large current strengths.

Figure 6 is a diagram of an arrangement including controlling means.

Figure 7 shows means whereby the spark gap length can be adjusted.

Figure 8 shows a unipolar connection for the motor.

Figure 9 shows a weak coupled system suitable for use with small power motors.

Figures 10, 11 and 12 show modified arrangements.

Figure 13 shows a form of inductive coupling for the motor circuit.

Figure 14 is a modified form of Figure 13 with inductive coupling.

Figure 15 is an arrangement with non-inductive motor.

Figure 16 is an arrangement with coupling by condenser.

Figures 17, 18 and 19 are diagrams of further modifications.

Figure 20 shows a simple form in which the aerial network is combined with special collectors.

Figure 21 shows diagrammatically an arrangement suitable for collecting large quantities of energy.

Figure 22 is a modified arrangement having two rings of collectors.

Figure 23 shows the connections for three rings of collectors.

Figure 24 shows a collecting balloon and diagram of its connection of condenser batteries.

Figures 25 and 26 show modified collector balloon arrangements.

Figure 27 shows a second method of connecting conductor for the balloon aerials.

Figure 28 shows an auto-transformer method of connection.

Figure 29 shows the simplest form of construction with incandescent cathode.

Figure 30 shows a form with cigar shaped balloon.

Figure 31 is a modified arrangement.

Figure 32 shows a form with cathode and electrode enclosed in a vacuum chamber.

Figure 33 is a modified form of Figure 32.

Figure 34 shows an arc light collector.

Figure 35 shows such an arrangement for alternating current.

Figure 36 shows an incandescent collector with Nernst lamp.

Figure 37 shows a form with a gas flame.

Figure 1 illustrates a simple diagram for converting static electricity into dynamic energy of a high number of oscillations. For the sake of clearness in the drawings an influence machine is assumed to be employed and not an aerial antenna. 13 and 14 are combs for collecting the static electricity of the influence machine. 7 and 8 are spark discharging electrodes, 6 and 5 condensers, 9 an inductive primary coil, 10 secondary coil, 11 and 12 ends of conductors of the secondary coil 10. When the disc of the static influence machine is rotated by mechanical means, the combs collect the electric charges one the positive and the other the negative, and charge the condensers 5 and 6 until such a high potential is formed across the spark gap 7—8, that the spark gap is jumped. As the spark gap 7—8 forms a closed circuit with condensers 6 and 5, and inductive resistance 9, as is well known, waves of high frequency electromagnetic oscillations will pass in this circuit.

The high frequency of the oscillations produced in the primary circuit induces waves of the same periodicity in the secondary circuit. Thus in the primary circuit electromagnetic oscillations are formed by the passage of the spark over the spark gap and these waves are maintained by fresh charges of static electricity.

By suitably selecting the ratio between the number of the coils in the primary and secondary circuits with regard to a correct application of the co-efficients of resonance (capacity, inductance, and resistance) the high voltage of the primary circuit may be suitably converted into low voltage and high current strength.

When the oscillatory discharges in the primary circuit becomes weaker or entirely cease, the condensers are charged again by the static electricity until the accumulated charge again breaks down the spark gap. All this is repeated as long as electricity is produced by the static machine by employing mechanical energy.

An elementary form of the invention is shown in Figure 2 in which two spark gaps in parallel are used one of which may be termed the working gap 7 in Figure 2, whilst the second serves as a safety device for excess voltage and consists of a larger number of spark gaps than the working section, which gaps are arranged in series and are bridged by very small capacities as is illustrated in a_1, b_1, c_1, Figure 2 which allow of uniform sparking in the safety section.

In Figure 2 A is the aerial antenna for collecting charges of atmospheric electricity, 13 is the earth connection of the second part of the spark gap, 5 and 6 are condensers, 9 a primary coil. Now when through the aerial A the positive atmospheric electricity seeks to combine with the negative charge to earth, this is prevented by (the air gap between) the spark gaps. The resistance of the spark gap 7 is, as shown in the drawings, lower than that of the other safety section which consists of three spark gaps connected in

series, and consequently a three times greater air resistance is offered by the latter.

So long therefore, as the resistance of the spark gap 7 is not overloaded, so that the other spark gaps have an equal resistance with it the discharges take place only over spark gap 7. Should however the voltage be increased by any influences so that it might be dangerous for charging the condensers 5 and 6 or for the coil insulation 9 and 10 in consequence of break down, by a correct regulation of this spark gap the second spark gap can discharge free from inductive effects direct to earth without endangering the machine.

Without this second spark gap, arranged in parallel having a higher resistance than the working spark gap it is impossible to collect and render available large quantities of electrical energy.

The action of this closed oscillation circuit consisting of spark gap 7, two condensers 5 and 6, primary coil 9, and also secondary coil 10 is exactly the same as the one described in Figure 1 with the arrangement of the static induction machine with the only difference that here the second spark gap is provided. The electromagnetic high frequency alternating current obtained can be tapped off from the conductors 11 and 12 for lighting and heating purposes. Special kinds of motors adapted for working with these peculiar electrical charges may be connected at 14 and 15 which can work with static electricity charges or with high frequency oscillations.

In addition to the use of spark gaps in parallel a second measure of security is also necessary for taking off the current. This precaution consists according to this invention, in the introduction of and method of connecting certain protective electromagnets or choking coils in the aerial circuit as shown by S in Figure 3.

A single electromagnet only having a core of the thinnest possible separate laminations is connected with the aerial.

In the case of high voltages in the aerial network or at places where there are frequent thunder storms, several such magnets may however be connected in series.

In the case of large units or plants several electromagnets can be employed in parallel or in series parallel.

The windings of these electromagnets may be simply connected in series with the aerials. In this case the winding preferably consists of several thin parallel wires, which make up together, the necessary section.

The winding may be made of primary and secondary windings in the form of a transformer. The primary winding will be then connected in series with the aerial network, and the secondary winding more or less short-circuited over a regulating resistance or an induction coil. In the latter case it is possible to regulate to a certain extent the effect of the choking coils. In the further description of the connecting and constructional diagrams the aerial electromagnet choke coil is indicated by a simple ring S.

Figure 3 shows the simplest way of converting atmospheric electricity into electromagnetic wave energy by the use of special motors adapted for high oscillatory currents or static charges of electrical energy. Recent improvements in motors for working with static charges and motors working by resonance, that is to say, having groups of tuned electromagnetic cooperating circuits render this possible but such do not form part of the present invention.

A motor adapted to operate with static charges will for the sake of simplicity be diagrammatically indicated by two semicircles 1 and 2 and the rotor of the motor by a ring M. (Figure 3.) A is a vertical aerial or aerial network. S the safety choke or electromagnet with coil O as may be seen is connected with the aerial A. Adjacent the electromagnet S the aerial conductor is divided into three circuits, the circuit 8 giving the safety spark gap, the circuit 7 with the working spark gap, and then a circuit including the stator terminal 1, the rotor and stator terminal 2 at which a connection is made to the earth wire. The two spark gaps are also connected metallically with the earth wire. The method of working these diagrams is as follows:

The positive atmospheric electric charge collected tends to combine with the negative electricity (or earth electricity) connected with the earth wire. It travels along the aerial A through the electromagnet S without being checked as it flows in the same direction as the direct current. Further, its progress is arrested by two sparks gaps placed in the way and the stator condenser surfaces. The stator condenser surfaces are charged until the charge is greater than the resistance of the spark gap 7, whereupon a spark springs over the spark gap 7 and an oscillatory charge is obtained as by means of the motor M, stator surfaces 1 and 2, and spark gap 7, a closed oscillation circuit is obtained for producing the electromagnetic oscillations. The motor here forms the capacity and the necessary inductance and resistance, which, as is well known, are necessary for converting static electricity into electromagnetic wave energy.

The discharges formed are converted into mechanical energy in special motors and can not reach the aerial network by reason of the electromagnet or choke. If, however, when a spark springs over the spark gap 7 a greater quantity of atmospheric electricity tends to flow to earth, a counter voltage is

induced in the electromagnet, which is greater the more rapidly and strongly the flow of current direct to the earth is. By the formation of this opposing voltage a sufficiently high resistance is offered to the flow of atmospheric electricity direct to earth to prevent a short circuit with the earth.

The circuit containing spark gap 8 having a different wave length which is not in resonance with the natural frequency of the motor, does not endanger the motor and serves as security against excess voltage, which, as practical experiments have shown, may still arise in certain cases, but can be conducted direct to earth through this spark gap.

In the diagram illustrated in Figure 4 the spark gap 7 is shunted across condensers 5 and 6 from the motor M. This construction affords mainly a better insulation of the motor against excess voltage and a uniform excitation through the spark gap 7.

In Figure 5 a diagram is illustrated for transforming large current strengths which may be employed direct without motors, for example, for lighting or heating purposes. The main difference is that here the spark gap consists of a star shaped disc 7 which can rotate on its own axis and is rotated by a motor opposite similarly fitted electrodes 7^a. When separate points of stars face one another, discharges take place, thus forming an oscillation circuit over condensers 5 and 6 and inductance 9 for oscillatory discharges. It is evident that a motor may also be directly connected to the ends of the spiral 9.

The construction of the diagram shown in Figure 6 permits of the oscillation circuit of the motor being connected with an induction coil. Here a regulating inductive resistance is introduced for counter-acting excess voltages in the motor. By cutting the separate coils 9 (coupled inductively to the aerial) in or out the inductive action on the motor may be more or less increased or variable aerial action may be exerted on the oscillation circuit.

In Figure 7 the oscillation circuit is closed through the earth (E and E_1). The spark gap 7 may be prolonged or shortened by more or fewer spark gaps being successively connected by means of a contact arm 7^b.

Diagram 8 shows a unipolar connection of the motor with the aerial network. Here two oscillation circuits are closed through the same motor. The first oscillation circuit passes from aerial A through electromagnet S, point x, inductance 9^a to the earth condenser 6 and further, over spark gap 7 to the aerial condenser 5 and back to x. The second oscillation circuit starts from the aerial condenser 5 at the point x^1 over the inductance 9 to the earth condenser 6 at the point x^3 and through the condenser 6 over the spark gap 7 back to x^1. The motor itself is inserted between the two points of the spark gap 7. From this arrangement slightly damped oscillation wave currents are produced.

In the diagram illustrated in Figure 9 a loosely coupled system of connections is illustrated which is assumed to be for small motors for measuring purposes. A indicates the aerial conductor, S the electromagnet in the aerial conductor, 9 the inductance, 7 the spark gap, 5 and 6 condensers, E the earth, M the motor, and 1 and 2 stator connections of the motor. The motor is directly metallically connected with the oscillation circuit.

In Figure 10 a purely inductive coupling is employed for the motor circuit. The motor is connected with the secondary wire 10 as may be seen in Figure 11 in a somewhat modified diagram connection. The same applies to the diagram of Figure 12.

The diagrams hitherto described preferably allow of motors of small and medium strength to be operated. For large aggregates, however, they are too inconvenient as the construction of two or more oscillation circuits for large amounts of energy is difficult; the governing is still more difficult and the danger in switching on or off is greater.

A means of overcoming such difficulties is shown in Figure 13. The oscillation circuit here runs starting from the point x over condenser 5, variable inductance 9, spark gap 7 and the two segments (3^a and 4^a) forming arms of a Wheatstone bridge, back to x. If the motor is connected by brushes 3 and 4 transversely to the two arms of the bridge as shown in the drawings, electromagnetic oscillations of equal sign are induced in the stator surfaces 1 and 2 and the motor does not revolve. If however, the brushes 3 and 4 are moved in common with the conducting wires 1 and 2 which connect the brushes with the stator poles a certain alteration or displacement of the polarity is obtained and the motor commences to revolve.

The maximum action will result if one brush 3 comes on the central sparking contact 7 and the other brush 4 on the part x. They are however, usually in practice not brought on to the central contact 7 but only held in the path of the bridge segments 4^a and 3^a in order not to connect the spark gaps with the motor oscillation circuit.

As however, the entire oscillation energy can thereby not act on the motor it is better to carry out the same system according to the diagram 14. The diagram 14 differs from the foregoing only by the motor not being directly metallically connected with the segments of the commutator, but only a primary coil 9 which induces in a secondary coil 10, current which feeds the motor M and takes the place of the rotor. By this

arrangement a good transforming action is obtained, a loose coupling and also an oscillation circuit without a spark gap.

In Figure 15 the motor is not purely inductively as in 14, but directly metallically branched off from the primary coil (at x and x^1) after the principle of the auto-transformer.

In Figure 16 instead of an inductance a condenser 6 is in similar manner, and for the same object inserted between the segments 3^a and 4^a. This has the advantage that the segments 3^a and 4^a need not be made of solid metal but may consist of spiral coils whereby a more exact regulation is possible and further motors of high inductance may be employed.

The arrangements of Figures 17, 18 and 19 may be employed for use with resonance and particularly with induction condenser motors; between the large stator induction condenser surfaces, small reversing pole condensers are connected, which, as may be seen from Figures 17, 18 and 19 are led together to earth. Such reversing poles have the advantage that with large quantities of electrical energy the spark formation between the separate oscillation circuits ceases.

Figure 19 shows a further method which prevents electromagnetic oscillations of high number of alternations formed in the oscillation circuit striking back to the aerial conductor. It is based on the well known principle that a mercury lamp, one electrode of which is formed of mercury, the other of solid metal such as steel allows an electric charge to pass in only one direction from the mercury to the steel and not vice versa. The mercury electrode of the vacuum tube N is therefore connected with the aerial conductor and the steel electrode with the oscillation circuit. From this it results that charges can pass only from the aerial through the vacuum tube to the oscillation circuit, but not vice versa. Oscillations which are formed on being transformed in the oscillation circuit cannot pass to the aerial conductor.

In practice these vacuum tubes must be connected behind an electromagnet as the latter alone affords no protection against the danger of lightning.

As regards the use of spark gaps, all arrangements as used for wireless telegraphy may be used. Of course the spark gaps in large machines must have a sufficiently large surface. In very large stations they are cooled in liquid carbonic acid or better still in liquid nitrogen or hydrogen; in most cases the cooling may also take place by means of liquefied low homologues of the metal series or by means of hydrocarbons the freezing point of which lies at between −90° C. and −40° C. The spark gap casing must also be insulated and be of sufficient strength to be able to resist any pressure which may arise. Any undesirable excess super-pressure which may be formed must be automatically let off. I have employed with very good results mercury electrodes which were frozen in liquid carbonic acid, the cooling being maintained during the operation from the outside through the walls.

Figure 20 is one of the simplest forms of construction of an aerial network in combination with collectors, transformers and the like illustrated diagrammatically. E is here the earth wire, 8 the safety spark gap, 7 the working spark gap, 1 and 2 the stator surfaces of the motor, 5 a condenser battery, S the protective magnet which is connected with the coil in the aerial conductor, A^1 to A^{10} aerial antennæ with collecting balloons, N horizontal collecting or connecting wires from which, to the centre a number of connections run.

The actual collectors consist of metal sheaths preferably made of an aluminium magnesium alloy, and are filled with hydrogen or helium and are attached to copper plated steel wires. The size of the balloon is selected so that the actual weight of the balloon and the weight of the conducting wire is supported thereby. On the top of the balloon aluminium spikes, made and gilded in a special manner hereinafter described, are arranged in order to produce a conductor action. Small quantities of radium preparations, more particularly polonium-ionium or mesothorium preparations considerably increase the ionization, and therewith the action of these collectors.

In addition to metal balloons, fabric balloons which are superficially metal coated according to Schoop's metal spraying process, may however also be employed. A metallic surface may also be produced by lacquering with metallic bronzes, preferably according to Schoop's spraying process or lacquering with metallic bronze powders in two electrical series of widely different metals, because thereby the collecting effect is considerably increased.

Instead of the ordinary round balloons, elongated cigar shaped ones may be employed. In order also to utilize the frictional energy of the wind, patches or strips of non-conducting substances which produce electricity by friction, may be attached to the metallized balloon surfaces. The wind will impart a portion of its energy in the form of frictional electricity, to the balloon casing, and thereby the collecting effect is substantially increased.

In practice however, very high towers (up to 300 metres is fully admissible) may be employed as antennæ. In these towers copper tubes rise freely further above the top of the tower. A gas lamp secured

against the wind is then lit at the point of the copper tube and a netting is secured to the copper tube over the flame of this lamp to form a collector. The gas is conveyed through the interior of the tube up to the summit. The copper tube must be absolutely protected from moisture at the place at which it enters the tower and also rain must be prevented running down the walls of the tower which might lead to a bad catastrophe. This is done by bell shaped enlargements which expand downwards, being arranged in the tower in the form of high voltage insulators of Siamese pagodas.

Special attention must be devoted to the foundations of such towers. They must be well insulated from the ground, which may be obtained by first embedding a layer of concrete in a box form to a sufficient depth in the ground and inserting in this an asphalt lining and then glass bricks cast about 1 or 2 metres in thickness. Over this in turn there is a ferro-concrete layer in which alone the metal foot of the tube is secured. This concrete block must be at least 2 metres from the ground and be fully protected at the sides by a wooden covering, from moisture. In the lower part of the tower a wood or glass house for the large condenser batteries or for the motors may be constructed. In order to lead the earth connection to the ground water, a well insulated pit constructed of vitreous bricks, must be provided. Several such towers are erected at equal distances apart and connected with a horizontal conductor. The horizontal connecting wires may either run directly from tower to tower or be carried on bell shaped insulators similar to those in use for high voltage conductors. The width of the network may be of any suitable size, and the connection of the motors can take place at any suitable places.

In order to collect large quantities of electricity with few aerials it is well to provide the aerial conductor with batteries of condensers as shown in two methods of construction in Figures 21 and 22. In Figure 21 the batteries of condensers 5 are connected on the one hand with the aerial electricity collectors Z by the aerial conductor A, and on the other hand interconnected in series with an annular conductor from which horizontal conductors run to the connecting points C to which the earth wire is connected.

Figure 22 shows a similar arrangement. Should two such series of antennæ rings be shown by a voltmeter to have a large difference of potential (for example, one in the mountains and one in the plain) or even of different polarity these differences may be compensated for by connecting sufficiently large condenser batteries (5, 5^a, 5^b) by means of Maji star conductors D and D^1. In Figure 23 a connection of three such rings of collectors to form a triangle with a central condenser battery is illustrated.

The condenser batteries of such large installations must be embedded in liquefied gases or in liquids freezing at very low temperatures. In such cases a portion of the atmospheric energy must be employed for liquefying these gases. It is also preferable to employ pressure. By this means the condenser surfaces may be diminished, and still allow for large quantities of energy to be stored, secure against breakdown. For smaller installations the immersing of the condensers in well insulated oil or the like, suffices. Solid substances on the other hand cannot be employed as insulators.

The arrangement in the diagrams hitherto described was always such that the condenser batteries were connected with both poles directly to the aerial conductors. An improved diagram of the connections for obtaining atmospheric electricity for the condenser batteries has however, been found to be very advantageous, this arrangement consists in that they are connected by only one pole (unipolar) to the collecting network. Such a method of arrangement is very important, as by means of it a constant current and an increase of the normal working pressure or voltage is obtained. If for example a collecting balloon aerial which is allowed to rise to a height of 300 metres, shows 40,000 volts above earth voltage, in practice it has been found that the working voltage (with a withdrawal of the power according to the method hereinbefore described by means of oscillating spark gaps and the like) is only about 400 volts. If however, the capacity of the condenser surfaces be increased, which capacity in the above mentioned case was equal to that of the collecting surface of the balloon aerials, to double the amount, by connecting the condenser batteries with only one pole, the voltage rises under an equal withdrawal of current up to and beyond 500 volts. This can only be ascribed to the favourable action of the connecting method.

In addition to this substantial improvement it has also been found preferable to insert double inductances with electromagnets and to place the capacities preferably between two such electromagnets. It has also been found that the useful action of such condensers can be further increased if an induction coil be connected as inductive resistance to the unconnected pole of the condenser, or still better if the condenser itself be made as an induction condenser. Such a condenser may be compared with a spring which when compressed carries in itself accumulated force, which it again gives off when released. In charging, a charge with reversed sign is formed at the

other free condenser pole, and if through the spark gap a short circuit results, the accumulated energy is again given back since now new quantities of energy are induced at the condenser pole connected with the conductor network, which in fact charges with opposite signs to that at the free condenser pole. The new induced charges have of course the same sign as the collector network. The whole voltage energy in the aerial is thereby however increased. In the same space of time larger quantities of energy are accumulated than is the case without such inserted condenser batteries.

In Figures 24 and 25 two different diagrams of connections are more exactly illustrated, Figure 24 shows a collecting balloon and the diagram of the connections to earth. Figure 25 four collecting balloons and the parallel connection of the condenser batteries belonging thereto.

A is the collecting balloon made of an aluminium magnesium alloy (electron metal, magnalium) of a specific gravity of 1.8 and a thickness of plate 0.1 to 0.2 mm. Inside there are eight strong vertical ribs of T shaped section about 10 to 20 mm. in height and about 3 mm. in thickness with the projecting part directed inwards (indicated by *a*, *b*, *c*, *d* and so forth); they are riveted together to form a firm skeleton and are stiffened in a horizontal direction by two cross ribs. The ribs are further connected with one another internally and transversely by means of thin steel wires, whereby the balloon obtains great power of resistance and elasticity. Rolled plates of 0.1 to 0.2 mm. in thickness made of magnalium alloy are then either soldered or riveted on this skeleton so that a fully metallic casing with smooth external surface is obtained. Well silvered or coppered aluminium plated steel wires run from each rib to the fastening ring 2. Further, the coppered steel hawser L preferably twisted out of separate thin wires (shown in dotted lines in Figure 24) and which must be long enough to allow the balloon to rise in the desired height, leads to a metal roller or pulley 3 and from thence to a winch W, well insulated from the earth. By means of this winch, the balloon, which is filled with hydrogen, or helium, can be allowed to rise to a suitable height (300 to 5,000 metres) and brought to the ground for recharging or repairs.

The actual current is taken directly through a friction contact from the metal roller 3 or from the wire, or even from the winch or simultaneously from all three by means of brushes (3, 3^a and 3^b). Beyond the brushes the conductor is divided, the paths being:—firstly over 12 to the safety spark gap 8, from thence to the earth conductor E^1, and secondly over electromagnet S^1, point 13, to a second loose electromagnet having an adjustable coil S^2, then to the spark gap 7 and to the second earth conductor E^2. The actual working circuit is formed through the spark gap 7, condensers 5 and 6, and through the primary coil 9; here the static electricity formed by oscillatory discharges is accumulated and converted into high frequency electromagnetic oscillations. Between the electromagnets S^1 and S^2 at the crossing point 13, four condenser batteries are introduced which are only indicated diagrammatically in the drawings each by one condenser. Two of these batteries (16 and 18) are made as plate condensers and prolonged by regulating induction coils or spirals 17 and 19 while the two others (21 and 23) are induction condensers. As may be seen from the drawings each of the four condenser batteries 16, 18, 21, 23 is connected only by one pole to the aerial or to the collector conductor. The second poles 17, 19, 22, 24 are open. In the case of plate condensers having no inductive resistance an induction coil is inserted. The object of such a spiral or coil is the displacement of phase of the induction current by ¼ periods, whilst the charging current of the condenser poles which lie free in the air, works back to the collector aerial. The consequence of this is that in discharges in the collector aerial the back inductive action of the free poles allows a higher voltage to be maintained in the aerial collecting conductor than would otherwise be the case. It has also been found that such a back action has an extremely favourable effect on the wear of the contacts. Of course the inductive effect may be regulated at will within the limits of the size of the induction coil, the length of the coil in action being adjustable by means of wire connection without induction (see Fig. 24, No. 20).

S^1 and S^2 may also be provided with such regulating devices in the case of S^2 (illustrated by 11). If excess voltage be formed it is conducted to earth through the wire 12 and spark gap 8 or through any other suitable apparatus, since this formation would be dangerous for the other apparatus.

The action of these condenser batteries has already been hereinbefore described.

The small circles on the collector balloon indicate places at which zinc amalgam or gold amalgam or other photoelectric acting metals in the form of small patches in extremely thin layers (.01 to .05 mm. in thickness) are applied to the balloon casing of light metal. Such metallic patches may also be applied to the entire balloon as well as in greater thickness to the conducting network. The capacity of the collector is thereby considerably strengthened at the surface. The greatest possible effect in collecting may be obtained by polonium amalgams and the like. On the surface of the

collector balloon metal points or spikes are also fixed along the ribs, which spikes serve particularly for collecting the collector charge. Since it is well known that the resistance of the spikes is less the sharper the spike is, for this purpose it is therefore extremely important to employ as sharp spikes as possible. Experiments made as regards these have shown that the formation of the body of the spike or point also plays a large part. for example, spikes made of bars or rollers with smooth surfaces, have a many times greater point resistance as collector accumulator spikes than those with rough surfaces. Various kinds of spike bodies have been experimented with for the collector balloons hereinbefore mentioned. The best results were given by spikes which were made in the following way. Fine points made of steel, copper, nickel, or copper and nickel alloys, were fastened together in bundles and then placed as anode with the points in a suitable electrolyte (preferably in hydrochloric acid or muriate of iron solutions) and so treated with weak current at 2 to 3 volts pressure. After 2 to 3 hours according to the thickness of the spikes or pins the points become extremely sharp and the bodies of the spikes have a rough surface. The bundle can then be removed and the acid washed off with water. The spikes are then placed as cathode in a bath consisting of solution of gold, platinum, iridium, paladium or wolfram salts or their compounds and coated at the cathode galvanically with a thin layer of precious metal, which must however be sufficiently firm to protect them from atmospheric oxidation.

Such spikes act at a 20 fold lower voltage almost as well as the best and finest points made by mechanical means. Still better results are obtained if polonium or radium salts are added to the galvanic bath when forming the protective layer or coating. Such pins have a low resistance at their points and even at one volt and still lower pressures have an excellent collector action.

In Figure 24 the three unconnected poles are not connected with one another in parallel. That is quite possible in practice without altering the principle of the free pole. It is also preferable to interconnect in parallel to a common collector network, a series of collecting aerials.

Figure 25 shows a diagram for such an installation. A^1, A^2, A^3, A^4 are four metal collector balloons with gold or platinum coated spikes which are electrolytically made in the presence of polonium emanations or radium salts, which spikes or needles are connected over four electro-magnets S^1, S^2, S^3, S^4, through an annular conductor R. From this annular conductor four wires run over four further electromagnets S^a, S^b, S^c, S^d, to the connecting point 13. There the conductor is divided, one branch passing over 12 and the safety spark gap 8 to the earth at E^1, the other over inductive resistance J and working spark gap 7 to the earth at E^2. The working circuit, consisting of the condenser 5 and 6 and a resonance motor or a condenser motor M, such as hereinbefore described, is connected in proximity round the sparking gap section 7.

Instead of directly connecting the condenser motor of course the primary circuit for high frequency oscillatory current may also be inserted.

The condenser batteries are connected by one pole to the annular conductor R and can be either inductionless (16 and 18) or made as induction condensers as shown by 21 and 23. The free poles of the inductionless condensers are indicated by 17 and 19, those of the induction condensers by 22 and 24. As may be seen from the drawings all these poles 17, 22, 19, 24 may be interconnected in parallel through a second annular conductor without any fear that thereby the principle of the free pole connection will be injured. In addition to the advantages already set forth the parallel connection also allows of an equalization of the working pressure in the entire collector network. Suitably constructed and calculated induction coils 25 and 26 may also be inserted in the annular conductor of the free poles, by means of which a circuit may be formed in the secondary coils 27 and 28 which allows current produced in this annular conductor by fluctuations of the charges or the like appearances to be measured or otherwise utilized.

According to what has been hereinbefore stated separate collector balloons may be connected at equidistant stations distributed over the entire country, either connected directly with one another metallically or by means of intermediate suitably connected condenser batteries through high voltage conductors insulated from earth. The static electricity is converted through a spark gap into dynamic energy of a high number of oscillations and may in such form be coupled as a source of energy by means of a suitable method of connecting, various precautions being observed and with special regulations. The wires leading from the collector balloons have hitherto been connected through an annular conductor without this endless connection, which can be regarded as an endless induction coil, being able to exert any action on the whole conductor system.

It has now been found that if the network conductor connecting the aerial collector balloons with one another is not made as a simple annular conductor, but preferably short circuited in the form of coils over a

condenser battery or spark gap or through thermionic tubes or valves or audions, then the total collecting network exhibits quite new properties. The collection of atmospheric electricity is thereby not only increased but an alternating field may be easily produced in the collector network. Further, the atmospheric electrical forces showing themselves in the higher regions may also be directly obtained by induction. In Figures 26 and 28 a form of construction is shown on the basis of which the further foundations of the method will be more particularly explained.

In Figure 26 1, 2, 3, 4 are metal collector balloons, 5, 6, 7, 8 their metallic aerial conductors and I the actual collector network. This consists of five coils and is mounted on high voltage insulators in the air, on high voltage masts (or with a suitable construction of cable embedded in the earth). One coil has a diameter of 1 to 100 km. or more. S and S^1 are two protective electromagnets, F the second safety section against excess voltage, E its earth conductor and E^1 the earth conductor of the working section. When an absorption of static atmospheric electricity is effected through the four balloon collectors, the current in order to reach the earth connection E^1 must flow spirally through the collector network over the electromagnet S, primary induction coil 9, conductor 14, anode A of the audion tube, incandescent cathode K, as the way over the electromagnet and safety spark gap F offers considerably greater resistance. Owing to the fact that the accumulated current flows in one direction, an electromagnetic alternating field is produced in the interior of the collector network coil, whereby the whole free electrons are directed more or less into the interior of the coil. An increased ionization of the atmosphere is therefore produced. In consequence of this the points mounted on the collector balloon show a considerably reduced resistance and therefore increased static charges between the points on the balloon and the surrounding atmosphere are produced. The result of this is a considerably increased collector effect.

A second effect which could not be obtained otherwise is obtained by the electromagnetic alternating field which running parallel to the earth surface, acts more or less with a diminishing or increasing effect on the earth magnetic field, whereby in the case of fluctuations in the current a return induction current of reversed sign is always produced in the collector coil by earth magnetism. Now if, however, a constantly pulsating continuous alternating field is produced as stated in the above collector network I, an alternating current of the same periodicity is produced also in the collecting network coil. As the same alternating field is further transmitted to the aerial balloon, the resistance of its points is thereby considerably reduced, whilst the collector action is considerably increased. A further advantage is that positive electrons which collect on the metal surfaces during the conversion into dynamic current produce a so-called drop of potential of the collector area. As an alternating field is present, the negative ions surrounding the collector surfaces, when discharge of the collector surfaces takes place produce by the law of induction, an induction of reversed sign on the collector surface and so forth (that is to say again a positive charge). In addition to the advantages hereinbefore set forth, the construction of connecting conductors in coil form when of sufficiently large diameter, allows of a utilization of energy arising in higher regions also in the simplest way. As is well known electric discharges frequently take place at very great elevations which may be observed, such as St. Elmo's fires or northern lights. These energy quantities have not been able to be utilized up to now. By this invention all these kinds of energy, as they are of an electromagnetic nature and the direction of the axis of the collector coils stands at right angles to the earth's surface, can be more or less absorbed in the same way as a receiver in wireless telegraphy absorbs waves coming from a far distance. With a large diameter of the spiral it is possible to connect large surfaces and thereby to take up also large quantities of energy.

It is well known that large wireless stations in the summer months, and also in the tropics are very frequently unable to receive the signals in consequence of interruptions which are caused by atmospheric electricity, and this takes place with vertical coils of only 40 to 100 m. diameter. If on the contrary horizontal coils of 1 to 100 km. diameter be employed very strong currents may be obtained through discharges which are constantly taking place in the atmosphere. Particularly in the tropics or still better in the polar regions where the northern lights are constantly present, large quantities of energy may probably be obtained in this way. A coil with several windings should act the best. In similar manner any alteration of the earth magnetism should act inductively on such a coil.

It is not at all unlikely that earthquakes and spots on the sun will also produce an induction in such collector coils of sufficient size. In similar manner this collector conductor will react on earth currents more particularly when they are near the surface of the earth or even embedded in the earth. By combining the previous kind of current collectors so far as they are adapted for

the improved system with the improved possibilities of obtaining current the quantities of free natural energy which are to be obtained in the form of electricity are considerably increased.

In order to produce in the improved collector coil uniform current oscillations of an undamped nature so-called audion high vacuum or thermionic tubes of suitable connection are employed instead of the previously known spark gaps (Fig. 26, Nos. 9–18). The main aerial current flows through electromagnet S (which in the case of a high number of alternations is not connected here but in the earth conductor E^1) and may be conveyed over the primary coils in the induction winding through wire 14 to the anode A of the high vacuum grid tube. Parallel with the induction resistance 9 a regulating capacity of suitable size, such as condenser 11 is inserted. In the lower part of the vacuum grid tube is arranged the incandescent filament or the cathode K which is fed through a battery B. From the battery B two branches run, one to the earth conductor E^1 and the other through battery B^1 and secondary coil 10 to the grid anode g in the vacuum tube. By the method of connections shown in dotted lines, a desired voltage at the grid electrode g may also be produced through the wire 17 which is branched off from the main current conductor through switches 16 and some small condensers (a, b, c, d) connected in series, and conductor 18, without the battery B^1 being required.

The action of the entire system is somewhat as follows:—

On the connecting conductor of the aerial collector network being short circuited to earth, the condenser pole 11 is charged and slightly damped oscillations are formed in the short circuited existing oscillation circuit formed of the condenser 11 and self inductance 9. In consequence of the coupling through coil 10, fluctuations of voltage take place in the grid circuit 15 with the same frequency, which, fluctuations in turn influence the strength of the electrode current passing through the high vacuum amplyfying tube and thus produce current fluctuations of the same frequency in the anode circuit. A permanent supply of energy to the oscillation circuits 9 and 10 consequently takes place, until a condition of balance is set up, in which the consumed oscillation energy is equal to that absorbed. Thereby constant undamped oscillations are now produced in the oscillation circuits 9–11.

For regular working of such oscillation producers high vacuum strengthening tubes are necessary and it is also necessary that the grid and anode voltages shall have a phase difference of 180° so that if the grid is negatively charged, then the anode is positively charged and vice versa. This necessary difference of phase may be obtained by most varied connections, for example, by placing the oscillation circuit in the grid circuit or by separating the oscillation circuit and inductive coupling from the anodes and the grid circuit and so forth.

A second important factor in this way of converting static atmospheric electricity into undamped oscillations is that care must be taken that the grid and anode voltages have a certain relation to one another; the latter may be obtained by altering the coupling and a suitable selection of the self induction in the grid circuit, or as shown by dotted lines 18, 17, 16 by means of a larger or smaller number of condensers of suitable size connected in series; in this case the battery B^1 may be omitted. With a suitable selection of the grid potential a glow discharge takes place between the grid g and the anode A, and accordingly at the grid there is a cathode drop and a dark space is formed. The size of this cathode drop is influenced by the ions which are emitted in the lower space in consequence of shock ionization of the incandescent cathodes K and pass through the grid in the upper space. On the other hand the number of the ions passing through the grid is dependent on the voltage between the grid and the cathode. Thus if the grid voltage undergos periodic fluctuations (as in the present case) the amount of the cathode drop at the grid fluctuates and consequently the internal resistance of the tube correspondingly fluctuates, so that when a back coupling of the feed circuit with the grid circuit takes place, the necessary means are afforded for producing undamped oscillations and of taking current, according to requirements from the collecting conductor.

The frequency of the undamped oscillations produced is with a suitably loose coupling equal to the self frequency of the oscillation circuits 9 and 10. By a suitable selection of the self induction of the coil 9 and capacity 11 it is possible to extend from frequencies which produce electromagnetic oscillations of only a few metres wave length down to the lowest practical alternating current frequency. For large installations a suitable number of frequency producing tubes in the form of the well known high vacuum transmission tubes of .5 to 2 kw. in size may be connected in parallel so that in this respect no difficulty exists.

The use of such tubes for producing undamped oscillations, and also the construction and method of inserting such transmission tubes in an accumulator or dynamo circuit is known and also that such oscillation producing tubes only work well at voltages of 1,000 up to 4,000 volts, so that on the contrary their use at lower voltages is

considerably more difficult. By the use of high voltage static electricity this method of producing undamped oscillations as compared with that through spark gaps must be regarded as an ideal solution particularly for small installations of outputs of from 1 to 100 kw.

By the application of safety spark gaps, with interpolation of electro-magnets, not only is short circuiting avoided but also the taking up of current is regulated. Oscillation producers inserted in the above way form a constantly acting electromagnetic alternating field in the collector coil, whereby as already stated, a considerable accumulating effect takes place. The withdrawal wire or working wire is connected at 12 and 13, but current may be taken by means of a secondary coil which is firmly or movably mounted in any suitable way inside the large collector coil, i. e. in its electromagnetic alternating field, so long as the direction of its axis runs parallel with that of the main current collecting coil.

In producing undamped oscillations of a high frequency (50,000 per second and more) in the oscillation circuits 9 and 11, electromagnets S and S^1 must be inserted if the high frequency oscillations are not to penetrate the collector coil, between the oscillation producers and the collector coil. In all other cases they are connected shortly before the earthing (as in Figs. 27 and 28).

In Figure 27 a second method of construction of the connecting conductor of the balloon aerials is illustrated in the form of a coil. The main difference consists in that in addition to the connecting conductor I another annular conductor II is inserted parallel to the former on the high voltage masts in the air (or embedded as a cable in the earth) but both in the form of a coil. The connecting wire of the balloon aerials is indicated as a primary conductor and also as a current producing network; the other is the consumption network and is not in unipolar connection with the current producing network.

In Figure 27 the current producing network I is shown with three balloon collectors 1, 2, 3 and aerial conductors 4, 5, 6; it is short circuited through condenser 19 and inductance 9. The oscillation forming circuit consists in this diagram of spark gap *f*, inductance 10, and condenser 11; the earth wire E, is connected to earth over electromagnet S^1. F is the safety spark gap which is also connected to earth through a second electromagnet S at E. On connecting up the condenser circuit 11 this is charged over the spark gap *f* whereby an oscillatory discharge is formed. This discharging current acts through inductance 10 on the inductively coupled secondary 9, whereby in the producing network a modification of the potential of the condenser 19 is produced. The consequence of this is that oscillations arise in the coil shaped producer network. These oscillations induce a current in the secondary circuit II, which has a smaller number of windings and a less resistance, the voltage of which, according to the proportion of the number of windings and of the ohmic resistance, is considerably lower whilst the current strength is greater.

In order to convert the current thus obtained into current of an undamped character, and to tune its wave lengths, a sufficiently large regulatable capacity 20 is inserted between the ends 12 and 13 of the secondary conductor II. Here also current may be taken without an earth conductor, but it is advisable to insert a safety spark gap E^1 and to connect this with the earth over an electromagnet S^2.

The producer network may be connected with the working network II over an inductionless condenser 21 or over an induction condenser 22, 23. In this case the secondary conductor is unipolarly connected with the energy conductor.

In Figure 28 the connecting conductor between the separate accumulator balloons is carried out according to the autotransformer principle. The collecting coil connects four aerial balloons 1, 2, 3, 4, the windings of which are not made side by side but one above the other. In Figure 28 the collector coil I is shown with a thin line, the metallically connected prolongation coils II with a thick line. Between the ends I^1 and II^1 of the energy network I a regulating capacity 19 is inserted. The wire I^1 is connected with the output wire and with the spark gap F.

As transformer of the atmospheric electricity an arrangement is employed which consists in using rotary pairs of condensers in which the one stator surface B is connected with the main current, whilst the other A is connected with the earth pole. Between these pairs of short circuited condensers are caused to rotate from which the converted current can be taken by means of two collector rings and brushes, in the form of an alternating current, the frequency of which is dependent on the number of balloons and the revolutions of the rotor. As the alternating current formed in the rotor can act, in this improved method of connection described in this invention, through coils 10 on the inductance 9, an increase or diminution of the feed current in I can be obtained according to the direction of the current by back induction. Current oscillations of uniform rhythm thereby result in the coil shaped windings of the producer net-work.

As the ends of this conductor are short cir-

cuited through the regulatable condenser 19 these rhythms produce short circuited undamped oscillations in the energy conductor, the periodicity and wave lengths of which oscillations can be adjusted according to desire by altering the capacity 19 to a given wave length and therewith also to a given frequency. These currents may also be employed in this form directly as working current through the conductors II^1 and III. By inserting the condenser 20 a connection between these conductors may also be made, whereby harmonic oscillations of desired wave length are formed. By this means quite new effects as regards current distribution are obtained. The withdrawal of current can even take place without direct wire connection if, at a suitable point in the interior of the producing network (quite immaterially whether this has a diameter of 1 or 100 km.) a coil tuned to these wave lengths and of the desired capacity is firmly or movably mounted in the aerial conductor in such a way that its axial direction is in parallel with that of the collector coil. In this case a current is induced in the producing network, the size of which is dependent on the total capacity and resistance and also on the periodicity employed. A possibility is thereby afforded in future, of taking energy from the producer network by wireless means. As thereby in addition to atmospheric electricity also magnetic earth currents and the energy from the higher atmosphere (at least partially) may be simultaneously obtained, this last system for collecting the atmospheric energy is of particular importance for the future.

Of course everywhere instead of spark gaps suitable grid vacuum tubes may be employed as producers for undamped oscillations. The separate coils of the producer net-work with large diameters may be connected with one another through separate conductors all in parallel or all in series or in groups in series. By regulating the number of oscillations and also the extent of the voltage more or less large collector coils of this kind may be employed. The coils may also be divided spirally over the entire section. The coils may be carried out in annular form or also in triangular, quadrangular, hexagonal or octagonal form.

Of course wires may be carried from a suitable place to the centre or also laterally which serve the current waves as guides. This is necessary when the currents have to be conducted over mountains and valleys and so forth. In all these cases the current must be converted into a current of suitable periodicity.

As already hereinbefore mentioned separate collecting balloons may be directly metallically interconnected at equidistant stations distributed over the entire country or may be connected by interpolation of suitable condenser batteries by means of high voltage conductors. The static electricity is converted through a spark gap into dynamic energy of a high number of oscillations, and could then in such form, with a suitable arrangement of the connections, observing various measures of precaution, be employed as source of energy after separate or special regulation.

According to this invention in order to increase the collecting effect of the balloon in the aerial collector conductor or in the earth wire, radiating collectors are employed. These consist either of incandescent metal or oxide electrodes in the form of vacuum grid tubes, or electric arcs (mercury and the like electrodes) Nernst lamps, or finally flames of various kinds may be simply connected with the respective conductor.

It is well known that energy can be drawn off from a cathode consisting of an incandescent body opposite an anode charged with positive electricity (vacuum grid tube). Hitherto however, a cathode was always first directly placed opposite an anode, and secondly the system always consisted of a closed circuit.

Now if we dispense with the ordinary ideas in forming light or flame arcs in which a cathode must always stand directly opposite an anode, and if we place an incandescent cathode opposite an anode charged to a high potential or another body freely floating in the air, or regard the incandescent cathode only as a source of unipolar discharge (which represent group and point discharges in electro-static machines similar to unipolar discharges), it may be ascertained that incandescent cathodes and less perfectly all incandescent radiators, flames and the like admit of relatively large current densities and allow large quantities of electric energy to radiate into the open space in the form of electron streams as transmitters.

The object of this invention is as described below, if such incandescent oxide electrodes or other incandescent radiators or flames are not freely suspended in space but connected metallically with the earth so that they can be charged with negative terrestrial electricity, these radiators possess the property of absorbing the free positive electrical charges contained in the air space surrounding them (that is to say of collecting them and conducting them to earth). They can therefore, serve as collectors and have, in comparison to the action of the spikes, or points, a very large radius of action R; the effective capacity of these collectors is much greater than the geometrical capacity (R_0-) calculated in an electro-static sense.

Now as our earth is surrounded as is well

known, with an electro-static field and the difference of potential

$$\frac{\delta V}{\delta h}$$

of the earth field according to the latest investigations, is in summer about 60 to 100 volts and in winter 300 to 500 volts per metre of difference in height (δh), a simple calculation gives the result that when such a radiation collector or flame collector is arranged for example on the ground, and a second one is mounted vertically over it at a distance of 2,000 metres and both are connected by a conducting cable, there is a difference of potential in summer of about 2,000,000 volts and in winter even of 6,000,000 volts and more.

According to Stefan Boltzmann's law of radiation, the quantity of energy which an incandescent surface (temperature T) of 1 sq. cm. radiates in a unit of time into the open air (temperature T_o) is expressed by the following formula:

$$S=\sigma\ (T^4-T^4{}_0)\ \text{watt/sq. cm.}$$

and the universal radiation constant σ is according to the latest researches of Ferry (Annales de Chimie et de physique 17 page 267 (1909)) equal to 6.30×10^{-12} watt/sq. cm.

Now if an incandescent surface of 1 sq. cm. shows, as compared with the surrounding space a periodic fall of potential δV it radiates (independent of the current direction, that is to say of the sign) in accordance with the above formula, for example at a temperature of 3725° C. an energy of 1.6 kw. per sq. cm. per second. As for the radiation the same value can be calculated for the collection of energy, but reversed. Now as carbon electrodes at the temperature of the electric arc support on the current basis a current density up to from 60 to 65 amperes per sq. cm. no difficulties will result in this direction in employing radiating collectors as accumulators.

If the earth be regarded as a cosmically insulated condenser in the sense of geometrical electro-statics *x* there results from the geometric (compare Ewald Rasch, "das elektrische Bogenlicht" (The electric arc light) page 169) capacity of the earth according to Chwolson:

For negative charging 1.3×10^6 Coulomb

For negative potential $V=10\times10^8$ volts. From this there results however, $EJT\cong24.7\times10^{24}$ watt/Sec. Now if it is desired to make a theoretic short circuit through an earthed flame collector this would represent an electric total work of about 79,500 10^{10} kilowatt years. As the earth must be regarded as a rotating mechanism which is thermo-dynamically, electromagnetically, and also kinematically coupled with the sun and stars system by cosmic radiations and gravitation a diminution of the electric energy of the earth field is not to be feared. The energies which the incandescent collectors would withdraw from the earth field can only cause by the withdrawal of motor work a lowering of the earth temperature (temperature $T_E=300$) and reduce this to that of the world space ($T=O$) by using the entire energy. This is however not the case as the earth does not represent a cosmically entirely insulated system. On the contrary there is conveyed ~~to~~ the same according to the recent value corrected by Ferry for the solar constants through the radiation from the sun an energy of $18,500\times10^{10}$ kw. Accordingly any lowering of the earth temperature (T_E) without a simultaneous lowering of the sun's temperature (T_S) would contradict Stefan Boltzmann's law of radiation.

$$S=\sigma\,(T_S{}^4-T_E{}^4).$$

From this it must be concluded that if the earth temperature (T_E) sinks, the total radiation S absorbed by the earth increases, and further also that the secular speed of cooling of the earth is directly dependent on that of the sun and the other radiators cosmically coupled with the sun and is connected most closely with these.

The incandescent radiation collectors may, according to this invention, be employed for collecting atmospheric electricity if they (1) are charged with the negative earth electricity (that is to say when they are directly connected by means of a metallic conductor with the earth) and (2) if large capacities (metal surfaces) charged with electricity are mounted opposite them as positive poles in the air. This is regarded as the main feature of the present invention as without these inventive ideas it would not be possible to collect with an incandescent collector, sufficiently large quantities of the electrical charges contained in the atmosphere as technology requires; the radius of action of the flame collectors would also be too small, especially if it be considered that the very small surface density (energy density) (σ about$=2\times7\ .\ 10^9$ St. E. per sq. cm.) does not allow of large quantities of charge being absorbed from the atmosphere.

x) Calculated according to Poisson's calculation;

$\Delta V=-4\pi\delta$; as here the alteration of the potential or potential gradients only takes place in the direction of the normal, this calculation assumes the simple form

$$\delta=\frac{1}{4\pi}\times\frac{\delta^2V}{\delta n^2}$$

It has indeed already been proposed to employ flame collectors for collecting atmospheric electricity and it is known that

their collecting effect is substantially greater opposite the points. It is however, not known that the quantities of current which could hitherto be obtained are too small for technical purposes. According to my experiments the reason for this is to be found in the too small capacities of the collector conductor poles. If such flame or radiating collectors have no or only small positive surfaces, their radius of action for large technical purposes is too small. If the incandescent collectors be constantly kept in movement in the air they may collect more according to the speed of the movement, but this is again not capable of being carried out in practice.

By this invention the collector effect is considerably increased by a body charged with a positive potential and of the best possible capacity being also held floating (without direct earth connection) opposite such an incandescent collector which is held floating in the air at a desired height. If for example, a collecting balloon of sheet metal or of metalized balloon fabric be caused to mount to 300 up to 3,000 metres in the air and as positive pole it is brought opposite such a radiating collector connected by a conductor to earth, quite different results are obtained.

The metallic balloon shell (with a large surface) is charged to a high potential by the atmospheric electricity. This potential is greater the higher the collecting balloon is above the incandescent collector. The positive electricity acts concentratedly on the anode floating in the air as it is attracted through the radiation shock ionization, proceeding from the incandescent cathode. The consequence of this is that the radius of action of the incandescent cathode collector is considerably increased and thereby also the collecting effect of the collecting balloon surface. Further the large capacity of the anode floating in the air plays therefore an important part because it allows of the taking of large charges, and thereby a more uniform current is obtained even when there is a large consumption: this cannot be the case with small surfaces.

In the present case the metallic collecting balloon is a positive anode floating in the air and the end of the earth conductor of this balloon serves as positive pole surface opposite the surface of the radiating incandescent cathode, which in turn is charged with negative earth electricity being conductingly connected to earth.

The process may be carried out by two such contacts (negative incandescent cathode and anode end of a capacity floating in the air) a condenser and an inductive resistance being switched on in parallel, whereby simultaneously undamped oscillations may be formed.

In very large installations it is advisable to connect two such radiating collectors in series. Thus an arc light incandescent cathode may be placed below on the open ground and an incandescent cathode which is heated by special electro-magnetic currents be located high in the air. Of course for this the special vacuum Liebig tubes with or without grids may also be employed. An ordinary arc lamp with oxide electrodes may be introduced on the ground and the positive pole is not directly connected with the collecting balloon, but through the upper incandescent cathode or over a condenser. The method of connecting the incandescent cathode floating in the air may be seen in Figs. 29–33.

B is the air balloon, K a Cardan ring (connection with the hawser) C the balloon, L a good conducting cable, P a positive pole, N negative incandescent cathode, and E earth conductor.

Fig. 29 represents the simplest form of construction. If electric oscillations are produced below on the ground by means of a carbon arc lamp or in other suitable way a considerably greater electric resistance is opposed to that in the direct way by inserting an electrical inductive resistance 9. Consequently between P and N a voltage is formed, and as, over N and P only an inductionless ohmic resistance is present, a spark will spring over so long as the separate induction co-efficients and the like are correctly calculated. The consequence of this is that the oxide electrode (carbon or the like) is rendered incandescent and then shows as incandescent cathode an increased collecting effect. The positive poles must be substantially larger than the negative in order that they may not also become incandescent. As they are further connected with the large balloon area which has a large capacity and is charged at high voltage, an incandescent body which is held floating in the air and a positive pole which can collect large capacities is thereby obtained in the simplest way. The incandescent cathode is first caused to become incandescent by means of separate energy produced on the earth, and then maintained by the energy collected from the atmosphere.

Fig. 30 only shows the difference that instead of a round balloon a cigar shaped one (of metal or metalized fabric) may be employed and also a condenser 5 is inserted between the incandescent cathode and the earth conductor so that a short circuited oscillation circuit over P. N 5 and 9 is obtained. This has the advantage that quite small quantities of electricity cause the cathode to become incandescent and much larger cathode bodies may be rendered incandescent.

In this form of construction both the in-

candescent cathode and also the positive electrode may be enclosed in a vacuum chamber as may be seen in Fig. 32. A cable L is carried well insulated through the cover of a vessel and ends in a condenser disc 5. The cover is arched in order to keep off the rain. The vessel is entirely or partially made of magnetic metal and well insulated inside and outside. Opposite the disc 5 another disc 6 and on this again a metallic positive pole of the vacuum tube *g* with the incandescent cathode (oxide electrode) N is arranged. The negative electrode is on the one hand connected with the earth conductor E, and on the other hand with the inductive resistance 9 which is also connected with the cable L with the positive pole and wound round the vessel in coils. The action is exactly the same as that in Fig. 29 only instead of an open incandescent cathode one enclosed in vacuo is employed. As in such collectors only small bodies can be brought to incandescence in large installations a plurality of such vacuum tubes must be inserted in proximity to one another. According to the previous constructions Figs. 31 and 33 are quite self evident without further explanations.

Figs. 34–37 represent further diagrams of connections over radiating and flame collectors, and in fact, how they are to be arranged on the ground.

Fig. 34 shows an arc light collector with oxide electrodes for direct current and its connection; Fig. 35 a similar one for alternating current, Fig. 36 an incandescent collector with a Nernst lamp and Fig. 37 a similar one with a gas flame.

The positive pole 1 of the radiating collectors is always directly connected to the aerial collecting conductor A. In Fig. 34 this is further connected over the condenser battery 5 with a second positive electrode 3. The direct current dynamo *b* produces current which flows over between the electrodes 3 and 2 as an arc light. On the formation of an arc the negative incandescent electrode 2 absorbs electricity from the positive poles standing opposite it and highly charged with atmospheric electricity and conveys the same to the working circuit. The spark gap 7, inductive resistance 9 and induction coil 10 are like the ones previously described. The protective electromagnet S guards the installation against earth circuiting, the safety spark gap 8 from excess voltage or overcharging.

In Fig. 35 the connection is so far altered that the alternating current dynamo feeds the exciting coil 11 of the induction condenser. 12 is its negative and 13 its positive pole; if the coil 3 on the magnet core of the dynamo is correctly calculated and the periodicity of the alternating current is sufficiently high an arc light can be formed between the two poles 1 and 2. As the cathode 2 is connected with the negatively charged earth, and therefore always acts as a negative pole, a form of rectification of the alternating current produced by the dynamo 3 is obtained, the second half of the period is always suppressed. The working circuit may be carried out in the same way as in Fig. 34; the working spark gap 7 may however be dispensed with, and instead thereof between the points *n* and *m* a condenser 5 and an induction resistance 9 may be inserted from which the current is taken inductively.

Fig. 36 represents a form of construction similar to Fig. 34 only that here instead of an arc lamp a Nernst incandescent body is employed. The Nernst lamp is fed through the battery 3. The working section is connected with the negative pole, the safety spark gap with the + poles. The working spark gap 7 may also be dispensed with and the current for it taken at 12 over the oscillation circuit 5, 11 (shown in dotted lines).

Flame collectors (Fig. 37) may also be employed according to this invention. The wire network 1 is connected with the aerial collector conductor A and the burner with the earth. At the upper end of the latter, long points are provided which project into the flame. The positive electrode is connected with the negative over a condenser 5 and the induction coil 9 with the earth.

The novelty in this invention is firstly, the use of incandescent cathodes opposite positive poles which are connected with large metallic capacities as automatic collecting surfaces, (2) the connection of the incandescent cathodes with the earth whereby, in addition to the electricity conveyed to them from the battery or machine which causes the incandescing, also the negative charge of the earth potential is conveyed, and (3) the connection of the positive and negative poles of the radiating collectors over a condenser circuit alone or with the introduction of a suitable inductive resistance, whereby simultaneously an oscillatory oscillation circuit may be obtained. The collecting effect is by these methods quite considerably increased.

I declare that what I claim is:—

1. An electrical energy generating system, comprising a conducting surface for static charges, means to support same at a distance above the earth, a conductor leading to the earth level, a spark gap associated with said conductor to convert electrostatic charges into electromagnetic high frequency oscillations means to supply said electromagnetic energy to a net work, and a spark gap of greatly increased relative resistance in parallel therewith.

2. An electrical energy generating system

comprising a conductor, means to support same above the earth level, an inductance therein, a spark gap associated with said conductor, a second spark gap of much higher relative resistance in parallel therewith and an energy receiving circuit coupled with the spark gap of lesser resistance.

3. An electrical energy generating system comprising a collecting surface, means to support same above the earth level, a conductor connecting said collecting surface with the earth level, a choke in said conductor, an electromagnetic resistance converting electrostatic energy to electromagnetic energy, a safety higher resistance in parallel therewith and a net work coupled with the conversion resistance of lesser value.

4. An electrical energy generating system comprising electric conductors spaced above the earth to form electromagnetic oscillating circuits, conductors connecting to earth level, electrostatic to electromagnetic energy conversion means therein, a safety high electrostatic resistance in parallel therewith and means to alter the electromagnetic characteristic of the circuits.

5. An electrical energy generating system comprising in combination a static collecting surface arranged above the earth, conductors connecting to earth level, a pair of spark gaps in parallel of different electrostatic resistance, a utilization net work shunted across the spark gap of lesser resistance and an electromagnetic choke in said conductors.

6. An electrical energy generating system comprising an open circuit energy collecting aerial, a pair of sparking gaps in parallel of widely different resistance, connected thereto and a closed electric oscillation circuit in shunt across the gap of lesser resistance.

7. An electrical energy generating system comprising an open circuit energy collecting aerial, a pair of sparking gaps in parallel of widely different resistance connected thereto, a closed electric oscillation circuit in shunt across the gap of lesser resistance, a plurality of electrostatic collecting surfaces, means to connect said collecting surfaces in parallel in groups and means to connect said groups symmetrically with said aerial.

In witness whereof, I have hereunto signed my name this 30 day of Dec., 1920, in the presence of two subscribing witnesses.

HERMANN PLAUSON.

Witnesses:
H. F. Armstrong,
W. H. Beeston.

US 20150102676A1

(19) **United States**

(12) **Patent Application Publication**

(10) **Pub. No.: US 2015/0102676 A1**

Dinwiddie et al.

(43) **Pub. Date: Apr. 16, 2015**

(54) METHOD AND APPARATUS FOR EXTRACTING AND CONVEYING ELECTRICAL ENERGY FROM THE EARTH'S IONOSPHERE CAVITY

(71) Applicant: **Earth Energies, Inc.**, Johns Creek, GA (US)

(72) Inventors: **John Dinwiddie**, Cary, NC (US); **Terry L. Wright**, Suwanee, GA (US)

(21) Appl. No.: **14/509,846**

(22) Filed: **Oct. 8, 2014**

Related U.S. Application Data

(60) Provisional application No. 61/889,894, filed on Oct. 11, 2013.

Publication Classification

(51) **Int. Cl.**
H01F 38/14 (2006.01)

(52) **U.S. Cl.**
CPC ***H01F 38/14*** (2013.01); *H01F 2038/146* (2013.01)

(57) ABSTRACT

The system and apparatus of one or more embodiments of the present invention extracts, conditions, and conveys electric power from the earth ionosphere cavity through the integrated and collaborative operation of the system and apparatus consisting of a capacitively-coupled insulated elevated terminal (coupled capacitor upper plate), an evacuated spark gap, an integrated step-down transformer and resonant capacitor, and a ground terminal (coupled capacitor lower plate). The architecture governing exemplary embodiments of the system and apparatus of the present invention emulates the natural architecture governing the interaction of living trees with the electrical energy resident in the earth ionosphere cavity. The implementation of such exemplary embodiments of the present invention utilizes standard and customized components appropriate for their function within the system and apparatus.

The extracted electric power from the earth ionosphere cavity manifests in the form of broadband electromagnetic waves in the 0 to 200 Hz frequency range. Electric energy from these waves produce magnetic fields inside the integrated step-down transformer which are added together by the primary coil of the integrated step-down transformer, and delivered as 60 Hz 120/240 VAC to an electric load via the secondary coil of the integrated step-down transformer resonating at 60 Hz due to the influence of the integrated resonant capacitor.

The system and apparatus of exemplary embodiments of the present invention extracts, conditions, and conveys ionosphere cavity-resident electric power in alternating current and direct current realms.


10
E-field
.1 – 14 Hz AC ULF (Lightning Generated) 22
Tesla coil or other biasing will accelerate recharge rate (fast recharge)
Insulated
Instantaneous electrical current drawn to spark gap; inhibited from CUP as voltage rises on transformer side and extinguishes spark; CUP begins recharging
Capacitor Upper Plate (CUP) (Elevated Terminal) 12
Capacitor Reaches Threshold & Fires (Slow Discharge)
Develops High Voltage Charge Relative to Ground Voltage
Hoping to replace with solid state relay
Evacuated Spark Gap
Spark Triggers
Step-Down Transformers 28
Parallel Resonant Transformer Primary & Secondary Coils 16
Capacitor @ 60 Hz 18
Capacitor drain rate, spark gap extinguishing from voltage rise, integrated resonant transformer/capacitor, and biasing will be balanced to suit application
Electric Load (home)
*5 kW, 60 Hz, 120/240 VAC
Ultra High Instantaneous Current
14
Capacitor Lower Plate (CLP) (Ground Terminal)
Broadband ULF Current (pump)
Resonant Transformer & Capacitor Continue to Ring @ 60 Hz (16 & 18)
See Drawing 2 (44, 46, 48,58, 54)
Ground
Earth
See Drawing 2 (52)
*5 kW preferred embodiment
100 kW alternative embodiment
35,000 kW alternative embodiment
COPYRIGHT 2013
EARTH ENERGIES, INC.
PROPRIETARY & CONFIDENTIAL
EARTH ENERGIES, INC.


10
E-field
Insulated
.1 ~ 13 Hz AC ULF (Lightning Generated) 22
Tesla coil or other biasing will accelerate recharge rate (fast recharge)
Instantaneous electrical current drawn to spark gap; inhibited from CUP as voltage rises on transformer side and extinguishes spark; CUP begins recharging
Capacitor Upper Plate (CUP) (Elevated Terminal) 12
Capacitor Reaches Threshold & Fires (Slow Discharge)
Develops High Voltage Charge Relative to Ground Voltage
Hoping to replace with solid state relay
Evacuated Spark Gap
Spark Triggers
Step-Down Transformers 28
Parallel Resonant Transformer Primary & Secondary Coils 15
Capacitor @ 60 Hz 18
Capacitor drain rate, spark gap extinguishing from voltage rise, integrated resonant transformer/ capacitor, and biasing will be balanced to suit application
Electric Load (home)
*5 kW, 60 Hz, 120/240 VAC
Ultra High Instantaneous Current
Broadband ULF Current (pump)
16
Capacitor Lower Plate (CLP) (Ground Terminal)
Resonant Transformer & Capacitor Continue to Ring @ 60 Hz (16 & 18)
See Drawing 2 (44, 46, 48,58, 54)
Ground
Earth
See Drawing 2 (52)
*5 kW preferred embodiment
300 kW alternative embodiment
30,000 kW alternative embodiment
Copyright 2013
Earth Energies, Inc.
Proprietary & Confidential
Earth Energies, Inc.

FIG. 1


As Inserted
42 (4)
56
40
44
After Deployed
Bezel Anchor Slots (4)
50
Spool View Inside Bezel Blow-up
48
Bezel Ground Wire Escape Portals Holes with Wire end exposed (X)
54
46
Cut-away View (Installed)
Bezel Threads
58
Bezel External View
52
(Y)
Ground Terminal Optimizer Apparatus for Lower Coupled Capacitor Plate (Ground Terminal)
Copyright 2013
Earth Energies, Inc.
Proprietary & Confidential
Earth Energies, Inc.

FIG. 2

METHOD AND APPARATUS FOR EXTRACTING AND CONVEYING ELECTRICAL ENERGY FROM THE EARTH'S IONOSPHERE CAVITY

[0001] This application claims benefit of U.S. Provisional Application No. 61/889894, filed 11 Oct. 2013, titled, "Method and Apparatus for Extracting and Conveying Electrical Energy From the Earth's Ionosphere Cavity," the disclosure of which is incorporated herein by reference in its entirety.

BACKGROUND OF THE INVENTION

[0002] A portion of the disclosure of this patent document contains material which is subject to copyright protection. The copyright owner has no objection to the facsimile reproduction by any-one of the patent document or the patent disclosure, as it appears in the Patent and Trademark Office patent file or records, but otherwise reserves all copyright whatsoever.

[0003] The invention is an apparatus and methodology for extracting electric power manifesting as a broadband collection of electric field oscillations in the 0 to 200 Hz frequency range within the Earth's ionosphere cavity, through the use of an elevated biased hemispherical or other curved surface capacitor coupling the ionosphere cavity and Earth, and then conveying this electrical energy at the proper frequency, amperage, and voltage to existing homes and buildings where it is delivered for consumption over existing home or building wiring.

DESCRIPTION OF THE RELATED ART

[0004] The current state of the art in this field is focused on the bending of radio frequency waves in the Earth's ionosphere cavity for the purpose of distorting (through reflection) the resident cavity's magnetic field to physically direct the stimulating electrical energy to targeted locations within the Earth's ionosphere cavity and/or coordinates on the Earth's surface at specific energy levels appropriate to specific applications. The regenerative feedback was done by Sutton's active antenna.

[0005] Nikola Tesla attempted to transmit wireless power in the "natural medium"; however, Tesla bad no description of a device to receive natural oscillations as described in the present disclosure.

[0006] There is no known prior art in the field of electric energy extraction from the ionosphere cavity and conveyance to other terminals within the cavity for delivery of usable electric power.

SUMMARY OF THE INVENTION

[0007] In one exemplary embodiment of the present invention, a properly-scaled electric power extraction/conveyance apparatus is installed at a typical consumer residential home to deliver 60 Hz 120/240 VAC electric power, sufficient to convey the equivalent of 5 kW of continuous electricity, to the home's existing electric service entry component to power electrical appliances in the home over existing home electric wiring.

[0008] In another exemplary embodiment of the present invention, a properly-scaled electric power extraction/conveyance apparatus is installed at an appropriate location within an industrial park or neighborhood to deliver 60 Hz 120/240 V AC electric power, sufficient to convey the equivalent of 300 kW of continuous electricity, to the service entry components of industrial buildings or neighborhood homes to power electrical devices and appliances over existing building or home electric wiring.

[0009] Alternative exemplary embodiments of the present invention will extract direct current electric power from the Earth ionosphere cavity, generated by the earth's rotating magnetosphere, and convey in the form of conditioned direct current to direct current load sources, or convert to alternating current and convey in the form of conditioned alternating current to alternating current load sources.

BRIEF DESCRIPTION OF THE DRAWINGS

[0010] A disclosure embodiments of the present invention, is set forth more particularly in the remainder of the specification, which makes reference to the accompanying figures, in which:

[0011] FIG. **1** provides an example of an electric power extraction and conveyance apparatus for one residential-scale embodiment of the present invention. Certain additional example embodiments of the present invention utilize similar fundamental technologies, but differ in the scale (size) of the components and characteristics of the electricity conveyed for consumption; and

[0012] FIG. **2** is a schematic illustration of ground terminals for use with embodiments of the present invention.

DETAILED DESCRIPTION

[0013] Applicant has discovered that trees extract and use electric power from the Earth ionosphere cavity. The present invention emulates the architecture of electric power extraction and usage methodology inherent in the natural operation of living trees, but uses standard and customized components, common in the field, for its implementation. The natural electric power extraction and use of electric power by trees leverages the shape and physical composition of trees as instances of large electrical capacitors coupled to the ionosphere cavity. The canopy of trees (upper limbs and leaf structures) emulates the upper plates of a coupled capacitor, the trunks of trees emulate a combined dielectric and resonant transformer/capacitor, and the root systems of trees emulate ground terminals (lower coupled capacitor plates). The extraction of electric power from the ionosphere cavity by trees is in the form of ultra-low frequency broadband waves (oscillations) in the frequency range of 0.1 to 14 Hertz (ULF). Inherent tree physical composition and control structure (i.e., DNA/RNA) govern the use of the extracted electric power to accomplish tree growth, seasonal metabolic adjustments, and reproductive processes. Any excess extracted electric power by trees is returned to the ionosphere cavity. The present invention is an exemplary instance of this same natural architecture using standard and customized components that facilitate extraction and conveyance of ionosphere cavity-resident broadband electric power at useful scales sufficient to provide continuous electrical power for electrical devices used by people.

[0014] One preferred exemplary embodiment of the present invention is in the form shown in Drawing **1** above and will deliver continuous 60 Hz 120/240 V AC electric power to consumer residences (and other structures with similar electricity conditioning and consumption requirements) equivalent to electric power capacity of 5 kilowatts.

[0015] A secondary exemplary embodiment of the present invention is also in the form shown in FIG. **1**, appropriately scaled for larger electrical power demands and related conveyance capacity, and will deliver continuous 60 Hz 120/240 V AC electric power to larger buildings or electrical distribution facilities for commercial office parks with electric power capacity of 300 kilowatts.

[0016] A third exemplary embodiment of the present invention is also in the form shown in FIG. **1**, appropriately scaled for larger electrical power capacity, and will deliver continuous 60 Hz 120/240 VAC electric power to utility substations with electric power capacity of 30,000 kilowatts (or higher).

[0017] The following system, power sources, and component descriptions provide additional details of the present invention in various embodiments.

[0018] Earth's ionosphere cavity (**10**) is a reservoir of continuously-generated electrical energy (E-Field) in both direct current (DC) and alternating current (AC) realms. The DC electric energy is created by the constant rotation of the Earth's magnetosphere exposed to the solar wind. Earth's perpetually moving magnetic fields create the DC electric power in the ionosphere cavity E-Field per the equations in James Clerk Maxwell's fundamental theory of electromagnetism. AC electrical energy in the ionosphere cavity is generated from the persistent E-Field disturbances (i. e., oscillations) caused by lightning discharges. The present invention includes the direct extraction of AC electric power from the ionosphere cavity, and the direct extraction of DC electric power from the ionosphere cavity which is converted to AC electric power before conveyance. Optional operational configurations of the present invention will also enable conveyance of extracted DC electric power for potential scenarios where the conveyance of conditioned DC electricity is required.

[0019] Electric-field oscillations (**22**) are induced by lightning and encapsulated in the earth-ionosphere cavity, creating a continuous source of renewable electrical energy. The frequency of lightning occurrences in the ionosphere cavity averages thirty (30) strikes per second, with each strike representing approximately one (1) terawatt (TW) of instantaneous energy. Assuming an average energy dissipation rate for each lightning strike of fifteen (15) microseconds (μsec), i. e., the time involved for one (1) terawatt of instantaneous energy to dissipate to zero (0) energy, these lightning-induced electric field oscillations are sufficient to provide 4,500 times the entire electric energy consumption on planet Earth at the projected consumption rate for the year 2100 (55.3 TWh annually). Lightning-induced E-Field oscillations vary between 0.1 and 14 Hertz with wavelengths exceeding the practicality of an electromagnetic antenna for collecting the energy. The present invention utilizes capacitive coupling to overcome this obstacle.

[0020] An insulated upper capacitor plate (terminal) (12) elevated above the influence of the ground floor collects E-Field oscillations from the ionosphere cavity. This insulated elevated terminal, capacitively-coupled to the E-Field bounded by the earth-ionosphere cavity, is arranged in a surface of large radii of curvature, supporting maximum surface connection to the E-Field without leaking the high voltage charge applied to the elevated terminal. The capacitance and resistance of the elevated terminal are responsive to the reception of broadband electric-field frequencies in the 0 to 200 hertz range. The elevated terminal is subject to high voltage alternating current biasing used to collect electric-field oscillations generated by lightning impulses in the earth-ionosphere cavity.

[0021] An evacuated spark gap (**24**) connected to the elevated terminal (**12**) prevents electrical discharge occurring between the elevated terminal and the ionosphere cavity. As the high voltage alternating current approaches peak voltage the spark gap energizes and a large voltage is applied to the step-down transformer primary coil (**16**). The high voltage pumps high current from the ground terminal (**14**, **26**) converting the electric-field to a magnetic field within the transformer (**16**). The step-down transformer is connected to a 60 hertz resonant capacitor (**18**), the secondary side of the transformer resonating at 60 hertz will supply a 60 hertz 120/240 VAC power to the load. Filter circuits will condition the power. The evacuated spark gap function may be accomplished by solid state circuitry in the implementation of the present invention.

[0022] The resonant transformer (**16**) is integrated with a parallel resonant capacitor across the transformer where the integrated combination resonates at 60 hertz supplying power to the electricity consuming structure (home or business). Various step-down transformers (**28**) are utilized to condition the conveyed electricity to accommodate the requirements of the receiving station for various embodiments of the present invention.

[0023] Ground (**26**) is the source of electric current for the present invention. A ground terminal, connected to the soil, is arranged in a surface of large radii of curvature to permit instantaneous sourcing of high currents from earth ground without temperature and voltage rise inhibiting the ground terminal collection of current. The capacitance and resistance of the ground terminal to earth is minimized to promote on demand current sourcing. Drawing **2** illustrates an exemplary apparatus of the present invention that optimizes ground connection quality by maximizing the penetration extent and resulting surface area of the ground terminal's extension into the soil.

[0024] Step-down transformers (**28**) are scaled to transform the electrical current and voltage into structured and conditioned electricity that is compatible with the electric power needs of the load sources for various embodiments of the present invention.

[0025] A mechanical nut (**40**) solidly attached to shaft **44** to facilitate extension, when turned, of large gauge copper wire extrusions (**46**).

[0026] A downward pointed anchor flat shaft (**42**) attached to the bezel **50** via a T-slot in bezel.

[0027] A copper (or other highly-conductive metal) spool base (**44**) sourcing "X" independently attached large gauge pointed copper wires (**46**) of length "Y", where "X" is equal to the number of escape portals in bezel (**50**), and "Y" is the length determined to yield optimum surface area of wires of type **46** for high quality connectivity to soil. The spool can freely rotate inside the bezel (**48**) and emulates the primary root structure of a living tree.

[0028] Sharpened large gauge (reinforced) copper wires (**46**), quantity "X", of length "Y" emulating the root structure of living trees.

[0029] Threaded bezel (spool-housing sleeve) (**48**) with drilled escape portal holes with end of copper wires (**46**) protruding through holes ½ inch.

[0030] Bezel anchor slots (**50**) of twice the height of anchor flat shafts (**42**) and T-slotted to accommodate anchor flat shafts.

[0031] Extended pointed end (**52**) of inner spool base shaft.

[0032] Escape portals (**54**) in bezel to allow for large gauge copper wire (**46**) extension into soil.

[0033] Connector port (**56**) for connection to ground terminal (**14**) in Drawing **1**.

[0034] Bezel threads (**58**).

[0035] Various embodiments of the present invention will include one or more of the following characteristics in various combinations. These descriptions are provided for purposes of example. Not all of the following characteristics will be required for any given exemplary embodiment.

[0036] Characteristic 1, The form (shape), physical composition, size, insulation, location altitude, discharge capacitive threshold and discharge rate, and the strength of AC or DC biasing applied to the (CUP) upper coupled capacitor plate (**12**: elevated terminal) all form an integrated whole, the purpose of which is to extract and temporarily store DC or AC electric power from the Earth's ionosphere cavity (**10**) at high voltage, and to trigger the energizing of the evacuated spark gap (**24**).

[0037] Characteristic 2, The elevated terminal (**12**) is capacitively coupled to the E-Field (**10**) bounded by the earth ionosphere cavity, and arranged in a surface of large radii of curvature, supporting maximum surface connection to the E-Field without leaking the high voltage charge applied to the elevated terminal (**12**).

[0038] Characteristic 3, The capacitance and resistance of the elevated terminal (**12**) are responsive to the reception of broadband electric-field frequencies in the 0 to 200 hertz range.

[0039] Characteristic 4, The elevated terminal (**12**) is subject to high voltage alternating current biasing used to collect E-Field oscillations generated by lightning impulses in the earth-ionosphere cavity.

[0040] Characteristic 5, An alternative instantiation of elevated terminal (**12**) is subject to high voltage direct current biasing used to collect E-Field direct current generated by the Earth's rotating magnetosphere.

[0041] Characteristic 6, The evacuated spark gap (**24**) may be in the form of a cohesive physical spark ignition or an operational emulation of this function through solid state circuitry.

[0042] Characteristic 7, The evacuated spark gap (**24**) connected to the elevated terminal (**12**) prevents electrical discharge occurring between the elevated terminal and the ionosphere cavity.

[0043] Characteristic 8, The high voltage alternating current from the E-Field, induced into the elevated terminal (**12**), approaches peak voltage and causes the evacuated spark gap (**24**) to energize and a large voltage is applied to the step-down transformer primary coil (**16**).

[0044] Characteristic 9, The high voltage alternating current impulse from the elevated terminal (**12**), which causes the evacuated spark gap (**24**) to energize, manifests as alternating current on broadband frequencies between 0.1 and 200 Hz.

[0045] Characteristic 10, In an alternative instantiation of the elevated terminal (**12**) the stored high voltage direct current, which causes the evacuated spark gap (**24**) to energize, manifests as direct current on broadband frequencies between 0 and 200 Hz.

[0046] Characteristic 11, The high voltage applied to the step-down transformer primary coil (**16**) pumps high current from the ground terminal (**14**), converting the electric-field to a magnetic field within the transformer (**16**).

[0047] Characteristic 12, The high current pumped from the ground terminal (**14**), caused by high voltage applied to the step-down transformer primary coil (**16**), will attempt to normalize the field and extinguish the evacuated spark gap (**24**).

[0048] Characteristic 13, The transformer's (**16**) magnetic field expands in response to the high current electric-field inrush from the ground terminal (**14**).

[0049] Characteristic 14, The primary winding inside the step-down transformer (**16**) will add the energy from each broadband frequency together into a single magnetic field, where it will become a 60 Hz frequency at the secondary winding of the transformer (**16**).

[0050] Characteristic 15, The step-down transformer (**16**) is connected to a 60 Hertz resonant capacitor (**18**).

[0051] Characteristic 16, The secondary (coil) side of the step-down transformer (**16**), resonating at 60 hertz, will supply a 60 hertz 120/240 VAC power to the electric load.

[0052] Characteristic 17, Filter circuits within the step-down transformer will condition the power according to the electric power needs of the electric load.

[0053] Characteristic 18, Electric-field lines exist (within the Earth's ionosphere cavity) that are horizontal to the surface of the Earth and extend to heights above 30,000 feet, with voltage gradients typically 100 Volts per vertical meter.

[0054] Characteristic 19, Lightning impulses create global broadband oscillations in the Earth ionosphere cavity electric-field between 0.1 and 14 Hertz.

[0055] Characteristic 20, Rotation of the Earth's magnetosphere creates global electric field oscillations in the Earth ionosphere cavity that manifest as electromagnetic waves in the 0 to 200 Hertz frequency range.

[0056] Characteristic 21, Global broadband oscillations in the Earth ionosphere cavity electric-field can be used for wireless energy transmission without harm to people, plants, or trees.

[0057] Characteristic 22, A maximum quality ground connection is achieved by expanding the surface area of the ground connection (**48** and **44**) through extension of high-conductor large gauge copper wires (**46**) horizontally through bezel (**48**) escape portals (**54**) along depth of source spool (**44**) and bezel (**48**).

[0058] Characteristic 23, The technique described in Characteristic 22 effectively expands the diameter of the ground source spool (**44**) with regard to quality of ground connection.

[0059] Characteristic 24, Bezel threads (**58**) expand surface area of bezel (**48**) touching earth, enhancing ground connection quality.

[0060] Characteristic 25, Bezel threads (**58**) enhance ground connection quality of bezel (**48**), source spool (**44**), and high conductor large gauge copper wires (**46**) through rotational insertion and resulting friction hold v. other (direct drive) insertion methods which can result in corruption of ground hole integrity caused by imprecise angle and/or vibration during insertion.

[0061] While one or more embodiments of the present invention have been described above, it should be understood that any and all equivalent realizations of the present invention are included within the scope and spirit thereof. Thus, the embodiments presented herein are by way of example only

and are not intended as limitations of the present invention. Therefore, it is contemplated that any and all such embodiments are included in the present invention.

What is claimed is:

1. A power receiver for extracting electrical energy from the earth's electric field, said power receiver comprising:

a resonant transformer connected between a ground terminal disposed below the surface of the earth and an elevated terminal;

impulse generator for generating and applying a high voltage electrical impulse to a primary winding of the resonant transformer to induce current flow from the ground terminal through the primary winding of the transformer; and

a power conversion circuit connected to a secondary winding of the resonant transformer to convert electrical current flowing through the secondary winding to a desired form.

2. The power receiver of claim **1** wherein a resonant frequency of the resonant transformer is below 200 Hz.

3. The power receiver of claim **1** wherein the elevated terminal comprises an upper capacitive plate coupled to the earth's ionosphere cavity.

4. The power receiver of claim **3** wherein the impulse generator comprises:

the upper capacitive plate;

a pair of electrodes separated by a spark gap, said electrodes connected between the upper capacitive plate and the primary winding of the resonant transformer and configured to generate a spark when a voltage difference between the electrodes reaches a predetermined level.

5. The power receiver of claim **1** further comprising a lower capacitive plate coupled to the ground terminal.

6. The power receiver of claim **1** wherein the resonant transformer comprises a capacitor connected in parallel with a primary winding of the resonant transformer.

* * * * *

W. I. PENNOCK.

APPARATUS FOR COLLECTING ATMOSPHERIC ELECTRICITY.

APPLICATION FILED JUNE 26, 1907.

911,260. Patented Feb. 2, 1909.



Fig. 2.

Fig. 1.

6'
7
3
5
5
4
6'
6
7
7
14
14
4
8
13
1
12
11
11
11
12
12
14
14
14
12
12
9
12
14
16
15
15
10
17
17
2
14
17

WITNESSES

F. J. Hartman.

Alston B. Moulton

INVENTOR

Walter I. Pennock.

BY

ATTORNEY

UNITED STATES PATENT OFFICE.

WALTER I. PENNOCK, OF PHILADELPHIA, PENNSYLVANIA.

APPARATUS FOR COLLECTING ATMOSPHERIC ELECTRICITY.

No. 911,260. Specification of Letters Patent. Patented Feb. 2, 1909.

Application filed June 26, 1907. Serial No. 380,907.

To all whom it may concern:

Be it known that I, Walter I. Pennock, a citizen of the United States, residing at Philadelphia, in the county of Philadelphia and State of Pennsylvania, have invented certain new and useful Improvements in Apparatus for Collecting Atmospheric Electricity, of which the following is a specification.

My invention relates to a method of collecting electricity from a strata laden with electricity at high altitudes in the atmosphere, through the medium of a wire cable suspended from one or more balloons and in conveying this electricity to the earth's surface.

The object of my invention is to provide a conveyance of the electro motive force to be found in the upper strata of the atmosphere to the earth's surface; where it may be utilized for commercial and other purposes.

A further object of my invention is to provide a device or mechanism by which a suitable collector for the electrical energy in the upper strata of the earth's atmosphere may be elevated in the said strata and by which the said electric energy may be transmitted to and collected at the earth's surface, from which point it may be conducted to any place where it is desired to use the same.

A further object of my invention is to support and anchor said device in any desired position.

A further object of my invention is to provide an improved form of collector through which the energy of the said upper strata of the earth's atmosphere may be collected and transmitted for various purposes to the earth's surface.

Other objects of my invention will appear in the specification and claims below.

For a further full, clear and complete disclosure of my invention, reference may be had to the following description and accompanying drawings, in which like reference characters refer to corresponding parts.

Figure 1 is an elevational view of one form or embodiment of my invention and Fig. 2 is a detailed view of one form of my improved collector.

The passage of the electrical current to the earth under ordinary conditions is prevented by an obstruction afforded by the dense lower strata of the atmosphere, which is a bad conductor of electricity, as shown by the electrodes of an ordinary static machine. When the electrodes are placed close together, the atmosphere is seen to carry the current across from one electrode to another, but if placed far apart the current is obstructed by the intervening air. The dense lower strata of the atmosphere affords one of the best non-conductors of electricity, as shown in the conduction of the electric current by telegraph, or trolley wires on the earth's surface, where only a small quantity of the electric current escapes through the atmosphere; while rarefied atmosphere affords a good conducting media, as shown by the vacuum tube. The upper strata of the atmosphere being rare in proportion to the altitude, and being a good conductor of electricity while the lower strata of the atmosphere being dense and affording a non-conducting media for the electric current, thus causes an obstruction to the electric current, or power in its passage to the earth's surface from the electric strata of the atmosphere under ordinary conditions. When, however, the cumulus clouds of a thunder storm pass over the surface of the earth, these clouds being of very great height, the moisture in said clouds forms a better conductor of electricity than does the dry air, with the result that the electricity in the upper strata of the atmosphere breaks through the said cloud as a streak of lightning and in that form reaches even to the earth's surface, while the thin or shallow strata of clouds, observed in the so-called "settled rain" storm, do not extend upward to a sufficient height to form a conducting medium for the electricity from the electric strata to the earth's surface. For this reason there is usually no lightning during the said latter variety of rain storm.

By means of my invention, I have provided a mechanism for collecting the electrical energy or power created by nature and stored in the upper strata of rarefied air of the earth's atmosphere and have provided a conductor for said electric energy to the earth's surface.

Referring now to the drawings 1 indicates what may be called the lower limits or boundaries of the strata of electric energy above the surface 2 of the earth.

3 indicates a balloon which is elevated to a high altitude until it enters the said stra-

tum. The said balloon 3 carries a bar 4 of wood or any other suitable non-conducting material suspended by insulating links 5 or any other suitable form of insulation from the balloon 3. Upon either end of the said bar 4 I mount collectors, one form of which I have illustrated as spheres of coiled wire 6—6′ the outer ends 7 of which terminate in sharp points. The inner turns of the said spheres 6 and 6′ are wrapped around the wooden bar 4 and united as at 8 to a conductor of electric energy, preferably a large copper wire 9. This wire or conductor 9 extends to the earth's surface and may have its end suitably attached to an electric accumulator or other piece of electrical apparatus. I have illustrated one form of my invention in which the conductor 9 is connected to one pole of a storage battery 10 on the earth's surface.

The spiral spheres 6, 6′ are preferably provided with a polished metallic surface to form a good conductor of electricity and the material of said spheres should also be of such a character that it will not rust or corrode or tarnish. A polished copper wire or a copper wire plated with platinum or gold or a solid platinum or gold wire may be used for this purpose, inasmuch as these materials are least affected by moisture and the atmosphere. The said spheres or collectors may be made of smooth wire as shown in the sphere designated by the numeral 6 or of barbed wire, as is shown at 6′ and illustrated on a larger scale in Fig. 2 of the drawings. The latter form is preferable inasmuch as it provides a large number of points through which the electricity may flow to the wire from the surrounding air in the said upper strata of the earth's atmosphere.

In order that the supporting balloon 3 may be held in a relatively fixed position, it should be suitably anchored to the earth's surface. Inasmuch as the balloon 3 must be elevated to a very high position, the weight of the anchoring cables forms an important consideration, and if desired or necessary one or more supplemental balloons 11, 11, 11 may be attached to each of the anchoring cables 12, 12, 12 as illustrated in Fig. 1, to relieve the balloon 3 of such weight as would prevent it from ascending into the said electrical strata. In order that the electricity from the said upper strata of the earth's atmosphere may not be conducted down the anchoring cables 12, 12, 12, I attach them to the supporting balloon 3 and to the supplemental balloons 11 and to the earth's surface through suitable insulating devices 14.

In the form of my invention illustrated in Fig. 1, below the bar 4, I suspend a ring 13 of any suitable material from the balloon 3, and attach the anchoring cables 12 thereto by means of insulating rings 14, 14, 14. I may also provide additional insulating rings 14 between that portion of the anchoring cables 12 between the balloon 3 and the supplemental balloons 11, and also between that part of the cable 12 between the supplemental balloons 12 and the earth's surface. I may also provide, near the earth's surface and at the lower end of the anchoring cables 12, similar insulating links 14. While I have described links as forming a convenient form of insulating device for the purposes above set forth, I do not wish to be construed as being limited to the same, inasmuch as any suitable non-conducting connection may be used in place of the links 14.

The terminals 15, 15 of the storage battery 10 may be connected to any piece of electric apparatus which it is desired to run or operate and if desirable one of the poles of the battery is adapted to be connected by the switch 16 with the earth's surface. The lower ends of the anchoring cables 12 are securely anchored to the earth's surface as at 17.

With the apparatus arranged and connected in the manner illustrated in Fig. 1, the electric energy in the high strata of the earth's atmosphere passes to and through the conductive spiral spheres 6 or 6′ to the conductor 9 and is suitably stored or used at the earth's surface, while the balloons 11 support a part of the weight of the anchoring cables 12, and permit the balloon 3 to ascend as high as is possible, or necessary for it to enter the said electrical strata of the earth's atmosphere. By arranging the anchorage 17 of the cables 12 symmetrically or in any other position than in a straight line, the balloon 3 may be held in a substantially fixed position with relation to the earth.

While I have illustrated in the drawings and have described in the specification a form of apparatus in which my invention may be carried out, it is obvious that the drawings are more or less diagrammatic drawings, that is to say, that the proportions of the various parts are not necessarily those which would operate to the best advantage, inasmuch as certain portions have been shown as greatly enlarged in the drawings for the sake of clearness, and that it is likely that more than one supplemental balloon would be requird for each cable in order to support the weight of the same, and to relieve the supporting balloon 3 of such weight, as would prevent it from ascending into the high electrical strata of the earth's atmosphere, but such changes in form, proportion and arrangement I regard as being fully within the aim and scope of my invention, so long as such forms or modifications fall within the scope of the appended claims. It is also to be understood that the storage battery or accumulator which I have shown as being connected to my collector, is only a type of apparatus which can be operated by the current collected by the spheres 6, 6′ and transmitted to the earth through the wire 9, and when I use the word "accumulator", I mean any piece of useful apparatus which is operated by the current transmitted thereto through the wire or conductor 9.

Having thus described my invention, what I claim and desire to protect by Letters Patent of the United States is:

1. The combination with an electrical collector comprising a bar of non-conducting material, and an open spherical conductor carried by said bar, of means to support said collector in the high electrical strata of the earth's atmosphere.

2. The combination with a balloon, of an electrical collector supported thereby and insulated therefrom, comprising a bar of non-conducting material, and a conductor wound spirally around said bar.

3. The combination with an electrical collector comprising a non-conducting bar, and a conductive wire wound thereon to form an open substantially spherical body, and means to support said collector in the high electrical strata of the earth's atmosphere.

4. The combination with a balloon, of an electrical collector carried thereby and comprising a non-conducting bar, and a polished wire wound spirally thereon to form an open substantially spherical body.

5. The combination with an electrical collector comprising a non-conducting bar, and a wire wound spirally thereon to form an open substantially spherical body, said wire being provided with pointed conducting projections, and means to support said collector in the high electrical strata of the earth's atmosphere.

6. The combination with a balloon, of an electrical collector carried thereby comprising a non-conducting bar, and a conducting wire wound spirally thereon to form open substantially spherical bodies upon the opposite ends thereof.

7. The combination with a balloon, of an electrical collector carried thereby comprising a non-conducting bar, a conducting wire wound spirally thereon to form open substantially spherical bodies upon the opposite ends thereof, an electrical accumulator, and an electrical connection between the said collector and said accumulator.

8. The combination with a balloon, and means to anchor said balloon, of an electrical collector supported by said balloon and insulated therefrom, an electrical accumulator, and a conductor connecting said collector and said accumulator.

9. The combination of an electrical collector, means to support said collector at a high elevation from the earth's surface and within the electrical strata of the earth's atmosphere, an electrical accumulator at the earth's surface, an electrical connection between said collector and said accumulator, and means to insulate said supporting means from said collector and from the earth.

In testimony whereof, I have hereunto set my hand this 25th day of June, 1907.

WALTER I. PENNOCK.

Witnesses:
HUGH F. QUINN,
WM. G. GLENN.

Fig. 1


+
A
−
3
5
4
6
7
1
2
8
+ −
− +
9
10
11
12

Fig. 3



Fig. 2


3
9
4
1
2
F
5
E
1
11
12
E
2

Fig 4


3
5
4
1
2
F
9
E
E
2

Fig. 5.



Fig. 6.


7
6
F
8
E1
E2
12

Fig. 7.


+
−
14
13
2
4
F
1
3
8
6
5
−
+
16
15
7
E1
E2
17
17

Fig.8



Fig. 10



Fig. 9.



Fig. 11



Fig.12


+
3
4
7
8
9
10
5
1
2
11
12
E1
E2

Fig. 13.


L
20
1a
10
3
3a
2
9
1
2a
4
4a
11
5
12
E1
E2

Fig. 14


9a
10a
5
6
18
19
16
17
1
2
10
9
11
12
E1
E2

Fig. 16


1
2
9
8
18
19
17
16
7
3
4
5
11
12
E1
E2

Fig. 15


9
3
5
4
6
18
19
16
9x
1
2
9a
8
7
9b
10
10a
11
12
E1
E2

Fig. 17.


1
3
8
4
2
18
19
17
16
6
5
7
9
10
11
12
E1
E2

French Patent # 551,882
Apparatus for Capture of Electric Currents in the Atmosphere



Fig. 1

Fig. 2

French Patent # 565,395
Combined Apparatus for Capture of Atmospheric Electric Currents with Immediate Implementation


5
4
1
6
6
1
2
1
3
5
4

Fig. 2.

Fig. 1.

Fig. 3.


1
2
3
4
5
+
-
7
7
-
+
-
+
R²
R³
R³
R²
R
12
12
R⁴
R⁴
R'
R'
-
+
+
-
11
11
L
L
-
+

Fig. 4.



Fig. 5.



US 28793
Electric Apparatus

Abstract -- An aerostat for obtaining atmpspheric and terrestrial electricity...


Plate 1.
C
A
C
D
D
E
L
a
a
G
G
K
K
I
J
P
P
R
R
Q
Q


Plate 2
A
B
D B E
A
D
B
B
B'
B
B
E
G
G
G'
G
E
E
J
L
K
P
P
P
P
Q
Q


Plate 3.
Q
R
P
M
L
L
P
P
P
Q


Plate 4.
Fig. 2.
Fig. 1.
E'
B
B
G
E
D
G
G'
G'
G
G
I
I'
I''
I
I'''
I
I
Fig. 3.
Fig. 4.


Plate 5.
Fig. 1.
Fig. 2.
Fig. 3.
P
P
P
P
E
T


Plate 6.
Fig. 1.
Fig. 6.
Fig. 5.
Fig. 8.
O
O
P'
P'
P'
P'
S
P
Fig. 7.
Fig. 2.
Fig. 4.
N
P
P
P
A
A
P
T
T
T
A
A
K
T
N
Fig. 3.

Witnesses:
Arthur L. McIntire
Louis Bosworth.

N. PETERS. Photo-Lithographer, Washington, D. C.

Invent
H. G. Kion
by Munn & Co.
Attorneys.

US 126356
Improvement in Collecting Energy for Telegraph

Abstract -- A tower for the purpose of receiving and imparting natural electricity, so as to be in constant contact with the upper stratum of electricity which surrounds the earth, by tapping which a never-failing supply is formed when brought into contact with the earth.


Fig: 1.
Fig: 2.
Fig: 3.
Fig: 4.
Fig: 5.
Fig: 6.
Fig: 7.
WITNESSES.
INVENTOR.
W. H. Ward

US 129971
Telegraph Power

Abstract -- Utilizing natural electricity and establishing an electrical current without the aid of wires, batteries, or cables...

US 674427
Collecting Atmospheric Electricity

Abstract -- An appartus for colecting and driving or conducting atmospheric electricity which renders it practicable to obtain material quantities of teh same in serviceable form.

Fig:1.



Fig:3.

Fig: 2.





Fig: 4.

US 911260
Collecting Atmospheric Electricity

Abstract -- A method of colecting electricity from a strata laden with electricity at high altitudes in the atmoshere, through the medium of a wire cable suspended from one or more balloons ...


Fig. 1.
Fig. 2.
3
6'
7
5
4
6
14
8
13
1
11
12
9
10
2
16
15
17
WITNESSES
INVENTOR
Walter I. Pennock.
BY

US 1014719
Collecting Atmospheric Electricity

Abstract -- A method of colecting electricity from a strata laden with electricity at high altitudes in the atmoshere, through the medium of a wire cable suspended from one or more balloons ...



1
4
2
3
11
12
7
5
35
39
38
8
40



6
6
54
45
33
46
52
48
47
50
49
51

Fig. 1.



11
10
9
5
28
20
6
22
7
20
21
7
7

Fig. 3.



7
36
35
39
38
40

Fig. 2.



10
24
31
30
32
9
26
25
23
27
28
19
29
5
20
21
22

Fig. 4.

INVENTOR
Walter I. Pennock.

Fig. 5.


7
43
35
41
42
7
43
8

Fig. 6.


43
35
41
42
43

Fig. 7.


7
42
41
43
35
41
36
38
42
43
8

INVENTOR
Walter I. Pennock.

US 1540998
Conversion of Atmospheric Electric Energy

Abstract -- Method of obtaining atmospheric electricity by means of metallic ballon collectors...

Filed Jan. 13, 1921 12 Sheets-She

Fig. 1.


13
14
7
8
6
5
9
10
11
12

Fig. 2.


1
5
14
11
C_1
b_1
a_1
7
9
10
M
1
2
12
6
13
15

Fig. 3.


A
0
S
a
a
a
a
8
7
M
1
2
E.

Fig. 4.


S
5
1
8
7
M
2
6
E
E_1

Fig. 5.


A
S
5
8
7
7a
9
E
6

Fig. 6



Filed Jan. 13, 1921 12 Sheets-Sheet 2


A
S
1
M
2
E
7
7b
E1
8
E2

Fig. 7.


A
X
5
9
X1
X4
1
M
7
8
X5
2
X2
6
9a
X3
E1
E

Fig. 8.


A
S
X
8
X2
5
1
M
X1
9
2
X3
7
6
X4
E
E1

Fig. 9.


A
S
5
8
7
9
10
6
E

Fig. 10.


A
S
9
1
7
8
10
M
2
5
E

Fig. 11.


A
S
X
9
10
1
5
7
2
9a
10a
X1

Fig. 12.


A
S
5
X
9
1
4a
4
M
3
3a
8
X1
2
7
E

Fig. 13.


Fig. 14.
A
S
X
8
1
M
4
10
3a
5
9
3
2
4a
7
E


Fig. 15.
A
S
5
1
4
X
X1
3a
M
9
2
6
Z
3
4a
7
E


Fig. 16.
A
S
8
5
1
4
6
3a
M
9
3
2
4a
7


Fig. 17.
A
S
1
R
1a
M
2a
8
2
7
E1
E


Fig. 18.
A
S
1
6
M
9
2
7
8
E2
E1
E


Fig. 19.
A
N
1
8
R
1²
1¹
2
5
X
7
E
E2
E


Fig. 20.
Z
Z
A1
A2
A3
A4
A5
A10
Z
A9
n
n
A6
n
A8
A7
n
X
X1
X5
n
X9
n
A
n
X6
n
S
5
1
7
8
2
E

Inventor
Hermann Plauson
by Knight Bros
Attorneys


Z
A
5
C
x
D
5a
5b
D1
X
E
1
2
3
3a
4
4a
7
C2
C3
C1
D3
M
E1
E2
E3
5c
Inventor
Hermann Plauson

Fig. 21.

Fig. 22.

Fig. 23.


A
a
b
c
d
e
2
L
3a
3
3b
W
12
S1
18
20
19
17
16
13
21
22
23
24
11
S2
5
14
8
7
9
10
6
15
E1
E2
Invento
Hermann
by Knight

Fig. 24.

Fig. 25.


A1
A2
A3
A4
S2
22
21
27
S1
S3
25
R.
Sb
17
16
S4
13
18
20
Sa
Sd
12
Sc
19
26
28
24
23
J.
8
5
M
7
6
E1
E2

Inventor


I
S
S1
abcd
F1
A
g
F
K
B
B1
E1
E

Fig. 26.


2
1
3
5
4
19
9
II
22
6
II
F
f
21
I
10
23
S
E
11
S1
E1
20
F1
SII
17
EII.
12
13
Inventor

Fig. 27.


1
2
3
4
5
6
II
8
7
II
I
I
III
II¹
I¹
III
20
19
II¹
9
12
10
A
a
14
F
b
B
13
S₁
S
E₁
E

Fig. 28.


B
C
K
P
L
P
+
+
N
N
9
−
E

Fig. 29.


a
b
a
b
F
B
C
K
L
P
+
N
−
9
5
−
E

Fig. 30.

Inventor
Hermann Plauson
by
Knight Bros
Attorneys

Filed Jan. 13, 1921 12 Sheets-Sheet 11


z
B
C
K
P
L
+
+
–
–
9
10
11
–
E

Fig. 31.


z
B
C
K
L
5
6
+
9
G
N
–
E

Fig. 32.



Fig. 33.

Inventor
Hermann Plauson
by Knight Bros
attorneys


Filed Jan. 13, 1921 12 Sheets-Shee
Fig. 34
Fig. 35.
Fig. 36.
Fig. 37.
A
E
E1
S
1
2
3
5
6
7
8
9
10
11
12
13
m
n
+
−

GB 149,917

Improvements in & Relating to Radio Communication Systems

Abstract -- Radio transmission and reception through the use of living vegetable organisms such as trees, plants, and the like.

Fig 1


4
5
30
31
22
21
24
18
25
28
39
26
27
17
16
29
32
19
33
15
6
7
8
2
9
3
1
13
10
14
13
11
12

US 1826727
Radio Apparatus


Fig. 1.
Fig. 2.
Fig. 3.
Fig. 4.
1
2
3
4
5
6
7
8
9
10
11
31
32
33
34
35
36
37
38
INVENTOR
Chancy J. Britten
By Chappell & Earl
ATTORNEYs

US 2143437
Radiant Energy System

Abstract -- An apparatus for receiving and transmitting radiant energy within a wide range of frequencies without necessity of a source of local energy.


34
29
32
30
33
22
31
S
S
N
35
18
26
35
INPUT
17
20
21
23
24
OUTPUT
19
25
28
27

Fig. 2


159
162
160
162
161
163
163
12
10
4
14
15
13
4
11

Fig. 3


10
11
14
15
13

Fig. 4


INPUT
22
18
29
21
24
23
20
17
20
23
24
21
18
29
25

Fig. 9

Inventor

James Marion Fisher

By Murray & Zugelter

Attorney


151
149
150
143
148
139
142
49
48
56
143
141
140
144
133
136
147
138
134
29
136
148
137
145
146

Fig.5


155
132
154
152
153

Fig.7


152
131
153
132


156
155
132
157
158
152

Fig.8


116
114
117
29
34
107
114
115
106
113
103
118
99
104
102
108
112
119
101
109
120
111
128
125
100
110
29
129
106
121
123
124
127
128
130
125
126
48
56
49
48
56
49
105
122

Inventor

James Marion Fisher

US 2813242
Powering Electrical Devices with Energy Abstracted from the Atmosphere

Abstract -- A convenient and economical provision of power for the operation of electronic circuits and devices using transistors, and of other electrical devices hving modest power requirements.


RF POWER
35
36
37
41
46
43
40
42
44
TRANSISTOR OSCILLATOR
52
55
61
64
69
70
HIGH VOLTAGE LEVEL d-C POWER
LOW VOLTAGE LEVEL d-C POWER

FiG. 3


1
2
3
5
6
7
10
11
12
15
16
20
22
21
17
23
25
26
+1 v.
27
-2 v.
30
31

FIG. 1


35
36
37
41
46
43
40
42
44
+DC
45
LOAD
-DC

FIG. 2

INVENTOR
Lloyd R. Crump

US 3205381
Ionospheric Battery

Abstract -- A method and apparatus for tapping the enormous reservoir of energy existing in the ionosphere...


16
10
12
14
32
22
28
26
24
18
18
30
34
20
16
INVENTOR
Leslie G. Smith,
BY
ATTORNEYS

Fig. 1


10
12
40
36
22
38
32
28
26
30
40
34
14
40
36
38
40

Fig. 2

US 3273066
Apparatus for Detecting Changes in the Atmospheric Electric Field

Abstract -- A cloud detector and or an apparatus for sensing electrostatic conditions in the earth's atmosphere...


Fig. 1
14
30
24
22
20
12
Pressure Sensor
18
Block. Oscill.
Transmitter
16
26
28
34
32
Receiver -36-
Recorder -38-
Fig. 3
24
26
R1
R2
R3
C
66
64
64
62
62
Temperature Channel
Humidity Channel
INVENTOR:
Lothar H. Ruhnke
By Alan C. Rose
Attorney

US 3760257
EM Wave Energy Converter

Abstract -- Electromagnetic wave energy is converted into electric power with an array of mutually insulated electromagnetic wave absorber elements each responsive to an electric field component of the wave as it impinges thereon. Each element includes a portion tapered in the direction of wave propagation to provide a relatively wideband response spectrum. Each element includes an output for deriving a voltage replica of the electric field variations intercepted by it. Adjacent elements are positioned relative to each other so that an electric field subsists between adjacent elements in response to the impinging wave. The electric field results in a voltage difference between adjacent elements that is fed to a rectifier to derive d.c. output power. The element pairs may be arranged in a two-dimensional array to provide power conversion of randomly polarized electromagnetic waves, such as sunlight.

FIG. 1


D
23
11
Ē
24
R_L
25
21
16
13
15
Prop.
16
B
14
17
12
22
L

FIG. 2


135
135
135
34
34
3
31e
31d
31
31
31a
34
135
34
31
31b
33
31
31
31
31
32
31c
31
3


38
42
31a
P
N
36
37
41
31b
39
32
38
37
31c
42
P
N
36
35

FIG. 3

US 3931577
Radio Receiver Protection Arrangement

Abstract -- A receiver protection arrangement in which a voltage dependent on aerial voltage and a voltage dependent on aerial current are aggregated and applied to means responsive to a predetermined aggregate level to effectively short circuit the aerial lead. Additional means may be provided to dissipate energy in the input stage of a protected receiver to cause a reduced impedance to be reflected across the output of the protective arrangement.


3
L1
T1
C3
1
2
R3
R2
D1
Tr
R4
D3
C2
Q1
D2
C1
R1

Fig. 1.


R6
R3
R5
C5
Q2
D4
Q1
Q3
C4
R4
R7

Fig. 2.


1ST. AMPL.
5
2
D7
R9
D5
D6
C7
T2
R8
D8
D9
C6
4

Fig. 3.

US 4,628,299

Seismic Warning System Using RF Energy Monitor

Abstract -- The ambient broadband radio frequency field strength from broadcast stations is monitored (Figure 4) by periodic sampling (50, 52). A warning indication is provided if the field strength drops significantly. Drops in such field strength have been correlated empirically with the occurrence of seismic activity, usually several days later. Thus the indication serves as an early warning of an impending earthquake. In one preferred embodiment, a broadband, horizontal, very long monopole antenna (40) was connected to a rectifying and smoothing circuit (Figure 3) to provide a dc output proportional to the ambient rf field...



FIG 3

Your Support Maintains this Service --

BUY

The Rex Research Civilization Kit

... It's Your Best Bet & Investment in Sustainable Humanity on Earth ...
Ensure & Enhance Your Survival & Genome Transmission ...
Everything @ rexresearch.com on a Data DVD !

ORDER PAGE

H. C. VION.

Electric Apparatus.

No. 28,793.

Patented June 19, 1860.


Plate 1.
C
A
C
D
D
E
L
a
a
G
G
K
K
I
J
P
P
R
R
Q
Q


Plate 2.
A
A
B
D
B
E
D
B
B
B'
B
B
E
G
G
G'
G
E
I
J
L
K
P
P
P
P
Q
Q


Plate 3.
Q
R
P
M
L
L
P
P
P
Q


Plate 4.
E'
Fig. 2.
Fig. 1.
B
B
G
E
D
G
G'
I
I'
I''
I
I'''
I
G'
6
I
G
Fig. 3.
Fig. 4.


Plate 5.
Fig. 1.
Fig. 2.
Fig. 3.
O
O
O
O
P
P
P
P
T
E


Plate 6.
O
P'
P'
Fig. 1.
Fig. 6.
Fig. 5.
Fig. 8.
O
O
P'
P'
P'
P'
S
P
Fig. 7.
Fig. 2.
Fig. 4.
N
P
P
P
A
A
A
A
T
T
T
P
K
T
Fig. 3.
N

Witnesses:
Arthur L. McIntire
Lewis Bosworth

Inventor:
H. C. Vion
by Munn & Co.
Attorneys.

N. PETERS, Photo-Lithographer, Washington, D. C.

UNITED STATES PATENT OFFICE.

H. CHARLES VION, OF PARIS, FRANCE.

IMPROVED METHOD OF UTILIZING ATMOSPHERIC ELECTRICITY.

Specification forming part of Letters Patent No. **28,793**, dated June 19, 1860.

To all whom it may concern:

Be it known that I, HIPPOLYTE CHARLES VION, of Paris, in the Empire of France, engineer, have invented a new Mode of Obtaining Atmospheric Electricity and Terrestrial Electricity and its Industrial Applications; and I do hereby declare that the following is a full, clear, and exact description of the same, reference being had to the accompanying drawings, making part of this specification, in which—

Plate 1 represents a front elevation; Plate 2, a side elevation of an aerostat, in combination with certain other devices for obtaining atmospheric and terrestrial electricity; Plate 3, a plan of the device for obtaining terrestrial electricity; Plate 4, detached portions of the apparatus. Plate 5 shows a front view, and Plate 6 a vertical section and various details of the apparatus when applied in mountainous regions, the use of an aerostat being dispensed with.

The object of my invention is to form an electric pile of great power by using the positive electricity contained in the atmosphere, and the negative electricity contained in the earth, so as to make the electricity therein contained available for industrial purposes.

To enable others skilled in the art to make and use my invention, I will proceed to describe its construction and operation.

A is aerostat of a tubular form closed at both ends. It is made of suitable material, so as to be impervious to air. Its dimensions are such as to give it great ascensional power when filled with gas.

a a are valves in the surface of the aerostat, to be opened when the inflation of the aerostat should become too great.

A long india-rubber tube, I, communicates with the interior of the aerostat, being attached to the latter, near one end of its ends D, as seen in Plate 1, while the lower end of the tube I is attached to a gasometer, (not shown in the drawings.) The gasometer is to be fed with hydrogen gas, produced by the action of the pile itself, the negative wires of which (afterward to be described) enter a body of water at or near the base of the apparatus and decompose the water so as to produce the hydrogen gas. As the aerostat is supposed to be at a considerable height the tube I must be of corresponding length, and is constructed of a number of tubes, short wooden tubes I′ being inserted where the tubes I are joined, and a fastening-ring, I″, being slipped over each of the joints, as seen in Fig. 3 of Plate 4. At certain distances the tube I is fastened to the net-work of the positive wires (afterward to be described) in order to secure the tube against the action of the wind, and at each of these fastening-places a washer, I‴, is inserted in the tube in order that the tube shall not be compressed by the wire or other means employed to fasten it to the net-work of positive wires. (See Fig. 4, Plate 4.)

The aerostat is surrounded with a net-work of wires, one layer of the wires, C, being parallel with the axis of the aerostat and fastened to rings D at both ends of the aerostat, and the other layer of wires, B, extending partially around the aerostat at right angles to the wires C. One end of each of the wires B extends around an iron tube, E, some distance below the aerostat and meets the other end of it between the tube E and the aerostat. The two ends are fastened together by a ligature, B′. (See Fig. 1, Plate 4.) Each end of the tube E terminates into a ball, *e*. The wires B are fastened to the surface of the tube E by means of a helical wire, F, wound around the tube and across the wires B, as seen in Fig. 1, Plate 4. The upper ends of long vertical wires G are also wound around cylinder E, each wire G between two of the wires B, and the ends secured by a ligature, G′, as seen in Fig. 1, Plate 4. The helical wire F is also wound across the wires G, so as to keep them in their places on tube E.

The vertical wires G, which are to be the conductors of the positive electricity of the atmosphere, must be of a length proportionate to the desired efficacy of the electric pile, and the size and ascensional power of the aerostat must, of course, be adequate to sustain the weight of and keep suspended the wires G, (a weight still further increased by the horizontal cross-wires H, with which the vertical wires G are interlaced, in order to form a net-work not liable to be deranged by the action of the winds or similar influences.) The two outside wires, G, are stronger than the rest of them, and their lower ends are fastened to dynamometers of any suitable construction. These dynamometers are attached to the ends or a massive iron cylinder, J, and they serve to indicate the tension in the outside wires, G, and the corresponding ascensional power of the aerostat. According to the reading of these dynamometers the aerostat has to be supplied (through tube I) with more or less gas. The lower end of each of the wires G is wound around the cylinder J, and secured by ligatures similar to those above described. The wires G are all insulated (by a coating of gutta-percha or similar substance,) except where they are in contact with tube E and with cylinder J, and a similar insulating coating is laid on cylinder J, after the lower ends of the wires G have been fastened to it.

Another cylinder, K, similar to J, is placed at some distance from and parallel to cylinder J. It is connected with cylinder J by wires L, wound around both cylinders and interlaced with cross-wires M. The wire-work L M and cylinders are insulated (in a manner already described) against outside influences, so that the only electric communication between the two cylinders will be through the wires L. The two cylinders are placed upon insulated columns P. The cylinder K may be used as a substitute for cylinder J, and vice versa, whenever repairs become necessary. Insulated branch wire or wires are attached to the cylinders J K and wires L, so as to conduct the positive electricity obtained from the atmosphere by means of the above-described apparatus to wherever it is desired for industrial purposes. The insulated wires Q (interlaced with cross-wires R) are placed on the ground underneath and parallel to the positive wires L. Both ends of each of the wires Q are sunk into the earth or submerged in water, and fastened to a metallic plate coated with a metal not subject to oxidation. These wires Q are the conductors for the negative electricity of the earth, and a branch wire or wires attached to the wires Q serve to transmit the negative terrestrial electricity to wherever it is wanted for industrial or other purposes.

By uniting to the ends of the positive and the negative branch wire or wires a powerful electric current will be obtained, one pole of which is the atmosphere and the other the earth, and may be applied to any suitable useful purpose.

I will now proceed to describe the modification of the above-described apparatus when to be applied in mountainous countries.

P represents the positive electric copper or other metal wires coated over with an insulating substance. The upper ends of each of the positive wires is soldered to a prompter, O, at P′, Figs. 1, 5, and 6, Plate 6. The lower portion of each of the positive-wires is secured to an insulator, T, Fig. 2, Sheet 6. The positive wires are held above the ground by joints A, Figs. 3 and 4, Sheet 6, projecting from the soil at suitable distances from each other. The wires P are intended to follow the inequalities of the ground on which they are laid.

The prompters O, Figs. 5 and 6, Sheet 6, are iron rods sharpened to a point and silvered or coppered at their upper ends. The lower part of the prompter is fastened into a pole, S, covered with tar, which isolates the prompter and holds it in a firm position. A large metallic plate may be soldered to each prompter, as shown in Fig. 6. The positive wires may be soldered to the rod of each prompter or to the plate which is fastened thereto.

One or more branch lines, E, are soldered up to the positive wires to transmit the positive atmospheric electricity for which the wires P are the conductors to any desirable point.

N are negative iron or other metal conductors coated with an insulating substance. The upper ends of these wires rest on the ground near the positive insulators. The lower ends of these wires are soldered to a metallic plate or plates, V, Fig. 7, Plate 6, coated with a metal not subject to oxidation. The negative wires are sunk into the ground at very great depth or into wells, rivers, or into the sea. The negative electric branch wires are attached to the negative conductors N in the same manner as the positive branch wires are to the positive conductors. The branch wires and the soldering are coated over with an insulating substance. They are intended to carry the negative terrestial electricity to any desired point.

What I claim as my invention, and desire to secure by Letters Patent, is—

1. The peculiar arrangement of means herein specified, whereby I am enabled to use the positive electricity contained in the atmosphere and the negative electricity contained in the earth, and thus form an electric pile of considerable power and make the electricity therein contained available for industrial purposes, as set forth.

2. The combination of an aerostat and vertical wire-work with a tube, I, for admitting gas into the aerostat, in the manner and for the purposes above set forth.

CHARLES VION.

Witnesses:
HARRY W. SPENCER,
A. GUION, Jr.

W. I. PENNOCK.

APPARATUS FOR COLLECTING ELECTRICAL ENERGY.

APPLICATION FILED JAN. 4, 1911.

1,014,719. Patented Jan. 16, 1912.

2 SHEETS—SHEET 1.


1
4
2
11
12
3
1
4
2
11
12
3
5
7
35
38
8
40
39
6
6


54
45
53
46
52
48
47
50
49
51

Fig. 1.


11
10
9
5
28
20
6
7
20
22
21
7

Fig. 3.


7
36
35
39
38
40

Fig. 2.


10
31
30
32
24
9
26
25
23
29
27
28
19
5
20
21
22

Fig. 4.

INVENTOR
Walter I. Pennock.

WITNESSES
Elizabeth L. Smith
J. Stuart Freeman.

BY

ATTORNEY

W. I. PENNOCK.

APPARATUS FOR COLLECTING ELECTRICAL ENERGY.

APPLICATION FILED JAN. 4, 1911.

1,014,719. Patented Jan. 16, 1912.

2 SHEETS—SHEET 2.

Fig. 5.


7
43
35
41
42
7
43
8

Fig. 6.


43
35
41
42
43

Fig. 7.


7
42
41
43
35
36
41
38
42
43
8

WITNESSES

Elizabeth L. Smith,

J. Stuart Freeman.

INVENTOR

Walter I. Pennock.

BY

ATTORNEY

UNITED STATES PATENT OFFICE.

WALTER I. PENNOCK, OF PHILADELPHIA, PENNSYLVANIA.

APPARATUS FOR COLLECTING ELECTRICAL ENERGY.

1,014,719. Specification of Letters Patent. Patented Jan. 16, 1912.

Application filed January 4, 1911. Serial No. 600,777.

To all whom it may concern:

Be it known that I, WALTER I. PENNOCK, a citizen of the United States, residing at Philadelphia, county of Philadelphia, and State of Pennsylvania, have invented certain new and useful Improvements in Apparatus for Collecting Electrical Energy, of which the following is a full, clear, and exact disclosure.

The present invention relates to an improved means for collecting the charges of electricity from the upper atmosphere and more particularly to that form which consists in one or more captive balloons from which is suspended a suitable form of metallic conductor.

The principal objects of the device are: to provide a collector for atmospheric and static electricity, which when in operative position will present a large surface to currents of air, but which will offer comparatively little resistance thereto, to provide a collector of such material and construction as will be more efficient in its operation than any previously constructed for a similar purpose, to provide a means for maintaining such a collector suspended in the air and at right angles to opposing currents thereof, and to provide a suitable anchorage for holding said means captive.

With these principal objects in view, the present invention consists in further advantages which are brought out in the following specification and accompanying drawings, in both of which like numerals refer to like parts, and in which drawings—

Figure 1 is a perspective view of the complete device in operative position, Fig. 2 is an enlarged detail view of the wire mesh and the manner in which it is attached to the supporting balloons, Fig. 3 is a detail of the manner of securing the collector-supporting and anchor cables to the balloons, Fig. 4 is an enlarged cross section of the swivel connection shown in Fig. 3, Fig. 5 is top plan view of the reinforcing braces on the screen, Fig. 6 is an elevation of the same and Fig. 7 is an end view of the structure shown in Figs. 5 and 6.

Referring to the drawings, in Fig. 1 thereof, a plurality of balloons 1 of any suitable type is shown, each of which embodies hollow metallic elongated gas tanks 2, extending from the rear of which are single, rigidly affixed rudders 3, while on the sides of the tanks are secured stationary lifting planes 4.

To the bottom and slightly to the rear of the center of the tanks 2 is secured a suitable swivel 5, by which the anchor ropes 6 and the suspension ropes 7 for the metallic conductor 8 are secured to the balloons 1. A suitable form of swivel joint is illustrated in Figs. 3 and 4, but any type can be used that embodies the essential features shown therein.

The swivel joint illustrated consists in the base plate 9 having a looped portion 10 integral therewith and projecting from the upper face thereof. Secured to the loop 10 is a set of three light electrically conductive supporting ropes or cables 11 which extend upwardly and are secured at intervals to the bottom 12 of the balloon above.

The lower or revoluble member 19 of the swivel joint preferably comprises three upwardly directed curved arms, 20, 21, and 22, respectively, forming at their junction a T-shape as shown, said arms at their upper extremities being integral with the plate 23. The member 19 is revoluble below and concentric with the plate 9, and the two members are lightened in weight by opposed concentric grooves as shown at 24. Contact between said members is made through the roller bearings 25, which are carried in the opposed concentric grooves 26 and 27 of the respective upper and lower plates. Furthermore, said plates are maintained in coöperative relation with each other by means of a bolt 28 passing through centrally drilled holes 29 and 30 in the respective lower and upper plates, the drilled hole 30 opening upwardly into an enlarged recess 31, in which is sunken the nut 32 on the bolt 28. Two of the arms 20 and 22 of the lower revoluble member 19 extend in diametrical alinement, while from the central point thereof extends the third arm 21 at right angles thereto, and upward to the plate 23.

Suspended below the plurality of balloons is a hollow rod 35, of any suitable material, connected at regular intervals such as at points 36, by metallic ropes 7, to the alined arms 20 and 22 of the swivel joint 5. Below and parallel to the rod 35 is a similar but smaller rod 38 suspended therefrom by means of suitable couplings 39. From the rod 38 hangs a wire mesh 40 of any suitable form, such as can be extended over a considerable area and which will offer comparatively little resistance to the passage of air therethrough. The metal in such a screen is preferably rough, sharp or jagged and a convenient form embodying these characteristics is expanded sheet metal such as is used for lathing and for reinforcing concrete construction. Instead of the single hollow rod 35 alone, applicant contemplates the use of reinforcing means to prevent the buckling of the rod in a stiff wind, such, for instance, as the arrangement of wire bracing shown in Figs. 5, 6 and 7 in which cross rods 41, secured to the rod 35 at the center thereof are attached to the ends thereof by means of stretched wires 42. Between the rods, 41 and the ends of the rod 35 are secured sets of cross rods 43 which support the wires 42 and strengthen the rod 35 at as many points as they may be placed.

For the purpose of maintaining the balloons and apparatus suspended therefrom captive, the light metallic cables 6 terminating downwardly in insulators 45 are employed. These insulators in turn are connected by means of short sections of rope 46 to the eye 47 of a suitable swivel 48, embedded in the anchorage 49.

When the balloons with the metallic screen suspended therefrom are allowed to rise into one of the higher altitudes, the entire apparatus being of metallic construction and uninsulated will become energized by contact with the surrounding natural charges of electricity. From the above description it is evident then that, while the screen 8, on account of its great extent, will be the greatest collecting agent, it will be seen that the balloons themselves and the suspending wires will also coöperate as one large collector, since no parts of which are insulated from any of the neighboring parts thereof. Consequently, when the apparatus described has reached an altitude or strata of the atmosphere abounding in static charges of electricity, an amount of the said charges proportionate to the surface area of the metal exposed will collect upon the apparatus as a whole and will be conducted downwardly toward the earth by means of the various anchor ropes 6, but will not pass into the ground on account of the interposition of the insulators 45.

To use the electrical charges thus acquired, a plurality of Leyden jars 50, or other suitable collectors are supported above the surface of the earth and insulated therefrom by any suitable means as represented by the blocks 51. Either the inner or outer conducting surfaces of the jars may be connected together and energized by the accumulated charge. In the present instance, the inner surfaces of the accumulators are shown to be connected, and the connecting means 52 is in turn connected to the ropes 6 by means of wires 53. These wires are secured to the ropes mentioned by means of suitable binding posts 54.

In the device described the anchor ropes 6 are of substantially the same length, and when the apparatus is raised to the desired altitude and is being blown by the currents of air, the balloons are turned by means of the vanes 3 to parallel relation with each other, and furthermore, from the manner in which the device is held captive and the collecting net 40 is suspended from the balloons, it is obvious that said net will at all times readily swing into a plane substantially perpendicular to any current of air acting upon the balloons above. The purpose of the swivel joint shown in Figs. 3 and 4 is principally for allowing the balloons to readily aline themselves with any new direction of the wind before the apparatus, including the suspended screen, can swing about the swivel 48, and said joint will also prevent the twisting of the ropes 7, when any rapid shifting of the air currents may occur.

While applicant has shown a set of Leyden jars as the accumulators in the accompanying drawings, it is obvious that any other suitable form may be used, and furthermore, that although not illustrated, any suitable apparatus may be run thereby, such as for instance, wireless telegraphic instruments.

Furthermore, although but one embodiment of the invention has been described, it is to be understood that various modifications may be made therein, and in fact several are contemplated by applicant that are of such structure as fall well within the scope of the appended claim.

Having thus described my invention, what I claim and desire to protect by Letters Patent of the United States, is:

A collector for charges of electricity, comprising a plurality of supporting means, a metallic gauze sustained thereby to lie in a plane and substantially equidistant from each of said supporting means, anchoring means emanating from a common point to each of said supporting means, means operative to maintain said supporting means in their normal positions, and means between each of said supporting means and said gauze to permit each of said supporting means to readily and independently aline itself to accord with any alteration in the direction of opposing air currents.

In witness whereof I have hereunto set my hand this 28 day of December, A. D. 1910.

WALTER I. PENNOCK.

Witnesses:
Mildred S. Temple,
E. Eugenia Pennock.

Aug. 2, 1932. H. L. BUMBAUGH 1,869,661

LIGHTNING PROTECTION SYSTEM AND METHOD

Filed July 26, 1927 2 Sheets-Sheet 1

Fig. 1.


33
27
40
40
40
33
27
40
2
2
25
11
23
22
20
19
18
21

Fig. 2.


32
33
27
40
12
14
13
16
25
11
15

Fig. 3.


15
16
40
16
15
40
12
11
12
11

Fig. 5.





Fig. 4.

Inventor

Harold L. Bumbaugh

By Lyon & Lyon

Attorneys

Aug. 2, 1932. H. L. BUMBAUGH 1,869,661

LIGHTNING PROTECTION SYSTEM AND METHOD

Filed July 26, 1927 2 Sheets-Sheet 2


33
32
27
30
31
29
28
28
26
38
35
36
34
37
24
23
39
25
22
40

Fig. 6.


24
33
32
31
38
29
36
37
23
35
22
34
25

Fig. 7.


33
32
31
34
24
29
38
23
37
36
41
20
20
21
19
18
35
22
25
21
17

Fig. 8.

Inventor

Harold L. Bumbaugh

By Lyon & Lyon

Attorneys

Patented Aug. 2, 1932

1,869,661

UNITED STATES PATENT OFFICE

HAROLD L. BUMBAUGH, OF SAN FRANCISCO, CALIFORNIA, ASSIGNOR TO STANDARD OIL COMPANY OF CALIFORNIA, OF SAN FRANCISCO, CALIFORNIA, A CORPORATION OF DELAWARE

LIGHTNING PROTECTION SYSTEM AND METHOD

Application filed July 26, 1927. Serial No. 208,536.

This invention relates to lightning protection systems and, also, to lightning protection methods.

In general, an object of the invention is to protect particular areas or structures against being struck by lightning.

More particularly, an object of the invention is to provide a system and method whereby the point or points for receiving the lightning strokes are predetermined.

Another object is to make provision for taking care of the consequential secondary discharges.

Heretofore, it has been a practice for protecting certain areas and structures from lightning strokes, to provide towers, masts and network, singly or enclosing said areas or structures, thus providing a multiplicity of points in the expectation that one or more of said points would receive the lightning stroke in event of the stroke occurring in the vicinity of the area or structure thus protected, thus diverting the lightning stroke from said area or structure. Protection against lightning might possibly be afforded in this manner if it were practicable to erect towers in sufficient number and of sufficient height or to provide metallic enclosures of a type that would insure immunity for the enclosed area or structure against lightning strokes. This, however, is not, generally, feasible economically. Accordingly, another object of the present invention is to afford adequate protection in an economical and practicable manner.

In order to more clearly understand the invention, let it be assumed that there is a cloud sufficiently charged with electricity at a considerable height above the earth, imposing by its influence, an equal charge of electricity of opposite sign on the earth. The result will be a potential difference between the cloud and the earth, the presence of which is manifested in the form of an electrostatic atmospheric potential gradient. As a further result, there will be tendency toward equalization of this potential gradient through the medium of whatever conduction may exist across or through the dielectric or dielectrics separating the charged bodies which, in this instance, are the cloud and the earth.

As the cloud approaches the earth, or as the charge on the cloud increases, the potential gradient becomes steeper and the air intervening between the cloud and the earth becomes subjected to a greater electrostatic stress. The greater this stress the greater will be the tendency of the dielectric to break down and become to a greater or less degree conductive of electric current. In this case, conductivity is primarily due to ionization, probably the ionization of collision, when electrons are pulled from the atoms of the dielectric by the more or less intense strain exerted by the potential gradient. The theoretical explanation of what occurs implies a breaking up of the atoms of the dielectric into electrons and protons which, under the influence of the potential gradient, are drawn, respectively, toward the positively charged body and the negatively charged body.

Other factors being equal, the conduction across a stratum of air will be in direct ratio to the degree of ionization which, in turn, is largely dependent on the potential gradient. Therefore, when two electrically charged bodies of opposite sign exist and there is a tendency toward equalization of potential between them, under such conditions a reduction in the potential difference may take the form of a visible phenomena, when the so-termed ionization potential of the dielectric has been reached. This will be visibly indicated by the formation of corona and under slightly higher potentials, by the formation of streamers, these manifestations generally preceding a more or less complete breakdown of the dielectric, particularly under conditions of increasing or extremely high potential gradient. Under these conditions it is probable that the ionization of collision is supplemented by ionization due to increase in temperature, since the increased molecular activity causes more electrons to give up their energy in the form of heat which results from collision. The effects are undoubtedly cumulative when the potential gradient is sufficiently high.

The rate at which equalization of potential occurs between an electrically charged cloud and the earth depends on the steepness of the potential gradient and the character of the dielectric and, under a sufficiently steep potential gradient, every projecting point on the surface of the earth, such as blades of grass and leaves on the trees, in the vicinity, will have an electric discharge ranging from an infinitesimal amount to an amount that results in visible corona and streamers. If the cloud attains sufficient electric charge and has sufficient capacity, to make it a potential source of lightning strokes, some path of ionization or breakdown of the dielectric may occur between the cloud and the earth and along this highly conducting path, the current flow which constitutes a lightning stroke will take place. The earth end of this path of ionization will be at some point which, under the existing potential gradient, has a greater discharge, or ionizing influence, than any other nearby point. This is because the power of ionization is the result of the introduction into the space under stress of a number of free electrons (created through ionization) with a consequent tendency to render that particular portion of the space relatively conducting by moving under the influence of the potential gradient and tending to leave a more or less ionized path, and, therefore, one that is more or less conducting of electric current. It follows from this that the ground point first furnishing ionization or electrons in sufficient degree, will be the point from which the path of ionization will start and, if the path of ionization be then completed to the charged cloud, said point will be the one where lightning will strike the earth, all other conditions being the same.

In nature, there are so many variables which influence the behavior and occurrence of lightning strokes that it is manifestly impossible to predetermine and locate every danger point with a view toward avoiding the hazard at said point and in the area adjacent to said point. It is an object of the present invention to artificially create, at will, and at any desired point, an ionized area corresponding to the ionized area at the earth end or point of the lightning stroke so that, by locating this point removed from a particular structure or area, the same will be protected or rendered immune against lightning discharges, any discharge in that particular area being taken by the specially prepared point.

The potential of metallic objects or bodies on the earth is that of the earth and, under the influence of electrical disturbances, a considerable electric charge may be carried to a point considerably above the surface of the earth. As long as the potential gradient remains unchanged, this elevated charge will be in equilibrium and, accordingly, no hazard is present from such conditions; but, in the event of a sudden change in the potential gradient following a lightning discharge, there is a tremendous surge of current from the metallic objects or bodies to the earth. This surge is composed of the elevated charges, the potential of which, when the gradient is reduced, is above that of the earth. If an unbroken path, such as is formed by a metallic conductor of ample capacity, exists from the elevated charges to the earth, the charges, suddenly released, are carried harmlessly to the earth along said path and the electrical equilibrium is again restored. However, any break in the conducting path or lack of capacity of the metallic conductor to properly take care of the current flow will result in a bridging of the gap, resulting from the break in the conductor, by the electric current and the consequent formation of an arc across said gap, thus producing a serious fire hazard.

These electric charges, which take up their position under the stress of a potential gradient are known as bound charges and, when released, following lightning strokes, constitute secondary electric surges which are particularly hazardous in the presence of inflammable liquids and gases. The roof of a reservoir or tank used for the storage of petroleum is a typical example of hazard due to secondary electric discharges or surges. Accordingly, it is an object of this invention to provide a path of electric current conductive material of a capacity to handle the maximum surges to the earth and to make this path a part of the structure to be protected.

In the system I at present propose to employ, there is an electric device for producing corona, brush, streamer, or other high frequency discharges from the top of suitable towers, masts or other elevated structures grounded to the earth, to provide a path along which lightning discharges will flow, and included in the system is a grounded metallic network or grid having a capacity sufficient to relieve the area or structure being protected from any bound electrical charge released by a sudden decrease in the atmospheric potential gradient, such as may follow a stroke of lightning in the vicinity of said area or structure. This grounded metallic network is in all instances placed directly on the surface of and in contact with any roof, tank roof, reservoir roof or other structure which may under a high gradient be the seat of bound charges which upon release may form a secondary surge to ground.

The accompanying drawings illustrate a system constructed in accordance with the provisions of this invention and capable of operating to perform the method in accordance with the invention, the drawings being more or less diagrammatic.

Figure 1 is a view of a lightning protection system embodying the invention.

Figure 2 is an enlarged view, mainly in

section, from the line indicated by 2—2, Figure 1.

Figure 3 is an enlarged plan view of the left portion of Figure 1 showing the reservoir and the elements adjacent thereto.

Figure 4 is a plan showing in detail the base of one of the masts, together with the guy wires and grounding wires.

Figure 5 is a plan view of one of the masts, together with its guy wires and the anchors for said wires, the mast being shown in section.

Figure 6 is an enlarged view of the ionizing apparatus, the housing being shown in section.

Figure 7 is a wiring diagram of the wiring of the ionizing apparatus.

Figure 8 is a diagram of electrical connections.

Referring to the drawings, the area or structure to be protected against lightning strokes may be, for example, a tank farm of the character used for the storage of petroleum and its products. In Figure 3, two tanks or reservoirs of such tank farm are indicated at 11 and on each of them is a metallic network or grid 12 for conducting to ground the bound charges that may exist on the reservoir roof. As indicated in Figure 2 the grids 12 may be metallically bonded to the reservoir roofs 13 as indicated at 14 so that, under the influence of an unbalanced potential, any secondary electrical discharges will be carried to the earth, without arcing, by grounds 15 from the grids. Said grounds may be pipes. The grids are connected to the pipes by wires 16.

Now referring, more particularly, to Figure 8, there is provided a manually controlled switch 17 connecting with a source of commercial or other electric current, preferably at a location that is remote from the area and structure that are to be protected. The manually operated switch 17 is connected by wires 18, 19 to remote control switches 20. 21 indicates a line protector for grounding transients and lightning surges that may occur in the wires 18, 19. The remote control switches 20 are connected by wires 22, 23 to a high frequency, high voltage generator or resonance coil 24 which, when in operation, produces the electrical discharge for ionization. The generator 24 is grounded at 25 to the earth so that lightning discharges will be conducted to the earth.

In Figure 8 but one resonance coil or generator 24 is indicated, but, preferably, the upper end of each mast 40 will be provided with such coil or generator and this comprises a portion of the ionization apparatus which is illustrated, more or less diagrammatically in toto in Figure 6. Referring more particularly to said Figure 6 there is provided a base 26 mounted in a housing 27. The base 26 is of suitable electrical insulating material such as hard rubber, bakelite or the like. Mounted on the base 26 is a support 28 for primary winding 29. Also mounted on the base 26 is a cylinder 30 of suitable insulating material, such as hard rubber, bakelite or the like, and on said cylinder is a secondary winding 31. Connected to one end of the secondary winding 31 and projecting through the top of the housing 27 into the atmosphere is a vertical metal rod 32. The rod 32 is surmounted by a metal ball 33. The other end of the secondary winding 31 is connected to a point on the primary winding 29 and the secondary winding 31 is connected by a wire 34 to the ground 25 hereinbefore mentioned. Mounted in the housing 27 is a line-voltage transformer 35. The secondary winding 36 of the transmitter 35 connects with a spark gap 37 and also connects with the ground 25 and with a variable condenser 38 which, in turn, connects with the primary winding 29.

The housing 27 is constructed of suitable weather proof material and covers all elements of the ionizing apparatus excepting the ball 33 and a portion of the rod 32 and the housing may be connected to the mast, with which it is associated, by a pipe flange 39 which is secured to the bottom of the housing and which is threaded on to the upper end of the mast.

The above described system operates to perform the various operations of the method, as follows: Assuming that there are indications of an approaching storm or that a storm may eventually occur in the area or near the structure to be protected, the manually operated switch 17 will be closed, thus energizing the lines 18, 19 so as to operate the remote control switches 20. This connects the ionization apparatus with the source of power and renders the system operative for producing the desired effect on lightning discharges. The high frequency, high voltage generator operates to produce sufficient free electrons adjacent the ball 33 to insure that, if a path of ionization is even completed from the earth to a cloud in that area, the earth end of that path will be in the ionized zone surrounding the ball 33.

It is to be understood that the remote control switches may be dispensed with and the system put into and out of operative condition by manually operated switch or switches at the base of the mast or other supporting structure.

It is to be understood that the system above described may be modified in any suitable manner to suit local conditions.

It will appear from the foregoing that the methhod of protecting an area or structure against lightning involves the operation of producing a definite zone of relatively high ionization at a point or points removed from the area that is to be protected. The method also includes the operation of conducting to the earth from any elevated objects that may be in the protected area, the secondary electrical surge resulting from a lightning discharge in the vicinity.

It is to be particularly noted that in this system the metallic grid or network lies directly on the structure that is to be protected with no dielectric separating the grid and structure. Consequently, when the grid drains the charges to ground, following a lightning discharge in the vicinity, it drains from the structure to ground charges on the structure and, therefore, no fire hazard can exist there.

I claim:

1. The combination with a reservoir for inflammable substances, of a metallic grid in contact with and extending over said reservoir and electrically connected with the earth, an elevated structure at one side of the reservoir, and a means mounted on the elevated structure operable to artificially produce a higher ionized zone above the level of the grid than is producible in said zone by the natural charged condition of the earth, the last mentioned means being electrically connected with the earth.

2. The combination with a reservoir for inflammable substances, of a metallic grid resting on the roof of said reservoir in contact with and bonded thereto, means for electrically connecting the metallic grid with the earth, and means for artificially producing a measurably higher ionized zone at a point removed from the grid than is producible in said zone by the natural charged condition of the earth, the last mentioned means being electrically connected with the earth.

Signed at Ventura, Calif., this 5th day of July, 1927.

HAROLD L. BUMBAUGH.

US008045314B2

(12) **United States Patent**
Ibok

(10) **Patent No.: US 8,045,314 B2**
(45) **Date of Patent: Oct. 25, 2011**

---

(54) **METHOD OF ATMOSPHERIC DISCHARGE ENERGY CONVERSION, STORAGE AND DISTRIBUTION**

(75) Inventor: **Effiong Etukudo Ibok**, Sunnyvale, CA (US)

(73) Assignee: **The Travis Business Group, Inc.**, Sunnyvale, CA (US)

(*) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 0 days.

(21) Appl. No.: **12/534,115**

(22) Filed: **Aug. 1, 2009**

(65) **Prior Publication Data**

US 2010/0220424 A1 Sep. 2, 2010

(51) **Int. Cl.**

H01T 23/00	(2006.01)
H02H 1/04	(2006.01)
H02H 1/00	(2006.01)

(52) **U.S. Cl.** **361/231**; 361/117; 361/126; 361/127; 361/128; 361/233

(58) **Field of Classification Search** 361/117, 361/126–128, 231, 233
See application file for complete search history.

(56) **References Cited**

U.S. PATENT DOCUMENTS

911,260	A *	2/1909	Pennock	307/149
1,869,661	A *	8/1932	Bumbaugh	174/2
5,367,245	A *	11/1994	Mims	322/2 R
6,038,117	A *	3/2000	Dullni et al.	361/58
6,813,137	B2 *	11/2004	Matsuoka et al.	361/305
7,033,406	B2 *	4/2006	Weir et al.	29/623.5
2002/0101700	A1 *	8/2002	Betts	361/230
2006/0001068	A1 *	1/2006	Mosley et al.	257/306
2009/0109712	A1 *	4/2009	Calloway	363/32
2010/0007321	A1 *	1/2010	Ogram	323/299

FOREIGN PATENT DOCUMENTS

DE	4205521	A1 *	4/1993
JP	04208637	A *	7/1992
JP	08330093	A *	12/1996

OTHER PUBLICATIONS

English language abstract of Kobayashi (JP 04-208637).*
English language machine translation of Kimura (JP 08-330093).*
English language machine translation of Pengel (DE 4205521).*

* cited by examiner

Primary Examiner — Jared Fureman
Assistant Examiner — Scott Bauer
(74) *Attorney, Agent, or Firm* — Blakely, Sokoloff, Taylor & Zafman, LL

(57) **ABSTRACT**

A method of converting atmospheric electrical discharge to a useable form of energy by arresting, storage and retransmission of lightning induced electrical discharge is disclosed. The invention discloses methods of deploying this technology even in isolated locations where no electricity infrastructure exists. Additionally, the potential for achieving in excess of 1 GWe of electrical power supply at costs orders of magnitude lower than fossil fuel or solar is also disclosed. Isolated collection units are disclosed. A method of deployment of these devices on individual cars and recharge stations is disclosed which in effect unplugs these automotive and recharge stations from the grid. This capability significantly decreases their dependence on the electricity grid infrastructure, enabling a much more enhanced rollout capability for the industry. The concept of Energy Dams is disclosed. These are facilities with substantial electrical energy storage capacities with the capability of receiving energy feeds from various generation sources.

18 Claims, 21 Drawing Sheets





Fig. 1a



Fig. 1b


60
30
0
-30
70
50
40
30
20
15
10
8
6
4
2
1
.8
.6
.4
.2
.1

Global Distribution of Lightning Strikes: April 1995 – February, 2003. (Source: NASA)

Fig. 1c


10
20
30
40
50
60

Fig. 2


70
Ti or Cu
80
90

Fig. 3


110
+
100
−
120
130

Fig. 4


140
150
160
170
180
190
200
-
-
-
-
+

Fig. 5


230
+
240
210
220

Fig. 6


250
260
270
280
290
300
305
310
1
2
n

Fig. 7a


311
312
313
314
315

Fig. 7b


318
316
317
319

Fig 7c


1
2
3
4
n
+ve
320
330
340
GND
350

Fig. 8a


333
332
335
331
336
334

Fig. 8b


380
390
400
370
360

Fig. 9



Fig. 10


440
450
460
470
480
490
500

Fig. 11


510
520
530
540

Fig. 12



Fig. 13


610
600
580
590
+

Fig. 14


620
630
640
GND
650
660

Fig. 15


670
680
690
700
710
720
GND

Fig. 16

METHOD OF ATMOSPHERIC DISCHARGE ENERGY CONVERSION, STORAGE AND DISTRIBUTION

TECHNICAL FIELD

This invention relates to the field of electrical energy generation and storage in general and the conversion of atmospheric electrical discharge to a useable form of energy by arresting, storage and retransmission of lightning induced electrical discharge in particular.

BACKGROUND OF INVENTION

Lightning has always been a destructive force of nature. Causing death by electrocution and starting fires both in residential areas and in forests. In either case the loss of life and property is substantial. Lightning strikes have affected communication systems, and by uncontrolled arcing, electricity grids leading to loss of power with substantial economic loss

Lightning is the number one cause of forest and farm fires just in the United States and causes over 80 percent of all livestock losses due to accidents. Property losses run into billions of dollars annually and thousands of deaths and injury are reported yearly. Business losses from power and communications failure run into billions of dollars annually. Up to now, lightning strike damage has generally been controlled primarily by grounding.

A lightning discharge can have voltage of 10 MV to 100 MV and current of 1 kA to 300 kA. It packs so much voltage that it can leap a mile through the air and strike another object. Lightning can strike a building directly or leaping to it after striking a tree or other nearby object or by following a power line. It can strike any object that provides an easier path to the ground for it than the air. Because of the large network of lines, lightning can strike a utility pole at one point and be transmitted to any location in the network. Because of this, utility companies use multiple grounding and other protective devices per mile to ameliorate the lightning effects.

There has been a lot of activity in the alleviation of lightning damage but none in utilizing its energy potential.

U.S. Pat. No. 7,495,168 discloses a dipole lightning conductor which can gather electrical charges from the atmosphere during a thunderstorm, opposite to the polarity of the adjacent cloud on one side and induce a different polarity on the other end contacting the ground. When a sufficient potential difference is reached between the dipole and the earth, a dielectric breakdown occurs sending a large amount of earth charge to the thundercloud, inducing a thunderbolt.

In U.S. Pat. No. 6,012,330, Palmer discloses a method of inducing lightning strikes by shooting a stream of ionized water into a thundercloud and triggering electrical conduction through the ionized water column to the ground. In this invention, while ionized water is used, advantage is taken also of capillary wetting of conducting mesh cable at the tip of which is tethered a balloon of conductor coated Mylar. It is easier to float a balloon than to pump a column of water to any significant height.

In U.S. Pat. No. 6,320,119 Gumley discloses a capacitively coupled composite air terminal with sharp and rounded end components for voltage manipulation to minimize electric field ahead of streamers to minimize corona discharge.

Kato, in U.S. Pat. No. 5,280,335, discloses a compound lightning low voltage arrester with high energy tolerance for power and telephone lines comprising a spark gap is connected to a serial combination of Zinc Oxide arrestor and a non-inductive resistor. By cooperative execution between the spark gap and the Zinc Oxide arrester, the Zinc Oxide is chosen to be of a rating such that thermal breakdown does not occur before the spark gap ignition voltage is reached. The arrangement ensures reliable and predictable discharge and arrester survival even under multiple lightning strikes of close proximity.

Subbarao in U.S. Pat. No. 4,338,648, discloses a discharge counter and arrester current meter to determine arrester steady state current and the number of discharge events occurring during a thunder storm lightning arrester event.

Greenwald and Moses in U.S. Pat. No. 5,610,813 disclose a thunderstorm cell detection and mapping system for acquiring localized lightning strike information and identifying and locating active thunderstorm cells.

In U.S. Pat. No. 4,272,720, a method of differentiating between cloud-cloud and cloud-ground discharges is disclosed. Indicating discharge events with no accompanying lightning ground strike. This indicates that even in the absence of streamers, there is significant electrical discharge that can be converted and stored.

Weir and Nelson disclose in U.S. Pat. No. 7,033,406, a high energy density ceramic capacitor with energy capacity of 52 kW·h in 2005 cu·in, the equivalent of 1600 kW·h/m^3. Hansen in U.S. Pat. No. 6,078,494 discloses multilayer ceramic capacitors comprising doped barium-calcium-zirconium-titanate dielectric, the materials basis for U.S. Pat. No. 7,033,406. It is claimed to be characterized by high dielectric constant, high stability of capacitance value, long service life, low loss factor, high insulation resistance capacitance, low voltage dependence, and wide temperature range stability. Electrodes of base metal alloys from the group of Ni, Fe, Co or their alloys are claimed to be perhaps just as effective as noble metals containing gold, silver, platinum and palladium and may also contain Cr, Ti, Zr, V, Al, Zn, Cu, Sn, Pb, Mn, Mo and W.

Although the energy density capacity is not disclosed, it may be in the same range as U.S. Pat. No. 7,033,406 showing a path for storing the energy that can be extracted from lightning discharge.

U.S. Pat. No. 5,361,187, claims dielectric constant (k) of up to 19000 using similar group of dielectrics and processes. In U.S. Pat. No. 5,604,167 dielectric constant values of between 11,000 and 14,000 are disclosed by the same inventor with equivalent materials and processes.

Since these capacitors use standard powder processing technique, it can reasonably be expected that equivalent characteristics may be observed with naturally occurring doped silicates such as phyllosilicates for example, montmorillonite: $(Na,Ca)_{0.33}(Al,Mg)_2(Si_4O_{10})(OH)_2.nH_2O$, or cyclosilicates such as Benitoite—$BaTi(Si_3O_9)$ as base materials appropriately calcined and doped.

In U.S. Pat. No. 6,078,494 multilayer ceramic capacitors comprising doped barium-calcium-zirconium-titanate dielectric is disclosed. It is claimed to be characterized by high dielectric constant, high stability of capacitance value, long service life, low loss factor, high insulation resistance and low voltage dependence, and wide temperature range stability. Electrodes of base metal alloys from the group of Ni, Fe, Co or their alloys are claimed to be perhaps just as effective as noble metals containing gold, silver, platinum and palladium and may also contain Cr, Ti, Zr, V, Al, Zn, Cu, Sn, Pb, Mn, Mo and W. In U.S. Pat. No. 5,361,187, the inventors claim dielectric constants of up to 19000 using similar group of dielectrics and processes. In U.S. Pat. No. 5,604,167 dielectric constant values of between 11,000 and 14,000 is disclosed by the same inventors with equivalent materials and processes. Since these capacitors use standard powder processing technique, it can reasonably be expected that equivalent characteristics may be observed with naturally occurring doped silicates such as phyllosilicates for example, various grades of montmorillonite: $(Na,Ca)_{0.33}(Al,Mg)_2(Si_4O_{10})(OH)_2.nH_2O$, or cyclosilicates such as Benitoite—$BaTi(Si_3O_9)$ as base materials appropriately calcined and doped.

Although the technology to arrest lightning strikes has been around for at least a hundred years, this invention to harness and store that power has only become viable due to recent advances in super-capacitor technology which has made possible the fabrication of ultrahigh capacitance capacitors with very long lifetimes, high power, high energy densities and very fast charge and discharge rates.

Just as flood water, another destructive force of nature in times past was controlled by building dams, and from the dams eventually came hydroelectric power; and wind including thunderstorms has now been harnessed to generate electricity, this invention describes the technology to harness the power of atmospheric discharges including lightening storms to generate useable electrical energy.

This disclosure also introduces the concept of an Energy Dam. Facilities of substantial energy storage capacity capable of receiving energy feeds from various energy sources such as Solar, Wind, Thermal Power plants and Lightning. For example, during a thunderstorm, electricity generated by wind and lightning is collected and stored.

Lightning strikes every part of the globe but not uniformly. The regions with the highest historical concentration of lightning strikes are shown in FIG. **1***c*. These include Florida and the Gulf Coast in the Americas, the Equatorial Highlands of DRC, Rwanda and Burundi in Central Africa and the Monsoon Belt in Asia.

Except for the Americas, typically, these regions have very little electricity infrastructure. With the capability disclosed here, substantial reserves of electricity can be generated, stored and possibly traded.

In regions of epileptic electricity supply, disruptions in power do not necessarily translate into disruption in service. Since when power is generated, it is fed into these energy dams or local storage units for eventual use. Just as in water supply, the customer is not necessarily conscious of when the local water company is pumping water into storage tanks or local dams, in energy dams, the customer need not be conscious of whether or when electricity is being generated by the utility company because the power to his home is drawn not necessarily live from the grid but from the local energy storage units or energy dams.

BRIEF SUMMARY OF THE INVENTION

A method of harnessing atmospheric discharge and storing said energy in a useful form for subsequent use is presented.

Since the voltage of a lighting bolt can be as high as 100 MV, a methodology for safely channeling this discharge for storage is disclosed.

It is the also the object of this invention to present a storage medium in which an energy capacity of 1 MW·h in a volume of under 1 m^3 can be achieved.

It is also a further objective of this invention to show how lightening strikes on tall buildings can be harnessed to provide energy for the building either directly or fed into the grid.

It is also an objective of this invention to present a methodology for harnessing lightening, heretofore a source of power disruptions for electricity grids and converting it into a useable form of energy and feeding it back into the grid.

Since each electricity grid has a lightning suppression unit, a methodology for harnessing the impulse from these units from lightening strikes and feeding it back into the grid is disclosed.

a method of deploying a network of said storage units along a utility grid is also disclosed.

It is also the objective of this invention to disclose a method of modifying the storage units for single building deployment.

A method of deploying said storage units as vehicular charging centers even in locations not readily served by a utility grid is also disclosed.

A method of manipulating the direction and movement of the lightening bolt in open air locations and redirecting them to predetermined collection points is disclosed.

Lightning storms are some of the major causes of wild fires in the world. A method of redirecting the electrical discharges in any given space via a network of polarized and non-polarized collectors is presented. The discharges can be stored, fed into the grid or grounded.

A method for non-spontaneous discharge generation and storage is disclosed. And a method for adapting the methodology for electric automotive deployment is also disclosed.

BRIEF DESCRIPTION OF DRAWINGS

For understanding of the present invention reference is made of the accompanying drawings in the following DETAILED DESCRIPTION OF THE INVENTION. In the drawings:

FIG. **1***a*. Picture of lightning strike over a city.

FIG. **1***b*. Picture of lightning strike over open plain.

FIG. **1***c*: Global Distribution of Lightning Strikes: April 1995-February, 2003. (Source: NASA).

FIG. **2** shows a schematic of discharge collection and storage system.

FIG. **3** shows a schematic of collection unit showing metallic composition variation.

FIG. **4** Shows a Schematic of composite collector showing polarized ends.

FIG. **5** Schematic of collector network configuration with negatively polarized ends to manipulate and redirect lightning electrical discharge away from the earth for eventual collection at a predetermined location.

FIG. **6** Plan view of polarized collection network as shown in FIG. **5** acting to concentrate and modulate the electrical discharge and redirect such for collection at predetermined location.

FIG. **7***a*. Schematic showing a representation of a network of varistors arranged in rows and columns with the net effect of applying resistive arrestors in parallel and in series to effect voltage mitigation of atmospheric discharges prior to collection and storage.

FIG. **7***b*: Schematic of varistor of power mitigation unit showing cascade of ZnO arrestor in series with non-inductive resistor in parallel with spark gap.

FIG. **7***c*: Multilayer varistor with ZnO, ZnS and WO_3/WSi_2

FIG. **8***a*. Schematic showing cross section of a collection unit.

FIG. **8***b*. Schematic showing cross-section of multilayer ceramic capacitor of **8***a*.

FIG. **9** Schematic of collection unit network mesh in forested area with air frames deployed on each tree as collection of trees linked in a mesh network.

FIG. **10** Plan-view schematic of collection unit network mesh of FIG. **9**

FIG. **11** Schematic showing collection unit deployment on electricity transmission poles linked in a network and fed into the electricity grid.

FIG. **12** Schematic showing collection unit deployment on light poles or wireless towers.

FIG. **13** Schematic showing network of linked collection units and storage units on transmission lines, light poles or wireless towers fed into the grid.

FIG. **14**. Schematic of a system for non-spontaneous atmospheric discharge generation and storage.

FIG. **15** Schematic of atmospheric discharge collection and storage unit deployable on automotive units.

FIG. **16** Schematic of balloon-assisted discharge collection and storage unit.

DETAILED DESCRIPTION OF THE INVENTION

This invention describes a method of harnessing the electrical energy in atmospheric discharges, including, but not limited to lightning, storing said electrical energy and transmitting said energy for use. To this end, as an illustration, the preferred embodiments are represented in the drawings shown in FIGS. **2** to **15**.

Since lightning discharge voltages range from 10 MV to 100 MV with current of 10 kA to 100 kA, the technology challenge will be in mitigating the ultrahigh power which range from 100 GW to in excess of 10,000 GW. Although individual strikes last less than 100 μsec, thunderstorms usually last longer than 30 min. in any cloud formation and location. Indicating that the energy that can be mined from any location in a thunderstorm can run in excess of 50 GW·H. Enough energy for 500,000 homes consuming 1000 kW·h per month. At $100 per 1000 kWh, the revenue equivalent is $5 million per thunderstorm per location.

In solar energy generation, the cost of a 1 MWe rating PV panel is about $1 million. To achieve 1 GWe, the cost implications will be about $1 billion. In fossil fuel plants, the construction cost is approximately $1.3 million per MWe, putting the cost for a 1 GWe at ~$1.3 billion excluding fuel, carbon footprint, and other operating cost. Though thunderstorms are not continuous, with storage capability, the cost basis for an atmospheric discharge energy source will be several orders of magnitude lower than fossil fuel or solar of any architecture.

One embodiment of this invention is depicted in FIG. **2**. Lightning is collected at the air terminals **10**, **20** and transmitted through the conductor **30** to an arrestor **40** and on to the capacitor **50** where the electricity is stored. From which it can be extracted **60** at point of use or transmitted into the grid.

The degree of atmospheric discharge charge collection can be influenced by the metallurgical composition of the collectors. FIG. **3** illustrates the fabrication of the collector with different metals of varying conductivities and atmospheric and electrical stability. In this embodiment, metallurgical compositions for the various segments comprise Ti, Cu, Al. Other metals or their alloys can be used depending on the required properties and the locations of deployment.

In yet another embodiment of the invention as shown in FIG. **4**, a composite collector with opposite polarity air terminals **100**, **110** is used. The air terminals are isolated from each other by an insulator **120**. The negative polarity terminal serves to deflect and manipulate the charge to the positive terminal from which it is conducted to the storage unit **130**.

Another embodiment of the invention is illustrated in FIGS. **5** and **6**. In this representation, negative polarity collectors, **160** deflect the atmospheric discharge so that they do not reach the ground but are deflected for collection at a predetermined terminal **180** of positive polarity and thereafter storage **200**. A plan view representation of this embodiment is shown in FIG. **6**.

It is essential to mitigate the power of the lightning before storage. In one embodiment of this invention, a collection of varistors of various power capacities, linked in series **270**,**280** and **290** are connected in parallel in lines **1** to n, to achieve a desired capability as shown in FIG. **7***a*. The resultant power is stored in the capacitor **300**. An insulator or fuse **305** is placed at the end of the varistor chain to protect the capacitor **300** against over-current. In the event of overstressing, the dielectric or varistor is deformed and the excess current is grounded.

Each component of the power mitigation unit is any of the following configurations as shown in FIG. **7***b*: A ZnO varistor **312** connected in series with a non-inductive resistor **313** and in parallel with a spark gap **311**. The resultant current is further modulated through another ZnO unit **314** and resistor **315**. A cascade of this configuration could be adopted to achieve the desired properties.

Zinc Oxide has a relatively large band gap of ~3.3 eV at room temperature. The consequence of this large band gap includes, higher breakdown voltages, ability to sustain large electric field and high power and temperature operation. Because of this, ZnO is the primary component in varistors and in voltage suppression devices. Zinc Sulfide has a band gap of 3.5 eV for the cubic form and as high as 3.91 eV for the hexagonal form at 300K. While ZnO band gap can be tuned from between 3-4 eV by alloying with magnesium oxide or cadmium oxide, the co-processing of ZnO with ZnS of the hexagonal wurtzite form should provide electrical field and other operational advantages over ZnO alone.

Multilayers of ZnO and ZnS or as sandwich layers with each other with ZnO achieving 50-99.9 mol. % of each layer can be adopted to improve on the suppression properties of the single layer ZnO varistor as is shown in FIG. **7***c*. Said varistor comprising a ceramic base body **318** of multiple layers, terminal electrodes **316**, **317** and internal electrodes **319**.

Alloying of ZnO with metal oxides and nitrides of transition elements including W, Zr, Mo, Mg, Cr, and Ti may improve its band gap characteristics and improve its voltage response non-linearity. Tungsten, in the form of tungsten silicide has very unique crystallization characteristics, particularly in the presence of dopants such as phosphorus or arsenic. Upon post deposition anneal, the Si in the non-stoichiometric tungsten silicide (WSix) segregates to the grain boundaries and the film interfaces. The dopant atoms diffuse preferentially along the grain boundaries. When oxidized, it is the segregated silicon that is oxidized selectively. If the W is exposed to the oxidizing ambient of O_2/Ar or O_2/N_2 at temperatures in excess of 700° C., tungsten oxide WOx (x=3, or 1.5) is formed. It has no corresponding crystallographic orientation to the underlying tungsten silicide or metal, being in the form of an amorphous powder. The fabrication of multilayer varistors with ZnO and WSi_2/WO_3, SiO_2 should provide the flexibility of modulation of the effective grain sizes of the host material to within 0.5-10μ as the case may be. This precise grain size control provides corresponding modulation of the electrical properties including overvoltage suppression.

A schematic of the storage unit **320** is shown in FIG. **8***a*. A collection of capacitors **330** are connected in parallel to achieve a desired capacitance. A schematic of the cross-section of each capacitor unit is shown in FIG. **8***b*. The unit **331** with dielectric layers **332** is a multilayer capacitor comprising alternately stacked internal electrodes **335**, **336** connected to external electrodes **333**, **334**. The dielectric layers may be of uniform composition, or layers of different compositions optimized for flexibility in the modulation of desired electrical, physical and reliability properties.

Capacitance in excess of 1 kF/m^3 with energy storage capacity of 1.5 MW·h is reported as being possible by existing art. With compositional and manufacturing improvements disclosed here these benchmarks are expected to be surpassed making possible energy storage capacities of up to 1 GW·h. Sufficient energy for 1000 households consuming 1000 kW·h of electricity per month for one month.

Lightning storms are a major cause of wildfire. To address this, in yet another embodiment of this invention as represented in FIG. **9**, air terminals **360** are set up on a selection of trees and connected by a conductor **370** in a mesh array as shown in FIG. **10**. The impinging charge is transmitted through a conductor **380**, through a suppressor unit **390** and on to the storage unit **400**.

Utility transmission lines usually have lightning collectors along the length of the network. In this invention as demonstrated in FIG. **11** air terminals **440** deployed transmission poles **450** are linked by a polarized conductor **460**. At predetermined locations the impinging charge is conducted through a suppression unit **490** and thereafter into the storage unit **500**. The stored energy is periodically released into the grid.

In yet another embodiment of the invention, air terminals **510** are deployed on light poles **520**. The collected charged are modified and stored in a storage unit **540**.

In another embodiment, the air terminal/collection units are deployed on radio transmission towers. The charge could be stored individually at each tower location or linked in a network as shown in FIG. **13**. In either case, the stored energy be used at each individual location or fed into the grid **570**.

In the absence of a thundercloud, lightening flash can be generated by the modification of the natural bias between the cloud and ground. This is demonstrated in FIG. **14**, where a positively biased conductor **580** of height greater than nearest ground elevation or nearest structure. The increased elevation and bias facilitates cloud to ground discharge even when there is no active lightning storm. The incoming charge is isolated by an insulator **600** and stored in the storage unit **610**.

In yet another embodiment of this invention, a balloon of conductive material is tethered to a terminal via a mesh line of conducting material. The balloon captures cloud to cloud discharges which are transmitted down to storage. In yet another embodiment this tether line may be wetted by a conductive solution such as but not limited to salt solution to facilitate the discharge conduction.

Another embodiment of this invention is shown in FIG. **15**. In an isolated collection system as shown here, the air terminal **620** which may be biased or unbiased is connected to a collection/storage unit **650**, **660** respectively by conductor **640** and isolated by a dielectric or insulator **670**. Should the discharge exceed the capacity of the isolation, the isolation is bridged and the charge grounded. This isolated collection system is particularly useful where there is no utility grid, particularly in very remote and isolated locations.

This isolated collection capability enables deployment on individual houses and isolated farms. In electric automotive recharge stations, this capability enables the location of these facilities in any location even those not served by regular electricity utilities lines.

In isolated rural areas, the deployment of these isolated collection units enables the provision of electricity where electricity grid infrastructure is not available or practical. The storage units can be deployed in banks as the estimated anticipated usage dictates.

In another embodiment of this invention, the isolated collection unit is modified to be portable for deployment on automobiles. The charge in the storage unit is linked with the automobile's electrical power or storage unit. Alternatively, it can replace the power storage unit of the automobile for pure EV or hybrid cars. Additionally, it can unplug these cars from the grid. With the ambitious industry plans for electric or hybrid cars the infrastructure for charging these cars either in garages or charging stations is somewhat limited. The capability to both 'charge as you go' and unplug from the grid would expand the infrastructure significantly.

In yet another embodiment of this invention, the isolated collection unit is deployed on trains. This could be in commuter trains that directly fed from the grid, or long-haul trains to augment or replace the fossil fuel used.

It is understood that the presentation of these steps in this disclosure is not exhaustive. Only the preferred embodiments of the invention and but a few of the examples of its versatility are shown and described in the present disclosure. It should be readily apparent to those of ordinary skill in the art that the invention is capable of use in various other combinations, environments and applications and is capable of changes or modifications within the scope of the inventive concept as expressed herein. These changes and modifications may be made without departing from the spirit and scope of the invention as set forth in the appended claims.

The invention claimed is:

1. A method of converting an atmospheric electrical discharge into a

useable form of electrical energy comprising

deflecting the discharge to an air terminal via one or more separate air terminals of a polarity, the air terminal having an opposite polarity to the polarity of the separate air terminals;

arresting the discharge via the air terminal to a power mitigating (step down) unit via a conducting unit connected to the air terminal; wherein said power mitigating unit is not a transformer,

reducing voltage of the discharge via the power mitigating unit modulated according to a capacity of the power mitigating unit, wherein the discharge is grounded if in excess of the capacity, and wherein the power mitigating unit reduces the voltage of the discharge from approximately higher than 100 MV (mega volt) and 100 kA (kilo amperes) to below 20 kV (kilo volt), 10 kA; and

storing the discharge with the reduced voltage in an energy storage unit connected to the power mitigating unit, the storage unit comprising modules of high energy density capacitors and the storage unit discharging the electrical energy into a power grid or to an appliance.

2. The method of claim **1** wherein the discharge is caused by incident lightning and wherein the arrestor and mitigating unit comprise an array of self-healing varistors in series and parallel chosen to ensure total conversion of the discharge to a voltage/current level suitable for storage in said capacitors.

3. The method of claim **1**, where the power mitigation unit a configuration selected from a group consisting of:

(a) single ZnO varistor,

(b) Zinc Oxide arrester connected in series with a non-inductive resistor,

(c) Zinc Oxide arrester in series with a non-inductive resistor and in parallel with a spark gap, and

(d) a cascade of configurations as described in (c).

4. The method of claim **1** wherein the storage unit comprises modular array of high energy density multilayered doped ceramic capacitors with storage capacity of 10 kW·h (kilowatt hour) to 1 GW·h (gigawatt hour) and volume 0.1 to 1 m^3 and up to 1000 units.

5. The method of claim **1** in which the air terminal and the storage unit are configured in a mobile unit and deployed on mobile platform having a battery, wherein the mobile unit provides the electrical energy to power the battery without a need for recharging the battery at fixed charging locations.

6. The method of claim **1** wherein the storage unit is located in a charging station, and wherein the storage unit includes modular capacitors for charging an electric vehicle from the charging station.

7. The method of claim **1** wherein the air terminals are deployed on buildings, wherein a portion of the electrical energy stored is used by the buildings and wherein a portion of electrical energy is stored in a central energy storage facility connected to a plurality of storage units.

8. The method of claim **1** wherein the said storage units are located underground.

9. The method of claim **1** wherein the storage unit is receives energy feeds from more than one electricity generation sources, each source being selected from a group consisting of Thermal energy source, Hydro energy source, Solar energy source, Wind energy source and Lightning energy source.

10. The method of claim **4** wherein the ceramic capacitors are fabricated to provide modulation of effective grain sizes within a specified range.

11. The method of claim **4** wherein the multilayer ceramic capacitors comprises dielectric layers of varying compositions individually or as sandwich layers with each other containing Barium-Titanate silicates as host material doped with Zr, WSi2/WO3 to modulate grain growth to between 0.1 to 10 μm, said modulation providing corresponding control of electrical and reliability properties.

12. The method of claim **2** wherein the varistors comprise multilayers of ZnO and ZnS individually layered or as sandwich layers with each other with ZnO achieving 50-99.9% of each layer, said layers being alloyed metal oxides of transition elements to improve voltage response non-linearity.

13. A method to protect a position from impact of an electrical

discharge caused by lightning, the method comprises redirecting the electrical discharge from the position via an array of air terminals to an air terminal of a collection unit, said collection unit comprising a power mitigating unit and a storage unit and wherein the power mitigating unit is not a transformer, the air terminal of the collection unit biased with a first

polarity, each of the array of air terminals biased with a second polarity with a magnitude, the second polarity opposite to the first polarity, wherein the redirection is controlled by the magnitude and the second polarity; and

storing the electrical discharge in the collection unit located significantly removed from the impact position.

14. The method of claim **13** wherein the discharge redirection is via a biased conductor to the collection unit.

15. The method of claim **13** wherein the position is located in an area of a forest, wherein the array of air terminals are deployed on trees in the forest, wherein tips of the array of air terminals are positioned in close proximity to treetops of the trees, and wherein the discharge is fed into an electricity grid as electrical energy from the collection unit.

16. The method of claim **1** wherein the storage unit is connected to electrical power lines of the power grid and wherein the electrical energy is fed back into the power grid via the electrical power lines.

17. The method of claim **1** wherein the storage unit is located at a telecom tower, a light poles or other free standing structure with a need for operational energy and wherein the electrical energy from the storage unit is used for the operational energy.

18. A method of generation of atmospheric discharge, the method comprising:

modulating bias of a dipole air terminal conductor to capture charges from clouds to ground without occurrence of natural lightning, the conductor including a balloon, a terminal and a tether line connecting the balloon and the terminal, wherein the bias has a magnitude and a polarity controlled by the modulation relative to the ground; and wherein the tether line is a conductive cable soaked by an ionic liquid including salt solution to facilitate conduction of the charge, and

storing the charge in a collection unit comprising a power mitigation unit and a storage unit wherein said power mitigation unit is not a transformer, feeding said charge into an electricity grid or appliance.

* * * * *

US 20010032905A1

(19) **United States**

(12) **Patent Application Publication**

Grandics

(10) **Pub. No.: US 2001/0032905 A1**

(43) **Pub. Date: Oct. 25, 2001**

(54) **METHOD AND APPARATUS FOR CONVERTING ELECTROSTATIC POTENTIAL ENERGY**

(76) Inventor: **Peter Grandics**, Carlsbad, CA (US)

Correspondence Address:
OPPENHEIMER WOLFF & DONNELLY LLP
Suite 3800
2029 Century Park East
Los Angeles, CA 90067-3024 (US)

(21) Appl. No.: **09/732,110**

(22) Filed: **Dec. 7, 2000**

Related U.S. Application Data

(63) Non-provisional of provisional application No. 60/169,378, filed on Dec. 7, 1999.

Publication Classification

(51) **Int. Cl.^{7}** **B64C 15/00**; B64C 27/82

(52) **U.S. Cl.** **244/51**

(57) **ABSTRACT**

A new method is described to produce directional currents in the space lattice, the fundamental fabric of the universe. The currents may be unidirectional or vortexual in nature and are suitable for propulsion or the generation of electric power. For propulsion, the unidirectional currents are induced by charging capacitors possessing suitable geometries. This will allow the manufacture of vehicles capable of levitation and flight. The vortexual space lattice currents are produced in a suitable pyramid when electrostatic and magnetic fields interact transversally. The vortex causes charge separation and current in the coil wrapped around the pyramid.



FIG. 1


1st VORTEX
WAVE
2nd VORTEX



FIG. 2



FIG. 3

FIG. 4


26
27
23
24
25
19
20
21
22
14
15
16
17
18
8
9
10
11
12
13
1
2
3
4
5
6
7



FIG. 5


ELECTRON
POSITRON

FIG. 6


ELECTRON
POSITRON

FIG. 7

FIG. 8


POSITIVE CHARGE
NEGATIVE CHARGE

FIG. 9


ELECTROSTATIC FIELD
MAGNETIC FIELD


106
TOP PLATE
110
80KV
DC
102
DETECTOR COIL
100
PYRAMID
108
104
OSCILLOSCOPE
GROUND

FIG. 10

METHOD AND APPARATUS FOR CONVERTING ELECTROSTATIC POTENTIAL ENERGY

CROSS-REFERENCES

[0001] This application claims priority from Provisional Application Ser. No. 60/169,378, by Peter Grandics, filed Dec. 7, 1999, also entitled "Method and Apparatus for Converting Electrostatic Potential Energy," the contents of which are hereby incorporated by this reference.

BACKGROUND OF THE INVENTION

[0002] This invention is directed to methods and apparatus for conversion of electrostatic energy. Specifically, this invention describes methods to cause directional movements in the space lattice.

[0003] To fully comprehend the theoretical basis for these methods, first the genesis of the elemental particles electron and positron needs to be discussed based on geometric or space relationships, and their interactions at the sub-elemental particle level must be clarified. The advantage of such an approach is that it can be visualized, and not just expressed mathematically. by definition, the word "structure" implies a geometric relationship, and such relationship must be of great importance in atomic structures even though they are hidden from direct view.

[0004] The study of geometric relationships of macroscopic structures of matter may provide important insights into the properties of matter at the microscale. Astrophysics suggests the universe probably started with an energy burst from one point. This big bang theory is supported by visual and electronic evidence that the galaxies are expanding away from a single center.

[0005] In stellar formation, gravitational pull and velocity generate a rotary vortex. Even in the relative absence of such factors, all objects spiral at some given rate peculiar to their special influences. A spiral is created when an object moves forward while rotating. Earth's movement in space is an example of this process. The Earth orbits the sun, while the sun pulls it along towards the direction of Vega in the constellation Hercules. the combined circular and forward motion creates a spiral. Our sun has the same motion in relation to the galaxy center. Our galaxy, the Milky Way, also spirals away from the Big Bang center.

[0006] Water going down a drain demonstrates some of the special influences affecting spiral formation. The spiral, caused by Coriolis forces, changes dynamically under the effects of gravitational pull, drain diameter, obstructions, temperature, pressure, volume, viscosity, and stirring. The spiral changes shape and acceleration but maintains the universal shape of a spiral. The water flow is responsive to all possible factors, and so is the spiral.

[0007] Remarkably, the spiral vortex has a "memory" of itself. When a vortex is distorted to become elliptical, it spontaneously returns to its original circular form. The vortex is a self-sustaining type of motion; its resiliency is comparable to that of atomic bodies.

[0008] Spirals condense energy and sine waves transmit it along a frictional line of force between them (**FIG. 1**). Spirals and waves could be considered illusions of each other. Two opposed spirals form a wave, or a wave produces two spirals. A sine is the producer of waves of spiral forces. Any fluid capable of supporting wave motion can also support vortex motion.

[0009] The spiral is the prominent form of organization of matter. The large proportion of spiral galaxies among celestial bodies visibly demonstrates this. On the microscale, even the building block of life, the DNA uses this structure and spirals are likely to be dominant at the level of the atom and below. This is the subject of the present theory. I propose that all atoms, all stellar formations use the mutable spiral to adapt to their spiral environment.

[0010] Another proposition is that all mediums of matter can be considered a type of crystal. Crystallinity is readily recognizable in the mineral world, but it is also a more general state of matter. Besides solid crystals, liquid crystals also exist. by definition, a crystal is a regularly repeating atomic arrangement, such as a chemical element, a compound or an isomorphous mixture. Therefore, the term crystal applies to material expressions where crystallinity is not so obvious, e.g., gases, complex biologics and various life forms, including viruses, bacteria and higher organisms. Air and water could be considered loose crystals subject to fast molecular drift. At low temperatures where molecular drift is reduced, gases form solid or liquid crystals. Soil and stone and metal are opaque cryptocrystals with slower rates of molecular drift. On the macroscale, the Earth could be seen as faceted crystal with its mountain ridges are the ridges of a geodesic sphere. Biopolymers such as DNA, proteins or polysaccharides fit well the definition of a crystal and are commonly made into crystals. All life can be seen as a crystal. From fish to humans, we are liquid crystals on a skeletal lattice.

[0011] Crystals are the shape of discrete units of matter and notably the channelized direction of energy, that is, the direction energy that flows unforced. Crystals form the basis for corpuscle-wave conversion. Crystals create resonance and conduct the flow of energy between states. Crystals can also be considered lenses. By definition, a lens is a device capable of refracting, or bending light. Light is an energy flow, so on a more general term, a lens can be defined as any object capable of changing the direction of energy flow. By this broader definition, even an electric wire is a lens as it is capable of changing the direction of flow of electrical energy. lenses communicate energy as part of the principle that all matter vibrate, all matter transmit, and all matter receives energy. The universe changes energy states with lenses. Following this line of reasoning, the universe could be viewed as a resonant crystal lens.

[0012] This observation is important because the universe is considered to be largely empty, the largest component of which is the so-called vacuum space. Since Nature seems to use the same geometrical organizing principles from macro to micro, I suggest that the vacuum space must also be "crystalline". Since the term crystalline is associated with material of which the vacuum space is substantially devoid, I will use an extended meaning of "structured" when discussing crystallinity of vacuum space.

[0013] The theory of "crystalline" vacuum space was introduced by Simhony (Simhony, M. (1990) The Electron-Positron Lattice Space, Cause of Relativity and Quantum Effects, Physics Section 5, The Hebrew University, Jerusalem., and Simhony, M. (1994) Invitation to the Natural

Physics of Matter, Space, and Radiation, World Scientific Publishing Co., London, UK.). Simhony reasoned that three-dimensional physical phenomena must have three-dimensional physical causes and explanations.

[**0014**] He demonstrated that physical reality can be described by the laws of classical physics supplemented by the presence of a space lattice. This led to the development of the theory of an electron-positron lattice space (epola for short). In the epola, bound electron-positron pairs reside at the lattice sites of a face-centered cubical "crystal" structure similar to that of NaCl crystals (Kennon, N. F. (1978) Patterns in Crystals, John Wiley & Sons, New York.).

[**0015**] The epola theory allowed a physical explanation of all yet unexplained postulates of quantum mechanics and relativity including the particle-wave duality, the quantized nature of electron orbits in the atom, the electromagnetic radiation, the photon, and gravitational interactions as well as the relationship of electrostatic, magnetic and gravitational interactions. He demonstrated gravity to be a derivative of electromagnetism.

[**0016**] There is a large body of evidence suggesting that the vacuum space is not empty at all. Experiments verify that the vacuum space contains an enormous residual background energy (some examples are: Boyer, T. H. (1985) The classical vacuum (zero-point energy) Scientific American 70-78, Haisch, B., Rueda, A. and Puthoff, H. E. (1994) Beyond $E=mc^2$, The Sciences, 34, No. 6, 26-31, and B.

[**0017**] Haisch and A. Rueda, (1999).On the relation between zero-point-field-induced inertial mass and the Einstein-de Broglie formula, Physics Letters A, in press), called zero-point energy (ZPE). The ZPE manifests as a pervasive and vast electromagnetic field called the zero-point field (ZPF). a dynamic field, ZPF is a virtual plasma, with particles arising and disappearing of a background energy field serving as a baseline, or zero point, for all physical processes. The ZPE remains even at absolute zero. Simhony has described zero-point energy fluctuations as analogous to brownian motion of epola particles around their lattice sites. A potential alternative term for the lattice space is zero-point-field (ZPF) described in 1994 by Haisch, Rueda and Puthoff (Haisch, B., Rueda, A. and Puthoff, H. E. (1994) Beyond E=mc2, The Sciences, 34, No. 6, 26-31). This area remains an active field of research.

[**0018**] Simhony also suggested that all particles of matter are directly formed from the lattice space, the mechanism of which remains undetermined. The present theory intends to answer this question in terms of lattice space.

[**0019**] I propose that the vacuum space has a lattice structure similar to that introduced by Simhony. this structure is a face-centered cube having 27 lattice sites (**FIG. 2**). on the lattice sites reside the elemental "particles" forming all particles of matter. These are "particles of energy" rather than particles of matter.

[**0020**] I propose that the "particle of energy" of the space lattice, called here the subtle electron, is a spiral energy vortex tied into itself in the form of a circumvolution cissoid. The circumvolution cissoid is a spiral turn around an axis converging into an apex, in a self-imploding, self-sustaining vortex motion (**FIG. 3**). The vortex pulsates and its vibration is a function of **(2_Ø)x, where Ø is the Fibonacci series number and** x=0,1,2,3, the number of turns the circumvolution cissoid makes. Once started up, such a vortex would run practically indefinitely inside the space lattice.

[**0021**] The internal friction of such a space lattice must be so low that it would only be noticeable as a red shift in the spectra of distant galaxies. The space lattice, like its constituent energy vortices, must also be a resilient structure with only limited compressibility. At the same time, it must have fluidity since it is capable of transmitting waves with transverse displacement. In the absence of atomic oscillators, the space lattice would be incapable of dissipating energy in the form of heat.

[**0022**] Vortices maintain their circular forms as well as their proportions and dimensions. The adjacent vortices have a coordinating effect that establishes axial alignment and rolling contact between vortices within the space lattice. In that sense, there is a great deal of similarity between crystals of material bodies and the structure of the space lattice. I postulate that the space lattice is an incompressible, frictionless fluid made out of cubes of units cells of subtle electron vortices.

[**0023**] We can consider the space lattice equivalent to motion. A space lattice in motion necessarily has inertia. Although inertia is generally attributed to moving material bodies, it is actually a property of motion. Inertia is just the continuity of motion. In the case of vortex motion the inertia is localized. Localized inertia can also be called momentum. To account for the elemental particles of matter, we need a space lattice that is capable of moving.

[**0024**] Anderson discovered in 1932, that when 1.02 MeV photon energy is absorbed into the vacuum space, an electron-positron pair can appear. this observation is explained here as a glimpse into the formation of elemental particles of matter. To become matter, energy must become more angular. This hypothesis is derived from the observation that all material expression is a type of crystal, and is the compound and derivative of a fundamental triangular form which all the seven crystal systems can be derived (Kennon, N. F. (1978) Patterns in Crystals, John Wiley & Sons, New York.). The mechanics of this expression at the level of the space lattice are explained as follows: As the energy of electromagnetic radiation propagates through the space lattice, it polarizes the subtle electron energy vortices (for analogy see **FIG. 1**). Subsequently, the "energy particles" of the space lattice, the subtle electrons, undergo a phase transition similar to the condensation of gases. This happens at the resonant frequency of the 1.02 MeV gamma radiation.

[**0025**] The 27 subtle electrons of the unit cell of space lattice rearrange into a pyramidal segment of the cube (**FIG. 5**) on six levels each forming circles of vortices. An open-flat presentation of the rearrangement is shown in **FIG. 4**. This structure is the postulated smallest unit of matter. note that the cube is composed of six interlocking pyramids so the cube and the pyramid are resonant structures. Inside the pyramid, the subtle electron rings form a vortex capable of circulating the fluid space lattice. The pumping action is driven by the self-sustaining, pulsating vortex motion of its constituent subtle electrons (**FIG. 3**). The overall shape is a cone fitting inside the pyramid. The formation of matter follows the geometry of the space lattice (**FIG. 5**) and thus we may conclude that the space lattice provides the blueprint for matter.

[**0026**] An electron is produced when two such cones are joined in a tip-to-tip conformation (**FIG. 6**). The positron is made out of two vortices (cones) facing base-to-base. The energy vortices which make up the electrons have a resilient vibratory structure which should be capable of vibrating at various frequencies and modes. This would allow us to account for the series of spectral lines, a signature of absorbing and emitting energy at various frequencies.

[**0027**] These complex vortex particles have a pumping effect and circulate the fluid space lattice. For the electron, the space lattice is drawn in polarly and expelled equatorially. For the positron, the space lattice is drawn in equatorially and expelled polarly (**FIG. 7**). The direction of circulation of fluid space lattice determines the positive or negative polarities. When in close proximity, a specific flow coupling occurs between the electron and positron (**FIG. 7**). It is quite probable that a similar flow coupling exists between a proton and an electron inside the atom, although such coupling is stable in the case of the proton. This is likely a result of the different vibratory structure of the vortex proton.

[**0028**] The instability of the electron-positron pair is also derived from this model. The perfectly fitting, counter-rotating cones of energy extinguish each other with the release of a combined energy of 1.02 Mev. This results in the reconstitution of the respective unit cells of the space lattice along with the release of the phase transition energy.

[**0029**] The size of the subtle electron is estimated based on the "nuclear radius" of 0.1 fm for the electron, to be approximately 0.005 fm. The lattice constant for the unit cell of space lattice is approximately half of the "nuclear radius" of the electron, i.e,.0.05 fm. This indicates that the space lattice is quite dense compared to atomic bodies.

[**0030**] The model explains the attraction of free electric charges as follows (**FIG. 8**): Opposite charges move towards each other. This movement is due to the equatorial circulation of fluid space lattice from the negative charge to the positive charge and the polar circulation of space lattice from the positive to the negative charge. The attraction of the vortices pull the two partners together. The electrostatic field between separated charges is defined as the flow of the space lattice from the protons to the electrons and the outside return flow of space lattice from the electrons to the protons (see **FIG. 8**). This explanation will eventually lead to a hydromechanical theory of electricity.

[**0031**] Interestingly, there is a net unidirectional flow of fluid space lattice in the axial direction of the free electric charges (**FIG. 8**) flowing in at the negative pole and flowing out at the positive pole. if the charges have a steady parallel orientation, e.g., as in an electric condenser, then a pressure differential must arise in the space lattice around the opposite poles of the condenser. To fully appreciate the significance of this conclusion, we must first examine how material bodies accelerate through the space lattice.

[**0032**] Accelerating objects encounter resistance facing an increased pressure of the space lattice at the front end and a reduced pressure at the rear end of the object. This situation is common to all propulsion methods which apply mechanical force on the physical object. Therefore, it is logical to suggest that a pressure differential of space lattice at the opposite sides of material bodies is always accompanied by a change in the rest or motion of such bodies. To obtain a propulsion force, instead of exerting force on the physical object we should transfer the space lattice that controls the behavior of the object from the rear end of the object to its front end.

[**0033**] Therefore, a sufficiently charged object in which the charges have a steady parallel orientation should behave as an accelerating object, i.e., it should move toward the direction of its positive pole. In fact, this happens due to its own generated space lattice pressure differential Now that the fundamentals are developed, the effect may provide the basis for a new propulsion and gravity cancellation method, and may give us insights into the mechanism of gravitation. A craft utilizing such propulsion method could exhibit inertialess acceleration as it would meet no resistance from the surrounding space lattice.

[**0034**] The theory also allows us to develop strategies for tapping into the energy of the space surrounding us. Separated charges in an electric condenser cause a directional flow of the fluid space lattice. Conversely, if we could induce a directional flow of the space lattice, it would cause a separation of charges in material objects. To explain how such an effect could be produced, first the physical basis of magnetism must be explained.

[**0035**] I have described the physical basis for the electrostatic field as a flow of a space lattice current from the positive charges to the negative charges and back on the outside to the positive charges. I shall now explain how these space lattice currents flow in an electric wire. The space lattice flow which connects the electrons to the protons of the atoms in the wire becomes extended in the length of the wire. This is the same direction as the direction of movement of electrons which, in the current, flow in the outer shell of the wire. The external return flow of the space lattice will be in the opposite direction in the space around the wire. This flow constitutes the magnetic field. In a solenoid, the surrounding space lattice flows in the opposite direction relative to the path of the electrons. The magnetic effect will appear as either N or S magnetic poles. The magnetic poles are mirror images of each other. This suggests that a single isolated magnetic pole cannot exist.

[**0036**] In the electrostatic field, the outside space lattice currents flow between electrically charged particles. The magnetic field, on the other hand exhibits a closed circuit flow of the space lattice along the path of a solenoid or a circuit. Electric and magnetic forces are produced by movement of the space lattice in spirals or whirls.

[**0037**] An electric charge and a magnetic pole do interact even though they do not apply any force to each other. A magnetic pole will bring about a directional orientation of the electrons in a charged object, while an electric charge will cause the electric polarization of the adjacent surface of a magnetic pole.

[**0038**] The final question remains is the superimposition of electrostatic and magnetic fields on each other. The practical significance of the interaction of axially oriented electrostatic and magnetic fields is likely to be small compared to their interaction at an angle. A transversal superimposition of a magnetic field on an electrostatic field will cause the distortion of both fields. The axial flow of the space lattice between the electric poles, which is the physical basis for the electrostatic field, will be distorted, but its circulation will continue. Similarly, the rotating space lattice, which is the basis for the magnetic field, will also be distorted, flowing in irregular circuits.

[0039] To study the transverse superimposition of electrostatic and magnetic fields, a shaped electrostatic field must be created (**FIG. 9**). When a magnetic field interacts with the shaped flow of the space lattice, it could result in the formation of a space lattice vortex at the points where the two flows intersect. This is based on previous hypothesis that the space lattice is an incompressible fluid, wherein the intersecting currents cannot penetrate but distort each other's flow patterns.

[0040] To expand this shaped electrostatic field into three dimensions, a pyramid is required. I have already discussed the importance of the pyramidal geometry in the formation of matter. The pyramidal geometry may also be important for producing a space lattice perturbation, which is the equivalent of a magnetic field when it follows a rotational symmetry (e.g. a vortex).

[0041] If with transversally superimposed electrostatic and magnetic fields a pyramid did indeed produce a vortex in the space lattice, then the rotational flow of the space lattice should cause the separation of charges and an electric current in material bodies, as predicted by this theory. This means that under appropriate conditions, a pyramid could become a power generator.

[0042] For power generation in a pyramid, the source of the electrostatic and magnetic fields could potentially be the Earth. The earth has a high voltage electric field such that the earth's surface is negatively charged while the atmosphere is positively charged (Feynman, R. P. (1964) Lectures on Physics, v.2, 9-2, Addison Wesley, Inc., Palo Alto, Calif.). The voltage field is believed to be maintained by the Sun's radiation energy and/or cosmic ray energy and extends from the ionosphere to the surface creating a potential difference of about 400,000 V. The Earth's electrostatic field never seems to get depleted despite all the storm activities and discharging of energy. The voltage gradient is estimated to be 200 V/m around the surface of the earth. The total energy reaching earth at any moment is about 700 MW (400,000 V multiplied by a current of 1800 A). The magnetic field strength of the earth is about 0.5 Gauss and exhibits continuous pulsations with main frequencies of 8 to 16 Hz.

[0043] Therefore, the earth's electrostatic and magnetic fields could potentially be utilized to create a space lattice vortex in and around a sufficiently sized pyramid. This hypothesis has been tested experimentally. The earth's electrostatic field was modeled as described in the Examples.

[0044] Therefore, there is a need for an improved method and apparatus for the conversion of electrostatic energy as described herein.

SUMMARY OF THE INVENTION

[0045] Pursuant to this invention new techniques are described to produce directional currents in the space lattice. The currents are induced either by separated charges, properly positioned magnetic fields or by the interaction of electrostatic and magnetic fields at an angle, specified by the side angle of a pyramid. The induced space lattice currents can be utilized to generate specific effects which may vary from propulsion, to gravity cancellation and power generation.

[0046] In particular, an aspect of the present invention is a method producing directional currents in the space lattice utilizing:

[0047] (1) separated electric charges; and

[0048] (2) the interaction of electrostatic and magnetic fields.

[0049] In one preferred embodiment of the invention, electric charges are separated in an oriented fashion. The orientation can be a parallel orientation. The orientation can be obtained in a capacitor. The capacitor can be used for the propulsion of a vehicle. The capacitor can provide lift and lateral movement control for said vehicle.

[0050] The interaction of electrostatic and magnetic fields can be set up in a pyramid.

[0051] The interaction can produce a vortex in the space lattice.

[0052] The vortex can be tapped to produce electric power, which can be obtained by wrapping a coil around the pyramid.

BRIEF DESCRIPTION OF THE DRAWINGS

[0053] The following invention will become better understood with reference to the specification, appended claims, and accompanying drawings, where:

[0054] **FIG. 1** is a diagram showing the relationship between a spiral and a wave;

[0055] **FIG. 2** is a diagram demonstrating the geometry of the space lattice;

[0056] **FIG. 3** is a diagram demonstrating the circumvolution cissoid;

[0057] **FIG. 4** is a diagram demonstrating the smallest unit of matter;

[0058] **FIG. 5** is a diagram showing the rearrangement of the unit cell;

[0059] **FIG. 6** is a diagram exhibiting the structures of electron and positron;

[0060] **FIG. 7** is a diagram demonstrating the flow coupling of electron and positron;

[0061] **FIG. 8** is a diagram showing the attraction of electric charges;

[0062] **FIG. 9** is a diagram showing the interaction of a shaped electrostatic field with a magnetic field;

[0063] **FIG. 10** is a diagram displaying the arrangement of the capacitors in the craft; and

[0064] **FIG. 11** is a diagram demonstrating the pyramid experimental setup.

DESCRIPTION OF THE PREFERRED EMBODIMENT

[0065] Pursuant to this invention, novel methods are described to induce directional currents in the space lattice which is postulated to be part of the boundary conditions of the Universe. These methods are useful in providing for the conversion of electrostatic energy into a useful form. The first method relates to generating an unidirectional flow of the space lattice which could be useful in cancelling gravity and generating a propulsion force. A possible configuration for keeping the charges separated and stored is in the form of a capacitor. The shape of the capacitor and the body of such device is important for optimal performance. A pyramidal or conical shape is preferred for the alignment of the capacitors (**FIG. 10**). Optimally, the shape of the capacitor follows the shape of the craft.

[**0066**] In **FIG. 10**, the pyramid **100** is surrounded by a detector coil **102** which is in turn connected to an oscilloscope **104**. In the experimental setup shown, the field is established by a top plate **106** and a ground **108** connected to a source of DC electrical energy **110**.

[**0067**] The conductive elements of the capacitor are layered into the pyramidal or conical segment of the hull of such craft. Optimally, there should be several layers of negatively charged conductors on the outside while a single layer of positively charged conductor in the inside of the craft. All conductive elements should be carefully insulated in order to keep the charges inside the capacitor.

[**0068**] In the center of the craft, a conductive, insulated pole is mounted such that the pole extends out into the exterior at the top of the craft. The tip of that pole has a metal ball mounted on which is also positively charged. When all the capacitor plates are charged, they induce an unidirectional, upward flow of the space lattice. This means that the space lattice pressure above the craft will be higher than the space lattice pressure at the bottom of the craft. This pressure differential is unstable and progresses towards an equilibrium. It will grab the craft and propels it forward in order to eliminate the pressure gradient. This requires that a sufficiently high voltage be applied. My estimation is that about 5 kV is needed to lift every gram of an object. The capacitors incorporated into the hull will give control over lift.

[**0069**] To obtain directional control over all three axes of movement, three capacitors need to be mounted at the bottom of the craft apart from each other. These capacitors, could take the shape of a ball and would be mounted on retractable shafts. The top half of the capacitors would be positively charged while the bottom half is negatively charged. When in flight, the capacitors are retracted and charged based on the needs of directional control. To achieve forward movement, the charges on one capacitor facing the direction of the desired path should be reduced relative to the other two capacitors. This would make the craft tilt forward and start moving in that direction. An alternative method of lateral directional control could be obtained by dividing the capacitor bank in the hull into segments which segments could be charged individually.

[**0070**] Upon landing, the three ball capacitors would be protracted on their shafts and serve as landing gear. On landing, they would be discharged because the earth is the greater ground. On launching, the main capacitors of the body would be activated causing a lift-off. The three capacitor landing gear would then be retracted and charged up so that they can function for lateral directional control. On-board static generators would supply the voltage required for the operation of the craft.

[**0071**] The most significant aspect of this type of propulsion system would be the loss of inertia during acceleration. Inertial forces pose great obstacles to improving the performance of current propulsion techniques. Since we are now in control of the space lattice surrounding the craft, it will encounter no resistance from the space lattice. The passengers of such craft would feel no forces acting upon their bodies even if the craft achieved enormous accelerations.

[**0072**] This overall design is suitable for the development of a wide range of transportation vehicles, from automobile-type to aircraft and spacecraft. The impact of such a technology on our economy would be enormous. We could eliminate a major factor in environmental pollution, the generation of greenhouse gases which place a great stress on our ecosystem. In the United states, 66% of the greenhouse gases are produced by transportation vehicles and just 34% by power generation. The signs of global warming and the deterioration of the ecosystem are visible from every direction.

[**0073**] The developing countries are bent on establishing the same economical model evolved in the developed countries, representing about 16% of the world population. Worldwide mass deployment of our current energy technologies would most likely cause an environmental catastrophe which may terminate higher life-forms on this planet.

[**0074**] This makes it very important that the focus of our energy sector shifts towards renewable, non-polluting sources of energy. The subject invention offers a solution in this regard. The transversal interaction of electrostatic and magnetic fields in and around a pyramid offers the potential to tap into the electromagnetic field of our planet. I have found that a pyramid becomes a power generator when the electrostatic voltage field gradient of the earth is reproduced around it. Tapping the energy field was as simple as placing a coil around the pyramid.

[**0075**] The optimal size production pyramid is likely going to be large. The optimal material composition may be alternative layers of metal and dielectric to maximize the total amount of charges the pyramid can hold. This is important for increasing the performance of the pyramid. A coil is then wrapped around the pyramid to tap into the generated field. The orientation of the pyramid to the magnetic North pole does not seem to be a prerequisite for operation. Such a pyramid generator will be called the pyramitron.

[**0076**] The following Examples illustrate the features and advantages of the subject invention. Accordingly, it is to be understood that the description in this disclosure is to facilitate comprehension of the invention and should not be construed to limit the scope thereof as persons skilled in the art can, in light of this disclosure, generate additional embodiments without exceeding the scope or departing from the spirit of the claimed invention.

EXAMPLE 1

[**0077**] Demonstration of the pyramitron: For the experiments, I have randomly selected a one-foot base length foam pyramid from a pyramid vendor (The Pyramid Project, Ft. Wayne, Ind.). The outside of the pyramid was covered with aluminum foil. The pyramid was placed on a 2'x2' insulating polyethylene platform equipped with an adjustable height 2'x2' size aluminum top plate, 1/16" thick (**FIG. 10**). The height of the aluminum plate was adjusted as needed and a gap of 1 ¼" between the plate and the tip of the pyramid was used in the experiments.

[**0078**] A high voltage (HV) CRT power source producing 30 kV DC was taken from a television set. I have assumed that an actual energy producing pyramid should be relatively high in order to obtain a large voltage drop from its tip to the ground. Therefore, assuming a height of 150 m for a life-size pyramid and a voltage drop of 200 V/m near the surface of the Earth, the 30 kV voltage is in the range of the voltage-drop expected for the height of a practical size pyramid.

[**0079**] The positive pole was attached to the top aluminum plate. This simulated the positive charge of the atmosphere. One corner of the pyramid was attached to the negative pole of the high voltage power source, while the opposite corner of the pyramid was grounded. This setup served as a model for the electrostatic field distribution around a potential life sized pyramid.

[**0080**] As controls, either a 1'x1' sheet of aluminum foil or an aluminum foil-covered box, having the main dimensions of the test pyramid (1'x1'x⅝"), was used as a negative pole. The detector coils were made by winding up a 24 gauge enamel-coated magnetic wire (20 turns, approximately 8 cm diameter). A Tektronix high-frequency oscilloscope, model no.2236 was used for signal acquisition and analysis.

[**0081**] The first set of experiments were control measurements with the box of the same height and base lengths as the test pyramid. The detector coil was placed on the top of the box. Measurements were taken with and without the high voltage applied. One corner of the box was attached to the HV power source (negative pole) and the opposite corner to the ground. The same arrangement was used for the flat square (1'x1') foil. The peak-to-peak signal amplitude for the box was 8 mV and the signal frequency was 2 MHz. For the flat foil sheet, the signal amplitude was 12 mV with a frequency of 1.43 MHz. The signal form was of a decaying sine wave.

[**0082**] When high voltage was applied to these shapes, a signal amplitude of 14 mV was obtained for the flat sheet and a 16 mV for the box. The signal frequency was 1.54 MHz for the flat sheet and 2 MHz for the box. The wave forms were of decaying sine waves in all these experiments.

[**0083**] When the pyramid was tested without HV, the peak-to-peak signal amplitude was measured at 60 mV with a frequency of 2 MHz. The wave form was different from those of the control experiments; it was a modulated, decaying sine. When the high voltage was applied, the signal amplitude increased up to 180-200 mV, while the frequency remained at 2 MHz. The pyramid produced a signal intensity significantly higher than the controls. When a metal (aluminum) pyramid of the same size (wall thickness 1⁄16" inch) was tested in the same high voltage field using the same detection coil, a voltage of 1-1.5 V was detected at the frequency of 2 MHz.

[**0084**] The experiments confirmed theoretical assumptions about the pyramidal shape's ability to cause perturbations in the space lattice when the pyramid is placed in transverse electrostatic and magnetic fields. The resulting space lattice vortex causes a separation of charges in the detection coil, producing a voltage signal greatly exceeding control levels. Control values for the flat sheet and the box in the electrostatic field were at the level of the background noise. Thus, when the electrostatic and magnetic fields intersected at 90° or 0°, no effect was observed. However, when the fields intersected at an angle defined by the pyramidal shape, a large signal was produced. The pyramid is clearly instrumental in generating the signal. This finding provides the second experimental proof for the present theory of electric polarities. It also demonstrates that potentially, we may be able to tap into the electromagnetic field of our planet and draw electric energy. The practical implications of this finding are enormous.

I claim:

1. A method producing directional currents in the space lattice utilizing:

(a) separated electric charges; and

(b) the interaction of electrostatic and magnetic fields.

2. The method of claim 1 wherein said electric charges are separated in an oriented fashion.

3. The method of claim 2 wherein said orientation is a parallel orientation.

4. The method of claim 3 wherein said orientation is obtained in a capacitor.

5. The method of claim 4 wherein said capacitor is used for the propulsion of a vehicle.

6. The method of claim 5 wherein said capacitor is providing lift and lateral movement control for said vehicle.

7. The method of claim 1 wherein interaction of electrostatic and magnetic fields is set up in a pyramid.

8. The method of claim 1 wherein said interaction is producing a vortex in the space lattice.

9. The method of claim 8 wherein said vortex can be tapped to produce electric power.

10. The method of claim 9 wherein said electric power is obtained by wrapping a coil around the pyramid.

* * * * *

US 20030193319A1

(19) **United States**

(12) **Patent Application Publication** (10) **Pub. No.: US 2003/0193319 A1**

Wood et al. (43) **Pub. Date: Oct. 16, 2003**

(54) ION POWERED PLATFORM

(76) Inventors: **James Rick Wood**, Grapevine, TX (US); **Mark K. Browder**, Frisco, TX (US)

Correspondence Address:
WILLIAMS, MORGAN & AMERSON, P.C.
10333 RICHMOND, SUITE 1100
HOUSTON, TX 77042 (US)

(21) Appl. No.: **10/121,226**

(22) Filed: **Apr. 12, 2002**

Publication Classification

(51) **Int. Cl.**^{7} **H02P 9/00**
(52) **U.S. Cl.** .... 322/2 A

(57) ABSTRACT

An apparatus and method for powering a platform from an ambient electrostatic gradient are disclosed. The apparatus includes an ion powered platform comprises a platform body, an electrical load carried by the platform body; and an electrically conductive probe. The electrically conductive probe is electrically connected to the electrical load at a first point thereon and adapted to generate electrical energy from an ambient electrostatic field gradient. The electrically conductive probe extends from the electrical load such that a second point thereon is vertically displaced from the first point and on the opposite connection of the load. The method includes comprises positioning a first point on an electrically conductive probe at least a predetermined vertical distance from a second point on the electrically conductive probe at which the electrically conductive probe is electrically connected to the electrical load; initiating relative movement between an ambient atmosphere and the electrically conductive probe; and supplying energy generated by an electrical potential created by initiating the relative movement to the electrical load.





FIG. 1



FIG. 3



FIG. 2A



FIG. 2B



FIG. 2C



FIG. 2D



FIG. 2E



FIG. 2F



FIG. 4


800
810
EXTEND A FIRST POINT ON AN ELECTRICALLY CONDUCTIVE PROBE AT LEAST A PREDETERMINED VERTICAL DISTANCE FROM A SECOND POINT ON THE ELECTRICALLY CONDUCTIVE PROBE
820
INITIATE RELATIVE MOVEMENT BETWEEN THE AMBIENT ATMOSPHERE AND THE CONDUCTIVE PROBE
830
SUPPLY THE ENERGY GENERATED BY THE ELECTRICAL POTENTIAL CREATED BY INITIATING THE RELATIVE MOVEMENT TO THE ELECTRICAL LOAD

FIG. 8



FIG. 5A



FIG. 5B



FIG. 6A



FIG. 6B


700
505
305
150
405
405
110
140
405
305
150
150
305
505
505

FIG. 7A


700
505
705
150
105
305
405
140
110
405
405
105
150
305
505

FIG. 7B

ION POWERED PLATFORM

BACKGROUND OF THE INVENTION

[**0001**] 1. Field of the Invention

[**0002**] The present invention pertains to an electronic power supply, and, more particularly, to a method and apparatus for powering an electronic device from an ambient (i.e., naturally occurring, as opposed to man-made) electrostatic field gradient.

[**0003**] 2. Description of the Related Art

[**0004**] Technological advances enable ever smaller, more capable tools and devices. Electronic components continue to shrink in size while increasing the power of their applications. One example of this phenomenon is the ubiquitous microprocessor that forms the heart of the personal computer. However, the fabrication and design techniques underpinning this phenomenon are applicable to other active and passive electronic components. At the same time, electronic components are finding their way into a broader range of applications. These factors contribute to a discernible trend toward smaller, more capable, and more powerful tools and devices in many areas.

[**0005**] One factor nevertheless continues to retard this trend—power. All these electronic components require electrical power. Furthermore, their power consumption typically rises as the size decreases and the capability increases. Power is typically supplied either by a battery or through an electrical cord connected to a powered electrical grid or a generator. Batteries continue to be relatively large and heavy despite recent, significant advances in battery technology. Connection to a power grid and/or generator brings numerous limitations regarding portability and convenience arising from the umbilical/electrical cord.

[**0006**] The present invention is directed to resolving, or at least reducing, one or all of the problems mentioned above.

SUMMARY OF THE INVENTION

[**0007**] The invention includes an apparatus and method for powering a platform from an ambient electrostatic gradient.

[**0008**] Thus, in a first aspect of the invention, an ion powered platform comprises a platform body, an electrical load carried by the platform body; and an electrically conductive probe. The electrically conductive probe is electrically connected to the electrical load at a first point thereon and adapted to generate electrical energy from an ambient electrostatic field gradient. The electrically conductive probe extends from the electrical load such that a second point thereon is vertically displaced from the first point and on the opposite connection of the load.

[**0009**] In a second aspect, the invention includes a method for powering an electrical load on an ion powered platform with ions. The method comprises positioning a first point on an electrically conductive probe at least a predetermined vertical distance from a second point on the electrically conductive probe at which the electrically conductive probe is electrically connected to the electrical load; initiating relative movement between an ambient atmosphere and the electrically conductive probe; and supplying energy generated by an electrical potential created by initiating the relative movement to the electrical load.

BRIEF DESCRIPTION OF THE DRAWINGS

[**0010**] The invention may be understood by reference to the following description taken in conjunction with the accompanying drawings, in which like reference numerals identify like elements, and in which:

[**0011**] **FIG. 1** conceptually depicts, in a partially sectioned perspective view, one particular embodiment of an ion powered platform constructed in accordance with the present invention;

[**0012**] **FIG. 2A** to **FIG. 2F** depicts alternative embodiments of the electrically conductive probe of the ion powered platform of **FIG. 1** implemented in electrically conductive solids;

[**0013**] **FIG. 3** conceptually depicts an alternative embodiment in which an ionization source is located at the distal end of an electrically conductive probe;

[**0014**] **FIG. 4** conceptually depicts another alternative embodiment employing a secondary ionization source to enhance ionization efficiency;

[**0015**] **FIG. 5**A and **FIG. 5B** illustrate the operation of embodiments employing a primary ionization source and a primary and a secondary ionization source, respectively;

[**0016**] **FIG. 6A** and **FIG. 6B** conceptually depict yet another alternative embodiment in which the ion powered platform is stationary;

[**0017**] **FIG. 7**A and **FIG. 7B** conceptually depict yet another alternative embodiment in which the electrically conductive probe is implemented in an ionized fluid medium; and

[**0018**] **FIG. 8** illustrates a method practiced in accordance with one aspect of the present invention.

[**0019**] While the invention is susceptible to various modifications and alternative forms, the drawings illustrate specific embodiments herein described in detail by way of example. It should be understood, however, that the description herein of specific embodiments is not intended to limit the invention to the particular forms disclosed, but on the contrary, the intention is to cover all modifications, equivalents, and alternatives falling within the spirit and scope of the invention as defined by the appended claims.

DETAILED DESCRIPTION OF THE INVENTION

[**0020**] Illustrative embodiments of the invention are described below. In the interest of clarity, not all features of an actual implementation are described in this specification. It will of course be appreciated that in the development of any such actual embodiment, numerous implementation-specific decisions must be made to achieve the developers' specific goals, such as compliance with system-related and business-related constraints, which will vary from one implementation to another. Moreover, it will be appreciated that such a development effort, even if complex and time-consuming, would be a routine undertaking for those of ordinary skill in the art having the benefit of this disclosure.

[**0021**] **FIG. 1** conceptually illustrates, in a partially sectioned perspective view, one particular embodiment of an ion powered platform **100** constructed in accordance with the present invention. For instance, Earth's atmosphere includes an ambient electrostatic field gradient of approximately 100 to 300 volts per meter over most of Earth's surface, although this varies with, for instance, altitude and weather conditions. The ion powered platform **100** extends an electrically conductive probe **105** at least a predetermined vertical distance to utilize this electrostatic field gradient to power an electrical load **110**. The movement of the electrically conductive probe **105** through the electrostatic field gradient causes individual molecules in the atmosphere to ionize, thereby generating an electrical potential across the electrically conductive probe **105**. This electrical potential is then harnessed to power the electrical load **110**. Note that the movement of the electrically conductive probe **105** through the electrostatic field gradient is a relative movement. In other words, the atmosphere streams past the conductive probe **105**. This can result from a motive force imparted to or by the ion powered platform **100** causing it to move. Alternatively, this can result from a wind blowing across a stationary, or slow moving, electrically conductive probe **105**.

[**0022**] More particularly, the ion powered platform **100** comprises a platform body **115**, the electrical load **110** carried by the platform body **115**, and the electrically conductive probe **105**. The electrically conductive probe **105** is electrically connected to the electrical load **110** and is electrically grounded at a first point **140**. In the illustrated embodiment, the first point **140** is grounded by electrically connecting it to an electrically conductive patch **145** on the fuselage **170** of the airframe **160**. Note that, if the fuselage **170** is fabricated from an electrically conductive material, the first point **140** can be grounded at any point thereon. The electrically conductive probe **105** extends from the electrical load **110** such that a second point **150** thereon is vertically displaced from the first point **140**. The electrically conductive probe **105** is adapted to generate electrical energy from an ambient electrostatic field gradient, as is discussed further below

[**0023**] The invention admits wide variation in the implementation of the platform body **115**. In the illustrated embodiment, the platform **100** is a flying vehicle, and so the platform body **115** includes an airframe **160** to which the electrical load **110** is mounted and a fuselage **170**. Thus, the platform body **115** of the illustrated embodiment houses the electrical load **110**, but this is not necessary to the practice of the invention. The electrical load **110** may be left exposed to the ambient environment in some alternative embodiments. Indeed, the ion powered platform **100** may be implemented in alternative embodiments as, for example, a reconnaissance drone or a ground-based robotic vehicle. The ion powered platform **100** need not even be a vehicle, but might alternatively be, e.g., a container made of wood, metal, plastic, or some other material.

[**0024**] The identity of the electrical load **110** will be implementation specific. In the illustrated embodiment, the electrical load **110** is a fuse capacitor. The fuse capacitor charges with electrical energy received from the electrically conductive probe **105** at the first point **140**. When the fuse capacitor charges sufficiently, the flying submunition is armed and ready to detonate. However, the invention admits variation in the implementation of the electrical load **110** as wide as that for the ion powered platform body **115**. The electrical load **110** may be, for example, in alternative embodiments, a motor, or some high-power, short-burst communications circuitry. The motor may also be a high voltage or a low voltage motor, depending on the implementation.

[**0025**] The invention also permits wide variation in implementing the electrically conductive probe **105**. The shape and/or geometry of the electrically conductive probe **105** is not material to the practice of the invention. Alternative embodiments are illustrated in **FIG. 2A** to **FIG. 2E**. The electrically conductive probe **105** of **FIG. 1** may be, for instance:

[**0026**] an electrically conductive fiber **105***a*, as shown in **FIG. 2A**;

[**0027**] an electrically conductive ribbon **105***b*, as shown in **FIG.** 2B, for instance, woven or otherwise fabricated from electrically conductive fibers (e.g., the electrically conductive fiber **105***a*) or a flexible material coated by metal or a metallized polymer;

[**0028**] an electrically conductive rod **105***c*, as shown in **FIG.** 2C, such as a metallized glass rod;

[**0029**] an array **105***d* of electrically conductive rods (e.g., the electrically conductive rod **105***c*) ribbons (e.g., the electrically conductive ribbon **105***b*), or electrically conductive fibers (e.g, the electrically conductive fiber **105***a*) as shown in **FIG. 2D**;

[**0030**] an electrically conductive sheet **105***e*, as shown in **FIG.** 2E, fabricated from, e.g., a metal or electrically conductive composite material; or

[**0031**] an electrically conductive ring **105***f*, as shown in **FIG.** 2F, fabricated from, e.g., a metal or an electrically conductive composite material.

[**0032**] Thus, the electrically conductive probe **105** may by flexible (e.g., as are the electrically conductive fiber **105***a* and electrically conductive ribbon **105***b*) or rigid (e.g., like the electrically conductive rod **105***c* and electrically conductive sheet **105***e*). Note also that the vertical displacement between the two most vertically distant points on the electrically conductive probe **105** contributes more significantly to its operation than its actual shape and/or geometry.

[**0033**] The vertical displacement between the two most vertically distant points on the electrically conductive probe **105** will be implementation specific. The vertical displacement will primarily be a factor of the power requirements of the electrical load and the electrostatic field gradient, applied in light of commonly accepted engineering principles. For instance, as was previously mentioned, Earth's electrostatic field gradient varies from approximately 100 to approximately 300 volts per meter in fair weather and at sea level. However, these values will vary with altitude and weather—

bad weather, for example, can greatly increase the magnitude. Note that the invention may find extraterritorial application, e.g., on Venus, Mars, or Europa, whose ambient electrostatic field gradients may vary from that of Earth's. Similarly, the power requirements of the electrical load **110** may vary over time as the ion powered platform **100** enters differing operational modes. Similarly, some applications might be more tolerant of power supply faults than are other, thereby providing greater latitude in design.

[**0034**] Another important factor is the volume of ionized air. Greater volumes tend to produce a greater electrical potential. For this reason, implementations of the electrically conductive probe **105** that maximize this volume of ionized air may be generally preferred for most embodiments. The array **105***d* in **FIG. 2D** might therefore be preferred over the electrically conductive rod **105***c* in **FIG. 2C**. The electrically conductive ribbon **105***b* in **FIG. 2B** might also generally be preferred over the electrically conductive fiber **105***a* in **FIG. 2A**. However, each implementation may be different, and this principle is not universally applicable to all embodiments.

[**0035**] Still referring to **FIG. 1**, in one particular implementation, the electrically conductive element **105** is an electrically conductive fiber, or "streamer," extending from the ion powered platform **100**. The first and second points **140**, **150** are separated by 100 meters and generate a potential difference of 10,000 volts. In the illustrated embodiment, as was mentioned, this potential is used to charge a fuse capacitor in a flying submunition. However, in alternative embodiments, a high voltage capacitor could be used to, for instance, provide current to a switching circuit to create lower voltage higher current pulses adequate to run a small motor. By utilizing this larger current capability, the ability to deliver energy for useful work is made possible.

[**0036**] Design constraints may make it difficult or impractical to provide the requisite vertical displacement in some implementations. One such embodiment **300** is shown in **FIG. 3**. In these embodiments, the ionizing effect of the electrically conductive probe **105**, shown in **FIG. 1**, can be enhanced by including an ionization source **305** at the point **150** of the electrically conductive probe **105** most distal from the electrical load **110**. For embodiments where the point **140** does not contact the electrical ground **145**, the ionization source **305** may be located anywhere on the electrically conductive probe **105**, but the point **150** most distal the electrical load **110** may be used to produce enhanced results. Where the electrically conductive probe **105** is an array (e.g., the array **105***d* in **FIG. 2D**), each element of the array can include an ionization source **305** on the end thereof. The ionization source **305** contains a low level, radioactive source of alpha or beta particles encapsulated in a suitable material. Suitable alpha emitters include, but are not limited to, isotopes of Polonium and Americium (Am). Suitable beta emitters include, but are not limited to, Tritium. Suitable encapsulating materials include, but are not limited to, glass compositions such as silicate, borosilicate, aluminasilicate, and borate. In some embodiments, the point **150** can be doped with an alpha emitter or a beta emitter during manufacture.

[**0037**] Suitable alpha and beta emitters are commercially available. For instance, suitable alpha emitters are sold under the mark RadSPHERES™ by:

MO-SCI Corporation

4000 Enterprise Drive, P.O. Box 2

Rolla, Mo. 65402-0002

573-364-2338 (ph)

573-364-9589(fax)

[**0038**] Additional information is available on the World Wide Web at <http://www.thomasregister.com/olc/mo-sci-corp/radsph.htm>. The RadSPHERES™ alpha emitters are glass microspheres of encapsulated low-level radioactive materials. Alternatively, the low-level radioactive material may be encapsulated in a bar-shaped material. However, other commercially available alpha emitters and beta emitters may also be employed.

[**0039**] Some embodiments successfully employ further ionization efficiency than that provided by the ionization source **305** in **FIG. 3**. One such embodiment **400** is conceptually illustrated in **FIG. 4**. In **FIG. 4, a** second ionization source **405** is on or near the electrical load **110** on the end thereof opposite the first point **140** where the electrically conductive probe **105** is electrically connected to the electrical load **110**. The second ionization source **405** may, like the first ionization source **305**, be any suitable alpha or beta particle emitter. In the illustrated embodiments, the first and second ionization sources **305**, **405** are of the same construction and materials, but this is not necessary to the practice of the invention.

[**0040**] Turning now to **FIG. 5A** and **FIG. 5B**, in operation, the relative movement between the electrically conductive probe **105** and the ambient atmosphere, generally indicated by the arrows **500**, ionizes the air streaming past the electrically conductive probe **105**. Hence, the potential created between the first point **140** and the second point **150** on the electrically conductive probes **105**. Each ionization source **305** creates an ionization region **505**, which is a volume of air ionized by the ionization source **305** without having to stream past the electrically conductive probe **105**. The increase in the volume of ionized air increases the efficiency of the coupling to the electrostatic field gradient in the vicinity of the ionization source **305**, which includes at least a portion of the electrically conductive probe **105**. Thus, as the ionization sources **305** increase the volume of ionized air, they increase the efficiency of the coupling to the electrostatic field gradient.

[**0041**] Note that the embodiments described above contemplate that the ion powered platforms **100, 300, 400,** move relative to Earth's atmosphere. However, this is not necessary to the practice of the invention. The same effect can be achieved by placing a stationary ion powered platform in a location with air movement. Consider, for instance, the ion powered platform **600** shown in **FIG. 6A**. The ion powered platform **600** is a sensor, but is stationary. The ion powered platform **600** includes an electrically conductive probe **605** that is an array. The elements of the array **605** are rigid, and each has an ionization source **305** electrically connected to the end thereof as was described above. The ion powered platform **600** also includes an ionization source **405** on the other side of the electrical load **110**, which is a capacitor in the illustrated embodiment. **FIG. 6B** conceptually illustrates the electrical circuit of the ion powered platform **600**, first shown in **FIG. 6**A, which includes a transformer **620**. The ion powered platform **600** is then placed in an area expected to consistently experience high winds, represented by the arrow **615**. If the winds are high and consistent enough, the fuse capacitor (i.e., the electrical load **110**) will charge and the sensor (i.e., the ion powered platform **600**) may then be activated.

[**0042**] Yet another alternative embodiment **700** is illustrated in **FIG. 7**A and **FIG. 7B**. The embodiment **700** is part of a propeller-driven propulsion system for a flying vehicle not otherwise shown. The propeller **705** includes three blades **710**. The number of blades **710** is immaterial to the practice of the invention. Each blade **710** is doped at the distal end **715** thereof to produce a primary ionization source **305**. Each primary ionization source **305** generates an ionization region **505** as described above relative to the embodiment **500** shown in **FIG. 5**. The embodiment **700** also includes a secondary ionization source **405**. The electrical load **110** in this embodiment is a motor for driving the propeller **705**. The motor may be, for example, a surface acoustic wave linear motor, an ultrasonic motor, or an electrostatic motor, depending on the implementation.

[**0043**] The embodiment **700** is launched from another flying vehicle, and so is moving relative to the atmosphere. As is best shown in **FIG. 7**B, the atmosphere streams past the primary ionization sources **305** on the distal ends **715** of the blades **710** and through the ionization regions **505**, as represented by the arrows **720**. The ionized atmosphere completes an electrical circuit between the first point **140** (i.e., the electrical ground) on the ring **725** and the second points **150** on the distal ends **715**. Thus, the electrically conductive probe **105** in this embodiment is implemented in an ionized fluid medium as opposed to an electrically conductive solid.

[**0044**] Thus, the invention includes, in another aspect, a method **800**, illustrated in **FIG. 8**, for powering an electrical load (e.g., the electrical load **110** in **FIG. 1**) on a ion powered platform (e.g., the ion powered platforms **100**, **300**, **400**, **600**, in **FIG. 1**, **FIG. 3**, **FIG. 4**, and **FIG. 6**A, respectively) with ions. The method **800** begins by extending a first point on an electrically conductive probe at least a predetermined vertical distance from a second point on the electrically conductive probe at which the electrically conductive probe is electrically connected to the electrical load (at **810**). This extension may occur during fabrication, between fabrication and deployment, or after deployment. Next, the method **800** initiates relative movement between the ambient atmosphere and the electrically conductive probe (at **820**). Note that the movement is relative. As is apparent from the discussion above, the relative to some fixed point, the ion powered platform may move through the atmosphere, the atmosphere may move over the ion powered platform, or both the ion powered platform and atmosphere may move. Finally, the method **800** supplies the energy generated by the electrical potential created by initiating the relative movement to the electrical load (at **830**).

[**0045**] This concludes the detailed description. The particular embodiments disclosed above are illustrative only, as the invention may be modified and practiced in different but equivalent manners apparent to those skilled in the art having the benefit of the teachings herein. Furthermore, no limitations are intended to the details of construction or design herein shown, other than as described in the claims below. It is therefore evident that the particular embodiments disclosed above may be altered or modified and all such variations are considered within the scope and spirit of the invention. Accordingly, the protection sought herein is as set forth in the claims below.

What is claimed:

1. An ion powered platform, comprising:

a platform body;

an electrical load carried by the platform body; and

an electrically conductive probe electrically connected to the electrical load at a first point thereon and adapted to generate electrical energy from an ambient electrostatic field gradient, the electrically conductive probe extending from the electrical load such that a second point thereon is vertically displaced from the first point and on the opposite connection of the load.

2. The ion powered platform of claim 1, further comprising an ionization source electrically coupled to the second end of the probe.

3. The ion powered platform of claim 2, wherein the ionization source comprises one of an alpha-particle emitter and a beta-particle emitter.

4. The ion powered platform of claim 3, wherein the alpha-particle emitter includes one of Polonium and Americium.

5. The ion powered platform of claim 4, wherein the Polonium or Americium is encapsulated in one of silicate, borosilicate, aluminasilicate, and borate.

6. The ion powered platform of claim 3, wherein the beta-particle emitter includes Tritium.

7. The ion powered platform of claim 2, further comprising a second ionization source affixed to the electrical load at a third point on the electrical load distal from the first point.

8. The ion powered platform of claim 7, wherein the second ionization source comprises one of an alpha-particle emitter and a beta-particle emitter.

9. The ion powered platform of claim 8, wherein the alpha-particle emitter includes one of Polonium and Americium.

10. The ion powered platform of claim 9, wherein the Polonium or Americium is encapsulated in one of silicate, borosilicate, aluminasilicate, and borate.

11. The ion powered platform of claim 8, wherein the beta-particle emitter includes Tritium.

12. The ion powered platform of claim 1, wherein the electrically conductive probe comprises one of a fiber, a ribbon, a rod, a ring, and a sheet.

13. The ion powered platform of claim 12, wherein the fiber comprises an electrically conductive carbon filament.

14. The ion powered platform of claim 13, wherein at least one of the ribbon, the rod, the ring, and the sheet comprises a plurality of electrically conductive carbon filaments, a metallized glass, a metal coating, or a metallized polymer.

15. The ion powered platform of claim 1, wherein the electrically conductive probe comprises

a first ionization source;

a second ionization source; and

an ionized fluid medium between the first and second ionization sources.

16. The ion powered platform of claim 15, wherein at least one of first and second ionization sources comprises one of an alpha-particle emitter and a beta-particle emitter.

17. The ion powered platform of claim 16, wherein the alpha-particle emitter includes one of Polonium and Americium.

18. The ion powered platform of claim 17, wherein the Polonium or Americium is encapsulated in one of silicate, borosilicate, aluminasilicate, and borate.

19. The ion powered platform of claim 16, wherein the beta-particle emitter includes Tritium.

20. An ion powered platform, comprising:

a platform body;

an electrical load carried by the platform body; and

means for generating electrical energy from an ambient electrostatic field gradient.

21. The ion powered platform of claim 20, further comprising a first means for ionizing a region of air, the ionizing means being electrically coupled to the generating means.

22. The ion powered platform of claim 21, wherein the ionizing means comprises one of means for emitting alpha-particles and means for emitting beta-particles.

23. The ion powered platform of claim 21, further comprising second means for ionizing a region of air electrically coupled to the generating means.

24. The ion powered platform of claim 20, wherein the generating means comprises one of a fiber, a ribbon, a rod, a ring, and a sheet.

25. The ion powered platform of claim 20, wherein the generating means comprises:

first means for ionizing a region of air;

second means for ionizing a region of air; and

an ionized fluid medium between the first and second ionizing means.

26. A method for powering an electrical load on an ion powered platform with ions, comprising:

positioning a first point on an electrically conductive probe at least a predetermined vertical distance from a second point on the electrically conductive probe at which the electrically conductive probe is electrically connected to the electrical load;

initiating relative movement between an ambient atmosphere and the electrically conductive probe; and

supplying energy generated by an electrical potential created by initiating the relative movement to the electrical load.

27. The method of claim 26, further comprising providing an ionization source as the first point.

28. The method of claim 27, further comprising providing a second ionization source on the side of the electrical load opposite the second point.

29. The method of claim 26, further comprising providing an ionization source on the side of the electrical load opposite the second point.

30. The method of claim 26, wherein extending the first point on the electrically conductive probe at least the predetermined vertical distance from the second point includes extending on deployment of the ion powered platform.

31. The method of claim 26, wherein extending the first point on the electrically conductive probe at least the predetermined vertical distance from the second point includes extending on manufacture of the ion powered platform.

32. The method of claim 26, wherein initiating the relative movement includes placing the ion powered platform in motion.

33. The method of claim 26, wherein initiating the relative movement includes deploying the ion powered platform in expectation of a desirable wind pattern.

* * * * *

US 20080191580A1

(19) **United States**
(12) **Patent Application Publication**
Deyo
(10) **Pub. No.: US 2008/0191580 A1**
(43) **Pub. Date: Aug. 14, 2008**

(54) HARMONIC ENERGY EXCHANGE DEVICE

(76) Inventor: **Harold Stanley Deyo**, Pueblo West, CO (US)

Correspondence Address:
HAROLD S DEYO, JR.
241 S. DOS PALOS DRIVE
PUEBLO WEST, CO 81007

(21) Appl. No.: **11/675,060**

(22) Filed: **Feb. 14, 2007**

Publication Classification

(51) **Int. Cl.**
H02N 11/00 (2006.01)
(52) **U.S. Cl.** **310/300**

(57) ABSTRACT

This invention converts inertial impulses into electric currents. Specifically, it converts impulses created by the impacts of high-energy particles from the Sun and other cosmic sources into the Earth's Magnetosphere and the varying D, E, F1 and F2 layers of its Ionosphere to controlled electric currents. This invention presents a new method of utilizing energy from the Sun and other sources of high energy articles as a virtually, inexhaustible, alternative-energy source for the world.





FIGURE 1


13
14
12
2
1
3
4
5
6
10
11
7
9
8

FIGURE 2


SOLAR WIND DIRECTION
OUTER VAN ALLEN BELT
OUTER LAYERS
22
INNER VAN ALLEN BELT
F-LAYERS IONOSPHERE
E-LAYER IONOSPHERE
D-LAYER IONOSPHERE
MESOSPHERE
STRATOSPHERE
EARTH
23
TROPOSPHERE
21
EARTH SURFACE
MAGNETOSPHERE
INNER VAN ALLEN BELT
OUTER VAN ALLEN BELT

FIGURE 3




2
1
3
4
5
6
10
11
9
7
8

HARMONIC ENERGY EXCHANGE DEVICE

BACKGROUND OF THE INVENTION

[0001] 1. Field of Invention

[0002] This invention relates to the conversion of impact energies created by the collision of high-speed cosmic particles and electromagnetic radiations with "Earth's Outer Layers" to produce inertial waves in the dielectric Troposphere which are subsequently converted into electricity by this invention.

[0003] The term "Earth's Outer Layers" refers to: Earth's Magnetosphere, Van Allen Belts, Ionosphere, Mesosphere, and Stratosphere as illustrated in FIG. **2**

[0004] 2. Description of the Prior Art

[0005] One day while reading an old scientific magazine I saw a small article on the research of Dr. John Trump of MIT (the basis for an electrostatic generator patented later by Onezime P. Breaux in U.S. Pat. No. 4,127,804). The article talked about a series of experiments which Dr. Trump had performed with a 2-plate, capacitor in a vacuum dielectric. Briefly, he discovered that by varying the distance between the two plates one could produce current flows in one direction or the other between either of the plates and ground.

[0006] The Solar Wind strikes "Earth's Outer Layers" constantly as do many other cosmic particles. At any given instant of time, the vector product of these impacts produces either a net pressure increase or decrease in the Troposphere. This creates random waves of pressure in the "Earth's Outer Layers" as one charged "plate" moves in relation to the oppositely-charged Earth's surface as the other "plate". This variation of pressure in the "Earth's Outer Layers" is equivalent to moving an outer "plate" back and forth toward the Troposphere and the Earth's surface as the inner "plate"—thus giving rise to variations in voltage on both "plates". In this case the Troposphere (see FIG. **2**) acts as the dielectric medium instead of the vacuum in the Trump experiments. Furthermore, the Troposphere, itself, is also compressed and decompressed by these random waves of pressure on the "Earth's Outer Layers". Thus, I reasoned if one could create a charged envelope or field of sufficient voltage within the Troposphere, one could convert these random pressure waves in the dielectric Troposphere into current flow on the Earth's surface.

[0007] As "Earth's Outer Layers" surround the planet, any impact waves propagate throughout all of them when they are present—even to the nighttime side of the planet. Thus, I also reasoned one could extract power from these impacts anywhere on Earth's surface or in its atmosphere whether it be day or night. The pressure waves on the dark side of Earth would be less energetic than those occurring on the daytime side because the nighttime layers of the Ionosphere are compressed so much that the D-Layer of the Ionosphere disappears at night and the F1 and F2-Layers of the Ionosphere combine into one F-Layer. I calculated the available energy from these impact waves would be significantly less by 30-45% depending upon one's location on the night side of the planet in respect to the terminator.

[0008] Many years ago around 1900 Dr Nikola Tesla built and tested a device to extract energy from the Sun using an apparatus which forms part of my own invention (see U.S. Pat. Nos. 685,957 an 685,958 dated 5 Nov. 1901).

[0009] Subsequently, Dr. Thomas Henry Moray, another inventor and student of these Tesla patents made a device which apparently accessed the same source of energy but with a method different than my own. As Dr. Moray was never granted a patent for his device I cannot be certain that his work is considered prior art but I list it here as part of my due diligence. Apparently, he had trouble explaining the source of energy his device was converting to the patent reviewer and was, thus, not granted a patent for his impressive work. Dr. Moray's public disclosure of certain aspects of his invention are public knowledge through his published lectures and his book, "The Sea of Energy in Which the Earth Floats'—published in 1931.

[0010] Since the beginning of the 20th Century mankind has been looking for new sources of electric power to feed the ever-increasing energy demands of the human population. In the last half of the 19th Century coal, whale oil, human and animal labor, moving water, wind and wood were main sources of energy. However, in the first quarter of the 20th Century mankind began to use more electricity produced by hydroelectric generators and other generators producing electricity by combustion of fossil fuels. With increasing use of gasoline engines and the increasing use of electrical appliances the demand for electricity accelerated the addition of heat and greenhouse gases into the Earth's ecosystem.

[0011] In the last half of the 20th Century many forward-thinking individuals began looking for alternate energy sources to reduce the emissions of greenhouse gases. All of the alternate energy systems investigated and/or developed in the last 56 years have had significant drawbacks to their usage as the main energy supply for the needs of humanity.

[0012] Some of those alternate energy systems were nowhere near as efficient as the existing systems. Some of the alternate energy systems still introduced extra heat into the environment like the existing fossil fuel and nuclear energy systems. And, yet, others produced even more greenhouse gases than the existing energy systems. Some of the new systems used food resources to produce combustible fuels which, consequently, reduced the food resources of the planet. Among the leaders in the new energy sources was and is nuclear energy which produces extra heat, toxic wastes and materials which can be used in nuclear weapons. Hydroelectric energy sources do not add heat to the ecosystem but they are not an inexhaustible resource as they depend upon rainfall which is diminishing as global warming increases. Wind energy resources do not add heat to the ecosystem but they are not constant and require expensive conversion and storage equipment.

[0013] The ideal energy source for mankind will not add heat to the planet's ecosystem, will not produce by-product green house gases; will not deplete our food and water resources; will not produce toxic wastes; however, it will be portable, self-replenishing and constantly available in real time anywhere on Earth and in useful quantities.

[0014] Our major source of natural energy on Earth is the Sun. Energy from the Sun enters the Earth's ecosphere by particle bombardment, radiated electromagnetic energy, gravitational variations and magnetic processes. Mankind has developed various methods of capturing energy from the Sun already. Silicon-based solar cells convert light in a narrow bandwidth into electron flows. These cells are—at most—only 50% efficient and only work when the Sun is shining on them and at an optimum angle. Wind turbines only work when there is wind to power them and are—for the most part—not portable. Devices to convert wave action in the oceans only work when there are waves created by the wind and tidal effects caused by gravitational variations; and they are not portable enough to be used in common transportation devices.

[0015] I concluded if mankind could find an inexpensive method of obtaining electricity from the Sun in some form that worked both day and night and which was already flowing into the Earth's ecosystem, we might be able to develop a clean and self-replenishing energy source which would add no extra heat to our ecosystem, would not alter our planetary albedo and might well be made in a portable form.

SUMMARY OF THE INVENTION

[0016] The Harmonic Energy Exchange Device (or "HEED") offers an interim solution to Earth's dwindling fossil fuel resources. It utilizes a previously untapped energy resource which exists throughout the known Universe. By the very nature of the invention, it only interrupts the flow of energy from the Sun and all the other cosmic sources of high-energy particles on their normal journey to the Earth by way of The Outer Layers.

[0017] The invention does not add energy to the normal thermodynamic equilibrium of the planet and its associated outer layers. The invention does not produce wastes—toxic or otherwise. It does not produce harmful gases; and in some embodiments it could even assist in the rebuilding of our thinning ozone shield. Use of this invention will eventually remove mankind's dependence on fossil fuels and create new occupations. It will be cheap enough that homeowners will be able to install their own HEED and sell back energy to the grid until such time as every home has their own HEED and civilization has completely weaned itself from the use of fossil fuels and nuclear energy in its current form.

BRIEF DESCRIPTION OF DRAWING

[0018] FIG. **1**: Is the preferred embodiment of the circuit diagram of my invention incorporating references to external stimuli which are used to activate the circuit. It represents a parallel tuned circuit to store the energy.

[0019] FIG. **2**: Is an illustration of the Earth and it immediate environment as a global capacitor where The Outer Layers form one plate and the Earth's surface form the other plate and both are separated by the Troposphere as a dielectric medium.

[0020] FIG. **3**: Is an alternate embodiment of the circuit diagram of my invention incorporating references to external stimuli which are used to activate the circuit. It represents the use of a series tuned circuit to store the energy.

DETAILED DESCRIPTION OF A PREFERRED EMBODIMENT OF THE INVENTION

[0021] Be it known that I, Harold Stanley Deyo, Jr, a citizen of both The United States of America and The Commonwealth of Australia, residing in the community of Pueblo West in Pueblo County, Colorado have invented an Harmonic Energy Exchange Device which converts dynamic pressures in the ambient media around Earth to controlled electric currents.

[0022] This invention as represented in FIG. **1** is unique in that it is designed to extract electricity from random pressure waves propagated in the Troposphere **14** by impacts of the solar wind and other cosmic particles with the Earth's "The Outer Layers" **22** of FIG. **2**.

[0023] In FIG. **1**, the Troposphere **14** in its rest state is represented by the line of "+" marks **14**. The convergent or compression state **12** of the random waves in the Troposphere **14** is represented by the lower line of dots while the divergent or decompression state **13** of the random waves in the Troposphere **14** is represented by the upper line of dots. The preferred embodiment of my invention FIG. **1** is a method of coupling a parallel, resonant, electrical circuit to these random pressure waves to extract electricity from them.

[0024] As Dr John Trump's research and Onezime P. Breaux's U.S. Pat. No. 4,127,804 show, when one plate of a charged capacitor is moved closer to or farther from the other plate of that capacitor a voltage change appears on both plates of that capacitor. Furthermore, the electric field gradient between those plates changes as the plates are moved in this manner. Thus they have described a method of converting mechanical energy into electrical current by simply varying the plate spacing over time which can be expressed as ds/dt where "ds" is the change in spacing and "dt" is the change in time.

[0025] As illustrated in FIG. **2**, The Outer Layers can be viewed as one plate of a capacitor comprised of the Earth's surface itself as one plate **21** and Earth's outer layers as the other plate **22** where the Earth's Troposphere **23** serves as the dielectric medium separating the two plates. There is a charge between these plates which varies extremely rapidly but not with a constant period. At any given instant, the vector product of all the impacts by the cosmic particles with The Outer Layers **22** will create a pressure wave in The Outer Layers **22** which will manifest in the Troposphere **23**. Whatever that vector product is, it will alter the field gradient in the dielectric Troposphere **23**. That alteration will either increase or decrease the effective spacing between "plates" **22** and **23**.

[0026] In order to capture and convert the resulting voltage variations produced at or near the Earth's surface **21** of FIG. **2**, this invention creates its own, localized stress field **3** of FIG. **1** established in the Troposphere **23** of FIG. **2** with a charged, conductive surface **1** of FIG. **1** which is encased in high-voltage insulation **2** of FIG. **1** and extending into the Troposphere **23** of FIG. **2**.

[0027] In FIG. **1**, a series of high-voltage, starting pulses is applied across points **4** and **6** on opposite sides of a capacitor **5** to create the localized stress field **3**. As these high-voltage starting pulses are applied, the parallel resonant circuit formed by inductor coil **7** and variable capacitor **11** both referenced to ground **8** is stimulated into resonance within the bandwidth determined by the values of these circuit components. Tuning of this circuit is effected through variable capacitor **11**. The high voltage charge on conductive surface **1** of FIG. **1** is maintained by the parallel tuned circuit formed by inductor coil **7** and variable capacitor **11**.

[0028] Then as the random, pressure waves propagate throughout the Troposphere **23** of FIG. **2**, the localized stress field **3** of FIG. **1** is oscillated by the compression wave front **12** and the decompression wave front **13**—both of FIG. **1** which creates voltage changes on capacitor **5**.

[0029] In FIG. **1**, the resulting voltages changes on capacitor **5** will add energy to the parallel resonant circuit formed by inductor coil **7** and variable capacitor **11** which acts as a tank circuit to store the energy which has been passed to it. As energy builds in the parallel circuit the voltage of the circuit rises until a spark discharge occurs across the gap **9** also referenced to ground **8**. The current will only discharge in one direction as determined by diode **10**. The circuit will work without diode **10** but a diode is used here as one method to keep from draining all the energy from the tank circuit when a discharge occurs.

[0030] This resonant circuit can be tuned to various bandwidths to maximize the efficiency of the conversion process depending upon location of the device, time of day, temperature variations, relative humidity and other variables in the ambient Troposphere **23** of FIG. **2** around the conductive surface **1** of FIG. **1**. A resistive load to extract power from the resonant circuit can be used instead of the spark gap **9** of FIG. **1**.

[0031] This preferred embodiment uses a parallel, tuned circuit to access a wide range of frequencies usually to be found in the range of 4.5 to 7 MHz. This range encompasses the major, naturally-occurring, resonant frequencies found in the ionosphere.

[0032] A second embodiment of this invention as shown in FIG. **3** replaces the parallel tuned circuit formed by inductor coil **7** and variable capacitor **11** in FIG. **1** placed in parallel to each other and referenced to ground **8** in FIG. **1**. This second embodiment forms a series tuned circuit formed by inductor coil **7** and variable capacitor **11** in FIG. **3** placed in series to each other and referenced to ground **8** of FIG. **3**. It differs from the preferred embodiment only in the placement of variable capacitor **11** of FIG. **3** so that it is in series with coil **7** of FIG. **3**.

[0033] This embodiment limits the frequency range and, hence, the energy the system will store when compared to the preferred embodiment. It produces higher voltages across the spark gap **9** of FIG. **3** than those produced in the preferred embodiment across the spark gap **9** of FIG. **1**.

1. An apparatus for coupling to the pressure waves created in the Earth's Magnetosphere and the varying D, E, F1 and F2 layers of its Ionosphere by the impacts of various high-energy particles from both our Sun and other cosmic sources.

2. An electrical circuit for harmonically converting the pressure waves described in claim (**1**) into periodic electric current discharges.

* * * * *

US 20120286623A1

(19) **United States**

(12) **Patent Application Publication** (10) **Pub. No.: US 2012/0286623 A1**

Ogram (43) **Pub. Date: Nov. 15, 2012**

(54) **ATMOSPHERIC ENERGY COLLECTION**

(75) Inventor: **Mark E. Ogram**, Tucson, AZ (US)

(73) Assignee: **Sefe, Inc.**, Tempe, AZ (US)

(21) Appl. No.: **13/103,963**

(22) Filed: **May 9, 2011**

Publication Classification

(51) **Int. Cl.**
H02N 3/00 (2006.01)

(52) **U.S. Cl.** **310/309**

(57) **ABSTRACT**

The subject matter described herein is an atmospheric energy collector. The atmospheric energy collector includes of a windsock arrangement that has a large up-wind opening on one side and that tapers from the larger up-wind opening on the one side to a small down-wind opening on the other side. The up-wind side is secured to a tether such that an electrically conducting material (e.g. metal) included in construction of the atmospheric energy collector is connected to the tether. The windsock arrangement is extended outwards by wind and the like atmospheric conditions such that the electrically conducting material collects the atmospheric energy and transfers the collected energy to the tether.




100
106
102
118
104
110
114
114
112
116
WIND

FIG. 1A



FIG. 1B


160
162
134
132

FIG. 1C


206
204
202
208

FIG. 2



FIG. 3B


300
306
304
302

FIG. 3A


402
DC-IN
404
406
DC-AC
408
GRID

FIG. 4A


402
DC-IN
404
408
STEP DOWN TRANSFORMER
410
412
GROUND

FIG. 4B


402
DC-IN
414
416
DC-OUT

FIG. 4C


106
102
118
104
110
114
114
112
116
WIND
502
504
500

FIG. 5


602
Is it windy?
Yes
604
Wind-sock stretched outward by the wind to collect atmospheric electricity
606
Is current within predetermined range?
No
608
Adjust height of wind-sock by using adjusting mechanism

FIG. 6

ATMOSPHERIC ENERGY COLLECTION

TECHNICAL FIELD

[0001] The subject matter described herein relates to a light-weight, extendible electricity collecting windsock arrangement comprising an enhanced collection surface for atmospheric electrical energy collection.

BACKGROUND

[0002] The atmosphere above the earth is known to include electrical charge. The earth's surface is negatively charged, while the air above it is positively charged. All atmospheric effects are a result of an interplay between these two huge areas of opposite electrical energy. The potential difference between the positively charged atmosphere and the negatively charged earth surface causes atmospheric electrical energy to be developed. Some of this atmospheric electrical energy may be experienced through thunderstorms.

[0003] Even though there is a huge amount of atmospheric electrical energy in the atmosphere, collection of the atmospheric electrical energy still remains a problem. Due to high voltage and low current conditions, there is a need for large collection surfaces for maximizing the collection of atmospheric electrical energy. Note that the terms atmospheric electricity, atmospheric energy, and atmospheric electrical energy have been used interchangeably in this specification.

[0004] The problem of low current is compounded by a heavy weight of the collectors of atmospheric electrical energy. The heavy weight of the collectors increases payload requirements of a lift mechanism, which may be used to lift the collectors to an appropriate height or altitude so that the collection of atmospheric electrical energy is maximized. Thus, a need exists for large yet light-weight collectors such that payload requirements for the lift mechanism remain reasonable.

SUMMARY

[0005] The subject matter described herein relates to an atmospheric energy collector. The atmospheric energy collector includes an electricity collecting windsock arrangement that has a large up-wind opening on one side and that tapers from the larger up-wind opening on the one side to a small down-wind opening on the other side. The up-wind side is secured to a tether such that an electrically conducting material (e.g. metal) included in construction of the atmospheric energy collector is connected to the tether. The electricity collecting windsock arrangement is extended outwards by wind and the like atmospheric conditions such that the electrically conducting material collects the atmospheric energy and transfers the collected energy to the tether. Further, the electricity collecting windsock includes light-weight collectors such that payload requirements for the lift mechanism remain reasonable (i.e. remain within a predetermined value).

[0006] In one aspect, an electricity collection apparatus includes a tether and a windsock. The windsock is formed of an insulation material with a metal deposited on at least a portion of the insulation material. The metal of the windsock is electrically connected to the tether. The windsock extends in a direction of ambient wind to provide a surface area based on the ambient wind, and the surface area provides the metal to collect electrical energy from the ambient wind, the collected electrical energy being transferred to the tether.

[0007] In another aspect, an electricity collection apparatus includes a windsock formed of an insulation material the windsock to extend in a direction of ambient wind to provide a surface area based on the ambient wind. The apparatus further includes one or more electrical conductors provided on at least a portion of the insulation material to collect electrical energy from the ambient wind. The apparatus further includes an electrically conductive tether connected with windsock to anchor the windsock in the direction of the ambient wind, the electrically conductive tether being electrically connected to the one or more electrical conductors provided on at least a portion of the insulation material to transfer the collected electrical energy from the one or more electrical conductors to an electrical storage.

[0008] The subject matter described herein provides many advantages. For example, large collection surfaces allow a maximized collection of atmospheric energy. Moreover, the light-weight collectors allow payload requirements for the lift mechanism to remain reasonable (i.e. remain within a predetermined value).

[0009] The details of one or more variations of the subject matter described herein are set forth in the accompanying drawings and the description below. Other features and advantages of the subject matter described herein will be apparent from the description and drawings, and from the claims.

DESCRIPTION OF DRAWINGS

[0010] The accompanying drawings, which are incorporated in and constitute a part of this specification, show certain aspects of the subject matter disclosed herein and, together with the description, help explain some of the principles associated with the disclosed implementations. In the drawings,

[0011] FIG. **1**A illustrates extendible electricity collecting windsock arrangement that is used for collection of atmospheric electrical energy in accordance with implementations of the current subject matter;

[0012] FIG. **1**B illustrates a cross-section of one implementation of the electrically conducting windsock in accordance with implementations of the current subject matter;

[0013] FIG. **1**C illustrates a cross-section of another implementation of the electricity collecting windsock in accordance with implementations of the current subject matter;

[0014] FIG. **2** illustrates an exemplary conductive line in accordance with implementations of the current subject matter;

[0015] FIG. **3**A illustrates a front view of a conductive line in accordance with implementations of the current subject matter;

[0016] FIG. **3**B illustrates a top view of the conductive line shown in FIG. **3** in accordance with implementations of the current subject matter;

[0017] FIGS. **4**A, **4**B, and **4**C illustrate electrical schematics for handling the static charge from the atmosphere in accordance with implementations of the current subject matter;

[0018] FIG. **5** illustrates an adjusting apparatus (winch motor and spool) that enables adjustment of location/height of the electricity collecting windsock arrangement in accordance with implementations of the current subject matter; and

[0019] FIG. **6** is a process flow diagram illustrating aspects of a method in accordance with implementations of the current subject matter.

[0020] When practical, similar reference numbers denote similar structures, features, or elements.

DETAILED DESCRIPTION

[0021] To address these and potentially other issues with currently available solutions, one or more implementations of the current subject matter provide methods, systems, articles or manufacture, and the like that can, among other possible advantages, provide an energy collector formed as a windsock and having an enhanced collection surface for atmospheric electrical energy collection. In preferred implementations, an electricity collecting windsock is formed as a flexible cylinder, a truncated cone, or a cone with a metal surface, and is mounted to a mast or other tether so as to capture ambient wind which extends the windsock outward from the mast, in turn forming the largest possible surface area for the wind conditions to enable the metal surface to collect atmospheric amperage. The collected amperage is transferred from the metal surface of the electricity collecting windsock to the mast or tether, and eventually to an electricity storage device. Although implementations in which windsock arrangements having one windsock each are discussed below, those or ordinary skill in the art understand that a windsock arrangement may include two or more windsocks for enhanced atmospheric electricity collection.

[0022] FIG. **1**A illustrates an implementation of electricity collecting windsock arrangement **100** that is used to collect atmospheric electrical energy. The electricity collecting windsock arrangement **100** includes an extendible electricity collecting windsock **102**. The extendible electricity collecting windsock **102** is made of a material that has a high tensile strength and provides electrical insulation. This electrically insulating material **134** (discussed below with respect to FIG. **1**B) may be a plastic or a flexible glass, such as polyester like polyethylene terephthalate (PET) or biaxially-oriented polyethylene terephthalate (BoPET). BoPET is known in the industry by different trade names, some of which are Mylar, Melinex and Hostaphan.

[0023] As is described later with respect to FIGS. **1**B and **1**C, which illustrate cross-sections of implementations of electricity collecting windsock **102**, a thin coat of an electrically conducting material **132**, **162** is deposited on the electrically insulating material **134**. The deposited electrically conducting material **132**, **162** is a good conductor of electricity, and helps electricity collecting windsock **102** to tap atmospheric electrical energy. The electrically conducting material may be any one of a metal or a suitable alloy, such as one of or a combination of one or more of gold, silver, copper, aluminum, and the like.

[0024] The electricity collecting windsock **102** has a large up-wind opening up-wind opening **104** on one side. The electricity collecting windsock **102** tapers from the large up-wind opening **104** on the one side to a small down-wind opening **106** on the other side of the electricity collecting windsock **102**. The up-wind opening **104** has a metal loop **110** on the circumference of the up-wind opening **104**. The metal loop **110** is attached to a tether **112** using an attachment mechanism **114**. The attachment mechanism **114** may include a soldering mechanism. In some implementations, other attachment mechanisms **114** are also known to be used, such as nut and bolt mechanism, threading mechanism, gluing mechanism, and the like. The electricity collecting windsock **102** is extended outwards by wind **116** and/or like atmospheric conditions such that the electrically conducting material (e.g. metal) collects the atmospheric electrical energy and transfers the collected energy to the tether **112**.

[0025] The tether **112** includes a conductive line that is isolated from the ground. The conductive line is used to transfer the collected atmospheric electrical energy from the electricity collecting windsock **102** to an electricity storage device (not shown) where the collected atmospheric charge may be gathered for later or simultaneous use.

[0026] When wind **116** strikes against the electricity collecting windsock arrangement **100** in the direction illustrated, the electricity collecting windsock **102** extends outward, thus allowing the electrically conducting material **132** (discussed below with respect to FIG. **1**B) to collect maximum possible atmospheric electricity. In one implementation, the outward extension **118** is fifty feet or more. When there is no wind, the electricity collecting windsock **102** may be in a relatively compressed state such that the length of the electricity collecting windsock **102** is less than the outward extension **118** caused by windy conditions or like atmospheric conditions. The collected atmospheric electrical energy is communicated to the tether **112**.

[0027] FIG. **1**B illustrates a cross-section **130** of one implementation of the electrically conducting windsock **102**. The cross-section **130** illustrates the electrically conducting material **132** deposited on the inner surface of the electrically insulating material **134**. The electricity collecting windsock **102** includes the electrically conducting material **132** and the electrically insulating material **134** such that the electrically conducting material **132** forms the inner surface of the electricity collecting windsock **102**. When the wind **116** strikes the electricity collecting windsock arrangement, the electricity collecting windsock **102** extends outward, thus allowing the electrically conducting material **132** to collect maximum possible atmospheric electricity. The electrically conducting material **132** may include multiple collectors that are spaced apart such that the collection surface is greatly enhanced. The multiple collectors may be spaced apart in patterns, such as spaced apart lines, squares, rectangles, circles, and the like, or any other pattern that may maximize the collection of the atmospheric electrical energy. As noted above, the electrically insulating material **134** may be a plastic or a flexible glass, such as polyester like polyethylene terephthalate (PET) or biaxially-oriented polyethylene terephthalate (BoPET). The electrically conducting material **132** may be a metal or alloy, such as one of or a combination of one or more of gold, silver, copper, aluminum, and the like.

[0028] FIG. **1**C illustrates a cross-section **160** of another implementation of the electricity collecting windsock **102**. The electrically conducting material (e.g. metal deposit) **132**, **162** may be placed on both sides of the electrically insulating material **134** such that the collection ability is increased even further. Multiple collectors are implemented and are spaced apart on electrically conducting material **132**, **162** such that the collection surface is greatly enhanced. The multiple collectors may form one or more patterns, as noted above with respect to FIG. **1**B. Furthermore, the electrically insulating material **134** (e.g. mylar) used in the electricity collecting windsock **102** is light, thereby minimizing the overall weight of the electricity collecting windsock **102** and reducing the weight for payload calculations. The electrically conducting materials **132**, **162** may be an electrically conducting metal or alloy, such as one of or a combination of at least one of gold, copper, aluminum, silver, and the like. The electrically conducting materials **132**, **162** may be made of the same metal/alloy or a different metal/alloy.

[0029] The electrically conducting materials **132**, **162** may be attached to the electrically insulating material **134** by a gluing mechanism. In some implementations, other attachment mechanisms are known to be implemented, such as paint coating mechanism, a threading mechanism, a nut and bolt mechanism, soldering mechanism, and the like. The attachment mechanism between the electrically conducting material **132** and the electrically insulating material **134** may or may not be the same as the attachment mechanism between the electrically conducting material **162** and the electrically insulating material **134**.

[0030] FIG. **2** illustrates an exemplary conductive line in accordance with one implementation. This type of conductive line is commonly referred to as poly-wire. The conductive line consists of multiple interwoven strands of plastic **202** and **204** woven into a cord or rope arrangement having intertwined therein exposed metal wires **206** and **208**. Although FIG. **2** illustrates two plastic strands and two metal wires, any number of possible combinations of plastic strands and metal wires is possible. The exposed metal wires **206** and **208** attract the atmospheric static charge and transmit the charge down to the electricity storage device (not shown).

[0031] FIG. **3**A illustrates a front view of a conductive line **300** in accordance with another implementation. FIG. **3**B illustrates a top view of the conductive line **300** illustrated in FIG. **3**. The conductive line **300** creates an ionized pathway for the flow of the static charges from the atmosphere to the electricity storage device via the electricity collecting windsock arrangement **100**. This conductive line utilizes a tube **302** having an outer layer **304** of PET Film (Biaxially-oriented polyethylene terephtalate polyester film). The tube **302** provides exceptionally high tensile strength and is chemically and dimensionally stable. In one implementation, the tube **302** may have an ideal diameter of between two and three inches. An interior metal coating **306** provides an initial conduit for the flow of static charge. The static charge through the metal may force the tube **302** to expand due to the repulsion experienced by like charges. Further, the flow of electricity causes the interior of the tube **302** to become ionized to provide an additional pathway for the atmospheric static charges to the electricity storage device (not shown).

[0032] FIGS. **4**A, **4**B, and **4**C illustrate electrical schematics for handling the static charge from the atmosphere. By maintaining the voltage being collected in a prescribed range, an electrical conversion system is easily designed. While FIGS. **4**A, **4**B, and **4**C illustrate some electrical configurations, those of ordinary skill in the art readily recognize a variety of other configurations that may serve the same function.

[0033] Referencing FIG. **4**A, Direct Current In (DC IN) **402** is buffered by a gang of capacitors **404** before being communicated to a DC/AC converter **406**. The DC/AC converter converts the direct current into alternating current suitable for placement over an existing electrical grid **408** such as normally found from a power-plant. Those of ordinary skill in the art readily recognize a variety of DC/AC converters that may work in this capacity.

[0034] FIG. **4**B illustrates an electrical arrangement suitable for use in charging a battery. DC IN **402** is buffered by capacitor bank **404** before entering into a step down transformer **408**. Step down transformer **408** reduces the voltage so that the voltage can safely be introduced into battery **410**, which is connected to ground **412** at the battery's other pole. Those of ordinary skill in the art readily recognize a variety of batteries that may work in this capacity.

[0035] In FIG. **4**C, DC IN **402** is fed into an adjustable rheostat **414**, which is controlled by the controller so that the DC OUT **416** falls within a specified range.

[0036] FIG. **5** illustrates an adjusting apparatus **500** that enables adjustment of height of the electricity collecting windsock arrangement **100** in accordance with one implementation. As per one implementation, the height of the electricity collecting windsock **102** can be adjusted using a winch motor **502** and a spool **504**. The winch motor **502** and the spool **504** can release or withdraw the tether **112** to adjust the height of the electricity collecting windsock **102** that is connected to the tether **112**. In one implementation, this release and the withdrawal may be performed manually. In another implementation, this release and the withdrawal may be performed automatically based on information obtained from a sensor system that measures atmospheric electrical energy being collected per unit time. If the sensor indicates that a current flow is diminishing, then the tether **112** is released/extended from the spool **504** to increase the altitude of the electricity collecting windsock **102** such that more static charge from the atmosphere is gathered. If the sensor indicates that collected atmospheric electrical energy exceeds a preset level per unit time, the tether **112** is withdrawn onto the spool **504** to decrease the static charge being collected from the atmosphere.

[0037] FIG. **6** is a process flow diagram illustrating aspects of a method consistent with implementations of the current subject matter. At step **602**, the functioning of the electricity collecting windsock arrangement **100** depends on whether atmospheric conditions are windy. If the atmospheric conditions are windy, the wind **116** stretches/extends outward the electricity collecting windsock **102**—Step **604**. Next, it is determined whether the atmospheric electrical energy (atmospheric current) that is collected is in a predetermined range—Step **606**. If the collected atmospheric electrical energy is in the predetermined range, the flow goes back to step **604**. If the current is not in the predetermined range, the height of the electricity collecting windsock **102** may be adjusted using adjusting apparatus **500**, such as the winch motor **502** and spool **504**. One skilled in the art understands that other implementations may include any other adjusting apparatus **500**, such as a pulley, a wheel mechanism, or the like.

[0038] The implementations set forth in the foregoing description do not represent all implementations consistent with the subject matter described herein. Instead, they are merely some examples consistent with aspects related to the described subject matter. Although a few variations have been described in detail herein, other modifications or additions are possible. In particular, further features and/or variations can be provided in addition to those set forth herein. For example, the implementations described above can be directed to various combinations and sub-combinations of the disclosed features and/or combinations and sub-combinations of one or more features further to those disclosed herein. In addition, the logic flows depicted in the accompanying figures and/or described herein do not necessarily require the particular order shown, or sequential order, to achieve desirable results. The scope of the following claims may include other implementations or embodiments.

What is claimed is:

1. An electricity collection apparatus comprising:

a tether; and

a windsock formed of an insulation material with a metal deposited on at least a portion of the insulation material, the metal of the windsock being electrically connected to the tether, the windsock to extend in a direction of ambient wind to provide a surface area based on the ambient wind, the surface area providing the metal to collect electrical energy from the ambient wind, the collected electrical energy being transferred to the tether.

2. The apparatus in accordance with claim **1**, wherein the metal is deposited on at least one of opposite sides of the insulation material.

3. The apparatus in accordance with claim **2**, wherein the metal is a metal selected from a group of metals comprising gold, silver, copper and aluminum.

4. The apparatus in accordance with claim **1**, wherein the insulation material is a polyester film.

5. The apparatus in accordance with claim **1**, wherein the transferred electrical energy at the tether is further transferred from the tether to an electricity storage device.

6. The apparatus in accordance with claim **1**, wherein the metal comprises conductors that are light-weight thereby allowing payload requirements for adjusting the windsock to an optimum location to be within a predetermined value, the optimum location comprising a height of the windsock from ground level.

7. The apparatus in accordance with claim **6**, wherein the deposited metal conductors form a pattern that maximizes the collection of the electrical energy at the optimum location.

8. An electricity collection apparatus comprising:

a windsock formed of an insulation material having a metal deposited on at least a portion of the insulation material, the windsock to extend in a direction of ambient wind to provide a surface area based on the ambient wind, the surface area providing the metal to collect electrical energy from the ambient wind; and

an electrically conductive tether connected with windsock to anchor the windsock in the direction of the ambient wind, the electrically conductive tether being electrically connected to the metal of the insulation material, the collected electrical energy being transferred to the tether.

9. The apparatus in accordance with claim **8**, wherein the metal is deposited on at least one of opposite sides of the insulation material.

10. The apparatus in accordance with claim **9**, wherein the metal is a metal selected from a group of metals comprising gold, silver, copper and aluminum.

11. The apparatus in accordance with claim **8**, wherein the insulation material is a polyester film.

12. The apparatus in accordance with claim **8**, wherein the transferred electrical energy at the tether is further transferred from the tether to an electricity storage device.

13. The apparatus in accordance with claim **8**, wherein the metal comprises conductors that are light-weight thereby allowing payload requirements for adjusting the windsock to an optimum location to be within a predetermined value, the optimum location comprising a height of the windsock from ground level.

14. The apparatus in accordance with claim **13**, wherein the metal conductors form a pattern that maximizes the collection of the electrical energy at the optimum location.

15. An electricity collection apparatus comprising:

a windsock formed of an insulation material the windsock to extend in a direction of ambient wind to provide a surface area based on the ambient wind;

one or more electrical conductors provided on at least a portion of the insulation material to collect electrical energy from the ambient wind; and

an electrically conductive tether connected with windsock to anchor the windsock in the direction of the ambient wind, the electrically conductive tether being electrically connected to the one or more electrical conductors provided on at least a portion of the insulation material to transfer the collected electrical energy from the one or more electrical conductors to an electrical storage.

* * * * *

US 20150102676A1

(19) **United States**

(12) **Patent Application Publication** (10) **Pub. No.: US 2015/0102676 A1**

Dinwiddie et al. (43) **Pub. Date: Apr. 16, 2015**

(54) **METHOD AND APPARATUS FOR EXTRACTING AND CONVEYING ELECTRICAL ENERGY FROM THE EARTH'S IONOSPHERE CAVITY**

(71) Applicant: **Earth Energies, Inc.**, Johns Creek, GA (US)

(72) Inventors: **John Dinwiddie**, Cary, NC (US); **Terry L. Wright**, Suwanee, GA (US)

(21) Appl. No.: **14/509,846**

(22) Filed: **Oct. 8, 2014**

Related U.S. Application Data

(60) Provisional application No. 61/889,894, filed on Oct. 11, 2013.

Publication Classification

(51) **Int. Cl.**
H01F 38/14 (2006.01)

(52) **U.S. Cl.**
CPC ***H01F 38/14*** (2013.01); *H01F 2038/146* (2013.01)

(57) **ABSTRACT**

The system and apparatus of one or more embodiments of the present invention extracts, conditions, and conveys electric power from the earth ionosphere cavity through the integrated and collaborative operation of the system and apparatus consisting of a capacitively-coupled insulated elevated terminal (coupled capacitor upper plate), an evacuated spark gap, an integrated step-down transformer and resonant capacitor, and a ground terminal (coupled capacitor lower plate). The architecture governing exemplary embodiments of the system and apparatus of the present invention emulates the natural architecture governing the interaction of living trees with the electrical energy resident in the earth ionosphere cavity. The implementation of such exemplary embodiments of the present invention utilizes standard and customized components appropriate for their function within the system and apparatus.

The extracted electric power from the earth ionosphere cavity manifests in the form of broadband electromagnetic waves in the 0 to 200 Hz frequency range. Electric energy from these waves produce magnetic fields inside the integrated step-down transformer which are added together by the primary coil of the integrated step-down transformer, and delivered as 60 Hz 120/240 VAC to an electric load via the secondary coil of the integrated step-down transformer resonating at 60 Hz due to the influence of the integrated resonant capacitor.

The system and apparatus of exemplary embodiments of the present invention extracts, conditions, and conveys ionosphere cavity-resident electric power in alternating current and direct current realms.


10
E-field
Insulated
.1 – 14 Hz AC ULF (Lightning Generated) 22
Tesla coil or other biasing will accelerate recharge rate (fast recharge)
Instantaneous electrical current drawn to spark gap; Inhibited from CUP as voltage rises on transformer side and extinguishes spark; CUP begins recharging
Capacitor Reaches Threshold & Fires (Slow Discharge)
Capacitor Upper Plate (CUP) (Elevated Terminal)
12
Develops High Voltage Charge Relative to Ground Voltage
Hoping to replace with solid state relay
Evacuated Spark Gap
Spark Triggers
Step-Down Transformers 28
Parallel Resonant Transformer Primary & Secondary Coils 16
Capacitor @ 60 Hz 18
Capacitor drain rate, spark gap extinguishing from voltage rise, integrated resonant transformer/ capacitor, and biasing will be balanced to suit application
Electric Load (home)
*5 kW, 60 Hz, 120/240 VAC
Ultra High Instantaneous Current
14
Capacitor Lower Plate (CLP) (Ground Terminal)
Broadband ULF Current (pump)
Resonant Transformer & Capacitor Continue to Ring @ 60 Hz (16 & 18)
See Drawing 2 (44, 46, 48,58, 54)
Ground
Earth
See Drawing 2 (52)
*5 kW preferred embodiment
100 kW alternative embodiment
35,000 kW alternative embodiment
Copyright 2013
Earth Energies, Inc.
Proprietary & Confidential
Earth Energies, Inc.


10
E-field
Insulated
.1 – 14 Hz AC ULF (Lightning Generated) 22
Tesla coil or other biasing will accelerate recharge rate (fast recharge)
Instantaneous electrical current drawn to spark gap; inhibited from CUP as voltage rises on transformer side and extinguishes spark; CUP begins recharging
Capacitor Upper Plate (CUP) (Elevated Terminal) 12
Capacitor Reaches Threshold & Fires (Slow Discharge)
Develops High Voltage Charge Relative to Ground Voltage
Hoping to replace with solid state relay
Evacuated Spark Gap
Spark: Triggers
Step-Down Transformers 28
Parallel Resonant Transformer Primary & Secondary Coils 16
Capacitor @ 60 Hz 18
Capacitor drain rate, spark gap extinguishing from voltage rise, integrated resonant transformer/ capacitor, and biasing will be balanced to suit application
Electric Load (home)
*5 kW, 60 Hz, 120/240 VAC
Ultra High Instantaneous Current
14
Capacitor Lower Plate (CLP) (Ground Terminal)
Broadband ULF Current (pump)
Resonant Transformer & Capacitor Continue to Ring @ 60 Hz (16 & 18)
See Drawing 2 (44, 46, 48,58, 54)
Ground
Earth
See Drawing 2 (52)
*5 kW preferred embodiment
300 kW alternative embodiment
30,000 kW alternative embodiment
Copyright 2013
Earth Energies, Inc.
Proprietary & Confidential
Earth Energies, Inc.

FIG. 1


As Inserted
42 (4)
56
40
44
After
Deployed
Bezel
Anchor
Slots (4)
50
Spool View
Inside Bezel
Blow-up
48
46
Bezel Ground Wire
Escapa Portals Holes
with Wire end
exposed (X)
54
Cut-away
View
(Installed)
Bezel Threads
58
Bezel External View
52
(Y)
Ground Terminal Optimizer Apparatus for Lower Coupled
Capacitor Plate (Ground Terminal)
Copyright 2013
Earth Energies, Inc.
Proprietary & Confidential
Earth Energies, Inc.

FIG. 2

METHOD AND APPARATUS FOR EXTRACTING AND CONVEYING ELECTRICAL ENERGY FROM THE EARTH'S IONOSPHERE CAVITY

[0001] This application claims benefit of U.S. Provisional Application No. 61/889894, filed 11 Oct. 2013, titled, "Method and Apparatus for Extracting and Conveying Electrical Energy From the Earth's Ionosphere Cavity," the disclosure of which is incorporated herein by reference in its entirety.

BACKGROUND OF THE INVENTION

[0002] A portion of the disclosure of this patent document contains material which is subject to copyright protection. The copyright owner has no objection to the facsimile reproduction by any-one of the patent document or the patent disclosure, as it appears in the Patent and Trademark Office patent file or records, but otherwise reserves all copyright whatsoever.

[0003] The invention is an apparatus and methodology for extracting electric power manifesting as a broadband collection of electric field oscillations in the 0 to 200 Hz frequency range within the Earth's ionosphere cavity, through the use of an elevated biased hemispherical or other curved surface capacitor coupling the ionosphere cavity and Earth, and then conveying this electrical energy at the proper frequency, amperage, and voltage to existing homes and buildings where it is delivered for consumption over existing home or building wiring.

DESCRIPTION OF THE RELATED ART

[0004] The current state of the art in this field is focused on the bending of radio frequency waves in the Earth's ionosphere cavity for the purpose of distorting (through reflection) the resident cavity's magnetic field to physically direct the stimulating electrical energy to targeted locations within the Earth's ionosphere cavity and/or coordinates on the Earth's surface at specific energy levels appropriate to specific applications. The regenerative feedback was done by Sutton's active antenna.

[0005] Nikola Tesla attempted to transmit wireless power in the "natural medium"; however, Tesla bad no description of a device to receive natural oscillations as described in the present disclosure.

[0006] There is no known prior art in the field of electric energy extraction from the ionosphere cavity and conveyance to other terminals within the cavity for delivery of usable electric power.

SUMMARY OF THE INVENTION

[0007] In one exemplary embodiment of the present invention, a properly-scaled electric power extraction/conveyance apparatus is installed at a typical consumer residential home to deliver 60 Hz 120/240 VAC electric power, sufficient to convey the equivalent of 5 kW of continuous electricity, to the home's existing electric service entry component to power electrical appliances in the home over existing home electric wiring.

[0008] In another exemplary embodiment of the present invention, a properly-scaled electric power extraction/conveyance apparatus is installed at an appropriate location within an industrial park or neighborhood to deliver 60 Hz 120/240 V AC electric power, sufficient to convey the equivalent of 300 kW of continuous electricity, to the service entry components of industrial buildings or neighborhood homes to power electrical devices and appliances over existing building or home electric wiring.

[0009] Alternative exemplary embodiments of the present invention will extract direct current electric power from the Earth ionosphere cavity, generated by the earth's rotating magnetosphere, and convey in the form of conditioned direct current to direct current load sources, or convert to alternating current and convey in the form of conditioned alternating current to alternating current load sources.

BRIEF DESCRIPTION OF THE DRAWINGS

[0010] A disclosure embodiments of the present invention, is set forth more particularly in the remainder of the specification, which makes reference to the accompanying figures, in which:

[0011] FIG. **1** provides an example of an electric power extraction and conveyance apparatus for one residential-scale embodiment of the present invention. Certain additional example embodiments of the present invention utilize similar fundamental technologies, but differ in the scale (size) of the components and characteristics of the electricity conveyed for consumption; and

[0012] FIG. **2** is a schematic illustration of ground terminals for use with embodiments of the present invention.

DETAILED DESCRIPTION

[0013] Applicant has discovered that trees extract and use electric power from the Earth ionosphere cavity. The present invention emulates the architecture of electric power extraction and usage methodology inherent in the natural operation of living trees, but uses standard and customized components, common in the field, for its implementation. The natural electric power extraction and use of electric power by trees leverages the shape and physical composition of trees as instances of large electrical capacitors coupled to the ionosphere cavity. The canopy of trees (upper limbs and leaf structures) emulates the upper plates of a coupled capacitor, the trunks of trees emulate a combined dielectric and resonant transformer/capacitor, and the root systems of trees emulate ground terminals (lower coupled capacitor plates). The extraction of electric power from the ionosphere cavity by trees is in the form of ultra-low frequency broadband waves (oscillations) in the frequency range of 0.1 to 14 Hertz (ULF). Inherent tree physical composition and control structure (i.e., DNA/RNA) govern the use of the extracted electric power to accomplish tree growth, seasonal metabolic adjustments, and reproductive processes. Any excess extracted electric power by trees is returned to the ionosphere cavity. The present invention is an exemplary instance of this same natural architecture using standard and customized components that facilitate extraction and conveyance of ionosphere cavity-resident broadband electric power at useful scales sufficient to provide continuous electrical power for electrical devices used by people.

[0014] One preferred exemplary embodiment of the present invention is in the form shown in Drawing **1** above and will deliver continuous 60 Hz 120/240 V AC electric power to consumer residences (and other structures with similar electricity conditioning and consumption requirements) equivalent to electric power capacity of 5 kilowatts.

[0015] A secondary exemplary embodiment of the present invention is also in the form shown in FIG. **1**, appropriately scaled for larger electrical power demands and related conveyance capacity, and will deliver continuous 60 Hz 120/240 V AC electric power to larger buildings or electrical distribution facilities for commercial office parks with electric power capacity of 300 kilowatts.

[0016] A third exemplary embodiment of the present invention is also in the form shown in FIG. **1**, appropriately scaled for larger electrical power capacity, and will deliver continuous 60 Hz 120/240 VAC electric power to utility substations with electric power capacity of 30,000 kilowatts (or higher).

[0017] The following system, power sources, and component descriptions provide additional details of the present invention in various embodiments.

[0018] Earth's ionosphere cavity (**10**) is a reservoir of continuously-generated electrical energy (E-Field) in both direct current (DC) and alternating current (AC) realms. The DC electric energy is created by the constant rotation of the Earth's magnetosphere exposed to the solar wind. Earth's perpetually moving magnetic fields create the DC electric power in the ionosphere cavity E-Field per the equations in James Clerk Maxwell's fundamental theory of electromagnetism. AC electrical energy in the ionosphere cavity is generated from the persistent E-Field disturbances (i. e., oscillations) caused by lightning discharges. The present invention includes the direct extraction of AC electric power from the ionosphere cavity, and the direct extraction of DC electric power from the ionosphere cavity which is converted to AC electric power before conveyance. Optional operational configurations of the present invention will also enable conveyance of extracted DC electric power for potential scenarios where the conveyance of conditioned DC electricity is required.

[0019] Electric-field oscillations (**22**) are induced by lightning and encapsulated in the earth-ionosphere cavity, creating a continuous source of renewable electrical energy. The frequency of lightning occurrences in the ionosphere cavity averages thirty (30) strikes per second, with each strike representing approximately one (1) terawatt (TW) of instantaneous energy. Assuming an average energy dissipation rate for each lightning strike of fifteen (15) microseconds (μsec), i. e., the time involved for one (1) terawatt of instantaneous energy to dissipate to zero (0) energy, these lightning-induced electric field oscillations are sufficient to provide 4,500 times the entire electric energy consumption on planet Earth at the projected consumption rate for the year 2100 (55.3 TWh annually). Lightning-induced E-Field oscillations vary between 0.1 and 14 Hertz with wavelengths exceeding the practicality of an electromagnetic antenna for collecting the energy. The present invention utilizes capacitive coupling to overcome this obstacle.

[0020] An insulated upper capacitor plate (terminal) (12) elevated above the influence of the ground floor collects E-Field oscillations from the ionosphere cavity. This insulated elevated terminal, capacitively-coupled to the E-Field bounded by the earth-ionosphere cavity, is arranged in a surface of large radii of curvature, supporting maximum surface connection to the E-Field without leaking the high voltage charge applied to the elevated terminal. The capacitance and resistance of the elevated terminal are responsive to the reception of broadband electric-field frequencies in the 0 to 200 hertz range. The elevated terminal is subject to high voltage alternating current biasing used to collect electric-field oscillations generated by lightning impulses in the earth-ionosphere cavity.

[0021] An evacuated spark gap (**24**) connected to the elevated terminal (**12**) prevents electrical discharge occurring between the elevated terminal and the ionosphere cavity. As the high voltage alternating current approaches peak voltage the spark gap energizes and a large voltage is applied to the step-down transformer primary coil (**16**). The high voltage pumps high current from the ground terminal (**14**, **26**) converting the electric-field to a magnetic field within the transformer (**16**). The step-down transformer is connected to a 60 hertz resonant capacitor (**18**), the secondary side of the transformer resonating at 60 hertz will supply a 60 hertz 120/240 VAC power to the load. Filter circuits will condition the power. The evacuated spark gap function may be accomplished by solid state circuitry in the implementation of the present invention.

[0022] The resonant transformer (**16**) is integrated with a parallel resonant capacitor across the transformer where the integrated combination resonates at 60 hertz supplying power to the electricity consuming structure (home or business). Various step-down transformers (**28**) are utilized to condition the conveyed electricity to accommodate the requirements of the receiving station for various embodiments of the present invention.

[0023] Ground (**26**) is the source of electric current for the present invention. A ground terminal, connected to the soil, is arranged in a surface of large radii of curvature to permit instantaneous sourcing of high currents from earth ground without temperature and voltage rise inhibiting the ground terminal collection of current. The capacitance and resistance of the ground terminal to earth is minimized to promote on demand current sourcing. Drawing **2** illustrates an exemplary apparatus of the present invention that optimizes ground connection quality by maximizing the penetration extent and resulting surface area of the ground terminal's extension into the soil.

[0024] Step-down transformers (**28**) are scaled to transform the electrical current and voltage into structured and conditioned electricity that is compatible with the electric power needs of the load sources for various embodiments of the present invention.

[0025] A mechanical nut (**40**) solidly attached to shaft **44** to facilitate extension, when turned, of large gauge copper wire extrusions (**46**).

[0026] A downward pointed anchor flat shaft (**42**) attached to the bezel **50** via a T-slot in bezel.

[0027] A copper (or other highly-conductive metal) spool base (**44**) sourcing "X" independently attached large gauge pointed copper wires (**46**) of length "Y", where "X" is equal to the number of escape portals in bezel (**50**), and "Y" is the length determined to yield optimum surface area of wires of type **46** for high quality connectivity to soil. The spool can freely rotate inside the bezel (**48**) and emulates the primary root structure of a living tree.

[0028] Sharpened large gauge (reinforced) copper wires (**46**), quantity "X", of length "Y" emulating the root structure of living trees.

[0029] Threaded bezel (spool-housing sleeve) (**48**) with drilled escape portal holes with end of copper wires (**46**) protruding through holes ½ inch.

[0030] Bezel anchor slots (**50**) of twice the height of anchor flat shafts (**42**) and T-slotted to accommodate anchor flat shafts.

[0031] Extended pointed end (**52**) of inner spool base shaft.

[0032] Escape portals (**54**) in bezel to allow for large gauge copper wire (**46**) extension into soil.

[0033] Connector port (**56**) for connection to ground terminal (**14**) in Drawing **1**.

[0034] Bezel threads (**58**).

[0035] Various embodiments of the present invention will include one or more of the following characteristics in various combinations. These descriptions are provided for purposes of example. Not all of the following characteristics will be required for any given exemplary embodiment.

[0036] Characteristic 1, The form (shape), physical composition, size, insulation, location altitude, discharge capacitive threshold and discharge rate, and the strength of AC or DC biasing applied to the (CUP) upper coupled capacitor plate (**12**: elevated terminal) all form an integrated whole, the purpose of which is to extract and temporarily store DC or AC electric power from the Earth's ionosphere cavity (**10**) at high voltage, and to trigger the energizing of the evacuated spark gap (**24**).

[0037] Characteristic 2, The elevated terminal (**12**) is capacitively coupled to the E-Field (**10**) bounded by the earth ionosphere cavity, and arranged in a surface of large radii of curvature, supporting maximum surface connection to the E-Field without leaking the high voltage charge applied to the elevated terminal (**12**).

[0038] Characteristic 3, The capacitance and resistance of the elevated terminal (**12**) are responsive to the reception of broadband electric-field frequencies in the 0 to 200 hertz range.

[0039] Characteristic 4, The elevated terminal (**12**) is subject to high voltage alternating current biasing used to collect E-Field oscillations generated by lightning impulses in the earth-ionosphere cavity.

[0040] Characteristic 5, An alternative instantiation of elevated terminal (**12**) is subject to high voltage direct current biasing used to collect E-Field direct current generated by the Earth's rotating magnetosphere.

[0041] Characteristic 6, The evacuated spark gap (**24**) may be in the form of a cohesive physical spark ignition or an operational emulation of this function through solid state circuitry.

[0042] Characteristic 7, The evacuated spark gap (**24**) connected to the elevated terminal (**12**) prevents electrical discharge occurring between the elevated terminal and the ionosphere cavity.

[0043] Characteristic 8, The high voltage alternating current from the E-Field, induced into the elevated terminal (**12**), approaches peak voltage and causes the evacuated spark gap (**24**) to energize and a large voltage is applied to the step-down transformer primary coil (**16**).

[0044] Characteristic 9, The high voltage alternating current impulse from the elevated terminal (**12**), which causes the evacuated spark gap (**24**) to energize, manifests as alternating current on broadband frequencies between 0.1 and 200 Hz.

[0045] Characteristic 10, In an alternative instantiation of the elevated terminal (**12**) the stored high voltage direct current, which causes the evacuated spark gap (**24**) to energize, manifests as direct current on broadband frequencies between 0 and 200 Hz.

[0046] Characteristic 11, The high voltage applied to the step-down transformer primary coil (**16**) pumps high current from the ground terminal (**14**), converting the electric-field to a magnetic field within the transformer (**16**).

[0047] Characteristic 12, The high current pumped from the ground terminal (**14**), caused by high voltage applied to the step-down transformer primary coil (**16**), will attempt to normalize the field and extinguish the evacuated spark gap (**24**).

[0048] Characteristic 13, The transformer's (**16**) magnetic field expands in response to the high current electric-field inrush from the ground terminal (**14**).

[0049] Characteristic 14, The primary winding inside the step-down transformer (**16**) will add the energy from each broadband frequency together into a single magnetic field, where it will become a 60 Hz frequency at the secondary winding of the transformer (**16**).

[0050] Characteristic 15, The step-down transformer (**16**) is connected to a 60 Hertz resonant capacitor (**18**).

[0051] Characteristic 16, The secondary (coil) side of the step-down transformer (**16**), resonating at 60 hertz, will supply a 60 hertz 120/240 VAC power to the electric load.

[0052] Characteristic 17, Filter circuits within the step-down transformer will condition the power according to the electric power needs of the electric load.

[0053] Characteristic 18, Electric-field lines exist (within the Earth's ionosphere cavity) that are horizontal to the surface of the Earth and extend to heights above 30,000 feet, with voltage gradients typically 100 Volts per vertical meter.

[0054] Characteristic 19, Lightning impulses create global broadband oscillations in the Earth ionosphere cavity electric-field between 0.1 and 14 Hertz.

[0055] Characteristic 20, Rotation of the Earth's magnetosphere creates global electric field oscillations in the Earth ionosphere cavity that manifest as electromagnetic waves in the 0 to 200 Hertz frequency range.

[0056] Characteristic 21, Global broadband oscillations in the Earth ionosphere cavity electric-field can be used for wireless energy transmission without harm to people, plants, or trees.

[0057] Characteristic 22, A maximum quality ground connection is achieved by expanding the surface area of the ground connection (**48** and **44**) through extension of high-conductor large gauge copper wires (**46**) horizontally through bezel (**48**) escape portals (**54**) along depth of source spool (**44**) and bezel (**48**).

[0058] Characteristic 23, The technique described in Characteristic 22 effectively expands the diameter of the ground source spool (**44**) with regard to quality of ground connection.

[0059] Characteristic 24, Bezel threads (**58**) expand surface area of bezel (**48**) touching earth, enhancing ground connection quality.

[0060] Characteristic 25, Bezel threads (**58**) enhance ground connection quality of bezel (**48**), source spool (**44**), and high conductor large gauge copper wires (**46**) through rotational insertion and resulting friction hold v. other (direct drive) insertion methods which can result in corruption of ground hole integrity caused by imprecise angle and/or vibration during insertion.

[0061] While one or more embodiments of the present invention have been described above, it should be understood that any and all equivalent realizations of the present invention are included within the scope and spirit thereof. Thus, the embodiments presented herein are by way of example only

and are not intended as limitations of the present invention. Therefore, it is contemplated that any and all such embodiments are included in the present invention.

What is claimed is:

1. A power receiver for extracting electrical energy from the earth's electric field, said power receiver comprising:

a resonant transformer connected between a ground terminal disposed below the surface of the earth and an elevated terminal;

impulse generator for generating and applying a high voltage electrical impulse to a primary winding of the resonant transformer to induce current flow from the ground terminal through the primary winding of the transformer; and

a power conversion circuit connected to a secondary winding of the resonant transformer to convert electrical current flowing through the secondary winding to a desired form.

2. The power receiver of claim **1** wherein a resonant frequency of the resonant transformer is below 200 Hz.

3. The power receiver of claim **1** wherein the elevated terminal comprises an upper capacitive plate coupled to the earth's ionosphere cavity.

4. The power receiver of claim **3** wherein the impulse generator comprises:

the upper capacitive plate;

a pair of electrodes separated by a spark gap, said electrodes connected between the upper capacitive plate and the primary winding of the resonant transformer and configured to generate a spark when a voltage difference between the electrodes reaches a predetermined level.

5. The power receiver of claim **1** further comprising a lower capacitive plate coupled to the ground terminal.

6. The power receiver of claim **1** wherein the resonant transformer comprises a capacitor connected in parallel with a primary winding of the resonant transformer.

* * * * *

US 20170117714A1

(19) **United States**
(12) **Patent Application Publication**
Dinwiddie et al.
(10) **Pub. No.: US 2017/0117714 A1**
(43) **Pub. Date: Apr. 27, 2017**

(54) **POWER RECEIVER FOR EXTRACTING POWER FROM ELECTRIC FIELD ENERGY IN THE EARTH**

(71) Applicant: **Earth Energies, Inc.**, Johns Creek, GA (US)

(72) Inventors: **John Dinwiddie**, Cary, NC (US); **Terry L. Wright**, Suwanee, GA (US); **David R. Ames**, Johns Creek, GA (US)

(21) Appl. No.: **15/397,281**

(22) Filed: **Jan. 3, 2017**

Related U.S. Application Data

(63) Continuation-in-part of application No. 14/509,772, filed on Oct. 8, 2014, now Pat. No. 9,564,268.

(60) Provisional application No. 61/889,894, filed on Oct. 11, 2013.

Publication Classification

(51) **Int. Cl.**

H02J 4/00	(2006.01)
H02J 7/35	(2006.01)
H02J 3/38	(2006.01)

(52) **U.S. Cl.**
CPC *H02J 4/00* (2013.01); *H02J 3/385* (2013.01); *H02J 7/35* (2013.01)

(57) **ABSTRACT**

A resonant transformer connected between a ground terminal and elevated terminal draws current from the earth's electric field through a primary winding of the transformer. An impulse generator applies a high voltage impulse to the primary winding of the resonant transformer to cause current to flow from the ground terminal through the primary winding. The flow of current through the primary winding of the resonant transformer induces a current in the secondary winding, which may be converted and filtered to a usable form, e.g. 60 Hz AC or DC.




POWER
CONVERTER
60 Hz
OR
DC
L

FIG 1


IMPULSE GENERATOR
POWER CONVERTER 60 Hz OR DC
L

FIG 2


IMPULSE GENERATOR
POWER CONVERTER 60 Hz OR DC
L

FIG 3


65
70
DO
GND
7.83 HZ
BATT +
75
1Ω
.05 μF
60
80
BATT-
15
50
0.01 μF
10
95
100
105
90
35
55
40
115
30
45
25
120
1000 μ F
125
+
INPUT
MPPT
CHARGE
CONTROLLER
LOAD
-
+
-
BATT +
BATT -
130
110
135
INVERTER
120V 60 HERTZ
OUT

FIG 4


IMPULSE GENERATOR
POWER CONVERTER 60 Hz AC OR DC
L

FIG 5


200
235
225
220
230
215
240
205
210

FIG 6A


200
215
235
210

FIG 6B


200
215
235
210
220

FIG 6C



FIG 7A



FIG 7B



FIG 7C

POWER RECEIVER FOR EXTRACTING POWER FROM ELECTRIC FIELD ENERGY IN THE EARTH

[0001] This application is a continuation-in-part of prior U.S. application Ser. No. 14/509772 filed 8 Oct. 2014 which claims the benefit of U.S. Provisional Application No. 61/889894 filed 11 Oct. 2013, the disclosures of all of which are incorporated by reference herein in their entirety.

TECHNICAL FIELD

[0002] The present invention relates generally to renewable energy, and more particularly to methods and apparatus for extracting energy from subsurface electrical fields beneath the earth's surface.

BACKGROUND

[0003] The earth and the ionosphere cavity may be viewed as a global electric circuit. Electrical currents are constantly flowing within the earth and its atmosphere. Within the earth, the majority of the earth's energy is carried by extremely low frequency (ELF) and ultralow frequency (ULF) waves in the 0-200 Hz frequency range. The earth's rotating magnetic field and positive lightning are two energy sources that sustain the ELF/ULF waves within the earth and the atmosphere.

[0004] A great deal of research has been devoted to studying the electric field present in the earth's ionosphere cavity. Joseph M. Crawley, the "Fair Weather Atmosphere as a Power Source", Proceedings ESA Annual Meeting on Electrostatics 2011; O. Jefimenko, "Operation of Electric Motors from Atmospheric Electric Field," American Journal of Physics, Vol. 39, Pgs. 776-779, 1971; M. L. Breuer, "Usability of Tapping Atmospheric Charge as a Power Source," Renewable Energy, Vol. 28, Pgs. 1121-1127, 2003. Numerous attempts have been made in the past to extract electrical energy from the earth's atmosphere. For example, U.S. Pat. No. 1,540,998 to Plauson describes a system for converting atmospheric electrical energy into usable power. These past attempts have been successful in producing only small amounts of power from the electrical field in the earth's ionosphere cavity. The modest success of these experiments compared to results from other renewable energy sources, such as solar and wind, has tempered further research and prevented widespread use of the electric field in the ionosphere cavity as an energy source.

SUMMARY

[0005] The present invention relates to a power receiver for extracting power from electric fields beneath the earth's surface. In embodiments of the present disclosure, a resonant transformer connected to a ground terminal draws current from the earth's electric field through the primary winding of the transformer. Current flow through the resonant transformer is induced by applying a high voltage impulse to the primary winding. The flow of current through the primary winding of the resonant transformer induces a current in the secondary winding, which may be converted and filtered to a usable form, e.g. 60 Hz AC or DC.

[0006] In some embodiments of the power receiver, the resonant frequency of the resonant transformers is below 200 Hz.

[0007] In some embodiments of the power receiver, the resonant transformer comprises a ferro-resonant transformer.

[0008] In some embodiments, the power receiver further comprises an elevated terminal.

[0009] In some embodiments of the power receiver, the primary winding of the resonant transformer is connected between the ground terminal and elevated terminal.

[0010] In some embodiments of the power receiver, the elevated terminal comprises an upper capacitive plate coupled to the earth's ionosphere cavity.

[0011] In some embodiments of the power receiver, the impulse generator comprises the upper capacitive plate and a spark gap connected between the upper capacitive plate and the primary winding of the resonant transformer. The spark gap comprises a pair of electrodes separated by a gap and configured to generate a spark when a voltage difference between the electrodes reaches a predetermined level.

[0012] In some embodiments of the power receiver, the impulse generator comprises a pulse generator for generating low voltage pulses, a step-up transformer for converting the low voltage pulses provided by the pulse generator to high voltage impulses, and a spark gap connected between the step-up transformer and the primary winding of the resonant transformer to generate a spark responsive to the high voltage impulses from the step-up transformer.

[0013] In some embodiments of the power receiver, the impulse generator comprises a pulse generator for generating low voltage pulses, and a step-up transformer connected to the primary winding of the resonant transformer for converting the low voltage pulses provided by the pulse generator to high voltage impulses.

[0014] In some embodiments of the power receiver, the impulse generator comprises a solid state spark generator.

[0015] In some embodiments of the power receiver, the resonant transformer includes a capacitor connected in parallel with the primary winding.

[0016] In some embodiments of the power receiver, the resonant transformer includes a capacitor connected in series with the primary winding between the impulse generator and the elevated terminal.

[0017] In some embodiments, the power receiver comprises multiple resonant transformers having primary windings connected in parallel between the ground terminal and the elevated terminal.

[0018] In some embodiments of the power receiver, the resonant transformers have different resonant frequencies.

[0019] In some embodiments of the power receiver, the resonant frequencies of the resonant transformers are all below 200 Hz.

[0020] In some embodiments of the power receiver, the resonant frequencies of the resonant transformers are matched to respective Schumann resonances.

[0021] Another embodiment of the power receiver comprises a resonant circuit connected to a ground terminal disposed below the surface of the earth, an impulse generator for generating and applying a high voltage electrical impulse to the resonant circuit to induce current flow from the ground terminal through the resonant circuit, and a power conversion circuit connected to the resonant circuit to convert electrical current flowing through the resonant circuit to a desired form. The resonant circuit has a resonant frequency below 200 Hertz.

[0022] In some embodiments of the power receiver, the resonant circuit comprises a resonant transformer having a primary winding, a secondary winding, and resonant capacitor connected in series with the primary winding.

[0023] In some embodiments of the power receiver, the resonant circuit comprises multiple resonant transformers having primary windings connected in parallel to the ground terminal.

[0024] In some embodiments of the power receiver, the resonant transformers have different resonant frequencies.

[0025] In some embodiments of the power receiver, the resonant frequencies of the resonant transformers are all below 200 Hz.

[0026] In some embodiments of the power receiver, the resonant frequencies of the resonant transformers are matched to respective Schumann resonances.

[0027] Other embodiments of the disclosure comprise a ground terminal for a power receiver. In one embodiment, the ground terminal comprises a ground shaft configured for insertion beneath the surface of the earth, a hollow cylinder surrounding the ground shaft and having a plurality of openings, and a plurality of ground wires connected at one end to the ground shaft. The ground wires are wound around the ground shaft and have free ends protruding through respective openings in the hollow shaft so that rotation of the ground shaft relative to the hollow cylinder causes the ground wires to extend radially into the earth.

[0028] Other embodiments of the disclosure comprise methods of extracting power from the earth. In one embodiment, the method comprises applying a high voltage impulse to resonant circuit coupled to a ground terminal disposed beneath the surface of the earth to initiate resonance in the resonant circuit and induce the flow of current from the ground terminal to the resonant circuit, and converting the current flowing from the ground terminal into the resonant circuit into a useful form.

[0029] In some embodiments of the method, the resonant circuit comprises a resonant transformer including a primary winding coupled to the ground terminal and a second winding coupled to a power converter, and applying a high voltage impulse to resonant circuit comprises applying a high voltage impulse to the primary winding of the resonant transformer.

[0030] In some embodiments of the method, applying a high voltage impulse to the primary winding of the resonant transformer comprises applying an impulse in the range to 10,000 to 40,000 volts to primary winding of the transformer.

BRIEF DESCRIPTION OF THE DRAWINGS

[0031] FIG. **1** illustrates a first exemplary embodiment of a power receiver.

[0032] FIG. **2** illustrates a second exemplary embodiment of a power receiver.

[0033] FIG. **3** illustrates a third exemplary embodiment of a power receiver.

[0034] FIG. **4** illustrates a fourth exemplary embodiment of a power receiver.

[0035] FIG. **5** illustrates a fifth exemplary embodiment of a power receiver.

[0036] FIG. **6**A is an exploded perspective view of an exemplary ground antenna array for the power receiver.

[0037] FIG. **6**B is a perspective view of an assembled ground antenna array before being deployed.

[0038] FIG. **6**C is a perspective view of an assembled ground antenna array after being deployed.

[0039] FIG. **7**A is a side view of an insertion tool for installing the ground antenna array.

[0040] FIG. **7**B is a top view of the insertion tool for installing the ground antenna array.

[0041] FIG. **7**C is a bottom view of the insertion tool for installing the ground antenna array.

DETAILED DESCRIPTION

[0042] Referring now to the drawings, a power receiver for extracting energy from the earth's electric field are illustrated and indicated generally by the numeral **10**. Various embodiments of the power receiver **10** are described and similar reference numbers are used throughout the description to indicate similar components.

[0043] The power receiver **10** converts energy in the ELF/ULF waves to useful form, e.g. 60 Hz AC or DC. The power receiver **10** is essentially a resonance circuit that resonates at the natural resonance frequencies in the earth's electric field. These resonance frequencies, known as Schumann resonance frequencies, occur at 7.83 Hz, 14.3 Hz, 20.8 Hz, 27.3 Hz, and 33.8 Hz. A high voltage impulse initiates resonance within the power receiver **10**. In the resonant mode, the impedance of the power receiver **10** is reduced to near zero thus inducing ground currents to flow into the power receiver **10** where the ground currents are converted to useful form.

[0044] FIG. **1** illustrates a first embodiment of the power receiver **10**. The power receiver **10** comprises a resonant transformer **30** connected between an elevated terminal **15** and ground terminal **25**. In this embodiment, the elevated terminal **15** is capacitively coupled to electric fields within the earth's ionosphere cavity and functions as an upper capacitive plate. A lower capacitive plate **20** is connected to the ground terminal **25** beneath the surface of the earth.

[0045] The resonant transformer **30** comprises a primary winding **35**, secondary winding **40**, ferromagnetic core **45**, and capacitor **50**. One end of the primary winding **35** is connected to the lower capacitive plate **20** and ground terminal **25**. The opposite end of the primary winding **35** is connected via a spark gap **90** to the elevated terminal **15**. The capacitor **50** is connected in parallel with the primary winding **35** of the resonant transformer **30** to form an LC circuit **55** with a resonance frequency range of between about 0.1 and 200 Hz. In a preferred embodiment, the resonant transformer has a Q of about 10 or greater and resonance frequency in the range of about 0.1-200 Hertz. For example, the resonant transformer **30** may have a resonance frequency of about 7.83 Hz, the fundamental Schumann resonance frequency. The secondary winding **40** of the resonant transformer **30** is connected to a power converter **110** as will be hereinafter described in greater detail. The power converter **110** converts the energy extracted from the earth's electric field by the power receiver **10** into a usable form for driving a load **140**.

[0046] The elevated terminal/upper capacitive plate **15** comprises an insulated, dish-shaped plate with a large radius of curvature. The capacitance and resistance of the elevated terminal is chosen for receiving broadband electric field frequencies in the 0-200 Hz range. The upper capacitive plate **15** is sized to maximize to the extent practical coupling with the electric field in the earth's ionosphere cavity.

[0047] The lower capacitive plate **20** is also a dish-shaped plate with a large radius of curvature. One function of the lower capacitive plate **20** is to collect charge from the earth's ground currents and provide an instantaneous source of current as hereinafter described. The capacitance and resistance of the lower capacitive plate **20** is selected to promote the flow of current from the ground with minimal losses.

[0048] The spark gap **90** connected between the elevated terminal **15** and resonant transformer **30** comprises a pair of electrodes **95**, **100** separated by an evacuated air gap **105**. Electrode **95** is connected to the upper capacitive plate **15**. Electrode **100** is connected to the resonant transformer **30**. The spark gap **105** prevents electrical discharge from the upper capacitive plate **15** to the earth's ionosphere cavity. The spark gap **90** in combination with the elevated terminal **15** function as an impulse generator that applies a high voltage impulse of about 10,000-40,000 volts to the primary winding **35** to initiate resonance in the transformer **30**.

[0049] In operation, the capacitive coupling of the upper capacitive plate **15** induces a high voltage operating current in the upper capacitive plate **15**. The upper capacitive plate is connected to a first electrode **95** to the spark gap **90**. When the voltage difference between the electrodes **95** and **100** reaches a threshold, a spark forms across the electrodes **95**, **100** and a high voltage impulse is applied to the primary winding **35** of the resonant transformer **30**. This high voltage impulse initiates resonance within the transformer **30**.

[0050] In resonant mode, the impedance of the resonance transformer is reduced to nearly zero allowing current to flow from the capacitive plate **20** and ground terminal **25** through the primary winding **35** of the transformer **30**, which in turn induces current in the secondary winding **40**. Power converter **110** converts the current flowing through the secondary winding **40** into a usable form for driving a load **140**. The transformer **30** will continue to resonate for a short period of time. By providing high voltage impulses to the primary winding **35** of the resonant transformer **30** at periodic intervals, it is possible to maintain a continuous flow of current from the earth into the resonant transformer **30**, thus producing a continuous supply of power.

[0051] FIG. **2** discloses a second embodiment of the primary receiver **10**. This embodiment includes a resonant transformer **30** connected between an elevated terminal **15** and ground terminal **25**. The resonant transformer **30** comprises a primary winding **35**, secondary winding **40**, ferromagnetic core **45** and a high voltage capacitor **50**. One end of the primary winding **35** is connected to the ground terminal **25**. The opposite end of the primary winding **35** is connected to the elevated terminal **15**. The capacitor **50** has a capacitance of about 0.01 micro-farads. In contrast to the previous embodiment, capacitor **50** is connected in series with the primary winding **35** and elevated terminal **15** and forms a LC circuit **55** with a Q of about 10 or greater and a resonance frequency in the range of about 0.1 to 200 Hz. In a preferred embodiment, the resonance frequency of the transformer **30** is 7.83 Hz, the fundamental Schumann resonance frequency. An impulse generator **60** is connected between the primary winding **35** of the resonant transformer **30** and the series capacitor **50** and applies a high voltage impulse to the primary winding **35** of the resonant transformer **30**. A battery **130** or other external power source supplies power to the impulse generator **60**. As previously described, the high voltage impulse applied by the impulse generator **60** initiates resonance within the resonant transformer **30** inducing current flow from the ground terminal **25** into the primary winding **35** of the resonant transformer **30**. The flow of current from the ground terminal **25** through the primary winding **35** induces current in the secondary winding **40**. Power converter **110** converts the electrical energy in the current flowing through the primary winding **40** into a usable form.

[0052] In contrast to the first embodiment, it is not required to capacitively couple the elevated terminal **15** in the second embodiment to the earth's ionosphere cavity. Rather, the elevated terminal **15** in this embodiment provides lightning protection and dissipates some of the energy flowing into the power receiver **10** to the earth's ionosphere cavity. Also, in contrast to the first embodiment, the capacitor **50** is connected in series between the primary winding **35** of the transformer **30** and the elevated terminal **15**. Those skilled in the art will appreciate that the capacitor **50** could also be connected in parallel rather than series with the primary winding **35** as shown in FIG. **1**. Another difference is that the impulse generator **60** has an external power source. The amount of energy generated by the power receiver **10**, however, is far greater than the energy needed to generate high voltage impulses. The first embodiment does not require an external power source to generate high voltage impulses.

[0053] FIG. **3** illustrates a third embodiment of the power receiver **10**. This embodiment is essentially the same as the embodiment shown in FIG. **2**. The main difference is that a center tap of the primary winding **35** in the resonant transformer **30** is connected to an electrical ground **85**. It should be appreciated that the electrical ground **85** may be different than the earth ground. When the center tap of the resonant transformer **30** is grounded at a distance away from the ground terminal **25** (e.g. 50 ft to 100 ft), the power receiver **10** becomes a transmitter via the ground loop formed.

[0054] FIG. **4** illustrates the power receiver **10** of FIG. **2** in greater detail. The power receiver includes a resonant transformer **30** connected between a ground terminal **25** and an elevated terminal **15**. The ground terminal **25** may comprise a ⅝-inch×8-foot copper ground rod, such as the ERICO 615880UPC. The elevated terminal **15** may comprise a 90% copper mesh formed into a hemisphere with a radius of about 9 inches. The elevated terminal **15** may be elevated at a height of approximately 6 feet above the ground.

[0055] The resonant transformer **30** includes a primary winding **35**, secondary winding **40**, ferromagnetic core **45** and series capacitor **50** configured as previously described. The resonant transformer **30** may have a Q of about 10 and a resonance frequency in the range of about 0.1 to 200 Hz. The resonant transformer **30** may be made using an Allanson transformer (part #1530BP120R) connected in series with a 0.01 micro-farad capacitor, such as the Condensor Products high voltage capacitor (part #TC 103-17-125). The resonant transformer **30** is used in a step-down configuration. The center tap of the resonant transformer **30** may optionally be connected to a ground.

[0056] An impulse generator **60** is connected between the primary winding **35** of the resonant transformer **30** and the series capacitor **50** and applies a high voltage impulse in the range of about 10,000 to 40,000 volts to the primary winding of the transformer **30**. A battery **130** or other external power source supplies power to the impulse generator **60**. The power converter **110** connects to the secondary winding **40**

of the resonant transformer **30** for converting current in the secondary winding of the transformer to a useful form.

[0057] The impulse generator **60** comprises a pulse generator **65** for generating low voltage pulses, a step-up transformer **80** for converting the low voltage pulses from the pulse generator **65** to high voltage pulses, and a spark gap **90** for generating sparks responsive to the high voltage pulses from the step-up transformer **80**.

[0058] The pulse generator **65** comprises a square wave generator **70**, such as a Sinometer VC2002 function signal generator, and solid state relay **75**. The square wave generator **70** generates a digital pulse stream. In one embodiment, the digital pulse stream generates a square waveform with a frequency of about 7.83 Hz. The frequency of the digital pulse stream is selected to match the resonance frequency of the transformer **30**, though such is not necessarily required. The pulse stream output from the square wave generator **70** is applied to the solid state relay **75**. The solid state relay **75** is connected between a battery or other power source and a first winding of the step-up transformer **80**. The battery may comprise a 12 V, 7.0 A/H sealed lead acid battery, such as the ELB 1270A by Lithonia Lighting. The solid state relay **75** functions as a switch that is activated responsive to the waveform from the square wave generator **70** to provide a continuous stream of low voltage pulses from the battery to the first winding of the step-up transformer **80**. A 1 ohm resistor is connected between the solid state relay **75** and step-up transformer **80**.

[0059] The step-up transformer **80** may comprise a Transco 15 kV, 30 mA neon sign transformer (part #S15612). The step-up transformer **80** converts the low voltage pulses from the pulse generator **65** to high voltage pulses that are applied to the spark gap **90**. The step-up transformer has a 0.5 micro-farad capacitor connected in parallel with the primary winding of the step-up transformer **80**. The step-up transformer produces pulses at the output of about 30,000 to 40,000 volts.

[0060] The spark gap **90** comprises a pair of electrodes **95**, **100** separated by an air gap **105**. A suitable spark gap electrode pair is the Information Unlimited SPARK05 ¼-inch×1-inch tungsten electrodes. As previously described, when the voltage potential between the electrodes **95**, **100** reaches a threshold, a spark forms between the electrodes **95**, **100** and supplies a nearly instantaneous, high voltage impulse to the primary winding **35** of the resonant transformer **30**. This high voltage impulse initiates resonance in the resonant transformer **30** inducing current flow from the ground terminal **25** through the primary winding **35** of the resonant transformer **30**.

[0061] The power converter **110** comprises a bridge rectifier **115**, filter capacitor **120**, charge controller **125**, and inverter **135**. A suitable rectifier is the Micro Commercial Components 10 amp, 1000 volt bridge rectifier (Part #GBJL 1010). The bridge rectifier **115** converts the AC current flowing through the secondary winding **40** of the resonant transformer to a DC current. A filter capacitor **120** removes unwanted frequencies from the DC current. A suitable capacitor **120** is Cornell Dubilier 1000uF 450VDC capacitor (part #383LX102M450N082). The filter capacitor **120** has a capacitance of about 1000 micro-farads. The DC current is input to the charge controller **125**. The charge controller **125** may, for example, comprise a maximum power point tracking (MPPT) charge controller, such as a Tracer 4215 BN MPPT Solar Charge Controller, which is commonly used in solar power generating systems. The charge controller **125** applies a small amount of energy to a battery **30** to charge the battery **130**. As previously noted, the battery **130** serves as a power source for the impulse generator **60**. The remaining current is supplied to an inverter **135**, which converts the DC current to an AC current with a desired voltage and frequency, e.g., 120 volts/60 Hz AC. A suitable inverter **135** is the 1500 W Pure Sine power inverter (AIMS) (part #PWRI1500125).The power converter **110** as shown in FIG. **4** may be utilized in the embodiment shown in FIGS. **1**, **2** and **3**.

[0062] FIG. **5** illustrates a power receiver **10** according to another embodiment. The power receiver **10** comprises a plurality of resonant transformers **30** connected between a ground terminal **25** and elevated terminal **15**. Each of the resonant transformers **30** comprises a primary winding **35**, secondary winding **40**, ferromagnetic core **45** and series capacitor **50**. The primary windings **35** of the resonant transformers **30** are connected in parallel. The secondary windings **40** are connected in series with the power converter **110**. An impulse generator **60** applies a high voltage impulse to the primary windings **35** of the resonant transformers **30**. A battery **130** or other external power source supplies power to the impulse generator **60**. The power converter **110** converts the current in the power converter circuit to a usable form for driving a load **140**.

[0063] In one embodiment, each of the resonant transformers **30** shown in FIG. **5** is configured to have a different resonant frequency. In one embodiment, the resonant transformers **30** are configured to resonate at frequencies of 7.83 Hz, 14.8 Hz, 20.3 Hz and 26.8 Hz respectively. Additional resonant transformers **30** could be added to operate at other resonance frequencies.

[0064] FIGS. **6A-6C** illustrate a high quality ground antenna array **200** which may be used as a ground terminal **25**. The ground antenna array **200** comprises a generally cylindrical ground shaft **205** disposed with a hollow cylinder **220** and a plurality of reinforced, heavy gauge ground wires **210** attached at one end to the ground shaft **205**. The ground shaft **205** and ground wires **210** should be highly conductive and have low resistance to supply current from the ground to the power receiver **10**. In one embodiment, the ground wires **210** may be copper or other highly-conductive metal. The end of the ground shaft may be pointed to facilitate insertion into the earth. A connection port on the ground shaft **220** is provided to electrically connect the ground antenna array **220** to the resonant transformer **30**.

[0065] The hollow cylinder **220** has external threads **25** to facilitate insertion into the ground. A rotator nut **235** is fixedly secured to the top end of the hollow shaft **220**. A square shaft **215** protrudes from the top end of the ground shaft **205** into the opening in the rotator nut **235**. FIG. **6B**. A tool **250**, shown in FIG. **7**, engages with the rotator nut **235** and square shaft **215** during insertion of the ground antennas array **200** into the ground as will be hereinafter described.

[0066] The insertion tool **250** is shown in FIG. **7**. The insertion tool **250** includes a tool body **255** having a first socket **260** on one side to fit the rotator nut **235** on the hollow cylinder **220** and a second socket **265** on the other side to fit the square shaft **215** on the ground shaft **205**. Arms **270** extend from the outer periphery of the tool body **255** for manually or mechanically turning the insertion tool **250**.

[0067] Before the antenna array **200** is deployed, the ground wires **210** are wound around the ground shaft **205** with the free ends protruding slightly from respective openings **230** in the hollow cylinder **220** to a distance not to exceed one half (½) the depth of the external threads **225** on the hollow cylinder **220**. FIG. **6**B illustrates the ground antenna array **200** before deployment. FIG. **6**C illustrates the ground antenna array in a deployed configuration.

[0068] Installation of the ground antenna array **200** is performed in two stages. In the first stage, a hole slightly smaller in diameter than the threads **235** of the hollow cylinder **220** is drilled into the Earth to a depth matching the length of the hollow cylinder **220** or slightly longer. The hole is filled with water and the water is allowed to soak into the soil. After the ground is softened, the hollow cylinder **220** is rotated using the insertion tool **250** to insert the ground antenna array **200** into the ground. The first socket **260** of the insertion tool **250** is engaged with the rotator nut **230** and the insertion tool **250** is turned by hand or a mechanized rotating shaft fitted and attached to the tool arms **270** to thread the ground assembly into the hole. During the initial insertion of the ground antenna array **200**, the ground shaft **205** is fixed to the hollow shaft **220** and rotates with the hollow shaft. The hollow cylinder **220** is rotated until it reaches the full depth of the hole.

[0069] Once the ground antenna array **200** has been fully inserted into the earth, the insertion tool **250** is flipped over and the second socket **265** of the insertion tool **250** is engaged with the square shaft **215**. The insertion tool **250** is turned by hand or a mechanized rotating shaft fitted and attached to the tool arms **270** to rotate the ground shaft **205**. During the second phase, the ground shaft **205** rotates freely inside the hollow cylinder **220**. Rotation of the ground shaft **205** causes the reinforced ground wires **210** to extend radially into the earth. The ground shaft **220** is rotated until the ground wires are fully extended. The ends of the ground wires may be sharpened to aid in the extension of the ground wires during the second phase.

[0070] After the ground antenna array **200** is deployed, a connection cable **280** is attached to a connection port **240** on the ground shaft **220** to electrically connect the ground antenna array **220** to the resonant transformer **30** in the power receiver **10**.

What is claimed is:

1. A power receiver for extracting electrical energy from the earth's electric field, said power receiver comprising:

a resonant transformer connected to a ground terminal disposed below the surface of the earth;

an impulse generator for generating and applying a high voltage electrical impulse to a primary winding of the resonant transformer to induce current flow from the ground terminal through the primary winding of the transformer; and

a power conversion circuit connected to a secondary winding of the resonant transformer to convert electrical current flowing through the secondary winding to a desired form.

2. The power receiver of claim **1** wherein a resonant frequency of the resonant transformers is below 200 Hz.

3. The power receiver of claim **1** wherein the resonant transformer comprises a ferro-resonant transformer.

4. The power receiver of claim **1** further comprising an elevated terminal, and wherein the primary winding of the resonant transformer is connected between the ground terminal and elevated terminal.

5. The power receiver of claim **1** wherein the impulse generator comprises:

a pulse generator for generating low voltage pulses;

a step-up transformer for converting the low voltage pulses provided by the pulse generator to high voltage impulses;

a spark gap connected between the step-up transformer and the primary winding of the resonant transformer to generate a spark responsive to the high voltage impulses from the step-up transformer.

6. The power receiver of claim **1** wherein the impulse generator comprises a solid state spark generator.

7. The power receiver of claim **1** wherein said resonant transformer includes a capacitor connected in parallel with the primary winding.

8. The power receiver of claim **1** wherein said resonant transformer includes a capacitor connected in series with the primary winding between the impulse generator and the elevated terminal.

9. The power receiver of claim **1** comprising multiple resonant transformers having primary windings connected in parallel between the ground terminal and the elevated terminal.

10. The power receiver of claim **9** wherein the resonant transformers have different resonant frequencies.

11. The power receiver of claim **10** wherein the resonant frequencies of the resonant transformers are matched to respective Schumann resonances.

12. A power receiver for extracting electrical energy from the earth's electric field, said power receiver comprising:

a resonant circuit connected to a ground terminal disposed below the surface of the earth, said resonant circuit having a resonant frequency below 200 Hertz

an impulse generator for generating and applying a high voltage electrical impulse to the resonant circuit to induce current flow from the ground terminal through the resonant circuit; and

a power conversion circuit connected to the resonant circuit to convert electrical current flowing through the resonant circuit to a desired form.

13. The power receiver of claim **12** wherein the impulse generator comprises:

a pulse generator for generating low voltage pulses;

a step-up transformer for converting the low voltage pulses provided by the pulse generator to high voltage impulses;

a spark gap connected between the step-up transformer and resonant circuit to generate a spark responsive to the high voltage impulses from the step-up transformer.

14. The power receiver of claim **12** wherein the resonant circuit comprises a resonant transformer having a primary winding, a secondary winding, and resonant capacitor connected in parallel with the primary winding.

15. The power receiver of claim **12** wherein the resonant circuit comprises a resonant transformer having a primary winding, a secondary winding, and resonant capacitor connected in series with the primary winding.

16. The power receiver of claim **12** wherein the resonant circuit comprises multiple resonant transformers having primary windings connected in parallel to the ground terminal.

17. The power receiver of claim **16** wherein the resonant transformers have different resonant frequencies.

18. The power receiver of claim **17** wherein the resonant frequencies of the resonant transformers are matched to respective Schumann resonances.

* * * * *

rexresearch.com

Atmospheric & RF Electricity Collectors

GB 157263

Process and Apparatus for Converting Static Atmospheric Electrical Energy into Dynamic Electrical Energy of any Suitable High Periodicity

Abstract -- Atmospheric electricity, utilizing; influence machines.-Static atmospheric charges are converted into alternating-currents of any desired frequency by rotary machines, the stator and rotor elements of which form condensers having a capacity which varies during the revolution as described in Specincation 157,262. In the simplest form, Fig. 2, the curved stator plates 2, 1 are connected to earth E2 and the aerial A which collects the atmospheric charges and is earthed through a safety spark gap F. The rotor is motor-driven and consists of concentric plates 3, 4 joined through slip-,rings (not shown) to an inductance 9 shunted by a condenser 5. With a given aerial polarity, rotation of the plates 3, 4 causes current reversals on the circuit A, 1, 9, 2, E@, whereby oscillations are set upon the circuit 9, 5, these being tapped by leads 11, 12. The condenser 5 may consist of concentric tubes rotating with the rotor or of two juxtaposed wound spirals having capacity. The stator and rotor condenser plates may extend over nearly a semicircle in place of the quadrants shown in Fig. 2 and the rotor may comprise two consecutive cylindrical plates or coil condensers each divided into halves, the inner half of each being connected to the outer half of the other. Fig. 7 shows a form in which rings 1, 2, mounted in a casing comprising upper and lower parts insulated from each other, are connected to the stator condenser plates at intervals. The rotor plates 3, in equal number, are connected to slip-rings 5, 6 from which alternating-current is taken by brushes when the rotor is motor-driven. The rings 1, 2 are respectively connected to the aerial collector and earth E2. Several methods of grouping the stator-rotor condenser pairs and the components of the oscillating circuit are described. The oscillatory current in the rotor circuit may react through a transformer on the main charging current and two pairs of stator and rotor plates 1, 2, 3, 4, Fig. 13, may be employed arranged on diameters at right-angles, the oscillatory circuit in this case consisting of a mutual inductance 5 having capacity and a portion of an adjustable inductance 9 in the stator earth connector E2. By suitably proportioning the stator and rotor plates, 'resonance may be established, whereby undamped waves may be produced. In the form shown in Fig. 15, for high-frequency oscillations, the aerial A and earth wire are tapped at points between the stator plates 1, 2 and condensers 16, 18 which are joined through an inductance 9. The rotor current is conveyed to the power circuit 11, 12 through transformers 10, 10<a>. The members composing the stator and rotor plates may be slotted, as shown in Fig. 8, with holes 1 for attaching them to the frame, or they may have spiral slots in their surfaces. Alternatively, they may be formed by embedding spiral wires 3 in a vulcanite mass 1 so as to give a smooth surface as shown in Fig. 11.

Fig. 1



A
+
−
3 5 4
6 7
1
2
8
+ − − +
9
10
11
12

Fig. 3



Fig. 2



3 9 4
1
5
2
F
E1
11
12
E2

Fig 4



3 5 4
1
9
2
F
E
E2

Fig. 5.



Fig. 6.



7
6
8
F
E1
E2
12

Fig. 7.



+
−
14
13
2
4
1
F
8
3
5
−
6
+
16
15
7
E1
E2
17
17

Fig. 8



Fig. 10



Fig. 9.



Fig. 11



Fig. 12


+
3
4
7
8
9
5
1
2
10
11
12
E_1
E_2

Fig. 13.


L
20
1^a
10
3
3^a
2
9
1
2a
4
4a
5
11
12
E_1
E_2

Fig. 14


9a
10a
5
6
18
19
17
16
1
2
10
9
11
12
E1
E2

Fig. 16


1
2
9
8
18
19
17
16
7
3
4
5
11
12
E1
E2

Fig. 15


9
3
5
4
6
18
19
16
9x
1
2
9a
8
7
9b
10
10a
11
12
E1
E2

Fig. 17.


1
3
8
4
2
18
19
17
16
6
5
7
9
10
11
12
E1
E2

French Patent # 551,882
Apparatus for Capture of Electric Currents in the Atmosphere



Fig. 1

Fig. 2

French Patent # 565,395
Combined Apparatus for Capture of Atmospheric Electric Currents with Immediate Implementation


5
4
4
6
6
1
2
1
3
5
4

Fig. 2.

Fig. 1.

Fig. 3.


1
2
3
4
5
+
-
7
7
R²
R³
R³
R²
R
12
12
R⁴
R⁴
R¹
R¹
11
11
L
L
-
+

Fig. 4.



Fig. 5.



US 28793
Electric Apparatus

Abstract -- An aerostat for obtaining atmpspheric and terrestrial electricity...


Plate 1.
C
A
C
D
D
E
L
a
a


Plate 2
A
B
D
B
E
A
D
B


G
K
I
J
P
R
Q
E
B'
B
G'
J I K
Plate 3.
M
Plate 4.
Fig. 2.
Fig. 1.
E'
D
Fig. 3.
Fig. 4.
I'
I''
Plate 5.
Fig. 1.
Fig. 2.
Fig. 3.
Plate 6.
Fig. 6.
Fig. 5.
Fig. 8.
O
P'
S
Fig. 7.
Fig. 2.
Fig. 4.
Fig. 3.
T
A
N
K
Witnesses:
Arthur L. McIntire
Louis Bannath
Inventor
H. G. Vion
by Munn & Co.
Attorneys.
N. PETERS. Photo-Lithographer. Washington, D.C.

US 126356

Improvement in Collecting Energy for Telegraph

Abstract -- A tower for the purpose of receiving and imparting natural electricity, so as to be in constant contact with the upper stratum of electricity which surrounds the earth, by tapping which a never-failing supply is formed when brought into contact with the earth.


Fig: 1.
Fig: 2.
Fig: 3.
Fig: 4.
Fig: 5.
Fig: 6.
Fig: 7.
WITNESSES.
INVENTOR.
Frank R. Rathbun
H. S. Rathbun
W. H. Ward

US 129971
Telegraph Power

Abstract -- Utilizing natural electricity and establishing an electrical current without the aid of wires, batteries, or cables...

US 674427
Collecting Atmospheric Electricity

Abstract -- An appartus for colecting and driving or conducting atmospheric electricity which renders it practicable to obtain material quantities of teh same in serviceable form.

Fig:1.



Fig:3.

Fig: 2.


18
15
21
20
19
23
22
17
16
24
25



Fig:4.

US 911260
Collecting Atmospheric Electricity

Abstract -- A method of colecting electricity from a strata laden with electricity at high altitudes in the atmoshere, through the medium of a wire cable suspended from one or more balloons ...


Fig. 2.
7
6'
Fig. 1.
3
5
6'
5
4
6
7
7
14
14
4
8
13
1
11
11
11
12
12
14
14
14
12
12
9
12
14
16
15
15
17
10
2
14
14
17
17
INVENTOR
Walter I. Pennock.
WITNESSES
F. J. Hartman
BY

US 1014719
Collecting Atmospheric Electricity

Abstract -- A method of colecting electricity from a strata laden with electricity at high altitudes in the atmoshere, through the medium of a wire cable suspended from one or more balloons ...


Fig. 1.
1
2
3
4
5
6
7
8
11
12
35
38
39
40
45
46
47
48
49
50
51
52
53
54
Fig. 2.
7
35
36
38
39
40
Fig. 3.
5
6
7
9
10
11
20
21
22
28
Fig. 4.
5
9
10
19
20
21
22
23
24
25
26
27
28
29
30
31
32

INVENTOR
Walter I. Pennock.

Fig. 5.


7
43
35
41
42
7
43
8

Fig. 6.


43
35
41
42
43

Fig. 7.


7
42
41
43
35
41
36
38
43
42
8

INVENTOR
Walter I. Pennock.

US 1540998
Conversion of Atmospheric Electric Energy

Abstract -- Method of obtaining atmospheric electricity by means of metallic ballon collectors...

Filed Jan. 15, 1921 12 Sheets-She

Fig. 1.


13
14
7
8
6
5
9
10
11
12

Fig. 2.


1
14
5
11
C_1
b_1
7
9
10
1
a_1
12
2
6
13
15

Fig. 3.


A
O
S
a
a
a
a
8
7
1
2
E.

Fig. 4.


S
5
8
7
1
2
6
E
E_1

Fig. 5.


A
S
5
8
7
7a
9
E
6

Fig. 6



Filed Jan. 13, 1921 12 Sheets-Sheet 2


A
S
1
2
7
7b
8
E
E1
E2

Fig. 7.


A
x
5
9
x1
x4
1
7
8
x5
x2
6
2
9a
x3
E1
E

Fig. 8.


A
S
X
8
X2
5
1
X1
9
2
X3
7
6
X4
E
E1

Fig. 9.


A
S
5
8
7
9
10
6
E

Fig. 10.



Fig. 11.


S
X
9
10
7
5
1
2
9a
10a
X1

Fig. 12.


5
X
9
1
4a
4
3
3a
8
X1
2
7
E

Fig. 13.


A
S
X
8
1
M
10
4
3a
5
9
3
2
4a
7
E

Fig. 14.


A
S
5
1
4
X
X1
3a
M
9
3
2
6
Z
4a
7
E

Fig. 15.


A
S
8
5
1
4
6
3a
M
9
3
2
4a
7

Fig. 16.


A
S
1
R
1a
M
2a
8
2
7
E1
E

Fig. 17.


A
S
1
6
9
M
2
7
8
E2
E1
E

Fig. 18.


A
N
1
8
R
1^2
1^1
2
5
X
7
E
E2
E

Fig. 19.


Z
Z
Z
A1
A2
A3
A4
A5
A10
A9
n
n
A6
A8
A7
n
X1
X
X5
n
X9
n
n
X6
n
A
S
5
1
7
8
2
E

Fig. 20.

Inventor
Hermann Plauson
by Knight Bros
Attorneys


Fig. 21.

Fig. 22.

Fig. 23.

Z
A
5
C
X
D
D1
5
5a
5b
1
2
3
3a
4
4a
7
E
C2
C3
C1
M
D3
D1
5a
5b
5c
E2
E3
E1
Inventor
Hermann Plauson


A
a
b
c
d
e
2
L
3a
3
3b
W
12
S1
18
20
19
17
16
13
21
22
23
24
11
S2
5
14
8
7
9
10
15
6
E1
E2
Invento
Hermann
by Knight

Fig. 24.

Fig. 25.


A1
A2
A3
A4
S2
S1
S3
22
21
27
25
R.
S4
Sb
17
16
13
18
20
19
Sa
Sc
Sd
12
26
28
24
23
J.
8
5
M
7
6
E1
E2

Inventor


I
S
S1
abcd
F1
A
K
B
B1
F
E1
E

Fig. 26.


2
1
3
5
4
19
9
6
22
II
II
21
I
F
f
10
23
S
E
11
S1
E1
20
F1
SII
17
EII.
12
13

Fig. 27.


1
2
4
3
5
6
II
8
7
II
I
I
III
II1
I1
III
20
19
II1
9
12
10
A
a
14
F
b
B
13
S1
S
E1
E

Fig. 28.


B
C
K
L
P
+
N
P
+
N
9
−
E

Fig. 29.


a
b
a
b
F
B
C
K
L
P
+
N
−
9
5
−
E

Fig. 30.

Inventor
Hermann Plauson
by
Knight Bros
Attorneys

Filed Jan. 13, 1921 12 Sheets-Sheet 11


z
B
C
K
L
P
+
+
−
−
9
10
11
−
E

Fig. 31.


z
B
C
K
L
5
6
+
9
G
N
−
E

Fig. 32.



Fig. 33.

Inventor
Hermann Plauson
by Knight Bros
attorneys


Filed Jan. 13, 1921
12 Sheets-Shee
Fig. 34
A
1
+
+
2
3
5
+
6
−
7
8
9
10
S
E
E_1
Fig. 35.
A
5
n
+
1
2
8
9
10
13
12
11
+
3
6
−
−
m
S
E
E_1
Fig. 36.
A
5
1
2
3
11
12
8
7
9
10
S
E
E_1
Fig. 37.
A
5
1
2
3
8
9
10
S
E
E_1

GB 149,917
Improvements in & Relating to Radio Communication Systems

Abstract -- Radio transmission and reception through the use of living vegetable organisms such as trees, plants, and the like.

Fig 1


5
30
31
22
21
24
23
28
26
25
17
16
20
19
32
33
15
7
6
8
2
9
1
3
13
10
14
18
11
12

US 1826727
Radio Apparatus


Fig. 1
7
6
8
10
11
33
9
2
3
4
31
1
Fig. 3
34
37
36
35
2
Fig. 2
6
7
33
3
38
34
35
36
37
2
3
31
4
38
1
32
Fig. 4
10
9
−
+
7
3
33
31
5
INVENTOR
Chancy J. Britten
By Chappell & Earl
ATTORNEYS

US 2143437
Radiant Energy System

Abstract -- An apparatus for receiving and transmitting radiant energy within a wide range of frequencies without necessity of a source of local energy.


34
29
32
30
33
22
31
S
S
N
35
35
18
26
INPUT
17
20
21
23
24
OUTPUT
25
19
28
27

Fig.2


159
162
160
162
161
163
163
12
10
14
15
13
4
4
11

Fig.3


10
11
14
15
13

Fig.4


INPUT
22
18
29
21
24
23
20
17
20
23
21
24
18
25
29

Fig.9

Inventor

James Marion Fisher

By Murray & Zugelter

Attorney


151
149
150
143
148
139
142
143
141
49
48
56
144
140
133
135
134
138
152
131
153
132
147
29
136
137
145
146
148

Fig.5


155
182
154
152
153

Fig.7


156
155
152
157
158
152

Fig.8


116
114
117
94
107
29
106
114
113
115
103
104
108
112
118
99
102
119
101
100
109
120
111
128
125
106
110
29
129
121
123
124
127
128
123
130
126
48
56
49
105
48
56
49
122

Inventor

James Marion Fisher

US 2813242
Powering Electrical Devices with Energy Abstracted from the Atmosphere

Abstract -- A convenient and economical provision of power for the operation of electronic circuits and devices using transistors, and of other electrical devices hving modest power requirements.


RF POWER
35
36
37
41
43
46
40
42
44
TRANSISTOR OSCILLATOR
52
55
61
64
69
70
HIGH VOLTAGE LEVEL d-C POWER
LOW VOLTAGE LEVEL d-C POWER

FiG. 3


1
2
5
15
16
20
22
21
17
6
23
25
3
7
26
+1 v.
10
11
27
-2 v.
12
30
31

FIG. 1


35
36
37
41
46
43
+DC
45
LOAD
40
42
44
-DC

FIG. 2

INVENTOR
Lloyd R. Crump

US 3205381
Ionospheric Battery

Abstract -- A method and apparatus for tapping the enormous reservoir of energy existing in the ionosphere...


16
10
12
14
32
22
28
26
18
24
30
34
18
20
16

Fig. 1


10
40
12
36
22
32
38
28
26
40
30
34
14
40
36
38
40

Fig. 2

INVENTOR
Leslie G. Smith,
BY
Diggins & LeBlanc
ATTORNEYS

US 3273066
Apparatus for Detecting Changes in the Atmospheric Electric Field

Abstract -- A cloud detector and or an apparatus for sensing electrostatic conditions in the earth's atmosphere...


Fig. 1
14
30
24
22
20
Pressure Sensor
12
Transmitter
18
Block. Oscill.
16
26
28
34
32
Receiver -36-
Recorder -38-
Fig. 3
24
26
R1
R2
R3
66
C
64
64
62
62
Temperature Channel
Humidity Channel

INVENTOR:
Lothar H. Ruhnke

By Alan C. Rose
Attorney

US 3760257
EM Wave Energy Converter

Abstract -- Electromagnetic wave energy is converted into electric power with an array of mutually insulated electromagnetic wave absorber elements each responsive to an electric field component of the wave as it impinges thereon. Each element includes a portion tapered in the direction of wave propagation to provide a relatively wideband response spectrum. Each element includes an output for deriving a voltage replica of the electric field variations intercepted by it. Adjacent elements are positioned relative to each other so that an electric field subsists between adjacent elements in response to the impinging wave. The electric field results in a voltage difference between adjacent elements that is fed to a rectifier to derive d.c. output power. The element pairs may be arranged in a two-dimensional

array to provide power conversion of randomly polarized electromagnetic waves, such as sunlight.

FIG. 1


D
23
11
Ē
24
R_L
16
21
25
15
Prop.
13
16
14
17
B
12
22
L

FIG. 2


135
135
34
135
3
31e
34
31d
31
31
31a
34
135
31
34
31
31b
31
33
31
31
32
31c
31
3


38
31a
42
P
N
36
37
41
31b
39
32
38
31c
37
42
P
N
36

FIG. 3



US 3931577

Radio Receiver Protection Arrangement

Abstract -- A receiver protection arrangement in which a voltage dependent on aerial voltage and a voltage dependent on aerial current are aggregated and applied to means responsive to a predetermined aggregate level to effectively short circuit the aerial lead. Additional means may be provided to dissipate energy in the input stage of a protected receiver to cause a reduced impedance to be reflected across the output of the protective arrangement.



Fig. 1.



Fig. 2.


1ST. AMPL.
2
5
D7
R9
D5
D6
C7
T2
R8
D8
D9
C6
4

Fig. 3.

US 4,628,299
Seismic Warning System Using RF Energy Monitor

Abstract -- The ambient broadband radio frequency field strength from broadcast stations is monitored (Figure 4) by periodic sampling (50, 52). A warning indication is provided if the field strength drops significantly. Drops in such field strength have been correlated empirically with the occurrence of seismic activity, usually several days later. Thus the indication serves as an early warning of an impending earthquake. In one preferred embodiment, a broadband, horizontal, very long monopole antenna (40) was connected to a rectifying and smoothing circuit (Figure 3) to provide a dc output proportional to the ambient rf field...


Ant
40
Cn 1
Cp 1
0.047 µF
-V out
42
Dn2
Dp2
+V out
44
1N34
Dn1
Dp1
1N34
Cn2 40 µF
Cp2 40µF

FIG 3

Your Support Maintains this Service --

BUY

The ***Rex Research Civilization Kit***

... It's Your Best Bet & Investment in Sustainable Humanity on Earth ...
Ensure & Enhance Your Survival & Genome Transmission ...
Everything @ rexresearch.com on a Data DVD !

ORDER PAGE

Sept. 7, 1965 **L. G. SMITH** **3,205,381**

IONOSPHERIC BATTERY

Filed March 9, 1962


12
36
40
10
22
28
32
26
30
34
38
40
40
36
14
40
38

Fig. 2


12
14
18
16
32
26
28
30
34
20
16
22
24
10
18

Fig. 1

INVENTOR

Leslie G. Smith,

BY Diggins & Le Blanc

ATTORNEYS

United States Patent Office

3,205,381

Patented Sept. 7, 1965

3,205,381

IONOSPHERIC BATTERY

Leslie G. Smith, Waltham, Mass., assignor, by mesne assignments, to the United States of America as represented by the Administrator of the National Aeronautics and Space Administration

Filed Mar. 9, 1962, Ser. No. 178,721

11 Claims. (Cl. 310—5)

This invention relates to a method and apparatus for tapping the enormous reservoir of energy existing in the ionosphere and more particularly for furnishing electrical power to space vehicles.

Within recent years various space probes and space vehicles such as satellites have been launched by man in an effort to learn more about the earth and the solar system within which he lives. Each of these various space craft has employed numerous electrical circuits which are utilized to detect and transmit back to earth certain information ascertained by the craft as it moves through space. In view of the presence of such electrical circuits, some source of electrical power must be made available whereby these circuits can be energized. In the past there have been three main sources of electrical power carried by space vehicles for energizing these circuits, namely, (1) conventional storage batteries, (2) solar batteries and (3) a combination of the conventional storage and solar batteries. Although these various electrical power sources have functioned with some degree of success each has certain serious limitations which cannot be readily overcome.

In the first instance, the conventional storage battery may be of either the wet or dry type but, due to its superior storage capacity, the wet cell type is used nearly exclusively in space vehicles. This additional storage capacity of the wet cell battery is of great importance since the useful life of the vehicle is usually dependent upon the proper operation of its electrical circuits which are, in turn, directly dependent upon the capacity and life of the available power source. Use in space vehicles of a storage battery that utilizes a liquid electrolyte presents several problems that have not been completely solved, however, nor is there any apparent solution to some of these problems. For example, to increase the output capacity of the battery and thereby extend the useful life of the satellite a greater amount of electrolyte must be carried by the battery. But to increase the quantity of electrolyte carried by the battery results in both an increase in size and weight of the power source and space vehicle which cannot, in most instances, be tolerated. Furthermore, the electrolyte may not function correctly if it is subjected to the extreme conditions of space such as, for example, the changes in temperature that are normally encountered. Thus, to insure the proper operation of the wet cell battery involved in powering a space vehicle and to prevent any leakage that might occur should the battery be damaged, some shielding or insulating of the battery is usually involved which, needless to say, adds materially to the cost and weight of the vehicle.

To overcome the space, weight and leakage problems encountered when storage batteries of the conventional wet cell type are used, space engineers have turned to the recently developed solar cell or battery which converts the light rays received from the sun directly into electrical energy. While these solar batteries do not require any type of electroylte and are, therefore, relatively light in comparison to the wet cell storage battery, they are expensive and their inherent principle of operation presents one problem which cannot be overcome, namely, the inability of the solar cell to produce power while the space vehicle is shaded from the sun such as occurs when a satellite is in the shadow cast by the earth.

In an effort to overcome this loss of power which occurs each time a satellite passes into the shadow cast by the earth or some other heavenly body, a storage battery of the wet cell type was added to the vehicle. While the satellite is in the sunlight the solar battery powers the various electrical circuits and charges the storage battery so that, once the sunlight is no longer available, the storage battery can be switched on to furnish the necessary electrical power to the vehicle. While this combined system functions satisfactorily, there is added to the already existing problems of weight, size and electrolyte leakage the problem of incorporating a battery charging and switch-over system between the solar and storage batteries. The addition of this type of system to the power source is undesirable since it adds unduly to the complexity, sensitivity and cost of the space vehicle.

According to the present invention, it has been found that some of the foregoing disadvantages of space vehicle power sources can be overcome by employing an ionospheric type battery which utilizes the ionosphere or other ionized medium existing in outer space as a supplemental source of energy. Since power is a scarce commodity essential for the operation of the space vehicle and for the proper functioning of its experiments, any means for supplying additional power while adding only slightly to the weight of the vehicle, increases the efficiency and life of the space vehicle. Although it has been known for some time that the ionosphere contains an enormous reservoir of energy in the form of excited and ionized atoms and molecules, no practical method has heretofore been found whereby this energy could be utilized as a source of power for earth satellites even though much thought has been given to this problem. The operation of the present invention is based upon the discovery that the ionosphere can be utilized as a part of supplemental power source for the load circuit in a space vehicle when said vehicle is equipped with electrodes having different work functions which, in turn, are electrically connected through the load circuit.

Accordingly, a primary object of this invention is to provide a method of producing electrical power from ionized media existing in nature.

Another object of this invention is to provide a simple, highly reliable supplemental power source for space vehicles.

Yet another object of this invention is to provide an ionospheric battery for use by satellites.

Still another object of this invention is to provide an ionospheric battery which utilizes the ionosphere as an electrolyte.

A further object of this invention is to provide a supplemental power source for space vehicles that will operate when shielded from the sun.

Yet a further object of this invention is to provide a power source for a satellite that is light and inexpensive to produce.

Another object of this invention is to provide a satellite with various shaped electrodes constructed of metals having different contact potentials.

These and further objects and advantages of this invention will become more apparent upon reference to the following description, claims and the appended drawings wherein:

FIGURE 1 is a cross sectional view of an orbiting satellite equipped with a power source constructed in accordance with one embodiment of the present invention; and

FIGURE 2 is a view in partial section of an orbiting satellite equipped with a power source constructed in accordance with a second embodiment of the present invention.

With continuing reference to the accompanying drawings wherein like reference numerals designate similar parts throughout the various views, and with initial attention directed to the embodiment of FIGURE 1, reference numeral **10** is used to generally designate a space satellite which is orbiting or otherwise passing through an ionized layer or medium such as, for example, the ionosphere which surrounds the earth. As is well known, the ionosphere contains an enormous number of excited and ionized atoms and molecules which are generated or produced when the gasses surrounding the earth are subjected to bombardment by high energy particles and rays such as, for example, ultra-violet or cosmic rays that originate throughout the solar system. Although these various ionized particles created by this bombardment are invisible to the eye they are represented pictorially by the various dots **12** for purposes of clarity.

The satellite **10** consists of an envelope or outer skin surface **14** which may be constructed of metal, ceramic or any other like material which is suitable for space vehicles of this type. As seen in FIGURE 1, a plurality of electrically conductive electrodes **16–18**, which are shown in the form of rods and are constructed of materials having different contact potentials (work functions), are mounted in a spaced relationship in the medium **12** through apertures **20** in the envelope **14** of the satellite. In order to prevent a leak from occurring between the normally pressurized interior **22** of the satellite and the ionosphere, which is a near vacuum, and to insulate the electrodes in case a metal is used for the envelope **14**, vacuum tight insulator feed-through elements **24** are fitted around the electrodes **16–18** and are securely mounted within the aperture **20**. These feed-through elements may be of any suitable type so long as they are constructed to withstand the changes in environmental conditions encountered in space without losing their insulative and sealing qualities.

Carried within the cavity or interior **22** of the satellite **10** is a load circuit **26** which may be, for example, a transmitter or any other electrical device that requires a source of electrical power for its proper operation. The load circuit **26** is mounted to the interior wall of the satellite by suitable means (not shown) and has its positive and negative power input terminals **28–30** connected to the various electrodes **16–18** respectively, by suitable electrical conductors **32–34**.

The overall principle and operation of the ionospheric battery in relationship to the satellite **10** can be explained substantially in the following manner. While the satellite remains on earth prior to its being hurled into or through an ionized medium, the electrodes **16–18** are at substantially the same potential since very few ionized particles are present. Thus, no current will flow through the load circuit **26**. However, once the satelllite is launched and it enters an ionized medium a potential difference will be established between the electrodes **16–18** and an electrical current will begin to flow through the load circuit **26**. This difference in electrical potential that exists between the electrodes **16–18** while the satellite is in an ionized medium is attributed to the fact that the electrodes **16** are constructed of a material having a different contact potential or work function from that of the electrodes **18**. This difference in contact potential between the electrodes **16–18** will result in the free electrons of the ionized medium being collected on one group of electrodes, for example the electrodes **16**, while the positive ions produced when the gas is ionized will be collected on the other electrodes **18**. With the electrodes **16** charged to a negative potential in relationship to electrodes **18**, a predetermined amount of current will flow through the load circuit **26** and can thus be utilized to power an electrical circuit such as the transmitter mentioned above.

The exact material from which the two types of electrodes **16** and **18** are constructed will depend upon several factors such as, for example, the amount of output power desired, the material readily available for constructing the electrodes, the susceptibility of the material to damage or destruction when exposed to the environmental conditions existing in space, and various other considerations that will be readily apparent to a worker in the battery field.

While the electrodes **16–18** used in the ionospheric battery of FIGURE 1 have been described as rods or whip-like elements it is to be realized that the electrodes may take other shapes. By way of example, a plurality of flat, plate-like electrodes **36–38** are shown mounted on a satellite in FIGURE 2. These electrodes are constructed of materials having different contact potentials and are insulated from the outer surface **14** of the satellite when this is necessary by an insulative layer **40** of any suitable material having the desired insulative properties under the severe conditions existing in space. The use of these plate electrodes **36–38** has the advantage of increasing the surface area exposed to the ionized medium thus permitting a larger output current to be produced without the necessity of using excessively long electrodes as might be the case if the rod electrodes of FIGURE 1 were used.

The output current of the battery is dependent upon the degree to which the medium is ionized and to the extent that the electrode surface area is exposed to the medium. An increase in either results in an increase in the efficiency of the battery. From an analysis of various experiments it is expected that a current of about two microamps per cm.^2 of electrode surface at a potential of one volt would be produced if the satellite is orbiting in the ionosphere at an altitude of approximately 350 km. and electrodes of gold and platinum are used.

It will also be readily apparent that the envelope of the satellite itself could be constructed in sectional form and of materials having different contact potential thus eliminating the necessity of attaching different electrodes to the satellite or the slight increase in weight necessarily involved. Of course the various sections of material making up the envelope of the satellite would have to be insulated from one another to prevent electrical shorting from occurring.

It will be apparent from the foregoing that the power source of this invention is extremely light, rugged and involves a minimum of cost to construct. By using the vast natural reservoir of energy existing in the form of ionized gases for producing the electrical power necessary to energize the various electrical circuits of a space vehicle a practically indefinite source of electrical power is made available to the vehicle. An ionospheric battery constructed in accordance with this invention is also much more reliable in operation than other heretofore known power sources since no liquid electrolyte is involved which can leak, deteriorate or otherwise become spent, nor is the operation of the battery dependent upon its position in relationship to a source of light.

The invention may be embodied in other specific forms without departing from the spirit or essential characteristics thereof. The present embodiments are therefore to be considered in all respect as illustrative and not restrictive, the scope of the invention being indicated by the appended claims rather than by the foregoing description, and all changes which come within the meaning and range of equivalency of the claims are therefore intended to be embraced therein.

What is claimed and desired to be secured by United States Letters Patent is:

1. A space vehicle equipped with a generator of electrical energy operable in the ionosphere as a supplemental source of potential for a load thereof, said generator comprising at least two electrode means on said vehicle and positioned to contact said ionosphere when said vehicle is in said ionosphere, said two electrode means each having different contact potentials, one of said two electrode means being gold and the other being

platinum, and electrical connector means connecting said two electrode means to said load.

2. Apparatus for generating electrical energy from the ionosphere comprising, a pair of spaced electrode means having different contact potentials positioned to contact said ionosphere so that a direct-current electric potential is established between said electrode means, load circuit means, and means electrically connecting said load circuit means to said electrode means whereby said load circuit means is powered by the direct-current electrical potential existing between said electrodes.

3. Apparatus for generating electrical energy from the ionosphere comprising, carrier means, a first electrode having a first contact potential mounted on said carrier means, a second electrode having a second contact potential spaced from said first electrode and mounted on said carrier means, said first and second electrodes being positioned on said carrier means so that they will be in contact with said ionosphere when said apparatus is placed in the ionosphere so that a direct-current electric potential is established between said first and second electrodes, and an electrical load circuit connected between said first and second electrodes, said load circuit being powered by the direct-current potential produced by said first and second electrodes.

4. Apparatus according to claim **3** wherein said first and second electrodes extend away from said carrier means.

5. Apparatus according to claim **3** wherein said first and second electrodes form a portion of said carrier means.

6. In a space vehicle adapted to pass through ionized areas in space, a power source for said vehicle while it is passing through said ionized areas comprising, a plurality of electrode means located on the outer surface of said vehicle, said electrode means being constructed of materials having different contact potentials, and means connecting said electrode means together through a load circuit whereby said circuit receives a source of direct-current as said space vehicle passes through said ionized areas.

7. In a space vehicle according to claim **6** wherein said electrode means are rod shaped.

8. In a space vehicle according to claim **6** wherein said electrode means are plate shaped.

9. A satellite comprising an envelope, electrical load means carried in said envelope, apertures extending through said envelope at spaced points, electrode means having different contact potentials, said electrode means passing through said apertures, means in said aperture for insulating said electrode means from said envelope, and electrical conductor means connected between said electrode means and said electrical load means whereby said electrical load means is energized by the direct-current electric potential established when said electrode means passes through an ionized medium.

10. A space satellite comprising an envelope, an electrical load circuit carried in said envelope, a power supply for said electrical load circuit comprising a first electrode having a first contact potential connected to said electrical load circuit and extending through said envelope and a second electrode having a second contact potential connected to said electrical load circuit and extending through said envelope, said first and second electrodes being insulated from one another so that said electrical load circuit is powered by the direct-current electric potential established by said first and second electrodes coming in contact with an ionized medium.

11. The method of powering electrical circuit means carried by a space vehicle comprising the steps of positioning first and second electrode means having different work functions on said vehicle, passing said vehicle through the ionosphere so that said first and second electrode means are in contact therewith and produce a direct-current potential between them, and connecting said first and second electrodes to said electrical circuit means by means of electrical connector means, whereby said direct-current potential is made available for operating said circuit.

References Cited by the Examiner

UNITED STATES PATENTS

414,943	11/89	Dewey	310—5 X
911,260	2/09	Pennock	310—5 X
2,303,321	12/42	Bennett	175—264
2,445,305	7/48	Hochgesaug	250—83.6
2,510,397	6/50	Hansell	171—330
2,802,113	8/57	Ohmart	250—83.6
2,864,012	12/58	Thomas	310—3
2,900,535	8/59	Thomas	310—3
3,021,472	2/62	Hernqvist	322—2

LLOYD McCOLLUM, *Primary Examiner.*

JOHN H. MACK, *Examiner.*

(No Model.)

M. W. DEWEY.

METHOD OF UTILIZING NATURAL ELECTRIC ENERGY.

No. 414,943. Patented Nov. 12, 1889.


p
p
p
F
p'
p'
p'
F'
a
A'
A
d'
c
c
d
b
S
N
b'
f
f
e
S
N
K
I
g
i
m
h
D
l
l
l
L
n
L'
H
D
D
J
G
d'
o
M
B
d
E
c'
c'
C
c'
c'
c'
c'
c'

WITNESSES:

C. L. Bendixon

A. F. Walz.

INVENTOR

Mark W. Dewey

BY

Duell, Laass & Duell

ATTORNEYS

N. PETERS, Photo-Lithographer, Washington, D. C.

UNITED STATES PATENT OFFICE.

MARK W. DEWEY, OF SYRACUSE, NEW YORK, ASSIGNOR TO THE DEWEY CORPORATION, OF SAME PLACE.

METHOD OF UTILIZING NATURAL ELECTRIC ENERGY.

SPECIFICATION forming part of Letters Patent No. 414,943, dated November 12, 1889.

Application filed May 1, 1889. Serial No. 309,171. (No model.)

To all whom it may concern:

Be it known that I, MARK W. DEWEY, of Syracuse, in the county of Onondaga, in the State of New York, have invented new and useful Improvements in the Method of Utilizing Natural Electric Energy, of which the following, taken in connection with the accompanying drawings, is a full, clear, and exact description.

The object of this invention is to provide a method whereby natural electrical energy—such as the so-called "atmospheric electrical energy," or electrical energy that may be derived from the difference of potential existing between two points, one being the earth and the other the atmosphere at an elevation above the earth—may be collected or utilized for the various uses to which electricity is applied.

It has been found that the presence of electricity in the upper regions of the atmosphere is not confined to thunder-clouds, but can be detected at all times and often in great quantities in different conditions of the atmosphere. In fine weather this electricity is mostly positive; but in showery or stormy weather negative electricity is as frequently met with as positive, and it is in such weather that the indications of electricity, whether positive or negative, are usually the strongest. It has also been found that as we proceed farther from the earth's surface, whether upward from a level plane thereof or horizontally from an elevation, the potential of points in the air becomes more and more different from that of the earth, the difference being, in a broad sense, simply proportional to the distance; hence we can infer that there is electricity residing on the surface of the earth, the density of which at any moment in the locality of observation is measured by the difference of potential found to exist between the earth and a given point in the air near it. The results of observations show that the variations of the electricity residing in the atmosphere is the main cause of the variations of the electricity on the surface of the earth. A charged cloud or body of air induces electricity of the opposite kind to its own on the parts of the earth's surface over which it passes and produces such variations. The difference of potential in increasing the distance from the earth is due to electricity induced on the surface of the earth by opposite electricity in the air overhead, and the air being a non-conductor the electricities are unable to combine. As electrical density is greater on projecting parts of a surface than on those which are plane or concave, stronger indications are obtained on hills than in valleys, if the collecting apparatus be at the same distance from the ground in both cases. The average difference of potential is greater in the winter than in the summer. Little or no effects can be obtained within inclosures or under trees, as they tend to screen the apparatus.

Inasmuch as electricity travels in preference through the best conductors, it follows that if a path of low resistance is formed (such as the erection of a metal pole) to a sufficient elevation above the earth the electricities in the atmosphere and that on the surface of the earth will tend to combine and travel through the said path in a current or currents, and if this pole terminates in a metal point or a number of such points the earth and clouds exchange their opposite electricities without a disruptive discharge—as the lightning—but in a slow and gradual way through convection. Besides supplying the top of the pole with points, a metal plate to which the said points are fixed attracts the opposite electricity in the atmosphere. In order to obtain a greater and increased effect, a large metal plate is buried at the foot of the pole and electrically connected therewith, and is provided with points or branches extending in different directions in the ground. The plate and branches may be surrounded by metallic refuse, coke, or other good conducting substance. The metallic points on the top of the pole should be sharp, and preferably of copper, and may be platinized, gilded, or galvanized to prevent corrosion. It having been ascertained by practical experiments that either a flame or dropping water at an elevation above the surface of the earth produces convection of electricity, it is obvious that such means may be employed in place of the points hereinbefore referred to. As the electricity in the atmosphere is sometimes positive and other times negative, the direction of the currents is not always the same—that is, the atmospheric electrical energy is composed of a current of an alternating character, flowing in one direction on an average about as much of the time as in the opposite direction, but the length of the current in a certain direction, or the lengths of time between reversals or changes in the direction of its flow, is greatly varied. This and also the varied strength of the currents have prevented the utilization of atmospheric electrical energy in commercial quantities for the various purposes for which electricity is generally employed. In order to utilize such a current or currents, they should be transformed into a continuous direct current of uniform strength. The apparatus for accomplishing the transformation of atmospheric electricity into a direct current of uniform strength is susceptible of being greatly modified. The preferred form of apparatus, however, for carrying the invention practically into effect I will now proceed to describe to show that the method is capable of actual performance. Said apparatus is illustrated in the diagram accompanying this specification.

Referring specifically to said diagram, A represents a metallic pole, which is shown bare, but may be enveloped in suitable insulating material, if desirable. B is the base of the aforesaid pole, which base is of insulating material set in the ground E. C is a large metal plate beneath the said base, and has points or branches *c'* extending therefrom in different directions in the ground. C' is a metallic post extending from the said plate above the surface of the ground and having a terminal *d* of the circuit D. On the top of said pole is mounted a metallic cap F, consisting, preferably, of a convex disk provided with sharp iron or copper points *p*, which project in all directions from the same. As before mentioned, the said points may be plated with a suitable metal that forms a good conductor and prevents corrosion. Similar caps F' may be placed on other insulated poles, as A', in the vicinity, and connected with the main pole A by an electric conductor *a*, for increasing the effect. The pole A' may be of wood, and the pole A may also be of the same material if provided with a metal conductor within or on the outside, extending from the cap to the other terminal *d'* of the circuit D. The said circuit D leads from the terminal *d* through an automatic variable resistance G, thence to one of the poles of a secondary or storage battery H, and from the other pole of said battery through an automatic current-regulator to the terminal *d'*. An automatic current-reverser or pole-changer J is located in the said circuit for reversing the current whenever there is a change in its direction, so that it may be rectified or straightened during transit and caused to travel at all times whether its direction is toward or from the earth in one and the same direction through a portion of the circuit containing the secondary battery. The reversals are accomplished automatically by means of a pivoted polarized armature *b*, located between two electro-magnets *c c*, having their coils included in a shunt-circuit between the leads of the circuit D. The magnets are wound so that a north pole will be presented to the armature on one side and a south pole on the other. When the current is flowing in a certain direction, the said polarized armature will be repelled by one magnet and attracted by the other, and thereby moved to one side. When the current changes its direction through the magnets, the poles of the said magnets are reversed and the armature is both repelled and attracted to the other side. An arm *b'*, of diamagnetic material, is fixed to and extends from the armature and is moved by the same. Between a movable end of the arm and the said current-reverser is a pivoted connection or link *e*, by which the motion of the arm is conveyed to the reverser. Stops *f* are provided for limiting the movement of the said arm, and an adjustable resistance *d'* is included in the shunt *d''* to regulate the current through the same.

The current-regulator hereinbefore referred to prevents short-circuiting or the rapid discharge of the secondary battery into the air and ground when the strength of said battery-current becomes greater than that passing to the battery. Said regulator is composed of an electro-magnet I, having its coil in the circuit D. A pivoted polarized armature *g* is connected at its pivot to one terminal of the coil of said magnet, and when the current is flowing to the battery said armature is attracted by the magnet I and held in contact with the stop *h*, to which the terminal of the secondary battery is connected. In the aforesaid condition a free or low-resistance path for the current is provided to the battery; but when the battery-current exceeds the charging-current the magnet-poles are reversed and the armature is repelled by the magnet, and the free path of the circuit is broken between the armature *g* and stop *h*. In order to maintain the armature in the latter position until the charging-current has been increased in strength above that of the battery-current or discharging-current, and so that the said regulator will automatically operate, a shunt path K of high resistance is provided around the armature *g* and stop *h*. The high resistance of the said shunt is obtained by including a rheostat *m*. This shunt path or circuit K, with the resistance, permits a small but sufficient amount of current to flow through the magnet I to hold the armature away from the stop *h* until the current is reversed, and then move the armature back to stop *h* to close the free or low-resistance path. A spring *i* is provided to assist the movement of the armature from the magnet when it is repelled by the same.

The electric current may be directly conducted to translating devices—such as lamps or electromotors; but, as hereinbefore stated, said current is preferably employed to charge one or more cells of the secondary battery H, and this battery stores or accumulates the electrical energy and supplies the said translating devices. To illustrate the latter feature, leads or wires L and L′ are extended from the poles or electrodes of said battery, and translating devices, in the shape of incandescent lamps *l*, are connected with the said wires in multiple arc. In the wire L is a common circuit maker and breaker *n* to close and open the circuit to the lamps. The said battery may be charged in series or parallel.

The automatic variable resistance G maintains the current flowing through the circuit D approximately uniform by increasing the resistance therein upon an increase of strength. Said resistance is not absolutely necessary and may be dispensed with.

The lightning-arrester M is to short-circuit a very heavy current to prevent the same from passing through the other parts of the apparatus and injuring it. A low-resistance shunt O, with a circuit maker and breaker therein, is connected between the leads of the circuit D, near the terminals *d* and *d′*, to completely short-circuit the apparatus when desired.

Having described my invention, what I claim as new, and desire to secure by Letters Patent, is—

1. The method of utilizing atmospheric electrical energy, consisting in conducting the electric current or currents between the earth and a point in the atmosphere at an elevation above the earth, rectifying or straightening the currents during transit, and storing or accumulating the electrical energy of said rectified current or currents.

2. As preliminary steps in the method of utilizing atmospheric electrical energy, conducting the electric current or currents through a path of low resistance between the earth and the atmosphere at an elevation above the earth, maintaining an approximately uniform strength of current and rectifying or straightening the same during transit.

3. As preliminary steps in the method of utilizing atmospheric electrical energy, conducting the electric current or currents through a path of low resistance between the earth and the atmosphere at an elevation above the earth, and rectifying or straightening said currents during transit.

4. The method of utilizing atmospheric electrical energy or deriving energy from the difference of electrical potential existing between the earth and a point or points in the atmosphere at an elevation above the earth, consisting in conducting the current or currents between the two points through a path of low resistance, rectifying or straightening the said currents in a portion of the path during transit, and storing or accumulating the electrical energy thereof.

5. The method of utilizing atmospheric electrical energy or deriving energy from the difference of electrical potential existing between the earth and a point or points in the atmosphere at an elevation above the earth, consisting in conducting the current or currents between the two points through a path of low resistance, maintaining an approximately uniform strength of current, rectifying or straightening the said currents in a portion of the path during transit, and storing or accumulating the electrical energy.

6. The method of utilizing atmospheric electrical energy composed of a current of a varied alternating character, consisting in conducting the electric current or currents through a path of low resistance between the earth and the atmosphere at an elevation above the earth, and then accumulating the electrical energy of said current or currents while flowing in both directions in one or more cells of a secondary or storage battery, as described.

In testimony whereof I have hereunto signed my name this 29th day of April, 1889.

MARK W. DEWEY. [L. S.]

Witnesses:
C. H. DUELL,
C. L. BENDIXON.

No. 649,621. Patented May 15, 1900.

N. TESLA.

APPARATUS FOR TRANSMISSION OF ELECTRICAL ENERGY.

(Application filed Feb. 19, 1900.)

(No Model.)



Witnesses:
Benjamin Miller.
G. W. Martling.

Nikola Tesla, Inventor

by Kerr, Page & Cooper Att'ys

THE NORRIS PETERS CO., PHOTO-LITHO., WASHINGTON, D. C.

UNITED STATES PATENT OFFICE.

NIKOLA TESLA, OF NEW YORK, N. Y.

APPARATUS FOR TRANSMISSION OF ELECTRICAL ENERGY.

SPECIFICATION forming part of Letters Patent No. 649,621, dated May 15, 1900.

Original application filed September 2, 1897, Serial No. 650,343. Divided and this application filed February 19, 1900. Serial No. 5,780. (No model.)

To all whom it may concern:

Be it known that I, NIKOLA TESLA, a citizen of the United States, residing at the borough of Manhattan, in the city of New York, county and State of New York, have invented certain new and useful Improvements in Apparatus for the Transmission of Electrical Energy, of which the following is a specification, reference being had to the drawing accompanying and forming a part of the same.

This application is a division of an application filed by me on September 2, 1897, Serial No. 650,343, entitled "Systems of transmissions of electrical energy," and is based upon new and useful features and combinations of apparatus shown and described in said application for carrying out the method therein disclosed and claimed.

The invention which forms the subject of my present application comprises a transmitting coil or conductor in which electrical currents or oscillations are produced and which is arranged to cause such currents or oscillations to be propagated by conduction through the natural medium from one point to another remote therefrom and a receiving coil or conductor at such distant point adapted to be excited by the oscillations or currents propagated from the transmitter.

This apparatus is shown in the accompanying drawing, which is a diagrammatic illustration of the same.

A is a coil, generally of many turns and of a very large diameter, wound in spiral form either about a magnetic core or not, as may be desired. C is a second coil formed by a conductor of much larger size and smaller length wound around and in proximity to the coil A.

The apparatus at one point is used as a transmitter, the coil A in this case constituting a high-tension, secondary, and the coil C the primary, of much lower tension, of a transformer. In the circuit of the primary C is included a suitable source of current G. One terminal of the secondary A is at the center of the spiral coil, and from this terminal the current is led by a conductor B to a terminal D, preferably of large surface, formed or maintained by such means as a balloon at an elevation suitable for the purposes of transmission. The other terminal of the secondary A is connected to earth, and, if desired, to the primary also, in order that the latter may be at substantially the same potential as the adjacent portions of the secondary, thus insuring safety. At the receiving-station a transformer of similar construction is employed; but in this case the longer coil A′ constitutes the primary, and the shorter coil C′ the secondary, of the transformer. In the circuit of the latter are connected lamps L, motors M, or other devices for utilizing the current. The elevated terminal D′ connects with the center of the coil A′, and the other terminal of said coil is connected to earth and preferably, also, to the coil C′ for the reasons above stated.

The length of the thin wire coil in each transformer should be approximately one-quarter of the wave length of the electric disturbance in the circuit, this estimate being based on the velocity of propagation of the disturbance through the coil itself and the circuit with which it is designed to be used. By way of illustration, if the rate at which the current traverses the circuit including the coil be one hundred and eighty-five thousand miles per second then a frequency of nine hundred and twenty-five per second would maintain nine hundred and twenty-five stationary moves in a circuit one hundred and eighty-five thousand miles long and each wave would be two hundred miles in length.

For such a low frequency, which would be resorted to only when it is indispensable for the operation of motors of the ordinary kind under the conditions above assumed, I would use a secondary of fifty miles in length. By such an adjustment or proportioning of the length of wire in the secondary coil or coils the points of highest potential are made to coincide with the elevated terminals D D′, and it should be understood that whatever length be given to the wires this requirement should be complied with in order to obtain the best results.

It will be readily understood that when the above-prescribed relations exist the best conditions for resonance between the transmitting and receiving circuits are attained, and owing to the fact that the points of highest potential in the coils or conductors A A′ are coincident with the elevated terminals the maximum flow of current will take place in the two coils, and this, further, necessarily implies that the capacity and inductance in each of the circuits have such values as to secure the most perfect condition of synchronism with the impressed oscillations.

When the source of current G is in operation and produces rapidly pulsating or oscillating currents in the circuit of coil C, corresponding induced currents of very much higher potential are generated in the secondary coil A, and since the potential in the same gradually increases with the number of turns toward the center and the difference of potential between the adjacent turns is comparatively small a very high potential impracticable with ordinary coils may be successively obtained.

As the main object for which the apparatus is designed is to produce a current of excessively-high potential, this object is facilitated by using a primary current of very considerable frequency; but the frequency of the currents is in a large measure arbitrary, for if the potential be sufficiently high and the terminals of the coils be maintained at the proper elevation where the atmosphere is rarefied the stratum of air will serve as a conducting medium for the current produced and the latter will be transmitted through the air, with, it may be, even less resistance than through an ordinary conductor.

As to the elevation of the terminals D D′, it is obvious that this is a matter which will be determined by a number of things, as by the amount and quality of the work to be performed, by the condition of the atmosphere, and also by the character of the surrounding country. Thus if there be high mountains in the vicinity the terminals should be at a greater height, and generally they should always be at an altitude much greater than that of the highest objects near them. Since by the means described practically any potential that is desired may be produced, the currents through the air strata may be very small, thus reducing the loss in the air.

The apparatus at the receiving-station responds to the currents propagated from the transmitter in a manner which will be well understood from the foregoing description. The primary circuit of the receiver—that is, the thin wire coil A′—is excited by the currents propagated by conduction through the intervening natural medium from the transmitter, and these currents induce in the secondary coil C′ other currents which are utilized for operating the devices included in the circuit thereof.

Obviously the receiving-coils, transformers, or other apparatus may be movable—as, for instance, when they are carried by a vessel floating in the air or by a ship at sea. In the former case the connection of one terminal of the receiving apparatus to the ground might not be permanent, but might be intermittently or inductively established without departing from the spirit of my invention.

It is to be noted that the phenomenon here involved in the transmission of electrical energy is one of true conduction and is not to be confounded with the phenomena of electrical radiation which have heretofore been observed and which from the very nature and mode of propagation would render practically impossible the transmission of any appreciable amount of energy to such distances as are of practical importance.

What I now claim as my invention is—

1. The combination with a transmitting coil or conductor connected to ground and to an elevated terminal respectively, and means for producing therein electrical currents or oscillations, of a receiving coil or conductor similarly connected to ground and to an elevated terminal, at a distance from the transmitting-coil and adapted to be excited by currents caused to be propagated from the same by conduction through the intervening natural medium, a secondary conductor in inductive relation to the receiving-conductor and devices for utilizing the current in the circuit of said secondary conductor, as set forth.

2. The combination with a transmitting coil or conductor having its ends connected to ground and to an elevated terminal respectively, a primary coil in inductive relation thereto and a source of electrical oscillations in said primary circuit, of a receiving conductor or coil having its ends connected to ground and to an elevated terminal respectively and adapted to be excited by currents caused to be propagated from the transmitter through the natural medium and a secondary circuit in inductive relation to the receiving-circuit and receiving devices connected therewith, as set forth.

3. The combination with a transmitting instrument comprising a transformer having its secondary connected to ground and to an elevated terminal respectively, and means for impressing electrical oscillations upon its primary, of a receiving instrument comprising a transformer having its primary similarly connected to ground and to an elevated terminal, and a translating device connected with its secondary, the capacity and inductance of the two transformers having such values as to secure synchronism with the impressed oscillations, as set forth.

4. The combination with a transmitting instrument comprising an electrical transformer having its secondary connected to ground and to an elevated terminal respectively, and means for impressing electrical oscillations upon its primary, of a receiving instrument comprising a transformer having its primary similarly connected to ground and to an elevated terminal, and a translat-

ing device connected with its secondary, the capacity and inductance of the secondary of the transmitting and primary of the receiving instruments having such values as to secure synchronism with the impressed oscillations, as set forth.

5. The combination with a transmitting coil or conductor connected to ground and an elevated terminal respectively, and means for producing electrical currents or oscillations in the same, of a receiving coil or conductor similarly connected to ground and to an elevated terminal and synchronized with the transmitting coil or conductor, as set forth.

6. The combination with a transmitting instrument comprising an electrical transformer, having its secondary connected to ground and to an elevated terminal respectively, of a receiving instrument comprising a transformer, having its primary similarly connected to ground and to an elevated terminal, the receiving-coil being synchronized with that of the transmitter, as set forth.

7. The combination with a transmitting coil or conductor connected to ground and to an elevated terminal respectively, and means for producing electrical currents or oscillations in the same, of a receiving coil or conductor similarly connected to ground and to an elevated terminal, the said coil or coils having a length equal to one-quarter of the wave length of the disturbance propagated, as set forth.

8. The combination with a transmitting coil or conductor connected to ground and to an elevated terminal respectively, and adapted to cause the propagation of currents or oscillations by conduction through the natural medium, of a receiving-circuit similarly connected to ground and to an elevated terminal, and of a capacity and inductance such that its period of vibration is the same as that of the transmitter, as set forth.

9. The transmitting or receiving circuit herein described, connected to ground and an elevated terminal respectively, and arranged in such manner that the elevated terminal is charged to the maximum potential developed in the circuit, as set forth.

10. The combination with a transmitting coil or conductor connected to ground and to an elevated terminal respectively of a receiving-circuit having a period of vibration corresponding to that of the transmitting-circuit and similarly connected to ground and to an elevated terminal and so arranged that the elevated terminal is charged to the highest potential developed in the circuit, as set forth.

NIKOLA TESLA.

Witnesses:
PARKER W. PAGE,
MARCELLUS BAILEY.

No. 685,957. Patented Nov. 5, 1901.

N. TESLA.

APPARATUS FOR THE UTILIZATION OF RADIANT ENERGY.

(Application filed Mar. 21, 1901.)

(No Model.)



Fig.1


P
T
C
b
r
a
w
M
T'
d
t
t'
R
P'

Fig.2


S
P
D
a
B
R
T
C
d
T'
P'

Fig.3


k
S
P
t
t'
T
C
T'
p
s
R

Fig.4

Witnesses:
Raphaël Netter
M. Lawson Dyer.

Inventor
Nikola Tesla
by Kerr, Page & Cooper Att'ys.

THE NORRIS PETERS CO., PHOTO-LITHO., WASHINGTON, D. C.

UNITED STATES PATENT OFFICE.

NIKOLA TESLA, OF NEW YORK, N. Y.

APPARATUS FOR THE UTILIZATION OF RADIANT ENERGY.

SPECIFICATION forming part of Letters Patent No. 685,957, dated November 5, 1901.

Application filed March 21, 1901. Serial No. 52,153. (No model.)

To all whom it may concern:

Be it known that I, NIKOLA TESLA, a citizen of the United States, residing at the borough of Manhattan, in the city, county, and State of New York, have invented certain new and useful Improvements in Apparatus for the Utilization of Radiant Energy, of which the following is a specification, reference being had to the drawings accompanying and forming a part of the same.

It is well known that certain radiations—such as those of ultra-violet light, cathodic, Roentgen rays, or the like—possess the property of charging and discharging conductors of electricity, the discharge being particularly noticeable when the conductor upon which the rays impinge is negatively electrified. These radiations are generally considered to be ether vibrations of extremely small wave lengths, and in explanation of the phenomena noted it has been assumed by some authorities that they ionize or render conducting the atmosphere through which they are propagated. My own experiments and observations, however, lead me to conclusions more in accord with the theory heretofore advanced by me that sources of such radiant energy throw off with great velocity minute particles of matter which are strongly electrified, and therefore capable of charging an electrical conductor, or, even if not so, may at any rate discharge an electrified conductor either by carrying off bodily its charge or otherwise.

My present application is based upon a discovery which I have made that when rays or radiations of the above kind are permitted to fall upon an insulated conducting-body connected to one of the terminals of a condenser while the other terminal of the same is made by independent means to receive or to carry away electricity a current flows into the condenser so long as the insulated body is exposed to the rays, and under the conditions hereinafter specified an indefinite accumulation of electrical energy in the condenser takes place. This energy after a suitable time interval, during which the rays are allowed to act, may manifest itself in a powerful discharge, which may be utilized for the operation or control of mechanical or electrical devices or rendered useful in many other ways.

In applying my discovery I provide a condenser, preferably of considerable electrostatic capacity, and connect one of its terminals to an insulated metal plate or other conducting-body exposed to the rays or streams of radiant matter. It is very important, particularly in view of the fact that electrical energy is generally supplied at a very slow rate to the condenser, to construct the same with the greatest care. I use, by preference, the best quality of mica as dielectric, taking every possible precaution in insulating the armatures, so that the instrument may withstand great electrical pressures without leaking and may leave no perceptible electrification when discharging instantaneously. In practice I have found that the best results are obtained with condensers treated in the manner described in a patent granted to me February 23, 1897, No. 577,671. Obviously the above precautions should be the more rigorously observed the slower the rate of charging and the smaller the time interval during which the energy is allowed to accumulate in the condenser. The insulated plate or conducting-body should present as large a surface as practicable to the rays or streams of matter, I having ascertained that the amount of energy conveyed to it per unit of time is under otherwise identical conditions proportionate to the area exposed, or nearly so. Furthermore, the surface should be clean and preferably highly polished or amalgamated. The second terminal or armature of the condenser may be connected to one of the poles of a battery or other source of electricity or to any conducting body or object whatever of such properties or so conditioned that by its means electricity of the required sign will be supplied to the terminal. A simple way of supplying positive or negative electricity to the terminal is to connect the same either to an insulated conductor supported at some height in the atmosphere or to a grounded conductor, the former, as is well known, furnishing positive and the latter negative electricity. As the rays or supposed streams of matter generally convey a positive charge to the first condenser-terminal, which is connected to the plate or conductor above mentioned, I usually connect the second terminal of the condenser to the ground, this being the most convenient way of obtaining negative electricity, dispensing with the necessity of providing an artificial source. In order to utilize for any useful purpose the energy accumulated in the condenser, I furthermore connect to the terminals of the same a circuit including an instrument or apparatus which it is desired to operate and another instrument or device for alternately closing and opening the circuit. This latter may be any form of circuit-controller, with fixed or movable parts or electrodes, which may be actuated either by the stored energy or by independent means.

My discovery will be more fully understood from the following description and annexed drawings, to which reference is now made, and in which—

Figure 1 is a diagram showing the general arrangement of apparatus as usually employed. Fig. 2 is a similar diagram illustrating more in detail typical forms of the devices or elements used in practice, and Figs. 3 and 4 are diagrammatical representations of modified arrangements suitable for special purposes.

As illustrative of the manner in which the several parts or elements of the apparatus in one of its simplest forms are to be arranged and connected for useful operation, reference is made to Fig. 1, in which C is the condenser, P the insulated plate or conducting-body which is exposed to the rays, and P′ another plate or conductor which is grounded, all being joined in series, as shown. The terminals T T′ of the condenser are also connected to a circuit which includes a device R to be operated and a circuit-controlling device *d* of the character above referred to.

The apparatus being arranged as shown, it will be found that when the radiations of the sun or of any other source capable of producing the effects before described fall upon the plate P an accumulation of electrical energy in the condenser C will result. This phenomenon, I believe, is best explained as follows: The sun, as well as other sources of radiant energy, throws off minute particles of matter positively electrified, which, impinging upon the plate P, communicate continuously an electrical charge to the same. The opposite terminal of the condenser being connected to the ground, which may be considered as a vast reservoir of negative electricity, a feeble current flows continuously into the condenser, and inasmuch as these supposed particles are of an inconceivably small radius or curvature, and consequently charged to a relatively very high potential, this charging of the condenser may continue, as I have actually observed, almost indefinitely, even to the point of rupturing the dielectric. If the device *d* be of such character that it will operate to close the circuit in which it is included when the potential in the condenser has reached a certain magnitude, the accumulated charge will pass through the circuit, which also includes the receiver R, and operate the latter.

In illustration of a particular form of apparatus which may be used in carrying out my discovery I now refer to Fig. 2. In this figure, which in the general arrangement of the elements is identical to Fig. 1, the device *d* is shown as composed of two very thin conducting-plates *t t′*, placed in close proximity and very mobile, either by reason of extreme flexibility or owing to the character of their support. To improve their action, they should be inclosed in a receptacle, from which the air may be exhausted. The plates *t t′* are connected in series with a working circuit, including a suitable receiver, which in this case is shown as consisting of an electromagnet M, a movable armature *a*, a retractile spring *b*, and a ratchet-wheel *w*, provided with a spring-pawl *r*, which is pivoted to armature *a*, as illustrated. When the radiations of the sun or other radiant source fall upon plate P, a current flows into the condenser, as above explained, until the potential therein rises sufficiently to attract and bring into contact the two plates *t t′*, and thereby close the circuit connected to the two condenser-terminals. This permits a flow of current which energizes the magnet M, causing it to draw down the armature *a* and impart a partial rotation to the ratchet-wheel *w*. As the current ceases the armature is retracted by the spring *b*, without, however, moving the wheel *w*. With the stoppage of the current the plates *t t′* cease to be attracted and separate, thus restoring the circuit to its original condition.

Fig. 3 shows a modified form of apparatus used in connection with an artificial source of radiant energy, which in this instance may be an arc emitting copiously ultra-violet rays. A suitable reflector may be provided for concentrating and directing the radiations. A magnet R and circuit-controller *d* are arranged as in the previous figures; but in the present case the former instead of performing itself the whole work only serves the purpose of alternately opening and closing a local circuit, containing a source of current B and a receiving or translating device D. The controller *d*, if desired, may consist of two fixed electrodes separated by a minute air-gap or weak dielectric film, which breaks down more or less suddenly when a definite difference of potential is reached at the terminals of the condenser and returns to its original state upon the passage of the discharge.

Still another modification is shown in Fig. 4, in which the source S of radiant energy is a special form of Roentgen tube devised by me, having but one terminal k, generally of aluminium, in the form of half a sphere, with a plain polished surface on the front side, from which the streams are thrown off. It may be excited by attaching it to one of the terminals of any generator of sufficiently high electromotive force; but whatever apparatus be used it is important that the tube be exhausted to a high degree, as otherwise it might prove entirely ineffective. The working or discharge circuit connected to the terminals T T′ of the condenser includes in this case the primary p of a transformer and a circuit-controller comprising a fixed terminal or brush t and a movable terminal t' in the shape of a wheel, with conducting and insulating segments, which may be rotated at an arbitrary speed by any suitable means. In inductive relation to the primary wire or coil p is a secondary s, usually of a much greater number of turns, to the ends of which is connected a receiver R. The terminals of the condenser being connected, as indicated, one to an insulated plate P and the other to a grounded plate P′, when the tube S is excited rays or streams of matter are emitted from the same, which convey a positive charge to the plate P and condenser-terminal T, while terminal T′ is continuously receiving negative electricity from the plate P′. This, as before explained, results in an accumulation of electrical energy in the condenser, which goes on as long as the circuit including the primary p is interrupted. Whenever the circuit is closed owing to the rotation of the terminal t', the stored energy is discharged through the primary p, this giving rise in the secondary s to induced currents, which operate the receiver R.

It is clear from what has been stated above that if the terminal T′ is connected to a plate supplying positive instead of negative electricity the rays should convey negative electricity to plate P. The source S may be any form of Roentgen or Lenard tube; but it is obvious from the theory of action that in order to be very effective the electrical impulses exciting it should be wholly or at least preponderatingly of one sign. If ordinary symmetrical alternating currents are employed, provision should be made for allowing the rays to fall upon the plate P only during those periods when they are productive of the desired result. Evidently if the radiations of the source be stopped or intercepted or their intensity varied in any manner, as by periodically interrupting or rythmically varying the current exciting the source, there will be corresponding changes in the action upon the receiver R, and thus signals may be transmitted and many other useful effects produced. Furthermore, it will be understood that any form of circuit-closer which will respond to or be set in operation when a predetermined amount of energy is stored in the condenser may be used in lieu of the device specifically described with reference to Fig. 2 and also that the special details of construction and arrangement of the several parts of the apparatus may be very greatly varied without departure from the invention.

Having described my invention, what I claim is—

1. An apparatus for utilizing radiant energy, comprising in combination a condenser, one armature of which is subjected to the action of rays or radiations, independent means for charging the other armature, a circuit and apparatus therein adapted to be operated or controlled by the discharge of the condenser, as set forth.

2. An apparatus for utilizing radiant energy, comprising in combination, a condenser, one armature of which is subjected to the action of rays or radiations, independent means for charging the other armature, a local circuit connected with the condenser-terminals, a circuit-controller therein and means adapted to be operated or controlled by the discharge of the condenser when the local circuit is closed, as set forth.

3. An apparatus for utilizing radiant energy, comprising in combination, a condenser, one terminal of which is subjected to the action of rays or radiations, independent means for charging the other armature, a local circuit connected with the condenser-terminals, a circuit-controller therein dependent for operation on a given rise of potential in the condenser, and devices operated by the discharge of the condenser when the local circuit is closed, as set forth.

4. An apparatus for utilizing radiant energy, comprising in combination, a condenser, one terminal of which is subjected to the action of rays or radiations, and the other of which is connected with the ground, a circuit and apparatus therein adapted to be operated by the discharge of the accumulated energy in the condenser, as set forth.

5. An apparatus for utilizing radiant energy, comprising in combination, a condenser, one terminal of which is subjected to the action of rays or radiations and the other of which is connected with the ground, a local circuit connected with the condenser-terminals, a circuit-controller therein and means adapted to be operated by the discharge of the condenser when the local circuit is closed, as set forth.

6. An apparatus for utilizing radiant energy, comprising in combination, a condenser, one terminal of which is subjected to the action of rays or radiations and the other of which is connected with the ground, a local circuit connected with the condenser-terminals, a circuit-controller therein adapted to be operated by a given rise of potential in the condenser, and devices operated by the discharge of the condenser when the local circuit is closed, as set forth.

7. An apparatus for utilizing radiant en-

ergy, comprising a condenser, having one terminal connected to earth and the other to an elevated conducting-plate, which is adapted to receive the rays from a distant source of radiant energy, a local circuit connected with the condenser-terminals, a receiver therein, and a circuit-controller therefor which is adapted to be operated by a given rise of potential in the condenser, as set forth.

NIKOLA TESLA.

Witnesses:
M. LAWSON DYER,
RICHARD DONOVAN.

W. I. PENNOCK.

APPARATUS FOR COLLECTING ATMOSPHERIC ELECTRICITY.

APPLICATION FILED JUNE 26, 1907.

911,260. Patented Feb. 2, 1909.


Fig. 2.
7
6'
Fig. 1.
3
5
5
4
6'
6
7
7
14
14
4
8
13
1
12
11
11
11
12
12
14
14
14
12
12
9
12
14
16
15
15
17
10
2
14
14
17
17

INVENTOR

Walter I. Pennock.

WITNESSES

F. J. Hartman.

Alston B. Moulton

BY

ATTORNEY

UNITED STATES PATENT OFFICE.

WALTER I. PENNOCK, OF PHILADELPHIA, PENNSYLVANIA.

APPARATUS FOR COLLECTING ATMOSPHERIC ELECTRICITY.

No. 911,260. Specification of Letters Patent. Patented Feb. 2, 1909.

Application filed June 26, 1907. Serial No. 380,907.

To all whom it may concern:

Be it known that I, Walter I. Pennock, a citizen of the United States, residing at Philadelphia, in the county of Philadelphia and State of Pennsylvania, have invented certain new and useful Improvements in Apparatus for Collecting Atmospheric Electricity, of which the following is a specification.

My invention relates to a method of collecting electricity from a strata laden with electricity at high altitudes in the atmosphere, through the medium of a wire cable suspended from one or more balloons and in conveying this electricity to the earth's surface.

The object of my invention is to provide a conveyance of the electro motive force to be found in the upper strata of the atmosphere to the earth's surface; where it may be utilized for commercial and other purposes.

A further object of my invention is to provide a device or mechanism by which a suitable collector for the electrical energy in the upper strata of the earth's atmosphere may be elevated in the said strata and by which the said electric energy may be transmitted to and collected at the earth's surface, from which point it may be conducted to any place where it is desired to use the same.

A further object of my invention is to support and anchor said device in any desired position.

A further object of my invention is to provide an improved form of collector through which the energy of the said upper strata of the earth's atmosphere may be collected and transmitted for various purposes to the earth's surface.

Other objects of my invention will appear in the specification and claims below.

For a further full, clear and complete disclosure of my invention, reference may be had to the following description and accompanying drawings, in which like reference characters refer to corresponding parts.

Figure 1 is an elevational view of one form or embodiment of my invention and Fig. 2 is a detailed view of one form of my improved collector.

The passage of the electrical current to the earth under ordinary conditions is prevented by an obstruction afforded by the dense lower strata of the atmosphere, which is a bad conductor of electricity, as shown by the electrodes of an ordinary static machine. When the electrodes are placed close together, the atmosphere is seen to carry the current across from one electrode to another, but if placed far apart the current is obstructed by the intervening air. The dense lower strata of the atmosphere affords one of the best non-conductors of electricity, as shown in the conduction of the electric current by telegraph, or trolley wires on the earth's surface, where only a small quantity of the electric current escapes through the atmosphere; while rarefied atmosphere affords a good conducting media, as shown by the vacuum tube. The upper strata of the atmosphere being rare in proportion to the altitude, and being a good conductor of electricity while the lower strata of the atmosphere being dense and affording a non-conducting media for the electric current, thus causes an obstruction to the electric current, or power in its passage to the earth's surface from the electric strata of the atmosphere under ordinary conditions. When, however, the cumulus clouds of a thunder storm pass over the surface of the earth, these clouds being of very great height, the moisture in said clouds forms a better conductor of electricity than does the dry air, with the result that the electricity in the upper strata of the atmosphere breaks through the said cloud as a streak of lightning and in that form reaches even to the earth's surface, while the thin or shallow strata of clouds, observed in the so-called "settled rain" storm, do not extend upward to a sufficient height to form a conducting medium for the electricity from the electric strata to the earth's surface. For this reason there is usually no lightning during the said latter variety of rain storm.

By means of my invention, I have provided a mechanism for collecting the electrical energy or power created by nature and stored in the upper strata of rarefied air of the earth's atmosphere and have provided a conductor for said electric energy to the earth's surface.

Referring now to the drawings 1 indicates what may be called the lower limits or boundaries of the strata of electric energy above the surface 2 of the earth.

3 indicates a balloon which is elevated to a high altitude until it enters the said stra-

tum. The said balloon 3 carries a bar 4 of wood or any other suitable non-conducting material suspended by insulating links 5 or any other suitable form of insulation from the balloon 3. Upon either end of the said bar 4 I mount collectors, one form of which I have illustrated as spheres of coiled wire 6—6′ the outer ends 7 of which terminate in sharp points. The inner turns of the said spheres 6 and 6′ are wrapped around the wooden bar 4 and united as at 8 to a conductor of electric energy, preferably a large copper wire 9. This wire or conductor 9 extends to the earth's surface and may have its end suitably attached to an electric accumulator or other piece of electrical apparatus. I have illustrated one form of my invention in which the conductor 9 is connected to one pole of a storage battery 10 on the earth's surface.

The spiral spheres 6, 6′ are preferably provided with a polished metallic surface to form a good conductor of electricity and the material of said spheres should also be of such a character that it will not rust or corrode or tarnish. A polished copper wire or a copper wire plated with platinum or gold or a solid platinum or gold wire may be used for this purpose, inasmuch as these materials are least affected by moisture and the atmosphere. The said spheres or collectors may be made of smooth wire as shown in the sphere designated by the numeral 6 or of barbed wire, as is shown at 6′ and illustrated on a larger scale in Fig. 2 of the drawings. The latter form is preferable inasmuch as it provides a large number of points through which the electricity may flow to the wire from the surrounding air in the said upper strata of the earth's atmosphere.

In order that the supporting balloon 3 may be held in a relatively fixed position, it should be suitably anchored to the earth's surface. Inasmuch as the balloon 3 must be elevated to a very high position, the weight of the anchoring cables forms an important consideration, and if desired or necessary one or more supplemental balloons 11, 11, 11 may be attached to each of the anchoring cables 12, 12, 12 as illustrated in Fig. 1, to relieve the balloon 3 of such weight as would prevent it from ascending into the said electrical strata. In order that the electricity from the said upper strata of the earth's atmosphere may not be conducted down the anchoring cables 12, 12, 12, I attach them to the supporting balloon 3 and to the supplemental balloons 11 and to the earth's surface through suitable insulating devices 14.

In the form of my invention illustrated in Fig. 1, below the bar 4, I suspend a ring 13 of any suitable material from the balloon 3, and attach the anchoring cables 12 thereto by means of insulating rings 14, 14, 14. I may also provide additional insulating rings 14 between that portion of the anchoring cables 12 between the balloon 3 and the supplemental balloons 11, and also between that part of the cable 12 between the supplemental balloons 12 and the earth's surface. I may also provide, near the earth's surface and at the lower end of the anchoring cables 12, similar insulating links 14. While I have described links as forming a convenient form of insulating device for the purposes above set forth, I do not wish to be construed as being limited to the same, inasmuch as any suitable non-conducting connection may be used in place of the links 14.

The terminals 15, 15 of the storage battery 10 may be connected to any piece of electric apparatus which it is desired to run or operate and if desirable one of the poles of the battery is adapted to be connected by the switch 16 with the earth's surface. The lower ends of the anchoring cables 12 are securely anchored to the earth's surface as at 17.

With the apparatus arranged and connected in the manner illustrated in Fig. 1, the electric energy in the high strata of the earth's atmosphere passes to and through the conductive spiral spheres 6 or 6′ to the conductor 9 and is suitably stored or used at the earth's surface, while the balloons 11 support a part of the weight of the anchoring cables 12, and permit the balloon 3 to ascend as high as is possible, or necessary for it to enter the said electrical strata of the earth's atmosphere. By arranging the anchorage 17 of the cables 12 symmetrically or in any other position than in a straight line, the balloon 3 may be held in a substantially fixed position with relation to the earth.

While I have illustrated in the drawings and have described in the specification a form of apparatus in which my invention may be carried out, it is obvious that the drawings are more or less diagrammatic drawings, that is to say, that the proportions of the various parts are not necessarily those which would operate to the best advantage, inasmuch as certain portions have been shown as greatly enlarged in the drawings for the sake of clearness, and that it is likely that more than one supplemental balloon would be requird for each cable in order to support the weight of the same, and to relieve the supporting balloon 3 of such weight, as would prevent it from ascending into the high electrical strata of the earth's atmosphere, but such changes in form, proportion and arrangement I regard as being fully within the aim and scope of my invention, so long as such forms or modifications fall within the scope of the appended claims. It is also to be understood that the storage battery or accumulator which I have shown as being connected to my collector, is only a type of apparatus which can be operated by the current collected by the spheres 6, 6′ and transmitted to the earth through the wire 9, and when I use the word "accumulator", I mean any piece of useful apparatus which is operated by the current transmitted thereto through the wire or conductor 9.

Having thus described my invention, what I claim and desire to protect by Letters Patent of the United States is:

1. The combination with an electrical collector comprising a bar of non-conducting material, and an open spherical conductor carried by said bar, of means to support said collector in the high electrical strata of the earth's atmosphere.

2. The combination with a balloon, of an electrical collector supported thereby and insulated therefrom, comprising a bar of non-conducting material, and a conductor wound spirally around said bar.

3. The combination with an electrical collector comprising a non-conducting bar, and a conductive wire wound thereon to form an open substantially spherical body, and means to support said collector in the high electrical strata of the earth's atmosphere.

4. The combination with a balloon, of an electrical collector carried thereby and comprising a non-conducting bar, and a polished wire wound spirally thereon to form an open substantially spherical body.

5. The combination with an electrical collector comprising a non-conducting bar, and a wire wound spirally thereon to form an open substantially spherical body, said wire being provided with pointed conducting projections, and means to support said collector in the high electrical strata of the earth's atmosphere.

6. The combination with a balloon, of an electrical collector carried thereby comprising a non-conducting bar, and a conducting wire wound spirally thereon to form open substantially spherical bodies upon the opposite ends thereof.

7. The combination with a balloon, of an electrical collector carried thereby comprising a non-conducting bar, a conducting wire wound spirally thereon to form open substantially spherical bodies upon the opposite ends thereof, an electrical accumulator, and an electrical connection between the said collector and said accumulator.

8. The combination with a balloon, and means to anchor said balloon, of an electrical collector supported by said balloon and insulated therefrom, an electrical accumulator, and a conductor connecting said collector and said accumulator.

9. The combination of an electrical collector, means to support said collector at a high elevation from the earth's surface and within the electrical strata of the earth's atmosphere, an electrical accumulator at the earth's surface, an electrical connection between said collector and said accumulator, and means to insulate said supporting means from said collector and from the earth.

In testimony whereof, I have hereunto set my hand this 25th day of June, 1907.

WALTER I. PENNOCK.

Witnesses:
HUGH F. QUINN,
WM. G. GLENN.

N. TESLA.

APPARATUS FOR TRANSMITTING ELECTRICAL ENERGY.

APPLICATION FILED JAN. 18, 1902. RENEWED MAY 4, 1907.

1,119,732. Patented Dec. 1, 1914.



WITNESSES:

M. Lawson Dyer

Benjamin Miller.

Nikola Tesla, INVENTOR,

BY Kerr, Page & Cooper,

his ATTORNEYS.

UNITED STATES PATENT OFFICE.

NIKOLA TESLA, OF NEW YORK, N. Y.

APPARATUS FOR TRANSMITTING ELECTRICAL ENERGY.

1,119,732. Specification of Letters Patent. **Patented Dec. 1, 1914.**

Application filed January 18, 1902, Serial No. 90,245. Renewed May 4, 1907. Serial No. 371,817.

To all whom it may concern:

Be it known that I, Nikola Tesla, a citizen of the United States, residing in the borough of Manhattan, in the city, county, and State of New York, have invented certain new and useful Improvements in Apparatus for Transmitting Electrical Energy, of which the following is a specification, reference being had to the drawing accompanying and forming a part of the same.

In endeavoring to adapt currents or discharges of very high tension to various valuable uses, as the distribution of energy through wires from central plants to distant places of consumption, or the transmission of powerful disturbances to great distances, through the natural or non-artificial media, I have encountered difficulties in confining considerable amounts of electricity to the conductors and preventing its leakage over their supports, or its escape into the ambient air, which always takes place when the electric surface density reaches a certain value.

The intensity of the effect of a transmitting circuit with a free or elevated terminal is proportionate to the quantity of electricity displaced, which is determined by the product of the capacity of the circuit, the pressure, and the frequency of the currents employed. To produce an electrical movement of the required magnitude it is desirable to charge the terminal as highly as possible, for while a great quantity of electricity may also be displaced by a large capacity charged to low pressure, there are disadvantages met with in many cases when the former is made too large. The chief of these are due to the fact that an increase of the capacity entails a lowering of the frequency of the impulses or discharges and a diminution of the energy of vibration. This will be understood when it is borne in mind, that a circuit with a large capacity behaves as a slackspring, whereas one with a small capacity acts like a stiff spring, vibrating more vigorously. Therefore, in order to attain the highest possible frequency, which for certain purposes is advantageous and, apart from that, to develop the greatest energy in such a transmitting circuit, I employ a terminal of relatively small capacity, which I charge to as high a pressure as practicable. To accomplish this result I have found it imperative to so construct the elevated conductor, that its outer surface, on which the electrical charge chiefly accumulates, has itself a large radius of curvature, or is composed of separate elements which, irrespective of their own radius of curvature, are arranged in close proximity to each other and so, that the outside ideal surface enveloping them is of a large radius. Evidently, the smaller the radius of curvature the greater, for a given electric displacement, will be the surface-density and, consequently, the lower the limiting pressure to which the terminal may be charged without electricity escaping into the air. Such a terminal I secure to an insulating support entering more or less into its interior, and I likewise connect the circuit to it inside or, generally, at points where the electric density is small. This plan of constructing and supporting a highly charged conductor I have found to be of great practical importance, and it may be usefully applied in many ways.

Referring to the accompanying drawing, the figure is a view in elevation and part section of an improved free terminal and circuit of large surface with supporting structure and generating apparatus.

The terminal D consists of a suitably shaped metallic frame, in this case a ring of nearly circular cross section, which is covered with half spherical metal plates P P, thus constituting a very large conducting surface, smooth on all places where the electric charge principally accumulates. The frame is carried by a strong platform expressly provided for safety appliances, instruments of observation, etc., which in turn rests on insulating supports F F. These should penetrate far into the hollow space formed by the terminal, and if the electric density at the points where they are bolted to the frame is still considerable, they may be specially protected by conducting hoods as H.

A part of the improvements which form the subject of this specification, the transmitting circuit, in its general features, is identical with that described and claimed in my original Patents Nos. 645,576 and 649,621. The circuit comprises a coil A which is in close inductive relation with a primary C, and one end of which is connected to a ground-plate E, while its other end is led through a separate self-induction coil B and a metallic cylinder B′ to the terminal D.

The connection to the latter should always be made at, or near the center, in order to secure a symmetrical distribution of the current, as otherwise, when the frequency is very high and the flow of large volume, the performance of the apparatus might be impaired. The primary C may be excited in any desired manner, from a suitable source of currents G, which may be an alternator or condenser, the important requirement being that the resonant condition is established, that is to say, that the terminal D is charged to the maximum pressure developed in the circuit, as I have specified in my original patents before referred to. The adjustments should be made with particular care when the transmitter is one of great power, not only on account of economy, but also in order to avoid danger. I have shown that it is practicable to produce in a resonating circuit as E A B B′ D immense electrical activities, measured by tens and even hundreds of thousands of horse-power, and in such a case, if the points of maximum pressure should be shifted below the terminal D, along coil B, a ball of fire might break out and destroy the support F or anything else in the way. For the better appreciation of the nature of this danger it should be stated, that the destructive action may take place with inconceivable violence. This will cease to be surprising when it is borne in mind, that the entire energy accumulated in the excited circuit, instead of requiring, as under normal working conditions, one quarter of the period or more for its transformation from static to kinetic form, may spend itself in an incomparably smaller interval of time, at a rate of many millions of horse power. The accident is apt to occur when, the transmitting circuit being strongly excited, the impressed oscillations upon it are caused, in any manner more or less sudden, to be more rapid than the free oscillations. It is therefore advisable to begin the adjustments with feeble and somewhat slower impressed oscillations, strengthening and quickening them gradually, until the apparatus has been brought under perfect control. To increase the safety, I provide on a convenient place, preferably on terminal D, one or more elements or plates either of somewhat smaller radius of curvature or protruding more or less beyond the others (in which case they may be of larger radius of curvature) so that, should the pressure rise to a value, beyond which it is not desired to go, the powerful discharge may dart out there and lose itself harmlessly in the air. Such a plate, performing a function similar to that of a safety valve on a high pressure reservoir, is indicated at V.

Still further extending the principles underlying my invention, special reference is made to coil B and conductor B′. The latter is in the form of a cylinder with smooth or polished surface of a radius much larger than that of the half spherical elements P P, and widens out at the bottom into a hood H, which should be slotted to avoid loss by eddy currents and the purpose of which will be clear from the foregoing. The coil B is wound on a frame or drum D^1 of insulating material, with its turns close together. I have discovered that when so wound the effect of the small radius of curvature of the wire itself is overcome and the coil behaves as a conductor of large radius of curvature, corresponding to that of the drum. This feature is of considerable practical importance and is applicable not only in this special instance, but generally. For example, such plates at P P of terminal D, though preferably of large radius of curvature, need not be necessarily so, for provided only that the individual plates or elements of a high potential conductor or terminal are arranged in proximity to each other and with their outer boundaries along an ideal symmetrical enveloping surface of a large radius of curvature, the advantages of the invention will be more or less fully realized. The lower end of the coil B—which, if desired, may be extended up to the terminal D—should be somewhat below the uppermost turn of coil A. This, I find, lessens the tendency of the charge to break out from the wire connecting both and to pass along the support F′.

Having described my invention, I claim:

1. As a means for producing great electrical activities a resonant circuit having its outer conducting boundaries, which are charged to a high potential, arranged in surfaces of large radii of curvature so as to prevent leakage of the oscillating charge, substantially as set forth.

2. In apparatus for the transmission of electrical energy a circuit connected to ground and to an elevated terminal and having its outer conducting boundaries, which are subject to high tension, arranged in surfaces of large radii of curvature substantially as, and for the purpose described.

3. In a plant for the transmission of electrical energy without wires, in combination with a primary or exciting circuit a secondary connected to ground and to an elevated terminal and having its outer conducting boundaries, which are charged to a high potential, arranged in surfaces of large radii of curvature for the purpose of preventing leakage and loss of energy, substantially as set forth.

4. As a means for transmitting electrical energy to a distance through the natural media a grounded resonant circuit, comprising a part upon which oscillations are impressed and another for raising the ten-

sion, having its outer conducting boundaries on which a high tension charge accumulates arranged in surfaces of large radii of curvature, substantially as described.

5. The means for producing excessive electric potentials consisting of a primary exciting circuit and a resonant secondary having its outer conducting elements which are subject to high tension arranged in proximity to each other and in surfaces of large radii of curvature so as to prevent leakage of the charge and attendant lowering of potential, substantially as described.

6. A circuit comprising a part upon which oscillations are impressed and another part for raising the tension by resonance, the latter part being supported on places of low electric density and having its outermost conducting boundaries arranged in surfaces of large radii of curvature, as set forth.

7. In apparatus for the transmission of electrical energy without wires a grounded circuit the outer conducting elements of which have a great aggregate area and are arranged in surfaces of large radii of curvature so as to permit the storing of a high charge at a small electric density and prevent loss through leakage, substantially as described.

8. A wireless transmitter comprising in combination a source of oscillations as a condenser, a primary exciting circuit and a secondary grounded and elevated conductor the outer conducting boundaries of which are in proximity to each other and arranged in surfaces of large radii of curvature, substantially as described.

9. In apparatus for the transmission of electrical energy without wires an elevated conductor or antenna having its outer high potential conducting or capacity elements arranged in proximity to each other and in surfaces of large radii of curvature so as to overcome the effect of the small radius of curvature of the individual elements and leakage of the charge, as set forth.

10. A grounded resonant transmitting circuit having its outer conducting boundaries arranged in surfaces of large radii of curvature in combination with an elevated terminal of great surface supported at points of low electric density, substantially as described.

NIKOLA TESLA.

Witnesses:
M. LAMSON DYER,
RICHARD DONOVAN.

Nov. 12, 1957

L. R. CRUMP

2,813,242

POWERING ELECTRICAL DEVICES WITH ENERGY ABSTRACTED FROM THE ATMOSPHERE

Filed March 12, 1954


RF POWER
35
36
37
41
46
43
40
42
44
TRANSISTOR OSCILLATOR
52
55
61
64
69
70
HIGH VOLTAGE LEVEL d-c POWER
LOW VOLTAGE LEVEL d-c POWER

FIG. 3


1
2
3
5
6
7
10
11
12
15
16
17
20
21
22
23
25
26
+1 v.
27
-2 v.
30
31

FIG. 1


35
36
37
40
41
42
46
43
44
+DC
45
LOAD
-DC

FIG. 2

INVENTOR
Lloyd R. Crump

BY W. E. Thibodeau + A. W. Dew
ATTORNEYS

United States Patent Office

2,813,242

Patented Nov. 12, 1957

2,813,242

POWERING ELECTRICAL DEVICES WITH ENERGY ABSTRACTED FROM THE ATMOSPHERE

Lloyd R. Crump, Silver Spring, Md.

Application March 12, 1954, Serial No. 415,986

1 Claim. (Cl. 321—2)

(Granted under Title 35, U. S. Code (1952), sec. 266)

The invention described herein may be manufactured and used by or for the Government for governmental purposes without payment to me of any royalty thereon.

This invention relates to the convenient and economical provision of power for the operation of electronic circuits and devices using transistors, and of other electrical devices having modest power requirements.

A great advantage of transistors, and a major reason for their enthusiastic reception since their introduction a few years ago, is the fact that they will operate satisfactorily with very low supply voltages and currents. One milliwatt or even less is sufficient to power a transistor in many applications. Various batteries have been developed to provide, in a minimum of space, the relatively minute amounts of power needed by transistors.

My invention provides methods and means that permit transistor circuits, and also other low-powered electrical devices, to be economically and conveniently operated without any batteries whatever, and indeed without any power supply whatever as power supplies are ordinarily conceived.

The invention centers around my discovery that it is practicable to construct operative transistor circuits that are able to abstract from the atmosphere sufficient electromagnetic energy to provide all necessary supply voltages and currents for their own operation. Circuits and devices powered according to my invention will operate indefinitely without any local power source whatever.

I have successfully constructed and demonstrated such circuits. For example, I have constructed a batteryless transistor radio receiver on which I have listened to either nearby or distant broadcast stations as desired, using either headphones or a loudspeaker; this receiver has been powered entirely by electromagnetic energy abstracted from the atmosphere.

From the successful operation of this receiver, and from other experimental work, it becomes clear that, by the methods and means of the invention, a great variety of practical and useful transistor circuits can be powered entirely by energy abstracted from the atmosphere.

Furthermore, as will become apparent below, my invention is applicable to the powering of other electrical devices requiring relatively small amounts of power.

An object of the present invention is to provide methods and means for powering transistor circuits entirely from radiofrequency energy abstracted from the atmosphere.

Another object is to provide methods and means for powering remote radio receivers, low-powered radio transmitters, and other low-powered electrical devices, with energy received by radio from a master station, so that no local power supplies are needed by the devices and so that the powering or non-powering of the remote device is under the control of the master station.

A further object is to provide methods and means for powering transistor circuits and other low-powered electrical devices with radiofrequency energy received from one or more remote radio transmitters.

Other objects, aspects, uses, and advantages of the invention will become apparent from the following description and from the drawing.

Figure 1 is a schematic diagram of a transistor radio receiver in which all necessary power is supplied by energy abstracted from the atmosphere in accordance with the invention.

Figure 2 is a schematic diagram showing a general application of the invention to provide direct-current power to a load.

Figure 3 is a schematic diagram of a system for obtaining a high energy D.-C. source at a high voltage level using energy abstracted from the atmosphere.

Referring to Figure 1, a receiving antenna **1** is connected to antenna coupling coils **2** and **3**, the other ends of which are connected to ground. A parallel resonant circuit consisting of coil **5** and capacitor **6** is coupled to coil **2**. A second parallel resonant circuit consisting of coil **7** and capacitor **10** is coupled to coil **3**. A third parallel resonant circuit consisting of coil **11** and capacitor **12** is also coupled to coil **3**.

Coil **5** and capacitor **6** are tuned to the frequency of a radio transmitter from which it is desired to receive information—for instance, an amplitude-modulated standard broadcast station. The signal received from this transmitter need not be strong. The signal is detected by diode **15** to obtain an audio-frequency information signal. This audio signal is coupled through a capacitor **16** and is amplified by a circuit that includes a transistor **17** having a base **20**, an emitter **21**, and a collector **22**. The amplified audio output of the transistor is coupled through an audio transformer **23** to an electroacoustical transducer, preferably a permanent-magnet dynamic loudspeaker **25** as shown.

The novelty of the invention lies largely in the method and means by which the necessary direct-current power is supplied to the emitter and collector circuits of transistor **17**. This method and means will now be described.

Coil **7** and capacitor **10**, and also coil **11** and capacitor **12**, are tuned to receive radio signals of relatively high strength. It does not matter whether these signals contain information. These power signals are rectified by diodes **26** and **27** to provide direct-current power that is filtered by capacitors **30** and **31**. The D.-C. power thus obtained is utilized to power the transistor **17**.

In the circuit shown, two tuned circuits (coil **7** and capacitor **10**, and coil **11** and capacitor **12**) are tuned to power signals and the D.-C. voltages obtained from each are connected in series. The tuned power circuits may be tuned to the same or different power signals. Under certain circumstances it may be desirable to use more than two tuned power circuits and to tune them to more than two power signals; in this way power can be obtained from several signals and combined. On the other hand, if a strong power signal is available, a single tuned power circuit may suffice to give the needed D.-C. power.

Even weak information signals can be received successfully. A plurality of transistor amplifier stages can be used if desired, or other circuits such as superheterodyne circuits can be used. It is merely necessary that a sufficiently strong power signal or signals be available to provide the small amount of D.-C. needed to power the transistors.

If the information signal happens to be strong, it can be used as the power signal; all of the tuned circuits (coil **5** and capacitor **6**, coil **7** and capacitor **10**, coil **11** and capacitor **12**) are tuned to the information signal.

Engineers who have observed my invention in operation have been surprised at the unexpectedly good results obtained, even with readily available power signals of quite moderate strength. For instance, sufficient power for satisfactory operation of a loudspeaker at low volumes is readily obtained from a 5-kilowatt standard broadcast station 5 miles away, using only an indoor antenna to pick up the power signal as well as information signals. In typical operation under these conditions a D.-C. voltage of about 2.5 to 3 volts is obtained between the emitter and the collector, at a current of about 250 microamperes; D.-C. power input to the transistor is thus of the order of 0.5 to 1 milliwatt. So far as I am aware, no one has ever before discovered and demonstrated the practicability of this method of powering a radio receiver.

Because existing broadcast stations within a radius of a number of miles provide adequate power signals, the invention is readily practicable with existing power signals in almost any location in or near any city in the United States.

Although I have described a transistor radio receiver powered by my invention, it will be readily apparent that the invention is applicable to the powering of any transistor circuit using one or a number of transistors, and to the powering of other devices requiring relatively small amounts of power. For instance, sensitive electromechanical, electrochemical, or electrothermal devices can be operated by the method of the invention.

Referring to Figure 2, which shows a more general embodiment of my invention, an antenna **35** picks up radiofrequency energy from the atmosphere. This energy flows through coil **36**, which is coupled to a tuned circuit consisting of coil **37** and capacitor **40**. The radiofrequency voltage across capacitor **40** is rectified by diode **41** and filtered by a low-pass filter **46** consisting of capacitors **42** and **44** and choke coil **43**. The resulting D.-C. voltage is applied to a load **45**.

In the practice of my invention, larger amounts of power can be obtained for short periods of time by storing received energy in a suitable energy storage device. Stored energy may then be withdrawn at intervals at a more rapid rate than that at which it was received and put into the storage device. In this way the invention can be used to provide short pulses of relatively very high electrical energy. This result can be readily obtained by charging a relatively large capacitor with direct current and then discharging the capacitor rapidly into a load when desired. This rapid discharge can be initiated automatically when the voltage across the capacitor reaches a certain level, or it can be initiated when a transistor radio receiver receives a certain information signal.

Higher voltages can be obtained with the invention by means of well known devices for raising D.-C. voltages as shown in Figure 3. The D.-C. voltage output from the capacitor **44** can be used to power a low frequency transistor oscillator **52** whose A.-C. output is raised to a higher voltage level by the transformer **55**. This relatively high A.-C. voltage can then be rectified by a diode **61** and fed to a capacitor **64** to provide a high energy D.-C. source at a relatively high voltage level at the terminals **69** and **70**. If desired, energy can now be withdrawn from the capacitor **64** at intervals in short pulses of high energy at a high voltage level. Pulsed radio transmission is one of the possible uses for this form of the invention. Other uses would be to provide a single relatively powerful pulse needed to actuate an electrothermal or electromechanical device.

As has been indicated above, in many locations and particularly anywhere in or near most American cities, power signals normally present in the atmosphere are readily available for the easy and convenient practice of the invention. However, the invention also has important applications in systems in which the necessary power signal is generated and transmitted specifically for the operation of the particular system. Such systems can, for example, comprise a master station transmitting all the power that is needed for hundreds or thousands of fixed or mobile transistor receivers or other remote devices over a range of many miles. This eliminates the need for hundreds or thousands, as the case may be, of local power supplies. At the same time, such a system has the advantage that all of the remote devices can be simultaneously activated or deactivated at the will of the master station, simply by starting or stopping the transmission of the power signal. In such systems it will often be advantageous to use power signals of frequencies sufficiently high to permit the use of resonant receiving antennas of small physical dimensions for signal pickup at the remote devices. In addition to the power signal, the master station may transmit an information signal on the same or a different carrier.

Certain types of devices powered entirely by received radio waves are of course well known. The well-known "crystal set" of the early days of radio, which used a diode rectifier to demodulate an amplitude-modulated radiofrequency signal, is an outstanding example of such a device. My invention is readily distinguishable from such prior devices, however. In typical prior devices a modulated radiofrequency signal is applied to a diode to obtain unidirectional half-wave pulses whose amplitudes vary with modulation. These pulses are integrated by means of a capacitor to obtain a unidirectional signal the amplitude of which follows the audiofrequency modulation envelope. If the radiofrequency signal is received with sufficient strength the audio signal may have sufficient power to operate headphones or similar utilization device without power amplification; but the signal is utilized for its information content, rather than to supply non-information-containing power.

My invention, on the other hand, entails the utilization of received radiofrequency energy to supply power to at least one pair of circuit points (across capacitor **31** in Fig. 1, for example), such circuit points requiring power solely for its power content and not for any information or modulation it may contain. In other words, my invention entails the utilization of radiofrequency energy to supply power that would otherwise have to be supplied by batteries, generator, or other local power source.

It will be apparent that the embodiments shown are only exemplary and that various modifications can be made in construction and arrangement within the scope of the invention as defined in the appended claim.

I claim:

An electrical device for obtaining a high energy D.-C. source at a high voltage level using energy abstracted from the atmosphere, said device comprising in combination: resonant means for receiving radio waves, first rectifier means for converting said radio waves into first direct current energy, first capacitor means for storing said first direct current energy, an oscillator powered by said direct current energy, said oscillator producing an A.-C. output, transformer means for raising said A.-C. output to an increased voltage level, second rectifier means for converting the A.-C. output of increased voltage level from said transformer into second direct current energy, and second capacitor means for storing said second direct current energy.

References Cited in the file of this patent

UNITED STATES PATENTS

1,540,998	Plauson	June 9, 1925
2,056,824	Cawley	Oct. 6, 1936
2,553,734	Adler	May 22, 1951
2,569,687	Pan	Oct. 2, 1951
2,647,957	Mallinckrodt	Aug. 4, 1953

OTHER REFERENCES

Turner: "A crystal receiver with transistor amplifier," Radio and Television News, January 1950.

Dec. 17, 1963 W. C. BROWN **3,114,517**

MICROWAVE OPERATED SPACE VEHICLES

Filed May 12, 1959 2 Sheets-Sheet 1



26
10
20
22
26
28
24
26
15
14
18
16
12

FIG. 1



FIG. 3

INVENTOR
WILLIAM C. BROWN
BY H. Vincent Harsha
ATTORNEY

Dec. 17, 1963 W. C. BROWN **3,114,517**

MICROWAVE OPERATED SPACE VEHICLES

Filed May 12, 1959 2 Sheets-Sheet 2


20
22
24
26
30
28
15
14

FIG. 2


32
34
33
40
40
37
40
42
35
40
36
38
15
14

FIG. 4

INVENTOR
WILLIAM C. BROWN
BY H. Vincent Harsha
ATTORNEY

United States Patent Office

3,114,517
Patented Dec. 17, 1963

3,114,517
MICROWAVE OPERATED SPACE VEHICLES

William C. Brown, Weston, Mass., assignor to Raytheon Company, Lexington, Mass., a corporation of Delaware

Filed May 12, 1959, Ser. No. 812,710
11 Claims. (Cl. 244—1)

This invention pertains generally to space vehicles and the like, and more particularly to a novel form of space vehicle and a system for maintaining such vehicle in flight or at a desired location in spaced-apart relationship with respect to a mother planet or the like.

The prior art affords many examples of apparatus adapted to be propelled in spaced-apart relationship with the earth, as well as systems for maintaining this relationship in opposition to the gravitational field thereof. Exemplary devices of this type are conventional aircraft (both jet and propeller driven) and the more modern un-manned or pilotless vehicles such as rocket-propelled missiles. However, the operation of each of these vehicles of the prior art necessitates the expenditure of a fuel carried by the vehicle. Further, while an orbital Earth satellite requires no applied energy in executing a given orbit, enormous quantities of fuel are consumed in launching the satellite into orbit. Also, where the satellite vehicle is designed for the subsequent correction of or other change in the orbital path, a fuel supply must be carried by the satellite in order to provide the desired corrective thrusts.

It is thus apparent that in each of these prior art vehicles a fuel supply must be carried thereby for local consumption in order to initiate, maintain or alter a given flight pattern, whether such pattern involves motion of the vehicle relative to the Earth or a substantially motionless hovering with respect thereto. It therefore follows that the maximum payload capabilities of such vehicles are limited by the fact that the vehicle must support the weight of the fuel carried thereby. Also, such vehicles are not naturally adapted to indefinitely long periods of continuous operation, since the fuel supply therein will eventually be exhausted, necessitating a return of the vehicle to a refueling base, or alternatively, an in-flight refueling process as is accomplished with some conventional aircraft.

The utility of a space vehicle or the like which is capable of sustained flight over an indefinitely long period of time without employing a local fuel supply is evident, and the applications therefor are numerous. For example, a vehicle capable of perpetual operation (except for mechanical failure) and stationed in space above the surface of the Earth, either within or without the atmosphere thereof, may perform alarm and surveillance tasks by radar techniques, along with guidance and protection of defense vehicles, and may simultaneously provide long-haul broadband communications. Systems of such vehicles or platforms may be established to provide radar and communication networks.

These desired operational characteristics are provided by the vehicle of the present invention, which vehicle is energized by means of transmitted microwave electromagnetic energy that is beamed toward the vehicle. The microwave energy incident upon the vehicle is converted into appropriate mechanical forces which produce the desired flight operation of the vehicle. The advantages attendant the utilization of microwave energy, in contrast to electromagnetic energy of other wavelengths, are readily apparent. Microwaves have been generally defined as radio waves whose wavelength is less than 30 centimeters, with a lower wavelength limit on the order of one millimeter or one centimeter sometimes being applied to what is called "the microwave region." The superiority of microwaves is due in part to the fact that

it is generally necessary to focus the transmitted energy so as to achieve a desirably high power density at a remote point or area with respect to a given generator or transmitter power level. In accordance with the laws of optics, the sharpness of the beam produced by an antenna varies as the ratio of antenna dimensions to the wavelength of the transmitted energy. Thus, for a given or desired power density or beam sharpness, a decrease in the wavelength of the transmitted energy permits a corresponding decrease in the dimensions of the antenna. From the standpoint of mechanical convenience, it is generally desirable to employ small antennas and other components, and it is therefore advantageous to employ energy of very short wavelength. In addition, the difficulties encountered in relatively long wave transmission as a result of natural and man-made interference or noise (which noise would interfere with the transmission of radar or communications intelligence via the microwave power beam) do not occur with any appreciable significance at microwave frequencies. Also, where the space vehicle is to be operated at an altitude above the ionosphere, long wave transmission will generally be reflected by the reflecting layers thereof, while microwaves pass through such layers substantially unaffected.

In view of the several advantages stated above, it might appear desirable to employ the shortest wavelength possible commensurate with the power-generating capabilities of the transmitter at the wavelength chosen. A lower limit is fixed, however, for the wavelength that may be used in a practical radiating system in view of the increasing losses due to absorption occurring in the atmosphere at wavelengths below five to ten centimeters. In the one to two centimeter region, there is a peak in absorption by water vapor, and even for dry air the absorption of electromagnetic energy increases very rapidly below one or two centimeters. It may thus be seen that microwaves in a region having the approximate bounds of two and thirty centimeters are readily adaptable to convenient radiation of energy to a remote point with small transmission loss, with the preferred wavelengths being of the order of five or ten centimeters in order to accomplish efficient focusing with a transmitting lens system of reasonable size without inflicting an intolerable power loss by absorption.

The key to the practical utilization of high-power electromagnetic beams for remote energization of space vehicles and the like is a device which will generate large amounts of power within this wavelength region. In addition, many applications of such high-power beams require such refinements as broad electronic bandwidth and low phase distortion, placing the additional requirement of sophisticated performance on the high-power generator. A device which currently satisfies the duel requirements of high power output and refined performance is the Amplitron tube, a relatively new type of crossed-field vacuum tube which may be used as a compact, highly efficient, broadband amplifier capable of handling high peak and average powers, and which generally comprises a circular but non-reentrant, dispersive network matched at both ends over the frequency region of interest, and a reentrant electron beam originating from a continuously-coated (or nearly so) cathode coaxial with the network, with a D.-C. potential being applied between the cathode and anode, and a magnetic field applied parallel to the axis of the cathode and transverse to the electric field between the anode and the cathode. For a more complete description of the Amplitron, reference may be had to my application Serial No. 706,812, filed January 2, 1958, for "Low Level Duplexer System," now United States Letters Patent No. 2,933,723, which issued April 19, 1960. Amplitrons currently available are capable of producing 15 or 20 kilowatts of average radio-frequency power in the neighborhood of ten centimeters in wavelength, and future models are expected to yield 500 kilowatts or more average power, with 50 megawatt peak power.

It is accordingly a primary object of this invention to provide a space vehicle or the like designed for an indefinitely long period of operation either in moving flight or at a selectable location with respect to the Earth or other mother planet, with energy necessary for such operation being supplied to such device in the form of microwave electormagnetic energy.

A further object of the invention is to provide a system for maintaining a space vehicle either in moving flight or at a selectable location with respect to a mother planet or the like in response to microwave electromagnetic energy transmitted from such mother planet to the vehicle.

In accordance with an exemplary embodiment of the present invention, this system for maintaining flight of the space vehicle includes means on the Earth or some other mother planet for radiating microwave energy in a beam directed toward and focused on the vehicle for substantially continuously supplying such vehicle with the power necessary for the operation thereof. The space vehicle of the invention has means associated therewith for receiving and converting incident microwave energy into appropriate forces applied to the vehicle to sustain flight. The received microwave energy may be directly converted into a flight-producing force as by an ion engine or the like, or the microwave energy may be subjected to a mesne conversion to heat. In the latter case, means are provided for applying the heat converted to a suitable fluid medium which is expanded thereby to perform the work necessary to propel or sustain the vehicle.

In one preferred form of the apparatus of the invention, a plurality of thrust-providing engines are mounted for rotary movement about a substantially vertical common axis along which the beam of energy is normally transmitted, with suitable airfoil means being mounted for movement with such engines to provide the lifting force necessary to maintain flight of such vehicle. Means are provided for apportioning the received energy between the several engines in such manner as to selectively energize the engines to maintain the vehicle centered on the transmitted beam.

In an alternative form of the apparatus of this invention, a plurality of thrust-providing engines are symmetrically positioned with respect to the vertical central axis of the vehicle along which the beam of energy is normally transmitted. Means are provided for distributing the received energy between the engines so as to differentially energize the engines to apply corrective forces to the vehicle upon the occurrence of angular or translational displacement of the axis thereof from the center line of the radiated beam.

With the above considerations and objects in mind, the invention itself will now be described in connection with a preferred embodiment thereof given by way of example and not of limitation, and with reference to the accompanying drawings, in which:

FIG. 1 is a perspective view of a preferred form of the apparatus of the present invention, schematically indicating the control system therefor;

FIG. 2 is a partial sectional view in elevation of the vehicle shown in FIG. 1, the section being taken substantially centrally of the vehicle;

FIG. 3 is a plan view of a portion of the apparatus of FIG. 1; and

FIG. 4 is a partial sectional view in elevation of an alternative form of the apparatus of this invention.

Referring now to FIG. 1, one preferred form of the vehicle of the present invention is indicated generally at **10**. As shown, the vehicle **10** is adapted to be maintained in flight or in hovering position with respect to the Earth or other mother planet **12** by means of energy transmitted to the vehicle as radiated microwave electromagnetic energy in beam form, as indicated by lobe **14** having center line **15**. A suitable transmitter **16** is provided for this purpose, along with a beam-forming transmitting antenna **18**. As will be appreciated by those skilled in the art, the representations of the transmitting equipment and microwave beam in FIG. 1 are highly diagrammatic in form, and the present invention is not limited to any particular transmitter or antenna assembly. As a practical matter, however, the reflector of the antenna assembly **18** is considerably larger than most of the reflectors of the prior art in order to focus a large amount of power at a high-altitude (e.g. 65,000 feet) space vehicle. In an exemplary embodiment, the antenna reflector is at least partially supported in a large bowl or other dug-out area on the Earth's surface so as to provide a convenient means of support therefor. Also, the antenna may actually comprise a large number of small horn and reflector assemblies. In addition, the transmitter **16** is capable of much greater power output than most of the prior art transmitters, and, as stated in the earlier paragraphs of this specification, the power-generating element of the transmitter is preferably an Amplitron tube in order to achieve sufficient power output.

The microwave energy that illuminates the vehicle **10** is intercepted by the under or concave side of the reflecting member **20**, the curvature of which is such that the energy received along a substantially straight line parallel to the central axis of the radiated beam of energy is reflected into an annular opening **22** in the frame member **24**. The latter frame member may preferably comprise a hollow waveguide for the received radio-frequency energy, and the energy applied thereto through the opening **22** is, in turn, applied to the several engines **26** connected thereto.

The means for maintaining flight or hovering conditions in the vehicle **10** include the several engines **26**, which effect a rotary motion of the vehicle frame in the direction shown by the arrows about a substantially vertical central axis normally coinciding with the center line of the transmitted beam **14** of microwave energy. Upon such rotary motion of the vehicle frame, a sustaining lift is provided by means of a plurality of airfoil members **28**, which may generally be in the form of the rotary wings of a helicopter or the like. It will be understood that only the basic elements of the vehicle **10** are shown in the drawing, and that other frame members and the like would normally be provided to support a payload of radar, communication or other similar equipment. In this connection, the beam **14** also provides a signal-information link between the ground station and the payload equipment on the vehicle.

FIG. 2 shows in somewhat greater detail the construction of the apparatus of FIG. 1, with the showing of FIG. 2 being taken along a vertical plane through one of the supporting airfoil members **28**. The construction and operation of the several thrust engines will not be discussed in detail herein, since a complete description of engines suitable for this purpose is provided in my application Serial Number 812,697, filed May 12, 1959, now United States Letters Patent No. 3,083,528, which issued April 2, 1963, and assigned to the assignee of the present application. As disclosed in such application, an exemplary embodiment of an engine suitable for use in the vehicle of the present application includes a heat-exchanging container means adapted to be energized by microwave energy to heat a gaseous medium therein and cause expansion of same to produce a jet stream for providing a propulsive thrust. In one preferred form of the invention, the container means comprises an electromagnetic waveguide of lossy characteristics which produces heat upon energization by suitable electromagnetic energy to raise the temperature of a gaseous medium passing therethrough. A member of stacked and closely-spaced electrically lossy plates is preferably mounted within the waveguide to serve as the main means for absorbing microwave energy and converting same into heat, as described in detail in the aforementioned copending application. The plurality of closely spaced plates form therebetween a series of narrow passages through which passes the gaseous medium which is to be heated thereby. The microwave energy employed is of sufficiently high frequency to produce a pronounced skin effect in the waveguide and associated heat-exchanger, so that the energy expended in creating heat in the steady state condition is effectively and quickly transferred to the gaseous medium in which the particular conductor exhibiting the skin effect is immersed. This latter feature is particularly advantageous in transient-state conditions with respect to the ability of the engine of this invention to provide almost instantaneous response to a change in the level of the applied microwave energy, since little or no time lag is involved in converting electromagnetic energy to heat and transferring it to the cooling gas. As is evident, the heated gas may be formed into a jet stream in order to provide propulsion, or a turbine may be driven thereby to provide a rotary shaft output for driving a propeller or the like.

As may be seen in FIG. 2, the engines 26 are supported from the rotary frame member 24 by means of suitable supporting members 30 which also serve as the means for transferring the microwave energy in the interior of the frame member 24 to the interior of the engines 26. Thus, each of the supporting members 30 must be adapted to act as a transmission line of short length for the radio-frequency energy employed. The particular curvature of the reflecting member 20 is chosen so as to effect the reflection of radiated energy indicated in FIG. 2, viz., the energy transmitted toward the vehicle reaches the reflector member 20 along substantially straight parallel paths as shown by the vertical dash-dot lines, and upon reflection all of the received energy is focused on the opening 22 in the frame member 24 so that it may be transferred into the several engines 26.

FIG. 3 shows that the direction of thrust produced by each of the engines 26 is not quite tangential to the circle of rotation thereof. As shown, the engines 26 are mounted at a small angle with respect to the periphery of the frame member 24, so that while the major portion of the thrust produced by each of the engines is tangential to such periphery, a small component thereof is directed away from the center of the vehicle. This construction is employed in order to provide a vehicle which is capable of a self-centering or beam riding operation, as will be more fully described below.

In the operation of the device thus far described, transmitter 16 generates a suitable microwave signal for transmission to the vehicle 10 by means of the radiating antenna 18. In the normal operation of the device, the reflecting member 20 will be centrally positioned in the radiated beam 14, and the energy of the beam will therefore be reflected in equal amounts toward all portions of the annular opening 22 in frame member 24. As a result, the three engines 26 will receive equal amounts of the radio-frequency energy, and normal operation is thereby effected, resulting in a rotary movement of the engines 26 and the frame member 24 about the central vertical axis of the vehicle 10. As mentioned above, such rotational movement of the frame member 24 produces a corresponding rotation of the airfoil members 28 to provide a vertical thrust for maintaining the vehicle 10 in flight or in a hovering position with respect to the mother planet 12.

In order to maintain the vehicle 10 in a desired location with respect to the center-line of the transmitted radio-frequency beam 14, viz., at a centered position with the vertical central axis of the vehicle coinciding with the center line of the transmitted beam, the shape of the concave reflecting surface of member 20 is chosen as described above to reflect energy of the beam 14 equally to the several engines 26 when the vehicle 10 is properly centered in the beam 14. Upon a lateral displacement of the vehicle 10 from the beam 14, one side of the reflecting surface 20 will be illuminated by more radiated energy than the opposite side, and the several engines 26 are thereupon differentially energized to provide corrective lateral forces to achieve recentering of the vehicle in the beam. It will be understood that the desired tolerance as to vehicle position and the lateral dimensions of the beam and the vehicle are so interrelated that a displacement beyond such tolerance will result in a significant degree of such differential energization. For example, if the vehicle 10 were to be displaced toward the right in FIG. 2, the left-hand portion of the reflecting member 20 would lie nearer the center of the beam 14, and the engine shown in FIG. 2 would thereupon receive a greater amount of energy than the other engines. Since the engine 26 of FIG. 2 (as well as each of the remaining engines of the vehicle) provides a component of thrust normal to the circle of rotation thereof and directed away from the center of the vehicle, such additional energization of the engine shown in FIG. 2 will provide a resultant lateral thrust toward the left in this figure. It is evident that the particular engine 26 shown in FIG. 2 will be in motion, and will therefore not remain at the position shown to continuously receive the major portion of the energy intercepted by reflector member 20. As each of the engines 26 passes through the azimuthal position of rotation opposite to the direction of lateral displacement of the vehicle 10 from the center of the beam 14, it then receives a greater energization than the remaining engines, and such differential energization of the several engines 26 continues with the rotational movement of such engines until the vehicle is once again centered in the beam 14. As will be appreciated by those skilled in the art, there must be a minimum lag in the transient response of each of the engines 26 in order to achieve the self-centering action. In this connection, the efficacy of the engine of my aforementioned copending application is evident. As stated above, the thermal time lag of this engine is minimal as a result of the fact that there is a significant skin effect in the microwave heat exchanger, and the transient-state heat changes are produced in intimate proximity to the fluid medium to be heated. As a result of the propinquity of the heat source (the shallow skin effect penetration of the heat-exchanging wall) and the sink (the fluid medium to be heated), such engines are able to respond almost instantaneously to a change in the power input, thus making the self-centering of vehicle 10 feasible.

An alternative form of the apparatus of this invention is shown in FIG. 4, with the vehicle therein being indicated generally at 32. As shown, the vehicle 32 includes reflector numbers 33 and 34 having concave lower surfaces for reflecting incident microwave energy of beam 14 to respective focal points indicated generally at 35 and 37. A plurality of supporting arms 40 are provided for mounting the respective engines 36 and 38 on the reflecting members 34 and 33. The diagrammatic showings of engines 36 and 38 in FIG. 4 are intended to represent jet engines of the type disclosed in my aforementioned copending application, and it is to be understood that the microwave energy necessary for operation of each engine 36 and 38 is received at the upper or intake end thereof. The focus "points" 35 and 37 are in reality areas rather than points, and the engines 36 and 38 are intentionally mounted slightly inboard of a centered position with respect to the associated area 35 or 37, so that normally not all of the energy at each area is directed into the respective engine. This condition is indicated in FIG. 4 by the several reflected dot-dash lines which pass by rather than into the mouths of engines 36 and 38. The particular proportion of energy that is thus normally wasted, as compared to that portion which is collected by the engines, is a matter of choice in design in a given instance, but it is generally desirable to utilize a major portion (e.g., 85 or 90 percent) of the available energy for normal energization of the engines. The magnitude of the portion that is normally wasted will generally be determined in accordance with the peak wind velocities occurring at the altitude at which the vehicle is to operate, as will be better understood in connection with the description of the operation of vehicle 32.

As in the case of the vehicle described in connection with the earlier figures, there will normally be other additional members employed in actual practice in order to support such operational or "pay load" equipment as radar, communications transceivers and the like. The configuration of the reflecting surface of members 33 and 34 is such as to equally divide energy of beam 14 between the engines mounted on the vehicle 32 when such vehicle is centered (both translationally and angularly) with respect to the beam 14, as shown in FIG. 4. As may be seen, the positions in which the engines 36 and 38 are mounted is such as to provide respective thrusts directed upwardly and away from the center of the vehicle 32. Thus, the thrust produced by each of the engines 36 and 38 has a major component substantially parallel to the direction of transmission of the radio-frequency energy, along with a minor component normal thereto and directed away therefrom. By means of this construction, the vehicle 32 may be maintained in flight or hovering condition and may also be controlled as to attitude in the plane of the drawing sheet. As will become apparent in connection with the description of the operation of the apparatus of FIG. 4, it will be necessary to provide three such engines to achieve attitude control in all directions.

In the operation of the vehicle of FIG. 4, when the vehicle is operating in a centered position with respect to the beam of microwave energy 14, with the central vertical axis of the vehicle in registry with the center line of the radiated beam, a propulsive thrust is provided for either propelling the vehicle upwardly or for maintaining a given altitude in opposition to gravitational forces, and the thrust components normal to the direction of the radiated beam 14 are equal in magnitude and so directed as to cancel each other.

When the vehicle 32 is moved from this desired position, as by wind forces or the like, the vehicle is re-centered on the beam by virtue of the structure described. For example, if the vehicle were to suffer translation toward the right as viewed in FIG. 4, the reflecting member 34 would lie nearer the center of the beam 14 and would therefore intercept a greater amount of radio-frequency energy that would member 33. Accordingly, engine 36 would be illuminated with more energy than falls on engine 38, and the oppositely-directed horizontal or lateral components of force exerted by the respective engines would result in a net lateral force applied to the vehicle 32 and directed toward the left in FIG. 4. This lateral correcting force will be so applied until the vehicle is once again entered on the beam. A corresponding operation obtains where the vehicle 32 is displaced laterally to the left in FIG. 4.

In addition, the structure of FIG. 4 provides automatic attitude correction to restore the vehicle to a desired position upon an unwanted angular displacement thereof with respect to the center line of the beam 14 of radiated energy. For example, if the vehicle 32 were to be angularly displaced in a clockwise direction about an axis perpendicular to the drawing sheet and passing through apex 42, the reflecting member 33 would, as a result, be moved toward a position more nearly normal to the direction of the incoming radiant energy. As a result, the angles of incidence and reflection are correspondingly increased, and the focus point 35 is moved toward the engine 38 to supply a greater level of energization thereto. A corresponding decrease in the energization of engine 36 obtains, and a net resultant force is applied to the vehicle 32 about the aforementioned axis at apex 42 to correct the attitude of the vehicle. As is evident, a similar but oppositely-directed operation occurs upon angular displacement of the vehicle 32 in a counter-clockwise direction.

The invention has been described above in considerable detail, and particularly with reference to its application to a space vehicle adapted to be maintained at a desired altitude and lateral position in spaced-apart relationship with respect to the Earth or other mother planet. However, it will be apparent to those skilled in the art that the invention is equally applicable to vehicles adapted for movement relative to such mother planet, whether involving a change in altitude, latitude or longitude, or some combination thereof, so long as a suitable beam of radiant energy is provided. The vehicle of FIG. 4 is shown and described as having a separate dished reflector for each engine. However, it is evident that a single reflecting surface of revolution may equally well be employed, along with a suitable annular collecting and distributing means, as indicated in FIGS. 1 and 2. Conversely, the separate reflectors of FIG. 4 may equally well be employed in the embodiment of FIGS. 1 and 2. Further, the embodiment of FIG. 4 is not necessarily strictly alternative to that of the preceding figures, since the two embodiments may be combined in a single vehicle to perform the combined results of each embodiment.

In addition, the invention is not limited to use of any particular form of thrust-providing engine (except as to the requirement that it be energized by received radiant energy), and the particular means for creating the propulsive thrust may be either a jet stream, a propeller or the like. In this connection, it should be noted that while the vehicle of the present invention is described as being energized solely by microwave electromagnetic energy, the vehicle may also include a conventional engine and fuel supply system for supplementing the action of the microwave engines until such fuel supply is exhausted. Also, the invention is applicable to tethered air vehicles, and where the operating altitude is low, the tethering means may serve as a transmission line for supplying energy to the vehicle without prohibitive losses. Hence the invention is not to be considered as being limited to the particular details given, nor to the specific application to which reference has been made during the description of the apparatus, except insofar as may be required by the scope of the appended claims.

What is claimed is:

1. A thrust-propelled space vehicle adapted to be maintained in a centered position with respect to a beam of radiated energy, comprising a plurality of thrust engines mounted for rotary movement about a common axis, a major portion of the thrust applied to such vehicle by each of said engines being substantially tangential to the circle of rotation thereof with a minor portion of such thrust being directed outwardly from such circle, airfoil means mounted for movement with said engines to apply a lifting force to such vehicle, means for receiving energy radiated toward such vehicle in a beam normally lying along said axis and for applying such energy to said plurality of engines to energize the latter thereby, the energy thus being applied to said engines being apportioned in accordance with the relative positions of each of said engines and the center of such beam upon a displacement of such beam away from said axis, with those engines disposed more nearly in the direction of displacement of such beam center from said axis at any given instant receiving relatively greater energization than others, whereby corrective forces are applied to such vehicle in directions substantially normal to said axis to maintain such vehicle centered on such beam.

2. A thrust-propelled space vehicle comprising a plurality of thrust engines mounted for rotation about a common axis at equal distances therefrom, a major portion of the thrust applied to such vehicle by each of said engines being substantially tangential to the circle of rotation thereof with a minor portion of such thrust being

directed outwardly from such circle, airfoil means mounted for movement with said engines to provide a lift force for sustaining air flight of such vehicle, means for receiving energy radiated toward such vehicle in a beam normally lying along said axis and for applying such energy to said plurality of engines in amounts apportioned in direct relationship with the respective distances of each of said engines from the center line of such beam at any given instant, whereby said engines are energized by such received energy to provide movement of said airfoil means and to provide corrective forces to such vehicle in directions substantially normal to said axis to maintain such vehicle centered on such beam.

3. A thrust-propelled space vehicle in accordance with claim 2, with such radiated energy being microwave electromagnetic energy, said engines including means for converting incident electromagnetic energy into propulsive thrust, and said energy receiving and applying means comprising a concave surface of revolution positioned on said axis to reflect the electromagnetic energy of such beam to said engines.

4. A thrust-propelled space vehicle adapted to be maintained in a centered position with respect to a beam of radiated energy, comprising a pair of thrust engines adapted to be energized by such radiated energy and mounted in symmetrical relationship on opposite sides of a central axis of such vehicle, said pair of engines being mounted in a substantially common plane including such central axis and at angles with respect to such axis to apply to such vehicle respective thrusts having components directed away from such axis, and means symmetrically disposed about such axis for directing energy from such beam to said engines in respective amounts apportioned in accordance with the relative distances between each of said engines and the center line of such beam, whereby said engines are differentially energized to exert corrective thrusts upon displacement of such axis from the center line of such beam.

5. A thrust-propelled space vehicle in accordance with claim 4, with such radiated energy being microwave electromagnetic energy, said engines including means for converting electromagnetic energy into propulsive thrust, and said directing means comprising a pair of concave reflecting members each reflecting a portion of the energy of such beam to a respective one of said converting means.

6. A thrust-propelled space vehicle adapted to be maintained in a centered position with respect to a beam of radiated energy, comprising a plurality of thrust engines adapted to be energized by such radiated energy and mounted in symmetrical relationship with respect to a central axis of such vehicle, the thrust produced by each of said engines being substantially confined to a respective plane including such central axis and having components both parallel with and directed away from such central axis, and means symmetrically disposed about such axis for directing energy from such beam to said engines in respective amounts apportioned in accordance with the relative distances between each of said engines and the center line of such beam, whereby said engines are differentially energized to exert corrective thrusts upon displacement of such axis from the center line of such beam.

7. A system for maintaining a thrust-propelled space vehicle in spaced-apart relationship with a mother planet at a selectable location with respect thereto, comprising a control station on such mother planet for transmitting microwave electromagnetic energy in a substantially vertically-directed beam to such vehicle, a plurality of thrust engines on such vehicle mounted for rotary movement about a substantially vertical common axis, a major portion of the thrust applied to such vehicle by each of said engines being substantially tangential to the circle of rotation thereof with a minor portion of such thrust being directed outwardly from such circle, airfoil means mounted for movement with said engines to provide a lifting force for sustaining air flight of such vehicle, means for receiving energy transmitted toward such vehicle along said axis from said control station and for applying such energy to said plurality of engines to energize the latter thereby, the energy thus being applied to said engines being apportioned in accordance with the relative positions of each of said engines and the center of such beam upon a displacement of such beam away from said axis, with those engines disposed more nearly in the direction of displacement of such beam center from said axis at any given instant receiving relatively greater energization than others, whereby corrective forces are applied to such vehicle in directions substantially normal to said axis to maintain such vehicle centered on such beam.

8. A system for maintaining a thrust-propelled space vehicle in spaced-apart relationship with a mother planet at a selectable location with respect thereto, comprising a control station on such mother planet for transmitting microwave electromagnetic energy in a substantially vertically-directed beam toward such vehicle, a pair of thrust engines on such vehicle adapted to be energized by such radiated energy and mounted in symmetrical relationship on opposite sides of a central axis of such vehicle normally coinciding with the center line of such beam, said pair of engines being mounted in a substantially common plane including such central axis and at angles with respect to such axis to provide respective thrusts to such vehicle having components both normal to and parallel with such axis, and means symmetrically disposed about such axis for directing energy from such beam to said engines in respective amounts apportioned in accordance with the relative distances between each of said engines and the center line of such energy beam, whereby said engines are differentially energized to exert corrective thrusts upon displacement of such axis from the center line of such beam.

9. A system for maintaining a thrust-propelled space vehicle in spaced-apart relationship with a mother planet at a selectable location with respect thereto, comprising a control station on such mother planet for transmitting microwave electromagnetic energy in a substantially vertically-directed beam toward such vehicle, a plurality of thrust engines on such vehicle adapted to be energized by such transmitted energy and mounted in symmetrical relationship with respect to a central axis of such vehicle normally coinciding with the center line of such beam, the thrust produced by each of said engines being substantially confined to a respective plane including such central axis and having components both parallel with and directed away from such central axis, and means symmetrically disposed about such axis for directing energy from such beam to said engines in respective amounts apportioned in accordance with the relative distances between each of said engines and the center line of such energy beam, whereby said engines are differentially energized to exert corrective thrusts upon displacement of such axis from the center line of such beam.

10. A space vehicle, comprising body means, antenna means on said body means for intercepting incident microwave energy, means on said body means for converting said intercepted microwave energy directly into a flight-producing force applied to said body means, and means for directing microwave energy intercepted by said antenna means to said converting means.

11. A system for remotely energizing a space vehicle, comprising means at a control station on a mother planet for generating microwave energy, means at such control station to radiate such microwave energy to such space vehicle, antenna means on said vehicle for intercepting such radiated microwave energy, means on such vehicle for converting said intercepted microwave energy directly into a flight-producing force applied to such vehicle, and

means for directing microwave energy intercepted by said antenna means to said converting means.

References Cited in the file of this patent

UNITED STATES PATENTS

889,790	Kitsee	June 2, 1908
930,508	Vreeland	Aug. 10, 1909
2,471,744	Hershberger	May 31, 1949
2,769,601	Hagopian	Nov. 6, 1956
2,813,242	Crump	Nov. 12, 1959
2,941,764	Lee et al.	June 21, 1960
2,949,550	Brown	Aug. 16, 1960

OTHER REFERENCES

"Vistas in Astronautics," published by Pergamon Press in 1958; page 192.

Advanced Propulsion Systems, published 1959 by Pergamon Press, pp. 81–88.

United States Patent [19]

Phillips, Sr.

[11] **Patent Number: 4,685,047**

[45] **Date of Patent: Aug. 4, 1987**

[54] APPARATUS FOR CONVERTING RADIO FREQUENCY ENERGY TO DIRECT CURRENT

[76] Inventor: **Raymond P. Phillips, Sr.,** 1200 S. Frances, Terrell, Tex. 75160

[21] Appl. No.: **886,138**

[22] Filed: **Jul. 16, 1986**

[51] **Int. Cl.⁴** **H02M 7/06**

[52] **U.S. Cl.** **363/126**; 307/151

[58] **Field of Search** 363/125, 126; 307/151

[56] References Cited

U.S. PATENT DOCUMENTS

649,621	11/1901	Tesla	455/39
685,957	5/1902	Tesla	455/619
3,434,678	3/1969	Brown et al.	307/151
3,445,767	5/1969	Beard	324/78
3,678,365	8/1972	Fremiot	307/151
3,723,891	3/1973	Whitely	307/246
3,760,257	9/1973	Fletcher et al.	307/151
3,784,845	1/1974	Haas	307/519
3,792,290	2/1974	Brocker	307/522
3,944,935	3/1976	Plant	307/519
4,079,268	3/1978	Fletcher et al.	307/151
4,079,325	3/1978	Mawhinney et al.	307/261
4,085,377	4/1978	Turski et al.	307/519
4,195,237	3/1980	Meslener	307/261
4,297,557	10/1981	Tyler et al.	219/10.55 B
4,360,741	11/1982	Fitzsimmons et al.	307/151
4,360,865	11/1982	Yasumura et al.	363/126
4,393,441	8/1983	Enge	363/126

Primary Examiner—Patrick R. Salce
Assistant Examiner—Jeffrey Sterrett
Attorney, Agent, or Firm—Millen & White

[57] ABSTRACT

Apparatus for and methods of converting radio frequency energy into direct current for generating electric power includes a dipolar antenna for receiving radio frequency energy and a circuit connected thereto for converting the radio frequency energy to direct current. The circuit has a positive output line connected to one pole of the antenna and a negative output line connected to the other pole of the antenna. A positive transmitting diode is in the positive output line and a negative transmitting diode is in the negative output line. First and second bus lines and a pair of tuned circuits of opposite polarity couple the positive output line and negative line to the bus line with one of the bus lines being connected to ground. Each tuned circuit includes a first bridging line connecting the positive output line to the first and second ground lines and a second bridging line connecting the negative output line to the first and second ground lines. Each bridging line has a diode therein oriented at a polarity which is reverse with respect to the input diode. The bridging lines of each tuned circuit are connected to one another by an inductance and have capacitors disposed between the diode and the bus lines. A direct current device is connected to the positive line of the circuit.

11 Claims, 1 Drawing Figure




TO SIMILAR CELLS
+
-
C
RF
C1
D4
C2
D3
RF
D1
D2

APPARATUS FOR CONVERTING RADIO FREQUENCY ENERGY TO DIRECT CURRENT

BACKGROUND OF THE INVENTION

1. Field of the Invention

The instant invention relates to methods of an apparatus for converting radio frequency energy to direct current; more particularly, the instant invention relates to methods and apparatus for converting radio frequency energy to direct current wherein the direct current is of sufficient magnitude to power devices such as battery charges and electric motors without the use of amplification.

2. Technical Considerations in Prior Art

There has long been interest in technology directed to transmitting electrical energy over a distance without utilizing conductors, such as wire conductors. Development of such a technology has enormous potential. This was first recognized by Nikola Tesla who in 1899 constructed a 200 foot Tesla coil rated at 300 kilowatts and 150 kilocycles. Tesla hoped to set up standing waves of electrical energy around the whole surface of the earth, so that receiving antennas set at optimum points could tap the power when needed. Tesla was able to light hundreds of lamps at a distance of about 40 kilometers with his device without utilizing electrical conductors. The scheme has generally remained a scientific curiosity but has provided the initial groundwork for current developments wherein attempts are being made to transmit power by microwaves. However, power transmitted by microwaves is envisioned in the form of a beam of very high intensity which is focused from a microwave generator to a receiving antenna. This technology is envisioned as being used for many types of purposes such as transmitting microwave energy collected from gigantic solar power satellites and "star wars"-type weapons systems. However, the focused microwave beam is not suitable for many applications in that the beam must be directed toward a receiving antenna and cannot be transmitted through most objects, including living objects, without destroying the objects.

The instant invention relies on converting energy from standing waves which are emitted from radio frequency antennas in the RF range rather than the microwave range. Of particular interest are very low frequencies which are not used in communications and are available for transmitting power. Also of interest with respect to the instant invention are the low frequency waves emitted by the earth due to pulsation thereof caused by its magnetic field. These low frequency standing "earth" waves can be picked up by receivers tuned thereto.

SUMMARY OF THE INVENTION

It is an object of the invention to provide new and improved methods of an apparatus for converting radio frequency currents to direct current for practical uses other than communications, wherein the direct current energy converted from the radio frequency input energy does not require amplification.

Upon further study of the specification and appended claims, further objects and advantages of this invention will become apparent to those skilled in the art.

The instant invention contemplates an RF antenna for receiving radio waves. The RF antenna connected to a circuit configured in accordance with the principles of the instant invention to convert the RF signals to direct current. The radio frequency signals received by the antenna are transmitted to first and second leads, with one lead being rectified to transmit positive voltage and the other lead being rectified to transmit negative voltage. The positive voltage lead being connected directly to a positive output line and the negative voltage lead being connected directly to a negative output line. The positive output line is connected to a pair of bus lines through a first pair of capacitors, while the negative output line is connected to the pair of bus lines by a second pair of capacitors. Disposed between the first bus line and the positive output line is a reverse diode of negative polarity, while disposed between the negative output line and first bus line is a reverse diode of positive polarity. The positive and negative output lines are connected to one another through an inductance which is in parallel with the capacitors of the first and second pair connected between the second bus line and the positive and negative output lines.

In accordance with one embodiment of the invention the afore-described circuit is duplicated for each positive and negative output line. In accordance with another embodiment of the invention, the afore-described circuitry is coupled to additional circuits identically configured in order to increase the direct current output of the arrangement.

In accordance with a further configuration of the invention, the antenna utilized is a dipolar antenna of aluminum wire arranged in a "butterfly" configuration.

The instant invention further contemplates the method of utilizing the afore-described elements so as to generate direct current having sufficient power to perform tasks such as charging batteries, lighting lamps and powering direct current electric motors without the use of amplifiers.

BRIEF DESCRIPTION OF THE DRAWING

Various other objects, features and attendant advantages of the present invention will be more fully appreciated as the same becomes better understood when considered in connection with the accompanying drawing, in which like reference characters designate the same or similar parts throughout the several views, and wherein:

There is shown a diagram of a circuit in accordance with the instant invention in combination with a driven device and a dipolar antenna which receives radio frequency waves which are converted to DC current for powering the driven device.

DESCRIPTION OF THE PREFERRED EMBODIMENT

Referring now to the drawing, there is shown a dipolar antenna, designated generally by the numeral **10**, which receives radio frequency waves from an RF transmitter **11**. The radio frequency waves are transmitted to a radio frequency to direct current converting circuit, designated generally by the numeral **12**, through a coaxial cable **13** and DC current from the circuit **12** is used to power an output device, designated generally by the numeral **15**, which may for example by a battery charger DC motor or lighting device. The circuit **12** has no other power inputs other than the radio frequency energy transmitted thereto by the antenna **10** and therefore includes no amplifiers for amplifying the RF energy.

The source of radio frequencies convertible to direct current by the circuit shown may include sources of high frequency, low frequency (LF), very low frequency (VLF) and extremely low frequency (ELF) radio waves as well as seismic vibration of the earth's magnetic fields.

Preferably, the dipolar antenna **10** is formed of two triangular loops of aluminum wire **16** and **17**, one of which is connected to the annular conductor **18** of the coaxial cable **13** and the other of which is connected to the center conductor **19** of the coaxial cable. The size of the bipolar antenna **10** is dependent on the particular application to which it is put. In accordance with one embodiment of the invention, the antenna **10** is approximately 12 inches in width and 18 inches in length. Such an antenna is used to receive five watt energy, such as that generated by a walkie-talkie or citizen-band radio.

The annular conductor **18** of the coaxial cable **13** is connected to a positive lead **21** of the circuit **12**, while the center conductor **19** of the coaxial cable is connected to a negative lead **22** of the circuit. A positive transmitting diode D1 is disposed between the lead **21** and the remainder of the circuit **12** while a negative transmitting diode D2 is disposed between the lead **21** to a positive output line **25** while the negative diode D2 is connected to a negative output line **26**. Accordingly, the positive voltages with respect to ground are produced on output line **25** and negative voltages with respect to ground are produced on output line **26**.

In order to provide a DC output of sufficient power, a plurality of inductance-capacitance, RF, tuned circuits **30**, each forming a positive cell, or a negative cell, are utilized for connecting the positive output line **25** and negative output line **26** to first and second bus lines **31** and **32**, respectively. Bus line **32** is connected to ground while bus line **32** can be connected to circuits similar to circuit **12**. The positive output line **25** is connected by a first bridging line **33** to the first and second bus lines **31** and **32** while the negative output line **26** is connected by a second bridging line **34** to the first and second bus lines. The bridging line **33** has capacitors C1 and C2 disposed between the positive output line **25** and the first and second bus lines **31** and **32**, while the bridging line **34** also has capacitors C1 and C2 dispensed between the negative output line **26** and the first and second bus lines **31** and **32**. Connected between the bridging lines **33** and **34**, is an inductor **35** which serves as an RF choke, while disposed between the positive output line **25** and the capacitor C1 there is a negative polarity diode D4 referred to herein as a bridging diode and disposed between the negative output line **26** and capacitor C1 in line **34** there is a positive polarity diode D3 referred to herein as a bringing diode. As is seen of the drawing, the RF tuned circuit cell **30** is repeated a plurality of times. In the specific example shown, the circuit **12** has separate cells **30**, **37**, **38** and **39**. The cells **30** and **38** are of opposite polarity and balance one another while the cells **37** and **39** of opposite polarity and also balance one another. In order for the system to function, a pair of opposite polarized cells must be utilized. The particular number of cells **30** and the value of the components thereof are determined by the configuration of the dipolar antenna **10** and the power and frequency of the RF transmitter **11**.

The radio frequency to direct current conversion circuit **12** may itself be connected to a duplicate circuit via pins **41** so as to provide additional direct current output on lines similar to positive output line **25** and negative output line **26** the output lines may be connected together in order to boost the total output of the system.

An operative embodiment of the invention utilizes the following elements:

Diodes D1, D2, D3 and D4—Germanium Diodes, Archer **1** N34A, Catalog #1123.
Inductor **35**-47 Milli henry R. F. Choke
Capacitors C1 and C2-0.**47** Pico Farads at 200 volts
Coaxial Cable **13**—50 ohms
Dipolar Antenna **10**—aluminum wire triangular loops approximately 12 inches by 18 inches.

From the foregoing description, one skilled in the art can easily ascertain the essential characteristics of this invention, and without departing from the spirit and scope thereof, can make various changes and modifications of the invention to adapt it to various usages and conditions.

What is claimed is:

1. Apparatus for converting radio frequency energy into direct current for generating electric power, the apparatus comprising:

a dipolar input for receiving radio frequency energy;

a positive output line connected to one pole of the dipolar input and a negative output line connected to the other pole of the dipolar input;

a positive transmitting input diode means in the positive output line and a negative transmitting input diode means in the negative output line;

first and second bus lines and a pair of tuned circuits of opposite polarity coupling the positive output line and negative output line to the bus lines, one of the bus lines being connected to ground;

each tuned circuit including a first bridging line connecting the positive output line to the first and second bus lines and a second bridging line connecting the negative output line to the first and second bus lines, each bridging line having a bridging diode means therein oriented at a polarity which is reverse with respect to the transmitting input diode means of the respective output line; the bridging lines of each tuned circuit being connected to one another by an inductance and having capacitors disposed between the bridging diode means thereon and the bus lines, and

a direct current device connected to the bridging lines of the tuned circuit.

2. The apparatus of claim **1**, wherein there are a plurality of similarly configured tuned circuits connected between the output lines and the bus lines.

3. The apparatus of claim **2**, wherein there are a plurality of radio frequency-to-direct current conversion circuits connected to one another to provide a direct current power array tuned to a specific radio frequency such as a high frequency source, low frequency source, very low frequency source, extremely low frequency source, or source created by seismic vibrations of the earth's magnetic field.

4. The apparatus of claim **3** wherein the dipolar input is a dipolar antenna.

5. The apparatus of claim **1**, wherein the device connected to the output lines is a direct current motor.

6. The apparatus of claim **1**, wherein the device connected to the output line is an illuminating device.

7. The apparatus of claim **1**, wherein the device connected to the output lines is a battery charger.

8. The apparatus of claim **1**, wherein the device connected to the output lines is a DC-to-AC inverter.

9. The apparatus of claim **1**, wherein there are a plurality of radio frequency to direct current converter circuits connected to one another to form an array of circuits tuned to a particular radio frequency.

10. The apparatus of claim **1** wherein the dipolar input is a dipolar antenna.

11. The apparatus of claim **10**, wherein the dipolar antenna utilizes aluminum wire arranged in pair of triangular loops.

* * * * *

UNITED STATES PATENT AND TRADEMARK OFFICE

CERTIFICATE OF CORRECTION

PATENT NO. : 4,685,047
DATED : August 4, 1987
INVENTOR(S) : Raymond P. Phillips, Sr.

It is certified that error appears in the above-identified patent and that said Letters Patent is hereby corrected as shown below:

On the Title Page "11 Claims" should read -- 12 Claims --.

Column 4, Claim 1, Line 21:

Reads: "into direct current for generating electric power, the"

Should Read: --into direct current, the--

Column 4, Claim 5, Line 62:

Reads: "nected to the output lines is a direct current motor."

Should Read: --nected to the output lines is a direct-current motor.--

Column 4, Claim 8, Line 68:

Reads: "nected to the output lines is a DC-to-AC inverter. "

Should Read: --nected to the output lines is a DC-to-AC converter.--

Please add the following new claim:

--12. The apparatus of claim 1 wherein the dipolar input is a coazial cable.--

Signed and Sealed this

Third Day of November, 1987

Attest:

DONALD J. QUIGG

Attesting Officer

Commissioner of Patents and Trademarks

UNITED STATES PATENT AND TRADEMARK OFFICE

CERTIFICATE OF CORRECTION

PATENT NO. : 4,685,047

DATED : August 4, 1987

INVENTOR(S) : Raymond P. Phillips, Sr.

It is certified that error appears in the above-identified patent and that said Letters Patent is hereby corrected as shown below:

On the Title Page, Item [57],
IN THE ABSTRACT:

Line 1: Reads: "Apparatus for and methods of converting radio fre-"
Should Read: --Apparatus for converting radio fre- --

Line 9: "transmitting diode is in the positive output line and a"
--transmitting diode is located in the positive output line and a"

Line 10: "negative transmitting diode is in the negative output"
--negative transmitting diode is located in the negative output--

Line 24: "to the positive line of the circuit"
--to the output lines of the circuit--

COL. 1
Line 9: "the instant invention relates to methods of an appara-"
--the instant invention relates to appara- --

COL. 1
Line 8: "to methods and apparatus for converting radio fre-"
--to apparatus for converting radio fre- --

COL. 1
Line 14: "as battery charges and electric motors without the use"
--as battery chargers and electric motors without the use--

UNITED STATES PATENT AND TRADEMARK OFFICE

CERTIFICATE OF CORRECTION

PATENT NO. : 4,685,047

Page 2 of 4

DATED : August 4, 1987

INVENTOR(S) : Raymond P. Phillips, Sr.

It is certified that error appears in the above-identified patent and that said Letters Patent is hereby corrected as shown below:

COL. 1
Line 29: "tific curiosity but has provided the initial groundwork"
--tific curiosity, but has provided the initial groundwork--

COL. 1
Line 57: "improved methods of an apparatus for converting radio"
--improved apparatus for converting radio--

COL. 2
Line 6: "tive voltage. The positive voltage lead being connected"
--tive voltage. The positive voltage lead is connected--

COL. 2
Line 8: "age lead being connected directly to a negative output"
--age lead is connected directly to a negative output--

COL. 2
Line 58: "ted to a radio frequency to direct current converting"
--ted to a radio frequency-to-direct current converting--

COL. 2
Line 62: "by the numeral 15, which may for example by a battery"
--by the numeral 15, which may for example be a battery--

UNITED STATES PATENT AND TRADEMARK OFFICE
CERTIFICATE OF CORRECTION

PATENT NO. : 4,685,047 Page 3 of 4
DATED : August 4, 1987
INVENTOR(S) : Raymond P. Phillips, Sr.

It is certified that error appears in the above-identified patent and that said Letters Patent is hereby corrected as shown below:

COL. 3
Line 23: "and the remainde of the circuit 12 while a negative"
--and the remainder of the circuit 12, while a negative--

COL. 3
Line 25: "to a positive output line 25 while the negative diode D2"
--a positive output line 25, while the negative transmitting diode D2--

COL. 3
Line 31: "a plurality of inductance-capacitance, RF, tuned cir-"
--a plurality of inductance-capacitance, RF-tuned cir- --

COL. 3
Line 32: "cuits 30, each forming a positive cell, or a negative cell,"
--cuits 30, each forming either a positive cell or a negative cell,--

COL. 3
Line 50: "polarity diode D4 referred to herein as a bridging diode"
--polarity diode D4, referred to herein as a bridging diode--

COL. 3
Line 53: "D3 referred to herein as a bringing diode. As is seen of"
--D3, referred to herein as a bridging diode. As is seen of--

COL. 3
Line 58: "other while the cells 37 and 39 of opposite polarity and"
--other, while the cells 37 and 39 of opposite polarity--

UNITED STATES PATENT AND TRADEMARK OFFICE
CERTIFICATE OF CORRECTION

PATENT NO. : 4,685,047 Page 4 of 4

DATED : August 4, 1987

INVENTOR(S) : Raymond P. Phillips, Sr.

It is certified that error appears in the above-identified patent and that said Letters Patent is hereby corrected as shown below:

COL. 3
Line 67: "via pins 41 so as to provide additional direct current"
--via pin 41 so as to provide additional direct current--

COL. 4
Line 1: "negative output line 26 the output lines may be con-"
--negative output line 26. The output lines may be con- --

Claim 12, line 2: Change "coazial" to --coaxial--.

Signed and Sealed this

Eleventh Day of July, 1989

Attest:

DONALD J. QUIGG

Attesting Officer

Commissioner of Patents and Trademarks

United States Patent [19]
Eastlund

[11] **Patent Number:** **4,686,605**
[45] **Date of Patent:** **Aug. 11, 1987**

[54] METHOD AND APPARATUS FOR ALTERING A REGION IN THE EARTH'S ATMOSPHERE, IONOSPHERE, AND/OR MAGNETOSPHERE

[75] Inventor: **Bernard J. Eastlund**, Spring, Tex.
[73] Assignee: **APTI, Inc.**, Los Angeles, Calif.
[21] Appl. No.: **690,333**
[22] Filed: **Jan. 10, 1985**
[51] **Int. Cl.**^{4} **H05B 6/64;** H05C 3/00; H05H 1/46
[52] **U.S. Cl.** .... **361/231;** 89/1.11; 380/59; 244/158 R
[58] **Field of Search** .... 361/230, 231; 244/158 R; 376/100; 89/1.11; 380/59

[56] **References Cited**

PUBLICATIONS

Liberty Magazine, (2/35) p. 7 N. Tesla.
New York Times (9/22/40) Section 2, p. 7 W. L. Laurence.
New York Times (12/8/15) p. 8 Col. 3.

Primary Examiner—Salvatore Cangialosi
Attorney, Agent, or Firm—Roderick W. MacDonald

[57] ABSTRACT

A method and apparatus for altering at least one selected region which normally exists above the earth's surface. The region is excited by electron cyclotron resonance heating to thereby increase its charged particle density. In one embodiment, circularly polarized electromagnetic radiation is transmitted upward in a direction substantially parallel to and along a field line which extends through the region of plasma to be altered. The radiation is transmitted at a frequency which excites electron cyclotron resonance to heat and accelerate the charged particles. This increase in energy can cause ionization of neutral particles which are then absorbed as part of the region thereby increasing the charged particle density of the region.

15 Claims, 5 Drawing Figures



FIG. 1


NORTH POLE
10
20
M_B
11
12
15
C
TRANSMITTER
16
14
POWER GENERATOR
17
EQUATOR
13
R
M_B
SOUTH POLE

FIG. 2


R_2
M_B1
[F=-μ•∇B]
R_1

FIG. 3


[F=-μ•∇B]
R2
11
θ
12
e
i
i
n
i
i
i
e
R1
n
i
10

FIG. 4


30
R3
11
12
f3
33
20
15
31
10
32


TREATER
MHD GENERATOR
TRANSMITTER

FIG. 5

METHOD AND APPARATUS FOR ALTERING A REGION IN THE EARTH'S ATMOSPHERE, IONOSPHERE, AND/OR MAGNETOSPHERE

DESCRIPTION

1. Technical Field

This invention relates to a method and apparatus for altering at least one selected region normally existing above the earth's surface and more particularly relates to a method and apparatus for altering said at least one region by initially transmitting electromagnetic radiation from the earth's surface essentially parallel to and along naturally-occurring, divergent magnetic field lines which extend from the earth's surface through the region or regions to be altered.

2. Background Art

In the late 1950's, it was discovered that naturally-occuring belts exist at high altitudes above the earth's surface, and it is now established that these belts result from charged electrons and ions becoming trapped along the magnetic lines of force (field lines) of the earth's essentially dipole magnetic field. The trapped electrons and ions are confined along the field lines between two magnetic mirrors which exist at spaced apart points along those field lines. The trapped electrons and ions move in helical paths around their particular field lines and "bounce" back and forth between the magnetic mirrors. These trapped electrons and ions can oscillate along the field lines for long periods of time.

In the past several years, substantial effort has been made to understand and explain the phenomena involved in belts of trapped electrons and ions, and to explore possible ways to control and use these phenomena for beneficial purposes. For example, in the late 1950's and early 1960's both the United States and U.S.S.R. detonated a series of nuclear devices of various yields to generate large numbers of charged particles at various altitudes, e.g., 200 kilometers (km) or greater. This was done in order to establish and study artifical belts of trapped electrons and ions. These experiments established that at least some of the extraneous electrons and ions from the detonated devices did become trapped along field lines in the earth's magnetosphere to form artificial belts which were stable for prolonged periods of time. For a discussion of these experiments see "The Radiation Belt and Magnetosphere", W. N. Hess, Blaisdell Publishing Co., 1968, pps. 155 et sec.

Other proposals which have been advanced for altering existing belts of trapped electrons and ions and/or establishing similar artificial belts include injecting charged particles from a satellite carrying a payload of radioactive beta-decay material or alpha emitters; and injecting charged particles from a satellite-borne electron accelerator. Still another approach is described in U.S. Pat. No. 4,042,196 wherein a low energy ionized gas, e.g., hydrogen, is released from a synchronous orbiting satellite near the apex of a radiation belt which is naturally-occurring in the earth's magnetosphere to produce a substantial increase in energetic particle precipitation and, under certain conditions, produce a limit in the number of particles that can be stably trapped. This precipitation effect arises from an enhancement of the whistler-mode and ion-cyclotron mode interactions that result from the ionized gas or "cold plasma" injection.

It has also been proposed to release large clouds of barium in the magnetosphere so that photoionization will increase the cold plasma density, thereby producing electron precipitation through enhanced whistler-mode interactions.

However, in all of the above-mentioned approaches, the mechanisms involved in triggering the change in the trapped particle phenomena must be actually positioned within the affected zone, e.g., the magnetosphere, before they can be actuated to effect the desired change.

The earth's ionosphere is not considered to be a "trapped" belt since there are few trapped particles therein. The term "trapped" herein refers to situations where the force of gravity on the trapped particles is balanced by magnetic forces rather than hydrostatic or collisional forces. The charged electrons and ions in the ionosphere also follow helical paths around magnetic field lines within the ionosphere but are not trapped between mirrors, as in the case of the trapped belts in the magnetosphere, since the gravitational force on the particles is balanced by collisional or hydrostatic forces.

In recent years, a number of experiments have actually been carried out to modify the ionosphere in some controlled manner to investigate the possibility of a beneficial result. For detailed discussions of these operations see the following papers: (1) Ionospheric Modification Theory; G. Meltz and F. W. Perkins; (2) The Platteville High Power Facility; Carrol et al.; (3) Arecibo Heating Experiments; W. E. Gordon and H. C. Carlson, Jr.; and (4) Ionospheric Heating by Powerful Radio Waves; Meltz et al., all published in Radio Science, Vol. 9, No. 11, November, 1974, at pages 885–888; 889–894; 1041–1047; and 1049–1063, respectively, all of which are incorporated herein by reference. In such experiments, certain regions of the ionosphere are heated to change the electron density and temperature within these regions. This is accomplished by transmitting from earth-based antennae high frequency electromagnetic radiation at a substantial angle to, not parallel to, the ionosphere's magnetic field to heat the ionospheric particles primarily by ohmic heating. The electron temperature of the ionosphere has been raised by hundreds of degrees in these experiments, and electrons with several electron volts of energy have been produced in numbers sufficient to enhance airglow. Electron concentrations have been reduced by a few percent, due to expansion of the plasma as a result of increased temperature.

In the Elmo Bumpy Torus (EBT), a controlled fusion device at the Oak Ridge National Laboratory, all heating is provided by microwaves at the electron cyclotron resonance interaction. A ring of hot electrons is formed at the earth's surface in the magnetic mirror by a combination of electron cyclotron resonance and stochastic heating. In the EBT, the ring electrons are produced with an average "temperature" of 250 kilo electron volts or kev (2.5×10^9K) and a plasma beta between 0.1 and 0.4; see, "A Theoretical Study of Electron—Cyclotron Absorption in Elmo Bumpy Torus", Batchelor and Goldfinger, Nuclear Fusion, Vol. 20, No. 4 (1980) pps. 403–418.

Electron cyclotron resonance heating has been used in experiments on the earth's surface to produce and accelerate plasmas in a diverging magnetic field. Kosmahl et al. showed that power was transferred from the electromagnetic waves and that a fully ionized plasma

was accelerated with a divergence angle of roughly 13 degrees. Optimum neutral gas density was 1.7×10^{14} per cubic centimeter; see, "Plasma Acceleration with Microwaves Near Cyclotron Resonance", Kosmahl et al., Journal of Applied Physics, Vol. 38, No. 12, Nov., 1967, pps. 4576–4582.

DISCLOSURE OF THE INVENTION

The present invention provides a method and apparatus for altering at least one selected region which normally exists above the earth's surface. The region is excited by electron cyclotron resonance heating of electrons which are already present and/or artifically created in the region to thereby increase the charged particle energy and ultimately the density of the region.

In one embodiment this is done by transmitting circularly polarized electromagnetic radiation from the earth's surface at or near the location where a naturally-occurring dipole magnetic field (force) line intersects the earth's surface. Right hand circular polarization is used in the northern hemisphere and left hand circular polarization is used in the southern hemisphere. The radiation is deliberately transmitted at the outset in a direction substantially parallel to and along a field line which extends upwardly through the region to be altered. The radiation is transmitted at a frequency which is based on the gyrofrequency of the charged particles and which, when applied to the at least one region, excites electron cyclotron resonance within the region or regions to heat and accelerate the charged particles in their respective helical paths around and along the field line. Sufficient energy is employed to cause ionization of neutral particles (molecules of oxygen, nitrogen and the like, particulates, etc.) which then become a part of the region thereby increasing the charged particle density of the region. This effect can further be enhanced by providing artificial particles, e.g., electrons, ions, etc., directly into the region to be affected from a rocket, satellite, or the like to supplement the particles in the naturally-occurring plasma. These artificial particles are also ionized by the transmitted electromagnetic radiation thereby increasing charged particle density of the resulting plasma in the region.

In another embodiment of the invention, electron cyclotron resonance heating is carried out in the selected region or regions at sufficient power levels to allow a plasma present in the region to generate a mirror force which forces the charged electrons of the altered plasma upward along the force line to an altitude which is higher than the original altitude. In this case the relevant mirror points are at the base of the altered region or regions. The charged electrons drag ions with them as well as other particles that may be present. Sufficient power, e.g., 10^{15} joules, can be applied so that the altered plasma can be trapped on the field line between mirror points and will oscillate in space for prolonged periods of time. By this embodiment, a plume of altered plasma can be established at selected locations for communication modification or other purposes.

In another embodiment, this invention is used to alter at least one selected region of plasma in the ionosphere to establish a defined layer of plasma having an increased charged particle density. Once this layer is established, and while maintaining the transmission of the main beam of circularly polarized electromagnetic radiation, the main beam is modulated and/or at least one second different, modulated electromagnetic radiation beam is transmitted from at least one separate source at a different frequency which will be absorbed in the plasma layer. The amplitude of the frequency of the main beam and/or the second beam or beams is modulated in resonance with at least one known oscillation mode in the selected region or regions to excite the known oscillation mode to propagate a known frequency wave or waves throughout the ionosphere.

BRIEF DESCRIPTION OF THE DRAWINGS

The actual construction, operation, and apparent advantages of this invention will be better understood by referring to the drawings in which like numerals identify like parts and in which:

FIG. **1** is a simplified schematical view of the earth (not to scale) with a magnetic field (force) line along which the present invention is carried out;

FIG. **2** is one embodiment within the present invention in which a selected region of plasma is raised to a higher altitude;

FIG. **3** is a simplified, idealized representation of a physical phenomenon involved in the present invention; and

FIG. **4** is a schematic view of another embodiment within the present invention.

FIG. **5** is a schematic view of an apparatus embodiment within this invention.

BEST MODES FOR CARRYING OUT THE INVENTION

The earth's magnetic field is somewhat analogous to a dipole bar magnet. As such, the earth's magnetic field contains numerous divergent field or force lines, each line intersecting the earth's surface at points on opposite sides of the Equator. The field lines which intersect the earth's surface near the poles have apexes which lie at the furthest points in the earth's magnetosphere while those closest to the Equator have apexes which reach only the lower portion of the magnetosphere.

At various altitudes above the earth's surface, e.g., in both the ionosphere and the magnetosphere, plasma is naturally present along these field lines. This plasma consists of equal numbers of positively and negatively charged particles (i.e., electrons and ions) which are guided by the field line. It is well established that a charged particle in a magnetic field gyrates about field lines, the center of gyration at any instance being called the "guiding center" of the particle. As the gyrating particle moves along a field line in a uniform field, it will follow a helical path about its guiding center, hence linear motion, and will remain on the field line. Electrons and ions both follow helical paths around a field line but rotate in opposite directions. The frequencies at which the electrons and ions rotate about the field line are called gyromagnetic frequencies or cyclotron frequencies because they are identical with the expression for the angular frequencies of gyration of particles in a cyclotron. The cyclotron frequency of ions in a given magnetic field is less than that of electrons, in inverse proportion to their masses.

If the particles which form the plasma along the earth's field lines continued to move with a constant pitch angle, often designated "alpha", they would soon impact on the earth's surface. Pitch angle alpha is defined as the angle between the direction of the earth's magnetic field and the velocity (V) of the particle. However, in converging force fields, the pitch angle does change in such a way as to allow the particle to

turn around and avoid impact. Consider a particle moving along a field line down toward the earth. It moves into a region of increasing magnetic field strength and therefore sine alpha increases. But sine alpha can only increase to 1.0, at which point, the particle turns around and starts moving up along the field line, and alpha decreases. The point at which the particle turns around is called the mirror point, and there alpha equals ninety degrees. This process is repeated at the other end of the field line where the same magnetic field strength value B, namely Bm, exists. The particle again turns around and this is called the "conjugate point" of the original mirror point. The particle is therefore trapped and bounces between the two magnetic mirrors. The particle can continue oscillating in space in this manner for long periods of time. The actual place where a particle will mirror can be calculated from the following:

$$\sin^2 \text{alpha}_o = B_o/B_m \quad (1)$$

wherein:

alpha_o = equatorial pitch angle of particle

B_o = equatorial field strength on a particular field line

B_m = field strength at the mirror point

Recent discoveries have established that there are substantial regions of naturally trapped particles in space which are commonly called "trapped radiation belts". These belts occur at altitudes greater than about 500 km and accordingly lie in the magnetosphere and mostly above the ionosphere.

The ionosphere, while it may overlap some of the trapped-particle belts, is a region in which hydrostatic forces govern its particle distribution in the gravitational field. Particle motion within the ionosphere is governed by both hydrodynamic and electrodynamic forces. While there are few trapped particles in the ionosphere, nevertheless, plasma is present along field lines in the ionosphere. The charged particles which form this plasma move between collisions with other particles along similar helical paths around the field lines and although a particular particle may diffuse downward into the earth's lower atmosphere or lose energy and diverge from its original field line due to collisions with other particles, these charged particles are normally replaced by other available charged particles or by particles that are ionized by collision with said particle. The electron density (N_e) of the plasma will vary with the actual conditions and locations involved. Also, neutral particles, ions, and electrons are present in proximity to the field lines.

The production of enhanced ionization will also alter the distribution of atomic and molecular constituents of the atmosphere, most notably through increased atomic nitrogen concentration. The upper atmosphere is normally rich in atomic oxygen (the dominant atmospheric constituent above 200 km altitude), but atomic nitrogen is normally relatively rare. This can be expected to manifest itself in increased airglow, among other effects.

As known in plasma physics, the characteristics of a plasma can be altered by adding energy to the charged particles or by ionizing or exciting additional particles to increase the density of the plasma. One way to do this is by heating the plasma which can be accomplished in different ways, e.g., ohmic, magnetic compression, shock waves, magnetic pumping, electron cyclotron resonance, and the like.

Since electron cyclotron resonance heating is involved in the present invention, a brief discussion of same is in order. Increasing the energy of electrons in a plasma by invoking electron cyclotron resonance heating, is based on a principle similar to that utilized to accelerate charged particles in a cyclotron. If a plasma is confined by a static axial magnetic field of strength B, the charged particles will gyrate about the lines of force with a frequency given, in hertz, as $f_g = 1.54 \times 10^3 B/A$, where: B = magnetic field strength in gauss, and A = mass number of the ion.

Suppose a time-varying field of this frequency is superimposed on the static field B confining the plasma, by passage of a radiofrequency current through a coil which is concentric with that producing the axial field, then in each half-cycle of their rotation about the field lines, the charged particles acquire energy from the oscillating electric field associated with the radio frequency. For example, if B is 10,000 gauss, the frequency of the field which is in resonance with protons in a plasma is 15.4 megahertz.

As applied to electrons, electron cyclotron resonance heating requires an oscillating field having a definite frequency determined by the strength of the confining field. The radio-frequency radiation produces time-varying fields (electric and magnetic), and the electric field accelerates the charged particle. The energized electrons share their energy with ions and neutrals by undergoing collisions with these particles, thereby effectively raising the temperature of the electrons, ions, and neutrals. The apportionment of energy among these species is determined by collision frequencies. For a more detailed understanding of the physics involved, see "Controlled Thermonuclear Reactions", Glasstone and Lovberg, D. Van Nostrand Company, Inc., Princeton, N.J., 1960 and "The Radiation Belt and Magnetosphere", Hess, Blaisdell Publishing Company, 1968, both of which are incorporated herein by reference.

Referring now to the drawings, the present invention provides a method and apparatus for altering at least one region of plasma which lies along a field line, particularly when it passes through the ionosphere and/or magnetosphere. FIG. **1** is a simplified illustration of the earth **10** and one of its dipole magnetic force or field lines **11**. As will be understood, line **11** may be any one of the numerous naturally existing field lines and the actual geographical locations **13** and **14** of line **11** will be chosen based on a particular operation to be carried out. The actual locations at which field lines intersect the earth's surface is documented and is readily ascertainable by those skilled in the art.

Line **11** passes through region R which lies at an altitude above the earth's surface. A wide range of altitudes are useful given the power that can be employed by the practice of this invention. The electron cyclotron resonance heating effect can be made to act on electrons anywhere above the surface of the earth. These electrons may be already present in the atmosphere, ionosphere, and/or magnetosphere of the earth, or can be artificially generated by a variety of means such as x-ray beams, charged particle beams, lasers, the plasma sheath surrounding an object such as a missile or meteor, and the like. Further, artificial particles, e.g., electrons, ions, etc., can be injected directly into region R from an earth-launched rocket or orbiting satellite carrying, for example, a payload of radioactive beta-decay material; alpha emitters; an electron accelerator; and/or ionized gases such as hydrogen; see U.S. Pat. No. 4,042,196. The altitude can be greater than about 50 km if desired,

e.g., can be from about 50 km to about 800 km, and, accordingly may lie in either the ionosphere or the magnetosphere or both. As explained above, plasma will be present along line **11** within region R and is represented by the helical line **12**. Plasma **12** is comprised of charged particles (i.e., electrons and ions) which rotate about opposing helical paths along line **11**.

Antenna **15** is positioned as close as is practical to the location **14** where line **11** intersects the earth's surface. Antenna **15** may be of any known construction for high directionality, for example, a phased array, beam spread angle (θ) type. See "The MST Radar at Poker Flat, Alaska", Radio Science, Vol. 15, No. 2, Mar.-Apr. 1980, pps. 213–223, which is incorporated herein by reference. Antenna **15** is coupled to transmitter **16** which generates a beam of high frequency electromagnetic radiation at a wide range of discrete frequencies, e.g., from about 20 to about 1800 kilohertz (kHz).

Transmitter **16** is powered by power generator means **17** which is preferably comprised of one or more large, commercial electrical generators. Some embodiments of the present invention require large amounts of power, e.g., up to 10^9 to 10^{11} watts, in continuous wave or pulsed power. Generation of the needed power is within the state of the art. Although the electrical generators necessary for the practice of the invention can be powered in any known manner, for example, by nuclear reactors, hydroelectric facilities, hydrocarbon fuels, and the like, this invention, because of its very large power requirement in certain applications, is particularly adapted for use with certain types of fuel sources which naturally occur at strategic geographical locations around the earth. For example, large reserves of hydrocarbons (oil and natural gas) exist in Alaska and Canada. In northern Alaska, particularly the North Slope region, large reserves are currently readily available. Alaska and northern Canada also are ideally located geographically as to magnetic latitudes. Alaska provides easy access to magnetic field lines that are especially suited to the practice of this invention, since many field lines which extend to desirable altitudes for this invention intersect the earth in Alaska. Thus, in Alaska, there is a unique combination of large, accessible fuel sources at desirable field line intersections. Further, a particularly desirable fuel source for the generation of very large amounts of electricity is present in Alaska in abundance, this source being natural gas. The presence of very large amounts of clean-burning natural gas in Alaskan latitudes, particularly on the North Slope, and the availability of magnetohydrodynamic (MHD), gas turbine, fuel cell, electrogasdynamic (EGD) electric generators which operate very efficiently with natural gas provide an ideal power source for the unprecedented power requirements of certain of the applications of this invention. For a more detailed discussion of the various means for generating electricity from hydrocarbon fuels, see "Electrical Aspects of Combustion", Lawton and Weinberg, Clarendon Press, 1969. For example, it is possible to generate the electricity directly at the high frequency needed to drive the antenna system. To do this, typically the velocity of flow of the combustion gases (v), past magnetic field perturbation of dimension d (in the case of MHD), follow the rule:

$$v=df$$

where f is the frequency at which electricity is generated. Thus, if $v=1.78\times10^6$ cm/sec and $d=1$ cm then electricity would be generated at a frequency of 1.78 mHz.

Put another way, in Alaska, the right type of fuel (natural gas) is naturally present in large amounts and at just the right magnetic latitudes for the most efficient practice of this invention, a truly unique combination of circumstances. Desirable magnetic latitudes for the practice of this invention interest the earth's surface both northerly and southerly of the equator, particularly desirable latitudes being those, both northerly and southerly, which correspond in magnitude with the magnetic latitudes that encompass Alaska.

Referring now to FIG. **2** a first ambodiment is illustrated where a selected region R_1 of plasma **12** is altered by electron cyclotron resonance heating to accelerate the electrons of plasma **12**, which are following helical paths along field line **11**.

To accomplish this result, electromagnetic radiation is transmitted at the outset, essentially parallel to line **11** via antenna **15** as right hand circularly polarized radiation wave **20**. Wave **20** has a frequency which will excite electron cyclotron resonance with plasma **12** at its initial or original altitude. This frequency will vary depending on the electron cyclotron resonance of region R_1 which, in turn, can be determined from available data based on the altitudes of region R_1, the particular field line **11** being used, the strength of the earth's magnetic field, etc. Frequencies of from about 20 to about 7200 kHz, preferably from about 20 to about 1800 kHz can be employed. Also, for any given application, there will be a threshhold (minimum power level) which is needed to produce the desired result. The minimum power level is a function of the level of plasma production and movement required, taking into consideration any loss processes that may be dominant in a particular plasma or propagation path.

As electron cyclotron resonance is established in plasma **12**, energy is transferred from the electromagnetic radiation **20** into plasma **12** to heat and accelerate the electrons therein and, subsequently, ions and neutral particles. As this process continues, neutral particles which are present within R_1 are ionized and absorbed into plasma **12** and this increases the electron and ion densities of plasma **12**. As the electron energy is raised to values of about 1 kilo electron volt (kev), the generated mirror force (explained below) will direct the excited plasma **12** upward along line **11** to form a plume R_2 at an altitude higher than that of R_1.

Plasma acceleration results from the force on an electron produced by a nonuniform static magnetic field ($\overline{B}$). The force, called the mirror force, is given by

$$F=-\mu\nabla B \tag{2}$$

where μ is the electron magnetic moment and $\nabla\overline{B}$ is the gradient of the magnetic field, μ being further defined as:

$$W_\perp/B=mV_\perp^2/2B$$

where $W_\perp$ is the kinetic energy in the direction perpendicular to that of the magnetic field lines and B is the magnetic field strength at the line of force on which the guiding center of the particle is located. The force as represented by equation (2) is the force which is responsible for a particle obeying equation (1).

Since the magnetic field is divergent in region R_1, it can be shown that the plasma will move upwardly from the heating region as shown in FIG. 1 and further it can be shown that

$$\tfrac{1}{2}M_eV_{e\perp}^2(x) \approx \tfrac{1}{2}M_eV_{e\perp}^2(Y) + \tfrac{1}{2}M_iV_{i\parallel}^2(Y) \quad (3)$$

where the left hand side is the initial electron transverse kinetic energy; the first term on the right is the transverse electron kinetic energy at some point (Y) in the expanded field region, while the final term is the ion kinetic energy parallel to B at point (Y). This last term is what constitutes the desired ion flow. It is produced by an electrostatic field set up by electrons which are accelerated according to Equation (2) in the divergent field region and pulls ions along with them. Equation (3) ignores electron kinetic energy parallel to B because $V_{e\parallel} \approx V_{i\parallel}$, so the bulk of parallel kinetic energy resides in the ions because of their greater masses. For example, if an electromagnetic energy flux of from about 1 to about 10 watts per square centimeter is applied to region R, whose altitude is 115 km, a plasma having a density (N_e) of 10^{12} per cubic centimeter will be generated and moved upward to region R_2 which has an altitude of about 1000 km. The movement of electrons in the plasma is due to the mirror force while the ions are moved by ambipolar diffusion (which results from the electrostatic field). This effectively "lifts" a layer of plasma **12** from the ionosphere and/or magnetosphere to a higher elevation R_2. The total energy required to create a plasma with a base area of 3 square kilometers and a height of 1000 km is about 3×10^{13} joules.

FIG. **3** is an idealized representation of movement of plasma **12** upon excitation by electron cyclotron resonance within the earth's divergent force field. Electrons (e) are accelerated to velocities required to generate the necessary mirror force to cause their upward movement. At the same time neutral particles (n) which are present along line **11** in region R_1 are ionized and become part of plasma **12**. As electrons (e) move upward along line **11**, they drag ions (i) and neutrals (n) with them but at an angle θ of about 13 degrees to field line **11**. Also, any particulates that may be present in region R_1, will be swept upwardly with the plasma. As the charged particles of plasma **12** move upward, other particles such as neutrals within or below R_1, move in to replace the upwardly moving particles. These neutrals, under some conditions, can drag with them charged particles.

For example, as a plasma moves upward, other particles at the same altitude as the plasma move horizontally into the region to replace the rising plasma and to form new plasma. The kinetic energy developed by said other particles as they move horizontally is, for example, on the same order of magnitude as the total zonal kinetic energy of stratospheric winds known to exist.

Referring again to FIG. **2**, plasma **12** in region R_1 is moved upward along field line **11**. The plasma **12** will then form a plume (cross-hatched area in FIG. **2**) which will be relatively stable for prolonged periods of time. The exact period of time will vary widely and be determined by gravitational forces and a combination of radiative and diffusive loss terms. In the previous detailed example, the calculations were based on forming a plume by producing 0^+energies of 2 ev/particle. About 10 ev per particle would be required to expand plasma **12** to apex point C (FIG. **1**). There at least some of the particles of plasma **12** will be trapped and will oscillate between mirror points along field line **11**. This oscillation will then allow additional heating of the trapped plasma **12** by stochastic heating which is associated with trapped and oscillating particles. See "A New Mechanism for Accelerating Electrons in the Outer Ionosphere" by R. A. Helliwell and T. F. Bell, Journal of Geophysical Research, Vol. 65, No. 6, June, 1960. This is preferably carried out at an altitude of at least 500 km.

The plasma of the typical example might be employed to modify or disrupt microwave transmissions of satellites. If less than total black-out of transmission is desired (e.g., scrambling by phase shifting digital signals), the density of the plasma (N_e) need only be at least about 10^6 per cubic centimeter for a plasma orginating at an altitude of from about 250 to about 400 km and accordingly less energy (i.e., electromagnetic radiation), e.g., 10^8 joules need be provided. Likewise, if the density $N_e$is on the order of 10^8, a properly positioned plume will provide a reflecting surface for VHF waves and can be used to enhance, interfere with, or otherwise modify communication transmissions. It can be seen from the foregoing that by appropriate application of various aspects of this invention at strategic locations and with adequate power sources, a means and method is provided to cause interference with or even total disruption of communications over a very large portion of the earth. This invention could be employed to disrupt not only land based communications, both civilian and military, but also airborne communications and sea communications (both surface and subsurface). This would have significant military implications, particularly as a barrier to or confusing factor for hostile missiles or airplanes. The belt or belts of enhanced ionization produced by the method and apparatus of this invention, particularly if set up over Northern Alaska and Canada, could be employed as an early warning device, as well as a communications disruption medium. Further, the simple ability to produce such a situation in a practical time period can by itself be a deterring force to hostile action. The ideal combination of suitable field lines intersecting the earth's surface at the point where substantial fuel sources are available for generation of very large quantitities of electromagnetic power, such as the North Slope of Alaska, provides the wherewithal to accomplish the foregoing in a practical time period, e.g., strategic requirements could necessitate achieving the desired altered regions in time periods of two minutes or less and this is achievable with this invention, especially when the combination of natural gas and magnetohydrodynamic, gas turbine, fuel cell and/or EGD electric generators are employed at the point where the useful field lines intersect the earth's surface. One feature of this invention which satisfies a basic requirement of a weapon system, i.e., continuous checking of operability, is that small amounts of power can be generated for operability checking purposes. Further, in the exploitation of this invention, since the main electromagnetic beam which generates the enhanced ionized belt of this invention can be modulated itself and/or one or more additional electromagnetic radiation waves can be impinged on the ionized region formed by this invention as will be described in greater detail herein after with respect to FIG. **4**, a substantial amount of randomly modulated signals of very large power magnitude can be generated in a highly nonlinear mode. This can cause confusion of or interference with or even complete disruption of guidance systems employed by

even the most sophisticated of airplanes and missiles. The ability to employ and transmit over very wide areas of the earth a plurality of electromagnetic waves of varying frequencies and to change same at will in a random manner, provides a unique ability to interfere with all modes of communications, land, sea, and/or air, at the same time. Because of the unique juxtaposition of usable fuel source at the point where desirable field lines intersect the earth's surface, such wide ranging and complete communication interference can be achieved in a resonably short period of time. Because of the mirroring phenomenon discussed hereinabove, it can also be prolonged for substantial time periods so that it would not be a mere transient effect that could simply be waited out by an opposing force. Thus, this invention provides the ability to put unprecedented amounts of power in the earth's atmosphere at strategic locations and to maintain the power injection level, particularly if random pulsing is employed, in a manner far more precise and better controlled than heretofore accomplished by the prior art, particularly by the detonation of nuclear devices of various yeilds at various altitudes. Where the prior art approaches yielded merely transitory effects, the unique combination of fuel and desirable field lines at the point where the fuel occurs allows the establishment of, compared to prior art approaches, precisely controlled and long-lasting effects which cannot, practically speaking, simply be waited out. Further, by knowing the frequencies of the various electromagnetic beams employed in the practice of this invention, it is possible not only to interfere with third party communications but to take advantage of one or more such beams to carry out a communications network even though the rest of the world's communications are disrupted. Put another way, what is used to disrupt another's communications can be employed by one knowledgeable of this invention as a communications network at the same time. In addition, once one's own communication network is established, the far-reaching extent of the effects of this invention could be employed to pick up communication signals of other for intelligence purposes. Thus, it can be seen that the disrupting effects achievable by this invention can be employed to benefit by the party who is practicing this invention since knowledge of the various electromagnetic waves being employed and how they will vary in frequency and magnitude can be used to an advantage for positive communication and eavesdropping purposes at the same time. However, this invention is not limited to locations where the fuel source naturally exists or where desirable field lines naturally intersect the earth's surface. For example, fuel, particularly hydrocarbon fuel, can be transported by pipeline and the like to the location where the invention is to be practiced.

FIG. 4 illustrates another embodiment wherein a selected region of plasma R_3 which lies within the earth's ionosphere is altered to increase the density thereof whereby a relatively stable layer **30** of relatively dense plasma is maintained within region R_3. Electromagnetic radiation is transmitted at the outset essentially parallel to field line **11** via antenna **15** as a right hand circularly polarized wave and at a frequency (e.g., 1.78 megahertz when the magnetic field at the desired altitude is 0.66 gauss) capable of exciting electron cyclotron resonance in plasma **12** at the particular altitude of plasma **12**. This causes heating of the particles (electrons, ions, neutrals, and particulates) and ionization of the uncharged particles adjacent line **11**, all of which are absorbed into plasma **12** to increase the density thereof. The power transmitted, e.g., 2×10^6 watts for up to 2 minutes heating time, is less than that required to generate the mirror force F required to move plasma **12** upward as in the previous embodiment.

While continuing to transmit electromagnetic radiation **20** from antenna **15**, a second electromagnetic radiation beam **31**, which is at a defined frequency different from the radiation from antenna **15**, is transmitted from one or more second sources via antenna **32** into layer **30** and is absorbed into a portion of layer **30** (cross-hatched area in FIG. **4**). The electromagnetic radiation wave from antenna **32** is amplitude modulated to match a known mode of oscillation f_3 in layer **30**. This creates a resonance in layer **30** which excites a new plasma wave **33** which also has a frequency of f_3 and which then propogates through the ionosphere. Wave **33** can be used to improve or disrupt communications or both depending on what is desired in a particular application. Of course, more than one new wave **33** can be generated and the various new waves can be modulated at will and in a highly nonlinear fashion.

FIG. **5** shows apparatus useful in this invention, particularly when those applications of this invention are employed which require extremely large amounts of power. In FIG. **5** there is shown the earth's surface **40** with a well **41** extending downwardly thereinto until it penetrates hydrocarbon producing reservoir **42**. Hydrocarbon reservoir **42** produces natural gas alone or in combination with crude oil. Hydrocarbons are produced from reservoir **42** through well **41** and wellhead **43** to a treating system **44** by way of pipe **45**. In treater **44**, desirable liquids such as crude oil and gas condensates are separated and recovered by way of pipe **46** while undesirable gases and liquids such as water, H_2S, and the like are separated by way of pipe **47**. Desirable gases such as carbon dioxide are separated by way of pipe **48**, and the remaining natural gas stream is removed from treater **44** by way of pipe **49** for storage in conventional tankage means (not shown) for future use and/or use in an electrical generator such as a magnetohydrodynamic, gas turbine, fuel cell or EGD generator **50**. Any desired number and combination of different types of electric generators can be employed in the practice of this invention. The natural gas is burned in generator **50** to produce substantial quantities of electricity which is then stored and/or passed by way of wire **51** to a transmitter **52** which generates the electromagnetic radiation to be used in the method of this invention. The electromagnetic radiation is then passed by way of wire **53** to antenna **54** which is located at or near the end of field line **11**. Antenna **54** sends circularly polarized radiation wave **20** upwards along field line **11** to carry out the various methods of this invention as described hereinabove.

Of course, the fuel source need not be used in its naturally-occurring state but could first be converted to another second energy source form such as hydrogen, hydrazine and the like, and electricity then generated from said second energy source form.

It can be seen from the foregoing that when desirable field line **11** intersects earth's surface **40** at or near a large naturally-occurring hydrocarbon source **42**, exceedingly large amounts of power can be very efficiently produced and transmitted in the direction of field lines. This is particularly so when the fuel source is natural gas and magnetohydrodynamic generators are employed. Further, this can all be accomplished in a

relatively small physical area when there is the unique coincidence of fuel source **42** and desirable field line **11**. Of course, only one set of equipment is shown in FIG. **5** for sake of simplicity. For a large hydrocarbon reservoir **42**, a plurality of wells **41** can be employed to feed one or more storage means and/or treaters and as large a number of generators **55** as needed to power one or more transmitters **52** and one or more antennas **54**. Since all of the apparatus **44** through **54** can be employed and used essentially at the sight where naturally-occurring fuel source **42** is located, all the necessary electromagnetic radiation **20** is generated essentially at the same location as fuel source **42**. This provides for a maximum amount of usable electromagnetic radiation **20** since there are no significant storage or transportation losses to be incurred. In other words, the apparatus is brought to the sight of the fuel source where desirable field line **11** intersects the earth's surface **40** on or near the geographical location of fuel source **42**, fuel source **42** being at a desirable magnetic latitude for the practice of this invention, for example, Alaska.

The generation of electricity by motion of a conducting fluid through a magnetic field, i.e., magnetohydrodynamics (MHD), provides a method of electric power generation without moving mechanical parts and when the conducting fluid is a plasma formed by combustion of a fuel such as natural gas, an idealized combination of apparatus is realized since the very clean-burning natural gas forms the conducting plasma in an efficient manner and the thus formed plasma, when passed through a magnetic field, generates electricity in a very efficient manner. Thus, the use of fuel source **42** to generate a plasma by combustion thereof for the generation of electricity essentially at the site of occurrence of the fuel source is unique and ideal when high power levels are required and desirable field lines **11** intersect the earth's surface **40** at or near the site of fuel source **42**. A particular advantage for MHD generators is that they can be made to generate large amounts of power with a small volume, light weight device. For example, a 1000 megawatt MHD generator can be construed using superconducting magnets to weigh roughly 42,000 pounds and can be readily air lifted.

This invention has a phenomenal variety of possible ramifications and potential future developments. As alluded to earlier, missile or aircraft destruction, deflection, or confusion could result, particularly when relativistic particles are employed. Also, large regions of the atmosphere could be lifted to an unexpectedly high altitude so that missiles encounter unexpected and unplanned drag forces with resultant destruction or deflection of same. Weather modification is possible by, for example, altering upper atmosphere wind patterns or altering solar absorption patterns by constructing one or more plumes of atmospheric particles which will act as a lens or focusing device. Also as alluded to earlier, molecular modifications of the atmosphere can take place so that positive environmental effects can be achieved. Besides actually changing the molecular composition of an atmospheric region, a particular molecule or molecules can be chosen for increased presence. For example, ozone, nitrogen, etc. concentrations in the atmosphere could be artificially increased. Similarly, environmental enhancement could be achieved by causing the breakup of various chemical entities such as carbon dioxide, carbon monoxide, nitrous oxides, and the like. Transportation of entities can also be realized when advantage is taken of the drag effects caused by regions of the atmosphere moving up along diverging field lines. Small micron sized particles can be then transported, and, under certain circumstances and with the availability of sufficient energy, larger particles or objects could be similarly affected. Particles with desired characteristics such as tackiness, reflectivity, absorptivity, etc., can be transported for specific purposes or effects. For example, a plume of tacky particles could be established to increase the drag on a missile or satellite passing therethrough. Even plumes of plasma having substantially less charged particle density than described above will produce drag effects on missiles which will affect a lightweight (dummy) missile in a manner substantially different than a heavy (live) missile and this affect can be used to distinguish between the two types of missiles. A moving plume could also serve as a means for supplying a space station or for focusing vast amount of sunlight on selected portions of the earth. Surveys of global scope could also be realized because the earth's natural magnetic field could be significantly altered in a controlled manner by plasma beta effects resulting in, for example, improved magnetotelluric surveys. Electromagnetic pulse defenses are also possible. The earth's magnetic field could be decreased or disrupted at appropriate altitudes to modify or eliminate the magnetic field in high Compton electron generation (e.g., from high altitude nuclear bursts) regions. High intensity, well controlled electrical fields can be provided in selected locations for various purposes. For example, the plasma sheath surrounding a missile or satellite could be used as a trigger for activating such a high intensity field to destroy the missile or satellite. Further, irregularities can be created in the ionosphere which will interfere with the normal operation of various types of radar, e.g., synthetic aperture radar. The present invention can also be used to create artificial belts of trapped particles which in turn can be studied to determine the stability of such parties. Still further, plumes in accordance with the present invention can be formed to simulate and/or perform the same functions as performed by the detonation of a "heave" type nuclear device without actually having to detonate such a device. Thus it can be seen that the ramifications are numerous, far-reaching, and exceedingly varied in usefulness.

I claim:

1. A method for altering at least one region normally existing above the earth's surface with electromagnetic radiation using naturally-occurring and diverging magnetic field lines of the earth comprising transmitting first electromagnetic radiation at a frequency between 20 and 7200 kHz from the earth's surface, said transmitting being conducted essentially at the outset of transmission substantially parallel to and along at least one of said field lines, adjusting the frequency of said first radiation to a value which will excite electron cyclotron resonance at an initial elevation at least 50 km above the earth's surface, whereby in the region in which said electron cyclotron resonance takes place heating, further ionization, and movement of both charged and neutral particles is effected, said cyclotron resonance excitation of said region is continued until the electron concentration of said region reaches a value of at least 10^6 per cubic centimeter and has an ion energy of at least 2 ev.

2. The method of claim **1** including the step of providing artificial particles in said at least one region which are excited by said electron cyclotron resonance.

3. The method of claim **2** wherein said artificial particles are provided by injecting same into said at least one region from an orbiting satellite.

4. The method of claim **1** wherein said threshold excitation of electron cyclotron resonance is about 1 watt per cubic centimeter and is sufficient to cause movement of a plasma region along said diverging magnetic field lines to an altitude higher than the altitude at which said excitation was initiated.

5. The method of claim **4** wherein said rising plasma region pulls with it a substantial portion of neutral particles of the atmosphere which exist in or near said plasma region.

6. The method of claim **1** wherein there is provided at least one separate source of second electromagnetic radiation, said second radiation having at least one frequency different from said first radiation, impinging said at least one second radiation on said region while said region is undergoing electron cyclotron resonance excitation caused by said first radiation.

7. The method of claim **6** wherein said second radiation has a frequency which is absorbed by said region.

8. The method of claim **6** wherein said region is plasma in the ionosphere and said second radiation excites plasma waves within said ionosphere.

9. The method of claim **8** wherein said electron concentration reaches a value of at least 10^{12} per cubic centimeter.

10. The method of claim **8** wherein said excitation of electron cyclotron resonance is initially carried out within the ionosphere and is continued for a time sufficient to allow said region to rise above said ionosphere.

11. The method of claim **1** wherein said excitation of electron cyclotron resonance is carried out above about 500 kilometers and for a time of from 0.1 to 1200 seconds such that multiple heating of said plasma region is achieved by means of stochastic heating in the magnetosphere.

12. The method of claim **1** wherein said first electromagnetic radiation is right hand circularly polarized in the northern hemisphere and left hand circularly polarized in the southern hemisphere.

13. The method of claim **1** wherein said electromagnetic radiation is generated at the site of a naturally-occurring hydrocarbon fuel source, said fuel source being located in at least one of northerly or southerly magnetic latitudes.

14. The method of claim **13** wherein said fuel source is natural gas and electricity for generating said electromagnetic radiation is obtained by burning said natural gas in at least one of magnetohydrodynamic, gas turbine, fuel cell, and EGD electric generators located at the site where said natural gas naturally occurs in the earth.

15. The method of claim **14** wherein said site of natural gas is within the magnetic latitudes that encompass Alaska.

* * * * *

US006116544A

United States Patent [19]

Forward et al.

[11] **Patent Number: 6,116,544**

[45] **Date of Patent: Sep. 12, 2000**

[54] **ELECTRODYNAMIC TETHER AND METHOD OF USE**

[75] Inventors: **Robert L. Forward**, Houston, Tex.; **Robert P. Hoyt**, Seattle, Wash.

[73] Assignee: **Tethers Unlimited, Inc.**, Seattle, Wash.

[21] Appl. No.: **08/929,271**

[22] Filed: **Sep. 12, 1997**

[51] **Int. Cl.**^{7} **B64G 1/00**

[52] **U.S. Cl.** .... **244/158 R**; 244/166; 244/172

[58] **Field of Search** .... 244/158 R, 164, 244/166, 172

[56] **References Cited**

U.S. PATENT DOCUMENTS

4,097,010	6/1978	Colombo et al.	244/158 R
4,824,051	4/1989	Engelking	244/158 R
4,923,151	5/1990	Roberts	244/158 R

OTHER PUBLICATIONS

"Tethers Open New Space Options" by Ivan Bekey, *Astronautics & Aeronautics*, 1983.

Primary Examiner—J. Woodrow Eldred
Attorney, Agent, or Firm—Arthur M. Dula

[57] **ABSTRACT**

The present invention comprises an electrodynamic tether structure and a method of use. The structure of the tether taught by the present invention is a short, wide, interconnected multiwire (compared to the long, narrow single wires of the prior art) conductive tether whose area maximizes electrodynamic drag while simultaneously minimizing the Area-Time-Product swept by the tether during its operating life. The preferred tether length is two kilometers to five kilometers. The preferred tether mass is one percent to five percent of the spacecraft mass. The method of operation comprises orienting the tether structure at an angle to the local vertical to maximize electrodynamic drag on the host spacecraft and minimize tether instability. The angle of 35.26 degrees is preferred.

26 Claims, 12 Drawing Sheets




100
80
60
40
20
0
SURVIVAL PROBABILITY %
0
0.5
1
1.5
2
2.5
3
3.5
4
Time (Years)
Hoytether
1-week survival
probability > 99%
Hoytether
Survival Probability
Single-line tether
survival probability
83%
1/e survival probability
Baseline
single-line
tether

FIG. 1a

ELECTRODYNAMIC THRUST



FIG. 1b

Reentry Time Sensitivity
Unpowered 5 km ProSEDS Tether



Enrico Lorenzini, SAO, NASA ProSEDS Mission (July 1997), NASA/MSFC Grant NAG8-1303

FIG. 1c



FIG. 2a


209
207
205
203
201
211
213

FIG. 2b


209
207
205
211
219
213
217
215
221

FIG. 2c


309
307
310
305
311
303
313
301
315

FIG. 3



Area-Time Product for Mean and Extremes of Exospheric Temperature
(m = 1000 kg, Cd = 2.0 ; 1% Tether, 1 km x 25 cm; power = 1077 watts)
(5% Tether, 1 km x 25 cm; power =5385 watts)

FIG. 4



Conventional Solid Rocket Motor System

Percent Increase in Orbital Mass vs. Altitude and I' (Isp = 288 sec)

FIG. 5


τ
τ = 35.26°

FIG. 6



FIG. 7


τ
τ

FIG.8



FIG.9



FIG. 10


1100
1008
1002
1006
1004

FIG. 11


F_{GB}
T_{GB}
$F_{GB}\sin\tau$
m_B
$L\sin\tau$
$L\cos\tau$
L
F_{GT}
T_{GT}
$F_{GT}\sin\tau$
m_T
$F_E\cos\tau$
$L/2\cos\tau$
E
τ
F_E
T_E
I
B
$E\cos\tau$
v
M

FORCES AND TORQUES ON AN UPWARD DEPLOYED CONDUCTING TETHER DUE TO THE MOTION OF THE HOST SPACECRAFT THROUGH THE MAGNETIC FIELD OF THE EARTH.

FIG. 12

ELECTRODYNAMIC TETHER AND METHOD OF USE

TECHNICAL FIELD

This invention relates generally to apparatus and methods useful for changing the state vector of a space object when the space object is moving relative to a magnetic field. More specifically, the present invention relates to an apparatus and method of using a conducting tether to produce an electrodynamic force to deorbit a satellite from its orbit around a celestial body, such as the Earth, which has an associated magnetic field.

RESERVATION OF RIGHTS

This application is subject to certain rights of the U.S. government as a result of contracts between the U.S. government and the inventors.

BACKGROUND ART

The present invention has its principal utility in outer space, primarily for deorbiting satellites at the end of their useful life to mitigate the harm and reduce the liability created by the proliferation of space debris. In order to obtain a better understanding of the present invention it is helpful to understand the prior art of space tethers, especially tether dynamics and tether electrodynamics. The present invention may be more readily understood through a review of the experimental prior art and a mathematical analysis of electrodynamic space tethers.

Prior Art Tethers:

A tether was originally a rope or chain used to fasten an animal so that it grazed only within certain limits. Tethers have been used for decades in space to attach astronauts to their spacecraft.

In 1974 Professor Guiseppe Colombo, holder of the Galileo chair of astronomy at the University of Padua in Italy, proposed using a long tether to support a satellite from an orbiting platform. U.S. Pat. No. 4,097,010, which issued to Professor Colombo and Mario Grossi on Jun. 27, 1978, teaches a satellite connected by means of a long tether to a powered spacecraft. Colombo actively pursued the design of a tethered satellite system.

Several NASA experiments, such as the two Small Expendable Deployer System (SEDS 1 & 2) experiments and the Plasma Motor Generator (PMG) experiment used tethers in space. SEDS used a nonconducting tether. The PMG used a 500-meter conducting tether. The Tethered Satellite System flights in 1992 and 1996 (TSS-1 & 1R) used a 20,000-meter conducting tether.

On the TSS-1 mission the tether deployed only 260 meters (853 feet) before the deployer failed. On the TSS-1R the tether was deployed 19,500 meters. In the SEDS-2 flight, a 0.8-mm diameter, 20,000-meter long braided single-line tether was deployed to study tether dynamics and lifetime. Orbital debris or a meteoroid severed this tether in less than four days.

In the TSS-1R flight, the conducting single-line tether was severed after five hours of deployment. This failure was caused by an electric arc produced by the 3,500 volts of electric potential generated by the conductive tether's movement through the Earth's magnetic field.

The Tether Physics and Survivability (TiPS) satellite consists of two end masses connected by a 4,000-meter long non-conducting tether. This satellite was deployed on Jun. 20, 1996 at an altitude of 1,022 kilometers (552 nautical miles). Its tether is an outer layer of Spectra™ 1000 braid over a core of acrylic yarn. The yarn will "puff" its outer braid to two millimeters to "give it a larger cross section to improve its resistance to debris and small micrometeoroids", according to the National Reconnaissance Office (NRO), which is a sponsor of the TiPS mission. As of Jun. 21, 1997 the TiPS tether had survived one year.

References:

1. Joseph A. Carroll, "SEDS Deployer Design and Flight Performance", paper WSEDSA-1 at the 4th International Conference on Tethers in Space, Washington, D.C., April 1995.
2. James E. McCoy, et. al. "Plasma Motor-Generator (PMG) Flight Experiment Results", pp.57–84, Proceedings of the 4th International conference on Tethers in Space, Washington, D.C., April 1995.
3. W. John Raitt, et. al. "The NASA.ASI-TSS-1 Mission, Summary of Results and Reflight Plans, pp. 107–118, Proceedings of the 4th International conference on Tethers in Space, Washington, D.C., April 1995.
4. Joseph C. Anselmo, "NRO Orbiting Spacecraft Studies Tether Survivability", Aviation Week, page 24, Jul. 1, 1996.

These experiments all used single line tethers.

The following reference is illustrative of the current state of the art in space tethers: Paul A. Penzo and Paul W. Ammann. Tethers in Space Handbook—Second Edition. NASA Office of Space Flight, NASA Headquarters, Washington, D.C. 20546. See also the hundreds of references in the 33 page bibliography at the end of the handbook.

The "Hoytether"™, an Improved, High-Reliability Tether:

In 1991, one of the present inventors, Robert Hoyt, invented a lightweight net-like structure that provides many redundant load-bearing paths. A number of primary load bearing lines running the length of the structure are connected periodically by diagonal secondary lines. The disclosed embodiment of this invention has the secondary lines firmly connected by knots to the primary lines. The secondary lines are connected only to the primary lines. At either end of the disclosed structure, a support ring enforces the cylindrical spacing between the primary lines. The secondary lines are designed with a small amount of slack. These secondary lines are only put under load if a primary line fails. This specific tether structure was disclosed to the public in 1992 (Forward, R. L., "Failsafe Multistrand Tether Structures for Space Propulsion", AIAA paper 92–3214, 28th Joint Propulsion Conference, Nashville, Tenn., 1992 (hereinafter "1992 Hoytether structure"). This structure was named a "Hoytether". The term "Hoytether" is used throughout the remainder of this specification for this type of tether structure.

The present invention uses an improved Hoytether, which was invented by the same inventors as the present invention. This improved Hoytether is the subject of a copending PCT application. The Hoytether is discussed briefly in this specification to aid understanding of the present invention.

The 1992 Hoytether design teaches that the normally slack secondary lines have half the cross-section (0.707 the diameter) of the primary lines. There are twice as many secondary lines as primary lines, thus the mass of the secondary lines is equal to the mass of the primary lines. In an undamaged Hoytether, the primary lines carry the entire load, while none of the secondary lines are under load.

While the survival probability of a single-line tether decreases exponentially with time, the Hoytether can maintain a high, i.e. greater than 99 percent, survival probability

for periods of months or years (forward and Hoyt, "Failsafe Multiline Hoythther Lifetimes", Paper AIAA 95–2890, 31^{st} Joint Propulsion Conference, July 1995).

References:

1. Robert L. Forward, Failsafe Multistrand Tethers for Space Propulsion, Forward Unlimited, P.O. Box 2783, Malibu, Calif. 90265, July 1992, Final Report on NASA Contract NAS8-39318 SBIR 91-1 Phase I.
2. Robert L. Forward and Robert P. Hoyt, Failsafe Multistrand Tether SEDS Technology Demonstration, Final Report on NAS8-40545 with NASA/MSFC (Jun. 14, 1995).
3. Robert L. Forward and Robert P. Hoyt, "High Strength-to-Weight Tapered Hoytether for LEO to GEO Payload Transfer" Final Report on contract number NAS8-40690 with NASA/MSFC (Jul. 10, 1996).

The Hoytether is essentially a tri-axial net structure, with 'primary' lines running along the length of the tether and two sets of 'secondary' lines connecting these primaries diagonally. They can be made by hand and connected with knots as is taught by the 1992 Hoytether structure. Because knotted connections severely limit the strength of a structure, it is desirable to use a knotless fabrication technique to achieve interconnections that have strengths approaching the limits of the constituent material. As these tethers may be many kilometers long; fast and inexpensive mechanical methods are required for their practical fabrication.

Hoytethers may be made by mechanical braiding, i.e. three-dimensional braiding, such as 3-D rotation braiding using braiding machines such as those developed by the Herzog Company in Germany (August Herzog Maschinenfabrik GmbH & Co., Postfach 2260.26012, Oldenburg, Germany. The specialized loom developed by the Nichimo Company of Japan (Nichimo Company Ltd., 2-6-2 Ohtemachi, Chiyoda-Ku, Tokyo, Japan) is used to produce "Ultracross" knotless fishing nets in which the individual strands are braided as a 4-braid line, and the strands are interbraided where they cross. This produces netting that has slipless interconnections that are very strong, approaching the maximum capability of the fiber. Such a loom could, with some modifications, produce the present invention's structure. Only two such machines exist, one in Japan, the other in Washington State. Unfortunately neither can work with the small line diameters needed to practice the preferred embodiment of the present invention. See generally, Ko, F. K., "Braiding", in *Engineered Materials Handbook, Vol.* 1., *Composites*. ASM International, Metals Park, Ohio, 1957. Pp. 519–528.

The most common 3-dimensional braiding machines are 4-step braiders based upon the designs of Maistre (German Patent P230-16986, issued 1973) and Forentine (U.S. Pat. No. 4,312,261, issued 1982). Braiding is accomplished by using pneumatics or solenoids to push the parts of the braiding machine to the proper positions. This is a slow process and making a Hoytether kilometers long with these machines would be very time consuming and expensive. The composites division of Albany International (Albany International Research Company, 777 West Street, Mansfield, Mass.) also produces a 3-D braiding machine. This machine uses modular braiding components that arc assembled breadboard fashion on a large wall.

Although braiding is the preferred technique, alternate fabrication methods such as Raschel knitting and crocheting can be used successfully. Multikilometer long Hoyththers are presently being produced for the inventors by the vendors Culzean Fabrics and Flemings Textiles using an electronically controlled crochet machine produced by Comez in Italy.

Space Tether Systems:

The prior art teaches the use of tethers in space applications. U.S. Pat. No. 5,163,641, issued on Apr. 9, 1990 to Yasaka, teaches the use of a powered spacecraft connected by a tether to a satellite. This tether is disconnected to change the state vector of the satellite. The state of the art of energy and momentum transfer using space tethers is discussed in Ivan Beckey's article "Tethering, a new Technique for Payload Deployment", Aerospace America, March 1997, at pages 36–40. Beckey concludes, "Tethers can perform the same functions as propulsive upper stages of direct payload injection, but at lower weight and cost per pound." U.S. Pat. No. 4,923,151, issued Mar. 1, 1988 to Roberts, Wilknson and Webster, teaches a tether power generator for earth orbiting satellites. U.S. Pat. No. 4,580,747, issued Mar. 15, 1983 to Pearson, teaches use of a long tether extending downward into the atmosphere from a satellite. The state vector of the satellite is changed by forces acting on a lifting body connected to the end of the tether. U.S. Pat. No. 4,824,051, issued Jan. 12, 1987 to Engelking, teaches passing an electric current through a conductive tether attached to a satellite to provide propulsive force to alter the orbit of the satellite. U.S. Pat. No. 5,082,211, issued Jan. 21, 1992 to Werka, teaches use of a tether to deorbit space debris. U.S. Pat. No. 4,727,373, issued Mar. 31, 1986 to Hoover, teaches an orbiting stereo imaging radar system having two spacecraft in synchronous parallel orbits connected by a tether.

Tether Dynamics:

In order to understand the forces that cause a tethered satellite to move upward and away from an orbiting satellite, for example, it is first necessary to explain briefly how a satellite remains in orbit. An orbiting satellite is acted on by the force of gravity which pulls it toward Earth, and by a centrifugal force, which pushes it away from Earth. The centrifugal force" (actually inertia) results from the motion of the satellite around its circular orbit. This is the same force that one can experience by swinging a ball around on the end of a string. A satellite is maintained in its orbit when it travels at the natural speed for its altitude and, as a result, the centrifugal force is equal to the gravitational force.

At the typical orbital altitude of 250 kilometers for a low-Earth orbit satellite, for example, a speed of approximately 7.6-km per second is required to create sufficient centrifugal force to balance gravitational attraction on the satellite. If the altitude is changed, the two opposing forces will no longer be in balance unless the satellite also changes its speed. A higher orbital altitude requires a slightly lower speed so the satellite will take longer to complete an orbit. Because of this, if two free-flying satellites are in orbits at different altitudes, the lower satellite will circle the Earth in less time than the satellite in the higher orbit.

If two satellites, at different altitudes, are connected to each other by a tether, they are forced to travel around their orbits together—in the same period of time, which is longer than the natural period of the lower satellite but shorter than that of the upper satellite. The lower satellite will, therefore, slow down below the natural speed for its orbit and will tend to fall to a lower orbit because the centrifugal force will now be less than the gravitational attraction of the Earth. An upward force in the tether that makes up the difference between centrifugal and gravitational forces holds it in place, however.

Correspondingly, the upper satellite will be accelerated above its natural orbiting speed (increasing its centrifugal force above the gravitational attraction) and will tend to move to a higher orbit. It, too, is held in place by an additional force (downward) in the tether. In other words,

the net force downward on the lower satellite is balanced, through the tether, by the net force upward on the upper satellite. The effect of unbalanced forces on the two satellites is, therefore, to create tension in the tether. During the TSS-1 & 1R experiments, the inertia of the tethered satellite causes the satellite to rise above the orbiter as the tether is reeled out. Very close to the orbiter, there is little difference in the two orbits, and the tension force is insufficient to overcome friction in the deployer mechanism; therefore, until the satellite reaches a separation of approximately 1000-meters, the tension is augmented by small tether-aligned thrusters on the satellite. Beyond this point, the tension in the tether is the only force required.

By experimenting with a ball hung on a piece of elastic cord (a paddleball, for example) it is possible to simulate all the different types of oscillations that are possible on a space-based tether system. The elastic cord, representing the tether, may compress and stretch, causing the ball to bounce up and down (longitudinal oscillation). It also may move in a circular (skip-rope) motion or may develop wave-like motions (transverse oscillations). Even if the string itself remains straight, it is possible to get the ball swinging back and forth about its attachment point on the paddle like a child on a swing rope (pendulous motion).

Each type of motion occurs with a particular frequency, which depends on the length and tension of the tether. When the frequencies are different, the motions do not interact; however, at some tether lengths, the frequencies of two or more types of oscillation can become very close. At this point, energy can be transferred from one typc of motion to another, a phenomenon known as resonance. For instance, the transverse oscillations in the tether may cause the satellite to swing back and forth in pendulous motion.

Many different factors may cause oscillations; the movements of the satellite or Shuttle are but two of these. For an electrodynamic tether, the skip-rope and pendulous oscillations are of particular interest. If a current is passed through a tether, the current will interact with Earth's magnetic field, resulting in a force that may produce skip-rope and pendulous oscillations. Because it is necessary to maintain control of the satellite, much study has gone into identifying the different types of possible motions and the methods used to control them.

One way to control the magnitude of those motions that cause a change in tension or transverse motion at the end of the tether is to have an end mass connected to the Hoytether that maintains a controlled tension on the tether, working much like a spring-loaded 'dog leash'. This may be as simple as a coiled spring, or as complex as an active control system that measures the tension and transverse forces on the tether and adjusts the applied tension according to a local or remotely operating algorithm.

Electrodynamic Effects of Conductive Tethers:

Electric potential is generated across a conductive tether by its motion through the Earth's magnetic field. Electromagnetic forces acting on a conductive tether in orbit can make the tether system behave like an electric motor or generator, thereby exerting a useful force to alter the state vector of the tether and any mass attached to it.

Electrodynamic tether propulsion is unlike most other types of space propulsion in use or being developed for space application today—there is no hot gas expelled to provide thrust. Instead, the environment of near-Earth space is being utilized to propel a spacecraft or upper stage via electrodynamic interactions.

A charged particle moving in a magnetic field experiences a force that is perpendicular to its direction of motion and the direction of the field. When a current flows through a long, conducting tether the electrons flowing through the tether experience this force due to the fact that they are moving along the wire in the presence of Earth's magnetic field. This force is transferred to the tether and to whatever the tether is attached (like a spacecraft, satellite, space station or upper stage). It can be an orbit-raising thrust force or orbit-lowering drag force, depending upon the direction of current flow. Operation in one mode allows boost from LEO to higher orbit while reversing the current flow provides negative thrust for deboost. The principle is much the same for an electric motor; reverse its operation and it acts as a generator. The current passing through the tether is returned through the ionosphere to complete the current loop with collection and emission occurring on opposite ends of the tether.

The PMG experiment demonstrated that a conducting tether can be used as both a motor and a generator. The TSS experiments, especially TSS-1R showed that very large voltages (about 3500 volts) can be generated by a sufficiently long tether.

Uses of an electrodynamic tether as an orbit raising and lower propulsion system has many advantages over competing systems:

a. It is nearly propellantless. Most other systems expel hot gases and require extensive resupply. To emit current, the electrodynamic tether propulsion system may use plasma contactors developed as a part of the International Space Station Program. These contactors consume less than 20 kg of xenon gas per year with a 50% duty cycle. The electrodynamic tether propulsion system can also use field emitter arrays, which emit electrons without the use of any gas.

b. It can change both altitude and inclination. The Earth's magnetic field is non-uniform and can therefore provide both in- and out-of-plane forces for inclination changes as well as altitude changes. This is of particular interest to payloads requiring polar orbits in that they can be launched on a small launch vehicle into a lower inclination orbit and have it raised in space by the proper phasing of current through the tether.

A demonstration of the propulsive capabilities of electrodynamic tethers was recently approved for a flight test in 1999. The Propulsive SEDS or ProSEDS mission, will fly as a secondary payload on a Delta II launch vehicle and deploy a 5-km conducting tether using the existing SEDS deployer concept. The ProSEDS experiment will be followed by the Electrodynamic Tether Upper Stage (EDTUS) experiment that will demonstrated the use of electrodynamic forces to change both the altitude and inclination of the experimental spacecraft. FIGS. **1B** and **1C** show the calculated electrodynamic thrust at several inclinations and the reentry time sensitivity of the ProSEDS tether, respectively.

One application for long-life conducting electrodynamic tethers is as a "Terminator Tether™" for removing from orbit unwanted Earth orbiting spacecraft at the end of their useful lives. When the mission of the satellite is completed, the Terminator Tether™, weighing a small fraction of the mass of the satellite, would be deployed. The electrodynamic interaction of the conducting tether with the Earth's magnetic field will induce current flow in the tether conductor. The resulting energy loss from the heat generated by the current flowing through the ohmic resistance in the conducting tether will remove energy from the spacecraft, eventually causing it to deorbit, thus reducing the amount of orbital space debris that must be coped with in the future.

In the following analysis, it is shown that the amount of energy loss generated by an electrodynamic tether is essen-

tially independent of its length or area, and instead is primarily proportional to the tether mass and the physical properties of the conductor metal chosen. In the typical example calculated, a 1000-kg spacecraft can be deorbited from a 1000-km high Earth orbit by a 10-kg mass tether in a month, while a 1-kg tether can deorbit a 1000-kg spacecraft in less than a year.

To the knowledge of the inventors, Joseph P. Loftus of NASA/JSC first proposed the general concept of using an electrodynamic tether to deorbit spent satellites. (Joseph P. Loftus <JLoftus@ems.jsc.nasa.gov>, personal communication via email to Robert Forward, Monday Jun. 10, 1996 15:50:10.) In order to show that the Loftus deorbit concept was not obvious to those skilled in the art of electrodynamic tethers, Forward contacted the leading expert, Joseph Carroll, of Chula Vista, Calif., who built and participated in the flight test of the PMG. After being told of the Loftus concept in a telephone conversation, his reply in an Email message dated Aug. 5, 1996, was "such a system would be feasible . . . by it is still not obvious to me that it would be useful . . . "

Loftus was considering the use of electrodynamic drag from a conducting tether to achieve this goal of bringing the unwanted spacecraft down from its high orbit (where atmospheric drag is negligible) to a 200-km orbit, where atmospheric drag would rapidly finish off the task of removing the unwanted spacecraft from orbit. The tether Loftus was considering was a single-line, conducting tether, typically 1-mm in diameter, 1-km long, and, if made of aluminum, 2-kg in mass. He would include means at the ends of the tether to contact the ambient space plasma around the Earth to complete the current loop.

Unfortunately it is probable that space impactors would sever the 1-mm diameter, 1-km long single-line tether proposed by loftus within a 1/e lifetime of four months. This would produce orbital debris rather than removing it. The motivation for this work is the NASA Safety Standard NSS 1740.14 "(Guidelines and Assessment Procedures for Limiting Orbital Debris." The relevant portion of the Standard starts on page 6-3: General Policy Objective-Postmission Disposal of Space Structures. Item 6-1: "Disposal for final mission orbits passing through LEO: A spacecraft or upper stage with perigee altitude below 2000 km in its final orbit will be disposed of by one of three methods." The method of interest is the atmospheric reentry option, Option a: "Leave the structure in an orbit in which, using conservative projections for solar activity, atmospheric drag will limit the lifetime to no longer than 25 years after completion of mission. If drag enhancement devices are to be used to reduce the orbit lifetime, it should be demonstrated that such devices will significantly reduce the area-time product of the system or will not cause the spacecraft or large debris to fragment if a collision occurs while the system is decaying from orbit."

The NASA standard applies only to NASA spacecraft and even then only to completely new spacecraft designs. New versions of existing designs are to make a "best effort" to meet the standard, but will not be required to change their design to do so. The Department of Defense has adopted the NASA standard with the same provisos. An Interagency Group report has recommended that the NASA standard be taken as a starting point for a national standard. It is NASA's recommendation to the Interagency Group that the safety requirement be phased in only as spacefaring nations reach consensus internationally, which is being done through the International Debris Coordination Working Group whose members are Russia, China, Japan, ESA, UK, India, France, Italy, and the US.

Thus, although the NASA Safety Standard in its present form is not the "Law", the existence of the standard means that some time in the future a similar requirement may be imposed on all spacecraft. This could result in major growth in future space tether business, with a sale to every non-geostationary spacecraft being "mandated" by government safety regulations, somewhat as the sale of seat belts and airbags for every car are mandated.

In fact, three of the companies planning to set up "constellations" of low to medium orbit communications: Teledesic, Iridium and Odessey have committed their companies to abide by the spirit of NASA Safety Standard 1740.14 by using one means or another to deorbit their spacecraft before they reach end of life.

Problems with Prior Art Tethers:

All electrodynamic tether designs proposed by the prior art teach that the tether should be operated at a right angle to the magnetic field through which the tether is moving. This is a problem because the electrodynamic force acting on the tether causes the tether to align itself with the magnetic field force lines. To overcome this problem the prior art teaches the use of a large ballast mass attached to the end of the tether and/or use of a very long (tens to hundreds of kilometers) tether. The large ballast mass is expensive to take to orbit because it replaces useful payload. The long tether sweeps a larger Area-Time-Product during its useful life and thus is more likely to impact other space objects, either debris or another spacecraft.

Another problem common to all proposed prior art tethers is tether instability. If the tether produces a large electrodynamic drag force, which is desirable because a large drag force will cause the satellite to deorbit quickly, then the tether will be dynamically unstable. This instability can cause the tether to lose its effectiveness, act uncontrollably and even wrap around the satellite or otherwise malfunction. Experts skilled in the art of tether design have opined that this dynamic instability is inherently unavoidable in any electrodynamic tether system. The prior art solution, such as that presently being used in the ProSEDS experiment, has been to use a large ballast mass to increase the stabilizing gravity-gradient force and/or to limit the electrodynamic drag of the tether to less that the maximum that could be produced. In the ProSEDS experiment, the conducting electrodynamic tether is five kilometers long. To insure stability, it will be augmented by a 20–35 kilometer long non-conducting tether, which to further have stability will have a 40 kilogram ballast end mass.

Yet another problem of all proposed prior art electrodynamic tether systems is how to radiate away the energy produced by the tether's operation. A satellite moving at an orbital velocity of 18,000 miles per hour has a kinetic energy of over 10,000 calories per gram. To put this amount of energy in an understandable perspective, it may be noted that when nitroglycerine explodes it produces about 1,500 calories per gram. Prior art designs of electrodynamic drag tethers teach the use of the electrical energy generated by the tether to charge batteries or operate electronics, with the excess energy being converted into heat by a resistive load. This excess heat must be radiated to the space environment or it will melt the resistive load. Thus the resistive load, and/or its associated radiator structures, must be massive and replace useful payload.

DISCLOSURE OF THE INVENTION

The present invention comprises an electrodynamic tether structure and a method of use. The principal industrial utility of the present invention is to deorbit satellites in Earth orbit

at the end of their useful life. This embodiment of the present invention is sometimes referred to in this specification as a "Terminator Tether™" because it terminates the orbital lifetime of the host spacecraft. The structure of the tether taught by the present invention is a short, wide, interconnected-multiwire (compared to the long single wires of the prior art) conductive Hoytether whose area maximizes electrodynamic drag while simultaneously minimizing the Area-Time-Product swept by the tether during its operating life. The preferred tether length is two to five kilometers. The preferred tether mass is one to five percent (1%–5%) of the spacecraft mass. The method of operation comprises orienting the tether structure at a 35.26-degree trailing angle to the local vertical to maximize electrodynamic force on the tether while avoiding tether instability and allowing use of a small tether end mass.

The present invention also teaches that the satellite-tether system may be rotated around its common center of mass to centrifugally produce tension force in the tether structure to oppose forces causing tether instability. The angle of the conductive tether structure of the present invention with respect to the velocity vector of the host spacecraft may be controlled by the method of the present invention so it interacts with the encountered magnetic field to induce a maximum current flow in the tether. This produces maximum electrodynamic drag. All or a portion of this electric power may be stored and then controllably applied to the conductive tether to produce an induced electrodynamic force. This induced electrodynamic force may by used to enhance the drag force, to rotate the tether-satellite system and/or to provide satellite propulsion, i.e. to change the state vector of the satellite for any useful purpose, e.g. to avoid collision or to change the host spacecraft's orbit to an orbit more favorable for more rapid deorbiting.

The present invention also teaches a tether structure that also functions as a thermal radiator and/or plasma contactor. An embodiment of the present invention using conducting elements of the satellite, e.g. the solar arrays, as electrodynamic tether structures is also disclosed.

BRIEF DESCRIPTION OF THE DRAWINGS

The present invention may be better understood with reference to the following drawings:

FIG. **1***a* is a graph comparing the survival probability of a single line tether as taught by the prior art to the Hoytether used by the present invention.

FIG. **1***b* is a graph showing the level of electrodynamic thrust for a 10 kilometer, 10 kilowatt tether at various altitudes and inclinations.

FIG. **1***c* is a graph showing reentry time sensitivity of a five kilometer ProSEDS tether for several conditions of current flow in the electrodynamic tether.

FIGS. **2***a*, **2***b* and **2***c* show the Hoytether structure used by the preferred embodiment of the present invention.

FIG. **2***d* shows the Hoytape structure used by the preferred embodiment of the present invention.

FIG. **3** is a block electrical diagram of an electrodynamic tether system.

FIG. **4** is a graph showing a graph of the Area-Time product for three separate levels of exospheric temperature (for neutral drag calculations) and for two separate assumptions regarding tether mass and power drawn from the ambient plasma (for the Terminator Tether™ calculations).

FIG. **5** is the percent additional mass required in orbit to drop the perigee of a circular orbit at altitude, at, to a value of 200 kilometers using standard chemical rocket as taught by the prior art for deorbiting unwanted spacecraft.

FIG. **6** is a deorbit tether system shown operating with its electrodynamic tether at a trailing 35.26-degree angle to the encountered magnetic field, as is taught by the preferred embodiment of the present invention.

FIG. **7** shows an embodiment of the present invention in which the electrodynamic tether—satellite system is rotated about its center of mass to avoid tether instability.

FIG. **8** shows an embodiment of the present invention wherein the tether is powered to provide induced electrodynamic force.

FIG. **9** shows an embodiment of the present invention wherein the solar power system structure of the satellite is used as an electrodynamic tether.

FIG. **10** shows the use of a portion of the tether structure as a thermal radiator and plasma contactor.

FIG. **11** shows the braiding of an ohmic resistive load into the tether structure.

FIG. **12** is a force diagram showing the forces and torques on an upward deployed conducting tether due to the motion of the host spacecraft through the magnetic field of the Earth.

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENT

The principal industrial utility of the present invention is the deorbiting of satellites in Earth orbit, which necessarily can happen only in outer space. Until the present invention is reduced to actual practice by use with satellites in outer space and a body of practical experience is thereby obtained, the present invention can only be constructively reduced to practice, such as by this written specification and its associated drawings, diagrams and graphs and by reference to electric measurements made on conducting tethers in space by the PMG and TSS experiments. The inventors provide herein a detailed discussion of the theory of the present invention to help those skilled in the art of aerospace and tether engineering to understand the present invention and to make and use the best embodiment of the present invention known to the inventors at the time this specification was prepared, without undue experimentation.

Although the present invention is discussed in this specification in its preferred embodiment as a means of deorbiting satellites, it must be emphasized that discussion of this specific use in no way limits the broad scope of the present invention. The present invention can be used to change the direction and speed, i.e. the state vector, of any space object providing that object is in motion relative to any magnetic field. This magnetic field may be that of the Earth or of any other celestial body, for example Jupiter or the sun.

In this specification the material forming the structure of the electrodynamic tether is specified as being a conductor. For example, a metal, such as copper or aluminum wire could be used. Likewise, nonmetallic conductor, such as carbon nanotubes, or a conductive polymer could form the conductive structure of the tether.

FIG. **1***a* shows the survival curve for a Hoytether as used by the present invention vs. the survival curve of a prior art single line tether. The survival probability curve of the Hoytether as a function of time does not conform to the well known "1/e decay" shape of a single-line tether. The Hoytether can maintain a high level of survival probability, about 99 percent, until it nears its 'lifetime'. Its survival probability then drops rapidly to zero. A detailed mathemati-

cal analysis of the difference between Hoytether and single tether survival probabilities is given in Appendix E "Small Impactor Survival Probabilities of Hoytethers" and Appendix F "Large Orbital Debris Survival Probabilities of Hoytethers", both contained in the Final Report of NASA Contract NAS8-40545. The resulting cut probability with time for the Hoytether has a "bingo curve" shapes. In a bingo game, at least five numbers must be called before anyone can win, and usually many numbers have to be called before one of the bingo cards gets five in a row. In the Hoytether at least four cuts must happen at the same level before any failure occurs, and many cuts have to be made before any one of the levels has all four lines cut. The bingo curve has the property that the probability of survival stays very high for periods short compared to the lifetime. The probability of survival is greater than 99% for periods shorter than 10% of the lifetime. This is much better performance than the 1/e curve of a single line tether, where the probability of survival is only 90% at 10% of the 1/e lifetime.

FIG. **1***b* shows the calculated level of electrodynamic thrust, in Newtons, produced by a ten kilowatt, ten kilometer single conductor tether at altitudes between 200 and 1400 kilometers and at orbital inclinations between zero degrees and eighty degrees.

FIG. **1***c* is a graph showing the reentry time sensitivity calculated for a five kilometer ProSEDS single conductor tether at altitudes between 200 and 500 kilometers with current flow in the tether between on flow and one ampere.

FIGS. **1***b* and **1***c* are the work of Enrico Lorenzini of the Smithsonian Astrophysical Observatory from his study "Performance Evaluation of the Electrodynamic Tether Tug", NASA/MSFC Grant NAG8-1303 (Nov. 12, 1966). They show that experts in the field believe that the present invention will have industrial utility, as the current flow of one ampere in FIG. **1***c* decreases the deorbit time for the calculated case from more than 180 days to less than 20 days.

FIG. **2***a* is an isometric drawing showing the generally cylindrical structure of the Hoytether. In FIG. **2***a*, primary lines **201** and **203** are shown connected via secondary lines **211**. In FIG. **2***b*, which is a schematic illustration of the structure shown in FIG. **2***a*, primary lines **201**, **203**, **205**, **207** and **209** are connected, each to their respective adjacent primary lines, by a plurality of secondary lines **221**. These connections, for example as shown at interconnection **213**, are made by knotless, slipless interconnections, such as Soutache braiding of twisted connections.

FIG. **2***c* shows the Hoytether structure of FIG. **2***b* but with a severed primary line **205** at breakpoint **215**. The second level of secondary lines **217**, shown as bold lines in FIG. **2***c*, redistribute the load from the severed primary line **215** at point **217** back to line **215** at points **219** and **221**, above and below the break, respectively.

For the electrodynamic tether, a preferred embodiment would be to unroll the tubular Hoytetherr™ into a flat Hoytape™ as shown in FIG. **2***d*.

FIG. **3** generally shows the arrangement of functional elements of an electrodynamic tether system. Of course such a system must have a means of attachment to the spacecraft, a deployer, the tether itself, some form of space plasma cathode contactor, some form of space plasma anode contactor, a power dissipation system, and a communication and control system. Each of these individual elements are known in some form to those skilled in the art of aerospace engineering. Thus the present inventors do not feel it is necessary to describe them in detail in this specification.

In FIG. **3**, a space object **301**, i.e. a satellite in Earth orbit, or any other space object either natural or man made, is physically connected to the tether system. The tether system comprises a deployer **303** from which a conductive Hoytether **305** having a bare segment **307** extends upward from space object **301**. The positively biased anode end **309** of tether **305** collects electrons from the ionosphere as space object **301** moves in direction **310** across the Earth's magnetic field. These electrons flow through the conductive structure of the Hoytether to the power system interface **311**, where it supplies power to an associated load, not shown. The electrons then flow to the negatively biased cathode **313** where electrons are ejected into the space plasma **315**, thus completing the electric circuit.

In order to allow those skilled in the art to better appreciate the broad scope of the present invention, the inventors will now provide an example using specific tether and system values to compare the Terminator Tether™ to prior art means, ie a rocket, for deorbiting a satellite.

Terminator Tethers™:

When an Earth orbiting conducting space tether moves through the magnetic field of the Earth, an electric field is generated in the tether that is proportional to the velocity of the conductor, the magnetic field strength of the Earth, and the angle between the conducting tether and the magnetic field lines. From data obtained during the various electrodynamic experiments that have been conducted in space to date, such as the PMG, TSS-1, and TSS-1R experiments, a typical value of the generated emf per unit length of tether of E=100–200 Volts/kilometer can be assumed. The electric potential V developed at the ends of a tether of length L is then V=EL. For a tether of length L=10 km, the electric potential developed is V=1000 V. For calibration, the 20-km long TSS-1R tether, at the moment of failure, was developing a potential of 3500 volts, which is 175 volts/km.

The mass of a conducting tether of length L, cross-sectional area A, and densin, d is given by m=dLA. Typical values for the density are d=2700 kg per cubic meter for aluminum and 8900-kg per cubic meter for copper. For a typical aluminum tether of mass m=10 kg and length L=10 km, the cross-sectional area will be A=0.37 mm squared. If this were a solid-wire single-line tether, the diameter of the wire would be D=0.69 mm (21.5 gauge). If this were an 18 line tubular Hoytether, the diameter of the lines in the Hoytether would be D=0.16 mm (34 gauge).

The resistance of a conducting tether of length L and cross-sectional area A is given by R=rL/A, where r is the resistivity of the conductor in nano-ohm-meters (nΩ-m). Typical values for the resistivity are r=27.4nΩ-m for aluminum and 17.0 -nΩ-m for copper. For the m=10 kg aluminum tether of length L=10 km and cross-sectional area A=0.37 mm squared at 20 degrees C, the end-to-end resistance is 750 Ω. This value of resistance is the essentially the same whether the conductor area is concentrated into a single-line tether or divided up into many lines as in a multiline Hoytether.

The current I generated in the conducting tether by the electric potential V between the ends of the tether applied across the tether resistance R is I=V/R. For the 10 kg mass aluminum tether of length L=10 km, electric potential V=EL=1000 volts, and resistance R=750 Ω the current is I=V/R=1.33 Amps. Currents near these values were measured in the TSS-1R experiment at the time of failure. At the time of failure of the TSS-1R tether, none of the plasma contactors on the Space Shuttle or the Italian Satellite were operating. Thus the current was being collected by the conductive surface area of the Space Shuttle and the Italian

Satellite at the two ends of the tether. The Space Shuttle area is quite large, so it was not the limiting factor in current collection. The diameter of the Italian Satellite was 1.6 m, which would give it an effective plasma contact area of about 8 square meters. This shows that, if the plasma contact area of the ends of a conductive space tether can be make large enough, then ampere level currents can be extracted from the ambient space plasma without the use of space plasma contactors.

The power dissipated as ohmic heating in the tether is given by P=IE. For an aluminum tether of mass m=10 kg, resistivity r=27 nΩ-m, and density d=2700 kg/cubic meter, subjected to an electric field of E=100 V/m, the power dissipated in the ohmic losses of the conductor is P=IV= 1330 Watts. For a 1 kg mass tether, it would be still a considerable 133 Watts of dissipation.

There will no doubt be additional dissipation of energy in plasma ohmic losses, plasma wave generation, and plasma ion acceleration, but the ohmic losses in the conducting tether alone are sufficient for the task of deorbiting an unwanted spacecraft massing 100 to 1000 times more than the tether.

The decay time of a metric ton spacecraft moving from a 1000 km altitude orbit to a 200 km altitude orbit with an energy difference of dU=3.3GJ, when its energy is being dissipated at a power of P=1330 W by an aluminum tether massing just 10 kg, or 1% the mass of the spacecraft, is about one month. This is a remarkably short time, and indicates that the concept of using a conductive tether to deorbit a spacecraft is indeed feasible. If the aluminum tether massed only 1 kg, or 1/1000th the mass of the spacecraft it was deorbiting, then the decay time would rise to 10 months, still a reasonable value.

In reality, of course, the actual decay time will be longer than this. If the electrodynamic drag force is very large, and becomes larger than the gravity gradient forces pulling on the ends of the tether (which force is proportional to the mass of the tether), then the tether will tend to align itself along the magnetic field lines instead of across them, and the drag force will decrease because of the small angle between the conductor length and the magnetic field lines. The tether will then settle into an angle determined by the balance between these two forces.

Is the Terminator Tether™ theoretically a better means than atmospheric drag or a rocket engine for deorbiting satellites at the end of their useful life?

In the formula for da/dt (change in altitude per change in time), using the assumptions of near-circular spiral trajectories, the Area-Time-Product (Z), the criteria by which NASA judges compliance with Safety Standard 1740.14, is given by:

$$Z = A\int dt = -\frac{m}{C_D}\int \frac{da}{\rho(a)\sqrt{\mu a}},$$

where ρ(a) is simply the density as a function of semi-major axis. Thus, for a static atmosphere, the problem of area-time product is reduced to quadrature. Note that the area-time product depends only on the density profile and the ratio of spacecraft mass to drag-coefficient and is linearly related to that ratio.

The basic altitude-dependence of the atmospheric density, represented here by ρ(a) can be expressed in a low-order power series of ln(density)=f(ln(altitude)), so that it will be possible to develop a representation of the log—log relationship between altitude and density. The three static levels of atmospheric density are modeled as 5th order polynomials in the natural log of the altitude and are representative of well known atmosphere models, for example, Jacchia, L. G., “Thermospheric Temperature, Density, and Composition: New Model,” SAO Special Report 375, March 1977. 2. Anon., Marshall Space Flight Center, “Long-Range Statistical Solar Activity Estimation,” Atmospheric Sciences Division, 1989.) The values of exospheric temperature are reasonable (about 2-sigma) high and low solar activity values of 1400 and 800 kelvins respectively. The mean value is taken to be 1100 kevins.

FIG. **4** shows a graph of the Area-Time product for three separate levels of exospheric temperature (for neutral drag calculations) and for two separate assumptions regarding tether mass and power drawn from the ambient plasma (for the Terminator Tether™ calculations). The density profiles for the three values of exospheric temperature represent the extremes and mean values to be expected during the next several decades. The exospheric temperature goes through a cycle of about an 11 year period with maximum about 1400 kelvins and minimum about 800 kelvins.

The tether calculations include an inherent assumption that the Terminator Tether™ transfers all the energy extracted from the ambient space plasma into drag that decreases the orbital energy of the spacecraft at a rate given by the power drawn by the tether. Thus, the change in energy for a spacecraft of mass m at an initial altitude h is given by the expression:

$$\Delta E = -m\left\{\frac{\mu}{2(R_e + h)} - \frac{\mu}{2(R_e + 250)}\right\},$$

and the time required to effect this change in energy of the mass, m, is just

$$\Delta t = \Delta E/P,$$

where P is the power drawn by the tether from the ambient plasma charge.

The curves for 1% and 5% tethers do not include the effects of atmospheric drag because the electrodynamic drag is orders of magnitude greater than the neutral atmospheric drag. At altitudes greater than about 700 km, the electrodynamic drag is 200 to 3000 times greater than the neutral drag forces.

It is clear, from FIG. **4** that the Terminator Tether™ concept is far superior to neutral drag in removing spacecraft from orbit, no matter how much additional area is added to the passive spacecraft to increase the atmospheric drag. The analyst should note that FIG. **4** is proportional to mass; that is, the Area-Time-Product values should be multiplied by the mass of the spacecraft and divided by 1000 kg. This is true for the neutral drag and Terminator Tether™ curves alike. The power levels assumed for the 1% and 5% tethers are only 80% of their theoretical values. This is done to provide a 20% margin on the power available from the ambient plasma and electrodynamic gradient.

Conventional rocket mechanisms can remove spacecraft from orbit, but this mechanism is apparently not viable from mass considerations when these factors are compared with the capabilities of the Terminator Tether™. A satellite owner may decide to satisfy the NASA safety requirements by adding a small solid motor and the associated hardware, software, sensors and structure to make the package independent, to be used to deorbit the spacecraft in case the main spacecraft power, attitude, or propulsion system fails.

The requirements of such a rocket motor system are more stringent than those attributed to ordinary spacecraft. The

rocket motor deorbit system must operate when some or all other systems of the spacecraft have failed. These more stringent requirements are balanced by lesser requirements of performance. The backup system must simply deorbit the spacecraft; it does not have to perform all the other duties of the spacecraft. But the backup system must know when to fire under all kinds of anomalous situations, including tumbling, offset of center of mass (because of loss of parts due to collisions), and lack of knowledge of the orbital position.

FIG. **5** shows the percent additional mass required by the rocket motor system to drop the perigee of a circular orbit at some initial perigee altitude to a value of 200 km. The atmospheric drag at this 200 km perigee altitude will remove any spacecraft (in the range considered) from orbit in a few revolutions. The contours of constant stage propellant mass fraction, λ, range from low values of 0.5 through reasonable values of 0.65 to 0.7, up to the values associated with the best solid motors ($\lambda\nabla 0.93$) without adding any extra hardware to the emergency stage. An effective, independent stage to provide a retro deltaV of from 50 to 325 m/s will almost certainly have a λ of the order of 0.6 to 0.75. If the emergency stage is required to perform its own attitude determination, the stage propellant mass fraction may be as low as 0.55 or 0.50. Note that the additional mass, shown in FIG. **5**, must also be lofted to orbit in the first place, to provide the mass on orbit for the originally intended service. The stage propellant mass fraction, λ, is a key stage performance parameter that describes the ratio of the mass of propellant to the mass of the stage. That is $\lambda=m_p/(m_p+m_I)$, where m_p is the mass of the propellant and m_I is the mass of everything else in the stage (not including the payload or any stages above or below the stage being considered). Typical independent small rocket stages have values of λ from 0.60 to 0.75. The curves of stage propellant mass fraction are shown as straight lines (a minor approximation) and are included only from 0.5 to 0.95, the extremes of reasonable design practice.

These calculations that show, beyond any reasonable doubt, that the Terminator Tether™ concept is far superior to conventional mechanisms such as drag enhancement devices or small rocket deorbit propulsion systems. The superiority is measured in terms of Area-Time-Product, NASA's measure of the likelihood of collision with other spacecraft in the path of the descending spent member of a constellation. Tether calculations were made using conservative assumptions that the power extractable from the ambient plasma and electrodynamic gradient is only 80% of the theoretical power available to a perfect tether crossing the magnetic field lines at a right angle, i.e. normally.

The following analysis is presented by the inventors to help those skilled in the art to better understand the present invention when it is used as a Terminator Tether™ for removing from orbit unwanted non-geostationary Earth-orbiting spacecraft at the end their useful lives. The primary result of that analysis is that the electrical power P in the tether that is converted into heat by the resistance of the tether and radiated away into space will remove energy from the spacecraft, causing it to rapidly deorbit, thus reducing the amount of orbital space debris that must be coped with in outer space. Tether electric power P is given by:

$$P=(vB)^2m/2rd$$

where m is the mass of the conducting tether, r and d are the resistivity and density of the conducting material, and v is the velocity of the spacecraft's motion through the Earth's magnetic field B. For a m=10 kg tether of aluminum with

resistivity of r=27.4 nΩ-m and density $d=2700\ kg/m^3$, moving at a velocity v=7037 m/s relative to the Earth's horizontal magnetic field B=26.5 μT, the power dissipated is P=2350 W! This energy loss in the form of heat must necessarily come out of the kinetic energy of the host spacecraft. For a typical example, a 1000 kg spacecraft in a 1000 km high orbit subjected to an energy loss of 2350 J/s from a 10 kg tether (1% the mass of the host spacecraft) will be deorbited in a few weeks.

Power levels of the magnitude estimated in the previous paragraph have been measured in a real orbital space experiment, the TSS-1R mission carried out on the Shuttle Orbiter in 1995. In that experiment, a large Italian spacecraft, 1.6 m in diameter, was deployed upward from the Shuttle Orbiter at the end of a conducting copper wire tether covered with electrical insulation. As the tether was slowly deployed upwards, a series of measurements were made of the open circuit voltage induced in the tether by its motion through the Earth's magnetic field. The voltage between the end of the tether and the Orbiter ground varied from zero volts at the start to 3500 V when the amount of tether deployed approached its maximum length of 20 km. Periodically, the end of the tether was connected either to one of two different electron guns, which supplied contact to the surrounding space plasma, or to the Orbiter ground. The bare surfaces of the Shuttle Orbiter proved to be a surprisingly good plasma contactor via a combination of ton collection and secondary electron emission. The current flow through the tether was deliberately limited by control circuits and the current capacity of the electron guns to about 0.5 amperes, but power levels of 1800 Watts were reached.

The tether was intended to have a fully deployed length of 20 km, but at a deployed length of 19.5 km, when about 3500 V was being induced at the end of the tether inside the Orbiter reel mechanism, a flaw in the insulation allowed an electrical spark to jump in an uncontrolled manner from the tether to the Orbiter ground. With no control circuits to keep the current level down to 0.5 amperes, the current flow jumped to 1.1 amperes, and the total power generated was P=3850 Watts Most of this energy went into the electrical arc, which burned through the tether, causing it to break and halting the experiment. This experiment showed that large areas of bare conducting material, such as that provided by the 8 square meter area of the Italian spacecraft at one end of the tether and the very large surface area of the Shuttle Orbiter spacecraft at the other end of the tether, can collect and emit amperes of current, while thousands of volts of potential can be generated by sufficiently long tethers moving at orbital speeds.

Thus, both theory and experimental data collected in the space environment indicate that significant amounts of electrodynamic drag force can be obtained from a low mass conducting tether attached to a host spacecraft, provided the ends of the conductor can exchange sufficient numbers of electrons with the surrounding space plasma.

Experimental data from the TSS-1R data also produced the amazing result that the efficiency of a bare metal surface in "contacting" the space plasma is many times better than the standard theory would predict. The 8 square meters of bare surface area of the Italian spacecraft were sufficient to collect the 1.1 A of electron current. This amount of area is easily replicated by a few hundred meters of bare wire, considering that the effective collection diameter around the wire is the Debye length, which is a few centimeters at the typical values for space plasma density and temperature.

Because of this result, that a bare wire can easily collect electrons, Les Johnson, Nobie Stone, Chris Rupp, and others

at NASA Marshall Space Flight Center have formed a team, which includes the present inventors, which is embarked on a new flight experiment. The experiment is scheduled for a piggy-back flight on a Delta II launch of an AF Global Positioning Satellite in early 2000. The goal of the experiment is to demonstrate that electrodynamic drag from a wire moving at orbital speeds through the Earth's magnetic field will create a large enough electrodynamic drag force to deorbit the Delta II second stage, whose mass is greater than 1000 kilograms, in a few weeks. This is essentially a demonstration of the Loftus electrodynamic drag deorbit concept and the first step in the development of a Terminator Tether™.

The ProSEDS (Propulsion Small Expendable-tether Deployer System) mission will use a 5 km long copper wire conductive tether massing 18 kg connected to a 20–35 km long nonconducting tether, which is in turn connected to a 25–40 kg ballast mass. The total of 25–40 km of tether length and the 25–40 kg ballast mass on the end will provide enough gravity gradient force to keep the tether aligned near the zenith, so that the direction of the current in the tether is at right angles to both the direction of the spacecraft motion in the nominal EW direction and the Earth's near-equatorial magnetic field in the nominal NS direction.

An important feature of the ProSEDS experiment is that it is designed to be completely self-powered. It uses a battery to initiate deployment and to power up the plasma contactor, but once current is flowing through the tether, some of the power is tapped off and used to recharge the battery. The battery, in turn, powers the current control electronics, the telemetry, system, and the plasma contactor. The ProSEDS mission will not be designed to allow ground control changes in operation, primarily because of the increase in complexity and cost associated with that option.

The present invention is the use of a small, low-mass deployer/controller package containing a large collecting area, short length, multiline space tether, such as a Hoytape mesh made of aluminum wire, as a "Terminator Tether™" for a constellation spacecraft. The Terminator Tether™ would be deployed when the host spacecraft is no longer working or no longer wanted. The electrodynamic drag from the Terminator Tether™ would rapidly remove the unwanted spacecraft from the constellation and a few weeks later complete the deorbit of the host spacecraft from space by burnup in the upper atmosphere of the Earth. For a Terminator Tether™ to be of maximum usefulness for constellation spacecraft, it would be desirable to minmize the mass and the length of the tether. A lower added mass means more mass for revenue producing transponders, while a shorter tether length means a lower collision cross-section Area-Time Product during deorbit.

FIG. **6** shows a spacecraft **600** having a state vector **602** that causes the spacecraft to move across magnetic field lines **601**. Spacecraft **600** has a conductive tether **603** attached to it by tether deployer and control system **605**. The outer end of tether **603** is attached to tether end mass **607**. Spacecraft **600** also has an attached electron emitter means **613**.

In FIG. **6**, spacecraft **600** has a velocity and direction defined by state vector **602**. As spacecraft **600** moves it causes conductive tether **603** to cut magnetic field lines **601**. As this happens the distal end of the conductive tether collects electrons, shown as arrows **611**, from the space plasma. Electrons **611** move through the conductive tether **603**, are passed through a resistive load, not shown, in control system **605**, and are emitted back into the space plasma as electrons **615** from electron emitter **613**. This produces an electrodynamic drag in the direction shown by arrow **609**.

As is discussed in detail in the electrodynamic drag analysis below, especially in that sections of the analysis titled "Optimization of Tether Angle", the maximum electrodynamic drag of the tether is achieved when the angle, shown as the Greek letter τ in FIG. **6**, is 35.26 degrees, trailing, to the direction of the magnetic field lines. This angle may be maintained by a feedback control circuit that maximizes the electrodynamic drag of the tether system, as is discussed in detail below. The tether structure **603** is a Hoytether having a length of about 2 to 5 kilometers. The use of the 35.26 degree angle to the magnetic field reduces the tether instability, allowing the use of a short tether which will have a small Area-Time-Product. This will minmize the possibility that the tether will impact another space object during its use.

In FIG. **7**, spacecraft **700** has a state vector **702** across magnetic field lines **704**. Conductive tether **706** is attached to spacecraft **700** by tether deployer and control system **708**. The distal end of tether **706** is attached to a tether end mass **710**. Spacecraft **700** has an electron emitter means **714**.

Functionally, electrons **712** flow from the space plasma into conductive tether **706**, are passed through a resistive load in control unit **708** and are emitted into the space plasma by electron emitter **714** as free electrons **716**. As is discussed in detail in the analysis below, this produces an electrodynamic drag on satellite **700**, which causes it to deorbit.

In FIG. **7**, spacecraft **700** is rotating with an angular velocity indicated by arrow **718**. This rotation causes a centrifugal force **720** to place tension on conductive tether **706**. This force **720** places tension on the tether **706** in a direction that counters tether instability. The Tether **706** may be at any angle to the magnetic field while the rotation of the tether-satellite system is producing this useful tension. FIG. **7** shows the angle to be 35.26 degrees, which is optimum, but any angle will work.

FIGS. **8***a* and **8***b* show a powered Terminator Tether™. In FIG. **8***a* the spacecraft **800** has a state vector **802** that causes it and its associated conductive tether **806** to move across magnetic field **804**. Tether **806** has an end mass **808** that is proximate a plasma contactor **810**. Just as was discussed in the embodiment of the present invention shown in FIG. **6** and FIG. **7**, an electric current moves through the circuit formed by the space plasma, the plasma contactor **810**, the conductive tether **806**, and the electron emitter **815**, thence back into the space plasma as electrons **816**. This creates an electrodynamic drag on the tether in the direction shown by arrow **818**.

In FIG. **8***b*, similar numbers indicate similar structures. In FIG. **8***b*, however, an electric power source, not shown, in spacecraft **800** provides electrons to conductive tether **806**. The electrons are emitted from the end **812** of the tether **806**. Electrons are collected to from the space plasma **814** by contactor **815**, thus completing the electric circuit. The result is an electrodynamic force on tether **806**, and therefore on spacecraft **800**, in the direction show by arrow **820**.

Spacecraft **800** in FIG. **8***b* may be rotated as is taught in the embodiment of the invention shown in FIG. **7**, above, to allow the control system to time the application of electric current to the tether **806** to cause force **820** to be exert force in any desired direction along the circle made by the rotating tether. This allows the state vector of the spacecraft to be modified to raise or lower the spacecraft's orbital altitude, or to otherwise usefully change its orbital elements.

FIG. **9** show an embodiment of the present invention wherein the conductive structure of a satellite is used as the tether. In FIG. **9**, a spacecraft **900** which has a state vector

901 and is moving across magnetic field **903**, has two attached solar panels, **902** and **904**. Solar panels **902** and **904** have conductive aluminum frames **908** and **906**, respectively. Frame **906** is electrically and mechanically connected to plasma contactor **912**. Frame **908** is electrically and mechanically connected to electron emitter **910**. As spacecraft **900** moves across magnetic field **903**, electrons from the space plasma **914** flow through contactor **912** and frame **906** to the body of spacecraft **900**, where the current flows through a resistive load, not shown, and then into frame **908** and electron emitter **910** to the space plasma **916**, thus completing the circuit. This creates an electrodynamic drag on spacecraft **900**. If the power output from solar panels **902** and **904** was directed to flow into the frames, **906** and **908**, then the electrodynamic interaction with the space plasma would cause a useful force to be impressed on spacecraft **900**, as was discussed in connection with FIG. **8** above. The spacecraft may be rotated and/or oriented to a desired angle with the magnetic field lines, as was also discussed above.

FIG. **10** shows an embodiment of the present invention wherein the plasma contactor and the resistive load are structurally part of the conductive tether. In FIG. **10** spacecraft **1000** has a state vector **1001** that causes it to pass through magnetic field **1003**. Spacecraft **1000** has a tether control and deployment system **1005** that is connected to a conductive tether **1007** having an end mass **1013**. A contactor portion **1015** of the conductive tether **1007** near end mass **1013** is adapted to contact the space plasma so as to receive or emit electrons. This may be the bare wire strands of a wide Hoytether, or it may be any other plasma contactor means that can be conveniently made electrically part of the Hoytether structure, such as points or metal fuzz. A second resistive portion **1009** of tether structure **1007** is adapted to be a resistive load. This may be done by making a portion of the tether structure from a material, such as nichrome steel wire, that has suitable electrical resistance The large surface area of the Hoytether provides an excellent radiator structure into the three degree Kelvin radiation sink of outer space.

FIG. **11** shows an alternative embodiment of the load resistance/radiator structure of the present invention. In FIG. **11**, a biline Hoytether **1002** is attached to its control and deployer system **1100** on a spacecraft, not shown, and to a tether end mass **1004**. A resistive load, **1006** is woven into the Hoytether structure, whereby this load **1006** and the section of the Hoytether **1002** into which it is woven act together as a thermal radiator allowing photons **1008** to radiate into the thermal sink of outer space.

The following detailed analysis of the present invention will help those skilled in the art to better understand and use the present invention.

Electrodynamic Drag Analysis:

The following is an optimization analysis of the electrodynamic drag produced by a conducting tether deployed from a host spacecraft that it is to deorbit. The force and torque diagram used in the analysis is shown in FIG. **12**, which shows the forces and torques on an upward deployed conducting tether due to the motion of the host spacecraft through the magnetic field of the Earth.

Physical Constants and Assumptions:

The analysis that follows will use the following physical constants and assumptions:

Newton's gravitational constant $G=6.67\times10^{-11}$ $m^3/kg\text{-}s^2$.

Mass of Earth $M_e=5.976\times10^{24}$ kg.

Radius of Earth near equator $R_e=6378$ km.

Assumed host spacecraft altitude h=622 km.

Assumed host spacecraft orbital radius a=7000 km.

Host spacecraft orbital velocity $w=\omega a=[GM_e/a\ ]^{1/2}=7546$ m/s.

Vertical gravity gradient at spacecraft $2\Gamma=2GM_e/a^3=2.32\times10^{-6}\ s^{-2}$.

Centrifugal gradient at spacecraft $\omega^2=GM_e/a^3=1.16\times10^{-6}\ s^{-2}$.

Combined gradient at spacecraft $3\Gamma=3GM_e/a^3=3\omega^2=3.49\times10^{-6}\ s^{-2}$.

Magnetic field of Earth (tilted dipole approximation):

Magnitude $B_o=35\ \mu T=0.35$ gauss.

Angle between magnetic pole and spin pole 11.5°.

Field components at spacecraft with altitude a and angle β between radius vector of spacecraft and magnetic equatorial plane.

Horizontal $B_H=B_o(R_e/a)^3\cos\beta=26.5\ \mu T\cos\beta$.

Vertical $B_V=2B_o(R_e/a)^3\sin\beta=52.9\ \mu T\sin\beta$.

Electrodynamic Tether Constants and Assumptions:

The electrodynamic tether is assumed to be made of a conducting metal, and have a length L, density d, resistivity r, and cross-sectional area A that is constant along the length of the tether. If the tether is a single round wire of diameter D, then the cross-sectional area is $A=\pi D^2/4$. Because of the micrometeorite and space debris hazard, however, it is likely the tether will be made up of redundantly interconnected multiple lines whose individual cross-sectional areas add up to A. Given these assumptions, the tether mass is then $m_T=dLA$, while the end-to-end tether resistance is $R_T=rL/A=rdL^2/m_T$.

Specific Conductivity Parameter:

The choice of the metal conductor to be used in a space tether is determined by a combination of low resistivity (high conductivity) and low density, with cost, strength, and melting point as secondary considerations for certain applications. Copper has a resistivity r=17.0 nΩ-m, a density d=8933 kg/m, and a "specific conductivity" of 1/rd=6,585 $m^2/\Omega\text{-}kg$. Aluminum has a resistivity r=27.4 nΩ-m, which is significantly greater than that of copper, but it has a much lower density of $d=2700\ kg/m^3$. As a result, aluminum's "specific conductivity" of $1/rd=13{,}500\ m^2/\Omega\text{-}kg$ is twice the conductivity per unit mass of copper. Silver, because of its higher density and higher cost, is not competitive as an electrodynamic space tether even though its resistivity of 16.1 nΩ-m is slightly better than that of copper. An alternate candidate material would be beryllium, with a resistivity r=32.5 nΩ-m, density $d=1850\ kg/m^3$, and a "specific conductivity" of $1/rd=16{,}630\ m^2/\Omega\text{-}kg$, slightly better than that of the much cheaper aluminum. Beryllium also has a higher melting point at 1551 K than aluminum at 933 K, so some of its alloys may be a preferred material for some electrodynamic applications despite its higher materials cost. Unfortunately, despite decades of metallurgical research by the nuclear power industry, highly ductile alloys of beryllium have not been found, so it is difficult to pull beryllium into wire. As a result, because of its high specific conductivity, low cost, and ready availability in ductile wire form, it will be assumed for this analysis that the electrodynamic tether will be made of aluminum wire.

Typical Resistance Values:

To be economically competitive, the mass of the tether needs to be a small fraction of the mass of the host spacecraft it is required to deorbit. Since a typical constellation spacecraft has a mass of about 1000 kg, a typical Terminator Tether™ with a mass that is 2% of the host spacecraft mass would consist of a deployer/controller package with a mass $m_D=10$ kg, containing an aluminum tether with a mass $m_T=10$ kg with a volume of $LA=m_T/d=3.70\times10^{-3}\ m^3$. If this 10 kg of aluminum were formed into a tether with a length

of L=2 km and a cross-sectional area of A=1.85 mm^2, then the end-to-end resistance of the tether would be $R=rL/A=rdL^2/m_T=29.6\ \Omega$ A longer tether would have a proportionately smaller cross-sectional area and a higher resistance; for example, a 5 km long tether with the same mass would have a resistance of 185 Ω.

Orbit Inclination Assumption:

In order to make the remainder of the analysis mathematically tractable, it will be assumed that the orbit of the host spacecraft is circular and above the magnetic equator, so that the angle between the radius vector to the spacecraft and the magnetic equatorial plane is β=0 degrees. In this orbit, the velocity v of the spacecraft with respect to the magnetic field is the orbital velocity w less the rotational velocity of the magnetic field at the orbital radius a due to the once per day rotation of the Earth, or:

$$v=W-2\pi a/1\mathrm{day}=(7546-509)\mathrm{m/s}=7037\mathrm{m/s}$$

This equation also shows why electrodynamic drag will not be useful for removing geostationary spacecraft from orbit. At the geostationary orbital radius of a=42,200 km, the relative velocity of the spacecraft and the rotating magnetic field of the Earth is zero.

With this assumption of an orbit above the magnetic equator, the vertical component of the Earth's magnetic field is zero and the horizontal component of the Earth's magnetic field is at right angles to both the local vertical and the direction of motion of the spacecraft. The total magnetic field seen by the host spacecraft and its Terminator Tether™ is then orthogonally horizontal and has the magnitude:

$$B=B_H=B_o[R_e/a]^3 \cos\beta=26.5\mu T.$$

Where for simplicity the subscript H will be dropped for the remainder of this analysis.

This orbit, with its inclination of 11.5° with respect to the spin equator, will not stay in the plane of the magnetic equator, but will vary ±11.5° above and below it as the Earth rotates, causing a variation in magnetic field strength of ±0.5 μT, as well as a slight variation in angle. This 2% variation is negligible in terms of the other uncertainties in this analysis. It is not until the orbital inclination of the host spacecraft orbit reaches 60°, where cos 60°=0.5, that there is a significant drop in the expected magnitude of the electrodynamic drag forces calculated in this analysis.

Electromagnetic Drag Effects in Polar Orbit:

In many medium Earth orbit communication satellite constellations, there are a significant number of spacecraft at high inclinations and in nearly polar orbits. The high inclination spacecraft, with inclinations between 60° and 78.5°, will all have orbits that stay between the magnetic poles. Although the amount of electrodynamic drag will be significantly less than that experienced by spacecraft with orbits at lower inclinations, the direction of the induced electric fields in the tether will always be in the proper direction. If the tether is vertically upward, the outer tip of the tether will be positively charged and the bare wire in the tether will pull electrons out of the surrounding space plasma, while the electron emitter at the host spacecraft end will eject the electrons back into the space plasma to complete the circuit.

For spacecraft in near polar orbits with inclinations between 78.5° and 90°, however, there will be much more drastic variations. First of all, for a spacecraft in a 90° orbit that happens to pass directly over the magnetic poles, there is no horizontal component of the magnetic field when it is passing over one of the magnetic poles, so no voltage is generated in the tether during that part of the orbit, while the horizontal component of the magnetic field near the magnetic equator, while strong in magnitude, is along the spacecraft velocity vector, so no voltage is generated in the tether in that part of the orbit either. As a result, there will be negligible electrodynamic drag experienced by the host spacecraft during that particular orbit. The Earth is rotating, however, and the magnetic pole is rotating with it. A few orbits later, the host spacecraft will be passing over the Earth's spin pole at a point where the horizontal component of the magnetic field is exactly at right angles to the direction of motion of the spacecraft, so the full voltage is generated in the tether. When passing over the spin pole, the spacecraft radius vector is at an angle of 11.5° from the magnetic pole and at an angle β=78.5° away from the magnetic equatorial plane. With these assumptions, the magnitude of the horizontal component of the magnetic field at the Earth's spin pole is a respectable:

$$B=B_o[R_e/a]^3 \cos 78.5°=5.28\mu T$$

or 20% of the maximum value experiences by spacecraft orbiting above the magnetic equator. This value will drop slightly as the orbit continues, then build back up as the spacecraft passes over the opposite pole. As the Earth continues to rotate, bringing the magnetic pole again under the orbit, and the interaction of the tether with the horizontal component of the magnetic field again drops to zero. The average coupling of a tether to the Earth's magnetic field over all polar trajectories has been calculated to be 12.3 percent.

A problem experienced only by spacecraft with orbit inclinations greater than 78.5°:

The spacecraft will no longer be traveling from west to east with respect to the magnetic field axis, but will have a retrograde motion as it moves through the magnetic field. As a result, the voltage generated by the motion of the tether through the Earth's magnetic field will switch direction. The outer tip will be negatively charged and will attempt to collect ions, which is a much less efficient process than collecting electrons.

There are a number of solutions to this problem. The first is to increase the mass and length of the tether supplied to a spacecraft assigned to a polar orbit, so that higher voltages, currents, and drag are generated during the limited times the spacecraft is passing over the poles in the right direction. The second is to supply a tether with plasma contactors at both ends that can emit electrons from either end, allowing the current to flow either way, depending upon which direction the spacecraft is passing around the magnetic pole. The third is to utilize the first number of passes to torque the orbit of the spacecraft until the orbit inclination has been shifted below 60°, then turn on the electrodynamic drag full time to deorbit the spacecraft from this more favorable orbit inclination. This orbit torqueing maneuver is accomplished by activating the electrodynamic drag mechanism only when the magnetic field orientation is such that a strong out-of-plane component of force is created. This orbit torqueing maneuver can be augmented by switching to a propulsion mode, where power saved in the batteries during the drag force mode is pumped back into the tether when the magnetic field is in the opposite direction, applying electrodynamic propulsion to torque the orbit even further. With the tether at a large and stable trailing orientation, the coupling to the magnetic field can be significant to a vertical tether.

In summary, spacecraft in near-polar orbits might take longer to bring down, and might have to utilize specially designed Terminator Tethers™ that might cost and mass

more than the simpler Terminator Tethers™ usable in lower inclination orbits, but a Terminator Tether™ can still remove a spacecraft from a polar orbit when desired.

The inventors now present a detailed analysis and optimization of a typical Terminator Tether™ attached to a typical host spacecraft in a typical low inclination orbit.

Electromotive Generation of Voltage and Current in the Tether:

When an object is moved at a velocity v through a magnetic field B, an electric field is generated in the frame of reference of the moving object given by:

$$E = v \times B = vB$$

where the magnetic field B of the Earth, being mostly tangent to the Earth's surface in the north-south direction, is at right angles to the velocity vector v of the spacecraft, assumed to be orbiting in a generally west-east direction. The direction of the electric field E will be at right angles to both v and B, or along the local vertical. It should be noted that this electric field exists in the moving frame of reference because a moving magnetic field creates an electric field. No object actually has to be there, but if it is, then the relative motion of the magnetic field of the Earth will not only apply magnetic forces to whatever material the object is made out of, but electric forces too.

Note also that the velocity used in this equation is the relative velocity between the object and the magnetic field. Because the Earth's magnetic field rotates with the Earth, the motion of the magnetic field must be subtracted from the orbital velocity of the object to obtain the relative velocity.

Voltage generation in a Conducting Tether:

If the moving object is a long conducting wire of length L, the electric field E, generated in the wire produces a voltage V between the opposite ends of the wire given by:

$$V = E \bullet L = EL \cos \tau = vBL \cos \tau$$

where τ is the angle between the length vector L of the tether and the electric field vector E, assumed to be in the vertical direction at right angles to the velocity vector v in the plane of FIG. **12** and the magnetic field vector B out of the plane of FIG. **12**. A typical value for the voltage level built up in a vertically oriented tether with length L=5 km and $\tau=0$, moving at a velocity of v=7037 m/s through the Earth's horizontal magnetic field of strength 26.5 μT, is 932 V, or 0.186 V/m. Spacecraft in higher inclination orbits would experience somewhat smaller electric fields. For calibration, the voltage measured between the ends of the 19.5 km long TSS-1R tether was 3500 V, or 0.175 V/m.

Contacting the Space Plasma:

Although a voltage will build up between the ends of the conducting tether, no current will flow unless the circuit is completed. The circuit cannot be completed with another wire, for it too will have a similar voltage generated in it by the moving magnetic field. Fortunately, empty space is not empty, and in near-Earth regions not too distant from the Earth's atmosphere there exists highly electrically conductive space plasma, kept partially ionized by radiation from the Sun. The electron and ion density varies from the dark to light side, with altitude, with season, with sunspot cycle, with contamination level, etc. but it typically varies from 10^{11} to 10^{13} electrons/cc.

Fortunately, it has been found that if a bare conductive surface such as the spherical Italian spacecraft in the TSS-1R experiment, or the long bare wire to be used in the ProSEDS experiment, or a multiline conducting wire Hoytape mesh, is charged to a few hundred volts, the bare conductor will readily pull electrons out of the space plasma. So all that is needed to complete a connection to the space plasma at the positively charged (upper) end of the tether is a sufficient large area of uninsulated conductor.

It is more difficult to eject electrons from a wire or to collect positive ions from the space plasma. Although it is conceivable that a very large area at the other end of the tether could collect enough ions to complete the circuit as was demonstrated during the TSS-1R mission when the Shuttle orbiter was found to be an adequate plasma contactor for over an amp of current, the present method chosen is to use an electron emitter of some sort, either a hot cathode, a plasma cathode or contactor, a field-emission device, or something similar. Once provisions have been made at both ends of the tether to allow the flow of electrons out of one end of the tether and into the other end, and the altitude of the host spacecraft is not too high, then there will be sufficient conductivity in the space plasma surrounding the host spacecraft to allow current to flow through the tether.

Current Flow In The Tether:

The amount of current I flowing through the tether depends upon the total resistance R in the circuit. This resistance will consist of three components, the effective resistance of the plasma, the resistance of the tether, calculated earlier as $R_T = rL/A = rdL^2/m_T$, and a control resistor R_C, which will be varied as needed to optimize the Terminator Tether™ performance. There will also need to be a parasitic load on the current in the form of a charging device to charge some batteries. The batteries in turn will be used to power the control and communication circuits, and drive the electron emitting devices at the negative end of the tether. A well-designed Terminator Tether™ will thus be completely self-powered, except for an initial charge in the batteries to provide electrical power for the deployment and startup procedure. For simplicity of analysis it will be assumed that this battery charging load, which absorbs power like a resistor, but which stores it and uses it later instead of dissipating it immediately as heat, is included in the control resistor R_c. Normally, this load would act as a "base resistance" below which the control resistor could not be lowered, but since the charging circuit can be turned off when desired, and operations continued without interruption using the power stored in the batteries, it will be assumed that the control resistor can be taken to near zero value in those circumstances where the space plasma conductivity is low, or the magnetic field is in the wrong orientation and the voltage being generated in the tether is not large. Under these circumstances, lowering the control resistor to near zero allows a much higher current to flow for a given generated voltage, thus increasing the power being dissipated in the tether and maintaining a high level of electrodynamic drag on the host spacecraft.

A properly designed Terminator Tether™ will have plenty of bare metal area for electron collection at the positive end, while the electron emitters at the other end are efficient in terms of emitting large electron currents at low voltages and therefore low powers, while at the same time the mass, length, and area of the conducting tether have been made such that the resistance of the tether is moderately high. Under these conditions, the effective resistance of the space plasma will be much less than the design resistance of the tether. To make the mathematics more tractable it will be assumed that the plasma resistance is can be neglected and that the voltage available to drive the tether is the full voltage generated by the moving magnetic field. Although voltage will be needed to power the electron emitter, what-

ever its form, it will be assumed that the required voltage and power will be supplied by the batteries. The batteries in turn will be powered by the battery charging circuit, whose effective resistance is included in the control resistor (except for those short periods when the plasma or magnetic field interactions are weak).

Given all these assumptions concerning the total resistance in the circuit, the current I flowing through the tether is then given by:

$$I=V/R=vBL\cos\tau/(R_C+rdL^2/m_T)$$

A typical current level can be estimated by assuming that the control resistance R_C should be about the same size as the tether resistance R_T, which for an aluminum tether with resistivity r=27.4 nΩ-m, density d=2700 kg/m^3, length L=5 km, and mass m_T=10 kg, is R_T=185 Ω, giving a total resistance, including the control resistance R_C, of R=370 Ω. Thus the current flowing though a tether of length L=5 km, generating a voltage of V=932 V, would be I=V/R=2.52 A.

Power Dissipation Analysis:

The induced current I flowing through the tether resistance R_T will generate heat in the wire, which will be radiated into space and lost. That radiated energy must come from somewhere. There is also power taken out of the current flow by the battery charging circuit and ultimately dissipated. In order to conform to energy conservation laws, this power and energy must come from a decrease in the total kinetic and potential energy of the host spacecraft, causing it to deorbit. Set forth below is a detailed, optimized force analysis which will calculate the drag force on the host spacecraft. In this section, by using some simplifying assumptions, it is possible to produce a general argument based on energy conservation laws, which will illustrate the broad scope of the present invention.

For this energy conservation analysis it will be assumed that the plasma resistance is small compared with the tether resistance, and that the control resistance is equal to the tether resistance:

$$R_C=R_T=rL/A=rdL^2/m_T$$

Assume that the ballast mass at the end of the tether is a large piece of the defunct host spacecraft, such as a solar panel, antenna, or battery pack, so that the gradient force is large and the tether is always oriented along the vertical so that the angle τ=0°. Also assume the spacecraft is in an orbit above the magnetic equator and thus is moving at right angles to the Earth's magnetic field, so that the angle between the orbital velocity vector and the magnetic field vector is 90°, and the electric field vector is in the vertical direction, aligned perfectly with the tether length vector. Under these ideal conditions, the voltage between the ends of the tether is given by:

$$V=E\bullet L=(v\times B)\bullet L=vBL$$

The current in the tether is then just:

$$I=V/(R_C+R_T)=vBm_T/2rdL$$

The power dissipated as ohmic heating in the tether is then given by:

$$P=IV=(vB)^2m_T/2rd$$

This equation shows the interesting result that the power dissipated does not depend upon the length or the area of the tether (within reason), but only the mass of the tether m_T, the resistivity r and density d of the tether material, and the velocity v of the conducting tether through the Earth's magnetic field B.

For a typical aluminum tether of mass m_T=10 kg, the power dissipated is an impressive P=2350 W. Even if only a small fraction of this power is dissipated in a real system, the kinetic energy of the host spacecraft would suffer a significant energy loss with time.

Orbital Energy Extraction Analysis:

The total energy U of a spacecraft of mass M in orbit around the Earth consists of two components, its positive orbital kinetic energy and its negative gravitational potential energy. If a circular orbit of altitude h and radius a=R_e+h is assumed, then the total energy of the spacecraft moving at a velocity w=$(GM_e/a)^{1/2}$ is:

$$U=+Mw^2/2-GMM_e/a=-GMM_e/2a$$

The system will be dissipating energy in the tether to decrease the energy U of the unwanted spacecraft from its relatively low negative value in a high Earth orbit to a greater negative value in a lower Earth orbit. To give a specific example, an unwanted spacecraft with a mass of M=1000 kg (a metric ton) in an orbit with an altitude of h=1000 km and a high orbital radius of a(H)=R_e+h=7371 km, then its (negative) total energy is:

$$U(H)=-GMM_e/2a(H)=-27.1\text{ GJ or }-27.1\text{ MJ/kg}$$

It is desired to lower the spacecraft to an orbit with an altitude just outside the atmosphere of h=200 km or a lower orbital radius of a(L)=R_e+h=6571 km, where atmospheric drag will finish the job. The total (negative) energy of a metric ton spacecraft at 200 km altitude is:

$$U(L)=-GMM_e/2a(L)=-30.4\text{ GJ}$$

Thus, the amount of energy needed to be dissipated in order to move the 1000 kg spacecraft from a 1000 km orbit with a total energy U(H)=−27.1 GJ down to a 200 km orbit with energy U(L)=−30.4 CJ is:

$$dU=U(H)-U(L)=3.3\text{ GJ.}$$

The decay time T of a metric ton spacecraft moving from a 1000 km altitude orbit to a 200 km altitude orbit with an energy difference of dU=3.3 GJ, when its energy is being dissipated at a power of P=2350 W by a typical aluminum tether massing just 10 kg or 1% the mass of the spacecraft, is found to be T=dU/P=16 days.

The actual decay time will be longer than this. If the electrodynamic drag force is very large, and becomes larger than the gravity gradient forces pulling on the ends of the tether, then the tether will tend to align itself along the magnetic field lines instead of across them, and the drag force will decrease because of the small angle between the conductor length and the magnetic field lines. The tether current will need to be controlled until the angle of the tether settles into an angle determined by the balance between these two forces. These electrodynamic torque vs. gradient torque dynamic interaction effects are discussed in the next section.

Force and Torque Balance Analysis:

It is now possible to calculate the forces and torques on the tether. It is also possible to use the fact that the electrodynamic and gravity forces and torques on the tether must balance each other out to calculate and teach some optimum values for some of the Terminator Tether™ parameters.

Electrodynamic Force and Torque:

As discussed above, both theory and experiment show that: provided the conducting tether is moved rapidly through the Earth's magnetic field in order to generate a voltage across it, and provided good contact is made with the space plasma, the conducting tether will have a current flowing through it. When a wire (moving or not) carrying a current I is embedded in a magnetic field B, there will be an electrodynatnic force F_E generated on each element of the wire. The electrodynamic force will be at right angles to the magnetic field vector and the length vector of the wire element, with a magnitude given by:

$$F_E=J\times B=ILB$$

where B is the horizontal component of the magnetic field, which is perpendicular to the assumed magnetic equator orbit plane, while the tether length vector L is assumed to lie in the orbit plane. If, as will be the case most of the time, the electron current is leaving the space plasma and entering the tether along the length of the tether, then IL needs to be replaced with an integral of the current along the length of the tether.

Note that the electrodynamic force amplitude or direction is not directly dependent on the motion of the tether through the Earth's magnetic field. The electrodynamic force would be the same if the tether were not moving and the current was being supplied by a battery. Since the current I is a function of the orbital velocity, however, there is a secondary dependence of the electrodynamic force magnitude on the orbital velocity, but not its direction. The electrodynamic force is always at right angles to the conductor, and stays at right angles to the conductor as the angle τ varies, as shown in FIG. **12**.

Assuming that the electrodynamic drag force is applied uniformly along the length of the tether, it is possible to make the simplifying assumption that the integrated force is effectively applied at right angles to the center of mass of the tether at the point L/2 as shown in FIG. **12**. The electrodynamic torque on the tether is then:

$$T_E=F_E L/2=IBL^2/2=vB^2L^3 \cos \tau/2(R_C+rdL^2/m_T)=vB^2L^3 \cos \tau/2R$$

Gravity Gradient Forces and Torques:

When a tether and its ballast end mass are deployed from a host spacecraft, the gravity gradient force field of the Earth, combined with the orbital centrifugal gradient force field, will cause the tether to deploy either up or down from the host spacecraft. The direction desired depends on which end of the tether is connected to the electron emitter. Normally, the electron emitter will be on the end attached to the host spacecraft, in which case the desired direction of deployment will be upward so that the induced voltage in the tether will produce an excess of electrons at the electron emitter end of the tether. The desired upward direction is chosen by having the deployer eject the ballast mass in the upward direction. Once the ballast mass has been started in that direction, the centrifugal force due to the orbital motion of the ballast mass will cause the ballast mass to continue to accelerate in the upward direction until it is brought to a halt by the full deployment of the tether.

If there were no electrodynamic or atmospheric drag, the equilibrium direction of the tether would be exactly along the vertical, since the combined gradient field is a maximum in that direction. Because a significant amount of electromagnetic drag is expected, the actual angle of the tether with respect to the local vertical will be at some angle τ, lagging behind the spacecraft motion in the plane of the orbit, as shown in FIG. **12**. In the following analysis shows that there is an optimum angle for τ that produces the largest electrodynamic drag force on the host spacecraft without producing tether instability.

The combined vertical gravity gradient and centrifugal gradient field 3Γ acting on the ballast mass m_B at the end of the tether of length L will produce a gradient force F_{GB} given by:

$$F_{GB}=-3_{\Gamma}m_B L \cos \tau$$

The strength of the force depends not only on the ballast mass m_B and the strength of the gradient field 3Γ, but also the component along the radial direction of the distance of the ballast mass from the center of mass, which is L cos τ. This force acts in the vertical direction along the radius vector leading from the ballast mass away from the center of the Earth. The amount of gradient force is not large. For a ballast mass of m_B=10 kg and a tether length of L=5 km, the gradient force is about 0.175 N.

As can be seen in FIG. **12**, the component of this gradient force that is at right angles to the tether, given by F_{GB} sin τ, will produce a torque T_{GB} on the tether that tends to restore the tether toward the vertical, lessening the angle τ.

$$T_{GB}=LF_{GB} \sin \tau=-3_{\Gamma}m_B L^2 \sin \tau \cos \tau$$

The tether mass m_T also contributes to the gradient force and torque. If it is assumed that the tether has a uniform cross section, then it is possible to replace the distributed mass of the tether with an equivalent point mass m_T placed at the center of mass of the tether, which is the point L/2 along the tether, and a distance L/2 cos τ in the radial direction. The gradient force due to the tether mass is then:

$$F_{GT}=-3/2_{\Gamma}m_T L \cos \tau$$

While the gradient torque is:

$$T_{GT}=-L/2F_{GT} \sin \tau=-3/4_{\Gamma}m_B L^2 \sin \tau \cos \tau$$

The total gradient torque attempting to restore the tether to its vertical orientation is then:

$$T_G=T_{GB}+T_{GT}=3_{\Gamma}(m_B+m_T/4)L^2 \sin \tau \cos \tau$$

It is important to notice the variation of the total gravity gradient torque as the tether angle τ is varied. Since the gradient force is always in the radial or vertical direction, there is no torque on the tether when the tether is vertical, as is the case when there are no aerodynamic or electromagnetic drag forces. Once the drag forces become important and start to apply torque to the tether, increasing the tether angle τ, those drag torques causing an increase in tether angle τ will be opposed by a rising gradient torque which will attempt to decrease the tether angle. For small tether angles, the gradient torque increases first linearly with τ, then as sin τ, since cos τ is near unity for small τ, then at τ=45° the gradient torque reaches its maximum, where sin τ=cos τ=0.707 and sin τ cos τ=0.50. When this angle is reached, the tether is a point of catastrophic instability, for if there is a further increase in the electrodynamic drag force, causing the angle τ to become greater than 45°, the gradient torque, instead of growing stronger to counteract the increased drag torque, will become weaker and the tether angle will go rapidly to 90°.

To restore control to the tether angle if the instability occurs, it will be necessary to turn off the electrodynamic drag forces by shutting off the current flow through the tether. The τ=90° position for the tether and ballast mass is

a gravitationally unstable orientation. After a time, slight fluctuations in the gravity field will allow the gradient force to slowly take over and restore the tether to the vertical orientation, which, unless it can be controlled in some way, is equally likely to be up or down. It would therefore be desirable to maintain control of the tether angle so as to avoid the tether angle getting into the region of instability.

Torque Balance on the Tether:

The angle τ of the tether is determined by a balance between the electrodynamic torque T_E attempting to increase the angle τ and the gradient torque T_G attempting to decrease the angle τ. Balance is achieved when the two torques are equal:

$$T_E=T_G=T_{GB}+T_{GT}$$

or:

$$vB^2L^3 \cos \tau/2R=3_{\Gamma}(m_B+m_T/4)L^2 \sin \tau \cos \tau$$

Simplifing and rearranging yields an equation giving us the angle τ at which torque balance occurs:

$$\tau=\arcsin[vB^2L/6_{\Gamma}(m_B+m_T/4)R]$$

The physical interpretation of this equation is that the maximum electrodynamic force that can be sustained on the tether is limited by the gradient force on the tether. It is possible to increase the electrodynamic force by decreasing the total resistance R of the tether (for example, by using a tether with a larger mass and a lower tether resistance), but if the tether resistance is too low, then the quantity in brackets becomes greater than unity and this equation has no solution, indicating that the tether has reached an angle where instability sets in.

To maintain control of the tether angle, it will be necessary to vary the control resistance of the tether to compensate for variations in magnetic field strength and direction, plasma density (which affects the plasma resistance), and other factors, and thereby maintain the tether at an intermediate angle where both the electrodynamic and gradient forces are at an appreciable level and balance each other.

Optimization of Tether Angle:

At first glance, it might seem that the optimum angle for the tether would be 45°, since at that angle the gradient torque is largest and therefore can counteract a larger electrodynamic drag force. However, since the 45° angle is the point where instability sets in, it is desirable to set the tether angle at some value below 45°. The optimum angle is that which maximizes the horizontal or drag component of the electrodynamic force. This optimum angle τ is derived from the equation for the horizontal component of the electrodynamic force, or the electrodynamic drag force, since it opposes the host spacecraft motion:

$$F_{ED}=F_E \cos \tau=6[m_B+m_T/4]\Gamma L \sin \tau \cos^2\tau$$

By setting the partial derivative$\square F_{ED}/\square\tau=0$ and solving, it is possible to calculate that the optimum angle for the tether that gives the maximum electrodynamic drag force F_{ED}, while still keeping the tether torques balanced and under control, is $\tau=\arctan(0.707)=35.26°$. With this angle selected and maintained by varying the control resistor R_C to compensate for variations in plasma contact resistance and variatins in the strength and direction of the Earth's magnetic field B seen at the spacecraft, the tether experience the maximum stable value for the electromagnetic drag force of:

$$F_{ED}(\max,\tau=35.26^{\circ})=2.31[m_B+m_T/4]\Gamma L$$

There are many ways to provide the sensing information needed to provide the feedback signals to the control resistor, but the simplest is to merely measure the drag acceleration on the host spacecraft with a set of accelerometers, and maximiize the force in the direction opposite to the host spacecraft motion. Another method would be to measure the current in the tether, and knowing the tether resistance and the amount of control resistance, calculate the power being extracted and maximize that value. Alternate methods would be to use an optical position sensor or GPS receivers at both ends of the tether to measure the angle of the tether or the position of the ballast mass with respect to the host spacecraft.

To make an estimate of the magnitude of drag force attainable, assume that a typical aluminum tether with a length of L=5 km, a tether mass of m_T=10 kg and a ballast mass of m_B=10 kg is being used. Then the maximum gradient force limited electrodynamic drag force is F_{ED}= 0.167 N. The power being dissipated in the canoical tether at the angle τ, with $R_C=R_T=rdL^2/m_T=185\ \Omega$ is given by:

$$P=IR=[vBL \cos \tau]^2(R_C+rdL^2m_T)$$

which for an angle τ=35.26° results in a power dissipation of 1570 W. Thus, the thrust level per unit power obtained by the typical Terminator Tether™ would be about 0.106 N/kW. This number is comparable to the value of 0.148 N/kW estimated for the much heavier and longer TSS-1R tether.

Reconciliation of Energy and Force Analysis:

By a force and torque balance analysis an optimum angle for the tether has been discovered at which it is possible to obtain a maximum in the drag component of the electrodynamic force. There is also an additional component of the electrodynamic force, the component in the vertical direction, $F_{EV=FE}$ sin(τ), which is downward for an upwardly deployed tether. This component of force combines with the gravity force of the Earth to effectively allow the host spacecraft to orbit a little faster than normal for that orbital altitude. It does not contribute to the deorbiting of the host spacecraft. But since this vertical component of force is created by current running through the tether, and that current is creating heat and dissipating energy as it passes through the tether, there might be some concern that the force and torque balance analysis above does not conform to the law of conservation of energy.

The inventors will now show, in a very general manner, that no matter what the tether angle, the electrical power being dissipated in the tether is exactly equal to the power being lost by the slowing of the host spacecraft.

The "deorbit power" P_D that must be removed from a spacecraft moving at a velocity v when that motion is opposed by a drag force F_{ED} is:

$$P_D=v\bullet F_{ED}=vF_E \cos \tau=vILB \cos \tau=I[vBL \cos \tau]$$

But, since the voltage V induced across the tether of length L and tilt angle τ moving at a velocity v through a horizontal magnetic field B is

$$V=E\bullet L=EL \cos \tau=vBL \cos \tau$$

Therefore:

$$P_D=IV=P_E$$

And the deorbit power P_D extracted from the slowing of the spacecraft by the drag component of the electrodynamic

force is always exactly equal to the electrical power P_E being dissipated as heat in the tether circuits, independent of the tether angle.

Optimization of Tether Mass Distribution:

If it is not possible to use a piece of the host spacecraft as ballast mass, then the mass of the ballast must be included in the Terminator Tether™ mass. It would be desirable to minimize the total Terminator Tether™ mass, since every kilogram saved means that another kilogram's worth of revenue-producing transponders can be added to the working payload of the host spacecraft. Given a total mass for the Terminator Tether™ and the mass of the deployer/controller unit, it is possible to optimize the mass distribution between the ballast mass and the tether mass to obtain a minimum total Terminator Tether™ mass. A well-designed Terminator Tether™ will also have most, if not all, of the deployer mass incorporated into the ballast mass.

Assume that the total Terminator Tether™ mass consists of the deployer/controller mass m_D, the tether mass m_T, and the ballast mass m_B, with $m_B > m_T > m_D$. Of the three mass components in the Terminator Tether™, two of them affect the electrodynamic drag performance. If it is assumed that the ballast mass is a factor X larger than the tether mass, or $m_B = Xm_T$, the maxinum drag force that can be obtained is now:

$$F_{ED}(\max)=2.31m_T(X+0.25)\Gamma L$$

If it is assumed that the control resistor has been adjusted so that this maximum value for the electrodynamic drag force is maintained as the motion of the spacecraft along its orbit moves the spacecraft into regions with different magnetic field strengths and plasma densities, then for the angle $\tau=35.26°$, $\cos(35.26°)=0.817$, and the maximum electrodynamic drag force in terms of the electrodynamic parameters will be:

$$0.817vB^2L^2/(R_C+rdL^2/m_T)=F_{ED}(\max)=2.31m_T(X+0.25)\Gamma L$$

or canceling out terms and rearranging:

$$(X+0.25)=0.353vB^2L/\Gamma m_T(R_C+rdL^2/m_T)$$

It is now possible to make the further simplifying assumption that to maintain control of the tether, the control resistor needs to be roughly the same size as the tether resistance or $R_C \approx rdL^2/m_T$. Using this assumption produces an equation for the optimum value for the ratio X of the ballast mass to the tether mass:

$$\begin{aligned} X = vB^2/\Gamma rdL - 0.25 &= -0.25 + \frac{vB^2}{12\sin\gamma\cos\gamma\Gamma rdL} \\ &= -0.25\frac{\Lambda}{L} \end{aligned}$$

Where Λ is the "effective electrodynamic length".

If the tether is short, so that L is small, this equation indicates that the ballast mass must be increased to increase the gradient force, since it is the gradient force which determines the upper limit to the amount of electrodynamic drag force that can be generated without losing control of the tether.

Assuming the usual values for the Earth's magnetic and gradient fields, the velocity of the host spacecraft through the magnetic field, and the resistivity and density of aluminum, this equation becomes:

$$X=10.9/L-0.25$$

where L is in kilometers.

For a typical tether of length L=5 km, X=1.93. If the total mass for the Terminator Tether™ is 20 kg, or 2% of the host spacecraft mass, and the mass of the deployer is 10 kg, then the remaining 10 kg should be distributed so that 6.59 kg is in the ballast mass while 3.41 kg is in tether mass.

Optimization of Tether Length:

If the ballast mass consists of a piece of the host spacecraft, then the mass of the ballast does not have to be considered in the optimization of the Tether system. In this case, the optimum distribution of the Tether mass is to put as much mass as possible into the tether, with a minimum in the deployer/controller package. Under this assumption, the optimum length of the tether is determined by the desire to keep the Area-Time Product of the host spacecraft plus Tether to a minimum.

In a long tether of length L, the effective "collision" cross-sectional area is not the area of the tether, but the larger area produced by multiplying the length of the tether by sum of the width of the tether plus the width of the "target" spacecraft that would be damaged by the tether hitting it. Thus, to decrease the "area" portion of the Area-Time Product, it would be desirable to shorten the tether, making it thicker, and perhaps slightly wider, at the same time, thus keeping the same tether mass and electron collection area, and thereby maintaining the drag force and keeping the decay time at the same level. The result will be a shortening of the Area-Time Product.

If the tether is shortened too much, however, the smaller voltage generated across the shorter tether will leave less voltage margin for the operation of the plasma contactors and the battery recharge system. Since the maximum voltage that can be generated is about 200 V/km, and typical plasma contactors and battery, chargers take 25–100 V to operate, a minimum length for a Tether would be roughly 2 km. Host spacecraft operating in polar orbits, where the conditions for voltage generation are not as good, may require a tether length of 5 km or more.

Since many watts of heat power will be dissipated in the control resistor, means must usually be provided to radiate the heat away into space. One low-mass method of accomplishing this is to make the control resistor (or resistors) in the form of a long, electrically insulated, high resistivity wire similar to those used in electric blankets, but designed to operate at a higher temperature, and during the fabrication of the electrodynamic tether, incorporate the high resistivity wire (or wires) into the end of the tether closest to the control circuit by weaving or braiding the insulated high resistivity wire in with the uninsulated aluminum wire of the electrodynamic tether. The surface area of a long wire is very large, so in this extended wire configuration, exposed to the space all around it, the hot control resistor wire can self-radiate its power into cold space without incurring the mass penalty of a separate radiating surface.

Implementation:

The basic optimum structure for a Terminator Tether™ would be one of the many types of Hoytethers. A multiline (6–12 primary line) Hoytape™ will provide the largest contact area with the plasma, since both sides of the tape would be able to pass current to the plasma. If the spacing between the primary lines is chosen to be larger than twice the Debye length of the plasma, then the effective current collection area per unit length of the Hoytape is proportional to the width of the Hoytape mesh, not the diameter of the wires in the mesh. Thus, a Hoytape not only provides an assured longer life for the Terminator Tether™, but very short lengths will also provide a very large current collection areas.

The deployer for the tether can deploy the Terminator Tether™ either down or up or both. The deployer can stay

attached to the spacecraft as was done in the SEDS missions, or perhaps a better alternative would have the deployer ejected from the spacecraft, with one end of the tether still attached to the spacecraft, reeling out tether as it leaves. The empty deployer would then act as a ballast mass at the end of the Terminator Tether™, which would improve the performance.

The "Remora Remover"

In addition to attaching Terminator Tethers to spacecraft before launch, it is possible to consider a missile-like application. This "Remora Remover" missile would use a Terminator Tether™ carried by a seeker missile similar to the small "hit-to-kill" missiles developed by the Space Defense Initiative Office that deployed a net loaded with oriented metal rods. The Remora Remover missile would hunt down a spacecraft that needs to be removed from space, but instead of hitting the spacecraft, the missile would be programmed to rendezvous with the spacecraft and attach itself to the host spacecraft using a hooked net, harpoon, or adhesive "sucker". The Remora Remover missile would then deploy the Terminator Tether™, which would bring down both the spacecraft and the missile.

The inventors have presented two analyses, backed up with data obtained from space flight experiments. One analysis was based on generalized energy conservation laws while the other analysis use force and torque balance arguments. Both analyses show that optimized aluminum wire tethers 2 to 5 km in length and massing just 1% to 5% of the mass of the host spacecraft can deorbit the host spacecraft in the order of a few weeks, thus mitigating the long-lived orbital debris hazard created by a constellation spacecraft after their end-of-life.

Power Augmented Operation of the Tether:

It is well known in the aerospace literature that if a spacecraft has a power supply and a conducting tether hanging from it, and the spacecraft is in an orbit or trajectory that takes it near a body, such as the Earth or Jupiter, which has both a magnetic field and a region of moderate density electron-ion plasma, and electrical current is pumped from the power supply through the tether and back through the plasma, that the current flowing through the tether will interact with the magnetic field of the body, producing forces on the tether and thence on the spacecraft, changing its orbit or trajectory. These forces can be used to increase or decrease the spacecraft altitude and/or inclination. The amount of altitude or inclination change is proportional to the ratio of the power available from the power supply divided by the mass of the spacecraft and varies with altitude. The unpowered Terminator Tether™ is a simple example of such a system, in which only altitude decrease is possible, although small amounts of both inclination increase or decrease are possible at the same time. Some typical references to this prior art are: Les Johnson, "Propulsive Small Expendable Deployer System Mission (ProSEDS)", Proceedings of the OAST 8th Advanced Propulsion Workshop, JPL, Pasadena, Calif., 20–22 May 1997; and Les Johnson, Joe Carroll, Robert D. Estes, Enrico Lorenzini, Brian Gilchrist, Manuel Martinez-Sanchez, Juan Sanmartin, and Irwin Vas, "Electrodynamic Tethers for Reboost of the International Space Station and Spacecraft Propulsion, AIAA Paper 1996.

Since the Terminator Tether™ of the invention is normally associated with a satellite that has a power supply in the form of a solar panel combined with a storage battery, the Terminator Tether™ can be operated in the "powered propulsion" mode if desired. Such a mode would be useful when attempting to avoid a collision between the Terminator Tether™ and another spacecraft. In such cases, the power from the solar panel, augmented by the power stored in the battery, can be used to temporarily operate the Terminator Tether™ in the propulsion mode instead of the normal drag mode. This would enable to Terminator Tether™ to raise its altitude and/or increase or decrease its inclination to avoid a collision.

In addition, the Terminator Tether™ could be operated in the "power-augmented drag" mode. In this mode, there will be a current induced in the tether by the motion of the spacecraft through the magnetic field, which will cause a drag force on the spacecraft. This induced current would then be augmented by additional current in the same direction generated by the solar panel and the storage batteries in the power supply. The increased current will cause an increased drag force. If there is a significant vertical component of the magnetic field there will also be an increased force normal to the orbital plane, which will cause an increased rate of change of inclination.

When the Terminator Tether™ is operated in the "powered propulsion" or "power-augmented drag" mode, the conditions for stable optimum operation will be essentially the same as in the "unpowered drag" mode. The reason the conditions stay the same is that the maximum tether force than can be effectively utilized is limited by the strength of the gradient force, which has not changed, since the length and mass of the tether and the ballast mass has not changed for these different modes of operation. As a result the optimum operational angle for the tether is still 35.26 degrees, and the optimum ratio of ballast mass to tether mass for different tether lengths and tether material is still determined by the analysis of the invention as is set forth above.

In the analysis given above, where the optimum tether angle was found, the tether was assumed to be in the plane of the orbit and lagging behind the spacecraft motion, since in the "unpowered drag" mode, that would be its normal position, although if the component of the magnetic field along the orbit were high, there would be some tilt of the tether out of the plane of the orbit, producing a force tending to change the inclination of the orbit. In either of the "powered" modes of operation of the Terminator Tether™, however, the tilt of the tether could be forward toward the motion of the spacecraft or strongly tilted to one side or the other of the orbital plane. In all these cases, if the electrodynamic force is allowed to become too large, and the tether angle exceeds 45 degrees, the restoring force of the gradient field will drop off and the tether angle will go unstable. As a result, the optimum angle for the tether that will give the maximum stable force, whether it is a maximum drag force, and maximum propulsion force, or a maximum inclination change force, will be 35.26 degrees, and the optimum ratio for the mass of the tether versus the mass of the ballast will be the same as for the unpowered drag case.

The analysis that gave the optimum angle as 35.26 degrees assumed that the tether would be oriented like a rigid rotor. In reality, variations in forces along the tether will probably cause the tether to hang in a slightly curved shape, where the optimum angle may not be exactly 35.26 degrees from the local vertical. The optimum angle of the tether as it leaves the host spacecraft in such a case is where the drag force is largest.

The present invention is discussed in this disclosure in terms of its space applications as a Terminator Tether™ useful for the removal of unwanted satellites. It should be understood, however, that the present invention is useful in any application where a space object can use a conductive tether to produce electrodynamic force through interaction

with a magnetic field. The invention, therefore, should be limited not by this description, but only by the appended claims and their equivalents.

What is claimed is:

1. A method of operating a conductive tether attached to a space object, said conductive tether being oriented at an angle to magnetic field lines of an external magnetic field and said conductive tether moving across the magnetic field lines of said external magnetic field at said angle to producing an electric current in said conducting tether and a resulting electrodynamic force acting on said tether and said attached space object comprising,

Controlling the amount of electric current flowing in said conducting tether to vary the angle between the conductive tether the field lines of the external magnetic field and the electrodynamic force acting on said tether and attached space object.

2. A method as in claim **1** wherein said angle is less than 45 degrees.

3. A method as in claim **1** wherein said angle is 35.26 degrees.

4. A method as in claim **1** wherein said angle is controlled to average 35.26 degrees over time.

5. A method as in claim **1** wherein said angle is controlled to average 35.26 degrees over the length of the tether.

6. A method as in claim **1** wherein the space object and the tether connected to it are rotated about their center of mass while the conductive tether interacts with the external magnetic field.

7. A method as in claim **1** wherein the angle of the conductive tether to the external magnetic field is controlled by sensing a measurable parameter of the space object/conductive tether system.

8. A method as in claim **7** wherein the parameter is current flow in the conductive tether.

9. A method as in claim **7** wherein the parameter is the electrical power dissipated in the conductive tether and the current control system.

10. A method as in claim **7** wherein the parameter is the relative position of the space object and the position of the far end tip of the tether.

11. A method as in claim **7** wherein the parameter is the acceleration of the space object.

12. A method as in claim **6** wherein the parameter is the state vector of the space object as measured by the Global Positioning System.

13. A method as in claim **1** including the step of applying electric power to the conductive tether to change the state vector of the space object.

14. A method of operating a conductive tether attached to a space object, said conductive tether being oriented at an angle to the local vertical between said space object and a celestial body having a magnetic field having magnetic field lines external to said conductive tether; said conductive tether moving across said magnetic field lines of said external magnetic field at an angle to the local vertical to produce an electric current in said conducting tether and a resulting electrodynamic force acting on said tether and said attached space object comprising,

Controlling the amount of electric current flowing in said conducting tether to vary the angle between the conductive tether the local vertical between said space object and said celestial body to vary the electrodynamic force acting on said tether and attached space object.

15. A method as in claim **14** wherein said angle is less than 45 degrees.

16. A method as in claim **14** wherein said angle is controlled to average 35.26 degrees over time.

17. A method as in claim **14** wherein the space object and the tether connected to it are rotated about their center of mass while the conductive tether interacts with the external magnetic field.

18. A method as in claim **14** wherein the angle of the conductive tether to the external magnetic field is controlled by sensing a measurable parameter of the space object/conductive tether system.

19. A method as in claim **18** wherein the parameter is current flow in the conductive tether.

20. A method as in claim **18** wherein the parameter is the acceleration of the space object caused by the electrodynamic force acting on the space object.

21. A method as in claim **18** wherein the parameter is the change in the state vector of the space object as measured by the Global Positioning System.

22. A method as in claim **14** including the step of applying electric power to the conductive tether to change the state vector of the space object.

23. A method as in claim **14** wherein the celestial body is the Earth and the magnetic field is the Earth's magnetic field.

24. A method as in claim **14** wherein the celestial body is the sun and the magnetic field is the Sun's magnetic field.

25. A method as in claim **14** wherein the magnetic field is the vector sum of the magnetic fields from all celestial bodies in the solar system.

26. A method as in claim **14** wherein the conductive tether is a Hoytether.

* * * * *

US007643312B2

(12) United States Patent
Vanderelli et al.

(10) **Patent No.: US 7,643,312 B2**

(45) **Date of Patent: *Jan. 5, 2010**

(54) **METHOD AND APPARATUS FOR A WIRELESS POWER SUPPLY**

(75) Inventors: **Timm A. Vanderelli**, Ligonier, PA (US); **John G. Shearer**, Ligonier, PA (US); **John R. Shearer**, Pittsburgh, PA (US)

(73) Assignee: **Powercast Corporation**, Ligonier, PA (US)

(*) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 0 days.

This patent is subject to a terminal disclaimer.

(21) Appl. No.: **11/357,578**

(22) Filed: **Feb. 17, 2006**

(65) **Prior Publication Data**

US 2006/0164866 A1 Jul. 27, 2006

Related U.S. Application Data

(63) Continuation of application No. 10/966,880, filed on Oct. 15, 2004, now Pat. No. 7,027,311.

(60) Provisional application No. 60/511,860, filed on Oct. 17, 2003.

(51) **Int. Cl.**
H02M 5/00 (2006.01)

(52) **U.S. Cl.** **363/8**

(58) **Field of Classification Search** 363/8, 363/59, 60, 157, 184, 165; 455/270, 272, 455/273, 275, 276.1, 277.1; 307/151
See application file for complete search history.

(56) **References Cited**

U.S. PATENT DOCUMENTS

4,471,344	A		9/1984	Williams	
4,685,047	A	*	8/1987	Phillips, Sr.	363/126
4,700,179	A		10/1987	Fancher	
4,703,190	A	*	10/1987	Tamura et al.	307/2
4,857,893	A		8/1989	Carroll	
5,296,866	A		3/1994	Sutton	
5,612,652	A	*	3/1997	Crosby	333/24 R
5,731,762	A		3/1998	Gila et al.	
5,737,177	A	*	4/1998	Mett et al.	361/234
5,889,383	A		3/1999	Teich	
5,898,911	A	*	4/1999	White	455/232.1

(Continued)

FOREIGN PATENT DOCUMENTS

EP	0 168 947 A1	1/1986

(Continued)

OTHER PUBLICATIONS

Soohoo, "Magnetic Thin Film Inductors for Integrated Circuit Applications," IEEE Transactions in Magnetic, vol. MAG-15, No. 6, pp. 1803-1805 (Nov. 1979).

(Continued)

Primary Examiner—Matthew V Nguyen

(57) **ABSTRACT**

An apparatus for a wireless power supply including a mechanism for receiving a range of RF radiation across a collection of frequencies. The apparatus includes a mechanism for converting the RF radiation across the collection of frequencies, preferably at a same time into DC. A method for a wireless power supply including the steps of receiving a range of RF radiation across a collection of frequencies. There is the step of converting the RF radiation across the collection of frequencies, preferably at a same time into DC.

20 Claims, 2 Drawing Sheets



U.S. PATENT DOCUMENTS

5,952,814	A		9/1999	Van Lerberghe	
6,054,925	A		4/2000	Proctor et al.	
6,094,161	A	*	7/2000	Cassen et al.	342/175
6,100,804	A		8/2000	Brady et al.	
6,127,799	A		10/2000	Krishnan	
6,130,603	A		10/2000	Briechle	
6,177,872	B1		1/2001	Kodukula et al.	
6,184,651	B1		2/2001	Fernandez et al.	
6,184,789	B1		2/2001	Richley et al.	
6,284,651	B1		9/2001	Sharan et al.	
6,289,237	B1		9/2001	Mickle et al.	
6,480,699	B1		11/2002	Lovoi	
6,549,064	B2		4/2003	Bandy et al.	
6,633,750	B1	*	10/2003	Dacus et al.	455/126
6,841,981	B2	*	1/2005	Smith et al.	323/312
6,999,327	B2	*	2/2006	Smith et al.	363/60
7,027,311	B2	*	4/2006	Vanderelli et al.	363/8
7,274,921	B2	*	9/2007	Smith et al.	455/313

FOREIGN PATENT DOCUMENTS

JP	3034862	3/1997
JP	10-257697	9/1998
JP	10-295043	11/1998
JP	2000-278887	10/2000

OTHER PUBLICATIONS

Saleh and Qureshi, “Permalloy ThinFilm Inductors,” Electronic Letters, vol. 6, No, 26, pp. 850-852 (Dec. 31, 1970).

Reinhold Rydenberg, “The Receipt of Electric Waves in the Wireless Telegraphy,” Annalen de Physik IV, 25, 1908, p. 466.

PCT/US2004/034194 International Preliminary Report on Patentability dated Apr. 18, 2006.

PCT/US2004/034194 International Search Report dated Jun. 17, 2005.

* cited by examiner


12
ANT.
24
22
D1 THRU Dx
RECTIFY
26
28
+
DC OUTPUT
-
18
INDUCTOR (L)
RESONATE
STORE
CS1 THRU CSx
T1 THRU Tx
20
INTEGRATE
C1 THRU Cx
14
10
26
16
GND.

FIG.1


MEDIUM WAVE EXAMPLE
OPTIMIZED FOR MEDIUM WAVE BROADBAND
RF ENERGY RETRIEVAL, COLLECTION & STORAGE
SCHEMATIC DIAGRAM & PARTS VALUES.
12
ANT.
24
22
26
1N34A x 6
+
DC OUTPUT
-
2200 uF
14
28 uH x 7
28
26
.068 uF x 8
18
20
16
26
10
GND.

FIG. 2


12
RECEIVING MEANS
CONVERTING MEANS
14

FIG. 3

METHOD AND APPARATUS FOR A WIRELESS POWER SUPPLY

This application is a continuation application of application Ser. No. 10/966,880 filed on Oct. 15, 2004, now U.S. Pat. No. 7,027,311.

The nonprovisional application designated above, namely application Ser. No. 10/966,880, filed Oct. 15, 2004, claims the benefit of U.S. Provisional Application No.:

APPLICATION NO. 60/511,860
FILING DATE Oct. 17,2003

FIELD OF THE INVENTION

The present invention is related to the retrieval of radiated electrical energy. More specifically, the present invention is related to the retrieval of radiated electrical energy that is optimized for any given portion of the RF spectrum using a plurality of taps.

BACKGROUND OF THE INVENTION

In the operation of the invention, ambient RF and generated RF signals provide a source of potential energy that can be gathered, stored and supplied to a multitude of devices requiring electrical energy or that can restore energy lost by a discharged source.

Traditional RF receiving devices utilize an antenna to capture a narrow band of frequencies within the RF spectrum, whereby the collection of RF frequencies is then filtered, or tuned, to a specific frequency(s) for the purposes of maximizing the signal being transmitted within the chosen frequency (s). The potential energy contained in the signal is then used for its intended purpose, such as audio, video or data processing. These RF receiving devices have focused on maximizing selectivity of the frequency in order to isolate and to be coherent without interference from other sources.

SUMMARY OF THE INVENTION

The present invention pertains to an apparatus for a wireless power supply. The apparatus comprises means for receiving a range of RF radiation across a collection of frequencies, preferably at a same time. The apparatus comprises means for converting the RF radiation across the collection of frequencies, preferably at a same time into DC.

The present invention pertains to a method for a wireless power supply. The method comprises the steps of receiving a range of RF radiation across a collection of frequencies, preferably at a same time. There is the step of converting the RF radiation across the collection of frequencies, preferably at a same time into DC.

BRIEF DESCRIPTION OF THE DRAWINGS

In the accompanying drawings, the preferred embodiment of the invention and preferred methods of practicing the invention are illustrated in which:

FIG. **1** is a schematic representation of a preferred embodiment of an apparatus of the present invention.

FIG. **2** is a schematic representation of a preferred embodiment of an apparatus of the present invention optimized for medium wave bandwidth RF energy retrieval, collection and storage.

FIG. **3** is a block diagram of the apparatus of the present invention.

DETAILED DESCRIPTION

Referring now to the drawings wherein like reference numerals refer to similar or identical parts throughout the several views, and more specifically to FIG. **1** thereof, there is shown an apparatus **10** for a wireless power supply. The apparatus **10** comprises means **12** for receiving a range of RF radiation across a collection of frequencies, preferably at a same time. The apparatus **10** comprises means **14** for converting the RF radiation across the collection of frequencies, preferably at a same time into DC.

Preferably, the converting means **14** includes an absorbing mechanism **16** which is resonant for a desired band of RF spectrum. The absorbing mechanism **16** preferably includes an inductor **18** which is resonant for the desired band of RF spectrum. Preferably, the converting means **14** includes a plurality of taps **20** placed at points along the inductor **18** to access the RF energy.

The tap points preferably are calculated by matching the inductor's **18** impedance to the desired band of RF spectrum. Preferably, the receiving means **12** includes an antenna **22**. The converting means **14** preferably includes a rectifying mechanism **24** which rectifies the RF energy and converts it into DC voltage. Preferably, the rectifying mechanism **24** includes a plurality of diodes **26** at each tap point which rectifies the RF energy and converts it into DC voltage.

The apparatus **10** preferably includes a storage device **28** for storing the DC voltage. Preferably, the antenna **22** impedance is matched 1:1 with the inductor **18** impedance. The RF spectrum preferably is between 60 Hz to 28 gigahertz.

The present invention pertains to a method for a wireless power supply. The method comprises the steps of receiving a range of RF radiation across a collection of frequencies. There is the step of converting the RF radiation across the collection of frequencies, preferably at a same time into DC.

Preferably, the converting step includes the step of absorbing the energy. The absorbing step preferably includes the step of absorbing the energy with an inductor **18**. Preferably, the converting step includes the step of accessing the absorbing energy with a plurality of taps **20** on the inductor **18**. There is preferably the step of matching the inductor's impedance to a desired RF range.

Preferably, the converting step includes the step of rectifying energy available at each tap and converting it into DC voltages. The rectifying step preferably includes the step of rectifying the energy available at each tap and converting it into DC voltages with diodes **26**. Preferably, the converting step includes the step of summing the DC voltages. The summing step preferably includes the step of adding the DC voltages among a series capacitor integrator. Preferably, there is the step of storing the summed DC voltages. There is preferably the step of using the stored DC voltages.

A method and apparatus **10** for retrieval of radiated electrical energy is described herein. The radiated energy to be captured is being transmitted in the portion of the electromagnetic spectrum sometimes referred to as RF, or Radio Frequency. The primary purpose of the method and apparatus **10** described herein, is to receive RF energy and convert the energy into a usable form of power. The method and apparatus **10** does not discern or interpret individual signals or frequencies. It is designed to absorb and convert signal, carrier and any associated interference for a chosen band or range of frequencies into reusable power.

In contrast, to traditional RF receiving devices, this methodology and apparatus **10** avoids selectivity. It has the unique characteristic of accepting broad ranges of the RF spectrum as a collection of frequencies. Each collected range of frequencies is then rectified, or converted, as a whole into a single voltage. Preferably, at the same time of RF absorption, the resultant voltage is generated. The apparatus **10** makes no attempt to tune for any specific frequency or signal. Each voltage, which is gathered from a given range of frequencies, is then added together and made available to power a device directly, to be stored, or to supply energy to a recharging apparatus. As is implicit from the aforementioned description, preferably, the apparatus **10** receives the RF radiation across the collection of frequencies at the same time.

The radiated electrical energy, to be utilized by the circuit, can be in the form of a wide range of the RF spectrum. Some examples of ambient RF sources can include, but are not limited to: Very Low Frequency—VLF (Maritime/Aeronautical Mobile), Medium Frequency—MF (AM Radio Broadcast), High Frequency—HF (Shortwave Radio Broadcast), Very High Frequency—VHF (TV and FM Radio Broadcast), Ultra High Frequency—UHF (TV, HDTV, PCS, WiFi) and certain Microwave transmissions. In addition, the apparatus **10** allows for the reception of dedicated RF transmission that are generated and broadcast for the specific purpose of transmitting power to the apparatus **10** for absorption, collection and utilization. In this case, it is not necessary for the dedicated RF transmission to contain a specific signal or data that needs to be interpreted for ancillary purposes such as audio/video or data reception and interpretation.

Using the technique described herein, one can design and create an apparatus **10** that is optimized for any given portion of the RF Spectrum. The necessary electrical and magnetic characteristics of the apparatus **10** components will vary depending on the chosen portion of the spectrum. Because of this, it is impractical to create one single apparatus **10** to cover the entire RF spectrum. However, it is possible to create individual apparatus **10**, each designed for a given RF band, and combine both the apparatus **10**, their outputs for maximum power efficiency.

A portion of a selected RF frequency band is intercepted by an antenna **22** placed in the field of emitted energy. The antenna **22** receives energy, in accordance with its design efficiency, and directs it into a system where it is absorbed, rectified, summed and delivered for use or storage.

RF Energy→Antenna→
[Absorbed→Rectified→Integrated→Delivered]
→Used

RF signals striking an antenna **22** are fed into an inductor (L), which is resonant for the desired band of RF spectrum. Note: In areas with a high concentration of RF energy, there is no need to attach an antenna **22**. The absorbed RF energy, consisting of fundamental, harmonic, inter-harmonic and standing waves is accessed via taps **20** (T**1**-Tx) on the inductor **18** which are placed at points along the inductor **18**. A key characteristic of this device is that a capacitor-less front-end allows for the inductors' wide bandwidth and maximum admittance of the incoming RF energy. The tap points are calculated by matching the inductor **18** section's impedance to the desired RF range.

The resultant RF energy, available at each tap point, is rectified by a device, such as diodes **26** (D**1**-Dx), and converted into DC Voltages. The individual rectified voltages are spread among a series capacitor integrator consisting of capacitors (C**1**-Cx). This broadband approach allows maximum energy to be spread among the series capacitor stack.

The sum of the voltages available from C**1**-Cx is stored in any storage device **28** such as a capacitor or group of capacitors Cs (s**1**-sx) and made available for immediate use, or to supply electronic device(s) requiring intermittent power. The electrical characteristics of the storage devices or capacitors, the configuration and actual number of storage devices is dependent on the voltage and power requirements of the device the apparatus **10** is delivering power to. (See Figure One)

Although not considered part of the apparatus **10**, the antenna **22** is an integral component of any practical device utilizing the method and apparatus **10** described. The key characteristics of the antenna **22** would be that it is capable of wide band reception, optimized for the chosen bandwidth, and takes into consideration the necessary effective area to support the power requirements of the target device.

Ideally, the antenna **22** impedance is matched 1:1 with the inductor **18** impedance of the apparatus **10**.

Note: In areas with a high concentration of RF energy, there is no need to attach an antenna **22** to the apparatus **10**.

Inductor **18**:

The characteristics of the inductor **18** is dependent on the chosen bandwidth of frequencies to be collected and utilized. The ideal inductor **18** should be constructed so that the mid point of total inductance would be resonant at the center frequency of the chosen RF segment or spectrum.

Multiple taps **20** provide fundamental and inter-harmonic output voltages from the selected band segments of radio frequency energy.

For example, a medium wave circuit (FIG. **2**), utilizing an antenna **22** impedance of 375 ohms, into an inductive circuit with 375 ohms of reactance, with a center frequency of 1.2 MHz would require an inductance of 100 uH. The effective bandwidth would be approximately 2 MHz wide. (−3 db down at each end of the band).

The inductor **18** can be calculated using the following standard resonance formula (Formula 1):

L=(d squared times n squared) divided by (18 times d plus 40 times j)

Where

L=inductance in micro-henrys.

d=conductor diameter in inches.

j=conductor length in inches.

n=number of conductor iterations.

Using similar formulae, the required inductance can be re-calculated for henrys, milli-henrys, pico-henrys and nano-henrys. ie. VLF, LF, MW, HF, VHF, UHF and Microwave frequency band segments.

Utilizing a capacitor-less front-end insures the inductors' wide bandwidth, and maximum admittance to the incoming RF energy.

Taps **20**:

Taps **20** are to be constructed and placed at points along the inductor **18**. Each tap provides an individual output voltage into the rectifying portion of the apparatus **10**.

The number of taps **20** from the inductor **18** can be calculated by the following formula (Formula 2):

Tn=Bw times pi

Where

Tn=Total number of taps.

Bw=Effective Bandwidth of inductor (in Megahertz).

Pi=3.1416

The default position of each tap on the inductor **18** is equidistant along the inductor **18**. Tap positions can also be calculated for optimum output voltage. When calculating the taps **20**, one must take into consideration known frequencies within the chosen band segment that contain higher RF energies, And using a standard resonance inductance formula (1) each individual tap can be calculated for the required frequency and optimum voltage output.

Rectifiers:

The RF energy available at each tap is converted to DC voltage via a rectifying device. The type of rectifying device to be used is dependent on the chosen frequency band, and includes crystal, germanium, silicon and any other types.

Integrator:

A voltage integrator is composed of capacitors C**1**-Cx. The values of these capacitors are dependent on the chosen frequency band, the unique characteristics of the rectifiers and the load imposed by the Storage stage. The reactance of this circuit varies greatly, even during normal operation. However, one can use a standard formula for capacitive reactance as a starting point for preliminary calculations:

$$Xc=1/(2*pi*F*C)$$

Where

Xc=Capacitive reactance in ohms

C=Capacitance in Microfarads.

F=Frequency in Hertz.

Pi=3.1416

Storage:

Storage component(s) are determined by the power requirements of the attached device(s), and the available RF energy absorbed by the inductor (L).

Using a Medium Wave example, a 2,200 micro-farad electrolytic capacitor is used as storage.

Sample Apparatus 10: Medium Wave (AM) Wireless Power Supply

A device has been constructed, using the method stated above, which uses the ambient (existing) AM Broadcast band of the RF spectrum as its source of energy. The device's primary purpose is to optimize the energy absorbed, collected and converted to reusable power.

The size and characteristics of the antenna **22** required for the circuit to operate are not considered a design requirement for the apparatus **10**. The antenna **22** needed to obtain sufficient energy to charge a storage device **28** in a typical urban area with several AM radio stations, would be similar to one used for a standard AM radio. In areas where there is a higher concentration of RF energy, the apparatus **10** itself, without an antenna **22**, is sufficient to develop stored power.

The inductor **18** is in the form of an air coil comprised of enameled #28 gauge wire wound onto a 2" form. The coil is a continuous tightly wound wire with taps **20** placed every twenty turns with a total of six taps **20** available (T**1**-T**6**). The top of the coil is where the antenna **22** is connected. The bottom of the coil is connected to ground.

Germanium diodes (IN34A) (D**1**-D**6**) are connected to each tap on the coil. The series capacitor integrator (C**1**-C**6**) is constructed as illustrated with the C**6** attached to ground. C**1**-C**6** are poly capacitors with a 0.068 uF rating. The power storage device **28** utilized in this sample apparatus **10**, C7, is a 2200 uF electrolytic capacitor.

Very wide band operation can be utilized by coupling multiple instances of the Broadband Wireless Power Supply together.

For Example:

A BWPS circuit designed and constructed (see design considerations) for a Very Low Frequency wave segment (60 Hz center frequency), can be coupled into another BWPS circuit designed and constructed (see design considerations) for an Ultra High Frequency wave segment (5 GHz center frequency). The outputs of each individual circuit connect (via another integrator circuit) into a common storage device **28** (i.e., capacitor) to "pool" collected and converted RF energy together. This technique can be repeated for any or all segments of the energy spectrum.

Although the invention has been described in detail in the foregoing embodiments for the purpose of illustration, it is to be understood that such detail is solely for that purpose and that variations can be made therein by those skilled in the art without departing from the spirit and scope of the invention except as it may be described by the following claims.

What is claimed is:

1. An apparatus, comprising:

means for receiving RF radiation within a plurality of frequency bands; and

means for converting separately the received RF radiation associated with each of the plurality of frequency bands into DC, the converting means includes an inductor and at least three taps, each tap from the at least three taps being placed at a unique point along the inductor to access an energy associated with the RF radiation.

2. An apparatus as described in claim **1** wherein the inductor includes one or more portions, each portion of the inductor is uniquely associated with one frequency band from the plurality of frequency bands, each portion of the inductor has a resonant frequency within that frequency band.

3. An apparatus as described in claim **2** wherein the tap points are calculated based on the resonant frequency for each portion of the inductor.

4. An apparatus as described, in claim **1** wherein the receiving means includes an antenna.

5. An apparatus as described in claim **1** wherein the converting means includes a rectifying mechanism which rectifies the energy associated with the received RE radiation to produce rectified energy and converts the rectified energy into a DC voltage.

6. An apparatus as described in claim **5** wherein the rectifying mechanism includes a diode at each tap point to rectify the energy associated with the received RF radiation into the DC voltage.

7. An apparatus as described in claim **5** further comprising a storage device for storing the DC voltage.

8. A method, comprising:

receiving RF radiation within a plurality of frequency bands at a single antenna;

separating the received RE radiation into a plurality of portions of the received RE radiation independent of a capacitor, each portion from the plurality of portions of the received RE radiation uniquely associated with a frequency band from the plurality of frequency bands; and

converting separately the plurality of portions of the received RE radiation into DC.

9. A method as the described in claim **8** wherein the converting includes absorbing an energy associated with the received RF radiation.

10. A method as described in claim **9** wherein the absorbing includes absorbing the energy with an inductor.

11. A method as described in claim **10** wherein the converting includes accessing the absorbed energy with a plurality of taps on the inductor.

12. A method as described in claim **11** wherein the converting includes rectifying the energy associated with each tap to produce rectified energy and converting the rectified energy associated with each tap into a DC voltage.

13. A method as described in claim **12** wherein the rectifying includes rectifying the energy associated with each tap to produce rectified energy and converting the rectified energy associated with each tap into the DC voltage with a diode.

14. A method as described in claim **13** wherein the converting includes adding the DC voltage associated with each tap from the plurality of taps into a single DC voltage.

15. A method as described in claim **14** wherein the adding includes integrating the DC voltage associated with each tap from the plurality of taps with a series capacitor integrator.

16. A method as described in claim **14** further comprising storing the single DC voltage.

17. An apparatus, comprising:

means for receiving a range of RF radiation across a collection of frequencies; and

means for converting RF radiation across the collection of frequencies into DC, including multiple taps to access the PT radiation across the collection of frequencies.

18. An apparatus, comprising:

means for receiving a range of RF radiation across a collection of frequencies with a single antenna; and

means for converting RF radiation across the collection of frequencies from the single antenna into DC, the converting means includes an inductor that is resonant for a desired band of RF spectrum, the inductor having a plurality of taps placed at points along the inductor to access the RE energy.

19. A method, comprising:

receiving a range of RF radiation across a collection of frequencies at a single antenna;

converting the RF radiation received at the single antenna across the collection of frequencies into DC by absorbing the energy with an inductor; and

accessing the absorbed energy with a plurality of taps on the inductor.

20. A method, comprising:

receiving radiation within an RF spectrum band via a single antenna, a first portion of the received radiation being associated with a first portion of the RF spectrum band, a second portion of the received radiation being associated with a second portion of the RF spectrum band different than the first portion;

converting separately the received radiation from each of the first portion of the RF spectrum band and the second portion of the RF spectrum band into a DC voltage; and

combining the DC voltage associated with the first portion of the RF spectrum band and the DC voltage associated with the second portion of the RE spectrum band.

* * * * *

UNITED STATES PATENT AND TRADEMARK OFFICE

CERTIFICATE OF CORRECTION

PATENT NO. : 7,643,312 B2
APPLICATION NO. : 11/357578
DATED : January 5, 2010
INVENTOR(S) : Timm A. Vanderelli et al.

Page 1 of 1

It is certified that error appears in the above-identified patent and that said Letters Patent is hereby corrected as shown below:

Column 6, line 36 (claim 5, line 3), replace "RE radiation" with -- RF radiation --.

Column 6, line 48 (claim 8, line 4), replace "RE radiation" with -- RF radiation --.

Column 6, line 49 (claim 8, line 5), replace "RE radiation" with -- RF radiation --.

Column 6, line 51 (claim 8, line 7), replace "RE radiation" with -- RF radiation --.

Column 6, line 55 (claim 8, line 11), replace "RE radiation" with -- RF radiation --.

Column 7, line 19 (claim 17, line 6), replace "PT radiation" with -- RF radiation --.

Column 8, line 3 (claim 18, line 9), replace "RE energy" with -- RF energy --.

Column 8, line 24 (claim 20, line 13), replace "RE spectrum band" with -- RF spectrum band --.

Signed and Sealed this
Eighteenth Day of January, 2011

David J. Kappos

David J. Kappos
Director of the United States Patent and Trademark Office

US008686575B2

(12) **United States Patent**
McCowen

(10) **Patent No.: US 8,686,575 B2**
(45) **Date of Patent: Apr. 1, 2014**

(54) ENERGY COLLECTION

(75) Inventor: **Clint McCowen**, Navarre, FL (US)

(73) Assignee: **Ion Power Group, LLC**, Navarre, FL (US)

(*) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 0 days.

(21) Appl. No.: **12/255,130**

(22) Filed: **Oct. 21, 2008**

(65) **Prior Publication Data**

US 2009/0040680 A1 Feb. 12, 2009

Related U.S. Application Data

(63) Continuation of application No. 11/358,264, filed on Feb. 21, 2006, now Pat. No. 7,439,712.

(51) **Int. Cl.**

F02B 63/04	(2006.01)
F03G 7/08	(2006.01)
H02K 7/18	(2006.01)
H02N 1/00	(2006.01)

(52) **U.S. Cl.**
USPC .... **290/1 R**; 322/2 A

(58) **Field of Classification Search**
USPC .... 290/1 R; 322/2 A; 126/660; 60/641.8, 60/641.11, 641.12, 659, 698; 244/158.2
See application file for complete search history.

(56) **References Cited**

U.S. PATENT DOCUMENTS

674,427	A		5/1901	Palencsar	307/149
911,260	A		2/1909	Pennock	307/149
1,014,719	A		1/1912	Pennock	307/149
2,473,819	A	*	6/1949	Pittman	315/36
3,532,959	A	*	10/1970	Erickson	320/166
3,780,722	A	*	12/1973	Swet	126/680
3,946,227	A		3/1976	Bingham	250/281
4,079,225	A	*	3/1978	Warner	219/110
4,092,250	A		5/1978	Sano et al.	210/500.29
4,104,696	A		8/1978	Cochran, Jr.	361/229
4,146,800	A	*	3/1979	Gregory et al.	290/44
4,180,056	A	*	12/1979	Schnabel et al.	126/660
4,201,197	A	*	5/1980	Dismer	126/600
4,206,396	A	*	6/1980	Marks	322/2 A
4,224,496	A	*	9/1980	Riordan et al.	219/110
4,307,936	A	*	12/1981	Ochiai	385/120
4,314,192	A	*	2/1982	Caro	322/2 R
4,346,478	A	*	8/1982	Sichling	398/107
4,425,905	A	*	1/1984	Mori	126/578
4,433,248	A	*	2/1984	Marks	290/44
RE31,678	E	*	9/1984	Ochiai	385/115

(Continued)

FOREIGN PATENT DOCUMENTS

WO	2007098341	8/2007

OTHER PUBLICATIONS

"Emissivity Values for Common Materials & Non-Metals", Raytek—A Fluke Company, http://www.raytek.com/Raytek/en-r0/IREducation/EmissivityNonMetals.htm, 1999.*

Primary Examiner — Pedro J Cuevas
(74) *Attorney, Agent, or Firm* — Benjamin A. Balser; Balser & Grell IP Law

(57) **ABSTRACT**

An energy collection system may collect and use the energy generated by an electric field. Collection fibers are suspended from a support wire system supported by poles. The support wire system is electrically connected to a load by a connecting wire. The collection fibers may be made of any conducting material, but carbon and graphite are preferred. Diodes may be used to restrict the backflow or loss of energy.

25 Claims, 10 Drawing Sheets



(56) **References Cited**

U.S. PATENT DOCUMENTS

4,483,311	A *	11/1984	Whitaker	126/602
4,489,269	A *	12/1984	Edling et al.	322/2 R
4,512,335	A *	4/1985	Mori	126/678
4,653,223	A *	3/1987	Mori	47/17
4,653,472	A *	3/1987	Mori	126/683
4,676,226	A *	6/1987	Mori	126/680
4,809,675	A *	3/1989	Mori	126/578
4,852,454	A *	8/1989	Batchelder	89/1.11
4,943,125	A *	7/1990	Laundre' et al.	385/35
4,988,159	A *	1/1991	Turner et al.	385/33
5,047,892	A	9/1991	Sakata et al.	361/231
5,114,101	A *	5/1992	Stern et al.	244/172.8
5,145,257	A *	9/1992	Bryant et al.	374/131
5,379,103	A *	1/1995	Zigler	356/73
5,851,309	A *	12/1998	Kousa	136/248
5,942,806	A *	8/1999	Veliadis	290/1 R
6,025,591	A	2/2000	Taylor et al.	250/292
6,038,363	A *	3/2000	Slater et al.	385/147
6,116,544	A *	9/2000	Forward et al.	244/158.2
6,173,922	B1 *	1/2001	Hoyt et al.	244/158.2
6,226,440	B1 *	5/2001	Lyons	385/119
6,419,191	B1 *	7/2002	Hoyt et al.	244/158.2
6,425,391	B1 *	7/2002	Davoren et al.	126/683
6,735,830	B1	5/2004	Merciel	250/324
6,765,212	B2 *	7/2004	Goetz et al.	250/339.11
6,846,447	B2 *	1/2005	Mbachu et al.	264/406
6,853,447	B2 *	2/2005	Goetz	356/237.1
6,894,772	B2 *	5/2005	Goetz et al.	356/237.1
6,925,852	B2 *	8/2005	Susko	73/23.2
6,974,110	B2	12/2005	Grandics	244/171.5
7,109,597	B1 *	9/2006	Bose	290/43
7,128,867	B2 *	10/2006	Mbachu et al.	264/406
7,231,809	B2 *	6/2007	Susko	73/31.05
7,259,475	B2 *	8/2007	Hong et al.	307/64
7,439,712	B2 *	10/2008	McCowen	322/2 A
7,449,668	B2 *	11/2008	Schutten et al.	250/214 SW
7,478,712	B2 *	1/2009	McCowen	191/45 R
7,532,819	B1 *	5/2009	Triebes et al.	398/121
2002/0026933	A1 *	3/2002	Gottlieb	126/628
2002/0108892	A1 *	8/2002	Goetz et al.	209/576
2002/0109094	A1 *	8/2002	Goetz et al.	250/339.11
2002/0109835	A1 *	8/2002	Goetz	356/237.1
2003/0107869	A1	6/2003	Pan et al.	361/306.2
2003/0125630	A1 *	7/2003	Furnish	600/461
2003/0193319	A1 *	10/2003	Wood et al.	322/2 A
2004/0011925	A1 *	1/2004	Grandics	244/62
2004/0083793	A1 *	5/2004	Susko	73/31.05
2004/0094853	A1 *	5/2004	Mbachu et al.	264/40.1
2004/0160711	A1	8/2004	Stumberger	361/20
2005/0101024	A1 *	5/2005	Mbachu et al.	436/85
2005/0136311	A1 *	6/2005	Ueda et al.	429/30
2005/0270525	A1 *	12/2005	Susko	356/326
2007/0107765	A1 *	5/2007	Schutten et al.	136/243
2007/0195481	A1 *	8/2007	McCowen	361/233
2007/0218323	A1 *	9/2007	Sudo et al.	429/13
2007/0223171	A1	9/2007	Guy et al.	361/126
2007/0273206	A1 *	11/2007	McCowen	307/9.1
2007/0297892	A1 *	12/2007	Kildegaard	415/1
2008/0145714	A1 *	6/2008	Kagami	429/13
2009/0107842	A1	4/2009	Park et al.	204/554
2009/0114495	A1 *	5/2009	McCowen	191/45 R
2009/0216292	A1 *	8/2009	Pless et al.	607/33
2010/0090562	A1 *	4/2010	McCowen	310/309
2010/0090563	A1 *	4/2010	McCowen	310/309
2012/0164555	A1 *	6/2012	Yamazaki et al.	429/482
2012/0299559	A1 *	11/2012	McCowen	322/2 A
2013/0276776	A1 *	10/2013	Te Kamp et al.	126/660

* cited by examiner



FIGURE 1


100
110
110
120
130
110
110
140
150

FIGURE 2



FIGURE 2A



FIGURE 2B


200
240
260
250
270
130

FIGURE 2C

FIGURE 2D


278
200
130
275


200
280
285
130

FIGURE 2E

FIGURE 2F



FIGURE 2G


200
294
130
292


300
310
330
320
340
150

FIGURE 3


400
310
440
410
420
450
430
150

FIGURE 4

FIGURE 5


310
500
510
520
150

FIGURE 6


310
600
610
620
630
640

FIGURE 7


310
700
720
150



FIGURE 8

800
From Collectors
810
820
825
830
150
870


910
SUSPEND COLLECTION FIBER FROM SUPPORT STRUCTURE WIRE
920
CONNECT LOAD TO SUPPORT STRUCTURE WIRE
930
CONNECT DIODE BETWEEN SUPPORT STRUCTURE WIRE AND LOAD
940
STORE ENERGY PROVIDED TO LOAD

FIGURE 9

ENERGY COLLECTION

CROSS REFERENCE TO RELATED APPLICATION

This application is a continuation application of U.S. patent application Ser. No. 11/358,264, filed on Feb. 21, 2006, which is incorporated by reference herein.

TECHNICAL FIELD

The present disclosure is generally related to energy and, more particularly, is related to systems and methods for collecting energy.

BACKGROUND

The concept of fair weather electricity deals with the electric field and the electric current in the atmosphere propagated by the conductivity of the air. Clear, calm air carries an electrical current, which is the return path for thousands of lightening storms simultaneously occurring at any given moment around the earth. For simplicity, this energy may be referred to as static electricity or static energy. FIG. **1** illustrates a weather circuit for returning the current from lightning, for example, back to ground **10**. Weather currents **20**, **30** return the cloud to ground current **40**.

In a lightening storm, an electrical charge is built up, and electrons arc across a gas, ionizing it and producing the lightening flash. As one of ordinary skill in the art understands, the complete circuit requires a return path for the lightening flash. The atmosphere is the return path for the circuit. The electric field due to the atmospheric return path is relatively weak at any given point because the energy of thousands of electrical storms across the planet are diffused over the atmosphere of the entire Earth during both fair and stormy weather. Other contributing factors to electric current being present in the atmosphere may include cosmic rays penetrating and interacting with the earth's atmosphere, and also the migration of ions, as well as other effects yet to be fully studied.

Some of the ionization in the lower atmosphere is caused by airborne radioactive substances, primarily radon. In most places of the world, ions are formed at a rate of 5-10 pairs per cubic centimeter per second at sea level. With increasing altitude, cosmic radiation causes the ion production rate to increase. In areas with high radon exhalation from the soil (or building materials), the rate may be much higher.

Alpha-active materials are primarily responsible for the atmospheric ionization. Each alpha particle (for instance, from a decaying radon atom) will, over its range of some centimeters, create approximately 150,000-200,000 ion pairs.

While there is a large amount of usable energy available in the atmosphere, a method or apparatus for efficiently collecting that energy has not been forthcoming. Therefore, a heretofore unaddressed need exists in the industry to address the aforementioned deficiencies and inadequacies.

SUMMARY

Embodiments of the present disclosure provide systems and methods for collecting energy. Briefly described in architecture, one embodiment of the system, among others, can be implemented by a support structure wire elevated above a ground level, at least one collection fiber electrically connected to the support structure wire; a load electrically connected to the support structure wire; and a diode electrically connected between the load and at least one collection fiber.

Embodiments of the present disclosure can also be viewed as providing methods for collecting energy. In this regard, one embodiment of such a method, among others, can be broadly summarized by the following steps: suspending at least one collection fiber from a support structure wire elevated above ground level, the fiber electrically connected to the support structure wire; providing a load with an electrical connection to the support structure wire to draw current; and providing a diode electrically connected between the collection fiber and the load.

Other systems, methods, features, and advantages of the present disclosure will be or become apparent to one with skill in the art upon examination of the following drawings and detailed description. It is intended that all such additional systems, methods, features, and advantages be included within this description, be within the scope of the present disclosure, and be protected by the accompanying claims.

BRIEF DESCRIPTION OF THE DRAWINGS

Many aspects of the disclosure can be better understood with reference to the following drawings. The components in the drawings are not necessarily to scale, emphasis instead being placed upon clearly illustrating the principles of the present disclosure. Moreover, in the drawings, like reference numerals designate corresponding parts throughout the several views.

FIG. **1** is a circuit diagram of a weather energy circuit.

FIG. **2** is a perspective view of an exemplary embodiment of many energy collectors elevated above ground by a structure.

FIG. **2**A is a side view of an energy collection fiber suspended from a support wire.

FIG. **2**B is a side view of an exemplary embodiment of an energy collection fiber suspended from a support wire and with an additional support member.

FIG. **2**C is a perspective view of a support structure for multiple energy collection fibers.

FIG. **2**D is a side view of an exemplary embodiment of a support structure for multiple energy collection fibers.

FIG. **2**E is a side view of a support structure for an energy collection fiber.

FIG. **2**F is a side view of an exemplary embodiment of a support structure for an energy collection fiber.

FIG. **2**G is a side view of a support structure for multiple energy collection fibers.

FIG. **3** is a circuit diagram of an exemplary embodiment of a circuit for the collection of energy.

FIG. **4** is a circuit diagram of an exemplary embodiment of a circuit for the collection of energy.

FIG. **5** is a circuit diagram of an exemplary embodiment of an energy collection circuit for powering a generator and motor.

FIG. **6** is a circuit diagram of an exemplary embodiment of a circuit for collecting energy and using it for the production of hydrogen and oxygen.

FIG. **7** is a circuit diagram of an exemplary embodiment of a circuit for collecting energy, and using it for driving a fuel cell.

FIG. **8** is a circuit diagram of an exemplary embodiment of a circuit for collecting energy.

FIG. **9** is a flow diagram of an exemplary embodiment of collecting energy with a collection fiber.

DETAILED DESCRIPTION

Electric charges on conductors reside entirely on the external surface of the conductors, and tend to concentrate more around sharp points and edges than on flat surfaces. Therefore, an electric field received by a sharp conductive point may be much stronger than a field received by the same charge residing on a large smooth conductive shell. An exemplary embodiment of this disclosure takes advantage of this property, among others, to collect and use the energy generated by an electric field in the atmosphere. Referring to collection system **100** presented in FIG. **2**, at least one collection device **130** may be suspended from a support wire system **120** supported by poles **110**. Collection device **130** may comprise a diode or a collection fiber individually, or the combination of a diode and a collection fiber. Support wire system **120** may be electrically connected to load **150** by connecting wire **140**. Supporting wire system **120** may be any shape or pattern. Also, conducting wire **140** may be one wire or multiple wires. The collection device **130** in the form of a fiber may comprise any conducting or non-conducting material, including carbon, graphite, Teflon, and metal. An exemplary embodiment utilizes carbon or graphite fibers for static electricity collection. Support wire system **120** and connecting wire **140** can be made of any conducting material, including aluminum or steel, but most notably, copper. Teflon may be added to said conductor as well, such as non-limiting examples of a Teflon impregnated wire, a wire with a Teflon coating, or Teflon strips hanging from a wire. Conducting wire **120**, **140**, and **200** may be bare wire, or coated with insulation as a non-limiting example. Wires **120** and **140** are a means of transporting the energy collected by collection device **130**.

An exemplary embodiment of the collection fibers as collection device **130** includes graphite or carbon fibers. Graphite and carbon fibers, at a microscopic level, can have hundreds of thousands of points. Atmospheric electricity may be attracted to these points. If atmospheric electricity can follow two paths where one is a flat surface and the other is a pointy, conductive surface, the electrical charge will be attracted to the pointy, conductive surface. Generally, the more points that are present, the higher energy that can be gathered. Therefore, carbon, or graphite fibers are examples that demonstrate exemplary collection ability.

In at least one exemplary embodiment, the height of support wire **120** may be an important factor. The higher that collection device **130** is from ground, the larger the voltage potential between collection device **130** and electrical ground. The electric field may be more than 100 volts per meter under some conditions. When support wire **120** is suspended in the air at a particular altitude, wire **120** will itself collect a very small charge from ambient voltage. When collection device **130** is connected to support wire **120**, collection device **130** becomes energized and transfers the energy to support wire **120**.

A diode, not shown in FIG. **2**, may be connected in several positions in collection system **100**. A diode is a component that restricts the direction of movement of charge carriers. It allows an electric current to flow in one direction, but essentially blocks it in the opposite direction. A diode can be thought of as the electrical version of a check valve. The diode may be used to prevent the collected energy from discharging into the atmosphere through the collection fiber embodiment of collection device **130**. An exemplary embodiment of the collection device comprises the diode with no collection fiber. A preferred embodiment, however, includes a diode at the connection point of a collection fiber to support system **120** such that the diode is elevated above ground. Multiple diodes may be used between collection device **130** and load **150**. Additionally, in an embodiment with multiple fibers, the diodes restricts energy that may be collected through one fiber from escaping through another fiber.

Collection device **130** may be connected and arranged in relation to support wire system **120** by many means. Some non-limiting examples are provided in FIGS. **2A-2G** using a collection fiber embodiment. FIG. **2A** presents support wire **200** with connecting member **210** for collection device **130**. Connection member **210** may be any conducting material allowing for the flow of electricity from connection device **130** to support wire **200**. Then, as shown in FIG. **2**, the support wire **200** of support system **120** may be electrically connected through conducting wire **140** to load **150**. A plurality of diodes may be placed at any position on the support structure wire. A preferred embodiment places a diode at an elevated position at the connection point between a collection fiber embodiment of collection device **130** and connection member **210**.

Likewise, FIG. **2B** shows collection fiber **130** electrically connected to support wire **200** and also connected to support member **230**. Support member **230** may be connected to collection fiber **130** on either side. Support member **230** holds the fiber steady on both ends instead of letting it move freely. Support member **230** may be conducting or non-conducting. A plurality of diodes may be placed at any position on the support structure wire. A preferred embodiment places a diode at elevated position at the connection point between collection fiber **130** and support wire **200** or between fiber **130**, support member **230**, and support wire **200**.

FIG. **2C** presents multiple collection fibers in a squirrel cage arrangement with top and bottom support members. Support structure **250** may be connected to support structure wire **200** by support member **240**. Structure **250** has a top **260** and a bottom **270** and each of the multiple collection fibers **130** are connected on one end to top **260** and on the other end to bottom **270**. A plurality of diodes may be placed at any position on support structure **250**. A preferred embodiment places a diode at an elevated position at the connection point between collection fiber **130** and support structure wire **200**.

FIG. **2D** presents another exemplary embodiment of a support structure with support members **275** in an x-shape connected to support structure wire **200** at intersection **278** with collection fibers **130** connected between ends of support members **275**. A plurality of diodes may be placed at any position on the support structure. A preferred embodiment places a diode at an elevated position at the connection point between collection fiber **130** and support wire **200**.

FIG. **2E** provides another exemplary embodiment for supporting collection fiber **130**. Collection fiber **130** may be connected on one side to support member **285**, which may be connected to support structure wire **200** in a first location and on the other side to support member **280**, which may be connected to support structure wire **200** in a second location on support structure wire **200**. The first and second locations may be the same location, or they may be different locations, even on different support wires. A plurality of diodes may be placed at any position on the support structure. A preferred embodiment places one or more diodes at elevated positions at the connection point(s) between collection fiber **130** and support wire **200**.

FIG. **2F** presents another exemplary embodiment of a support for a collection fiber. Two support members **290** may support either side of a collection fiber and are connected to support wire **200** in a single point. A plurality of diodes may be placed at any position on the support structure. A preferred embodiment places a diode at an elevated position at the connection point between collection fiber **130** and support wire **200**.

FIG. **2G** provides two supports as provided in FIG. **2F** such that at least two support members **292**, **294** may be connected to support structure wire **200** in multiple locations and collection fibers **130** may be connected between each end of the support structures. Collection fibers **130** may be connected between each end of a single support structure and between multiple support structures. A plurality of diodes may be placed at any position on the support structure. A preferred embodiment places one or more diodes at elevated positions at the connection point(s) between collection fiber **130** and support structure wire **200**.

FIG. **3** provides a schematic diagram of storing circuit **300** for storing energy collected by one or more collection devices (**130** from FIG. **2**). Load **150** induces current flow. Diode **310** may be electrically connected in series between one or more collection devices (**130** from FIG. **2**) and load **150**. A plurality of diodes may be placed at any position in the circuit. Switch **330** may be electrically connected between load **150** and at least one collection device (**130** from FIG. **2**) to connect and disconnect the load. Capacitor **320** may be connected in parallel to the switch **330** and load **150** to store energy when switch **330** is open for delivery to load **150** when switch **330** is closed. Rectifier **340** may be electrically connected in parallel to load **150**, between the receiving end of switch **330** and ground. Rectifier **340** may be a full-wave or a half-wave rectifier. Rectifier **340** may include a diode electrically connected in parallel to load **150**, between the receiving end of switch **330** and ground. The direction of the diode of rectifier **340** is optional.

In an exemplary embodiment provided in FIG. **4**, storage circuit **400** stores energy from one or more collection devices (**130** from FIG. **2**) by charging capacitor **410**. If charging capacitor **410** is not used, then the connection to ground shown at capacitor **410** is eliminated. A plurality of diodes may be placed at any position in the circuit. Diode **310** may be electrically connected in series between one or more collection devices (**130** from FIG. **2**) and load **150**. Diode **440** may be placed in series with load **150**. The voltage from capacitor **410** can be used to charge spark gap **420** when it reaches sufficient voltage. Spark gap **420** may comprise one or more spark gaps in parallel. Non-limiting examples of spark gap **420** include mercury-reed switches and mercury-wetted reed switches. When spark gap **420** arcs, energy will arc from one end of the spark gap **420** to the receiving end of the spark gap **420**. The output of spark gap **420** may be electrically connected in series to rectifier **450**. Rectifier **450** may be a full-wave or a half-wave rectifier. Rectifier **450** may include a diode electrically connected in parallel to transformer **430** and load **150**, between the receiving end of spark gap **420** and ground. The direction of the diode of rectifier **450** is optional. The output of rectifier **450** is connected to transformer **430** to drive load **150**.

FIG. **5** presents motor driver circuit **500**. One or more collection devices (**130** from FIG. **2**) are electrically connected to static electricity motor **510**, which powers generator **520** to drive load **150**. A plurality of diodes may be placed at any position in the circuit. Motor **510** may also be directly connected to load **150** to drive it directly.

FIG. **6** demonstrates a circuit **600** for producing hydrogen. A plurality of diodes may be placed at any position in the circuit. One or more collection devices (**130** from FIG. **2**) are electrically connected to primary spark gap **610**, which may be connected to secondary spark gap **640**. Non-limiting examples of spark gaps **610**, **640** include mercury-reed switches and mercury-wetted reed switches. Secondary spark gap **640** may be immersed in water **630** within container **620**. When secondary spark gap **640** immersed in water **630** is energized, spark gap **640** may produce bubbles of hydrogen and oxygen, which may be collected to be used as fuel.

FIG. **7** presents circuit **700** for driving a fuel cell. A plurality of diodes may be placed at any position in the circuit. Collection devices (**130** from FIG. **2**) provide energy to fuel cell **720** which drives load **150**. Fuel cell **720** may produce hydrogen and oxygen.

FIG. **8** presents exemplary circuit **800** for the collection of energy. Storage circuit **800** stores energy from one or more collection devices (**130** from FIG. **2**) by charging capacitor **810**. If charging capacitor **810** is not used, then the connection to ground shown at capacitor **810** is eliminated. A plurality of diodes may be placed at any position in the circuit. The voltage from capacitor **810** can be used to charge spark gap **820** when it reaches sufficient voltage. Spark gap **820** may comprise one or more spark gaps in parallel or in series. Non-limiting examples of spark gap **820** include mercury-reed switches and mercury-wetted reed switches. When spark gap **820** arcs, energy will arc from one end of spark gap **820** to the receiving end of spark gap **820**. The output of spark gap **820** may be electrically connected in series to rectifier **825**. Rectifier **825** may be a full-wave or a half-wave rectifier. Rectifier **825** may include a diode electrically connected in parallel to inductor **830** and load **150**, between the receiving end of spark gap **820** and ground. The direction of the diode of rectifier **825** is optional. The output of rectifier **825** is connected to inductor **830**. Inductor **830** may be a fixed value inductor or a variable inductor. Capacitor **870** may be placed in parallel with load **150**.

FIG. **9** presents a flow diagram of a method for collecting energy. In block **910**, one or more collection devices may be suspended from a support structure wire. In block **920**, a load may be electrically connected to the support structure wire to draw current. In block **930** a diode may be electrically connected between the support structure wire and the electrical connection to the load. In block **940**, energy provided to the load may be stored or otherwise utilized.

Any process descriptions or blocks in flow charts should be understood as representing modules, segments, or portions of code which include one or more executable instructions for implementing specific logical functions or steps in the process, and alternate implementations are included within the scope of the preferred embodiment of the present disclosure in which functions may be executed out of order from that shown or discussed, including substantially concurrently or in reverse order, depending on the functionality involved, as would be understood by those reasonably skilled in the art of the present disclosure.

It should be emphasized that the above-described embodiments of the present disclosure, particularly, any "preferred" embodiments, are merely possible examples of implementations, merely set forth for a clear understanding of the principles of the disclosure. Many variations and modifications may be made to the above-described embodiment(s) of the disclosure without departing substantially from the spirit and principles of the disclosure. All such modifications and variations are intended to be included herein within the scope of this disclosure and the present disclosure and protected by the following claims.

Therefore, at least the following is claimed:

1. A method of collecting energy comprising:

suspending at least one collection device with, in operation, microscopic points of a cross-section of the collection device exposed to the environment, the at least one collection device electrically connected to the support structure;

providing a load with an electrical connection to the at least one collection device to passively draw current; and powering a fuel cell between the support structure and the load, the powering performed with energy collected from the at least one collection device.

2. The method of claim 1, wherein the collection device comprises a diode.

3. The method of claim 1, wherein the collection device comprises a collection fiber.

4. The method of claim 1, wherein the collection device comprises a diode and a collection fiber and the diode is electrically connected between the collection fiber and the load.

5. The method of claim 1, further comprising storing energy provided to the load.

6. The method of claim 5, wherein storing energy provided to the load comprises storing energy in a capacitor or an inductor.

7. The method of claim 3, wherein the collection fiber comprises carbon fiber or graphite fiber.

8. A system of energy collection comprising:

a support structure;

at least one collection device with, in operation, microscopic points of a cross-section of the collection device exposed to the environment, the collection device electrically connected to and suspended from the support structure, the at least one collection device configured to passively draw current;

a load electrically connected to the at least one collection device; and

a diode electrically connected between the at least one collection device and the support structure.

9. The system of claim 8, wherein the collection device comprises a diode.

10. The system of claim 8, wherein the collection device comprises a collection fiber.

11. The system of claim 8, wherein the collection device comprises a collection fiber and a diode electrically connected between the load and the collection fiber.

12. The system of claim 9, wherein the diode is elevated relative to the ground level.

13. The system of claim 10, wherein the collection fiber comprises a carbon fiber or a graphite fiber.

14. The system of claim 8, further comprising:

a switch connected in series between the at least one collection device and the load; and

a capacitor connected in parallel with the switch and the load.

15. The system of claim 14, wherein the switch comprises an interrupter connected between the at least one collection device and the load, and wherein the interrupter comprises at least one of a fluorescent tube, a neon bulb, an AC light, and a spark gap.

16. The system of claim 15, further comprising a transformer connected between the interrupter and the load.

17. The system of claim 8, further comprising:

a motor for providing power, the motor connected between the at least one collection device and the load; and

a generator powered by the motor.

18. The system of claim 8, further comprising a fuel cell between the support structure and the load.

19. The system of claim 18, wherein the fuel cell produces hydrogen and oxygen.

20. A system of collecting energy comprising:

means for suspending at least one collection device with, in operation, microscopic points of a cross-section of the collection device exposed to the environment, the at least one collection device electrically connected to the means for suspending;

means for passively inducing current flow, the means for inducing current flow electrically connected to the means for suspending; and

means for restricting the backflow of charge carriers, the means for restricting the backflow of charge carriers electrically connected between the at least one collection device and the means for inducing current flow.

21. A system of energy collection comprising:

a support structure;

at least one collection device with, in operation, microscopic points of a cross-section of the collection device exposed to the environment, the collection device electrically connected to and suspended from the support structure, the at least one collection device configured to passively draw current;

a load electrically connected to the at least one collection device; and

a switch connected in series between the at least one collection device and the load, the switch comprising an interrupter connected between the at least one collection device and the load, and wherein the interrupter comprises at least one of a fluorescent tube, a neon bulb, an AC light, and a spark gap.

22. The system of claim 21, further comprising a transformer connected between the interrupter and the load.

23. A system of energy collection comprising:

a support structure;

at least one collection device with, in operation, microscopic points of a cross-section of the collection device exposed to the environment, the at least one collection device electrically connected to and suspended from the support structure, the collection device configured to passively draw current;

a load electrically connected to the at least one collection device;

a motor for providing power, the motor connected between the at least one collection device and the load; and

a generator powered by the motor.

24. A system of energy collection comprising:

a support structure;

at least one collection device with, in operation, microscopic points of a cross-section of the collection device exposed to the environment, the at least one collection device electrically connected to and suspended from the support structure the at least one collection device configured to passively draw current;

a load electrically connected to the at least one collection device; and

a fuel cell between the support structure and the load.

25. The system of claim 24, wherein the fuel cell produces hydrogen and oxygen.

* * * * *

US 20120274144A1

(19) **United States**

(12) **Patent Application Publication** (10) **Pub. No.: US 2012/0274144 A1**

Gasparini et al. (43) **Pub. Date: Nov. 1, 2012**

(54) **SYSTEM AND METHOD FOR EFFICIENTLY HARVESTING ENVIRONMENTAL ENERGY**

(75) Inventors: **Alessandro Gasparini**, Cusano Milanino (IT); **Stefano Ramorini**, Arluno (IT); **Giorgio Massimiliano Membretti**, Milano (IT)

(73) Assignee: **STMICROELECTRONICS S.R.L.**, Agrate Brianza (MB) (IT)

(21) Appl. No.: **13/456,814**

(22) Filed: **Apr. 26, 2012**

(30) **Foreign Application Priority Data**

Apr. 29, 2011 (IT) TO2011A000379

Publication Classification

(51) **Int. Cl.**
H02J 1/00 (2006.01)

(52) **U.S. Cl.** **307/80**

(57) **ABSTRACT**

A transducer converts energy coming from an energy source into an electrical signal for storage as electrical energy on a first storage element. A switch is selectively actuated to pass electrical energy from the first storage element to a second storage element. The selective actuation of the switch is driven by sensing electrical energy stored in the second storage element. The switch is closed when electrical energy in the second storage element is sensed to fall below a first threshold. The switch is opened when electrical energy in the second storage element is sensed to rise above a second threshold.




1
TRANSDUCER
$P_{TRANSD}max$
SCAVENGING INTERFACE
P_{SCAV}
V_{OUT}
DC-DC CONVERTER
P_{LOAD}
8
2
4
5
6

Fig.1


1
3
2
R_S
V_{TRANSD_EQ}
4,6,8
R_{LOAD}
GND
GND

Fig.2


10
TRANSDUCER
2
$P_{TRANSD}max$
SCAVENGING INTERFACE
4
P_{SCAV}
12
V_{OUT_INT}
14
16
V_{IN_CONV}
P_{CONV}
DC-DC CONVERTER
6
P_{LOAD}
18a
18n

Fig.3


TRANSDUCER
V_TRANSD
C1
LOGIC
V_OUT_INT
GND
C2
V_IN_CONV
DC-DC CONVERTER
18n

Fig.4


P_TRANSD max
SCAVENGING INTERFACE
P_SCAV
V_OUT_INT
P_CONV
V_INV_CONV
DC – DC CONVERTER
P_LOAD
4
12
16
6

Fig.5


P_TRANSD max
SCAVENGING INTERFACE
P_SCAV
V_OUT_INT
P_CONV
V_INV_CONV
DC – DC CONVERTER
P_LOAD
4
12
16
6

Fig.6


28
41
26
24
14
40
DRIV. CIRCUIT
32
V_{IN_CONV}
V_P
+
CONTROL CIRCUIT
V_{COMP}
COMP.
V_R
-
38
36
34
V_P
GND

Fig.7


V_{COMP}
$V_{COMP}+$
0
V_L'
V_R
V_H'
V_P
$V_{COMP}-$
VHYST

Fig.8


[V]
V_TRASD
0,5
1
1,5
2
2,5
3
3,5
4
4,5
5
[s]

Fig.9


[V]
30
25
V_H 20
15
10
5
V_L
0
0,5
1
1,5
2
2,5
3
3,5
4
4,5
5
[s]
t_1
t_2
t_3
t_4
t_5
V_OUT_INT
V_IN_CONV

Fig.10


100
50
10
2
50
102
102
10
2
50

Fig.11

SYSTEM AND METHOD FOR EFFICIENTLY HARVESTING ENVIRONMENTAL ENERGY

PRIORITY CLAIM

[0001] This application claims priority from Italian Application for Patent No. TO2011A000379 filed Apr. 29, 2011, the disclosure of which is hereby incorporated by reference.

TECHNICAL FIELD

[0002] The present invention relates to a system and to a method for efficiently harvesting environmental energy.

BACKGROUND

[0003] As is known, systems for harvesting energy (also known as "energy harvesting" or "energy scavenging" systems) from intermittent environmental energy sources, have aroused and continue to arouse considerable interest in a wide range of technological fields. Typically, energy harvesting systems are designed to harvest, store, and transfer energy generated by mechanical sources to a generic load of an electrical type.

[0004] One of the main energy sources that can be used for harvesting mechanical energy and converting it into electrical energy is constituted by piezoelectric or electromagnetic devices. Low-frequency vibrations, such as for example mechanical vibrations of disturbance in systems with moving parts, can be a valid energy source.

[0005] The main needs that are felt in the field of systems for harvesting energy from environmental sources include minimum consumption of energy of the components of the systems themselves, maximum efficiency for harvesting, conversion, and storage of energy, and the need to supply the energy stored to a plurality of devices different from one another that use it for their operation.

[0006] FIG. **1** is a schematic illustration, by means of functional blocks, of an energy harvesting system of a known type.

[0007] The energy harvesting system **1** of FIG. **1** comprises: a transducer **2**, for example of an electromagnetic or piezoelectric type, subjected in use to environmental mechanical vibrations and configured for converting mechanical energy into electrical energy; a scavenging interface **4**, for example comprising a rectifier circuit, configured for receiving at input an AC signal generated by the transducer **2** and supplying at output a DC signal for charging a capacitor **5** connected to the output of the scavenging interface **4**; and a DC-DC converter **6**, connected to the capacitor **5** for receiving at input the electrical energy stored by the capacitor **5** and supplying it to an electrical load **8**.

[0008] The global efficiency η_{TOT} of the energy harvesting system **1** is given by Eq. (1) below:

$$\eta_{TOT}=\eta_{TRANSD}\cdot\eta_{SCAV}\cdot\eta_{DCDC} \quad (1)$$

[0009] where: η_{TRANSD} is the efficiency of the transducer **2**, indicating the amount of energy available in the environment that has been effectively converted, by the transducer **2**, into electrical energy; η_{SCAV} is the efficiency of the scavenging interface **4**, indicating the energy consumed by the scavenging interface **4** and the factor of impedance decoupling between the transducer and the interface; and η_{DCDC} is the efficiency of the DC-DC converter **6**.

[0010] As is known, in order to supply to the load the maximum power available, the impedance of the load should be equal to that of the source. As illustrated in FIG. **2**, the transducer **2** can be represented schematically, in this context, as a voltage generator **3** provided with an internal resistance R_S of its own. The maximum power P_{TRANSD}^{MAX} that the transducer **2** can supply at output may be defined as:

$$P_{TRANSD}^{MAX}=V_{TRANSD\_EQ}^{2}/4R_S;\ \text{if}\ R_{LOAD}=R_S \quad (2)$$

[0011] Where: V_{TRANSD_EQ} is the voltage produced by the equivalent voltage generator; and R_{LOAD} is the equivalent electrical resistance on the output of the transducer **2** (or, likewise, seen at input to the scavenging interface **4**), which takes into due consideration the equivalent resistance of the scavenging interface **4**, of the DC-DC converter **6**, and of the load **8**.

[0012] On account of the impedance decoupling ($R_{LOAD}\neq R_S$), the power at input to the scavenging interface **4** is lower than the maximum power available P_{TRANSD}^{MAX}.

[0013] The power P_{SCAV} stored by the capacitor **5** is a fraction of the power recovered by the interface, and is given by Eq. (3):

$$P_{SCAV}=\eta_{TRANSD}\cdot\eta\text{SCAV}\cdot P_{TRANSD}^{MAX} \quad (3)$$

[0014] whilst the power P_{EL_LOAD} supplied at output by the DC-DC converter to the electrical load **8** is given by the following Eq. (4):

$$P_{EL\_LOAD}=P_{DCDC}\cdot\eta_{DCDC} \quad (4)$$

[0015] where P_{DCDC} is the power received at input by the DC-DC converter **8**, in this case coinciding with P_{SCAV}.

[0016] The main disadvantage of the configuration according to FIG. **1** regards the fact that the maximum voltage supplied at output by the scavenging interface **4** is limited by the input dynamics of the DC-DC converter **8**.

[0017] The voltage V_{OUT} across the capacitor **5** (supplied at output by the scavenging interface **4** and at input to the DC-DC converter **8**) is in fact determined on the basis of the power balancing according to the following Eq. (5):

$$P_{STORE}=P_{SCAV}-P_{DCDC} \quad (5)$$

[0018] where P_{STORE} is the excess power with respect to the power required by the load, recovered by the interface and stored in the capacitor.

[0019] In applications where the transducer **2** converts mechanical energy into electrical energy in a discontinuous way (i.e., the power P_{TRANSD}^{MAX} varies significantly in time) and/or the power P_{EL_LOAD} required by the electrical load **8** varies significantly in time, also the voltage V_{OUT} consequently presents a plot that is variable in time.

[0020] This causes, for example, a variation of the efficiency factor η_{DCDC}, which assumes low values at high values of V_{OUT}. The maximum value of V_{OUT} is moreover limited by the range of input voltages allowed by the DC-DC converter. Maximization of the window of values allowed at input by the DC-DC converter **6** requires a specific design of the DC-DC converter; however, also in the latter case, an upper limit of the range of allowable values for V_{OUT} is imposed.

[0021] There is a need in the art to provide system and a method for efficiently harvesting environmental energy that will enable the aforesaid problems and disadvantages to be overcome.

SUMMARY

[0022] In accordance with an embodiment, a system and method enable maximization of the storage of electrical charge without requiring constraints of design of other components of the system itself, maximizing the global efficiency.

[0023] According to the present invention a system and a method for efficiently harvesting environmental energy are provided as defined in the annexed claims.

BRIEF DESCRIPTION OF THE DRAWINGS

[0024] For a better understanding of the present invention, preferred embodiments thereof are now described, purely by way of non-limiting example and with reference to the attached plates of drawings, wherein:

[0025] FIG. **1** shows an energy harvesting system according to a known embodiment;

[0026] FIG. **2** shows an equivalent circuit representation of the system of FIG. **1**;

[0027] FIG. **3** shows an energy harvesting system according to one embodiment of the present invention;

[0028] FIG. **4** shows at a greater circuit detail the system of FIG. **3**;

[0029] FIG. **5** shows the system of FIG. **3** during a first operating step;

[0030] FIG. **6** shows the system of FIG. **3** during a second operating step;

[0031] FIG. **7** is a schematic illustration of control logic for the system of FIG. **3**;

[0032] FIG. **8** shows a hysteresis curve of a hysteretic comparator of the control logic of FIG. **7**;

[0033] FIGS. **9** and **10** show the time plots of electrical signals internal to the system of FIG. **3**; and

[0034] FIG. **11** shows a vehicle comprising the system of FIG. **3**.

DETAILED DESCRIPTION OF THE DRAWINGS

[0035] FIG. **3** shows an energy harvesting system **10** according to one embodiment.

[0036] In a way similar to what is illustrated in FIG. **1** and described with reference to said figure, the energy harvesting system **10** comprises the transducer **2** and the scavenging interface **4**, electrically coupled to one another in a way in itself known.

[0037] The energy harvesting system **10** further comprises: a first storage element **12**, for example one or more capacitors; a second storage element **16**, for example one or more capacitors; a switch **14**, connected between the first storage element **12** and the second storage element **16**, which can be operated for connecting the first and second storage elements **12**, **16** to one another; and the DC-DC converter **6**, electrically coupled to the second storage element **16** and configured for supplying one or more loads **18***a* . . . **18***n* connected to respective outputs **6***a* . . . **6***n* of the DC-DC converter **6**.

[0038] In greater detail, as illustrated in FIG. **4**, the scavenging interface **4** comprises, according to one embodiment, a rectifier **20**, for example comprising diodes **21** connected to one another to form a Graetz-bridge structure **22**. The rectifier **20** has the function of receiving at input an AC signal (for example, a voltage signal) generated by the transducer **2** and supplying at output a corresponding DC signal (once again, a voltage signal). It is evident that the rectifier **20** is not necessary in the case where the transducer **2** is configured for generating at output a DC signal (in particular, a voltage signal) V_{TRANSD}.

[0039] The input terminals of the bridge structure **22** are connected to respective output terminals of the transducer **2** so as to be biased at the input voltage V_{TRANSD} generated at output by the transducer **2**. The output terminals of the bridge structure **22** are, instead, connected between a ground reference terminal GND, at reference voltage V_{REF}, and a biasing terminal **24**, at voltage V_{OUT_INT}. The first storage element **12** is connected between the biasing terminal **24** and the ground reference terminal GND, and, in use, is charged to a voltage $V_{OUT\_NT}-V_{REF}$. For example, the voltage V_{REF} is 0 V. The voltage V_{REF} can, however, assume values other than 0 V, for example be in a neighborhood of 0 V, or assume other values still, higher or lower than of 0 V, indifferently.

[0040] The switch **14** is connected between the biasing terminal **24** and an intermediate terminal **26**. The second storage element **16** is connected between the ground reference terminal GND and the intermediate terminal **26**. In this way, in use, the switch **14** can be operated for coupling the second storage element **16** with the biasing terminal **24**, providing ideally a connection in parallel between the first and second storage elements **12**, **16** and, alternately, uncoupling the second storage element **16** from the biasing terminal **24** insulating electrically the first storage element **12** from the second storage element **16**. The switch **14** is controlled in opening and closing by an appropriate control logic **28**, which will be described more fully in what follows.

[0041] In use, the voltage V_{OUT_INT} generated at output by the scavenging interface **4** is stored in the first storage element **12**. In the case where the switch **14** is open, there is no transfer of charge from the first storage element **12** to the second storage element **16** and the DC-DC converter **6**. The switch **14** can be driven in closing for the time necessary to charge the second storage element **16**, by transfer of charge from the first storage element **12**. Once a desired state of charge of the second storage element **16** has been reached, the switch **14** is opened, insulating the first storage element **12** from the second storage element **16**.

[0042] The first storage element **12** is configured for storing a high electrical charge. In particular, the storage element **12** is an element of a capacitive type having a capacitance C_1 of between 10 μF and 100 μF, for example equal to 50 μF. The second storage element **16** is also of a capacitive type, having a capacitance C_2 of between 1 μF and 20 μF, for example equal to 10 μF. The second storage element **16** is moreover configured in such a way that the voltage that is set up between its conduction terminals does not exceed the range of voltages allowed at input by the DC-DC converter **6** used. In this way, it is possible to use DC-DC converters **6** of a known type, designed without particular constraints of input dynamics deriving from the specific technical application.

[0043] If V_L is the lower limit of the range of voltages allowed at input by the DC-DC converter, and V_H is the upper limit of the range of voltages allowed at input by the DC-DC converter, the condition that brings about opening of the switch **14** is given by $V_{IN\_CONV}>V_H$, whereas the condition that brings about closing of the switch **14** is given by $V_{IN\_CONV}<V_L$. Hence, in use, we find that $V_L<V_{IN\_CONV}<V_H$. Said condition is ensured, in use, by the logic **28**, which implements, for example, a hysteretic algorithm such as to satisfy the aforesaid condition for the voltage V_{IN_CONV}.

[0044] FIG. **5** shows a portion of the energy harvesting system **10** during an operating step in which the switch **14** is open, in particular during a step of charging of the first storage element **12** via the energy supplied by the transducer **2** and of simultaneous supply of the DC-DC converter **6** by means of the second storage element **16**. The DC-DC converter **6** is supplied at input by the charge stored in the second storage element **16**, which consequently, during the step according to FIG. **5**, decreases. The first storage element **12** is electrically uncoupled from the load **18***a* . . . **18***n* and receives at input the voltage V_{TRANSD} appropriately rectified by the scavenging interface **4** (and reduced by a factor depending upon the efficiency η_{TRANSD} of the scavenging interface **4**). The first storage element **12** is hence charged.

[0045] With reference to what has been described in regard to FIG. **5**, it is evident that the supply of the DC-DC converter **6** is possible only if the second storage element **16** has been previously pre-charged. In an initial step of start-up of the energy harvesting system **10**, the operating step of FIG. **5** comprises the step of charging both the first and the second storage elements **12**, **16**, in a way similar to what is described in what follows with reference to FIG. **6**.

[0046] FIG. **6** shows a portion of the energy harvesting system **10** during an operating step in which the switch **14** is closed. Said operating condition is achieved when the voltage V_{IN_CONV} across the second storage element **16** drops below the limit value V_L and in the start-up step when both the first and the second storage elements **12**, **16** are discharged. In this case, the logic **28** controls the switch **14** in closing. The first and second storage elements **12**, **16** are hence electrically coupled to one another via the connection provided by the switch **14** closed (ideally, considering a switch **14** with zero internal resistance, they are connected in parallel to one another), and there is a transfer of charge between the first and second storage elements **12**, **16**. In particular, the second storage element is charged by means of the charge stored in the first storage element **12**. Consequently, in the absence of supply by the transducer **2** (via the scavenging interface **4**), the voltage V_{OUT_INT} drops and the voltage V_{IN_CONV} increases up to the value V_H (provided that, of course, the voltage V_{OUT_INT} is sufficiently high as to enable the voltage V_{IN_CONV} to reach the value V_H). When the value $V_{IN\_CONV}=V_H$ is reached, the logic **28** controls the switch **14** in opening, and flow returns to the condition of FIG. **5**.

[0047] FIG. **7** is a schematic illustration of the control logic **28**, configured for controlling the switch **14** in opening and closing, according to one embodiment of the present invention.

[0048] The control logic **28** comprises: a first resistor **32** and a second resistor **34**, connected between the intermediate terminal **26** and the ground reference terminal GND; a comparator **36**, including a first input terminal configured for receiving a reference signal V_R at input, a second input terminal connected between the first and second resistors **32**, **34** for receiving a partition signal V_p proportional to the signal V_{IN_CONV}, and an output terminal for supplying at output a comparison signal V_{COMP} indicating a result of the comparison between the reference signal V_R and the partition signal V_P; a control circuit **38**; and a driving circuit **40**, connected to the control circuit **38**.

[0049] The comparator **36** is a hysteretic comparator, of a known type. The comparator hence receives at input the signal to be monitored (partition signal V_P) and the reference signal V_R, around which it generates, in a known way, the hysteresis. The triggering thresholds are hence $V_H'=V_R+V_{HYST}/2$ and $V_L'=V_R-V_{HYST}/2$ (see also FIG. **8**). Alternatively, the comparator **36** can be without hysteresis. In this case, the comparison signal V_{COMP} varies when the partition signal V_P rises/drops with respect to the threshold value given by the reference signal V_R. A hysteretic comparator is advantageous as compared to a non-hysteretic comparator in so far as it is less subject to undesirable variations of the output signal (comparison signal V_{COMP}) due to electrical noise.

[0050] The control circuit **38** is configured for receiving at input the comparison signal V_{COMP} and, on the basis of the value assumed by the comparison signal V_{COMP}, controlling, via the driving circuit **40**, the switch **14** in opening and closing. The control circuit **38** is, for example, a microprocessor circuit configured for carrying out the aforementioned step of checking on the comparison signal V_{COMP}. Furthermore, the control circuit **38** and the driving circuit **40** can be built in integrated form as a single control and driving circuit.

[0051] The switch **14** is, for example, a MOSFET of a P type, having a first conduction terminal (source terminal), connected to the biasing terminal **24**, a second conduction terminal (drain terminal), connected to the intermediate terminal **26**, and a control terminal (gate terminal). In this case, the switch **14** is of a type designed to sustain high voltages between its source and drain terminals (e.g., drift MOS, DMOS, etc.). The diode **41** must be connected as illustrated in FIG. **7** in order to prevent conduction when the switch **14** is open.

[0052] In detail, the diode **41** is connected between the source terminal S and the drain terminal D of the switch **14**, in antiparallel configuration (with respect to the normal direction of flow of the current through the switch **14**). As is known, a characteristic of a MOSFET is that of displaying, under certain operating conditions, the electrical properties of a diode (parasitic diode). Said diode is electrically set (integrated) between the source and drain terminals of the MOSFET. In other words, the switch **14** can present the electrical behavior of a diode, in which the cathode of the diode corresponds to the source terminal and the anode to the drain terminal. The diode **41** is hence the diode integrated in the MOSFET that forms the switch **14**.

[0053] If technologies different from MOSFET technology are used for the switch **14**, the diode **41** may not be present.

[0054] The driving circuit **40** is connected to the gate terminal of the switch **14** and is configured for biasing appropriately the gate terminal of the switch **14** in order to drive the transistor in conduction or inhibition. Said circuit is in effect a level shifter capable of converting the signal (typically at low voltage) produced by the control logic **38** into a CMOS signal referenced to the terminal **24** (source of the switch **14**). By so doing it is possible to generate a correct driving signal of the switch **14** without jeopardizing operation thereof and without damaging the gate oxide thereof.

[0055] The value of resistance of the resistors **32** and **34** is chosen as high as possible according to the area on silicon available so as to guarantee the lowest current absorption at the node **26**, and so as to maximize the overall efficiency of the system **10**. The ratio between the resistors **32** and **34** is chosen so as to be able to compare the voltage at the node **26** with the low-voltage reference V_R normally generated by a bandgap circuit.

[0056] The comparator **36** is a hysteretic comparator, of a type in itself known. As illustrated schematically in FIG. **8**, the comparator **36** is provided with two different triggering thresholds: a lower threshold (positioned at a value V_L' proportional to V_L) for falling-edge values of the signal V_P applied at input to the comparator **36**, and an upper threshold (positioned at a value V_H' proportional to V_H) for rising-edge values of the signal V_P applied at input to the comparator **36**. For example, $V_L'=3$ V and $V_H'=20$ V.

[0057] The output V_{COMP} of the comparator **36** assumes two values, indicated in FIG. **8** as V_{COMP}^{+} and V_{COMP}^{-}. FIG. **8** exemplifies a comparator **36** with hysteresis around the value of the reference V_R.

[0058] In use, during charging of the second storage element **16**, the output of the comparator **36** is at the value V_{COMP}^{-}; the switch **14** is driven into a closed state by the control circuit **38** and by the driving circuit **40**; and the voltage V_{IN_CONV} across the second storage element **16** increases until it reaches the value V_H. When the voltage V_{IN_CONV} reaches a value equal to V_H (i.e., the voltage V_P reaches a value equal to V_H'), the output V_{COMP} of the comparator **36** switches from V_{COMP}^{-} to V_{COMP}^{+}. The control logic **38**, via the driving circuit **40**, opens the switch **14**, and the DC-DC converter **6** is supplied at input exclusively by the second storage element **16**. Then, the voltage V_{IN_CONV} (i.e., the signal V_P) decreases until it reaches the lower limit value V_L (i.e., V_L'); at this point, the output V_{COMP} of the comparator **36** switches to the value V_{COMP}^{-} and the control logic **38**, via the driving circuit **40**, closes the switch **14**, and the second storage element **16** is again charged by means of the charge stored in the first storage element **12**.

[0059] What has been described above is also illustrated in FIGS. **9** and **10**, which show the time plots of the signals V_{TRANSD} (FIG. **9**), and V_{OUT_INT} and V_{IN_CONV} (FIG. **10**). It should here be noted that the signal V_{TRANSD}, supplied at output by the transducer **2**, has an ideal time plot of an impulsive type, with pulses having all the same amplitude and the same frequency (they are uniform in time with respect to one another). The signal V_{OUT_INT} is defined on the basis of the ideal signal V_{TRANSD}. Each pulse of the signal V_{TRANSD} of the transducer **2** generates an increase in the signal V_{OUT_INT}, which assumes a steplike local profile. A real signal source V_{TRANSD} is typically of a discontinuous type, with pulses having amplitudes different from one another and random onset frequency. A source of this type will cause a corresponding variation of the profile of increase of the signal V_{OUT_INT}.

[0060] In an initial step of start-up of the energy harvesting system **10** (not illustrated in FIG. **10**), the voltage present across the first storage element **12** is lower than the value V_L. The switch **14** is closed and the transducer **2** supplies energy to the first and second storage elements **12**, **16**, charging them (time interval preceding time T_1). Then, when the voltage across the first and second storage elements **12**, **16** reaches the limit value of V_H (time t_1), the switch **14** is opened. The voltage V_{IN_CONV} across the second storage element **16** starts to decrease, whilst the voltage V_{OUT_INT} across the first storage element **12** continues to rise (i.e., the process for charging the first storage element **12** continues).

[0061] Of course, what has been illustrated in FIGS. **9** and **10** indicates an optimal operating condition, in which the environmental energy converted by the transducer **2** is sufficiently high and such as to be higher than the energy used for charging the second storage element **16** and used by the electrical load **18***a*, . . . , **18***n*.

[0062] When the voltage V_{IN_CONV} reaches the lower-limit value $V_{IN\_CONV}=V_L$ (time t_2), the switch **14** is closed and there is a transfer of charge from the first storage element **12** to the second storage element **16**. The voltage V_{IN_CONV} increases until the value $V_{IN\_CONV}=V_H$ is reached (time t_3).

[0063] The switch **14** is then opened again, and the step of discharge of the second storage element **16** is resumed.

[0064] As is known, the operation of charge sharing between the first storage element **12** and the second storage element **16** following upon closing of the switch **14** is the cause of a power loss due to the presence of the switch **14** itself. This causes a consequent reduction in the global efficiency of the energy harvesting system **10**. The power P_{CHARGE} useful for charging the second storage element **16** is given by the following Eq. (6):

$$P_{CHARGE}=P_{SCAV}-P_{CONV}-P_{SH} \tag{6}$$

[0065] where P_{SH} is the mean power lost during the operation of charge sharing.

[0066] The mean power P_{SH} is defined as the ratio between the energy lost ΔE and the time interval T_{SH} elapsing between a given charge-sharing event and a subsequent charge-sharing event (for example, with reference to FIG. **10**, the interval t_2-t_4).

[0067] The energy ΔE and the interval T_{SH} are defined by Eqs. (7) and (8):

$$T_{SH}=\frac{0.5\cdot C_2\cdot(V_H^2-V_L^2)}{\eta_{DCDC}\cdot P_{LOAD}} \tag{7}$$

$$\Delta E=0.5\cdot C_2\cdot(V_H-V_L)\cdot\left[2\cdot V_{OUT}+(V_H-V_L)\cdot\left(\frac{C_1-C_2}{C_1}\right)\right] \tag{8}$$

[0068] Consequently, P_{SH} is given by Eq. (9):

$$P_{SH}=\frac{\Delta E}{T_{SH}}=\left[\frac{2\cdot V_{OUT}-\frac{C_2}{C_1}\cdot(V_H-V_L)}{(V_H-V_L)}-1\right]\cdot\eta_{DCDC}\cdot P_{LOAD} \tag{9}$$

[0069] If the charge balancing is positive, the voltage V_{OUT_INT} across the first storage element **12** increases during the cycles T_{SH}; otherwise, it decreases. In order to maximize the value of energy stored in the first storage element **12** (and hence maximize the interval T_{SH}), it is advisable to maximize the threshold value V_H, which in any case must be kept within the input dynamics of the DC-DC converter **6**. It is hence advisable to use DC-DC converters **6** with high input dynamics (in particular, with an upper limit of input dynamics of a value that is as high as possible) so as to enable high threshold values V_H.

[0070] When the interval T_{SH} is maximized, the power dissipated on account of operations of charge sharing is reduced in so far as also the frequency of occurrence of the latter is reduced.

[0071] FIG. **11** shows a vehicle **100** comprising the energy harvesting system **10**, according to one embodiment of the present invention. The vehicle **100** is, in particular, a motor vehicle. It is evident, however, that the energy harvesting system **10** can be used in any vehicle **100** or in systems or apparatuses other than a vehicle. In particular, the energy harvesting system **10** can find application in generic systems in which it is desirable to harvest, store, and use environmental energy, in particular by means of conversion of mechanical energy into electrical energy.

[0072] With reference to FIG. **11**, the vehicle **100** comprises one or more transducers **2** coupled in a known way to a portion of the vehicle **100** that is subject to mechanical stresses and/or vibrations, for converting said mechanical stresses and/or vibrations into electric current.

[0073] The energy harvesting system **10** is connected to one or more electrical loads **18***a* . . . **18***n*. In particular, according to one application of the present invention, the electrical loads **18***a* . . . **18***n* comprise TPM (tire-parameter monitoring) sensors **50** for monitoring parameters of tires **102**. In this case, the TPM sensors **50** are coupled to an internal portion of the tires **102** of the vehicle **100**. Likewise, also the transducers **2** (for example, of an electromagnetic or piezoelectric type) are coupled to an internal portion of the tire **102**. The stress on of the transducers **2** when the vehicle **100** is travelling causes the production of a current/voltage electrical signal at output from the transducer **2** by means of conversion of the mechanical energy into electrical energy. The electrical energy thus produced is stored, as described previously, in the first storage element **12**, and supplied, when necessary, to the second storage element **16**, which in turn makes it available for the DC-DC converter **6** to which two or more TPM sensors **50** are connected. Thanks to the fact that the first storage element **12** has a capacitance greater than that of the second storage element **16**, which is not constrained by parameters of design of the DC-DC converter **6**, when the vehicle **100** stops it is in any case possible to supply the TPM sensors **50** using the electrical energy stored in the first storage element **12**. By appropriately sizing the first storage element **12** it is possible to increase or reduce as desired the range of autonomy of supply of the TPM sensors **50** when the vehicle is stationary.

[0074] According to one embodiment of the present invention, the energy harvesting system **10**, comprising one or more transducers, and the TPM sensors, are glued inside one or more tires **102**.

[0075] The impact of the tire **102** on the ground during motion of the vehicle **100** enables production of electrical energy.

[0076] As an alternative to what is illustrated in FIG. **11**, the energy harvesting system **10** can be set in any other portion of the vehicle **100**, and/or used for supplying an electrical load other than or additional to the TPM sensors **50**.

[0077] Another possible application of the energy harvesting system **10** is the generation of electrical energy by exploiting the mechanical energy produced by an individual when he is walking or running. In this case, the energy harvesting system **10** is located inside the shoes of said individual (for example, inside the sole). In systems aimed at fitness, where it is particularly interesting to count the steps, it is useful to recover energy from the vibrations induced by walking/running to be able to supply without the use of a battery acceleration sensors and/or RFID transmitters capable of communicating with cellphones, devices for playing music, or with any other apparatus involved in information on the steps performed.

[0078] From an examination of the characteristics of the invention obtained according to the present disclosure the advantages that it affords are evident.

[0079] In particular, the system according to the present invention has a high efficiency and autonomy irrespective of external conditions, such as possible energy peaks acquired by the transducer or a temporary absence of energy. In fact, the first storage element **12**, which has a high capacity for storing energy, has the function of reserving energy in situations of temporary absence of energy; the switch **14** is configured for uncoupling, when necessary, the first storage element **12** from the DC-DC converter **6** and from the load of the latter, rendering operativeness of the energy harvesting system **10** independent of any particular temporary conditions external to the system itself.

[0080] Furthermore, the architecture proposed for the energy harvesting system **10** enables use of standard electronic components, i.e., ones not developed purposely for this application (for example, the DC-DC converter **6** does not need to be designed to satisfy particular conditions of input dynamics), which means a considerable economic saving and saving in terms of overall efficiency.

[0081] Finally, the hysteretic control of the switch **14** enables storage of a high electrical charge in the capacitor **16** without jeopardizing the functionality of the DC-DC converter **6** and without requiring any modification thereof.

[0082] Finally, it is clear that modifications and variations may be made to what has been described and illustrated herein, without thereby departing from the sphere of protection of the present invention, as defined in the annexed claims.

[0083] For example, there may be present a plurality of transducers **2**, all of the same type or of a type different from one another, indifferently. For example, the transducer/transducers can be chosen in the group comprising: electrochemical transducers (designed to convert chemical energy into an electrical signal), electromechanical transducers (designed to convert mechanical energy into an electrical signal), electroacoustic transducers (designed to convert variations of pressure into an electrical signal), electromagnetic transducers (designed to convert a magnetic field into an electrical signal), photoelectric transducers (designed to convert light energy into an electrical signal), electrostatic transducers, or thermoelectrical transducers.

What is claimed is:

1. A system, comprising:

a transducer configured to convert energy coming from an external energy source into an electrical signal;

a first storage element coupled to an output of the transducer and configured to receive said electrical signal and store electrical energy,

a second storage element configured to store electrical energy; and

a switch coupled between the first and the second electrical-energy storage elements and operable to electrically couple the first and second storage elements to one another and, alternatively, uncouple the first and second storage elements from one another.

2. The system according to claim **1**, wherein the first storage element comprises a first conduction terminal and a second conduction terminal, wherein the second storage element comprises a first conduction terminal and a second conduction terminal, wherein the second conduction terminals of the first and second storage elements are connected to a common reference terminal, wherein the first conduction terminals of the first and second storage elements are connected to respective terminals of the switch in such a way that, when the switch is operated to electrically couple the first and second storage elements, the respective first conduction terminals of the first and second storage elements are coupled to one another.

3. The system according to claim **1**, wherein said first storage element has an electrical energy storage capacity greater than that of said second storage element.

4. The system according to claim **1**, further comprising control logic having an output coupled to control said switch, said control logic configured to close the switch when the electrical energy stored in the second storage element is lower than a first threshold value, and further configured to open the switch when the electrical energy stored in the second storage element is higher than a second threshold value.

5. The system according to claim **4**, wherein the control logic comprises:

a comparator with hysteresis configured to receive on a first input a first comparison signal indicative of electrical energy stored in the second storage element, and receive on a second input a second predefined comparison signal, and supply at the output a third comparison signal indicative of a result of a comparison between the first and second comparison signals;

a control and driving circuit configured to receive the third comparison signal and, on the basis of the third comparison signal, control opening or closing of the switch.

6. The system according to claim **1**, wherein the first storage element includes a capacitor and wherein the electrical signal generated by the transducer is an AC voltage signal, the system further comprising a scavenging interface having an input connected to the transducer and an output connected to the first storage element, the scavenging interface configured to receive at an input the electrical signal and generate at an output a first intermediate DC signal to charge the first storage element.

7. The system according to claim **1**, further comprising a DC-DC converter coupled between the second storage element and an electrical load, said DC-DC converter configured to receive a second intermediate signal depending upon the electrical energy stored in the second storage element and supply said electrical load via said second intermediate signal.

8. The system according to claim **7**, wherein the second storage element includes a capacitor having biasing terminals, the DC-DC converter further configured to accept a voltage signal having a value lower than a maximum value, and the second storage element being configured in such a way that the difference of potential that, in use, is set up across its terminals has a value lower than said maximum value.

9. The system according to claim **1**, comprising an energy-harvesting system for use in harvesting energy from movement of a support.

10. The system according to claim **9**, wherein said support is a means of transport.

11. The system according to claim **9**, wherein said transducer is chosen in the group comprising: electrochemical transducer, electromechanical transducer, electroacoustic transducer, electromagnetic transducer, photoelectric transducer, electrostatic transducer, thermoelectrical transducer.

12. An energy-harvesting method, comprising:

converting, by a transducer, energy from an external energy source into electrical energy to generate an electrical signal;

storing said electrical energy in a first storage element;

coupling the first storage element to a second storage element so as to store, in the second storage element, at least a portion of the electrical energy stored in the first storage element;

alternatively, uncoupling the first storage element from the second storage element so as to insulate the first storage element from the second storage element; and

during uncoupling, supplying an electrical load with electrical energy stored in the second storage element.

13. The method according to claim **12**, further comprising monitoring the electrical energy stored in the second storage element, wherein a coupling of the first storage element to the second storage element is carried out when the electrical energy stored in the second storage element falls lower than a first threshold value, and wherein uncoupling of the first storage element from the second storage element is carried out when the electrical energy stored in the second storage element rises higher than a second threshold value.

14. The method according to claim **12**, wherein monitoring:

supplying, on a first input of a comparator with hysteresis, a first comparison signal indicative of the electrical energy stored in the second storage element;

supplying, on a second input of the comparator with hysteresis, a second predefined comparison signal; and

generating, at an output of the comparator with hysteresis, a third comparison signal indicative of a result of a comparison between the first and second comparison signals,

wherein said coupling and uncoupling actions are performed on the basis of a value assumed by the third comparison signal.

15. The method according to claim **12**, wherein the first storage element includes a capacitor and wherein the electrical signal generated by the transducer is an AC voltage signal, the method further comprising:

rectifying the electrical signal generated by the transducer to generate a first intermediate DC signal; and

charging the first storage element with the first intermediate signal.

16. A circuit, comprising:

a first capacitor having a first terminal coupled to a reference voltage node and a second terminal coupled to an input node and configured to store first electrical energy;

a second capacitor having a third terminal coupled to said reference voltage node and a fourth terminal and configured to store second electrical energy;

a switching circuit having an input terminal coupled to the first terminal and an output terminal coupled to the fourth terminal;

a hysteresis comparator coupled to sense the second electrical energy at the fourth terminal and configured to close the switching circuit in response to sensed second electrical energy falling below a first threshold and open the switching circuit in response to sensed electrical energy rising above a second threshold.

17. The circuit of claim **16**, further comprising a rectifying circuit configured to rectify an AC signal to generate an DC signal at said input node.

18. The circuit of claim **17**, further comprising a transducer circuit configured to convert non-electrical energy into said AC signal.

19. The circuit of claim **18**, further comprising a DC-DC converter circuit having an input coupled to said fourth terminal and configured to supply power to a load from the second electrical energy.

20. The circuit of claim **16**, wherein said first capacitor has an electrical energy storage capacity greater than that of said second capacitor.

* * * * *

US 20150102676A1

(19) **United States**
(12) **Patent Application Publication**
Dinwiddie et al.

(10) **Pub. No.: US 2015/0102676 A1**
(43) **Pub. Date: Apr. 16, 2015**

(54) **METHOD AND APPARATUS FOR EXTRACTING AND CONVEYING ELECTRICAL ENERGY FROM THE EARTH'S IONOSPHERE CAVITY**

(71) Applicant: **Earth Energies, Inc.**, Johns Creek, GA (US)

(72) Inventors: **John Dinwiddie**, Cary, NC (US); **Terry L. Wright**, Suwanee, GA (US)

(21) Appl. No.: **14/509,846**

(22) Filed: **Oct. 8, 2014**

Related U.S. Application Data

(60) Provisional application No. 61/889,894, filed on Oct. 11, 2013.

Publication Classification

(51) **Int. Cl.**
H01F 38/14 (2006.01)

(52) **U.S. Cl.**
CPC ***H01F 38/14*** (2013.01); *H01F 2038/146* (2013.01)

(57) **ABSTRACT**

The system and apparatus of one or more embodiments of the present invention extracts, conditions, and conveys electric power from the earth ionosphere cavity through the integrated and collaborative operation of the system and apparatus consisting of a capacitively-coupled insulated elevated terminal (coupled capacitor upper plate), an evacuated spark gap, an integrated step-down transformer and resonant capacitor, and a ground terminal (coupled capacitor lower plate). The architecture governing exemplary embodiments of the system and apparatus of the present invention emulates the natural architecture governing the interaction of living trees with the electrical energy resident in the earth ionosphere cavity. The implementation of such exemplary embodiments of the present invention utilizes standard and customized components appropriate for their function within the system and apparatus.

The extracted electric power from the earth ionosphere cavity manifests in the form of broadband electromagnetic waves in the 0 to 200 Hz frequency range. Electric energy from these waves produce magnetic fields inside the integrated step-down transformer which are added together by the primary coil of the integrated step-down transformer, and delivered as 60 Hz 120/240 VAC to an electric load via the secondary coil of the integrated step-down transformer resonating at 60 Hz due to the influence of the integrated resonant capacitor.

The system and apparatus of exemplary embodiments of the present invention extracts, conditions, and conveys ionosphere cavity-resident electric power in alternating current and direct current realms.


10
E-field
Insulated
.1 – 14 Hz AC ULF (Lightning Generated) 22
Tesla coil or other biasing will accelerate recharge rate (fast recharge)
Instantaneous electrical current drawn to spark gap; Inhibited from CUP as voltage rises on transformer side and extinguishes spark; CUP begins recharging
Capacitor Reaches Threshold & Fires (Slow Discharge)
Capacitor Upper Plate (CUP) (Elevated Terminal)
12
Develops High Voltage Charge Relative to Ground Voltage
Hoping to replace with solid state relay
Evacuated Spark Gap
Spark Triggers
Step-Down Transformers 28
Parallel Resonant Transformer Primary & Secondary Coils 16
Capacitor @ 60 Hz 18
Capacitor drain rate, spark gap extinguishing from voltage rise, integrated resonant transformer/ capacitor, and biasing will be balanced to suit application
Electric Load (home)
*5 kW, 60 Hz, 120/240 VAC
Ultra High Instantaneous Current
14
Capacitor Lower Plate (CLP) (Ground Terminal)
Broadband ULF Current (pump)
Resonant Transformer & Capacitor Continue to Ring @ 60 Hz (16 & 18)
See Drawing 2 (44, 46, 48,58, 54)
Ground
Earth
See Drawing 2 (52)
*5 kW preferred embodiment
100 kW alternative embodiment
35,000 kW alternative embodiment
COPYRIGHT 2013
EARTH ENERGIES, INC.
PROPRIETARY & CONFIDENTIAL
EARTH ENERGIES, INC.


10
E-field
Insulated
.1 ~ 14 Hz AC ULF
(Lightning
Generated)
22
Tesla coil or other
biasing will
accelerate
recharge rate
(fast recharge)
Instantaneous electrical
current drawn to
spark gap; inhibited from
CUP as voltage rises
on transformer side
and extinguishes spark;
CUP begins recharging
Capacitor Upper Plate (CUP)
(Elevated Terminal)
12
Capacitor Reaches
Threshold & Fires
(Slow Discharge)
Develops High
Voltage Charge
Relative to
Ground Voltage
Hoping to
replace with
solid state relay
Evacuated
Spark Gap
Spark
Triggers
Step-Down
Transformers
28
Parallel Resonant
Transformer
Primary &
Secondary Coils
15
Capacitor @
60 Hz
18
Capacitor drain rate, spark gap
extinguishing from
voltage rise, integrated
resonant transformer/
capacitor, and biasing will be
balanced to suit application
Electric
Load
(home)
*5 kW, 60 Hz, 120/240 VAC
Ultra High Instantaneous Current
18
Capacitor Lower Plate (CLP)
(Ground Terminal)
Broadband
ULF Current
(pump)
Resonant Transformer &
Capacitor Continue to
Ring @ 60 Hz (16 & 18)
See Drawing 2 (44,
46, 48,58, 54)
Ground
Earth
See Drawing 2 (52)
*5 kW preferred embodiment
300 kW alternative embodiment
36,000 kW alternative embodiment
Copyright 2013
Earth Energies, Inc.
Proprietary & Confidential
Earth Energies, Inc.

FIG. 1


As Inserted
42 (4)
56
40
44
After Deployed
Bezel Anchor Slots (4)
50
Spool View Inside Bezel Blow-up
Bezel Ground Wire Escape Portals Holes with Wire end exposed (X)
54
48
46
Cut-away View (Installed)
Bezel Threads
58
Bezel External View
52
(Y)
Ground Terminal Optimizer Apparatus for Lower Coupled Capacitor Plate (Ground Terminal)
Copyright 2013
Earth Energies, Inc.
Proprietary & Confidential
Earth Energies, Inc.

FIG. 2

METHOD AND APPARATUS FOR EXTRACTING AND CONVEYING ELECTRICAL ENERGY FROM THE EARTH'S IONOSPHERE CAVITY

[0001] This application claims benefit of U.S. Provisional Application No. 61/889894, filed 11 Oct. 2013, titled, "Method and Apparatus for Extracting and Conveying Electrical Energy From the Earth's Ionosphere Cavity," the disclosure of which is incorporated herein by reference in its entirety.

BACKGROUND OF THE INVENTION

[0002] A portion of the disclosure of this patent document contains material which is subject to copyright protection. The copyright owner has no objection to the facsimile reproduction by any-one of the patent document or the patent disclosure, as it appears in the Patent and Trademark Office patent file or records, but otherwise reserves all copyright whatsoever.

[0003] The invention is an apparatus and methodology for extracting electric power manifesting as a broadband collection of electric field oscillations in the 0 to 200 Hz frequency range within the Earth's ionosphere cavity, through the use of an elevated biased hemispherical or other curved surface capacitor coupling the ionosphere cavity and Earth, and then conveying this electrical energy at the proper frequency, amperage, and voltage to existing homes and buildings where it is delivered for consumption over existing home or building wiring.

DESCRIPTION OF THE RELATED ART

[0004] The current state of the art in this field is focused on the bending of radio frequency waves in the Earth's ionosphere cavity for the purpose of distorting (through reflection) the resident cavity's magnetic field to physically direct the stimulating electrical energy to targeted locations within the Earth's ionosphere cavity and/or coordinates on the Earth's surface at specific energy levels appropriate to specific applications. The regenerative feedback was done by Sutton's active antenna.

[0005] Nikola Tesla attempted to transmit wireless power in the "natural medium"; however, Tesla bad no description of a device to receive natural oscillations as described in the present disclosure.

[0006] There is no known prior art in the field of electric energy extraction from the ionosphere cavity and conveyance to other terminals within the cavity for delivery of usable electric power.

SUMMARY OF THE INVENTION

[0007] In one exemplary embodiment of the present invention, a properly-scaled electric power extraction/conveyance apparatus is installed at a typical consumer residential home to deliver 60 Hz 120/240 VAC electric power, sufficient to convey the equivalent of 5 kW of continuous electricity, to the home's existing electric service entry component to power electrical appliances in the home over existing home electric wiring.

[0008] In another exemplary embodiment of the present invention, a properly-scaled electric power extraction/conveyance apparatus is installed at an appropriate location within an industrial park or neighborhood to deliver 60 Hz 120/240 V AC electric power, sufficient to convey the equivalent of 300 kW of continuous electricity, to the service entry components of industrial buildings or neighborhood homes to power electrical devices and appliances over existing building or home electric wiring.

[0009] Alternative exemplary embodiments of the present invention will extract direct current electric power from the Earth ionosphere cavity, generated by the earth's rotating magnetosphere, and convey in the form of conditioned direct current to direct current load sources, or convert to alternating current and convey in the form of conditioned alternating current to alternating current load sources.

BRIEF DESCRIPTION OF THE DRAWINGS

[0010] A disclosure embodiments of the present invention, is set forth more particularly in the remainder of the specification, which makes reference to the accompanying figures, in which:

[0011] FIG. **1** provides an example of an electric power extraction and conveyance apparatus for one residential-scale embodiment of the present invention. Certain additional example embodiments of the present invention utilize similar fundamental technologies, but differ in the scale (size) of the components and characteristics of the electricity conveyed for consumption; and

[0012] FIG. **2** is a schematic illustration of ground terminals for use with embodiments of the present invention.

DETAILED DESCRIPTION

[0013] Applicant has discovered that trees extract and use electric power from the Earth ionosphere cavity. The present invention emulates the architecture of electric power extraction and usage methodology inherent in the natural operation of living trees, but uses standard and customized components, common in the field, for its implementation. The natural electric power extraction and use of electric power by trees leverages the shape and physical composition of trees as instances of large electrical capacitors coupled to the ionosphere cavity. The canopy of trees (upper limbs and leaf structures) emulates the upper plates of a coupled capacitor, the trunks of trees emulate a combined dielectric and resonant transformer/capacitor, and the root systems of trees emulate ground terminals (lower coupled capacitor plates). The extraction of electric power from the ionosphere cavity by trees is in the form of ultra-low frequency broadband waves (oscillations) in the frequency range of 0.1 to 14 Hertz (ULF). Inherent tree physical composition and control structure (i.e., DNA/RNA) govern the use of the extracted electric power to accomplish tree growth, seasonal metabolic adjustments, and reproductive processes. Any excess extracted electric power by trees is returned to the ionosphere cavity. The present invention is an exemplary instance of this same natural architecture using standard and customized components that facilitate extraction and conveyance of ionosphere cavity-resident broadband electric power at useful scales sufficient to provide continuous electrical power for electrical devices used by people.

[0014] One preferred exemplary embodiment of the present invention is in the form shown in Drawing **1** above and will deliver continuous 60 Hz 120/240 V AC electric power to consumer residences (and other structures with similar electricity conditioning and consumption requirements) equivalent to electric power capacity of 5 kilowatts.

[0015] A secondary exemplary embodiment of the present invention is also in the form shown in FIG. **1**, appropriately scaled for larger electrical power demands and related conveyance capacity, and will deliver continuous 60 Hz 120/240 V AC electric power to larger buildings or electrical distribution facilities for commercial office parks with electric power capacity of 300 kilowatts.

[0016] A third exemplary embodiment of the present invention is also in the form shown in FIG. **1**, appropriately scaled for larger electrical power capacity, and will deliver continuous 60 Hz 120/240 VAC electric power to utility substations with electric power capacity of 30,000 kilowatts (or higher).

[0017] The following system, power sources, and component descriptions provide additional details of the present invention in various embodiments.

[0018] Earth's ionosphere cavity (**10**) is a reservoir of continuously-generated electrical energy (E-Field) in both direct current (DC) and alternating current (AC) realms. The DC electric energy is created by the constant rotation of the Earth's magnetosphere exposed to the solar wind. Earth's perpetually moving magnetic fields create the DC electric power in the ionosphere cavity E-Field per the equations in James Clerk Maxwell's fundamental theory of electromagnetism. AC electrical energy in the ionosphere cavity is generated from the persistent E-Field disturbances (i. e., oscillations) caused by lightning discharges. The present invention includes the direct extraction of AC electric power from the ionosphere cavity, and the direct extraction of DC electric power from the ionosphere cavity which is converted to AC electric power before conveyance. Optional operational configurations of the present invention will also enable conveyance of extracted DC electric power for potential scenarios where the conveyance of conditioned DC electricity is required.

[0019] Electric-field oscillations (**22**) are induced by lightning and encapsulated in the earth-ionosphere cavity, creating a continuous source of renewable electrical energy. The frequency of lightning occurrences in the ionosphere cavity averages thirty (30) strikes per second, with each strike representing approximately one (1) terawatt (TW) of instantaneous energy. Assuming an average energy dissipation rate for each lightning strike of fifteen (15) microseconds (μsec), i. e., the time involved for one (1) terawatt of instantaneous energy to dissipate to zero (0) energy, these lightning-induced electric field oscillations are sufficient to provide 4,500 times the entire electric energy consumption on planet Earth at the projected consumption rate for the year 2100 (55.3 TWh annually). Lightning-induced E-Field oscillations vary between 0.1 and 14 Hertz with wavelengths exceeding the practicality of an electromagnetic antenna for collecting the energy. The present invention utilizes capacitive coupling to overcome this obstacle.

[0020] An insulated upper capacitor plate (terminal) (12) elevated above the influence of the ground floor collects E-Field oscillations from the ionosphere cavity. This insulated elevated terminal, capacitively-coupled to the E-Field bounded by the earth-ionosphere cavity, is arranged in a surface of large radii of curvature, supporting maximum surface connection to the E-Field without leaking the high voltage charge applied to the elevated terminal. The capacitance and resistance of the elevated terminal are responsive to the reception of broadband electric-field frequencies in the 0 to 200 hertz range. The elevated terminal is subject to high voltage alternating current biasing used to collect electric-field oscillations generated by lightning impulses in the earth-ionosphere cavity.

[0021] An evacuated spark gap (**24**) connected to the elevated terminal (**12**) prevents electrical discharge occurring between the elevated terminal and the ionosphere cavity. As the high voltage alternating current approaches peak voltage the spark gap energizes and a large voltage is applied to the step-down transformer primary coil (**16**). The high voltage pumps high current from the ground terminal (**14**, **26**) converting the electric-field to a magnetic field within the transformer (**16**). The step-down transformer is connected to a 60 hertz resonant capacitor (**18**), the secondary side of the transformer resonating at 60 hertz will supply a 60 hertz 120/240 VAC power to the load. Filter circuits will condition the power. The evacuated spark gap function may be accomplished by solid state circuitry in the implementation of the present invention.

[0022] The resonant transformer (**16**) is integrated with a parallel resonant capacitor across the transformer where the integrated combination resonates at 60 hertz supplying power to the electricity consuming structure (home or business). Various step-down transformers (**28**) are utilized to condition the conveyed electricity to accommodate the requirements of the receiving station for various embodiments of the present invention.

[0023] Ground (**26**) is the source of electric current for the present invention. A ground terminal, connected to the soil, is arranged in a surface of large radii of curvature to permit instantaneous sourcing of high currents from earth ground without temperature and voltage rise inhibiting the ground terminal collection of current. The capacitance and resistance of the ground terminal to earth is minimized to promote on demand current sourcing. Drawing **2** illustrates an exemplary apparatus of the present invention that optimizes ground connection quality by maximizing the penetration extent and resulting surface area of the ground terminal's extension into the soil.

[0024] Step-down transformers (**28**) are scaled to transform the electrical current and voltage into structured and conditioned electricity that is compatible with the electric power needs of the load sources for various embodiments of the present invention.

[0025] A mechanical nut (**40**) solidly attached to shaft **44** to facilitate extension, when turned, of large gauge copper wire extrusions (**46**).

[0026] A downward pointed anchor flat shaft (**42**) attached to the bezel **50** via a T-slot in bezel.

[0027] A copper (or other highly-conductive metal) spool base (**44**) sourcing "X" independently attached large gauge pointed copper wires (**46**) of length "Y", where "X" is equal to the number of escape portals in bezel (**50**), and "Y" is the length determined to yield optimum surface area of wires of type **46** for high quality connectivity to soil. The spool can freely rotate inside the bezel (**48**) and emulates the primary root structure of a living tree.

[0028] Sharpened large gauge (reinforced) copper wires (**46**), quantity "X", of length "Y" emulating the root structure of living trees.

[0029] Threaded bezel (spool-housing sleeve) (**48**) with drilled escape portal holes with end of copper wires (**46**) protruding through holes ½ inch.

[0030] Bezel anchor slots (**50**) of twice the height of anchor flat shafts (**42**) and T-slotted to accommodate anchor flat shafts.

[0031] Extended pointed end (**52**) of inner spool base shaft.

[0032] Escape portals (**54**) in bezel to allow for large gauge copper wire (**46**) extension into soil.

[0033] Connector port (**56**) for connection to ground terminal (**14**) in Drawing **1**.

[0034] Bezel threads (**58**).

[0035] Various embodiments of the present invention will include one or more of the following characteristics in various combinations. These descriptions are provided for purposes of example. Not all of the following characteristics will be required for any given exemplary embodiment.

[0036] Characteristic 1, The form (shape), physical composition, size, insulation, location altitude, discharge capacitive threshold and discharge rate, and the strength of AC or DC biasing applied to the (CUP) upper coupled capacitor plate (**12**: elevated terminal) all form an integrated whole, the purpose of which is to extract and temporarily store DC or AC electric power from the Earth's ionosphere cavity (**10**) at high voltage, and to trigger the energizing of the evacuated spark gap (**24**).

[0037] Characteristic 2, The elevated terminal (**12**) is capacitively coupled to the E-Field (**10**) bounded by the earth ionosphere cavity, and arranged in a surface of large radii of curvature, supporting maximum surface connection to the E-Field without leaking the high voltage charge applied to the elevated terminal (**12**).

[0038] Characteristic 3, The capacitance and resistance of the elevated terminal (**12**) are responsive to the reception of broadband electric-field frequencies in the 0 to 200 hertz range.

[0039] Characteristic 4, The elevated terminal (**12**) is subject to high voltage alternating current biasing used to collect E-Field oscillations generated by lightning impulses in the earth-ionosphere cavity.

[0040] Characteristic 5, An alternative instantiation of elevated terminal (**12**) is subject to high voltage direct current biasing used to collect E-Field direct current generated by the Earth's rotating magnetosphere.

[0041] Characteristic 6, The evacuated spark gap (**24**) may be in the form of a cohesive physical spark ignition or an operational emulation of this function through solid state circuitry.

[0042] Characteristic 7, The evacuated spark gap (**24**) connected to the elevated terminal (**12**) prevents electrical discharge occurring between the elevated terminal and the ionosphere cavity.

[0043] Characteristic 8, The high voltage alternating current from the E-Field, induced into the elevated terminal (**12**), approaches peak voltage and causes the evacuated spark gap (**24**) to energize and a large voltage is applied to the step-down transformer primary coil (**16**).

[0044] Characteristic 9, The high voltage alternating current impulse from the elevated terminal (**12**), which causes the evacuated spark gap (**24**) to energize, manifests as alternating current on broadband frequencies between 0.1 and 200 Hz.

[0045] Characteristic 10, In an alternative instantiation of the elevated terminal (**12**) the stored high voltage direct current, which causes the evacuated spark gap (**24**) to energize, manifests as direct current on broadband frequencies between 0 and 200 Hz.

[0046] Characteristic 11, The high voltage applied to the step-down transformer primary coil (**16**) pumps high current from the ground terminal (**14**), converting the electric-field to a magnetic field within the transformer (**16**).

[0047] Characteristic 12, The high current pumped from the ground terminal (**14**), caused by high voltage applied to the step-down transformer primary coil (**16**), will attempt to normalize the field and extinguish the evacuated spark gap (**24**).

[0048] Characteristic 13, The transformer's (**16**) magnetic field expands in response to the high current electric-field inrush from the ground terminal (**14**).

[0049] Characteristic 14, The primary winding inside the step-down transformer (**16**) will add the energy from each broadband frequency together into a single magnetic field, where it will become a 60 Hz frequency at the secondary winding of the transformer (**16**).

[0050] Characteristic 15, The step-down transformer (**16**) is connected to a 60 Hertz resonant capacitor (**18**).

[0051] Characteristic 16, The secondary (coil) side of the step-down transformer (**16**), resonating at 60 hertz, will supply a 60 hertz 120/240 VAC power to the electric load.

[0052] Characteristic 17, Filter circuits within the step-down transformer will condition the power according to the electric power needs of the electric load.

[0053] Characteristic 18, Electric-field lines exist (within the Earth's ionosphere cavity) that are horizontal to the surface of the Earth and extend to heights above 30,000 feet, with voltage gradients typically 100 Volts per vertical meter.

[0054] Characteristic 19, Lightning impulses create global broadband oscillations in the Earth ionosphere cavity electric-field between 0.1 and 14 Hertz.

[0055] Characteristic 20, Rotation of the Earth's magnetosphere creates global electric field oscillations in the Earth ionosphere cavity that manifest as electromagnetic waves in the 0 to 200 Hertz frequency range.

[0056] Characteristic 21, Global broadband oscillations in the Earth ionosphere cavity electric-field can be used for wireless energy transmission without harm to people, plants, or trees.

[0057] Characteristic 22, A maximum quality ground connection is achieved by expanding the surface area of the ground connection (**48** and **44**) through extension of high-conductor large gauge copper wires (**46**) horizontally through bezel (**48**) escape portals (**54**) along depth of source spool (**44**) and bezel (**48**).

[0058] Characteristic 23, The technique described in Characteristic 22 effectively expands the diameter of the ground source spool (**44**) with regard to quality of ground connection.

[0059] Characteristic 24, Bezel threads (**58**) expand surface area of bezel (**48**) touching earth, enhancing ground connection quality.

[0060] Characteristic 25, Bezel threads (**58**) enhance ground connection quality of bezel (**48**), source spool (**44**), and high conductor large gauge copper wires (**46**) through rotational insertion and resulting friction hold v. other (direct drive) insertion methods which can result in corruption of ground hole integrity caused by imprecise angle and/or vibration during insertion.

[0061] While one or more embodiments of the present invention have been described above, it should be understood that any and all equivalent realizations of the present invention are included within the scope and spirit thereof. Thus, the embodiments presented herein are by way of example only

and are not intended as limitations of the present invention. Therefore, it is contemplated that any and all such embodiments are included in the present invention.

What is claimed is:

1. A power receiver for extracting electrical energy from the earth's electric field, said power receiver comprising:

a resonant transformer connected between a ground terminal disposed below the surface of the earth and an elevated terminal;

impulse generator for generating and applying a high voltage electrical impulse to a primary winding of the resonant transformer to induce current flow from the ground terminal through the primary winding of the transformer; and

a power conversion circuit connected to a secondary winding of the resonant transformer to convert electrical current flowing through the secondary winding to a desired form.

2. The power receiver of claim **1** wherein a resonant frequency of the resonant transformer is below 200 Hz.

3. The power receiver of claim **1** wherein the elevated terminal comprises an upper capacitive plate coupled to the earth's ionosphere cavity.

4. The power receiver of claim **3** wherein the impulse generator comprises:

the upper capacitive plate;

a pair of electrodes separated by a spark gap, said electrodes connected between the upper capacitive plate and the primary winding of the resonant transformer and configured to generate a spark when a voltage difference between the electrodes reaches a predetermined level.

5. The power receiver of claim **1** further comprising a lower capacitive plate coupled to the ground terminal.

6. The power receiver of claim **1** wherein the resonant transformer comprises a capacitor connected in parallel with a primary winding of the resonant transformer.

* * * * *

US006960975B1

(12) United States Patent
Volfson

(10) **Patent No.: US 6,960,975 B1**
(45) **Date of Patent: Nov. 1, 2005**

(54) **SPACE VEHICLE PROPELLED BY THE PRESSURE OF INFLATIONARY VACUUM STATE**

(76) Inventor: **Boris Volfson**, 5707 W. Maple Grove Rd., Apt. 3046, Huntington, IN (US) 46750

(*) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 8 days.

(21) Appl. No.: **11/079,670**

(22) Filed: **Mar. 14, 2005**

Related U.S. Application Data

(63) Continuation of application No. 10/633,778, filed on Aug. 4, 2003, now abandoned.

(51) **Int. Cl.**^{7} **H01F 6/00**; F03H 5/00
(52) **U.S. Cl.** **335/216**; 60/200.1
(58) **Field of Search** 335/216; 60/200.1

(56) **References Cited**

U.S. PATENT DOCUMENTS

3,626,605	A	12/1971	Wallace
3,626,606	A	12/1971	Wallace
3,823,570	A	7/1974	Wallace
5,197,279	A	3/1993	Taylor
6,353,311	B1	3/2002	Brainard et al.

OTHER PUBLICATIONS

M.T. French, "To the Stars by Electromagnetic Propulsion", http://www.mtjf.demon.co.uk/antigravp2.htm#cforce.

Evgeny Podkletnov, "Weak Gravitational Shielding Properties of Composite Bulk $YBa_2Cu_33O_{(7-x)}$ Superconductor Below 70K Under E.M. Field", LANL database number cond-mat/9701074, v. 3, 10 pages, Sep. 16, 1997.

N. LI & D.G. Torr, "Effects of a Gravitomagnetic Field on Pure Superconductors", Physical Review, vol. 43, p. 457, 3 pages, Jan. 15, 1991.

Evgeny Podkletnov, Giovanni Modanese "Impulse Gravity Generator Based on Charged $YBa_2Cu_33O_{7-y}$ Superconductor with Composite Crystal Structure", arXiv.org/physics database, #0108005 vol. 2, 32 pages, 8 figures, Aug. 30, 2001.

S. Kopeikin & E. Fomalont, "General Relativistic Model for Experimental Measurement of the Speed of Propagation of Gravity by VLBI", Proceedings of the 6th European VLBI Network Symposium Jun. 25-28, 2002, Bonn, Germany, 4 pages.

Sean M. Carroll, "The Cosmological Constant", http://pancake.uchicago.edu/~carroll/encyc/, 6 pages.

Chris Y. Taylor and Giovanni Modanese, "Evaluation of an Impulse Gravity Generator Based Beamed Propulsion Concept", American Institute of Aeronautics and Astronautics, Inc., 2002.

Peter L. Skeggs, "Engineering Analysis of the Podkletnov Gravity Shielding Experiment", Quantum Forum, Nov. 7, 1997, http://www.inetarena'.com/~noetic/pls/podlev.html).

Primary Examiner—Ramon M. Barrera

(57) **ABSTRACT**

A space vehicle propelled by the pressure of inflationary vacuum state is provided comprising a hollow superconductive shield, an inner shield, a power source, a support structure, upper and lower means for generating an electromagnetic field, and a flux modulation controller.

A cooled hollow superconductive shield is energized by an electromagnetic field resulting in the quantized vortices of lattice ions projecting a gravitomagnetic field that forms a spacetime curvature anomaly outside the space vehicle. The spacetime curvature imbalance, the spacetime curvature being the same as gravity, provides for the space vehicle's propulsion. The space vehicle, surrounded by the spacetime anomaly, may move at a speed approaching the light-speed characteristic for the modified locale.

13 Claims, 6 Drawing Sheets




3
14
10
8
5
13
2
1
6
4
11
9
12
7

FIG. 1


19
15
17
18
16

FIG. 2A


23
17
22
20
21

FIG. 2B



FIG. 3A



FIG. 3B



FIG. 4A



FIG. 4B



FIG.5A



FIG.5B



FIG.6



FIG.7A



FIG.7B

SPACE VEHICLE PROPELLED BY THE PRESSURE OF INFLATIONARY VACUUM STATE

CROSS REFERENSE TO RELATED APPLICATIONS

This is a continuation of application Ser. No. 10/633,778 filed on Aug. 4, 2003, now abandoned.

TECHNICAL FIELD

The technical field of this disclosure represents space vehicles propelled by the electro-magnetically changed properties of vacuum, particularly the pressure of inflationary vacuum state.

BACKGROUND OF THE INVENTION

The existence of a magnetic-like gravitational field has been well established by physicists for general relativity, gravitational theories, and cosmology. The consequences of the effect of electromagnetically-affected gravity could be substantial and have many practical applications, particularly in aviation and space exploration.

There are methods known for converting electromagnetism into a propulsive force that potentially generates a large propulsive thrust. According to these methods, the machine thrust is produced by rotating, reciprocating masses in the following ways: centrifugal thrust, momentum thrust, and impulse thrust. ("To the Stars by Electromagnetic Propulsion", M. T. French, http://www.mtjf.demon.co.uk/antigravp2.htm#cforce).

However, the electromagnetic propulsion in an ambient space, or space that is not artificially modified, is not practical for interstellar travel because of the great distances involved. No interstellar travel is feasible without some form of distortion of space. In turn, no alteration of space is possible without the corresponding deformation of time. Gravitomagnetic alteration of space, resulting in the space-time curvature anomaly that could propel the space vehicle, could be a feasible approach to future space travel.

In the late 1940s, H. B. G. Casimir proved that the vacuum is neither particle nor field-free. It is a source of zero-point-fluctuation (ZPF) of fields such as the vacuum gravitomagnetic field. ZPF fields lead to real, measurable physical consequences such as the Casimir force. The quantized hand-made electromagnetic processes, such as those occurring in superconductors, affect the similarly quantized ZPFs. The most likely reason is the electron-positron creation and annihilation, in part corresponding to the "polarization effect" sited by Evgeny Podkletnov in explaining the gravitomagnetic effect reportedly observed by him in 1992. ("Weak Gravitational Shielding Properties of Composite Bulk YBa$_2$Cu$_3$3O$_{(7-x)}$ Superconductor Below 70 K Under E.M. Field", Evgeny Podkletnov, LANL database number cond-mat/9701074, v. 3, 10 pages, 16 Sep. 1997).

The investigation of gravitomagnetism, however, started well before Podkletnov. In the U.S. Pat. No. 3,626,605, Henry Wm. Wallace describes an experimental apparatus for generating and detecting a secondary gravitational field. He also shows how a time-varying gravitomagnetic field can be used to shield the primary background of a gravitoelectric field.

In the U.S. Pat. No. 3,626,606, Henry Wm. Wallace provides a variation of his earlier experiment. A type III-V semiconductor material, of which both components have unpaired nuclear spin, is used as an electronic detector for the gravitomagnetic field. The experiment demonstrates that the material in his gravitomagnetic field circuit has hysterisis and remanence effects analogous to magnetic materials.

In the U.S. Pat. No. 3,823,570, Henry Wm. Wallace provides an additional variation of his experiment. Wallace demonstrates that, by aligning the nuclear spin of materials having an odd number of nucleons, a change in specific heat occurs.

In the U.S. Pat. No. 5,197,279, James R. Taylor discloses Electromagnetic Propulsion Engine where solenoidal windings generate an electromagnetic field that, without the conversion into a gravitomagnetic field, generates the thrust necessary for the propulsion.

In the U.S. Pat. No. 6,353,311 B1, John P. Brainard et al. offer a controversial theory of Universal Particle Flux Field, and in order to prove it empirically, provide a shaded motor-type device. This device is also intended for extracting energy from this hypothetical Field.

In the early 1980s, Sidney Coleman and F. de Luca noted that the Einsteinean postulate of a homogeneous Universe, while correct in general, ignores quantized local fluctuation of the pressure of inflationary vacuum state, this fluctuation causing local cosmic calamities. While the massless particles propagate through large portions of Universe at light speed, these anomaly bubbles, depending on their low or high relative vacuum density, cause a local increase or decrease of the propagation values for these particles. Scientists disagree about the possibility, and possible ways, to artificially create models of such anomalies.

In the early 1990s, Ning Li and D. G Torr described a method and means for converting an electromagnetic field into a gravitomagnetic field. Li and Torr suggested that, under the proper conditions, the minuscule force fields of superconducting atoms can "couple", compounding in strength to the point where they can produce a repulsion force ("Effects of a Gravitomagnetic Field on Pure Superconductors", N. Li and D. G. Torr, Physical Review, Volume 43, Page 457, 3 pages, 15 Jan. 1991).

A series of experiments, performed in the early 1990s by Podkletnov and R. Nieminen, reportedly resulted in a reduction of the weights of objects placed above a levitating, rotating superconductive disk subjected to high frequency magnetic fields. These results substantially support the expansion of Einstainean physics offered by Li & Torr. Podkletnov and Giovanni Modanese have provided a number of interesting theories as to why the weight reduction effect could have occurred, citing quantum gravitational effects, specifically, a local change in the cosmological constant. The cosmological constant, under ordinary circumstances, is the same everywhere. But, according to Podkletnov and Modanese, above a levitating, rotating superconductive disk exposed to high frequency magnetic fields, it is modified. ("Impulse Gravity Generator Based on Charged YBa$_2$Cu$_3$3O$_{7-y}$ Superconductor with Composite Crystal Structure", Evgeny Podkletnov, Giovanni Modanese, arXiv.org/physics database, #0108005 volume 2, 32 pages, 8 figures, Aug. 30, 2001).

In the July 2004 paper, Ning Wu hypothesized that exponential decay of the gravitation gauge field, characteristic for the unstable vacuum such as that created by Podkletnov and Nieminen, is at the root of the gravitational shielding effects (Gravitational Shielding Effects in Gauge Theory of Gravity, Ning Wu, arXiv:hep-th/ 0307225 v 1 23 Jul. 2003, 38 pages incl. 3 figures, July 2004).

In 2002, Edward Fomalont and Sergei Kopeikin measured the speed of propagation of gravity. They confirmed that the speed of propagation of gravity matches the speed of light. ("General Relativistic Model for Experimental Measurement of the Speed of Propagation of Gravity by VLBI", S. Kopeikin and E. Fomalont, Proceedings of the 6^{th} European VLBI Network Symposium Jun. 25–28 2002, Bonn, Germany, 4 pages).

String theory unifies gravity with all other known forces. According to String theory, all interactions are carried by fundamental particles, and all particles are just tiny loops of space itself forming the spacetime curvature. Gravity and bent space are the same thing, propagating with the speed of light characteristic of the particular curvature. In light of the Fomalont and Kopeikin discovery, one can conclude that if there is a change in the speed of propagation of gravity within the spacetime curvature, then the speed of light within the locality would also be affected.

In general relativity, any form of energy affects the gravitational field, so the vacuum energy density becomes a potentially crucial ingredient. Traditionally, the vacuum is assumed to be the same everywhere in the Universe, so the vacuum energy density is a universal number. The cosmological constant Λ is proportional to the vacuum pressure ρ_Λ: $\Lambda=(8\pi G/3c^2)\rho_\Lambda$, where G is Newton's constant of gravitation and c is the speed of light ("The Cosmological Constant", Sean M. Carroll, http://pancake.uchicago.edu/~carroll/encyc/, 6 pages). Newer theories, however, permit local vacuum fluctuations where even the "universal" constants are affected: $\Lambda_1=(8\pi G_1/3c_1^2)\rho_{\Lambda_1}$.

Analyzing physics laws defining the cosmological constant, a conclusion can be drawn that, if a levitating, rotating superconductive disk subjected to high frequency magnetic fields affects the cosmological constant within a locality, it would also affect the vacuum energy density. According to the general relativity theory, the gravitational attraction is explained as the result of the curvature of spacetime being proportional to the cosmological constant. Thus, the change in the gravitational attraction of the vacuum's subatomic particles would cause a local anomaly in the curvature of the Einsteinean spacetime.

Time is the fourth dimension. Lorentz and Einstein showed that space and time are intrinsically related. Later in his life, Einstein hypothesized that time fluctuates both locally and universally. Ruggero Santilli, recognized for expanding relativity theory, has developed the isocosmology theory, which allows for variable rates of time. Time is also a force field only detected at speeds above light speed. The energy of this force field grows as its propagation speed declines when approaching light-speed. Not just any light-speed: the light-speed of a locale. If the conditions of the locale were modified, this change would affect the local time rate relative to the rate outside the affected locale, or ambient rate. The electromagnetically-generated gravitomagnetic field could be one such locale modifier.

Analyzing the expansion of Einstainean physics offered by Li & Torr, one could conclude that gravity, time, and light speed could be altered by the application of electromagnetic force to a superconductor.

By creating a spacetime curvature anomaly associated with lowered pressure of inflationary vacuum state around a space vehicle, with the lowest vacuum pressure density located directly in front of the vehicle, a condition could be created where gravity associated with lowered vacuum pressure density pulls the vehicle forward in modified spacetime.

By creating a spacetime curvature anomaly associated with elevated pressure of inflationary vacuum state around the space vehicle, with the point of highest vacuum pressure density located directly behind the vehicle, a condition could be created where a repulsion force associated with elevated vacuum pressure density pushes the space vehicle forward in modified spacetime. From the above-mentioned cosmological constant equation, re-written as:

$$\rho_\Lambda = \frac{3c^2}{8\pi G}\Lambda$$

it is clear that the increase in the vacuum pressure density could lead to a substantial increase in the light-speed. If the space vehicle is moving in the anomaly where the local light-speed is higher than the light-speed of the ambient vacuum, and if this vehicle approaches this local light-speed, the space vehicle would then possibly exceed the light-speed characteristic for the ambient area.

The levitating and rotating superconductor disk, which Podkletnov used to protect the object of experiment from the attraction produced by the energy of the vacuum, was externally energized by the externally-powered solenoid coils. Thus, Podkletnov's system is stationary by definition and not suitable for travel in air or space. Even if the superconductive disk is made part of the craft, and if it is energized by the energy available on the craft, the resulting anomaly is one-sided, not enveloping, and not providing the variable speed of light (VSL) environment for the craft.

In a recent (2002) article, Chris Y. Tailor and Modanese propose to employ an impulse gravity generator directing, from an outside location, an anomalous beam toward a spacecraft, this beam acting as a repulsion force field producing propulsion for the spacecraft. ("Evaluation of an Impulse Gravity Generator Based Beamed Propulsion Concept", Chris Y. Taylor and Giovanni Modanese, American Institute of Aeronautics and Astronautics, Inc., 2002, 21 pages, 10 figures). The authors of the article, however, didn't take into account the powerful quantized processes of field dispersion, which would greatly limit the distance of propagation of the repulsive force. At best, the implementation of this concept could assist in acceleration and deceleration at short distances from the impulse gravity generator, and only along a straight line of travel. If the travel goal is a space exploration mission rather than the shuttle-like commute, the proposed system is of little use.

Only a self-sufficient craft, equipped with the internal gravity generator and the internal energy source powering this generator, would have the flexibility needed to explore new frontiers of space. The modification of the spacetime curvature all around the spacecraft would allow the spacecraft to approach the light-speed characteristic for the modified locale, this light-speed, when observed from a location in the ambient space, being potentially many times higher than the ambient light-speed. Then, under sufficient local energies, that is, energies available on the spacecraft, very large intergalactic distances could be reduced to conventional planetary distances.

In "The First Men in the Moon" (1903), H. G. Wells anticipates gravitational propulsion methods when he describes gravity repelling "cavorite." Discovered by Professor Cavor, the material acts as a "gravity shield" allowing Cavor's vehicle to reach the Moon. Prof. Cavor built a large spherical gondola surrounded on all sides by cavorite shutters that could be closed or opened. When Prof. Cavor closed all the shutters facing the ground and opened the shutters facing the moon, the gondola took off for the Moon.

Until today, no cavorite has been discovered. However, recent research in the area of superconductivity, nanomaterials and quantum state of vacuum, including that of Li, Torr, Podkletnov, and Modanese, has resulted in important new information about the interaction between a gravitational field and special states of matter at a quantum level. This new research opens the possibility of using new electromagnetically-energized superconductive materials allowing stable states of energy, the materials useful not only in controlling the local gravitational fields, but also in creating new gravitomagnetic fields.

BACKGROUND OF INVENTION: OBJECTS AND ADVANTAGES

There are four objects of this invention:

The first object is to provide a method for generating a pressure anomaly of inflationary vacuum state that leads to electromagnetic propulsion.

The second object is to provide a space vehicle capable of electromagnetically-generated propulsion. The implementation of these two objects leads to the development of the space vehicle propelled by gravitational imbalance with gravity pulling, and/or antigravity pushing, the space vehicle forward.

The third object is to provide a method for generating a pressure anomaly of inflationary vacuum state, specifically, the local increase in the level of vacuum pressure density associated with the greater curvature of spacetime. The speed of light in such an anomaly would be higher than the speed of light in the ambient space.

The fourth object is to provide the space vehicle capable of generating an unequally-distributed external anomaly all around this vehicle, specifically the anomaly with the elevated level of vacuum pressure density. The anomaly is formed in such a way that gravity pulls the space vehicle forward in the modified spacetime at a speed possibly approaching the light-speed specific for this modified locale. If the vacuum pressure density of the locale is modified to be substantially higher than that of the ambient vacuum, the speed of the vehicle could conceivably be higher than the ambient light-speed.

SUMMARY OF THE INVENTION

This invention concerns devices self-propelled by the artificially changed properties of the pressure of inflationary vacuum state to speeds possibly approaching the light-speed specific for this modified locale. Furthermore, this invention concerns devices capable of generating the spacetime anomaly characterized by the elevated vacuum pressure density. The devices combining these capabilities may be able to move at speeds substantially higher than the light-speed in the ambient space.

The device of this invention is a space vehicle. The outside shell of the space vehicle is formed by a hollow disk, sphere, or the like hollowed 3-dimensional shape made of a superconductor material, hereinafter a hollow superconductive shield. An inner shield is disposed inside the hollow superconductive shield. The inner shield is provided to protect crew and life-support equipment inside.

A support structure, upper means for generating an electromagnetic field and lower means for generating an electromagnetic field are disposed between the hollow superconductive shield and the inner shield. A flux modulation controller is disposed inside the inner shield to be accessible to the crew.

Electrical energy is generated in a power source disposed inside the hollow superconductive shield. The electrical energy is converted into an electromagnetic field in the upper means for generating an electromagnetic field and the lower means for generating an electromagnetic field.

Electrical motors, also disposed inside the hollow superconductive shield, convert the electrical energy into mechanical energy.

The mechanical energy and the electromagnetic field rotate the hollow superconductive shield, and the upper and the lower means for generating an electromagnetic field, against each other.

The electromagnetic field is converted into a gravitomagnetic field in the hollow superconductive shield.

The gravitomagnetic field, propagated outward, orthogonally to the walls of the hollow superconductive shield, forms a pressure anomaly of inflationary vacuum state in the area of propagation. The pressure anomaly of inflationary vacuum state is comprised of an area of relatively lower vacuum pressure density in front of the space vehicle and an area of relatively higher vacuum pressure density behind the vehicle.

The difference in the vacuum pressure density propels the space vehicle of this invention forward.

BRIEF DESCRIPTION OF THE DRAWINGS

FIG. **1** is a cross-sectional view through the front plane taken along the central axis of a space vehicle provided by the method and device of this invention.

FIGS. **2**A & **2**B are diagrams, presented as perspective views, showing some of the physical processes resulting from a dynamic application of an electromagnetic field to a hollow superconductive shield. Only one line of quantized vortices, shown out of scale, is presented for illustration purposes.

FIGS. **3**A & **3**B are diagrams, presented as perspective views, showing a vacuum pressure density anomaly associated with lowered pressure of inflationary vacuum state and a vacuum pressure density anomaly associated with elevated pressure of inflationary vacuum state, respectively. Both anomalies are shown on the background of Universal curvature of inflationary vacuum state.

FIGS. **4**A & **4**B are diagrams, presented as perspective views, showing a spacetime anomaly associated with lowered pressure of inflationary vacuum state and a spacetime anomaly associated with elevated pressure of inflationary vacuum state, respectively. Both anomalies are shown on the background of Universal spacetime.

FIGS. **5**A, **5**B, **6**, **7**A, & **7**B are diagrams of spacetime curvature anomalies generated by the space vehicle of the current invention, these anomalies providing for the propulsion of the space vehicle.

DRAWINGS—REFERENCE NUMERALS

1 hollow superconductive shield
2 inner shield
3 upper shell
4 lower shell
5 support structure
6 upper rotating element
7 lower rotating element
8 upper means for generating an electromagnetic field
9 lower means for generating an electromagnetic field
10 flux lines
11 power source

12 life-support equipment
13 flux modulation controller
14 crew
15 clockwise shield motion vector
16 counterclockwise EMF motion vector
17 wire grid
18 clockwise quantized vortices of lattice ions
19 outward gravitomagnetic field vector
20 counterclockwise shield motion vector
21 clockwise EMF motion vector
22 counterclockwise quantized vortices of lattice ions
23 inward gravitomagnetic field vector
24 vacuum pressure density anomaly associated with lowered pressure of inflationary vacuum state
25 Universal curvature of inflationary vacuum state
26 vacuum pressure density anomaly associated with elevated pressure of inflationary vacuum state
27 spacetime anomaly associated with lowered pressure of inflationary vacuum state
28 spacetime anomaly associated with elevated pressure of inflationary vacuum state
29 Universal spacetime
30 substantially droplet-shaped spacetime curvature anomaly associated with lowered pressure of inflationary vacuum state
31 substantially droplet-shaped spacetime anomaly associated with elevated pressure of inflationary vacuum state
32 substantially egg-shaped spacetime anomaly associated with lowered pressure of inflationary vacuum state
33 area of the lowest vacuum pressure density
34 substantially egg-shaped spacetime anomaly associated with elevated pressure of inflationary vacuum state
35 area of the highest vacuum pressure density

DESCRIPTION OF THE PRESENTLY PREFERRED EMBODIMENT

FIG. **1** is a cross-sectional view through the front plane taken along the central axis of a space vehicle provided by the method and device of this invention. A hollow superconductive shield **1** forms a protective outer shell of the space vehicle. The hollow superconductive shield **1** may be shaped as a hollow disk, sphere, or the like 3-dimensional geometrical figure formed by the 2-dimensional rotation of a curve around the central axis.

In the preferred embodiment, the hollow superconductive shield **1** is made of a superconductor such as YBa2Cu3O7-y, or a like high-temperature superconductor with a composite crystal structure cooled to the temperature of about 40 degrees K. The skilled in the art may envision the use of many other low- and high-temperature superconductors, all within the scope of this invention.

An inner shield **2** is disposed inside the hollow superconductive shield **1**. The inner shield **2** is comprised of an upper shell **3** and a lower shell **4**, the shells **3** and **4** adjoined with each other. Executed from insulation materials such as foamed ceramics, the inner shield **2** protects the environment within the shield from the electromagnetic field and severe temperatures.

A support structure **5** is disposed between the hollow superconductive shield **1** and the inner shield **2**, concentric to the hollow superconductive shield. The support structure **5** is comprised of an upper rotating element **6** and a lower rotating element **7**.

The upper rotating element **6** is pivotably disposed inside the hollow superconductive shield **1** and may envelope the upper shell **3**. The lower rotating element **7** is pivotably disposed inside the hollow superconductive shield **1** and may envelope the lower shell **4**. Even though the preferred embodiment has two rotating elements, a skilled in the art may envision only one rotating element, or three or more rotation elements, all within the scope of this invention.

Upper means for generating an electromagnetic field **8** are disposed between the hollow superconductive shield **1** and the upper shell **3**. The upper means for generating an electromagnetic field **8** are affixed to the upper rotating element **6** at an electromagnetic field-penetrable distance to the hollow superconductive shield **1**.

Lower means for generating an electromagnetic field **9** are disposed between the hollow superconductive shield **1** and the lower shell **4**. The lower means for generating an electromagnetic field **9** are affixed to the lower rotating element **7** at an electromagnetic field-penetrable distance to the hollow superconductive shield **1**.

The upper means for generating an electromagnetic field **8** and the lower means for generating an electromagnetic field **9** could be solenoid coils or electromagnets. In the process of operation of the space vehicle, the electromagnetic field identified by flux lines **10**, is controllably and variably applied to the hollow superconductive shield **1**.

Electric motors are disposed inside the hollow superconductive shield along its central axis.

A power source **11** is disposed inside the hollow superconductive shield **1** and may be disposed inside the lower shell **4**. The power source **11** is electrically connected with the upper means for generating an electromagnetic field **8**, the lower means for generating an electromagnetic field **9**, and the electric motors. In-turn, the upper means for generating an electromagnetic field **8**, the lower means for generating an electromagnetic field **9**, and the electric motors provide for the rotation of the upper rotating element **6** and the lower rotating element **7**. The power source **11** may be executed as a nuclear power generator.

Life-support equipment **12** is disposed inside the inner shield **2**, and may be disposed inside the lower shell **4**. The life-support equipment **12** may include oxygen, water, and food.

A flux modulation controller **13** is disposed inside the inner shield **2**, and may be disposed inside the upper shell **3**. The flux modulation controller **13** is in communication with the upper means for generating an electromagnetic field **8**, the lower means for generating an electromagnetic field **9**, the power source **11**, and the electric motors.

The flux modulation controller **8** may be executed as a computer or a microprocessor. The flux modulation controller **8** is provided with a capability of modulating the performance parameters of the upper means for generating an electromagnetic field **8**, the lower means for generating an electromagnetic field **9**, the power source **11**, and the electric motors.

A crew **14** may be located inside the upper shell **3** of the inner shield **2** and may consist of one or more astronauts. The crew has a free access to the life-support equipment **12** and the flux modulation controller **8**. A skilled in the art may envision a fully-automated, pilotless craft, which is also within the scope of this invention.

A skilled in the art may also envision the embodiment (not shown), also within the scope of this invention, where the hollow superconductive shield is pivotable, and the support structure with the means for generating an electromagnetic field is affixed on the outside of the inner shield.

FIGS. **2A** & **2B** are diagrams showing the results of the quantized electromagnetic turbulence within the superconductive shell of the hollow superconductive shield provided by the relative rotational motion of the hollow superconductive shield against the upper means for generating an electromagnetic field.

FIG. **2A** shows the clockwise relative rotational motion of the hollow superconductive shield, this motion identified by a clockwise shield motion vector **15**, and the counterclockwise relative rotational motion of upper means for generating an electromagnetic field, this motion identified by a counterclockwise EMF motion vector **16**.

The electromagnetic field, controllably and variably applied by the upper means for generating an electromagnetic field, whose various positions are identified by a wire grid **17**, to the hollow superconductive shield (not shown), causes quantized electromagnetic turbulence within the hollow superconductive shield. This turbulence is represented by a plurality of clockwise quantized vortices of lattice ions **18**. Only one line of the clockwise quantized vortices of lattice ions **18**, out of scale, is shown for illustration purposes only. Each of the clockwise quantized vortices of lattice ions **18** generates a gravitomagnetic field identified by an outward gravitomagnetic field vector **19** directed orthogonally away from the hollow superconductive shield.

FIG. **2B** shows the counterclockwise relative rotational motion of the hollow superconductive shield, this motion identified by a counterclockwise shield motion vector **20**, and the clockwise relative rotational motion of upper means for generating an electromagnetic field, this motion identified by a clockwise EMF motion vector **21**.

The electromagnetic field, controllably and variably applied by the upper means for generating an electromagnetic field identified by the wire grid **17**, to the hollow superconductive shield (not shown), causes quantized electromagnetic turbulence within the hollow superconductive shield, this turbulence represented by a plurality of counterclockwise quantized vortices of lattice ions **22**. Only one line of the counterclockwise quantized vortices of lattice ions **22**, out of scale, is shown for illustration purposes only. Each of the counterclockwise quantized vortices of lattice ions **22** generates a gravitomagnetic field identified by an inward gravitomagnetic field vector **23** directed orthogonally toward the hollow superconductive shield.

The electrical requirements for providing the Li-Torr effect are as follows:

Podkletnov has reported using the high frequency current of 10^5 Hz. He also used 6 solenoid coils @ 850 Gauss each. The reported system's efficiency reached 100% and the total field in the Podkletnov's disk was about 0.5 Tesla. The maximum weight loss reported by Podkletnov was 2.1%.

The preferred embodiment of the device of current invention is capable of housing 2–3 astronauts and therefore is envisioned to be about 5 meters in diameter at the widest point. The preferred space vehicle's acceleration is set at 9.8 m/s/s providing that gravity on board is similar to that on the surface of Earth.

The means for generating an electromagnetic field may be comprised of 124 solenoid coils. At the same 100% efficiency reported by Podkletnov, the total field required providing the acceleration of 9.8 m/s/s is 5,000 Tesla, or about 40 Tesla per coil. Skeggs suggests that on the Podkletnov device, out of 850 Gauss developed on the coil surface, the field affecting the superconductor and causing the gravitomagnetism is only 400 Gauss ("Engineering Analysis of the Podkletnov Gravity Shielding Experiment, Peter L. Skeggs, Quantum Forum, Nov. 7, 1997, http://www.inetarena.com/~noetic/pls/podlev.html, 7 pages). This translates into 47% device efficiency.

In this 47%-efficient space vehicle, the total field required achieving the 9.8 m/s/s acceleration is about 10,600 Tesla, or 85.5 Tesla per each of 124 solenoid coils. It must be noted that at this acceleration rate, it would take nearly a year for the space vehicle to reach the speed of light.

It also must be noted that Skeggs has detected a discrepancy between the Li-Torr estimates and Podkletnov's practical results. If Podkletnov's experimental results are erroneous while the Li-Torr estimates are indeed applicable to the space vehicle of this invention, then the energy requirements for achieving the sought speed would be substantially higher than the above estimate of 10,600 Tesla.

Podkletnov has concluded that, in order for the vacuum pressure density anomaly to take place, the Earth-bound device must be in the condition of Meissner levitation. As are all space bodies, the space vehicle is a subject to the pressure inflationary vacuum state and the gravitational force, which, within the migrating locality of the expanding Universe, in any single linear direction, are substantially in equilibrium. Thus, for the space vehicle, the requirement of Meissner levitation is waved.

The propagation of the gravitomagnetic field identified by the outward gravitomagnetic field vector **19** and the inward gravitomagnetic field vector **23** would cause exotic quantized processes in the vacuum's subatomic particles that include particle polarization, ZPF field defects, and the matter-energy transformation per $E=mc^2$. The combination of these processes would result in the gravitational anomaly. According to the general relativity theory, gravitational attraction is explained as the result of the curvature of spacetime being proportional to the gravitational constant. Thus, the change in the gravitational attraction of the vacuum's subatomic particles would cause a local anomaly in the curvature of the Einsteinean spacetime.

Gravity is the same thing as bent space, propagating with the speed of light characteristic for the particular spacetime curvature. When bent space is affected, there is a change in the speed of propagation of gravity within the spacetime curvature anomaly. The local speed of light, according to Fomalont and Kopeikin always equal to the local speed of propagation of gravity, is also affected within the locality of spacetime curvature anomaly.

Creation of spacetime curvature anomalies adjacent to, or around, the space vehicle, these anomalies characterized by the local gravity and light-speed change, has been the main object of this invention.

FIG. **3A** shows a diagram of a vacuum pressure density anomaly associated with lowered pressure of inflationary vacuum state **24** on the background of Universal curvature of inflationary vacuum state **25**. The vacuum pressure density anomaly associated with lowered pressure of inflationary vacuum state **24** is formed by a multitude of the inward gravitomagnetic field vectors. According to the cosmological constant equation, $\Lambda=(8\pi G/3c^2)\rho_\Lambda$, where the cosmological constant Λ is proportional to the vacuum energy pressure ρ_Λ, G is Newton's constant of gravitation, and c is the speed of light, the curvature of spacetime is proportional to the gravitational constant. According to the general relativity theory, the change in the vacuum pressure density is proportional to the change in the spacetime curvature anomaly. By replacing ρ_Λ with the vacuum pressure density, P times the vacuum energy coefficient κ, and replacing c with Δdistance/Δtime, we derive to $\Lambda=[8\pi G/3(\Delta\text{distance}/\Delta\text{time})^2]P_\kappa$, and could now construct a vacuum pressure density curvature diagram.

The vacuum pressure density curvature anomaly associated with lowered pressure of inflationary vacuum state **24** is shown here as a flattened surface representing the lowered pressure of the inflationary vacuum state. This anomaly is the result of the exotic quantized processes in the subatomic particles caused by the quantized turbulence occurring in the hollow superconductive shield. The XYZ axes represent three dimensions of space and the P axis represents the vacuum pressure density.

FIG. **3**B shows a diagram of a vacuum pressure density anomaly associated with elevated pressure of inflationary vacuum state **26** on the background of the Universal curvature of inflationary vacuum state **25**. The vacuum pressure density anomaly associated with elevated pressure of inflationary vacuum state **26** is formed by a multitude of the outward gravitomagnetic field vectors. The anomaly is shown here as a convex surface representing the elevated pressure of inflationary vacuum state. The diagrams of FIGS. **3**A & **3**B are not to scale: the anomaly sizes are exaggerated for clarity.

FIGS. **4**A & **4**B show diagrams of a spacetime anomaly associated with lowered pressure of inflationary vacuum state **27**, and a spacetime anomaly associated with elevated pressure of inflationary vacuum state **28**, respectively, each on the background a diagram of Universal spacetime **29**.

The quaterized Julia set $Q_{n+1}=Q_n^2+C_0$ is assumed to be an accurate mathematical representation of the Universal spacetime. The generic quaternion Q_0 belongs to the Julia set associated with the quaternion C, and n tends to infinity. If we assume that the quaternion value C_0 is associated with the Universal spacetime **29**, C_1 is the value of quaternion C for the spacetime anomaly associated with lowered pressure of inflationary vacuum state **27**, and C_2 is the value of quaternion C for the spacetime anomaly associated with elevated pressure of inflationary vacuum state **28**, then we can construct two diagrams.

The diagram of FIG. **4**A shows the spacetime anomaly associated with lowered pressure of inflationary vacuum state **27** as a quaterized Julia set contained in a 4-dimensional space: $Q_{n+1}=Q_n^2+C_1$ on the background of the Universal spacetime **29** represented by $Q_{n+1}=Q_n^2+C_0$.

The diagram of FIG. **4**B shows the spacetime anomaly associated with elevated pressure of inflationary vacuum state **28** as a quaterized Julia set $Q_{n+1}=Q_n^2+C_2$, also on the background of the Universal spacetime **29** represented by $Q_{n+1}=Q_n^2+C_0$. On both diagrams, the XYZ axes represent three dimensions of space, and the T axis represents time. The diagrams are not to scale: the anomaly sizes are exaggerated for clarity, and the halves of quaterized Julia sets, conventionally associated with the hypothetical Anti-Universe, are omitted.

FIGS. **5**A, **5**B, **6**, **7**A, & **7**B show simplified diagrams of spacetime curvature anomalies generated by the space vehicle of the current invention, these anomalies providing for the propulsion of the space vehicle. In each case, the pressure anomaly of inflationary vacuum state is comprised of an area of relatively lower vacuum pressure density in front of the space vehicle and an area of relatively higher vacuum pressure density behind the space vehicle. Because the lower pressure of inflationary vacuum state is associated with greater gravity and the higher pressure is associated with the higher repulsive force, the space vehicle is urged to move from the area of relatively higher vacuum pressure density toward the area of relatively lower vacuum pressure density.

FIG. **5**A illustrates the first example of spacetime curvature modification. This example shows a substantially droplet-shaped spacetime curvature anomaly associated with lowered pressure of inflationary vacuum state **30** adjacent to the hollow superconductive shield **1** of the space vehicle. The anomaly **30** is provided by the propagation of a gravitomagnetic field radiating orthogonally away from the front of the hollow superconductive shield **1**. This gravitomagnetic field may be provided by the relative clockwise motion of the upper means for generating an electromagnetic field, and relative counterclockwise motion of the hollow superconductive field, as observed from above the space vehicle.

In this example, the difference between the spacetime curvature within the substantially droplet-shaped spacetime anomaly associated with lowered pressure of inflationary vacuum state, and the ambient spacetime curvature, the spacetime curvature being the same as gravity, results in the gravitational imbalance, with gravity pulling the space vehicle forward.

FIG. **5**B illustrates the second example of spacetime curvature modification. This example shows a substantially droplet-shaped spacetime anomaly associated with elevated pressure of inflationary vacuum state **31** adjacent to the hollow superconductive shield **1** of the space vehicle. The anomaly **31** is provided by the propagation of a gravitomagnetic field radiating orthogonally away from the back of the hollow superconductive shield. This gravitomagnetic field may be provided by the relative counterclockwise motion of the lower means for generating an electromagnetic field, and relative clockwise motion of the hollow superconductive field, as observed from below the space vehicle.

In this example, the difference between the spacetime curvature within the substantially droplet-shaped spacetime anomaly associated with elevated pressure of inflationary vacuum state, and the ambient spacetime curvature, the spacetime curvature being the same as gravity, results in the gravitational imbalance, with the repulsion force pushing the space vehicle forward.

FIG. **6** illustrates the third example of spacetime curvature modification. This example shows the formation of the substantially droplet-shaped spacetime anomaly associated with lowered pressure of inflationary vacuum state **30** combined with the substantially droplet-shaped spacetime anomaly associated with elevated pressure of inflationary vacuum state **31**. This combination of anomalies may be provided by the relative clockwise motion of the upper means for generating an electromagnetic field and relative clockwise motion of the hollow superconductive field, combined with the relative clockwise motion of the lower means for generating an electromagnetic field, as observed from above the space vehicle.

In this example, the difference between the spacetime curvature within the substantially droplet-shaped spacetime anomaly associated with lowered pressure of inflationary vacuum state, and the spacetime curvature of the substantially droplet-shaped spacetime anomaly associated with elevated pressure of inflationary vacuum state, the spacetime curvature being the same as gravity, results in the gravitational imbalance, with gravity pulling, and the repulsion force pushing, the space vehicle forward.

FIG. **7**A illustrates the fourth example of spacetime curvature modification. This example shows the formation of a substantially egg-shaped spacetime anomaly associated with lowered pressure of inflationary vacuum state **32** around the hollow superconductive shield **1** of the space vehicle. The anomaly **32** is provided by the propagation of gravitomagnetic field of unequally-distributed density, this gravitomagnetic field radiating in all directions orthogonally away from the hollow superconductive shield. The propagation of the unequally-distributed gravitomagnetic field leads to the similarly unequally-distributed spacetime curvature anomaly. This unequally-distributed gravitomagnetic field may be provided by the relatively faster clockwise motion of the upper means for generating an electromagnetic field relative to the hollow superconductive field, combined with the relatively slower counterclockwise motion of the lower means for generating an electromagnetic field, as observed from above the space vehicle.

An area of the lowest vacuum pressure density **33** of the substantially egg-shaped spacetime anomaly associated with lowered pressure of inflationary vacuum state **32** is located directly in front of the space vehicle.

In this example, the variation in the spacetime curvature within the substantially egg-shaped spacetime anomaly associated with lowered pressure of inflationary vacuum state, the spacetime curvature being the same as gravity, results in a gravitational imbalance, with gravity pulling the space vehicle forward in modified spacetime.

FIG. **7**B illustrates the fifth example of spacetime curvature modification, also with the purpose of providing for a propulsion in modified spacetime. This example shows the formation of a substantially egg-shaped spacetime anomaly associated with elevated pressure of inflationary vacuum state **34** around the hollow superconductive shield **1** of the space vehicle. The anomaly **34** is provided by the propagation of gravitomagnetic field of unequally-distributed density, this gravitomagnetic field radiating in all directions orthogonally away from the hollow superconductive shield. The propagation of the unequally-distributed gravitomagnetic field leads to the similarly unequally-distributed spacetime curvature anomaly. This unequally-distributed gravitomagnetic field may be provided by the relatively slower counterclockwise motion of the upper means for generating an electromagnetic field relative to the hollow superconductive field, combined with the relatively faster clockwise motion of the lower means for generating an electromagnetic field, as observed from above the space vehicle.

An area of the highest vacuum pressure density **35** of the substantially egg-shaped spacetime anomaly associated with elevated pressure of inflationary vacuum state **34** is located directly behind the space vehicle.

In this example, the variation in the spacetime curvature within the substantially egg-shaped spacetime anomaly associated with elevated pressure of inflationary vacuum state, the spacetime curvature being same as gravity, results in a gravitational imbalance, with the repulsion force pushing the space vehicle forward in modified spacetime at speeds approaching the light-speed characteristic for this modified area. This light-speed might be much higher than the light-speed in the ambient space.

By creating alternative anomalies and modulating their parameters, the space vehicle's crew would dilate and contract time and space on demand. The space vehicle, emitting a vacuum pressure modifying, controllably-modulated gravitomagnetic field in all directions, would rapidly move in the uneven spacetime anomaly it created, pulled forward by gravity or pushed by the repulsion force. The time rate zone of the anomaly is expected to have multiple quantized boundaries rather than a single sudden boundary affecting space and time in the immediate proximity of the vehicle. Speed, rate of time, and direction in space could be shifted on demand and in a rapid manner. The modulated light-speed could make the space vehicle suitable for interstellar travel. Because of the time rate control in the newly created isospace, the accelerations would be gradual and the angles of deviation would be relatively smooth. The gravity shielding would further protect pilots from the ill-effects of gravity during rapid accelerations, directional changes, and sudden stops.

What is claimed is:

1. A space vehicle propelled by the pressure of inflationary vacuum state is claimed comprising:

a hollow superconductive shield,

an inner shield, the inner shield disposed inside said hollow superconductive shield, said inner shield comprising an upper shell and a lower shell,

a support structure, the support structure disposed between said hollow superconductive shield and said inner shield concentrically to said hollow superconductive shield, said support structure comprised of an upper rotating element and a lower rotating element,

upper means for generating an electromagnetic field, the upper means for generating an electromagnetic field disposed between said hollow superconductive shield and said upper shell, affixed to said upper rotating element at an electromagnetic field-penetrable distance to said hollow superconductive shield,

lower means for generating an electromagnetic field, the lower means for generating an electromagnetic field disposed between said hollow superconductive shield and said lower shell, affixed to said lower rotating element at an electromagnetic field-penetrable distance to said hollow superconductive shield,

electric motors, the electric motors disposed inside said hollow superconductive shield along the central axis of said hollow superconductive shield,

a power source, the power source disposed inside said hollow superconductive shield, said power source electrically connected with said upper means for generating an electromagnetic field, said lower means for generating an electromagnetic field, and said electric motors,

life-support equipment, the life-support equipment disposed inside said inner shield,

a flux modulation controller, the flux modulation controller disposed inside said inner shield, said flux modulation controller in communication with said upper means for generating an electromagnetic field, said lower means for generating an electromagnetic field, said power source, and said electric motors, and

a crew, the crew disposed inside said inner shield accessibly to said life-support and said flux modulation controller.

2. The space vehicle of claim **1** wherein said hollow superconductive shield is composed of a high-temperature ceramic superconductor with a composite crystal structure, and is cooled to a temperature of about 40 degrees K.

3. The space vehicle of claim **1** wherein said inner shield is composed of insulating materials such as foamed ceramics.

4. The space vehicle of claim **1** wherein said power source is a nuclear generator.

5. The space vehicle of claim **1** wherein said flux modulation controller is a computer.

6. The space vehicle of claim **1** wherein said upper rotating element and said lower rotating element are pivoted, urged to rotate by said upper means for generating an electromagnetic field, said lower means for generating an electromagnetic field, and said electric motors.

7. The space vehicle of claim **1** wherein said hollow superconductive shield is pivoted and urged to rotate by said upper means for generating an electromagnetic field, said lower means for generating an electromagnetic field, and said electric motors.

8. A method for generating pressure anomaly of inflationary vacuum state is claimed comprising the following steps, some occurring simultaneously:

providing a space vehicle comprising a hollow superconductive shield, an inner shield, a support structure, upper means for generating an electromagnetic field, lower means for generating an electromagnetic field, electric motors, a power source, life-support equipment, a flux modulation controller, and a crew,

generating electrical energy in said power source,

converting said electrical energy into an electromagnetic field in said upper means for generating an electromagnetic field and said lower means for generating an electromagnetic field,

converting said electrical energy into mechanical energy in said electrical motors,

rotating said upper means for generating an electromagnetic field and said lower means for generating an electromagnetic field relative to said hollow superconductive shield,

converting said electromagnetic field into a gravitomagnetic field in said hollow superconductive shield,

propagating said gravitomagnetic field outward, orthogonal to the walls of said hollow superconductive shield, and

forming a pressure anomaly of inflationary vacuum state in the area of propagation of said gravitomagnetic field, the pressure anomaly of inflationary vacuum state comprised of an area of relatively lower vacuum pressure density in front of said space vehicle and an area of relatively higher vacuum pressure density behind said vehicle,

whereby said space vehicle is urged to move from said area of relatively higher vacuum pressure density toward said area of relatively lower vacuum pressure density.

9. The method of claim **8** wherein said pressure anomaly of inflationary vacuum state is a substantially droplet-shaped anomaly associated with lowered pressure of inflationary vacuum state provided by the propagation of a gravitomagnetic field radiating orthogonally away from the front of said hollow superconductive shield,

whereby providing for the gravitational imbalance where the lowered pressure of inflationary vacuum state is pulling said space vehicle forward.

10. The method of claim **8** wherein said pressure anomaly of inflationary vacuum state is a substantially droplet-shaped anomaly associated with elevated pressure of inflationary vacuum state provided by the propagation of a gravitomagnetic field radiating orthogonally away from the back of said hollow superconductive shield,

whereby providing for the gravitational imbalance where the elevated pressure of inflationary vacuum state is pushing said space vehicle forward.

11. The method of claim **8** wherein said pressure anomaly of inflationary vacuum state is comprised of a substantially droplet-shaped anomaly associated with lowered pressure of inflationary vacuum state and a substantially droplet-shaped anomaly associated with elevated pressure of inflationary vacuum state,

whereby providing for the gravitational imbalance where the lowered pressure of inflationary vacuum state is pulling, and the elevated pressure of inflationary vacuum state is pushing, said space vehicle forward.

12. The method of claim **8** wherein said pressure anomaly of inflationary vacuum state is a substantially egg-shaped anomaly associated with lowered pressure of inflationary vacuum state provided by the unequally-distributed gravitomagnetic field propagated in all directions orthogonally away from said hollow superconductive shield with an area of lowest vacuum pressure density disposed directly in front said space vehicle,

whereby providing for the gravitational imbalance such that the lowered pressure of inflationary vacuum state is pulling said space vehicle forward in modified spacetime.

13. The method of claim **8** wherein said pressure anomaly of inflationary vacuum state is a substantially egg-shaped anomaly associated with elevated pressure of inflationary vacuum state provided by the unequally-distributed gravitomagnetic field propagated in all directions orthogonally away from said hollow superconductive shield with an area of highest vacuum pressure density disposed directly behind said space vehicle,

whereby providing for the gravitational imbalance such that the highest pressure of inflationary vacuum state is pushing said space vehicle forward in modified spacetime at a speed possibly approaching a local light-speed, the local light-speed which may be substantially higher than the light-speed in the ambient space.

* * * * *

455-619 AU 233 EX
FIP3106 OR 685,958

55

No. 685,958. **Patented Nov. 5, 1901.**

N. TESLA.

METHOD OF UTILIZING RADIANT ENERGY.

(Application filed Mar. 21, 1901.)

(No Model.)

Electric steping motor
energized by corpuscular
energy from sun



Fig.1

No refs.



Fig.2

pick up

Witnesses:
Raphaël Netter
M. Lawson Dyer

Nikola Tesla, Inventor

by Kerr, Page & Cooper Att'ys

UNITED STATES PATENT OFFICE.

NIKOLA TESLA, OF NEW YORK, N. Y.

METHOD OF UTILIZING RADIANT ENERGY.

SPECIFICATION forming part of Letters Patent No. 685,958, dated November 5, 1901.

Application filed March 21, 1901. Serial No. 52,154. (No model.)

To all whom it may concern:

Be it known that I, NIKOLA TESLA, a citizen of the United States, residing at the borough of Manhattan, in the city, county, and State of New York, have invented certain new and useful Improvements in Methods of Utilizing Radiant Energy, of which the following is a specification, reference being had to the drawings accompanying and forming a part of the same.

It is well known that certain radiations—such as those of ultra-violet light, cathodic, Roentgen rays, or the like—possess the property of charging and discharging conductors of electricity, the discharge being particularly noticeable when the conductor upon which the rays impinge is negatively electrified. These radiations are generally considered to be ether vibrations of extremely small wave lengths, and in explanation of the phenomena noted it has been assumed by some authorities that they ionize or render conducting the atmosphere through which they are propagated. My own experiments and observations, however, lead me to conclusions more in accord with the theory heretofore advanced by me that sources of such radiant energy throw off with great velocity minute particles of matter which are strongly electrified, and therefore capable of charging an electrical conductor, or even if not so may at any rate discharge an electrified conductor either by carrying off bodily its charge or otherwise.

My present application is based upon a discovery which I have made that when rays or radiations of the above kind are permitted to fall upon an insulated conducting body connected to one of the terminals of a condenser, while the other terminal of the same is made by independent means to receive or to carry away electricity, a current flows into the condenser so long as the insulated body is exposed to the rays, and under the conditions hereinafter specified an indefinite accumulation of electrical energy in the condenser takes place. This energy after a suitable time interval, during which the rays are allowed to act, may manifest itself in a powerful discharge, which may be utilized for the operation or control of mechanical or electrical devices or rendered useful in many other ways.

In applying my discovery I provide a condenser, preferably of considerable electrostatic capacity, and connect one of its terminals to an insulated metal plate or other conducting body exposed to the rays or streams of radiant matter. It is very important, particularly in view of the fact that electrical energy is generally supplied at a very slow rate to the condenser, to construct the same with the greatest care. I use by preference the best quality of mica as dielectric, taking every possible precaution in insulating the armatures, so that the instrument may withstand great electrical pressures without leaking and may leave no perceptible electrification when discharging instantaneously. In practice I have found that the best results are obtained with condensers treated in the manner described in a patent granted to me February 23, 1897, No. 577,671. Obviously the above precautions should be the more rigorously observed the slower the rate of charging and the smaller the time interval during which the energy is allowed to accumulate in the condenser. The insulated plate or conducting body should present as large a surface as practicable to the rays or streams of matter, I having ascertained that the amount of energy conveyed to it per unit of time is under otherwise identical conditions proportionate to the area exposed, or nearly so. Furthermore, the surface should be clean and preferably highly polished or amalgamated. The second terminal or armature of the condenser may be connected to one of the poles of a battery or other source of electricity or to any conducting body or object whatever of such properties or so conditioned that by its means electricity of the required sign will be supplied to the terminal. A simple way of supplying positive or negative electricity to the terminal is to connect the same either to an insulated conductor, supported at some height in the atmosphere, or to a grounded conductor, the former, as is well known, furnishing positive and the latter negative electricity. As the rays or supposed streams of matter generally convey a positive charge to the first condenser-terminal, which is connect-

RADIANT ENERGY.

EXAMINER

ed to the plate or conductor above mentioned, I usually connect the second terminal of the condenser to the ground, this being the most convenient way of obtaining negative electricity, dispensing with the necessity of providing an artificial source. In order to utilize for any useful purpose the energy accumulated in the condenser, I furthermore connect to the terminals of the same a circuit including an instrument or apparatus which it is desired to operate and another instrument or device for alternately closing and opening the circuit. This latter may be any form of circuit-controller, with fixed or movable parts or electrodes, which may be actuated either by the stored energy or by independent means.

The rays or radiations which are to be utilized for the operation of the apparatus above described in general terms may be derived from a natural source, as the sun, or may be artificially produced by such means, for example, as an arc-lamp, a Roentgen tube, and the like, and they may be employed for a great variety of useful purposes.

My discovery will be more fully understood from the following detailed description and annexed drawings, to which reference is now made, and in which—

Figure 1 is a diagram showing typical forms of the devices or elements as arranged and connected in applying the method for the operation of a mechanical contrivance or instrument solely by the energy stored; and Fig. 2 is a diagrammatical representation of a modified arrangement suitable for special purposes, with a circuit-controller actuated by independent means.

Referring to Fig. 1, C is the condenser, P the insulated plate or conducting body, which is exposed to the rays, and P′ another plate or conductor, all being joined in series, as shown. The terminals T T′ of the condenser are also connected to a circuit including a receiver R, which is to be operated, and a circuit-controlling device *d*, which in this case is composed of two very thin conducting-plates *t t′*, placed in close proximity and very mobile, either by reason of extreme flexibility or owing to the charater of their support. To improve their action, they should be inclosed in a receptacle from which the air may be exhausted. The receiver R is shown as consisting of an electromagnet M, a movable armature *a*, a retractile spring *b*, and a ratchet-wheel *w*, provided with a spring-pawl *r*, which is pivoted to armature *a*, as illustrated. The apparatus being arranged as shown, it will be found that when the radiations of the sun or of any other source capable of producing the effects before described fall upon the plate P an accumulation of electrical energy in the condenser C will result. This phenomenon, I believe, is best explained as follows: The sun as well as other sources of radiant energy throw off minute particles of matter positively electrified, which, impinging upon the plate P, communicate an electrical charge to the same. The opposite terminal of the condenser being connected to the ground, which may be considered as a vast reservoir of negative electricity, a feeble current flows continuously into the condenser, and inasmuch as these supposed particles are of an inconceivably small radius or curvature, and consequently charged to a relatively very high potential, this charging of the condenser may continue, as I have found in practice, almost indefinitely, even to the point of rupturing the dielectric. Obviously whatever circuit-controller be employed it should operate to close the circuit in which it is included when the potential in the condenser has reached the desired magnitude. Thus in Fig. 2 when the electrical pressure at the terminals T T′ rises to a certain predetermined value the plates *t t′*, attracting each other, close the circuit connected to the terminals. This permits a flow of current which energizes the magnet M, causing it to draw down the armature *a* and impart a partial rotation to the ratchet-wheel *w*. As the current ceases the armature is retracted by the spring *b* without, however, moving the wheel *w*. With the stoppage of the current the plates *t t′* cease to be attracted and separate, thus restoring the circuit to its original condition.

Many useful applications of this method of utilizing the radiations emanating from the sun or other source and many ways of carrying out the same will at once suggest themselves from the above description. By way of illustration a modified arrangement is shown in Fig. 2, in which the source S of radiant energy is a special form of Roentgen tube devised by me having but one terminal *k*, generally of aluminium, in the form of half a sphere with a plain polished surface on the front side, from which the streams are thrown off. It may be excited by attaching it to one of the terminals of any generator of sufficiently-high electromotive force; but whatever apparatus be used it is important that the tube be exhausted to a high degree, as otherwise it might prove entirely ineffective. The working or discharge circuit connected to the terminals T T′ of the condenser includes in this case the primary *p* of a transformer and a circuit-controller comprising a fixed terminal or brush *t* and a movable terminal *t′* in the shape of a wheel with conducting and insulating segments which may be rotated at an arbitrary speed by any suitable means. In inductive relation to the primary wire or coil *p* is a secondary *s*, usually of a much greater number of turns, to the ends of which is connected a receiver R. The terminals of the condenser being connected as indicated, one to an insulated plate P and the other to a grounded plate P′, when the tube S is excited rays or streams of matter are emitted from the same, which convey a positive charge to the plate P and condenser-terminal T, while terminal T′ is continuously receiving negative electricity from the plate

P′. This, as before explained, results in an accumulation of electrical energy in the condenser, which goes on as long as the circuit including the primary p is interrupted. Whenever the circuit is closed, owing to the rotation of the terminal t', the stored energy is discharged through the primary p, this giving rise in the secondary s to induced currents which operate the receiver R.

It is clear from what has been stated above that if the terminal T′ is connected to a plate supplying positive instead of negative electricity the rays should convey negative electricity to plate P. The source S may be any form of Roentgen or Lenard tube; but it is obvious from the theory of action that in order to be very effective the electrical impulses exciting it should be wholly or at least preponderatingly of one sign. If ordinary symmetrical alternating currents are employed, provision should be made for allowing the rays to fall upon the plate P only during those periods when they are productive of the desired result. Evidently if the radiations of the source be stopped or intercepted or their intensity varied in any manner, as by periodically interrupting or rythmically varying the current exciting the source, there will be corresponding changes in the action upon the receiver R, and thus signals may be transmitted and many other useful effects produced. Furthermore, it will be understood that any form of circuit-closer which will respond to or be set in operation when a predetermined amount of energy is stored in the condenser may be used in lieu of the device specifically described with reference to Fig. 1, and also that the special details of construction and arrangement of the several parts of the apparatus may be very greatly varied without departure from the invention.

Having described my invention, what I claim is—

1. The method of utilizing radiant energy, which consists in charging one of the armatures of a condenser by rays or radiations, and the other armature by independent means, and discharging the condenser through a suitable receiver, as set forth.

2. The method of utilizing radiant energy, which consists in simultaneously charging a condenser by means of rays or radiations and an independent source of electrical energy, and discharging the condenser through a suitable receiver, as set forth.

3. The method of utilizing radiant energy, which consists in charging one of the armatures of a condenser by rays or radiations, and the other by independent means, controlling the action or effect of said rays or radiations and discharging the condenser through a suitable receiver, as set forth.

4. The method of utilizing radiant energy, which consists in charging one of the armatures of a condenser by rays or radiations and the other by independent means, varying the intensity of the said rays or radiations and periodically discharging the condenser through a suitable receiver, as set forth.

5. The method of utilizing radiant energy, which consists in directing upon an elevated conductor, connected to one of the armatures of a condenser, rays or radiations capable of positively electrifying the same, carrying off electricity from the other armature by connecting the same with the ground, and discharging the accumulated energy through a suitable receiver, as set forth.

6. The method of utilizing radiant energy, which consists in charging one of the armatures of a condenser by rays or radiations, and the other by independent means, and effecting by the automatic discharge of the accumulated energy the operation or control of a suitable receiver, as set forth.

NIKOLA TESLA.

Witnesses:
M. LAWSON DYER,
RICHARD DONOVAN.

United States Patent [19]
Eastlund

[11] **Patent Number:** **4,686,605**
[45] **Date of Patent:** **Aug. 11, 1987**

[54] **METHOD AND APPARATUS FOR ALTERING A REGION IN THE EARTH'S ATMOSPHERE, IONOSPHERE, AND/OR MAGNETOSPHERE**

[75] Inventor: **Bernard J. Eastlund**, Spring, Tex.
[73] Assignee: **APTI, Inc.**, Los Angeles, Calif.
[21] Appl. No.: **690,333**
[22] Filed: **Jan. 10, 1985**
[51] **Int. Cl.**^{4} **H05B 6/64**; H05C 3/00; H05H 1/46
[52] **U.S. Cl.** .... **361/231**; 89/1.11; 380/59; 244/158 R
[58] **Field of Search** .... 361/230, 231; 244/158 R; 376/100; 89/1.11; 380/59

[56] **References Cited**

PUBLICATIONS

Liberty Magazine, (2/35) p. 7 N. Tesla.
New York Times (9/22/40) Section 2, p. 7 W. L. Laurence.
New York Times (12/8/15) p. 8 Col. 3.

Primary Examiner—Salvatore Cangialosi
Attorney, Agent, or Firm—Roderick W. MacDonald

[57] **ABSTRACT**

A method and apparatus for altering at least one selected region which normally exists above the earth's surface. The region is excited by electron cyclotron resonance heating to thereby increase its charged particle density. In one embodiment, circularly polarized electromagnetic radiation is transmitted upward in a direction substantially parallel to and along a field line which extends through the region of plasma to be altered. The radiation is transmitted at a frequency which excites electron cyclotron resonance to heat and accelerate the charged particles. This increase in energy can cause ionization of neutral particles which are then absorbed as part of the region thereby increasing the charged particle density of the region.

15 Claims, 5 Drawing Figures



FIG. 1


11
NORTH POLE
10
MB
20
12
15
TRANSMITTER 16
14
C
POWER GENERATOR 17
EQUATOR
13
R
MB
SOUTH POLE

FIG. 2


R2
M_{B_1}
[F=-μ•∇B]
R1

FIG. 3


[F = -μ·∇B]
R2
11
θ
12
i
e
n
R1
10


30
R3
11
12
f3
33
20
31
15
10
32

FIG. 4


TREATER
MHD GENERATOR
TRANSMITTER

FIG. 5

METHOD AND APPARATUS FOR ALTERING A REGION IN THE EARTH'S ATMOSPHERE, IONOSPHERE, AND/OR MAGNETOSPHERE

DESCRIPTION

1. Technical Field

This invention relates to a method and apparatus for altering at least one selected region normally existing above the earth's surface and more particularly relates to a method and apparatus for altering said at least one region by initially transmitting electromagnetic radiation from the earth's surface essentially parallel to and along naturally-occurring, divergent magnetic field lines which extend from the earth's surface through the region or regions to be altered.

2. Background Art

In the late 1950's, it was discovered that naturally-occuring belts exist at high altitudes above the earth's surface, and it is now established that these belts result from charged electrons and ions becoming trapped along the magnetic lines of force (field lines) of the earth's essentially dipole magnetic field. The trapped electrons and ions are confined along the field lines between two magnetic mirrors which exist at spaced apart points along those field lines. The trapped electrons and ions move in helical paths around their particular field lines and "bounce" back and forth between the magnetic mirrors. These trapped electrons and ions can oscillate along the field lines for long periods of time.

In the past several years, substantial effort has been made to understand and explain the phenomena involved in belts of trapped electrons and ions, and to explore possible ways to control and use these phenomena for beneficial purposes. For example, in the late 1950's and early 1960's both the United States and U.S.S.R. detonated a series of nuclear devices of various yields to generate large numbers of charged particles at various altitudes, e.g., 200 kilometers (km) or greater. This was done in order to establish and study artifical belts of trapped electrons and ions. These experiments established that at least some of the extraneous electrons and ions from the detonated devices did become trapped along field lines in the earth's magnetosphere to form artificial belts which were stable for prolonged periods of time. For a discussion of these experiments see "The Radiation Belt and Magnetosphere", W. N. Hess, Blaisdell Publishing Co., 1968, pps. 155 et sec.

Other proposals which have been advanced for altering existing belts of trapped electrons and ions and/or establishing similar artificial belts include injecting charged particles from a satellite carrying a payload of radioactive beta-decay material or alpha emitters; and injecting charged particles from a satellite-borne electron accelerator. Still another approach is described in U.S. Pat. No. 4,042,196 wherein a low energy ionized gas, e.g., hydrogen, is released from a synchronous orbiting satellite near the apex of a radiation belt which is naturally-occurring in the earth's magnetosphere to produce a substantial increase in energetic particle precipitation and, under certain conditions, produce a limit in the number of particles that can be stably trapped. This precipitation effect arises from an enhancement of the whistler-mode and ion-cyclotron mode interactions that result from the ionized gas or "cold plasma" injection.

It has also been proposed to release large clouds of barium in the magnetosphere so that photoionization will increase the cold plasma density, thereby producing electron precipitation through enhanced whistler-mode interactions.

However, in all of the above-mentioned approaches, the mechanisms involved in triggering the change in the trapped particle phenomena must be actually positioned within the affected zone, e.g., the magnetosphere, before they can be actuated to effect the desired change.

The earth's ionosphere is not considered to be a "trapped" belt since there are few trapped particles therein. The term "trapped" herein refers to situations where the force of gravity on the trapped particles is balanced by magnetic forces rather than hydrostatic or collisional forces. The charged electrons and ions in the ionosphere also follow helical paths around magnetic field lines within the ionosphere but are not trapped between mirrors, as in the case of the trapped belts in the magnetosphere, since the gravitational force on the particles is balanced by collisional or hydrostatic forces.

In recent years, a number of experiments have actually been carried out to modify the ionosphere in some controlled manner to investigate the possibility of a beneficial result. For detailed discussions of these operations see the following papers: (1) Ionospheric Modification Theory; G. Meltz and F. W. Perkins; (2) The Platteville High Power Facility; Carrol et al.; (3) Arecibo Heating Experiments; W. E. Gordon and H. C. Carlson, Jr.; and (4) Ionospheric Heating by Powerful Radio Waves; Meltz et al., all published in Radio Science, Vol. 9, No. 11, November, 1974, at pages 885–888; 889–894; 1041–1047; and 1049–1063, respectively, all of which are incorporated herein by reference. In such experiments, certain regions of the ionosphere are heated to change the electron density and temperature within these regions. This is accomplished by transmitting from earth-based antennae high frequency electromagnetic radiation at a substantial angle to, not parallel to, the ionosphere's magnetic field to heat the ionospheric particles primarily by ohmic heating. The electron temperature of the ionosphere has been raised by hundreds of degrees in these experiments, and electrons with several electron volts of energy have been produced in numbers sufficient to enhance airglow. Electron concentrations have been reduced by a few percent, due to expansion of the plasma as a result of increased temperature.

In the Elmo Bumpy Torus (EBT), a controlled fusion device at the Oak Ridge National Laboratory, all heating is provided by microwaves at the electron cyclotron resonance interaction. A ring of hot electrons is formed at the earth's surface in the magnetic mirror by a combination of electron cyclotron resonance and stochastic heating. In the EBT, the ring electrons are produced with an average "temperature" of 250 kilo electron volts or kev (2.5×10^9K) and a plasma beta between 0.1 and 0.4; see, "A Theoretical Study of Electron—Cyclotron Absorption in Elmo Bumpy Torus", Batchelor and Goldfinger, Nuclear Fusion, Vol. 20, No. 4 (1980) pps. 403–418.

Electron cyclotron resonance heating has been used in experiments on the earth's surface to produce and accelerate plasmas in a diverging magnetic field. Kosmahl et al. showed that power was transferred from the electromagnetic waves and that a fully ionized plasma

was accelerated with a divergence angle of roughly 13 degrees. Optimum neutral gas density was 1.7×10^{14} per cubic centimeter; see, "Plasma Acceleration with Microwaves Near Cyclotron Resonance", Kosmahl et al., Journal of Applied Physics, Vol. 38, No. 12, Nov., 1967, pps. 4576–4582.

DISCLOSURE OF THE INVENTION

The present invention provides a method and apparatus for altering at least one selected region which normally exists above the earth's surface. The region is excited by electron cyclotron resonance heating of electrons which are already present and/or artifically created in the region to thereby increase the charged particle energy and ultimately the density of the region.

In one embodiment this is done by transmitting circularly polarized electromagnetic radiation from the earth's surface at or near the location where a naturally-occurring dipole magnetic field (force) line intersects the earth's surface. Right hand circular polarization is used in the northern hemisphere and left hand circular polarization is used in the southern hemisphere. The radiation is deliberately transmitted at the outset in a direction substantially parallel to and along a field line which extends upwardly through the region to be altered. The radiation is transmitted at a frequency which is based on the gyrofrequency of the charged particles and which, when applied to the at least one region, excites electron cyclotron resonance within the region or regions to heat and accelerate the charged particles in their respective helical paths around and along the field line. Sufficient energy is employed to cause ionization of neutral particles (molecules of oxygen, nitrogen and the like, particulates, etc.) which then become a part of the region thereby increasing the charged particle density of the region. This effect can further be enhanced by providing artificial particles, e.g., electrons, ions, etc., directly into the region to be affected from a rocket, satellite, or the like to supplement the particles in the naturally-occurring plasma. These artificial particles are also ionized by the transmitted electromagnetic radiation thereby increasing charged particle density of the resulting plasma in the region.

In another embodiment of the invention, electron cyclotron resonance heating is carried out in the selected region or regions at sufficient power levels to allow a plasma present in the region to generate a mirror force which forces the charged electrons of the altered plasma upward along the force line to an altitude which is higher than the original altitude. In this case the relevant mirror points are at the base of the altered region or regions. The charged electrons drag ions with them as well as other particles that may be present. Sufficient power, e.g., 10^{15} joules, can be applied so that the altered plasma can be trapped on the field line between mirror points and will oscillate in space for prolonged periods of time. By this embodiment, a plume of altered plasma can be established at selected locations for communication modification or other purposes.

In another embodiment, this invention is used to alter at least one selected region of plasma in the ionosphere to establish a defined layer of plasma having an increased charged particle density. Once this layer is established, and while maintaining the transmission of the main beam of circularly polarized electromagnetic radiation, the main beam is modulated and/or at least one second different, modulated electromagnetic radiation beam is transmitted from at least one separate source at a different frequency which will be absorbed in the plasma layer. The amplitude of the frequency of the main beam and/or the second beam or beams is modulated in resonance with at least one known oscillation mode in the selected region or regions to excite the known oscillation mode to propagate a known frequency wave or waves throughout the ionosphere.

BRIEF DESCRIPTION OF THE DRAWINGS

The actual construction, operation, and apparent advantages of this invention will be better understood by referring to the drawings in which like numerals identify like parts and in which:

FIG. **1** is a simplified schematical view of the earth (not to scale) with a magnetic field (force) line along which the present invention is carried out;

FIG. **2** is one embodiment within the present invention in which a selected region of plasma is raised to a higher altitude;

FIG. **3** is a simplified, idealized representation of a physical phenomenon involved in the present invention; and

FIG. **4** is a schematic view of another embodiment within the present invention.

FIG. **5** is a schematic view of an apparatus embodiment within this invention.

BEST MODES FOR CARRYING OUT THE INVENTION

The earth's magnetic field is somewhat analogous to a dipole bar magnet. As such, the earth's magnetic field contains numerous divergent field or force lines, each line intersecting the earth's surface at points on opposite sides of the Equator. The field lines which intersect the earth's surface near the poles have apexes which lie at the furthest points in the earth's magnetosphere while those closest to the Equator have apexes which reach only the lower portion of the magnetosphere.

At various altitudes above the earth's surface, e.g., in both the ionosphere and the magnetosphere, plasma is naturally present along these field lines. This plasma consists of equal numbers of positively and negatively charged particles (i.e., electrons and ions) which are guided by the field line. It is well established that a charged particle in a magnetic field gyrates about field lines, the center of gyration at any instance being called the "guiding center" of the particle. As the gyrating particle moves along a field line in a uniform field, it will follow a helical path about its guiding center, hence linear motion, and will remain on the field line. Electrons and ions both follow helical paths around a field line but rotate in opposite directions. The frequencies at which the electrons and ions rotate about the field line are called gyromagnetic frequencies or cyclotron frequencies because they are identical with the expression for the angular frequencies of gyration of particles in a cyclotron. The cyclotron frequency of ions in a given magnetic field is less than that of electrons, in inverse proportion to their masses.

If the particles which form the plasma along the earth's field lines continued to move with a constant pitch angle, often designated "alpha", they would soon impact on the earth's surface. Pitch angle alpha is defined as the angle between the direction of the earth's magnetic field and the velocity (V) of the particle. However, in converging force fields, the pitch angle does change in such a way as to allow the particle to

turn around and avoid impact. Consider a particle moving along a field line down toward the earth. It moves into a region of increasing magnetic field strength and therefore sine alpha increases. But sine alpha can only increase to 1.0, at which point, the particle turns around and starts moving up along the field line, and alpha decreases. The point at which the particle turns around is called the mirror point, and there alpha equals ninety degrees. This process is repeated at the other end of the field line where the same magnetic field strength value B, namely Bm, exists. The particle again turns around and this is called the "conjugate point" of the original mirror point. The particle is therefore trapped and bounces between the two magnetic mirrors. The particle can continue oscillating in space in this manner for long periods of time. The actual place where a particle will mirror can be calculated from the following:

$$\sin^2 \text{alpha}_o = B_o/B_m \quad (1)$$

wherein:

alpha_o = equatorial pitch angle of particle

B_o = equatorial field strength on a particular field line

B_m = field strength at the mirror point

Recent discoveries have established that there are substantial regions of naturally trapped particles in space which are commonly called "trapped radiation belts". These belts occur at altitudes greater than about 500 km and accordingly lie in the magnetosphere and mostly above the ionosphere.

The ionosphere, while it may overlap some of the trapped-particle belts, is a region in which hydrostatic forces govern its particle distribution in the gravitational field. Particle motion within the ionosphere is governed by both hydrodynamic and electrodynamic forces. While there are few trapped particles in the ionosphere, nevertheless, plasma is present along field lines in the ionosphere. The charged particles which form this plasma move between collisions with other particles along similar helical paths around the field lines and although a particular particle may diffuse downward into the earth's lower atmosphere or lose energy and diverge from its original field line due to collisions with other particles, these charged particles are normally replaced by other available charged particles or by particles that are ionized by collision with said particle. The electron density (N_e) of the plasma will vary with the actual conditions and locations involved. Also, neutral particles, ions, and electrons are present in proximity to the field lines.

The production of enhanced ionization will also alter the distribution of atomic and molecular constituents of the atmosphere, most notably through increased atomic nitrogen concentration. The upper atmosphere is normally rich in atomic oxygen (the dominant atmospheric constituent above 200 km altitude), but atomic nitrogen is normally relatively rare. This can be expected to manifest itself in increased airglow, among other effects.

As known in plasma physics, the characteristics of a plasma can be altered by adding energy to the charged particles or by ionizing or exciting additional particles to increase the density of the plasma. One way to do this is by heating the plasma which can be accomplished in different ways, e.g., ohmic, magnetic compression, shock waves, magnetic pumping, electron cyclotron resonance, and the like.

Since electron cyclotron resonance heating is involved in the present invention, a brief discussion of same is in order. Increasing the energy of electrons in a plasma by invoking electron cyclotron resonance heating, is based on a principle similar to that utilized to accelerate charged particles in a cyclotron. If a plasma is confined by a static axial magnetic field of strength B, the charged particles will gyrate about the lines of force with a frequency given, in hertz, as $f_g = 1.54 \times 10^3 B/A$, where: B = magnetic field strength in gauss, and A = mass number of the ion.

Suppose a time-varying field of this frequency is superimposed on the static field B confining the plasma, by passage of a radiofrequency current through a coil which is concentric with that producing the axial field, then in each half-cycle of their rotation about the field lines, the charged particles acquire energy from the oscillating electric field associated with the radio frequency. For example, if B is 10,000 gauss, the frequency of the field which is in resonance with protons in a plasma is 15.4 megahertz.

As applied to electrons, electron cyclotron resonance heating requires an oscillating field having a definite frequency determined by the strength of the confining field. The radio-frequency radiation produces time-varying fields (electric and magnetic), and the electric field accelerates the charged particle. The energized electrons share their energy with ions and neutrals by undergoing collisions with these particles, thereby effectively raising the temperature of the electrons, ions, and neutrals. The apportionment of energy among these species is determined by collision frequencies. For a more detailed understanding of the physics involved, see "Controlled Thermonuclear Reactions", Glasstone and Lovberg, D. Van Nostrand Company, Inc., Princeton, N.J., 1960 and "The Radiation Belt and Magnetosphere", Hess, Blaisdell Publishing Company, 1968, both of which are incorporated herein by reference.

Referring now to the drawings, the present invention provides a method and apparatus for altering at least one region of plasma which lies along a field line, particularly when it passes through the ionosphere and/or magnetosphere. FIG. **1** is a simplified illustration of the earth **10** and one of its dipole magnetic force or field lines **11**. As will be understood, line **11** may be any one of the numerous naturally existing field lines and the actual geographical locations **13** and **14** of line **11** will be chosen based on a particular operation to be carried out. The actual locations at which field lines intersect the earth's surface is documented and is readily ascertainable by those skilled in the art.

Line **11** passes through region R which lies at an altitude above the earth's surface. A wide range of altitudes are useful given the power that can be employed by the practice of this invention. The electron cyclotron resonance heating effect can be made to act on electrons anywhere above the surface of the earth. These electrons may be already present in the atmosphere, ionosphere, and/or magnetosphere of the earth, or can be artificially generated by a variety of means such as x-ray beams, charged particle beams, lasers, the plasma sheath surrounding an object such as a missile or meteor, and the like. Further, artificial particles, e.g., electrons, ions, etc., can be injected directly into region R from an earth-launched rocket or orbiting satellite carrying, for example, a payload of radioactive beta-decay material; alpha emitters; an electron accelerator; and/or ionized gases such as hydrogen; see U.S. Pat. No. 4,042,196. The altitude can be greater than about 50 km if desired,

e.g., can be from about 50 km to about 800 km, and, accordingly may lie in either the ionosphere or the magnetosphere or both. As explained above, plasma will be present along line **11** within region R and is represented by the helical line **12**. Plasma **12** is comprised of charged particles (i.e., electrons and ions) which rotate about opposing helical paths along line **11**.

Antenna **15** is positioned as close as is practical to the location **14** where line **11** intersects the earth's surface. Antenna **15** may be of any known construction for high directionality, for example, a phased array, beam spread angle (θ) type. See "The MST Radar at Poker Flat, Alaska", Radio Science, Vol. 15, No. 2, Mar.-Apr. 1980, pps. 213–223, which is incorporated herein by reference. Antenna **15** is coupled to transmitter **16** which generates a beam of high frequency electromagnetic radiation at a wide range of discrete frequencies, e.g., from about 20 to about 1800 kilohertz (kHz).

Transmitter **16** is powered by power generator means **17** which is preferably comprised of one or more large, commercial electrical generators. Some embodiments of the present invention require large amounts of power, e.g., up to 10^9 to 10^{11} watts, in continuous wave or pulsed power. Generation of the needed power is within the state of the art. Although the electrical generators necessary for the practice of the invention can be powered in any known manner, for example, by nuclear reactors, hydroelectric facilities, hydrocarbon fuels, and the like, this invention, because of its very large power requirement in certain applications, is particularly adapted for use with certain types of fuel sources which naturally occur at strategic geographical locations around the earth. For example, large reserves of hydrocarbons (oil and natural gas) exist in Alaska and Canada. In northern Alaska, particularly the North Slope region, large reserves are currently readily available. Alaska and northern Canada also are ideally located geographically as to magnetic latitudes. Alaska provides easy access to magnetic field lines that are especially suited to the practice of this invention, since many field lines which extend to desirable altitudes for this invention intersect the earth in Alaska. Thus, in Alaska, there is a unique combination of large, accessible fuel sources at desirable field line intersections. Further, a particularly desirable fuel source for the generation of very large amounts of electricity is present in Alaska in abundance, this source being natural gas. The presence of very large amounts of clean-burning natural gas in Alaskan latitudes, particularly on the North Slope, and the availability of magnetohydrodynamic (MHD), gas turbine, fuel cell, electrogasdynamic (EGD) electric generators which operate very efficiently with natural gas provide an ideal power source for the unprecedented power requirements of certain of the applications of this invention. For a more detailed discussion of the various means for generating electricity from hydrocarbon fuels, see "Electrical Aspects of Combustion", Lawton and Weinberg, Clarendon Press, 1969. For example, it is possible to generate the electricity directly at the high frequency needed to drive the antenna system. To do this, typically the velocity of flow of the combustion gases (v), past magnetic field perturbation of dimension d (in the case of MHD), follow the rule:

$$v=df$$

where f is the frequency at which electricity is generated. Thus, if $v=1.78\times10^6$ cm/sec and d=1 cm then electricity would be generated at a frequency of 1.78 mHz.

Put another way, in Alaska, the right type of fuel (natural gas) is naturally present in large amounts and at just the right magnetic latitudes for the most efficient practice of this invention, a truly unique combination of circumstances. Desirable magnetic latitudes for the practice of this invention interest the earth's surface both northerly and southerly of the equator, particularly desirable latitudes being those, both northerly and southerly, which correspond in magnitude with the magnetic latitudes that encompass Alaska.

Referring now to FIG. 2 a first ambodiment is illustrated where a selected region R_1 of plasma **12** is altered by electron cyclotron resonance heating to accelerate the electrons of plasma **12**, which are following helical paths along field line **11**.

To accomplish this result, electromagnetic radiation is transmitted at the outset, essentially parallel to line **11** via antenna **15** as right hand circularly polarized radiation wave **20**. Wave **20** has a frequency which will excite electron cyclotron resonance with plasma **12** at its initial or original altitude. This frequency will vary depending on the electron cyclotron resonance of region R_1 which, in turn, can be determined from available data based on the altitudes of region R_1, the particular field line **11** being used, the strength of the earth's magnetic field, etc. Frequencies of from about 20 to about 7200 kHz, preferably from about 20 to about 1800 kHz can be employed. Also, for any given application, there will be a threshhold (minimum power level) which is needed to produce the desired result. The minimum power level is a function of the level of plasma production and movement required, taking into consideration any loss processes that may be dominant in a particular plasma or propagation path.

As electron cyclotron resonance is established in plasma **12**, energy is transferred from the electromagnetic radiation **20** into plasma **12** to heat and accelerate the electrons therein and, subsequently, ions and neutral particles. As this process continues, neutral particles which are present within R_1 are ionized and absorbed into plasma **12** and this increases the electron and ion densities of plasma **12**. As the electron energy is raised to values of about 1 kilo electron volt (kev), the generated mirror force (explained below) will direct the excited plasma **12** upward along line **11** to form a plume R_2 at an altitude higher than that of R_1.

Plasma acceleration results from the force on an electron produced by a nonuniform static magnetic field ($\bar{B}$). The force, called the mirror force, is given by

$$F=-\mu\nabla B \qquad (2)$$

where μ is the electron magnetic moment and $\nabla\bar{B}$ is the gradient of the magnetic field, μ being further defined as:

$$W_\perp/B=mV_\perp^2/2B$$

where $W_\perp$ is the kinetic energy in the direction perpendicular to that of the magnetic field lines and B is the magnetic field strength at the line of force on which the guiding center of the particle is located. The force as represented by equation (2) is the force which is responsible for a particle obeying equation (1).

Since the magnetic field is divergent in region R_1, it can be shown that the plasma will move upwardly from the heating region as shown in FIG. **1** and further it can be shown that

$$\tfrac{1}{2}M_eV_{e\perp}^2(x) \approx \tfrac{1}{2}M_eV_{e\perp}^2(Y) + \tfrac{1}{2}M_iV_{i\,||}^2(Y) \qquad (3)$$

where the left hand side is the initial electron transverse kinetic energy; the first term on the right is the transverse electron kinetic energy at some point (Y) in the expanded field region, while the final term is the ion kinetic energy parallel to B at point (Y). This last term is what constitutes the desired ion flow. It is produced by an electrostatic field set up by electrons which are accelerated according to Equation (2) in the divergent field region and pulls ions along with them. Equation (3) ignores electron kinetic energy parallel to B because $V_{e\,||} \approx V_{i\,||}$, so the bulk of parallel kinetic energy resides in the ions because of their greater masses. For example, if an electromagnetic energy flux of from about 1 to about 10 watts per square centimeter is applied to region R, whose altitude is 115 km, a plasma having a density (N_e) of 10^{12} per cubic centimeter will be generated and moved upward to region R_2 which has an altitude of about 1000 km. The movement of electrons in the plasma is due to the mirror force while the ions are moved by ambipolar diffusion (which results from the electrostatic field). This effectively "lifts" a layer of plasma **12** from the ionosphere and/or magnetosphere to a higher elevation R_2. The total energy required to create a plasma with a base area of 3 square kilometers and a height of 1000 km is about 3×10^{13} joules.

FIG. **3** is an idealized representation of movement of plasma **12** upon excitation by electron cyclotron resonance within the earth's divergent force field. Electrons (e) are accelerated to velocities required to generate the necessary mirror force to cause their upward movement. At the same time neutral particles (n) which are present along line **11** in region $R_1$are ionized and become part of plasma **12**. As electrons (e) move upward along line **11**, they drag ions (i) and neutrals (n) with them but at an angle θ of about 13 degrees to field line **11**. Also, any particulates that may be present in region R_1, will be swept upwardly with the plasma. As the charged particles of plasma **12** move upward, other particles such as neutrals within or below R_1, move in to replace the upwardly moving particles. These neutrals, under some conditions, can drag with them charged particles.

For example, as a plasma moves upward, other particles at the same altitude as the plasma move horizontally into the region to replace the rising plasma and to form new plasma. The kinetic energy developed by said other particles as they move horizontally is, for example, on the same order of magnitude as the total zonal kinetic energy of stratospheric winds known to exist.

Referring again to FIG. **2**, plasma **12** in region R_1 is moved upward along field line **11**. The plasma **12** will then form a plume (cross-hatched area in FIG. **2**) which will be relatively stable for prolonged periods of time. The exact period of time will vary widely and be determined by gravitational forces and a combination of radiative and diffusive loss terms. In the previous detailed example, the calculations were based on forming a plume by producing 0+energies of 2 ev/particle. About 10 ev per particle would be required to expand plasma **12** to apex point C (FIG. **1**). There at least some of the particles of plasma **12** will be trapped and will oscillate between mirror points along field line **11**. This oscillation will then allow additional heating of the trapped plasma **12** by stochastic heating which is associated with trapped and oscillating particles. See "A New Mechanism for Accelerating Electrons in the Outer Ionosphere" by R. A. Helliwell and T. F. Bell, Journal of Geophysical Research, Vol. 65, No. 6, June, 1960. This is preferably carried out at an altitude of at least 500 km.

The plasma of the typical example might be employed to modify or disrupt microwave transmissions of satellites. If less than total black-out of transmission is desired (e.g., scrambling by phase shifting digital signals), the density of the plasma (N_e) need only be at least about 10^6 per cubic centimeter for a plasma orginating at an altitude of from about 250 to about 400 km and accordingly less energy (i.e., electromagnetic radiation), e.g., 10^8 joules need be provided. Likewise, if the density $N_e$is on the order of 10^8, a properly positioned plume will provide a reflecting surface for VHF waves and can be used to enhance, interfere with, or otherwise modify communication transmissions. It can be seen from the foregoing that by appropriate application of various aspects of this invention at strategic locations and with adequate power sources, a means and method is provided to cause interference with or even total disruption of communications over a very large portion of the earth. This invention could be employed to disrupt not only land based communications, both civilian and military, but also airborne communications and sea communications (both surface and subsurface). This would have significant military implications, particularly as a barrier to or confusing factor for hostile missiles or airplanes. The belt or belts of enhanced ionization produced by the method and apparatus of this invention, particularly if set up over Northern Alaska and Canada, could be employed as an early warning device, as well as a communications disruption medium. Further, the simple ability to produce such a situation in a practical time period can by itself be a deterring force to hostile action. The ideal combination of suitable field lines intersecting the earth's surface at the point where substantial fuel sources are available for generation of very large quantitities of electromagnetic power, such as the North Slope of Alaska, provides the wherewithal to accomplish the foregoing in a practical time period, e.g., strategic requirements could necessitate achieving the desired altered regions in time periods of two minutes or less and this is achievable with this invention, especially when the combination of natural gas and magnetohydrodynamic, gas turbine, fuel cell and/or EGD electric generators are employed at the point where the useful field lines intersect the earth's surface. One feature of this invention which satisfies a basic requirement of a weapon system, i.e., continuous checking of operability, is that small amounts of power can be generated for operability checking purposes. Further, in the exploitation of this invention, since the main electromagnetic beam which generates the enhanced ionized belt of this invention can be modulated itself and/or one or more additional electromagnetic radiation waves can be impinged on the ionized region formed by this invention as will be described in greater detail herein after with respect to FIG. **4**, a substantial amount of randomly modulated signals of very large power magnitude can be generated in a highly nonlinear mode. This can cause confusion of or interference with or even complete disruption of guidance systems employed by

even the most sophisticated of airplanes and missiles. The ability to employ and transmit over very wide areas of the earth a plurality of electromagnetic waves of varying frequencies and to change same at will in a random manner, provides a unique ability to interfere with all modes of communications, land, sea, and/or air, at the same time. Because of the unique juxtaposition of usable fuel source at the point where desirable field lines intersect the earth's surface, such wide ranging and complete communication interference can be achieved in a resonably short period of time. Because of the mirroring phenomenon discussed hereinabove, it can also be prolonged for substantial time periods so that it would not be a mere transient effect that could simply be waited out by an opposing force. Thus, this invention provides the ability to put unprecedented amounts of power in the earth's atmosphere at strategic locations and to maintain the power injection level, particularly if random pulsing is employed, in a manner far more precise and better controlled than heretofore accomplished by the prior art, particularly by the detonation of nuclear devices of various yeilds at various altitudes. Where the prior art approaches yielded merely transitory effects, the unique combination of fuel and desirable field lines at the point where the fuel occurs allows the establishment of, compared to prior art approaches, precisely controlled and long-lasting effects which cannot, practically speaking, simply be waited out. Further, by knowing the frequencies of the various electromagnetic beams employed in the practice of this invention, it is possible not only to interfere with third party communications but to take advantage of one or more such beams to carry out a communications network even though the rest of the world's communications are disrupted. Put another way, what is used to disrupt another's communications can be employed by one knowledgeable of this invention as a communications network at the same time. In addition, once one's own communication network is established, the far-reaching extent of the effects of this invention could be employed to pick up communication signals of other for intelligence purposes. Thus, it can be seen that the disrupting effects achievable by this invention can be employed to benefit by the party who is practicing this invention since knowledge of the various electromagnetic waves being employed and how they will vary in frequency and magnitude can be used to an advantage for positive communication and eavesdropping purposes at the same time. However, this invention is not limited to locations where the fuel source naturally exists or where desirable field lines naturally intersect the earth's surface. For example, fuel, particularly hydrocarbon fuel, can be transported by pipeline and the like to the location where the invention is to be practiced.

FIG. 4 illustrates another embodiment wherein a selected region of plasma R_3which lies within the earth's ionosphere is altered to increase the density thereof whereby a relatively stable layer **30** of relatively dense plasma is maintained within region R_3. Electromagnetic radiation is transmitted at the outset essentially parallel to field line **11** via antenna **15** as a right hand circularly polarized wave and at a frequency (e.g., 1.78 megahertz when the magnetic field at the desired altitude is 0.66 gauss) capable of exciting electron cyclotron resonance in plasma **12** at the particular altitude of plasma **12**. This causes heating of the particles (electrons, ions, neutrals, and particulates) and ionization of the uncharged particles adjacent line **11**, all of which are absorbed into plasma **12** to increase the density thereof. The power transmitted, e.g., 2×10^6 watts for up to 2 minutes heating time, is less than that required to generate the mirror force F required to move plasma **12** upward as in the previous embodiment.

While continuing to transmit electromagnetic radiation **20** from antenna **15**, a second electromagnetic radiation beam **31**, which is at a defined frequency different from the radiation from antenna **15**, is transmitted from one or more second sources via antenna **32** into layer **30** and is absorbed into a portion of layer **30** (cross-hatched area in FIG. 4). The electromagnetic radiation wave from antenna **32** is amplitude modulated to match a known mode of oscillation f_3 in layer **30**. This creates a resonance in layer **30** which excites a new plasma wave **33** which also has a frequency of f_3 and which then propogates through the ionosphere. Wave **33** can be used to improve or disrupt communications or both depending on what is desired in a particular application. Of course, more than one new wave **33** can be generated and the various new waves can be modulated at will and in a highly nonlinear fashion.

FIG. **5** shows apparatus useful in this invention, particularly when those applications of this invention are employed which require extremely large amounts of power. In FIG. **5** there is shown the earth's surface **40** with a well **41** extending downwardly thereinto until it penetrates hydrocarbon producing reservoir **42**. Hydrocarbon reservoir **42** produces natural gas alone or in combination with crude oil. Hydrocarbons are produced from reservoir **42** through well **41** and wellhead **43** to a treating system **44** by way of pipe **45**. In treater **44**, desirable liquids such as crude oil and gas condensates are separated and recovered by way of pipe **46** while undesirable gases and liquids such as water, H_2S, and the like are separated by way of pipe **47**. Desirable gases such as carbon dioxide are separated by way of pipe **48**, and the remaining natural gas stream is removed from treater **44** by way of pipe **49** for storage in conventional tankage means (not shown) for future use and/or use in an electrical generator such as a magnetohydrodynamic, gas turbine, fuel cell or EGD generator **50**. Any desired number and combination of different types of electric generators can be employed in the practice of this invention. The natural gas is burned in generator **50** to produce substantial quantities of electricity which is then stored and/or passed by way of wire **51** to a transmitter **52** which generates the electromagnetic radiation to be used in the method of this invention. The electromagnetic radiation is then passed by way of wire **53** to antenna **54** which is located at or near the end of field line **11**. Antenna **54** sends circularly polarized radiation wave **20** upwards along field line **11** to carry out the various methods of this invention as described hereinabove.

Of course, the fuel source need not be used in its naturally-occurring state but could first be converted to another second energy source form such as hydrogen, hydrazine and the like, and electricity then generated from said second energy source form.

It can be seen from the foregoing that when desirable field line **11** intersects earth's surface **40** at or near a large naturally-occurring hydrocarbon source **42**, exceedingly large amounts of power can be very efficiently produced and transmitted in the direction of field lines. This is particularly so when the fuel source is natural gas and magnetohydrodynamic generators are employed. Further, this can all be accomplished in a

relatively small physical area when there is the unique coincidence of fuel source **42** and desirable field line **11**. Of course, only one set of equipment is shown in FIG. **5** for sake of simplicity. For a large hydrocarbon reservoir **42**, a plurality of wells **41** can be employed to feed one or more storage means and/or treaters and as large a number of generators **55** as needed to power one or more transmitters **52** and one or more antennas **54**. Since all of the apparatus **44** through **54** can be employed and used essentially at the sight where naturally-occurring fuel source **42** is located, all the necessary electromagnetic radiation **20** is generated essentially at the same location as fuel source **42**. This provides for a maximum amount of usable electromagnetic radiation **20** since there are no significant storage or transportation losses to be incurred. In other words, the apparatus is brought to the sight of the fuel source where desirable field line **11** intersects the earth's surface **40** on or near the geographical location of fuel source **42**, fuel source **42** being at a desirable magnetic latitude for the practice of this invention, for example, Alaska.

The generation of electricity by motion of a conducting fluid through a magnetic field, i.e., magnetohydrodynamics (MHD), provides a method of electric power generation without moving mechanical parts and when the conducting fluid is a plasma formed by combustion of a fuel such as natural gas, an idealized combination of apparatus is realized since the very clean-burning natural gas forms the conducting plasma in an efficient manner and the thus formed plasma, when passed through a magnetic field, generates electricity in a very efficient manner. Thus, the use of fuel source **42** to generate a plasma by combustion thereof for the generation of electricity essentially at the site of occurrence of the fuel source is unique and ideal when high power levels are required and desirable field lines **11** intersect the earth's surface **40** at or near the site of fuel source **42**. A particular advantage for MHD generators is that they can be made to generate large amounts of power with a small volume, light weight device. For example, a 1000 megawatt MHD generator can be construed using superconducting magnets to weigh roughly 42,000 pounds and can be readily air lifted.

This invention has a phenomenal variety of possible ramifications and potential future developments. As alluded to earlier, missile or aircraft destruction, deflection, or confusion could result, particularly when relativistic particles are employed. Also, large regions of the atmosphere could be lifted to an unexpectedly high altitude so that missiles encounter unexpected and unplanned drag forces with resultant destruction or deflection of same. Weather modification is possible by, for example, altering upper atmosphere wind patterns or altering solar absorption patterns by constructing one or more plumes of atmospheric particles which will act as a lens or focusing device. Also as alluded to earlier, molecular modifications of the atmosphere can take place so that positive environmental effects can be achieved. Besides actually changing the molecular composition of an atmospheric region, a particular molecule or molecules can be chosen for increased presence. For example, ozone, nitrogen, etc. concentrations in the atmosphere could be artificially increased. Similarly, environmental enhancement could be achieved by causing the breakup of various chemical entities such as carbon dioxide, carbon monoxide, nitrous oxides, and the like. Transportation of entities can also be realized when advantage is taken of the drag effects caused by regions of the atmosphere moving up along diverging field lines. Small micron sized particles can be then transported, and, under certain circumstances and with the availability of sufficient energy, larger particles or objects could be similarly affected. Particles with desired characteristics such as tackiness, reflectivity, absorptivity, etc., can be transported for specific purposes or effects. For example, a plume of tacky particles could be established to increase the drag on a missile or satellite passing therethrough. Even plumes of plasma having substantially less charged particle density than described above will produce drag effects on missiles which will affect a lightweight (dummy) missile in a manner substantially different than a heavy (live) missile and this affect can be used to distinguish between the two types of missiles. A moving plume could also serve as a means for supplying a space station or for focusing vast amount of sunlight on selected portions of the earth. Surveys of global scope could also be realized because the earth's natural magnetic field could be significantly altered in a controlled manner by plasma beta effects resulting in, for example, improved magnetotelluric surveys. Electromagnetic pulse defenses are also possible. The earth's magnetic field could be decreased or disrupted at appropriate altitudes to modify or eliminate the magnetic field in high Compton electron generation (e.g., from high altitude nuclear bursts) regions. High intensity, well controlled electrical fields can be provided in selected locations for various purposes. For example, the plasma sheath surrounding a missile or satellite could be used as a trigger for activating such a high intensity field to destroy the missile or satellite. Further, irregularities can be created in the ionosphere which will interfere with the normal operation of various types of radar, e.g., synthetic aperture radar. The present invention can also be used to create artificial belts of trapped particles which in turn can be studied to determine the stability of such parties. Still further, plumes in accordance with the present invention can be formed to simulate and/or perform the same functions as performed by the detonation of a "heave" type nuclear device without actually having to detonate such a device. Thus it can be seen that the ramifications are numerous, far-reaching, and exceedingly varied in usefulness.

I claim:

1. A method for altering at least one region normally existing above the earth's surface with electromagnetic radiation using naturally-occurring and diverging magnetic field lines of the earth comprising transmitting first electromagnetic radiation at a frequency between 20 and 7200 kHz from the earth's surface, said transmitting being conducted essentially at the outset of transmission substantially parallel to and along at least one of said field lines, adjusting the frequency of said first radiation to a value which will excite electron cyclotron resonance at an initial elevation at least 50 km above the earth's surface, whereby in the region in which said electron cyclotron resonance takes place heating, further ionization, and movement of both charged and neutral particles is effected, said cyclotron resonance excitation of said region is continued until the electron concentration of said region reaches a value of at least 10^6 per cubic centimeter and has an ion energy of at least 2 ev.

2. The method of claim **1** including the step of providing artificial particles in said at least one region which are excited by said electron cyclotron resonance.

3. The method of claim **2** wherein said artificial particles are provided by injecting same into said at least one region from an orbiting satellite.

4. The method of claim **1** wherein said threshold excitation of electron cyclotron resonance is about 1 watt per cubic centimeter and is sufficient to cause movement of a plasma region along said diverging magnetic field lines to an altitude higher than the altitude at which said excitation was initiated.

5. The method of claim **4** wherein said rising plasma region pulls with it a substantial portion of neutral particles of the atmosphere which exist in or near said plasma region.

6. The method of claim **1** wherein there is provided at least one separate source of second electromagnetic radiation, said second radiation having at least one frequency different from said first radiation, impinging said at least one second radiation on said region while said region is undergoing electron cyclotron resonance excitation caused by said first radiation.

7. The method of claim **6** wherein said second radiation has a frequency which is absorbed by said region.

8. The method of claim **6** wherein said region is plasma in the ionosphere and said second radiation excites plasma waves within said ionosphere.

9. The method of claim **8** wherein said electron concentration reaches a value of at least 10^{12} per cubic centimeter.

10. The method of claim **8** wherein said excitation of electron cyclotron resonance is initially carried out within the ionosphere and is continued for a time sufficient to allow said region to rise above said ionosphere.

11. The method of claim **1** wherein said excitation of electron cyclotron resonance is carried out above about 500 kilometers and for a time of from 0.1 to 1200 seconds such that multiple heating of said plasma region is achieved by means of stochastic heating in the magnetosphere.

12. The method of claim **1** wherein said first electromagnetic radiation is right hand circularly polarized in the northern hemisphere and left hand circularly polarized in the southern hemisphere.

13. The method of claim **1** wherein said electromagnetic radiation is generated at the site of a naturally-occurring hydrocarbon fuel source, said fuel source being located in at least one of northerly or southerly magnetic latitudes.

14. The method of claim **13** wherein said fuel source is natural gas and electricity for generating said electromagnetic radiation is obtained by burning said natural gas in at least one of magnetohydrodynamic, gas turbine, fuel cell, and EGD electric generators located at the site where said natural gas naturally occurs in the earth.

15. The method of claim **14** wherein said site of natural gas is within the magnetic latitudes that encompass Alaska.

* * * * *

No. 887,357. PATENTED MAY 12, 1908.

N. B. STUBBLEFIELD.

WIRELESS TELEPHONE.

APPLICATION FILED APR. 5, 1907.

3 SHEETS—SHEET 1.



10
11
14
15
16
17
18
19
21
22
23
8
9
24

Fig. 1.



Fig. 3.



24
25
26
27
28
29
30
31
32

Fig. 2.

Witnesses

Jas. K. McCathran

B. G. Foster

Nathan B. Stubblefield, Inventor

By E. G. Siggers

Attorney

No. 887,357. PATENTED MAY 12, 1908.

N. B. STUBBLEFIELD.

WIRELESS TELEPHONE.

APPLICATION FILED APR. 5, 1907.

3 SHEETS—SHEET 2.


37
36
35
39
38
34
40
41
34
32
33
33
34
34
32
40
41
34

Fig. 4.

40
41
42
43
43
44

Fig. 5.

Witnesses

Jas. K. McCathran

B. G. Foster

Nathan B. Stubblefield, Inventor

By E. G. Siggers

Attorney

No. 887,357. PATENTED MAY 12, 1908.

N. B. STUBBLEFIELD.

WIRELESS TELEPHONE.

APPLICATION FILED APR. 5, 1907.

3 SHEETS—SHEET 3.


48
48
46
46
47
48
48
49
51
52
53
50

Fig. 6.


48
46
54
54
55
56
57
58

Fig. 7.

Witnesses
Jas. K. McCathran
B. G. Foster

Nathan B. Stubblefield,
Inventor

By E. G. Siggers
Attorney

UNITED STATES PATENT OFFICE.

NATHAN B. STUBBLEFIELD, OF MURRAY, KENTUCKY, ASSIGNOR OF TWELVE AND ONE-HALF ONE-HUNDREDTHS TO CONN LINN, FIVE ONE-HUNDREDTHS TO R. DOWNS, FIVE ONE-HUNDREDTHS TO B. F. SCHROADER, FIVE ONE-HUNDREDTHS TO GEORGE C. McLARIN, FIVE ONE-HUNDREDTHS TO JOHN P. McELRATH, TWO AND ONE-HALF ONE-HUNDREDTHS TO JEFF D. ROULETT, AND ONE-TWENTIETH TO SAMUEL E. BYNUM, ALL OF MURRAY, KENTUCKY.

WIRELESS TELEPHONE.

No. 887,357. Specification of Letters Patent. Patented May 12, 1908.

Application filed April 5, 1907. Serial No. 366,544.

To all whom it may concern:

Be it known that I, NATHAN B. STUBBLEFIELD, a citizen of the United States, residing at Murray, in the county of Calloway and State of Kentucky, have invented a new and useful Wireless Telephone, of which the following is a specification.

The present invention relates to means for electrically transmitting signals from one point to another without the use of connecting wires, and more particularly comprehending means for securing telephonic communication between moving vehicles and way stations.

The principal object of the invention is to provide simple and practical means of a novel nature whereby clear and audible communication can be established, said means being simple and of a character that will permit certain of the station mechanisms to be small and compact.

In the accompanying drawings:—Figure 1 is a perspective view, showing means for establishing communication between a vessel and a shore station. Fig. 2 is a diagrammatic view of the mechanism mounted on the boat. Fig. 3 is a cross sectional view on an enlarged scale of the shore coil. Fig. 4 is a perspective view of a road-way, showing a system for establishing communication between road vehicles and a way-station, the latter being illustrated diagrammatically. Fig. 5 is a detail view of a vehicle equipped with one of the instruments, which is shown diagrammatically. Fig. 6 is a perspective view showing the system applied to a railway for establishing communication between a moving train and a way-station. Fig. 7 is a sectional view through a car showing in diagram the car mechanism illustrated in Fig. 6.

Similar reference numerals designate corresponding parts in all the figures of the drawings.

Referring to the embodiment illustrated in Figs. 1, 2 and 3, a water-way 8 is disclosed, upon which a vessel 9 operates. Surrounding the path of travel of the vessel, and preferably elevated on poles 10, is a coil 11 of considerable magnitude. This coil, as shown in Fig. 3, consists of an outer casing 12, within which is placed a conducting wire comprising a plurality of convolutions 13, each of which is insulated from the other. The terminals 14 of this coil extend to a suitable way-station, and at the station is located a powerful source of electrical energy 15, to which is connected by a suitable wire 16 an electrically operated transmitter 17. The battery or other source of electricity has a connection 18 with one of the leads 14. A receiver 19 of the ordinary type has a connection with the same lead 14, to which the battery is connected, and both the receiver and transmitter have connections 21 with the contacts of a switch 22. This switch has suitable means, as for instance, a spring 23, which normally maintains the receiver in circuit with the coil 11, as will be evident by reference to Fig. 1, but if the switch is thrown to break the circuit, it will then cut in the source of electrical energy 15 and the transmitter 17.

An outfit similar to the above, is located on the vehicle or boat 9, but the coil 24 thereof, shown in Fig. 2, is much smaller. As further illustrated in said figure, the mechanism mounted on the boat, consists of a transmitter 25, and a battery or other source of electrical energy 26 electrically connected, as shown at 27 and having a connection 28 with one of the leads of the coil. The receiver 29 also has a connection 30 with said lead. A switch 31 is connected to the other lead, and is normally held in a position by a spring 32 to maintain a closed circuit through the receiver 29 and the coil, though it may be moved to cut out said receiver and close the circuit through the coil, the source of electrical energy and the transmitter.

In this system, if it is desired to transmit from one station, as for instance, the shore-station, the switch 22 is moved downwardly to cut out the receiver and throw in the transmitter and source of electrical energy, while the operator upon the boat or vehicle leaving the mechanism in the condition shown in Fig. 2, holds the receiver 29 to his ear. If therefore the operator at the shore-station uses the transmitter in the ordinary manner, a varying current corresponding to that passing through the coil of great magnitude 11, will be induced in the coil 24, and the speech or other sounds will thus be transmitted to the operator on the boat. By reversing the arrangement, speech may be transmitted from the boat to the shore station.

The use of coils for both stations, each coil consisting of a plurality of convolutions has been found by experience to be of the utmost value, and furthermore experience has demonstrated that the employment of coils of different magnitudes is of great importance, for it has been found that while two small coils can be used to transmit but a short distance, if one large coil of the character set forth is employed, the other may be very small, and speech or sounds can be transmitted comparatively great distances from one to the other. These sounds are clearly audible.

The structure disclosed in Figs. 4 and 5 is of the same general character. A road-way 32 is disclosed surrounded by a coil 33 of great magnitude that is supported on suitable poles 34. The way-station 35 consists of a transmitter 36, a source of electrical energy 37 connected thereto, a receiver 38, and a switch 39, whereby the receiver or the transmitter and source of electrical energy can be thrown into circuit with the coil 33. The vehicles 40, which operate on the roadway, are provided with smaller coils 41 and instruments consisting of receivers 42, transmitters 43, sources of electrical energy 44 and switches 45 all arranged in the manner already described. In a system of this kind, it will be evident that the occupant of one vehicle may telephone to the home or way-station, and the message can be transmitted to another vehicle. Thus it will be evident that communication can be established between two moving vehicles or between a way-station and any vehicle desired which is within the range of the home- or way-station. The system is also capable of use in connection with railways, and in Figs. 6 and 7, such a system is disclosed in connection therewith. A comparatively great coil 46 is supported on opposite sides of the railway 47 by poles 48 and a station 49 has a receiver 50 and a transmitter 51, a source of electrical energy 52 and a switch 53, the last mentioned being employed for throwing either the receiver or the transmitter and source of electrical energy into closed circuit with the coil 46. One or more cars of a railway train is equipped with an outfit consisting of a coil 54, a receiver 55, a transmitter 56, a source of electrical energy 57, and a switch 58 for throwing either the receiver or the transmitter and source of electrical energy into circuit with the coil 54. It will be evident that the operation of these two last described systems are substantially the same as that first set forth, and no extended description thereof is believed to be necessary.

From the foregoing, it is thought that the construction, operation, and many advantages of the herein described invention will be apparent to those skilled in the art, without further description, and it will be understood that various changes in the size, shape, proportion, and minor details of construction, may be resorted to without departing from the spirit or sacrificing any of the advantages of the invention.

Having thus fully described my invention, what I claim as new, and desire to secure by Letters Patent, is:—

1. In a system of the character described, the combination with a vehicle, of a comparatively small coil of conducting material mounted thereon, electrical transmitting and receiving mechanism including a source of electrical energy connected to the small coil and carried by the vehicle, a stationary aerial coil of much greater magnitude than the small coil having its opposite stretches or sides extending along the opposite sides of the path of travel of the vehicle and elevated above the same and above the vehicle coil, and electrical transmitting and receiving mechanism connected to the greater coil and including a source of heavy electrical current.

2. In a system of the character described, the combination with a vehicle, of a coil of conducting material mounted thereon, electrical transmitting mechanism, a source of electrical energy connected thereto, receiving mechanism, means for connecting either the transmitting mechanism and source of electrical energy or the receiving mechanism to the coil, a stationary coil of greater magnitude surrounding the path of travel of the vehicle and comprising a plurality of convolutions of conducting material, the different convolutions being insulated one from the other, means for supporting the coil in an elevated position, electrical transmitting mechanism, a source of great electrical energy connected to said transmitting mechanism, electrical receiving mechanism, and means for electrically connecting either the transmitting mechanism and source of electrical energy or the receiving mechanism to the said coil of greater magnitude.

3. Means for communicating between a plurality of stations which consists of an aerial electrical coil of great magnitude, means for supporting the said coil, a station electrically connected to the great coil and comprising transmitting and receiving mechanism that includes a source of heavy electrical energy, and a plurality of other separate stations simultaneously in coacting relation with the aerial coil, each of said latter stations comprising a coil of conducting material spaced from but in coacting relation with said great coil and below the same, and transmitting and receiving mechanism connected to said other coil and including a source of electrical energy.

4. Means for communicating between a plurality of stations which consists of an aerial coil of conducting material of great magnitude, transmitting and receiving mechanism connected to said aerial coil and including a source of heavy electrical energy, a plurality of vehicles movable between the opposite sides or stretches of the great coil, coils carried by said vehicles and disposed within the field of action of the aerial coil, and transmitting and receiving mechanism mounted on each vehicle and including a source of electrical energy.

In testimony, that I claim the foregoing as my own, I have hereto affixed my signature in the presence of two witnesses.

NATHAN B. STUBBLEFIELD.

Witnesses:
J. P. McElrath,
J. H. Coleman.

Russian Military Outposts

"The Russian Woodpecker"
Duga Radar Array, Chenobyl, Ukraine
51°18'20.17"N, 30°04'02.60"E



"Woodpecker" Duga radar array, Chenobyl, Ukraine

The Russian Woodpecker

Duga-3 array outside Chernobyl. The array of pairs of cylindrical/conical cages on the right are the driven elements, fed at the facing points with a form of ladder line suspended from stand-off platforms at top right. A back plane reflector of small wires can just be seen left of center, most clearly at the bottom of the image.

The Russian Woodpecker was a notorious Soviet signal that could be heard on the shortwave radio bands worldwide between July 1976 and December 1989. It sounded like a sharp, repetitive tapping noise, at 10 Hz, giving rise to the "Woodpecker" name. The random frequency hops disrupted legitimate broadcast, amateur radio, and utility transmissions and resulted in thousands of complaints by many countries worldwide.

The signal was long believed to be that of an over-the-horizon radar (OTH) system. This theory was publicly confirmed after the fall of the Soviet Union, and is now known to be the Duga-3[1] system, part of the Soviet ABM early-warning network. This was something that NATO military intelligence was well aware of all along, having photographed it and giving it the NATO reporting name Steel Yard.



"Woodpecker" Duga radar array, Chenobyl, Ukraine by Necator

Woodpecker - Woodpecker on shortwave radio interfering with WWVH, November 2, 1984.

History

The Soviets had been working on early warning radars for their anti-ballistic missile systems through the 1960s, but most of these had been line-of-sight systems that were useful for raid analysis and interception only. None of these systems had the capability to provide early-warning of a launch, which would give the defenses time to study the attack and plan a response. At the time the Soviet early-warning satellite network was not well developed, so work started on over-the-horizon radar systems for this associated role in the late 1960s.

The first experimental system, Duga-1, was built outside Mykolaiv in the Ukraine, successfully detecting rocket launches from Baikonur Cosmodrome at 2,500 kilometers. This was followed by the prototype Duga-2, built on the same site, which was able to track launches from the far east and submarines in the Pacific Ocean as the missiles flew towards Novaya Zemlya. Both of these radars were aimed east and were fairly low power, but with the concept proven work began on an operational system. The new Duga-3 systems used a transmitter and receiver separated by about 60 km.[2]



РЛС Дуга-1 Чернобыль-2 (Radar arch-1 Chernobyl-2) by DM.HANTER

Appearance

Starting in 1976 a new and powerful radio signal was detected worldwide, and quickly dubbed the Woodpecker by amateur radio operators. Transmission power on some woodpecker transmitters was estimated to be as high as 10 MW EIRP. As well as disrupting shortwave amateur radio and broadcasting it could sometimes be heard over telephone circuits due to the strength of the signals. This led to a thriving industry of "Woodpecker filters" and noise blankers.

One idea amateur radio operators used to combat this interference was to attempt to "jam" the signal by transmitting synchronized unmodulated continuous wave signals, at the same pulse rate as the offending signal. This idea was considered, but abandoned as impractical. Simple CW pulses didn't appear to have any effect. However, playing back recordings of the woodpecker transmissions sometimes caused the woodpecker transmissions to shift frequency leading to speculation that the receiving stations were able to differentiate between the "signature" waveform of the woodpecker transmissions and a simple pulsed carrier.[4]

Чорнобиль-2. Приймальні антени. (Chernobyl-2. RX antennas.) by djcrok

Identification

Triangulation quickly revealed the signals came from Ukraine. Confusion due to small differences in the reports being made from various military sources led to the site being alternatively located near Kiev, Minsk, Chernobyl, Gomel or Chernihiv. All of these reports were describing the same deployment, with the transmitter only a few kilometers southwest of Chernobyl (south of Minsk, northwest of Kiev) and the receiver about 50 km northwest of Chernobyl (just west of Chernihiv, south of Gomel). Unknown to most observers, NATO was well aware of the new radar installation, which they referred to as Steel Yard.

Even from the earliest reports it was suspected they were tests of an over-the-horizon radar., and this remained the most popular theory during the cold war. Several other theories were floated as well, including everything from jamming western broadcasts to submarine communications. The broadcast jamming theory was debunked early on when a monitoring survey showed that Radio Moscow and other pro-Soviet stations were just as badly affected by woodpecker interference as Western stations. More speculative explanations were also offered, claiming it was a system for weather control or even an attempt at mass subconscious mind control.

As more information about the signal became available, its purpose as a radar signal became increasingly obvious. In particular, its signal contained a clearly recognizable structure in each pulse, which was eventually identified as a 31-bit pseudo-random binary sequence, with a bit-width of 100 µs resulting in a 3.1 ms pulse. This sequence is usable for a 100 µs chirped pulse amplification system, giving a resolution of 15 km (10 mi) (the distance light travels in 50 µs). When a second Woodpecker appeared, this one located in eastern Russia but also pointed toward the US and covering blank spots in the first system's pattern, this conclusion became inescapable.

In 1988, the Federal Communications Commission conducted a study on the Woodpecker signal. Data analysis showed an inter-pulse period of about 90 ms, a frequency range of 7 to 19 MHz, a bandwidth of 0.02 to 0.8 MHz, and typical transmission time of 7 minutes.

- **The signal was observed using three repetition rates: 10 Hz, 16 Hz and 20 Hz.**
- **The most common rate was 10 Hz, while the 16 Hz and 20 Hz modes were rather rare.**
- **The pulses transmitted by the woodpecker had a wide bandwidth, typically 40 kHz.**

Пропускной пункт на территорию РЛС (Checkpoint to the territory of the radar) - by Alex Taranenko

Disappearance

Starting in the late 1980s, even as the FCC was publishing studies of the signal, the signals became less frequent, and in 1989 disappeared altogether. Although the reasons for the eventual shutdown of the Duga-3 systems have not been made public, the changing strategic balance with the fall of the cold war in the late 1980s likely had a major part to play. Another factor was the success of the US-KS early-warning satellites, which entered preliminary service in the early 1980s, and by this time had grown into a complete network. The satellite system provides immediate, direct and highly secure warnings, whereas any radar-based system is subject to jamming, and the effectiveness of OTH systems is also subject to atmospheric conditions.

According to some reports, the Komsomolsk-na-Amure installation in Siberia was taken off combat alert duty in November 1989, and some of its equipment was subsequently scrapped. Google Maps photography of the area shows that the antenna has been removed. The original Duga-3 site lies within the 30 kilometer Zone of Alienation around the Chernobyl power plant. It appears to have been permanently deactivated, since their continued maintenance did not figure in the negotiations between Russia and Ukraine over the active early warning radars at Mukachevo and Sevastopol. The antenna still stands, however, and has been used by amateurs as a transmission tower (using their own antennas) and has been extensively photographed.

УВАГА!
ВЇЗД НА ТЕРИТОРІЮ БЕЗ ДОЗВОЛУ
КАТЕГОРИЧНО ЗАБОРОНЕНО!
ТЕРИТОРІЯ ДСП КОМПЛЕКС

Warning Sign and Antennas by markus_online_world

Positions

Duga-1 and -2, Nikolayev, 47°02′28.33″N, 32°11′57.29″E
Duga-3, Gomel/Minsk, (Chernobyl-2) 51°18′19.06″N, 30°03′57.35″E and 51°38′15.98″N, 30°42′10.41″E
Duga-3, Komsomolsk-na-Amure, 50°53′34.66″N, 136°50′12.38″E and 50°23′07.98″N, 137°19′41.87″E



РЛС / Radar station by Alex Taranenko

Appearances in media

The Ukrainian-developed computer game S.T.A.L.K.E.R has a plot focused on the Chernobyl Nuclear Power Plant and the nuclear accident there. The game heavily features actual locations in the area, including the Duga-3 array. It is presented as the "Brain Scorcher", a wide-area mind control device which must be deactivated by the player.

References:

1. **The Russian word "duga" means "arc" in English.**
2. **Sean O'Connor. Russian Strategic Defense - Part 2, The ABM Network**
3. **Dave Finley (7 July 1982). "Radio hams do battle with 'Russian Woodpecker'". *The Miami Herald***
4. **David L. Wilson (Summer 1985). "The Russian Woodpecker... A Closer Look". *Monitoring Times***
5. **"Mystery Soviet over-the-horizon tests". *Wireless World*: 53. February 1977**
6. **J.P. Martinez (April 1982). "Letter from J. P. Martinez". *Wireless World*: 89**

Further reading

- **Headrick, James M., Looking over the horizon , IEEE Spectrum, pp. 36 - 39 (July 1990).**
- **Headrick, James M. and Skolnik, Merrill I., Over-the-horizon radar in the HF band, Proceedings of the IEEE, vol. 62, no. 6 pp. 664 - 673 (June 1974).**
- **Headrick, James M., Ch. 24: "HF over-the-horizon radar," in: Radar Handbook, 2nd ed., Merrill I. Skolnik, ed. [New York: McGraw-Hill, 1990].**
- **Kosolov, A. A., ed. Fundamentals of Over-the-Horizon Radar (translated by W. F. Barton) [Norton, Mass.: Artech House, 1987].**

External links

- **Chernobyl-2. Sercet Military Facility in the territory of exclusion zone. Text and photos 2008**
- **OTH-Radar "Chornobyl - 2" and Center of space-communication**
- **"Circle" is an auxiliary system for OTH-Radar "Chornobyl - 2"**

- **The Russian Woodpecker, *Miami Herald*, July 1982.**
- **Steel Yard OTH, globalsecurity.org**
- **Sound clip of Russian Woodpecker interfering with WWVH time station, November 1984 (Wikimedia Commons)**
- **Some pictures of Chernobyl-2**
- **Images of the Gomel installation.**

Retrieved from http://en.wikipedia.org/wiki/Russian_Woodpecker



Чорнобиль-2. Приймальні антени. (Chernobyl-2. RX antennas.) by djcrok

Чорнобиль-2. Приймальні антени (Chernobyl-2. Receiving Antenna) by djcrok

Чорнобиль-2. (Chernobyl-2.) by djcrok



Чорнобиль-2. Приймальні антени. (Chernobyl-2. RX antennas.) by djcrok

Чорнобиль-2. Приймальні антени. (Chernobyl-2. RX antennas.) by djcrok



Чорнобиль-2. Приймальні антени. (Chernobyl-2. RX antennas.) by djcrok



Чорнобиль-2. Приймальні антени. (Chernobyl-2. RX antennas.) by djcrok

Дуга (Arc) by A.Miched

СОВЕТСК
WWW.KRANZ.COM.UA

Чорнобиль-2. Залишки соціалізму. (Remains of socialism.) by djcrok



Чорнобиль-2. Залишки соціалізму. (Remains of socialism.) by djcrok

www.kranz.com.ua

http://www.kranz.com.ua/oth_radar_chornobyl2_R.htm

http://www.kranz.com.ua/report/oth_radar_chornobyl2_52.htm

FAIR USE NOTICE: This page contains copyrighted material the use of which has not been specifically authorized by the copyright owner. Pegasus Research Consortium distributes this material without profit to those who have expressed a prior interest in receiving the included information for research and educational purposes. We believe this constitutes a fair use of any such copyrighted material as provided for in 17 U.S.C § 107. If you wish to use copyrighted material from this site for purposes of your own that go beyond fair use, you must obtain permission from the copyright owner.

~ MENU ~

Webpages © 2001-2016
Blue Knight Productions

FIP8102 XR 3,273,066

X5264R

Sept. 13, 1966 L. H. RUHNKE 3,273,066

APPARATUS FOR DETECTING CHANGES IN THE ATMOSPHERIC ELECTRIC FIELD

Filed Dec. 20, 1963 2 Sheets-Sheet 1

Fig. 1



14
30
24
22
20
12
Pressure Sensor
18
Transmitter
Block. Oscill.
16
26
28
34
32
Receiver -36-
Recorder -38-

Fig. 3



24
26
R1
R2
R3
66
C
64
64
62
62
Temperature Channel
Humidity Channel

INVENTOR:
Lothar H. Ruhnke

By Alan C. Rose
Attorney

Sept. 13, 1966 L. H. RUHNKE 3,273,066

APPARATUS FOR DETECTING CHANGES IN
THE ATMOSPHERIC ELECTRIC FIELD

Filed Dec. 20, 1963

2 Sheets-Sheet 2

Fig. 2


46
44
42
50
48
14
12
Cloud Detector,
Ascending
Recording
Sample
Voltage Gradient
vs
Altitude
Ground
Station
~32~
Volts/Unit Distance

INVENTOR:
Lothar H. Ruhnke

By Alan C. Rose
Attorney

3,273,066
Patented Sept. 13, 1966

3,273,066

APPARATUS FOR DETECTING CHANGES IN THE ATMOSPHERIC ELECTRIC FIELD

Lothar H. Ruhnke, Minneapolis, Minn., assignor to Litton Systems, Inc., Beverly Hills, Calif.

Filed Dec. 20, 1963, Ser. No. 332,186
4 Claims. (Cl. 325—113)

This invention relates to a cloud detector or an apparatus for sensing electrostatic conditions in the earth's atmosphere.

Cloud detection apparatus which is presently employed is usually of the "ceilometer" type which merely measures the height of the lower surface of the clouds to indicate the ceiling conditions. One object of the present invention is to determine the location of both the top and the bottom of one or more cloud formations of the atmosphere.

While electrostatic sensors of one type or another have been proposed heretofore for use in the atmosphere, they have been so complex and expensive that they have not enjoyed widespread use. In addition, cloud radars have recently been developed, but their usefulness is limited by failures when different zones of the atmosphere contain droplets of different sizes, as discussed more fully below. Accordingly, it is another object of the present invention to simplify and reduce the cost of cloud detectors, while maintaining reliability, compatibility with existing equipment, and adequate sensitivity for all practical purposes.

In accordance with an illustrative embodiment of the present invention, a conventional U.S. Weather Bureau or U.S. Army meteoroligical radiosonde transmitter may be provided with a modulator which is controlled by a field effect transistor. The input to the field effect transistor is a dipole antenna. Each of the arms of the dipole antenna may be five to fifty feet in length, for example, and one of the dipole elements may trail the radiosonde package while the other element may extend forward in the direction of movement of the unit. When a balloon is employed to carry the cloud detector unit aloft, a weight may be attached to one of the antenna elements so it hangs below the instrument package, while the other antenna element can extend along, or even form the flexible connection between the radiosonde unit and the balloon. A receiving unit is provided to pick up the modulated signals from the radiosonde apparatus, demodulate these signals and record them. While it is contemplated that the receiver may normally be situated on the ground and receive signals from a rising radiosonde unit, the radiosonde unit could well be employed by an aircraft to determine conditions below a cloud layer. Under these conditions the receiver would be mounted on the plane and the radiosonde unit could be parachuted to the ground.

In accordance with a feature of the present invention, therefore, a system for detecting electrostatic field conditions in the atmosphere includes a transmitter, arrangements for moving the transmitter through the atmosphere, an antenna extending a substantial distance from the transmitter, and a field effect transistor connected to receive electrostatic input signals from said antenna and to modulate the output of the transmitter in accordance with voltages detected by the antenna.

In accordance with one aspect of the present invention, simplicity of circuitry and stability of operation are achieved by the use of dynamic circuitry which measures the instantaneous difference in potential between two antenna elements. Thus, a high input resistor may be connected between the input antenna elements. With this type of arrangement the instrument package must be continuously moved through the atmosphere in order to give meaningful results. Under these conditions, the recorded output indicates changes in electric fields. A constant electric field, corresponding to a linear change in potential produces no substantial output signal. It has been determined that a balloon velocity of about five meters per second will produce good results with a dipole antenna shunted by a 1,000 megohm resistor and connected to a field effect transistor as discussed in detail in the present specification. With lower velocities, a higher input impedance or greater amplification would be required, with higher velocities, such as rocket propulsion or the like, permitting even lower input impedances and simpler input circuits.

Accordingly, it is a feature of the invention that apparatus is provided for moving a radiosonde unit through the atmosphere at a predetermined rate, that two element input antenna preferably of the dipole type is provided, and that the antenna is connected to the radiosonde by simple dynamic amplification circuitry, which requires continuous movement of the apparatus to give useful output information.

The novel features which are believed to be characteristic of the invention both as to its organization and method of operation, together with further objects and advantages thereof, will be better understood from the following description considered in conjunction with the accompanying drawings in which a typical embodiment of the invention is illustrated by way of example. It is to be expressly understood, however, that the drawings are for the purpose of illustration and description only and are not intended as a definition of the limits of the invention.

In the drawing:

FIG. 1 is a schematic block diagram of a radiosonde equipment for sensing changes in the electric field of the atmosphere, and thus detecting clouds, in accordance with the present invention;

FIG. 2 is a diagrammatic showing of the record obtained under typical cloud conditions; and

FIG. 3 is a circuit diagram indicating a typical arrangement of connections of a dipole antenna, a field effect transistor, and the input terminals of a standard meteorological radiosonde apparatus.

With reference to the drawings, FIG. 1 shows a radiosonde package **12** supported by a balloon **14**. The radiosonde unit includes a transmitter **16**, blocking oscillator **18**, pressure sensor **20**, and a field effect transistor unit **22**. A dipole antenna having an upper element **24** and a lower element **26** is connected to the input of the field effect transistor unit **22**. A small weight **28** is secured to the lower end of the antenna element **26** to hold it in the extended position. Similarly, the upper antenna element **24** extends in the other direction, and it may either form the support for the radiosonde unit **12** or may be closely associated with the supporting cable. A parachute **30** is provided for safe return of the instrument package to ground.

A ground or receiving station **32** may include an antenna **34**, receiver and demodulator **36**, and a recording apparatus **38**.

FIG. 2 shows a typical recording of the electrostatic field obtained as the ballon **14** and instrument package **12** rise through the successive layers of clouds **42**, **44**, and **46**, along the center line of the drawing. It is known that the electrostatic potential in the atmosphere increases from ground potential to plus 300,000 volts at elevations of about 30 miles. It is also known that the atmospheric electric field, which is the gradient of the potential, is substantially increased within clouds. As the package enters the lower edge of a cloud, the sudden increase in electric field causes a pulse of current to flow through resistor R_1 in one direction, and upon leaving the cloud, the sudden reduction in electric field causes an oppositely directed current pulse. This produces the positive swing shown at **48** in FIG. 2 as the unit enters the cloud and the negative peak **50** as the apparatus is rising through the upper surface of the cloud stratus **42**. A similar pattern is observed as the unit goes through the higher cloud formations **44** and **46**. With a knowledge of the speed of ascent of the balloon and instrument package, the location of the upper and lower surfaces of successive cloud layers may be determined by the present apparatus. Accordingly, despite the presence of a relatively low cloud layer which completely obscures other cloud formations, ground personnel may readily determine the meterological conditions relating to clouds above this low ceiling.

Returning to FIG. 1, the radiosonde equipment represented by blocks **16**, **18** and **20** is well known. The meterological radiosonde system which will be taken as typical is designated by the military by the numbers AN/AMT 4B. The Army technical manual which describes this radiosonde system is identified as TM 11–2432A–TO 31M4–2AMT–11, dated June 26, 1958. The radiosonde transmitter operates at a frequency of 1680 megacycles per second. This transmitter is modulated by a blocking oscillator **18**, the frequency of the blocking oscillator being controlled by the meteorological conditions which are detected. Normally, a thermistor for measuring the temperature and a humidity sensor are alternately switched to the input terminals of the blocking oscillator **18**. In the present case, the cloud detector circuitry is connected to both of these terminals. The barometric pressure sensor **20** may also be retained in the unit, and it may be connected to control the frequency of the blocking oscillator **18** by a switching action as described below.

With reference to FIG. 3, the humidity channel input terminals **62** and the temperature channel input terminals **64** of the standard radiosonde unit are shown at the right-hand side of the circuit. Atmospheric electric signals received by the dipole antenna elements **24** and **26** are applied to the field effect transistor **66** and are then coupled by a suitable circuit to the input terminals **62** and **64** of the radiosonde. While other field effect transistors may be employed, type C 610 of Crystallonics, Inc., was found to be suitable from a sensitivity and reliability standpoint for the present purposes. The input to the field effect transistor is shunted by a 1,000 megohm resistor R_1 to stabilize the input characteristic. Suitable biasing of the transistor **66** is provided by resistor R_3. Because the impedance of the transistor **66** is substantially lower than that of the temperature and humidity sensors which are normally employed, a 110,000 ohm resistor in the blocking oscillator was removed and a capacitor C was connected in parallel to the input terminals. The capacitor was selected to produce a modulation frequency of approximately 100 cycles per second in the absence of an input signal. Positive and negative voltages will then raise or lower this frequency.

In the radiosonde apparatus, signals from the pressure sensor **20** are normally employed to switch from the temperature channel terminals **64** to the humidity channel terminals **62**. This switch is well known in the art as a baroswitch. The barometric pressure switching action provides an indication of altitude, so it is useful to preserve this information. Accordingly, the resistor R_2 is employed between the transistor **66** and one terminal **64** to reduce the output signal slightly, thus changing the modulation level and preserving the pressure and thus altitude information.

With regard to the length of the dipole elements **24** and **26**, the size of resistor R_1 and the amplification of the field effect transistor, these are fixed by several factors. First, the antenna elements should be large enough to provide a substantial input signal, but should be relatively small as compared with normal cloud thicknesses. Lengths of 5 to 50 feet for each dipole would be of the proper order of magnitude. The resistor R_1 was chosen to reduce the input impedance between dipoles **24** and **26** below the point where fog and dampness and the resultant shunt impedance will introduce instability into the transmitted signals. With these parameters, and a speed of ascent of the order of 5 meters per second, it was determined that a single field effect transistor provided the necessary amplification for operation with the standard radiosonde unit.

As mentioned generally above, cloud radars are subject to failure under certain atmospheric conditions. Thus, the radar return is proportional to the sixth power of the droplet or particle size, while the human eye and optical systems respond to the second power of the droplet size. With the radar return proportional to such a high power of the droplet diameter, if a radar is adjusted to pick up a cloud having large particles, other clouds having small size particles are not detected. The present electrostatic system, however, responds in a manner which is nearly the same as the optical response, and therefore does not fail under atmospheric conditions where different size droplets or particles are present in successive clouds.

It is to be understood that the above described arrangements are illustrative of the application of the principles of the invention. Numerous other arrangements within the scope of the invention may be devised by those skilled in the art. Thus, by way of example and not of limitation, a somewhat different shape of antenna could be employed to pick up electrostatic field variations and apply them to the field effect transistor, an inherently stabilized transistor may be used, and the instrument package may be carried by rocket or other suitable propulsion arrangements than the balloon shown in the drawings. Accordingly, it is evident that various changes may be made in the present invention without departing from the spirit of the invention as defined in the present claims.

What is claimed is:

1. An apparatus for sensing electrostatic conditions in the atmosphere comprising:

a radiosonde apparatus including means for modulating the output frequency thereof, said means including an R-C circuit;

a pair of probes positioned in respectively different locations in the atmosphere with respect to said radiosonde;

a field effect transistor having its drain and gate terminals connected across said pair of probes and having its source and drain terminals connected in series with the resistance of said R-C circuit to modulate said radiosonde; and

a stabilizing high resistance connected across the two probes and across said gate and drain terminals of said transistor.

2. In an apparatus for sensing atmospheric electrostatic field conditions;

a balloon;

an instrument package connected to and spaced from said balloon, said instrument package including a transmitter, means including an R-C circuit for modulating said transmitter, and a field effect transistor having source and drain terminals connected in series with the resistance in said R-C circuit to modulate said transmitter;

antenna means including an antenna and resistance means connected across said antenna, said resistance means also being connected across the gate and the drain of said field effect transistor, said antenna extending upward from said package toward said balloon and downwardly from said package for applying signals to said field effect transistor in response to said field conditions to render said modulating means responsive to said field conditions.

3. An apparatus for sensing changes of the atmospheric electric field at cloud boundaries, which comprises:

a blocking oscillator-type modulated radiosonde including fixed resistance means and capacitance means connected in parallel with said fixed resistance means, said capacitance means being effective to discharge through said resistance means to control the modulation of said radiosonde;

dipole antenna means responsive to changes of the atmospheric electric field for producing a signal indicative of said changes;

resistance means connected across said dipole antenna means; and

a field effect transistor having source and drain terminals connected in series with said fixed resistance means and a gate terminal connected to said dipole antenna means for reception of said signal, said field effect transistor being responsive to said signal for varying the rate of discharge of said capacitance means to cause the blocking oscillator to modulate said radiosonde in accordance with the second changes in the atmospheric electric field.

4. An apparatus for sensing changes of the atmospheric electric field at cloud boundaries, which comprises:

radiosonde means including a blocking oscillator having fixed resistance means and capacitance means connected in parallel with said fixed resistance means, said capacitance means being effective to discharge through said resistance means to control the frequency of oscillation of said blocking oscillator;

dipole antenna means responsive to changes of the atmospheric electric field for producing a signal indicative of said changes;

resistance means connected across said dipole antenna; and

a field effect transistor having source and drain terminals connected in series with said fixed resistance means and a gate terminal connected to said dipole antenna means for reception of said signal, said field effect transistor being responsive to said signal for varying the rate of discharge of said capacitance means to control the frequency of oscillation of said blocking oscillator in accordance with the sensed changes in the atmospheric electric field.

References Cited by the Examiner

UNITED STATES PATENTS

2,463,527	3/1949	Dunmore	325—113
3,038,154	6/1962	Zworykin et al.	325—113 XR
3,056,888	10/1962	Atalla	307—88
3,062,043	11/1962	Marsh et al.	340—193.2

DAVID G. REDINBAUGH, *Primary Examiner.*

JOHN W. CALDWELL, *Examiner.*

United States Patent [19]

Gundlach

[11] **Patent Number: 4,595,852**

[45] **Date of Patent: Jun. 17, 1986**

[54] **ELECTROSTATIC GENERATOR**

[76] Inventor: **Robert W. Gundlach,** 2434 Turk Hill Rd., Victor, N.Y. 14564

[21] Appl. No.: **599,199**

[22] Filed: **Apr. 11, 1984**

[51] **Int. Cl.⁴** **H02N 1/00**

[52] **U.S. Cl.** **310/309**

[58] **Field of Search** 310/308–310

[56] **References Cited**

U.S. PATENT DOCUMENTS

2,610,994	9/1952	Bosch et al.	310/309
2,644,903	7/1953	Lehrer	310/307
2,739,248	3/1956	Meier	310/309
2,756,352	7/1956	Felici et al.	310/308 X

Primary Examiner—Donovan F. Duggan

[57] **ABSTRACT**

A novel induction-type electrostatic generator is disclosed in which moving electrodes are transported back and forth between two Faraday cages. Each moving electrode, once enclosed by a cage, is contacted to the cage, then separated by more than the sparking distance before making electrical connection to the opposite moving electrode or to ground. In this way, charge opposite in polarity but proportional in magnitude to the charge on each cage, is induced in each moving electrode and carried into and imparted onto the next cage, progressively elevating the cage potentials until the corona or arcing limits are reached. Initiation of charging is spontaneous, deriving from inevitable statistical imbalances in nature.

5 Claims, 4 Drawing Figures




30
+
26
31
20
22
25
+
23
24
20
29
28

PRIOR ART

FIG. 1


62
63
64
65
66
60
64
61

FIG. 3



FIG. 2a



FIG. 2b

ELECTROSTATIC GENERATOR

BACKGROUND OF THE INVENTION

This invention relates to electrostatic generators, and more particularly to an improved induction-type electrostatic generator that is efficient, compact, and inexpensive, in which electrodes are transported back and forth between two Faraday cages.

The Greeks were the first to record observations of static electricity several thousand years ago. They discovered that amber, when rubbed vigorously with fur or fabrics under dry conditions, takes on electrostatic charge. In fact, the Greek word for amber, "electron", has become the root of many of our words relating to electricity.

It was not until about 1660 that the first electrostatic generator was invented. Otto von Guericke of Magdeburg, Germany showed electrostatic sparks could be produced by spinning and rubbing a dry sulfur globe. In this device, high potentials were developed by friction, or triboelectric charging. More than 200 years passed before James Wimshurst invented the first reliable induction-type generator, called the "influence machine" at the time (1878). This involved two insulating discs sliding against each other as they rotated in opposite directions on a common axis. Attached to these oppositely rotating plates were metal sectors into which charges are induced and carried to a capacitor for storage. The metal sectors continue inducing opposite charges in each other and carrying the charges to the appropriate ends of the capacitor, gradually building up the potentials of the capacitor until sparking voltages are reached. Wimshurst built many such machines, some with oppositely rotating discs more than two meters in diameter. The only substantial application of the Wimshurst generator appears to have been to operate the early X-ray tubes.

Then, in 1937, Robert Van de Graaff invented a belt-type generator in which an insulating belt, sometimes carrying conducting elements, transported charges into a giant conducting sphere, or "Faraday cage", to generate, in some cases, over a million volts. Van de Graaff charged the moving belt by spraying corona charge onto it or, alternatively, by frictionally charging it.

In the 1960's Prof. A. D. Moore designed an induction-type generator for instructional purposes. This is the simplest of the prior art generators to understand, and works purely by induction, requiring neither corona nor frictional charging means to produce the potential differences. FIG. **1** is a schematic diagram of Moore's "Dirod" generator, which he described in his book "Electrostatics", (Doubleday, Garden City, NJ, 1968; a Doubleday Anchor Book). In this generator, rods $\mathbf{20}_{(1\rightarrow N)}$ are rotated between two collector electrodes, **22** and **24**. Each rod makes momentary electrical contact to collectors **22** and **24** through flexible conducting brushes **23** and **25**, respectively, as insulating disk **26** is rotated counterclockwise about its center. Just above and below rotating disc **26** are supported conducting rods **28** and **30**, called "inductors", electrically connected to collector electrodes **22** and **24**, respectively. At the point of nearest approach to each inductor, each of the rods $\mathbf{20}_n$ is momentarily contacted, one at a time, to ground or to the opposite rod $\mathbf{20}_{(n+N/2)}$ through flexible conducting brushes **29** and**31**, respectively. Any incipient charge or potential difference between collector electrodes **22** and **24** will induce opposite charges in those rods $\mathbf{20}_n$ and $\mathbf{20}_{(n+N/2)}$ adjacent the inductors **28** and **30**. For example, if we assume that, of the many billions of electrons in each of the collector electrodes, there is a slight excess in collector **22**, then collector **24** will be slightly positive relative to collector **22**. Inductor **28** will therefore induce positive charges in each rod $\mathbf{20}_n$ as it is grounded in its proximity to inductor **28**. At the same time inductor **30** induces negative charges in each rod $\mathbf{20}_{(n+N/2)}$ when grounded next to inductor **30**. As the charged rods separate from inductor rods **30** and **28**, their potentials increase so that part of the induced charges flow off to the collector plates **22** and **24**, increasing their negative and positive potentials, respectively. As the potentials of the collector electrodes increase, so the charges induced in rods $\mathbf{20}_n$ by inductors **28** and **30** increase, quickly driving the collector electrodes to their maximum values. Once charging begins it will be seen how the potential difference grows at a progressively increasing rate. The statistical imbalance of nature insures that the initial imbalance can always be depended on. (To understand how the instability builds on itself, we need only understand why a sharpened pencil cannot be balanced long on its point; the restoring force is negative, and is proportional to the degree of imbalance.) Professor Moore's Dirod generator routinely produces 60 to 70 kV, depending on the spacing of the rods **20** from inductors **28** and **30**, since air breakdown (arcing) occurs at about 30 kV per cm for gaps larger than a few millimeters. This generator is not entirely satisfactory for manufacturing as an educational toy or for use for demonstrations because it is relatively complicated and expensive to produce and complex to understand.

SUMMARY OF THE INVENTION

Accordingly, the present invention provides a simplified electrostatic generator for an educational toy. Also, the present invention provides an electrostatic generator that is more efficient, more affordable, more rugged, and easier to understand for teaching purposes and experimental uses than prior art devices.

The foregoing and other features of the instant invention will be more apparent from a further reading of the specification and claims and from the drawings, in which:

FIG. **1** is a schematic plan view of a prior art generator.

FIG. **2***a* is a schematic plan view of the preferred embodiment of the present invention.

FIG. **2***b* is an isometric view of the preferred embodiment of the present invention.

FIG. **3** shows an alternative embodiment of the present invention that employs a single mobile electrode.

While the invention will be described hereinafter in connection with a preferred embodiment and an alternative embodiment, it will be understood that it is not intended to limit the invention to those embodiments. On the contrary, it is intended to cover all alternatives, modifications, and equivalents as may be included within the spirit and scope of the invention as defined by the appended claims.

DESCRIPTION OF THE PREFERRED EMBODIMENT

In the pesent invention the induction-type generator has been simplified and made much more efficient by combining each pair of collector and inductor electrodes into a single Faraday cage, as shown in FIGS. 2*a* and 2*b*. As Faraday taught, and Van de Graaff put to use, by enclosing a charged object in a conducting cage, the potential of the whole cage is increased as if all the charges were placed onto the cage, itself. In fact, if the enclosed charged object is conducting and makes conductive contact with the cage, all charges do, indeed, flow from the charged object onto the surrounding "Faraday cage".

In this example only two rotor electrodes **40***a* and **40***b* are shown. In fact, any even number can be used, within practical space limitations. An odd number could be used if external ground is provided during charge induction. With an even number of rotor electrodes, contacts **48** and **50** can be connected to each other, instead of to external ground, to induce electrons from one rotor electrode to the other. Rotor electrode **40***a* is transported by clockwise rotation from one cage **42**, to the other cage **44**, making sequential contact first with the surrounding, or enclosing case, through contact post **43**, then, after adequate separation from contact post **43**, making momentary contact with ground or the opposite rotor electrode **40***b* through contact posts **50** and **48**, whereby charges opposite to those on the enclosing cage are induced on each rotor plate and then transported to the opposite cage through brushes **49** and **51**. This results in a progressive build-up of opposite electrostatic potentials on collector cages **42** and **44**. Assuming thin, flat rotor plates **40**, the capacitance of each rotor plate **40** to the shell or cage **42** when the plate is totally enclosed by the cage is given by:

$$C = \frac{K\epsilon_0 A}{t}$$

where C is capacitance, K is the dielectric constant of the medium (K=1 for air), ϵ_o is the permittivity of space ($\epsilon_o = 9\times10^{-12}$), A is the area of the surface of the rotor plate, and t is the distance between the rotor plate **40** and the inner surface of the shell **42**. Each plate carries a charge q out of one shell and into the other shell every half rotation, equal to:

$$q = CV.$$

It is possible, then, to calculate the current that can be supplied by this generator for any specified values of rotor plate area A, distance t between the rotor plate **40** and the parallel surface of the cage **42**, and speed of rotation of the rotor plates.

$$i = \frac{dq}{dt} = 4\omega CV$$

where ω is the spin velocity in rotations per second. For example, an area of 100 cm^2 on each face of the rotor plate ($A = 2\times10^{-2}$m^2), and a plate-to-cage spacing of 1 cm ($t = 10^{-2}$m), and a spin velocity of ten rotations per second, gives a generator current of:

$$i = 40\ CV = 40 \times \left(\frac{9\times10^{-12}\times2\times10^{-2}}{10^{-2}}\right) V = 7.2\times10^{-10}\ V\ \text{amperes}$$

Clearly, then, current is very low for very low voltages, but builds exponentially with time, the initial voltage build-up can be expedited by placing a charged object on one of the cages. Once the maximum potential of, say, 20 kV is reached, the generator of this example of the present invention would produce a current of:

$$i = 1.4\times10^{-5}\ \text{amperes, or about } 14\ \mu A$$

FIG. **3** shows another embodiment of the present invention. Here a single mobile electrode **60** is mounted on a hinge **61** and swings reciprocally between Faraday cages **62** and **64**. In this figure, the top plate of each cage **62** and **64** has been removed for clarity. Movable electrode **60** enters either cage **62** or **64**, makes conducting contact with said cage, separates from said conducting contact by more than the sparking distance (1 cm for every 30 kV), and then makes the electrical contact to ground while it is still enclosed by said cage. During grounding, charges opposite to the charge on the enclosing cage are induced in electrode **60**, and these are transported by movable electrode **60** into and deposited onto the opposite Faraday cage. Swinging contacts **63** and **65** prevent electrical contact between movable plate **60** and ground during entry of plate **60** to each cage, while they insure contact with conducting edges **64** and **66** during exit, while plate **60** is still fully enclosed within the associated Faraday cage. Since the charges induced on movable plate **60** are proportional to the charges on the enclosing cage, repeating the cyclic process produces progressively increasing potentials until corona or sparking limits are reached.

In summary, the advantages of the electrostatic generator of the present invention are its elegant simplicity for construction, for providing a simple understanding for the student, its ruggedness of design for portability without damage, affordability of cost, and its high efficiency derived by maximizing the rotor area and thus capacitance, for a given spacing, the spacing determining the inherent limitation of voltage imposed by dielectric breakdown of air or other fluid medium in which the generator is operated. If we wish to develop potentials of 30 kV operating in air, for example, the spacing of rotors **40** to cages **42** must be at least one cm, since the dielectric breakdown of air for such gaps is 30 kV/cm.

While the principles described herein have been described by the example of FIGS. 2*a*, 2*b*, and **3**, it should be understood that the concepts disclosed can be embodied in various mechanical designs without departing from the teachings of this invention and may come within the scope of the following claims.

What is claimed is:

1. A spontaneous non-frictional electrostatic induction-type generator, comprising:

(a) two Faraday cages:

(b) electrode means, substantially surrounded by and mounted for rotary movement relative to said Faraday cages in order to enable said Faraday cages to serve alternately as both the inductor and collector electrodes: and

(c) flexible contact means comprising a single set of brushes mounted to said rotary electrode means so as to extend by centrifugal force into electrical contact with said Faraday cages, then, after separating from each cage by more than the sparking distance, momentarily contacting each said flexible contact means to ground or to opposite ends of a conductor connecting said flexible contact means to each other to progressively charge said Faraday cages.

2. The spontaneous non-frictional electrostatic induction-type generator of claim 1, wherein said electrode means comprises an even number of movable electrodes, and flexible contact means mounted for centrifugal extension to make momentary electrical contact separately to each cage; then, after separating from each cage by more than the sparking distance, momentarily connecting said movable elctrodes to each other.

3. The method of claim 1, wherein an even number of rotary movable electrodes is provided, and means, mounted for extension by centrifugal force, is provided for contacting said rotary movable electrodes separately to each Faraday cage, then, after separating from each cage by more than the sparking distance, momentarily connecting said rotary movable electrodes to each other.

4. The spontaneous electrostatic induction-type generator of claim 1, wherein said electrode means comprises a plurality of movable electrodes.

5. A method of generating high electrostatic potentials using a spontaneous, non-frictional electrostatic induction-type generator comprising the steps of:

(a) providing two Faraday cages;

(b) providing electrode means substantially surrounded by and mounted for rotary movement relative to said Faraday cages; and

(c) providing flexible contact means mounted to said rotary electrode means so as to extend by centrifugal force into electrical contact with each cage separately, then, after separating from each cage by more than the sparking distance, momentarily contacting to ground or to a neutral conductor, in order to progressively charge said Faraday cages.

* * * * *

US007855476B2

(12) **United States Patent**
Ogram

(10) **Patent No.: US 7,855,476 B2**
(45) **Date of Patent: Dec. 21, 2010**

---

(54) **ATMOSPHERIC ELECTRICAL GENERATOR**

(76) Inventor: **Mark Ellery Ogram**, 780 S. Freeman Rd., Tucson, AZ (US) 85748

(*) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 254 days.

(21) Appl. No.: **12/218,297**

(22) Filed: **Jul. 14, 2008**

(65) **Prior Publication Data**

US 2010/0007218 A1 Jan. 14, 2010

(51) **Int. Cl.**
H02G 11/00 (2006.01)

(52) **U.S. Cl.** **307/145**; 307/149; 361/218; 361/230

(58) **Field of Classification Search** 307/149, 307/145; 244/30, 31; 174/2; 361/212, 215–218, 361/230, 231
See application file for complete search history.

(56) **References Cited**

U.S. PATENT DOCUMENTS

674,427	A *	5/1901	Palencsar	307/149
911,260	A *	2/1909	Pennock	307/149
1,014,719	A *	1/1912	Pennock	307/149
1,540,998	A *	6/1925	Plauson	310/309
3,121,196	A *	2/1964	Kasemir	324/464
4,234,167	A *	11/1980	Lane	254/291
4,486,669	A *	12/1984	Pugh	290/44
4,842,219	A *	6/1989	Jakubowski et al.	244/31
5,203,542	A	4/1993	Coley et al.	
6,254,034	B1 *	7/2001	Carpenter	244/153 R
6,829,911	B2	12/2004	Davis et al.	
6,961,662	B2	11/2005	Murphy	
7,016,785	B2	3/2006	Makela et al.	
7,200,418	B2	4/2007	Kaikuranta et al.	
7,330,366	B2	2/2008	Lee et al.	
7,375,492	B2	5/2008	Calhoon et al.	
7,378,181	B2	5/2008	Skinlo	
7,388,350	B1	6/2008	Wright	
7,394,671	B2	7/2008	Fukumoto et al.	
7,397,220	B2	7/2008	Uchida et al.	

* cited by examiner

Primary Examiner—Fritz M Fleming
(74) *Attorney, Agent, or Firm*—Mark Ogram

(57) **ABSTRACT**

A mechanism to tap an electrical source which uses an aircraft (preferably a lighter than air balloon) tethered by a conductive line. The conductive line is extended/withdrawn by a winch motor to adjust the altitude of the aircraft. The conductive line is isolated from the ground and an electrical conductor is connected to the conductive line and to an electrical load. In this manner, static electricity generated in the atmosphere is gathered for use.

15 Claims, 4 Drawing Sheets




18
10A
10B
10
11
12
19
13
14
15
8
5
16
6
17
7
23
23
21
23
23
12
22
5

FIG. 1

FIG. 2


30
START
31A
LIGHTNING ?
Y
32A
WITHDRAW BALLOON
N
31B
CURRENT IN RANGE ?
Y
N
31C
TOO HIGH ?
N
Y
32B
WITHDRAW BALLOON SET DISTANCE
32C
EXTEND BALLOON SET DISTANCE

FIG. 3


40
DC-IN
41
42
DC-AC
43
GRID

FIG. 4A


40
DC-IN
41
43
STEP DOWN TRANSFORMER
44
45
GROUND

FIG. 4B


40
DC-IN
46
47
DC-OUT

FIG. 4C


51A
50A
50B
51B

FIG. 5



FIG. 6A



FIG. 6B
REPLACEMENT


71
70
72
73
74

FIG. 7



FIG. 8A


85A
83
84
85B

FIG. 8B

ATMOSPHERIC ELECTRICAL GENERATOR

BACKGROUND OF THE INVENTION

This invention relates to the production of electrical energy and more particularly to the production of electrical energy from the atmosphere.

Everyone is familiar with Benjamin Franklin's kite experiment of 1752. Using a kite whose string had become wet, negative charges from the passing clouds flowed into the string, down to the suspended key, and then into a Leyden jar via a thin metal wire. Franklin was protected by a dry silk string; but, when Franklin's knuckle came too close to the key, he received a strong shock. Fortunately, Benjamin Franklin was not killed, others who tried this same experiment were not so lucky.

Since then, the formation of lightning has remained something of a mystery. Lightning bolts are triggered when a negatively charged cloud base induces a positive charge from the ground, thereby forming a "pathway" for the discharge of the collected electrical energy.

Lightning travels up to 60,000 miles per hour with a flash that is brighter than ten million 100-watt lightbulbs. This wattage is as much power as is produced by all of the electricity plants in the United States and with a voltage of up to 300 million volts.

It is this very fact, the power within lightning is immense, that has prevented any successful collection of the electrical energy from lightning. The electricity in lightning is far too extreme for current technology to harness.

While lightning has attracted a energy starved industrial world, no one has developed any technique to harness this naturally occurring electrical source.

It is clear there is a continuing need for an electrical source other than carbon-based fuels and that the naturally occurring electricity in the atmosphere is being ignored.

SUMMARY OF THE INVENTION

The invention is a mechanism which taps into the naturally occurring static electricity in the atmosphere. Whereas heretofore, the attempt to garner electricity from the atmosphere has focused exclusively on capturing lightning, the present invention syphons off the static electricity which is generated from any agitated air and avoids lightning.

Lightning is only the final discharge of the static electricity, whether that lightning is intra-cloud lightning, cloud-to-ground lightning, or inter-cloud lightning. Other types of final discharges are known as heat lightning, summer lightning, sheet lightning, ribbon lightning, silent lightning, ball lightning, bead lightning, elves, jets, and sprites. Well before these discharges are observed, as the atmosphere becomes agitated by wind or thermal activity, static electricity is being generated.

The present invention recognizes that this static electricity is being formed and creates a mechanism to capture it.

The mechanism of this invention utilizes an aircraft such as a lighter than air balloon. While the preferred embodiment uses a foil balloon, a variety of other aircraft are obvious to those of ordinary skill in the art, including, but not limited to: gliders, rubber balloons (such as weather balloons), biaxially-oriented polyethylene terephthalate polyester film balloons, and latex balloons.

Within this discussion, the balloon is referenced, but, the invention is not intended to be limited solely to balloons.

The balloon is sent aloft and is tethered by a conductive line. In this context, the conductive line may be any obvious to those of ordinary skill in the art. For the preferred embodiment, the conductive line is a generically referred to as a "poly-rope" and is commercially available through a variety of sources. A suitable conductive line is described in U.S. Pat. No. 5,203,542, entitled "Apparatus for Improved Electric Fence Wire Construction for use with Intensive Grazing" issued Apr. 20, 1993, to Coley, et al. and incorporated hereinto by reference.

The conductive line is played out of a winch to control the altitude of the balloon. The motor controlling the winch is able to reverse direction to both extend and withdraw the conductive line which is wrapped around a spool on the winch. The winch/spool combination are part of a base unit.

In some embodiments of the invention, the spool is constructed of rubber so as to insulate the conductive line from the winch assembly. In this embodiment, only the conductive line is charged by the atmospheric static electricity while the winch remains neutral.

In yet another embodiment, the winch/spool are part of a base unit which is itself isolated from the ground by an insulator. In this embodiment, the entire base unit is charged by the atmospheric static electricity.

A conductor, such as an insulated wire, is electrically connected to the conductive line. In one embodiment, where the conductive line is electrically isolated from the spool and winch motor, the conductor is connected to the conductive line. In the embodiment where the conductive line is electrically connected to the base unit, then the conductor is connected anywhere on a metallic base unit.

The other end of the conductor is connected to a load. The load in this case can be any of a variety of electrical loads well known to those of ordinary skill in art, including, but not limited to a motor, a battery system, or the electrical grid for the system.

In the preferred embodiment, a sensor array is used to monitor the activities both at the base unit (such as electrical flow within the conductor) and in the surrounding locale.

A sensor monitoring the electrical flow (i.e. voltage and/or current) within the conductor is used to monitor the electrical activity within the conductor.

In the preferred embodiment, a lightning sensor monitors for lightning activity within the locale. As noted earlier, the electrical characteristic of lightning is so extreme that ideally this discharge is avoided as it might damage the mechanism of this invention.

The sensor array is utilized by a controller, such as microprocessor, programmed to operate the mechanism as outlined herein.

The controller operates the winch motor to extend or withdraw the conductive line and by extension the altitude of the balloon. The controller is programmed to operate the winch by monitoring the electrical characteristics of the conductor and adjusting the balloon's altitude to maintain these characteristics within the conductor within a preset range.

This preset range is established either in the base programming of the controller or is established by an operator of the system.

As example, by controlling the amount of current being withdrawn from the atmosphere, the mechanism operates within a safe range and also provides a relatively stable current flow from which a variety of activities can take place (such as DC-AC conversion).

The controller also utilizes the lightning sensor to protect the mechanism from a lightning strike. Should lightning be detected within a pre-determined range (as established by the software or defined by an operator), then the balloon is pulled down to minimize the risk of damage from a lightning strike.

The invention, together with various embodiments thereof will be more fully explained by the following description of the accompanying drawings.

DRAWINGS IN BRIEF

FIG. **1** diagrams the preferred embodiment of the invention.

FIG. **2** illustrates the collection of the negative charged particles in the atmosphere.

FIG. **3** is a flow-chart of the operation of the controller for the preferred embodiment of the invention.

FIGS. **4**A, **4**B, and **4**C are electrical schematics for handling the static charge from the atmosphere.

FIG. **5** illustrates a conductive line used in the preferred embodiment of the invention.

FIGS. **6**A and **6**B illustrate an alternative conductive line creating an ionized pathway for the flow of the static charges from the atmosphere.

FIG. **7** illustrates the controller of an alternative embodiment and the associated safety devices.

FIGS. **8**A and **8**B illustrate two embodiments of enhanced electrical collection leads.

DRAWINGS IN DETAIL

FIG. **1** diagrams the preferred embodiment of the invention.

Balloon **10** is an aircraft which, in this illustration, is a lighter than air balloon. Wings **10**A, extending from the body of balloon **10**, provide additional lift in air flow **18**. Tail **10**B helps to stabilize balloon **10**.

Balloon **10** is tethered to the ground via conductive line **12**. As noted earlier, a variety of configurations and materials are available to serve as conductive line **12**. In this illustration, a poly-wire is used Poly-wire is commercially available through a variety of vendors, including, but not limited to: Jeffers Livestock and Zareba Systems, Inc, of Ellendale, Minn.

In this embodiment, located proximate to balloon **10**, is an electrical collection enhancement lead **11** which assists in the collection of the static electrical charge in the atmosphere. Electrical collection enhancement lead **11** is configured to attract the static charge and conduct the charge into the conductive line **12**.

The electricity flows down the conductive line into spool **13**, where the conductive line **12** is collected and either withdrawn or dispensed through operation of winch motor **14**.

Winch motor **14** and spool **13** are mounted onto base unit **16** which is electrically isolated from ground **7** using insulator **17**. Note, in this embodiment of the invention, when electricity is being collected from the atmosphere, the entire base unit **16** becomes charged. In another embodiment of the invention, spool **13** is constructed of rubber, thereby preventing base unit **16** from becoming charged, thereby restricting the charging from the atmosphere to only conductive line **12**.

In this embodiment, conductor **6** is connected to base unit **16** (since the entire base unit **16** is charged and the base unit is metallic) to communicate the electrical current to load **5**. Conductor **6** is ideally an insulated wire.

The electrical current through conductor **6** is measured using sensor **8**.

In the alternative embodiment discussed above, where only the conductive line **12** is charged, then conductor **6** is connected to conductive line **12**.

Controller **15**, located in this embodiment on base unit **16**, operates winch motor **14** in response to signals from sensor **8** (measuring the current being discharged to load **5**) to maintain the current flow within a pre-defined range. As the current flow diminishes, then the conductive line **12** extended from spool **13** to increase the altitude of balloon **10** to that more static charge from the atmosphere is gathered; as the current flow falls exceeds a preset level, conductive line **12** is withdrawn onto spool **13** to decrease the static charge being collected from the atmosphere.

The range of current flow through conductor **6** is ideally set by the program, although some embodiments of the invention permit an operator to establish this range of operation.

In an alternative embodiment, the sensor monitoring conductor **6** monitors the voltage therein.

In the preferred embodiment of the invention, controller **15** is also equipped with a lightning sensor **19**. In this embodiment, when lightning is sensed within a preset range, then substantially all of conductive line **12** is wound onto spool **13** to pull balloon **10** near the ground and protect the entire mechanism from being damaged from a lightning discharge.

In the preferred embodiment, the "safe" distance form lightning is set in the programming of controller **15** and is ideally two miles; other embodiments permit the operator to "safe" distance.

There are a variety of lightning sensors well known to those of ordinary skill in the art, including, but not limited to those described in: U.S. Pat. No. 7,016,785, entitled "Lightning Detection" issued to Makela, et al. on Mar. 21, 2006; U.S. Pat. No. 6,829,911, entitled "Lightning Detection and Prediction Alarm Device" issued to Jones, et al. on Dec. 7, 2004; U.S. Pat. No. 7,200,418, entitled "Detection of Lightning" issued to Karikuranta, et al. on Apr. 3, 2007; and U.S. Pat. No. 6,961,662, entitled "Systems and Methods for Spectral Corrected Lightning Detection" issued to Murphy on Nov. 1, 2005; all of which are incorporated hereinto by reference.

In another embodiment of the invention, controller **15** is not located on base unit **16**, rather it is remote and communicates its control signals to winch motor **14** using radio waves.

FIG. **2** illustrates the collection of the negative charged particles in the atmosphere.

Static charges **23** are generated in the atmosphere by agitated air. These static charges are often collected at the bottom of clouds, but exist in other environments as well.

Balloon **21** is extended into this strata of static charges **23** which are then attracted to conductive line **12** to flow to base unit **22** and then onto load **5**.

By increasing or decreasing the altitude of balloon **21** (defined by the length of the extended conductive line **12**), conductive line **12** is selectively exposed to varying densities and levels of the static charge strata, and by extension, the current flow or voltage is increased or decreased.

FIG. **3** is a flow-chart of the operation of the controller for the preferred embodiment of the invention.

Once the program starts **30**, the lightning sensor is checked to determine if lightning has occurred within the unsafe range **31**A, if it has, then the balloon is lowered **32**A, and the program continues monitoring the status of lightning until no lightning is detected.

When the lightning status is acceptable, then the current within the conductor is checked to see if the current is within the prescribed range **31**B. If the current is acceptable (within range) the program returns to check the lightning status **31**A; otherwise a determination is made to see if the current is above the prescribed range **31**C.

If the current is above the prescribed range, then the altitude of the balloon is withdrawn a set amount **32**B (ideally twenty-five feet) and the program loops back to see if the current is within range **31**B.

If the current is below the prescribed range, then the altitude of the balloon is extended a set amount **32**C (ideally twenty-five feet) and the program loops back to see if the current is within range **31**B.

In this manner of feed-back and minor adjustments in the altitude of the balloon, the current is maintained within a prescribed range which can be handled by the downstream electrical system.

As noted earlier, some embodiments of the invention monitor the voltage instead of the current.

FIGS. **4**A, **4**B, and **4**C are electrical schematics for handling the static charge from the atmosphere.

By maintaining the voltage being collected in a prescribed range, an electrical conversion system is easily designed. While FIGS. **4**A, **4**B, and **4**C illustrate some electrical configurations, those of ordinary skill in the art readily recognize a variety of other configurations which will serve the same function.

Referencing FIG. **4**A, Direct Current In (DC IN) **40** is buffered by a gang of capacitors **41** before being communicated to a DC/AC converter **42**. The DC/AC converter converts the direct current into a an alternating current suitable for placement over an existing electrical grid **43** such as normally found from a power-plant.

Those of ordinary skill in the art readily recognize a variety of DC/AC converters, including, but not limited to: U.S. Pat. No. 7,394,671, entitled "Controller IC, DC-AC Conversion Apparatus, and parallel running system of DC-AC Conversion Apparatuses" issued to Fukumoto, et al. on Jul. 1, 2008; and, U.S. Pat. No. 7,330,366, entitled "DC-AC Converter" issued to Lee, et al. on Feb. 12, 2008; all of which are incorporated hereinto by reference.

FIG. **4**B illustrates an electrical arrangement suitable for use in charging a battery. DC IN **40** is buffered by capacitor bank **41** before entering into a step down transformer **43**. Step down transformer **43** reduces the voltage so that the voltage can safely be introduced into battery **44** which is connected to ground **45** at the battery's other pole.

Those of ordinary skill in the art readily recognize a variety of batteries which will work in this capacity, including, but not limited to those described in: U.S. Pat. No. 7,378,181, entitled "Electric Storage Battery Construction and Manufacture" issued to Skinlo on May 27, 2008; U.S. Pat. No. 7,388,350, entitled "Battery with Electronic Compartment" issued to Wright on Jun. 17, 2008; U.S. Pat. No. 7,397,220, entitled "Connection Member and Battery Pack" issued to Uchida, et al. on Jul. 8, 2008; and, U.S. Pat. No. 7,375,492, entitled "Inductively Charged Battery Pack" issued to Calhoon, et al. on May 20, 2008; all of which are incorporated hereinto by reference.

In FIG. **4**C, DC IN **40** is fed into an adjustable rheostat **46** which is controlled by the controller so that the DC OUT **47** falls within a specified range.

FIG. **5** illustrates a conductive line used in the preferred embodiment of the invention.

This type of conductive line is commonly called poly-wire and consists of multiple interwoven strands of plastic **50**A and **50**B woven into a cord or rope arrangement having intertwined therein exposed metal wires **51**A and **51**B. While this illustration shows two plastic strands and two metal wires, any number of possible combinations is possible.

The exposed metal wires **51**A and **51**B attract the atmospheric static charge and transmit the charge down to the base unit (not shown).

FIGS. **6**A and **6**B illustrate an alternative conductive line creating an ionized pathway for the flow of the static charges from the atmosphere.

This conductive line utilizes a tube **60** having an outer layer **62** of PET Film (Biaxially-oriented polyethylene terephtalate polyester film) which provides exceptionally high tensile strength and is chemically and dimensionally stable. The tube has an ideal diameter of between two and three inches.

An interior metal coating **61** provides an initial conduit for the flow of static charge. The static charge through the metal forces the tube to expand due to the repulsion experienced by like charges. Further, the flow of electricity causes the interior of the tube **60** to become ionized to provide an additional pathway for the atmospheric static charges to the base unit (not shown).

Because outer layer **62** provides a gas barrier, the resulting ionization is not dissipated by air currents, thereby providing a highly stable pathway.

FIG. **7** illustrates the controller of an alternative embodiment and the associated safety devices.

In this embodiment, controller box **70**, resting on insulating pad **72**, is in communication with the sensors as described above. Using the input from these sensors, when there is flow of electricity through the base unit, warning flashing light **71** is illuminated. To electrically neutralize the mechanism, switch **73** is activated to pass any existing current into the ground **74**.

FIGS. **8**A and **8**B illustrate two embodiments of enhanced electrical collection leads.

Referencing FIG. **8**A, enhanced electrical collection lead **82** is a wire mesh which is in electrical communication with conductive line **81** and balloon **80**. Because of the significant amount of metal exposed by enhanced electrical collection lead **82**, more static electricity from the atmosphere is drawn to the collection lead **82**, and then down conductive line **81** to the base unit (not shown).

Conductive lead **82** is positioned proximate to balloon **80**.

In FIG. **8**B, poly-wire **83** has enhanced electrical collection leads **84** wrapped therearound. Collection leads **84** have pointed ends **85**A and **85**B which have a propensity to attract more electricity than rounded ends do.

It is clear from the foregoing that the present invention captures an entirely new source of electrical energy.

What is claimed is:

1. A mechanism to tap an electrical source comprising:

a) a lighter than air balloon suspended in the atmosphere;

b) a base unit having a spool of conductive line on a winch motor, one end of said conductive line secured to said lighter than air balloon, a portion of said conductive line collecting electricity in the atmosphere, said winch motor capable of selectively extending or withdrawing said conductive line from said spool;

c) an insulator electrically isolating said conductive line from ground;

d) a conductor having a first end electrically connected to said conductive line and a second end electrically connected to a load being powered by collected electricity from said conductive line;

e) an electrical flow sensor monitoring electrical flow through said conductor and generating an electrical flow indicia indicative of said electrical flow in said conductor; and,

f) a controller receiving said electrical flow indicia and selectively operating said winch motor such that said electrical flow indicia remains within a selected operating range.

2. The mechanism to tap an electrical source according to claim **1**, wherein said selected operating range is established by an operator.

3. The mechanism to tap an electrical source according to claim **2**, further including a warning light activated when said electrical flow indicia is non-zero.

4. The mechanism to tap an electrical source according to claim **1**,

a) further including a lightning sensor generating a lightning presence indicia indicative of lightning within a prescribed range, said presence indicia being communicated to said controller; and,

b) wherein said control mechanism, in response to said lightning presence indicia, operates said winch motor to withdraw substantially all of said conductive line onto said spool.

5. The mechanism to tap an electrical source according to claim **4**, wherein said prescribed range is established by an operator.

6. The mechanism to tap an electrical source according to claim **1**, further including an electrical collection enhancement lead in electrical contact with a first end of said conductive material, said electrical collection enhancement lead configured to attract static electricity.

7. The mechanism to tap an electrical source according to claim **6**, wherein said electrical collection enhancement lead is positioned proximate to said lighter than air balloon.

8. The mechanism to tap an electrical source according to claim **7**, wherein said electrical collection enhancement lead includes at least two pointed electrical conductors.

9. The mechanism to tap an electrical source according to claim **1**, wherein said insulator electrically isolates said conductive line from said winch motor.

10. The mechanism to tap an electrical source according to claim **1**, wherein said insulator electrically isolates said base unit from ground.

11. A mechanism comprising:

a) an airborne aircraft having a conductive line secured to a winch capable of extending or withdrawing said conductive line from a spool, when said airborne aircraft is aloft, said conductive line collecting electricity from the atmosphere;

b) a conductor having a first end electrically connected to said conductive line and a second end electrically connected to a load such that collected electricity from said conductive line powers said load;

c) an electrical flow sensor monitoring electrical flow through said conductor and generating an electrical flow indicia indicative of said electrical flow in said conductor; and,

d) a controller receiving said electrical flow indicia adjusting an altitude of said airborne aircraft via said winch such that said electrical flow indicia remains within a selected operating range.

12. The mechanism to tap an electrical source according to claim **11**,

a) further including a lightning sensor communicating with said controller; and,

b) wherein said controller, in response to selected signals from said lightning sensor withdraws substantially all of said conductive line.

13. A mechanism to tap an electrical source comprising:

a) a lighter than air balloon suspended in the atmosphere;

b) a base unit having a spool of conductive line on a winch motor, one end of said conductive line suspended by said balloon, a portion of said conductive line collecting electricity from the atmosphere, said winch motor capable of adjusting an altitude of said lighter than air balloon by selectively extending or withdrawing said conductive line from said spool;

c) a conductor having a first end electrically connected to said conductive line and a second end electrically connected to a load being powered by said collected electricity from said conductive line;

d) a sensor array having,

  1) an electrical flow sensor monitoring electrical flow through said conductor and generating an electrical flow indicia indicative of said electrical flow in said conductor, and,

  2) a lightning sensor monitoring existence of proximate lightning; and,

e) a controller responsive to said electrical flow indicia from said sensor array to selectively operate said winch motor.

14. The mechanism to tap an electrical source according to claim **13**,

a) further including a warning light; and,

b) wherein said controller activates said warning light when said electrical flow in said conductor is non-zero.

15. The mechanism to tap an electrical source according to claim **14**, further including an electrical collection enhancement lead in electrical contact with said conductive material, said electrical collection enhancement lead configured to attract static electricity and positioned proximate to said lighter than air balloon.

* * * * *

US009160156B2

(12) **United States Patent**
Allen et al.

(10) **Patent No.: US 9,160,156 B2**
(45) **Date of Patent: Oct. 13, 2015**

(54) SYSTEM FOR HARVESTING ATMOSPHERIC ELECTRICITY

(75) Inventors: **Edward H. Allen**, Lancaster, CA (US); **Sergey Macheret**, Palmdale, CA (US)

(73) Assignee: **Lockheed Martin Corporation**, Bethesda, MD (US)

(*) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 357 days.

(21) Appl. No.: **13/276,259**

(22) Filed: **Oct. 18, 2011**

(65) **Prior Publication Data**

US 2013/0093261 A1 Apr. 18, 2013

(51) **Int. Cl.**

H05F 7/00 (2006.01)
H02G 13/00 (2006.01)
B64D 45/02 (2006.01)

(52) **U.S. Cl.**

CPC ***H02G 13/20*** (2013.01); ***B64D 45/02*** (2013.01); *H05F 7/00* (2013.01)

(58) **Field of Classification Search**

CPC H02G 13/20; B64D 45/02; H05F 7/00
USPC 361/231, 230
See application file for complete search history.

(56) **References Cited**

U.S. PATENT DOCUMENTS

3,719,829 A * 3/1973 Vaill 307/149
4,017,767 A * 4/1977 Ball 361/117
4,950,978 A * 8/1990 Govaert 324/72
5,726,855 A * 3/1998 Mourou et al. 361/213
8,045,314 B2 * 10/2011 Ibok 361/231
2014/0231679 A1 * 8/2014 Kremeyer et al. 250/505.1

OTHER PUBLICATIONS

Tzzortzakis et al. "Concatenation of plasma filaments created in air by femtosecond laser infrared laser pulses", 2003, Applied Physics B, vol. 767, pp. 609-612.*

Zhou et al. , Revival of femtosecond laser plasma filaments in air by a nanosecond laser, Jun. 24, 2009, Optic Express, vol. 17, No. 14, pp. 1 -7.*

Assion et al., "Control of Chemical Reactions by Feedback-Optimized Phase-Shaped Femtosecond Laser Pulses", Science, Oct. 30, 1998, pp. 919-922, vol. 282.

* cited by examiner

Primary Examiner — Zeev V Kitov
(74) *Attorney, Agent, or Firm* — Baker Botts L.L.P.

(57) ABSTRACT

Systems, methods and apparatus for harvesting atmospheric electricity are provided. The system includes a laser configured to form a plasma filament and a collector configured to collect electricity flowing along the plasma filament. The plasma filament comprises an electrically conducting plasma filament. Atmospheric electricity may be collected by having the plasma filament form at least a part of a conducting path: (1) between ground and a cloud, (2) between differently charged regions of the same cloud, (3) between differently charged regions of different clouds, and (4) between different regions of atmosphere, where there is a vertical voltage gradient. When the plasma filament is not long enough to form the entire conducting path, a lightning may be triggered to complete the conducting path needed to collect atmospheric electricity.

21 Claims, 6 Drawing Sheets




140
CLOUD
100
120
130
110
GROUND

FIG. 1


140
CLOUD
210
200
120
130
110
220
GROUND

FIG. 2


CLOUD

FIG. 3A


CLOUD

FIG. 3B


300
422
421
420
CLOUD 1
310
431
432
430
CLOUD 2

FIG. 4


520
VERTICAL
VOLTAGE
GRADIENT
510
501
300
310

FIG. 5


632
130
L
620
C
R
633
610
631

FIG. 6

SYSTEM FOR HARVESTING ATMOSPHERIC ELECTRICITY

STATEMENT REGARDING FEDERALLY SPONSORED RESEARCH OR DEVELOPMENT

Not applicable.

FIELD OF THE INVENTION

The subject technology relates in general to a system for harvesting atmospheric electricity, and more particularly to a system that uses a laser to form an electrically conducting plasma filament for harvesting atmospheric electricity.

BACKGROUND

It is well known that large quantities of electrical energy are present in the atmosphere and in lightning. Lightning was one of the first forms of electricity harnessed in the modern age by Benjamin Franklin in his famous kite experiment.

A lightning discharge typically contains on the order of 10^{10} Joules of energy. It has been estimated that the total electrical power of lightning across the Earth is of the order of 10^{12} watts. Collection of electrical energy from clouds associated with lightning is a problem that needs to be resolved.

Lightning is but a small part of the total electrical activity of the atmosphere. When a local build up of charge above the Earth exceeds the local breakdown potential of the atmosphere a lightning discharge occurs. However, there is a continual invisible flow of charge from Ionosphere to Earth occurring day and night over the entire surface of the globe, which exceeds the global lightning power output by many times. The source of this flow of charge from the atmosphere to Earth is the Sun. Radiation from the Sun helps form most of the ions found in the Ionosphere, a highly charged region above the atmosphere, through ionization of atmospheric molecules. Solar radiation, particularly in the UV and soft x-ray bands, consist of photons whose energies are well suited to ionization. The Sun also emits continuously a solar wind of positively charged particles. These are captured by the Earth's magnetic field and further contribute to the Ionosphere. The positively charged region in the Ionosphere in turn induces (by electrostatic induction) a negative charge on the surface of the Earth. The Earth becomes in effect an enormous spherical capacitor. A potential gradient or electric field is thus established between the two "plates" of this capacitor, the Ionosphere (or Electrosphere) and the surface of the Earth. While the upper strata of the atmosphere conduct electricity reasonably well, the lower levels act as an insulator or dielectric. Near the surface of the Earth, this electrostatic potential gradient is on the order of about 100 Vm^{-1} in summer, rising to 300 Vm^{-1} in winter. This flow of charge can be tapped and directed to provide useable electrical power. This source of atmospheric electricity has the following advantages: (1) Simple and robust technology; (2) Low cost technology—much cheaper than photovoltaics or wind turbines; (3) Available day and night in all weather conditions—in fact, more power is produced at night than during the day; and (4) Available at any point on the Earth's surface. Collection of this source of atmospheric electricity is another problem that needs to be resolved.

SUMMARY

According to various aspects of the subject technology, a system for harvesting atmospheric electricity is provided that solves some or all of the foregoing problems. In some aspects, the system may be used to harvest atmospheric electricity arising from an electrostatic potential gradient: (1) between ground and a cloud, (2) between differently charged regions of the same cloud, (3) between differently charged regions of different clouds, and (4) between different regions of atmosphere, where there is a vertical voltage gradient. In other aspects, the system may be used to harvest atmospheric electricity arising from an electrostatic potential gradient between the Ionosphere (or Electrosphere) and the surface of the Earth.

According to various aspects of the subject technology, a system for harvesting atmospheric electricity is provided. The system comprises a laser configured to form a plasma filament. The system also comprises a collector configured to collect electricity flowing along the plasma filament.

According to various aspects of the subject technology, a method for harvesting atmospheric electricity is provided. The method comprises forming a plasma filament with a laser. The method also comprises collecting electricity flowing along the plasma filament.

According to various aspects of the subject technology, an apparatus for harvesting atmospheric electricity is provided. The apparatus comprises means for forming a plasma filament with a laser. The system also comprises means for collecting electricity flowing along the plasma filament.

It is understood that other configurations of the subject technology will become readily apparent to those skilled in the art from the following detailed description, wherein various configurations of the subject technology are shown and described by way of illustration. As will be realized, the subject technology is capable of other and different configurations and its several details are capable of modification in various other respects, all without departing from the scope of the subject technology. Accordingly, the drawings and detailed description are to be regarded as illustrative in nature and not as restrictive.

BRIEF DESCRIPTION OF THE DRAWINGS

The accompanying drawings, which are included to provide further understanding of the subject technology and are incorporated in and constitute a part of this specification, illustrate aspects of the subject technology and together with the description serve to explain the principles of the subject technology.

FIG. **1** illustrates a first example of a system for harvesting atmospheric electricity. The system comprises a laser configured to form a plasma filament and a collector configured to collect electricity flowing along the plasma filament. The plasma filament forms a conducting path between ground and a cloud.

FIG. **2** illustrates a second example of a system for harvesting atmospheric electricity. A plasma filament and a lightning together form a conducting path between ground and a cloud. A condensing mirror directs the beam of laser towards the cloud.

FIG. **3**A illustrates a third example of a system for harvesting atmospheric electricity. A laser system situated on an airplane forms two plasma filaments that together complete a conducting path between a first region of a cloud and a second region of the cloud. The first region of the cloud and the second region of the cloud carry opposite electric charges. A collector configured to collect electricity flowing along the two plasma filaments is also situated on the same airplane as the laser system.

FIG. 3B illustrates a fourth example of a system for harvesting atmospheric electricity. It is similar to FIG. 3A, except two lightnings complete the conducting path between a first region of a cloud and a second region of the cloud (i.e., a first lightning electrically connects the first region of the cloud to one of the plasma filaments and a second lightning electrically connects the second region of the cloud to the other plasma filament).

FIG. 4 illustrates a fifth example of a system for harvesting atmospheric electricity. A laser system situated on an airplane forms two plasma filaments that together complete a conducting path between a first cloud and a second cloud. The region of the first cloud that is connected to the first plasma filament and the region of the second cloud that is connected to the second plasma filament carry opposite electric charges.

FIG. 5 illustrates a sixth example of a system for harvesting atmospheric electricity. A laser situated on an airplane forms a plasma filament that completes a conducting path between a first region of atmosphere and a second region of atmosphere. A collector situated on the same airplane as the laser can collect electricity flowing along the plasma filament, because a vertical voltage gradient exists between the first region of atmosphere and the second region of atmosphere.

FIG. 6 illustrates an example of a collector configured to collect electricity flowing along the plasma filament. The collector may be a charge collection circuit characterized by capacitance, inductance, and resistance. The electricity may be collected by charging a capacitor.

DETAILED DESCRIPTION

The detailed description set forth below is intended as a description of various configurations of the subject technology and is not intended to represent the only configurations in which the subject technology may be practiced. The appended drawings are incorporated herein and constitute a part of the detailed description. The detailed description includes specific details for the purpose of providing a thorough understanding of the subject technology. However, it will be apparent to those skilled in the art that the subject technology may be practiced without these specific details. In some instances, well-known structures and components are shown in block diagram form in order to avoid obscuring the concepts of the subject technology. Like components are labeled with identical element numbers for ease of understanding.

FIG. 1 illustrates a first example of a system **100** for harvesting atmospheric electricity. The system **100** comprises a laser **110** configured to form a plasma filament **120** and a collector **130** configured to collect electricity flowing along the plasma filament **120**. The plasma filament **120** forms a conducting path between ground and a cloud **140**.

The plasma filament **120** comprises an electrically conducting plasma filament. The plasma comprises of electrons and positive ions. The electrically conducting plasma filament may be formed in atmosphere using an ultra short pulse laser (USPL). The USPL forms a plasma filament by raising the conductivity of a very small diameter channel (~100 microns or less) for a very brief time. The propagation of high power (~10^{14} W/cm^2) pulses from the USPL is accompanied by filamentation—self-channeling of femtosecond laser pulses in stable high-intensity light filaments with ~100 microns diameters (so that the Kerr effect focusing balances defocusing due to plasma formation). This filamentation keeps the beam virtually free of diffraction divergence. The long plasma strings have high electron densities (10^{16}/cm^3) which support high conductivities. The ionization of air at these intensities results from multi-photon processes. Filamentation has been produced and detected at altitudes as high as 13-20 km. Almost no beam scattering occurs in filamentation phenomenon, and virtually all the pulse energy is invested in ionization of air molecules. With the typical electron density and channel diameter, a 160 mJ pulse is sufficient to generate a 1 km long channel.

Once initiated, plasma filaments cannot go on forever, and typically only propagate a kilometer or so before energy depletion and exhaustion. However, by using two coaxial USPL projection optics having different time-lensing parameters, a near and far filament could be initiated in a "daisy-chain" to extend the total length of the conductive channel. The onset of filamentation in the far filament is time-lensed to coincide with the exhaustion range of the near filament. Additionally, using negative chirp, femtosecond laser pulses can propagate almost without loss until different frequency components of the wave packet, propagating at different speeds due to dispersion in air, come together at a certain desired location so that the laser intensity there exceeds the filamentation threshold, resulting in long ionized filaments created at a distance of up to several miles from the laser source. In other words, negative chirp is used to essentially focus a beam of the laser at a desired distance to form the plasma filament there. Accordingly, this technique may be used to move the starting point and to extend the length of the plasma filament.

The size, electrical conductivity, and lifetime of the plasma filaments are enhanced by an auxiliary radio-frequency electromagnetic waves or microwaves. The plasma filament may act like an antenna to absorb the auxiliary radio-frequency (RF) electromagnetic waves or microwaves.

The pulsed collection of electric charge and energy is repeated with an optimal (possibly very high) repetition rate of the pulsed laser and of the auxiliary RF waves or microwaves. The energy collected per one pulse should exceed the energy spent on creating and enhancing the plasma filaments, so that the net energy collected is positive. The optimal pulse repetition rate (PRR) depends upon atmospheric conditions which can vary widely over even short time durations. As a general rule, one tries to tune the repetition rate to the plasma relaxation time (the ion-electron recombination time) so that the conductivity of the filament remain as high as is optimal given the atmospheric conditions at the time. A feedback control system that varies the PRR as well as the rest of the pulse-shaping parameters may be employed to optimize the net power production of the system. For more information regarding pulse shaping and tailoring, which is the central theme of the field called "quantum control", please see A. Assion, T. Baumert, M. Bergt, T. Brixner, B. Kiefer, V. Seyfried, M. Strehle, G. Gerber (30 October). "Control of Chemical Reactions by Feedback-Optimized Phase-Shaped Femtosecond Laser Pulses". Science 282 (5390): 919-922. doi: 10.1126/science.282.5390.919. PMID 9794756.

FIG. 2 illustrates a second example of a system **200** for harvesting atmospheric electricity. A plasma filament **120** and a lightning **210** together form a conducting path between ground and a cloud **140**. A condensing mirror **220** directs the beam of laser **110** towards the cloud **140**. A collector **130** is configured to collect electricity flowing along the plasma filament **120**.

In the case of electricity collection from the cloud **140**, the initial and RF-enhanced plasma filaments can be relatively short, not reaching all the way from ground to the cloud **140**. The relatively short plasma filament can be optimized so that it would trigger propagation of the so-called leader (as in natural lightning), which would effectively use the energy and potential of the cloud to eventually create an electrically conducting path between ground and the cloud **140**. The final conducting path would comprise of a plasma filament **120** and a lightning **210**.

It is not shown in the figures, but alternatively both the laser **110** and the collector **130** may be placed on a mobile device, which moves together with the cloud. One such mobile device may be a vehicle moving on the ground, but another such mobile device may be an airplane flying in the air. In the case of an airplane flying in the air, plasma filaments may be formed by the laser to reach both ground and the cloud at the same time. In the event the plasma filament directed at ground is not long enough to reach ground, a lightning may also be formed to complete the conducting path to ground.

FIG. **3**A illustrates a third example of a system **300** for harvesting atmospheric electricity. A laser system situated on an airplane **310** forms two plasma filaments (**321**, **322**) that together complete a conducting path between a first region **331** of a cloud **330** and a second region **332** of the cloud **330**. The first region **331** of the cloud **330** and the second region **332** of the cloud **330** carry opposite electric charges. In the example shown here, the first region **331** of the cloud **330** carries positive electric charges, while the second region **332** of the cloud **330** carries negative electric charges. A collector configured to collect electricity flowing along the two plasma filaments is also situated on the same airplane **310** as the laser. Positive and negative charges are naturally separated within the cloud, so this example makes use of the electrostatic potential gradient between different regions of the same cloud.

FIG. **3**B illustrates a fourth example of the system **300** for harvesting atmospheric electricity. It is similar to FIG. **3**A, except two lightnings (**341**, **342**) complete the conducting path between a first region **331** of a cloud **330** and a second region **332** of the cloud **330** (i.e., a first lightning **341** electrically connects the first region **331** of the cloud **330** to one of the plasma filaments **321** and a second lightning **342** electrically connects the second region **332** of the cloud **330** to the other plasma filaments **322**). The lightning formation is again because the initial and RF-enhanced plasma filaments can be relatively short, not reaching all the way from the collector situated on airplane **310** to the cloud **330**. These relatively short plasma filaments can be optimized so that they would trigger propagation of the so-called leader (as in natural lightning), which would eventually create an electrically conducting path between the two regions of cloud **330** via a connection through airplane **310**. The final conducting path would comprise of two plasma filaments (**321**, **322**) and two lightnings (**341**, **342**). Of course, one of the lightnings may not be formed, if one of the plasma filament can reach all the way from airplane **310** to cloud **330**.

FIG. **4** illustrates a fifth example of the system **300** for harvesting atmospheric electricity. A laser system situated on an airplane **310** forms two plasma filaments (**421**, **431**) that together complete a conducting path between a first cloud **420** and a second cloud **430**. The region **422** of the first cloud **420** that is connected to the first plasma filament **421** and the region **432** of the second cloud **430** that is connected to the second plasma filament **431** carry opposite electric charges. In the example shown here, region **422** of cloud **420** carries positive electric charges, while region **432** of cloud **430** carry negative electric charges. Positive and negative charges are naturally separated within the cloud, so this example makes use of the electrostatic potential gradient between different regions of different clouds. Once again, in case one of the plasma filament cannot reach all the way from airplane **310** to any one of the clouds, then lightning may be formed to complete an electrically conducting path from airplane **310** to any one of the clouds. But these embodiments are not shown in the figures.

FIG. **5** illustrates a sixth example of the system **300** for harvesting atmospheric electricity. A laser system situated on an airplane **310** forms a plasma filament **501** that completes a conducting path between a first region **510** of atmosphere and a second region **520** of atmosphere. A collector situated on the same airplane **310** as the laser system can collect electricity flowing along the plasma filament **501**, because a vertical voltage gradient exists between the first region **510** of atmosphere and the second region **520** of atmosphere. Because no clouds are needed for this embodiment, atmospheric electricity collection is possible under fair weather conditions (relying on the naturally existing vertical voltage gradient in the atmosphere) as well as under foul weather conditions.

FIG. **6** illustrates an example of a collector **130** configured to collect electricity flowing along a plasma filament **620**. The collector may be a charge collection circuit characterized by capacitance **631**, inductance **632**, and resistance **633**. The electricity may be collected by charging a capacitor associated with capacitance **631**. Battery **610** represents these naturally existing voltage sources: (1) between ground and a cloud, (2) between differently charged regions of the same cloud, (3) between differently charged regions of different clouds, and (4) between different regions of atmosphere, where there is a vertical voltage gradient. The plasma filament **620** can, for the purpose of analysis and optimization of the charge collection process, be viewed as electromagnetic transmission lines characterized by their effective capacitance, inductance, and resistance per unit length. Accordingly, the parameters of the charge collection circuit and of the effective transmission line representing the plasma filaments are optimized, so as to maximize the net charge and energy collected (minus the energy spent on generating and enhancing the plasma filaments).

The foregoing description is provided to enable a person skilled in the art to practice the various configurations described herein. While the subject technology has been particularly described with reference to the various figures and configurations, it should be understood that these are for illustration purposes only and should not be taken as limiting the scope of the subject technology.

There may be many other ways to implement the subject technology. Various functions and elements described herein may be partitioned differently from those shown without departing from the scope of the subject technology. Various modifications to these configurations will be readily apparent to those skilled in the art, and generic principles defined herein may be applied to other configurations. Thus, many changes and modifications may be made to the subject technology, by one having ordinary skill in the art, without departing from the scope of the subject technology.

It is understood that the specific order or hierarchy of steps in the processes disclosed is an illustration of exemplary approaches. Based upon design preferences, it is understood that the specific order or hierarchy of steps in the processes may be rearranged. Some of the steps may be performed simultaneously. The accompanying method claims present elements of the various steps in a sample order, and are not meant to be limited to the specific order or hierarchy presented.

A phrase such as "an aspect" does not imply that such aspect is essential to the subject technology or that such aspect applies to all configurations of the subject technology. A disclosure relating to an aspect may apply to all configurations, or one or more configurations. An aspect may provide one or more examples of the disclosure. A phrase such as an "aspect" may refer to one or more aspects and vice versa. A phrase such as an "embodiment" does not imply that such embodiment is essential to the subject technology or that such embodiment applies to all configurations of the subject technology. A disclosure relating to an embodiment may apply to all embodiments, or one or more embodiments. An embodiment may provide one or more examples of the disclosure. A phrase such an "embodiment" may refer to one or more embodiments and vice versa. A phrase such as a "configuration" does not imply that such configuration is essential to the subject technology or that such configuration applies to all configurations of the subject technology. A disclosure relating to a configuration may apply to all configurations, or one or more configurations. A configuration may provide one or more examples of the disclosure. A phrase such as a "configuration" may refer to one or more configurations and vice versa.

Furthermore, to the extent that the term "include," "have," or the like is used in the description or the claims, such term is intended to be inclusive in a manner similar to the term "comprise" as "comprise" is interpreted when employed as a transitional word in a claim.

The word "exemplary" is used herein to mean "serving as an example, instance, or illustration." Any embodiment described herein as "exemplary" is not necessarily to be construed as preferred or advantageous over other embodiments.

A reference to an element in the singular is not intended to mean "one and only one" unless specifically stated, but rather "one or more." The term "some" refers to one or more. Underlined and/or italicized headings and subheadings are used for convenience only, do not limit the subject technology, and are not referred to in connection with the interpretation of the description of the subject technology. All structural and functional equivalents to the elements of the various configurations described throughout this disclosure that are known or later come to be known to those of ordinary skill in the art are expressly incorporated herein by reference and intended to be encompassed by the subject technology. Moreover, nothing disclosed herein is intended to be dedicated to the public regardless of whether such disclosure is explicitly recited in the above description.

What is claimed is the following:

1. A system for harvesting atmospheric electricity, comprising:

a laser configured to form a plasma filament comprising at least a first filament and a second filament, wherein onset of formation of the second filament coincides with an exhaustion range of the first filament;

an auxiliary source of electromagnetic energy operable to enhance the plasma filament by applying electromagnetic energy to the plasma filament; and

a collector configured to collect electricity flowing along the plasma filament.

2. The system of claim **1**, wherein the plasma filament comprises an electrically conducting plasma filament.

3. The system of claim **1**, wherein the laser is a pulsed laser.

4. The system of claim **3**, wherein the pulsed laser is pulsed at an optimal repetition rate.

5. The system of claim **1**, wherein the electromagnetic energy comprises at least one of radio-frequency energy or microwave energy.

6. The system of claim **1**, wherein the plasma filament forms at least a part of a conducting path between ground and a cloud.

7. The system of claim **6**, wherein at least one lightning forms another part of the conducting path between ground and the cloud.

8. The system of claim **1**, wherein the plasma filament forms at least a part of a conducting path between a first region of a cloud and a second region of the cloud.

9. The system of claim **8**, wherein at least one lightning forms another part of the conducting path between the first region of the cloud and the second region of the cloud.

10. The system of claim **1**, wherein:

the laser is further configured to form a second plasma filament,

the plasma filament is connected to a region of a first cloud, and

the second plasma filament is connected to a region of a second cloud.

11. The system of claim **1**, wherein the plasma filament completes a conducting path between a first region of atmosphere and a second region of atmosphere.

12. The system of claim **11**, wherein a vertical voltage gradient exists between the first region of atmosphere and the second region of atmosphere.

13. The system of claim **1**, wherein the collector comprises a charge collection circuit.

14. The system of claim **1**, wherein the laser is situated on ground.

15. The system of claim **1**, wherein the laser is situated on a mobile device.

16. The system of claim **15**, wherein the mobile device is an airplane.

17. The system of claim **1**, wherein negative chirp is used to move the starting point of formation of the plasma filament to a desired location.

18. A method for harvesting atmospheric electricity, the method comprising:

forming a plasma filament with a laser, wherein the plasma filament comprises at least a first filament and a second filament, and wherein onset of formation of the second filament coincides with an exhaustion range of the first filament;

applying electromagnetic energy to the plasma filament to enhance the plasma filament; and

collecting electricity flowing along the plasma filament.

19. An apparatus for harvesting atmospheric electricity, the apparatus comprising:

means for forming a plasma filament with a laser, wherein the plasma filament comprises at least a first filament and a second filament, and wherein onset of formation of the second filament coincides with an exhaustion range of the first filament;

means for applying electromagnetic energy to the plasma filament to enhance the plasma filament; and

means for collecting electricity flowing along the plasma filament.

20. The system of claim **1**, wherein the laser is an ultra short pulse laser (USPL).

21. The system of claim **1**, wherein the laser comprises two coaxial USPL projection optics having different time-lensing parameters.

* * * * *

US 20100220424A1

(19) **United States**

(12) **Patent Application Publication**

IBOK

(10) **Pub. No.: US 2010/0220424 A1**

(43) **Pub. Date: Sep. 2, 2010**

(54) **METHOD OF ATMOSPHERIC DISCHARGE ENERGY CONVERSION, STORAGE AND DISTRIBUTION**

(75) Inventor: **EFFIONG ETUKUDO IBOK**, SUNNYVALE, CA (US)

Correspondence Address:
THE TRAVIS BUSINESS GROUP, INC.
1005 E. HOMESTEAD RD.
SUNNYVALE, CA 94087 (US)

(73) Assignees: **EFFIONG ETUKUDO IBOK**, SUNNYVALE, CA (US); **THE TRAVIS BUSINESS GROUP, INC**, SUNNYVALE, CA (US)

(21) Appl. No.: **12/534,115**

(22) Filed: **Aug. 1, 2009**

Publication Classification

(51) **Int. Cl.**
H02H 3/22 (2006.01)
H02J 7/00 (2006.01)

(52) **U.S. Cl.** **361/117**; 320/166

(57) **ABSTRACT**

A method of converting atmospheric electrical discharge to a useable form of energy by arresting, storage and retransmission of lightning induced electrical discharge is disclosed. The invention discloses methods of deploying this technology even in isolated locations where no electricity infrastructure exists. Additionally, the potential for achieving in excess of 1 GWe of electrical power supply at costs orders of magnitude lower than fossil fuel or solar is also disclosed. Isolated collection units are disclosed. A method of deployment of these devices on individual cars and recharge stations is disclosed which in effect unplugs these automotive and recharge stations from the grid. This capability significantly decreases their dependence on the electricity grid infrastructure, enabling a much more enhanced rollout capability for the industry. The concept of Energy Dams is disclosed. These are facilities with substantial electrical energy storage capacities with the capability of receiving energy feeds from various generation sources.





Fig. 1a



Fig. 1b


70
50
40
30
20
15
10
8
6
4
2
1
.8
.6
.4
.2
.1

Global Distribution of Lightning Strikes: April 1995 – February, 2003. (Source: NASA)

Fig. 1c


20
30
40
60
10
50

Fig. 2


70
Ti or Cu
80
90

Fig. 3


+
110
110
130
−
100

Fig. 4


+
180
190
200
150
-
-
-
-
140
160
170

Fig. 5


230
+
240
210
220

Fig. 6


310
305
290
n
300
280
260
2
250
1
270

Fig. 7a


312
313
314
315
311

Fig. 7b


316
318
319
317

Fig 7c


+ve
1
2
3
4
n
320
330
340
GND
350

Fig. 8a


333
332
335
331
336
334

Fig. 8b


360
370
380
390
400

Fig. 9



Fig. 10


440
450
460
470
480
490
500

Fig. 11


510
520
530
540

Fig. 12



Fig. 13


610
600
580
590
+

Fig. 14


650
660
640
620
630
GND

Fig. 15


670
680
690
700
GND
710
720

Fig. 16

METHOD OF ATMOSPHERIC DISCHARGE ENERGY CONVERSION, STORAGE AND DISTRIBUTION

TECHNICAL FIELD

[0001] This invention relates to the field of electrical energy generation and storage in general and the conversion of atmospheric electrical discharge to a useable form of energy by arresting, storage and retransmission of lightning induced electrical discharge in particular.

BACKGROUND OF INVENTION

[0002] Lightning has always been a destructive force of nature. Causing death by electrocution and starting fires both in residential areas and in forests. In either case the loss of life and property is substantial. Lightning strikes have affected communication systems, and by uncontrolled arcing, electricity grids leading to loss of power with substantial economic loss

[0003] Lightning is the number one cause of forest and farm fires just in the United States and causes over 80 percent of all livestock losses due to accidents. Property losses run into billions of dollars annually and thousands of deaths and injury are reported yearly. Business losses from power and communications failure run into billions of dollars annually. Up to now, lightning strike damage has generally been controlled primarily by grounding.

[0004] A lightning discharge can have voltage of 10 MV to 100 MV and current of 1 kA to 300 kA. It packs so much voltage that it can leap a mile through the air and strike another object. Lightning can strike a building directly or leaping to it after striking a tree or other nearby object or by following a power line. It can strike any object that provides an easier path to the ground for it than the air. Because of the large network of lines, lightning can strike a utility pole at one point and be transmitted to any location in the network. Because of this, utility companies use multiple grounding and other protective devices per mile to ameliorate the lightning effects.

[0005] There has been a lot of activity in the alleviation of lightning damage but none in utilizing its energy potential.

[0006] U.S. Pat. No. 7,495,168 discloses a dipole lightning conductor which can gather electrical charges from the atmosphere during a thunderstorm, opposite to the polarity of the adjacent cloud on one side and induce a different polarity on the other end contacting the ground. When a sufficient potential difference is reached between the dipole and the earth, a dielectric breakdown occurs sending a large amount of earth charge to the thundercloud, inducing a thunderbolt.

[0007] In U.S. Pat. No. 6,012,330, Palmer discloses a method of inducing lightning strikes by shooting a stream of ionized water into a thundercloud and triggering electrical conduction through the ionized water column to the ground. In this invention, while ionized water is used, advantage is taken also of capillary wetting of conducting mesh cable at the tip of which is tethered a balloon of conductor coated Mylar. It is easier to float a balloon than to pump a column of water to any significant height.

[0008] In U.S. Pat. No. 6,320,119 Gumley discloses a capacitively coupled composite air terminal with sharp and rounded end components for voltage manipulation to minimize electric field ahead of streamers to minimize corona discharge.

[0009] Kato, in U.S. Pat. No. 5,280,335, discloses a compound lightning low voltage arrester with high energy tolerance for power and telephone lines comprising a spark gap is connected to a serial combination of Zinc Oxide arrestor and a non-inductive resistor. By cooperative execution between the spark gap and the Zinc Oxide arrester, the Zinc Oxide is chosen to be of a rating such that thermal breakdown does not occur before the spark gap ignition voltage is reached. The arrangement ensures reliable and predictable discharge and arrester survival even under multiple lightning strikes of close proximity.

[0010] Subbarao in U.S. Pat. No. 4,338,648, discloses a discharge counter and arrester current meter to determine arrester steady state current and the number of discharge events occurring during a thunder storm lightning arrester event.

[0011] Greenwald and Moses in U.S. Pat. No. 5,610,813 disclose a thunderstorm cell detection and mapping system for acquiring localized lightning strike information and identifying and locating active thunderstorm cells.

[0012] In U.S. Pat. No. 4,272,720, a method of differentiating between cloud-cloud and cloud-ground discharges is disclosed. Indicating discharge events with no accompanying lightning ground strike. This indicates that even in the absence of streamers, there is significant electrical discharge that can be converted and stored.

[0013] Weir and Nelson disclose in U.S. Pat. No. 7,033,406, a high energy density ceramic capacitor with energy capacity of 52 kW.h in 2005 cu.in, the equivalent of 1600 $kW.h/m^3$. Hansen in U.S. Pat. No. 6,078,494 discloses multilayer ceramic capacitors comprising doped barium-calcium-zirconium-titanate dielectric, the materials basis for U.S. Pat. No. 7,033,406. It is claimed to be characterized by high dielectric constant, high stability of capacitance value, long service life, low loss factor, high insulation resistance capacitance, low voltage dependence, and wide temperature range stability. Electrodes of base metal alloys from the group of Ni, Fe, Co or their alloys are claimed to be perhaps just as effective as noble metals containing gold, silver, platinum and palladium and may also contain Cr, Ti, Zr, V, Al, Zn, Cu, Sn, Pb, Mn, Mo and W.

[0014] Although the energy density capacity is not disclosed, it may be in the same range as U.S. Pat. No. 7,033,406 showing a path for storing the energy that can be extracted from lightning discharge.

[0015] U.S. Pat. No. 5,361,187, claims dielectric constant (k) of up to 19000 using similar group of dielectrics and processes. In U.S. Pat. No. 5,604,167 dielectric constant values of between 11,000 and 14,000 are disclosed by the same inventor with equivalent materials and processes.

[0016] Since these capacitors use standard powder processing technique, it can reasonably be expected that equivalent characteristics may be observed with naturally occurring doped silicates such as phyllosilicates for example, montmorillonite: $(Na,Ca)_{0.33}(Al,Mg)_2(Si_4O_{10})(OH)_2.nH_2O$, or cyclosilicates such as Benitoite —$BaTi(Si_3O_9)$ as base materials appropriately calcined and doped.

[0017] In U.S. Pat. No. 6,078,494 multilayer ceramic capacitors comprising doped barium-calcium-zirconium-titanate dielectric is disclosed. It is claimed to be characterized by high dielectric constant, high stability of capacitance value, long service life, low loss factor, high insulation resistance and low voltage dependence, and wide temperature range stability. Electrodes of base metal alloys from the group of Ni, Fe, Co or their alloys are claimed to be perhaps just as effective as noble metals containing gold, silver, platinum and palladium and may also contain Cr, Ti, Zr, V, Al, Zn, Cu, Sn, Pb, Mn, Mo and W. In U.S. Pat. No. 5,361,187, the inventors claim dielectric constants of up to 19000 using similar group of dielectrics and processes. In U.S. Pat. No. 5,604,167 dielectric constant values of between 11,000 and 14,000 is disclosed by the same inventors with equivalent materials and processes. Since these capacitors use standard powder processing technique, it can reasonably be expected that equivalent characteristics may be observed with naturally occurring doped silicates such as phyllosilicates for example, various grades of montmorillonite: $(Na,Ca)_{0.33}(Al,Mg)_2(Si_4O_{10})(OH)_2.nH_2O$, or cyclosilicates such as Benitoite—$BaTi(Si_3O_9)$ as base materials appropriately calcined and doped.

[0018] Although the technology to arrest lightning strikes has been around for at least a hundred years, this invention to harness and store that power has only become viable due to recent advances in super-capacitor technology which has made possible the fabrication of ultrahigh capacitance capacitors with very long lifetimes, high power, high energy densities and very fast charge and discharge rates.

[0019] Just as flood water, another destructive force of nature in times past was controlled by building dams, and from the dams eventually came hydroelectric power; and wind including thunderstorms has now been harnessed to generate electricity, this invention describes the technology to harness the power of atmospheric discharges including lightening storms to generate useable electrical energy.

[0020] This disclosure also introduces the concept of an Energy Dam. Facilities of substantial energy storage capacity capable of receiving energy feeds from various energy sources such as Solar, Wind, Thermal Power plants and Lightning. For example, during a thunderstorm, electricity generated by wind and lightning is collected and stored.

[0021] Lightning strikes every part of the globe but not uniformly. The regions with the highest historical concentration of lightning strikes are shown in FIG. **1***c*. These include Florida and the Gulf Coast in the Americas, the Equatorial Highlands of DRC, Rwanda and Burundi in Central Africa and the Monsoon Belt in Asia.

[0022] Except for the Americas, typically, these regions have very little electricity infrastructure. With the capability disclosed here, substantial reserves of electricity can be generated, stored and possibly traded.

[0023] In regions of epileptic electricity supply, disruptions in power do not necessarily translate into disruption in service. Since when power is generated, it is fed into these energy dams or local storage units for eventual use. Just as in water supply, the customer is not necessarily conscious of when the local water company is pumping water into storage tanks or local dams, in energy dams, the customer need not be conscious of whether or when electricity is being generated by the utility company because the power to his home is drawn not necessarily live from the grid but from the local energy storage units or energy dams.

BRIEF SUMMARY OF THE INVENTION

[0024] A method of harnessing atmospheric discharge and storing said energy in a useful form for subsequent use is presented.

[0025] Since the voltage of a lighting bolt can be as high as 100 MV, a methodology for safely channeling this discharge for storage is disclosed.

[0026] It is the also the object of this invention to present a storage medium in which an energy capacity of 1 MW.h in a volume of under 1 m^3 can be achieved.

[0027] It is also a further objective of this invention to show how lightening strikes on tall buildings can be harnessed to provide energy for the building either directly or fed into the grid.

[0028] It is also an objective of this invention to present a methodology for harnessing lightening, heretofore a source of power disruptions for electricity grids and converting it into a useable form of energy and feeding it back into the grid.

[0029] Since each electricity grid has a lightning suppression unit, a methodology for harnessing the impulse from these units from lightening strikes and feeding it back into the grid is disclosed.

[0030] a method of deploying a network of said storage units along a utility grid is also disclosed.

[0031] It is also the objective of this invention to disclose a method of modifying the storage units for single building deployment.

[0032] A method of deploying said storage units as vehicular charging centers even in locations not readily served by a utility grid is also disclosed.

[0033] A method of manipulating the direction and movement of the lightening bolt in open air locations and redirecting them to predetermined collection points is disclosed.

[0034] Lightning storms are some of the major causes of wild fires in the world. A method of redirecting the electrical discharges in any given space via a network of polarized and non-polarized collectors is presented. The discharges can be stored, fed into the grid or grounded.

[0035] A method for non-spontaneous discharge generation and storage is disclosed. And a method for adapting the methodology for electric automotive deployment is also disclosed.

BRIEF DESCRIPTION OF DRAWINGS

[0036] For understanding of the present invention reference is made of the accompanying drawings in the following DETAILED DESCRIPTION OF THE INVENTION. In the drawings:

[0037] FIG. **1***a*. Picture of lightning strike over a city.

[0038] FIG. **1***b*. Picture of lightning strike over open plain.

[0039] FIG. **1***c*: Global Distribution of Lightning Strikes: April 1995-February, 2003. (Source: NASA).

[0040] FIG. **2** shows a schematic of discharge collection and storage system.

[0041] FIG. **3** shows a schematic of collection unit showing metallic composition variation.

[0042] FIG. **4** Shows a Schematic of composite collector showing polarized ends.

[0043] FIG. **5** Schematic of collector network configuration with negatively polarized ends to manipulate and redirect lightning electrical discharge away from the earth for eventual collection at a predetermined location.

[0044] FIG. **6** Plan view of polarized collection network as shown in FIG. **5** acting to concentrate and modulate the electrical discharge and redirect such for collection at predetermined location.

[0045] FIG. **7***a*. Schematic showing a representation of a network of varistors arranged in rows and columns with the net effect of applying resistive arrestors in parallel and in series to effect voltage mitigation of atmospheric discharges prior to collection and storage.

[0046] FIG. 7*b:* Schematic of varistor of power mitigation unit showing cascade of ZnO arrestor in series with non-inductive resistor in parallel with spark gap.

[0047] FIG. 7*c:* Multilayer varistor with ZnO, ZnS and WO_3/WSi_2

[0048] FIG. **8***a*. Schematic showing cross section of a collection unit.

[0049] FIG. **8***b*. Schematic showing cross-section of multilayer ceramic capacitor of **8***a*.

[0050] FIG. **9** Schematic of collection unit network mesh in forested area with air frames deployed on each tree as collection of trees linked in a mesh network.

[0051] FIG. **10** Plan-view schematic of collection unit network mesh of FIG. **9**

[0052] FIG. **11** Schematic showing collection unit deployment on electricity transmission poles linked in a network and fed into the electricity grid.

[0053] FIG. **12** Schematic showing collection unit deployment on light poles or wireless towers.

[0054] FIG. **13** Schematic showing network of linked collection units and storage units on transmission lines, light poles or wireless towers fed into the grid.

[0055] FIG. **14**. Schematic of a system for non-spontaneous atmospheric discharge generation and storage.

[0056] FIG. **15** Schematic of atmospheric discharge collection and storage unit deployable on automotive units.

[0057] FIG. **16** Schematic of balloon-assisted discharge collection and storage unit.

DETAILED DESCRIPTION OF THE INVENTION

[0058] This invention describes a method of harnessing the electrical energy in atmospheric discharges, including, but not limited to lightning, storing said electrical energy and transmitting said energy for use. To this end, as an illustration, the preferred embodiments are represented in the drawings shown in FIGS. **2** to **15**.

[0059] Since lightning discharge voltages range from 10 MV to 100 MV with current of 10 kA to 100 kA, the technology challenge will be in mitigating the ultrahigh power which range from 100 GW to in excess of 10,000 GW. Although individual strikes last less than 100 μsec, thunderstorms usually last longer than 30 min. in any cloud formation and location. Indicating that the energy that can be mined from any location in a thunderstorm can run in excess of 50 GW.H. Enough energy for 500,000 homes consuming 1000 kW.h per month. At $100 per 1000 kWh, the revenue equivalent is $5 million per thunderstorm per location.

[0060] In solar energy generation, the cost of a 1 MWe rating PV panel is about $1 million. To achieve 1 GWe, the cost implications will be about $1 billion. In fossil fuel plants, the construction cost is approximately $1.3 million per MWe, putting the cost for a 1 GWe at ~$1.3 billion excluding fuel, carbon footprint, and other operating cost. Though thunderstorms are not continuous, with storage capability, the cost basis for an atmospheric discharge energy source will be several orders of magnitude lower than fossil fuel or solar of any architecture.

[0061] One embodiment of this invention is depicted in FIG. **2**. Lightning is collected at the air terminals **10**, **20** and transmitted through the conductor **30** to an arrestor **40** and on to the capacitor **50** where the electricity is stored. From which it can be extracted **60** at point of use or transmitted into the grid.

[0062] The degree of atmospheric discharge charge collection can be influenced by the metallurgical composition of the collectors. FIG. **3** illustrates the fabrication of the collector with different metals of varying conductivities and atmospheric and electrical stability. In this embodiment, metallurgical compositions for the various segments comprise Ti, Cu, Al. Other metals or their alloys can be used depending on the required properties and the locations of deployment.

[0063] In yet another embodiment of the invention as shown in FIG. **4**, a composite collector with opposite polarity air terminals **100**, **110** is used. The air terminals are isolated from each other by an insulator **120**. The negative polarity terminal serves to deflect and manipulate the charge to the positive terminal from which it is conducted to the storage unit **130**.

[0064] Another embodiment of the invention is illustrated in FIGS. **5** and **6**. In this representation, negative polarity collectors, **160** deflect the atmospheric discharge so that they do not reach the ground but are deflected for collection at a predetermined terminal **180** of positive polarity and thereafter storage **200**. A plan view representation of this embodiment is shown in FIG. **6**.

[0065] It is essential to mitigate the power of the lightning before storage. In one embodiment of this invention, a collection of varistors of various power capacities, linked in series **270**,**280** and **290** are connected in parallel in lines **1** to n, to achieve a desired capability as shown in FIG. **7***a*. The resultant power is stored in the capacitor **300**. An insulator or fuse **305** is placed at the end of the varistor chain to protect the capacitor **300** against over-current. In the event of overstressing, the dielectric or varistor is deformed and the excess current is grounded.

[0066] Each component of the power mitigation unit is any of the following configurations as shown in FIG. **7***b:* A ZnO varistor **312** connected in series with a non-inductive resistor **313** and in parallel with a spark gap **311**. The resultant current is further modulated through another ZnO unit **314** and resistor **315**. A cascade of this configuration could be adopted to achieve the desired properties.

[0067] Zinc Oxide has a relatively large band gap of ~3.3 eV at room temperature. The consequence of this large band gap includes, higher breakdown voltages, ability to sustain large electric field and high power and temperature operation. Because of this, ZnO is the primary component in varistors and in voltage suppression devices. Zinc Sulfide has a band gap of 3.5 eV for the cubic form and as high as 3.91 eV for the hexagonal form at 300K. While ZnO band gap can be tuned from between 3-4 eV by alloying with magnesium oxide or cadmium oxide, the co-processing of ZnO with ZnS of the hexagonal wurtzite form should provide electrical field and other operational advantages over ZnO alone.

[0068] Multilayers of ZnO and ZnS or as sandwich layers with each other with ZnO achieving 50-99.9 mol. % of each layer can be adopted to improve on the suppression properties of the single layer ZnO varistor as is shown in FIG. **7***c*. Said varistor comprising a ceramic base body **318** of multiple layers, terminal electrodes **316**, **317** and internal electrodes **319**.

[0069] Alloying of ZnO with metal oxides and nitrides of transition elements including W, Zr, Mo, Mg, Cr, and Ti may improve its band gap characteristics and improve its voltage response non-linearity. Tungsten, in the form of tungsten silicide has very unique crystallization characteristics, particularly in the presence of dopants such as phosphorus or arsenic. Upon post deposition anneal, the Si in the non-stoichiometric tungsten silicide (WSix) segregates to the grain boundaries and the film interfaces. The dopant atoms diffuse preferentially along the grain boundaries. When oxidized, it is the segregated silicon that is oxidized selectively. If the W is exposed to the oxidizing ambient of O_2/Ar or O_2/N_2 at temperatures in excess of 700° C., tungsten oxide WOx (x=3, or 1.5) is formed. It has no corresponding crystallographic orientation to the underlying tungsten silicide or metal, being in the form of an amorphous powder. The fabrication of multilayer varistors with ZnO and WSi_2/WO_3, SiO_2 should provide the flexibility of modulation of the effective grain sizes of the host material to within 0.5-10μ as the case may be. This precise grain size control provides corresponding modulation of the electrical properties including overvoltage suppression.

[0070] A schematic of the storage unit **320** is shown in FIG. **8***a*. A collection of capacitors **330** are connected in parallel to achieve a desired capacitance. A schematic of the cross-section of each capacitor unit is shown in FIG. **8***b*. The unit **331** with dielectric layers **332** is a multilayer capacitor comprising alternately stacked internal electrodes **335**, **336** connected to external electrodes **333**, **334**. The dielectric layers may be of uniform composition, or layers of different compositions optimized for flexibility in the modulation of desired electrical, physical and reliability properties.

[0071] Capacitance in excess of 1 kF/m^3 with energy storage capacity of 1.5 MW.h is reported as being possible by existing art. With compositional and manufacturing improvements disclosed here these benchmarks are expected to be surpassed making possible energy storage capacities of up to 1 GW.h. Sufficient energy for 1000 households consuming 1000 kW.h of electricity per month for one month.

[0072] Lightning storms are a major cause of wildfire. To address this, in yet another embodiment of this invention as represented in FIG. **9**, air terminals **360** are set up on a selection of trees and connected by a conductor **370** in a mesh array as shown in FIG. **10**. The impinging charge is transmitted through a conductor **380**, through a suppressor unit **390** and on to the storage unit **400**.

[0073] Utility transmission lines usually have lightning collectors along the length of the network. In this invention as demonstrated in FIG. **11** air terminals **440** deployed transmission poles **450** are linked by a polarized conductor **460**. At predetermined locations the impinging charge is conducted through a suppression unit **490** and thereafter into the storage unit **500**. The stored energy is periodically released into the grid.

[0074] In yet another embodiment of the invention, air terminals **510** are deployed on light poles **520**. The collected charged are modified and stored in a storage unit **540**.

[0075] In another embodiment, the air terminal/collection units are deployed on radio transmission towers. The charge could be stored individually at each tower location or linked in a network as shown in FIG. **13**. In either case, the stored energy be used at each individual location or fed into the grid **570**.

[0076] In the absence of a thundercloud, lightening flash can be generated by the modification of the natural bias between the cloud and ground. This is demonstrated in FIG. **14**, where a positively biased conductor **580** of height greater than nearest ground elevation or nearest structure. The increased elevation and bias facilitates cloud to ground discharge even when there is no active lightning storm. The incoming charge is isolated by an insulator **600** and stored in the storage unit **610**.

[0077] In yet another embodiment of this invention, a balloon of conductive material is tethered to a terminal via a mesh line of conducting material. The balloon captures cloud to cloud discharges which are transmitted down to storage. In yet another embodiment this tether line may be wetted by a conductive solution such as but not limited to salt solution to facilitate the discharge conduction.

[0078] Another embodiment of this invention is shown in FIG. **15**. In an isolated collection system as shown here, the air terminal **620** which may be biased or unbiased is connected to a collection/storage unit **650**, **660** respectively by conductor **640** and isolated by a dielectric or insulator **670**. Should the discharge exceed the capacity of the isolation, the isolation is bridged and the charge grounded. This isolated collection system is particularly useful where there is no utility grid, particularly in very remote and isolated locations.

[0079] This isolated collection capability enables deployment on individual houses and isolated farms. In electric automotive recharge stations, this capability enables the location of these facilities in any location even those not served by regular electricity utilities lines.

[0080] In isolated rural areas, the deployment of these isolated collection units enables the provision of electricity where electricity grid infrastructure is not available or practical. The storage units can be deployed in banks as the estimated anticipated usage dictates.

[0081] In another embodiment of this invention, the isolated collection unit is modified to be portable for deployment on automobiles. The charge in the storage unit is linked with the automobile's electrical power or storage unit. Alternatively, it can replace the power storage unit of the automobile for pure EV or hybrid cars. Additionally, it can unplug these cars from the grid. With the ambitious industry plans for electric or hybrid cars the infrastructure for charging these cars either in garages or charging stations is somewhat limited. The capability to both 'charge as you go' and unplug from the grid would expand the infrastructure significantly.

[0082] In yet another embodiment of this invention, the isolated collection unit is deployed on trains. This could be in commuter trains that directly fed from the grid, or long-haul trains to augment or replace the fossil fuel used.

[0083] It is understood that the presentation of these steps in this disclosure is not exhaustive. Only the preferred embodiments of the invention and but a few of the examples of its versatility are shown and described in the present disclosure. It should be readily apparent to those of ordinary skill in the art that the invention is capable of use in various other combinations, environments and applications and is capable of changes or modifications within the scope of the inventive concept as expressed herein. These changes and modifications may be made without departing from the spirit and scope of the invention as set forth in the appended claims.

REFERENCES

[0084] U.S. Pat. No. 7,495,168,
[0085] U.S. Pat. No. 6,012,330
[0086] U.S. Pat. No. 6,078,494
[0087] U.S. Pat. No. 4,338,648
[0088] U.S. Pat. No. 6,407,900
[0089] U.S. Pat. No. 6,924,598
[0090] U.S. Pat. No. 5,569,972

[0091] U.S. Pat. No. 5,289,335
[0092] U.S. Pat. No. 4,272,720
[0093] U.S. Pat. No. 4,338,648
[0094] U.S. Pat. No. 5,610,813
[0095] U.S. Pat. No. 6,320,119
[0096] U.S. Pat. No. 5,604,167

1. A method of converting an atmospheric electrical discharge into a useable form of electrical energy comprising the following steps:

(a) Arresting the discharge via an air terminal,
(b) Said air terminal connected via a conducting unit to a power mitigating (step down) unit which can reduce the discharge voltage from approximately higher than 100 MV and 100 KA to below 20 kV, 10 kA.
(c) The step down unit connected to an energy storage unit which may comprise modules of high energy density capacitors
(d) Said storage units arranged such that the stored electrical energy can be discharged into the grid or to an appliance at point of use as desired.

2. A method of claim **1** wherein the arrestor and mitigating unit comprise an array of self-healing varistors in series and parallel chosen to ensure total conversion of the incident lightning discharge to a voltage/current level suitable for storage in said capacitors.

3. A method of claim **2**, where the power mitigation unit is any of the following configurations:

(a) Single ZnO varistor or
(b) Zinc Oxide arrester connected in series with a non-inductive resistor
(c) Zinc Oxide arrester in series with said non-inductive resistor and in parallel with a spark gap.
(d) A cascade of configuration as described in (c).

4. A method of claim **1** wherein the storage unit comprises modular array of high energy density doped ceramic capacitors with storage capacity of 10 kWe.h to 1 GWe.h and volume 0.1 to 1 m^3 and up to 1000 units as the desired capacity dictates.

5. A method of broad spatial lightning protection by the manipulation of the path of an electrical discharge via the manipulation of the air terminal bias magnitude and polarity Said arrestors being arranged in an array to achieve the redirection of the discharge path. The discharge path being directed to a collection unit at some location significantly removed from the initial discharge impact position.

6. A method of claim **5** wherein the discharge redirection is via a biased conductor to the said collection and storage unit.

7. A method of claim **5** wherein the area of protection is a forest whereby:

(a) A network array of air terminals is deployed on trees, in close proximity to said trees with tip approximating the treetops, or girding the trees to redirect the discharge along a biased conductor to a collection unit for the purpose of mitigating lightning induced fires.
(b) Said discharge electrical energy being stored or fed into the electricity grid.

8. A method of claim **1** wherein the discharge collection is on electrical power lines and the stored energy is fed back into the grid.

9. A method of claim **1** wherein the discharge collection and storage are at telecom towers, light poles or other free standing structures. Said storage being at individual collection sites or some location serving an array of collectors and said stored energy used for individual structure's operational energy need or fed back into the utility grid.

10. A method of non-spontaneous generation of atmospheric discharge by the following:

(a) Modulation of the magnitude and bias in a dipole air terminal relative to the ground
(b) Conductive material balloon tethered by a conductive mesh cable.
(c) Said cable being soaked by an ionic liquid, including, a salt solution to facilitate said atmospheric discharge conduction.

The discharge thus formed is stored for feeding into the greed or for operation as a stand-alone energy dam.

11. A method of claim **1** in which the discharge collection unit is configured as a mobile unit. Said unit being deployed on an automobile or any mobile platform. The said deployed unit extracting electrical charge from the atmosphere and storing such energy in a deployed storage unit on the said automobile. The energy thus stored, feeds the car battery which obviates the need for recharging at charging centers or from the grid.

12. A method of claim **1** wherein the electrical discharge energy collection unit is a stand-alone unit comprising modular capacitors configured as an electric vehicle charging station.

13. A method of claim **1** wherein the air terminals are deployed on buildings and the discharge energy collected thereby are:

(a) Stored and fed back into the grid.
(b) Stored for use by each building
(c) Stored in a central energy storage facility for use by the community in general.

14. A method of claim **1** wherein the said storage units are underground.

15. A method of claim **1** wherein the storage unit is of capacity and configuration to accept energy feeds from multiple electricity generation sources: Thermal, Hydro, Solar, Wind and Lightning.

16. A method of claim **4** wherein the storage unit is integrated into a Utility's Switch Farm.

17. A method of claim **4** wherein the multilayer ceramic capacitor unit comprises dielectric layers of varying compositions individually or as sandwich layers with each other containing Barium-Titanate silicates as host material doped with Zr, WSi_2/WO_3 to modulate grain growth to between 0.1 to 10 μm as the case may be; said modulation providing corresponding control of electrical and reliability properties.

18. A method of claim **1** wherein the varistor comprise multilayers of ZnO and ZnS individually layered or as sandwich layers with each other with ZnO achieving 50-99.9% of each layer; said layers being alloyed metal oxides of transition elements including W, Zr, Mo, Mg, Cr, Ti to improve voltage response non-linearity.

* * * * *

(19) **United States**
(12) **Patent Application Publication**
Rodriguez Montes et al.
(10) **Pub. No.: US 2011/0075316 A1**
(43) **Pub. Date: Mar. 31, 2011**

(54) **SYSTEM FOR RECOVERING AND USING THE ELECTROSTATIC CHARGE GENERATED BY LIGHTNING**

(76) Inventors: **Angel Rodriguez Montes**, Ordino (ES); **Antonio Claveria Canal**, La Massana (ES)

(21) Appl. No.: **12/891,388**

(22) Filed: **Sep. 27, 2010**

(30) **Foreign Application Priority Data**

Sep. 29, 2009 (ES) 200901924

Publication Classification

(51) **Int. Cl.**
H05F 7/00 (2006.01)

(52) **U.S. Cl.** **361/225**

(57) **ABSTRACT**

A system for the recovery and use of the electrostatic charge present in the atmosphere during storms generated by lightning, transforming natural energy into electrical energy useful for consumption, and providing the necessary protection for lives and property against electro-atmospheric phenomena, has an ecological lightning conductor, an electrical conductor connected by one end to the low-frequency electrode of the lightning conductor, and an enhanced intelligent earth wire, whereto the conductor is joined by its other end. The conductor includes a series of probes and magnetic field detectors which will send information to the microprocessor and from there to the mainframe computer. The control device allows regulation of the earth resistance, thereby generating more or less charge, diverting the energy to the accumulators or to earth through dissipator electrodes.




1
5
2
9
3
8
6
10
7
12
6
11
4
11

FIG. 1


13
14
15
16
1
5

FIG. 2


14
13
15
16
1
5

FIG.3

SYSTEM FOR RECOVERING AND USING THE ELECTROSTATIC CHARGE GENERATED BY LIGHTNING

CROSS-REFERENCE TO RELATED APPLICATION

[0001] The invention described and claimed hereinbelow is also described in Spanish Patent Application ES 2009 01924 filed on Sep. 29, 2009. This Spanish Patent Application, whose subject matter is incorporated here by reference, provides the basis for a claim of priority of invention under 35 U.S.C. 119(a)-(d)

BACKGROUND OF THE INVENTION

[0002] The present invention relates to a system which allows the recovery and use of the electrostatic charge present in the atmosphere during storms which generates lightning, thereby achieving the transformation of natural energy into electrical energy useful for domestic and industrial consumption, while providing essential and adequate protection to persons, animals and property against the aforementioned atmospheric electrical phenomena.

[0003] Different technical and scientific arguments relative to the effective application of the system that is the object of this invention will be explained in detail in this description, in addition to describing the elements that compose the aforementioned system.

[0004] During an atmospheric storm formation process, variable electrical fields appear which are responsible for the generation and appearance of lightning, which are discharges between the ground and the atmosphere. As a result of the generation of electrical charges within the cloud, the atmosphere increases its electrical potential, inducing a variable ground voltage.

[0005] It has been scientifically proven that if this ground voltage is controlled, the current flowing through the ground can also be controlled, thereby adequately leveraging the full potential of this energy.

[0006] This will primarily avoid the electrical saturation of that area, which could call, excite or create a lightning bolt therein and, secondly, this energy may be accumulated in the most adequate manner.

[0007] This process for recovering energy from the atmosphere is carried out before and during the first phase of the generation of lightning charges. The effect of attenuating the electrical field of the atmosphere causes the disappearance of the lightning discharge to ground, on not having sufficient potential for formation thereof, thereby allowing prevention and protecting persons, animals and property.

[0008] Widely known are the experiments and achievements of Benjamin Franklin in the 18th century, inventor of the passive lightning conductor equipped with a priming device or those developed subsequently using the "multipoint" system, the action of which is based on ionisation and excitation, constant or by impulses, of the electro-atmospheric field in order to capture the lightning discharge.

[0009] Mention must be made of radioactive lightning conductors, currently in disuse for evident safety reasons due to radiation hazard; likewise, other devices based on the filtration of high frequencies and harmonic components are also known to exist, equipped with two or more external electrical connections and having different components such as coils, resistors and condensers, duly connected and having the necessary siliceous sand for absorbing the thermal inertia produced when the system functions as a whole.

[0010] Reference is made herein to patent of invention P 200202884/2, by the same inventors, which relates to a deionising lightning conductor of electrostatic charge, based on three insulators equipped with a variable noble gas dielectric in its interior.

[0011] According to the data provided by the world meteorological detection system, more than four thousand storms form in the Earth's atmosphere every day, which generate around eight million lightning bolts.

[0012] The phenomenon called "lightning" is the electrical reaction caused by the saturation of electrostatic charges generated by the progressive accumulation of an electric field between the ground and the cloud, during the activation of a typical storm.

[0013] This phenomenon is randomly present as of an electro-atmospheric potential of 10/45 kV. It is generated between two points of attraction of different polarity and same potential for the purpose of compensating the saturation of the electrostatic charge. Lightning charge density is proportional to the saturation of the electrostatic charge of the area: the higher the charge density, the higher the risk of generating a tracker or "leader" and, subsequently, a lightning discharge.

[0014] Lightning charge intensity is variable, depending on the critical moment when the resistance in the air between the two transfer points break down; it will also be influenced by serially exposed materials such as soils, rocks, wood, iron or other metals, lightning conductors, earth wires, etc. A lightning bolt can transport an average charge of 20 GW of power per second, equivalent to one hundred million ordinary incandescent light bulbs.

[0015] This electrical phenomenon is represented in the form of an electronic shadow, which determines the elements that will be affected by charge exchange.

[0016] Studies carried out on the electro-atmospheric field at ground level reveal that charge distribution during the generation of the high-voltage field is not static but rather dynamic, on being randomly formed and generating the moving tracker or leader and different geographical points at the same time. The intensity and location of this electronic shadow can change radically and affect the low or lateral areas of high structures or buildings.

[0017] The behavioural study of a conventional pointed lightning conductor has demonstrated that they generate, to a greater or lesser extent, electromagnetic effects in the installations themselves, as well as in neighbouring installations, upon capturing the lightning bolt. In the case of ionising lightning conductors, accidents frequently occur for this reason.

[0018] Recently, enhancements made in electrostatic charge deionising lightning conductors through the application and incorporation of new technologies, such as a special cable adaptable to different forms of energy transport, eliminates causes of accidents and improves the reliability of the facilities, in addition to acting within an ecological electrical environment free of electromagnetic interferences.

SUMMARY OF THE PRESENT INVENTION

[0019] Accordingly, it is an object of the present invention to provide a new system which allows recovering and using the electrostatic charge generated by lightening and provides for highly advantageous results.

[0020] In keeping with these objects this system allows to cover all levels of electrical risk, diversity in the type and polarity of lightning bolts for any type of structure. It is an individual and collective protection system which bases its operating principle on the orderly transformation of ions flowing in a current, and is useful for working at low voltages and previously be derived to an accumulation area.

[0021] The system is composed of an external electrode acting as an ecological lightning conductor, an electric conductor, designed and calculated for a wide range of frequencies, and having anti-corrosive protection and an intelligent earth wire, complemented by energy accumulators and dissipator electrodes, capable of deriving all current leakage to earth, all of said components being controlled by a microprocessor which manages the energy as it appears, controlling its intensity, as well as the charge of the aforementioned accumulators for subsequent consumption.

[0022] The system also incorporates an alarm-based alert device, both private and public, for occupational risk prevention management against lightning risk.

[0023] At meteorological level, the system allows data to be obtained relative to the behaviour of the electric field, temperatures, atmospheric pressure, humidity and quantity of discharges.

[0024] The invention being described incorporates magnetic field detectors and detectors for controlling earth leakage current intensity, for subsequent analysis thereof and the consequent alarms. These detectors send the information to the microprocessor, upon recording the abrupt magnetic field variations.

[0025] The deionisation system of the lightning conductor itself facilitates the appearance of small currents in the earth wire, where charges are intelligently accumulated for subsequent use thereof. Depending on the intensity of the natural earth electric field, the ecological lightning conductor system generates the appearance of an earth leakage current which passes through the electrical conductor from the lightning conductor, strictly speaking, to the earth wire. The automatic control system regulates earth resistance in order to generate more or less charge and divert energy to the accumulators or to the enhanced intelligent earth wire.

[0026] The intelligent earth wire incorporates an electronic system which automatically regulates its own electrical resistance with reference to the physical earth. This control system allows controlled energy transfer, maintaining a resistance of less than 5 ohms in the earth installation during the four seasons of the year and varying, as required, the electrical conductivity of the physical earth and its humidity in order to facilitate or stop leakage currents.

[0027] The intelligent earth wire consists of special electrodes, according to the type of soil and/or terrain, aimed at facilitating current leakage and avoiding corrosion of the metals. These electrodes are installed conveniently protected against the aggressiveness of any chemical or electrochemical reaction.

[0028] The novel features which are considered as characteristic for the present invention are set forth in particular in the appended claims. The invention itself, however, both as to its construction and its method of operation, together with additional objects and advantages thereof, will be best understood from the following description of specific embodiments when read in connection with the accompanying drawings.

BRIEF DESCRIPTION OF THE DRAWINGS

[0029] FIG. **1** is a longitudinal diagram of the system in accordance with the present invention, illustrating the layout of the different components thereof;

[0030] FIG. **2** shows an outer view of the ecological lightning conductor of the inventive system; and

[0031] FIG. **3** is a complementary view of the preceding figure, showing a fully sectional view of the lightning conductor of the inventive system.

DESCRIPTION OF THE PREFERRED EMBODIMENTS

[0032] A system for recovering and using the electrostatic charge generated by the lightning of the present invention includes an ecological lightning conductor **1**, disposed on a mast **2**, which is installed at the highest point of the existing structure by means of adequate bearings or on a newly built tower, an electrical conductor **3** and an intelligent earth wire **4**.

[0033] The electrical conductor **3** is connected by one end to the mast or low electrical resistance electrode **5** of the lightning conductor **1**, and connected to the intelligent earth wire **4** by the other end, said conductor incorporating a series of probes **6** and magnetic field detectors **7** that will send information to the microprocessor **8**.

[0034] These data, recorded by the microprocessor **8**, are sent to a mainframe computer **9** where they are processed, being immediately displayed on a screen or sent to an "Internet"-type data transport network.

[0035] The intelligent earth wire **4** is equipped with a control device **10** which will analyse, in real time, the earth current leakages, sending the data to the aforementioned mainframe computer **9**. Depending on the intensity of the leakage, the system will manage the information, generating alarms or modifying the processes for sending current to the energy accumulators **11**, disposed next to the intelligent earth wire **4**. This earth wire **4** also has dissipator electrodes **12** at ground level.

[0036] The ecological lightning conductor **1** has a toroidal-shaped body **13**, closed by its upper part by an upper frame **14** and completed by a lower frame **15** whereto, in the central appendix **16** of its lower part, is fixed to the mast or low electrical resistance electrode **5**.

[0037] The dielectric product, which is essential for the object to act as a lightning conductor in itself, is disposed in the interior of the toroidal body **13** of the ecological lightning conductor. The dielectric product can be of noble gas.

[0038] The previously described characteristics of the ecological lightning conductor confer the quality of deionising lightning conductor to this system component, which allows the appearance, as mentioned earlier, of small currents in the intelligent earth wire **4**, where the charges are accumulated for their subsequent consumption in the energy accumulators **11**.

[0039] During a storm process, a high-voltage field is generated at ground level which is proportional to the charge of the cloud and the distance that separates it from the ground.

[0040] As of a certain magnitude of the natural electric field on the physical earth, the equipotential installation of earth wires of the system facilitates transfer of the charges through the electrical conductor **3**, charges which, regardless of their polarity, are concentrated on the mast or lower electrode **5** of the lightning conductor **1**, disposed at the highest point of the installation that configures the system, which is connected to the earth wire by means of the electrical conductor **3**. The current that circulates through the lightning conductor-conductor-earth wire system is proportional to the charge within the cloud.

[0041] The low resistance of this mast or lower electrode **5** of the lightning conductor **1**, facilitates the capture of opposing charges in the electrode or upper body **13**. During this energy transfer process, a small current flow takes place between the cathode and anode in the interior of the lightning conductor, in the direction of the current flow.

[0042] The resulting effect causes the appearance of a weak leakage current that derives to the electrical earth wiring of the installation, which is controlled by a microprocessor **8** which, in turn, causes current shunting to an accumulation system **11** or to dissipator electrodes **12** at ground level.

[0043] The evolution of the electro-atmospheric phenomenon is recorded in a database by means of electric probes **6** installed in the electrical conductor **3**, disposed between the lightning conductor **1** and intelligent earth wire **4**, and magnetic field detectors **7**. The data are stored, in real time, in a microprocessor **8** thanks to the transfer of data from the probes **6** to the mainframe computer **9**, via radio or conductor. These data may be viewed on a PC screen and statistics calculated, both real time and historical, for the purpose of carrying out electromagnetic and electrical prevention studies.

[0044] The novel technology of the system that is the object of the invention, and which is being described, allows optimisation of industrial process management and enhancement of personal electrical safety.

[0045] Depending on the intensity of the current that flows through the conductor **3** towards the earth wire **4**, high electric field alarms may be generated, consequently alerting of the risk of electrical storm in the area, with lightning activity.

[0046] Having sufficiently described the characteristics of the system that is the object of the present invention, we must point out that any variation in dimensions, shapes, types of materials and layout of the different components shall not alter the essentiality of the invention and may be necessary according to the protection requirements of the desired area, based on factors such as the geographical area, environmental context and dimensions.

[0047] It will be understood that each of the elements described above, or two or more together, may also find a useful application in other types of constructions differing from the types described above.

[0048] While the invention has been illustrated and described as embodied in a system for recovering and using the electrostática charge generated by ligntening, it is not intended to be limited to the details shown, since various modifications and structural changes may be made without departing in any way from the spirit of the present invention.

[0049] Without further analysis, the foregoing will so fully reveal the gist of the present invention that others can, by applying current knowledge, readily adapt it for various applications without omitting features that, from the standpoint of prior art, fairly constitute essential characteristics of the generic or specific aspects of this invention.

What is claimed as new and desired to be protected by Letters Patent is set forth in the appended claims.

1. A system for recovering and using an electrostatic charge generated by lightning and being present in an atmosphere during storms for transforming a natural energy into electrical energy and providing a necessary protection to persons, animals and property, the system comprising components including an element selected from the group consisting of an external electrode and an ecological lightning conductor, a mast fixing said electrode, an intelligent earth wire, an electrical conductor joining said element to said intelligent earth wire, energy accumulators, dissipation electrodes, electric probes, magnetic field detectors, and a microprocessor controlling all the components of the system and transferring data to a mainframe computer.

2. A system for recovering and using the electrostatic charge as defined in claim **1**, wherein said ecological lightning conductor has a toroidal-shaped body housing containing a dielectric product, an upper frame closing said body, a lower frame completing said body, and a lower central appendix in which a member selected from a group consisting of said mast and a low electrical resistance electrode is fixed.

3. A system for recovering and using the electrostatic charge as defined in claim **2**, wherein said toroidal-shaped boyd of said ecological lightening conductor contains a noble gas.

4. A system for recovering and using the electrostatic charge as defined in claim **1**, wherein said electrical conductor has one end connected to a member selected from the group consisting of a mast and an electrode and is designed for a wide range of frequencies and has adequate anti-corrosion protection, said electrical conductor also having another end joined to said intelligent earth wire, said electrical conductor incorporating said electric probes and said magnetic field detectors.

5. A system for recovering and using the electrostatic charge as defined in claim **1**, wherein said intelligent earth wire is provided with disipator electrodes at a ground level according to a type of a component selected from the group consisting of soil, terrain and both.

6. A system for recovering and using the electrostatic charge as defined in claim **1**, further comprising a control device analyzing earth current leakages in real time and sending data to the mainframe computer, generating according to a leakage intensity, alarms or modifying a process for sending current to said accumulators.

* * * * *

US 20140042987A1

(19) **United States**
(12) **Patent Application Publication**
LAI

(10) **Pub. No.: US 2014/0042987 A1**
(43) **Pub. Date: Feb. 13, 2014**

(54) **LIGHTNING ENERGY STORAGE SYSTEM**

(75) Inventor: **JAMES CHYI LAI**, Saint Paul, MN (US)

(73) Assignee: **NORTHERN LIGHTS SEMICONDUCTOR CORP.**, SAINT PAUL, MN (US)

(21) Appl. No.: **13/571,057**

(22) Filed: **Aug. 9, 2012**

Publication Classification

(51) **Int. Cl.**
H02J 7/00 (2006.01)

(52) **U.S. Cl.**
USPC **320/166**

(57) **ABSTRACT**

Embodiments of the present invention relate to an apparatus and method for collecting and/or storing electrical energy in lightning. A specific embodiment provides a lightning energy storage system that includes a lightning rod, a wire, a lightning energy harvester, and a ground rod. The lightning rod is configured to attract lightning and transfer electrical energy. The lightning energy harvester incorporates at least one magnetic capacitor and a switch. The ground rod is connected to the wire. A control signal controls the switch to direct the electrical energy to ground through the ground rod or to direct the electrical energy to charge the magnetic capacitor, in response to a charging state of the magnetic capacitor.




101
200
102
103
104

Fig. 1


200
210
230
220

Fig. 2


240
200
200
250
253

Fig. 3


switch
transformer
detector

Fig. 4


101
102
201
103
104

Fig. 5

LIGHTNING ENERGY STORAGE SYSTEM

TECHNICAL FIELD

[0001] Embodiments of the present invention relate to an energy storage system. Specific embodiments pertain to a lightning energy storage system.

BACKGROUND OF INVENTION

[0002] For years people have been attempting to find an effective and inexpensive energy source for various energy consuming facilities of modern day living, commerce, and technology. One of the prime concerns in utilizing the energy sources is how to achieve environmentally protective eco-friendly resources.

[0003] Lightning is a phenomenon of an atmospheric electrical discharge. When the electric field becomes strong enough, an electrical discharge (the bolt of lightning) occurs within clouds or between clouds and the ground. Lightning occurs with both positive and negative polarity. An average bolt of negative lightning carries an electric current of 30,000 amperes (30 kA), and transfers 15 coulombs of electric charge and 500 megajoules of energy. Large bolts of lightning can carry up to 120 kA and 350 coulombs. An average bolt of positive lightning carries an electric current of about 300 kA—about 10 times that of negative lightning.

[0004] Therefore, it would be beneficial to have an apparatus to collect and/or store the electrical energy of lightning.

BRIEF SUMMARY

[0005] Embodiments of the invention relate to an apparatus and method for collecting and/or storing the electrical energy. Specific embodiments are directed to an apparatus and method for collecting and/or storing the electrical energy of lightning. A specific embodiment pertains to a lightning energy storage system that includes a lightning rod, a wire, a lightning energy harvesting unit and a ground rod. The lightning rod is configured to attract lightning and transfer electrical energy. The lightning energy harvesting unit incorporates at least one magnetic capacitor and a switch. The magnetic capacitor comprises a first magnetic section, a second magnetic section, and a dielectric section configured between the first magnetic section and the second magnetic section. The dielectric section is configured to store the electrical energy and has a thickness of at least 10 angstrom to reduce, and preferably prevent, electrical energy leakage. The ground rod is connected to the wire. A control signal controls the switch to direct the electrical energy to ground through the ground rod or to direct the electrical energy to charge the magnetic capacitor in response to a charging state of the magnetic capacitor.

[0006] In an embodiment, the thickness of the dielectric section is 100 angstrom.

[0007] In an embodiment, the lightning energy harvesting unit further comprises a transformer connected to the wire to adjust a voltage of the electrical energy to charge the magnetic capacitor.

[0008] In an embodiment, the lightning energy harvesting unit is packaged in a box, wherein the box has an environmentally sealing cover.

[0009] In an embodiment, the lightning energy harvesting unit further comprises a detector to detect the charging state of the magnetic capacitor and issue the control signal is response to the charging state.

[0010] In an embodiment, the lightning energy harvesting unit comprises a plurality of magnetic capacitors that are parallel connection and fabricated in a substrate.

[0011] In an embodiment, the substrate further comprises a first connector and a second connector, the electrical energy charges the magnetic capacitors through the first connector and the magnetic capacitors supply the electrical energy to an external device through the second connector.

[0012] In an embodiment, the substrate further comprises a third connector connected to the ground rod.

[0013] In an embodiment, when the charging state of the magnetic capacitors are fully charged, the switch switches the first connector to connect with the third connector to direct the electrical energy to the ground rod, and when the charging state of the magnetic capacitors are not fully charged, the switch switches the first connector to connect with the magnetic capacitors to direct the electrical energy to charge the magnetic capacitors.

BRIEF DESCRIPTION OF DRAWINGS

[0014] In order to make the foregoing as well as other aspects, features, advantages, and embodiments of the present disclosure more apparent, the accompanying drawings are described as follows:

[0015] FIG. **1** is a schematic block diagram of an apparatus for collecting and storing the electrical energy in lightning in accordance with an embodiment of the disclosure.

[0016] FIG. **2** is a schematic diagram of a magnetic capacitor to store electrical energy in lightning according to an embodiment of the disclosure.

[0017] FIG. **3** is a schematic diagram of a plurality of magnetic capacitors fabricated in a substrate together to store electrical energy in lightning according to an embodiment of the disclosure.

[0018] FIG. **4** is a schematic diagram of a plurality of magnetic capacitor fabricated in a substrate together to store electrical energy in lightning according to another embodiment of the disclosure.

[0019] FIG. **5** is a schematic block diagram of an apparatus for collecting and storing the electrical energy in lightning in accordance with another embodiment of the disclosure.

DETAILED DISCLOSURE

[0020] Reference will now be made in detail to the various embodiments of the disclosure, one or more examples of which are illustrated in the figures. Each example is provided by way of explanation of the disclosure, and is not meant as a limitation of the disclosure. For example, features illustrated or described as part of one embodiment can be used in conjunction with other embodiments to yield yet a further embodiment. It is intended that the present disclosure includes such modifications and variations.

[0021] FIG. **1** is a schematic block diagram of an apparatus for collecting and storing the electrical energy in lightning. The apparatus **100** for collecting and storing the electrical energy in lightning includes one or more lightning rod **101**, a wire **102**, one or more lightning energy harvester (LEH) units **103** and a ground rod **104**. The lightning rod **101** is structured to attract lightning and transfer electrical energy. The lightning rod **101** is a metal rod or metallic object mounted on top of a building **200**. In another embodiment, the lightning rod **101** is mounted on top of a tower **201**.

[0022] The wire **102** is disposed in connecting between the lightning rod **101** and the lightning energy harvester (LEH) unit **103** or ground rod **104**. The structural adaptation of the wire **102** is such as to direct electrical energy from the lightning rod **101** to the lightning energy harvester (LEH) unit **103** for storing or the ground rod **104** for discharging.

[0023] In an embodiment, the lightning energy harvester unit **103** is packaged in a box. The box has environmentally sealed cover for safety and protection from weather elements. The lightning energy harvester (LEH) unit **103** is composed of one or more magnetic capacitor **200**. Magnetic capacitor is constructed based on the GMC (Giant Magnetic Capacitance) theory. It has a capacitance 10^6-10^{17} times larger than that of standard capacitor of equivalent dimensions and dielectric materials. A magnetic capacitor is an energy storage apparatus. FIG. **2** shows a schematic diagram of a magnetic capacitor to store electrical energy in lightning according to an embodiment of the disclosure. An magnetic capacitor **200** has a first magnetic section **210**, a second magnetic section **220**, and a dielectric section **230** configured between the first magnetic section **210** and the second magnetic section **220**. The dielectric section **230** is a thin film, and the dielectric section **230** is composed of dielectric material, such as $BaTiO_3$ or TiO_3. The dielectric section **230** is arranged to store electrical energy, and the first magnetic section **210** and the second magnetic section **220** are needed to generate the insulating-effect to prevent the current from passing through (i.e. electrical energy, leakage). The dielectric section **230** further has a thickness at least 10 angstroms (Å) to prevent the electrical energy leakage. In an embodiment, the thickness of the dielectric section **230** is at least 10 Å, at least 100 Å, and/or 100 Å to prevent the electrical energy leakage.

[0024] In another embodiment, a plurality of magnetic capacitors **200** may be fabricated in a substrate **240** together to form the lightning energy harvester unit **103** as illustrated in FIG. **3**. A connector **250** is formed in the substrate **240** for connecting to wire **102**. These magnetic capacitors **200** are connected in parallel and connected to the connector **250** to receive the electrical energy in lightning and to the connector **253** for supplying electrical energy to an external device.

[0025] In another embodiment, the lightning energy harvester unit **103** further comprises a power management module **260**. The power management module **260** connects to the wire **102** through a connector **251** and connects to the ground rod **104** through the connector **252**. The power management module **260** includes a detector **2601** and a switch **2602**. The detector **2601** detects the magnetic capacitor **200** to determine an electrical energy state stored in the magnetic capacitors **200**. In an embodiment, when the electrical energy stored in the magnetic capacitors **200** is over a set value, the detector **2601** issues a control signal to the switch **2602** to switch the switch **2602** to direct the electrical energy in lightning to ground through the ground rod **104**. For example, the lightning rod **101** receives the electrical energy in lightning to charge these magnetic capacitors **200**. The detector **2601** detects the charging state of theses magnetic capacitor **200** in real time. When the detector **2601** determines these magnetic capacitors **200** are fully charged, the detector **2601** issues a control signal to switch the switch **2602** to direct the electrical energy in lightning to ground through the ground rod **104**. Moreover, in a specific embodiment, the power management module **260** further includes a transformer **2603** to transform the voltage of the electrical energy in lightning to a charging voltage to charge these magnetic capacitors **200**.

[0026] It will be apparent to those ordinarily skilled in the art that various modifications and variations can be made to the structure of the present disclosure without departing from the scope or spirit of the disclosure. In view of the foregoing, it is intended that the present disclosure cover modifications and variations of this disclosure provided they fall within the scope of the following claims.

1. A lightning energy storage system, comprising:
- a lightning rod configured to attract lightning and transfer electrical energy;
- a wire;
- a lightning energy harvesting unit, wherein the lightning energy harvesting unit comprises at least one magnetic capacitor and a switch, wherein each of the at least one magnetic capacitor comprises:
  - a first magnetic section;
  - a second magnetic section; and
  - a dielectric section configured between the first magnetic section and the second magnetic section, wherein the dielectric section is structured to store the electrical energy, wherein the dielectric section has a thickness of at least 10 angstroms; and
- a ground rod,
- wherein a control signal controls the switch to direct the electrical energy to ground through the ground rod or to direct the electrical energy to charge the at least one magnetic capacitor in response to a charging state of the at least one magnetic capacitor.

2. The system of claim **1**, wherein the thickness of the dielectric section is at least 100 angstroms.

3. The system of claim **1**, wherein the lightning energy harvesting unit further comprises a transformer connected to the wire, wherein the transformer adjusts a voltage of the electrical energy to charge the at least one magnetic capacitor.

4. The system of claim **1**, wherein the lightning energy harvesting unit is packaged in a box, wherein the box has an environmentally sealing cover.

5. The system of claim **1**, wherein the lightning energy harvesting unit further comprises a detector to detect the charging state of the at least one magnetic capacitor and issue the control signal in response to the charging state.

6. The system of claim **1**, wherein the at least one magnetic capacitor comprises a plurality of magnetic capacitors, wherein the plurality of magnetic capacitors are connected in parallel.

7. The system of claim **2**, wherein the thickness of the dielectric section is 100 angstroms.

8. The system of claim **7**, wherein the substrate further comprises a first connector and a second connector, wherein the electrical energy charges the plurality of magnetic capacitors through the first connector and the plurality of magnetic capacitors supply the electrical energy to an external device through the second connector.

9. The system of claim **8**, wherein the substrate further comprises a third connector connected to the ground rod.

10. The system of claim **9**, wherein when the charging state of the plurality of magnetic capacitors is fully charged, the switch switches the first connector to connect with the third connector to direct the electrical energy to the ground rod.

11. The system of claim **9**, wherein when the charging state of the plurality of magnetic capacitors is not fully charged, the switch switches the first connector to connect with the plurality of magnetic capacitors to direct the electrical energy to charge the plurality of magnetic capacitors.

12. The system of claim **2**, wherein the thickness of the dielectric section is 100 angstroms.

* * * * *

WIKIPEDIA

Crookes radiometer

Crookes radiometer

The **Crookes radiometer**, also known as a **light mill**, consists of an airtight glass bulb, containing a partial vacuum. Inside are a set of vanes which are mounted on a spindle. The vanes rotate when exposed to light, with faster rotation for more intense light, providing a quantitative measurement of electromagnetic radiation intensity. The reason for the rotation was a cause of much scientific debate in the ten years following the invention of the device,[1][2] but in 1879 the currently accepted explanation for the rotation was published.[3][4] Today the device is mainly used in physics education as a demonstration of a heat engine run by light energy.

It was invented in 1873 by the chemist Sir William Crookes as the by-product of some chemical research. In the course of very accurate quantitative chemical work, he was weighing samples in a partially evacuated chamber to reduce the effect of air currents, and noticed the weighings were disturbed when sunlight shone on the balance. Investigating this effect, he created the device named after him.

It is still manufactured and sold as an educational aid or curiosity.

Contents

General description
- Effect observations
- Origin of the name

Thermodynamic explanation
- Movement with black-body absorption
- Movement with black-body radiation

Explanations for the force on the vanes

All-black light mill

Nanoscale light mill

See also

References

External links

General description

The radiometer is made from a glass bulb from which much of the air has been removed to form a partial vacuum. Inside the bulb, on a low friction spindle, is a rotor with several (usually four) vertical lightweight vanes spaced equally around the axis. The vanes are polished or white on one side and black on the other.

When exposed to sunlight, artificial light, or infrared radiation (even the heat of a hand nearby can be enough), the vanes turn with no apparent motive power, the dark sides retreating from the radiation source and the light sides advancing.

Cooling the radiometer causes rotation in the opposite direction.


A Crookes radiometer in action

Effect observations

The effect begins to be observed at partial vacuum pressures of a few torr (several hundred pascals), reaches a peak at around 10^{-2} torr (1 pascal) and has disappeared by the time the vacuum reaches 10^{-6} torr (10^{-4} pascal) (see explanations note 1). At these very high vacuums the effect of photon radiation pressure on the vanes can be observed in very sensitive apparatus (see Nichols radiometer) but this is insufficient to cause rotation.

Origin of the name

- The prefix "radio-" in the title originates from the combining form of Latin *radius*, a ray: here it refers to electromagnetic radiation.
- A Crookes radiometer, consistent with the suffix "- meter" in its title, can provide a quantitative measurement of electromagnetic radiation intensity.

This can be done, for example, by visual means (e.g., a spinning slotted disk, which functions as a simple stroboscope) without interfering with the measurement itself.

Radiometers are now commonly sold worldwide as a novelty ornament; needing no batteries, but only light to get the vanes to turn. They come in various forms, such as the one pictured, and are often used in science museums to illustrate "radiation pressure" – a scientific principle that they do not in fact demonstrate.

Thermodynamic explanation

Movement with black-body absorption

When a radiant energy source is directed at a Crookes radiometer, the radiometer becomes a heat engine. The operation of a heat engine is based on a difference in temperature that is converted to a mechanical output. In this case, the black side of the vane becomes hotter than the other side, as radiant energy from a light source warms the black side by black-body absorption faster than the silver or white side. The internal air molecules are heated up when they touch the black side of the vane. The details of exactly how this moves the warmer side of the vane forward are given in the section below.


A Crookes radiometer in action with the light switched on and off.(note that the explanation given in the caption to the clip doesn't agree with the explanation below)

The internal temperature rises as the black vanes impart heat to the air molecules, but the molecules are cooled again when they touch the bulb's glass surface, which is at ambient temperature. This heat loss through the glass keeps the internal bulb temperature steady with the result that the two sides of the vanes develop a temperature difference. The white or silver side of the vanes are slightly warmer than the internal air temperature but cooler than the black side, as some heat conducts through the vane from the black side. The two sides of each vane must be thermally insulated to some degree so that the polished or white side does not immediately reach the temperature of the black side. If the vanes are made of metal, then the black or white paint can be the insulation. The glass stays much closer to ambient temperature than the temperature reached by the black side of the vanes. The external air helps conduct heat away from the glass.

The air pressure inside the bulb needs to strike a balance between too low and too high. A strong vacuum inside the bulb does not permit motion, because there are not enough air molecules to cause the air currents that propel the vanes and transfer heat to the outside before both sides of each vane reach thermal equilibrium by heat conduction through the vane material. High inside pressure inhibits motion because the temperature differences are not enough to push the vanes through the higher concentration of air: there is too much air resistance for "eddy currents" to occur, and any slight air movement caused by the temperature difference is damped by the higher pressure before the currents can "wrap around" to the other side.

Movement with black-body radiation

When the radiometer is heated in the absence of a light source, it turns in the forward direction (i.e. black sides trailing). If a person's hands are placed around the glass without touching it, the vanes will turn slowly or not at all, but if the glass is touched to warm it quickly, they will turn more noticeably. Directly heated glass gives off enough infrared radiation to turn the vanes, but glass blocks much of the far-infrared radiation from a source of warmth not in contact with it. However, near-infrared and visible light more easily penetrate the glass.

If the glass is cooled quickly in the absence of a strong light source by putting ice on the glass or placing it in the freezer with the door almost closed, it turns backwards (i.e. the silver sides trail). This demonstrates black-body radiation from the black sides of the vanes rather than black-body absorption. The wheel turns backwards because the net exchange of heat between the black sides and the environment initially cools the black sides faster than the white sides. Upon reaching equilibrium, typically after a minute or two, reverse rotation ceases. This contrasts with sunlight, with which forward rotation can be maintained all day.

Explanations for the force on the vanes

Over the years, there have been many attempts to explain how a Crookes radiometer works:

1. Crookes incorrectly suggested that the force was due to the pressure of light.[5] This theory was originally supported by James Clerk Maxwell, who had predicted this force. This explanation is still often seen in leaflets packaged with the device. The first experiment to test this theory was done by Arthur Schuster in 1876, who observed that there was a force on the glass bulb of the Crookes radiometer that was in the opposite direction to the rotation of the vanes. This showed that the force turning the vanes was generated inside the radiometer. If light pressure were the cause of the rotation, then the better the vacuum in the bulb, the less air resistance to movement, and the faster the vanes should spin. In 1901, with a better vacuum pump, Pyotr Lebedev showed that in fact, the radiometer only works when there is low-pressure gas in the bulb, and the vanes stay motionless in a hard vacuum.[6] Finally, if light pressure were the motive force, the radiometer would spin in the opposite direction, as the photons on the shiny side being reflected would deposit more momentum than on the black side where the photons are absorbed. This results from conservation of momentum - the momentum of the reflected photon exiting on the light side must be matched by a reaction on the vane that reflected it. The actual pressure exerted by light is far too small to move these vanes but can be measured with devices such as the Nichols radiometer.
2. Another incorrect theory was that the heat on the dark side was causing the material to outgas, which pushed the radiometer around. This was effectively disproved by both Schuster's[7] and Lebedev's experiments.[6]
3. A partial explanation is that gas molecules hitting the warmer side of the vane will pick up some of the heat, bouncing off the vane with increased speed. Giving the molecule this extra boost effectively means that a minute pressure is exerted on the vane. The imbalance of this effect between the warmer black side and the cooler silver side means the net pressure on the vane is equivalent to a push on the black side and as a result the vanes spin round with the black

side trailing. The problem with this idea is that while the faster moving molecules produce more force, they also do a better job of stopping other molecules from reaching the vane, so the net force on the vane should be the same. The greater temperature causes a decrease in local density which results in the same force on both sides. Years after this explanation was dismissed, Albert Einstein showed that the two pressures do not cancel out exactly at the edges of the vanes because of the temperature difference there. The force predicted by Einstein would be enough to move the vanes, but not fast enough.

4. The final piece of the puzzle, thermal transpiration, was theorized by Osborne Reynolds[8] in an unpublished paper that was refereed by Maxwell, who then published his paper which contained a critique of the mathematics in Reynolds's unpublished paper.[9] Maxwell died that year and the Royal Society refused to publish Reynolds's critique of Maxwell's rebuttal to Reynolds's unpublished paper, as it was felt that this would be an inappropriate argument when one of the people involved had already died.[3] Reynolds found that if a porous plate is kept hotter on one side than the other, the interactions between gas molecules and the plates are such that gas will flow through from the cooler to the hotter side. The vanes of a typical Crookes radiometer are not porous, but the space past their edges behaves like the pores in Reynolds's plate. On average, the gas molecules move from the cold side toward the hot side whenever the pressure ratio is less than the square root of the (absolute) temperature ratio. The pressure difference causes the vane to move, cold (white) side forward due to the tangential force of the movement of the rarefied gas moving from the colder edge to the hotter edge.[3]

All-black light mill

To rotate, a light mill does not have to be coated with different colors across each vane. In 2009, researchers at the University of Texas, Austin created a monocolored light mill which has four curved vanes; each vane forms a convex and a concave surface. The light mill is uniformly coated by gold nanocrystals, which are a strong light absorber. Upon exposure, due to geometric effect, the convex side of the vane receives more photon energy than the concave side does, and subsequently the gas molecules receive more heat from the convex side than from the concave side. At rough vacuum, this asymmetric heating effect generates a net gas movement across each vane, from the concave side to the convex side, as shown by the researchers' Direct Simulation Monte Carlo (DSMC) modeling. The gas movement causes the light mill to rotate with the concave side moving forward, due to Newton's Third Law. This monocolored design promotes the fabrication of micrometer- or nanometer- scaled light mills, as it is difficult to pattern materials of distinct optical properties within a very narrow, three-dimensional space.[10][11]

Nanoscale light mill

In 2010 researchers at the University of California, Berkeley succeeded in building a nanoscale light mill that works on an entirely different principle to the Crookes radiometer. A gold light mill, only 100 nanometers in diameter, was built and illuminated by laser light that had been tuned. The possibility of doing this had been suggested by the Princeton physicist Richard Beth in 1936. The torque was greatly enhanced by the resonant coupling of the incident light to plasmonic waves in the gold structure.[12]

See also

- Photophoresis
- Thermophoresis
- Marangoni effect
- Nichols radiometer
- Solar energy
- Solar wind
- Crookes tube

References

Home | Contact | Site Map | Radio Stations & Memorabilia | Amateur Radio

Crystal Sets Introduction | Resistor & Capacitor Conversion Tables

Crystal Sets (Part1) | Build Your Own Crystal Set (Part 2)

Spider's Web Crystal Set (Part 3) | Crystal Set By Kenneth Rankin (Part 4) | Crystal Radio Links

CRYSTAL SETS 5: EXPERIMENTAL CRYSTAL SETS

.



Picture 1 - The Complete Experimental Crystal Set

THE POPULARITY of the crystal radio arises from its simplicity, and the fact that it needs no power supply. The circuit here allows for easy experiments with tuning, aerial and diode coupling, and frequency coverage. Wrong connections can cause no damage to any components.

A Crystal Set is more often than not used for the reception of medium and long wave radio, but short wave reception is also quite feasible. It will normally be possible to receive some of the stronger international radio stations.

This is adapted from an article that appeared in the 1970's in Everyday Electronics, and gave me almost endless hours of fun!

BASIC CIRCUIT

The basic circuit is shown in Picture 2 below. The coil L1 can be air cored, or have a ferrite rod placed in its winding. The variable capacitor C1, in conjunction with aerial-earth capacitance, tunes the circuit to resonate with the wanted radio station frequency. The diode D1 "detects" or demodulates the radio signal so that the programme is heard in the earpiece.

This basic circuit can be modified in various ways to obtain better performance.

EARPHONE

As most constructors will be using a Crystal Earpice to listen to the crystal set it is essential that a 47k Ohm resistor is connected across the earphone terminals (TB1/1 and TB1/2 in the diagram), i.e. in parallel with the earphone, otherwise results will be very quiet.

A High Impedance headset of 20k Ohms (20,000 Ohms) may give even better results, but these are very difficult to obtain , so unless you happen to already own such a headset the Crystal Earphone with 47k resistor will be the only option. An ordinary magnetic earpiece or Walkman headphones will not work with a crystal set.

ASSEMBLY

Construction is of a 'breadboard' type using a wooden board of about 165 x 130 mm. A 12-way block connector, TB1, is used to connected together the components and this is screwed onto the wooden board. The use of a block connector provides an easy method of connecting the components together and then subsequently rearranging them as the experiments progress.

Tuning capacitor C1 is screwed to a bracket made of some scrap metal which is then also screwed firmly down to the baseboard, see Picture 1 above. Thin plywood screwed to the front edge of the baseboard would also provide a suitable method of fixing the tuning capacitor to the base. A knob with pointer is fitted to C1, and a scale is drawn and fitted behind this.

Except for C1, all connections are made by the terminals of the 12-way terminal block as shown in Picture 4. Loosen the screws with a small screwdriver, insert the bared ends of the wires, and tighten the screws. The various locations on the terminal block, TB1, are also shown in the circuit diagram, Picture 2.

AERIAL AND EARTH

Crystal receivers need a long wire aerial preferably strung outside and about 25m long, or as long as is possible to install. If this is outside it should be high and clear of earthed objects as this will improve performance.

An earth is absolutely essential for a crystal set to work properly. The earth lead can be run to an earth rod or spike that is buried to a depth of about 1 meter into damp soil. Or it may be soldered to a bare metal can which is buried in damp soil.

It is feasible, though not recommended, that the earth lead can be connected to the earthing terminal of a hi-fi system or even to the bare metal case of a personal computer that is plugged into an earthed mains outlet, but is switched OFF.

Stranded, insulated wire, or purpose made aerial wire can be used for the aerial and earth leads.



Picture 2 - The Basic Circuit



Picture 3 - Photo Of The General Layout

INDUCTORS (The Tuning Coils)

The following four coils are suggested for initial use as L1 :

Coil 1: Make a thin card tube to slide on a 10mm diameter ferrite rod, and on this tube wind about 105 turns of 32 s.w.g. enamelled copper wire, side by side. Secure ends with sticky tape.

Coil 2: Make a similar coil to to coil 1 having about 15 turns of 24 s.w.g. enamelled wire on the card tube. Loops of cotton will help hold the ends in place.

Coil 3: Wind 9 turns of 20 s.w.g. bare tinned copper wire on an object about 20mm in diameter. Remove and stretch to separate the turns, to obtain a coil about 25mm long.

Coil 4: Make a similar coil to coil 3, but with 5 turns.

The Ferrite Rod

It will be necessary to have a ferrite rod of about 60mm to 75mm long available. Coils 1 and 2 will provide reception of medium wave and the longer short wave bands. Coil 3 should cover about 3 - 10MHz shortwave with the ferrite placed in it, or about 6 - 18MHz with the ferrite rod removed. Coil 4 should cover about 6 -13MHz with the rod in, and about 9 - 20MHz without the' rod.

It will be noted that as the ferrite rod is inserted, any particular signal has to be re-tuned by opening Cl. This arises because the ferrite increases the inductance of the winding, so less parallel capacitance is needed for the same resonant frequency.

EFFICIENCY CHECKS

Tune in a m.w. transmission using coil 1 which gives good headphone volume. Place a microammeter or multi-range meter on a sensitive range in series with the headphones. A reading of 50-100uA or more may be obtained, depending on aerial, earth, earphone resistance and resistor value, coil and detector efficiency and strength of signals at your locality.

Placing the ferrite rod in the coil and re-tuning should boost the meter reading to some extent. Surplus or other detector diodes can be tried by substituting them in turn and noting the meter reading. Improvements to the aerial (or earth) will also show up as a rise in meter reading.

If experimenting with a crystal earpiece, which gives no direct current circuit, the meter may be clipped across the phone leads, i.e. D1 cathode to earth.



Picture 4 - Baseboard Layout Of The Crystal Set

AERIAL COUPLING

The aerial loads the tuned circuit heavily when connected directly to the top of the tuned circuit, as in Picture 2. This damps the tuning action and it can be found that stations spread out all over the dial, which is unsatisfactory.

The series capacitor, C2 connected in Picture 5(a) reduces the loading and thus improves the sharpness of the tuning. A variable or pre-set capacitor of about 250pF maximum is most suitable. for this role, though it is possible to experiment with a variety of fixed value capacitors in this range also.

Connecting the aerial to a tapping on the coil, as in Picture 5 (b) also sharpens tuning. It may also increase volume. Try about 2 turns from earth for coil 4, or 4 turns from earth for coil 3.

Another method is to have a coupling primary, as in Picture 5 (c). This consists of a second coil, with about one third the turns of the original wound on top of the existing coil.

You can even combine these methods to find what arrangement best suits the aerial in use.

The diode can be disconnected from the end of L1 and taken to a spare position on TB1 for example location TB1/9. You can then run a flying-lead fitted with a crocodile clip from this position, connecting it to various tappings on the coil as required as in Picture 5 (d). This method also reduces loading on the tuned circuit.

Coils with spaced turns of bare wire are readily tapped. For other coils, small loops can be made every ten turns or so, and crocodile clips can be attached to these when selecting tapping points.



Picture 5 - Alternative Methods Of Aerial Coupling

SHORT WAVES

For shortwave reception, a good efficient outdoor aerial is certainly recommended. Evening listening in the region around 5 - 9MHz in often proves to be the most fruitful.

Since there is no amplification, as with a valve or transistor receiver, certain frequencies will seem to be completely dead at particular times of day. So if the crystal receiver works satisfactorily on medium wave and longwave, but no shortwave signals are heard, check again in the evening, or after dark, when conditions are different.

PARTS REQUIRED

C1	**365pF or 500pF Air Spaced Tuning Capacitor**
D1*	**OA47, IN34, OA81, OA90, OA91, IN94 or similar point contact small signal Germanium Diode** * The OA47 will be of particular interest since it has the lowest forward bias voltage of any of these diodes which will make the crystal set somewhat more sensitive and therefore louder. The US equivalent of the British OA47 is the IN34.
TL1	**High Impedance Headphones (20,000 Ohms)** **or Crystal Earphone**
TB1	**12-Way Plastic Screw Block Terminal**
Also Required:	**47 k Ohm Resistor for Crystal Earphone: Enamelled Copper Wire: 32 and 24 s.w.g. for L1: 20 s.w.g. tinned wire for L1: Ferrite Rod 10mm diameter x 75 mm long: 25m of wire for aerial: Wire and rod or spike etc for earth: Wood for base e.g. 10mm x165mm x 130mm: Scrap of metal of thin plywood for C1 bracket/front panel: Knob: Crocodile clip(s)**

Adapted from an article in Everyday Electronics magazine, November 1981, By F.G. Rayer.

HERE ARE A COUPLE OF VERY INTERESTING CRYSTAL SET DESIGNS SENT IN BY KRYSATEC - "THE RAT" - FROM THE CZECH REPUBLIC


Crystal radio
Made by Rat
100p
LW / MW
2mH
500p
earphone
4kOhm
5n
180uH
500p
2x 1NN41

1/ Using old coils from old bulb radio for MW and LW band. Though it would be straightforward to wind the coils - one for Long Wave, one for Medium Wave and a coupling coil. Variable capacitor is 2 x 500pF only one half is used: 500pF. For the crystal earphone a resistor of about 82k ohm in parallel is required. This set also uses two Ge diodes as a multiplier in the quest for for higher audio signal output.


Crystal radio with simple amplifier
Made by Rat
100p
LW / MW
2mH
+3V
M22
M5
500p
25k
earphone
150R - 4KOhm
100n
5n
gnd
180uH
500p
2x 1NN41
102NU70
Ge diode
Ge transistor

2. If signals are not strong signal in your location, then the above circuit design can be considered. A simple transistor amplifier is used. A variable resistor M22 is used for better sensitivity which can be adjusted for poor signals. This crystal radio is aversion from cca 1960 - 1970 y.



Rat's finished Crystal Set with additional amplification - very neat!

'Minilabs' Crystal Radio

BELOW: Ian Tomlinson kindly sent in a photograph of the box that contained the kit for his John Adams Toys 'Minilabs' Crystal Radio.

It is a very simple circuit consisting of the coil (inductor) with a sliding contact that provides variable tapping points, a diode and crystal earphone. All that is added is the aerial and earth. There is no variable tuning capacitor for simplicity and to keep costs down.

The coil provides the inductance required for tuning into a certain frequency (wavelength). These days a variable "tuning" capacitor is normally wired in parallel across the inductance (coil) in order to vary the resonance of the tuned circuit and therefore enable to easily tune into various transmitters on different frequencies. This crystal is tuned varying the number of turns on the coil (ie varying the inductance) by tapping off at different points using the sliding contact ("ball").

The crystal earpiece, or high Z headphone, is connected between the output of the detector diode (the other end from the coil) and earth. The volume from a crystal earpiece may be considerably improved by connecting a resistor of - somewhere between - 4.7 k and 47k ohms in parallel with the earpiece. A crystal earpiece cannot directly allow current to flow through it and the parallel resistor therefore allows current to better flow through the circuit.

John Adams Toys
Crystal
Radio Kit
Make a radio complete with tuning coil, antenna and earphone.
Pack contains all you need including full instructions.
No battery required.
Ages 8–14

'Minilabs' crystal set by John Adams Toys

A discussion on configurations for Crystal Sets by Felix Scerri VK4FUQ

This discussion, by Felix Scerri VK4FUQ, was posted at this address which no longer appears on the web www.tarc.org.au/techinfo2.htm (error 404) so here it is reproduced:

Crystal Set design is one of my passions closely allied with my obsession for audio and high fidelity.

My main interest in crystal sets, apart from the wonder of a radio receiver that does not require a power source, is the potential excellence of the recovered audio quality from normal AM broadcast stations.

Personally, it is one of my great laments that most people have never heard how good wideband AM can sound. A high performance crystal set or similar TRF approach is, in my opinion,the only way to do it. There are a few people around who have heard the audible results of my efforts,and can only agree.

I have often wondered,given the ultimate simplicity of the crystal set, being essentially a tuned circuit,a diode detector and some form of output device, what it takes to achieve optimum performance. What follows are my thoughts on the matter.

Crystal Set optimisation, is in my opinion, all about reduction of circuit losses. Essentially this means high "Q" tuned circuits and high quality detectors. Efficient output devices also help too. But as we will see, there are some trade-offs required as well. A high "Q" tuned circuit is always benefical, as a high "Q" tuned circuit has lowest RF losses,highest potential selectivity,and highest voltage at resonance, which is very useful for the diode being fed from the tuned circuit. Variable capacitors, even the "modern" miniature variable capacitors (although the older air dielectric units, as used in old valve receivers are more desirable) for various reasons,are generally quite efficient, and a higher "Q" coil will produce the most worthwhile improvements.The best (highest "Q") coils are wound with "Litz" wire, which is a multistranded woven wire with all strands insulated from each other. The performance of Litz wire wound coils is spectacular, unfortunately, although I know Litz wire is still being made, from personal

experience, it is VERY rare in Australia.

Efficient coil design can be quite complex and all my coils are wound on ferrite rods. There seems to be,at least for ordinary single wire windings (close wound), an optimum wire thickness for optimum coil "Q". I have determined .315 mm winding wire to be about optimum for simple (single wire) coils on ferrite rods. Thicker wire is NOT better, believe it or not.

Lacking Litz wire, an interesting winding approach I have developed is to use two slightly thinner wires wound as a bifilar winding connected together at the beginning and end of the coil, yields considerably higher "Q" compared to a simple single wire winding. I have found 0.25 mm winding wire optimum in this application.

Whilst high "Q" coils are beneficial from the RF point of view, there is a possible downside. If one is interested in maximum selectivity and sensitivity, there is no problem, but remember highest "Q" results in a narrowed audio band-width as a simple consequence of band-width. For high fidelity applications this could be a disadvantage under some circumstances, although there are clever ways around this.

Regardless of ultimate coil "Q", selectivity is a major issue with crystal sets generally. Here another trade-off is evident. For the maximum voltage into the diode, connecting the diode to the high impedance end of the coil (i.e. the top) yields the greatest voltage but the selectivity is usually terrible, because of severe "loading" by the diode circuit. For this reason, tapping well own the coil improves selectivity at the expense of signal volume (reduced voltage). Once again there are ways around this. As described in my "Double Tuned Crystal Set Tuner" article in "Amateur Radio" magazine, March 2002, the use of two separately tuned coupled resonant circuits allows top connection into the diode without compromising overall selectivity, thanks to the use of a second tuned circuit which is fed from the external antenna. The whole network forms a double tuned input bandpass filter and in practice this approach works very well. For single coil crystal sets I recommend the use of an un-tuned "antenna" winding adjacent to the "hot" end of the main coil, preferably adjustable (old paper reels from sewing cotton threads are ideal). This allows the degree of coupling to be optimised under actual listening conditions. The double tuned set up is best, yielding superb selectivity, but the un-tuned antenna coil arrangement also works quite well, especially if the diode is tapped well down the main coil.Tapping halfway works well.

The other method of performance improvement involves the use of the most effective detector system possible. Here things get very interesting. In fact the temptation is to use more complex circuitry, but that gets away from the charming simplicity of the crystal set. As an example, my own crystal set tuner has at times mutated into a TRF tuner complete with FET RF preamplifiers, active(powered) detectors and other enhancements. These modifications do work well, but loses the simplicity of a basic crystal set. In actuality, a simple diode detector can work extremely well, subject to some qualification. Diodes like to work with a reasonable level of RF input voltage. Audio distortion can result under conditions of low signal level, due to diode transfer curve non linearity and other factors, such as the widespread use of broadcast station "processing". The actual type of diode makes a difference. The 1N34A germanium diode is very popular for crystal set use, although in my experience just about ANY germanium diode will work, although it is worth trying different specimens. Some are definitely better than others. Even from a pack of twenty 1N34A's from the same source, some were definitely better than others. Measuring the average value of rectified output voltage across the diode load resistor will show which diodes are best. By the way, I regard a diode load resistor as being mandatory. I find a value of about 47K about right, especially if a crystal earpiece is being used or the crystal set is being used as a tuner feeding an audio pre-amplifier and following amplifier. If using high impedance magnetic type headphones, the headphones provide the diode DC load.

Another type of diode that is very interesting, is the hot carrier diode. There seem to be a lot of different hot carrier diodes around these days. There are even hot carrier diodes now being sold as "germanium diode equivalents". I have tried them and they do work acceptably well, but they are not quite as good as genuine germanium diodes such as the 1N34A. Typical UHF mixer hot carrier diodes, such as the 1N5711 will not work well in crystal set service simply because their "turn on voltage"is too high, similar to silicon diodes such as the 1N4148/914 series, which require a lot of RF input to function adequately as RF detectors, however a simple technique can be used to turn hot carrier diodes such as the 1N5711 into superlative detectors.

I guess we are cheating a little, because the technique is to use a little voltage bias supplied via a 1.5v battery, through a simple potentiometer voltage divider arrangement, with capacitor (for DC isolation) fed into the diode from the tuned circuit. With applied adjustable bias, I find the 1N5711 diodes absolutely superlative detectors under ANY signal strength conditions. I find the detection quality also superlative, with a clarity and low noise profile unmatched by any other diode arrangement. In my opinion, hot carrier diodes, running bias,are the best detectors overall.

Regarding other detector arrangements, the diode "voltage doubler" is often recommended, however my own

experiments with the doubler arrangement have been inconclusive and slightly disappointing overall. I have found no real advantage in their use over a simple (one) diode detector, believe it or not.

Yes, they do work, but they're nothing special, at least in my opinion.

Any comments on this general subject of crystal set optimisation would be welcome.

73's Felix Scerri VK4FUQ.
22nd July 2002



Above: CRYSTAL SET BASED CIRCUIT PROVIDING A HIGH QUALITY PROGRAMME SOURCE

IMPROVED VERSION OF THE ABOVE CONCEPT !! New update from Felix Scerri February 2010:

New 'two FET infinite impedance AM detector'

I've developed a new version of my old favourite FET 'infinite impedance' AM detector that I think sounds very nice. I include a short audio of one of our local AM stations. I picked this station as it is my reference 'torture test AM station' as they run very heavy 'processing' which normally sounds yuck with all my other (diode and non diode) detectors! However it's quite clean with this detector. What do you reckon? I'll do up a circuit if you'd like to feature it in your TRF radio section. A general draft article follows.

'A favourite non diode based AM detector that I've built and used many times over the years is the FET based infinite impedance detector, offering very good general AM detector performance, especially under weak RF signal conditions where diode based detectors do not perform well, especially in terms of audio distortion.

However one of the slightly strange things I've noticed about the simple FET based infinite impedance detector is the variable audio quality noted, even when using the same type of FET. Some I've built have sounded good and others slightly fuzzy when used with an audio preamp and fed into a high quality audio system. I've been giving this a considerable bit of thought of late and I've wondered if the audio distortion might be a result not necessarily of the detection process itself, but the FET stage in its guise as a 'source follower' audio stage which essentially, it is.

I have long been aware that as a simple audio buffer stage, the FET based 'source follower' can exhibit a considerable amount of audio distortion, and a technique I've long used to greatly reduce this audio distortion is to use a second FET in the source lead of the first FET as a 'constant current source' which serves to 'linearise' and

greatly reduce audio distortion in the buffer stage overall. So, to test the theory I built a simple one FET infinite impedance AM detector which worked well, but with just a hint of audio 'fuzziness' on received AM stations. So I added a second FET in the source lead of the first FET wired as a constant current source, taking the output from the source of the first RF detector FET and the source resistor and RF bypass capacitor off the source lead of the second FET 'constant current source'. The result, totally clean audio! The theory seems proved! I call this modified detector the 'Two FET infinite impedance detector'

))) Here's what is sounds like - click to play the audio file (((

Here is the circuit diagram:



This detector has been a real eye opener for me in terms of its excellent performance, especially considering its circuit simplicity. Indeed in the past I have designed other more complex FET based infinite impedance circuits that do not quite work as well in practical terms as this latest circuit, at least according to my well calibrated ears!

I do not have access to any precise test equipment but my well calibrated ears tell me this 'two FET infinite impedance detector' is a beauty, surpassing practically every other AM detector I've built even at low RF input, and that's rather a impressive claim and the audio quality when used as an AM tuner feeding a high quality audio system is quite remarkable. Possibly the best thing about this detector is its excellent performance under weak signal conditions. Diode based detectors also work beautifully, but the use of an RF stage to ensure detection over a linear portion of the diode's curve is mandatory! This compound infinite impedance detector works



beautifully on the sniff of a useable RF signal.

Just add a high Q tuned circuit and that's it!

Felix Scerri
VK4FUQ

A better FET for the 'basic' Infinite Impedance Detector:

Quite recently by accident, I've realised the MPF102 FET that I've long used in my FET based infinite impedance detectors is possibly not the best FET to use. This was the reason why I developed the 'two FET' infinite impedance detector some time ago which works very well.

However I've found the choice of a more suitable FET works beautifully in the basic FET based infinite impedance detector circuit, which has appeared for many years in many editions of the ARRL Handbook.

I use the 2N5457 and others of the same 'family' may be equally suitable, but I haven't tried them! However with a 2N5457 in place of an MPF102, the basic infinite impedance detector has became my AM detector of choice. It works beautifully even at low signal input with lovely and clean low distortion audio along with a very high input impedance for good tuning selectivity. It's a beauty! The basic generic circuit is attached, courtesy of Rod Elliott's ESP website.

73 Felix VK4FUQ
10 / 02 / 2012.



The basic generic circuit is attached, courtesy of Rod Elliott's ESP website
Felix Scerri VK4FUQ

As often happens with me, my renewed interest in FET based 'infinite impedance detectors' of late has led to some interesting new research and I may have considerably improved the 'two FET infinite impedance detector' as a result.

My research suggests that although the use of a CCS (constant current source) reduces audio distortion in an audio stage, the value of the 'source resistor' in the CCS stage is somewhat critical for best results.

By using a potentiometer in lieu of a fixed resistor I have found that a resistance value of around 470 kohms cleaned up all overall audio distortion. I used an MPF102 as the CCS in this circuit. An interesting and worthwhile little circuit refinement.

73 Felix VK4FUQ
21 / 02 / 2012.

A Minimum Component Count High Quality AM Detector

I was generally messing around with various circuit ideas and I came up with this AM detector circuit, a simple diode detector along with a FET stage. It was an attempt to provide good performance along with minimum number of components. Actually I've been pleasantly surprised at the excellent level of general performance and the best of all, it sounds great!

The circuit is quite conventional being a BAT 46 diode detector feeding an MPF102 FET buffer/ common source amplifier stage. I would ordinarily use a FET source buffer stage in this application, but opted to use a simple low gain FET 'common source' amplifier stage instead, with excellent results. I also used a BAT 46 Schottky diode instead of an ordinary germanium signal diode.

This was done for several reasons. Firstly, germanium diodes are now very hard to find but in any case these 'germanium diode equivalent' Schottky diodes are actually a superior diode, having very low noise, almost zero back leakage and an essentially complete absence of carrier storage effects and very good weak signal sensitivity. I call these diodes high fidelity diodes as they sound wonderful as RF detectors.



Circuit Diagram of the Minimum Component Count AM Detector by Felix Scerri



Minimum Component Count AM Detector by Felix Scerri



A Closer View

The high impedance of the FET's gate circuit is perfect for optimal buffering of the diode detector, something very important for good low distortion diode detector performance. Apart from providing slight voltage gain, the use of the common source FET amplifier is a new idea, as this prevents the possibility of incidental RF rectification occurring in a FET source follower stage, which can happen. A 1 uf plastic film capacitor may be added in series with the audio 'hot' output lead to block the DC offset out of the FET drain, if required.

Despite no additional RF stage ahead of the diode, audio quality on even relatively weak RF strength stations is actually very good, and of course the audio quality will be even better with increasing RF signal strength, something which will also increase the audio output level. Just on this, for a long time I was somewhat negative regarding diode detectors, as one AM station locally (the strongest one) was always distorted when using a diode detector.

I strongly suspected a transmitter fault, but my complaints were ignored, until one day some time ago when all audio distortion suddenly disappeared! Nothing was ever 'said', but I realised that my suspicions of a long standing transmitter fault were correct, after all!

73 Felix
VK4FUQ
02 March 2012

Voltage Doubler Detector

This is an AM detector circuit that I've long known about and which worked ok, but never seemed to work as well as it should have. However I spent some time late last night trying to optimise the circuit, with some success.

It is a curious circuit being essentially a 'voltage doubler' originally developed for power supply applications, and its use as an AM detector is hard to analyse! It seems that the component values in the circuit are somewhat critical for good performance and if not, the performance is rather 'ordinary'. The circuit that I eventually came up with uses a 150 picofarad 'input capacitor' with a 150 kohm 'load' resistor and loaded into a FET common source voltage amplifier stage (as previously described) through a coupling capacitor with a 1 Mohm input resistance.



With these circuit values, it all works 'quite well'. Give it a go! It's an interesting AM detector with quite good 'sensitivity' and clean audio quality, and it seems to work well at low signal levels.

73 Felix
vk4fuq.

16th April 2012.

Simple AM detectors: What works best? A practical experimenters viewpoint.

I have written a lot about simple AM detectors for use as tuners for feeding into an audio amplifier, and it has been a long time interest. These days I use either diode based or 'infinite impedance' types of AM detectors. In this location our 'local' AM stations are quite distant and are therefore quite weak in terms of signal strength.

As such I find infinite impedance detectors based on field effect transistors give consistently better results for tuner applications due to their lower apparent overall detector distortion. Diode based detectors are quite 'fussy' as they require both optimal output buffering (AC/DC ratio) and an 'adequate' (beyond the diode knee) level of RF signal injection. http://www.tonnesoftware.com/appnotes/demodulator/diodedemod.html

Diode based detectors will happily 'detect' at very low signal levels, however the (inevitable) audio distortion that results, can be extremely irritating to the ear! Under these conditions I find infinite impedance detectors (even without additional RF preamplification and subject to individual FET characteristics), generally sound 'cleaner' and more pleasant to the ear.

FET's of course require a power source for operation whereas diodes are passive (un-powered) detectors (most of the time), however this is of no real advantage in a tuner application as an 'active' audio amplifier stage will generally be required anyway for audio level boosting, buffering etc.

In the end it will come down to a consideration of prevailing RF signal levels and other related circuit considerations at one's location. If local RF levels are strong, a well designed diode detector will give excellent results. If not, an 'infinite impedance' type of detector is most likely the better option unless one goes towards the option of additional RF preamplification prior to the diode detector.

73 Felix
vk4fuq.

17th April 2012.

ANOTHER DETECTOR by Felix Scerri !

I've tried diode based 'voltage doubler' (or more correctly 'diode integrator') AM detectors before with indifferent results, however the other day, just trying a few ideas I came up with this version that works rather well, with low audio distortion, high audio output and really 'nice' audio quality and the best of all, it seems to work very at very low RF input level.

The two diode 'voltage doubler' detector using two BAT 46 silicon schottky diodes feed directly into a MPF102 source follower stage set at 1 Megohm input resistance. The 'input' capacitor feeding the diodes from a tuned circuit is 68 picofarads.

I have the simple RF filter right on the output of the FET stage. In that respect this circuit is vaguely similar to the old 'Selstead-Smith' valve AM detector of the past. An interesting one! I am very happy with its general performance. Regards, Felix vk4fuq 11/04/2013



Felix Scerri VK4FUQ

UPDATE - JUNE 2013

G’day all, readers may recall the two FET infinite impedance detector I developed some time ago. That circuit worked well, but some samples of the MPF102 regretfully produced distorted output. However a recent discovery has resulted in an improved version that has truly exemplary performance.

The MPF102 is in all honesty a device essentially designed for VHF applications, but is often used in simple audio applications albeit with occasionally indifferent results, due to general device parameter ‘spread’. More or less by empirical trial and error I have found that a simple change in source resistor value to 100 k (from a much lower value), pretty well fixes everything.

In a FET source follower circuit this is interesting as the output impedance is actually a lot lower than 100 k due to the action of the FET’s transconductance. It is similar to the action of a bipolar transistor emitter follower circuit. In fact a simple infinite impedance detector with a 100 k source resistor actually works very well and will be good enough for many applications, however the addition of a second FET as a constant current source does markedly reduce overall audio distortion in the stage overall, and produces very clean and low distortion audio quality and also reduces the output impedance considerably (good for tuner applications), so take your pick!

Regards, Felix vk4fuq 02/06/2013.

UPDATE - JANUARY 2014
A simple modification to the basic FET 'infinite impedance' AM detector that dramatically improves performance.



VERY LOW DISTORTION A.M. DETECTOR.
(INFINITE impedance!)

17/01/14
FELIX SCERRI.
VK4FUQ.

G’day all, over the Christmas break just messing around I worked out (mostly by accident), a simple modification for the simple FET based ‘infinite impedance’ detector circuit that dramatically improves weak signal performance and also greatly reduces audio distortion.

Essentially by the addition of another FET ‘buffer’ stage, another source follower, capacitively coupled from the first detector stage. The circuit is actually a simplified version of the circuit that I described in this link, http://sound.westhost.com/articles/am-radio.htm (figure 6) and testing the two head to head, they both sound superb and the simpler version is actually somewhat easier to build. I cannot get over how low distortion and ‘nice’ the recovered audio sounds. It is a joy to listen to!

Regards, Felix vk4fuq 12/01/2014.

Diodes for ‘weak signal’ crystal set applications.

As I am primarily interested in using crystal sets as AM tuners for feeding into a preamplifier/amplifier and loudspeakers, the actual type of diode can be relatively critical. In a strong signal area, not so much, but in a weak signal area such as where I reside, definitely. A diode with a good ‘square law’ performance (the area below the ‘knee’ in the diode curve), generally results in much cleaner and lower distortion than other good performing diodes, and believe me diode distortion under weak conditions, even with optimised diode ‘buffering’ used is very nasty sounding to the ear!

Testing many, many diodes in actual working crystal sets and listening critically to the audio output, it seems to me that the best diodes to use under weak signal conditions are the so called ‘gold bonded’ germanium diodes. I have sampled many different gold bonded germanium diodes and they all work well in this specific application, although sometimes the rectified output voltage may not be as high as other germanium or silicon schottky diodes, however the audio quality is much cleaner and shows much less apparent distortion!

I have tried OA5, OA47, IN141 and several ‘CG’ gold bonded germanium diodes with consistently excellent results. Other ‘ordinary’ germanium diodes may also work well under weak signal conditions, but they will need to be tested individually to check actual performance in a working circuit. One thing that I have noticed about germanium diodes is that due the ‘point contact’ nature of their construction, even diodes of the same specific type can exhibit rather different levels of performance!

The otherwise very good BAT46 silicon schottky diode works extremely well at good RF input level but not so well at weak RF input, especially when heavy broadcast ‘processing’ (commonplace these days), is used. New ‘gold bonded’ germanium diodes are probably no longer made although I am aware that they can be purchased through vendors over the internet. Apart from that, they may be found in old gear. As stated earlier, ordinary germanium diodes may be quite good but will need to be checked individually. Diodes are complex things!

Felix (vk4fuq). 29/01/2014.

* * * * * * * * * * * * * *

Just when I thought that I’ve tried everything I realised that I’ve not tried a voltage doubler (diode integrator) detector with an RF stage in front. It is an unfortunate fact that all diode detectors ‘need’ a good RF injection level (and buffering) or audio distortion becomes ‘bad’ (an understatement!)

Consider yourself very lucky if you live in a strong signal area! (unfortunately I don’t). Anyway I quickly built a couple of prototypes which worked ok but not as well as hoped. Initially I tried using a source follower buffer (no voltage gain), but converting it to a common source amplifier (with appreciable voltage gain), seemed no better, which was strange.

After staring at my prototype for what seemed like forever with my magnifiers on, I (finally) realised my mistake. A common source stage takes its output off the ‘drain’ terminal of the FET, not the ‘source’ terminal as it does with the FET source follower buffer stage. I shifted one wire, and all worked as expected and it sounds fantastic! All diode detectors (one diode envelope detectors, doubler detectors etc), need good RF input and a simple untuned FET RF gain stage works very well. As to the sound, it sounds great.

73 vk4fuq 10/03/2014.


100 uf. electrolytic capacitor
+
MPF102
1.8KΩ
68 pf
1uf
D
G
S
MPF102.
D
G
S
Audio o
output.
o
use ~~captor~~ dc blocking capacitor if capacitor needed on output
To Tuned Circuit
1MΩ
560Ω
100 pf.
100KΩ
1MΩ
1KΩ
Diodes BAT46 x 2.
VK4FUQ.
12/03/14

Felix Scerri's FET Crystal Set with Voltage Doubler

A 'nice sounding' AM detector - update October 2015

Looking through these pages the other day I was slightly shocked to realize that I've completely forgotten about some of the circuits that I've contributed in earlier days! They all work pretty well, however in my advancing older age and a little like my tastes in high fidelity generally, I'm starting to show a particular preference for 'nice sounding' bits of audio gear.

I guess that this also means low noise/low distortion too, although with AM broadcasting, at least in this country and probably elsewhere in the world too, the very common use of broadcasting 'processing' tends to make it hard for AM detectors generally, often resulting in a 'hard/compressed' sort of sound although still low in distortion, is not 'nice sounding', if that makes any sense!

Well of all the AM detectors that I've tried and/or developed, only one sounds 'nice' when confronted by heavy broadcast processing and that is an AM detector 'based' on a voltage doubler/diode integrator circuit (similar to the above circuit, actually the 68 pf capacitor should be changed to .1 uf, for slightly greater output).

It has taken me a very long time (years) to 'optimise' this circuit, but as it presently stands this is my favourite 'nice sounding' AM detector, and gets most use for general high quality listening on the AM broadcast band. It sounds really good! It somewhat reminds me of an old OA47 gold bonded diode detector from years ago before such abhorrent 'processing' became commonplace!

Ah yes the OA47….now that is a lovely sounding detector diode!

Regards, Felix vk4fuq. 17 / 10 / 2015.

* * * * * * * * * * * * * * *

That's it for crystal sets. I hope you try building one, it's easy and great fun!

See some useful links below....

73's
Mike

Crystal Sets (Part1) | **Build Your Own Crystal Set (Part 2)**

Spider's Web Crystal Set (Part 3) | **Crystal Set By Kenneth Rankin (Part 4)** | **Crystal Radio Links**

Amateur Radio

M0MTJ Visit my amateur radio pages M0MTJ

Visit my Amateur Radio Pages >

No AM radio stations or transmitters in your locality or country?

Spitfire
AM Transmitter

Has your local medium wave broadcast station closed or been moved to VHF/FM or Digital? Don't worry. You can still build and experiment with crystal sets and TRF radios by also buying or even building a simple low power AM transmitter. So, not only can you use your crystal sets but you can also run your own radio station that can be heard in and around your home - playing the music or programmes that you want to hear!

SSTRAN AMT3000 Superb high fidelity medium wave AM transmitter kits from SSTRAN. Versions available for 10kHz spacing in the Americas (AMT3000 or AMT3000-SM) and 9kHz spacing in Europe and other areas (AMT3000-9 and AMT3000-9SM). Superb audio quality and a great and well designed little kit to build: http://www.sstran.com/pages/products.html

POWER
GAIN
MODULATION
COMPRESSION
SSTRAN
AMT3000

http://www.sstran.com/

Other AM transmitters available:

Spitfire & Metzo Complete, high quality ready built medium wave AM Transmitters from Vintage Components: http://www.vcomp.co.uk/index.htm Vintage Components offer a choice of the high quality Spitfire and Metzo transmitters:

SPITFIRE AM Medium Wave Transmitter with 100 milliwatt RF output power:

http://www.vcomp.co.uk/spitfire/spitfire.htm

Spitfire
AM Transmitter

METZO AM Medium Wave Transmitter with built in compressor:

Gain
Comp
Mod
Metzo

http://www.vcomp.co.uk/metzo/metzo.htm

AM88 LP A basic AM transmitter kit from North County Radio.
http://www.northcountryradio.com/Kitpages/am88.htm

LINKS: Fine links to more Crystal Radio websites here

Component Suppliers: Links to electronic component suppliers here

Amateur Radio
M0MTJ Visit my amateur radio pages M0MTJ

Visit my Amateur Radio Pages >

Crystal Sets (Part1) | Build Your Own Crystal Set (Part 2)

Spider's Web Crystal Set (Part 3) | Crystal Set By Kenneth Rankin (Part 4) | Crystal Radio Links

^Top Of Page

Home | Contact | Site Map | Radio Stations & Memorabilia | Amateur Radio

Crystal Sets Introduction | Resistor & Capacitor Conversion Tables

www.mds975.co.uk © 2004 - 2015

Nov. 12, 1957

L. R. CRUMP

POWERING ELECTRICAL DEVICES WITH ENERGY
ABSTRACTED FROM THE ATMOSPHERE

Filed March 12, 1954

2,813,242


RF POWER
35
36
37
41
46
43
40
42
44
TRANSISTOR OSCILLATOR
52
55
61
64
69
70
HIGH VOLTAGE LEVEL d-c POWER
LOW VOLTAGE LEVEL d-c POWER

FiG. 3


1
2
5
15
16
20
22
21
17
6
23
25
3
7
26
+1 v.
10
31
30
11
27
-2 v.
12

FIG. 1


35
36
37
41
46
43
40
42
44
+DC
45
LOAD
-DC

FIG. 2

INVENTOR
Lloyd R. Crump

BY W.E. Thibodeau + A.W. Dew

ATTORNEYS

United States Patent Office

2,813,242

Patented Nov. 12, 1957

2,813,242

POWERING ELECTRICAL DEVICES WITH ENERGY ABSTRACTED FROM THE ATMOSPHERE

Lloyd R. Crump, Silver Spring, Md.

Application March 12, 1954, Serial No. 415,986

1 Claim. (Cl. 321—2)

(Granted under Title 35, U. S. Code (1952), sec. 266)

The invention described herein may be manufactured and used by or for the Government for governmental purposes without payment to me of any royalty thereon.

This invention relates to the convenient and economical provision of power for the operation of electronic circuits and devices using transistors, and of other electrical devices having modest power requirements.

A great advantage of transistors, and a major reason for their enthusiastic reception since their introduction a few years ago, is the fact that they will operate satisfactorily with very low supply voltages and currents. One milliwatt or even less is sufficient to power a transistor in many applications. Various batteries have been developed to provide, in a minimum of space, the relatively minute amounts of power needed by transistors.

My invention provides methods and means that permit transistor circuits, and also other low-powered electrical devices, to be economically and conveniently operated without any batteries whatever, and indeed without any power supply whatever as power supplies are ordinarily conceived.

The invention centers around my discovery that it is practicable to construct operative transistor circuits that are able to abstract from the atmosphere sufficient electromagnetic energy to provide all necessary supply voltages and currents for their own operation. Circuits and devices powered according to my invention will operate indefinitely without any local power source whatever.

I have successfully constructed and demonstrated such circuits. For example, I have constructed a batteryless transistor radio receiver on which I have listened to either nearby or distant broadcast stations as desired, using either headphones or a loudspeaker; this receiver has been powered entirely by electromagnetic energy abstracted from the atmosphere.

From the successful operation of this receiver, and from other experimental work, it becomes clear that, by the methods and means of the invention, a great variety of practical and useful transistor circuits can be powered entirely by energy abstracted from the atmosphere.

Furthermore, as will become apparent below, my invention is applicable to the powering of other electrical devices requiring relatively small amounts of power.

An object of the present invention is to provide methods and means for powering transistor circuits entirely from radiofrequency energy abstracted from the atmosphere.

Another object is to provide methods and means for powering remote radio receivers, low-powered radio transmitters, and other low-powered electrical devices, with energy received by radio from a master station, so that no local power supplies are needed by the devices and so that the powering or non-powering of the remote device is under the control of the master station.

A further object is to provide methods and means for powering transistor circuits and other low-powered electrical devices with radiofrequency energy received from one or more remote radio transmitters.

Other objects, aspects, uses, and advantages of the invention will become apparent from the following description and from the drawing.

Figure 1 is a schematic diagram of a transistor radio receiver in which all necessary power is supplied by energy abstracted from the atmosphere in accordance with the invention.

Figure 2 is a schematic diagram showing a general application of the invention to provide direct-current power to a load.

Figure 3 is a schematic diagram of a system for obtaining a high energy D.-C. source at a high voltage level using energy abstracted from the atmosphere.

Referring to Figure 1, a receiving antenna **1** is connected to antenna coupling coils **2** and **3**, the other ends of which are connected to ground. A parallel resonant circuit consisting of coil **5** and capacitor **6** is coupled to coil **2**. A second parallel resonant circuit consisting of coil **7** and capacitor **10** is coupled to coil **3**. A third parallel resonant circuit consisting of coil **11** and capacitor **12** is also coupled to coil **3**.

Coil **5** and capacitor **6** are tuned to the frequency of a radio transmitter from which it is desired to receive information—for instance, an amplitude-modulated standard broadcast station. The signal received from this transmitter need not be strong. The signal is detected by diode **15** to obtain an audio-frequency information signal. This audio signal is coupled through a capacitor **16** and is amplified by a circuit that includes a transistor **17** having a base **20**, an emitter **21**, and a collector **22**. The amplified audio output of the transistor is coupled through an audio transformer **23** to an electroacoustical transducer, preferably a permanent-magnet dynamic loudspeaker **25** as shown.

The novelty of the invention lies largely in the method and means by which the necessary direct-current power is supplied to the emitter and collector circuits of transistor **17**. This method and means will now be described.

Coil **7** and capacitor **10**, and also coil **11** and capacitor **12**, are tuned to receive radio signals of relatively high strength. It does not matter whether these signals contain information. These power signals are rectified by diodes **26** and **27** to provide direct-current power that is filtered by capacitors **30** and **31**. The D.-C. power thus obtained is utilized to power the transistor **17**.

In the circuit shown, two tuned circuits (coil **7** and capacitor **10**, and coil **11** and capacitor **12**) are tuned to power signals and the D.-C. voltages obtained from each are connected in series. The tuned power circuits may be tuned to the same or different power signals. Under certain circumstances it may be desirable to use more than two tuned power circuits and to tune them to more than two power signals; in this way power can be obtained from several signals and combined. On the other hand, if a strong power signal is available, a single tuned power circuit may suffice to give the needed D.-C. power.

Even weak information signals can be received successfully. A plurality of transistor amplifier stages can be used if desired, or other circuits such as superheterodyne circuits can be used. It is merely necessary that a sufficiently strong power signal or signals be available to provide the small amount of D.-C. needed to power the transistors.

If the information signal happens to be strong, it can be used as the power signal; all of the tuned circuits (coil **5** and capacitor **6**, coil **7** and capacitor **10**, coil **11** and capacitor **12**) are tuned to the information signal.

Engineers who have observed my invention in operation have been surprised at the unexpectedly good results obtained, even with readily available power signals of quite moderate strength. For instance, sufficient power for satisfactory operation of a loudspeaker at low volumes is readily obtained from a 5-kilowatt standard broadcast station 5 miles away, using only an indoor antenna to pick up the power signal as well as information signals. In typical operation under these conditions a D.-C. voltage of about 2.5 to 3 volts is obtained between the emitter and the collector, at a current of about 250 microamperes; D.-C. power input to the transistor is thus of the order of 0.5 to 1 milliwatt. So far as I am aware, no one has ever before discovered and demonstrated the practicability of this method of powering a radio receiver.

Because existing broadcast stations within a radius of a number of miles provide adequate power signals, the invention is readily practicable with existing power signals in almost any location in or near any city in the United States.

Although I have described a transistor radio receiver powered by my invention, it will be readily apparent that the invention is applicable to the powering of any transistor circuit using one or a number of transistors, and to the powering of other devices requiring relatively small amounts of power. For instance, sensitive electromechanical, electrochemical, or electrothermal devices can be operated by the method of the invention.

Referring to Figure 2, which shows a more general embodiment of my invention, an antenna **35** picks up radiofrequency energy from the atmosphere. This energy flows through coil **36**, which is coupled to a tuned circuit consisting of coil **37** and capacitor **40**. The radiofrequency voltage across capacitor **40** is rectified by diode **41** and filtered by a low-pass filter **46** consisting of capacitors **42** and **44** and choke coil **43**. The resulting D.-C. voltage is applied to a load **45**.

In the practice of my invention, larger amounts of power can be obtained for short periods of time by storing received energy in a suitable energy storage device. Stored energy may then be withdrawn at intervals at a more rapid rate than that at which it was received and put into the storage device. In this way the invention can be used to provide short pulses of relatively very high electrical energy. This result can be readily obtained by charging a relatively large capacitor with direct current and then discharging the capacitor rapidly into a load when desired. This rapid discharge can be initiated automatically when the voltage across the capacitor reaches a certain level, or it can be initiated when a transistor radio receiver receives a certain information signal.

Higher voltages can be obtained with the invention by means of well known devices for raising D.-C. voltages as shown in Figure 3. The D.-C. voltage output from the capacitor **44** can be used to power a low frequency transistor oscillator **52** whose A.-C. output is raised to a higher voltage level by the transformer **55**. This relatively high A.-C. voltage can then be rectified by a diode **61** and fed to a capacitor **64** to provide a high energy D.-C. source at a relatively high voltage level at the terminals **69** and **70**. If desired, energy can now be withdrawn from the capacitor **64** at intervals in short pulses of high energy at a high voltage level. Pulsed radio transmission is one of the possible uses for this form of the invention. Other uses would be to provide a single relatively powerful pulse needed to actuate an electrothermal or electromechanical device.

As has been indicated above, in many locations and particularly anywhere in or near most American cities, power signals normally present in the atmosphere are readily available for the easy and convenient practice of the invention. However, the invention also has important applications in systems in which the necessary power signal is generated and transmitted specifically for the operation of the particular system. Such systems can, for example, comprise a master station transmitting all the power that is needed for hundreds or thousands of fixed or mobile transistor receivers or other remote devices over a range of many miles. This eliminates the need for hundreds or thousands, as the case may be, of local power supplies. At the same time, such a system has the advantage that all of the remote devices can be simultaneously activated or deactivated at the will of the master station, simply by starting or stopping the transmission of the power signal. In such systems it will often be advantageous to use power signals of frequencies sufficiently high to permit the use of resonant receiving antennas of small physical dimensions for signal pickup at the remote devices. In addition to the power signal, the master station may transmit an information signal on the same or a different carrier.

Certain types of devices powered entirely by received radio waves are of course well known. The well-known "crystal set" of the early days of radio, which used a diode rectifier to demodulate an amplitude-modulated radiofrequency signal, is an outstanding example of such a device. My invention is readily distinguishable from such prior devices, however. In typical prior devices a modulated radiofrequency signal is applied to a diode to obtain unidirectional half-wave pulses whose amplitudes vary with modulation. These pulses are integrated by means of a capacitor to obtain a unidirectional signal the amplitude of which follows the audiofrequency modulation envelope. If the radiofrequency signal is received with sufficient strength the audio signal may have sufficient power to operate headphones or similar utilization device without power amplification; but the signal is utilized for its information content, rather than to supply non-information-containing power.

My invention, on the other hand, entails the utilization of received radiofrequency energy to supply power to at least one pair of circuit points (across capacitor **31** in Fig. 1, for example), such circuit points requiring power solely for its power content and not for any information or modulation it may contain. In other words, my invention entails the utilization of radiofrequency energy to supply power that would otherwise have to be supplied by batteries, generator, or other local power source.

It will be apparent that the embodiments shown are only exemplary and that various modifications can be made in construction and arrangement within the scope of the invention as defined in the appended claim.

I claim:

An electrical device for obtaining a high energy D.-C. source at a high voltage level using energy abstracted from the atmosphere, said device comprising in combination: resonant means for receiving radio waves, first rectifier means for converting said radio waves into first direct current energy, first capacitor means for storing said first direct current energy, an oscillator powered by said direct current energy, said oscillator producing an A.-C. output, transformer means for raising said A.-C. output to an increased voltage level, second rectifier means for converting the A.-C. output of increased voltage level from said transformer into second direct current energy, and second capacitor means for storing said second direct current energy.

References Cited in the file of this patent

UNITED STATES PATENTS

1,540,998	Plauson	June 9, 1925
2,056,824	Cawley	Oct. 6, 1936
2,553,734	Adler	May 22, 1951
2,569,687	Pan	Oct. 2, 1951
2,647,957	Mallinckrodt	Aug. 4, 1953

OTHER REFERENCES

Turner: "A crystal receiver with transistor amplifier," Radio and Television News, January 1950.

FREE-POWER AM RECEIVER (P,E)

This project uses a strange way to get its power. It uses power “extracted” from the tuned station to give to the amplifier transistor. With a reasonably strong applied modulation envelope, this type of detector produces a strong demodulated output.

Naturally, the closer you are to a strong station, the more current your radio will be able to supply.

For best results, you must do everything possible to deliver a strong signal to the transistor detector. We recommend a good antenna and ground, the latter preferably being made to a water pipe or solid external ground composed of a pipe driven at least 5 feet into moist earth. This is important for ensuring maximum signal pickup.

If you have plenty of space available, the longer the antenna (up to about 100 feet), the better the results.

Figure 1 shows the schematic diagram of the Free-Power AM receiver. Observe that the heart of the circuit is a germanium transistor that works as a detector and audio amplifier.

Components placement on a terminal strip used as a chassis is shown in ***Figure 2.*** The terminal strip can be fixed on an experiment board that can be constructed using some common tools and materials.

Q1 is any germanium transistor, such as GE-2 or 2N107. You can find germanium transistors in old nonworking AM transistor radio receivers. Nonworking AM radios can also supply the variable capacitor and the loopstick (ferrite rod).

Earphone must be a high-impedance crystal type. Low-impedance earphones don’t function in this circuit.


A
A
Q1
(*)
L1
CV
(*)
R1
12K
C1
1μF
+
XTAL
R2
10K
G
(*) SEE TEXT

Figure 1


L1
A
G
EARPHONE
XTAL
Q1
CV
R1
+
C1

Figure 2

Parts List — Free-Power AM Receiver

Q1	- NPN or PNP germanium transistor - see text
XTAL	- Crystal earphone
L1	- Loopstick - see text
CV	- 365 pF variable capacitor - see text
R1	- 12,000 ohm, 1/4W, 5% resistor
C1	- 1 uF, 25 WVDC electrolytic capacitor

Ideas to Explore

To learn more about the circuit:

- Replace L1 by 15 turns of No. 28 wire, wound on a ferrite rod, to tune short-wave stations.
- By replacing Q1 with a germanium diode and removing R1 and C1 you'll transform this radio into a simple crystal set.
- Alter R1 in a range between 4,700 and 47,000 ohms to get better performance, depending on the transistor used.
- Replace the transistor with a silicon type, such as the BC548. What will happen with sensivity?

Science project involving the circuit and uncommon uses:

- Explain how crystal sets function and tell about radio history. If you are interested in more radio history, several texts can be found in the public library.
- If you want to learn more about radio receivers, try to find information about heterodyne and super-hereterodyne types.

OLEG D. JEFIMENKO
West Virginia University

Electrostatic Motors

Their History, Types, and Principles of Operation —

With many illustrations, of which 57 are
by
David K. Walker
of
Waynesburg College

Electret Scientific Company
Star City

UNIVERSITY OF COLORADO
DENVER CAMPUS LIBRARY

Copyright © 1973 by
Electret Scientific Company
P.O. Box No. 4132
Star City, West Virginia 26505

All rights reserved

Printed in the United States of America

This book is dedicated to an accomplished
farmer, craftsman, musician,
educator, and lawyer
MY FATHER

PREFACE

The fascinating science of electrostatics was developed mainly in the 18th century at a time when the technology and industry were too primitive to put this science to practical uses. As a result, serious research in electrostatics soon lost its momentum and, except for a few isolated efforts, was practically nonexistent during the entire 19th century. Only very recently practical aspects of electrostatics began to make their impact on the industry and economy, and the once glamorous but long forgotten science has again appeared at the focal point of serious scientific investigations.

A peculiar obstacle stands, however, in the way of many such investigations: because of the one and one half century of neglect of electrostatic explorations there is a singular lack of easily available quantitative and qualitative information on even the most basic electrostatic phenomena, techniques, and devices. Whereas experimental and theoretical data pertaining to most modern sciences are well documented and are easily retrievable from numerous reference sources, many data in the field of electrostatics must be extracted through thorough and laborious firsthand studies of old books and magazines, the very existence of which is not generally known, and which are not readily available in any of the present-day libraries or repositories.

It is precisely this kind of obstacle that the author encountered, when several years ago he started his research on electrostatic motors. Luckily, however, the obstacle soon transformed itself into a highly rewarding experience of studying various "ancient" books and periodicals and searching through electrostatic inventories of various European and American science museums. In the course of these studies he found numerous forgotten publications on electrostatic motors and found that several old electrostatic motors can actually be seen in some of the museums. (It is interesting to note that the latter motors are usually not on public display, apparently because of a lack of adequate information about their purpose and mode of operation available to museum personnel. It is also interesting to note that certain types of electrostatic motors were frequently employed in various animated toys during the second half of the 18th century, and that, although some of these toys are shown in museums, they are usually shown without an explanation of what made them move or how they were supposed to function.)

The purpose of this book is to describe the various types of electrostatic motors reported in the scientific literature between 1700 and the present, and to discuss in general terms their various design features and principles of operation. The book is written for a wide circle of readers, and care has been taken to avoid technical details that would be useful only to a small group of specialists. The readers interested in additional scientific and technical data on the various motors are referred to appropriate original publications cited in this book.

The material is presented in several chapters, each chapter describing a particular class of motors. The sequence of the chapters corresponds to the chronological order in which the earliest motor belonging to each particular chapter was invented. The sequence of material in each chapter is normally arranged also in a chronological order. The last chapter describes some of the most recent research results on electrostatic motors and extrapolates these results into the immediate future.

The author is grateful to his wife Valentina for typing the manuscript and for otherwise helping him to make the book ready for publication. He is also grateful to Dr. David K. Walker for reading the manuscript and for drawing the illustrations for the book.

Oleg D. Jefimenko

CONTENTS

Preface vii

1. What are Electrostatic Motors? 1

Electromagnetic and Electrostatic Motors. Some Unique Properties of Electrostatic Motors. Classification of Electrostatic Motors.

2. Electric Pendulum Motors; Contact Motors. 6

Gordon Electric Bells. Electric Swing. Electric Seesaw. Electric Perpetuum Mobile. Dailey Reciprocating Motor. Electric Racing Ball.

3. Electric Wind Motors. 22

Gordon Electric Fly. Hamilton Electrometer. Langenbucher Electrometer. Electric Orrery. Kinnersley Electric Horse-Race. Bichat Electric Tourniquet. Corona-Kraft Levitation. Electric Wind Wheels and Turbines. King Electric Rabbit Hunt.

4. Franklin's Spark Motors and Their Descendants. 39

Franklin First Motor. Franklin Second Motor. Moore Motors. Bell Jar Motors. Another Electric Perpetuum Mobile. Dressel Nuclear Battery Motor.

5. Corona Motors and Motors Similar to Them. 56

Holtz Rotation Phenomenon. Poggendorff Motor. Christiansen Motors. Gruel Electric Tourbillion. Ruhmkorff Motor. Johnson Motors. McVay Motors.

6. Capacitor Motors. 73

Zipernowsky Motor. Van Huffel Motor. Synchronous and Asynchronous Motors. Bollée Capacitor Motors. Moore Interdigital Motor.

7. Induction Motors. 84

Arno Motor. Weiler Induction Motors. Bollée Induction Motors. Choi and Dunn Motor.

8. Liquid-Immersed Motors. 91

Weiler Liquid-Immersed Motor. Secker Motors. Quincke Motor.

9. Electret Motors. 97

Gubkin Motor. Slot-Effect Motors. Synchronous Electret Motor.

10. What to Expect from Electrostatic Motors. 106

Motors for Miniaturized Systems. New Corona Motors. Sources of Power for Electrostatic Motors. Operation of Electrostatic Motors from Atmospheric Electricity.

11. Index 120



PLATE 1

Here is what H. B. Dailey wrote about this electrostatic motor which he and his father built in 1880: "Whether or not there is about the instrument and its history that which would ever give it a claim to any measure or serious interest, it is at least an electric motor most unique. A motor without magnetism, wiring, or any iron in its make up. A motor that runs by the action of the direct push and pull of the pure unconverted electricity itself".



PLATE 2

It was Benjamin Franklin who in 1748 constructed the first electrostatic motors. No original drawings or models of his motors are known to exist, but his first motor must have looked very similar to this replica designed by the author for the Electret Scientific Company.



PLATE 3

Franklin's second motor probably looked very much like this replica also designed by the author for the Electret Scientific Company. Whereas the first motor operated from the electricity stored in Leyden jars, this motor operated from the electricity stored in the motor itself.



PLATE 4

The first corona motor was designed around 1869 by the German physicist Poggendorff. Poggendorff made a thorough study of the motor, but failed to appreciate its possibilities in the mistaken belief that no sources of electricity could supply enough power to any electric motor to make it do useful work. This simplified version of Poggendorff's motor was built by the author.



PLATE 5

The electret—a permanently electrized dielectric—is essentially a product of the 20th century. When an electret is placed between slotted electrodes to which a voltage is applied, the electret experiences a force. This motor designed by the author utilizes the slot effect. The rotor of the motor is a carnauba wax electret made of two oppositely polarized half-disks. The motor was built in 1966.



PLATE 6

A more practical design of an electret motor incorporates stationary electrets and rotating electrodes. The electrets can be easily withdrawn from the motor for servicing or replacement. The motor operates from approximately 60 volts dc. This particular motor was the first ever operated from atmospheric electricity.



PLATE 7

In this electret motor developed in the author's laboratory (as were all the electret motors reproduced in these photographs) several thin mica electrets are used as active elements. This arrangement of electrets makes good use of the available space and allows one to construct relatively powerful electret motors.



PLATE 8

This "hoop" electret motor built in 1967 by D. K. Walker has a stationary cylindrical electret. The rotor is made of four pairs of bent aluminum plates enclosing the electret. The motor requires no commutator. The motor has been operated for several years without any servicing.



PLATE 9

Corona motors are probably the most promising electrostatic motors. This 0.1-hp modern version of the Poggendorff motor has a cylindrical rotor instead of a disk. The motor operates from a 6000-volt power supply as well as from an earth field antenna.



PLATE 10

The operation of electrostatic motors from antennas can be demonstrated with this lecture-room apparatus. The Van de Graaff generator produces electric charges in the air. The sharp-point antenna collects the charges from the air and delivers them to one terminal of an electrostatic motor whose other terminal is grounded.

PLATE 11

The author and D. K. Walker attempt to operate an electret motor from a 20-foot pole antenna in front of the Physics Building of the West Virginia University. The tall building screened the atmospheric field, and the motor did not run, although it operated very well from the same antenna in the nearby unobstructed parking lot.



PLATE 12

The author operates electrostatic motors by means of an airborne antenna.

1

WHAT ARE ELECTROSTATIC MOTORS?

Conventional electric motors create mechanical motion as a result of magnetic forces acting upon electric currents. These motors are properly called *electromagnetic motors*. There is, however, another type of electric motor, in which the motion is created as a result of electric, or "electrostatic", forces acting between electric charges. Motors of this type are called *electrostatic motors*.

It is interesting to note that in nature the electrostatic forces are much stronger than the magnetic ones. There are many ways in which this can be demonstrated. For example, although a considerable effort may be needed to separate a magnet from an object attracted by it, a much greater effort is needed to break the magnet; this is because the magnet and the object are held together by magnetic forces, while the molecules of matter in the magnet (as well as in any other body) are held together by electrostatic forces.

Why, then, do we not use the electrostatic forces in our electric devices, and in motors in particular, at least on as wide a scale as we use the "inferior" magnetic forces? There are two main reasons for that. First, it is difficult to establish appreciable concentrations of electric charges without causing an electric breakdown in the medium surrounding or supporting the charges (although with modern insulating materials and techniques this difficulty becomes progressively less serious). Second, powerful electrostatic devices require voltages of many kilovolts for their operation, and until recently such voltages could not be produced conveniently and economically.

Motors of great power, however, are not the only ones needed. Equally important are low-power motors capable of performing various special tasks. In this respect electrostatic motors may compete successfully with their electromagnetic cousins even now.

Although electrostatic motors are not yet widely known or used, they already hold at least five very impressive records as compared with the electromagnetic motors:

1. The first electric motor ever invented was an electrostatic one. It was built about 100 years before the first electromagnetic motor was conceived.

2. The electric motor that operated without interruption longer than any other electric motor was an electrostatic one. This was a pendulum-type motor, known as the "electric perpetuum mobile", installed at the University of Insbruck, Austria, in 1823. Since then it operated continuously at least until 1909, powered by a Zamboni pile (an early high-voltage battery).
3. Electrostatic motors have been operated from voltages in excess of 10^5 volts, which is much higher than the voltages suitable for operating electromagnetic motors.
4. Electrostatic motors have been operated by using currents smaller than 10^{-9}amp, which is much less than the currents needed to operate electromagnetic motors.
5. The first electric motor that operated directly from the atmospheric electricity was an electrostatic motor. None of the presently available electromagnetic motors can operate directly from this source.

Even this short list reflecting some of the more obvious peculiarities of electrostatic motors shows quite clearly that electrostatic motors possess a number of unique properties. These properties undoubtedly will make electrostatic motors increasingly more important for the science, engineering, and technology of the future.

Many different types and designs of electrostatic motors are possible. It is customary to classify electrostatic motors in accordance with some prominent feature of their mode of operation or some prominent feature of their design. Thus, in reference to the techniques used for delivering electric charges to the active part of a motor one speaks of *contact motors*, *spark motors*, *corona motors*, *induction motors*, and *electret motors*. In reference to the medium in which the active part of a motor is located one speaks of *liquid-* or *gas-immersed motors*. In reference to the material and design of the active part of a motor one speaks of *dielectric motors* (the active part is made mainly of dielectric material) and *conducting-plate*, or *capacitor*, *motors* (the active part is made mainly of metal and resembles a variable capacitor). Finally, in reference to the rate of rotation of a motor relative to the period of the applied voltage (for ac operated motors) one speaks of *synchronous motors* and *asynchronous motors*.

This classification of electrostatic motors does not make it possible, however, to specify uniquely each individual motor. Also, two or more different operation modes are usually possible for most electrostatic motors (for example, certain motors can be operated at will as contact, spark, or corona motors). Therefore an assignment of a particular motor to one or another of the above types or categories is frequently more or less arbitrary. This applies, of course, also to the present book, where certain motors described in the chapters that follow could be equally well discussed under different chapter headings, and where the inclusion of certain motors in a particular chapter was occasionally dictated by the fact that such an inclusion resulted in a more coherent development of the subject matter.

2

ELECTRIC PENDULUM MOTORS; CONTACT MOTORS

If "electric motor" is understood to be a device converting electric energy into a continuous mechanical motion, then the first two electric motors were invented in the early 1740's by Andrew Gordon, a Scottish Benedictine monk and professor of philosophy at Erfurt, Germany.[1] Gordon's first motor was a device known as the "electric bells" (his second motor will be described in the next chapter). The device and its operation were as follows. A metallic clapper (pendulum) was suspended by a silk thread between two oppositely charged bells (Fig. 1). From an initial contact with one of the bells the clapper acquired a charge of the same polarity as that of the bell. Due to repulsion of like charges and attraction of opposite charges the clapper was then repelled by this bell and attracted by the second bell. As the clapper struck the second bell, it gave off its initial charge and acquired a charge of the same polarity as that of the second bell. Then the clapper was repelled by the latter and attracted by the first bell, which it struck again, and so on.

Numerous variations of Gordon's bells have been described by later authors, mostly as devices for lecture-room demonstrations of electrostatic forces. Such devices are widely used for this purpose even now.

An ingenious application of Gordon's bells was made by Benjamin Franklin in 1752. He connected the bells to an insulated lightning rod as a warning device "to give notice when the rod should be electrified".[2] (It appears that at that time neither Franklin nor any other scientist suspected how dangerous this "warning" device could be. The extreme danger of experiments with insulated lightning rods became clear a year later, when in 1753 the Russian physicist George Wilhelm Richmann was killed by lightning that entered his laboratory through such a rod, as he approached it in order to measure its electrification with a specially constructed electrometer.)

In a later modification of Gordon's invention one of the two bells was mounted on a Leyden jar (Fig. 2); the bells would then ring for as long as there was enough electric energy stored in the jar to move the clapper. (Franklin described the operation of an electric pendulum powered by a Leyden jar in 1747; see Ref. 2, p. 189.)

Sometimes Gordon's bells were made as a set



FIGURE 1

The so-called "electric bells" constituted the first device that converted electrical energy into a continuous mechanical motion. They were invented in about 1742 by Andrew Gordon, a professor of philosophy at Erfurt, Germany.



FIGURE 2

In a later modification of Gordon's invention one of the two bells was mounted on a Leyden jar. The bells would then ring for as long as there was enough electrical energy stored in the jar to move the clapper.



FIGURE 3

Sometimes Gordon's bells were made as a set of three bells and two clappers, all suspended from a horizontal bar, the central bell being insulated from the bar and grounded by means of a light chain.



FIGURE 4

Another modification of Gordon's bells was a set of bell chimes arranged on a wooden base in a circular formation around the central bell. A separate clapper was then present for each of the outside bells.



FIGURE 5

The electrical and mechanical principle of Gordon's invention could be used not only for ringing bells but for creating a mechanical motion in general. In this "electric swing" this principle was used to operate an animated toy.



FIGURE 6

Various electrostatically operated toys were invented in the 18th and 19th centuries. This "electric seesaw" was basically a conducting bar oscillating about a horizontal axis on the same principle as the clapper of Gordon's bells.

of three bells and two clappers, all suspended from a horizontal bar, the central bell being insulated from the bar and grounded by means of a light chain (Fig. 3). Another modification of Gordon's bells was a set of bell chimes arranged in a circular formation around the central bell (Fig. 4); a separate clapper was then present for each of the outside bells, each clapper moving between one of the latter and the central bell (the central bell was usually grounded, the outside bells were connected to an electrostatic generator).

The electrical and mechanical principle of Gordon's invention could be used, of course, not only for ringing bells but also for a variety of other purposes. In particular, this principle was later used in two electrically operated toys: the "electric swing" and the "electric seesaw", which utilized, respectively, an insulated pendulum made as a swing (Fig. 5) and an insulated conducting swing bar capable of oscillating about a horizontal axis (Fig. 6).[3,4]

Except for Franklin's bells, all of the above devices were designed for operation from an electrostatic generator or from Leyden jars charged by such a generator. However, in 1806 a high-voltage chemical battery ("dry pile", later known as the "Zamboni pile") was invented by Georg Behrens, and in 1810 this pile was adapted by Giuseppe Zamboni to operate primitive electrostatic motors.[5] Inasmuch as a Zamboni pile could remain active for many years, the little motors that operated from it were known as the "electric perpetuum mobile". An example of such a perpetuum mobile is shown in Fig. 7 (see Chapter 4 for another design). The apparatus consisted of a light rigid insulated pendulum, pivoted just above the center of gravity, with a light conducting ring at the top. The ring was located between the two knobs of a Zamboni pile. When the ring contacted one of the knobs, it acquired a charge from the knob and was repelled from this knob and attracted to the second knob, and so on, just like the clapper in Gordon's bells. One such perpetuum mobile is reported to have operated without interruption for at least 86 years.[6]

The most sophisticated device derivable from Gordon's electric bells was probably the reciprocating electrostatic motor (Fig. 8 and Plate 1) built in 1880 by Howard B. Dailey and Elijah M. Dailey.[7] The motor, which is now at the Museum of History and Technology of the Smithsonian Institution, was described by one of its builders as follows:

"This machine operates by the direct action of static electric attractions and repulsions. It is constructed entirely of fine wood, glass and hard rubber, there being no magnetic materials used. The flywheel is of laminated, soft wood and runs in journal bearings of very small diameter. The moving balls, mounted on the walking beam of vulcanite, are made of wood, hollowed out so that the walls are about 2 millimeters thick.



FIGURE 7

This electric pendulum operated from a Zamboni pile, an early high-voltage battery. Since the pile remained active for years, the pendulum was known as an "electric perpetuum mobile".



FIGURE 8

The most sophisticated device derivable from Gordon's bells was probably this reciprocating electrostatic motor built in 1880 by H. B. Dailey and E. M. Dailey.

They are covered with aluminum foil for static conductivity. The stationary balls are of solid wood.

"To operate the engine the stationary balls are charged with electricity from a static electric generator, such as a Holtz machine, the upper balls being connected through the brass ball to one pole of the machine while the lower stationary balls are connected through the binding post on the bed frame to the opposite pole of the machine. Under proper conditions, when charged, the engine will make about 375 revolutions per minute.

"The walnut base upon which the engine is mounted is 14" long, 4" wide and 1¾" thick. The movable balls are about 1½" in diameter; the upper stationary balls are 1¾" in diameter; and the lower stationary balls, 1½". The four glass rods, mounted vertically, are about 6" high and spaced 6" apart along the bed. The diameter of the flywheel is 5¾". It is gilded and has small wire spokes. The connecting rod is 7" in length."*

The electric principle of Gordon's bells could be used also for producing a continuous unidirectional motion. A fascinating device of this type was the "electric racing ball", or the "electric planetarium", an excellent description of

---

*The author is grateful to Mr. Elliot N. Sivowitch, Smithsonian Institution Museum Specialist, for kindly providing this description and the photograph of Dailey's motor.



FIGURE 9

The electric principle of Gordon's bells could be used also for producing a continuous unidirectional motion. This "electric racing ball" was propelled along a conducting hoop by the same mechanism that moved the clapper in Gordon's bells.

which has been provided by M. Guyot.[8] The apparatus consisted of an insulated horizontal conducting hoop positioned above a conducting disk having a vertical rim concentric with the hoop (Fig. 9). The arrangement constituted a track for a light sphere of glass placed on the disk between the hoop and the rim. When the hoop and the disk were connected to an electrostatic generator, the sphere ran along this track due to attraction and repulsion exerted by the hoop and the disk upon the points of the sphere that acquired charges from contact with the disk and the hoop (the rolling of the sphere usually had to be initiated with a light push by hand, but once the sphere had started to run, it continued running for as long as the electrostatic generator was in operation).

Since the moving elements in the above described motors were charged by contact, the motors may be classified as "contact motors". This method of charging, however, is neither the only possible nor the most expedient one. Therefore contact motors will probably always be subordinate to most of the motors described in the following chapters. In this connection it may be useful to note that, upon a closer examination of the operation of Gordon's bells and other similar devices, one recognizes that the charging of the moving elements in these devices usually occurs by means of a spark that jumps from a stationary electrode (bell) to a moving element (clapper) as soon as the latter comes close enough to the former. Thus the actual physical contact between the moving and stationary components in these devices is not at all necessary for their operation. In fact, such a contact is harmful insofar as it results in energy losses from impact and friction.

REFERENCES

1. P. Benjamin, *A History of Electricity*, John Wiley and Sons, New York, 1898, pp. 506, 507.
2. J. Sparks, Ed., *The Works of Benjamin Franklin*, Whittemore, Niles, and Hall, Boston, 1856, Vol. 5, p. 301.
3. F. M. Avery, *Modern Electricity and Magnetism*, Sheldon and Company, New York, 1885, p. 241.
4. A. Neuburger, *Ergötzliches Experimentierbuch*, Ullstein & Co., Berlin, 1920, pp. 434-436.
5. Gilbert, *Annalen der Physik*, Ser. 1, Vol. 49, pp. 35-46, (1815).
6. Müller-Pouillet, *Lehrbuch der Physik und Meteorologie*, Friedrich Vieweg und Sohn, Braunschweig, 1909, 10th edn., Vol. 4, p. 338.
7. H. B. Dailey, *Modern Electrics*, Vol. 5, pp. 916-917 (1912).
8. M. Guyot, *Nouvelles Recreations Physiques et Mathematiques*, Gueffier, Paris, 1786, Vol. 1, pp. 272-274 and Plate 27.

3

ELECTRIC WIND MOTORS

As already mentioned in the preceding chapter, Andrew Gordon invented two electric motors. His second motor was the "electric fly",[1,2] also known as the "electric whirl", "electric pinwheel", or "electric reaction wheel" (Fig. 10). The electric fly consisted of one or more light metal arms with sharp-point ends bent at right angles to each arm and in the same circumferential direction. The fly was pivoted at its center on an insulated needle. When the needle was connected to an electrostatic generator, a corona discharge* took place from the sharp points of the fly. The air near these points became charged with charges of the same polarity as that of the fly and was then repelled from the points due to repulsion of like charges (the resulting motion of the air is known as the "electric wind"). Similarly, the points themselves were repelled from the charges in the air, and the fly rotated therefore in the opposite sense to that in which the points were directed.

---

*Corona discharge is a spontaneous electric conduction in a gas (air) originating from sharp conducting bodies whose electrostatic potential relative to the ground is 3000 volts or higher.

Also the electric fly was used for ringing bells or chimes. This was accomplished by suspending from the fly a clapper, which, as the fly rotated, struck in turn several bells positioned in a circular formation underneath the fly (Fig. 11).[3]

In 1760, Hamilton, professor of philosophy at Dublin, suggested to use a similar device as an electrometer.[4] In this electrometer small weights were suspended from the fly. As the fly turned, the weights were deflected from the vertical direction by centrifugal forces. This deflection was a measure of the fly's speed and, hence, of the strength of the source to which the fly was connected. A more sophisticated electrometer utilizing the electric fly was described by Jakob Langenbucher,[5] a silversmith at Augsburg, Germany, who spent a large part of his time and fortune on improving electrostatic generators and studying electrostatic phenomena. In this electrometer the fly was mounted on a thin vertical cylinder. A fine string was fastened to the cylinder. The string passed over a small pulley and had a light pan attached to its free end. A small weight was placed on the pan. As the fly turned, the string



FIGURE 10

Andrew Gordon invented two electric motors. His second motor was the so-called "electric fly".



FIGURE 11
Also the electric fly was used for ringing bells with the aid of a clapper suspended from it.

wound itself on the cylinder lifting the pan and the weight. The maximum weight that could be lifted by this electrometer was a measure of the strength of the source from which the fly was operated.

The principle of the electric fly was later used to operate an orrery depicting the orbital motions of the Sun, the Moon, and the Earth (Fig. 12).[6] In such an orrery, also known as the "electrical tellurium", the longer bent arm carried a large sphere at one end, while at the other end it carried a similar but smaller bent arm, each end of which also carried a small sphere. The three spheres represented the Sun, the Moon, and the Earth. The arms were pivoted on sharp points, and each arm had a perpendicular sharp point in the horizontal plane. When the instrument was connected to an electrostatic generator, the two systems rotated about their points of support, the smaller system, being lighter, rotated more rapidly than the larger one. The relative masses of the spheres were adjusted to make the Earth-Moon system rotate twelve times for every single rotation of the Sun.

An interesting variation of the electric fly was constructed in 1761 by Ebenezer Kinnersley, a Philadelphia school teacher and close friend of Benjamin Franklin. Kinnersley called his device the "electrical horse-race".[7] This was a cross formed by two pieces of wood of equal length (probably about 18 inches long) supported horizontally on a central pin. A light figure of horse



FIGURE 12

The principle of the electric fly was later used to operate an orrery depicting the orbital motions of the Sun, the Moon, and the Earth. The masses of the spheres were adjusted to make the Earth-Moon system rotate twelve times for every single rotation of the Sun.



FIGURE 13

An interesting variation of the electric fly was constructed in 1761 by Ebenezer Kinnersley, a friend of Benjamin Franklin. Kinnersley called his device the "electrical horse-race". The electrical horse-race was a popular toy in the latter part of the 18th century.

with his rider was placed upon each extremity of the cross. The motion was produced by corona discharge from the spurs of the riders (Fig. 13). The electrical horse-race was a popular toy in the latter part of the 18th century. Interesting descriptions of this toy have been provided by Langenbucher (Ref. 5, p. 206 and Plate 8), and by Guyot.[8]

To show more convincingly that the electric fly converted electrical energy into mechanical energy, electric flies were placed on horizontal axes and were arranged to lift small weights (Fig. 14) or to climb inclined rails (Fig. 15).[9]

Operation of the electric fly in liquids was investigated by Aimé.[10] A historical account of electric fly studies was presented by Tomlinson.[11] The mechanism of the fly was discussed at some length by Mascart.[12] A quantitative study of the forces acting upon the electric fly was performed by Kämpfer.[13]

A more efficient modification of the electric fly was proposed in 1887 by Bichat.[14] Bichat's electric "tourniquet" consisted of a light vertical frame capable of turning about a vertical axis and supporting two thin vertical wires producing a corona discharge along their entire length. The vertical sides of the frame acted as "spoilers" preventing a corona discharge from the "back side" of the wires. A simple motor based on Bichat's device is shown in Fig. 16.

In recent years the principle of the electric fly (reaction force experienced by a sharp point as a



FIGURE 14

Electric fly converted electrical energy into mechanical energy and could lift small weights.



FIGURE 15

Electric fly developed enough mechanical energy for climbing inclined rails.



FIGURE 16

A more efficient modification of the electric fly was proposed in 1887 by Bichat, who called his device the "electric tourniquet".

result of a corona discharge from it) has been suggested for a flying machine ("corona-kraft levitation").[15] The lift realizable from such a machine does not, however, appear to be of practical significance.[16]

Closely related to the electric fly were the "electric wind wheels" and the "electric wind turbines". Like the electric fly, they were invented in the 1740's and utilized a corona discharge from sharp points for their operation. Benjamin Franklin studied these devices in 1747 (he first learned of them from his friend Philip Syng). According to Franklin (Ref. 7, p. 184) they were "light windmill-wheels made of stiff paper vanes; also. . .little wheels, of the same matter, but formed like water-wheels". Their probable appearance was as shown in Figs. 17 and 18. Later versions of these devices have been described by Guyot (Ref. 8, pp. 274, 275 and Plate 27), by Langenbucher (Ref. 5, pp. 75, 76 and Plate 3), by Gale,[17] and by Neuburger.[18]

A delightful electric toy using the electric wind for its propulsion was made by W. R. King, an associate of James Wimshurst (the designer of the electrostatic machine carrying his name). This toy, which may be called an "electrical rabbit hunt", now at the Science Museum in London, is shown in a simplified form in Fig. 19. It consists of a small electric wind turbine mounted on a vertical shaft carrying five light metal arms on its upper end; the arms support



FIGURE 17

Closely related to Gordon's electric fly was the "electric wind wheel". Like the electric fly, it was invented in the 1740's and utilized a corona discharge from two sharp points for its operation.



FIGURE 18

Benjamin Franklin studied this "electric wind turbine" in 1747. He concluded that its action depended not as much on the electric wind as on the forces between the charges present on its moving and stationary parts.



FIGURE 19

A delightful electric toy utilizing the electric wind for its propulsion was made by E. R. King, an associate of James Wimshurst. This toy, which may be called an "electrical rabbit hunt", is now at the Science Museum in London.

figurines of a rabbit, three dogs, and a horseman, who chase each other in a beautiful little garden, as the arms turn powered by the turbine below.

In studying the electric wind motors, Benjamin Franklin concluded that their action depended not as much on the electric wind as such, but on the repulsion and attraction of electric charges present on the moving and stationary parts of the motors (Ref. 7, p. 184). It is very probable that this conclusion led him to the invention of his big electric motors, the famous "electrical wheels", which are described in the next chapter.

REFERENCES

1. P. Benjamin, *A History of Electricity*, John Wiley and Sons, New York, 1898, pp. 506, 507.
2. J. C. Poggendorff, *Geschichte der Physik*, Johann A. Barth, Leipzig, 1879, p. 846.
3. V. K. Chew, *Physics for Princes*, Her Majesty's Stationery Office, London, 1968, p. 13.
4. B. Wilson, *Philosophical Transactions*, Vol. 51, p. 896 (1760).
5. J. Langenbucher, *Beschreibung einer beträchtlich verbesserten Elektrisiermaschine*, Mathäus Reigers, Augsburg, 1780, pp. 54-56 and Plate 3.
6. G. Adams, *An Essay on Electricity*, London, 1799, 5th edn., pp. 580-581 and Plate 4.

7. J. Sparks, Ed., *The Works of Benjamin Franklin*, Whittemore, Niles, and Hall, Boston, 1856, Vol. 5, p. 371.
8. M. Guyot, *Nouvelles Recreations Physiques et Mathematiques*, Gueffier, Paris, 1786, Vol. 1, pp. 249, 250 and Plate 25.
9. H. J. Oosting, *Zeitschrift für den Physikalischen und Chemischen Unterricht*, Vol. 9, pp. 84-85 (1896).
10. R. Aimė, *Annales de Chimie et de Physique*, Ser. 2, Vol. 62, p. 421 (1833).
11. C. Tomlinson, *Philosophical Magazine*, Ser. 4, Vol. 27, p. 202 (1864).
12. M. E. Mascart, *Traitė d'Electricitė Statique*, G. Masson, Paris, 1876, Vol. 1, pp. 175-179.
13. D. Kämpfer, *Annalen der Physik*, Ser. 3, Vol. 20, pp. 601-614 (1887)
14. E. Bichat, *Annales de Chimie et de Physique*, Vol. 12, pp. 64-79 (1887).
15. A. Christenson and S. Moller, *AIIA Journal*, Vol. 5, pp. 1768-1733, (1967).
16. L. B. Loeb, *Electrical Coronas*, University of California Press, Berkley, 1965, pp. 402-406.
17. L. D. Gale, *Elements of Natural Philosophy*, Mark H. Newman, New York, 1846, p. 164.
18. A. Neuburger, *Ergötzliches Experimentierbuch*, Ullstein & Co., Berlin, 1920, pp. 432, 433.

4

FRANKLIN'S SPARK MOTORS AND THEIR DESCENDANTS

If one defines the "electric motor" as a machine capable of converting substantial amounts of electrical energy into mechanical energy, then it was Benjamin Franklin who invented the electric motor, for he was the first person to design and to construct a machine capable of accomplishing such a conversion.

Franklin built two electric motors, which he called "electrical wheels". He described them in a letter to Peter Collinson, Fellow of the Royal Society of London, written in Philadelphia in 1748.[1]

His first motor was a big machine, about 40 inches in diameter. The main part of this motor was a wooden disk mounted horizontally on a vertical wooden axle and carrying 30 glass spokes with brass thimbles on their ends (Fig. 20 and Plate 2). The axle turned on a sharp point of



FIGURE 20

Franklin's first "electrical wheel" was the earliest device converting substantial amounts of electrical energy into mechanical energy.



FIGURE 21

Franklin's second "electrical wheel" was more efficient than the first. It was powered by the electric charge stored in its capacitor-rotor.

iron fixed in its lower end and was kept in the vertical position by a strong wire mounted in its upper end and passing through a small hole in a thin stationary brass plate. Two oppositely charged Leyden jars (bottles) were placed in close proximity to the thimbles on the spokes, so that when the wheel turned, the thimbles barely missed the knobs of the jars.

As the thimbles moved past the Leyden jars, a spark jumped between a jar knob and the passing thimble, charging the latter with a charge of the same polarity as that of the knob. Therefore each knob attracted the oncoming thimbles ("opposite charges attract") and repelled the departing thimbles ("like charges repel"), causing the motor to turn. The motor, being perfectly symmetric, could turn in either direction, and usually required a starting push by hand to initiate the charging of the thimbles.

Here is how Franklin himself described the operation of his motor:[1]

"If now the wire of a bottle, electrified in the common way, be brought near the circumference of this wheel, it will attract the nearest thimble, and so put the wheel in motion; that thimble, in passing by, receives a spark, and thereby being electrified, is repelled, and so driven forwards; while a second being attracted, approaches the wire, receives a spark, and is driven after the first, and so on till the wheel has gone once round, when the thimbles before electrified approaching the wire, instead of being attracted as they were at first, are repelled, and the motion presently ceases. But if another bottle, which had been charged through the coating (e.i. charged oppositely to the first, O. J.), be placed near the same wheel, its wire will attract the thimble repelled by the first, and thereby double the force that carries the wheel round; and, not only taking out the fire (electric charge, O. J.) that had been communicated to the thimbles by the first bottle, but even robbing them of their natural quantity, instead of being repelled when they come again towards the first bottle, they are more strongly attracted, so that the wheel mends its pace, till it goes with a great rapidity, twelve or fifteen rounds in a minute, and with such strength, as that the weight of one hundred Spanish dollars, with which we once loaded it, did not seem in the least to retard its motion".

Franklin was not quite pleased with this motor, however, because it required "a foreign force, to wit, that of the bottles" for its operation. He constructed therefore a second, "self-moving", motor, which itself contained the electrical energy to be converted into the mechanical motion.

The second motor was made as follows (Fig. 21 and Plate 3). A disk of window glass, 17 inches in diameter, was gilded on each side, except for narrow areas next to the edge. Several lead spheres (bullets) were fixed to the edge of the disk and were connected in alternation to the two gold layers. The disk was mounted on a vertical axle consisting of two pieces of strong wire, each about 9 inches long; the upper wire being in contact with the top layer of gold, the lower wire being in contact with the bottom layer. The lower wire terminated in a sharp point resting on a piece of brass cemented within a glass salt-cellar. The upper wire passed through a hole in a thin brass plate cemented on a long strong piece of glass. This wire carried a small ball on its upper end for preventing a corona discharge from it. Several glass pillars with thimbles on their tops were positioned in a circle around the disk, so that the spheres on the edge of the disk barely missed the thimbles when the disk was in motion. The motor was powered by electricity stored in the disk itself, which, due to the two layers of gold, constituted a capacitor capable of storing an appreciable quantity of charge (to charge the rotor, the two layers of gold were temporarily connected to an electrostatic friction generator).

The motor operated on the same principle as Franklin's first motor, except that now the thimbles were stationary and received positive or negative charges from the passing spheres, rather than the other way around. As in the first motor, the rotation persisted as long as there was enough charge stored in the capacitor (rotor) to produce sparks between the spheres and the thimbles.

Franklin reported that his second motor

(which was more powerful than the first one) could make 50 turns in a minute and could run for up to 30 minutes on a single charging of the rotor.[1] Experiments with replicas of Franklin's motors performed by the author indicate that the original motors developed a power of the order of 0.1 watt,[2,3] which was a very impressive achievement for that very early period in the history of electric science.

Several authors have described simplified versions of Franklin's motors.[4,5] Miniature Franklin-type motors have been constructed and described by A. D. Moore[6] (Fig. 22). One such motor consists of a Plexiglas disk about 4 inches in diameter with small conducting balls embedded in the rim. The disk turns on a horizontal axis supported by a base behind the disk. The motor runs when placed between two conductors connected to an electrostatic generator. To make the motor self-starting and one-way running, the conductors may be provided with short auxiliary rods tangential to the disk; since the rods dispatch sparks predominantly in the direction of their free ends, the disk also turns in this direction. Another little motor of the same type designed by Moore is shown in Fig. 23.

An obvious improvement of Franklin's motors would be to use a cylindrical rotor with electrodes in the shape of long strips. Such electrodes would accept more charge than thimbles or spheres, and the power of the motor would be increased considerably. Motors of this type



FIGURE 22

Several authors have described simplified versions of Franklin's motors. One such motor consists of a Plexiglas disk about 4 inches in diameter with small conducting balls embedded in the rim. The disk turns on a horizontal axis supported by a base behind the disk.



FIGURE 23

This inexpensive miniature Franklin-type motor of recent design can be used for lecture-room demonstrations of electrostatic forces. The rotor disk can be made from cardboard, wood, or plastic. For the rotor electrodes one can use thumbtacks or small aluminum foil disks.

have indeed been constructed. Here is a description of a "bell jar" motor taken from a book published in 1847 (Fig. 24):

"On a pivot, *a*, suspend a bell jar having four pieces of tinfoil pasted on its sides, *b*, *c*, *d*; connect the jar, by means of the insulated wire, *y*, with the prime conductor (high-voltage terminal of an electrostatic friction generator, O. J.) so that the pieces of tinfoil may receive sparks. On the opposite side arrange a conductor, *x*, in connection with the ground by a chain. On putting the machine into activity, the jar will commence rotating on its pivot."[7]

Small motors closely related to both Franklin's first motor and to pendulum motors were used in the rotary-type "perpetuum mobile" (see Chapter 2) operated from a Zamboni pile.[8] The main part of these motors (Fig. 25) was a light insulated arm pivoted on a sharp point and carrying a piece of tinsel on each end. The tinsels could just touch the knobs of the pile when the arm was moving on its pivot. The device functioned in the same manner as Franklin's first motor, the two tinsels corresponding to the thimbles of the latter.

An analogous design has recently been described as a "millifleapower motor" operating from a nuclear battery.[9] In this motor a light aluminum vane with pointed ends (Fig. 26) bent so as to form an inverted V is mounted at its midpoint on the tip of a sharp needle protruding from the positive terminal of the battery. As the



FIGURE 24

This "bell jar" Franklin-type motor had a cylindrical rotor with tinfoil electrodes in the shape of long strips.



FIGURE 25

This small motor was used as a rotary-type "perpetuum mobile" operating from a Zamboni pile. Such motors turned for years without stopping.



FIGURE 26

An analogous design has recently been described as a "millifleapower motor" operating from a nuclear battery.

vane turns, its ends come close to two spheres connected with the ground through a high resistance and become attracted by them. A discharge from the ends of the vane charges the two spheres, and the spheres then repel the ends of the vane. During the time it takes the vane to complete one half of its revolution, the charges of the spheres leak off to the ground, so that the spheres can again attract the ends of the vane, accept new charges from them, and then again repel them. The motor is expected to run for many years.

An interesting motor derivable from Franklin's first motor and from pendulum motors was suggested for operation from an electrophorus.[10] The main part of this motor (Fig. 27) was a light conducting ring supported in a vertical plane on an insulated needle. In front of the ring there were two insulated spheres, which were so positioned that the ring just missed them as it turned on its needle. The spheres were either charged oppositely by the electrophorus, or only one sphere was charged, in which case the second sphere was grounded. The device operated on the same principle as Franklin's first motor.

Of all the motors discussed above, Franklin's original motors and the bell jar motor were the most powerful ones. One can make such motors even more powerful by increasing the number of moving and stationary electrodes. But this can be done only up to a limit, because if the electrodes are too close to one another, sparks will



FIGURE 27

This motor derivable from Franklin's first motor and from pendulum motors was suggested for operation from an electrophorus.

jump all around from one electrode to the next, thus short-circuiting the motor. The motor will then not work at all, unless the operating voltage is lowered. But by lowering the voltage one also lowers the power, so that the gain obtained by increasing the number of electrodes becomes offset by the decrease in the operating voltage. Franklin type motors have therefore an inherent limitation in their power characteristics, and the fact that they depend for their operation on the presence of many metallic electrodes is one of their disadvantages.

Since in Franklin's motors and in other motors described in this chapter the rotor is charged by means of electric sparks, these motors may be classified as "spark motors". Toward the end of the 19th century a way was found to construct electrostatic motors based on the same mechanism of attraction and repulsion between electric charges as in Franklin's motors, but with rotors (or stators) charged more efficiently than it is possible to do by means of the sparks. These motors are described in the next chapter.

REFERENCES

1. J. Sparks, Ed., *The Works of Benjamin Franklin*, Whittemore, Niles, and Hall, Boston, 1856, Vol. 5, pp. 204-207.
2. O. Jefimenko and D. K. Walker, *The Physics Teacher*, Vol. 9, pp. 121-129 (1971).
3. O. Jefimenko, *American Journal of Physics*, Vol. 39, pp. 1139-1140 (1971).

4. M. Guyot, *Nouvelles Recreations Physiques et Mathematiques*, Gueffier, Paris, 1786, Vol. 1, pp. 272-274 and Plate 27.
5. Dayton C. Miller, *Sparks, Lightning, Cosmic Rays*, MacMillan, New York, 1939, pp. 63, 64.
6. A. D. Moore, *Electrostatics*, Doubleday and Company, Inc., New York, 1968, pp. 104-108.
7. J. W. Draper, *Text-Book on Chemistry*, Harper and Brothers, New York, 1847, p. 105.
8. M. J. Jamin, *Cours de Physique*, Gauthier-Villars, Paris, 1869, 2nd edn., Vol. 3, p. 39.
9. R. H. Dressel, *High School Science Bulletin of the New Mexico State University*, Vol. 6, pp. 3-4 (April 1, 1964).
10. H. Wommelsdorf, *Annalen der Physik*, Ser. 4, Vol. 70, pp. 135-138 (1923).

5

CORONA MOTORS AND MOTORS SIMILAR TO THEM

In 1867, W. Holtz, the inventor of the electrostatic "influence" machine (generator) carrying his name, discovered that this machine could function as a motor when powered by another similar machine.[1] In order to study this effect in some detail, the famous German physicist J. C. Poggendorff ordered the construction of a special device, analogous to Holtz's machine, but designed to operate only as a motor and provided with numerous adjustable components so as to operate under a wide range of conditions.[2]

The basic part of this motor was a vertical glass-disk rotor placed between two ebonite crosses carrying metallic sharp-needle "combs" (Fig. 28 and Plate 4). The sharp points of the combs almost touched the surface of the disk, so that the disk could be charged by means of a corona discharge from the combs when they were connected in alternation to an electrostatic generator. Each comb could be oriented so as to make an arbitrary angle with respect to a radial direction.

Just like the sparks in Franklin's motors, the corona discharge from a comb deposited on the rotor a charge of the same polarity as that of the comb. Each comb repelled therefore the segment of the rotor carrying charges which it sprayed onto the rotor and attracted the segment carrying charges sprayed onto the rotor by the preceding comb. Because of a continuous discharge between the combs and the rotor, almost the entire surface of the rotor was sprayed with electric charges. The repulsion and attraction between the combs and the rotor, were therefore not only much stronger than in Franklin's motors, (where only the electrodes were charged) but were also much steadier, since the distances between the combs and the charges on the rotor were always the same. As a result, the torque and power obtainable with this motor were far greater than those obtainable with Franklin's motors of similar dimensions.

Poggendorff made a thorough study of his motor, varying all its important parameters (his article comprises 32 pages). He used several rotors of different thickness and surface characteristics, whose weight ranged from 2.5 to 4.5 pounds (all rotors were 15 inches in diameter). He varied the number, the orientation, and the polarity of the combs.



FIGURE 28

Poggendorff's corona motor had a glass-disk rotor placed between two ebonite crosses carrying metallic sharp-needle "combs".

He found that a motor with combs arranged along the radii of the rotor could rotate equally well in either direction but was not self-starting, since such combs sprayed charges onto the rotor in a perfectly symmetric fashion. However, if the combs were slanted relative to the radii, the motor became self-starting and unidirectional, because such combs sprayed charges predominantly in one direction. He also fould that the performance of the motor could be improved by placing pieces of glass, cardboard, or metal close to the surface of the rotor (this is the principle of the modern "backing plate" or "lining"; see Chapter 10). When properly adjusted, the motor could run at better than 300 rpm.

Poggendorff had fully appreciated the superiority of his motor in comparison fo Franklin's motors, and had stated so at the end of his article. In fact, he had indicated that his motor used from 1200 to 1800 times as much current as Franklin's motors, in which case, assuming that the operating voltage of his motor was the same as that of Franklin's motors (approximately 100 kilovolts), the power of his motor must have been close to 100 watts.

At the time when Poggendorff's article was written, however, it was considered unscientific to expect that electricity (*any* electricity) could ever become a significant source of motive power. This may be the reason why Poggendorff, speaking of the rotation phenomenon that he investigated, declared at the end of his article: "...it would be a sanguine hope if one wanted to believe that any useful mechanical effect could be achieved with it. That this is not possible, follows already from the consideration of how small is the quantity of electricity that is here put into play in comparison to that developed by a voltaic battery, with which one nevertheless, even with the help of the magnetismus produced by it, has so far achieved nothing substantial ("Erkleckliches")". The argument was obviously weak, but taking into account Poggendorff's reputation as an eminent scientist, it was probably sufficient to discourage further serious investigations of the corona-induced rotation for many years to come.

Since Poggendorff's motor depended on a corona discharge for its operation, the motor may be classified as a "corona motor".

Holtz's rotation phenomenon was also studied by the Danish physicist C. Christiansen (whose interest in the phenomenon had been aroused by a preliminary report of Poggendorff's investigations published in 1867).[3] Christiansen described two motors based on Holtz's discovery. His first motor consisted of a horizontal disk rotor and two stationary corona-producing combs. His second motor was similar to the first except that in it the glass disk was stationary and the combs constituted the rotor. The rotor combs in this second motor were located below the glass disk and were charged by means of two foil strips hanging from them and sliding along



FIGURE 29

This self-starting corona motor with a cylindrical rotor was described in 1871 under the name of "electric tourbillion".



FIGURE 30

In this hand-held corona motor (attributed to Ruhmkorff) the horizontal wire, by a corona discharge, extracted charges from the power source, and the vertical needle connected to this wire, also by a corona discharge, sprayed these charges onto the rotor.

two horizontal concentric contact rings mounted on the base of the motor.

Cylindrical and spherical motors operating on the same principle as Poggendorff's motor were described in 1871 by W. Gruel (Fig. 29), who called them the "electric tourbillions".[4] Gruel pointed out that these motors could be made self-starting and unidirectional by inclining the combs in the same rotational direction with respect to the surface of the rotor. He also suggested that by providing the rotors with a series of holes, the motors could be used as sirens.

A disk motor not noticeably different from Poggendorff's motor was patented in the U.S.A. in 1891 by J. W. Davis and J. B. Farrington.[5]

An interesting hand-held corona motor (attributed to Ruhmkorff) was described in 1876 by M. E. Mascart.[6] The motor had a horizontal mica disk rotor (Fig. 30) supported on a vertical needle by a jewel bearing, such as are used for supporting compass needles. Below the disk there were two vertical corona-producing needles mounted on a hard rubber base. One of the latter needles was connected to a metal handle, the other was connected to a long, stiff, horizontal wire terminating in a sharp point. To set the motor in motion, the operator held the motor so that the sharp point of the horizontal wire was in the proximity of a charged conductor. By a corona discharge, the horizontal wire then extracted charges from the conductor, and the ver-



FIGURE 31

This motor had two insulated corona-producing points tangential to the rotor disk and oriented in the same rotational direction.



FIGURE 32

This corona motor with a compound glass rotor could run at about 2000 rpm and had a power of about 90 watts.

tical needle connected to this wire, also by a corona discharge, sprayed these charges onto the rotor. The second vertical needle discharged the rotor and conducted its charges to the ground through the hand and body of the operator.

A number of experiments with Poggendorff type corona motors were reported in 1921 by V. E. Johnson.[7] One of his motors was similar to Ruhmkorff's motor (Fig. 31). This was a horizontal mica disk, about 6 inches in diameter, supported on a vertical needle point. At the edge of the disk there were two insulated corona-producing points tangential to the disk and oriented in the same rotational direction. Another of Johnson's motors was a big machine consisting of two stationary glass disks and a three-piece glass rotor that could rotate on ball bearings between the stationary disks. The rotor was made of two large glass disks separated by a smaller disk so as to have a deep slot along its edge. Two flat sharp-point combs were inserted diametrically opposite to one another into the slot of the rotor (Fig. 32). Johnson estimated that his motor could run at about 2000 rpm and had a power of about 90 watts.

Just as Poggendorff's motor was derived from Holtz's electrostatic machine, a series of electrostatic motors were similarly derived from Wimshurst's electrostatic machine.

In 1891 five such motors were constructed by William McVay of New York City.[8] McVay's first motor (Fig. 33) consisted of two horizontal glass disks, about 12 inches in diameter, one stationary and the other rotating on the vertical axis just above the first. The lower disk had two quadrants of tinfoil, and the upper disk had 16 tinfoil sectors, as shown in the figure. The power (from a Wimshurst machine) was delivered to the motor by means of two insulated arms, each of which terminated in two brushes, one touching continually one of the lower quadrants, the other charging a sector on the upper disk just clear of the edge of the quadrant. Charges of the same polarity were thus deposited on the quadrant and on the sector, causing them to repel each other. An "equalizer" reduced the charge of the sectors before they passed over the further edge of an oppositely charged quadrant, thus reducing the back torque on the rotating disk. An important new feature of this motor was the simultaneous charging of the stationary quadrants and of the moving sectors, which assured a relatively strong starting torque and, together with the neutralizing system, assured a reliable unidirectional operation. McVay also constructed motors of cylindrical geometry, one of which is shown in Fig. 34. In this motor the quadrants were located on the inner cylinder, while the charging and neutralizing brushes were on the neck of the outside cylinder.

McVay's first motor was later modified for charging by combs, rather than by brushes (Fig. 35). The motor then operated essentially as



FIGURE 33

McVay's first motor consisted of two horizontal glass disks, about 12 inches in diameter, one stationary and the other rotating on the vertical axis just above the first.



FIGURE 34

In this McVay's motor the quadrants were located on the inner cylinder (shown as two segments), while the charging and neutralizing brushes were on the neck of the outside cylinder.



FIGURE 35

McVay's first motor was later modified for charging by combs, rather than by brushes. The motor then operated essentially as Poggendorff's corona motor, retaining, however, its self-starting and unidirectional qualities.

Poggendorff's corona motor, retaining, however, its self-starting and unidirectional qualities.

Instructions for building a Poggendorff motor may be found in the May 1971 issue of Popular Science.[9] Instructions for building a simple McVay motor may be found in the January 1914 issue of Electrical Experimenter[10] (the author is grateful to Mr. Thorn L. Mayes for this information).

Since a corona discharge in air at atmospheric pressure requires a minimum voltage of about 3000 volts, ordinary corona motors can operate only from sources capable of supplying a voltage of this magnitude. Such voltages are, of course, easily attainable at the present time, and since the corona motors are very simple and efficient devices, they have been further developed and studied in recent years. We shall return to them in the last chapter of this book.

REFERENCES

1. W. Holtz, *Annalen der Physik*, Ser. 2, Vol. 130, pp. 168-171 (1867).
2. J. C. Poggendorff, *Annalen der Physik*, Ser. 2, Vol. 139, pp. 513-546 (1870).
3. C. Christiansen, *Annalen der Physik*, Ser. 2 Vol. 137, p. 490 (1869).
4. "Elektrischer Tourbillion", *Annalen der Physik*, Ser. 2 Vol. 144, p. 644 (1871).
5. U. S. Patent No. 459678.

6. M. E. Mascart, *Traité d'Electricité Statique*, G. Masson, Paris, 1876, Vol. 1 pp. 179, 180.
7. V. E. Johnson, *Modern High Speed Influence Machines*, E. and F. N. Spon, London, 1921, pp. 175-205.
8. "A Group of Static Motors", *Electrical World*, Vol. 18, p. 418 (1891).
9. C. P. Gilmore and W. J. Hawkins, *Popular Science Monthly*, Vol. 198, pp. 95-97 and 114 (May 1971).
10. "A Static Electric Motor", *Electrical Experimenter*, January 1914, p. 137.

6

CAPACITOR MOTORS

In 1889, Karl Zipernowsky, a Hungarian engineer (co-inventor of practical electrical transformers), constructed a new type of electrostatic motor,[1] which was derived from Thomson's quadrant electrometer.[2] The rotor of this motor (Fig. 36) consisted of two pairs of aluminum sectors insulated from each other and from the rest of the apparatus. The stator consisted of four double (hollow) sectors of brass enclosing the rotor. The rotor was fitted with a commutator in four parts, by means of which the sectors of the rotor were charged oppositely to those sectors of the stator into which they were entering and identically to those sectors of the stator which they were leaving. An interesting property of this motor was that it could operate from high-voltage dc as well as from high-voltage ac sources.



FIGURE 36

This motor was built in 1889 by Karl Zipernowsky, a Hungarian engineer. It operated from dc as well as from ac sources.



FIGURE 37

This capacitor motor was described in 1904 by van Huffel. Its rotor could be charged by contact or by sparks.

Inasmuch as Zipernowsky's motor operated as a result of the electric forces exerted by one charged conducting plate upon a second charged conducting plate (which are the same forces that act upon the two plates of a capacitor) it constituted what is now called an electrostatic "capacitor motor".

A simpler version of a capacitor motor was described in 1904 by van Huffel.[3] This motor was based on the so-called Thomson's replenisher.[4] The motor had an essentially cylindrical geometry (Fig. 37) and consisted of a rotor with two insulated bent brass plates mounted on a vertical axle and located between two similar, but slightly larger, plates of the stator. The rotor plates (which were not quite coaxial) were charged by means of two metallic tongues connected to the stator plates; the tongues touched the rotor plates just as the latter began to clear the stator plates. The charging of the rotor plates could occur by a direct contact as well as through a spark, depending on the adjustment of the tongues.

Since capacitor motors do not require sparks or a corona discharge for their operation, they can operate, at least in principle, from as low a voltage as one desires to use. This is one of their important advantages and is one of the reasons that such motors have been given considerable attention in recent years. Furthermore, as already indicated, capacitor motors can operate not only from dc sources, but also from ac sources. Finally, when powered by an ac source, they can operate both as synchronous and asynchronous motors (Zipernowsky's original motor operated from ac as an asynchronous motor).

A synchronous capacitor-type electrostatic motor is merely a multi-electrode capacitor motor without a commutator, the proper charging of the rotor being accomplished by continuously supplying an ac voltage of proper frequency between the stator and the rotor (Fig. 38). It is easy to see that if the rotor moves by one electrode in one period of the supply voltage, then the ac voltage accomplishes the same effect as that accomplished by a dc voltage with a commutator. The synchronous velocity is therefore $2\pi f/N$, where f is the frequency of the supply voltage and N is the number of the electrodes.

Several precision-made synchronous motors were described in 1969 by B. Bollée.[5] One of these motors ran on sapphire bearings and had a cylindrical aluminum rotor 1 centimeter long and 0.45 centimeters in diameter; the rotor and the stator had 60 electrodes each, with a 0.001 centimeter gap between stator and rotor electrodes. The maximum power of this motor was about 100 microwatts at 220 volts and 50 hertz. Another motor (for an electric clock) had a dielectric disk rotor, with four rows of 100 electrodes on each side, located between two bearing covers, each with five rows of 100 elec-



FIGURE 38

In a synchronous capacitor-type electrostatic motor the proper charging of the rotor is accomplished by continuously supplying an ac voltage of proper frequency between the stator and the rotor.



FIGURE 39

This synchronous electrostatic motor is essentially a variable capacitor with a rotatable shaft. The design of this motor is similar to the design of an electrostatic variable-capacitance generator.

trodes; the gap width in the axial direction was 0.01 centimeter. At 200 volts this motor had a maximum output of 600 microwatts. An interesting feature of this motor was that it had no slip ring on the rotor shaft, and that the rotor was therefore not connected to the power source. Instead, the stator was divided into two mutually insulated halves. This arrangement reduced the friction of the rotor and improved the performance of the motor. Still another motor was essentially a variable capacitor with a rotatable shaft. It had 15 plates in the stator and 14 in the rotor, each 0.03 centimeters thick; the gaps between stator and rotor plates were 0.015 centimeters (Fig. 39). The design of this motor is similar to the design of the electrostatic variable-capacitance generator described by N. J. Felici.[6]

According to Bollée, the maximum average torque on the rotor in a capacitor-type electrostatic motor is $T_{\max} = kNV^2$, where k is a geometrical constant, and V is the peak voltage applied. A motor with many electrodes is therefore slow but produces greater torque. The power of the motor is proportional to the square of the applied voltage and to the frequency but does not depend on the number of electrodes.

An important parameter in capacitor-type electrostatic motors is the capacitance difference $C_{\max} - C_{\min}$, where $C_{\max}$ is the greatest capacitance between the rotor and the stator and $C_{\min}$ is the smallest capacitance as they oc-



FIGURE 40

This interesting motor has been described by Moore, who calls it the "Interdigital Motor". The stator consists of a glass bowl with strips of aluminum foil glued to it. The rotor is a single conducting ball inside the bowl.

cur when the rotor turns. The larger this parameter is, the better are both the torque and the power. The main objective in the design of such motors is therefore to obtain the greatest possible variation of the capacitance.

An interesting motor which can be classified either as a modified Franklin's second motor or as a modified capacitor-type motor has been described by Moore,[7] who calls it the Interdigital Motor. The stator consists of a glass bowl with strips of aluminum foil glued to it (Fig. 40). The rotor is a single conducting ball inside the bowl; the ball runs along the sloping side when the strips are connected to an electrostatic generator (positive and negative strips are connected in alternation). Several balls can be placed into the bowl at the same time, and all of them will then run.

REFERENCES

1. "Zipernowsky Electrostatic Motor", *Electrical World*, Vol. 14, p. 260 (1889).
2. W. Thomson, *British Association Report*, 1855 (2), p. 22.
3. N. G. van Huffel, *Zeitschrift für den Physikalischen und Chemischen Unterricht*, Vol. 17, pp. 316-317 (1904).
4. W. Thomson, *British Association Report*, 1867, pp. 489-513.
5. B. Bollée, *Philips Technical Review*, Vol. 30, pp. 178-194 (1969).

6. N. J. Felici, *Electronics and Power*, Vol. 11, pp. 169-171 (1965).
7. A. D. Moore, *Electrostatics*, Doubleday and Company, Inc., New York, 1968, p. 109.

7

INDUCTION MOTORS

In 1892-1893, electrostatic motors of a fundametally new kind were described by Riccardo Arno[1,2] and by W. Weiler.[3] Their motors operated on the principle that the polarization of a dielectric in a variable electric field lags behind the field inducing the polarization. Therefore if a dielectric body is placed into a rotating electric field, the polarization charges* induced on the body will experience a force causing the body to follow the rotation of the field.

Arno's motor (Fig. 41) had a cylindrical stator formed by four insulated copper segments enclosing the space in which the rotating field was to be produced. The rotor was a hollow closed ebonite cylinder supported on two steel points turning in holes in glass; the cylinder weighed 40.33 grams, was 18 centimeters long and 8 centimeters in diameter. The rotating field was produced by means of a high-voltage transformer (3800 volts output), an RC-circuit, and a mercury commutator. The rotor attained a speed of about 250 rpm and developed a torque of 176 $\text{centimeter}^2 \times \text{gram} \times \text{second}^{-2}$.

---

*See, for example, O. Jefimenko "Electricity and Magnetism", Appleton-Century-Crofts, Inc. (1966), pp. 245-249.

Weiler used a hand-operated double commutator for his motors. The commutator delivered high voltage from an electrostatic generator in sequence to the four segments of a stator, thus producing the needed rotating electric field. Weiler described four different motors utilizing rotating fields. One of his motors was similar to Arno's motor. The operation of this motor (and that of Arno's motor) can be explained with the aid of Fig. 42, representing the top view of the motor. When segment A of the stator is positive, and segment B is negative, the electric field of the stator induces in the dielectric rotor (assumed to be at rest) polarization charges as shown in the figure. After the commutator has completed ¼ revolution, segment C is positive and segment D is negative. Thus the field has rotated by 90°, and now it polarizes the rotor in a new direction (at 90° with respect to the first). However, since it takes a certain time for the polarization charges to relax to zero, some of the initial polarization charges are still on the rotor, so that the distribution of the polarization charges on the rotor is not symmetrical relative



FIGURE 41

Arno's induction motor operated on the principle that the polarization of a dielectric in a variable electric field lags behind the field.



FIGURE 42

The operation of Arno's and Weiler's induction motors can be explained with the aid of this diagram.

to the charges on the stator. The rotor experiences therefore a torque due to attraction and repulsion between the rotor charges and stator charges, and the rotor turns.

Weiler also experimented with motors having noncylindrical rotors. One such motor is shown in Fig. 43. Rotating field electrostatic motors with disk-shaped rotors were built and studied between 1894 and 1901 in Japan by Hiderato Ho.[4]

Since Arno's and Weilers motors depend for their operation on induced polarization charges, they may be called "induction motors".

Induction motors, too, have a number of appealing features which attracted considerable interest to such motors in recent years: the motors can operate from both dc and ac; the motors can operate from low-voltage sources; since the motors require no brushes or slip rings, friction losses in these motors are very small.

Several carefully designed induction motors (both cylindrical and flat) were described in 1969 by Bollée.[5] One such motor of cylindrical geometry operated from a three-phase power supply at 220 volts and 50 hertz. The stator had 12 electrodes, which surrounded a rotor 15 centimeters in diameter. A disk-type induction motor operating from a three-phase power supply had a rotor consisting of 10 glass disks, each 6 centimeters in diameter, coated with a thin layer of slightly conductive material and mounted on a common axle. The rotor turned inside a ring



FIGURE 43

In 1892-1893, Weiler also experimented with induction motors having noncylindrical rotors, such as the motor shown in this drawing. Induction motors have a number of appealing features which attracted considerable interest to such motors in recent years.

formed by 60 comb-shaped stator electrodes. The maximum torque was 2000 centimeter^2 × gram × second $^{-2}$ at 220 volts and 50 hertz.

Another interesting motor described by Bollée was a linear induction motor, which "may be regarded as a segment of rotating-field motor bent straight".[5]

An extensive mathematical analysis of the induction motors was published in 1970 by Soon Dal Choi and D. A. Dunn.[6] They tested their theoretical results on a cylindrical motor with 72 electrodes. The motor was 14 inches wide, 14 inches high, and 19¼ inches long. It had a Plexiglas rotor that turned at a maximum rate of about 1000 rpm when powered by a 10-kilovolt source.

REFERENCES

1. R. Arno, *Rediconti della Atti Reale Accademia dei Lincei*, Vol. 1 (2), p. 284 (1892).
2. R. Arno, *The Electrician*, Vol. 29, pp. 516-518 (1892).
3. W. Weiler, *Zeitschrift für den Physikalischen und Chemischen Unterricht*, Vol. 7, pp. 1-4 (1893).
4. "A Rotary Field Electrostatic Induction Motor", *Electrical World*, Vol. 37, pp. 1012-1014 (1901).
5. B. Bollée, *Philips Technical Review*, Vol. 30, pp. 178-194 (1969).
6. S. D. Choi and D. A. Dunn, *Proceedings of the IDEE*, Vol. 59, pp. 737-738 (1971).

8

LIQUID-IMMERSED MOTORS

In 1893, W. Weiler discovered that a glass cylinder placed in a poorly conducting liquid between two spherical electrodes began to rotate when the electrodes were connected to an electrostatic generator.[1] He then constructed a small motor based on this discovery (Fig. 44). The principle of the operation of this motor was essentially the same as that of a cylindrical corona motor, except that the charges were now deposited on the rotor not by a corona discharge, but by the conduction current in the liquid.

In 1896, G. Quincke reported the same phenomenon and published a very comprehensive experimental study of it.[2] His device is shown in a simplified form in Fig. 45. It is interesting to note that Quincke, rather than Weiler, has been credited by subsequent investigators with the discovery of the rotation of dielectric bodies in



FIGURE 44

In 1893, W. Weiler discovered that a glass cylinder placed in poorly conducting liquid between two spherical electrodes began to rotate when the electrodes were connected to an electrostatic generator.



FIGURE 45

In 1896, G. Quincke reported the same phenomenon of rotation and published a very comprehensive experimental study of it. His liquid-immersed motor is shown in a simplified form in the above drawing.

poorly conducting liquids.

Weiler-type liquid-immersed dielectric motors were recently studied in considerable detail by P. E. Secker and his co-workers.[3,4] Their motors operated in various semi-insulating liquids such as hexane, hexane doped with amyl alcohol or ethyl alcohol, and isoamyl alcohol.

In one of their motors the electrodes were stainless steel squares 1.8 centimeters on a side. Their separation was varied from 1 to 2.5 centimeters. The rotor, of ebonite or Perspex, was 0.95 centimeters in diameter and 2.2 centimeters long. The operating voltage was from 3 to 30 kilovolts. The speed of the motor was found to be a linear function of the applied voltage, with the maximum recorded speed of about 2500 rpm.

In another motor, a stator with six electrodes was used (Fig. 46). The rotor was made of Perspex and was 7/8 inches in diameter and 2 inches long; it had a layer of high-permittivity material on its surface (titanium ceramic in polystyrene). Powered by a 30-kilovolt source, the motor turned at 1700 rpm, and the total power input amounted to 5.4 watts, of which 2.7 watts appeared at the rotor shaft.

A discussion of electrohydrodynamic effects that may take place during an operation of liquid-immersed motors has been presented by J. R. Melcher and G. I. Taylor.[5]

Because of considerable hydrodynamical losses, the motors of this type will apparently always have a relatively low output torque.



FIGURE 46

This liquid-immersed dielectric motor was recently studied in considerable detail by P. E. Secker and his co-workers.

REFERENCES

1. W. Weiler, *Zeitschrift für den Physikalischen und Chemischen Unterricht*, Vol. 6, pp. 194-195 (1893).
2. G. Quincke, *Annalen der Physik*, Ser. 3, Vol. 59, pp. 417-486 (1896).
3. P. E. Secker and I. N. Scialom, *Journal of Applied Physics*, Vol. 39, pp. 2957-2961 (1968).
4. P. E. Secker and M. R. Belmont, *Journal of Physics D: Applied Physics*, Vol. 3, pp. 216-220 (1970).
5. J. R. Melcher and G. I. Taylor, *Annual Review of Fluid Mechanics*, Vol. 1, pp. 111-146 (1969).

9

ELECTRET MOTORS

In general, an electret is a permanently charged dielectric body. In a more restricted sense of the word, an electret is a permanently polarized dielectric body and may be considered to constitute the electrical counterpart of a permanent magnet. It is this latter type of electret that has been used for constructing electrostatic motors.

In 1961, the Russian physicist A. N. Gubkin described an electret motor[1] shown schematically in Fig. 47. The motor consisted of a stator formed by two horizontal, axially symmetric, parallel-plate capacitors and a rotor formed by two flat, axially symmetric, oppositely polarized electrets mounted on a vertical axle and capable of passing between the plates of the capacitors. The motor operated as follows. When a voltage was applied to the two capacitors, so that



FIGURE 47

In 1961, the Russian physicist A. N. Gubkin described this motor with two electrets in the rotor and two parallel-plate capacitors in the stator. A commutator was used to change the polarity of the capacitors.

plates A and D were positive and plates B and C were negative, the capacitors attracted the electrets as soon as the latter came close to the plates, and the electrets were pulled into the capacitors. A commutator changed the polarity of the plates just as the electrets were coming out from the capacitors, and the electrets were then repelled from them, and so on. Thus the rotor was set in a continuous rotation.

A well-known property of electrets is that they lose their polarization in the absence of adequate shielding. Electret motors with almost perfect shielding were described by this author and by D. K. Walker in 1970.[2] These motors were based on the so-called "electret slot effect".[3] The slot effect works as follows (Fig. 48). An electret is placed between two pairs of electrodes, each pair forming a slot. If a voltage is applied to one or both electrode pairs, the electret (or the electrodes) experiences a force in a direction perpendicular to the slot and parallel to the plates. This arrangement insures both a nearly perfect shielding and a relatively large force.

A simple electret motor utilizing the slot effect is shown in Fig. 49 and Plate 5.* It uses a disk-shaped carnauba wax electret rotor consisting of two oppositely polarized half-disks. The stator has two pairs of electrodes connected to a

---

*The motor was designed by the author and built by one of his students, Charles Lynn Walls, in 1966.



FIGURE 48

The slot effect works as follows. An electret is placed between two pairs of electrodes, each pair forming a slot. If a voltage is applied to one or both electrode pairs, the electret experiences a force in a direction perpendicular to the slot and parallel to the plates.



FIGURE 49

This simple electret motor utilizes the slot effect. The rotor is made of a disk-shaped electret consisting of two oppositely polarized half-disks. The stator has two pairs of slotted electrodes connected to a cylindrical commutator, which is charged by contact or by sparks.

cylindrical commutator. The thickness of the rotor is ½ inch, the diameter is 5 inches. The motor operates from an 8-kilovolt power supply and rotates at 1500 rpm.

Similar motors with stationary electrets and rotating electrodes are shown in Plates 6 and 7.

A more sophisticated slot-effect motor[2] uses a cylindrical electret (Fig. 50 and Plate 8). The electret is stationary; it is shaped as a hollow cylinder and has four sections of opposite radial polarization. The rotor is made of four internal and four external aluminum electrodes forming two cylinders with four slots in each. The inner electrodes are cross-connected with the outer ones, and all electrodes are supported by a Plexiglas disk mounted on a steel axle. This motor uses no commutator. The power is delivered to two adjacent external electrodes by means of two sharp points which charge the rotor through a corona discharge. The overall diameter of this motor is 3 inches, the operating voltage is 6 kilovolts, the speed is up to 5000 rpm, the power is about 20 milliwatts.

Synchronous electret motors for electric clocks have been recently announced by the General Time Corporation. The motors are about 1¼ inches in diameter and ¼ inch thick. In these motors (Fig. 51) a thin plastic electret disk with 15 active sectors and 15 equally large cut-outs is the rotor. The rotor is placed between two stator plates fabricated as printed circuit boards. Each stator plate has 30 elec-



FIGURE 50

This more advanced slot-effect motor uses a stationary cylindrical electret and works without a commutator. The rotor has 8 slots.



FIGURE 51

In this simplified version of a synchronous electret motor for electric clocks a thin plastic electret disk with several active sectors and several cut-outs is used as the rotor.

trodes connected in alternation to the two input terminals. The operation of this motor is similar to that of the first slot-effect motor described above (Fig. 49) except that the reversal of polarity of the electrodes is accomplished directly by the applied ac voltage rather than by a commutator.

Of all presently known types of electrostatic motors, electret motors are the newest and (together with corona motors) the most highly promising ones. We shall return to them once again in the next chapter.

REFERENCES

1. A. N. Gubkin, *Electrets*, Academy of Sciences, Moscow, 1961, pp. 130-133 (in Russian).
2. O. Jefimenko and D. K. Walker, *Conference on Dielectric Materials, Measurements and Applications*, The Institution of Electrical Engineers, London, 1970, pp. 146-149.
3. O. Jefimenko, *Proceedings of the West Virginia Academy of Sciences*, Vol. 40, pp. 345-348 (1968).

10

WHAT TO EXPECT FROM ELECTROSTATIC MOTORS

Having described the various types of electrostatic motors we shall now present a brief discussion of the current aims in the electrostatic motor research and a brief discussion of the most probable future uses and applications of these motors.

It has been pointed out by Bollée[1] that electromagnetic motors rapidly lose their efficiency in scaled-down versions (which is due to the relative increase in energy dissipation in the magnet coils) and that very small capacitor-type and induction-type electrostatic motors may be a better choice for miniaturized systems. Therefore one may expect that miniature electrostatic motors of these types will find applications in various sensor and control devices where only very small torques and power are needed.

Experiments with electret motors conducted in the author's laboratory[2] indicate that these motors may be very useful in systems where powers of up to 1 watt are needed.

The most promising electrostatic motors appear to be, however, the corona motors. These motors possess a number of highly desirable features. Here are some of them: the motors are extremely simple in design; they require no expensive materials; their maintenance is very simple; having only few metal parts they possess a very good power-to-weight ratio; they are fully capable of developing appreciable amounts of power; and they can attain very high speeds.

Our present-day awareness of the many attractive properties of corona motors is to a great extent due to the work of the Russian engineers Yu. Karpov, V. Krasnoperov, and Yu. Okunev published in 1958 and 1960.[3,4] They described a 6-watt cylindrical corona motor of improved design (Fig. 52) operating from a 7-kilovolt power supply and turning at a rate of 6000 rpm. This motor had a hollow Plexiglas rotor 10.5 centimeters in diameter and 17 centimeters long with a conducting lining on its inner surface. The stator supported 16 knife-like electrodes inclined relative to the surface of the rotor in the direction of the desired rotation. The lining of the rotor served to increase the electric field in the gap between the electrodes and the surface of the rotor and thus to enhance the corona discharge from the electrodes.

A high-speed corona motor with a disk rotor



FIGURE 52

In 1958, the Russian engineers Yu. Karpov, V. Krasnoperov, and Yu. Okunev described a 6-watt cylindrical corona motor of an improved design operating from a 7-kilovolt power supply and turning at a rate of 6000 rpm. This motor had a Plexiglas rotor.



FIGURE 53

This corona motor with a disk rotor and circumferential electrodes was described by J. D. N. Van Wyck and G. J. Kühn of South Africa in 1961. It had a rotor 1.5 inches in diameter turning in jewel bearings. Operating from 13 kilovolts, the motor ran at 12000 rpm.



FIGURE 54

The performance of a corona motor depends on the shape and arrangement of electrodes and the structure of the rotor. The curved electrodes of this motor produce an especially large torque. The lining of the rotor increases the power.



FIGURE 55

The mechanism of electric interaction producing rotational motion in corona motors can be used to achieve a translational motion as well. This drawing shows the principle of a linear corona motor with multiple electrodes.

and circumferential electrodes was described by J. D. N. Van Wyck and G. J. Kühn of South Africa in 1961.[5] The motor (Fig. 53) had a rotor 1.5 inches in diameter turning in jewel bearings. The stator supported 6 sharp-point electrodes. Operating from 8-13 kilovolts, the motor developed speeds of up to 12000 rpm.

A similar motor was studied in Poland by B. Sujak and W. Heffner in 1963.[6]

A number of advanced corona motors were studied in the author's laboratory;[7] an example of these motors is given in Fig. 54 and Plate 9. A diagram of a linear corona motor designed by the author is shown in Fig. 55. Instructions for building the corona motors of the author's design may be found in the May 1971 issue of Popular Science.[8]

It appears that corona motors with input power of 100 to 1000 watts and efficiency of at least 60% can be constructed without any difficulty. There seems to be no reason why even more powerful corona motors could not be built. It is likely that the motors can be further improved by using rotors immersed in a gas other than the air at atmospheric pressure.

Performance characteristics of corona motors strongly depend on the design and geometrical configuration of the electrodes spraying charges onto the rotor. Several typical electrode types and electrode configurations for corona motors are shown in Fig. 56. Especially interesting is the electrode arrangement shown in Fig. 56c.



FIGURE 56

(a) Slanted electrodes and disk rotor with a conducting lining in the middle; (b) Straight electrodes; (c) Foil electrodes shielded on one side; (d) Curved electrodes and cylindrical rotor with a conducting lining.

This arrangement is used in conjunction with thin disk-shaped rotors "sandwiched" between two insulating stator plates. An even number of windows is cut in each stator plate, and metal foil electrodes are glued to the walls of the holes, as shown by heavy lines in Fig. 56c. In this arrangement there is a dielectric medium on one side of each electrode, and there is air on the other side. Therefore the electrodes spray charges predominantly in the direction of the side facing the air. Thus a motor with electrodes of this type is unidirectional and self-starting. Furthermore, the entire "sandwich" comprising the rotor and the two stator plates may be very thin. Therefore many such "sandwiches" can be placed on a single axle thus forming a compound motor in which good use is made of the entire volume occupied by the motor. There are indications that compound motors of this type can develop up to 1000 horsepower for each cubic meter of their volume.

An important property of electrostatic motors is that they can operate from a much greater variety of sources than the electromagnetic motors. It is, of course, obvious that any sources used for operating conventional electromagnetic motors can be used to operate the electrostatic motors. However, the electrostatic motors can operate also from sources from which no other motors can operate. The reason for this is that the electrostatic motors are extra-high impedence devices and thus require extremely small currents for their operation.

One very interesting source of electricity for electrostatic motors is the ordinary capacitor. It is true that capacitors, as we know them now, do not store appreciable amounts of electric energy. However, if high-permittivity low-loss dielectric materials were developed, then the capacitor would become a very useful device for storage of electric energy, and possibly could be used in place of the chemical batteries for operating electrostatic motors.

Another possible source of power for electrostatic motors are high-impedance high-voltage batteries of the type of Zamboni pile.

A potentially very important source of electricity for powering electrostatic motors are electrostatic generators. Considerable advances in the development of such generators have been made in recent years[9,10] and it is conceivable that electrostatic motor-generators will be used to convert the high-voltage dc produced by such generators into the conventional low-voltage dc or ac.

Finally, a very interesting source for powering electrostatic motors is the atmospheric electric field. In fact, it appears possible to extract the energy contained in this field by means of electrostatic motors. Experiments on such an energy extraction have been conducted by the author.[11,12] In these experiments an electret motor and a corona motor were powered by simple earth-field antennas (Fig. 57; Plates 10 to



FIGURE 57

Small electrostatic motors can be powered from atmospheric electricity by means of simple earth-field antennas. Whether or not it will be possible to operate large motors in this manner will depend on how successful we are in designing antennas capable of extracting appreciable power from the earth electric field.

12). The corona motor was the one shown in Plate 9. The electret motor was similar to that shown in Fig. 49, but with the electret stationary and the electrodes rotating (Plate 6). These experiments indicate that it is entirely possible to operate small electrostatic motors from atmospheric electricity. Whether or not it will be possible to operate large motors in this manner will depend on how successful we will be in designing and building earth-field antennas capable of extracting appreciable power from the earth electric field.

In conclusion it may be useful to mention that a quantitative electrostatic motor research is now only in its very rudimentary stage. Almost all papers on electrostatic motors published thus far deal with the qualitative aspects of the performance of the various types of motors. Only very few papers deal with the optimization of design and with the quantitative aspects of the operation of the motors, likewise only very few papers present a theoretical analysis of the electrostatic motors. It is clear therefore that the electrostatic motors still constitute an essentially unexplored area of physics and engineering, and that the electrostatic motor research is presently one of the potentially most rewarding research fields in modern electrostatics.

REFERENCES

1. B. Bollée, *Philips Technical Review*, Vol. 30, pp. 178-194 (1969).

2. O. Jefimenko and D. K. Walker, *Conference on Dielectric Materials, Measurements and Applications*, the Institution of Electrical Engineers, London, 1970, pp. 146-149.
3. Yu. Karpov, V. Krasnoperov, and Yu. Okunev, *Tekhnika Molodezhi*, Vol. 26, pp. 36-37 (Sept. 1958) (in Russian).
4. Yu. Karpov, V. Krasnoperov, Yu. T. Okunev, and V. V. Pasynkov, "On the Motion of Dielectrics in an Electric Field", in *Dielectric Physics*, Academy of Sciences, Moscow, 1960, pp. 124-131 (in Russian).
5. J. D. N. Van Wyck and G. J. Kühn, *Nature*, Vol. 192, pp. 640-650 (1961).
6. B. Sujak and W. Heffner, *Acta Physica Polonica*, Vol. 23, pp. 715-726 (1963).
7. O. Jefimenko and H. Fischbach-Nazario, *Proceedings of the West Virginia Academy of Sciences*, Vol. 42, pp. 216-221 (1971).
8. C. P. Gilmore and W. J. Hawkins, *Popular Science Monthly*, Vol. 198, pp. 95-97, 114 (May 1971).
9. N. J. Felici, *Elektrostatische Hochspannungs Generatoren*, G. Braun, Karlsruhe, 1957.
10. J. Hughes and P. Secker, *New Scientist and Science Journal*, Vol. 49, pp. 468-470 (1971).
11. O. Jefimenko, *American Journal of Physics*, Vol. 39, pp. 776-778 (1971).
12. W. Aston, *West Virginia University Magazine*, Vol. 3, Number 4, Spring 1971, pp. 6-11.

INDEX

INDEX

Adams, G., 37
Aimé, R., 29,38
Arno, Q., 84,90
Arno Motor, 84,85,87
Aston, W., 118
Asynchronous motors, 4, 77
Atmospheric electricity, 3, 115-117
Avery, F. M., 21

Backing plate, 59, 107
Behrens, G., 14
Bell jar motor, 48, 49, 52
Belmont, M. R., 96
Benjamin, P., 21
Bichat, E., 29, 32, 38
Bollée, B., 77, 80, 82, 90, 106, 117
Bollée capacitor motors, 77, 79, 80
Bollée induction motors, 88, 90

Capacitor motors, 4, 73-77, 80, 82, 106
Chew, V. K., 37
Choi, S. D., 90
Christenson, A., 38
Christiansen, C., 60, 71
Christiansen motor, 60
Classification of electrostatic motors, 4
Collinson, P., 39
Contact motors, 4, 6, 20
Corona discharge, 22, 56, 71
Corona-kraft levitation, 33
Corona motors, 4, 56, 58, 60-66, 68-71, 107-112, 115, 116

Dailey, H. B. and E. M., 15, 21
Dailey motor, 15-18
Davis, J. W., 63
Draper, J. W., 55
Dressel, R. H., 51, 55
Dunn, D. A., 90

Earth-field antennas, 115, 116, 117
Electret, 97, 99
Electret motors, 4, 97-104, 106, 114, 115
Electret slot effect, 99, 100
Electric bells, 6, 8-11, 23, 25
Electric chimes, 11, 14, 23, 25
Electric fly, 22-26, 29-31
Electric horse-race, 26, 28, 29

Electric motor, 1, 6, 39
Electric orrery, 26, 27
Electric pendulum, 6
Electric pendulum motors, 6, 15, 16
Electric perpetuum mobile, 3, 15, 16, 48, 50
Electric pinwheel, 22
Electric planetarium, 18, 19
Electric rabbit hunt, 33, 36
Electric racing ball, 18, 19
Electric reaction wheel, 22
Electric seesaw, 13, 14
Electric swing, 12, 14
Electric tellurium, 26, 27
Electric tourbillion, 61, 63, 71
Electric tourniquet, 29, 32
Electric toys, 12, 13, 14, 28, 29, 33, 36
Electric wheels, 37, 39
Electric whirl, 22
Electric wind, 23
Electric wind motors, 22 ff, 33-35
Electric wind turbines, 33, 35
Electric wind wheels, 33, 34
Electromagnetic motors, 1-3, 106, 114
Electrophorus, 52
Electrostatic forces, 1
Electrostatic generators, 80, 115
Electrostatic motors, 1-4, 106, 107, 114-117

Farrington, J. B., 63
Felici, N. J., 80, 83, 118
Franklin, Benjamin, 7, 33, 37, 39, 42, 43
Franklin bells, 7, 14
Franklin first motor, 39-45, 48, 52
Franklin motors, 39-45, 54, 57, 59
Franklin second motor, 41, 43-45, 82

Gale, L. D., 33, 38
Gilmore, C. P., 72, 118
Gordon, A., 6, 22
Gordon bells, 6, 8, 15, 18, 20
Gruel, W., 63
Gruel motor, 61, 63
Gubkin, A. N., 97, 105
Gubkin motor, 97-99
Guyot, M., 20, 21, 29, 33, 38, 55

Hamilton, 23
Hamilton electrometer, 23
Hawkins, W. J., 72, 118
Heffner, W., 112, 118
Ho, H., 88
Holtz, W., 56, 71
Holtz rotation phenomenon, 56, 59, 60
Van Huffel, N. G., 76, 82
Van Huffel motor, 75, 76
Hughes, J., 118

Induction motors, 4, 84-90, 106
Interdigital motor, 81, 82

Jamin, M. J., 55
Jefimenko, O., 54, 84, 105, 117, 118
Johnson, R., 66
Johnson motors, 64, 65, 66

Kämpfer, D., 29, 38
Karpov, Yu., 107, 108, 118
King, W. R., 33
Kinnersley, E., 26
Krasnoperov, V., 107, 108, 118
Kühn, G. J. 110, 118

Langenbucher, J., 23, 29, 33, 37
Langenbucher electrometer, 23, 24
Levitation, electrostatic, 33
Leyden jar, 6, 42, 43
Linear corona motor, 111, 112
Linear induction motor, 90
Liquid-immersed motors, 4, 91-95
Loeb, L. B., 38

McVay, W., 66
McVay motors, 66-71
Magnetic forces, 1
Mascart, M. E., 29, 38, 63, 72
Mayes, T. L., 71
Melcher, J. R., 94, 96
Miller, D. C., 55
Millifleapower motor, 48, 51
Moller, S., 38
Moore, A. D., 45-47, 55, 81-83
Müller-Pouillet, 21

Neuburger, A., 21, 33, 38

Okunev, Yu., 107, 108, 118
Oosting, H. J., 38

Pendulum motors, 3, 6, 15, 16
Perpetuum mobile, electric, 3, 15, 16, 48, 50
Poggendorff, J. C., 37, 56, 59, 60, 71
Poggendorff motor, 56-60, 66, 71

Quincke, G., 91, 93, 96

Reciprocating motor, 15, 17, 18
Richmann, G. W., 7
Rotating field motors, 84-90
Ruhmkorff, 63
Ruhmkorff motor, 62, 63

Scialom, I. N., 96
Secker, P. E., 94, 96, 118
Secker motor, 94, 95
Sivowitch, E. N., 18
Slot effect, 99, 100
Slot-effect motors, 99-103
Spark motors, 4, 39-41, 46, 47, 49, 50, 53, 54
Sparks, J., 21, 38, 54
Sujak, B., 110, 118
Synchronous motors, 4, 77, 102
Syng, P., 33

Taylor, G. I., 94, 96
Thomson, W., 82
Thomson electrometer, 73
Thomson replenisher, 76
Tomlinson, C., 29, 38

Walker, D. K., 54, 99, 105
Weiler, W., 84, 90, 91, 96
Weiler induction motors, 87-89
Weiler liquid-immersed motor, 91, 92
Wilson, B., 37
Wimshurst, J., 33
Wommelsdorf, H., 55
Van Wyck, J. D. N., 110, 118

Zamboni, G., 14
Zamboni pile, 3, 14, 15, 48, 115
Zipernowsky, K., 73, 77
Zipernowsky motor, 73, 74, 82

This book was set in Century Textbook.
The format was designed by the author.
The drawings were done by
Dr. D. K. Walker from the author's sketches.
The printer and binder was
Morgantown Printing & Binding Company.

Picture Credits

Plate 1: courtesy Smithsonian Institution, Washington, D.C.
Plates 2 and 3: courtesy Electret Scientific Company, Star City, W. Va.
Plates 6, 9, 11, and 12: courtesy West Virginia University, Morgantown, W. Va.
Plates 4, 5, 7, 8, and 10: author's photographs.

US008253639B2

(12) **United States Patent**
Cohen

(10) **Patent No.: US 8,253,639 B2**
(45) **Date of Patent: Aug. 28, 2012**

(54) **WIDEBAND ELECTROMAGNETIC CLOAKING SYSTEMS**

(76) Inventor: **Nathan Cohen**, Belmont, MA (US)

(*) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 498 days.

(21) Appl. No.: **12/547,104**

(22) Filed: **Aug. 25, 2009**

(65) **Prior Publication Data**

US 2010/0156556 A1 Jun. 24, 2010

Related U.S. Application Data

(60) Provisional application No. 61/189,966, filed on Aug. 25, 2008.

(51) **Int. Cl.**
H01Q 15/02 (2006.01)
H01Q 19/06 (2006.01)

(52) **U.S. Cl.** **343/753**; 343/909

(58) **Field of Classification Search** 343/753, 343/909, 910; 333/135
See application file for complete search history.

(56) **References Cited**

U.S. PATENT DOCUMENTS

5,471,224	A *	11/1995	Barkeshli	343/909
5,714,961	A *	2/1998	Kot et al.	343/769
6,473,048	B1 *	10/2002	Diaz	343/753

* cited by examiner

Primary Examiner — Michael C Wimer
(74) *Attorney, Agent, or Firm* — McDermott Will & Emery LLP

(57) **ABSTRACT**

Arrangement of resonators in an aperiodic configurations are described, which can be used for electromagnetic cloaking of objects. The overall assembly of resonators, as structures, do not all repeat periodically and at least some of the resonators are spaced such that their phase centers are separated by more than a wavelength. The arrangements can include resonators of several different sizes and/or geometries arranged so that each size or geometry corresponds to a moderate or high "Q" response that resonates within a specific frequency range, and that arrangement within that specific grouping of akin elements is periodic in the overall structure. The relative spacing and arrangement of groupings can be defined by self similarity and origin symmetry.

14 Claims, 4 Drawing Sheets



FIG. 1


100
1
106
106
104
B1
B2
A1
B3
A2
A3
A4
102
106
106
2


200
1
2
OBJECT
B1
B2
B3
A1
A2
A3
202

FIG. 2

FIG. 3



FIG. 4



WIDEBAND ELECTROMAGNETIC CLOAKING SYSTEMS

RELATED APPLICATION

This application claims priority to U.S. Provisional Patent Application No. 61/189,966, filed 25 Aug. 2008 and entitled "Method and Apparatus for Wideband Electromagnetic Cloaking, Negative Refractive Index Lensing and Metamaterial Applications," the entire contents of which are incorporated herein by reference.

BACKGROUND

Much time and effort has been devoted to the quest for so-called invisibility machines. Beyond science fiction, however, there has been little if any real progress toward this goal.

Materials with negative permittivity and permeability leading to negative index of refraction were theorized by Russian noted physicist Victor Veselago in his seminal paper in *Soviet Physics* USPEKHI, 10, 509 (1968). Since that time, metamaterials have been developed that produce negative index of refraction, subject to various constraints. Such materials are artificially engineered micro/nanostructures that, at given frequencies, show negative permeability and permittivity. Metamaterials have been shown to produce narrow band, e.g., typically less than 5%, response such as bent-back lensing. Such metamaterials produce such a negative-index effect by utilizing a closely-spaced periodic lattice of resonators, such as split-ring resonators, that all resonate. Previous metamaterials provide a negative index of refraction when a sub-wavelength spacing is used for the resonators.

In the microwave regime, certain techniques have been developed to utilize radiation-absorbing materials or coatings to reduce the radar cross section of airborne missiles and vehicles. While such absorbing materials can provide an effective reduction in radar cross section, these results are largely limited to small ranges of electromagnetic radiation.

SUMMARY

Embodiments of the present disclosure can provide techniques, including systems and/or methods, for cloaking objects at certain wavelengths/frequencies or over certain wavelength/frequency ranges (bands). Such techniques can provide an effective electromagnetic lens and/or lensing effect for certain wavelengths/frequencies or over certain wavelength/frequency ranges (bands).

The effects produced by such techniques can include cloaking or so-called invisibility of the object(s) at the noted wavelengths or bands. Representative frequencies of operation can include, but are not limited to, those over a range of 500 MHz to 1.3 GHz, though others may of course be realized. Operation at other frequencies, including for example those of visible light, infrared, ultraviolet, and as well as microwave EM radiation, e.g., K, Ka, X-bands, etc. may be realized, e.g., by appropriate scaling of dimensions and selection of shape of the resonator elements.

Exemplary embodiments of the present disclosure can include a novel arrangement of resonators in an aperiodic configuration or lattice. The overall assembly of resonators, as structures, do not all repeat periodically and at least some of the resonators are spaced such that their phase centers are separated by more than a wavelength. The arrangements can include resonators of several different sizes and/or geometries arranged so that each size or geometry ("grouping") corresponds to a moderate or high "Q" (that is moderate or low bandwidth) response that resonates within a specific frequency range, and that arrangement within that specific grouping of akin elements is periodic in the overall structure—even though the structure as a whole is not an entirely periodic arrangement of resonators. The relative spacing and arrangement of groupings (at least one for each specific frequency range) can be defined by self similarity and origin symmetry, where the "origin" arises at the center of a structure (or part of the structure) individually designed to have the wideband metamaterial property.

For exemplary embodiments, fractal resonators can be used for the resonators in such structures because of their control of passbands, and smaller sizes compared to non-fractal based resonators. Their benefit arises from a size standpoint because they can be used to shrink the resonator (s), while control of passbands can reduce or eliminates issues of harmonic passbands that would resonate at frequencies not desired.

It should be understood that other embodiments of wideband electromagnetic resonator or cloaking systems and methods according to the present disclosure will become readily apparent to those skilled in the art from the following detailed description, wherein exemplary embodiments are shown and described by way of illustration. The systems and methods of the present disclosure are capable of other and different embodiments, and details of such are capable of modification in various other respects. Accordingly, the drawings and detailed description are to be regarded as illustrative in nature and not as restrictive.

BRIEF DESCRIPTION OF THE DRAWINGS

Aspects of the disclosure may be more fully understood from the following description when read together with the accompanying drawings, which are to be regarded as illustrative in nature, and not as limiting. The drawings are not necessarily to scale, emphasis instead being placed on the principles of the disclosure. In the drawings:

FIG. **1** depicts a diagrammatic plan view of a resonator cloaking system utilizing a number of cylindrical shells, in accordance with exemplary embodiments of the present disclosure;

FIG. **2** depicts a diagrammatic plan view of a resonator cloaking system utilizing a number of shells having an elliptical cross-section, in accordance with an alternate embodiment of the present disclosure;

FIG. **3** depicts an exemplary embodiment of a portion of shell that includes repeated conductive traces that are configured in a fractal-like shape; and

FIG. **4** depicts a perspective view (photograph) of an exemplary embodiment of the present disclosure.

While certain embodiments depicted in the drawings, one skilled in the art will appreciate that the embodiments depicted are illustrative and that variations of those shown, as well as other embodiments described herein, may be envisioned and practiced within the scope of the present disclosure.

DETAILED DESCRIPTION

The present disclosure is directed to novel arrangements of resonators useful for obscuring or hiding objects at given bands of electromagnetic radiation. Embodiments of the present disclosure can provide techniques, including systems and/or methods, for hiding or obscuring objects at certain wavelengths/frequencies or over certain wavelength/frequency ranges or bands. Such techniques can provide an effective electromagnetic lens and/or lensing effect for certain wavelengths/frequencies or over certain wavelength/frequency ranges or bands. The effects produced by such techniques can include cloaking or so-called invisibility of the object(s) at the noted wavelengths or bands.

Representative frequencies of operation can include, but are not limited to, those over a range of about 500 MHz to about 1.3 GHz, though others may of course be realized. Operation at other frequencies, including for example those of visible light, infrared, ultraviolet, and as well as microwave EM radiation, e.g., K, Ka, X-bands, etc. may be realized, e.g., by appropriate scaling of dimensions and selection of shape of the resonator elements.

Embodiments of the present disclosure include arrangement of resonators or resonant structures in aperiodic configurations or lattices. The overall assembly of resonator structures can include nested or concentric shells, that each include repeated patterns of resonant structures. The resonant structures can be configured as a close-packed arrangement of electrically conductive material. The resonant structures can be located on the surface of a circuit board.

The overall assemblies, as structures, do not all repeat periodically and at least some of the resonators are spaced such that their phase centers are separated by more than a wavelength. The arrangements can include resonators of several different sizes and/or geometries arranged so that each size or geometry ("grouping") corresponds to a moderate or high quality-factor "Q" response (that is, one allowing for a moderate or low bandwidth) that resonates within a specific frequency range, and that arrangement within that specific grouping of like elements is periodic in the overall structure—even though the structure as a whole is not an entirely periodic arrangement of resonators. The relative spacing and arrangement of groupings (at least one for each specific frequency range) can be defined by self similarity and origin symmetry, where the "origin" arises at the center of a structure (or part of the structure) individually designed to have the wideband metamaterial property.

For exemplary embodiments, fractal resonators can be used for the resonators because of their control of passbands, and smaller sizes. A main benefit of such resonators arises from a size standpoint because they can be used to shrink the resonator(s), while control of passbands can reduce/mitigate or eliminate issues of harmonic passbands that would resonate at frequencies not desired.

Exemplary embodiments of a resonator system for use at microwave (or nearby) frequencies can be built from belts of circuit boards festooned with resonators. These belts can function to slip the microwaves around an object located within the belts, so the object is effectively invisible and "see thru" at the microwave frequencies. Belts, or shells, having similar closed-packed arrangements for operation at a first passband can be positioned within a wavelength of one another, e.g., $\frac{1}{10}\lambda$, $\frac{1}{8}\lambda$, $\frac{1}{4}\lambda$, $\frac{1}{2}\lambda$, etc.

An observer can observe an original image or signal, without it being blocked by the cloaked object. Using no power, the fractal cloak can replicates the original signal (that is, the signal before blocking) with great fidelity. Exemplary embodiments can function over a bandwidth from about 500 MHz to approximately 1500 MHz (1.5 GHz), providing 3:1 bandwidth; operation within or near such can frequencies can provide other bandwidths as well, such as 1:1 up to 2:1 and up to about 3:1.

FIG. **1** depicts a diagrammatic plan view of a cloaking system **100** and RF testing set up in accordance with exemplary embodiments of the present disclosure. As shown in FIG. **1**, a number of concentric shells (or bands) **102** are placed on a platform (parallel to the plane of the drawing). The shells include a flexible substrate (e.g., polyimide with or without composite reinforcement) with conductive traces (e.g., copper, silver, etc.) in fractal shapes or outlines. The shells **102** surround an object to be cloaked (shown as **104** in FIG. **1**). A transmitting antenna **1** and a receiving antenna **2** are configured at different sides of the system **100**, for verifying efficacy of the cloaking system **100** and recording results. The shells **102** can be held in place by radial supports **106** (while only four are shown, **12** were used in the exemplary embodiment indicated).

The shells indicated in FIG. **1** are of two types, one set (A**1**-A**4**) configured for optimal operation over a first wavelength/frequency range, and another set (B**1**-B**3**) configured for optimal operation over a second wavelength/frequency range. (The numbering of the shells is of course arbitrary and can be reordered, e.g., reversed.)

For an exemplary embodiment of system **100**, the outer set of shells (A**1**-A**4**, with A**1** being the innermost and A**4** the outmost) had a height of about 3 to 4 inches (e.g., 3.5 inches) and the inner set of shells had a height of about 1 inch less (e.g., about 2.5 to 3 inches). The spacing between the shells with a larger fractal shape (A**1**-A**4**) was about 2.4 cm while the spacing between shells of smaller fractal generator shapes (B**1**-B**3**) was about 2.15 cm (along a radial direction). In a preferred embodiment, shell A**4** was placed between shell B**2** and B**3** as shown. The resonators formed on each shell by the fractal shapes can be configured so as to be closely coupled (e.g., by capacitive coupling) and can serve to propagate a plasmonic wave.

It will be appreciated that while, two types of shells and a given number of shells per set are indicated in FIG. **1**, the number of shell types and number of shells for each set can be selected as desired, and may be optimized for different applications, e.g., wavelength/frequency bands.

FIG. **2** depicts a diagrammatic plan view of a cloaking system (or electrical resonator system) according to an alternate embodiment in which the individual shells have an elliptical cross section. As shown in FIG. **2**, a system **200** for cloaking can include a number of concentric shells (or bands) **202**. These shells can be held in place with respect to one another by suitable fixing means, e.g., they can be placed on a platform (parallel to the plane of the drawing) and/or held with a frame. The shells **202** can include a flexible substrate (e.g., polyimide with or without composite reinforcement) with a close-packed arrangement of electrically conductive material formed on the first surface. As stated previously for FIG. **1**, the closed-packed arrangement can include a number of self-similar electrical resonator shapes. The resonator shapes can be made from conductive traces (e.g., copper, silver, gold, silver-based ink, etc.) having a desired shape, e.g., fractal shape, split-ring shape, and the like. The shells **202** can surround an object to be cloaked, as indicated in FIG. **2**.

As indicated in FIG. **2** (by dashed lines **1** and **2** and arrows), the various shells themselves do not have to form closed surfaces. Rather, one or more shells can form open surfaces. This can allow for preferential cloaking of the object in one direction or over a given angle (solid angle). Moreover, while dashed lines **1** and **2** are shown intersecting shells B**1**-B**3** and A**1**-A**3** of system **200**, one or more shells of each group of shells (B**1**-B**3** and A**1**-A**3**) can be closed while others are open.

With further regard to FIGS. **1**-**2**, it should be appreciated that the cross-sections shown for each shell can represent closed geometric shapes, e.g., spherical and ellipsoidal shells.

As indicated previously, each shell of a cloaking system can include multiple resonators. The resonators can be repeated patterns of conductive traces. These conductive traces can be closed geometric shapes, e.g., rings, loops, closed fractals, etc. The resonator(s) can being self similar to at least second iteration. The resonators can include split-ring shapes, for some embodiments. The resonant structures are not required to be closed shapes, however, and open shapes can be used for such.

In exemplary embodiments, the closed loops can be configured as a fractals or fractal-based shapes, e.g., as depicted by **302** in FIG. **3** for an exemplary embodiment of a shell **300**, or **402** in FIG. **4**. The dimensions and type of fractal shape can be the same for each shell type but can vary between shell types. This variation (e.g., scaling of the same fractal shape) can afford increased bandwidth for the cloaking characteristics of the system (e.g., system **100** of FIG. **1**) This can lead to periodicity of the fractal shapes of common shell types but aperiodicity between the fractal shapes of different shell types.

Examples of suitable fractal shapes (for use for shells and/or a scatting object) can include, but are not limited to, fractal shapes described in one or more of the following patents, owned by the assignee of the present disclosure, the entire contents of all of which are incorporated herein by reference: U.S. Pat. Nos. 6,452,553; 6,104,349; 6,140,975; 7,145,513; 7,256,751; 6,127,977; 6,476,766; 7,019,695; 7,215,290; 6,445,352; 7,126,537; 7,190,318; 6,985,122; 7,345,642; and, U.S. Pat. No. 7,456,799.

Other suitable fractal shape for the resonant structures can include any of the following: a Koch fractal, a Minkowski fractal, a Cantor fractal, a torn square fractal, a Mandelbrot, a Caley tree fractal, a monkey's swing fractal, a Sierpinski gasket, and a Julia fractal, a contour set fractal, a Sierpinski triangle fractal, a Menger sponge fractal, a dragon curve fractal, a space-filling curve fractal, a Koch curve fractal, an Iypanov fractal, and a Kleinian group fractal.

FIG. **3** depicts an exemplary embodiment of a shell **300** (only a portion is shown) that includes repeated conductive traces that are configured in a fractal shape **302** (the individual closed traces). For the exemplary embodiment shown, each resonator shape **302** is about 1 cm on a side. Such resonator could, e.g., be used for the fractal shapes of shells B**1**-B**3** of FIG. **1**, in which case similar fractal shapes of larger size (e.g., about 1.5 cm on a side) could be used for shells A**1**-A**4**. The conductive trace is preferably made of copper. While exemplary fractal shapes are shown in FIG. **3**, the present disclosure is not limited to such and any other suitable fractal shapes (including generator motifs) may be used in accordance with the present disclosure.

It will be appreciated that the resonant structures of the shells may be formed or made by any suitable techniques and with any suitable materials. For example, semiconductors with desired doping levels and dopants may be used as conductive materials. Suitable metals or metal containing compounds may be used. Suitable techniques may be used to place conductors on/in a shell, including, but no limited to, printing techniques, photolithography techniques, etching techniques, and the like.

It will also be appreciated that the shells may be made of any suitable material(s). Printed circuit board materials may be used. Flexible circuit board materials are preferred. Other material may, however, be used for the shells and the shells themselves can be made of non-continuous elements, e.g., a frame or framework. For example, various plastics may be used.

FIG. **4** depicts a perspective view (photograph) of an exemplary embodiment of a cloak system **400** according to the present disclosure. As shown, the system includes a number of resonator shells **402** each having a close-packed arrangement of electrically conductive material (self-similar resonators **404**) formed on one surface. Two different shell configurations are shown, four larger shells and two smaller shells. The smaller shells included close-packed arrangements of resonator structures in which each resonator shape (as shown by **302** in FIG. **3**) was about 1 cm on a side. Similar fractal shapes of larger size (e.g., about 1.5 cm on a side) were used for the larger shells.

In FIG. **4**, a transmitting (source) antenna and a receiving antenna are shown as triangular shapes on the left and right, respectively (though functionally of each could of course be interchanged for the other). Twelve radially arrayed spacers are shown in FIG. **4**. The system **400** is shown supported on a Nalgene tank and Delrin platform and Delrin supports (radial supports) RF absorbers were placed in the immediate vicinity of the set up; further RF tripods (e.g., available from ETS) were used; all such materials were substantially transparent at the RF frequencies investigated/used. The cloak system **400** consists of six belts of fractal metamaterial (i.e., fractal-resonant structures shown in FIG. **3**) on flexible Taconic EF35 (low loss) circuit board. The belts are shown surround a scattering ring (object). The arrangement is supported by RF transparent plastics in a comb support. The entire system **400** was shown to be easily built up and broken down within a minute or two. The scale in FIG. **4** is about 0.7 meters across. The height of each shell can of course be selected as desired depending on the situation/application.

While embodiments are shown and described herein as having shells in the shape of concentric rings (circular cylinders), shells can take other shapes in other embodiments. For example, one or more shells could have a generally spherical shape (with minor deviations for structural support). In an exemplary embodiment, the shells could form a nested arrangement of such spherical shapes, around an object to be shielded (at the targeted/selected frequencies/wavelengths). Shell cross-sections of angular shapes, e.g., triangular, hexagonal, while not preferred, may be used.

One skilled in the art will appreciate that embodiments and/or portions of embodiments of the present disclosure can be implemented in/with computer-readable storage media (e.g., hardware, software, firmware, or any combinations of such), and can be distributed and/or practiced over one or more networks. Steps or operations (or portions of such) as described herein, including processing functions to derive, learn, or calculate formula and/or mathematical models utilized and/or produced by the embodiments of the present disclosure, can be processed by one or more suitable processors, e.g., central processing units ("CPUs") implementing suitable code/instructions in any suitable language (machine dependent on machine independent).

While certain embodiments and/or aspects have been described herein, it will be understood by one skilled in the art that the methods, systems, and apparatus of the present disclosure may be embodied in other specific forms without departing from the spirit thereof.

For example, while certain wavelengths/frequencies of operation have been described, these are merely representative and other wavelength/frequencies may be utilized or achieved within the scope of the present disclosure.

Furthermore, while certain preferred fractal generator shapes have been described others may be used within the scope of the present disclosure. Accordingly, the embodiments described herein are to be considered in all respects as illustrative of the present disclosure and not restrictive.

What is claimed is:

1. An electrical resonator system, comprising:

a plurality of concentric electrical resonator shells, each shell including a substrate having first and second surfaces and a close-packed arrangement of electrically conductive material formed on the first surface, wherein the closed-packed arrangement comprises a plurality of self-similar electrical resonator shapes and is configured to operate at a desired passband of electromagnetic radiation;

wherein the close-packed arrangements of at least two of the electrical resonator shells are different in size and/or shape; and

wherein a resonator in the close-packed arrangement comprises a second order or higher fractal.

2. The system of claim **1**, wherein said passband is about 2:1.

3. The system of claim **2**, wherein said passband is about 3:1.

4. The system of claim **1**, wherein the electrical system is configured and arranged so that radiation incident on the system from a given direction has an intensity on a point-by-point basis such at each respective antipodal point, relative to an object placed at the center of the system, the radiation has the same or similar intensity.

5. The system of claim **1**, wherein the system is configured and arranged so that radiation incident on the system from a direction in cylindrical coordinates has the same or similar intensity at the antipodal point after having traversed the system.

6. The system of claim **1**, wherein the plurality of shells comprises a first pair of shells having similar closed-packed arrangements for operation at a first passband, wherein the two shells are positioned within ⅛λ of one another.

7. The system of claim **6**, wherein the plurality of shells comprises a second pair of shells having similar closed-packed arrangements for operation at a second frequency band, wherein the two shells are positioned within ⅛λ of one another.

8. The system of claim **1**, wherein the plurality of shells are hemispherical.

9. The system of claim **1**, wherein the plurality of shells are cylindrical.

10. The system of claim **1**, wherein the plurality of shells are spherical.

11. The system of claim **1**, wherein said fractal is selected from the group consisting of a Koch fractal, a Minkowski fractal, a Cantor fractal, a torn square fractal, a Mandelbrot, a Caley tree fractal, a monkey's swing fractal, a Sierpinski gasket, and a Julia fractal.

12. The system of claim **1**, wherein the fractal is selected from the group consisting of a contour set fractal, a Sierpinski triangle fractal, a Menger sponge fractal, a dragon curve fractal, a space-filling curve fractal, a Koch curve fractal, a Lypanov fractal, and a Kleinian group fractal.

13. The system of claim **1**, wherein the plurality of concentric electrical resonator shells are configured and arranged for operation at K band, Ka band, or X-band.

14. The system of claim **1**, wherein the system is operational over a bandwidth from about 500 MHz to about 1500 MHz.

* * * * *

NU ENERGY TECHNOLOGIES
Your Energy Source for the New Millennium



Radiant Energy
Power Generation

revised millennium edition

Information in this document is subject to change without notice and does not represent a commitment on the part of Bruce A. Perreault. The information described in this document is furnished under a license agreement or nondisclosure agreement. The information may be used or copied only in accordance with the terms of the agreement. It is against the law to copy this information on magnetic tape, disk, or any other medium for any purpose other than the purchaser’s personal use.

LICENSE AGREEMENT

IMPORTANT – By reading the pages to follow and/or by using the enclosed information, you agree to be bound by the terms set-forth herein by Bruce A. Perreault (BAP). BAP grants you a limited, non-exclusive, non-transferable, royalty-free license for the use of one copy of the enclosed information. BAP retains all title and all ownership rights to this information. All rights not expressly granted are reserved to BAP. You shall not rent, lease, sell, sub-license, assign, or otherwise transfer the information. You shall not decompose or disassemble the information except to the extent that this restriction is expressly prohibited by law. Your license for the use of the information shall commence upon your receipt of it. The license shall continue until terminated in writing by the author or his estate. The information is deemed accepted by you. In no event shall Bruce A. Perreault be liable for any consequential, incidental, direct, indirect, special, punitive, or other damages whatsoever arising out of this agreement or the use of or inability to use the information, except to the extent that this limitation is prohibited by law.

Copyright Information

Unless otherwise noted, all materials (including without limitation all text, graphics, instructions, and demonstrations) are copyrighted, ©1999, 2000, July 2001 & November 2001 by Bruce A. Perreault. The material available through this publication may be freely used for attributed **noncommercial educational** purposes only. Due credit is hereby requested and notification is to be given to the author.

All materials may not be reproduced, stored in any retrieval system, or used in any way for commercial purposes without the express prior written permission of the copyright holder.

ISBN 1-930216-01-7

Dedication

Dr. Thomas Henry Moray, of Salt Lake City, Utah, was probably the first to use Radiant Energy as a source of power. His tireless effort, to gain recognition for this work, has been an inspiration to me.

The original concepts presented by the late Dr. Thomas Henry Moray, of Salt Lake City, between the years 1909 to 1974, have paved a road to our energy independence. He made history by drawing the attention of the scientific community to certain discoveries of far-reaching importance. His research involved the direct application of Radiant Energy, to the ultimate electric particles of the atoms and molecules of the Universe. Dr. Moray's discoveries, when demonstrated, convinced large numbers of scientific men who had witnessed them in action. However, there were a few scientists in high places who prevented the commercial success of this technology.

If these eminent men, the supposed leaders of the scientific community, had the privilege of studying under Dr. Moray; they would have understood his discoveries and applauded them. But in their ignorance of Radiant Energy, they refused to believe or even listen politely to the facts that he often demonstrated.

One of his prototypes measured about 42 x 26 x 22 inches and weighed no more than sixty pounds. It generated around four kilowatts of electrical power and was demonstrated in front of scores of witnesses. Unfortunately, these few people, knowing nothing of the truth, have done incalculable damage to Moray's discoveries over the years.

In its' widest form, Radiant Energy can be said to be the "Holy Grail of Free Energy." Those who wish to study this exciting subject will do well to give serious attention to Dr. Moray's original discoveries and to my recent research.

It should be as easy to accept the fact that a device can be built to receive radiation from its surroundings as it is to accept a radio that receives broadcast waves. One device transforms radio energy coming from a transmitter to sound while the other transposes electrical particles into heat, light, or power. The fundamentals are the same in radio and in the Radiant Energy (R. E.) device. The radio receiver receives transmitted energy waves out of the air; the R. E. device receives energy waves from atomic ions and converts them into electricity. As in the reception of radio waves, the Radiant Energy circuit is tuned to respond to the natural energy that is emitted from certain intermolecular reactions.

Table of Contents

BOOK DEDICATION ii
LIST OF FIGURES iv
INTRODUCTION v

SECTION 1
ATOMOSPHERIC ELECTRICITY 1

SECTION 2
THE WIRELESS TELEGRAPHIC CONNECTION 3

SECTION 3
MORAY'S CIRCUITRY 7

SECTION 4
EARLY DEMONSTRATIONS 10

SECTION 5
MY RADIANT ENERGY RESEARCH 31

SECTION 6
ION VALVE TECHNOLOGY EXPLAINED 35

SECTION 7
EDWIN GRAY'S ENERGY SYSTEM 39

SECTION 8
TREATISE ON MATTER & ENERGY 41

SECTION 9
ALPHA FUSION 47

SECTION 10
THE TRUTH ABOUT NUCLEAR SCIENCE 53

REFERENCE PATENT
HERMANN PLAUSON - JUNE 9, 1925 - 1,540,998 56

List of figures

Number **Page**

Figure 1 - EARLY RADIANT ENERGY CIRCUIT 7

Figure 2 - SOURCES OF RADIANT ENERGY 8

Figure 3 - PROOF OF CONCEPT 34

Figure 4 - ION VALVE 35

Figure 5 - RADIANT ENERGY GENERATOR CONCEPT DEVICE 37

Figure 6 - EDWIN GRAY ENERGY SYSTEM 40

Radiant Energy is emitted as charged particles from all bodies at a constant rate. The mystery surrounding it will unlock untold amounts of energy. Under the proper conditions, it can be rendered susceptible to the most incomprehensible changes caused by the oscillations, pulsation and surging throughout the Universe.

It was discovered by the Curie’s that all matter is radioactive. It can be shown that radium, barium, uranium, thorium, polonium, vanadium, cerium, molybdenum, zinc, aluminum, etc... will imprint radiographs on sensitive photographic paper.

The Sun’s explosions hurl intense surges of Radiant Energy at the Earth. The atmosphere absorbs these particles, shielding all life on the planet from deadly harm. Electrical charge is induced into the clouds that form in the lower atmosphere. This is due to the fact that clouds are in constant motion and travel parallel to the highly charged upper atmosphere. Once enough charge is built up in a cloud, it discharges to the ground as lightening. Static charge is thus transformed into kinetic oscillations. The Earth’s magnetic field quivers in response to these surgings. Is it too far fetched to reason that we can duplicate this natural process to obtain electrical power?

If an oscillating tank circuit has the correct impedance, reactance and inductance it will absorb energy from an external oscillating electrical source. Energy is captured. The tank oscillations can be kept alive by establishing resonance with the external source. Therefore, energy is not drawn from the transformer that powers the tank circuit. In the case of the Radiant Energy Receiver, it becomes possible to harness the atomic electrons that are generated within specially constructed energized plasma tubes.

What I have just revealed here is the "Holy Grail of Energy." The implications of this discovery are far and wide. Is humankind ready for such a revelation? What will be explained in the pages to follow is nothing more than a glorified radio receiver, one that is designed to oscillate with the oscillations of the Universe. It locks onto the very wheelwork of nature. This Radiant Energy receiver should last for many years with very little maintenance, no more than for a good radio.

"Electric power is everywhere present in unlimited quantities and can drive the world's machinery without the need of coal, oil, gas, or any other of the common fuels."

-Nikola Tesla

Atmospheric Electricity

We have succeeded in penetrating many secrets of Nature. Because of this we have an obligation to honor her abundant miracles with care and respect.

Since the time of Benjamin Franklin and his famous kite experiments not much has been learned about the nature of atmospheric electricity and how to convert it into useful power. Certain people have discussed this form of energy to some extent. Some theoretical papers in the so-called "free energy" field have been written. Many of these theorists deny that our ionized atmosphere can be utilized to produce usable amounts of electrical power. They are determined to cling to their wild unproven theories.

Nevertheless, I have taken it upon myself to find a solution to converting ionized particles into useful electrical currents. The properties of radioactive matter have shown me that large quantities of energy can be collected and converted. I have found that with the right circuits and components, rivers of high-voltage static electricity can be efficiently transformed into a lower practical voltage. It is my desire to be able to furnish irrefutable proof of this process, in this new millennium. However, there are still more questions that need to be answered. The utilization of the atmospheric electricity on completely new ground has to first take place.

The production and utilization of atmospheric electricity for the well being of humankind has been the goal of scholars and researchers for countless years now. However, the implementation of a real working device has remained a pious desire until today. This is because well-intentioned researchers turn away from the simple fact that there is free electricity in the atmospheric air just waiting to power our appliances. Only in the last year have I realized through new experiences and investigations that atmospheric electricity may be drawn into an electronic device in usable quantities to be converted into useful power.

Many researchers after investigating atmospheric electricity become astonished when they realize that there is nothing new in the World. They find out that the features of atmospheric electricity have been with us for a very long time, before the knowledge of electricity. The wisdom of the effects and utilization of atmospheric electricity dates back many thousands of years, as we can infer from the biblical texts. We read in the first book of Moses, that the all-holiest temple of Jehovah housed the Ark of the Covenant. With the exception of the high priests, this Ark would kill anyone getting to close to it. Furthermore, we read that 40 priests dared to approach the Ark, in the absence of Moses and Aaron. Lightning issued out from it, killing all 40 priests.

It is written in the second book of Moses, Chapter 25 verses 10-11:

10. Frame an ark of acacia-wood; the length whereof shall be of two cubits and a half (45 inches): the width, a cubit and a half (27 inches): the height, likewise a cubit and a half.
11. And thou shall overlay it with the purest gold within and without (exactly like a capacitor).

The biblical text sited here indicates that the Ark was made out of a noble wood that acted as a good electrical insulator and that gold was to be laid inside and out. Thereby, all conditions were just right for creating a good electrical capacitor. From the description we can tell that Moses and Aaron knew how to collect electrostatic energy from the atmosphere. This Ark of the Covenant could only have been a very large capacitor with a huge capacity. It was charged by atmospheric electricity from the accounts given. The fact that it remained fully charged with this electricity must be attributed to the dry climate in Palestine. Knowledge of this energy was a coveted secret kept by Moses and the high priests of Egypt. They were the first connoisseurs of atmospheric electricity.

When the study of meteorology first began there was a big interest in atmospheric electricity. Many in this field thought to use it. This is revealed through the patents of the time. The first relevant patent was granted to inventor Dr. Heinrich Rudolph of St. Goarshausen according to the German Patent Office; D.R.P. No. 98180 January 19, 1897.

Benjamin Franklin in America made a few attempts to utilize atmospheric electricity. He once built a motor that implied a commercially significant amount of energy might be derived from the Earth's atmosphere. It has been observed that a potential gradient of 150 volts per meter of height is always available on average.

There are three major causes of atmospheric ionization shown in **Figure 2**. The first one is due to the cosmic rays and the second cause is due to the solar winds. The solar winds consist of 96% protons and the remaining percentage is atoms of tritium. There are other particles but they are relatively unimportant. Almost all of these high-energy particles are absorbed by the Earth's upper atmosphere causing it to become ionized. This is how the ionosphere is created. However, the area where the reaction between the solar wind and the magnetosphere takes place is far outside of the Earth's atmosphere. The charged solar wind particles rattle our planet's magnetic cage long before its gas envelope neutralizes them. The third cause of atmospheric ionization is due to the content of radioactive gasses contained in the air we breathe. In the ground radioactive substances such as radium, thorium and actinium are spread throughout the soil. These elements generate gaseous radioactive emanations that spread in the air and ionize its molecules. The actinium-emanation generated from the decay of U235 plays a major role because of its brief radioactive half-life of 3.9 seconds.

Radio Ionics

There are not enough charged ions in the air to be converted into electrical power. This on the surface appears to be a correct calculation and assumption. There simply are not enough of them. However, what has been overlooked is the fact that these ions are in a state of constant surging motion. This is the mechanism to obtain power from this sea of energy! It is not the charge that should be looked at. These ions are in motion like magnets are in motion in a generator. Can you see the correlation here? It is the motion of the ions that **induce** electrical current. By means of properly tuned radio ionic circuit rests a possible solution to harnessing this source of energy. Hermann Plauson was successful in converting atmospheric energy into useful electrical currents. He was granted a patent titled "Conversion of Atmospheric Electric Energy" – U.S. Patent No. 1,540,998. In this patent he states that "St. Elmo's fire and the northern lights can be more or less absorbed in the same way as a receiver in wireless telegraphy absorbs waves coming from a far distance." This patent has been added to the end of this book for your study. It begins on page 59.

The Wireless Telegraphic Connection

Radio in the early years was called "wireless telegraphy." Beginning around the year 1913, amateur wireless telegraph stations were set up in trees and housetops. Aerials and masts dotted the countryside. It is estimated that there was almost "a quarter of a million stations." They were used to send and receive wireless telegraph signals, not voice. Vacuum tubes were not yet widely known. These stations had to rely on spark gaps.

It was the energy spikes, or surges put out by the spark-gap transmitters that first caught T. H. Moray’s attention back in 1903. In 1909 Moray devised a circuit that would draw electricity from these surges of energy that traveled through the ground. By the fall of 1910 he obtained enough electrical energy from the ground to power a miniature arc lamp. During the Christmas holidays of 1911 he was able to power an old type 16-candle carbon arc lamp at about half of its brightness.

In 1912 while Henry Moray was on mission with the Mormon Church in Uppsala, Sweden, his passion for crystal radios got him started in his research in the science of radiant energy. Every spare moment he searched for a mineral that could possibly work as a radio detector. Moray had found two specimens that worked well as radio detectors. The material found in the hillside could have very well been a type of **argenti-zinciferrous-galena.** This type of galena is highly sensitive to radio waves that allowed his receiver to function without a battery. I make this assumption because a galena type synthetic formula can be found in Moray’s Electrotherapeutic Apparatus – U.S. Patent No. 2,460,707. This material using only the power transmitted from a local wireless station could drive a small horn speaker as reported by Moray.

The other detector material was a white, powdery, stone-like material that he found in a railway car, located in Abisko, Sweden. From military records we know for certain that this white material was "**fused silica.**" Silica is the chemical name for the simple oxide of silicon, silicon dioxide (SiO_4). Mineralogists call this compound **quartz.** This is normally found in nature in its crystalline form. Finding this mineral in a fused state can only mean one thing. That, what Moray found was **metamict quartz.** A metamict is a crystalline mineral that loses its crystal structure due to radioactive destruction. For this to occur the quartz had to have contained trace amounts of uranium and/or thorium, which is why it was found in a "fused" state, in a more or less amorphous state, the so-called metamict state, owing to radiation damage from α-decay of these impurities. "Over the course of hundreds of millions of years, α-decay doses as high as 10^{19} decays/g can occur, which may lead to the complete amorphization"**(1)** of the quartz structure.

Moray's rare mineral find became known as the "Swedish stone." He was able to light a standard 100-watt General Electric light bulb in June of 1925 with this Swedish stone. By August 1925 he was able power an electric flat iron along with the 100-watt bulb. Therefore, bringing the total power consumed to 655 watts. People would quite often demand that he would draw too much power from his device and the white, stone-like material would overheat and burn up.

A problem of drawing power from telegraph stations appeared when the Federal Radio Commission on Nov. 11, 1928 limited the amount that could be transmitted. The transmitted frequency also had to be well defined. Spark-gap transmitters simply could not meet these requirements. Scores of spark gap driven telegraph stations had to be dismantled and in effect had been given death sentences. This spelled disaster for Moray. He could still draw energy from the background radio noise produced by the great cosmos but the amount of power that he could obtain was severely limited. Originally, Moray's source of power was drawn from the local spark gap radio transmitting stations through the ground. Moray could draw power from the radio frequencies generated by nature but unfortunately only very low power could be had from this source. This forced Moray to develop a more favorable detector material. It was not too long before he got the inspiration to add radioactive dopants to his Swedish stone material and to other types of semiconductive materials. This occurred shortly after the Radio Allocation Act of 1928 when Moray's detectors were no longer able to receive steady incoming power. His Radiant Energy receiver could produce power but it only came in regular pulses. It was not constant without the added radioactive material. The addition of radioactive dopants to semiconductors allowed his receiver to produce a steady flow of energy.

Radiant Energy Early Definition

Professor Langley showed that out of the total amount of radiation coming from the Sun, only the visible portion of the spectrum represents only 19%. He presented the theory that there is only one kind of energy radiated from sunlight. That, heat, and chemical effects depend entirely upon the state or condition which radiant energy may happen to fall on matter.

Professor Langley wrote that up until 1872 it was almost universally believed that there were three different kinds of **entities**–actinic, luminous, and thermal, represented in the spectrum. There is only one radiant energy that appears to us as 'actinic,' or 'luminous,' or 'thermal' radiation, according to the way we observe it. Heat and light, therefore, can not be things in themselves, but separate sensations to our bodily sensors. They are merely effects of this mysterious thing called "radiant energy."

The Italian physicist Melloni stated that, "light is merely a series of caloric indications sensible to the organs of sight, or vice versa, the radiation of obscure heat are veritable invisible radiation of light." Melloni wrote this in 1843, but it was not adopted until Langley by his elaborate researches, more refined and complex, proved it. The great physicists of society then adopted the doctrine of one radiant energy.

Only a few researchers know the immediate effect of radiant energy: electromagnetic. The results of two centuries of observation all point to this conclusion. When a mighty tongue of white-hot matter darts across the abyss of a large spot or cavern on the Sun, the equilibrium of the Earth's magnetic field is disturbed and the effect is a magnetic storm. The needles of magnetographs throughout the world quiver and oscillate. The vibrations take place on opposite sides of our planet, the impulse passes from the Sun to the side nearest of the Earth and then to the most distant side, whether through or around the Planet's surface.

After centuries of investigation from Gilbert to Tesla, this most wonderful research still holds admiration and mystery for all that study this vast science; electrodynamics. Power is cut out of the seemingly emptiness of space, and the hurrying waves are caught and chained to servitude in artificial light and electric appliances. The Sun, being electromagnetic, emits waves that carry power, which beat and surge against the Earth. A magnetic field is space that surrounds a magnet. This space might be filled with air, wood, stone, glass, or might be a vacuum. But the waves are not quenched. They flow through all of these things. A freely suspended magnet in a magnetic field will move, and the Earth's surface is surrounded by a magnetic field, that is acted upon by the Sun's magnetic field. Suspend a sewing needle by a silk fiber in the Earth's magnetic field and it will come to rest parallel to the field's north and south poles. Now, if this field becomes disturbed, that is; if it becomes stronger or weaker, the needle will move. This is a magnetic storm. When a gas jet is hurled across a spot on the Sun the disturbance reaches the Earth in the same time that light does. So, radiance traveling at 186,000 miles per second is reaching the Earth in eight minutes and nineteen seconds.

The most memorable magnetic storm occurred on November 17, 1882. This was one of the most violent recorded. The daily press was burdened with accounts of widespread magnetic disturbance. In some places telegraphic communication was suspended. The turbulence filled that great quadrilateral from New York to Yankton, Nashville and Winnipeg. In Milwaukee, the carbons in the electric lamps were lighted, rendered incandescent by currents of electricity flowing on the wires. At other locations, switchboards in telegraph offices were set on fire and sending keys were melted, while electric balls were seen hovering on the telegraph lines in Nebraska.

The Earth's aurora holds the key to harnessing the Sun's daily pulsation. An aurora is the visible effect of obscure undulations from the Sun, as they come dashing on the Earth with a speed of 186,000 miles per second. In a six-month winter, say at the North Pole of the Earth, the Sun is far south of the equator, and none of its rays can shine on the Earth's northern pole. However, the aurora is very bright. It displays many colors, and these flash and glow with rapid variations. The light, although caused by the Sun, does not come direct. It is caused by the turbulence set up in the Earth's magnetic field by electromagnetic upheaval on the Sun. The field of the Earth is "tuned" with the Sun's field, as was the coherer in the days of wireless telegraphy and telephony. The aurora is known to be electrical, for magnets and compass needles on ships are always affected. Could the coherer of the days of old teach us something new?

No magnet can be placed near a "current" of electricity, or a static charge without making an oscillation. Every oscillation sends out a wave, like a stone falling in water. An electromagnetic wave from the Sun disturbs the Earth's magnetic field in the same way that an induction coil used in wireless telegraphy does. The Earth and coherer are both doing the same thing with the same kind of electromagnetic waves. The coherer in a distant receiving station will react to natural electromagnetic wave fronts from the Sun. It will likewise react to the artificial wave fronts coming from the induction coil. The electromagnetic wave makes the loose particles of metal between the knobs in the glass tube coherer generate dots and dashes.

Making a device "oscillate with the oscillations of the Universe" may not be too far off the mark in obtaining energy. Perhaps a radon-powered diode (ion valve) will act as a one way gate to this energy? This type of specialized diode offers zero resistance to electrical current. It is also an ion gate that can function in the million-volt range. Today's state of the art high voltage diodes will not meet our requirement. This is because as more are added in series the greater the electrical resistance becomes. I believe that Moray's Swedish stone met our requirements utilizing only a trace amount of radon generating material.

Moray found that semiconductive materials doped with radioactive impurities have an increased sensitivity. One such satisfactory formula included a triboluminescent zinc mixture consisting of pure zinc sulfide, radioactive impurities and pure germanium metal. He also found that "artificial radiation" could be used in place of the radioactive impurities. For example, by exposing bismuth to wavelengths of energy emitted from one of his unique vacuum tubes, he was able to create "active bismuth," today known as Polonium–210. This is what Moray called "artificial radiation." When added to the zinc sulfide, it would glow a bluish-green. When this glowing material was then doped into ultra-pure germanium it made an excellent emitter of secondary electrons. This synthetic substance was called "fission material" by Moray. This transistor type material is said to be superior even to what is available today.

"The Moray germanium mixture gives certain unique results in functioning as in a valve and or booster (amplifier). Made in form of rounded stones or pellets compressed under high pressure and fused. Combination contains **radium chloride, thorium, uranium, and pure germanium metal-triboluminescent zinc.** Some pellets fastened to envelop with pure tin in place of solder. Bismuth pellets fused to side. Germanium mixture pellets float between other pellets but making firm, needlepoint-like contact. Have used silicon too, which has some of the properties of germanium. Germanium works best when impurities are introduced. Care must be taken when alloyed with other substances, as too much other mixture added worsens conductivity and germanium loses its properties." * T.H. Moray, 5th edition, The Sea of Energy in Which the Earth Floats (1978), p. 71.

I had often asked myself: what ever became of Moray’s radiant energy tubes? Wouldn’t it be nice to run some tests on them? These questions have been put to rest because these very tubes are now in my possession. It was communicated to me that the widow of T. H. Moray gave these tubes and his notebook to a man named Stan Mahurin. This man knew Moray and his wife quite well.

Mr. Mahurin passed the tubes onto a close friend because he had no clue as to their function but insisted on keeping the notebook. The next owner of the tubes had no clue either. These tubes remained in storage for over twenty-five years. I was contacted because of my passion for Radiant Energy research and was given the opportunity to purchase them. I promptly replied and have had the honor to inspect them first hand. Upon inspection of these tubes there does not appear to be any radioactive material in them. However, this does not mean that it was never in the tubes. Moray stated that he was using what he called "artificial radiation." From his notes we know that he created this artificial radioactive material by attracting radon gas to a metal by giving it a negative charge. We also know that radon decays to lead-210, a beta emitter with a half-life of around 22 years. This would mean that Moray's source of induced radioactive material would eventually burn itself out. This would explain why Moray did not have a running prototype in his later years.

My own research is now nearly complete. My next project is to build a radiant energy generator that will demonstrate a few hundred watts of excess power above what the circuits require to be self-sustaining. The final step will be for me to develop a commercial unit for general use. Through this millennium edition of my book, the shroud of mystery surrounding this old source of energy may now be lifted.

1) Miami University, Herbert Jaeger Physics

Moray’s Circuitry


antenna
"It's the ions, not the electrons!
-T.H. Moray
radiant energy detector
A radioactive salt was applied to the copper element with varnish
To lights
earth ground

Early Radiant Energy Circuit - Figure 1

It is assumed that the average reader of this publication is familiar with the elementary principles of radio transmission. Granting this, it is of course reasonable to believe that such readers will understand how an oscillating current is set up in a circuit comprising an inductance or coil of wire, a capacitor and a spark gap. The capacitor is charged with a high tension current from any convenient source such as a transformer or induction coil. When the potential stored in the capacitor reaches a critical value, the air in the gap between the spark gap electrodes can no longer stand the strain. The capacitor discharges across the gap in a succession of crashing sparks. As the current from the capacitor crosses the gap in one direction, it literally over-reaches itself just as a pendulum will swing past the neutral point when given a push by hand. After the first rush of current passes in one direction, a reversal of the cycle occurs and a second rush in the opposite direction occurs. This operation is repeated many thousands of times per second. The discharge gradually dies down as all the energy is either completely radiated or used up in heat or performing work. The oscillations cease once the potential across the capacitor has been lowered so that the spark can no longer jump the air gap. The capacitor immediately takes a fresh charge from the transformer and the entire cycle of operations is repeated. It will be understood that all of this passes in an infinitesimal fraction of a second. The charge and discharge of the capacitor takes place so rapidly that the observer can detect no change in the solid spark that appears continuously to fill the gap. It should also be understood that if the oscillating tank circuit has the correct impedance, reactance and inductance, it would absorb energy from an external oscillating electrical source. Energy is therefore **captured.** The tank oscillations can be kept alive by establishing resonance with the external source. In the case of Moray's early radiant energy receiver, the capacitor was charged through a material that acted like a high voltage diode. This material he called "Swedish stone." Electrons (electricity) were actually generated in the discharge tubes and fed back to the antenna and ground circuitry. This mode of energy generation is explained in more detail on pages 37 to 38.

What has been explained here is the Holy Grail of energy. The implications of this discovery are far and wide. Is humankind ready for such a revolutionary design? This receiver locks onto the very wheelwork of Nature. This device should last for many years with very little maintenance, no more than for a good radio.



Sources of Radiant Energy - Figure 2

SOME FACTS TO THINK ABOUT

1. Cosmic particles are hurled at the Earth from outer space.

2. The Sun emits ionized **protons** and **tritium** atoms that are carried to the Earth by the solar winds 24 hours each and every day.

3. The Earth's upper atmosphere absorbs the charge carried by the particles in the solar winds causing it to become ionized.

4. The Earth's ionized atmospheric region is called the "ionosphere." It is sort of a half gas and half plasma.

5. Water vapor (clouds) become charged by induction as they travel parallel to the ionosphere.

6. When clouds become sufficiently charged they will discharge according to Pupin’s theory of capacitive discharge. The energy is released in the form of light and electrical oscillations.

7. There is a cloud discharge about one hundred times each second that is randomly located somewhere on the planet, generating a tremendous amount of oscillating electrical energy. The total energy per discharge is approximately "**two million-million watts.**" Now multiply this by one hundred and you have an unbelievable amount of unleashed energy.

8. The facts presented are Nature’s process of generating oscillating electrical energy.

Moray’s Radiant Energy Detector Tube

T.H. Moray invented a very unique vacuum tube. He called this discovery, the "Moray-valve." It functioned as a high-voltage, high frequency, minute capacitance detector tube. It included solid-state semiconductors mounted "under ideal conditions."

This Radiant Energy valve contained Moray’s fission material. It replaced the original Swedish Stone. It’s anode acted as a collector made with a molybdenum disulfide rod. The metal case served as a parabolic reflector to concentrate and focus the secondary ions that were expelled from the fission material.

Radiant Energy in Moray's detector comes to us in waves of separate and distinct units called photons. There are definite relationships between the energies of these particles and the zinc sulfide (triboluminescent zinc) germanium mixture, contained in Moray’s fission material. The zinc sulfide in the mixture is highly sensitive to the photons generated from the fission material. The sulfide transforms the high frequency photons into lower frequency photons. These photons then **impinge** upon the germanium. The germanium being sensitive to these lower frequency photons emit secondary photo ions. The hemisphere that contains the active materials was filled with a low-pressure water vapor and was comparatively simple in construction.

Thomas H. Moray successfully demonstrated an electrical device, weighing less than sixty pounds, that extracted enormous amounts of energy: 4,000 watts. This unconventional source of energy is abundant day or night throughout the year. To understand how this device generates energy, you must carefully read the material contained in this book. I have compiled this information to assist you in understanding radiant energy power generation without giving away the entire contents of my discoveries.

On the introduction page in the "The Sea of Energy in Which the Earth Floats," 4th edition, Moray explains that radiant energy is kinetic in nature. It is rendered sensible by conversion of its energy. He states that "this is the phenomenon of the transducer fueled by a fission reaction. In the final analysis, radiant energy is a means of using the energy released by the fissionable reactions taking place in the stellar crucibles of the universe." Moray in his 2nd edition, on page 61, describes the "universe" as being both stellar and atomic. The final clue to the inter-most secret of Moray’s energy device can be found on page 33 in this same edition; "It is an accepted fact that when various substances are bombarded with alpha particles they are found to give off **electrons.**" How much clearer could he have made this? He further states; "just as sodium, potassium, cesium, rubidium, barium and strontium react to visible light or wavelengths within a certain range, might not certain other substances react to oscillations from the Cosmos or artificially produced radiation?" Moray’s **fission material** clearly fits this description. How could we not know from this description how Moray’s "detector" functioned? He also states; "the universe is analogous to a radio transmitting station. It is continually emitting energy, only of a greater range of wavelengths." Is it this type of statement that has confused people seeking answers? I say that this is a certainty.

What is revealed within this publication should clear a path to the understanding of Moray’s radiant energy device for the reader. It will be understood that ionic recombination can be directed to produce intense surges of electromagnetic energy. More clearly, ionic energy is converted into electromagnetic energy. The conversion from ionic to electromagnetic energy can then be transformed into useful electrical power by conventional radio circuitry.

Electronics vs. Ionics

The Earth’s electric field that exists between the surface and the ionosphere is charged to about 360,000 volts. It is estimated that the stored energy ranges from about one million to a billion kilowatts. This field provides a low current at high voltage and will not power today’s appliances because they use high current, low voltage electromagnetic power. In 1748, Benjamin Franklin was the first to invent an electrostatic motor that could run on the earth’s energy field. Did this scientist of yesteryear point us in the right direction?

At the Paris Electrical Exhibition of 1881, Professor Amos Dolbear successfully demonstrated his electrostatic transducer for the telephone. He obtained US Patents No. 239,742 and No. 240,578 for this invention.

Thomas Edison’s 1880 discovery of thermionic emission, the current of electron flow in a vacuum tube, created the first electronic device. Sir William H. Preece called this the "Edison Effect." Edison had discovered the fundamentals of the electron tube and was granted US Patent No.307, 031. Its’ basic principle was to be used in radio communication for many years to follow.

In 1887 Dolbear was forced to go to court against Alexander Graham Bell to establish that he was the inventor of the telephone. Dolbear lost this infringement case. The judge consequently ruled that Bell was the inventor of the telephone. This decision was the pivotal point of our electrical development. Because of this one decision by a court, inventors moved in the direction of electromagnetic driven components.

Conventional radio tubes to this day are based on electron emission. Electron flow through a vacuum tube is where we get the word "electronic." If science had gone the way of ionic emission instead of electron emission in radio tubes I believe that our technology would be drastically different today.

I have designed radio tubes that carry an ion current instead of electrons. Vacuum tubes that carry electrons are called "electron valves." My tubes carry ions and therefore are called "ion valves." This changes everything about inductance and capacitance in any circuitry. Capacitance then becomes the real key element in electron transfer through associated wires and circuitry. It may be of interest to you that "ohm’s law" only applies to conventional electron tubes. In a conventional electron tube the mean velocity of an electron is about 1 cm per second. In my ion tube charge transfer is much faster. When using an ion tube as a rectifier or oscillator this changes the whole mathematical equation on the electrodynamics of the associated electrical circuits.

I believe that T. H. Moray's tube oscillators were actually ion valves. This is what allowed them to run cold. This is the Holy Grail of energy that can be used to tap into the sea of energy that is all around us. We are bathed in this sea of ions at all times. This is not just a wild dream. The circuits given in this publication are proof positive that a new technology is just on the horizon.

With the release of this publication, there can now be no doubt that we are at the dawn of a revived energy revolution. I have given a great gift to science. All I ask for in return is that you shout from your rooftops the information gleaned and to please give me the credit for what I have earned.

Early Demonstrations

What follows are accounts given by observers of the T. H. Moray radiant energy device that utilizes the vast stores of energy in the Universe without mechanical force, but through **ionic oscillations**. The statements have been edited for clarity without changing the meaning being conveyed.

A brief description of the device

A brief description of what the device has done will be given. Also, successful demonstrations will be described like those that have been made in the presence of hundreds of reliable witnesses, many of whom are highly trained and hold degrees in physics and electrical engineering. There will be a brief description of why the device works based on the oscillations of condensers. I do not believe in perpetual motion. I have no quarrel with those that may; the operation of the Moray device is **not** perpetual motion. It utilizes energy that exists and transforms it into useful forms. An electrical generator is not really a generator, as it creates nothing. The generator does not make electricity. It is merely pumped. From that standpoint, an electric generator might be referred to as an electron pump. The Moray energy device might be called an **electric siphon**, or high speed-oscillating turbine.

T. H. Moray's device was enclosed in a box 10 x 10.5 x 26 inches, one wire leading from the device to a special balanced antenna. Another wire was connected to a balanced ground connection.

In my version, a special tube ion is used. The switch of the device is simply turned on. The device is adjusted so that a synchronized resonance is established. Once it is operating, the device "siphons" energy. A specially constructed high frequency transformer is used to control the output so that any desired voltage may be obtained.

On page 17 of the "Nature of the World and of Men" (compiled by the technical staff, Chicago Institute of Technology), we learn that our planet is receiving energy from the Sun continuously at the rate of 160,000 horsepower per inhabitant.

In the "Physical Review," Dr. Gunn of the U. S. Navy Research Laboratories states that the Earth itself is a huge dynamo, producing 200,000,000 amperes of electrical current. For more detail, read pages 334 to page 344, "Physical Review," July 15, 1939.

The Aurora Borealis is definitely considered to be an electrical phenomenon produced by the passage of electric charges through the rarefied gases of the higher atmosphere.

The conversion of matter to energy in the stars is now generally accepted as fact. During radioactive disintegration energy waves are radiated. Thus, we may conclude that energy waves of very high frequency are sent out from the stars, one of which is our Sun.

Similar to the reception of radio waves, the Moray circuit is resonance tuned by the right arrangement of inductance, capacities and oscillators. These components respond to the particular wave frequency "oscillations" of energy from the Cosmos. Moray used a special valve to prevent return of the power to the outer circuit and forced it to go through the power application circuit.

All that is necessary to put the device in operation is to start electric oscillations in the circuit due to a difference of potential between ground and atmosphere.

The frequency of the current is extremely high, as is shown by the brush discharge when either the antenna lead or the ground wire is disconnected from the machine. Certain difficulties of insulation inherent in high frequency currents are avoided by the ingenious operations of the oscillator tubes that reduce the frequency on the output side.

Standard electric light globes become exceedingly hot in one spot about the size of a dime when operated on this current. This is due to the fact that the gas in the globes becomes incandescent under the influence of the very high frequency current. Also, the luminosity of the incandescent gas is much higher and whiter than with ordinary current. A variation of the Tesla, high frequency, button type globe would be ideal for use with this device.

Ordinarily, when a potential is applied to the terminals of a condenser, a full charge is acquired almost instantaneously. The filling up of Moray's oscillator tubes is similar to water being poured into a bucket. That is, the longer the voltage is applied the greater the charge that is taken, up to the maximum capacity for a given potential and frequency.

R.E. experiments have been made at different places, many miles from all power lines. One experiment occurred more than 50 miles from any power lines and 26 miles from even a farmer's telephone. The locations for these experiments were selected by those making the test and not by the inventor. These locations were not prearranged but selected as they drove along in their own car, not the auto of the inventor.

In an endurance test, the device was operated under seals for a total of 157 hours and 55 minutes. Then the seals were broken and the device was put under severe strain and tests for about another hour and then shut off.

Close examination of the device, showed that all parts were in perfect shape and could have been run indefinitely. During the entire test the light burned evenly and brightly without flickering. There was no change in the brilliance from day to day.

The quantity of current passing through the secondary of the transformer, experts have asserted, is sufficient to burn up similar wire if ordinary current was used. Yet, there is no heating of the transformer, even though cooling air was not present, as it is completely enclosed. All parts of the machine run absolutely cool regardless of the length of time operated.

It makes no difference whether one 50-watt lamp is used or whether fifty of them are connected to the machine; the current is adapted to the load.

This current has another physical characteristic as seen in photographs of light bulbs operated by the radiant energy (R.E.) device. The photographic images of such bulbs are extremely bright. So, the emulsion density in the area of the bulb image is extremely low, virtually zero. If one takes a photograph of the original print the resulting film has the same characteristics. Prints made from this second film have these same characteristics as well. The light bulb images have such extreme low density that one has to reduce the exposure of other parts of the image in order to get a satisfactory picture. Yet the light from the R. E. device is whiter and less harsh, even to stressed eyes. Here is further evidence that this current is different from any coming from conventional sources in use today.

There is no sound coming from the machine when in operation, there being no moving parts, electrical oscillations or prime mover operations.

The current cannot be derived from batteries, as it can be seen. Doctors of Physics have pronounced this current to be high frequency. Only an alternating current has these properties. Batteries provide only direct current.

It cannot be induction from adjacent power lines, as an induced current is always the same frequency as the inducing current. There is no power line on Earth carrying current of these frequencies. This current cannot be caused by radio signals. These are much too weak. To operate a loud speaker, it is necessary to amplify a radio signal many times, to say nothing of lighting a lamp or heating a flat iron. Also, the frequency of the incoming current is higher than radio signals.

Moray gave a demonstration for a nationally known physicist, a professor in one of the greatest universities of this country. The physicist made these observations:

Moray states that when the oscillators are connected to the circuit the condensers fill slowly. The longer the current is applied the greater the charge they take, up to their maximum for the applied voltage. This is similar to filling a bucket by pouring the water into it. The condensers do not take the charge instantaneously, as is ordinarily the case.

Moray has also stated that the size of wire in the transformer could not carry the amperage passing through it without burning up if ordinary current were used. Yet the wires remained absolutely cool no matter how long the machine operated.

The above points show these currents to be entirely out of the ordinary. They cannot be accounted for by induction from existing power lines or current from batteries.

Another short account follows

Today Mr. Judd, Mr. Adams and attorney Nebeker visited the inventor's laboratory. After the "radiant energy" device was packed into the attorneys’ auto, we drove away. The three above-mentioned gentlemen began to discuss where they should go to make the test experiment. The inventor did not want to have any say in where the test was made. He wanted the test to be made at a place selected by them. At last, the three men decided to go up Emigration Canyon, as there are no power lines there. After driving about four miles up the canyon they selected a place. Then they changed their minds, selecting another place a few hundred feet further up the canyon.

Mr. Judd stayed in the car because of an injured foot, while Mr. Nebeker and Mr. Adams put up the antenna and ground. The inventor then took the device out of the car and connected it to the "antenna and ground." The switch on the device was opened and closed many times as in all former experiments, but no light appeared. The device was then "tuned in" as Mr. Judd had witnessed in previous tests. Then the switch was closed and the lights came on. The "antenna wire" was momentarily disconnected. The lights went out but came back on when the "antenna" was again connected to the device. The same thing happened when the "ground wire" was disconnected and then reconnected. All this with Mr. Judd hopping around on one foot, he having gotten out of the car when the tuning process was started. All three gentlemen were very well satisfied and pleased with what they saw. It was dusk when they left the canyon.

The following is a letter describing a similar test performed at a different location

Dear Mr. Cooley,

This letter is being written for your information. It is a record of the electrical demonstration made October 29th, 1926, by inventor T. H. Moray for Attorney Judd, Mr. Knight and myself.

As prearranged, I met Moray and Judd at the Moray laboratory about 7:10 a.m. on October 29th, 1926. We carried the electrical equipment in my car and left Mr. Judd's car in the Moray parking lot.

I remember that the odometer registered 19 miles at Charleston and 26 miles as we left the last electric power line near the mouth of Daniel's Canyon. It registered 52 miles when we stopped to do the demonstration. Thus, we were 26 miles from the nearest power line and also 26 miles from the nearest one wire rural telephone line.

Moray requested that we select a place near a stream of water so that the ground pipe could be sunk in its bed to be more effective. The ground in the mountains, at this time of year, was frozen. We stopped at a place about 10 miles southeast of the Daniel's Strawberry summit and about 200 yards west of the main road to Duchesne. This location was almost due east from what Mr. Knight called Haystack Mountain. It was perhaps ¾ of a mile east of Strawberry Lake on a little stream that made a zigzag course through a gently sloping grassy flat.

The antenna wire was put up without any aid or instructions whatever from Moray, as it had been "balanced." Moray did suggest that the wire be stretched tighter to prevent so much sag at its' center. This was done and the wire then appeared to clear the ground by 7 or 8 feet at its lowest point.

Operation of the R.E. device;

The balanced ground rod was pointed at the end to make it easier to drive into the ground.

The antenna wire was insulated from the poles with two quartz glass insulators about six inches long. A piece of wire about two feet long connected each insulator to the poles. The lead-in wire was fastened to the antenna at a point about 10 or 15 feet from the east pole. I helped Moray solder the connection where the lead-in wire was fastened onto the antenna wire. I also helped him solder the ground wire to the rod. I stepped the distance between the two antenna poles and estimated it to be 87 feet as I took 29 steps intended to be three feet each.

Moray took his electrical equipment out of the automobile and placed it on the running board of the car. Two dry boards were laid on the ground and a rubber mat from my office was placed on the boards for Moray to stand on. This was as a precaution against electric shocks. The running board was hardly large enough for the equipment so we took the seat cushion out of the front seat and placed it on the mat. Moray transferred the equipment to the seat cushion and connected it up there.

Very light snowflakes fell occasionally and a tarpaulin was hung over the top of the auto doors to protect the equipment from getting wet. When all of the wire connections were made and the device synchronized in resonance by Moray. It was just 1:05 PM by my watch. Before "tuning in" he closed the switch but no light appeared. After "tuning in" for slightly more than 10 minutes the switch was closed and the light appeared immediately. It was slightly after 1:15 PM by my watch. Moray closed the switch two or three times before and during the tuning operation but no light appeared until perfect "balance" was established.

While the lights were burning the antenna lead-in wire was disconnected from the apparatus. The lights went out. When reconnected again, the lights reappeared. Moray disconnected the "ground wire" and the lights went out. He then reconnected it and the lights appeared again.

E. C. Johnson of Salt Lake City, Utah signed the above letter.

Mr. Nelton Welling wrote this letter, describing yet another test

Your interest in the Moray invention to take electrical energy from the "air" and make it usable for light, heat and power purposes is the reason for this letter. It describes a demonstration that I saw of his device on Saturday, February 21.

A dozen people were present, including Paul Harsh, Mark Yuri and Mr. Ferguson.

I first witnessed a demonstration of this device three months ago. Since then, the cabinet containing the machine has been simplified and improved. It was quite apparent that there was no possible faking of the power produced.

The tuning device was improved. The time required to bring in the energy was shortened from five minutes to less than a minute.

The operation was as simple as tuning in a well-equipped radio set. A lady who witnessed the demonstration for the first time also performed this tuning. She operated the device as easily as Dr. Moray himself did. This was after she had seen him "tune in" the energy.

A pilot light on the cabinet first became illuminated. The switch was then closed, connecting a light rack with the current. Instantly thirty 50-watt lamps and five 100-watt lamps were brilliantly lit.

A regular, Hot Point flat iron was then connected without dimming the lights in the least. The inventor stated that the result would have been the same had one hundred lamps been used in place of the 35 on the light rack.

The lights and iron together were consuming more than four-horse power of electric energy.

On account of the brilliancy of the lights it was apparent that much more than ordinary voltage was going into them. The excessive heat, which developed in one spot, made me feel that they would soon burn out, but they did not.

I confidently believe Dr. Moray is on the threshold of perfecting one of the most amazing fundamental inventions of history.

Very sincerely yours,

Nilton H. Welling

The next document is a lengthy report written by T. J. Yates to the Secretary of Utah about Morays work

Dear Secretary of the State of Utah,

Many men of science have come from foreign countries and from the East and the West and have been shown demonstrations. Not one of them has been able to find any fault with what they have seen or heard. Names of these men will be furnished upon request. These men have had the device opened for their inspection. They have pronounced the experiments to be wonderful, that the current is high frequency, the color of the light different, that the device carries many times as much current without even getting slightly warm. Any other electrical device of like construction, known to man, would burst into flame if it were carrying that much current. They state that the "tubes used are far more powerful than anything known to science today." The drawings, circuits and theory have been pronounced by leading men of science as scientifically, electrically, mechanically sound and correct.

It is generally accepted now by science. Moray's device proves there is energy coming from somewhere, that such a field of energy surrounds the Earth.

As Moray explains it, the oscillator tubes pick up electrical oscillations through the circuit of the device itself. As stated, the Moray device picks up these surgings or oscillations of energy coming and returning to the Universe. It is tuned to oscillate in harmony (sympathetically) with the oscillations of the Universe just as musical instruments can be made to vibrate together. Every oscillation, whether large or small, is completed during the same interval of time, the heartbeats of life. The oscillations of the Universe are governed by the same eyelet of time and are completed during the same interval of time. As Moray stated years ago, these waves of energy have a regular beat note of time, coming and going like the waves of the sea. They are in a very definite mathematical order of time, coming to the Earth from every direction. They are stronger in the day time than at night, but always coming with a regular beat note that might be referred to as the Father of Time; the Sire of Gravitation.

This energy has a definite elastic rigidity and density, which is subject to displacement and strains. When the strain is removed, this medium will spring back to its old position and beyond, surging back and forth as the waves of the sea. It will continue to oscillate until the original pressure is used up. If the internal impedance is too great, there will be no oscillations. It will merely slide back in a dead beat to its unrestrained state. By cutting down the resistance to the minimum and by synchronous resonance (sympathy) of the device with that of the Universe, recovery will be quicker and quicker. Finally inertia will assert itself and lengthen the time of final recovery by carrying the recoil beyond the natural oscillation. Thus, the vibrations are prolonged by oscillation. When the recovery is distinctly oscillatory, resonance sets in. The oscillations will go on forever because they come from the Universe. These electric oscillations are not simple ones, but surges with a definite beat note.

One will ask, how can you get steady energy from such surging? Since there is a great amount of energy at such a terrific potential could not a steady flow of water be obtained from the surging of the sea?

The operation of the condensers need not be repeated here as they have been fully explained in the enclosed account.

It is not claimed that all of Moray's theory is proven. But it is claimed that the device works. The results are certain. In the absence of better explanations, Moray's theories are as good as any.

Moray explained his theory to a well-known and noted American scientist, who said, "You go in your theory back to the law of gravitation."

In this day and age, anything is possible. What was done with radiant energy has been called "radical." Nevertheless, of the great number of learned men who have seen and heard of Moray's work, not one has been able to disprove his claims, theories or discoveries. Some of these men are amongst America's foremost in science. They have spent from five hours to many days on the theory and claims and made test experiments. Hence, these further explanations of the Moray theory, on which he has spent his time from boyhood.

Fully realizing that whatever the difficulties in discovering new truths, there are still greater obstacles in getting them recognized. As Mark Twain once said, "It takes many years to get a new idea fixed in the human mind." One should not be long surprised at the attacks of some or at the exasperation of a certain number of worthy people. Not surprising is the silence of a greater number of the scholars who have heard of these experiments. It is hard for the average human mind to rid itself of inherited ideas, which so completely and unconsciously control our line of thought. Franklin, Faraday, Cavendish and others were unable to always express themselves so that their peers understood their inner meaning. They gave to the World their ideas in a form unintelligible to others of their day. Yet their ideas have since become known facts.

The theory described here is not new in the main, nor is it contrary to ideas that science has accepted today. It is however original with Moray in application. When Moray first advanced them years ago they were "killed" by those who heard of them before they got very far. Be that as it may, Moray has studied "radiant energy" and found a means of using it. Heat, light, power and energy are not things in themselves. They are sensations, or effects produced by this "cosmic power," directly or indirectly.

"ASTRONOMY," by Robert H. Baker, P.H. D. Professor of Astronomy, University of Illinois

Page 303:

Another problem relates to the apparent lavish expenditure of this radiation. Of all the energy that pours forth from the Sun, the planets and their satellites intercept less than one part in 200 million. The remainder spreads through interstellar space with little chance, so far as we know, of being recovered. The suggestion that the Sun shines only in the direction of material that can intercept it, may appeal from the point of view of economy, but appears to have little else to recommend it. It would seem that Nature is squandering its resources of energy so prodigally that it must end in bankruptcy. But we doubtless have at present, an imperfect account of the situation.

"FOUNDATIONS OF THE UNIVERSE," by M. Luckiesh, D. SS. Director of Lighting Research Laboratory, General Electric Company printed in 1925

Page 5:

In the far-off stellar crucibles, we see the same laws being obeyed as in our laboratories. Tracing down, to the almost infinitesimal constituents of the extremely minute atom, we find that apparently it does not exist at all. It is not even as the realistic matter that we have supposed it to be. There at its very foundation, it seems to consist of electric charges that probably simulate the motions of celestial bodies. It is becoming more and more certain that the apparent complexity of Nature is due to our lack of knowledge. As the picture unfolds, it promises a marvelous simplicity.

Pages 41-43:

The great success of the atomistic principle relating to the kinetic theory of matter, is one of the wonders of the modern scientific age. As expected, it has found other applications equally fascinating and promising. It is now being pressed further into the service of explaining the structure of matter.

Maxwell's Theory

When Maxwell (1873) propounded the electromagnetic theory of light (radiation), his achievement was epochal. The exact manner in which the radiant energy traversed space was not known. The next epochal event was the founding by Planck (1900) of the quantum theory. Here we have the atomistic principle applied to energy instead of being confined to the material of the Universe as it had been. In other words, in the quantum theory, we have the atomistic idea applied to physical processes. We now have the atom of matter, the atom (electron) of electricity and the atom (quantum) of action (a product of energy and time). Planck assumed the emission of radiation (from the Sun, a lamp filament, etc.), to occur discontinuously. He conceived elements of energy of equal magnitude; analogous to the equality of electrons, or atoms of a given element. Radiant energy is emitted at various wavelengths or frequencies that must be taken into account in the laws of radiation. Now, the physicist uses quanta as commonly as he does electrons and atoms and molecules. Bodies are built of molecules, the molecules of atoms, and the atoms of electrons (and protons). Here we see the atomistic principle applied to "material" (matter) and then to electricity (what shall we call it)? Finally, a physical process, the radiation emitted by the electrons, is divided into quanta. With such pictures of the Universe being constructed, we may cease to be surprised at anything, but our interest and admiration will grow.

One of the most marvelous relationships that has ever been revealed in the entire science of physics is that between light and electricity. Knowing now how to view the structure of atoms, this relationship is not quite so surprising. Half century ago, there was a total absence of knowledge, pertaining to the existence of electrons in atoms of matter. So, the sudden revelation, that light (and radiation in general) is an electrical phenomenon, was very startling and revolutionary. Even today those persons, who are unfamiliar with fundamental physics, find it difficult to believe that energy traveling from yonder star to the eyes, is electromagnetic in nature. But that has been amply proved. It is the atoms in those distant stellar crucibles that possess moving electrons that are emitting electromagnetic waves of many wavelengths or frequencies. Here on Earth, we have many 'receiving stations' that are tuned to certain ranges of wavelengths.

"RADIANT ENERGY," by Edgar Lucien Larkin (1903)

Pages 17-18:

Radiant here means proceeding from a center in straight lines in every direction. Energy is internal and inherent.

Professor Barker, "Physics," page 4, says: "Energy is defined as a condition of matter in which any definite portion may effect changes in any other definite portion." This was written in 1892 and discoveries since confirm it. Energy then, is a state of matter. Or rather, is it the result of a particular state in which matter may be when any observed phase of energy appears?

These two notions, matter and energy, or possibly one, are the sum total of all that has been found during three centuries of incessant research? This search has been in that portion of the Universe visible in a forty-inch telescope, armed with the most powerful spectroscope ever made.

It is the belief of the writer that all this space is saturated with inconceivably minute corpuscles. J. J. Thomson recently discovered these. These are doubtless either electricity in its ultimate refinement, or very closely allied to it, or its immediate carriers. The smallest particle of hydrogen has long been thought to be the smallest mass of any known particle of matter. But the corpuscles detected by Thomson have only one-thousandth the mass of the hydrogen atom. The Earth and Sun, all suns and dark bodies in space, all granular matter, moves through the primordial cosmic mass of electrical corpuscles as would a wire screen through water. The wide spaces in diamond, glass, steel, flint, or anything else, allow these "bodies smaller than atoms," as Thomson calls them, to pass through.

Larkin's Theory on the transmission of energy

From the definition of energy, it is the potential of the Universe. When matter is in a phase allowing it to be active, it affects other quantities of matter at a distance. The method of transfer is known to be by means of wave motion. Each impulse moves from the emitting to the receiving mass on a rigorously straight line. One continuous set of oscillations in this straight line is called a ray. Each negative or Thomsonian corpuscle makes a double vibration to and fro like a pendulum straight across the direction of the ray – i.e., at right angles to it. The corpuscle moves over and returns to the original position it had before the excursion. The corpuscles are negative and can be drawn out of their original straight path by the action of magnetism. So, the entire wave motion of the Universe is electromagnetic. This is what Maxwell prophesied forty years ago. Thomson fulfilled the prophecy.

After one corpuscle makes an oscillation across the direction of the ray and returns, the next does likewise and the next and so on. After the first corpuscle makes a swing, another distant from it 186,000 miles in the same straight line, will also make a vibration at the end of the first second of time.

"ATOMS AND RAYS," by Sir Oliver Lodge, Fellow of the Royal Society of Science and holder of five or six Doctors degrees from colleges, with honors from a score more. He has held offices of President in a dozen or more Scientific Societies. Printed in 1924

The term 'light' strictly speaking, means that kind of ethereal radiation which is able to affect the eye. But it is common knowledge that there are many other wavelengths of radiation besides those that effects the eye. It is not clearly known why the eye is sensitive to some kinds of ethereal radiation and not to others. That, no doubt, is a question for physicists and physiologists in collaboration. But the eyes of animals, insects and man, all appear to be sensitive to a limited range of ethereal radiation, which is therefore called light. Some kinds of radiation can affect a photographic plate. Other kinds can stimulate the chemical actions going on in the leaves of plants and thereby supply the energy needed for vegetable growth. Another kind, a rather deeper harmony as it were, supplies everything on Earth with warmth and by evaporating water contributes to most of the phenomena of weather. Other kinds, again, are omitted when individual electrons, traveling at a high speed in a vacuum, encounter the obstruction of a target. These kinds of invisible radiation are called x-rays. And, at the opposite end of the scale, great antennas emit another kind of radiation. These are the Hertzian waves employed in radio.

If describing these kinds of radiation as different, we are not speaking quite accurately. They differ only as treble notes differ from bass notes. They differ in rapidity or rate, or vibration or wavelength. They do not differ in any other essential particular. The longest waves are telegraphic ones, which may be a mile long. Much, much shorter are the x-rays, whose wavelength is actually smaller than atoms, and only expressible in billionths of an inch. This whole range of waves, travel at precisely the same speed. This is the only speed at which the ether is able to transmit energy. They are all of the same electromagnetic character. They are all subject to the same optical laws of interference, of reflection and polarization, which have long been studied in departments of physics.

Moray would qualify the above by saying there are speeds greater than the speed of light

Whatever an electric charge is, or is not, it is certainly a focus of energy. Imagine an ether vortex, containing the known mass of the electron and circulating with the velocity of light. The energy of this vortex would be equal to that of the electric field in the space surrounding the electron. This coincidence, if it were a coincidence, can hardly fail to have some meaning. Some thinkers are beginning to view the whole material Universe as being built up of ether in various states of self contained or intrinsic motion. These adjectives are intended to discriminate between rotary motion, like that of a top or a whirlpool and ordinary locomotion, or whiffling from place to place. Locomotion has not been attributed to the ether, which is the most stationary thing we know. It is perhaps the only stationary thing that exists, but it may be full of what is sometimes called "stationary motion." This is a paradoxical term, appropriate to the condition of a sleeping top.

Those who hold this view of the Universe are strengthened in their position by Einstein's expression of energy in general. It is well known that all ordinary energy, such as the motion of railway trains, or croquet balls, etc, is merely relative to the Earth, or to some other piece or matter. There is nothing absolute about it. But Einstein gives an expression for what could be called absolute energy, in which the only relevant velocity is that of light. All the phenomena of Nature, at any rate in inorganic Nature may be due to, this great ethereal velocity. It must appear in a form that enables it to appear to our animal derived senses. For the spinning motion itself is impalpable and beyond the ken of our instruments. It can be detected only when it partially exhibits itself as transmitted waves in the form of radiation.

All the light that we experience can be resolved into vibrations or tremors in the ether. That is how we first knew about the ether. But all electric and magnetic phenomena and therefore, all chemical activity are likewise known to be modes of manifestation of the ether of space. The complete manner and meaning of which have still to be worked out.

So the question arises, What is matter? Is that too a manifestation of some peculiar properties in the ether? We know now that matter is built up of protons and electrons. But analyzing these into their fundamentals, we find far more than a hint that they are but special modifications in the all-pervading ether. They are essentially resolvable into ethereal energy of a specific kind. Hence, we are beginning to think that matter itself is a form of energy.

Energy is one thing in the physical universe that directly appeals to us. We apprehend it under a great variety of forms. And it is becoming provable that what we call matter is one of those forms. Most of the known forms of energy are convertible one into another. The energy of motion turns into heat, as does the energy of electric currents, unless it is converted into the energy of chemical separation or electric charge. Conversion from one form to another, without loss, is the sign-natural of energy. The proof that matter is a form of energy will not be clinched until it can be demonstrated that matter too is convertible into other forms of energy.

Such a process has not yet been performed in our laboratories, or has it? Though it is believed to be occurring in the giant stars. The interior of stars is at an altogether exceptional temperature and pressure.

This constitutes a laboratory where results can be beyond the scope of our present manipulation. In the light from those stars we see some small residual outcomes of this production of energy at the expense of matter. In their motions, we probably see the same thing. That, which we ordinarily recognize as the locomotive energy of bodies, seems now to be overflow or surplus of the violent constitutional energy within. This energy, at present seems inaccessible to us, but is possessed in enormous amount by the very constitution of the atoms of matter. Fortunately, a few of those atoms have given us the hint. They have spontaneously emitted their energy. We call it radioactivity. It is only the heavy atoms of fission material and other substances at that end of the series, which still retain the property of spontaneous disintegration. The other more familiar atoms seem to have lost that power, and settled down into apparent stability and quiescence. These atoms show no obvious sign of possessing any such power. But to the eye of science, it is there. Means have been sought for getting at it.

Combination of atoms into molecules and the interaction of molecules generally have long been known to give rise to various forms of energy. Witness ordinary combustion and the power of explosives. **Simple atoms like those of hydrogen, can be packed together so as to form the more complex atoms of higher elements. This process will liberate vast stores of energy, much greater than could be obtained from ordinary kinds of chemical combination.** It is highly unlikely that this will go on spontaneously or uncontrollably or dangerously, under such conditions, as we are familiar with on Earth. They may be violent enough under the conditions in the interior of stars, including perhaps our Sun. But here, on Earth, they are traceable, guided and controllable. They will not run rampant and do damage, except by reason of bad or malevolent arrangements and then only on a relative small scale.

How soon energy of this kind may become commercial, no one can say. The practical way is by using energy from the cosmos; i.e., not by so-called fission material.

Another Testimonial

TO WHOM IT MAY CONCERN,

This is to certify that on the evening of March 16, 1929, along with Dr. Wilkinson, of Cedar City, I witnessed a demonstration at the laboratory of T. Henry Moray, Salt Lake City, Utah.

Dr. Moray claims to have invented an apparatus that will produce electrical energy without the use of a prime mover. This apparatus was demonstrated on this occasion.

1. Description of the Apparatus

The apparatus uses an antenna specially balanced or an aerial capacitor and a special ground wire. These were connected to the terminals of a switch. Two wooden boxes were placed on a table. On one of these boxes was a high-frequency transformer. In the other box were two sets of condensers, ten large ones in one set and ten small ones in the other set. There were two composition cylinders, each about 1 – 1/8 inches in diameter and four inches long. Each of these cylinders weighed about three or four ounces. In addition, there was another box approximately hemispherical in shape, about two inches in diameter and weighing about two ounces. There were also coils of wires and other equipment. These pieces of apparatus were connected by a number of wires.

Two of these wires were led out to the switch. One was attached to the blade of the switch and the other its' jaw. When the switch was closed, the antenna, lead-in, apparatus in the boxes and ground wire, were all in series.

The other wires leading out of the box were connected to six 100-watt lamps connected in multiple during part of the demonstration. A flat iron was connected during part of the demonstration, as well.

2. Demonstration

During the demonstration the apparatus was connected in series as above described, except that a small switch connected in series with the coil was left open.

Dr. Moray energized and synchronized the device in three or four minutes. The lamps were lighted and remained bright as long as the switch was left closed, which was about 60 minutes. He then connected an electric flat iron. In a short time, the iron was hot. When the "ground wire" was disconnected and then the lead-in was disconnected, the lights went out.

3. Objections people have made

I. That there is a hidden wire from the electric lighting current obtains the power.

II. That the power is obtained from batteries.

4. Tests

Before and after the demonstration I closed the big switch that connects or shorts the antenna and ground. I also made other tests. If the antenna or lead-in were connected to the lighting circuit this would have produced a short circuit. I further tested the device by closing and opening the switch several times to see if any sparks appeared. But there were no sparks. I placed my wet finger between the blade and the jaws of the switch and could not feel any electricity. I touched my hand to both sides of the switch and the wall to check for ground but could not feel anything. We turned the table over and examined it carefully for hidden wires but found none. With the apparatus all connected as when operating the lights the contacts with the switch were moved but produced no arcing. This indicates that the circuit was dead.

While the demonstration was being conducted and the lamps were receiving energy through the apparatus, the main switch, that controls the lights in the building, was opened. All lights on the house circuit went out but the lights on the Radiant Energy circuit were not altered. They were neither brighter nor dimmer at that time. Thus the lights could not have received their power from that source.

The condensers were thoroughly tested. The terminals were shorted, the positive to the negative. If they had been batteries they would have showed a spark. But no sign of spark appeared. I connected them to the electric terminals then tested them. After being charged, the large condensers gave a vigorous discharge, showing a brilliant strong arc and a loud sound. They showed a sudden discharge as condensers are supposed to do and batteries never do.

The small condensers were less vigorous in discharging. They displayed the same snappy discharge of a condenser and not how a battery discharges. These tests proved positively that condensers and not batteries were in the cases. Besides no batteries of such size, could produce such power. The boxes were completely emptied thus leaving no possible place for batteries to be stored. Besides the boxes were not large enough in order to hide batteries.

During the time that the lights were burning the connections with the big switch were moved along the switch and vigorous arcing occurred. Thus, proving that electrical energy was passing through this apparatus.

5. Conclusions

The electric lamps received energy from some source. During the demonstration, which lasted for more than an hour, the lights were brilliant at all times, just as bright at the end as at the beginning of the demonstration.

The lights were a different color and brighter and whiter than those on the house circuit. The electric energy that lighted the lamps and heated the flat iron was not received from the house circuit.

One is therefore forced to the conclusion that the electric energy was received from some other source. As difficult as it is to understand, with our present knowledge, the only conclusion that can be drawn from the demonstration is that the energy was received by and through the apparatus as claimed by Dr. Moray.

T. J. YATES, KE N.E.

This next letter is from Murray O. Hayes Ph.D.

To all whom it may concern,

It is now more than two years since I first became acquainted with Dr. T. H. Moray and the work he is carrying on. In that time he has demonstrated inventive ability of an exceptional order.

Perhaps the most wonderful of his inventions is a device whereby he is able to draw electric power from the Cosmos. This energy is not derived by induction from power lines, as has been suggested by some, nor is it derived from radio stations. This has been demonstrated by taking the apparatus more than 50 miles from the nearest power line and over a hundred miles from the nearest radio station. At this location it operated just as well as anywhere else. This device was subjected to an endurance test in which it was operated continuously for a week. During this test a 100-watt lamp was lighted simultaneously along with the heating of a 575-watt standard Hot Point flat iron, making a total of 675-watts. It is very evident that no batteries could sustain such a current drain as this. Besides the current is high frequency.

He has also invented a very sensitive sound detector whereby it is possible to hear conversations carried on in an ordinary tone of voice, at a distance of several blocks.

He has also worked out numerous radio designs that eliminate many of the parts now considered necessary for good reception. Yet, there was no apparent diminution in quality or volume. In fact, there was a notable elimination of interference from static when some of these designs were used.

He has devised a means for measuring with some degree of accuracy the energy evolved during mental activity. His device shows variable deflections of a sensitive galvanometer needle that appeared to be related to the rigor of mental activity.

There are a great many other equally remarkable things that he has done. For example, reducing old rubber from truck tires to the state of a viscous fluid. This fluid is readily vulcanized without the addition of a smoke sheet as is necessary with other processes. He also created a high frequency therapeutic device and numerous other devices, which show great ingenuity.

Murray O. Hayes Ph.D.

This letter is addressed to Mr. Lovesy is from Murray O. Hayes, Ph.D.

Dear Mr. Lovesy,

As promised during our recent discussion, I am writing about my acquaintance with the construction and operating principles of the Moray device for utilizing cosmic energy.

You are already aware that I have seen many demonstrations of what this mechanism will do. Also, I have seen the parts of which it is built. Recently Dr. Moray has shown to me the wiring diagram of the device. I can find no inconsistencies in it, not anything that does not appear to be logical and sound. While this device appears to be very complicated, when looking at the machine, it is in reality very simple in essence. It is based on reorganized laws of electricity, when all is explained. There are many features which appear to be incidental, but they are in reality of basic importance.

He has also shown to me and explained the detector that his device uses. In this he has applied a fundamental principle of electric circuits which, I believe, would not have been noticed unless pointed out by him. This detector also has numerous features which appear incidental but are the heart of the matter and of first importance.

In my own home he connected his detector into a crystal set for receiving radio in place of the crystal. The reception was better than with the Erla crystal, though the antenna was merely one of the bell type. He also took a lump of lead treated according to a process of his own. He used in it place of the crystal and got wonderful reception of radio signals. They were loud enough, in fact, to operate an old fashion horn speaker of the type put out of RCA about 1923.

I was recently present when an electrical engineer representing the Russian government was given a demonstration of the energy machine. He at first said that the amplification of radio waves accounted for the output energy. However, it would be a real achievement to amplify such waves sufficiently to light six one hundred-watt lights at one time. This is in addition to heating a flat iron of the standard five hundred seventy-five-watt type. When engineer saw the inside of the device, he admitted that it could not have been radio waves. He remarked many times, "It is very interesting."

This machine has been operated in my presence so many times, under so many different conditions of weather and of Season that I am positively convinced that it is what its' inventor claims it to be. I also believe that its' commercial adaptation is feasible. I believe that Dr. Moray has explained everything to me without reservation. I am sure that this is a revolutionary and epoch making invention.

Sincerely yours,

Dr. Murray O. Hayes

Patent Correspondence

Dear Henry,

For your information, I wish to report on the matter of your radiant energy machine since coming here.

We arrived here Friday, July 10. On Monday, July 13, I spent the whole day in the search room of the Patent Office. I examined every patent issued by the U. S. on devices for the reception of radiant energy. Most of them were so obviously dissimilar to your invention that they did not consume much time. Not one is there which shows, on reading, even the remotest resemblance to your radiant energy machine. Not one mentions such an idea.

Neither is there any patent that suggests anything like your oscillator tubes. I feel perfectly safe in saying that there is not one chance in a hundred thousand that the examiner will find any disclosures that will restrict your claims. I have always felt certain that you would obtain broad protection on your radiant energy invention. But now I know it for certain.

You may use this letter in any way that you see fit.

Very truly yours,

Murray O. Hayes

Thomas J. Yates, E.E., M.E, wrote this notarized letter

TO WHOM IT MAY CONCERN,

I witnessed a demonstration of the apparatus invented by Dr. T. H. Moray by which he produces electrical energy. A report of that visit has already been made.

I now have, about two years later, witnessed a second demonstration of the same device; some changes in the apparatus were noted. A great improvement was made in the performance. The condensers, coils and other parts, noted at the previous test, were now in one small box about 10 x 10 x 30 inches. A safer and better means of starting the device has been devised. Once the apparatus is put in operation, it will continue to charge itself.

The lamp rack that formerly held six 100-watt lamps has been replaced. The new rack is larger and holds thirty-two 50-watt lamps, three 100-watt lamps and a receptacle to receive an extension plug and cord. On the other end of this cord a 575-watt electric iron was connected. During this test, all of the electric lamps were lighted at one time. Their light was whiter and more brilliant than other lights in the room, which were supplied from the house circuit. When the lights were on bright, the electric iron was plugged in. There was no noticeable blinking or sudden diminution of the lights as in the usual house lighting systems when an electrical iron is turned on. The lights were as bright as before the iron was plugged in. The iron heated quite rapidly. In about 2½ minutes it was hot enough to be used for ironing.

I made a thorough and careful examination of the entire system to see if electricity could have been introduced from some other source. I inspected every part of the system, all wires were checked; the switch was removed and examined. Leads from the switch to the box containing the condensers and coils were checked. The box itself was lifted and examined. The leads from the box to the lamp rack were inspected. The lamp rack was lifted and examined, as was the ground wire from the switch to the water pipe on which it was grounded. Not an inch of space was overlooked where there might be any metal that would carry the power. I am prepared to say that no such connection existed from which power could be had from any other system.

A crystal radio set was connected to the lead-in wire from the antenna on one side and to the ground wire on the other. Perfect reception was had. If there had been power from other sources on the antenna or lead-in wire radio reception would not have been possible. Instead a loud humming sound would be produced. This was demonstrated that by connecting the radio set to the house lighting system.

When Moray's system was working, the lights were burning bright. The terminal attached to the antenna was disconnected. A vigorous arcing occurred and the sparks jumped over an air gap as long as eighteen inches. This would indicate that the power was high voltage. The nature of the sparks indicated a high frequency current.

I do not understand the principle by which Dr. Moray's device produces the electric energy. The condensers and the coils of wire are common. The cylinders called "oscillators" and the small conical shell called the "detector" are the only things not commonly known, but the system works. It produces electric power in abundance and does all that Dr. Moray claims for it.

I do not own any stock or interest in Moray's work. My only purpose in issuing this statement is in the interest of the advancement of science. I consider this development a great advance in the science of producing electrical energy.

Very truly yours,

In witness to the above I hereunto sign my name.

(Signed) Thomas J. Yates, E.E., M.E.

STATE OF UTAH COUNTY OF SALT LAKE

Thomas J. Yates, being first duly sworn, deposes and says that he has read the foregoing statement and acknowledges that he wrote and signed the same as above set up.

(SEAL)

Thomas J. Yates

Subscribed and sworn to before me this 18th day of December 1930.

My Commission expires R. J. Chapman May 7, 1934 Notary Public – residing at Salt Lake City, Utah.

This is a letter addressed to Moray from W. H. Lovesy

Dear Henry,

I have handed you the original letter from Murray O. Hayes, in which he described being shown and having explained to him the wiring diagram of your R.E. device. Also the fundamentals of the detector were explained to him. In that letter he stated plainly these fundamentals would not have been noticed unless pointed out by you. At the same time, he had become familiar with all of the details of the construction of your device for utilizing cosmic energy. He added that you had applied only fundamental principles of electric circuits.

There is attached a second letter containing details of Mr. Hayes educational record.

I made the memorandums on the face of these two original documents at the time I was consulting with Murray O. Hayes in my office. At the time he definitely advised me of being shown every detail of your invention. Mr. Hayes stated that he could make one of the machines himself from the information that had been given him.

Murray O. Hayes made similar statements to me several times. I have made repeated requests that he makes these declarations. Namely that he had been shown every detail of the invention. Perhaps these repeated requests gave him the impression that I had a doubt about the invention.

Personally, I have never had a doubt. But I thought that only you held the real detailed secrets of the invention. I had a conference in New York with Dr. Harvey Fletcher and Dr. Carl Eyring at the Bell laboratories. I agreed with them to ask you to give the details of your invention to Murray O. Hayes. The purpose was to determine if he could duplicate your machine. In every instance his answer was emphatic and to the effect that he could do so.

Yours truly, W. H. Lovesy

This letter is from Geo. R. Pyper

To Whom It May Concern,

I have worked in electricity all my life. I was with the Utah Power and Light Company for thirteen years and worked in all departments including sub-stations. I have been with the Kearns Corporation for over seventeen years. I have been in charge of all the electrical work for the Tribune and Telegram Publishing Company and in the Kearns and Tribune Buildings.

In last December I witnessed a demonstration at Dr. Moray's laboratory of his electrical marvel box. He let me see inside this box. There was a H. F. transformer, some of his cold tubes and some condensers. Dr. Moray connected this box to a special balanced aerial and ground wire from outside the building. Two of us held a counter poise antenna attached to glass insulators in the room. When he connected the box to this counter poise antenna, I saw the same results as with the external aerial.

During this demonstration and while the lamp and appliances were operating, I shorted the aerial and ground wires. There was no spark; it just turned off the power from the box. I then took hold of both of these wires and felt nothing, they were both cold.

He then took a larger box, about 18 x 30 x 15 inches and connected it to the outside aerial and ground wire. From this box he lighted about fifty 100-watts, 120-volt lamps, ran a small motor specially wound at great speed, an original electric iron and a 500-watt glow heater.

Dr. Moray then disconnected the appliances and lamps and attached two long wires to the box. We pulled the main line, Utah Power and Light Company service switch for his building. We attached the wire from the box to the building side of the switch. He lighted his building and heated iron heaters. In fact, he did everything the Utah Power and Light Company service would do except run motors that I understand have to be specially wound.

Standard globes were used. They seemed to give a softer whiter light that was more like daylight.

I am satisfied from my experience in electricity that there was no fake of any kind such as concealed batteries or wires. Everything was in the open so I could see every operation. I did not see the inside of the larger box.

It was a very remarkable demonstration and one that I will always remember.

Geo. R. Pyper

SECTION SUMMARY

Whenever a fairly large amount of oppositely charged ions coexist within a small volume of space extensive recombination occurs. The resulting accumulative radiation can add up to an intense, constant wide-band frequency. This phenomenon prevails around many stars in our own galaxy and is concentrated around nebulas and star clusters. Indeed, this is a very old source of energy. All we have to do is attach our machines to this "wheelwork of nature."

SECTION REFERENCES

"The Sea of Energy In Which The Earth Floats" by T. H. Moray, 5th Edition 1978

The Eyring Research Institute, before Henry Moray died, was working on "Direct Energy Conversion Systems." This involves using radioactive material in conjunction with the quartz junction. p. 89

In 1942, shortly after World War II began for the United States, Henry Moray attempted to rebuild a radiant energy device. He used the remaining bit of what was known as the "Swedish Stone." This material limited the amount of power that his device could draw. Consequently, in the larger unit, he developed a second detector that forced him into extensive research involving nuclear materials and radioactive reactions. He became deeply involved in the study of synthetic radioactivity as described by Gustave LeBon in his book, "The Evolution of Matter." p. 186

Others may discover Direct Energy Conversion Systems using synthetic radioactive materials. Bell laboratories have made millions of dollars from semiconductors, though no credit has been given to Henry Moray. p. 190

This is from a speech given by T. H. Moray on Jan. 23, 1962 at the Valley State College Northridge, California

It is now estimated, because of present advances in dielectrics that a 100-lb. unit can be made to deliver 300KW. That is gross weight, not net weight. p. 11

"The Sea of Energy In Which The Earth Floats" 4th Edition 1960, by T. H. Moray

Nikola Tesla was not referring to so-called atomic energy or nuclear energy but to the energy that is continually bombarding the Earth from outer space. Call it cosmic, or what one will. p. 1

Enough energy is coming to the Earth to light 1,193,600 one hundred-watt lamps for every human being alive today. No fuel of any kind will be taken. Energy can be "picked-up" directly by great ocean liners, railroads, airplanes, automobiles or any form of transportation. In addition, heat, light and power can be available for use in all kinds of buildings. p. 1

Electrons are spontaneously being emitted from the nuclei found in Nature. Every new discovery on the subject bears out the claim that all "space" is filled with energy containing millions of amperes at very high voltages. p. 89

In the case of R. E. devices, a different effect is established. The oscillations from the Universe are trapped by the R. E. valve and continue to enter the circuit as the waves of the sea beat upon the shore. p. 92

Pellets were made of a mixture of the **Moray lead** that withstands heat over 1800°F. Using pure germanium mixed with bismuth, iron sulfide, triboluminescent zinc and certain other impurities **including the Moray fission material,** he obtained a substance that had wonderful properties as a detector or valve for radio signals. p. 128

With this germanium combination alloy used as a detector, it was found that radios would operate without batteries or any source of power other than that obtained from the **radio transmitting station.** p. 128

To make this special R. E. energy valve, he used a lump of lead (Moray lead). It was treated according to the process that he has discovered and got wonderful reception on a radio. p. 129

"Radiant Energy" 3rd edition by T. H. Moray, 1945

This energy, or as Dr. Moray explains it, these oscillations of energy, are picked up by the device through the oscillators, or neutron bombardment. p. 8

In reference to electrons, neutrons, protons and ions: It is my theory, in using these terms, that they are the energy of the Universe. p. 17

My device oscillates because of the oscillations of the Universe caused by the disintegration of matter. p. 18

Radiant Energy 2^{nd} edition by T. H. Moray, 1931

As far as atomic energy is concerned for heat, light and power, it is and always will be nothing more or less than an expensive, dangerous, glorified steam plant or an equally dangerous thermoelectric device. The process involves breaking into the lines of force of the radiation field that surrounds the reactor to capture energy. Such a plant, no matter how efficient, never is the complete answer to the World's energy problems. Costs and weight will always be a great problem.

Any nuclear fuel, even the most "super nuclear pile reactor," or what have you, is, and always will be, just another way to operate an energy plant from any heat, light and power viewpoint. p. 1

When Moray used the word "Universe" he was often referring to the atom. Moray refers to cosmic energy that relates to both "stellar space" as it does to "atomic space." p. 61

The facts involved are the same in both the radio receiving set and this device. The nature of the mechanism, however, in one differs greatly from the other. The radio receiving set receives transmitted energy waves out of the air and transposes them into sound waves. The R.E. device receives oscillations from the Universe, and transposes them into electricity. p. 13

If the frequency is raised high enough, molecules will separate and the atoms are freed. Raise the vibration of the atoms still higher and higher and they will resolve themselves into the original elements of which all matter is constituted. p. 15

Cosmic rays are constantly creating radioactive carbon. The fusion of small atoms together to make larger ones gives off more energy than so-called "splitting" of the larger uranium or plutonium atoms. The uranium energy release ratio is only 1 to 1000 – that is only 1/1000 of the heavy atoms are changed in the uranium "atom splitting" process of the atomic pile. p. 60

11 April 1990

Arthur Glenn Foster
Principal Engineer wrote:

There are some interesting side details. "We" (a group of us in government and industry, loosely coupled) were pursuing "Project X". We had a contract to process some of the Moray "valve," fine-ground, "Swedish Stone" into pressed "detector" pellets. The pellet material was doped with a tiny amount of unpurified radium reduced from U238 yellow cake.

The pellets were subjected to a huge number of millibars of pressure by a tetrahedral press used for manufacturing artificial diamonds. This technique was developed and patented by Dr Tracy Hall after he left GE. When a certain critical pressure was reached "something" in the material "flashed." The electric pulse produced was so violent that it burned out the 2000-amp carbon-die heater power supply, blew the main breakers in the building and blew the power line transformer on the outside power pole!

My Radiant Energy Research

Whenever radiation from a radioactive substance ionizes atoms, electrons are emitted. The electrons almost immediately recombine with the positively charged atoms that expelled them in the first place. Charge equilibrium occurs at the exact moment of recombination, along with electromagnetic oscillation. A by-product of this phenomenon is called **ionic oscillation**. Radioactive particles will again separate the newly recombined atom. In fact, any electrically neutral atom will lose electrons when exposed to radioactive matter. The atom that is left behind becomes a positive ion. This process of ionization and recombination is a continuous cycle as long as the atom is exposed to a source of ionizing radiation.

Whenever a fairly large amount of oppositely charged ions coexist within a small volume of space, the accumulative radiation from recombination can add up to an intense, constant wide-band frequency. This phenomenon prevails around many stars in our own galaxy and is concentrated around nebulas and star clusters. Indeed, this is a very old source of energy. All we have to do is attach our machines to this "wheelwork of nature."

What has just been revealed to you here is the final secret to harnessing the very wheelwork of nature. Ionic recombination of the decay products of radioactive isotopes will produce intense surges of electromagnetic energy. More often the wavelengths created are in the infrared (thermal) range. However, the wavelengths generated can also manifest within the radio frequency range or even far into the **gamma** end of the electromagnetic spectrum. They can even be made to manifest as free electrons. What does the decay of radioactive matter teach us about the nature of energy?

Under the right conditions, radioactive particles can be made to generate intense surges of energy in the radio frequency range. Tune into this energy with a tank circuit that will resonate with it and you have yourself a powerful source of electrical power.

To the best of my knowledge no person has ever harnessed radioisotopic energy using the process that I have just explained, with the exception of T. H. Moray and myself. There is not a patent to be found that even closely resembles it. Radio astronomy only gives us hints about these **"ionic oscillations."**

Many radioactive isotopes could be used to generate electrical power. However, the real power behind these isotopes is the radon gas that they release. I have pointed this out many times in my writings, lectures and articles. Polonium can be cheaply manufactured by bombarding the metal bismuth with a source of neutrons.

In United States Patent 2,728,867, it is stated that each gram of nuclear fuel that is undergoing fission gives off around twenty watts of power. In comparison, one gram of **polonium** will generate about one hundred and forty watts of power. This is **seven times** more energy than what is available from a conventional nuclear reactor!

If polonium is made to generate surges of intense electron oscillations then it becomes a powerful source of radio energy. A simple **ion valve**, or call it what you will, can be used to generate these oscillations. They in turn can be directly converted to electrical power. This unique valve is shown in **Figure 4.** Before it can function it must be connected to a source of high-voltage. In order for electrical energy to be extracted, it must also be connected to a proper circuit. One such circuit is detailed in **Figure 5.** The electronic circuit shown is basically what is required for this conversion. Many additional stages can be added for more power. Many other circuit and component configurations can also be used but the fundamental conversion principle will remain the same. The circuit and components shown in this book will give you the general idea of the principles involved.

The actual mechanics and electronics of building and validating a radiant energy prototype are relatively simple. It is fun and easy. Moray's devices used a detector that was ionized by radioactive impurities. However, radioactive material need not be used, from what we now know.

Those involved in building prototypes, must first confront some serious issues before beginning. I will try to enumerate a few pitfalls and make descriptions as clear as I can. This will fortunately and blessedly push some of you into action, but for others it will be viewed as an impossible challenge.

What are the most important assets for beginning my research?

1. Dedication
2. Motivation
3. Passion
4. Do instead of just theorizing.

What is the second most important thing?

The lone wolf researcher will need a lot of skills if their project is to be successful. Among the most valuable skills are those involving electronics technology. Plus, some familiarities with machine shop practice and materials. A good sense of organization is important. Being able to stand-back and observe the big picture, along with a lot of plain, good old common sense; are necessary skills to have. The "hands-on-imperative" must be at the very core of your efforts.

What if I have few tools and skills but have the dedication?

Then you need to have some cash, the green stuff. You will have to buy the skills, knowledge and time of others. You can farm out electronics and machining chores but it will be expensive. The more that you can do for yourself the better off it will be for you in the long run.

A fully equipped, skilled, advanced amateur radiant energy experimenter might slip by for about $300.00 for everything. If you have only a few tools hanging around then a proof of concept prototype might cost you around $500.00 because of the extra tools that you will have to purchase. Later you can build a more powerful prototype to replace the proof of concept design. Your basic working design will not have to be replaced. You can add more components as your research progresses. Simple dedication goes a long way. Watching, paying attention to details and doing it right the first time; are all very important. With this borne in mind, you could complete a powerful prototype for around $5,000.00 that could provide power for the average home. However, it is not now my intention to instruct you on how to build a home power unit. This book was written so that you may validate the technology; refinements still have to be made.

Are there any dangers involved?

Yes, of course there are! There are a number of ways to wind up in an early grave! Most of the lethal dangers can be avoided with **skills**. Read first and do second. Reference books and a solid, broad-based scientific library are your true assets. Access to the Internet would also be very helpful. Know the danger zones in the various disciplines that you are going to come across in your research endeavors.

The radiant energy circuitry is connected to an antenna and ground. A lightning strike could fry the device and burn down your house to boot. I take no responsibility for this. You build these circuits at your own risk. Take the time to install lightning protection on the antenna and ground leads. It could save you a lot of grief in the long run.

Some specific dangers include:

1. Crushed and mangled hands of the unwary or metal splinters in the eyes or skin.

2. There are burn and eye damage hazards.

3. Imploding glass bell jars, power valves, can scatter glass splinters at high velocity into face and body. Always use glass enclosures that can withstand the vacuum that is being applied.

Do you have what it takes to go the distance?

If you have what it takes and there is a burning passion for this research then you are probably ready to begin. This is not a place for a wimpy mentality. If you become frustrated or fail in your experiments, have the courage and good grace to realize how this came about. Make the effort to find out where you made your mistakes.

More than likely, you are going into this research with learning from books that have been written to hide certain facts from you. Do not expect results over night. Learn all that you can by careful observation, educate yourself, search out the truth first and let Nature be your guide.

There are political powers in this World that would not like to see us succeed in getting radiant energy power implemented. They know quite well that this energy source will liberate the global community. This mode of power generates not only power, but it will also generate hope for our decaying World.

Fundamental Validation Test Circuit

First of all, let me say, there is no fringe science involved with radiant energy power generation. This is a very old source of energy being extracted and harnessed in a unique, new way. I do not claim to have discovered anything new in nature. What I do claim is an improved method to convert radiant energy (atomic ions) into useful electrical power. Think of the radiant energy receiver as a type of electronic heat pump, only it is pumping ions, not heat. No laws of physics are being violated. No new laws are being implied.

Energy from the Dissociation of Matter

It is no secret that electrical current can be obtained by utilizing a couple of dissimilar metals. You can plunge a dissimilar couple into an electrolyte to obtain electrical current. This is called electrochemical energy. You can heat the junction of a pair of dissimilar wires that have been twisted together at their ends to generate electrical potential. This is called "thermoelectricity." However, what is not generally known is that you can also generate electrical current with plasma or a glow discharge as your medium between two dissimilar electrodes. This effect is the result of "triboelectricity." All these forms of electrical energy are caused by the dissociation of matter. This dissociation of matter is called "radioactivity" by the scientific world. All electrical phenomenon is the result of this radioactive decay.



Proof of Concept - Figure 3

- The "ion gate" in this circuit uses two .001mfd/20kvdc capacitors and two 20kv, 100-nanosecond diodes.
- There are varieties of electronic circuits that can be built to serve as ion pumps. The circuit used was designed by Robert E. Iannini and can be found on my website at: http://www.nuenergy.org/plasma.htm
- The ion valve in the above proof of concept prototype consists of a standard aluminum electrical conduit that is six inches in length. Its center wire is a 60 µm diameter tungsten wire secured with two half-inch PVC end caps.

Preliminary Ion Valve Validation

1. The output at the ion gate reads around 5KVDC using an analog high voltage test probe without the ion-regulator valve in the circuit. With the ion valve in circuit a 20KVDC reading is obtained with at least a 25% reduction in current being drawn to power the circuit.
2. The apparent energy gain in the above ion valve appears from the fact that when negative ions produced at the surface of the inner cylinder bombard the center wire secondary negative ions are generated. The negative ions, when accelerated with sufficient voltage are capable of dislodging (dissociation) other negatively charged ions by from the target against which they impinge upon; and a significant result is that the number of secondary ions may be several times greater than the number of primary ions. This has the effect of reducing power drain from the power supply. A.W. Hull observed this effect in a thermionic tube – HULL, Proc. I.R.E., 6, 5, 1918.
3. The ion valve can be used as a quenching (regulator) device that can provide clean sinusoidal currents to the output current.

Ion Valve Technology Explained

An ion valve that has been preconditioned with radon gas will uniquely add electrons to an applied high-voltage source. Inputted energy can be converted to a higher wattage electrical output. Using an ion valve in this embodiment the basic design has an axial, negatively charged cathode wire that extends the length of the cylinder. The anode is made out of an aluminum cylinder that is positively charged. Its cathode is a tungsten wire or rod that is negatively charged.



Ion Valve - Figure 4

In the diagram shown here negatively charged ions are formed at the surface of the center cathode wire. Positively charged ions are formed on the inner surface of the anode cylinder.

When a surge of ions flows through the valve they are added to the negative ions that sit on the cathode. They are now attracted to the positive anode cylinder. A few milliseconds later the positive ions on the surface of the inner cylinder are attracted to the negatively charged onrushing ions. When these negative and positive charges collide they neutralize each other generating electromagnetic oscillation. This characteristic has the effect of suppressing any **inductive kick back** seen from the loads that would normally flow back towards the power supply. Feedback from the loads to the power supply will result in wasteful heat losses.

I am fully convinced that my ion valve is a refined version of Edwin Gray's conversion tube described in his US Patents No. 4,595,975 and No. 4,661,747. **Chauncey J. Britten** also describes a similar component in his US Patent No. 1,826,727. Mr. Britten's component appears to be a prior variation of my ion-regulator valve design. Britten's valve was said to have lit up his home in 1930 according to a local newspaper article of that time period. Russian scientist **Alexander Chernetski** experimented with what appears to have been a type of ion-regulator valve. It is said that he got up to five times more energy out of his device than what he put into it. Plans were made to commercialize the invention but like the Moray, Gray and Britten devices it never became a commercial product.

The ion valve is not to be confused with a current rectifier. The ion valve prevents ions from flowing back to the power source. It is an 'energy dam' for the lack of a better description. Both negative and positive ions can flow through this component. The valve has a charge blocking effect. This is why Moray stated that "the valves are not rectifiers in the sense that they operate as radio valves in changing AC or HF to DC. Ion valves have an actual valve action in stopping the 'flow' of energy in one direction. Its function may be thought of as an oscillatory action similar to the waves of the sea, without rectification, from returning to the outer circuit." p. 209, The Sea of Energy, 5th edition. This rather cryptic language now makes more sense seeing first hand how my ion valve works.

The metal atoms in the cathode wire are bonded to each other through electron sharing. In another embodiment, to break these bonds the wire is given a positive charge and the cylinder is given a negative charge. The negative charge on the cylinder negatively ionizes any gas that contacts it. These ions rush towards the positive cathode. When an ion that carries an excess electron hits head on with a positively charged metal atom the electron combines with the metal atom. The absorbed electron passes along its kinetic energy onto the metal atom causing it to break its bonds with the atoms that were joined to it. This generates an intense burst of free electrons. The "sea electron" model helps to explain this effect. It is where metal atoms are bathed in a "sea" of valence electrons. If this model is taken one step further it can be shown that when metallic atoms are dissociated from each other excess electrons are released as pure electrical energy. This occurs because the electrons no longer take part in the intermolecular binding force that existed before the dissociation took place. The freed electrons will add amperage to the output circuit to which it is connected. Henceforth, the equation **I x E = P** holds true in this system. Where, "I" represents electrons (amperage), "E" electromotive force (ionic voltage) and "P" is the power generated.

The ion-regulator valve is an important component to the radiant energy converter. Add a grid to this valve and you then have an ion driven oscillator component. The ion-regulator valve can be used as a rectifier by heating its cathode. Electric motors can be made to draw less current from the power supply. Communication systems that take advantage of the ion valve as an oscillator could make present day radio transmission obsolete. Electrical power transmission and its generation could also receive a fresh new start. The possibilities are refreshing. It is an honor to offer humankind this technology. It is my goal to build and bring devices to market that will introduce new products that will better the quality of our lives.


Spiral Grid
Glass Wall of Tube
Filament Support (Springs)
Radon gas
Plate (cut away)
Filament
Plate Support
Grid Support
Filament Support
Wires Sealed here
Leading-in Wires
Glass Stem
Brass Shell Base
Cement Holds Tube in Base
TRIODE ION VALVES
A1
Prongs
g1
C1
7.5V
Filament Rheostat
Filament Battery
grid coil 2.5mH
2K
A2
g2
C2
7.5V
load
6-18mfd
3.8mH
P1
P2
7pfd
430 volts
2 turns #22
2 turns #22
350 VDC 1250 mfd
2N3055
Q2
400V 1 amp
27
1/2 watt
5 turns #22
270
1/4 watt
350 VDC 1250 mfd
5 turns #22
12 volts
TIP 100 Darlington NPN
Q1
12 to 240 volt transformer
2N3055
10K
470
1/2 watt
Q3
25V 2200 mfd

Radiant Energy Generator Concept Device - Figure 5

To activate an ion valve a vacuum is pulled, radon gas is introduced and a negative charge is applied to the cathode wire. The radon decays and deposits lead–210. This is a beta emitter and will supply electrons without the need for filament current.

T55 Taylor electron tubes were used in the above public demonstration device due to nuclear regulatory restrictions. Other radio vacuum tubes may be substituted. The energy output of this device does not give the slightest shock when the hands are in direct contact with it. Voltage meters will not respond to this type of energy. A 100-watt light bulb placed across the output will be brighter than if powered by conventional current. The filament within the light bulb can be seen to glow a cherry red and the gas is excited throughout. It is not a form of electricity that we are accustomed to experiencing. This type of electrical current should not be confused with what powers the circuitry of **Figure 5**.

The source of energy that drives the circuit is a wavelength of energy that T. H. Moray loosely called "radiant energy." To obtain power from this energy source a receiver must be built that will oscillate in harmony with it. This particular type of radiant energy possesses great powers of penetration, exceeding, in fact, the penetrating powers of ordinary x-rays. These rays have been proven to be harmless and may be used, if desired, to produce clear radiographs. They are antiseptic, germicidal, and are good tissue builders possessing wonderful healing powers. They will also effect photographic plates, produce phosphorescence in certain substances, render the surrounding air conductive to electricity and can produce heat in some materials.

WARNING!

Electricity is EXTREMELY DANGEROUS and caution should always be used when working around it. Please take the time to educate yourself sufficiently. If you don't understand something, investigate further before attempting it. Take liberal advantage of encyclopedias, science books, and other reference materials. This book was compiled for information purposes only. I do not control the materials used in construction, the methods of construction, nor the applications of the construction, therefore; I AM NOT RESPONSIBLE FOR DANGEROUS OR UNDESIRABLE RESULTS. Always use rubber gloves when working with high-voltages.

ALL SAFETY PROCEDURES MUST BE CAREFULLY OBSERVED
MEASURING HIGH VOLTAGE IS NOT RECOMMENDED

Disclaimer: *The author assumes no liability for any incidental, consequential or other liability from the use of this information. All risks and damages, incidental or otherwise, arising from the use or misuse of the information contained herein are entirely the responsibility of the user. Although careful precaution has been taken in the preparation of this material, no responsibility is assumed for omissions or errors.*

Edwin Gray's Energy System

Thomas H. Moray invented a high efficiency 6,000-hertz power supply. It turns out that Edwin Gray's power supply also produced this same frequency. Gray claimed that electrical equipment such as solid state radio; television and light bulbs would operate on this type of current.

The overall efficiency of the Gray device was said to be extremely high. From one of his company press releases we are told that it will power loads four times longer in comparison to a standard DC to AC inverter power supply. This particular press statement indicates that he was planning to market a device that put out a 6Khz frequency, as compared to the standard 60Hz frequency coming from the public utility power grid.

Both the Moray and Gray energy systems harnessed a very old source of energy in very unique ways. They could be the solution to our power needs by using an inexpensive renewable energy. The advantages over other systems are many. The World is indeed moving at a suicidal pace, we need this technology more than ever. It will light lights, run motors and electrical appliances.

When you put a high potential current across two separate elements, ionization will occur between them. The high voltage elements **12** & **34** develop a pre-discharge plasma glow between them. The charge polarity given to the tube **14** in the Gray circuit puts it into an **impulse mode.** When a glow pre-discharge is present in this mode no current flows. The tube **14** functions pretty much like a Geiger radiation detection tube waiting for an electromagnetic surge to trigger it into conduction.

Discharge occurs across the spark gap **62** once the capacitor **16** charges to the gaps' breakdown voltage. Once the arc is broken the capacitor **16** recharges, the cycle repeats and the cycle repeats so long as the batteries remain charged. This discharge current flows along the red wire shown in **Figure 6**.

Consider an electron moving through a magnetic field, whose lines of force are at right angles to its direction of motion. It is known that the electron is constrained to move in a circular path. In fact, if the field is made strong enough the electron may be forced to revolve in a circular orbit whose diameter is smaller than the field. If a magnetic field is applied transversely to the motion of the electrons, they may be deflected to such an extent as to prevent them from reaching the plate. Thus they are constrained to return to the cathode. A.W. Hall of the General Electric Co. was the first to use this principle in a highly efficient vacuum tube converter that he called a magnetron. The sudden discharge through the element **12** generates an intense electromagnetic field that collapses very abruptly. This discharges the energy stored in capacitor **38** in series with the load **36** and capacitor **16**. During this discharge cycle capacitors **16** & **38** recharge and in the same moment a powerful surge of electrical oscillations flows through the load **36.** The collapsing magnetic field in conjunction with the reappearance of the pre-glow discharge instantly generates a pulse train of electrical oscillations. This surge of power runs Gray's unique high frequency motor. The motor functions with extreme efficiency because DC resistance is reduced to a minimum and wasteful heat loss is practically non-existent in this system.


U.S. Patent
Apr. 28, 1987
Sheet 1 of 2
4,661,747
FIG. 1
48
10
38
40
26
36
20
18
28
A.C.
14
30
66
32
34
62
12
64
46
42
22
FIG. 5
16
24
44

Edwin Gray Energy System - Figure 6

1. The blue wires represent the high frequency current path that powers the load **36**.

2. The red wires represent the current discharge path that occurs when the spark gap in the Gray conversion tube **14** fires. Storage batteries **40** and **18** alternately recover the discharge energy through a double-poled switch **48**.

3. When the capacitor **16** discharges an intense oscillating high frequency electromagnetic field is generated through the "switching tube" and load circuit.

Treatise On Matter & Energy

Matter and Energy are one and the same…

Three Primary Particles

Atomic theory does not predict every reaction created by the various states of matter and of energy. There are principles in Nature yet to be revealed. Something has been missing from the over-all atomic picture of matter and energy. There are three primary particles that bring the elements into existence. Just as the colors red, green and blue combine to give us the entire rainbow, the same holds true of the three primary particles: protons, neutrons and electrons. The combination of these three basic primary particles is what gives physical mass to an element and its' unique characteristics. Its physical size, its mass, gives it a signature. This signature is given an "elemental" name.

If a given element is not in a kinetic state then it is said to be at complete rest. It is cold. The external forces acting upon it determine a particle's energy level. When struck by another particle, it becomes kinetic. It is this kinetic activity that we call heat. This heat or kinetic energy level may be raised by particles which impinge upon it that have higher kinetic energy levels. The "heat" of an element may be lowered by other elements that impinge upon it that have lower kinetic energy levels. This will cause the element to lose some of its heat. It is therefore "cooled." However, the elements fundamental make up is not changed. An element may acquire the kinetic energy level of visible light and still retain its fundamental properties. Its' signature is not changed.

Gamma Radiation

An atom that absorbs or expels neutron particles will ring like a bell. It emits gamma energy. Whenever an atom gains or loses neutron energy it generates gamma energy. Gamma energy is a disturbance phenomenon.

The only difference between natural and artificial gamma energy levels is their origins. Natural gamma rays are emitted from the nucleus of a radioisotope. Artificial gamma energy is generated outside the atom. Gamma rays and x-rays are often called photons. They have no mass and no charge and may be considered to be energy disturbances in space.

Wavelength

The kinetic energy level of the radiating element determines the wavelength of energy. A low kinetic level is represented by a long wavelength on the chart. A high kinetic level represents a short wavelength on the chart. The "speed of light" is therefore a relative term. Energy is contingent upon the matter that it impinges upon.

The x-rays begin at about the middle of the ultraviolet portion of the spectrum. These are called soft x-rays. Those that extend into the lower portion of the gamma range are called hard x-rays. Beyond this range, they are cosmic rays. These energy disturbances are called "photons." They are not particles. They are disturbances caused by the kinetic states of particles in motion. This energy spectrum proceeds in order of decreasing wavelength: sound, thermal, visible light, ultraviolet, gamma, and the cosmic rays.

Pair Production

If a photon has sufficient energy, its' energy may be absorbed by atoms. The photon interacts with electrons. This gives rise to a process called "pair production," in which the energy of the photon is absorbed by the atom.

Photo Disintegration – Gamma Energy

Atoms can absorb high-energy x-ray photons, those with energies above 10 MeV (Million electron Volts). Here, the electrons within atoms are raised to an excited state and instantaneously emit high-energy gamma radiation. This makes the atom receptive to nuclear transformation. This process is called "photo-disintegration."

1.02 MeV Energy Barrier

It has been calculated that when one electron pairs with another, 0.51 MeV of photon energy results. Since two electrons are involved in a pair production event, a photon must have at least 1.02 MeV of energy to separate them. A photon with less than 1.02 MeV will not produce a pair production event. Any energy in excess of 1.02 MeV is distributed equally between the two electrons.

Electrical Energy – Electron Cloud

An atom is negatively ionized when it gains electrons. The atom is positively ionized when it loses electrons. How can it be then that a helium particle expelled from radioactive decay is charged to millions of volts positive? This observation can mean only one thing, that the electron shells are really an abstract thought for mathematical calculations, when concretely the atom is a mixture of electrons, neutrons and protons. The electron cloud consists of thousands of actual electrons. It must be noted that an electron is approximately 1,830 times smaller than the mass of a proton. The scientific community has ignored this little fact. As an example it will take around 1,830 electrons to equal the mass of one proton in the hydrogen atom. So, it is said that there is one proton and one electron in the hydrogen atom. What really should be said is that there is one proton and approximately 1,830 electrons. However, it is much easier to state that there is one electron in the hydrogen atom for simplicity. The mathematical electron shell theory need not be modified to fit this reality. It is convenient to use the square root of the actual number of electrons that surround each nucleus, for day to day chemical formulations.

When electrons or negative ions rush towards a positively charged atom in order to reach equilibrium, it is said that an electric current is generated. This current is created by a particular energy state called "voltage." If a metallic conductor has electrical current flowing in one direction one end of the conductor has an excess of electrons. The opposite end has a deficit of electrons. All "electric oscillations" are a result of this phenomenon. Battery power, direct current generators, alternating current alternators, radio, microwaves, radar, electronic oscillators, metallic coils and condensers, electron-tubes, ion-tubes and transistors, magnetrons, klystrons, lasers, masers and molecular transitions; all carry these oscillations.

So then, what is electricity? This question has eluded the most able intellects throughout human history. Could this be because science ignored the fact that the electron in an atom is actually representing more than one thousand electrons, not just one? As observation shows, two states of energy exist, one "negative" and the other "positive." How could it be that there are two states, identical in their properties, opposite in character, both clinging to matter, both attracting and yet completely neutralizing each other? From this analogy, it is safe to say that electron differences create the effects of electricity.

Chemical Cohesion

Atoms are attracted by virtue of their differing kinetic phase relationships. Matter stays together because of this principle. Atoms are continually expanding and contracting in unison with their kinetic frequencies. Expanding particles are attracted to contracting ones and visa-versa. "Gravitation" might turn out to be a grand display of this phenomenon. Atoms will repel atoms only if they are in the state of coherent kinetic vibration. This occurs when atoms are vibrating in phase with each other. Coherence will raise energy levels. Differing elements will form "compounds" when their fundamental frequencies are in accord with each other. They must ring harmoniously.

Ultra Chemistry

The first law of thermodynamics describes the principle of the conservation of energy. It states that "energy is not created or destroyed; it merely changes form." The fact is that the creation or destruction of energy is a result of matter being broken down or built up. They both go hand in hand.

I strongly believe that the three primary particles were created at the beginning of the Universe and that they can not be destroyed. However, the good news is that to serve our needs we can artificially alter the elements, (cosmic soups) of these three particles, protons, neutrons and electrons).

I will dare to further state that neutrons not only reside in the "nucleus," but they also exist throughout the atom as a homogenous mix with the other primary particles. The most simplistic expression of the Perreault Atom involves the bold statement that neutrons reside in balance with the protons and electrons in the atoms. This concept applies throughout the entire Periodic Chart of the Elements.

Isotopes

Three hydrogen elements (isotopes) are known to exist that are chemically similar but have different weights. The three weigh differently due to neutron content. These are all hydrogen atoms. However, it is the neutron count in the atomic shell that determines the isotope.

It is clearly established that triple weight hydrogen (tritium) decays to helium–3. In this particular transformation a charged normal weight hydrogen element (protium) carries an excess electron in its shell. It can react with tritium and emit an electron as a by-product of the reaction. At this moment the electron is emitted at an accelerated rate and is seen as beta energy. This model will not alter the way we view chemistry, however, it should change how nuclear changes are viewed.

Gravitation

Each individual atom is at the center of it's own universe and has a unique resonant frequency that is representative of it's specific mass. Lithium for an example has a greater mass than the hydrogen atom and will vibrate at a lower frequency in comparison. Therefore, we may say that it is caught by earth's gravitational pull more readily and has more weight. This may help to explain how physical objects are attracted to the Earth.

Stored Nuclear Energy

Have you ever wondered about spontaneous radioactive decay? Is there a super charged state of matter? If an atom becomes ionized by either gaining or by losing electrons then why can there not be a nuclear ionization too? I hypothesize that atoms do become ionized on the nuclear level by gaining or losing neutrons. This may appear incidental but could be at the very heart of an ultra-chemistry. I say that it is highly likely that this very phenomenon is behind natural spontaneous radioactive decay and explains many unanswered questions in nuclear science.

Atoms can gain or expel neutron particles, some to a greater or lesser degree. Thorium can readily be transformed into a fissile isotope of uranium by absorbing neutrons. It is a known fact that thorium stores more energy than uranium, coal, oils and all other fuels combined. This represents a tremendous amount of stored energy. Transformed thorium could be our most economic source of energy. It is almost as abundant as the element lead.

It is only by passing from one state of equilibrium to another that matter can lose or gain energy, consequently emitting radiation. The notion that radioactivity originated in a peculiar chemical process was adopted and defended by Rutherford. "Radioactivity," says he, "is due to a succession of chemical changes." Research has found that this "succession" is due to neutron transformation.

Nuclear Transformation

Elements that absorb neutrons and become unstable are called "radioisotopes." When an atom absorbs neutrons it is seen as a "fusion" reaction. When an atom loses neutrons, it is seen as a "fission" reaction. All elements can "transform" into a radioisotope and visa-versa. Radioactive isotopes are unstable and will transform into stable elements. A radioactive isotope will eventually revert back to the original element on it's own accord. Radioisotopes are nature's storehouses of energy. We need not look any farther for our energy needs. Nature holds an inexhaustible supply.

Induced Radioactivity

When bismuth is exposed to radium, initially it becomes several hundred times more active than the radium. This is due to emanation that clings to the surface of the bismuth. Emanation is widely known as radon gas that will eventually decay to polonium. It releases more energy than any single natural element ever discovered.

If beryllium is exposed to radium, neutrons are generated. These neutrons will have penetrating power several times that of the most energetic gamma energies. This activity is due, not to an alteration of the inactive matter itself, but to an admixture of a very small quantity of intensely active matter. Is this the neutron? Could it be that a neutron is actually an inert monatomic gas? This would certainly explain a few gaps in accepted atomic theory.

I have found that "radioactive" matter can be electronically synthesized. I find that radioactive matter is simply in an atomically charged state. It has been recognized that when an atom gains or loses electrons, it becomes "charged." However, I have taken this one step further by suggesting that matter will also become super charged when it gains or loses neutrons. This super charge that the atom acquires depends largely on its energy state and the type of radioactive gas that it reacts with at the moment of contact.

Strange Nuclear Facts

Primary neutron particles and gamma energy levels are generated in nuclear transformations. This results in the atom becoming super charged.

A "chain-reaction" in radioactive matter is due to the concentration of excess neutrons. The greater the concentration of excess neutrons, the more accelerated the decay process becomes.

For example, if beryllium metal is added to radium metal, neutrons are expelled. These neutrons can be used to cause secondary nuclear reactions in fissile material. The beryllium becomes the nuclear trigger.

The energy released by the transformation of beryllium is estimated to be at around 50 MeV and that of boron nearly as large. The excess neutrons generated can be used to super charge atoms thus transforming them into radioisotopes.

Cold Fusion

Here is a "cold fusion" reaction to consider. Radon gas (a pure alpha emitter) generated from the decay of radium is deposited onto a beryllium wire. Beryllium will react with an excited alpha particle that will generate a "cold fusion" reaction without the need for excessive heat, as is the case for "hot fusion." The reaction that results is: the ${}_4Be^9 + {}_2He^4 \rightarrow {}_6C^{12} + {}_0n^1$ (cold fusion) mentioned above. This secondary neutron energy now can effect a reaction in nuclear fuels. Atoms need not be fragmented in this reaction. Therefore, this reaction is "clean." There are other examples but this formula will give you a general idea.

Alpha fusion is actually cold fusion. The end result generates neutrons from the production of fusion by alpha particle collision. A simple equation where mass squared by it's speed equates to temperature. This equation can be applied to a kinetically energetic alpha particle in my model. Simply stated, a fusion reaction occurs when there is a temperature differential between the alpha particle and the target that it impinges upon. It must also be noted that no new neutrons will result because the reaction consumes what it releases. This is cold fusion.

The over all reaction is 'cold' in the general sense; in contrast to reactions that produce excess residual heat. To site a cross correlation; a thermal heat pump will absorb hot particles right out of the cold air of winter. The average temperature is cold. This analogy can be applied to the alpha fusion reaction just sited. The particles involved are in the midst of relatively cool ones. The average temperature is cold. This is my justification for dubbing it a "cold fusion" reaction. You may still consider the reaction to be hot. In fact, it is in every real sense of the word. Even so, the term 'cold fusion' is a non-mathematical one. We can use it to denote the difference between reactions that result from a CERN particle reactor and those that are naturally directed by ultra chemical reactions. As you can see, I do not buy into what the textbooks say about what constitutes the nuclear verses chemical reaction. All reactions are chemical in my point of view. The sited alpha reaction is an ultra extension of chemistry. The textbooks have over complicated the "nuclear reaction" in my assessment and in doing so have fogged the truth in many instances.

So-called "cold fusion" researchers have overlooked the fact that the electrodes that they are using contain traces of naturally occurring radioisotopes. Alpha particle emitters such as Pt190 & Pt192 are two examples. What is an alpha particle anyway? It is a super charged helium atom is it not? Couldn't you also say that it is the atomic ash of nuclear decay? That is exactly what researchers are finding in their experimental cold fusion setups. Neutrons may also be generated as a result of a cold fusion reaction but we might not always detect them. If the neutrons generated equal the neutrons absorbed in the reaction there is nothing left to detect. In my opinion this is the signpost of a clean nuclear reaction.

Some Ignored Uranium Facts

1. U235 emits ultraviolet light. Galen Winsor[1]

2. U238 expels electrons most readily when exposed to a wavelength of 3000 Angstroms in the ultraviolet spectrum. H. C. Renschler[2]

3. The UV light wavelength of 254 nanometers (nm) is a catalyst to oxidation processes.

4. The 254 nm frequency of light kills viruses, molds and other pathogens by rendering their DNA inactive. It therefore disinfects drinking water.

5. The human skin is reddened (erythema) and is most sensitive to the wavelength of 3000 Angstroms (254 nm range). Hauser and Vahle[3]

SECTION SUMMARY

Bombardment by alpha or beta particles does not "disintegrate" atoms. Rather, this bombardment goes beyond normal chemical changes. Energy is transformed by neutron absorption or by neutron emission.

What other discoveries await us? The future is indeed a glorious jewel to behold. Will we continue to follow the path that leads us further away from this great storehouse of energy?

Alpha Fusion

The Department of Energy (DOE) has hindered the development of this technology by holding fast to its' bogus restrictions on radioactive materials. I allege that they fear a miniature, clean atomic power source that will deny the Department of Defense its supply of weapons-grade plutonium.

The DOE’s 45-year old H-bomb fusion program sucks up all government fusion funding. The DOE’s fusion projects are located at the Princeton University Plasma Physics Lab. These projects are top-secret, cold-war research projects using fusion for massive production of plutonium and tritium for nuclear weapons.

The Princeton fusion reactor burns tritium, a radioactive fuel that produces deadly **neutron** radiation, 80% of its total output of energy. This reactor, if used in conjunction with a breeder reactor, is capable of "breeding" 100 times more plutonium than can be produced by a conventional utility reactor. This is a fuel machine for nuclear weapons of destruction.

Congressman George Brown, Chairman of the Science, Space and Technology Committee, had introduced a new bill, in early May of 1994. This bill would have allowed for clean, compact, "neutron-less" fusion energy technologies that would compete with the DOE’s weapons program. This bill was never passed!

In spite of resistance from the DOE against clean atomic reactions, the "Fusion Energy Research and Development Act" (Brown's bill) would have created an Office for Alternative Fusion Energy and a separate budget for Alternative Fusion Technologies.

A neutron free, atomic device could generate electricity at minimal cost. It would compete with any petroleum-based fuels. This would mean no more oil spills, among many other benefits that I have already outlined.

Dr. Bogdan Maglich was the driving force behind the neutron free technology and the alternative fusion bill. He discovered the **omega meson** and other particles. In 1961, his omega meson discovery won him and three associates, a citation from President John F. Kennedy.

Dr. Maglich invented the "Migma," a miniature reactor that demonstrated the principle of a non-radioactive nuclear reaction in a 6-cubic-inch volume. While most fusion reactions are radioactive, Dr. Maglich’s reactor utilizes a design that is virtually non-radioactive. In 1984, Dr. Maglich planned to demonstrate the magmas' energy capabilities. The tests were to be done in cooperation with nuclear labs in Russia, under the State Department's "Conversion of Peaceful Nuclear Research" program for Russian scientists.

Dr. Maglich had flown supporters with him to Washington to persuade the Congress to give the project an affirmative vote. The DOE and the nuclear-industry lobbyist defeated the vote. Humanity was on the brink of an energy technology that would have been compact, safe and almost zero residues except for the electricity that it produced.

A space shuttle full of moon dust would contain enough helium–3 to meet all the energy needs of the U.S. for an entire year. Dr. Maglich pointed out that nine grams of helium–3 are the equivalent of 1,000 barrels of crude oil. A Migma reactor could breed helium–3 from seawater. You do not need to go to the moon.

The Bechtel Corporation in 1989 subcontracted with Dr. Maglich to produce an engineering design of a clean nuclear reactor slated for a space power station. Dr. Maglich at the time was about ready to publish his completed design. The Defense Department (DOD) at this point stepped in and classified the plans before he could utter one word. DOD called his reactor "export controlled," a classification forbidding any written or verbal presentation of this invention to anyone except for government officials. This clearly violated an international agreement that forbids withholding information on controlled nuclear reactions. The agency justified this classification by saying that this type of research contains "ground-breaking work."

The bottom line is that **neutron free** atomic reactions do not generate weapons fuel. The DOE would stand to lose its funding for nuclear weapons fuel if non-radioactive reactors were to be commercialized. These groundbreaking designs would threaten all nuclear power plants.

In the final analysis, it is relatively simple. The alpha particle proves to be an effective energy source in inducing fusion when combined with the right material. We can safely come to the conclusion that through the proper conditions that the alpha particle can provide incredible amounts of power for our use.

Energy Released by Alpha Fusion vs. Uranium Fission

"Alpha fusion" is an amazing process. Here is a comparison of the energy released per atom of uranium that undergoes fission verses alpha fusion via neutron absorption.

$$\text{U235 fission} = 161{,}000 \text{ kWh/kg } (2\text{x}10^{8} \text{ BTU/lb.})$$

vs.

$$\text{Alpha fusion} = 1.68\text{x}10^{11} \text{ kWh/kg } (2.6\text{x}10^{14} \text{ BTU/lb.})$$

The potential implication of this alpha fusion formula staggers the imagination. There is room for unlimited innovation and creativity. Imagine having a device that could safely provide power for several decades without recharging. Sounds almost like science fiction you say? It is a scientific fact! Plutonium–238 is a non-fissile isotope that decays by **alpha particle** emission with essentially zero associated gamma emissions. This type of plutonium spontaneously produces about one kilowatt of energy for two kilograms of mass. This reaction will release alpha particles that can only travel a short distance before they are stopped. This process decreases slowly over time. After ten years the energy production is about 92 percent of the initial value. Even after 87 years the material produces half as much energy as it did when was first started.

When positively charged helium atoms (alpha particles) collide with the **electron cloud** that envelops another atom the positive charge is eventually canceled by these collisions. This is called "absorption." Atoms ring like a bell when impinged upon by alpha particles. This ringing state generates **x-rays**. The wavelength of this generated x-ray depends on the charge of the alpha particle and what type of atom it hits. If the x-ray generated has an energy level that exceeds 10MeV, atoms absorb it. In this case, the neutrons are raised to an excited state. They may be broken loose from the shells of an element or a neutron may be added to a shell. Gaining or losing neutrons via this process may create isotopes. We can efficiently do this by exposing atoms to alpha particles. This model clearly demonstrates that energy is transformed from one state to another. It is neither created nor is it destroyed.

Generally, the formation of a chemical compound is accompanied by the release of a definite amount of heat per unit mass of the substance formed. The burning of a fuel is a chemical reaction in which oxygen is consumed. The quantity of heat released when a unit of fuel is burned with oxygen is called the "heat of combustion." For the average coal, this value is from 7,000 to 8,000 calories per gram or 12,000 to 14,000 BTUs per pound.

In contrast, **radioisotopic** transformation is accompanied by the release of enormous energy when compared to conventional oxygen – electron oxidation. However, this does not justify the theory advanced that neutrons occupy the center of atoms. It is my hypothesis that neutrons reside in the orbital shells of elements and not within the nucleus. To envision this atomic structure one only has to look at our own solar system to see this on a grand scale. Isotopic oxidation (neutron oxidation) simply involves the neutrons. However, the energy involved is much greater because the neutrons represent neutral charge and therefore the binding energy of the elemental shells is of a greater magnitude.

When the unstable isotope of an element reverts back to its original stable state energy is released in the transformation. Now, consider that incident electrons are impinging upon, for example, the naturally occurring element U235. Assuming its absorption wavelength is correct, according to the resonant frequency of this element, then excess energy can be released. This may be done with any isotope. However, U235 will "self-fission" and under the right conditions, will not require any source of energy other than what it emits. Excess energy is released only after enough neutrons are captured to cause the transformation of the U235 atom. This is called the "break even" point, beyond which excess energy is released to effect a "chain-reaction."

We are not limited to the U235 isotope to use as a fuel source. This element is used in a commercial nuclear reactor because it undergoes self-fission and requires no additional catalyst in order to "burn." The public does not generally know that the U238 in a commercial reactor does not undergo fission. The only reason for its presence is to capture neutrons that transform it into weapons grade plutonium (Pu^{239}).

U238 will "fission" via fast neutrons generated by the alpha fusion process. However, there is one small hitch to the alpha fusion process. A nuclear fusion fuel material is needed along with the U238 alpha emitter. This material generates the required fast neutrons for this type of fission. All that is needed is the right type of spark to speed up the decay rate. Radium or radiothorium could also be used as the alpha source. Beryllium, boron, or carbon can be used as the fusion catalyst. Any of the elements below periodic number fifteen feasibly could be utilized. However, these three elements sited pack the most wallop. My process uses alpha fusion formulas that show the way to a simple and economical method. No excess neutrons result to create a toxic waste problem. Fully depleted U238 could be used that does not contain U235. Instead of making nuclear bullets, like the ones used in the Gulf War, we could be using our reserves of depleted uranium as a beneficial fuel source.

Plutonium is not feasible at this time, so plain old, natural, untreated uranium will also work. One pound of "yellow-cake" (U_3O_8) is equivalent to 31 barrels of oil or 10 tons of coal. At the moment yellow cake costs only $12.50 per pound.

Radon gas from naturally occurring radio emissive uranium or thorium ores can be directly converted into electricity. The case surrounding these materials will provide adequate shielding. These devices can be designed to be compact so that a lightweight unit could be built. It has been estimated that for every pound of fuel, that, one kilowatt of power can be generated.

For political reasons' people, organizations and government agencies have strongly opposed the use of all forms of nuclear energy. These people have made the general population paranoid of any and all radioactive materials. Despite this strong opposition and threats against it's development, work continues with the dream of harnessing transformations safely. The atom makes energy available to us. I have proposed a radical atomic theory to explain the nuclear energy process. Conventional atomic theory has many flaws. It does not completely explain the energy created by a nuclear reaction. Does this mean that the nuclear reactor does not completely create energy? No matter what theory you wish to use in explaining atomic power, the fact still remains that energy is transformed.

James Chadwick discovered the neutron in February 1932. Later, further studies were made to discover what effects would be produced by bombarding different materials with this new particle. Researchers for the next several years bombarded every known element with neutrons and recorded hundreds of new radioactive isotopes. My own research in this area has revealed many secrets of the vast reservoirs of energy contained within the atom.

The First Neutron Initiator

The initiator for the first plutonium weapon was composed of polonium coated onto beryllium. The polonium came from the Radium Chemical Company.

Electronically Activated Neutron Source

In the winter of 1996, I applied a 90,000-volt negative charge to a carbon rod. This carbon rod was surrounded with radioactive ore in a closed container. Under these conditions, the radon gas emitted from the ore was attracted and absorbed into the charged rod. This began my research into electronically assisted atomic transformations.

"It must be first remarked that helium is a gas which accompanies all radioactive minerals. It was from these bodies that it was first obtained – a catalyst with an interesting effect."

"This derivation from radium is a **special helium** since it appears to possess the property of spontaneously vanishing. Its' only resemblance to ordinary helium seems to consist of the momentary presence of some spectral rays." * The Sea of Energy, 5th edition, pages 229-230.

Breeding U234

Mix a dilute solution of uranium nitrate and finely divided carbon together. The solution is boiled for about half an hour. Radon is united with the carbon. After which the carbon is filtered out. To unite the radon with the carbon, the two are exposed to a strong source of **gamma radiation.** This is the **catalyst** that accelerates nuclear (ultra-chemical) reactions.

The reaction is as follows: $C^{12} + Rn^{222} \rightarrow U^{234}$ (uranium "X") + $\mathbf{e}\uparrow$

To concentrate the U234 the excess carbon can be removed by burning.

The results of my life-long research have opened a doorway that could lead to electronically induced nuclear fusion. I originally named this process "alpha fission" to connote the electronically induced atomic reaction. The term was chosen so as to cause the least adverse social reaction to this discovery, due to the fact that the public has been duped into a state of paranoia by its global governments. Later, this term was changed to alpha fusion, as this is a more accurate term than the original chosen term.

Conventional nuclear reactors generate deadly toxic radioactive wastes as by-products. These reactors are even more deadly than anyone realizes. Fuel rods in the reaction process are extremely hot and are subjected to enormous internal pressure. You can not tell me that untold amounts of deadly radon gas are not leaking into our environment. The fact of the matter is that a special detector would be required to detect this leakage. Scintillation, Geiger and Alpha counters will not detect this gas because the mass of the radon gas can not penetrate the sensors on these meters. We must take a close look at clean nuclear processes before it is too late (if it isn't already).

With the advent of electronically triggered neutrons, a self-sustaining chain reaction can be obtained and may be highly controlled. I find this especially true if **thorium ore** is used. Thorium emits **thoron** (Rn^{220}). Owing to its extremely short half-life, thoron by itself can not be used as a source of strong radiation. However, in conjunction with its parent substance radiothorium, it can indeed be used as a strong source of radioactivity.

Thoron has a short half-life of 54.5 seconds. On the other hand Radon–222 has a considerably long half-life of 3.5 days making it a hazard. Thoron is safe and convenient to work with because there are no long-lived products in its disintegration chain. Therefore, there is minimal danger of permanent contamination. The parent substance, radiothorium, may be obtained from thorium solutions in the manner described next.

Radiothorium is generally used as a parent source of thoron. Radiothorium has a conveniently long half-life of nearly two years. Extractions of radiothorium can be obtained in a highly emanating state. A small quantity of iron chloride is added to a thorium solution and precipitated as hydroxide by ammonia or as oxalate by oxalic acid. The precipitate, the hydroxide or oxalate of iron, is washed very carefully and dried at room temperature. This precipitate should have a high activity rate. It will not lose more than 20% of its initial activity rate for many months. This radiothorium preparation may be spread into a thin layer in a shallow brass tray placed at the bottom of a small lead-shielded container. The active deposit thorium can be collected on a negatively charged wire, insulated with respect to the container. The emanated **thoron** gas may also be absorbed into various materials.

Many radioactive isotopes could be used to generate electrical power. However, the power behind these isotopes is really with the radon gas. I have pointed this out many times in my writings, lectures and articles. Simply by bombarding bismuth, we can create polonium. In United States Patent 2,728,867, it is stated that the available energy of a commercial nuclear fuel rod is around twenty watts of power per gram. In comparison, **polonium** will generate one hundred and forty watts of power per gram. This is **seven times** more energy than is available from the conventional fission process!

The atomic ions emitted from radioactive isotopes can be directly converted to electrical power. My conversion method shown in Section 5, **Figure 4** can be used to convert this source of radiant energy. Additional stages can be added for more power. The circuit shown gives a general idea of how such an energy conversion device can function. By no means is this technology limited to this one circuit or configuration.

Radon Fuel

My research has revealed that the energy devices of T. H. Moray, Alfred Hubbard, Reverend Antonio d'Angelo, Joseph Papp, and others all contained a source of **radon gas.** They may or may have not realized that this was what they were using as their fuel. We will never know this for sure. However, what we do know for certain is that they all used radium in their energy devices. When my prototype is ready to be demonstrated I too will show how radon can be used to generate electricity. Demonstrations will have to be performed in private until my device obtains an exemption from government restrictions.

The facts show beyond doubt that radon gas was the fuel source that has powdered many so-called "free energy" devices. You can say that these devices ran on the energy of the cosmic rays. It is these rays that created radioactive thorium and uranium that we find in the ground. High-energy cosmic rays are really neutrons as Nikola Tesla had discovered. When a cosmic particle reacts with either thorium or uranium a radioisotope is created. This is why you see a consistent percentage of U235 all over the planet. This percentage represents an accumulation of comic ray bombardment over the lifetime of our world. Nature offers us this fuel that can be used to obtain electrical power with no moving parts and it is out there free for the taking. We do not have to split atoms to harness this storehouse of energy. Nature has already safely done this for us.

In order for clean nuclear power generation to enter into public use, high-grade radioactive ores must be secured without restrictions. Recent attempts to obtain these ores have been blocked by the United States Government. Once these ores are obtained I will build a high wattage radiant energy converter. Through my writings, lectures and published articles I have attempted to explain my research. Over the years I have made my research available to the public and have asked for little in return. I am asking you at this to help me to get this technology implemented, within the constraints of the law. As a former United States President once stated: "Sometimes when we reach for the stars, we fall short but we must press on."

President Ronald Reagan

The Truth about Nuclear Science

Present day alternative energy researchers find hope in that, one day, power will be obtained from the energy that runs the Cosmos. In reality, this dream has only proved to be a lure to its followers, beyond the limits of credibility. A quagmire of unsubstantiated hypotheses exists that are bottomless and lack reality. The facts of many newly conceived energy concepts are wholly inadequate, lacking justification, and incapable of throwing any light on the promise of inexpensive, abundant sources of energy.

The Earth is indeed bathed in a sea of cosmic and solar energies. Can a device be built that can transform these energies into usable power? I believe that T. H. Moray did build such a device. This has inspired me to conduct my own research and to build my own prototypes. How the radiant energy device really worked might shock a few people once the facts become realized.

Nature is my best teacher. Within one of her classrooms there are mineral samples that give out pure electrical energy. They are the radioactive rocks. If radioactive matter from these rocks derives its energy elsewhere, this must be of a type entirely different from any presently known. It is capable of penetrating, without loss, hundreds of feet of solid rock.

Nikola Tesla’s investigations brought him to the conclusion that the Earth was being showered with "tiny particles, each carrying so small a charge that we are justified in calling them neutrons." He stated that "…they move with great velocity, exceeding that of light."

Dr. Thomas Moray called into existence the concept of unlimited radiant energy (the cosmic ray), permeating all space and all matter, unimpeded. Such a view, at first glimpse, merges perfectly with the continuous and permanent activity of radium extracted from certain rocks. This activity seems to last for an indefinite time. There appears to be no rational reason why radioactivity, however intense and powerful, should decay or diminish with the passage of time. Yet, radiant matter (radioactivity) does decay. The demonstrated "half-life" values have proven that the stored energy within radiant matter will eventually be depleted.

At some point in my own research, I had to ask myself three important questions:

1) Is there anything opposed, either to reason or to probability, to the view that the energy evolved from radium is actually derived from an existing previously unsuspected internal process within the atom?

2) Within the decay process does the element experience a transformation into other elements?

3) How is it that such enormous stores of energy in matter have remained so long unknown?

In my experience, a specimen of radium chloride is dissolved in water and the liquid is then evaporated. Bringing this compound back to its dry state, as the result of this very simple operation, the radium has lost the greater part of its radioactivity. The penetrating beta and gamma rays completely disappear. The remaining non-penetrating alpha rays will be only one quarter as powerful as they were initially. Then a strange thing happens. Left alone, the radium will spontaneously recover its lost activity. Little by little, day by day, until at the end of a month, it will be no less active than it was before it went into solution. This appears to be in direct conflict with the zealous statement that "radioactivity of radium cannot be affected by any known process." On studying this experiment carefully, we will find that when radium chloride is dissolved in water something escapes into the air. This "something" is intensely radioactive. It diffuses in the air, but will remain if contained within a gas-tight, closed vessel. In short, this "something" is a gas possessing the property of radioactivity to a very intense degree. This gas was called "emanation" in days of old. Today it is called **RADON-222**. It has a half-life of around 3.8 days. This radon gas is highly radioactive. Thorium releases **RADON-220** that is intensely radioactive and has a half-life of around 55.6 seconds. Uranium emits **RADON-219**, the most intensely radioactive substance, having a half-life of only 3.96 seconds.

Radon that has been separated from its parent source will rapidly decay. It is easy enough to conclude from this experiment that energy is stored within the radium atom. This accounts for the comparatively rapid decay of the activity of the generated radon gas. This gas is depleting its internal store of energy so rapidly that it is soon exhausted. On the other hand how is the gradual recovery of the radioactivity of the parent radium explained? This question is the golden key to unlocking the secret of its power.

If it is true that energy comes from within, as large as the store of energy within the atom must be to explain its radioactivity, yet it cannot be infinite. Therefore, it is expected that the activity will slowly decay with the passing of time. Two radioactive bodies, one much more radioactive than the other, are compared together. It is expected that the activity of the more powerful body will decay faster than that of the other. A time will come for both of these substances, when the internal stores of energy are exhausted, that the radioactivity will come to an end. Therefore, radium, a substance containing the store of energy, can no longer be radium when the energy is lost. Coal is not coal after it is burnt. When energy is obtained from matter, the matter changes. Before it can be restored to its former state, the energy evolved must be put back. In no case, is it possible for matter to part with its store of chemical energy and remain the same, otherwise perpetual motion could be easily constructed.

We conclude that, if the energy is stored in the radium, it must be within the atom. Therefore, if radium changes, it must be a change of the atom and of the element itself. This change would be its ultra-chemical reaction. This is a more fundamental and deep-seated change than the normal chemistry or any known kind of material change. Until the discovery of radioactivity, such changes certainly had never been observed. If the energy of radium comes from within, then it must be subjected to this ultra-chemistry that has eluded the chemist. This process of ultra-chemistry must be understood as a special extension of chemistry. It is not some vaguely possible, transcendental nuclear condition in the Sun and stars. Once this is understood, the answers will become as sure as the nose on your face.

Imagine that a month has passed. The radium chloride is once again dissolved in water and evaporated down to dryness exactly as before. Once more you will find in the process, that the radium has lost the same large proportion of its radioactivity. Again it gains a new amount of radon gas no less than before it went into solution. Repeat this experiment as often as you like. You will find the result always the same. The radon that you separate from the radium is decaying away from day to day. But the radium will also generate a spontaneous fresh new batch of radon. In order to make sense of this, we have to answer these nagging questions; "from where does the energy of radium come?" Does it come from nowhere, or is it being newly created out of nothing? This is a view that is not acceptable for a plausible twenty-first-century physical science.

If our doctrines of energy are true, then there are only two possible answers to consider. Either the energy must be derived from within the radium, or it must be supplied from elsewhere. This simple narrowing down of all the possible answers may appear to you somewhat simplistic, but in reality, it carries with it far more than appears on the surface. Being a minute property of the element, radioactivity is therefore a property of the atom. If we say that the energy comes from within, this means that there must exist an enormous and not previously suspected store of energy in matter, or at least in radioactive matter.

Dr. Moray often advanced the theory that radium acts merely as a transforming mechanism, that it converts the cosmic rays into electrical particles. He states that it retransmits energy in a form that we recognize. Tesla also entertained this view. There are electrical transformers dotted all over our country receiving transmitted but dangerous high-tension currents from the central power station. These are "transformed" into comparatively safe, low-tension currents for your house. Are the atoms of radium acting as the transformers of a mysterious and unknown source of external energy, first receiving it and then delivering it up again in a form that can be recognized? It may be said that so vague a view, postulating the existence of limitless and mysterious supplies of omnipresent energy, cannot be directly disproved. One thing is for certain; this view provides a way of escape from some of the more distasteful "logical" assertions, namely that all forms of energy are stored within the atoms and molecules.

If radium owes its activity to an energy source outside itself, one has only to isolate it. We have seen that to quench radioactivity, or to modify it in any way is one of the things mainstream science cannot do.

An experiment has proven that even in its natural state in the mine, hundreds of feet deep down in the Earth, pitchblende exhibits its normal radioactivity. Over 100 years ago, scientists concluded that some sort of radiation must exist in the atmosphere. This conclusion arises because under all circumstances, air is found to be have a slight positive concentration of ionized particles. The atoms are minus an electron. This radiation is constantly much stronger at high altitudes than at the Earth’s surface. This leads us to conclude that such radiation does not originate on this planet but rather from somewhere in the outer regions of space. The fact that the intensity of this radiation does not increase during daylight hours eliminates the sun as its source. Also, the intensity does not decrease during the day or increase by night, therefore it cannot be a result of any particular group of stars.

Spontaneous Decay

Does not the "free emanating" state of a salt of radium teach anything about its decay mechanism? Results obtained by Dr. Alois Gaschler and Otto Hahn in the 1920's proved conclusively that when radium becomes finely divided, it most readily emits radon. This teaches us that radioactive change is effected by confinement. How many scientists have paid attention to this all-important lesson? Is it actually the true mechanism behind what is being called "fission?"

It is in my humble educated opinion that the seat of radioactivity is due to radon gas trapped within the lattice of certain heavy metals. The best comparison that I can think of is coal and the stored hydrogen gas within its lattice. Its stored hydrogen reserve reacts with oxygen transforming these two gasses into H_2O with the release of heat. The carbon contained in the coal also reacts with oxygen when a high enough heat is generated from the hydrogen reaction and combustion occurs, transforming the carbon and oxygen into CO_2. Pretty much the same fundamental principle must occur when radon gas is released from its heavy metal prison. The reactant in this later case is a neutron from a previous radon gas emission. Radon reacts with a metal, losing a neutron to it. When this occurs, the radon becomes highly unstable, emitting alpha particles and rapidly transforming into stable lead. From this reaction it is clear that radon is not as inert as we were lead to believe. In fact, I say that radon is at the very foundation of nuclear reactions.

Since the discovery of radium by Madame Curie, the fundamental method of its extraction has not changed. The process utilizes the same methods that were instituted by Madame Curie and M. Debierne. Radioactive ores are first treated with a warm solution of hydrochloric acid that dissolves the metals. The addition of sulfuric acid precipitates the insoluble barite's that are always present, carrying along with them all the radium as barium sulfate. It is necessary that barium is present in the process. If the solution does not contain a sufficient quantity, then some barium has to be added. It is said that the barium acts as a "carrier" to the radium. Can there be any other explanation? It never made much sense to me why the radium would not precipitate out without the barium. I simply could not accept the notion that it acted as the carrier. The answer to this problem becomes relatively simple if you let Nature be your teacher. Forget what the textbooks tell you. We know from her lessons that radiation can be induced into non-radioactive elements, do we not? Could it be then, that something in the separated hydrochloric solution is transforming the barium into what we call radium? Ala-ka-zam, low and behold, there sure is, it is called **URANIUM–235.**

Nu Radium Formula

Radium may be synthetically manufactured by fusing dry uranium nitrate mixed with about 0.5% of dry barium nitrate. This is done in the heat of an electric arc. The mass is then treated with nitric acid, water and sulfuric acid, successively. Radioactive barium sulfate, possessing all the physical properties of the "element" discovered by Madame Curie, is obtained by this formula. This material will emit ultra-violet rays, x-rays, excite phosphor screens and cause air to conduct electricity. The chloride and the carbonate of radium may also be created by using uranium chloride or uranium carbonate respectively and will have the same properties.

Uranium nitrate typically contains about 0.72 per cent **U235**. The barium reacts with the U235 creating pure radium. Take note here that this is an ultra-chemical reaction and that the barium is not a carrier as has been believed. Best results are obtained when 0.72 per cent barium is added, making it equal or less than the amount of U235 contained in the nitrate. If sulfuric acid is added after the reaction takes place, then radium sulfate is precipitated. This material can now be filtered for removal from the solution. The synthetically created radium radioisotope results when barium reacts with **RADON–219**. It can not come into being otherwise. **All other radioisotopes may be called into existence by using U235 as the source of energy transformation.** There are other processes involved but this will be discussed in a future paper. Radioisotopes created by ultra-chemical processes will have far reaching ramifications, if and when it is taken under the wing of mainstream science. Radioisotopes could be made to order literally in a jar. These findings indicate that all radioactive substances originate from the U235 atom. Now the question arises; where did the U235 atom originate? I can only speculate at this point that it is created when a cosmic ray hits a stable U238 atom head-on. If my conclusions turn out to be correct, then the energy stored in radiant matter is a product of an external cosmic force and an internal force without contradiction.

Clean Nuclear Reactors

Mother Nature offers us a clean nuclear process to supply the World with energy. My reasoning is based upon her process that leaves behind a clean, non-toxic ash. You have seen it in children's balloons at birthday parties. The inert gas that I am referring to here is called "helium." When I shine ultraviolet light onto a radioactive ore, the trapped helium gas will fluoresce a lime-green. The only ash, left behind by Nature’s process, is what is seen under the ultraviolet lamp. There are no deadly radio toxins like the ones found in the commercial reactor. It makes all the difference in creation how the reaction is carried out and for what purpose. I will also tell you that eating radium, like the women did who painted the glow-in-the-dark watch and clock dials will create serious health problems. A little common sense goes a long way.

The commercial nuclear reactor releases excessive amounts of neutrons. This is a direct result of the reaction of **RADON–219** with the zircalloy fuel rod casing. It is highly likely that we can design reactors that will release only pure electrical particles in place of the toxic radioisotopes created by stray neutrons. Why not build clean reactors that do not generate excessive neutron release? Maybe it is because this is not presently perceived by mainstream science? Knowing the true facts makes it a relatively simple matter to acquire a cleaner burning reaction. The only major modification in reactor design is to find a more suitable fuel rod casing. Eliminate the excess neutrons and you will have a clean burn.

Are Neutrons What Really Cause Fission?

1. Alpha bombardment of any element with atomic numbers from **1** through **15** will generate a new and stable element that will release one excess neutron from the reaction.
2. Neutron bombardment of any stable element from **16** and above will generate a new and unstable element by capturing neutrons. One or more neutrons are released from the reaction. The targeted element will gain the weight of the absorbed neutrons.
3. Neutron bombardment of an unstable element generates one helium–4 atom from each reaction. The atomic weight of the targeted element looses the weight of one helium–4 atom as a result of the reaction.

From these three facts, it is not too hard to figure out that the "moderator" in a commercial nuclear reactor is actually what initially supplies the required neutrons for a "fission reaction." The excess neutrons created are what react with a "fissile fuel" that creates a secondary reaction. The release of thermal energy is a by-product. Scientists of yesteryear had these facts straight. Why are present day nuclear theories so off course? It will only be when these facts resurface that advances will be made in the way we obtain energy.

CONCLUSION

The devices that I have presented at public tests do not contain radioactive materials for obvious reasons. However, the underlying principles have been adequately demonstrated. I have used star-mode electrodes in the past to slowly discharge the capacitors in a prototype device. Advanced discharge systems are now being utilized. In 1995 I discovered ion valve circuits that are now being used in my most recent prototype. Even though these public tests have not contained radioactive material, my research has been validated.

Funding has not permitted me to build a device that can power a home or electric car. However, my prototypes have proven beyond doubt that with the proper funding this can be accomplished. It is my hope, through the publication of my findings, that funding will be forthcoming. At this point in time, it is most important to me that I receive credit for my for work and that my research discoveries do not fall on deaf ears.

Public tests are performed as necessary to validate the technologies. These demonstrations are deemed as research and development tests only. No power claims are expressed or implied.

For almost fifteen years now I have carried out many experiments. The fruits of this research are ripening. Many fruits are within grasp but they are not yet quite ripe for the picking. The intent of revealing my progress to the World is to insure that this work is not done in vain. Through my writings I have attempted to explain the many facets of "radiant energy" and how it is possible to draw useable power from it. If radiant energy can be given to the World then humankind will have the potential to reach heights not yet dreamed or conceived. Today, I freely give to you the results of my life's work. Together we can reclaim our independence!

REFERENCES

Winsor, "Nuclear Scare Scam" – lecture

"Radiations from Radioactive Substances" by
Sir E. Rutherford, J. Chadwick, and **C. D. Ellis** 1930

Rentschler, A. I. E. E. 1930, p. 49 & p. 576

Hauser and **Vahle, Strahlentherapie,** 1921, p. 13 & p. 41

"The Interpretation of Radium and the Structure of the Atom" **by Frederick Soddy, M.A., F.R.S.** 1920

Annual Report of the Smithsonian Institution (1899) "An Experimental Study of Radio-active Substances" p.162

United States Patent No. 1,644,370 **A. Gaschler** – Oct. 3, 1927

United States Patent No. 1,655,184 **Otto Haun** – Jan 3, 1928

HISTORICAL COMMENTARY

Tesla's last ten years of his life, 1933 - 1943, contrary to popular belief, were his most productive years in his private laboratory located on Canadian soil. This was communicated to me through his last known living assistant, Arthur H. Matthews, E.E., and B.Sc. before he passed away in 1986. He also revealed to me that special primary batteries with replaceable zinc electrodes powered Tesla's electric car. This car also had a "fluid transmission" and could travel at 90 miles per hour. The electric motor could run on the batteries for three hundred miles before you had to pull over and attend to the batteries and then you were on your way for another three hundred miles. Matthews claimed that there were enough spare parts in the trunk to run the car for one year! The performance of this vehicle seems to be impossible. However, the characteristics of Tesla's unidirectional electrical current can generate short duration high-energy that will generate high frequency oscillations when dumped through an inductive coil. This unique principle makes possible many seemingly impossible innovations. It was this principle that was at the very heart of Tesla's Magnifying Transmitter, also known as his "DC transformer" to his assistant Arthur H. Matthews.

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 1

Fig. 1.


13
14
7
8
6
5
9
10
11
12

Fig. 2.


1
14
5
C1
b1
a1
7
9
10
11
12
1
M
2
6
15
13

Fig. 3.


A
O
S
a
a
a
a
8
7
1
M
2
E

Fig. 4.


S
5
1
8
7
M
2
6
E
E1

Fig. 5.


A
S
5
8
7
7a
9
E
6

Fig. 6



Inventor
Hermann Plauson

by Knight Bros
attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 2


Fig. 7.
A
S
1
M
2
7
7b
8
E
E1
E2


Fig. 8.
A
X
5
9
X1
X4
7
1
M
2
8
X5
X2
6
9a
X3
E1
E


Fig. 9.
A
S
X
8
X2
5
1
M
X1
9
2
X3
7
6
X4
E
E1


Fig. 10.
A
S
5
8
7
9
10
6
E


Fig. 11.
9
1
7
8
10
M
2
5
E


Fig. 12.
A
S
X
9
10
1
5
7
2
9a
10a
X1


Fig. 13.
5
X
9
1
4a
4
M
3
3a
8
X1
2
7
E

Inventor

Hermann Plauson

by Knight Bros

attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 3


S
A
x
8
1
M
2
4
10
3a
5
9
3
4a
7
E

Fig. 14.


S
A
5
4
x
x1
3a
M
1
9
3
2
6
z
4a
7
E

Fig. 15.


S
A
8
5
4
6
1
9
3a
M
3
2
4a
7

Fig. 16.


S
A
1
R
1a
M
2a
8
2
7
E1
E

Fig. 17.


S
A
6
1
9
M
2
7
8
E2
E1
E

Fig. 18.


A
N
8
1
R
1²
1¹
2
5
x
7
E
E2
E

Fig. 19.


z
A1
A2
A3
A4
A5
z
A10
z
A9
n
A8
n
A7
A6
n
n
X
X1
X5
n
X9
n
n
X6
n
A
S
5
1
7
8
2
E

Fig. 20.

Inventor
Hermann Plauson
by Knight Bros
Attorneys

June 9, 1925. **1,540,998**

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 4


5
X
Z
5a
5b
D'
D
C
A
1
2
3
3a
4
4a
7
E
M
C1
C2
C3
D1
D3
E1
E2
E3
5c

Fig. 22.

Fig. 21.

Fig. 23.

Inventor
Hermann Plauson
by Knight Bros
Attorneys

June 9, 1925. **1,540,998**

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 5


A
a
b
c
d
e
2
L
3a
3
3b
W
12
20
19
18
S1
17
16
13
21
22
23
24
11
S2
5
14
8
7
9
10
15
6
E1
E2

Fig. 24.

Inventor

Hermann Plauson

by Knight Bros

Attorneys

June 9, 1925. **1,540,998**

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 6

Fig. 25.



A1
A2
A3
A4
S2
S1
S3
22
21
27
25
R.
S4
Sb
16
13
18
17
20
19
Sa
Sd
Sc
12
26
28
24
23
J.
8
5
7
M
6
E1
E2

Inventor

Hermann Plauson

by

Knight Bros

attorneys

June 9, 1925. **1,540,998**

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921, 12 Sheets-Sheet 7


1
2
3
4
5
6
7
8
I
19
S
S1
abcd
F1
16
A
18
17
12
14
g
9
10
11
K
13
B
B1
15
14
F
E1
E

Fig. 26.

Inventor
Hermann Plauson
by
Knight Bros
Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921. 12 Sheets-Sheet 8


22
23
II
I
6
3
2
5
1
4
21
II
S_II
E_II
F_I
13
9
10
S_I
E_I
17
20
19
11
f
E
F
S
I
12

Fig. 27.

Inventor

Hermann Plauson

by Knight Bros

Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12 Sheets-Sheet 9



1
2
4
5
3
6
II
8
7
II
I
I
III
III
II¹
I¹
20
19
II¹
9
12
10
A
a
14
F
b
B
13
S₁
S
E₁
E

Fig. 28.

Inventor
Hermann Plauson
by
Knight Bros
attorneys

June 9, 1925. **1,540,998**

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921. 12 Sheets-Sheet 10


B
C
K
L
P
+
−
N
P
+
−
N
9
−
E

Fig. 29.


a
b
a
b
F
B
C
K
L
P
+
N
−
9
5
−
E

Fig. 30.

Inventor
Hermann Plauson
by
Knight Bros
Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan 13 1921 12 Sheets-Sheet 11


z
B
C
K
P
L
+
+
–
–
9
10
11
–
E

Fig. 31.


z
B
C
K
L
5
6
+
9
G
N
–
E

Fig. 32.



Fig. 33.

Inventor
Hermann Plauson
by Knight Bros
Attorneys

June 9, 1925.

1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921

12 Sheets-Sheet 12


A
1
+
5
+
3
2
+
6
–
7
8
9
10
S
A
E
E1

Fig. 34


A
5
n
+
1
8
10
9
2
13
12
+
3
6
–
–
11
m
S
E
E1

Fig. 35.


5
1
2
11
12
3
8
7
9
10
S
E
E1

Fig. 36.


A
5
1
2
9
10
3
8
S
E
E1

Fig. 37.

Inventor

Hermann Plauson

by Knight Bros

Attorneys

Patented June 9, 1925. **1,540,998**

UNITED STATES PATENT OFFICE.

HERMANN PLAUSON, OF HAMBURG, GERMANY.

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY.

Application filed January 13, 1921. Serial No. 437,107.

To all whom it may concern:

Be it known that I, Hermann Plauson, Esthonian subject, residing in Hamburg, Germany, have invented certain new and useful Improvements in the Conversion of Atmospheric Electric Energy, of which the following is a specification.

Methods of obtaining atmospheric electricity by means of metallic nettings set with spikes which are held by means of ordinary or anchored kite balloons made of fabrics and filled with hydrogen, are in theory already known. Atmospheric electricity obtained in this way has been suggested to be used in the form of direct current for the charging of accumulators. This knowledge however is at present only theoretical as the conversion in practice has hitherto been a failure. No means are known of protecting the apparatus from destruction by lightning. The balloons used for collecting the charge must also be made of very large size in order to be able to support the weight of the metallic netting and the heavy cable connections.

Instead of using heavy metallic netting as collectors attached to single air balloons of non-conducting materials which are liable to be torn and are permeable to the gas, it is proposed to use metallic balloon collectors which have the following important advantages—

(*a*) The metallic cases are impenetrable to helium and hydrogen; they also represent large metallic weather-proof collecting surfaces.

(*b*) Radio active means and the like may be easily applied internally or externally; whereby the ionization is considerably increased and therewith also the quantity of atmospheric electricity capable of being collected.

(*c*) Such balloon collectors of light metal do not require to be of large size as they have to carry only their own moderate weight, and that of the conducting cable or wire.

(*d*) The entire system therefore offers little surface for the action of storm and wind and is resistant and stable.

(*e*) Each balloon can be easily raised and lowered by means of a winch so that all repairs, recharging and the like can be carried out without danger during the operation.

It is further proposed to use a collecting aerial network of several separate collectors spread out in the air above the earth, which collectors are interconnected by electrical conductors.

According to this invention charges of atmospheric electricity are not directly converted into mechanical energy, and this forms the main difference from previous inventions, but the static electricity which runs to earth through aerial conductors in the form of direct current of very high voltage and low current strength is converted into electro-dynamic energy in the form of high frequency vibrations. Many advantages are thereby obtained and all disadvantages avoided.

The very high voltage of static electricity of a low current strength can be converted by this invention to voltages more suitable for technical purposes and of greater current strength. By the use of closed oscillatory circuits it is possible to obtain electromagnetic waves of various amplitude and thereby to increase the degree of resonance of such current. Such resonance allows various values of inductance to be chosen whereby again the governing of the starting and stopping of machines driven thereby by simply tuning the resonance between coils of the machine and the transformer circuit forming the resonance can easily be obtained. Further, such currents have the property of being directly available for various uses, even without employing them for driving motors, of which there may be particularly mentioned, lighting, production of heat and use in electro-chemistry.

Further, with such currents a series of apparatus may be fed without direct current supply through conductors and also the electro-magnetic high frequency currents may be converted by means of special motors adapted for electro-magnetic oscillations into mechanical energy, or finally converted by special machines into alternating current of low frequency or even into direct current of high potential.

The invention is more particularly described with reference to the accompanying diagrams in which:—

Figure 1 is an explanatory figure.

Figure 2 is a diagrammatic view of the simplest form.

Figure 3 shows a method of converting atmospheric electrical energy for use with motors.

Figure 4 is a diagram showing the use of protective means.

Figure 5 is a diagram of an arrangement for converting large current strengths.

Figure 6 is a diagram of an arrangement including controlling means.

Figure 7 shows means whereby the spark gap length can be adjusted.

Figure 8 shows a unipolar connection for the motor.

Figure 9 shows a weak coupled system suitable for use with small power motors.

Figures 10, 11 and 12 show modified arrangements.

Figure 13 shows a form of inductive coupling for the motor circuit.

Figure 14 is a modified form of Figure 13 with inductive coupling.

Figure 15 is an arrangement with non-inductive motor.

Figure 16 is an arrangement with coupling by condenser.

Figures 17, 18 and 19 are diagrams of further modifications.

Figure 20 shows a simple form in which the aerial network is combined with special collectors.

Figure 21 shows diagrammatically an arrangement suitable for collecting large quantities of energy.

Figure 22 is a modified arrangement having two rings of collectors.

Figure 23 shows the connections for three rings of collectors.

Figure 24 shows a collecting balloon and diagram of its connection of condenser batteries.

Figures 25 and 26 show modified collector balloon arrangements.

Figure 27 shows a second method of connecting conductor for the balloon aerials.

Figure 28 shows an auto-transformer method of connection.

Figure 29 shows the simplest form of construction with incandescent cathode.

Figure 30 shows a form with cigar shaped balloon.

Figure 31 is a modified arrangement.

Figure 32 shows a form with cathode and electrode enclosed in a vacuum chamber.

Figure 33 is a modified form of Figure 32.

Figure 34 shows an arc light collector.

Figure 35 shows such an arrangement for alternating current.

Figure 36 shows an incandescent collector with Nernst lamp.

Figure 37 shows a form with a gas flame.

Figure 1 illustrates a simple diagram for converting static electricity into dynamic energy of a high number of oscillations. For the sake of clearness in the drawings an influence machine is assumed to be employed and not an aerial antenna. 13 and 14 are combs for collecting the static electricity of the influence machine. 7 and 8 are spark discharging electrodes, 6 and 5 condensers, 9 an inductive primary coil, 10 secondary coil, 11 and 12 ends of conductors of the secondary coil 10. When the disc of the static influence machine is rotated by mechanical means, the combs collect the electric charges one the positive and the other the negative, and charge the condensers 5 and 6 until such a high potential is formed across the spark gap 7—8, that the spark gap is jumped. As the spark gap 7—8 forms a closed circuit with condensers 6 and 5, and inductive resistance 9, as is well known, waves of high frequency electromagnetic oscillations will pass in this circuit.

The high frequency of the oscillations produced in the primary circuit induces waves of the same periodicity in the secondary circuit. Thus in the primary circuit electromagnetic oscillations are formed by the passage of the spark over the spark gap and these waves are maintained by fresh charges of static electricity.

By suitably selecting the ratio between the number of the coils in the primary and secondary circuits with regard to a correct application of the co-efficients of resonance (capacity, inductance, and resistance) the high voltage of the primary circuit may be suitably converted into low voltage and high current strength.

When the oscillatory discharges in the primary circuit becomes weaker or entirely cease, the condensers are charged again by the static electricity until the accumulated charge again breaks down the spark gap. All this is repeated as long as electricity is produced by the static machine by employing mechanical energy.

An elementary form of the invention is shown in Figure 2 in which two spark gaps in parallel are used one of which may be termed the working gap 7 in Figure 2, whilst the second serves as a safety device for excess voltage and consists of a larger number of spark gaps than the working section, which gaps are arranged in series and are bridged by very small capacities as is illustrated in a_1, b_1, c_1, Figure 2 which allow of uniform sparking in the safety section.

In Figure 2 A is the aerial antenna for collecting charges of atmospheric electricity, 13 is the earth connection of the second part of the spark gap, 5 and 6 are condensers, 9 a primary coil. Now when through the aerial A the positive atmospheric electricity seeks to combine with the negative charge to earth, this is prevented by (the air gap between) the spark gaps. The resistance of the spark gap 7 is, as shown in the drawings, lower than that of the other safety section which consists of three spark gaps connected in

series, and consequently a three times greater air resistance is offered by the latter.

So long therefore, as the resistance of the spark gap 7 is not overloaded, so that the other spark gaps have an equal resistance with it the discharges take place only over spark gap 7. Should however the voltage be increased by any influences so that it might be dangerous for charging the condensers 5 and 6 or for the coil insulation 9 and 10 in consequence of break down, by a correct regulation of this spark gap the second spark gap can discharge free from inductive effects direct to earth without endangering the machine.

Without this second spark gap, arranged in parallel having a higher resistance than the working spark gap it is impossible to collect and render available large quantities of electrical energy.

The action of this closed oscillation circuit consisting of spark gap 7, two condensers 5 and 6, primary coil 9, and also secondary coil 10 is exactly the same as the one described in Figure 1 with the arrangement of the static induction machine with the only difference that here the second spark gap is provided. The electromagnetic high frequency alternating current obtained can be tapped off from the conductors 11 and 12 for lighting and heating purposes. Special kinds of motors adapted for working with these peculiar electrical charges may be connected at 14 and 15 which can work with static electricity charges or with high frequency oscillations.

In addition to the use of spark gaps in parallel a second measure of security is also necessary for taking off the current. This precaution consists according to this invention, in the introduction of and method of connecting certain protective electromagnets or choking coils in the aerial circuit as shown by S in Figure 3.

A single electromagnet only having a core of the thinnest possible separate laminations is connected with the aerial.

In the case of high voltages in the aerial network or at places where there are frequent thunder storms, several such magnets may however be connected in series.

In the case of large units or plants several electromagnets can be employed in parallel or in series parallel.

The windings of these electromagnets may be simply connected in series with the aerials. In this case the winding preferably consists of several thin parallel wires, which make up together, the necessary section.

The winding may be made of primary and secondary windings in the form of a transformer. The primary winding will be then connected in series with the aerial network, and the secondary winding more or less short-circuited over a regulating resistance or an induction coil. In the latter case it is possible to regulate to a certain extent the effect of the choking coils. In the further description of the connecting and constructional diagrams the aerial electromagnet choke coil is indicated by a simple ring S.

Figure 3 shows the simplest way of converting atmospheric electricity into electromagnetic wave energy by the use of special motors adapted for high oscillatory currents or static charges of electrical energy. Recent improvements in motors for working with static charges and motors working by resonance, that is to say, having groups of tuned electromagnetic cooperating circuits render this possible but such do not form part of the present invention.

A motor adapted to operate with static charges will for the sake of simplicity be diagrammatically indicated by two semicircles 1 and 2 and the rotor of the motor by a ring M. (Figure 3.) A is a vertical aerial or aerial network. S the safety choke or electromagnet with coil O as may be seen is connected with the aerial A. Adjacent the electromagnet S the aerial conductor is divided into three circuits, the circuit 8 giving the safety spark gap, the circuit 7 with the working spark gap, and then a circuit including the stator terminal 1, the rotor and stator terminal 2 at which a connection is made to the earth wire. The two spark gaps are also connected metallically with the earth wire. The method of working these diagrams is as follows:

The positive atmospheric electric charge collected tends to combine with the negative electricity (or earth electricity) connected with the earth wire. It travels along the aerial A through the electromagnet S without being checked as it flows in the same direction as the direct current. Further, its progress is arrested by two sparks gaps placed in the way and the stator condenser surfaces. The stator condenser surfaces are charged until the charge is greater than the resistance of the spark gap 7, whereupon a spark springs over the spark gap 7 and an oscillatory charge is obtained as by means of the motor M, stator surfaces 1 and 2, and spark gap 7, a closed oscillation circuit is obtained for producing the electromagnetic oscillations. The motor here forms the capacity and the necessary inductance and resistance, which, as is well known, are necessary for converting static electricity into electromagnetic wave energy.

The discharges formed are converted into mechanical energy in special motors and can not reach the aerial network by reason of the electromagnet or choke. If, however, when a spark springs over the spark gap 7 a greater quantity of atmospheric electricity tends to flow to earth, a counter voltage is

induced in the electromagnet, which is greater the more rapidly and strongly the flow of current direct to the earth is. By the formation of this opposing voltage a sufficiently high resistance is offered to the flow of atmospheric electricity direct to earth to prevent a short circuit with the earth.

The circuit containing spark gap 8 having a different wave length which is not in resonance with the natural frequency of the motor, does not endanger the motor and serves as security against excess voltage, which, as practical experiments have shown, may still arise in certain cases, but can be conducted direct to earth through this spark gap.

In the diagram illustrated in Figure 4 the spark gap 7 is shunted across condensers 5 and 6 from the motor M. This construction affords mainly a better insulation of the motor against excess voltage and a uniform excitation through the spark gap 7.

In Figure 5 a diagram is illustrated for transforming large current strengths which may be employed direct without motors, for example, for lighting or heating purposes. The main difference is that here the spark gap consists of a star shaped disc 7 which can rotate on its own axis and is rotated by a motor opposite similarly fitted electrodes 7^a. When separate points of stars face one another, discharges take place, thus forming an oscillation circuit over condensers 5 and 6 and inductance 9 for oscillatory discharges. It is evident that a motor may also be directly connected to the ends of the spiral 9.

The construction of the diagram shown in Figure 6 permits of the oscillation circuit of the motor being connected with an induction coil. Here a regulating inductive resistance is introduced for counter-acting excess voltages in the motor. By cutting the separate coils 9 (coupled inductively to the aerial) in or out the inductive action on the motor may be more or less increased or variable aerial action may be exerted on the oscillation circuit.

In Figure 7 the oscillation circuit is closed through the earth (E and E_1). The spark gap 7 may be prolonged or shortened by more or fewer spark gaps being successively connected by means of a contact arm 7^b.

Diagram 8 shows a unipolar connection of the motor with the aerial network. Here two oscillation circuits are closed through the same motor. The first oscillation circuit passes from aerial A through electromagnet S, point x, inductance 9^a to the earth condenser 6 and further, over spark gap 7 to the aerial condenser 5 and back to x. The second oscillation circuit starts from the aerial condenser 5 at the point x^1 over the inductance 9 to the earth condenser 6 at the point x^3 and through the condenser 6 over the spark gap 7 back to x^1. The motor itself is inserted between the two points of the spark gap 7. From this arrangement slightly damped oscillation wave currents are produced.

In the diagram illustrated in Figure 9 a loosely coupled system of connections is illustrated which is assumed to be for small motors for measuring purposes. A indicates the aerial conductor, S the electromagnet in the aerial conductor, 9 the inductance, 7 the spark gap, 5 and 6 condensers, E the earth, M the motor, and 1 and 2 stator connections of the motor. The motor is directly metallically connected with the oscillation circuit.

In Figure 10 a purely inductive coupling is employed for the motor circuit. The motor is connected with the secondary wire 10 as may be seen in Figure 11 in a somewhat modified diagram connection. The same applies to the diagram of Figure 12.

The diagrams hitherto described preferably allow of motors of small and medium strength to be operated. For large aggregates, however, they are too inconvenient as the construction of two or more oscillation circuits for large amounts of energy is difficult; the governing is still more difficult and the danger in switching on or off is greater.

A means of overcoming such difficulties is shown in Figure 13. The oscillation circuit here runs starting from the point x over condenser 5, variable inductance 9, spark gap 7 and the two segments (3^a and 4^a) forming arms of a Wheatstone bridge, back to x. If the motor is connected by brushes 3 and 4 transversely to the two arms of the bridge as shown in the drawings, electromagnetic oscillations of equal sign are induced in the stator surfaces 1 and 2 and the motor does not revolve. If however, the brushes 3 and 4 are moved in common with the conducting wires 1 and 2 which connect the brushes with the stator poles a certain alteration or displacement of the polarity is obtained and the motor commences to revolve.

The maximum action will result if one brush 3 comes on the central sparking contact 7 and the other brush 4 on the part x. They are however, usually in practice not brought on to the central contact 7 but only held in the path of the bridge segments 4^a and 3^a in order not to connect the spark gaps with the motor oscillation circuit.

As however, the entire oscillation energy can thereby not act on the motor it is better to carry out the same system according to the diagram 14. The diagram 14 differs from the foregoing only by the motor not being directly metallically connected with the segments of the commutator, but only a primary coil 9 which induces in a secondary coil 10, current which feeds the motor M and takes the place of the rotor. By this

arrangement a good transforming action is obtained, a loose coupling and also an oscillation circuit without a spark gap.

In Figure 15 the motor is not purely inductively as in 14, but directly metallically branched off from the primary coil (at x and x^1) after the principle of the auto-transformer.

In Figure 16 instead of an inductance a condenser 6 is in similar manner, and for the same object inserted between the segments 3^a and 4^a. This has the advantage that the segments 3^a and 4^a need not be made of solid metal but may consist of spiral coils whereby a more exact regulation is possible and further motors of high inductance may be employed.

The arrangements of Figures 17, 18 and 19 may be employed for use with resonance and particularly with induction condenser motors; between the large stator induction condenser surfaces, small reversing pole condensers are connected, which, as may be seen from Figures 17, 18 and 19 are led together to earth. Such reversing poles have the advantage that with large quantities of electrical energy the spark formation between the separate oscillation circuits ceases.

Figure 19 shows a further method which prevents electromagnetic oscillations of high number of alternations formed in the oscillation circuit striking back to the aerial conductor. It is based on the well known principle that a mercury lamp, one electrode of which is formed of mercury, the other of solid metal such as steel allows an electric charge to pass in only one direction from the mercury to the steel and not vice versa. The mercury electrode of the vacuum tube N is therefore connected with the aerial conductor and the steel electrode with the oscillation circuit. From this it results that charges can pass only from the aerial through the vacuum tube to the oscillation circuit, but not vice versa. Oscillations which are formed on being transformed in the oscillation circuit cannot pass to the aerial conductor.

In practice these vacuum tubes must be connected behind an electromagnet as the latter alone affords no protection against the danger of lightning.

As regards the use of spark gaps, all arrangements as used for wireless telegraphy may be used. Of course the spark gaps in large machines must have a sufficiently large surface. In very large stations they are cooled in liquid carbonic acid or better still in liquid nitrogen or hydrogen; in most cases the cooling may also take place by means of liquefied low homologues of the metal series or by means of hydrocarbons the freezing point of which lies at between −90° C. and −40° C. The spark gap casing must also be insulated and be of sufficient strength to be able to resist any pressure which may arise. Any undesirable excess super-pressure which may be formed must be automatically let off. I have employed with very good results mercury electrodes which were frozen in liquid carbonic acid, the cooling being maintained during the operation from the outside through the walls.

Figure 20 is one of the simplest forms of construction of an aerial network in combination with collectors, transformers and the like illustrated diagrammatically. E is here the earth wire, 8 the safety spark gap, 7 the working spark gap, 1 and 2 the stator surfaces of the motor, 5 a condenser battery, S the protective magnet which is connected with the coil in the aerial conductor, A^1 to A^{10} aerial antennæ with collecting balloons, N horizontal collecting or connecting wires from which, to the centre a number of connections run.

The actual collectors consist of metal sheaths preferably made of an aluminium magnesium alloy, and are filled with hydrogen or helium and are attached to copper plated steel wires. The size of the balloon is selected so that the actual weight of the balloon and the weight of the conducting wire is supported thereby. On the top of the balloon aluminium spikes, made and gilded in a special manner hereinafter described, are arranged in order to produce a conductor action. Small quantities of radium preparations, more particularly polonium-ionium or mesothorium preparations considerably increase the ionization, and therewith the action of these collectors.

In addition to metal balloons, fabric balloons which are superficially metal coated according to Schoop's metal spraying process, may however also be employed. A metallic surface may also be produced by lacquering with metallic bronzes, preferably according to Schoop's spraying process or lacquering with metallic bronze powders in two electrical series of widely different metals, because thereby the collecting effect is considerably increased.

Instead of the ordinary round balloons, elongated cigar shaped ones may be employed. In order also to utilize the frictional energy of the wind, patches or strips of non-conducting substances which produce electricity by friction, may be attached to the metallized balloon surfaces. The wind will impart a portion of its energy in the form of frictional electricity, to the balloon casing, and thereby the collecting effect is substantially increased.

In practice however, very high towers (up to 300 metres is fully admissible) may be employed as antennæ. In these towers copper tubes rise freely further above the top of the tower. A gas lamp secured

against the wind is then lit at the point of the copper tube and a netting is secured to the copper tube over the flame of this lamp to form a collector. The gas is conveyed through the interior of the tube up to the summit. The copper tube must be absolutely protected from moisture at the place at which it enters the tower and also rain must be prevented running down the walls of the tower which might lead to a bad catastrophe. This is done by bell shaped enlargements which expand downwards, being arranged in the tower in the form of high voltage insulators of Siamese pagodas.

Special attention must be devoted to the foundations of such towers. They must be well insulated from the ground, which may be obtained by first embedding a layer of concrete in a box form to a sufficient depth in the ground and inserting in this an asphalt lining and then glass bricks cast about 1 or 2 metres in thickness. Over this in turn there is a ferro-concrete layer in which alone the metal foot of the tube is secured. This concrete block must be at least 2 metres from the ground and be fully protected at the sides by a wooden covering, from moisture. In the lower part of the tower a wood or glass house for the large condenser batteries or for the motors may be constructed. In order to lead the earth connection to the ground water, a well insulated pit constructed of vitreous bricks, must be provided. Several such towers are erected at equal distances apart and connected with a horizontal conductor. The horizontal connecting wires may either run directly from tower to tower or be carried on bell shaped insulators similar to those in use for high voltage conductors. The width of the network may be of any suitable size and the connection of the motors can take place at any suitable places.

In order to collect large quantities of electricity with few aerials it is well to provide the aerial conductor with batteries of condensers as shown in two methods of construction in Figures 21 and 22. In Figure 21 the batteries of condensers 5 are connected on the one hand with the aerial electricity collectors Z by the aerial conductor A, and on the other hand interconnected in series with an annular conductor from which horizontal conductors run to the connecting points C to which the earth wire is connected.

Figure 22 shows a similar arrangement. Should two such series of antennæ rings be shown by a voltmeter to have a large difference of potential (for example, one in the mountains and one in the plain) or even of different polarity these differences may be compensated for by connecting sufficiently large condenser batteries ($5, 5^a, 5^b$) by means of Maji star conductors D and D^1. In Figure 23 a connection of three such rings of collectors to form a triangle with a central condenser battery is illustrated.

The condenser batteries of such large installations must be embedded in liquefied gases or in liquids freezing at very low temperatures. In such cases a portion of the atmospheric energy must be employed for liquefying these gases. It is also preferable to employ pressure. By this means the condenser surfaces may be diminished, and still allow for large quantities of energy to be stored, secure against breakdown. For smaller installations the immersing of the condensers in well insulated oil or the like, suffices. Solid substances on the other hand cannot be employed as insulators.

The arrangement in the diagrams hitherto described was always such that the condenser batteries were connected with both poles directly to the aerial conductors. An improved diagram of the connections for obtaining atmospheric electricity for the condenser batteries has however, been found to be very advantageous, this arrangement consists in that they are connected by only one pole (unipolar) to the collecting net-work. Such a method of arrangement is very important, as by means of it a constant current and an increase of the normal working pressure or voltage is obtained. If for example a collecting balloon aerial which is allowed to rise to a height of 300 metres, shows 40,000 volts above earth voltage, in practice it has been found that the working voltage (with a withdrawal of the power according to the method hereinbefore described by means of oscillating spark gaps and the like) is only about 400 volts. If however, the capacity of the condenser surfaces be increased, which capacity in the above mentioned case was equal to that of the collecting surface of the balloon aerials, to double the amount, by connecting the condenser batteries with only one pole, the voltage rises under an equal withdrawal of current up to and beyond 500 volts. This can only be ascribed to the favourable action of the connecting method.

In addition to this substantial improvement it has also been found preferable to insert double inductances with electromagnets and to place the capacities preferably between two such electromagnets. It has also been found that the useful action of such condensers can be further increased if an induction coil be connected as inductive resistance to the unconnected pole of the condenser, or still better if the condenser itself be made as an induction condenser. Such a condenser may be compared with a spring which when compressed carries in itself accumulated force, which it again gives off when released. In charging, a charge with reversed sign is formed at the

other free condenser pole, and if through the spark gap a short circuit results, the accumulated energy is again given back since now new quantities of energy are induced at the condenser pole connected with the conductor network, which in fact charges with opposite signs to that at the free condenser pole. The new induced charges have of course the same sign as the collector network. The whole voltage energy in the aerial is thereby however increased. In the same space of time larger quantities of energy are accumulated than is the case without such inserted condenser batteries.

In Figures 24 and 25 two different diagrams of connections are more exactly illustrated, Figure 24 shows a collecting balloon and the diagram of the connections to earth. Figure 25 four collecting balloons and the parallel connection of the condenser batteries belonging thereto.

A is the collecting balloon made of an aluminium magnesium alloy (electron metal, magnalium) of a specific gravity of 1.8 and a thickness of plate 0.1 to 0.2 mm. Inside there are eight strong vertical ribs of T shaped section about 10 to 20 mm. in height and about 3 mm. in thickness with the projecting part directed inwards (indicated by *a*, *b*, *c*, *d* and so forth); they are riveted together to form a firm skeleton and are stiffened in a horizontal direction by two cross ribs. The ribs are further connected with one another internally and transversely by means of thin steel wires, whereby the balloon obtains great power of resistance and elasticity. Rolled plates of 0.1 to 0.2 mm. in thickness made of magnalium alloy are then either soldered or riveted on this skeleton so that a fully metallic casing with smooth external surface is obtained. Well silvered or coppered aluminium plated steel wires run from each rib to the fastening ring 2. Further, the coppered steel hawser L preferably twisted out of separate thin wires (shown in dotted lines in Figure 24) and which must be long enough to allow the balloon to rise in the desired height, leads to a metal roller or pulley 3 and from thence to a winch W, well insulated from the earth. By means of this winch, the balloon, which is filled with hydrogen, or helium, can be allowed to rise to a suitable height (300 to 5,000 metres) and brought to the ground for recharging or repairs.

The actual current is taken directly through a friction contact from the metal roller 3 or from the wire, or even from the winch or simultaneously from all three by means of brushes (3, 3^a and 3^b). Beyond the brushes the conductor is divided, the paths being:—firstly over 12 to the safety spark gap 8, from thence to the earth conductor E^1, and secondly over electromagnet S^1, point 13, to a second loose electromagnet having an adjustable coil S^2, then to the spark gap 7 and to the second earth conductor E^2. The actual working circuit is formed through the spark gap 7, condensers 5 and 6, and through the primary coil 9; here the static electricity formed by oscillatory discharges is accumulated and converted into high frequency electromagnetic oscillations. Between the electromagnets S^1 and S^2 at the crossing point 13, four condenser batteries are introduced which are only indicated diagrammatically in the drawings each by one condenser. Two of these batteries (16 and 18) are made as plate condensers and prolonged by regulating induction coils or spirals 17 and 19 while the two others (21 and 23) are induction condensers. As may be seen from the drawings each of the four condenser batteries 16, 18, 21, 23 is connected only by one pole to the aerial or to the collector conductor. The second poles 17, 19, 22, 24 are open. In the case of plate condensers having no inductive resistance an induction coil is inserted. The object of such a spiral or coil is the displacement of phase of the induction current by ¼ periods, whilst the charging current of the condenser poles which lie free in the air, works back to the collector aerial. The consequence of this is that in discharges in the collector aerial the back inductive action of the free poles allows a higher voltage to be maintained in the aerial collecting conductor than would otherwise be the case. It has also been found that such a back action has an extremely favourable effect on the wear of the contacts. Of course the inductive effect may be regulated at will within the limits of the size of the induction coil, the length of the coil in action being adjustable by means of wire connection without induction (see Fig. 24, No. 20).

S^1 and S^2 may also be provided with such regulating devices in the case of S^2 (illustrated by 11). If excess voltage be formed it is conducted to earth through the wire 12 and spark gap 8 or through any other suitable apparatus, since this formation would be dangerous for the other apparatus.

The action of these condenser batteries has already been hereinbefore described.

The small circles on the collector balloon indicate places at which zinc amalgam or gold amalgam or other photoelectric acting metals in the form of small patches in extremely thin layers (.01 to .05 mm. in thickness) are applied to the balloon casing of light metal. Such metallic patches may also be applied to the entire balloon as well as in greater thickness to the conducting network. The capacity of the collector is thereby considerably strengthened at the surface. The greatest possible effect in collecting may be obtained by polonium amalgams and the like. On the surface of the

collector balloon metal points or spikes are also fixed along the ribs, which spikes serve particularly for collecting the collector charge. Since it is well known that the resistance of the spikes is less the sharper the spike is, for this purpose it is therefore extremely important to employ as sharp spikes as possible. Experiments made as regards these have shown that the formation of the body of the spike or point also plays a large part. for example. spikes made of bars or rollers with smooth surfaces, have a many times greater point resistance as collector accumulator spikes than those with rough surfaces. Various kinds of spike bodies have been experimented with for the collector balloons hereinbefore mentioned. The best results were given by spikes which were made in the following way. Fine points made of steel, copper, nickel, or copper and nickel alloys, were fastened together in bundles and then placed as anode with the points in a suitable electrolyte (preferably in hydrochloric acid or muriate of iron solutions) and so treated with weak current at 2 to 3 volts pressure. After 2 to 3 hours according to the thickness of the spikes or pins the points become extremely sharp and the bodies of the spikes have a rough surface. The bundle can then be removed and the acid washed off with water. The spikes are then placed as cathode in a bath consisting of solution of gold, platinum, iridium, paladium or wolfram salts or their compounds and coated at the cathode galvanically with a thin layer of precious metal, which must however be sufficiently firm to protect them from atmospheric oxidation.

Such spikes act at a 20 fold lower voltage almost as well as the best and finest points made by mechanical means. Still better results are obtained if polonium or radium salts are added to the galvanic bath when forming the protective layer or coating. Such pins have a low resistance at their points and even at one volt and still lower pressures have an excellent collector action.

In Figure 24 the three unconnected poles are not connected with one another in parallel. That is quite possible in practice without altering the principle of the free pole. It is also preferable to interconnect in parallel to a common collector network, a series of collecting aerials.

Figure 25 shows a diagram for such an installation. A^1. A^2, A^3, A^4 are four metal collector balloons with gold or platinum coated spikes which are electrolytically made in the presence of polonium emanations or radium salts, which spikes or needles are connected over four electro-magnets S^1, S^2, S^3, S^4, through an annular conductor R. From this annular conductor four wires run over four further electromagnets S^a, S^b, S^c, S^d, to the connecting point 13. There the conductor is divided, one branch passing over 12 and the safety spark gap 8 to the earth at E^1, the other over inductive resistance J and working spark gap 7 to the earth at E^2. The working circuit, consisting of the condenser 5 and 6 and a resonance motor or a condenser motor M, such as hereinbefore described, is connected in proximity round the sparking gap section 7.

Instead of directly connecting the condenser motor of course the primary circuit for high frequency oscillatory current may also be inserted.

The condenser batteries are connected by one pole to the annular conductor R and can be either inductionless (16 and 18) or made as induction condensers as shown by 21 and 23. The free poles of the inductionless condensers are indicated by 17 and 19, those of the induction condensers by 22 and 24. As may be seen from the drawings all these poles 17, 22, 19, 24 may be interconnected in parallel through a second annular conductor without any fear that thereby the principle of the free pole connection will be injured. In addition to the advantages already set forth the parallel connection also allows of an equalization of the working pressure in the entire collector network. Suitably constructed and calculated induction coils 25 and 26 may also be inserted in the annular conductor of the free poles, by means of which a circuit may be formed in the secondary coils 27 and 28 which allows current produced in this annular conductor by fluctuations of the charges or the like appearances to be measured or otherwise utilized.

According to what has been hereinbefore stated separate collector balloons may be connected at equidistant stations distributed over the entire country, either connected directly with one another metallically or by means of intermediate suitably connected condenser batteries through high voltage conductors insulated from earth. The static electricity is converted through a spark gap into dynamic energy of a high number of oscillations and may in such form be coupled as a source of energy by means of a suitable method of connecting, various precautions being observed, and with special regulations. The wires leading from the collector balloons have hitherto been connected through an annular conductor without this endless connection, which can be regarded as an endless induction coil, being able to exert any action on the whole conductor system.

It has now been found that if the network conductor connecting the aerial collector balloons with one another is not made as a simple annular conductor, but preferably short circuited in the form of coils over a

condenser battery or spark gap or through thermionic tubes or valves or audions, then the total collecting network exhibits quite new properties. The collection of atmospheric electricity is thereby not only increased but an alternating field may be easily produced in the collector network. Further, the atmospheric electrical forces showing themselves in the higher regions may also be directly obtained by induction. In Figures 26 and 28 a form of construction is shown on the basis of which the further foundations of the method will be more particularly explained.

In Figure 26 1, 2, 3, 4 are metal collector balloons, 5, 6, 7, 8 their metallic aerial conductors and I the actual collector network. This consists of five coils and is mounted on high voltage insulators in the air, on high voltage masts (or with a suitable construction of cable embedded in the earth). One coil has a diameter of 1 to 100 km. or more. S and S^1 are two protective electromagnets, F the second safety section against excess voltage, E its earth conductor and E^1 the earth conductor of the working section. When an absorption of static atmospheric electricity is effected through the four balloon collectors, the current in order to reach the earth connection E^1 must flow spirally through the collector network over the electromagnet S, primary induction coil 9, conductor 14, anode A of the audion tube, incandescent cathode K, as the way over the electromagnet and safety spark gap F offers considerably greater resistance. Owing to the fact that the accumulated current flows in one direction, an electromagnetic alternating field is produced in the interior of the collector network coil, whereby the whole free electrons are directed more or less into the interior of the coil. An increased ionization of the atmosphere is therefore produced. In consequence of this the points mounted on the collector balloon show a considerably reduced resistance and therefore increased static charges between the points on the balloon and the surrounding atmosphere are produced. The result of this is a considerably increased collector effect.

A second effect which could not be obtained otherwise is obtained by the electromagnetic alternating field which running parallel to the earth surface, acts more or less with a diminishing or increasing effect on the earth magnetic field, whereby in the case of fluctuations in the current a return induction current of reversed sign is always produced in the collector coil by earth magnetism. Now if, however, a constantly pulsating continuous alternating field is produced as stated in the above collector network I, an alternating current of the same periodicity is produced also in the collecting network coil. As the same alternating field is further transmitted to the aerial balloon, the resistance of its points is thereby considerably reduced, whilst the collector action is considerably increased. A further advantage is that positive electrons which collect on the metal surfaces during the conversion into dynamic current produce a so-called drop of potential of the collector area. As an alternating field is present, the negative ions surrounding the collector surfaces, when discharge of the collector surfaces takes place produce by the law of induction, an induction of reversed sign on the collector surface and so forth (that is to say again a positive charge). In addition to the advantages hereinbefore set forth, the construction of connecting conductors in coil form when of sufficiently large diameter, allows of a utilization of energy arising in higher regions also in the simplest way. As is well known electric discharges frequently take place at very great elevations which may be observed, such as St. Elmo's fires or northern lights. These energy quantities have not been able to be utilized up to now. By this invention all these kinds of energy, as they are of an electromagnetic nature and the direction of the axis of the collector coils stands at right angles to the earth's surface, can be more or less absorbed in the same way as a receiver in wireless telegraphy absorbs waves coming from a far distance. With a large diameter of the spiral it is possible to connect large surfaces and thereby to take up also large quantities of energy.

It is well known that large wireless stations in the summer months, and also in the tropics are very frequently unable to receive the signals in consequence of interruptions which are caused by atmospheric electricity, and this takes place with vertical coils of only 40 to 100 m. diameter. If on the contrary horizontal coils of 1 to 100 km. diameter be employed very strong currents may be obtained through discharges which are constantly taking place in the atmosphere. Particularly in the tropics or still better in the polar regions where the northern lights are constantly present, large quantities of energy may probably be obtained in this way. A coil with several windings should act the best. In similar manner any alteration of the earth magnetism should act inductively on such a coil.

It is not at all unlikely that earthquakes and spots on the sun will also produce an induction in such collector coils of sufficient size. In similar manner this collector conductor will react on earth currents more particularly when they are near the surface of the earth or even embedded in the earth. By combining the previous kind of current collectors so far as they are adapted for

the improved system with the improved possibilities of obtaining current the quantities of free natural energy which are to be obtained in the form of electricity are considerably increased.

In order to produce in the improved collector coil uniform current oscillations of an undamped nature so-called audion high vacuum or thermionic tubes of suitable connection are employed instead of the previously known spark gaps (Fig. 26, Nos. 9–18). The main aerial current flows through electromagnet S (which in the case of a high number of alternations is not connected here but in the earth conductor E^1) and may be conveyed over the primary coils in the induction winding through wire 14 to the anode A of the high vacuum grid tube. Parallel with the induction resistance 9 a regulating capacity of suitable size, such as condenser 11 is inserted. In the lower part of the vacuum grid tube is arranged the incandescent filament or the cathode K which is fed through a battery B. From the battery B two branches run, one to the earth conductor E^1 and the other through battery B^1 and secondary coil 10 to the grid anode *g* in the vacuum tube. By the method of connections shown in dotted lines, a desired voltage at the grid electrode *g* may also be produced through the wire 17 which is branched off from the main current conductor through switches 16 and some small condensers (*a*, *b*, *c*, *d*) connected in series, and conductor 18, without the battery B^1 being required.

The action of the entire system is somewhat as follows:—

On the connecting conductor of the aerial collector network being short circuited to earth, the condenser pole 11 is charged and slightly damped oscillations are formed in the short circuited existing oscillation circuit formed of the condenser 11 and self inductance 9. In consequence of the coupling through coil 10, fluctuations of voltage take place in the grid circuit 15 with the same frequency, which, fluctuations in turn influence the strength of the electrode current passing through the high vacuum amplyfying tube and thus produce current fluctuations of the same frequency in the anode circuit. A permanent supply of energy to the oscillation circuits 9 and 10 consequently takes place, until a condition of balance is set up, in which the consumed oscillation energy is equal to that absorbed. Thereby constant undamped oscillations are now produced in the oscillation circuits 9–11.

For regular working of such oscillation producers high vacuum strengthening tubes are necessary and it is also necessary that the grid and anode voltages shall have a phase difference of 180° so that if the grid is negatively charged, then the anode is positively charged and vice versa. This necessary difference of phase may be obtained by most varied connections, for example, by placing the oscillation circuit in the grid circuit or by separating the oscillation circuit and inductive coupling from the anodes and the grid circuit and so forth.

A second important factor in this way of converting static atmospheric electricity into undamped oscillations is that care must be taken that the grid and anode voltages have a certain relation to one another; the latter may be obtained by altering the coupling and a suitable selection of the self induction in the grid circuit, or as shown by dotted lines 18, 17, 16 by means of a larger or smaller number of condensers of suitable size connected in series; in this case the battery B^1 may be omitted. With a suitable selection of the grid potential a glow discharge takes place between the grid *g* and the anode A, and accordingly at the grid there is a cathode drop and a dark space is formed. The size of this cathode drop is influenced by the ions which are emitted in the lower space in consequence of shock ionization of the incandescent cathodes K and pass through the grid in the upper space. On the other hand the number of the ions passing through the grid is dependent on the voltage between the grid and the cathode. Thus if the grid voltage undergos periodic fluctuations (as in the present case) the amount of the cathode drop at the grid fluctuates and consequently the internal resistance of the tube correspondingly fluctuates, so that when a back coupling of the feed circuit with the grid circuit takes place, the necessary means are afforded for producing undamped oscillations and of taking current, according to requirements from the collecting conductor.

The frequency of the undamped oscillations produced is with a suitably loose coupling equal to the self frequency of the oscillation circuits 9 and 10. By a suitable selection of the self induction of the coil 9 and capacity 11 it is possible to extend from frequencies which produce electromagnetic oscillations of only a few metres wave length down to the lowest practical alternating current frequency. For large installations a suitable number of frequency producing tubes in the form of the well known high vacuum transmission tubes of .5 to 2 kw. in size may be connected in parallel so that in this respect no difficulty exists.

The use of such tubes for producing undamped oscillations, and also the construction and method of inserting such transmission tubes in an accumulator or dynamo circuit is known and also that such oscillation producing tubes only work well at voltages of 1,000 up to 4,000 volts, so that on the contrary their use at lower voltages is

considerably more difficult. By the use of high voltage static electricity this method of producing undamped oscillations as compared with that through spark gaps must be regarded as an ideal solution particularly for small installations of outputs of from 1 to 100 kw.

By the application of safety spark gaps, with interpolation of electro-magnets, not only is short circuiting avoided but also the taking up of current is regulated. Oscillation producers inserted in the above way form a constantly acting electromagnetic alternating field in the collector coil, whereby as already stated, a considerable accumulating effect takes place. The withdrawal wire or working wire is connected at 12 and 13, but current may be taken by means of a secondary coil which is firmly or movably mounted in any suitable way inside the large collector coil, i. e. in its electromagnetic alternating field, so long as the direction of its axis runs parallel with that of the main current collecting coil.

In producing undamped oscillations of a high frequency (50,000 per second and more) in the oscillation circuits 9 and 11, electromagnets S and S^1 must be inserted if the high frequency oscillations are not to penetrate the collector coil, between the oscillation producers and the collector coil. In all other cases they are connected shortly before the earthing (as in Figs. 27 and 28).

In Figure 27 a second method of construction of the connecting conductor of the balloon aerials is illustrated in the form of a coil. The main difference consists in that in addition to the connecting conductor I another annular conductor II is inserted parallel to the former on the high voltage masts in the air (or embedded as a cable in the earth) but both in the form of a coil. The connecting wire of the balloon aerials is indicated as a primary conductor and also as a current producing network; the other is the consumption network and is not in unipolar connection with the current producing network.

In Figure 27 the current producing network I is shown with three balloon collectors 1, 2, 3 and aerial conductors 4, 5, 6; it is short circuited through condenser 19 and inductance 9. The oscillation forming circuit consists in this diagram of spark gap *f*, inductance 10, and condenser 11; the earth wire E, is connected to earth over electromagnet S^1. F is the safety spark gap which is also connected to earth through a second electromagnet S at E. On connecting up the condenser circuit 11 this is charged over the spark gap *f* whereby an oscillatory discharge is formed. This discharging current acts through inductance 10 on the inductively coupled secondary 9, whereby in the producing network a modification of the potential of the condenser 19 is produced. The consequence of this is that oscillations arise in the coil shaped producer network. These oscillations induce a current in the secondary circuit II, which has a smaller number of windings and a less resistance, the voltage of which, according to the proportion of the number of windings and of the ohmic resistance, is considerably lower whilst the current strength is greater.

In order to convert the current thus obtained into current of an undamped character, and to tune its wave lengths, a sufficiently large regulatable capacity 20 is inserted between the ends 12 and 13 of the secondary conductor II. Here also current may be taken without an earth conductor, but it is advisable to insert a safety spark gap E^1 and to connect this with the earth over an electromagnet S^2.

The producer network may be connected with the working network II over an inductionless condenser 21 or over an induction condenser 22, 23. In this case the secondary conductor is unipolarly connected with the energy conductor.

In Figure 28 the connecting conductor between the separate accumulator balloons is carried out according to the autotransformer principle. The collecting coil connects four aerial balloons 1, 2, 3, 4, the windings of which are not made side by side but one above the other. In Figure 28 the collector coil I is shown with a thin line, the metallically connected prolongation coils II with a thick line. Between the ends I^1 and II^1 of the energy network I a regulating capacity 19 is inserted. The wire I^1 is connected with the output wire and with the spark gap F.

As transformer of the atmospheric electricity an arrangement is employed which consists in using rotary pairs of condensers in which the one stator surface B is connected with the main current, whilst the other A is connected with the earth pole. Between these pairs of short circuited condensers are caused to rotate from which the converted current can be taken by means of two collector rings and brushes, in the form of an alternating current, the frequency of which is dependent on the number of balloons and the revolutions of the rotor. As the alternating current formed in the rotor can act, in this improved method of connection described in this invention, through coils 10 on the inductance 9, an increase or diminution of the feed current in I can be obtained according to the direction of the current by back induction. Current oscillations of uniform rhythm thereby result in the coil shaped windings of the producer net-work.

As the ends of this conductor are short cir-

cuited through the regulatable condenser 19 these rhythms produce short circuited undamped oscillations in the energy conductor, the periodicity and wave lengths of which oscillations can be adjusted according to desire by altering the capacity 19 to a given wave length and therewith also to a given frequency. These currents may also be employed in this form directly as working current through the conductors II¹ and III. By inserting the condenser 20 a connection between these conductors may also be made, whereby harmonic oscillations of desired wave length are formed. By this means quite new effects as regards current distribution are obtained. The withdrawal of current can even take place without direct wire connection if, at a suitable point in the interior of the producing network (quite immaterially whether this has a diameter of 1 or 100 km.) a coil tuned to these wave lengths and of the desired capacity is firmly or movably mounted in the aerial conductor in such a way that its axial direction is in parallel with that of the collector coil. In this case a current is induced in the producing network, the size of which is dependent on the total capacity and resistance and also on the periodicity employed. A possibility is thereby afforded in future, of taking energy from the producer network by wireless means. As thereby in addition to atmospheric electricity also magnetic earth currents and the energy from the higher atmosphere (at least partially) may be simultaneously obtained, this last system for collecting the atmospheric energy is of particular importance for the future.

Of course everywhere instead of spark gaps suitable grid vacuum tubes may be employed as producers for undamped oscillations. The separate coils of the producer net-work with large diameters may be connected with one another through separate conductors all in parallel or all in series or in groups in series. By regulating the number of oscillations and also the extent of the voltage more or less large collector coils of this kind may be employed. The coils may also be divided spirally over the entire section. The coils may be carried out in annular form or also in triangular, quadrangular, hexagonal or octagonal form.

Of course wires may be carried from a suitable place to the centre or also laterally which serve the current waves as guides. This is necessary when the currents have to be conducted over mountains and valleys and so forth. In all these cases the current must be converted into a current of suitable periodicity.

As already hereinbefore mentioned separate collecting balloons may be directly metallically interconnected at equidistant stations distributed over the entire country or may be connected by interpolation of suitable condenser batteries by means of high voltage conductors. The static electricity is converted through a spark gap into dynamic energy of a high number of oscillations, and could then in such form, with a suitable arrangement of the connections, observing various measures of precaution, be employed as source of energy after separate or special regulation.

According to this invention in order to increase the collecting effect of the balloon in the aerial collector conductor or in the earth wire, radiating collectors are employed. These consist either of incandescent metal or oxide electrodes in the form of vacuum grid tubes, or electric arcs (mercury and the like electrodes) Nernst lamps, or finally flames of various kinds may be simply connected with the respective conductor.

It is well known that energy can be drawn off from a cathode consisting of an incandescent body opposite an anode charged with positive electricity (vacuum grid tube). Hitherto however, a cathode was always first directly placed opposite an anode, and secondly the system always consisted of a closed circuit.

Now if we dispense with the ordinary ideas in forming light or flame arcs in which a cathode must always stand directly opposite an anode, and if we place an incandescent cathode opposite an anode charged to a high potential or another body freely floating in the air, or regard the incandescent cathode only as a source of unipolar discharge (which represent group and point discharges in electro-static machines similar to unipolar discharges), it may be ascertained that incandescent cathodes and less perfectly all incandescent radiators, flames and the like admit of relatively large current densities and allow large quantities of electric energy to radiate into the open space in the form of electron streams as transmitters.

The object of this invention is as described below, if such incandescent oxide electrodes or other incandescent radiators or flames are not freely suspended in space but connected metallically with the earth so that they can be charged with negative terrestrial electricity, these radiators possess the property of absorbing the free positive electrical charges contained in the air space surrounding them (that is to say of collecting them and conducting them to earth). They can therefore, serve as collectors and have, in comparison to the action of the spikes, or points, a very large radius of action R; the effective capacity of these collectors is much greater than the geometrical capacity (R_0–) calculated in an electro-static sense.

Now as our earth is surrounded as is well

known, with an electro-static field and the difference of potential

$$\frac{\delta V}{\delta h}$$

of the earth field according to the latest investigations, is in summer about 60 to 100 volts and in winter 300 to 500 volts per metre of difference in height (δh), a simple calculation gives the result that when such a radiation collector or flame collector is arranged for example on the ground, and a second one is mounted vertically over it at a distance of 2,000 metres and both are connected by a conducting cable, there is a difference of potential in summer of about 2,000,000 volts and in winter even of 6,000,000 volts and more.

According to Stefan Boltzmann's law of radiation, the quantity of energy which an incandescent surface (temperature T) of 1 sq. cm. radiates in a unit of time into the open air (temperature T_o) is expressed by the following formula:

$$S = \sigma\ (T^4 - T^4{}_O)\ \text{watt/sq. cm.}$$

and the universal radiation constant σ is according to the latest researches of Ferry (Annales de Chimie et de physique 17 page 267 (1909)) equal to 6.30×10^{-12} watt/sq. cm.

Now if an incandescent surface of 1 sq. cm. shows, as compared with the surrounding space a periodic fall of potential δV it radiates (independent of the current direction, that is to say of the sign) in accordance with the above formula, for example at a temperature of 3725° C. an energy of 1.6 kw. per sq. cm. per second. As for the radiation the same value can be calculated for the collection of energy, but reversed. Now as carbon electrodes at the temperature of the electric arc support on the current basis a current density up to from 60 to 65 amperes per sq. cm. no difficulties will result in this direction in employing radiating collectors as accumulators.

If the earth be regarded as a cosmically insulated condenser in the sense of geometrical electro-statics x there results from the geometric (compare Ewald Rasch, "das elektrische Bogenlicht" (The electric arc light) page 169) capacity of the earth according to Chwolson:

For negative charging 1.3×10^{6} Coulomb

For negative potential $V = 10 \times 10^{8}$ volts. From this there results however, $EJT \cong 24.7 \times 10^{24}$ watt/Sec. Now if it is desired to make a theoretic short circuit through an earthed flame collector this would represent an electric total work of about 79,500 10^{10} kilowatt years. As the earth must be regarded as a rotating mechanism which is thermo-dynamically, electromagnetically, and also kinematically coupled with the sun and stars system by cosmic radiations and gravitation a diminution of the electric energy of the earth field is not to be feared. The energies which the incandescent collectors would withdraw from the earth field can only cause by the withdrawal of motor work a lowering of the earth temperature (temperature $T_E = 300$) and reduce this to that of the world space ($T = O$) by using the entire energy. This is however not the case as the earth does not represent a cosmically entirely insulated system. On the contrary there is conveyed to the same according to the recent value corrected by Ferry for the solar constants through the radiation from the sun an energy of 18,500 $\times 10^{10}$ kw. Accordingly any lowering of the earth temperature (T_E) without a simultaneous lowering of the sun's temperature (T_S) would contradict Stefan Boltzmann's law of radiation.

$$S = \sigma\ (T_S{}^4 - T_E{}^4).$$

From this it must be concluded that if the earth temperature (T_E) sinks, the total radiation S absorbed by the earth increases, and further also that the secular speed of cooling of the earth is directly dependent on that of the sun and the other radiators cosmically coupled with the sun and is connected most closely with these.

The incandescent radiation collectors may, according to this invention, be employed for collecting atmospheric electricity if they (1) are charged with the negative earth electricity (that is to say when they are directly connected by means of a metallic conductor with the earth) and (2) if large capacities (metal surfaces) charged with electricity are mounted opposite them as positive poles in the air. This is regarded as the main feature of the present invention as without these inventive ideas it would not be possible to collect with an incandescent collector, sufficiently large quantities of the electrical charges contained in the atmosphere as technology requires; the radius of action of the flame collectors would also be too small, especially if it be considered that the very small surface density (energy density) (σ about$=2 \times 7\ .\ 10^{9}$ St. E. per sq. cm.) does not allow of large quantities of charge being absorbed from the atmosphere.

x) Calculated according to Poisson's calculation;

$\Delta V = -4\pi\delta$; as here the alteration of the potential or potential gradients only takes place in the direction of the normal, this calculation assumes the simple form

$$\delta = \frac{1}{4\pi} \times \frac{\delta^2 V}{\delta n^2}$$

It has indeed already been proposed to employ flame collectors for collecting atmospheric electricity and it is known that

their collecting effect is substantially greater opposite the points. It is however, not known that the quantities of current which could hitherto be obtained are too small for technical purposes. According to my experiments the reason for this is to be found in the too small capacities of the collector conductor poles. If such flame or radiating collectors have no or only small positive surfaces, their radius of action for large technical purposes is too small. If the incandescent collectors be constantly kept in movement in the air they may collect more according to the speed of the movement, but this is again not capable of being carried out in practice.

By this invention the collector effect is considerably increased by a body charged with a positive potential and of the best possible capacity being also held floating (without direct earth connection) opposite such an incandescent collector which is held floating in the air at a desired height. If for example, a collecting balloon of sheet metal or of metalized balloon fabric be caused to mount to 300 up to 3,000 metres in the air and as positive pole it is brought opposite such a radiating collector connected by a conductor to earth, quite different results are obtained.

The metallic balloon shell (with a large surface) is charged to a high potential by the atmospheric electricity. This potential is greater the higher the collecting balloon is above the incandescent collector. The positive electricity acts concentratedly on the anode floating in the air as it is attracted through the radiation shock ionization, proceeding from the incandescent cathode. The consequence of this is that the radius of action of the incandescent cathode collector is considerably increased and thereby also the collecting effect of the collecting balloon surface. Further the large capacity of the anode floating in the air plays therefore an important part because it allows of the taking of large charges, and thereby a more uniform current is obtained even when there is a large consumption: this cannot be the case with small surfaces.

In the present case the metallic collecting balloon is a positive anode floating in the air and the end of the earth conductor of this balloon serves as positive pole surface opposite the surface of the radiating incandescent cathode, which in turn is charged with negative earth electricity being conductingly connected to earth.

The process may be carried out by two such contacts (negative incandescent cathode and anode end of a capacity floating in the air) a condenser and an inductive resistance being switched on in parallel, whereby simultaneously undamped oscillations may be formed.

In very large installations it is advisable to connect two such radiating collectors in series. Thus an arc light incandescent cathode may be placed below on the open ground and an incandescent cathode which is heated by special electro-magnetic currents be located high in the air. Of course for this the special vacuum Liebig tubes with or without grids may also be employed. An ordinary arc lamp with oxide electrodes may be introduced on the ground and the positive pole is not directly connected with the collecting balloon, but through the upper incandescent cathode or over a condenser. The method of connecting the incandescent cathode floating in the air may be seen in Figs. 29–33.

B is the air balloon, K a Cardan ring (connection with the hawser) C the balloon, L a good conducting cable, P a positive pole, N negative incandescent cathode, and E earth conductor.

Fig. 29 represents the simplest form of construction. If electric oscillations are produced below on the ground by means of a carbon arc lamp or in other suitable way a considerably greater electric resistance is opposed to that in the direct way by inserting an electrical inductive resistance 9. Consequently between P and N, a voltage is formed, and as, over N and P only an inductionless ohmic resistance is present, a spark will spring over so long as the separate induction co-efficients and the like are correctly calculated. The consequence of this is that the oxide electrode (carbon or the like) is rendered incandescent and then shows as incandescent cathode an increased collecting effect. The positive poles must be substantially larger than the negative in order that they may not also become incandescent. As they are further connected with the large balloon area which has a large capacity and is charged at high voltage, an incandescent body which is held floating in the air and a positive pole which can collect large capacities is thereby obtained in the simplest way. The incandescent cathode is first caused to become incandescent by means of separate energy produced on the earth, and then maintained by the energy collected from the atmosphere.

Fig. 30 only shows the difference that instead of a round balloon a cigar shaped one (of metal or metalized fabric) may be employed and also a condenser 5 is inserted between the incandescent cathode and the earth conductor so that a short circuited oscillation circuit over P. N 5 and 9 is obtained. This has the advantage that quite small quantities of electricity cause the cathode to become incandescent and much larger cathode bodies may be rendered incandescent.

In this form of construction both the in-

candescent cathode and also the positive electrode may be enclosed in a vacuum chamber as may be seen in Fig. 32. A cable L is carried well insulated through the cover of a vessel and ends in a condenser disc 5. The cover is arched in order to keep off the rain. The vessel is entirely or partially made of magnetic metal and well insulated inside and outside. Opposite the disc 5 another disc 6 and on this again a metallic positive pole of the vacuum tube *g* with the incandescent cathode (oxide electrode) N is arranged. The negative electrode is on the one hand connected with the earth conductor E, and on the other hand with the inductive resistance 9 which is also connected with the cable L with the positive pole and wound round the vessel in coils. The action is exactly the same as that in Fig. 29 only instead of an open incandescent cathode one enclosed in vacuo is employed. As in such collectors only small bodies can be brought to incandescence in large installations a plurality of such vacuum tubes must be inserted in proximity to one another. According to the previous constructions Figs. 31 and 33 are quite self evident without further explanations.

Figs. 34–37 represent further diagrams of connections over radiating and flame collectors, and in fact, how they are to be arranged on the ground.

Fig. 34 shows an arc light collector with oxide electrodes for direct current and its connection; Fig. 35 a similar one for alternating current, Fig. 36 an incandescent collector with a Nernst lamp and Fig. 37 a similar one with a gas flame.

The positive pole 1 of the radiating collectors is always directly connected to the aerial collecting conductor A. In Fig. 34 this is further connected over the condenser battery 5 with a second positive electrode 3. The direct current dynamo *b* produces current which flows over between the electrodes 3 and 2 as an arc light. On the formation of an arc the negative incandescent electrode 2 absorbs electricity from the positive poles standing opposite it and highly charged with atmospheric electricity and conveys the same to the working circuit. The spark gap 7, inductive resistance 9 and induction coil 10 are like the ones previously described. The protective electromagnet S guards the installation against earth circuiting, the safety spark gap 8 from excess voltage or overcharging.

In Fig. 35 the connection is so far altered that the alternating current dynamo feeds the exciting coil 11 of the induction condenser. 12 is its negative and 13 its positive pole; if the coil 3 on the magnet core of the dynamo is correctly calculated and the periodicity of the alternating current is sufficiently high an arc light can be formed between the two poles 1 and 2. As the cathode 2 is connected with the negatively charged earth, and therefore always acts as a negative pole, a form of rectification of the alternating current produced by the dynamo 3 is obtained, the second half of the period is always suppressed. The working circuit may be carried out in the same way as in Fig. 34; the working spark gap 7 may however be dispensed with, and instead thereof between the points *n* and *m* a condenser 5 and an induction resistance 9 may be inserted from which the current is taken inductively.

Fig. 36 represents a form of construction similar to Fig. 34 only that here instead of an arc lamp a Nernst incandescent body is employed. The Nernst lamp is fed through the battery 3. The working section is connected with the negative pole, the safety spark gap with the + poles. The working spark gap 7 may also be dispensed with and the current for it taken at 12 over the oscillation circuit 5, 11 (shown in dotted lines).

Flame collectors (Fig. 37) may also be employed according to this invention. The wire network 1 is connected with the aerial collector conductor A and the burner with the earth. At the upper end of the latter, long points are provided which project into the flame. The positive electrode is connected with the negative over a condenser 5 and the induction coil 9 with the earth.

The novelty in this invention is firstly, the use of incandescent cathodes opposite positive poles which are connected with large metallic capacities as automatic collecting surfaces, (2) the connection of the incandescent cathodes with the earth whereby, in addition to the electricity conveyed to them from the battery or machine which causes the incandescing, also the negative charge of the earth potential is conveyed, and (3) the connection of the positive and negative poles of the radiating collectors over a condenser circuit alone or with the introduction of a suitable inductive resistance, whereby simultaneously an oscillatory oscillation circuit may be obtained. The collecting effect is by these methods quite considerably increased.

I declare that what I claim is:—

1. An electrical energy generating system, comprising a conducting surface for static charges, means to support same at a distance above the earth, a conductor leading to the earth level, a spark gap associated with said conductor to convert electrostatic charges into electromagnetic high frequency oscillations means to supply said electromagnetic energy to a net work, and a spark gap of greatly increased relative resistance in parallel therewith.

2. An electrical energy generating system

comprising a conductor, means to support same above the earth level, an inductance therein, a spark gap associated with said conductor, a second spark gap of much higher relative resistance in parallel therewith and an energy receiving circuit coupled with the spark gap of lesser resistance.

3. An electrical energy generating system comprising a collecting surface, means to support same above the earth level, a conductor connecting said collecting surface with the earth level, a choke in said conductor, an electromagnetic resistance converting electrostatic energy to electromagnetic energy, a safety higher resistance in parallel therewith and a net work coupled with the conversion resistance of lesser value.

4. An electrical energy generating system comprising electric conductors spaced above the earth to form electromagnetic oscillating circuits, conductors connecting to earth level, electrostatic to electromagnetic energy conversion means therein, a safety high electrostatic resistance in parallel therewith and means to alter the electromagnetic characteristic of the circuits.

5. An electrical energy generating system comprising in combination a static collecting surface arranged above the earth, conductors connecting to earth level, a pair of spark gaps in parallel of different electrostatic resistance, a utilization net work shunted across the spark gap of lesser resistance and an electromagnetic choke in said conductors.

6. An electrical energy generating system comprising an open circuit energy collecting aerial, a pair of sparking gaps in parallel of widely different resistance, connected thereto and a closed electric oscillation circuit in shunt across the gap of lesser resistance

7. An electrical energy generating system comprising an open circuit energy collecting aerial, a pair of sparking gaps in parallel of widely different resistance connected thereto, a closed electric oscillation circuit in shunt across the gap of lesser resistance, a plurality of electrostatic collecting surfaces, means to connect said collecting surfaces in parallel in groups and means to connect said groups symmetrically with said aerial.

In witness whereof, I have hereunto signed my name this 30 day of Dec., 1920, in the presence of two subscribing witnesses.

HERMANN PLAUSON.

Witnesses:
H. F. Armstrong,
W. H. Beeston.

Nu Energy Technologies

A Leading Source for Clean & Economical Energy...
powering our future with revolutionary radio ionic energy

INVENTION AND DISCOVERY

Radiant Energy Power Generation

Nuclear Science has been incorrect since the advent of the Atomic "chain reaction"

It would be logical to expect that the discovery of fission was the authoritative answer to nuclear science. It would be normal also to expect that no single individual could really claim to be its "inventor," since it is a natural physical process. The efforts of hundreds of dedicated scientists were required to bring it into existence. Countless descriptions on the origin of atomic decay have been theorized. Since the advent of the atomic chain reaction nuclear science has been written into scientific law. However, this was based on atomic-bomb era mentality and is not correct according to what the author of this book has unveiled.

Mr. Bruce A. Perreault knows the truth about nuclear reactions. He is a catalyst who will ultimately lead humankind to the successful development of radiant energy power generators.

By any normal standard this man is the discoverer of a revised nuclear standard that promises to open new roads to invention and discovery.

Bruce A. Perreault, P. O. Box 22, Rumney, New Hampshire 03266-0022 USA
Copyrighted © 1999, 2000 & 2001 All Rights Reserved

Website: http://www.nuenergy.org

ISBN 1-930216-01-7
52495
9 781930 216013

$24.95 USD Retail

advertisement

TAX REFORM
SHOULDN'T HURT
CALIFORNIANS
CALL CONGRESSM
JEFF DENHAM

EVERYTHING
A NEW
MOM NEEDS
Baby Depot
at Burlington
SHOP NOW



Step 1: Round Up Some LEDs!

advertisement

ALLIED ELECTRONICS
Make a
Stronger
Connection
Avoid Failures with
Terminations That last
PHOENIX CONTACT
LEARN MORE

About This Instructable

8,885 views

59 favorites

License: (cc) BY-NC-SA

Free Energy From LEDs

by Throttle78 (/member/Throttle78/) in electronics (/technology/electronics/)

Download
(/id/Free-Energy-From-LEDs/)
3 Steps
Collection
I Made it!
Favorite
Share



First you'll need to get however many LEDs you want. You'll then want to connect the LEDs in a series, leaving a positive and negative wire.

NOTE: This works with any LEDs, but I have found that it works best with Red LEDs

Step 2: Go Towards the Light!

Then you'll want to get a light source (lamp or daylight) and put the circuit right in the strongest part of the light.

Step 3: It's As Simple As That!



Throttle78 (/member/Throttle78/)
Follow 4
(/member/Throttle78/)

advertisement

EVERYTHING A NEW MOM NEEDS
Baby Depot at Burlington
SHOP NOW

Just hook up the wires to a voltmeter and you'll see how much power they are generating. I was able to produce 1 volt just by using 3 LEDs and a bright lamp.

(As if you couldn't tell, this is my first ible, so some advice would be greatly appreciated)

Inspiration for this project and more information on how this works can be found at https://www.instructables.com/id/Better-LED-as-light-sensor

advertisement



Even Bitcoin Cant Do This
These tiny "penny cryptos" could be 10x better than bitcoin
Palm Beach Group



Even Bitcoin Cant Do This
These tiny "penny cryptos" could be 10x better than bitcoin
Palm Beach Group

EVERYTHING A NEW MOM NEEDS
Baby Depot at Burlington
SHOP NOW

Comments

be nice We have a be nice comment policy. Please be positive and constructive.

I Made it! Add Images Post Comment

uwezi (/member/uwezi/) 2015-05-20 Reply

An LED is a very poor solar cell in the same way that a solar cell is a very poor LED. Both are optimized for their primary function: to emit light OR to convert light ot electricity. Both work in the opposite way as well, but apart from studying the underlying physics there is nothing to be gained from using LEDs as solar cells.

Get a cheap solar-powered garden light for EUR 0.50 or an equivalent amount of money from your nearest hardware store and you get an LED and a useful solar cell module for your projects.



(https://cdn.instructables.com/FTO/W3XL/I9UE2ST3/FTOW3XLI9UE2ST3.LARGE.jpg)



Throttle78 (/member/Throttle78/) 2013-11-10 Reply

I only have 4 LEDs, so I have not been able to generate enough current to power something.

assasinsareus (/member/assasinsareus/) ▸ Throttle78 (/member/Throttle78/) 2014-12-17 Reply

I'm afraid even with 4,000 LEDs you would struggle to actually power something. Voltage and Current are interdependent. A large voltage does not mean a large current. Power in terms of Watts is represented in terms of Voltage x Current. You would be much better off with actual solar cells. Using the LED as a light sensor is a good use for this phenomonon.

EVERYTHING A NEW MOM NEEDS
Baby Depot
at Burlington
SHOP NOW

zeldekins (/member/zeldekins/) 2014-01-13 Reply

I think you can use powe LED (1W) to achive more energy!



Throttle78 (/member/Throttle78/) 2013-11-11 Reply

Lean04, you do realize a simple schematic of this would be an LED?

lean04 (/member/lean04/) ▸ Throttle78 (/member/Throttle78/) 2013-12-04 Reply

since you´ve asked for advice i was suggesting a schematic so you have a more complete and friendly instructable, and it wouldn´t be a simple LED, because you´d be showing a lots of simple LEDs in series (in this particular case) for those DIYers that are new to electronics...

Bastl3r (/member/Bastl3r/) 2013-11-19 Reply

The LEDs are acually in reverse (anode on negative and cathode on positive connector). The current is there, but it is somewhere between nano- and microamperes.

The current that is generated could be used to indicate sunlight (or the absence of it) as shown in this schematic (http://www.dieelektronikerseite.de/Pics/Tricks/Dioden-Sperrstrom%20S01.GIF) , the D1 is the diode in the way you use it.

Your method of producing energy is barely enough to keep a microcontroller in low-power-mode, but not using it to make any program run.

With an array of 1000 LEDs in parallel you could produce about 1-10mA which would be nothing fancy, if you think of the costs compared to a little solar power module.

Most of the energy you put into the LEDs (the 100W lamp) is wasted, because of the less energy you get out
P = 1V * (ca. 1-10µA) = 1-10µW.

Even if it would be more current (for example 10µA per LED) the output of power would still be around 30-50µA with 3-5 LEDs

I would suggest a net of lemons to build a lemon battery or some other chemical ways (vinegar and copper) which produce more power than the LEDs in reverse.

---

lean04 (/member/lean04/) 2013-11-10 Reply

Maybe placing some schematics would help and measuring the current too

---

andrea biffi (/member/andrea+biffi/) 2013-11-10 Reply

that's interesting, but maybe a picture of the multimeter with output voltage will explain better the goal..

Kiteman (/member/Kiteman/) 2013-11-10 Reply

So, you're using LEDs as tiny solar cells?

Have you powered anything with them yet?

Kimerserd (/member/Kimerserd/) 2013-11-09 Reply

U go my robot bro!

Throttle78 (/member/Throttle78/) 2013-11-09 Reply

I was unable to detect any amps with only 3 LEDs.

---

mman1506 (/member/mman1506/) 2013-11-09 Reply

now how much current can they supply?

---

mettaurlover (/member/mettaurlover/) ▸ mman1506 (/member/mman1506/) Reply
2013-11-09

Nowhere near enough to be useful, unfortunately, since they aren't designed to do this. A similarly-priced solar panel typically outputs far, far more voltage and current than a bunch of LEDs can, and isn't likely to decide that it wants to emit light instead of generating power if there's any surplus power in the system, such as a backup battery.

⬇ More Comments

EVERYTHING A NEW MOM NEEDS
Baby Depot
at Burlington
SHOP NOW



Newsletter

Let your inbox help you discover our best projects, classes, and contests. Instructables will help you learn how to make anything!

enter email | I'm in!

About Us

Who We Are (/about/)

Advertise (/advertise/)

Contact (/about/contact.jsp)

Jobs (/community/Positions-available-at-Instructables/)

Help (/id/how-to-write-a-great-instructable/)

Find Us

- Facebook (http://www.facebook.com/instructables)
- Youtube (http://www.youtube.com/user/instructablestv)
- Twitter (http://www.twitter.com/instructables)
- Pinterest (http://www.pinterest.com/instructables)
- Google+ (https://plus.google.com/+instructables)

Resources

For Teachers (/teachers/)

Residency Program (/pier9residency)

Gift Premium Account (/account/give?sourcea=footer)

Forums (/community/?categoryGroup=all&category=all)

Answers (/tag/type-question/?sort=RECENT)

Sitemap (/sitemap/)

EVERYTHING
A NEW
MOM NEEDS
Baby Depot
at Burlington
SHOP NOW

Terms of Service (http://usa.autodesk.com/adsk/servlet/item?siteID=123112&id=21959721) |
Privacy Statement (http://usa.autodesk.com/adsk/servlet/item?siteID=123112&id=21292079) |
Legal Notices & Trademarks (http://usa.autodesk.com/legal-notices-trademarks/) | Mobile Site (https://www.instructables.com)
(http://usa.autodesk.com/adsk/servlet/pc/index?id=20781545&siteID=123112)
© 2017 Autodesk, Inc.

Visite 109 675
Pagine 245 310

MAREA SISTEMI

HOME

YOU ALSO PARTICIPATE IN THE SOCIAL NETWORK OF MAREASISTEMI

GOOGLE + FACEBOOK CONTACT FACEBOOK PAGE **YOUTUBE**

facebook
mareasistemi.com

Electricity from the earth's atmosphere. An old forgotten idea

Source: http://scienzaearte.blogspot.it/2011/03/energia-elettrica-dallatmosfera.html

Solar, wind, hydroelectric, geothermal, biogas. These are the main renewable and non-polluting energy sources. But sure not to leave something out?
It is known that the Earth's atmosphere has a potential difference that increases with height. For non-professionals it the atmosphere was a charged battery. This is evident during thunderstorms, when this charge finds its outlet in th frightening and fascinating phenomena that are lightning. Many have imagined and studied methods for storing ligh energy, but this presents numerous problems:

1) it is not known in advance where a lightning will strike or in any case where a thunderstorm will take place; 2) ev lightning strike could be intercepted, for example by attracting it with a kind of lightning rod, it would be extrem difficult to store all its energy, since the discharge is very short; 3) moreover, most of the lightning energy dissipat light, heat and sound. In short, a "power plant" based on the interception of lightning would not be very profitable. **W less known, however, is that the atmosphere has this charge even when there is not even a cloud in the sk**

. The idea of deriving electricity directly from the earth's atmosphere dates back more than a century ago. To m knowledge - I urge readers to post comments if they are aware of other studies - the latest and most promising study field was carried out by the Estonian engineer and inventor **Hermann Plauson** . His studies took place in the 1920 almost a century ago. Is it possible that since then there has been no progress in this field? Why did the idea of extra electricity from the Earth's atmosphere go into oblivion, even though it seemed promising at the time of Plauson's stu



Image taken from the magazine "Science and Invention" (1922), where we describe the invention of Hermann Plau
Let's see before giving a brief description of the method used by Plauson. An electricity collector, consisting for exan
a balloon filled with helium, was raised to an altitude of several hundred meters, connected to the ground by a condu
cable. The balloon itself was made of conductive material and was covered with innumerable little needles, capabl
collecting atmospheric electricity through a phenomenon called field effect emission . High-voltage electricity w
conveyed to the ground by the conductor cable, and was converted into low-voltage electricity to be used by comn
electric users.

In the description of his invention , Plauson reports that he managed to get about 3.4 kW (kilowatt) in a "pilot" exper
using two of these balloons.
Returning to the first question: why such a promising technology was abandoned?
Several hypotheses can be made. The Plauson method provided - even if it was not bound - the use of radioactive ma
(radio and / or polonium), whose ionizing properties were used as a "catalyst" to increase the current inflow. It is ob
that today any alternative energy proposal based on the use of radioactive material would not be frowned upon,
considering the possible environmental impact that could result from accidental contamination. As a note
it is interesting *to mention* that until the eighties a type of lightning conductor covered with a thin layer of americiu
radioactive material), similar in concept to the Plauson collectors, was used in Italy: it is useless to say that these de
are currently become outlaws.
Another possible reason why the idea was abandoned may be related to the fact that the energy needs in the 20s wer
lower than today's ones: a typical "central" "at Plauson", composed of 100 separate balls the one from the other of a
100 meters (so 1 km of side), would have generated some hundreds of kilowatt: a power of all respect for those time
that pales a bit 'when compared to the energy produced by a single wind generator - about 1 Megawatt.
This reason, however, would justify only part of the abandonment of research in this field, since a system that allows
obtain even a few kilowatts using just a couple of balls could be competitive - compared to wind energy - in areas
windy and not served by the electricity network. **Let's** add at this point **an advantage that this system would hav
wind and solar: uninterrupted production 24 hours a day and 365 days a year** .
Apparently, therefore, the only major obstacle would seem to be represented by the use of radioactive material. And
we are meeting the recent technological development. In recent years, in fact, techniques have been developed to ol
nanomaterials that are very efficient from the point of view of field effect emission: in practice they are super-pins
could function as effective collectors of atmospheric electricity without resorting to use of radioactive material.
Some might argue, and rightly so, "But are these particular nanomaterials safe from the health point of view?"
Unfortunately, since these are new technologies, it is still difficult to estimate the impact in this sense, but some studi
under way. If, as is hoped, these materials will be considered harmless to health, then it can not be excluded that t
research on electric energy obtained directly from the earth's atmosphere will find a new vigor and this source not
exploited can go alongside the best known renewable and non-polluting sources.
As a final note it should be added that even without using radioactive material and the nanomaterials mentioned abo

system similar to that of Plauson could provide modest but useful quantities of electricity, finding application especi
the areas of developing countries far from large centers inhabited.

Hermann PLAUSON

Conversion of Atmospheric Electricity

Source: Source: rexresearch.com



In 1920 the German engineer Hermann Plauson published a text "Gew und Verwertung der Atmospharischen Elektrizitat" (Acquisition and atmospheric electricity).

Where he concluded that atmospheric electricity could be captur exploited by men.

In this regard he wrote:

"Humanity will be free from worry about the threat of freezing death, knowing that in a prec time it will be possible to exploit the natural resources to the fullest ... Humanity will no longer suffer from the cold, because Mother Nature will give her abundant gift power."

Plauson designed a series of helium-filled balloons, able to collect atmospheric electricity in t through the use of thermionic rectifiers, Leida bottle condensers and induction coils, his idea supply energy to whole Germany.

Biography (Wikipedia)

Meridian International Research: Atmospheric Electricity Research

***Science & Invention* (Feb. 1922) : "Power from the Air" (I)**

***Science & Invention* (March 1922) : "Power from the Air" (II)**

Plauson's Patents (List)

H. Plauson: USP # 1,540,998 - Conversion of Atmospheric Electricity

H. Plauson: British Patent # 157,262 - Improvements in Electric Motors

H. Plauson: British Patent # 157,263 - Process & Apparatus for Converting Static Atmospheric Electrical Energy into Dynamic Electrical Energ

***Science & Invention* (June 1928) - "Harnessing Nature's Electricity"**

H. Plauson: British Patent # 299735 - Rapidly Moving Electron Process for Producing [PDF]

H. Plauson: *Gewinnung und Verwertung der Atmosphatischen Elecktrizitat* (1922) [PDF]

---

http://en.wikipedia.org/wiki/Hermann_Plauson

Biography

Hermann Plauson was an Estonian engineer and inventor. Plauson investigated the production of energy and power via atmospheric electricity.

Plauson was the director of the Fischer-Tropsch "Otto Traun Research Laboratories" in Hamburg, Germany during the Weimar Republic of the 1920s. Nikola Tesla's idea for connecting machinery to the "wheelwork of nature". Plauson's US Patent # 1,540,998 methods of converting alternating radian electricity into rectified continuous current pulses. He developed the Plauson's converter, an electrostatic generator. In 1920, Plauson published a bo *Production and Utilization of the Atmospheric Electricity* " (*Gr., Gewinnung und Verwertung der Atmospharischen Elektrizitat*). A copy of this boo British Library.

It is believed to be Gertrud Plauson (the exact relationship is unknown;

"Power from the Air". *Science and Invention* , Feb. 1922, no. 10. Vol IX, Whole No. 106. New York. (nuenergy.org)
"Power from the Air". *Science and Invention* , March 1922.

***Science and Invention,* Vol. IX (106) # 10 (February 1922)**

Power from the Air (I)

by

Hugo Gernsback

In the war there was developed in Germany in the new art --- or science --- that bids fair to revolutionize our present means of obtaining power.

This art, which is as new now as wireless, is 25 years ago, will be attainments during the next 25 years that may appear fantastic today. Hermann Plauso of the new science, has devoted years of labor to his researches and he has now been using small power plants, generating electricity direct from the a night, without interruption at practically no cost, once the plant is constructed.
We have occasion, to describe the system, roughly, from cabled dispatches, but complete information is available now. The amount of electrical power in our atmosphere is astounding. Herr Plauson found in his experiments a single balloon sent to a height of 300 yards gave a constant current at 400 amperes, or in 24 hours over 17-1 / 4 kilowatts! By using two balloons in connection with a special condenser battery, the power obtained was 81-1 / 2 24 hours. The actual current delivered was 6.8 amperes at 500 volts.

The best balloons used by the inventor are made of thin aluminum leaf. No fabric was used. A simple internal system of ribs, stays and wires, gives rigidity as well as a certain amount of elasticity. The balloon, when made airtight, is filled with hydrogen or better, with helium. It will then stay aloft for time. The outer surface is dotted with extremely sharp pins, made sharp electrolytically. Ordinary pins did not prove good current collectors, as they lack sharpness. The pins themselves were made from amalgamated zinc, containing a radium preparation, in order to ionize the air. It was also found that by outer surface of the balloon with zinc-amalgam more current could be collected. Even better results were obtained with polonium amalgam. Plauson sta function of these amalgams is purely photoelectric.

One hundred of such captive balloons, separated one hundred yards from each other, will give a steady yield of 200 horsepower. This is the minimum, the winter this figure increases up to 400 horsepower, due to the higher electrification of the atmosphere.

We need not go into the technic of how the current is finally made useable for industrial purposes, suffice it to say that the problem has been entirely solv Plauson. By using batteries of condensers, high tension transformers, etc., the current can be transformed to any form desires. Such as for lighting lam motors, charging storage batteries, etc.

Plauson also invented a sort of electrostatic rotary transformer which gives alternating current without the use of condensers and transformers. Indeed, i very great, as it actually 'sucks' the current down rapidly from the collector balloons. There is no doubt that this invention will soon come into universal the world. We will see the land dotted with captive balloons, particularly in the country and wherever water power does not abound. Indeed, the time is when nearly all of our power will be derived from the atmosphere. So far it seems to be the cheapest form of power known, it being much cheaper even power --- the cheapest form of power known today. Not only that, but as the inventor points out, no devastating thunder storms occur near such aerial po because the balloons act not only as lightning arresters, but they quickly discharge the biggest thunder cloud, safely and noiselessly through their grou gaps.

***Science & Invention* (March 1922), page 1006, 1007**

Power from the Air (II)

by

Hugo Gernsback

[For many years electrical engineers have endeavored to devise some means whereby it would become possible to utilize the free electrical energy eve the atmosphere, but they were not successful, as every now and then an extra heavy surge of static current would rush down the elevated conductor an the lives of the experimenters, or else destroy the apparatus connected with it. A German engineer has, however, devised the somewhat elaborate s shown in brief, and he has succeeded, at least so his report states, in safely extracting several kilowatts of electrical power from the atmosphere w surfaced balloons, elevated to a height of only 1000 feet.]



©1922 BY SCIENCE AND INVENTION

We have previously treated of the extraction of electrical energy from the atmosphere. The difference of electric potential in different parts of the atmo
the difference between the upper air and earth make it a tempting proposition to obtain power from atmospheric electricity. The power would take the f
potential difference with a discharge almost of a static nature. It has long appeared rather doubtful to conservative engineers, if such a source of power s
be available. Yet when we see the lightning flash, it certainly suggests very high power, even though the total of its energy may be small, on account
duration of the discharge It is not to the thunder storm that we look for getting power from the atmosphere, as the subject is now being seriously inve
German scientist, Hermann Plauson, has published a very elaborate work on this subject, and has investigated the use of kites, balloons and tow
utilization of the high potentials existing in the air at different altitudes, and has studied out the construction of motors to be operated by the pecu
discharge which will be obtained, if the projects are successfully carried out.

We will first speak of the methods used for collecting electricity from the upper air. The author cites several German patents. One of them shows the u
balloon. The balloon is shown floating in the air, kite fashion, and from it hangs a great net or aerial for the collection of electricity. The conductor fro
leads to the ground station; quite an elaborate description is given of the net-work which the patentee proposes to have covered with needle points. A wi
in or pays out cable for the balloon, and the patentee claims that by sending the apparatus to a height of about one mile he will have 225,000 volts to dra
then speaks o a battery of 20,000 cells in series, which will use up to 40,000 to 50,000 volts in the charging. This certainly provides for a reasonable
potential.

But our author discards this idea and first suggests something more permanent. He proposes the erection of towers to be in the neighborhood of 1,000 f
about the height of the Eiffel Tower. At the summit he has his collecting aerial. The appliance consists of a number of copper tubes; within each one he
burn gas lamps, whose products of combustion will reach the aerial, a collecting net-work covering the tops of the tubes. One of his apprehensions is
should wet his connections trouble might ensue, so he proposes a protection at the top in the shape of a great bell-like shield, resembling in his terms
pagoda". He also compares the form of the protection to that of a great petticoat insulator. Another of his difficulties is that he must have his tower ins
the earth. He, therefore describes a complicated foundation for his structure. He proposes first to pour in at the bottom of the excavation a foundatio
concrete. On this he places a layer of asphalt, and then a layer of cast glass, three to ten feet thick, and then comes a reinforced concrete foundation, t
metallic foot of the tower is to be anchored. This foundation must rise at least seven feet above the ground level, and is to be boarded in on all sides
from moisture. The author's idea s to erect a number of these towers connected by a horizontal cable, to which the aerials for collection of potentials are

The author strongly advocates balloons as collectors of the electric power of the air. These he depicts covered with spots. These spots indicate areas to b
coated and prepared to collect potential from the atmosphere.

In the first place he describes the balloon as made of thin metallic leaf supported by internal ribs. Steel wires silver-plated, copper-plated, or aluminum-
from the balloon to the pendant or junction ring. To this ring the tether cable is attached and runs to an insulated windlass on the surface of the earth. Th
to rise to an altitude varying from 300 feet to three miles.

The coating of the spots is to be of the thinnest amalgam, of mercury and gold, or zinc, or even polonium, perhaps only 1/2500 inch thick. All over the u the balloon are numberless metal points. To prepare the needle-like wires, they are collected into bundles and are treated electrolytically in a bath, dissolved in part. This gives a sharp point and roughened surface, all adapted for collecting the electric energy. The points may be of copper, steel, or metallic alloy. After this corrosion. As it may be termed, the wires are plated with gold or other of the so-called noble metals. It is advised that poloniu salts be added to the plating bath.

Dr Plauson devotes many pages of his book to describing his motor. This is a rotary motor including a stator and rotor and its peculiarity is that it contai develops no electromagnetic field properly speaking, but works by static excitation. One typical arrangement is shown in our illustration. The stator plat plates are concentric with each other, representing segments of cylinders. The alternation of negative and positive charged plates produces the rota connections there is included a safety spark gap to take care of dangerous potentials. Inductances and capacities are also used and indicated. It was fo plates heated, owing to the Foucalt currents, and to overcome this, several methods of subdividing the stator and rotor plates, are described by the author.

The whole subject is quite captivating, and it really seems as if the utilization of the electricity of the air may be almost in sight. It would seem possible experiments in this direction by means of the Eiffel Tower, but of course, the trouble here is that the tower is grounded, and perfect insulation of th surface is absolutely essential.

And now our author gives us some practical details. He says that on the Finland plains he carried out experiments with a balloon made of aluminu collecting needles of amalgamated zinc with a radium preparation as an ionizer. The surface of the balloon was sprinkled over with zinc amalgam. It wa a height of 300 meters, early 1,000 feet, and was held by a copper-plated steel wire. A constant current of 1.8 amperes at an average of 400 volts potentia was obtained. This gave nearly three-quarters of a kilowatt, or close to one horsepower. The collector of the balloon insulated from the earth showed 42,000 volts. By sending up a second balloon with an antenna to the same height at a distance of 100 meters from the first balloon, a current of over 3 a obtained. Then by putting into the circuit a large condenser, whose capacity was equal to the surface capacity of both balloons, and of the antenna conn current rose to 6.8 amperes with about 500 volts mean tension. By the use of these two balloons, he eventually ran up the power to 3.4 kilowatts.

Science & Invention (June 1928)



Remarkable European Experiments with Atmospheric Electrical Discharges with Potentials as High as 3,000,000 Volts

By HENRY TOWNSEND

elevation of 350 ft., and these students of natural electrical phenomena have found a very desirable location in the Alps, where they can suspend between one mountain and an adjacent one, a strong iron cable having a length of about 2,000 ft. This cable is about 250 feet above the intervening valley, and from it these daring engineers have suspended a coarsely woven wire net, which serves as an electrical capacity to gather the electricity from the atmosphere. As shown in the pictures, the wire net is supplied with numerous sharp points to aid in collecting the current from the air.

As the accompanying photographs of the actual apparatus and wire cable used last year clearly show, an adjustable spark gap of considerable length is provided. By adjusting this spark gap to various lengths, it is possible to judge the voltage of the discharge which leaps the gap at any moment. Mr. F. W. Peek, Jr., the well-known American worker in the realm of high voltage measurements, together with other engineers, have provided tabulated data and curves for various lengths of both needle and sphere type spark gaps. As one of the accompanying diagrams shows, it is a simple matter to calculate the voltage when a certain length of gap is used. The engineer first checks the length of the gap on the chart; he then follows a line horizontally from the gap length, to where it intersects with the angular line on the chart; and from the point of intersection he looks in a visual line downward to a place where the voltage is given. For needle spark gap measurements, the characteristic curve on the chart is practically a straight line, while for sphere gaps the characteristic curve on the voltage versus gap length, is a curved line. Those interested in high voltage measurements by means of the spark gap method can find the voltage-gap tables and charts in the *Standardization Rules* of the American Institute of Electrical Engineers. According to Mr. Peek's researches, the voltage per foot of atmospheric electrical discharges is about 100,000, while in laboratory measurements with A.C., transformer high potential discharges, the average voltage per foot of spark was found to be about 150,000 volts. The voltage of a lightning flash may

(*Continued on page* 156)



↑ Actual photo a
shows 13 ft., he
spark obtained i
the collecting net
the Alps by the
man scientists.
voltage is about 2,
000. The spark occu
once per second fo
minutes.



Photo, left, shows
adjustable spark
used in the Alps.
tice the heavy e
trode on the end of
adjustable arm to w
the spark jumps

←

Actual photograph of the experimental "kite" used by the German experimenters in the Alps Mountains, for the purpose of accumulating high potential electrical discharges from the atmosphere. Note the size of the insulators.



Below we see 3,000
volt artificial light
stroke produced in
E. Laboratory at P
field, Mass. Note n
↓



if-
you pledge
yourself to secrecy we will teach you the secrets of
Real Professional
Magic

Dr. Harlan Tarbell, internationally known magician and teacher of some of the world's greatest magicians.

Learn to be a Magician

For the first time in the history of Magic the age-old, sacredly guarded secrets of the Mystic Art are being revealed. Now at last you can learn to be a Real Professional Magician. Yes, and you can learn this wonderful art *easily and quickly* AT HOME. You are taught the mysterious *Principles* by which the Professional Magician works. You are taught everything from wonderful impromptu effects to massive stage illusions. But before you can study, you must sign the Magician's Solemn Pledge of Secrecy. This means that you are getting the *guarded secrets* of the Magic Profession. Think of that!

Earn $250 to $1000 a Month
There's a big demand for Magic entertainment. Magicians get big money. Dr. Tarbell gets as high as $250 for a half hour's work. Unlimited opportunities for you!

Low Prices Easy Terms

Write Today Send today for free Magic book, low prices and easy terms. Don't delay. Mail the coupon NOW!

Tarbell System, Inc., Studio A-142
1920 Sunnyside Avenue, Chicago, Ill.

Gentlemen: Without any obligation send me your free literature and information all about your wonderful "Tarbell Course in Magic." Also tell me about your Low Price Offer and Easy Payment Plan.

Name..

Address...

....*Age*.........

HARNESSING NATURE'S ELECTRICITY

By HENRY TOWNSEND

(*Continued from page* 111)



Remarkable cathode ray oscillograph used by Mr. F. W. Peck, Jr., in causing lightning to write its autograph with a pencil of electrons on a photographic film.

easily be 100,000,000 volts, as Mr. Peek has pointed out in one of his scientific papers.

WHY THE EXPERIMENTS ARE BEING MADE

ONE of the main reasons why these dangerous experiments are being carried on by the three young German scientists, whose names we have already learned, is because science believes that with a sufficiently high voltage, it will be possible for man to disintegrate the atom, and in this way make available a tremendous source of power as yet untapped. These experts have calculated that they will be able to obtain electrical energy in sufficient quantity from one of these powerful atmospheric discharges, to equal the Alpha rays obtained from 220 pounds of radium. As we have mentioned before, these experiments are of course fraught with great danger, and for that reason the experimenters seek refuge in a special lightning-proof hut, which is located about 600 ft., from the spark gap. When electrical storms are in the vicinity, it is especially important that the scientists keep within their protected fortress, for otherwise they would very probably be killed by a stray electrical discharge.

One of the peculiar things about this whole line of experiment is that the average layman does not realize perhaps, that there is a high electrical stress in the atmosphere on clear days, as well as when thunder storms are overhead. This fact has been known for a hundred years and more, and many years ago measurements of the various electrical potentials at increasing altitudes, were observed and measured by scientific investigators. There are a number of different ways in which these high electrical potentials found in the atmosphere can be measured; one of these methods involves the use of a calibrated spark gap. In this case the gap is set to a predetermined length, and when a discharge jumps this gap, the engineers know of course from previous experience and measurements, just what voltage is present. Another method of measuring extra high potentials, such as here
countered, requires the use of a static v
meter, which involves the use of a statio
and of a movable or rotary set of m
plates, forming a condenser, to which
indicating needle is attached. For volta
above 2,000, static voltmeters have been
in a great many American central stati
and they have many desirable and us
characteristics. Of course as the vol
to be measured increases, the space betw
the quadrant shaped stationary and mov
plates is increased and vice versa.
electrostatic field from voltages below 2
is not sufficient to warrant the use o
static voltmeter. Another method of m
uring high potentials involves the use
the so-called vacuum tube voltmeter.

The general characteristics of the
mospheric electrical discharges, inclu
lightning, have been measured and reco
by one of the newest scientific instrum
known as the cathode ray oscillograph.
means of this quite remarkable, high v
age scientific apparatus. Mr. Peck, one
the well-known General Electric Comp
staff of research engineers, has made s
very interesting and remarkable discove
concerning the nature of natural electr
discharges, particularly of lightning
charges. Many people will probably wo
why Mr. Peek and some of his collea
in the engineering profession, including
three daring German students, Mes
Brasch, Lange and Urban, play with
dangerous electrical discharges, and
they are at all interested in them. We
plained previously why the German sav
are intent on finding out all they can al
these tremendous voltages obtained f
the atmosphere, while Mr. Peck, we
say, also has a very practical reason
carrying on experiments with these de
dealing bolts of Thor. Mr. Peek has
for many years intent on finding out w
causes the huge insulators on long dista
high potential transmission lines to br
down when electrical storms break loose
these regions.

Plauson's Electrical Patents

USP # 1,540,998
Conversion of Atmospheric Electric Energy
6-09-1925

GB157262
Improvements in Electric Motors
1922-07-10

GB157263
Process and Apparatus for Converting Static Atmospheric Electrical Energy into Dynamic Electrical Energy of any Suitable High Periodicity
7-10-1922

British Patent # 299,735
Apparatus for Producing Rapidly Moving Electrons
7-15-1930

FI21227
Elektrisk uppvärmningsanordning
4-25-1946

Varmelegeme med elektriske varmemodstande
DK67691C
9-27-1948

FR877362
Dispositif de chauffage électrique
12-04-1942

DE734794
Elektrisches Heizsystem
4-24-1943

CH222509
Elektrischer Heizkörper zur Erwärmung von Flüssigkeiten
7-31-1942

DE738107
Elektrolyt fuer unmittelbare elektrische Warmwasser-Radiatorenheizung mit Elektroden
8-03-1943

DE433476
Verfahren zur Herstellung von Elektroden und Schleifkontakten fuer Dynamomaschinen
8-31-1926

CH94021
Elektrode und Verfahren zu deren Herstellung
4-01-1922

CA226423
Electrode for Electrolytic Apparatuses
11-21-1922

---

http://www.meridian-int-res.com/Energy/Atmospheric.htm

Atmospheric Electricity Research
[Excerpts]

In the nineteenth and early twentieth centuries, a large number of researchers investigated ways to extract electrical power from the Earth's ambient electr

The leader in this field was Dr Hermann Plauson who in the 1920s succeeded in generating significant quantities of electrical power comparable with m
photovoltaic systems of a similar scale...

The leader in this field before the Second World War appears to have been Dr Hermann Plauson. Dr Plauson was an Estonian citizen who lived in Ha
Switzerland. He carried out experiments in Finland with aerostats manufactured from magnesium-aluminium alloy, covered with electrolytically deposit
The needles were further doped with a radium compound to increase local ionisation of the air. (This was the era in which the hands of watches were h
with radium to make them luminous in the dark). Zinc amalgam patches were also painted onto the aerostats. Plauson obtained a power output of betwe
and 3.4kW from one and two aerostats 300m above ground level. Dr Plauson filed patents in the USA, Great Britain and Germany in the 1920s
"Gewinnung und Verwertung der Atmosphärischen Elektrizität" is the most detailed known account of the technology.

Other atmospheric electricity researchers contemporary to Dr Plauson included Walter Pennock and MW Dewey in the USA, Andor Palencsar in Hung
Heinrich Rudolph in Germany. Hippolyte Charles Vion in Paris predated them all, putting forward proposals in the 1850s and 1860s.

Heinrich Rudolph made an interesting contribution to the design of the aerostat collectors. In 1898 he designed an elliptical aerostat made up of faceted
minimise the effect of wind. The design bears a strong resemblance to Northrop's 2003 UCARS unamnned helicopter UAV project. The design uses
Effect to help keep the aerostat on station and minimise wind effects.

In recent times, the only person who seems to have been active in this field is Dr Oleg Jefimenko. Dr Jefimenko carried out experiments on driving e motors from the Earth's electric field in the 1970s and has recently called for research into the neglected field of electrostatic motors to be renewed.

MIR's Research Programme

Since 1997 we have been carrying out theoretical research into conversion of atmospheric electricity into useable electrical power.

From a low level (5m high) simple zinc antenna we are able to obtain sufficient charge to light a number of white power LEDs. Further experimental in with metallic aerostat collectors and cavity resonant slow wave antennae concepts are ongoing...

Advantages of Atmospheric Electricity

Simple and robust technology
Low Cost technology - much cheaper than photovoltaics or wind turbines
Available day and night in all weather conditions - in fact, more power is produced at night than during the day
Available at any point on the Earth's surface

1. *Gewinnung und Verwertung der Atmosphärischen Elektrizität*, Dr Hermann Plauson, Hamburg, (1920)
2. Conversion of Atmospheric Electric Energy, USP 1,540,998, Dr Hermann Plauson, (1925)
3. Assembly for the Induction of Lightning into a Superconducting Magnetic Energy Storage System, USP 5,367,245 Goven Mims, (1994)
4. Electrostatic Motors are Powered by Electric Field of the Earth; CL Stong, *Scientific American*, (October 1974)
5. Operation of Electric Motors from the Atmospheric Electric Field; Dr Oleg Jefimenko, *American Journal of Physics*, vol. 39, July 1971.
6. *Electrostatic Motors: Their Principles, Types and Theory of Operation*; Dr Oleg Jefimenko, Electret Scientific, (1972).
7. Parametric Electric Machine, USP 4,622,510, Ferdinand Cap, (1986).

US Patent # 1,540,998

Conversion of Atmospheric Electric Energy

(9 June 1925)

Hermann PLAUSON

Be it known that I, Hermann Plauson, Estonian subject, residing in Hamburg, Germany, have invented certain new and useful improvements in the Conversio Electric Energy, of which the following is a specification.

Methods of obtaining atmospheric electricity by means of metallic nettings set with spikes which are held by means of ordinary or anchored kite balloons m filled with hydrogen, are in theory already known. Atmospheric electricity obtained in this way has been suggested to be used in the form of direct current fo accumulators. This knowledge however is at present only theoretical as the conversion in practice has hitherto been a failure. No means are known of protect from destruction by lightning. The balloons used for collecting the charge must also me be made of very large size in order to be able to support the weig netting and the heavy cable connections.

Instead of using heavy metallic netting as collectors attached to single air ballons of non-conducting materials which are liable to be torn and are permeab proposed to use metallic balloon collectors which have the following important advantages ---

(a) The metallic cases are impenetrable to helium and hydrogen; they also represent large metallic weather-proof collecting surfaces.

(b) Radio active means the like may be easily applied internally or externally; whereby the ionization is considerable increased and therewith also the quanti electricity capable of being collected.

(c) Such balloon collectors of light metal do not require to be of large size as they have to carry only their own moderate weight, and that of the conducting cab

(d) The entire system therefore offers little surface for the action of storm and wind and is resistant and stable.

(e) Each balloon can be easily raised and lowered by means of a winch so that all repairs, recharging and the like can be carried out without danger during the c

It is further proposed to use a collecting aerial network of several separate collectors spread out in the air above the earth, which collectors are interconne conductors.

According to this invention charges of atmospheric electricity are not directly converted into mechanical energy, and this forms the main difference from pre but the static electricity which runs to earth through aerial conductors in the form of direct current of very high voltage and low current strength is conve dynamic energy in the form of high frequency vibrations. Many advantages are thereby obtained and all disadvantages avoided.

The very high voltage of static electricity of a low current strength can be converted by this invention to voltages more suitable for technical purposes and of gr the use of closed oscillatory circuits it is possible to obtain electromagnetic waves of various amplitude and thereby to increase the degree of resonance of s resonance allows various values of inductance to be chosen whereby again the governing of the starting and stopping of machines driven thereby by simply tun between coils of the machine and the transformer circuit forming the resonance can easily be obtained. Further, such currents have the property of being dire various uses, even without employing them for driving motors, of which there may be particularly mentioned, lighting, production of heat and use in electro-ch

Further, with such currents a series of apparatus may be fed without direct current supply through conductors and also the electro-magnetic high frequency converted by means of special motors adapted for electro-magnetic oscillations into mechanical energy, or finally converted by special machines into alternati frequency or even into direct current of high potential.

The invention is more particularly described with reference to the accompanying diagrams in which: ---

Figure 1 is and explanatory figure.

Figure 2 is a diagrammatic view of the simplest form.

Figure 3 shows a method of converting atmospheric electrical energy for use with motors.

Figure 4 is a diagram showing the use of protective means.

Figure 5 is a diagram of an arrangement for converting large current strengths.

Figure 6 is a diagram of an arrangement including controlling means.

Figure 7 shows means whereby the spark gap length can be adjusted.

Figure 8 shows a unipolar connection for the motor.

Figure 9 shows a weak coupled system suitable for use with small power motors.

Figures 10, 11, and 12 show modified arrangements.

Figure 13 shows a form of inductive coupling for the motor circuit.

Figure 14 is a modified form of Figure 13 with inductive coupling.

Figure 15 is an arrangement with non-inductive motor.

Figure 16 is an arrangement with coupling by condenser.

Figure 17, 18, and 19 are diagrams of further modifications.

Figure 20 shows a simple form in which the serial network is combined with special collectors.

Figure 21 shows diagrammatically an arrangement suitable for collecting large quantities of energy.

Figure 22 is a modified arrangement having two rings of collectors.

Figure 23 shows the connection for three rings of collectors.

Figure 24 shows a collecting balloon and diagram of its connection of condenser batteries.

Figure 25 and 26 show modified collector balloon arrangements.

Figure 27 shows a second method of connecting conductor for the balloon aerials.

Figure 28 shows an auto-transformer method of connection.

Figure 29 shows the simplest form of construction with incandescent cathode.

Figure 30 shows a form with cigar shaped balloon.

Figure 31 is a modified arrangement.

Figure 32 shows a form with cathode and electrode enclosed in a vacuum chamber.

Figure 33 is a modified form of Figure 32.

Figure 34 shows an arc light collector.

Figure 35 shows such an arrangement for alternating current.

Figure 36 shows an incandescent collector with Nernst lamp.

Figure 37 shows a form with a gas flame.

Fig. 1.



Fig. 2.



Figure 1 illustrates a simple diagram for converting static electricity into dynamic power of a high number of oscillations. For the sake of clearness in the draw machine is assumed to be employed and not an aerial antenna. 13 and 14 are combs for collecting the static electricity of the influence machine. 7 and 8 are electrodes. 5 and 6 are condensers, 9 an inductive primary coil, 10 secondary coil, 11 and 12 ends of conductors of the secondary coil 10. When the disc of th machine is rotated by mechanical means, the combs collect the electric charges one the positive and the other the negative, and charge the condensers 5 and 6 potential is formed across the spark gap 7-8, that the spark gap is jumped. As the spark gap 7-8 forms a closed circuit with condensers 5 and 6, and inductive well known, waves of high frequency electromagnetic oscillations will pass in this circuit.

The high frequency of the oscillations produced in the primary circuit induces waves of the same periodicity in the secondary circuit. Thus in the primary circui oscillations are formed by the passage of the spark over the spark gap and these waves are maintained by fresh charges of static electricity.

By suitably selecting the ratio between the number of the coils in the primary and secondary circuits with regard to a correct application of the co-effici (especially, inductance and resistance) the high voltage of the primary circuit may be suitably converted into low voltage and high current strength.

When the oscillatory discharges in the primary circuit becomes weaker or entirely cease, the condensers are charged again by the static electricity until the ac again breaks down the spark gap. All this is repeated as long as electricity is produced by the static machine employing mechanical energy.

An elementary form of the invention is shown in Figure 2 in which two spark gaps in parallel are used one of which may be termed the working gap 7 in Fi second serves as a safety device for excess voltage and consists of a larger number of spark gaps than the working section, which gaps are arranged in series a very small capacities as is illustrated in a, b, c, Figure 2 which allow of uniform sparking in the safety section.

In Figure 2 A is the aerial antenna for collecting charges of atmospheric electricity. 13 is the earth connection of the second part of the spark gap, 5 and 6 ar primary coil. Now when through the aerial A the positive atmospheric electricity seeks to combine with the negative charge to earth, this is prevented by (the the spark gaps. The resistance of the spark gap 7 is, as shown in the drawings, lower than that of the other safety section which consists of three spark gaps co and consequently a three times greater air resistance is offered by the latter.

So long, therefore, as the resistance of the spark gap 7 is not overloaded, so that the other spark gaps have an equal resistance with it the discharges take plac gap 7. Should however the voltage be increased by and influences so that it might be dangerous for charging the condensers 5 and 6 or for the coil insul consequence of break down, by a correct regulation of this spark gap the second spark gap can discharge free from inductive effects direct to earth withou machine.

Without this second spark gap, arranged in parallel having a higher resistance than the working spark gap it is impossible to collect and render available l electrical energy.

The actions of this closed oscillation circuit consisting of spark gap 7, two condensers 5 and 6, primary coil 9, and also secondary coil 10 is exactly the described in Figure 1 with the arrangement of the static induction machine with the only difference that here the second spark gap is provided. The elec frequency alternating current obtained can be tapped off from the conductors 11 and 12 for lighting and heating purposes. Special kinds of motors adapted these peculiar electrical charges may be connected at 14 and 15 which can work with static electricity charges or with high frequency oscillations.

In addition to the use of spark gaps in parallel a second measure of security is also necessary for taking off the current. This precaution consists according to the introduction of and method of connecting certain protective electromagnets or choking coils in the aerial circuit as shown by S in Figure 3.

A single electromagnet only having a core of the thinnest possible separate laminations is connected with the aerial.

In the case of high voltages in the aerial network or at places where there are frequent thunder storms, several such magnets may however be connected in serie

In the case of large units or plants several electromagnets can be employed in parallel or in series parallel.

The windings of these electromagnets may be simply connected in series with the aerials. In this case the winding preferably consists of several thin parallel w up together, the necessary section.

The winding may be made of primary and secondary windings in the form of a transformer. The primary windings will be then connected in series with the ae the secondary winding more or less short-circuited over a regulating resistance or an induction coil. In the latter case it is possible to regulate to a certain exter choking coils. In the further description of the connecting and constructional diagrams the aerial electromagnet choke coil is indicated by a simple ring S.



Figure 3 shows the simplest way of converting atmospheric electricity into electromagnetic wave energy by the use of special motors adapted for high oscil static charges of electrical energy. Recent improvements in motors for working with static charges and motors working by resonance, that is to say, having electromagnetic cooperating circuits render this possible but such do not form part of the present invention.

A motor adapted to operate with static charges will for the sake of simplicity be diagrammatically indicated by the two semicircles 1 and 2 and the rotor of th M (Figure 3). A is a vertical aerial or aerial network. S the safety choke or electromagnet with coil O as may be seen is connected with the aerial A. Adjacent S the aerial conductor is divided into three circuits, the circuit 8 giving the safety spark gap, the circuit 7 with the working spark gap, and then a circuit in terminal 1, the rotor and stator terminal 2 at which a connection is made to the earth wire. The two spark gaps are also connected metallically with the earth wi working these diagrams is as follows:

The positive atmospheric electric charge collected tends to combine with the negative electricity (or earth electricity) connected with the earth wire. It travels a through the electromagnet S without begin checked as it flows in the same direction as the direct current. Further, its progress is arrested by two sparks gaps and the stator condenser surfaces. The stator condenser surfaces are charged until the charge is greater than the resistance of the spark gap 7, whereupon a spar spark gap 7 and an oscillatory charge is obtained as by means of the motor M, stator surfaces 1 and 2, and spark gap 7, a closed oscillation circuit is obtained electromagnetic oscillations. The motor here forms the capacity and the necessary inductance and resistance, which, as is well known, are necessary for electricity into electromagnetic wave energy.

The discharge formed are converted into mechanical energy in special motors and cannot reach the aerial network by reason of the electromagnet or choke. If, spark springs over the spark gap 7 a greater quantity of atmospheric electricity tends to flow to earth, a counter voltage is induced in the electromagnet, wh more rapidly and strongly the flow of current direct to the earth is. By the formation of this opposing voltage a sufficiently high resistance is offered to the flo electricity direct to earth to prevent a short circuit with the earth.

The circuit containing spark gap 8 having a different wave length which is not in resonance with the natural frequency of the motor, does not endanger the mo security against excess voltage, which, as practical experiments have shown, may still arise in certain cases, but can be conducted direct to earth through this sp

In the diagram illustrated in Figure 4 the spark gap 7 is shunted across condensers 5 and 6 from the motor M. This construction affords mainly a better insula against excess voltage and a uniform excitation through the spark gap 7.

In Figure 5 a diagram is illustrated for transforming large current strengths which may be employed direct without motors, for example, for lighting or heati main difference is that here the spark gap consists of as star shaped disk 7 which can rotate on its own axis and is rotated by a motor opposite similarly fit When separate points of stars face one another, discharges take place, thus forming an oscillation circuit over condensers 5 and 6, and inductance 9 for oscillat is evident that a motor may also be directly connected to the ends of the spiral 9.

The construction of the diagram shown in Figure 6 permits of the oscillation circuit of the motor being connected with an induction coil/ Here a regulating indu introduced for counter-acting excess voltages in the motor. By cutting the separate coils 9 (coupled inductively to the aerial) in or out the inductive action on more or less increased or variable aerial action may be exerted on the oscillation circuit.



In Figure 7 the oscillation circuit is closed through the earth (E and E1). The spark gap 7 may be prolonged or shortened by more or fewer spark gaps b connected by means of a contact arm 7b.

Diagram 8 shows a unipolar connection of the motor with the aerial network. Here two oscillation circuits are closed through the same motor. The first oscillat from aerial A through electromagnet S, point *x*, inductance 9a to the earth condenser 6 and further, over spark gap 7 to the aerial condenser 5 and back oscillation circuit starts from the aerial condenser 5 at the point x^1 over the inductance 9 to the earth condenser 6 at the point x^3 and through the condenser 6 c 7 back to x^1. The motor itself is inserted between the two points of the spark gap 7. From this arrangement slightly damped oscillation wave currents are produc

In the diagram illustrated in Figure 9 a loosely coupled system of connections is illustrated which is assumed to be for small motors for measuring purpose aerial conductor, S the electromagnet in the aerial conductor, 9 the inductance, 7 the spark gap, 5 and 6 condensers, E the earth, M the motor, and 1 and 2 stat the motor. The motor is directly metallically connected with the oscillation circuit.

In Figure 10 a purely inductive coupling is employed for the motor circuit. The motor is connected with the secondary wire 10 as may be seen in Figure modified diagram connection. The same applies to the diagram of Figure 12.

The diagrams hitherto described preferably allow of motors of small and medium strength to be operated. For large aggregates, however, they are too in construction of two or more oscillation circuits for large amounts of energy is difficult; the governing is still more difficult and the danger in switching on or of

A means of overcoming such difficulties is shown in Figure 13. The oscillation circuit here runs starting from the point x over condenser 5, variable inductan and the two segments (3a and 4a) forming arms of a Wheatstone bridge, back to x, If the motor is connected by brushes 3 and 4 transversely to the two arm shown in the drawings, electromagnetic oscillations of equal sign are induced in the stator surfaces 1 and 2 and the motor does not revolve. If however the br moved in common with the conducting wires 1 and 2 which connect the brushes with the stator poles a certain alteration or displacement of the polarity is motor commences to revolve.

The maximum action will result if one brush 3 comes on the central sparking contact 7 and the other brush 4 on the part *x*. They are however, usually in practi the central contact 7 but only held in the path of the bridge segments 4a and 3a in order not to connect the spark gaps with the motor oscillation circuit.



As however, the entire oscillation energy can thereby not act on the motor it is better to carry out the same system according to the diagram 14. The diagram 1 foregoing only by the motor not being directly metallically connected with the segments of the commutator, but only a primary coil 9 which induces in a s current which feeds the motor M and takes the place of the rotor. By this arrangement a good transforming action is obtained, a loose coupling and also an without a spark gap.

In Figure 15 the motor is not purely inductive as in 14, but directly metallically branched off from the primary coil (at *x* and x^1) after the principle of the auto-tr

In Figure 16 instead of an inductance a condenser 6 is in similar manner, and for the same object inserted between the segments 3a and 4a. This has the a segments 3a and 4a need not be made of solid metal but may consist of spiral coils whereby a more exact regulation is possible and further motors of high in employed.

The arrangements of Figures 17, 18 and 19 may be employed for use with resonance and particularly with induction condenser motors; between the larg condenser surfaces, small reversing pole condenser surfaces, mall reversing pole condensers are connected, which, as may be seen from Figures 17, 18 and 19 earth. Such reversing poles have the advantage that with large quantities of electrical energy the spark formation between the separate oscillation circuits ceases

Figure 19 shows a further method which prevents electromagnetic oscillations of high number of alternations formed in the oscillation circuit striking b conductor. It is based on the well known principle that a mercury lamp, one electrode of which is formed of mercury, the other of solid metal such as steel charge to pass in only one direction from the mercury to the steel and not vice versa. The mercury electrode of the vacuum tube N is therefore connect conductor and the steel electrode with the oscillation circuit. From this it results that charges can pass only from the aerial through the vacuum tube to the osci not vice versa. Oscillations which are formed on being transformed in the oscillation circuit cannot pass to the aerial conductor.

In practice these vacuum tubes must be connected behind an electromagnet as the latter alone affords no protection against the danger of lightning.

As regards the use of spark gaps, all arrangements as used for wireless telegraphy may be used. Of course the spark gaps in large machines must have a surface. In very large stations they are cooled in liquid carbonic acid or better still in liquid nitrogen or hydrogen; in most cases the cooling may also take p liquefied low homologues of the metal series or by means of hydrocarbons the freezing point of which lies at between –90° C and –40° C. The spark gap ca insulated and be of sufficient strength to be able to resist any pressure which may arise. Any undesirable excess super-pressure which may be formed must be off. I have employed wit very good results mercury electrodes which were frozen in liquid carbonic acid, the cooling being maintained during the operation through the walls.

Figure 20 is one of the simplest forms of construction of an aerial network in combination with collectors, transformers and the like illustrated diagrammatic earth wire, 8 the safety spark gap, 7 the working spark gap, 1 and 2 the stator surfaces of the motor, 5 a condenser battery, S the protective magnet which is c coil in aerial conductor, A^1 to A^{10} aerial antennae with collecting balloons, N horizontal collecting or connecting wire from which, to the center a number of co

The actual collectors consist of metal sheaths preferably made of an aluminum magnesium alloy, and are filled with hydrogen or helium and are attached t c wires. The size of the balloon is selected so that the actual weight of the balloon and the weight of the conducting wire is supported thereby. On top of the b spikes, made and gilded in a special manner hereinafter described, are arranged in order to produce a conductor action. Small quantities of radium pr particularly polonium-ionium or meso-thorium preparations considerably increase the ionization, and therewith the action of these collectors.

In addition to metal balloons, fabric balloons which are superficially metal coated according to Schoop's metal spraying process, may also be employed. A me also me produced by lacquering with metallic bronzes, preferably according to Schoop's spraying process or lacquering with metallic bronze powders in two e widely different metals, because thereby the collecting effect is considerably increased.

Instead of the ordinary round balloons, elongated cigar shaped ones may be employed. In order also to utilize the frictional energy of the wind, patches conducting substances which produce electricity by friction, may be attached to the metalized balloon surfaces. The wind will impart a portion of its ener frictional electricity, to the balloon casing, and thereby the collecting effect is substantially increased.

In practice however, very high towers (up to 300 meters is fully admissible) may be employed as antennae. In these towers copper tubes rise freely further ab tower. A gas lamp secured against the wind is then lit at the point of the copper tube and a netting is secured to the copper tube over the flame of this lamp to The gas is conveyed through the interior of the tube up to the summit. The copper tube must be absolutely protected from moisture at the place at which it ent also rain must be prevented running down the walls of the tower which might lead to a bad catastrophe. This is done by bell shaped enlargements which ex being arranged in the tower in the form of high voltage insulators of Siamese pagodas.

Special attention must be devoted to the foundations of such towers. They must be well insulated from the ground, which may be obtained by first embedding a in a box form to a sufficient depth in the ground and inserting in this an asphalt lining and then glass bricks cast about 1 or 2 meters in thickness. Over this ferro-concrete layer in which alone the metal foot of the tube is secured. This concrete block must be at least 2 meters from the ground and be fully protecte wooden covering, from moisture. In the lower part of the tower a wood or glass house for the large condenser batteries or for the motors may be constructed. Ir earth connection to the ground water, a well insulated pit constructed of vitreous brick, must be provided. Several such towers are erected at equal distances ap with a horizontal conductor. The horizontal connecting wires may either run directly from tower to tower or be carried on bell shaped insulators similar to tho voltage conductors. The width of the network may be of any suitable size and the connection of the motors can take place at any suitable places.



In order to collect large quantities of electricity with few aerials it is well to provide the aerial conductor with batteries of condensers as shown in Figures 21 21 the batteries of condensers 5 are connected on the one hand with the aerial electricity collectors Z by the aerial conductor A, and on the other hand interc with an annular conductor from which horizontal conductors run to the connecting points C to which the earth wire is connected.

Figure 22 shows a similar arrangement, Should two such series of antennae rings be shown by a voltmeter to have a large difference of potential (for exa mountains and one in the plain) or even of different polarity these differences may be compensated for by connecting sufficiently large condenser batteries (5, of Maji star conductors D and D^1. In Figure 23 a connection of three such rings of collectors to form a triangle with a central condenser battery is illustrated.

The condenser batteries of such large installations must be embedded in liquid gases or in liquids freezing at very low temperatures. In such cases a portion o energy must be employed for liquefying these gases. It is also preferable to employ pressure. By this means the condenser surfaces may be diminished, and st quantities of energy to be stored, secure against breakdown. For smaller installation the immersing of the condensers in well-insulated oil or the like, suffices. on the other hand cannot be employed as insulators.

The arrangement in the diagrams hitherto described was always such that the condenser batteries were connected with both poles directly to the aerial condens diagram of the connections for obtaining atmospheric electricity for the condenser batteries has however, been found to be very advantageous. This arrangeme they are connected only by one pole (unipolar) to the collecting network. Such a method of arrangement is very important, as by means of it a constant curre of the normal working pressure or voltage is obtained. If for example a collecting balloon aerial which is allowed to rise to a height of 300 meters, shows 40 earth voltage, in practice it has been found that the working voltage (with a withdrawal of the power according to the method hereinbefore described by me spark gaps and the like) is only about 400 volts. If however, the capacity of the condenser surfaces be increased, which capacity in the above mentioned case w the collecting surface of the balloon aerials, to double the amount, by connecting the condenser batteries with only one pole, the voltage rises under an equ current up to and beyond 500 volts. This can only be ascribed to the favorable action of the connecting method.

In addition to this substantial improvement it has also been found preferable to insert double inductances with electromagnets and to place the capacities prefer such electromagnets. It has also been found that the useful action of such condensers can be further increased if an induction coil be connected as inductive unconnected pole of the condenser, or still better if the condenser itself be made as an induction condenser. Such a condenser may be compared with a sp compressed carries in itself accumulated force, which it again gives off when released. In charging, a charge with reversed sign is formed at the other free cond through the spark gap a short circuit results, the accumulated energy is again given back since now new quantities of energy are induced at the condenser po the conductor network, which in fact charges with opposite signs to that at the free condenser pole. The new induced charges have of course the same sig network. The whole voltage energy in the aerial is thereby however increased. In the same space of time larger quantities of energy are accumulated than is such inserted condenser batteries.



Fig. 24.



Fig. 25.

In Figures 24 and 25 two different diagrams of connections are more exactly illustrated, Figure 24 shows a collecting balloon and the diagram of the connectio 25 shows four collecting balloons and the parallel connection of the condenser batteries belonging thereto.

A is the collecting balloon made of an aluminum magnesium alloy (electron metal, magnalium) of a specific gravity of 1.8 and a thickness of plate 0.1 to 0.2 are eight strong vertical ribs of T-shaped section about 10 to 20 mm in height and about 3 mm in thickness with the projecting part directed inwards (indicate so forth); they are riveted together to form a firm skeleton and are stiffened in a horizontal direction by two cross ribs. The ribs are further connected with one and transversely by means of thin steel wires, whereby the balloon obtains great power of resistance and elasticity. Rolled plates of 0.1 to 0.2 mm in t magnalium alloy are then either soldered or riveted on this skeleton so that a fully metallic casing with smooth external surface is obtained Well silvered or co plated steel wires run from each rib to the fastening ring 2. Further, the coppered steel hawser L preferably twisted out of separate thin wires (shown in dotted l and which must be long enough to allow the balloon to rise in the desired height, leads to a metal roller or pulley 3 and from thence to a winch W, well insulat By means of this winch, the balloon, which is filled with hydrogen, or helium, can be allowed to rise to a suitable height (300 to 5000 meters) and brought recharging or repairs.

The actual current is taken directly through a friction contact from the metal roller 3 or from the wire, or even from the winch or simultaneously from all t brushes (3, 3a and 3b). Beyond the brushes the conductor is divided, the paths being: --- firstly over 12 to the safety spark gap 8, from thence to the earth c secondly over electromagnet S^1, point 13, to a second loose electromagnet having an adjustable coil S^2, then to the spark gap 7 and to the second earth conduc working circuit is formed through the spark gap 7, condensers 5 and 6, and through the primary coil 9; here the static electricity formed by oscillatory discharg and converted into high frequency electromagnetic oscillations. Between the electromagnets S^1 and S^2 at the crossing point 13, four condenser batteries are are only indicated diagrammatically in the drawings each by one condenser. Two of these batteries (16 and 18) are made as plate condensers and prolon induction coils or spirals 17 and 19 while the two others (21 and 23) are induction condensers. As may be seen from the drawings each of the four condenser b and 23 is connected by only one pole to the aerial or to the collector conductor. The second poles 17, 19, 22 and 24 are open. In the case of plate condensers ha resistance an induction coil is inserted. The object of such a spiral or coil is the displacement of phase by the induction current by 1/4 periods, whilst that of th of the condenser poles which lie free in the air, works back to the collector aerial. The consequence of this is that in discharges in the collector aerial the back i the free poles allows a higher voltage to be maintained in the aerial collecting conductor than would otherwise be the case. It has also been found that such a b extremely favorable effect on the wear of the contacts. Of course the inductive effect may be regulated at will within the limits of the size of the induction coil coil in action being adjustable by means of wire connection without induction (see Figure 24, No. 20).

S^1 and S^2 may also be provided with such regulating devices in the case of S^2 (illustrated by 11). If excess voltage be formed it is conducted to earth throug spark gap 8 or through any other suitable apparatus, since this formation would be dangerous for the other apparatus.

The small circles on the collector balloon indicate places at which zinc amalgam or gold amalgam or other photoelectric acting metals in the form of small pat thin layers (0.01 to 0.05 mm in thickness) are applied to the entire balloon as well as in greater thickness to the conducting network. The capacity of the co considerably strengthened at the surface. The greatest possible effect in collecting may be obtained by polonium amalgams and the like. On the surface of the metal points or spikes are also fixed along the ribs, which spikes serve particularly for collecting the collector charge. Since it is well known that the resistanc less the sharper the spike is, for this purpose it is therefore extremely important to employ as sharp spikes as possible. Experiments made as regards these ha formation of the body of the spike or point also plays a large part, for example, spikes made of bars or rollers with smooth surface, have a many times greater p collector accumulator spikes than those with rough surfaces. Various kinds of spike bodies have been experimented with for the collector balloons hereinbefo best results were given by spikes which were made in the following way. Fine points made of steel, copper, nickel, or copper and nickel alloys, were fastened to and then placed as anode with the points in a suitable electrolyte (preferably in hydrochloric acid or muriate of iron solutions) and so treated with weak curr pressure. After 2 to 3 hours according to the thickness of the spikes or pins the points become extremely sharp and the bodies of the spikes have a rough surfac then be removed and the acid washed off with water. The spikes are then placed as cathode in a batch consisting of solution of gold, platinum, iridium, palla salts or their compounds and coated a the cathode galvanically with a thin layer of precious metal, which must however be sufficiently firm to protect them oxidation.

Such spikes act at a 20-fold lower voltage almost as well as the best and finest points made by mechanical means. Still better results are obtained if polonium c added to the galvanic bat when forming he protective layer or coating. Such pins have a low resistance at their points and even at one volt and still lower p excellent collector action.

In Figure 24 the three unconnected poles are not connected with one another in parallel. That is quite possible in practice without altering the principle of the f preferable to interconnect in parallel to a common collector network, a series of collecting aerials:

Figure 25 shows a diagram for such an installation. A^1, A^2, A^3, A^4 are four metal collector balloons with gold or platinum coated spikes which are electrolyti presence of polonium emanations or radium salts, which spikes or needles are connected over four electromagnets S^1, S^2, S^3, S^4, through an annular condu annular conductor four wires run over four further electromagnets Sa, Sb, Sc, Sd, to the connecting point 13. There the conductor is divided, one branch passin safety spark gap 8 to the earth at E^1, the other over inductive resistance J and working spark gap 7 to the earth at E^2. The working circuit, consisting of the c and a resonance motor M, such as hereinbefore described, is connected in proximity round the sparking gap section 7.

Instead of directly connecting the condenser motor of course the primary circuit for high frequency oscillatory current may also be inserted.

The condenser batteries are connected by one pole to the annular conductor R and can be either inductionless (16 and 18) or made as induction condensers as 23. The free poles of the inductionless condensers are indicated by 17 and 19, those of the induction condensers by 22 and 24. As may be seen from the drawin 17, 22, 19, 24 may be interconnected in parallel through a second annular conductor without any fear that thereby the principle of the free pole connection v addition to the advantages already set forth the parallel connection also allows of an equalization of the working pressure in the entire collector network. Su and calculated induction coils 25 and 26 may also be inserted in the annular conductor of the free poles, by means of which a circuit may be formed in the s and 28 which allows current produced in this annular conductor by fluctuations of the charges of the like appearances to be measured or otherwise utilized.

According to what has been hereinbefore stated separate collector balloons may be connected at equidistant stations distributed over the entire country, either c with one another metallically or by means of intermediate suitably connected condenser batteries through high voltage conductors insulated from earth. The s converted through a spark gap into dynamic energy of a high number of oscillations and may in such form be coupled as a source of energy b y means of a connecting, various precautions being observed and with special regulations. The wires leading from the collector balloons have hitherto been connected th conductor without this endless connection, which can be regarded as an endless induction coil, being able to exert any action on the whole conductor system.

It has now been found that if the network conductor connecting the aerial collector balloons with one another is not made as a simple annular conductor, bu circuited in the form of coils over a condenser battery or spark gap or through thermionic tubes or valves or audions, then the total collecting network e properties. The collection of atmospheric electricity is thereby not only increased but an alternating field may be easily produced in the collector netw atmospheric electrical forces showing themselves in the higher regions may also be directly obtained by induction. In Figures 26 and 28 a form of constructio basis of which the further foundations of the method will be more particularly explained.



Fig. 26.

In Figure 26, 1, 2, 3, 4 are metal collector balloons, 5, 6, 7, 8 their metallic aerial conductors and I the actual collector network. This consists of five coils a high voltage insulators in the air, in high voltage masts (or with a suitable construction of cable embedded in the earth). One coil has a diameter of 1 or 100 k S^1 are two protective electromagnets, F the second safety section against excess voltage, E its earth conductor and E1 the earth conductor of the working absorption of static atmospheric electricity is effected through the four balloon collectors, the current in order to reach the earth connection E1 must flow sp collector network over the electromagnet S, primary induction coil 9, conductor 14, anode A of the audion tube, incandescent cathode K, as the way over the e safety spark gap F offers considerably greater resistance. Owing to the fact that the accumulated current flows in one direction, an electromagnetic alternating in the interior of the collector network coil, whereby the whole free electrons are directed more or less into the interior of the coil. An increased ionization of

thereby produced. In consequence of this the points mounted on the collector balloon show a considerably reduced resistance and therefore increased static ch
points on the balloon and the surrounding atmosphere are produced. The result of this is a considerably increased collector effect.

A second effect which could not be obtained otherwise is obtained by the electromagnetic alternating field which running parallel to the earth surface, acts m
diminishing or increasing effect on the earth magnetic field, whereby in the case of fluctuations in the current a return induction current of reversed sign is al
the collector coil by earth magnetism. Now if, however, a constantly pulsating continuous alternating field is produced as stated in the above collector networ
current of the same periodicity is produced also in the collecting network coil. As the same alternating field is further transmitted to the aerial balloon, the resis
is thereby considerably reduced, whilst the collector action is considerably increased. A further advantage is that positive electrons which collect on the meta
the conversion into dynamic current produce a so-called drop of potential of the collector area. As an alternating field is present, the negative ions surround
surfaces, when discharge of the collector surfaces takes place produce by the law of induction, an induction of reversed sign on the collector surface and so fo
again a positive charge). In addition to the advantages hereinbefore set forth, the construction of connecting conductors in coil form when of sufficiently large
of a utilization of energy arising in higher regions also in the simplest way. As is well known electric discharges frequently take place at very great elevatio
observed as St Elmo's fire or northern lights. These energy quantities have no been available to be utilized up to now. By this invention all these kinds of ener
an electromagnetic nature and the direction of axis of the collector coils stands at right angles to the earth's surface, can be more or less absorbed in the same
in wireless telegraphy absorbs waves coming from a far distance. With a large diameter of the spiral it is possible to connect large surfaces and thereby to
quantities of energy.

It is well known that large wireless stations in the summer months, and also in the tropics are very frequently unable to receive the signals in consequence of in
are caused by atmospheric electricity, and this takes place with vertical coils of only 40 to 100 meters diameter. If on the contrary horizontal coils of 1 to 10
employed very strong currents may be obtained through discharges which are constantly taking place in the atmosphere. Particularly in the tropics or still b
regions where the northern lights are constantly present, large quantities of energy may probably be obtained in this way. A coil with several windings shou
similar manner any alteration of the earth magnetism should act inductively on such a coil.

It is not at all unlikely that earthquakes and spots on the sun will also produce an induction in such collector coils of sufficient size. In similar manner this co
will react on earth current more particularly when they are near the surface of the earth or even embedded in the earth. By combining the previous kind of cu
far as they are adapted for the improved system with the improved possibilities of obtaining current the quantities of free natural electricity which are to be ob
of electricity are considerably increased.

In order to produce in the improved collector coil uniform current oscillations of an undamped nature so-called audion high vacuum or thermionic tubes of su
are employed instead of the previously known spark gaps (Figure 26, Nos. 9-18). The main aerial current flows through electromagnet S (which in the case of
alternations is not connected here but in the earth conductor E^1) and may be conveyed over the primary coils in the induction winding through wire 14 to th
high vacuum grid tube. Parallel with the induction resistance 9 a regulating capacity of suitable size, such as condenser 11 is inserted. In the lower part of the
is arranged the incandescent filament or the cathode K which is fed through a battery B. From the battery B two branches run, one to the earth conductor
through battery B^1 and secondary coil 10 to the grid above *g* in the vacuum tube. By the method of connections shown in dotted lines, a desired voltage at th
may also be produced through the wire 17 which is branched off from the main current conductor through switches 16 and some small condensers (*a, b, c*
series, and conductor 18, without the battery B^1 being required.

The action of the entire system is somewhat as follows: --

On the connecting conductor of the aerial collector network being short circuited to earth, the condenser pole 11 is charged and slightly damped oscillations
short circuited existing oscillation circuit formed of the condenser 11 and self inductance 9. In consequence of the coupling through coil 10, fluctuations of vol
the grid circuit 15 with the same frequency, which, fluctuations in turn influence the strength of the electrode current passing through the high vacuum amplify
produce current fluctuations of the same frequency in the anode circuit. A permanent supply of energy to the oscillation circuits 9 and 10 consequently ta
condition of balance is set up, in which the consumed oscillation energy is equal to that absorbed. Thereby constant undamped oscillations are now produced
circuits 9-11.

For regular working of such oscillation producers high vacuum strengthening tubes are necessary and it is also necessary that the grid and anode voltages s
difference of 180° so that if the grid is negatively charged, then the anode is positively charged and vice versa. This necessary difference of phase may be
varied connections, for example, by placing the oscillation circuit in the grid circuit or by separating the oscillation circuit and inductive coupling from the an
circuit and so forth.

A second important factor in this way of converting static atmospheric electricity into undamped oscillations is that care must be taken hat the grid and anod
certain relation to one another; the latter may be obtained by altering the coupling and a suitable selection of the self-induction in the grid circuit, or as shown b
17, 18 by means of a larger or smaller number of condensers of suitable size connected in series; in this case the battery B^1 may be omitted. With a suitable se
potential a glow discharge takes place between the grid *g* and the anode A, and accordingly at the grid there is a cathode drop and a dark space is formed
cathode drop is influenced by the ions which are emitted in the lower space in consequence of shock ionization of the incandescent cathodes K and pass throu
upper space. On the other hand the number of ions passing through the grid is dependent on the voltage between the grid and the cathode. Thus is the grid v
periodic fluctuations (as in the present case) the amount of the cathode drop at the grid fluctuates and consequently the internal resistance of the tube correspon
so that when a back coupling of the feed circuit with the grid circuit takes place, the necessary means are afforded for producing undamped oscillations and
according to requirements from the collecting conductor.

The frequency of the undamped oscillations produced is with a suitably loose coupling equal to the self-frequency of the oscillation circuits 9 and 10. By a su
the self induction of the coil 9 and capacity 11 it is possible to extend from frequencies which produce electromagnetic oscillation of only a few meters wavel
lowest practical alternating current frequency. For large installations a suitable number of frequency-producing tubes of the well-known high vacuum transmi
to 2 kw in size may be connected in parallel so that in this respect no difficulty exists.

The use of such tubes for producing undamped oscillations, and also the construction and method of inserting such transmission tubes in an accumulator or
known and also that such oscillation producing tubes only work well at voltages of 1000 up to 4000 volts, so that on the contrary their use at lower voltages is c
difficult. By the use of high voltage static electricity this method of producing undamped oscillations as compared with that through spark gaps must be reg
solution particularly for small installations of outputs of from 1 to 100 kw.

By the application of safety spark gaps, with interpolation of electromagnets, not only is short-circuiting avoided but also the taking up of current is regu
producers inserted in the above way form a constantly acting electromagnetic alternating field in the collector coil, whereby as already stated, a considerable ac
takes place. The withdrawal wire or working wire is connected at 12 and 13, but current may be taken by means of a secondary coil which is firmly or movabl
suitable way inside the large collector coil, i.e., in its electromagnetic alternating field, so long as the direction of its axis runs parallel with that of the main
coil.

In producing undamped oscillations of a high frequency (50,000 per second or more) in the oscillation circuits 9 and 11, electromagnets S and S^1 must be in
frequency oscillations are not to penetrate the collector oil, between the oscillation producers and the collector coil. In all other cases they are connected s
earthing (as in Figures 27 and 28).



Fig. 27.

In Figure 27 a second method of construction of the connecting conductor of the balloon aerials is illustrated in the form of a coil. The main difference c addition to the connecting conductor I another annular conductor II is inserted parallel to the former on the high voltage masts in the air (or embedded as a cabl both in te form of a coil. The connecting wire of the balloon aerials is indicated as a primary conductor and also as a current producing network; the other is network and is not in unipolar connection with the current producing network.

In Figure 27 the current producing network I is shown with three balloon collectors 1, 2, 3 and aerial conductors 4, 5, 6; it is short-circuited through c inductance 9. The oscillation forming circuit consists in this diagram of spark gap f, inductance 10, and condenser 11; the earth wire E, is connected to earth ov S^1. F s the safety spark gap which is also connected to earth through a second electromagnet S at E. On connecting up the condenser circuit 11 this is charged c f whereby an oscillatory discharge is formed. This discharging current acts through inductance 10 on the inductively coupled secondary 9, whereby in the pro modification of the potential of the condenser 19 is produced. The consequence of this is that oscillations arise in the coil shaped producer network. These osc current in the secondary circuit II, which has a smaller number of windings and a less resistance, the voltage of which, according to the proportion of the nu and of the ohmic resistance, is considerably lower whilst the current strength is greater.

In order to convert the current thus obtained into current of an undamped character, and to tune its wavelengths, a sufficiently large regulatable capacity 20 in the ends 12 and 13 of the secondary conductor II. Here also current may be taken without an earthy conductor, but it is advisable to insert a safety spark gap this with the earth over an electromagnet S2.

The producer network may be connected with the working network II over an inductionless condenser 21 or over an induction condenser 22, 23. In this ca conductor is unipolarly connected with the energy conductor.



28.

In Figure 28 the connecting conductor between the separate accumulator balloons is carried out according to the autotransformer principle. The collecting c aerial balloons 1, 2, 3, 4, the windings of which are not made side by side but one above the other. In Figure 28 the collector coil I is shown with a thin lin connected prolongation coils II with a thick line. Between the ends I^1 and II^1 of the energy network I a regulating capacity 19 is inserted. The wire I^1 is co output wire and with the spark gap F.

As transformer of the atmospheric electricity an arrangement is employed which consists in using rotary pairs of condensers in which the one stator surface B the main current, whilst the other A is connected with the earth pole. Between these pairs of short-circuited condensers are caused to rotate from which the con be taken by means of two collector rings and brushes, in the form of an alternating current, the frequency of which is dependent on the number of balloons and the rotor. As the alternating current formed in the rotor can act, in this improved method of connection described in this invention, through coils 1 on the increase or diminution of the feed current in I can be obtained according to the direction of the current by back induction. Current oscillations of uniform rhyt in the coil shaped windings of the produce network.

As the ends of this conductor are short-circuited through the regulatable condenser 19 these rhythms produce short-circuited undamped oscillations in the ener periodicity and wave lengths of which oscillations can be adjusted according to desire by altering the capacity 19 to a given wavelength and therewith also to a

These currents may also be employed in this form directly as working current through the conductors II^1 and III. By inserting the condenser 20 a connecti conductors may also be made, whereby harmonic oscillations of desired wavelengths are formed. By this means quite new effects as regards current distribu The withdrawal of current can even take place without direct wire connection if, at a suitable point in the interior of the producing network (quite immaterially a diameter of 1 or 100 km) a coil tuned to these wavelengths and of the desired capacity is firmly or movably mounted in the aerial conductor in such a direction is in parallel with that of the collector coil. In this case a current is induced in the producing network, the size of which is dependent on the total capac and also on the periodicity employed. A possibility is thereby afforded in future, of taking energy from the producer network by wireless means. As there atmospheric electricity also magnetic earth currents and energy from the higher atmosphere (at leas partially may be simultaneously obtained, this last system atmospheric energy is of particular importance for the future.

Of course everywhere instead of spark gaps grid vacuum tubes may be employed as producers for undamped oscillations. The separate coils of the producer n diameters may be connected with one another through separate conductors all in parallel or all in series or in groups in series. By regulating the number of osc the extent of the voltage more or less large collector coils of this kind may be employed. The coils may also be divided spirally over the entire section. The co out in angular form or also in triangular, quadrangular, hexagonal or octagonal form.

Of course wires may be carried from a suitable place to the center or also laterally which serve the current waves as guides. This is necessary when the cu conducted over mountains and valley and so forth. In all these cases the current must be converted into a current of suitable periodicity.

As already hereinbefore mentioned separate collecting balloons may be directly metallically interconnected at equidistant stations distributed over the entire c connected by interpolation of suitable condenser batteries by means of high voltage conductors. The static electricity is converted through a spark gap into dy high number of oscillations, and could then in such forms, wit a suitable arrangement of the connections, observing various measures of protection, be empl energy after separate or special regulation.

According to this invention in order to increase the collecting effect of the balloon in the aerial collector conductor or in the earth wire, radiating collectors are consist either of incandescent metal or oxide electrodes in the form of vacuum grid tubes, or electric arcs (mercury and the like electrodes), Nernst lamps, or various kinds may be simply connected with the respective conductor.

It is well known that energy can be drawn of from a cathode consisting of an incandescent body opposite an anode charged with positive electricity (vacuum gr however, a cathode was always first directly placed opposite an anode, and secondly the system always consisted of a closed circuit.

Now if we dispense with the ordinary ideas in forming light or flame arcs in which a cathode must always stand directly opposite an anode, charged to a another body freely floating in the air, or regard the incandescent cathode only as a source of unipolar discharge (which represent group and point discharg machines similar to unipolar discharges), it may be ascertained that incandescent cathodes and less perfectly all incandescent radiators, flames and the like a large current densities and allow large quantities of electric energy to radiate into the open space in the form of electron streams as transmitters.

The object of this invention is as described below, if such incandescent oxide electrodes or other incandescent radiators or flames are not freely suspen connected metallically with the earth so that they can be charged with negative terrestrial electricity, these radiators possess the property of absorbing the free charges contained in the air space surrounding them (that is to say of collecting them and conducting them to earth). They can therefore serve as collec comparison to the action of the spikes, or points, a very large radius of action R; the effective capacity of these collectors is much greater than the geometri calculated in an electrostatic sense.

Now as our earth is surrounded as is well known with an electrostatic field and the difference of potential

$$\frac{\delta V}{\delta h}$$

of the earth field according to the latest investigations, is in summer about 60 to 100 volts and in winter 300 to 500 volts per meter of difference in heigh calculation gives the result that when such a radiation collector or flame collector is arranged for example on the ground, and a second one is mounted vert distance of 2000 meters and both are connected by a conducting cable, there is a difference in potential in summer of about 2,000,000 volts and in winter e volts and more.

According to Stefan Boltzmann's law of radiation, the quantity of energy which an incandescent surface (temperature T) of 1 sq cm radiates in a unit of time (temperature T_o) is expressed by the following formula:

$S = \delta (T^4 - T^4_o)$ watt./sq cm.

And the universal radiation constant δ is according to the latest researches of Ferry (*Annales de Chimie et de Physique*, 17: 267 [1909]) equal to 6.30×10^{-12} w

Now if an in incandescent surface of 1 sq cm shows, as compared with the surrounding space a periodic fall of potential δV it radiates (independent of the curr is to say of the sign) in accordance with the above formula, for example at a temperature of 3725° C an energy of 1.6 kw/sq cm/second. As for the radiation th be calculated for the collection of energy, but reversed. Now, as carbon electrodes at the temperature of the electric arc support on the current basis a current d 60 to 65 amperes per sq cm no difficulties will result in this direction in employing radiating collectors as accumulators.

If the earth be regarded as a cosmically insulated condenser in the sense of geometrical electrostatics *x* there results from the geometric (compare Ed *Elektrische Bogenlicht* [The Electric Arc Light], page 169) capacity of the earth according to Chwolson:

For negative charging 1.3×10^6 Coulomb

For negative potential $V = 10 \times 10^8$ volts.

From this there results however, EJT = 24.7×10^{24} watt/sec. Now if it is desired to make a theoretic short circuit through an earthed flame collector this w electric total work of about $79{,}500 \times 10^{10}$ kilowatt years. As the earth must be regarded as a rotating mechanism which thermodynamically, electromagn kinematically coupled with the sun and star system by cosmic radiations and gravitation a diminution of the electric energy of the earth field is not to be fea which the incandescent collectors would withdraw from the earth field can only case by the withdrawal of motor work a lowering of the earth temperature (300) and reduce this to that of the world space (T = O) by using the entire energy. This is however not the case as the earth does not represent a cosmically system. On the contrary there is conveyed to the same according to the recent value corrected by Perry for the solar constants through the radiation from the $18{,}500 \times 10^{10}$ kw. Accordingly, any lowering of the earth temperature (T_E) without a simultaneous lowering of the sun's temperature (T_S) would contradict St law of radiation.

$S = \delta (s^4 - T^4)$.

From this it must be concluded that if the earth temperature (T_E) sinks the total radiation S absorbed by the earth increases, and further also that the secular sp
the earth is directly dependent on that of the sun and the other radiators cosmically coupled with the sun and is connected most closely with these.

The incandescent radiation collectors may, according to this invention, be employed for collecting atmospheric electricity if they (1) are charged with t
electricity (that is to say when they are directly connected by means of a metallic conductor with the earth) and (2) if large capacities (metal surfaces) charge
are mounted opposite them as positive poles in the air. This is regarded as the main feature of the present invention as without these inventive ideas it would
collect with an incandescent collector, sufficiently large quantities of the electrical charges contained in the atmosphere as the technology requires; the radiu
flame collectors would also be too small, especially if it be considered that the very small surface density (energy density) (δ about = 2 x 7 . 10^9 St. E. per
allow of large quantities of charge being absorbed from the atmosphere.

x) Calculated according to Poisson's calculation:

$\Delta V = -4\pi\delta$; as here the alteration of the potential or potential gradients only takes place in the direction o the normal, this calculation assumes the simple fo

$$\delta = \frac{1}{4\pi} \times \frac{\delta^2 V}{\delta n^2}$$

It has indeed already been proposed to employ flame collectors for collecting atmospheric electricity and it is known that their collecting effect is substantially
the points. It is however, not known that the quantities of current which could hitherto be obtained are too small for technical purposes. According to my exper
for this is to be found in the too small capacities of the collector conductor poles. If such flame or radiating collectors have no or only small positive surfac
action for large technical purposes is too small. If the incandescent collectors be constantly kept in movement in the air they may collect more according to
movement, but this again is not capable of being carried out in practice.

By this invention the collector effect is considerably increased by a body charged with a positive potential and of the best possible capacity being also held
direct earth connection) opposite such an incandescent collector which is held floating in the air at a desired height. If for example, a collecting balloon of
metalized balloon fabric be caused to mount to 300 up to 3000 meters in the air and as positive pole it is brought opposite such a radiating collector connected
the earth, quite different results are obtained.

The metallic balloon shell (with a large surface) is charged to a high potential by the atmospheric electricity. This potential is greater the higher the collecting
the incandescent collector. The positive electricity acts concentratedly on the anode floating in the air as it is attracted through the radiation shock ionization
the incandescent cathode. The consequence of this is that the radius of action of the incandescent cathode collector is considerably increased and thereby a
effect of the collecting balloon surface. Further the large capacity of the anode floating in the air plays therefore an important part because it allows of the takin
and thereby a more uniform current is obtained even when there is a large consumption: this cannot be the case with small surfaces.

In the present case the metallic collecting balloon is a positive anode floating in the air and the end of the earth conductor of this balloon serves as positive pol
the surface of the radiating incandescent cathode, which in turn is charged with negative earth electricity being conductively connected to earth.

The process may be carried out by two such contacts (negative incandescent cathode and anode end of a capacity floating in the air) a condenser and an in
being switched on in parallel, whereby simultaneously undamped oscillations may be formed.

In very large installations it is advisable to connect two such radiating collectors in series. Thus an arc light incandescent cathode may be placed below on the
an incandescent cathode which is heated by special electromagnetic currents be located high in the air. Of course for this the special vacuum Liebig tubes wi
may also be employed. An ordinary arc lamp with oxide electrodes may be introduced on the ground and the positive pole is not directly connected with the c
but through the upper incandescent cathode or over a condenser. The method of connecting the incandescent cathode floating in the air may be seen in Figures

B is the air balloon, K a Cardan ring (connection with the hawser), C the balloon, L a good connecting cable, P a positive pole, N negative incandescent cat
conductor.



Figure 29 represents the simplest form of construction. If electric oscillations are produced below on the ground by means of a carbon arc lamp or in oth considerably greater electric resistance is opposed to that in the direct way by inserting an electrical inductive resistance 9. Consequently between P and N, a and as, over N and P only an inductionless ohmic resistance is present, a spark will spring over so long as the separate induction co-efficients and the calculated. The consequence of this is that the oxide electrode (carbon or the like) is rendered incandescent and then shows as incandescent cathode an inc effect. The positive poles must be substantially larger than the negative in order that they may not also become incandescent. As they are further connect balloon area which has a large capacity and is charged at high voltage, an incandescent body which is held floating in the air and a positive pole which capacities is thereby obtained in the simplest way. The incandescent cathode is first caused to become incandescent by means of separate energy produced on t maintained by the energy collected from the atmosphere.

Figure 30 only shows the difference that instead of a round balloon a cigar-shaped one (of metal or metalized fabric) may be employed and also a conde between the incandescent cathode and the earth conductor so that a short circuited oscillation circuit over P.N. 5 and 9 is obtained. This has the advantage quantities of electricity cause the cathode to become incandescent and much larger cathode bodies may be rendered incandescent.



In this form of construction both the incandescent cathode and also the positive electrode may be enclosed in a vacuum chamber as may be seen in Figure carried well insulated through the cover of a vessel and ends in a condenser disc 5. The cover is arched in order to keep off the rain. The vessel is entirely or magnetic metal and well-insulated inside and outside. Opposite the disc 5 another disc 6 and on this again a positive pile of the vacuum tube g with the inca (oxide electrode) N is arranged. The negative electrode is on the one hand connected with the earth conductor E, and on the other hand with the inductive resi also connected with the cable L with the positive pole and wound round the vessel in coils. The action is exactly the same as that in Figure 29 only in incandescent cathode one enclosed in vacuo is employed. As in such collectors only small bodies can be brought to incandescence in large installations a vacuum tubes must be inserted in proximity to one another. According to the previous constructions Figures 31 and 33 are quite self evident without further exp



Figures 34-37 represent further diagrams of connections over radiating and flame collectors, and in fact, how they are to be arranged on the ground.

Figure 34 shows an arc light collector with oxide electrodes for direct current and its connection; Figure 35 a similar one for alternating current, Figure 3 collector with a Nernst lamp and Figure 37 a similar one with a gas flame.

The positive pole 1 of the radiating collectors is always directly connected to the aerial collecting conductor A. In Figure 34 this is further connected over the 5 with a second positive electrode 3. The direct current dynamo *b* produces current which flows over between the electrodes 3 and 2 as an arc light. On the fo the negative incandescent electrode 2 absorbs electricity from the positive poles standing opposite it and highly charged with atmospheric electricity and conve working circuit. The spark gap 7, inductive resistance 9 and induction coil 10 are like the ones previously described. The protective electromagnet S guar against earth circuiting, the safety spark gap 8 from excess voltage or overcharging.

In Figure 35 the connection is so far altered that the alternating current dynamo feeds the exciting coil 11 of the induction condenser. 12 is its negative and 13 i the coil 3 on the magnet core of the dynamo is correctly calculated and the periodicity of the alternating current is sufficiently high an arc light can be forme poles 1 and 2. As the cathode 2 is connected with the negatively charged earth, and therefore always acts as a negative pole, a form of rectification of the a produced by the dynamo 3 is obtained, the second half of the period is always suppressed. The working circuit may be carried out in the same way as in Figur gap 7 may however be dispensed with, and instead thereof between the points m and n a condenser 5 and an induction resistance 9 may be inserted from wh taken inductively.

Figure 36 represents a form of construction similar to Figure 34 only that here instead of an arc lamp a Nernst incandescent body is employed. The Nernst la the battery 3. The working section is connected with the negative pole, the safety spark gap with the + poles. The working spark gap 7 may also be dispe current for it taken at 12 over the oscillation circuit 5, 11 (shown in dotted lines).

Flame collectors (Figure 37) may also be employed according to this invention. The wire network 1 is connected with the aerial collector conductor A and th earth. At the upper end of the latter, long points are provided which project into the flame. The positive electrode is connected with the negative over a co induction coil 9 with the earth.

The novelty in this invention is firstly, the use of incandescent cathodes opposite positive poles which are connected with large metallic capacities as au surfaces, (2) the connection of the incandescent cathodes with the earth whereby, in addition to the electricity conveyed to them from the battery or machine incandescing, also the negative charge of the earth potential is conveyed, and (3) the connection of the positive and negative poles of the radiating collectors circuit alone or with the introduction of a suitable inductive resistance, whereby simultaneously an oscillatory oscillation circuit may be obtained. The coll these methods quite considerably increased.

I declare that what I claim is: --- [Claims not included here]

British Patent # 157,262

(10 July 1922)

Improvements in Electric Motors

Hermann Plauson // Otto Traun's Forchungs-Laboratorium GmbH

This invention relates to that type of motor in which rotation is produced by means of the attraction and repulsion of surfaces carrying charges of electricity.

According to this invention a stator and rotor are formed of condensor surfaces and charges of electricity thereon imposed in the form of alternating currents of

The invention is more particularly described with reference to the accompanying drawing in which: ---

Figure 1 shows a simple form of motor and feed.


Fig.1
1
3
4a
3x
14
5
7
8
9
6
10
12
16
17
11
4x
4
15
3a
2
13

Figure 2 is a modification of Figure 1.


Fig.2.
a
11
14
2
5
9
8
3
8
-9
b
1
10
4
7
15
6
10
d
12
13

Figure 3 shows one form of a spiral condenser surface.

Figure 4 shows a wire wound condenser surface.

Figure 5 is a diagram of one type of rotor.


Fig.3


Fig.4


Fig.5.
1
4
5
7
6
9
10
3
8
2
14
15

The inner plates of the condenser 5 and 6 are charged from a spark gap 7, 8 connected to a source of energy of sufficiently high pressure (alternating or direct potential has risen so far that a spark springs over.

The spark gap 7, 8 forms with the condenser 5 and self-inductance 9 and condenser 6 a closed oscillatory circuit and alternating currents of high frequency w this circuit. The high frequency current produced in the primary circuit 9 excite by induction in the secondary circuit 10 currents of the same periodicity.

The improved type of motor is fed by the discharges produced by the induction in the secondary circuit.

Hitherto only Tesla's motor system (shown diagrammatically in Figure 1, 16 and 17) was known for this purpose. The above-mentioned diagram is only sho the fundamental principle. It has however no practical interest for carrying out large machines by reason of the impossibility of the regulation and the low effic

Now according to this process, all these defects are overcome by the construction of a machine which is applicable for high frequency currents and of a more nature. The difference between the principle of construction of these motors as compared with those hitherto customary consists in that the motor is not based magnetic induction only (as have been all motors hitherto and also Tesla's motors).

It has been fund that the machine constructed according to Figure 1 cannot only be fed directly with static electricity but if it is connected to a source of high fr will operate.

The applicants call this new type of motors 'condenser motors' to differentiate them from hitherto existing types.

The simplest form of construction of such condenser motors is shown in Figure 1, and this motor may be fed with high frequency alternating currents.

At a given moment positive electricity is charged by means of the lead 14 to the stator surface 1 and to the brush 3x (Figure 1). The brush 3x is connect condenser surface 3, so that both the stator surface 1 and also the rotor surface 3 is charged with positive electricity. The stator surface 1 and the rotor sur charged with positive electricity and the second rotor surfaces 4 and 4a by brushes 4x with negative electricity, such motors can then be started by providing i surfaces 11, 12, the earth connection 13 of one of which is broken by a switch (not shown) according to the direction of rotation desires, or alternatively t started by a separate source of alternating current in a manner similar to the starting of synchronous motors of known construction. After a half revolution of t 3x comes in contact with the second collector surface 4 so that now this surface is connected by the brush 3x with the stator surface 1 and the brush 4x with the 3. Consequently with a reverse direction of current through the second half of the oscillation period all the hereinbefore mentioned effects take place in the which, however, produces no alteration in the direction of rotation because the dead points between two directions of oscillation are overcome by inertia.

Although this motor is easy to start it can only be employed for small experimental and measuring purposes because the stator and rotor surfaces are made of s heated by Foucalt (eddy) currents. In spite of its simplicity and its unsuitability for use in practice it must however be regarded as a basic type for technical calc

The condenser motor shown in Figure 2 differs from Figure 1 by the rotor surfaces consisting of six condenser surfaces connected one behind the other in s connected with three collector surfaces, so that at any one moment only two adjacent collector surfaces come under the two brushes (3 and 4). In its other actio to Figure 1. The leads 14 and 15 may be connected either to the ends of the secondary coil 10 or directly with the source of energy. The outer thicker line i surfaces 1 and 2 (that is to say the unmoving part of the motor), 11 and 12 shown by thick dotted lines means earthed additional poles of the stator, 8, 9, an parts of the rotor condenser surfaces which in turn are connected with the collector surfaces 8, 9, and 10. 5, 6, and 7 are the inner parts of the condenser surfac 3 and 4 are brushes.

Hitherto stator and rotor surfaces of compact metal have been spoken of. These however become highly heated with eddy currents and hardly yield 10-15% c examining into such small useful effects it was found that certain forms of metal sections in the stator and condenser surfaces highly increase these. It was t that if slots or notches be cut in the metal surfaces of the stator and rotor in the form of a spiral, not only was a higher useful effect possible, but also an easier a regulation could be obtained.

Experiments have shown that by such a form of construction it is possible to build a very useful motor for high frequency alternating currents more partic undamped nature.

If for example the system of construction of a stator shown in Figure 1, but four polar, be taken and the system of rotor construction shown diagrammaticall with the form of construction of the condensers of the stator as well as of the rotor according to Figure 3, a condenser motor is obtained which works well in e high frequency alternating current. It was also observed that the motors in such forms of construction were found to be more sensitive to resonance effects. S works the best if stator and rotor surfaces have equal capacity and self-inductance so that the windings both in the stator and also in the rotor are in resonance.

A motor constructed according to the foregoing kind is already fully technically applicable. But even these motors have a series of faults, more particularly construction. For example, the attachment of the spiral condenser surfaces both of the stator and of the rotor sown in Figure 3 are in practice difficult to carry practice the condenser and stator surfaces are simply wound of wire or bands in the form shown in Figure 4. Such stator and rotor surfaces may, without fu regarded as electromagnetic poles, although they are not made of iron as is the case in electromagnets. Such machines may be spoken of directly as motors f alternating currents in which the separate pole surfaces consists of wound induction condenser surfaces of which one is sound on the stator and the other on the

If the coil as shown in Figure 4 be made of well insulated wires the coil can be embedded in insulating material either for the stator or motor surfaces as has in the case of ordinary single and multiphase motors. At the same time the possibility is afforded by increasing the number of turns to produce a greater or sm the self induction co-efficients.

In Figure 5 is shown a modified construction of a rotor for a four pole motor consisting of four condenser surfaces 1, 2, 3, 4, of which 1 and 2 are connected th 9 coupled with the coil 10. Four inner surfaces 5, 6, 7, 8 are provided of which 5 and 6 are directly connected also 7 and 8 similarly connected.

The pairs of like poles are connected by wires 14 and 15 to the source of energy. By a suitable selection of the values of the reactance and capacity in these circuits may be formed.

Having now particularly described and ascertain the nature of our said invention and in what manner the same is to be performed, we declare that what we cla not included here]

British Patent # 157,263

Process & Apparatus for Converting Static Atmospheric Electrical Energy into Dynamic Electrical Energy of any Suitable High

Hermann Plauson // H.O. Traun's Forschungs-Laboratorium GmbH

Static aerial electricity in the form of direct current can be converted by using spark gaps and with the assistance of oscillatory circuits into dynamic electrical high number of alternations of a more or less undamped nature and in such form --- either direct or by means of a special kind of resonance or 'condenser moto utilized for technical purposes as mechanical energy.

For small installations this system may be very well employed; about 100 horsepower may be stated as practical limit. In constructions of larger aggregate diff the spark gaps however increase considerably. Further it is desirable to convert the accumulated currents of from 100 to 1000 periods which may then be use types of alternating current machines instead of into electromagnetic waves of a high number of alternations.

In experimenting with condenser motors the construction of which forms the object of British Patent # 157,262 it was observed that the rotor, if one pole of the connected with the aerials collecting aerial electricity and the other pole with the earth, not only could act as a motor, but if vice versa the rotor connection interrupted and the rotor caused to rotate by means of another motor, that when the brushes supply an alternating current the periodicity of which is dependent poles and the revolutions of the rotor. Such an apparatus may therefore be regarded as a transformer of static into dynamic electrical energy.

The invention is more particularly described with reference to the accompanying diagrams in which: ---



In Figure 1A is a strong accumulator battery, 1 and 2 are the outer poles of the transformer, consisting of simple metallic plates or are as shown in Figures 8- coils without an electromagnet being present. Between these poles an armature is revolubly mounted on a shaft, which armature also consists of two similar cy plates 3 and 4. These are metallically connected with two collector rings 5 and 6 on which two brushes 7 and 8 freely run which again are short-circuited with c primary coil 9. 10 is the secondary coil with the free ends 11 and 12. If through the accumulator battery the stator plate 1 is charged with positive electricity, it of reverse sign on the rotor surface 3 which is connected by the brushes 7 and 8 over the primary coil 9 with the second rotor surface 4. This latter is there positive electricity, which in turn induces negative electricity on the stator surface 2/ Up to this moment everything takes place in the same way as if two connected one behind the other in the current circuit A. If however, by means of mechanical power, this rotor be caused to rotate, the surface conditions ar quarter revolution the rotor plates are between the stator plates and therefore no condenser surface faces another. By this means however, the capacity of th reduced to a minimum and a change of current will also result in the main 9. Now if the rotor be turned further through 90 degrees by mechanical energy the ro opposite the stator plate 2 and the rotor plate 4 opposite the stator plate 1, so that then the rotor pates are in a field of reverse sign. A fresh charge of curr direction now runs through the primary coil 9. After a further half revolution the same action is repeated so that after a full revolution the initial condition is aga result of such a revolution is an alternating current the periodicity of which is equal to the number of revolution. In practice of course not two poles but possible would be employed because thereby the number of alternations would e considerably increased. The primary alternating current thus obtained induces circuit an alternating current the potential of which is dependent on the winding of the coil. Figure 7 shows a multipolar machine.

If the stator surface 1, instead of being connected with the battery be connected with a collecting aerial network and the other stator surface 2 be directly eart wich is otherwise constructed as hereinbefore, be rotated by a separate motor a much stronger alternating current results which is to be ascribed to the circums higher potential can be charged on the pole surfaces of the stator by reason of the higher pressure of the static electricity than where accumulators are employ the transformer has of course much larger quantities of energy supplied to it.

Figure 2 shows a mode of connections. The stator surface 1 is connected with the aerial antennae which is connected through the safety spark gap F to earth surface 2 is directly earthed at E2. The inner revoluble rotor surfaces 3 and 4 are interconnected by means of an induction coil which is constructed directly current is taken as in Figure 1 up to collector rings by means of brushes, which are not shown for the sake of clearness, and further conveyed through the cond Between these a condenser 5 may be inserted. There is thereby formed a short oscillatory oscillation circuit free from spark gaps, which circuit consists of th and condenser 5 and is fed by the periodic charging current impulse. By this means the possibility is afforded of obtaining a kind of current which is charac periods and is undamped and oscillatory. Of course a simple alternating current may be obtained by cutting out the condenser.

Instead of the induction coil the condenser may also b constructed in the rotor. His can be carried out in such a way that its ends serve directly as collecto current through the brushes. In Figure 3 such a motor is sketched in perspective, 3 and 4 are the rotor surfaces, 5 and 6 are the condenser surfaces constructed t rotor consisting of two co-axial cylinders fitting one in the other in such a way that free room is left for the brushes 7 on one end of the condenser cylinder 6.

The condenser may be made in the form of a cylindrically wound spiral forming the capacity and reactance as shown in Figure 4. A further type of transfo Figure 5. The difference consists in the stator and rotor surfaces not only each assuming a quarter of the circuit but almost the half. By this means the space condenser surface is better utilized. Charge is produced only when the rotor surfaces face the full scope of the stator surfaces.

In addition a condition is obtained in which the stator surfaces are inductively connected by the rotor surfaces. The consequence of this is that an a simultaneously results which is produced without sparking otherwise the connection is as before.

Figure 6 shows the alternation of the rotor surfaces; the rotor here consists of two cylindrical condenser plates arranged concentrically, each divided int connected so that half the inner cylinder is connected to half the outer. Such a machine shows the more complete transformer action.

Fig.7.



Figure 7 shows a four polar transformer. It consists of a metal casing, the lower half of which is fastened with the foundation plates 17 to the support or foun
half, the cover, is connected by bolts 15 and 16 firmly with the under part. This upper sleeve or casing is insulated from the under part. Two rings 1 and 2
constructed in the casing. The ring 1 is metallically connected with the collector aerial and the ring 2 with the earth. On both rings an equal number of s
mounted side by side but well insulated from one another and thus form an electrostatic field similar to the electromagnetic in many alternating current ma
consists in similar manner of two rings 5 and 6 on which an equal number of rotor surfaces are fixed so that each stator surface faces a rotor surface. By the br
alternating current formed is removed from the collector. The charge is conveyed by the conductor 14 to and by 13 away. If this rotor be then rotated by mea
positive and negative fields precisely as in the case of magnetizing will alter and thereby an alternating current is formed in the rotor, the periods of which are
number of the poles and the revolutions per second.

At the commencement it was thought that this apparatus could only be regarded as alternating current converters, but it was soon found that much more energy
rotate the rotor than might be necessary to overcome the friction. It was then found that the considerable expenditure of energy for rotating the rotor was caus
being moved through strongly electrostatic fields since the electrostatic lines of force must be cut at right angles and that further in the conductors a stronger
was otherwise to be expected. This apparatus must therefore not only be regarded as a transformer, but also as an energy producer, with the difference that the
obtained instead of by means of electromagnets, by static fields of high pressure. The entire system may, to some extent, be compared with a dynamo in wh
takes place by means of a fixed constant magnet. It was further ascertained that this way of using the atmospheric electricity produced a sort of suction on the
and that thus suitable greater quantities of current could be obtained.

The effects which in this apparatus became evident are extremely interesting and open a prospect of being able to obtain here a great deal more. Merely that
made it possible to transform suitable quantities of atmospheric electricity into alternating current of high or lower frequency (without the use of spark gaps)
extreme utility of these apparatus. Should in future, the construction of larger aggregates be necessary the transformer installation may be constructed in such
which are fed by a current obtained from an installation with spark gaps produce a certain quantity of energy which may then be employed for producing cu
the last described system.

The results of the examinations made for this may be construed as follows.

(1) If solid electrodes (condenser surfaces, rotor and stator surfaces) are employed they become hot. This effect may be considerably reduced by cutting the el
form Figure 8, but not entirely removed. This form allows the surface of the condenser plate to be enlarged or increased; the electrodes may be fastened in a
the under frame by perforation 1, 2, 3, 4, 5.

Fig.8



Fig. 9.



(2) If nicks or notches in spiral form as shown in Figure 9 seen from the side end in Figure 10 in section are employed, not only is the transformer effect gre
yields also more current, but require greater quantities of energy for their movement than a simple commutator action would require.

Fig. 10



Fig. 11



(3) The greatest effect is obtained if the rotor and stator surfaces are wound in flat spiral form of suitably thick wire, and in such a way that the inductive effec
the capacity is calculated in suitable proportion and this result is adapted to a suitable periodicity. In practice this is preferably done by the wire bent in spiral fo
in a separate vulcanite or hard rubber mass (see Figure 11) so that a smooth pole surface is formed similar to that in phase motors.

Fig. 12



Fig. 13.



Regular undamped oscillations of a high frequency may however be produced if the converter be carried out in the manner shown in Figure 13. The aerial wir
connected with the ring 20. To this two pole surfaces 1 and 2 are connected. The inductive earth pole is also connected with a second ring 10 from which again
2a are branched off. Of course in similar manner any suitable number of poles may be branched of. In similar manner there are in the rotor two poles fastened
and 4 and 3a and 4a) connected with separate collector rings. From these two rings the current is collected by means of two brushes. The induced alternating c
directly metallically connected with an inductive earth stator conductor over an induction coil 9. Further a combined inductance and capacity 5 is inserted betw
11 and 12 in parallel with the converter. By this means a sparkless oscillatory circuit is obtained which can act on the exciting current in the stator. This pro
periodic alteration of the charging quantities according to the oscillation curves of the rotor currents in consequence of which the stator charge also commenc
oscillations and if the stator and rotor surfaces are calculated to one another in such a way that they are adapted to form oscillations of waves of similar
converter is caused to oscillate and furnishes undamped oscillations of a high number of alternations, but of periodically changed amplitude, the form of whic
the amplitude of the main alternating current and is caused by the number of the poles and revolutions per second. Thus an alternating current of, for examp
formed, the separate periods of which are formed by undamped oscillations of a higher number of alternations. In Figures 14-16 four other diagrams of convert
the object of which is not to produce usual alternating current, but oscillations of high frequency.

Fig. 14



The main difference of these systems from those previously described is that from the connection of the collecting aerials is made between the stator pole 1 (F
pole 16 of the condenser 17 and the earth connection between a second stator pole 2 and the pole 18 of the condenser 19. The other poles of these condensers 1
circuited through a ring over two inductive primary coils 9 and 9a with one another. The secondary coils form the rotor conductors 10 and 10a. The rotor itsel

the manner shown in Figure 6 of two short-circuited plate condensers which may be wound as shown in Figure 11. In similar manner of course the stator sur
formed. The collector rings of the rotor with the two brushes for collecting current are here not shown in order to simplify the drawings. By the conn
condensers in the exiting circuit of the converter and also by the action of the alternating current produced in the rotor on the stator circuit, with a correct
capacity and the self-induction co-efficients a maximum action may be obtained. The kind of current produced will be similar to that described for Figure 12.


Fig. 15

The novelty of the converter illustrated in Figure 15 consists mainly in that the current resulting in the rotor is not directly employed, but only serves a exci
coils 9a and 9b. The working current is produced in the secondary coils 10 and 10a and further conducted through the conductors 11 and 12. The stator currer
by the regulatable inductive resistance 9 to the same resonance as the rotor current.


Fig. 16

In Figure 16 a very similar system is shown to Figure 14. The condenser 5 is however connected in parallel with the converter; and by the inductive resistance
rotor a short circuited oscillatory circuit is formed which gives extraordinarily good results and is simple in construction.

The inductive resistance 9 may also instead of being constructed in the rotor be constructed as primary coil employed outside the rotor and short circuit the
over the stator surfaces (see Figure 17).


Fig. 17.

The last six types serve only for producing oscillations of a high number of alternations. If it be desired to obtain ordinary alternating current there complica
arrangements are not required as the types illustrated in Figures 1 to 11 suffice. It is self-evident that these arrangements may be altered in various ways by r
condenser surfaces in practice.
Having now particularly described and ascertained the nature of our said invention and in what manner the same is to be performed, we declare that what
Claims not included here]

If you want to support our research, make an optional donation.
Thanks

If you want to support our research make a donation Thanks

Donazione

advertisement

FREE ENERGY MICROWAVE

Technology (/technology/) > Electronics | by GEORGE CHANIOTAKIS (/member/GEORGE+CHANIOTAKIS/)

Follow

4,604 56 5

Posted Dec. 22, 2015 | (cc) BY-NC-SA



(https://cdn.instructables.com/FDX/8QWT/IIHPDOEW/FDX8QWTIIHPDOEW.LARGE.jpg)




In electronics, a diode is a two-terminal electronic component that conducts primarily in one direction; it has low resistance to the flow of current in one direction, and high resistance in the other. A semiconductor diode, the most common type today, is a crystalline piece of semiconductor material with a p–n junction connected to two electrical terminals. A vacuum tube diode has two electrodes, a plate and a heated cathode. Semiconductor diodes were the first semiconductor electronic devices. The discovery of crystals' rectifying abilities was made by German physicist Ferdinand Braun in 1874. The first semiconductor diodes, called cat's whisker diodes, developed around 1906, were made of mineral crystals such as galena. Today, most diodes are made of silicon, but other semiconductors such as selenium or germanium are sometimes used.

This diode is able to detect RF signals and converts it to DC electricity to power a Led the amazing thing about this is that its completely passive and doesn't require any batteries... Gold Plated Slug 1N23B is Vintage U.S. ARMY Military for General Purpose UHF-MW Silicon Mixer. Primarily used in the Allies’ radar systems during World War II.

Add Tip Ask Question

Step 1:

June 4, 1968 P. T. FARNSWORTH 3,386,883

METHOD AND APPARATUS FOR PRODUCING NUCLEAR-FUSION REACTIONS

Filed May 13, 1966 16 Sheets-Sheet 1

FIG. 1



22
27
27
20
21
23
26
25
24
28
22a
r_o
r_c
r_a
+
-

INVENTOR
PHILO T. FARNSWORTH
BY Wood, Gust & Irish

ATTORNEYS

FIG. 2


22
b
31
(Va+ΔVa)
Va
V
V
a
26
30a
29
21
20
r_o
r_{a_1}
r_{c_1}
r_c
r_a

INVENTOR
PHILO T. FARNSWORTH

BY Hood, Gust & Irish

ATTORNEYS

June 4, 1968 P. T. FARNSWORTH **3,386,883**

METHOD AND APPARATUS FOR PRODUCING NUCLEAR-FUSION REACTIONS

Filed May 13, 1966 16 Sheets-Sheet 3

FIG. 3


22
31
$(V_a+\Delta V_a)$
V_a
V
32
26
30
29
21
20
r_0
r_{c_2}
r_{a_1}
r_{c_1}
r_c
r_a

FIG. 4


34
⊖
⊖
⊖
33
26
20
21
29

INVENTOR
PHILO T. FARNSWORTH

BY Wood, Gust & Irish

ATTORNEYS

June 4, 1968 P. T. FARNSWORTH **3,386,883**

METHOD AND APPARATUS FOR PRODUCING NUCLEAR-FUSION REACTIONS

Filed May 13, 1966 16 Sheets-Sheet 4



FIG. 5a



FIG. 5b

FIG. 10



INVENTOR
PHILO T. FARNSWORTH
BY Hood, Gust & Irish
ATTORNEYS

FIG. 6



6[a]



6[b]



6[c]



INVENTOR
PHILO T. FARNSWORTH
BY Hood, Gust & Irish

ATTORNEYS

June 4, 1968 P. T. FARNSWORTH **3,386,883**

METHOD AND APPARATUS FOR PRODUCING NUCLEAR-FUSION REACTIONS

Filed May 13, 1966 16 Sheets-Sheet 6

FIG. 7



INVENTOR
PHILO T. FARNSWORTH
BY Hood Gust & Irish

ATTORNEYS

June 4, 1968 P. T. FARNSWORTH **3,386,883**

METHOD AND APPARATUS FOR PRODUCING NUCLEAR-FUSION REACTIONS

Filed May 13, 1966 16 Sheets-Sheet 7

FIG. 8



FIG. 9


0-200KV.
VARIABLE
- 46 +
24
43
+ -
25
47
23
42
36
20
ION GUN
45
99
22a
GAS SOURCE
21
26
39
40
22
99
45a
GAS SOURCE
37
37
ION GUN
FILAMENT VOLTAGE
0-1000 VOLTS VARIABLE
100
38
38
44
VACUUM PUMP
r_o
r_c
r_c'
r_a

INVENTOR
PHILO T. FARNSWORTH
BY Wood, Gust & Irish
ATTORNEYS

FIG. 11


71
75
68
78
100
21
22
22
98
99
45
GAS SOURCE
99
20
20
20
69
67
65
70
40
40
66
101
36
21
39
104
37,38
37
26
47a
38
40
39
40
63
64
61
62
60
51
50
59
54
22a
22a
53
58a
52
55
49
56
56
22
22
57
58
108
109

INVENTOR
PHILO T. FARNSWORTH
BY Hood, Gust & Irish
ATTORNEYS.

June 4, 1968 P. T. FARNSWORTH **3,386,883**

METHOD AND APPARATUS FOR PRODUCING NUCLEAR-FUSION REACTIONS

Filed May 13, 1966 16 Sheets-Sheet 9

FIG. 12


74
43
+
−
73
−
46
+
47
77
75
72
Z
72
68
−
25
+
76
71

INVENTOR
PHILO T. FARNSWORTH
BY Hood, Gust & Irish
ATTORNEYS

METHOD AND APPARATUS FOR PRODUCING NUCLEAR-FUSION REACTIONS

Filed May 13, 1966

16 Sheets-Sheet 10

FIG_13


21
100
+
-
90
89
88
93
22,22a
87
20
94
97
96
86
93
84
83
98
82
20
21
79
85
81
80
20

FIG_20


85
81
82
87
87
93
85
86
85
83
87
79

FIG_21


90
88
92
96
22,22a
95
97
94
89
91
98

FIG_22


23
57
56
58a
58
55
56

INVENTOR
PHILO T. FARNSWORTH
BY Hood, Gust & Irish
ATTORNEYS

June 4, 1968 P. T. FARNSWORTH 3,386,883

METHOD AND APPARATUS FOR PRODUCING NUCLEAR-FUSION REACTIONS

Filed May 13, 1966 16 Sheets-Sheet 11

FIG. 14


107
15
15
106
36
104

FIG. 15


104
107
106
105
38
36
37
21

FIG. 16


101
40
36
17
17
102

FIG. 17


40
101
36
102
40
21
103

INVENTOR
PHILO T. FARNSWORTH
BY Hood Gust & Irish
ATTORNEYS

June 4, 1968 **P. T. FARNSWORTH** **3,386,883**

METHOD AND APPARATUS FOR PRODUCING NUCLEAR-FUSION REACTIONS

Filed May 13, 1966 16 Sheets-Sheet 13

FIG. 18a


0-180°
PLANE
N
20
22
22
22
48
45°
90°
47b
48
48
45°
90°
NORTHERN
HEMISPHERE
EQUATORIAL
PLANE
SOUTHERN
HEMISPHERE
22a
22a
S

FIG. 18b


90°
48
48
22
22
90°
45°
22
EQUATORIAL
PLANE
180°
90°
0°
48
48
90°
48
22
270°

FIG. 19


GAS INLET
FILAMENT
TERMINAL
92
91
FILAMENT
TERMINAL
FILAMENT
VOLTAGE
0-1000
VOLTS
VARIABLE
100
22,22a
90
GUN-ANODE
TERMINAL

INVENTOR
PHILO T. FARNSWORTH
BY Wood, Gust & Irish
ATTORNEYS

June 4, 1968 P. T. FARNSWORTH 3,386,883

METHOD AND APPARATUS FOR PRODUCING NUCLEAR-FUSION REACTIONS

Filed May 13, 1966 16 Sheets-Sheet 13


-
+
25
72a
118
113
117
89
22
71a
114
22a
119
120
69a
70
115
116
79
158
99
45
GAS SOURCE
47a
80
103
121
37
26
20
21
112
50a
111
49a
44
VACUUM PUMP
100
110

Fig. 23

INVENTOR.
Philo T. Farnsworth,
BY Hood, Gust & Irish
Attorneys.

June 4, 1968 P. T. FARNSWORTH **3,386,883**

METHOD AND APPARATUS FOR PRODUCING NUCLEAR-FUSION REACTIONS

Filed May 13, 1966 16 Sheets-Sheet 14

Fig.25



138
140
137
135
139
134
133
21
103
136

Fig.29



90
87
161
97
95
94
92
91
98
+
−

Fig.24



121
129
127
130
128
132
126
125
122
154
131
123
−
+
37
124
21

INVENTOR.
Philo T. Farnsworth,
BY Hood, Gust & Irish
Attorneys.

June 4, 1968 P. T. FARNSWORTH 3,386,883

METHOD AND APPARATUS FOR PRODUCING NUCLEAR-FUSION REACTIONS

Filed May 13, 1966 16 Sheets-Sheet 15


+
-
154
20
21
142
141
146
121
155
157
126
144
156
145
-
+
141
146
143
153
151
150
149
148
152
147

Fig. 26

INVENTOR.
Philo T. Farnsworth,
BY Hood, Gust & Irish
Attorneys.

June 4, 1968 P. T. FARNSWORTH **3,386,883**

METHOD AND APPARATUS FOR PRODUCING NUCLEAR-FUSION REACTIONS

Filed May 13, 1966 16 Sheets-Sheet 16



22b
160
22b
165
166
28
28
S
S
167a
167a
164
164
161
167
N
N
159
97
98
89a
162
94
163
+
-
29
29
93
90
87
79
81
82
20
80
121
169
168
21
26
16
164
164
159
167

FIG. 27

FIG. 28

INVENTOR.

Philo. T. Farnsworth,

BY Hood, Gust & Irish

Attorneys.

United States Patent Office

3,386,883
Patented June 4, 1968

3,386,883

METHOD AND APPARATUS FOR PRODUCING NUCLEAR-FUSION REACTIONS

Philo T. Farnsworth, Fort Wayne, Ind., assignor to International Telephone and Telegraph Corporation, a corporation of Delaware

Filed May 13, 1966, Ser. No. 549,849
19 Claims. (Cl. 176—1)

ABSTRACT OF THE DISCLOSURE

A method and apparatus for producing controlled nuclear-fusion reaction by use of self-generated electric fields and inertial ionized-gas containment. The apparatus comprises a spherical anode which concentrically surrounds a cathode. A plurality of ion guns are mounted on the exterior of the anode in spherically spaced and diametrically aligned relationship such that the beam axes intersect at the center of the cathode. Appropriate apertures are provided in the cathode for passage of the ions. Other apertures permit passage of positively charged particles outwardly from the cathode interior, but are biased negatively to prevent the flow of electrons into the interelectrode space.

A voltage is applied between the anode and cathode. Ions from the guns are propelled and focused into the center of the cathode establishing in the cathode interior a series of concentric spherical sheaths of alternating maxima and minima potentials called "virtual electrodes." The ions in the innermost "virtual electrode" have fusion energies, and are contained at a density sufficient to produce a self-sustained fusion reaction.

I. *Introduction*

The present invention relates to a method and apparatus for producing nuclear-fusion reactions, and more particularly to a method and apparatus for producing controlled nuclear-fusion reactions by use of self-generated electric fields and inertial ionized gas containment.

In the well-known fusion reactions, nuclei of two light elements are combined to form a nucleus of a single heavier element, together with a release of the excess binding energy in the form of sub-atomic particles (neutrons and protons). Before the positively charged nuclei can be brought close enough together for fusion to take place, sufficient energy must be supplied to overcome the forces of electrostatic repulsion between them. There are many possible reactions involving the combination of two light nuclei which are accompanied by the release of energy, but hydrogen isotopes (deuterium and tritium) and helium, under the proper circumstances, are considered to be the most likely to produce controllable fusion reactions. Examples of these reactions are:

(1) ${}_1D^2+{}_1D^2\rightarrow{}_2He^3$ (.82 mev.) $+{}_0n^1$ (2.45 mev.)
(2) ${}_1D^2+{}_1D^2\rightarrow{}_1T^3$ (1.01 mev.) $+{}_1p^1$ (3.02 mev.)
(3) ${}_1D^2+{}_1T^3\rightarrow{}_2He^4$ (3.5 mev.) $+{}_0n^1$ (14.1 mev.)
(4) ${}_1D^2+{}_2He^3\rightarrow{}_2He^4$ (3.6 mev.) $+{}_1p^1$ (14.7 mev.)

It has been determined that to produce a "self-sustained fusion reaction" (release of more energy from the reaction than is required to produce it) the density of the fusionable particles must be maintained at a high order. It is generally accepted that if such a density could be so contained, the other problems involved in producing a self-sustained fusion reaction, principally that of raising the particle energy-levels high enough to overcome their repelling forces, could be solved. Most suggestions and proposals for plasma containment employ very high magnetic fields; these include the pinched discharge, the

Stellerator, the magnetic mirror, the Astron, and the like. This invention departs widely from those approaches by utilizing self-generated electric fields for containing the ionized gases. Through the use of such electric fields, many, if not most, of the complex problems inherent in the magnetic-field devices have been overcome.

Methods and apparatus capable of producing such continuous reactions are disclosed and claimed in my application Ser. No. 165,639, filed Jan. 11, 1962, entitled, "Electric Discharge Device for Producing Interactions Between Nuclei," now U.S. Patent No. 3,258,402, issued on June 28, 1966. Generally speaking, one form of the invention of my aforesaid application is of spherical geometry, in which an electron-emissive cathode concentrically surrounds a shell-like anode having an inner concentric cavity or space. The anode is permeable to the flow of atomic particles, while the cathode is not. In operation, an electrical discharge, composed of high-order magnitude electron and ion currents in the space enveloped by the anode, produces a radial potential distribution which is, generally speaking, a minimum adjacent to the center of the anode cavity and a maximum adjacent to the anode wall. Ions created at points intermediate the center and the anode wall fall toward and oscillate through the center at velocities which are dependent upon the operating potentials, the potentials developed within the anodic space and the potentials at which the ions are born. With developed potentials of sufficiently high magnitude, the ions are propelled at nuclear reacting energies, so that ion collisions occur at the center and thus produce nuclear-fusion reactions.

The present invention structurally differs fundamentally therefrom in the respect that the cathode and anode elements are reversed, and the anode therefore surrounds the cathode. The cathode is substantially impervious to the flow of electrons therethrough and is reasonably permeable to the free flow of positively charged particles, while the anode shell is not. An electrical gaseous discharge developed within the device causes the concentration of electrons and ions toward and into the central structureless zone of the volume enclosed by the cathode, thereby producing in said zone concentric, abrupt, shell-like, potential barriers of alternating polarities or virtual cathodes and anodes. High-energy ions within the space of the structure are propelled toward and through these virtual electrodes to the geometric center of the structure, there producing, in concert with the low-energy ions created in that region, an ion concentration of extremely high density. When the space charge in the center fully develops, the potential difference between the innermost virtual cathode and the first adjacent virtual anode reaches a magnitude sufficient to propel ions through the center at fusion-reacting energies. Atomic and sub-atomic products produced by these reactions are available for the production of useful power. The present invention involves novel and improved means and methods for confining the ionized gas particles, regardless of the charge; compressing them into small volumes with high densities; and then maintaining them in a stable condition for a prolonged and continuous period of time.

It is, therefore, an object of the present invention to provide a method and means for compressing and confining an ionized gas discharge by the use of self-generated electric fields.

It is another object of the present invention to provide an electric-field method and means for producing a stable electric discharge.

It is still another object of this invention to provide a method and apparatus for converting the energy released from the nuclear reactions into useful heat energy.

It is another object of this invention to provide a method and apparatus for converting positively-charged particles from the nuclear-fusion reaction directly into electrical power.

It is still another object of this invention to provide a source of electrical power and heat in which the kinetic energy of the products of the nuclear-fusion reactions are converted directly into electrical power with or without accompanying neutrons.

II. *Description of theoretical device*

In the accomplishment of the above and related objects, an electric discharge device has an anode which surrounds a cathode that electrically encloses a structureless space or volume. The cathode is rendered practically impervious to electrons but reasonably pervious to ions. The anode and cathode are uniquely designed and assembled to form an electron-optical system wherein the cathodic space is maintained completely filled with the electrical discharge. Traversing electrons, under the influence of the electron optice, follow radial-like paths through the cathodic space and, as the cathode is quite impervious to electrons, they are thereby kept from being intercepted in appreciable numbers by the surrounding anode. Electron energy spread is thus maintained at minimum values, and there is developed a high-magnitude electron circulatory current which serves to produce the required potential gradient in the cathodic space.

A variety of fusion reactions are possible, with certain of the reactions being useful in directly generating electrical power. The charged particles of these particular fusion reactions are emitted at sufficient kinetic energies to overcome the decelerating field of the anode. This results in the particles, charged positively, performing work against the anode field, and thereby augmenting the energy stored in that field. The remainder of the energy is converted into heat at the anode, but the deposit of the positive charges thereon results in their conversion directly into electrical energy or power. Energy converted into heat also may be utilized in the generation of power.

The above-mentioned and other features and objects of this invention, and the manner of attaining them, will become more apparent and the invention itself will be best understood by reference to the following description of embodiments of this invention taken in conjunction with the accompanying drawings, wherein:

FIG. 1 is a diagrammatic illustration of an embodiment of the present invention used in explaining the theory of operation;

FIGS. 2 and 3 are potential distribution curves used in explaining the operating principles of this invention;

FIG. 4 is a simplified diagram used in explaining the theory of charged particle scattering;

FIGS. *5a, 5b,* 6, *6a, 6b, 6c,* 7 and 8 are graphs used in explaining the principles of this invention;

FIG. 9 is a further diagrammatic illustration of an embodiment of this invention (more elaborate than FIG. 1) used in explaining the theory of operation;

FIG. 10 is a graph of the deuterium-tritium reaction used in explaining the operation of this invention;

FIG. 11 is a partial diametral cross-section of a working embodiment of this invention;

FIG. 12 is an axial section of one part of the terminal and supporting structure for the embodiment of FIG. 11;

FIG. 13 is a fragmentary axial section of one ion gun of FIG. 11;

FIG. 14 is an enlarged fragmentary plan view of a cathode biasing screen assembly of FIG. 11;

FIG. 15 is a cross-section taken along section line **15—15** of FIG. 14;

FIG. 16 is an enlarged fragmentary plan view of an ion aperture assembly of FIG. 11;

FIG. 17 is a cross-section taken along section line **17—17** of FIG. 16;

FIGS. 18*a* and 18*b* are diagrams used in explaining the relative positions of the ion guns and the screen-covered apertures in the cathode;

FIG. 19 is an end view of an ion gun;

FIGS. 20 and 21 are cross-sections taken along section lines 20—20 and 21—21, respectively, of FIG. 13;

FIG. 22 is a cross-section taken along section line **22—22** of FIG. 11;

FIG. 23 is a partial cross-section of another working embodiment of this invention;

FIG. 24 is an enlarged fragmentary cross-section of the biasing screen assembly mounted on the cathode shown in FIG. 23;

FIG. 25 is an enlarged fragmentary cross-section of the ion-aperture assembly mounted on the cathode shown in FIG. 23;

FIG. 26 is an enlarged fragmentary cross-section of the terminal assembly for applying the biasing voltage to the biasing screen assembly of FIGS. 23 and 24;

FIG. 27 is an enlarged, fragmentary sectional view of another embodiment of an ion gun assembly;

FIG. 28 is a cross-section taken substantially along section line **28—28** of FIG. 27; and

FIG. 29 is a cross-section taken substantially along section line **29—29** of FIG. 27.

III. *Simplified explanation of operation*

It has been accepted that fusion reactions, which will yield more energy than that supplied to produce the effect, will occur only in high-density plasmas in which the overall kinetic energies of the ions composing the gas are high enough to overcome their mutual repelling forces. Most approaches proposed or under study to produce these conditions employ powerful external magnets to contain and compress the plasma into a small volume to increase the density and temperature (energy) of the particles therein. Such magnetic fields thus far have been successful in confining the plasma particles in the required high-density configuration for only extremely short (microseconds) fusion reactions. The time required to produce the favorable conditions (interval between pulses) is so great that energy output is extremely small when compared with the energy input.

This invention differs fundamentally from those in that charge-particles are compressed into a suitably dense configuration through the action of an "electrodynamic lens" established by confined bi-polar charges in a volume of free space. Such bi-polar charges are developed into a spherical configuration in such a way as to establish a plurality of concentric spherical potential sheaths radially spaced, these sheaths having large potential differences therebetween. The maxima and minima potential sheaths alternate radially and are characterized, respectively, as virtual anodes and cathodes. A virtual cathode is innermost and substantially coincident with the geometric center.

From this arrangement to virtual anodes and cathodes, a radial potential distribution obtains in a spherical space, with one potential minimum being near the center. Thus positively charged particles in this space fall toward and through the center; hence, in effect they are focused onto the center. The focusing forces may be considered as resulting from bi-polar (electron-ion) charge optics.

Bi-polar charges moving radially within the space produce a radial potential distribution as described above. It is, therefore, convenient to characterize these bi-polar charge optics as "Poisson Optics" inasmuch as the solution of Poisson's differential equation (given later on) for the radial potential distribution resulting from bi-polar charges in a spherical configuration reveals the phenomenon of the aforedescribed virtual anodes and cathodes. The electric field which obtains within this free space occupied by these virtual electrodes I call a "poissor."

The trajectories of the charged particles are determined by the composite field or poissor which is produced by the aggregate of the fields of the oppositely charged particles. When a positively charged particle (ion) of zero velocity falls from a point just inside a virtual anode (which defines a spherical positive-potential boundary), it is accelerated toward the adjacent virtual cathode and, in passing beyond it, decelerates toward a condition of zero velocity at an equipotential boundary of that from which it started, and then repeats this velocity rate of change from zero to maximum, and then again to zero in the opposite direction. Electrons likewise will oscillate through virtual anodes between negative equipotential barriers. Since one polarity of charged particle approaches its maximum velocity while the other polarity approaches its minimum, the two species maintain their separate identities and spaced charges. Hence, it is seen that the particles are trapped inertially between such equipotential boundaries; accordingly, I call my method for containing the nuclear-fusion reacting particles "inertial containment." The ions which are created on the inward sides of the boundaries of the spherical virtual anodes and which oscillate through or near the center of the device produce the required density thereat to satisfy the conditions for a self-sustaining nuclear fusion reaction. Thus, the charged particles are literally compressed into the required density in the central region by the process of inertial containment, and the present device utilizes this process.

Referring to the drawings, and more particularly to FIG. 1, an evacuated spherical electron-tube structure is shown which comprises a spherical, anode shell **20** at radius r_a, enclosing a sperical, cathode shell **21** of radius r_c, and an ion gun **22** which is mounted on the outside of the anode **20** as shown. The anode and cathode electrodes are concentrically arranged as shown. The cathode **21** and its field are substantially impervious to electron flow to the anode **20**, but is pervious to the flow of positively charged particles such as ions. In this theoretical exemplification, the cathode **21** may be considered as an open-mesh electrode formed of metallic screen or the like, which is constructed of a material, the surface of which emits electrons upon bombardment by ions or electrons and preferably is photoelectric in the ultra-violet spectral region. Suitable connections are made to the electrodes, a lead **23** being connected to the anode **20** for applying a positive potential thereto and another lead **24** being connected from the cathode **21** for connection to a negative potential terminal. A power source, such as a battery **25**, delivering a suitably high voltage is connected as shown to the leads **23** and **24**. In the preferred embodiment of this invention, the anode **20** is operated at ground potential.

In one embodiment of this invention, ions of a suitable nuclear-fusion reactive gas are introduced into the space enclosed by the cathode **21**. An electrical discharge composed of high-magnitude electron and ion currents forms in the cathodic volume and develops a difference of potential which is, generally speaking, a minimum near the geometric center **26** and a maximum adjacent to the anode **20**, with one or more potential maxima (virtual anodes) and minima (virtual cathodes) concentrically enclosed within the cathode **21**. Ions created at points adjacent to potential maxima (virtual anodes) fall toward and oscillate through adjacent potential minima (virtual cathodes) with energies equivalent to the potentials at the points where they start their journeys. These ions, falling inwardly toward the center **26** from regions of high potentials, will be propelled at velocities (energies) which are sufficient to overcome the repelling forces of other high-energy ions and also the slower (target) ions born in the region near the center **26** and collide, thus producing nuclear-fusion reactions.

In order to obtain ions with fusion-reacting energies, the sizes of the virtual cathodes and anodes must be maintained such that the boundaries thereof are well defined, and the potential differences therebetween are pronounced. This is achieved by methods which are explained in detail in the written description later following.

IV. *Description of poissor (virtual-electrode system) formation*

With suitable potentials applied to the electrodes, and with the ion gun **22** energized, ions of a fusion reactive gas are directed into the space enclosed by cathode **21**, where they will be accelerated radially inwardly toward the geometric center **26**. Since there is a potential gradient between the anode **20** and cathode **21**, the positively charged ions, as indicated by the numeral **27**, will be accelerated by the cathode **21**. Inasmuch as the latter is substantially ion permeable, each ion **27** will continue its transit and, if the optics are considered to be perfect, it will pass through the center **26** and travel onwardly in a straight line until the repelling field of the anode **20** at about the point **28** is reached. At this point, the direction of travel of the ion will be reversed, and it will repeat the diametric excursion to the opposite side of the device adjacent to the anode **20**, passing through the center **26** enroute.

Because the potential within the cathode is uniform (assuming no other ions or electrons are in existence), ions **27** will experience no velocity-changing force while traveling therethrough. Thus, an ion may be considered as starting its travel at or near a given point on the anode, accelerating toward the cathode, traveling with constant velocity through the cathodic space, and then decelerating from the cathode to the vicinity of the anode where its velocity becomes zero and it reverses its direction of travel. This ion will continue its oscillatory motion until it is lost by one of several competing actions, which will be explained later on. The significance of this single-ion concept is two-fold: firstly, it recognizes that the normal space potential inside cathode **21** is uniform at the value of the cathode, and an ion traveling thereacross does so with uniform velocity; and secondly, that the ion will oscillate within the space enclosed by anode **20** until ultimately collected by the cathode **21**.

Now let it be assumed that two ions leave the anode simultaneously from diametrically oposite points, such as from ion guns **22** and **22***a*. Each of these ions will be propelled radially inwardly toward the exact center **26** of the cathodic space so that they would collide at that point in the absence of any other forces. Inasmuch as each ion is positively charged, it will exert a repelling force upon the other, such that their respective velocities will be progressively decreased until they nearly reach the exact center **26**, where they will have given up all of their energies and stop. Under the repelling influence of their respective fields, they will reverse their direction of travel and be accelerated outwardly. In a practical embodiment, however, the ions will experience a diverting effect and will pass each other at minimum velocity rather than stopping. Upon passing through the cathode **21**, the ions will be decelerated by the anode **20** field until they stop adjacent to the anode **20**, whereupon the cycle is repeated. Even though the unipotential space inside the cathode **21** exerts no force on a single ion passing therethrough, two ions approaching each other along a diametral path experience coulomb repulsion and velocity changes which serve to create a positive electric field in the cathodic space, the maximum effect occurring in the central region where the velocity is the least. This may be properly described as a space-charge effect.

Now assume that a copious quantity of ions are introduced into the space immediately adjacent to the anode **20** from a number of symmetrically disposed ion guns. These ions will converge toward the center **26** at progressively decreasing velocities until they reach a minimum velocity and thereafter diverge outwardly along essentially the same diameters, accelerating until they pass out through the cathode **21**. The ions contribute a positive charge to the cathodic space which increases progressively as the coulomb forces become effective and reach a maximum within center **26**; as the ions leave the center **26**, they absorb energy from that field on their passage to the cathode **21**. Thus, surrounding the cathodic center **26** (and inside the cathode **21**), a virtual anode will be produced which can be made to have a potential which can exceed that potential (V_a) of the anode **20** by a factor ΔV_a equal to the average voltage increase which is required by the ions from the ion guns to penetrate the anode **20** field. The ions, therefore, oscillate back and forth through the permeable cathode **21** until lost by one of several competing actions which will be explained later, since they do not re-enter the anode **20**.

The establishment of the ion space-charge inside the cathode **21** may be better understood by reference to the graph of FIG. 2 wherein the abscissa represents the radius of the device and the ordinate represents the potential distribution therein. The magnitude of the ion space-charge is dependent upon the amount of space-charge current flowing in the cathodic space. For a minute quantity of current, the positive charge contribution is small, and the potential at the center would appear as shown by curve *a*. A larger current will produce a more positive potential distribution such as curve *b*. Greater or lesser currents will change the potential at the center **26** correspondingly.

Since the cathode **21** is not completely permeable to the flow of ions therethrough, ions will impact it and dislodge secondary and Auger neutralization electrons thereby. (During operation of the device, electrons also will be supplied from the photoelectric cathode **21** by ultra-violet radiation from Bremsstrahlung and recombination.) Electrons, to be able to leave the cathode **21**, must be excited to a potential $(V_c+\Delta V_c)$, V_c being the potential of the cathode **21**. The electrons so emitted by cathode **21** will leave with a Fermi-Dirac distribution of velocities and the potential gradient near the cathode **21** thereby becomes more negative by the factor ΔV_c than that of cathode **21**, and the potential curve moves down until it has a minimum at a radius r_{c_1}, close to that of the cathode **21**, at which the potential corresponds to the average velocity of emission. For this condition, most of the electrons are slowed down until they come to rest, thus creating a virtual cathode **29** at a radius r_{c1}, and from which the electrons may flow in either direction, i.e., either return to the cathode **21** or flow into the central cathodic volume.

Some electrons, under the attractive influence of the positive potential gradient (virtual anode) created in the central volume by the ions and the repelling influence of the virtual cathode **29**, will be accelerated toward the center **26** until their mutually repelling coulomb forces predominate. They then will be decelerated, giving up kinetic energy to the field, and ultimately may be scattered through large angles, returning to the virtual cathode **29**, where they will repeat the cycle. Since the electron density is the greatest in the small spherical volume enveloping the center **26**, the negative space-charge contribution by the electrons will be the greatest in that region and a potential minimum or a crater will develop in the center of the positive gradient *b* (FIG. 2) which will increase in depth until a virtual cathode **30***a*, with a potential equal to that of virtual cathode **29**, is created at the center **26**, radius r_0. This action is accompanied by an outward displacement of the peak of the positive potential gradient to a radius r_{a_1}, where a spherical potential sheath or virtual anode **31** is formed.

The description thus far has disregarded the presence of neutral gas molecules within the device. When neutral gas is present, it initially will be distributed equally throughout the volume enclosed by anode **20**. The electrons and ions oscillating within the cathode **21** space will strike the neutral gas molecules, creating additional electrons and ions which, under the influence of the electric fields, will be set into oscillatory motion, the lengths of their respective paths being determined by the potentials at the points within the cathodic space where they were created. For example, suppose an ion is born in the outward (cathode) side of the virtual anode **31** (FIG. 2); it will be propelled through the virtual cathode **29** and impact the cathode **21**, thereby producing additional electrons. The electron which was released during the creation of the ion will pass through the virtual anode **31**, and be brought to rest in the vicinity of the virtual cathode **30***a* where, neglecting any deviation, it will reverse its direction and return to the point where created. Now suppose the ion and electron were created on the inside of virtual anode **31** (FIG. 2). The ion will move inwardly, being accelerated toward and through the virtual cathode **30***a*, and will come to rest at the positive barrier on the opposite side of the center **26**, and then oscillate between those barriers. The electron will be propelled through the virtual anode **31** and will go into oscillation between the virtual cathode **29** and the virtual cathode **30***a*. By far the greatest number of ions (and electrons) will be produced near the virtual cathode **30***a*, because the probability of ionization by electron impact is greater the slower the electron and because the electron density is the greatest in the virtual cathode.

As the process continues, the ion and electron space currents tend to build up a small positive potential maximum within the virtual cathode **30***a* (FIG. 2) by virtue of the ions that are created in that region and which oscillate through it. Thus, a vestigial virtual anode **32** (FIG. 3) is formed in the center **26**, and the virtual cathode **30***a* moves to a new location **30** at radius r_{c_2}. When neutral, gas molecules are present in the virtual cathode, ionization will occur. The electrons so created will be nearly indistinguishable from and react in the same manner as those in the virtual cathode, i.e., they will be accelerated outwardly toward a virtual anode. The associated ions will be born with the very low kinetic energy of the neutral particles and therefore will remain in the vicinity of the virtual cathode, neutralizing some of the space charge. These combined actions of electrons and ions will result in smaller negative space charge which decreases the radius of the virtual cathode. The new radial potential distribution is shown in FIG. 3. It will be noted that an increase in the electron space-charge current within the virtual anode **32** could result in the formation of a new virtual cathode therein. This process of adding virtual electrodes, theoretically, could continue until a point of confusion is reached where they merge and the field collapses. In actual practice, however, the number of virtual electrodes in a poissor may, and will, be controlled. In the practical exemplifications described herein, only two virtual cathodes (**29** and **30**), one virtual anode **31** and the vestigial anode **32** will be assumed to exist.

It must be borne in mind that in an actual operating device neither the ions nor the electrons are traveling precisely radially; moreover, there is a velocity spread within both the ion and electron groups due to interparticle scattering. As a result, the points where ions and electrons reverse their direction of motion do not lie on mathematically thin surfaces; accordingly, the virtual anodes and cathodes have finite radial thicknesses which are called "potential gradient sheaths" or simply "sheaths."

At this point, it will be appreciated that the space charge buildup inside the cathode **21** has resulted in the development of concentric potential gradient sheaths which serve in confining negatively and positively charged particles to movement in paths, almost all of which intersect at the center **26**, while others oscillate along path lengths which are determined by the energy levels at which the charged particles were created. When a high kinetic energy ion (projectile) passes near a low kinetic energy ion (target) in the central volume, scattering occurs. An energy transfer takes place therebetween which sets the target ion into oscillation and tends to trap the projectile. The positively charged particles for fusion reactions thus are compressed into such a densely packed volume concentric with the geometric center **26** that the probability of those particles being fused is high.

The manifestation of a poissor (virtual-electrode system) by radiation of light within spherical geometries similar to the device described above has been observed through viewing ports and studied photographically, on many occasions.

V. *Other atomic processes in the discharge*

In the immediately preceding discussion, the ions and electrons have been considered as moving past each other, interacting only through their respective space charges. There are a number of other atomic processes which can occur, however, and it will be shown in the following that the design of the apparatus can be such as to minimize some of these effects and use others to good advantage.

As has already been explained, the high-energy ions or electrons, in the absence of outside influences, would oscillate radially through the space of the anode **20** or the cathode **21** (FIG. 3). The ion transit time between the limits of its travel, i.e., the time which an ion takes for one traversal of its path, is proportional to the ion path length and inversely proportional to its average velocity. This ion oscillatory action will, in the presence of electrons and neutral gas, continue only until one of four possible actions occurs:

(a) the ion path is altered by the "scattering process";
(b) the ion "captures" an electron from a neutral atom, called charge exchange, or recombines with an electron and becomes a neutral atom;
(c) the ion is fused by a nuclear reaction; or,
(d) the ion is captured by the cathode or the anode wall.

A scattering event is a collision of or near collision of two or more particles in which the energies and momentums of the individual particles are altered, but total energy and momentum are conserved. In an ionized gas, ion-ion scattering and electron-electron deflections from coulomb forces are of primary importance because energy is most readily transferred between particles of similar masses. Electron-ion deflections involve much less energy transfer because of the large mass difference between the two species.

"Scattering" is the total statistical effect of the probability of electrostatic deflection of like particles with boh radius and distance as variables; i.e., the deflecting of particles of like charge by the coulomb repelling forces. Ion scattering takes place mostly in the virtual anodes where the kinetic energies are low and the ion densities are many fold greater than anywhere else along the ions' paths. Scattering in the virtual anodes cannot result in a large energy transfer. When an ion is scattered in a virtual anode and is accelerated toward a virtual cathode, it gains high kinetic energy and its path is essentially radial. (As the ions and electrons are oscillating within a spherical enclosure, their current densities increase radially inwardly as $1/r^2$ where r is the distance from the geometric center **26** to the point where the density is measured.) An ion will be deflected from its path as it approaches another ion if it is unable to approach closely enough (within the radius of fusion, r_f) for the sub-atomic attractive nuclear forces to predominate. This particular distance between two ion (r_f) where scattering is replaced by fusion, can be calculated if the fusion cross-section for the particular ion is known. For example, if we assume that the fusion cross-section (σ_f) for tritium ions with deuterium ions is:

$$5\times10^{-24}\text{ cm.}^2$$

then

$$\pi(r_f)^2=\sigma_f=5\times10^{-24}$$

$$r_f=\sqrt{\frac{5\times10^{-24}}{\pi}}\simeq1.26\times10^{-12}\text{ cm.}\tag{5}$$

If scattering is too great, it will not be possible to maintain the high ion density at the center **26** necessary to assure the required fusion probability. In other words, the effect of scattering is to increase the size of the minute volume of the central vestigial virtual anode **32**. Thus it becomes advantageous to limit the number of ion trips through the center, for a given particle energy, in order to prevent an increase in that volume by scattering.

The deflection angle will depend upon how closely the two ions approach each other, this angle being directly proportional to the density of the target ions bound within the innermost virtual cathode **30** (FIG. 3) and inversely proportional to the square of the energy of the scattered ion. Ions which approach each other at a distance less than r_f will fuse; those that are unable to close within that range will be deflected. The scattering angle will be greater the closer the ions come to each other. The critical angle where fusion occurs, called the "angle of fusion," can be calculated using Rutherford's formula. Neglecting multiple scattering for the tritium-deuterium ions, this angle turns out to be 58°; thus, scattering will take place only when the angles are less than 58°. It can be shown mathematically that the probability of the scattering angle exceeding 8° is only about 10%.

As an ion has a much shorter wavelength than an electron, its atomic dimensions are much smaller. Two important consequences follow:

(a) Diffraction effects will not occur in elastic scattering. Thus, over a major part of angular range, elastic scattering will be the same as that given by the classical theory. (At very small angles, the quantum theory will give better results.)

(b) Elastic scattering will be confined to very small angles. The scattered intensity will decrease with an increase of scattering angle, and the scattering is concentrated to small angles as the incident energy is increased: the total scattering will decrease with increasing energy.

For elastic collisions, the cross-section will be small if:

$$\frac{r}{v}\times de\gg\frac{h}{2\pi}\tag{6}$$

where

de=ionization energy
h=Planck's constant
v=velocity of the ions
r=radius of ion deflection

The greater the value of de, the greater will be the energy at which maximum inelastic cross-section will occur. Because of small values of de, charge-exchange is the most important inelastic collision process.

An ion can be neutralized by an encounter with an electron. This can happen in two different ways: an ion can collide with a neutral atom and rob it of its electron ("charge-exchange"), or the ion may collide with the free electron and recombine to form a neutral atom. The probability of recombination is extremely unlikely compared to charge exchange (see Brown, "Basic Data of Plasma Physics," Wiley, 1959, page 104) and will occur only if the two colliding particles are traveling in the same direction at about the same velocity. Since the charge-exchange cross-section is greater than 10^{-16} cm.^{2} between 1 kev. and 50 kev., charge exchange will occur over a wide range. The gentler the slope of the potential gradient, the longer will be the ion path length within which charge-exchange can occur. The only region in which recombination can occur is close to the virtual cathodes **29** and **30** where the electron velocity is lowest and ion velocity is highest.

When charge-exchange occurs, there is very little energy transfer between the two particles other than the transfer of an electron from one nucleus to the other. The old ion, which becomes a neutral atom, retains almost all of its velocity, and, since it is no longer influenced by the electric field, it simply travels onwardly until it is lost at the tube wall. The newly formed ion has the energy corresponding to the potential at the point in space where it was created. It begins an oscillatory motion of its own through the center **26**, or travels to the cathode **21** with no indication of having been previously deflected. The newly formed ion may be considered to be continuing to increase the average number of trips started by the old ion, but with the disadvantage of having suffered an energy loss. The ion charge-exchange cycle of the inner side of the virtual anode **31** may be repeated several times before the energy loss becomes so great that fusion will not occur.

When recombination occurs, a neutral atom results, which travels outwardly until it is either reionized by another electron or ion or migrates to the tube walls. Recombination results in a loss of energy through radiation as well as a loss of both ions and electrons from the space charge; it is fortunate that the probability of this event occurring is so low and thus represents a negligible energy loss. This condition is achieved by maintaining the paths of the electrons as nearly radial as possible. One means for obtaining this radial motion is to hold the velocity spread of the electrons to a minimum.

Control of charge-exchange by limiting ion trips

Ion scattering will be limited if the number of ion trips through the center of the device can be limited. It will now be shown that this number of ion trips hence charge-exchange can be controlled.

The extent of charge-exchange may be calculated from the relationship which expresses that probability per trip P_c as follows:

$$P_c = \rho_n \times \sigma_c \times L \tag{7}$$

in which:

L=the length of one ion path in centimeters;

ρ_n=the neutral gas density in particles per cubic centimeter; and

σ_c=the charge-exchange cross-section in cm.^{2}.

The highest possible value for P_c is unity (1), since this means that the event of charge-exchange occurs. The obvious minimum value of P_c is zero (0). From the formula, if the calculated value for P_c is 10^{-6}, this means that an ion makes on an average 10^6 oscillatory trips before the energy loss of the ion by charge-exchange becomes so great that it will not be able to reach a fusion radius. Values for charge-exchange cross-section may be obtained from the curve of Jackson & Schriff in "Physical Review," vol. 89, No. 2, page 359, 1953.

In the case at hand, it is desirable to limit the number of ion trips to less than one million during the occurrence of from four (4) to six (6) charge-exchange cycles. If an average of four (4) captures per 10^6 is assumed, then:

$$P_c = \frac{4}{10^6} = 4 \times 10^{-6}$$

Now assuming as an example that the path length is 0.135 centimeter and the value of σ_c is 10^{-16} cm.^{2}, then the value of the neutral gas density ρ_n may be derived from Equation 7 as follows:

$$\rho_n = \frac{P_c}{\sigma_c \times L} = \frac{4 \times 10^{-6}}{10^{-16} \times 0.135} = \frac{1}{250{,}000 \times 10^{-16} \times 0.135}$$
$$\simeq 3 \times 10^{11} \text{ particles/cm.}^3$$

Thus, it is readily observed that the control of charge-exchange, which in turn governs to a major extent the shape of the potential distribution, is achieved by adjustment of gas density as charge-exchange cross-section is inversely proportional to gas density. Thus it is desirable to work at the lowest practicable gas density.

Maintaining radial thinness of virtual cathode by controlling electron scattering

During space charge build-up, electrons initially have energies for oscillating within the confines of the cathode **21** along radial paths which pass through the center **26**. These electrons suffer the same type of deflective forces as approaching ions, such that meeting electrons scatter. Electrons approaching each other at or near the center **26** deflect along different paths which are also radial. However, if the electrons should meet at points other than the center **26**, they will deflect along new paths which may become either more radial or less radial. As the electron transits continue, the non-radial electrons can and do meet with other electrons, producing further non-radial and radial electrons such that eventually, after a relatively large number of electron transits, electron movements inside the cathode **21** tend to become, in some measure, non-radial. FIG. 4 shows a simplified example of this deflection for two different locations of an electron (**33** and **34**) with respect to an electron traveling along a non-radial path. In FIG. 4, the electron **33** is deflected along the new (and radial) path, while electron **34** is deflected along a more non-radial path. If the deflection angle is large, some of the electrons could, unless otherwise prevented, acquire sufficient energy to penetrate the virtual cathode **29** and the cathode **21** and be absorbed by the anode **20** or to enter the cathode **21** and thus be removed from the field; others will accumulate orbital momentum.

The required condition for producing sharply resolved virtual anodes and cathodes is initially achieved by controlling the number of electron trips within the cathodic space. This condition may be represented by the equation:

$$I_e = 2\overline{N}_e \times i_{e2c} \tag{8}$$

where

I_e=the circulatory electron current through the virtual anode **31** inside the cathode **21** (FIG. 3),

i_{e2c}=the electron current emitted from the inner surface of the cathode **21** (FIG. 3),

$\overline{N}_e$=the average number of electron trips ($2\overline{N}_e$ is the average number of round trips).

If a particle's path is through the center, the distance from its starting point to the point where it commences its return journey is the equivalent of two trips or one "round trip." Where the path of the particle is away from the center, the distance from its point of origin to its reversal point is one trip. It is desired that the factor $\overline{N}_e$ fall somewhere between the figures of 10^3 and 10^4. If $\overline{N}_e$ becomes too large, the virtual cathodes and anodes will not form properly. Thus, by preventing the number of electron trips from becoming excessive, the non-radial component of the electron space-current can be held to a minimum.

The number of electron trips may be made relatively small by maintaining a high electron current density within the cathodic space. Since the maximum value of the circulatory electron current I_e is limited by space-charge saturation, which is a function of the cathode voltage gradient, I_e (Equation 8) may be made to approach its saturation limit by increasing the cathode current i_{e2c}, thereby confining a very large number of electrons within the cathode **21** which make but few round trips. Accordingly, few orbital electrons will be formed. In a practical device, the electron current can be increased by the use of electron emitters within the cathode **21**.

The paths of the orbiting electrons are elliptical, and each such electron is therefore subjected to a precessional force which causes the electron's path to sweep a spherical surface inside the cathode. These electrons contribute to the electron circulatory current and also to the fields of the virtual cathodes. Because of their elliptical paths, with non-radial velocity components, orbital electrons cannot approach the virtual cathodes as closely as radial electrons. Thus, their maximum space charge contributions occur farther from the virtual cathodes than those from radials, and the virtual cathodes will tend to be displaced inwardly. Excessively large numbers of orbital electrons (greater than 10% of the electron circulatory current) therefore are undesirable as they prevent the maintaining of sharply defined virtual electrodes. In actual practice, the orbital electrons appear not to exceed that limit.

Orbital electrons, in addition to their contribution to the electron circulatory current, further reduce the probability of recombination. In the fusion-reaction volume enclosed by the virtual cathode **30**, this becomes extremely important as it greatly reduces the loss of fusion-reactive ions from that region. In the region outside of the virtual cathode **30**, the orbital electrons, as previously shown, not only contribute to the field which maintains the virtual cathode **29**, but also displaces that cathode inwardly toward the virtual anode **31** and thereby reduce greatly, any cusps or singularities in the electric field pattern of the virtual cathode **29** produced by the anode **20** field penetrating through the apertures in the cathode **21**.

VI. Particle flow

Further consideration of the process involved in the present invention requires investigation of the space-charge optics and the particle flow. The laws by which charged particles move from an emitter to a collector without regard to the direction of voltage between electrodes have been described by Langmuir and Blodgett ("Physical Review," vol. 24, No. 1, pp. 49–59, June 1924). That particular derivation was made to calculate the currents limited by space-charge between concentric spheres (either electron or ion but not in the presence of each other). For this invention, however, bi-polar charges exist within the spherical electrodes, and the Poisson's equation becomes:

$$\frac{d^2V}{dr^2}+\frac{2}{r}\left(\frac{dV}{dr}\right)=4\pi(\rho_e-\rho_i) \tag{10}$$

where V is the potential at any radius r, and ρ_e and ρ_i are the electron and ion volumetric space-charge densities.

Equation 10, together with the energy equations

$$\tfrac{1}{2}M_e v_e^2=eV, \text{ and } \tfrac{1}{2}M_i v_i^2=e(V_b-V)$$

where M is the mass of the charged particle, e the charge of the electron, v the velocity of the charged particle at any potential V, and b is the point of ion entry (which in this invention is considered to be the anode since most of the charged particles are assumed to be formed at or very near to their respective electrodes); and the density, charge and velocity relationships

$$J_e=\rho_e v_e, \text{ and } J_i=\rho_i v_i$$

(where J is the charge of the space-charge) are sufficient to determine all the relations involved in the electron and ion space-charge flows; i.e., all motions are assumed to be radial in this basic determination.

By following the general approach employed by Langmuir in a later paper, "The Interaction of Electron and Positive Ion Space Charges in Cathode Sheaths," ("Physical Review," vol. 33, page 954, June 1929), Equation 10 reduces to

$$3\mu\frac{d^2\mu}{d\gamma^2}+\left(\frac{d\mu}{d\gamma}\right)^2+3\mu\left(\frac{d\mu}{d\gamma}\right)=1-\gamma\left[\frac{\mu^{4/3}}{\mu_b{}^{4/3}-\mu^{4/3}}\right]^{1/2} \tag{11}$$

where

$$\lambda=\frac{I_i}{I_e}\sqrt{\frac{M_i}{M_e}} \tag{12}$$

I_i=the circulatory ion current;

I_e=the circulatory electron current in the presence of ions;

$\gamma=ln(r/r_0)$, (r_0 being the radius of the emitting surface); and

$\mu=f(\gamma)$, (corresponding to the α of Langmuir and Blodgett and becomes α when λ equals zero). In this ideal treatment μ_b is taken at the anode and is thus a constant.

A quantity similar to λ was used by Langmuir in his June 1929 referenced paper which he called α. He showed that the potential gradient at the surface of the anode was proportional to $(1-\alpha)^{1/2}$ and so became imaginary if $\alpha>1$. In other words, if α were to become greater than unity, ions would be withdrawn faster than injected. While those calculations referred to a plane-parallel discharge, the same limitation has been found to apply to the spherical concentric shells if the area used in evaluating the current density J from the total current I is taken to be the area of a surface four-fifths of the distance from the emitter to the collector. (See I. Langmuir and K. T. Compton, "Review of Modern Physics," Vol. III, No. 2, April 1931) where one is confronted with radial flow, however, λ may be larger than unity and still satisfy the boundary conditions.

Once I_e is selected, then λ and I_i are uniquely determined; the ratio of the radii is likewise uniquely determined.

It will be noted, from Equation 12, that when one is concerned with a fixed ratio of the radii of the virtual electrodes, λ has but one value and therefore becomes a constant. When λ is zero (no ion current present), Langmuir and Blodgett's α may be substituted for μ in Equation 11 and reduces to:

$$3\alpha\frac{d^2\alpha}{d\gamma^2}+\left(\frac{d\alpha}{d\gamma}\right)^2+3\alpha\left(\frac{d\alpha}{d\gamma}\right)=1 \tag{13}$$

which, as should be, is the Langmuir and Blodgett equation.

Spangenberg (book "Vacuum Tubes," 1st ed. 1948, § 8.4, p. 181) submits that the equation for the electron space-charge flow of current for concentric spherical electrodes in the absence of ions is:

$$I_0=\frac{29.34\times10^{-6}\times V^{3/2}}{\alpha^2} \tag{14}$$

where V is the potential difference between the spherical electrodes and α is a function of $\lambda=ln\ (r/r_0)$ given by the Maclaurin series:

$$\alpha=\gamma-0.3\gamma^2+0.075\gamma^3-0.0013\gamma^4+\ \ldots \tag{14a}$$

The values for α are valid whether the cathode is external or internal and can be found in tabular form in Table II of the referenced Langmuir and Blodgett paper. Two functions designated as α^2 and $(-\alpha)^2$ are listed. The first applies to the case where the voltage V is evaluated at a point P outside the electron emitting electrode; the second where P is inside that source.

Germane to this invention, Langmuir's logic may be extended into the determination of electron and ion circulatory currents in the present of each other. As was the case for the Langmuir and Blodgett Equation 13, Equation 11 probably cannot be integrated directly, but a solution was obtained in the same manner as used by Langmuir and Blodgett. The electron circulatory current in the presence of ions took the form:

$$I_e=\frac{29.34\times10^{-6}\times V^{3/2}}{\mu^2} \tag{15}$$

The values for μ being obtained by expanding the Taylor's series:

(15a)

$$\mu=f(\gamma)=\gamma_0+\frac{\gamma+\gamma_0}{1}f'(\gamma_0)+\frac{(\gamma-\gamma_0)^2}{2}f''(\gamma_0)+\frac{(\gamma+\gamma_0)^3}{3}f'''(\gamma_0)-\ \ldots$$

Equation 15a is expanded near zero to avoid infinite terms in the higher derivatives.

It is apparent from Equation 15 that the electron circulatory current I_e is independent of the actual sizes of the spheres since the radii enter only as a ratio.

Knowing the value of λ and the circulatory electron current from Equation 12, circulatory ion current I_i can be determined. Thus:

$$I_i = I_e \times \lambda \times \sqrt{\frac{M_e}{M_i}} = \frac{29.34 \times 10^{-6} \times V^{3/2}}{(-\mu)^2 \sqrt{\frac{M_e}{M_i}}} \lambda \tag{16}$$

It was at this point in the solution of the Poisson equation for bi-polar charges in a spherical geometry that I was led to conclude, and which was later verified by experimentation, that a phenomenon of alternating virtual cathodes and anodes could be made to exist in the volume enclosed by the inner hollow electrode of a fusor. Furthermore, to satisfy the Poisson's equation, λ would have to be greater than unity when a virtual cathode enclosed a virtual anode, such as shown by r_{c_1} and r_{a_1} (FIG 3). A "singularity" or mathematical discontinuity appears to exist at the virtual anode. Likewise, such a "singularity" appears to exist at the virtual cathode r_{c_2}, enclosed by the virtual anode r_{a_1}. In this type of system "a space-charge saturated current cannot be produced on the side of an emitting surface which radiates outwardly." The radial potential distribution for the fusor of this invention is shown in FIG. 5*a*. That such "singularities" do exist in the fusor of this invention can be likened to the case of a charge uniformly distributed over an imaginary spherical shell.

If one assumes that a positive charge Q is uniformly distributed over an imaginary spherical shell of radius r_1, Gauss' law for electrostatic charges may be applied to calculate the field intensity (E) and the potential (V) at any radius r inside and outside of the radius r_{a_1} (FIG. 5). Additionally, the surface charge density ρ_s may be calculated as a function of the radial distance r. (See Sec. 1–20, Chapter 1, Part I, of "Electromagnetics" by John D. Kraus, McGraw–Hill Electrical and Electronics Engineering Series, 1st Ed., 1953.) It is found that the field intensity E is zero (in the absence of electric charges) for any radius inside the shell and the absolute potential at a radius outside the shell is given by

$$V = \frac{Q}{4\pi r \xi_0} \tag{17}$$

where Q is the positive charge in coulombs; and ξ_0 is the permittivity of air in farads per meter. Since the field intensity is zero inside the shell, the potential within the shell will be constant. The surface density ρ_s is zero everywhere except at the radius of the shell where it has the value

$$\rho_s = \frac{Q}{4\pi r_1^2} \tag{18}$$

The variation of E, V and ρ_s is shown by FIG. 6, curves (*a*), (*b*) and (*c*).

The similarity of the radial potential gradients of FIGS. 5*a* and 6*b* is marked. Inasmuch as the gradient (dV/dr) at r_1 (FIG. 6) and r_{a_1} (FIG. 5*a*) is zero, and a condition for space-charge saturation at r_{a_1} is defined by an infinitely thin spherical shell at that radius, it is reasonable to assume that Equations 17 and 18 can be applied to the treatment of a radial potential distribution such as shown by FIG. 5*a*, even though that field is not produced by bound charges. It is helpful to identify the referenced emitting surfaces by subscripts (cathode *c* and numeral or anode *a* and numeral) which produced the circulating current (electron or ion) being calculated.

Since the circulatory currents through all virtual electrodes have constant values for all radii between the limits of travel thereof, it becomes fundamental that:

$$\frac{I_e}{I_0} = k^2 \tag{19}$$

where k^2 is a constant independent of the voltages at any radii. Using Equations 14 and 15, Equation 19 may be written in the form:

$$k^2 = \frac{\dfrac{29.34 \times 10^{-6} \times V_a^{3/2}}{-\mu_c^2}}{\dfrac{29.34 \times 10^{-6} \times V_a^{3/2}}{-\alpha_c^2}} = \frac{-\alpha_c^2}{-\mu_c^2} \tag{20}$$

when the real cathode *c* is the emitting surface.

Langmuir's Equation 12, et seq., in his paper of June, 1929, teaches a method for computing values of I_e/I_0 for plane-parallel electrodes for any values of his α (which corresponds to my λ for the spherical-electrode geometry).

When the ratio of the radii r_{a1}/r_{c1} (FIG. 3) approaches unity, the spherical geometry approaches the plane-parallel geometry so closely that the potential gradient at r_{c1} becomes zero and I_e/I_0 (and k^2) takes the same value as Langmuir's for α equal to unity, which is 1.8605. This means that the electron circulatory current in the presence of unlimited ions will be 1.8605 times that for the same applied potential in the absence of ions.

When λ becomes zero, i.e., no ion current present, I_e/I_0 again is the same as Langmuir's α and I_e/I_0 (and k^2) which is unity.

Thus, one observes that with the limits for Langmuir's α and my λ being identical, it holds that α and λ will be the same for intermediate values. Accordingly, I have computed and plotted in FIG. 7 the values of I_e/I_0 for various values of λ so as to permit obtaining any intermediate values readily.

Experimentally, one may apply a desired potential between the real anode **20** at radius r_a and the real cathode **21** at radius r_c (FIG. 3) and measure the current I_0 therebetween. Ions from the ion sources are then injected and measurements of the resulting currents I_e recorded. The ratios of I_e/I_0 may then be calculated and the corresponding values for λ obtained from FIG. 7.

Thus, having values for I_e/I_0 (or k^2), I_e and λ, one may compute values for the corresponding I_i $(-\alpha)^2$, and $(-\mu)^2$, keeping in mind that the virtual electrodes cannot emit outwardly and only the negative values for α and μ are valid. With these data, one has the means for obtaining the radial potential distribution.

The radius of the virtual anode r_{a_1} (FIG. 5*a*) is generally known quite accurately from experimental data of a variety of kinds and largely by heuristic reasoning based on those data. The actual value of r_{a_1} (and the resulting ratio r_{c_1}/r_{a_1}) depends upon the total energy losses, which will be taken up later, required to maintain the desired poissor and the magnitude of the high-energy ion current which flows through (or into) the real cathode **21** (radius r_c). The approximate values for r_{a_1} have been determined visually for experimental fusors.

In the design of a working embodiment of a fusor, it is essential that the volume enclosed by the innermost virtual cathode, such as **30** at radius r_{c_2} (FIG. 5*a*) be adequate to confine a sufficient total number of fusion particles (at a volumetric density of unity fusion probability) to assure the generation of a useful amount of power. It has been found that if the ratio of the radii of the adjacent pair of virtual electrodes is much greater than 3, the inner virtual cathode may not form; if the ratio of radii is too small, the circulatory currents required to maintain the poissor become excessively large.

In an actual working embodiment of a fusor, the radii of the virtual anodes and cathodes can be computed, as well as the values of the currents and the radial potential distribution outside of the virtual cathode **30** at radius r_{c_2}. The radial potential within the aforementioned virtual cathode has not been computed because as the radii of the balance of the virtual electrode system become much samller, errors in ion and electron optics begin to reveal themselves to the extent that it is not known whether or not the system continues to repeat itself. Since fusion does occur in the small volume in the fusor's center, the space-charge conditions prevailing therein have therefore been determined by logic and heuristic reasoning.

In FIG. 3 is illustrated diagrammatically one embodiment of this invention consisting of an anode **20**, a cathode **21** and an ion gun **22**. Enclosed within the cathode **21** is shown a poissor with a virtual cathode **29** at a radius of r_{c1}, a virtual anode **31** at a radius of r_{a1}, a virtual cathode **30** at a radius of r_{c2}, and a vestigial virtual anode **32** at a radius of r_o. To understand the operation of the fusor, it is important to distinguish between the currents which flow through the apertures of the real cathode **21**, referred to herein as "mesh currents" (i_m), and the current which flows into the real cathode **21**, termed "cathode current" (i_c).

The ion "mesh current" (i_{im}) is produced by the ions:

(a) injected into the cathode **21** space from the ion guns;
(b) released by the anode **20** under bombardment by electrons and neutral gas molecules;
(c) created in the volume between the anode **20** and the cathode **21**; and,
(d) created by the ionization process within the volume r_{a1} to r_{c1}.

Those ions which originate on the anode **20** will be collected by the cathode **21**, or returned to the anode **20** after but one round trip; those few ions created on the inward side of the virtual anode **31** ($r \leqq r_{a1}$) which have sufficient energy to penetrate therethrough will be collected by the anode **20** or the cathode **21** after only a few round trips; the other ions will oscillate from the virtual anode **31** through the cathode **21** apertures until collected by the cathode **21**. The potential of the virtual anode **31** will build up to that of the anode **20**.

The electron "mesh current" (i_{em}) which initially may be quite large and is extremely useful in the formation of the virtual electrode system, will become so small in operation as to be negligible. It is made up of those electrons emitted by the inner surface of the real cathode **21** and which flow through the cathode **21** apertures to the anode **20**.

The total mesh current through the cathode **21** apertures, therefore, is the algebraic sum of the ion mesh current and the electron mesh current. Thus,

$$i_m=i_{im}+i_{em} \tag{21}$$

The net cathode **21** current i_c is the algebraic sum of the ion current into, and the electron currents into and out of it. Ions flowing into and electrons flowing out of the cathode **21** as usual are positive currents to the cathode **21**. Thus,

$$i_c=i_{ic}+i_{e2c}-i_{e1c}+i_{ec}' \tag{22}$$

where i_{ic} is the ion current into the cathode; i_{e1c} is the electron current into the inside of the cathode; i_{e2c} is the electron current out of the inner surface of the cathode; and i_{ec}' is the electron current from the outside surface of the cathode to the anode.

The space current i_s into or out of the volume enclosed by the cathode **21** is the sum of the mesh current and the cathode **21** current, so

$$i_s=i_m+i_c \tag{23}$$

The general condition for an equilibrium potential field occurs when i_s becomes zero, as no charges are then being added or removed from the space. Accordingly,

$$i_m=i_c=0 \tag{24}$$

and when i_c is zero, the power consumed by the device is a minimum.

It is the ion mesh current i_{im} into the central cathode **21** volume which maintains the density of the virtual anode **31**, and which causes any free charges therein to be oscillated radially. As the inward flow of ions continues, the positive potential at the virtual anode **31** increases until all the inward flow of ions is cancelled by the outward flow to the cathode **21**. The net ion mesh current then becomes zero. Neglecting the minute electron mesh current i_{em}, when all the electrons that are emitted from the inside of the cathode **21**, as well as all of the ions and electrons generated within the cathode **21** volume, return to the cathode **21**, it is apparent from Equation 22 that only the electron current, i_{ec}', remains to flow to the anode **20**. Thus, for i_c to become zero, i_{ec}' must likewise be brought to zero. Such an equilibrium potential field can be obtained when there are sufficient ions reaching the anode **20** to compensate for i_{ec}'.

Those ions from the virtual anode **31** which have energies equivalent to or greater than V_a will reach the anode **20** and remove an equal or greater number of electrons therefrom. With a sufficient number of such ions reaching the anode **20**, the component of cathode **20** current, i_{ec}' can be reduced to zero.

In the disclosure thus far, a space-charge saturation of the cathode volume has been assumed. The ions which are created near the virtual anode **31** ($r \leqq r_{a1}$), where the ionization process is a maximum, have energies approaching eV_{a1}. They traverse the inner virtual cathode **30** and the vestigial virtual anode **32** at fusion-reacting energies; this is an essential operating condition. The bulk of the ions which make up the ion mesh current i_{im} are created in the volume outside the virtual anode **31** ($r \geqq r_{a1}$) and, like those ions from the ion guns **22** and the anode **20**, are ultimately collected by the cathode **21**; thus, if space-charge saturation could exist in this region, it would produce such an extremely large energy loss that nuclear-fusion reactions could not obtain. Fortunately, as previously shown, ion space-charge saturation cannot exist in this region, and operating conditions are maintained such that the ion circulatory current is just adequate to assure a virtual anode **31** of the desired size. Thus, the ideal radial potential distribution for the device of this invention (sometimes referred to herein as a "fusor") is as shown in FIG. *5a* where the poissor is maintained by ion space-charge saturation in the volume $r \leqq r_{a1}$ and a non-space charge (dissymmetrical) field exists in the cathode **21** volume where r is greater than r_{a1}. λ, therefore, has the value which gives ion space-charge saturation only in the region adjacent to the radiating surface of the virtual anode **31** where the potential gradient is zero; electron space-charge saturation obtains in the region just inside of r_{c2}.

Within a virtual anode **31** (FIG. *5a*), each positive charge must be matched by an electron. Most of the flux lines from the ions at a radius $r \leqq r_{a1}$ terminate in the virtual cathode **30**; where $r \geqq r_{a1}$, most of the flux lines terminate in the virtual cathode **29**. All the charged particles in the cathode **21** volume are free to move and are in oscillation. The virtual anode **31** at r_{a1}, the locus of maximum ion density, has the potential practically equivalent to V_a, and very few ions are formed inside that virtual anode with energies greater than eV_{a1}. Thus, to maintain the potential V_{a1}, it is only necessary that there be an equal number of flux lines from the inner of r_{a1} to r_{c2} as there are outward to r_{c1} (FIG. *5a*). Ions with lesser energies than eV_{a1} will reach their reversal loci at radii greater than r_{a1} when $r \geqq r_{a1}$ or less than r_{a1} when $r \leqq r_{a1}$ and those ion densities will be less than at r_{a1}. If a few ions are generated inside of r_{a1} with energies greater than eV_{a1}, they will pass through the virtual anode **31** and fall to the cathode **21**, and in some instances to the anode **20**; they do not contribute to the ion circulatory current. The virtual anode **31** thus acts as an effective hi-pass ion filter for ions with energies greater than eV_{a1}. Inside the virtual anode **31** where $r \leqq r_{a1}$, the ions travel slowly for a relatively large portion of their radial paths as they approach their respective reversal loci; the opposite is true outside the radius r_{a1} where the ions are decelerated rapidly as they approach r_{a1}, giving up their energies within a very short distance from r_{a1}.

The radial potential V_r is a function of the radius r and the time t; i.e., $V_r=f(r,t)$. The buildup of the poissor inside the radius r_{a_1}, together with the creation of the asymmetrical field outward from r_{a_1}, is shown diagrammatically by FIG. 8. The anode **20** and the cathode **21** initially are at ground potential as shown. If a negative potential of V'_c (curve *a*, FIG. 8) of approximately −30 kv. is applied to cathode **21**, and ions from the ion guns are injected into the cathode **21** volume concurrently, they begin to charge that volume positively. This charge will increase until the potential at some internal radius r_{a_1} is sufficient to return the ions to the cathode **21** at the same rate at which they enter the cathodic **21** volume. This equilibrium may be expressed by the relation

$$i_{\mathrm{im}}=i_{\mathrm{ic}} \tag{25}$$

As soon as the potential inside the cathode **21** becomes positive, electrons emitted from the inner surface of cathode **21** will be accelerated toward and oscillate through the central volume and quickly establish virtual cathodes at r_{c_1} and r_{c_2}. With the virtual cathodes formed, the position of the virtual anode between them is determined. The equilibrium radius and the potential of the virtual anode at r_{a_1} requires a somewhat longer buildup time than the formation of the virtual cathodes at r_{c_1} and r_{c_2} because of the longer ion transit time.

When the negative potential on the cathode **21** is abruptly increased from V_c' to $V'_c{}'$ to $V'_c{}''$, similar sequences of events occur. Each of the subsequent equilibrium radial potential gradients is shown by curves *b* and *c* of FIG. 8.

To determine the position of the virtual electrodes, it is only necessary to establish the radial density distribution of electrons and ions. The radial potential distribution already has been so calculated. The virtual anode locus will lie close to the surface where the ion density is the greatest. The virtual cathodes will lie at the termini of the electron paths where the electron densities are the highest.

A practical embodiment of this invention by which the aforesaid conditions for a self-sustaining nuclear-fusion reaction can be produced is shown diagrammatically by FIG. 9. A spherical anode **20** of radius r_a encloses dual concentric cathodes **21** and **36** of radii r_c and r_c', respectively, and ion guns **22** and **22***a* mounted on the outside of anode **20**. The concentric cathodes **21** and **36**, which are constructed of an electron-emitting material such as stainless steel, molybdenum or the like, and which have an openness of about 70% by virtue of spherically spaced, registered apertures **37** and **38**, are supported within the anode **20** by suitable insulators (not shown). The concentricity of the cathodes **21** and **36** is maintained by suitable insulators therebetween (not shown). Attached to the outer cathode **36** on the axis passing through the ion gun **22** is a conical sleeve **40** through which the intense pencil-like ion beam is focused. Suitable connections are made between the unidirectional power supply **25** and the electrodes through leads **23**, **24**, and **42**. The anode **20** is maintained at or near ground potential as shown, while negative potentials are applied to the cathodes **21** and **36** from a supply **43**, with the outer being more negative than the inner.

In operation, most of the ions from the ion guns **22** and **22***a* are utilized to establish the initial virtual anode in the central volume of cathode **21** as previously described. Electrons from cathode **21** are prevented from reaching the anode **20** by the negatively biased outer cathode **36**. The early removal of ions from the non-space-charge saturated field is greatly enhanced by the second cathode **36**, and only those positive charges with energies greater than V_a have any likelihood of avoiding capture on their first outward pass from the virtual anode **31** (FIG. 5*a*). Ions captured by the outer cathode **36** (FIG. 9), will create electrons therefrom which either will enter the cathodic space or be returned by the outermost virtual cathode.

VII. *Losses*

In order to form and sustain a radial-potential distribution such as is shown in FIG. 5*a*, it is first necessary to compensate for all losses. For a typical small fusor, these losses, which represent about 10% of the total power created, in their order of importance and magnitude are:

(1) Heat loss—7%
(2) Charge interchange—2%
(3) Power required to create electrons—⅔ of 1%
(4) Bremsstrahlung—⅓ of 1%

Heat loss.—In the center of an inner virtual cathode in a poissor, the ions from the inner side of the adjacent virtual anode are traversing the center from all directions. As they pass near other ions, they will experience some deflection which will result in small deviations from radial paths and thus they will appear to be in random motion. This is the equivalent of a very high apparent temperature, about 1.6 ×10⁹ °K. for 100 kev. or about 11,600 °K./c.v. (Maxwell-Boltzman constant). This apparent temperature reduces to about 2×10^6 degrees K. in a distance of a few millimeters from the center. Any neutral atom which passes through this central region will be heated to an extremely high temperature. It will experience a cryogenic pumping action that will expel it to one of the real electrodes where, upon impact, it will give up its kinetic energy (heat), penetrate the surface to a depth determined by its kinetic energy, then diffuse out in a random direction following the cosine law. There is very little likelihood of its again reaching the center as it will remain in the vicinity of the electrode until ionization takes place.

It becomes very serious when too many high-energy neutral atoms are intercepted by the cathode as the cooling thereof is most difficult. On the other hand, cooling of the anode is relatively easy. The cooling of the cathode may be accomplished by conduction through its electrical connections to the power supply. The size of the cathode does affect the cooling problem, as increasing the size reduces the heating per unit area by the ratio of $1/r^2$ since the circulating currents are independent of the radii of the spheres.

Rutherford's scattering equation shows how the neutron count can be made to increase with an increase in applied voltage, for: the current rises by the three-halves power; and the particle density may be increased as it is proportional to four times the energy (or voltage) squared. Accordingly, the heat loss will decrease with an increase in voltage as there will be less scattering. For example, refer to FIG. 10, which shows a typical neutron cross-section curve for an equal mixture of deuterium and tritium. The operating points *a* and *b* are for the same fusion cross-section (σ_f), but from the point of view of the heat losses, *b* provides for more efficient performance, for:

$$\frac{N_{\frac{\theta}{2}}}{N_o}=\frac{\pi\rho_e{}^4}{4w^2}\cot\theta \tag{26}$$

where

$$N_{\frac{\theta}{2}}$$

is the number of ions deflected by half angles; N_o is the total number of ions; and W is the energy ($mv.^2=2W$); ($(mv.^2)^2=4W^2$) which shows that the lower the voltage the greater the losses.

Charge interchange.—Ions travel relatively slowly within the radial thickness adjacent to the virtual anode due to the repelling forces of their like charges. Therefore, there is a fairly high probability that a charge interchange with a neutral atom may occur. This loss is discussed in my Patent No. 3,258,402, previously mentioned. This loss becomes sizeable if there are too many gas molecules present. The gas density (pressure) must be kept as low as is possible to maintain a high fusion probability. This affects the fusor's design characteristics. In practice, the fusor is operated at a neutral gas density of 3.535×10^{13} molecules or less, such that

ρ_n is the normal gas density of 2.687×10^{19} molecules/cc. at normal temperature (20° C.) and pressure (760 mm. of Hg); and

ρ_i the operating gas density, in ions per cc., is

$$\frac{2.687\times10^{19}}{760\times10^{-3}}\times10^{-6}=3.535\times10^{13}\text{ ions/cc.}$$

at a working pressure of one micron (10^{-3} mm. Hg).

As the power level of a fusor is increased, more ion current will be required from the ion guns, which in turn will increase the radius of the virtual anode **31** (FIG. *5a*). This will mean a larger volume which, for ion space-charge saturation, will result in an increase of the total number of the ions contained therein. The greater power input (ions) will increase the power loss, thus again increasing the radius of the virtual anode until equilibrium is reached where the power input equals the power dissipated.

Bremsstrahlung.—When high-energy electrons are deflected on their passage through the virtual anode **31**, they radiate at right angles to their directions of motion. As the electrons have momentum which must be conserved, there will occur an equal and opposite reaction when an electron changes its direction of travel. Since these reactions take place after the electron changes its direction, they are non-radial. These non-radial electrons broaden the virtual cathode **30** with a movement toward the center **26**, and thus increase the electron temperatures. The so-called "radiation dampening" effect of the excess ions (positive nuclei) in the virtual anode tends to reduce the Bremsstrahlung losses to less than 1% of the power available in the virtual anode. With the value of the ion density in the virtual anode, the electron scattering can be computed by the well-known Rutherford formula for scattering.

VIII. *Fusion reactions*

The fusor, as shown diagrammatically in FIG. 9, is initially evacuated to a pressure of from 10^{-9} to 10^{-10} millimeters of mercury by means of a vacuum pump **44**, the anode **20** being the hermetically sealed envelope. Potentials are applied to the various electrodes as already explained and a fusion-reactive fuel, in the form of gas, is introduced into the ion guns **22**, **22*a*** from sources **45** and **45*a*** at a pressure of from 10^{-6} to 10^{-4} millimeters of mercury. This fuel gas is ionized by the guns **22**, **22*a*** and formed into ion beams directed diametrically toward center **26**. A poissor forms, as previously explained.

High energy ions oscillate through the region of the center **26** along diametral paths, terminating adjacent to the virtual anode **31** (FIG. *5a*). Other lower energy ions follow shorter diametral paths within the virtual anode **31** through the same region, thereby contributing to the density of ionic particles in the center. With the virtual anode **31** potential high enough (100 kv.), collisions of the high energy ions with others in the center **26** region will produce nuclear-fusion reactions.

There are a number of nuclear-fusion reactions which are possible. Fusion reactions of an exothermic nature will be specifically considered as one type of reaction which this invention seeks to attain. Power production by such reactions is theoretically proportional to both the amount of energy released per reaction and the number of reactions taking place per unit time. The number of reactions per unit time is obtained from the product of the nuclear cross-section, which expresses the probability for a specific nuclear reaction to occur, the number of ions in the center **26** region, and the number of projectile particles passing through this region from the anode **20** and the virtual anode **31** (FIG. *5a*) per unit time. The nuclear cross-section, or the probability that a nuclear reaction will occur, is a function of the velocity or energy of the interacting particles, which in this device is a function of the potential difference between the anode **20**, the virtual anode **31** and the center **26** (FIG. 3). From the above, it is clear that good power-producing reactions require a large nuclear cross-section and also a large amount of input energy.

One reaction which theoretically is outstanding in meeting the above requirement is the tritium reaction with deuterium. The nuclear equation for this process is:

(3) ${}_1D^2+{}_1T^3\rightarrow{}_2He^4$ (3.5 mev.)$+{}_0n^1$ (14.1 mev.)

This states that a triton plus a deuteron plus the sum of their kinetic energies results in a nuclear reaction whose products are helium 4, a neutron, and the sum of the excess binding energy and the kinetic energy possessed by the original triton and deuteron. The reaction energy released is 17.6 million electron volts (mev.) for the sample above. This value is large compared with the values for other possible reactions, which in most cases yield 3 or 4 mev. The nuclear cross-section for the reaction shown in Equation 3 peaks at a value of about 5×10^{-24} cm.^{2} for projectile energies of 100 kiloelectron volts (kev.). This cross-section value is about 10^2 times larger than that for most competing reactions when compared at the same projectile energies.

Additional possible reactions are the following:

(1) ${}_1D^2+{}_1D^2\rightarrow{}_2He^3$ (.82 mev.)$+{}_0n^1$ (2.45 mev.)

(2) ${}_1D^2+{}_1D^2\rightarrow{}_1T^3$ (1.01 mev.)$+{}_1p^1$ (3.02 mev.)

(4) ${}_1D^2+{}_2He^3\rightarrow{}_2He^4$ (3.6 mev.)$+{}_1p^1$ (14.7 mev.)

Reactions 1 and 2 have a lower value of released energy and a lower 100 kev. cross-section value than Reaction 3. Reaction 4 has about the same energy value but a lower 100 kev. cross-section value.

IX. *Fusion products in the discharge*

As already explained, when an external voltage is applied between the anode **20** and the cathode **21**, **36** (FIG. 9), a system of virtual anodes and cathodes (poissor) is formed within the cathodic space. The radial potential distribution of the poissor was shown in FIG. *5a*. It is within the minute volume enclosed by the virtual cathode **30**, where the ion density is the greatest and the energies (velocities) of the projectile ions a maximum, that the probability of fusion is the highest.

It was shown by Equations 1, 2, 3 and 4 that, using only six deuterons, it is possible to trigger four different nuclear-fusion reactions, and these reactions result in the creation of five new kinds of particles having a total energy of 43.2 million electron volts (mev.). Four of these five particles (${}_1p^1$, ${}_1T^3$, ${}_2He^3$ and ${}_2He^4$) are positively charged, and carry 26.65 mev.; the fifth is a neutral particle, the neutron, and the two produced by the two reactions carry 16.55 mev. There are two important aspects of this energy distribution between the charged and uncharged particles. Firstly, the neutrons will escape from the reacting system and dissipate their energy elsewhere as heat, because being uncharged, they easily pass through material walls. Only the charged particles will be retained within the reacting region and be available to compensate for energy losses (radiation, recombination, etc.) and to sustain the nuclear-fusion reactions. Secondly, it is only the energy of the charged particles, which represents 64% of the energy released by the four reactions, that is available to be converted directly into electrical power. It should be noted that only those ions which are created by the fusion reaction will have sufficient energy to produce electrical energy.

All of the particles formed by the nuclear-fusion reaction are ejected radially outward from the reaction volume with the high energies shown by Equations 1 through 4. These energies (velocities) are more than adequate to propel them through the virtual anode **31** (FIG. 5*a*). Under the influence of the real cathode **21**, **36** (FIG. 9), they will be accelerated on their outward journey until passing through the cathode apertures **37**, **38**, where they will be decelerated by the anodic field and either brought to rest short of the anode **20** or impact the anode. If particles do not reach the anode **20**, they will then reverse their direction of travel and go into oscillation through the center. Those which do strike the anode **20** will dissipate their remaining energies as heat and at the same time deposit their charges on the anode. A few particles may strike the cathode and be captured, with an accompanying release of secondary electrons.

With deuterium only in the fusor, for two D—D reactions (Equations 2 and 3) will take place at essentially equal rates. The positively charged products of these reactions which go into oscillation increase the ion circulatory current, thus increasing the ion density in the reaction space and hence the probability of fusion. The oscillating reactive particles ($_1T^3$ and $_2He^3$) may fuse with deuterons to produce the reactions shown by Equations 1 and 4, or may experience scattering, capture or recombination with electrons and become neutral atoms. The non-fusionable particles ($_1p^1$ and $_2He^4$) contribute to the fusion process only by the creation of fusion-reactive ions through the capture of electrons from fuel-gas atoms and by their contribution to the space-charge; ultimately, they will become neutral gas atoms. The neutral gas atoms will drift toward the electrode walls, where eventually they will be scavenged from the reaction system by the vacuum pump 44 (FIG. 9).

It has been stated that some of the charged particles will reach the real anode **20** when ejected by the nuclear-fusion reactions. When this occurs, the particles remove enough electrons from the anode **20** to neutralize their positive charges and form gas atoms. This is the equivalent of producing a current which flows from the anode **20** to the battery **25** (FIG. 9) (power supply). In other words, the charged particles have been coverted directly into electrical energy. This is one of the unique features of this invention.

Insertion of a suitable resistor **46** (FIG. 9) in series with the power lead **24** becomes a means for coupling the converted electrical power to an external load. A switch **47** is used to connect selectively this resistor **46** into the series arrangement.

It will be seen from Equations 1 through 4 that as many positive charges enter the fusion region as are removed therefrom. In other words, nuclear charges are conserved. What the fusion reactions do accomplish is the formation of new particles with the release of the excess binding energy of the original ions and, as the original energy must be conserved, the excess is applied to the new particles. Accordingly, the new particles leave the reaction volume at extremely high velocities. The replacement ions which enter the reaction volume do so at the comparatively low velocities of the order of 100 to 200 kev. Thus, there is an extremely short period when the potential in the center is less than prior to the fusion reaction which, in effect, tends momentarily to increase the negative potential of the virtual cathode **30** as well as decrease the virtual anode **31**, and there is an associated increase in the electron current. This effect produces an increase in the radii of the virtual electrodes until the original potential of the vestigial anode **32** (FIG. 5*a*) can be restored. Thus, there is a periodic expanding and contracting of the poissor volume by the very high frequency oscillation of the inertially contained particles.

When the fusion reaction commences, there will be more positive charges leaving the center than flowing in and this condition will continue until steady state is reached. This would tend to develop what might be termed a "potential well" (more negative potential) at the virtual cathode **30**. Such a condition could not exist, as current would then flow from the real cathode **21**, **36** (FIG. 10) to the virtual cathode **30**. Accordingly, the virtual cathode **30** must be returned to the real cathode potential within an extremely short period of time. This is accomplished by an equivalent increase in the potential of the virtual anode **31**. The loss of positively charged particles from the center produces a positive bias on the virtual cathode **30** which is equivalent to an increase in the potential of the virtual anode **31**. As these increases are cumulative until the steady state condition is produced, it is seen that the virtual anode **31** (FIG. 5*a*) reaches the potential of the real anode **20**.

The positively charged particles formed by the fusion reaction perform work against the field of the virtual anode **31** as they pass through it. In so doing, their velocities are reduced somewhat, thus increasing the field and contributing to the potential of the virtual anode. They are then accelerated by the cathode, regaining energy.

It is the potential of the virtual cathode **30** (FIG. 3) which contributes to the energy of the positively charged particles which oscillate through the center **26**. As the energies of the reacting particles increase, within the resonance limits of the nuclear-fusion cross-section, the probability of fusion increases. Electrons which are created within the virtual anode **31** are ejected radially outwardly with sufficient energy to overcome the repelling field of the real cathode.

If one were to lose control of the input density of the fuel-gas atoms, it might appear that the process of building up the potential of the virtual anode **31** could continue unabated and might well result in a catastrophic accident. Such is not the case, however, as there are "built-in" safety processes which act to prevent such a build-up. The principal control is the cross-section resonance phenomenon which occurs in nuclear reactions. The cross-section curves for D—D (total), D—T and D—HE^3 reactions, such as contained in "Physical Review," vol. 88, p. 468, 1952, by Connor, Bonner and Smith, and also "Physical Review," vol. 88, p. 473, 1952, by the same authors, show that the D—T curve exhibits a maximum at an energy of 110 kilo-electron volts (kev.), where it falls off sharply with increasing deuteron energy. In the same energy range, the D—He^3 cross-sections are appreciably less than the D—D (total) and the D—T values, but the curve is rising rapidly with increasing deuteron energy and it crosses the D—D (total) curve at 120 kev.; it approaches the D—T curve at 500 kev., its peak, and then falls off rapidly. For example, in the range of deuteron energies from 120 to 200 kev., the D—T cross-sections decrease 1 barn (10^{-24} cm.^{2}) while the D—D (total) and the D—He^3 cross-sections increase only about 0.5 barn, an overall decrease of approximately 1 barn. After the D—He^3 cross-sections pass their maximum at 500 kev., the decrease in the overall cross-sections is much more pronounced. Thus, it is apparent that the build-up in the potential of the virtual anode will be checked at deuteron energies greater than about 150 to 200 kev.

Another built-in safety process which assists in preventing a "run-away" by the so-called "potential well" is the widening of the negative potential sheath (virtual cathode **30**) (FIG. 5*a*), as the radius is changed by the oscillating particles, which produces a decrease in the fusion cross-sections.

The conversion of the positively charged particles into electrical energy at the anode has been touched upon briefly. This phase will now be covered in some detail. In order to prevent the over-heating of the anode, it is highly desirable that most of the particle energy be given up to the decelerating virtual and real anode fields. The particles would reach the anode **20** with very much less than their original energies and thus dissipate less heat to it with a significant increase in the overall efficiency. The ideal situation would permit the charges to reach the anode **20** (FIG. 9) with little or no remaining energy, deposit their charges and drift away as neutral gas atoms. Obviously, with such a wide range of energies, 0.82 to

14.7 mev., this condition cannot be achieved. Therefore, one may envision two different operating situations; namely, (a) be satisfied with the maximum electrical conversion that can be obtained with the minimum heating of the anode **20**, or, (b) operate the fusor as a heat machine to convert heat and charged particles into the maximum amount of electric power.

In the first situation, it becomes necessary to restrict, as nearly as possible, the fusion reactions to those of Equations 2 and 3, where the energies range from 0.8 to 3.02 mev., and to operate the anode at a potential which will produce a deceleration of the 0.8 mev. particles such that they arrive at the anode **20** with just sufficient energy to deposit their charges. The 3.02 mev. particles under this condition will impact the anode **20** and convert its remaining energy into heat. Inasmuch as approximately 50% of the D—D reactions will follow the proton branch, it is not possible to eliminate that higher energy particle. The reactions of Equations 1 and 4 may be reduced appreciably by operating the fusor at a lower than normal gas density, thereby removing the neutral helium-three and tritium atoms by the use of a large volume vacuum pump **44** before they have an opportunity to fuse.

In direct contrast, if the device is to be operated as a heat generator, the D—T and D—He^3 reactions must be encouraged. Since the contribution of the D—T and D—He^3 reactions could be quite significant in the direct conversion to electricity, it might prove advantageous in some applications to produce tritium by bombarding lithium-six with the neutrons:

$$(27)\qquad {}_3Li^6+{}_0n^1\rightarrow{}_2He^4+{}_1T^3+4.6\text{ mev.}$$

and then utilize the tritium as a fuel gas.

If enough positively charged particles can be made to reach the anode **20** to reverse the current flow from the battery **25**, it then becomes possible to remove the applied anode (cathode) voltage **25** while continuing the nuclear-fusion reactions. If I and V_a are the measured current and anode voltage before fusion, then after fusion commences the input power in watts will be

$$(28)\qquad W=V_a\times\left[I-\langle F\rangle e(A-B)\right]$$

where $\langle F\rangle$ is the fusion expectancy; e is the electric charge; A is the interception factor of the positively charged particles by the anode; and B is the interception factor of the positively charged particles by the cathode. Since the cathode **21**, **36** is almost pervious to positively charged particles, A will be very much greater than B and when the value of

$$\left[-\langle F\rangle e(A-B)\right]$$

becomes greater than $I(V_a)$, the fusor will become truly self-sustaining. This condition will be reached without the aid of an external load. To remove electrical energy in excess of that required to drive the fusor, it only becomes necessary to add an external load **46** such as shown in FIG. 9.

Working embodiment

A working embodiment of this invention as shown in FIG. 9 is illustrated in substantial detail in FIGS. 11 through 22. In these figures, like numerals indicate like parts. The anode **20** is of spherical construction, being fabricated of two hemispherical shells of stainless steel hermetically sealed together at the equators by means of suitable annular sealing flanges **47a**. Concentrically positioned inside the anode **20** are the two cathode shells **36** and **21**, respectively, which are also assembled of hemispherical shells of stainless steel. The means for supporting these electrodes concentrically will be described in detail hereinafter.

Eight ion guns **22**, **22a** are mounted on the exterior of the anode **20** in spherically spaced and diametrically aligned relationship, these guns all having beam axes which intersect at the center **26** of the fusor. The precise location of these ion guns **22**, **22a** is explained in connection with the spherical diagrams of FIGS. 18*a* and 18*b* which show the angular relationship therebetween. Each of the ion guns is indicated by a circle with a center dot indicating the spot at which the gun axis intersects a spherical surface defined by the anode **20**. FIG. 18*a* illustrates a spherical surface corresponding to the anode and cathode shells with the plane of the drawing being the same as the cross-sectional plane of FIG. 11. This latter plane includes the north and south poles of the sphere. The line **47b** indicates the equatorial plane at right angles to the plane of the drawing. In FIG. 11, this equatorial plane would pass midway between the annular flanges **47a**. The guns **22** and **22a** are located in the planes spaced 45° from the equatorial plane **47b** as shown, these planes passing through the tube center **26** and being rotated about the equatorial diameter which is perpendicular to the plane of the drawing. As shown in FIG. 18*b*, which is a right angle projection of the spherical surface of FIG. 18*a*, there are four such guns **22** spaced 90° apart on the spherical surface and on the same meridian. In terms of angular displacement, these guns are indicated as lying on the 0°, 90°, 180° and 270° lines. Within each plane containing guns, each gun center is at the intersection of a radius 45° above the equator and the spherical surface, certain of the radii lying in the plane of FIG. 18*a*.

Four ion guns **22** are so located in the upper or northern hemisphere of the sphere while four other guns **22a** are located allochirally in the southern hemisphere.

The apertures **37** and **38** in the cathode shells **21** and **36**, respectively, are in twelve registered pairs, each pair **37** and **38** being diagrammatically indicated by an X mark which is assigned numeral **48** in FIGS. 18*a* and 18*b*. The locations of the ion guns and the apertures **48** are indicated as being on the same spherical surface for showing the angular relation therebetween. There are four screen aperture pairs **48** on the equator as shown in FIG. 18*b* at the 0°, 90°, 180° and 270° lines. Planes intersecting the north and south poles which are spaced from each other by 90° contain the remaining aperture pairs **48**, these planes being spaced 45° from the 0°–180° plane which includes the north and south poles also. In these individual 90° planes, on a radius at an angle of 35°16′ with respect to the equatorial plane **47b**, lie the remaining aperture pairs **48**. The spherical surface containing the aperture pairs **48** may be regarded as that of one of the cathode shells **21** and **36**.

With the equators of the cathode and anode shells lying in the same equatorial plane, the aperture pairs **48** are thus spherically offset in a regular angular pattern from the ion guns **22** and **22a**.

The anode **20** shell, as well as the cathode shells **21** and **36**, are supported in position by a tubular mounting assembly indicated generally by the numeral **49**. This mounting assembly includes a stainless steel pipe section **50** perimetrically welded at one end to an opening **51** in the anode shell **20**. Coaxially and hermetically secured to the opposite end of the tube **50** is a larger diameter supporting tube or pipe section **52**. Inside this larger tube **52** is a smaller diameter sleeve **53** having a sliding fit therewith, the upper end portion of sleeve **53** being secured to the radial flange **54** which joins the two pipe sections **50** and **52**.

At the bottom end of the sleeve **53** is coaxially secured a mounting ring **55** from which depends four metal posts **56** spaced 90° apart around the axis of the pipe section **52**. A metal disc **57** is coaxially secured to the bottom ends of the posts **56** by means of suitable screws **58**, this disc **57** having secured to the central portion thereof a ceramic post **58a**. This post **58a** is coaxially positioned inside the pipe section **52** as well as the smaller pipe section 50 by means of the mounting sleeve, rings and posts just described.

Secured to the upper end of the post 58*a* and coaxially extending thereabove is a metal post 59 having threadedly connected thereto a disc-like mounting stud 60 which is welded into an opening 61 in the outer cathode shell 36. Abutting against the flat surface of this stud 60 is a ceramic or the like spacer 62 having a boss 63 intimately fitting into a locating aperture 64 in the inner cathode shell 21. The spacer 62 is sandwiched between the two shells 21 and 36, thereby determining the spacing therebetween.

The post 59 is of such length with respect to the pipe section 50, for example, as to position the two cathode shells 21 and 36 concentrically inside the anode shell 20. This post 59 may be regarded as coinciding with the south poles of the cathode and anode shells.

At the north poles of these shells is located further supporting structure as well as a terminal assembly for connecting the operating voltages to the electrodes. This assembly includes an annular spacer 65 of suitable insulating material, such as boron nitride, positioned between the two shells 21 and 36 so as to determine the spacing therebetween. This spacing is the same as that between the south poles. Coaxially secured inside this spacer 65 is a conductive terminal button 66 which is intimately conductively fitted into a companion aperture in the shell 21. This aperture coincides with the north pole of the shell.

Telescoped over an upwardly projecting portion 67 of the spacer 65 is an elongated tubular element or conductor 68 which intimately fits into and makes conductive contact with an aperture 69 in the outer shell 36.

This conductor 68 passes diametrically outwardly through the relatively large insulating aperture 70 in the anode 20 in spaced relation therewith, this spacing being large enough to provide insulation at the high voltage at which the fusor is operated. A conductive tubular assembly 71 is rigidly and hermetically sealed to the exterior of the anode 20 in registry with the aperture 70 and extends coaxially outwardly with respect to the conductor 68. At the upper end of this assembly 71 is secured a relatively long, cylindrically shaped insulator 72 (FIG. 12) which has secured to the upper end thereof a conductive terminal assembly 73. This terminal assembly 73 is provided with a suitable connection terminal 74 by means of which cathode bias from the battery 43 may be connected to a wire 75 which extends coaxially through the conductor 68 and connects to the terminal button 66. This tubular assembly 71, 72 and 73 which coaxially surrounds the conductor 68 is hermetically sealed such that the space between the conductor 68 and the assembly 71, 72 and 73 may be evacuated and held at the same pressure as the interior of the anode 20.

Inasmuch as high operating potentials prevail between the conductor 68 and the outer tubular assembly 71, 72 and 73, suitable corona shields 76, 77 and 78, of annular configuration, are used for the purpose of preventing corona discharge. Other configurations for the terminal and supporting assembly may be used without departing from the spirit and scope of this invention, the requirement for such an assembly being that it provide the necessary physical support for the fusor anode and cathode elements and also be capable of supplying the anode and cathode elements with the operating voltages without producing corona discharges or field emission.

All of the ion guns 22 and 22*a* are identically constructed such that a description of one will suffice for all. For this purpose, reference is made to FIGS. 11, 13, 19, 20 and 21. Each ion gun includes a conductive housing or sleeve 79 of stainless steel or the like which is perimetrically sealed to an opening 80 in the anode shell 20. The sleeve 79 is positioned such that its axis coincides with a diameter of the anode 20. Coaxially secured internally to the sleeve 79 and against the anode 20 is an aperture plate 81 having a beam-defining aperture 82. Coaxially positioned inside the sleeve 79 in radially spaced and insulated relation therewith is an anode sleeve 83 having a frusto-conically shaped bore 84, the smaller diameter end of this bore being positioned as shown. Three arcuately shaped and circumferentially spaced insulators 85 surround the anode 83 in spaced relation therewith. For securing these insulators 85 to the anode 83, a thin metal ribbon 86 fits into a shallow circumferentially groove and binds the three insulators 85 against the anode 83.

Axial positional support for the anode 83 is provided by means of three ceramic, axially extending posts 87 which are fastened to the outer surface of the anode 83 at points spaced circumferentially equally part. One such post 87 is shown in FIG. 13. Considering this latter figure along with FIGS. 20 and 21, these three posts 87 are secured to a metallic mounting ring 88 which in turn is secured at its outer periphery to a cap assembly indicated by the numeral 89. This cap assembly 89 is composed of suitably machined metal parts formed to a substantially cylindrical shape of somewhat larger diameter than the sleeve 79, this cap assembly 89 being hermetically sealed to the sleeve 79.

As shown more clearly in FIGS. 19 and 21, three power supply terminals 90, 91 and 92 are mounted in the cap assembly 89 and are spaced circumferentially apart 120°. The terminal 90 has a wire conductor 93 internally thereof which passes coaxially through one of the supporting posts 87 and connects to the anode 83. The terminals 91 and 92 have suitably strong, bar-like conductors 94 and 95 which project into the central portion of the gun and pass through a block 96 of insulation for maintaining the spacing therebetween. At the innermost ends of these conductors 94 and 95 is connected a thermionic filament 97, this filament being in the form of a circular loop of wire located coaxially with respect to the axis of the ion gun. As shown in FIG. 11, this filament 97 is situated to the rear of the anode 83.

A pipe fitting 98 is also secured to the cap assembly 89 midway between the two filament terminals 91 and 92 and communicates with the inside of the ion gun as shown. By means of this pipe connection 98, fusion-reactive gas may be admitted to the interior of the ion guns from a suitable source 45 (FIG. 9) by the adjustment of series-connected hand valves 99.

The anode 83 is maintained insulated from the surrounding sleeve 79 such that a power supply 100 may be connected between this anode 83 and the sleeve 79 as well as the anode 20. In FIGS. 11 and 13, such a power supply 100 is indicated as being connected with the positive electrode to the terminal 90 and the negative electrode to ground and the housing 79 of the ion gun. This power supply 100 in an operating embodiment of this invention is designed to supply a voltage which is variable between the limits of 0 and 1,000. A suitable voltage connected between the two terminals 91 and 92 (FIG. 21) serves to energize the filament 97.

Each ion gun 22 in operation generates and emits a beam of ions which is directed toward the fusor center 26. In order to approach this center 26, the beam must penetrate the cathode structure 36, 21, and for this purpose a suitable aperture assembly is provided therein. This assembly is indicated in enlarged detail in FIGS. 16 and 17 and is shown in proper coaxial relationship with respect to the ion guns in FIG. 11. Each aperture assembly includes an annular insert 101 having smoothly radiused corners, which tightly conductively fits into a companion aperture 102 in the shell 36. The shell 21 is provided with an aperture 103 of the same diameter as aperture 102 in precise radial registry therewith.

The beam emitted from the respective ion gun 22 passes through the annulus 101 and the aperture 103. Each aperture 38 in the cathode shell 36 is covered with a biasing screen indicated by the numeral 104 (FIGS. 14 and

15), this biasing screen **104** being secured in position by means of a first mounting ring **107** secured to the outside of the shell **36** in registry with the opening **38** and another ring **106** which clamps the screen **104** to the ring **105**. The aperture **37** in the shell **21** is of a size equal to that of the aperture **38**. The two rings **105** and **106** are firmly, conductively secured to the shell **36** by means of a series of circumferentially spaced screws **107**.

Except where otherwise stated, the structure of FIG. 11 is fabricated of metal and primarily of stainless steel. The cathode shell **21** should be of a material which is photoelectric, and two suitable materials having the necessary properties are stainless steel and molybdenum. Other material obviously may be used without departing from the spirit and scope of this invention.

Inasmuch as the dimensions of the structure of FIG. 11 are relatively small in comparison with the operating voltages which are used, it is of course necessary to take the usual precautions in connection with preventing field emission and corona discharge. Suitable corona shields in various places are used as explained in some detail hereinabove, and all sharp edges, corners, points and the like, from which field emission could occur, are avoided.

The ion guns **22** and **22***a* are disposed in pairs which are diametrically opposite each other. Additionally, the axes of these opposite pairs are set to be coincident such that the ion beams emitted thereby will occupy essentially the same pencil-like space. This space passes through the fusor center **26**.

The operation of the device of FIG. 11 is essentially as has already been described hereinbefore in connection with FIG. 9. To start with, all operating voltages are turned "Off" and a suitable vacuum pump **44** is connected to the interior of the anode shell **20**. Referring to FIG. 11, such a vacuum pump is connected to an outlet port **108** in the cap **109** which seals the end of pipe section **52**. Thus, gas inside the anode **20** as well as the cathode shells **21** and **36** may be evacuated therefrom, through the pipe sections **50** and **52**, through webs in the disc **57** and out of the port **108**.

The pump **44** is allowed to operate for a sufficient period of time and the fusor is otherwise outgassed so as to remove contaminates which could interfere with operation.

After outgassing and evacuating the fusor to a pressure of from 10^{-9} to 10^{-10} millimeters of mercury, a suitable fusion-reactive gas, such as deuterium, from gas sources **45** and **45***a* (FIGS. 9 and 11), is admitted to the ion guns **22** and **22***a* by adjustment of the valves **99**. For this purpose, these valves **99** are opened just sufficiently to admit small quantities of gas which will raise the pressure to from 10^{-6} to 10^{-4} millimeters of mercury. However, just prior to admitting this gas to the ion guns, operating voltages are applied to the fusor as previously explained. In this connection, in order to have complete control of the fusor operation, it is desirable that all voltages be applied progressively starting from zero voltage. Initially, the voltage is applied to the terminals **91** and **92** for heating the filaments **97** of all of the ion guns **22** and **22***a*. Next, the voltages of ion gun power supplies **100** are increased progressively starting with zero voltage until a sufficiently high difference of potential is applied between the anodes **83** and the respective filaments **97** so as to ionize the fusion reactive gas that has been admitted and to form ion beams. Next, the power supply **25** is steadily increased in voltage until fusion reactions are noted. The detection of neutron counts by usual methods can serve as such an indication. The power supplies **100** are adjusted until a satisfactory degree of ionization as well as suitable intense and compact ion beams are obtained which are directed toward the fusor center **26**. Instrumental in the formation and acceleration of these ion beams is, of course, the potential applied to the anode **20** and the cathode **21, 36**.

The vacuum pump **44** connected to the port **108** may be kept operating continuously so as to maintain the neutral gas pressure within the fusor to suitably low levels, and, additionally, the gas valves **99** may be opened slightly or may be opened and closed intermittently for the purpose of supplying necessary quantities of fuel gas to the fusor in order to obtain the reactions desired. By adjusting the high voltage supply **25**, the reaction rate can be changed. Similarly, adjustment of the ion gun anode voltage can affect the reaction rate. Increasing and reducing, selectively, the quantity of neutral gas admitted to the fusor also affects the reaction rate. Therefore, desired reaction rates may be controlled by adjustment of the various circuit and system parameters. A gas pressure of about 10^{-5} mm. Hg continuously maintained has been found suitable for producing fusion reactions.

As shown in FIG. 12, the switch **47** which is connected in series with the high voltage supply **25** is closed, and the neutron-producing reactions just described are obtained. If it is desired to obtain an electrical output from the fusor, it is only necessary to open the switch **47** to place the resistor **46** in series with the high voltage supply. As the reaction rate increases within the fusor and reaches a suitably high value, a reverse current is developed in the circuit of the anode **20** in the direction of the arrow Z adjacent to the resistor **46**. This results in the development of a voltaged drop across the resistor **46**. This reverse current Z will develop when the voltage generated on the anode **20** exceeds that of the supply **25**. Once this self-sustaining operation is achieved by the generation of this anode voltage, the high voltage supply **25** may be taken out of the circuit by first disconnecting the battery and then providing a conductive or essentially short circuit in place of the supply **25**. However, such a circuit change is not necessary if the supply **25** is adapted to conduct current in the reverse direction.

In order to form the poissor in the center of the cathode **21, 36**, it is, as previously explained, necessary to have both ions and electrons. These ions are supplied primarily by the ion guns **22** and **22***a*. The electrons are in part provided by photoemission from the internal surface of the cathode shell **21**. The ions from the ion guns **22** and **22***a* establish the initial virtual anode as previously explained in the central volume of the cathode shell **21**. The poissor thereupon forms, as previously explained. Electron flow from the inside of the cathode shell **21** to the anode **20** is inhibited by reason of the fact that the cathode shell **36** is biased negatively with respect to the shell **21**. This bias is supplied by the power supply **43** and is adjusted to a value at which the external anode **20** current is reduced to a desired minimum. The screens **104** over the openings **38** in the outer cathode shell **36** provide the desired equal potential surface which is more negative than the potential on the cathode shell **21**. This inhibits the escape of electrons from the inside of the shell **21**, thereby reducing losses due to the interception of such electrons by the anode **20**. Also, the screens **104** prevent the positive field from the anode **20** from entering the apertures **37** of the cathode shell **21** and upsetting the spherical configuration of the equal potential surface therein, as previously explained.

The various aperture pairs **37** and **38** are arranged in diametric opposition for radial ion traversal. A cathode shell **21** and **36** construction of about 70% openness provides adequate ion permeability.

Alternative working embodiment

In FIGS. 22 through 26 is illustrated an alternative working embodiment wherein like numerals indicate like parts. Basically, the difference between this embodiment and the one just described and shown in FIG. 11 resides in the use of a single cathode shell assembly **21** instead of the double-shell arrangement **21** and **36** of FIG. 11. The construction of the fusor of FIG. 23 to the extent that it differs from the arrangement of FIG. 11 will be described in detail in the following.

The cathode shell **21** of FIG. 23 is mounted in concentric relation with respect to the anode **20** by means of the pedestal assembly **49*a*** which corresponds to the assembly **49** of the fusor of FIG. 11. This assembly **49*a*** includes a stainless steel or the like supporting tube **50*a*** secured at one end to the anode **20** as shown. An apertured disc **110** is perimetrically fastened inside the tube **50*a*** in the position shown and has secured thereto a ceramic post **111** which projects coaxially through the tube **50*a*** to a position just inside the anode **20**. The opposite end of the ceramic post **111** is secured to a mounting plate **112** suitably rigidly secured to the cathode shell **21**. All the parts just described are sufficiently strong and rigid to position securely the cathode **21** with respect to the anode **20**.

The left-hand end of the tube **50*a*** of FIG. 23 is adapted to have a vacuum pump connected thereto the same as has already been described in connection with the preceding embodiments.

The high voltage terminal assembly **72*a*** corresponds to the assembly **72** of FIG. 11. This assembly **72*a*** comprises a conductive tubular assembly **71*a*** capped at its right-hand end as shown in FIG. 23 with a bottle-like insulator **113** which is sealed in vacuum-tight relation to the tubular assembly **71*a***. Extending coaxially through the assembly **71*a*** and the insulator **113** is a rod-like electrode **114** which corresponds to the tubular element **68** of FIGS. 11 and 12. The inner end **68*a*** of this electrode **114** has rigid conductors **115** connected to a mounting plate **116** secured to the cathode **21** as shown. The opposite end **117** of the electrode **114** penetrates in vacuum-sealed relation the re-entrant end wall portion **118** of the insulator **113** to have connected thereto the high voltage leads shown diagrammatically in FIG. 23. The parts **71*a*, 113, 114, 115** and **116** are sufficiently strong and rigid as to assist in centering and securing the cathode **21** within the anode **20**. A suitable bellows structure **119** is incorporated within the assembly **71*a*** along with a threaded micrometer adjustment **120** for tilting the assembly **71*a*, 113** slightly so as to position adjustably the cathode **21** within the anode **20**. The total support for the cathode is provided by the two assemblies **49*a*** and **71*a***.

The cathode **21** itself may be made identical to the cathode **21** of FIG. 11, apertures **37** and **103** being provided therein. The biasing function of the outer shell **36** of FIG. 11, however, is performed by a biasing screen assembly shown in enlarged detail in FIG. 24 and identified generally by numeral **121**. This assembly includes an annular spacer **122** of stainless steel or the like which has secured to the underside thereof a fine mesh, conductive screen **123** which full covers the aperture **37**. Concentrically positioned on the peripheral portion of the screen **123** is an annular insulator **124** L-shaped in cross-section as shown. Seated on the insulator **124** is another spacer **125** of some suitable conductor such as stainless steel which has secured to the upper side thereof a second screen **126** like the other screen **123**. The screen **126** is arranged parallel to but is spaced from the screen **123** for performing the purposes previously explained in connection with the screens of FIGS. 14 and 15 which are attached to the outer cathode shell **36**.

Fitted over the spacer **125** is another annular insulator **127** of L-shaped cross-section which engages the main spacer **122** for holding the second spacer **125** in concentric position.

Superposed on and in engagement with the spacer **122** and the insulator **127** is a flat annular retaining ring **128** which clamps the parts **124, 125** and **127** into assembly. An annular cap **129** fits over the retaining ring **128** as shown, and a plurality of circumferentially spaced screws **130** passing through the parts **129, 128, 122** clamp the latter together and secure the same to the cathode **21**.

A sleeve **131** of insulating material is radially secured within a companion aperture in the main spacer **122** as shown and receives therethrough a conductive connecting wire or lead **132**. This lead at its inner end is conductively connected to the spacer **125** by being clamped between the spacer **125** and the insulator **124** as shown. Each of the apertures **37** in the cathode **21** is provided with a biasing screen assembly **121** as just described and the leads **132** of all of these assemblies are connected together so that the biasing potentials applied to all of the screens **126** will be the same.

As in the fusor of FIG. 11, each of the cathode apertures **103** of the fusor of FIG. 23 is coaxially aligned with the beam axis of the respective ion guns **22** and **22*a***. However, in each of the apertures **103** of the fusor of FIG. 23 is provided a biasing-electrode assembly shown in enlarged detail in FIG. 25. This assembly includes a tubular sleeve **133** of ceramic having an enlarged annular projection **134** thereon. The sleeve **133** intimately fits into the cathode opening **103** with the projection **134** seating against the outer cathode surface. A tubular metal insert or electrode **135** is snugly received by the sleeve **133** as shown and is provided with an end portion **136** which engages the bottom end of the sleeve **133** as shown. The upper end of the insert **135** is flared outwardly into a smoothly radiused flange **137** which overlaps the upper end of the sleeve **133**. A suitable wire-like conductor **138** is wrapped around the insert **135** between the flange **137** and the upper end of the sleeve **133**. This wire **138** is of such diameter as to have a wedging fit between the flange **137** and the sleeve **133** thereby locking the electrode **135** to the sleeve **133**. The assembly described thus far is finally secured to the cathode shell **21** by means of a clamping ring **139** fitted over the projection **134** and welded to the shell **21**.

Either as a part of the wire **138** or otherwise secured thereto is a connecting lead **140** for applying a biasing potential to the electrode **135**. As will now be apparent, this electrode **135** is insulated from the cathode **21**.

All of the ion-aperture assemblies as shown in FIG. 25 are interconnected by leads **140**. All of these leads **140** are interconnected with the leads **132** of the biasing screen assemblies **121** so that the electrodes **135** will have the same biasing potential applied thereto as the various screen **126**.

Biasing potential is connected to the biasing electrodes **135** (FIGS. 24 and 25) by means of the assembly shown in FIG. 26. This assembly includes an evacuated tubular housing, indicated generally by the numeral **141**, composed of tubular housing **142** of metal hermetically sealed at the inner end to anode **20** and at the outer end to a glass insulator **143** also of tubular configuration. Coaxially within the tubular housing **141** is a center conductor assembly composed of a metal tube **144** which is hermetically sealed at its outer end with a metallic plug **145**. A tubular conductor **146** is also sealed at one end to the plug **145** and receives on the other end a sleeve-like terminal **147** hermetically sealed at **148** to the conductor **146** and at the end **149** to the outer end of the insulator **143**. The space between the outer wall **142, 143** and the conductor assembly **144, 145, 146** is vacuum-tight and in communication with the fusor interior. A metal cap **150** conductively carrying a sleeve-like contactor **151** telescopes over and conductively engages the terminal **147**. The cap **150** is molded into a protective rubber cover **152** which carries a conductive pin **153** connected at one end to the cap **150** and projects outwardly to a point at which a connection may be made to an external biasing circuit. This biasing circuit is indicated as being in the form of a battery **154** having its positive terminal connected to the cathode shell **21** and the negative terminal to the pin **153**.

A loop of spring wire indicated by the numeral **155** conductively engages the peripheral portions of one of the screens **126** and is formed by convoluting one end portion of a wire **156** which extends through the conductive tube **144**. This wire **156** is of such length that the upper end thereof engages the conductive plug **145** and makes conductive contact therewith. The wire **156** is maintained in position within the tube **144** by means of a small metal ring **157** fitted into the end of the tube **144**. It will now be seen that by providing one of these assemblies **141** on the fusor of FIG. 23, biasing potential may be applied to all of the screens **126** and ion-aperture electrodes **135**.

Referring to the ion guns **22** and **22*a*** of the fusor of FIG. 23, it should be noted that annular magnets **158** are provided thereon which encircle the sleeve elements **79**. These magnets **158** have one pole adjacent to the anode **20** and the other pole outwardly therefrom. They are positioned with respect to the anode **83** (FIG. 13) such as to lengthen the travel of the electrons emitted by the cathode **97** axially of the gun thereby increasing the probability of ionization by each electron. This provides an increase in ion generation over the electrostatic arrangement shown in FIG. 13. In all other respects, the ion guns **22** and **22*a*** of FIG. 23 are like that shown and described in connection with FIG. 13.

The operation of a fusor of FIG. 23 is the same as that of the fusor of FIG. 11 in almost all respects. The same techniques and operating voltages are applied, and all of the voltages are made variable so as to provide convenient control of fusor operation. As in the case of the fusor of FIG. 11, the bias on the screens **126** and the electrodes **135** and supplied by the battery **154**, for example, is adjusted to a value at which the external anode circuit current is reduced to a desired minimum. The screens **126** over the openings **37** in the cathode shell **21** provide the desired equipotential surface which is more negative than the potential on the cathode shell **21** as well as the inner screens **123**. This inhibits the escape of electrons from the inside of the shell **21** thereby reducing losses due to the interception of such electrons by the anode **20**. Also, the screens **126** prevent the positive field from the anode **20** from entering the apertures **37** and disturbing the spherical configuration of the poissor therein, as explained previously.

The electrodes **135** form the same biasing function, these being more negative than the cathode shell **21**, thereby setting up equipotential surfaces which inhibit the outward flow of electrons from the interior of the cathode shell **21**.

Alternative ion gun

In FIGS. 27 through 29 is illustrated an alternative ion gun **22*b*** which may be substituted for the guns **22** and **22*a*** of the preceding embodiments. Comparing this gun **22*b*** with the one of FIG. 13, like numerals will indicate like parts. Instead of providing a cap such as **89** in FIG. 13 for sealing off the end of the gun, a ring flange **89*a***, like the flange **87**, is used for mounting one end of a tubular anode extension, indicated by the numeral **159**. The outer end of this extension **159** is hermetically sealed by means of a cap structure **160**. Thus, it will be noted that the body or envelope of the gun **22*b*** which includes the parts **79** and **159** is considerably longer than the bodies of the guns **22** and **22*a***.

Carried by the wire conductor **93** of the terminal **90** is a tubular electrode **161** which corresponds to some extent to a control grid in an ordinary vacuum tube. This sleeve **161** is secured to the conductor **93** and additionally has a conductive connection **162** to one of the filament leads **94**. The filament **97** as well as the electrode **161** are biased negatively by means of a battery **163**, the negative terminal being connected to the conductor **93** and the positive terminal to the body of the gun **22*b***. This body **79**, **159** constitutes a conductive extension of the anode **20** such that it is operated at the same potential as the anode **20**. Surrounding the anode extension **159** is a series of bar magnets **164** arranged with the longitudinal axis thereof parallel to the axis **165** of the gun **22*b***. Supporting these bar magnets **164** are two axially spaced mounting rings **166** and **167**, these rings being made of iron or some equally suitable, highly magnetic material. A band **167*a*** clamps these magnets onto rings **166** and **167** and retains them in assembly. There are six such magnets used in the arrangement of FIG. 27 as shown more clearly in FIG. 28; however, either a greater or fewer number may be used without departing from the scope of this invention.

In operating the guns **22*b***, the same conditions of fusor operation as explained previously are observed. More specifically, with respect to the gun **22*b***, a suitable filament voltage is applied to the filament **97** for the generation of ionizing electrons. Since the filament **97** is substantially contained within the length of the electrode **161**, the electrons in order to travel to the anode **159** must move axially of the gun. By reason of the focusing influence of the magnets **164**, the electrons will be directed rightwardly as viewed in FIG. 27 in a spiral path until they are eventually collected by the right-hand end portion of the anode **159**. Fusion-reactive gas admitted to the gun via the fitting **98** will be ionized by these electrons, such ions thereupon coming under the influence of the more negative electrode **161** as well as the fusor cathode **21**. The ions eventually are accelerated through the aperture **82** and form into beams which travel paths intersecting the tube center **26**.

Higher ion currents may be obtained from the ion guns **22*b*** than those of FIG. 11 inasmuch as the ionizing electrons emitted from the filament **97** (FIG. 27) are accelerated through longer paths before interception by the anode; hence, they have a greater probability of producing ions before being intercepted.

In the following are given dimensions and values for system and circuit parameters for the embodiment of this invention as shown in FIG. 23, these being given by way of illustration only and not by way of limitation.

Dimensions

Internal diameter of anode shell **20**	inches	6
Thickness of anode shell **20**	do	0.093
Anode **20** material		[1] 304
Internal diameter of cathode shell **21**	inches	4.38
Thickness of shell **21**	do	0.060
Cathode **21** material		[1] 304
Size of openings **37**	inches diameter	1.75
Size of openings **103**	do	0.625
Inner diameter of rings **124, 125, 127**	inches	1.500
Size of screens **123** and **126**	mesh	[2] 15
Spacing between screens **123** and **126**	inch	0.140
Overall height of assembly **121** radially beyond cathode **21**	inch	0.320
Inner diameter of electrode **135**	do	0.437
Length of electrode **135**	do	0.500
Distance electrode **135** projects radially outwardly from cathode **21**	inch	0.312
Size of opening **80**	do	1.125
Outer diameter of sleeve **79**	do	1.500
Inner diameter of aperture **82**	do	0.500
Internal axial length of gun **22, 22*a***	do	2.875
Length of anode **84**	do	1.000
Minimum inner diameter of anode **84**	do	0.625
Maximum inner diameter of anode **84**	do	0.825
Spacing of filament **97** from the adjacent end of anode **84**	inch	0.125
Space between anode **84** and sleeve **79**	do	0.187
Thickness of aperture ring **81**	do	0.375
Distance between ring **81** and anode **84**	do	0.500

[1] Stainless steel.
[2] Woven tungsten.

For a neutron count of 10^9, the following operating parameters for the fusor of FIG. 23 may be used as an approximation. Adjustments of voltages and dimensions may be required for obtaining this precise count.

Fusion-reactive gas	Deuterium and tritium, equal portions.
Neutral gas pressure in fusor	2 microns.
Anode **20** circuit current	30 milliamperes.
Anode **20** applied voltage	100 kilvolts.
Voltage of supply **100** as applied to the anode **84**	250 volts.
Voltage applied to the filament **97**	6 volts.
Filament **97** current	7 amperes.
Bias voltage on screens **126**	500 volts.

A viewing port assembly **168** is attached to the anode **20** as shown in FIG. 27 for the purpose of permitting observation, either directly or indirectly by means of closed circuit television equipment, of the reaction which occurs in the center, the outer end of the assembly **168** being vacuum sealed by reason of a window **169**.

While there have been described above the principles of this invention in connection with specific apparatus, it is to be clearly understood that this description is made only by way of example and not as a limitation to the scope of the invention.

What is claimed is:

1. In a device for producing nuclear reactions, anode means, cathode means inside said anode means, said cathode means defining a volume centrally located with respect to both said anode and cathode means, said volume being free of tangible structure, said cathode means being open to the flow of gaseous particles therethrough, a fusion-reactive gas within said volume, means supplying a potential between said cathode and anode means for establishing an electric field therebetween, means including said cathode and anode means and said potential-supplying means for accelerating ions of said gas to fusion-reacting energies along converging radial paths in said volume, and means for inhibiting flow of electrons from said volume to said anode means, said inhibiting means including means for biasing the open portions of cathode means more negatively than the cathode means itself.

2. The device of claim **1** wherein said volume is substantially spherical in shape and said paths have a common intersection in the central portion of said volume, and further including means maintaining said gas at sub-atmospheric pressure.

3. The device of claim **1**, said cathode means being a generally spherically shaped metallic shell having a plurality of openings therein.

4. The device of claim **3** wherein said anode means is a generally spherically shaped metallic shell concentrically surrounding said cathode shell, said inhibiting means including a plurality of biasing electrodes, one electrode for each opening, said biasing electrodes having portions peripherally coextensive with said openings, respectively, and means for applying biasing potential to said biasing electrodes for establishing said equipotential surfaces.

5. The device of claim **4**, including means connected to said anode shell for generating and injecting charge-particles into the space between said cathode and anode means, the magnitude of said electric field being adequate to direct at least a portion of said charge-particles through at least a portion of said openings and into said volume.

6. The device of claim **4**, including a plurality of ion guns carried by said anode shell in radial alignment with respective ones of said openings, means including said ion guns for directing ions through said openings and into said volume, whereby ions from said guns may be projected toward the opposite side of said anode shell.

7. The device of claim **6** wherein the first openings diametrically aligned with said ion guns, respectively, are free of structure and the remaining second openings are covered with biasing screens, respectively, means insulating said screens from the cathode shell next adjacent to said volume, the biasing electrodes for said first openings including annular elements coaxially fitted into the respective cathode shell openings, said annular elements being insulated from said cathode shell.

8. The device of claim **7** wherein each of said second openings is covered with two screens, the first of said screens being conductively mounted on said cathode shell, each second opening further having an annular insulating device coaxially surrounding the same and operatively mounted on the outer side of said cathode shell, each insulating device having a second of said screens mounted thereon spaced from the first screen, and connections to said second screens for biasing the same negatively with respect to said cathode shell.

9. The device of claim **6**, wherein the means for maintaining said gas at sub-atmospheric pressure includes a supply of neutral fusion-reactive gas connected to said ion guns and also means for controlling the pressure of said gas as admitted to said ion guns in the range of from 10^{-3} to 10^{-8} millimeters of mercury, said ion guns and said anode shell being hermetically sealed and in communication with each other, said controlling means including a vacuum pump for exhausting gas from within the space of said anode shell.

10. The device of claim **2**, said anode means incudling a generally spherical anode shell, said cathode means including two generally spherical concentric cathode shells spaced apart a predetermined distance, said two cathode shells having a plurality of openings therein which are in radial registry, said cathode shells being concentric with respect to said anode shell, means for biasing the outer one of said cathode shells more negative than the inner one.

11. The device of claim **10**, including means connected to said anode shell for generating and injecting charge-particles into the space between said cathode and anode shells, the magnitude of said electric field being adequate to direct at least a portion of said charge-particles through at least a portion of said openings and into said volume.

12. The device of claim **11**, including a plurality of ion guns carried by said anode shell in radial alignment with respective ones of said openings, means including said ion guns for directing ions through said openings and into said volume, whereby ions from said guns may be projected toward the opposite side of said anode shell.

13. The device of claim **12**, wherein the first openings diametrically are free of structure and the remaining second openings of the outer cathode shell are covered with biasing screens, respectively, said screens being conductively secured to said outer cathode shell, said means for maintaining said gas at sub-atmospheric pressure includes a supply of neutral fusion-reactive gas connected to said ion guns and also means for controlling the pressure of said gas admitted to said guns in the range of from 10^{-3} to 10^{-8} millimeters of mercury, said ion guns and said anode shell being hermetically sealed and in communication with each other, said controlling means including a vacuum pump for exhausting gas from within the space of said anode shell.

14. The device of claim **13** including means connected to said anode means for coupling electrical power therefrom.

15. In a device for producing nuclear reactions comprising anode means, cathode means inside said anode means, said cathode means defining a volume free of tangible structure, a fusion-reactive gas within said volume, said cathode means having openings for the traversal therethrough of charge-particles, means including said anode and cathode means and ions of said gas forming a space charge in the central portion of said volume, said space charge including electrons and ions of said gas so distributed as to produce a substantially spherical electric field which confines target ions in a point-like region in said central portion and oscillates projectile ions through said region at nuclear reacting energies, whereby fusion reactions result from collisions between said projectile ions and between said projectile ions and target ions, and means for biasing the openings in said cathode means negatively with respect to said cathode means for inhibiting the flow of electrons from the volume inside said cathode means to said anode means.

16. The device of claim **15** wherein said space charge is arranged in a configuration which provides a spherical virtual anode concentrically surrounding a spherical virtual cathode, said cathode means including a generally spherical shell concentrically surrounding said virtual anode thereby providing an electric field therebetween which exerts a force outwardly on a positively charged particle in a direction radially toward said cathode means, the potential of said virtual anode being of a magnitude which propels ions inwardly and oscillates them as projectiles through said virtual cathode at nuclear-reacting energies, whereby collisions of ions in the region of said virtual cathode produces nuclear reactions.

17. The device of claim **15** wherein said gas is of a composition that reactant products of fusion include positively charged particles which are propelled outwardly against the field of said anode means with sufficient energy to transfer the charges thereof to said anode means thereby generating electrical power, and circuit means connected to said anode means for coupling the generated electrical power therefrom to a utilization device.

18. The device of claim **17** wherein said anode means includes a generally spherical conductive anode shell, said cathode means includes a generally spherical conductive cathode shell concentrically positioned inside said anode shell, said cathode shell having said openings therein, said positively charged particles passing through said openings in transit from said volume toward said anode shell, and said circuit means including a load impedance connected in series between said anode and cathode means whereby said generated electrical power may be coupled from said impedance to a utilization device.

19. The device of claim **17** wherein said space charge-forming means includes a power supply connected to said anode and cathode means for applying an operating voltage thereto; the value of said operating voltage, the composition of said gas and the number of gaseous particles within said volume being so related that the fusion reactions are self-sustaining and contribute more power to said circuit means than is consumed in initiating such reactions.

References Cited

UNITED STATES PATENTS

3,258,402 6/1966 Farnsworth ----------- 176—1

REUBEN EPSTEIN, *Primary Examiner.*

Nº 1098 A.D. 1913

Date of Application, 14th Jan., 1913—Accepted, 14th Jan., 1914

COMPLETE SPECIFICATION.

Improvements in and relating to Apparatus for Producing Electricity.

I, Roy Jerome Meyers, of Hotel Altamont, Baltimore, in the State of Maryland, United States of America, Electrician, do hereby declare the nature of this invention and in what manner the same is to be performed, to be particularly described and ascertained in and by the following statement:—

This invention relates to improvements in apparatus for the production of electrical currents, and the primary object in view is the production of a commercially serviceable electrical current without the employment of mechanical or chemical action. To this end the invention comprises means for producing what I believe to be dynamic electricity from the earth and its ambient elements.

I am, of course, aware that it has been proposed to obtain static charges from upper strata of the atmosphere, but such charges are recognized as of widely variant potential and have thus far proved of no practical commercial value, and the present invention is distinguished from all such apparatus as has heretofore been employed for attracting static charges by the fact that this improved apparatus is not designed or employed to produce or generate irregular, fluctuating or other electrical charges which lack constancy, but on the other hand I have by actual test been able to produce from a very small apparatus at comparatively low elevation, say about fifty or sixty feet above the earth's surface, a substantially constant current at a commercially usable voltage and amperage. This current I ascertained by repeated tests is capable of being readily increased by additions of the unit elements in the apparatus hereinafter set forth, and I am convinced from the constancy of the current obtained and its comparatively low potential that the current is dynamic and not static, although, of course, it is not impossible that certain static discharges occur and, in fact, I have found occasion to provide against the damage which might result from such discharge by the provision of lightning arresters and cut-out apparatus which assist in rendering the obtained current stable by eliminating sudden fluctuations which sometimes occur during conditions of high humidity from what I consider static discharges. The nature of my invention is obviously such that I have been unable to establish authoritatively all of the principles involved, and some of the theories herein expressed may possibly prove erroneous, but I do know and am able to demonstrate that the apparatus which I have discovered does produce, generate, or otherwise acquire a difference of potential representing a current value which is commercially serviceable and may be delivered at the voltage and amperage above stated, or varied therefrom at the will of the operator according to the uses to which the current is to be subjected.

The invention comprises generically means for producing electrical currents of serviceable potential substantially without the employment of mechanical or chemical action, and in this connection I have been able to observe no chemical action whatever on the parts utilized although deterioration may possibly occur in some of the parts, but so far as I am able to determine such deterioration does not add to the current supply but is merely incidental to the effect of climatic action.

The invention more specifically comprises the employment of a magnet or

[*Price 8d.*]

BIRMINGHAM REFERENCE LIBRARY PUBLIC LIBRARIES

magnets and a co-operating element, such as zinc disposed adjacent to the magnet or magnets and connected in such manner and arranged relative to the earth so as to produce current, my observation being that current is produced only when such magnets have their poles facing substantially to the north and south and the zincs are disposed substantially along the magnets.

The invention also comprehends other details of construction, combinations and arrangements of parts as will hereinafter be fully set forth and claimed.

In the accompanying drawings:

Figure 1 is a top plan view of an apparatus embodying the features of the present invention, the arrow accompanying the figure indicating substantially the geographical north, parts of the figure being diagrammatic for condensing the showing.

Figure 2 is a view in side elevation of the parts seen in plan in Figure 1.

Figure 3 is a vertical section taken on the plane indicated by the line 3—3 of Figure 2 and looking in the direction indicated by the arrow.

Figure 4 is a detail view partly in elevation and partly in section showing the detail connections of the converter and intensifier.

Figure 5 is a transverse section taken on the planes indicated by line 5—5 of Figure 4 and looking downwardly.

Figure 6 is an enlarged detail fragmentary section illustrating the parts at the juncture of the conductors and one of the intensifiers.

Figure 7 is an enlarged detail view partly in elevation and partly in section of one of the automatic cut-outs and

Figure 8 is a diagrammatic view of one of the simplest forms of embodiments of the invention.

Referring to the drawing by numerals, 1, 1 indicates magnets connected by a magnetic substance 2, preferably an iron wire. The magnets 1 are arranged in pairs, one pair being spaced beneath the other, and interposed between the magnets are zinc plates 3, 3 connected by an iron wire conductor 4. Suitable insulating supports 5 are arranged for sustaining the respective magnets 1 and plates 3, 3. Each plate 3 is preferably bent substantially into **V** form, as clearly seen in Figure 1, and the **V** of one of the plates opens or faces toward the north and the **V** of the other plate to the south. I have determined by experimentation that it is essential that the plates 3 be disposed substantially north and south with their flat faces approximately parallel to the adjacent faces of the co-operating magnets, although by experience I have not discovered any material difference in the current obtained when the plates are disposed slightly to one side of north and south, as for instance when disposed in the line of the magnetic polarity of the earth. The same is true with respect to the magnets 1, the said magnets being disposed substantially north and south for operative purposes, although I find that it is immaterial whether the north pole of one of the magnets is disposed to the north and the south pole to the south, or *vice versa,* and it is my conviction from experience that it is essential to have the magnets of each pair connected by magnetic material so that the magnets substantially become one with a pole exposed to the north and a pole exposed to the south. In Figure 1, I have indicated in full lines by the letters S and N the respective polarities of the magnets 1, and have indicated in dotted lines the other poles of those magnets when the connection 2 is severed. I have found that the magnets and zinc plates operate to produce, whether by collection or generation I am not certain, electrical currents when disposed substantially north and south, but when disposed substantially east and west no such currents are produced. I also find that the question of elevation is by no means vital, but it is true that more efficient results are obtained by placing the zincs and magnets on elevated supports. I furthermore find from tests that it is possible to obtain currents from the apparatus with the zincs and magnets disposed in a building or otherwise enclosed, although more efficient results are obtained by having the said elements arranged in the open.

While in Figures 1, 2 and 3, I have shown the magnets and the zinc plates as superimposed, it will be apparent, as hereinafter fully set forth, that these elements may be juxtaposed in horizontal planes, and substantially the same results will be secured. Furthermore, the magnets 1 with the interposed zincs 3, as shown in Figures 1, 2 and 3 merely represent a unit which may be repeated either horizontally or vertically for increasing the current supply, and when the unit is repeated the zinc plates are arranged alternating with the magnets throughout the entire series as hereinafter indicated.

A conductor 6 is connected in multiple with the conductors 2 and a conductor 7 is connected with conductor 4, the conductor 6 extending to one terminal of a rectifier which I have indicated by the general reference character 8, and the conductor 7 extending to the other terminal of said rectifier. The rectifier as seen in diagram in Figure 1 may assume any of several well known embodiments of the electrical valve type and may consist of four assymmetric cells or Cooper-Hewitt mercury vapor lamps connected as indicated in Figure 1 for permitting communication of the positive impulses from conductor 7 only to the line conductor 9 and the negative impulses from the conductor 7 only to the line conductor 10, and permitting the positive impulses from the conductor 6 only to the line conductor 9 and the negative impulses from conductor 6 only to the line conductor 10. The current from this rectifier may be delivered through the conductors 9 and 10 to any suitable source for consumption.

While the said rectifier 8 may consist of any of the known types, as above outlined, it preferably consists of a specially constructed rectifier which also has the capacity of intensifying the current and comprises specifically the elements shown in detail in Figures 4, 5 and 6 wherein I have disclosed the detail wiring of the rectifier when composed of four of the rectifying and intensifying elements instead of assymmetric cells or simple mercury vapor valves. As each of these structures is an exact embodiment of all the others, one only will be described, and the description will apply to all. The rectifying element of each construction consists of a mercury tube 11 which is preferably formed of copper but may be formed of glass or other suitable material, and comprises a cylinder having its end portions tapered and each terminating in an insulating plug or stopper 12. Through the upper stopper 12 is extended the electrode 13 which extends well into the tube and preferably substantially one-half the length thereof to a point adjacent the inner end of an opposing electrode 14 which latter electrode extends thence downwardly through the insulation 12 at the lower end of the tube. The tube 11 is supplied with mercury and is adapted to operate on the principle of the mercury vapor lamp, serving to rectify current by checking back impulses of one sign and permitting passage of impulses of the other. To avoid the necessity for utilizing a starter, as is common with the lamp type of electrical valve, the supply of mercury within the tube may be sufficient to contact with the lower end of the electrode 13 when current is not being supplied, so that as soon as current is passed from one electrode to the other sufficiently for volatilizing that portion of the mercury immediately adjacent the lower end of electrode 13, the structure begins its operation as a rectifier. The tube 11 is surrounded by a tube 15 which is preferably spaced from tube 11 sufficiently for allowing atmospheric or other cooling circulation to pass the tube 11. In some instances, it may be desirable to cool the tube 11 by a surrounding body of liquid, as hereinafter indicated. The tube 15 may be of insulating material but I find efficient results attained by the employment of a steel tube, and fixed to the ends of the tube are insulating disks 16, 16 forming a spool on which are wound twin wires 6^1 and 7^1, the wire 6^1 being connected at the inner helix of the coil with the outer end of the electrode 14, the lower portion of said electrode being extended to one side of the tube 11 and passed through an insulating sleeve 17 extending through the tube 15, and at its outer end merging into the adjacent end of the wire 6^1. The wire 7^1 extends directly from the outer portion of the spool through the several helices to a point adjacent the juncture of the electrode 14 with wire 6^1 and thence extends in mechanical parallelism with the wire throughout the coil, the wire 6^1 ending in a terminal 18 and the wire 7^1 ending in a terminal 19. For the sake of convenience of description and of tracing the circuits, each of the apparatus just above described and herein known as an intensifier and rectifier will be mentioned as A, B, C and D, respectively. Conductor 6 is formed with branches 20 and 21 and conductor 7 is formed with similar branches 22 and 23. Branch 20 from conductor 6 connects with conductor 7^1 of intensifier B and branch 21 of conductor 6 connects with the conductor 7^1 of intensifier C, while branch 22 of conductor 7 connects with conductor 7^1 of intensifier A and branch 23 of conductor 7 connects with conductor 7^1 of intensifier D. A conductor 27 is connected with terminal 19 of intensifier A and extends to and is connected with terminal 18 of intensifier C, and a conductor 28 is connected with the terminal 19 of intensifier C and extends to and is connected with electrode 13 of intensifier A. A conductor 29 extends from the terminal 19 of intensifier B to the terminal 18 of intensifier D and a conductor 30 extends from the terminal 19 of intensifier D to electrode 13 of intensifier B. Each electrode 13 is supported on a spider 13^1 resting on the upper disk 16 of the respective intensifier. Conductors 31 and 32 are connected with the terminals 18 of intensifiers A and B and are united to form the positive line wire 9 which co-operates with the negative line wire 10 and extends to any suitable point of consumption. The line wire 10 is provided with branches 35 and 36 extending to the electrodes 13 of intensifiers C and D for completing the negative side of the circuit.

Thus it will be seen that alternating currents produced in the wires 6 and 7 will be rectified and delivered in the form of a direct current through the line wires 9 and 10, and I find by experiment that the wires 6 and 7 should be of iron, preferably soft, and may of course be insulated, the other wiring not specified as iron being of copper or other suitable material.

In carrying out the operation as stated, the circuits may be traced as follows: A positive impulse starting at the zincs 3 is directed along conductor 7 to branch 23 to conductor 7^1 and the winding of intensifier D to terminal 19 through conductor 30 to electrode 13 of the rectifier of intensifier B through said rectifier to the conductor 6^1, through the winding thereof to the contact 18, conductor 32 and to the line wire 9. The next or negative impulse directed along conductor 7 cannot find its way along branch 23 and the circuit just above traced because it cannot pass across the rectifier of intensifier B but instead the negative impulse passes along conductor 22 to conductor 7 of intensifier A and the winding thereof to the contact 19 to conductor 27 to contact 18 of intensifier C, to the winding of the wire 6^1 thereof to the electrode 14 through the rectifier to the electrode 13 and conductor 36 to the line wire 10. A positive impulse delivered to wire 6 passes along the said wire to the branch 21 to the conductor 7^1 of intensifier C and the winding thereof to the contact 19, conductor 28, electrode 13 of the rectifier of intensifier A, electrode 14 thereof and conductor 6^1 to contact 18 and wire 31 to line wire 9. Obviously the positive impulse cannot pass along the wire 20 because of its inverse approach to the rectifier of intensifier B. The next impulse or negative impulse delivered to conductor 6 cannot pass along conductor 21 because of its connection with electrode 13 of the rectifier of intensifier A, but instead passes along conductor 20 to the wire 7^1 and its winding forming part of intensifier B to the contact 19 and conductor 29 to contact 18 and the winding of wire 6^1 of intensifier D to the electrode 14 and through the rectifier to the electrode 13 and conductor 35 to line wire 10. Thus the current is rectified and all positive impulses directed along one line and all negative impulses along the other line so that the potential difference between the two lines will be maximum for the given current of the alternating circuit. It is, of course, apparent that a less number of intensifiers with their accompanying rectifier elements may be employed with a sacrifice of the impulses which are checked back from a lack of ability to pass the respective rectifier elements, and in fact I have secured efficient results by the use of a single intensifier with its rectifier elements, as hereinafter set forth.

Grounding conductors 37 and 38 are connected respectively with the conductors 6 and 7 and are provided with the ordinary lightning arresters 39 and 40 respectively for protecting the circuit against high tension static charges.

Conductors 41 and 42 are connected respectively with the conductors 6 and 7 and each connects with an automatic cut-out 43 which is grounded as at 44. Each of said automatic cut-outs is exactly like the other and one of the same is shown in detail in Figure 7 and comprises the inductive resistance 45 provided with an insulated binding post 46 with which the respective conductor 6 or 7 is connected, said post also supporting a spring 48 which sustains an armature 49 adjacent the core of the resistance 45. The helix of resistance 45 is connected preferably through the spring to the binding post at one end and at the other end is grounded on the core of the resistance, the said core being grounded by ground conductor 44 which extends to the metallic plate 52 imbedded in moist carbon or other inductive material 53 buried in the earth. Each of the conductors 41, 42 and 44 is of iron, and in this connection I wish it understood that where I state the specific substance I am able to verify the accuracy of the statement by the results of tests which I have made, but of course I wish to include along with such substance all equivalents, as for instance, where iron is mentioned its by-products, such as steel, and its equivalents such as nickel and other magnetic substances are intended to be comprehended. The cut-out apparatus seen in detail in Figure 7 is employed particularly for insuring against high tension currents it being obvious from the structure shown that when potential rises beyond the limit established by the tension of the spring sustaining the armature 49, the armature will be moved to a position contacting with the core of the cut-out device and thereby directly close the ground connection for line wire 41 with conductor 44, eliminating the resistance of winding 45 and allowing the high tension current to be discharged to the ground. Immediately upon such discharge the winding 45 losing its current will allow the core to become demagnetized and release the armature 49 whereby the ground connection is substantially broken leaving only the connection through the winding 45 the resistance of which is sufficient for insuring against loss of low tension current.

In Figure 8 I have illustrated an apparatus which though apparently primitive in construction and arrangement comprehends the first successful embodiment which I produced in the course of the discovery of the present invention, and it will be observed that the essential features of the invention are therein disclosed. The structure delineated in said figure consists of horse shoe magnets 54, 54, one facing north and the other south, that is, each opening in the respective directions indicated and the two being connected by an iron wire 55 which is uninsulated and wrapped about the respective magnets at or adjacent the neutral zone thereof, and the wire 55 is preferably soldered to the respective magnets each end portion of the wire 55 being extended from the respective magnet to and connected with, as by being soldered to, a zinc plate 56, there being a plate 56 for each magnet and each plate being arranged longitudinally substantially parallel with the legs of the magnet and with the faces of the plate exposed toward the respective legs of the magnet, the plate being thus arranged endwise toward the north and south. An iron wire 57 connects the plates 56, the ends of the wire being preferably connected adjacent the outer ends of the plates but from experiment I find that the wire may be connected at practically any point to the plate. Lead wires 58 and 59 are connected respectively with the wires 55 and 57 and supply an alternating current ordinarily at a comparatively low tension, and to control such current the wires 58 and 59 may be extended to a rectifier or combined rectifier and intensifier, as above set forth.

The tests which I have found successful with the apparatus seen in Figure 8 were carried out by the employment first of horse shoe magnets approximately four inches in length, the bar comprising the horse shoe being about one inch square, the zincs being dimensioned proportionately and from this apparatus with the employment of a single intensifier and rectifier, as above stated, I was able to obtain a constant current of 8 volts.

It should be obvious that the magnets forming one of the electrodes of this apparatus may be permanent or may be electro-magnets, or a combination of the two.

While the magnets mentioned throughout the above may be formed of any magnetic substance, I find the best results obtained by the employment of the nickel chrome steel.

While the successful operation of the various devices which I have constructed embodying the present invention have not enabled me to arrive definitely and positively at fixed conclusions relative to the principles and theories of operation and the source from which current is supplied, I wish it to be understood that I consider myself as the first inventor of an apparatus of the general type hereinbefore described capable of producing commercially serviceable electricity, for which reason my claims hereinafter appended contemplate that I may utilize a wide range of equivalents so far as concerns details of construction suggested as preferably employed.

The current which I am able to obtain is dynamic in the sense that it is not static and its production is accomplished without chemical or mechanical action either incident to the actual chemical or mechanical motion or incident to changing calorific conditions so that the elimination of necessity for the use of chemical or mechanical action is to be considered as including the elimination of the necessity for the use of heat or varying degrees thereof.

Having now particularly described and ascertained the nature of my said invention, and in what manner the same is to be performed, I declare that what I claim is:—

1. Means for producing dynamic electricity without mechanical or chemical action.

2. Electricity producing means as claimed in Claim 1, characterized in that said means is capable of producing low tension current.

3. Electricity producing means as claimed in Claim 1, characterized in that said means comprises a magnet, and means co-operating with the latter.

4. Means as set forth in Claim 3, characterized in that the parts are stationary.

5. Means as claimed in Claim 3, characterized in that the magnet is disposed substantially north and south.

6. Means as claimed in Claims 1, 3 and 5, wherein the means coacting with the magnet is a metal and said parts are disposed substantially north and south.

7. Means as claimed in Claims 1, 3 and 6, in which the metal is zinc, and combined with conductors connected with the co-operating parts to deliver current therefrom.

8. Means as set forth in Claim 1, characterized in that said means comprises spaced magnets with an adjacent co-operating zinc, and an iron wire connecting the magnets, and means to deliver electrical current from said parts.

9. Means as set forth in Claim 8, characterized in that the current delivery means comprises an intensifier and rectifier.

10. Means as set forth in Claim 8, characterized in that the current delivery means comprises wires connected with the magnets and zinc, an electrical valve connected with one of said wires, and independent helices surrounding said valve, one of said helices being connected with the terminal of the valve at the opposite side from the contact of said wire and the other of said helices being connected with the other wire, the electrical valve comprising a mercury vapor rectifier.

11. The process of producing electricity comprising exposing a magnet and

co-operating means disposed substantially north and south and taking off current therefrom.

12. The process of producing electricity comprising disposing stationary elements in co-operative relation in respect to each other and with respect to the earth for giving off relatively low tension electrical current, substantially without chemical action.

13. Electricity producing means constructed and operating substantially as described with reference to the accompanying drawings.

Dated this 13th day of January, 1913.

W. P. THOMPSON & Co.,
6, Lord Street, Liverpool, and at
Bradford & London,
Agents for the Applicant.

Reference has been directed, in pursuance of Section 7, Sub-section 4, of the Patents and Designs Act, 1907, to Specifications No. 16,709 of 1887, No. 14,033 of 1899, No. 15,412 of 1906, and No. 5457 of 1911.

Redhill: Printed for His Majesty's Stationery Office, by Love & Malcomson, Ltd.—1914.

A.D. 1913. JAN. 14. No. 1098.

MEYERS' COMPLETE SPECIFICATION.

(2 SHEETS)
SHEET 1.

Fig. 1.


S
1
9
1
N
N
7
2
6
10
9
8
41
42
37
38
43
48
49
49
44
39
40
1
3
1
S
N
+

Fig. 8. Fig. 6.


54
56
55
IRON WIRE
UNINSULATED
IRON WIRE
IRON WIRE
52
58
57
54
56
TO RECTIFIER
7'
6'
6'
6'
17
14
7'

Fig. 2.


1
1
3
2
6
5
3
4
3
6
1
7
1
2
5
3
TO RECTIFIER

Fig. 3.


1
5
3
3
6
7
5
1
5
TO RECTIFIER

[This Drawing is a reproduction of the Original on a reduced scale.]

BIRMINGHAM
REFERENCE LIBRARY
PUBLIC LIBRARIES

Malby & Sons, Photo-Litho.

A.D. 1913. JAN. 14. No 1098.
MEYERS' COMPLETE SPECIFICATION.

(2 SHEETS)
SHEET 2.

[This Drawing is a full-size reproduction of the Original.]

Fig. 7.


48
46
41
49
45
44
53
52

Fig. 4.


+
31
15
13
13'
16
19
18
11
A
6
5
28
27
B
7'
5
20
12
14
17
16
22
32
13
+ 9
18
19
7
29
7'
30
18
13
11
19
C
21
7'
D
36
23
7'
35
10 –

Fig. 5.


17
+
–
7'
7
14
6'
15
11
7'

REFERENCE LIBRARY PUBLIC LIBRARIES

Malby & Sons, Photo-Litho.

A.D. 1913. Jan. 14. No. 1098.
MEYERS' Complete Specification.

[This Drawing is a full-size reproduction of the Original.]

Fig. 7.


48
46
41
44
53
52
49
45

Fig. 4

Fig. 5


31
15
13'
16
19
13
11
32
13
18
19
7
A
28
29
27
B
5
5
7'
7'
14
12
22
17
16
13
30
11
19
18
19
C
23
D
36
7'
7'
35
10
9
+
−
I.
17
+
−
7'
7
14
15
11

BIRMINGHAM REFERENCE LIBRARY PUBLIC LIBRARIES

Malby & Sons, Photo-Litho.

United States Patent [19]
Eastlund

[11] **Patent Number:** **4,686,605**
[45] **Date of Patent:** **Aug. 11, 1987**

[54] **METHOD AND APPARATUS FOR ALTERING A REGION IN THE EARTH'S ATMOSPHERE, IONOSPHERE, AND/OR MAGNETOSPHERE**

[75] Inventor: **Bernard J. Eastlund**, Spring, Tex.

[73] Assignee: **APTI, Inc.**, Los Angeles, Calif.

[21] Appl. No.: **690,333**

[22] Filed: **Jan. 10, 1985**

[51] **Int. Cl.⁴** **H05B 6/64**; H05C 3/00; H05H 1/46

[52] **U.S. Cl.** .... **361/231**; 89/1.11; 380/59; 244/158 R

[58] **Field of Search** .... 361/230, 231; 244/158 R; 376/100; 89/1.11; 380/59

[56] **References Cited**

PUBLICATIONS

Liberty Magazine, (2/35) p. 7 N. Tesla.

New York Times (9/22/40) Section 2, p. 7 W. L. Laurence.

New York Times (12/8/15) p. 8 Col. 3.

Primary Examiner—Salvatore Cangialosi
Attorney, Agent, or Firm—Roderick W. MacDonald

[57] **ABSTRACT**

A method and apparatus for altering at least one selected region which normally exists above the earth's surface. The region is excited by electron cyclotron resonance heating to thereby increase its charged particle density. In one embodiment, circularly polarized electromagnetic radiation is transmitted upward in a direction substantially parallel to and along a field line which extends through the region of plasma to be altered. The radiation is transmitted at a frequency which excites electron cyclotron resonance to heat and accelerate the charged particles. This increase in energy can cause ionization of neutral particles which are then absorbed as part of the region thereby increasing the charged particle density of the region.

15 Claims, 5 Drawing Figures



FIG. 1


11
MB
NORTH POLE
10
20
12
15
TRANSMITTER 16
14
POWER GENERATOR 17
C
EQUATOR
13
R
MB
SOUTH POLE

FIG. 2


R2
MB1
[F=-μ•∇B]
R1

FIG. 3


[F=-μ•∇B]
R2
11
θ
e
i
i
n
i
i
i
12
R1
e
n
i
10

FIG. 4


30
R3
11
12
f3
33
20
31
15
10
32


TREATER
MHD GENERATOR
TRANSMITTER

FIG. 5

METHOD AND APPARATUS FOR ALTERING A REGION IN THE EARTH'S ATMOSPHERE, IONOSPHERE, AND/OR MAGNETOSPHERE

DESCRIPTION

1. Technical Field

This invention relates to a method and apparatus for altering at least one selected region normally existing above the earth's surface and more particularly relates to a method and apparatus for altering said at least one region by initially transmitting electromagnetic radiation from the earth's surface essentially parallel to and along naturally-occurring, divergent magnetic field lines which extend from the earth's surface through the region or regions to be altered.

2. Background Art

In the late 1950's, it was discovered that naturally-occuring belts exist at high altitudes above the earth's surface, and it is now established that these belts result from charged electrons and ions becoming trapped along the magnetic lines of force (field lines) of the earth's essentially dipole magnetic field. The trapped electrons and ions are confined along the field lines between two magnetic mirrors which exist at spaced apart points along those field lines. The trapped electrons and ions move in helical paths around their particular field lines and "bounce" back and forth between the magnetic mirrors. These trapped electrons and ions can oscillate along the field lines for long periods of time.

In the past several years, substantial effort has been made to understand and explain the phenomena involved in belts of trapped electrons and ions, and to explore possible ways to control and use these phenomena for beneficial purposes. For example, in the late 1950's and early 1960's both the United States and U.S.S.R. detonated a series of nuclear devices of various yields to generate large numbers of charged particles at various altitudes, e.g., 200 kilometers (km) or greater. This was done in order to establish and study artifical belts of trapped electrons and ions. These experiments established that at least some of the extraneous electrons and ions from the detonated devices did become trapped along field lines in the earth's magnetosphere to form artificial belts which were stable for prolonged periods of time. For a discussion of these experiments see "The Radiation Belt and Magnetosphere", W. N. Hess, Blaisdell Publishing Co., 1968, pps. 155 et sec.

Other proposals which have been advanced for altering existing belts of trapped electrons and ions and/or establishing similar artificial belts include injecting charged particles from a satellite carrying a payload of radioactive beta-decay material or alpha emitters; and injecting charged particles from a satellite-borne electron accelerator. Still another approach is described in U.S. Pat. No. 4,042,196 wherein a low energy ionized gas, e.g., hydrogen, is released from a synchronous orbiting satellite near the apex of a radiation belt which is naturally-occurring in the earth's magnetosphere to produce a substantial increase in energetic particle precipitation and, under certain conditions, produce a limit in the number of particles that can be stably trapped. This precipitation effect arises from an enhancement of the whistler-mode and ion-cyclotron mode interactions that result from the ionized gas or "cold plasma" injection.

It has also been proposed to release large clouds of barium in the magnetosphere so that photoionization will increase the cold plasma density, thereby producing electron precipitation through enhanced whistler-mode interactions.

However, in all of the above-mentioned approaches, the mechanisms involved in triggering the change in the trapped particle phenomena must be actually positioned within the affected zone, e.g., the magnetosphere, before they can be actuated to effect the desired change.

The earth's ionosphere is not considered to be a "trapped" belt since there are few trapped particles therein. The term "trapped" herein refers to situations where the force of gravity on the trapped particles is balanced by magnetic forces rather than hydrostatic or collisional forces. The charged electrons and ions in the ionosphere also follow helical paths around magnetic field lines within the ionosphere but are not trapped between mirrors, as in the case of the trapped belts in the magnetosphere, since the gravitational force on the particles is balanced by collisional or hydrostatic forces.

In recent years, a number of experiments have actually been carried out to modify the ionosphere in some controlled manner to investigate the possibility of a beneficial result. For detailed discussions of these operations see the following papers: (1) Ionospheric Modification Theory; G. Meltz and F. W. Perkins; (2) The Platteville High Power Facility; Carrol et al.; (3) Arecibo Heating Experiments; W. E. Gordon and H. C. Carlson, Jr.; and (4) Ionospheric Heating by Powerful Radio Waves; Meltz et al., all published in Radio Science, Vol. 9, No. 11, November, 1974, at pages 885–888; 889–894; 1041–1047; and 1049–1063, respectively, all of which are incorporated herein by reference. In such experiments, certain regions of the ionosphere are heated to change the electron density and temperature within these regions. This is accomplished by transmitting from earth-based antennae high frequency electromagnetic radiation at a substantial angle to, not parallel to, the ionosphere's magnetic field to heat the ionospheric particles primarily by ohmic heating. The electron temperature of the ionosphere has been raised by hundreds of degrees in these experiments, and electrons with several electron volts of energy have been produced in numbers sufficient to enhance airglow. Electron concentrations have been reduced by a few percent, due to expansion of the plasma as a result of increased temperature.

In the Elmo Bumpy Torus (EBT), a controlled fusion device at the Oak Ridge National Laboratory, all heating is provided by microwaves at the electron cyclotron resonance interaction. A ring of hot electrons is formed at the earth's surface in the magnetic mirror by a combination of electron cyclotron resonance and stochastic heating. In the EBT, the ring electrons are produced with an average "temperature" of 250 kilo electron volts or kev (2.5×10^9K) and a plasma beta between 0.1 and 0.4; see, "A Theoretical Study of Electron—Cyclotron Absorption in Elmo Bumpy Torus", Batchelor and Goldfinger, Nuclear Fusion, Vol. 20, No. 4 (1980) pps. 403–418.

Electron cyclotron resonance heating has been used in experiments on the earth's surface to produce and accelerate plasmas in a diverging magnetic field. Kosmahl et al. showed that power was transferred from the electromagnetic waves and that a fully ionized plasma

was accelerated with a divergence angle of roughly 13 degrees. Optimum neutral gas density was 1.7×10^{14} per cubic centimeter; see, "Plasma Acceleration with Microwaves Near Cyclotron Resonance", Kosmahl et al., Journal of Applied Physics, Vol. 38, No. 12, Nov., 1967, pps. 4576–4582.

DISCLOSURE OF THE INVENTION

The present invention provides a method and apparatus for altering at least one selected region which normally exists above the earth's surface. The region is excited by electron cyclotron resonance heating of electrons which are already present and/or artifically created in the region to thereby increase the charged particle energy and ultimately the density of the region.

In one embodiment this is done by transmitting circularly polarized electromagnetic radiation from the earth's surface at or near the location where a naturally-occurring dipole magnetic field (force) line intersects the earth's surface. Right hand circular polarization is used in the northern hemisphere and left hand circular polarization is used in the southern hemisphere. The radiation is deliberately transmitted at the outset in a direction substantially parallel to and along a field line which extends upwardly through the region to be altered. The radiation is transmitted at a frequency which is based on the gyrofrequency of the charged particles and which, when applied to the at least one region, excites electron cyclotron resonance within the region or regions to heat and accelerate the charged particles in their respective helical paths around and along the field line. Sufficient energy is employed to cause ionization of neutral particles (molecules of oxygen, nitrogen and the like, particulates, etc.) which then become a part of the region thereby increasing the charged particle density of the region. This effect can further be enhanced by providing artificial particles, e.g., electrons, ions, etc., directly into the region to be affected from a rocket, satellite, or the like to supplement the particles in the naturally-occurring plasma. These artificial particles are also ionized by the transmitted electromagnetic radiation thereby increasing charged particle density of the resulting plasma in the region.

In another embodiment of the invention, electron cyclotron resonance heating is carried out in the selected region or regions at sufficient power levels to allow a plasma present in the region to generate a mirror force which forces the charged electrons of the altered plasma upward along the force line to an altitude which is higher than the original altitude. In this case the relevant mirror points are at the base of the altered region or regions. The charged electrons drag ions with them as well as other particles that may be present. Sufficient power, e.g., 10^{15} joules, can be applied so that the altered plasma can be trapped on the field line between mirror points and will oscillate in space for prolonged periods of time. By this embodiment, a plume of altered plasma can be established at selected locations for communication modification or other purposes.

In another embodiment, this invention is used to alter at least one selected region of plasma in the ionosphere to establish a defined layer of plasma having an increased charged particle density. Once this layer is established, and while maintaining the transmission of the main beam of circularly polarized electromagnetic radiation, the main beam is modulated and/or at least one second different, modulated electromagnetic radiation beam is transmitted from at least one separate source at a different frequency which will be absorbed in the plasma layer. The amplitude of the frequency of the main beam and/or the second beam or beams is modulated in resonance with at least one known oscillation mode in the selected region or regions to excite the known oscillation mode to propagate a known frequency wave or waves throughout the ionosphere.

BRIEF DESCRIPTION OF THE DRAWINGS

The actual construction, operation, and apparent advantages of this invention will be better understood by referring to the drawings in which like numerals identify like parts and in which:

FIG. **1** is a simplified schematical view of the earth (not to scale) with a magnetic field (force) line along which the present invention is carried out;

FIG. **2** is one embodiment within the present invention in which a selected region of plasma is raised to a higher altitude;

FIG. **3** is a simplified, idealized representation of a physical phenomenon involved in the present invention; and

FIG. **4** is a schematic view of another embodiment within the present invention.

FIG. **5** is a schematic view of an apparatus embodiment within this invention.

BEST MODES FOR CARRYING OUT THE INVENTION

The earth's magnetic field is somewhat analogous to a dipole bar magnet. As such, the earth's magnetic field contains numerous divergent field or force lines, each line intersecting the earth's surface at points on opposite sides of the Equator. The field lines which intersect the earth's surface near the poles have apexes which lie at the furthest points in the earth's magnetosphere while those closest to the Equator have apexes which reach only the lower portion of the magnetosphere.

At various altitudes above the earth's surface, e.g., in both the ionosphere and the magnetosphere, plasma is naturally present along these field lines. This plasma consists of equal numbers of positively and negatively charged particles (i.e., electrons and ions) which are guided by the field line. It is well established that a charged particle in a magnetic field gyrates about field lines, the center of gyration at any instance being called the "guiding center" of the particle. As the gyrating particle moves along a field line in a uniform field, it will follow a helical path about its guiding center, hence linear motion, and will remain on the field line. Electrons and ions both follow helical paths around a field line but rotate in opposite directions. The frequencies at which the electrons and ions rotate about the field line are called gyromagnetic frequencies or cyclotron frequencies because they are identical with the expression for the angular frequencies of gyration of particles in a cyclotron. The cyclotron frequency of ions in a given magnetic field is less than that of electrons, in inverse proportion to their masses.

If the particles which form the plasma along the earth's field lines continued to move with a constant pitch angle, often designated "alpha", they would soon impact on the earth's surface. Pitch angle alpha is defined as the angle between the direction of the earth's magnetic field and the velocity (V) of the particle. However, in converging force fields, the pitch angle does change in such a way as to allow the particle to

turn around and avoid impact. Consider a particle moving along a field line down toward the earth. It moves into a region of increasing magnetic field strength and therefore sine alpha increases. But sine alpha can only increase to 1.0, at which point, the particle turns around and starts moving up along the field line, and alpha decreases. The point at which the particle turns around is called the mirror point, and there alpha equals ninety degrees. This process is repeated at the other end of the field line where the same magnetic field strength value B, namely Bm, exists. The particle again turns around and this is called the "conjugate point" of the original mirror point. The particle is therefore trapped and bounces between the two magnetic mirrors. The particle can continue oscillating in space in this manner for long periods of time. The actual place where a particle will mirror can be calculated from the following:

$$\sin^2 \text{alpha}_o = B_o/B_m \qquad (1)$$

wherein:

alpha$_o$ = equatorial pitch angle of particle

B$_o$ = equatorial field strength on a particular field line

B$_m$ = field strength at the mirror point

Recent discoveries have established that there are substantial regions of naturally trapped particles in space which are commonly called "trapped radiation belts". These belts occur at altitudes greater than about 500 km and accordingly lie in the magnetosphere and mostly above the ionosphere.

The ionosphere, while it may overlap some of the trapped-particle belts, is a region in which hydrostatic forces govern its particle distribution in the gravitational field. Particle motion within the ionosphere is governed by both hydrodynamic and electrodynamic forces. While there are few trapped particles in the ionosphere, nevertheless, plasma is present along field lines in the ionosphere. The charged particles which form this plasma move between collisions with other particles along similar helical paths around the field lines and although a particular particle may diffuse downward into the earth's lower atmosphere or lose energy and diverge from its original field line due to collisions with other particles, these charged particles are normally replaced by other available charged particles or by particles that are ionized by collision with said particle. The electron density (N_e) of the plasma will vary with the actual conditions and locations involved. Also, neutral particles, ions, and electrons are present in proximity to the field lines.

The production of enhanced ionization will also alter the distribution of atomic and molecular constituents of the atmosphere, most notably through increased atomic nitrogen concentration. The upper atmosphere is normally rich in atomic oxygen (the dominant atmospheric constituent above 200 km altitude), but atomic nitrogen is normally relatively rare. This can be expected to manifest itself in increased airglow, among other effects.

As known in plasma physics, the characteristics of a plasma can be altered by adding energy to the charged particles or by ionizing or exciting additional particles to increase the density of the plasma. One way to do this is by heating the plasma which can be accomplished in different ways, e.g., ohmic, magnetic compression, shock waves, magnetic pumping, electron cyclotron resonance, and the like.

Since electron cyclotron resonance heating is involved in the present invention, a brief discussion of same is in order. Increasing the energy of electrons in a plasma by invoking electron cyclotron resonance heating, is based on a principle similar to that utilized to accelerate charged particles in a cyclotron. If a plasma is confined by a static axial magnetic field of strength B, the charged particles will gyrate about the lines of force with a frequency given, in hertz, as $f_g = 1.54 \times 10^3 B/A$, where: B = magnetic field strength in gauss, and A = mass number of the ion.

Suppose a time-varying field of this frequency is superimposed on the static field B confining the plasma, by passage of a radiofrequency current through a coil which is concentric with that producing the axial field, then in each half-cycle of their rotation about the field lines, the charged particles acquire energy from the oscillating electric field associated with the radio frequency. For example, if B is 10,000 gauss, the frequency of the field which is in resonance with protons in a plasma is 15.4 megahertz.

As applied to electrons, electron cyclotron resonance heating requires an oscillating field having a definite frequency determined by the strength of the confining field. The radio-frequency radiation produces time-varying fields (electric and magnetic), and the electric field accelerates the charged particle. The energized electrons share their energy with ions and neutrals by undergoing collisions with these particles, thereby effectively raising the temperature of the electrons, ions, and neutrals. The apportionment of energy among these species is determined by collision frequencies. For a more detailed understanding of the physics involved, see "Controlled Thermonuclear Reactions", Glasstone and Lovberg, D. Van Nostrand Company, Inc., Princeton, N.J., 1960 and "The Radiation Belt and Magnetosphere", Hess, Blaisdell Publishing Company, 1968, both of which are incorporated herein by reference.

Referring now to the drawings, the present invention provides a method and apparatus for altering at least one region of plasma which lies along a field line, particularly when it passes through the ionosphere and/or magnetosphere. FIG. **1** is a simplified illustration of the earth **10** and one of its dipole magnetic force or field lines **11**. As will be understood, line **11** may be any one of the numerous naturally existing field lines and the actual geographical locations **13** and **14** of line **11** will be chosen based on a particular operation to be carried out. The actual locations at which field lines intersect the earth's surface is documented and is readily ascertainable by those skilled in the art.

Line **11** passes through region R which lies at an altitude above the earth's surface. A wide range of altitudes are useful given the power that can be employed by the practice of this invention. The electron cyclotron resonance heating effect can be made to act on electrons anywhere above the surface of the earth. These electrons may be already present in the atmosphere, ionosphere, and/or magnetosphere of the earth, or can be artificially generated by a variety of means such as x-ray beams, charged particle beams, lasers, the plasma sheath surrounding an object such as a missile or meteor, and the like. Further, artificial particles, e.g., electrons, ions, etc., can be injected directly into region R from an earth-launched rocket or orbiting satellite carrying, for example, a payload of radioactive beta-decay material; alpha emitters; an electron accelerator; and/or ionized gases such as hydrogen; see U.S. Pat. No. 4,042,196. The altitude can be greater than about 50 km if desired,

e.g., can be from about 50 km to about 800 km, and, accordingly may lie in either the ionosphere or the magnetosphere or both. As explained above, plasma will be present along line **11** within region R and is represented by the helical line **12**. Plasma **12** is comprised of charged particles (i.e., electrons and ions) which rotate about opposing helical paths along line **11**.

Antenna **15** is positioned as close as is practical to the location **14** where line **11** intersects the earth's surface. Antenna **15** may be of any known construction for high directionality, for example, a phased array, beam spread angle (θ) type. See "The MST Radar at Poker Flat, Alaska", Radio Science, Vol. 15, No. 2, Mar.-Apr. 1980, pps. 213–223, which is incorporated herein by reference. Antenna **15** is coupled to transmitter **16** which generates a beam of high frequency electromagnetic radiation at a wide range of discrete frequencies, e.g., from about 20 to about 1800 kilohertz (kHz).

Transmitter **16** is powered by power generator means **17** which is preferably comprised of one or more large, commercial electrical generators. Some embodiments of the present invention require large amounts of power, e.g., up to 10^9 to 10^{11} watts, in continuous wave or pulsed power. Generation of the needed power is within the state of the art. Although the electrical generators necessary for the practice of the invention can be powered in any known manner, for example, by nuclear reactors, hydroelectric facilities, hydrocarbon fuels, and the like, this invention, because of its very large power requirement in certain applications, is particularly adapted for use with certain types of fuel sources which naturally occur at strategic geographical locations around the earth. For example, large reserves of hydrocarbons (oil and natural gas) exist in Alaska and Canada. In northern Alaska, particularly the North Slope region, large reserves are currently readily available. Alaska and northern Canada also are ideally located geographically as to magnetic latitudes. Alaska provides easy access to magnetic field lines that are especially suited to the practice of this invention, since many field lines which extend to desirable altitudes for this invention intersect the earth in Alaska. Thus, in Alaska, there is a unique combination of large, accessible fuel sources at desirable field line intersections. Further, a particularly desirable fuel source for the generation of very large amounts of electricity is present in Alaska in abundance, this source being natural gas. The presence of very large amounts of clean-burning natural gas in Alaskan latitudes, particularly on the North Slope, and the availability of magnetohydrodynamic (MHD), gas turbine, fuel cell, electrogasdynamic (EGD) electric generators which operate very efficiently with natural gas provide an ideal power source for the unprecedented power requirements of certain of the applications of this invention. For a more detailed discussion of the various means for generating electricity from hydrocarbon fuels, see "Electrical Aspects of Combustion", Lawton and Weinberg, Clarendon Press, 1969. For example, it is possible to generate the electricity directly at the high frequency needed to drive the antenna system. To do this, typically the velocity of flow of the combustion gases (v), past magnetic field perturbation of dimension d (in the case of MHD), follow the rule:

$$v = df$$

where f is the frequency at which electricity is generated. Thus, if $v = 1.78 \times 10^6$ cm/sec and d=1 cm then electricity would be generated at a frequency of 1.78 mHz.

Put another way, in Alaska, the right type of fuel (natural gas) is naturally present in large amounts and at just the right magnetic latitudes for the most efficient practice of this invention, a truly unique combination of circumstances. Desirable magnetic latitudes for the practice of this invention interest the earth's surface both northerly and southerly of the equator, particularly desirable latitudes being those, both northerly and southerly, which correspond in magnitude with the magnetic latitudes that encompass Alaska.

Referring now to FIG. 2 a first ambodiment is illustrated where a selected region R_1 of plasma **12** is altered by electron cyclotron resonance heating to accelerate the electrons of plasma **12**, which are following helical paths along field line **11**.

To accomplish this result, electromagnetic radiation is transmitted at the outset, essentially parallel to line **11** via antenna **15** as right hand circularly polarized radiation wave **20**. Wave **20** has a frequency which will excite electron cyclotron resonance with plasma **12** at its initial or original altitude. This frequency will vary depending on the electron cyclotron resonance of region R_1 which, in turn, can be determined from available data based on the altitudes of region R_1, the particular field line **11** being used, the strength of the earth's magnetic field, etc. Frequencies of from about 20 to about 7200 kHz, preferably from about 20 to about 1800 kHz can be employed. Also, for any given application, there will be a threshhold (minimum power level) which is needed to produce the desired result. The minimum power level is a function of the level of plasma production and movement required, taking into consideration any loss processes that may be dominant in a particular plasma or propagation path.

As electron cyclotron resonance is established in plasma **12**, energy is transferred from the electromagnetic radiation **20** into plasma **12** to heat and accelerate the electrons therein and, subsequently, ions and neutral particles. As this process continues, neutral particles which are present within R_1 are ionized and absorbed into plasma **12** and this increases the electron and ion densities of plasma **12**. As the electron energy is raised to values of about 1 kilo electron volt (kev), the generated mirror force (explained below) will direct the excited plasma **12** upward along line **11** to form a plume R_2 at an altitude higher than that of R_1.

Plasma acceleration results from the force on an electron produced by a nonuniform static magnetic field ($\overline{B}$). The force, called the mirror force, is given by

$$F = -\mu \nabla B \qquad (2)$$

where μ is the electron magnetic moment and $\nabla \overline{B}$ is the gradient of the magnetic field, μ being further defined as:

$$W_{\perp}/B = mV_{\perp}^2/2B$$

where $W_{\perp}$ is the kinetic energy in the direction perpendicular to that of the magnetic field lines and B is the magnetic field strength at the line of force on which the guiding center of the particle is located. The force as represented by equation (2) is the force which is responsible for a particle obeying equation (1).

Since the magnetic field is divergent in region R_1, it can be shown that the plasma will move upwardly from the heating region as shown in FIG. **1** and further it can be shown that

$$\tfrac{1}{2}M_eV_{e\perp}^2(x) \approx \tfrac{1}{2}M_eV_{e\perp}^2(Y) + \tfrac{1}{2}M_iV_{i\parallel}^2(Y) \quad (3)$$

where the left hand side is the initial electron transverse kinetic energy; the first term on the right is the transverse electron kinetic energy at some point (Y) in the expanded field region, while the final term is the ion kinetic energy parallel to B at point (Y). This last term is what constitutes the desired ion flow. It is produced by an electrostatic field set up by electrons which are accelerated according to Equation (2) in the divergent field region and pulls ions along with them. Equation (3) ignores electron kinetic energy parallel to B because $V_{e\parallel} \approx V_{i\parallel}$, so the bulk of parallel kinetic energy resides in the ions because of their greater masses. For example, if an electromagnetic energy flux of from about 1 to about 10 watts per square centimeter is applied to region R, whose altitude is 115 km, a plasma having a density (N_e) of 10^{12} per cubic centimeter will be generated and moved upward to region R_2 which has an altitude of about 1000 km. The movement of electrons in the plasma is due to the mirror force while the ions are moved by ambipolar diffusion (which results from the electrostatic field). This effectively "lifts" a layer of plasma **12** from the ionosphere and/or magnetosphere to a higher elevation R_2. The total energy required to create a plasma with a base area of 3 square kilometers and a height of 1000 km is about 3×10^{13} joules.

FIG. **3** is an idealized representation of movement of plasma **12** upon excitation by electron cyclotron resonance within the earth's divergent force field. Electrons (e) are accelerated to velocities required to generate the necessary mirror force to cause their upward movement. At the same time neutral particles (n) which are present along line **11** in region $R_1$are ionized and become part of plasma **12**. As electrons (e) move upward along line **11**, they drag ions (i) and neutrals (n) with them but at an angle θ of about 13 degrees to field line **11**. Also, any particulates that may be present in region R_1, will be swept upwardly with the plasma. As the charged particles of plasma **12** move upward, other particles such as neutrals within or below R_1, move in to replace the upwardly moving particles. These neutrals, under some conditions, can drag with them charged particles.

For example, as a plasma moves upward, other particles at the same altitude as the plasma move horizontally into the region to replace the rising plasma and to form new plasma. The kinetic energy developed by said other particles as they move horizontally is, for example, on the same order of magnitude as the total zonal kinetic energy of stratospheric winds known to exist.

Referring again to FIG. **2**, plasma **12** in region R_1 is moved upward along field line **11**. The plasma **12** will then form a plume (cross-hatched area in FIG. **2**) which will be relatively stable for prolonged periods of time. The exact period of time will vary widely and be determined by gravitational forces and a combination of radiative and diffusive loss terms. In the previous detailed example, the calculations were based on forming a plume by producing 0+energies of 2 ev/particle. About 10 ev per particle would be required to expand plasma **12** to apex point C (FIG. **1**). There at least some of the particles of plasma **12** will be trapped and will oscillate between mirror points along field line **11**. This oscillation will then allow additional heating of the trapped plasma **12** by stochastic heating which is associated with trapped and oscillating particles. See "A New Mechanism for Accelerating Electrons in the Outer Ionosphere" by R. A. Helliwell and T. F. Bell, Journal of Geophysical Research, Vol. 65, No. 6, June, 1960. This is preferably carried out at an altitude of at least 500 km.

The plasma of the typical example might be employed to modify or disrupt microwave transmissions of satellites. If less than total black-out of transmission is desired (e.g., scrambling by phase shifting digital signals), the density of the plasma (N_e) need only be at least about 10^6 per cubic centimeter for a plasma orginating at an altitude of from about 250 to about 400 km and accordingly less energy (i.e., electromagnetic radiation), e.g., 10^8 joules need be provided. Likewise, if the density $N_e$is on the order of 10^8, a properly positioned plume will provide a reflecting surface for VHF waves and can be used to enhance, interfere with, or otherwise modify communication transmissions. It can be seen from the foregoing that by appropriate application of various aspects of this invention at strategic locations and with adequate power sources, a means and method is provided to cause interference with or even total disruption of communications over a very large portion of the earth. This invention could be employed to disrupt not only land based communications, both civilian and military, but also airborne communications and sea communications (both surface and subsurface). This would have significant military implications, particularly as a barrier to or confusing factor for hostile missiles or airplanes. The belt or belts of enhanced ionization produced by the method and apparatus of this invention, particularly if set up over Northern Alaska and Canada, could be employed as an early warning device, as well as a communications disruption medium. Further, the simple ability to produce such a situation in a practical time period can by itself be a deterring force to hostile action. The ideal combination of suitable field lines intersecting the earth's surface at the point where substantial fuel sources are available for generation of very large quantitities of electromagnetic power, such as the North Slope of Alaska, provides the wherewithal to accomplish the foregoing in a practical time period, e.g., strategic requirements could necessitate achieving the desired altered regions in time periods of two minutes or less and this is achievable with this invention, especially when the combination of natural gas and magnetohydrodynamic, gas turbine, fuel cell and/or EGD electric generators are employed at the point where the useful field lines intersect the earth's surface. One feature of this invention which satisfies a basic requirement of a weapon system, i.e., continuous checking of operability, is that small amounts of power can be generated for operability checking purposes. Further, in the exploitation of this invention, since the main electromagnetic beam which generates the enhanced ionized belt of this invention can be modulated itself and/or one or more additional electromagnetic radiation waves can be impinged on the ionized region formed by this invention as will be described in greater detail herein after with respect to FIG. **4**, a substantial amount of randomly modulated signals of very large power magnitude can be generated in a highly nonlinear mode. This can cause confusion of or interference with or even complete disruption of guidance systems employed by

even the most sophisticated of airplanes and missiles. The ability to employ and transmit over very wide areas of the earth a plurality of electromagnetic waves of varying frequencies and to change same at will in a random manner, provides a unique ability to interfere with all modes of communications, land, sea, and/or air, at the same time. Because of the unique juxtaposition of usable fuel source at the point where desirable field lines intersect the earth's surface, such wide ranging and complete communication interference can be achieved in a resonably short period of time. Because of the mirroring phenomenon discussed hereinabove, it can also be prolonged for substantial time periods so that it would not be a mere transient effect that could simply be waited out by an opposing force. Thus, this invention provides the ability to put unprecedented amounts of power in the earth's atmosphere at strategic locations and to maintain the power injection level, particularly if random pulsing is employed, in a manner far more precise and better controlled than heretofore accomplished by the prior art, particularly by the detonation of nuclear devices of various yeilds at various altitudes. Where the prior art approaches yielded merely transitory effects, the unique combination of fuel and desirable field lines at the point where the fuel occurs allows the establishment of, compared to prior art approaches, precisely controlled and long-lasting effects which cannot, practically speaking, simply be waited out. Further, by knowing the frequencies of the various electromagnetic beams employed in the practice of this invention, it is possible not only to interfere with third party communications but to take advantage of one or more such beams to carry out a communications network even though the rest of the world's communications are disrupted. Put another way, what is used to disrupt another's communications can be employed by one knowledgeable of this invention as a communications network at the same time. In addition, once one's own communication network is established, the far-reaching extent of the effects of this invention could be employed to pick up communication signals of other for intelligence purposes. Thus, it can be seen that the disrupting effects achievable by this invention can be employed to benefit by the party who is practicing this invention since knowledge of the various electromagnetic waves being employed and how they will vary in frequency and magnitude can be used to an advantage for positive communication and eavesdropping purposes at the same time. However, this invention is not limited to locations where the fuel source naturally exists or where desirable field lines naturally intersect the earth's surface. For example, fuel, particularly hydrocarbon fuel, can be transported by pipeline and the like to the location where the invention is to be practiced.

FIG. 4 illustrates another embodiment wherein a selected region of plasma R_3which lies within the earth's ionosphere is altered to increase the density thereof whereby a relatively stable layer **30** of relatively dense plasma is maintained within region R_3. Electromagnetic radiation is transmitted at the outset essentially parallel to field line **11** via antenna **15** as a right hand circularly polarized wave and at a frequency (e.g., 1.78 megahertz when the magnetic field at the desired altitude is 0.66 gauss) capable of exciting electron cyclotron resonance in plasma **12** at the particular altitude of plasma **12**. This causes heating of the particles (electrons, ions, neutrals, and particulates) and ionization of the uncharged particles adjacent line **11**, all of which are absorbed into plasma **12** to increase the density thereof. The power transmitted, e.g., 2×10^6 watts for up to 2 minutes heating time, is less than that required to generate the mirror force F required to move plasma **12** upward as in the previous embodiment.

While continuing to transmit electromagnetic radiation **20** from antenna **15**, a second electromagnetic radiation beam **31**, which is at a defined frequency different from the radiation from antenna **15**, is transmitted from one or more second sources via antenna **32** into layer **30** and is absorbed into a portion of layer **30** (cross-hatched area in FIG. 4). The electromagnetic radiation wave from antenna **32** is amplitude modulated to match a known mode of oscillation f_3 in layer **30**. This creates a resonance in layer **30** which excites a new plasma wave **33** which also has a frequency of f_3 and which then propogates through the ionosphere. Wave **33** can be used to improve or disrupt communications or both depending on what is desired in a particular application. Of course, more than one new wave **33** can be generated and the various new waves can be modulated at will and in a highly nonlinear fashion.

FIG. **5** shows apparatus useful in this invention, particularly when those applications of this invention are employed which require extremely large amounts of power. In FIG. **5** there is shown the earth's surface **40** with a well **41** extending downwardly thereinto until it penetrates hydrocarbon producing reservoir **42**. Hydrocarbon reservoir **42** produces natural gas alone or in combination with crude oil. Hydrocarbons are produced from reservoir **42** through well **41** and wellhead **43** to a treating system **44** by way of pipe **45**. In treater **44**, desirable liquids such as crude oil and gas condensates are separated and recovered by way of pipe **46** while undesirable gases and liquids such as water, H_2S, and the like are separated by way of pipe **47**. Desirable gases such as carbon dioxide are separated by way of pipe **48**, and the remaining natural gas stream is removed from treater **44** by way of pipe **49** for storage in conventional tankage means (not shown) for future use and/or use in an electrical generator such as a magnetohydrodynamic, gas turbine, fuel cell or EGD generator **50**. Any desired number and combination of different types of electric generators can be employed in the practice of this invention. The natural gas is burned in generator **50** to produce substantial quantities of electricity which is then stored and/or passed by way of wire **51** to a transmitter **52** which generates the electromagnetic radiation to be used in the method of this invention. The electromagnetic radiation is then passed by way of wire **53** to antenna **54** which is located at or near the end of field line **11**. Antenna **54** sends circularly polarized radiation wave **20** upwards along field line **11** to carry out the various methods of this invention as described hereinabove.

Of course, the fuel source need not be used in its naturally-occurring state but could first be converted to another second energy source form such as hydrogen, hydrazine and the like, and electricity then generated from said second energy source form.

It can be seen from the foregoing that when desirable field line **11** intersects earth's surface **40** at or near a large naturally-occurring hydrocarbon source **42**, exceedingly large amounts of power can be very efficiently produced and transmitted in the direction of field lines. This is particularly so when the fuel source is natural gas and magnetohydrodynamic generators are employed. Further, this can all be accomplished in a

relatively small physical area when there is the unique coincidence of fuel source **42** and desirable field line **11**. Of course, only one set of equipment is shown in FIG. **5** for sake of simplicity. For a large hydrocarbon reservoir **42**, a plurality of wells **41** can be employed to feed one or more storage means and/or treaters and as large a number of generators **55** as needed to power one or more transmitters **52** and one or more antennas **54**. Since all of the apparatus **44** through **54** can be employed and used essentially at the sight where naturally-occurring fuel source **42** is located, all the necessary electromagnetic radiation **20** is generated essentially at the same location as fuel source **42**. This provides for a maximum amount of usable electromagnetic radiation **20** since there are no significant storage or transportation losses to be incurred. In other words, the apparatus is brought to the sight of the fuel source where desirable field line **11** intersects the earth's surface **40** on or near the geographical location of fuel source **42**, fuel source **42** being at a desirable magnetic latitude for the practice of this invention, for example, Alaska.

The generation of electricity by motion of a conducting fluid through a magnetic field, i.e., magnetohydrodynamics (MHD), provides a method of electric power generation without moving mechanical parts and when the conducting fluid is a plasma formed by combustion of a fuel such as natural gas, an idealized combination of apparatus is realized since the very clean-burning natural gas forms the conducting plasma in an efficient manner and the thus formed plasma, when passed through a magnetic field, generates electricity in a very efficient manner. Thus, the use of fuel source **42** to generate a plasma by combustion thereof for the generation of electricity essentially at the site of occurrence of the fuel source is unique and ideal when high power levels are required and desirable field lines **11** intersect the earth's surface **40** at or near the site of fuel source **42**. A particular advantage for MHD generators is that they can be made to generate large amounts of power with a small volume, light weight device. For example, a 1000 megawatt MHD generator can be construed using superconducting magnets to weigh roughly 42,000 pounds and can be readily air lifted.

This invention has a phenomenal variety of possible ramifications and potential future developments. As alluded to earlier, missile or aircraft destruction, deflection, or confusion could result, particularly when relativistic particles are employed. Also, large regions of the atmosphere could be lifted to an unexpectedly high altitude so that missiles encounter unexpected and unplanned drag forces with resultant destruction or deflection of same. Weather modification is possible by, for example, altering upper atmosphere wind patterns or altering solar absorption patterns by constructing one or more plumes of atmospheric particles which will act as a lens or focusing device. Also as alluded to earlier, molecular modifications of the atmosphere can take place so that positive environmental effects can be achieved. Besides actually changing the molecular composition of an atmospheric region, a particular molecule or molecules can be chosen for increased presence. For example, ozone, nitrogen, etc. concentrations in the atmosphere could be artificially increased. Similarly, environmental enhancement could be achieved by causing the breakup of various chemical entities such as carbon dioxide, carbon monoxide, nitrous oxides, and the like. Transportation of entities can also be realized when advantage is taken of the drag effects caused by regions of the atmosphere moving up along diverging field lines. Small micron sized particles can be then transported, and, under certain circumstances and with the availability of sufficient energy, larger particles or objects could be similarly affected. Particles with desired characteristics such as tackiness, reflectivity, absorptivity, etc., can be transported for specific purposes or effects. For example, a plume of tacky particles could be established to increase the drag on a missile or satellite passing therethrough. Even plumes of plasma having substantially less charged particle density than described above will produce drag effects on missiles which will affect a lightweight (dummy) missile in a manner substantially different than a heavy (live) missile and this affect can be used to distinguish between the two types of missiles. A moving plume could also serve as a means for supplying a space station or for focusing vast amount of sunlight on selected portions of the earth. Surveys of global scope could also be realized because the earth's natural magnetic field could be significantly altered in a controlled manner by plasma beta effects resulting in, for example, improved magnetotelluric surveys. Electromagnetic pulse defenses are also possible. The earth's magnetic field could be decreased or disrupted at appropriate altitudes to modify or eliminate the magnetic field in high Compton electron generation (e.g., from high altitude nuclear bursts) regions. High intensity, well controlled electrical fields can be provided in selected locations for various purposes. For example, the plasma sheath surrounding a missile or satellite could be used as a trigger for activating such a high intensity field to destroy the missile or satellite. Further, irregularities can be created in the ionosphere which will interfere with the normal operation of various types of radar, e.g., synthetic aperture radar. The present invention can also be used to create artificial belts of trapped particles which in turn can be studied to determine the stability of such parties. Still further, plumes in accordance with the present invention can be formed to simulate and/or perform the same functions as performed by the detonation of a "heave" type nuclear device without actually having to detonate such a device. Thus it can be seen that the ramifications are numerous, far-reaching, and exceedingly varied in usefulness.

I claim:

1. A method for altering at least one region normally existing above the earth's surface with electromagnetic radiation using naturally-occurring and diverging magnetic field lines of the earth comprising transmitting first electromagnetic radiation at a frequency between 20 and 7200 kHz from the earth's surface, said transmitting being conducted essentially at the outset of transmission substantially parallel to and along at least one of said field lines, adjusting the frequency of said first radiation to a value which will excite electron cyclotron resonance at an initial elevation at least 50 km above the earth's surface, whereby in the region in which said electron cyclotron resonance takes place heating, further ionization, and movement of both charged and neutral particles is effected, said cyclotron resonance excitation of said region is continued until the electron concentration of said region reaches a value of at least 10^6 per cubic centimeter and has an ion energy of at least 2 ev.

2. The method of claim **1** including the step of providing artificial particles in said at least one region which are excited by said electron cyclotron resonance.

3. The method of claim **2** wherein said artificial particles are provided by injecting same into said at least one region from an orbiting satellite.

4. The method of claim **1** wherein said threshold excitation of electron cyclotron resonance is about 1 watt per cubic centimeter and is sufficient to cause movement of a plasma region along said diverging magnetic field lines to an altitude higher than the altitude at which said excitation was initiated.

5. The method of claim **4** wherein said rising plasma region pulls with it a substantial portion of neutral particles of the atmosphere which exist in or near said plasma region.

6. The method of claim **1** wherein there is provided at least one separate source of second electromagnetic radiation, said second radiation having at least one frequency different from said first radiation, impinging said at least one second radiation on said region while said region is undergoing electron cyclotron resonance excitation caused by said first radiation.

7. The method of claim **6** wherein said second radiation has a frequency which is absorbed by said region.

8. The method of claim **6** wherein said region is plasma in the ionosphere and said second radiation excites plasma waves within said ionosphere.

9. The method of claim **8** wherein said electron concentration reaches a value of at least 10^{12} per cubic centimeter.

10. The method of claim **8** wherein said excitation of electron cyclotron resonance is initially carried out within the ionosphere and is continued for a time sufficient to allow said region to rise above said ionosphere.

11. The method of claim **1** wherein said excitation of electron cyclotron resonance is carried out above about 500 kilometers and for a time of from 0.1 to 1200 seconds such that multiple heating of said plasma region is achieved by means of stochastic heating in the magnetosphere.

12. The method of claim **1** wherein said first electromagnetic radiation is right hand circularly polarized in the northern hemisphere and left hand circularly polarized in the southern hemisphere.

13. The method of claim **1** wherein said electromagnetic radiation is generated at the site of a naturally-occurring hydrocarbon fuel source, said fuel source being located in at least one of northerly or southerly magnetic latitudes.

14. The method of claim **13** wherein said fuel source is natural gas and electricity for generating said electromagnetic radiation is obtained by burning said natural gas in at least one of magnetohydrodynamic, gas turbine, fuel cell, and EGD electric generators located at the site where said natural gas naturally occurs in the earth.

15. The method of claim **14** wherein said site of natural gas is within the magnetic latitudes that encompass Alaska.

* * * * *

United States Patent [19]
Eastlund

[11] **Patent Number:** **4,686,605**
[45] **Date of Patent:** **Aug. 11, 1987**

[54] METHOD AND APPARATUS FOR ALTERING A REGION IN THE EARTH'S ATMOSPHERE, IONOSPHERE, AND/OR MAGNETOSPHERE

[75] Inventor: **Bernard J. Eastlund**, Spring, Tex.
[73] Assignee: **APTI, Inc.**, Los Angeles, Calif.
[21] Appl. No.: **690,333**
[22] Filed: **Jan. 10, 1985**
[51] **Int. Cl.**⁴ **H05B 6/64;** H05C 3/00; H05H 1/46
[52] **U.S. Cl.** .... **361/231;** 89/1.11; 380/59; 244/158 R
[58] **Field of Search** .... 361/230, 231; 244/158 R; 376/100; 89/1.11; 380/59

[56] **References Cited**

PUBLICATIONS

Liberty Magazine, (2/35) p. 7 N. Tesla.
New York Times (9/22/40) Section 2, p. 7 W. L. Laurence.
New York Times (12/8/15) p. 8 Col. 3.

Primary Examiner—Salvatore Cangialosi
Attorney, Agent, or Firm—Roderick W. MacDonald

[57] **ABSTRACT**

A method and apparatus for altering at least one selected region which normally exists above the earth's surface. The region is excited by electron cyclotron resonance heating to thereby increase its charged particle density. In one embodiment, circularly polarized electromagnetic radiation is transmitted upward in a direction substantially parallel to and along a field line which extends through the region of plasma to be altered. The radiation is transmitted at a frequency which excites electron cyclotron resonance to heat and accelerate the charged particles. This increase in energy can cause ionization of neutral particles which are then absorbed as part of the region thereby increasing the charged particle density of the region.

15 Claims, 5 Drawing Figures



FIG. 1


11
MB
NORTH POLE
10
20
12
15
TRANSMITTER 16
14
POWER GENERATOR 17
C
EQUATOR
13
R
MB
SOUTH POLE

FIG. 2


R2
MB1
[F=-μ•∇B]
R1

FIG. 3


[F = -μ·∇B]
R2
11
θ
e
i
n
i
i
i
i
12
R1
e
n
i
10

FIG. 4


30
R3
11
12
f3
33
20
15
31
10
32


TREATER
MHD GENERATOR
TRANSMITTER

FIG. 5

METHOD AND APPARATUS FOR ALTERING A REGION IN THE EARTH'S ATMOSPHERE, IONOSPHERE, AND/OR MAGNETOSPHERE

DESCRIPTION

1. Technical Field

This invention relates to a method and apparatus for altering at least one selected region normally existing above the earth's surface and more particularly relates to a method and apparatus for altering said at least one region by initially transmitting electromagnetic radiation from the earth's surface essentially parallel to and along naturally-occurring, divergent magnetic field lines which extend from the earth's surface through the region or regions to be altered.

2. Background Art

In the late 1950's, it was discovered that naturally-occuring belts exist at high altitudes above the earth's surface, and it is now established that these belts result from charged electrons and ions becoming trapped along the magnetic lines of force (field lines) of the earth's essentially dipole magnetic field. The trapped electrons and ions are confined along the field lines between two magnetic mirrors which exist at spaced apart points along those field lines. The trapped electrons and ions move in helical paths around their particular field lines and "bounce" back and forth between the magnetic mirrors. These trapped electrons and ions can oscillate along the field lines for long periods of time.

In the past several years, substantial effort has been made to understand and explain the phenomena involved in belts of trapped electrons and ions, and to explore possible ways to control and use these phenomena for beneficial purposes. For example, in the late 1950's and early 1960's both the United States and U.S.S.R. detonated a series of nuclear devices of various yields to generate large numbers of charged particles at various altitudes, e.g., 200 kilometers (km) or greater. This was done in order to establish and study artifical belts of trapped electrons and ions. These experiments established that at least some of the extraneous electrons and ions from the detonated devices did become trapped along field lines in the earth's magnetosphere to form artificial belts which were stable for prolonged periods of time. For a discussion of these experiments see "The Radiation Belt and Magnetosphere", W. N. Hess, Blaisdell Publishing Co., 1968, pps. 155 et sec.

Other proposals which have been advanced for altering existing belts of trapped electrons and ions and/or establishing similar artificial belts include injecting charged particles from a satellite carrying a payload of radioactive beta-decay material or alpha emitters; and injecting charged particles from a satellite-borne electron accelerator. Still another approach is described in U.S. Pat. No. 4,042,196 wherein a low energy ionized gas, e.g., hydrogen, is released from a synchronous orbiting satellite near the apex of a radiation belt which is naturally-occurring in the earth's magnetosphere to produce a substantial increase in energetic particle precipitation and, under certain conditions, produce a limit in the number of particles that can be stably trapped. This precipitation effect arises from an enhancement of the whistler-mode and ion-cyclotron mode interactions that result from the ionized gas or "cold plasma" injection.

It has also been proposed to release large clouds of barium in the magnetosphere so that photoionization will increase the cold plasma density, thereby producing electron precipitation through enhanced whistler-mode interactions.

However, in all of the above-mentioned approaches, the mechanisms involved in triggering the change in the trapped particle phenomena must be actually positioned within the affected zone, e.g., the magnetosphere, before they can be actuated to effect the desired change.

The earth's ionosphere is not considered to be a "trapped" belt since there are few trapped particles therein. The term "trapped" herein refers to situations where the force of gravity on the trapped particles is balanced by magnetic forces rather than hydrostatic or collisional forces. The charged electrons and ions in the ionosphere also follow helical paths around magnetic field lines within the ionosphere but are not trapped between mirrors, as in the case of the trapped belts in the magnetosphere, since the gravitational force on the particles is balanced by collisional or hydrostatic forces.

In recent years, a number of experiments have actually been carried out to modify the ionosphere in some controlled manner to investigate the possibility of a beneficial result. For detailed discussions of these operations see the following papers: (1) Ionospheric Modification Theory; G. Meltz and F. W. Perkins; (2) The Platteville High Power Facility; Carrol et al.; (3) Arecibo Heating Experiments; W. E. Gordon and H. C. Carlson, Jr.; and (4) Ionospheric Heating by Powerful Radio Waves; Meltz et al., all published in Radio Science, Vol. 9, No. 11, November, 1974, at pages 885–888; 889–894; 1041–1047; and 1049–1063, respectively, all of which are incorporated herein by reference. In such experiments, certain regions of the ionosphere are heated to change the electron density and temperature within these regions. This is accomplished by transmitting from earth-based antennae high frequency electromagnetic radiation at a substantial angle to, not parallel to, the ionosphere's magnetic field to heat the ionospheric particles primarily by ohmic heating. The electron temperature of the ionosphere has been raised by hundreds of degrees in these experiments, and electrons with several electron volts of energy have been produced in numbers sufficient to enhance airglow. Electron concentrations have been reduced by a few percent, due to expansion of the plasma as a result of increased temperature.

In the Elmo Bumpy Torus (EBT), a controlled fusion device at the Oak Ridge National Laboratory, all heating is provided by microwaves at the electron cyclotron resonance interaction. A ring of hot electrons is formed at the earth's surface in the magnetic mirror by a combination of electron cyclotron resonance and stochastic heating. In the EBT, the ring electrons are produced with an average "temperature" of 250 kilo electron volts or kev (2.5×10^9K) and a plasma beta between 0.1 and 0.4; see, "A Theoretical Study of Electron—Cyclotron Absorption in Elmo Bumpy Torus", Batchelor and Goldfinger, Nuclear Fusion, Vol. 20, No. 4 (1980) pps. 403–418.

Electron cyclotron resonance heating has been used in experiments on the earth's surface to produce and accelerate plasmas in a diverging magnetic field. Kosmahl et al. showed that power was transferred from the electromagnetic waves and that a fully ionized plasma

was accelerated with a divergence angle of roughly 13 degrees. Optimum neutral gas density was 1.7×10^{14} per cubic centimeter; see, "Plasma Acceleration with Microwaves Near Cyclotron Resonance", Kosmahl et al., Journal of Applied Physics, Vol. 38, No. 12, Nov., 1967, pps. 4576–4582.

DISCLOSURE OF THE INVENTION

The present invention provides a method and apparatus for altering at least one selected region which normally exists above the earth's surface. The region is excited by electron cyclotron resonance heating of electrons which are already present and/or artifically created in the region to thereby increase the charged particle energy and ultimately the density of the region.

In one embodiment this is done by transmitting circularly polarized electromagnetic radiation from the earth's surface at or near the location where a naturally-occurring dipole magnetic field (force) line intersects the earth's surface. Right hand circular polarization is used in the northern hemisphere and left hand circular polarization is used in the southern hemisphere. The radiation is deliberately transmitted at the outset in a direction substantially parallel to and along a field line which extends upwardly through the region to be altered. The radiation is transmitted at a frequency which is based on the gyrofrequency of the charged particles and which, when applied to the at least one region, excites electron cyclotron resonance within the region or regions to heat and accelerate the charged particles in their respective helical paths around and along the field line. Sufficient energy is employed to cause ionization of neutral particles (molecules of oxygen, nitrogen and the like, particulates, etc.) which then become a part of the region thereby increasing the charged particle density of the region. This effect can further be enhanced by providing artificial particles, e.g., electrons, ions, etc., directly into the region to be affected from a rocket, satellite, or the like to supplement the particles in the naturally-occurring plasma. These artificial particles are also ionized by the transmitted electromagnetic radiation thereby increasing charged particle density of the resulting plasma in the region.

In another embodiment of the invention, electron cyclotron resonance heating is carried out in the selected region or regions at sufficient power levels to allow a plasma present in the region to generate a mirror force which forces the charged electrons of the altered plasma upward along the force line to an altitude which is higher than the original altitude. In this case the relevant mirror points are at the base of the altered region or regions. The charged electrons drag ions with them as well as other particles that may be present. Sufficient power, e.g., 10^{15} joules, can be applied so that the altered plasma can be trapped on the field line between mirror points and will oscillate in space for prolonged periods of time. By this embodiment, a plume of altered plasma can be established at selected locations for communication modification or other purposes.

In another embodiment, this invention is used to alter at least one selected region of plasma in the ionosphere to establish a defined layer of plasma having an increased charged particle density. Once this layer is established, and while maintaining the transmission of the main beam of circularly polarized electromagnetic radiation, the main beam is modulated and/or at least one second different, modulated electromagnetic radiation beam is transmitted from at least one separate source at a different frequency which will be absorbed in the plasma layer. The amplitude of the frequency of the main beam and/or the second beam or beams is modulated in resonance with at least one known oscillation mode in the selected region or regions to excite the known oscillation mode to propagate a known frequency wave or waves throughout the ionosphere.

BRIEF DESCRIPTION OF THE DRAWINGS

The actual construction, operation, and apparent advantages of this invention will be better understood by referring to the drawings in which like numerals identify like parts and in which:

FIG. **1** is a simplified schematical view of the earth (not to scale) with a magnetic field (force) line along which the present invention is carried out;

FIG. **2** is one embodiment within the present invention in which a selected region of plasma is raised to a higher altitude;

FIG. **3** is a simplified, idealized representation of a physical phenomenon involved in the present invention; and

FIG. **4** is a schematic view of another embodiment within the present invention.

FIG. **5** is a schematic view of an apparatus embodiment within this invention.

BEST MODES FOR CARRYING OUT THE INVENTION

The earth's magnetic field is somewhat analogous to a dipole bar magnet. As such, the earth's magnetic field contains numerous divergent field or force lines, each line intersecting the earth's surface at points on opposite sides of the Equator. The field lines which intersect the earth's surface near the poles have apexes which lie at the furthest points in the earth's magnetosphere while those closest to the Equator have apexes which reach only the lower portion of the magnetosphere.

At various altitudes above the earth's surface, e.g., in both the ionosphere and the magnetosphere, plasma is naturally present along these field lines. This plasma consists of equal numbers of positively and negatively charged particles (i.e., electrons and ions) which are guided by the field line. It is well established that a charged particle in a magnetic field gyrates about field lines, the center of gyration at any instance being called the "guiding center" of the particle. As the gyrating particle moves along a field line in a uniform field, it will follow a helical path about its guiding center, hence linear motion, and will remain on the field line. Electrons and ions both follow helical paths around a field line but rotate in opposite directions. The frequencies at which the electrons and ions rotate about the field line are called gyromagnetic frequencies or cyclotron frequencies because they are identical with the expression for the angular frequencies of gyration of particles in a cyclotron. The cyclotron frequency of ions in a given magnetic field is less than that of electrons, in inverse proportion to their masses.

If the particles which form the plasma along the earth's field lines continued to move with a constant pitch angle, often designated "alpha", they would soon impact on the earth's surface. Pitch angle alpha is defined as the angle between the direction of the earth's magnetic field and the velocity (V) of the particle. However, in converging force fields, the pitch angle does change in such a way as to allow the particle to

turn around and avoid impact. Consider a particle moving along a field line down toward the earth. It moves into a region of increasing magnetic field strength and therefore sine alpha increases. But sine alpha can only increase to 1.0, at which point, the particle turns around and starts moving up along the field line, and alpha decreases. The point at which the particle turns around is called the mirror point, and there alpha equals ninety degrees. This process is repeated at the other end of the field line where the same magnetic field strength value B, namely Bm, exists. The particle again turns around and this is called the "conjugate point" of the original mirror point. The particle is therefore trapped and bounces between the two magnetic mirrors. The particle can continue oscillating in space in this manner for long periods of time. The actual place where a particle will mirror can be calculated from the following:

$$\sin^2 \text{alpha}_o = B_o/B_m \quad (1)$$

wherein:

alpha$_o$=equatorial pitch angle of particle

B$_o$=equatorial field strength on a particular field line

B$_m$=field strength at the mirror point

Recent discoveries have established that there are substantial regions of naturally trapped particles in space which are commonly called "trapped radiation belts". These belts occur at altitudes greater than about 500 km and accordingly lie in the magnetosphere and mostly above the ionosphere.

The ionosphere, while it may overlap some of the trapped-particle belts, is a region in which hydrostatic forces govern its particle distribution in the gravitational field. Particle motion within the ionosphere is governed by both hydrodynamic and electrodynamic forces. While there are few trapped particles in the ionosphere, nevertheless, plasma is present along field lines in the ionosphere. The charged particles which form this plasma move between collisions with other particles along similar helical paths around the field lines and although a particular particle may diffuse downward into the earth's lower atmosphere or lose energy and diverge from its original field line due to collisions with other particles, these charged particles are normally replaced by other available charged particles or by particles that are ionized by collision with said particle. The electron density (N$_e$) of the plasma will vary with the actual conditions and locations involved. Also, neutral particles, ions, and electrons are present in proximity to the field lines.

The production of enhanced ionization will also alter the distribution of atomic and molecular constituents of the atmosphere, most notably through increased atomic nitrogen concentration. The upper atmosphere is normally rich in atomic oxygen (the dominant atmospheric constituent above 200 km altitude), but atomic nitrogen is normally relatively rare. This can be expected to manifest itself in increased airglow, among other effects.

As known in plasma physics, the characteristics of a plasma can be altered by adding energy to the charged particles or by ionizing or exciting additional particles to increase the density of the plasma. One way to do this is by heating the plasma which can be accomplished in different ways, e.g., ohmic, magnetic compression, shock waves, magnetic pumping, electron cyclotron resonance, and the like.

Since electron cyclotron resonance heating is involved in the present invention, a brief discussion of same is in order. Increasing the energy of electrons in a plasma by invoking electron cyclotron resonance heating, is based on a principle similar to that utilized to accelerate charged particles in a cyclotron. If a plasma is confined by a static axial magnetic field of strength B, the charged particles will gyrate about the lines of force with a frequency given, in hertz, as $f_g = 1.54 \times 10^3 B/A$, where: B=magnetic field strength in gauss, and A=mass number of the ion.

Suppose a time-varying field of this frequency is superimposed on the static field B confining the plasma, by passage of a radiofrequency current through a coil which is concentric with that producing the axial field, then in each half-cycle of their rotation about the field lines, the charged particles acquire energy from the oscillating electric field associated with the radio frequency. For example, if B is 10,000 gauss, the frequency of the field which is in resonance with protons in a plasma is 15.4 megahertz.

As applied to electrons, electron cyclotron resonance heating requires an oscillating field having a definite frequency determined by the strength of the confining field. The radio-frequency radiation produces time-varying fields (electric and magnetic), and the electric field accelerates the charged particle. The energized electrons share their energy with ions and neutrals by undergoing collisions with these particles, thereby effectively raising the temperature of the electrons, ions, and neutrals. The apportionment of energy among these species is determined by collision frequencies. For a more detailed understanding of the physics involved, see "Controlled Thermonuclear Reactions", Glasstone and Lovberg, D. Van Nostrand Company, Inc., Princeton, N.J., 1960 and "The Radiation Belt and Magnetosphere", Hess, Blaisdell Publishing Company, 1968, both of which are incorporated herein by reference.

Referring now to the drawings, the present invention provides a method and apparatus for altering at least one region of plasma which lies along a field line, particularly when it passes through the ionosphere and/or magnetosphere. FIG. **1** is a simplified illustration of the earth **10** and one of its dipole magnetic force or field lines **11**. As will be understood, line **11** may be any one of the numerous naturally existing field lines and the actual geographical locations **13** and **14** of line **11** will be chosen based on a particular operation to be carried out. The actual locations at which field lines intersect the earth's surface is documented and is readily ascertainable by those skilled in the art.

Line **11** passes through region R which lies at an altitude above the earth's surface. A wide range of altitudes are useful given the power that can be employed by the practice of this invention. The electron cyclotron resonance heating effect can be made to act on electrons anywhere above the surface of the earth. These electrons may be already present in the atmosphere, ionosphere, and/or magnetosphere of the earth, or can be artificially generated by a variety of means such as x-ray beams, charged particle beams, lasers, the plasma sheath surrounding an object such as a missile or meteor, and the like. Further, artificial particles, e.g., electrons, ions, etc., can be injected directly into region R from an earth-launched rocket or orbiting satellite carrying, for example, a payload of radioactive beta-decay material; alpha emitters; an electron accelerator; and/or ionized gases such as hydrogen; see U.S. Pat. No. 4,042,196. The altitude can be greater than about 50 km if desired,

e.g., can be from about 50 km to about 800 km, and, accordingly may lie in either the ionosphere or the magnetosphere or both. As explained above, plasma will be present along line **11** within region R and is represented by the helical line **12**. Plasma **12** is comprised of charged particles (i.e., electrons and ions) which rotate about opposing helical paths along line **11**.

Antenna **15** is positioned as close as is practical to the location **14** where line **11** intersects the earth's surface. Antenna **15** may be of any known construction for high directionality, for example, a phased array, beam spread angle (θ) type. See "The MST Radar at Poker Flat, Alaska", Radio Science, Vol. 15, No. 2, Mar.-Apr. 1980, pps. 213–223, which is incorporated herein by reference. Antenna **15** is coupled to transmitter **16** which generates a beam of high frequency electromagnetic radiation at a wide range of discrete frequencies, e.g., from about 20 to about 1800 kilohertz (kHz).

Transmitter **16** is powered by power generator means **17** which is preferably comprised of one or more large, commercial electrical generators. Some embodiments of the present invention require large amounts of power, e.g., up to 10^9 to 10^{11} watts, in continuous wave or pulsed power. Generation of the needed power is within the state of the art. Although the electrical generators necessary for the practice of the invention can be powered in any known manner, for example, by nuclear reactors, hydroelectric facilities, hydrocarbon fuels, and the like, this invention, because of its very large power requirement in certain applications, is particularly adapted for use with certain types of fuel sources which naturally occur at strategic geographical locations around the earth. For example, large reserves of hydrocarbons (oil and natural gas) exist in Alaska and Canada. In northern Alaska, particularly the North Slope region, large reserves are currently readily available. Alaska and northern Canada also are ideally located geographically as to magnetic latitudes. Alaska provides easy access to magnetic field lines that are especially suited to the practice of this invention, since many field lines which extend to desirable altitudes for this invention intersect the earth in Alaska. Thus, in Alaska, there is a unique combination of large, accessible fuel sources at desirable field line intersections. Further, a particularly desirable fuel source for the generation of very large amounts of electricity is present in Alaska in abundance, this source being natural gas. The presence of very large amounts of clean-burning natural gas in Alaskan latitudes, particularly on the North Slope, and the availability of magnetohydrodynamic (MHD), gas turbine, fuel cell, electrogasdynamic (EGD) electric generators which operate very efficiently with natural gas provide an ideal power source for the unprecedented power requirements of certain of the applications of this invention. For a more detailed discussion of the various means for generating electricity from hydrocarbon fuels, see "Electrical Aspects of Combustion", Lawton and Weinberg, Clarendon Press, 1969. For example, it is possible to generate the electricity directly at the high frequency needed to drive the antenna system. To do this, typically the velocity of flow of the combustion gases (v), past magnetic field perturbation of dimension d (in the case of MHD), follow the rule:

$$v = df$$

where f is the frequency at which electricity is generated. Thus, if $v = 1.78 \times 10^6$ cm/sec and d=1 cm then electricity would be generated at a frequency of 1.78 mHz.

Put another way, in Alaska, the right type of fuel (natural gas) is naturally present in large amounts and at just the right magnetic latitudes for the most efficient practice of this invention, a truly unique combination of circumstances. Desirable magnetic latitudes for the practice of this invention interest the earth's surface both northerly and southerly of the equator, particularly desirable latitudes being those, both northerly and southerly, which correspond in magnitude with the magnetic latitudes that encompass Alaska.

Referring now to FIG. 2 a first ambodiment is illustrated where a selected region R_1 of plasma **12** is altered by electron cyclotron resonance heating to accelerate the electrons of plasma **12**, which are following helical paths along field line **11**.

To accomplish this result, electromagnetic radiation is transmitted at the outset, essentially parallel to line **11** via antenna **15** as right hand circularly polarized radiation wave **20**. Wave **20** has a frequency which will excite electron cyclotron resonance with plasma **12** at its initial or original altitude. This frequency will vary depending on the electron cyclotron resonance of region R_1 which, in turn, can be determined from available data based on the altitudes of region R_1, the particular field line **11** being used, the strength of the earth's magnetic field, etc. Frequencies of from about 20 to about 7200 kHz, preferably from about 20 to about 1800 kHz can be employed. Also, for any given application, there will be a threshhold (minimum power level) which is needed to produce the desired result. The minimum power level is a function of the level of plasma production and movement required, taking into consideration any loss processes that may be dominant in a particular plasma or propagation path.

As electron cyclotron resonance is established in plasma **12**, energy is transferred from the electromagnetic radiation **20** into plasma **12** to heat and accelerate the electrons therein and, subsequently, ions and neutral particles. As this process continues, neutral particles which are present within R_1 are ionized and absorbed into plasma **12** and this increases the electron and ion densities of plasma **12**. As the electron energy is raised to values of about 1 kilo electron volt (kev), the generated mirror force (explained below) will direct the excited plasma **12** upward along line **11** to form a plume R_2 at an altitude higher than that of R_1.

Plasma acceleration results from the force on an electron produced by a nonuniform static magnetic field ($\overline{B}$). The force, called the mirror force, is given by

$$F = -\mu \nabla B \qquad (2)$$

where μ is the electron magnetic moment and $\nabla \overline{B}$ is the gradient of the magnetic field, μ being further defined as:

$$W_\perp/B = mV_\perp^2/2B$$

where $W_\perp$ is the kinetic energy in the direction perpendicular to that of the magnetic field lines and B is the magnetic field strength at the line of force on which the guiding center of the particle is located. The force as represented by equation (2) is the force which is responsible for a particle obeying equation (1).

Since the magnetic field is divergent in region R_1, it can be shown that the plasma will move upwardly from the heating region as shown in FIG. **1** and further it can be shown that

$$\tfrac{1}{2}M_eV_{e\perp}^2(x) \approx \tfrac{1}{2}M_eV_{e\perp}^2(Y) + \tfrac{1}{2}M_iV_{i\parallel}^2(Y) \qquad (3)$$

where the left hand side is the initial electron transverse kinetic energy; the first term on the right is the transverse electron kinetic energy at some point (Y) in the expanded field region, while the final term is the ion kinetic energy parallel to B at point (Y). This last term is what constitutes the desired ion flow. It is produced by an electrostatic field set up by electrons which are accelerated according to Equation (2) in the divergent field region and pulls ions along with them. Equation (3) ignores electron kinetic energy parallel to B because $V_{e\parallel} \approx V_{i\parallel}$, so the bulk of parallel kinetic energy resides in the ions because of their greater masses. For example, if an electromagnetic energy flux of from about 1 to about 10 watts per square centimeter is applied to region R, whose altitude is 115 km, a plasma having a density (N_e) of 10^{12} per cubic centimeter will be generated and moved upward to region R_2 which has an altitude of about 1000 km. The movement of electrons in the plasma is due to the mirror force while the ions are moved by ambipolar diffusion (which results from the electrostatic field). This effectively "lifts" a layer of plasma **12** from the ionosphere and/or magnetosphere to a higher elevation R_2. The total energy required to create a plasma with a base area of 3 square kilometers and a height of 1000 km is about 3×10^{13} joules.

FIG. **3** is an idealized representation of movement of plasma **12** upon excitation by electron cyclotron resonance within the earth's divergent force field. Electrons (e) are accelerated to velocities required to generate the necessary mirror force to cause their upward movement. At the same time neutral particles (n) which are present along line **11** in region $R_1$are ionized and become part of plasma **12**. As electrons (e) move upward along line **11**, they drag ions (i) and neutrals (n) with them but at an angle θ of about 13 degrees to field line **11**. Also, any particulates that may be present in region R_1, will be swept upwardly with the plasma. As the charged particles of plasma **12** move upward, other particles such as neutrals within or below R_1, move in to replace the upwardly moving particles. These neutrals, under some conditions, can drag with them charged particles.

For example, as a plasma moves upward, other particles at the same altitude as the plasma move horizontally into the region to replace the rising plasma and to form new plasma. The kinetic energy developed by said other particles as they move horizontally is, for example, on the same order of magnitude as the total zonal kinetic energy of stratospheric winds known to exist.

Referring again to FIG. **2**, plasma **12** in region R_1 is moved upward along field line **11**. The plasma **12** will then form a plume (cross-hatched area in FIG. **2**) which will be relatively stable for prolonged periods of time. The exact period of time will vary widely and be determined by gravitational forces and a combination of radiative and diffusive loss terms. In the previous detailed example, the calculations were based on forming a plume by producing 0+energies of 2 ev/particle. About 10 ev per particle would be required to expand plasma **12** to apex point C (FIG. **1**). There at least some of the particles of plasma **12** will be trapped and will oscillate between mirror points along field line **11**. This oscillation will then allow additional heating of the trapped plasma **12** by stochastic heating which is associated with trapped and oscillating particles. See "A New Mechanism for Accelerating Electrons in the Outer Ionosphere" by R. A. Helliwell and T. F. Bell, Journal of Geophysical Research, Vol. 65, No. 6, June, 1960. This is preferably carried out at an altitude of at least 500 km.

The plasma of the typical example might be employed to modify or disrupt microwave transmissions of satellites. If less than total black-out of transmission is desired (e.g., scrambling by phase shifting digital signals), the density of the plasma (N_e) need only be at least about 10^6 per cubic centimeter for a plasma orginating at an altitude of from about 250 to about 400 km and accordingly less energy (i.e., electromagnetic radiation), e.g., 10^8 joules need be provided. Likewise, if the density $N_e$is on the order of 10^8, a properly positioned plume will provide a reflecting surface for VHF waves and can be used to enhance, interfere with, or otherwise modify communication transmissions. It can be seen from the foregoing that by appropriate application of various aspects of this invention at strategic locations and with adequate power sources, a means and method is provided to cause interference with or even total disruption of communications over a very large portion of the earth. This invention could be employed to disrupt not only land based communications, both civilian and military, but also airborne communications and sea communications (both surface and subsurface). This would have significant military implications, particularly as a barrier to or confusing factor for hostile missiles or airplanes. The belt or belts of enhanced ionization produced by the method and apparatus of this invention, particularly if set up over Northern Alaska and Canada, could be employed as an early warning device, as well as a communications disruption medium. Further, the simple ability to produce such a situation in a practical time period can by itself be a deterring force to hostile action. The ideal combination of suitable field lines intersecting the earth's surface at the point where substantial fuel sources are available for generation of very large quantitities of electromagnetic power, such as the North Slope of Alaska, provides the wherewithal to accomplish the foregoing in a practical time period, e.g., strategic requirements could necessitate achieving the desired altered regions in time periods of two minutes or less and this is achievable with this invention, especially when the combination of natural gas and magnetohydrodynamic, gas turbine, fuel cell and/or EGD electric generators are employed at the point where the useful field lines intersect the earth's surface. One feature of this invention which satisfies a basic requirement of a weapon system, i.e., continuous checking of operability, is that small amounts of power can be generated for operability checking purposes. Further, in the exploitation of this invention, since the main electromagnetic beam which generates the enhanced ionized belt of this invention can be modulated itself and/or one or more additional electromagnetic radiation waves can be impinged on the ionized region formed by this invention as will be described in greater detail herein after with respect to FIG. **4**, a substantial amount of randomly modulated signals of very large power magnitude can be generated in a highly nonlinear mode. This can cause confusion of or interference with or even complete disruption of guidance systems employed by

even the most sophisticated of airplanes and missiles. The ability to employ and transmit over very wide areas of the earth a plurality of electromagnetic waves of varying frequencies and to change same at will in a random manner, provides a unique ability to interfere with all modes of communications, land, sea, and/or air, at the same time. Because of the unique juxtaposition of usable fuel source at the point where desirable field lines intersect the earth's surface, such wide ranging and complete communication interference can be achieved in a resonably short period of time. Because of the mirroring phenomenon discussed hereinabove, it can also be prolonged for substantial time periods so that it would not be a mere transient effect that could simply be waited out by an opposing force. Thus, this invention provides the ability to put unprecedented amounts of power in the earth's atmosphere at strategic locations and to maintain the power injection level, particularly if random pulsing is employed, in a manner far more precise and better controlled than heretofore accomplished by the prior art, particularly by the detonation of nuclear devices of various yeilds at various altitudes. Where the prior art approaches yielded merely transitory effects, the unique combination of fuel and desirable field lines at the point where the fuel occurs allows the establishment of, compared to prior art approaches, precisely controlled and long-lasting effects which cannot, practically speaking, simply be waited out. Further, by knowing the frequencies of the various electromagnetic beams employed in the practice of this invention, it is possible not only to interfere with third party communications but to take advantage of one or more such beams to carry out a communications network even though the rest of the world's communications are disrupted. Put another way, what is used to disrupt another's communications can be employed by one knowledgeable of this invention as a communications network at the same time. In addition, once one's own communication network is established, the far-reaching extent of the effects of this invention could be employed to pick up communication signals of other for intelligence purposes. Thus, it can be seen that the disrupting effects achievable by this invention can be employed to benefit by the party who is practicing this invention since knowledge of the various electromagnetic waves being employed and how they will vary in frequency and magnitude can be used to an advantage for positive communication and eavesdropping purposes at the same time. However, this invention is not limited to locations where the fuel source naturally exists or where desirable field lines naturally intersect the earth's surface. For example, fuel, particularly hydrocarbon fuel, can be transported by pipeline and the like to the location where the invention is to be practiced.

FIG. 4 illustrates another embodiment wherein a selected region of plasma R_3 which lies within the earth's ionosphere is altered to increase the density thereof whereby a relatively stable layer **30** of relatively dense plasma is maintained within region R_3. Electromagnetic radiation is transmitted at the outset essentially parallel to field line **11** via antenna **15** as a right hand circularly polarized wave and at a frequency (e.g., 1.78 megahertz when the magnetic field at the desired altitude is 0.66 gauss) capable of exciting electron cyclotron resonance in plasma **12** at the particular altitude of plasma **12**. This causes heating of the particles (electrons, ions, neutrals, and particulates) and ionization of the uncharged particles adjacent line **11**, all of which are absorbed into plasma **12** to increase the density thereof. The power transmitted, e.g., 2×10^6 watts for up to 2 minutes heating time, is less than that required to generate the mirror force F required to move plasma **12** upward as in the previous embodiment.

While continuing to transmit electromagnetic radiation **20** from antenna **15**, a second electromagnetic radiation beam **31**, which is at a defined frequency different from the radiation from antenna **15**, is transmitted from one or more second sources via antenna **32** into layer **30** and is absorbed into a portion of layer **30** (cross-hatched area in FIG. 4). The electromagnetic radiation wave from antenna **32** is amplitude modulated to match a known mode of oscillation f_3 in layer **30**. This creates a resonance in layer **30** which excites a new plasma wave **33** which also has a frequency of f_3 and which then propogates through the ionosphere. Wave **33** can be used to improve or disrupt communications or both depending on what is desired in a particular application. Of course, more than one new wave **33** can be generated and the various new waves can be modulated at will and in a highly nonlinear fashion.

FIG. **5** shows apparatus useful in this invention, particularly when those applications of this invention are employed which require extremely large amounts of power. In FIG. **5** there is shown the earth's surface **40** with a well **41** extending downwardly thereinto until it penetrates hydrocarbon producing reservoir **42**. Hydrocarbon reservoir **42** produces natural gas alone or in combination with crude oil. Hydrocarbons are produced from reservoir **42** through well **41** and wellhead **43** to a treating system **44** by way of pipe **45**. In treater **44**, desirable liquids such as crude oil and gas condensates are separated and recovered by way of pipe **46** while undesirable gases and liquids such as water, H_2S, and the like are separated by way of pipe **47**. Desirable gases such as carbon dioxide are separated by way of pipe **48**, and the remaining natural gas stream is removed from treater **44** by way of pipe **49** for storage in conventional tankage means (not shown) for future use and/or use in an electrical generator such as a magnetohydrodynamic, gas turbine, fuel cell or EGD generator **50**. Any desired number and combination of different types of electric generators can be employed in the practice of this invention. The natural gas is burned in generator **50** to produce substantial quantities of electricity which is then stored and/or passed by way of wire **51** to a transmitter **52** which generates the electromagnetic radiation to be used in the method of this invention. The electromagnetic radiation is then passed by way of wire **53** to antenna **54** which is located at or near the end of field line **11**. Antenna **54** sends circularly polarized radiation wave **20** upwards along field line **11** to carry out the various methods of this invention as described hereinabove.

Of course, the fuel source need not be used in its naturally-occurring state but could first be converted to another second energy source form such as hydrogen, hydrazine and the like, and electricity then generated from said second energy source form.

It can be seen from the foregoing that when desirable field line **11** intersects earth's surface **40** at or near a large naturally-occurring hydrocarbon source **42**, exceedingly large amounts of power can be very efficiently produced and transmitted in the direction of field lines. This is particularly so when the fuel source is natural gas and magnetohydrodynamic generators are employed. Further, this can all be accomplished in a

relatively small physical area when there is the unique coincidence of fuel source **42** and desirable field line **11**. Of course, only one set of equipment is shown in FIG. **5** for sake of simplicity. For a large hydrocarbon reservoir **42**, a plurality of wells **41** can be employed to feed one or more storage means and/or treaters and as large a number of generators **55** as needed to power one or more transmitters **52** and one or more antennas **54**. Since all of the apparatus **44** through **54** can be employed and used essentially at the sight where naturally-occurring fuel source **42** is located, all the necessary electromagnetic radiation **20** is generated essentially at the same location as fuel source **42**. This provides for a maximum amount of usable electromagnetic radiation **20** since there are no significant storage or transportation losses to be incurred. In other words, the apparatus is brought to the sight of the fuel source where desirable field line **11** intersects the earth's surface **40** on or near the geographical location of fuel source **42**, fuel source **42** being at a desirable magnetic latitude for the practice of this invention, for example, Alaska.

The generation of electricity by motion of a conducting fluid through a magnetic field, i.e., magnetohydrodynamics (MHD), provides a method of electric power generation without moving mechanical parts and when the conducting fluid is a plasma formed by combustion of a fuel such as natural gas, an idealized combination of apparatus is realized since the very clean-burning natural gas forms the conducting plasma in an efficient manner and the thus formed plasma, when passed through a magnetic field, generates electricity in a very efficient manner. Thus, the use of fuel source **42** to generate a plasma by combustion thereof for the generation of electricity essentially at the site of occurrence of the fuel source is unique and ideal when high power levels are required and desirable field lines **11** intersect the earth's surface **40** at or near the site of fuel source **42**. A particular advantage for MHD generators is that they can be made to generate large amounts of power with a small volume, light weight device. For example, a 1000 megawatt MHD generator can be construed using superconducting magnets to weigh roughly 42,000 pounds and can be readily air lifted.

This invention has a phenomenal variety of possible ramifications and potential future developments. As alluded to earlier, missile or aircraft destruction, deflection, or confusion could result, particularly when relativistic particles are employed. Also, large regions of the atmosphere could be lifted to an unexpectedly high altitude so that missiles encounter unexpected and unplanned drag forces with resultant destruction or deflection of same. Weather modification is possible by, for example, altering upper atmosphere wind patterns or altering solar absorption patterns by constructing one or more plumes of atmospheric particles which will act as a lens or focusing device. Also as alluded to earlier, molecular modifications of the atmosphere can take place so that positive environmental effects can be achieved. Besides actually changing the molecular composition of an atmospheric region, a particular molecule or molecules can be chosen for increased presence. For example, ozone, nitrogen, etc. concentrations in the atmosphere could be artificially increased. Similarly, environmental enhancement could be achieved by causing the breakup of various chemical entities such as carbon dioxide, carbon monoxide, nitrous oxides, and the like. Transportation of entities can also be realized when advantage is taken of the drag effects caused by regions of the atmosphere moving up along diverging field lines. Small micron sized particles can be then transported, and, under certain circumstances and with the availability of sufficient energy, larger particles or objects could be similarly affected. Particles with desired characteristics such as tackiness, reflectivity, absorptivity, etc., can be transported for specific purposes or effects. For example, a plume of tacky particles could be established to increase the drag on a missile or satellite passing therethrough. Even plumes of plasma having substantially less charged particle density than described above will produce drag effects on missiles which will affect a lightweight (dummy) missile in a manner substantially different than a heavy (live) missile and this affect can be used to distinguish between the two types of missiles. A moving plume could also serve as a means for supplying a space station or for focusing vast amount of sunlight on selected portions of the earth. Surveys of global scope could also be realized because the earth's natural magnetic field could be significantly altered in a controlled manner by plasma beta effects resulting in, for example, improved magnetotelluric surveys. Electromagnetic pulse defenses are also possible. The earth's magnetic field could be decreased or disrupted at appropriate altitudes to modify or eliminate the magnetic field in high Compton electron generation (e.g., from high altitude nuclear bursts) regions. High intensity, well controlled electrical fields can be provided in selected locations for various purposes. For example, the plasma sheath surrounding a missile or satellite could be used as a trigger for activating such a high intensity field to destroy the missile or satellite. Further, irregularities can be created in the ionosphere which will interfere with the normal operation of various types of radar, e.g., synthetic aperture radar. The present invention can also be used to create artificial belts of trapped particles which in turn can be studied to determine the stability of such parties. Still further, plumes in accordance with the present invention can be formed to simulate and/or perform the same functions as performed by the detonation of a "heave" type nuclear device without actually having to detonate such a device. Thus it can be seen that the ramifications are numerous, far-reaching, and exceedingly varied in usefulness.

I claim:

1. A method for altering at least one region normally existing above the earth's surface with electromagnetic radiation using naturally-occurring and diverging magnetic field lines of the earth comprising transmitting first electromagnetic radiation at a frequency between 20 and 7200 kHz from the earth's surface, said transmitting being conducted essentially at the outset of transmission substantially parallel to and along at least one of said field lines, adjusting the frequency of said first radiation to a value which will excite electron cyclotron resonance at an initial elevation at least 50 km above the earth's surface, whereby in the region in which said electron cyclotron resonance takes place heating, further ionization, and movement of both charged and neutral particles is effected, said cyclotron resonance excitation of said region is continued until the electron concentration of said region reaches a value of at least 10^6 per cubic centimeter and has an ion energy of at least 2 ev.

2. The method of claim **1** including the step of providing artificial particles in said at least one region which are excited by said electron cyclotron resonance.

3. The method of claim 2 wherein said artificial particles are provided by injecting same into said at least one region from an orbiting satellite.

4. The method of claim 1 wherein said threshold excitation of electron cyclotron resonance is about 1 watt per cubic centimeter and is sufficient to cause movement of a plasma region along said diverging magnetic field lines to an altitude higher than the altitude at which said excitation was initiated.

5. The method of claim 4 wherein said rising plasma region pulls with it a substantial portion of neutral particles of the atmosphere which exist in or near said plasma region.

6. The method of claim 1 wherein there is provided at least one separate source of second electromagnetic radiation, said second radiation having at least one frequency different from said first radiation, impinging said at least one second radiation on said region while said region is undergoing electron cyclotron resonance excitation caused by said first radiation.

7. The method of claim 6 wherein said second radiation has a frequency which is absorbed by said region.

8. The method of claim 6 wherein said region is plasma in the ionosphere and said second radiation excites plasma waves within said ionosphere.

9. The method of claim 8 wherein said electron concentration reaches a value of at least 10^{12} per cubic centimeter.

10. The method of claim 8 wherein said excitation of electron cyclotron resonance is initially carried out within the ionosphere and is continued for a time sufficient to allow said region to rise above said ionosphere.

11. The method of claim 1 wherein said excitation of electron cyclotron resonance is carried out above about 500 kilometers and for a time of from 0.1 to 1200 seconds such that multiple heating of said plasma region is achieved by means of stochastic heating in the magnetosphere.

12. The method of claim 1 wherein said first electromagnetic radiation is right hand circularly polarized in the northern hemisphere and left hand circularly polarized in the southern hemisphere.

13. The method of claim 1 wherein said electromagnetic radiation is generated at the site of a naturally-occurring hydrocarbon fuel source, said fuel source being located in at least one of northerly or southerly magnetic latitudes.

14. The method of claim 13 wherein said fuel source is natural gas and electricity for generating said electromagnetic radiation is obtained by burning said natural gas in at least one of magnetohydrodynamic, gas turbine, fuel cell, and EGD electric generators located at the site where said natural gas naturally occurs in the earth.

15. The method of claim 14 wherein said site of natural gas is within the magnetic latitudes that encompass Alaska.

* * * * *

Source : Fonte: rexresearch.com

Hermann PLAUSON

Conversion of Atmospheric Electricity

Biography (Wikipedia)

Meridian International Research: Atmospheric Electricity Research

***Science & Invention* (Feb. 1922): "Power from the Air" (I)**

***Science & Invention* (March 1922): "Power from the Air" (II)**

Plauson's Patents (List)

H. Plauson: USP # 1,540,998 -- Conversion of Atmospheric Electricity

H. Plauson: British Patent # 157,262 -- Improvements in Electric Motors

H. Plauson: British Patent # 157,263 -- Process & Apparatus for Converting Static Atmospheric Electrical Energy into Dynamic Electrical Energy...

***Science & Invention* (June 1928) - "Harnessing Nature's Electricity"**

H. Plauson : British Patent # 299735 -- Process for Producing Rapidly Moving Electrons [PDF]

H. Plauson : *Gewinnung und Verwertung der Atmosphatischen Elecktrizitat* (1922) [PDF]

---

http://en.wikipedia.org/wiki/Hermann_Plauson

Biography

Hermann Plauson was an Estonian engineer and inventor. Plauson investigated the production of energy and power via atmospheric electricity.

Plauson was the director of the Fischer-Tropsch "Otto Traun Research Laboratories" in Hamburg, Germany during the Weimar Republic of the 1920s. He built on Nikola Tesla's idea for connecting machinery to the "wheelwork of nature". Plauson's US Patent # 1,540,998 describes methods to convert alternating radiant static electricity into rectified continuous current pulses. He developed the Plauson's converter, an electrostatic generator. In 1920, Plauson published a book titled "*Production and Utilization of the Atmospheric Electricity*" (*Gr., Gewinnung und Verwertung der Atmospharischen Elektrizitat*). A copy of this book is in the British Library.

It is believed that he was related to Gertrud Plauson (the exact relationship is unknown; she may be his wife).

"Power from the Air". *Science and Invention* , Feb. 1922, no. 10. Vol IX, Whole No. 106. New York. (nuenergy.org)
"Power from the Air". *Science and Invention* , March 1922.

***Science and Invention,* Vol. IX (106) #10 (February 1922)**

Power from the Air (I)

by

Hugo Gernsback

During the war there was developed in Germany a new art --- or science --- that bids fair to revolutionize our present means of obtaining power.

This art, which is as new now as wireless was 25 years ago, will attain proportions during the next 25 years that may appear fantastic today. The inventor of the new science, an engineer of note, Herr Hermann Plauson, has devoted years of labor to his researches and he has now actually in use small power plants, that generate electricity direct from the air, day and night, without interruption at practically no cost, once the plant is constructed.

We had occasion, in one of our former issues, to describe the system, roughly, from cabled dispatches, but complete information is available now. The amount of electrical power that resides in our atmosphere is astounding. Herr Plauson found in his experiments that a single balloon sent aloft to a height of 300 yards gave a constant current at 400 volts of 1.8 amperes, or in 24 hours over 17-1/4 kilowatts! By using two balloons in connection with a special condenser battery, the power obtained was 81-1/2 kilowatts in 24 hours. The actual current delivered was 6.8 amperes at 500 volts.

The best balloons used by the inventor are made of thin aluminum leaf. No fabric was used. A simple internal system of ribs, stays and wires, gives the balloon rigidity as well as a certain amount of elasticity. The balloon, when made airtight, is filled with hydrogen or better, with helium. It will then stay aloft for weeks at a time. The outer surface is dotted with extremely sharp pins, made sharp electrolytically. Ordinary pins did not prove good current collectors, as they lacked extreme sharpness. The pins themselves were made from amalgamated zinc, containing a radium preparation, in order to ionize the air. It was also found that by dotting the outer surface of the balloon with zinc-amalgam more current could be collected. Even better results were obtained with polonium amalgam. Plauson states that the function of these amalgams is purely photoelectric.

One hundred of such captive balloons, separated one hundred yards from each other, will give a steady yield of 200 horsepower. This is the minimum, because in the winter this figure increases up to 400 horsepower, due to the higher electrification of the atmosphere.

We need not go into the technic of how the current is finally made useable for industrial purposes, suffice it to say that the problem has been entirely solved by Herr Plauson. By using batteries of condensers, high tension transformers, etc., the current can be transformed to any form desires. Such as for lighting lamps, running motors, charging storage batteries, etc.

Plauson also invented a sort of electrostatic rotary transformer which gives alternating current without the use of condensers and transformers. Indeed, its output is very great, as it actually ‘sucks’ the current down rapidly from the collector balloons. There is no doubt that this invention will soon come into universal use all over the world. We will see the land dotted with captive balloons, particularly in the country and wherever water power does not abound. Indeed, the time is not distant when nearly all of our power will be derived from the atmosphere. So far it seems to be the cheapest form of power known, it being much cheaper even than water power --- the cheapest form of power known today. Not only that, but as the inventor points out, no devastating thunder storms occur near such aerial power plants, because the balloons act not only as lightning arresters, but they quickly discharge the biggest thunder cloud, safely and noiselessly through their grounded spark gaps.

***Science & Invention* (March 1922), page 1006, 1007**

Power from the Air (II)

by

Hugo Gernsback

[For many years electrical engineers have endeavored to devise some means whereby it would become possible to utilize the free electrical energy ever present in the atmosphere, but they were not successful, as every now and then an extra heavy surge of static current would rush down the elevated conductor and endanger the lives of the experimenters, or else destroy the apparatus connected with it. A German engineer has, however, devised the somewhat elaborate scheme here shown in brief, and he has succeeded, at least so his report states, in safely extracting several kilowatts of electrical power from the atmosphere with metallic surfaced balloons, elevated to a height of only 1000 feet.]



©1922 BY SCIENCE AND INVENTION

We have previously treated of the extraction of electrical energy from the atmosphere. The difference of electric potential in different parts of the atmosphere, and the difference between the upper air and earth make it a tempting proposition to obtain power from atmospheric electricity. The power would take the form of high potential difference with a discharge almost of a static nature. It has long appeared rather doubtful to conservative engineers, if such a source of power should really be available. Yet when we see the lightning flash, it certainly suggests very high power, even though the total of its energy may be small, on account of the small duration of the discharge It is not to the thunder storm that we look for getting power from the atmosphere, as the subject is now being seriously investigated. A German scientist, Hermann Plauson, has published a very elaborate work on this subject, and has investigated the use of kites, balloons and towers, for the utilization of the high potentials existing in the air at different altitudes, and has studied out the construction of motors to be operated by the peculiar type of discharge which will be obtained, if the projects are successfully carried out.

We will first speak of the methods used for collecting electricity from the upper air. The author cites several German patents. One of them shows the use of a kite balloon. The balloon is shown floating in the air, kite fashion, and from it hangs a great net or aerial for the collection of electricity. The conductor from the aerial leads to the ground station; quite an elaborate description is given of the net-work which the patentee proposes to have covered with needle points. A windlass takes in or pays out cable for the balloon, and the patentee claims that by sending the apparatus to a height of about one mile he will have 225,000 volts to draw upon. He then speaks o a battery of 20,000 cells in series, which will use up to 40,000 to 50,000 volts in the charging. This certainly provides for a reasonable large fall of potential.

But our author discards this idea and first suggests something more permanent. He proposes the erection of towers to be in the neighborhood of 1,000 feet high, or about the height of the Eiffel Tower. At the summit he has his collecting aerial. The appliance consists of a number of copper tubes; within each one he proposes to burn gas lamps, whose products of combustion will reach the aerial, a collecting net-work covering the tops of the tubes. One of his apprehensions is that if rain should wet his connections trouble might ensue, so he proposes a protection at the top in the shape of a great bell-like shield, resembling in his terms “a Siamese pagoda”. He also compares the form of the protection to that of a great petticoat insulator. Another of his difficulties is that he must have his tower insulated from the earth. He, therefore describes a complicated foundation for his structure. He proposes first to pour in at the bottom of the excavation a foundation of simple concrete. On this he places a layer of asphalt, and then a layer of cast glass, three to ten feet thick, and then comes a reinforced concrete foundation, to which the metallic foot of the tower is to be anchored. This foundation must rise at least seven feet above the ground level, and is to be boarded in on all sides to protect it from moisture. The author’s idea s to erect a number of these towers connected by a horizontal cable, to which the aerials for collection of potentials are secured.

The author strongly advocates balloons as collectors of the electric power of the air. These he depicts covered with spots. These spots indicate areas to be variously coated and prepared to collect potential from the atmosphere.

In the first place he describes the balloon as made of thin metallic leaf supported by internal ribs. Steel wires silver-plated, copper-plated, or aluminum-coated, run from the balloon to the pendant or junction ring. To this ring the tether cable is attached and runs to an insulated windlass on the surface of the earth. The balloon is to rise to an altitude varying from 300 feet to three miles.

The coating of the spots is to be of the thinnest amalgam, of mercury and gold, or zinc, or even polonium, perhaps only 1/2500 inch thick. All over the upper face of the balloon are numberless metal points. To prepare the needle-like wires, they are collected into bundles and are treated electrolytically in a bath, so as to be dissolved in part. This gives a sharp point and roughened surface, all adapted for collecting the electric energy. The points may be of copper, steel, or some hard metallic alloy. After this corrosion. As it may be termed, the wires are plated with gold or other of the so-called noble metals. It is advised that polonium or radium salts be added to the plating bath.

Dr Plauson devotes many pages of his book to describing his motor. This is a rotary motor including a stator and rotor and its peculiarity is that it contains no coils, develops no electromagnetic field properly speaking, but works by static excitation. One typical arrangement is shown in our illustration. The stator plates and rotor plates are concentric with each other, representing segments of cylinders. The alternation of negative and positive charged plates produces the rotation. In the connections there is included a safety spark gap to take care of dangerous potentials. Inductances and capacities are also used and indicated. It was found that the plates heated, owing to the Foucalt currents, and to overcome this, several methods of subdividing the stator and rotor plates, are described by the author.

The whole subject is quite captivating, and it really seems as if the utilization of the electricity of the air may be almost in sight. It would seem possible to carry out experiments in this direction by means of the Eiffel Tower, but of course, the trouble here is that the tower is grounded, and perfect insulation of the collecting surface is absolutely essential.

And now our author gives us some practical details. He says that on the Finland plains he carried out experiments with a balloon made of aluminum leaf with collecting needles of amalgamated zinc with a radium preparation as an ionizer. The surface of the balloon was sprinkled over with zinc amalgam. It was sent up to a height of 300 meters, early 1,000 feet, and was held by a copper-plated steel wire. A constant current of 1.8 amperes at an average of 400 volts potential difference was obtained. This gave nearly three-quarters of a kilowatt, or close to one horsepower. The collector of the balloon insulated from the earth showed a tension of 42,000 volts. By sending up a second balloon with an antenna to the same height at a distance of 100 meters from the first balloon, a current of over 3 amperes was obtained. Then by putting into the circuit a large condenser, whose capacity was equal to the surface capacity of both balloons, and of the antenna connections, the current rose to 6.8 amperes with about 500 volts mean tension. By the use of these two balloons, he eventually ran up the power to 3.4 kilowatts.

Science & Invention (June 1928)


HARNESSING NATURE'S ELECTRICITY
INSULATORS
IRON CABLE
2200 FEET LONG
ADJUSTABLE SPARK GAP
260 FT.
INSULATED WIRES
CORONA OF BLUISH GREEN LIGHT
2,600,000 VOLTS - 1927
10,000,000 VOLTS EXPECTED-1928
TEST HUT 660 FEET FROM SPARK GAP

Remarkable European Experiments with Atmospheric Electrical Discharges with Potentials as High as 3,000,000 Volts

By HENRY TOWNSEND

elevation of 350 ft., and these students of natural electrical phenomena have found a very desirable location in the Alps, where they can suspend between one mountain and an adjacent one, a strong iron cable having a length of about 2,000 ft. This cable is about 250 feet above the intervening valley, and from it these daring engineers have suspended a coarsely woven wire net, which serves as an electrical capacity to gather the electricity from the atmosphere. As shown in the pictures, the wire net is supplied with numerous sharp points to aid in collecting the current from the air.

As the accompanying photographs of the actual apparatus and wire cable used last year clearly show, an adjustable spark gap of considerable length is provided. By adjusting this spark gap to various lengths, it is possible to judge the voltage of the discharge which leaps the gap at any moment. Mr. F. W. Peek, Jr., the well-known American worker in the realm of high voltage measurements, together with other engineers, have provided tabulated data and curves for various lengths of both needle and sphere type spark gaps. As one of the accompanying diagrams shows, it is a simple matter to calculate the voltage when a certain length of gap is used. The engineer first checks the length of the gap on the chart; he then follows a line horizontally from the gap length, to where it intersects with the angular line on the chart; and from the point of intersection he looks in a visual line downward to a place where the voltage is given. For needle spark gap measurements, the characteristic curve on the chart is practically a straight line, while for sphere gaps the characteristic curve on the voltage versus gap length, is a curved line. Those interested in high voltage measurements by means of the spark gap method can find the voltage-gap tables and charts in the *Standardization Rules* of the American Institute of Electrical Engineers. According to Mr. Peek's researches, the voltage per foot of atmospheric electrical discharges is about 100,000, while in laboratory measurements with A.C., transformer high potential discharges, the average voltage per foot of spark was found to be about 150,000 volts. The voltage of a lightning flash may

(*Continued on page* 156)



↑ Actual photo above shows 13 ft., heavy spark obtained from the collecting net in the Alps by the German scientists. The voltage is about 2,000,000. The spark occurred once per second for 30 minutes.



Photo, left, shows the adjustable spark gap used in the Alps. Notice the heavy electrode on the end of the adjustable arm to which the spark jumps.

←

Below we see 3,000,000-volt artificial lightning stroke produced in G. E. Laboratory at Pittsfield, Mass. Note man. ↓

Actual photograph of the experimental "kite" used by the German experimenters in the Alps Mountains, for the purpose of accumulating high potential electrical discharges from the atmosphere. Note the size of the insulators.





if-

you pledge
yourself to secrecy we will teach you the secrets of
Real Professional
Magic

Dr. Harlan Tarbell, internationally known magician and teacher of some of the world's greatest magicians.

Learn to be a Magician

For the first time in the history of Magic the age-old, sacredly guarded secrets of the Mystic Art are being revealed. Now at last you can learn to be a Real Professional Magician. Yes, and you can learn this wonderful art *easily and quickly* AT HOME. You are taught the mysterious *Principles* by which the Professional Magician works. You are taught everything from wonderful impromptu effects to massive stage illusions. But before you can study, you must sign the Magician's Solemn Pledge of Secrecy. This means that you are getting the *guarded secrets* of the Magic Profession. Think of that!

Earn $250 to $1000 a Month
There's a big demand for Magic entertainment. Magicians get big money. Dr. Tarbell gets as high as $250 for a half hour's work. Unlimited opportunities for you!

Low Prices Easy Terms

Write Today Send today for free Magic book, low prices and easy terms. Don't delay. Mail the coupon NOW!

Tarbell System, Inc., Studio A-142
1920 Sunnyside Avenue, Chicago, Ill.
Gentlemen: Without any obligation send me your free literature and information all about your wonderful "Tarbell Course in Magic." Also tell me about your Low Price Offer and Easy Payment Plan.

Name..

Address..

.... *Age*........

HARNESSING NATURE'S ELECTRICITY

By HENRY TOWNSEND

(*Continued from page* 111)



Remarkable cathode ray oscillograph used by Mr. F. W. Peek, Jr., in causing lightning to write its autograph with a pencil of electrons on a photographic film.

easily be 100,000,000 volts, as Mr. Peek has pointed out in one of his scientific papers.

WHY THE EXPERIMENTS ARE BEING MADE

ONE of the main reasons why these dangerous experiments are being carried on by the three young German scientists, whose names we have already learned, is because science believes that with a sufficiently high voltage, it will be possible for man to disintegrate the atom, and in this way make available a tremendous source of power as yet untapped. These experts have calculated that they will be able to obtain electrical energy in sufficient quantity from one of these powerful atmospheric discharges, to equal the Alpha rays obtained from 220 pounds of radium. As we have mentioned before, these experiments are of course fraught with great danger, and for that reason the experimenters seek refuge in a special lightning-proof hut, which is located about 600 ft., from the spark gap. When electrical storms are in the vicinity, it is especially important that the scientists keep within their protected fortress, for otherwise they would very probably be killed by a stray electrical discharge.

One of the peculiar things about this whole line of experiment is that the average layman does not realize perhaps, that there is a high electrical stress in the atmosphere on clear days, as well as when thunder storms are overhead. This fact has been known for a hundred years and more, and many years ago measurements of the various electrical potentials at increasing altitudes, were observed and measured by scientific investigators. There are a number of different ways in which these high electrical potentials found in the atmosphere can be measured; one of these methods involves the use of a calibrated spark gap. In this case the gap is set to a predetermined length, and when a discharge jumps this gap, the engineers know of course from previous experience and measurements, just what voltage is present. Another method of measuring extra high potentials, such as here encountered, requires the use of a static voltmeter, which involves the use of a stationary and of a movable or rotary set of metal plates, forming a condenser, to which an indicating needle is attached. For voltages above 2,000, static voltmeters have been used in a great many American central stations, and they have many desirable and useful characteristics. Of course as the voltage to be measured increases, the space between the quadrant shaped stationary and movable plates is increased and vice versa. The electrostatic field from voltages below 2,000 is not sufficient to warrant the use of a static voltmeter. Another method of measuring high potentials involves the use of the so-called vacuum tube voltmeter.

The general characteristics of the atmospheric electrical discharges, including lightning, have been measured and recorded by one of the newest scientific instruments, known as the cathode ray oscillograph. By means of this quite remarkable, high voltage scientific apparatus, Mr. Peek, one of the well-known General Electric Company staff of research engineers, has made some very interesting and remarkable discoveries concerning the nature of natural electrical discharges, particularly of lightning discharges. Many people will probably wonder why Mr. Peek and some of his colleagues in the engineering profession, including the three daring German students, Messrs. Brasch, Lange and Urban, play with such dangerous electrical discharges, and why they are at all interested in them. We explained previously why the German savants are intent on finding out all they can about these tremendous voltages obtained from the atmosphere, while Mr. Peek, we may say, also has a very practical reason for carrying on experiments with these death-dealing bolts of Thor. Mr. Peek has been for many years intent on finding out what causes the huge insulators on long distance, high potential transmission lines to break down when electrical storms break loose over these regions.

Plauson's Electrical Patents

USP # 1,540,998
Conversion of Atmospheric Electric Energy
6-09-1925

GB157262
Improvements in Electric Motors
1922-07-10

GB157263
Process and Apparatus for Converting Static Atmospheric Electrical Energy into Dynamic Electrical Energy of any Suitable High Periodicity
7-10-1922

British Patent # 299,735
Apparatus for Producing Rapidly Moving Electrons
7-15-1930

FI21227
Elektrisk uppvärmningsanordning
4-25-1946

Varmelegeme med elektriske varmemodstande
DK67691C
9-27-1948

FR877362
Dispositif de chauffage électrique
12-04-1942

DE734794
Elektrisches Heizsystem
4-24-1943

CH222509
Elektrischer Heizkörper zur Erwärmung von Flüssigkeiten
7-31-1942

DE738107
Elektrolyt fuer unmittelbare elektrische Warmwasser-Radiatorenheizung mit Elektroden
8-03-1943

DE433476
Verfahren zur Herstellung von Elektroden und Schleifkontakten fuer Dynamomaschinen
8-31-1926

CH94021
Elektrode und Verfahren zu deren Herstellung
4-01-1922

CA226423
Electrode for Electrolytic Apparatuses
11-21-1922

---

http://www.meridian-int-res.com/Energy/Atmospheric.htm

Atmospheric Electricity Research
[Excerpts]

In the nineteenth and early twentieth centuries, a large number of researchers investigated ways to extract electrical power from the Earth's ambient electric field.

The leader in this field was Dr Hermann Plauson who in the 1920s succeeded in generating significant quantities of electrical power comparable with modern solar photovoltaic systems of a similar scale...

The leader in this field before the Second World War appears to have been Dr Hermann Plauson. Dr Plauson was an Estonian citizen who lived in Hamburg and Switzerland. He carried out experiments in Finland with aerostats manufactured from magnesium-aluminium alloy, covered with electrolytically deposited needles. The needles were further doped with a radium compound to increase local ionisation of the air. (This was the era in which the hands of watches were hand painted with radium to make them luminous in the dark). Zinc amalgam patches were also painted onto the aerostats. Plauson obtained a power output of between 0.72kW and 3.4kW from one and two aerostats 300m above ground level. Dr Plauson filed patents in the USA, Great Britain and Germany in the 1920s. His book "Gewinnung und Verwertung der Atmosphärischen Elektrizität" is the most detailed known account of the technology.

Other atmospheric electricity researchers contemporary to Dr Plauson included Walter Pennock and MW Dewey in the USA, Andor Palencsar in Hungary and Dr Heinrich Rudolph in Germany. Hippolyte Charles Vion in Paris predated them all, putting forward proposals in the 1850s and 1860s.

Heinrich Rudolph made an interesting contribution to the design of the aerostat collectors. In 1898 he designed an elliptical aerostat made up of faceted surfaces to minimise the effect of wind. The design bears a strong resemblance to Northrop's 2003 UCARS unamnned helicopter UAV project. The design uses the Coanda Effect to help keep the aerostat on station and minimise wind effects.

In recent times, the only person who seems to have been active in this field is Dr Oleg Jefimenko. Dr Jefimenko carried out experiments on driving electrostatic motors from the Earth's electric field in the 1970s and has recently called for research into the neglected field of electrostatic motors to be renewed.

MIR's Research Programme

Since 1997 we have been carrying out theoretical research into conversion of atmospheric electricity into useable electrical power.

From a low level (5m high) simple zinc antenna we are able to obtain sufficient charge to light a number of white power LEDs. Further experimental investigations with metallic aerostat collectors and cavity resonant slow wave antennae concepts are ongoing...

Advantages of Atmospheric Electricity

Simple and robust technology
Low Cost technology - much cheaper than photovoltaics or wind turbines
Available day and night in all weather conditions - in fact, more power is produced at night than during the day
Available at any point on the Earth's surface

1. *Gewinnung und Verwertung der Atmosphärischen Elektrizität*, Dr Hermann Plauson, Hamburg, (1920)
2. Conversion of Atmospheric Electric Energy, USP 1,540,998, Dr Hermann Plauson, (1925)
3. Assembly for the Induction of Lightning into a Superconducting Magnetic Energy Storage System, USP 5,367,245 Goven Mims, (1994)
4. Electrostatic Motors are Powered by Electric Field of the Earth; CL Stong, *Scientific American*, (October 1974)
5. Operation of Electric Motors from the Atmospheric Electric Field; Dr Oleg Jefimenko, *American Journal of Physics*, vol. 39, July 1971.
6. *Electrostatic Motors: Their Principles, Types and Theory of Operation*; Dr Oleg Jefimenko, Electret Scientific, (1972).
7. Parametric Electric Machine, USP 4,622,510, Ferdinand Cap, (1986).

US Patent # 1,540,998

Conversion of Atmospheric Electric Energy

(9 June 1925)

Hermann PLAUSON

Be it known that I, Hermann Plauson, Estonian subject, residing in Hamburg, Germany, have invented certain new and useful improvements in the Conversion of Atmospheric Electric Energy, of which the following is a specification.

Methods of obtaining atmospheric electricity by means of metallic nettings set with spikes which are held by means of ordinary or anchored kite balloons made of fabric and filled with hydrogen, are in theory already known. Atmospheric electricity obtained in this way has been suggested to be used in the form of direct current for the charging of accumulators. This knowledge however is at present only theoretical as the conversion in practice has hitherto been a failure. No means are known of protecting the apparatus from destruction by lightning. The balloons used for collecting the charge must also me be made of very large size in order to be able to support the weight of the metallic netting and the heavy cable connections.

Instead of using heavy metallic netting as collectors attached to single air ballons of non-conducting materials which are liable to be torn and are permeable to the gas, it is proposed to use metallic balloon collectors which have the following important advantages ---

(a) The metallic cases are impenetrable to helium and hydrogen; they also represent large metallic weather-proof collecting surfaces.

(b) Radio active means the like may be easily applied internally or externally; whereby the ionization is considerable increased and therewith also the quantity of atmospheric electricity capable of being collected.

(c) Such balloon collectors of light metal do not require to be of large size as they have to carry only their own moderate weight, and that of the conducting cable or wire.

(d) The entire system therefore offers little surface for the action of storm and wind and is resistant and stable.

(e) Each balloon can be easily raised and lowered by means of a winch so that all repairs, recharging and the like can be carried out without danger during the operation.

It is further proposed to use a collecting aerial network of several separate collectors spread out in the air above the earth, which collectors are interconnected by electrical conductors.

According to this invention charges of atmospheric electricity are not directly converted into mechanical energy, and this forms the main difference from previous inventions, but the static electricity which runs to earth through aerial conductors in the form of direct current of very high voltage and low current strength is converted into electro-dynamic energy in the form of high frequency vibrations. Many advantages are thereby obtained and all disadvantages avoided.

The very high voltage of static electricity of a low current strength can be converted by this invention to voltages more suitable for technical purposes and of greater strength. By the use of closed oscillatory circuits it is possible to obtain electromagnetic waves of various amplitude and thereby to increase the degree of resonance of such current. Such resonance allows various values of inductance to be chosen whereby again the governing of the starting and stopping of machines driven thereby by simply tuning the resonance between coils of the machine and the transformer circuit forming the resonance can easily be obtained. Further, such currents have the property of being directly available for various uses, even without employing them for driving motors, of which there may be particularly mentioned, lighting, production of heat and use in electro-chemistry.

Further, with such currents a series of apparatus may be fed without direct current supply through conductors and also the electro-magnetic high frequency currents may be converted by means of special motors adapted for electro-magnetic oscillations into mechanical energy, or finally converted by special machines into alternating current of low frequency or even into direct current of high potential.

The invention is more particularly described with reference to the accompanying diagrams in which: ---

Figure 1 is and explanatory figure.

Figure 2 is a diagrammatic view of the simplest form.

Figure 3 shows a method of converting atmospheric electrical energy for use with motors.

Figure 4 is a diagram showing the use of protective means.

Figure 5 is a diagram of an arrangement for converting large current strengths.

Figure 6 is a diagram of an arrangement including controlling means.

Figure 7 shows means whereby the spark gap length can be adjusted.

Figure 8 shows a unipolar connection for the motor.

Figure 9 shows a weak coupled system suitable for use with small power motors.

Figures 10, 11, and 12 show modified arrangements.

Figure 13 shows a form of inductive coupling for the motor circuit.

Figure 14 is a modified form of Figure 13 with inductive coupling.

Figure 15 is an arrangement with non-inductive motor.

Figure 16 is an arrangement with coupling by condenser.

Figure 17, 18, and 19 are diagrams of further modifications.

Figure 20 shows a simple form in which the serial network is combined with special collectors.

Figure 21 shows diagrammatically an arrangement suitable for collecting large quantities of energy.

Figure 22 is a modified arrangement having two rings of collectors.

Figure 23 shows the connection for three rings of collectors.

Figure 24 shows a collecting balloon and diagram of its connection of condenser batteries.

Figure 25 and 26 show modified collector balloon arrangements.

Figure 27 shows a second method of connecting conductor for the balloon aerials.

Figure 28 shows an auto-transformer method of connection.

Figure 29 shows the simplest form of construction with incandescent cathode.

Figure 30 shows a form with cigar shaped balloon.

Figure 31 is a modified arrangement.

Figure 32 shows a form with cathode and electrode enclosed in a vacuum chamber.

Figure 33 is a modified form of Figure 32.

Figure 34 shows an arc light collector.

Figure 35 shows such an arrangement for alternating current.

Figure 36 shows an incandescent collector with Nernst lamp.

Figure 37 shows a form with a gas flame.

Fig. 1.



Fig. 2.



Figure 1 illustrates a simple diagram for converting static electricity into dynamic power of a high number of oscillations. For the sake of clearness in the drawings an influence machine is assumed to be employed and not an aerial antenna. 13 and 14 are combs for collecting the static electricity of the influence machine. 7 and 8 are spark discharging electrodes. 5 and 6 are condensers, 9 an inductive primary coil, 10 secondary coil, 11 and 12 ends of conductors of the secondary coil 10. When the disc of the static influence machine is rotated by mechanical means, the combs collect the electric charges one the positive and the other the negative, and charge the condensers 5 and 6 until such a high potential is formed across the spark gap 7-8, that the spark gap is jumped. As the spark gap 7-8 forms a closed circuit with condensers 5 and 6, and inductive resistance 9, as is well known, waves of high frequency electromagnetic oscillations will pass in this circuit.

The high frequency of the oscillations produced in the primary circuit induces waves of the same periodicity in the secondary circuit. Thus in the primary circuit electromagnetic oscillations are formed by the passage of the spark over the spark gap and these waves are maintained by fresh charges of static electricity.

By suitably selecting the ratio between the number of the coils in the primary and secondary circuits with regard to a correct application of the co-efficients of resonance (especially, inductance and resistance) the high voltage of the primary circuit may be suitably converted into low voltage and high current strength.

When the oscillatory discharges in the primary circuit becomes weaker or entirely cease, the condensers are charged again by the static electricity until the accumulated charge again breaks down the spark gap. All this is repeated as long as electricity is produced by the static machine employing mechanical energy.

An elementary form of the invention is shown in Figure 2 in which two spark gaps in parallel are used one of which may be termed the working gap 7 in Figure 2, whilst the second serves as a safety device for excess voltage and consists of a larger number of spark gaps than the working section, which gaps are arranged in series and are bridged by very small capacities as is illustrated in a, b, c, Figure 2 which allow of uniform sparking in the safety section.

In Figure 2 A is the aerial antenna for collecting charges of atmospheric electricity. 13 is the earth connection of the second part of the spark gap, 5 and 6 are condensers, 9 a primary coil. Now when through the aerial A the positive atmospheric electricity seeks to combine with the negative charge to earth, this is prevented by (the air gap between) the spark gaps. The resistance of the spark gap 7 is, as shown in the drawings, lower than that of the other safety section which consists of three spark gaps connected in series, and consequently a three times greater air resistance is offered by the latter.

So long, therefore, as the resistance of the spark gap 7 is not overloaded, so that the other spark gaps have an equal resistance with it the discharges take place only over spark gap 7. Should however the voltage be increased by and influences so that it might be dangerous for charging the condensers 5 and 6 or for the coil insulation 9 and 10 in consequence of break down, by a correct regulation of this spark gap the second spark gap can discharge free from inductive effects direct to earth without endangering the machine.

Without this second spark gap, arranged in parallel having a higher resistance than the working spark gap it is impossible to collect and render available large quantities of electrical energy.

The actions of this closed oscillation circuit consisting of spark gap 7, two condensers 5 and 6, primary coil 9, and also secondary coil 10 is exactly the same as the one described in Figure 1 with the arrangement of the static induction machine with the only difference that here the second spark gap is provided. The electromagnetic high frequency alternating current obtained can be tapped off from the conductors 11 and 12 for lighting and heating purposes. Special kinds of motors adapted for working with these peculiar electrical charges may be connected at 14 and 15 which can work with static electricity charges or with high frequency oscillations.

In addition to the use of spark gaps in parallel a second measure of security is also necessary for taking off the current. This precaution consists according to this invention, in the introduction of and method of connecting certain protective electromagnets or choking coils in the aerial circuit as shown by S in Figure 3.

A single electromagnet only having a core of the thinnest possible separate laminations is connected with the aerial.

In the case of high voltages in the aerial network or at places where there are frequent thunder storms, several such magnets may however be connected in series.

In the case of large units or plants several electromagnets can be employed in parallel or in series parallel.

The windings of these electromagnets may be simply connected in series with the aerials. In this case the winding preferably consists of several thin parallel wires, which make up together, the necessary section.

The winding may be made of primary and secondary windings in the form of a transformer. The primary windings will be then connected in series with the aerial network, and the secondary winding more or less short-circuited over a regulating resistance or an induction coil. In the latter case it is possible to regulate to a certain extent the effect of the choking coils. In the further description of the connecting and constructional diagrams the aerial electromagnet choke coil is indicated by a simple ring S.


Fig. 3.


Fig. 4.


Fig. 5.


Fig. 6

Figure 3 shows the simplest way of converting atmospheric electricity into electromagnetic wave energy by the use of special motors adapted for high oscillatory currents or static charges of electrical energy. Recent improvements in motors for working with static charges and motors working by resonance, that is to say, having groups of tuned electromagnetic cooperating circuits render this possible but such do not form part of the present invention.

A motor adapted to operate with static charges will for the sake of simplicity be diagrammatically indicated by the two semicircles 1 and 2 and the rotor of the motor by a ring M (Figure 3). A is a vertical aerial or aerial network. S the safety choke or electromagnet with coil O as may be seen is connected with the aerial A. Adjacent the electromagnet S the aerial conductor is divided into three circuits, the circuit 8 giving the safety spark gap, the circuit 7 with the working spark gap, and then a circuit including the stator terminal 1, the rotor and stator terminal 2 at which a connection is made to the earth wire. The two spark gaps are also connected metallically with the earth wire. The method of working these diagrams is as follows:

The positive atmospheric electric charge collected tends to combine with the negative electricity (or earth electricity) connected with the earth wire. It travels along the aerial A through the electromagnet S without begin checked as it flows in the same direction as the direct current. Further, its progress is arrested by two sparks gaps placed in the way and the stator condenser surfaces. The stator condenser surfaces are charged until the charge is greater than the resistance of the spark gap 7, whereupon a spark springs over the spark gap 7 and an oscillatory charge is obtained as by means of the motor M, stator surfaces 1 and 2, and spark gap 7, a closed oscillation circuit is obtained for producing the electromagnetic oscillations. The motor here forms the capacity and the necessary inductance and resistance, which, as is well known, are necessary for converting static electricity into electromagnetic wave energy.

The discharge formed are converted into mechanical energy in special motors and cannot reach the aerial network by reason of the electromagnet or choke. If, however, when a spark springs over the spark gap 7 a greater quantity of atmospheric electricity tends to flow to earth, a counter voltage is induced in the electromagnet, which is greater the more rapidly and strongly the flow of current direct to the earth is. By the formation of this opposing voltage a sufficiently high resistance is offered to the flow of atmospheric electricity direct to earth to prevent a short circuit with the earth.

The circuit containing spark gap 8 having a different wave length which is not in resonance with the natural frequency of the motor, does not endanger the motor and serves as security against excess voltage, which, as practical experiments have shown, may still arise in certain cases, but can be conducted direct to earth through this spark gap.

In the diagram illustrated in Figure 4 the spark gap 7 is shunted across condensers 5 and 6 from the motor M. This construction affords mainly a better insulation of the motor against excess voltage and a uniform excitation through the spark gap 7.

In Figure 5 a diagram is illustrated for transforming large current strengths which may be employed direct without motors, for example, for lighting or heating purposes. The main difference is that here the spark gap consists of as star shaped disk 7 which can rotate on its own axis and is rotated by a motor opposite similarly fitted electrodes 7a. When separate points of stars face one another, discharges take place, thus forming an oscillation circuit over condensers 5 and 6, and inductance 9 for oscillatory discharges. It is evident that a motor may also be directly connected to the ends of the spiral 9.

The construction of the diagram shown in Figure 6 permits of the oscillation circuit of the motor being connected with an induction coil/ Here a regulating inductive resistance is introduced for counter-acting excess voltages in the motor. By cutting the separate coils 9 (coupled inductively to the aerial) in or out the inductive action on the motor may be more or less increased or variable aerial action may be exerted on the oscillation circuit.

Filed Jan. 13, 1921 12 Sheets-Sheet 2



In Figure 7 the oscillation circuit is closed through the earth (E and E1). The spark gap 7 may be prolonged or shortened by more or fewer spark gaps being successively connected by means of a contact arm 7b.

Diagram 8 shows a unipolar connection of the motor with the aerial network. Here two oscillation circuits are closed through the same motor. The first oscillation circuit passes from aerial A through electromagnet S, point *x*, inductance 9a to the earth condenser 6 and further, over spark gap 7 to the aerial condenser 5 and back to *x*. The second oscillation circuit starts from the aerial condenser 5 at the point x^1 over the inductance 9 to the earth condenser 6 at the point x^3 and through the condenser 6 over the spark gap 7 back to x^1. The motor itself is inserted between the two points of the spark gap 7. From this arrangement slightly damped oscillation wave currents are produced.

In the diagram illustrated in Figure 9 a loosely coupled system of connections is illustrated which is assumed to be for small motors for measuring purposes. A indicates the aerial conductor, S the electromagnet in the aerial conductor, 9 the inductance, 7 the spark gap, 5 and 6 condensers, E the earth, M the motor, and 1 and 2 stator connections of the motor. The motor is directly metallically connected with the oscillation circuit.

In Figure 10 a purely inductive coupling is employed for the motor circuit. The motor is connected with the secondary wire 10 as may be seen in Figure 11 in a somewhat modified diagram connection. The same applies to the diagram of Figure 12.

The diagrams hitherto described preferably allow of motors of small and medium strength to be operated. For large aggregates, however, they are too inconvenient as the construction of two or more oscillation circuits for large amounts of energy is difficult; the governing is still more difficult and the danger in switching on or off is greater.

A means of overcoming such difficulties is shown in Figure 13. The oscillation circuit here runs starting from the point x over condenser 5, variable inductance 9, spark gap 7, and the two segments (3a and 4a) forming arms of a Wheatstone bridge, back to x, If the motor is connected by brushes 3 and 4 transversely to the two arms of the bridge as shown in the drawings, electromagnetic oscillations of equal sign are induced in the stator surfaces 1 and 2 and the motor does not revolve. If however the brushes 3 and 4 are moved in common with the conducting wires 1 and 2 which connect the brushes with the stator poles a certain alteration or displacement of the polarity is obtained and the motor commences to revolve.

The maximum action will result if one brush 3 comes on the central sparking contact 7 and the other brush 4 on the part *x*. They are however, usually in practice not brought on the central contact 7 but only held in the path of the bridge segments 4a and 3a in order not to connect the spark gaps with the motor oscillation circuit.

Filed Jan. 13, 1921 12 Sheets-Sheet


Fig. 14.


Fig. 15.


Fig. 16.


Fig. 17.


Fig. 18.


Fig. 19.


Fig. 20.

Inventor
Hermann Plauson
by Knight Bros
Attorneys

As however, the entire oscillation energy can thereby not act on the motor it is better to carry out the same system according to the diagram 14. The diagram 14 differs from the foregoing only by the motor not being directly metallically connected with the segments of the commutator, but only a primary coil 9 which induces in a secondary coil 10, current which feeds the motor M and takes the place of the rotor. By this arrangement a good transforming action is obtained, a loose coupling and also an oscillation circuit without a spark gap.

In Figure 15 the motor is not purely inductive as in 14, but directly metallically branched off from the primary coil (at *x* and x^1) after the principle of the auto-transformer.

In Figure 16 instead of an inductance a condenser 6 is in similar manner, and for the same object inserted between the segments 3a and 4a. This has the advantage that the segments 3a and 4a need not be made of solid metal but may consist of spiral coils whereby a more exact regulation is possible and further motors of high inductance may be employed.

The arrangements of Figures 17, 18 and 19 may be employed for use with resonance and particularly with induction condenser motors; between the large stator induction condenser surfaces, small reversing pole condenser surfaces, mall reversing pole condensers are connected, which, as may be seen from Figures 17, 18 and 19 are led together to earth. Such reversing poles have the advantage that with large quantities of electrical energy the spark formation between the separate oscillation circuits ceases.

Figure 19 shows a further method which prevents electromagnetic oscillations of high number of alternations formed in the oscillation circuit striking back to the aerial conductor. It is based on the well known principle that a mercury lamp, one electrode of which is formed of mercury, the other of solid metal such as steel allows an electric charge to pass in only one direction from the mercury to the steel and not vice versa. The mercury electrode of the vacuum tube N is therefore connected with the aerial conductor and the steel electrode with the oscillation circuit. From this it results that charges can pass only from the aerial through the vacuum tube to the oscillation circuit, but not vice versa. Oscillations which are formed on being transformed in the oscillation circuit cannot pass to the aerial conductor.

In practice these vacuum tubes must be connected behind an electromagnet as the latter alone affords no protection against the danger of lightning.

As regards the use of spark gaps, all arrangements as used for wireless telegraphy may be used. Of course the spark gaps in large machines must have a sufficiently large surface. In very large stations they are cooled in liquid carbonic acid or better still in liquid nitrogen or hydrogen; in most cases the cooling may also take place by means of liquefied low homologues of the metal series or by means of hydrocarbons the freezing point of which lies at between –90° C and –40° C. The spark gap casing must also be insulated and be of sufficient strength to be able to resist any pressure which may arise. Any undesirable excess super-pressure which may be formed must be automatically let off. I have employed wit very good results mercury electrodes which were frozen in liquid carbonic acid, the cooling being maintained during the operation from the outside through the walls.

Figure 20 is one of the simplest forms of construction of an aerial network in combination with collectors, transformers and the like illustrated diagrammatically. E is here the earth wire, 8 the safety spark gap, 7 the working spark gap, 1 and 2 the stator surfaces of the motor, 5 a condenser battery, S the protective magnet which is connected with the coil in aerial conductor, A^1 to A^{10} aerial antennae with collecting balloons, N horizontal collecting or connecting wire from which, to the center a number of connections run.

The actual collectors consist of metal sheaths preferably made of an aluminum magnesium alloy, and are filled with hydrogen or helium and are attached t copper plated steel wires. The size of the balloon is selected so that the actual weight of the balloon and the weight of the conducting wire is supported thereby. On top of the balloon aluminum spikes, made and gilded in a special manner hereinafter described, are arranged in order to produce a conductor action. Small quantities of radium preparations, more particularly polonium-ionium or meso-thorium preparations considerably increase the ionization, and therewith the action of these collectors.

In addition to metal balloons, fabric balloons which are superficially metal coated according to Schoop's metal spraying process, may also be employed. A metallic surface may also me produced by lacquering with metallic bronzes, preferably according to Schoop's spraying process or lacquering with metallic bronze powders in two electrical series of widely different metals, because thereby the collecting effect is considerably increased.

Instead of the ordinary round balloons, elongated cigar shaped ones may be employed. In order also to utilize the frictional energy of the wind, patches or strips of non-conducting substances which produce electricity by friction, may be attached to the metalized balloon surfaces. The wind will impart a portion of its energy in the form of frictional electricity, to the balloon casing, and thereby the collecting effect is substantially increased.

In practice however, very high towers (up to 300 meters is fully admissible) may be employed as antennae. In these towers copper tubes rise freely further above the top of the tower. A gas lamp secured against the wind is then lit at the point of the copper tube and a netting is secured to the copper tube over the flame of this lamp to form a collector. The gas is conveyed through the interior of the tube up to the summit. The copper tube must be absolutely protected from moisture at the place at which it enters the tower and also rain must be prevented running down the walls of the tower which might lead to a bad catastrophe. This is done by bell shaped enlargements which expand downwards, being arranged in the tower in the form of high voltage insulators of Siamese pagodas.

Special attention must be devoted to the foundations of such towers. They must be well insulated from the ground, which may be obtained by first embedding a layer of concrete in a box form to a sufficient depth in the ground and inserting in this an asphalt lining and then glass bricks cast about 1 or 2 meters in thickness. Over this in turn there is a ferro-concrete layer in which alone the metal foot of the tube is secured. This concrete block must be at least 2 meters from the ground and be fully protected at the sides by a wooden covering, from moisture. In the lower part of the tower a wood or glass house for the large condenser batteries or for the motors may be constructed. In order to lead the earth connection to the ground water, a well insulated pit constructed of vitreous brick, must be provided. Several such towers are erected at equal distances apart and connected with a horizontal conductor. The horizontal connecting wires may either run directly from tower to tower or be carried on bell shaped insulators similar to those in use for high voltage conductors. The width of the network may be of any suitable size and the connection of the motors can take place at any suitable places.

Fig. 21. Fig. 22.



Fig. 23.

In order to collect large quantities of electricity with few aerials it is well to provide the aerial conductor with batteries of condensers as shown in Figures 21 and 22. In Figure 21 the batteries of condensers 5 are connected on the one hand with the aerial electricity collectors Z by the aerial conductor A, and on the other hand interconnected in series with an annular conductor from which horizontal conductors run to the connecting points C to which the earth wire is connected.

Figure 22 shows a similar arrangement, Should two such series of antennae rings be shown by a voltmeter to have a large difference of potential (for example, one in the mountains and one in the plain) or even of different polarity these differences may be compensated for by connecting sufficiently large condenser batteries (5, 5a, 5b) by means of Maji star conductors D and D^1. In Figure 23 a connection of three such rings of collectors to form a triangle with a central condenser battery is illustrated.

The condenser batteries of such large installations must be embedded in liquid gases or in liquids freezing at very low temperatures. In such cases a portion of the atmospheric energy must be employed for liquefying these gases. It is also preferable to employ pressure. By this means the condenser surfaces may be diminished, and still allow for large quantities of energy to be stored, secure against breakdown. For smaller installation the immersing of the condensers in well-insulated oil or the like, suffices. Solid substances on the other hand cannot be employed as insulators.

The arrangement in the diagrams hitherto described was always such that the condenser batteries were connected with both poles directly to the aerial condensers. An improved diagram of the connections for obtaining atmospheric electricity for the condenser batteries has however, been found to be very advantageous. This arrangement consists in that they are connected only by one pole (unipolar) to the collecting network. Such a method of arrangement is very important, as by means of it a constant current and an increase of the normal working pressure or voltage is obtained. If for example a collecting balloon aerial which is allowed to rise to a height of 300 meters, shows 40,000 volts above earth voltage, in practice it has been found that the working voltage (with a withdrawal of the power according to the method hereinbefore described by means of oscillating spark gaps and the like) is only about 400 volts. If however, the capacity of the condenser surfaces be increased, which capacity in the above mentioned case was equal to that of the collecting surface of the balloon aerials, to double the amount, by connecting the condenser batteries with only one pole, the voltage rises under an equal withdrawal of current up to and beyond 500 volts. This can only be ascribed to the favorable action of the connecting method.

In addition to this substantial improvement it has also been found preferable to insert double inductances with electromagnets and to place the capacities preferably between two such electromagnets. It has also been found that the useful action of such condensers can be further increased if an induction coil be connected as inductive resistance to the unconnected pole of the condenser, or still better if the condenser itself be made as an induction condenser. Such a condenser may be compared with a spring which when compressed carries in itself accumulated force, which it again gives off when released. In charging, a charge with reversed sign is formed at the other free condenser pole, and if through the spark gap a short circuit results, the accumulated energy is again given back since now new quantities of energy are induced at the condenser pole connected with the conductor network, which in fact charges with opposite signs to that at the free condenser pole. The new induced charges have of course the same sign as the collector network. The whole voltage energy in the aerial is thereby however increased. In the same space of time larger quantities of energy are accumulated than is the case without such inserted condenser batteries.


Fig. 24.


Fig. 25.

In Figures 24 and 25 two different diagrams of connections are more exactly illustrated, Figure 24 shows a collecting balloon and the diagram of the connections to earth. Figure 25 shows four collecting balloons and the parallel connection of the condenser batteries belonging thereto.

A is the collecting balloon made of an aluminum magnesium alloy (electron metal, magnalium) of a specific gravity of 1.8 and a thickness of plate 0.1 to 0.2 mm. Insider there are eight strong vertical ribs of T-shaped section about 10 to 20 mm in height and about 3 mm in thickness with the projecting part directed inwards (indicated by a, b, c, d and so forth); they are riveted together to form a firm skeleton and are stiffened in a horizontal direction by two cross ribs. The ribs are further connected with one another internally and transversely by means of thin steel wires, whereby the balloon obtains great power of resistance and elasticity. Rolled plates of 0.1 to 0.2 mm in thickness made of magnalium alloy are then either soldered or riveted on this skeleton so that a fully metallic casing with smooth external surface is obtained Well silvered or coppered aluminum plated steel wires run from each rib to the fastening ring 2. Further, the coppered steel hawser L preferably twisted out of separate thin wires (shown in dotted lines in Figure 24) and which must be long enough to allow the balloon to rise in the desired height, leads to a metal roller or pulley 3 and from thence to a winch W, well insulated from the earth. By means of this winch, the balloon, which is filled with hydrogen, or helium, can be allowed to rise to a suitable height (300 to 5000 meters) and brought to the ground for recharging or repairs.

The actual current is taken directly through a friction contact from the metal roller 3 or from the wire, or even from the winch or simultaneously from all three by means of brushes (3, 3a and 3b). Beyond the brushes the conductor is divided, the paths being: --- firstly over 12 to the safety spark gap 8, from thence to the earth conductor E^1, and secondly over electromagnet S^1, point 13, to a second loose electromagnet having an adjustable coil S^2, then to the spark gap 7 and to the second earth conductor E^2. The actual working circuit is formed through the spark gap 7, condensers 5 and 6, and through the primary coil 9; here the static electricity formed by oscillatory discharges is accumulated and converted into high frequency electromagnetic oscillations. Between the electromagnets S^1 and S^2 at the crossing point 13, four condenser batteries are introduced which are only indicated diagrammatically in the drawings each by one condenser. Two of these batteries (16 and 18) are made as plate condensers and prolonged by regulating induction coils or spirals 17 and 19 while the two others (21 and 23) are induction condensers. As may be seen from the drawings each of the four condenser batteries 16, 18, 21 and 23 is connected by only one pole to the aerial or to the collector conductor. The second poles 17, 19, 22 and 24 are open. In the case of plate condensers having no inductive resistance an induction coil is inserted. The object of such a spiral or coil is the displacement of phase by the induction current by 1/4 periods, whilst that of the charging current of the condenser poles which lie free in the air, works back to the collector aerial. The consequence of this is that in discharges in the collector aerial the back inductive action of the free poles allows a higher voltage to be maintained in the aerial collecting conductor than would otherwise be the case. It has also been found that such a back action has an extremely favorable effect on the wear of the contacts. Of course the inductive effect may be regulated at will within the limits of the size of the induction coil, the length of the coil in action being adjustable by means of wire connection without induction (see Figure 24, No. 20).

S^1 and S^2 may also be provided with such regulating devices in the case of S^2 (illustrated by 11). If excess voltage be formed it is conducted to earth through the wire 12 and spark gap 8 or through any other suitable apparatus, since this formation would be dangerous for the other apparatus.

The small circles on the collector balloon indicate places at which zinc amalgam or gold amalgam or other photoelectric acting metals in the form of small patches in extremely thin layers (0.01 to 0.05 mm in thickness) are applied to the entire balloon as well as in greater thickness to the conducting network. The capacity of the collector is thereby considerably strengthened at the surface. The greatest possible effect in collecting may be obtained by polonium amalgams and the like. On the surface of the collector balloon metal points or spikes are also fixed along the ribs, which spikes serve particularly for collecting the collector charge. Since it is well known that the resistance of the spikes is less the sharper the spike is, for this purpose it is therefore extremely important to employ as sharp spikes as possible. Experiments made as regards these have shown that the formation of the body of the spike or point also plays a large part, for example, spikes made of bars or rollers with smooth surface, have a many times greater point resistance as collector accumulator spikes than those with rough surfaces. Various kinds of spike bodies have been experimented with for the collector balloons hereinbefore mentions. The best results were given by spikes which were made in the following way. Fine points made of steel, copper, nickel, or copper and nickel alloys, were fastened together in bundles and then placed as anode with the points in a suitable electrolyte (preferably in hydrochloric acid or muriate of iron solutions) and so treated with weak current at 2 to 3 volts pressure. After 2 to 3 hours according to the thickness of the spikes or pins the points become extremely sharp and the bodies of the spikes have a rough surface. The bundle can then be removed and the acid washed off with water. The spikes are then placed as cathode in a batch consisting of solution of gold, platinum, iridium, palladium or wolfram salts or their compounds and coated a the cathode galvanically with a thin layer of precious metal, which must however be sufficiently firm to protect them from atmospheric oxidation.

Such spikes act at a 20-fold lower voltage almost as well as the best and finest points made by mechanical means. Still better results are obtained if polonium or radium salts are added to the galvanic bat when forming he protective layer or coating. Such pins have a low resistance at their points and even at one volt and still lower pressures have an excellent collector action.

In Figure 24 the three unconnected poles are not connected with one another in parallel. That is quite possible in practice without altering the principle of the free pole. It is also preferable to interconnect in parallel to a common collector network, a series of collecting aerials.

Figure 25 shows a diagram for such an installation. A^1, A^2, A^3, A^4 are four metal collector balloons with gold or platinum coated spikes which are electrolytically made in the presence of polonium emanations or radium salts, which spikes or needles are connected over four electromagnets S^1, S^2, S^3, S^4, through an annular conductor R. From this annular conductor four wires run over four further electromagnets Sa, Sb, Sc, Sd, to the connecting point 13. There the conductor is divided, one branch passing over 12 and the safety spark gap 8 to the earth at E^1, the other over inductive resistance J and working spark gap 7 to the earth at E^2. The working circuit, consisting of the condenser 5 and 6 and a resonance motor M, such as hereinbefore described, is connected in proximity round the sparking gap section 7.

Instead of directly connecting the condenser motor of course the primary circuit for high frequency oscillatory current may also be inserted.

The condenser batteries are connected by one pole to the annular conductor R and can be either inductionless (16 and 18) or made as induction condensers as shown by 21 and 23. The free poles of the inductionless condensers are indicated by 17 and 19, those of the induction condensers by 22 and 24. As may be seen from the drawings all these poles 17, 22, 19, 24 may be interconnected in parallel through a second annular conductor without any fear that thereby the principle of the free pole connection will be injured. In addition to the advantages already set forth the parallel connection also allows of an equalization of the working pressure in the entire collector network. Suitable constructed and calculated induction coils 25 and 26 may also be inserted in the annular conductor of the free poles, by means of which a circuit may be formed in the secondary coils 27 and 28 which allows current produced in this annular conductor by fluctuations of the charges of the like appearances to be measured or otherwise utilized.

According to what has been hereinbefore stated separate collector balloons may be connected at equidistant stations distributed over the entire country, either connected directly with one another metallically or by means of intermediate suitably connected condenser batteries through high voltage conductors insulated from earth. The static electricity is converted through a spark gap into dynamic energy of a high number of oscillations and may in such form be coupled as a source of energy b y means of a suitable method f connecting, various precautions being observed and with special regulations. The wires leading from the collector balloons have hitherto been connected through an annular conductor without this endless connection, which can be regarded as an endless induction coil, being able to exert any action on the whole conductor system.

It has now been found that if the network conductor connecting the aerial collector balloons with one another is not made as a simple annular conductor, but preferably short circuited in the form of coils over a condenser battery or spark gap or through thermionic tubes or valves or audions, then the total collecting network exhibits quite new properties. The collection of atmospheric electricity is thereby not only increased but an alternating field may be easily produced in the collector network. Further, the atmospheric electrical forces showing themselves in the higher regions may also be directly obtained by induction. In Figures 26 and 28 a form of construction is shown on the basis of which the further foundations of the method will be more particularly explained.



Fig. 26.

In Figure 26, 1, 2, 3, 4 are metal collector balloons, 5, 6, 7, 8 their metallic aerial conductors and I the actual collector network. This consists of five coils and is mounted on high voltage insulators in the air, in high voltage masts (or with a suitable construction of cable embedded in the earth). One coil has a diameter of 1 or 100 km or more. S and S^1 are two protective electromagnets, F the second safety section against excess voltage, E its earth conductor and E1 the earth conductor of the working section. When an absorption of static atmospheric electricity is effected through the four balloon collectors, the current in order to reach the earth connection E1 must flow spirally through the collector network over the electromagnet S, primary induction coil 9, conductor 14, anode A of the audion tube, incandescent cathode K, as the way over the electromagnet and safety spark gap F offers considerably greater resistance. Owing to the fact that the accumulated current flows in one direction, an electromagnetic alternating field is produced in the interior of the collector network coil, whereby the whole free electrons are directed more or less into the interior of the coil. An increased ionization of the atmosphere is thereby produced. In consequence of this the points mounted on the collector balloon show a considerably reduced resistance and therefore increased static charges between the points on the balloon and the surrounding atmosphere are produced. The result of this is a considerably increased collector effect.

A second effect which could not be obtained otherwise is obtained by the electromagnetic alternating field which running parallel to the earth surface, acts more or less with a diminishing or increasing effect on the earth magnetic field, whereby in the case of fluctuations in the current a return induction current of reversed sign is always produced in the collector coil by earth magnetism. Now if, however, a constantly pulsating continuous alternating field is produced as stated in the above collector network I, an alternating current of the same periodicity is produced also in the collecting network coil. As the same alternating field is further transmitted to the aerial balloon, the resistance to its points is thereby considerably reduced, whilst the collector action is considerably increased. A further advantage is that positive electrons which collect on the metal surfaces during the conversion into dynamic current produce a so-called drop of potential of the collector area. As an alternating field is present, the negative ions surrounding the collectors surfaces, when discharge of the collector surfaces takes place produce by the law of induction, an induction of reversed sign on the collector surface and so forth (that is to say again a positive charge). In addition to the advantages hereinbefore set forth, the construction of connecting conductors in coil form when of sufficiently large diameter, allows of a utilization of energy arising in higher regions also in the simplest way. As is well known electric discharges frequently take place at very great elevations which may be observed as St Elmo’s fire or northern lights. These energy quantities have no been available to be utilized up to now. By this invention all these kinds of energy, as they are of an electromagnetic nature and the direction of axis of the collector coils stands at right angles to the earth’s surface, can be more or less absorbed in the same way as a receiver in wireless telegraphy absorbs waves coming from a far distance. With a large diameter of the spiral it is possible to connect large surfaces and thereby to take up also large quantities of energy.

It is well known that large wireless stations in the summer months, and also in the tropics are very frequently unable to receive the signals in consequence of interruptions which are caused by atmospheric electricity, and this takes place with vertical coils of only 40 to 100 meters diameter. If on the contrary horizontal coils of 1 to 100 km diameter be employed very strong currents may be obtained through discharges which are constantly taking place in the atmosphere. Particularly in the tropics or still better in the polar regions where the northern lights are constantly present, large quantities of energy may probably be obtained in this way. A coil with several windings should act the best. In similar manner any alteration of the earth magnetism should act inductively on such a coil.

It is not at all unlikely that earthquakes and spots on the sun will also produce an induction in such collector coils of sufficient size. In similar manner this collector conductor will react on earth current more particularly when they are near the surface of the earth or even embedded in the earth. By combining the previous kind of current collectors so far as they are adapted for the improved system with the improved possibilities of obtaining current the quantities of free natural electricity which are to be obtained in the form of electricity are considerably increased.

In order to produce in the improved collector coil uniform current oscillations of an undamped nature so-called audion high vacuum or thermionic tubes of suitable connection are employed instead of the previously known spark gaps (Figure 26, Nos. 9-18). The main aerial current flows through electromagnet S (which in the case of a high number of alternations is not connected here but in the earth conductor E^1) and may be conveyed over the primary coils in the induction winding through wire 14 to the anode A of the high vacuum grid tube. Parallel with the induction resistance 9 a regulating capacity of suitable size, such as condenser 11 is inserted. In the lower part of the vacuum grid tube is arranged the incandescent filament or the cathode K which is fed through a battery B. From the battery B two branches run, one to the earth conductor E^1 and the other through battery B^1 and secondary coil 10 to the grid above *g* in the vacuum tube. By the method of connections shown in dotted lines, a desired voltage at the grid electrode *g* may also be produced through the wire 17 which is branched off from the main current conductor through switches 16 and some small condensers (*a, b, c, d*) connected in series, and conductor 18, without the battery B^1 being required.

The action of the entire system is somewhat as follows: --

On the connecting conductor of the aerial collector network being short circuited to earth, the condenser pole 11 is charged and slightly damped oscillations are formed in the short circuited existing oscillation circuit formed of the condenser 11 and self inductance 9. In consequence of the coupling through coil 10, fluctuations of voltage take place in the grid circuit 15 with the same frequency, which, fluctuations in turn influence the strength of the electrode current passing through the high vacuum amplifying tube and thus produce current fluctuations of the same frequency in the anode circuit. A permanent supply of energy to the oscillation circuits 9 and 10 consequently takes place, until a condition of balance is set up, in which the consumed oscillation energy is equal to that absorbed. Thereby constant undamped oscillations are now produced in the oscillation circuits 9-11.

For regular working of such oscillation producers high vacuum strengthening tubes are necessary and it is also necessary that the grid and anode voltages shall have a phase difference of 180° so that if the grid is negatively charged, then the anode is positively charged and vice versa. This necessary difference of phase may be obtained by most varied connections, for example, by placing the oscillation circuit in the grid circuit or by separating the oscillation circuit and inductive coupling from the anodes and the grid circuit and so forth.

A second important factor in this way of converting static atmospheric electricity into undamped oscillations is that care must be taken hat the grid and anode voltages have a certain relation to one another; the latter may be obtained by altering the coupling and a suitable selection of the self-induction in the grid circuit, or as shown by dotted lines 16, 17, 18 by means of a larger or smaller number of condensers of suitable size connected in series; in this case the battery B^1 may be omitted. With a suitable selection of the grid potential a glow discharge takes place between the grid *g* and the anode A, and accordingly at the grid there is a cathode drop and a dark space is formed. The size of this cathode drop is influenced by the ions which are emitted in the lower space in consequence of shock ionization of the incandescent cathodes K and pass through the grid in the upper space. On the other hand the number of ions passing through the grid is dependent on the voltage between the grid and the cathode. Thus is the grid voltage undergoes periodic fluctuations (as in the present case) the amount of the cathode drop at the grid fluctuates and consequently the internal resistance of the tube correspondingly fluctuates, so that when a back coupling of the feed circuit with the grid circuit takes place, the necessary means are afforded for producing undamped oscillations and of taking current, according to requirements from the collecting conductor.

The frequency of the undamped oscillations produced is with a suitably loose coupling equal to the self-frequency of the oscillation circuits 9 and 10. By a suitable selection of the self induction of the coil 9 and capacity 11 it is possible to extend from frequencies which produce electromagnetic oscillation of only a few meters wavelength down to the lowest practical alternating current frequency. For large installations a suitable number of frequency-producing tubes of the well-known high vacuum transmission tubes of 0.5 to 2 kw in size may be connected in parallel so that in this respect no difficulty exists.

The use of such tubes for producing undamped oscillations, and also the construction and method of inserting such transmission tubes in an accumulator or dynamo circuit is known and also that such oscillation producing tubes only work well at voltages of 1000 up to 4000 volts, so that on the contrary their use at lower voltages is considerably more difficult. By the use of high voltage static electricity this method of producing undamped oscillations as compared with that through spark gaps must be regarded as an ideal solution particularly for small installations of outputs of from 1 to 100 kw.

By the application of safety spark gaps, with interpolation of electromagnets, not only is short-circuiting avoided but also the taking up of current is regulated. Oscillation producers inserted in the above way form a constantly acting electromagnetic alternating field in the collector coil, whereby as already stated, a considerable accumulating effect takes place. The withdrawal wire or working wire is connected at 12 and 13, but current may be taken by means of a secondary coil which is firmly or movable mounted in any suitable way inside the large collector coil, i.e., in its electromagnetic alternating field, so long as the direction of its axis runs parallel with that of the main current collecting coil.

In producing undamped oscillations of a high frequency (50,000 per second or more) in the oscillation circuits 9 and 11, electromagnets S and S^1 must be inserted if the high frequency oscillations are not to penetrate the collector oil, between the oscillation producers and the collector coil. In all other cases they are connected shortly before the earthing (as in Figures 27 and 28).



Fig. 27.

In Figure 27 a second method of construction of the connecting conductor of the balloon aerials is illustrated in the form of a coil. The main difference consists in that in addition to the connecting conductor I another annular conductor II is inserted parallel to the former on the high voltage masts in the air (or embedded as a cable in the earth) but both in te form of a coil. The connecting wire of the balloon aerials is indicated as a primary conductor and also as a current producing network; the other is the consumption network and is not in unipolar connection with the current producing network.

In Figure 27 the current producing network I is shown with three balloon collectors 1, 2, 3 and aerial conductors 4, 5, 6; it is short-circuited through condenser 19 and inductance 9. The oscillation forming circuit consists in this diagram of spark gap f, inductance 10, and condenser 11; the earth wire E, is connected to earth over electromagnet S^1. F s the safety spark gap which is also connected to earth through a second electromagnet S at E. On connecting up the condenser circuit 11 this is charged over the spark gap f whereby an oscillatory discharge is formed. This discharging current acts through inductance 10 on the inductively coupled secondary 9, whereby in the producing network a modification of the potential of the condenser 19 is produced. The consequence of this is that oscillations arise in the coil shaped producer network. These oscillations induce a current in the secondary circuit II, which has a smaller number of windings and a less resistance, the voltage of which, according to the proportion of the number of windings and of the ohmic resistance, is considerably lower whilst the current strength is greater.

In order to convert the current thus obtained into current of an undamped character, and to tune its wavelengths, a sufficiently large regulatable capacity 20 in inserted between the ends 12 and 13 of the secondary conductor II. Here also current may be taken without an earthy conductor, but it is advisable to insert a safety spark gap E1 and to connect this with the earth over an electromagnet S2.

The producer network may be connected with the working network II over an inductionless condenser 21 or over an induction condenser 22, 23. In this case the secondary conductor is unipolarly connected with the energy conductor.



28.

In Figure 28 the connecting conductor between the separate accumulator balloons is carried out according to the autotransformer principle. The collecting coil connects four aerial balloons 1, 2, 3, 4, the windings of which are not made side by side but one above the other. In Figure 28 the collector coil I is shown with a thin line, the metallically connected prolongation coils II with a thick line. Between the ends I^1 and II^1 of the energy network I a regulating capacity 19 is inserted. The wire I^1 is connected with the output wire and with the spark gap F.

As transformer of the atmospheric electricity an arrangement is employed which consists in using rotary pairs of condensers in which the one stator surface B is connected with the main current, whilst the other A is connected with the earth pole. Between these pairs of short-circuited condensers are caused to rotate from which the converted current can be taken by means of two collector rings and brushes, in the form of an alternating current, the frequency of which is dependent on the number of balloons and the revolutions of the rotor. As the alternating current formed in the rotor can act, in this improved method of connection described in this invention, through coils 1 on the inductance 9, an increase or diminution of the feed current in I can be obtained according to the direction of the current by back induction. Current oscillations of uniform rhythm thereby result in the coil shaped windings of the produce network.

As the ends of this conductor are short-circuited through the regulatable condenser 19 these rhythms produce short-circuited undamped oscillations in the energy conductor, the periodicity and wave lengths of which oscillations can be adjusted according to desire by altering the capacity 19 to a given wavelength and therewith also to a given frequency. These currents may also be employed in this form directly as working current through the conductors II^1 and III. By inserting the condenser 20 a connection between these conductors may also be made, whereby harmonic oscillations of desired wavelengths are formed. By this means quite new effects as regards current distribution are obtained. The withdrawal of current can even take place without direct wire connection if, at a suitable point in the interior of the producing network (quite immaterially whether this has a diameter of 1 or 100 km) a coil tuned to these wavelengths and of the desired capacity is firmly or movably mounted in the aerial conductor in such a way that is axial direction is in parallel with that of the collector coil. In this case a current is induced in the producing network, the size of which is dependent on the total capacity and resistance and also on the periodicity employed. A possibility is thereby afforded in future, of taking energy from the producer network by wireless means. As thereby in addition to atmospheric electricity also magnetic earth currents and energy from the higher atmosphere (at leas partially may be simultaneously obtained, this last system for collecting the atmospheric energy is of particular importance for the future.

Of course everywhere instead of spark gaps grid vacuum tubes may be employed as producers for undamped oscillations. The separate coils of the producer network with large diameters may be connected with one another through separate conductors all in parallel or all in series or in groups in series. By regulating the number of oscillations and also the extent of the voltage more or less large collector coils of this kind may be employed. The coils may also be divided spirally over the entire section. The coils may be carried out in angular form or also in triangular, quadrangular, hexagonal or octagonal form.

Of course wires may be carried from a suitable place to the center or also laterally which serve the current waves as guides. This is necessary when the currents have to be conducted over mountains and valley and so forth. In all these cases the current must be converted into a current of suitable periodicity.

As already hereinbefore mentioned separate collecting balloons may be directly metallically interconnected at equidistant stations distributed over the entire country or may be connected by interpolation of suitable condenser batteries by means of high voltage conductors. The static electricity is converted through a spark gap into dynamic energy of a high number of oscillations, and could then in such forms, wit a suitable arrangement of the connections, observing various measures of protection, be employed as source of energy after separate or special regulation.

According to this invention in order to increase the collecting effect of the balloon in the aerial collector conductor or in the earth wire, radiating collectors are employed. These consist either of incandescent metal or oxide electrodes in the form of vacuum grid tubes, or electric arcs (mercury and the like electrodes), Nernst lamps, or finally flames of various kinds may be simply connected with the respective conductor.

It is well known that energy can be drawn of from a cathode consisting of an incandescent body opposite an anode charged with positive electricity (vacuum grid tube). Hitherto however, a cathode was always first directly placed opposite an anode, and secondly the system always consisted of a closed circuit.

Now if we dispense with the ordinary ideas in forming light or flame arcs in which a cathode must always stand directly opposite an anode, charged to a high potential or another body freely floating in the air, or regard the incandescent cathode only as a source of unipolar discharge (which represent group and point discharges in electrostatic machines similar to unipolar discharges), it may be ascertained that incandescent cathodes and less perfectly all incandescent radiators, flames and the like admit of relatively large current densities and allow large quantities of electric energy to radiate into the open space in the form of electron streams as transmitters.

The object of this invention is as described below, if such incandescent oxide electrodes or other incandescent radiators or flames are not freely suspended in space but connected metallically with the earth so that they can be charged with negative terrestrial electricity, these radiators possess the property of absorbing the free positive electrical charges contained in the air space surrounding them (that is to say of collecting them and conducting them to earth). They can therefore serve as collectors and have, in comparison to the action of the spikes, or points, a very large radius of action R; the effective capacity of these collectors is much greater than the geometrical capacity (R_{o-}) calculated in an electrostatic sense.

Now as our earth is surrounded as is well known with an electrostatic field and the difference of potential

$$\frac{\delta V}{\delta h}$$

of the earth field according to the latest investigations, is in summer about 60 to 100 volts and in winter 300 to 500 volts per meter of difference in height (δh), a simple calculation gives the result that when such a radiation collector or flame collector is arranged for example on the ground, and a second one is mounted vertically over it at a distance of 2000 meters and both are connected by a conducting cable, there is a difference in potential in summer of about 2,000,000 volts and in winter even of 6,000,000 volts and more.

According to Stefan Boltzmann's law of radiation, the quantity of energy which an incandescent surface (temperature T) of 1 sq cm radiates in a unit of time into the open air (temperature T_o) is expressed by the following formula:

$S = \delta (T^4 - T^4_o)$ watt./sq cm.

And the universal radiation constant δ is according to the latest researches of Ferry (*Annales de Chimie et de Physique*, 17: 267 [1909]) equal to 6.30 x 10^{-12} watt/sq cm.

Now if an in incandescent surface of 1 sq cm shows, as compared with the surrounding space a periodic fall of potential δV it radiates (independent of the current direction, that is to say of the sign) in accordance with the above formula, for example at a temperature of 3725° C an energy of 1.6 kw/sq cm/second. As for the radiation the same value can be calculated for the collection of energy, but reversed. Now, as carbon electrodes at the temperature of the electric arc support on the current basis a current density up to from 60 to 65 amperes per sq cm no difficulties will result in this direction in employing radiating collectors as accumulators.

If the earth be regarded as a cosmically insulated condenser in the sense of geometrical electrostatics *x* there results from the geometric (compare Edwald Rasch: *Das Elektrische Bogenlicht* [The Electric Arc Light], page 169) capacity of the earth according to Chwolson:

For negative charging 1.3 x 10^6 Coulomb

For negative potential V = 10 x 10^8 volts.

From this there results however, EJT = 24.7 x 10^{24} watt/sec. Now if it is desired to make a theoretic short circuit through an earthed flame collector this would represent an electric total work of about 79,500 x 10^{10} kilowatt years. As the earth must be regarded as a rotating mechanism which thermodynamically, electromagnetically and also kinematically coupled with the sun and star system by cosmic radiations and gravitation a diminution of the electric energy of the earth field is not to be feared. The energies which the incandescent collectors would withdraw from the earth field can only case by the withdrawal of motor work a lowering of the earth temperature (temperature $T_E = 300$) and reduce this to that of the world space (T = O) by using the entire energy. This is however not the case as the earth does not represent a cosmically entirely insulated system. On the contrary there is conveyed to the same according to the recent value corrected by Perry for the solar constants through the radiation from the sun an energy of 18,500 x 10^{10} kw. Accordingly, any lowering of the earth temperature (T_E) without a simultaneous lowering of the sun's temperature (T_s) would contradict Stefan Boltzmann's law of radiation.

$S = \delta (s^4 - T^4)$.

From this it must be concluded that if the earth temperature (T_E) sinks the total radiation S absorbed by the earth increases, and further also that the secular speed of cooling of the earth is directly dependent on that of the sun and the other radiators cosmically coupled with the sun and is connected most closely with these.

The incandescent radiation collectors may, according to this invention, be employed for collecting atmospheric electricity if they (1) are charged with the negative earth electricity (that is to say when they are directly connected by means of a metallic conductor with the earth) and (2) if large capacities (metal surfaces) charged with electricity are mounted opposite them as positive poles in the air. This is regarded as the main feature of the present invention as without these inventive ideas it would not be possible to collect with an incandescent collector, sufficiently large quantities of the electrical charges contained in the atmosphere as the technology requires; the radius of action of the flame collectors would also be too small, especially if it be considered that the very small surface density (energy density) (δ about = 2 x 7 . 10^9 St. E. per sq cm) does not allow of large quantities of charge being absorbed from the atmosphere.

x) Calculated according to Poisson's calculation:

$\Delta V = -4\pi\delta$; as here the alteration of the potential or potential gradients only takes place in the direction o the normal, this calculation assumes the simple form

$$\delta = \frac{1}{4\pi} \times \frac{\delta^2 V}{\delta n^2}$$

It has indeed already been proposed to employ flame collectors for collecting atmospheric electricity and it is known that their collecting effect is substantially greater opposite the points. It is however, not known that the quantities of current which could hitherto be obtained are too small for technical purposes. According to my experiments the reason for this is to be found in the too small capacities of the collector conductor poles. If such flame or radiating collectors have no or only small positive surfaces, their radius of action for large technical purposes is too small. If the incandescent collectors be constantly kept in movement in the air they may collect more according to the speed of the movement, but this again is not capable of being carried out in practice.

By this invention the collector effect is considerably increased by a body charged with a positive potential and of the best possible capacity being also held floating (without direct earth connection) opposite such an incandescent collector which is held floating in the air at a desired height. If for example, a collecting balloon of sheet metal or of metalized balloon fabric be caused to mount to 300 up to 3000 meters in the air and as positive pole it is brought opposite such a radiating collector connected by a conductor to the earth, quite different results are obtained.

The metallic balloon shell (with a large surface) is charged to a high potential by the atmospheric electricity. This potential is greater the higher the collecting balloon is above the incandescent collector. The positive electricity acts concentratedly on the anode floating in the air as it is attracted through the radiation shock ionization, proceeding from the incandescent cathode. The consequence of this is that the radius of action of the incandescent cathode collector is considerably increased and thereby also the collection effect of the collecting balloon surface. Further the large capacity of the anode floating in the air plays therefore an important part because it allows of the taking o large charges, and thereby a more uniform current is obtained even when there is a large consumption: this cannot be the case with small surfaces.

In the present case the metallic collecting balloon is a positive anode floating in the air and the end of the earth conductor of this balloon serves as positive pole surface opposite the surface of the radiating incandescent cathode, which in turn is charged with negative earth electricity being conductively connected to earth.

The process may be carried out by two such contacts (negative incandescent cathode and anode end of a capacity floating in the air) a condenser and an inductive resistance being switched on in parallel, whereby simultaneously undamped oscillations may be formed.

In very large installations it is advisable to connect two such radiating collectors in series. Thus an arc light incandescent cathode may be placed below on the open ground and an incandescent cathode which is heated by special electromagnetic currents be located high in the air. Of course for this the special vacuum Liebig tubes wit or without grids may also be employed. An ordinary arc lamp with oxide electrodes may be introduced on the ground and the positive pole is not directly connected with the collecting balloon, but through the upper incandescent cathode or over a condenser. The method of connecting the incandescent cathode floating in the air may be seen in Figures 29-33.

B is the air balloon, K a Cardan ring (connection with the hawser), C the balloon, L a good connecting cable, P a positive pole, N negative incandescent cathode, and E earth conductor.



Fig. 29.



Fig. 30.

Figure 29 represents the simplest form of construction. If electric oscillations are produced below on the ground by means of a carbon arc lamp or in other suitable way a considerably greater electric resistance is opposed to that in the direct way by inserting an electrical inductive resistance 9. Consequently between P and N, a voltage is formed, and as, over N and P only an inductionless ohmic resistance is present, a spark will spring over so long as the separate induction co-efficients and the like are correctly calculated. The consequence of this is that the oxide electrode (carbon or the like) is rendered incandescent and then shows as incandescent cathode an increased collecting effect. The positive poles must be substantially larger than the negative in order that they may not also become incandescent. As they are further connected with the large balloon area which has a large capacity and is charged at high voltage, an incandescent body which is held floating in the air and a positive pole which can collect large capacities is thereby obtained in the simplest way. The incandescent cathode is first caused to become incandescent by means of separate energy produced on the earth, and then maintained by the energy collected from the atmosphere.

Figure 30 only shows the difference that instead of a round balloon a cigar-shaped one (of metal or metalized fabric) may be employed and also a condenser 5 is inserted between the incandescent cathode and the earth conductor so that a short circuited oscillation circuit over P.N. 5 and 9 is obtained. This has the advantage that quite small quantities of electricity cause the cathode to become incandescent and much larger cathode bodies may be rendered incandescent.



In this form of construction both the incandescent cathode and also the positive electrode may be enclosed in a vacuum chamber as may be seen in Figure 32. A cable L is carried well insulated through the cover of a vessel and ends in a condenser disc 5. The cover is arched in order to keep off the rain. The vessel is entirely or partially made of magnetic metal and well-insulated inside and outside. Opposite the disc 5 another disc 6 and on this again a positive pile of the vacuum tube g with the incandescent cathode (oxide electrode) N is arranged. The negative electrode is on the one hand connected with the earth conductor E, and on the other hand with the inductive resistance 9 which is also connected with the cable L with the positive pole and wound round the vessel in coils. The action is exactly the same as that in Figure 29 only instead of an open incandescent cathode one enclosed in vacuo is employed. As in such collectors only small bodies can be brought to incandescence in large installations a plurality of such vacuum tubes must be inserted in proximity to one another. According to the previous constructions Figures 31 and 33 are quite self evident without further explanations.



Figures 34-37 represent further diagrams of connections over radiating and flame collectors, and in fact, how they are to be arranged on the ground.

Figure 34 shows an arc light collector with oxide electrodes for direct current and its connection; Figure 35 a similar one for alternating current, Figure 36 an incandescent collector with a Nernst lamp and Figure 37 a similar one with a gas flame.

The positive pole 1 of the radiating collectors is always directly connected to the aerial collecting conductor A. In Figure 34 this is further connected over the condenser battery 5 with a second positive electrode 3. The direct current dynamo *b* produces current which flows over between the electrodes 3 and 2 as an arc light. On the formation of an arc the negative incandescent electrode 2 absorbs electricity from the positive poles standing opposite it and highly charged with atmospheric electricity and conveys the same to the working circuit. The spark gap 7, inductive resistance 9 and induction coil 10 are like the ones previously described. The protective electromagnet S guards the installation against earth circuiting, the safety spark gap 8 from excess voltage or overcharging.

In Figure 35 the connection is so far altered that the alternating current dynamo feeds the exciting coil 11 of the induction condenser. 12 is its negative and 13 its positive pole; if the coil 3 on the magnet core of the dynamo is correctly calculated and the periodicity of the alternating current is sufficiently high an arc light can be formed between the two poles 1 and 2. As the cathode 2 is connected with the negatively charged earth, and therefore always acts as a negative pole, a form of rectification of the alternating current produced by the dynamo 3 is obtained, the second half of the period is always suppressed. The working circuit may be carried out in the same way as in Figure 34; the working gap 7 may however be dispensed with, and instead thereof between the points m and n a condenser 5 and an induction resistance 9 may be inserted from which the current is taken inductively.

Figure 36 represents a form of construction similar to Figure 34 only that here instead of an arc lamp a Nernst incandescent body is employed. The Nernst lamp is fed through the battery 3. The working section is connected with the negative pole, the safety spark gap with the + poles. The working spark gap 7 may also be dispensed with and the current for it taken at 12 over the oscillation circuit 5, 11 (shown in dotted lines).

Flame collectors (Figure 37) may also be employed according to this invention. The wire network 1 is connected with the aerial collector conductor A and the burner with the earth. At the upper end of the latter, long points are provided which project into the flame. The positive electrode is connected with the negative over a condenser 5 and the induction coil 9 with the earth.

The novelty in this invention is firstly, the use of incandescent cathodes opposite positive poles which are connected with large metallic capacities as automatic collecting surfaces, (2) the connection of the incandescent cathodes with the earth whereby, in addition to the electricity conveyed to them from the battery or machine which causes the incandescing, also the negative charge of the earth potential is conveyed, and (3) the connection of the positive and negative poles of the radiating collectors over a condenser circuit alone or with the introduction of a suitable inductive resistance, whereby simultaneously an oscillatory oscillation circuit may be obtained. The collecting effect is by these methods quite considerably increased.

I declare that what I claim is: --- [Claims not included here]

British Patent # 157,262
(10 July 1922)

Improvements in Electric Motors

Hermann Plauson // Otto Traun’s Forchungs-Laboratorium GmbH

This invention relates to that type of motor in which rotation is produced by means of the attraction and repulsion of surfaces carrying charges of electricity.

According to this invention a stator and rotor are formed of condensor surfaces and charges of electricity thereon imposed in the form of alternating currents of high frequency.

The invention is more particularly described with reference to the accompanying drawing in which: ---

Figure 1 shows a simple form of motor and feed.


Fig. 1
1+
+
+
4a
14
3
3x
12
5
7
8
9
10
16
17
11
6
4x
4
15
3a+
2
13

Figure 2 is a modification of Figure 1.


Fig. 2.
a
11
14
5
9
8
3
8
9
10
4
b
1
13
6
10
7
d
12
13

Figure 3 shows one form of a spiral condenser surface.

Figure 4 shows a wire wound condenser surface.

Figure 5 is a diagram of one type of rotor,


Fig. 3


Fig. 4


Fig. 5.
1
4
5
7
6
9
10
3
8
2
14
15

The inner plates of the condenser 5 and 6 are charged from a spark gap 7, 8 connected to a source of energy of sufficiently high pressure (alternating or direct current), until the potential has risen so far that a spark springs over.

The spark gap 7, 8 forms with the condenser 5 and self-inductance 9 and condenser 6 a closed oscillatory circuit and alternating currents of high frequency will be produced in this circuit. The high frequency current produced in the primary circuit 9 excite by induction in the secondary circuit 10 currents of the same periodicity.

The improved type of motor is fed by the discharges produced by the induction in the secondary circuit.

Hitherto only Tesla's motor system (shown diagrammatically in Figure 1, 16 and 17) was known for this purpose. The above-mentioned diagram is only shown for illustrating the fundamental principle. It has however no practical interest for carrying out large machines by reason of the impossibility of the regulation and the low efficiency.

Now according to this process, all these defects are overcome by the construction of a machine which is applicable for high frequency currents and of a more or less undamped nature. The difference between the principle of construction of these motors as compared with those hitherto customary consists in that the motor is not based on the principle of magnetic induction only (as have been all motors hitherto and also Tesla's motors).

It has been fund that the machine constructed according to Figure 1 cannot only be fed directly with static electricity but if it is connected to a source of high frequency current it will operate.

The applicants call this new type of motors 'condenser motors' to differentiate them from hitherto existing types.

The simplest form of construction of such condenser motors is shown in Figure 1, and this motor may be fed with high frequency alternating currents.

At a given moment positive electricity is charged by means of the lead 14 to the stator surface 1 and to the brush 3x (Figure 1). The brush 3x is connected with the rotor condenser surface 3, so that both the stator surface 1 and also the rotor surface 3 is charged with positive electricity. The stator surface 1 and the rotor surface 3 being both charged with positive electricity and the second rotor surfaces 4 and 4a by brushes 4x with negative electricity, such motors can then be started by providing intermediate stator surfaces 11, 12, the earth connection 13 of one of which is broken by a switch (not shown) according to the direction of rotation desires, or alternatively the motor may be started by a separate source of alternating current in a manner similar to the starting of synchronous motors of known construction. After a half revolution of the rotor the brush 3x comes in contact with the second collector surface 4 so that now this surface is connected by the brush 3x with the stator surface 1 and the brush 4x with the collector surface 3. Consequently with a reverse direction of current through the second half of the oscillation period all the hereinbefore mentioned effects take place in the reverse direction which, however, produces no alteration in the direction of rotation because the dead points between two directions of oscillation are overcome by inertia.

Although this motor is easy to start it can only be employed for small experimental and measuring purposes because the stator and rotor surfaces are made of solid metal and are heated by Foucalt (eddy) currents. In spite of its simplicity and its unsuitability for use in practice it must however be regarded as a basic type for technical calculations.

The condenser motor shown in Figure 2 differs from Figure 1 by the rotor surfaces consisting of six condenser surfaces connected one behind the other in series and they are connected with three collector surfaces, so that at any one moment only two adjacent collector surfaces come under the two brushes (3 and 4). In its other actions it corresponds to Figure 1. The leads 14 and 15 may be connected either to the ends of the secondary coil 10 or directly with the source of energy. The outer thicker line indicates the stator surfaces 1 and 2 (that is to say the unmoving part of the motor), 11 and 12 shown by thick dotted lines means earthed additional poles of the stator, 8, 9, and 10 are the outer parts of the rotor condenser surfaces which in turn are connected with the collector surfaces 8, 9, and 10. 5, 6, and 7 are the inner parts of the condenser surfaces of the rotor and 3 and 4 are brushes.

Hitherto stator and rotor surfaces of compact metal have been spoken of. These however become highly heated with eddy currents and hardly yield 10-15% of useful effect. In examining into such small useful effects it was found that certain forms of metal sections in the stator and condenser surfaces highly increase these. It was then further found that if slots or notches be cut in the metal surfaces of the stator and rotor in the form of a spiral, not only was a higher useful effect possible, but also an easier starting and even a regulation could be obtained.

Experiments have shown that by such a form of construction it is possible to build a very useful motor for high frequency alternating currents more particularly those of an undamped nature.

If for example the system of construction of a stator shown in Figure 1, but four polar, be taken and the system of rotor construction shown diagrammatically in Figure 5, but with the form of construction of the condensers of the stator as well as of the rotor according to Figure 3, a condenser motor is obtained which works well in either direction for high frequency alternating current. It was also observed that the motors in such forms of construction were found to be more sensitive to resonance effects. Such a motor then works the best if stator and rotor surfaces have equal capacity and self-inductance so that the windings both in the stator and also in the rotor are in resonance.

A motor constructed according to the foregoing kind is already fully technically applicable. But even these motors have a series of faults, more particularly in their building construction. For example, the attachment of the spiral condenser surfaces both of the stator and of the rotor sown in Figure 3 are in practice difficult to carry out. Therefore in practice the condenser and stator surfaces are simply wound of wire or bands in the form shown in Figure 4. Such stator and rotor surfaces may, without further difficulty, be regarded as electromagnetic poles, although they are not made of iron as is the case in electromagnets. Such machines may be spoken of directly as motors for high frequency alternating currents in which the separate pole surfaces consists of wound induction condenser surfaces of which one is sound on the stator and the other on the rotor.

If the coil as shown in Figure 4 be made of well insulated wires the coil can be embedded in insulating material either for the stator or motor surfaces as has already been done in the case of ordinary single and multiphase motors. At the same time the possibility is afforded by increasing the number of turns to produce a greater or smaller alteration of the self induction co-efficients.

In Figure 5 is shown a modified construction of a rotor for a four pole motor consisting of four condenser surfaces 1, 2, 3, 4, of which 1 and 2 are connected though an iductance 9 coupled with the coil 10. Four inner surfaces 5, 6, 7, 8 are provided of which 5 and 6 are directly connected also 7 and 8 similarly connected.

The pairs of like poles are connected by wires 14 and 15 to the source of energy. By a suitable selection of the values of the reactance and capacity in these circuits resonance circuits may be formed.

Having now particularly described and ascertain the nature of our said invention and in what manner the same is to be performed, we declare that what we claim is: --- [Claims not included here]

British Patent # 157,263

Process & Apparatus for Converting Static Atmospheric Electrical Energy into Dynamic Electrical Energy of any Suitable High Periodicity

Hermann Plauson // H.O. Traun’s Forschungs-Laboratorium GmbH

Static aerial electricity in the form of direct current can be converted by using spark gaps and with the assistance of oscillatory circuits into dynamic electrical wave energy of a high number of alternations of a more or less undamped nature and in such form --- either direct or by means of a special kind of resonance or 'condenser motors' --- ready to be utilized for technical purposes as mechanical energy.

For small installations this system may be very well employed; about 100 horsepower may be stated as practical limit. In constructions of larger aggregate difficulties as regards the spark gaps however increase considerably. Further it is desirable to convert the accumulated currents of from 100 to 1000 periods which may then be used for the ordinary types of alternating current machines instead of into electromagnetic waves of a high number of alternations.

In experimenting with condenser motors the construction of which forms the object of British Patent # 157,262 it was observed that the rotor, if one pole of the stator surface be connected with the aerials collecting aerial electricity and the other pole with the earth, not only could act as a motor, but if vice versa the rotor connection with the stator be interrupted and the rotor caused to rotate by means of another motor, that when the brushes supply an alternating current the periodicity of which is dependent on the number of poles and the revolutions of the rotor. Such an apparatus may therefore be regarded as a transformer of static into dynamic electrical energy.

The invention is more particularly described with reference to the accompanying diagrams in which: ---



In Figure 1A is a strong accumulator battery, 1 and 2 are the outer poles of the transformer, consisting of simple metallic plates or are as shown in Figures 8-11, made of wire coils without an electromagnet being present. Between these poles an armature is revolubly mounted on a shaft, which armature also consists of two similar cylindrically curved plates 3 and 4. These are metallically connected with two collector rings 5 and 6 on which two brushes 7 and 8 freely run which again are short-circuited with one another over a primary coil 9. 10 is the secondary coil with the free ends 11 and 12. If through the accumulator battery the stator plate 1 is charged with positive electricity, it induces a charge of reverse sign on the rotor surface 3 which is connected by the brushes 7 and 8 over the primary coil 9 with the second rotor surface 4. This latter is therefore charged with positive electricity, which in turn induces negative electricity on the stator surface 2/ Up to this moment everything takes place in the same way as if two condensers were connected one behind the other in the current circuit A. If however, by means of mechanical power, this rotor be caused to rotate, the surface conditions are altered. After a quarter revolution the rotor plates are between the stator plates and therefore no condenser surface faces another. By this means however, the capacity of the entire system is reduced to a minimum and a change of current will also result in the main 9. Now if the rotor be turned further through 90 degrees by mechanical energy the rotor plate 3 comes opposite the stator plate 2 and the rotor plate 4 opposite the stator plate 1, so that then the rotor pates are in a field of reverse sign. A fresh charge of current in the reverse direction now runs through the primary coil 9. After a further half revolution the same action is repeated so that after a full revolution the initial condition is again produced. The result of such a revolution is an alternating current the periodicity of which is equal to the number of revolution. In practice of course not two poles but as many poles as possible would be employed because thereby the number of alternations would e considerably increased. The primary alternating current thus obtained induces in the secondary circuit an alternating current the potential of which is dependent on the winding of the coil. Figure 7 shows a multipolar machine.

If the stator surface 1, instead of being connected with the battery be connected with a collecting aerial network and the other stator surface 2 be directly earthed, but the rotor wich is otherwise constructed as hereinbefore, be rotated by a separate motor a much stronger alternating current results which is to be ascribed to the circumstance that a much higher potential can be charged on the pole surfaces of the stator by reason of the higher pressure of the static electricity than where accumulators are employed. By this means the transformer has of course much larger quantities of energy supplied to it.

Figure 2 shows a mode of connections. The stator surface 1 is connected with the aerial antennae which is connected through the safety spark gap F to earth at E1. The stator surface 2 is directly earthed at E2. The inner revoluble rotor surfaces 3 and 4 are interconnected by means of an induction coil which is constructed directly in the motor. The current is taken as in Figure 1 up to collector rings by means of brushes, which are not shown for the sake of clearness, and further conveyed through the conductors 11 and 12. Between these a condenser 5 may be inserted. There is thereby formed a short oscillatory oscillation circuit free from spark gaps, which circuit consists of the induction coil 9 and condenser 5 and is fed by the periodic charging current impulse. By this means the possibility is afforded of obtaining a kind of current which is characterized by longer periods and is undamped and oscillatory. Of course a simple alternating current may be obtained by cutting out the condenser.

Instead of the induction coil the condenser may also b constructed in the rotor. His can be carried out in such a way that its ends serve directly as collector rings for taking current through the brushes. In Figure 3 such a motor is sketched in perspective, 3 and 4 are the rotor surfaces, 5 and 6 are the condenser surfaces constructed to form part of the rotor consisting of two co-axial cylinders fitting one in the other in such a way that free room is left for the brushes 7 on one end of the condenser cylinder 6.

The condenser may be made in the form of a cylindrically wound spiral forming the capacity and reactance as shown in Figure 4. A further type of transformer is shown in Figure 5. The difference consists in the stator and rotor surfaces not only each assuming a quarter of the circuit but almost the half. By this means the space and the effective condenser surface is better utilized. Charge is produced only when the rotor surfaces face the full scope of the stator surfaces.

In addition a condition is obtained in which the stator surfaces are inductively connected by the rotor surfaces. The consequence of this is that an alternating current simultaneously results which is produced without sparking otherwise the connection is as before.

Figure 6 shows the alternation of the rotor surfaces; the rotor here consists of two cylindrical condenser plates arranged concentrically, each divided into two halves and connected so that half the inner cylinder is connected to half the outer. Such a machine shows the more complete transformer action.

Fig.7.



Figure 7 shows a four polar transformer. It consists of a metal casing, the lower half of which is fastened with the foundation plates 17 to the support or foundation. The upper half, the cover, is connected by bolts 15 and 16 firmly with the under part. This upper sleeve or casing is insulated from the under part. Two rings 1 and 2 are cylindrically constructed in the casing. The ring 1 is metallically connected with the collector aerial and the ring 2 with the earth. On both rings an equal number of stator surfaces are mounted side by side but well insulated from one another and thus form an electrostatic field similar to the electromagnetic in many alternating current machines. The rotor consists in similar manner of two rings 5 and 6 on which an equal number of rotor surfaces are fixed so that each stator surface faces a rotor surface. By the brushes 7 and 8 the alternating current formed is removed from the collector. The charge is conveyed by the conductor 14 to and by 13 away. If this rotor be then rotated by means of a motor the positive and negative fields precisely as in the case of magnetizing will alter and thereby an alternating current is formed in the rotor, the periods of which are dependent on the number of the poles and the revolutions per second.

At the commencement it was thought that this apparatus could only be regarded as alternating current converters, but it was soon found that much more energy was necessary to rotate the rotor than might be necessary to overcome the friction. It was then found that the considerable expenditure of energy for rotating the rotor was caused by a conductor being moved through strongly electrostatic fields since the electrostatic lines of force must be cut at right angles and that further in the conductors a stronger current arose than was otherwise to be expected. This apparatus must therefore not only be regarded as a transformer, but also as an energy producer, with the difference that the excitation here is obtained instead of by means of electromagnets, by static fields of high pressure. The entire system may, to some extent, be compared with a dynamo in which the excitation takes place by means of a fixed constant magnet. It was further ascertained that this way of using the atmospheric electricity produced a sort of suction on the collector network, and that thus suitable greater quantities of current could be obtained.

The effects which in this apparatus became evident are extremely interesting and open a prospect of being able to obtain here a great deal more. Merely that these transformer made it possible to transform suitable quantities of atmospheric electricity into alternating current of high or lower frequency (without the use of spark gaps) shows already the extreme utility of these apparatus. Should in future, the construction of larger aggregates be necessary the transformer installation may be constructed in such a way that motors which are fed by a current obtained from an installation with spark gaps produce a certain quantity of energy which may then be employed for producing current according to the last described system.

The results of the examinations made for this may be construed as follows.

(1) If solid electrodes (condenser surfaces, rotor and stator surfaces) are employed they become hot. This effect may be considerably reduced by cutting the electrodes in ribbed form Figure 8, but not entirely removed. This form allows the surface of the condenser plate to be enlarged or increased; the electrodes may be fastened in a simple manner on the under frame by perforation 1, 2, 3, 4, 5.

Fig.8



Fig. 9.



(2) If nicks or notches in spiral form as shown in Figure 9 seen from the side end in Figure 10 in section are employed, not only is the transformer effect greater but the poles yields also more current, but require greater quantities of energy for their movement than a simple commutator action would require.

Fig. 10



Fig. 11



(3) The greatest effect is obtained if the rotor and stator surfaces are wound in flat spiral form of suitably thick wire, and in such a way that the inductive effect combining with the capacity is calculated in suitable proportion and this result is adapted to a suitable periodicity. In practice this is preferably done by the wire bent in spiral form being inserted in a separate vulcanite or hard rubber mass (see Figure 11) so that a smooth pole surface is formed similar to that in phase motors.

Fig.12



Fig. 13.



Regular undamped oscillations of a high frequency may however be produced if the converter be carried out in the manner shown in Figure 13. The aerial wire L is metallically connected with the ring 20. To this two pole surfaces 1 and 2 are connected. The inductive earth pole is also connected with a second ring 10 from which again two, poles 1a and 2a are branched off. Of course in similar manner any suitable number of poles may be branched of. In similar manner there are in the rotor two poles fastened to one another (3 and 4 and 3a and 4a) connected with separate collector rings. From these two rings the current is collected by means of two brushes. The induced alternating current is however directly metallically connected with an inductive earth stator conductor over an induction coil 9. Further a combined inductance and capacity 5 is inserted between the two wires 11 and 12 in parallel with the converter. By this means a sparkless oscillatory circuit is obtained which can act on the exciting current in the stator. This produces however, a periodic alteration of the charging quantities according to the oscillation curves of the rotor currents in consequence of which the stator charge also commences with resonance oscillations and if the stator and rotor surfaces are calculated to one another in such a way that they are adapted to form oscillations of waves of similar length the entire converter is caused to oscillate and furnishes undamped oscillations of a high number of alternations, but of periodically changed amplitude, the form of which is dependent on the amplitude of the main alternating current and is caused by the number of the poles and revolutions per second. Thus an alternating current of, for example, 100 periods is formed, the separate periods of which are formed by undamped oscillations of a higher number of alternations. In Figures 14-16 four other diagrams of converters are illustrated, the object of which is not to produce usual alternating current, but oscillations of high frequency.

Fig.14



The main difference of these systems from those previously described is that from the connection of the collecting aerials is made between the stator pole 1 (Figure 14) and one pole 16 of the condenser 17 and the earth connection between a second stator pole 2 and the pole 18 of the condenser 19. The other poles of these condensers 17 and 19 are short circuited through a ring over two inductive primary coils 9 and 9a with one another. The secondary coils form the rotor conductors 10 and 10a. The rotor itself is constructed in the manner shown in Figure 6 of two short-circuited plate condensers which may be wound as shown in Figure 11. In similar manner of course the stator surfaces may also be formed. The collector rings of the rotor with the two brushes for collecting current are here not shown in order to simplify the drawings. By the connection of the two condensers in the exiting circuit of the converter and also by the action of the alternating current produced in the rotor on the stator circuit, with a correct calculation of the capacity and the self-induction co-efficients a maximum action may be obtained. The kind of current produced will be similar to that described for Figure 12.

Fig.15



The novelty of the converter illustrated in Figure 15 consists mainly in that the current resulting in the rotor is not directly employed, but only serves a exciter of the primary coils 9a and 9b. The working current is produced in the secondary coils 10 and 10a and further conducted through the conductors 11 and 12. The stator current may be brought by the regulatable inductive resistance 9 to the same resonance as the rotor current.

Fig. 16



In Figure 16 a very similar system is shown to Figure 14. The condenser 5 is however connected in parallel with the converter; and by the inductive resistance constructed in the rotor a short circuited oscillatory circuit is formed which gives extraordinarily good results and is simple in construction.

The inductive resistance 9 may also instead of being constructed in the rotor be constructed as primary coil employed outside the rotor and short circuit the oscillatory circuit over the stator surfaces (see Figure 17).

Fig. 17.



The last six types serve only for producing oscillations of a high number of alternations. If it be desired to obtain ordinary alternating current there complicated constructional arrangements are not required as the types illustrated in Figures 1 to 11 suffice. It is self-evident that these arrangements may be altered in various ways by means of different condenser surfaces in practice.

Having now particularly described and ascertained the nature of our said invention and in what manner the same is to be performed, we declare that what we claim is: --- [Claims not included here]

How Phased Array Antennas Work

One of these exotic antennas is in your future.

What do you think of when you hear the term antenna? Do you picture a cell phone tower, an old TV antenna, a vertical whip antenna used for CB radio, or a wire antenna used by hams? Or, something else completely?

Antennas come in a wide range of forms depending on the application, service, and frequency of operation. Some antennas you can't even see -- like the four or five units in your smartphone. These antennas are single element devices, a metal structure, or printed circuit board (PCB) pattern that are connected to a receiver or transmitter by a transmission line.

Now, another type of antenna is emerging to address the forthcoming exotic 5G cellular systems and other advanced wireless products like Wi-Fi routers. This antenna is the phased array: a group of antennas that work together to provide some significant benefits and capabilities not available with the simple antennas we know.

Phased arrays have been used for years in military radars for long range detection of missiles. They're also widely used in military and commercial aircraft radars and some satellites. These phased arrays are expensive, but today thanks to new technology and higher frequencies, phased arrays are smaller and more affordable making them practical for new wireless devices. This article is an introductory tutorial on this special antenna type you need to know about.

Antenna Types

Different types of antenna elements are used to make up an array. Those commonly used in phased arrays are the dipole and patch; refer to **Figure 1**. The dipole is a basic half wavelength conductor fed at the center. A patch is usually a half wavelength copper square on a PCB. Other antenna types have been used. The spacing between the antenna elements varies with the design but is generally a little more or less than a half wavelength.

Remember the relationship between frequency (f) and wavelength (λ):

$$f = 300/\lambda$$

$$\lambda = 300/f$$

Here, λ is in meters and f is in MHz.

For example, a frequency of 1,296 MHz has a wavelength of:

$$\lambda = 300/1296 = 0.23 \text{ meters or } 23 \text{ cm}$$

A half wavelength is:

$$\lambda/2 = 11.5 \text{ cm or about } 4.5 \text{ inches}$$

(NOTE: There are 2.54 cm per inch.)

Also keep in mind that the length of an antenna depends on the frequency of operation. A half wavelength is generally computed with the expression:

$$L = 492/f$$

where f is the frequency in MHz and the length L is in feet. This formula can also be used where L is in meters:

$$\lambda = 150/f$$

The higher the frequency, the smaller the antenna. At



Figure 1. Common antenna types: **(a)** half wave dipole; **(b)** patch.

Post comments on this article and find any associated files and/or downloads at **www.nutsvolts.com/magazine/issue/2018/09**.



Figure 2. The radiation patterns of a dipole **(a)** and a patch **(b)**.

the lower frequencies, the antennas are just too large to be practical. For example, at 30 MHz, a half wavelength is about 16.4 feet long. A multiple array would be enormous. However, at 5 GHz or 5,000 MHz, a half wavelength is only:

$$\lambda/2 = 150/5000 = 0.03 \text{ meters or } 1.18 \text{ inches}$$

Bigger arrays at the higher frequencies are smaller and more practical.

Many of the new 5G cellular systems will operate in the millimeter wave bands; 28 GHz is an example. One half wavelength at this frequency is only:

$$\lambda/2 = 150/28000 = 0.00536 \text{ meters or } 0.21 \text{ inches}$$

A half wavelength at 60 GHz (a popular unlicensed frequency band) is only:

$$\lambda/2 = 150/60000 = 0.0025 \text{ meters or roughly } 0.1 \text{ inches}$$

At these frequencies, large arrays can be packaged in a small space. The antenna array may even be small enough to integrate on a semiconductor chip along with the related circuitry. This translates into phased arrays inside smartphones and other portable equipment.

Figure 2a shows the radiation pattern of a basic dipole. Its figure 8 pattern causes most power to be radiated broadside from the antenna element and also some in other directions, except in those directions at the ends of the antenna elements. By using multiple antennas in an array, the radiation pattern can be shaped into a narrower beam as shown in **Figure 2b**. This pattern or lobe is made up of multiple signals from multiple antennas in the array. The signals are focused, making them stronger and allowing the beam to be pointed in a desired direction.

Phased Array Defined

A phased array is two or more antennas used together to provide some desired characteristic or feature not available with a single antenna. An array is usually a collection of multiple antennas arranged in a matrix of rows and columns or some other pattern.



Figure 3. A 16-patch array on a PCB. The back of the board is a solid copper backplane that serves as a reflector. Feed lines are not shown.

Figure 3 shows an example using 16 square patch antennas on a PCB. The antennas in the matrix are individually fed units, but collectively they work together as a single antenna. The backside of the PCB has a copper backplane that acts as a reflector. Feed lines are not shown.

The whole idea of the phased array is to achieve some needed features. These key features are:

- **Gain –** Gain is like amplification. Some types of antennas boost the signal level or effective radiated power (ERP) as if greater signal power is used. Gain applies to both transmitting and receiving.
- **Directivity –** Directivity implies that the antenna is more effective in one direction or another. Directivity means that the signal is narrowly focused in one direction. This focusing of the signal is what creates the antenna gain. **Figure 2** showed the broad radiation pattern of a standard dipole and the radiation pattern (or lobe) of a phased array.
- **Interference Minimization –** Pointing the antenna in a particular direction means that it's less effective in the other directions. This feature helps eliminate or reduce interference for signals coming in from other directions. Nulls can be created to take out undesirable signals.
- **Steerable –** Phased arrays can be adjusted to reposition a lobe on-the-fly. The direction of the signal can be changed electronically to optimize the gain. This allows them to scan horizontally and/or vertically.



Figure 4. An original approach to implementing an array with separate circuits. The phase increments are selected to create a lobe of a desired width and point in a desired direction..

Phased Array Operation

Phased arrays implement what we call beamforming. This is done by taking the radiation patterns of each of the antennas in the array and adding them together in such a way that they concentrate the energy into a narrow beam or lobe. The individual antenna signals are said to be interfering with one another either constructively or destructively. Some signals combine to form a stronger composite signal, while others partially cancel one another out.

The radio signal to be transmitted is a sine wave. When you algebraically add two sine waves of the same frequency but different phases, you get another sine wave of the same frequency but with a different amplitude and phase. By manipulating the phase and amplitude of the signal at each antenna, the composite beam can be varied in both width and length (power level). Plus, the beam can be steered to point in a desired direction.

There are several ways to implement the phased array. The older analog method is shown in **Figure 4**. The RF signal from the transmitter power amplifier (PA) is sent to a power divider that splits the RF into equal amounts of signal, creating multiple paths to the antennas. The signals pass through attenuators and phase shifters that allow individual adjustment of the signal level and phase to each antenna element.

Phase shifters introduce a short delay that can be varied. These phase shifters and attenuators can be adjusted electronically so that changes can be made quickly as needed.

Figure 4 shows how the phase shifters influence the composite signal. The red curve represents the wave front from each antenna. With no delay on the top antenna and equal incremental delays on the lower elements, you can see that the delayed waves occur further out in time to the right. Then, they combine to create a composite wave front that is shifted upward at an angle.

This older method used separate attenuators, phase shifters, and other components. A newer approach is modular. That is, the antenna element and related transmit and receive amplifiers, shifters, attenuators, and switches are packaged together as a module; refer to **Figure 5**. In transmit mode, the signal from the transceiver passes through the attenuator, phase shifter, and T/R switch to the power amplifier and then to the antenna.

In receive mode, the signal from the antenna passes through the T/R switch to the low noise amplifier and through the phase shifter and attenuator to the receiver section of the transceiver.



Figure 5. The modular approach to building phased array packages with all components on a single chip. The attenuators and phase shifters are electronically changed by an external microcontroller that is programmed to implement a desired beam width and direction.

These modules can be packaged together as an array as needed. Today, semiconductor technology lets you put one or more modules on a single semiconductor chip.

A good example of a commercial product available to implement phased arrays is the Anokiwave family of millimeter wave phased array front-ends. The AWMF-0139 operates in the 24 to 26 GHz band allocated to the coming 5G cellular networks It encapsulates four modules per IC. **Figure 6** shows how 64 of these chips can be used to make a 4 x 64 = 256 element array. Another similar IC is Analog Devices ADAR1000.


5G Active Antenna Array Formation

Courtesy of Anokiwave, Inc.

Figure 6. The Anokiwave AWMF-0139 IC contains four antenna modules. These ICs are mounted on the back of the PCB with the patch array on the front.

MIMO

Phased array antennas can also be used for multiple input multiple output (MIMO). MIMO is a technique that transmits the same data with multiple antennas over the same path in the same bandwidth. This does two things.

First, each signal takes a slightly different route to the receiving antennas. The result is less fading and greater data reliability. Second, MIMO multiplies the data rate by a factor that is determined by the number of transmit and receive antennas. Common configurations are 2 x 2, 4 x 2, 4 x 4, and 8 x 8, where the first number is the number of transmit antennas and the second number is the number of receive antennas.

A multi-element phased array can be partitioned into sections making it suitable for some MIMO applications. For example, the 256-element array could be arranged to provide four 64-element arrays or sixteen 16-element arrays. With beam steering capability, the signal path can be optimized for best performance.

Also, 5G cellular radios operating in the millimeter wave bands will use MIMO to give gigabit data rates. The big hurdle is putting a phased array into a smartphone handset. Initially, two antennas will be used and later will be increased to four. MIMO is also widely used in Wi-Fi routers. **NV**

Learn About Charlieplexing LEDs

Build The

Analog Style LED Clock

Get the kit from the *Nuts & Volts* Webstore
store.nutsvolts.com

PRELIMINARY PLANS TO RUN YOUR CAR ON TAP WATER!

IT ALSO WORKS ON YOUR
TRUCK / RV / MOTORCYCLE / AIRPLANE (ETC)

Will This Work?

These plans were sent to the Spirit of Ma'at anonymously, from someone who does not want his or her name printed (for obvious reasons).
We have had them checked by an expert who believes that they are real.
We also have talked with another individual who has patented a similar device, and we know by personal experience that the technology is sound.
So although we cannot guarantee it, we believe these plans will enable you to build a car that runs on water. If you test it out, though, do as the writer suggests and use an old car that doesn't represent a loss of value if you can't make it work. And leave everything intact so that you can always reconnect back to gas if you have to.

But if you do get it working, please send us your experience for our readers. You could be a national hero and help save our country and our world.

We know for certain that an automobile will run on water. So this could be an interesting project for you mechanical types, with a great reward of never having to purchase gasoline for the rest of your life - and helping humanity at the same time.

Re The Need to Rustproof Your Exhaust System

It is possible to make a hybrid of both gas and water (a system that is being tested now in Mexico), which would eliminate the need to open the head and remove the exhaust system. Just a thought. It takes only a small amount of gas to keep the system dry.

The text sent from the anonymous individual was edited slightly for better reading. The following is his/her words and drawings, which has been given into the public domain.
- Spirit of Ma'at LLC

Introduction

It is suggested you try this out to begin with on a second vehicle you own, one that you don't need to live with everyday, until you perfect this technology.

Do-it-yourself plans allow the individual (that's you and me, folks) to make a difference. This is the easiest and lowest-cost way to convert your car to run on (relatively) free energy.

Now, with existing technology, anyone can stand up and make a difference by reducing the local automotive pollution, eliminate gasoline expenses, help restore our atmosphere, and breathe a little easier.

In putting these plans into operation, you will be making use of your entire existing system except for the fuel tank and the catalytic converter.

The Plan

Build and install a low-cost alternative method for running your vehicle (internal combustion engine) on tap water, using off-the-shelf components.

This is simply an efficient way to convert ordinary tap water into gaseous hydrogen and oxygen, and then burn these vapors in the engine, instead of gasoline.

This "minisystem" runs easily from your existing battery and electrical system, and it plugs into your carburetor with simple off-the-shelf fittings.

You will be installing a plastic water tank, a control circuit, a reaction chamber, a hi-pressure carb/FI fitting, and 3 gauges, and then hooking into your existing carb/FI.

The simplicity comes from its being an "on-demand" system requiring no fancy storage or plumbing. You crank the gas pedal or throttle, and you electrically create more vapor for immediate consumption, on demand; low-high flow rate as needed, from idle to maximum power. The only real change is that you are using tap water as fuel, instead of the traditional petroleum-based fuel.

Given a choice, which way would you choose?

Frequently Asked Questions

Q: Does it really work ?
A: Yes; this is well-established technology dating back to stainless steel. But be sure to follow these instructions using the proper mechanical and electrical assembly techniques, as this plan incorporates the best qualities of several techniques.

Q: How does it qualify as "free energy"?
A: If you're paying someone for the water you use, then it is not strictly free. But the alternative is to keep buying into expen$ive ga$oline and its resultant hydrocarbon pollution.

Q: Is it safe?
A: Technically, it is safer than running on fossil fuel because you are no longer choking on your own emissions (health-wise). In general, it is practically as safe as your current gasoline arrangement. You will be installing a few simple safety devices, using current automotive standards.

Q: What kind of performance can I expect?
A: Properly adjusted, your modified vapor-only fuel system will run cooler, and at a modestly higher power level. The mileage performance expected from this design ranges from 50-300 mpg (of water), depending on your adjusting skills.

Q: Can I do the modification myself?
A: Why not? If you don't have any mechanical skills, and you know someone with basic mechanical and/or electrical skills, you can even delegate some of the construction. If you are using a fuel-injected engine, you may have to get a mechanic's opinion. [There will have to be an adapter inserted into the fuel-injection system, just as you would have to do if you were going to run on propane, hydrogen, or natural gas. Ed.)

Q: What is the environmental impact that my vehicle will have?
A: It will be producing H20 steam (water vapor) and unburnt O2 (Oxygen). Hence, it will be cleaning the environment, rather than dumping nauseous toxins into it. Plus you will be helping to save our dwindling supply of atmospheric oxygen. Any excess vapor in the reaction becomes either steam or oxygen. You can also expect to be receiving more than casual interest from those around you.

Q: Isn't this really a steam engine?
A: No. Really. Exceedingly high temperature and pressure are not used. This is strictly an internal-combustion engine (burning orthohydrogen) with residual steam in the exhaust as a by-product.

There are a few things you should know about gasoline:

Gasoline as a fuel is not necessary; it is optional.

Gasoline versus Water

There is a lot of thermochemical energy in gasoline, but there is even more energy in water. The DOE (Department of Energy) has quoted about 40%, so it is probably much more than that.

Most people are unaware that "internal combustion" is defined as "a thermo-vapor process" - as in "no liquid in the reaction." Most of the gasoline in a standard internal combustion engine is actually consumed, (cooked, and finally, broken down) in the catalytic converter after the fuel has been not-so-burnt in the engine. Sadly, this means that most of the fuel we use in this way is used only to cool down the combustion process, a pollution-ridden and inefficient means of doing that.

How It Works

Exceedingly simple. Water is pumped as needed to replenish and maintain the liquid level in the chamber. The electrodes are vibrated with a 0.5-5A electrical pulse which breaks $2(H_2O) => 2H_2 + O_2$. When the pressure reaches say 30-60 psi, you turn the key and go. You step on the pedal, you send more energy to the electrodes, and thus more vapor to the cylinders; i.e. fuel vapor on demand.

You set the idle max-flow rate to get the most efficient use of power, and you're off to the races.

In the big picture, your free energy is coming from the tap water in an open system, as the latent energy in the water is enough to power the engine and hence drive the alternator and whatever belt-driven accessories. And the alternator is efficient enough to run the various electrical loads (10 - 20 amps), including the additional low current to run this vapor reaction. No extra batteries are required.

STEP BY STEP CONSTRUCTION (Please refer to diagrams at the end of this document)

OVERVIEW - Here is the suggested sequence of steps:

1. Install the CHT (or EGT) gauge and measure your current operating temp range (gasoline), for comparison.

2. Build and test the controller to verify the correct pulse output.

3. Build the reaction chamber and test it with the controller (i.e pressure out).

4. Install the tank, controller, chamber, and pressure fittings.

5. Run engine and adjust the control circuit as necessary for best performance.

6. Install the stainless steel valves and get the pistons/cylinders coated with ceramic.

7. Coat the exhaust system with ceramic without the catalytic converter (or let it rust out and then replace the whole dang thang with stainless steel pipe sections).

YOU WILL NEED

plastic water tank with pump and level sensor.
control circuit, wiring, connectors, and epoxy.
reaction chamber with electrodes and fittings.
3/8" stainless steel flex-tubing, fittings and clamps.
carb/FI vapor-pressure fitting kit. - pressure, CHT (or EGT), & level gauges.
stainless steel valves.
copper mesh junction.
ceramic surface treatment for cylinders & pistons.
stainless steel or ceramic treated exhaust assembly.

BASIC TOOLS

drill, screwdriver and pliers
hole cutter
wire-wrap, solder-iron and clippers
DVM and oscilloscope.

REACTION CHAMBER

Construct as shown in the diagrams. Use a section of 4" PVC waste pipe with a threaded screw-cap fitting on one end and a standard end-cap at the other. Make sure to drill-and-epoxy or tap threads thru the PVC components for all fittings. Set and control the water level in the chamber so that it well submerses the pipe electrodes; yet leave some headroom to build up the hydrogen/oxygen vapor pressure. Use stainless steel wires inside the chamber or otherwise use a protective coating; use insulated wires outside. Ensure that the epoxy perfects the seal, or otherwise lay down a bead of water-proof silicone that can hold pressure.

The screw fitting may require soft silicone sealant, or a gasket; its purpose is to hold pressure and allow periodic inspection of the electrodes. No leaks, no problems. Make sure you get a symmetric 1-5mm gap between the 2 stainless steel pipes. The referenced literature suggests that the closer to 1mm you get, the better. You will want to get your chamber level sensor verified before you epoxy the cap on.

Make your solder connections at the wire/electrode junctions nice, smooth, and solid; then apply a water-proof coating, e.g. the epoxy you use for joining the pipes to the screw cap. This epoxy must be waterproof and be capable of holding metal to plastic under pressure. You will want to get your chamber level sensor verified before you epoxy the cap on.

CONTROL CIRCUIT

The diagrams show a simple circuit to control and drive this mini-system. You are going to make a 'square-pulse' signal that 'plays' the electrodes like a tuning fork; which you can watch on an oscilloscope. The premise given by the literature is: the faster you want do go down the road, the 'fatter' you make the pulses going into the reaction chamber. Duty cycle will vary with the throttle in the vicinity of 90%MARK 10%SPACE (OFF/ON).

There is nothing sacred about how the pulse waveform is generated; there are many ways to generate pulses, and the attached diagrams show a few. The diagram shows the NE555-circuit approach from the referenced patent. The output switching transistor must be rated for 1-5 amps @ 12VDC (in saturation).

Go with a plan that works for you or your friendly neighborhood technoid or mechanic, and go get all the circuit elements from your local electronics store, such as Radio-Shack or Circuits-R-Us, including the circuit board, IC sockets, and enclosure/box.

DigiKey has better selection, service, and knowledge; plus they have no minimum order. Be sure to use a circuit board with a built-in ground plane, and to accommodate room for mounting 2 or 3 of the gauges. Mounting the reaction chamber in the engine compartment will require running a stub to your pressure gauge where you can watch it.

You can easily make 30-gauge wire-wrap connections between the socket pins and thru-hole discrete components having wire leads. Also make sure to get spec sheets on any IC you use. More details of the best circuits to use will be announced pending prototype testing. You will want to get your chamber level sensor verified before you epoxy the cap on.

Throttle Control

If you have a throttle position sensor, you should be able to access the signal from the sensor itself OR from the computer connector. This signal is input to the circuit as the primary control (i.e. throttle level = pulse width = vapor rate).

If you don't have such a signal available, you will have to rig a rotary POT (variable resistor) to the gas linkage (i.e. coupled to something at the gas pedal or throttle cable running to the carb or FI. If you make the attachment at the carb/FI, be sure to use a POT that can handle the engine temp cycles. Don't use a cheezy-cheapy POT; get one rated for long life and mechanical wear; mount it securely to something sturdy and stationary that will not fall apart when you step on the gas.

Control Range. The full throttle RANGE (idle-max) MUST control the vapor rate, i.e. pulse-width (duty). The resistor values at the throttle signal must allow the throttle signal voltage, say 1-4 Volt swing, to drive the VAPOR RATE. You will be using this voltage swing to generate a 10% ON 'square' pulse. The patent implies using a 'resonant' pulse in the 10-250 KHz frequency range; but it is not explicitly stated so.

In this circuit, you will simply tune to whatever frequency makes the most efficient vapor conversion. You will have to get into the specs for each IC you use, to insure you connect the right pins to the right wires, to control the frequency and pulse width. You can use spare sockets to try out different discrete component values. Just keep the ones that are spec-compatible in the circuit, and get the job done.

You crank up the throttle signal and put more electrical energy (fatter pulses) into the electrodes; verify you can get 10% duty on the scope (2 - 100 usec on the horizontal time-base). Your averaging DVM will display the 90%-10% DC voltage across the output transistor (Vce or Vds or Output to Ground). Set and connect DVM in the supply current and measure .5 - 5 amps, without blowing the DVM fuse. Now verify that you got everything you wanted.

Verify your wiring connections using your DVM as a continuity detector. Check your wiring 1 at a time and yellow line your final schematic as you go. You can best use board-mount miniature POTs for anything you want to set-and-forget. The LEDs are there to give you a quick visual check of normal vs abnormal operation of your new creation. You will want to get your chamber level sensor verified before you epoxy the cap on.

CARB/FI CONNECTION

The diagram also shows that fittings are required to the carb/FI l. There are ready-made kits (such as by Impco) available for making your pressure fittings to the carburetor or fuel-injector as the case may be. You will necessarily be sealing the built-in vents and making a 1-way air-intake.

The copper mesh comprises the inadvertent backfire' protection for the reaction chamber. Make sure that all vapor/duct junctions are air-tight and holding full pressure without leakage. Your new 'system' is considered successful and properly adjusted when you get the full power range at lower temp and minimum vapor flow without blowing the pressure safety valve.

CHT (or EGT)

Monitor your engine temp with the CHT (cylinder head temp) or EGT (exhaust gas temp) instead of your original engine temp indicator (if any). Your existing gauge is too slow for this application and will not warn you against overheating until after you have burnt something. Make sure that your engine runs no hotter than in the gasoline arrangement. VDO makes a CHT gauge with a platinum sensor that fits under your spark plug against the cylinder head (make sure it is really clean before you re-install your spark plug (as this is also an electrical ground).

ENGINE/EXHAUST TREATMENT

Get the valves replaced with stainless steel ones and get the pistons/cylinders ceramic-treated ASAP when you have successfully converted and run your new creation. Do not delay as these items will rust, either by sheer use or by neglect (i.e. letting it sit). You could make max use of your current exhaust system by using it with your new deal until it rusts through, then have your mechanic or welder friend to fit a stainless steel exhaust pipe (no catalytic converter is required). But it could be easier and cheaper to send your existing exhaust system out for the ceramic treatment, and then simply re-attach it to the exhaust ports.

GENERAL

1. Do not discard or remove any of the old gasoline setup components, e.g. tank, carb/FI, catalytic converter, unless necessary. Better to always leave an easy way to revert back to something that at least runs, just in case. Some people are leaving their gasoline setup completely intact, and switching back and forth at will, just to have a backup plan.

2. Set your throttle circuit so that you get minimum vapor flow at idle, and maximum vapor flow at full power without blowing the pressure relief valve. In this way, you control how 'lean' your mixture is by the strength of the pulse (i.e. “fatness” at the optimum pulse frequency).

3. If you just don't get enough power (at any throttle setting), it means that you need to (1) change the pulse frequency, (2) change the gap between the electrodes, (3) change the size (bigger) electrodes, or (4) make a higher output pulse voltage (last resort). Always use an output transistor, such as a MOSFET, that is rated for the voltage and current you need to get the job done. OK so you might have to play around with it some. Isn't that where all the Fun is anyhow?

4. If you get any engine knock our loud combustions (not compensated by adjusting the timing), it means that you need to install an additional coil in the chamber, and drive the coil with an additional pulse signal (about 19 Hz on the .1sec time base (see diagram). Here,

you will be slowing down the burn rate just enough so that the vapors burn thru out the power stroke of the piston. Be sure to include a board-mount POT to set the correct strength of this 2nd pulse signal into the coil. This is a stainless steel coil of about 1500 turns (thin wire) that you can arrange like a donut around the center pipe (but NOT touching either electrode), directly over the circular 1-5mm gap. You want no knocking at any power/throttle setting; smooth power only, but also no excess hydrogen leftover from the combustion.

5. Build the canister(s) as tall as you can without compromising your ability to mount them conveniently near the dash panel, or in the engine compartment, as the case may be. This way, you can always make the electrodes bigger, if necessary without undue hardship. Remember that anything in the engine compartment should be mounted in a bullet-proof, vibration and temperature tolerant fashion.

6. If you have to drill a thru-hole for wiring or plumbing thru metal, make sure to also install a grommet for protection against chafing. Always watch your chamber pressure range from IDLE (15-25 psi) - FULL POWER (30-60 psi). Set your safety-pressure relief-valve to 75 psi and make sure it's rated for much higher.

7. Shut OFF the power switch and pull over if there is any malfunction of the system. Your engine will last longest when it still develops FULL POWER+ at some minimum temperature that we are sure you can find, by leaning back the Royal Vapor Flow and/or by making use of the water-vapor cooling technique (see diagram). Keep good mpg performance records, and periodic maintenance/inspection. Keep it clean; save some money; clean the air; heal the planet; happy motoring; tell a friend; enjoy your freedom and self-empowerment.

8. There lacks documented material for perfecting this vapor system thru a fuel injector; there may be some details you will discover on your own as working prototypes progress. For example, you may be restricted to inject the hydrogen/oxygen vapor without any water vapor, as it may rust the injectors. If engine temp and CHT is a problem, then you will want to re-think your plan, e.g. ceramic-coating the injectors. There is always “replacing the FI system with a Carb.”

9. If you install the water-vapor system (for lower operating temp/stress), you will want to lean the mixture (vapor/air) for minimum vapor flow rate to achieve any given throttle position (idle - max). Make sure that you get a minimum flow for IDLE and a modestly sufficient flow for MAX, that does the cooling job without killing the combustion.

10. If you cannot find stainless steel pipe combinations that yield the 1-5mm gap, you can always regress back to alternating plates of +/- electrodes.

11. If you are concerned about the water freezing in your system, you can (a) add some

98% isopropyl alcohol and re-adjust the pulse frequency accordingly; or (b) install some electric heating coils.

12. Do not let ANYONE ever compromise your dream, your freedom, your independence or your truth.

REFERENCES

Stephen Chambers 'Apparatus for Producing Orthohydrogen and/or Parahydrogen' US Patent 6126794, uspto.gov
Stanley Meyer 'Method for the Production of a Fuel Gas' US Patent 4936961, uspto.gov
Creative Science & Research, 'Fuel From Water', fuelless.com
Carl Cella "A Water-Fuelled Car" Nexus Magazine Oct-Nov 1996
Peter Lindemann "Where in the World is All the Free Energy", free-energy.cc <http://www.free-energy.cc/>
George Wiseman "The Gas-Saver and HyCO Series" eagle-research.com <http://www.eagle-research.com/>
C. Michael Holler "The Dromedary Newsletter" and "SuperCarb Techniques"
Stephen Chambers "Prototype Vapor Fuel System" xogen.com <http://www.xogen.com/>

COMMON LAW COPYRIGHT #285714: All rights to the use and duplication of these plans are hereby reserved for the People, in their efforts to heal and restore the environment. Dare to express your uniqueness and environmental ideals. This technology is an exercise in responsible self-determination.

DISCLAIMER: The Spirit of Ma'at LLC and the Spirit of Ma'at ezine and the author of this document assumes no liability for the use or misuse of this information; which is made available as public-domain information and free of charge, for the purposes of education, ecology, health, well-being, freedom, liberty, and pursuit of happiness.

CONVERT YOUR ENGINE TO BURN HYDROGEN AND OXYGEN VAPOR FROM WATER....... ON DEMAND + POLLUTION-FREE

FIGURE 1


level and pressure gauges
water tank
carb or F.I.
engine
control circuit
pump
electrode pulses
reaction chamber
exhaust system

BUILD YOUR OWN WATER VAPOR SYSTEM CONTROLLER FROM THE-SHELF MATERIALS


PRESSURE GAUGE
1-WAY VALVE
3/8"
SAFETY VALVE
CHAMBER
1-WAY VALVE
LEVEL SENSOR
4" PVC drain pipe
stainless steel pipes
1/4"
DRAIN VALVE
epoxy-filled end-cap
CHAMBER LEVEL
PULSE
CHT
THROTTLE
CONTROL CIRCUIT
PRESSURE FITTINGS
TANK LEVEL
+
-
ARRESTOR
BAT
CARB/FI
AIR
WATER TANK
ENGINE
PUMP
EXHAUST SYSTEM

FIGURE 2 BLOC DIAGRAM

BUILD YOUR OWN WATER VAPOR SYSTEM CONTROLLER FROM THE-SHELF MATERIALS


12 VDC
fuse
on/off
+
bat
-
electrodes
diode
off/on pulse
throttle
pulsewidth control
on/off signal
electrode switch
adj. frequency
f
oscillator
pulse generator
ground
tank level sensor
tank level gauge
chamber level gauge
chamber level sensor
"pump active"
+ 12VDC
+ 12VDC
pump
detector
switch
ground

FIGURE 3 E-DIAGRAM

BUILD YOUR OWN WATER VAPOR SYSTEM CONTROLLER FROM THE-SHELF MATERIALS

REV. A


electrodes
12 VDC
on/off
fuse
12 VDC
+
bat
-
1k
"pwr on"
+
10uf
throttle adjust
pulsewidth adjust
2k
7
4
8
.1uf
on/off
signal
6
20k
10k
2
-
7
LM741
pwm
1 - 4V
idle-max
5
3
throttle
10k
3
+
6
4
100k
NE555
.1uf
2
1
1N4007
.1uf
8
1
.1uf
IFR510
TR3
d
2
6
7
g
pulses
out
TC4420CPA
MOSFET
DRIVER
4
5
MOSFET
s
switch
12VDC
CD4069
1k
2
3
14
4
5
1
7
TRIGGER
6
oscillator
ground
frequency
adjust
2k
1k
dipswitch
.01u
.1u
.03u
3300pf
+ 12VDC
pressure
gauge
L
tank
level
sensor
spark plug
L
cht
gauge
L
tank level
gauge
chamber
level
sensor
L
chamber level
gauge
100k
10k
2
7
LM741
3
+
6
4
100k
detector
.01uf
"pump active"
1k
pump
10k
E3055T
ground

FIGURE 4 E-SCHEMATIC

BUILD YOUR OWN WATER VAPOR SYSTEM
CONTROLLER FROM THE-SHELF MATERIALS

REV. A


CHAMBER
stainless steel 'donut' coil
PULSES
fast
slow
THROTTLE
CONTROL CIRCUIT
slow pulse
1N4007
pulse width adjust
% strength adjust
12VDC
19Hz pulse
4
8
7
6
5
3
1
2
10k
10k
10k
2N3055
.1uf
1uf
ground
NE555
19 Hz trigger
.01uf
N = fast pulse rate/19
divide by N
out
clock
in
existing circuit
fast pulse
555
3
2
4420
TR3

FIGURE 5   OPTIONAL PRAHYDROGEN ENHANCEMENT

BUILD YOUR OWN WATER VAPOR SYSTEM
CONTROLLER FROM THE-SHELF MATERIALS


valve
3/8"
VAPOR CHAMBER
1-WAY VALVE
LEVEL SENSOR
see-thru fuel filter w. glass removed
DRAIN VALVE
CHAMBER LEVEL
1-WAY VALVE
rig level sensor & pump same as in Figure 3
PRESSURE FITTINGS
3/8"
CARB/FI
AIR
WATER TANK
ENGINE
tapped pressure fitting
2nd PUMP
EXHAUST SYSTEM

FIGURE 6 OPTIONAL WATER COOLING

Capacitors we used are electrolytic rated at 400 volts x 47 uF put in series to equal 6,000 volts, the diodes we used were silicon 1000 volt 2 amp placed in series to equal 6,000 volts......... Ground was connected to laboratory wall out let ground.

If you decide to try Tesla's experiment by pumping DC into the ground be careful, I tried this and it does work but is very dangerous to you or your neighbors. If someone is taking a shower or using water they can get killed or shocked. do this experiment far away from humans and animals. you can get far more energy out than you put in. I will not tell you much more because it is such a dangerous experiment.



RADIO SCIENCE Journal of Research NBS/USNC–URSI
Vol. 69D, No. 8, August 1965

Schumann Resonances [1]

Janis Galejs

Applied Research Laboratory, Sylvania Electronic Systems, a Division of Sylvania Electric Products Inc.,
40 Sylvan Road, Waltham, Mass. 02154

(Received February 3, 1965)

This paper reviews the current work in the field of Schumann resonances and discusses the topics of waveforms and frequency estimates, resonance frequencies and Q factors, source distributions and noise spectra, diurnal and seasonal changes of power spectra, and variations of resonance frequencies. Observations of the above phenomena are correlated with theoretical considerations.

1. Introduction

The resonances in the spherical shell between the earth and ionosphere that are due to azimuthal waves have been considered in two recent survey papers [Galejs, 1964a; Wait, 1964a]. This work contains experimental data as well as the required theory. The basic theory of the resonances has been reviewed by Wait [1964b]. In the present summary the emphasis will be on correlation between measurements and available theory. There will be no extensive analytical developments, but frequent references will be made to literature.

Based on theoretical considerations, Schumann [1952a, b, 1957] postulated resonances of the earth-to-ionosphere cavity. Koenig [1958, 1959, 1961] obtained the first experimental indication of Schumann resonances by observing noise waveforms in the output of a narrow band amplifier. Detailed frequency spectra of this noise were first obtained by Balser and Wagner [1960]. Other measurements have been reported by Fournier [1960]; Benoit and Houri [1961, 1962]; Lokken et al. [1961, 1962]; Polk and Fitchen [1962]; Gendrin and Stefant [1962a]; Balser and Wagner [1962a, b, 1963]; Rycroft [1963]; Chapman and Jones [1964].

The fundamental theory of Schumann resonances [Schumann 1952a, b, 1957] is discussed in a book by Wait [1962]. Raemer [1961a, b] considers the observable noise spectra as the response of the earth-to-ionosphere cavity due to lightning flashes all over the world, but the homogeneous sharply bounded ionosphere model of Raemer introduces high losses, and he does not succeed in reproducing the spectral measurements of Balser and Wagner [1960]. Galejs [1961a, b] uses an isotropic ionosphere model of exponentially increasing conductivity which is based on measured or calculated characteristics of the lower ionosphere. This model permits a close reproduction of the noise spectra measurements in the resonance region, and it also provides an agreement with measured ELF attenuation rates [Chapman and Macario, 1956; Jean et al., 1961].

Models of an anisotropic ionosphere are difficult to apply to the problem of earth-to-ionosphere cavity resonances because of the variations of the magnetic field vector along the surface of the earth. The propagation parameters can be estimated in the presence of a horizontal magnetic field component from the work of Galejs and Row [1964] and of Galejs [1964b]. The earth-to-ionosphere cavity resonances have been analyzed for a nonhomogeneous ionosphere in the presence of a radial (vertical) magnetic field by Thompson [1963] and Galejs [1965]. A thin-shell approximation of the ionosphere with a superimposed radial magnetic field has been considered by Wait [1964c]. Some other work of Wait [1963a, b], although intended for a different frequency range, can also be applied to the earth-to-ionosphere resonance problem in the presence of a radial magnetic field.

Additional references are available in the comprehensive bibliography by Brock-Nannestad [1962].

2. Waveforms and Frequency Estimates

In wide band recordings of atmospheric signals an ELF component or slow tail follows the initial VLF component of the transient [Hepburn and Pierce, 1953; Liebermann, 1956a, b; Tepley, 1959; Pierce, 1960]. An oscillatory structure of the signal becomes noticeable by passing it through a band-pass filter. An example of a noise recording in the output of a 2 to 30 c/s band-pass filter [Lokken, 1964, private communication] is shown in figure 1. The two horizontal magnetic field components have been observed simultaneously in Canada and in Antarctica. There is a correlation between the high intensity ELF noise bursts observed at the various sites. A recording of one of the waveforms is shown in figure 2. The darkened areas indicate resonance frequencies around 8, 14, and 20 c/s. Noise waveforms in the 5 to 20 c/s band have been reported by Polk and Fitchen [1962] and Polk [1962]. Figure 3 shows sample recordings of the outputs of two coils the axes of which are oriented in the north to south (N–S) and east to west (E–W) directions. Frequency of these waveforms has been estimated by counting the cycles between the second markers shown on the records. The average frequency computed in this procedure should be higher than the resonance frequencies of a spectral analysis [Galejs, 1962a, 1964a]. Noise recordings made simultaneously in Germany and in Rhode Island have been reported by Keefe, Polk, and Koenig [1964].

---

[1] Paper presented at the ULF Symposium, Boulder, Colo., Aug. 17–20, 1964.



FIGURE 1. *Noise recording in the 2 to 30 c/s band.*



FIGURE 2. *Recording of the noise waveform X of Westham Island, B.C.*



FIGURE 3. *Noise recording in the 5 to 20 c/s band.*

3. Resonance Frequencies and Q Factors

3.1. Definitions

A resonance frequency and Q factor may be determined from spectral measurements. Analytically it is also possible to compute the power spectrum of the noise waveform. However, it is more convenient to relate the resonance frequency and the Q factor to the analytically determined propagation parameters. The radial electrical field due to the vertical dipole excitation can be represented by

$$E_r = -\frac{iIds}{4\omega\epsilon ha^2}\frac{\nu(\nu+1)}{\sin\nu\pi}P_\nu(-\cos\theta) \tag{1}$$

where

$$\nu(\nu+1) = (k_0 aS)^2. \tag{2}$$

For a wave that propagates in the spherical shell between the earth and the ionosphere S is defined as the ratio of the complex wave number k to free space wave number $k_0 (S = k/k_0)$. The real part of S can be seen to be inversely proportional to the phase velocity, and the imaginary part of S is proportional to the attenuation constant. This parameter S is determined from solving the appropriate boundary value problem of the earth, the air space and the chosen ionosphere model [Wait, 1962; Galejs, 1964a]. The resonance frequencies of the nth mode are determined from the minima of $\sin\nu\pi$ in (1) [Galejs, 1962a, 1964a] which gives

$$f_n \approx \frac{7.5\sqrt{n(n+1)}}{\mathrm{Re}S}. \tag{3}$$

Typical values of ReS are 1.4 to 1.2 for frequencies in the resonance region.

The cavity Q may be determined as a ratio between the stored energy and energy loss per cycle or simply by the width of the resonance curves. As shown in the appendix, in the present problem the electrically stored energy W_e differs from the magnetically stored energy W_h, and the Q definition should consider the sum of the average stored energies W_e and W_h. This expression for Q is

$$Q=\frac{(\mathrm{Re}S)^2+1}{4\mathrm{Re}S\,\mathrm{Im}S}. \tag{4}$$

When considering only the magnetically stored energy Q is given by

$$Q=\frac{1}{2\,\mathrm{Re}S\,\mathrm{Im}S}. \tag{5}$$

For a given set of propagation parameters this will give a lower Q figure than (4). This expression has been used in the past work of Galejs [1961a, 1962a, b, 1964a]. Considering only the electrically stored energy gives

$$Q=\frac{\mathrm{Re}S}{2\,\mathrm{Im}S}. \tag{6}$$

The last expression can also be derived from the concept of complex resonance frequencies [Wait, 1964a] or by considering the half-power band width of the resonance curve. All three Q definitions yield the same results as ReS approaches unity, but they will differ near the lower resonance frequency of the earth ionosphere cavity. Equation (4) will be used in the present calculation.

Experimentally determined Q values that are estimated from the half-power bandwidths of the resonance curves neglect the effects of adjacent resonances and of near-field noise that will tend to add to the background level. Hence, the half-power level is estimated too low, the apparent half-power bandwidth is larger and the estimated Q factor may be too low.

3.2. Characteristics of the Boundary

In the theoretical models that are advanced for explaining the resonance frequencies and the Q-factor measurements [Wait, 1962; Galejs, 1964a; Wait, 1964a] it is necessary to consider the boundary properties of the spherical shell.

In the frequency range of the resonances the displacement currents of ground are negligible and the ground conductivity $\sigma_g=10^{-3}$ to 1 mho/m is much higher than the effective ionospheric conductivity σ_i that is estimated to be of the order of 10^{-7} to 10^{-6} mho/m. The ground conductivity σ_g may be assumed as infinite in the first approximation and only the ionospheric properties require a detailed analysis.

The ionosphere acts as an anisotropic conductor and for a z-directed magnetic field its conductivity tensor is of the form

$$[\sigma]=\begin{bmatrix}\sigma_1 & -\sigma_2 & 0\\ \sigma_2 & \sigma_1 & 0\\ 0 & 0 & \sigma_0\end{bmatrix}. \tag{7}$$

Equations for computing the conductivity components are available in literature [Galejs, 1964a and b] and typical conductivity profiles are shown in figure 4 but some uncertainties still apply to such models [VanZandt, 1964]. The above computations consider the ion effects, but assume the operating frequency to be zero. These profiles can be further approximated by straight lines through the lower ionosphere in the semilogarithmic plots of figure 4, which corresponds to an expoential height variation of the conductivity components. In a further simplification the anisotropy may be ignored ($\sigma_1=\sigma_0$, $\sigma_2=0$). Even a simple one or two layer model can be assumed, such as shown in figure 5. These particular models have been used in past work by Raemer [1961a and b], Galejs [1962a and b], and by Chapman and Jones [1964]. In the isotropic exponential model the conductivity is given by

$$\sigma(z)=\sigma(z_0)\ \exp\ [\beta(z-z_0)] \tag{8}$$

where $z_0=60$ km and the day and night models are characterized by $\sigma(z_0)=4.63\times10^{-8}$ mho/m and $\beta=0.308$ km^{-1} and by $\sigma(z_0)=6.5\times10^{-10}$ mho/m and $\beta=0.44$ km^{-1}, respectively.



FIGURE 4. *Components of the tensor conductivity* F=0.



FIGURE 5. *Models of ionospheric conductivity.*

3.3. Single Layer Ionosphere

The single layer ionosphere model of Raemer [1961a and b] assumes the boundary height of the ionosphere to be constant, but the conductivity to change with frequency so as to obtain the correct resonant frequencies. However, the resulting *Q* factors are approximately two times lower than in measurements. The same difficulties are experienced with an ionosphere model of constant conductivity, but frequency dependent boundary height. Similar results are obtained by Madden [1961] with a conductivity of $\sigma = 1.8 \times 10^{-6}$ mho/m and the ionospheric boundary at $h = 80$ km. The deficiencies of a single layer ionosphere model are less pronounced if it is attempted to achieve only a partial match of the resonant frequencies, as seen from Wait [1964a]. However, the *Q* factors will be too low in particular at the higher resonance frequencies ($f \approx 30$ c/s).

Compressibility effects of the ionosphere have been considered by Seshadri [1965b] using the model of a perfectly conducting flat earth and a sharply bounded homogeneous isotropic and lossless ionosphere. The compressibility of the ionosphere does not affect the wave propagation below it for frequencies in the range of Schumann resonances and in the ELF band. However, the compressibility should be considered for waves that propagate inside the ionosphere [Seshadri, 1965a].

3.4. Two-Layer Ionosphere Models

Two-layer models give more accurate values of the resonance frequencies and of cavity *Q* or of the complex propagation parameter *S*. Two-layer and multilayer models have been discussed by Wait [1958, 1962]; Madden [1961]; Jean et al. [1961], and a particularly successful two-layer model has been constructed by Chapman and Jones [1964a, b]. This model, which is indicated in figure 5, has been applied in the frequency range of earth-to-ionosphere cavity resonances and also for frequencies up to 1 kc/s.

Such models are usually derived by trial and error procedures and they are difficult to correlate with continuous ionosphere profiles, such as shown in figure 4.

3.5. Models of Continuously Varying Ionosphere

The isotropic exponential model gives a reasonable approximation to the ionospheric conductivity versus height profile through the lower ionosphere layers, and the propagation parameters of the model can be determined from closed form expressions of the surface impedance [Galejs, 1961a, 1962a, b, 1964a]. Calculated resonance frequencies and *Q* factors that are based on (3), (4), and available values of *S* [Galejs, 1962a] are listed in tables I and II. Calculations are based on daytime or day and nighttime ionosphere models. The *Q* factors considered also the effects of cosmic ray ionization [Bourdeau et al., 1959] that give a nearly exponential conductivity versus height variation as indicated by Galejs [1962a]. Cosmic ray ionization decreases the effective *Q* figures, in particular for the lower frequencies. The calculated *Q* values are still somewhat higher than those estimated from experimental data.

TABLE I

RESONANCE FREQUENCIES OF THE SPHERICAL SHELL BETWEEN THE EARTH AND IONOSPHERE

	n	1	2	3	4
RESONANCE FREQUENCY f_n IN C/S	LOSSLESS CAVITY	10.6	18.3	25.9	33.5
	DAYTIME WITH h = 45 KM	7.6	13.5	19.4	25.4
	AVERAGE DATA OF DAY WITH h = 45 KM AND OF NIGHT WITH h = 60 KM	8.05	14.25	20.5	26.8
	MEASUREMENTS	8	14.1	20.3	26.4

TABLE II

Q FACTORS OF EARTH-IONOSPHERE CAVITY RESONANCES

	f IN C/S	10	30	100
Q - FACTORS	DAY WITH h = 45 KM, NIGHT WITH h = 60 KM	8.5	7	6.7
	DAYTIME ONLY WITH h = 45 KM	6.5	5.4	5.2
	DAY WITH h = 45 KM, NIGHT WITH h = 60 KM, COSMIC RAY IONIZATION	5.5	6	6.4
	MEASUREMENTS	4	6	

3.6. Magnetic Field Effects

The magnetic field effects for a homogeneous sharply bounded ionosphere model have been discussed by Wait [1962] in a quasi-longitudinal approximation for a superimposed radial magnetic field and also for a transverse magnetic field (east-west or west-east propagation along the magnetic equator).

The propagation parameters have been determined by Galejs and Row [1964] and Galejs [1964a, 1964b] in the presence of a horizontal magnetic field. These data provide an indication of propagation characteristics of the waves near the magnetic equator, but they do not apply directly to the earth-ionosphere resonance problem, where the **H** vector is nearly horizontal only over a small surface portion of the earth.

The earth-ionosphere cavity resonance frequencies have been considered in the thesis of Thompson [1963] for a radial magnetic field. He uses a multilayer ionosphere model that approximates the continuous altitude variation of the conductivity tensor. The azimuthal field variation is expressed in terms of the Legendre polynomials $P_n(\cos\theta)$ for the nth mode. The wave equation has four different solutions for each of the ionosphere layers, but it has only two solutions for the space between the ionosphere and the perfectly conducting ground surface. The solution of the problem and the resonance condition for the mode n are obtained after multiplying a sequence of 4×4 matrices. In these computations the displacement currents of the ionosphere are neglected. The computed resonance frequencies are in agreement with measurements, but the Q values are in the range of 15 to 20, with the exception of nighttime anisotropic solutions, where $Q=7$ to 10. The lowering of the nighttime Q figures by the magnetic field has been attributed to wave penetration through the ionosphere and to energy thus escaping from the earth-ionosphere cavity.

Another solution to the problem of earth's ionosphere cavity resonance in the presence of a radial magnetic field is given by Galejs [1965]. The azimuthal field variation is expressed in terms of the Legendre functions $P_\nu(-\cos\theta)$, and the solution of the wave equation is set up so that the four solutions of the ionospheric layers where $\sigma > \omega\epsilon_0$ degenerate into two solutions for the lower ionospheric layers where $\sigma << \omega\epsilon_0$ and for free space. After computing the surface impedance at the lower boundary of the ionosphere, the propagation parameters are determined from the solutions of the modal equation for TM modes, althought the coupling between TE and TM modes is considered in the processes of computing the surface impedance. Only the vertically polarized TM modes are assumed to propagate below the ionosphere. Such assumptions have been justified for a single layer ionosphere model at higher frequencies [Wait 1962, p. 269] and for a thin ionospheric shell also for frequencies in the resonance range [Wait, 1964c].

In the numerical calculations the anisotropic ionosphere models are those of figure 4 and further calculations are made for ionosphere models which consider electrons and ions at an operating frequency of 20 c/s, as indicated in figures 3 and 4 of Galejs [1964b]. In the isotropic ionosphere models σ_0 remains unaltered, $\sigma_1=\sigma_0$, and $\sigma_2\rightarrow 0$. The calculated resonance frequencies f_n are listed in table III. The isotropic day or night models exhibit too high resonance frequencies, but the average for the anisotropic day or night models gives nearly correct results, although the first resonance occurs near 7.7 c/s. At night the various anisotropic models give different results, while their results are nearly the same for daytime or for the isotropic models. The calculated Q factors are listed in table IV. At daytime the Q factors are lowered slightly due to anisotropy. The losses are principally due to absorption in the lower D region where the collision frequencies are high and the magnetic field has only small effects. At nighttime the anisotropy reduces the Q values drastically, and the ions have a considerable effect. For the isotropic models the energy remains below the ionosphere, the losses in the lower ionosphere are small and the Q values are high. For the anisotropic models some energy penetrates the ionosphere and escapes from the earth to ionosphere cavity. Hence the Q figure is low.

TABLE III

RESONANCE FREQUENCIES OF THE SPHERICAL SHELL BETWEEN THE EARTH AND IONOSPHERE IN THE PRESENCE OF A RADIAL MAGNETIC FIELD

	IONOSPHERE MODEL	n	1	2	3	4
RESONANCE FREQUENCY f_n IN C/S	DAY, ANISOTROPIC		7.8	13.8	19.8	26
	DAY, ISOTROPIC		8.1	14.2	20.4	26.6
	NIGHT, ANISOTROPIC	EL.+ IONS F = 20	7.6	15.2	23.2	29.5
		EL.+ IONS F = 0	7.7	13.8	20.1	26.9
		EL. ONLY F = 0	7.8	14.1	20.7	27.8
	NIGHT, ISOTROPIC		8.6	15.3	21.3	27.4
	MEASUREMENTS		8	14.1	20.3	26.4

TABLE IV

Q-FACTORS OF EARTH-IONOSPHERE CAVITY RESONANCES IN THE PRESENCE OF A RADIAL MAGNETIC FIELD

	IONOSPHERE MODEL	F	10	30
Q-FACTORS	DAY, ANISOTROPIC		6.8	5.6
	DAY, ISOTROPIC		8.3	7
	NIGHT, ANISOTROPIC	EL. + IONS F = 20	1.7	6.6
		EL. + IONS F = 0	2.0	2.7
		EL. ONLY F = 0	2.8	4.5
	NIGHT, ISOTROPIC		8.8	9.3
	MEASUREMENTS		4	6

The previous calculations have assumed a constant radial magnetic field (S pole) all over the globe. A reversal of the static magnetic field (N pole) causes negligible differences in the propagation parameters or in the values of f_n and Q. Hence a model using the average of the radial magnetic field may provide a first order estimate of the anisotropy effects. The present calculations assume the radial magnetic of the polar regions to be extended over the whole surface of the globe and the anisotropy effects should be too pronounced. The analytical results are highly dependent on the detailed structure of the nighttime anisotropic ionosphere, and further studies of it may be in order.

4. Source Distributions and Noise Spectra

Most of the ELF energy is of terrestrial origin and is caused by thunderstorm activity, although there are some high latitude events of an apparent extraterrestrial origin. Such emissions of approximately 800 c/s have been detected near Kiruna, Sweden [Egeland, 1964] and of 14 to 17 c/s on Kerguelen Island in the Southern part of the Indian Ocean [Gendrin and Stephant, 1964, private communication]. The Spectran recording of the signals received at Kerguelen is shown in figure 6. The upper trace shows a normal signal with resonances near 8, 14, 20, and 25 c/s. There is an additional signal of 14 to 17 c/s on the two lower traces. When neglecting the presence of such extraneous signals the terrestrial noise spectra can be calculated after estimating the dipole moments of the sources and using propagation parameters that are appropriate to the selected ionosphere model.



FIGURE 6. *Spectran recordings of noise waveforms at Kerguelen Island.*



FIGURE 7. *Estimated lighting flash spectrum.*

Raemer [1961a, b] has estimated the power spectrum of the dipole moment in a median lightning flash Ids (or the first derivative of the electrostatic moment dM/dt) based on statistics of lightning strokes compiled by Williams [1959]. Later work of Raemer [1963 private communication] has lead to a revised estimate. These spectra are shown in figure 7. Pierce [1963] has computed the magnitude of the frequency spectra of the second derivative d^2M/dt^2, and Rycroft [1963] has calculated the frequency spectra of dM/dt using a similar representation of the lightning moments. The square of the frequency spectrum computed by Rycroft [1963] is also indicated in figure 7.

An equivalent power spectrum for the dipole moment of terrestrial noise sources has been deduced by Harris and Tanner [1962] from the measurements of Balser and Wagner [1960] by estimating the complex propagation constant within this frequency range in a "trial and error" approach. Harris and Tanner [1962] do not require an ionosphere model or any knowledge of lightning waveforms and their statistics for obtaining this equivalent power spectrum.

After determining the source spectra and the propagation parameters the power spectrum of the received noise may be computed from

$$G(i\omega)=\frac{g(i\omega)\,|\nu(\nu+1)|^2}{8(ak_0h)^2\,|\nu+\frac{1}{2}|\,[\cosh(2\pi\,\mathrm{Im}\,\nu)-\cos(2\pi\,\mathrm{Re}\,\nu)]}\cdot\left\{\frac{\sinh[2\,\mathrm{Im}\,\nu\,(\pi-\theta)]}{(-\mathrm{Im}\,\nu)}-\frac{\sin[(2\,\mathrm{Re}\,\nu+1)(\pi-\theta)-(\pi/2)]}{\mathrm{Re}\,\nu+\frac{1}{2}}\right\}_{\theta_1}^{\theta_2}, \quad (9)$$

where the ν is given by (2) and where the sources are assumed to be uniformly distributed in the θ interval of $\theta_1<\theta<\theta_2$. The derivation of (9) starts from (1) and Legendre functions $P_\nu(-\cos\theta)$ are replaced by an asymptotic expansion. There are also equivalent spectral representations in terms of Legendre polynomials [Raemer, 1961a, b].



FIGURE 8. *ELF Noise spectrum—effective ionospheric height assumed constant.*



FIGURE 10. *Noise spectrum for 47° ≤ θ ≤ 128°.*



FIGURE 9. *Noise spectrum for 38° ≤ θ ≤ 72°.*



FIGURE 11. *Diurnal variation of the resonance modes at Ipswich, Mass., February 1961 (vertical electric field), Chambon-la-Foret (near Paris) July 1962 and at Tromso (Norway) April 1962 (horizontal magnetic field).*

The noise spectrum of Raemer [1961b] has been used for computing the observed noise spectra in conjunction with a sharply bounded ionosphere model. This spectrum is shown in figure 8 and is seen to exhibit excessively damped higher resonance peaks.

The exponential ionosphere model [Galejs, 1961b, 1962a, 1964a] produces a better agreement with measurements as seen in figures 9 and 10. In this work propagation is assumed to be uniform around the surface of the earth and the propagation parameters represent the average of day and night conditions. The sources are assumed to be uniformly distributed over the θ interval indicated in the figures (θ is defined with respect to the observer).

5. Diurnal and Seasonal Changes of Power Spectra

Balser and Wagner [1962a] have recorded diurnal variations of measured noise spectra. Their measurements of the diurnal variations of the power level at the first three resonance frequencies are shown in figure 11 together with similar measurements by Gendrin and Stefant [1962a]. Diurnal variations of the fields near the two lower resonance frequencies have been measured at Kingston, R.I., by Polk, Huck, and Yu [1963, private communication]. The maximum signal intensity occurs between 1500 and 1800 UT. In an amplitude versus time plot the signal peak is broader during summer than winter. Seasonal and diurnal variations of the noise power in the ELF frequency band below 35 c/s have been described by Wright [1963] without singling out the individual resonance modes. The measurements are made at Byrd Station, Antarctica (80°S, 120°W) and show peak intensities near 1000 UT during spring and summer and near 2300 UT during most of the year.

The gross features of the spectrum, such as the number of peaks and their approximate time of occurance, may be explained qualitatively by noting areas of globe with particularly high thunderstorm activity and by measuring the polar angle θ from these source regions to the observation point. The vertical electric field E_r and the horizontal magnetic field H_ϕ of the mode n exhibit the θ dependence of

$$E_r \sim P_n(\cos\theta) \tag{10}$$

$$H_\phi \sim \frac{d}{d\theta} P_n(\cos\theta), \tag{11}$$

where $P_n(\cos\theta)$ is a Legendre polynomial of the order n. A particular geographical region will contribute to the measured values of E_r or H_ϕ in the mode n if the right hand sides of (10) or (11) are sizeable for those values of θ. Such considerations have been reported by Balser and Wagner [1962a] and Gendrin and Stefant [1962a].

More detailed calculations have been carried out by Abraham [1964, private communication; Galejs 1964a] who used available estimates of geographical distributions of the noise sources and who calculated the day and night propagation effects after expressing the fields as a sum of recirculating azimuthal waves.

In the expression for the electric field component E_r of (1), the Legendre function is replaced by the leading term of its asymptotic expansion. The function $\sin \nu\pi$ is expanded into

$$(\sin \nu\pi)^{-1} = -2i \sum_{n=0}^{\infty} e^{i(2n+1)\nu\pi} \tag{12}$$

which is valid for Im $\nu > 0$. This results in [Abraham, 1964, private communication]

$$E_r = \frac{Ids}{2\omega\epsilon h a^2} \frac{\nu(\nu+1)}{\sqrt{2\pi(\nu+\frac{1}{2})\sin\theta}} e^{i\frac{3\pi}{4}}$$

$$\sum_{n=0}^{\infty} \left\{ e^{i(\nu+\frac{1}{2})(\theta+2n\pi)-i2n\frac{\pi}{2}} + e^{i(\nu+\frac{1}{2})[2\pi(n+1)-\theta]-i(2n+1)\frac{\pi}{2}} \right\}. \tag{13}$$

The first term of the summation represents a wave which has traveled the direct distance from the source to the observation point (θ) plus n full circles around the sphere ($2n\pi$), while experiencing a phase shift of ($-\pi/2$) radians at each traversal of the source point or its antipode. The other term of the summation represents a wave which has traveled toward the observation point across the antipode of the source ($2\pi-\theta$) and has made furthermore n circles around the sphere ($2n\pi$) and has also experienced a phase shift of ($-\pi/2$) radians at each traversal of the source point or its antipode. This physical interpretation of (13), which is equivalent to (1) for $\nu=$const., permits a heuristic consideration of the ν differences between the day and night hemispheres. The multiplicative ν factors in front of the n summation are assumed to be constant and equal to $\overline{\nu}$ which is intermediate between the day and night ν values. The θ factors of the exponentials are replaced by integrals in order to account for the ν variation seen by the circular wave front as it propagates in the θ-direction with respect to the source. The amplitude changes at the day and night boundary can be also considered for each traveling wave by assuming that the energy of the wave remains constant after passing the day and night boundary. This results in decreased amplitudes for the larger ionospheric height of the night hemisphere. In the numerical work the surface of the earth was subdivided into 10° cells. Each cell had a constant surface density of noise sources but a variation was allowed from cell to cell. The plots of thunderstorm days over the world were used to set relative values of lightning activity for each of the cells, by assuming that the distribution of squared dipole moment per unit area is directly proportional to the thunderstorm day plots according to the Handbook of Geophysics [1960]. The diurnal variations were accounted for by a multiplicative factor in terms of local time at the source [Williams, 1959]. The final equation used in the spectrum calculations is similar to (9), although it is algebraically more involved [Abraham, 1964, private communication].

The diurnal variations of the noise power at the first three Schumann resonances have been computed using the exponential ionosphere model of figure 5 and are shown in figure 12. The calculations have disregarded the noise sources near the antipode where the usual asymptotic approximation of the Legendre functions is inaccurate. Figure 12 shows a qualitative agreement with the measurements of Balser and Wagner [1962a], that are shown in figure 11.

An example of seasonal power variations is shown in figure 13. It indicates a decreased noise power near the higher frequencies and/or during winter months.

Based on measurements at one location of the earth it is also possible to predict the noise levels at other locations using this procedure of noise spectrum calculations. The noise that is due to a worldwide distribution of thunderstorms depends on the frequency variation and also on the absolute value of the power spectrum of the mean dipole moment of the source $g(i\omega, \theta, \phi)$. The θ and ϕ dependence may be estimated from the thunderstorm frequency maps as was indicated before, which leaves the absolute value and the frequency dependence of $g(i\omega)$ as an unknown. Assuming that $g(i\omega)$ is the same for all noise sources, it may be determined by making the calculations to agree with measurements at one particular location. This gives a uniquely determined noise distribution over the surface of the earth and the accuracy of this model can be checked by com-



FIGURE 12. *Calculated diurnal variation of noise power at the peak of the resonance modes—wintertime—Boston, Mass.*



FIGURE 13. *Calculated noise spectrum for local noon in northern hemisphere.*



FIGURE 14. *Comparison of calculated field strength's data with July 1963 measurements by DECO and RCA.*

paring the calculations with measurements at other locations. In an example, measurements by DECO at Boulder, Colo., [Maxwell, 1963, private communication] and by RCA at Long Island, N.Y. [Powers, 1964, private communication], were used to determine $g(i\omega)$. The calculations by Abraham [1964, private communication] based on these values of $g(i\omega)$ have been compared with simultaneous measurements made in Malta and Alaska [Maxwell, 1963, private communication]. As seen from figure 14 the analytic curves agree in shape with the measurements, but the normalization with respect to Boulder gives somewhat higher predictions of the noise level. This may possibly be caused by summertime thunderstorm activity in the mountains near Boulder, Colo., that would give significant near-fields and a high estimate for the function $g(i\omega)$. The calculations are extended above the region of the earth-ionosphere cavity resonances to show that more significant noise level changes occur at higher frequencies.

In the calculations leading to figures 12 through 14 the day and night effects are considered most accurately if the day and night boundary is located symmetrically with respect to source (i.e., source at local noon or midnight). For nonsymmetrical day and night boundaries it is difficult to estimate the effects of wave front distortion. When neglecting such distortions (or assuming propagation strictly in the θ-direction), this method can account for $\nu(\theta)$ variations, which may be caused by ionosphere parameter changes or by changes of the static magnetic field along the surface of the earth. The assymptotic expansions of $P_\nu(-\cos\theta)$ used in (13) or (9) can be modified to increase their accuracy for observations near the source or its antipode [Abraham, 1965].

6. Variations of Resonance Frequencies

Diurnal frequency variations of the earth-ionosphere cavity modes have been reported by Balser and Wagner

[1962b], Gendrin and Stefant [1963], Rycroft [1963] and by Chapman and Jones [1964b]. The resonance frequencies vary by about ±0.2 to 0.3 c/s, but the changes are not simultaneous for the different modes; a low resonance frequency of one mode occurs simultaneously with a high frequency of a different mode.



FIGURE 15. *Diurnal frequency variations measured by Gendrin and Stefant.*



FIGURE 16. *Diurnal frequency variations measured by Rycroft.*



FIGURE 17. *Nuclear effects on earth-ionosphere cavity resonances.* Measurements by Gendrin and Stefant.

A high altitude nuclear explosion has been shown to affect the earth-to-ionosphere cavity resonances by simultaneously lowering all the resonance frequencies [Gendrin and Stefant, 1962a and b; Balser and Wagner, 1963]. Tepley et al., [1963] noted also an increase of signal strength for observations near the conjugate point of the explosion. The lowering of resonance frequency shown in figure 17 has been attributed to worldwide lowering of the effective ionosphere in a model of a single layer isotropic ionosphere [Gendrin and Stefant, 1962b]. The depression of the resonance frequency can be also explained by assuming an exponential daytime ionosphere to be effective around the globe [Row, 1964, private communication]. As an illustration the daytime resonance frequencies of table 1 compare with the measured resonance frequencies of figure 17. There are VLF observations [Zmuda et al, 1963] that can be explained by a lowering (or increasing electron density) of the *D*-region boundary. Brady et al., [1964] interpreted VLF diurnal phase shifts to show that some enhanced *D*-region ionization persists for several days following the event.

The lowering of the resonance frequency following a nuclear explosion has been attributed by Chapman and Jones [1964a] in their two-layer ionosphere model solely to a decreasing conductivity of the *E*-region.

After measuring a change of the resonance frequencies following a nuclear explosion, it is possible to advance simple ionosphere models for explaining a particular change. However, no attempt has been reported to predict resonance shifts for different nuclear yields and detonation altitudes. This rather complex problem requires a quantitative evaluation of the various nuclear mechanisms that may lead to ionosphere perturbations. If such information is available, the computation of the resonance shifts is relatively simple. It would be also of interest to investigate the effects of sudden ionosphere disturbances (SID) and to discriminate between SID's and nuclear effects.

The resonant frequency changes can be considered more accurately with nonuniform models of the propagation geometry. A perturbation method [Wait, 1964b] or numerical techniques [Madden and Thompson, 1964] have been used for solving such problems.

Madden and Thompson [1964] compute the local surface impedance and propagation constant for a uniform cylindrical shell between the anisotropic ionosphere and the earth using matrix multiplication techniques. There is a smooth variation of the parameters between polar and equatorial regions and also between day and night hemispheres. These local surface impedances and propagation constants are assumed to characterize a spherical transmission line of nonuniform parameters. The resonance frequencies and Q factors are computed numerically using a lumped parameter approximation of the two-dimensional transmission line. This model has been applied to explain the diurnal frequency variations and also the frequency changes due to a nuclear explosion.

7. Areas of Future Work

There are numerous observations of earth-ionosphere cavity resonances and existing ionosphere and source models account for most observed characteristics like the resonance frequency, Q factors, shape of the noise spectra, and diurnal variations of the received power.

Future work appears to be required in a systematic study of diurnal and seasonal amplitude and frequency variations of resonances. These changes should also be correlated with ionospheric disturbances. The parameters of the nighttime ionosphere require also a future clarification. The variations of the ionosphere parameters and the variations of the magnetic field vector along the surface of the earth should be incorporated in future calculations [Wait, 1964b; Madden and Thompson, 1964]. Much work remains to be done for assessing nuclear effects on the earth ionosphere resonance and for discriminating between lower level nuclear and sudden ionospheric disturbances.

The work of Sylvania reported in this paper has been supported principally by the Office of Naval Research under Contract Nonr 3185(00).

8. Appendix. Q Factors

The basic definition of the Q factor of a cavity with lossy walls is

$$\frac{1}{Q_i}=\frac{\int\int \mathbf{E}\times\mathbf{H}^*\cdot\mathbf{ds}}{\frac{\omega\epsilon_0}{2}\int\int\int \mathbf{E}\cdot\mathbf{E}^*dv+\frac{\omega\mu_0}{2}\int\int\int \mathbf{H}\cdot\mathbf{H}^*dv} \tag{14}$$

where the surface integral is extended over the cavity walls and the volume integral covers the inside of the cavity. The ground surface is assumed to be a perfect conductor and E_θ is related to H_ϕ at the ionospheric boundary by the surface impedance Z_s as $E_\theta=Z_sH_\phi$. However E_θ is assumed to be small relative to E_r for vertically polarized waves. Equation (14) is rewritten as

$$\frac{1}{Q_i}=\frac{2\int\int \mathrm{Re}Z_s|H_\phi|^2(a+h)^2\sin\theta d\theta d\phi}{\omega\int\int\int[\epsilon_0|E_r|^2+\mu_0|H_\phi|^2]r^2dr\sin\theta d\theta d\phi} \tag{15}$$

$$\approx\frac{2\mathrm{Re}Z_s}{\omega h}\,\frac{\int|H_\phi|^2\sin\theta d\theta}{\int[\epsilon_0|E_r|^2+\mu_0|H_\phi|^2]\sin\theta d\theta} \tag{16}$$

where a is the radius of earth, h is the ionospheric height and where the cavity is assumed to be uniform. For excitation by a radial electric dipole of moment Idr the field component E_r and H_ϕ follow from (21), (61), and (62) of Galejs [1964a] as

$$E_r=\frac{iIdr}{4\pi h\omega\epsilon a^2}\,\frac{n(n+1)(2n+1)}{D_n}\,P_n(\cos\theta) \tag{17}$$

$$H_\phi=-\frac{Idr}{4\pi ha}\,\frac{(2n+1)}{D_n}\,\frac{\partial}{\partial\theta}P_n(\cos\theta) \tag{18}$$

with $D_n=n(n+1)-\nu(\nu+1)$. Substituting (17) and (18) in (16) and evaluating the integrals gives

$$\frac{1}{Q_i}=\frac{2\mathrm{Re}Z_s}{\omega\mu_o h\left[\frac{n(n+1)}{(k_0a)^2}+1\right]} \tag{19}$$

where $k_0=\omega\sqrt{\mu_0\epsilon_0}$. From the approximate modal equation

$$S=\sqrt{1+\frac{iZ_s}{\omega\mu_0h}} \tag{20}$$

it follows that

$$2\ \mathrm{Re}S\ \mathrm{Im}S=\frac{\mathrm{Re}Z_s}{\omega\mu_0h}\cdot \tag{21}$$

Applying (21) and the resonance condition

$$n(n+1)\approx(k_0a\ \mathrm{Re}S)^2 \tag{22}$$

(19) simplifies to

$$\frac{1}{Q_i}=\frac{4\ \mathrm{Re}S\ \mathrm{Im}S}{(\mathrm{Re}S)^2+1} \tag{23}$$

which was listed as (4). When considering the differences of E_r, H_ϕ, Z_s, and h between the day and night hemispheres it follows that

$$\frac{1}{Q_i} \approx \frac{2[\mathrm{Re}S\ \mathrm{Im}S|_{\mathrm{day}} + \mathrm{Re}S\ \mathrm{Im}S|_{\mathrm{night}}]}{(\mathrm{Re}S|_{\mathrm{avg}})^2 + 1}. \qquad (24)$$

The form (5) or (6) is obtained by neglecting the E integral or H integral, and by doubling the value of the H integral or E integral in (14).

9. References

Abraham, L. G. Jr., Aspects of the terrestrial ELF noise spectrum when near the source or its antipode, Radio Sci., J. Res. NBS **69D** (July 1965).

Balser, M., and C. A. Wagner (Nov. 1960), Observations of earth-ionosphere cavity resonances, Nature **188,** 638–641.

Balser, M., and C. A. Wagner (Feb. 1962a), Diurnal power variations of the earth-ionosphere cavity modes and their relationship to worldwide thunderstorm activity, J. Geophys. Res. **67,** No. 2, 619–625.

Balser, M., and C. A. Wagner (Sept. 1962b), On frequency variations of the earth-ionosphere cavity modes, J. Geophys. Res. **67,** No. 10, 4081–4083.

Balser, M., and C. A. Wagner (July 1, 1963), Effect of a high-altitude nuclear detonation on the earth-ionosphere cavity, J. Geophys. Res. **68,** No. 13, 4115–4118.

Benoit, R., and A. Houri (1961), Propagation of very-low-frequencies in the earth-ionosphere system, Ann. Geophys. (France) **17,** No. 4, 370–373.

Benoit, R., and A. Houri (Nov. 5, 1962), Power spectrum measurements of geophysical noise. Application to earth-to-ionosphere cavity, C. R. Acad. Sci. (France) **255,** 2496–2498.

Bourdeau, R. E., E. C. Whipple, and J. F. Clark (Oct. 1959), Analytic and Experimental Conductivity between the stratosphere and the ionosphere, J. Geophys. Res. **64,** 1363–1370.

Brady, A. H., D. D. Crombie, A. G. Jean, A. C. Murphy, and F. K. Stede (May 1, 1964), Long-lived effects in the D region after the high altitude nuclear explosion of 9 July 1962, J. Geophys. Res. **69,** 1921.

Brock-Nannestad, L. (Sept. 1962), Bibliography electromagnetic phenomena with special reference to ELF (1–3000 c/s) TR 10 Saclant, ASW Research Center, La Spezia, Italia.

Chapman, F. W., and D. L. Jones (May 16, 1964a), Earth-ionosphere cavity resonances and the propagation of extremely low frequency radio waves, Nature **202,** 654–657.

Chapman, F. W. and D. L. Jones, Observations of earth-ionosphere cavity resonances and their interpretation in terms of a two-layer ionosphere model, Radio Sci., J. Res. NBS **68D,** 1177–1185 (Nov. 1964b).

Chapman, F. W., and R. C. Macario (May 1956), Propagation of audio frequency radio waves to great distances, Nature **177,** 930–933.

Egeland, A. (1964a) ELF (500–1000 c/s) emissions at high latitude, Proc. NATO Advanced Study Institute on Natural Electromagnetic Phenomena Below 30 kc/s, Bad Homburg, West Germany, July–Aug. 1963, pp. 157–166 (Plenum Press, New York, N.Y.).

Fournier, H. (Aug. 17, 1960), Some aspects of the first high-frequency geomagnetic recordings obtained at Garchy, C. R. Acad. Sci. (France) **251,** No. 7, 962–964.

Galejs, J. (1961a), Terrestrial extremely-low-frequency noise spectrum in the presence of exponential ionospheric conductivity profiles, J. Geophys. Res. **66,** No. 9, 2787–2792.

Galejs, J. (Nov. 1961b), ELF waves in presence of exponential ionospheric conductivity profiles, IRE Trans. Ant. Prop. **AP-9,** 554–562.

Galejs, J. (July 1962a), A further note on terrestrial extremely-low frequency propagation in the presence of an isotropic ionosphere with an exponential conductivity-height profile, J. Geophys. Res. **67,** No. 7, 2715–2728.

Galejs, J. (1962b), Terrestrial extremely-low frequency propagation in the presence of an isotropic ionosphere with an exponential conductivity height profile, Proc. International Conference on the Ionosphere, London, pp. 467–474 (Chapman and Hall).

Galejs, J. (1964a), Terrestrial extremely-low frequency propagation, Proc. NATO Advanced Study Institute on Natural Electromagnetic Phenomena Below 30 kc/s, Bad Homburg, West Germany, July–Aug. 1963, pp. 205–258 (Plenum Press, New York, N.Y.).

Galejs, J. (June 1964b), ELF and VLF waves below an inhomogeneous anisotropic ionosphere, Radio Sci. J. Res. NBS **68D,** No. 6, 693–707.

Galejs, J., and R. V. Row (Jan. 1964), Propagation of ELF waves below an inhomogeneous anisotropic ionosphere, IEEE Trans. Ant. Prop. **AP-12,** No. 1, 74–83.

Galejs, J., On the terrestrial propagation of ELF and VLF waves in the presence of a radial magnetic field, Radio Sci., J. Res. NBS **69D,** No. 5 (May 1965).

Gendrin, R., and R. Stefant (Sept. 1962a), Magnetic records between 0.2 and 30 c/s, AGARD Conference on Propagation of Radio Frequencies Below 300 kc/s, Munich, Germany.

Gendrin, R., and R. Stefant (1962b), Effects of the very high altitude nuclear explosion of the July 9, 1962 on the earth to ionosphere cavity resonances, experimental results and interpretation, C. R. Acad. Sci. **255,** 2273–2275 and 2493–2495.

Handbook of Geophysics (1960), USAF Air Research and Development Command, Airforce Cambridge Research Center (Macmillan Co., New York, N.Y.).

Harris, F. B., Jr., and R. L. Tanner (1962), A method for determination of lower ionosphere properties by means of field measurements on sferics, J. Res. NBS **66D** (Radio Prop.), No. 4, 463–478.

Hepburn, F., and E. T. Pierce (May 9, 1953), Atmospherics with very-low-frequency components, Nature (GB) **171,** 837–838.

Jean, A. G., Jr., and A. C. Murphys, J. R. Wait, and D. F. Wasmundt (1961), Propagation attenuation rates at ELF, J. Res NBS **65D** (Radio Prop.), No. 5, 475–479.

Keefe, T. J., C. Polk, and H. L. Koenig (1964), Results of simultaneous ELF measurements at Brannenburg (Germany) and Kingston, R.I., ULF Symposium, Boulder, Colo. Aug. 17–20, 1964.

Koenig, H. (Dec. 1958), Atmospherics geringster frequenzen, Dissertation an der Technischen Hochschule München.

Koenig, H. (July 1959), Atmospherics geringster frequenzen, Z. Angew. Phys. **11,** No. 7, 264–274.

Koenig, H., E. Haine, and C. H. Antoniadis (Aug. 1961), Messung von 'atmospherics' geringster frequenzen in Bonn, Z. Angew. Phys. **13,** No. 8, 364–367.

Liebermann, L. (Dec. 1956a), Extremely-low-frequency electromagnetic waves: I. Reception from lightning, J. Appl. Phys. **27,** No. 12, 1473–1476.

Liebermann, L. (Dec. 1956b), Extremely-low-frequency electromagnetic waves: II. Propagation properties, J. Appl. Phys. **27,** No. 12, 1477–1483.

Lokken, J. E., J. A. Schand, and C. S. Wright (1962), A note on the classification of geomagnetic signals below 30 c/s, Can. J. Phys. **40,** 1000–1009.

Madden, T. R. (1961), An analysis of the earth-ionosphere electromagnetic resonances, unpublished class notes for MIT course 12.88, April 24.

Madden, T. Rand, W. Thompson, Low-frequency electromagnetic oscillations of the earth-ionosphere cavity, Report on Project NRL 371–401, Geophysics Laboratory, MIT, Cambridge, Mass. (Sept. 22, 1964). Also Rev. Geophys. **3,** No. 2 (May 1965).

Pierce, E. T. (July–Aug. 1960), Some ELF phenomena, J. Res. NBS **64D** (Radio Prop.), No. 4, 383–386.

Pierce, E. T. (July 1, 1963), Excitation of earth-ionosphere cavity resonances by lightning flashes, J. Geophys. Res. **68,** No. 13, 4125–4127.

Polk, C., and F. Fitchen (May–June 1962), Schumann resonances of the earth-ionosphere cavity—extremely low frequency reception at Kingston, R.I., J. Res. NBS **66D** (Radio Prop.), No. 3, 313–318.

Polk, C. (1962), ELF propagation and the earth-ionosphere resonant cavity, paper presented at the meeting of the Ionospheric Research Committee of AGARD in Munich, West Germany, Sept. 17–21, 1962.

Raemer, H. R. (1961a), On the extremely-low-frequency spectrum of earth-ionosphere cavity response to electric storms, J. Geophys. Res. **66,** No. 5, 1580–1583.

Raemer, H. R. (Nov.–Dec. 1961b), On the spectrum of terrestrial radio noise at extremely low frequencies, J. Res. NBS **65D** (Radio Prop.), No. 6, 581–594.

Rycroft, M. J. (Dec. 1963), Low frequency disturbances of natural origin of the electric and magnetic fields of the earth, Ph.D. Thesis, University of Cambridge.

Schumann, W. O. (1952a), Über die strahlungslosen Eigenschwingungen einer leitenden Kugel, die von einer Luftschicht und einer Ionosphärenhülle umgeben ist, Z. Naturforsch, **72,** 149–154.

Schumann, W. O. (1952b), Über die Dämpfung der elektromagnetischen Eigenschwingungen des Systems Erde-Luft-Ionosphäre, Z. Naturforsch **72,** 250–252.

Schumann, W. O. (Aug. 1957), Elektrische Eigenschwingungen des Hohlraumes Erde-Luft-Ionosphäre, Z. Angew. Phys. **9,** 373–378.

Seshadri, S. R., Radiation from electromagnetic sources in a plasma, IEEE Transactions on Antennas and Prop. **AP–13,** No. 1, 79–88 (Jan. 1965a).

Seshadri, S. R. (March 1965b), VLF propagation in a sharply bounded, compressible isotropic ionosphere, IEEE Trans. Ant. Prop. **AP–13,** No. 2, 311–317.

Tepley, L. R. (Dec. 1959), A comparison of sferics as observed in the very-low-frequency and extremely-low-frequency bands, J. Geophys. Res. **64,** No. 12, 2315–2329.

Tepley, L., R. C. Wentworth, K. G. Lambert, H. V. Prentiss, K. D. Amundsen and D. R. Hillendahl (26 Dec. 1963), Sub ELF geomagnetic fluctuations, III final report Contract AF 19(628)–462, Lockheed Missile and Space Co., Palo Alto, Calif.

Thompson, W. B. (Feb. 1963), A layered model approach to the earth-ionosphere cavity resonance problem, Ph.D. Thesis, Department of Geology and Geophysics, MIT.

VanZandt, T. E. (1964), Ionosphere, ULF Symposium, Boulder, Colo., Aug. 17–20.

Wait, J. R. (March 1958), Extension to mode theory of VLF propagation, J. Geophys. Res. **63,** 125–135.

Wait, J. R. (1962), Electromagnetic waves in stratified media (Macmillan Co., New York, N.Y.).

Wait, J. R. (Feb. 1963a), The mode theory of VLF radio propagation for a spherical earth and a concentric anisotropic ionosphere, Can. J. Phys. **41,** 299–315.

Wait, J. R. (May–June 1963b), Concerning solutions of the VLF mode problem for an anisotropic curved ionosphere, J. Res. NBS **67D** (Radio Prop.), No. 3, 297–302.

Wait, J. R. (April 1964a), On the theory of Schumann resonances in the earth-ionosphere cavity, Can. J. Phys. **42,** 575–582.

Wait, J. R. (1964b), Earth-ionosphere cavity resonances and the propagation of ELF radio waves, ULF Symposium, Boulder, Colo., Aug. 17–20. Also Radio Sci. J. NBS **69D,** No. 8.

Wait, J. R. (1964c), Cavity resonances for a spherical earth with a concentric anisotropic shell (private communication).

Wait, J. R. (1964d), A note on the Schumann problem for nonuniform boundaries (private communication).

Williams, J. C. (May 1959), Thunderstorms and VLF radio noise, Ph.D. Thesis, Harvard University, Division of Engineering and Applied Physics.

C. S. Wright (July–Aug. 1963), Conjugate relations of micropulsations and other ionospheric phenomena, NATO Advanced Study Institute on Natural Electromagnetic Phenomena Below 30 kc/s, Bad Homburg, Germany.

Zmuda, A. J., B. W. Shaw, and C. R. Haave (Feb. 1, 1963), VLF disturbances and the high-altitude nuclear explosion of July 9, 1962, J. Geophys. Res. **68,** No. 3, 745–758.

(Paper 69D8–538)

rexresearch.com

Jules GUILLOT

Atmospheric Electric Generator

FLUKE CONNECT
Capture equipment performance.
FLUKE
Learn more


Over-The-Air Television Made Wireless for Devices
ANTENNAS DIRECT
CLEARSTREAM TV
STREAMING SMARTPHONE TABLET TV
SHOP NOW

SPOT HERO
Tired of paying for parking tickets?
Book Now



Shared by L. Cozma (Thanks !) --

The Guillot device generated about 2.5-3 Kilowatts with antenna height of ~ 20 meters. Power depends on the total collector surface and height of the vertical antenna. The apparatus in the photo produced ~300 watts with a collector 2 meters tall.

"Practical Utilization of Atmospheric Electricity"

by

Gillbert Darida

in *The Invention Encyclopedia,* pp. 204-207 (1930, Geo. Constantinescu, Ed.)

"The Earth has its own negative electricity, in the soil, and the atmosphere which surrounds the Earth is charged with positive electricity. The electric potential (the voltage) increases with the altitude, so we can say that the electric force is proportional to the atmospheric altitude (after Franklin, Quetelet, Lord Kelvin, Mascart, Joubert and other scientists).

The recent observations demonstrate that the air at 6000-7000 meters in altitude, is very highly charged with positive electricity, which could be explained by the friction between the external photosphere and the upper atmosphere of Earth, which rotates at a speed of more than 100,000 Kilometer per hour.

In that way, the Earth works like an electrostatic generator with electric charging by influence --- the upper atmosphere is positively charged by influence and the Earth crust obtains the negative polarity.

Between the two environments, the air and the soil, and inside the low atmosphere, in conditions of good weather, there are sbout 800 positive ions and also, 680 negative ion (and electrons) in just one square-centimeter of normal ionised air.

The Earth behaves like an huge electric armature negatively charged, which repels the electrons and attracts the positive ions. That positive ions' attraction determinates an electric current, also called "convective current". That's like an invisible continous bombardment, subject to daily and seasonal variations, which could be aproximated at **3 x 10 ^ -16 Amperes per square-centimeter,** and that is a total value of 1500 Amperes for the entire surface of the Earth.
The question is --- how does this current always maintains the same direction ? We can suppose that the natural radioactive emissions of the soil is responsable for this. We also know that radioactive emissions of the Earth works usually near the soil surface, and that explains the ionisation phenomenona inside caves.

The ionisation of the low atmosphere could also be the effect of the radioactive emissions of the Earth, especially when the X radiation works. Also, the Earth atmosphere is ionisated by the external radiation proceeding from the Sun and from the space environment, especially the action of ultraviolet radiation and the electron fascicles emitted by the Sun surface, at the temperature of 6000 deg. Celsius.

The capture of atmosphere electricity has been used in France, with aerial cables mounted on the Mont Blanc, and also in Germany --- with conductive cables carried by the captive baloons.

The atmosphere electricity collect system invented by eng. Jules Guillot is most ingenious and it relies on "the **electric siphon**" [*m.n. --- the discharging devices or spark-gap used today from the protection of aerial electric cables against the atmospheric electricity ; Jules Guillot has thought to recuperate and to use that electricity*].

His method consisted in the direct "pumping" of the atmosphere electricity using a collecting device which had two antennae and several collecting rods.

One antenna is **vertical** and it has a lot of **rods** scattered like an opened **fan**, with the tips against the **zenith**, for collecting the **negative** electricity which comes from the air ; the **horizontal** antenna is orientated against the **South** and its role is to collect the **positive** electricity.

The air electricity seems to have the double-polarity, as we can see at two electrised clouds when between them apears the electric discharge. The air could have different electric charging and the ionisation processus of atmosphere is very heterogenous. The inventor Guillot used **two separated and insulated armatures with the positive armature against the South** (more precisely, against the **Equator**...) and the **negative** armature against the **zenith**.

We can see in the scheme :

1,- the device P is the "**collector apparatus**" having **15-20 meters height** ; it also has a lot of **rods** which are scattered **fan**-like, all this on top of an **iron pillar** ; and also an **horizontal antenna** S oriented against the **South** ; the two antennae are disposed at **90 deg. angle** forming the two armatures where the electrical tension must apear. As the **height** of the pillar **increases**, the **voltage** increases more and more ;

2,- a system of **lightning-rods** (p1, p2, p3) for protection against discharges of atmospheric electricity during storms;

3,- the regulator system (**voltage regulator**, etc) R ;

4,- the electric **resistors** (Cn) for absorbing the parasite currents ;

5,- the "electric siphons" which have the role of making a magnetic field as a good environment for the transport of the ionized fluid, absorbing the electricity from the air ; the E1 and E2 are their regulator devices ;

6,- an **auxilliary continous current power supply** which send the current against an special **excitation coil**, used as starting device ; it works only when the system is starting.
This collector device works very good for lighting and heating. The device made by Guillot had **20 meters height** on the total surface of **3 square-meters**. Also, J.Guillot used and electrical transformer for the industrial utilization of this "collector" --- as power supply for industrial electric engines."

French Patent # 551,882

Apparatus for Capture of Electric Currents in the Atmosphere

16 April 1923

Considering the terrestrial globe like the inductor of a dynamo, where the extraterrestrial ether is the inductor of electric currents circulating in the atmosphere; the apparatus of the invention described here selects through the device described below two perfectly distinct currents and eliminates others.

The device includes:

1, The air sensor; 2, a series of lightning rods; 3, vacuum; 4, an array of resistances; 5, vacuum; 6, witnesses.

1. An aerial sensor mounted on a pole is composed of **magnetic steel** fixed and sealed by a porcelain **insulator**, and surrounded a base by a **bronze ring** which are screwed **32 points of soft iron**, all forming antenna a pole. level beside it and isolated from the first, forming the 2nd pole, is fixed a sharp point of magnetic steel fixed in the horizontal position and directed towards the south and **movable to an angle of 45** is sealed in a porcelain insulator. This point is also circled a **ring of copper** notches figure. 1.

2. A series of 6 lightning surge arrestors at corners between each pole and the earth and the various gauges.

3. A first **regulator** form of a device similar absolutely similar to the aerial amtenna, but the two poles are superposed and opposed to the vertical point, and a **copper disk connects to ground**. Opposite the horizontal point, a **ring of tin** to which are welded tubes alternatively **16 tubes** composed each composed of **copper-lead** and **iron-lead** . The ring connects to the **ground** as shown in figure. 2.

A second regulator form of **automatic breakers** balanced on 3 poles and two poles also equally balanced.

4. A panel of **resistances** composed of **wire mesh** in bunches from different sections of **glass tubes** containing **copper** dust, **coal** and flowers of **sulfur**.

Vacuum cleaners consists of a **wooden box** on each pole, containing a **porcelain vase** in which **layers** isolated with **mica** is made up of **mercury, tin, coal, copper** and **sulfur**, all contaied in a **copper tube**.

6. The witnesses are comprised of ordinary incandescent lamps.

Resume

By the point at the zenith and the point to the south we channel two currents forming the two poles. We also protect from lightning. It regularizes the flow by a regulator and similar devices by a controlling each devise of adequate strength of the current harmful nature of these devices do not have loads. The refined current is conducted by ordinary copper wires**.**

French Patent # 565,395

Combined Apparatus for Capture of Atmospheric Electric Currents with Immediate Implementation

25 January 1924

We know that earth with its constitution, its rotation and movement in space, provides the electricity in the atmosphere. The electrical currents escape into space or largely accumulate towards the equator, as a result of the greater periphery of the globe.

In the atmosphere, there are two clearly distinct poles, i.e., clouds that can be electrically positive or negative; everything in nature shows this, otherwise it would be difficult to explain the lightning that occurs between the clouds and which are none other than contrary cloud electrical charges discharged by too close proximity.

The invention relates to a set of devices capable of capturing the atmospheric electricity.

So far, all searches made for this purpose has been to capture the atmosphere, i.e., that brought together into one system to capture two poles and opposes effect has been to destroy or cancel each other leaving the amount as the difference of the strongest to weakest.

It is therefore easy to understand why, considering the two poles of air as about equal, it is almost impossible to measure some potential with the land, the highest on the lowest remaining which can be positive or negative, copper being the strongest of one or other of these polarities.

It is on this basis that all research until now have been made, and that is why we must consider that all the time, between the two poles captured in the atmosphere and not in any mixture of systems uptake, it is possible to obtain tension and intensity, a considerable and measurable power captured separately between the two poles and remaining isolated from one another until their utilization .

In accordance with this invention, this collection is made by attraction of primary electrical currents in teh atmosphere, either positively or negatively charged, by an antenna that has two points absolutely isolated from one another, where one points to the zenith to attract negative electricity, and the other turned south, toward the equator to draws in the masses grouped in this area.

This shows and proves the existence of atmospheric electrical currents, and that it is possible to capture them with specially designed equipment primarily acting as regulators, as the persistent difficulty encountered so far in realizing their capture lies with large variations of tension in which the current atmosphere is present in space, for each of the poles, and an overload could inevitably fatal.

The patent in its present form of presentation does not cover the regulators or devices that are anticipated in the system, because they can be designed in different ways and give the same result, but covers the application and grouping of equipment operating as automatic relays with variable influence to limit current tension to that chosen for utilization.

These devices have a role associated with an overflow reservoir outside carrying excess liquid; these regulators will divert the excess voltage flows to ground.

We can still absorb these regulators having filters because they have the sole purpose of diverting the post being used , currents that are not yet known but likely that we will call for simplicity, abnormal currents. [sic...]

The patent also covers systems for regulating currents, applied to each of the poles because it is recognized that the shape and tension of the currents of the two poles are not equivalent.

The method of capture is by special antenna has directed two points in the atmosphere, as will be stated after this, with Boot ecoulement prior to the current atmosphere is also of great importance.

Finally, the current atmospheric reception is adequate even with the installation of a post, which can be expected at any location without the need for special altitude, as has been attempted in previous efforts.

We refer to the attached drawings:.

Figure 1 represents in elevation and side view an antenna that only has two points, to overcome an elevation ;

Figure 2 is the end of one of the peaks, the horizontal:



Fig. 1

Fig. 2

Figure 3 shows schematically the table on which are mounted various devices or accessories that act as regulators of current tensions.

Fig. 3.


1
2
3
4
5
7
R²
R³
R
R³
R²
12
12
R⁴
R⁴
R¹
R¹
11
11
L
L
+
-

Figure 4 is a scheme of surge arrestors, and

Figure 5 a table of resistances.

Fig. 4.



Fig. 5.



The necessary arrangements to capture atmospheric current form is as follows:

1. The **antenna** in figure 1 is formed with two peaks: the 1 is **steel**, supported by a **bronze ring** 2, surrounded by a **spiral form** 3; this point is oriented for attracting the **zenith** layers of **negative electricity** and the other edge 4 contains **copper coils** 6, and is oriented **south** to the **equator** to draw in the masses grouped in this area. To use this antenna it suffices to be raised on a mast or **pole** to a height a little higher than that of surrounding houses.

2. On the table **lightning arrestors**, contained 4, forms of 7 **copper horns** used to absorb large atmospheric discharges by certain time, as it would be dangerous to allow movement in the devices regulators.

3. On a table of **two** symmetrical systems **regulators**, Figure 3, one for each pole, to obtain and allow a regularization of large excesses in the current tensions, by automatically absorbing surges before passing over the surfacea chosen for the desired use. These regulators are represented on the drawing by the references R, R1, R2, R3, R4.

4. In the **resistance** panel in communication with regulators, these resistances are formed as **spiral coils or screens** 8, **tubes 9 of glass filled with fine coal dust , aluminum powder, sulfur and fine copper dust**. Finally, **two** special 10 **processors** and constitutes **layers** of metal forming an **absorbant** for harmful or abnormal currents.

5. As a source of energy formed **auxiliary batteries** 11 and **Ruhmkorff coils** 12 to get into the antenna sufficient attraction by means of an adjustment of intensity, which once it begins, allows the constant flow of atmospheric current in the system.

In considering Figure 3, which represents a sort of an installation scheme of the device, the reception of atmospheric electrical current will, as set out above, producing a priming of these currents. This boot is made in launching the system which is double to answer each of the poles, the current batteries 11 through 12 and reels going to the antenna.

This boot will continue until the disposal of electrical current atmosphere is evident by the one or more table lamps L of resistance shown in Figure 5.

Once the lights illuminate it is advisable to charge the batteries to boot. Natural flow and constant currents will be captured by the regulators , Figure 3; they will regularize in tension and in amperage and then directed to use in table lamps.

It has been said above that regulators R, etc., are intended and designed to automatically eliminate earth surge currents capture and abnormal currents that cannot yet be level but that these regulators could be replaced by devices with the same function.

There is therefore no need to describe in detail and especially the claims. We only specify that these regulators must be proper protection for the purposes described above.



The spark-gap with magnetic blowing :
a,- the initial stage ; the impulse current send in soil through the shunt-resistences 3, because the coils 2 have an impedance too big for the impulse of 10/20 µs ;
the spark-gap 1 has two elements disc-shaped 1a and 1b, the inferior disc have one electrode and the upper disc the other electrode of the spark-gap circuit.
b,- the second stage ; the accompanying current discharge - after the impulse current ;
this accompanying current pass through the coils 2 which produce the magnetic field with the role to extend the electric arc into the slit between insulator discs 1a and 1b ; the thickness of this slit is smaller and smaller in accord with the extension of the electric arc, in this manner producing the magnifing of its electric resistance and finally, the electric arc extinction.



1,- the spark-gap individual devices which work in the manner to extend the electric arc of the accompanying electric current ;
2,- the coils which produce the magnetic field for the magnetic blowing ;
3,- the electric shunt-resistances in parallel connection on the blowing coils, with the role of reducing the current inside this coils
4,- the disc with unlinear resistance ;
5,- electrical resistance for the homogenous distribution of the electric field in all the elements of the spark-gap.

In Jules Guillot scheme, that kind of device could be used for leading the current.

Spark-gap element with circuit for the magnetic blowing of the electric fascicle







a,- the spark-gap with variable resistance ;
b,- the tube spak-gap ;
t - the time

The tube spark-gap has the aerial spark gap with the electrodes 5 and 6 disposed at the insulator 8 extremities ; and one arc-over spark-gap device between the rod 4 and the electrode 1.

At start, the first spark apear in the aerial spark-gap and then, the electric dicharge goes to the gas-producing tube 7, where it makes the arc-over. The local pressure in the gas allow the electric arc extinction, after managing the over electric tension into soil. The capacity C which is created between the external ring 3 and the rod 4 is bigger than the Capacity C_1between 1 an 2 in that manner, when the overtension apears, the auxiliary spark-gap 1, 2 will start working and then, the main spark-gap 1, 4. In this circuit, the electrode 9 is connected at the aerial electric line and the electrode 1 at the Earth.

In the image above, it is an classic tube spark-gap used for the protection of aerial electric cables. The atmospheric electricity is discharged in soil and lost... The Guillot's inventions used that kind of devices for leading and absorbing of the atmospheric electricity.

DARIDA, Gillbert : "Practical Utilization of Atmospheric Electricity";
(in *The Invention Encyclopedia,* pp. 204-207 ; 1930, Geo. Constantinescu, Ed.) --



Utilizarea practică a electricității atmosferice

Pământul ca și celelalte astre, posedă o electricitate proprie negativă în interior, iar aerul care-l înconjoară este pozitiv. Potențialul sau tensiunea electrică a aerului se mărește pe măsură ce ne ridicăm în înălțime, astfel că putem spune că intensitatea electrică este proporțională cu înălțimea (după lucrările remarcabile ale lui Franklin, Quetelet, Lord Kelvin, Mascart, Joubert și a altor mari savanți fizicieni).

Observațiile făcute recent, au arătat că aerul regiunilor înalte dela 6000—7000 m este foarte încărcat cu electricitate pozitivă, a cărei explicație se datorește frecării fotosferei sau atmosferei terestre, prin învârtirea pământului în jurul soarelui cu mai mult de o sută de mii de km pe oră. Această frecare directă în fluidul eteric ambiant, face ca aerul să se încarce cu electricitate pozitivă prin influență, iar pământul să se încarce negativ.

Intre cele două medii, fluidic (aerul) și (pământul) materie, știința ne spune, că în partea de jos a atmosferei, pe timp frumos un centimetru cub de aer ionizat, conține circa 800 particule cu ioni pozitivi și 680 ioni negativi (electroni).

Pământul se comportă ca un enorm conductor încărcat negativ, respingând electroni și atrăgând ionii pozitivi. Această atracție a ionilor pozitivi determină un curent electric, zis și curent de convențiune. E un fel de bombardament invizibil supus variațiunilor zilei și a sezoanelor, putându-l evalua aproximativ la o densitate mijlocie remarcabilă, dela 3×10^{16} sau a 30 quatrilionime de amper pe cm cub, ceea ce dă pentru întreagă suprafață a pământului un curent formidabil, de 1500 de amperi.

Se pune întrebarea cum un astfel de curent poate să-și întreție mereu același sens? Aceasta este enigma pe care ne-o punem, studiind curenții naturali ai atmosferei noastre, presupunem că poate să fie o legătură a acțiunii emanațiunilor radioactive. Aceste emanaţiuni fiind din gaze radioactive grele, se găsesc de obiceiu în mare abundenţă aproape de pământ ceea ce ne explică marea ionizare observată în general în grote şi caverne.

Ionizarea atmosferică poate de asemenea fi produsă în parte, de acţiunea razelor X, foarte pătrunzătoare şi de diferite substanţe radioactive închise în subsolul pământului. De asemenea poate să mai fie, ţinând seama de acţiunea «Calei Lactee» şi de ionizarea luminei solare, foarte bogată în radiaţiuni ultraviolete



Fig. 108

precum şi a electronilor emişi direct din radierea căldurii solare de circa 6000 de grade.

Captarea electricităţii atmosferice a fost utilizată în Franţa prin cabluri aeriene montate pe Mont Blank, iar în Germania prin cabluri susţinute de baloane captive.

Sunt mai multe sisteme, vom da pe scurt pe cel mai ingenios procedeu, inventat de ing. Jules Guillot, bazat pe sifonul electric. Procedeul consistă de a pompa direct din atmosferă, electricitate


P
PĂMÂNT
S
ECUATOR
E₁
E₂
R
Cₙ
LĂMPI

prin ajutorul unui aparat de captare, format din 2 antene aeriene şi o serie de bobine după cum se vede în fig. 108. Una din antene este verticală în formă de evantaiu dirijată cu vârfurile către zenit, pentru a capta electricitatea negativă din atmosferă; cea care este orizontală, este dirijată către Sud, pentru a capta electricitate pozitivă.

Electricitatea în aer pare să fie cu dublă polaritate, după cum se vede la 2 nori electrizaţi, cari deplasându-se în sens contrar, dau naştere unei scântei (fulger) când distanţa respectivă poate să fie străbătută de puternica lor diferenţă de potenţial. Straturile de aer de densităţi diferite, nu sunt toate antrenate de aceeaşi viteză prin rotaţia pământului, ele se electrizează deci prin frecarea decalajului lor respectiv.

Aceste sunt consideraţiunile ce l-au făcut pe inventator să aşeze în atmosferă doi poli complet distincţi şi perfect izolaţi, al cărui pol pozitiv *S* (fig. 109) poate fi dirijat în direcţiunea Sudului, şi a celuilalt negativ *P*, în direcţiunea zenitului. Fig. 109 arată schema montajului şi a conexiunilor compuse după cum urmează: 1. dintr'o antenă dublă aeriană, montată pe stâlpi de 15—20 m înălţime. Această parte care se mai numeşte şi aparat de captat, este format din vârfurile *P*, dispuse în evantai în vârful unei tije de oţel dirijate către zenit, pentru a capta curenţii negativi ai atmosferei şi dintr'o altă antenă orizontală a cărei săgeată este îndreptată către sud *S*, adică către equator, pentru a recepta curenţii pozitivi. Aceste două părţi dispuse în unghiu de 90⁰, formează cei doi poli al curentului aerian, a cărei diferenţă de potenţial este suficientă pentru a permite utilizarea electricităţii atmosferice.

Fig. 109

French Patent # 551,882

Appareil Capteur de Courants Electriques dans L'Atmosphere

BREVET D'INVENTION.

XII. — Instruments de précision, électricité.

5. — Production de l'électricité, moteurs électriques.

N° 551.882

Appareil capteur de courants électriques dans l'atmosphère.

M. Jules GUILLOT résidant en France (Tarn-et-Garonne).

Demandé le 27 septembre 1921, à 15h 20m, à Paris.
Délivré le 15 janvier 1923. — Publié le 16 avril 1923.
[Brevet d'invention dont la délivrance a été ajournée en exécution de l'art. 11 § 7 de la loi du 5 juillet 1844 modifiée par la loi du 7 avril 1902.]

Considérant le globe terrestre comme l'induit d'une dynamo, dont l'éther supraterrestre est l'inducteur, des courants électriques circulent dans l'intervalle c'est-à-dire dans la couche atmosphérique; l'inventeur capte au moyen de l'appareil décrit ci-dessous deux de ces courants parfaitement distincts et élimine les autres.

L'appareil comprend :

1° Le capteur aérien; 2° une série de parafoudres; 3° les régulateurs; 4° un tableau de résistances; 5° les aspirateurs; 6° les témoins.

1° Le capteur aérien monté sur un poteau est composé d'une pointe d'acier aimanté fixée par scellement sur un isolateur porcelaine et cerclée à sa base par une bague de bronze sur laquelle sont vissées 32 aiguilles de fer doux, le tout formant l'antenne d'un pôle. A côté et isolé de la première, formant le 2e pôle, est fixée une pointe d'acier aimanté dans la position horizontale et dirigée vers le sud dont la base coudée à 45° est scellée sur un isolateur porcelaine. Cette pointe est également cerclée d'une bague de cuivre à encoches fig. 1.

2° Une série de 6 parafoudres à cornes entre chaque pôle et la terre et à écartements variés.

3° Un premier régulateur formé d'un appareil absolument semblable au capteur aérien, mais ayant les deux pôles superposés, et, opposé à la pointe verticale, un disque de cuivre relié à la terre. Opposé à la pointe horizontale, une roue à jante d'étain sur laquelle sont soudés alternativement 16 tubes composés eux-mêmes de deux métaux soudés : cuivre-plomb et fer-plomb. Cette roue est reliée à la terre par son pivot fig. 2.

Un deuxième régulateur formé d'appareils à déclanchement automatique au nombre de 3 par pôles et deux basculateurs également par pôles.

4° Un tableau de résistances composé de fils de maillechort en boudins de différentes sections, de tubes en verre contenant des poussières de cuivre, du charbon de cornue et de la fleur de soufre.

5° Les aspirateurs composés d'une boîte en bois sur chaque pôle, contenant un vase de porcelaine dans lequel par couches superposées et isolées au mica est placé du mercure, de l'étain, du charbon, du cuivre et du soufre, le tout traversé par une tige de cuivre.

6° Les témoins composés de lampes à incandescence ordinaires.

RÉSUMÉ.

Par la pointe au zénith et par la pointe au sud nous canalisons deux courants formant les deux pôles. On protège l'ensemble par des parafoudres. On régularise le débit par un régulateur semblable et par des appareils à déclanchement commandant chacun des résistances appropriées de la nature du courant nuisible dont ces appareils sont chargés. Les courants épurés sont conduits aux témoins par des fils de cuivre ordinaire.

Jules GUILLOT,
Moissac (Tarn-et-Garonne).

XII. — Instruments de précision, électricité.

5. — Production de l'électricité, moteurs électriques.

N° 565.395

Dispositif combiné pour capter les courants électriques atmosphériques avec application immédiate.

M. Jules GUILLOT résidant en France (Allier).

Demandé le 6 avril 1923, à 11^{h} 30^{m}, à Paris.
Délivré le 7 novembre 1923. — Publié le 25 janvier 1924.

On sait que la terre, par sa propre constitution, sa rotation et son mouvement dans l'espace, fournit à elle seule l'électricité que l'on utilise et qui est en suspension dans l'atmosphère. Les courants électriques, qui s'échappent de la surface du globe, montent directement dans l'espace où les grandes masses sont accumulées vers l'équateur, par suite de la plus grande périphérie du globe.

Dans l'atmosphère, il y a deux pôles parfaitement distincts, c'est-à-dire que des nuages peuvent être électrisés, soit d'électricité positive ou négative; ceci, tout dans la nature le démontre, sans quoi, il serait difficile d'expliquer la provenance des éclairs qui se produisent entre les nuages et qui ne sont autres que des nuages chargés d'électricité contraire et qui s'amorcent entre eux par un trop grand rapprochement.

L'invention dont il s'agit concerne un dispositif formé d'un ensemble d'appareils aptes à la captation de ces courants atmosphériques.

Jusqu'à ce jour, toutes les recherches faites dans ce but ont été de capter dans l'atmosphère une seule catégorie de courants atmosphériques, c'est-à-dire, qu'on a réuni dans un même système de captation, deux pôles opposés et dont l'effet a été de se détruire ou de s'annuler l'un à l'autre laissant comme quantité que la différence du plus fort au plus faible.

Il sera donc facile de comprendre pourquoi, en considérant les deux pôles d'un courant atmosphérique comme à peu près égaux, il est presque impossible par certains temps de mesurer le potentiel avec la terre, du plus fort sur le plus faible subsistant et qui peut être positif ou négatif, suivant que le plus fort est de l'une ou de l'autre de ces polarités.

C'est sur cette base que toutes les recherches jusqu'à nos jours ont été faites et c'est pourquoi, il faut considérer que par tous les temps, entre les deux pôles captés dans l'atmosphère et non mélangés dans aucun des systèmes de captation, il est possible d'obtenir, en tension et en intensité, une puissance aussi considérable que l'on puisse désirer et qui sera mesurée entre les deux pôles captés séparément et toujours isolés l'un de l'autre jusqu'à leur utilisation.

Suivant l'invention, cette captation se fait par attraction dans l'atmosphère au moyen d'un amorçage des courants électriques, soit positif ou négatif, par une antenne à deux pointes absolument isolées l'une de l'autre, dont l'une tournée vers le zénith attire les couches d'électricité négative, et l'autre, tournée vers le sud, puise vers l'équateur, dans les masses groupées dans cette zone.

Ceci exposé et l'existence des courants électriques atmosphériques étant prouvée, il est

possible de les capter à la condition de disposer d'appareils spéciaux étudiés surtout pour jouer le rôle de régulateurs, attendu que la difficulté persistante rencontrée jusqu'alors pour réaliser la captation incombe aux grandes variations de tensions sous lesquelles les courants atmosphériques se présentent dans l'espace, pour chacun des pôles, et dont l'écoulement dans un poste de captation serait inévitablement funeste.

Le présent brevet sous sa forme de présentation doit donc couvrir, non pas le ou les dispositifs régulateurs qui sont prévus dans le système, car ils peuvent être conçus d'une façon toute différente et donner le même résultat, mais sur l'application raisonnée et le groupement d'appareils fonctionnant automatiquement et intervenant chacun comme relais d'influence variable pour limiter la tension des courants captés dans l'atmosphère à celle choisie pour utilisation.

Ces appareils ont un rôle assez connexe avec celui de trop-pleins sur un réservoir qui acheminent à l'extérieur l'excès de liquide; ici ces régulateurs détournent l'excès de tension des courants à la terre.

On peut encore assimiler ces régulateurs à des filtres car ils ont pour but de détourner du poste d'utilisation, des courants qui ne sont pas encore de nature connue mais que pour simplicité on appellera courants parasites ou anormaux.

Le brevet portera aussi sur le système de régulation des courants, appliqué à chacun des pôles, car il est reconnu que la forme et la tension des courants aux deux pôles ne sont pas équivalentes.

Le mode de captation par antenne spéciale à deux pointes orientées dans l'atmosphère, comme il sera indiqué ci-après, avec amorçage préalable pour l'écoulement des courants atmosphériques est aussi d'une grande importance.

Enfin la réception des courants atmosphériques se fait à l'endroit même de l'installation du poste; celui-ci peut être prévu en un lieu quelconque sans nécessiter d'altitude particulière, comme cela a été tenté dans des essais préconçus.

Sur les dessins ci-annexés auxquels on se réfère

La fig. 1 représente en élévation et en coupe partielle l'antenne seule, à deux pointes, surmontant un poteau d'élévation;

La fig. 2 est le plan de l'une des pointes, celle horizontale:

La fig. 3 montre schématiquement le tableau sur lequel sont montés les divers appareils ou accessoires qui jouent le rôle de régulateurs des tensions de courants.

La fig. 4 est un schéma de parafoudre, et

La fig. 5 un tableau de résistances.

Le dispositif nécessaire à la captation des courants atmosphériques est formé comme suit :

1° D'une antenne, fig. 1, formée de deux pointes dont l'une 1 est en acier, supportée par une bague de bronze 2 entourée d'une spirale 3 formant self; cette pointe est tournée vers le zénith pour attirer les couches d'électricité négative; l'autre pointe 4 comporte un cadre 5 de huit branches supportant des spirales de cuivre 6 et est tournée vers le sud pour puiser vers l'équateur dans les masses groupées dans cette zone. Pour l'utilisation de cette antenne il suffira qu'elle soit portée par un mât ou poteau de hauteur un peu supérieure à celle des habitations environnantes.

2° D'un tableau de parafoudre, fig. 4, formé de cornes de cuivre 7 servant à absorber les tros grosses décharges atmosphériques que par certains temps, il serait dangereux de laisser circuler dans les appareils régulateurs.

3° D'une table de deux systèmes symétriques de régulateurs, fig. 3, un pour chaque pôle, qui permet d'obtenir une régularisation assez grande dans les tensions des courants en absorbant automatiquement les surtensions dépassant la tension choisie pour l'utilisation désirée. Ces régulateurs sont représentés sur le dessin par les références R, R^1, R^2, R^3, R^4.

4° D'un tableau de résistance en communication avec les régulateurs, ces résistances sont formées de spirales de maillechor 8, de tubes 9 de verre remplis de poussière fine de charbon de cornue, de poudre d'aluminium, de soufre et de poussière fine de cuivre; enfin, deux appareils spéciaux 10 formant transformateurs et constitués de couches de métaux absorbant certains courants nuisibles ou anormaux.

5° D'une source auxiliaire d'énergie formée de piles 11 et de bobines Ruhmkorff 12 permettant d'obtenir dans l'antenne une attraction suffisante au moyen d'un dispositif de



réglage d'intensité qui, une fois amorcé, permet l'écoulement constant des courants de l'atmosphère dans le système.

En considérant la fig. 3 qui représente en quelque sorte le schéma d'installation du dispositif, la réception des courants électriques atmosphériques se fera de la façon indiquée ci-dessus, en produisant un amorçage de ces courants. Cet amorçage est fait en lançant dans le système qui est double pour répondre à chacun des pôles, le courant des piles 11 passant par les bobines 12 et se rendant à l'antenne.

Cet amorçage sera maintenu et réglé jusqu'à ce que l'écoulement des courants électriques atmosphériques se soit manifesté par l'allumage d'une ou plusieurs lampes L du tableau des résistances représenté en fig. 5 portant la prise d'utilisation.

Dès que l'allumage des lampes sera constaté on sera averti de la captation des courants atmosphériques et on pourra couper le courant des piles d'amorçage. L'écoulement naturel et constant des courants captés se produira dans les appareils régulateurs de la table, fig. 3; ils seront régularisés en tension et en nature puis dirigés au tableau des lampes pour utilisation.

Il a été dit ci-dessus que les régulateurs R, etc., étaient prévus et conçus pour éliminer automatiquement à la terre les surtensions des courants captés ainsi que les courants anormaux qui ne peuvent encore être classés. mais que ces régulateurs pouvaient être remplacés par des appareils faisant le même office.

Il n'y a donc pas lieu de les décrire en détail et de les revendiquer spécialement. L'avenir seul précisera si ces régulateurs doivent faire l'objet d'une protection propre pour l'application décrite ci-dessus.

RÉSUMÉ.

Dispositif combiné pour capter les courants électriques atmosphériques avec application immédiate, caractérisé :

1° En ce que l'organe de captation est une antenne à deux branches orientées différemment, l'une vertical avec self est tournée vers le zénith pour puiser les courants négatifs, l'autre horizontale comporte un plateau central avec enroulement de fil et est orientée vers le sud pour puiser les courants positifs; l'orientation des pointes restant fonction du lieu terrestre où se fait la captation des courants considérés.

2° En ce que l'écoulement des courants atmosphériques dans le système récepteur est subordonné à un amorçage qui consiste à lancer dans l'antenne un courant provenant d'une source auxiliaire, telle que des piles reliées à des bobines de Ruhmkorff.

3° En ce qu'un tableau parafoudre est interposé entre l'antenne ou organe de captation et le tableau des régulateurs pour préserver l'installation en éliminant à la terre les décharges brusques atmosphériques.

4° En ce que les régulateurs sont disposés suivant deux systèmes symétriques correspondant à chacun des pôles des courants atmosphériques.

J. GUILLOT.

Par procuration :

V. Prévost.

Parts List

Steel Rods, magnetic, 2
Insulator, porcelain
Ring, bronze
Rods, soft iron, 32
Ring, copper
Surge Protector
Disk, copper
Ring, tin
Tubes, steel
Rx Cu-Pb, Fe-Pb
Breakers, automatic
Resistances : Wire Mesh, Glass Tube. Cu, C, S powder
Vacuum Cleaners : Box, Jar, Mica &

Tube, copper;
Rx : Hg, Sn, C, Cu, S
Battery
Ignition Coil

Your Support Maintains this Service --

BUY

The Rex Research Civilization Kit

... It's Your Best Bet & Investment in Sustainable Humanity on Earth ...
Ensure & Enhance Your Survival & Genome Transmission ...
Everything @ rexresearch.com on a Data DVD !

ORDER PAGE

Rex Research, POB 19250, Jean, NV 89019 USA

archive.today
webpage capture
Saved from http://www.rexresearch.com/guillot/guillot.htm search
history
5 May 2015 11:19:54 UTC
All snapshots from host www.rexresearch.com
Webpage Screenshot
share download .zip report error or abuse

rexresearch.com

Jules GUILLOT

Atmospheric Electric Generator



Shared by L. Cozma (Thanks !) --

The Guillot device generated about 2.5-3 Kilowatts with antenna height of ~ 20 meters. Power depends on the total collector surface and height of the vertical antenna. The apparatus in the photo produced ~300 watts with a collector 2 meters tall.

"Practical Utilization of Atmospheric Electricity"

by

Gillbert Darida

in *The Invention Encyclopedia*, pp. 204-207 (1930, Geo. Constantinescu, Ed.)

"The Earth has its own negative electricity, in the soil, and the atmosphere which surrounds the Earth is charged with positive electricity. The electric potential (the voltage) increases with the altitude, so we can say that the electric force is proportional to the atmospheric altitude (after Franklin, Quetelet, Lord Kelvin, Mascart, Joubert and other scientists).

The recent observations demonstrate that the air at 6000-7000 meters in altitude, is very highly charged with positive electricity, which could be explained by the friction between the external photosphere and the upper atmosphere of Earth, which rotates at a speed of more than 100,000 Kilometer per hour.

In that way, the Earth works like an electrostatic generator with electric charging by influence --- the upper atmosphere is positively charged by influence and the Earth crust obtains the negative polarity.

Between the two environments, the air and the soil, and inside the low atmosphere, in conditions of good weather, there are sbout 800 positive ions and also, 680 negative ion (and electrons) in just one square-centimeter of normal ionised air.

The Earth behaves like an huge electric armature negatively charged, which repels the electrons and attracts the positive ions. That positive ions' attraction determinates an electric current, also called "convective current". That's like an invisible continous bombardment, subject to daily and seasonal variations, which could be aproximated at **3 x 10 ^ -16 Amperes per square-centimeter,** and that is a total value of 1500 Amperes for the entire surface of the Earth.
The question is --- how does this current always maintains the same direction ? We can suppose that the natural radioactive emissions of the soil is responsable for this. We also know that radioactive emissions of the Earth works usually near the soil surface, and that explains the ionisation phenomenona inside caves.

The ionisation of the low atmosphere could also be the effect of the radioactive emissions of the Earth, especially when the X radiation works. Also, the Earth atmosphere is ionisated by the external radiation proceeding from the Sun and from the space environment, especially the action of ultraviolet radiation and the electron fascicles emitted by the Sun surface, at the temperature of 6000 deg. Celsius.

The capture of atmosphere electricity has been used in France, with aerial cables mounted on the Mont Blanc, and also in Germany --- with conductive cables carried by the captive baloons.

The atmosphere electricity collect system invented by eng. Jules Guillot is most ingenious and it relies on "the **electric siphon**" [*m.n. --- the discharging devices or spark-gap used today from the protection of aerial electric cables against the atmospheric electricity ; Jules Guillot has thought to recuperate and to use that electricity*].

His method consisted in the direct "pumping" of the atmosphere electricity using a collecting device which had two antennae and several collecting rods.

One antenna is **vertical** and it has a lot of **rods** scattered like an opened **fan**, with the tips against the **zenith**, for collecting the **negative** electricity which comes from the air ; the **horizontal** antenna is orientated against the **South** and its role is to collect the **positive** electricity.

The air electricity seems to have the double-polarity, as we can see at two electrised clouds when between them apears the electric discharge. The air could have different electric charging and the ionisation processus of atmosphere is very heterogenous. The inventor Guillot used **two separated and insulated armatures with the positive armature against the South** (more precisely, against the **Equator**...) and the **negative** armature against the **zenith**.

We can see in the scheme :

1,- the device P is the "**collector apparatus**" having **15-20 meters height** ; it also has a lot of **rods** which are scattered **fan**-like, all this on top of an **iron pillar** ; and also an **horizontal antenna** S oriented against the **South** ; the two antennae are disposed at **90 deg. angle** forming the two armatures where the electrical tension must apear. As the **height** of the pillar **increases**, the **voltage** increases more and more ;

2,- a system of **lightning-rods** (p1, p2, p3) for protection against discharges of atmospheric electricity during storms;

3,- the regulator system (**voltage regulator**, etc) R ;

4,- the electric **resistors** (Cn) for absorbing the parasite currents ;

5,- the "electric siphons" which have the role of making a magnetic field as a good environment for the transport of the ionized fluid, absorbing the electricity from the air ; the E1 and E2 are their regulator devices ;

6,- an **auxilliary continous current power supply** which send the current against an special **excitation coil**, used as starting device ; it works only when the system is starting.
This collector device works very good for lighting and heating. The device made by Guillot had
20 meters height on the total surface of **3 square-meters**. Also, J.Guillot used and electrical transformer for the industrial utilization of this "collector" --- as power supply for industrial electric engines."

French Patent # 551,882

Apparatus for Capture of Electric Currents in the Atmosphere

16 April 1923

Considering the terrestrial globe like the inductor of a dynamo, where the extraterrestrial ether is the inductor of electric currents circulating in the atmosphere; the apparatus of the invention described here selects through the device described below two perfectly distinct currents and eliminates others.

The device includes:

1, The air sensor; 2, a series of lightning rods; 3, vacuum; 4, an array of resistances; 5, vacuum; 6, witnesses.

1. An aerial sensor mounted on a pole is composed of **magnetic steel** fixed and sealed by a porcelain **insulator**, and surrounded a base by a **bronze ring** which are screwed **32 points of soft iron**, all forming antenna a pole. level beside it and isolated from the first, forming the 2nd pole, is fixed a sharp point of magnetic steel fixed in the horizontal position and directed towards the south and **movable to an angle of 45** is sealed in a porcelain insulator. This point is also circled a **ring of copper** notches figure. 1.

2. A series of 6 lightning surge arrestors at corners between each pole and the earth and the various gauges.

3. A first **regulator** form of a device similar absolutely similar to the aerial amtenna, but the two poles are superposed and opposed to the vertical point, and a **copper disk connects to ground**. Opposite the horizontal point, a **ring of tin** to which are welded tubes alternatively **16 tubes** composed each composed of **copper-lead** and **iron-lead** . The ring connects to the **ground** as shown in figure. 2.

A second regulator form of **automatic breakers** balanced on 3 poles and two poles also equally balanced.

4. A panel of **resistances** composed of **wire mesh** in bunches from different sections of **glass tubes** containing **copper** dust, **coal** and flowers of **sulfur**.

Vacuum cleaners consists of a **wooden box** on each pole, containing a **porcelain vase** in which **layers** isolated with **mica** is made up of **mercury, tin, coal, copper** and **sulfur**, all contaied in a **copper tube**.

6. The witnesses are comprised of ordinary incandescent lamps.

Resume

By the point at the zenith and the point to the south we channel two currents forming the two poles. We also protect from lightning. It regularizes the flow by a regulator and similar devices by a controlling each devise of adequate strength of the current harmful nature of these devices do not have loads. The refined current is conducted by ordinary copper wires**.**

French Patent # 565,395

Combined Apparatus for Capture of Atmospheric Electric Currents with Immediate Implementation

25 January 1924

We know that earth with its constitution, its rotation and movement in space, provides the electricity in the atmosphere. The electrical currents escape into space or largely accumulate towards the equator, as a result of the greater periphery of the globe.

In the atmosphere, there are two clearly distinct poles, i.e., clouds that can be electrically positive or negative; everything in nature shows this, otherwise it would be difficult to explain the lightning that occurs between the clouds and which are none other than contrary cloud electrical charges discharged by too close proximity.

The invention relates to a set of devices capable of capturing the atmospheric electricity.

So far, all searches made for this purpose has been to capture the atmosphere, i.e., that brought together into one system to capture two poles and opposes effect has been to destroy or cancel each other leaving the amount as the difference of the strongest to weakest.

It is therefore easy to understand why, considering the two poles of air as about equal, it is almost impossible to measure some potential with the land, the highest on the lowest remaining which can be positive or negative, copper being the strongest of one or other of these polarities.

It is on this basis that all research until now have been made, and that is why we must consider that all the time, between the two poles captured in the atmosphere and not in any mixture of systems uptake, it is possible to obtain tension and intensity, a considerable and measurable power captured separately between the two poles and remaining isolated from one another until their utilization .

In accordance with this invention, this collection is made by attraction of primary electrical currents in teh atmosphere, either positively or negatively charged, by an antenna that has two points absolutely isolated from one another, where one points to the zenith to attract negative electricity, and the other turned south, toward the equator to draws in the masses grouped in this area.

This shows and proves the existence of atmospheric electrical currents, and that it is possible to capture them with specially designed equipment primarily acting as regulators, as the persistent difficulty encountered so far in realizing their capture lies with large variations of tension in which the current atmosphere is present in space, for each of the poles, and an overload could inevitably fatal.

The patent in its present form of presentation does not cover the regulators or devices that are anticipated in the system, because they can be designed in different ways and give the same result, but covers the application and grouping of equipment operating as automatic relays with variable influence to limit current tension to that chosen for utilization.

These devices have a role associated with an overflow reservoir outside carrying excess liquid; these regulators will divert the excess voltage flows to ground.

We can still absorb these regulators having filters because they have the sole purpose of diverting the post being used , currents that are not yet known but likely that we will call for simplicity, abnormal currents. [sic...]

The patent also covers systems for regulating currents, applied to each of the poles because it is recognized that the shape and tension of the currents of the two poles are not equivalent.

The method of capture is by special antenna has directed two points in the atmosphere, as will be stated after this, with Boot ecoulement prior to the current atmosphere is also of great importance.

Finally, the current atmospheric reception is adequate even with the installation of a post, which can be expected at any location without the need for special altitude, as has been attempted in previous efforts.

We refer to the attached drawings:.

Figure 1 represents in elevation and side view an antenna that only has two points, to overcome an elevation ;

Figure 2 is the end of one of the peaks, the horizontal:



Fig. 1

Fig. 2

Figure 3 shows schematically the table on which are mounted various devices or accessories that act as regulators of current tensions.

Fig. 3.


1
2
3
4
5
+
-
7
7
R²
R³
R
R³
R²
12
12
R⁴
R⁴
R¹
R¹
11
11
L
L

Figure 4 is a scheme of surge arrestors, and

Figure 5 a table of resistances.

Fig.4.



Fig.5.



The necessary arrangements to capture atmospheric current form is as follows:

1. The **antenna** in figure 1 is formed with two peaks: the 1 is **steel**, supported by a **bronze ring** 2, surrounded by a **spiral form** 3; this point is oriented for attracting the **zenith** layers of **negative electricity** and the other edge 4 contains **copper coils** 6, and is oriented **south** to the **equator** to draw in the masses grouped in this area. To use this antenna it suffices to be raised on a mast or **pole** to a height a little higher than that of surrounding houses.

2. On the table **lightning arrestors**, contained 4, forms of 7 **copper horns** used to absorb large atmospheric discharges by certain time, as it would be dangerous to allow movement in the devices regulators.

3. On a table of **two** symmetrical systems **regulators**, Figure 3, one for each pole, to obtain and allow a regularization of large excesses in the current tensions, by automatically absorbing surges before passing over the surfacea chosen for the desired use. These regulators are represented on the drawing by the references R, R1, R2, R3, R4.

4. In the **resistance** panel in communication with regulators, these resistances are formed as **spiral coils or screens** 8, **tubes 9 of glass filled with fine coal dust , aluminum powder, sulfur and fine copper dust**. Finally, **two** special 10 **processors** and constitutes **layers** of metal forming an **absorbant** for harmful or abnormal currents.

5. As a source of energy formed **auxiliary batteries** 11 and **Ruhmkorff coils** 12 to get into the antenna sufficient attraction by means of an adjustment of intensity, which once it begins, allows the constant flow of atmospheric current in the system.

In considering Figure 3, which represents a sort of an installation scheme of the device, the reception of atmospheric electrical current will, as set out above, producing a priming of these currents. This boot is made in launching the system which is double to answer each of the poles, the current batteries 11 through 12 and reels going to the antenna.

This boot will continue until the disposal of electrical current atmosphere is evident by the one or more table lamps L of resistance shown in Figure 5.

Once the lights illuminate it is advisable to charge the batteries to boot. Natural flow and constant currents will be captured by the regulators , Figure 3; they will regularize in tension and in amperage and then directed to use in table lamps.

It has been said above that regulators R, etc., are intended and designed to automatically eliminate earth surge currents capture and abnormal currents that cannot yet be level but that these regulators could be replaced by devices with the same function.

There is therefore no need to describe in detail and especially the claims. We only specify that these regulators must be proper protection for the purposes described above.



The spark-gap with magnetic blowing :
a,- the initial stage ; the impulse current send in soil through the shunt-resistences 3, because the coils 2 have an impedance too big for the impulse of 10/20 μs ;
the spark-gap 1 has two elements disc-shaped 1a and 1b, the inferior disc have one electrode and the upper disc the other electrode of the spark-gap circuit.
b,- the second stage ; the accompanying current discharge - after the impulse current ;
this accompanying current pass through the coils 2 which produce the magnetic field with the role to extend the electric arc into the slit between insulator discs 1a and 1b ; the thickness of this slit is smaller and smaller in accord with the extension of the electric arc, in this manner producing the magnifing of its electric resistance and finally, the electric arc extinction.



1,- the spark-gap individual devices which work in the manner to extend the electric arc of the accompanying electric current ;
2,- the coils which produce the magnetic field for the magnetic blowing ;
3,- the electric shunt-resistances in parallel connection on the blowing coils, with the role of reducing the current inside this coils
4,- the disc with unlinear resistance ;
5,- electrical resistance for the homogenous distribution of the electric field in all the elements of the spark-gap.

In Jules Guillot scheme, that kind of device could be used for leading the current.

Spark-gap element with circuit for the magnetic blowing of the electric fascicle



a,- the spark-gap with variable resistance ;
b,- the tube spak-gap ;
t - the time

The tube spark-gap has the aerial spark gap with the electrodes 5 and 6 disposed at the insulator 8 extremities ; and one arc-over spark-gap device between the rod 4 and the electrode 1.

At start, the first spark apear in the aerial spark-gap and then, the electric dicharge goes to the gas-producing tube 7, where it makes the arc-over. The local pressure in the gas allow the electric arc extinction, after managing the over electric tension into soil. The capacity C which is created between the external ring 3 and the rod 4 is bigger than the Capacity C_1 between 1 an 2 in that manner, when the overtension apears, the auxiliary spark-gap 1, 2 will start working and then, the main spark-gap 1, 4. In this circuit, the electrode 9 is connected at the aerial electric line and the electrode 1 at the Earth.

In the image above, it is an classic tube spark-gap used for the protection of aerial electric cables. The atmospheric electricity is discharged in soil and lost... The Guillot's inventions used that kind of devices for leading and absorbing of the atmospheric electricity.

DARIDA, Gillbert : "Practical Utilization of Atmospheric Electricity";
(in *The Invention Encyclopedia,* pp. 204-207 ; 1930, Geo. Constantinescu, Ed.) --

Pământul ca şi celelalte astre, posedă o electricitate proprie negativă în interior, iar aerul care-l înconjoară este pozitiv. Potenţialul sau tensiunea electrică a aerului se măreşte pe măsură ce ne ridicăm în înălţime, astfel că putem spune că intensitatea electrică este proporţională cu înălţimea (după lucrările remarcabile ale lui Franklin, Quetelet, Lord Kelvin, Mascart, Joubert şi a altor mari savanţi fizicieni).

Observaţiile făcute recent, au arătat că aerul regiunilor înalte dela 6000—7000 m este foarte încărcat cu electricitate pozitivă, a cărei explicaţie se datoreşte frecării fotosferei sau atmosferei terestre, prin învârtirea pământului în jurul soarelui cu mai mult de o sută de mii de km pe oră. Această frecare directă în fluidul eteric ambiant, face ca aerul să se încarce cu electricitate pozitivă prin influenţă, iar pământul să se încarce negativ.

Intre cele două medii, fluidic (aerul) şi (pământul) materie, ştiinţa ne spune, că în partea de jos a atmosferei, pe timp frumos un centimetru cub de aer ionizat, conţine circa 800 particule cu ioni pozitivi şi 680 ioni negativi (electroni).

Pământul se comportă ca un enorm conductor încărcat negativ, respingând electroni şi atrăgând ionii pozitivi. Această atracţie a ionilor pozitivi determină un curent electric, zis şi curent de convenţiune. E un fel de bombardament invizibil supus variaţiunilor zilei şi a sezoanelor, putându-l evalua aproximativ la o densitate mijlocie remarcabilă, dela 3×10^{16} sau a 30 quatrilionime de amper pe cm cub, ceea ce dă pentru întreagă suprafaţă a pământului un curent formidabil, de 1500 de amperi.

Se pune întrebarea cum un astfel de curent poate să-şi întreţie mereu acelaşi sens? Aceasta este enigma pe care ne-o punem, studiind curenţii naturali ai atmosferei noastre, presupunem că poate să fie o legătură a acţiunii emanaţiunilor radioactive. Aceste emanaţiuni fiind din gaze radioactive grele, se găsesc de obiceiu în mare abundenţă aproape de pământ ceea ce ne explică marea ionizare observată în general în grote şi caverne.

Ionizarea atmosferică poate de asemenea fi produsă în parte, de acţiunea razelor X, foarte pătrunzătoare şi de diferite substanţe radioactive închise în subsolul pământului. De asemenea poate să mai fie, ţinând seama de acţiunea «Calei Lactee» şi de ionizarea luminei solare, foarte bogată în radiaţiuni ultraviolete precum şi a electronilor emişi direct din radierea căldurii solare de circa 6000 de grade.



Fig. 108

Captarea electricităţii atmosferice a fost utilizată în Franţa prin cabluri aeriene montate pe Mont Blank, iar în Germania prin cabluri susţinute de baloane captive.

Sunt mai multe sisteme, vom da pe scurt pe cel mai ingenios procedeu, inventat de ing. Jules Guillot, bazat pe sifonul electric. Procedeul consistă de a pompa direct din atmosferă, electricitate



prin ajutorul unui aparat de captare, format din 2 antene aeriene și o serie de bobine după cum se vede în fig. 108. Una din antene este verticală în formă de evantaiu dirijată cu vârfurile către zenit, pentru a capta electricitatea negativă din atmosferă; cea care este orizontală, este dirijată către Sud, pentru a capta electricitate pozitivă.

Electricitatea în aer pare să fie cu dublă polaritate, după cum se vede la 2 nori electrizați, cari deplasându-se în sens contrar, dau naștere unei scântei (fulger) când distanța respectivă poate să fie străbătută de puternica lor diferență de potențial. Straturile de aer de densități diferite, nu sunt toate antrenate de aceeași viteză prin rotația pământului, ele se electrizează deci prin frecarea decalajului lor respectiv.

Aceste sunt considerațiunile ce l-au făcut pe inventator să așeze în atmosferă doi poli complet distincți și perfect izolați, al cărui pol pozitiv *S* (fig. 109) poate fi dirijat în direcțiunea Sudului, și a celuilalt negativ *P*, în direcțiunea zenitului. Fig. 109 arată schema montajului și a conexiunilor compuse după cum urmează: 1. dintr'o antenă dublă aeriană, montată pe stâlpi de 15—20 m înălțime. Această parte care se mai numește și aparat de captat, este format din vârfurile *P*, dispuse în evantai în vârful unei tije de oțel dirijate către zenit, pentru a capta curenții negativi ai atmosferei și dintr'o altă antenă orizontală a cărei săgeată este îndreptată către sud *S*, adică către equator, pentru a recepta curenții pozitivi. Aceste două părți dispuse în unghiu de 90°, formează cei doi poli al curentului aerian, a cărei diferență de potențial este suficientă pentru a permite utilizarea electricității atmosferice.

Fig. 109

French Patent # 551,882

Appareil Capteur de Courants Electriques dans L'Atmosphere



BREVET D'INVENTION.

XII. — Instruments de précision, électricité.

5. — PRODUCTION DE L'ÉLECTRICITÉ, MOTEURS ÉLECTRIQUES.

N° 551.882

Appareil capteur de courants électriques dans l'atmosphère.

M. JULES GUILLOT résidant en France (Tarn-et-Garonne).

Demandé le 27 septembre 1921, à 15^h 20^m, à Paris.
Délivré le 15 janvier 1923. — Publié le 16 avril 1923.
[Brevet d'invention dont la délivrance a été ajournée en exécution de l'art. 11 § 7 de la loi du 5 juillet 1844 modifiée par la loi du 7 avril 1902.]

Considérant le globe terrestre comme l'induit d'une dynamo, dont l'éther supraterrestre est l'inducteur, des courants électriques circulent dans l'intervalle c'est-à-dire dans la couche atmosphérique; l'inventeur capte au moyen de l'appareil décrit ci-dessous deux de ces courants parfaitement distincts et élimine les autres.

L'appareil comprend :

1° Le capteur aérien; 2° une série de parafoudres; 3° les régulateurs; 4° un tableau de résistances; 5° les aspirateurs; 6° les témoins.

1° Le capteur aérien monté sur un poteau est composé d'une pointe d'acier aimanté fixée par scellement sur un isolateur porcelaine et cerclée à sa base par une bague de bronze sur laquelle sont vissées 32 aiguilles de fer doux, le tout formant l'antenne d'un pôle. A côté et isolé de la première, formant le 2^e pôle, est fixée une pointe d'acier aimanté dans la position horizontale et dirigée vers le sud dont la base coudée à 45° est scellée sur un isolateur porcelaine. Cette pointe est également cerclée d'une bague de cuivre à encoches fig. 1.

2° Une série de 6 parafoudres à cornes entre chaque pôle et la terre et à écartements variés.

3° Un premier régulateur formé d'un appareil absolument semblable au capteur aérien, mais ayant les deux pôles superposés, et, opposé à la pointe verticale, un disque de cuivre relié à la terre. Opposé à la pointe horizontale, une roue à jante d'étain sur laquelle sont soudés alternativement 16 tubes composés eux-mêmes de deux métaux soudés : cuivre-plomb et fer-plomb. Cette roue est reliée à la terre par son pivot fig. 2.

Un deuxième régulateur formé d'appareils à déclanchement automatique au nombre de 3 par pôles et deux basculateurs également par pôles.

4° Un tableau de résistances composé de fils de maillechort en boudins de différentes sections, de tubes en verre contenant des poussières de cuivre, du charbon de cornue et de la fleur de soufre.

5° Les aspirateurs composés d'une boîte en bois sur chaque pôle, contenant un vase de porcelaine dans lequel par couches superposées et isolées au mica est placé du mercure, de l'étain, du charbon, du cuivre et du soufre, le tout traversé par une tige de cuivre.

6° Les témoins composés de lampes à incandescence ordinaires.

RÉSUMÉ.

Par la pointe au zénith et par la pointe au sud nous canalisons deux courants formant les deux pôles. On protège l'ensemble par des parafoudres. On régularise le débit par un régulateur semblable et par des appareils à déclanchement commandant chacun des résistances appropriées de la nature du courant nuisible dont ces' appareils sont chargés. Les courants épurés sont conduits aux témoins par des fils de cuivre ordinaire.

JULES GUILLOT,
Moissac (Tarn-et-Garonne).

XII. — Instruments de précision, électricité.

5. — Production de l'électricité, moteurs électriques.

N° 565.395

Dispositif combiné pour capter les courants électriques atmosphériques avec application immédiate.

M. Jules GUILLOT résidant en France (Allier).

Demandé le 6 avril 1923, à 11h 30m, à Paris.
Délivré le 7 novembre 1923. — Publié le 25 janvier 1924.

On sait que la terre, par sa propre constitution, sa rotation et son mouvement dans l'espace, fournit à elle seule l'électricité que l'on utilise et qui est en suspension dans l'atmosphère. Les courants électriques, qui s'échappent de la surface du globe, montent directement dans l'espace où les grandes masses sont accumulées vers l'équateur, par suite de la plus grande périphérie du globe.

Dans l'atmosphère, il y a deux pôles parfaitement distincts, c'est-à-dire que des nuages peuvent être électrisés, soit d'électricité positive ou négative; ceci, tout dans la nature le démontre, sans quoi, il serait difficile d'expliquer la provenance des éclairs qui se produisent entre les nuages et qui ne sont autres que des nuages chargés d'électricité contraire et qui s'amorcent entre eux par un trop grand rapprochement.

L'invention dont il s'agit concerne un dispositif formé d'un ensemble d'appareils aptes à la captation de ces courants atmosphériques.

Jusqu'à ce jour, toutes les recherches faites dans ce but ont été de capter dans l'atmosphère une seule catégorie de courants atmosphériques, c'est-à-dire, qu'on a réuni dans un même système de captation, deux pôles opposés et dont l'effet a été de se détruire ou de s'annuler l'un à l'autre laissant comme quantité que la différence du plus fort au plus faible.

Il sera donc facile de comprendre pourquoi, en considérant les deux pôles d'un courant atmosphérique comme à peu près égaux, il est presque impossible par certains temps de mesurer le potentiel avec la terre, du plus fort sur le plus faible subsistant et qui peut être positif ou négatif, suivant que le plus fort est de l'une ou de l'autre de ces polarités.

C'est sur cette base que toutes les recherches jusqu'à nos jours ont été faites et c'est pourquoi, il faut considérer que par tous les temps, entre les deux pôles captés dans l'atmosphère et non mélangés dans aucun des systèmes de captation, il est possible d'obtenir, en tension et en intensité, une puissance aussi considérable que l'on puisse désirer et qui sera mesurée entre les deux pôles captés séparément et toujours isolés l'un de l'autre jusqu'à leur utilisation.

Suivant l'invention, cette captation se fait par attraction dans l'atmosphère au moyen d'un amorçage des courants électriques, soit positif ou négatif, par une antenne à deux pointes absolument isolées l'une de l'autre, dont l'une tournée vers le zénith attire les couches d'électricité négative, et l'autre, tournée vers le sud, puise vers l'équateur, dans les masses groupées dans cette zone.

Ceci exposé et l'existence des courants électriques atmosphériques étant prouvée, il est

possible de les capter à la condition de disposer d'appareils spéciaux étudiés surtout pour jouer le rôle de régulateurs, attendu que la difficulté persistante rencontrée jusqu'alors pour réaliser la captation incombe aux grandes variations de tensions sous lesquelles les courants atmosphériques se présentent dans l'espace, pour chacun des pôles, et dont l'écoulement dans un poste de captation serait inévitablement funeste.

Le présent brevet sous sa forme de présentation doit donc couvrir, non pas le ou les dispositifs régulateurs qui sont prévus dans le système, car ils peuvent être conçus d'une façon toute différente et donner le même résultat, mais sur l'application raisonnée et le groupement d'appareils fonctionnant automatiquement et intervenant chacun comme relais d'influence variable pour limiter la tension des courants captés dans l'atmosphère à celle choisie pour utilisation.

Ces appareils ont un rôle assez connexe avec celui de trop-pleins sur un réservoir qui acheminent à l'extérieur l'excès de liquide; ici ces régulateurs détournent l'excès de tension des courants à la terre.

On peut encore assimiler ces régulateurs à des filtres car ils ont pour but de détourner du poste d'utilisation, des courants qui ne sont pas encore de nature connue mais que pour simplicité on appellera courants parasites ou anormaux.

Le brevet portera aussi sur le système de régulation des courants, appliqué à chacun des pôles, car il est reconnu que la forme et la tension des courants aux deux pôles ne sont pas équivalentes.

Le mode de captation par antenne spéciale à deux pointes orientées dans l'atmosphère, comme il sera indiqué ci-après, avec amorçage préalable pour l'écoulement des courants atmosphériques est aussi d'une grande importance.

Enfin la réception des courants atmosphériques se fait à l'endroit même de l'installation du poste; celui-ci peut être prévu en un lieu quelconque sans nécessiter d'altitude particulière, comme cela a été tenté dans des essais préconçus.

Sur les dessins ci-annexés auxquels on se réfère

La fig. 1 représente en élévation et en coupe partielle l'antenne seule, à deux pointes, surmontant un poteau d'élévation;

La fig. 2 est le plan de l'une des pointes, celle horizontale:

La fig. 3 montre schématiquement le tableau sur lequel sont montés les divers appareils ou accessoires qui jouent le rôle de régulateurs des tensions de courants.

La fig. 4 est un schéma de parafoudre, et

La fig. 5 un tableau de résistances.

Le dispositif nécessaire à la captation des courants atmosphériques est formé comme suit :

1° D'une antenne, fig. 1, formée de deux pointes dont l'une 1 est en acier, supportée par une bague de bronze 2 entourée d'une spirale 3 formant self; cette pointe est tournée vers le zénith pour attirer les couches d'électricité négative; l'autre pointe 4 comporte un cadre 5 de huit branches supportant des spirales de cuivre 6 et est tournée vers le sud pour puiser vers l'équateur dans les masses groupées dans cette zone. Pour l'utilisation de cette antenne il suffira qu'elle soit portée par un mât ou poteau de hauteur un peu supérieure à celle des habitations environnantes.

2° D'un tableau de parafoudre, fig. 4, formé de cornes de cuivre 7 servant à absorber les tros grosses décharges atmosphériques que par certains temps, il serait dangereux de laisser circuler dans les appareils régulateurs.

3° D'une table de deux systèmes symétriques de régulateurs, fig. 3, un pour chaque pôle, qui permet d'obtenir une régularisation assez grande dans les tensions des courants en absorbant automatiquement les surtensions dépassant la tension choisie pour l'utilisation désirée. Ces régulateurs sont représentés sur le dessin par les références R, R^1, R^2, R^3, R^4.

4° D'un tableau de résistance en communication avec les régulateurs, ces résistances sont formées de spirales de maillechor 8, de tubes 9 de verre remplis de poussière fine de charbon de cornue, de poudre d'aluminium, de soufre et de poussière fine de cuivre; enfin, deux appareils spéciaux 10 formant transformateurs et constitués de couches de métaux absorbant certains courants nuisibles ou anormaux.

5° D'une source auxiliaire d'énergie formée de piles 11 et de bobines Ruhmkorff 12 permettant d'obtenir dans l'antenne une attraction suffisante au moyen d'un dispositif de



réglage d'intensité qui, une fois amorcé, permet l'écoulement constant des courants de l'atmosphère dans le système.

En considérant la fig. 3 qui représente en quelque sorte le schéma d'installation du dispositif, la réception des courants électriques atmosphériques se fera de la façon indiquée ci-dessus, en produisant un amorçage de ces courants. Cet amorçage est fait en lançant dans le système qui est double pour répondre à chacun des pôles, le courant des piles 11 passant par les bobines 12 et se rendant à l'antenne.

Cet amorçage sera maintenu et réglé jusqu'à ce que l'écoulement des courants électriques atmosphériques se soit manifesté par l'allumage d'une ou plusieurs lampes L du tableau des résistances représenté en fig. 5 portant la prise d'utilisation.

Dès que l'allumage des lampes sera constaté on sera averti de la captation des courants atmosphériques et on pourra couper le courant des piles d'amorçage. L'écoulement naturel et constant des courants captés se produira dans les appareils régulateurs de la table, fig. 3; ils seront régularisés en tension et en nature puis dirigés au tableau des lampes pour utilisation.

Il a été dit ci-dessus que les régulateurs R, etc., étaient prévus et conçus pour éliminer automatiquement à la terre les surtensions des courants captés ainsi que les courants anormaux qui ne peuvent encore être classés. mais que ces régulateurs pouvaient être remplacés par des appareils faisant le même office. Il n'y a donc pas lieu de les décrire en détail et de les revendiquer spécialement. L'avenir seul précisera si ces régulateurs doivent faire l'objet d'une protection propre pour l'application décrite ci-dessus.

RÉSUMÉ.

Dispositif combiné pour capter les courants électriques atmosphériques avec application immédiate, caractérisé :

1° En ce que l'organe de captation est une antenne à deux branches orientées différemment, l'une vertical avec self est tournée vers le zénith pour puiser les courants négatifs, l'autre horizontale comporte un plateau central avec enroulement de fil et est orientée vers le sud pour puiser les courants positifs; l'orientation des pointes restant fonction du lieu terrestre où se fait la captation des courants considérés.

2° En ce que l'écoulement des courants atmosphériques dans le système récepteur est subordonné à un amorçage qui consiste à lancer dans l'antenne un courant provenant d'une source auxiliaire, telle que des piles reliées à des bobines de Ruhmkorff.

3° En ce qu'un tableau parafoudre est interposé entre l'antenne ou organe de captation et le tableau des régulateurs pour préserver l'installation en éliminant à la terre les décharges brusques atmosphériques.

4° En ce que les régulateurs sont disposés suivant deux systèmes symétriques correspondant à chacun des pôles des courants atmosphériques.

J. GUILLOT.

Par procuration :

V. Prévost.

Parts List

Steel Rods, magnetic, 2
Insulator, porcelain
Ring, bronze
Rods, soft iron, 32
Ring, copper
Surge Protector
Disk, copper
Ring, tin
Tubes, steel
Rx Cu-Pb, Fe-Pb
Breakers, automatic
Resistances : Wire Mesh, Glass Tube. Cu, C, S powder
Vacuum Cleaners : Box, Jar, Mica &
Tube, copper;
Rx : Hg, Sn, C, Cu, S
Battery
Ignition Coil

Your Support Maintains this Service -- and Your Survival ...

The Civilization Kit

... It's Your Best Bet & Investment in Sustainable Humanity on Earth ...
Everything @ rexresearch.com, plus the Bonus Files CD !
<< $13, Postpaid Anywhere >> from :

Rex Research, POB 19250, Jean, NV 89019 USA

United States Patent [19]

Rogers, Sr.

[11] **4,292,804**

[45] **Oct. 6, 1981**

---

[54] **METHOD AND APPARATUS FOR OPERATING AN ENGINE ON COMPRESSED GAS**

[76] Inventor: **Leroy K. Rogers, Sr.,** #5 Capistrano Ct., Ft. Myers, Fla. 33908

[21] Appl. No.: **158,303**

[22] Filed: **Jun. 10, 1980**

[51] **Int. Cl.**^{3} **F15B 11/06**

[52] **U.S. Cl.** **60/407**; 91/187; 91/275

[58] **Field of Search** 60/407, 412; 91/187, 91/275, 364

[56] **References Cited**

U.S. PATENT DOCUMENTS

3,881,399	5/1975	Sagi et al.	91/187 X
3,885,387	5/1975	Simington	60/407 X
4,018,050	4/1977	Murphy	60/412 X

Primary Examiner—Allen M. Ostrager
Attorney, Agent, or Firm—Burns, Doane, Swecker & Mathis

[57] **ABSTRACT**

The present invention relates to a method and apparatus for operating an engine having a cylinder and a piston reciprocable therein on compressed gas. The apparatus comprises a source of compressed gas connected to a distributor which distributes the compressed gas to the cylinder. A valve is provided to selectively admit compressed gas to the cylinder when the piston is in an approximately top dead center position. In one embodiment of the present invention the timing of the opening of the valve is advanced such that the compressed gas is admitted to the cylinder progressively further before the top dead center position of the piston as the speed of the engine increases. In a further embodiment of the present invention a valve actuator is provided which increases the length of time over which the valve remains open to admit compressed gas to the cylinder as the speed of the engine increases. A still further embodiment of the present invention relates to an apparatus for adapting a conventional internal combustion engine for operation on compressed gas.

22 Claims, 8 Drawing Figures





FIG. 1

FIG. 6


94
85
93
92
53
91
96
55
85

FIG. 7


67
49
47
45
51
67
43
43
99
85
53
95
101
102
6
85
97
6
91
41
92
93
94
96
55


61
43
59
43
67
57
65
53
65
67
67
43
43

FIG. 3


47
45
49
51
59
63
60
65
61
3
3
67
43
65
65
43
41
53
55
57

FIG. 2

FIG. 5


85
69
53
83
73
71
85

FIG. 4


67
45
47
67
43
71
49
69
85
43
85
75
5
5
83
81
73
77
72
53
79
87
89
55

FIG. 6


153
155
141
135
143
140
141
137
149
129
149
127
147
145
157

METHOD AND APPARATUS FOR OPERATING AN ENGINE ON COMPRESSED GAS

BACKGROUND AND SUMMARY OF THE PRESENT INVENTION

The present invention relates to a method and apparatus for operating an engine using a compressed gas as the motive fluid. More particularly, the present invention relates to a apparatus for adapting a pre-existing internal combustion engine for operation on a compressed gas.

Air pollution is one of the most serious problems facing the world today. One of the major contributors to air pollution is ordinary internal combustion engine which are used in most motor vehicles today. Various devices, including many items mandated by legislation, have been proposed in an attempt to limit the pollutants which an internal combustion engine exhausts to the air. However, most of these devices have met with limited success and are often both prohibitively expensive and complex. A clean alternative to the internal combustion engine is needed to power vehicles and other machinery.

A compressed gas, preferably air, would provide an ideal motive fluid for a engine since it would eliminate the usual pollutants exhausted from an internal combustion engine. An apparatus for converting an internal combustion engine for operation on compressed air is disclosed in U.S. Pat. No. 3,885,387 issued May 27, 1975 to Simington. The Simington patent discloses an apparatus including a source of compressed air and a rotating valve actuator which opens and closes a plurality of mechanical poppet valves. The valves deliver compressed air in timed sequence to the cylinders of an engine through adapters located in the spark plug holes. However, the output speed of an engine of this type is limited by the speed of the mechanical valves and the fact that the length of time over which each of the valves remains open cannot be varied as the speed of the engine increases.

Another apparatus for converting an internal combustion engine for operation on steam or compressed air is disclosed in U.S. Pat. No. 4,102,130 issued July 25, 1978 to Stricklin. The Stricklin patent discloses a device which changes the valve timing of a conventional four stroke engine such that the intake and exhaust valves open once for every revolution of the engine instead of once every other revolution of the engine. A reversing valve is provided which delivers live steam or compressed air to the intake valves and is subsequently reversed to allow the exhaust valves to deliver the expanded steam or air to the atmosphere. A reversing valve of this type however does not provide a reliable apparatus for varying the amount of motive fluid injected into the cylinders when it is desired to increase the speed of the engine. Further, a device of the type disclosed in the Stricklin patent requires the use of multiple reversing valves if the cylinders in a multi-cylinder engine were to be fired sequentially.

Therefore, it is an object of the present invention to provide a reliable method and apparatus for operating an engine or converting an engine for operation with a compressed gas.

A further object of the present invention is to provide a method and apparatus which is effective to deliver a constantly increasing amount of compressed gas to an engine as the speed of the engine increases.

A still further object of the present invention is to provide a method and apparatus which will operate an engine using compressed gas at a speed sufficient to drive a conventional automobile at highway speeds.

It is still a further object of the present invention to provide a method and apparatus which is readily adaptable to a standard internal combustion engine to convert the internal combustion engine for operation with a compressed gas.

Another object of the invention is to provide a method and apparatus which utilizes cool expanded gas, exhausted from a compressed gas engine, to operate an air conditioning unit and/or an oil cooler.

These and other objects are realized by a method and apparatus according to the present invention for operating an engine having at least one cylinder and a reciprricating piston therein using compressed gas as a motive fluid. The apparatus includes a source of compressed gas and a distributor connected with the source of the compressed gas for distributing the compressed gas to the at least one cylinder. A valve is provided for admitting the compressed gas to the cylinder when the piston is in approximately a top dead center position within the cylinder. An exhaust is provided for exhausting the expanded gas from the cylinder as the piston returns to approximately the top dead center position.

In a preferred embodiment of the present invention a device is provided for varying the duration of each engine cycle over which the valve remains open to admit compressed gas to the cylinder dependent upon the speed of the engine. In a further preferred embodiment of the present invention, an apparatus for advancing the timing of the opening of the valve is arranged to admit the compressed gas to the cylinder progressively further before the top dead center position of the piston as the speed of the engine increases.

Further features of the present invention include a valve for controlling the amount of compressed gas admitted to the distributor. Also, a portion of the gas which has been expanded in the cylinder and exhausted through the exhaust valve is delivered to a compressor to be recompressed and returned to the source of compressed gas. A gear train is selectively engagable to drive the compressor at different operating speed depending upon the pressure maintained at the source of compressed air and/or the speed of the engine. Still further, a second portion of the exhaust gas is used to cool a lubricating fluid for the engine or to operate an air conditioning unit.

In a preferred embodiment of the present invention, the valve for admitting compressed gas to the cylinder is electrically actuated. The device for varying the duration of each engine cycle over which the intake valve remains open as the speed of the engine increase comprises a rotating element whose effective length increases as the speed of the engine increases such that a first contact on the rotating element is electrically connected to a second contact for a longer period of each engine cycle. The second contact actuates the valve whereby the valve remains in an open position for a longer period of each engine cycle as the speed of the engine increases.

Still further features of the present invention include an adaptor plate for supporting the distributor above an intake manifold of a conventional internal combustion engine after a carburetor has been removed to allow air to enter the cylinders of the engine through the intake manifold and conventional intake valves. Another adaptor plate is arranged over an exhaust passageway of the internal combustion engine to reduce the cross-sectional area of the exhaust passageway.

BRIEF DESCRIPTION OF THE DRAWINGS

Preferred embodiments of a method and apparatus for operating an engine according to the present invention will be described with reference to the accompanying drawings wherein like members bear like reference numerals and wherein:

FIG. 1 is a schematic representation of an apparatus according to the present invention arranged on an engine;

FIG. 2 is a side view of one embodiment of a valve actuator according to the present invention;

FIG. 3 is a cross-sectional view taken along the line 3—3 in FIG. 2;

FIG. 4 is a cross-sectional view of a second embodiment of a valve actuator according to the present invention;

FIG. 5 is a view taken along the line 5—5 in FIG. 4;

FIG. 6 is a cross-sectional view of a third embodiment of a valve actuator according to the present invention;

FIG. 7 is a view taken along the line 7—7 in FIG. 6;

FIG. 8 is a cross-sectional view of a gearing unit to drive a compressor according to the present invention.

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENTS

With reference to FIG. 1, an engine block **21** (shown in phantom) having two banks of cylinders with each bank including cylinders **20** having pistons **22** reciprocable therein (only one of which is shown in phantom) in a conventional manner. While the illustrated engine is a V-8 engine, it will be apparent that the present invention is applicable to an engine having any number of pistons and cylinders with the V-8 engine being utilized for illustration purposes only. A compressed gas tank **23** is provided to store a compressed gas at high pressure. It may also be desirable to include a small electric or gas compressor to provide compressed gas to supplement the compressed gas held in the tank **23**. In a preferred embodiment, the compressed gas is air which can be obtained from any suitable source.

A line **25** transports the gas withdrawn from the tank **23** when a conventional shut off valve **27** is open. In addition, a solenoid valve **29** preferably operated by a suitable key operated switch (not shown) for the engine is also arranged in the line **25**. In normal operation, the valve **27** is maintained open at all times with the solenoid valve **29** operating as a selective shut off valve to start and stop the engine **21** of the present invention.

A suitable regulating valve **31** is arranged downstream from the solenoid valve **29** and is connected by a linkage **33** to a throttle linkage **35** which is operator actuated by any suitable apparatus such as a foot pedal (not shown). The line **25** enters an end of a distributor **33** and is connected to an end of a pipe **35** which is closed at the other end. A plurality of holes, which are equal to the number of cylinders in the engine **21**, are provided on either side of the pipe **35** along the length of the pipe **35**.

When the present invention is used to adapt a conventional internal combustion engine for operation on compressed gas, an adaptor plate **36** is provided to support the distributor **33** in spaced relation from the usual intake opening in the intake manifold of the engine after a conventional carburetor has been removed. In this way, air is permitted to enter the internal combustion engine through the usual passageways and to be admitted to the cylinders through suitable intake valves (not shown). The adaptor plate **36** is secured to the engine block **21** and the distributor **33** by any suitable apparatus, e.g., bolts.

Each of the holes in the pipe **35** is connected in fluid-tight manner to a single line **37**. Each line **37** carries the compressed gas to a single cylinder **20**. In a preferred embodiment, each of the lines **37** is ½ inch high pressure plastic tubing attached through suitable connectors to the distributor **33** and the pipe **35**. Each of the lines **37** is connected to a valve **39** which is secured in an opening provided near the top of each of the cylinders **20**. In the case of a conversion of a standard internal combustion engine, the valves **39** can be conveniently screwed into a tapped hole in the cylinder **20** typically provided for a spark plug of the internal combustion engine. In a preferred embodiment, the valves **39** are solenoid actuated valves in order to provide a fast and reliable opening and closing of the valves **39**.

Each of the valves **39** is energized by a valve actuator **41** through one of a plurality of wires **43**. The valve actuator **41** is driven by a shaft of the engine similar to the drive for a conventional distributor of an internal combustion engine. That is, a shaft **55** of the valve actuator **41** is driven in synchronism with the engine **21** at one half the speed of the engine **21**.

A first embodiment of the valve actuator **41** (FIGS. 2 and 3) receives electrical power through a wire **45** which is energized in a suitable manner by a battery, and a coil if necessary (not shown) as is conventional in an internal combustion engine. The wire **45** is attached to a central post **47** by a nut **49**. The post **47** is connected to a conducting plate **51** arranged within a housing **53** for the valve actuator **41**. Within the housing **53**, the shaft **55** has an insulating element **57** secured to an end of the shaft **55** for co-rotation therewith when the shaft **55** is driven by the engine **21**. A first end of a flexible contact **59** is continuously biased against the conducting plate **51** to receive electricity from the battery or another suitable source. A second end of the contact **59** is connected to a conducting sleeve **60** which is in constant contact with a spring biased contact **61** which is arranged within the sleeve **60**. The contact **61** is biased by a spring **63** which urges the contact **61** towards a side wall of the housing **53**.

With reference to FIG. 3, a plurality of contacts **65** are spaced from one another and are arranged around the periphery of the housing **53** at the same level as the spring biased contact **61**. Each contact **65** is electrically connected to a post **67** which extends outside of the housing **53**. The number of contacts **65** is equal to the number of cylinders in the engine **21**. One of the wires **43**, which actuate the valves **39**, is secured to each of the posts **67**.

In operation, as the shaft **55** rotates in synchronism with the engine **21**, the insulating element **57** rotates and electricity is ultimately delivered to successive ones of the contacts **65** and wires **43** through the spring biased contact **61** and the flexible contact **59**. In this way, each of the electrical valves **39** is actuated and opened in the proper timed sequence to admit compressed gas to each of the cylinders **20** to drive the pistons **22** therein on a downward stroke.

The embodiment illustrated in FIGS. 2 and 3 is effective to actuate each of the valves 39 to remain open for a long enough period of time to admit sufficient compressed gas to each of the cylinders 20 of the engine 21 to drive the engine 21. The length of each of the contacts 65 around the periphery of the housing 53 is sufficient to permit the speed of the engine to be increased when desired by the operator by moving the throttle linkage 35 which actuates the linkage 33 to further open the regulating valve 31 to admit more compressed gas from the tank 23 to the distributor 33. However, it has been found that the amount of air admitted by the valves 39 when using the first embodiment of the valve actuator 41 (FIGS. 2 and 3) is substantially more than required to operate the engine 21 at an idling speed. Therefore, it may be desirable to provide a valve actuator 41 which is capable of varying the duration of each engine cycle over which the solenoid valves 39 are actuated, i.e., remain open to admit compressed gas, as the speed of the engine 21 is varied.

A second embodiment of a valve actuator 41 which is capable of varying the duration of each engine cycle over which each of the valves 39 remains open to admit compressed gas to the cylinders 20 dependent upon the speed of the engine 21 will be described with reference to FIGS. 4 and 5 wherein members corresponding to those of FIGS. 2 and 3 bear like reference numerals. The wire 45 from the electrical source is secured to the post 47 by the nut 49. The post 47 has a annular contact ring 69 electrically connected to an end of the post 47 and arranged within the housing 53. The shaft 55 rotates at one half the speed of the engine as in the embodiment of FIGS. 2 and 3.

At an upper end of the shaft 55, a splined section 71 slidably receives an insulating member 73. The splined section 71 of the shaft 55 positively holds the insulating member 73 for co-rotation therewith but permits the insulating member 73 to slide axially along the length of the splined section 71. Near the shaft 55, a conductive sleeve 72 is arranged in a bore 81 in an upper surface of the insulating element 73 generally parallel to the splined section 71. A contact 75, biased towards the annular contact ring 69 by a spring 77, is arranged within the conductive sleeve 72 in contact therewith. The conductive sleeve 72 also contacts a conductor 79 at a base of the bore 81.

The conductor 79 extends to the upper surface of the insulating element 73 near an outer periphery of the insulating element 73 where the conductor 79 is electrically connected to a flexible contact 83. The flexible contact 83 selectively engages a plurality of radial contacts 85 arranged on an upper inside surface of the housing 53. A weak spring 87 arranged around the splined section 71 engages a stop member 89 secured on the shaft 55 and the insulating element 73 to slightly bias the insulating element 73 towards the upper inside surface of the housing 53 to ensure contact between the flexible contact 83 and the upper inside surface of the housing 53. As best seen in FIG. 5, the radial contacts 85 on the upper inside surface of the housing 53 are arranged generally in the form of radial spokes extending from the center of the housing 53 with the number of contacts being equal to the number of cylinders 20 in the engine 21. The number of degrees covered by each of the radial contacts 85 gradually increases as the distance from the center of the upper inside surface of the housing 53 increases.

In operation of the device of FIGS. 4 and 5, as the shaft 55 rotates, electricity flows along a path through the wire 45 down through post 47 to the annular contact member 69 which is in constant contact with the spring biased contact 75. The electrical current passes through the conductive sleeve 72 to the conductor 79 and then to the flexible contact 83. As the flexible contact 83 rotates along with the insulating member 73 and the shaft 55, the tip of the flexible contact 83 successively engages each of the radial contacts 85 on the upper inside of the housing 53. As the speed of the shaft 55 increases, the insulating member 73 and the flexible contact 83 attached thereto move upwardly along the splined section 71 of the shaft 55 due to the radial component of the splines in the direction of rotation under the influence of centrifugal force. As the insulating member 73 moves upwardly, the flexible contact 83 is bent such that the tip of the contact 83 extends further radially outwardly from the center of the housing 53 (as seen in phantom lines in FIG. 4). In other words, the effective length of the flexible contact 83 increases as the speed of the engine 21 increases.

As the flexible contact 83 is bent and the tip of the contact 83 moves outwardly, the tip remains in contact with each of the radial contacts 85 for a longer period of each engine cycle due to the increased angular width of the radial contacts with increasing distance from the center of the housing 53. In this way, the length of time over which each of the valves 39 remains open is increased as the speed of the engine is increased. Thus, a larger quantity of compressed gas or air is injected into the cylinders as the speed increases. Conversely, as the speed decreases and the insulating member 73 moves downwardly along the splined section 71, a minimum quantity of air is injected into the cylinder due to the shorter length of the individual radial contact 85 which is in contact with the flexible contact 83. In this way, the amount of compressed gas that is used during idling of the engine 21 is at a minimum whereas the amount of compressed gas which is required to increase the speed of the engine 21 to a level suitable to drive a vehicle on a highway is readily available.

With reference to FIGS. 6 and 7, a third embodiment of a valve actuator 41 according to the present invention includes an arcuate insulating element 91 having a first end pivotally secured by any suitable device such as screw 92 to the shaft 55 for co-rotation with the shaft 55. The screw 92 is screwed into a tapped hole in the insulating element 91 such that a tab 94 at an end of the screw 92 engages a groove 96 provided in the shaft 55. In this way, the insulating element 91 positively rotates with the shaft 55. However, as the shaft 55 rotates faster, a second end 98 of the insulating element 91 is permitted to pivot outwardly under the influence of centrifugal force because of the groove 96 provided in the shaft 55. A spring 93 connected between the second end 98 of the element 91 and the shaft 55 urges the second end of the element 91 towards the center of the housing 53.

A contact 99 similar to the contact 59 (FIG. 2) is arranged such that one end of the contact 99 is in constant contact with the conducting plate 51 located centrally within the housing 53. The other end of the contact 99 engages a conductive sleeve 101 arranged in bore 102. A contact element 95 is arranged in the conductive sleeve 101 in constant contact with the sleeve 101. The bore 102 is arranged generally parallel to the shaft 55 near the second end of the arcuate insulating element **91**. The contact **95** is biased by a spring **97** towards the upper inside surface of the housing **53** for selective contact with each of the plurality of radial contacts **85** which increase in arc length towards the outer peripheral surface of the housing **53** (FIG. **6**).

In operation of the device of FIGS. **6** and **7**, as the shaft **55** rotates the arcuate insulating element **91** rotates with the shaft **55** and the second end **98** of the insulating element **91** tends to pivot about the shaft **55** due to centrifugal force. Thus, as the effective length of the contact **95** increases, i.e., as the arcuate insulating element **91** pivots further outwardly, the number of degrees of rotation over which the contact **95** is in contact with each of the radial contacts **85** on the upper inside surface of the housing **53** increases thereby permitting each of the valves **39** to remain open for a longer period of each engine cycle to admit more compressed gas to the respective cylinder **20** to further increase the speed of the engine **21**.

With reference to FIG. **1**, a mechanical advance linkage **104** which is connected to the throttle linkage **35**, advances the initiation of the opening of each valve **39** such that compressed gas is injected into the respective cylinder further before the piston **22** in the respective cylinder **20** reaches a top dead center position as the speed of the engine is increased by moving the throttle linkage **35**. The advance linkage **104** is similar to a conventional standard mechanical advance employed on an internal combustion engine. In other words, the linkage **104** varies the relationship between the angular positions of a point on the shaft **55** and a point on the housing **53** containing the contacts. Alternatively, a conventional vacuum advance could also be employed. By advancing the timing of the opening of the valves **39**, the speed of the engine can more easily be increased.

The operation of the engine cycle according to the present invention will now be described. The compressed gas injected into each cylinder of the engine **21** drives the respective piston **22** downward to drive a conventional crankshaft (not shown). The movement of the piston downwardly causes the compressed gas to expand rapidly and cool. As the piston **22** begins to move upwardly in the cylinder **20** a suitable exhaust valve (not shown) arranged to close an exhaust passageway is opened by any suitable apparatus. The expanded gas is then expelled through the exhaust passageway. As the piston **22** again begins to move downwardly a suitable intake valve opens to admit ambient air to the cylinder. The intake valve closes and the ambient air is compressed on the subsequent upward movement of the piston until the piston reaches approximately the top dead center position at which time the compressed gas is again injected into the cylinder **20** to drive the piston **22** downward and the cycle begins anew.

In the case of adapting a conventional internal combustion engine for operation on compressed gas, a plurality of plates **103** are preferably arranged over an end of the exhaust passageways in order to reduce the outlet size of the exhaust passageways of the conventional internal combustion engine. In the illustrated embodiment, a single plate having an opening in the center is bolted to the outside exhaust passageway on each bank of the V-8 engine while another single plate having two openings therein is arranged with one opening over each of the interior exhaust passageways on each bank of the V-8 engine. A line **105** is suitably attached to each of the adaptor places to carry the exhaust to an appropriate location. In a preferred embodiment, the exhaust lines **105** are 1½" plastic tubing.

In a preferred embodiment, the exhaust lines **105** of one bank of the V-8 engine are collected in a line **107** and fed to an inlet of a compressor **109**. The pressure of the exhaust gas emmanating from the engine **21** according to the present invention is approximately 25 p.s.i. In this way, the compressor **109** does not have to pull the exhaust into the compressor since the gas exhausted from the engine **21** is at a positive pressure. The positive pressure of the incoming fluid increases the efficiency and reduces wear on the compressor **109**. The exhaust gas is compressed in the compressor **109** and returned through a line **111** and a check valve **113** to the compressed gas storage tank **23**. The check valve **113** prevents the flow of compressed gas stored in the tank **23** back towards the compressor **109**.

A suitable pressure sensor **115** is arranged at an upper end of the tank **23** and sends a signal along a line **117** when the pressure exceeds a predetermined level and when the pressure drops below a predetermined level. The line **117** controls an electrically actuated clutch **119** disposed at a front end of the compressor **109**. The clutch **119** is operative to engage and disengage the compressor **109** from a drive pulley **121**. Also, the signal carried by the line **117** actuates a suitable valve **123** arranged on a compressor housing **125** to exhaust the air entering the compressor housing **125** from the line **107** when the clutch **119** has disengaged the compressor **109** from the drive pully **121**.

In a preferred embodiment, when the pressure is the tank **23** reaches approximately 600 p.s.i., the clutch **119** is disengaged and the compressor **109** is deactivated and the valve **123** is opened to exhaust the expanded gas delivered to the compressor **109** from the line **107** to the atmosphere. When the pressure within the tank **23** drops below approximately 500 p.s.i., the sensor **115** sends a signal to engage the clutch **119** and close the valve **123**, thereby operating the compressor **109** for supplying the tank **23** with compressed gas.

The pulley **121** which drives the compressor **109** through the clutch **119** is driven by a belt **127** which is driven by a pulley **129** which operates through a gear box **131**. With reference to FIGS. **1** and **8**, a second pulley **133** on the gear box is driven by a belt **135** from a pulley **137** arranged on a drive shaft **139** of the engine **21**. The pulley **137** drives a splined shaft **140** which has a first gear **141** and a second larger gear **143** arranged thereon for rotation with the splined shaft **140**. The splined shaft **140** permits axial movement of the gears **141** and **143** along the shaft **140**.

In normal operation (as seen in FIG. **8**), the first gear **141** engages a third gear **145** arranged on a shaft **147** which drives the pulley **129**. The shafts **140** and **147** are arranged in suitable bearings **149** arranged at each end thereof. When the speed of the engine **21** drops below a predetermined level, a suitable sensor **151** responsive to the speed of the drive shaft **139** of the engine **21** generates a signal which is transmitted through a line **153** to a solenoid actuator **155** arranged within the gear box **131**. The solenoid actuator **155** moves the first and second gears **141**, **143** axially along the splined shaft **140** to the right as seen in FIG. **8** such that the second, larger gear **143** engages a fourth smaller gear **157** which is arranged on the shaft **147**. The ratio of the second gear **143** to the fourth gear **157** is preferably approximately 3 to 1.

In this way, when the speed of the engine **21** drops below the predetermined level as sensed by the sensor **151** (which predetermined level is insufficient to drive the compressor **109** at a speed sufficient to generate the 500-600 pounds of pressure which is preferably in the tank **23**), the solenoid actuator **155** is energized to slide the gears **143**, **141** axially along the splined shaft **140** so that the second, larger gear **143** engages the fourth, smaller gear **157** to drive the pulley **129** and hence the compressor **109** at a higher rate of speed to generate the desired pressure. When the speed of the engine increases above the predetermined level, in a preferred embodiment approximately 1500 rpm, the solenoid actuator **155** is deactivated by the sensor **151** thereby moving the gears **143** and **141** to the left as seen in FIG. **8** such that the first gear **141** re-engages with the third gear **145** to effectuate a 1 to 1 ratio between the output shaft **139** of the engine **21** and the pulley **129**.

The other bank of the V-8 engine has its exhaust ports arranged with adapter plates **103** similar to those on the first bank. However, the exhaust from this bank of the engine **21** is not collected and circulated through the compressor **109**. In a preferred embodiment, a portion of the exhaust is collected in a line **159** and fed to an enlarged chamber **161**. A second fluid is fed through a line **163** into the chamber **161** to be cooled by the cool exhaust emmanating from the engine **21** in the line **159**. The second fluid in the line **163** may be either transmission fluid contained in a transmission associated with the engine **21** or a portion of the oil used to lubricate the engine **21**. A second portion of the exhaust from the second bank of the V-8 engine is removed from the line **159** in a line **165** and used as a working fluid in an air conditioning system or for any other suitable use.

It should be noted that the particular arrangement utilized for collecting and distributing the gas exhausted from the engine **21** would be determined by the use for which the engine is employed. In other words, it may be advantageous to rearrange the exhaust tubing such that a larger or smaller percentage of the exhaust is routed through the compressor **109**. It should also be noted that since the exhaust lines **105** are plastic tubing, a rearrangement of the lines for a different purpose is both simple and inexpensive.

In operation of the engine of the present invention, the engine **21** is started by energizing the solenoid valve **29** and any suitable starting device (not shown), e.g., a conventional electric starter as used on an internal combustion engine. Compressed gas from the full tank **23** flows through the line **25** and a variable amount of the compressed gas is admitted to the distributor **33** by controlling the regulator valve **31** through the linkage **33** and the operator actuated throttle linkage **35**. The compressed gas is distributed to each of the lines **37** which lead to the individual cylinders **20**. The compressed gas is admitted to each of the cylinders **20** in timed relationship to the position of the pistons within the cylinders by opening the valves **39** with the valve actuator **41**.

When it is desired to increase the speed of the engine, the operator moves the throttle linkage **35** which simultaneously admits a larger quantity of compressed gas to the distributor **33** from the tank **23** by further opening the regulator valve **31**. The timing of the valve actuator **41** is also advanced through the linkage **104**. Still further, as the speed of the engine **21** increases, the effective length of the rotating contact **83** (FIG. **4**) or **95** (FIG. **6**) increases thereby electrically contacting a wider portion of one of the stationary radial contacts **85** to cause each of the valves **39** to remain open for a longer period of each engine cycle to admit a larger quantity of compressed gas to each of the cylinders **20**.

As can be seen, the combination of the regulating valve **31**, the mechanical advance **104**, and the valve actuator **41**, combine to produce a compressed gas engine which is quickly and efficiently adaptable to various operating speeds. However, all three of the controls need not be employed simultaneously. For example, the mechanical advance **104** could be utilized without the benefit of one of the varying valve actuators **41** but the high speed operation of the engine may not be as efficient. By increasing the duration of each engine cycle over which each of the valves **39** remains open to admit compressed gas to each of the cylinders **20** as the speed increases, conservation of compressed gas during low speed operation and efficient high speed operation are both possible.

After the compressed gas admitted to the cylinder **20** has forced the piston **22** downwardly within the cylinder to drive the shaft **139** of the engine, the piston **22** moves upwardly within the cylinder **20** and forces the expanded gas out through a suitable exhaust valve (not shown) through the adapter plate **103** (if employed) and into the exhaust line **105**. The cool exhaust can then be collected in any suitable arrangement to be compressed and returned to the tank **23** or used for any desired purpose including use as a working fluid in an air conditioning system or as a coolant for oil.

When using the apparatus and method of the present invention to adapt a ordinary internal combustion engine for operation with compressed gas it can be seen that considerable savings in weight are achieved. For example, the ordinary cooling system including a radiator, fan, hoses, etc. can be eliminated since the compressed gas is cooled as it expands in the cylinder. In addition, there are no explosions within the cylinder to generate heat. Further reductions in weight are obtained by employing plastic tubing for the lines which carry the compressed gas between the distributor and the cylinders and for the exhaust lines. Once again, heavy tubing is not required since there is little or no heat generated by the engine of the present invention. In addition, the noise generated by an engine according to the present invention is considerably less than that generated by an ordinary internal combustion engine since there are no explosions taking place within the cylinders.

The principles of preferred embodiments of the present invention have been described in the foregoing specification. However, the invention which is intended to be protected is not to be construed as limited to the particular embodiments disclosed. The embodiments are to be regarded as illustrative rather than restrictive. Variations and changes may be made by others without departing from the spirit of the invention. Accordingly, it is expressly intended that all such variations and changes which fall within the spirit and the scope of the present invention as defined in the appended claims be embraced thereby.

What is claimed is:

1. An apparatus for operating an engine having at least one cylinder and a reciprocating piston therein comprising:

a source of compressed gas;

distributor means connected with the source of compressed gas for distributing the compressed gas to the at least one cylinder;

valve means for admitting the compressed gas to the at least one cylinder when the piston is in approximately a top dead center position within the cylinder;

altering means for increasing the duration of each engine cycle over which the valve means admits compressed gas to the at least one cylinder as the speed of the engine increases; and

exhaust means for exhausting gas as the piston subsequently approaches approximately the top dead center position.

2. The apparatus of claim 1 further comprising control means for controlling the amount of compressed gas admitted to the distributor means.

3. The apparatus of claim 1 wherein the valve means is a solenoid valve secured in an opening in the cylinder above the level of the piston at the top dead center position.

4. The apparatus of claims 1 or 2 further comprising means for advancing the timing of the valve means as the speed of the engine increases such that compressed gas is admitted progressively further before the top dead center position as the speed of the engine increases.

5. The apparatus of claim 4 wherein the means for advancing the timing comprises a mechanical linkage connected to an operator actuated accelerator linkage.

6. The apparatus of claim 1 wherein a portion of the gas exhausted through the exhaust means is compressed in a compressor driven by an output shaft of the engine and is returned to the source of compressed gas.

7. The apparatus of claim 1 wherein a portion of the gas exhausted through the exhaust means is used to cool transmission fluid for a transmission associated with the engine.

8. The apparatus of claim 1 wherein a portion of the gas exhausted through the exhaust means is used as a working fluid in an air conditioning system.

9. The apparatus of claim 6 further comprising first gearing means interposed between the output shaft of the engine and the compressor for increasing the speed at which the compressor is driven.

10. The apparatus of claim 6 further comprising clutch means attached to the compressor both for disengaging the compressor from the output shaft of the engine when a first predetermined pressure at the source of compressed gas is exceeded and for engaging the compressor with the output shaft of the engine when the pressure at the source of compressed gas drops below a second predetermined pressure.

11. The apparatus of claim 9 further comprising means for both disengaging the first gearing means when a predetermined speed of the engine is exceeded and engaging a second gearing means for driving the compressor at a speed slower than the first gearing means when the predetermined speed of the engine is exceeded.

12. The apparatus of claim 1 wherein the valve means is electrically actuated and wherein the altering means comprises:

a rotating member timed with the at least one cylinder and arranged within a housing;

first and second contacts arranged on a first end of the rotating member and on an inside surface of the housing, respectively;

means for increasing the distance of the first contact from the rotational axis of the rotating member as the speed of the engine increases such that the first contact moves radially outwardly within the housing; and

said second contact presenting a longer arc length to the first contact as the distance of the first contact from the rotational axis of the rotating member increases.

13. The apparatus of claim 12 wherein the rotating member comprises an arcuate arm and wherein the means for increasing the distance of the first contact comprises pivotally mounting a second end of the arcuate arm about the axis of rotation of the rotating member and spring means for biasing the first end of the arcuate arm towards a radially inward position whereby the first end of the arcuate arm pivots radially outwardly as the speed of the engine increases.

14. The apparatus of claim 12 wherein the rotating member is axially slidably received on a rotating shaft for co-rotation therewith, said shaft having splines with a radial component in the direction of rotation, and wherein the first contact comprises a flexible contact located on an upper surface of the rotating member, said flexible contact being biased against the inside surface of the housing which carries the second contacts whereby as the speed of the engine increases the rotating member is urged axially along the splined shaft towards the inside surface of the housing such that the flexible contact is forced radially outwardly along the inside surface.

15. The apparatus of claim 12 wherein the second contact comprises of radially extending conductor arranged on an upper inside surface of the housing, said conductor increasing in arc length as the conductor extends radially outwardly from a central portion of the housing.

16. An apparatus for adapting an internal combustion engine for operation with compressed gas, the internal combustion engine having at least one cylinder, a piston reciprocable within the at least one cylinder, intake and exhaust means disposed in the at least one cylinder, and a tapped hole in the at least one cylinder adapted to receive a spark plug, the apparatus comprising:

a source of compressed gas;

distributor means connected with the source of compressed gas for distributing the compressed gas to the at least one cylinder;

valve means arranged in the tapped hole for admitting the compressed gas to the at least one cylinder when the piston is in approximately a top dead center position within the cylinder; and

altering means for increasing the duration of each engine cycle over which the valve means remains open to admit the compressed gas as the speed of the engine increases.

17. An apparatus as in claim 16 further comprising first adapter plate means for supporting the distributor means above an intake manifold of the engine, which adaptor plate means allows ambient air to enter through the intake manifold.

18. The apparatus of claim 16 further comprising second adapter plate means for reducing the exit area of the exhaust means.

19. A method of operating an engine on compressed gas, said engine having at least one cylinder and a piston reciprocable therein comprising the steps of:

delivering compressed gas from a source to a distributor;

distributing the compressed gas to the at least one cylinder;

admitting compressed gas to the at least one cylinder through an intake valve when the piston is at approximately a top dad center position;

increasing the duration of each engine cycle over which compressed gas is admitted to the at least one cylinder as the engine speed increases; and

exhausting the remaining gas when the piston subsequently reaches approximately the top dead center position.

20. The method of claim **19** further comprising the step of controlling the amount of compressed gas which is delivered to the distributor.

21. The method of claim **19** further comprising the step of advancing the timing of the opening of the intake valve as the speed of the engine increases.

22. An apparatus for operating an engine having at least one cylinder and a piston reciprocable therein on compressed gas comprising:

a source of compressed gas;

distributor means connected with the source of compressed gas for distributing the compressed gas to the at least one cylinder;

electrically actuated valve means secured in an opening in the at least one cylinder for selectively admitting compressed gas to the at least one cylinder when the piston is in approximately a top dead center position; and

means for advancing the timing of the valve means as the speed of the engine increases whereby compressed gas is admitted progressively further before the top dead center position as the speed of the engine increases.

* * * * *

FortuneCity Get your free website today!
Web hosting Custom Email SiteBuilder
H&R BLOCK AT HOME™. Get It Right.℠ File for FREE ▸ H&R BLOCK At Home
Ads by Google Pipe Fittings Pipe Break Pipe Welder Acrylic Pipe

---

Goodbye Chemtrails, Hello Blue Skies!
The Do-It-Yourself Kit for Sky Repair

This web page reproduced with permission from
Ken Adachi of Educate_yourself organization
original page
Jan. 10. 2002

A couple of years ago, I was standing outside a restaurant on a sunny day in southern California showing Joanna Beck, wife of Dr. Bob Beck, just how simple it was to disperse clouds using The Visual Ray (http://educate-yourself.org/visualray21may0.html), a technique I learned from reading Trevor James Constable's book, *The Cosmic Pulse of Life*. After demonstrating the technique to her on a couple of smaller clouds, we worked together on evaporating a particular large cumulus cloud and noticed how the blueness of the sky was slightly darker where the large cloud had existed only a few minutes earlier, a result of intensified orgone energy accumulating in that area. Almost simultaneously, we wondered aloud whether a group of people could use this technique to break up chemtrails! I tried it a number of times on my own, but I couldn't get chemtrail 'clouds' to break up and disperse the same way normal clouds would and I wondered silently whether a *Cloudbuster*, a simple invention of Wilhelm Reich.to direct orgone energy in the atmosphere, could tackle the job.

Over the course of 35 years, Trevor Constable had modified Reich's original long pipe arrayed Cloudbuster down to a much smaller, compact, and simpler design that could 'make' or 'break' weather in any direction he chose: He could make rain or stop it; he could relieve drought and break up smog or create a dry spell and intensify smog conditions. It all depended on how you manipulated the atmospheric ether in a given area. Trevor discovered that it all depends on how you apply his modified Cloudbuster design to direct the *flow* of etheric energy. If you bottle up the etheric flow, or stymie its normal expansive and contractile pulse, you will get drought (and smog). If you release the etheric flow after being 'bottled up' or stuck during a dry spell, you will get torrential rains. There is likely no civilian on the face of this earth who has accumulated more expertise about weather engineering than Trevor James Constable

Don Croft

However, the hero of this article is **Don Croft** (zapper16@earthlink.net), a man who was led to Reich's work with orgone energy and Cloudbusters by another route entirely. Someone had directed Don to a web site (http://www.orgone.net) that discussed Reich's observations about orgone energy and how you could utilize Reich's inventions of the Orgone Accumulator (abbreviated "oracs") involving a much smaller design than the conventional oracs built by Reich using metal shavings, magnets, crystals, and epoxy or polyester resin. Don started to make cone shaped oracs using the above mentioned materials (and plastic funnels for the mold) and called them "Holy Hand Grenades" (HHG's) (http://educate-yourself.org/HHGconstruction10jan02.html). He also incorporated these ideas into his "terminator" zappers (contact me if interested: Editor@educate-yourself.org) .

"Holy Hand Grenades" Batman!

These things had the ability to focus life positive energy and break up areas of noxious energies or DOR, a word coined by Reich which means Deadly Orgone Energy. Don calls them orgone *generators* since they neutralize DOR and seem to only generate positive, life affirming energies. Don began planting these HHG's in outdoor locations near nuclear power plants and other (classified) areas of noxious, life depleting energies and started to have a definite effect on improving the energy fields radiating from these zones. Since he already was thinking about using the cloudbuster to try and break up chemtrails, Don took it a step further and combined a large version of his HHG with a cloudbuster utilizing rigid copper pipes and a 2 gallon plastic bucket to hold the whole enchilada together. This modification of Reich's Cloudbuster is a unique and original design idea of Don's and produces some rather special effects.

He set up his combo orac/cloudbuster outside on a chemtrail overcast day with the pipes pointing straight up and sure enough, after a while, the chemtrails started to break up revealing blue sky above. The longer he left the orac/CB in place, the clearer the sky got , eventually covering an area out to 90 miles. He later improved the orac design and got the coverage to extend out to 120 miles.

Don had contacted me by E mail last year and was sending me reports of his success with the orac/CB both in this country and abroad. He had sent the instructions to an African man named Gert Botha living in Namibia who built a modified version of the device using locally scavenged materials (read "Africa's First Cloudsbuster" {http://educate-yourself.org/africasfirstcloudbusterjun01.html}and then see Gert's Report {http://educate-yourself.org/gertbothareportoct01.html}). Initially, Gert found that his Cloudbuster was having an effect on the incessant sand storms causing them to constantly change direction, but eventually he found that aiming the Cloudbuster south at an angle of 30 degrees to the horizon forced the sandstorms to stop. After being parked in this position for two months, his orac/CB brought on torrential rains for the first time in years in one of the driest regions of Africa.

Psychic Dames

Don gains many of his "insights" about his oracs and other devices through dowsing with his wife, Carol Derry, and his daughter, Nora, who both possess psychic ability, big time. His two psychic 'dames' also keep him one step ahead of the Bad Guys. Don is on the road most of the time and whenever the black op types try to move in on him, he learns about it before they do! The Bad Guys have their high tech advantages, but it seems the Universe takes care of its own when you're trying to do the Right Thing. In Don's case, he's been provided with exactly the sort of 'assistance' he needs (three cheers for Carol and Nora!).

Your Weekend Project

Complete instructions to make your own orac/CB or "ChemBuster" are included in this article. It will cost you about $150 US dollars if you buy all of the materials new, but if you're a scrounger, you can probably do it for the cost of the plastic resin. The instructions were written by Don Croft with a little bit of editing by another man who wished to remain anonymous. The pictures were mostly supplied by Don, but Mr. Anonymous threw in one photo of his own orac/CB breaking up chemtrails in the midwest, his neck of the woods. Anyone with modest do-it-yourself skills can build these devices, but be aware that an orac/CloudBuster is not a toy. It directs orgone energy, both the good type and the harmful DOR type.

If you don't educate yourself about a Cloudbusters and handle this thing carelessly, you could experience some discomfort, but not the sort of DOR that Reich's Cloudbuster design could accumulate. Trevor Constable told me first hand a story about the late Robert McCullough, Reich's friend and assistant in the Arizona desert in the 1950's. Dr Reich and Bob were running pioneering experiments with Reich's Cloudbuster when Bob had allowed a big (functioning) Cloudbuster to accidentally touch the side of his bare leg-which instantly paralyzed his leg and caused him excruciating pain. It took weeks to recover and Bob walked with a limp and had to use a cane for the rest of his life. You need to remember to discharge an active Cloudbuster before touching the pipes. Don recommends touching the base of the unit after touching the pipes to discharge any DOR energy. You could also lay the unit on its side on the ground and remove the pipes with a rubber glove. Laying the pipes on the bare earth should discharge them of any DOR.

So here's the edited reprint of Don's papers on Chemtrail Busting and the complete instructions for making your own "Chembuster" .

You can also review an earlier version of Don's Cloudbuster directions (http://educate-yourself.org/CBconstructioninfo1feb02.html) which he had sent to me in August, 2001. It includes some interesting uses for the CB not included in the directions given below. At the time, Don indicated that you could get 5 double pointed quartz crystals from "David" at **davdart@texas.net** for $7 including shipping, but I don't know if that contact is still valid. Give it a try.

How to Build A Cloudbuster to Disperse Chemtrails and Improve the Weather

By Don Croft

Definition of a contrail: A contrail occurs when a plane travels at a high altitude (about 30,000 ft. or more) and compresses the air into a water vapor or ice crystals through jet engines or the wing tips pushing through the air. This trail disappears after anywhere from a few seconds to 15 minutes, as the water vapor evaporates.

Definition of a chemtrail: The term "chemtrail" is a relatively new word, which appeared in the last few years along with the appearance of chemtrails. A chemtrail is very different from a contrail. At first a chemtrail might look a bit like a contrail. However, instead of disappearing like a contrail does, a chemtrail just keeps spreading out and forming a hazy cloud bank. These trails traverse the whole sky and stay for up to around five or even eight hours. They have been known to turn what was originally a clear blue sky into a grey haze. (Note: As of Nov 2001 there are already several dozen cloudbusters in seven countries, so if you see chemtrails that don't last anywhere near this long, there may already be a cloudbuster in the area).

It is believed chemtrails are composed at least in part by an oil based substance of unknown content that is actually being sprayed from jets on populated areas. It has also been found that some chemtrails contain red blood cells, aluminum, mycoplasma, viruses and other unknown biological components. There are many reports of increased diseases, especially respiratory ailments, in areas where there are chemtrails.

Chemtrails are often seen to be sprayed by white planes with no markings. Sometimes you will see these planes give off no contrail at all, and immediately after the same kind of plane in the same area will start to leave a thick chemtrail. At other times, distinct short gaps in chemtrails have been photographed, as though the plane ran out of chemicals and then had to start spraying with a new supply.

For information on Chemtrails see the sites listed at http://www.carnicom.com/contrails.htm

History of the Cloudbuster

The Wilhelm Reich cloudbuster (CB) was well known for its ability to create rain. But a problem existed with its continued use, in that the deadly orgone energy that it absorbed could in fact hurt the operator if it was not correctly "drained off". This "draining off" of deadly orgone energy was accomplished by 1. Connecting the cloudbuster to a body of running water (difficult) or 2. Connecting the cloudbuster output to an orgone accumulator. However, the orgone accumulator would soon become saturated with the deadly orgone energy which in turn caused more problems for the operator. So the cloudbuster, as good a technology as it is, has lain dormant for many years.

The Cloudbuster Re-Invented

By utilizing the research of Wilhelm Reich, we have created a cheap, portable and easy to build device that consistently destroys Chemtrails and heals the atmosphere. The "chembuster" is the answer to these ongoing attacks. Unlike the original cloudbuster, the CB changes the deadly orgone energy to good orgone energy and does NOT become saturated or dangerous to the operator. You can build one for about $150.



Join The Battle - Now!

It is human nature to sit on the sidelines and think that one person cannot change the things that are happening to our country. You now have no excuse for inaction. For a few dollars and a few hours of your time YOU can make a difference.

A properly constructed CB unit should be able to greatly reduce the effects of chemtrails for about 45 miles in all directions (90 mile diameter) from the unit. If used with Slim Spurling's environmental tools, and a few extra crystals, the diameter can be increased to about 120 miles in all directions.

With this device a mere few hundred concerned citizens can SHUT DOWN the multi-billion dollar chemtrail program. The chembuster cannot do any damage. It can only help and heal. Its up to you to join the fight to save America.

Chembuster Construction Details



Cloudbuster Materials



Set pipes in bottom spacer



Middle Plywood Spacer

CLOUDBUSTER DIRECTIONS

BUCKET: Base: 9" in dia., 9" deep. I use two-gallon plastic buckets from the Home Depot paint department, but two-gallon food buckets, available from restaurants, or two-gallon spackle buckets from drywall contractors are fine. Leave the buckets on, as the handles make it easier to move the finished cloudbuster.

COPPER PIPES: Six standard Type M, 1" copper pipes, 6' long, open at one end, the capped ends submerged to within an inch or so of the bottom of the bucket before casting. For portability and shipping, you can use 12” sections of pipe in the base, adding five-foot lengths by putting couplers between the 12” and five-foot pieces. You won’t need to buy as much copper pipe this way, too.

CRYSTALS: I glued a double-terminated (two pointed ends) quartz crystal, about 2" long, into a .75” section of garden hose, (or use electrical tape) then, glue to the inside of each of the six copper end caps, pointing in the same direction as the pipe will be after the cap is glued on. I use 'Goop' glue. Tape, or solder around the cap where it joins the pipe to prevent resin from leaking into the cap during casting. (Note) Another option is to add one citrine gemstone to each pipe before adding the crystal, this smoothes the CB’s energy and helps to transmute negative energies. However, citrine does not seem to make the CB any more effective at eliminating chemtrails.

METAL PARTICLES: Get some metal particles from a machine shop, recycling yard or a place where they saw a lot of aluminum (sign shops and aluminum fabrication shops are good places to look). I use aluminum for weight considerations, but ANY metal will do. Very fine particles (such as filings from a key-making machine) aren’t quite as good as ones that will easily go through a ½” screen are okay. There really is a wide margin of suitability! .
PLYWOOD: Template 1 - 3/4” exterior plywood is used to make the base for the copper endcaps/pipes. I arrange the six pipes evenly around a 2 1/2” radius circle, which makes the pipes 2 1/2” apart on centers. A flat, 1 1/4” auger bit drills a suitable hole for each end cap.

Template 2 - Make another piece to fit inside the rim of the bucket. Remember to cut a section away so you can fit your fingers under it to remove it from the bucket. This piece is not part of the finished CB, just used to get the spacing for the pipes right during construction. Cut the holes in this with a 1 1/8” flat bit so that it will fit well over the six pipes. This piece will hold the pipes in position while the second batch of resin hardens.

Template 3 - I make a circular plywood spacer for the top ends of the pipes, 4” radius with 1 1/8” holes on the same 2 1/2” radius circles for the pipe ends. This keeps the pipes parallel with each other and fairly rigid.


CLOUDBUSTER TEMPLATE
THIS EDGE ALLOWS YOU TO PUT THE TEMPLATE IN & TAKE IT OUT OF THE BUCKET RIM DURING CONST.
RIM OF BUCKET
TOP OF PIPES
1 1/8"
1 1/4"
TO FIT ENDCAPS
BOTTOM
BOTTOM RIM TOP
BOTTOM AND TOP OF PIPES
THIS PATTERN IS MADE ACCORDING TO THE 2-GALLON HOME DEPOT BUCKET ($2)

Not to scale Widest circle is 9 1/8”

RESIN: I use polyester resin (used to build fiberglass boats) but epoxy also works, as does envirotech resin from www.eti-usa.com (this sets up very quickly, so you need to be proficient with it). (If you are going to construct many of these units, try to purchase your resin in 5 gallon buckets over the internet, possibly from a surfboard or boat manufacturing supply company. Home depot gets $24 per gallon for resin)

On a level surface, pour an inch or so of catalyzed resin into the bottom of the bucket and stir in metal particles until the surface is uniform and flat. CAUTION: Resin fumes are flammable; use in a warm, but well ventilated area.

The ratio that seems to work is approx. one part resin to one part metal particles.
Put the base Template 1 onto that before it hardens, so that it just touches the surface and doesn't

sink in much. Pour a half gallon of catalyzed resin into the bucket after the six pipes are set into the holes in the base template. Use the dowel to stir in handfuls of metal particles in the same ratio as before. Note that the wood Template 1 should not be pushed down to the bottom of the bucket with the resin squishing over the top.

Carefully move the Template 2 down on to the six pipes until it is snugly within the rim of the bucket. Put the top Template 3 onto the top of the pipes and move them until the pipes are parallel. After the resin has hardened, remove the second template and set it aside. This is only used during construction, as I mentioned.

You can finish off putting the resin/metal mixture in now in two stages if you want, up to within a half inch of the rim of the bucket. Now it’s finished (wait until it hardens before you move it. You will actually use about one gallon of metal shavings and 1 ½ gal. Of resin.

A MONEY SAVING SUGGESTION, ALSO FOR BETTER PORTABILITY:

Cut six pipes, 12" long, and put the crystals/endcaps on them for the base. Buy six coupler joints which allow a pipe to come into them from both directions and stop at the middle. This allows you to make the rest of the pipe assembly from three pipes, 10' long, cut in half. The finished product leaves you with only one piece of pipe, four feet long leftover.

When positioning the 12" pipes for pouring the second layer of mix, temporarily tape the top ends of the 12" pipes so no metal particles are dropped in them by mistake.

After the mix is made, take off the tape and push the rim plywood piece down onto the pipes so that it fits into the rim of the bucket.

Put the spacers (soldered if desired), then the 5' pipes onto the 12" base pipes, then put the third (top) plywood piece onto the 5’ copper pipes.

The pipes will look skewed, most likely, so just twist the top plywood piece around until the pipes line up parallel. As you do that, the rim plywood piece will move around. You need to do this expeditiously, though not in a hurry, so that the resin doesn't harden before you're done.

We experimented with 5' extensions to the pipes to increase the range. It had a strong effect on the moon and on the upper atmosphere of the planet for hundreds of miles. We also apparently shut down the weather warfare facility under Homestead Air Force Base by leaving the extended cloudbuster pointing at the dead orgone field above it for a week.

We found that we don't need to point it in any particular direction in order to clear the atmosphere of bad orgone, and the longer it's left standing, the nicer it feels for a longer distance from the cloudbuster (many miles). We just stand it on its bottom, pointing straight up. We did once eliminate a belt of smog which was just off the coast by aiming at it for a few minutes, so direction can be a factor.

Cloudbusters destroy chemtrails consistently. It may take a few days for your cloudbuster to activate the environment enough to do this, but after that point the spew will disappear within seconds of leaving the UN jets and dissipated trails that drift within range of the cloudbuster will also disperse, but more slowly. The ones that are made up of solids take longer to dissipate, but we’ve found that these only make up about 10% or so of the spewing episodes.

Dr. Reich's cloudbusters were extremely dangerous when in operation since he had no orgone generator attached to them. Bad orgone does carry a charge which can quickly drain one's life force away when it's concentrated in one spot. It's similar to a strong positively charges static electrical field. When cloudcover is unproductive or unbalanced (too much lightning, for instance, or too much rain) the cloudbuster busts it up.

It also may help stop drought. Overall, it just balances the weather, I think it sort of mediates between the ground and the atmosphere somehow. The one in Namibia, Africa finally brought heavy rain to the desert there. It happened 9/5/01, and continued for several days. Gert, the fellow who made the cloudbuster and reported the occurrence, told me that this had simply never happened in the Namib desert before to the best of anyone's knowledge. It's arguably the driest region on the planet.

WARNING: If you touch the pipes when they're drawing in strong unbalanced or dead orgone and don't put your hand on the base after that, you may experience headaches, even into the next day, as a friend of ours did recently.

Mind you that our efforts, though somewhat pioneering, should be seen mainly as a springboard for further developments rather than the last word.

SUGGESTION: If you want even more rain, try putting water on top of the material in the bucket and/or hosing down the whole apparatus daily. In freezing climates, cover the top of the six pipes so water can't freeze and shatter the crystals. The CB appears to effect chemtrails equally well whether it's placed indoors or out. Up to seven crystals can be placed in each pipe to improve performance.

CB plowing through chemtrails in the midwest

Additional Information from Ken Adachi

Concering discharge of a CB. The origanl CB as built by Reich could channel both positive orgone and negative DOR and DOR is the problem when touching the pipes. Don Croft's modification for all practical purposes eliminates 99% of the potential dangers of DOR , but he does report that some people have gotten a headache by touching the pipes of an active unit (meaning it's been set up outdoors for a few days and pointing up) without grounding the energy by touching the base of the unit where the orac is located.

Concerning rain making. You don't have to do anything special. Simply set the unit up and give it a few days or a couple of weeks. One technique found to work was to pour water onto the base of the pipes (not into the pipes) and allow it to puddle on the top of the orac (encased in resin within the bucket). Orgone has a tremendous affinity for water and the presence of water on the orac seems to stimulate the production of rain clouds.

Below is Don Croft's chat list for the chembuster CB, HHgs info, etc. Very active site with many fascinating postings. You can read all of the previously posted messages about the success others have been having with Don's CB ref. breaking chemtrails and producing rain, etc.. Maybe you could post it to the Energy 2000 chat list and gain their attention faster than I.

cloudbuster newsgroup yahoo website

Anyone can read the previously posted messages. If you want to join and contribute to the chat, you have to agree to either be in the process of building a CB or have already built one. He doesn't want armchair 'experimenters' spouting off without hands-on experience. I can understand that.

Free Newsletter:

All information posted on this web site is the opinion of the author and is provided for educational purposes only. It is not to be construed as medical advice. Only a licensed medical doctor can legally offer medical advice in the United States. Consult the healer of your choice for medical care and advice.

Educate-Yourself

The Freedom of Knowledge, The Power of Thought

Further URL Links for further and related subjects at Educate yourself organization

Current News | Introduction | Colloidal Silver | Chemtrails | Emerging Diseases | Forbidden Cures | Immunity Boosting
Nutrition | Mind-Body Connection | Ozone | Bioelectrification | Story on Drugs | Vaccine Dangers | Newsletter | Links
Coming Attractions | New World Order | NWO News | Pam Schuffert | Reports From Peru | Phil Schneider | Al Bielek
Trevor James Constable | Mind Control | Brice Taylor | Ted Gunderson | Free Energy | Membership | Help | Discussion
Light Therapy | 2003 | Anna Hayes | Gary Wade | Tone Generator | Home | Contact Us | Products | Search | Letters

© Copyright 2002 Educate-Yourself.org All Rights Reserved.

Send any questions or comments to Educate-Yourself

New Information is being added to this website constantly. You may wish to bookmark it now.

Some additional notes and info from Graham Snook another cloudbuster builder

graham snook

Here are some photos of cloud busters The following photograph of a cloudbuster and is made of wood and plastic pipes, this is not my best subject i can make things but putting it down on paper is a problem for me, so here we go

They are 16 tubes 1"1/2 inch wide set in a wooden box with an accumulator section at the bottom where the end has two pipes just fit in the end, one pipe has a water pipe fitted the comes from the water mains and runs when in use it works well and the pond is full of life and i site around the pond for hours gives me a nice feeling as well as busting clouds and moving weather fronts away, its not a good idea to keep it on for long periods you can rewrite this if you wish i hope you get the idea of this type of cloud buster.

This cloud buster is of metal construction and has three metal pipes with the end sealed up and four slots cut in the pipe about four inch from the end or so about 1 inch wide by 8 inch then you make the end into a capacitor Cut some thick plastic the stuff used under concrete you can get it from the builders merchants, and then get some aluminium foil at the end wrap a piece of plastic round to cover the slots that you have cut in the ends then aluminium foil then plastic and keep going until you do this about 20 time then wrap it in duct tape to keep it all together make sure its tight the one in the photo can turn 360 degrees and move up or down its also can change a weather front over 1000 miles the tubes are insulated from the mount as well



A bit of a close up of the cloud busters if you need and more info let me know





all the best graham snook

☐

Subscribe to energy2000

enter email address YAHOO! Groups Join Now!

Powered by groups.yahoo.com

LINKS

Experiments in non conventional energy CD
click for ordering details here

ENERGY 2000

Powered by FortuneCity,
Get your free website today!
FortuneCity
web hosting • domain names
web design • online games

Metaphysical Power Tools
Advanced Radionics Orgone Magick Life Force Energy Technologies
www.Metaphysical-Tools.com/

Don Croft Zapper
Don's Best Selling Zapper is Now On Sale.
YourHealthByDesign.com

Energy You Can FEEL
Reiki Orgone Generators make energy that you can FEEL + EMF Protection
ReikiOrgone.com

Session 25 : **Electrodynamic Tethers**

Electrodynamic tethers are long, thin conductive wires deployed in space that can be used to generate power by removing kinetic energy from their orbital motion, or to produce thrust when adding energy from an on-board source. In either case, the frictional or thrust force, is produced electrodynamically, through the interaction between moving charges and magnetic fields. From here, we notice that the application of electrodynamic tethers is restricted to celestial objects that have a non-zero magnetic field and ionospheric plasma (e.g., Earth, Jupiter, Saturn, etc, not the moon or Mercury, etc).

The fundamental aspect of tethers is that, as looked from a reference frame moving at some velocity $\vec{v}$ with respect to a fixed frame (for example, an object in orbit moving with respect to the earth), an (EFM) induced electric field will be generated,

$$\vec{E}' = \vec{E} + \vec{v} \times \vec{B} \tag{1}$$

Where $\vec{E}$ and $\vec{E}'$ are the electric fields in the stationary and moving frames, respectively. There is magnetic field $\vec{B}$. The orbital situation is depicted in the figure, where there is no electric field in the stationary frame, $\vec{E} = 0$.



From here, the induced EMF (E_m) will be just the product of the magnitude of the velocity vector and the "horizontal" component of the magnetic field, $E_m = vB_H$. Assuming an elevation β of the magnetic field with respect to the horizontal, and a magnetic co-latitude of θ_m, we can write this field as,

$$E_m = vB_0 \sin\theta_m \cos\beta \tag{2}$$

where B_0 is the local magnitude of the magnetic field. Since in general the orbit will be inclined by an angle i, both the elevation and col-latitude will change and in consequence the magnitude of the E_m field will change over time.





As an example of the magnitude of E_m, consider a tether in a 300 km circular orbit. At this altitude, the orbital velocity is about 7700 m/s with a baseline field of $B_0 \sim 2.6 \times 10^{-5}$ Tesla. We then get $E_m \sim vB_0 \approx 200$ V/km. If the tether is aligned in the direction of the field $\vec{E}'$, then a potential of $V_m = 4$ kV will be generated from end to end of a 20 km long tether. In principle, one could make use of this (non-constant) voltage source to generate power.

Tethers as Power Generators

In this case, we have a spacecraft deploying an insulated tether "upwards" as shown in the figure. We assume the tether moves with a velocity $\vec{v}$ under a perpendicular magnetic field $\vec{B}$. The tether has length ℓ and a corresponding resistance R_T.



As the tether moves, we have a field $E_m = vB$ that will generate an "open circuit" voltage $V_{oc} = vB\ell$. If there is a load resistance R_L in series, the a (positive) current will flow, as ionospheric electrons are collected on an exposed anode at the top of the tether,

$$I = \frac{V_{oc} - \Delta V}{R_T + R_L} \tag{3}$$

where ΔV is the (relatively small) total potential drop due to plasma sheaths at the anode and cathode. To complete the circuit, a cathode releases the electrons at the bottom of the tether. Given this current flow, electrical power will be generated at the load,

$$P = I^2 R_L = \left(\frac{V_{oc} - \Delta V}{R_T + R_L}\right)^2 R_L \tag{4}$$

We observe that the generated power is both zero when the load resistance is either zero or ∞. This means there is an optimum resistance that will yield maximum power. To find this, we differentiate Eq. (4) and set it to zero, therefore,

$$P_{max} = \frac{(V_{oc} - \Delta V)^2}{4R_T} \qquad \text{which occurs when} \qquad R_L = R_T \tag{5}$$

The efficiency of this power-generating tether can be defined as,

$$\eta_g \;=\; \frac{P}{IV_{oc}} \;=\; \frac{I^2R_L}{IV_{oc}} \;=\; \frac{R_L}{R_T+R_L}\left(1-\frac{\Delta V}{V_{oc}}\right) \tag{6}$$

We can easily verify that for maximum power generation, the efficiency is $\eta_g \approx 0.5$. Ideally, we would like $R_L \gg R_T$ for maximum efficiency, but then we get lower power.

We can also verify that the input power IV_{oc} is identical to the rate of change of the electrodynamic drag work (force $\vec{F}$, force density $\vec{f}$),

$$\dot{W} \;=\; \vec{F}\cdot\vec{v} \;=\; \int \vec{f}\cdot\vec{v}\,dV \;=\; \int \vec{j}\times\vec{B}\cdot\vec{v}\,dV \;=\; IB\ell v \;=\; IE_m\ell \;=\; IV_{oc} \tag{7}$$

Tethers as Thrusters

Now, we have a spacecraft that deploys the tether "downwards". In this case, the anode at the bottom collects electrons from the ionosphere. The E_m field will point also upwards, however, we now have an on-board power supply that forces the net (positive) current in the opposite direction, as shown.



Instead of removing energy from the orbit, this configuration will add energy, as the force density $\vec{f}=\vec{j}\times\vec{B}$ points in the direction of the velocity vector $\vec{v}$,

$$\vec{F} \;=\; \int \vec{f}\,dV \;=\; IB\ell\frac{\vec{v}}{v} \tag{8}$$

With the current give by,

$$I = \frac{V_s - \Delta V - E_m \ell}{R_T} \tag{9}$$

We could also write the magnitude of this force (thrust) as,

$$F = \frac{IBv\ell}{v} = \frac{IE_m\ell}{v} = \frac{\dot{W}}{v} \tag{10}$$

Therefore, the rate of work added to the orbit is,

$$\dot{W} = Fv \tag{11}$$

The efficiency of the tether as a thruster is,

$$\eta_t = \frac{\dot{W}}{IV_s} = \frac{IE_m\ell}{IV_s} = \frac{V_{oc}}{V_s} < 1 \tag{12}$$

It is then possible to use a tether both as a generator and a propellant-less thruster. In fact, since the tether can be used as a generator, an interesting question would be: what is the tether efficiency compared against a fuel cell? Fuel cells make use of some consumable (like propellant) to produce electric power. As an exercise, calculate the efficiency of a tether producing power when its drag is compensated by a thruster consuming propellant. This is a tether working as a fuel cell.

Tether Dynamics

As we have seen, it is important that the tether is oriented along the radial vector in its orbit for it to be used as an electrodynamic generator or thruster.





ℓ
θ
m_2
cm
$\ell_2 = \ell \frac{m_1}{m}$
$\ell_1 = \ell \frac{m_2}{m}$
m_1
$\Omega = \sqrt{\frac{\mu}{R^3}}$

We need to analyze the tether dynamics to verify that such alignment can be achieved without the use of complicated active control.

Referring to the schematic, we have a mass-less tether of length $\ell = \ell_1 + \ell_2$ with two point masses at its ends, such that $m_1 + m_2 = m$. Let us analyze the dynamics of m_2, assuming that the center of mass (cm) is orbiting at a radius R. There will be a centrifugal force acting on m_2 given by,

$$\frac{m_2 v^2}{R + \ell_2 \cos\theta} = \frac{m_2 v^2}{R\left(1 + \frac{\ell_2}{R}\cos\theta\right)} \tag{13}$$

which is balanced by a gravitational force,

$$\frac{m_2 \mu}{(R + \ell_2 \cos\theta)^2} = \frac{m_2 \mu}{R^2\left(1 + \frac{\ell_2}{R}\cos\theta\right)^2} \tag{14}$$

In addition, the orbital velocity is,

$$v = \Omega R\left(1 + \frac{\ell_2}{R}\cos\theta\right) \tag{15}$$

and since $\sqrt{\mu/R} = R\Omega$, then $\mu = R^3\Omega^2$. The net (upwards) force acting on m_2 is the difference between these two forces,

$$F_{net} = m_2\Omega^2 R\left(1 + \frac{\ell_2}{R}\cos\theta\right) - m_2\Omega^2 R\frac{1}{\left(1 + \frac{\ell_2}{R}\cos\theta\right)^2} \tag{16}$$

Even for a long wire, we have $\ell_2 \ll R$, therefore we can approximate,

$$\frac{1}{\left(1 + \frac{\ell_2}{R}\cos\theta\right)^2} \approx 1 - 2\frac{\ell_2}{R}\cos\theta$$

the net force on m_2 is then,

$$F_{net} = 3m_2\ell_2\Omega^2\cos\theta = 3\frac{m_1 m_2}{m}\ell\,\Omega^2\cos\theta \tag{17}$$

The projection of this force on the direction of the wire is the tension,

$$T = F\cos\theta \tag{18}$$

The tension on a 20 km tether for a mass of 100 kg would be 7.4 N, which is not a strong force enabling the use of light and thin wires. The projection of the net force in the orthogonal direction generates a torque,

$$\tau = -F\ell\sin\theta \qquad \text{and for small } \theta, \qquad \tau = -3\frac{m_1 m_2}{m}\ell^2\Omega^2\theta \tag{19}$$

It is the clear that the gravity gradient force gives a torque that goes in the opposite direction to the tether defection from the vertical and therefore the it tends to stabilize the tether in the direction favorable for its use as electrodynamic actuator.

Given its moment of inertia J, the tether rotational dynamics are described by,

$$J\frac{d\omega}{dt} = \tau \qquad \text{where} \qquad J = m_1\ell_1^2 + m_2\ell_2^2 = \frac{m_1 m_2}{m}\ell^2 \tag{20}$$

Combining Eq. (19) and Eq. (20), we get,

$$\ddot{\theta} + 3\,\Omega^2\theta = 0 \tag{21}$$

which means the tether will oscillate at a frequency,

$$f_\omega = \sqrt{3}\,\Omega \tag{22}$$

For example, at 500 km altitude, we have $\Omega \approx 10^{-3}$ rad/s, which corresponds to an orbital period of 94 minutes. The corresponding oscillation time for the tether would then be 54 minutes, which means we have a “lazy” oscillation. The dynamic analysis in the off-plane direction is somewhat more complicated, but yields an oscillation frequency in the same order, 2Ω.

MIT OpenCourseWare
http://ocw.mit.edu

16.522 Space Propulsion
Spring 2015

For information about citing these materials or our Terms of Use, visit: http://ocw.mit.edu/terms.

rexresearch.com

Paul BAUMANN

Testatika Generator

life.augmented INNOVATIVE SEMICONDUCTOR SOLUTIONS Digi-Key ELECTRONICS Learn More

Methernitha Group: CH-3517 Linden, Switzerland

Photo Gallery & Videos

Links:

Methernitha ~ http://www.methernitha.com
http://utenti.tripod.it/testatikmachine/
Paul E. Potter ~ http://website.lineone.net/~aarekhu/index.html

Hans Holzerr: Testatika Demonstration Notes

Paul Potter: Back-Engineered Testatika

P. Potter: Principle Experiment

Anonymous: Believe It or Not --- Here It is!

Cyril Smith: Testatika Generator and Over-Unity

Methernitha: The Research Work of Methernitha in the Field of the so-called Free Energy"

P. Potter: Transcript of Methernitha Testatika Video

Testatika Demonstration (4 August 1999)

Translation by Stefan Hartmann < harti@harti.com > & Hans Holzherr

From: Hans Holzherr
To: Stefan Hartmann

Recently, over 30 technicians and engineers (most of them retired) were allowed to visit the Methernitha group in Linden, Switzerland, where they witnessed a demo of the different Testatika machines.

Here is a report from Hans Holzherr from Switzerland who was present:

Hello Mr. Hartmann,

To your questions: > Have you seen live a machine with a load? If so, what load?

I am referring in the following to the model with the 50-cm diameter disks. This machine was already running when the visitors stepped into the room, and was not halted during the whole time --- we were there for about 1.5 hrs. As a first load a 1000-Watt lamp was connected for approximately 10 seconds whose brightness did NOT diminish --- the corresponding sequence on the Testatika film is just an effect of the camera aperture's automatic adjusting to the sudden brightness! The second load was a U-shaped heating element, that Mr.Baumann handed to me. It became so hot within one second that I had to put it down immediately! What was particularly impressive was that while he pulled back one of the contact wires (that was with the lamp, I believe), a 1-cm long arc appeared between the output electrode and the connecting wire for approximately one second. The apparatus was under a plexiglass hood. Near the base it had two holes which Baumann used to insert the contact wires to touch the output electrodes.

How do you think the high wattage is produced ?

Good question! I'd love to know the answer, too!

Did the disks slow down when a load was placed across the output electrodes ?

I did not notice that (nobody else did), but of course you tend to turn your look to 'where the action is' (the lamp etc.) The disks turned with 15 rpm, which is quite slow. The spin rate was regulated magnetically.

What general impression did you have ?

It was really impressive! One can hardly believe it, with this slow rotation. In any case, this cannot be explained in terms of bare electrostatics in the sense of the Wimshurst machine. The perforated sheets seem to have a key function... Beside the pick-up and the drive electrodes there are a number of small plexiglass blocks with glued-on perforated sheets, whose function is unknown.

As Adolf Schneider already mentioned, my colleague Bernhard XXX and I want to try to copy the principle experiment shown by Baumann --- without much hope to find anything extraordinary, though.

The device consists of a horizontal swiveling plexiglass arm with a small rectangular plexiglass plate at both ends glued to the lower side of the arm. The lower side of the arm is covered with perforated aluminum sheets (square holes), while the bottom of the plates is covered with brass wire mesh. Beneath each plate five additional plates are glued onto the base plate. There is also wire mesh between each pair of plates in the two blocks. From the mesh layer between the lowest plate and the base a wire goes to the two capacitors, which are connected in parallel . Baumann seized the arm with both hands and turned it about ten times back and forth (a full rotation was not possible, because the capacitors were in the way), then measured the DC voltage with a digital measuring instrument: 60 Volts. Then, as he short-circuited the condensers a loud crack could be heard. I don´t know if that already is an abnormal result...

On my question Baumann replied that with metal foil (instead of wire mesh) the device would not produce that effect.

For more information, Contact: leo@zelator.in-berlin.de

"Back-Engineered Testatika"

by

Paul E. Potter

http://website.lineone.net/~aarekhu/index.html

(Copyright 2000)

That the Swiss Methernitha group's Testatika machine is thought to be based on a Wimshurst electrostatic generator, is only a sparse approximation of the truth --- of the great multitude of electrostatic influence machines developed around the 1900's it more closely follows the charge-separation-and-collection system used by the 1898 Pidgeon machine [note 1] for its electrical circuit.

Its 50-per-disc steel grilles or 'gitter-grilles' are plainly unique to the Methernitha (see fig.1) but in principle follow on from previous research and patents for corrugated sectors which were found to be more efficient charge carriers [note 2] than flat ones, and from a similar example in more recent times of aluminium rods extending out like wheel spokes from an insulating hub of perspex [note 3].

Another unique function of these perforated grilles attached to the discs is how they induce charge from the rotating discs onto the special collecting pads, or 'tasten' antennae keys (which are also perforated --- so as to more readily pick up charge); for in a Wimshurst you had conductive brushes or rails of sharp points which actually touched the discs or were placed very close to them, but in the Methernitha the charge has to be made to traverse a parallel air-gap to the pads and for this purpose the metal gitter-grilles are so designed to create miniature eddy-currents of charged air which circulate in and out of the perforated metal's surface charges, and are more easily bounced out to the collecting pads. This process is categorised as VARIABLE CAPACITANCE electrostatic generation.

Careful note needs to be made of how the Methernitha uses its basically Pidgeon setup with regard to its neutralising rods (that equalise and stabilise the opposite charges --- see fig.2), and how charges are picked up from one area and accumulated at others, so that the polarities of charge are distributed correctly to specific areas on both discs [note 4].

And although there have been some fanciful claims, or misinformation, that it uses all sorts of radioactive materials to achieve its pulsed output I most strongly believe that the auxiliary electromagnetic circuit, that wraps itself around the rotating discs, portrays a simple electronic approach; afterall, who would use radium radioactive emission alongside leyden jar capacitors ! Indeed, the more you look into certain elements of its construction the more they point to three main eras of electronics development, the 1900's, the 1920's and the 1950/60's. The authentic Methernitha was designed and developed by purists who believed they had discovered a previously unknown electronic phenomenon, but they wanted to keep an integrity to the early pioneering days of the Pidgeon, Wimshurst and Holtz electrostatic machinery; they would not use such modern devices as transistors or IC chips (more's the pity) --- but they do use some pretty uncommon electronic engineering in their circuit [note 5].

Obviously, the electronics are in two parts; one --- the electrostatic generator and its particular technologies of how to direct what charge where, and two --- the very unique auxiliary electromagnetic circuit of inductances, capacitances and rectification that mobilises that 'static' electricity. To understand how they convert static energy into an electromotive force you would do well to go back to the earliest years of radio. From the pages of spark radio you soon appreciate just how important oscillation circuits and their valve rectifiers were, and moreover, how difficult it proved to engineer them. For although radio transmitters and receivers from the 1900's used resonating circuits their oscillations were controlled by sparks between two contacts and, of course, they were relatively inefficient. Not until the 1920's did the first electric current oscillations become an observable controlled phenomenon when someone coupled a rectifier valve, a capacitor, and a resistor together [note 6]. The early 1920's also saw the best era of experimentation and invention for novel devices that turned static energy into useable electromagnetic energy; it was in a 1921 patent that we see a German physicist Hermann Plauson describe in great detail his methods to convert static power, not only from rotary influence machines but also from balloons collecting atmospheric electricity up in the sky; and by using thermionic rectifiers, leyden jar capacitors and inductor coils he proposed a free-energy network that was to power the whole of Germany [note 7] ! The thermionic rectifier valve heralded a new era for radio and high voltage physics, and as it was then subjected to such a broad array of experiments and modifications to improve its efficiency so it paved the way for all sorts of new avenues in electronics. Indeed, with such a technical catalogue of similarities with what we see in the available photographs of Testatika it can be assumed without doubt that the horizontal glass tube which sits on top of the Methernitha machines is exactly what a home-made vacuum thermionic rectifying valve would look like; with its internal anode mesh-plate, surrounded by a coiled copper grid, fed by a glowing (heated) cathode wire running horizontally across its centre and capped by two black end-pieces, which are too big and bulbous to be mere end-caps and must surely be black rubber vacuum seals to seal the glass tube and the input/output wires [note 8].

With such a rectifier, some induction coils, and some leyden jar capacitors you have a circuit that oscillates, and that's what has to happen with a Methernitha, the electromagnetic circuit has to oscillate for it to work, and then the oscillations have to be rectified (or even modulated) so that the resulting single-pole pulses can be channeled through the big cans, which are basically high-efficiency transformers, and outputted as reduced voltage higher current DC pulses (see fig.3).

The precise components used to oscillate the primary oscillating circuit are, I believe, not to be seen in any of the available photographs, but there are various hints for their approximate whereabouts on the machine. Firstly, according to electronic design there should be a capacitor and coil configuration in close proximity to the rectifier. Well, from the picture "3KWREAR" can be seen the two long upright tubes which, according to those who have seen them first-hand, comprise a spirally turned aluminium strip (which indicates they are chokes [note 9]) inside a glass tube, inside the same sort of outer shielding that the big cans have (which indicates they are electrostatic shields), inside yet another glass tube, and are terminated at the top with a brass connecting rod which does a right-angled turn and passes into the side of the tower --- but only two-thirds up the height of the tower. These two assemblies must form a connection to the rectifier, because the rectifier is at the top of the tower, so why don't these electrostatically sensitive tubes extend all the way up to it ? Again, from the photographs of the rear and front of the Methernithas there is a wire that comes out of the tower's side wall at about 4 inches above the upright's brass terminals and this wire then passes through a short black tube and on to the rectifier valve. This, of course, would happen on both sides of the tower, enabling a connection to both ends of the rectifier. But why have this 4 inch gap of connections at the top of the tower ? Something is placed inside the top of the tower in this intermediate space which is very necessary to the circuit, and I think it must be the location of the capacitor/inductor configuration to oscillate the circuit. This (fig.4) is how I would see the inside of the top of the towers [note 10].

I've seen some of the patented inventions that rotate discs --- by using magnets (i.e., H.Rosenberg's permanent magnet excited rotational machine, US Patent # 3,411,027), and by utilising inscribed metalised discs (US Patent # 3,239,705 for instance), but there simply isn't enough room for these to be located in the Methernitha disc setup --- also, you don't want to interfere with the ES fields that zip around the revolving discs: From the reports of those who have seen the small machines working it appears their discs were rotated by small DC electric motors after they were hand-started, some re-wound with thinner wire (to presumably increase their torque) and powered directly from the discs' generated electricity --- but I have also seen how two discs can continue to rotate simply by careful placement of curved electrodes [note 11] which would act on the charges on the discs --- like the 3kw Testatica Distatica generators.

After reading through the many early accounts of electrostatic rotary machines, and some of the more recent ones, you can't help but be puzzled by the Methernitha's incredibly low rotational speed of just 60 rpm (and in the 1999 engineers report as low 15 rpm !). Most other early experimenters boasted up to 3000 rpm. J.G.Trump in his work on high voltage generation in space [note 12] spun his rotary machine at 10,000 rpm (to produce 433 Watts at 24 KV no less). One reason for this low speed might be to do with the close proximity of the 50 lamellas (gitter-grilles) on the discs at their inner ends, they are very close together, I think too close. Air, normally an insulator, breaks down and conducts at around 25-35 KV (this figure has been fairly constant from day-one of electrostatic machine experiments right through to the present day --- because air has a breakdown field strength of 3x106 volts/metre) and short-circuits the circuit. I feel that because this design of grilles is prone to short-circuiting at high voltages the Methernitha people have limited their rotational speed so as to ensure a low operating voltage --- of what I'd guesstimate to be only 12 to 24KV.

But, is this a waste of extra potential ? Not necessarily, for I don't think that the main power output comes solely from what the two counter-rotating discs supply.

There is, I believe, a far more important power generator --- the electron cascade generator, and the Methernitha has two of them, held inside the two horseshoe magnets, and providing the circuits to the magnets are made to oscillate at the right frequency at a high enough voltage then these metalised-perspex laminated blocks can enmass A MUCH LARGER AMOUNT OF ELECTRICITY THAN WHAT IS PUT INTO THEM.

This, perhaps, is the previously unknown electronic phenomenon that the Methernitha group have so zealously been trying to protect against unscrupulous entrepreneurs. But I would say that this copious supply of free energy is already known to the world --- it is not readily available - and its principles are not fully understood, as yet, but it is known about.

As the descriptions say (on the Testatika website), between the horseshoe magnet legs are four blocks of transparent 'plexiglass' type material alternated with copper and aluminium plates (that may or may not be perforated), in the sequence c-p-a-c-p-a-c-p-a-c-p-a (also see fig.6). And according to the Linden Experiment, where Paul Baumann induces a resonance of about 80-140 MHz in a coiled horseshoe and then has an aluminium-insulator-copper block moved between the horseshoe legs, a voltage could be taken off the plates of the block which measured 700 volts (DC presumably) [note 13]. This incredible phenomenon has never been replicated by any 'outside researcher', and is said to be the basis by which the Methernitha machine could be understood how to work [the clue, possibly, to this Principle Experiment may be variable-capacitance and dielectric-absorpsion].

But what, I hear you say, is an electron cascade... Well, it was only by chance, very recently, that I happened to listen to an audio tape by a Dr. Flanagan about crystal water; when I switched the tape over after the end of side one Dr. Flanagan then began talking about an electronic configuration that applied a high frequency, high voltage alternating field across an insulator --- that created what he called an electron cascade effect --- Yes, I thought, here is the answer to the Methernitha Machine.

The electron cascade or avalanche effect is where air molecules are accelerated to the device at such a high velocity that they collide with other molecules and atoms in the air to liberate new electrons which in turn also collide and liberate even more 'free electrons' from other air molecules (see fig.5), all of which become accelerated by the electric field, and an avalanche of electron-multiplications progresses throughout the whole immediate environment [note 14]. It's a chain reaction, and an entirely safe one, it happens in a more ferocious way in lightning strikes, and is a natural phenomenon. And, as in this case, the environment actually becomes part of the circuit [note 15] because the process is actually negatively-ionising the air surrounding the Methernitha machines, and that is why those who have been near these generators when working say the air around about them is cool and fresh [note 16].

In view of the fact that it's designers have chosen to wind insulated wire (which may or may not be bifilar) around the horseshoe metal it is likely that the horseshoes are used for some form of induction [note 17], it would also be very possible to draw directly from this part of the circuit the extra electric current produced from the electron cascade blocks, with suitable connections that might lead downward into the wooden base (where it is believed that an alternate layering of perforated metal plates and insulating plates - making up a large high-voltage storage capacitor - is located). This power could then be discharged as a pulsed output of high wattage, especially if the final output part of the electronic circuit is configured as a Pulse Forming Network of multiple sections of inductor / capacitor combinations [note 18].

The two big cans at the side, the big capacitors, are probably not highly technical (see fig.7), once the fundamental formula has been decided upon all models of a Testatika generator would follow a similar construction process. The written descriptions are a little contradictory but they seem to suggest a central input rod, or tube, connecting at the bottom of the cans to a stack of inter-linked pancake coils, that are wound secondary-outside primary-inside, fitted around a core of 6 hollow donut-ring magnets stacked in such a way with plastic spacers as to allow air gaps between them, and then finally the output of each can is a connection from the top coil of the secondaries of the pancake coils to a brass ring around the centre of the black plastic top lid --- and from the photographs can be seen a large diameter wire or tube [note 19] connecting that polarity's output terminal to the top lid's brass ring via a brass screw terminal. I would suggest that the ring magnets (of anistropic ferrite perhaps) are gapped in this way to prevent the magnetic flux fields of the pancake primaries co-joining as one sprawling field, because it would be more advantageous, and safer, to have each separate pancake's magnetic flux cut it's own adjoining secondary coil, and divide the secondary output voltage into smaller amounts of potential, thus depending less on complicated insulating procedures that accompany high voltage single primary / single secondary transformers.

The use of aluminium mesh and solid copper sheeting is commonly used in electronic construction; the outer aluminium mesh cylinder would be used to shield stray electrostatic charges, and the solid copper cylinder is to shield the large amount of stray electromagnetic fields produced by the transforming process from high voltage/low current to lower voltage/higher current [note 20]. Obviously they don't want field contamination taking place between the sensitive electrostatic generator and the transformers.

Within these two outside shielding-cylinders are 'grid condensers' which, according to the 1999 report by the 30 engineers, can be as many as 20 layers of perforated sheet (presumably as concentric cylinders) - which I have indicated (in fig.7 for instance) as being electrically connected

BETWEEN each separate secondary winding - in the fashion of an old discovery from the early days of wireless telegraphy and based on the 'disruptive discharge coil' devised by Nikola Tesla, that such a condenser connected in the center of a secondary coil collects the maximum amount of voltage created by that secondary. This configuration of one condenser inside another inside another etc etc, has a striking similarity to the layout of a pulse forming network [see note 18].

In the red wired can the transformer is wired to output negative, and the blue wired can's transformer is wired to output positive polarity. Special note should be made of a similar arrangement for divided primary / secondary windings devised by Van de Graaff in his 'High Voltage Electromagnetic Charged-Particle Accelerator Apparatus Having an Insulating Magnetic Core' [note 21] with respect to magnetic reluctance gaps.

Whilst it has been said that the clear perspex disc was designated the 'cloud' disc, and the (rear) dark disc the 'ground' disc I would think this relates to different types of acrylics or plastics that might become charged to different polarities, as in the triboelectric series, where frictional charging of different plastics --- and then bringing them close together, might cause donation or acceptance from one to the other; I would think from the above that cloud represents a donator (positive charge) and that ground must mean an acceptor (negative charge). Has anyone tried the combination of a teflon disc (extremely negative charge) with a glass disc (highly positive charge) ?

Or discs doped with paramagnetic particles perhaps [note 22] ?

The circuit has to be made to oscillate for it to work, and then the oscillations have to be rectified, so that DC pulses can be channeled through the transformers in the big cans and converted to high-current DC output. The rectifying-diode, together with the coils L1 and L2, and the capacitors C5 and VC4 are one of many configurations that will create the oscillations and rectify them. The rectifier must have a heated filament to provide cathodic electrons, and its efficiency is greatly improved by being inside a vacuum enclosure.

A reed switch is triggered by magnets in the disc rim to provide a timing pulse to indicate the disc's rpm.

What makes this machine 'over unity' is its ability to *magnify* its basic input - and this it does by creating and utilizing an electron cascade effect, which ionizes and polarizes the air in the environment surrounding the two horseshoe-magnet configurations (basically by oscillating the dielectric blocks with high frequency high voltage pulses), the air molecules are accelerated toward the blocks at high speed to cause them to collide with other air molecules to dislodge free-electrons, which are also accelerated to free up more electrons by further collisions, and so on and so forth. The resulting avalanche permeates the surrounding environment.

In each Big Can is a step-down transformer of multiple pancake coil windings especially coupled to a toroid-magnet core so as to intensify the field and produce divided voltage outputs which charge up separate 'condenser-grilles', which build up the charge for output. Electrostatic shielding in the big cans is provided by the outer perforated aluminium cylinder and magnetic shielding is provided by a solid copper cylinder.


Full Circuit
Alternative Rectifier
C
filament
C
Plate (anode)
Rectifier-Diode
Coil (grid)
Filament (cathode)
HF Choke UPR2
C5
HF Choke UPR1
VC4
Reed Switch Amp
Out +
SC1
If+
Pos
p
J+
Neg
ml1
Ib-
n
Neg
Pos
+
F
Pos
FRONT
Pos
P
Ib+
If-
Neg
Pos
Neg
n
B
BACK
Pos
rear link wire
SW1
L2
L1
+
-
-
SC2
Out -
Secondary(BS1)
C1
+
-
to base capacitor
ML2
C2
+
-
HP1
HS1
C3
+
-
HP2
HS2
Electron (ECG 1) Cascade Generator
Electron (ECG 2) Cascade Generator
Secondary(BS2)
Primary(BP2)
Hidden Wires in the Wooden Base (& possibly Lecher-wired for high-frequency resonance)

© Paul E Potter 2000

Back-Engineered Methernitha --- Notes

Note 1 --- For more information on the Pidgeon machine see "Electrical Influence Machines" by John Gray, 1903 p. 206 & "Philosophical Magazine" Dec 1898, p. 564, and of course the Pidgeon patents.

Note 2 --- See "Modern High Speed Influence Machines" by V.E. Johnson, 1921, p. 76. Johnson was not only a researcher of electrostatic machines but was also an innovative constructor of them, and as such was keen to try any technique that made his generators more powerful than even the specialised Wommelsdorf multi-disc condenser machines. This book is an absolute must for those who wish to work in this field. Another 'must' is the website of Antonio Carlos M. de Queiroz (http://www.coe.ufrj.br/~acmq/electrostatic.html) which is absolutely full of information about (and with links to) present-day developments in electrostatic machines.

Note 3 --- See "Self-Excited, Alternating, High-Voltage Generation Using A Modified Electrostatic Influence Machine" by M.Zahn, et al., American Journal of Physics, Vol 42 (1974) p. 289.

Note 4 The Methernitha designers have taken a basic Pidgeon electric field system and added a few modifications of their own, partly to lock a certain polarity of charge to a certain area so as to stabilise it, and also to boost certain areas with charge. As in their use, for example, of an extra field plate located at the top-centre in front of the front disc (just under the rectifying valve), note also that this plate, or antennae key, is indirectly coupled to the rest of the circuit, via a coil setup. Much the same occurs with the two plates slightly below it, these plates are connected to a brass terminal which connects to a copper wire that goes down and winds in a coil shape around a hollow plastic tube, and inside the tube will be another wire or small coil that draws off the electric charge. So these three plates are using not direct connection but induction to get their charge.

Note 5 ------- By looking at how each of the photographed machines have been constructed you can see that these are high quality crafted structures. I would think each would start off as sub-assemblies fitted together by pairs or small groups of members, those sub-assemblies of wooden base, big cans, perspex framework, discs with bearings and axles, when completed would be passed on to the electrical engineers of the community who would then fit the wiring connections, vacuum tube rectifier and make sure that not only did they work but that they looked like a work of art.

Note 6 --- The Fleming valve had been around since 1905 and while it progressed to the thermionic valve and audion, by 1922 the ‘Pearson and Anson Effect’ was discovered whereby oscillating currents could be produced with a resistor, capacitor and thermionic valve coupled together.

Note 7 --- See US Patent 1,540,998 (9 June 1925) Conversion of Atmospheric Electric Energy by Hermann Plauson. He also wrote a book of the subject titled "Gewinnung und Verwertung der Atmospharischen Elektrizitat" in 1920 in German (which is currently held in the British Library).

Note 8 --- Whilst some have seen the smaller 300 Watt machine’s discharger/rectifier quite open and not encased in a vacuum tube the vacuum tube models would be much more efficient and would waste less current. Also, the rectifier tube must have a heated filament (which on the 3KW machines can be seen as a glowing line running the whole length of the grid and coil assembly between the two black end caps, and in the films you can see faint flashes coming from behind the rectifier so possibly the filament is wrapped around the other side of the grid/coil assembly as well). Coolridge, back in the 1900’s, discovered that no discharge from the cathode to the anode would occur, even at 100,000 volts, unless the filament was heated (Physics Review, Vol. 2, Dec 1913, p. 418). Aluminium mesh will give off electrons quite readily and can be used as a cold cathode --- but a heated cathode offers the advantage of being able to control the oscillations.

Note 9 --- The two long upright tubes are without doubt choke coil assemblies in precisely the right place to slow down the current where it gets oscillated and rectified. In a choke the higher the flow of current the greater will be its resistance to that current flow. An even better form of choke will have some form of iron core inside it.

Note 10 --- I have come up with 6 different circuits for this oscillation section, some of which include small quartz crystals. (See notes 13 and 16 on frequency of oscillation). The black dial at the rear of the 3kw machine is most likely to select a variety of capacitances so as to control the oscillations of the circuit, which in turn control disc rotational speed.

Note 11 --- The phenomenon of electrostatic motors has been well researched over the years (see "Electrostatic Motors" O. Jefimenko in "Physics Teacher" Vol. 9, March 1971, p. 121-9, and in "Electrostatics And Its Applications" by A.D. Moore (1973) p. 131-147; "Electrostatic Motors" by B.Bollee in "Philips Tech. Review" Vol 30 (1969), p. 178-194). The Methernitha Testatika generators (see a recent report by 30 engineers) auto-rotate, after they have been started by hand, by the same principles of these ES motors.

Note 12 --- J.G.Trump worked for the US Air Force and pioneered some highly efficient electrostatic machines around the 1960's (see"Electrostatic Sources of Electric Power" in "Elec. Eng." 66:525, June 1947; and "High Voltage Generation in Space:The Parametric Electrostatic Machine" in "Progr. Astronaut. Rocketry" (vol 3 --- Energy Conversion for Space Power) 1961 p745).

Note 13 --- Although the 'Linden Experiment' was thought to register a frequency of 80-140 MHz this does not necessarily mean that the Methernitha generators would oscillate at that rate also. Such a frequency seems unnecessarily high.

Note 14 --- See "Plasma --- The Fourth State of Matter" by D.A. Frank-Kamenetskii (1972) pp10, and Dr.Patrick Flanagan's US patents 4,743,275 (May 10, 1988) and 4,391,773 (Jul 5, 1983).

Note 15 --- The effect is very similar to the converging forces in a non-uniform field, the oscillating perspex blocks become one 'electrode' and the surrounding air in the room becomes the opposite 'electrode', and by the processes of electrophoresis and dielectrophoresis the electrically charged particles in the air (the electrons and negative ions) are drawn toward the central electrode, which in this case is the perspex block assembly (see "Nonuniform Electric Fields" by Herbert A. Pohl in "Scientific American" (Dec 1960) p. 107-8). I am much more inclined to believe that the ingenuity of the design of these types of machines comes from physicists and not electronic engineers.

Note 16 --- Dr. Flanagan actually uses the electron field generator in his own special ionizer (see Method of Purifying Air and Negative Field Generator US Patent 4,391,773).

How does an electron cascade generator work, I would think that while you have an alternating electron movement (and Dr. Flanagan reckons this effect occurs with a high voltage field alternating at above 20 KHz) at the metal electrodes, the perspex blocks sandwiched between them would transfer the electricity not through their mass but around it, as surface charge --- actually in the layer of air right next to the insulator's surface. Its the same principle as dielectric absorption - the perspex blocks don't discharge themselves fast enough to keep up with the alternating voltage and so they accumulate more and more charge --- until it forms as a layer of charge on the insulator's surface. This means that at a high enough frequency the surface-air molecules polarize, with the more mobile electrons separating from the slower bulks of those molecules and while the electrons get thrusted back and forth a secondary layer of (slower) positive air ions develops, and so on, and the process of high voltage high frequency polarization triggers the electron avalanche effect.

In the event that the perspex blocks are indeed ELECTRETS (as free-energy researcher Geoff Egel and others suggest) I would think that they would work in a similar fashion to the above process, of dielectric absorption that charges up the blocks before they produce the cascade-effect. Because in the electret the electrons charged into the perspex/plastic, and the positive ions, would still be manipulated by the reversing electromagnetic field in such a way as to orientate (as with dipoles) back and forth, to eventually reach the point (if the whole circuit is tuned properly) where they would attain resonance with the immediate air surrounding them. And if this effect is similar to an inductance then possibly a back-emf will result also, to increase the output voltage. Either way I believe the effect will still be an electron cascade through the environment and the product of this oscillating output (at the blocks) could similarly be drawn off and accumulated in the multi-layered base capacitor network.

I would suggest that a test program to find the best type of blocks would be; One --- try different types of plastic/acrylic/ceramic materials for the blocks.
Two --- try different methods of electrifying the plastics (as with electrets). Three --- try plastics doped with semiconducting particles. Four - try plastics doped with paramagnetic particles. Five - try hollow plastic blocks containing an electrolytic fluid. More information on plastics will be found on the Electret vs Dielectric Absorption Page.

Note 17 --- There are several definitions of Bifilar, one where the wires cancel out their magnetic fields, and one where the wires are wound to ensure a tight low-loss magnetic flux coupling, in this case you need all the magnetic flux you can get so it must be the latter --- See "Transformers For Electronic Circuits" by Nathan R. Grossner (1967), p. 224 etc.

Most commonly used magnetic metal is Mumetal, which is an easily saturable magnetic material, routing magnetic flux through it rather than in the surrounding air, so as to enhance the mutual induction between the two coilings of red wire around the horseshoe legs.

Note 18 --- So that the machine's output voltage doesn't drain away when it is connected up to a large load, what is needed here is a Pulse Forming Network (or artificial delay line). "Such a network is an improvement on simple capacitor storage because of the cascading action from one capacitor to the next along the chain. At the beginning, all capacitors are charged to the same voltage but as soon as the first one starts to loose voltage, the one behind it is then free to discharge into it. This topping-up action, which trickles down the network from capacitor to capacitor, is the mechanism by which the voltage across the output terminals tends to hold onto its original level." (see "High Energy Discharge Systems" A.P.Stephenson, Electronics Today International, March 1992, pp. 24-26).

Note 19 --- When voltage of a high potential and high frequency flows along a wire it does so on the outer surface (called the ‘skin effect’) and so the Methernitha would use thick wiring or even 1/8" tubing to connect its circuit.

Note 20 --- Two references for shielding are: "A Shielded Loop" by S. Goldman in "Electronics" Vol 11 (1938), pp. 20-22; and "Measurements in Radio Engineering" by F.E. Terman (1935), p. 218 & p. 341.

Note 21 --- For information on maximum voltage in the center of a secondary coil see "A Handbook of Wireless Telegraphy" by J. Erskine-Murray (1913) p. 42; and an article called "Dielectric Hysteresis at Radio Frequencies" by E.F.W. Alexanderson in "Proc. I.R.E., Vol. 2 (June 1914) p137-157. For Van de Graaff's transformer see US patents 3,323,069 (May 30, 1967) and 3,187,208 (June 1, 1965). These patents were not just for a Van de Graaff high voltage generator, they were for a special system devised by Van de Graaff long after his generator had been in use to convert static electricity into current electricity. This system may be a little too complicated for the Methernitha but, nevertheless, the principles he used for multiple primary / secondary windings may be of some interest.

Note 22 --- Dr. Flanagan modified his insulator blocks, made of resin, by doping them with paramagnetic granules (such as silicon carbide) to enhance even more the electron cascade effect; which is an idea that the physicist Thomas Townsend Brown first experimented with (by using lead oxide granules) in his US Patent 3,187,206 (June 1, 1965) to good effect. The surrounding air could also be ‘enhanced’ in similar fashion to polarise it's electric charge and improve its side of the performance (for those interested in the ‘physics’ of this see an article by W.A.Douglas Rudge "On Some Sources of Disturbance of the Normal Atmospheric Potential Gradient" in Proc. Royal Soc. A, Vol. 90 (1914) pp. 571, etc).

Note 23 --- Some other generators with similarities to the Testatika machine are the "Electrostatic Energy Field Power Generating System" invented by William W. Hyde (US Patent 4,897,592 of Jan 30, 1990) is a rotor/stator variable capacitance machine capable of producing 300 KV. Other such generators are; "Parametric Electric Machine" invented by Ferdinand Cap (US Patent 4,622,510 of Nov 11, 1986) which has a series resonant (LCR) circuit structured into it so that it oscillates --- and indeed operates AT RESONANCE to ensure a high output; "Electrostatic Generator" invented by Dan B. Le May, et al. (US Patent 3,094,653 of Jun 18 1963) is a very ingenious system of variable capacitance; the "Electrostatic Machine" by Noel Felici (US Patent 2,522,106 of Sep 12, 1950) is a good standard which utilizes a valve rectifier; and the "Electrostatic Generator" by William S. Spencer (US Patent 1,415,779 of May 9, 1922) is an early rotor/stator generator which transferred its electric impulses through a transformer to produce a higher current output.

Fig.2


P
N
rear field
P
If+
Pos
J+
Neg
Ib-
(neg)
n
Neg
Neg
+
Pos
C
Pos
Neg
F
C
Neg
Pos
-
P
Rb
Rf
If-
Pos
Neg
Ib+
Pos
n
B
Ib-
P
If+
C
Pos
70
n
Neg
C
P
Rf
F
G
If-
Rb
Ib+
n
4
C'
G
C'
C
C
F
C
C
+
-
1
B'
B
P
N
A
A
3
E
C
D
C'
C
C'
D'
H
C
2

Pidgeon (configured as Methernitha machine)

Pidgeon machine

Wimshurst machine


grid circuit
plate circuit
heated filament
magnetic pulse switch (circuit)
L¹ L²
VC¹
C¹
+
-
circuit 3
UPR¹
L¹
VC¹
+
P
L²
G
F
-
C¹
UPR²

Fig. 4 - Tower Circuits


high-mass particles
electrodes
-
+
perspex, plastic or resin insulators

Fig. 6 - ECG Doped


secondary output
primary input - high tension voltage
perforated aluminium cylinder for electrostatic shielding
high tension insulation
sheet copper cylinder for magnetic flux containment
primary winding
secondary link wire to base multi-capacitor/ pulse forming network
secondary winding
final grid-sheet attached to brass output ring
separate interlinked pancake windings of primary and secondary coils
air-gaps between magnet rings
perforated sheets of multi-plane grid-condenser [1]
primary output to choke and rectifier

Fig.7

[1] In the Testatika-Distatica Video it has... "By means of **grid-condensers** the energy is stored and it is then uniformly discharged, at the same time reducing the high-voltage and building up power with additional devices."

"Principle Experiment"

by

Paul E. Potter

With respect to the 30 engineer's report (of 1999) the 'principle experiment' was set up in such a way (see diag 1) that by swivelling the cross-piece over two other plexiglas blocks a current was transferred into two capacitors. Possibly when someone grabs hold of the swivelling cross-piece they transfer some static electricity from their body to the grilles of the cross-piece which, when vigorously turned back and forth will initiate a transfer of electric charge to the two stacks of blocks below them attached to the base. This may either be because anyone walking over a carpet or wearing man-made fibres will already hold thousands of volts of electrostatic charge - which will be enough to 'prime' this apparatus after touching it, to get it to work, much the same as when a rotating influence machine has to be primed with an electric charge before it will work; or, as many researchers have surmised already, that the plexiglas blocks glued to the swivelling cross-piece had been charged up with electricity as an ELECTRET.

The use of mesh around the cross-piece guarantees a variable capacitance to the moving arms --- and as these are moved quickly over the base blocks (again, alternated with mesh and Plexiglas) an amount of electric charge will be transferred to them EACH TIME the arms go backward-and-forward over them. Electronically, you have one variable capacitance acting upon another variable capacitance - which is why Baumann said that if metal foil were used instead of the mesh it would not produce the same effect.

What happens next is called "dielectric absorption", and the following extract, from "Dielectrics" by P.J.Harrop (1972) pp71, will explain;

"When a given dielectric [i.e., plexiglas] has a field put across it, and this field is then removed, the electrodes are briefly shorted out (not enough for all the ions and particles to relapse back) and the device left on open circuit one finds subsequently that it has partially charged up again.

This is due to the slow-moving charge carriers remaining in position. It can be a frightening phenomenon with practical dielectrics since a person who has briefly discharged a charged insulator may subsequently touch it and be severely shocked." Some dielectric materials being more prone to this effect than others, and so obviously some experimentation will be needed to choose the best perspex, plexiglas, plastic, or acrylic materials so as to take the most advantage from this dielectric absorption effect.

Once the blocks are being charged up the electric charge simply flows into the two interconnected capacitors and accumulates.


Principle Experiment
capacitors
grille (steel ?)
plexiglas plate and (brass ?) wire mesh glued on underside of arm
plexiglas arm cross-piece
plexiglas plate glued on underside of arm
grille (steel ?)
perforated (square hole) mesh (aluminium ?)
wire mesh (brass ?)
plexiglas plate glued to underside of arm with (brass ?) mesh covering
plexiglas plates glued together with (brass ?) mesh between

Linden Experiment ~

A look at the only available diagram of the Linden experiment (see diag 2) shows a horseshoe magnet coupled to what seems to be a closed-ended wire. It can also be seen in this diagram that the wire coils around the magnet are sufficiently spaced apart so as to provide capacitance (between each coil of the wire) in the circuit. So, with capacitance, coils (for induction), and magnetic flux, you have all the ingredients needed to make an oscillating circuit --- provided there is a supply of voltage and some sort of interruption mechanism - then you have a circuit that will resonate. And this leads us back to that oft repeated question --- is the block used in the Linden Experiment an electret. The first person to PUBLISH how they have duplicated this experiment will be the one to answer that question...

But there is something wrong with this diagram --- the resonant frequency of this simple circuit --- depending only on the values of inductance and capacitance included in the circuit would consequently enable it to oscillate at only a few kilohertz at best. No circuit of capacitance/inductance can be made to resonate at such a high frequency as claimed, not even if it included any form of quartz crystal. If, as the diagram says, it resonates at 140 MHz then there must be a Lecher wire system (the running of two conducting wires in a parallel line, about a foot apart or less, for several feet) to make it resonate at such a high frequency. It would seem to me also that a required modification of the Linden Experiment diagram would be to put a different metal into this circuit where the wire is said to be "closed-ended", say for instance a zinc plate, then there will be a contact voltage established between the copper wire and the zinc plate. Such a voltage would start the circuit resonating, for the reasons stated above.

And as with the Tini setup if a block comprising two metal plates separated by a suitable dielectric material (such as plexiglas) is placed in an oscillating electric field the electric charge on the metal plates will permeate into the dielectric, and for the same reasons as detailed above in the Principle Experiment, will temporarily accumulate voltage because of dielectric absorption. As I have already said elsewhere there is a great similarity between the phenomenon of the Testatika horseshoe blocks (and the Tini setup) and the principle behind Patrick Flanagan's Electron Field Generator which energizes an electron cascade mechanism throughout the immediate environment.


solderd jion
2 feet approx
10 to 25 turns
Insulated house wire copper
With grid dip meter shown to resonate at about 80-140 Mhz
The Linden Experiment
as performed by P.Baunmann in front of witnesses
N
S
Plates could have
N
S
been placed this way instead
http://www2.murray.net.au/users/egel
Horse shoe Magnet
Insulation Persplex or other
Aluminium Plate
copper plate
shift position
1mm square
shift angle
voltmter showed 700 volts
(c) Geoff Egel
Capacitor

Geoff Egel (1997) --- http://www2.murray.net.au/users/egel ~

Rectifier Circuit ~


J+
ML¹
ML²
C¹
C²
SC¹
SC²
24kV DC
BS¹
BP¹
BS²
BP²
out +
out -
C^BASE
L³
C^BASE
L⁴
HP¹
HS¹
ECG¹
ECG²
HS²
HP²
C³
L¹
L²
VC⁴
C⁵
UPR¹
UPR²
P
G
F
+
-

The rectifier forms the basis for Testatika's operation
For whilst the LC circuits L^1, VC^4, UPR^1, UPR^2 and C^5 set up
oscillations from the generator's high voltage output the
rectifier controls the oscillations to provide positive dc pulses
(which are then directed through a step-down transformer
BP^1/BS^1 and BP^2/BS^2), to supply power
at a higher current rate and lower voltage.


single filament
rectifier

Unidentified European Report ~

"Believe or Not, Here It Is!"

The first really running "free energy" machine coming from Switzerland, Europe. It was developed over a 20 years Research period by a religious group called: METHERNITHA. This group lives in CH-3517 Linden, Switzerland. The inventor of this superb machine, Mr.Paul Baumann claims, its running principle was found by studying the lightning effects from nature.

And here are the facts :

* Testatika is an influence-type Wimhurst machine which runs on it's own energy, once started by counterclock revolving it's 2 dics by hand !!!

* Testatika not only runs on it' own energy, but produces also a huge amount of excess power, at least 3 KWATTS of power! That is enough to supply a one-person apartment with one machine!

* The machine you see during this demo-animation is only about 70 cm wide, 40 cm deep and about 60 cm tall !

* It delivers DC-Voltage ranging from 270 til 320 Volts, only depending on the dryness of the air! At this voltage it can supply at least 10 Amperes of DC-current !

* Testatika is not a perpetuum mobile, but an energy machine that collects it's huge amount of "FREE" energy from the charged and ionized air particles. But there are still some technological tricks implemented to overcome the normal drag-resistance of a conventional Wimhurst machine, which is still the secret of the Methernitha group !!!

When will this technology be available for everyone?

The Testatika machines, (there already exists also some smaller units which only deliver about 200-300 Watts) are not yet mass-production type models! They are still laboratory prototype units, although they are build with a very good craftmansship !

For more info contact directly:

METHERNITHA, CH-3517 LINDEN, Switzerland
TEL.-Nr.: ++ 41 31 97 11 24

The pictures are from some photos and from a video-tape Methernitha sells. It shows the machines (also the smaler ones) and explains also Methernitha's spiritual aims. The tape has a running length of about 40 minutes and is really worth looking at it! It is also available in
VHS-NTSC and American language. It also shows Methernitha's earlier research developments like huge wind generators.

With the Testatika there is no fraud, hidden batteries or any other hidden energy source. It is really running! They already have the technology of ten years ahead! No more oil, no more pollution, no more atomic waste products, no more hunger in this world! This is the machine the mankind has dreamed about for centuries. Now it has come true!

More information about the Methernitha machine is also available in the German magazine *RAUM & ZEIT*, issue Nr.40 (8).

Jean L. Naudin Labs (4 February 1998) ~

"Testatika Generator and Over-Unity"

by

Cyril Smith

Having read Nelson Camus' article purporting to "explain" the Testatika over-unity generator (http://members.aol.com/overunity2/nelson/testatic.htm), I am of the opinion that the real explanation is hidden amongst the 19th century electrical mumbo jumbo which makes up much of the machine (Leyden Jars, Horseshoe Magnets, Wimshurst Generator and so on). From the description of spiral-wound foil capacitors containing radioactive material and placed within current carrying coils it strikes me that perhaps the real energy comes from Beta particles (fast electrons) absorbed into the electrical circuit.

To extract energy from Beta particles it is not just enough to capture them. Clearly this will result in a current flow according to the capture rate, but current by itself is not power. The kinetic energy of the particle must be captured and this will result in potential difference or voltage. If a Beta particle enters a thin foil conductor normal to its surface and is captured, then the potential difference associated with giving up its kinetic energy can be expected to occur across the opposite faces of the foil. If however the Beta particle were turned so as to enter at a shallow grazing angle to the surface, not only would the probability of capture be increased (since the particle will travel further within the material) but the potential difference will occur along the length of the foil. Beta particles travelling even at relavistic velocities can be turned within short distances by relatively weak magnetic fields, so the concept shown in the following Figure suggests itself.



Methernitha Statement of Purpose ~

"The Research Work of Methernitha in the Field of the so-called Free Energy"

Ever since the foundation of Methernitha there existed a department for research, development and electronics, which was concerned with the problem of alternative energy sources, namely with technologies, which were suited to exploit the inherent forces of nature and thus to unlock sources of energy without disturbing natures ecological balance in any negative way. Any technology man invents should serve him in short as well as in long terms, and this condition is not fulfilled as soon as it opposes nature in any way.

This team of research within Methernitha works completely autonomous and is financed out of the co-operatives own resources, without any outside support.

The efficient utilisation of wind energy was one of the first objectives of Methernitha's research program. At the beginning generators with special excitation were developed, which allowed to load the cells of accumulators even at low RPM at times when there are only moderate air movements.

Utilising the kinetic energy of water currents was another field of interest of the development team, but it was pursued more as hobby. The key problem was here to transfer the slow revolutions of the waterwheel to an extent that the excitation threshold of the generator could be surpassed by a minimal loss of energy.

Also solar cells and solar heat collectors attracted the attention of our researchers since a long time. But since in these fields other institutions have attained outstanding results, Methernitha started, and this was already more than 30 years ago, to concentrate its efforts on lesser known and even generally unknown sources of energy. The result of this scientific work is the Thestatica machine.

The question arises: How it comes, that Methernitha, nothing more than a private organisation, could invest so much time, engagement, perseverance and financial resources in this kind of research.

Research and development are integrated parts of the general idealistic concept of Methernitha. To make you understand these ideals and goals, we will now introduce you into the practical sides of this spiritual community Methernitha, as it functions as a co-operative of people, living and working together.

Linden is a calm village of farmers just as dozens of others in the region of the valley called Emmental. However Linden is also the home of a special form of human life, which is capable of attracting more and more people from all over the globe, and which has repeatedly caused astonishment through its excellent functioning, even in extremely difficult situations.

There is no doubt that the formation of Methernitha is also a good part of the life story of Paul Baumann. Through his extraordinary technical capabilities, but also through his astonishing practicable wisdom he opened relations to all kind of people with ideals and in many places, and pretty soon, the idea to form a co-operative enterprise took shape.

"In the name of the God Almighty" people of equal thinking gathered and founded a co-operative, which could serve as the economic basis of this spiritual community.

"We want to be a united group of brothers, and never separate however severe the burden may be", this was the solemn vow.

Renunciation of alcohol and smoking and the will to realise a harmonious community life without dispute and discord like in the original Christian communities were the prerequisites to become a member. For the members Methernitha is an ideal opportunity to lead a fulfilled life by practising charity.

A workshop was erected and soon, one house after the other grew on these premises. Also all construction was done out of own resources and solely with the savings from the common work.

Today Methernitha is a social model proving the quality of its ideals through its well functioning just more than forty years. The people working here are almost without exception members of Methernitha.

Not even the prospering development that took place over the following decades could impair or even suppress the global idealistic aims. On the contrary, everybody works in his own interest with diligence and great joy towards the erection and the support of their new homeland and according to the principle:

One for all and all for one!

With this word one can conquer anything. Also the ancient truths appear again and attain respect.

The people living here feel themselves as members of a family, like a group sitting in the same boat and proud, but also grateful proprietors of their own beautiful homeland, which they may shape exactly as they wish to. Evidently, this form of human social life can function only on the base of idealistic principles.

The question arises, how the realisation of a sincere religious philosophy of life may be brought in harmony with a successful economic management. It is not obvious at all, that this is attainable.

Nowadays there are many amongst us that are caught in the world-wide and dense network of social and economic dependencies and obligations and many also feel the confrontation with its problems.

One member of the economic directory has recently phrased this in the following way:

"The fact that all essential functions of Methernitha are fulfilled without any external force, driven solely through inner conviction, which causes everybody to help and take care of the other, this is for me the most astonishing effect which is produced by this form of living together. It seems to be a miracle."

Another miracle within Methernitha is the Thestatica, which is the result of more than 20 years of research.

This wonder machine is lurked from nature, nothing else. Nature is the greatest source of power as well as knowledge which man has, and it still conceals many secrets, which are only revealed to those, who approach and tie in with them with highest respect and responsibility.

To understand nature and to perceive its voice, man is obliged to experience silence and solitude, and it was there, where the knowledge about this technology was obtained.

For these reasons it was always a great concern of Methernitha to acquire properties, untouched by man as far as possible, be it in valleys or forests, in the mountains or ashore of lakes, where one could study nature, ones own being and the creator of all this universe in silence and concentration and without being disturbed.

The public never understood this properly, rather interpreted it wrongly as an act of seclusion, assuming we had to hide something unclean. We actually had --- and still have --- to take great troubles to realise undisturbed all the things we intended to accomplish.

Such undertaking in research and development necessitate considerable financial expenditures. Therefore we are quite often obliged to construct things with most primitive means and materials. What was thrown away by our affluent society, we collect and possibly set up with it a cornerstone in the discovery of new forces and truth.

We are fortunate in gaining the experience that paradoxically the most beautiful and useful results can be achieved by just using the most simple means. Never did we use any borrowed capital because we want to stay free Swiss citizens and do not want to be hindered or even bound in any way in the pursuance of our aims.

The two conterrotating discs generate an electrostatic charge. One disc represents the earth, the other the cloud. Using grid electrodes the charges are bound. After that they are collected by non-contacting so-called antenna keys and then sorted.

After being initially turned on by hand, the discs rotate by themselves according to the electrostatic laws about attraction and repulsion. A rectifying diode keeps the cycles in steady state. Otherwise the impulses of attraction and repulsion would accumulate and cause the discs to run faster and faster. The correct speed is of great importance and for optimal power generation the discs have to run quite steady and slow.

By means of grid condensers the energy is stored and then uniformly discharged, at the same time reducing the high voltage and building up power with additional devices. Finally the machine supplies a uniform direct current, which varies according to the size of the model. The machine furnishes about 3-4kW permanent output, depending on humidity, whereby the electric potential ranges from 270 to 320Volt. High humidity of the atmosphere prevents the build-up of electric potential. The drier the air, the better.

No doubt, through the so far achieved results one main objective has been reached, namely to prove that it is possible to use Free Energy. Nevertheless the research work is not yet completed.

To the educated physicist many a thing of this machine may seem impossible, maybe even crazy. Maybe he is also offended by the conceptions used to explain the whole. Only partly we could use the concepts of conventional physical terminology to explain and define only approximately the functions and properties of the various parts of the machine.

After all it will be necessary to create some more new concepts like the one we have already used before, when we termed the non-contacting collectors of electric charges as antenna keys.

This machine puts experts, which are just trained in conventional physics to a very hard test, because its mode of action is not explainable with the state of the art of officially accepted physical knowledge, or at the most only partially explainable. However also a trained specialist should remain free and independent in his thinking, and should avoid to be limited by the temporal framework of publicly admitted knowledge in any science.

It has to be remembered that the established science was already many times forced to change or give up some of its very fundamental concepts. Think about Galilee, to name only one example. Our human society almost condemned this man as a sorcerer and magician, just because he investigated and discovered a truth that seemed unacceptable by the established science of the days.

The book knowledge of any times is not wrong, but it is incomplete, and therefore allows to draw wrong conclusions.

We are part of a new area which brings to light many new facts and new knowledge. The clothes of nowadays science have become too tight and should be stripped off, just as the larva of an insect does with its skin. Only this will allow a true metamorphosis to take its course, and finally, at the limits and at the destination of all worldly knowledge, an universal and unlimited spiritual science, radiating and beautiful, just as the completed imago of an insect, may give its blessings and benediction to a renovated humanity.

To ever reach there, a universal development of man has to take place. This however is only possible when man becomes aware of his true role within the whole creation, and again learns to recognise his true tasks, because the whole universe functions within a strict and precisely structured order according to the will and word of the creator. Therefore also man should recognise and realise these universal laws that are valid within the whole and within every part of this creation.

The hard facts rather show how far man has left the divine order through his self willed and authoritarian way of action and that he has become the actual cause of all discord and evil on this planet.

Unfortunately the ruling bodies that should be responsible for the well-being of the people work too often with the target to make life more and more difficult and to render impossible every free spiritual development.

Instead of utilising the achievements of science and technology for the benefit and preservation of all form of life, they are abused carelessly and irresponsibly to destroy and to kill, and thus turn them into a curse upon mankind.

To change all this, the evolution of a new technology is not enough, even if it were the most ecological and ingenious. To change this present status one has to go much deeper down, to the root-cause of all this evil, and this is mans way of thinking, his state of mind.

The ancient divine commandments are still valid today and also show today the way and direction humanity should go, as clearly spoken by the prophet Mica:

God has told you what is good. And what is it that the Lord asks of you? Only to act justly, to love loyalty, to walk wisely before your God.

"Testatika-Distatica Machine"

(Transcribed from the Methernitha Testatika video by Paul E Potter)

"... The efficient utilization of wind energy was one of the first objectives of Methernitha's research program.

At the beginning generators with special excitation were developed which allowed to load the cells of accumulators even at low rpm, at times when there are only moderate movements.

Utilizing the kinetic energy of water currents was another field of interest of the development team, but it was pursued more as hobby. The key problem was here to transfer the slow revolutions of the water-wheel to an extent that the excitation threshold of the generator could be surpassed by a minimal loss of energy. Also solar cells and solar heat collectors attracted the attention of our researchers since a long time. But since in these fields other institutions have obtained outstanding results Methernitha started, and this was already more than 20 years ago [since 1960], to concentrate its efforts on lesser-known and even generally unknown sources of energy, the result of this scientific work is the Testatika machine of which most of you may have heard already.

The two counter-rotating discs generate an electrostatic charge. One disc represents the earth, the other the cloud. Using grid-electrodes* the charges are bound. After that they are collected by non-contacted, so-called, antennae keys** and then sorted [shorted ?].

After being initially turned on by hand the discs rotate by themselves according to the electrostatic laws about attraction and repulsion.

A rectifying-diode keeps the cycles in steady state, otherwise the impulses of attraction and repulsion would accumulate and cause the disc to run faster and faster. The correct speed is of great importance, and for optimum power generation the discs have to run quite steady and slow.

By means of grid-condensers* the energy is stored and it is then uniformly discharged, at the same time reducing the high-voltage and building up power with additional devices.

Finally, the machine supplies a uniform direct current which varies according to size of the model.

The machine furnishes about 3 to 4 Kilo-Watt permanent output, depending on humidity, whereby the electrical potential ranges from 270 to 320 volt. High humidity of the atmosphere prevents the build up of electric potential. The dryer the air the better.

No doubt, through the so-far achieved results, one main objective has been reached, namely, to prove that it is possible to use free energy. Nevertheless, the research work is not yet completed: To finish a model which can be handed out more or less to anybody and without any haphazards, also to non-specialists, much work and also time will still be needed.

Only partly we could use the concepts of conventional physical terminology in order to explain and define only approximately the functions and properties of the various parts of the machine. After all, it will be necessary to create some more new concepts, like the one we have already used before, when we termed the non-contacting collectors of electric charge as antennae keys**. This machine puts experts who are just trained in conventional physics to a very hard test..."

* The German original has gitter-condensers, with gitter defined as wire lattice, grille, grate.

** the original word used is tasten or taster, which means antenna, probe, key.

Your Support Maintains this Service --

BUY

The Rex Research Civilization Kit

... It's Your Best Bet & Investment in Sustainable Humanity on Earth ...
Ensure & Enhance Your Survival & Genome Transmission ...
Everything @ rexresearch.com on a Data DVD !

ORDER PAGE

Energy Projects

Electrodynamic Tether Photos

Deployment of the Tether Satellite



Boom Deploy



Initial Deploy



Satellite Deployed



Closeup of boom showing tether



Close up of end of boom

Tether Break



The tether deployed to one mile

Shortly after the breakreak



The tether coils as it moves away from the Shuttle





The base of the tether boom. The area looks more like a Tesla Laboratory than the space shuttle hanger bay.

After the Break

The following three images are those displayed for the public showing the white specks that appearall around the tether after it has broken free. NASA calls these "dust and debris" particles, though Mission control in the audio portion of the videos state that they see a "lot of stuff swimming around" and that the tether is wider than expected.







If you compare these images to the ones we captured from a hard to find high resolution copy of the video on this page you will see a remarkale difference. The video is a must see.

Video Clip
STS-75 'The Tether Incident' Feb 1996
Editors Note: This video has been removed several times by Youtube. Currently it is available again. If it does get removed again, email me and I can send you a copy as we have it on disk now. Contact me at webmaster
This one is from the hand held Infrared Camera and is not as clear as the other one was STS-75 Alternate Copy

Comments:

What is most interesting to note is that most of the video clips above are taken from this video, yet NASA does not show the video itself. The copy on Youtube is a transmission intercept copy. However the fact that the NASA info site DOES use those clips gives credibility to the video that it is indeed a NASA film - Zorgon

Tethered Satellite System (TSS-1R)
Source of Clips: NASA STS-75 Mission Pictures

Kennedy Space Center STS-75 Mission Fact Sheet

"Critters" from STS-75

The Report After the Fact

NASA/TP—2003-21228
Low Earth Orbit Spacecraft Charging Design Guidelines

Below are a few keynote excerpts from the PDF file. The entire 367 page document is available below for those with technically savy who want to read the entire paper...

Excerpt 1:
In the case of the TSS-1R tether, its 20 km length produced a maximum of about 3500 V potential between its most positive and negative ends, since it wasn?t oriented perfectly perpendicular to the velocity vector and the Earth?s magnetic field. A satellite at its upper end collected electrons, and an electron gun at the lower end emitted electrons to complete the circuit. When the electron gun was not in operation, a large resistance prevented the Shuttle from being biased thousands of volts negative of its surrounding plasma. However, there remained a large voltage between the tether lower end and the Shuttle orbiter. This enormous bias eventually led to a continuous arc on the tether (see The Continuous Arc, section 4.2.3.1 below), which broke, freeing the satellite and ending the experiment. During the arc, the satellite collected over 1 Amp of electron current to keep the arc going. Probe theory (Cohen et al, 19870010625 N) is usually used to calculate the total current collected by a wire with distributed potentials. However, before the break, TSS-1R demonstrated that a satellite at a high positive potential could collect an anomalously large electron current. See Zhang, et al (20000110580), Stone and Raitt (19990084046 and 20000025437), and Stone, et al (19980202347)

Excerpt 2:
Sustained arcs (continuous arcs) - These are the events that have been attributed with the destruction of on-orbit solar arrays. Generally, the process begins with a fast transient (a so-called trigger arc). Under some conditions, the transient develops into an arc that is fed directly by the entire array, effectively becoming a short-circuit. Such events invariably involve large quantities of energy and can be severely damaging to cells, interconnects or power traces.





Excerpt 3:
When the structure or array capacitance electrically connected to the arc site is sufficiently large, the initial transient arcs themselves can be large enough to produce significant damage. In Figure 9, we see an anodized aluminum plate that has undergone repeated arcing in the laboratory with the ISS structure capacitance attached. Its thermal properties have been completely destroyed, along with most of the insulating surface layer of aluminum oxide.

Excerpt 4:

The most famous sustained arc event of all led to the breakage of the TSS-1R electrodynamic tether, and the loss of the attached satellite. The image below shows the burned, frayed and broken tether end still attached to the Shuttle after the break. **Incidentally, the tether continued arcing long after it and its satellite were drifting free, until finally it went into night conditions where the electron density was insufficient to sustain the arc.** Noel Sargent (2002) has investigated whether the TSS-1R arc was seen to disrupt Shuttle communications. Although he has found no record of disturbed communications during the event, for most of the time the arc was shielded by metallic structures from the communications antennas, and when the tether broke, the arc was many meters from the receiving antennas. It remains to be seen whether sustained arcs produce radio noise severe enough to be a communications problem.

Comments:

This is official confirmation that the tether continued to produce plasma energy long after it broke free, accounting for the "fluorescent bulb" glowing effect viewed after. We believe this concentrated collection of plasma energy is what attracted the "swarm" of "critters" to a "feeding frenzy"

To get the full PDF file you can download LEO_Charging_Guidelines_v1.3.1.zip



Tether Optical Phenomena Experiment (TOP)

Using a hand-held camera system with image intensifiers and special filters, the TOP investigation will provide visual data that may allow scientists to answer a variety of questions concerning tether dynamics and optical effects generated by TSS-1R. In particular, this experiment will examine the high-voltage plasma sheath surrounding the satellite...

In one mode of operation, the current developed in the Tethered Satellite System is closed by using electron accelerators to return electrons to the plasma surrounding the orbiter. The interaction between these electron beams and the plasma is not well understood...

Associate Investigator: Stephen Mende, Lockheed Martin

SOURCE

The Report After the Fact

...



The most famous sustained arc event of all led to the breakage of the TSS-1R electrodynamic tether, and the loss of the attached satellite. Figure 8 shows the burned, frayed and broken tether end still attached to the Shuttle after the break. Incidentally, the tether continued arcing long after it and its satellite were drifting free, until finally it went into night conditions where the electron density was insufficient to sustain the arc.

.....



Figure 8 – The end of the remaining TSS-1R tether

…

It is thus possible that an astronaut, grounded to ISS by his tether or conductive tools, could undergo an arc at only –50 V. A sneak circuit analysis showed that such arcs could put 1 Amp of current through an astronaut's heart. Since 0.1 Amp is enough to cause heart stoppage, it is imperative that if the ISS plasma contactors are inoperable during astronaut EVAs, a method be used to prevent ISS astronaut workplaces from floating more than 50 V negative.

…

For many ISS surfaces, peak arc strengths of hundreds of Amps have been calculated. Arcs this strong will melt the arc site and spew molten metal through space. Plasma chamber tests of this kind of arcing are spectacular indeed! Arcs on one anodized surface have been seen to trigger arcs on nearby line-of-sight surfaces.

…

Finally, an arc on an electrodynamic tether may become continuous. The infamous arc on the TSS-1R tether that led to its break and the loss of the satellite was a continuous (sustained) arc with its power supplied by the tether.

…



Had TSS-1R used a tether of greater resistance, the threshold arc current could not have been maintained. For example, a total tether resistance of ten thousand ohms would have limited the arc current to less than 0.4 Amps, less than the sustained arc threshold. Alternatively, if the satellite electron collection capability had been limited to less than ½ Amp, the arc could not have been sustained. Of course, these measures would have severely restricted the power or propulsion that could be obtained by tether operation and could not be tolerated on an experiment that was not just a proof-of-concept. An arc detection circuit could have also been used to shut the tether down at the satellite end when very large currents were first detected. One should never assume that a high voltage power system will not arc.

...



Ionized gases can be emitted by plasma sources such as hollow cathode plasma contactors or from neutral gas sources at high positive potentials. Locally, the plasma density can be greater than the ambient plasma density and similar plasma interactions can occur with high voltage components. On ISS, the Plasma Contacting Units (PCUs), when operating, produce a local xenon plasma of much greater density than ambient. It has been estimated that the invisible plasma ball produced is some eight meters in radius before its density decreases below the ambient plasma density in LEO. Arcing and current collection from such a plasma could occur in much the same way as with an ambient plasma, implying that solar arrays and other active sites should be kept out of induced plasma plumes.

...

Electrodynamic Tethers ~ **Menu**
Critters ~ **Critters 01** ~ **Critters 02** ~ **Critters 03**

Copyright Notice

All pictures and photos on this page, unless otherwise noted, have been gathered from pubic domain sources or are available under GNU License. Further documentation is available on our Copyright Page and our Legal Department.

Article Quotes all have links to their appropriate source and are noted. All other text not so noted is available under the terms of the GNU Free Documentation License

All information on this page is used only for non profit educational purposes. All reasonable attempts have been made that no credits are missed, but with a work of this size omissions may occur. If you see anything of yours that has not been properly credited or wish to have removed please contact the Webmaster

Menu



Webpages © 2001-2006
Blue Knight Productions

STS 75 TETHER INCIDENT



Tether Deployed

Tether Satellite being deployed from the Shuttle Bay of STS-75



213506148 DAY:056

Tether Activated

Tether Satellite begins to glow as it gathers electricity from the Ionosphere

213809089 DAY:056



Tether Breaks Free

Tether Satellite cable fries the connection and breaks free... still producing energy. The glow increases and the cable gets wider. (More on this later)

-

Tether Broke Free

Tether Satellite worth 100 million has overloaded the circuits within minutes of being activated because the NASA Scientists under estimated the potential. The tether in just a few moments of operation produced 10 times the anticipated power and they forgot to install a circuit breaker.

-

NOTES:
Add "Critter" Portion
Add Video
Add FLV Viewer

TETHER BROKEN FREE AND DRIFTING AWAY

Tether Drifting Away

At this point the STS 75 Astronauts switched to Infrared camera. What you are seeing is the Tether at about 80 nautical miles away from the Shuttle. Notice that it has straightened out and has become much wider. This is commented on by Mission Control as they say its wider than expected.

It is also at this point that the plasma collected by the tether that is "still glowing like a fluorescent bulb" (according to a NASA report issued after the event (See Below)) attracts the "Critters" or UFO's as most people call them. To see more about the "Critters" VISIT HERE In the image include below you can see the Tether Satellite at the tip. By this time the Tether is almost as wide as the Satellite itself.

Going behind the tether you see one of the "Critters" It is CLEARLY behind the tether. This is what NASA calls "dust and debris" The purpose of this paper is to show the tether however, not the "Critters". If you want to know more about them either email us or check out the pages linked to above.

STS-75 - 'The Tether Incident'

Tether Swarmed by "Critters"

Matt (Matyas) had written me that he has found documents hinting at a Tether in operation near Jupiter. He is still following that up, but it seems the Cassini Spacecraft has found one or more in the vicinity of Saturn

Cassini Spacecraft Image

Is this the lost Tether Satellite? Or is there another one in operation near Saturn?


Tether Satellite

Tether Near Saturn

Judging by the scale of Saturn, it would seem this is NOT the lost Satellite, but a much larger one. The STS 75 Tether was 12 miles long... This one is huge

(Note Dates and Size are being calculated)

Source: Original Image NASA Cassini/ Huygens W00028414.jpg



Cassini Spacecraft Image
Tether Near Saturn

..

Cassini Spacecraft Image
Tether Near Saturn

[**Source: Original Image NASA Cassini/ Huygens W00026015.jpg**]

Cassini Spacecraft Image

Source: Original Image NASA Cassini/ Huygens N00008771.jpg

~ MENU ~

US006116544A

United States Patent [19]

Forward et al.

[11] **Patent Number: 6,116,544**

[45] **Date of Patent: Sep. 12, 2000**

[54] **ELECTRODYNAMIC TETHER AND METHOD OF USE**

[75] Inventors: **Robert L. Forward**, Houston, Tex.; **Robert P. Hoyt**, Seattle, Wash.

[73] Assignee: **Tethers Unlimited, Inc.**, Seattle, Wash.

[21] Appl. No.: **08/929,271**

[22] Filed: **Sep. 12, 1997**

[51] **Int. Cl.**^{7} **B64G 1/00**

[52] **U.S. Cl.** .... **244/158 R**; 244/166; 244/172

[58] **Field of Search** .... 244/158 R, 164, 244/166, 172

[56] **References Cited**

U.S. PATENT DOCUMENTS

4,097,010	6/1978	Colombo et al.	244/158 R
4,824,051	4/1989	Engelking	244/158 R
4,923,151	5/1990	Roberts	244/158 R

OTHER PUBLICATIONS

"Tethers Open New Space Options" by Ivan Bekey, *Astronautics & Aeronautics*, 1983.

Primary Examiner—J. Woodrow Eldred
Attorney, Agent, or Firm—Arthur M. Dula

[57] **ABSTRACT**

The present invention comprises an electrodynamic tether structure and a method of use. The structure of the tether taught by the present invention is a short, wide, interconnected multiwire (compared to the long, narrow single wires of the prior art) conductive tether whose area maximizes electrodynamic drag while simultaneously minimizing the Area-Time-Product swept by the tether during its operating life. The preferred tether length is two kilometers to five kilometers. The preferred tether mass is one percent to five percent of the spacecraft mass. The method of operation comprises orienting the tether structure at an angle to the local vertical to maximize electrodynamic drag on the host spacecraft and minimize tether instability. The angle of 35.26 degrees is preferred.

26 Claims, 12 Drawing Sheets



τ = 35.26°


Hoytether
Survival Probability
Hoytether
1-week survival
probability > 99%
Single-line tether
survival probability
83%
1/e survival probability
Baseline
single-line
tether
0
0.5
1
1.5
2
2.5
3
3.5
4
Time (Years)
100
80
60
40
20
0
SURVIVAL PROBABILITY %

FIG. 1a


ELECTRODYNAMIC THRUST
10-kW system
10-km tether, 50% bare
i = 0°
i = 45°
i = 70°
i = 80°
Electrodynamic thrust (N)
1.0
0.9
0.8
0.7
0.6
0.5
0.4
0.3
0.2
0.1
0.0
200
400
600
800
1000
1200
1400
Altitude (km)

FIG. 1b

Reentry Time Sensitivity
Unpowered 5 km ProSEDS Tether



Enrico Lorenzini, SAO, NASA ProSEDS Mission (July 1997),
NASA/MSFC Grant NAG8-1303

FIG. 1c



FIG. 2a


209
207
205
203
201
211
213

FIG. 2b


209
207
205
211
219
213
217
215
221

FIG. 2c


309
307
310
305
311
303
313
301
315

FIG. 3



Area-Time Product for Mean and Extremes of Exospheric Temperature

(m = 1000 kg, Cd = 2.0 ; 1% Tether, 1 km x 25 cm; power = 1077 watts)

(5% Tether, 1 km x 25 cm; power =5385 watts)

FIG. 4



Conventional Solid Rocket Motor System

Percent Increase in Orbital Mass vs. Altitude and I' (Isp = 288 sec)

FIG. 5


τ
τ = 35.26°

FIG. 6



FIG. 7


τ
τ

FIG.8



FIG. 9



FIG. 10


1100
1008
1002
1006
1004

FIG. 11


F_GB
T_GB
L sinτ
F_GB sinτ
m_B
L cosτ
L
F_GT
T_GT
F_GT sinτ
m_T
F_E cosτ
L/2 cosτ
τ
E
F_E
I
⊕
B
E cosτ
T_E
v
M

FORCES AND TORQUES ON AN UPWARD DEPLOYED CONDUCTING TETHER DUE TO THE MOTION OF THE HOST SPACECRAFT THROUGH THE MAGNETIC FIELD OF THE EARTH.

FIG. 12

ELECTRODYNAMIC TETHER AND METHOD OF USE

TECHNICAL FIELD

This invention relates generally to apparatus and methods useful for changing the state vector of a space object when the space object is moving relative to a magnetic field. More specifically, the present invention relates to an apparatus and method of using a conducting tether to produce an electrodynamic force to deorbit a satellite from its orbit around a celestial body, such as the Earth, which has an associated magnetic field.

RESERVATION OF RIGHTS

This application is subject to certain rights of the U.S. government as a result of contracts between the U.S. government and the inventors.

BACKGROUND ART

The present invention has its principal utility in outer space, primarily for deorbiting satellites at the end of their useful life to mitigate the harm and reduce the liability created by the proliferation of space debris. In order to obtain a better understanding of the present invention it is helpful to understand the prior art of space tethers, especially tether dynamics and tether electrodynamics. The present invention may be more readily understood through a review of the experimental prior art and a mathematical analysis of electrodynamic space tethers.

Prior Art Tethers:

A tether was originally a rope or chain used to fasten an animal so that it grazed only within certain limits. Tethers have been used for decades in space to attach astronauts to their spacecraft.

In 1974 Professor Guiseppe Colombo, holder of the Galileo chair of astronomy at the University of Padua in Italy, proposed using a long tether to support a satellite from an orbiting platform. U.S. Pat. No. 4,097,010, which issued to Professor Colombo and Mario Grossi on Jun. 27, 1978, teaches a satellite connected by means of a long tether to a powered spacecraft. Colombo actively pursued the design of a tethered satellite system.

Several NASA experiments, such as the two Small Expendable Deployer System (SEDS 1 & 2) experiments and the Plasma Motor Generator (PMG) experiment used tethers in space. SEDS used a nonconducting tether. The PMG used a 500-meter conducting tether. The Tethered Satellite System flights in 1992 and 1996 (TSS-1 & 1R) used a 20,000-meter conducting tether.

On the TSS-1 mission the tether deployed only 260 meters (853 feet) before the deployer failed. On the TSS-1R the tether was deployed 19,500 meters. In the SEDS-2 flight, a 0.8-mm diameter, 20,000-meter long braided single-line tether was deployed to study tether dynamics and lifetime. Orbital debris or a meteoroid severed this tether in less than four days.

In the TSS-1R flight, the conducting single-line tether was severed after five hours of deployment. This failure was caused by an electric arc produced by the 3,500 volts of electric potential generated by the conductive tether's movement through the Earth's magnetic field.

The Tether Physics and Survivability (TiPS) satellite consists of two end masses connected by a 4,000-meter long non-conducting tether. This satellite was deployed on Jun. 20, 1996 at an altitude of 1,022 kilometers (552 nautical miles). Its tether is an outer layer of Spectra™ 1000 braid over a core of acrylic yarn. The yarn will "puff" its outer braid to two millimeters to "give it a larger cross section to improve its resistance to debris and small micrometeoroids", according to the National Reconnaissance Office (NRO), which is a sponsor of the TiPS mission. As of Jun. 21, 1997 the TiPS tether had survived one year.

References:

1. Joseph A. Carroll, "SEDS Deployer Design and Flight Performance", paper WSEDSA-1 at the 4th International Conference on Tethers in Space, Washington, D.C., April 1995.
2. James E. McCoy, et. al. "Plasma Motor-Generator (PMG) Flight Experiment Results", pp.57–84, Proceedings of the 4th International conference on Tethers in Space, Washington, D.C., April 1995.
3. W. John Raitt, et. al. "The NASA.ASI-TSS-1 Mission, Summary of Results and Reflight Plans, pp. 107–118, Proceedings of the 4th International conference on Tethers in Space, Washington, D.C., April 1995.
4. Joseph C. Anselmo, "NRO Orbiting Spacecraft Studies Tether Survivability", Aviation Week, page 24, Jul. 1, 1996.

These experiments all used single line tethers.

The following reference is illustrative of the current state of the art in space tethers: Paul A. Penzo and Paul W. Ammann. Tethers in Space Handbook—Second Edition. NASA Office of Space Flight, NASA Headquarters, Washington, D.C. 20546. See also the hundreds of references in the 33 page bibliography at the end of the handbook.

The "Hoytether"™, an Improved, High-Reliability Tether:

In 1991, one of the present inventors, Robert Hoyt, invented a lightweight net-like structure that provides many redundant load-bearing paths. A number of primary load bearing lines running the length of the structure are connected periodically by diagonal secondary lines. The disclosed embodiment of this invention has the secondary lines firmly connected by knots to the primary lines. The secondary lines are connected only to the primary lines. At either end of the disclosed structure, a support ring enforces the cylindrical spacing between the primary lines. The secondary lines are designed with a small amount of slack. These secondary lines are only put under load if a primary line fails. This specific tether structure was disclosed to the public in 1992 (Forward, R. L., "Failsafe Multistrand Tether Structures for Space Propulsion", AIAA paper 92–3214, 28th Joint Propulsion Conference, Nashville, Tenn., 1992 (hereinafter "1992 Hoytether structure"). This structure was named a "Hoytether". The term "Hoytether" is used throughout the remainder of this specification for this type of tether structure.

The present invention uses an improved Hoytether, which was invented by the same inventors as the present invention. This improved Hoytether is the subject of a copending PCT application. The Hoytether is discussed briefly in this specification to aid understanding of the present invention.

The 1992 Hoytether design teaches that the normally slack secondary lines have half the cross-section (0.707 the diameter) of the primary lines. There are twice as many secondary lines as primary lines, thus the mass of the secondary lines is equal to the mass of the primary lines. In an undamaged Hoytether, the primary lines carry the entire load, while none of the secondary lines are under load.

While the survival probability of a single-line tether decreases exponentially with time, the Hoytether can maintain a high, i.e. greater than 99 percent, survival probability

for periods of months or years (forward and Hoyt, "Failsafe Multiline Hoythther Lifetimes", Paper AIAA 95–2890, 31^{st} Joint Propulsion Conference, July 1995).

References:

1. Robert L. Forward, Failsafe Multistrand Tethers for Space Propulsion, Forward Unlimited, P.O. Box 2783, Malibu, Calif. 90265, July 1992, Final Report on NASA Contract NAS8-39318 SBIR 91-1 Phase I.
2. Robert L. Forward and Robert P. Hoyt, Failsafe Multistrand Tether SEDS Technology Demonstration, Final Report on NAS8-40545 with NASA/MSFC (Jun. 14, 1995).
3. Robert L. Forward and Robert P. Hoyt, "High Strength-to-Weight Tapered Hoytether for LEO to GEO Payload Transfer" Final Report on contract number NAS8-40690 with NASA/MSFC (Jul. 10, 1996).

The Hoytether is essentially a tri-axial net structure, with 'primary' lines running along the length of the tether and two sets of 'secondary' lines connecting these primaries diagonally. They can be made by hand and connected with knots as is taught by the 1992 Hoytether structure. Because knotted connections severely limit the strength of a structure, it is desirable to use a knotless fabrication technique to achieve interconnections that have strengths approaching the limits of the constituent material. As these tethers may be many kilometers long; fast and inexpensive mechanical methods are required for their practical fabrication.

Hoytethers may be made by mechanical braiding, i.e. three-dimensional braiding, such as 3-D rotation braiding using braiding machines such as those developed by the Herzog Company in Germany (August Herzog Maschinenfabrik GmbH & Co., Postfach 2260.26012, Oldenburg, Germany. The specialized loom developed by the Nichimo Company of Japan (Nichimo Company Ltd., 2-6-2 Ohtemachi, Chiyoda-Ku, Tokyo, Japan) is used to produce "Ultracross" knotless fishing nets in which the individual strands are braided as a 4-braid line, and the strands are interbraided where they cross. This produces netting that has slipless interconnections that are very strong, approaching the maximum capability of the fiber. Such a loom could, with some modifications, produce the present invention's structure. Only two such machines exist, one in Japan, the other in Washington State. Unfortunately neither can work with the small line diameters needed to practice the preferred embodiment of the present invention. See generally, Ko, F. K., "Braiding", in *Engineered Materials Handbook, Vol. 1., Composites*. ASM International, Metals Park, Ohio, 1957. Pp. 519–528.

The most common 3-dimensional braiding machines are 4-step braiders based upon the designs of Maistre (German Patent P230-16986, issued 1973) and Forentine (U.S. Pat. No. 4,312,261, issued 1982). Braiding is accomplished by using pneumatics or solenoids to push the parts of the braiding machine to the proper positions. This is a slow process and making a Hoytether kilometers long with these machines would be very time consuming and expensive. The composites division of Albany International (Albany International Research Company, 777 West Street, Mansfield, Mass.) also produces a 3-D braiding machine. This machine uses modular braiding components that arc assembled breadboard fashion on a large wall.

Although braiding is the preferred technique, alternate fabrication methods such as Raschel knitting and crocheting can be used successfully. Multikilometer long Hoyththers are presently being produced for the inventors by the vendors Culzean Fabrics and Flemings Textiles using an electronically controlled crochet machine produced by Comez in Italy.

Space Tether Systems:

The prior art teaches the use of tethers in space applications. U.S. Pat. No. 5,163,641, issued on Apr. 9, 1990 to Yasaka, teaches the use of a powered spacecraft connected by a tether to a satellite. This tether is disconnected to change the state vector of the satellite. The state of the art of energy and momentum transfer using space tethers is discussed in Ivan Beckey's article "Tethering, a new Technique for Payload Deployment", Aerospace America, March 1997, at pages 36–40. Beckey concludes, "Tethers can perform the same functions as propulsive upper stages of direct payload injection, but at lower weight and cost per pound." U.S. Pat. No. 4,923,151, issued Mar. 1, 1988 to Roberts, Wilknson and Webster, teaches a tether power generator for earth orbiting satellites. U.S. Pat. No. 4,580,747, issued Mar. 15, 1983 to Pearson, teaches use of a long tether extending downward into the atmosphere from a satellite. The state vector of the satellite is changed by forces acting on a lifting body connected to the end of the tether. U.S. Pat. No. 4,824,051, issued Jan. 12, 1987 to Engelking, teaches passing an electric current through a conductive tether attached to a satellite to provide propulsive force to alter the orbit of the satellite. U.S. Pat. No. 5,082,211, issued Jan. 21, 1992 to Werka, teaches use of a tether to deorbit space debris. U.S. Pat. No. 4,727,373, issued Mar. 31, 1986 to Hoover, teaches an orbiting stereo imaging radar system having two spacecraft in synchronous parallel orbits connected by a tether.

Tether Dynamics:

In order to understand the forces that cause a tethered satellite to move upward and away from an orbiting satellite, for example, it is first necessary to explain briefly how a satellite remains in orbit. An orbiting satellite is acted on by the force of gravity which pulls it toward Earth, and by a centrifugal force, which pushes it away from Earth. The centrifugal force" (actually inertia) results from the motion of the satellite around its circular orbit. This is the same force that one can experience by swinging a ball around on the end of a string. A satellite is maintained in its orbit when it travels at the natural speed for its altitude and, as a result, the centrifugal force is equal to the gravitational force.

At the typical orbital altitude of 250 kilometers for a low-Earth orbit satellite, for example, a speed of approximately 7.6-km per second is required to create sufficient centrifugal force to balance gravitational attraction on the satellite. If the altitude is changed, the two opposing forces will no longer be in balance unless the satellite also changes its speed. A higher orbital altitude requires a slightly lower speed so the satellite will take longer to complete an orbit. Because of this, if two free-flying satellites are in orbits at different altitudes, the lower satellite will circle the Earth in less time than the satellite in the higher orbit.

If two satellites, at different altitudes, are connected to each other by a tether, they are forced to travel around their orbits together—in the same period of time, which is longer than the natural period of the lower satellite but shorter than that of the upper satellite. The lower satellite will, therefore, slow down below the natural speed for its orbit and will tend to fall to a lower orbit because the centrifugal force will now be less than the gravitational attraction of the Earth. An upward force in the tether that makes up the difference between centrifugal and gravitational forces holds it in place, however.

Correspondingly, the upper satellite will be accelerated above its natural orbiting speed (increasing its centrifugal force above the gravitational attraction) and will tend to move to a higher orbit. It, too, is held in place by an additional force (downward) in the tether. In other words,

the net force downward on the lower satellite is balanced, through the tether, by the net force upward on the upper satellite. The effect of unbalanced forces on the two satellites is, therefore, to create tension in the tether. During the TSS-1 & 1R experiments, the inertia of the tethered satellite causes the satellite to rise above the orbiter as the tether is reeled out. Very close to the orbiter, there is little difference in the two orbits, and the tension force is insufficient to overcome friction in the deployer mechanism; therefore, until the satellite reaches a separation of approximately 1000-meters, the tension is augmented by small tether-aligned thrusters on the satellite. Beyond this point, the tension in the tether is the only force required.

By experimenting with a ball hung on a piece of elastic cord (a paddleball, for example) it is possible to simulate all the different types of oscillations that are possible on a space-based tether system. The elastic cord, representing the tether, may compress and stretch, causing the ball to bounce up and down (longitudinal oscillation). It also may move in a circular (skip-rope) motion or may develop wave-like motions (transverse oscillations). Even if the string itself remains straight, it is possible to get the ball swinging back and forth about its attachment point on the paddle like a child on a swing rope (pendulous motion).

Each type of motion occurs with a particular frequency, which depends on the length and tension of the tether. When the frequencies are different, the motions do not interact; however, at some tether lengths, the frequencies of two or more types of oscillation can become very close. At this point, energy can be transferred from one typc of motion to another, a phenomenon known as resonance. For instance, the transverse oscillations in the tether may cause the satellite to swing back and forth in pendulous motion.

Many different factors may cause oscillations; the movements of the satellite or Shuttle are but two of these. For an electrodynamic tether, the skip-rope and pendulous oscillations are of particular interest. If a current is passed through a tether, the current will interact with Earth's magnetic field, resulting in a force that may produce skip-rope and pendulous oscillations. Because it is necessary to maintain control of the satellite, much study has gone into identifying the different types of possible motions and the methods used to control them.

One way to control the magnitude of those motions that cause a change in tension or transverse motion at the end of the tether is to have an end mass connected to the Hoytether that maintains a controlled tension on the tether, working much like a spring-loaded 'dog leash'. This may be as simple as a coiled spring, or as complex as an active control system that measures the tension and transverse forces on the tether and adjusts the applied tension according to a local or remotely operating algorithm.

Electrodynamic Effects of Conductive Tethers:

Electric potential is generated across a conductive tether by its motion through the Earth's magnetic field. Electromagnetic forces acting on a conductive tether in orbit can make the tether system behave like an electric motor or generator, thereby exerting a useful force to alter the state vector of the tether and any mass attached to it.

Electrodynamic tether propulsion is unlike most other types of space propulsion in use or being developed for space application today—there is no hot gas expelled to provide thrust. Instead, the environment of near-Earth space is being utilized to propel a spacecraft or upper stage via electrodynamic interactions.

A charged particle moving in a magnetic field experiences a force that is perpendicular to its direction of motion and the direction of the field. When a current flows through a long, conducting tether the electrons flowing through the tether experience this force due to the fact that they are moving along the wire in the presence of Earth's magnetic field. This force is transferred to the tether and to whatever the tether is attached (like a spacecraft, satellite, space station or upper stage). It can be an orbit-raising thrust force or orbit-lowering drag force, depending upon the direction of current flow. Operation in one mode allows boost from LEO to higher orbit while reversing the current flow provides negative thrust for deboost. The principle is much the same for an electric motor; reverse its operation and it acts as a generator. The current passing through the tether is returned through the ionosphere to complete the current loop with collection and emission occurring on opposite ends of the tether.

The PMG experiment demonstrated that a conducting tether can be used as both a motor and a generator. The TSS experiments, especially TSS-1R showed that very large voltages (about 3500 volts) can be generated by a sufficiently long tether.

Uses of an electrodynamic tether as an orbit raising and lower propulsion system has many advantages over competing systems:

a. It is nearly propellantless. Most other systems expel hot gases and require extensive resupply. To emit current, the electrodynamic tether propulsion system may use plasma contactors developed as a part of the International Space Station Program. These contactors consume less than 20 kg of xenon gas per year with a 50% duty cycle. The electrodynamic tether propulsion system can also use field emitter arrays, which emit electrons without the use of any gas.

b. It can change both altitude and inclination. The Earth's magnetic field is non-uniform and can therefore provide both in- and out-of-plane forces for inclination changes as well as altitude changes. This is of particular interest to payloads requiring polar orbits in that they can be launched on a small launch vehicle into a lower inclination orbit and have it raised in space by the proper phasing of current through the tether.

A demonstration of the propulsive capabilities of electrodynamic tethers was recently approved for a flight test in 1999. The Propulsive SEDS or ProSEDS mission, will fly as a secondary payload on a Delta II launch vehicle and deploy a 5-km conducting tether using the existing SEDS deployer concept. The ProSEDS experiment will be followed by the Electrodynamic Tether Upper Stage (EDTUS) experiment that will demonstrated the use of electrodynamic forces to change both the altitude and inclination of the experimental spacecraft. FIGS. **1**B and **1**C show the calculated electrodynamic thrust at several inclinations and the reentry time sensitivity of the ProSEDS tether, respectively.

One application for long-life conducting electrodynamic tethers is as a "Terminator Tether™" for removing from orbit unwanted Earth orbiting spacecraft at the end of their useful lives. When the mission of the satellite is completed, the Terminator Tether™, weighing a small fraction of the mass of the satellite, would be deployed. The electrodynamic interaction of the conducting tether with the Earth's magnetic field will induce current flow in the tether conductor. The resulting energy loss from the heat generated by the current flowing through the ohmic resistance in the conducting tether will remove energy from the spacecraft, eventually causing it to deorbit, thus reducing the amount of orbital space debris that must be coped with in the future.

In the following analysis, it is shown that the amount of energy loss generated by an electrodynamic tether is essen-

tially independent of its length or area, and instead is primarily proportional to the tether mass and the physical properties of the conductor metal chosen. In the typical example calculated, a 1000-kg spacecraft can be deorbited from a 1000-km high Earth orbit by a 10-kg mass tether in a month, while a 1-kg tether can deorbit a 1000-kg spacecraft in less than a year.

To the knowledge of the inventors, Joseph P. Loftus of NASA/JSC first proposed the general concept of using an electrodynamic tether to deorbit spent satellites. (Joseph P. Loftus <JLoftus@ems.jsc.nasa.gov>, personal communication via email to Robert Forward, Monday Jun. 10, 1996 15:50:10.) In order to show that the Loftus deorbit concept was not obvious to those skilled in the art of electrodynamic tethers, Forward contacted the leading expert, Joseph Carroll, of Chula Vista, Calif., who built and participated in the flight test of the PMG. After being told of the Loftus concept in a telephone conversation, his reply in an Email message dated Aug. 5, 1996, was "such a system would be feasible . . . by it is still not obvious to me that it would be useful . . . "

Loftus was considering the use of electrodynamic drag from a conducting tether to achieve this goal of bringing the unwanted spacecraft down from its high orbit (where atmospheric drag is negligible) to a 200-km orbit, where atmospheric drag would rapidly finish off the task of removing the unwanted spacecraft from orbit. The tether Loftus was considering was a single-line, conducting tether, typically 1-mm in diameter, 1-km long, and, if made of aluminum, 2-kg in mass. He would include means at the ends of the tether to contact the ambient space plasma around the Earth to complete the current loop.

Unfortunately it is probable that space impactors would sever the 1-mm diameter, 1-km long single-line tether proposed by loftus within a 1/e lifetime of four months. This would produce orbital debris rather than removing it. The motivation for this work is the NASA Safety Standard NSS 1740.14 "(Guidelines and Assessment Procedures for Limiting Orbital Debris." The relevant portion of the Standard starts on page 6-3: General Policy Objective-Postmission Disposal of Space Structures. Item 6-1: "Disposal for final mission orbits passing through LEO: A spacecraft or upper stage with perigee altitude below 2000 km in its final orbit will be disposed of by one of three methods." The method of interest is the atmospheric reentry option, Option a: "Leave the structure in an orbit in which, using conservative projections for solar activity, atmospheric drag will limit the lifetime to no longer than 25 years after completion of mission. If drag enhancement devices are to be used to reduce the orbit lifetime, it should be demonstrated that such devices will significantly reduce the area-time product of the system or will not cause the spacecraft or large debris to fragment if a collision occurs while the system is decaying from orbit."

The NASA standard applies only to NASA spacecraft and even then only to completely new spacecraft designs. New versions of existing designs are to make a "best effort" to meet the standard, but will not be required to change their design to do so. The Department of Defense has adopted the NASA standard with the same provisos. An Interagency Group report has recommended that the NASA standard be taken as a starting point for a national standard. It is NASA's recommendation to the Interagency Group that the safety requirement be phased in only as spacefaring nations reach consensus internationally, which is being done through the International Debris Coordination Working Group whose members are Russia, China, Japan, ESA, UK, India, France, Italy, and the US.

Thus, although the NASA Safety Standard in its present form is not the "Law", the existence of the standard means that some time in the future a similar requirement may be imposed on all spacecraft. This could result in major growth in future space tether business, with a sale to every non-geostationary spacecraft being "mandated" by government safety regulations, somewhat as the sale of seat belts and airbags for every car are mandated.

In fact, three of the companies planning to set up "constellations" of low to medium orbit communications: Teledesic, Iridium and Odessey have committed their companies to abide by the spirit of NASA Safety Standard 1740.14 by using one means or another to deorbit their spacecraft before they reach end of life.

Problems with Prior Art Tethers:

All electrodynamic tether designs proposed by the prior art teach that the tether should be operated at a right angle to the magnetic field through which the tether is moving. This is a problem because the electrodynamic force acting on the tether causes the tether to align itself with the magnetic field force lines. To overcome this problem the prior art teaches the use of a large ballast mass attached to the end of the tether and/or use of a very long (tens to hundreds of kilometers) tether. The large ballast mass is expensive to take to orbit because it replaces useful payload. The long tether sweeps a larger Area-Time-Product during its useful life and thus is more likely to impact other space objects, either debris or another spacecraft.

Another problem common to all proposed prior art tethers is tether instability. If the tether produces a large electrodynamic drag force, which is desirable because a large drag force will cause the satellite to deorbit quickly, then the tether will be dynamically unstable. This instability can cause the tether to lose its effectiveness, act uncontrollably and even wrap around the satellite or otherwise malfunction. Experts skilled in the art of tether design have opined that this dynamic instability is inherently unavoidable in any electrodynamic tether system. The prior art solution, such as that presently being used in the ProSEDS experiment, has been to use a large ballast mass to increase the stabilizing gravity-gradient force and/or to limit the electrodynamic drag of the tether to less that the maximum that could be produced. In the ProSEDS experiment, the conducting electrodynamic tether is five kilometers long. To insure stability, it will be augmented by a 20–35 kilometer long non-conducting tether, which to further have stability will have a 40 kilogram ballast end mass.

Yet another problem of all proposed prior art electrodynamic tether systems is how to radiate away the energy produced by the tether's operation. A satellite moving at an orbital velocity of 18,000 miles per hour has a kinetic energy of over 10,000 calories per gram. To put this amount of energy in an understandable perspective, it may be noted that when nitroglycerine explodes it produces about 1,500 calories per gram. Prior art designs of electrodynamic drag tethers teach the use of the electrical energy generated by the tether to charge batteries or operate electronics, with the excess energy being converted into heat by a resistive load. This excess heat must be radiated to the space environment or it will melt the resistive load. Thus the resistive load, and/or its associated radiator structures, must be massive and replace useful payload.

DISCLOSURE OF THE INVENTION

The present invention comprises an electrodynamic tether structure and a method of use. The principal industrial utility of the present invention is to deorbit satellites in Earth orbit

at the end of their useful life. This embodiment of the present invention is sometimes referred to in this specification as a "Terminator Tether™" because it terminates the orbital lifetime of the host spacecraft. The structure of the tether taught by the present invention is a short, wide, interconnected-multiwire (compared to the long single wires of the prior art) conductive Hoytether whose area maximizes electrodynamic drag while simultaneously minimizing the Area-Time-Product swept by the tether during its operating life. The preferred tether length is two to five kilometers. The preferred tether mass is one to five percent (1%–5%) of the spacecraft mass. The method of operation comprises orienting the tether structure at a 35.26-degree trailing angle to the local vertical to maximize electrodynamic force on the tether while avoiding tether instability and allowing use of a small tether end mass.

The present invention also teaches that the satellite-tether system may be rotated around its common center of mass to centrifugally produce tension force in the tether structure to oppose forces causing tether instability. The angle of the conductive tether structure of the present invention with respect to the velocity vector of the host spacecraft may be controlled by the method of the present invention so it interacts with the encountered magnetic field to induce a maximum current flow in the tether. This produces maximum electrodynamic drag. All or a portion of this electric power may be stored and then controllably applied to the conductive tether to produce an induced electrodynamic force. This induced electrodynamic force may by used to enhance the drag force, to rotate the tether-satellite system and/or to provide satellite propulsion, i.e. to change the state vector of the satellite for any useful purpose, e.g. to avoid collision or to change the host spacecraft's orbit to an orbit more favorable for more rapid deorbiting.

The present invention also teaches a tether structure that also functions as a thermal radiator and/or plasma contactor. An embodiment of the present invention using conducting elements of the satellite, e.g. the solar arrays, as electrodynamic tether structures is also disclosed.

BRIEF DESCRIPTION OF THE DRAWINGS

The present invention may be better understood with reference to the following drawings:

FIG. **1***a* is a graph comparing the survival probability of a single line tether as taught by the prior art to the Hoytether used by the present invention.

FIG. **1***b* is a graph showing the level of electrodynamic thrust for a 10 kilometer, 10 kilowatt tether at various altitudes and inclinations.

FIG. **1***c* is a graph showing reentry time sensitivity of a five kilometer ProSEDS tether for several conditions of current flow in the electrodynamic tether.

FIGS. **2***a*, **2***b* and **2***c* show the Hoytether structure used by the preferred embodiment of the present invention.

FIG. **2***d* shows the Hoytape structure used by the preferred embodiment of the present invention.

FIG. **3** is a block electrical diagram of an electrodynamic tether system.

FIG. **4** is a graph showing a graph of the Area-Time product for three separate levels of exospheric temperature (for neutral drag calculations) and for two separate assumptions regarding tether mass and power drawn from the ambient plasma (for the Terminator Tether™ calculations).

FIG. **5** is the percent additional mass required in orbit to drop the perigee of a circular orbit at altitude, at, to a value of 200 kilometers using standard chemical rocket as taught by the prior art for deorbiting unwanted spacecraft.

FIG. **6** is a deorbit tether system shown operating with its electrodynamic tether at a trailing 35.26-degree angle to the encountered magnetic field, as is taught by the preferred embodiment of the present invention.

FIG. **7** shows an embodiment of the present invention in which the electrodynamic tether—satellite system is rotated about its center of mass to avoid tether instability.

FIG. **8** shows an embodiment of the present invention wherein the tether is powered to provide induced electrodynamic force.

FIG. **9** shows an embodiment of the present invention wherein the solar power system structure of the satellite is used as an electrodynamic tether.

FIG. **10** shows the use of a portion of the tether structure as a thermal radiator and plasma contactor.

FIG. **11** shows the braiding of an ohmic resistive load into the tether structure.

FIG. **12** is a force diagram showing the forces and torques on an upward deployed conducting tether due to the motion of the host spacecraft through the magnetic field of the Earth.

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENT

The principal industrial utility of the present invention is the deorbiting of satellites in Earth orbit, which necessarily can happen only in outer space. Until the present invention is reduced to actual practice by use with satellites in outer space and a body of practical experience is thereby obtained, the present invention can only be constructively reduced to practice, such as by this written specification and its associated drawings, diagrams and graphs and by reference to electric measurements made on conducting tethers in space by the PMG and TSS experiments. The inventors provide herein a detailed discussion of the theory of the present invention to help those skilled in the art of aerospace and tether engineering to understand the present invention and to make and use the best embodiment of the present invention known to the inventors at the time this specification was prepared, without undue experimentation.

Although the present invention is discussed in this specification in its preferred embodiment as a means of deorbiting satellites, it must be emphasized that discussion of this specific use in no way limits the broad scope of the present invention. The present invention can be used to change the direction and speed, i.e. the state vector, of any space object providing that object is in motion relative to any magnetic field. This magnetic field may be that of the Earth or of any other celestial body, for example Jupiter or the sun.

In this specification the material forming the structure of the electrodynamic tether is specified as being a conductor. For example, a metal, such as copper or aluminum wire could be used. Likewise, nonmetallic conductor, such as carbon nanotubes, or a conductive polymer could form the conductive structure of the tether.

FIG. **1***a* shows the survival curve for a Hoytether as used by the present invention vs. the survival curve of a prior art single line tether. The survival probability curve of the Hoytether as a function of time does not conform to the well known "1/e decay" shape of a single-line tether. The Hoytether can maintain a high level of survival probability, about 99 percent, until it nears its 'lifetime'. Its survival probability then drops rapidly to zero. A detailed mathemati-

cal analysis of the difference between Hoytether and single tether survival probabilities is given in Appendix E "Small Impactor Survival Probabilities of Hoytethers" and Appendix F "Large Orbital Debris Survival Probabilities of Hoytethers", both contained in the Final Report of NASA Contract NAS8-40545. The resulting cut probability with time for the Hoytether has a "bingo curve" shapes. In a bingo game, at least five numbers must be called before anyone can win, and usually many numbers have to be called before one of the bingo cards gets five in a row. In the Hoytether at least four cuts must happen at the same level before any failure occurs, and many cuts have to be made before any one of the levels has all four lines cut. The bingo curve has the property that the probability of survival stays very high for periods short compared to the lifetime. The probability of survival is greater than 99% for periods shorter than 10% of the lifetime. This is much better performance than the 1/e curve of a single line tether, where the probability of survival is only 90% at 10% of the 1/e lifetime.

FIG. **1***b* shows the calculated level of electrodynamic thrust, in Newtons, produced by a ten kilowatt, ten kilometer single conductor tether at altitudes between 200 and 1400 kilometers and at orbital inclinations between zero degrees and eighty degrees.

FIG. **1***c* is a graph showing the reentry time sensitivity calculated for a five kilometer ProSEDS single conductor tether at altitudes between 200 and 500 kilometers with current flow in the tether between on flow and one ampere.

FIGS. **1***b* and **1***c* are the work of Enrico Lorenzini of the Smithsonian Astrophysical Observatory from his study "Performance Evaluation of the Electrodynamic Tether Tug", NASA/MSFC Grant NAG8-1303 (Nov. 12, 1966). They show that experts in the field believe that the present invention will have industrial utility, as the current flow of one ampere in FIG. **1***c* decreases the deorbit time for the calculated case from more than 180 days to less than 20 days.

FIG. **2***a* is an isometric drawing showing the generally cylindrical structure of the Hoytether. In FIG. **2***a*, primary lines **201** and **203** are shown connected via secondary lines **211**. In FIG. **2***b*, which is a schematic illustration of the structure shown in FIG. **2***a*, primary lines **201, 203, 205, 207** and **209** are connected, each to their respective adjacent primary lines, by a plurality of secondary lines **221**. These connections, for example as shown at interconnection **213**, are made by knotless, slipless interconnections, such as Soutache braiding of twisted connections.

FIG. **2***c* shows the Hoytether structure of FIG. **2***b* but with a severed primary line **205** at breakpoint **215**. The second level of secondary lines **217**, shown as bold lines in FIG. **2***c*, redistribute the load from the severed primary line **215** at point **217** back to line **215** at points **219** and **221**, above and below the break, respectively.

For the electrodynamic tether, a preferred embodiment would be to unroll the tubular Hoytetherr™ into a flat Hoytape™ as shown in FIG. **2***d*.

FIG. **3** generally shows the arrangement of functional elements of an electrodynamic tether system. Of course such a system must have a means of attachment to the spacecraft, a deployer, the tether itself, some form of space plasma cathode contactor, some form of space plasma anode contactor, a power dissipation system, and a communication and control system. Each of these individual elements are known in some form to those skilled in the art of aerospace engineering. Thus the present inventors do not feel it is necessary to describe them in detail in this specification.

In FIG. **3**, a space object **301**, i.e. a satellite in Earth orbit, or any other space object either natural or man made, is physically connected to the tether system. The tether system comprises a deployer **303** from which a conductive Hoytether **305** having a bare segment **307** extends upward from space object **301**. The positively biased anode end **309** of tether **305** collects electrons from the ionosphere as space object **301** moves in direction **310** across the Earth's magnetic field. These electrons flow through the conductive structure of the Hoytether to the power system interface **311**, where it supplies power to an associated load, not shown. The electrons then flow to the negatively biased cathode **313** where electrons are ejected into the space plasma **315**, thus completing the electric circuit.

In order to allow those skilled in the art to better appreciate the broad scope of the present invention, the inventors will now provide an example using specific tether and system values to compare the Terminator Tether™ to prior art means, ie a rocket, for deorbiting a satellite.

Terminator Tethers™:

When an Earth orbiting conducting space tether moves through the magnetic field of the Earth, an electric field is generated in the tether that is proportional to the velocity of the conductor, the magnetic field strength of the Earth, and the angle between the conducting tether and the magnetic field lines. From data obtained during the various electrodynamic experiments that have been conducted in space to date, such as the PMG, TSS-1, and TSS-1R experiments, a typical value of the generated emf per unit length of tether of E=100–200 Volts/kilometer can be assumed. The electric potential V developed at the ends of a tether of length L is then V=EL. For a tether of length L=10 km, the electric potential developed is V=1000 V. For calibration, the 20-km long TSS-1R tether, at the moment of failure, was developing a potential of 3500 volts, which is 175 volts/km.

The mass of a conducting tether of length L, cross-sectional area A, and densin, d is given by m=dLA. Typical values for the density are d=2700 kg per cubic meter for aluminum and 8900-kg per cubic meter for copper. For a typical aluminum tether of mass m=10 kg and length L=10 km, the cross-sectional area will be A=0.37 mm squared. If this were a solid-wire single-line tether, the diameter of the wire would be D=0.69 mm (21.5 gauge). If this were an 18 line tubular Hoytether, the diameter of the lines in the Hoytether would be D=0.16 mm (34 gauge).

The resistance of a conducting tether of length L and cross-sectional area A is given by R=rL/A, where r is the resistivity of the conductor in nano-ohm-meters (nΩ-m). Typical values for the resistivity are r=27.4nΩ-m for aluminum and 17.0 -nΩ-m for copper. For the m=10 kg aluminum tether of length L=10 km and cross-sectional area A=0.37 mm squared at 20 degrees C, the end-to-end resistance is 750 Ω. This value of resistance is the essentially the same whether the conductor area is concentrated into a single-line tether or divided up into many lines as in a multiline Hoytether.

The current I generated in the conducting tether by the electric potential V between the ends of the tether applied across the tether resistance R is I=V/R. For the 10 kg mass aluminum tether of length L=10 km, electric potential V=EL=1000 volts, and resistance R=750 Ω the current is I=V/R=1.33 Amps. Currents near these values were measured in the TSS-1R experiment at the time of failure. At the time of failure of the TSS-1R tether, none of the plasma contactors on the Space Shuttle or the Italian Satellite were operating. Thus the current was being collected by the conductive surface area of the Space Shuttle and the Italian

Satellite at the two ends of the tether. The Space Shuttle area is quite large, so it was not the limiting factor in current collection. The diameter of the Italian Satellite was 1.6 m, which would give it an effective plasma contact area of about 8 square meters. This shows that, if the plasma contact area of the ends of a conductive space tether can be make large enough, then ampere level currents can be extracted from the ambient space plasma without the use of space plasma contactors.

The power dissipated as ohmic heating in the tether is given by P=IE. For an aluminum tether of mass m=10 kg, resistivity r=27 nΩ-m, and density d=2700 kg/cubic meter, subjected to an electric field of E=100 V/m, the power dissipated in the ohmic losses of the conductor is P=IV=1330 Watts. For a 1 kg mass tether, it would be still a considerable 133 Watts of dissipation.

There will no doubt be additional dissipation of energy in plasma ohmic losses, plasma wave generation, and plasma ion acceleration, but the ohmic losses in the conducting tether alone are sufficient for the task of deorbiting an unwanted spacecraft massing 100 to 1000 times more than the tether.

The decay time of a metric ton spacecraft moving from a 1000 km altitude orbit to a 200 km altitude orbit with an energy difference of dU=3.3GJ, when its energy is being dissipated at a power of P=1330 W by an aluminum tether massing just 10 kg, or 1% the mass of the spacecraft, is about one month. This is a remarkably short time, and indicates that the concept of using a conductive tether to deorbit a spacecraft is indeed feasible. If the aluminum tether massed only 1 kg, or 1/1000th the mass of the spacecraft it was deorbiting, then the decay time would rise to 10 months, still a reasonable value.

In reality, of course, the actual decay time will be longer than this. If the electrodynamic drag force is very large, and becomes larger than the gravity gradient forces pulling on the ends of the tether (which force is proportional to the mass of the tether), then the tether will tend to align itself along the magnetic field lines instead of across them, and the drag force will decrease because of the small angle between the conductor length and the magnetic field lines. The tether will then settle into an angle determined by the balance between these two forces.

Is the Terminator Tether™ theoretically a better means than atmospheric drag or a rocket engine for deorbiting satellites at the end of their useful life?

In the formula for da/dt (change in altitude per change in time), using the assumptions of near-circular spiral trajectories, the Area-Time-Product (Z), the criteria by which NASA judges compliance with Safety Standard 1740.14, is given by:

$$Z = A\int dt = -\frac{m}{C_D}\int \frac{da}{\rho(a)\sqrt{\mu a}},$$

where ρ(a) is simply the density as a function of semi-major axis. Thus, for a static atmosphere, the problem of area-time product is reduced to quadrature. Note that the area-time product depends only on the density profile and the ratio of spacecraft mass to drag-coefficient and is linearly related to that ratio.

The basic altitude-dependence of the atmospheric density, represented here by ρ(a) can be expressed in a low-order power series of ln(density)=f(ln(altitude)), so that it will be possible to develop a representation of the log—log relationship between altitude and density. The three static levels of atmospheric density are modeled as 5th order polynomials in the natural log of the altitude and are representative of well known atmosphere models, for example, Jacchia, L. G., "Thermospheric Temperature, Density, and Composition: New Model," SAO Special Report 375, March 1977. 2. Anon., Marshall Space Flight Center, "Long-Range Statistical Solar Activity Estimation," Atmospheric Sciences Division, 1989.) The values of exospheric temperature are reasonable (about 2-sigma) high and low solar activity values of 1400 and 800 kelvins respectively. The mean value is taken to be 1100 kevins.

FIG. **4** shows a graph of the Area-Time product for three separate levels of exospheric temperature (for neutral drag calculations) and for two separate assumptions regarding tether mass and power drawn from the ambient plasma (for the Terminator Tether™ calculations). The density profiles for the three values of exospheric temperature represent the extremes and mean values to be expected during the next several decades. The exospheric temperature goes through a cycle of about an 11 year period with maximum about 1400 kelvins and minimum about 800 kelvins.

The tether calculations include an inherent assumption that the Terminator Tether™ transfers all the energy extracted from the ambient space plasma into drag that decreases the orbital energy of the spacecraft at a rate given by the power drawn by the tether. Thus, the change in energy for a spacecraft of mass m at an initial altitude h is given by the expression:

$$\Delta E = -m\left\{\frac{\mu}{2(R_e+h)} - \frac{\mu}{2(R_e+250)}\right\},$$

and the time required to effect this change in energy of the mass, m, is just

$$\Delta t = \Delta E/P,$$

where P is the power drawn by the tether from the ambient plasma charge.

The curves for 1% and 5% tethers do not include the effects of atmospheric drag because the electrodynamic drag is orders of magnitude greater than the neutral atmospheric drag. At altitudes greater than about 700 km, the electrodynamic drag is 200 to 3000 times greater than the neutral drag forces.

It is clear, from FIG. **4** that the Terminator Tether™ concept is far superior to neutral drag in removing spacecraft from orbit, no matter how much additional area is added to the passive spacecraft to increase the atmospheric drag. The analyst should note that FIG. **4** is proportional to mass; that is, the Area-Time-Product values should be multiplied by the mass of the spacecraft and divided by 1000 kg. This is true for the neutral drag and Terminator Tether™ curves alike. The power levels assumed for the 1% and 5% tethers are only 80% of their theoretical values. This is done to provide a 20% margin on the power available from the ambient plasma and electrodynamic gradient.

Conventional rocket mechanisms can remove spacecraft from orbit, but this mechanism is apparently not viable from mass considerations when these factors are compared with the capabilities of the Terminator Tether™. A satellite owner may decide to satisfy the NASA safety requirements by adding a small solid motor and the associated hardware, software, sensors and structure to make the package independent, to be used to deorbit the spacecraft in case the main spacecraft power, attitude, or propulsion system fails.

The requirements of such a rocket motor system are more stringent than those attributed to ordinary spacecraft. The

rocket motor deorbit system must operate when some or all other systems of the spacecraft have failed. These more stringent requirements are balanced by lesser requirements of performance. The backup system must simply deorbit the spacecraft; it does not have to perform all the other duties of the spacecraft. But the backup system must know when to fire under all kinds of anomalous situations, including tumbling, offset of center of mass (because of loss of parts due to collisions), and lack of knowledge of the orbital position.

FIG. **5** shows the percent additional mass required by the rocket motor system to drop the perigee of a circular orbit at some initial perigee altitude to a value of 200 km. The atmospheric drag at this 200 km perigee altitude will remove any spacecraft (in the range considered) from orbit in a few revolutions. The contours of constant stage propellant mass fraction, λ, range from low values of 0.5 through reasonable values of 0.65 to 0.7, up to the values associated with the best solid motors ($\lambda \nabla 0.93$) without adding any extra hardware to the emergency stage. An effective, independent stage to provide a retro deltaV of from 50 to 325 m/s will almost certainly have a λ of the order of 0.6 to 0.75. If the emergency stage is required to perform its own attitude determination, the stage propellant mass fraction may be as low as 0.55 or 0.50. Note that the additional mass, shown in FIG. **5**, must also be lofted to orbit in the first place, to provide the mass on orbit for the originally intended service. The stage propellant mass fraction, λ, is a key stage performance parameter that describes the ratio of the mass of propellant to the mass of the stage. That is $\lambda = m_p/(m_p + m_l)$, where m_p is the mass of the propellant and m_l is the mass of everything else in the stage (not including the payload or any stages above or below the stage being considered). Typical independent small rocket stages have values of λ from 0.60 to 0.75. The curves of stage propellant mass fraction are shown as straight lines (a minor approximation) and are included only from 0.5 to 0.95, the extremes of reasonable design practice.

These calculations that show, beyond any reasonable doubt, that the Terminator Tether™ concept is far superior to conventional mechanisms such as drag enhancement devices or small rocket deorbit propulsion systems. The superiority is measured in terms of Area-Time-Product, NASA's measure of the likelihood of collision with other spacecraft in the path of the descending spent member of a constellation. Tether calculations were made using conservative assumptions that the power extractable from the ambient plasma and electrodynamic gradient is only 80% of the theoretical power available to a perfect tether crossing the magnetic field lines at a right angle, i.e. normally.

The following analysis is presented by the inventors to help those skilled in the art to better understand the present invention when it is used as a Terminator Tether™ for removing from orbit unwanted non-geostationary Earth-orbiting spacecraft at the end their useful lives. The primary result of that analysis is that the electrical power P in the tether that is converted into heat by the resistance of the tether and radiated away into space will remove energy from the spacecraft, causing it to rapidly deorbit, thus reducing the amount of orbital space debris that must be coped with in outer space. Tether electric power P is given by:

$$P = (vB)^2 m / 2rd$$

where m is the mass of the conducting tether, r and d are the resistivity and density of the conducting material, and v is the velocity of the spacecraft's motion through the Earth's magnetic field B. For a m=10 kg tether of aluminum with resistivity of r=27.4 nΩ-m and density d=2700 kg/m^3, moving at a velocity v=7037 m/s relative to the Earth's horizontal magnetic field B=26.5 μT, the power dissipated is P=2350 W! This energy loss in the form of heat must necessarily come out of the kinetic energy of the host spacecraft. For a typical example, a 1000 kg spacecraft in a 1000 km high orbit subjected to an energy loss of 2350 J/s from a 10 kg tether (1% the mass of the host spacecraft) will be deorbited in a few weeks.

Power levels of the magnitude estimated in the previous paragraph have been measured in a real orbital space experiment, the TSS-1R mission carried out on the Shuttle Orbiter in 1995. In that experiment, a large Italian spacecraft, 1.6 m in diameter, was deployed upward from the Shuttle Orbiter at the end of a conducting copper wire tether covered with electrical insulation. As the tether was slowly deployed upwards, a series of measurements were made of the open circuit voltage induced in the tether by its motion through the Earth's magnetic field. The voltage between the end of the tether and the Orbiter ground varied from zero volts at the start to 3500 V when the amount of tether deployed approached its maximum length of 20 km. Periodically, the end of the tether was connected either to one of two different electron guns, which supplied contact to the surrounding space plasma, or to the Orbiter ground. The bare surfaces of the Shuttle Orbiter proved to be a surprisingly good plasma contactor via a combination of ton collection and secondary electron emission. The current flow through the tether was deliberately limited by control circuits and the current capacity of the electron guns to about 0.5 amperes, but power levels of 1800 Watts were reached.

The tether was intended to have a fully deployed length of 20 km, but at a deployed length of 19.5 km, when about 3500 V was being induced at the end of the tether inside the Orbiter reel mechanism, a flaw in the insulation allowed an electrical spark to jump in an uncontrolled manner from the tether to the Orbiter ground. With no control circuits to keep the current level down to 0.5 amperes, the current flow jumped to 1.1 amperes, and the total power generated was P=3850 Watts Most of this energy went into the electrical arc, which burned through the tether, causing it to break and halting the experiment. This experiment showed that large areas of bare conducting material, such as that provided by the 8 square meter area of the Italian spacecraft at one end of the tether and the very large surface area of the Shuttle Orbiter spacecraft at the other end of the tether, can collect and emit amperes of current, while thousands of volts of potential can be generated by sufficiently long tethers moving at orbital speeds.

Thus, both theory and experimental data collected in the space environment indicate that significant amounts of electrodynamic drag force can be obtained from a low mass conducting tether attached to a host spacecraft, provided the ends of the conductor can exchange sufficient numbers of electrons with the surrounding space plasma.

Experimental data from the TSS-1R data also produced the amazing result that the efficiency of a bare metal surface in "contacting" the space plasma is many times better than the standard theory would predict. The 8 square meters of bare surface area of the Italian spacecraft were sufficient to collect the 1.1 A of electron current. This amount of area is easily replicated by a few hundred meters of bare wire, considering that the effective collection diameter around the wire is the Debye length, which is a few centimeters at the typical values for space plasma density and temperature.

Because of this result, that a bare wire can easily collect electrons, Les Johnson, Nobie Stone, Chris Rupp, and others

at NASA Marshall Space Flight Center have formed a team, which includes the present inventors, which is embarked on a new flight experiment. The experiment is scheduled for a piggy-back flight on a Delta II launch of an AF Global Positioning Satellite in early 2000. The goal of the experiment is to demonstrate that electrodynamic drag from a wire moving at orbital speeds through the Earth's magnetic field will create a large enough electrodynamic drag force to deorbit the Delta II second stage, whose mass is greater than 1000 kilograms, in a few weeks. This is essentially a demonstration of the Loftus electrodynamic drag deorbit concept and the first step in the development of a Terminator Tether™.

The ProSEDS (Propulsion Small Expendable-tether Deployer System) mission will use a 5 km long copper wire conductive tether massing 18 kg connected to a 20–35 km long nonconducting tether, which is in turn connected to a 25–40 kg ballast mass. The total of 25–40 km of tether length and the 25–40 kg ballast mass on the end will provide enough gravity gradient force to keep the tether aligned near the zenith, so that the direction of the current in the tether is at right angles to both the direction of the spacecraft motion in the nominal EW direction and the Earth's near-equatorial magnetic field in the nominal NS direction.

An important feature of the ProSEDS experiment is that it is designed to be completely self-powered. It uses a battery to initiate deployment and to power up the plasma contactor, but once current is flowing through the tether, some of the power is tapped off and used to recharge the battery. The battery, in turn, powers the current control electronics, the telemetry, system, and the plasma contactor. The ProSEDS mission will not be designed to allow ground control changes in operation, primarily because of the increase in complexity and cost associated with that option.

The present invention is the use of a small, low-mass deployer/controller package containing a large collecting area, short length, multiline space tether, such as a Hoytape mesh made of aluminum wire, as a "Terminator Tether™" for a constellation spacecraft. The Terminator Tether™ would be deployed when the host spacecraft is no longer working or no longer wanted. The electrodynamic drag from the Terminator Tether™ would rapidly remove the unwanted spacecraft from the constellation and a few weeks later complete the deorbit of the host spacecraft from space by burnup in the upper atmosphere of the Earth. For a Terminator Tether™ to be of maximum usefulness for constellation spacecraft, it would be desirable to minmize the mass and the length of the tether. A lower added mass means more mass for revenue producing transponders, while a shorter tether length means a lower collision cross-section Area-Time Product during deorbit.

FIG. **6** shows a spacecraft **600** having a state vector **602** that causes the spacecraft to move across magnetic field lines **601**. Spacecraft **600** has a conductive tether **603** attached to it by tether deployer and control system **605**. The outer end of tether **603** is attached to tether end mass **607**. Spacecraft **600** also has an attached electron emitter means **613**.

In FIG. **6**, spacecraft **600** has a velocity and direction defined by state vector **602**. As spacecraft **600** moves it causes conductive tether **603** to cut magnetic field lines **601**. As this happens the distal end of the conductive tether collects electrons, shown as arrows **611**, from the space plasma. Electrons **611** move through the conductive tether **603**, are passed through a resistive load, not shown, in control system **605**, and are emitted back into the space plasma as electrons **615** from electron emitter **613**. This produces an electrodynamic drag in the direction shown by arrow **609**.

As is discussed in detail in the electrodynamic drag analysis below, especially in that sections of the analysis titled "Optimization of Tether Angle", the maximum electrodynamic drag of the tether is achieved when the angle, shown as the Greek letter τ in FIG. **6**, is 35.26 degrees, trailing, to the direction of the magnetic field lines. This angle may be maintained by a feedback control circuit that maximizes the electrodynamic drag of the tether system, as is discussed in detail below. The tether structure **603** is a Hoytether having a length of about 2 to 5 kilometers. The use of the 35.26 degree angle to the magnetic field reduces the tether instability, allowing the use of a short tether which will have a small Area-Time-Product. This will minmize the possibility that the tether will impact another space object during its use.

In FIG. **7**, spacecraft **700** has a state vector **702** across magnetic field lines **704**. Conductive tether **706** is attached to spacecraft **700** by tether deployer and control system **708**. The distal end of tether **706** is attached to a tether end mass **710**. Spacecraft **700** has an electron emitter means **714**.

Functionally, electrons **712** flow from the space plasma into conductive tether **706**, are passed through a resistive load in control unit **708** and are emitted into the space plasma by electron emitter **714** as free electrons **716**. As is discussed in detail in the analysis below, this produces an electrodynamic drag on satellite **700**, which causes it to deorbit.

In FIG. **7**, spacecraft **700** is rotating with an angular velocity indicated by arrow **718**. This rotation causes a centrifugal force **720** to place tension on conductive tether **706**. This force **720** places tension on the tether **706** in a direction that counters tether instability. The Tether **706** may be at any angle to the magnetic field while the rotation of the tether-satellite system is producing this useful tension. FIG. **7** shows the angle to be 35.26 degrees, which is optimum, but any angle will work.

FIGS. **8***a* and **8***b* show a powered Terminator Tether™. In FIG. **8***a* the spacecraft **800** has a state vector **802** that causes it and its associated conductive tether **806** to move across magnetic field **804**. Tether **806** has an end mass **808** that is proximate a plasma contactor **810**. Just as was discussed in the embodiment of the present invention shown in FIG. **6** and FIG. **7**, an electric current moves through the circuit formed by the space plasma, the plasma contactor **810**, the conductive tether **806**, and the electron emitter **815**, thence back into the space plasma as electrons **816**. This creates an electrodynamic drag on the tether in the direction shown by arrow **818**.

In FIG. **8***b*, similar numbers indicate similar structures. In FIG. **8***b*, however, an electric power source, not shown, in spacecraft **800** provides electrons to conductive tether **806**. The electrons are emitted from the end **812** of the tether **806**. Electrons are collected to from the space plasma **814** by contactor **815**, thus completing the electric circuit. The result is an electrodynamic force on tether **806**, and therefore on spacecraft **800**, in the direction show by arrow **820**.

Spacecraft **800** in FIG. **8***b* may be rotated as is taught in the embodiment of the invention shown in FIG. **7**, above, to allow the control system to time the application of electric current to the tether **806** to cause force **820** to be exert force in any desired direction along the circle made by the rotating tether. This allows the state vector of the spacecraft to be modified to raise or lower the spacecraft's orbital altitude, or to otherwise usefully change its orbital elements.

FIG. **9** show an embodiment of the present invention wherein the conductive structure of a satellite is used as the tether. In FIG. **9**, a spacecraft **900** which has a state vector

901 and is moving across magnetic field **903**, has two attached solar panels, **902** and **904**. Solar panels **902** and **904** have conductive aluminum frames **908** and **906**, respectively. Frame **906** is electrically and mechanically connected to plasma contactor **912**. Frame **908** is electrically and mechanically connected to electron emitter **910**. As spacecraft **900** moves across magnetic field **903**, electrons from the space plasma **914** flow through contactor **912** and frame **906** to the body of spacecraft **900**, where the current flows through a resistive load, not shown, and then into frame **908** and electron emitter **910** to the space plasma **916**, thus completing the circuit. This creates an electrodynamic drag on spacecraft **900**. If the power output from solar panels **902** and **904** was directed to flow into the frames, **906** and **908**, then the electrodynamic interaction with the space plasma would cause a useful force to be impressed on spacecraft **900**, as was discussed in connection with FIG. **8** above. The spacecraft may be rotated and/or oriented to a desired angle with the magnetic field lines, as was also discussed above.

FIG. **10** shows an embodiment of the present invention wherein the plasma contactor and the resistive load are structurally part of the conductive tether. In FIG. **10** spacecraft **1000** has a state vector **1001** that causes it to pass through magnetic field **1003**. Spacecraft **1000** has a tether control and deployment system **1005** that is connected to a conductive tether **1007** having an end mass **1013**. A contactor portion **1015** of the conductive tether **1007** near end mass **1013** is adapted to contact the space plasma so as to receive or emit electrons. This may be the bare wire strands of a wide Hoytether, or it may be any other plasma contactor means that can be conveniently made electrically part of the Hoytether structure, such as points or metal fuzz. A second resistive portion **1009** of tether structure **1007** is adapted to be a resistive load. This may be done by making a portion of the tether structure from a material, such as nichrome steel wire, that has suitable electrical resistance The large surface area of the Hoytether provides an excellent radiator structure into the three degree Kelvin radiation sink of outer space.

FIG. **11** shows an alternative embodiment of the load resistance/radiator structure of the present invention. In FIG. **11**, a biline Hoytether **1002** is attached to its control and deployer system **1100** on a spacecraft, not shown, and to a tether end mass **1004**. A resistive load, **1006** is woven into the Hoytether structure, whereby this load **1006** and the section of the Hoytether **1002** into which it is woven act together as a thermal radiator allowing photons **1008** to radiate into the thermal sink of outer space.

The following detailed analysis of the present invention will help those skilled in the art to better understand and use the present invention.

Electrodynamic Drag Analysis:

The following is an optimization analysis of the electrodynamic drag produced by a conducting tether deployed from a host spacecraft that it is to deorbit. The force and torque diagram used in the analysis is shown in FIG. **12**, which shows the forces and torques on an upward deployed conducting tether due to the motion of the host spacecraft through the magnetic field of the Earth.

Physical Constants and Assumptions:

The analysis that follows will use the following physical constants and assumptions:

Newton's gravitational constant $G=6.67\times10^{-11}$ $m^3/kg\text{-}s^2$.
Mass of Earth $M_e=5.976\times10^{24}$ kg.
Radius of Earth near equator $R_e=6378$ km.
Assumed host spacecraft altitude h=622 km.
Assumed host spacecraft orbital radius a=7000 km.
Host spacecraft orbital velocity $w=\omega a=[GM_e/a\,]^{1/2}=7546$ m/s.
Vertical gravity gradient at spacecraft $2\Gamma=2GM_e/a^3=2.32\times10^{-6}\ s^{-2}$.
Centrifugal gradient at spacecraft $\omega^2=GM_e/a^3=1.16\times10^{-6}\ s^{-2}$.
Combined gradient at spacecraft $3\Gamma=3GM_e/a^3=3\omega^2=3.49\times10^{-6}\ s^{-2}$.
Magnetic field of Earth (tilted dipole approximation):
  Magnitude $B_o=35\ \mu T=0.35$ gauss.
  Angle between magnetic pole and spin pole 11.5°.
  Field components at spacecraft with altitude a and angle β between radius vector of spacecraft and magnetic equatorial plane.
  Horizontal $B_H=B_o(R_e/a)^3\cos\beta=26.5\ \mu T\cos\beta$.
  Vertical $B_V=2B_o(R_e/a)^3\sin\beta=52.9\ \mu T\sin\beta$.

Electrodynamic Tether Constants and Assumptions:

The electrodynamic tether is assumed to be made of a conducting metal, and have a length L, density d, resistivity r, and cross-sectional area A that is constant along the length of the tether. If the tether is a single round wire of diameter D, then the cross-sectional area is $A=\pi D^2/4$. Because of the micrometeorite and space debris hazard, however, it is likely the tether will be made up of redundantly interconnected multiple lines whose individual cross-sectional areas add up to A. Given these assumptions, the tether mass is then $m_T=dLA$, while the end-to-end tether resistance is $R_T=rL/A=rdL^2/m_T$.

Specific Conductivity Parameter:

The choice of the metal conductor to be used in a space tether is determined by a combination of low resistivity (high conductivity) and low density, with cost, strength, and melting point as secondary considerations for certain applications. Copper has a resistivity r=17.0 nΩ-m, a density d=8933 kg/m, and a "specific conductivity" of 1/rd=6,585 $m^2/\Omega\text{-}kg$. Aluminum has a resistivity r=27.4 nΩ-m, which is significantly greater than that of copper, but it has a much lower density of d=2700 kg/m^3. As a result, aluminum's "specific conductivity" of 1/rd=13,500 $m^2/\Omega\text{-}kg$ is twice the conductivity per unit mass of copper. Silver, because of its higher density and higher cost, is not competitive as an electrodynamic space tether even though its resistivity of 16.1 nΩ-m is slightly better than that of copper. An alternate candidate material would be beryllium, with a resistivity r=32.5 nΩ-m, density d=1850 kg/m^3, and a "specific conductivity" of 1/rd=16,630 $m^2/\Omega\text{-}kg$, slightly better than that of the much cheaper aluminum. Beryllium also has a higher melting point at 1551 K than aluminum at 933 K, so some of its alloys may be a preferred material for some electrodynamic applications despite its higher materials cost. Unfortunately, despite decades of metallurgical research by the nuclear power industry, highly ductile alloys of beryllium have not been found, so it is difficult to pull beryllium into wire. As a result, because of its high specific conductivity, low cost, and ready availability in ductile wire form, it will be assumed for this analysis that the electrodynamic tether will be made of aluminum wire.

Typical Resistance Values:

To be economically competitive, the mass of the tether needs to be a small fraction of the mass of the host spacecraft it is required to deorbit. Since a typical constellation spacecraft has a mass of about 1000 kg, a typical Terminator Tether™ with a mass that is 2% of the host spacecraft mass would consist of a deployer/controller package with a mass $m_D=10$ kg, containing an aluminum tether with a mass $m_T=10$ kg with a volume of $LA=m_T/d=3.70\times10^{-3}\ m^3$. If this 10 kg of aluminum were formed into a tether with a length

of L=2 km and a cross-sectional area of A=1.85 mm^2, then the end-to-end resistance of the tether would be R=rL/A=rdL^2/m$_T$=29.6 Ω A longer tether would have a proportionately smaller cross-sectional area and a higher resistance; for example, a 5 km long tether with the same mass would have a resistance of 185 Ω.

Orbit Inclination Assumption:

In order to make the remainder of the analysis mathematically tractable, it will be assumed that the orbit of the host spacecraft is circular and above the magnetic equator, so that the angle between the radius vector to the spacecraft and the magnetic equatorial plane is β=0 degrees. In this orbit, the velocity v of the spacecraft with respect to the magnetic field is the orbital velocity w less the rotational velocity of the magnetic field at the orbital radius a due to the once per day rotation of the Earth, or:

$$v=W-2\pi a/1\text{day}=(7546-509)\text{m/s}=7037\text{m/s}$$

This equation also shows why electrodynamic drag will not be useful for removing geostationary spacecraft from orbit. At the geostationary orbital radius of a=42,200 km, the relative velocity of the spacecraft and the rotating magnetic field of the Earth is zero.

With this assumption of an orbit above the magnetic equator, the vertical component of the Earth's magnetic field is zero and the horizontal component of the Earth's magnetic field is at right angles to both the local vertical and the direction of motion of the spacecraft. The total magnetic field seen by the host spacecraft and its Terminator Tether™ is then orthogonally horizontal and has the magnitude:

$$B=B_H=B_o[R_e/a]^3\cos\beta=26.5\mu\text{T}.$$

Where for simplicity the subscript H will be dropped for the remainder of this analysis.

This orbit, with its inclination of 11.5° with respect to the spin equator, will not stay in the plane of the magnetic equator, but will vary ±11.5° above and below it as the Earth rotates, causing a variation in magnetic field strength of ±0.5 μT, as well as a slight variation in angle. This 2% variation is negligible in terms of the other uncertainties in this analysis. It is not until the orbital inclination of the host spacecraft orbit reaches 60°, where cos 60°=0.5, that there is a significant drop in the expected magnitude of the electrodynamic drag forces calculated in this analysis.

Electromagnetic Drag Effects in Polar Orbit:

In many medium Earth orbit communication satellite constellations, there are a significant number of spacecraft at high inclinations and in nearly polar orbits. The high inclination spacecraft, with inclinations between 60° and 78.5°, will all have orbits that stay between the magnetic poles. Although the amount of electrodynamic drag will be significantly less than that experienced by spacecraft with orbits at lower inclinations, the direction of the induced electric fields in the tether will always be in the proper direction. If the tether is vertically upward, the outer tip of the tether will be positively charged and the bare wire in the tether will pull electrons out of the surrounding space plasma, while the electron emitter at the host spacecraft end will eject the electrons back into the space plasma to complete the circuit.

For spacecraft in near polar orbits with inclinations between 78.5° and 90°, however, there will be much more drastic variations. First of all, for a spacecraft in a 90° orbit that happens to pass directly over the magnetic poles, there is no horizontal component of the magnetic field when it is passing over one of the magnetic poles, so no voltage is generated in the tether during that part of the orbit, while the horizontal component of the magnetic field near the magnetic equator, while strong in magnitude, is along the spacecraft velocity vector, so no voltage is generated in the tether in that part of the orbit either. As a result, there will be negligible electrodynamic drag experienced by the host spacecraft during that particular orbit. The Earth is rotating, however, and the magnetic pole is rotating with it. A few orbits later, the host spacecraft will be passing over the Earth's spin pole at a point where the horizontal component of the magnetic field is exactly at right angles to the direction of motion of the spacecraft, so the full voltage is generated in the tether. When passing over the spin pole, the spacecraft radius vector is at an angle of 11.5° from the magnetic pole and at an angle β=78.5° away from the magnetic equatorial plane. With these assumptions, the magnitude of the horizontal component of the magnetic field at the Earth's spin pole is a respectable:

$$B=B_o[R_e/a]^3\cos 78.5°=5.28\mu\text{T}$$

or 20% of the maximum value experiences by spacecraft orbiting above the magnetic equator. This value will drop slightly as the orbit continues, then build back up as the spacecraft passes over the opposite pole. As the Earth continues to rotate, bringing the magnetic pole again under the orbit, and the interaction of the tether with the horizontal component of the magnetic field again drops to zero. The average coupling of a tether to the Earth's magnetic field over all polar trajectories has been calculated to be 12.3 percent.

A problem experienced only by spacecraft with orbit inclinations greater than 78.5°:

The spacecraft will no longer be traveling from west to east with respect to the magnetic field axis, but will have a retrograde motion as it moves through the magnetic field. As a result, the voltage generated by the motion of the tether through the Earth's magnetic field will switch direction. The outer tip will be negatively charged and will attempt to collect ions, which is a much less efficient process than collecting electrons.

There are a number of solutions to this problem. The first is to increase the mass and length of the tether supplied to a spacecraft assigned to a polar orbit, so that higher voltages, currents, and drag are generated during the limited times the spacecraft is passing over the poles in the right direction. The second is to supply a tether with plasma contactors at both ends that can emit electrons from either end, allowing the current to flow either way, depending upon which direction the spacecraft is passing around the magnetic pole. The third is to utilize the first number of passes to torque the orbit of the spacecraft until the orbit inclination has been shifted below 60°, then turn on the electrodynamic drag full time to deorbit the spacecraft from this more favorable orbit inclination. This orbit torqueing maneuver is accomplished by activating the electrodynamic drag mechanism only when the magnetic field orientation is such that a strong out-of-plane component of force is created. This orbit torqueing maneuver can be augmented by switching to a propulsion mode, where power saved in the batteries during the drag force mode is pumped back into the tether when the magnetic field is in the opposite direction, applying electrodynamic propulsion to torque the orbit even further. With the tether at a large and stable trailing orientation, the coupling to the magnetic field can be significant to a vertical tether.

In summary, spacecraft in near-polar orbits might take longer to bring down, and might have to utilize specially designed Terminator Tethers™ that might cost and mass

more than the simpler Terminator Tethers™ usable in lower inclination orbits, but a Terminator Tether™ can still remove a spacecraft from a polar orbit when desired.

The inventors now present a detailed analysis and optimization of a typical Terminator Tether™ attached to a typical host spacecraft in a typical low inclination orbit.

Electromotive Generation of Voltage and Current in the Tether:

When an object is moved at a velocity v through a magnetic field B, an electric field is generated in the frame of reference of the moving object given by:

$$E = v \times B = vB$$

where the magnetic field B of the Earth, being mostly tangent to the Earth's surface in the north-south direction, is at right angles to the velocity vector v of the spacecraft, assumed to be orbiting in a generally west-east direction. The direction of the electric field E will be at right angles to both v and B, or along the local vertical. It should be noted that this electric field exists in the moving frame of reference because a moving magnetic field creates an electric field. No object actually has to be there, but if it is, then the relative motion of the magnetic field of the Earth will not only apply magnetic forces to whatever material the object is made out of, but electric forces too.

Note also that the velocity used in this equation is the relative velocity between the object and the magnetic field. Because the Earth's magnetic field rotates with the Earth, the motion of the magnetic field must be subtracted from the orbital velocity of the object to obtain the relative velocity.

Voltage generation in a Conducting Tether:

If the moving object is a long conducting wire of length L, the electric field E, generated in the wire produces a voltage V between the opposite ends of the wire given by:

$$V = E \bullet L = EL \cos \tau = vBL \cos \tau$$

where τ is the angle between the length vector L of the tether and the electric field vector E, assumed to be in the vertical direction at right angles to the velocity vector v in the plane of FIG. **12** and the magnetic field vector B out of the plane of FIG. **12**. A typical value for the voltage level built up in a vertically oriented tether with length L=5 km and τ=0, moving at a velocity of v=7037 m/s through the Earth's horizontal magnetic field of strength 26.5 μT, is 932 V, or 0.186 V/m. Spacecraft in higher inclination orbits would experience somewhat smaller electric fields. For calibration, the voltage measured between the ends of the 19.5 km long TSS-1R tether was 3500 V, or 0.175 V/m.

Contacting the Space Plasma:

Although a voltage will build up between the ends of the conducting tether, no current will flow unless the circuit is completed. The circuit cannot be completed with another wire, for it too will have a similar voltage generated in it by the moving magnetic field. Fortunately, empty space is not empty, and in near-Earth regions not too distant from the Earth's atmosphere there exists highly electrically conductive space plasma, kept partially ionized by radiation from the Sun. The electron and ion density varies from the dark to light side, with altitude, with season, with sunspot cycle, with contamination level, etc. but it typically varies from 10^{11} to 10^{13} electrons/cc.

Fortunately, it has been found that if a bare conductive surface such as the spherical Italian spacecraft in the TSS-1R experiment, or the long bare wire to be used in the ProSEDS experiment, or a multiline conducting wire Hoytape mesh, is charged to a few hundred volts, the bare conductor will readily pull electrons out of the space plasma. So all that is needed to complete a connection to the space plasma at the positively charged (upper) end of the tether is a sufficient large area of uninsulated conductor.

It is more difficult to eject electrons from a wire or to collect positive ions from the space plasma. Although it is conceivable that a very large area at the other end of the tether could collect enough ions to complete the circuit as was demonstrated during the TSS-1R mission when the Shuttle orbiter was found to be an adequate plasma contactor for over an amp of current, the present method chosen is to use an electron emitter of some sort, either a hot cathode, a plasma cathode or contactor, a field-emission device, or something similar. Once provisions have been made at both ends of the tether to allow the flow of electrons out of one end of the tether and into the other end, and the altitude of the host spacecraft is not too high, then there will be sufficient conductivity in the space plasma surrounding the host spacecraft to allow current to flow through the tether.

Current Flow In The Tether:

The amount of current I flowing through the tether depends upon the total resistance R in the circuit. This resistance will consist of three components, the effective resistance of the plasma, the resistance of the tether, calculated earlier as $R_T = rL/A = rdL^2/m_T$, and a control resistor R_C, which will be varied as needed to optimize the Terminator Tether™ performance. There will also need to be a parasitic load on the current in the form of a charging device to charge some batteries. The batteries in turn will be used to power the control and communication circuits, and drive the electron emitting devices at the negative end of the tether. A well-designed Terminator Tether™ will thus be completely self-powered, except for an initial charge in the batteries to provide electrical power for the deployment and startup procedure. For simplicity of analysis it will be assumed that this battery charging load, which absorbs power like a resistor, but which stores it and uses it later instead of dissipating it immediately as heat, is included in the control resistor R_c. Normally, this load would act as a "base resistance" below which the control resistor could not be lowered, but since the charging circuit can be turned off when desired, and operations continued without interruption using the power stored in the batteries, it will be assumed that the control resistor can be taken to near zero value in those circumstances where the space plasma conductivity is low, or the magnetic field is in the wrong orientation and the voltage being generated in the tether is not large. Under these circumstances, lowering the control resistor to near zero allows a much higher current to flow for a given generated voltage, thus increasing the power being dissipated in the tether and maintaining a high level of electrodynamic drag on the host spacecraft.

A properly designed Terminator Tether™ will have plenty of bare metal area for electron collection at the positive end, while the electron emitters at the other end are efficient in terms of emitting large electron currents at low voltages and therefore low powers, while at the same time the mass, length, and area of the conducting tether have been made such that the resistance of the tether is moderately high. Under these conditions, the effective resistance of the space plasma will be much less than the design resistance of the tether. To make the mathematics more tractable it will be assumed that the plasma resistance is can be neglected and that the voltage available to drive the tether is the full voltage generated by the moving magnetic field. Although voltage will be needed to power the electron emitter, what-

ever its form, it will be assumed that the required voltage and power will be supplied by the batteries. The batteries in turn will be powered by the battery charging circuit, whose effective resistance is included in the control resistor (except for those short periods when the plasma or magnetic field interactions are weak).

Given all these assumptions concerning the total resistance in the circuit, the current I flowing through the tether is then given by:

$$I=V/R=vBL\cos\tau/(R_C+rdL^2/m_T)$$

A typical current level can be estimated by assuming that the control resistance R_C should be about the same size as the tether resistance R_T, which for an aluminum tether with resistivity r=27.4 nΩ-m, density d=2700 kg/m^3, length L=5 km, and mass m_T=10 kg, is R_T=185 Ω, giving a total resistance, including the control resistance R_C, of R=370 Ω. Thus the current flowing though a tether of length L=5 km, generating a voltage of V=932 V, would be I=V/R=2.52 A.

Power Dissipation Analysis:

The induced current I flowing through the tether resistance R_T will generate heat in the wire, which will be radiated into space and lost. That radiated energy must come from somewhere. There is also power taken out of the current flow by the battery charging circuit and ultimately dissipated. In order to conform to energy conservation laws, this power and energy must come from a decrease in the total kinetic and potential energy of the host spacecraft, causing it to deorbit. Set forth below is a detailed, optimized force analysis which will calculate the drag force on the host spacecraft. In this section, by using some simplifying assumptions, it is possible to produce a general argument based on energy conservation laws, which will illustrate the broad scope of the present invention.

For this energy conservation analysis it will be assumed that the plasma resistance is small compared with the tether resistance, and that the control resistance is equal to the tether resistance:

$$R_C=R_T=rL/A=rdL^2/m_T$$

Assume that the ballast mass at the end of the tether is a large piece of the defunct host spacecraft, such as a solar panel, antenna, or battery pack, so that the gradient force is large and the tether is always oriented along the vertical so that the angle τ=0°. Also assume the spacecraft is in an orbit above the magnetic equator and thus is moving at right angles to the Earth's magnetic field, so that the angle between the orbital velocity vector and the magnetic field vector is 90°, and the electric field vector is in the vertical direction, aligned perfectly with the tether length vector. Under these ideal conditions, the voltage between the ends of the tether is given by:

$$V=E\bullet L=(v\times B)\bullet L=vBL$$

The current in the tether is then just:

$$I=V/(R_C+R_T)=vBm_T/2rdL$$

The power dissipated as ohmic heating in the tether is then given by:

$$P=IV=(vB)^2m_T/2rd$$

This equation shows the interesting result that the power dissipated does not depend upon the length or the area of the tether (within reason), but only the mass of the tether m_T, the

resistivity r and density d of the tether material, and the velocity v of the conducting tether through the Earth's magnetic field B.

For a typical aluminum tether of mass m_T=10 kg, the power dissipated is an impressive P=2350 W. Even if only a small fraction of this power is dissipated in a real system, the kinetic energy of the host spacecraft would suffer a significant energy loss with time.

Orbital Energy Extraction Analysis:

The total energy U of a spacecraft of mass M in orbit around the Earth consists of two components, its positive orbital kinetic energy and its negative gravitational potential energy. If a circular orbit of altitude h and radius a=R_e+h is assumed, then the total energy of the spacecraft moving at a velocity w=$(GM_e/a)^{1/2}$ is:

$$U=+Mw^2/2-GMM_e/a=-GMM_e/2a$$

The system will be dissipating energy in the tether to decrease the energy U of the unwanted spacecraft from its relatively low negative value in a high Earth orbit to a greater negative value in a lower Earth orbit. To give a specific example, an unwanted spacecraft with a mass of M=1000 kg (a metric ton) in an orbit with an altitude of h=1000 km and a high orbital radius of a(H)=R_e+h=7371 km, then its (negative) total energy is:

$$U(H)=-GMM_e/2a(H)=-27.1\text{ GJ or }-27.1\text{ MJ/kg}$$

It is desired to lower the spacecraft to an orbit with an altitude just outside the atmosphere of h=200 km or a lower orbital radius of a(L)=R_e+h=6571 km, where atmospheric drag will finish the job. The total (negative) energy of a metric ton spacecraft at 200 km altitude is:

$$U(L)=-GMM_e/2a(L)=-30.4\text{ GJ}$$

Thus, the amount of energy needed to be dissipated in order to move the 1000 kg spacecraft from a 1000 km orbit with a total energy U(H)=−27.1 GJ down to a 200 km orbit with energy U(L)=−30.4 CJ is:

$$dU=U(H)-U(L)=3.3\text{ GJ.}$$

The decay time T of a metric ton spacecraft moving from a 1000 km altitude orbit to a 200 km altitude orbit with an energy difference of dU=3.3 GJ, when its energy is being dissipated at a power of P=2350 W by a typical aluminum tether massing just 10 kg or 1% the mass of the spacecraft, is found to be T=dU/P=16 days.

The actual decay time will be longer than this. If the electrodynamic drag force is very large, and becomes larger than the gravity gradient forces pulling on the ends of the tether, then the tether will tend to align itself along the magnetic field lines instead of across them, and the drag force will decrease because of the small angle between the conductor length and the magnetic field lines. The tether current will need to be controlled until the angle of the tether settles into an angle determined by the balance between these two forces. These electrodynamic torque vs. gradient torque dynamic interaction effects are discussed in the next section.

Force and Torque Balance Analysis:

It is now possible to calculate the forces and torques on the tether. It is also possible to use the fact that the electrodynamic and gravity forces and torques on the tether must balance each other out to calculate and teach some optimum values for some of the Terminator Tether™ parameters.

Electrodynamic Force and Torque:

As discussed above, both theory and experiment show that: provided the conducting tether is moved rapidly through the Earth's magnetic field in order to generate a voltage across it, and provided good contact is made with the space plasma, the conducting tether will have a current flowing through it. When a wire (moving or not) carrying a current I is embedded in a magnetic field B, there will be an electrodynatnic force F_E generated on each element of the wire. The electrodynamic force will be at right angles to the magnetic field vector and the length vector of the wire element, with a magnitude given by:

$$F_E = J \times B = ILB$$

where B is the horizontal component of the magnetic field, which is perpendicular to the assumed magnetic equator orbit plane, while the tether length vector L is assumed to lie in the orbit plane. If, as will be the case most of the time, the electron current is leaving the space plasma and entering the tether along the length of the tether, then IL needs to be replaced with an integral of the current along the length of the tether.

Note that the electrodynamic force amplitude or direction is not directly dependent on the motion of the tether through the Earth's magnetic field. The electrodynamic force would be the same if the tether were not moving and the current was being supplied by a battery. Since the current I is a function of the orbital velocity, however, there is a secondary dependence of the electrodynamic force magnitude on the orbital velocity, but not its direction. The electrodynamic force is always at right angles to the conductor, and stays at right angles to the conductor as the angle τ varies, as shown in FIG. **12**.

Assuming that the electrodynamic drag force is applied uniformly along the length of the tether, it is possible to make the simplifying assumption that the integrated force is effectively applied at right angles to the center of mass of the tether at the point L/2 as shown in FIG. **12**. The electrodynamic torque on the tether is then:

$$T_E = F_E L/2 = IBL^2/2 = vB^2L^3 \cos\tau/2(R_C + rdL^2/m_T) = vB^2L^3 \cos\tau/2R$$

Gravity Gradient Forces and Torques:

When a tether and its ballast end mass are deployed from a host spacecraft, the gravity gradient force field of the Earth, combined with the orbital centrifugal gradient force field, will cause the tether to deploy either up or down from the host spacecraft. The direction desired depends on which end of the tether is connected to the electron emitter. Normally, the electron emitter will be on the end attached to the host spacecraft, in which case the desired direction of deployment will be upward so that the induced voltage in the tether will produce an excess of electrons at the electron emitter end of the tether. The desired upward direction is chosen by having the deployer eject the ballast mass in the upward direction. Once the ballast mass has been started in that direction, the centrifugal force due to the orbital motion of the ballast mass will cause the ballast mass to continue to accelerate in the upward direction until it is brought to a halt by the full deployment of the tether.

If there were no electrodynamic or atmospheric drag, the equilibrium direction of the tether would be exactly along the vertical, since the combined gradient field is a maximum in that direction. Because a significant amount of electromagnetic drag is expected, the actual angle of the tether with respect to the local vertical will be at some angle τ, lagging behind the spacecraft motion in the plane of the orbit, as shown in FIG. **12**. In the following analysis shows that there is an optimum angle for τ that produces the largest electrodynamic drag force on the host spacecraft without producing tether instability.

The combined vertical gravity gradient and centrifugal gradient field 3Γ acting on the ballast mass m_B at the end of the tether of length L will produce a gradient force F_{GB} given by:

$$F_{GB} = -3_\Gamma m_B L \cos\tau$$

The strength of the force depends not only on the ballast mass m_B and the strength of the gradient field 3Γ, but also the component along the radial direction of the distance of the ballast mass from the center of mass, which is L cos τ. This force acts in the vertical direction along the radius vector leading from the ballast mass away from the center of the Earth. The amount of gradient force is not large. For a ballast mass of m_B=10 kg and a tether length of L=5 km, the gradient force is about 0.175 N.

As can be seen in FIG. **12**, the component of this gradient force that is at right angles to the tether, given by $F_{GB} \sin\tau$, will produce a torque T_{GB} on the tether that tends to restore the tether toward the vertical, lessening the angle τ.

$$T_{GB} = LF_{GB} \sin\tau = -3_\Gamma m_B L^2 \sin\tau \cos\tau$$

The tether mass m_T also contributes to the gradient force and torque. If it is assumed that the tether has a uniform cross section, then it is possible to replace the distributed mass of the tether with an equivalent point mass m_T placed at the center of mass of the tether, which is the point L/2 along the tether, and a distance L/2 cos τ in the radial direction. The gradient force due to the tether mass is then:

$$F_{GT} = -3/2_\Gamma m_T L \cos\tau$$

While the gradient torque is:

$$T_{GT} = -L/2F_{GT} \sin\tau = -3/4_\Gamma m_B L^2 \sin\tau \cos\tau$$

The total gradient torque attempting to restore the tether to its vertical orientation is then:

$$T_G = T_{GB} + T_{GT} = 3_\Gamma (m_B + m_T/4) L^2 \sin\tau \cos\tau$$

It is important to notice the variation of the total gravity gradient torque as the tether angle τ is varied. Since the gradient force is always in the radial or vertical direction, there is no torque on the tether when the tether is vertical, as is the case when there are no aerodynamic or electromagnetic drag forces. Once the drag forces become important and start to apply torque to the tether, increasing the tether angle τ, those drag torques causing an increase in tether angle τ will be opposed by a rising gradient torque which will attempt to decrease the tether angle. For small tether angles, the gradient torque increases first linearly with τ, then as sin τ, since cos τ is near unity for small τ, then at τ=45° the gradient torque reaches its maximum, where sin τ=cos τ=0.707 and sin τ cos τ=0.50. When this angle is reached, the tether is a point of catastrophic instability, for if there is a further increase in the electrodynamic drag force, causing the angle τ to become greater than 45°, the gradient torque, instead of growing stronger to counteract the increased drag torque, will become weaker and the tether angle will go rapidly to 90°.

To restore control to the tether angle if the instability occurs, it will be necessary to turn off the electrodynamic drag forces by shutting off the current flow through the tether. The τ=90° position for the tether and ballast mass is

a gravitationally unstable orientation. After a time, slight fluctuations in the gravity field will allow the gradient force to slowly take over and restore the tether to the vertical orientation, which, unless it can be controlled in some way, is equally likely to be up or down. It would therefore be desirable to maintain control of the tether angle so as to avoid the tether angle getting into the region of instability.

Torque Balance on the Tether:

The angle τ of the tether is determined by a balance between the electrodynamic torque T_E attempting to increase the angle τ and the gradient torque T_G attempting to decrease the angle τ. Balance is achieved when the two torques are equal:

$$T_E=T_G=T_{GB}+T_{GT}$$

or:

$$vB^2L^3 \cos \tau/2R=3_{\Gamma}(m_B+m_T/4)L^2 \sin \tau \cos \tau$$

Simplifing and rearranging yields an equation giving us the angle τ at which torque balance occurs:

$$\tau=\arcsin[vB^2L/6_{\Gamma}(m_B+m_T/4)R]$$

The physical interpretation of this equation is that the maximum electrodynamic force that can be sustained on the tether is limited by the gradient force on the tether. It is possible to increase the electrodynamic force by decreasing the total resistance R of the tether (for example, by using a tether with a larger mass and a lower tether resistance), but if the tether resistance is too low, then the quantity in brackets becomes greater than unity and this equation has no solution, indicating that the tether has reached an angle where instability sets in.

To maintain control of the tether angle, it will be necessary to vary the control resistance of the tether to compensate for variations in magnetic field strength and direction, plasma density (which affects the plasma resistance), and other factors, and thereby maintain the tether at an intermediate angle where both the electrodynamic and gradient forces are at an appreciable level and balance each other.

Optimization of Tether Angle:

At first glance, it might seem that the optimum angle for the tether would be 45°, since at that angle the gradient torque is largest and therefore can counteract a larger electrodynamic drag force. However, since the 45° angle is the point where instability sets in, it is desirable to set the tether angle at some value below 45°. The optimum angle is that which maximizes the horizontal or drag component of the electrodynamic force. This optimum angle τ is derived from the equation for the horizontal component of the electrodynamic force, or the electrodynamic drag force, since it opposes the host spacecraft motion:

$$F_{ED}=F_E \cos \tau=6[m_B+m_T/4]\Gamma L \sin \tau \cos^2\tau$$

By setting the partial derivative$\square F_{ED}/\square\tau=0$ and solving, it is possible to calculate that the optimum angle for the tether that gives the maximum electrodynamic drag force F_{ED}, while still keeping the tether torques balanced and under control, is τ=arctan(0.707)=35.26°. With this angle selected and maintained by varying the control resistor R_C to compensate for variations in plasma contact resistance and variatins in the strength and direction of the Earth's magnetic field B seen at the spacecraft, the tether experience the maximum stable value for the electromagnetic drag force of:

$$F_{ED}(\max,\tau=35.26°)=2.31[m_B+m_T/4]\Gamma L$$

There are many ways to provide the sensing information needed to provide the feedback signals to the control resistor, but the simplest is to merely measure the drag acceleration on the host spacecraft with a set of accelerometers, and maximiize the force in the direction opposite to the host spacecraft motion. Another method would be to measure the current in the tether, and knowing the tether resistance and the amount of control resistance, calculate the power being extracted and maximize that value. Alternate methods would be to use an optical position sensor or GPS receivers at both ends of the tether to measure the angle of the tether or the position of the ballast mass with respect to the host spacecraft.

To make an estimate of the magnitude of drag force attainable, assume that a typical aluminum tether with a length of L=5 km, a tether mass of m_T=10 kg and a ballast mass of m_B=10 kg is being used. Then the maximum gradient force limited electrodynamic drag force is F_{ED}=0.167 N. The power being dissipated in the canoical tether at the angle τ, with $R_C=R_T=rdL^2/m_T=185\ \Omega$ is given by:

$$P=IR=[vBL \cos \tau]^2(R_C+rdL^2m_T)$$

which for an angle τ=35.26° results in a power dissipation of 1570 W. Thus, the thrust level per unit power obtained by the typical Terminator Tether™ would be about 0.106 N/kW. This number is comparable to the value of 0.148 N/kW estimated for the much heavier and longer TSS-1R tether.

Reconciliation of Energy and Force Analysis:

By a force and torque balance analysis an optimum angle for the tether has been discovered at which it is possible to obtain a maximum in the drag component of the electrodynamic force. There is also an additional component of the electrodynamic force, the component in the vertical direction, $F_{EV=FE}$ sin(τ), which is downward for an upwardly deployed tether. This component of force combines with the gravity force of the Earth to effectively allow the host spacecraft to orbit a little faster than normal for that orbital altitude. It does not contribute to the deorbiting of the host spacecraft. But since this vertical component of force is created by current running through the tether, and that current is creating heat and dissipating energy as it passes through the tether, there might be some concern that the force and torque balance analysis above does not conform to the law of conservation of energy.

The inventors will now show, in a very general manner, that no matter what the tether angle, the electrical power being dissipated in the tether is exactly equal to the power being lost by the slowing of the host spacecraft.

The "deorbit power" P_D that must be removed from a spacecraft moving at a velocity v when that motion is opposed by a drag force F_{ED} is:

$$P_D=v\bullet F_{ED}=vF_E \cos \tau=vILB \cos \tau=I[vBL \cos \tau]$$

But, since the voltage V induced across the tether of length L and tilt angle τ moving at a velocity v through a horizontal magnetic field B is

$$V=E\bullet L=EL \cos \tau=vBL \cos \tau$$

Therefore:

$$P_D=IV=P_E$$

And the deorbit power P_D extracted from the slowing of the spacecraft by the drag component of the electrodynamic

force is always exactly equal to the electrical power P_E being dissipated as heat in the tether circuits, independent of the tether angle.

Optimization of Tether Mass Distribution:

If it is not possible to use a piece of the host spacecraft as ballast mass, then the mass of the ballast must be included in the Terminator Tether™ mass. It would be desirable to minimize the total Terminator Tether™ mass, since every kilogram saved means that another kilogram's worth of revenue-producing transponders can be added to the working payload of the host spacecraft. Given a total mass for the Terminator Tether™ and the mass of the deployer/controller unit, it is possible to optimize the mass distribution between the ballast mass and the tether mass to obtain a minimum total Terminator Tether™ mass. A well-designed Terminator Tether™ will also have most, if not all, of the deployer mass incorporated into the ballast mass.

Assume that the total Terminator Tether™ mass consists of the deployer/controller mass m_D, the tether mass m_T, and the ballast mass m_B, with $m_B > m_T > m_D$. Of the three mass components in the Terminator Tether™, two of them affect the electrodynamic drag performance. If it is assumed that the ballast mass is a factor X larger than the tether mass, or $m_B = Xm_T$, the maxinum drag force that can be obtained is now:

$$F_{ED}(\max)=2.31m_T(X+0.25)\Gamma L$$

If it is assumed that the control resistor has been adjusted so that this maximum value for the electrodynamic drag force is maintained as the motion of the spacecraft along its orbit moves the spacecraft into regions with different magnetic field strengths and plasma densities, then for the angle $\tau = 35.26°$, $\cos(35.26°) = 0.817$, and the maximum electrodynamic drag force in terms of the electrodynamic parameters will be:

$$0.817vB^2L^2/(R_C+rdL^2/m_T)=F_{ED}(\max)=2.31m_T(X+0.25)\Gamma L$$

or canceling out terms and rearranging:

$$(X+0.25)=0.353vB^2L/\Gamma m_T(R_C+rdL^2/m_T)$$

It is now possible to make the further simplifying assumption that to maintain control of the tether, the control resistor needs to be roughly the same size as the tether resistance or $R_C \approx rdL^2/m_T$. Using this assumption produces an equation for the optimum value for the ratio X of the ballast mass to the tether mass:

$$\begin{aligned} X = vB^2/\Gamma rdL - 0.25 &= -0.25 + \frac{vB^2}{12\sin\gamma\cos\gamma\Gamma rdL} \\ &= -0.25\frac{\Lambda}{L} \end{aligned}$$

Where Λ is the "effective electrodynamic length".

If the tether is short, so that L is small, this equation indicates that the ballast mass must be increased to increase the gradient force, since it is the gradient force which determines the upper limit to the amount of electrodynamic drag force that can be generated without losing control of the tether.

Assuming the usual values for the Earth's magnetic and gradient fields, the velocity of the host spacecraft through the magnetic field, and the resistivity and density of aluminum, this equation becomes:

$$X=10.9/L-0.25$$

where L is in kilometers.

For a typical tether of length L=5 km, X=1.93. If the total mass for the Terminator Tether™ is 20 kg, or 2% of the host spacecraft mass, and the mass of the deployer is 10 kg, then the remaining 10 kg should be distributed so that 6.59 kg is in the ballast mass while 3.41 kg is in tether mass.

Optimization of Tether Length:

If the ballast mass consists of a piece of the host spacecraft, then the mass of the ballast does not have to be considered in the optimization of the Tether system. In this case, the optimum distribution of the Tether mass is to put as much mass as possible into the tether, with a minimum in the deployer/controller package. Under this assumption, the optimum length of the tether is determined by the desire to keep the Area-Time Product of the host spacecraft plus Tether to a minimum.

In a long tether of length L, the effective "collision" cross-sectional area is not the area of the tether, but the larger area produced by multiplying the length of the tether by sum of the width of the tether plus the width of the "target" spacecraft that would be damaged by the tether hitting it. Thus, to decrease the "area" portion of the Area-Time Product, it would be desirable to shorten the tether, making it thicker, and perhaps slightly wider, at the same time, thus keeping the same tether mass and electron collection area, and thereby maintaining the drag force and keeping the decay time at the same level. The result will be a shortening of the Area-Time Product.

If the tether is shortened too much, however, the smaller voltage generated across the shorter tether will leave less voltage margin for the operation of the plasma contactors and the battery recharge system. Since the maximum voltage that can be generated is about 200 V/km, and typical plasma contactors and battery, chargers take 25–100 V to operate, a minimum length for a Tether would be roughly 2 km. Host spacecraft operating in polar orbits, where the conditions for voltage generation are not as good, may require a tether length of 5 km or more.

Since many watts of heat power will be dissipated in the control resistor, means must usually be provided to radiate the heat away into space. One low-mass method of accomplishing this is to make the control resistor (or resistors) in the form of a long, electrically insulated, high resistivity wire similar to those used in electric blankets, but designed to operate at a higher temperature, and during the fabrication of the electrodynamic tether, incorporate the high resistivity wire (or wires) into the end of the tether closest to the control circuit by weaving or braiding the insulated high resistivity wire in with the uninsulated aluminum wire of the electrodynamic tether. The surface area of a long wire is very large, so in this extended wire configuration, exposed to the space all around it, the hot control resistor wire can self-radiate its power into cold space without incurring the mass penalty of a separate radiating surface.

Implementation:

The basic optimum structure for a Terminator Tether™ would be one of the many types of Hoytethers. A multiline (6–12 primary line) Hoytape™ will provide the largest contact area with the plasma, since both sides of the tape would be able to pass current to the plasma. If the spacing between the primary lines is chosen to be larger than twice the Debye length of the plasma, then the effective current collection area per unit length of the Hoytape is proportional to the width of the Hoytape mesh, not the diameter of the wires in the mesh. Thus, a Hoytape not only provides an assured longer life for the Terminator Tether™, but very short lengths will also provide a very large current collection areas.

The deployer for the tether can deploy the Terminator Tether™ either down or up or both. The deployer can stay

attached to the spacecraft as was done in the SEDS missions, or perhaps a better alternative would have the deployer ejected from the spacecraft, with one end of the tether still attached to the spacecraft, reeling out tether as it leaves. The empty deployer would then act as a ballast mass at the end of the Terminator Tether™, which would improve the performance.

The "Remora Remover"

In addition to attaching Terminator Tethers to spacecraft before launch, it is possible to consider a missile-like application. This "Remora Remover" missile would use a Terminator Tether™ carried by a seeker missile similar to the small "hit-to-kill" missiles developed by the Space Defense Initiative Office that deployed a net loaded with oriented metal rods. The Remora Remover missile would hunt down a spacecraft that needs to be removed from space, but instead of hitting the spacecraft, the missile would be programmed to rendezvous with the spacecraft and attach itself to the host spacecraft using a hooked net, harpoon, or adhesive "sucker". The Remora Remover missile would then deploy the Terminator Tether™, which would bring down both the spacecraft and the missile.

The inventors have presented two analyses, backed up with data obtained from space flight experiments. One analysis was based on generalized energy conservation laws while the other analysis use force and torque balance arguments. Both analyses show that optimized aluminum wire tethers 2 to 5 km in length and massing just 1% to 5% of the mass of the host spacecraft can deorbit the host spacecraft in the order of a few weeks, thus mitigating the long-lived orbital debris hazard created by a constellation spacecraft after their end-of-life.

Power Augmented Operation of the Tether:

It is well known in the aerospace literature that if a spacecraft has a power supply and a conducting tether hanging from it, and the spacecraft is in an orbit or trajectory that takes it near a body, such as the Earth or Jupiter, which has both a magnetic field and a region of moderate density electron-ion plasma, and electrical current is pumped from the power supply through the tether and back through the plasma, that the current flowing through the tether will interact with the magnetic field of the body, producing forces on the tether and thence on the spacecraft, changing its orbit or trajectory. These forces can be used to increase or decrease the spacecraft altitude and/or inclination. The amount of altitude or inclination change is proportional to the ratio of the power available from the power supply divided by the mass of the spacecraft and varies with altitude. The unpowered Terminator Tether™ is a simple example of such a system, in which only altitude decrease is possible, although small amounts of both inclination increase or decrease are possible at the same time. Some typical references to this prior art are: Les Johnson, "Propulsive Small Expendable Deployer System Mission (ProSEDS)", Proceedings of the OAST 8th Advanced Propulsion Workshop, JPL, Pasadena, Calif., 20–22 May 1997; and Les Johnson, Joe Carroll, Robert D. Estes, Enrico Lorenzini, Brian Gilchrist, Manuel Martinez-Sanchez, Juan Sanmartin, and Irwin Vas, "Electrodynamic Tethers for Reboost of the International Space Station and Spacecraft Propulsion, AIAA Paper 1996.

Since the Terminator Tether™ of the invention is normally associated with a satellite that has a power supply in the form of a solar panel combined with a storage battery, the Terminator Tether™ can be operated in the "powered propulsion" mode if desired. Such a mode would be useful when attempting to avoid a collision between the Terminator Tether™ and another spacecraft. In such cases, the power from the solar panel, augmented by the power stored in the battery, can be used to temporarily operate the Terminator Tether™ in the propulsion mode instead of the normal drag mode. This would enable to Terminator Tether™ to raise its altitude and/or increase or decrease its inclination to avoid a collision.

In addition, the Terminator Tether™ could be operated in the "power-augmented drag" mode. In this mode, there will be a current induced in the tether by the motion of the spacecraft through the magnetic field, which will cause a drag force on the spacecraft. This induced current would then be augmented by additional current in the same direction generated by the solar panel and the storage batteries in the power supply. The increased current will cause an increased drag force. If there is a significant vertical component of the magnetic field there will also be an increased force normal to the orbital plane, which will cause an increased rate of change of inclination.

When the Terminator Tether™ is operated in the "powered propulsion" or "power-augmented drag" mode, the conditions for stable optimum operation will be essentially the same as in the "unpowered drag" mode. The reason the conditions stay the same is that the maximum tether force than can be effectively utilized is limited by the strength of the gradient force, which has not changed, since the length and mass of the tether and the ballast mass has not changed for these different modes of operation. As a result the optimum operational angle for the tether is still 35.26 degrees, and the optimum ratio of ballast mass to tether mass for different tether lengths and tether material is still determined by the analysis of the invention as is set forth above.

In the analysis given above, where the optimum tether angle was found, the tether was assumed to be in the plane of the orbit and lagging behind the spacecraft motion, since in the "unpowered drag" mode, that would be its normal position, although if the component of the magnetic field along the orbit were high, there would be some tilt of the tether out of the plane of the orbit, producing a force tending to change the inclination of the orbit. In either of the "powered" modes of operation of the Terminator Tether™, however, the tilt of the tether could be forward toward the motion of the spacecraft or strongly tilted to one side or the other of the orbital plane. In all these cases, if the electrodynamic force is allowed to become too large, and the tether angle exceeds 45 degrees, the restoring force of the gradient field will drop off and the tether angle will go unstable. As a result, the optimum angle for the tether that will give the maximum stable force, whether it is a maximum drag force, and maximum propulsion force, or a maximum inclination change force, will be 35.26 degrees, and the optimum ratio for the mass of the tether versus the mass of the ballast will be the same as for the unpowered drag case.

The analysis that gave the optimum angle as 35.26 degrees assumed that the tether would be oriented like a rigid rotor. In reality, variations in forces along the tether will probably cause the tether to hang in a slightly curved shape, where the optimum angle may not be exactly 35.26 degrees from the local vertical. The optimum angle of the tether as it leaves the host spacecraft in such a case is where the drag force is largest.

The present invention is discussed in this disclosure in terms of its space applications as a Terminator Tether™ useful for the removal of unwanted satellites. It should be understood, however, that the present invention is useful in any application where a space object can use a conductive tether to produce electrodynamic force through interaction

with a magnetic field. The invention, therefore, should be limited not by this description, but only by the appended claims and their equivalents.

What is claimed is:

1. A method of operating a conductive tether attached to a space object, said conductive tether being oriented at an angle to magnetic field lines of an external magnetic field and said conductive tether moving across the magnetic field lines of said external magnetic field at said angle to producing an electric current in said conducting tether and a resulting electrodynamic force acting on said tether and said attached space object comprising,

Controlling the amount of electric current flowing in said conducting tether to vary the angle between the conductive tether the field lines of the external magnetic field and the electrodynamic force acting on said tether and attached space object.

2. A method as in claim **1** wherein said angle is less than 45 degrees.

3. A method as in claim **1** wherein said angle is 35.26 degrees.

4. A method as in claim **1** wherein said angle is controlled to average 35.26 degrees over time.

5. A method as in claim **1** wherein said angle is controlled to average 35.26 degrees over the length of the tether.

6. A method as in claim **1** wherein the space object and the tether connected to it are rotated about their center of mass while the conductive tether interacts with the external magnetic field.

7. A method as in claim **1** wherein the angle of the conductive tether to the external magnetic field is controlled by sensing a measurable parameter of the space object/conductive tether system.

8. A method as in claim **7** wherein the parameter is current flow in the conductive tether.

9. A method as in claim **7** wherein the parameter is the electrical power dissipated in the conductive tether and the current control system.

10. A method as in claim **7** wherein the parameter is the relative position of the space object and the position of the far end tip of the tether.

11. A method as in claim **7** wherein the parameter is the acceleration of the space object.

12. A method as in claim **6** wherein the parameter is the state vector of the space object as measured by the Global Positioning System.

13. A method as in claim **1** including the step of applying electric power to the conductive tether to change the state vector of the space object.

14. A method of operating a conductive tether attached to a space object, said conductive tether being oriented at an angle to the local vertical between said space object and a celestial body having a magnetic field having magnetic field lines external to said conductive tether; said conductive tether moving across said magnetic field lines of said external magnetic field at an angle to the local vertical to produce an electric current in said conducting tether and a resulting electrodynamic force acting on said tether and said attached space object comprising,

Controlling the amount of electric current flowing in said conducting tether to vary the angle between the conductive tether the local vertical between said space object and said celestial body to vary the electrodynamic force acting on said tether and attached space object.

15. A method as in claim **14** wherein said angle is less than 45 degrees.

16. A method as in claim **14** wherein said angle is controlled to average 35.26 degrees over time.

17. A method as in claim **14** wherein the space object and the tether connected to it are rotated about their center of mass while the conductive tether interacts with the external magnetic field.

18. A method as in claim **14** wherein the angle of the conductive tether to the external magnetic field is controlled by sensing a measurable parameter of the space object/conductive tether system.

19. A method as in claim **18** wherein the parameter is current flow in the conductive tether.

20. A method as in claim **18** wherein the parameter is the acceleration of the space object caused by the electrodynamic force acting on the space object.

21. A method as in claim **18** wherein the parameter is the change in the state vector of the space object as measured by the Global Positioning System.

22. A method as in claim **14** including the step of applying electric power to the conductive tether to change the state vector of the space object.

23. A method as in claim **14** wherein the celestial body is the Earth and the magnetic field is the Earth's magnetic field.

24. A method as in claim **14** wherein the celestial body is the sun and the magnetic field is the Sun's magnetic field.

25. A method as in claim **14** wherein the magnetic field is the vector sum of the magnetic fields from all celestial bodies in the solar system.

26. A method as in claim **14** wherein the conductive tether is a Hoytether.

* * * * *

QRP HomeBuilder - QRPHB -

Component level (mostly analog) electronics from microwave to AF. Jazz guitars and guitar amplifiers. Radio astronomy. I apply science and critical thinking in my daily life.

Showing posts with label **UHF RF Grounding**. Show all posts

Saturday, 29 April 2017

UHF Travels



Many amateur experimenters stay in the familiar comfort zone of HF. A small number venture into VHF, and even fewer devote time designing, building and operating for the UHF & microwave spectrums.

Outside of amateur radio, broadband UHF radio operation dominates the airwaves: data or voice communications on smart phones hum along nonstop on WAN, LAN, cellular, PCS, PSTN and satellite networks. Then too, we've got the ISM bands that backbone industry and commerce @ UHF and higher spectrums for multiple groups, including radio astronomers.

Also digital television broadcasting standards may involve the UHF spectrum, and so, a pattern emerges: UHF circuitry sending data that's controlled by CPUs.

This UHF proliferation benefits us experimenters by providing an excellent bevy of fast parts such as 25+ GHz transistors, cheaper, more abundant transmission line + connector choices, numerous scientific articles, faster + cheaper test equipment --- and loads of inspiration. To boot, many transmitting circuits are low voltage and/or low power – aka "QRP". This is the new QRP ! Fresh, relevant, science-driven -- and supporting the marriage of code plus RF design in the new age via the latest tools, techniques and hardware.

The physics and challenges of RF design haven't changed however. For example, the Smith Chart still works perfectly, and measurement techniques remain the same. However, some differences become quickly obvious as you plow in: 1 stark example == resonator Q. Vitamin Q gets hard to come by as we move up in frequency. Further, the ease + slack and forgiveness of HF quietly disappears and this proves both vexing and challenging to us builders.

Casual construction techniques work poorly at UHF. Consider a Class A common emitter BJT amplifier: A poorly RF grounded emitter lead may add parasitic inductance that results in series feedback which degenerates the signal and reduces amplifier gain.

Further, I've learned that a high bandwidth transistor amp designed and/or built poorly make frustrating oscillators, or, just offers low gain due to mismatch or

Translate

Select Language ▼

My Blog List

Jay's Astronomical Observing Blog

Observing and Sketches from December 19th through December 21st, 2017. - I got some observing in on December 18th and 19th, 2017 out at my dark site off of Forest Road 006 at Juniper Grove. A couple of images. A little snow...

2 hours ago

Ripples in the Ether

Arduino – Si5351 Powered Signal Generator - Arduino – Si5351 Powered Signal Generator Please enjoy this write-up of a nifty, compact signal generator project using the Etherkit Si5351A Breakout Board...

23 hours ago

VE7SL - Steve - Amateur Radio Blog



CLE 226 / CLE 227 NDB Listening Event Results - *CLE 226 and CLE 227*, both running during the Christmas to New Year period, produced some excellent propagation on the MF NDB band in most parts of the...

1 day ago

Victor Herrero Radio Astronomy Blog



Sun Earth Jupiter 20171223 - ... *Many thanks to: Taxpayers of the United States of America, the Juno, STEREO, WIND Spacecraft Teams, the Panetary Data System Team, Prof. Dr. Kazumas...

2 weeks ago

The Signal Path

Rohde & Schwarz RTB2004 10-Bit, 2.5GS/s MSO Oscilloscope Review, Teardown & Experiments - In this episode Shahriar reviews the Rohde & Shwarz RTB2004 10-Bit oscilloscope. With its high-resolution touch-screen, intuitive and capable GUI as well a...

3 weeks ago

EA4EOZ, an amateur radio electronic enthusiast

Icom IC-R7100 and its clicking noise - Some time ago an Icom IC-R7100 instability. Unsurprisingly RF filters with poor RF grounding @ UHF poorly attenuate UHF. I'll show this graphically in the next section.

UHF design looks scary to some: you have to master the Smith Chart, obtain some fast transistors, and learn about microstrip techniques and so on.

Then comes the task of making your test bench. Yikes!

High bandwidth gear may equal high cost depending on what you build or purchase. For sure, you'll need some form of a 50 Ω detector. My main UHF detector = a 3 GHz spectrum analyzer with a tracking generator. This allows me to measure with or without sweeping 1 or 2 port circuits. You also get a frequency counter in the RG + SA package -- so it seems like a good choice; at least for now.

I also designed and built a wide band return-loss bridge and plan to improve this design over time. I would love to own a network analyzer, but will hold off until I find an affordable unit with a bandwidth >= 10 GHz. 10 GHz? Yes, I hope to work 10 GHz EME using JTF4 mode with Doppler correction on homebrew gear 1 day.

My eventual goal @ UHF -- to design and build a UHF radio astronomy system looms in the background, however, first, I must learn to design and match amplifiers, tackle low phase noise, temperature-stable oscillators and learn how to make filters that work well into microwave.

I'll blog some of my experiments starting today.

[1] Ugly Construction

RF signals follow the path of least impedance. This means plying double-sided copper clad board with the lower half serving as the microstrip ground plane. Currently, I use glass-fiber epoxy laminate FR-4, 1 ounce copper boards with 1.37 mil trace thickness and a substrate height of 1.6mm (1/16 inch).


MG Chemicals
COPPER CLAD BOARD
Complies with IPC-4101C/21 Stress Relieved UV Blocked
Flame Retardant - UL Rated 94-V0. UL-FR-4, 1 oz Copper

Above — I got a deal on some MG-Chemicals FR-4 and will use it for all of my 2017 experiments. FR-4 is common, easily available and cost effective. Permittivity, or the dielectric constant Er = ranges between batches and manufacturers of FR-4. I've read Er values from 3.9 to 4.8 and tend to use the standard 4.7. This means a 50 Ω stripline gets cut to a 2.9mm width.

Although, substrate thickness varies and insertion loss increase with frequency, I think we can manage OK with FR-4 copper clad laminate board at UHF. PTFE-based boards pose an option if we require critical impedances , λ fractions, or lower insertion loss as you move up in frequency.

arrived to my shack. It's a nice receiver and works surprisingly well but almost the very first time I powered it up an anno...

1 month ago

Circuit Salad

PWM Vibrato that sound Awesome! - Vibrato is the slight changing of frequency of a musical note. This can be accomplished by means of a varying time delay in a delay line or by phase shifti...

2 months ago

Amateur Radio Astronomy

Radio-Sky Spectrograph works with Radio-Jupiter Pro, - There are a number of ways that Radio-Sky programs can interact with one another. For example, RTL Bridge can send signal strength from a RTL dongle recei...

4 months ago

Davide Bucci's Blog

-

Pages

- Home
- Guitar Related Index

My Micro Updates

Working on guitar amp circuitry Dec 2017

My Support Pages

- My Email
- My Articles
- Old pops.net site downloads & info
- Javascript Tools
- My RF Resources
- Jupiter Modular Receiver Main Index
- Radio Astronomy Links
- Solar Ham Data and Graphs

My Links

- Ed Ting: Telescope Review site
- Etherkit
- Kuhne Microwave Components
- Luis Cupido: Deep Space Radio

Simple Post Index

- 7 MHz scratch synthesizer
- 90 Degree Phase Shift: AF - UHF
- AF power amp design
- Anton Chekhov
- Funster receiver Part 1
- Funster Receiver Part 2
- Funster receiver part 3
- Harmonic VXO
- High IIP3 mixers
- hybrid-cascode regen detector
- Inverter crystal oscillator tips
- Jupiter receiver notes. KISS mixer
- Line - in audio amplifier Part 1
- Line - in audio amplifier Part 2
- LM386 notes
- Measure Crystal Q
- Measure resonator Q at VHF
- Oscillator phase noise
- Rail to rail audio power amp

DOUBLE SIDED
DOUBLE FACE
DOBLE CARA
DOPPIA FACCIA
DOPPELSEITIGES
1/16", 1.6 mm
#555
304 mm x 304 mm
(approx. 12" x 12")
Batch No. 16291

MG Chemicals
COPPER CLAD BOARD

Above — 4 square feet of FR-4 laid out on the lawn. These boards will hopefully bear some good experiments ahead.

RF Grounding

- Matjaž, S53MV
- MIT Haystack
- Moonbouncers org
- My Twitter Page
- Paul, W1GHZ
- Radio Astronomy supplies
- Radio-Sky Publishing
- Reeves Radio Science
- Rigol Canada - Electro-Meters
- Society of Amateur Radio Astronomers
- Solid State Regenerative Receivers
- Test Equipment
- UK Radio Astronomy Association
- W7ZOI -- EMRFD
- YOUDAC-VA3IU

- Regen receiver #4
- Regenerative receiver #5
- SAW Resonator
- Simpler Single-Signal Direct Conversion Receivers
- Sine wave side tone
- Tone balance control
- Trixie 2 -- simple low current DC receiver
- Two tone mixer IIP3 Notes
- UHF Bypass and decoupling
- UHF RF Grounding
- VXO- based freq synthesizer
- Xtal parameters with spectrum analyzer and tracking generator

Blog Archive

- ► 2014 (13)
- ► 2015 (19)
- ► 2016 (13)
- ▼ 2017 (8)
  - ► January (3)
  - ► April (1)
  - ► November (1)
  - ▼ December (3)
    - Op-amps Make Life Better
    - Peerless Martin Taylor Maestro - a brief review
    - 1969 Fender Deluxe Reverb Restoration

The Professors

Above — A portion of an older, beat-up 12 inch by 12 inch 40 gauge copper sheet I use to connect the copper surfaces at all board edges. I just cut it with scissors. You can also smooth out the pieces before, or after cutting them.

I get this sheet copper from Monte Allums in the USA. Click for his link. I've also built tops for shielded RF boxes and resonator dividers with this stuff. Oh, and I shielded an electric guitar control cavity for someone using this Cu as well.



Above — An example edge dressing. We start with a small 2-sided piece of FR-4 and a cutting of Montee Allums 40 gauge copper sheet.



Above — I' ve folded the copper sheet over 1 edge. Looking a little uneven, it's clearly not my best effort, but on the other hand -- it will work fine. I scraped the copper sheet with the edge of the scissors so it lies flush against the FR-4 with no air gaps. Time to solder.



Above — The copper sheet gets wrapped around soldered on both sides. Then repeat for the other 3 FR-4 sides. When completed, you'll have a board ready for carving out strip lines or applying classic ugly construction when using B+ posts, connectors and capacitors as stand-offs.

A 2-sided FR-4 board with copper strips joining all edges will provide stalwart RF grounding from DC to VHF. For UHF we need to drill via holes and connect the 2 surfaces with copper wires strategically located wherever UHF ground is needed.

I'll demonstrate why with an actual experiment based on a 7- element low-pass filter that I designed to use the lumped-element inductors and capacitors I had on hand.

The inductors = Coilcraft 1008CS series wire wound on ceramic chips. These are in size 0805. Click for a datasheet. I've since stocked many values of these amazing parts in both size 0805 and 0603.



Total Freq. Span = 1337.550

#, part, connection, value:

```
0 Load R = 50.0
1 cap par 9.0033
2 ind ser 27.1127
3 cap par 15.9815
4 ind ser 29.9824
5 cap par 15.9815
6 ind ser 27.1127
7 cap par 9.0033
8 rlb ser 0.0000
98 Source R = 50.0
99 Inductor Q = 60.0
```

top 0.0 dB

10.000 dB/div.

bottom -80.000 dB

Start Freq. 0.450 Frequency Units MHz 446.000 Freq./div stop Freq 1338.000

Part # 1 New Value 0

☐ Plot Reference

☑ Plot S11

Frequency 439.265 MHz S21= -2.99 dB S11= -5.66 dB

S21 -
S11 -
S21 Ref.-
878.5 MHz
Attenuation
= 61 dB
OK Match
5 - 415 MHz
2nd harmonic
of 3 dB frequency
Click to load new value
Drag Box on Plot to Zoom In
Click here to Zoom Out
Click here to Save S21 as Ref.
Place Cursor
Reset Cursor
Save as Default, Exit.
50 Ω
27n
33n
27n
50 Ω
9.1p
15p
15p
9.1p
Actual filter built from simulation

Above — Simulation of my filter in GPLA, a program that ships with EMRFD.

I then built a filter, but did not solder the copper edges together with Cu sheet metal and just use 1 via wire for the RF ground on each of the 4 caps.



13:10:04 2017-03-08

Ref 0.00 dBm Att 10 dB Marker4 3.0000 GHz -22.96 dB

Marker
3.000000000 GHz
-22.96 dB

Center Freq 1.5000 GHz Span 3.0000 GHz

RBW 30.000 kHz VBW 30.000 kHz SWT 3.3333 s

Marker Table

Marker	Trace	Type	X Axis	Amp
1D	1	Frequency	375.000000 MHz	-2.87 dB
2D	1	Frequency	750.000000 MHz	-54.86 dB
3D	1	Frequency	1.500000000 GHz	-42.19 dB
4D	1	Frequency	3.000000000 GHz	-22.96 dB

RIGOL
Local
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
(dB)
1
2
3
4

Above — A sweep out to 3 GHz shows sub-optimal RF grounding leads to poor attenuation above ~1.5 GHz. This = a terrible filter.


RIGOL
12:44:22 2017-03-11
Local
Status
Peak
TRIG Free
SWP Cont
Corr
S.T.
PA
C.W.
Blank
Blank
Math
Marker
Readout
Frequency
Mkr Table
On
Off
All Off
2/2
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
(dB)
1
2
3
4
Marker
3.000000000 GHz
-25.31 dB

Ref 0.00 dBm Att 10 dB Marker4 3.0000 GHz -25.31 dB

Center Freq 1.5000 GHz Span 3.0000 GHz

RBW 100.00 kHz VBW 100.00 kHz SWT 300.00 ms

Marker Table

Marker	Trace	Type	X Axis	Amp
1D	1	Frequency	655.000000 MHz	-57.32 dB
2D	1	Frequency	1.665000000 GHz	-46.57 dB
3D	1	Frequency	2.475000000 GHz	-57.53 dB
4D	1	Frequency	3.000000000 GHz	-25.31 dB

Above — A sweep made after adding the copper edges and 1 more via wire to each of the 4 capacitors. While better than previous, attenuation poops out at 2.475 GHz.


RIGOL
12:58:17 2017-03-11
Local
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
(dB)
1
2
3
4
Marker
2.000000000 GHz
-46.54 dB

Ref 0.00 dBm Att 10 dB Marker3 2.0000 GHz -46.54 dB

Center Freq 1.5000 GHz Span 3.0000 GHz

RBW 30.000 kHz VBW 30.000 kHz SWT 3.3333 s

Marker Table

Marker	Trace	Type	X Axis	Amp	
1D	1	Frequency	370.000000 MHz	-2.99 dB	3 dB cut-off frequency
2D	1	Frequency	740.000000 MHz	-59.29 dB	
3D	1	Frequency	2.000000000 GHz	-46.54 dB	
4D	1	Frequency	3.000000000 GHz	-40.70 dB	

Above — Final version swept after adding 2 more via wires to each of the 4 capacitors. Clearly soldering 4 copper via wires per ground node boosted the filter's attenuation at 3 GHz.



Popular 400-470 MHz elliptical low-pass filter sold on eBay

Above — I purchased a popular 400-470 MHz low-pass filter sold on eBay that sells for ~ $10.00. At 2.81 GHz, the filter's stop band just falls apart. Further, the 3 dB cut-off of my particular filter = 580 MHz; much higher than advertised.



Above — The low-pass filter swept above.

Above — A MCL PLP-550 low-pass filter. This older filter suffered bent pins and I failed to get a short path for the 4 ground pins to the ground plane on the lower half of the board. 1 mm of wire length potentially could = 1 nH of stray L.


MCL + A 1635
PLP−550


RIGOL
Local
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
(dB)
1
2
3
4
Marker
1.145000000 GHz
-60.57 dB

10:40:40 2017-04-30

Ref 0.00 dBm
Att 10 dB
Marker2 1.1450 GHz -60.57 dB

Center Freq 1.5000 GHz
RBW 100.00 kHz
VBW 100.00 kHz
Span 3.0000 GHz
SWT 300.00 ms

Marker Table

Marker	Trace	Type	X Axis	Amp
1D	1	Frequency	575.000000 MHz	-2.59 dB
2D	1	Frequency	1.145000000 GHz	-60.57 dB
3D	1	Frequency	2.000000000 GHz	-20.87 dB
4D	1	Frequency	3.000000000 GHz	-22.75 dB

Above — Poor RF ground at UHF trashed the upper stop band of my poorly mounted MCL PLP-550 low-pass filter.


RIGOL
11:19:36 2017-04-30
Local
Ref 0.00 dBm
Att 10 dB
Marker4 3.0000 GHz -21.51 dB
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
(dB)
Marker
3.000000000 GHz
-21.51 dB
1
2
3
4
Center Freq 1.5000 GHz
RBW 100.00 kHz
VBW 100.00 kHz
Span 3.0000 GHz
SWT 300.00 ms
Marker Table

Marker	Trace	Type	X Axis	Amp
1D	1	Frequency	580.000000 MHz	-3.16 dB
2D	1	Frequency	1.185000000 GHz	-62.88 dB
3D	1	Frequency	2.000000000 GHz	-35.33 dB
4D	1	Frequency	3.000000000 GHz	-21.51 dB

Above — I attempted to reduce the ground path lengths and also placed 2 via wires by each SMA connector. This boosted the UHF stop band somewhat. I'll take an entirely different approach when I redo this filter's breadboard 1 day.

I've learned the bitter truth about RF grounding @UHF -- and now RF ground lies foremost in my mind when I breadboard a circuit.

Multiple, short, low inductance via wires provide a low-impedance connection to the ground plane below and in addition to improving RF bypass may reduce noise + interference.

[2] SAW based Oscillators

SAW resonators offer an easy way to generate a single frequency with a decent loaded Q to reduce oscillator single sideband phase noise when compared to LC, or varactor-tuned circuits @ UHF.

It's also possible to tune them as a VCSO (voltage controlled SAW oscillator). They see use in many commercial items such as garage door openers, chemical sensors and even wearable medical devices. You'll often view them in datasheets covering the range of 200 - 1200 MHz, although other frequencies are also available. The unloaded Q of a typical SAW device lies between 6 - 12K. That's much better than that of a VCO with the inductor cut out in the copper board (Q = 50 - 100) and tuned with varactor(s).

Of course, the variable SAW resonator lacks the wide tuning bandwidth needed for many projects -- UHF work proves all about compromise.

So far, I've built 7 or 8 SAW oscillators and many were crappy. Some of the problems included oscillation at an overtone, low output, parasitic oscillation, and not running at the correct SAW frequency.

I'll show an oscillator I built to use for OIP3 measurements of BJT amplifiers using my lab-grade HP signal source as the other tone for these 2 tone measures.


Feedback Loop Oscillator with SAW resonator
12.3v
330n
100n
100p
560
470 µF
1K
10
100n
270
6.8 µF
150p
680
470p
22 µF
33
100p
82n
22n
315 MHz
SAW resonator
33K
2SC3583
68K
220p
MMIC
220p
27n
33n
27n
50 Ω
10p
8.2p
0.5p
12mm 50 Ω
microstrip
0.5p
33 mA
9.1p
15p
15p
9.1
2SC3583
SGA-3486
22n
13 mA
-17.7 dBm
7.5 mA
12.8 dB gain
Notes:
* High C to L ratio to boost loaded Q
* SAW QUL = 8400
* Excellent temperature stability
* COG tempco capacitors with
ultra-high Q from Vishay

Above — My first attempt at a feedback loop oscillator. Normally, we build negative resistance type oscillators.


Layout Template for Project
100n
10p
220n
22n
560
SAW
100p
1K
220µF
680
560p
33K
100p
c
33
22n
b
e
vias
vias
8.2p
0.5p
c
68K
10
b
e
vias

Above — Here's my bread board layout diagram for the first and second stages. I carved these signal paths into the topmost board with a motorized cutting tool. Some part values were changed during bench tests.


TD
H 500.0ps
5.000GSa/s 700 pts
D 0.00000000ps
T 2 4.37mV
HORIZONTAL
315.057MHz
STORAGE
DISK MANA.
NEW FILE
saw
Oscillator output
after 0.5 pF cap
Vpp = ****
Vpp = 82.4mV
1 200mU
2 Ω 20.0mV
22:49

Above —The output of the feedback loop oscillator. If you take the signal from the collector, the AC voltage may run as high as 1.5 Vpp, but it's rich with harmonic energy. I sampled some output from the transistor base via a 0.5 pF capacitor. All caps < 100n were C0G temperature coefficient. Transistors such as the 2SC3583 offer tremendous gain at HF, so HF and even AF bypass is needed to keep circuitry stable.


TD
H 500.0ps
5.000GSa/s 700 pts
D 0.00000000ps
T 2 4.37mV
HORIZONTAL
315.058MHz
STORAGE
DISK MANA.
NEW FILE
saw
Output of
Q2 matching
network
Vpp = ****
Vpp = 358mV
1 200mU
2 Ω 60.0mV
12:32

Above — Output of the second transistor stage. I'll comment about the collector feedback bias in a later blog post. I attempted to match the output impedance to the 50 ohm input impedance of the MMIC, I did OK, but failed to account for stray reactances and also I didn't have caps less than 0.5 pF at the time. The 33 Ω resistor in series with the 22n lower its Q to stabilize the amplifier.


TD
H 500.0ps
5.000GSa/s
700 pts
D 0.00000000ps
T
-3.12mV
HORIZONTAL
315.057MHz
STORAGE
DISK MANA.
NEW FILE
saw
50 Ω output
after LP Filter
Vpp = ****
Vpp = 1.00 V
1
200mV
2
Ω 200mV
15:40

Above — Output of the final stage, a MMIC. I lost significant signal amplitude because my poor filter layout. My carved microstrip paths were too long and so, acted like inductors that detuned the filter and created some reflections. Of course, you never know this until after you've carved your breadboard. Still, this circuit works OK for amplifier, or mixer 2-tone measures and I learned a lot by designing and making it.

This was by far the most temperature stable SAW oscillator I've built.


3 SAW oscillator with PIN diode switching
12.3v
47
100 pF
4K7
2N4401
220 µF
.1
47
.001
47
100 pF
68 nH
15K
100 pF
10K
82
100 pF
3.3 pF
10K
1K
39
50 Ω
100 pF
10K
1K8
5 pF
PIN
2SC2026
2SC2026
B
E
C
12 VDC

Problems encountered:

(I tried a number of SAW resonator combinations from 280- 416 MHz)

* Output amplitude varation for each SAW resonator
* Noise from resistance of PIN diode
* Some SAW resonators would not start where others were overdriven

Above — An experimental negative resistance oscillator that allowed the selection of 1 of 3 SAW resonators. It worked to a point. The problems encountered are shown in the inlay.



Butler Common Base SAW Oscillator

10.5v
100
12.30v
100p
47n
ceramic chip
Q = 60
100p
3K3
0.5p
- 5 dB
50 Ω
15
15
82
2.33v
0.5p
100p
1K
100
1.58v
47p
C2
SAW
288
MHz
14.2 mA
D1
100
1M
100K
270
100p
470p
VTune
VCSO

Increasing C2 boosts loaded Q of resonator to decrease oscillator phase noise

All caps C0G temp co.

add voltage control

Above — An experimental Butler SAW oscillator. When you remove the SAW resonator, the circuit still oscillated and needs to be within 5% of the SAW value or the frequency stability suffers. Further, the oscillator worked best with a tuned collector. I need to work on this some more. It doesn't take much to push this circuit into an overtone oscillator; intentional or not.

I'm always trying to boost the QL since SSB phase noise lies inversely proportional to the square of the loaded Q.



RIGOL
TD
H 500.0ps
5.000GSa/s
700 pts
D 0.00000000ps
T
2 3.12mV
315.041MHz
HORIZONTAL
STORAGE
DISK MANA.
NEW FILE
saw
Vpp = ****
Vpp = 337mV
Phs1→2 = *****
Freq = 316.4MHz
1
100mU
2
50.0mV
13:34

Above — The output signal with a tuned collector. Oscillators combine art, science and to some extent, a little luck.

[3] RF Amplifier

I'll show 1 experimental amp, since I'm still learning through experiments and this blog post is running long in the tooth.



Design and build a stable 1 GHz amp with no network analyzer and 50 Ω microstrip for L matches

Bench problems

Only had a 47n L for bias RFC, so lost a little gain.

VCE = 7.28 and not 8 volts

Hand carved strips into 16 ounce 1/16 inch, double side Cu board.

Limited ability to match ports

Microstrips a little long @ 1 GHz but OK for >= 2 GHz

2SC3583 S-parameters
VCE 8v IC = 5 mA @ 1 GHz
|S11| 0.202 , -131°
|S21| 4.004 , 83.6°
|S12| 0.101 , 61.3°
|S22| 0.50 , -30.1°

Rollet K = 1.03
MAG = 15.98 dB
MSG = 13.4 dB

Er = 4.5
λ /2 = 7.06 cm

Measures
S21 = 11.2 dB @ 1GHz
IC = 5.2 mA
Stable down to HF

Voltage regulator
12.3VDC
2N4401
7.5
100n
510
510
100 µF
10n
82p
8.2v
470 µF
7.40v
22K
470p
4.7
47p
3K3
22 µF
Bias
20
0.77v
100p
10n
3K3
7.28v
~ λ /2
50 Ω
100n
slide (1 pF) cap to match
50 Ω microstrip
47p
50 Ω
slide (1 pF) cap to match
2SC3583
47p
50 Ω microstrip
1p
1p
5.2 mA
~ λ /2

Above — A 1 GHz amp matched by the the brute-force method: The input and output are 50 Ω microstrip line slightly greater than λ /2 long (accounting for the FR-4 velocity factor). To tune the input and output, you slide a size 0805 capacitor along that's attached to a thick toothpick, find the sweet spot and then tune a variable cap right at the sweet spot. The variable cap then gets removed, measured, and a nearest standard value cap goes in place.

I chose a 2SC3583 BJT with a VCE of 8 volts and 5 mA collector current. Using datasheet S parameters I calculated the maximal available gain at 15.98 dB -- and also the maximum stable gain at 13.4 dB. In the breadboard, I got 11.2 dB gain, which seemed reasonable for my first, crude 1 GHz RF amp.



Above — The 1 GHz breadboard. It's too long for practical purposes, but not for learning.


RIGOL 04:55:38 2017-04-09

Ref 0.00 dBm Att 10 dB Marker1 1.0000 GHz -21.50 dBm

Marker
1.000000000 GHz
-21.50 dBm

Center Freq 1.0000 GHz Span 31.250 MHz
RBW 3.000 kHz VBW 3.000 kHz SWT 3.4722 s

Status
Peak
TRIG Free
SWP Cont
Corr
S.T.
PA
C.W.
Blank
Blank
Math
Local
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
1
Marker
Select Mkr
1 2 3 4
Normal
Delta
Delta Pair
Ref Delta
Span Pair
Span Center
Off
Mkr Trace
Auto
1/2

Available power with amp removed and replaced with a barrel connector (SMA)


RIGOL 05:19:16 2017-04-09

Ref 0.00 dBm Att 10 dB Marker1 1.0000 GHz -10.32 dBm

Marker
1.000000000 GHz
-10.32 dBm

Center Freq 1.0000 GHz Span 31.250 MHz
RBW 1.000 kHz VBW 1.000 kHz SWT 31.250 s

Status
Peak
TRIG Free
SWP Cont
Corr
S.T.
PA
C.W.
Blank
Blank
Math
Local
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
1
Peak
Next Peak
Peak Right
Peak Left
Min Search
Peak Peak
Cont Peak
On Off
Search Para
1/2

Gain S21 = 11.18 dB


25.00
THE ARRL
UHF/MICROWAVE
EXPERIMENTER'S MANUAL
ANTENNAS, COMPONENTS AND DESIGN
DB [S21] AMP
DB [S11] AMP
DB [S22] AMP
20.00
0.000
−20.00
0.420
0.440
FREQ−GHz
0.460

Above — My single best UHF reference book. Out of print.

Cheers!

Posted by Vasily Ivanenko at 22:11 4 comments:
Labels: UHF RF Grounding

Home Older Posts

Subscribe to: Posts (Atom)

Simple theme. Powered by Blogger.

DIRECT ELECTRICAL POWER

From the utilization of renewable ions

Full Disclosure 7th Edition



DIRECT ELECTRICAL POWER

From the utilization of renewable ions
Full Disclosure 7th Edition

The information disclosed in this document is released for educational purposes only. No power claims are being made. This is a limited release and is published to encourage scientific growth and development in the area of alternative energy research. This document is subject to change without notice and does not represent a commitment on the part of the author. In no event shall the author, his estate or, Radioionics Research be held liable for any consequential, incidental, direct, indirect, special, punitive, or other damages whatsoever arising out of the information that is provided, or the use of, or the inability to use the contained information, except to the extent that this limitation is prohibited by law.

Copyright Information

It is against copyright law to duplicate this information on magnetic tape, disk, or any other medium for any purpose other than for the purchaser's sole personal use. Unless otherwise noted, all materials (including without limitation all text, graphics, instructions, and demonstrations) are copyrighted.

Written & Disclosed by Bruce A. Perreault
© Copyright September 2016 - All Rights Reserved
ISBN 978-1-930216-13-0

Table of Contents

DIRECT ELECTRICAL POWER 1

Copyright Information 2

Table of Contents 3

Radioionics™ Research 5

Historical Background 6

Copy of Hand Written Article Signed by Dr. Mahlon Loomis, January 7, 1872 6

Radio News November, 1922, pages 974-978 Loomis lecture extract: 6

Brooklyn Eagle July 10, 1932 Nikola Tesla States: 13

Philadelphia Public Ledger November 2, 1933 Tesla 'Harnesses' Cosmic Energy 13

Atmospheric Electricity and Terrestrial Magnetism 15

The Study of Meteorology 17

The Origin of Lightning 18

RADIOIONIC ENERGY RECEIVER v5.4.7 21

Fundamental Description 21

Circuit Key 22

Circuit Theory 25

Operating Instructions 26

Summary 28

PATENTS 29

US Patent 7,800,286, Alpha Fusion Electrical Energy Valve, Bruce A. Perreault, Sept. 21, 2010 29

US Patent 2,813,242, Powering Electrical Devices with Energy Abstracted from the Atmosphere, Lloyd R. Crump, November 12, 1957 35

GB Patent 231,427, Improvements in and relating to Improved Means for Utilizing Electromagnetic Electricity for Transmitting and Generating Power, Serafino Orlando, April 2, 1925 38

US Patent 1,540,998, Conversion of Atmospheric Electric Energy, Hermann Plauson, June 9, 1925 45

US Patent 685,958 Method of Utilizing Radiant Energy, Nikola Tesla, Nov. 5, 1901 73

US Patent 129,971. Improvement in Telegraphing, Mahlon Loomis, July 30, 1872 77

UNCOMMON PARTS LIST 79

Author Biography

Bruce A. Perreault, of Dorchester, New Hampshire, expands on his radioionic valve discovery to harness the ions which surround our planet Earth to generate useful electrical power for our appliances and machinery. His dedicated efforts have rewarded him with this very plentiful source of energy which is available all year, even without wind or sun light.

Bruce has an extensive background in electronic equipment troubleshooting and repair. He creates innovative electronic schematics for prototypes for a science that does not yet exist in our present time frame. He has fine tuned his skills as an active researcher and designer for futuristic self-sustaining communities. He is internationally known for his scientific essays, articles, research reports, patent papers and idealistic community living based upon high moral standards.

His informal education comes from observing nature and her processes. This has given him a strong foundation in the fields of science and alternative energy technologies. His skills are diversified in electronics, mechanics, molecular & nuclear chemistry, metallurgy, machine tool operation and scientific glass work that provides him with a well-balanced knowledge base. He enjoys his life as a free spirited natural scientist and attributes his successes to living his life with a high degree of ethical standards, treating people the way he would like to be treated. Bruce is an individual who marches to a different drummer. His ideas, though unconventional, are not out of touch with reality. Bruce’s strong individuality enables him to stick to his ideas in spite of what some people feel are too unconventional.

His unique way of looking at problems stems from the fact that he doesn’t just accept as a given what the textbooks say; he goes beyond current thinking to bring about truly creative technical and philosophical innovations. Even though his lab is small, his ideas are expansive. The concepts that he strives to develop on a daily basis are designed to improve on the human condition. Bruce is capable of viewing the present as but a meager step toward the future of a better life for all worthy people around the globe. He is recognized today as being the principal leading investigator into harnessing the almost limitless supply of energy that surrounds our planet, making the key discovery how it can be efficiently converted from its useless ionic state into electromagnetic currents which is commonly called “electricity.” The future survival of life on this planet may depend on this unique natural resource.

Load
Max Loading
Antenna Tuning
Valve Tuning
RADIOIONIC RECEIVER

Radioionics™ Research is the gateway to generating safe, clean, and reliable energy. Based on the discoveries of Bruce A. Perreault, it is now possible to harvest the ambient energy that bathes our planet and transform it into useful electrical power. This energy appears to be an inexhaustible supply of energy. Our planet literally floats in this sea of energy that is abundant day or night. Bruce has devoted most of his adult life to perfecting the technology that is used to harness this ambient energy. When it is perfected he will offer it for a moderate price to anyone who will use it to better our human condition. He expects that a fully developed product will cost little to maintain.

We build and test high wattage radioionic energy receivers which harvest the abundant sea of radiant energy that continually bathes our planet. An insulated from the ground antenna wire and earth ground is electrically connected to this receiver which draws ambient radiant energy from our planet. Alternatively, a loop antenna and a bare antenna wire that is stretched between two electrically non-conductive poles can be electrically connected to a radiant energy receiver. With the use of a properly crafted ion valve corona discharger, plentiful ambient ions can instantly be converted into high frequency electromagnetic energy. When it is converted into a pulsating unidirectional flow of electrical current its high voltage can then be transformed into a lower voltage, to be stored in a bank of capacitors or other direct current storage components. The method to accomplish this will be revealed in this full disclosure book in easy to comprehend language. No new exotic physics theories are necessary to understand the science involved.

A new science is presented to extract useful naturally occurring electrical power from the sea of ambient energy from the planet which appears to be limitless. This energy source is available during the day or night, all year round, for no more maintenance than from a radio receiver, you cannot ask for a better energy source.

Historical Background



Copy of Hand Written Article
Signed by Dr. Mahlon Loomis, January 7, 1872

Thomas Appleby, in his 1967 biography "Mahlon Loomis", includes an 1868 letter Loomis sent to his brother, in which he declared -- "Telegraph! That's the least important result I expect to attain..." International wireless communication was merely the first of many spectacular advances Loomis thought could be accomplished by harnessing atmospheric electricity. The text of this 1872 lecture by Mahlon Loomis, reviewing his predictions of an amazing future including, among other things, an inexhaustible source of free electricity and the eventual ability to modify the Earth's climate, comes from S. R. Winters' article, "The Story of Mahlon Loomis."

Radio News
November, 1922, pages 974-978 Loomis lecture extract:

What I contemplate in this undertaking, which is based upon acknowledged scientific facts and mathematical truth, is to send messages from Continent to Continent across the oceans without the use of a cable or artificial battery; or between two stations on the earth, however distant from each other, without intervening wires.



Methods Suggested by Loomis for the Harnessing of Electricity from the Atmosphere

This is the primary undertaking, but with it comes also the ability to draw light, heat and motive power for all purposes, and that without expense beyond the original outlay for cost of apparatus. This is to be accomplished by using the Electrical Element from the inexhaustible supply of nature; not by using artificial batteries and chemical compounds which are but an imitation of nature, as I shall presently attend to, but by drawing from the great aerial reservoir ready-made and never-failing. Where do we look for the greatest display of might and power but to the atmosphere with its restless and appalling thunderbolt, coming unforeseen and shooting at random? In all nature nothing is so powerful, nor so terrible because powerful. And yet this great element goes to utterly idle waste, often causing death and devastation; strange to say, no attempt is ever made to utilize this immense wealth to the purposes of man. But when we consider the expense and imperfection of oceanic telegraphy in its present condition; when we consider the expense of fuel, and heat, of motive power, whether from animals, the waterfall or steam, when we consider these things, I say, and contrast them with the proposition to furnish for all of these, *one subtle Element*, tractable and obedient, inexhaustible and utterly without cost, or tax or tariff, then that proposition becomes fraught with an importance of the greatest magnitude.

In the first place, *is* there such an element? It is a well established fact of science that free electricity abounds in our atmosphere; that scarcely any traces of it are found less than four feet from the ground or surface of the earth; but on attaining greater height, it becomes more apparent, and the greater the altitude the more this element abounds; so that in reaching an elevation above the clouds it becomes so prevalent as to form a continuous and distinct element, in which our globe with its surrounding atmosphere lies and floats. That is a demonstrated scientific fact.

It is a well established fact in all electrical phenomena that certain *electrical conditions*, called "positive" and "negative," must exist in order to form a "circuit" or current with the electrical fluid. And these conditions we find most admirably arranged in the great electrical battery of nature. The earth, like the outside of a Leyden jar, or the copper plate of a galvanic battery, is always highly charged with negative electricity. The atmosphere, like the inside of a Leyden jar, or the zinc plate of a galvanic battery, is always highly charged with positive electricity, and the intervening air, like the glass of the Leyden jar, in the separated poles of the galvanic battery, is a perfect non-conductor, thus forming and constituting the most complete and colossal electric battery that ever gave an electric spark, but standing all unused. It is *just as much* superior to all artificial batteries combined as the sun is superior to our tallow candles.

It is, indeed, a mooted question with philosophers ho*w* this electricity comes there--whether the earth was primarily formed magnetic, and this atmospheric electricity is an "inductive" element, or whether it is eliminated from space and source unknown; but whether it is the one, or the other, the *great fact of its existence* remains, and pending the disagreement of the doctors as to its origin I simply make use of the elements as I find them.

Although it be a well-established fact that this element pervades space around our planet as abundantly and in the same manner as our atmosphere does, still can we reach and control it, and will it answer our purposes if we can do so?

Whatever methods may be devised in the future I am not competent to say, but there is *one way already demonstrated by experiments* by which we can reach, and avail sources of its benefit and value, and that is to *seek the highest mountain tops*, and thus penetrate this immense and unexplored field, whose virgin soil awaits the plowshare for a fruitful seedtime and harvest. Common hilltops, or inconsiderable mountain ranges, are inadequate to a successful demonstration, as ascending currents of heated air, or dampness and mists particularly peculiar to the elevation of the generality of clouds, would necessarily prevent the successful working of a long line of range, when attempted for permanent telegraphic purposes. But at an elevation of twelve or sixteen thousand feet, which is easily reached on the Rocky Mountains and the Alps, we may tap the storehouse of the mighty thunder and make it whisper glad tidings over the seas.

And this fluid, abounding as it does without limit, is the very kind or nature most desirable for our uses, from its uniform tension and persistent quality, being superior in kind and better in practical action than that generated by artificial means, and all that remains to be done to make it available in telegraphing and the varied purposes of life is to properly reach forth and pluck it from thus its slumbering bed. That it will fulfill our requirements is recognized by scientific axioms and abundantly demonstrated by common and familiar occurrences in casual meteorology.

It is within the knowledge of almost everyone that during severe and heavy thunderstorms, or in the time of brilliant displays of the Northern lights, long lines of telegraph have been worked by the inductive force of these meteoric displays, which, although casual occurrences firing themselves into notice, nevertheless has cumulative evidence in behalf of my proposition (system). For absolute date of time and place, I will refer to one distinct instance out of many as illustrating the inductive effect of the electricity of the atmosphere working a telegraph line. On the 2nd of September, 1859, communications were sent over the wire between South Braintree and Fall River stations in Massachusetts, a distance of 40 miles, with the aid of the celestial battery alone. This was during the appearance of the Northern lights, which are computed to be, on the average, from two to five miles in height and frequently to possess strength of current equal to that produced by a battery of 200 grose cups. Many cases are recorded also of communications having been made during thunderstorms. And let me here observe that these local and limited displays are similar in their effect to the great overlying stratum which will forever yield its power without diminution; and furthermore, that the first telegraph with its double wire to form the circuit bears the same relation to the one now in use (since one wire has been abandoned, making use of the earth in its stead), as the present system bears to the one which I now actuate. The earth now forms one-half of the circuit in all the telegraph lines, and I simply propose to discard the remaining wire or cable and penetrate the insulating medium of the dense atmosphere reaching the electrical stratum above and around the earth, to form the other half as well, or to make this atmospheric element practically and usefully reciprocate its fellow element of the earth. The advantages gained in this, simply in the art of telegraphy, are immense and greater than might at first appear aside from the saving of a cable (which is $12,500 per annum for the W. U. Co.) is that also of the battery power, and yet a persistent current of volume and intensity is supplied, like the air we breathe freely, abundantly and without cost.

Independent of its use in the art of telegraphy, it will otherwise result beneficially, almost beyond computation. Disarming the tornado and the thunderstorm of their terror and subduing their power to useful purposes, even as in times past have been the waterfall and steam power, this element will come forth from its heavenly home the willing messenger of glad tidings and great power.

Professor Since, of London, in the last edition of his work on electricity, says: “The value of the steam engine over electrical contrivances depends upon the cheapness of coals as compared with zinc, for if ever the philosopher should discover an effective carbon battery where there is no decomposition of zinc, then will the steam engine cease, then will gas companies he compelled to stop their works and a total revolution will be produced in all the physical forces employed by man.”

I say, the great battery of nature is most essentially and emphatically this “carbon battery,” for consumes no metal, its volume is unlimited and it’s working power inexhaustible and without diminution.

And now it remains for us to simply avail ourselves of this immense treasure yielding us the three great essentials of human life, viz., light, heat and physical power as well as land or oceanic telegraphy, without artificial battery, wire or cable and all without expense beyond the original outlay for construction, as it will last forever when once established. De La Rire says: “The Aurora, or Northern lights, is due to electric discharges taking place in the Polar Regions between the positive electricity of the atmosphere and the negative electricity of the earth.”

This is doubtless true and correct, but I will go further and say also that it is only the *accidental* reunion of the two electricities, and that it can be brought about regularly and constantly by artificial and suitably established means as well.

Lightning is the *accidental* reunion of the two separate electricities through an incidental or casual conductor, and my proposition is to harmonize its working, or systematically regulate this intermittent and unequal action, by suitable channels of communication.

We have levied upon the forests to warm our hearthstones; we have mined into the earth and made her yield up her coal, and her still more refined products of oil and gas; but the expense of them all outweighing in value the wealth of the land and the seas lies untouched and undisturbed.

The waterfall goes to waste, unless we cut and build artificial channels to avail ourselves of its power. The bed of the river is often choked with obstructions, extending in consequence its seething marshlands, which yield malarious death and devastation, until the channel is so constructed as to give it free current to the sea.

So this great electrical ocean, slumbering with giant power, untold wealth and willing aid, waits but the proper sluiceways or conducting channels to illuminate and to drive the wheelwork of the world. But in its unclaimed usefulness, its wild and random freaks only cause death and universal terror.

The mill and factory will then run with a more subtle power, although the waterwheel stands dry and idle. Our dwellings will glow with wholesome heat on wintry days and be illuminated with clear, unwavering light in the night time from the steady and exhaustless flow of this vital element, and the miner of coal shall leave his toil in the shaft for a nobler handicraft among his fellows up in the sunlight and the world. The crude gold of Ophir may lie in the ground, but the pure smelted metal of Omnipotence lies in the stratum over it.

We of the present century have taken great and unwarrantable self-glorification unto ourselves for the so-called “taming of the lightnings of the heaven” or of “harnessing the thunderbolts of Jove to do our bidding.” It sounds grand and intellectually powerful, but this is in fact all bombast and utterly incorrect—for the lightnings of heaven are *just as much untamed as ever*. That great natural electrical ocean from which the thunder draws it’s kindling spark has not yet been explored nor even invaded by the “taming” hand of man. All that man has done so far is to set up little, puny “lightning rods” all over the land to be protected in some slight degree from its untamed power and appalling demonstrations, yet shrinking with terror from their inefficiency whenever the dark cloud gathers in the sky. *Franklin* demonstrated the practicability of drawing electricity from the clouds to the earth, but not one step has since been taken to pursue that fact to a profitable practice. Thousands of human lives and millions of dollars are sacrificed because we have not “tamed” this power, and still we will not understand or heed this loud voice proclaiming from the skies what might and majesty of concentrated power the Almighty has put in store for the benefit, and not the destruction, of man. Air, fire and water are formed and transformed by this element or power-made and unmade it. They are all convertible elements. And this electrical essence will yet melt the icebergs in the seas of Thor, and vessels may ride in safety on their “Northern passage,” the entire globe made more productive, all malaria cleared from the atmosphere and the entire climates of this our planet toned and tempered by it.

When the Black Hills of the West are reported to contain in many places particles of gold dust forthwith thousands of eager toilers dare dangers, deprivations and death in hope for the uncertain pursuit. But in this limitless field--richest of all domains--how comparatively few there are to labor! Yet the certainty of its unfathomed wealth is patent to every reflecting mind. It is the new Garden of Eden of whose ripened fruits we may reach forth and partake in the way that God prescribed only, avoiding the wrath of His flaming sword by avoiding the evil of tampering with its apples through the sin of ignorance, for on the day we do that *we shall surely die*.

It is the grand element of life, as well as usefulness and power. It dallies gently with a straw and yet chains a universe of worlds in absolute obedience to its laws. Notwithstanding we know its many ways and workings, still the scalpel of chemical surgery, though honed and whetted with 60 centuries of human brain oil, cannot dissect the anatomy of its closely woven fibres nor reach the heart of its mighty pulse beat. We view with curious eye the several little phenomena which it produces, but we sink appalled at the terrible demonstrations of its live energy and might! The bud and leaf unfold and grow beneath its vital force and the subtle springs of human life pulsate with its glow. 'Tis the germ-essence throughout all animated nature and the power that compels all inanimate nature into obedience to perfect law and order.

It “Warms in the sun, refreshes in the breeze, Glows in the stars and blossoms in the trees; Lives through all life, extends through all extent, Spreads undivided, operates unspent.” And all serenely above the tornadoes conflict this promethean torch smoulders with lambent flame, to awaken whose majesty and might we need but touch its celestial brazier, and Neptune's strident rising from the sea will “tame” and utilize the thunder. No greater field for discovery and usefulness could possibly be opened to men and the immense advantages that would immediately reward the opening of the ports into this Celestial Empire would transcend all the great physical works of the earth. In her youth continents spread out with broad domain teeming with the fruitage of a new inheritance, and if we charter forth but one small vessel on an expedition to its genial shores, we may rest assured that it will return laden with more than the golden sands of the memorable Castellan fleet of three.

Sanded discoveries necessarily have limits set and their outlines are well-nigh traced. But in this dominion is the home of that mystic needle which points the way to all other lands and space and the limits of this domain are only measured by the red-winged spark from the eternal God into the dim haze of the uttermost Thule.

No great Alexander need ever weep again because he has no kingdoms to conquer, for here is ample field for noble ambition. Battalions armed with the hand of thought may march forth to profitable victory here. Here is field to construct interminable highways whose fleet chariots shall be laden with human thoughts coming and going for the good of man; and in these field new empires shall be conquered and new habitations built. Expeditions to the ice field of the North Pole offer but a meager reward even in the event of successful return. The immense work of the Pharaoh pyramids is great in the world's history. Bridging or tunneling the Straits of Dover and opening the Suez and Darien Canals are mighty projects, which, completed with the expenditure of untold treasure, will, no doubt, add many comforts to many nations; although their immediate benefit is of a local nature, but verify this proposition and the very *world* will shake and tremble at the august consummation and the souls of all her people will rejoice and be made glad.

What is there in this proposition savoring of impossibility, when all the elements of success involved are based on acknowledged facts and laws, as it is in science? The only argument that can be brought against it is the time-honored one, ever urged with so much pertinacity--*that it never has been done*--hence it is a vision and a folly. But the history of all important projects is that they have, from the remotest antiquity, been opposed simply on the ground of their being new. New and original enterprises never lack specious arguments to show their fallacy; and that which does cause and forever has caused strongest opposition to new realities in the public mind is the mere fact that they are *new* and previously unaccomplished. Yet everyone knows the futility and folly of this. The greater the magnitude of the enterprise, the greater might is this fallacy allowed to have.

When the theory of the rotation of the earth was first asserted it was denounced as the vagary of an abberated mind, because it was new and startling.

The theory, although well established by logic and reasoning, that there was another opposite side of the world from Europe was not kindly entertained there late in the fifteenth century. Thirty years ago Morse was looked upon as a crazy man. Just previous to laying the first Atlantic cable men eminent in learning gave an abundance of sage reasoning *why* it could never he made to transmit a message.

But all these combatted truths, which come up from time to time, appearing strange and erroneous simply because they are startlingly new, and because the scientific world has never previously recognized them in a collective and distinct manner, are the very leaven of our civilization--the sword and artillery that fight the hosts of the prince of darkness and elevate the standard of humanity. Nothing was ever lost by granting breath to the new-born child of science; but the world has forever lost and suffered by attempts at strangulation or the coldness of sympathy and neglect. It is one thing to strike physical fetters from oppressed races of man and aid them in their toil for prosperity and pursuit of happiness, but it is another and still greater to unbar the imprisoned thoughts of man--these angelic slaves--struggling under the lasts of derision and starving from cold neglect, especially when the purple and fine linen of our generation's pride of cultured elevation are spun and woven by the loom and anvil brain-stroke of these same enslaved and patient silent workers. But the world has from all time united in keeping them down and aided in maintaining this slavery.

The morning comes slowly, but the hour is about passed and gone when men may slight with impunity or turn indifferently away from the new born revelations that toiling, pioneering minds garner from rugged fields planted by the living God for our higher harvest and refinement. And it is not well for any man to oppose the growth or progress of these new plants that bud and promise, for the surely avenging Nemesis will follow on the trail of him or them who dare oppress the struggling truths of God, for shame and disgrace shall come sooner or later as their well-merited inheritance.

It is touching a class of sacred matters, which to the disgrace of individuals and the world has been ignored too frequently. And it is high noon of the day when the tide must turn and these slighted truths vital to our well being and our first pride of humanity must be allowed the sunlight and the helping hand. And if this my plan which promises so much for the benefit of man is erroneous or unimportant then prick it as a bubble and expose its empty nothingness. But meantime I am firm in the faith that this immense belt, like the rings around our sister planet Saturn, will yet form the halo of greatness and intelligence about our heads.

Common sense and intuitive perception declare it to be right; scientific facts and all the elements of earth and air array themselves in its defense; for it is founded on the solid was laid of the universe and its corner-stone was laid by the Great Builder.

MAHLON LOOMIS
January 7, 1872

Brooklyn Eagle
July 10, 1932
Nikola Tesla States:



"I have harnessed the cosmic rays and caused them to operate a motive device. I have advanced a theory of the cosmic rays and at every step of my investigations I have found it completely justified. The attractive feature of the cosmic rays is their constancy. They shower down on us throughout the whole 24 hours, and if a power plant is developed to use their power it will not require devices for storing energy as would be necessary with devices using wind, tide or sunlight. All of my investigations seem to point to the conclusion that they are small particles, each carrying so small a charge that we are justified in calling them neutrons. They move with great velocity, exceeding that of light. More than 25 years ago I began my efforts to harness the cosmic rays and I can now state that I have succeeded in operating a motive device by means of them. I will tell you in the most general way, the cosmic ray ionizes the air, and setting free many charged ions and electrons. These charges are captured in a condenser [capacitor] which is made to discharge through the circuit of the motor. I have hopes of building my motor on a large scale, but circumstances have not been favorable to carrying out my plan."

Philadelphia Public Ledger
November 2, 1933
Tesla 'Harnesses' Cosmic Energy

Inventor announces discovery to displace fuel in driving machinery. Calls Sun main source. A principle by which power for driving machinery of the world may be developed from the cosmic energy which operates the universe, has been discovered by Nikola Tesla, noted physicist and inventor of scientific devices, he announced today. This principle, which taps a source of power described as "everywhere present in unlimited quantities" and which may be transmitted by wire or wireless from central plants to any part of the globe, will eliminate the need of coal, oil, gas or any other of the common fuels, he said.

Dr. Tesla in a statement today at his hotel indicated the time was not far distant when the principle would be ready for practical commercial development. Asked whether the sudden introduction of his principle would upset the present economic system, Dr. Tesla replied, "It is badly upset already." He added that now as never before was the time ripe for the development of new resources. While in its present form the theory calls for the development of energy in central plants requiring vast machinery. Dr. Tesla said he might be able to work out a plan for its use by individuals. The central source of cosmic energy for the earth is the Sun, Dr. Tesla said, but "night will not interrupt the flow of new power supply." Clearly Tesla is not talking about an atomic reactor. He spoke about directly converting the ions contained within the confines of our Planet's Atmosphere, where they are created from the Radiant Energy of the Sun and are directly converted to electrical power!

Tesla believed that the Sun generates cosmic rays that strike the atmosphere of our planet which creates these highly charged particles. These charged particles (air ions) are the re-transmitters of Radiant Energy; it is this transfer of energy that could be used for practical purposes.

The mystery surrounding the direct conversion of the Radiant Energy of the Sun, the Cosmic Rays and the natural background radiation will unlock untold amounts of energy. Under the proper conditions, it can be rendered susceptible to the most incomprehensible changes caused by the oscillations, pulsation and surging throughout the Universe.

With Minimal Environmental Impact; a unique ion-valve has been designed and constructed by the author of this radiant energy research manual to provide a dam to the ionic surging of the atmosphere of our planet. If an oscillating tank circuit is used in conjunction with this valve, and it has the correct impedance, reactance and inductance, it will absorb the energy which can be transformed into useful electrical power. The tank oscillations are kept alive by establishing resonance with the surging throughout the Universe. Therefore, energy is not drawn from the transformer that powers the tank circuit. In the case of the radiant energy receiver, it becomes possible to draw energy into a properly designed electronic circuit with the aid of specially constructed electrical plasma tubes (ion valves). The implication of this energy source is mind boggling. A properly constructed receiver will harness electrical power from the energy of the Sun, the Cosmic Rays and from the Natural Background Radiation of the planet. It is a glorified Radiant Energy receiver, and one that is designed to receive and convert the oscillations of the Universe which is being generated. The device locks onto the very wheelwork of nature. When properly constructed it should last for many years with very little maintenance, no more than is required for a good radio receiver.

It will be understood that the energy that is being harnessed is not perpetual energy. Everything in the Universe eventually returns from whence it came. What is claimed is a device that can extract energy from the charged intermolecular ions that surround our planet, otherwise referred as the radiant energy of the Sun.

All that is needed is to build a receiver that will collect and convert it into useful electrical power. Present day alternative energy researchers find hope in that, one day, power will be obtained from the energy that runs the Cosmos. In reality, this dream has only proved to be a lure to its followers, beyond the limits of credibility. A quagmire of unsubstantiated hypotheses exists that are bottomless and lack reality. The facts of many newly conceived energy concepts are wholly inadequate, lacking justification, and is incapable of throwing any light on the promise of an inexpensive, abundant sources of energy. The Earth is indeed bathed in a sea of untapped energy that can be transformed into useful electrical power.

When electrically charged gas ions discharge it appears to be an incidental event that amounts to nothing more than a passing curiosity. It is sometimes seen as a natural event called "**Saint Elmo's fire**." It occurs when negatively and positively charged air molecules are mutually attracted to each other and neutralize each other through a process known as **corona discharge**. The fact is that this electrical discharge phenomenon is at the very heart of the radioionic receiver. Sharp pulses of electromagnetic energy are generated, which can then be transformed into useful electrical power with the use of a properly designed radioionic energy receiver.



Atmospheric Electricity and Terrestrial Magnetism

This energy receiver uses its ion valve corona discharger to electrically neutralize positively charged atmospheric ions with negatively charged ground ions. The end result is a pulsating unidirectional flow of radioionic oscillations which is further transformed into a useful flow of electrical power. When the radioionic receiver is synchronized (tuned) to the frequency of the generated electromagnetic ionic charge oscillations it transforms the high potential, low current into a more useful lower potential, higher current oscillating flow of electricity. Since the time of Benjamin Franklin's famous kite experiments not much has been learned about the nature of electrical charge and how to convert it into useful power. Certain people have discussed this to some extent. Some theoretical papers in the so-called "free energy" field have been written. Many of these theorists will even consider that ionizing particles can be utilized to produce usable amounts of electrical power. Nevertheless, I have taken it upon myself, with great personal conviction, to find a solution to converting charged particles that are stored within the Earth's Atmosphere into useful electrical power. I have found with the correct circuits and components, that ions can be efficiently transformed into useful electrical currents. It is my desire to be able to furnish irrefutable proof of this discovery. To begin this journey, scientists and researchers alike will have to snap out of their state of denial. The utilization of ionizing energy on completely new ground has to take place. The production and utilization of energy obtained from natural sources for the well being of humankind has been the goal of scholars and researchers for many years. This is because well intentioned researchers turn away from the simple fact that there is free electricity to be obtained from the planetary storehouse of ions. When large enough quantities of atmospheric ions are collected they can be converted into useful electrical power. Many researchers after investigating atmospheric electricity become astonished when they realize that it is a source that can be converted into useful electrical power and that it has been right under their noses all along.

To capture these ions an opposite polarity must be applied to one lead of an electrical capacitor. The electrostatic potential difference (high voltage) which is stored between the capacitor plates must be transformed into a suitable form of electricity because our electrical appliances aren't designed to function on this form of energy.

"Helium discovered on March 26, 1895, by Scottish Sir William Ramsay. He isolated it from the mineral cleveite which is a variety of uraninite. In every case where helium has been isolated, a radioactive substance has also been found in the mineral. The assumption has therefore been made that, since radium is continually changing into helium, where there is helium there is still, or must have been, radium; hence the obvious suggestion has been made that there is radium in the sun, and even that it plays a large part in the solar radiation. It has been calculated that 3.6 grams of radium per square meter of the sun's surface would amply suffice to supply all the heat the sun radiates. This throws a new light upon the age of the sun. Lord Kelvin, basing his arguments upon the consideration that the sun is a slowly cooling white-hot body, stated that it could not possibly be more than 20 million years old. Geologists, to account for the deposition of continents and the period of elevation, demanded at least 100 million years. The discovery of radium has thrown quite a new light upon the question. If the solar radiation is due either entirely, or in part, to the presence of radio-active bodies in the sun, it may be considerably older than was before considered possible by the physicist. The idea may occur that as radium gives off rays which are harmful to man, would the presence of so large a quantity of radium in the sun be detrimental, if not fatal, to life on the earth? Strutt and Joly have considered the problem from a mathematical point of view, both coming to the conclusion that it is very improbable that any of the radium rays could reach us at our great distance from the sun. Plausible explanations can be given of the earth's electricity and magnetism on the assumption that the sun's radiation is due wholly, or in part, to the presence of radium. It has long been known that the higher regions of the earth's atmosphere are at a higher potential than the lower. What this means is that the electricity of the higher regions is positive compared to that of the lower regions. If the sun's radiation is due to radium, the alpha radiation, proceeding towards the earth, would be absorbed by the outer layers of the earth's atmosphere, thus charging them with positive electricity. The beta radiation, being much more penetrative, would not be absorbed nearly so easily, and might reach the lower layers and the earth itself.

This would account for the negative potential of the lower layers of the atmosphere and of the earth. It has been experimentally shown that during the daytime, up to mid-day the outer layers of the air have been absorbing the alpha rays, while the beta radiation has mostly passed through. This accumulation of positive electricity stops to a much greater extent the negatively charged beta rays. A maximum effect is, therefore, produced about mid-day. The charges will be gradually dissipated as evening approaches, so that the potential difference diminishes. Looking down upon the earth above the north Geographical pole, the direction of rotation is counter clockwise. If the negatively charged particles in the lower regions of the atmosphere are carried round by the diurnal rotation, a magnetic field is thus established with the south pole in the position of the north geographical pole, and vice versa. It is well known that magnetic storms on the earth occur at periods of maximum sun-spot activity. This may be explained by the greater activity of the sun causing it to project electrons at a maximum rate towards the earth at such periods."

The Study of Meteorology

When the study of meteorology first began there was a big interest in atmospheric electricity. Many in this field thought to use it. This is revealed through the patents of the time. The first relevant patent was granted to inventor Dr. Heinrich Rudolph of St. Goarshausen, according to the German Patent Office; D.R.P. No. 98180 January 19, 1897.

Hermann Plauson was successful in converting atmospheric energy into useful electrical currents. He was granted a patent titled “Conversion of Atmospheric Electric Energy” U.S. Patent No. 1,540,998. In his patent he states, “St. Elmo’s fire and the northern lights can be more or less absorbed in the same way as a receiver in wireless telegraphy absorbs waves coming from a far distance.” It contains the foundation to building a powerful ion energy receiving and power conversion device.

There are three major causes of atmospheric ionization. The first one is due to the cosmic rays and the second cause is due to the solar winds. Over 95% of the particles in the solar wind are electrons and protons, in roughly equal numbers. Almost all of these high-energy particles interact with the earth's upper atmosphere causing it to become ionized. This is why the upper atmosphere is called the ionosphere. However, the area where the reaction between the solar wind and the magnetosphere takes place is far outside of the earth's atmosphere. The charged solar wind particles rattle the magnetic cage of our planet long before its gas envelope neutralizes them. The third cause of atmospheric ionization is due to the content of radioactive gas contained in the air that we breathe. In the ground radioactive substances such as radium, thorium, and actinium are spread throughout the soil. These elements generate gaseous radioactive emanations that spread in the air and ionize its molecules. The actinium-emanation generated from the decay of U235 plays a major role because of its brief radioactive half-life of only 3.9 seconds. Air, a mixture of gases, is largely composed of nitrogen and oxygen. It is generally considered as an insulator, and would be an excellent one if all the oxygen and nitrogen molecules were in the neutral state. However, the air is actually composed of varying quantities of neutral molecules and positive and negative ions. As the number of ions in the air is increased, the air becomes a progressively better conductor. In general, gradually more ions are found the higher we ascend until, at about a height of forty to fifty miles, a region called the ionosphere is reached. Here, there are sufficient numbers of ions to reflect radio waves. The ionosphere, although conductive, can be considered as a whole as being uncharged. This is due to the number of positive ions being equal to the number of negative ions plus electrons that are distributed in layers varying in height and in degree of ionization. In contrast, the earth has a surplus of electrons and is actually about 300,000 to 400,000 volts negative with respect to the ionosphere. This potential difference together with the total conductive qualities of the atmosphere is sufficient to cause the earth to continually lose electrons to the ionosphere. The entire earth’s surface and the ionosphere may be considered to be oppositely-charged plates of a vast capacitor with the air between them acting as a rather inferior insulator, for it leaks continuously. In addition to the presence of ions, which make the atmosphere slightly conductive, various meteorological processes called precipitation or hydrologic cycle, contribute to the leakage rate of this earth capacitor. Falling rain tends to bring down the less-mobile large ions toward the earth while electrons are carried upwards on rising moisture-laden air. This steady loss of electrons from the earth is called ionic current, and, infinitesimal as it is, it has been measured and amounts to about 9 micro amps for every square mile of the earth's surface. This current flows from the earth via the most convenient conductive path or those offering the least electrical resistance. Most of the electrons are discharged at natural and man-made points that project into the atmosphere. Static discharge can also occur when electrically charged particles (raindrops, snow, dust, etc.) strike the antenna of a radio receiver, inducing a current impulse in the associated circuitry and thereby producing broadband radio frequency noise.


RADIO
MICROWAVE
INFRARED
VISIBLE LIGHT
UV
HIGH-ENERGY
X-RAY
GAMMA
WAVELENGTH 5,000,000,000 10,000 500 250 0.5 0.0005 nanometers
ENERGY 0.000000248 0.124 2.48 4.96 2480 2,480,000 electron volts

The Origin of Lightning

In the "Origin of Lightning," Lockheed Service Digest Professor Langley showed that out of the total amount of radiation which is coming from the sun, that the visible portion represents only 19% of the total spectrum. He presented the theory that there is only one kind of energy radiated from sunlight. That, heat, and chemical effects depend entirely upon the state or condition which radiant energy may happen to fall on matter.

The Italian physicist Melloni stated that, "light is merely a series of caloric indications sensible to the organs of sight, or vice versa, the radiation of obscure heat are veritable invisible radiation of light." Melloni wrote this in 1843, but it was not adopted until Langley by his elaborate researches, more refined and complex, that proved when a mighty tongue of white hot matter darts across the abyss of a large spot or cavern on the sun, the equilibrium of the Earth's magnetic field is disturbed and the effect is an electromagnetic storm.

The needle of any magnetograph throughout the world will quiver and oscillate. These vibrations pass from the sun to the surface of our planet that is closest to it. These impulses then pass to the most distant side, whether through or around the planet's surface. After centuries of investigation from Gilbert to Tesla, this most wonderful research still holds admiration and mystery for all that study this vast science; electrodynamics. Power is cut out of the seemingly emptiness of space, and the hurrying waves are caught and chained to servitude in artificial light and electric appliances. The sun, being electromagnetic, emits waves that carry power, which beat and surge against the earth. A magnetic field is space that surrounds a magnet.

The most memorable magnetic storm occurred on November 17, 1882. This was one of the most violent recorded. The daily press was burdened with accounts of widespread magnetic disturbance. In some places telegraphic communication was suspended. The turbulence stretched from New York to Yankton, Nashville, and Winnipeg. In Milwaukee, the carbons in the electric lamps were lighted, rendered incandescent by currents of electricity flowing on the wires. At other locations, switchboards in telegraph offices were set on fire and sending keys were melted, while electric balls were seen hovering on the telegraph lines in Nebraska.

The earth's aurora holds the key to harnessing the sun's daily pulsation. An aurora is the visible effect of obscure undulations from the sun, as they come dashing on the earth with a speed of 186,000 miles per second. In a six-month winter, say at the North Pole of the earth, where the sun is far south of the equator, and none of its rays can shine on the earth's northern pole, the aurora is very bright. It displays many colors, and these flash and glow with rapid variations.

This space might be filled with air, wood, stone, glass, or might be a vacuum. Nevertheless, the waves are not quenched. They flow through all of these things. A freely suspended magnet in a magnetic field will move, and the earth's surface is surrounded by a magnetic field, that is acted upon by the sun's magnetic field. Suspend a sewing needle by a silk fiber in the earth's magnetic field and it will come to rest parallel to the field's north and south poles. Now, if this field becomes disturbed, that is, if it becomes stronger or weaker, the needle will move. This is a magnetic storm. When a gas jet is hurled across a spot on the sun, the disturbance reaches the earth in the same time that light does. Therefore, the radiance travels at 186,000 miles per second reaching the earth in eight minutes and nineteen seconds.

The light, although caused by the sun, does not come direct. It is caused by the turbulence set up in the earth's magnetic field by electromagnetic upheaval on the sun. The field of the earth is "tuned" with the sun's field, as was the coherer in the days of wireless telegraphy and telephony. The aurora is known to be electrical, magnets and compass needles on ships are always affected. Could the coherer of the days of old teach us something new?

No magnet can be placed near a "current" of electricity or a static charge without making an oscillation. Every oscillation sends out a wave, like a stone falling in water. An electromagnetic wave from the sun disturbs the earth's magnetic field in the same way that an induction coil used in wireless telegraphy does. The earth and coherer are both doing the same thing with the same kind of electromagnetic waves. The coherer in a distant receiving station will react to natural electromagnetic wave fronts from the sun. It will likewise react to the artificial wave fronts coming from the induction coil. The electromagnetic wave makes the loose particles of metal between the knobs in the glass tube coherer generate dots and dashes.

No magnet can be placed near a "current" of electricity or a static charge without making an oscillation. Every oscillation sends out a wave, like a stone falling in water.

The earth and coherer are both doing the same thing with the same kind of electromagnetic waves. The coherer in a distant receiving station will react to natural electromagnetic wave fronts from the sun. It will likewise react to the artificial wave fronts coming from the induction coil. The glass tube coherer generates dots and dashes. An Electromagnetic wave from the sun disturbs the earth's magnetic field in the same way that an induction coil used in wireless telegraphy does.

At first glance there aren't enough charged ions in the air to be converted into electrical power. This assumption on the surface appears to be a correct calculation assumption. You can say that there are not enough of them floating about. However, these ions are in a state of constant surging motion. By studying this particular sea of energy we can gather clues to obtaining power from its charged particles. To obtain electrical current from a generator its magnets must also be in a state of constant motion. Do you see a correlation here? What we learn is that charge in motion **induces** electrical current. The earth floats in a sea of ions that are forever present in its atmosphere. They are mostly generated when ultraviolet light coming from the Sun is absorbed in the ionosphere which surrounds our planet.

The Aurora Borealis is definitely considered an electrical phenomenon produced by the motion of electric charges through the rarefied gases of the upper atmosphere. The conducting ionosphere causes instability of this Earth energy model by short circuiting the ions in the Earth electric field. Auroral displays result in a process called ring currents, which occurs along magnetic field lines that connect the magneto tail with the ionosphere. This is the primary supply of planetary ionic energy for what is seen as the "aurora," setting up an oscillating field of ionized particles; therefore forming the aurora light display. It generates **radioionic radiation**. The light display is generated by ion convection currents that are formed in the plasma energy field of the magneto tail. These ion convention currents curve toward the Earth on the night side and enter or create the aurora light display at around 68 degrees latitude between 22 and 24 hours local time. The RIR has a frequency spectrum from around **17 to about 500 kHz,** with a peak power at around **200 kHz**. The total power is about 1,000 Megawatts. It originates at a low altitude, less than three Earth radii, with a power factor of about one per cent of the energy dissipation of the auroral ion particle streams. It appears that the on rushing ionizing particles excites the ionosphere, thereby generating powerful energies. Very strong radioionic currents have been reported, between **17.8 and 100 kHz,** with the greatest amplitude at around **31.1 kHz.** Some of these same frequencies have been observed by the Voyager II when it passed through the magnetospheres of Jupiter and Saturn.

RADIOIONIC ENERGY RECEIVER v5.4.7



Fundamental Description

The earth floats in a sea of ions that are forever present in its atmosphere. They are mostly generated when ultraviolet light coming from the Sun is absorbed in the ionosphere which surrounds our planet. To capture these ions an opposite polarity must be applied to one lead of an electrical capacitor. The electrostatic potential difference (high voltage) which is stored between the capacitor plates must be transformed into a suitable form of electricity because our electrical appliances aren't designed to function on this form of energy. They cannot be powered with raw ions. They require electromagnetic energy to function. No means were known to directly or to indirectly convert ionic charge (electrostatic) energy into electromagnetic energy (electricity).

Similar to the reception of radio waves, a properly tuned radioionic energy receiver can be tuned into resonance by the right arrangement of inductance and capacities. The components respond to the particular wave frequency "oscillations" of energy from the Planet. An ion valve dams the charge coming from the antenna and charges a bank of capacitors. The high voltage charge thus obtained can be stepped down into useful electrical power utilizing conventional electrical circuits.

The radioionic valve converter generates only a minute amount of waste heat and it can be built into a compact and light weight system. It offers a huge advantage of power to weight ratio, than all other energy sources, to the best of my knowledge. A conventional electrical generator must have mechanical power applied to it to make its rotor revolve while my radioionic generator sits perfectly still, requiring only an antenna to pick up the energy from its surroundings. There is an unlimited source of electricity that surrounds our entire planet that can be efficiently harnessed using radioionic valve converters.

I am not claiming any new laws of physics as having been discovered. I am simply expanding on what is presently known. What I do claim is that my method to convert the energy that is contained in the Earth's atmosphere is unique. Electrical power "generation" is accomplished through the utilization of oscillating ions. It is my objective to offer to the common person an affordable radioionic energy receiver which generates useful electrical power from the plentiful supply of planetary ions. The ever present quantity of "free" ions that are stored in the air and in the ground are diverted to flow through a new and improved ion valve, which doesn't require any exotic materials. The radioionic valve functions as a cold cathode corona mixing component which generates radioionic electrical power, using only the energy taken from the planet.

The antenna of a radioionic receiver draws in energy from the plentiful supply of ambient ions, which are generated from the ionizing ultraviolet solar radiation. The radioionic generator doesn't require the direct exposure of the Sun to maintain ionization as it operates during the night hours. Cosmic rays, terrestrial radioactivity and man-made electrical noise sources contribute only a small amount to the ionization process. The Sun is the primary cause of planetary ionization.

Circuit Key

To understand how the circuitry works you must already have a basic understanding of the elementary principles of radio technology. Granting this, it is of course reasonable to believe that you will understand how an oscillating current is set up in a circuit comprising an inductance or coil of wire, a capacitor and a spark gap.

The energy that is building up in the capacitor (**C2**) exists between the anode, cathode inter electrode gap of Perreault Plasma Valve (**PPV1**) literally over-reaches itself, just as a pendulum will swing past its neutral point when given a push by the hand. After the first rush of current passes in one direction, a reversal of the cycle occurs and a second rush in the opposite direction occurs. This operation is repeated many thousands of times per second. The discharge gradually dies down as all the energy is either completely radiated, used up in heating or in performing work. The oscillations cease once the potential across the capacitor has been reduced, and can no longer sustain a plasma field within the Perreault Plasma Valve (**PPV1**). The capacitor (**C2**) and inductor (**L1**) constitutes a tank circuit which is charged with the high tension ions that exists between the earth and its soil, where a highly energetic plasma field exists within the Perreault Plasma Valve (**PPV1**). The Perreault Plasma Valve (**PPV1**) acts as a high speed switch which disrupts the field causing it to pulsate at an extreme rate of frequency. The Perreault Plasma Valve (**PPV1**) discharges thru a succession of crashing sparks. Capacitor (**C2**) can immediately take a fresh charge from the antenna (**ANT**) that is a supply of **electropositive ions,** which in turn generates the plasma field within the Perreault Plasma Valve (**PPV1**), and the entire cycle of operations is repeated. The variable **1** to **20,000 volts** high voltage multiplier (**HVM**) is driven by the voltage multiplier **(HVM)** module. The high voltage module **(HVM)** obtains its power from the charged Ultra Capacitors (**UC1 – UC6**). The tank circuit inductor (**L1**) and capacitor (**C2**) is kept alive through the discharge of the Perreault Plasma Valve **(PPV1)**. It will be understood that all of this passes in an infinitesimal fraction of a second. It should also be understood that if this oscillating tank circuit has the correct impedance, reactance, and inductance, it will absorb energy from the antenna source of ions. With the correct conditions being met the tank oscillations can be kept alive by establishing resonance with the supply of planetary ions. The surge of radioionic high frequency waves is generated through the inductor (**L1**) coil. The high frequency electrostatic oscillations (radioionic) waves produced are induced into inductor (**L2**) transforming them into useful electromagnetic energy.

ANT – Bare copper wire, electrically isolated at least 5 feet height from the ground, optimally around 468 feet in horizontal length.

IN1, IN2 – Electrically non-conductive insulators.

G1 – Earth grounding rod.

L1 – Inductor: Tesla Secondary Coil; resonant in the 500 kHz range.

L2 – Inductor: Tesla Primary coil.

T1 – PVC tube for Tesla coil air core, not shown.

PPV1 – Perreault Plasma Valve: an open air improved, compact, open air valve, for efficiently generating high frequency, high power, electromagnetic oscillations with direct current. It consists of an *iron* (**Fe**) *cathode* and *aluminum anode* (**Al**) **thermoelectric** dissimilar metal couple. This thermoelectric couple generates intense radioionic oscillations with high efficiency, consuming the least amount of current, so that the maximum amount of current can flow through the inductor (**L1**), capacitor (**C2**) tank circuit, to provide power to the load (**L**). A more efficient cathode, anode combination might be used. Check with a good thermoelectric series chart. The most efficient and practical thermoelectric couple combination appears to be iron (**Fe**) and aluminum (**Al**). The choice made all depends on efficiency of the couple, material availability, cost, and the difficulty level working with the materials chosen. When you use a new Perreault Plasma Valve (**PPV1**) the output power of the receiver starts out much lower than when it has been used. Every second you use it the better it performs. You will find that the longer it is used the more energy is obtained from the receiver. A new, not yet used Perreault Plasma Valve (**PPV1**) will only give a fraction of the power of a broken in Perreault Plasma Valve (**PPV1**).

The Perreault Plasma Valve (**PPV1**) generates an oscillating electromagnetic field with every ionized particle that impinges upon its thermoelectric cathode to anode couple. An avalanche of secondary ions is also emitted with every ion which impinges upon the cathode. When the positive and negative ions mix they neutralize each other, generating a surge of electromagnetic waves of electrical power. Simply stated, the radioionic receiver obtains natural energy from a common radio antenna. This unique valve conducts oscillating ionic energy and converts it into oscillating electromagnetic energy. The high frequency can be transformed into a more desirable voltage, using a step down transformer configuration. This high frequency electricity can be used to supply power to conventional incandescent light-bulbs which provides a highly efficient light source.

The radioionic frequency is so high that its oscillations are a product of all the inductances of the circuit which are ringing from the high frequency spikes. The more voltage, not current, that is applied across the Perreault Plasma Valve (**PPV1**) the more power output will be obtained to power loads. To generate the radioionic oscillations efficiently you need only high voltage and no, or little current. If too much current is supplied then the current will suppress the high frequency radioionic oscillations. So, basically your source of high voltage must have a very high, if not infinite resistance and impedance from the positive air ions, as compared to the **electronegative** ground ions; the higher the potential difference that is supplied to the receiver the better. The high voltage module (**HVM**) fills this requirement.

To sum it all up; the Perreault Plasma Valve (**PPV1**) converts the high potential **electropositive air ions** into a high speed, high frequency electric power, and while doing so only allow current to flow only in one direction. Tank circuit inductor (**L2**) and capacitor (**C3**) is used to step down the voltage that surges through inductor **(L1)**.

This tank circuit converts the high voltage into a useful lower voltage. The electrical power that is generated to power electrical loads is high frequency. When this form of energy powers a light bulb, or fluorescent lamp an intense white light is produced. The light from a lamp that utilizes this form of electrical energy imparts an unusual glow to the light bulb. A light bulb displays a clear brilliancy without the associated haze that normally surrounds its filament when conventional 60 Hz electricity is used. Another added benefit of this high frequency electricity is that expensive and potentially hazardous fluorescent lamps that contain mercury can be replaced. The high frequency electricity can also be transmitted over hair size wires, minimizing the use of expensive wire. The wires that connect to the lamp will not generate heat as is normally expected, which is the case when using conventional electricity. It is surprising to see that when a lamp is electrically shorted with a piece of wire it still shines brightly! The high frequency electricity can be used directly to power lamps, or specially wound high frequency motors. When it is converted into **12 volts** direct current, using a diode that responds well to the high frequency, it can charge a direct current storage component.

C1 – Fixed capacitor: .001/20K volts.

C2, C3 – Variable air tuning capacitor: 250pF/1,500 volts.

PPV1 – Perreault Plasma Valve: See description on page 23.

D1, D2, D3, D4 – Diode: Shottky 1N5817 or equivalent. This is a low voltage radio frequency diode which converts radio frequency into a direct flow of useful current, where it is then stored in a bank of Ultra Capacitors (**UC1 – UC6**). An alternative method to store the electrical current that is received from the inductor (**L1**) can also be used. The stored energy is used to power the high voltage module (**HVM**), which allows the radioionic energy receiver to be self sustaining.

D5 – Diode: 20kV fast recovery.

R1 – Resistor: 10M ohm, fixed. This limits the output current of the high voltage module (**HVM**).

HVM – High Voltage Module: 20kV step up from 12 to 16 volts, 20-50 kHz, low current, variable output source. Diode (**D5**) puts a positive ionizing charge on the antenna (**ANT**). A half-wave series 250,000 volt Cockcroft–Walton multiplier (Greinacher multiplier) can be added as an option to the output, not shown. The addition of a voltage multiplier will increase the collection area of the antenna (**ANT**).

L – High Frequency Load: 12 volt RV or automotive repair incandescent bulb. The wires going to a light bulb don't get hot, only the bulb, or load (**L**) emits heat, this is because the electrical power is a high frequency, which can also be electrically shorted with a piece of wire and still provide power.

UC1, UC2, UC3, UC4, UC5, UC6 – Ultra Capacitor: 2.7 volt 500 Farad.

SW1 – Switch on/off.

Circuit Theory

1. The circuit shown draws into its elevated antenna (**ANT**) ambient ions that are stored in the air and in the soil of the planet. Positively charged air molecules (**+ions**) concentrate around the antenna (**ANT**) that is elevated in the air and is fed to an inductor (**L1**).

2. The aluminum **(Al)** anode cylinder of the Perreault Plasma Valve (**PPV1**) receives a positive charge from the positively charged antenna wire (**ANT**) and the high voltage module (**HVM**). Negatively charged ions are generated along the surface of its iron (**Fe**) cathode wire.

3. Negatively charged ions ground ions concentrate around an earthed grounding rod (**G1**) that is embedded in the earth's aerated soil. The cathode wire of the Perreault Plasma Valve (**PPV1**) receives a negative charge from the negatively charged ground rod (**G1**). Negatively charged ions are generated on the surface of the valve corona wire of the Perreault Plasma Valves (**PPV1**).

4. The Perreault Plasma Valve (**PPV1**) neutralizes the positively charged ions on its aluminum **(Al)** anode cylinder with onrushing negatively charged ions that are emitted from its iron (**Fe**) cathode wire. It is here where the oppositely charged ions are electrically neutralized and are converted into useful electromagnetic energy through the inductance of air core inductor (**L1**).

5. The high voltage oscillating electromagnetic field of primary inductor (**L1**) induces an electrical current into the secondary inductor (**L2**). Capacitor (**C2**) and capacitor (**C3**) tunes their respective tank circuits to synchronize with each other to maximize efficiency.

6. Inductor (**L1**) and variable air tuning 250pF 1,500 volt capacitor (**C2**) functions together as an electrical tank circuit. Capacitor (**C2**) is charged with the ever present positively charged ambient air ions which flow from the **(ANT)** to the ground **(G1)** supply of negative ions. The inductor (**L2**) has a lower number of turns compared inductor (**L1**). This has the effect of transforming the received high voltage oscillations into a lower voltage, higher amperage, alternating electrical current of useful electrical power.

7. The alternating electrical current is then rectified with diodes **D1**, **D2**, **D3** and **D4**, which are low voltage, radio frequency, **Shottky 1N5817**, or equivalent diodes.

8. The rectified electrical power charges **2.7 volt** 500 Farad (**UC1**), (**UC2**), (**UC3**), (**UC4**), (**UC5**), and (**UC6**) Ultra Capacitors, where they becomes a useful source of **12 – 16 volts** of stored direct electrical power.

9. Balancing resistors, not shown in the circuit, for simplicity, are used to ensure that the Ultra Capacitors **UC1**, **UC2**, **UC3**, **UC4**, **UC5**, and **UC6** are equally charged to avoid damage to them. A 12 volt regulation circuit is also used to avoid damaging the Ultra Capacitors **UC1**, **UC2**, **UC3**, **UC4**, **UC5**, and **UC6**.

10. The high frequency current at the load (**L**) can be used to power lamps, other high frequency motors, or inductive heating appliances. When it powers a light bulb, or fluorescent lamp, the light is pure white and it is extremely bright!

11. A **lightning arrester**, not shown in the diagram can be added to protect the circuit against lightening strikes. It would be connected between the antenna (**ANT**) and earth ground (**G1**).

Operating Instructions



1. Glass enclosure **2.** Cathode corona wire **3.** Anode cylinder **4.** Radon (radium ore) impregnated ceramic disc **5.** External; corona wire electrical contact terminal **6.** External anode cylinder electrical contact terminal.

What makes the present method to obtain electrical power from the planetary ions practical is that extreme antenna is height is not required. It does this with the aid of a high voltage, low current, electronically generated source, shown as a high voltage module (**HVM**) in the circuit diagram. This high voltage electronic source is a replacement for the **Atomic Ion Valve**, which is diagrammatically shown and described in my Alpha Fusion Electrical Energy Valve; **U.S. Patent No. 7,800,285**. This low wattage source consumes only a fraction of what the radioionic energy circuit receives. The negative ions generated by the electronic source draws into the receiver the oppositely charged electropositive atmospheric ions, or highest potential through mutual attraction. The positive ions that are generated by the electronic source draw into the receiver the oppositely charged planetary ions in its soil, or lowest potential through mutual attraction. The quantity of energy received depends on the potential difference of the electronic source. In the working device the electropositive atmospheric ions corresponds to the excess of electricity, which forms an invisible conductor around the channel of air around the antenna (**ANT**). Electrical power or electromagnetic energy is generated when the two electricities, electropositive and electronegative ions are combined in a type of mixing chamber, Perreault Plasma Valve (**PPV1**). It has been known for a long time that the atmosphere always contains ions, which is electricity in its fluid state. When the weather is good the atmosphere usually holds electropositive ions and the soil through induction holds an electronegative charge of ions. It is also known that the amount of stored ions is greater at higher elevations.

It is important that it is understood that a radioionic valve is a cold cathode tube, which utilizes a plasma field to regulate voltage, and to rectify high voltage. It utilizes a **thermoelectric cathode to anode couple**, which generates a multiplication of ions at the surface of the cathode. The radioionic valve functions on a form of ionic action that liberates more ions from the surface of its cathode, in place of the common electronic liberation that occurs in conventional radio tubes. A unique type of ionic liberation is accomplished when thermoelectric elements are bombarded with ionized particles. This is called ion multiplication.

A very small area cathode and large area anode is used in the construction of radioionic valves. A radioionic valve suppresses any arc (voltage) discharge but allows the ions to flow through it. The correct voltage polarity must be observed or a radioionic valve will arc itself out until its thin corona wire breaks and shorts to the cylinder anode. Without the use of the Perreault Plasma Valve (**PPV1**), continuous oscillations cannot be obtained. Instead, you get spikes that are spaced far apart. Also, a lot more current and energy is taken from the high voltage module (**HVM**) module, whereas with the radioionic valve, only a small amount of current is required to power the high voltage module (**HVM**).

The radioionic valve works due to a unique effect that occurs between the inter electrode spacing of the thermoelectric elements. It is here where the positive and negative ions coming from the antenna (**ANT**) and the ground (**G1**) neutralize each other, generating heat radiation which produces a desired **thermoelectric effect**. The reaction generates of an appreciable amount secondary ions. This isn't perpetual motion... the atmospheric ions receive energy from the ultraviolet radiation which the Sun generates.

What isn't disclosed in this patent is the fact that it is an atomic battery, where its generated high ionic potential was being used to draw planetary ions into the receiver circuitry. It is an *ion pump* because it pumps ions through the radioionic energy receiver. The atomic ion valve is now replaced with the high voltage module (**HVM**)**.**

The radioionic valve is unique in that it attracts airborne ions to itself. This omission was done purposely to avoid having a possible secrecy gag order slapped on it. The required high ionic potential is now being generated with an electronic source that replaces the use of radioactivity. The use of radioactivity was a major block to putting the radioionic energy receiver into public use.

My radioionic valve discoveries possess unusual merit. A properly constructed, tuned circuit is able to collect and convert planetary ions into useful electrical power. The technology provides a highly efficient, relatively low-cost, high power to weight ratio power supply. I have spent several years of research using my own personal funds on this ground breaking energy technology. Just as solar cells react to visible light, or let us say wave lengths, within a certain range, is it too difficult to comprehend how electromagnetic radiation is generated when ionized particles impinge upon the thermoelectric cathode to anode couple, in this unique plasma valve? I declare that it is heart of a radioionic energy receiver, which allows it to convert and tune into the plentiful supply of planetary ions, generating useful electrical power.

The high voltage module (**HVM**), and the tank circuit (capacitor **C2** and inductor **L1**) can be compared to a gasoline pump in an automotive vehicle. In the automotive vehicle gasoline is pumped to its combustion engine, where it is transformed into mechanical power. In the radioionic power generator ions (fuel source) are pumped to the Perreault Plasma Valve (**PPV1**) where they are transformed into electrical power. The fuel pump in an automotive vehicle pumps gasoline (fuel source) to its combustion engine. The pump isn't the source of power. It merely feeds the combustion engine with gasoline and air where they react chemically. The resulting violent reaction generates intense heat which is converted into mechanical power. In the radioionic energy generator the tank circuit (capacitor **C2** and inductor **L1**) pumps positively and negatively charged ions into the Perreault Plasma Valve (**PPV1**) where they are violently neutralized generating electromagnetic energy which is converted into useful electricity to provide power to electrical load (**L**).

The tank circuit capacitor (**C2**) and inductor (**L1**) is tuned with capacitor (**C2**) to synchronize with the Perreault Plasma Valve (**PPV1**) pulsation rate. This maximizes circuit efficiency.

The Ultra Capacitor bank (**U1–U6**) when fully discharged must be primed with an external **13** to **16** volt direct current energy source. Once the circuit is kick started into oscillation the priming battery is no longer required.

On/off switch (**SW1**) is closed to supply power to the high voltage multiplier (**HVM**). A small amount of power from the Ultra Capacitor bank (**U1–U6**) is used to provide power to the high voltage module (**HVM**). The high voltage module (**HVM**) attracts and directs planetary ions into the radioionic energy receiver, through the antenna (**ANT**).

Summary

To capture positively charged atmospheric ions an opposite negative polarity must be applied to one of the plates of an electrical capacitor, the positively charged end being connected to an antenna (**ANT**). The stored electrostatic potential which is stored is transformed into a more suitable lower electric potential, because our electrical appliances aren't designed to function on raw electrostatic energy. They require electromagnetic energy to work for us. At the onset of the radio era semiconducting crystal materials, called detectors, were used to convert oscillating, high frequency, electromagnetic energy (radio waves), into a current that flowed only in one direction. This was done because a sound reproducer (speaker) only responds to an electrical current which flows in one direction.

Radio crystals were the subject of an intense search to find a crystal that would provide the best result in converting alternating, high frequency, radio waves into a direct flow of current. Many thousands of radio amateurs tested numerous materials in different circuits and configurations. It was found that a single of "steel galena" offered the best results over all other crystals, a fact that holds true to this day. No means were known to convert raw electrostatic, "static" energy, into electromagnetic energy (electricity).

On November 5th, 1901 Nikola Tesla was granted patents; U.S. Patent No. 685,957 and U.S. Patent No. 685,958. These patents describe charging a high voltage capacitor with ions he obtained from the air. He is the first person known to have harnessed planetary ions. His results demonstrated the basic principle to capture atmospheric ions and then converting them into a small electromotive power.

Hermann Plauson was granted U.S. Patent No. 1,540,998 on June 9th 1925, which expands on Tesla's ground breaking discovery. Plauson showed that he could obtain several kilowatts of useful electrical power. Plauson's system requires sending balloons to high altitudes, which carry an ion collecting antenna.

My method to obtain useful electrical power from atmospheric ions further expands on Tesla and Plauson's methods they described in their patents. I accomplish this with the aid of an electronically generated high voltage source, improved ion collection antenna, and ion discharge components (plasma valves).

PATENTS

US Patent 7,800,286, Alpha Fusion Electrical Energy Valve, Bruce A. Perreault, Sept. 21, 2010



(12) **United States Patent**
Perreault

(10) **Patent No: US 7,800,286, B2**
(45) **Date of Patent: Sep. 21, 2010**

(54) **ALPHA FUSION ELECTRICAL ENERGY VALVE**

(76) Inventor: **Bruce Alan Perreault,** 1072 NH Route 118, Dorcester, NH (US) 03266-6409

(*) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 758 days.

(21) Appl. No. **11/744,769**

(22) Filed: **May 4, 2007**

Prior Publication Data

(65) US 2008/0272680 A1 Nov. 6, 2008

(51) **Int. C1**
HOIJ 17/32 (2006.01)
G2IH 1/00 (2006.01)

(52) **U.S. C1** **313/54**; 313/310; 310/305

Field of Classification Search .... None
See application file for complete search history.

(56) **References Cited**

U.S. PATENT DOCUMENTS

2,926,268	A *	2/1960	Ralph	313/54
2,958,798	A *	11/1960	Anton	313/54

* cited by examiner

Primary Examiner — Ashok Patel

(57) **ABSTRACT**

Alpha particles are directed and focused onto a delta-ray cathode target, where an alpha fusion reaction is generated. Delta radiation or high-energy secondary electrons are generated from the said alpha reaction. The cathode also becomes thermally active generating thermionic electrons. The electrons flow in the direction of an anode that absorbs their energy, generating electrical current in one direction, known in the electrical field as direct current.

1 Claim, 2 Drawing Sheet



FIG. 1


7
8
9
Voltage Step Up Converter
Alpha-fusion Valve
High Voltage Capacitors
Voltage Step Down Conveter
Low Voltage Capacitors
Inverter
Electrical Loads
10
11
12
13

FIG. 2

ALPHA FUSION ELECTRICAL ENERGY VALVE

FIELD OF INVENTION

This invention in general is related to atomic cells and nuclear batteries.

BACKGROUND OF THE INVENTION

Prior art atomic cells and nuclear batteries are limited because they generate low currents. Another drawback is that expensive radioisotopes are obtained from a nuclear reactor in their construction.

The present invention overcomes the aforementioned limitations by utilizing an alpha fusion reaction and radon emissive material. The alpha fusion reaction economically generates high power densities. The present invention provides a unique concept that offers improved performance over prior art direct nuclear conversion systems. The new and novel invention that will be described utilizes an alpha fusion reaction that generates practical and useful electrical current.

Devices that convert ionizing energy to electrical current have been used in prior art, but with poor results.

Atomic cells generate electric currents by utilizing charged particles that are ejected from radioactive substances. The Direct Conversion of Energy was published by the GPO in 1964. On pages 28-29 William R. Corliss discusses the direct use of charged particles that are ejected from radioisotopes. He states that high velocity beta particles ejected from $_{38}\mathrm{Sr}^{90}$ generates a flow of electrical current.

The negative charges on the particles become neutralized when they strike a metallic cylinder. The neutralized particles find their way back to the $_{38}\mathrm{Sr}^{90}$ becoming again ionized. This cycle repeats itself so as long as the $_{38}\mathrm{Sr}^{90}$ remains radioactive.

U.S. Pat. No. 2,926,268 describes a self-powered electron tube that generates secondary electrons when high-energy radiation, particularly from beta particles strike a semi-conductive material.

The power generated by the above two sited examples generate high-voltage but produce extremely low amperage. There are numerous patents issued world wide relating to the direct conversion of charged atomic particles that generates electrical current but all produce low power densities in the millionth of a watt range.

Despite the prior art that exists in this technology, it is believed that there has not previously existed a small, compact electrical device capable of generating a high power output. It is the object of this inventive to provide a method embodying a new and novel device to furnish an efficient and economical source of electrical power. The present invention resolves limitations of the prior art.

The primary object of the present invention is to provide a method that directly utilizes charged particles to produce electrical current, and a new and novel device for utilizing an alpha-fusion nuclear reaction to generate the charged particles.

SUMMARY OF THE INVENTION

The present invention relates to a method that generates electrons which can be converted to electrical energy and more particularly, to electrical power generation through the fusion of alpha particles with carefully chosen target elements, compounds, or alloys.

The present invention may serve as a source of electrical current that is consistent a full 24 hours per day which is safe and non-polluting.

The present invention is an original approach to the generation of electrical current, which relies upon an alpha fusion reaction. It is the main object of the present invention to provide a method and device for generating electrical energy that result from the reaction of alpha particles with specific materials.

It is generally accepted that helium gas will not form compounds in any chemical combination. This gas generally is believed to be chemically inert. What is not readily realized is that helium will react with a few substances when sufficiently excited. It is a well-established fact; helium is a gas that accompanies all radioactive minerals in an excited state. The name for a high-energy helium atom is called an “alpha particle” in the scientific literature. Until now, its role in nuclear transformations has not been fully realized. The quantity of energy that is released under certain conditions is considerable. This conclusion was reached by the early scientific community because the small amount of ejected particles coming from radioactive matter possesses an enormous velocity, carrying with them enormous amounts of energy. The alpha particle reaction is a liberator of an enormous reserve of stored atomic energy.

An example of an alpha fusion reaction can be demonstrated by depositing radon gas onto a beryllium wire. The resulting reaction was used to generate neutrons in the early days of atomic energy to initiate a fission reaction using fissile $_{92}\mathrm{U}^{235}$. The reaction is expressed in the following equations;

$$_{4}\mathrm{Be}^{9}+{_{2}\mathrm{He}^{4}}\text{ (high energy alpha particle)}\rightarrow{_{6}\mathrm{C}^{12}}\,{_{0}n^{1}}\text{ (fast neutron)}$$

$$_{4}\mathrm{Be}^{9}+{_{0}n^{1}}\text{ (fast neutron)}\rightarrow{_{4}\mathrm{Be}^{8}}+2{_{0}n^{1}}$$

$$_{4}\mathrm{Be}^{8}\rightarrow 2{_{2}\mathrm{He}^{4}}\text{ (high energy alpha particles)}$$

In these equations, beryllium reacts with an excited alpha particle generating a fusion reaction with neutrons as its by-product. Enrico Fermi describes this reaction in his U.S. Pat. No. 2,206,634 Process for the Production of Radioactive Substances. The atoms are not fragmented in the above expressed reaction as is the case when a fission reaction is created. A fusion reaction can produce non-radioactive stable by-products, along with a supply of useful electrons, unlike a fission reaction that creates a number of radioactive deadly waste products.

In the present invention a germanium plated, negatively charged corona cathode wire or thin rod, used in conjunction with a palladium or graphite positively charged anode concentric cylinder, can be utilized in its construction. Other materials can be used and this will not depart from the spirit of the present invention. Germanium used as a target material is a good choice because $_{32}\mathrm{Ge}^{72}$ will react with alpha particles generating stable $_{34}\mathrm{Se}^{77}$ and high-energy electrons within the process , in which:

$$_{32}\mathrm{Ge}^{72}+{_{2}\mathrm{He}^{4}}\text{ (high energy alpha particle)}\rightarrow{_{34}\mathrm{Se}^{75}}+{_{0}n^{1}}$$

$$_{34}\mathrm{Se}^{75}\ (e^{-}\text{ capture})\rightarrow{_{33}\mathrm{As}^{75}}\text{ stable}$$

$$_{32}\mathrm{Ge}^{76}+{_{0}n^{1}}\rightarrow{_{32}\mathrm{Ge}^{77}}$$

$$_{32}\mathrm{Ge}^{77}\rightarrow{_{33}\mathrm{As}^{77}}+\text{beta (high energy electron)}$$

$$_{33}\mathrm{As}^{72}\rightarrow{_{34}\mathrm{Se}^{77}}\text{ stable}+\text{beta (high energy electron)}$$

It takes at least 6.06 MeV of energy to generate a $_{32}\mathrm{Ge}^{72}$ alpha fusion reaction. Alpha particles are ejected from Po^{212}

with the energy release of 8.78 MeV, Po^{214} with the energy release 7.68 MeV, Po^{216} with the energy release of 6.78 MeV; these elements can be used to generate $_{32}Ge^{72}$ alpha fusion reactions. Therefore, Po^{218} with the energy release of 6.00 MeV cannot be used to generate a $_{32}Ge^{72}$ alpha fusion reaction. Po^{210} with the energy release of 5.30 MeV cannot be used to generate a $_{32}Ge^{72}$ alpha fusion reaction. These two later radioisotopes cannot be used to generate a $_{32}Ge^{72}$ alpha fusion reaction because their energy levels are below the threshold of 6.06 MeV that is required to initiate the reaction. Rn^{220} with the energy release of 6.29 vMeV of energy and can also be used to generate a $_{32}Ge^{72}$ alpha fusion reaction. It is a good choice because it is the daughter product of Th^{228}, which is abundant on the earth. It is a daughter product of Th^{232}, which is said to be more abundant than lead. The sited equations are a few theoretical examples from whence the present invention obtains its energy. Numerous reactions are possible. Other radioisotopes, than what is sited herein, might also be used and this will not depart from the spirit of the present invention.

A number of electron emitting and electron collecting materials can be used and this will not depart from the spirit of the invention. Other cathode and anode geometries may also be used and this will not depart from the spirit of the invention. However, the target material or cathode must be a delta-ray emitter. In the scope of the present invention, "a delta-ray is characterized by very fast electrons produced in quantity by alpha particles. Collectively, these electrons are defined as delta radiation when they have sufficient energy to ionize further atoms through subsequent interactions on their own."

In the present invention, a new and novel improvement in the art of the direct conversion of nuclear energy is made apparent. The present invention generates electrons that are the result of atomic reactions that are efficiently converted to electrical current, which is novel in the field. Converted atomic energy within the scope of the present invention is directly available for driving motors, lighting, production of heat, and can be used in electrochemistry, etc...

It is a further object of this invention to provide a device for generating electrical current that results from a self-generating electron source that is simple in construction and compact.

Thus, in accordance with the present invention there is provided a method of generating delta-rays, or secondary electrons through the prescribed fusion reaction. The present invention provides a method and device that gives improved performance over prior art that utilizes the direct conversion of atomic reactions to obtain electrical power.

Other objects and advantages of the present invention will become apparent from the following description of the preferred embodiment of the present invention, with references to the attached drawings, in which:

FIG.**1** is an embodiment in its most basic form illustrating the alpha fusion valve which is unique in the present art of generating electrical power; and

FIG.**2** is a block diagram that illustrates the invention in a useful embodiment. The diagram shows an electronic high voltage, low amperage, high frequency power supply. A means to rectify the output of the high frequency power supply is provided. The output of this power supply is coupled to the invention which activates the alpha fusion valve. The polarized current coming from the output of alpha fusion reaction vessel charges a storage capacitor. The stored charge is then connected to a voltage step-down circuit.

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENTS

The method to generate electrical energy includes a cathode which reacts with alpha particles generating electrically charged particles.

Furthermore, it will be understood that the generated electrical current can be directly converted into a useful voltage and amperage.

The conversion of the electrons that are emitted from said cathode generates useful electrical current that will be made apparent and that the alpha fusion valve is unique in generating electrical power. It will be made apparent in the following descriptions;

Referring now to FIG.**1** of the drawings, the said invention consists of a vessel **1** that is made out of an electrically insulating airtight material, such as glass, ceramic, plastic or the like.

It is preferred that a natural alpha source be used but an artificial alpha source might also be used and this will not depart from the spirit of the present invention.

Vessel **1** includes a corona wire **2**, made out of a delta-ray emissive element, compound, or alloy, such as germanium, silicon, or lead-sulfide, etc. . . . delta-ray emissive substances emit delta-ray electrons when bombarded with alpha particles.

The vessel **1** contains a high work function electron-collecting cylinder **3**, preferably made out of palladium because this metal can absorb a large volume of gas. After a period of time, the alpha particles lose their charge, become helium gas, build up, and the present invention eventually becomes electrically blocked. This is because helium gas is electrically non-conductive. A high work function material that has the ability to absorb gas will delay this process. Other alternative electrical collector materials, such as activated carbon, which has the ability to absorb large volumes of gas, may be used and this will not depart from the spirit of the invention.

Radon gas emissive e radioactive material **4** is placed at the base inside vessel **1**. The radioactive material **4** can be placed in a number of locations within vessel **1** and still not depart from the spirit of the invention. The electron emitter **2** can take the form of a wire, rod, cylinder, disc, plate, etc. . . . The electron collector **3** can also take the form of a wire, rod, cylinder, disc, plate, etc. . . . I do not stake my claim on the form or geometry of the electron emitter or electron collector. I stake my claim on the method used to generate electrical power using an alpha fusion reaction.

In the instant invention a negative charge of one-thousand volts or higher is applied to pin **5**, which is electrically connected to corona wire **2.** Respectively, a positive charge is applied to pin **6** which is electrically connected to a high work function electron collection cylinder **3**. This has the effect of attracting and concentrating radon gas onto the corona wire **2** which becomes an abundant supply of alpha reactive particles. A lower voltage may also be applied across pin **5** and pin **6**. The applied voltage will depend on the parameters of the wattage design of the present invention, which are too numerous to mention.

Electrically conductive pin 5 and pin 6 exit through an airtight seal at the bottom of vessel 1, not shown. There are a number of sealants that are available in the field. The inner cavity of vessel 1 is evacuated of air at a low pressure of about 1/10th of an atmosphere. The amount of air that is evacuated is not critical but care must be taken not to obtain too low of a vacuum because this can result in the generation of undesirable x-ray emission. There are a number of high voltage sources that can be used to apply the required activating potential through pin 5 and pin 6 and this will not depart from the spirit of the present invention. I stake my claim to my new and novel method that directly generates electrical power which results from alpha fusion process and I do not stake my claim to the activating external voltage source thereof.

The speed in which the present invention will build up power depends on the potential difference that is applied to it and type of radon gas that it contains. The quantity of the alpha particle source determines the amount of amperage that is generated. The target material **2** is also a determining factor of how much current will be generated. When the target material **2** temperature rises, a greater number of electrons are emitted from its surface. The heated cathode 2 increases the odds of alpha particles hitting head on with its atoms, thus, producing a greater number of alpha fusion reactions, which further increases the surface heat boiling off additional thermally generated electrons. The surface area of the cathode **2** and anode **3** is also a determining factor of how much electrical current will be obtained.

The present invention generates a high voltage direct current. The present invention also generates a greater amperage per given density from what has been obtained from any previously known method or device in the prior art.

The instant invention described can be slightly modified to convert high voltage, high frequency, and radio frequency currents into a direct current. This feature is accomplished by adding an electrically conductive substance such as mercury, not shown, into the electrically non-conducting vessel **1**. Any number of electrically conductive substances that will form a vapor or gas when heated can be used and this will not depart from the spirit of the invention. Said modification can also be utilized without the use of the radioactive substance **4**, if the input source has enough energy to excite the vapor or gas into its electrically conductive state. The present modifications of the primary invention is more efficient than the prior art in converting alternating or oscillating currents because there is less electrical resistance in the conversion process. Therefore, energy can be more efficiently received and converted into a direct current.

Referring now to FIG.**2** of the drawings:

The present invention is named alpha fusion valve 8 in the block diagram that follows:

The block diagram shown illustrates an example of how an alpha fusion valve **8** can be utilized in a practical application. Many differing types of systems are made possible using the present invention and will not depart from the spirit of the invention.

The alpha fusion valve **8** must be energized by an external potential difference to function if it is initially inactive or is allowed to become inactive after it has been producing power, not shown. This can be accomplished by applying a high voltage charge obtained from an electronic power supply **7**. The reactions will build up within the alpha fusion valve **8** to the point where the surface of its internal electron emitter is totally bathed with radon gas. The alpha fusion valve **8** has to be primed with a potential difference to begin generating electrical power. The alpha fusion valve **8** produces a high voltage direct current. The output of the alpha fusion valve **8** can be used to charge a high voltage capacitance **9**. The high voltage is then lowered to twelve volts through a step-down converter **10**. The twelve volts then charges low voltage capacitance **11** which can be set of parallel-connected twelve-volt storage batteries. A set of parallel-connected high farad capacitors could also be used. The stored energy in capacitance **11** can be used to provide power to electrical loads that require a twelve-volt direct current or it can provide a twelve-volt power supply to an inverter **12**. The output of the inverter **12** can be designed by methods known in the art to provide a voltage and frequency that is required by specific electrical loads **13**. It is preferable that an electronic voltage source be used to keep the alpha fusion valve **8** in a constant energized state, which can be alternating or non-alternating. Numerous electronic circuit designs may be used to supply the potential difference required to energize the alpha fusion valve **8**. Such electronic circuits are known in the field and are not what I stake my claim to. Alternatively, a strong enough source of alpha, beta, gamma radiation or a combination thereof may also be used to energize the alpha fusion valve **8**.

A simple earth ground and antenna raised to a suitable height can b e used to take advantage of the potential difference that exists between the planet and its atmosphere, although this is not always practical. Charging capacitance **9** with this method is unpredictable and slow. Any suitable circuit may be used to supply the required potential difference to energize the alpha fusion valve **8** and this will not depart from the spirit of the invention.

Having thus described the invention, what is claimed is:

1. An electrical energy generator for generating electric energy comprising:

a vessel constructed of an airtight, electrically insulating material, said vessel including a base and defining a cavity, the vessel further including:

(a) a negatively charged corona wire made of a low work function delta-ray emissive material which functions as an electron emitter, and including germanium, silicon or lead-sulfide for emitting delta-ray electrons when bombards with high energy alpha particles;

(b) a high work function electron collector having a cylindrical shape and made of palladium (Pd) or an activated carbon and located coaxially inside the vessel;

(c) a radon gas that decays to a radio isotope having an energy level greater that 6.06 MeV, which expands and thereby fills the cavity of the vessel; and

(d) first and second electrically conductive pins being attached to the base through airtight seal and facing away from the cavity, the first pin being electrically connected to the corona wire and the second pin being electrically connected to the high work function electron collector,

Wherein the corona wire is initially charged through an external negative charge applied at the first pin, and the high work function electron collector is initially charged through an external positive charge applied at the second pin, and

Wherein, after charging of the corona wire and the high work function electron collector, the first and second pins act as cathode and anode respectively of the electrical energy generator.

* * * * *

US Patent 2,813,242, Powering Electrical Devices with Energy Abstracted from the Atmosphere, Lloyd R. Crump, November 12, 1957

Nov. 12, 1957 L. R. CRUMP 2,813,242

POWERING ELECTRICAL DEVICES WITH ENERGY
ABSTRACTED FROM THE ATMOSPHERE
Filed March 12, 1954


RF POWER
35
36
37
41
46
43
40
42
44
TRANSISTOR OSCILLATOR
52
55
61
64
69
70
HIGH VOLTAGE LEVEL d-c POWER
LOW VOLTAGE LEVEL d-c POWER

FiG. 3


1
2
5
15
16
20
22
21
17
6
23
25
3
7
26
+1 v.
10
31
30
11
27
−2 v.
12

FIG. 1


35
36
37
41
46
43
+DC
45
LOAD
40
42
44
−DC

FIG. 2

INVENTOR
Lloyd R. Crump

BY W.E.Thibodeau + A.W. Dew

ATTORNEYS

2,813,242

POWERING ELECTRICAL DEVICES WITH ENERGY ABSTRACTED FROM THE ATMOSPHERE

Lloyd R. Crump, Silver Spring, Md.

Application March 12, 1954, Serial No. 415,986

1 Claim. (Cl. 321-2)

(Granted under Title 35, U. S. Code (1952), sec. 266)

The invention described herein may be manufactured and used by or for the Government for governmental purposes without payment to me of any royalty thereon. This invention relates to the convenient and economical provision of power for the operation of electronic circuits and devices using transistors, and of other electrical devices having modest power requirements.

A great advantage of transistors, and a major reason for their enthusiastic reception since their introduction a few years ago, is the fact that they will operate satisfactorily with very low supply voltages and currents. One milliwatt or even less is sufficient to power a transistor in many applications. Various batteries have been developed to provide, in a minimum of space, the relatively minute amounts of power needed by transistors.

My invention provides methods and means that permit transistor circuits, and also other low-powered electrical devices, to be economically and conveniently operated without any batteries whatever, and indeed without any power supply whatever as power supplies are ordinarily conceived.

The invention centers around my discovery that it is practicable to construct operative transistor circuits that are able to abstract from the atmosphere sufficient electromagnetic energy to provide all necessary supply voltages and currents for their own operation. Circuits and devices powered according to my invention will operate indefinitely without any local power source whatever.

I have successfully constructed and demonstrated such circuits. For example, I have constructed a batteryless transistor radio receiver on which I have listened to either nearby or distant broadcast stations as desired, using either headphones or a loudspeaker; this receiver has been powered entirely by electromagnetic energy abstracted from the atmosphere.

From the successful operation of this receiver, and from other experimental work, it becomes clear that, by the methods and means of the invention, a great variety of practical and useful transistor circuits can be powered entirely by energy abstracted from the atmosphere.

Furthermore, as will become apparent below, my invention is applicable to the powering of other electrical devices requiring relatively small amounts of power.

An object of the present invention is to provide methods and means for powering transistor circuits entirely from radiofrequency energy abstracted from the atmosphere.

Another object is to provide methods and means for powering remote radio receivers, low-powered radio transmitters, and other low-powered electrical devices, with energy received by radio from a master station, so that no local power supplies are needed by the devices and so that the powering or non-powering of the remote device is under the control of the master station.

A further object is to provide methods and means for powering transistor circuits and ether low-powered electrical devices with radiofrequency energy received from one or more remote radio transmitters.

Other objects, aspects, uses, and advantages of the invention will become apparent from the following description and from the drawing:

Figure 1 is a schematic diagram of a transistor radio receiver in which all necessary power is supplied by energy abstracted from the atmosphere in accordance with the invention.

Figure 2 is a schematic diagram showing a general application of the invention to provide direct-current power 10 to a load.

Figure 3 is a schematic diagram of a system for obtaining a high energy D.-C. source at a high voltage level using energy abstracted from the atmosphere.

Referring to Figure **1**, a receiving antenna **1** is connected to antenna coupling coils **2** and **3**, the other ends of which are connected to ground. A parallel resonant circuit consisting of coil 5 and capacitor **6** is coupled to coil **2**. A second parallel resonant circuit consisting of coil **7** and capacitor **10** is coupled to coil **3**. A third parallel resonant circuit consisting of coil **11** and capacitor **12** is also coupled to coil **3**.

Coil **5** and capacitor **6** are tuned to the frequency of a radio transmitter from which it is desired to receive information–for instance, an amplitude-modulated standard broadcast station. The signal received from this transmitter need not be strong. The signal is detected by diode **15** to obtain an audio-frequency information signal. This audio signal is coupled through a capacitor **16** and is amplified by a circuit that includes a transistor **17** having a base **20**, an emitter **21**, and a collector **22**. The amplified audio output of the transistor is coupled through an audio transformer **23** to an electroacoustical transducer, preferably a permanent-magnet dynamic loudspeaker **25** as shown.

The novelty of the invention lies largely in the method and means by which the necessary direct-current power is supplied to the emitter and collector circuits of transistor **17**. This method and means will now be described.

Coil **7** and capacitor **10**, and also coil **11** and capacitor **12**, are tuned to receive radio signals of relatively high strength. It does not matter whether these signals contain information. These power signals are rectified by diodes **26** and **27** to provide direct-current power that is filtered by capacitors **30** and **31**. The D.-C. power thus obtained is utilized to power the transistor **17**.

In the circuit shown, two tuned circuits (coil **7** and capacitor **10**, and coil **11** and capacitor **12**) are tuned to power signals and the D.-C. voltages obtained from each are connected in series. The tuned power circuits may be tuned to the same or different power signals. Under certain circumstances it may be desirable to use more than two tuned power circuits and to tune them to more than two power signals; in this way power can be obtained from several signals and combined. On the other hand, if a strong power signal is available, a single tuned power circuit may suffice to give the needed D.-C. power.

Even weak information signals can be received successfully. A plurality of transistor amplifier stages can be used if desired, or other circuit Is such as superheterordyne circuits can be used. It is merely necessary that a sufficiently strong power signal or signals be available to provide the small amount of D.-C. needed to power the transistors.

If the information signal happens to be strong, it can be used as the power signal; all of the tuned circuits (coil **5** and capacitor **6**, coil **7** and capacitor **10**, coil **11** and capacitor **12**) are tuned to the information signal.

Engineers who have observed my invention in operation have been surprised at the unexpectedly good results obtained, even with readily available power signals of quite moderate strength. For instance, sufficient power for satisfactory operation of a loudspeaker at low volumes is readily obtained from a 5-kilowatt standard broadcast station 5 miles away, using only an indoor antenna to pick up the power signal as well as information signals. In typical operation under these conditions a D.-C. voltage of about 2.5 to 3 volts is obtained between the emitter and the collector, at a current of about 250 microamperes; D.-C. power input to the transistor is thus of the order D.-C. power input to the transistor is thus of the order of 0.5 to 1 milliwatt. So far as I am aware, no one has ever before discovered and demonstrated the practicability of this method of powering a radio receiver.

Because existing broadcast stations within a radius of a number of miles provide adequate power signals, the invention is readily practicable with existing power signals in almost any location in or near any city in the United States.

Although I have described a transistor radio receiver powered by my invention, it will be readily apparent that the invention is applicable to the powering of any transistor circuit using one or a number of transistors, and to the powering of other devices requiring relatively small amounts of power. For instance, sensitive electromechanical, electrochemical, or electrothermal devices can be operated by the method of the invention.

Referring to Figure 2, which shows a more general embodiment of my invention, an antenna **35** picks up radiofrequency energy from the atmosphere. This energy flows through coil **36**, which is coupled to a tuned circuit consisting of coil **37** and capacitor **40**. The radiofrequency voltage across capacitor **40** is rectified by diode **41** and filtered by a low-pass filter **46** consisting of capacitors **42** and **44** and choke coil **43**. The resulting D.-C. voltage is applied to a load **45**.

In the practice of my invention, larger amounts of power can be obtained for short periods of time by storing received energy in a suitable energy storage device. Stored energy may then be withdrawn at intervals at a more rapid rate than that at which it was received and put into the storage device. In this way the invention can be used to provide short pulses of relatively very high electrical energy. This result can be readily obtained by charging a relatively large capacitor with direct current and then discharging the capacitor rapidly into a load when desired. This rapid discharge can be initiated automatically when the voltage across the capacitor reaches a certain level, or it can be initiated when a transistor radio receiver receives a certain information signal.

Higher voltages can be obtained with the invention by means of well known devices for raising D.-C. voltages as shown in Figure 3. The D.-C. voltage output from the capacitor **44** can be used to power a low frequency transister oscillator **52** whose A.-C. output is raised to a higher voltage level by the transformer 55. This relatively high A.-C. voltage can then be rectified by a diode **61** and fed to a capacitor **64** to provide a high energy D.-C. source at a relatively high voltage level at the terminals **69** and **70**. If desired, energy can now be withdrawn from the capacitor **64** at intervals in short pulses of high energy at a high voltage level. Pulsed radio transmission is one of the possible uses for this form of the invention. Other uses would be to provide a single relatively powerful pulse needed to actuate an electrothermal or electromechanical device.

As has been indicated above, in many locations and particularly anywhere in or near most American cities, power signals normally present in the atmosphere are readily available for the easy and convenient practice of the invention. However, the invention also has important applications in systems in which the necessary power signal is generated and transmitted specifically for the operation of the particular system. Such systems can, for example, comprise a master station transmitting all the power that is needed for hundreds or thousands of fixed or mobile transistor receivers or other remote devices over a range of many miles. This eliminates the need for hundreds or thousands, as the case may be, of local power supplies. At the same time, such a system has the advantage that all of the remote devices can be simultaneously activated or deactivated at the will of the master station, simply by starting or stopping the transmission of the power signal. In such systems it will often be advantageous to use power signals of frequencies sufficiently high to permit the use of resonant receiving antennas of small physical dimensions for signal pickup at the remote devices. In addition to the power signal, the master station may transmit an information signal on the same or a different carrier.

Certain types of devices powered entirely by received radio waves are of course well known. The well-known "crystal set" of the early days of radio, which used a diode rectifier to demodulate an amplitude-modulated radiofrequency signal, is an outstanding example of such a device. My invention is readily distinguishable from such prior devices, however. In typical prior devices a modulated radiofrequency signal is applied to a diode to obtain unidirectional half-wave pulses whose amplitudes vary with modulation. These pulses are integrated by means of a capacitor to obtain a unidirectional signal the amplitude of which follows the audiofrequency modulation envelope. If the radiofrequency signal is received with sufficient strength the audio signal may have sufficient power to operate headphones or similar utilization device without power amplification; but the signal is utilized for its information content, rather than to supply non-information-containing power.

My invention, on the other hand, entails the utilization of received radiofrequency energy to supply power to at least one pair of circuit points (across capacitor **31** in Fig. 1, for example), such circuit points requiring power solely for its power content and not for any information or modulation it may contain. In other words, my invention entails the utilization of radiofrequency energy to supply power that would otherwise have to be supplied by batteries, generator, or other local power source.

It will be apparent that the embodiments shown are only exemplary and that various modifications can be made in construction and arrangement within the scope of the invention as defined in the appended claim.

I claim:

An electrical device for obtaining a high energy D.-C. source at a high voltage level using energy abstracted from the atmosphere, said device comprising in combination: resonant means for receiving radio waves, first rectifier means for converting said radio waves into first direct current energy, first capacitor means for storing said first direct current energy, an oscillator powered by said direct current energy, said oscillator producing an A.-C. output, transformer means for raising said A.-C. output to an increased voltage level, second rectifier means for converting the A.-C. output of increased voltage level from said transformer into second direct current energy, and second capacitor means for storing said second direct current.

References Cited in the file of this patent

UNITED STATES PATENTS

1,540,998	Plauson	June 9, 1925
2,056,824	Cawley	Oct. 6, 1936
2,553,734	Adler	May 22, 1951
2,569,687	Pan	Oct. 2, 1951
2,647,957	Mallinckrodt	Aug. 4, 1953

OTHER REFERENCES

Turner: "A crystal receiver with transistor amplifier," Radio and Television News, January 1950.

GB Patent 231,427, Improvements in and relating to Improved Means for Utilizing Electromagnetic Electricity for Transmitting and Generating Power, Serafino Orlando, April 2, 1925

PATENT SPECIFICATION
Application Date: Jan. 3, 1924. No. 163/24
231,247
Complete Left: Sept. 23, 1924.
Complete Accepted: April 2, 1925

PROVISIONAL SPECIFICATION

Improvements in and relating to Improved Means for Utilizing Electromagnetic Radiation and Atmospheric Electricity for Transmitting and Generating Power.

I, Serafino Orlando, O.D.C., subject of the Kingdom of great Britain, of Birchircara, Malta, do hereby declare the nature of this invention to be as follows:-

We were accustomed to combine the idea of electricity with that of wire conductors, and everybody knew that for the transmission of electrical energy it was necessary to make an exclusive use of metallic wires. But at the present time it is no longer thought necessary to use these means for the transmission of electrical energy, so much so that both electrostatic and electromagnetic inductions are actions which are transmitted through the air, and although their fields of action are very limited, electricity can be transmitted not only through wires, but also through the ether, which is to be found in the air, and, as proof of this, we may adduce the phenomenon of wireless telegraphy. It is known that this phenomenon is due to electrical current most rapidly alternated produced by apparatuses in which oscillatory electrical discharges are produced.

These oscillatory discharges, which are the reciprocating motions of electricity, are not only limited to the system of the apparatuses in which they are produced, but, as the electrical spark causing them explodes in the air, they are a phenomenon which occurs in the either met with in the air, consequently, wherever the spark occurs, it produces in the either periodical motions which get spread spherically all round in all directions so far s they are not obstructed by some obstacle, and, therefore, it is inferred that the electrical waves are nothing but an electromotive force transmitted from one point to another by means of the ether. Above all, it is clear that the action of these oscillations at a distance is bound to be greater, the greater the energy employed in this oscillatory motion happens to be.

We know that the quantity of electrical energy which can be communicated to a conductor or to a system of conductors depends on its capacity. The smaller the conductor is, the less is its capacity, and, therefore, the smaller in the energy of the oscillations which are produced in it when, after having been charged, it is discharged through the medium of the spark.

In fact the period of these electrical oscillations increases proportionately to the square root of the capacity of the oscillatory system.

Consequently the above consideration warns us to use a system of conductors of great capacity in order to obtain extremely long waves, for the latter set in motion a quantity of energy greatly superior to that induced by short waves.

Now as these waves are propagated spherically al round in space in a directions, however much one tries to render the apparatuses powerful, it always remains true that the electrical energy transmitted in space is an electro-motive force dispersed in all directions, in a similar way to the luminous waves issuing from a lighted splinter, which spread through the ether in all directions, and in the same way as these, their intensity decreases as the distance increases, and, however great the energy sent forth by the generating station of wireless telegraphy to the receiving station may be, only a very slight fraction of the transmitted energy reaches it; first on account of the loss of intensity due to the distance from the source, and, secondly, because the electrical energy employed in these apparatuses is due to a pure phenomenon of resonances.

The same thing happens here as when a tuning fork, tuned to A (1a) pitch, is sounded in the vicinity of a pianoforte note having the same A sound, when the latter in its turn is caused to vibrate and emit sound.

Nobody, of course, refuses to recognize the great difference existing between the intensity of sound emitted by the tuning fork and that felt by vibration.

Therefore in order to succeed in solving the problem of wireless traction, setting aside the apparatuses in which the phenomenon of resonance are produced, it is necessary to have recourse to other contrivances, having the property of intercepting, or of better absorbing, in great quantities, the electrical energy dispersed in space, causing it to flow in a desired direction, or to flow towards a required point, which amounts to saying that it is necessary to construct an invisible conductor in space which may serve as a path to these waves, and to concentrate them at any point that may be required. The possibility of constructing such an apparatus results from the scientific proofs I am about to submit whilst unfolding my idea.

Rontgen rays, among other marvellous properties, possess one which is of great physical interest, that is, these rays discharge very rapidly the electrified bodies they meet with.

In order to prove in a simple way this fact, it will suffice to use a gold-leaf electroscope whose leaves are electrified with an ebonite rod, or with rubbed glass. As soon as the Rontgen rays are produced in its vicinity, the gold leaves at first ready to diverge and retain this position, now instantaneously fall down which is a sure proof that the air loses its insulation properties and becomes a conductor.

The fact that the air, traversed by these rays becomes a conductor, says Professor Gritetz, is explained by admitting that owing to them, the molecules of air split up, giving origin to very small particles, some of which are charge positively, and others negatively. It is therefore asserts that the air is ionized by these rays; the free ions in the vicinity of a charged body can become united to this electricity, and, therefore, can discharge it, and, consequently, this ionized air possesses a certain conductivity in such a way that if from any cause there is a difference of potential existing between two points in the air, an electric current is bound to pass, same as happens in a saline solution. Another property of great importance was observed when it was rendered possible to conduct to the outer side of a Crookes' tube cathodal rays, the negative electrons, which in electrolytic phenomena are inseparable from matter, are freed from the latter and subsist free; from which reason, owing to the high tension obtained in Crookes' tubes, they depart from the cathode with a velocity of about 1/3 that of light, and they act as if they carried away with them negative electricity, and, consequently, every body met with by the cathodal rays becomes electrified negatively.

The apparatus proposed by me to intercept, or rather absorb in great quantities, the electric waves and to profit by it in its application to electrical power generation, will consist of an assemblage of fine copper wires, in several layers, one inside the other, laid out in the form of a flat rhombus, of which one diagonal is remarkably greater than the other. The wires of the several layers, are relatively staggered. The two extremities of all these wires are placed in communication with the central main wire the latter to have such a section as to allow of a resistance which may correspond exactly to the one offered by all the wires, taken as a whole. Underneath in the centre of this apparatus, is placed a Crookes' tube capable of producing rays in great quantities. The position of this tube is determined so as to allow of the copper wires being traversed by the rays throughout all their extension. The superficies of the apparatus will be proportioned to the extent to which the rays are projected, which extension will depend on the form and size of the platinum cone existing at the centre of the tube.

The above-mentioned tube if of Thomson model, would be highly suited to the predetermined object; here the negative charge is transmitted to two diametrically opposed points, and, in the inner part, the cathodes are represented by two specular and concave aluminium, conductors, whilst in the centre of the tube is to be found the anode formed by the platinum cone receiving the positive charge.

When the current is discharging towards the tube, the cathodal rays strike the platinum cone at their focus respectively on each side, and thus large quantities of rays are projected in straight lines perpendicularly to the superficies of the tube.

The phenomena to be verified in this apparatus are the following:-

The rays emanating from the tube, when it is placed in the above-mentioned position, whilst they strike the surrounding air rendering it ionized and, consequently, conductive, must at the same time traverse the copper wires impregnating them with negative electricity. The extent of the layer of ionized air and the intensity of the negative charge will undoubtedly depend on the greater or lesser power of the apparatus in which the Rontgen and cathodal rays are generated.

The electric waves sent continually by the generating station with the rapidity of light in all directions, must, on their way through space, meet with the obstacle, so to say, wherever it may be, formed by the conductivity of the ionized air through the action of the Rontgen rays projected by the tube, and attracted and absorbed by this conductivity of the air, they produce in the space struck by the rays a true aerial conductor, which gets charged without interruption with electricity, for, as the air is a non-conductor, only the layer struck by the rays becomes charged with electricity, and the air which surrounds it must retain its insulating properties. With respect to electric waves absorbed by the ionized air, Professor Wimbledon Hill says:

Electric waves suffer the least absorption when travelling through a non-conductor medium like ether. Marconi observed in 1902 that signals that carried 1500 or more miles at night-time, would not carry for about 700 miles in the day. The action of day-light is responsible for the greater absorption; sunlight produces partial ionization of the atmosphere, and renders it conductive."

From what we have said before, it is inferred that the air ionized by the Rontgen rays should absorb electric waves in a greater quantity, as its conductivity is extraordinarily greater than when it is ionized through the action of solar rays. In fact it has been proved above that electrified bodies when discharged in the vicinity of the Rontgen rays, whilst this never happens through the action of solar rays, for if such a thing could occur, as the sun's rays strike all day long the atmosphere, the properties of the static electricity would not have been discovered, because we should never have been able to have a body charged with electricity. The rays projected by the tube, in lines perpendicular to the superficies of the tube, present to our sight the form and size of the invisible conductor produced by the ionization of the air which attracts and absorbs continually the electric energy; this electric energy, being bound to follow the course formed in the air by the projection of the rays, must necessarily come into contact with the wires charged negatively through the action of the rays themselves, and here then takes place the meeting of the two conductors charged with two kinds of electricity, for it is laid down as a law that two different conductors have always different potentials, namely a positive and a negative potential. The difference of potential causes the negative electrons of the ionised air to be urged on towards the positive conductor, whilst the positive ions are attracted by the negative conductor. In the contact with the two conductors they give up their charges, thus originating the electric current.

The magnitude of this current will depend on the greater or lesser ionization of the air, the greater the difference of potential between the two conductors, the quicker the electrons and ions will be displaced, thus communicating for each unit of time greater charges to the two conductors.

In the apparatus, the positive or highest potential corresponding to an excess of electricity ought to be found in the invisible conductor formed by the ionized air, because the potential of a conductor is inferred from the relation between the capacity of the conductor and the quantity of electricity it possesses, and therefore it follows as a consequence that the negative or lower potential corresponding to a deficiency of electricity ought to be found in the bundle of wires.

A difference of potential between two charged conductors has a consequence that when these two conductors are put into communication a flow of electricity is produced through the bodies joining together the two points of different potential, that is, an electric current is produced, or rather, an electromotive force from the higher potential to the lower; therefore, according to this other law, the electricity found in the conducting air, which is at the highest potential, should pass over the metallic conductors of the apparatus, which are at the lower potential.

It has also been said that the current is produced through the wires uniting together the two points at different potentials. In this apparatus, owing to the nature or one of the conductors, such as the ionised air, this joining wire is not required because air by itself, as can very easily understood, supplies this detect, as the electricity which it possesses is in continues contact with the other electricity produced continually in the wire; therefore as electricity flows with greater ease through metallic conductors, than through any other conductor, then the recombining of the two electricities, one of the ionised air, and the other of the wire, cannot occur through the medium of the air, but runs over the bundle of the metallic wires; and generates in these an electric current; the greater the difference of potentials, the greater will be also the flow of electricity from one point to the other. So long as the difference of potentials is maintained always constant, a true electric current is produced in the conductors, as can be experimented with electrostatic machine.

In fact, through the rotation of the machine, to one of the conductors is communicated positive energy, and to the other positive electricity, that is, a difference of potential is constantly maintained between them, whence the two electricities flow continuously in the wire, or in the wires, and an electric current is produced.

In the apparatus the two electricities, namely that of the air and that of the wires, both produced without interruption, through the action of the rays projected by the tube, finding themselves in continual contact the one with the other, the difference of potential is maintained constant, and provokes, as already proved above, the passage of electricity through the wires, or else the electric current.

ATMOSPHERIC ELECTRICITY

In addition besides the electric waves, also atmospheric electricity, for the same reason, ought to take part in the phenomenon, and be absorbed by the apparatus. In fact the atmosphere is in an electric state always and everywhere, so much so that the difference of potential even between localities not very far from one another is sometimes considerable. When it is fine weather, the air is usually electrified positively, and the earth, naturally, by induction, is electrified negatively. The free electricity of the atmosphere is in greater quantity in high regions. It undergoes variations of a relative periodicity during day-time and the seasons.

With regard to what I state, what is asserted by an American scientific journal, "Science and Invention," (May, 1921), is quite to the purpose.

"It is said the Dr. Plauson, a German scientist, has successfully demonstrated that if we send up metal surfaced balloons and tap the electrical energy from the atmosphere at a level of 1000 feet or more, we shall be able to realise an average of 200 h.p. per square metre, an area equivalent to 3.28 square feet. It is even claimed that in his latest experiments, as great a quantity of electrical energy as 400 to 500 h.p. has been realised per square metre. Under normal conditions, the potential gradient, as it is called, of the atmosphere increases with comparative regularity as we rise above the surface of the ground, the atmospheric potential per foot or per metre varies also, as may be well imagined, with the season of the year, and the potential or voltage has been found to average 100 volts per metre (3.28 square feet) in the summer months, while during the cold winter seasons the potential gradient rises to as high as 300 volts per metre..."

The same scientific journal (March, 1922) makes the following remarks:-

"The amount of electrical power that resides in our atmosphere is astounding Herr Plauson found in his experiments that a single balloon sent aloft at a height of 300 yards gave a constant current of 400 volts of 1.8 amperes, or in 24 hours, over 17¼ kilowats! By using two balloons in connexion with a special condenser battery, the power obtained was

81½ kilowats in 24 hours! The actual current delivered was 6.8 amperes at 500 volts..."

Now it is well known that X rays are effective at a distance of almost thirty feet according to a statement by the French Academy of Arts and Sciences with the following words:-

"X rays produce electrons on their passage through the air; these electrons are definite entities, and as they leave atoms, they may traverse matter or pass through the air in a straight path, and by their coming in collision with the atoms of the air; they render it a conductor of electricity. It is true that screens of lead suffice to protect the operators from the evil effects of X rays, but operators are sometimes careless, and then the rays are effective at a distance of almost thirty feet."

Supposing, therefore the air ionised by the rays to be five square metres, such at an altitude of 1000 feet, according to the latest experiments by Dr. Plauson, should effect a force equivalent to 5x200=100 up to 5x500=2500 h.p. Therefore, whenever the apparatus at an altitude of several metres from the ground is capable of absorbing from an area of five square metres as much electricity as is required to realise a force of 1% in comparison to that obtained at an altitude of 1000 feet from the earth, it should give a result of a force from 10 to 25 h.p.

Intensity Of Electric Waves

All physicists, among whom may be included Hertz and Faraday, admit that electric and luminous waves are identical, that is, oscillations of the ether of varying length. The luminous waves acting on sight, have a length varying from 4 to 7½ ten thousandth of a millimetre, according to the various colours, whilst the longer wave of 40.50 ten thousands of millimetres show themselves only for technical properties in apparatuses suited to this object.

Electric waves are much longer, for they measure from several centimetres, to thousands of metres, but the difference between these two kinds of waves is only in length.

Taking this for granted, we may state that electric waves before a very short duration of oscillation appear to us as light; while electric waves of a great duration of oscillation do not manifest themselves to us as light, but owing their effects of induction show themselves as electric waves, If all this be true; (and all consequences therefrom can be verified) it can surely be possible to obtain by means of electric waves the same phenomena as with luminous waves, and the laws ruling the latter can be applied to the former.

And this Hertz proved by experiments.

Now physics teach us that the intensity of light is inversely proportional to the square of the distance form the source, that is to say, it decreases with the square of the distance for the source that is from the distances . . . . 1, 2, 3, the intensity of light is proportional to the numbers . . . . 1, ¼, ¹/₉, *etc.*, and this occurs because light gets spread in all directions over spherical surfaces of a radius increasing with the distance. Spherical surfaces with rays . . . . 1, 2, 3, *etc.* have a magnitude proportional to the numbers . . . . 1, 4, 9, etc., that is spherical surfaces increase with the square of the X rays.

Therefore as the intensity of the light has to be communicated to ether waves whose sperficies increase at the square of the distance, each of the receives a part of the former (that is of light) whose magnitude decreases in the same measure.

Since luminous and electric waves, according to the above adduced proofs, are identical, the enunciated law of the intensity of light may be applied (taking into consideration the multiform variations of the atmosphere) to the intensity of electric waves.

Dated this 3rd day of January 1924.

SERAFINO ORLANDO,
Birchircara, Malta

COMPLETE SPECIFICATION

Improvements in and relating to Improved Means for Utilizing Electromagnetic Radiation and Atmospheric Electricity for Transmitting and Generating Power.

I, Serafino Orlando, of 47, Church Street, Kensigton, W 8, British subject, late of Birchircara, Malta, do hereby declare the nature of this invention and in what manner the same is to be performed, to be particularly described and ascertained in and by the following statement:-

My invention relates to an improved means of absorbing electromagnetic energy from ether. The electromagnetic energy may be of the form of electromagnetic waves radiated from some radio transmitting station or from the electrostatic charge in the atmosphere.

According to my invention I provide an arrangement of metallic conductors, preferably in the form of a network beneath which I introduce a source of X rays and from this source I project the rays upwards through the conductors.

It is known that a beam of X rays causes the air penetrated by such rays to become ionised and consequently conducting for a distance dependent on the strength of the rays.

I am aware that in conjunction with the X ray emitted by the X ray tube are certain other rays called cathodal rays which carry with them negatively charged electrons which cause all bodies they meet to become charge with negative electricity.

According to my invention I find that when electromagnetic waves strike the region of the ionised air enveloping the network of conductors, produced by the X rays projected into the network, the arrangement is found to be equivalent to a conductor of great height, but when the source of ionisation is removed practically no absorption of energy takes place in the conductors.

The function of the ionisation being to increase the small superficial area of metal exposed for the purpose of absorbing electromagnetic energy by rendering the air surrounding the conductors conducive to the passage of electromagnetic energy from a source of X rays or other rays capable of producing ionisation.

In this invention it is found desirable to arrange the size of network to suit the strength of the source of ionisation or conversely to arrange the strength of the source of ionisation to suit the size of network; it being desirable to fill the field of ionisation with conductors up to an intensity of ionisation which may be determined by experiment.

Should it be found desirable, the cathodal ray previously referred to may be prevented from striking the network of conductors by deflecting the by the aid of a magnet.

The invention is illustrated by way of an example in the accompanying drawing in which:-

Fig. (1) shows the network of conductors in plan and elevation.

Fig. (2) shows the electrical circuit.

In carrying my invention into effect according to the apparatus illustrated; the network of conductors shown in Fig. (1) consists of a number of fine copper wires (*a*) communicating with a central conductor (*b*).

In Fig. (2) a source of X rays (*c*) is shown beneath the arrangement of conductors (*a*) the details of which are shown in Fig. (1).

These conductors (*a*) may for convenience be connected to a terminal (*d*) to which apparatus to be actuated may be connected through another terminal (*c*) to earth.

The magnet (*m*) may be introduced for the purpose of deflecting the cathodal rays (*f*) previously referred to.

Having now particularly described and ascertained the nature of my said invention and in what manner the same is to be performed, I declare that what I claim is:-

1. A conductor or network of conductors which has been surrounded by an ionised gas for the purpose of increasing the power of the conductor to receive electromagnetic energy.

2. A conductor or network of conductors which has been surrounded by an ionised gas for the purpose of increasing the power of the conductor to transmit electromagnetic energy.

3. A conductor or network of conductors which has been surrounded by an ionised gas for the purpose of increasing the power of the conductor to absorb electrostatic charges from the atmosphere

4. A system of absorbing electromagnetic energy from the ether substantially as described with reference to the drawings.

Dated 2nd day of March 1925.
SERAFINO ORLANDO

Abingdon Printed for His Majesty's Stationary Office, by Burgess & Son.

231,247 COMPLETE SPECIFICATION

2nd Edition

SHEET 1

[This Drawing is a reproduction of the Original on a reduced scale]


a
b
SECTIONAL ELEVATION
a
a
PLAN

FIG. 1.

2 SHEETS

SHEET 1

SHEET 2

ATION



Charles & Read Ltd. Photo Litho.

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12, Sheets-Sheet 1

Fig. 1.


13
14
7
8
6
5
9
10
11
12

Fig. 2.


14
5
C_1
b_1
a_1
7
9
10
11
12
1
M
2
6
13
15

Fig. 3.


A
0
S
a
a
a
a
8
7
1
M
2
E

Fig. 4.


S
5
1
8
7
M
2
6
E
E_1

Fig. 5.


A
S
5
8
7
7a
9
E
6

Fig. 6



Inventor

Hermann Plauson

by Knight Bros

attorneys

June 9, 1925. **1,540,998**

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12, Sheets-Sheet 2


Fig. 7.
A
S
1
M
2
E
7
7b
E1
8
E2


Fig. 8.
A
X
5
9
X1
X4
1
M
7
8
X2
X5
2
6
9a
X3
E1
E


Fig. 9.
A
S
X
8
X2
5
1
M
9
X1
2
X3
7
6
X4
E
E1


Fig. 10.
A
S
5
8
7
9
10
6
E


Fig. 11.
A
S
9
7
8
10
1
M
2
5
E


Fig. 12.
A
S
X
9
10
1
5
7
2
9a
10a
X1


Fig. 13.
A
S
5
X
9
1
4a
4
M
3
3a
8
X1
2
7
E

Inventor

Normann Plauson

by Knight Bros attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12, Sheets-Sheet 3


Fig. 14.
A
S
x
8
1
4
10
3a
5
M
9
3
2
4a
7
E


Fig. 15.
A
S
5
1
4
x
x1
3a
M
9
2
6
Z
3
4a
7
E


Fig. 16.
A
S
8
5
1
4
6
3a
9
M
3
2
4a
7


Fig. 17.
A
S
1
R
1a
M
2a
8
2
7
E1
E


Fig. 18.
A
S
6
1
9
M
2
7
8
E2
E1
E


Fig. 19.
A
N
1
8
R
1²
1¹
2
5
7
x
E
E2
E


Fig. 20.
z
z
z
A1
A2
A3
A4
A5
A10
A9
A8
A7
A6
n
x
x1
x5
x9
x6
A
S
5
1
7
8
2
E

Inventor
Hermann Plauson
by Knight Bros
Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12, Sheets-Sheet 4


Fig. 22.

Fig. 23.

Fig. 21.

x
5
5
5
5
5
Z
x
X
5
Z
Z
x
5
Z
x
D'
5
5a
5b
C3
M
D1
E3
5a
5c
D3
E2
E1
5b
M
C1
C2
M
A
A
5
5
A
5
5
Z
A
5
Z
A
5
Z
C
A
5
Z
A
5
A
5
Z
A
5
Z
A
5
D
x
1
2
3a
3
7
4
4a
E

Inventor

Hermann Plauson

by Knight Bros

Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12, Sheets-Sheet 5


A
a
b
c
d
e
2
L
3a
3
3b
W
12
20
19
18
S_1
17
16
13
21
22
23
24
11
S_2
5
14
8
7
9
10
15
6
E_1
E_2

Fig. 24.

Inventor

Hermann Plauson

by Knight Bros

Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12, Sheets-Sheet 6

Fig. 25.



A_2
A_1
A_3
A_4
S_2
27
22
21
S_1
25
S_3
S_b
R.
20
S_4
16
13
18
17
19
S_a
S_c
12
S_d
26
28
24
23
J.
8
5
M
7
6
E_1
E_2

Inventor

Hermann Plauson

by Knight Bros attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12, Sheets-Sheet 7


1
2
3
4
5
6
7
8
I
19
S
S1
abcd
F1
16
A
18
17
12
g
9
14
10
11
K
13
B
B1
15
F
14
E1
E

Fig. 26.

Inventor
Hermann Plauson
by Knight Bros
Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12, Sheets-Sheet 8


22
23
II
4
6
3
2
5
9
10
19
11
f
E
F
S
S_I
E_I
20
17
13
12
F_I
S_{II}
E_{II}
I
1
4
21
II

Fig. 27.

Inventor

Hermann Plauson

by Knight Bros

Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12, Sheets-Sheet 9


1
2
4
5
3
6
II
8
7
II
I
I
III
II¹
I¹
III
20
19
II¹
9
12
10
14
a
A
b
B
13
F
S₁
S
E₁
E

Fig. 28.

Inventor

Hermann Plauson

by

Knight Bros

attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12, Sheets-Sheet 10


B
C
K
L
P
+
N
P
+
N
9
–
E

Fig. 29.


a
b
a
b
F
B
C
K
L
P
+
N
–
9
5
–
E

Fig. 30.

Inventor
Hermann Plauson
by
Knight Bros
Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12, Sheets-Sheet 11


z
B
C
K
L
P
+
+
9
−
−
10
11
−
E

Fig. 31.


z
B
C
K
L
5
6
+
9
G
N
−
E

Fig. 32.



Fig. 33.

Inventor
Hermann Plauson
by Knight Bro
Attorneys

June 9, 1925. 1,540,998

H. PLAUSON

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY

Filed Jan. 13, 1921 12, Sheets-Sheet 12


A
1
+
2
3
+
5
+
6
−
7
8
9
10
S
E
E1

Fig. 34


A
5
n
+
1
2
8
9
10
13
12
+
3
6
−
11
m
S
E
E1

Fig. 35.


A
5
1
2
11
12
3
8
7
9
10
S
E
E1

Fig. 36.


A
5
1
2
3
9
10
8
S
E
E1

Fig. 37.

Inventor

Hermann Plauson

by Knight Bros

Attorneys

Patented June 9, 1925

1,540,998

UNITED STATES PATENT OFFICE.

HERMANN PLAUSON, OF HAMBURG, GERMANY.

CONVERSION OF ATMOSPHERIC ELECTRIC ENERGY.

Application filed January 13, 1921. Serial No. 437,107

To all whom it may concern:

Be it known that I, Hermann Plauson, Estonian subject, residing in Hamburg, Germany, have invented certain new and useful improvements in the Conversion of Atmospheric Electric Energy, of which the following specification.

Methods of obtaining atmospheric electricity by means of metallic nettings set with spikes which are held by means of ordinary or anchored kite balloons made of fabrics and filled with hydrogen, are in theory already known. Atmospheric electricity obtained in this way has been suggested to be used in the form of direct current for the charging of accumulators. This knowledge however is at present only theoretical as the conversion practice has hitherto been a failure. No means are known for protecting the apparatus from destruction by lightening. The balloons used for collecting the charge must also be made of a very large size in order to be able to support the weight of the metallic netting and the heavy cable connections.

Instead of using heavy metallic netting as collectors attached to single air balloons of non-conducting material which are liable to be torn and are permeable to the gas, it is proposed to use metallic balloon collectors which have to following important advantages -

(a) The metallic cases are impenetrable to helium and hydrogen; they also represent large metallic weather-proof collecting surfaces.

(b) Radio active means and the like may be easily applied internally or externally; whereby the ionisation is considerably increased and therewith also the quantity of atmospheric electricity capable of being collected.

(c) Such balloon collectors of light metal do not require to be of large size as they have to carry only their own moderate weight, and that of the conducting cable or wire.

(d) the entire system therefore offers little surface for the action of storm and wind and is resistant and stable.

(e) Each balloon can be easily raised and lowered by means of a winch so that all repairs, recharging and the like can be carried out without danger during the operation.

It is further proposed to use a collecting aerial network of several separate collectors spread out in the air above the earth, which collectors are interconnected by electrical conductors.

According to this invention charges of atmospheric electricity are not directly converted into mechanical energy, and this forms the main differences from previous inventions, but the static electricity which runs to earth through aerial conductors in the form of direct current of very high voltage and low current strength is converted into electro-dynamic energy in the form of high frequency vibrations. Many advantages are thereby obtained and disadvantages avoided.

The very high voltage of static electricity of a low current strength can be converted by this invention to voltages more suitable for technical purposes and of greater current strength. By the use of close oscillatory circuits it is possible to obtain electromagnetic waves of various amplitude and thereby to increase the degree of resonance of such current. Such resonance allows various values of inductance to be chosen whereby again the governing of the starting and stopping of machine driven thereby by simply tuning the resonance between coils of the machine and the transformer circuit forming the resonance can easily be obtained. Further, such currents have the property of being directly available for various uses, even without employing them for driving motors, of which there may be particularly mentioned, lighting, production, of heat and use in electro-chemistry.

Further, with such current a series of apparatus may be fed without direct current supply through conductors and also the electromagnetic oscillations into mechanical energy, or finally converted by special machines into alternating current of low frequency or even into direct current of high potential.

The invention is more particularly described with reference to the accompanying diagrams in which:-

Figure 1 is an explanatory figure.

Figure 2 is a diagrammatic view of the simplest form.

Figure 3 shows a method of converting atmospheric electrical energy for use with motors.

Figure 4 is a diagram showing the use of protective means.

Figure 5 is a diagram of an arrangement for converting large current strengths.

Figure 6 is a diagram of an arrangement including controlling means.

Figure 7 shows means whereby the spark gap length can be adjusted.

Figure 8 shows a unipolar connection for the motor.

Figure 9 shows a weak coupled system suitable for use with small power motors.

Figures 10, 11 and 12 show modified arrangements.

Figure 13 shows a form of inductive coupling for the motor circuit.

Figure 14 is a modified form of Figure 13 with inductive coupling.

Figure 15 is an arrangement with non-conductive motor.

Figure 16 is an arrangement with coupling by condenser.

Figure 17, 18 and 19 are diagrams of further modifications.

Figure 20 shows a simple form in which the aerial network is combined with special collectors.

Figure 21 show diagrammatically an arrangement suitable for collecting large quantities of energy.

Figure 22 is a modified arrangement having two rings of collectors.

Figure 23 shows the connections for three rings of collectors.

Figure 24 shows a collecting balloon and diagram of its connection of condenser batteries.

Figure 25 and 26 show modified collector balloon arrangements.

Figure 27 shows a second method of connecting conductor for the balloon aerials.

Figure 28 shows an auto-transformer method of connection.

Figure 29 shows the simplest form of construction with incandescent cathode.

Figure 30 shows a form with cigar shape balloon.

Figure 31 is a modified arrangement.

Figure 32 shows a form with cathode and electrode enclosed in vacuum chamber.

Figure 33 is a modified form of Figure 32.

Figure 34 shows an arc light collector

Figure 35 shows such an arrangement for alternating current.

Figure 36 shows incandescent collector with Nernst lamp.

Figure 37 shows a form with a gas flame.

Figure 1 illustrates a simple diagram for converting static electricity into dynamic energy of a high number of oscillations. For the sake of clearness in the drawings an influence machine is assumed to be employed and not an aerial antenna. 13 and 14 are combs for collecting the static electricity of the influence machine. 7 and 8 are spark discharging electrodes, 6 and 5 condensers, 9 an inductive primary coil, 10 secondary coil, 11 and 12 ends of conductors of he secondary coil 10. When the disc of the static influence machine is rotated by mechanical means, the combs collect the electric charges one the positive and the other the negative, and charge the condensers 5 and 6 until such a high potential is formed across the spark gap 7-8, that the spark gap is jumped. As the spark gap 7-8 forms a closed circuit with condensers 6 and 5, and inductive resistance 9, as is well know, waves of high frequency electromagnetic oscillations will pass in this circuit.

The high frequency of the oscillations produced in this primary circuit induces waves of the same periodicity in the second circuit. Thus in the primary circuit electromagnetic oscillations are formed by the passage of the spark over the spark gap and these waves are maintained by fresh charges of static electricity.

By suitably selecting the ratio between the number of coils in the primary and secondary circuits with regard to a correct application of the co-efficients of resonance (capacity, inductance, and resistance) the high voltage of the primary circuit may be suitably converted into low voltage and high current strength.

When the oscillatory discharges in the primary circuit becomes weaker or entirely cease, the condensers are charged again by the static electricity until the accumulated charge again breaks down the spark gap. All this is repeated as long as electricity is produced by the static machine by employing mechanical energy.

An elementary form of the invention is shown in Figure 2 in which two spark gaps in parallel are used one of which may be termed the working gap 7 in Figure 2, whilst the second serves as a safety device for excess voltage and consists of a large number of spark gaps than the working section, which gaps are arranged in series and are bridged by very small capacities as is illustrated in a_1, b_1, c_1, Figure 2 which allow of uniform sparking in the safety section.

In Figure 2 A is the aerial antenna for collecting charges of atmospheric electricity. 13 is the earth connection of the second part of the spark gap, 5 and 6 are condensers, 9 a primary coil. Now when through the aerial A the positive atmospheric electricity seeks to combine with the negative charge to earth, this is prevented by (the air gap between) the spark gaps. The resistance of the spark gap 7 is, as shown in the drawings, lower than that of the other safety section which consists of the three spark gaps connected in

series, and consequently a three times greater air resistance is offered by the latter.

So long therefore, as the resistance of the spark gap 7 is not overloaded, so that the other spark gaps have an equal resistance with it the discharges take place only over spark gap 7. Should however the voltage be increased by any influences so it might dangerous for charging the condensers 5 and 6 or for the coils insulation 9 and 10 in consequence of break down, by a correct regulation of this spark gap the second spark gap can discharge free from inductive effects direct to earth without endangering the machine.

Without this second spark gap, arranged in parallel having a higher resistance than the working spark gap it is impossible to collect and render available large quantities of electrical energy.

The action of this closed oscillation circuit consisting of spark gap 7, two condensers 5 and 6, primary coil 9, and also secondary coil 10 is exactly the same as the one described in Figure 1 with the arrangement of the static induction machine with the only difference that here the second spark gap is provided. The electromagnetic high frequency alternating current obtained can be tapped off from the conductors 11 and 12 for lighting and heating purposes. Special kinds of motors adapted for working with these peculiar electrical charges may be connected at 14 and 15 which can work with static electricity charges or with high frequency oscillations.

In addition to the use of spark gaps in parallel a second measure of security is also necessary for taking off the current. This precaution consists according to this invention, in the introduction of and method of connecting certain protective electromagnets or choking coils in the aerial circuit as show by S in Figure 3.

A single electromagnet only having a core of the thinnest possible separate laminations is connected with the aerial.

In the case of high voltages in the aerial network or at places where there are frequent thunder storms, several such magnets may however be connected in series.

In the case or large units or plants several electromagnets can be employed in parallel or in series parallel.

The windings of these electromagnets maybe simply connected in series with the aerials. In this case the winding preferably consists of several thin parallel wires, which make up together the necessary section.

The winding may be made of primary and secondary windings in the form of a transformer. The primary winding will be then connected in series with the aerial network, and the secondary winding more or less short circuited over a regulating resistance or an induction coil. In the latter case it is possible to regulate to a certain extent the effect of the choking coils. In the further description of the connecting and constructional diagrams the aerial electromagnetic choke coil is indicated by a simple ring S.

Figure 3 shows the simplest way of converting atmospheric electricity into electromagnetic wave energy by the use of special motors adapted for high oscillatory currents or static charges of electrical energy. Recent improvements in motors for working with static charges and motors working by resonance, that is to say having groups of tuned electromagnetic cooperating circuits render this possible but such do not form part of the present invention.

A motor adapted to operate with static charges will for the sake of simplicity be diagrammatically indicated by two semi-circles 1 and 2 and the rotor of the motor by a ring M. (Figure 3) A is a vertical aerial or aerial network. S the safety choke or electromagnet with coil O as may be seen is connected with the aerial A. Adjacent the electromagnet S the aerial conductor is divided into three circuits, the circuit 8 giving safety spark gap, the circuit 7 with the working spark gap and then a circuit including the stator terminal 1, the rotor and stator terminal 2 at which a connection is made to the earth wire. The two spark gaps are also connected metallically with the earth wire. The method of working these diagrams are as follows:

The positive atmospheric electric charge collected tends to combine with the negative electricity (or earth electricity) connected with the earth wire. It travels along the aerial A through the electromagnet S without being checked as it flows in the same direction as the direct current. Further, its progress is arrested by two sparks gaps placed in the way and the stator condenser surfaces. The stator condenser surfaces are charged until the charge is greater than the resistance of the spark gap 7 and an oscillatory charge is obtained as by means of motor M, stator surfaces 1 and 2, and spark gap 7, a closed oscillation circuit is obtained for producing the electromagnetic oscillations. The motor here form the capacity and the necessary inductance and resistance, which, as is well know, are necessary for converting static electricity into electromagnet wave energy.

The discharges formed are converted into mechanical energy in special motors and can not reach the aerial network by reason of the electro-magnet or choke. If, however, when a spark springs over the spark gap 7 a greater quantity of atmospheric electricity tends to flow to earth, a counter voltage is induced in the electro-magnet, which is greater the more rapidly and strongly the flow of current direct to earth is. By the formation of this opposing voltage a sufficiently high resistance is offered to the flow of atmospheric electricity direct to earth to prevent a short circuit with the earth.

The circuit containing spark gap 8 having a different wave length which is not in resonance with the nature frequency of the motor, does not endanger the motor and serves as security against excess voltage, which, as practical experiments have shown, may still arise in certain cases but can be conducted direct to earth through this spark gap.

In the diagram illustrated in Figure 4 the spark gap 7 is shunted across condensers 5 and 6 from the motor M. This construction affords mainly a better insulation of the motor against excess voltage and a uniform excitation through the spark gap 7.

In Figure 5 a diagram is illustrated for transforming large current strengths which may be employed direct without motors, for example, for lighting or heating purposes. The main difference is that here the spark gap consists of a star shaped disc 7 which can rotate on its own axis and is rotated by a motor opposite similarly fitted electrodes 7^a. When separate points of stars face one another, discharging takes place, thus forming an oscillation circuit over condensers 5 and 6 and inductance 9 for oscillatory discharges. It is evident that a motor may also be directly connected to the ends of the spiral 9.

The construction of the diagram shown in Figure 6 permits of the oscillation circuit of the motor being connected with an induction coil. Here a regulating inductive resistance is introduced for counter-acting excess voltages in the motor. By cutting the separate coils 9 (coupled inductively to the aerial) in or out the inductive action on the oscillation circuit.

In Figure 7 the oscillation circuit is closed through the earth (E an E_1). Then spark gap 7 may be prolonged or shortened by more or fewer spark gaps being successively connected by means of a contact arm7^b.

Diagram 8 shows a unipolar connection of the motor with the aerial network. Here two oscillation circuits are closed through the same motor. The first oscillation circuit passes from aerial A through electromagnet S, point x, inductance 9^a to the earth condenser 6 and further, over spark gap 7 to aerial condenser 5 and to x. The second oscillation circuit starts from the aerial condenser 5 at the point x^1 over the inductance 9 to earth condenser 6 at the point x^3 and through the condenser 6 over the spark gap 7 back to x^1. The motor itself is inserted between two points of the spark gap 7. From this arrangement slightly damped oscillation wave currents are produced.

In the diagram illustrated in Figure 9 a loosely coupled system of connections is illustrated which is assumed to be for small motors for measuring purposes. A indicates the aerial conductor, S the electromagnet in the aerial conductor, 9 the inductance, 7 the spark gap, 5 and 6 condensers, E the earth, M the motor, and 1 and 2 stator connections of the motor. The motor is directly metallically connected with the oscillation circuit.

In Figure 10 a purely inductive coupling is employed for the motor circuit. the motor is connected with the secondary wire 10 as can be seen in Figure 11 in a somewhat modified diagram connection. The same applies to the diagram of figure 12.

The diagrams hitherto described preferably allow of motors of small and medium strength to be operated. For large aggregates, however, they are too inconvenient as the construction of two or more oscillation circuits for large amounts of energy is difficult; the governing is still more difficult and the danger in switching on or off is greater.

A means of overcoming such difficulties is shown in Figure 13. The oscillation circuit here runs starting from the point x over condenser 5, variable inductance 9, spark gap 7 and the two segments (3^a and 4^a) forming arms of a Wheatstone bridge, back to x. If the motor is connected by brushes 3 and 4 transversely to the two arms of the bridge as shown in the drawings, electromagnetic oscillations of equal sign are induced in the stator surfaces 1 and 2 and the motor does not revolve. If however, the brushes 3 and 4 are moved in common with the conducting wore 1 and 2 which connect the brushes with the stator poles a certain alteration or displacement of the polarity is obtained and the motor commences to revolve.

The maximum action will result if one brush 3 comes onto the central sparking contact 7 and the other brush 4 on the part x. They are however, usually in practice not brought on to the central contact 7 but only held in the path of the bridge segments 4^a and 3^a in order not to connect the spark gaps with the motor oscillation circuit.

As however, the entire oscillation energy can thereby not act on the motor it is better to carry out the same system according to the diagram Figure 14. The diagram 14 differs from the foregoing only by the motor not being directly metallically connected with segments of the communicator, but only a primary coil 9 which induces in a secondary coil 10, current which feeds the motor M and takes the place of the rotor. By this arrangement a good transforming action is obtained, a loose coupling and also an oscillation circuit without spark gap.

In Figure 15 the motor is not purely inductive as in 14, but directly metallically branched off from the primary coil (at x and x^1) after the principle of the auto-transformer.

In Figure 16 instead of an inductance a condenser 6 is in similar manner, and for the same object inserted between segments 3^a and 4^a. This has the advantage that the segments 3^a and 4^a need not be made of solid metal but may consist of spiral coils whereby a more exact regulation is possible and further motors of high inductance may be employed.

The arrangement of Figure 17, 18 and 19 may be employed for use with resonance and particularly with induction condenser motors; between the large stator induction condenser surfaces small reversing pole condensers are connected, which, as may be seen from Figure 17, 18 and 19 are led together to earth. Such reversing poles have the advantage that with large quantities of electrical energy the spark formation between the separate oscillation circuits ceases.

Figure 19 shows a further method which prevents electromagnetic oscillations of high number of alterations formed in the oscillation circuit striking back to the aerial conductor. It is based on the well known principle that a mercury lamp, one electrode of which is formed of mercury, the other of solid metal such as steel allows an electric charge to pass in only one direction from the mercury to the steel and not visa versa. The mercury electrode of the vacuum tube N is therefore connected with the aerial conductor and the steel electrode with the oscillation circuit cannot pass to the aerial conductor.

In practice these vacuum tubes must be connected behind the electromagnet as the latter alone affords no protection against the danger of lightening.

As regards the use of spark gaps, all arrangements as used for wireless telegraphy may be used. Of course the spark gaps in large machines must have a sufficiently large surface. In very large stations they are cooled in liquid carbonic acid or better still in liquid nitrogen or hydrogen; in most cases the cooling may also take place by means of liquefied low homologues of the metal series or by means of hydrocarbons the freezing point of which lies at between -90° C and -40° C. The spark gap casing must also be insulated and be of sufficient strength to be able to resist any pressure which may arise. Any undesirable excess super-pressure which may be formed must be automatically let off. I have employed with very good results mercury electrodes which were frozen in liquid carbonic acid, the cooling being maintained during the operation from the outside through the walls.

Figure 20 is one of the simplest forms of construction of an aerial network in combination with collectors, transformers and the like illustrated diagrammatically. E is here the earth wire, 8 the safety spark gap, 7 the working spark gap, 1 and 2 the stator surfaces of the motor, 5 a condenser battery, S the protective magnet which is connected with the coil in the aerial conductor, A^1 to A^{10} aerial antenna with collecting balloons, N horizontal collecting or connecting wires from which, to the centre a number of connections run.

The actual collectors consist of metal sheaths preferably made of an aluminium magnesium alloy, and are filled with hydrogen or helium and are attached to copper plated steel wires. The size of the balloon is selected so that the actual weight of the balloon and the weight of the conducting wire is supported thereby. On the top of the balloon and the weight of the conducting wire is supported thereby. On the top of the balloon aluminium spikes, made and gilded in a special manner hereinafter described, are arranged in order to produce a conductor action. Small quantities of radium preparations, more particularly polonium-ionium or mesothorium preparations considerably increase the ionisation, and therewith the action of these collectors.

In addition to metal balloon, fabric balloons which are superficially metal coated according to Schoop's metal spraying process, may however also be employed. A metallic surface may also be produced by lacquering with metal bronzes, preferably according to Schoop's metal spraying process or lacquering with metallic bronze powders in two electrical series of widely different metals, because thereby the collecting effect is considerably increased.

Instead of the ordinary round balloons, elongated cigar shaped ones may be employed. In order also to utilise the frictional energy of the wind, patches or strips of non-conducting substances which produce electricity by friction may be attached to the metallised balloon surfaces. The wind will impart a portion of its energy in the form of frictional electricity, to the balloon asing, and thereby the collecting effect is substantially increased.

In practice however, very high towers (up to 300 metres is fully admissible) may be employed as antenna. In these towers copper tubes rise freely further above the top of the tower. A gas lamp secured against the wind is then lit at the point of the copper tube and a netting is secured to the copper tube over the flame of this lamp to form a collector. The gas is conveyed through the interior of the tube up to the summit the copper tube must be absolutely protected from moisture at the place at which it enters the tower and also rain must be prevented running down the walls of the tower which may lead to a bad catastrophe. This is done by bell shaped enlargements which expand downwards, being arranged in the tower in the form of high voltage insulators of Siamese pagodas.

Special attention must be devoted to the foundations of such towers. They must be well insulated from the ground, which may be obtained by first embedding a layer of concrete in a box form to a sufficient depth in the ground and inserting in this an asphalt lining and then glass bricks cash about 1 or 2 metres in thickness. Over this in turn there is a ferro-concrete layer in which alone the metal foot of the tube is secured. This concrete block must be at least 2 metres from the ground and be fully protected at the sides by a wooden covering, from moisture. In the lower part of the tower a or glass house for the large condenser batteries or for the motors may be constructed. In order to lead the earth connection to the ground water, a well insulated pit constructed of vitreous bricks must be provided. Several such towers are erected at equal distances apart and connected with a horizontal conductor. The horizontal connecting wires may either run directly from tower to tower or be carried on bell shaped insulators similar to those in use for high voltage conductors. The width of the network may be of any suitable size and the connection of the motors can take place at any suitable places.

In order to collect large quantities of electricity with few aerials it is well to provide the aerial conductor with batteries of condensers as shown in two methods of construction in Figures 21 and 22. In Figure 21 the batteries of condenses 5 are connected on the one hand with the aerial collectors Z by the aerial conductor A, and the other hand interconnected in series with an annular conductor from which horizontal conductors run to the connecting points C to which the earth wire is connected.

Figure 22 shows a similar arrangement. Should two such series of antenna rings be shown by a voltmeter to have a large difference of potential (for example, one in the mountains and one in the plain) or even of different polarity these differences may be compensated for by connecting sufficiently large condenser batteries (5, 5^a, 5^b) by means of Maji star conductors D and D^1, In Figure 23 a connection of three such rings of collectors to form a triangle with central condenser battery is illustrated.

The condenser batteries of such large insulations must be embedded in liquefied gases or in liquids freezing at very low temperatures. In such cases a portion of the atmospheric energy must be employed for liquefying these gases. It is also preferable to employ pressure. By this means the condenser surfaces may be de diminished, and still allow for large quantities of energy to be stored, secure against breakdown. For smaller installations the immersing of the condensers in well insulated oil or the like, suffices. Solid substances on the other hand cannot be employed as insulators.

The arrangements in the diagrams hitherto described was always such that the condenser batteries were connected with both poles directly to the aerial conductor. An improved diagram of the connections for obtaining atmospheric electricity for the condenser batteries has however, been found to be very advantageous , this arrangement consists in that they are connected by only one pole (unipolar) to the collecting network. Such a method of arrangement is very important, as by means of it a constant current and an increase of the normal working pressure or voltage is obtained. If for example a collecting balloon aerial which is allowed to rise to a height of 300 metres, shows 40,000 volts above earth voltage, in practice it has been found that the working voltage (with a withdrawal of the power according to the method hereinbefore described by means of oscillation spark gaps and the like) is only about 400 volts. If however, the capacity of the condenser surface be increased, which capacity in the above mentioned case was equal to that of the collecting surface of the balloon aerials, to double the amount, by connecting the condenser batteries with only one pole, the voltage rises under an equal withdrawal of current up to and beyond 500 volts. This can only be ascribed to the favourable action of the connection method.

In addition to this substantial improvement it has also been found preferable to insert double inductances with electromagnets. It has also been found that the useful action of such condensers can be further increased if an induction coil be connected as inductive resistance to the unconnected pole of the condenser, or still better if the condenser itself be made as an induction condenser. Such a condenser may be compared with a spring which when compressed carries in itself accumulated force, which it again gives off when released. In charging a charge with reversed sign is formed at the

other free condenser pole, and if through the spark gap a short circuit results, the accumulated energy is again given back since now new quantities of energy are induced at the condenser pole connected with the conductor network, which in fact charges with opposite signs to that at the free condenser pole. The new induced charges have of course the same sign as the collector network. The whole voltage energy in the aerial is thereby however increased. In the same space of time larger quantities of energy are accumulated than is the case without such inserted condenser batteries.

In Figures 24 and 25 two different diagrams of connections are more exactly illustrated. Figure 24 show a collecting balloon and the diagram of the connections to earth. Figure 25 four collecting balloons and the parallel connection of the condenser batteries belonging thereto.

A is the collecting balloon made of an aluminium magnesium alloy (electron metal, magnalium) of a specific gravity of 1.8 and in thickness of plate 0.1 to 0.2 mm. Inside there are eight strong vertical ribs of T shaped section about 10 to 20 mm in height and about 3 mm in thickness with the projecting part directed inwards (indicated by a, b, c, d and so forth); they are riveted together to form a firm skeleton and are stiffened in a horizontal direction by two cross ribs. The ribs are further connected with one another internally and transversely by means of thin steel wires, whereby the balloon obtains great power of resistance and elasticity. Rolled plates of 0.1 to 0.2 mm in thickness made of magnalium alloy are then either soldered or riveted on this skeleton so that fully metallic casing with smooth external surface is obtained. Well silvered or coppered aluminium plated steel wires run form each rib to the fastening ring 2. Further, the coppered steel hawser L preferably twisted out of separate thin wires (shown in dotted lines in Figure 24) and which must be long enough to allow the balloon to rise in the desired height, leads to a metal roller or pulley 3 and from thence a winch W, well insulated from the earth. By means of this winch, the balloon, which is filed with hydrogen, or helium, can be allowed to rise to suitable height (300 to 5,000 metres) and brought to the ground for recharging or repairs.

The actual current is taken directly through a friction contact form the metal roller 3 or from the wore, or even from the winch or simultaneously form all thereby means of brush (3, 3^a and 3^b). Beyond the brushes the conductor is divided, the paths being:- firstly over 2 to the safety spark gap 8, from thence to the earth conductor E^1, and secondly over electromagnet S^1, point 13, to a second loose electromagnet having and adjustable coil S^2, then to the spark gap 7 and to the second earth conductor E^2. The actual working circuit is formed through spark gap 7, condensers 5 and 6, and through the primary coil 9; here the static electricity formed by oscillatory discharges is accumulated and converted into high frequency electromagnet oscillations. Between the electromagnets S^1 and S^2 at the crossing point 13, four condenser batteries are introduced which are only indicated diagrammatically in the drawings each by one condenser. Two of these batteries (16 and 18) are made as plate condensers and prolonged by regulating induction coils or spiral 17 and 19 while the two other (21 and 23) are induction condensers. As may be seen from the drawings each of the four condenser batteries 16, 18, 21 and 23 is connected only by one pole to the aerial or to the collector conductor. The second poles 17, 19, 22 and 24 are open. In the case of plate condensers having no inductive resistance and induction coil is inserted. The object of such a spiral or coil is the displacement of phase of the induction current by ¼ periods, whilst the charging current of the condenser poles which lie free in the air, works back to the collector aerial. The consequence of this is that in discharges in the collector aerial the back inductive action of the free pole allows a higher voltage to be maintained in the aerial collecting conductor than would otherwise be the case. It has also been found that such a back action has an extremely favourable effect on the wear of the contacts. Of course the inductive effect may be regulated at will within the limits of the size of the induction coil, the length of the coil in action being adjustable by means of wire connection without induction (see Fig. 24, No. 20).

S^1 and S^2 may also be provided with such regulating devices in the case of S^2 (illustrated by 11). If excess voltage be formed it is conducted to earth through the wire 12 and spark gap 8 or through any other suitable apparatus, since this formation would be dangerous for the other apparatus.

The action of these condenser batteries has already been hereinbefore described.

The small circles on the collector balloon indicate places at which zinc amalgam or gold amalgam or other photoelectric acting metals in the form of small patches in extremely thin layers (.01 to .05 mm in thickness) are applied to the balloon casing of light metal. Such metallic patches may also be applied to the entire balloon as well as in greater thickness to the conducting network. the capacity of the collector is thereby considerably strengthened at the surface. The greatest possible effect in collecting may be obtained by polonium amalgams and the like. On the surface of the collector balloon metal points or spikes are also fixed along the ribs, which spikes serve particularly for collecting the collector charge. Since it is well known that the resistance of the spikes is less the sharper the spike is, for this purpose it is therefore extremely important to employ as sharp spikes as possible. Experiments made as regards these have shown that the formation of the body of the spike or point also plays a large part for example spikes made of bars or rollers with smooth surfaces, have many times greater point resistance as collector accumulator spikes than those with rough surfaces. Various kinds of spike bodies have been experimental with for the collector balloons hereinbefore mentioned. The best results were given by spikes which were made in the following way. Fine points made of steel, copper, nickel, or copper and nickel alloys, were fastened together in bundles and then placed as anode with the points in a suitable electrolyte (preferably in hydrochloric acid or muriate of iron solutions) and so treated with weak current at 2 and 3 volts pressure. After 2 to 3 hours according to the thickness of the spikes or pins the points become extremely sharp and the bodies of the spikes have rough surface. The bundle can then be removed and the acid washed off with water. The spikes are then placed as cathode in a bath consisting of solution of gold, platinum, iridium, paladium or wolfram salts or their compounds and coated at the cathode galvanically with a thin layer of precious metal, which must however be sufficiently firm to protect them from atmospheric oxidation.

Such spikes act at a 20 fold lower voltage almost as well as the best and finest points made by mechanical means. Still better results are obtained if polonium or radium salts are added to the galvanic bath when forming the protective layer or coating. Such pins have a low resistance at their points and even at one volt and still lower pressures have an excellent collector action.

In Figure 24 the three unconnected poles are not connected with one another in parallel. That is quite possible in practice without altering the principle of the free pole. It is also preferable to interconnect in parallel to a common collector network, a series of collecting aerials.

Figure 25 shows a diagram for such an installation. A^1, A^2, A^3, A^4 are four metal collector balloons with gold or platinum coated spikes which electromagnetically made in the presence of polonium emanations or radium salts, which spikes or needles are connected over four electromagnets S^1, S^2, S^3, S^4, through an annular conductor R. From this annular conductor four wires run over four further electromagnets S^a, S^b, S^c, S^d, to the connecting point 13. There the conductor is divided, one branch passing over 12 and the safety spark gap 8 to the earth at E^1, the other over inductive resistance J and working spark gap 7 to the earth at E^2. The working circuit, consisting of the condenser 5 and 6 and the resonance motor or condenser motor M, such as hereinbefore described, is connected in proximity round the parking gap section 7.

Instead of directly connecting the condenser motor of course the primary circuit for high frequency oscillatory current may also be inserted.

The condenser batteries are connected b one pole to the annular conductor R and can be either inductionless (16 an 18) or made as induction condensers as shown by 21 and 23. The free poles of the inductionless condensers are indicated by 17 and 19, those of the induction condensers by 22 and 24. As may be seen from the drawings all these pole 17, 22, 19, 24 may be interconnected in parallel through a second annular conductor without fear that thereby the principle of the free pole connection will be injured. In addition to the advantages already set forth the parallel connection also allows of an equalisation of the working pressure in the entire collector network. Suitably constructed and calculated induction coils 25 and 26 may also be inserted in the annular conductor of the free poles, by means of which a circuit may be formed in the secondary coils 27 and 28 which allows current produced in this annular conductor by fluctuations of the charges or the like appearances to be measured or otherwise utilised.

According to what has been hereinbefore stated separate collector balloons may be connected at equidistant stations distributed over the entire country, either connected directly with one another metallically or by means of intermediate suitably connected condenser batteries through high voltage conductors insulated form earth. The static electricity is converted through a spark gap into dynamic energy of a high number of oscillations and may in such form be coupled as a source of energy by means of a suitable method of connecting, various precautions being observed, and special regulations. The wires leading from the collector balloons have hitherto been connected through an annular conductor without this endless connection, which can be regarded as an endless induction coil, being able to exert any action on the whole conductor system.

It has now been found that if the network conductor connecting the aerial collector balloons with one another is not made as a simple annular conductor but preferably short circuited in the form of coils of a condenser battery or spark gap or through thermionic tubes or valves or audions, then the total collecting network exhibits quite new properties. The collection of atmospheric electricity is thereby not only increased but an alternating field may be easily produced in the collector network. Further, the atmospheric electrical forces showing themselves in the higher regions may also be directly obtained by induction. In Figure 26 and 28 a form of construction is shown on the basis of which the further foundation of the method will be more particularly explained.

In Figure 26 1, 2, 3, 4 are metallic collector balloons 5, 6, 7, 8 their metallic aerial conductors and I the actual collector network. This consists of five coils and is mounted on high voltage insulators in the air, on high voltage insulators in the air, on high voltage masts (or with suitable construction cable embedded in the earth). One coil has a diameter of 1 to 100 km or more. S and S^1 are two protective electromagnets. F the second safety section against excess voltage, E its earth conductor and E^1 the earth conductor of the working section. When an absorption of static atmospheric electricity is effected through the four balloon collectors, the current in order to reach the earth connection E1 must flow spirally through the collector network over the electromagnet S, primary induction coil 9, conductor 14, anode A of the audion tube, incandescent cathode K, as the way over the electromagnet and safety spark gap F offers considerably greater resistance. Owing to the fact that the accumulated current flows in one direction, an electromagnetic alternating field is produced in the interior of the collector network coil, whereby the whole free electrons are directed more or less into the interior of the coil. An increased ionisation of the atmosphere is therefore produced. In consequence of this the points mounted on the collector balloon show a considerably reduced resistance and therefore increased static charges between the points on the balloon and the surrounding atmosphere are produced. The result of this is a considerably increased collector effect.

A second effect which could not be obtained otherwise is obtained by the electromagnetic alternating field which running parallel to the earth surface, act more or less with a diminishing or increasing effect on the earth magnetic field, whereby in the case of fluctuations in the current a return induction current of reversed sign is always is always produced in the collector coil by earth magnetism. Now if, however, a constantly pulsating continuous alternating field is produced as stated in the above collector network I, an alternating current of the same periodicity is produced also in the collecting network coil. As the same alternating field is further transmitted to the aerial balloon, the resistance of its points is thereby considerably reduced, whilst the collector action is considerably increased. A further advantage is that positive electrons which collect on the metal surfaces during the conversion into dynamic current produce a so called drop potential of the collector area. As an alternating field is present, the negative ions surrounding the collector surfaces, when discharge of the collector surfaces takes place produce by the law of induction, an induction of reversed sign on the collector surface and so forth (that is to say again a positive charge). In addition to the advantages hereinbefore set forth, the construction of connecting conductors in coil form when sufficiently large diameter, allows of a utilisation of energy arising in higher regions also in the simplest way. As is well know electric discharges frequently take place at very great elevations which may be observed, such as St. Elmo's fires or northern lights. These energy quantities have not been able to be utilised up to now. By this invention all these kinds of energy, as they are of an electromagnetic nature and the directions of the axis of the collector coils stands at right angles to the earth's surface, can be more or less absorbed in the same way as a receiver in wireless telegraphy absorbs waves coming from a far distance. With a large diameter of the spiral it is possible to connect large surfaces and thereby to take up also large quantities of energy.

It is well know that large wireless stations in the summer months, and also in the tropics are very frequently unable to receive the signals in consequence of interruptions which are caused by atmospheric electricity and this takes place with vertical coils of only 40 to 100 m diameter. If on the contrary horizontal coils of 1 to 100 km diameter be employed very strong currents may be obtained through discharges which are constantly taking place in the atmosphere. Particularly in the tropics or still better in the polar regions where the northern lights are constantly present, large quantities of energy may probably be obtained in this way. A coil with several windings should act the best. In similar manner any alteration of the earth magnetism should act inductively on such a coil.

It is not at all unlikely that earthquakes and spots on the sun will also produce an induction in such collector coils of sufficient size. In similar manner this collector conductor will react on earth currents more particularly when they are near the surface of the earth or even embedded in the earth. By combining the previous kind of current collectors so far as they are adopted for improved system with the improved possibilities of obtaining current the quantities of free natural energy which are to be obtained in the form of electricity are considerably increased.

In order to produce in the improved collector coil uniform current oscillations of an undamped nature so-called audion high vacuum or thermionic tubes of suitable connection are employed instead of the previously know spark gaps (Fig. 26, Nos.9-18). The main aerial current flows through electromagnet S (which in the case of a high number of alterations is not connected here but in the earth conductor E^1) and may be conveyed over the primary coils in the induction winding through wire 14 to the anode A of the high vacuum grid tube. Parallel with the induction resistance 9 a regulating capacity of suitable size, such as condenser 11 is inserted. In the lower part of the vacuum grid tube is arranged the incandescent filament or cathode K which is fed through a battery B. From the battery B two branches run, one to the earth conductor E^1 and the other through battery B^1 and secondary coil 10 to the grid anode g in the vacuum tube. By the method of connections shown in dotted lines, a desired voltage at the grid electrode g may also be produced through the wire 17 which is branched off from the main current conductor through switches 16 and some small condensers (a, b, c, d) connected in series, and conductor 18, without the battery B^1 being required.

The action of the entire system is somewhat as follows:-

On the connecting conductor of the aerial collector network being short circuited to earth, the condenser pole11 is charged ans slightly damped oscillations are formed in the short circuited existing oscillation circuit formed of the condenser 11 and self inductance 9. In consequence of the coupling through coil 10, fluctuations of voltage take place in the grid circuit 15 with the same frequency, which, fluctuations in turn influence the strength of the electrode current passing through the high vacuum amplyfying tube and thus produce current fluctuations of the same frequency in the anode circuit. A permanent supply of energy to the oscillation circuits 9 and 10 consequently takes place, until a condition of balance is set up, in which the consumed oscillation energy is equal to that absorbed. Thereby constant undamped oscillations are now produced in the oscillation circuits 9-11.

For regular working of such oscillation producers high vacuum strengthening tubes are necessary and it is also necessary that the grid and anode voltages shall have a phase difference of 180° so that if the grid is negatively charged, then the anode is positively charged and vice versa. This necessary difference of phase may be obtained by most varied connections, for example, by placing the oscillation circuit in the grid circuit or by separating the oscillation circuit and inductive coupling from the anodes and the grid circuit and so forth.

A second important factor in this way of converting static atmospheric electricity into undamped oscillations is that care must be taken that the grid and anode voltages have a certain relation to one another; the latter may be obtained be altering the coupling and a suitable selection of the self induction in the grid circuit, or as shown by dotted lines 18, 17, 16 by means of a larger or smaller number of condensers of suitable size connected in series; in this case the battery B^1 may be omitted. With a suitable selection of the grid potential a glow discharge takes place between the grid g and the anode A, and accordingly at the grid there is a cathode drop and a dark space is formed. The size of this cathode drop is influenced by the ions which are emitted in the lower space in consequence of shock ionization of the incandescent cathodes K and pass through the grid in the upper space. On the other hand the number of the ions passing through the grid is dependent on the voltage between the grid and the cathode. Thus if the grid voltage undergos periodic fluctuations (as in the present case) the amount of the cathode drop at the grid fluctuates and consequently the internal resistance of the tube correspondingly fluctuates, so that when a back coupling of the feed circuit with the grid circuit takes place, the necessary means are afforded for producing undamped oscillations and of taking current, according to requirements from the collecting conductor.

The frequency of the undamped oscillations produced is with a suitably loose coupling equal to the self frequency of the oscillation circuits 9 and 10. By a suitable selection of the self induction of the coil 9 and capacity 11 it is possible to extend from frequencies which produce electromagnetic oscillations of only a few metres wave length down to the lowest practical alternating current frequency. For large installations a suitable number of frequency producing tubes in the form of the well known high vacuum transmission tubes of .5 to 2kw. in size may be connected in parallel so that in this respect no difficulty exists.

The use of such tubes for producing undamped oscillations, and also the construction and method of inserting such transmission tubes in an accumulator or dynamo circuit is known and also that such oscillation producing tubes only work well at voltages of 1,000 up to 4,000 volts, so that on the contrary their use at lower voltages is

considerably more difficult. By use of high voltage static electricity this method of producing undamped oscillations as captured with that through spark gaps must be regarded as an ideal solution particularly for small installations of outputs of from 1 to 100 kw.

By the application of safety spark gaps, with interpolation of electromagnets, not only is short circuiting avoided by also the taking up of current is regulated. Oscillation producers inserted in the above way form a constantly acting electromagnetic alternating field in the collector coil, whereby as already stated, a considerable accumulated affect takes place. The withdrawal wire is connected at 12 and 13, but current may be taken by means of a secondary coil which is firmly or movably mounted in any suitable way inside the large collector coil, i.e. in its electromagnetic alternating field, so long as the direction of its axis runs parallel with that of the main current collecting coil.

In producing undamped oscillations of a high frequency (50,000 per second and more) in the oscillation circuits 9 and 11, electromagnets S and S^1 must be inserted if the high frequency oscillations are not to penetrate the collector coil. In all other cases they are connected shortly before earthing (as in Figs 27 and 28).

Figure 27 a second method of construction of the connecting conductor I another annular conductor II is inserted parallel to the former on the high voltage mast in the air (or embedded as a cable in the earth) but both n the form of a coil. The connecting wire of the balloon aerials is indicated as a primary conductor and also as a current producing network; the other is the consumption network and is not in the unipolar connection with current producing network.

In Figure 27 the current producing network I is shown with three balloon collectors 1, 2, 3 and aerial conductors 4, 5, 6; it is short circuited through condenser 19 and inductance 9. The oscillation forming circuit consists in this diagram of spark gap f, inductance 10, and condenser 11; the earth wire E, is connected to earth over electromagnet S^1. F is safety spark gap which is also connected to earth through a second electromagnet S and E. On connecting up the condenser circuit 11 this is charged over the spark gap f whereby an oscillatory discharge formed. This discharging current act through inductance 10 on the inductively coupled secondary 9, whereby in the producing network a modification of the potential of the condenser is produced. The consequence of this is that oscillations arise in the coil shaped producer network. These oscillations induce a current in the secondary circuit II, which has a smaller number of windings an a less resistance, the voltage of which, according to the proportion of the number of windings and of the ohmic resistance, is considerably lower whilst the current strength is greater.

In order to convert the current thus obtained into current of an undamped character, and to time its wave lengths, a sufficiently large regulatable capacity 20 is inserted between the ends 12 and 13 of the secondary conductor II. Here also current may bet taken without an earth conductor, but it is advisable to inert a safety spark gap E^1 and to connect this with the earth over electromagnet S^2.

The producer network may be connected with the working network II over an inductionless condenser 21 or over an induction condenser 22, 23. In this case the secondary conductor is unipolarly connected with the energy conductor.

In Figure 28 the connecting conductor between the separate accumulator balloons is carried out according to the autotransformer principle. The collecting coil connects four aerial balloons 1, 2, 3, 4, the windings of which are not made side by side but one above the other. In Figure 28 the collector coil I is shown with a thin line, the metallically connected prolongation coils II with a thick line. Between the ends I^1 and II^1 of the energy network I a regulating capacity 19 is inserted. The wire I^1 is connected with the output wire and with the spark gap F.

As transformer of the atmospheric electricity an arrangement is employed which consists in using rotary pair of condenser in which the one stator surface B is connected with the main current, whilst the other A is connected with the earth pole. Between these pairs of short circuited condensers are caused to rotate from which the converted current can be taken by means of two collector rings and brushes, in he form of an alternating current, the frequency of which is dependent on the number of balloons and the revolutions of the rotor. As the alternating current formed in the rotor can act, in this improved method of connection described in this invention, through coils 10 on the inductance 9, an increase or diminution of the feed current in I can be obtained according to the direction of the current by back induction. Current oscillations of uniform rhythm thereby result in the coil shaped winding of the producer network. As the ends of this conductor are short circuited through the regulatable condenser 19 these rhythms short circuited undamped oscillations in the energy conductor, the periodicity and wave lengths of which oscillations can be adjusted according to desire by alternating the capacity 19 to a given wave length and therewith also to a given frequency. These currents may also be employed in this form directly as working current through conductors II[1] and III. By inserting the condenser 20 a connection between these conductors may also be made, whereby harmonic oscillations of desired wave length are formed. By this means quite new effects as regards current distribution are obtained. The withdrawal of current can even take place without direct wire connection if, at a suitable point in the interior of the producing network (quite immaterially whether this has a diameter of 1 or 100 km) a coil tuned to these wave lengths and of the desired capacity is firmly or movably mounted in the aerial conductor in such a way that is axial direction is in parallel with tht of the collector coil. In this case a current is induced in the producing network, the size of which is dependent on the total capacity and resistance and also on the periodicity employed. A possibility is thereby afforded in future, of taking energy form the producer network by wireless means. As thereby in addition to atmospheric electricity also magnetic earth currents and the energy from the higher atmosphere (at least partially) may be simultaneously obtained, this last system for collecting the atmospheric energy is of particular importance for the future.

Of course everywhere instead of spark gaps suitable grid vacuum tubes may be employed as producers for undamped oscillations. The separate coils of the producer network with large diameters may be connected with one another through separate conductors all in parallel or all in series or in groups in series. By regulating the number of oscillations and also the extent of the voltage more or less large collector coils of this kind may be employed. The coils may also be divided spirally over the entire section. The coils may be carried out in annular form or also in triangular, quadrangular, hexagonal or octagonal form.

Of course wires may be carried from a suitable place to the centre or also laterally which serve the currents waves as guides. This is necessary when the currents have to be conducted over mountains and valleys and so forth. In all these cases the current must be converted into a current of suitable periodicity.

As already hereinbefore mentioned separate collecting balloons may be directly metallically interconnected at equidistant stations distributed over the entire country or may be connected by interpolation of suitable condenser batteries by means of high voltage conductors. The static electricity is converted through a spark gap into dynamic energy of a high number of oscillations, and could then in such form, with a suitable arrangement of the connections, observing various measures of precaution, be employed as source of energy after separate or special regulation

According to this invention in order to increase the collecting effect of the balloon in the aerial collector conductor or in the earth wire, radiating collectors are employed. These consist either of incandescent metal or oxide electrodes in the form of vacuum grid tubes, or electric arcs (mercury and the like electrodes) Nernst lamps or finally flames of various kinds may be simply connected with the respective conductor.

It is well known that energy can be drawn off from a cathode consisting of an incandescent body opposite an anode charged with positive electricity (vacuum grid tube). Hitherto however, a cathode was always first directly placed opposite an anode, and secondly the system always consisted of closed circuit.

Now if we dispense with the ordinary ideas in forming light or flame arcs in which a cathode must always stand directly opposite an anode, and if we place an incandescent cathode opposite an anode charged to a high potential or another body freely floating in the air, or regard the incandescent cathode only as a source of unipolar discharge (which represent group and point discharges in electrostatic machines similar to unipolar discharges), it may be ascertained that incandescent cathodes and less perfectly all incandescent radiators, flames and the like admit of relatively large current densities and allow large quantities of electric energy to radiate into the open space in the form of electron streams as transmitters.

The object of this invention is as described below, if such incandescent radiators or flames are not freely suspended in space but connected metallically with the earth so that they can be charged with negative terrestrial electricity, these radiators possess the property of absorbing the free positive electrical charges contained in the air space surrounding them (that is to say of collecting them and conducting them to earth). They can therefore, serve as collectors and have, in comparison to the action of the spikes, or points, a very large radius of action R; the effective capacity of these collectors is much greater than the geometrical capacity (R_O-) calculated in an electrostatic sense.

Now as our earth is surrounded as is well known, with an electrostatic field and the difference of potential

$$\frac{\delta V}{\delta h}$$

of the earth field according to the latest investigations, is in summer about 60 to 100 volts and in winter 300 to 500 volts per metre of difference in height (δh), a simple calculation gives the result that when such a radiation collector or flame collector is arranged for example on the ground, and a second one is mounted vertically over it at a distance of 2,000 metres and both are connected by a conducting cable, there is a difference of potential in summer of about 2,000,000 volts and in winter 6,000,000 volt or more.

According to Stefan Boltzmann's law of radiation, the quantity of energy which an incandescent surface (temperature T) of 1 sq cm radiates in a unit of time into the open air (Temperature T_O) is expressed by the following formula:

$$S = \delta\ (T^4 - T^4_O)\ \text{watt/sq cm}$$

and the universal radiation constant 6 is according to the latest researches of Ferry (Annales de Chimie et de physique 17 page 267 (1909)) equals to 6.30×10^{-22} watt/sq cm.

Now if an incandescent surface of 1 sq cm shows, as compared with the surrounding space a periodic fall of potential δV it radiates (independent of the current direction, that is to say of the sign) in accordance with the above formula, for example at a temperature of 3725°C an energy of 1.6 kw per sq cm per second. As for the radiation the same value can be calculated for the collection of energy, but reversed. Now as carbon electrodes at the temperature at the temperature of the electric arc support on the current basis density up to from 60 to 65 amperes per sq cm no difficulties will result in the direction in employing radiating collectors as accumulators.

If the earth be regarded as a cosmically insulated condenser in the sense of geometrical electrostatics x there results from the geometric (compare Ewald Rasch, "das elcktrische Bogenlicht" (The electric arc light) page169) capacity of the earth according to Chwolson:

For negative charging 1.3×10^5 Coulomb.
For negative potential $V = 10 \times 10^8$ volts. From this there results however, $EJT \cong 24.710^{24}$ watt/Sec. Now if it is desired to make a theoretic short circuit through an earthed flame collector this would represent an electric total work of about 79,500 10^{10} kilowatt years as the earth must be regarded as a rotating mechanism which is thermo-dynamically, electromagnetically, and also kinematically coupled with the sun and stars by cosmic radiations and gravitation a diminution of the electric energy of the earth field is not to be feared. The energies which the incandescent collectors would withdraw from the earth field can only cause by the withdrawal of motor work a lowering of the earth temperature (temperature $T_E = 300$) and reduce this to that of the world space (T=O) by using the entire energy. This is however not the case as the earth does not represent a cosmically entirely insulated system. On the contrary there is conveyed to the same according to the recent value corrected by Ferry for the solar constants through the radiation from the sun an energy of $18{,}500 \times 10^{10}$ kw. Accordingly any lowering of the earth temperature (T_E) without simultaneous lowering of the sun's temperature (T_S) would contradict Stefan Boltzmann's law of radiation.

$$S = \delta\ (T_S^4 - T_E^4).$$

From this it must be concluded that if the earth temperature (T_E) sinks, the total radiation S absorbed by the earth increases, and further also that the secular speed of cooling of the earth is directly dependant on that of the sun and the other radiators cosmically coupled with the sun and is connected most closely with these.

The incandescent radiation collectors may, according to this invention, be employed for collecting atmospheric electricity if they (1) are charged with the negative earth electricity (that is to say when they are directly connected by means of a metallic conductor with earth) and (2) if large capacities (metal surfaces) charged with electricity are mounted opposite them as positive poles in the air. This is regarded as the main feature of the present invention as without these inventive ideas it would not be possible to collect with an incandescent collector, sufficiently large quantities of the electrical charges contained in the atmosphere as technology requires; the radius action of the flame collectors would also be too small, especially if it be considered that the very small surface density (energy density) (δ about$=2 \times 7\ .\ 10^9$ St. E per sq cm) does not allow of large quantities of charge being absorbed form the atmosphere.

x) Calculated according to Poisson;s calculation;

$\Delta V = -4\pi\delta$; as here the alteration of potential or potential gradients only takes place in the direction of the normal, this calculation assumes the simple form

$$\delta \equiv \frac{\overline{1}}{4\pi} \times \frac{\overline{\delta^2 V}}{\delta n^3}$$

It has indeed already been proposed to employ flame collectors for collecting atmospheric electricity and it is known that

their collecting effect is substantially greater opposite the points. It is however, not known that the quantities of current which could hitherto be obtained are too small for technical purposes. According to my experiments the reason for this is to be found in the too small capacities of the collector conductor poles. If such flame or radiating collectors have no or only small positive surfaces, their radius of action for large technical purposes is too small. If the incandescent collectors be constantly kept in movement in the air they may collect more according to the speed of the movement, but this again not capable of being carried out in practice.

By this invention the collector effect is considerably increased by a body charged with a positive potential and of the best possible capacity being also held floating (without direct earth connection) opposite such an incandescent collector which is held floating in the air at a desired height. if for example, a collecting balloon of sheet metal or metallized balloon fabric be caused to mount to 300 up to 3000 metres in the air and as positive pole it is brought opposite such a radiating collector connected by a conductor to earth, quite different results are obtained.

The metallic balloon shell (with a large surface) is charged to a high potential by the atmospheric electricity. This potential is greater the higher the collecting balloon is above the incandescent collector. The positive electricity acts concentratedly on the anode floating in the air as it is attracted through the radiation shock ionization, proceeding from the incandescent cathode. The consequence of this is that the radius of action of the incandescent cathode collector is considerably increased and thereby also the collecting effect of the collecting balloon surface. Further the large capacity of the anode floating in the air plays therefore an important part because it allows of the taking of large charges, and thereby a more uniform current is obtained even when there is a large consumption; this cannot be the case with small surfaces.

In the present case the metallic collecting balloon is a positive anode floating in the air and the end of the earth conductor of this balloon serves as positive pole surface opposite the surface of the radiating incandescent cathode, which in turn is charged with negative earth electricity being conductingly connected to earth

The process may be carried out by two such contacts (negative incandescent cathode and anode end of a capacity floating in the air) a condenser and an inductive resistance being switched on in parallel, whereby simultaneously undamped oscillations may be formed.

In very large installations it is advisable to connect two such radiating collectors in series. Thus an are light incandescent cathode may be placed below on the open ground and an incandescent cathode which is heated be special electromagnetic currents be located high in the air. Of course for this the special vacuum Liebig tubes with or without grids may also be employed. An ordinary lamp with oxide electrodes may be introduced on the ground and the positive pole is not directly connected with the collecting balloon, but through the upper incandescent cathode or over a condenser. The method of connecting the incandescent cathode floating in the air may be seen in Fis. 29-33.

B is the air balloon, K a Cardan ring (connection with the hawser) C the balloon L a good conducting cable. P a positive pole, N negative incandescent cathode, and E earth conductor.

Fig. 29 represents the simplest form of construction. If electric oscillations are produced below on the ground by means of a carbon lamp or in other suitable way a considerably greater electric resistance is opposed to that in the direct way by inserting an electrical inductive resistance 9. Consequently between P and N a voltage is formed and as, over N and P only an inductionless ohmic resistance is present, a spark will spring over so long as the separate induction co-efficients and the like are correctly calculated. The consequence of this is that the oxide electrode (carbon or the like) is rendered incandescent and then shows as incandescent cathode an increased collecting effect. The positive poles must be substantially larger than the negative in order that they may not also become incandescent. As they are further connected with the large balloon area which has a large capacity and is charged at high voltage, an incandescent body which is held floating in the air and a positive pole which can collect large capacities is thereby obtained in the simplest way. The incandescent cathode is first caused to become incandescent by means of separate energy produced on the earth, and then maintained by the energy collected from the atmosphere.

Fig. 30 only shows the difference that instead of n round balloon a cigar shaped one (of metal or metalized fabric) may be employed and also a condenser 5 is inserted between the incandescent cathode and the earth conductor so that a short circuited oscillation circuit P. N 5 and 9 is obtained. This has the advantage that quite small quantities of electricity cause the cathode to become incandescent and much larger cathode bodies may be rendered incandescent.

In this form of construction both the in-

candescent cathode and also the positive electrode may be enclosed in a vacuum chamber as may be seen in Fig 32. A cable L is carried well insulated through the cover of a vessel and ends in a condenser disc 5. The cover is arched in order to keep off the rain. The vessel is entirely or partially made of magnetic metal and well insulated inside and outside. Opposite the metallic positive pole of the vacuum tube g with the incandescent cathode (oxide electrode) N is arranged. The negative electrode is on the one hand connected with the earth conductor E, and on the other hand with the inductive resistance 9 which is also connected with the cable L with the positive pole and wound round the vessel in coils. The action is exactly the same as that in Fig. 29 only instead of an open incandescent cathode one enclosed on vacuo is employed. As in such collectors only small bodies can be brought to incandescence in large installations a plurality of such vacuum tubes must be inserted in proximity to one another. According to the previous constructions Figs. 31 and 33 are quite self evident without further explanations

Figs 34-37 represent further diagrams of connections over radiating the flame collectors, and in fact, how they are to be arranged on the ground.

Fig. 34 shows n arc light collector with oxide electrodes for direct current and its connection;

Fig. 35 a similar one for alternating current,

Fig. 36 an incandescent collector with a Nernst lamp and Fig. 37 a similar one with a gas flame.

The positive pole 1 of the radiating collectors is always directly connected to the aerial collecting conductor A. In Fig. 34 this is further connected over the condenser battery 5 with a second positive electrode 3. The direct current dynamo b produces current which flows over between the electrodes 3 and 2 as an arc light. On the formation of arc the negative incandescent electrode 2 absorbs electricity from the positive poles standing opposite it and highly charged with atmospheric electricity and conveys the same to the working circuit. The spark gap 7, inductive resistance 9 and induction coil 10 are like the ones previously described. The protective electromagnet S guards the installation against earth circuiting, the safely spark gap 8 from excess voltage and overcharging.

In Fig. 35 the connection is so far altered that the alternating current dynamo feeds the exciting coil 11 of the induction condenser. 12 is its negative and 13 its positive pole; if the coil 3 on the magnet core of the dynamo is correctly calculated and the periodicity of the alternating current is sufficiently high an arc light can be formed between the two pole 1 and 2. As the cathode 2 is connected with the negatively charged earth, and therefore always acts as a negative pole, a form of rectification of the alternating current produced by the dynamo 3 is obtained, the second half of the period is always suppressed. The working circuit may be carried out in the same way as Fig. 34; the working spark gap 7 may however be dispensed with, and instead thereof between the points n and m a condenser 5 and a induction resistance 9 may be inserted from which the current is taken inductively.

Fig. 36 represents a form of construction similar to Fig. 34 only that here instead of an arc lamp a Nernst incandescent body is employed. The Nernst lamp is fed through the battery 3. the working section is connected with the negative pole, the safety spark gap with the + poles. The working spark gap 7 may also be dispensed with the current for it taken at 12 over the oscillation circuit 5, 11 (shown in dotted lines).

Flame collectors (Fig. 37) may also be employed according to this invention. The wire network 1 is connected with the aerial collector conductor A and the burner with the earth. At the upper end of the latter, long points are provided which project the flame. The positive electrode is connected with the negative over a condenser 5 and the induction coil 9 with the earth.

The novelty in this invention is firstly the use of incandescent cathodes opposite positive poles which are connected with large metallic capacities as automatic collecting surfaces, (2) the connection to the incandescent cathodes with the earth whereby, in addition to the electricity conveyed to them from the battery or machine which causes the incandescing, also the negative charge of the earth potential is conveyed, and (3) the connection of the positive and negative poles of the radiating collectors over a condenser circuit alone or with the introduction of a suitable inductive resistance, whereby simultaneously an oscillatory oscillation circuit by obtained. The collecting effect is by these methods quite considerably increased.

I declare that what I claim is:-

1. An electrical generating system, comprising a conducting surface for static charges, means to support same at a distance above the earth, a conductor leading to the earth level, n spark gap associated with said conductor to convert electrostatic charges into electromagnetic high frequency oscillations means to supply said electromagnetic energy to a net work, and a spark gap of greatly increased relative resistance in parallel therewith.

2. An electrical energy generating system

comprising a conductor, means to support same above the earth level, an inductance therein, a spark gap associated with said conductor, a second spark gap of much higher relative resistance in parallel therewith and an energy receiving circuit coupled with the spark gap of lesser resistance.

3. An electrical generating system comprising a collecting surface, means to support same above the earth level, a conductor connecting said connecting surfaces with the earth level, a choke in said conductor, an electromagnetic resistance converting electrostatic energy to electromagnetic energy, a safety higher resistance in parallel therewith and a net work coupled with the conversion resistance of lesser value,

4. An electrical energy generating system comprising electric conductors spaced above the earth to form electromagnetic oscillating circuits, conductors connecting to earth level, electrostatic to electromagnetic energy conversion means therein, a safety high electrostatic resistance in parallel therewith and means to alter the electromagnetic characteristics of he circuits

5. An electrical energy generating system comprising in combination a static collecting surface arranged above the earth, conductors connecting to earth level, a pair of spark gaps in parallel of different electrostatic resistance, a utilization net work shunted across the spark gap of lesser resistance and an electromagnetic choke in said conductors.

6. An electrical energy generating system comprising an open circuit energy collecting aerial, a pair sparking gaps in parallel of widely different resistance, connected thereto and a closed electric oscillation circuit in shunt across the gap of lesser resistance.

7. An electrical energy generating system comprising an open circuit energy collecting aerial, a pair of sparking gaps in parallel of widely different resistance connected thereto, a closed electric oscillation circuit in shunt across the gap of lesser resistance, a plurality of electrostatic collecting surfaces, means to connect said collecting surfaces in parallel in groups and means to connect said groups symmetrically with said aerial.

In witness whereof, I have hereunto signed my name this 30 day of Dec., 1920, in the presence to two subscribing witnesses.

HERMAN PLAUSON.

Witnesses:
H.F. Armstrong

No. 685,958 **Patented Nov. 5, 1901**

N. TELSA

METHOD OF UTILISING RADIANT ENERGY.
(Application filed Mar. 21, 1901.)

(No Model.)



Fig.1



Fig.2

Witnesses:
Raphaël Netter
M. Lawson Dyer

Nikola Tesla, Inventor
by Kerr, Page & Cooper Attys

UNITED STATES PATENT OFFICE.

NIKOLA TELSA, OF NEW YORK, N. Y.

METHOD OF UTILIZING RADIANT ENERGY

SPECIFICATION forming part of letter patent No. 685,958, dated November 5, 1901.

To all whom it may concern:

Be it known that I, Nikola Tesla, a citizen of the United States, residing at the borough of Manhattan, in the city, county, and State of New York, have invented certain new and useful improvements in Methods of Utilizing Radiant energy, of which the following is a specification, reference being had to the drawings accompanying and forming a part of the same.

It is well known that certain radiations - such as those of ultra-violet light, cathodic, Roentgen rays, or the like – possess the property of charging and discharging conductors of electricity, the discharge being particularly noticeable when the conductor upon which the rays impinge is negatively electrified. These radiations are generally considered to be either vibrations of extremely small wave lengths, and in explanation of the phenomena noted it has been assumed by some authorities that they ionize or render conducting the atmosphere through which they are propagated. My own experiments and observations, however, lead me to conclusions more in accord with the theory heretofore advanced by me that sources of such radiant energy throw off the great velocity minute particles of matter which are strongly electrified, and therefore capable of charging an electrical conductor, or even if not so may at any rate discharge an electrified conductor either carrying off bodily its charge or otherwise.

My present application is based upon a discovery which I have made that when rays or radiations of the above kind are permitted to fall upon an insulated conducting body connected to one of the terminals of a condenser, while the other terminal of the same is made by independent means to receive or to carry away electricity, a current flows into the condenser so long as the insulated body is exposed to the rays, and under the conditions hereinafter specified an indefinite accumulation of electrical energy in the condenser takes place. This energy after a suitable time interval, during which the rays are allowed to act, may manifest itself in a powerful discharge, which may be utilized for the operation or control of mechanical or electrical devices or rendered useful in many other ways.

In applying my discovery I provide a condenser, preferably of considerable electrostatic capacity, and connect one of its terminals to an insulated metal plate or other conducting body exposed to the rays or streams of radiant matter. It is very important, particularly in view of the fact that electrical energy is generally supplied at a very slow rate to the condenser, to construct the same with the greatest care. I use by preference the best quality of mica as dielectric, taking every possible precaution in insulating the armatures, so that the instrument may withstand great electrical pressure without leaking and may leave no perceptible electrification when discharging instantaneously. In practice I have found that the best results are obtained with condensers treated in the manner described in a patent granted to me February 23, 1897, No. 577,671. Obviously the above precautions should be the more rigorously observed the slower the rate of charging and the smaller the time interval during which the energy is allowed to accumulate in the condenser. The insulated plate or conducting body should present as large a surface as practicable to the rays or streams of matter, I having ascertained that the amount of energy conveyed to it per unit of time is under otherwise identical conditions proportionate to the area exposed, or nearly so. Furthermore, the surface should be clean and preferably highly polished or amalgamated. The second terminal or armature of the condenser may be connected to one of the poles of a battery or other source of electricity or to any conducting body or object whatever of such properties or so conditioned that by its means electricity of the required sign will be supplied to the terminal. A simple way of supplying positive or negative electricity to the terminal is to connect the same either to an insulated conductor, supported at some height in the atmosphere, or to a grounded conductor, the former, as is well know, furnishing positive and the latter negative electricity. As the rays or supposed streams of the first condenser-terminal, which is connected to the plate or conductor above mentioned, I usually connect the second terminal of the condenser to the ground, this being the most convenient way of obtaining negative electricity, dispensing with the necessity of providing an artificial source. In order to utilize for any useful purpose the energy accumulated in the condenser, I furthermore connect to the terminals of the same a circuit including an instrument or apparatus which it is desired to operate and another instrument or device for alternately closing and opening the circuit. This latter may be any form of circuit-controller, with fixed or movable parts or electrodes, which may be actuated either by the stored energy or by independent means.

The rays or radiations which are to be utilized for the operation of the apparatus above described in general terms may be derived from a natural source, as the sun, or may be artificially produced by such means, for example, as an arc-lamp, a Roentgen tube, and the like, and they may be employed for a great variety of useful purposes.

My discovery will be more fully understood from the following detailed description and annexed drawings, to which reference is now made, and in which-

Figure 1 is a diagram showing typical forms of the devices or elements as arranged and connected in applying the method for the operation of a mechanical contrivance or instrument solely by the energy stored; and Fig. 2 is a diagrammatical representation of a modified arrangement suitable for special purposes, with a circuit-controller actuated by independent means.

Referring to Fig. 1, C is the condenser, P the insulated plate or conducting body, which is exposed to the rays, and P' another plate or conductor, all being joined in series, as shown. The terminals T T' of the condenser are also connected to a circuit including a receiver R, which is to be operated, and a circuit-controlling device *d*, which in this case is composed of two very thin conducting-plates *t t'*, placed in close proximity and very mobile, either by reason of extreme flexibility or owing to the character of their support. To improve their action, they should be enclosed in a receptacle from which the air may be exhausted. The receiver R is shown as consisting of an electromagnet M, a movable armature *a*, a retractile spring *b*, and a ratchet-wheel *w*, provided with a spring-pawl *r*, which is pivoted to armature *a*, as illustrated. The apparatus being arranged as shown, it will be found that when the radiations of the sun or of any other source capable of producing the effects before described fall upon the plate P an accumulation of electrical energy in the condenser C will result. This phenomenon, I believe, is best explained as follows: The sun as well as other sources of radiant energy throw off minute particles of matter positively electrified, which, impinging upon the plate P, communicate an electrical charge to the same. The opposite terminal of the condenser being connected to the ground, which may be considered as a vast reservoir of negative electricity, a feeble current flows continuously into the condenser, and inasmuch as these supposed particles are of an inconceivably small radius or curvature, and consequently charged to a relatively very high potential, this charging of the condenser may continue, as I have found in practice, almost indefinitely, even to the point of rupturing the dielectric. Obviously whatever circuit-controller be employed it should operate to close the circuit in which it is included when the potential in the condenser has reached the desired magnitude. Thus in Fig. 1 when the electrical pressure at the terminals T T' rises to a certain predetermined value the plates *t t'*, attracting each other, close the circuit connected to the terminals. This permits a flow of current which energizes the magnet M, causing it to draw down the armature a and impart a partial rotation to the ratchet-wheel *w*. As the current ceases the armature is retracted by the spring *b* without, however, moving the wheel *w*. With the stoppage of the current the plates *t t'* cease to be attracted and separate, thus restoring the circuit to its original condition.

Many useful applications of this method of utilizing the radiations emanating from the sun or other source and many ways of carrying out the same will at once suggest themselves from the above description. By way of illustration a modified arrangement is shown in Fig. 2, in which the source S of radiant energy is a special form of Roentgen tube devised by me having but one terminal *k*, generally of aluminum, in the form of half a sphere with a plain polished surface on the front side, from which the streams are thrown off. It may be excited by attaching it to one of the terminals of any generator of sufficiently-high electromotive force; but whatever apparatus be used it is important that the tube be exhausted to a high degree, as otherwise it might prove entirely ineffective. The working or discharge circuit connected to the terminals T T' of the condenser includes in this case the primary *p* of a transformer and a circuit-controller comprising a fixed terminal or brush t and a movable terminal *t'* in the shape of a wheel with conducting and insulating segments which may be rotated at an arbitrary speed by any suitable means. In inductive relation to the primary wire or coil *p* is a secondary *s*, usually of a much greater number of turns, to the ends of which is connected a receiver R. The terminals of the condenser being connected as indicated, one to an insulated plate P and the other to a grounded plate P', when the tube S is excited rays or streams of matter are emitted from the same, which convey a positive charge to the plate P and condenser-terminal T, while terminal T' is continuously receiving negative electricity from the plate

P'. This, as before explained, results in an accumulation of electrical energy in the condenser, which goes on as long as the circuit including the primary *p* is interrupted. Whenever the circuit is closed, owing to the rotation of the terminal *t*', the stored energy is discharged through the primary *p*, this giving rise in the secondary *s* to induced currents which operate the receiver R.

It is clear from what has been stated above that if the terminal T' is connected to a plate supplying positive instead of negative electricity the rays should convey negative electricity to plate P. The source S may be any form of Roentgen or Lenard tube; but it is obvious from the theory of action that in order to be very effective the electrical impulses exciting it should be wholly or at least preponderatingly of one sign. If ordinary symmetrical alternating currents are employed, provision should be made for allowing the rays to fall upon the plate P only during those periods when they are productive of the desired result. Evidently if the radiations of the source be stopped or intercepted or their intensity varied in any manner, as by periodically interrupting or rhythmically varying the current exciting the source, there will be corresponding changes in the action upon the receiver R, and thus signals may be transmitted and many other useful effects produced. Furthermore, it will be understood that any form of circuit-closer which will respond to or be set in operation when a predetermined amount of energy is stored in the condenser may be used in lieu of the device specifically described with reference to Fig. 1, and also that the special details of construction and arrangement of the several parts of the apparatus may be very greatly varied without departure from the invention.

Having described my invention, what I claim is—

1. The method of utilizing radiant energy, which consists in charging one of the armatures of a condenser by rays or radiations, and the other armature by independent means, and discharging the condenser through a suitable receiver, as set forth.

2. The method of utilizing radiant energy, which consists in simultaneously charging a condenser by means of rays or radiations and an independent source of electrical energy, and discharging the condenser through a suitable receiver, as set forth.

3. The method of utilizing radiant energy, which consists in charging one of the armatures of a condenser by rays or radiations, and the other by independent means, controlling the action or effect of said rays or radiations and discharging the condenser through a suitable receiver, as set forth.

4. The method of utilizing radiant energy, which consists in charging one of the armatures of a condenser by rays or radiations and the other by independent means, varying the intensity of the said rays or radiations and periodically discharging the condenser through a suitable receiver, as set forth.

5. The method of utilizing radiant energy, which consists in directing upon an elevated conductor, connected to one of the armatures of a condenser, rays or radiations capable of positively electrifying the same, carrying off electricity from the other armature by connecting the same with the ground, and discharging the accumulated energy through a suitable receiver, as set forth.

6. The method of utilizing radiant energy, which consists in charging one of the armatures of a condenser by rays or radiations, and the other by independent means, and effecting by the automatic discharge of the accumulated energy the operation or control of a suitable receiver, as set forth.

NIKOLA TESLA.

Witnesses:
M. LAWSON DYER,
RICHARD DONOVAN.

UNITED STATES PATENT OFFICE.

MAHLON LOOMIS, OF WASHINGTON, DISTRICT OF COLUMBIA.

IMPROVEMENT IN TELEGRAPHING

Specification forming part of letter patent No. **129,971,** dated July 30, 1872.

To all whom it may concern:

Be it known that I, MAHLON LOOMIS, dentist, of Washington, District of Columbia, have invented or discovered a new and improved Mode of Telegraphing and of Generating Light, Heat, and Motive-Power; and I do hereby declare that the following is a full description thereof.

The nature of my invention or discovery consists, in general terms, of utilizing natural electricity and establishing an electrical current or circuit for telegraphic and other purposes without the aid of wires, artificial batteries, or cables to form such electrical circuit, and yet communicate from one continent of the globe to another.

To enable others skilled in electrical science to make use of my discovery, I will proceed to describe the arrangements and mode of operation.

As in dispensing with the double wire, (which was first used in telegraphing,) and making use of but one, substituting the earth instead of a wire to form one-half the circuit, so I now dispense with both wires, using the earth as one-half the circuit and the continuous electrical element far above the earth's surface for the other part of the circuit. I also dispense with all artificial batteries, but use the free electricity of the atmosphere, co-operating with that of the earth, to supply the electrical dynamic force or current for telegraphing and for other useful purposes, such as light, heat, and motive power.

As atmospheric electricity is found more and more abundant when moisture, clouds, heated currents of air, and other dissipating influences are left below and a greater altitude attained, my plan is to seek as high an elevation as practicable on the tops of high mountains, and thus penetrate or establish electrical connection with the atmospheric stratum or ocean overlying local disturbances. Upon these mountaintops I erect suitable towers and apparatus to attract the electricity, or, in other words, to disturb the electrical equilibrium, and thus obtain a current of electricity, or shocks or pulsations, which traverse or disturb the positive electrical body of the atmosphere above and between two given points by communicating it to the negative electrical body in the earth below, to form the electrical circuit.

I deem it expedient to use an insulated wire or conductor as forming a part of the local apparatus and for conducting the electricity down to the foot of the mountain, or as far away as may be convenient for a telegraph-office, or to utilize it for other purposes.

I do not claim any new key-board nor any new alphabet or signals; I do not claim any new register or recording instrument; but

What I claim as my invention or discovery, and desire to secure by Letters Patent, is –

The utilization of natural electricity from elevated points by connecting the opposite polarity of the celestial and terrestrial bodies of electricity at different points by suitable conductors, and, for telegraphic purposes, relying upon the disturbance produced in the two electro-opposite bodies (of the earth and atmosphere) by an interruption of the continuity of one of the conductors from the electrical body being indicated upon its opposite or corresponding terminus, and thus producing a circuit or communication between the two without an artificial battery or the further use of wires or cables to connect the co-operating stations.

MAHLON LOOMIS

Witnesses:
BOYD ELIOT,
C. C. WILSON.

UNCOMMON PARTS LIST


6
7
① On/Off
② Frequency control (voltage auto-adjusts to load & frequency)
③ Fuse
④ 12V DC Power input
⑤ Dedicated ground line
⑥ HV Return line
⑦ HV Power Output line
3
1
4
2
5

ION PUMP: High Voltage Module (HVM)

1-20kV, 20-50 kHz, 30-watt adjustable voltage multiplier, front panel adjustable output power supply, which is excellent for driving the high voltage module (**HVM**). Variable open circuit voltage is 1k-20kV with a short circuited current of 20mA. The frequency is adjustable from 20-50 kHz and is controlled from the front panel; voltage auto-adjusts to capacitive load & frequency. You can fine-adjust this high voltage module (**HVM**) to your output load (**L**).

INPUT - 12VDC, 3A (includes a 12V wall adapter)
OUTPUT - Variable 1-20kV
FREQUENCY - Variable 20-50 kHz
CURRENT - Reactance is limited to 20mA

To order go to: http://www.amazing1.com/products/1-20kv-20-50khz-30w-adjustable-power-supply.html

Perreault Plasma Valve (PPV)

Complete, and is ready for your radioionics energy receiver prototype. This component mixes positive and negative ions converting them into a surge of electromagnetic electrical energy.

To order go to: Radioionic Research Online Store

Don't Let The Big Energy Corporations Control You – Free Energy Is HERE

*(**+6** rating, **6** votes, **rated**)*

You need to be a registered member to rate this post.

May 26, 2012 *in* *Activism*, *Preparedness*, *Resistance*, *Science*, *Technology*

by Kellie

The below added text I have been looking into has been an easily made design. Our government goes to no end to stop men and women who help human kind with their awesome God given inventions. I am not afraid to share this as Alex does with his knowledge and research. It is to open the minds of those that are dumbed down by corporate America and the global elite to do as they bid…No…stand up and fight against their system.

Free energy is NOT a hoax as they want you to believe.

If you have any engineer in you or technical expertise – Read…It works !

Jes Ascanius' Version of Nikola Tesla's Aerial System

This sort of information may seem confusing and maybe a little too technical for you, so let me tell you about the practical and useful applications used by Jes Ascanius, a Danish developer, to whom thanks is due for sharing his design. Initially, he set up a system to charge his mobile phone battery overnight from an aerial. Then he went on to produce a full-size Tesla Aerial System as described at the start of this chapter. Let's start with the very simple system and progress from that to the more powerful arrangements.

The initial circuit uses one strand of solid wire which rises vertically to a 700 mm diameter drum where there are some twenty turns. The arrangement is like this:



The aerial wire is several metres long, and in the prototype, was supported by (and insulated from) the eaves of a house. The aerial should be vertical or near vertical and a proper earth connection provided by driving a metal rod into the ground or connecting a wire to a metal plate and burying the plate in the ground as a good electrical connection is needed here. The earth connection used here is a 12 mm copper pipe 3 metres long, driven into the ground and the ground around it saturated with water:

The wire used to connect with the earthing rod is very important and should not be less than 8 swg copper wire, that is, 4 mm diameter and 13 sq. mm. cross-sectional area. As with all free-energy devices, the exact constructional details are vital.

The diodes used are germanium 1N34 or 1N34a as germanium diodes drop far less voltage than do silicon diodes and the 1N34 types are low-loss diodes, particularly suited to this application. Ceramic disc types are recommended for the 200 nF capacitors. The prototype build looked like this:

REFEED 24/7
LISTEN NOW

UPCOMING MISSIONS

- Complete Your 'Base, Loc Interests' Sections Of You
  Complete by:Thursday Dec 31, 2
- Flood Alex With Demands Does And Does So Very T
  Complete by:Friday Jan 1, 2016 /
- #InfowarsMusic
  Complete by:Saturday Apr 30, 20
- Prevent Tyranny In All Nat
  Complete by:Sunday Jan 1, 2017
- Collaborators Remembere
  Complete by:Sunday Dec 31, 201
- Mission #4: Earth Psychic
  Complete by:Thursday Dec 31, 2
- N.D.A.A (National Defense
  Complete by:Sunday Jul 31, 2022
- Be The Best You Can Be
  Complete by:Wednesday Nov 30
- Agenda 21
  Complete by:Saturday Dec 31, 20
- U.N. Gun Arms Trade Trea
  Complete by:Saturday Dec 31, 20

INSPIRATION SITES

Infowars.com
PrisonPlanet.tv
Infowars Shop
PrisonPlanet.com

Asked by Infowars

How do you fee players kneeling anthem?

I stand with

I stand with

(https://www.squareoffs

INFOWARS.COM NE

UPCOMING EVENTS

There are no upcoming group e

SEARCH:

Search





Now, consider this circuit as described, to be one modular building block which can lead to unlimited power from an aerial. I will represent the circuit shown above as a rectangle, showing the above circuit as:



While it is possible to use more than one module with the aerial to get more power, the Danish developer then switched to the full-blown Tesla arrangement by attaching a 800 x 600 x 2 mm aluminium plate inside the sloping roof of his house:



The plate being suspended using nylon cord to prevent it touching the roof or anything else:

The plate is positioned between 3 and 3.5 metres (10 to 12 feet) above the ground and the attachment to the plate is also heavy-duty 8 swg cable:



The cable is connected to the aluminium plate using a brass bolt and nuts which the builder thinks may be significant, quite apart from avoiding any galvanitic connection to the circuit. The cable is then run vertically downwards to the circuit. For this arrangement a second earthing point is also used. This is a galvanised iron pipe 3 metres long, driven vertically into the ground which is saturated with water. The second earth is 2 metres away from the first earth.

This arrangement provides serious power, enough to cause injury to, or kill a careless human. With two modules, it will light an LED very brightly, driving it to 2.6 volts. If the LED is removed, then the voltage climbs to about twenty volts and is easily sufficient to charge a 12V battery or battery bank although that takes time. With twenty modules as 12V battery can be charged over night. It is estimated that with two hundred modules, the power would be sufficient to power a household although that has not yet been done. It should be borne in mind that each module is easy and cheap to make, so arranging for a stack of them where additional modules can be added at a later date for more power, is an ideal arrangement. The circuit is like this:



This circuit looks completely mad as the aerial input to the circuit appears to be directly short-circuited by the second earth connection. In spite of this, the circuit works very well when connected this way. Additional modules can be added without any known limit. Increased power can be had by either raising the aluminium plate higher above the ground, to say, 10 metres (33 feet), or by adding one or more additional aerial plates. As you have a good aerial connected through to a very good earth, there has to be the possibility of the equipment being hit by lightning, and so it is suggested that a protective spark-gap is installed between the aerial and the earth, close to the circuit, so that if high-voltage is suddenly applied to the aerial, the spark gap will fire and shunt the excess power through to the earth. Alternatively, possibly a better solution is to install a standard lightning rod system a few metres away from the aerial and a metre or two higher up, so that it forms a more attractive point for a lightning strike.

Further experimentation has shown that altering the connection point for the aerial has a significant effect on the results. If the connection is made at the mid point between the aerial plate and the earth connection, it produces a greater output:



With this arrangement a single module produces around 30 volts while the original method of connecting near the earth was giving about 26 volts with two modules.

Dragan Kljajic has been experimenting with this circuit and has started by building many of these modules on a printed circuit board like this:





Using two of these boards, Dragan is pulling 96 watts continuously from his aerial plate. He intends to extend this arrangement much further, but is being hindered at present by a local civil war.

There is a forum where some builders of this system share comments. One comment is that there is an increased risk of a lightning strike where you have an earthed aerial, and so it is advisable not to place the aerial plate inside a house, but perhaps suspended between two trees. Also, using a car spark plug connected across the module set can protect against lightning strikes damaging the circuitry.

← Truth is a commodity… Sad →

INFOWARS.COM VIDEOS:


Breaking!! Islamic Terrorist Strikes Christmas Weekend, More Attacks Planned

COMMENT ON THIS ARTICLE:

Comment rules

9 responses to *Don’t let the big energy corporations control you – Free energy is HERE*

Hendra said on April 26, 2016

Hello, I am new to this website and I am trying to build this things right now with the pcb. Has anyone successfully built this things with the PCB that Dragan make ?

THank you

Hendra

Log in to Reply

ifree said on June 1, 2012

cool. I remember reading an article about a farmer who was able to light a bunch of bulbs from a really long cable that somehow just inducted energy… this was after that idiotic show “Mythbusters” said it was impossible.. so, yeah. I don’t recommend that show.

Log in to Reply

Shaun said on June 1, 2012

I have made two of these boards but in A4 size with 32 modules on each board im in the process of drilling holes.
The alexkor circuit in Chap 7 is also worth looking at I will let you know when Im done with the Tesla /Jes Ascanius
circuit and what results I get I know its important to polish the plate and to have a very good earthing plate.

Log in to Reply

United said on May 28, 2012

Great post! thanks

Kakashi said on May 28, 2012

Is this transduction?

Log in to Reply

Kellie said on May 28, 2012

The whole article is here http://www.free-energy-info.com/Chapt7.html

Log in to Reply

WizarDave said on May 26, 2012

Gotta love Tesla!

Kellie said on July 6, 2012

Yes, and look how our great government treated him later in life up unto his death, and still to this day…Corrupticians !

Log in to Reply

ZerMaster said on May 26, 2012

Don’t forget about Tesla’s Turbine at 1PSI Steam hooked up to a generator (1PSI! think about it …) cheap to build and use. http://books.google.ro/books?id=BOMDAAAAMBAJ&pg=PA188&dq=popular+mechanics+Tesla&hl=en&sa=X&ei=BeC_T4G1FdDn-gbS-rCcCg&sqi=2&ved=0CCwQ6AEwAA#v=onepage&q=popular%20mechanics%20Tesla&f=false

http://www.youtube.com/watch?v=Oqyh-JyCmQc

Log in to Reply

Leave a reply

You must be logged in to post a comment.

BE ACTIVE
- LOGIN
- GROUPS
- MEMBERS
- F.A.Q.
- TUTORIALS

YOUR ACCOUNT
- LOGIN

MORE
- CONTACT
- WRITING TIPS
- TERMS OF SERVICE
- DIGITAL MILLENNIUM COPYRIGHT ACT

©2012 Planet.Infowars.com is a Planet Infowars, LLC company. All rights reserved - Digital Millennium Copyright Act Notice

(19) Europäisches Patentamt
European Patent Office
Office européen des brevets

(11) **EP 3 046 181 A2**

(12) **EUROPEAN PATENT APPLICATION**

(43) Date of publication:
20.07.2016 Bulletin 2016/29

(21) Application number: **15199968.7**

(22) Date of filing: **14.12.2015**

(51) Int Cl.:
H01Q 1/24 $^{(2006.01)}$ ***H01Q 9/26*** $^{(2006.01)}$
H02J 50/27 $^{(2016.01)}$

(84) Designated Contracting States:
AL AT BE BG CH CY CZ DE DK EE ES FI FR GB GR HR HU IE IS IT LI LT LU LV MC MK MT NL NO PL PT RO RS SE SI SK SM TR
Designated Extension States:
BA ME
Designated Validation States:
MA MD

(30) Priority: **23.12.2014 US 201414582033**

(71) Applicant: **Palo Alto Research Center, Incorporated**
Palo Alto, CA 94304 (US)

(72) Inventors:
- **CASSE, Bernard D.**
  Saratoga, CA 95070 (US)
- **DANIEL, George**
  Los Altos, CA 94022 (US)
- **VOLKEL, Armin R.**
  Mountain View, CA 94040 (US)
- **LIU, Victor**
  Mountain View, CA 94040 (US)

(74) Representative: **Gill Jennings & Every LLP**
The Broadgate Tower
20 Primrose Street
London EC2A 2ES (GB)

(54) MULTIBAND RADIO FREQUENCY (RF) ENERGY HARVESTING WITH SCALABLE ANTENNA

(57) A radio frequency (RF) energy harvesting device including a scalable metamaterial resonator antenna and a rectifying circuit formed on a flexible plastic substrate. The metamaterial resonator antenna includes a metal (e.g., silver) structure that is conformally fixedly disposed (i.e., either printed or deposited/etched) on the flexible substrate and configured to resonate at RF frequencies using primary and secondary antenna segments connected by linking segments such that captured RF signals are generated at two antenna end points that are 180° out-of-phase with each other. The rectifying circuit including additional metal structures that are also printed or otherwise formed on the flexible substrate, and one or more circuit elements that are configured to pass positive voltage pulses from the captured RF signals to an output node. Various metamaterial resonator antenna configurations are disclosed.



FIG. 1

EP 3 046 181 A2

Printed by Jouve, 75001 PARIS (FR)

Description

FIELD OF THE INVENTION

[0001] This invention relates to multiband radio frequency (RF) energy harvesting, and more particularly to a low-cost, scalable RF energy harvesting device.

BACKGROUND OF THE INVENTION

[0002] A rectenna (rectifying antenna) is a special type of antenna that is used to convert radio wave energy into direct current electricity. Rectennas are used in wireless power transmission systems that transmit power by radio waves. A typical rectenna element consists of a dipole antenna with a diode connected across the dipole elements. The diode rectifies the alternating current (AC) induced in the antenna by the radio waves to produce direct current (DC) power, which is then used to power a load connected across the diode. Schottky diodes are usually used because they have the lowest voltage drop and highest speed and therefore have the lowest power losses due to conduction and switching. Large rectennas consist of an array of many such dipole elements.

[0003] There exists a significant motivation to develop rectennas that efficiently capture RF energy. Due to the increasing use of radio frequency (RF) signals to transmit information, the presence of RF energy is almost ubiquitous. Moreover, the unused portions of transmitted RF signals (i.e., portions that are not captured and converted by a receiver) are essentially "wasted" in that the energy transmitted in unused RF signals is absorbed in ambient matter and thus lost. As such, in addition to providing power sources for remote/portable devices, a suitable rectenna capable of efficiently re-converting unused ambient RF energy would reduce overall energy demand by replacing batteries and other remote power sources.

[0004] Conventional rectennas capable of converting RF energy to DC power are unable to harvest most ambient RF energy. Existing RF rectennas can only produce usable DC voltages in the presence of high RF power density levels (typically above 1 W/m^2), and are therefore typically used in wireless power transmission systems where dedicated high-power transmitters generate RF energy at sufficiently high energies. Ambient RF energy is typically very low (from mW down to μW), and thus the use of conventional RF rectennas for energy harvesting has proven to be insufficient in remote locations. Also, conventional rectenna devices utilize antennas are single band (i.e., harvest narrow-band RF signals) and rectifying circuits are bulky, and therefore not scalable.

[0005] What is needed is a low-cost, high-conversion-efficiency and electrically-small RF rectenna that is capable of reliably harvesting ambient RF energy. In particular, what is needed is an RF energy harvesting device capable of harvesting multiband RF signal energy having low energy levels (i.e., tens of mW and below) including an antenna that can be scaled to accommodate different RF frequencies, thereby facilitating energy generation for remote devices (e.g., sensors) using a wide range of RF signal sources.

SUMMARY OF THE INVENTION

[0006] The present invention is directed to space-efficient RF energy harvesting devices (rectennas) that utilize novel metamaterial resonator antennas that are electrically-small and are capable of near-perfect RF energy absorption. The metamaterial resonator antenna includes one or more metal structures that are conformally fixedly disposed on a substrate (e.g., formed by printing a conductive (e.g., silver) ink or depositing/etching a metal layer) in a manner that facilitates low-cost fabrication using printed electronics techniques. The at least one metal structure forming the metamaterial resonator antenna includes two primary antenna segments and at least one secondary antenna segment that are disposed in a spaced-apart (parallel) folded arrangement and connected by two linking segments such that the overall antenna structure resonates at RF frequencies that are within an associated bandwidth range, and are configured such that captured RF signals generated at the two antenna end points are 180° out-of-phase from each other. Metamaterial resonator antennas such as those described herein can be tailored to have high impedance and exhibit near-perfect absorption. The rectifying circuit is coupled to the antenna end points, and includes circuit elements (one or more diodes, capacitors, inductors and/or resistors) that are configured to combine positive voltage pulses from the two captured RF signals to generate a usable output voltage. In some embodiments, the metamaterial resonator antenna arrangement facilitates nesting a smaller antenna within open spaces of a larger antenna, thereby facilitating capturing a wide range of RF frequencies without significantly changing the device's footprint (size), and thereby providing a highly scalable platform that facilitates remotely powering widely dispersed IC devices (e.g., sensors, processors, etc.) using either pre-existing RF signals (e.g., from ambient Wi-Fi signals) or dedicated charging RF sources. Moreover, because the metamaterial resonator antenna arrangement is formed on a substrate and can be configured for different RF frequencies, the present invention facilitates the low-cost production of RF energy harvesting device using inexpensive flexible plastic substrates and cost-effective printed electronics techniques, thereby minimizing overall manufacturing costs while maximizing the RF frequency band that can be converted into usable energy.

[0007] According to an embodiment of the invention, the rectifying circuit includes conductive structures that are conformally disposed on the substrate surface (i.e., generated during the same ink-jet printing run) with the antenna in order to further minimize manufacturing costs. In one embodiment, the rectifying circuit utilizes a conventional voltage doubler circuit (e.g., a Greinacher circuit) to combine the two captured RF signals in order to generate a usable output voltage. In a presently preferred embodiment, the rectifying circuit utilizes two dissimilar Zero Bias Schottky diodes and a capacitor that are configured to combine the two captured RF signals in a way that generates an output voltage with minimal energy loss. When the metamaterial resonator antennas of the present invention are combined with these novel rectifying circuits, the resulting RF energy harvesting devices exhibit high energy conversion efficiencies.

[0008] According to various embodiments of the present invention, the metamaterial resonator antenna is implemented using a novel two-part dipole antenna arrangement made up of two bilaterally symmetrical metal elements. In this case, each metal element includes one of the primary antenna segments, one of the linking segment, and a secondary antenna segment portion that extending from the linking segment to a distal end point located adjacent to one of the antenna end point. The primary antenna segment and the secondary antenna segment portion are concentrically arranged (i.e., such that they are separated by a uniform gap spacing), which produces the desired captured RF signal characteristics. In one series of specific embodiments, the primary and secondary segment portions are formed by straight (linear) wire segments that are connected at one or more 90° angles (corners), wherein "tuning" the antenna to resonate at a targeted RF frequency involves increasing the length of one or more of the straight segments, or utilizing two or three interconnected segments. With this arrangement, the antenna can be "tuned" to capture a wide range of RF frequencies without substantially increasing the antenna footprint. In other embodiments the primary and secondary segment portions are formed by concentric curved (e.g., semi-circular) wire segments that are connected by a linking segment. In one embodiment the linking segment is implemented using a step-shaped wire that allows the primary and secondary segments to have identical lengths.

[0009] According to various other embodiments of the present invention, the metamaterial resonator antenna is implemented using a novel "racetrack-type" configuration formed by a single contiguous metal structure having a shape similar to an oblong rectangle with rounded ends, where portions of the rounded end "curves" extends into the interior "infield" regions. In this case, the primary antenna segments are collinear and extend in opposite directions (e.g., downward and upward) from the antenna end points, a single secondary antenna segment is disposed parallel to and spaced from the primary segments, and a pair of "open circle" linking segments 123H-31/32 are used to connect the primary and secondary segments, thereby forming a racetrack-shaped structure including curved end segments extending from each of the "open circle" linking segments into the "infield" portion of the racetrack. This arrangement was found to capture RF signals over a substantially higher range than the two-part antenna design (described above), and is further "tunable" by way of changing the gap separating adjacent curved end points, or by adding one or more additional "racetracks" to the antenna structure.

[0010] The present invention is further directed to systems in which multiple RF energy harvesting devices including metamaterial resonator antennas and associated rectifying circuits are interconnected to generate a combined output voltage.

BRIEF DESCRIPTION OF THE DRAWINGS

[0011] These and other features, aspects and advantages of the present invention will become better understood with regard to the following description, appended claims, and accompanying drawings, where:

Fig. 1 is a top side perspective view showing an RF energy harvesting device according to an embodiment of the present invention;

Fig. 2 is a top side perspective view showing an RF energy harvesting device including first two-part antenna configuration according to a specific embodiment of the present invention;

Fig. 3A is a simplified diagram showing an RF energy harvesting device including the two-part antenna of Fig. 2;

Fig. 3B is a simplified diagram showing an RF energy harvesting system including three RF energy harvesting devices of Fig. 3A in a nested arrangement;

Figs. 4A, 4B and 4C are simplified diagrams showing two-part antenna configurations according to alternative specific embodiments of the present invention;

Fig. 5 is a simplified diagram showing an RF energy harvesting system utilizing two-part antennas according to another specific embodiment of the present invention;

Figs. 6A and 6B are simplified diagrams showing curved two-part antenna configurations according to alternative specific embodiments of the present invention;

Fig. 7 is a top plan view showing a "racetrack-type" metamaterial resonator antenna according to another specific embodiment of the present invention;

Fig. 8 is a simplified diagram showing an RF energy harvesting device including the "racetrack-type" antenna of Fig. 7;

Fig. 9 is a simplified diagram showing an RF energy harvesting system utilizing "racetrack-type" antennas according to another specific embodiment of the present invention; and

Figs. 10A and 10B are top plan views showing two-loop and three-loop "racetrack" antennas, respectively, according to alternative embodiments of the present invention.

DETAILED DESCRIPTION OF THE DRAWINGS

[0012] The present invention relates to an improvement in RF energy harvesting. The following description is presented to enable one of ordinary skill in the art to make and use the invention as provided in the context of a particular application and its requirements. The terms "coupled" and "connected", which are utilized herein, are defined as follows. The term "connected" is used to describe a direct connection between two circuit elements, for example, by way of a metal line formed in accordance with normal integrated circuit fabrication techniques. In contrast, the term "coupled" is used to describe either a direct connection or an indirect connection between two circuit elements. For example, two coupled elements may be directly connected by way of a metal line, or indirectly connected by way of an intervening circuit element (e.g., a capacitor, resistor, inductor, or by way of the source/drain terminals of a transistor). Various modifications to the preferred embodiment will be apparent to those with skill in the art, and the general principles defined herein may be applied to other embodiments. Therefore, the present invention is not intended to be limited to the particular embodiments shown and described, but is to be accorded the widest scope consistent with the principles and novel features herein disclosed.

[0013] Fig. 1 is a top side perspective view showing an RF energy harvesting device 100 according to a generalized embodiment of the present invention. RF energy harvesting device 100 utilizes a novel metamaterial resonator antenna 120 and a rectifying circuit 130.

[0014] Metamaterial resonator antenna 120 includes at least one metal structure 123 that is conformally fixedly disposed on a substrate 101 (e.g., formed by printing a conductive (e.g., silver) ink or depositing/etching a metal layer) in a manner that facilitates low-cost fabrication using printed electronics techniques. Metal structure 123 includes two primary antenna segments 123-1 and 123-2 and at least one secondary antenna segment 123-2 that are disposed in a spaced-apart (parallel) folded arrangement and connected by two linking segments 123-31 and 123-32. Specifically, first primary antenna segment 123-11 extends from a first antenna end point 121 to a first midpoint 123-11A, and second primary antenna segment 123-12 extends from a second antenna end point 122 to a second midpoint 123-21A. Secondary antenna segment 123-2 is disposed parallel to and spaced from the first and second primary antenna segments by a uniform gap distance S, with secondary antenna segment 123-2 having a first end disposed at a third midpoint 123-12A and an opposing second end disposed at a fourth midpoint 123-22A. First linking segment 123-31 is connected between first and third midpoints 123-11A and 123-12A, and second linking segment 123-32 connected between second and fourth midpoints 123-21A and 123-22A, with these linking segments being substantially shorter than primary and secondary segments. Each of these segments consists of an elongated metal line structure having a thickness T (e.g., 8 microns) and a line width LW (e.g., 2.5mm). By adjusting the overall length of primary antenna segments 123-11 and 123-12 and secondary antenna segment 123-2, the overall antenna structure is tailored to resonate at RF frequencies that are within an associated target bandwidth range, and are configured such that captured RF signals V_{121} and V_{122} generated at antenna end points 121 and 122 are 180° out-of-phase from each other. Metamaterial resonator antenna 120 is electrically-small and, when combined with certain rectifying circuits, facilitates near-perfect RF energy absorption. An advantage of metamaterial resonator antennas formed in accordance with the present invention, such as those described below, can be tailored to have high impedance and exhibit near-perfect absorption. The rectifying circuit 130 is coupled to the antenna end points 121/122, and includes circuit elements (one or more diodes, capacitors, inductors and/or resistors) that are configured to combine positive voltage pulses from the two captured RF signals V_{121}&V_{122} to generate a usable output voltage V_{OUT}. In some embodiments, the metamaterial resonator antenna arrangement facilitates nesting a smaller antenna within open spaces of a larger antenna, thereby facilitating capturing a wide range of RF frequencies without significantly changing the device's footprint (size), and thereby providing a highly scalable platform that facilitates remotely powering widely dispersed IC devices (e.g., sensors, processors, etc.) using either pre-existing RF signals (e.g., from ambient Wi-Fi signals) or dedicated charging RF sources. Moreover, because the metamaterial resonator antenna arrangement is formed on a substrate and can be configured for different RF frequencies, the present invention facilitates the low-cost production of RF energy harvesting device using inexpensive flexible plastic substrates and cost-effective printed electronics techniques, thereby minimizing overall manufacturing costs while maximizing the RF frequency band that can be converted into usable energy.

[0015] Referring again to Fig. 1, rectifying circuit 130 includes conductive structures 133-1 to 133-4 that are conformally disposed on the substrate surface 102 (i.e., generated during the same ink-jet printing run as that used to form antenna 120) in order to further minimize manufacturing costs. In the illustrated and presently preferred embodiment, rectifying circuit 130 utilizes two dissimilar Zero Bias Schottky diodes D1 and D2 and a capacitor C1 that are configured to combine the two captured RF signals V_{121} and V_{122} in a way that generates an output voltage V_{OUT} with minimal energy loss. Specifically, first diode D1 is coupled by way of conductive structure 133-1 between first antenna end point 121 and a first node N1 (which in this case is implemented by conductive structure 133-3. A first terminal of capacitor C1 is coupled to second antenna end point 122 by way of conductive structure 133-2, and a second terminal is connected to conductive structure 133-3 (node N1). Second diode D2 is connected between first node N1 and a second node N2, which is implemented by conductive structure 133-4. A second capacitor C2 is coupled between first antenna end point 121 and node N2, and in one embodiment conductive structure 133-1 is coupled to a ground or other voltage source. In an exemplary embodiment, diode D1 is implemented using a (first) Zero Bias Schottky diode having a very low forward voltage (e.g., 120 mV or less), a peak inverse voltage of 1.0 V or less, and a reverse current resistance of 5kΩ. Diode D2 is implemented using a (second) Zero Bias Schottky diode having a forward voltage of 150 mV or less (i.e., equal to or higher than that of diode D1), and a peak inverse voltage of at least 2.0 V (i.e., higher than that of diode D1), and a reverse current resistance of at least 10kQ (i.e., higher than that of diode D1). Capacitors C1 and C2 are either discrete (e.g., surface mounted) capacitor structures, or a fabricated capacitor structures (e.g., using printed electronics), and have a value determined in accordance with the characteristics (current and voltage) of DC output voltage V_{OUT}, and in a practical embodiment have a common capacitance value of 10pF. With this arrangement, a first intermediate voltage generated at first node N1 comprises a sum of positive voltage pulses of first RF signal V_{121}, which are passed through first diode D1, and second AC signal V_{122}, which is passed through first capacitor C1. With this arrangement, a second intermediate voltage is generated at second node N2 in accordance with positive voltage pulses that are passed from the first node N1 through the second diode D2. When the metamaterial resonator antennas of the present invention are combined with this novel rectifying circuit, the resulting RF energy harvesting devices exhibit high energy conversion efficiencies than when conventional rectifying circuits are utilized. However, in other embodiments (not shown), RF energy harvesting devices including the metamaterial resonator antennas of the present invention and conventional rectifying circuits (e.g., using a voltage doubler circuit, such as a Greinacher circuit, to combine the two captured RF signals) may be beneficially utilized to generate a usable output voltage.

[0016] Fig. 2 is a top side perspective view showing an RF energy harvesting device 100A including an open C-shaped two-part antenna 120A formed by metal structures that are conformally disposed on upper surface 102A of flexible plastic substrate 101A. Antenna 120A represents a first example of a two-part dipole antenna arrangement made up of two bilaterally symmetrical metal elements 123A-1 and 123A-2. Metal element 123A-1 includes a first primary antenna segment 123A-11 extending from first antenna end point 121A, a first linking segment 123A-13 attached to the end of primary antenna segment 123A-11, and a first secondary antenna segment 123A-12 extending from linking segment 123A-13 to a first distal end point 123A-13A disposed adjacent to first antenna end point 121A. Note that first primary antenna segment 123A-11 and first secondary antenna segment 123A-12 are concentrically arranged such that a uniform gap spacing GS separates first primary antenna segment 123A-11 and first secondary antenna segment 123A-12 along their entire length. Similarly, second metal element 123A-2 includes a second primary antenna segment 123A-21 extending from second antenna end point 122A, a second linking segment 123A-23, and a second secondary antenna segment 123A-22 extending from second linking segment 123A-23 to a second distal end point 123A-23A disposed adjacent to second antenna end point 122A, where second primary antenna segment 123A-21 and second secondary antenna segment 123A-22 are also concentrically arranged and separated by gap spacing GS along their entire length. Metal elements 123A-1 and 123A-2 collectively form an open C-shaped pattern surrounding central region 127 on three sides.

[0017] Fig. 3A is a simplified diagram showing RF energy harvesting device 100A of Fig. 2, where device 100A shows open C-shaped two-part antenna 120A using simple line structures in order to simplify the description of other embodiments set forth below. That is, Fig. 3A shows in simplified form antenna 120A coupled to a generalized rectifying circuit 130A, where primary antenna segments 123A-11 and 123A-21, secondary segments 123A-12 and 123A-22, and linking segments 123A-13 and 123A-23 are indicated by solid black lines. As further illustrated in Fig. 3A, each of primary antenna segments 123A-11 and 123A-21 and secondary segments 123A-12 and 123A-22 comprises at least two linear segments connected by a corner portion. For example, referring to the upper portion of Fig. 3A, second primary antenna segment 123A-21 includes two linear segments 123A-211 and 123A-212 connected by a corner (90° angle) portion 123A-21A.

[0018] Fig. 3B is a simplified diagram showing an RF energy harvesting system 200A including three RF energy harvesting devices 100A-1, 100A-2 and 100A-3 configured in a nested arrangement that illustrates an advantage of the open C-shaped configuration of antenna 120A (described above). Specifically, devices 100A-1, 100A-2 and 100A-3 respectively include three open C-shaped antennas 120A-1, 120A-2 and 120A-3, each coupled to an associated rectifying circuit 130A-1, 130A-2 and 130A-3 facilitate generate an combined system output voltage $V_{OUT-SYS}$ utilizing, for example, a parallel configuration similar to that described below with reference to Fig. 5. As illustrated in Fig. 3B, an advantage to forming metamaterial resonant antennas using the open C-shaped configuration described above is that multiple antennas of different sized can be concentrically "nested", which facilitates capturing RF energy over a wide range of RF frequencies without increasing the overall device/system footprint. That is, because antennas 120A-1, 120A-2 and 120A-3 have different sizes, each has a different inductance and hence resonates at a different RF frequency. By nesting antennas 120A-2 and 120A-3 inside the footprint of antenna 120A-1, system 200A facilitates capturing energy over a wider range of RF frequencies than would be possible using antenna 120A-1 alone, without increasing the substrate area required for antenna 120A.

[0019] Figs. 4A, 4B and 4C are simplified diagrams showing three additional two-part dipole antenna configurations that illustrate other approaches (i.e., in addition to increasing antenna size, as illustrated in Fig. 3B) for tailoring antenna inductance according to alternative specific embodiments of the present invention. In each case, the primary antenna segments and and secondary antenna segments include three interconnected linear sections that collectively form a C-shaped pattern, where dimensions of the three linear sections are changed to illustrate how metamaterial resonator antennas are tailored to achieve difference inductance values, whereby the antennas are altered to resonate at (and thereby collect energy from) different RF frequencies. For example, referring to Fig. 4A, antenna 120B includes primary segments 123B-11 and 123B-21 and secondary segments 123B-12 and 123B-22 that are connected by linking sections 123B-13 and 123B-23 in a manner similar to that described above with reference to antenna 120A (Fig. 2). Assuming the overall length L and width X1 of antenna 120B is the same as that of antenna 120A (Fig. 2), Fig. 4A illustrates that the inductance of antenna 120B can be tailored to achieve different inductances with little or minimal change to the overall antenna footprint by adding a third (vertical) section to each of the primary and secondary antenna segments. For example, second primary antenna segment 123B-21 includes three interconnected linear sections 123B-211, 123B-212 and 123B-213 that form a C-shaped pattern, where vertical antenna section 123B-213 increases the length of primary antenna segment 123B-21 by length Y1 without increasing the overall footprint of antenna 120B. Fig. 4B indicates that further tailoring is achieved by further lengthening these third (vertical) sections. Antenna 120C includes three-section primary segments 123C-11 and 123C-21 and secondary segments 123C-12 and 123C-22 that are connected by linking sections 123C-13 and 123C-23 in a manner similar to that of antenna 120B (Fig. 4A), however the inductance of antennal 120C is altered by way of lengthening the additional section. Specifically, second primary antenna segment 123C-21 includes three interconnected linear sections 123C-211, 123C-212 and 123C-213, where vertical antenna section 123C-213 has a length Y2 that increases the inductance of antenna 120C over that of antenna 120B without increasing the overall footprint of antenna 120C. Fig. 4C illustrates antenna 120D, which achieves even higher inductance by way of lengthening the horizontal sections of primary segments 123D-11 and 123D-21 and secondary segments 123D-12 and 123D-22 to width X2. For example, second primary antenna segment 123D-21 includes three interconnected linear sections 123D-211, 123D-212 and 123D-213, where horizontal antenna section 123D-212 has a width X2 that increases the inductance of antenna 120D over that of antenna 120C without significantly increasing the overall footprint of antenna 120C.

[0020] Fig. 5 is a simplified circuit diagram showing a RF energy harvesting system 200E including RF energy harvesting devices 100E-1, 100E-2 and 100E-3 that are connected in parallel between common ground sources and common system output nodes to maximize the current level of the system output voltage $V_{OUT-SYS}$. To facilitate the generation of combined system output voltage $V_{OUT-SYS}$, devices 100E-1, 100E-2 and 100E-3 respectively include similar rectifying circuits 130E-1, 130E-2 and 130E-3 that are optimized to provide their respective output voltages V_{OUT1} to V_{OUT3} in a manner that facilitates combination. Each rectifying circuit 130E-1, 130E-2 and 130E-3 includes diodes D1 and D2 and capacitors C1 configured as described above with reference to Fig. 1. In addition, rectifying circuits 130E-1, 130E-2 and 130E-3 are similar in that they respectively include output control circuits 135E-1, 135E-2 and 135E-3 configured to convert the intermediate voltage generated at node N2 into DC output voltages V_{OUT1} to V_{OUT3}. To facilitate combining these output voltages, output control circuits 135E-1, 135E-2 and 135E-3 include a (second) capacitor C2 that has essentially the same capacitance as capacitors C1, a third diode D3 and a storage capacitor C4 that are configured to store DC output voltages V_{OUT1} to V_{OUT3} for combination at system output node $V_{OUT-SYS}$. For example, referring to output control circuit 135E-1, diode D3 is connected between nodes N2 and N3 (which serves as an output node for rectifying circuit 130E-1), a first terminal of storage capacitor C4 is connected to node N3, and a resistor R2 connected between a second terminal of storage capacitor C4 and first antenna end point 121A (e.g., to the applied ground potential). In a practical embodiment, diode D3 is implemented using the same diode element as that utilized to implement diode D2 (e.g., a HSMS2850 Surface Mount Zero Bias Schottky Detector Diode manufactured by Agilent Technologies of Santa Clara, CA, USA). Capacitor C3 is implemented using a capacitive element sized in accordance with the characteristics (current and voltage) of DC output voltage V_{OUT}, and the size and characteristics of the system voltage present on system output node $V_{OUT-SYS}$. In an exemplary practical embodiment, utilizing the diode and capacitor component values mentioned above, capacitor C3 has a capacitance of 100pF, and resistor R2 has a nominal resistive value of 1Ω. Output control circuit 135E-2 and 135E-3 are configured identically to output control circuit 135E-1.

[0021] According to an aspect of the embodiment shown in Fig. 5, each device 100E-1, 100E-2 and 100E-3 includes a different two-part dipole metamaterial resonator antenna 120A, 120B and 120C, whereby devices 100E-1, 100E-2 and 100E-3 are configured to convert RF energy having different frequencies into output voltages V_{OUT1}, V_{OUT2} and V_{OUT3}. Two-part dipole metamaterial resonator antenna 120A, 120B and 120C are described in detail above. Because antennas 120A, 120B and 120C have different configurations (sizes), each generates an output voltage dependent on the availability of sufficient RF energy at the frequencies to which each antenna resonates. System 200E is therefore configured to generate output current over a much broader RF frequency range than would be possible using a single antenna by utilizing three different antenna arrangements.

[0022] Figs. 6A and 6B are simplified diagrams showing two curved two-part metamaterial resonator antennas 120F and 120G according to additional alternative specific embodiments of the present invention. Similar to the straight-section embodiments described above, each antenna 120F and 120G includes two bilaterally symmetrical metal elements 123F-1 and 123F-2 and 123G-1 and 123G-2, each including concentric, continuously-curved (e.g., substantially semi-circular) primary and secondary segments wire segments that are connected by a short linking segment.

[0023] Referring to Fig. 6A, metal element 123F-1 of antenna 120F includes a curved primary segment 123F-11 extending from antenna end point 121F to a (first) midpoint 123A-11A, a straight linking segment 123F-13 extending from midpoint 123F-11A to midpoint 123F-12A, and a curved secondary antenna segment 123F-12 extending from the second midpoint 123F-12A to a distal end point 124F-13A. Curved primary segment 123F-11 and curved secondary antenna segment 123F-12 are concentrically arranged such that they are separated along their entire length by a uniform gap spacing GS. Similarly, metal element 123F-2 includes a curved primary segment 123F-21 extending from antenna end point 121F to straight linking segment 123F-23, and a curved secondary antenna segment 123F-22 extending from linking segment 123F-23 to a distal end point 124F-23A, where curved primary segment 123F-21 and curved secondary antenna segment 123F-22 are concentrically arranged.

[0024] Referring to Fig. 6B, metal element 123G-1 of antenna 120G also includes a curved primary segment 123G-11 extending from antenna end point 121G to a midpoint 123A-11A, a straight linking segment 123G-13 extending from midpoint 123G-11A to midpoint 123G-12A, and a curved secondary antenna segment 123G-12 extending from the second midpoint 123G-12A to a distal end point 124G-13A, with curved primary segment 123G-11 and curved secondary antenna segment 123G-12 being concentrically arranged, and metal element 123G-2 includes a curved primary segment 123G-21 extending from antenna end point 122G to straight linking segment 123G-23, and a curved secondary antenna segment 123G-22 extending from linking segment 123G-23 to a distal end point 124G-23A, where curved primary segment 123G-21 and curved secondary antenna segment 123G-22 are concentrically arranged. Antenna 120G differs from antenna 120F in that, where linking segments 123F-13 and 123F-23 of antenna 120F are implemented by straight (linear shaped) wire structures, linking segments 123G-13 and 123G-23 of antenna 120G comprise two-segment step-shaped wire structures arranged such that the length primary antenna segments 123G-11 and 123G-21 is equal to the lengths of first secondary antenna segments 123G-12 and 123G-22, which facilitates improved antenna performance.

[0025] Fig. 7 is a top plan view showing a "racetrack-type" metamaterial resonator antenna 120H according to another specific embodiment of the present invention. Unlike the two-part dipole embodiments described above, antenna 120H has a single-piece (integral, contiguous) metal element 123H including (first and second) primary antenna segments 123H-11 and 123H-12 disposed on a first side of the "racetrack", a secondary antenna segment 123H-2 disposed on the second side of the "racetrack", and two open-circle linking segments 12H-31 and 123H-32 forming the two "curves" of the "racetrack". Primary antenna segments 123H-11 and 123H-12 are linear metal structures that are collinearly arranged and separated by a gap GW defined between the first and second antenna end points 121H and 122H. That is, referring to Fig. 7, primary antenna segment 123H-11 extends straight downward from end point 121H to a first midpoint 123H-11A, and primary antenna segment 123H-21 extends upward from end point 122H to a second midpoint 123H-21A. Secondary antenna segment 123H-2 is a continuous metal structure disposed parallel to and spaced at a distance S from primary antenna segments 123H-11 and 123-12, and extends substantially the entire length L between third and fourth midpoints 123H-12A and 123H-22A. Linking segment 123H-31 includes a semi-circular section 123H-311 connected between a lower end of primary antenna segment 123H-11 and a lower end of secondary antenna segment 123H-2 (i.e., between midpoints 123H-11A and 123H-12A), and (first and second) curved end sections 123H-312 and 123H-313 extending from semi-circular section 123H-311 into space 127 (i.e., into a region between primary antenna segment 123H-11 and secondary antenna segment 123H-2). Linking segment 123H-32 includes a semi-circular section 123H-321 connected between upper ends of second primary antenna segment 123H-12 and secondary antenna segment 123H-2 (i.e., between midpoints 123H-21A and 123H-22A), and (third and fourth) curved end sections 123H-322 and 123H-323 extending from semi-circular section 123H-321 into space 127. The resulting "racetrack-type" antenna configuration resonates at an associated bandwidth range such that captured RF signals generated on antenna end points 121H and 122H are 180° out-of-phase from each other. An advantage provided by antenna 120H is that this "racetrack-type" antenna configuration was found to capture RF signals over a substantially higher frequency range than the two-part dipole antenna configurations described above. Similar to the two-part configurations, the impedance of antenna 120H is tunable by way of increasing or decreasing the antenna footprint (size). In addition, the "racetrack-type" antenna configuration facilitates further "tunability" without changing the overall footprint by way of changing the gaps separating the curved end sections (e.g., the distance separating end sections 123H-322 and 123H-323), or by adding one or more additional "racetrack loops" to the antenna structure, as described in additional detail below. In a practical embodiment, a "racetrack-type" antenna was formed by the present inventors using silver ink (10$\mu\Omega$/cm) disposed on a PET substrate (250μm thick) with segments having a thickness of 8μm and line widths LW of 2.5mm, where racetrack structure included a straight-section length L of 120mm and linking segments having an inner radius r of 6.45mm (i.e., having an overall antenna length of approximately 5.8 inches), with the curved end segments formed using an opening angle φ of 60°, and with a gap width GW of 2.5mm. The resulting structure was found to resonate with peak efficiency at 914 MHz, and exhibited less than 10% loss in accepted power in the range of approximately 825 MHz to 1050 MHz.

[0026] Fig. 8 is a simplified diagram showing an RF energy harvesting device 100H including "racetrack-type" metamaterial resonator antenna 120H of Fig. 7. In this case, rectifying circuit 130H includes two discrete inductors L1H and L2H that are needed to facilitate proper transmission of captured RF signals to the other elements of rectifying circuit 130H. Specifically, inductor L1H is coupled between first antenna end point 121H and diode D1, and inductor L2H is coupled between antenna end point 122H and capacitor C1. In one embodiment, inductors L1H and L2H have the same (common) inductance value, and form a balanced circuit with antenna 120H and the elements of rectifying circuit 130H (i.e., capacitor C1, diodes D1 and D2, and output control circuit 135H, which may be implemented using any of the configurations described in copending application serial number 14/582,002 entitled "RECTIFYING CIRCUIT FOR MULTIBAND RADIO FREQUENCY (RF) ENERGY HARVESTING" [Attorney Docket No. 20140443US01 (XCP-203-1)], which is incorporated herein by reference in its entirety.

[0027] Fig. 9 is a simplified diagram showing an RF energy harvesting system 200H made up of three devices 100H-1, 100H-2, and 100H-3 respectively including "racetrack-type" metamaterial resonator antennas 120H-1 to 120H-3, where the output terminals of devices 100H-1, 100H-2, and 100H-3 are connected in series such that the second antenna end point of at least one RF energy harvesting device is connected to the output node of an adjacent RF energy harvesting device. According to an aspect of the disclosed embodiment, each energy harvesting device 100H-1 to 100H-3 includes a substantially identical "racetrack" antenna configuration. For example, device 100H-1 includes "racetrack" antenna 120H-1 configured as described above to resonate at RF frequencies within an associated bandwidth range. Device 100H-2 includes antenna 120H-2 and device 100H-3 includes antenna 120H-3, where antennas 120H-2 and 120H-3 are substantially identical in configuration with antenna 120H-1 (i.e., such that all three antennas resonate at the same RF frequency, and such that all three antennas generate substantially the same amount of energy). Each energy harvesting device 100H-1 to 100H-3 also includes a substantially identical rectifying circuit. For example, device 100H-1 includes rectifying circuit 130H-1 including a first diode D1 coupled between antenna end point 121H-1 and a first node N1, a first capacitor C1 coupled between end point 122H-1 and node N1, and a second diode D2 connected between node N1 and a second node N2. Rectifying circuit 130H-1 also includes an output control circuit 135H-1 coupled to node N2 that is configured (i.e., by way of third diode D3, second capacitor C2 that has the same capacitance as capacitor C1, and storage capacitor C4) to convert the intermediate voltage generated on node N2 into DC output voltage V_{OUT1}. Similarly, energy harvesting devices 100H-2 and 100H-3 respectively include rectifying circuits 130H-2 and 130H-3 having diodes D1 and D2 and capacitor C1, and output control circuits 135H-2 and 135H-3 including diodes D3 and capacitors C2 and C4) that generate respective DC output voltages V_{OUT2} and V_{OUT3}.

[0028] According to the series-connected arrangement implemented by system 200H, RF energy harvesting devices 100H-1 to 100H-3 are connected such that DC output voltages V_{OUT1}, V_{OUT2} and V_{OUT3} are combined such that system output voltage $V_{OUT-SYS}$ is maximized. Specifically, first antenna end point 121H-2 of RF energy harvesting device 100H-2 is connected to the output node of RF energy harvesting device 100H-3 (i.e., such that the ground plane of device 100H-2 is DC output voltage V_{OUT3}), whereby a voltage level of DC output voltage V_{OUT2} generated at the output node of device 100H-2 is "boosted" by DC output voltage V_{OUT3}. Similarly, antenna end point 121H-1 of RF energy harvesting device 100H-1 is connected to the output node of RF energy harvesting device 100H-3, whereby a voltage level of DC output voltage V_{OUT3} generated at the output node of device 100H-1 is "boosted" by DC output voltages V_{OUT2} and V_{OUT3}. Hence, the voltage level of system output voltage $V_{OUT-SYS}$ is maximized by the series arrangement.

[0029] Although not illustrated, it is understood that the "racetrack-type" antenna configuration may also be used in a nested-device arrangement similar to that shown and described above with reference to Fig. 3B.

[0030] Figs. 10A and 10B are top plan views respectively showing a two-loop "racetrack-type" metamaterial resonator antenna 120J and a three-loop "racetrack" "racetrack-type" metamaterial resonator antenna according to alternative embodiments of the present invention. In addition to tailoring the impedance of a racetrack antenna by altering the length and radius diameters of the "racetrack" shape, and by changing the gap distance between the curved end portions (as described above), it is also possible to tailor the antenna's impedance by way of adding one or more additional "loop" structures (i.e., such that the single integral metal antenna structure includes two or more "loops" as described below).

[0031] Referring to Fig. 10A, similar to the embodiment described above with reference to Fig. 7, antenna 120J includes a first "loop" structure surrounding region 127-1 formed by primary antenna segments 123J-11 and 123J-12 respectively extending from end points 121J and

122J, a (first) secondary antenna segment 123J-21, and (first and second) circular linking segments 123J-31 and 123J-32, which are configured in the manner described above with reference to Fig. 7. In addition, antenna 120J includes a second "loop" structure surrounding region 127-2 formed by first secondary antenna segment 123J-21, a second secondary antenna segment 123J-22 disposed parallel to primary antenna segments 123J-11 and 123J-12 and to first secondary antenna segment 123J-21 (i.e., such that first secondary antenna segment 123J-21 is between primary antenna segments 123J-11 and 123J-12 and second secondary antenna segment 123J-22), a (third) linking segment 123J-33 including a third semi-circular section 123J-331 connected between the first lower end of the first secondary antenna segment 123J-21 and a first lower end of the second secondary antenna segment 123J-22, and (fifth and sixth) curved end sections 123J-332 and 123J-333 extending from third semi-circular section 123J-331 into region 127-2, and a (fourth) linking segment 123J-34 including a fourth semi-circular section 123J-341 connected between an upper end of secondary antenna segment 123J-22 and an upper end of the secondary antenna segment 123J-21, and (seventh and eight) curved end sections 123J-342 and 123J-343 extending from semi-circular section 123J-341 into space 127-2. The addition of the second "loop" structure increases the overall inductance of antenna 120J over that of antenna 120H (Fig. 7), whereby antenna 120J is tailored to resonate at a different RF frequency than antenna 120H.

[0032] Referring to Fig. 10B, similar to the embodiment described with reference to Fig. 10A, antenna 120K includes a first "loop" structure formed by primary antenna segments 123J-11 and 123J-12 extending from end points 121K and 122K, respectively, a (first) secondary antenna segment 123J-21, and (first and second) circular linking segments 123J-31 and 123J-32, and a second "loop" structure formed by (first) secondary antenna segment 123J-21, a (second) secondary antenna segment 123J-22, and (third and fourth) circular linking segments 123J-33 and 123J-34. In addition, antenna 120J includes a third "loop" structure formed by (second) secondary antenna segment 123J-22, a (third) secondary antenna segment 123J-23, a (fifth) linking segment 123J-35 connecting lower ends of second antenna segments 123J-22 and 123J-23, and a (sixth) linking segment 123J-36 connecting upper ends of second antenna segments 123J-22 and 123J-23. The addition of the third "loop" structure further increases the overall inductance of antenna 120K over that of antenna 120J (Fig. 10A).

[0033] Although fabrication costs associated with producing the RF energy harvesting devices/systems of the present invention are minimized using the printing techniques described above, many of the benefits described herein may be achieved using other fabrication techniques. For example, the antenna and rectifying circuit may be fabricated using normal printed circuit board methods on either rigid or flexible substrate. Alternatively, the devices systems may be formed by machining or sintering.

[0034] Although the present invention has been described with respect to certain specific embodiments, it will be clear to those skilled in the art that the inventive features of the present invention are applicable to other embodiments as well, all of which are intended to fall within the scope of the present invention.

Claims

1. A radio frequency (RF) energy harvesting device comprising:

    a substrate having a substantially planar surface;
    a metamaterial resonator antenna including at least one metal element that is conformally fixedly disposed on the surface of the substrate, said at least one metal element including:

        a first primary antenna segment extending from a first antenna end point to a first midpoint,
        a second primary antenna segment extending from a second antenna end point to a second midpoint,
        at least one secondary antenna segment disposed parallel to and spaced from the first and second primary antenna segments by a uniform gap distance, said at least one secondary antenna segment having a first end disposed at a third midpoint and an opposing second end disposed at a fourth midpoint,
        a first linking segment connected between the first and third midpoints, and
        a second linking segment connected between the second and fourth midpoints,

    wherein the first and second primary antenna segments and said at least one secondary antenna segment are configured to resonate at RF frequencies that are within an associated bandwidth range such that a first captured RF signal is generated on the first antenna end point and a second captured RF signal is generated on the second antenna end point, said first capture RF signal being 180° out-of-phase from the second captured RF signal; and
    a rectifying circuit coupled to the first and second antenna end points, said rectifying circuit including circuit elements configured to pass positive voltage pulses from said first and second captured RF signals to an output node.

2. The RF energy harvesting device of Claim 1, wherein

said at least one elongated metal structure forming said metamaterial resonator antenna comprise a silver ink material.

3. The RF energy harvesting device of Claim 1, wherein said rectifying circuit further comprises a plurality of conductive structures conformally fixedly disposed on the surface of the substrate.

4. The RF energy harvesting device of Claim 3, wherein said rectifying circuit further comprises:

a first diode coupled between the first antenna end point and a first node;
a first capacitor coupled between the second antenna end point and the first node; and
a second diode coupled between the first node and a second node,
wherein the first diode has a lower forward voltage than the second diode, and the first diode has a lower reverse voltage than the second diode, whereby a first intermediate voltage generated at the first node comprises a sum of positive voltage pulses of the first RF signal that are passed through the first diode and the second AC signal passed through the first capacitor, and whereby a second intermediate voltage is generated at the second node in accordance with positive voltage pulses that are passed from the first node through the second diode.

5. The RF energy harvesting device of Claim 3, wherein said rectifying circuit comprises a Greinacher circuit.

6. The RF energy harvesting device of Claim 1, wherein said antenna comprises a two-part dipole antenna including first and second bilaterally symmetrical metal elements:

wherein said first metal element includes said first primary antenna segment, said first linking segment, and a first secondary antenna segment extending from the first linking segment to a first distal end point disposed adjacent to the first antenna end point, said first primary antenna segment and said first secondary antenna segment being concentrically arranged such that a uniform gap spacing separates the first primary antenna segment and said first secondary antenna segment along their entire length; and
wherein said second metal element includes said second primary antenna segment, said second linking segment, and a second secondary antenna segment extending from the second linking segment to a second distal end point disposed adjacent to the second antenna end point, said second primary antenna segment and said second secondary antenna segment being concentrically arranged such that said uniform gap spacing separates the second primary antenna segment and said second secondary antenna segment along their entire length.

7. A radio frequency (RF) energy harvesting system including a plurality of RF energy harvesting devices, each RF energy harvesting device comprising:

a metamaterial resonator antenna including at least one metal element that is conformally fixedly disposed on the surface of a substrate, said at least one metal element including:

a first primary antenna segment extending from a first antenna end point to a first midpoint,
a second primary antenna segment extending from a second first antenna end point to a second midpoint,
at least one secondary antenna segment disposed parallel to and spaced from the first and second primary antenna segments by a uniform gap distance, said at least one secondary antenna segment having a first end disposed at a third midpoint and an opposing second end disposed at a fourth midpoint,
a first linking segment connected between the first and third midpoints, and
a second linking segment connected between the second and fourth midpoints,
wherein the first and second primary antenna segments and said at least one secondary antenna segment are configured to resonate at RF frequencies that are within an associated bandwidth range such that a first captured RF signal is generated on the first antenna end point and a second captured RF signal is generated on the second antenna end point, said first capture RF signal being 180° out-of-phase from the second captured RF signal; and
a rectifying circuit coupled to the first and second antenna end points, said rectifying circuit including circuit elements configured to pass positive voltage pulses from said first and second captured RF signals to an output node,
wherein the plurality of RF energy harvesting devices are coupled together to generate a combined system output voltage.

8. A metamaterial resonator antenna comprising at least e metal element including:

a first primary antenna segment extending from

a first antenna end point to a first midpoint,
a second primary antenna segment extending from a second antenna end point to a second midpoint,
at least one secondary antenna segment disposed parallel to and spaced from the first and second primary antenna segments by a uniform gap distance, said at least one secondary antenna segment having a first end disposed at a third midpoint and an opposing second end disposed at a fourth midpoint,
a first linking segment connected between the first and third midpoints, and
a second linking segment connected between the second and fourth midpoints,

wherein the first and second primary antenna segments and said at least one secondary antenna segment are configured to resonate at frequencies that are within an associated bandwidth range such that a first captured signal is generated on the first antenna end point and a second captured signal is generated on the second antenna end point, said first capture signal being 180° out-of-phase from the second captured signal.

9. The metamaterial resonator antenna of Claim 8, wherein said at least one metal element comprises a single integral metal element comprising:

said first and second primary antenna segments comprising linear structures that are collinearly arranged and separated by a gap defined between the first and second antenna end points;
said secondary antenna segment disposed parallel to the first and second primary antenna segment;
said first linking segment comprising a first open-circle pattern including a first semi-circular section connected between the first primary antenna segment and a first end of the secondary antenna segment, and first and second curved end sections extending from said first semi-circular section into a space between said first primary antenna segment and the secondary antenna segment, and
said second linking segment comprising a second open-circle pattern including a second semi-circular section connected between the second primary antenna segment and a second end of the secondary antenna segment, and third and fourth curved end sections extending from said second semi-circular section into a space between said second primary antenna segment and the secondary antenna segment.


V$_{122}$
V$_{OUT}$
V$_{121}$
100
101
102
130
123-21A
123
LW
123-32
123-22A
S
123-12
127
122
121
123-2
123-11
123-31
T
123-12A
123-11A
133-2
C1
133-3
N1
D1
133-1
D2
N2
133-4
C2

FIG. 1


100A
102A
101A
123A-2
123A-21
123A-21A
W
H
122A
TO
RECTIFYING
CIRUIT
123A-22
123A-23A
GS
121A
123A-23
127A
GW
123A-13A
123A-11
123A-22A
L
123A-13
T
120A
123A-2
123A-1
123A-12A
123A-11A
123A-12

FIG. 2


100A
123A-211
123A-23
123A-21A
123A-21A
123A-21
123A-211
123A-22A
123A-22
122A
123A-23A
RECTIFYING CIRCUIT
130A
V_{OUT}
TO LOAD
123A-13A
123A-12
121A
123A-12A
123A-13
123A-11
123A-11A

FIG. 3A


200A
100A-1
120A-1
100A-2
120A-2
100A-3
130A-3
130A-2
130A-1
120A-3
RC
V_{OUT1}
RC
V_{OUT1} + V_{OUT2}
RC
$V_{OUT-SYS}$

FIG. 3B


120B
123B-212
123B-212
123B-21
123B-211
X1
Y1
123B-22
123B-23
122B
L
123B-23B
123B-13B
123B-13
123B-12
121B
123B-11

FIG. 4A


120C
123C-21
123C-212
123C-212
123C-211
X1
Y2
123C-22
122C
123C-23
123C-13
121C
123C-12
Y1
123C-11

FIG. 4B


120D
123D-21
123D-212
123D-212
123D-211
X2
123D-22
122D
121D
123D-12
123D-11

FIG. 4C


200E
100E-1
120A
130E-1
C1
135E-1
D1
N2
N3
V_{OUT1}
122A
121A
N1
D2
D3
C2
C4
100E-2
120B
130E-2
C1
135E-1
D1
V_{OUT2}
D2
D3
$V_{OUT-SYS}$
C2
C4
100E-3
120C
130E-3
C1
135E-3
D1
V_{OUT3}
D2
D3
C2
C4

FIG. 5


120F
GS
123F-21
123F-22
123F-2
123F-23
123F-23A
122F
123F-11A
123F-12A
123F-13A
123F-13
123F-1
121F
123F-12
123F-11

FIG. 6A


120G
123G-21
123G-2
123G-22
122G
123G-23
123G-23A
123G-13
123G-13A
123G-12A
121G
123G-1
123G-12
123G-11

FIG. 6B


120H
123H-323
123H-321
123H-322
123H-32
123H-22A
r
123H-21A
φ
123H
S
123H-12
LW
123H-2
127
122H
L
GW
121H
123H-11
123H-11A
123H-12A
123H-312
123H-311
123H-313
123H-31

FIG. 7


100H
123H
RECTIFYING
CIRCUIT 130H
C1
D1
N1
122H
L2H
120H
121H
L1H
D2
OUTPUT
VOLTAGE
CONTROL
CIRCUITRY
135H

FIG. 8


200H
120H-1
100H-1
130H-1
C1
135H-1
VOUT1
D1
122H-1
D2
D3
VOUT-SYS
121H-1
C2
C4
100H-2
120H-2
130H-2
C1
135H-1
D1
D2
D3
VOUT2
121H-2
C2
C4
100H-3
120H-3
130H-3
C1
135H-3
D1
D2
D3
VOUT3
C2
C4

FIG. 9


120J
123H-343
123J-34
123J-341
123H-342
123J-32
123J-2
123J-22
123J-21
122J
127-2
127-1
121J
123J-1
123H-332
123J-33
123J-331
123H-333
123J-31

FIG. 10A


120K
123K-36
123K-34
123K-32
123K-2
123K-22
123K-21
122K
123K-23
121K
123K-1
123K-35
123K-33
123K-31

FIG. 10B

REFERENCES CITED IN THE DESCRIPTION

This list of references cited by the applicant is for the reader's convenience only. It does not form part of the European patent document. Even though great care has been taken in compiling the references, errors or omissions cannot be excluded and the EPO disclaims all liability in this regard.

Patent documents cited in the description

- WO 14582002 A **[0026]**



4/6
45c
AS

BECK BOOK CO. LTD.
New and Secondhand Booksellers
53 PULTENEY STREET,
ADELAIDE, S.A.

THE BOY'S BOOK OF CRYSTAL SETS

with practical circuits

by
W. J. MAY

Medium, Long, and Short Wave designs
12 different circuits to suit all areas and conditions · Complete practical wiring diagrams
Comprehensive information on Aerial and Earth Installation · There are suitable designs for the beginner and advanced constructor

BERNARDS RADIO MANUALS

126

THE BOY'S BOOK of CRYSTAL SETS

BY

W. J. MAY

⁂

BERNARDS (PUBLISHERS) LTD.
THE GRAMPIANS
WESTERN GATE
LONDON W.6

General Editor
WALTER J. MAY

First Published—March, 1954
Second Impression—June, 1954
Third Impression—April, 1955
Fourth Impression—January, 1956
Fifth Impression—February, 1957
Sixth Impression—August, 1957
Seventh Impression—March, 1958
Eighth Impression—October, 1958
Ninth Impression—April, 1959
Tenth Impression—December, 1959
Eleventh Impression—April, 1960
Twelfth Impression—October, 1960
Thirteenth Impression—March, 1961
Fourteenth Impression—August, 1961
Fifteenth Impression—January, 1962
Sixteenth Impression—November, 1962
Seventeenth Impression—August, 1963
Eighteenth Impression—September, 1964

⁂

Printed by V. Cooper & Partners, Ltd., Flitcroft St., W.C.2
for Bernards (Publishers) Ltd., The Grampians, Western Gate, London, W.6

CONTENTS

Page

Preface - - - - - 4

Introduction - - - - 5

Receiver No. 1 - - - - 12

Receiver No. 2 - - - - 13

Receiver No. 3 - - - - 14

Receiver No. 4 - - - - 16

Receiver No. 5 - - - - 19

Receiver No. 6 - - - - 20

Receiver No. 7 - - - - 23

Receiver No. 8 - - - - 24

Receiver No. 9 - - - - 26

Receiver No. 10 - - - - 27

Receiver No. 11 - - - - 30

Receiver No. 12 - - - - 31

PREFACE

The Publishers make no apology for reviving interest in the crystal set. For too long the technical press has immersed itself in an orgy of complex superheterodyne receivers and television equipment, all of which is necessarily expensive. In the 1920's, crystal set construction was a fascinating and inexpensive pastime indulged in by the majority of boys of that day. Today this pleasurable hobby can be even more attractive, the introduction of the germanium crystal diode and high performance coils, has opened up new paths which will capture the interest of boys of all ages. Perhaps most important of all. not only can a receiver capable of impeccable reproduction be produced without any technical knowledge; but the cost is no greater than that of a few visits to the cinema

❦

INTRODUCTION

Before any attempt is made to construct a receiver, it is necessary to examine the problems which surround the crystal set, so that the best can be obtained from any of the designs attempted.

Firstly, it must be understood that the crystal set as it is to-day does **not** provide any amplification. It relies entirely on what is fed into it via the aerial and earth system and gives a very faithful replica of the original transmission.

From this it will be obvious that the aerial and earth system must be as efficient as possible if the final results are to be in any way outstanding. This because these are the only means by which the signals are fed to the receiver.

Secondly it is necessary to understand the nature of the transmitted signal, then it will be easy to understand the working of the set and to appreciate the function of each of the components.

When crystal sets first became popular, very little information was generally available, at least, not in a form that school-boys could understand.

We all built sets of all shapes and sizes, with coil designs that had to be seen to be believed, but very few of us had much idea of how they worked.

I well remember the case of a cousin of mine who, in those days acquired a magnificent variable capacitor or condenser as it was then called, this instrument had a most impressively engraved dial of polished ebonite, brass vanes and nickel plated end plates. Having observed similar dials on several highly priced commercial receivers in the town, he at once ripped out the somewhat tattered coil from the family receiver and replaced it with this device. The profound silence which ensued caused considerable amazement and dismay until a better informed adult explained the mysteries of L and C to him. Readers of this manual, however, will be better informed and there is no risk of failure with any of the designs described provided the instructions are carefully followed.

The Signal

To commence, we will assume that an orchestra is playing in a broadcasting studio. Since the principle of radio transmission is electrical it is necessary to change the sound produced by the orchestra into an electrical equivalent. This is carried out by the microphone, which picks up the sound and changes it into minute electric currents.

As they appear at the output of the microphone they are too small to be of use and accordingly are passed through a high power amplifier. These amplified currents could now be transmitted, but unfortunately, as we shall learn, owing to the inherent nature of the signal in this state, transmission over any useful distance would be impractical.

When the music from the orchestra is transformed into electrical currents they are in the form of alternating currents, usually called A.C., that is they rise to a maximum in one direction, fall to a minimum, rise to a maximum in the opposite direction and then fall to minimum again. This process is repeated over and over again. One complete rise and fall in each direction is called a cycle and is drawn in Fig. 1. Every time a note is struck on a piano, vibrations are sent out which reach the ear enabling you to hear it. These vibrations are also spoken of as cycles, they rise and fall in intensity the same way as an alternating current. The number of cycles radiated by any given note over a period of one second are referred to as its frequency. Middle C on the piano sends out 261 cycles every second and is known as having a frequency of 261. The microphone also " hears " the note and in the case of middle C produces minute A.C. at 261 cycles. This can be drawn as in Fig. 2, the only difference between Fig. 1 and 2 is, that the time factor is given so that the frequency can be identified. The higher the pitch of a note the higher the frequency and the lower the pitch the lower the frequency. On a piano the frequency of the top note is 3515 cycles and that of the lower 27 cycles. Those of you who have listened to an organ in a concert hall will have noticed that when a very deep note was played, it sounded like a growl to the ear, but the vibrating fre-



FIG 1



FIG 2



FIG 3



FIG 4

quency could be distinctly felt through the seat. Higher notes have too high a frequency to be observed in this manner.

The range of sounds which can be detected by the human ear are known as audio or low frequencies. From this you will understand that a low frequency amplifier is one which amplifies sound.

So that the transmitter will carry the programme over a useful distance it is necessary to radiate high frequencies. Now, as explained, the programme to be transmitted consists of low frequencies, and to overcome the difficulty, the transmitter generates A.C. of high frequency and combines it with the low frequencies. It will now be understood that the transmitted signal consists essentially of two different parts, a high and a low frequency content.

Fig. 3 gives a representation of the high frequency signal generated by the transmitter. In the case of the London Home Service, the frequency is 908000 cycles.

When referring to a high frequency signal on the medium or long wave-band it is usual to express the frequency in thousands of cycles, thus 908000 cycles becomes 908 kilo-cycles, which in turn may be abbreviated to 908 k/cs. It might at first be thought that by adding the low frequency or L.F. signal to the high frequency or H.F. carrier a form such as in Fig. 4 would result, such a combination is useless, and, so that the original L.F. content can be satisfactorily extracted by the receiver, the L.F. signal must vary the amplitude or output power of the H.F. signal as in Fig. 5.

It is in this form that the signal arrives at the receiving aerial. The aerial in itself is incapable of discriminating between one signal and another, and countless signals will be collected by the aerial at any one time. Many of these are too weak to be of use but the stronger ones must be sorted out since there is no point in receiving several programmes at once.

Fig. 6 shows the basic circuit of the input to a crystal. The coil L possesses a quality known as inductance, and the capacitor C, that of capacitance. If the coil had no capacitance whatever across it, all signals arriving at the aerial would be effectively short circuited to earth. As a matter of interest, it is impossible to obtain this state of affairs since even without any additional capacitor any coil **must** contain a certain amount of self capacitance.

By combining a coil and capacitor as in Fig. 6 a peculiar effect is observed, at one particular frequency, the signals are not short circuited to earth, but are developed across the coil. In other words the combined effect of L and C no longer provides a short circuit, **but only at one particular frequency.** If the value of C is altered the effect will be observed at a different frequency; likewise by altering L the frequency at which the effect will take place can be changed. There is a name for this phenomena, the frequency at which it occurs with any given L and C combination is known as the **resonant frequency.**

The values of the coils and capacitors shown in this manual have been carefully chosen so that resonance will be obtained at all frequencies where stations are broadcasting. Broadcasting stations work in bands of frequencies, those of major interest to crystal set constructors are the medium wave-band 1200 k/cs—600 k/cs and the long wave-band 300 kc/s—150 k/cs.

Usually a variable capacitor is used with a fixed inductance to cover one band and an additional coil switched in to increase the inductance to cover the other. In this way the L and C combination can be adjusted to provide resonance at the desired frequency of any given station. In other words you can **select** the station you want by varying C, that is turning the dial of the variable capacitor. This procedure is referred to as tuning. Having selected or tuned the required station it still remains necessary to change the form of the signal back to that of the original transmission. This process is called detection or de-modulation.

Examination of Fig. 5 will show that the signal has been duplicated, in other words, as it rises in one direction it also rises equally in the other. In this form the signal is useless since each half of the signal cancels the other, and if this signal is applied to a pair of headphones silence will result. Obviously some provision must be made to get rid of the unwanted half of the signal, and it is here that the crystal detector must be considered. This device will pass current in one direction only, ignoring any signal in the opposite direction, so that if the signal of Fig. 5 is passed through such a crystal, that of Fig. 7 will result. There is still the H.F. content to be reckoned



FIG 5



FIG 6



FIG 7



FIG 8

with, fortunately this is easily dealt with, a capacitor connected across the headphone terminals effectively disposes of this, leaving only the audio or L.F. content, as shown in Fig. 8. This audio content, which is a faithful replica of the original transmission is fed to the headphones. These in turn reverse the process of the microphone and transform the electrical currents into sound waves acceptable to the human ear.

Briefly then, your requirements are as follows:—

(1) A good aerial and earth installation, to make the most of the available signals.
(2) A receiver containing:—
    (a) Some form of coil and capacitor (L & C) combination to select or tune in the wanted station.
    (b) A crystal to get rid of the unwanted half of the signal (detection).
    (c) A fixed capacitor across the headphones to get rid of any remaining carrier.
(3) A pair of sensitive high resistance headphones.

Aerials

By this time the intending constructor will be able to appreciate the necessity of a good aerial. It is a point which cannot be over-emphasised. Assuming that you are in the fortunate position of being able to erect an outdoor aerial there are two main considerations, height and length.

One of the best that can be used is the inverted L shown diagramatically in Fig. 9.

It should be erected as high as is practical, every foot counts. The horizontal wire, that is the aerial proper, should have a minimum length of 60′ to which of course the length of the down lead is added. Where it is impossible to erect an aerial with an ideal horizontal length, a compromise must be effected.

Fig. 10 shows a three wire spreader aerial which gives quite a good effective length.

Suitable wire for a receiving aerial will not set any problems, stranded copper about 7/22 gauge is the best. 7/22 means that it consists of 7 strands of 22-gauge wire. This wire may be obtained covered, and for the present purpose is better than the plain or enamelled kind.

Note that insulators are used between the actual aerial wire and its anchoring supports, it is important that these are used, otherwise leakage will occur which will of course spoil its efficiency. Fig. 11 and 12 show how the wire may best be attached to two of the most common types of insulator available. Fig. 11 is of porcelain and is usually referred to as an egg insulator, whereas Fig. 12 shows a more modern (and more expensive) type in glass. If you are using the glass pattern, one is usually sufficient at each end of the aerial, but with the egg type two should be used. No doubt many readers will not be in a position to erect an out-door aerial, and must necessarily be content with an indoor installation.

The next best thing to a good out-door aerial is a replica constructed in a loft. If this form of construction is used, care must be taken when feeding the down lead to avoid close contact with the wall of the house. At the point where the lead feeds under the eaves, a length of rubber tubing can be used to cover the wire. The lead is fed through one of the small spaces left for ventilation purposes. A general idea is given by Fig. 13.

A less elaborate but quite effective aerial can be obtained by using a bed-spring. A length of 7/22 copper insulated wire is connected between the receiver and the spring. The spring should first be cleaned with emery cloth. Remove about 2″ of insulation from the wire and bind it tightly round the prepared spring. The joint may be covered with insulating tape which is obtainable from all electrical stores for a few pence.

Such aerials are quite popular since so many crystal sets are built for bedroom use.

When an aerial is required in the living room, the picture rail can be conveniently used. Insulated screw-eyes are fixed at intervals of about 3 feet along the rail, the wire is firmly anchored to one of them, and stretched right round the room until you arrive back at the starting point. By use of one of the insulated screw-eyes, the wire is secured and the down lead fed to the receiver. The idea is illustrated in Fig. 14.

Soldering

Before leaving the subject of aerials, a few words on soldering will not come amiss. Down leads on outdoor aerials should be soldered, and the same applies to loft types. Apart from aerial leads; earth leads and all the connections in the receiver will require soldering.

For the type of soldering necessary in radio construction an electric iron is the best solution. One of the small types marketed by Adcola or Henleys will be found admirable for the job. These are excellent for actual set construction but are hardly large enough for soldering the down lead to an outdoor type of aerial. Here the heat is dissipated much more quickly and a larger iron is required in order to get the solder to flow.

Ordinary irons which may be heated by a gas flame can be obtained very cheaply from most ironmongers' stores. Assuming the use of such an iron, first heat the iron until the copper bit is giving off a green coloured flame, the iron is now at the correct operating temperature. The bit is now discoloured or oxidised and its tip


60'
INSULATORS
TO RECEIVER

INVERTED 'L' AERIAL

FIG. 9


START
30'-40'
FINISH
INSULATORS
WOODEN SPACING POLES APPROX. 4' LONG.
TO RECEIVER

'SPREADER' AERIAL

FIG. 10


AERIAL
INSULATOR
TO RECEIVER
SUPPORTING WIRE OR ROPE.

METHOD OF FITTING PORCELAIN INSULATOR

FIG. 11


INSULATOR
SUPPORTING WIRE
AERIAL
TO RECEIVER

METHOD OF FITTING GLASS TYPE INSULATOR.

FIG. 12


FIT LENGTH OF RUBBER TUBING OVER AERIAL HERE
AERIAL
INSULATOR
TO RECEIVER

LOFT AERIAL.

FIG. 13


INSULATED SCREW EYES.
START
FINISH
TO RECEIVER

'PICTURE RAIL AERIAL.

FIG. 14

should be quickly cleaned with an old file which should be kept specially for the purpose. A better idea is to obtain a small block of sal-ammoniac and rub the tip of the hot iron on it. This will clean the tip of the bit perfectly. Next take a length of cored solder such as Ersin Multicore, and melt a little on to the prepared tip faces, now smooth it evenly over the surface with a piece of old rag (be very careful not to burn your fingers) the iron is now "tinned" and ready for use. When heating the iron, be very careful not to let the bit overheat or get red hot, otherwise the tinned surface will be destroyed and the whole process will have to be gone through again.

An electric iron will not overheat, and the tinning will last much longer than with ordinary types, and since the heat does not deteriorate there is less likelihood of making faulty joints.

Having obtained a tinned iron, the process of soldering joints is remarkably simple and anyone with a little patience can acquire the art in a very short time.

To solder two copper wires together: clean the wire with emery cloth, apply a prepared iron and some cored solder to it, the solder will flow evenly over the wire thus tinning it. Repeat the process with the remaining wire and then twist the two together. Now apply the iron to the joint from the underside and the cored solder to the joint on top. Solder will flow evenly over the joint. Remove both iron and solder and allow to set. The solder will harden or set in a few seconds but during this period the joint must not be touched or moved, as otherwise the joint will be "dry" and quite useless mechanically or electrically. On radio components, tags for soldering are already tinned though if they are old, or discoloured it is best to re-tin them. Normally, however, it is only necessary to twist the connecting wire to it and apply the iron and solder as explained.

Remember: never apply the solder to the iron and then the iron to the joint, always apply the iron and the solder to the joint. It is however a good thing to apply a little solder to the iron tip even when it is perfectly tinned just before making a new joint.

One final "DON'T," you will have noticed that the solder referred to is "cored," that is, it contains resin and other substances through its centre, plain solder as used by electricians and plumbers will not do, as it is the resin or flux


EARTH LEAD
COPPER EARTH TUBE
SOIL
COKE & SOOT MIXTURE.
A
EARTH LEAD
COKE
SOIL
PERFORATED TIN CONTAINING MIXTURE OF SAL AMMONIAC & COKE
B
EARTH LEAD
SOIL
PERFORATED TIN CONTAINING SAL AMMONIAC.
C

FIG. 15.

as it is called which makes the solder flow evenly and permits a good electrical joint.

Equally important do not attempt to use a separate flux or soldering fluid with plain solder or to "help" the cored solder, since these are almost certain to cause eventual corrosion and will destroy any components that have been contaminated.

Earths

The provision of a good earth is just as important as the rest of the installation.

Much disappointment would be avoided if this fact were not lost sight of, to avoid any slip up in this direction I am proposing to outline several well tried and efficient earth systems.

If it can be obtained, an earth rod, specially designed for the purpose provides the basis of a good earth connection. These were very popular some years ago when the majority of receivers were either crystal or battery operated, but in these days of modern mains driven sets they are not often used and consequently not always readily available.

Fig. 15 shows how it is used. First excavate a hole to a depth of three feet and fill with a mixture of soot and coke. Drive in the earth rod, which is a hollow copper tube, perforated. The lead to the receiver is connected at the top, and should be of covered 7/22 gauge, as used for the aerial system. Though not obvious it is important that this lead-in should be in covered wire, otherwise a number of indifferent earth contacts are likely to be made at various points along its length until it reaches the set. This is very undesirable and will spoil the efficiency of the system. It is essential to keep the soil surrounding the rod moist, which is one reason why the tube is hollow, and care must be taken to pour water into the tube at intervals.

A very efficient earth is the percolative type also popular at one time. Due to the chemicals used, it will extract moisture from its surroundings, thus maintaining a permanently moist earth. It should be installed as in Fig. 15b.

The container is of copper or zinc, anything else will quickly rust away, again a good quantity of coke is used. Fill the container with a mixture of sal-ammoniac and coke, and then bury in coke as illustrated. This earth will not require further attention. It is possible to use powdered calcium chloride instead of sal-ammoniac but unless a chemist can be persuaded to make some up it is better to stick to sal-ammoniac.

If a zinc container is not available and you do not use or cannot easily get coke, Fig. 15c should be used. This makes a better earth than many so-called "earths" that I have come across. Obtain as large a tin as possible, make a number of holes as shown. Solder the lead in the bottom and fill it with sal-ammoniac. Replace the lid and bury in the ground. The tin will eventually rust away, but the replacement cost is negligible.

If it is quite impossible to make direct contact with the ground, a water pipe must be pressed into service. This should be a main pipe feeding straight to ground and not a hot water pipe or one fed from a tank. Scrape the pipe clean and twist the lead in tightly around it, a copper clip is even better. Do not attempt to solder on to the water pipe; since cold water is flowing through the pipe, it is extremely unlikely that your soldering iron will heat up the water supply sufficiently to allow a sound electrical joint, though you may spring a leak.

No attempt should be made to utilise gas pipes; the possibility of causing a fire is certainly very remote but, they make incredibly bad earth connections due to a number of joints made before true ground is reached. These joints are at best only semi-conductors, at least from an electrical standpoint.

Headphones

Since the late war there have been a large number of head-phone sets available on the surplus market. These may be roughly divided into two types, high-impedance and low-impedance. For the crystal sets detailed in this book high-impedance 'phones are required and the low-impedance pattern will not be suitable unless a matching transformer is used. As this is likely to cost more than the rest of the installation including the set, it will be as well to avoid them.

High-impedance types have an impedance of $2000\,\Omega$ to $4000\,\Omega$ whereas the low-impedance types are usually $600\,\Omega$.

The remaining consideration is weight; often cheap headphones are very heavy and uncomfortable to wear, every endeavour should be made to obtain 'phones as light in weight as possible.

Crystals

All the sets shown in this book have been designed to work with modern germanium crystals rather than the older galena crystal.

These germanium crystals require no adjustment, which, in itself, removes the main objection to this class of receiver. Suitable crystals are available from the following manufacturers and on the surplus market: Mullard, G.E.C., Brimar, Westinghouse and B.T.H. They are of robust construction, some in glass, others in ceramic or plastic, but must not be subjected to heavy knocks, otherwise the contact point may become dislodged.

From the information given, you should now be able to install an excellent aerial and earth system, and have some idea of how the crystal set works, so it is time to pass on to the actual receiver construction.

CONSTRUCTION 1

If you examine the following circuits you will find that each one is different. In most cases the difference lies in the coil design and/or the method by which the crystal and aerial is tapped into it. Each of these circuits has its own particular advantage to suit different conditions and the ideal circuit in some localities is not necessarily the best in others. It is not just a matter of a given circuit giving louder results than another, if it were there would be no point in showing more than one.

The main problem is to obtain adequate selectivity without reducing the volume level.

A receiver is said to be selective when it tunes sharply, a set with poor selectivity allows the stations to spread over the dial and when used near a transmitter will receive the local stations mixed together, which of course is useless.

Consider Fig. 16a, this is a very simple receiver, with no special attempt to provide any great amount of selectivity. In areas where signal



FIG. 16a



LID SHOWN BROKEN AWAY TO REVEAL POSITION OF COMPONENTS.

FIG 16 b

strength is not high, or a short aerial is used, it will probably be ideal.

It would have been quite easy to increase the selectivity by providing a tap on the coil for the aerial as in Fig. 17a, but unfortunately, as the selectivity is increased overall volume is likely to decrease, so that unless you live close enough to the transmitter to have a large signal available and therefore need the selectivity, the circuit of Fig. 16a will be quite satisfactory.

Capacitor C1 is to prevent the aerial damping the circuit too heavily because this would flatten the tuning unnecessarily, however with small aerials it may be better to take the aerial direct to the black tag on L1. The signals are selected or tuned by L1 and C2, X1 is the crystal and C3 the capacitor across the 'phones to prevent unwanted carrier or R.F. reaching the 'phones.

A practical diagram (Fig. 16b) is provided showing the layout and all the wiring. You will require nuts and bolts to fix the coil, about ½", 4BA size will do, the other parts have locking nuts provided. An old 2-oz. tobacco tin makes a very good container and keeps the size down. Note that the metal box is connected to earth. With the exception of AC/DC receivers the metal work on any receiver or amplifier is connected to earth.

When S1 is open as in the diagram, the set will tune in long-wave stations, but when closed the medium wave-band will be received.

Components List, Fig. 16a

C1 100pF mica capacitor.
C2 500pF tuning capacitor, solid dielectric.
C3 1000pF mica capacitor.
X1 Germanium crystal.
L1 Crystal Set Coil. R.E.P.
S1 Single Pole toggle switch.
4 Insulated wander-plug sockets and plugs.
1 2-oz. tobacco tin (or similar container).

Make sure that the wander-plug sockets are of the insulated type, otherwise the metal case will join all the sockets together electrically.

Try to follow the theoretical diagram when wiring, a little practice will soon enable you to wire up a set without a practical diagram, which is a great advantage because often only the theoretical diagram is given when circuits are detailed in the technical press.

Fig 28 on page 34 gives a list of symbols used on the theoretical diagrams, so that you can readily identify the components.

2

Fig. 17a circuit is similar in many respects to that of Fig. 16a. The difference is purely one of selectivity, tuning will certainly be sharper, and even with comparatively inefficient aerials the design will put up a very good performance. There is no reason why the construction should not follow the same lines as the previous receiver but, by enlarging the set a little and using an air spaced tuning capacitor, the efficiency is improved. Observe that the colour coding on the coil, an R.E.P. Dual Range (Blue Box) is different from that of the Crystal set coil used on the previous design, and make sure it is correctly wired in.

C1 is a mica compression capacitor, often referred to as a "trimmer" and because it is adjustable, permits the set to be matched to aerials of varying lengths. Construction is carried out on a square panel of bakelite, perspex or wood, as shown in Fig. 17b. Perspex being clear like glass presents a most attractive finish, provided the set is neatly wired. It must be drilled slowly, however, otherwise the generated heat of the drill will make the hole wander, and spoil the panel.

After the set has been wired and tested a small wooden container can be made to house the completed set.

When carrying out reception tests, a little experiment is well worth while, to get the best out of the set. Try removing the germanium crystal from the green tag on L1 and connecting it to yellow, at the same time removing the lead from C1 to yellow and connecting it to green. Once the best arrangement has been found the wiring



FIG. 17 a

can be left permanently in that position. Note that two tags on the coil are unused, this is intentional because on this circuit the extra winding connected to these tags is not required. With the switch S1 closed, the coil will cover the medium wave-band, and when open, long wave stations can be received. It is customary to abbreviate the expression medium wave-band to M.W. and long wave-band to L.W.

Components List, Fig. 17a

C1	100pF mica trimmer capacitor.
C2	500pF variable capacitor (air spaced).
C3	1000pF mica capacitor.
L1	Dual Range Coil R.E.P. (Blue Box).
S1	Single Pole toggle switch.
X1	Germanium Crystal.
4	Terminals or wander-plugs and sockets. Perspex, bakelite or wood for mounting panel.



FIG. 17b

3

The design shown in Fig. 18a and 18b is more flexible than either of the preceding sets. That is, it can be varied to suit local conditions to a greater extent than the first two sets. This is made possible by the large number of taps provided on the coil.

You will notice that in this instance the coil is home-constructed on a cardboard former and is much larger than commercially produced coils. Coils wound in this manner are called **solenoids**, the turns are wound on side by side; in this case to a depth of some three inches. The diameter of the coil is made purposely large so as to obtain high efficiency. Modern commercial coils are invariably wave-wound and quite often are litzendraht which is the German for litz wire. This wire is made up of a number of strands of fine copper wire, each strand is enamelled to insulate it from the others, the whole is then silk covered. Litzendraht is more efficient than solid copper wire, and by using this and wave-winding, manufacturers can produce an efficient coil which is also small. Unfortunately wave-wound coils cannot be produced without a complex winding machine and home-constructed coils must take the solenoid form. It would be possible to use litzendraht but it is not easy to obtain by the reel, it is most expensive, and is difficult to handle. This last point is because at termination points, each strand must be cleaned of its enamel before a joint is made, and if one strand is broken, its advantage over plain copper wire is lost. How-



INSET SHOWING METHOD OF TAPPING COIL.

FIG. 18 a

ever, by using a former of reasonably large dimensions an efficient coil can be produced cheaply using ordinary copper wire.

The wire must be firmly secured at the start and finish of the windings. Pierce three small holes about ¼″ apart ½″ from the end of the former. Pass the wire through the first from the outside, return it through the second and pass it back again through the third. Leave some 6″ of wire at the end to make off the connection. It will now be possible to wind the turns on tightly without wire slipping.

Count on ten turns and make a loop 1″ long. The method of preparing loops is shown in Fig. 18a, loops or taps should always be made in this manner, never by baring the wire and soldering a further length of wire to it. Carry on with the winding, making off the taps every ten turns as directed until the coil is complete.

Construction is carried out on a wooden base-board and front panel. Secure the coil to the base-board as shown on Fig. 18b, mount the remaining components and proceed with the wiring.

When testing out, it will be found that the further the aerial is tapped down the coil towards the earth end, the greater the selectivity. A position should be found which permits separation of local stations without excessive loss of sensitivity.

The crystal tap is adjusted for best results and different settings of C1 tried out, when choosing the best position for the aerial tap.

Components List, Fig. 18a

C1	450pF padder.
C2	500pF variable capacitor.
C3	1000pF mica capacitor.
L1	See text and Fig. 18a.
X1	Germanium Crystal.
2	Crocodile Clips (to connect leads to coil taps).
4	Wander-plugs and sockets.



METHOD OF FIXING COIL

VIEW ON FRONT PANEL

FIG. 18 b

4

A most unusual design is reproduced in Fig. 19a.

It first appeared in America about three years ago, and it certainly does offer some advantage over more conventional sets. The tuning circuits are duplicated and two crystals are used, so the circuit may be described as a full-wave receiver. Signals received will certainly be louder than with simple sets, but care must be taken with the coil winding, as with the other receivers using home-made coils, otherwise results will be disappointing. Be very careful to ensure that all three windings are in the same direction, this is very important.

The distance between each winding should be ⅛". After the coil has been wound it is a good plan to warm it before a fire and paint the windings with "Durafix." Heating the coils makes the "Durafix" run freely. This substance sets quite hard and there will be no risk of the windings loosening. A small quantity of enamelled wire will cover the requirements of this coil, a 2 oz. reel will provide more than sufficient.

Before wiring in the germanium crystals, examine them carefully, note that one end is coloured red or in some cases marked with a positive sign thus +. You will notice, the sign is the same as the addition symbol used in arithmetic.

It is essential that both the red or positive ends are connected together, note that this is clearly marked on Fig. 19b. The receiver cannot work if



DETAILS OF COIL.

ALL COILS WOUND IN SAME DIRECTION.

FORMER CAN BE BAKELITE, OR WAXED CARDBOARD TUBE.

FIG. 19a

one of the crystals is connected the reverse way round.

A baseboard and panel form of assembly is used for this set which looks quite attractive if housed in a small polished cabinet. Dimensions are not at all critical but Fig. 19b gives a general idea of the layout that should be used. To avoid any unnecessary losses the coil should be mounted on perspex.

Obtain two strips of perspex 5½" long by ½" wide, drill fixing holes at both ends of each strip. It is best to clamp the two together when drilling these holes. Place one strip on the board in position, then put the coil and remaining strip over the first one and screw down. The coil will be clamped neatly and rigidly into position.

Twin socket bakelite strips are used to carry the aerial/earth and 'phone connections, if desired terminals mounted on pieces of bakelite could be used. These socket strips can be purchased from most shops selling components. If feet are not provided, drill two holes and screw into the edge of the base-board. Tag-strips are used to anchor some of the wires from the coil, and the germanium crystals. These also can be purchased for a few pence. At least two tags are necessary on one, and three on the other, though if the strips have more tags than required it is of no consequence. C3-C4, the ganged tuning capacitors have trimmers fitted, this should be stipulated when purchasing, and when first operating the set these small trimming capacitances are set about half-way. The idea of these trimmers is, that they compensate for any difference between the self-capacity of the tuning coils. With the switch S.1 open, that is in the OFF position, two


C1
3
S1
'PHONES
E
A
C1
C3
C2
TO FIXED VANES ON C1
TO MOVING VANES ON C1
C4
3
4
1
6
2
5
X1
X2
1
'PHONES
RED
E.
A.

FIG. 19 b

in a station at the high-frequency end of the band, that is with the vanes of C3-C4 towards the disengaged position. Adjust C1 for maximum volume, without interference from other stations. Now adjust the trimmers for loudest headphone strength. It may be necessary to run over the adjustments several times for best results. Once they are correctly set, the trimmers require no further adjustment. The tuning coil covers the M.W. band, 1500 kc/s. to 600 kc/s., as the capacitor C3-C4 is advanced and the vanes start to mesh, the frequency to which the receiver tunes **decreases** so that with the vanes disengaged the set is tuned to 1500 kc/s. approximately and at full mesh, 600 kc/s. Switch S1 is used as follows, for stations **lower** in frequency than 850 kc/s it should be in the ON position with the contact closed, but for stations **higher** in frequency, it is in the OFF position. As an example both the London Home Service and London Light Programme transmitters on the M.W. band operate at a higher frequency than 850 kc/s. If any doubt exists as to the operating frequency of a given station, reference should be made to the Radio Times which quotes both wave-lengths and frequency. If you know the wave-length in metres, it is simple to find the frequency. Divide 300,000 by the wave-length in metres, the dividend equals the frequency in kilocycles, i.e., 300,000 ÷ 300 metres = 1,000 kc/s. In the same way, dividing 300,000 by the frequency in kilocycles will produce the wave-length in metres.

To use the receiver, tune in the signal by C3-C4, adjust C1 for maximum volume without allowing stations to overlap.

Components List, Fig. 19a

C1	300pF solid dielectric variable capacitor.
C2	1000pF mica capacitor.
C3-4	500pF twin gang variable capacitor.
L1-2-3	See text and Fig. 19a.
X1-2	Germanium Crystal.
2	Tag-strips.
2	Twin socket strips.
S1	Single Pole toggle switch.

5

Whenever crystal sets are discussed, constructors are apt to think in terms of medium-wave reception. When you consider that at least 98% of published circuits are designed for this band (sometimes with the long-wave band thrown in as an afterthought) it is understandable. However, if you can provide a good outdoor aerial (and an equally good earth) there is a lot of fun to be had listening to the short-wave bands. This receiver is designed specially for short-wave reception.

A metal chassis is used for construction, these can be obtained ready made in aluminium from most good supply houses. It can be quite small and on the original model a 6" x 4" was used. Low loss components are used so as to obtain greatest efficiency on the short wave bands. The coil is a commercial product which plugs into a 4-pin base. Best results were obtained on the 3mc/s to 7mc/s band though coils covering other bands are available.

Note that the tuning capacitor C1 is smaller than normally used and has a maximum capacitance of 140pF.

Coil type 706/R covers the 3mc/s to 7mc/s band, but the set is equally satisfactory on the M.W. band, and to cover this coil type 706P should be used. This coil has an iron dustcore which can be adjusted to make the coil cover the required band. The effect of the core is as if turns were being added or removed from an ordinary coil. When dealing with the short waves it is customary to refer to the frequencies in terms of mega-cycles (mc/s) rather than kilo-cycles. One mega-cycle is equivalent to 1000 kilo-cycles, that is 1,000,000 cycles.

Layout and wiring can be clearly followed from Fig. 20b and a theoretical diagram is shown in Fig. 20a. Care should be taken when arranging a mounting for the aerial terminal. The best plan is to cut a 1" hole in the chassis, mount the aerial terminal on a piece of perspex and screw into the chassis. This avoids any unnecessary losses between aerial and chassis. The earth terminal is screwed directly into the chassis.



FIG. 20 a



FIG. 20 b

Wiring as shown in Fig. 20a is likely to give the best results, but other arrangements are possible and to get the best out of the set they should be tried.

Refer to Fig. 20a. The aerial is connected to pin 3 on L1, C1 to pin 2 and X1 the crystal to pin 4. If you have a long aerial try this combination—Aerial to pin 4, C1 to pin 2, and the crystal to pin 3. Connections to pin 1 are not altered. In a few cases the following arrangement may prove best. Crystal and C1 to pin 2, aerial to pin 3, pin 4 left free and again pin 1 is unaltered.

Tuning on the short-wave bands is more critical than on the medium waves so tune very slowly over the band and remember signal strength is likely to vary from day to day.

Components List, Fig. 20a

C1	140pF variable capacitor Eddystone 586.
C2	1000pF mica capacitor.
1	Coil holder Eddystone 707.
L1	3m/c—7m/c coil Eddystone 706/R.
1	Engraved tuning dial.
1	6"x4"x2½" chassis.
2	Terminals (Aerial-Earth).
1	Twin socket strip ('phones).
X1	Germanium Crystal.

6

Fig. 21a-b is yet another design from America and appeared in Radio Craft some years ago, designed by Mr. W. J. Spain. The original used a silicon crystal which preceded the development of the germanium. Results are certainly very good though of course on the model built here, a germanium crystal was used. Selectivity can be adjusted to suit all conditions and even at short distances from local stations. Good volume can be obtained without the programmes overlapping. Home made coils are used and for best results a 75' outdoor aerial is desirable.

Baseboard and panel construction is used, which can conveniently be housed in a small wooden cabinet.

Operation is a little more complicated than some of the other designs, but the results certainly merit the extra trouble taken. As with the other receivers much of the success obtainable is due to the coils and these must be carefully made otherwise results will be disappointing.

Layout and wiring can be followed quite easily from Fig. 21b and requires no special comment.

First make the coils. L1 is a tapped coil, the taps should be made in the same way as shown in Fig. 18b. It consists of 90 turns of 22 D.C.C. (double cotton covered) copper wire tapped at the following number of turns, 5, 10, 15, 25, 30, 40, 50, 60, 70 and 80. The former used has a diameter of 2". L2 is also wound on a 2" diameter former, this coil however is not tapped, it consists of 110 turns of 38 D.C.C. or enamelled copper wire. Great care must be taken when handling this wire, it is quite fine and in the hands of the inexperienced will easily break.

After wiring has been carried out the set can be put into operation.

Selectivity is controlled by S2, in position B tuning is broad but in position A it can be quite sharp.

When searching for a station switch S2 to B. Tune the station and switch S2 to A. The frequency range is controlled by the position of the tap on L1, a good plan is to start with the 5 turn tap on L1.

Components List, Fig. 21a

C1	500pF variable capacitor.
C2	500pF variable capacitor.
C3	1000pF Mica Capacitor.
X1	Germanium Crystal.
L1 & L2	See text.
S1	Single Pole toggle switch.
S2	Single Pole 2-way toggle switch.
2	Twin socket strips (Aerial/Earth and 'Phones).



FIG. 21 a


S1
X1
S2
B
A
RED
C1
C2
'PHONES
C3
TO SUITABLE TAPPING
L2
L1
AERIAL
EARTH

FIG. 21 b

Keep S1 open and C1 for tuning, adjusting the tap on L1 for best results. Very powerful signals are best brought in with S1 closed. When using C1 and adjusting the taps on L1, switch S2 is kept in the A position.

It will be found that C2 acts as a fine control on C1. One division of the tuning dial on C1 is roughly equal to a movement of 20 divisions on C2.

Note that the coils are mounted at right angles to one another and that in this instance wood has been used as far as possible, an aluminium or other metal chassis is not suitable.

7

A very useful receiver for both medium and long-wave reception is possible with the circuit of Fig. 22a-b. A home-made coil is used. On the original a 1¼″ diameter former was used but in fact this is not very critical and a 1½″ former could be used. An interesting point is the construction of the long-wave coil section. Solenoid coils as used for the medium wave-band are not efficient if the length is too great relative to the diameter. Now as the long-wave section has 300 turns, if wound as a solenoid the winding length would be very great and a lot of efficiency would be lost. To overcome the difficulty the coil is pile wound. If the whole coil were to be wound in one pile it would still be inefficient because of the capacity formed in the winding, but by dividing it into five sections a coil of reasonable efficiency results. The same remarks concerning winding apply to this coil as to all the others in

Components List, Fig. 22a

C1	300pF Mica Capacitor.
C2	500pF Variable Capacitor.
C3	1000 Mica Capacitor.
X1	Germanium Crystal.
L1-2	See Text.
S1	Single Pole Toggle Switch.


C1
1
2
3
4
5
L1
L2
S1
X1
RED
C2
C3
1¼″ DIA.
①
②
③
④
⑤
L1
L2
4″
L1. 112 TURNS OF 30 S.W.G. D.S.C. OR D.C.C. TAPPED AT 56 TURNS ② & 84 TURNS ③ WINDING FROM TOP OF FORMER.
L2. 300 TURNS OF 30 S.W.G. D.S.C. OR D.C.C. PILE WOUND 60 TURNS TO EACH PILE.
DETAILS OF COIL
ALL COILS WOUND IN SAME DIRECTION.
FORMER CAN BE BAKELITE OR WAXED CARDBOARD TUBE.

FIG. 22a



FIG. 22 b

this book, and readers should not, by this time, encounter any difficulties.

The design provides good selectivity with good sensitivity, and provided the set is not required to operate within a few miles of a powerful transmitter, no trouble will be encountered from interference between adjacent stations.

A wooden base-board and front panel is best for this design, and the wiring and layout can be clearly followed from Fig. 22b. Switch S1 is open for long-wave reception and closed for the medium-wave band.

Coil mounting can be on the same principle as for the full-wave design Fig. 19a-b.

8

If you look at all the other circuits shown in this book you will find that in each case the tuning capacitor and tuning coil are in parallel, this is by no means essential and the circuit of Fig. 23a shows a series arrangement that is the tuning capacitor is between the coil and earth instead of being wired up across it. This design also appeared in **Radio Craft** a few years ago.

An interesting point is that the coil is a conversion adapted from another type of component. To make this coil you must obtain an old I.F transformer as used in superheterodyne receivers.

You will require one designed to work anywhere between 450 and 470 kc/s. Some of the very early ones worked at 110 kcs/ but these are unsuitable.

The I.F. transformer must also be of the type tuned by an iron dust core at each end.

Dismantle the transformer, remove the parallel capacitors and mounting wires so that you are left with two coil bobbins and their former. Be very careful when un-soldering the wires from the supports because the coils are usually wound in litzendraht and must remain intact. Remove 25% (approximately) of the turns from one coil which we will call the secondary, and completely remove the iron dust slug from this coil, now cut the former in half, and mount as in Fig. 23a. Warm the coils with heat from your soldering iron or from a fire and gently slide the coils into position at the ends of the former as in Fig. 23a. The wax will set again holding the coils in their new position.

Note that the wires from the coils are connected to tags on the mountings. These are pieces of bakelite, and usually the original end pieces used on the I.F. transformer can be used.

A word about soldering litzendraht. Do not attempt to use emery paper. Prepare the end of wire by removing the outer silk covering and dip the end in methylated spirits. Ignite with a match and after about five seconds wipe with a cloth held between finger and thumb. This will quench the flame and will remove all traces of enamel from the wire. It is a good plan to experiment with the odd length of wire removed from the secondary coil. If the coils prove to be constructed of ordinary copper wire, it can of course be prepared with fine emery cloth in the normal manner.

Components List, Fig. 23a

C1 500pF variable capacitor.
X1 Germanium Crystal.
L1 See Text.
4 Plugs and sockets or terminals.

Wiring is straight forward as can be seen from Fig. 23b and requires no explanation.

Operation is as follows, selectivity is controlled by varying the distance between coils with the wing nut, and to an extent by the position of the primary iron dust core. Remember that the aerial and earth installations are as important with this set as with any other crystal receiver. No parallel capacitance appears necessary across the 'phones, the set works quite happily relying on the self-capacitance of the head-phones.



FIG. 23 a


TUNING CONTROL
C1
RED
PHONES
SEC.
PRI.
X1
AERIAL
EARTH
SELECTIVITY CONTROL
– FRONT VIEW –

FIG. 23 b

9

So as to give a truly varied selection of circuits, some of the sets have been designed around commercial coils whilst others use coils which must be home-constructed.


GREEN
C1
X1
L3
YELLOW
RED
RED
BLUE
MED
LONG
C2
L1
L2
MAUVE
C3
BLACK

FIG. 24 a

Most enthusiasts like to build their own coils but when it is a question of something really small combined with efficiency a commercial coil is the obvious choice.

Fig. 24a-b uses a tobacco tin or a similar container just as the design shown in Fig. 16a.

This receiver however is a little more selective and is more suitable than the earlier design, if you are near a transmitter or have a very long aerial. Take great care to connect the coil according to the colours shown on the diagrams. Sockets are used for wave-changing, this cheapens the cost a little and they are just as efficient.

Components List, Fig. 24a

C1	100pF Mica capacitor.
C2	500pF variable capacitor solid dielectric.
C3	1000pF Mica capacitor.
X1	Germanium crystal.
L1-2	R.E.P. dual range coil. Blue box.
6	Insulated wander-plug sockets.
5	Wander Plugs.
2oz.	Tobacco tin or similar container.



LID SHOWN BROKEN AWAY TO REVEAL POSITION OF COMPONENTS.

FIG. 24 b

10

In certain cases, signals from the local transmitter are too powerful to permit a crystal set with a normal coil to be of much use. I myself live in Hertfordshire a few miles from the London transmitters, and find a more elaborate circuit is necessary. Now in radio circles it is a well-known fact that the greater the number of tuned circuits, the greater the overall selectivity. Look at Fig. 25a, you will see that the usual L and C tuning arrangements have been duplicated. This type of circuit is known as a Band-Pass Filter. There are many kinds of such filters, this particular type is an inductively-coupled filter, note that energy from the first half (L2) is conveyed to L3 by way of two small inductors L1 and L4.

Tuning is quite sharp and the "feel" of the set is quite different from that of single coil designs. A small chassis is ideal for construction. 6"x4"x2½" was used on the original, though it could have been smaller.

Fig. 25b gives the layout and wiring.

Take particular notice that L1-2-3 is mounted horizontally and at right angles to L4-5-6, this is to prevent the coupling from being too "tight" which would ruin the idea of the filter. A good aerial and earth is of course necessary. It may be found on test that the selectivity is too great



FIG. 25 a.

and that volume has suffered. This can be ingeniously overcome by connecting a very small capacitance between the two Green tags on the coils. The simplest way is to connect it across the fixed vane connections on C2-C3. Values for this extra capacitance are a matter for experiment usually a value between 10pF and 47pF is sufficient. A small 50pF trimmer could be used and adjusted to suit. The ideal setting is to enable powerful adjacent stations to be received just short of overlap so that as much volume as possible is obtained.

There is one point to be observed with the ganged capacitor. It should be of the type fitted with trimmers though of course, there is no reason why you should not fit them yourself. These are to allow for differences between coils to be balanced out, and consist of a small variable capacitance across each main section.

When setting up the receiver, first set each trimmer at half way and tune in a station near the high-frequency end of the band (vanes nearly out) adjust the trimmers for maximum volume. If extra coupling capacity is added as described, try adjusting them further.

Once properly set up, no further adjustment is necessary.

Components List, Fig. 25a

C1	100pF Mica capacitor.
C2-3	2 x 500pF variable capacitor (see text).
C4	1000pF Mica capacitor.
L1-2-3	Dual Range Coil R.E.P. (Blue Box).
L4-5-6	Dual Range Coil R.E.P. (Blue Box).
X1	Germanium Crystal.
S1a-b	2 pole single throw toggle switch.
4	Terminals or plugs and sockets.


TUNING CONTROL
AERIAL
EARTH
WAVECHANGE SWITCH
'PHONES

FRONT OF COMPLETED RECEIVER.


MOVING VANES
C2 & C3
EARTH
AERIAL
C4
'PHONES
RED
X1
TO FIXED VANES ON C3
TO FIXED VANES ON C2
BLUE
YELL
BLACK
L 4,5,6.
GREEN
MAUVE
RED
S1a & b
C1
BLK
MAUVE
RED
L1,2,3.
BLUE
GREEN
YELLOW

EXPLODED UNDER-CHASSIS VIEW

FIG. 25 b

11

Another band-pass circuit is shown in Fig. 26a. This time home-made coils are used. This filter is not inductively coupled but entirely capacitive, relying on C3. As in the previous circuit it must be adjusted to give just sufficient " broadness " to the tuning to provide adequate volume without station overlap. To avoid unwanted coupling a screen is mounted between the coils, this is necessary because due to the size of the coils they would be bound to couple quite tightly without it. Such precautions were not necessary with the circuit of Fig. 25a, as the commercial coils are much smaller physically and the risk of unwanted coupling reduced.

The coils for this receiver are for medium wave reception only, this keeps the size down. Coil winding procedure has already been fully explained, and covers all the requirements of these coils. Base-board and panel construction is used, and for more accurate tuning since the coils are home-made, **separate tuning capacitors are recommended.** Fig. 26b gives the layout and practical wiring.

Components List, Fig. 26a

C1	100pF Mica capacitor.
C2	500pF variable capacitor.
C3	50pF Mica trimmer.
C4	500pF variable capacitor.
C5	1000pF mica capacitor.
L1-2	See text.
X1	Germanium Crystal.
4	Terminals or plugs and sockets.

For those who do not wish to bother with these a ganged capacitor can be used, but tuning may not be as good as with separate ones. The screen mounted between the coils is of aluminium or copper and should be about 1" higher than the coils and the same length as the baseboard depth.



FIG. 26a


2½" DIA
1
KEEP LEADS 5" LONG. CUT TO LENGTH ON CONSTRUCTION
2"
3
50 TURNS OF 28 S.W.G. ENAMELLED COPPER WIRE.
2
CENTRE TAP

COIL DETAILS.


C4
C3
C2
TOP OF COIL
3
1
L2
SCREEN
2
L1
3
1
2
TOP OF COIL
SCREEN MADE OF ALUMINIUM OR COPPER & TO BE 3" HIGH
C1
C5
X1
RED
'PHONES
E
AE

FIG. 26 b

12

Fig. 27a-b uses a band-pass filter for tuning, and the coils are home-constructed.

With this design a ganged capacitor is quite suitable as the coils tune quite accurately. It is essential that the coupling condenser C3 is **non-inductive**, there will be no difficulty in obtaining a new component of this pattern but it is as well to avoid old components which may not employ this form of construction.

Receivers using this type of filter are used to the best advantage when situated a short distance from a powerful transmitter and if selectivity is not important this particular design is not the most suitable.

Both medium-waves and long-waves are catered for: consider L1-2-3, this is the first half of the filter.

L1 is the aerial coupling coil, with S1 closed, the medium-waves are received. This coil is inductively coupled to L2 and L3. Again with S2 open L2 and L3 combined cover the long-waves and when S2 is closed the medium waves are covered.

Tuning for this half of the filter is by means of the capacitor C1, which is one half of the ganged capacitor. A screen is erected between the two sets of coils comprising the filter, and coupling is effected by C3, an earth return for the coils is provided by R1.

L4 and L5 operated in a similar manner to L2 and L3, tuning is by means of C2, the remaining section of the ganged capacitor. You will realise that the coils must be accurately wound otherwise tuning will not remain constant between the two sections over the band.

The ganged capacitor should be fitted with trimmer capacitors when purchased so that the two circuits can be balanced.

You will have noticed that this circuit uses three sets of switch contacts. A three-pole two-way wafer switch is the best choice otherwise either two or even three separate switches are necessary. All the necessary coil details are given in the diagrams, the tap on L4 is made in the same way as shown for other coils in the manual. One other component used only on this design, is the resistor R1, its size is not important because the current flowing is so small it can be ignored.

A ¼ watt rating is adequate, its precise value is not critical so that a 20% tolerance component is quite suitable.

Resistors are coded by colours and the 1000Ω type you require will bear the following sequence. At one end will be painted three coloured rings.

Components List, Fig. 27a

C1-2	500pF 2 gang, variable capacitor.
C3	0.05mfd. non-inductive paper capacitor.
C4	1000pF mica capacitor.
R1	1000 ohm resistor.
X1	Germanium Crystal.
S1-2-3	3-pole 2-way wafer switch.
L1-2-3 & L4-5	See text.
4	Terminals (Aerial, Earth and 'Phones).
	Sheet copper or aluminium for screen.



FIG. 27a


L2 - L4
58 TURNS No.30 S.W.G. ENAMELLED WIRE. CENTRE TAPPED.
L1. 75 TURNS No.36 S.W.G. ENAMELLED WIRE-PILE WOUND.
L3-L5
174 TURNS No. 36 S.W.G. ENAMELLED WIRE - WOUND IN 3 PILES OF 58 TURNS
2" DIA
3¼"
⅜"
¾"
½"
⅛"
¼"
⅛"
⅝"
1
2
3
4
5
6
7
8
L2 - L4
L1
L3 - L5
CENTRE TAP
COIL DETAILS.
KEEP LEADS 6" LONG & CUT TO LENGTH ON CONSTRUCTION
ON COIL L4 & L5. OMIT WINDINGS 4 TO 6
MOVING VANES ON C1 & C2
S3
S2
S1
C1 & C2 GANGED
TO FIXED VANES ON C1
TO FIXED VANES ON C2
SOLDER TAG
R1
C3
RED
X1
C4
L4. L5.
L1, L2, L3.
SCREEN MADE OF COPPER OR ALUMINIUM & TO BE 4¼" HIGH.
'PHONES
SCREEN
AERIAL
EARTH

FIG. 27 b


VARIABLE CAPACITOR
TUNING COIL WITH TAPPINGS
CRYSTAL DETECTOR
SINGLE POLE DOUBLE THROW SWITCH
FIXED CAPACITOR
SINGLE POLE SINGLE THROW SWITCH
DOUBLE POLE SINGLE THROW SWITCH
AERIAL
EARTH
"TWO GANG" VARIABLE CAPACITOR
WIRES CONNECTED
WIRES NOT CONNECTED
'PHONES
TUNING COIL.
RESISTOR

SYMBOLS USED IN THE CIRCUITS DESCRIBED.

FIG. 28

The first one is BROWN which represents 1, the first figure of the value, the second BLACK, this indicates the second numeral is nought, and the third colour is RED which tells us that two further ciphers or noughts are added to give the total value. From this you can see, we have 1 plus a nought equalling 10, plus two further noughts which total 1000. Some earlier types of resistor were painted differently, the whole body colour represented the first figure, one tip was coloured to represent the second figure, and a painted dot in the centre gave the number of ciphers to be added.

There are no other special points regarding construction except perhaps that if a long aerial is used, a small 100pF capacitor might be tried n the aerial lead to prevent damping the first uned circuit.

When setting up the receiver, tune to a station the high-frequency end of the M.W. band and the trimmers for loudest volume, no other stments are necessary.

CONCLUSION

The twelve receivers described are representative of the best crystal set designs available to-day. Their construction will provide many hours of useful enjoyment, and the results will give lasting pleasure.

A final word about components, if no actual maker is specified, any good class component can be used. Switches, fixed and variable capacitors and crystals, are available from numerous manufacturers all of which are invariably of excellent quality. Where a particular manufacturer's product is called for, the specification should be adhered to. The commercial coils specified are freely available from most supply houses specialising in components for constructors, but in case of difficulty write to Bernards (Publishers) Ltd., The Grampians, Western Gate, London, W.6, who will, on receipt of a S.A.E. be pleased to supply the address of your nearest stockist. Coil formers are not always easy to obtain and in this case advice should be sought from Post Radio Supplies, 395, Queensbridge Road, London, E.8, who will be pleased to help in any way possible.

* *

BERNARDS RADIO BOOKS

No.		Price
56.	Radio Aerial Handbook ...	2/6
57.	Ultra-Shortwave Handbook	2/6
58.	Radio Hints Manual ...	2/6
64.	Sound Equipment Manual	2/6
68.	Frequency Modulation Receivers' Manual	2/6
83.	Radio Instruments and their Construction	2/6
96.	Crystal Set Construction	1/-
99.	One Valve Receivers	1/6
100.	A Comprehensive Radio Valve Guide, Book 1	5/-
103.	"Radiofolder" A. The Master Colour Code Index for Radio and T.V. ...	1/6
104.	Three Valve Receivers ...	1/6
121.	A Comprehensive Radio Valve Guide, Book 2	5/-
123.	"Radiofolder" F. The Beginners' Push-Pull Amplifier	1/6
126.	Boys' Book of Crystal Sets and Simple Circuits	2/6
129.	Universal Gram Motor Speed Indicator	1/-
135.	All Dry Battery Portable Construction	2/6
138.	How to Make F.M. and T.V. Aerials, Bands 1, 2 and 3 ...	2/6
141.	Radio Servicing for Amateurs ...	3/6
143.	A Comprehensive Radio Valve Guide, Book 3	5/-
145.	Handbook of AM/FM Circuits and Components ...	2/-
146.	High Fidelity Loudspeaker Enclosures	5/-
147.	Practical Tape Recording Handbook ...	5/-
148.	Practical Transistor Receivers, Book 1	5/-
149.	Practical Stereo Handbook	3/6
150.	Practical Radio Inside Out	3/6
151.	Transistor Superhet Receivers ...	7/6
156.	Transistor Circuits Manual, No. 1	2/6
157.	A Comprehensive Radio Valve Guide, Book 4	5/-
158.	Radio, Television, Industrial Tubes, Semiconductor and Diodes Equivalents Handbook (208 pages)	9/6
159.	Realistic High Fidelity ...	5/-
160.	Coil Design and Construction Manual	5/-
161.	Radio, Television and Electronics Data Manual ...	3/6
162.	High Fidelity Stereo Gramophone	5/-
163.	Transistor Circuits Manual, No. 2 ...	2/6
165.	Hartley on Hi-Fi, Book 1. Radio Tuners	5/-
166.	Public Address Systems ...	2/6
168.	Transistor Circuits Manual, No. 4	2/6
170.	Transistor Circuits for Radio Controlled Models ...	7/6
171.	Super Sensitive Transistorised Pocket Set Construction	3/6
172.	International Radio Stations List	2/6
173.	Practical Transistor Audio Amplifiers	3/6
174.	Transistor Subminiature Receivers Handbook	5/-
175.	Transistorised Test Equipment and Servicing Manual	3/6
176.	Transistor Audio Amplifiers Manual	6/-
177.	Modern Transistor Circuits for Beginners	7/6
178.	Comprehensive Radio Valve Guide Book 5 ...	6/-
179.	Transistor Circuits Manual No. 5	5/-
180.	British Semiconductor Survey ...	15/-
181.	22 Tested Circuits Using Micro Alloy Transistors ...	5/-
182.	"At A Glance" Radio Valve & T.V. Tube Equivalents	3/6
183.	How to Receive Foreign T.V. Programmes on your Television Set by simple Modifications	5/-
184.	Tested Transistor Circuits Handbook...	2/6
185.	Tested Short-Wave Receiver Circuits using Micro Alloy Transistors (MAT's) ...	5/-
186.	Tested Superhet Circuits for Short-Wave and Communication Receivers using Micro Alloy Transistors (MAT's)	6/-
187.	The TSL Mark "4" Valved F.M. Tuner and its Construction	3/6
188.	Construction of the B.H. High Fidelity "14" watt Audio Amplifier	1/6
189.	How to build the world's smallest transistor radio. The Sinclair Micro 6 ...	1/-
190.	How to build the world's smallest High Fidelity Amplifier	1/6
191.	Practical Car Radio Handbook	6/-
501.	ABC's of Magnetism ...	5/-
502.	ABC's of Missile Guidance	5/-
503.	ABC's of Ultrasonics ...	5/-
504.	ABC's of Transistors ...	5/-
	Resistor Colour Code Disc Calculator ...	1/6
	Engineers' Reference Tables	1/6
	International Radio Tube Encyclopaedia—3rd Edition	63/-

MDS975 www.mds975.co.uk

CRYSTAL SETS 5
Experimental
Crystal Sets

MDS975 www.mds975.co.uk

Home | Contact | Site Map | Radio Stations & Memorabilia | Amateur Radio

Crystal Sets Introduction | Resistor & Capacitor Conversion Tables

Crystal Sets (Part1) | Build Your Own Crystal Set (Part 2)

Spider's Web Crystal Set (Part 3) | Crystal Set By Kenneth Rankin (Part 4) | Crystal Radio Links

CRYSTAL SETS 5: EXPERIMENTAL CRYSTAL SETS



Picture 1 - The Complete Experimental Crystal Set

THE POPULARITY of the crystal radio arises from its simplicity, and the fact that it needs no power supply. The circuit here allows for easy experiments with tuning, aerial and diode coupling, and frequency coverage. Wrong connections can cause no damage to any components.

A Crystal Set is more often than not used for the reception of medium and long wave radio, but short wave reception is also quite feasible. It will normally be possible to receive some of the stronger international radio stations.

This is adapted from an article that appeared in the 1970's in Everyday Electronics, and gave me almost endless hours of fun!

BASIC CIRCUIT

The basic circuit is shown in Picture 2 below. The coil L1 can be air cored, or have a ferrite rod placed in its winding. The variable capacitor C1, in conjunction with aerial-earth capacitance, tunes the circuit to resonate with the wanted radio station frequency. The diode D1 "detects" or demodulates the radio signal so that the programme is heard in the earpiece.

This basic circuit can be modified in various ways to obtain better performance.

EARPHONE

As most constructors will be using a Crystal Earpice to listen to the crystal set it is essential that a 47k Ohm resistor is connected across the earphone terminals (TB1/1 and TB1/2 in the diagram), i.e. in parallel with the earphone, otherwise results will be very quiet.

A High Impedance headset of 20k Ohms (20,000 Ohms) may give even better results, but these are very difficult to obtain , so unless you happen to already own such a headset the Crystal Earphone with 47k resistor will be the only option. An ordinary magnetic earpiece or Walkman headphones will not work with a crystal set.

ASSEMBLY

Construction is of a 'breadboard' type using a wooden board of about 165 x 130 mm. A 12-way block connector, TB1, is used to connected together the components and this is screwed onto the wooden board. The use of a block connector provides an easy method of connecting the components together and then subsequently rearranging them as the experiments progress.

Tuning capacitor C1 is screwed to a bracket made of some scrap metal which is then also screwed firmly down to the baseboard, see Picture 1 above. Thin plywood screwed to the front edge of the baseboard would also provide a suitable method of fixing the tuning capacitor to the base. A knob with pointer is fitted to C1, and a scale is drawn and fitted behind this.

Except for C1, all connections are made by the terminals of the 12-way terminal block as shown in Picture 4. Loosen the screws with a small screwdriver, insert the bared ends of the wires, and tighten the screws. The various locations on the terminal block, TB1, are also shown in the circuit diagram, Picture 2.

AERIAL AND EARTH

Crystal receivers need a long wire aerial preferably strung outside and about 25m long, or as long as is possible to install. If this is outside it should be high and clear of earthed objects as this will improve performance.

An earth is absolutely essential for a crystal set to work properly. The earth lead can be run to an earth rod or spike that is buried to a depth of about 1 meter into damp soil. Or it may be soldered to a bare metal can which is buried in damp soil.

It is feasible, though not recommended, that the earth lead can be connected to the earthing terminal of a hi-fi system or even to the bare metal case of a personal computer that is plugged into an earthed mains outlet, but is switched OFF.

Stranded, insulated wire, or purpose made aerial wire can be used for the aerial and earth leads.



Picture 2 - The Basic Circuit



Picture 3 - Photo Of The General Layout

INDUCTORS (The Tuning Coils)

The following four coils are suggested for initial use as L1 :

Coil 1: Make a thin card tube to slide on a 10mm diameter ferrite rod, and on this tube wind about 105 turns of 32 s.w.g. enamelled copper wire, side by side. Secure ends with sticky tape.

Coil 2: Make a similar coil to to coil 1 having about 15 turns of 24 s.w.g. enamelled wire on the card tube. Loops of cotton will help hold the ends in place.

Coil 3: Wind 9 turns of 20 s.w.g. bare tinned copper wire on an object about 20mm in diameter. Remove and stretch to separate the turns, to obtain a coil about 25mm long.

Coil 4: Make a similar coil to coil 3, but with 5 turns.

The Ferrite Rod

It will be necessary to have a ferrite rod of about 60mm to 75mm long available. Coils 1 and 2 will provide reception of medium wave and the longer short wave bands. Coil 3 should cover about 3 - 10MHz shortwave with the ferrite placed in it, or about 6 - 18MHz with the ferrite rod removed. Coil 4 should cover about 6 -13MHz with the rod in, and about 9 - 20MHz without the' rod.

It will be noted that as the ferrite rod is inserted, any particular signal has to be re-tuned by opening Cl. This arises because the ferrite increases the inductance of the winding, so less parallel capacitance is needed for the same resonant frequency.

EFFICIENCY CHECKS

Tune in a m.w. transmission using coil 1 which gives good headphone volume. Place a microammeter or multi-range meter on a sensitive range in series with the headphones. A reading of 50-100uA or more may be obtained, depending on aerial, earth, earphone resistance and resistor value, coil and detector efficiency and strength of signals at your locality.

Placing the ferrite rod in the coil and re-tuning should boost the meter reading to some extent. Surplus or other detector diodes can be tried by substituting them in turn and noting the meter reading. Improvements to the aerial (or earth) will also show up as a rise in meter reading.

If experimenting with a crystal earpiece, which gives no direct current circuit, the meter may be clipped across the phone leads, i.e. D1 cathode to earth.



Picture 4 - Baseboard Layout Of The Crystal Set

AERIAL COUPLING

The aerial loads the tuned circuit heavily when connected directly to the top of the tuned circuit, as in Picture 2. This damps the tuning action and it can be found that stations spread out all over the dial, which is unsatisfactory.

The series capacitor, C2 connected in Picture 5(a) reduces the loading and thus improves the sharpness of the tuning. A variable or pre-set capacitor of about 250pF maximum is most suitable. for this role, though it is possible to experiment with a variety of fixed value capacitors in this range also.

Connecting the aerial to a tapping on the coil, as in Picture 5 (b) also sharpens tuning. It may also increase volume. Try about 2 turns from earth for coil 4, or 4 turns from earth for coil 3.

Another method is to have a coupling primary, as in Picture 5 (c). This consists of a second coil, with about one third the turns of the original wound on top of the existing coil.

You can even combine these methods to find what arrangement best suits the aerial in use.

The diode can be disconnected from the end of L1 and taken to a spare position on TB1 for example location TB1/9. You can then run a flying-lead fitted with a crocodile clip from this position, connecting it to various tappings on the coil as required as in Picture 5 (d). This method also reduces loading on the tuned circuit.

Coils with spaced turns of bare wire are readily tapped. For other coils, small loops can be made every ten turns or so, and crocodile clips can be attached to these when selecting tapping points.



Picture 5 - Alternative Methods Of Aerial Coupling

SHORT WAVES

For shortwave reception, a good efficient outdoor aerial is certainly recommended. Evening listening in the region around 5 - 9MHz in often proves to be the most fruitful.

Since there is no amplification, as with a valve or transistor receiver, certain frequencies will seem to be completely dead at particular times of day. So if the crystal receiver works satisfactorily on medium wave and longwave, but no shortwave signals are heard, check again in the evening, or after dark, when conditions are different.

PARTS REQUIRED

C1	**365pF or 500pF Air Spaced Tuning Capacitor**
D1*	**OA47, IN34, OA81, OA90, OA91, IN94 or similar point contact small signal Germanium Diode** * The OA47 will be of particular interest since it has the lowest forward bias voltage of any of these diodes which will make the crystal set somewhat more sensitive and therefore louder. The US equivalent of the British OA47 is the IN34.
TL1	**High Impedance Headphones (20,000 Ohms)** **or Crystal Earphone**
TB1	**12-Way Plastic Screw Block Terminal**
Also Required:	**47 k Ohm Resistor for Crystal Earphone: Enamelled Copper Wire: 32 and 24 s.w.g. for L1: 20 s.w.g. tinned wire for L1: Ferrite Rod 10mm diameter x 75 mm long: 25m of wire for aerial: Wire and rod or spike etc for earth: Wood for base e.g. 10mm x165mm x 130mm: Scrap of metal of thin plywood for C1 bracket/front panel: Knob: Crocodile clip(s)**

Adapted from an article in Everyday Electronics magazine, November 1981, By F.G. Rayer.

HERE ARE A COUPLE OF VERY INTERESTING CRYSTAL SET DESIGNS SENT IN BY KRYSATEC - "THE RAT" - FROM THE CZECH REPUBLIC


Crystal radio
100p
LW / MW
2mH
500p
earphone
4kOhm
5n
180uH
500p
2x 1NN41
Made by Rat

1/ Using old coils from old bulb radio for MW and LW band. Though it would be straightforward to wind the coils - one for Long Wave, one for Medium Wave and a coupling coil. Variable capacitor is 2 x 500pF only one half is used: 500pF. For the crystal earphone a resistor of about 82k ohm in parallel is required. This set also uses two Ge diodes as a multiplier in the quest for for higher audio signal output.


Crystal radio with simple amplifier
100p
LW / MW
2mH
+3V
M22
M5
500p
25k
earphone
150R - 4KOhm
100n
5n
gnd
180uH
500p
2x 1NN41
102NU70
Ge diode
Ge transistor
Made by Rat

2. If signals are not strong signal in your location, then the above circuit design can be considered. A simple transistor amplifier is used. A variable resistor M22 is used for better sensitivity which can be adjusted for poor signals. This crystal radio is aversion from cca 1960 - 1970 y.



Rat's finished Crystal Set with additional amplification - very neat!

'Minilabs' Crystal Radio

BELOW: Ian Tomlinson kindly sent in a photograph of the box that contained the kit for his John Adams Toys 'Minilabs' Crystal Radio.

It is a very simple circuit consisting of the coil (inductor) with a sliding contact that provides variable tapping points, a diode and crystal earphone. All that is added is the aerial and earth. There is no variable tuning capacitor for simplicity and to keep costs down.

The coil provides the inductance required for tuning into a certain frequency (wavelength). These days a variable "tuning" capacitor is normally wired in parallel across the inductance (coil) in order to vary the resonance of the tuned circuit and therefore enable to easily tune into various transmitters on different frequencies. This crystal is tuned varying the number of turns on the coil (ie varying the inductance) by tapping off at different points using the sliding contact ("ball").

The crystal earpiece, or high Z headphone, is connected between the output of the detector diode (the other end from the coil) and earth. The volume from a crystal earpiece may be considerably improved by connecting a resistor of - somewhere between - 4.7 k and 47k ohms in parallel with the earpiece. A crystal earpiece cannot directly allow current to flow through it and the parallel resistor therefore allows current to better flow through the circuit.

John Adams Toys
Crystal Radio Kit
Make a radio complete with tuning coil, antenna and earphone.
Pack contains all you need including full instructions.
No battery required.
Ages 8–14

'Minilabs' crystal set by John Adams Toys

A discussion on configurations for Crystal Sets by Felix Scerri VK4FUQ

This discussion, by Felix Scerri VK4FUQ, was posted at this address which no longer appears on the web www.tarc.org.au/techinfo2.htm (error 404) so here it is reproduced:

Crystal Set design is one of my passions closely allied with my obsession for audio and high fidelity.

My main interest in crystal sets, apart from the wonder of a radio receiver that does not require a power source, is the potential excellence of the recovered audio quality from normal AM broadcast stations.

Personally, it is one of my great laments that most people have never heard how good wideband AM can sound. A high performance crystal set or similar TRF approach is, in my opinion,the only way to do it. There are a few people around who have heard the audible results of my efforts,and can only agree.

I have often wondered,given the ultimate simplicity of the crystal set, being essentially a tuned circuit,a diode detector and some form of output device, what it takes to achieve optimum performance. What follows are my thoughts on the matter.

Crystal Set optimisation, is in my opinion, all about reduction of circuit losses. Essentially this means high "Q" tuned circuits and high quality detectors. Efficient output devices also help too. But as we will see, there are some trade-offs required as well. A high "Q" tuned circuit is always benefical, as a high "Q" tuned circuit has lowest RF losses,highest potential selectivity,and highest voltage at resonance, which is very useful for the diode being fed from the tuned circuit. Variable capacitors, even the "modern" miniature variable capacitors (although the older air dielectric units, as used in old valve receivers are more desirable) for various reasons,are generally quite efficient, and a higher "Q" coil will produce the most worthwhile improvements.The best (highest "Q") coils are wound with "Litz" wire, which is a multistranded woven wire with all strands insulated from each other. The performance of Litz wire wound coils is spectacular, unfortunately, although I know Litz wire is still being made, from personal

experience, it is VERY rare in Australia.

Efficient coil design can be quite complex and all my coils are wound on ferrite rods. There seems to be,at least for ordinary single wire windings (close wound), an optimum wire thickness for optimum coil "Q". I have determined .315 mm winding wire to be about optimum for simple (single wire) coils on ferrite rods. Thicker wire is NOT better, believe it or not.

Lacking Litz wire, an interesting winding approach I have developed is to use two slightly thinner wires wound as a bifilar winding connected together at the beginning and end of the coil, yields considerably higher "Q" compared to a simple single wire winding. I have found 0.25 mm winding wire optimum in this application.

Whilst high "Q" coils are beneficial from the RF point of view, there is a possible downside. If one is interested in maximum selectivity and sensitivity, there is no problem, but remember highest "Q" results in a narrowed audio band-width as a simple consequence of band-width. For high fidelity applications this could be a disadvantage under some circumstances, although there are clever ways around this.

Regardless of ultimate coil "Q", selectivity is a major issue with crystal sets generally. Here another trade-off is evident. For the maximum voltage into the diode, connecting the diode to the high impedance end of the coil (i.e. the top) yields the greatest voltage but the selectivity is usually terrible, because of severe "loading" by the diode circuit. For this reason, tapping well own the coil improves selectivity at the expense of signal volume (reduced voltage). Once again there are ways around this. As described in my "Double Tuned Crystal Set Tuner" article in "Amateur Radio" magazine, March 2002, the use of two separately tuned coupled resonant circuits allows top connection into the diode without compromising overall selectivity, thanks to the use of a second tuned circuit which is fed from the external antenna. The whole network forms a double tuned input bandpass filter and in practice this approach works very well. For single coil crystal sets I recommend the use of an un-tuned "antenna" winding adjacent to the "hot" end of the main coil, preferably adjustable (old paper reels from sewing cotton threads are ideal). This allows the degree of coupling to be optimised under actual listening conditions. The double tuned set up is best, yielding superb selectivity, but the un-tuned antenna coil arrangement also works quite well, especially if the diode is tapped well down the main coil.Tapping halfway works well.

The other method of performance improvement involves the use of the most effective detector system possible. Here things get very interesting. In fact the temptation is to use more complex circuitry, but that gets away from the charming simplicity of the crystal set. As an example, my own crystal set tuner has at times mutated into a TRF tuner complete with FET RF preamplifiers, active(powered) detectors and other enhancements. These modifications do work well, but loses the simplicity of a basic crystal set. In actuality, a simple diode detector can work extremely well, subject to some qualification. Diodes like to work with a reasonable level of RF input voltage. Audio distortion can result under conditions of low signal level, due to diode transfer curve non linearity and other factors, such as the widespread use of broadcast station "processing". The actual type of diode makes a difference. The 1N34A germanium diode is very popular for crystal set use, although in my experience just about ANY germanium diode will work, although it is worth trying different specimens. Some are definitely better than others. Even from a pack of twenty 1N34A's from the same source, some were definitely better than others. Measuring the average value of rectified output voltage across the diode load resistor will show which diodes are best. By the way, I regard a diode load resistor as being mandatory. I find a value of about 47K about right, especially if a crystal earpiece is being used or the crystal set is being used as a tuner feeding an audio pre-amplifier and following amplifier. If using high impedance magnetic type headphones, the headphones provide the diode DC load.

Another type of diode that is very interesting, is the hot carrier diode. There seem to be a lot of different hot carrier diodes around these days. There are even hot carrier diodes now being sold as "germanium diode equivalents". I have tried them and they do work acceptably well, but they are not quite as good as genuine germanium diodes such as the 1N34A. Typical UHF mixer hot carrier diodes, such as the 1N5711 will not work well in crystal set service simply because their "turn on voltage"is too high, similar to silicon diodes such as the 1N4148/914 series, which require a lot of RF input to function adequately as RF detectors, however a simple technique can be used to turn hot carrier diodes such as the 1N5711 into superlative detectors.

I guess we are cheating a little, because the technique is to use a little voltage bias supplied via a 1.5v battery, through a simple potentiometer voltage divider arrangement, with capacitor (for DC isolation) fed into the diode from the tuned circuit. With applied adjustable bias, I find the 1N5711 diodes absolutely superlative detectors under ANY signal strength conditions. I find the detection quality also superlative, with a clarity and low noise profile unmatched by any other diode arrangement. In my opinion, hot carrier diodes, running bias,are the best detectors overall.

Regarding other detector arrangements, the diode "voltage doubler" is often recommended, however my own

experiments with the doubler arrangement have been inconclusive and slightly disappointing overall. I have found no real advantage in their use over a simple (one) diode detector, believe it or not.

Yes, they do work, but they're nothing special, at least in my opinion.

Any comments on this general subject of crystal set optimisation would be welcome.

73's Felix Scerri VK4FUQ.
22nd July 2002



Above: CRYSTAL SET BASED CIRCUIT PROVIDING A HIGH QUALITY PROGRAMME SOURCE

IMPROVED VERSION OF THE ABOVE CONCEPT !! New update from Felix Scerri February 2010:

New 'two FET infinite impedance AM detector'

I've developed a new version of my old favourite FET 'infinite impedance' AM detector that I think sounds very nice. I include a short audio of one of our local AM stations. I picked this station as it is my reference 'torture test AM station' as they run very heavy 'processing' which normally sounds yuck with all my other (diode and non diode) detectors! However it's quite clean with this detector. What do you reckon? I'll do up a circuit if you'd like to feature it in your TRF radio section. A general draft article follows.

'A favourite non diode based AM detector that I've built and used many times over the years is the FET based infinite impedance detector, offering very good general AM detector performance, especially under weak RF signal conditions where diode based detectors do not perform well, especially in terms of audio distortion.

However one of the slightly strange things I've noticed about the simple FET based infinite impedance detector is the variable audio quality noted, even when using the same type of FET. Some I've built have sounded good and others slightly fuzzy when used with an audio preamp and fed into a high quality audio system. I've been giving this a considerable bit of thought of late and I've wondered if the audio distortion might be a result not necessarily of the detection process itself, but the FET stage in its guise as a 'source follower' audio stage which essentially, it is.

I have long been aware that as a simple audio buffer stage, the FET based 'source follower' can exhibit a considerable amount of audio distortion, and a technique I've long used to greatly reduce this audio distortion is to use a second FET in the source lead of the first FET as a 'constant current source' which serves to 'linearise' and

greatly reduce audio distortion in the buffer stage overall. So, to test the theory I built a simple one FET infinite impedance AM detector which worked well, but with just a hint of audio 'fuzziness' on received AM stations. So I added a second FET in the source lead of the first FET wired as a constant current source, taking the output from the source of the first RF detector FET and the source resistor and RF bypass capacitor off the source lead of the second FET 'constant current source'. The result, totally clean audio! The theory seems proved! I call this modified detector the 'Two FET infinite impedance detector'

))) Here's what is sounds like - click to play the audio file (((

Here is the circuit diagram:



This detector has been a real eye opener for me in terms of its excellent performance, especially considering its circuit simplicity. Indeed in the past I have designed other more complex FET based infinite impedance circuits that do not quite work as well in practical terms as this latest circuit, at least according to my well calibrated ears!



I do not have access to any precise test equipment but my well calibrated ears tell me this 'two FET infinite impedance detector' is a beauty, surpassing practically every other AM detector I've built even at low RF input, and that's rather a impressive claim and the audio quality when used as an AM tuner feeding a high quality audio system is quite remarkable. Possibly the best thing about this detector is its excellent performance under weak signal conditions. Diode based detectors also work beautifully, but the use of an RF stage to ensure detection over a linear portion of the diode's curve is mandatory! This compound infinite impedance detector works

beautifully on the sniff of a useable RF signal.

Just add a high Q tuned circuit and that's it!

Felix Scerri
VK4FUQ

A better FET for the 'basic' Infinite Impedance Detector:

Quite recently by accident, I've realised the MPF102 FET that I've long used in my FET based infinite impedance detectors is possibly not the best FET to use. This was the reason why I developed the 'two FET' infinite impedance detector some time ago which works very well.

However I've found the choice of a more suitable FET works beautifully in the basic FET based infinite impedance detector circuit, which has appeared for many years in many editions of the ARRL Handbook.

I use the 2N5457 and others of the same 'family' may be equally suitable, but I haven't tried them! However with a 2N5457 in place of an MPF102, the basic infinite impedance detector has became my AM detector of choice. It works beautifully even at low signal input with lovely and clean low distortion audio along with a very high input impedance for good tuning selectivity. It's a beauty! The basic generic circuit is attached, courtesy of Rod Elliott's ESP website.

73 Felix VK4FUQ
10 / 02 / 2012.



The basic generic circuit is attached, courtesy of Rod Elliott's ESP website
Felix Scerri VK4FUQ

As often happens with me, my renewed interest in FET based 'infinite impedance detectors' of late has led to some interesting new research and I may have considerably improved the 'two FET infinite impedance detector' as a result.

My research suggests that although the use of a CCS (constant current source) reduces audio distortion in an audio stage, the value of the 'source resistor' in the CCS stage is somewhat critical for best results.

By using a potentiometer in lieu of a fixed resistor I have found that a resistance value of around 470 kohms cleaned up all overall audio distortion. I used an MPF102 as the CCS in this circuit. An interesting and worthwhile little circuit refinement.

73 Felix VK4FUQ
21 / 02 / 2012.

A Minimum Component Count High Quality AM Detector

I was generally messing around with various circuit ideas and I came up with this AM detector circuit, a simple diode detector along with a FET stage. It was an attempt to provide good performance along with minimum number of components. Actually I've been pleasantly surprised at the excellent level of general performance and the best of all, it sounds great!

The circuit is quite conventional being a BAT 46 diode detector feeding an MPF102 FET buffer/ common source amplifier stage. I would ordinarily use a FET source buffer stage in this application, but opted to use a simple low gain FET 'common source' amplifier stage instead, with excellent results. I also used a BAT 46 Schottky diode instead of an ordinary germanium signal diode.

This was done for several reasons. Firstly, germanium diodes are now very hard to find but in any case these 'germanium diode equivalent' Schottky diodes are actually a superior diode, having very low noise, almost zero back leakage and an essentially complete absence of carrier storage effects and very good weak signal sensitivity. I call these diodes high fidelity diodes as they sound wonderful as RF detectors.



Circuit Diagram of the Minimum Component Count AM Detector by Felix Scerri



Minimum Component Count AM Detector by Felix Scerri



A Closer View

The high impedance of the FET's gate circuit is perfect for optimal buffering of the diode detector, something very important for good low distortion diode detector performance. Apart from providing slight voltage gain, the use of the common source FET amplifier is a new idea, as this prevents the possibility of incidental RF rectification occurring in a FET source follower stage, which can happen. A 1 uf plastic film capacitor may be added in series with the audio 'hot' output lead to block the DC offset out of the FET drain, if required.

Despite no additional RF stage ahead of the diode, audio quality on even relatively weak RF strength stations is actually very good, and of course the audio quality will be even better with increasing RF signal strength, something which will also increase the audio output level. Just on this, for a long time I was somewhat negative regarding diode detectors, as one AM station locally (the strongest one) was always distorted when using a diode detector.

I strongly suspected a transmitter fault, but my complaints were ignored, until one day some time ago when all audio distortion suddenly disappeared! Nothing was ever 'said', but I realised that my suspicions of a long standing transmitter fault were correct, after all!

73 Felix
VK4FUQ
02 March 2012

Voltage Doubler Detector

This is an AM detector circuit that I've long known about and which worked ok, but never seemed to work as well as it should have. However I spent some time late last night trying to optimise the circuit, with some success.

It is a curious circuit being essentially a 'voltage doubler' originally developed for power supply applications, and its use as an AM detector is hard to analyse! It seems that the component values in the circuit are somewhat critical for good performance and if not, the performance is rather 'ordinary'. The circuit that I eventually came up with uses a 150 picofarad 'input capacitor' with a 150 kohm 'load' resistor and loaded into a FET common source voltage amplifier stage (as previously described) through a coupling capacitor with a 1 Mohm input resistance.



With these circuit values, it all works 'quite well'. Give it a go! It's an interesting AM detector with quite good 'sensitivity' and clean audio quality, and it seems to work well at low signal levels.

73 Felix
vk4fuq.

16th April 2012.

Simple AM detectors: What works best? A practical experimenters viewpoint.

I have written a lot about simple AM detectors for use as tuners for feeding into an audio amplifier, and it has been a long time interest. These days I use either diode based or 'infinite impedance' types of AM detectors. In this location our 'local' AM stations are quite distant and are therefore quite weak in terms of signal strength.

As such I find infinite impedance detectors based on field effect transistors give consistently better results for tuner applications due to their lower apparent overall detector distortion. Diode based detectors are quite 'fussy' as they require both optimal output buffering (AC/DC ratio) and an 'adequate' (beyond the diode knee) level of RF signal injection. http://www.tonnesoftware.com/appnotes/demodulator/diodedemod.html

Diode based detectors will happily 'detect' at very low signal levels, however the (inevitable) audio distortion that results, can be extremely irritating to the ear! Under these conditions I find infinite impedance detectors (even without additional RF preamplification and subject to individual FET characteristics), generally sound 'cleaner' and more pleasant to the ear.

FET's of course require a power source for operation whereas diodes are passive (un-powered) detectors (most of the time), however this is of no real advantage in a tuner application as an 'active' audio amplifier stage will generally be required anyway for audio level boosting, buffering etc.

In the end it will come down to a consideration of prevailing RF signal levels and other related circuit considerations at one's location. If local RF levels are strong, a well designed diode detector will give excellent results. If not, an 'infinite impedance' type of detector is most likely the better option unless one goes towards the option of additional RF preamplification prior to the diode detector.

73 Felix
vk4fuq.

17th April 2012.

ANOTHER DETECTOR by Felix Scerri !

I’ve tried diode based ‘voltage doubler’ (or more correctly ‘diode integrator’) AM detectors before with indifferent results, however the other day, just trying a few ideas I came up with this version that works rather well, with low audio distortion, high audio output and really ‘nice’ audio quality and the best of all, it seems to work very at very low RF input level.

The two diode ‘voltage doubler’ detector using two BAT 46 silicon schottky diodes feed directly into a MPF102 source follower stage set at 1 Megohm input resistance. The ‘input’ capacitor feeding the diodes from a tuned circuit is 68 picofarads.

I have the simple RF filter right on the output of the FET stage. In that respect this circuit is vaguely similar to the old ‘Selstead-Smith’ valve AM detector of the past. An interesting one! I am very happy with its general performance. Regards, Felix vk4fuq 11/04/2013



Felix Scerri VK4FUQ

UPDATE - JUNE 2013

G’day all, readers may recall the two FET infinite impedance detector I developed some time ago. That circuit worked well, but some samples of the MPF102 regretfully produced distorted output. However a recent discovery has resulted in an improved version that has truly exemplary performance.

The MPF102 is in all honesty a device essentially designed for VHF applications, but is often used in simple audio applications albeit with occasionally indifferent results, due to general device parameter ‘spread’. More or less by empirical trial and error I have found that a simple change in source resistor value to 100 k (from a much lower value), pretty well fixes everything.

In a FET source follower circuit this is interesting as the output impedance is actually a lot lower than 100 k due to the action of the FET’s transconductance. It is similar to the action of a bipolar transistor emitter follower circuit. In fact a simple infinite impedance detector with a 100 k source resistor actually works very well and will be good enough for many applications, however the addition of a second FET as a constant current source does markedly reduce overall audio distortion in the stage overall, and produces very clean and low distortion audio quality and also reduces the output impedance considerably (good for tuner applications), so take your pick!

Regards, Felix vk4fuq 02/06/2013.

UPDATE - JANUARY 2014
A simple modification to the basic FET 'infinite impedance' AM detector that dramatically improves performance.


VERY LOW DISTORTION A.M. DETECTOR.
(INFINITE IMPEDANCE)

17/01/14
FELIX SCERRI.
VK4FUQ.

G’day all, over the Christmas break just messing around I worked out (mostly by accident), a simple modification for the simple FET based ‘infinite impedance’ detector circuit that dramatically improves weak signal performance and also greatly reduces audio distortion.

Essentially by the addition of another FET ‘buffer’ stage, another source follower, capacitively coupled from the first detector stage. The circuit is actually a simplified version of the circuit that I described in this link, http://sound.westhost.com/articles/am-radio.htm (figure 6) and testing the two head to head, they both sound superb and the simpler version is actually somewhat easier to build. I cannot get over how low distortion and ‘nice’ the recovered audio sounds. It is a joy to listen to!

Regards, Felix vk4fuq 12/01/2014.

Diodes for ‘weak signal’ crystal set applications.

As I am primarily interested in using crystal sets as AM tuners for feeding into a preamplifier/amplifier and loudspeakers, the actual type of diode can be relatively critical. In a strong signal area, not so much, but in a weak signal area such as where I reside, definitely. A diode with a good ‘square law’ performance (the area below the ‘knee’ in the diode curve), generally results in much cleaner and lower distortion than other good performing diodes, and believe me diode distortion under weak conditions, even with optimised diode ‘buffering’ used is very nasty sounding to the ear!

Testing many, many diodes in actual working crystal sets and listening critically to the audio output, it seems to me that the best diodes to use under weak signal conditions are the so called ‘gold bonded’ germanium diodes. I have sampled many different gold bonded germanium diodes and they all work well in this specific application, although sometimes the rectified output voltage may not be as high as other germanium or silicon schottky diodes, however the audio quality is much cleaner and shows much less apparent distortion!

I have tried OA5, OA47, IN141 and several ‘CG’ gold bonded germanium diodes with consistently excellent results. Other ‘ordinary’ germanium diodes may also work well under weak signal conditions, but they will need to be tested individually to check actual performance in a working circuit. One thing that I have noticed about germanium diodes is that due the ‘point contact’ nature of their construction, even diodes of the same specific type can exhibit rather different levels of performance!

The otherwise very good BAT46 silicon schottky diode works extremely well at good RF input level but not so well at weak RF input, especially when heavy broadcast ‘processing’ (commonplace these days), is used. New ‘gold bonded’ germanium diodes are probably no longer made although I am aware that they can be purchased through vendors over the internet. Apart from that, they may be found in old gear. As stated earlier, ordinary germanium diodes may be quite good but will need to be checked individually. Diodes are complex things!

Felix (vk4fuq). 29/01/2014.

* * * * * * * * * * * * * *

Just when I thought that I’ve tried everything I realised that I’ve not tried a voltage doubler (diode integrator) detector with an RF stage in front. It is an unfortunate fact that all diode detectors ‘need’ a good RF injection level (and buffering) or audio distortion becomes ‘bad’ (an understatement!)

Consider yourself very lucky if you live in a strong signal area! (unfortunately I don’t). Anyway I quickly built a couple of prototypes which worked ok but not as well as hoped. Initially I tried using a source follower buffer (no voltage gain), but converting it to a common source amplifier (with appreciable voltage gain), seemed no better, which was strange.

After staring at my prototype for what seemed like forever with my magnifiers on, I (finally) realised my mistake. A common source stage takes its output off the ‘drain’ terminal of the FET, not the ‘source’ terminal as it does with the FET source follower buffer stage. I shifted one wire, and all worked as expected and it sounds fantastic! All diode detectors (one diode envelope detectors, doubler detectors etc), need good RF input and a simple untuned FET RF gain stage works very well. As to the sound, it sounds great.

73 vk4fuq 10/03/2014.



Felix Scerri's FET Crystal Set with Voltage Doubler

A 'nice sounding' AM detector - update October 2015

Looking through these pages the other day I was slightly shocked to realize that I've completely forgotten about some of the circuits that I've contributed in earlier days! They all work pretty well, however in my advancing older age and a little like my tastes in high fidelity generally, I'm starting to show a particular preference for 'nice sounding' bits of audio gear.

I guess that this also means low noise/low distortion too, although with AM broadcasting, at least in this country and probably elsewhere in the world too, the very common use of broadcasting 'processing' tends to make it hard for AM detectors generally, often resulting in a 'hard/compressed' sort of sound although still low in distortion, is not 'nice sounding', if that makes any sense!

Well of all the AM detectors that I've tried and/or developed, only one sounds 'nice' when confronted by heavy broadcast processing and that is an AM detector 'based' on a voltage doubler/diode integrator circuit (similar to the above circuit, actually the 68 pf capacitor should be changed to .1 uf, for slightly greater output).

It has taken me a very long time (years) to 'optimise' this circuit, but as it presently stands this is my favourite 'nice sounding' AM detector, and gets most use for general high quality listening on the AM broadcast band. It sounds really good! It somewhat reminds me of an old OA47 gold bonded diode detector from years ago before such abhorrent 'processing' became commonplace!

Ah yes the OA47….now that is a lovely sounding detector diode!

Regards, Felix vk4fuq. 17 / 10 / 2015.

* * * * * * * * * * * * * * *

That's it for crystal sets. I hope you try building one, it's easy and great fun!

See some useful links below....

73's
Mike

Crystal Sets (Part1) | Build Your Own Crystal Set (Part 2)

Spider's Web Crystal Set (Part 3) | Crystal Set By Kenneth Rankin (Part 4) | Crystal Radio Links

Amateur Radio
M0MTJ
Visit my amateur radio pages
M0MTJ

Visit my Amateur Radio Pages >

No AM radio stations or transmitters in your locality or country?

Spitfire
AM Transmitter

Has your local medium wave broadcast station closed or been moved to VHF/FM or Digital? Don't worry. You can still build and experiment with crystal sets and TRF radios by also buying or even building a simple low power AM transmitter. So, not only can you use your crystal sets but you can also run your own radio station that can be heard in and around your home - playing the music or programmes that you want to hear!

SSTRAN AMT3000 Superb high fidelity medium wave AM transmitter kits from SSTRAN. Versions available for 10kHz spacing in the Americas (AMT3000 or AMT3000-SM) and 9kHz spacing in Europe and other areas (AMT3000-9 and AMT3000-9SM). Superb audio quality and a great and well designed little kit to build: http://www.sstran.com/pages/products.html

POWER
GAIN
MODULATION
COMPRESSION
SSTRAN
AMT3000

http://www.sstran.com/

Other AM transmitters available:

Spitfire & Metzo Complete, high quality ready built medium wave AM Transmitters from Vintage Components: http://www.vcomp.co.uk/index.htm Vintage Components offer a choice of the high quality Spitfire and Metzo transmitters:

SPITFIRE AM Medium Wave Transmitter with 100 milliwatt RF output power:

http://www.vcomp.co.uk/spitfire/spitfire.htm

Spitfire
AM Transmitter

METZO AM Medium Wave Transmitter with built in compressor:

Gain
Comp
Mod
Metzo

http://www.vcomp.co.uk/metzo/metzo.htm

AM88 LP A basic AM transmitter kit from North County Radio.
http://www.northcountryradio.com/Kitpages/am88.htm

LINKS: Fine links to more Crystal Radio websites here

Component Suppliers: Links to electronic component suppliers here

Amateur Radio
MØMTJ Visit my amateur radio pages MØMTJ

Visit my Amateur Radio Pages >

Crystal Sets (Part1) | Build Your Own Crystal Set (Part 2)

Spider's Web Crystal Set (Part 3) | Crystal Set By Kenneth Rankin (Part 4) | Crystal Radio Links

^Top Of Page

Home | Contact | Site Map | Radio Stations & Memorabilia | Amateur Radio

Crystal Sets Introduction | Resistor & Capacitor Conversion Tables

www.mds975.co.uk © 2004 - 2015

May 9 2018, 4:29:05 pm

MY WEATHER STATION, BY DIMITRIS

Location: Peristeri of Athens, Greece
Position: 38° 00.58' NORTH / 23° 42.04' EAST
Elevation: 63 meters
contact me at meteo@otenet.gr

Click to enable Adobe Flash Player

Home Page | Lightnings | External Data | NEW My Projects | Knowledge | Friendly Sites | Photo Album | Guestbook | About

SWITCH TO CONTENTS

RF field strength meter version 1.

I made a RF simple field strength meter for test the remote control from doors ,alarm e.t.c at frequency VHF-UHF, i used one μA meter ,2 diodes ,2 ceramic capacitors,a potentiometer,a box ,and one telescopic antenna.When press the button at remote control,output there is small current RF,where with this simple circuit ,easy i can to know if remote controls it work or no.

Here it is the electronic design



Here it is the electronic material,without yet the potentiometer 47 Kohm, 2 capacitor 18 pF,2 diodes BAT 41,and a μA meter

Here it is the plastic box,i have open holes for μA meter ,and i have touch the telescopic antenna

Here with soldering iron the components it is ready



Here it is the sensitivity test

Here it the test with remote temperature /humidity sensor

It is ready

Ready with full open telescopic antenna

Click over to photo for to see a video about it

Click here for to see video
03/08/2009
Click here for to see video

RF field strength meter version 2.

I made a second version.The electronic design i saw from Here.

Here it is a electronic design.I left the old potentiometer 47 kohm and the μA meter 100 μA.


FSM
Telescopic
Whip
SW1
9V
2N3819
OA91
3M3
100p
10k
See
Text
L1

Here i added this electronic material.One transistor JFET 2N3819,one diode germanium AA119,one cap 100 pF,one resistor 3,3 Mohm,one clip 9 volt battery,one battery 9 volt,one switch on-off,and one inductor over ferrite 1,82 μH.

I use a coil over to ferrite about 1,82 μH (i removed little coil for it is about 1,82 μH)

Here i added a switch on-off,and i put the aerial antenna to other side.

From the other side.

I finnish with the soldering iron material.



RF field strength meter,It is ready

Here i make a test with out remote sensor from weather station at frequency 433 Mhz.

Here i make a test with remote control 433 Mhz

Here i make a test with mobile phone 1,8 Ghz.

Click here for you see a video

µA
04/01/2012

Click here for you see video
04/01/2012
Click here for you see video

PHGN 300
Crystal Radio
(in 45 minutes)


PORTABLE
RADIO KIT
P100

Ground Wire

Antenna
Need double
length

PORTABLE
RADIO KIT

Please put away like
this when done!


Variable
capacitor
P100
Medium
Moyen
Mediano
GaAs Diode
Ear piece


Pizoelectric
Ear phone
Inductor
Germanium
Diode
Connect
Antenna
Here
To Ground
Connection
Variable
Capacitor

Crystal Radio in 45 minutes.

Work in groups of 4.

2 people should assemble the radio and connect the ground wire.

2 people should string the antenna

If you get your radio to work using the GeAs diode,

Try the Gallinium + Cat Whisker

Return everything the way you found it before leaving


Copper Wire
“Cat’s Whisker”
Galena Crystal
Shottky Junction

The radios **must** have a good ground connection and a long antenna. Long means 100’-200’ of antenna wire outside. 200’ is better

Two possible routes are shown here. Use one.

Attach to tree branches you can reach.

When crossing a sidewalk, make it high so pedestrians don’t have to duck (they won’t).

You will take antenna down when class ends.


Kafadar Commons
Meyer Hall
Illinois St
16th St
Alderson Hall (Ah)
Berthoud Hall (Be)

REMOTE RF BATTERY CHARGING

Hubregt J. Visser[1*], V. Pop[1], B. Op het Veld[2], R.J.M. Vullers[1]
[1]imec/Holst Centre, Eindhoven, The Netherlands
[2]Philips Research, Eindhoven, The Netherlands
Huib.visser@imec-nl.nl

Abstract: The design of a remote RF battery charger is discussed through the analysis and design of the subsystems of a rectenna (rectifying antenna): antenna, rectifying circuit and loaded DC-to-DC voltage (buck-boost) converter. Optimum system power generation performance is obtained by adopting a system-level integration strategy. Our approach differs from the state of the art, i.e. interconnecting optimized subsystems which would lead to a sub-optimum system.

Keywords: battery, antenna, rectenna, RF, charging, remote, maximum power point, buck-boost, converter

INTRODUCTION

A general Microwave Power Transmission (MPT) system is shown in Fig.1. In the far-field of a transmit antenna, a receive antenna picks up part of the propagating radio waves. This antenna is connected – through an impedance matching network – to a rectifying circuit, where the Radio Frequency (RF) signal is converted into a DC signal. This DC signal is used to power an application or charge a battery. The combination of the *rect*ifying circuit and ant*enna* is commonly denoted as *rectenna*.



Fig. 1: General MPT system.

For charging batteries at a large distance we need to maximize the rectenna's output voltage. Thereto we may employ passive voltage multiplication techniques in the rectifier circuit and/or use (RF) voltage boosting.

RECTIFIER ANALYSIS

The rectifying circuit will consist of a single Schottky diode or a cascade of Schottky diodes.

A. Single Schottky Diode

In Fig. 2 we show the equivalent circuit for a packaged diode. Herein, d denotes an ideal diode, C_j is the junction capacitance, R_s is the bulk series resistance and L_p and C_p are the packaging parasitic inductance and capacitance, respectively. The values may be found in the diode's datasheet.

This packaged diode will be terminated with a load, consisting of a parallel circuit of a load resistor and a load capacitance and will be excited by a voltage source V_g with internal resistance R_g, see Fig. 2. V_g and R_g represent the antenna in our rectenna, see Fig. 1.

A thorough Runge-Kutta (RK) analysis revealed that for $C_L \geq 0.1\mu F$, for most commercially available Schottky diodes in the frequency range from 0.1 to 2.5GHz, the load may be considered to be a short circuit.



Fig. 2: Packaged diode with source and load.

For the short-circuit load, the input impedance is obtained in a very time-efficient way applying the RK. Fig. 3 shows the real and imaginary part of the input impedance as a function of the available input power for the AVAGO HSMS-2850 Schottky diode at 2.45GHz thus obtained.



Fig. 3: Time domain analysis results for HSMS-2850 diode at 2.45GHz.

When the $R_L C_L$ time is orders of magnitude larger than the microwave voltage period, the time-domain circuit equations tend to become stiff and the RK analysis becomes extremely time-inefficient.

Therefore, for the DC modelling, we employ the Ritz-Galérkin averaging method described in [2]. For the unbiased diode, the relation between output voltage

V_o and available antenna power P_{inc} is given by

$$\mathbf{I}_0\left(\frac{q}{nkT}\sqrt{8R_gP_{inc}}\right)=\left(1+\frac{V_o}{R_LI_s}\right)e^{\left(1+\frac{R_g+R_s}{R_L}\right)\frac{q}{nkT}V_o}, \qquad (1)$$

where $\mathbf{I}_0$ is the zero-order modified Bessel function of the first kind, q is the electron charge, n is the diode's ideality factor, k is Boltzmann's constant, T is the temperature in Kelvin and I_s is the diode's saturation current. Again through a RK analysis we found that the frequency-independence of equation (1) is justified and the outcome of the equation is good compared to a RK analysis for load resistors $R_L \geq 1k\Omega$ and fair for $R_L < 1k\Omega$ in the frequency range 0.1 - 2.5GHz. This is demonstrated in Fig. 4 that shows the output voltage as a function of available input power for the AVAGO HSMS-2850 Schottky diode [3], as calculated with equation (1) and as obtained with a RK4 method. The region of interest for energy harvesting is $P_{inc} \leq 0$dBm.



Fig. 4: RK and approximate V_0 for several R_L at 2.45GHz.

In the next section, we will apply the analysis method for voltage multiplyers.

B. Voltage Multiplication

The most basic voltage multiplier is the voltage doubler, see Fig. 5(a).



(a) (b) (c)

Fig. 5: Voltage doubler. (a) Circuit. (b) RF-equivalent circuit. (c) DC-equivalent circuit.

Whit an RF signal applied to the doubler the capacitors will act as short-circuits and the input impedance will halve with respect to that of a single diode, see Fig. 5(b). For DC, the capacitors will act as open circuits and the diodes will become voltage sources in series connection, see Fig. 5(c). Since, for the doubler, RK analysis is prevented by stiff equations and an implicit equation using the Ritz-Galérkin averaging method does not exist, we apply the following approximation. We may analyse the doubler as a single diode if, in equation (1) we double R_g (to obtain the same current flowing into the circuit) and halve R_L (to obtain the same current flowing out of the circuit). We do not double the output voltage as mentioned in [4]. We may extend the circuit in Fig. 5(a) to a n-times voltage multiplier, employing n diodes. We now use equation (1) wherein we multiply R_g by n and divide R_L by n.

Fig. 6 shows the measured and calculated output voltage as a function of P_{inc} for a voltage doubler. A fair agreement between model and measurement results – good enough for design purposes - is shown. For $n \geq 4$, measurement and calculation results start to differ substantially, the resistance of the capacitors is believed to be the main reason for this difference.



Fig. 6: Modelled and measured output voltage of a doubler circuit.

A recently claimed way of increasing the output voltage is by increasing the RF voltage at the input of the rectifier.

RF VOLTAGE BOOST CIRCUIT

The RF voltage boost principle is best explained by virtue of the lossless, LC-circuit shown in Fig.7.



Fig. 7 Example RF voltage boost circuit.

The voltage gain G_V of this circuit may be calculated as

$$G_V = \frac{V_{out}}{V_{in}} = \frac{1}{1-\omega^2 LC}, \qquad (2)$$

where $\omega = 2\pi f$ is the angular frequency. At resonance ($\omega^2 LC = 1$) the voltage gain becomes infinite. To boost the RF voltage at the input of the rectifier circuit, we place a reactive L-network between the antenna and rectifier of Fig.3 [5], see Fig.8



Fig. 8: Rectenna with RF voltage boost circuit.

Since the RF voltage boost circuit is assumed to be lossless, the output power must equal the input power:

$$P_{out} = \frac{1}{2}V_{out}^2\,\mathrm{Re}\{Y_L\} = P_{in} = \frac{1}{2}\left|\frac{1}{1+R_gY_{in}}\right|^2 V_{av}^2\,\mathrm{Re}\{Y_{in}\}. \quad (3)$$

For a maximum power transfer the electronics circuit is matched to the antenna, so that

$$R_g = \mathrm{Re}\{Z_{in}\} \wedge \mathrm{Im}\{Z_{in}\} = \mathrm{Im}\{Y_{in}\} = 0 \quad .(4)$$

With equations (3) and (4) the voltage gain is calculated as

$$G_V = \frac{V_{out}}{V_{av}} = \frac{1}{2}\sqrt{\frac{\mathrm{Re}\{Y_{in}\}}{\mathrm{Re}\{Y_L\}}} = \frac{1}{2}\sqrt{1+\left(\frac{B+B_L}{G_L}\right)^2}. \quad (5)$$

For a compact design, we incorporate Z=jX into the antenna [1]. The antenna impedance Z_{Ant} then becomes

$$Z_{Ant} = R_g + jX = \frac{G_L}{G_L^2+(B+B_L)^2} + j\frac{B+B_L}{G_L^2+(B+B_L)^2}. \quad (6)$$

Equation (5) leaves the impression that for a load admittance $Y_L=G_L+jB_L$ the output voltage level may be controlled by circuit component Y=jB. It is true that the voltage *gain* G_V may be controlled by jB, but this is not true for the parameter that really matters, i.e. the output voltage V_{out}.

The available antenna voltage V_a is given by

$$V_{av} = \sqrt{8R_gP_{inc}}, \quad (7)$$

where P_{inc} is the available power incident on the receive antenna. Substitution of equation (6) in equation (7) and using equation (5) leads to

$$V_{out} = G_VV_{av} = \sqrt{\frac{2P_{inc}}{G_L}}. \quad (8)$$

So, *none of the RF voltage boost circuit components can actually be used to increase the output voltage.* We may even leave out the admittance Y=jB. To increase the voltage V_{out}, we need to realize a rectifying circuit with a minimum G_L-value. In case of using a single Schottky diode, we need to select one with a very low G_L-value, when RF short-circuited.

ANTENNA

The antenna needs to have sufficient geometrical parameters to tune for realizing the desired (complex) input impedance. Moreover, we need a model for analysis and design of the antenna. For rectennas on objects we employ a rectangular microstrip antenna [1, 6], see Fig. 9(a). For free standing applications we employ folded dipole array antennas [1, 7], see Fig. 9(b).



(a) (b)

Fig. 9: Rectenna using a microstrip patch antenna (a) and a folded dipole antenna (b).

DC-TO-DC CONVERTER

The voltage of a single rectenna element (V_o) will be too low to charge most batteries directly. Fluctuations on the incidental power (P_{inc}) will further hinder the battery charging. Both imply that a DC-to-DC converter is needed to adapt the rectified voltage to the voltage of a battery or super-capacitor. Furthermore, the input resistance of the converter should be designed to set the rectenna circuit at its maximum power point (MPP). The rectenna's output power ($P_{dc}=V_o^2/R_L$) can be derived from $V_o(R_L,P_{inc})$ see equation (1) . Figure 10 shows P_{dc} vs. V_o for several values of P_{inc}. The red dots reveal the maximum power point (P_{mpp}) locations and the related voltages (V_{mpp}).

P_{mpp} and V_{mpp} can be translated to a load resistance (R_{mpp}). The input resistance of the DC-to-DC converter should be identical. The dependence of R_{mpp} on P_{inc} is shown in Figure 11. The curve is considered 'flat' enough to be represented by a constant resistance in the antenna incident power range of -10 to 0 dBm.

An unregulated buck-boost converter operating in the discontinuous conduction mode (DCM) is used to achieve a constant input resistance R_{dc} see Figure 12.

The converter's input resistance $R_L=R_{dc}$ is given by

$$R_{dc} = \frac{2L_c}{f_st_s^2}, \quad (9)$$

where L_c is the inductance of coil L_c, f_s is the switching frequency of the oscillator and t_s is the on-time of switch S_c. This means that R_{dc} is constant only if the term $f_st_s^2$ is constant because L_c has a fixed value.



Fig. 10: Rectified power (P_{dc}) and voltage (V_o) for several P_{inc}. The red dots indicate the maximum power.



Fig. 11: Optimal load resistance (R_{mpp}) vs. P_{inc}.



Fig. 12: DC-to-DC discrete buck-boost converter.

Both f_s and t_s are set by the oscillator which is based on a positive feed-back (3 times R_{hys}) and a delayed negative feed-back (R_l, R_h, D and C_{osc}). Assuming that the diode forward voltage drop of D is negligible, both feed-back paths scale with the oscillator's supply voltage (V_{sup}=V_{dc}+V_{bat}) which makes timing independent of V_{sup}. Equations (10) give the expressions for t_s and f_s.

$$t_s = \alpha R_h C_{osc},\quad f_s = \frac{1}{\alpha(R_l + R_h)C_{osc}},\quad \alpha = \ln\left(\frac{\frac{2}{3}V_{\sup} - V_d}{\frac{1}{3}V_{\sup} - V_d}\right). \quad (10)$$

The converter may charge a battery within a voltage range of 2.1 to 4.5V assuming a rectenna voltage range V_o of 0.21 to 1V (DC). An input under-voltage lockout of 210mV is used to prevent battery discharging due to inefficient conversion. A battery over-voltage lockout is used to protect the battery from overcharging.

Figure 13 shows the measured output voltage (V_{bat}) and power efficiency as a function of the input voltage (V_{in}=V_{dc}) for three values of the circuit feeding voltage (V_{scr}). The inset shows the circuit.



Fig. 13: Measured output voltage and power efficiency as a function of input voltage.

WIRELESS BATTERY CHARGING

A system consisting of a rectenna with voltage doubler, a DC-to-DC converter and a Li-Ion rechargeable battery for a 3-4.2V voltage range has been realized and subjected to an incident RF signal (EIRP≈1.2W). In comparison with a non-optimized system, using the same rectenna, battery and incident RF signal, an increase in working distance of 164% was achieved, going from 25 to 66cm.

CONCLUSIONS

The subsystems of a wireless RF battery charger are analyzed and designed for obtaining a maximum battery voltage. It is shown that including resonant circuits in the rectenna does not increase the voltage level. Using a voltage doubling rectifyer and designing a DC-to-DC converter matched to both the rectenna and the battery does lead to voltage maximization.

REFERENCES

[1] H.J. Visser, *Approximate Antenna Analysis for CAD*, John Wiley & Sons, Chichester, UK, 2009.

[2] R.G. Harrison and X. Le Polozec, "Nonsquarelaw Behavior of Diode Detectors Analyzed by the Ritz Galérkin Method", *IEEE Trans. Microw. Theory Techn.*, Vol.42, No.5, pp.840-846, May 1994.

[3] -, "HSMS-285x Series", *Datasheet*, Avago Tech., 2009.

[4] -, "Designing the Virtual Battery", *Application Note 1088*, Agilent Technologies, 1999.

[5] A. Shameli, et al., 'Power Harvester Design for Passive UHF RFID Tag Using a Voltage Boosting Technique', *IEEE Trans.Microw. Theory Techn.*, Vol. 55, No. 6, pp. 1089-1097, 2007.

rexresearch.com

Roy J. MEYERS

Absorber

How To Patent Your Idea
3 Easy Steps To Patent & Make Money Get A Free Patent & Invention Kit
www.Patent.InventionHome.com

Superior X-Ray Solutions
Performance, Reliability & Speed from the world leader in SCD
www.Bruker-AXS.com

Do You Have an Idea?
We Can Help Turn Your Idea Into A Real Product. Get Free Information!
NewProductHelp.com

Buckyballs Magnetic Toy
Get the Gadget on Everyone's List. Best prices on this year's hot toy!
www.getbuckyballs.com

Car Door Magnets: 50% Off
Magnetic Car Signs $4.99. No Mins. Full-Color. Upload Photos & Logos!
www.Vistaprint.com

Power Your Own Home
Reduce Utility Bills by 50% Lower C02 Emissions by 1/3
www.ClearEdgePower.com

Ads by Google

Renewable Clean Energy
Compact Electricity & Heat Unit For Homes & Small Businesses
www.ClearEdgePower.com

Do You Have an Idea?
We Can Help Turn Your Idea Into A Real Product. Get Free Information!
NewProductHelp.com

Patent Attorney/Engineer
Over 36 years experience. Staff available 24/7 by phone.
www.invention.net

C. Edholm: "Picks Power from Air" (*Technology World Magazine*, 1912 ?)
Dr L. Hirshberg: "Electricity from Air New Great Discovery (*Modern Electrics*, 1914 ?)
Roy J. Meyers: British Patent # 1098 (1913) -- Improvements in and Relating to Apparatus for Producing Electricity (PDF Format, requires Adobe Reader)
R. J. Meyers: British Patent # 1098 (1913) --- Transcription w/ enlarged figures
Notes & Comments
R. J. Meyers: British Patent # 1098 (1913) --- JPG version

***Technology World Magazine*, p. 279-281 (Year unknown, apparently circa 1912; another article about Meyers appeared in the November 1912 issue of *Electronic World*)**

"Picks Power from the Air"

by
Charlton Lawrence Edholm

A remarkable scene took place in the legislature of Arizona this spring when the lawmakers enthusiastically voted for the parole of a certain convict in the State penitentiary, granting him a leave of absence for 30 days and by means of private contributions raising a fund to defray his expenses to Washington DC and return.

The prisoner, Roy J. Meyers, is serving a 3-1/2 year sentence, but in spite of the fact that he bears the stigma of a convicted lawbreaker, he has demonstrated that a convict can be a useful member of society. During his imprisonment he perfected an electrical device of such original character as to arouse feelings of wonder and skepticism until experts had seen it in actual operation. It is a device to draw electricity from the atmosphere for light and power, and the 30-day parole was granted in order that the inventor might protect his rights through the patent office at Washington.

With the acquiescence of the legislature, Governor Hunt granted the parole and the prisoner was allowed to go free without any guard or any assurance but his word of honor that he would return. Two days before the period had elapsed, Meyer again presented himself before the governor, having accomplished his mission, and then returned to the penitentiary at Florence, where he continues to serve his sentence.

This, in brief, is the picturesque story which has called attention of the civilized world to a newly discovered electrical genius, and to another feature of the case which is of equal importance and human interest; namely, the enlightened policy pursued by our youngest State in its treatment of convicts...

Before entering the prison, Meyer had already applied for various patents, among them one for an improved trolley wheel head which prevents the trolley wheel from jumping the wire. Meyers had a conference with Superintendent Sims and Parole Clerk Sanders, and it was to these gentlemen that the inventor first explained the principles of his new device for securing electrical energy from the air. The officials were willing to give the man the opportunity to develop his plan and a little wooden building outside the walls was turned over to Meyers and was fitted up as a workshop and a laboratory. The first demonstration of the new apparatus was made shortly thereafter, the electricity drawn from the atmosphere being used to spark the gas engines of the pump house, and although the device was crude yet it did the work, and removed the doubts of his friends. Furtter development of the "absorber" followed, and his second model was constructed, and developed 8 volts. The machine came to the attention of the remarkable woman who brought his name before the legislature.

This was Miss Kate Barnard, State Commissioner of Charities and Corrections of Oklahoma, who was a guest of Mr. Sims, while studying prison conditions. She saw the machine at work, became familiar with the facts of Meyers' case, and was impressed by his rather blunt and unaffected personality, for Meyers has nothing of the polish or glibness of the poseur. He is a simple, earnest student of mechanical problems and not the sort of man to make a sentimental appeal for sympathy because of any grace of person or manner. Therefore it was the value of Meyers' invention, together with his essential integrity (in spite of his lapse) which so strongly impressed Miss Barnard that when she appeared before the Arizona legislature not long afterwards, addressing that body on the need of enlightened legislature along the line of her own work, she told the story of Roy Meyers and his epoch-making invention.

So, early in May, Meyers set out for Washington, unaccompanied.

In his own words: "When I arrived in Washington and laid my plans before the patent office experts, they merely smiled and told me that I would have to build a model and demonstrate my claims --- that it seemed strange that I, unknown as I am in the electrical world, should have accomplished the things for which Edison, Tesla and other experts have been striving for years.

"They could grasp the meaning of my drawings nor the explanation I tried to make to them. There was little time to spare, as I had only 20 days left of my leave, but I set to work in a few days was able to take a crude model around to the patent office to make a demonstration.

"Arriving at the patent office I telephoned to a friend who had been so kind as to introduce me and aid me in reaching the proper officials. The absorber was hoisted on two short poles and made to work. While they were as yet unable to understand the principles involved and hardly willing to believe their eyes, they were forced to admit that I had something new and different, and they told me that there would be no further objection; that I might file my application without further delay.

"I hope to construct my first large machine right here in Phoenix. I feel grateful; to Governor Hunt and others for what they have done for me and to the help they have given in securing protection I might not otherwise have had, and I am desirous of demonstrating this gratitude. I am going back to Florence today to resume the serving of my sentence, which will expire in 10 months. Then, here in Phoenix, I will begin the work of making my machines."

While there are some details of the device which the inventor refuses to make public, yet there are many general features that may be explained. It is planned that the machine, to be set up in Phoenix, will generate sufficient power to light the city, and will consist of a 200 foot tower upon which is placed the "absorber". The latter consists of a series of magnetized steel plates set in a circle (the manner of preparing them is kept secret) and this mechanism attracts the electricity from the atmosphere. This is carried by wires to a transformer in the engine house below and thence is applied to produce either power or light after the usual manner.

In an authorized statement Meyers says: "The flow of electricity is constant. When it emerges into the transformer it is in the form of a direct current. It will absorb the electricity day and night and will work whenever the wireless will work. I can put up a plant to supply such a building as the Adams Hotel for about $1500, and one of the principal items of the expense is the cost of the towers, the wires, the magnetizing of one set of plates, which is part of the secret of the treatment which makes it respond to the accumulations of the atmosphere.

"For use in the case of an electrical storm I have made what I call a modified form of circuit breaker, such as is commonly used as a lightning arrester on telegraph lines. In case of a storm the accumulator would suddenly become overcharged, possibly, and as the electricity would not of itself flow back into the air, the result might be disastrous. So I send it down into the ground, whenever the voltage rises above a certain amount."

Roy J. Meyers & the "Absorber"



Modern Electronics (1914 ?)

Electricity From Air New Great Discovery

by

Dr Leonard Keene Hirshberg

Working quietly in the heart of Baltimore for weeks on an invention which some critics say will revolutionize the method of converting electricity to practical use has been Roy J. Meyers, who like Benjamin Franklin, extracts the electric current from the air.

Mr Meyers invention was made last summer while he was confined in the penitentiary at Florence, Arizona. His first finished apparatus was made in Baltimore.

A practical, unlettered electrician, Mr Meyers, while in Arizona, was arrested on a comparatively minor charge and sent to the penitentiary. There he was placed in charge of the prison electrical plant, and there he says he made his discovery that the current which the civilized world is beginning to use most extensively for light and power could be transformed from the atmosphere without the aid of moving machines or batteries.

Miss Kate Barnard, Commissioner of Charities and Corrections, of Oklahoma, hearing of Meyers' invention and of his desire to have it patented, appeared before the Arizona Legislature to make an appeal in behalf of the young convict. As a result a special bill was passed which granted Meyers a month's leave of absence on parole. He went unaccompanied to Washington, filed his patent applications and returned to the penitentiary. Since then he has been indefinitely paroled.

He came to Baltimore as the place where he could easily obtain the mechanical parts needed to make a more nearly perfect machine than the crude model he has fashioned in the penitentiary workshop, and is making his headquarters here while working on his invention. With him is W.E. Chenot, who has been his assistant in assembling and testing the machine and who says that he has bought Meyers' patent rights for Germany.

They have proved beyond doubt that the invention is practical and that when finally brought to a state of perfection it will introduce a new epoch in the industrial use of electricity. By Westinghouse meters they tested the strength of the current gathered from the air, and with the use of only two of the four rectifying transformers the voltmeter recorded four and one-half volts, and the ammeter, which had the capacity of recording 75 amperes, was broken by the force of the current.

The machine itself is simple. It is in reality a transformer, which is familiar to anyone knowing anything at all about electricity in its practical uses. On a high tripod, which resembles somewhat the framework of a windmill tower, is the transformer, which Mr Meyers calls his 'absorber'. It is made up of an iron core, wrapped with copper wire. The secret of the invention is the manner in which the disks composing this 'absorber' are magnetized, and this secret Meyers says he found by accident while at work in prison.

What the machine, when finally perfected, will do is yet to be seen. Its inventor claims that it will greatly reduce the cost of making electricity. No batteries of any kind are needed, he says, and not a part of the machine turns upon the other. It is as durable, apparently, as an electric light pole. One of these machines, says Meyers, when perfected may be placed on a vehicle and transform enough electricity to give motive power, be that vehicle a locomotive or an automobile. He declared it can be placed on a building to furnish electric lights or power, and that the only wear will be upon the machinery which its current runs.

Meyers is 34 years old and he gained his knowledge of electricity by working in shops along the Pacific Coast. The depths of the mysteries of electricity he has not explored, but he is certain that he has found the means of absorbing it from the air and of converting it to the use of mankind.

British (GB) Patent # 191301098

Improvements in and Relating to Apparatus for Producing Electricity.

1-14-1914

Roy Jerome Meyers

Classification: - international: H05F7/00; H05F7/00; - european: H05F7/00
Application number: GBD191301098 19130114
Priority number(s): GBT191301098 19130114

Abstract ~ Vapour apparatus, arrangements of. - A rectifier for use with apparatus for producing electricity from the earth consists of mercury- vapour lamps constructed and arranged as shown in Fig. 4. Each lamp comprises two wires 6<1>, 7<1> wound around a steel tube 15 surrounding a

mercury tube 11 preferably of copper. The coil 6<1> is connected between the electrode 14 and the terminal 18, and the coil 7<1> between the terminals 19, 5. The coils 6<1>, 7<1> are preferably composed of soft iron. Reference has been directed by the Comp- troller to Specifications 16,709/87, 14,033/99, and 5457/11, [all in Class 53, Galvanic batteries], and 15,412/06.

British Patent # 1098

(January 14, 1913)

Improvements in and Relating to Apparatus for Producing Electricity

Roy Jerome Meyers

This invention relates to improvements in apparatus for the production of electrical currents, and the primary object in view is the production of a commercially serviceable electrical current without the employment of mechanical or chemical action. To this end the invention comprises means for producing what I believe to be dynamic electricity from the earth and its ambient elements.

I am, of course aware that it has been proposed to obtain static charges from upper strata of the atmosphere, but such charges are recognized as of widely variant potential and have thus far proved of no practical commercial value, and the present invention is distinguished from all such apparatus as has heretofore been employed for attracting static charges by the fact that this improved apparatus is not designed or employed to produce or generate irregular, fluctuating or other electrical charges which lack constancy, but on the other hand I have by actual test been able to produce from a very small apparatus at comparatively low elevation, say about 50 or 60 feet above the earth's surface, a substantially constant current at a commercially usable voltage and amperage. This current I ascertained by repeated tests is capable of being readily increased by additions of the unit elements in the apparatus hereinafter set forth, and I am convinced from the constancy of the current obtained and its comparatively low potential that the current is dynamic and not static, although, of course, it is not impossible that certain static discharges occur and, in fact, I have found occasion to provide against the damage which might result from such discharge by the provision of lightning arresters and cut-out apparatus which assist in rendering the obtained current stable by eliminating sudden fluctuations which sometimes occur during conditions of high humidity from what I consider static discharges. The nature of my invention is obviously such that I have been unable to establish authoritatively all of the principles involved, and some of the theories herein expressed may possibly prove erroneous, but I do know and am able to demonstrate that the apparatus which I have discovered does produce, generate, or otherwise acquire a difference of potential representing a current amperage above stated, or varied therefrom at the will of the operator according to the uses which the current is to be subjected.

The invention comprises generically means for producing electrical currents of serviceable potential substantially without the employment of mechanical or chemical action, and in this connection I have been able to observe no chemical action whatever on the parts utilized although deterioration may possibly occur in some of the parts, but so far as I am able to determine such deterioration does not add to the current supply but is merely incidental to the effect of climatic action.

The invention more specifically comprises the employment of a magnet or magnets and a co-operating element, such as zinc disposed adjacent to the magnet or magnets and connected in such manner and arranged relative to the earth so as to produce current, my observation being that current is produced only when such magnets have their poles facing substantially to the north and south and the zincs are disposed substantially along the magnets.

The invention also comprehends other details of construction, combinations and arrangements of parts as will hereinafter be fully set forth and claimed.

In the accompanying drawings:

Figure 1 is a top plan view of an apparatus embodying the features of the present invention, the arrow accompanying the figure indicating substantially the geographical north, parts of the figure being diagrammatic for condensing the showing.



Figure 2 is a view is side elevation of the parts seen in plan in Figure 1.

Fig.2.


1
1
3
2
6
5
9
4
9
6
1
7
1
2
5
3
TO RECTIFIER

Figure 3 is a vertical section taken on the plane indicated by the line 3-3 of Figure 2 and looking in the direction indicated by the arrow.

Fig.5.



Figure 4 is a detail view partly in elevation and partly in section showing the detail connections of the converter and intensifier.

Fig. 4


+
31
15
13'
16
19
13
11
18
6
A
5
28
27
B
7'
14
20
12
17
16
22
32
13
9
19
7
29
30
18
11
19
C
21
7'
D
36
23
7'
35
10
–

Figure 5 is a transverse section taken on the planes indicated by line 5-5 of Figure 4 and looking downwardly.

Fig. 5.


17
+
–
7'
7
14
6'
7'
15
11

Figure 6 is an enlarged detail fragmentary section illustrating the parts at the juncture of the conductors and one of the intensifiers.

Fig. 6



Figure 7 is an enlarged detail view partly in elevation and partly in section of one of the automatic cut-outs and

Fig. 7.



Figure 8 is a diagrammatic view of one of the simplest forms of embodiment of the invention.


Fig. 8.

Referring to the drawing by numerals, 1,1 indicates magnets connected by a magnetic substance 2, preferably an iron wire. The magnets 1 are arranged in pairs, one pair being spaced beneath the other, and interposed between the magnets are zinc plates 3,3 connected by an iron wire conductor 4. Suitable insulating supports 5 are arranged for sustaining the respective magnets 1 and plates 3,3. Each plate 3 is preferably bent substantially into V form, as clearly seen in Figure 1, and the V1 of one of the plates opens or faces toward the north and the V of the other plate to the South. I have determined by experimentation that it is essential that the plates 3 be disposed substantially north and south with their flat faces approximately parallel to the adjacent faces of the co-operating magnets, although by experience I have not discovered any material difference in the current obtained when the plates are disposed slightly to one side of north and south, as for instance when the plates are disposed slightly to one side of north and south, as for instance when disposed in the line of the magnetic polarity of the earth. The same is true with respect to the magnets 1, the said magnets being disposed substantially north and south for operative purposes, although I find that it is immaterial whether the north pole of one of the magnets is disposed to the north and the south pole to the south, or vice versa, and it is my conviction from experience that it is essential to have the magnets of each pair connected by magnetic material so that the magnets substantially become one with a pole exposed to the north and a pole exposed to the north. In Figure 1, I have indicated in full lines by the letters 8 and N the respective polarities of the magnets 1, and have indicated in dotted lines the other pole of those magnets when the connection 2 is severed. I have found that the magnets and zinc plates operate to produce, whether by collection or generation I am not certain, electrical currents when disposed substantially north and south, but when disposed substantially east and west no such currents are produced. I also find that the question of elevation is by no means vital, but it is true that more efficient results are obtained by placing the zincs and magnets on elevated supports. I furthermore find from tests that it is possible to obtain currents from the apparatus with the zincs and magnets disposed in a building or otherwise enclosed, although more efficient results are obtained by having the said elements arranged in the open.

While in Figures 1, 2, and 3, I have shown the magnets and the zinc plates as superimposed, it will be apparent, as hereinafter fully set forth, that these elements may be juxtaposed in horizontal planes, and substantially the same results will be secured. Furthermore, the magnets 1 with the interposed zincs 3, as shown in Figures 1, 2 and 3 merely represent a unit which may be repeated either horizontally or vertically for increasing the current supply, and when the unit is repeated the zinc plates are arranged alternating with the magnets throughout the entire series as hereinafter indicated.

A conductor 6 is connected in multiple with the conductors 2 and a conductor 7 is connected with conductor 4, the conductor 6 extending to one terminal of a rectifier which I have indicated by the general reference character 8, and the conductor 7 extending to the other terminal of said rectifier. The rectifier as seen in diagram in Figure 1 may assume any of several well known embodiments of the electrical valve type and may consist of four asymmetric cells or Cooper-Hewitt mercury vapor lamps connected as indicated in Figure 1 for permitting communication of the positive impulses from the conductor 6 only to the line conductor 9 and the negative impulses from conductor 6 on only to the line conductor 10. The current from this rectifier may be delivered through the conductors 9 and 10 to any suitable source for consumption.

While the said rectifier 8 may consist of any of the known types, as above outlined, it preferably consists of a specially constructed rectifier which also has the capacity of intensifying the current and comprises specifically the elements shown in detail in Figures 4, 5, and 6 wherein I have disclosed the detail wiring of the rectifier when composed of four of the rectifying and intensify in elements instead of asymmetric cells or simple mercury vapor valves. As each of these structures is an exact embodiment of all the others, one only will be described, and the description will apply to all. The rectifying element of each construction consists of a mercury tube 11 which is preferably formed of glass or other suitable material, and comprises a cylinder having its end portions tapered and each terminating in an insulating plug or stopper 12. Through the upper stopper 12 is extended the electrode 13 which extends well into the tube and preferably substantially one-half the length thereof to a point adjacent the inner end of an opposing electrode 14 which latter electrode extends thence downwardly through the insulation 12 at the lower end of the tube. The tube 11 is supplied with mercury and is adapted to operate on the principle of the mercury vapor lamp, serving to rectify current by checking back impulses of one sign and permitting passage of impulses of the other. To avoid the necessity for utilizing a starter, as is common with the lamp type of electrical valve, the supply of mercury within the tube may be sufficient to contact with the lower end of the electrode 13 when current is not being supplied, so that as soon as current is passed from one electrode to the other sufficiently for volatilizing that portion of the mercury immediately adjacent the lower end of electrode 13, the structure begins its operation as a rectifier. The tube 11 is surrounded by a tube 15 which is preferably spaced from tube 11 sufficiently for allowing atmospheric or other cooling circulation to pass the tube 11. In some instances, it may be desirable to cool the tube 11 by a surrounding body of liquid, as hereinafter indicated. The tube 15 may be of insulating material but I find efficient results attained by the employment of a steel tube, and fixed to the ends of the of the tube are insulating disks 16, 16 forming a spool on which are wound twin wires 6^1 and 7^1, the wire 6^1 being connected at the inner helix of the coil with the outer end of the electrode 14, the lower portion of said electrode being extended to one side of the tube 11 and passed through an insulating sleeve 17 extending through the tube 15, and at its outer end merging into the adjacent end of the wire 6^1. The wire 7^1 extends directly from the outer portion of the spool through the several helices to a point adjacent the juncture of the electrode 14 with wire 6^1 and thence extends in mechanical parallelism with the wire throughout the coil, the wire 6^1 ending in a terminal 18 and the wire 7^1 ending in a terminal 19. For the sake of convenience of description and of tracing the circuits, each of the apparatus just above described and herein known as an intensifier and rectifier will be mentioned as A, B, C and D, respectively. Conductor 6 is formed with branches 20 and 21 and conductor 7 is formed with similar branches 22 and 23. Branch 20 from conductor 6 connects with conductor 7^1 of intensifier B and branch 21 of conductor 6 connects with the conductor 7^1 of intensifier C, while branch 22 of conductor 7 of intensifier C, while branch 22 of conductor 7 connects with conductor 7^1 of intensifier D. A conductor 27 is connected with terminal 19 of intensifier A and extends to and is connected with the terminal 18 of intensifier C, and a conductor 7 connects with conductor 7^1 of intensifier D. A conductor 27 is connected with terminal 19 of intensifier A. and extends to and is connected with terminal 18 of intensifier C, and a conductor 28 is connected with the terminal 19 of intensifier C and extends from the terminal 19 of intensifier B to the terminal 18 of intensifier D to electrode 13 of intensifier B. Each electrode 13 is supported on a spider 13^1 resting on the upper disk 16 of the respective intensifier. Conductors 31 and 32 are connected with the terminals 18 of intensifiers A and B and are united to form the positive line wire 9 which co-operates with the negative line wire 10 and extends to any suitable point of consumption. The line wire 10 is provided with branches 35 and 36 extending to the electrodes 13 of intensifiers C and D for completing the negative side of the circuit.

Thus it will be seen that alternating currents produced in the wires 6 and 7 will be rectified and delivered in the form of a direct current through the line wires 9 and 10, and I find by experiment that the wires 6 and 7 should be of iron, preferably soft, and may of course be insulated, the other wiring not specified as iron being of copper or other suitable material.

In carrying out the operation as stated, the circuits may be traced as follows: A positive impulse starting at the zincs 3 is directed along conductor 7 to branch 23 to conductor 7^1 and the winding of the rectifier of intensifier B through said rectifier to the conductor 6^1, through the winding thereof to the contact 18, conductor 32 and to the line wire 9. The next or negative impulse directed along conductor 7 cannot find its way along branch 23 and the circuit just above traced because it cannot pass across the rectifier of intensifier B but instead the negative impulse passes along conductor 22 to conductor 7 of intensifier A and the winding thereof to the contact 19 and to conductor 27 to contact 18 of intensifier C, to the winding of the wire 6^1 thereof to the electrode 14 through the rectifier to the of the electrode 13 and conductor of intensifier A, electrode 14 thereof and conductor 6^1 to contact 18 and wire 31 to line wire 9. Obviously the positive impulse cannot pass along the wire 20 because of its inverse approach to the rectifier of intensifier B. The next impulse or negative impulse delivered to conductor 6 cannot pass along conductor 21 because of its connection with electrode 13 of the rectifier of intensifier A, but instead passes along conductor 20 to the wire 7^1 and its winding forming part of intensifier B to the contact 19 and conductor 29 to contact 18 and the winding of wire 6^1 of intensifier D to the electrode 14 and through the rectifier to the electrode 13 and conductor 35 to line wire 10. Thus the current is rectified and all positive impulses directed along one line and all negative impulses along the other lie s that the potential difference between the two lines will be maximum for the given current of the alternating circuit. It is, of course, apparent that a less number of intensifiers with their accompanying rectifier elements may be employed with a sacrifice of the impulses which are checked back from a lack of ability to pass the respective rectifier elements, and in fact I have secured efficient results by the use of a single intensifier with its rectifier elements, as hereinafter set forth.

Grounding conductors 37 and 38 are connected respectively with the conductors 6 and 7 and are provided with the ordinary lightning arresters 39 and 40 respectively for protecting the circuit against high tension static charges.

Conductors 41 and 42 are connected respectively with the conductors 6 and 7 and each connects with an automatic cutout 43 which is grounded as at 4. Each of said automatic cutouts is exactly like the other and one of the same is shown in detail in Figure 7 and comprises the inductive resistance 45 provided with an insulated binding post 46 wit which the respective conductor 6 or 7 is connected, said post also supporting a spring 48 which sustains an armature 49 adjacent to the core of the resistance 45. The helix of resistance 45 is connected preferably through the spring to the binding post at one end and at the other end is grounded on the core of the resistance, the said core being grounded by ground conductor 44 which extends to the metallic plate 52 embedded in moist carbon or other inductive material buried in the earth. Each of the conductors 41, 42 and 44 is of iron, and in this connection I wish it understood that where I state the specific substance I am able to verify the accuracy of the statement by the results of tests which I have made, but of course I wish to include along with such substances al equivalents, as for instance, where iron is mentioned its byproducts, such as steel, and its equivalents such as nickel and other magnetic substances are intended to be comprehended. The cutout apparatus seen in detail in Figure 7 is employed particularly for insuring against high tension currents, it being obvious from the structure shown that when potential rises beyond the limit established by the tension of the spring sustaining the armature 40, the armature will be moved to a position contacting with the core of the cutout device and thereby directly close the ground connection for line wire 41 with conductor 44, eliminating the resistance of winding 45 and allowing the high tension current to be discharged to the ground. Immediately upon such discharge the winding 45 losing its current will allow the core to become demagnetized and release the armature 49 whereby the ground connection is substantially broken leaving only the connection through the winding 45 the resistance of which is sufficient for insuring against loss of low tension current.

In Figure 8 I have illustrated an apparatus which though apparently primitive in construction and arrangement comprehends the first successful embodiment which I produced in the course of discovery of the present invention, and it will be observed that the essential features of the invention are therein disclosed. The structure delineated in said figure consists of horseshoe magnets 54, 55, one facing north and the other south, that is, each opening in the respective directions indicated and the two being connected by an iron wire 55 which is uninsulated and wrapped about the respective magnets each end portion of the wire 55 being extended from the respective magnets to and connected with, as by being soldered to, a zinc plate 56, there being a plate 56 for each magnet and each plate being arranged longitudinally substantially parallel with the legs of the magnet and with the faces of the plate exposed toward the respective legs of the magnet, the plate being thus arranged endwise toward the north and south. An iron wire 57 connects the plates 56, the ends of the wire being preferably connected adjacent the outer ends of the plates but from experiment I find that the wire may be connected at practically any point to the plate. Lead wires 58 and 59 are connected respectively with the wires 55 and 57 and supply an alternating current at a comparatively low tension, and to control such current the wires 58 and 59 may be extended to a rectifier or combined rectifier and intensifier, as above set forth.

The tests which I have found successful with the apparatus seen in Figure 8 were carried out by the employment first of horseshoe magnets approximately 4 inches in length, the bar comprising the horseshoe being about one inch square, the zincs being dimensioned proportionately and from this apparatus with the employment of a single intensifier and rectifier, as above stated, I was able to obtain a constant current of 8 volts.

It should be obvious that the magnets forming one of the electrodes of this apparatus may be permanent or may be electromagnets, or a combination of the two.

While the magnets mentioned throughout the above may be formed of any magnetic substance, I find the best results obtained by the employment of the nickel chrome steel.

While the successful operation of the various devices which I have constructed embodying the present invention have not enabled me to arrive definitely and positively at fixed conclusion relative to the principles and theories of operation and the source from which current is supplied, I wish it to be understood that I consider myself as the first inventor of the general type hereinbefore described capable of producing commercially serviceable electricity, for which reason my claims hereinafter appended contemplate that I may utilize a wide range of equivalents so far as concerns details of construction suggested as preferably employed.

The current which I am able to obtain is dynamic in the sense that it is not static and its production is accomplished without chemical or mechanical action either incident to the actual chemical or mechanical motion or incident to changing caloric conditions so that the elimination of necessity for the use of chemical or mechanical action is to be considered as including the elimination of the necessity for the use of heat or varying degrees thereof.

Having now particularly described and ascertained the nature of my said invention, and in what manner the same is to be performed, I declare that what I claim is: --- [Claims not included here]

NOTES & COMMENTS

From the Article in *Tech. World Mag*.:

1. First demo model was powerful enough to spark a gas engine.
2. Second model developed 8 volts.
3. Demo model at Patent Office was elevated on short poles.
4. The model planned to power Phoenix AZ would be elevated 200 feet.
5. The Absorber "consists of a series of magnetized steel plates set in a circle (the manner of preparing them is kept secret)".
6. "[T]he magnetizing of one set of plates... is part of the secret of the treatment which makes it respond to the accumulations of the atmosphere".

From British Patent # 1098 (1913):

"I have been able... to produce from a very small apparatus at comparatively low elevation, say about 50 or 60 feet above the earth's surface, a substantially constant current at a commercially useable voltage and amperage".

"This current... is capable of being readily increased by additions of the unit elements in the apparatus".

Fig. 1 and Fig. 2 show the magnet poles are connected N-S by a thick iron rod (thick compared to the lines used for wires in the drawings).

No angle is specified for the V-shaped zinc plates. The article (but not the patent) states that the plates are magnetized (obviously not zinc). Zinc-galvanized steel? Will a thin film of Zn work? Or, powdered Zn in a binder (more surface area)? Or, zinc-galvanized iron wire in a coil?

The Palmer Craig device (www.rexresearch.com/craig/craig.htm) is powered by the terrestrial magnetic field, and employs a thin film of bismuth to capture the energy as diamagnetism. Perhaps this can be integrated with Meyers' device.

Figure 8 (the demonstration of principle) show uninsulated iron wire being used to connect the plates and magnets. The wire is wound around the Bloch wall area of the horseshoe magnets. Perhaps Coler-type windings around the poles could be used here (See: www.rexresearch.com/coler/coler.htm). Coler used copper plates as "condensers" in his device. Could copper plates be used for the Meyers device? Perhaps flat (Tesla non-inductive) coils could be integrated here.

"It is essential that the plates 3 be disposed substantially N and S with their flat faces approximately parallel to the adjacent faces of the co-operating magnets....

"I find that it is immaterial whether the N pole of one of the magnets is disposed to the N and the S pole to the S, or vice versa".

"[T]he magnets and zinc plates... produce electrical currents when disposed... N and S, but when disposed... E and W no such currents are produced".

"[E]levation is by no means vital, but... more efficient results are obtained by placing the zincs and magnets on elevated supports".

"The elements may be disposed in horizontal planes [or vertically]...".

The "zinc plate 56... [is] arranged longitudinally substantially parallel with the legs of the magnet and with the faces of the plate exposed toward the respective legs of the magnet, the plate being thus arranged endwise toward the north and south".

The first model used "horseshoe magnets approximately 4 inches in length, the bar comprising the horseshoe being about one inch square, the zincs being dimensioned proportionately and from this apparatus with the employment of a single intensifier and rectifier, as above stated, I was able to obtain a constant current of 8 volts... [T]he magnets... may be permanent or may be electromagnets, or a combination of the two... I find the best results obtained by... nickel chrome steel".

Comments & Questions:

The rectifier is described as a preferred embodiment, but other designs also work. The Ed Gray capacitor design comes to mind (www.rexresearch.com/evgray/1gray.htm). The Tate Ambient Power Module also might apply (www.rexresearch/tate/tate.htm).

Would non-ferrous magnets work? Is there a frequency involved (oscilloscope tests)? Coler found that ferromagnetism has a resonant frequency about 180 KHz. Can the components be made adjustable for RLC-resonance?

Nº 1098 A.D. 1913

Date of Application, 14th Jan., 1913—Accepted, 14th Jan., 1914

COMPLETE SPECIFICATION.

Improvements in and relating to Apparatus for Producing Electricity.

I, Roy Jerome Meyers, of Hotel Altamont, Baltimore, in the State of Maryland, United States of America, Electrician, do hereby declare the nature of this invention and in what manner the same is to be performed, to be particularly described and ascertained in and by the following statement:—

This invention relates to improvements in apparatus for the production of electrical currents, and the primary object in view is the production of a commercially serviceable electrical current without the employment of mechanical or chemical action. To this end the invention comprises means for producing what I believe to be dynamic electricity from the earth and its ambient elements. I am, of course, aware that it has been proposed to obtain static charges from upper strata of the atmosphere, but such charges are recognized as of widely variant potential and have thus far proved of no practical commercial value, and the present invention is distinguished from all such apparatus as has heretofore been employed for attracting static charges by the fact that this improved apparatus is not designed or employed to produce or generate irregular, fluctuating or other electrical charges which lack constancy, but on the other hand I have by actual test been able to produce from a very small apparatus at comparatively low elevation, say about fifty or sixty feet above the earth's surface, a substantially constant current at a commercially usable voltage and amperage. This current I ascertained by repeated tests is capable of being readily increased by additions of the unit elements in the apparatus hereinafter set forth, and I am convinced from the constancy of the current obtained and its comparatively low potential that the current is dynamic and not static, although, of course, it is not impossible that certain static discharges occur and, in fact, I have found occasion to provide against the damage which might result from such discharge by the provision of lightning arresters and cut-out apparatus which assist in rendering the obtained current stable by eliminating sudden fluctuations which sometimes occur during conditions of high humidity from what I consider static discharges. The nature of my invention is obviously such that I have been unable to establish authoritatively all of the principles involved, and some of the theories herein expressed may possibly prove erroneous, but I do know and am able to demonstrate that the apparatus which I have discovered does produce, generate, or otherwise acquire a difference of potential representing a current value which is commercially serviceable and may be delivered at the voltage and amperage above stated, or varied therefrom at the will of the operator according to the uses to which the current is to be subjected.

The invention comprises generically means for producing electrical currents of serviceable potential substantially without the employment of mechanical or chemical action, and in this connection I have been able to observe no chemical action whatever on the parts utilized although deterioration may possibly occur in some of the parts, but so far as I am able to determine such deterioration does not add to the current supply but is merely incidental to the effect of climatic action.

The invention more specifically comprises the employment of a magnet or

[*Price 8d.*]

BIRMINGHAM REFERENCE LIBRARY

magnets and a co-operating element, such as zinc disposed adjacent to the magnet or magnets and connected in such manner and arranged relative to the earth so as to produce current, my observation being that current is produced only when such magnets have their poles facing substantially to the north and south and the zincs are disposed substantially along the magnets.

The invention also comprehends other details of construction, combinations and arrangements of parts as will hereinafter be fully set forth and claimed.

In the accompanying drawings:

Figure 1 is a top plan view of an apparatus embodying the features of the present invention, the arrow accompanying the figure indicating substantially the geographical north, parts of the figure being diagrammatic for condensing the showing.

Figure 2 is a view in side elevation of the parts seen in plan in Figure 1.

Figure 3 is a vertical section taken on the plane indicated by the line 3—3 of Figure 2 and looking in the direction indicated by the arrow.

Figure 4 is a detail view partly in elevation and partly in section showing the detail connections of the converter and intensifier.

Figure 5 is a transverse section taken on the planes indicated by line 5—5 of Figure 4 and looking downwardly.

Figure 6 is an enlarged detail fragmentary section illustrating the parts at the juncture of the conductors and one of the intensifiers.

Figure 7 is an enlarged detail view partly in elevation and partly in section of one of the automatic cut-outs and

Figure 8 is a diagrammatic view of one of the simplest forms of embodiments of the invention.

Referring to the drawing by numerals, 1, 1 indicates magnets connected by a magnetic substance 2, preferably an iron wire. The magnets 1 are arranged in pairs, one pair being spaced beneath the other, and interposed between the magnets are zinc plates 3, 3 connected by an iron wire conductor 4. Suitable insulating supports 5 are arranged for sustaining the respective magnets 1 and plates 3, 3. Each plate 3 is preferably bent substantially into **V** form, as clearly seen in Figure 1, and the **V** of one of the plates opens or faces toward the north and the **V** of the other plate to the south. I have determined by experimentation that it is essential that the plates 3 be disposed substantially north and south with their flat faces approximately parallel to the adjacent faces of the co-operating magnets, although by experience I have not discovered any material difference in the current obtained when the plates are disposed slightly to one side of north and south, as for instance when disposed in the line of the magnetic polarity of the earth. The same is true with respect to the magnets 1, the said magnets being disposed substantially north and south for operative purposes, although I find that it is immaterial whether the north pole of one of the magnets is disposed to the north and the south pole to the south, or *vice versa*, and it is my conviction from experience that it is essential to have the magnets of each pair connected by magnetic material so that the magnets substantially become one with a pole exposed to the north and a pole exposed to the south. In Figure 1, I have indicated in full lines by the letters S and N the respective polarities of the magnets 1, and have indicated in dotted lines the other poles of those magnets when the connection 2 is severed. I have found that the magnets and zinc plates operate to produce, whether by collection or generation I am not certain, electrical currents when disposed substantially north and south, but when disposed substantially east and west no such currents are produced. I also find that the question of elevation is by no means vital, but it is true that more efficient results are obtained by placing the zincs and magnets on elevated supports. I furthermore find from tests that it is possible to obtain currents from the apparatus with the zincs and magnets disposed in a building or otherwise enclosed, although more efficient results are obtained by having the said elements arranged in the open.

While in Figures 1, 2 and 3, I have shown the magnets and the zinc plates as superimposed, it will be apparent, as hereinafter fully set forth, that these elements may be juxtaposed in horizontal planes, and substantially the same results will be secured. Furthermore, the magnets 1 with the interposed zincs 3, as shown in Figures 1, 2 and 3 merely represent a unit which may be repeated either horizontally or vertically for increasing the current supply, and when the unit is repeated the zinc plates are arranged alternating with the magnets throughout the entire series as hereinafter indicated.

A conductor 6 is connected in multiple with the conductors 2 and a conductor 7 is connected with conductor 4, the conductor 6 extending to one terminal of a rectifier which I have indicated by the general reference character 8, and the conductor 7 extending to the other terminal of said rectifier. The rectifier as seen in diagram in Figure 1 may assume any of several well known embodiments of the electrical valve type and may consist of four assymmetric cells or Cooper-Hewitt mercury vapor lamps connected as indicated in Figure 1 for permitting communication of the positive impulses from conductor 7 only to the line conductor 9 and the negative impulses from the conductor 7 only to the line conductor 10, and permitting the positive impulses from the conductor 6 only to the line conductor 9 and the negative impulses from conductor 6 only to the line conductor 10. The current from this rectifier may be delivered through the conductors 9 and 10 to any suitable source for consumption.

While the said rectifier 8 may consist of any of the known types, as above outlined, it preferably consists of a specially constructed rectifier which also has the capacity of intensifying the current and comprises specifically the elements shown in detail in Figures 4, 5 and 6 wherein I have disclosed the detail wiring of the rectifier when composed of four of the rectifying and intensifying elements instead of assymmetric cells or simple mercury vapor valves. As each of these structures is an exact embodiment of all the others, one only will be described, and the description will apply to all. The rectifying element of each construction consists of a mercury tube 11 which is preferably formed of copper but may be formed of glass or other suitable material, and comprises a cylinder having its end portions tapered and each terminating in an insulating plug or stopper 12. Through the upper stopper 12 is extended the electrode 13 which extends well into the tube and preferably substantially one-half the length thereof to a point adjacent the inner end of an opposing electrode 14 which latter electrode extends thence downwardly through the insulation 12 at the lower end of the tube. The tube 11 is supplied with mercury and is adapted to operate on the principle of the mercury vapor lamp, serving to rectify current by checking back impulses of one sign and permitting passage of impulses of the other. To avoid the necessity for utilizing a starter, as is common with the lamp type of electrical valve, the supply of mercury within the tube may be sufficient to contact with the lower end of the electrode 13 when current is not being supplied, so that as soon as current is passed from one electrode to the other sufficiently for volatilizing that portion of the mercury immediately adjacent the lower end of electrode 13, the structure begins its operation as a rectifier. The tube 11 is surrounded by a tube 15 which is preferably spaced from tube 11 sufficiently for allowing atmospheric or other cooling circulation to pass the tube 11. In some instances, it may be desirable to cool the tube 11 by a surrounding body of liquid, as hereinafter indicated. The tube 15 may be of insulating material but I find efficient results attained by the employment of a steel tube, and fixed to the ends of the tube are insulating disks 16, 16 forming a spool on which are wound twin wires 6^1 and 7^1, the wire 6^1 being connected at the inner helix of the coil with the outer end of the electrode 14, the lower portion of said electrode being extended to one side of the tube 11 and passed through an insulating sleeve 17 extending through the tube 15, and at its outer end merging into the adjacent end of the wire 6^1. The wire 7^1 extends directly from the outer portion of the spool through the several helices to a point adjacent the juncture of the electrode 14 with wire 6^1 and thence extends in mechanical parallelism with the wire throughout the coil, the wire 6^1 ending in a terminal 18 and the wire 7^1 ending in a terminal 19. For the sake of convenience of description and of tracing the circuits, each of the apparatus just above described and herein known as an intensifier and rectifier will be mentioned as A, B, C and D, respectively. Conductor 6 is formed with branches 20 and 21 and conductor 7 is formed with similar branches 22 and 23. Branch 20 from conductor 6 connects with conductor 7^1 of intensifier B and branch 21 of conductor 6 connects with the conductor 7^1 of intensifier C, while branch 22 of conductor 7 connects with conductor 7^1 of intensifier A and branch 23 of conductor 7 connects with conductor 7^1 of intensifier D. A conductor 27 is connected with terminal 19 of intensifier A and extends to and is connected with terminal 18 of intensifier C, and a conductor 28 is connected with the terminal 19 of intensifier C and extends to and is connected with electrode 13 of intensifier A. A conductor 29 extends from the terminal 19 of intensifier B to the terminal 18 of intensifier D and a conductor 30 extends from the terminal 19 of intensifier D to electrode 13 of intensifier B. Each electrode 13 is supported on a spider 13^1 resting on the upper disk 16 of the respective intensifier. Conductors 31 and 32 are connected with the terminals 18 of intensifiers A and B and are united to form the positive line wire 9 which co-operates with the negative line wire 10 and extends to any suitable point of consumption. The line wire 10 is provided with branches 35 and 36 extending to the electrodes 13 of intensifiers C and D for completing the negative side of the circuit.

Thus it will be seen that alternating currents produced in the wires 6 and 7 will be rectified and delivered in the form of a direct current through the line wires 9 and 10, and I find by experiment that the wires 6 and 7 should be of iron, preferably soft, and may of course be insulated, the other wiring not specified as iron being of copper or other suitable material.

In carrying out the operation as stated, the circuits may be traced as follows: A positive impulse starting at the zincs 3 is directed along conductor 7 to branch 23 to conductor 7^1 and the winding of intensifier D to terminal 19 through conductor 30 to electrode 13 of the rectifier of intensifier B through said rectifier to the conductor 6^1, through the winding thereof to the contact 18, conductor 32 and to the line wire 9. The next or negative impulse directed along conductor 7 cannot find its way along branch 23 and the circuit just above traced because it cannot pass across the rectifier of intensifier B but instead the negative impulse passes along conductor 22 to conductor 7 of intensifier A and the winding thereof to the contact 19 to conductor 27 to contact 18 of intensifier C, to the winding of the wire 6^1 thereof to the electrode 14 through the rectifier to the electrode 13 and conductor 36 to the line wire 10. A positive impulse delivered to wire 6 passes along the said wire to the branch 21 to the conductor 7^1 of intensifier C and the winding thereof to the contact 19, conductor 28, electrode 13 of the rectifier of intensifier A, electrode 14 thereof and conductor 6^1 to contact 18 and wire 31 to line wire 9. Obviously the positive impulse cannot pass along the wire 20 because of its inverse approach to the rectifier of intensifier B. The next impulse or negative impulse delivered to conductor 6 cannot pass along conductor 21 because of its connection with electrode 13 of the rectifier of intensifier A, but instead passes along conductor 20 to the wire 7^1 and its winding forming part of intensifier B to the contact 19 and conductor 29 to contact 18 and the winding of wire 6^1 of intensifier D to the electrode 14 and through the rectifier to the electrode 13 and conductor 35 to line wire 10. Thus the current is rectified and all positive impulses directed along one line and all negative impulses along the other line so that the potential difference between the two lines will be maximum for the given current of the alternating circuit. It is, of course, apparent that a less number of intensifiers with their accompanying rectifier elements may be employed with a sacrifice of the impulses which are checked back from a lack of ability to pass the respective rectifier elements, and in fact I have secured efficient results by the use of a single intensifier with its rectifier elements, as hereinafter set forth.

Grounding conductors 37 and 38 are connected respectively with the conductors 6 and 7 and are provided with the ordinary lightning arresters 39 and 40 respectively for protecting the circuit against high tension static charges.

Conductors 41 and 42 are connected respectively with the conductors 6 and 7 and each connects with an automatic cut-out 43 which is grounded as at 44. Each of said automatic cut-outs is exactly like the other and one of the same is shown in detail in Figure 7 and comprises the inductive resistance 45 provided with an insulated binding post 46 with which the respective conductor 6 or 7 is connected, said post also supporting a spring 48 which sustains an armature 49 adjacent the core of the resistance 45. The helix of resistance 45 is connected preferably through the spring to the binding post at one end and at the other end is grounded on the core of the resistance, the said core being grounded by ground conductor 44 which extends to the metallic plate 52 imbedded in moist carbon or other inductive material 53 buried in the earth. Each of the conductors 41, 42 and 44 is of iron, and in this connection I wish it understood that where I state the specific substance I am able to verify the accuracy of the statement by the results of tests which I have made, but of course I wish to include along with such substance all equivalents, as for instance, where iron is mentioned its by-products, such as steel, and its equivalents such as nickel and other magnetic substances are intended to be comprehended. The cut-out apparatus seen in detail in Figure 7 is employed particularly for insuring against high tension currents it being obvious from the structure shown that when potential rises beyond the limit established by the tension of the spring sustaining the armature 49, the armature will be moved to a position contacting with the core of the cut-out device and thereby directly close the ground connection for line wire 41 with conductor 44, eliminating the resistance of winding 45 and allowing the high tension current to be discharged to the ground. Immediately upon such discharge the winding 45 losing its current will allow the core to become demagnetized and release the armature 49 whereby the ground connection is substantially broken leaving only the connection through the winding 45 the resistance of which is sufficient for insuring against loss of low tension current.

In Figure 8 I have illustrated an apparatus which though apparently primitive in construction and arrangement comprehends the first successful embodiment which I produced in the course of the discovery of the present invention, and it will be observed that the essential features of the invention are therein disclosed. The structure delineated in said figure consists of horse shoe magnets 54, 54, one facing north and the other south, that is, each opening in the respective directions indicated and the two being connected by an iron wire 55 which is uninsulated and wrapped about the respective magnets at or adjacent the neutral zone thereof, and the wire 55 is preferably soldered to the respective magnets each end portion of the wire 55 being extended from the respective magnet to and connected with, as by being soldered to, a zinc plate 56, there being a plate 56 for each magnet and each plate being arranged longitudinally substantially parallel with the legs of the magnet and with the faces of the plate exposed toward the respective legs of the magnet, the plate being thus arranged endwise toward the north and south. An iron wire 57 connects the plates 56, the ends of the wire being preferably connected adjacent the outer ends of the plates but from experiment I find that the wire may be connected at practically any point to the plate. Lead wires 58 and 59 are connected respectively with the wires 55 and 57 and supply an alternating current ordinarily at a comparatively low tension, and to control such current the wires 58 and 59 may be extended to a rectifier or combined rectifier and intensifier, as above set forth.

The tests which I have found successful with the apparatus seen in Figure 8 were carried out by the employment first of horse shoe magnets approximately four inches in length, the bar comprising the horse shoe being about one inch square, the zincs being dimensioned proportionately and from this apparatus with the employment of a single intensifier and rectifier, as above stated, I was able to obtain a constant current of 8 volts.

It should be obvious that the magnets forming one of the electrodes of this apparatus may be permanent or may be electro-magnets, or a combination of the two.

While the magnets mentioned throughout the above may be formed of any magnetic substance, I find the best results obtained by the employment of the nickel chrome steel.

While the successful operation of the various devices which I have constructed embodying the present invention have not enabled me to arrive definitely and positively at fixed conclusions relative to the principles and theories of operation and the source from which current is supplied, I wish it to be understood that I consider myself as the first inventor of an apparatus of the general type hereinbefore described capable of producing commercially serviceable electricity, for which reason my claims hereinafter appended contemplate that I may utilize a wide range of equivalents so far as concerns details of construction suggested as preferably employed.

The current which I am able to obtain is dynamic in the sense that it is not static and its production is accomplished without chemical or mechanical action either incident to the actual chemical or mechanical motion or incident to changing calorific conditions so that the elimination of necessity for the use of chemical or mechanical action is to be considered as including the elimination of the necessity for the use of heat or varying degrees thereof.

Having now particularly described and ascertained the nature of my said invention, and in what manner the same is to be performed, I declare that what I claim is:—

1. Means for producing dynamic electricity without mechanical or chemical action.
2. Electricity producing means as claimed in Claim 1, characterized in that said means is capable of producing low tension current.
3. Electricity producing means as claimed in Claim 1, characterized in that said means comprises a magnet, and means co-operating with the latter.
4. Means as set forth in Claim 3, characterized in that the parts are stationary.
5. Means as claimed in Claim 3, characterized in that the magnet is disposed substantially north and south.
6. Means as claimed in Claims 1, 3 and 5, wherein the means coacting with the magnet is a metal and said parts are disposed substantially north and south.
7. Means as claimed in Claims 1, 3 and 6, in which the metal is zinc, and combined with conductors connected with the co-operating parts to deliver current therefrom.
8. Means as set forth in Claim 1, characterized in that said means comprises spaced magnets with an adjacent co-operating zinc, and an iron wire connecting the magnets, and means to deliver electrical current from said parts.
9. Means as set forth in Claim 8, characterized in that the current delivery means comprises an intensifier and rectifier.
10. Means as set forth in Claim 8, characterized in that the current delivery means comprises wires connected with the magnets and zinc, an electrical valve connected with one of said wires, and independent helices surrounding said valve, one of said helices being connected with the terminal of the valve at the opposite side from the contact of said wire and the other of said helices being connected with the other wire, the electrical valve comprising a mercury vapor rectifier.
11. The process of producing electricity comprising exposing a magnet and

co-operating means disposed substantially north and south and taking off current therefrom.

12. The process of producing electricity comprising disposing stationary elements in co-operative relation in respect to each other and with respect to the earth for giving off relatively low tension electrical current, substantially without chemical action.

13. Electricity producing means constructed and operating substantially as described with reference to the accompanying drawings.

Dated this 13th day of January, 1913.

W. P. THOMPSON & Co.,
6, Lord Street, Liverpool, and at
Bradford & London,
Agents for the Applicant.

Reference has been directed, in pursuance of Section 7, Sub-section 4, of the Patents and Designs Act, 1907, to Specifications No. 16,709 of 1887, No. 14,033 of 1899, No. 15,412 of 1906, and No. 5457 of 1911.

Redhill: Printed for His Majesty's Stationery Office, by Love & Malcomson, Ltd.—1914.


Fig.1.
S
N
N
S
t
Fig.6
Fig.8.
UNINSULATED IRON WIRE
IRON WIRE
TO RECTIFIER
Fig.2.
t
TO RECTIFIER
Fig.3.
TO RECTIFIER

Fig.7.


48
46
41
44
53
52
49
45

Fig.4.


+I
31
15
13'
16
19
32
13
+9
18
13
11
19
7
A
6
28
27
29
B
5
5
7'
7'
22
12
14
17
16
13
30
20
18
11
19
18
19
28
C
D
21
36
7'
7'
35
10

Fig.5.


17
7'
7
14
6'
7'
15
11

Your Support Maintains this Service. Please Invest in the mind-boggling Rex Research Website CD -- Always The Best Investment ... Everything on this Website & More (the Bonus Files CD) -- Only $13, Postpaid Anywhere ! Secure Transaction via PayPal: All Major Credit Cards Accepted:

Buy Now

No Credit ? Don't like PayPal ? Send a Check/Money Order to:

Rex Research, PO Box 19250, Jean, NV 89019 USA

rexresearch.com

H. C. VION.

Electric Apparatus.

No. 28,793. Patented June 19, 1860.

Plate 1.


C
A
C
D
D
E
I
a
a
G
G
K
K
I
J
P
P
R
R
Q
Q

Plate 2.


A
A
B
D
B
E
D
B
B
B
B'
B
B
E
G
G
G'
G
E
I
J
I
K
P
P
P
P
Q
Q

Plate 3.


Q
R
P
M
L
L
P
P
P
Q

Plate 4.


Fig. 2.
Fig. 1.
E'
B
B
G
E
D
G
G'
G'
G
G
I
I'
I''
I
I'''
I
I
Fig. 3.
Fig. 4.

Plate 5.


Fig. 1.
Fig. 2.
Fig. 3.
O
O
O
O
P
P
P
P
P
E

Plate 6.


Fig. 6.
Fig. 5.
Fig. 8.
Fig. 1.
O
P'
P'
O
P'
P'
P'
P
S
Fig. 7.
Fig. 2.
Fig. 4.
A
N
P
P
P
A
P
T
T
T
A
A
T
K
Fig. 3.
N

Witnesses:
Arthur L. McIntire
Lewis Bosworth

Inventor:
H. C. Vion
by Munn & Co.
Attorneys.

N. PETERS, Photo-Lithographer, Washington, D. C.

UNITED STATES PATENT OFFICE.

H. CHARLES VION, OF PARIS, FRANCE.

IMPROVED METHOD OF UTILIZING ATMOSPHERIC ELECTRICITY.

Specification forming part of Letters Patent No. **28,793**, dated June 19, 1860.

To all whom it may concern:

Be it known that I, HIPPOLYTE CHARLES VION, of Paris, in the Empire of France, engineer, have invented a new Mode of Obtaining Atmospheric Electricity and Terrestrial Electricity and its Industrial Applications; and I do hereby declare that the following is a full, clear, and exact description of the same, reference being had to the accompanying drawings, making part of this specification, in which—

Plate 1 represents a front elevation; Plate 2, a side elevation of an aerostat, in combination with certain other devices for obtaining atmospheric and terrestrial electricity; Plate 3, a plan of the device for obtaining terrestrial electricity; Plate 4, detached portions of the apparatus. Plate 5 shows a front view, and Plate 6 a vertical section and various details of the apparatus when applied in mountainous regions, the use of an aerostat being dispensed with.

The object of my invention is to form an electric pile of great power by using the positive electricity contained in the atmosphere, and the negative electricity contained in the earth, so as to make the electricity therein contained available for industrial purposes.

To enable others skilled in the art to make and use my invention, I will proceed to describe its construction and operation.

A is aerostat of a tubular form closed at both ends. It is made of suitable material, so as to be impervious to air. Its dimensions are such as to give it great ascensional power when filled with gas.

a a are valves in the surface of the aerostat, to be opened when the inflation of the aerostat should become too great.

A long india-rubber tube, I, communicates with the interior of the aerostat, being attached to the latter, near one end of its ends D, as seen in Plate 1, while the lower end of the tube I is attached to a gasometer, (not shown in the drawings.) The gasometer is to be fed with hydrogen gas, produced by the action of the pile itself, the negative wires of which (afterward to be described) enter a body of water at or near the base of the apparatus and decompose the water so as to produce the hydrogen gas. As the aerostat is supposed to be at a considerable height the tube I must be of corresponding length, and is constructed of a number of tubes, short wooden tubes I′ being inserted where the tubes I are joined, and a fastening-ring, I″, being slipped over each of the joints, as seen in Fig. 3 of Plate 4. At certain distances the tube I is fastened to the net-work of the positive wires (afterward to be described) in order to secure the tube against the action of the wind, and at each of these fastening-places a washer, I‴, is inserted in the tube in order that the tube shall not be compressed by the wire or other means employed to fasten it to the net-work of positive wires. (See Fig. 4, Plate 4.)

The aerostat is surrounded with a net-work of wires, one layer of the wires, C, being parallel with the axis of the aerostat and fastened to rings D at both ends of the aerostat, and the other layer of wires, B, extending partially around the aerostat at right angles to the wires C. One end of each of the wires B extends around an iron tube, E, some distance below the aerostat and meets the other end of it between the tube E and the aerostat. The two ends are fastened together by a ligature, B′. (See Fig. 1, Plate 4.) Each end of the tube E terminates into a ball, *e*. The wires B are fastened to the surface of the tube E by means of a helical wire, F, wound around the tube and across the wires B, as seen in Fig. 1, Plate 4. The upper ends of long vertical wires G are also wound around cylinder E, each wire G between two of the wires B, and the ends secured by a ligature, G′, as seen in Fig. 1, Plate 4. The helical wire F is also wound across the wires G, so as to keep them in their places on tube E.

The vertical wires G, which are to be the conductors of the positive electricity of the atmosphere, must be of a length proportionate to the desired efficacy of the electric pile, and the size and ascensional power of the aerostat must, of course, be adequate to sustain the weight of and keep suspended the wires G, (a weight still further increased by the horizontal cross-wires H, with which the vertical wires G are interlaced, in order to form a net-work not liable to be deranged by the action of the winds or similar influences.) The two outside wires, G, are stronger than the rest of them, and their lower ends are fastened to dynamometers of any suitable construction. These dynamometers are attached to the ends or a massive iron cylinder, J, and they serve to indicate the tension in the outside wires, G, and the corresponding ascensional power of the aerostat. According to the reading of these dynamometers the aerostat has to be supplied (through tube I) with more or less gas. The lower end of each of the wires G is wound around the cylinder J, and secured by ligatures similar to those above described. The wires G are all insulated (by a coating of gutta-percha or similar substance,) except where they are in contact with tube E and with cylinder J, and a similar insulating coating is laid on cylinder J, after the lower ends of the wires G have been fastened to it.

Another cylinder, K, similar to J, is placed at some distance from and parallel to cylinder J. It is connected with cylinder J by wires L, wound around both cylinders and interlaced with cross-wires M. The wire-work L M and cylinders are insulated (in a manner already described) against outside influences, so that the only electric communication between the two cylinders will be through the wires L. The two cylinders are placed upon insulated columns P. The cylinder K may be used as a substitute for cylinder J, and vice versa, whenever repairs become necessary. Insulated branch wire or wires are attached to the cylinders J K and wires L, so as to conduct the positive electricity obtained from the atmosphere by means of the above-described apparatus to wherever it is desired for industrial purposes. The insulated wires Q (interlaced with cross-wires R) are placed on the ground underneath and parallel to the positive wires L. Both ends of each of the wires Q are sunk into the earth or submerged in water, and fastened to a metallic plate coated with a metal not subject to oxidation. These wires Q are the conductors for the negative electricity of the earth, and a branch wire or wires attached to the wires Q serve to transmit the negative terrestrial electricity to wherever it is wanted for industrial or other purposes.

By uniting to the ends of the positive and the negative branch wire or wires a powerful electric current will be obtained, one pole of which is the atmosphere and the other the earth, and may be applied to any suitable useful purpose.

I will now proceed to describe the modification of the above-described apparatus when to be applied in mountainous countries.

P represents the positive electric copper or other metal wires coated over with an insulating substance. The upper ends of each of the positive wires is soldered to a prompter, O, at P′, Figs. 1, 5, and 6, Plate 6. The lower portion of each of the positive-wires is secured to an insulator, T, Fig. 2, Sheet 6. The positive wires are held above the ground by joints A, Figs. 3 and 4, Sheet 6, projecting from the soil at suitable distances from each other. The wires P are intended to follow the inequalities of the ground on which they are laid.

The prompters O, Figs. 5 and 6, Sheet 6, are iron rods sharpened to a point and silvered or coppered at their upper ends. The lower part of the prompter is fastened into a pole, S, covered with tar, which isolates the prompter and holds it in a firm position. A large metallic plate may be soldered to each prompter, as shown in Fig. 6. The positive wires may be soldered to the rod of each prompter or to the plate which is fastened thereto.

One or more branch lines, E, are soldered up to the positive wires to transmit the positive atmospheric electricity for which the wires P are the conductors to any desirable point.

N are negative iron or other metal conductors coated with an insulating substance. The upper ends of these wires rest on the ground near the positive insulators. The lower ends of these wires are soldered to a metallic plate or plates, V, Fig. 7, Plate 6, coated with a metal not subject to oxidation. The negative wires are sunk into the ground at very great depth or into wells, rivers, or into the sea. The negative electric branch wires are attached to the negative conductors N in the same manner as the positive branch wires are to the positive conductors. The branch wires and the soldering are coated over with an insulating substance. They are intended to carry the negative terrestial electricity to any desired point.

What I claim as my invention, and desire to secure by Letters Patent, is—

1. The peculiar arrangement of means herein specified, whereby I am enabled to use the positive electricity contained in the atmosphere and the negative electricity contained in the earth, and thus form an electric pile of considerable power and make the electricity therein contained available for industrial purposes, as set forth.

2. The combination of an aerostat and vertical wire-work with a tube, I, for admitting gas into the aerostat, in the manner and for the purposes above set forth.

CHARLES VION.

Witnesses:
HARRY W. SPENCER,
A. GUION, JR.

WILLIAM H. WARD.

Improvement in Collecting Electricity for Telegraphing, &c.

No. 126,356. Patented April 30, 1872.


Fig;1.
Fig;2.
Fig;3.
Fig;4.
Fig;5.
Fig;6.
Fig;7.
L
M
O
K
I
p'
g
e
f
c
d
H
i
G
B
E
F
b'
a'
A
a
N
n
o
h
k
J
l
m
p
C
D

WITNESSES. INVENTOR.

Frank R. Rathbun

H. S. Rathbun

W. H. Ward

AM. PHOTO-LITHOGRAPHIC CO. N. Y. (OSBORNE'S PROCESS.)

126,356

UNITED STATES PATENT OFFICE.

WILLIAM HENRY WARD, OF AUBURN, NEW YORK.

IMPROVEMENT IN COLLECTING ELECTRICITY FOR TELEGRAPHING, &c.

Specification forming part of Letters Patent No. 126,356, dated April 30, 1872.

I, WILLIAM HENRY WARD, of Auburn, in the county of Cayuga and State of New York, have invented an Electrical Tower for Accumulating Natural Electricity for Telegraphic Purposes, of which the following is a specification:

My invention consists of a tower for the purpose of receiving and imparting natural electricity, so as to be in constant contact with that upper stratum of electricity which surrounds the earth, by tapping which a never-failing supply is formed when brought into contact with the earth, as will be more fully explained hereinafter.

In the accompanying drawing, Figure 1 represents a side elevation of my improved electrical tower. Fig. 2 is a vertical central section of the upper part of the same. Figs. 3, 4, 5, 6, and 7 are detached views of several parts of the same.

The tower is constructed in three separate sections, a lower, a middle, and an upper one, and is placed on elevated mountain tops or peaks. The lower one, A, is a mere shell, having a door, *a*, and is constructed of any material suitable for the purpose. It is insulated from the middle portion B by means of a glass diaphragm, *c*, held between similar diaphragms of rubber, *d*, and of gutta-percha, *e*, by means of flanges *a′* and *b′*, formed on the upper end of the lower portion and the lower end of the middle portion of the tower respectively. These flanges are secured to each other by insulated bolts *f*. The middle portion B is provided with suitable openings or windows, G, having shutters or slats *g* pivoted in them, so that, by means of raising or lowering rods *h*, suitably connected to said shutters, the openings G may be shut or opened. A projecting roof, H, is formed on or secured to the middle portion B just over the openings G, and which serves the double purpose of protecting the said openings from the effects of the weather, such as rain or snow, and also for receiving the aerial electricity, which may be drawn from it by wires *i*, for land-line purposes. Above this roof H the middle portion of the tower is again insulated by diaphragms of glass, rubber, and gutta-percha from the upper portion I of the tower in the same manner as it is insulated from its lower portion. A circular plate, *j*, secured on the inside of this upper portion, bears a short tube, J, which is surrounded by the tube K of the ventilator L, from which latter the vane M extends; or the tube J may be held by rods extending from the side of the tower centrally. This ventilator is supported by a rod or shaft, *k*, firmly attached to the tube K, and having its lower bearing in a step, *l*, on a brace, *m*, crossing the middle portion B of the tower just above the openings G. This rod or shaft *k* is formed in two parts, insulated from each other, as shown at *k′*. On the lower portion of this shaft *k* is keyed or otherwise secured a sleeve, *n*, from which a horizontal serpentine cam-plate, *o*, shown in detail in Figs. 4 and 5, extends, over the rim of which the forked ends *p* of rods *h* seize, and which is so arranged relatively to the vane M and the shutters or slats *g* that the revolution of the vane by the wind will open the windward and close the leeward shutters or slats *g* and openings G by means of the rods *h*. Guide-plates or their equivalents N, provided with suitable openings, through which the rods *h* pass, keep the upper forked ends *h* of the latter in constant contact with the cam-plate *o*, which raises or lowers the rods, and consequently opens or closes the openings G as it revolves. A circular roof, O, extends from the tube K of the ventilator so as to cover and protect the open upper end of the tower. The upper portion I of the tower is provided with an insulating-tube, *p′*, through which a copper wire, *q*, enters the portion I of the tower, and is coiled around the tube J just under the tube K, which wire may connect that upper portion of the tower with any land line of wires. The upper portion I of the tower, as well as the tubes J K, may be constructed of zinc, while the vane may be made of zinc, copper, or any equivalent material, which, with the zinc and the moisture of the atmosphere, would form an electrical current. As the vane revolves it opens the openings to windward and closes those to leeward, thus helping to drive an aerial current of electricity into the insulated middle portion of the tower, which current passes upwardly through the upper portion of the tower and out through the ventilator or the top, which is swung around by the wind or aerial electrical current, thus forming a draught in addition to the closing of the shutters or openings to leeward, by means of which draught the electrical current is forced upwardly and out at the vane. The top portion of the tower is of course completely insulated from all below it, including the revolving central ventilator-shaft. As the middle portion of the tower allows the electrical current of atmosphere, wind, &c., to pass within, up, and out at the top it forms a continuous current, whereby the tower is receiving continually fresh and new supplies of electricity, which can be drawn from the projecting roof H by the wires *i* for the use of land lines of telegraphs or for other purposes, such as light, heat, &c. By the use of aerial electricity I entirely dispense with artificial batteries, forming my circuit merely by connecting the aerial current with the earth current. For instance, to bring Buenos Ayres, in South America, into direct connection with New York, the following plan would be pursued: One electrical tower is erected on Pike's Peak or any other suitable high mountain in North America, and another similar tower on some suitable peak of the Andes in South America. The former would, by means of land-lines, be connected directly with Denver, which place is again connected with all the prominent cities of the States. In a similar manner the southern tower is connected by land-lines with the prominent cities via Quito. New York telegraphs to the tower on Pike's Peak, and the operator having connected the land-line with the aerial current, the signals are transmitted through the aerial current to the tower in the Andes in South America; and from there—the land-lines being suitably connected with the aerial current—to Quito and Buenos Ayres. In this manner a message would be sent entirely by natural electricity in place of artificial. In the same manner a message may be sent across the ocean by having a high tower on each continent, each of which towers would have to be, of course, through land-lines connected with the earth to enable the ground current with the aerial current to form a circuit. Different towers may be erected on the different continents, and if they are all what is technically called hooked on—that is to say, connected to the earth—a signal given at one tower will be repeated at all the towers, they being connected with each other by the aerial current. If the earth-connection is severed, or the insulation with the tower destroyed, there is no power; but by insulating the tower and concentrating its force to a point, bringing the same corresponding effect from the earth current in connection, an exceedingly powerful electrical force is created.

Having described my invention, I claim—

1. A tower constructed so as to collect, hold, distribute, and utilize aerial currents of natural electricity for telegraphic and other purposes, essentially as described.

2. A tower for collecting aerial currents of natural electricity, constructed of three sections, insulated from each other and the earth, or their equivalents, substantially in the manner described.

3. In an electrical tower, the combination of the shutters or slats *g* with the ventilator-vane in such a manner that the vane, through suitable mechanism, always opens the shutters to windward and closes them to leeward, substantially as described.

4. In an electrical tower, the collecting, distributing, and protecting roof H, substantially as and for the purpose described.

5. The combination of the tube J and ventilator L with its vane M and the coiled wire or small cable *q*, substantially as and for the purpose set forth.

6. The combination of the insulated shaft *k* and rods *h* having forked upper ends *k'* with the shutters or blinds *g*, serpentine cam-plate *o*, and ventilator L, substantially as and for the purpose described.

The above specification of my improvement, being a tower for accumulating natural electricity for telegraphic purposes, signed this 29th day of June, A. D. 1871.

W. H. WARD.

Witnesses:
A. L. PALMER,
J. H. STARIN.

Electronic Projects for Beginners

F. G. RAYER, T.Eng. (CEI), Assoc. IERE



ELECTRONIC PROJECTS FOR BEGINNERS

ALSO BY THE SAME AUTHOR

No. BP32	How to Build Your Own Metal and Treasure Locators
No. BP37	50 Projects Using Relays, SCRs & Triacs
No. BP39	50 (FET) Field Effect Transistor Projects
No. BP43	How to Make Walkie-Talkies
No. BP57	How to Build Your Own Solid State Oscilloscope
No. BP67	Counter Driver and Numeral Display Projects
No. BP75	Electronic Test Equipment Construction
No. BP79	Radio Control for Beginners
No. BP84	Digital IC Projects
No. BP90	Audio Projects
No. BP93	Electronic Timer Projects
No. BP97	IC Projects for Beginners

ELECTRONIC PROJECTS FOR BEGINNERS

by

F.G. RAYER, T.Eng.(CEI), Assoc. IERE

BERNARD BABANI (publishing) LTD
THE GRAMPIANS
SHEPHERDS BUSH ROAD
LONDON W6 7NF
ENGLAND

PLEASE NOTE

Although every care has been taken with the production of this book to ensure that any projects, designs, modifications and/or programs etc. contained herein, operate in a correct and safe manner and also that any components specified are normally available in Great Britain, the Publishers do not accept responsibility in any way for the failure, including fault in design, of any project, design, modification or program to work correctly or to cause damage to any other equipment that it may be connected to or used in conjunction with, or in respect of any other damage or injury that may be so caused, nor do the Publishers accept responsibility in any way for the failure to obtain specified components.

Notice is also given that if equipment that is still under warranty is modified in any way or used or connected with home-built equipment then that warranty may be void.

©1978 BERNARD BABANI (publishing) LTD

ISBN 0 85934 054 6

First Published – August 1978
Reprinted – September 1980
Reprinted – June 1982
Reprinted – January 1984
Reprinted – April 1986
Reprinted – February 1988
Reprinted – April 1989
Reprinted – August 1991

Printed and bound in Great Britain by Mayhew McCrimmon Printers Ltd.

CONTENTS

Page
INTRODUCTION 7
  Conversion Table 8

SECTION 1: "NO SOLDERING" PROJECTS 9
  Theoretical Circuits 11
  Signal Tracer 13
  Multivibrator 14
  "C" Substitution Box 16
  "R" Substitution Box 18
  SCR Controlled Light 18
  One Transistor Intercom 21
  Tuned Ferrite Aerial 23
  Diode Radio 25
  One Transistor Amplifier 31
  Two Transistor Amplifier 32
  Push-Pull Output Stage 34
  Boost Speaker 37

SECTION 2: MISCELLANEOUS DEVICES 39
  Soldering 39
  One Transistor Audio Oscillator 40
  Multivibrator 41
  Glissade 43
  Morse Oscillator for Phones 45
  Two Door Siren 46
  UJT Oscillator 48
  UJT Continuity Tester 49
  UJT High Voltage Producer 50
  Signal Blinker 51
  Mains Wiring 52
  Dimmer/Heat Control 53
  Two Power 55
  Sensitive Touch Switch 56
  Water Level Indicator 58
  Optical Isolator 60
  LED Indicator 61
  "Magic Candle" 62
  "Nerve Tester" 63

Page
Burglar Alarm 64
Transistor Tester 65
Treasure Locator 67

SECTION 3: RADIO AND AUDIO FREQUENCY 71
MW Booster 71
Midget MW Diode Radio/Tuner 74
One Transistor VHF Receiver/Converter 75
Morse and Sideband Resolver 78
Easy Preamplifier 81
741 Preamplifier 83
Tone Control for Your Discs Etc. 85
Two Channel Mixer 86
¼ Watt IC Amplifier 88
Class A Amplifier 90
Two Stage Amplifier 92

SECTION 4: POWER SUPPLIES 95
Easy PSU 95
Easy Regulated PSU 97
Multi-Voltage Regulated PSU 98
One Transistor Adjustable PSU 99
Zener Regulated Supply 102
Motor PSU with Reverse 103
Wrong Polarity Protector 104
Transistor Lead-Out Positions 105

EQUIVALENT SEMICONDUCTORS 107

Page 7 & 8 missing --------->

SECTION I
"NO SOLDERING" PROJECTS

With these, connections are generally made with small terminals, or nuts and bolts. By this means components are connected together, and fixed to an insulated board or panel.

A project can be built using one size of bolt and nut throughout, but it will be found convenient to have two or three sizes. Small nuts and bolts can then be used for connections between components, while larger bolts with extra nuts, or terminals, can be used to connect external items, such as headphones.

For one size throughout, 6ba screws or bolts will be satisfactory, about ½ inch long. Only a few are needed for each project, but they are quite inexpensive in 50 or 100 packs. Some extra nuts will prove useful, and also a quantity of 6ba washers. If the insulated board or panel is not too thick, the ½ inch bolts with an extra nut each will do as terminals for connecting external items.

A 4ba bolt is *larger* than 6ba, and a few of these, ½ inch or more long, also with washers and nuts, can be used for terminals, if preferred. It is also possible to obtain terminal heads, so that bolts with nuts can be used as terminals.

The 8ba size is *smaller* than 6ba. These can be of advantage in a project where size is to be kept down, or for positions where several leads come close together (as at a transistor). Bolts, nuts and washers (8ba throughout) can be obtained together.

Naturally all sorts of nuts and bolts, to hand or obtained from constructional toys or old electronic equipment, can be used. Results are not going to depend on the sizes used, which are more a matter of convenience and appearance

There is also considerable latitude in the insulated panels or boards used to carry the components. Some projects need only a few holes in a small board. Here, it is convenient to use 1/16 inch thick or similar paxolin sheet, cutting a piece of the wanted size and drilling holes for the bolts or terminals. A small hand drill is satisfactory for this purpose. The drills used can be 3/32 inch for 8ba bolts, 1/8 inch for 6ba, and 5/32 inch for 4ba, or any similar sizes giving clearance.

Where drilling is inconvenient, a ready-perforated board must be used. For projects where size is not important, perforated 1/8 inch thick hardboard is suitable – holes are generally at 1 inch intervals, but this is not important. For this type of board, the size of the holes will generally mean that 4ba nuts and bolts will be beeded.

Plain perforated board (that is, without any conductor foil) can be obtained with holes at 0.1 inch or 0.15 inch spacing but these holes are too small and too close together. However, such boards can be used instead of plain unperforated paxolin sheet by drilling the holes larger in just those places where bolts must be placed.

There is also a type of eyelet board, with holes at 5mm spacing and just large enough to take 8ba bolts. This is handy for small projects.

It is also relatively easy to prepare a fully perforated board or panel, which can be used for a number of projects in turn.

For a board up to about 4 x 6 inch paxolin 1/16 inch thick is adequate, with 1/8 inch sheet for larger boards. It is also possible to use 1/8 inch or similar PVC or other transparent sheet, which allows connections to be seen on both sides. Plain hardboard, or thin plywood, is also satisfactory. Hardboard or wood should be given a coat of shellac or similar varnish, before use, to keep out damp.

Where size is not important, the board can be drilled with holes spaced 1 inch from each other throughout. Do *not* mark off a grid with pencil lines, as this may cause leakage between adjacent terminals. An easy method is to mark such a grid on paper, secure this over the board or panel with tape, and drill all the holes. Make these of an appropriate size for the terminals or bolts.

For small items, the board will need to be prepared to suit.

But where a board is going to be a general purpose support for several projects in turn, it can be much larger. It is also handy to support it on two strips of wood, about 1 inch high, so that there is clearance underneath for bolts and connections.

It will be found that neat and efficient projects can be assembled on such boards, and that it is easy to check connections or components, or to make changes for experimental or other purposes.

Theoretical Circuits

A theoretical circuits shows an electronic device in simple form. Capacitors, resistors, transistors and other items are shown by their own symbols. Lines representing connections are drawn from symbol to symbol. The layout of actual components in the device may not be the same as the positions of the symbols in the theoretical circuit.

It will be found that it soon becomes easy to follow a theoretical circuit. An understanding of such circuits develops when they are compared with an actual layout which shows components and the connections.

The Signal Tracer in Fig. 1 is an example of this. The main item here is the transistor, which has emitter (E), base (B) and collector (C) wires. For the transistors shown, these wires come from the base as in the diagram, which is of the underside of the transistor. (Emitter, base and collector wires may be in different positions in other transistors.) It will be seen that the emitter E is connected to negative at the battery, and to a clip on a lentth of flexible wire.

The headphones – or single earpiece – go between collector C and battery positive. A headphone jack, marked P, is used to take a plug for the phones. Generally, an on-off switch would be present in one battery connection, but this is not necessary here as the circuit can be interrupted (to switch "off") by unplugging the phones. Exactly the same results would be obtained if two separate sockets were used, to take two plugs from the headphones.



FIG. 1.

Resistor R1 is connected from collector C to base B, and it supplies a base current for the transistor, so that the latter can operate as an amplifier.

The signal to be amplified is obtained through capacitor C1. A capacitor has plates or foils separated from each other by an insulator. There is no direct current circuit through the capacitor, so placing the test prod on various points of a circuit being tested does not upset direct current working conditions.

It is clear, from Fig. 1, how the theoretical circuit is made up as a practical piece of equipment, with C1, R1, transistor, phones and battery connected together in the way required.

With later projects, the theoretical circuit and practical wiring diagram may be shown together in this way, or may appear as separate diagrams when they are larger. If the theoretical circuit and wiring diagram are compared, so that capacitors, resistors and other items on one are also found on the other, it will soon be found that a theoretical circuit is readily followed and understood. It will be noted that the theoretical circuit could be built up in numerous ways, all equally satisfactory.

Signal Tracer

This locates and amplifies audio (sound) signals which may be present in a circuit. Construction is most easily carried out in a small plastic case (Fig. 1). An insulated board about 1¼ x 2 inch (or to suit the case) has three small bolts to secure emitter, base and collector leads of the transistor. Bolts also hold two small brackets, which press on the negative and positive ends of the 9v battery. String or elastic through holes in the board helps to secure the battery.

The prod is a long 6ba or 4ba bolt, or length of screwed rod. Lock one end of C1 lead with nuts, or loop it under the bolt head. Thread the clip flex through a hole in the case, and pass the prod through another hole, as shown. A washer and nut then fix the prod, with the board inside the case. The case lid can then be fitted, and the securing nut can be screwed on the phone outlet. Connections here can be tightly twisted round the outlet tags, and compressed with pliers. A piece of insulating sleeving is put on the test prod, and a clip with fixing screw is attached to the flexible lead.

Making Connections

For all the projects in this book, any thin insulated connecting wire can be used; or bare wire with insulated sleeving. It is handy to have two or more colours – such as red for positive, and black for negative circuits.

A loop is made at the bare end of the wire, and is put under the screw head, or under a washer. Where two or more leads go to the same bolt, it is convenient in some cases to have a washer or two extra, to go between loops. Each connection must be reasonably tight, and short circuits must not be allowed between wires or loops which are shown separated from each other.

Battery and external leads are generally of flexible wire. Positive and negative battery clips, with leads already attached, are available for transistor radio and similar batteries. Elsewhere it may be convenient to arrange contacts as in Fig. 1, or to twist wires to the battery tags.

The battery polarity (positive and negative) *must* always be correct, as shown.

When dealing with transistors, it will be found that some types have long wire leads, more than adequate for easy screwed connections. Others, such as the BC108 and similar types, have rather short wires, but can be held satisfactorily with 8ba bolts fairly near eath other. (With other transistor types not used in this section, soldering may be essential for proper connections to be made.)

Circuit Tracing

To use the signal tracer, connect the clip to the earth return line of the receiver or amplifier. The prod is then touched one by one on points where the audio signal should be present, working systematically through the audio amplifier, or from the first point where the signal can be heard. Take in each capacitor, joint, or stage in turn. When signals cease to be heard, the fault lies between this point and the previous point, where signals were heard.

Do not test any mains operated or high voltage equipment, as this is a job for an engineer who will follow the necessary and essential precautions for safety.

Medium or high impedance phones are most suitable for this tracer. A 600 ohm DC headset will be ideal. The tracer can be utilised as an amplifier for a crystal diode radio receiver

Multivibrator

You will be able to use this as an audio oscillator for numerous test purposes, or for Morse Code practice, or as a signal device in place of a bell or buzzer.



FIG. 2.

Fig. 2 shows the practical assembly of the device on an insulated board. A theoretical circuit is given in Fig. 14, and is not repeated here, so Figs. 2 and 14 should be looked at together.

R1 is the collector load resistor for transistor TR1. Collector current passes through this resistor, and an audio signal voltage is developed across it. Resistor R2 supplies base current for TR1.

TR2 has a similar collector resistor R4, and base resistor R3. Capacitor C1 couples the signal at the collector C of TR1 to the base B of TR2, while C2 similarly couples TR2 collector to TR1 base. Amplification in the transistors and feedback by the capacitors in this way result in the circuit oscillating. That is, each transistor goes rapidly in and out of conduction in turn, so that a voltage at audio frequency is produced across the collector load resistors. C3 is a coupling capacitor, allowing the signal voltage at the collector of TR2 to be taken to a loudspeaker or headphones.

With a circuit of this type, the component values, transistors, and battery voltage will not be critical. However, resistor values, capacitor values, battery voltage, transistors, and the loudspeaker or other sound-reproducing device will all have an influence on the frequency of oscillation, or tone produced.

The values for Fig. 2 (as in Fig. 14) are R1 6.8k, R2 100k, R3 33k, R4 330 ohm, C1 47nF, C2 47nF, C3 0.47μF, and 2N1306 transistors. This allows a good power output at medium frequency, with a 15 ohm loudspeaker.

An insulated board about 2½ x 5 inch is easily large enough, and it can be fully perforated, or holes can be drilled from Fig. 2, as already described. In many places the wire ends of resistors and capacitors are long enough to reach their connecting points. Elsewhere, bare or insulated wire leads are fitted as shown. Provide three bolts with extra nuts, or three terminals, for the connections to speaker, key and battery.

The loudspeaker should be fitted in a case, this having a front aperture about the same size as the speaker cone. This case can take the circuit board and battery.

For Morse, the key is connected to emitters and battery negative as shown, with flexible leads of convenient length. If the multivibrator is to be used as a warning device then these leads can instead go to a door bell push, or to a relay or SCR, used to complete the circuit, as with some later projects. In this way the multivibrator, with its speaker, can replace a buzzer or bell.

If the frequency of the multivibrator is to be changed, this can readily be done by altering the values of capacitors C1 and C2 in particular. The two capacitors need not be of the same value. Larger values reduce the frequency (lower the tone) while smaller capacitors increase the frequency. C3 also has some effect, due to loading from the speaker.

Such a circuit can be used with a battery voltage as low as 1.5v, for headphones. Transistor types are very uncritical. But if PNP transistors are fitted, the battery polarity must be reversed. The transistors shown are NPN.

"C" Substitution Box

When experimenting with circuits or checking a suspected capacitor, a box bringing into circuit a range of capacitor values may be used. In many circuit positions an exactly correct value is not required for testing by substitute, so that a very large number of capacitors need not be provided.



FIG. 3.

Such a box is easily made as in Fig. 3, using a plastic or other insulated case. Here, point 1 is common to all the capacitors, and any capacitor can be selected by connecting to points 2 to 8. Connections can be taken to 6ba bolts, using extra nuts. An alternative is to have eight sockets, with a pair of test leads equipped with plugs.

Suggested values are C1 100pF, C2 470pF, C2 1nF (1000pF or 0.001μF), C4 10nF (0.01μF), C5 0.1μF, C6 0.5μF, and C7 8μF. As the last capacitor will be polarised, mark its terminal to agree.

These values will be found sufficiently near for use in many coupling, decoupling, by-pass and similar circuit positions. The substitution box can be used in place of C1 or C2 in Fig. 2. But where a defective capacitor is found in a tuned circuit, it should be replaced by the exact value.

By ignoring terminal 1 and connecting leads to any pair of the terminals 2 to 8, two capacitors can be used in series. For those who like to work out the value of such combinations, it can be found from C1 x C2 over C1 plus C2, where C1 and C2 are the actual values present. As example, points 6 and 7 give 0.1μF and 0.5μF in series. The result is 0.1 x 0.5/0.1 + 0.5. That is 0.05 divided by 0.6, or approximately 0.083μF.

By using point 1 for one connection, and joining any two points 2 to 8, capacitors are in parallel. The total value can be found by addition. So joining 6 and 7 would give 0.6μF (0.1μF + 0.5μF).

"R" Substitution Box

A similar box can be made for resistors. If so, where two resistors are in series, the overall value is found by adding the separate values. So if 10k (10,000 ohm) and 5.6k (5600 ohm) resistors were in series, the total value would be 10k plus 5.6k = 15.6k. This would be near enough to 15k to substitute for such a value.

Where resistors are placed in parallel, the value is found as for capacitors in series. That is, R1 x R2 over R1 + R2. So for the 10k and 5.6k resistors, this would be approximately 3.6k.

Naturally each resistor may be selected alone, as for the capacitors. If sufficient terminals are provided, a large number of resistors could be fitted. For most transistor circuits, values from about 150 ohm to 270k will fill most needs.

SCR Controlled Light

This device will switch on a light, when the level of general illumination falls below that for which triggering is set. It can thus be used for an automatic night light. Operation can be from a battery; or from a mains power supply, as described later.

Fig. 4 is the circuit, and introduces two new devices. One is the light-dependent resistor LDR. The resistance of this component depends on the strength of the light falling on it. The resistance is low (some hundreds of ohms) with bright light, but rises to many thousands of ohms in dim light, or darkness.



FIG. 4.

The second device is the silicon controlled rectifier SCR. Normally, this does not allow current to pass from its cathode K to its anode A. However, a small current applied to its gate G will trigger it so that it conducts from cathode to anode. It remains in this state even when gate current is removed. It is restored to the non-conducting state by removing the voltage from its cathode, by opening switch S1.

In this device the SCR is controlled by the LDR. With illumination present the resistance from gate to cathode is low, so that when S1 is closed, current does not flow from the anode circuit through the 6 volt 3 watt lamp. As illumination falls, the resistance of the LDR rises. This continues until a sufficient gate potential is present to operate the SCR, which moves into its avalanche or conducting state, lighting the lamp. The potentiometer VR1 enables the resistance from positive to gate to be adjusted, to set the illumination level at which the circuit operates.

A 50v 1 amp SCR is more than adequate for this circuit, and it resembles a large transistor externally, and can be mounted by its wire ends.



FIG. 4B.

Fig. 4B shows constructional and wiring details. The SCR is mounted on a small insulated board. Clear bared wires are twisted tightly to the LDR, so that this also can be fitted by small bolts and nuts, as shown. The connections to VR1 are also tightly twisted and pressed together with pliers.

A battery holder for four 1.5v cells is shown, and connections to this can be by means of clips which have leads attached. The switch S1 is the small, low-voltage type having small screws, as used for toy lighting circuits and similar purposes.

A hole is cut in the box level with the LDR, which may be directed towards the window of the room, or positioned as found to give the results wanted. The bulb, in holder, can be positioned on top of the case. If light from it reaches the LDR this will not stop the circuit working, as the SCR can only be returned to the non-conducting state by opening the switch S1,

For an automatic night light or similar device, a case can be made from thin wood, with opening back or bottom. The device can also be used for various games, where momentarily interrupting the light falling on the LDR switches on the bulb.

If a detailed reference to the operation of the SCR is wanted, this can be found in "50 Projects Using Relays, SCRs & Triacs" (BP37, Babani Press).

One Transistor Intercom

A single high gain transistor will provide sufficient amplification for a 2-way loudspeaking intercom. This will allow communication between two rooms or other points.

Fig. 5 is the circuit. A 2-pole 3-way switch provides 2-way communication, with a central "Off" position. With the switch as in Fig. 5, section S1A takes loudspeaker SP1 to the base coupling capacitor C1. At the same time, section S1B connects the battery and transistor collector circuit to the



FIG. 5.

speaker SP2. SP1 then acts as a microphone, and sounds are reproduced in SP2.

With the switch in the opposite position, S1A selects SP2 as microphone, and amplified signals pass via S1B to SP1, so that speech can be in the other direction.

The switch, amplifier, battery and SP2 are assembled as the master control unit, and twin leads run to SP1. The person at SP1 should say "Over" so that the other person can operate the switch, and he in turn should say "Over" to signify that SP1 is again acting as microphone.

A simplified home-made change over switch is shown in Fig. 5. This is two strips of metal, pivoted so that they can be swung from side to side, and bearing on two of the three round-headed screws. A strip of insulating material is fitted so that both strips move together. In Fig. 5, this switch is in its "Off" position.

Ready made 2-pole 2-way switches can be obtained and used instead (see Fig. 49). Spring-loaded push switches are also available, and can be wired to provide "press to talk". A switch without a central "Off" position can also be used, a single pole on-off switch then being added in one battery connection.

The master unit can call SP1 by switching to speak, and allowing SP2 to be used as microphone. If calling in the other direction is required, a third connection, with bell push, battery and buzzer can be used. (An alternative, requiring more circuitry, but avoiding the need for a third wire, will be found in "Two Transistor Electronic Projects", (BP30, Babani Press.)

Fig. 5B shows assembly of the intercom in a wooden case. A 3½ inch speaker is suitable, so the whole can be quite a compact unit. The home-constructed switch, using the bolts below the speaker, can be replaced by a ready-made switch, as described, if preferred.

Best results are obtained with speaker units of quite high impedance – say 45 ohm to 75 ohm or so. The few other components are assembled on a small insulated board, as for earlier circuits.



FIG.5B.

The speaker at the remote point also requires a small case. Dimensions are not important, and it is possible to utilise plastic boxes of suitable type for each unit. Connections between units are by twin bell wire, or any similar twin conductor. With a transistor of other than the type shown, the value of R1 can be chosen to give maximum amplification.

Tuned Ferrite Aerial

This simple device will allow "portable" reception with the old type of receiver which normally requires an external aerial, and it can also give improved reception in terms of freedom from interference on the 160 metre amateur band and adjacent frequencies. As shown in Fig. 6, it consists of a tuned circuit with ferrite rod, and a coupling winding to connect to the receiver aerial and earth sockets. It will be found very useful with a communications type receiver, where a long extended outdoor or similar aerial results in a high level of noise and interference.



FIG. 6.

The device is constructed in a plastic lunch box about 6 x 4 x 4 inch or other *insulated* case. Some boxes of this kind, though strong, are of brittle material. These must be drilled without too much pressure, or they may crack. Drill points should also be sharp.

The rod is 6 inch long and 3/8 inch in diameter, and it is supported by two strips of insulating material, which are fixed with brackets. Each strip has a V-shaped notch, so that the rod can be held with thin string. L1 is the tuned winding, and it had sixty turns of 24 swg enamelled wire, side by side. Connections can be made to the frame (moving plates) and fixed plates of the capacitor VC1 by means of small bolts, or may be lightly twisted.

L2 is the coupling winding. Many communications type receivers have a low impedance input circuit, and twelve turns will be adequate for L2. The same wire can be used as for L1. With other receivers it may be worth while to experiment with the number of turns on L2, for best reception.

An air-spaced single gang capacitor of about 315pF is most suitable for VC1, and will allow the usual medium wave band of frequencies to be tuned as well. However, a smaller capacitor is suitable if the ferrite aerial is for 160m reception only, or for the high frequency end of the medium wave band. The actual frequencies tuned can be lowered by having more turns for L1, or by using a larger capacitance for VC1, or by having L1 more nearly towards the centre of the rod. Reducing VC1, or the number of turns on L1, or moving L1 to the end of the rod, will raise the highest frequency tuned.

The rod is directional, so the unit can be positioned for best signal pick up of wanted transmissions, or minimum reception of interference.

VC1 has to be adjusted in conjunction with tuning of the receiver and is set for best reception. Tuning with this control should be quite sharp.

A ready made MW transistor type receiver aerial can be useful for the medium wave band, and may in some cases reach 160 metres, if VC1 has a low minimum capacitance, and the winding is quite near the end of the rod. But should tuning not reach a high enough frequency, some turns will have to be removed.

Diode Radio

A lot of interest can be obtained from a diode radio receiver. It requires few components, no battery or other supply, and can give good headphone reception of a few of the more powerful transmitters. It can also be used as a tuner, as shown later, and will provide excellent audio quality for local station reception.

The circuit in Fig. 7 is intended for medium wave reception. That is, from about 200 metres to 500 metres, or 1500 kilohertz to 600 kilohertz.

The coil L1 is tuned by the variable capacitor VC1. At resonance with the wanted transmission, a signal voltage is developed across the coil. Detection or demodulation by the diode D1 allows the audio component of the signal to be recovered, and taken to the phones or to an amplifier. Such "crystal sets" were used in very many homes, in the early days of radio.



FIG. 7.

Fig. 7B shows the practical layout. It is convenient to use an insulated board larger than necessary, so that a transistor amplifier can be added later. A board about 5 x 8 inch is suggested, and it can be supported on 1 inch high runners (strips of wood) so that there is clearance for screws or terminals.

Coil L1 is wound with 26swg or similar wire, and has seventy turns, side by side. Secure the wire by passing it through two small holes, wind on about thirty five turns, and form a loop. Continue to wind in the same direction for a further thirty five turns, cut off the wire, and secure the end through two holes. The tube used can be 1½ inch to 2 inch in diameter, and can be paxolin, or can be made by winding thin card round a suitable object, smearing a little adhesive on to form a tube.

Point 1, the beginning of the coil, is taken to the fixed plates tag F of the variable capacitor, which is also connected to diode D1. The tapping 2 goes to the aerial terminal. End 3 is taken to the moving plates connection or metal frame of the capacitor. Ends 1 and 2, and loop 3, are left long enough to reach these points, and the insulation is carefully scraped off the wire where connections are to be made. The capacitor VC1 can best be about 500pF, but this exact value is not essential.



FIG. 7B.

Four terminals, for Aerial, Earth, and Phones, will complete the receiver. Best results will be had by connecting a good headset, of about 500 ohm to 2,000 ohm. Very low impedance earpieces, such as are employed with some transistor receivers, are not suitable here.

With a simple receiver of this kind it is necessary to employ a reasonably effective aerial and earth. Only in some circumstances will volume be great enough with no earth, or with a short aerial. The earth connection can be taken to a metal spike in the ground, or to a metal object buried in soil, or to any other available earth other than a mains circuit earth. (No connection must be made to any mains plug or other mains circuit.) A cold water pipe may provide a good earth. Gas pipes should not be used.

For the aerial, a length of aerial wire some 30 ft to 75 ft or so in all may form the aerial itself and lead-in. If this can be suspended quite high, and clear of buildings or earthed objects, signal strength will be improved. However, satisfactory reception may be obtained from an indoor aerial, or shorter aerial, if a good earth is present. A simple indoor aerial can be made from about 15 ft to 20 ft or so of thin insulated wire, fitted along two walls of the room near the ceiling with adhesive tape. (Do not fold the wire back on itself to obtain a greater length.)

Volume will be improved, with a poor aerial, if the aerial lead is taken directly to point 1 of the coil or F at VC1. However, this will make tuning even more flat or unselective, so cannot generally be employed with a long aerial.

Use as Tuner

In Fig. 8 components C1, C2 and R1 are added. C1 and R1 are to allow proper working of the detector diode D1, and may be considered as replacing the headphones. C2 is a coupling capacitor passing audio signals to the following amplifier.



FIG. 8.

As with the previous circuit, any general purpose detection type diode is satisfactory for D1, such as the OA91 and many similar devices. The value of C1 is not critical, and this component can be about 470pF or 1nF. R1 can be 100k to 220k or so. C2 should be of quite large value, and can be $0.1\mu F$ to $0.5\mu F$.

D1 can be moved from the position in Fig. 7B, and the few extra components added, as in Fig. 8.

When using the tuner to feed an amplifier, note that one phone terminal P is the earth line, and that audio signals are taken from the other terminal, connected to C2.

The earth line of the amplifier is connected to the earth line of the tuner. For a sensitive or powerful amplifier, a screened audio lead is recommended. This has an inner screened lead, which goes to C2, and a conductor former by the outer brading, which is the ground or earth. The lead should be fitted with a plug to suit the amplifier input socket.

Where the tuner is to be followed by a small headphone or similar amplifier, a screened audio lead is not required. So then connections are merely taken from terminals P-P in Fig. 8, remembering to join amplifier earth and tuner earth circuits as explained.

Medium and Long Wave

The addition of long wave coverage is worthwhile in some areas, and the coil can be modified as in Fig. 9 so that both MW and LW can be tuned.

A tube about 3 inch long and approximately 1½ inch in diameter will be necessary. The section L1 is wound as before. L2 consists of about two hundred turns of 34swg or 36swg wire, in two compact piles of one hundred turns each. All turns throughout are in the same direction. The junction of L1 and L2 goes to the waveband switch S1. The second switch terminal goes to 4 and earth line. MW tuning is obtained with S1 closed, and LW tuning with S1 open.



FIG. 9.

For accurate coverage of the usual MW and LW bands, and using a 1¼ inch diameter tube, L1 can be eighty-four turns of 32swg enamelled wire, with tapping 2 sixty turns from point 1. Leave a space of 5/8 inch and glue on a card disc cut to fit the tube. Also glue on two further discs, leaving spaces of ¼ inch between them. L2 is wound with 32swg double cotton covered wire, with one hundred and twenty turns in each slot (making 240 in all for L2). The coil can be fixed with two screws or small bolts, with spacers or extra nuts to hold it a little clear of the board. The windings should not be varnished, covered with adhesive, or wax.

With circuits of this kind there is no ganged tuning, or need for exact tuning of a particular frequency band. This means that coil winding details (wire gauge and covering, and diameter, or number of turns) can be varied to suit materials to hand. Ready-made coils can also be tried. Some commercially made coils with cores can give a slightly better performance than the air-cored home made type of coil. Coils can also be wound in a similar way to that in Fig. 6.

One Transistor Amplifier

Headphone volume obtained from the crystal diode receiver can be considerably boosted by adding a single transistor audio amplifier. Space for this can be found on the circuit board.

In Fig. 10, resistor R2 and the transistor have been added, with a switch S2 for on-off switching of the battery. R1, C1, D1 and C2 are already present, as shown in Fig. 8.



FIG. 10.

TR1, R2 and S2 are connected as shown. For TR1, a BC108, 2N706, or similar general purpose NPN transistor will be satisfactory. R2 can generally be 1 megohm with satisfactory results, but it can be worth while trying values from about 100k to 2.2 megohm here, as performance depends on the transistor, phones, and battery voltage.

Medium and high impedance phones, such as a 600 ohm DC headset, will be most suitable. The battery can be 4.5v to 9v.

If the phones are first connected to terminals P-P in Fig. 8, then taken to terminals P in Fig. 10, a very considerable increase in volume should be obtained.

If a PNP transistor is to be tried in this circuit, the polarity of the battery *must* be reversed.

Two Transistor Amplifier

Fig. 11 is the circuit for an easily made 2-transistor amplifier which can provide reasonable loudspeaker volume. The audio signal is taken to the input terminals, battery negative being the grounded side of this circuit.



FIG. 11.

C1 couples the audio signal to the base of the first amplifier TR1, which receives base current through R1. An amplified signal is developed across the collector resistor R2, and is coupled to the base of the following amplifier TR2 by means of C2.

The two resistors R3 and R4 set the base operating conditions for TR2, and the output is taken from TR2 emitter.

Fig. 11B shows assembly of the components on a small insulated board. If preferred, connections between components can be on the underside of the board, in the way shown for later circuits. Fit red and black flexible leads for battery connections. The amplifier, with its battery, can be fixed in an insulated box or metal case. Sockets can then be used for input and output circuits, and an on-off switch can be placed in one battery lead.



FIG. 11 B.

The board can be secured with bolts through its fixing holes, and through the bottom of the case. Extra nuts or other spacers must be placed between the case and board.

Whenever a metal box is used, remember that all connections and other circuits except the earth line must be insulated from the metal. The metal case itself is normally connected to the earth line, and a lead can be put under one of the fixing screws for this purpose. In Fig. 11, both input and speaker are returned to the earth line. So 3.5mm jack sockets of the type in which the outer or sleeve contact is common to the fixing bush could be used, as these points will be connected to battery negative and the earth line and metal box. But with some circuits it is necessary to use an insulated jack socket, or to insulate this from the metal. An example of this would arise if the speaker were placed in the collector circuit of TR2, as the outer or sleeve circuit would then need to go to battery positive.

Instead of the type of socket which takes a jack plug, ordinary single sockets can be used – two for input, and two for output. Or wires may be connected directly to the terminals provided in Fig. 11B.

Input to this amplifier may be directly from the crystal set, Fig. 7. Connect earth and battery negative lines; and C1 of the amplifier to D1. The effect of connecting C1 and R1, Fig. 8, across the crystal receiver phone terminals, can be tried.

The amplifier can operate a speaker of 15 ohm to 75 ohm impedance. Current with a 9v battery is about 25–30mA with a 15 ohm speaker, or 10–15mA with a 75 ohm speaker. Headphones can also be used if required.

Two BC108 or similar transistors will give very good results. For transistors of different type, it may be necessary to alter the values of R1 or R2 for best operation of TR1, or R3 or R4 for TR2.

Push-Pull Output Stage

For good volume, with low battery current, some form of push-pull output stage is generally used. This has two transistors, and each amplifies one half of the audio signal. Base bias conditions of the two transistors are so arranged that only a low current flows during silent intervals. Overall battery drain is thus much lower than if a single transistor were used to obtain a similar level of volume.

Fig. 12 is a typical push-pull output stage. T1 is the input or driver transformer, and an audio signal is taken to its primary P. The secondary S is centre tapped. So for one half of the audio cycle one transistor base is driven positive and the other transistor base is driven negative, this being reversed for the remaining half cycle. Thus each transistor conducts alternately, and the centre-tapped output transformer T2 combines the collector currents, to operate the speaker connected to the secondary S.



FIG.12.

R2 and R3 set the base bias conditions for the transistors. Bias is arranged so that collector current is low, when no audio signal is present. The emitter bias resistor R4 limits peak collector current.

If R3 is a pre-set resistor, as in Fig. 12, operating conditions can be arranged to suit the transistors fitted. For best results TR1 and TR2 should be a matched pair. This means that they will have similar gain and current characteristics. However, two transistors of the same type number will generally be satisfactory.

It is assumed that the same battery will supply earlier stages of the amplifier, and current for this purpose is taken from C1 and R1. R1 and C1 prevent audio signals present in the positive line passing back to earlier amplifier stages. The by-pass capacitor C2 also helps in this respect. With simple circuits not giving much overall amplification, or small power outputs, R1, C1 and C2 might all be omitted.

TR1 and TR2 are NPN transistors. If PNP transistors are to be tried, battery polarity must be reversed, and also the polarity of C1 and C2. PNP transistors, with a positive earth line, could be convenient where earlier stages also use PNP transistors and a positive earth.

When first using the circuit, a meter can be placed in one battery lead. R3 is set for minimum value. Battery current will then be low, but reproduction will be very distorted. Slowly increase the value at R3 until reproduction is at its best. This will cause a rise in battery current, so do not set R3 to an unnecessarily high value.

The driver transformer T1 can be of about 5:1 ratio. T2 can be a miniature type for low power, or a 500 milliwatt or 1 watt component for larger power. Its ratio can generally be about 8:1, for use with a 3 ohm speaker. T1 must have a centre tap on its secondary, and T2 a centre tapped primary.

Many transistors other than those given below can be used, the following being typical for negative ground or positive ground.

Negative earth (NPN transistors). 2 x BC108. R1 1.2k. R3 100 ohm fixed or 250 ohm pre-set. R4 4.7 ohm.

Positive earth (PNP transistors). 2 x AC128 or 2 x AC142. R2 4.7k. R3 82 ohm or 250 ohm pre-set. R4 4.7 ohm.

R1 will generally be 1k to 2.2k, depending on the earlier amplifier. The primary of T1 can be connected to terminals P in Fig. 10; or alternatively to any audio source where a reasonably strong signal is present.

Where signals are too strong, an audio gain control needs to be fitted. In Fig. 8 this can be done by omitting R1, and disconnecting C2 from D1. Connect the outer tags of a 100k volume control or log pot from D1 to earth line. Take C2 to the centre tag or slider of the potentiometer. Any required audio level can then be taken off by adjusting the control knob.

Fig. 12B shows the board layout.



FIG. 12 B.

Boost Speaker

For best reproduction, a speaker needs to be enclosed in a cabinet or fitted to a baffle board. A cabinet can be made from wood, and can be about 6 x 10 inch and 4 inch deep, or as required for the speaker unit. Cut an aperture in the cabinet front to match the cone diameter, and glue thin fabric behind this opening. The speaker can be fixed with nuts and bolts, or short woodscrews driven in from behind.

Connect flexible leads, with separate plugs or a jack plug, to suit the equipment.

Small pocket receivers, which have a miniature speaker, can give much improved volume and reproduction when used with a larger speaker. If a headphone socket, operated from the receiver output stage, is present, it is only necessary to plug the speaker into this. A fairly large speaker, of sensitive type, will give best results. A unit 5 inch to 6 inch in diameter, or about 4 x 7 inch, will be convenient. The speaker has to be of approximately the correct impedance, which should be found in the receiver operating instructions. Where the speaker impedance is wrong, a matching transformer has to be employed between receiver and speaker.

Extension speakers are less frequently used today, but if two leads are run into another room programmes from a non-portable type radio can be listened to there also.

Other "No Soldering" Projects

It will be seen that many of the circuits which follow, and especially those of simpler type, can be assembled without soldering. Where necessary, an examination of the practical layouts will give an indication of how components can be placed. Generally a little extra space should be allowed so that nut and bolt connecting points need not be extremely close together on the insulated board.

SECTION 2
MISCELLANEOUS DEVICES

Soldering

Soldering for electronic wiring will be found to be a very easy and straightforward matter. An electrically heated iron is usual, and as large areas of metal do not have to be raised to the melting point of the solder, a 20 watt to 25 watt iron is satisfactory. This will be perfectly safe if correctly fitted with a mains plug, and if placed on a metal plate or tray when not actually in use.

It is best to use cored solder, as made for electronic wiring.

Leads, tags and other items to be joined should be clean and bright. They have to be raised in temperature to the melting point of the solder at the actual points where a joint is to be made, and the active core of the solder, or flux, must be present here when the joint is being made.

The iron should be tinned – that is, have melted solder on its tip – and have reached its correct temperature. Leads can be hooked or looped into position. The joint is then heated with the iron, and the solder is simultaneously applied to the joint, so that it melts and flows over the surfaces to be soldered. This usually takes place in a second or two. The solder and iron should be removed at once, as excessive heating may damage some components, and especially transistors or other semiconductors. The joint cools in a few seconds, and should be rigid, and solder having flown onto the items to be joined.

A probable cause of poor joints is insufficient heating of items to be soldered, or carrying solder to the joint on the iron, so that the activity of the flux is wasted.

Electronic items such as tags and the wire ends of components are generally designed for easy soldering. They will be copper, tinned copper, and similar metals and alloys which solder readily. For this reason, difficulties are unusual.

Some metals do not solder readily, or need special methods. Aluminium is one of these, and it is not used where popular cored solders intended for copper or general wiring are employed.

Make sure that heat from the iron does not damage furniture or other items, and keep the flexible cord away from the heated tip. Always switch the iron off at once when the work in progress is to be left.

One Transistor Audio Oscillator

This can be used instead of a bell or buzzer warning, or for code practice and similar purposes. It needs very few components, Fig. 13, and can be made to work satisfactorily with a wide range of transistors.

In Fig. 13, an NPN transistor is shown in the theoretical circuit, so battery polarity is as indicated, with negative to emitter. If a PNP transistor is fitted, battery polarity must be reversed.



FIG.13.

(1) shows leads from a typical NPN transistor, such as the BC108, 2N706, and similar types. (2) is the base of the PNP AC128 transistor.

T1 can be a small speaker matching transformer, as used for push-pull stages. A centre tapped primary is necessary. The secondary S can be taken to a loudspeaker or headphones.

The values of R1, C1 and C2 can be varied considerably. C1 can be 0.1μF or so. R1 determines to some extent the power obtained, and can be about 22k, increased to 47k or 100k for lower power. The value of C2 has considerable influence on the note, or frequency of oscillation. Increasing the value of C2 lowers the pitch. C2 can be about 47nF to 4.7nF or thereabouts. A 9v battery can be used. Changes to the supply voltage will influence the note produced.

Fig. 13 also shows a layout for components, using either a fully perforated board, or a panel drilled to suit. Transformer T1 is fixed by screws. Small transformers of this type are usually wire ended, or have pins which pass down through holes in the board.

The wire ends of the resistors and capacitors are passed down through suitable holes, and bent over. The board is then turned so that the underside wiring can be carried out. In most places the wire ends of the components will be long enough to reach connecting points. Elsewhere, 24swg tinned copper wire, or similar connecting wire, will be used. Make the soldered joints as described, and snip off unwanted ends of wire. It is as well to leave the transistor to last, as this avoids heating it unnecessarily when soldering other items. Lengths of flex, anchored at holes in the board, are used for battery, key (or push) and speaker connections.

Multivibrator

Fig. 14 is the circuit of the multivibrator assembled in Fig. 2. Reference to Fig. 14B will show how this can also be prepared on a tag board.

The tag board has two rows of tags fitted to an insulated board, and it is five tags long in Fig. 14B. Boards of this type can be obtained in many sizes. It is also easy to cut a section from a long tag board, to suit the needs of the item to be assembled. Such boards are very handy indeed for electronic assemblies, as the tags support resistors, capacitors and other items, and a neat layout is readily achieved.



FIG. 14.

Tag strips are also useful for projects, and may have any number of tags required. Long tag strips can be cut down as necessary. Short tag strips have one tag for mounting the strip, longer strips having two tags formed as brackets for this purpose.

Place the components approximately as in Fig. 14B, and solder the wires to the tags. If any component values may be changed, do not twist the leads tightly round the tags before soldering, or removal will be difficult.

Wires which cross can be kept clear of each other, and then no insulated sleeving will be necessary. The transistors can be soldered on last, and can readily be changed without disturbing other parts.

The same layout can be used for the next project, though the component values are different.



FIG.14B.

Glissade

This device will produce swooping, rising and falling tones, for "effects" purposes, or can with additional skill be used to obtain musical notes through several octaves. The circuit is shown in Fig. 15, and reference can be made to Fig. 14B for a practical layout on a tag board.

In Fig. 15, suitable component values are:

R1	10k	C1	22nF
R2	12k	C2	22nF
R3	100k	C3	22nF
R4	10k	VR1	100k linear pot.

Transistors: 2 x BC108 or similar types.

The circuit is a wide frequency audio oscillator, in which the pitch can be controlled by VR1, and "on" switching is obtained by S. The oscillator is placed in a box, so that switch S and VR1 can be mounted on the top. The switch is a strip of springy metal, fitted with a spacer and bolt, so that it is just clear of a further bolt. A small downwards movement of the arm or knob completes the circuit.



FIG. 15.

VR1 has a ¼ inch shaft coupler, into which is screwed a length of 4ba threaded rod. A knob is also fitted to the end of this rod. It can be swung backwards or forwards, to change the resistance of VR1. Connect VR1 so that movement of the knob towards the right raises the pitch.

Output from C3 can go to high resistance headphones, for amusement, but should be taken to an audio amplifier. Gain of the amplifier will have to be turned back somewhat, as the output from the glissade is at a quite high level.

Swooping tones are produced by holding down the switch S and swinging the control knob attached to VR1 from side to side. For notes which do not swoop to frequency, switch S must be released while VR1 is rotated. A slight quivering motion of the hand controlling VR1 will produce a vibrate effect. It is useful to have an ordinary switch in parallel with the knob control S, and to have the amplifier audio gain control near the left hand, so that fading effects can be produced as well.

About 4.5v to 9v can be used, this influencing volume. Should other transistor types give an unsuitable range of frequencies, the note can be raised by reducing C1 or C2 (or both).

Morse Oscillator for Phones

By using the windings of magnetic headphones as part of the feedback circuit from collector to base, a single transistor oscillator can be made as in Fig. 16. Medium to high impedance phones are most suitable, and numerous other transistor types can be fitted.

The transistor and few other items are mounted on a tag strip. This is in turn bolted to a small insulated box, which can carry the battery. A 4.5v supply was found best with this oscillator. The note obtained can be modified by altering the voltage, resistor, or capacitor values.



FIG.16.

For serious code practice a good Morse key is required. It is adjusted so that only a small movement of the wrist is needed to operate it. Each letter consists of short and long sounds, shown as (•) and (–). The (–) has three times the length of the (•)

A •–
B –•••
C –•–•
D –••
E •
F ••–•
G ––•
H ••••
I ••
J •–––
K –•–
L •–••
M ––

N –•
O –––
P •––•
Q ––•–
R •–•
S •••
T –
U ••–
V •••–
W •––
X –••–
Y –•––
Z ––••

After learning the code, practice between two persons will be best to gain speed. Care should be taken to form each letter correctly.

Two Door Siren

This can be used as a warning device instead of a door bell. The circuit is arranged so that two bell pushes can be connected, and they will provide distinctive notes. It is thus clear which of the pushes has been used, as, for example, to distinguish between front and back doors.

Fig. 17 is the circuit. The collector of each transistor drives the base of the other through a capacitor with parallel resistor. T1 is centre tapped, and couples a loudspeaker.

Component values are intended for two AC128 or AC142, or similar transistors, as used in ½w to 1w output stages of receivers and small amplifiers. Other transistors will of course operate in this circuit. The pitch obtained can be modified by changing C3. The circuit shown is for PNP transistors, and battery polarity has to be reversed for NPN transistors.



FIG. 17.

Fig. 17B shows the oscillator wired on perforated board. For a self contained unit, the board can be screwed inside a case which is large enough to house the speaker and battery.

The note obtained when Push 1 is operated depends on the value of R3. In the same way, R4 allows a different note to be obtained when Push 2 is closed. If necessary, R3 or R4 can be changed, to obtain notes which are readily distinguished.

Transformer T1 is best of fairly high ratio, or can be the usual type of transistor output transformer, with a ratio of about 8:1. T1 and loading by the speaker influence the volume and notes obtained.



FIG. 17B.

In some circumstances it may be convenient to run a single twin lead from Push 1 on to Push 2, including an extra resistor at Push 2 itself, to modify the tone. This may save taking leads from Push 2 all the way back to the oscillator board.

UJT Oscillator

The uni-junction transistor is a device having emitter, Base 1, and Base 2, Fig. 18. B2 receives positive bias, in this case through the headphones. When forward bias on the emitter E is reached the UJT conducts.

In Fig. 18, the emitter potential rises as C1 charges through the resistor R1. When the UJT conducts, C1 is discharged, and the process is repeated. This can take place over a very wide range of frequencies, depending on the values used for R1 and C1. Here, these are chosen to produce an audio tone.

A battery supply of 3v to 9v will be convenient. For use of the UJT oscillator during code practice, place the key in one battery lead.



FIG. 18.

UJT Continuity Tester

Fig. 19 shows actual assembly of the circuit in Fig. 18 on a small perforated board. This is fitted in an insulated box, which carries a phone jack socket, and two sockets for Morse key or test leads. A 9v battery is used, secured with string or elastic.

For continuity tests, take prods or clips on the test leads to the suspected item. If the circuit is in order, the UJT oscillator will produce an audio tone. Oscillation will be obtained with a series resistance between the prods of up to 20k or more, so various components can also be tested, and some idea of the resistance in circuit can be gained from the sound obtained. The tester can also be used to check bulbs, lamps, fuses, extension and other leads, and similar items – these must of course be removed or disconnected from the equipment, before being tested.



FIG. 19.

UJT High Voltage Producer

The UJT oscillator can be used to produce a high voltage, at very low current, by connecting a transformer as in Fig. 20. A loudspeaker transformer, as would be used in valve equipment, is suitable, and will have a ratio of about 45:1 or so. The usual secondary, or low-resistance winding, is connected to B2 and positive, so that a step-up of voltage is obtained. This should be found to light a small neon lamp.

VR1 is fitted to allow some adjustment, to find the most suitable frequency of oscillation. For maximum possible high voltage output, if required, operating voltage and current should be raised. No rating of the UJT must be exceeded. For the 2N2646, the supply should not exceed 30v, emitter current should not be over 50mA, and dissipation of power in the device should not be more than 300 milliwatts. (Dissipation can be found from Voltage x Current.)



FIG.20.

A small mains transformer can be used for T1, with a low voltage winding, such as that for a 6.3v heater circuit, as primary, and the 200/250v winding as secondary. The high voltage output is alternating current.

Signal Blinker

Fig. 21 is a multivibrator in which the feedback capacitors C1 and C2 are of high value, so that conduction alternates between TR1 and TR2 at a low rate. A light emitting diode is placed in the collector circuit of TR2, and so flashes on and off.

This device can be used for various instruments and other equipment, and a flashing indicator draws attention to a greater extent than does one continuously illuminated. The LED can be located at any required point, with leads running to it.

Transistors other than the types shown can be utilised. R4 can usually be about 150 ohm for a 3v supply, 470 ohm to 1.2k for 6v, or 680 ohm to 1.5k for 9v. This depends to some extent on the amount of light required when the indicator is operating. Lower resistor values at R4 will increase light, but current must in any case be limited to the LED rating.



FIG. 21.

C1 and C2 need only be 6.4v working, and the device can be assembled on a very small perforated board. See p.61 for LED polarity.

Mains Wiring

All the devices described so far have operated from low voltage batteries, so than no shock hazard exists with them. However, it is necessary to employ mains power for some units, and proper care must then be taken to avoid any danger.

Power should be drawn from a 3-pin plug, and this should have a 3A or other low rating fuse installed. The live or L, neutral or N, and earth or E conductors must be correctly connected, both at the plug and the equipment.

The plug must always be withdrawn from the supply socket, before touching any internal connections, or making any adjustments or checks of any kind.

Apparatus operated from the mains must be constructed in a strong insulated box, such as can be obtained from various suppliers of electrical equipment; or when built in a metal box, the box must be soundly earthed. This is achieved by bolting the mains cord earth conductor to the box.

Boxes or cases can have ventilation holes or slots, but must be closed so that no one can touch live or dangerous connections or parts inside. It should be remembered that unskilled or unaware persons may eventually handle or use the equipment, so it must be arranged to present no unexpected hazards such as live terminals or parts, or openings for the fingers.

If these points are remembered, mains operated equipment can be safe to use and handle. No switch or other means of interrupting the circuit is put in the earth conductor, and any switch or equivalent device is placed in the live or L conductor. This leaves both earth and neutral permanently connected, for maximum safety.

Dimmer/Heat Control

It is often convenient to dim a filament lamp, or reduce the heat of a soldering iron to be left on for long periods, or the power of a low wattage heater. The silicon controlled rectifier circuit in Fig. 22 can be used for these purposes.

When the switch marked "Full" is closed, current for the load passes through this, so that full power is obtained.

When this switch is opened, current passes through the SCR. This device conducts only when the gate has been triggered, and the instantaneous point in the alternating current cycle where this arises is determined by the setting of the potentiometer VR1. Triggering is advanced as the wiper of VR1 is moved towards R1. The average power supplied to the load can thus be adjusted between wide limits. Since the device is operating as a half wave controller, full power is not obtained with VR1 at maximum, so the switch is closed as described.



FIG.22.

Fig. 22B shows construction of the SCR controller in a metal box. The front of this carries a socket outlet, and the mains cord has a 3-pin plug, wired as explained earlier. It is thus easy to plug the controller into an outlet, and insert the plug of the lamp or other item to be used in the new outlet.

The mains cord is secured with a clamp, and passes through an insulated grommet. The tag strip supporting the small items is mounted by an unused tag. A strip of metal is cut to clamp round the body of the SCR, and is soldered to one tag, as shown. Run earth and neutral leads from the cord up through a hole, and connect them to the E and N terminals of the socket outlet. Also earth the case, at E. A well insulated wire runs from the L terminal of the outlet, to the "Full" switch. The outlet can be secured with bolts and nuts.

R1 should be 1 watt, and C1 is a 500v capacitor. The neon is a small type as used for indicators, etc.

After checking that the controller operates correctly, the back of the box should be screwed in place. A suitable size is about 4 x 5 x 2 inch deep.



FIG.22B.

If a fully insulated box is used instead, then the bush of VR1 and of the switch should both be earthed by wires, except when these items are constructed wholly with insulated material. (This precaution is necessary to avoid any chance of metal parts outside the box becoming "live".)

Two Power

A circuit which will allow half or full power can be useful to reduce the heat of a soldering iron, or for dimming a filament lamp.

Fig. 23 is an easy circuit of this type. Full power is obtained when the switch S is closed. With S open, the silicon rectifier allows current to flow in one direction only, so that power is approximately halved. A 600v 1A or 1000v 1A rectifier is suitable.



FIG.23.

This device can be made by using an insulated junction box which will take a socket outlet and also the switch S. A 3-core cord with plug is run to the box, so that it can be used with any power point. The iron or other item can then be plugged into the outlet fitted to the junction box. Remember to make mains connections in the way described earlier, for safety. The switch S should be of fully insulated type.

Sensitive Touch Switch

In Fig. 24, finger contact with the touch pad switches on a low voltage bulb. This circuit is suitable for a battery operated portable bedside light, and for some other devices.

Normally the silicon controlled rectifier is not conducting, so the lamp is extinguished. Finger contact with the pad provides positive base bias for the transistor so that it conducts. This moves the transistor emitter and SCR gate positive, triggering the SCR. Current then flows from cathode K to anode A, and through the bulb. The SCR remains in the conducting condition until the battery circuit is interrupted by opening the switch. A push switch, normally closed, is most suitable here. Pressing it then switches off the bulb.

This touch pad is easily made from a piece of circuit board with foil strips. It can be about 2 x 1 inch, or of any convenient size. Join together alternate foils – e.g., 1, 3, 5 and 7 – by soldering a connecting wire through the holes. This will provide one connection to the pad. The other foils – 2, 4 and 6 – are similarly joined together for the other pad connection.

The pad is fixed to the top or side of a box, which can contain the battery and electronic components.



FIG. 24.

The sensitivity of the SCR, or gate current or potential needed to produce conduction, will depend somewhat on the individual device, while the gain of individual transistors will also be different. Numerous NPN types are suitable. If it is found that the switch is too sensitive, this can be corrected by placing a resistor from transistor base to SCR cathode or negative line. This resistor can be about 470k to 1 megohm or so. Excessive sensitivity will be apparent if the circuit is switched on by dust, damp air, or similar effects. The pad should be kept clean by wiping it with a dry cloth.

Fig. 24B shows assembly of the components on a tag strip. A small 50v 1A SCR is more than adequate. The bulb can be a screw in type, and can be 6.3v 0.15A, or 6.3v 0.3A. A 6v 3W (0.5A) bulb is also suitable, provided the battery is fairly large.

It is convenient to make a wooden box which will take the battery, and leave a little space for the tag strip assembly.



FIG. 24B

Water Level Indicator

This is a battery operated low voltage device, which is triggered by rising water. It can be used to give indication when a tank, cistern, fish or swimming pool has filled to the required level.

Fig. 25 shows the circuit, and also assembly on an insulated board. This also carries the battery, and it is fitted in a metal or plastic box.

In use, the base normally has no positive bias, as the sensor passes no current. When water reaches the sensor, it conducts, and the transistor passes collector current, to operate the indicator. R1 limits base current.

This circuit will operate satisfactorily with a wide range of PNP or NPN transistors, but battery polarity must be reversed for the PNP types.

The indicating or warning device can be one of the multivibrator or other audio oscillators shown earlier. These will give an audible warning, and will draw only a small current, so that a large transistor is not required.



FIG. 25.

For indoor use or in a location protected from rain, the sensor can be two bare wires, about ¼ inch apart, bolted to a strip of insulated material. Where rain could operate the device, it needs to be covered. Alternatively, it can be made from a piece of metal tube, with a central wire, as in Fig. 25. The wire is bound with insulating tape for about half its length, to fit tightly in the tube. Flexible leads are soldered on, and the joints covered with tape. The sensor can be suspended inside the tank or pool, with its bottom at the required water level.

If the transistor is a high gain one, so that damp operates the indicator, sensitivity can be reduced by connecting a 100k resistor from base to emitter.

Optical Isolator

In some equipment complete electrical isolation of one circuit from another is required, though signals must be able to pass. The optical isolator is a neat way to arrange this, and can be fitted up from the circuit in Fig. 26.



FIG. 26.

Electrically, the device is in two sections. The first has the light emitting diode LED, VR1, and transformer T1. When the battery is switched on, current flowing through the LED is adjusted by VR1, so that the LED glows dimly. A signal voltage in the secondary of T1 then modulates the LED light intensity.

To operate this circuit from a radio having a 2/3 ohm or similar speaker, a speaker matching transformer with a ratio of about 45:1 can be used. (The actual ratio is not very important.) Connect the usual transformer secondary to the radio speaker, so that T1 provides a step up effect.

The second part of the equipment has the light dependent resistor LDR, forming part of the network providing TR1 with base bias. VR2 allows adjustment of conditions for best amplification, which will depend on the transistor, and also the LDR, or stray light reaching the latter.

The LED and LDR can be enclosed in a card tube, or should at least be shielded from light, which will swamp the modulated illumination of the LDR, obtained from the LED.

With the circuits switched on, and VR1 adjusted so that the LED is illuminated, turn the radio to give fairly low volume. Adjust VR2 for best bias conditions. When these are reached, signals should be heard clearly in the headphones. VR1, VR2 and the audio input to T1 can then be adjusted for best results. TR1 can be the BC108, 2N706, or similar transistors suitable for audio amplification. A medium or high impedance headset will be satisfactory. Assembly can be on a perforated board, as for other circuits. Take care not to adjust VR1 so that the LED current is too high.

LED Indicator

A light emitting diode can be used as an indicator on battery powered equipment and the current required is very small. Fig. 27 is a LED indicator circuit. Here, the long wire of the LED is negative, but with some LEDs this is not so. A flat side may, or may not, be present. So polarity may have to be

FIG. 27.



found by trial – the correct connections are those allowing the LED to light. The series resistor may be about 150 ohm to 1k or more, depending on the actual voltage, and brightness required. Current drawn varies with different LEDs, and with voltage and series resistance, but can be about 5mA or less, without reducing the brightness too far.

The LED indicator with resistor is connected to the circuit where voltage is present when the equipment is on. LEDs are available in red, yellow, green and other colours, with grommets or clips for panel mounting. Different circuits may be identified by a range of colours.

"Magic Candle"

The triggering of a silicon controlled rectifier can be used for slave photoflash and similar purposes. In Fig. 28 it is employed to switch on a light when a match or lighter is brought near. Sensitivity is best in somewhat subdued light, and it will then be found that striking a match at some distance can bring on the light.



FIG.28.

The LDR has a high resistance when in darkness or subdued light, so that the gate potential of the SCR is not sufficiently high to trigger this device. When light reaches the LDR, its resistance falls, and the SCR gate voltage rises. The SCR then moves into its conducting condition, so that current flows through the bulb. The sensitivity of the circuit, or level of illumination needed to trigger the SCR, is set by VR1.

Components can be assembled on a small tag strip. This, with a battery, can occupy a tubular case, with the lamp on top. An opening is necessary opposite the LDR, and a hole is also made so that VR1 can be adjusted with a screwdriver. Here, a miniature pre-set 50k or 100k linear potentiometer is most suitable. It is necessary to have a small push switch to interrupt the battery current, as the SCR remains in the conducting condition until the circuit is momentarily broken. A 6V battery and bulb can be used. SCRs may fail to operate at all if attempts are made to use them with extremely low voltages, such as a single 1.5v cell.

"Nerve Tester"

This device tests the nerve, concentration, and steadiness of hand, and always provides amusement.

Connections and construction will be seen from Fig. 29. A wooden box at least 10 inch or 12 inch long will be used, and large enough to take the battery and other parts.

A stout bare wire – at least 14swg – is mounted with a bolt and spacer, and is bent in any way found appropriate, and according to the degree of difficulty wanted. A similar wire is fitted with a wooden handle, and has a loop bent at one end. A flexible lead of convenient length is soldered to this wire.

The problem is to pass the loop all along the shaped wire, without allowing contact, until the loop can be rested on a piece of insulated sleeving at the fixed end, as in Fig. 29. The size of the loop will also have considerable influence on the ease or otherwise of the likelihood of success.


FIG.29.

If loop and wire touch, current flows from the battery to the buzzer, which sounds. Current also flows to the relay winding, so that the relay contacts close. Even a momentary contact between loop and wire will thus cause the buzzer to sound until the switch is used to break the circuit.

Any 4.5v, 6v or similar battery and buzzer will be satisfactory, with a relay which operates on a similar voltage. Connections are to the relay contacts which remain open until the relay is energised.

In use, the device can stand upright. A back is attached with small screws.

Burglar Alarm

The same circuit arrangement as in Fig. 29 will provide a burglar alarm operated by pressure mats. The latter are available in various sizes, and consist of a thin pad which can be placed under a carpet or ordinary mat.

Leads from the mat or mats will run to the terminals at X–X. The buzzer should be changed for a bell, which need not be fitted in the box, but can be situated where it is best heard. Momentary weight on any of the mats will then switch on the bell, which will be locked on by the relay as described, and will ring until the unit is switched off.

Transistor Tester

A very useful check of transistors can be made with the aid of a multi-range test meter, with a selection of base resistors to provide base current, as in Fig. 30. This method does not give an exact indication of transistor gain, but it does allow defective transistors to be eliminated, and provides a good idea of the performance to be obtained from surplus or other unknown transistors.

A 6-way switch allows the base to be open circuit, or to receive current through one of the resistors R1 to R5. These values are R1 330k, R2 110k, R3 33k, R4 11k and R5 3.3k. After allowing for the base-emitter potential, switch positions and corresponding base currents are near the following: 1, zero; 2, 10μA; 3, 30μA; 4, 100μA; 5, 0.3mA, and 6, 1mA.


FIG.30.

Polarity is shown for NPN transistors. Reverse polarity of both meter and battery for PNP transistors.

For all tests, initially set the switch to 1, and the meter to its highest range (say 1 ampere). Afterwards, switch the meter to a lower range, after adjustment of the 6-way switch, as may prove to be necessary to obtain an easy reading.

With the switch at 1, a high reading on the meter shows that the transistor has a short circuit from emitter to collector, and is defective.

With germanium transistors, collector current (with the switch at 1) may be 0.1mA or so up to perhaps 0.5mA for small types, and up to some milliamperes for larger types. This small leakage current does not show that the transistor is defective.

In the case of silicon transistors, the leakage current (with switch at 1) will be zero or extremely small, if the device is in good condition.

The switch is then turned to one of the positions 2 to 6. If collector current does not rise, the transistor is defective. If current rises at each step, do not go beyond the switch setting which results in a safe collector current for the device actually being tested. This can be 10mA or less for some small transistors, or 100mA or so for those able to handle greater power, and up to an ampere or more for large power transistors, but limitation of base current will not allow full collector current with large types.

The approximate hFE or current amplification of the transistor (common emitter mode) can be found by noting the approximate base current and collector current. If the collector current with the switch at 1 was very small, it can be ignored. If not, take this value from the actual collector current read by the meter, with the switch at 2 to 6. Collector current (read by the meter) is then divided by base current (taken from the switch position as described). This gives the approximate hFE, or amplification, of the transistor.

It is convenient to mark the switch with the base current figures, and to have three small clips to attach a transistor to the circuit. Switch, clips, and battery can all be fitted to a small box. A development of the circuit would be to include a current meter, with switch and shunts, to replace the external general purpose test instrument.

Treasure Locator

This locator is among the simplest that can be constructed, as it uses an ordinary small portable radio as part of the detection circuitry. No modifications or connections to the radio are needed.



FIG.31.

Fig. 31 is the circuit. It has a single transistor as a low radio-frequency oscillator, operating in conjunction with the search coil. Oscillation is obtained by having a tapped coil, with outer leads going to base and collector circuits. The frequency of oscillation depends on the coil, and the parallel capacitors, trimmer T1, and C2.

The winding of the search coil is 6 inch in diameter, and is of 34swg enamelled wire. The coil former can be made from three pieces of 1/8 inch thick hardboard, or similar insulated material. Cut one disc 6 inch in diameter, and two others about 6½ inch in diameter. Smooth the edges with glasspaper, and cement them securely together, with the small disc between the larger discs. This provides a former with a channel to take the winding. The adhesive should be allowed to dry with the discs under pressure, so that there is no gap into which turns can fall. The former should also be varnished, and allowed to dry, before winding.

The wire is passed up through a small hole, this being point 1. Wind on fifteen turns. Make a loop and pass this up through a hole, for point 2. Wind a further twenty-five turns in the same direction, finishing off at point 3. These leads are scraped and soldered to a small tag strip. This is an anchor point for insulated leads which will run up the handle of the locator (Fig. 32).

Cut a block of wood, and drill it to take the bottom of a broomstick. Cement the block to the prepared coil.

Components are assembled on a tag strip as in Fig. 32. Mount this strip in a plastic lunch box or similar container, which will also take a small 9v battery, and the switch S1. A test for oscillation can be made by placing a meter in one battery lead, and shorting 1 and 3 of the coil. Meter current should change slightly. If not, look for some mistake in wiring.



FIG.32.

A shelf is bolted to the handle, and the detector rests on this, with connections passing down to the search coil. A few loops of tape or string will secure these to the handle.

Operation in Great Britain can be on frequencies under 100kHz. Initially tune the radio receiver to 200kHz on long wave, and place it near the coil. Adjust T1 until a strong whistle is heard in the receiver speaker. This is the 2nd harmonic of the oscillator. T1 is then screwed down very slightly from this position.

The small portable radio is placed on top of the locator box, and can be held here with elastic. It is tuned to the medium wave band. Some small adjustment of T1, and of the receiver tuning, may be required, until a suitable heterodyne is produced by a harmonic or multiple of the oscillator. It will then be found that the pitch of the note changes when the search coil approaches a metal object.

It should generally be found that sufficient coupling is obtained with the receiver when they are situated as in Fig. 32. If not, run a few inches of insulated wire from the transistor collector tag up through the box and place this under the receiver.

For best results, adjustments are directed towards obtaining a good change in pitch, when the search coil approaches metal.

For those interested in details of other detectors, reference can be made to "How to Build Your Own Metal and Treasure Locators" (No. 32, Babani Press).

[illegible]

The circuit is [illegible]. [illegible] 1000kHz. Initially tune the radio receiver [illegible] wave, and place it near the coil. Adjust T1 until a strong whistle is heard in the receiver's speaker. This is the [illegible] of the oscillators [illegible] slightly from this position.

The small portable radio is placed or taped [illegible] and can be held [illegible] wave band. Some small adjustment of T1, and of the receiver tuning, may be required, until a suitable heterodyne is produced by a harmonic or multiple of the oscillators. It will then be found that the pitch of the [illegible] changes as the search coil approaches a metal object.

It should generally be found that [illegible] with the search coil [illegible] in fig. 32. [illegible] a few inches of [illegible] from the [illegible] up through the [illegible]

For best results, adjustments are directed towards obtaining a good change in pitch when the search coil approaches metal.

For those interested in details of metal detection, reference can be made to "How to Build Your Own Metal and Treasure Locators" (No. 32, [illegible] Press).

SECTION 3
RADIO AND AUDIO FREQUENCY

MW Booster

This unit can be employed in conjunction with any ordinary portable having a ferrite rod aerial, and will provide a considerable increase in range and sensitivity to weak signals. It has two functions – to allow the use of an external aerial and earth, and to amplify and couple signals to the portable receiver.

Tuning coverage is for medium waves. That is, about 200–550 metres, or 1500–550kHz. Many overseas and other stations can be picked up on this band, and distant reception can be particularly common on the higher frequencies, during the hours of darkness.



FIG.33.

Fig. 33 is the circuit, and it uses a cored tuning coil with aerial coupling winding 8–9, tuned winding 6–1, and base coupling coil 5–7. These numbers are for the pins of the Denco (Clacton) "Blue" Range 2 component. It will be apparent that other coils, or surplus or home-wound inductors, can be substituted.

For the coil mentioned, VC1 is 315pF. However, this value is not too critical, provided the capacitor fitted allows tuning the wanted frequencies. A solid dielectric capacitor can be used, though the air spaced type is likely to be a little more efficient.

Coupling to the base is by C1, and resistors R1 and R2 set the base bias conditions, with R3 for emitter bias. These values will suit numerous RF transistors.

Fig. 33B shows assembly of the components on an insulated board. The coil is mounted by its threaded bush. When the board has been wired, it can be mounted by means of bolts with extra nuts. The case is preferably metal, for screening purposes, but the booster can be used satisfactorily with a plastic or similar box.



FIG. 33 B.

Fit a small slide switch to the box front, and aerial and earth sockets to the back, near the coil. A 9v battery is accommodated in the case.

Coupling to the transistor receiver is by means of a loop which is placed on the receiver ferrite rod, or near the rod. The loop can be about twenty turns of thin insulated wire, about ½ inch in diameter, and bound with cotton to keep the turns together The ends can be left long enough to reach the two connecting points in Fig. 33B.

If the case is metal, the booster and receiver can be near each other, so the loop leads will only need to be a few inches long. But when an insulated case is used, coupling from the receiver ferrite aerial or other circuits, to the booster coil, may cause instability. This will become apparent as whistles accompanying most signals. If this arises, the booster and receiver should be moved some inches apart. The aerial lead must not run near the loop connections.

Some receivers have an internal winding which is intended to couple an external aerial, and it may be possible to connect to this, so that a separate coupling loop is not required.

In some cases the earth connection may be omitted, though it can improve range. The aerial can be some 20ft to 40ft or so long. If possible, it should be high and clear of walls and other earthed objects.

If necessary, the coupling afforded by the loop to the receiver aerial circuit can be modified by moving the loop. Initially, tune in signals with the receiver, then adjust VC1 for resonance. This should provide a very considerable increase in the volume of weak signals. A scale can be fitted to the booster, and marked to agree with the receiver tuning by this means. This will allow tuning to be kept in step, and the booster should allow reception of transmissions which will be inaudible if it is removed.

Actual tuning coverage can be modified by adjusting the position of the coil core. This may be helpful in obtaining agreement between booster and receiver tuning. The booster is not required for the reception of powerful signals, and the receiver automatic gain control circuit will tend to mask any increase in signal strength obtained with such transmissions.

Midget MW Diode Radio/Tuner

A small, compact tuner can be of utility in allowing radio reception through an amplifier, and a diode receiver can give excellent quality of reception. Such a unit can also be employed alone, with headphones, for personal listening.

Fig. 34 is a receiver/tuner which can be built in a very small plastic or other insulated box. VC1 is a compression type trimmer, fitted with a small knob for adjustment by hand. To do this, it is necessary to remove the short screw (generally 6ba) and replace this with a longer one, which projects to take the knob. The latter can be a terminal head, or the cap from an empty tube of adhesive, secured with lock nuts.



FIG.34.

For best efficiency and small size, the tuning coil is wound on a piece of ferrite rod. It consists of seventy turns of 24swg or similar enamelled wire, on a rod about 1½ inch long and 3/8 inch in diameter. Actual details will not be critical. A piece can be obtained from a longer rod by cutting a notch round the rod with a file and snapping at this point with the fingers. A few touches of adhesive will hold the ends of the winding secure. The loop for the aerial connection is about one-third the total number of turns from the diode end of the coil. (Moving this tapping towards the earthed end of the coil will increase selectivity or sharpness of tuning, but reduce volume.)

Aerial and earth sockets, and a 3.5mm jack outlet, complete the receiver. Headphones can be plugged directly in here.

The aerial and earth can be provided as explained for the diode radio in Fig. 7.

To use the radio as a tuner, C1, R1 and C2 may be added. Suitable values are C1 470pF, R1 220k, and C2 0.25μF. A screened lead with jack plug should be made up to connect the tuner to the amplifier input socket.

One Transistor VHF Receiver/Converter

The super-regenerative receiver is well known for its great sensitivity, which equals that of a multi-stage superhet. It has no alignment difficulties, and few components, so is an interesting project. Its main disadvantages are its background hiss, but this ceases when a signal is tuned in, and its lack of selectivity. The latter is however relatively unimportant on the VHF bands. The circuit here is particularly intended for 2m reception, but is easily modified. It is not intended for FM signals.

In Fig. 35 the detector is a VHF FET, and the field effect transistor will be found very satisfactory in circuits of this kind. T1 is the pre-set tuning capacitor, which allows adjustment over a fairly wide band of frequencies. Tuning is by VC1, which does not require a reduction drive.



FIG. 35.

Control of super-regeneration is by means of the potentiometer VR1, which adjusts the FET drain potential. The value of VR1 is not very important, but a linear potentiometer is necessary.

C5 provides feedback from source to drain, for regeneration. R3 and the associated components form the quench network, with C6 feeding headphones, or an audio amplifier.

For best results, VR1 should enable the transistor to go smoothly into super-regeneration, which is shown by the hiss mentioned. Achieving this depends somewhat on the transistor, value of C5, adjustment of T1, and aerial loading. However, matters are not too critical.

Transistors unsuitable for VHF cannot be used. Individual FETs of the same type will also differ somewhat, so that in some cases it might be necessary to omit C5, or change the value. Alternatively, a small pre-set (not over 10pF) may be fitted. It will be found that a very small capacitance is required.

Another cause of failing to obtain super-regeneration is too tight aerial coupling, and this is easily corrected by moving the aerial coupling winding a little further from the larger winding.

The RF choke can be a VHF type, or can consist of seventy five turns of 36swg enamelled wire, side by side on a ¼ inch diameter insulated rod. Touches of adhesive may hold the end turns only.

Short leads are essential, and assembly on a tag board is shown in Fig. 35B. The variable capacitor is fitted first, and it can later attach the finished board to a panel, by means of an extra nut.



FIG. 35B.

The larger coil has five turns of 18swg wire, and is ½ inch in diameter and ¾ inch long. The smaller coil has two turns. Wiring to VC1, T1, C5, the coil and C1 must be as short as can be arranged. Connections elsewhere are reasonably direct. A ceramic disc capacitor may be used at C1. T1 should be a low loss trimmer.

The board can be fitted in a case which will carry VR1, and large enough for the battery and on-off switch. The case can be used to support a telescopic aerial, some 30 inch or so when extended.

Frequencies tuned by VC1 can be raised by unscrewing T1, or by stretching the larger coil to separate the turns more, or by using a coil with fewer turns, or of smaller diameter. The receiver is most suitable for use over the 70MHz to 200MHz range.

For the single transistor alone, a sensitive pair of medium or high resistance phones will be needed. Audio ouptut from C6 can be taken to an amplifier, for more powerful reception with phones, or to allow a loudspeaker to be used.

To use the circuit as a converter, tune a portable receiver to around 1500kHz (or as found to give best results, with no break through of unwanted medium wave signals). Place the receiver so that its ferrite aerial is coupled to the RF choke of the converter. When VR1 is correctly adjusted, conversion within the VHF circuit will then allow VHF signals to be heard with the receiver.

Component List

R1	1k	C1	1nF VHF disc
R2	10k	C2	22μF 10v
R3	12k	C3	4.7nF disc
VR1	20k linear pot.	C4	10nF disc
VC1	5pF air-spaced variable	C5	3.3pF VHF type
T1	20pF air spaced trimmer	C5	0.1μF

MPF102/BF244, or other VHF FET
Tagboard, wire for coils and choke, etc.

Morse and Sideband Resolver

Quite a number of inexpensive multi-band transistor receivers have frequency coverage which includes one or more Amateur bands. That is, 1.8, 3.5, 7, 14, 21, or 28MHz. On these bands transmissions are often in Morse code or CW, or single sideband. CW or SSB can be resolved by the specialised Amateur receivers and transceivers, but not with the general purpose home receiver. To receive CW or SSB with the latter type of radio, it is necessary to add an oscillator. This either generates a heterodyne or beat note for code reception, or replaces the carrier which was eliminated from the single sideband transmission.

The circuit in Fig. 36 may be used for these purposes. It generates a carrier of about the same frequency as that used in the intermediate frequency stages of the receiver, exact adjustment of frequency being by VC1,



FIG.36.

Most popular receivers have an intermediate frequency of about 455kHz to 470kHz. The circuit in Fig. 36 uses an intermediate frequency transformer of similar type, and adjustment of its core allows operation with any IF from 455 to 470kHz. Pin numbers are for the Denco (Clacton) IFT13, normally intended for 465kHz. The connections to the base winding (4 and 5) have to be phased to secure oscillation.

R1 and R2 provide base bias, and R3 emitter bias. R4, and the large capacitor C3, allows current to be drawn from the same battery as is used to run the receiver, if wished. Alternatively, a separate 9v battery may be employed here.

Fig. 36B shows the practical layout of components, and wiring to them, using a perforated board. Connections and joints are kept close against the underside of the board. When wiring is finished, the board is mounted in a metal box, using ½ inch bolts with extra nuts for clearance.

VC1 can best have a dial with a central zero mark, this showing when the plates are half meshed.



FIG. 36B.

An insulated lead is run from 2 on the IFT, and is placed near the receiver. This lead may be so positioned as to give best coupling into the IF stages of the receiver. If coupling is too weak, the signal from the CW/SSB Resolver will be inadequate. On the other hand, tight coupling will allow the carrier to swamp weak signals tuned in on the receiver. Fortunately the degree of coupling is not at all critical.

To set up the oscillator, first of all tune in any normal broadcast with the receiver. Set VC1 half closed and switch on. The core of the IFT should now be slowly adjusted until a loud heterodyne or beat note is heard accompanying the signal received. Set the core so that this note falls to about zero, or to a low pitch. It will then be possible to rotate VC1 either way from this central zero beat position, in each case producing a note which rises in frequency as VC1 is rotated.

To receive CW or Morse code, it is only necessary to tune in the code signal with the receiver, and then to adjust VC1 to obtain a note of the most suitable pitch. VC1 can be rotated either way from its central or zero beat position, to obtain best freedom from interference.

When receiving SSB, a more critical adjustment of VC1 is needed and the carrier produced must be at the right side of the SSB signal. (One side is used for the low frequency bands, and the other for the higher frequency bands.) If the carrier is the wrong side, the speech will be "inverted" or unintelligible. With careful adjustment of VC1, a setting will be found where the sideband signal is correctly resolved.

Easy Preamplifier

This amplifier can be placed in circuit before a larger amplifier, to boost the input, or it may be used alone with headphones.

A preamplifier will be added to existing equipment when a pickup or microphone having only a low output has been found to give insufficient volume. An amplifier may be able to provide a signal at a sufficiently high level. But with low input levels, output can be inadequate.

The stage in Fig. 37 can provide considerable gain. Audio input is to C1, and R1 provides base current for the transistor. Amplified signals are obtained across R2, and pass to the main amplifier (or phones) via the isolating capacitor C2.



FIG. 37.

With a BC108 or similar transistor, the supply can be about 9v to 15v. Numerous NPN transistors, intended for preamplifier use and of low noise type, will perform well. Current may be from a separate battery. Or it may in many cases be drawn from the main amplifier. To avoid instability or similar troubles, the positive supply should be from a well decoupled and smoothed point in the main amplifier. If this is not available, connect a 220µF capacitor from positive to negative in Fig. 37, and draw the positive supply through a 1k resistor. Negative is returned to the negative line of the main amplifier.

Should the main amplifier have a positive earth line, then the transistor can be a PNP type, R1 and R2 being changed to suit.

Fig. 37B shows assembly on a perforated board. When the circuit provides input to a main amplifier, it should generally be in a metal case. Input is by a screened lead, and a screened lead is also fitted for the audio circuit to the main amplifier. The case should be earthed to the negative line. This can be by means of one of the bolts securing the board.

Screening to avoid hum or instability will generally prove to be unnecessary when using the stage to operate headphones. So two sockets, or a jack socket, will be more convenient for the phone circuit.



FIG.37B.

741 Preamplifier

Integrated circuits have several stages of amplification, formed as a single chip and enclosed in a small case. The 741 is an easily obtained audio IC which can be used in many circuits. The uA741CE or metal can 741 is convenient, as its leads may be spaced to suit any ready perforated board. The dual in line 741 is electrically similar.

Fig. 38 shows a preamplifier using the metal can 741. Input is via C1 to 3. As shown, 7 and 4 are positive and negative, while output is from 6. Negative feedback is applied to 2, via R4. C3 is an isolating capacitor.



FIG.38.

Modification to the values of R3 or R4 allow feedback and gain to be adjusted between quite wide limits, but for general purposes the values shown are satisfactory. A wide range of voltages (not exceeding 36v) may be used. The actual output is from a complementary pair, and is easily adequate for very good headphone volume, if required.

Fig. 38B shows assembly of the integrated circuit amplifier on a perforated board. For phone working, input and output need not be screened. But for preamplifier use before a main amplifier, these circuits need to be made by means of screened leads.



FIG.38B.

Lead 8 is identified as in Fig. 38. The wires are spread out slightly, to fit the board perforations. After inserting components as shown, turn the board over. Bend and solder the wires, cutting off excess length. Sleeving can be put on any connections which run very near other leads or soldered joints.

If the preamplifier is to be used as a separate unit, input and output leads may be run to jack sockets, or sockets to suit other items of equipment. A metal case is advised, as this will help to avoid any pick up of hum, or other troubles due to coupling to the board wiring. The board can be secured to the metal box or case with ½ inch 6ba bolts, and extra nuts to give a little clearance.

The amplifier may be run from its own battery; or from a supply used with a main amplifier. For the latter, it is wise to provide a decoupled point, in a similar manner to that described for the transistor preamplifier. This consists of a quite large capacitor (say 220μF to 470μF) from positive to negative across the preamplifier supply circuit, and a resistor of 1k to 2.2k or so from preamplifier positive to positive on the main amplifier.

Tone Control for Your Discs Etc.

The preamplifiers shown have a substantially flat response. That is, they do not purposely emphasize bass or treble, or have similar effects in modifying the audio frequencies present. In some circumstances it is necessary to boost treble or bass, or reduce the emphasis of these frequencies, in order to obtain the most satisfactory reproduction.

This may be achieved by making a fully adjustable tone control, and Fig. 39 is a suitable circuit. A volume control is also incorporated, as this has not been present in the preamplifiers.



FIG.39.

The tone control is a passive circuit, needing no battery, and it can be placed between the source of audio signals (generally a microphone, pick-up, or radio tuner) and the amplifier or preamplifier. It may also be located between preamplifier and main amplifier, if wished.

Results are substantially flat with the treble control VR1 and base control VR2 in their central positions. Adjustment of VR1 and VR2 will provide separate boost or cut of treble, or boost or cut of bass frequencies. VR3 is the volume control.

The degree of control afforded by circuits of this type may be adjusted by alterations to the component values. In practice, it will be found that there is little point in having extreme levels of adjustment, which will never be required. The following values may be used: C1 and C2, 270pF; R1, 390k; R2 and R3, 100k; C3 680pF; VR1 and VR2, 2 megohm linear potentiometers; VR3, 2 megohm log potentiometer.

Components should be assembled in a metal case, for screening. The case is grounded to the earth line. Input and output sockets can be near the ends of the case, with VR1, VR2 and VR3 between. Components can be soldered directly to the potentiometer tags.

Two Channel Mixer

A mixer will permit fading in and out of two signals, such as these from tape and microphone, or radio and disc, and can be of considerable utility for home entertainment. The mixer in Fig. 40 takes two inputs, and also provides additional amplification, which will often be useful where input levels are not very high.

FIG. 40.



Input A has its individual volume control VR1, and Input B is similarly provided with VR2. Resistors R1 and R2 prevent short circuiting one input when the other potentiometer is set at zero. Coupling to the transistor base is by C1. R3 and R4 set base bias conditions, with R5 as the collector load and audio output from C2.

Component values are not very critical, though R3, R4 and R5 need to be selected to suit the transistor fitted. The mixer is connected and used in a similar way to that explained for the preamplifiers.

FIG. 40 B.



Fig. 40B is the layout, using a metal case or box. A screened output lead is provided. Input sockets A and B may be chosen to suit the type of plugs on existing equipment. The on-off switch is separate from the potentiometers, so that these can be left at pre-set levels if wished.

Component values may be chosen to suit low or high impedance inputs, if wished. Or the following may be used for general purposes:

Components List:

VR1, VR2, 1 megohm log potentiometers.
R1, R2, 200k
C1 0.5μF C2 0.5μF
R3 330k BC109
R4 22k
R5 10k

This is when using a 9v supply.

¼ Watt IC Amplifier

An integrated circuit which combines driver and push-pull output stages is used in Fig. 41. The IC is the MFC400B and is intended for operation from a 9v battery supply, and delivers up to about 250 milliwatts into a 16 ohm speaker. This will be found ideal for many projects, and for loudspeaker reception.



FIG. 41.

Audio input is to 2 of the IC, from the isolating capacitor C1. C2 is a by-pass capacitor to maintain stability. The IC has only four connections, 1 going to the negative line, and 3 to the positive supply. Audio output is from 4, and to the loudspeaker via C3. R1 provides negative feedback and bias to point 2.

The assembly of this amplifier on 0.15 inch matrix board is shown in Fig. 41B. Pin numbering is when looking at the top of the IC and the component side of the board.



FIG.41B.

A screened input circuit will be found necessary when the IC amplifier is used with a preamplifier or similar items. Connect the outer brading of this lead to the negative line, and the inner conductor to C1. Such screening is not necessary with very short connections from other stages to the IC amplifier, or when using it to amplify a crystal diode radio, or for similar purposes.

The on-off switch can be in either the positive or negative battery lead. The IC will be found to give a good performance with speakers of a higher impedance than that shown, and up to 75 ohm may be used (with some small loss in output). Units of lower impedance than 16 ohms should not be fitted.

The small size of this IC and the few extra components needed make is very suitable for miniature apparatus, probably with a 2½ inch speaker. It will also operate a large speaker well (see "Boost Speaker") and at a volume level adequate for many purposes.

Class A Amplifier

A Class A amplifier uses a single transistor, Fig. 42, which must thus operate over the whole audio cycle. As a result, the resting or no-signal current has to be fairly high, if other than a very low power output is to be obtained. An amplifier of this kind is thus most usual in circumstances where a fairly large current will be available. That is, with accumulator operated equipment (e.g., a car radio) or mains operated amplifiers. It can also be used for other purposes where operation is more or less on an intermittent basis (as in a Loud Hailer), or for somewhat lower power where simplicity is important.

The circuit in Fig. 42 can be used with any NPN transistor, or with PNP transistors if polarity is reversed. Small transistors of the 300mW and similar type will provide rather modest loudspeaker volume. Larger transistors, with a dissipation of 500mW to 1W or so, will be able to give reasonable power, and can often be useful here. The very large power transistor, such as that shown, will run at a much higher current level, and deliver several watts output.



FIG. 42.

T1 is the coupling or driver transformer, which may receive audio signals from a radio receiver, smaller amplifier, or other equipment. A step down ratio of about 5:1 to 10:1 will generally prove to be suitable.

For smaller Class A amplifiers, T1 may be omitted. R1 and VR1 may then be of about 1k, and the audio signal can be coupled to the transistor base by means of a fixed capacitor, as in earlier circuits.

T2 is the output or speaker transformer. This can be omitted when the speaker is of suitable impedance, and is able to carry the required collector current. This means that a 75 ohm or similar unit can be connected directly in the collector circuit, with low power transistors. If a 2/3 ohm speaker is used, then T2 is required with these for impedance matching.

With the large type of transistor, current may be 500mA to 1A or so, and this means that the usual speaker cannot be connected directly in circuit. Instead, a transformer or tapped choke will be needed.

The circuit is often operated from 12v (a vehicle supply) but can be used with 9v, or more than 12v.

R1 and VR1 set bias conditions, and R2 limits peak collector current. For the 2N3055, R2 may be 1 ohm. R1 can be 100 ohm, and VR1 25 ohm. T2 can be 2:1 for a 3.5 ohm speaker. C1 is 3200μF. Begin with VR1 at minimum value, slowly increasing this until reproduction is satisfactory. (This will set collector current at about ½ ampere.)

With other transistors, adjustment can be made in the same way, by slowly increasing the base bias until best results are secured. Raising the value of VR1 in Fig. 42, or reducing the value of R1, will increase collector current, and thus raise the power which can be handled. However, current is limited by the power handling capacity of the transistor, so a meter should be put in one battery lead, and a check made that the power dissipation of the transistor is not exceeded. With small transistors, current can be limited to 50mA or so.

Fig. 42B shows assembly of the circuit in Fig. 42. The power transistor is mounted on an aluminium plate, which acts as a heat sink to carry away heat from the transistor itself. Note that this plate is common to the collector. Base and Emitter pins pass through clearance holes. Smooth off any burr round the fixing and clearance holes, so that the transistor can rest flat on the metal. Where it is awkward to have the plate or case common to the collector, the usual insulation set can be fitted. This consists of bushes for the fixing bolts, and a thin mica washer to go under the transistor, so that electrical isolation is obtained.



FIG. 42 B.

The insulated board carrying the other components is mounted by long bolts with extra nuts. A large Class A stage transistor of this type will grow very warm to the touch, if run at anything like maximum power rating. This does not indicate any defect.

Two Stage Amplifier

The circuit of a 2-stage amplifier is shown in Fig. 43, and this can be used for loudspeaker reproduction. Input to the driver stage is by the isolating capacitor C1. Operating conditions in this stage depend largely on the values of R2, R3, and the emitter bias resistor R5.



FIG. 43.

T1 is the driver transformer, with centre tapped secondary, so that TR2/3 may be operated in push-pull (see Fig. 12). T2 couples output to a 2/3 ohm speaker.

With the values shown, a BC109 will give very good results in the TR1 position, with 2 x BC108s for the output stage. R7 is set so that battery current is around 10mA, with no signal present. Current rises from 20mA to 60mA or so, according to volume, when the amplifier is driven.

A pair of 2N1306 transistors may be used for the output stage. Other transistors are also possible here, as operating conditions can be adjusted by R7.

The 2N3706 will operate in the TR1 position, though with lower gain than the BC109. Numerous other small audio transistors can also be used here.

For full volume, a fairly strong input is required to TR1. It will thus be necessary to use a preamplifier, for low level signals.

Components List:

R1 3.3k
R2 47k
R3 15k
R4 1k
R5 680 ohm
R6 2.7k
R7 500 ohm pre-set
R8 4.7 ohm

C1 0.5μF
C2 100μF
C3 100μF
C4 4.7nF
C5 470μF

SECTION 4
POWER SUPPLIES

Mains power supplies are convenient for equipment which will receive long periods of use, and for items where the current needed is too heavy for economical running from batteries.

Such supplies should be operated from a 3-pin plug, fitted with a low rating fuse. Connect L, N and Earth correctly, both at the plug and at the equipment.

Those circuits where mains voltages are present must be so arranged that no shocks can be experienced. Mains voltage circuits include any means of anchoring the mains conductors in the equipment, the main on-off switch (if used), and primary connections of the mains transformer. Enclosing the whole equipment in an insulated or metal case will avoid accidental contact with such circuits or with the tags of switches or transformer. If the case is metal, earth it by the mains earth conductor.

Provided the secondary or low voltage circuit is correctly earthed, there is normally no danger from handling these connections, or equipment operated from the supply.

Easy PSU

A useful power supply suitable for many purposes can use the circuit in Fig. 44. Mains L (live) and N (neutral) conductors go to the primary P of the transforer. A switch is placed in the L circuit.

The secondary S can delivery any wanted low voltage, and also give isolation from the mains.

Almost all equipment will need direct current. The four separate rectifiers, or an equivalent single device, produce pulsating DC. The reservoir capacitor C1 smoothes this. Resistor R1, with the second capacitor C2, gives additional smoothing. Output from the supply is then substantially smooth DC, as would be obtained from a battery.



FIG. 44.

Sometimes R1 and C2 are omitted. Should hum accompany reproduction from an amplifier, this shows that smoothing is probably inadequate, and if so the cure is to add R1 and C2.

Any wanted voltage can be obtained by using a transformer with an appropriate secondary, with rectifiers and capacitors to suit.

C1 may charge up to approximately 1.4 times the RMS or usual voltage rating of the secondary S. Thus, if S were a 6.3v winding, about 8.8v would be expected across C1. But should R1 be present, a voltage drop will arise in it, the figure depending on the resistance value of R1, and current flowing.

For these reasons, the actual output may not be exactly the figure expected. This will often be unimportant, and such power supplies are largely used for all sorts of equipment.

For apparatus generally operated from a 9v or similar battery, a bell transformer with 3v, 5v and 8v output tappings is suitable. If R1 is 22 ohm, this will give around 9v at 100mA, with the 8v tap in use.

It is convenient to use 50v or 100v rectifiers, and the rating can be 1 ampere, with a 1 ampere transformer secondary. Four individual wire ended rectifiers can be mounted on a tag strip, and connected as in Fig. 44. A combined rectifier will have AC, positive, and negative tags (see Fig. 45) and can be fitted instead.

The capacitors need to be of large value, and have a voltage rating higher than the actual voltage which will be present. The 12v capacitors could be fitted in the circuit described. C1 can be 2500μF or larger, and C2 can be of similar value.

Easy Regulated PSU

With the circuit in Fig. 44, the exact voltage will depend on the current drawn, rising when current is low. To avoid this, some means of regulation may be employed.



FIG. 45.

Fig. 45 shows a typical regulation circuit, giving an output of approximately 9.4v. The output from the rectifier needs to be of somewhat higher voltage than required at the output, and a transformer with a 10v secondary is suitable. Current through R1 supplies the Zener diode, which holds the base of the transistor at virtually the same voltage for all current loads. Some voltage is lost in the transistor, so the output is nearly the same, for any current load. For up to about 200mA, a BFY51 or equivalent transistor is adequate, so this will do well for many purposes.

Multi-Voltage Regulated PSU

Fig. 46 is a somewhat similar circuit, but it has a switch, to select any one of the four Zener diodes. These may be chosen so that 6v, 9v, 12v and 15v will be available.



FIG. 46.

R1 supplies current for any diode, and 1 watt diodes should be used. With a 24v transformer and large transistor such as the 2N1970 or 0C29, an output of up to 1 ampere can then be drawn. The bridge rectifier must of course be rated at 1A or higher.

Note that this circuit has a PNP control transistor, so that polarity is obtained as shown. (Compare with the NPN transistor in the previous circuit.) However, either positive or negative can be grounded, and a separate earth terminal can be provided to allow this. A flying lead is placed between earth terminal and positive, or earth and negative, as required. The permanent negative earth connection shown in Fig. 45 must of course then be omitted.

More details of actual construction will be found later.

One Transistor Adjustable PSU

Fig. 47 is the circuit of a simple power supply unit which can be set to provide any output from zero to 12 volts. The transformer has a 17v secondary, rated at 1 ampere or higher. After rectification, DC is obtained from the reservoir capacitor C1.



FIG. 47.

VR1 is panel mounted, and allows the base potential of the control transistor to be set at the required voltage. C2 provides “electronic smoothing” from the base circuit.

The 12 volt 15 watt bulb is for short circuit protection. With relatively low currents, little voltage is lost here. But if a short circuit arises in the output circuit, current is limited to a little over 1A by the bulb. This reduces the chances of any damage due to temporary shorts in leads or equipment.

R1 is a bleeder resistor, drawing some current even when no external load is connected. The meter is the usual high resistance type, scaled from zero to 12v. VR1 is adjusted until this instrument shows the wanted voltage.

The regulation of this supply is not so good as that of supplies using a number of transistors. But it will be found suitable for all ordinary purposes, and to supply power for circuits in this book, as only a small change in voltage arises, with changes to the load, or current drawn.

Fig. 47B shows practical construction of this PSU. A similar layout can be adopted for the other power supply units.

The mains cord is anchored at a tag strip, and connections are made as described earlier. The mains switch is in the L conductor to the 240v winding, or primary, of the transformer.

A tag strip supports the rectifier, which has AC (~), positive and negative connected as shown. The lamp can be a vehicle type, supported by stout wires soldered to its base contacts, or side and tip. A hole is drilled in the panel level with this lamp, so that it will give indications of a short circuit or heavy load.

The transistor is mounted on the metal panel, to enable this to carry away heat, but is insulated from the metal. Use the correct insulation set (mica washer and bushes) which can generally be obtained with the transistor. A tag under one of the securing nuts provides the collector connection.

For voltage readings, a meter scaled 0–12v is most suitable. Or a 1mA meter, with 12k 1% series resistor, may be used. If so, a new scale, marked 0–12, can be drawn for it.

A 3 watt linear potentiometer is used. Earth and negative are connected to the metal panel, for equipment with a negative ground line. The positive output terminal or socket is insulated from the metal.

The case can be metal, or wood. It should have a few ventilation holes. The transistor can be expected to run quite warm, at maximum current. Heating here rises as the output voltage is reduced by VR1, as in these circumstances more voltage is dropped in the transistor.



FIG. 47B.

Zener Regulated Supply

Zener diodes alone may be used to provide a regulated supply. This can be convenient, as example, when operating 9v equipment from a car accumulator, where the voltage will vary somewhat during charging.

Fig. 48 shows two supplies regulated by a Zener diode only. With the first circuit, R1 and the negative line are taken to the supply, and the regulated output is obtained across the Zener in the polarity shown.



FIG. 48.

The second circuit is virtually the same, but polarity is reversed, so that the ground return is positive.

These circuits can be prepared for a wide range of voltages, by taking into account the Zener voltage and wattage, and thus the voltage to be dropped in R1 and R2.

For calculations, remember the following:
Voltage = Current in Amperes x Resistance in Ohms.
Current = Voltage divided by Resistance.
Resistance = Voltage divided by Current.

The units employed are ohms, amperes, and volts. Wattage may be found from Voltage x Current.

Select R1 or R2 so that the wattage rating of the Zener is not exceeded, with the smallest current ever to be drawn by the load. As example, suppose a 7.5v output is wanted, so that a 1½w 7.5v Zener is fitted. Approximately 200mA may thus flow through the Zener, if no current is taken by the load. Suppose the supply is up to 15v. It will be necessary to drop or waste 7.5v in R1 or R2. So a 42 ohm resistor may be fitted, with a little safety latitude. Any current from zero to about 150mA may then be drawn, without any important change in voltage.

Where a Zener diode would have to be of very large wattage, it may be more convenient to use the Zener to control the base potential of a transistor, as also shown for negative and positive earths in Fig. 48. (See also Fig. 45.) R3 or R4 then only need provide a relatively low current for the Zener and transistor base.

Motor PSU with Reverse

Fig. 49 is the circuit of a supply for model motors, and giving both speed control and reversing.



FIG.49.

A transformer with a 12v secondary will be suitable for the usual model requiring up to 12v. The circuit is similar to that of the supply in Fig. 47. The potentiometer VR1 gives speed control. C1 can be around 2,000μF.

"A" is one type of ready-made switch, and it can be obtained with a central off position. "B" shows a home-built switch, similar to that described in Fig. 5. The switch must not short circuit the supply when changing over polarity, and one with central off is recommended.

Motors reversed in this way must be of the permanent magnet type, in which a change of polarity causes the armature to run in the opposite direction. Train and many other model motors are of this construction. Motors with a wound field will not be reversed by changing the polarity of supply.

A controller of this kind should be constructed as shown earlier, so that it is safe to use, and so that no joints in the mains circuits can be touched.

Earthing can only be omitted when a double-insulated transformer, of the type specifically made to avoid any need for earthing, has been used. The whole controller should be so constructed that, even if a fault develops, mains voltages cannot reach the secondary circuit or model.

Wrong Polarity Protector

There is sometimes a danger that transistorised equipment may be connected to a vehicle or other supply in the wrong polarity. This will usually cause damage, and may destroy the semiconductor devices, or electrolytic capacitors.

Adding a diode to the circuit as in Fig. 50 will avoid this. For most small equipment, a silicon 100v 1A rectifier will be ideal. With the supply connected correctly, current passes with virtually no loss of voltage. But if the supply polarity is reversed, the diode does not conduct, so no harm is caused to the equipment. Such a diode is readily incorporated in almost any item which may from time to time be run from an external accumulator or dry battery supply where the polarity is not known.



FIG. 50.

Component Tolerances

For circuits in this book, exact component values are generally not too important. Capacitor values such as 47nF (0.047μF) and 0.05μF may be regarded as interchangeable. In the same way, a 125μF capacitor may replace 100μF, or 200μF can be used instead of 220μF, and so on.

Resistors will generally be the standard 5% tolerance types. In some circuits exact resistor values are not at all critical. In others, and especially base, emitter and collector circuits, the values which provide best results can have much less latitude.

Bases

The lead-out positions of base, emitter and collector wires have been shown for typical transistors. However, it is felt that Fig. 51 should be useful. This gives lead information for types most likely to be required for circuits in this book. Other types of transistors may of course be used successfully, but it is not practical to list all these, or show connections for them all.


C +
B
E
NPN
C –
B
E
PNP
2N706
E
B
C
BC107/8/9
NPN
BFY51
E
B
C
B
E
C
AC128
AC124
PNP
2N3704
2N3707
B C E
NPN
FET
2N5459
MPF102
G S D
UJT
E
B1
B2
2N2646
UJT
B1
E
B2
TIS43
OC29 PNP
B
E
C
NPN 2N3055

FIG. 51.

EQUIVALENT SEMICONDUCTORS

To help our overseas readers the following list of possible equivalents is shown below: –

AC128	CV9778, OC74–318, NKT281, 2N467, 2SB222–415, AC117–124–153, GET110, NKT302, SFT232, 2N659–1373–1384–1926–2001–2431–4106, 2SB370, SK3004, RS276–2005.
ACY39	CV9475, NKT243, ACZ10, 2N652–2303–2801.
AF117	2N642, 2SA155, AF102–105–127–133–137, BFX48, BSW19–73, GM1213B, NKT603F, SFT354, SK3006, 2N2273–2635–3324–4916–5354, RS276–2003.
BC107	CV9780, AM251, BC147–167–207–317, MPS6566, SK3020–3122, ZTX107, TT107, RS276–2009.
BC108	CV10541, AM252, BC148–168–208–318, MPS6520, SK3020, ZTX108, TT108, RS276–2009.
BC109	CV10769–10806, AM253, BC149–169–209–319, MPS6521, SK3020, ZTX109, TT109, RS276–2009.
BC147	BC171–182/L–207–317, MPS6566, SK3020, RS276–2013,
BC148	BC172–183/L–208–318, MPS6520, SK3020, BS276–2009.
BC149	BC184/L–209–173–319, MPS6521, SK3020, RS276–2009.
BF200	BF162–173–225–271–311–314, SE5020/1/2/3/4, SK3018, 2N616–2708–3288–3693, RS276–2011.
BFY51	CV7723–7726–10827–11238, BFX51–68A, BFR19, BSX45/X, BSY46–85, SK3024, 40347, 2SC708, ME6102 2N2193/4–2218–2410–3053–3252–4046, RS276–2009.
BSY95A	CV7648–9379, BC108A, BSX51–73–91, BFX96, BSY20–58–62, ME9022, SK3122, 2SC321, 2N744–914–1708–2218–2369–5187, RS276–2011.
MPF102	E305, SK3116.
OA81	AA117–118–132–144, AAZ15, OA91–95–161, SD38, 1N38–56–476–618, 1S33.
OC26	CV8560, NKT452, 2N257–297–458–553–1021, 2SB3, AD130–131–138–140–149, OC28, SK3009, TF80, T1156–3027, 2N174–1073–2870–RS276–2006.

OC29	CV7083–8356, NKT402, 2N457, 2SB86–425, AD150, ASZ16, AUY21, OC28–35–36, SK3009, T13028, 2N174–1073–2870, RS276–2006.
OC44	CV5710–7003, OC170–171–410–613, 2N1303, 2SA15, AF101–117–126, ASY55, AC191, BC126, NKT211, SKT358, SK3005, 2N36–1191/2–1352–1373–1384, RS276–2003.
OC70	CV5457, OC303–602, NKT214, 2N279–1305, 2SB75, AC122–125–151–163, ACY27–34, ASY27, BC213–206A, BSX36, SK3003, 2N1193–1352–1375–2429, RS276–2004.
OC71	CV5712–7005–8344, OC70–304–604, NKT214, 2N280–1305, 2SB77, AC122–125–151–163, ACY35, BSX36, OC3041, SK3003, 2N1193–1352–1375–1384–2429, RS276–2004.
OC72	AC122/3–125/6–131–151 IV–152–162–191, BC126–213–206A, NKT211, SFT353, 2N282–1190–1352–1371–1384–1991–2431, CV5713–7006–8440, RS276–2005.
OC76	CV8314, OC307–6025, 2N284–1305, NKT212, 2SB89, AC128–131–151–152, ACY28, ASY58–76, BC126–213–260A, SK3004, 2N394–1191–1352–1371–1384–1991, RS276–2004.
ORP12	RS276–116, LDR03, RPY25.
1N4001	BY127, EM502, RS276–1101/1135, 1S100.
1N4002	BY127, EM502, RS276–1102/1136, 1S100.
2N1306	CV7350–10686, NKT736, 2N634–635–636–1891–1993–1994–1995, ASY26–29, BSX19–20, RS276–2001.
2N1613	CV7440–8843, BFY33–34–67, BSY44, 2N698–699–717–1711–1889–1890–1893, BFY41, BSX45/6, BSY53, MPS6530, 2SC708, 2N2101.

N.B.: Although equivalent semiconductors may have similar electrical properties, physical dimensions may be different and this must be born in mind if space is tight and for mounting details.
Remember polarities if replacing PNP with NPN types and vice versa. If in doubt always be advised by your dealer for suitable equivalent semiconductors.

Notes

Please note overleaf is a list of other titles that are available in our range of Radio and Electronic Books.

These should be available from most good Booksellers, Radio Component Dealers and Mail Order Companies.

However, should you experience difficulty in obtaining any title in your area, then please write directly to the publishers enclosing payment to cover the cost of the book plus adequate postage.

If you would like a copy of our latest catalogue of Radio & Electronics Books then please send a Stamped Addressed Envelope.

BERNARD BABANI (publishing) LTD
The Grampians
Shepherds Bush Road
London W6 7NF
England

160	Coil Design and Construction Manual	£1.95
202	Handbook of Integrated Circuits (IC's) Equivalents & Substitutes	£1.95
205	First Book of Hi-Fi Loudspeaker Enclosures	£0.95
208	Practical Stereo and Quadrophony Handbook	£0.75
214	Audio Enthusiasts Handbook	£0.85
219	Solid State Novelty Projects	£0.85
220	Build Your Own Solid State Hi-Fi and Audio Accessories	£0.85
221	28 Tested Transistor Projects	£1.25
222	Solid State Short Wave Receivers for Beginners	£1.95
223	50 Projects Using IC CA3130	£1.25
224	50 CMOS IC Projects	£1.35
225	A Practical Introduction to Digital IC's	£1.75
226	How to Build Advanced Short Wave Receivers	£1.95
227	Beginners Guide to Building Electronic Projects	£1.95
228	Essential Theory for the Electronics Hobbyist	£1.95
RCC	Resistor Colour Code Disc	£0.20
BP1	First Book of Transistor Equivalents and Substitutes	£1.50
BP2	Handbook of Radio, TV, Ind & Transmitting Tube & Valve Equivalents	£0.60
BP6	Engineers and Machinists Reference Tables	£0.75
BP7	Radio and Electronic Colour Codes and Data Chart	£0.40
BP14	Second Book of Transistor Equivalents & Substitutes	£1.75
BP24	52 Projects Using IC741	£1.75
BP27	Chart of Radio, Electronic, Semi-conductor and Logic Symbols	£0.50
BP28	Resistor Selection Handbook	£0.60
BP29	Major Solid State Audio Hi-Fi Construction Projects	£0.85
BP32	How to Build Your Own Metal and Treasure Locators	£1.95
BP33	Electronic Calculator Users Handbook	£1.50
BP34	Practical Repair and Renovation of Colour TVs	£1.95
BP36	50 Circuits Using Germanium, Silicon and Zener Diodes	£1.50
BP37	50 Projects Using Relays, SCR's and TRIACS	£1.95
BP39	50 (FET) Field Effect Transistor Projects	£1.75
BP42	50 Simple L.E.D. Circuits	£1.50
BP43	How to Make Walkie-Talkies	£1.95
BP44	IC 555 Projects	£1.95
BP45	Projects in Opto-Electronics	£1.95
BP47	Mobile Discotheque Handbook	£1.35
BP48	Electronic Projects for Beginners	£1.95
BP49	Popular Electronic Projects	£1.95
BP50	IC LM3900 Projects	£1.35
BP51	Electronic Music and Creative Tape Recording	£1.95
BP52	Long Distance Television Reception (TV-DX) for the Enthusiast	£1.95
BP53	Practical Electronics Calculations and Formulae	£2.95
BP54	Your Electronic Calculator and Your Money	£1.35
BP55	Radio Stations Guide	£1.75
BP56	Electronic Security Devices	£1.95
BP57	How to Build Your Own Solid State Oscilloscope	£1.95
BP58	50 Circuits Using 7400 Series IC's	£1.75
BP59	Second Book of CMOS IC Projects	£1.95
BP60	Practical Construction of Pre-amps, Tone Controls, Filters & Attenuators	£1.95
BP61	Beginners Guide To Digital Techniques	£0.95
BP62	Elements of Electronics – Book 1	£2.95
BP63	Elements of Electronics – Book 2	£2.25
BP64	Elements of Electronics – Book 3	£2.25
BP65	Single IC Projects	£1.50
BP66	Beginners Guide to Microprocessors and Computing	£1.95
BP67	Counter, Driver and Numeral Display Projects	£1.75
BP68	Choosing and Using Your Hi-Fi	£1.65
BP69	Electronic Games	£1.75
BP70	Transistor Radio Fault-Finding Chart	£0.50
BP71	Electronic Household Projects	£1.75
BP72	A Microprocessor Primer	£1.75
BP73	Remote Control Projects	£1.95
BP74	Electronic Music Projects	£1.75
BP75	Electronic Test Equipment Construction	£1.75
BP76	Power Supply Projects	£1.95
BP77	Elements of Electronics – Book 4	£2.95

BP78	Practical Computer Experiments	£1.75
BP79	Radio Control for Beginners	£1.75
BP80	Popular Electronic Circuits – Book 1	£1.95
BP81	Electronic Synthesiser Projects	£1.75
BP82	Electronic Projects Using Solar Cells	£1.95
BP83	VMOS Projects	£1.95
BP84	Digital IC Projects	£1.95
BP85	International Transistor Equivalents Guide	£2.95
BP86	An Introduction to BASIC Programming Techniques	£1.95
BP87	Simple L.E.D. Circuits – Book 2	£1.35
BP88	How to Use Op-Amps	£2.25
BP89	Elements of Electronics – Book 5	£2.95
BP90	Audio Projects	£1.95
BP91	An Introduction to Radio DXing	£1.95
BP92	Easy Electronics – Crystal Set Construction	£1.75
BP93	Electronic Timer Projects	£1.95
BP94	Electronic Projects for Cars and Boats	£1.95
BP95	Model Railway Projects	£1.95
BP96	C B Projects	£1.95
BP97	IC Projects for Beginners	£1.95
BP98	Popular Electronic Circuits – Book 2	£2.25
BP99	Mini-Matrix Board Projects	£1.95
BP100	An Introduction to Video	£1.95
BP101	How to Identify Unmarked IC's	£0.65
BP102	The 6809 Companion	£1.95
BP103	Multi-Circuit Board Projects	£1.95
BP104	Electronic Science Projects	£2.25
BP105	Aerial Projects	£1.95
BP106	Modern Op-Amp Projects	£1.95
BP107	30 Solderless Breadboard Projects – Book 1	£2.25
BP108	International Diode Equivalents Guide	£2.25
BP109	The Art of Programming the 1K ZX81	£1.95
BP110	How to Get Your Electronic Projects Working	£1.95
BP111	Elements of Electronics – Book 6	£3.50
BP112	A Z-80 Workshop Manual	£2.75
BP113	30 Solderless Breadboard Projects – Book 2	£2.25
BP114	The Art of Programming the 16K ZX81	£2.50
BP115	The Pre-Computer Book	£1.95
BP116	Electronic Toys Games & Puzzles	£2.25
BP117	Practical Electronic Building Blocks – Book 1	£1.95
BP118	Practical Electronic Building Blocks – Book 2	£1.95
BP119	The Art of Programming the ZX Spectrum	£2.50
BP120	Audio Amplifier Fault-Finding Chart	£0.65
BP121	How to Design and Make your Own P.C.B.s	£1.95
BP122	Audio Amplifier Construction	£2.25
BP123	A Practical Introduction to Microprocessors	£2.25
BP124	Easy Add-on Projects for Spectrum ZX81 & Ace	£2.75
BP125	25 Simple Amateur Band Aerials	£1.95
BP126	BASIC & PASCAL in Parallel	£1.50
BP127	How to Design Electronic Projects	£2.25
BP128	20 Programs for the ZX Spectrum & 16K ZX81	£1.95
BP129	An Introduction to Programming the ORIC-1	£1.95
BP130	Micro Interfacing Circuits – Book 1	£2.25
BP131	Micro Interfacing Circuits – Book 2	£2.25
BP132	25 Simple Shortwave Broadcast Band Aerials	£1.95
BP133	An Introduction to Programming the Dragon 32	£1.95
BP134	Easy Add-on Projects for Commodore 64 & Vic-20	£2.50
BP135	The Secrets of the Commodore 64	£2.50
BP136	25 Simple Indoor and Window Aerials	£1.95
BP137	BASIC & FORTRAN in Parallel	£1.95
BP138	BASIC & FORTH in Parallel	£1.95
BP139	An Introduction to Programming the BBC Model B Micro	£2.50
BP140	Digital IC Equivalents and Pin Connections	£3.95
BP141	Linear IC Equivalents and Pin Connections	£3.95
BP142	An Introduction to Programming the Acorn Electron	£1.95
BP143	An Introduction to Programming the Atari 600XL and 800XL	£2.50
BP144	Further Practical Electronics Calculations and Formulae	£3.75
BP145	25 Simple Tropical and M.W. Band Aerials	£1.95

BERNARD BABANI BP48

Electronic Projects for Beginners

- In this book the newcomer to electronics will find a wide range of easily made projects, many complete with actual component and wiring layouts. Furthermore, a number of projects have been arranged so that they can be constructed without any need for soldering and, thus, avoid the need for a soldering iron.

- This book which is written by the very experienced author Mr. F.G. Rayer is divided into four sections:–
  1. "No Soldering" Projects
  2. Miscellaneous Devices
  3. Radio and Audio Frequency
  4. Power Supplies

- An absolute 'must' for all beginners in electronics.

ISBN 0-85934-054-6
00195
£1.95
9 780859 340540

frequency, in *Hertz* (named after a German physicist and abbreviated to Hz).

Often in electronic engineering we need to draw a *graph* or picture of such a vibration and we can imagine this being done as in Fig.1(i) for the pendulum. With an inked brush fixed as shown and with the paper moving, a wavy line is drawn and if for example the paper moves at 1 centimetre (cm) each second and the pendulum swings at 1 Hz (that is one to and fro movement per second) then the graph drawn on paper would appear as in Fig.1(ii) where the centre line is marked with a time scale.

This last graph is the form which we use to show a vibration pictorially. It is generally called a *frequency*, in this case of 1 Hz.

Audio frequencies (that is, those which can be heard) range upwards from about 20 to 20,000 Hz, from the lowest notes of a piano or organ to the highest as of a piccolo. Something vibrating at twenty thousand times in one second may be difficult to appreciate but it is nothing compared with the frequencies at which electrons can be made to vibrate, a million million times in one second is quite commonplace. So we are going to be confronted with very large numbers which are fortunately simplified by the metric system for just as 1 kilometre is the same as 1000 metres so 1 kilohertz is the same as 1000 Hz and the upper audio frequency of 20,000 Hz becomes 20 kHz. (kilo = 1000).

Now we all know how quickly sound waves are lost as they travel through the atmosphere so radio broadcasting uses much higher frequencies which peculiarly enough are not lost to the same extent. These *radio waves* are made to "carry" the audio frequencies of the program as we shall see later but first we should ourselves get rid of the confusion people experience with radio transmissions labelled both in "frequency" and "wavelength".



(i) Pendulum drawing its own graph


1 cm
1 cycle
Waveform
Start
Axis
0
1
2
3
Time in seconds
Pendulum swings equally each side of centre line (axis)
Represents 1 sec. in time

(ii) Graph when pendulum swings at 1 Hz and paper moves at 1 cm per second

Fig. 1 Pictorial representation of vibration

1.2 FREQUENCY AND WAVELENGTH

The dual labelling arises simply because the swing of the *waveform* of Fig.1(ii) can be described in two different ways, (i) as a frequency of 1 Hz or (ii) as the length along the axis of one cycle which is known appropriately as the wavelength. However the wavelength on the paper depends on how fast the paper moves and if we doubled the speed of movement to 2 centimetres per second (cm/s) then the wavelength would be *doubled* because twice as much paper would have moved under the pendulum during one cycle. Alternatively if the rate of swing of the pendulum were doubled to 2 Hz and the paper moved at 1 cm/s, then the wavelength would be *halved* because two cycles would be packed into the space on the graph previously occupied by one. From this we see that the wavelength (denoted by the Greek letter lambda, λ) increases with the speed or velocity (v) of the paper but decreases with the frequency (f) and the simple formula connecting them is

$$\lambda = \frac{v}{f},$$

that is, the wavelength is calculated by dividing the velocity by the frequency. Equally

$$f = \frac{v}{\lambda}.$$

Radio waves have the same form as shown in Fig.1(ii) and the wave itself travels through the atmosphere or space. The principles and formulae we have just examined apply but happily we are not concerned with paper speeds for all radio waves (and light) travel at the same unbelievable speed, three hundred million metres in one second (300,000,000 m/s – more than seven times round the Earth in one second!) So to find the wavelength of any radio transmission we simply divide 300,000,000 by the frequency (in Hz, not kHz), nasty numbers to deal with so the table in Appendix 1 is added as a guide, it covers the transmissions we will be tuning in on our crystal sets later. These range over the long and medium wavebands as follows:

Long Waves:	1000 – 1875m	(160 – 300 kHz)
Medium Waves:	190 – 550m	(545 – 1580 kHz).

As an example, a station broadcasting on 909 kHz has a wavelength of

$$\frac{v}{f} = \frac{300{,}000{,}000}{909{,}000} = 330 \text{ metres (330m)}.$$

As radio constructors we shall often find it more convenient to work in frequency rather than wavelength even though many radio set tuning dials are only marked in the latter.

1.3 ELECTRONS and ELECTRICITY

We all know about *gravity*, something which brings us down to earth with a bump. We attract the Earth according to our size and the Earth attracts us according to its own size and we know which one wins. But we do not know how gravity works, only that it does. It is indeed fortunate that Nature put gravity there or we would disappear into space. It is a powerful but unseen *force*, the strength of which is around us always, we are said to be within its *field*.

These few remarks will perhaps help in appreciating another arrangement of unseen forces due to something we call *charges*. Whereas there is only one gravity which always attracts, there are two different charges which either attract or do exactly the opposite, that is, repel each other and this is according to which of the two types meet. They are labelled positive (+) and negative (–), and there is a simple law which governs their behaviour, "like charges repel, unlike attract".

Electricity is not new, it has been around since the world began. It is the movement of *electrons* which are tiny *negative* charges, within anything, the air if there is a flash of lightning, along mains wires in the home or even through us if we touch something "live". The stuff of which any substance is made (even us) is built up of *atoms*. Each atom has some electrons all to itself just like the Sun has its planets (the Earth is one) revolving round it. An atom with its full complement of electrons is neither positive nor negative because it has a *positively* charged centre which just balances the *negative* charges on its electrons. However some of these little ball-shaped electrons can escape from their parent atoms, a neighbouring positive charge attracts them towards itself or a negative charge pushes them away. When this happens a free electron moves on its own in the spaces between the atoms and because it has lost a negative charge, the atom becomes positive. When electrons are freed in this way and pushed in one direction, this constitutes an *electric current*. This is shown pictorially in Fig.2,


Undisturbed neutral atom (takes no part in current flow)
Free electron moving towards positive pole of battery
Positive atom (has lost one or more electrons)
Inside the wire
(arrows show direction of movement)
Loop of wire
(iii) and release and repel electrons in front of them
(ii) These release and repel wire electrons which also move
(i) (−ve) electrons pushed into wire
−
+
3 volts
Electrons pulled out of wire leaving surplus of (+ve) atoms
Battery

Fig. 2 Electric current flow

where a battery is sending a current round a loop of wire. Chemical action within the battery has the effect of stripping electrons from their atoms and forcing them to crowd at the negative terminal, leaving positive atoms at the positive terminal. The more this happens, the greater the build-up of charge at each terminal and the difference in charge between the two terminals is called the *voltage*, in Fig.2 we have labelled it 3 volts. Thus higher voltage means greater charges which can therefore free and move more electrons in the wire, that is, cause a greater current.

The electron is tiny, so tiny in fact that we get lost in a sea of noughts when considering how many are involved in doing a job. Just as a single example, about 18 million million million (18 followed by 18 noughts) flow through a motor car headlamp bulb every second to light it. No wonder we can never see them.

So we can sum up by saying that an electron is a small charge of electricity normally living with an atom but when lots of them break away and move together in one direction, an electric current flows. When more exist at one point relative to another there is said to be a voltage between the points.

In Fig.2 the electron current is in one direction only and is known as a *direct current* (d.c.) If the battery connexions could be changed over at some very fast rate, electron flow in the wire would reverse its direction at the same rate, it is then known as an *alternating current* (a.c.) and audio and radio frequencies are such, that is, current flowing one way then the other at some frequency. As mentioned earlier we must get used to the idea that these tiny electrons can change direction millions of times in one second.

1.4 CONDUCTORS and INSULATORS

The fact that atoms give up electrons to make an electric current is the basis of electronic engineering, making currents of some predetermined size flow when and where we want. However not all atoms release electrons freely, in fact those of some materials hang on to them so tightly that releasing an electron is almost impossible. This divides materials broadly into two categories, *conductors* in which the atoms willingly give up electrons so that a current can flow, and *insulators* in which they do not. We therefore use a conductor to carry a current and wrap it with an insulator to stop the current going where it should not.

We rate the *ease* with which a material passes a current as its *conductance* but in practice we usually talk in terms of the opposite, its *resistance* (to current flow). Conductors have a low resistance, insulators high. Resistance is measured in *ohms*, (shorthand Ω, the Greek letter omega), practical values run from fractions of one ohm for a short length of wire to millions of ohms, expressed as megohms (MΩ) for insulators. In between there are kilohms (kΩ, 1kΩ = 1000Ω). Everything has a value of resistance, even we have.

We might see the relationship between voltage, current and resistance by considering a crowd of football fans at the stadium gates. The game is soon to commence and, anxious to get in, they create pressure on the gates. Each fan may be likened to an electron and those at the gates are being pushed by the agitation and anxiety of those behind. The pressure on the gates is the *voltage* but being closed, they present an infinitely high *resistance*. Nobody gets in (zero current). Now if the gates are opened slightly the gate resistance has fallen and some fans enter the ground (lower resistance, increased current). With the gates flung wide open everybody pours in (even lower resistance, high current). It is clear that the number of fans getting into the ground per minute (current) increases both with the pressure built up behind them (the driving force, voltage) and as the gates are opened more (lower resistance).

Copper is a good conductor and is used extensively in electronics for wires and components, silver is slightly better but

expensive. For insulators we can use for example, rubber, mica, most plastics, porcelain, glass or air. Thus wires usually consist of a copper conductor either bare or more usually coated with plastic (for example, electric light flex), current flows along the wire and it is confined to it by the insulation. Enamel is also an insulator so for many electronic purposes the insulation on a copper wire may consist of a thin coating of enamel only. This saves space but it must be treated with care for the enamel is easily damaged. In electronics diagrams when a wire is indicated for conducting current from one part or component to another we simply draw a single line and it is understood that the wire is either insulated or if not, supported in such a way that it touches nothing along its length. We will see how wires are drawn on circuit diagrams later.

There are many thicknesses or *gauges* of wire available from the hair-line to pencil thick. The world classifies them in different ways although generally the metric system is taking over in which a wire is described by its diameter in millimetres. Two other systems are still much in use, the *Standard Wire Gauge* (SWG) and the *American Wire Gauge* (AWG). Naturally we will use metric but where appropriate the nearest other gauges are also quoted.

Semiconductors are materials used in transistors etc. and they are neither good conductors nor good insulators, somewhere about half-way (semi = half).

1.5 RESONANCE

The pendulum mentioned in Section 1.1 is capable of keeping a clock accurate because it has a *natural* period of oscillation which depends only on its length (the shorter the pendulum, the faster it goes). It does not matter how hard it is pushed, eventually a pendulum settles down to the same time per cycle. A piano or any other musical string similarly has a natural period of oscillation but at a higher frequency, for example, for middle C the string vibrates at 262 Hz. The frequency in this case is determined by the thickness of the string and the tension in it and the piano tuner simply adjusts the tension to get the note right. When the note is played the wire is struck and set in vibration but it vibrates only at 262 Hz and this is called the *resonant* frequency. Similarly for all the other piano notes each wire has its resonant frequency. Resonance is a feature of all musical instruments by which they generate the delightful sounds we hear.

An electrical circuit can also resonate, that is, respond to one frequency only and two special components are required, an *inductor* and a *capacitor*. The inductor is a coil of wire and it has a distinctive property of *reactance* which affects a.c. only. The capacitor is a very different component from the inductor, it comprises metal plates which can hold a charge, it too has the property of reactance. We will not go into detail about these components yet because we will be looking at them more closely later. What is important here is that the inductor has one type of reactance which we label positive and the capacitor has the opposite type, so it is labelled negative. As with charges, a positive reactance can be cancelled out by an equal amount of negative reactance. The reactance of an inductor *increases* as frequency goes up but that of a capacitor falls and

> at low frequencies the reactance of an inductor is low, that of a capacitor is high
>
> at high frequencies the reactance of an inductor is high, that of a capacitor is low

so as frequency rises from low to high, with the reactance of the inductor rising and that of the capacitor falling, at some value they are both the same and cancel out.

Reactance, either positive or negative, is rather like resistance, it tries to stop current flowing so a circuit containing the two components can pass a high current at the frequency at which the reactances cancel but a lower current at all frequencies above and below this value because the reactances do not

cancel, there being more positive than negative or the other way round. The two components constitute a resonant or *tuned* circuit and we can begin to see how a radio receiver separates the wanted radio frequency from the others.

Let us now put this on a *circuit diagram* as in Fig.3. In diagrams the symbols are as shown and the shorthand for an inductor is L and for a capacitor, C. In Fig. 3(i) because both L and C have fixed values the circuit resonates at one frequency only. To make it resonate over a *range* of frequencies, for example the long or medium wavebands, we could vary either L or C and it will soon be evident that to vary C is much easier so Fig.3(ii) shows the complete tuned circuit we will construct. Variable capacitors are only available with certain maximum values so the inductors are wound to suit.


Wire connecting one terminal of inductor to one terminal of capacitor
Inductor
L
C
Capacitor
L
C
Variable capacitor

(i) Fixed (ii) Variable

Fig. 3 Tuning circuits

1.6 AERIAL and EARTH

The drawing of Fig.3(ii) is therefore that of a tuned circuit capable of selecting one radio frequency out of the many offered to it. The radio waves are collected and delivered to this circuit by an *aerial* (also known as an *antenna*). Away at the radio transmitter we might imagine that the transmitting aerial is shaking a charge of electrons to and fro as we might shake a rope to make it take up a waveshape as in Fig.1(ii). This projects an alternating field outwards and just like the field of gravity, invisible but always there waiting to move anything it can, the radio field or wave causes the electrons in an aerial conductor to flow one way or the other according to the direction of the field at that instant. Technically we say that the field *induces* a voltage in the conductor. The degree to which the electrons flow depends on the strength of the field, the height of the aerial and how good a conductor it is.

Thus we erect an aerial which is simply a long copper conductor suitably insulated where necessary to prevent electrons leaking away. Because we are using no transistors to boost the aerial signals, as large a signal as possible must be collected and for this the earth itself is helpful as a return conductor back to the radio station. It may be surprising that the earth can be used in this way because some earthly materials such as sand and rock are actually insulators but it is obvious that there are countless other paths through the earth each carrying its share of the electrons of a current. One of our problems is in making a sufficiently good contact with "earth".

Fig.4 shows the tuned circuit connected between aerial and earth so that the electrons disturbed by the radio signals flow through it and when capacitor C is suitably adjusted so that the circuit tunes to the wanted frequency, this is the one which appears across the output terminals. Note the symbols used in diagrams for aerial and earth and how a connexion is indicated. A *connexion* implies two metals in such close contact that electrons flow unimpeded from one to the other, the metals are then said to be "in contact".

1.7 MODULATION

We have seen that a radio program consists of audio frequencies of a few kilohertz, yet the radio transmission is at



Fig. 4 Aerial feeding a tuned circuit

a much higher frequency, up to and over 1000 kHz. The radio frequency is called a *carrier* because in effect this is what it does, it carries the audio frequency on its back, so to speak. The process of getting it to do this is known as *modulation* and what happens is that the strength or *amplitude* of the radio-frequency (r.f.) carrier is caused to vary according to the amplitude of the audio frequency. This becomes more evident when shown pictorially as in Fig.5. The three parts of the figure are all graphs, on a basis of time, of how the amplitude of the modulating (audio), carrier and modulated waves vary. An *oscilloscope*, which is a measuring instrument with a small television-type screen, is the electronic counterpart of our rather crude method of making an oscillating device draw its own graph as in Fig.1(i) and this is how Fig.5 would be produced when the appropriate waves are applied to the input terminals. We take a practical example, that of the highest note of the piano (about 4 kHz) being transmitted on a carrier of 200 kHz (1500m) and consider a time period of one thousandth of a second (1/1000s), seemingly a very short time indeed but in which there are 200 complete cycles of the carrier wave.



(i) Modulating wave



(ii) Carrier wave



(iii) Modulated wave

Fig. 5 A modulated wave

A *microphone* listens to the sound waves generated by the piano wire. Its *diaphragm* vibrates at the frequency of the sound wave hitting it and causes electrons to move in alternate directions in the circuit connected to it. The result is an electrical signal which is a replica of the original piano wire vibration. In one second the audio wave completes 4000 cycles, therefore in 1/1000s exactly 4 cycles are completed. Fig.5(i) does not show all 4 cycles, only part of the first and the end of the last but this is sufficient to demonstrate the principle. For convenience it also shows the wave "cleaned up", the true graph is more complicated although of the same basic frequency. In Fig.5(ii) is shown the r.f. carrier at 200 kHz therefore 200 complete cycles in 1/1000s.

In the modulation process the amplitude of the carrier is made to vary in accordance with that of the modulating wave so from (i) and (ii) in the figure we can deduce (iii), and this is how the program is carried, the frequency of the carrier is not changed whereas its amplitude is. Note that both the positive and negative halves of each cycle are equally affected. Fig.5(iii) therefore shows the sort of waveform appearing at the output terminals of Fig.4 and what is needed next is a device to extract the audio frequency from the carrier.

1.8 DETECTION

Headphones work in reverse to microphones, an incoming electrical variation at audio frequency causes the diaphragm to vibrate accordingly and hence set up sound waves in the ear canal. The form shown in Fig.5(iii) is not suitable for operating headphones directly because the movement of electrons in the headphone driving unit in one direction when the wave is positive is immediately cancelled by a similar movement but in the opposite direction when the wave goes negative. Firstly one of these movements must be suppressed, it is then possible to find the average of all the unidirectional (all positive or all negative) half-cycles left. This brings us to the subject of rectification and a *rectifier* or *diode* is a device

which allows electrons to flow through it in one direction only, that is, it can behave either as a conductor or insulator according to which of its two terminals is presented with electrons. Hence if the wave of Fig.5(iii) is applied to a diode either all the positive half-cycles or the negative ones are blocked according to which way round it is connected. Effectively therefore in our example there would be 200,000 unidirectional *pulses* of current each second. But these pulses are not all equal in strength, they vary in amplitude according to the modulating frequency so by adding them together and somehow finding the average value as we go, the original modulating frequency is restored. A capacitor is suitable for this because it can store electrons on its plates and so add the various pulses together. Looking at Fig.5 again the *detection* process firstly removes either the top or bottom half of (iii), then by an averaging process regains (i). We can now complete our basic crystal receiver circuit diagram as in Fig.6. D is the diode and C_2 the capacitor just mentioned and except for the latter which we will find we can manage without, this is the circuit we will first build for experience.

All very well, but we are building a *crystal* set, where is the crystal? This in fact has gone out of fashion and its place is now taken by the diode, cheaper, smaller, more reliable and



Fig. 6 Basic crystal (or diode) receiver circuit

needing no adjustment. Detection was accomplished in early receivers by means of a contact made between a fine-pointed wire and a crystal of galena, molybdenite or carborundum, each had its particular qualities. To obtain a suitable crystal/metal junction it was necessary to search around the crystal for a responsive spot using the end of the wire until the headphones sprang to life. This could take several minutes so woe to any member of the family thereafter causing sufficient rumpus for the contact to be lost. The wire became known as the *cat's whisker* and just to see what we have missed, Fig.7 shows a sketch of a crystal detector (minus its glass case) with a modern diode for comparison.



Fig. 7 Crystal and diode detectors

CHAPTER 2
COMPONENTS

Fig.6 shows the various components required for a basic receiver. Apart from the aerial and earth there is an inductor (L), variable capacitor (C_1), fixed capacitor (C_2), diode (D) and headphones. The inductor we will make ourselves although it could be bought (more of this later), the other components can be purchased from a radio component shop or mail-order service. The names and addresses are to be found in popular electronic or radio constructors' magazines, usually published monthly. Catalogues are so large nowadays that a charge may be made but to have one is an asset and note that the larger the catalogue, the more likely it is that the particular firm will be able to supply all the items required, this saves shopping around and postage. Nevertheless we must never forget that the defective radio set discarded by the family or friends, too expensive to repair yet somehow too good to throw away, can provide the experimenter with a plentiful supply of useful parts, especially the variable capacitor which we next consider.

So that we understand the components a little better, some notes follow.

2.1 CAPACITORS

To the newcomer a capacitor is a mysterious piece of equipment. It has no through connexion as do most other components, there is actually an insulator between its two sets of plates. Imagine two plates of metal placed close together as in Fig.8 and connected to a battery. As seen in Fig.2, a battery is a device which has a high pressure of electrons at its negative terminal and an equal lack of them at the positive terminal. When a battery is connected to the plates therefore there is a rush of electrons into the l.h. plate and equally out



Fig. 8 Charging the plates of a capacitor

of the r.h. plate, in the latter case attracted by the surplus of positive atoms at the battery + terminal. The l.h. plate is therefore negatively charged and the r.h. positive, all in a very short time. There is no flow of electrons across the air-gap between the plates because air is an insulator so the flow ends when, for example, the l.h. plate has reached the same "electron pressure" as that at the battery negative terminal for then there are two equal negative charges opposing each other. The plates are now said to be *charged* and if the battery is disconnected they remain so. If subsequently a circuit or wire is connected across the plates then for the tiniest fraction of a second they act as a battery and drive electrons round until they are *discharged*.

Little imagination is required to see that *capacitance*, which is the capability of storing a charge, depends on the area of the plates. It also varies with the separation between them, reduced separation giving greater capacitance. The insulation between the plates (the *dielectric*) need not be air, other

insulating materials are used and the capacitance increased. The unit of capacitance is the *Farad* but generally in radio we work in *microfarads* (μF – μ is the Greek "mew") which are millionths of a farad or in *picofarads* (pF) each of which is one millionth of a microfarad. Just to add to our confusion some capacitors are now so small that there is no room to print the value in pF on them so the *nanofarad* is used which is one thousandth of 1 μF or equally one thousand pF, thus:

$$\mathrm{nF} \times 1000 = \mathrm{pF} \quad \mu\mathrm{F} \times 1000 = \mathrm{nF} \quad \mu\mathrm{F} \times 1{,}000{,}000 = \mathrm{pF}$$

so a 0.0005μF capacitor could equally be quoted as (0.0005 x 1000)nF, i.e. 0.5nF or (0.0005 x 1,000,000)pF, i.e. 500pF.

If required, C_2 in Fig.6 would be a *fixed* capacitor, with one value of capacitance only, say about 1000pF (or 1nF). By using thin dielectrics and plates, such a capacitor is no more than a bead a few mm across in the middle of its two connecting wires.

Variable capacitors such as C_1 are more complicated because they are mechanically operated. Those for tuning radio receivers have maximum values ranging from about 300 to 500pF. The capacitor works by enmeshing a set of movable plates (many small ones are connected together as the equivalent of a single large plate) with a second set of plates which are fixed as shown in Fig.9. The dielectric is usually air but solid dielectric types are also available which are more compact. A (tuning) knob is fixed to the shaft, by turning clockwise the moving plates interleave more with the fixed ones, so increasing the capacity. The moving plates are in contact with the frame and are therefore connected to the *earthy* side of the tuned circuit. The fixed plates are insulated from the frame.

If an old radio receiver is being *cannibalized* (dismantled to provide spare parts), the variable capacitor is easily recognized. Its spindle will be coupled to the tuning dial and it will look something like Fig.9 but duplicated or triplicated, that is two or three complete capacitors on one spindle. This is quite usable, we need only connect one section and improved designs shown later in the book need two sections anyway.



Fig. 9 Variable capacitor

2.2 INDUCTORS

These take many forms but at this stage we consider the *air-cored* type only. Ours will consist of enamelled wire close-wound on a cardboard or plastic tube, the number of turns of the wire being chosen to produce the correct *inductance*. This is measured in henrys, again a large unit for radio constructors so we work in *microhenrys* (μH) one of these being one millionth of 1 henry.

When electrons flow in one direction in a coil of wire, they create a magnetic field running through the centre which can turn a compass needle just as the Earth's magnetic field or that of a permanent magnet does. Again the field is invisible but the force it can exert is there just the same. If the electrons reverse direction, so does the field and if it attracted

one end of a compass needle in the first instance, it would now repel it. Of equal importance is the fact that when the current ceases, support for the magnetic field is removed and it collapses but in so doing, itself creates electron flow in the windings. In a resonant circuit the rise and fall of the magnetic field of the inductor is complementary to the discharging and charging of the capacitor. There is a to and fro movement of electrons between them which is greatest at the resonant frequency.

To cover the medium waveband (Section 1.2) an inductor of about 200μH is needed.

Enamelled wire is obtainable in over 60 different sizes, a good one to start with is 0.56mm diameter. Constructional details of coils follow in Chapter 4. Note that the general term "coil" is frequently used instead of "inductor" in radio tuning applications.

2.3 DIODES

Study of the diode, so called because it has two *electrodes* (di = 2) brings us into touch with the semiconductors on which modern transistor technology is based. Our explanation must of necessity be very simplified and it starts with the two fundamental types of semiconductor materials. These are *silicon* compounds which either have an excess of positive atoms or of negative electrons. The first is obtained by mixing silicon (a grey, brittle material) with a substance which "steals" electrons from some of the normally neutral atoms thereby leaving them positive, the final material is described as *p-type*. Alternatively a substance can be added which gives extra electrons to the silicon which is then classed as *n-type*. It is when p-type silicon is placed in contact with n-type silicon that a diode with its rectifying properties is formed. Fig.10 shows a battery connected across a diode with its junction between the two semiconductors shown diagrammatically, it of course does not have clean boundary lines as suggested.



(i) Forward bias

(ii) Reverse bias

(iii) Rectifying an AC waveform

Fig. 10 Diode rectifier

In (i) the +atoms in the p-type and the −electrons in the n-type are forced straight across the junction by the similar charges of the battery. Some recombine to form neutral atoms in the junction area but the battery supplies plenty to make up for this. Thus current flows and the battery is then said to be connected in the *forward* direction.

(ii) When the battery connexions are reversed as shown, the *current carriers* (+ atoms and − electrons) are swept out of the junction whereupon no current can flow, that is, the device effectively becomes an insulator. This is the *reverse* direction.

Accordingly, if the battery potential is replaced by an a.c. waveform which in fact swings in both forward and reverse directions, the result is as shown in Fig.10(iii) where one half of each complete cycle is cut off.

We will see from the diode itself just how tiny the actual junction must be so if too many current carriers are pushed through the junction at once by applying too high a voltage, the heat created will burn it out. There are no such difficulties with a crystal set however because the voltages picked up by the aerial are minute. But we could be in trouble when soldering a diode wires onto tags because heat from the soldering iron travels along the wires to the junction, a golden rule therefore is not to cut the wires, to solder right at the ends and if possible use a *heat shunt* (see Appendix 3).

2.4 HEADPHONES

Resistance is mentioned in Section 1.4 and a crystal receiver needs headphones of 2000Ω resistance or more for most efficient working. Such headphones can be purchased but it is far better to make use of a type which is more available generally. Nowadays an increasing number of homes possess a pair of good quality stereo headphones, usually supplied with hi-fi systems, music centres, electronic organs and the like. This naturally saves purchasing them but if they do have to be bought, the low *impedance* types have many more uses for other projects. We can adapt them for ours.

We seem to have switched from the term "resistance" to "impedance", there is in fact a technical difference between the two even though they are both quoted in ohms, nevertheless as far as headphones are concerned we can look at both terms as meaning the same.

Stereo headphones are usually connected as shown in Fig.11 to a 6.5mm (¼ inch) jack plug. The wiring arranges for two separate *channels*, one to each earpiece. One wire is common to both so only three wires are needed. The plug has *tip*, *ring* and *sleeve* connexions insulated from each other as shown and we need to make our connexions to tip and ring only for the signal current then flows through the two earphones in *series* (that is, one after the other). This also happens to double the net headphone impedance to 16Ω since two 8Ω earphones in series gives 16Ω as shown in Fig.11. However we should not put 16Ω headphones directly on a circuit requiring a high impedance for some of the signal is wasted in so doing. What is necessary is to *match* the headphones to the receiver circuit by making them behave as though they have high impedance and this is effected by a *matching transformer*, miniature ones which are used between some transistor circuits and loudspeakers are suitable and inexpensive.

When electrons flow in a winding a magnetic field is set up and if another separate winding is within this field its electrons experience a force trying to move them. With a circuit connecting the two ends of the winding they can and do move and as we say, a current flows. This only happens while the current in the first winding is changing but this is the condition throughout crystal sets because all currents are alternating. A *transformer* consists of two or more separate windings which are in magnetic contact with each other, that is, they are close enough for the magnetic field of one to affect the other. Sometimes, as in the case of matching transformers, one winding is wound round the other with both on a metal core, alternatively as we shall find later (Section 5.5) many r.f. transformers have the two windings completely separated. The symbol for a transformer is shown in Fig.11.

Matching transformers convert impedances from one value to another and are sold quoting the impedances between



Fig. 11 Matching a high impedance receiver to low impedance headphones

which they should be used. We need not worry if we cannot get exact values as long as the impedance *ratio* is about right. Thus a transformer quoted as *primary* 1.0kΩ, *secondary* 5Ω (primary and secondary are the names of the windings) has a ratio of

$$\frac{1000\Omega}{5\Omega} = 200.$$

This ratio therefore raises 16Ω to 16 x 200 = 3200Ω as shown in Fig.11, the sort of value we are looking for (say, 1500 – 4000Ω). Thus the stereo headphones with transformer can replace high impedance headphones.

If stereo headphones cannot be borrowed, for real economy a crystal earpiece may be used instead, it has the right impedance and is surprisingly cheap, but as might be expected, much less efficient. Nevertheless one might usefully start with this type, leaving the purchase of more expensive headphones until later.

CHAPTER 3
AERIAL and EARTH

It is perhaps the two items at the input and output of the crystal set which affect the overall results most, the aerial/earth system and the headphones. In this chapter we discuss the former and how to install it, remembering that we are obtaining all the power for driving the headphones from the radio wave itself. We must therefore aim for the most efficient system possible but one which also suits our particular circumstances or location. The use of tiny aerials such as are found in portable receivers can only come by using circuits which are fed with extra power from batteries.

For our purpose aerial installations can be divided into three classes, in order of merit they are (i) outdoor, (ii) indoor loft and (iii) indoor room and the first decision must be as to whether we are building circuits simply for experience in the process of learning or whether a receiver is to be retained for use permanently. This naturally affects the types of wire used and the effort put into the installation, for example for a temporary installation a length of insulated wire slung around the room may be sufficient but we must bear in mind its limitations. Firstly two important reminders:

(i) recalling Section 1.6, the radio signal picked up by the aerial must flow through the tuned circuit, all of it. This implies that there should be no *leakage* paths to earth anywhere along the aerial for if there are, some signal electrons will be bypassed through these paths and be wasted.

(ii) the aerial should be as high as possible.

3.1 OUTDOOR AERIALS

Undoubtedly the best type although the most difficult to provide. Point (i) above reminds us that the aerial must be well insulated from earth all along its length. Air is an insulator so where an aerial runs through open space it can be of bare copper wire but insulated at its two supports. It so happens however that bare wire particularly suitable for outdoor aerials, for example 7 strand, of about 0.72mm (SWG 22, AWG 21 – stranding improves flexibility) may be difficult to obtain except from specialist wire firms so we will think in terms of insulated wire. This also happens to be easier to lead into the house and several kinds are available in most catalogues. Even twin-core plastic-coated mains flex or bell wire can be used quite cheaply as long as the wire itself is not likely to fracture under the tension of a long span. A typical outdoor installation is shown in Fig.12(i). With a little ingenuity and care that pipes or gutters are not pulled off the wall, fixings on both house and distant pole, tree or building can be made. Terminating the aerial wire on its insulators by twisting a loop round the span wire as shown in (ii) of the figure may be difficult with springy plastic-coated wires and here a binding of adhesive tape will help. A temporary insulated wire aerial needs no insulators and the wire can simply be tied at both ends.

The lead into the house must be insulated so if the aerial wire is bare an insulated lead must be jointed to it, preferably by soldering (see Appendix 3). Sometimes a ventilator or ill-fitting window or door will allow a thin plastic-insulated wire to be brought in without drilling through the woodwork (double-glazing makes life really difficult!), so much depends on the house or shed or wherever the receiver is to be used.

3.2 LOFT AERIALS

These are similar to the outdoor type but suspended within a loft or attic. Similar principles apply but in this case the down-lead is already in the house and may be brought down through the trap door or a tiny hole in the ceiling. Alternatively it may be run through the eaves and down the outside wall to be led

in as for the down-lead of an outdoor aerial. Preferably it should not be cabled down the wall but spaced from it.

3.3 ROOM AERIALS

Most likely to be used owing to their simplicity, these are unfortunately the least efficient. Nevertheless many readers will prefer to forego the rigours of outdoor or loft aerials and use this type. An insulated wire is simply run round the walls of the room (preferably an upstairs one) at picture rail or ceiling height back to the starting point at which the down-lead is taken. The wire is fixed by adhesive tape or preferably run through insulated screw hooks to keep it a short distance from the wall. The general arrangement is shown in Fig.12(iii).

3.4 EARTH

A good connexion to earth is essential and is most easily accomplished via a cold-water pipe (not gas, some of the joints may not conduct well) and a check should be made that the pipe does actually disappear into the ground and not find its way upwards to a plastic cold water tank in the attic. The pipe must be scraped or sandpapered clean and a connexion made to it by use of a special *earth clip* which is most likely to be available from an electrical (mains wiring) supplier. Alternatively a good connexion can be obtained by wrapping the earth wire round the pipe several times and then tightly twisting the free end over the main lead as shown in Fig.12(iv). For added security the loops of wire round the pipe may be pressed more tightly into contact by enclosing within a hose-clip of suitable dimensions. Soldering is preferable but not easily carried out because firstly the pipe must be emptied of water and secondly a very large iron or gas torch would be required to heat the mass of metal sufficiently for solder to flow.

Instead of a water-pipe connexion, a home-made earth spike


(Chimney fixing even better)
Support wire or rope
Aerial insulator
Aerial
To receiver
Down lead
Span (preferably 15 to 18 m)
Aerial insulator
Support wire or rope
End of aerial wire (not connected)
(Fixed as high as possible to pole, tree or building)

(i) Outdoor Aerial


Hole in insulator
Span wire
Lead-in
(or free end)

(ii) Attaching aerial to insulator


Ceiling
Insulated screw-hook
Aerial
Room
Down lead

(iii) Room aerial


Water pipe
Earth lead to receiver
Several turns of wire (finally secured by hose clip)

(iv) Earth connection to water pipe


Earth lead
Copper pipe
Washers
Ground

(v) Lead bolted to earth spike

Fig. 12 Aerial/earth systems

consisting of a metre or so of copper pipe can be driven into previously soaked ground and connected to the earth wire as above or by using a bolt, nut and washers as shown in (v) of the Figure.

CHAPTER 4
BUILDING AN ELEMENTARY RECEIVER

There is nothing to stop us building an advanced receiver first, for example, one of the circuits following later. But since our aim is not only to build sets but also to have at least a little understanding of them it is more sensible to start with the simplest. This will give us practice in wiring and even more important, produce something against which improved models can be assessed. Thus assuming that we now have an aerial and earth at our disposal and are capable of soldering (Appendix 3), we build the circuit of Fig.13(i) which is in fact that of Fig.6 minus C_2 and with the aerial connected just over half-way down the inductor. C_2 may be omitted because the inertia (inability to move quickly) of the headphone diaphragm does the job as well. Each r.f. pulse (as in, say, the top half of Fig.5(iii) will tend to move the diaphragm and it will be helped by those which follow since they arrive in rapid succession. The diaphragm cannot move quickly enough to restore between successive pulses although it is able to follow the slower variations in pulse strength, the audio signal.

This is to be a medium wave receiver and for this, using a variable tuning capacitor of about the average value of those available, i.e. 365pF, the inductor has a value of 230μH so our list of parts is:

L	Air-cored inductor, 230μH (details follow). Requires 18 grammes (just over ½oz) of 0.56mm (SWG 24, AWG 23) enamelled copper wire.
C	Variable capacitor, up to 500pF (see Section 2.1 – for this experimental receiver lower maximum values are in order).
D	Signal diode, AA119, OA91 or equivalent.
H	*Either* crystal earpiece and appropriate chassis or line socket (most likely 3.5mm)

or Pair of 8ohm stereo headphones with appropriate stereo chassis or line socket [most likely 6.5mm (¼inch)].

T Miniature audio output transformer (see Section 2.4 and Fig.11).

Also: tuning knob, connexion or tag strip, "hook-up" wire.



(i) Circuit



(ii) Inductor

Fig. 13 Elementary crystal set circuit and inductor

For the inductor a small quantity of enamelled wire, say 50-60 grammes (2oz) can usually be purchased, this is ample. 80 turns are wound on a 4cm (1½inch) diameter cardboard tube, we should not need to make one because they abound in plenty as the centre tubes of toilet or kitchen paper rolls. Failing this, any cylindrical plastic container having approximately this diameter and a length of at least 8cm will be suitable. Fig.13(ii) shows details of the inductor construction. Near one end of the tube two small holes about 1cm apart are made for anchoring the wire (a little clear adhesive helps) and some 5cm of wire is left for terminating. 35 turns are carefully wound along the tube, each turn just touching the previous one. Remember the enamel insulation is thin and easily scratched off. At this point a *tapping* is made as shown and again a little blob of adhesive holds the wire. The remaining 45 turns are then wound on, terminating through two holes as before. Scraping off the enamel and tinning the ends of the terminating wires and tapping loop completes the inductor. Should the end turns tend to loosen and ride along the tube, hold in position by pushing a pin through the tube while some adhesive over the wire and tube sets. We shall find after having built this set that modifications to improve it need additional tappings on the same type of coil. Readers who feel competent to tackle the hazards of seven tappings on one winding may prefer to wind the improved coil instead, simply leaving the tappings not required at this stage unused. See Section 5.1 and Fig.16. Precision is hardly needed so wires of diameter within about 10% of 0.56mm (1 gauge SWG or AWG either way) are quite suitable.

The capacitor is discussed in Section 2.1. If one can be obtained from an old radio set, so much the better. We need only a single-gang for this experimental model but some later ones will require 2-gang, leave unused gangs unconnected and check that no moving vane touches a fixed one. If a capacitor has to be purchased it will probably be found that the solid dielectric type is cheaper. Do not be too concerned about the maximum value, Section 5.3 shows that the coil can be adjusted to suit if required.

The tuning knob can be of any type, a large one (4-5cm diameter) makes fine tuning a little easier.

4.2 CONSTRUCTION

The component lay-out and wiring can to a great extent be to individual choice so what follows is one suggestion only, any other arrangement is equally suitable as long as the connexions are the same, that is, Fig.13(i) is followed. In true *breadboard* fashion a piece of wood at least 15 x 11 cm forms the base as shown in Fig.14, its thickness being such as to accommodate the screws holding the capacitor bracket and the terminal block. It is most likely that the capacitor bracket will have to be made, alternatively a small piece of plywood or hardboard nailed or screwed to the edge of the board and drilled for the capacitor to be fitted will suffice. As a general aid in connecting components together a 6-way mains terminal block is shown, these are usually purchased in 12-way flexible units which can be cut down as required. If desired a *tag-strip* may be used instead, all connexions on it being soldered instead of being held by screws. "Hook-up" wire can be purchased but it is possible to make do with many other types such as bare tinned copper, spare enamel-covered or even pieces of single core mains flex or bell wire, ends tinned where necessary. Remember to refer to Appendix 3 if there are still problems with soldering.

Fig.13(i) shows two alternative output arrangements, the crystal earpiece may be used in preference in which case the wires going to the primary winding of the audio output transformer are connected directly to terminals 4 and 5 of the terminal block instead, the transformer being omitted. The diode can be connected either way round, it does not matter whether we end up with the top or bottom half of Fig.5(iii), the result is the same. The miniature audio output transformer

will probably fit in as shown, the tags of the secondary winding being connected directly into the terminal block. It is the secondary winding which is connected to the headphones, this is the winding marked with the lower impedance of the two to be matched. A centre tap on the primary is left unconnected.

Should a chassis rather than a line socket be required for plugging in headphones or a crystal earpiece, the appropriate chassis-type socket may be fitted on the baseboard or front panel.



Fig. 14 Suggested component arrangement for elementary crystal set

A few hours work and our first set is completed. We cannot switch on because no on/off switch is required, all the power is free from the air so there is never a need to switch off.

4.3 LISTENING IN

When all is connected as in Fig.14 and with aerial and earth, medium wave radio stations should be heard and now we can assess what we have done. So far it is evident that individual circumstances will differ widely in

(i) the strength of the various radio waves where we live. They are affected by the power of the transmitter, the distance from it, what buildings are around us, and even whether it is day or night,
(ii) the efficiency of the aerial/earth system we have constructed,
(iii) whether we are using high quality headphones or simply an inexpensive crystal earpiece which apart from its lower efficiency uses one ear only.

Nevertheless given, say some moderately powerful local station(s) even a downstairs room aerial and a good waterpipe earth, radio programs should be received with ample loudness on the better types of headphones, with a crystal earpiece not so loudly yet ample on local stations. With an outdoor aerial things are noticeably better all round. But what is most likely to be much in evidence is that radio programs are not separated as we would wish them to be for when the tuning knob is turned a powerful local station may even be heard all the way and drown all others. One of our difficulties is that with the growth of local radio over the last few decades, many of us have moderately powerful radio stations only a few miles away. So what we have learned in Section 1.5 does not seem to work out so well in practice – but this is a simple experimental receiver, many improvements can be made. We have no right to expect the selectivity of the modern superheterodyne receiver with its hosts of transistors, tuned circuits

and special techniques. Nevertheless, by starting this way we have gained experience and confidence and will have little trouble in understanding each of the modifications which follow especially if we take them one at a time.

CHAPTER 5
MORE ADVANCED RECEIVERS

Such an uncomplicated receiver as we have constructed cannot be expected to perform as well as a more intricate one so we next look at some refinements, especially those from which can be discovered more about the basic principles of radio.

Readers with no local radio stations may find signals rather weak yet easy to separate while on the other hand those with one or two local stations will probably have more than adequate volume but little choice of station, the local ones swamping everything else and perhaps each other.

Selectivity is the ability of a receiver to respond to a particular radio frequency without interference from others and this may certainly seem to be lacking. However Fig.3(ii) in Section 1.5 considers only the ideal case, that of *pure* inductance and capacitance, that is, no electrons getting lost from the LC circuit in the process. When this does happen then the sharpness of tuning diminishes and the circuit is said to be *damped* – rather like reducing the brilliance of tone of a piano wire by holding a felt pad on it.

The damping arises from other circuits linked with the tuned circuit, in this case the aerial and earth, detector (diode) and headphones. The aerial/earth system hardly looks like a capacitor as in Fig.8, but in fact it is, the aerial wire is one plate, the earth the other. Thus the purity of the inductor is spoilt by having a tiny capacitor (C_a) connected across is as in Fig.15(i). The detector and headphones are connected directly across the tuned circuit and create even more damping, in a simple way we might consider that some electrons flow out of the tuned circuit instead of helping to build up the peak of activity which is required. Effectively this is rather like connecting a resistance (R) as also shown in Fig.15(i).


Equivalent capacity of aerial/ earth system
C_a
L
Tuning circuit
C
R
Equivalent resistance of detector + headphones

(i) Damping of LC circuit



(ii) Damping reduced

Fig. 15 Reduction of damping to improve selectivity

One way of reducing the damping with consequent improvement in selectivity is by tapping the aerial and/or diode lower down the inductor (i.e. towards the earthy end) so that they are effective over less turns but therefore unfortunately providing a weaker headphone signal. Thus the sharper the tuning, the lower the loudness and obviously we will have to find the best compromise between the two.

5.1 IMPROVING SELECTIVITY

Fig.16(i) shows the modified circuit for finding the best compromise between selectivity and loudness for each of our own particular circumstances. To avoid the possibility of mistakes when wiring, a reminder has been added about how wires are shown connected or not connected together on a diagram. The inductor now has 7 taps instead of one but still has a total of 80 turns. There is a tap at every 5 turns from the earthy end


(Wires not connected)
80
AA119
0A91
etc.
8 Ω
L
C
P
S
Headphones
8 Ω
Arrow indicates variable tap
0
(Wires connected)

(i) Circuit


Turn number 0 5 10 15 20 ....
4 cm diam. tube
Tapping loops (total 7)
5 turns
(Ends cleaned and tinned)
Stout copper wires (0·8–1·0 mm)*
as connexions and support
Soldered
Tube
Winding
Terminal block

(ii) Coil tappings and mounting

Fig. 16 Circuit with tapped inductor

for the first 35 turns, i.e. 7 taps in all. We can either use the earlier method of a long (5 cm) loop twisted where it leaves the winding or perhaps a shorter loop onto which another wire is soldered. One suggestion is to have loops about 1.5cm long, staggered along the inductor with the latter supported on a 12-way terminal block using stout tinned copper wire supports as shown in Fig.16(ii). Do not be too concerned about support wire gauge, many junk boxes can produce


Soldered
Winding
Flexible lead
Tube
Terminal block

(iii) Alternative mounting


To variable capacitor (see Fig. 14)
fixed plates
moving plates
Connections to inductor
Turn number → 0 5 15 25 35 80
[see (i) and (ii)]
10 20 30
P
S
Copper wires supporting inductor or flexible leads when inductor supported on receiver base
Diode
1 2 3 4 5 6 7 8 9 10 11 12
E
Flexible lead
Headphones (low impedance)

(iv) Suggested component arrangement

* 21–19 SWG, 20–18 AWG

something suitable, even the individual strands of scrap pieces of household mains cable. Equally the inductor might be fixed on two small blocks of wood with screws or adhesive as shown in Fig.16(iii) with flexible leads to the terminal block or to a tag strip instead.

The inductor requires 9 terminals of the block, the remaining 3 conveniently accommodate the headphone transformer (if

required) and a *flying lead* for the diode, these components are shown in Fig.16(iv). This is doing the job properly, there is no reason however (except for unreliability of contact) why both aerial and diode flying leads should not terminate on *crocodile clips* and be clipped onto the chosen taps as required.

Earth is connected to terminal 1 and the headphones to 11 and 12. Both the aerial and the diode lead are tried at terminals 2 – 9, a game of "poke and hope" but one which can be rewarding. Remember that generally but not always, the tappings with the lower numbers reduce loudness but increase selectivity. Aerial to terminal 8, diode to 9 brings us back to Fig.13(i) of course.

5.2 SWITCHED SELECTIVITY

A technique of selection of aerial and diode tappings by means of rotary switches has much to recommend it especially if setting changes are likely to be needed for reception of different stations. In this case two single-pole 8-way switches are required, usually obtainable as 12-way so leaving 4 spare. The drawing symbol shown in Fig.17 speaks for itself with regard to its action and it may be found from catalogues that there are two types of *action*, by which is meant the manner in which the switch changes over from one contact to the adjoining one. *Break before make* switches disconnect one circuit before the next is connected and *make before break* have a change-over period during which both circuits are connected at once for a short time. Either type is suitable for us. A knob to rotate each switch is also required, a small one, say 2 cm diameter or less is ample, if with an indicator line or pointer, so much the better. The modifications to Fig.16 for switching are given in Fig.17.

With such rotary switches a search for the optimum arrangement is quickly made. To tidy up such a receiver a front panel of plywood might be made and drilled to accommodate the



Fig. 17 - Switching aerial and diode leads

variable capacitor, the two switches and the headphone socket, the latter must then be of the chassis type. A pair of terminals for aerial and earth completes the receiver. On the panel the two rotary switches are easily labelled 1 – 8 but we are still uncertain about a tuning dial because we may not have the right variable capacitor for the inductor, this is the subject of the next section.

5.3 GETTING THE RANGE RIGHT

This is where we pause in receiver construction to remove some of the confusion which may still exist with regard to the tuning ingredients, wavelength, frequency, inductance and capacity, each of which has some bearing on the others, to fit together these four pieces of the puzzle, so to speak. For most crystal sets the inductance is fixed according to the variable capacitor available and we tune the receiver over the range by rotating the variable capacitor knob over half a circle. This is normally divided up into 180 *degrees* (180°) as shown on any *protractor* and as a reminder as the inner row of figures in Fig.18. The problem is to ascertain where on the dial a particular radio station should be found. Firstly we must relate degrees of rotation of the capacitor spindle with the actual capacitance and we might be forgiven for guessing that for, say, a 365pF capacitor the capacitance value at 0° is zero at at 180° is 365pF, but we could be sadly in error for (i) there is always some *residual* capacity when the plates are fully open, (ii) the maximum value may be reached before 180°. Having found the capacitance at each dial setting and knowing the inductance of the coil, the frequency and/or wavelength can be calculated. For those readers with calculators and an interest in arithmetic, this is explained more in Appendix 2. Fig.18 shows the result of such an exercise for a 365pF capacitor and our coil with its inductance of about 230μH. The figures are very approximate and are for one particular type of variable capacitor only. Most capacitors are designed to conform to a certain specified characteristic but there are inevitable differences in manufacture, furthermore there is no guarantee that our coils have exactly the inductance required. Accordingly it might pay to put on a few more turns than stated and then if wanted stations seem to be missing at the high-frequency end of the range, take some off to lower the inductance and hence increase the resonant frequency.

There is also the problem of having a capacitor of some other value than that used for Fig.18 or perhaps one has been taken from a derelict receiver with no idea whatsoever of the value. Measurement of capacitance is certainly beyond us at this stage, hence the technique above of adjusting the number of turns on the coil is the only one.

As an example of coil adjustment when the capacitance is known, say, 500pF, reduce the coil turns on Fig.13 to 65 – 70 to give an inductance of about 170μH. But if we are happy with a few local stations and none is too close to an end of the band, there is no problem.


Frequency (kHz)
Wavelength in brackets
Capacitance (pF)
Degrees rotation
Capacitor plates fully open (0°)
Capacitor plates fully meshed (180°)
1900 (160) 30
1450 (210) 50
1200 (255) 80
1050 (290) 100
920 (325) 130
850 (350) 150
780 (385) 180
730 (410) 205
690 (435) 230
650 (460) 260
630 (480) 280
600 (500) 310
570 (525) 335
550 (545) 360
530 (565) 390
20
30
40
50
60
70
80
90
100
110
120
130
140
150
160

Fig. 18 Approximate capacitance and frequency values for 365 pF variable capacitor and 230 μH coil

5.4 SWITCHED TUNING

This is a feature, simple to provide yet very useful in operation. A switch selects any one of a group of capacitors, each of the correct value for reception of its particular station. Fig.19 shows an arrangement for two stations only applied to the circuit of Fig.16. In addition a fully variable capacitor and tuning dial can be switched in if required. The system is not expensive and in fact for 2 or 3 fixed stations only, probably costs less than for a single variable. Suppose we are designing for two stations say on 909 and 1150 kHz. We could use a miniature single-pole change-over toggle switch or just two positions of a single-pole 8 or 12-way rotary switch for S. Both cost about the same so the latter might be preferable because it can accommodate more fixed stations if needed later. For the coil of Fig.16 the outer ring of Fig.18 is available for estimating the capacitance required in both cases, for example for 909kHz we might guess 135pF and for 1150kHz, 85pF (note that capacitance and frequency increase in opposite directions round the scale). We have considerable freedom of choice in setting up these two capacitances but a suggestion is to use 22pF *trimmers* with fixed ceramic capacitors as shown for $C_1 - C_4$. Trimmers are tiny variable capacitors, adjusted by a screw. When two capacitors are connected in *parallel* as C_1/C_2 and C_3/C_4 are, the total capacitance is the sum of the individual ones, thus a fixed 120pF in parallel with a 22pF trimmer can be varied over the range just over 120pF (all variable capacitors have some residual capacity) to 120 + 22 = 142pF. Hence 909 kHz can be tuned in by adjusting C_2 to make the combination about 135pF (more accurately, 133pF), this is done by adjusting C_2 until the station is heard at its best. Thereafter whenever S is switched to position 1, the station on 909 kHz should be heard. Similarly for as many other positions on the switch as we wish. Switched tuning and switched selectivity can be used together if required.


L
C_1 120 pF
C_2 22 pF
C_3 68 pF
C_4 22 pF
1
2
3
4
5
6
S
365 pF variable (if reqd.)
AA119 OA91, etc.
Headphone circuit (see Fig.11)
8Ω
8Ω
(C_2 and C_4 are trimmer capacitors)
S – position 1 909 kHz
" 2 1150 kHz
" 3–5 spare
" 6 variable over medium waveband

Fig. 19 Fig. 16(i) adapted for switched tuning

Capacitors may have a *maximum working voltage* quoted, above which the component is liable to break down. Any working voltage is suitable for these circuits because all signal voltages are extremely low.

5.5 TWO TUNED CIRCUITS

For many readers who have constructed the basic receiver, good selectivity may still be elusive even with variable tappings on the inductor as in Sections 5.1 and 5.2. Denied as we are in this book of overcoming the problem by the expedient of using transistors and batteries we must continue by exploring other ways of obtaining it. If a single tuned circuit is insufficient, why not use two, one after the other, rather like filtering wine once then a second time to further enhance its clarity? Technically this is a sound idea and the sharpness of tuning increases but one circuit must not damp the other too much for this is the very thing which itself impairs selectivity. Fig.20(i) shows such a circuit. Both inductors are the same as that in Fig.16 but because they are in magnetic contact they


C5
AA119
OA91 etc.
C3
47
pF
C1
365
pF
L1
L2
C2
365
pF
C4
47
pF
Air-cored transformer*
Iron-cored transformer*
(i) Circuit
Fixing screw holes
2 fixing screws
Screw terminals
Position 1
Position 2 (shifted left)
(iii) Moving inductor L1
To variable capacitor C1 (first section, fixed plates)
L1
Winding (see Fig. 16)
9 8 7 6 5 4 3 2 1
Terminal block (movable)
Aerial
(ii) Arrangement of inductors
To variable capacitor (moving plates)
To variable capacitor C2 (second section, fixed plates)
L2
Winding (see Fig. 16)
Diode and matching transformer as in Fig. 16(iv)
1 2 3 4 5 6 7 8 9 10 11 12
Diode flexible lead
Terminal block (fixed)

Fig. 21 A double-tuned crystal receiver

* See Section 2.4

form an r.f. transformer as mentioned in Section 2.4. The closer they are to each other, the more energy passes from the aerial to the detector but unfortunately each reduces the sharpness of tuning of the other. The practical circuit therefore requires that the separation between the two inductors is made variable to obtain the best compromise in any particular case. A suggestion is given in Fig.20(ii). Having some idea by now of the principles involved and the experience of building the elementary receiver we should no longer need a full practical layout except perhaps for the inductors themselves. By taking for example the arrangement of Fig.16(ii) we might fix the right-hand inductor by two screws through the terminal block into the base (there is usually one screw hole between each two pairs of terminals) but make the left-hand one adjustable by using two screws close together and shifting the block (and therefore the inductor) one or more positions to left or right as required [see (iii) of the Figure]. Adjustment should range from the tubes just touching end-on to some 4 – 5 cm apart. This adjustment is in addition to the aerial and diode tappings so we have plenty to play with. Start with aerial and diode at terminal 9.

For really fine adjustment, C_3 and C_4 may be added unless they are already provided on the variable capacitor sections. They are trimmer capacitors of small value, by connecting them as shown, their capacitances are added to those of the main ones, thus if C_1 were set at 300pF and C_3 to 20pF the effective capacity of the combination is 300 + 20 = 320pF. Their purpose is to even up (trim) any variations between capacitor sections and between the coils (we should be top-level coil winders indeed if L_1 and L_2 were identical). Any type of trimmer capacitor can be used and they are connected from the fixed plates of the main capacitors to the earth line. In use the trimmers are first set about half-way, a station is then tuned in at the high frequency end of the band by C_1/C_2, finally the trimmers C_3 and C_4 are adjusted for maximum loudness. This technique ensures that both tuned circuits resonate at the same frequency. Just in case when under weak signal conditions even more coupling between the inductors

is required than is obtained when they are at their closest, another trimmer capacitor C_5 of maximum value 4.7 or 5.5pF may be added and adjusted as required. Some of the signal then flows directly via C_5 in addition to that through the transformer $L_1 L_2$.

A circuit with double tuning which has already been published twice in this series is still especially worthy of our interest because again we learn more about the principles of radio. From Section 1.8, in looking at the basic idea of detection one could be forgiven for wondering whether blocking off and discarding every alternate half-cycle of the r.f. carrier wave was not somehow inefficient and certainly a power engineer would know it to be. What we have used so far is appropriately known as *half-wave* rectification, there is a more efficient system known as *full-wave*. Let us look at this graphically as in Fig.21(i), from which it is immediately evident that for a given input the full-wave circuit must have a greater output.

The crystal set circuit using full-wave detection is shown in Fig.21(ii), it is basically an adaptation of a standard full-wave rectification circuit used to produce direct current from the alternating current mains. L_1 and L_2 are so wound that when a signal flows in L_3 equal voltages are induced by transformer action in them in such directions that only one of the diodes passes current at a time. When the signal reverses direction the other diode is operative hence full-wave rectification as in (i) is obtained. Winding the coil needs a little more skill than hitherto but the result is a professional looking job as there are no untidy taps, the aerial is controlled by capacitors instead. Details of the coil are at (iii). A 2.5cm (1 inch) diameter tube is required, about 15 cm long. An odd piece of plastic water piping of this outside diameter might be found but failing this the tube can be made from a piece of thin cardboard 15 cm x 8 cm wrapped over a broom handle so that the long edges just meet, and lapped with gummed paper tape. Some 11 gm (less than ½oz) of 0.25mm (SWG 33, AWG 30) enamelled copper wire is required for the three windings and it is essential that L_1 and L_2 are wound in the same direction. The


+
−
time
Half-wave rectifier
=
time
or
time
Full-wave rectifier
or

(i) (i) Rectifier outputs


C5 365 pF
S
C6
1000 pF
(1 nF)
L3
5
2
3
6
1
4
L1
L2
C3
47
pF
C1
365
pF
C4
47
pF
C2
365
pF
D1
D2
Headphone circuit (see Fig. 11)
D1, D2 = AA119, OA91 etc.

(ii) Circuit of complete receiver


15 cm approx.
Gap 3–4 mm
L1
135 turns
L3
42 turns
L2
135 turns
(0·25 mm e.c. wire)
2·5 cm approx.
5
6
1
2
3
4
(Wire passes through pin-hole to inside of tube and is held in small slot or pin-hole at end of tube, finally secured with blob of adhesive)
e.c. = enamel covered

(iii) Details of R.F. transformer windings

Fig. 21 Full-wave detection

complete inductor is not self-supporting, it must therefore be screwed or glued to small wooden blocks on the baseboard. The diodes can be connected either way round but they must both be the same, that is, both marked ends to C_1 and C_2 or equally both to the matching transformer. Capacitor C_5 and switch S (either rotary, toggle or slide, in fact any *single pole, single throw* switch is satisfactory) can be mounted on a front panel with the tuning knob and dial (if fitted).

The trimmer capacitors C_3 and C_4 if added, are set as before. The rule given for the aerial capacitors is that for the high-frequency end of the range (above about 850 kHz, below 350m) S should be open (C_6 disconnected) otherwise S should be closed. Thereafter adjust C_1/C_2 for maximum loudness on the required station followed by C_5 for increased loudness or better selectivity.

5.6 ADDING LONG WAVES

Most broadcast radio transmitters are found on medium waves, hence our main interest in this band. However a few transmit on long waves and therefore need consideration. The inductance required for long waves is many times that for medium, accordingly a greater number of turns is required and if we wound an inductor using the single-layer principle used so far it would be of excessive length and inefficient. The immediate reaction to this is to *layer* or *pile* wind it, that is by successive layers on top of each other. But other inefficiencies now creep in.

(i) with so many turns a smaller gauge wire is necessary, this has higher resistance and such opposition to current flow results in a lower *quality factor* (Q) for the inductor (Q must be high for good selectivity).

(ii) inductor windings have capacitance between adjacent turns, each wire forming a capacitor plate with the wire insulation plus air as the dielectric. This is greatly increased with pile winding because wires not only have adjacent ones in the same layer but also in the next inner and outer layers. Special winding techniques using machines can minimize this effect but we cannot manage by hand. The net effect of the unwanted capacitance is similar to increasing the winding resistance, hence further lowering the Q.

We have to accept (i) or we end up with an enormous inductor therefore a finer wire is used, for example 0.315mm (SWG 30, AWG 28). For (ii) we can split the winding up to reduce the capacity and reduce it even further by changing to a different type of wire insulation with an extra covering or two of cotton, silk or nylon to increase the wire spacing. Unfortunately such covered wires are not so easily obtainable from the usual component firms and also are rather more expensive. It might be at this stage therefore that we should consider purchasing a ready-made coil. However, for those who wish to persist against all odds, a long wave/medium wave crystal receiver circuit which was published earlier is reproduced here [Fig.22(i)], it uses a home wound inductor for which DSC (double silk covered) or DCC (double cotton covered) wire can probably be obtained from a specialist wire firm. Details of the inductor are in (ii) of the Figure, some 50 – 60 gm (2 oz) of 0.315mm (SWG 30, AWG 28) wire are required and it is again wound on a 4cm diameter, 11cm long cardboard tube (e.g. toilet roll centre). Switch S is for wave band changing, when closed L_1 only is effective and this is the correct inductance with medium waves for a 500pF variable capacitor (using a lower value for C_1 requires an even larger inductor). When S is open, L_2 is added and the inductance rises to that required for long waves (about 2000μH). Note how L_2 is wound in separate piles to reduce the capacity, each pile winding can be built up without side supports but if preferred, cardboard discs can be fitted first [see (iii)] to make the job easier. The aerial and diode tappings are set for a compromise between loudness and selectivity but being a circuit without frills it is unlikely to reject fully local transmitters.


C2
300 pF
1
2
L1
3
4
L2
5
S
C1
500 pF
AA119
OA91
etc.
Headphone
circuit
(see Fig. 11)

(i) Circuit


11 cm
L1
L2
4
4
1
Tapping 2
Tapping 3
4
4
5
4 cm
56 t.
84 turns
112 turns
60 turns each pile (total 300)
(All wire 0·315 mm DSC or DCC)

(ii) Details of coil


0·5–1·0 cm
0·5 cm
Apply adhesive
round edge

(iii) Adding discs to coil former

Fig. 22 A LW/MW receiver

5.7 USING READY-MADE COILS

In the previous section we begin to get suspicious about the success of winding our own coils when selectivity is of major concern and when this is the case it may well be preferable to purchase ready-made ones instead. These are likely to be more efficient than the home-made types because generally they use metal instead of air cores. By filling the centre of the tube or *former* with certain metallic compounds the inductance is raised, thus fewer turns are required so resulting in less winding resistance and a higher Q which as we have discovered, is the secret of selectivity. Such coils may be available especially for crystal sets or are the aerial coils of a range of different types for home construction of complete transistor receivers. Diagrams for use are usually included with the coil. Be sure to order for the correct wave range (long or medium) because many series of coils include those for short-wave ranges also.

Having read so far and perhaps also having built one or more of the designs, our understanding and constructional abilities should certainly be at the level at which a circuit diagram included with a manufactured coil creates no misgivings.

APPENDIX I

WAVELENGTH – FREQUENCY CONVERSION

LONG WAVEBAND

λ metres	f kHz
1000	300
1050	286
1100	273
1150	261
1200	250
1250	240
1300	231
1350	222
1400	214
1450	207
1500	200
1550	194
1600	188
1650	182
1700	176
1750	171
1800	167
1850	162
1900	158

MEDIUM WAVEBAND

λ metres	f kHz
190	1579
200	1500
210	1429
220	1364
230	1304
240	1250
250	1200
260	1154
270	1111
280	1071
290	1034
300	1000
310	968
320	938
330	909
340	882
350	857
360	833
370	811

λ metres	f kHz
380	789
390	769
400	750
410	732
420	714
430	698
440	682
450	667
460	652
470	638
480	625
490	612
500	600
510	588
520	577
530	566
540	556
550	545

APPENDIX 2
SIMPLIFIED RESONANT CIRCUIT CALCULATIONS

There is a standard, well known formula relating the resonant frequency (f_o) of a tuned circuit with the values of inductance and capacitance therein, it is

$$f_o = \frac{1}{2\pi\sqrt{LC}}$$

where f_o is the resonant frequency in Hz
L is the inductance in henrys
C is the capacitance in farads
π is the ratio of circumference to diameter of a circle and is equal to 3.14159.......

For convenience throughout this book we consider frequency only in kilohertz (f_k), inductance in microhenrys (L_μ) and capacitance in picofarads (C_p), therefore

$$f_o = f_k \times 10^3, \quad L = L_\mu \times 10^{-6}, \quad C = C_p \times 10^{-12}$$

and substituting in the above formula

$$f_k \times 10^3 = \frac{1}{2\pi\sqrt{L\mu \times 10^{-6} \times C_p \times 10^{-12}}}$$

$$= \frac{1}{2\pi \times 10^{-9}\sqrt{L_\mu \times C_p}}$$

$$\therefore\ f_k = \frac{10^{-3} \times 10^9}{2\pi\sqrt{L\mu C_p}} = \frac{10^6}{2\pi\sqrt{L\mu C_p}}$$

$$\therefore\ f_k^2 = \frac{10^{12}}{4\pi^2 L_\mu C_p} = \frac{2533 \times 10^7}{L_\mu C_p}$$

giving us three useful formulae:

$$L_\mu = \frac{2533 \times 10^7}{f_k^2 C_p},$$

$$C_p = \frac{2533 \times 10^7}{f_k^2 L_\mu},$$

$$f_k = \sqrt{\frac{2533 \times 10^7}{L_\mu C_p}}.$$

With scientific calculators there is little difficulty because scientific notation is available but with a home or pocket calculator which has no such facility and displays only 8 digits, it is still straightforward as long as it has a $\sqrt{x}$ facility.

We cannot get 2533 followed by 7 0's into the display hence work with 4 and multiply by 1000 later. As an example, when $L_\mu = 230$ and $C_p = 365$

$$f_k = \sqrt{\frac{25330000}{230 \times 365} \times 1000} = \sqrt{301.72722 \times 1000}$$

$$= \sqrt{301727.22} = 549.3 \text{ (kHz)}.$$

Similarly for an inductor of 2600μH, the capacitance required to tune to 210 kHz is

$$C_p = \frac{25330000}{210 \times 210 \times 2600} \times 1000 = 220.9 \text{ (pF)}.$$

APPENDIX 3
SOLDERING

To be accomplished at soldering is an asset indeed for so many jobs around the home can be undertaken once the techniques and principles are understood, even plumbing. But that is another story, we are concerned with electrical joints only and happily success with these is really quite easy to achieve.

A3.1 SOLDER

As we see in Section 1.4, electrons flow easily within a conductor it is therefore imperative that should the latter be connected or jointed to another conductor, tag or terminal, the joint itself should not resist this flow. This is accomplished by the two metals being in such intimate contact that electrons flow across the joint as though the metal were continuous. A screw connection such as used in the terminal block of Fig.14 achieves this by the screw being forced into the metal to give a very tight and clean contact. Soldering is another method of joining two conductors together and it provides an excellent and secure electrical contact. Electrical solder is an alloy of tin and lead usually in a 60/40 ratio, this melts and flows at 190°C. Water boils at 100°C so as far as we personally are concerned, molten solder and soldering irons must be treated with respect and fingers kept off. Tin is a metal which readily alloys with copper, that is, it actually mixes with the copper at its surface, thus solder joining two pieces of copper acts as a cement and because of its intimate contact with the surface, electrons flow across without hindrance. Electrical solder is called *soft*, naturally it has some of the characteristic softness of lead, in fact wires can be peeled out of a soldered joint. *Hard* solder on the other hand has a higher melting point and results in a much stronger joint but it is more difficult to manipulate.

It is easy to realize that for solder to form an alloy with copper the surface of the latter must be immaculate, that is with absolutely no dirt, corrosion or *oxide* in the way. Copper readily forms its oxide when it is heated. The oxide is not copper although it is derived from it and therefore any present must be removed. Once copper is coated with solder, formation of oxide is prevented, the process is aptly called *tinning*.

Solder flowing over clean metal and forming an alloy correctly is like water flowing, it has the resemblance of *wetness*, conversely if it tries to flow over a contaminated surface with which it cannot alloy it does not give the appearance of wetting the metal. To assist in prevention of oxide and to aid in cleanliness a *flux* (= to make flow) is employed and to make our life easier modern solders are available looking rather like a thick, soft grey wire with a resin flux running down the centre. For us a solder about 0.7mm diameter (SWG 22, AWG 21) is most suitable. It is available in small coils or larger reels.

A3.2 SOLDERING TOOLS

Undoubtedly the most useful and most used type of soldering "iron" (the working part is actually copper) is the electric one, a heating element within the barrel of the iron heats one end of a copper *bit*, heat travels along the bit to the working end to set up a temperature above the melting point of solder so that solder in contact with the bit melts. A 20 or 25 watt iron has a bit small enough for fine electrical work but it cannot handle bigger jobs which extract heat from the bit faster than the element generates it. A non-electric iron has a copper bit on an iron rod with a handle at the end remote from the bit, the bit is heated separately, for example in a gas flame, when the bit has cooled it must be reheated.

The two almost essential tools for wiring are (i) a pair of long-nosed pliers, with a little practice fine wires can be manipulated quite easily, and (ii) a pair of wire or side-cutters. These two items may seem expensive for in fact they may cost more than the whole crystal set (excluding headphones) but they have many uses around the home so if the family toolbox does not already possess them, the cost will soon be repaid. However it is just possible to manage without them, whether to purchase depends so much on what future intentions are with regard to electronics as a hobby. A small file will also be occasionally required for re-shaping the iron bit.

A3.3 SOLDERING

For a soldered joint, not only the parts to be joined but also the tip of the soldering iron must be tinned. Assuming an electric iron, plug in and after a few minutes it will have reached working temperature. Do not rest the bit on anything metal otherwise heat is conducted away. Most small irons have a hook attached so that they can be hung in an upright position with the bit uppermost. Wipe across the tip of the iron with a small piece of clean rag, if the tip surface is silvery bright it is suitably tinned, failing this, unplug and allow to cool then file until clean copper is exposed all over the tip, then apply the end of a piece of cored solder. When the solder has received sufficient heat from the iron it will melt and flow over the tip, forming a bead of molten solder. If this is wiped away the tip will appear bright and tinned. Remember that little beads of molten solder can raise larger blisters! Filing and re-tinning the tip is only needed occasionally when it has become pitted.

Most component wires and tags are tinned for us during manufacture but if they are dirty or corroded, re-tinning may be necessary. However for practice let us tin and then joint two pieces of copper wire (if no untinned wire is available then tinning can be removed with emery cloth). Wire insulation can first be removed where necessary by cutting round with a knife (carefully, so as not to cut the wire itself) and pulling off. The ends of the wire must be bright copper by rubbing

with sandpaper, emery cloth or by scraping. For solder to flow over the surface the wire temperature must be above that of the melting point of solder. Firstly add a little solder to the tip of the iron as shown in Fig.23(i), next push the end of the wire into the bead to heat the wire (ii), then feed solder (and flux) onto the wire and molten bead,it will flow over the copper and in fact the solder can be "painted" on (iii). Then move the iron and solder along the wire slowly continuing the painting process as far as is required (some surplus solder may fall off, this is inevitable when we start). Finally remove the wire and immediately wipe with the clean rag for a bright, silvery surface to appear, only the surplus solder wipes off, not the alloy.

Tin two pieces of wire and then twist the tinned ends together for about 1cm. Apply solder to the twist as we did in (iii) for the single wire and it will flow easily into the joint, cementing the two wires together, they can subsequently be untwisted only with considerable difficulty by tearing out of the solder.

Fig.23(iv) illustrates the soldering of a capacitor lead to a tag (for clarity we assume that the tag is already connected to something). First check that all surfaces are tinned then loop the capacitor wire through the tag. Press the tip of the iron against the tag and feed solder between the tag and the tip as shown. As the joint heats up the solder will flow, sufficient being fed in to ensure that the wire is fully cemented to the tag. Remove the iron. It looks as though we need three hands for iron, solder and capacitor so the latter must be made self-supporting, perhaps by squeezing the loop of wire onto the tag. Once soldered it certainly must not be moved until the solder has set, quite a short time, especially if we blow on the joint to cool it. Later on when a little skill has developed it will be found possible to solder wires without making a loop through the tag, this is especially useful for experimental work because it facilitates later removal of components.

Provided that all parts are brightly tinned and solder is seen to flow easily into all the crevices and not form globules which


Resin-cored solder
Copper wire
Molten bead of solder
Soldering iron bit

(i) Preparing the iron (ii) Heating the wire (iii) Applying the solder


Solder
Capacitor
Bit
Tag strip

(iv) Soldering a component to a tag


Small plates of metal
Component
Component lead
Clothes peg
Metal plate
End of wire being soldered
Side view

(v) A home-made heat shunt

Fig. 23 Soldering

refuse to flow, a perfect joint is obtained. *Dry* joints occur when dirt or oxide or perhaps too much flux prevent the solder from alloying – a little experience will take care of this.

Finally, remember that if used carelessly a soldering iron and molten solder can cause burns. Also even when unplugged the bit may still remain hot for sometime.

A3.4 HEAT SHUNTS

Some components, especially diodes and transistors are damaged by excessive heat arriving along their connecting wires. Thus soldering operations should not be prolonged nor should the leads be shortened. A further protection is provided by the use of a *heat shunt*, just a small chunk of metal clipped to the lead near the body of the component. Heat flowing along the lead is absorbed by the shunt and is therefore prevented from continuing its passage along the wire into the heart of the device. Heat shunts can be purchased quite cheaply or made for example by clipping strips of metal (copper, aluminium etc) onto the wire using a clothes peg [see Fig.23(v)].

A long appendix because it is easier to solder than to explain how to do it. Good luck!

PUBLISHER'S NOTE

Readers who feel they would like, or have a need to understand electronics more fully may be interested in a series of books by the same author entitled "Elements of Electronics". The series starts at the very beginning and assumes that the reader has no mathematical experience whatsoever and therefore teaches all that is required as each book progresses. It is an educational step-by-step series in which the reader can advance his or her knowledge book by book. The publication numbers are BP62, 63, 64, 77 and 89 and full details are contained within the current Catalogue of Babani Books.

Please note overleaf is a list of other titles that are available in our range of Radio, Electronics and Computer Books.

These should be available from all good Booksellers, Radio Component Dealers and Mail Order Companies.

However, should you experience difficulty in obtaining any title in your area, then please write directly to the publisher enclosing payment to cover the cost of the book plus adequate postage.

If you would like a complete catalogue of our entire range of Radio, Electronics and Computer Books then please send a Stamped Addressed Envelope to:

BERNARD BABANI (publishing) LTD
THE GRAMPIANS
SHEPHERDS BUSH ROAD
LONDON W6 7NF
ENGLAND

160	Coil Design and Construction Manual	1.50p
202	Handbook of Integrated Circuits (IC's) Equivalents & Substitutes	1.75p
205	First Book of Hi-Fi Loudspeaker Enclosures	95p
221	28 Tested Transistor Projects	1.25p
222	Solid State Short Wave Receivers for Beginners	1.25p
223	50 Projects Using IC CA3130	1.25p
224	50 CMOS IC Projects	1.25p
225	A Practical Introduction to Digital IC's	1.25p
226	How to Build Advanced Short Wave Receivers	1.20p
227	Beginners Guide to Building Electronic Projects	1.50p
228	Essential Theory for the Electronics Hobbyist	1.25p
RCC	Resistor Colour Code Disc	20p
BP1	First Book of Transistor Equivalents and Substitutes	95p
BP2	Handbook of Radio, TV & Ind. & Transmitting Tube & Valve Equiv.	60p
BP6	Engineers and Machinists Reference Tables	75p
BP7	Radio and Electronic Colour Codes and Data Chart	40p
BP14	Second Book of Transistor Equivalents and Substitutes	1.75p
BP24	52 Projects Using IC741	1.25p
BP27	Chart of Radio Electronic Semiconductor and Logic Symbols	50p
BP32	How to Build Your Own Metal and Treasure Locators	1.75p
BP33	Electronic Calculator Users Handbook	1.50p
BP34	Practical Repair and Renovation of Colour TVs	1.25p
BP35	Handbook of IC Audio Preamplifier & Power Amplifier Construction	1.75p
BP36	50 Circuits Using Germanium, Silicon and Zener Diodes	95p
BP37	50 Projects Using Relays, SCR's and TRIACs	1.75p
BP39	50 (FET) Field Effect Transistor Projects	1.75p
BP40	Digital IC Equivalents and Pin Connections	2.50p
BP41	Linear IC Equivalents and Pin Connections	3.75p
BP42	50 Simple L.E.D. Circuits	95p
BP43	How to Make Walkie-Talkies	1.50p
BP44	IC555 Projects	1.95p
BP45	Projects in Opto-Electronics	1.75p
BP46	Radio Circuits Using IC's	1.35p
BP47	Mobile Discotheque Handbook	1.35p
BP48	Electronic Projects for Beginners	1.35p
BP49	Popular Electronic Projects	1.45p
BP50	IC LM3900 Projects	1.35p
BP51	Electronic Music and Creative Tape Recording	1.75p
BP52	Long Distance Television Reception (TV–DX) for the Enthusiast	1.95p
BP53	Practical Electronic Calculations and Formulae	2.95p
BP55	Radio Stations Guide	1.75p
BP56	Electronic Security Devices	1.75p
BP57	How to Build Your Own Solid State Oscilloscope	1.50p
BP58	50 Circuits Using 7400 Series IC's	1.50p
BP59	Second Book of CMOS IC Projects	1.50p
BP60	Practical Construction of Pre-amps, Tone Controls, Filters & Attn	1.45p
BP61	Beginners Guide to Digital Techniques	95p
BP62	Elements of Electronics – Book 1	2.25p
BP63	Elements of Electronics – Book 2	2.25p
BP64	Elements of Electronics – Book 3	2.25p
BP65	Single IC Projects	1.50p
BP66	Beginners Guide to Microprocessors and Computing	1.75p
BP67	Counter Driver and Numeral Display Projects	1.75p
BP68	Choosing and Using Your Hi-Fi	1.65p
BP69	Electronic Games	1.75p
BP70	Transistor Radio Fault-Finding Chart	50p
BP71	Electronic Household Projects	1.75p
BP72	A Microprocessor Primer	1.75p
BP73	Remote Control Projects	1.95p
BP74	Electronic Music Projects	1.75p
BP75	Electronic Test Equipment Construction	1.75p
BP76	Power Supply Projects	1.75p
BP77	Elements of Electronics – Book 4	2.95p
BP78	Practical Computer Experiments	1.75p
BP79	Radio Control for Beginners	1.75p
BP80	Popular Electronic Circuits – Book 1	1.95p
BP81	Electronic Synthesiser Projects	1.75p
BP82	Electronic Projects Using Solar-Cells	1.95p
BP83	VMOS Projects	1.95p
BP84	Digital IC Projects	1.95p
BP85	International Transistor Equivalents Guide	2.95p
BP86	An Introduction to Basic Programming Techniques	1.95p
BP87	Simple L.E.D. Circuits – Book 2	1.35p
BP88	How to Use Op-Amps	2.25p
BP89	Elements of Electronics – Book 5	2.95p
BP90	Audio Projects	1.95p
BP91	An Introduction to Radio DX-ing	1.95p
BP92	Electronics Simplified – Crystal Set Construction	1.95p
BP93	Electronic Timer Projects	1.95p
BP94	Electronic Projects for Cars and Boats	1.95p
BP95	Model Railway Projects	1.95p
BP96	C B Projects	1.95p
BP97	IC Projects for Beginners	1.95p
BP98	Popular Electronic Circuits – Book 2	2.25p
BP99	Mini-Matrix Board Projects	1.95p
BP100	An Introduction to Video	1.95p
BP101	How to Identify Unmarked IC's	65p
BP102	The 6809 Companion	1.95p
BP103	Multi-Circuit Board Projects	1.95p
BP104	Electronic Science Projects	2.25p
BP105	Aerial Projects	1.95p
BP106	Modern Op-Amp Projects	1.95p

BERNARD BABANI BP92

Electronics Simplified - Crystal Set Construction

■ This is a book written especially for those who wish to participate in the intricacies of electronics more through practical construction than by theoretical study. It is designed for all ages upwards from the day when one can read intelligently and handle simple tools.

■ This book replaces several now out-of-date ones on crystal set construction that we previously published, especially the very successful book No. 126 "Boys Book of Crystal Sets".

■ So many crystal set circuits exist that it is doubtful whether anything novel could be designed, hence the ones here are based on those from earlier publications, but completely modified to use modern inexpensive components and home-wound coils.

■ A book highly recommended for all newcomers to the fascinating hobby of electronics.

ISBN 0 85934 067 8

BERNARD BABANI (publishing) LTD
The Grampians
Shepherds Bush Road
London W6 7NF
England

£1.75

3 Transistor Short Wave Radio



Radio Shack advertised it's first perfboard electronics kits in 1967 and expanded the line in 1968 and 1969. By 1970 there were 26 kits available that included all the parts needed (except the battery) enclosed in a "space age pbox" that served as the packaging and the perforated board that the kit would be assembled on. The 3 Transistor Short Wave Radio project described here is based on the Radio Shack pbox kit of the same name, but it has been updated with silicon transistors and passive components and controls that can be obtained from electronics suppliers on Amazon. When I was a kid I was able to purchase the original 3 Transistor Short Wave Radio kit from the bargain bin of my local Radio Shack long after they were discontinued. I've built the updated radio kit described in this article and believe it works just as well as I remember the original kit did back in the 80's. To make it easy to replicate my work, I've provided illustrations and step-by-step assembly documentation based on the original assembly manual from Radio Shack. I do not make this kit available for sale and I've kept the original branding and copyright notices intact. What I've made available here is strictly for fun and educational purposes. I hope you have as much fun with this project as I did. The original branding, design and documentation are property of Radio Shack.

A little radio theory

If you would like to start building the radio you can skip this section. But if you are interested in knowing how this radio works then by all means, read on!

There are three major receiver types you can build with analog components:

- Tuned Radio Frequency (TRF) receiver
- Regenerative receiver

- Superheterodyne receiver

The simplest radio is the TRF receiver which can usually be constructed with only five components and requires no batteries or AC power. A TRF radio is the easiest to build but it is not very sensitive to weak signals and has difficulty distinguishing radio stations broadcasting on channels that are close together. A good antenna and ground connection is required to receive anything other than nearby high-power radio stations. A "crystal radio" is the most common TRF radio that experimenters will build.



TRF Receiver Block Diagram

The Regenerative receiver uses some of the same components as the TRF receiver but adds transistors to amplify the radio frequency and audio frequency signals used by the radio station. The Renerative receiver is extremely sensitive to weak signals but it is more complicated than a TRF receiver. It requires battery or AC power to operate, works best with a good antenna and ground connection, and uses two adjustments for tuning in the desired station. The 3 Transistor Short Wave Radio illustrated in this article is a regenerative receiver design.



Regerative Receiver Block Diagram

The Superheterodyne receiver uses many of the same components as the TRF and Regenerative receivers but adds special oscillator and amplifier circuits that make tuning into the desired station very easy. This is the type of receiver upon which all modern AM/FM radios are based. The Superheterodyne receiver is sensitive to weak signals and easily distinguishes between stations that are close together. Unfortunately the superheterodyne is the most complicated of the three receiver types and thus the most difficult to build.



Superheterodyne Receiver Block Diagram

In order for a radio receiver to be useful it needs a transmitter within range that is broadcasting information which can be detected and converted into some useful form of energy (electrical or mechanical). A radio transmitter uses electromagnetic waves to transport information through the ground, the atmosphere, or even across the vacuum of outer space. The properties used to describe these electromagnetic waves include amplitude, frequency, polarization, and direction of propagation. The most important properties for the radios described in this article are amplitude (sometimes referred to as signal strength) and frequency (sometimes referred to as a "channel"). Because electromagnetic waves get weaker with distance, amplitude at the transmitting antenna determines how far away the receiver can be and still detect the information in the broadcast. There are many different frequencies that a radio transmitter or receiver can use depending on the type of information that needs to be broadcast. Some frequencies can pass right through solid objects while others are reflected from stationary or moving objects. Some frequencies can carry voice conversations many hundreds or thousands of miles, while others carry high speed computer data over distances less than 30 feet. To help ensure that radio frequencies are used properly and fairly, all countries regulate who can use what frequency for what purpose. In the United States, the Federal Communications Commission (FCC) is responsible for making and enforcing the rules regulating the use of the radio frequency spectrum. The 3 Transistor Short Wave Radio described in this article is designed to operate in the High Frequency spectrum between 3MHz and 30Mhz.

Radio Frequency Spectrum



VLF = Very Low Frequency
LF = Low Frequency
MF = Medium Frequency
HF = High Frequency

VHF = Very High Frequency
UHF = Ultra High Frequency
SHF = Super High Frequency
EHF = Extremely High Frequency

Before a radio station can begin broadcasting, the operator must first determine the frequency that best fits the information it wants to send, and then construct a suitable transmitter and antenna to cover the desired area over which the receivers will be located. Next, the station operator must determine how the information to be broadcast will be superimposed onto the chosen radio frequency. The process of superimposing information onto a radio frequency is called "modulation". There are many different modulation techniques available but the two most popular are Amplitude Modulation (AM) and Frequency Modulation (FM).

With Amplitude Modulation, changes in the amplitude of the information signal causes a proportional change in the amplitude of the radio frequency signal (also referred to as a "carrier signal").


Information Signal
Radio Frequency Carrier Signal
AM
Modulator
Amplitude Modulated Carrier Signal

With Frequency Modulation, changes in the amplitude of the information signal causes a proportional shift in the frequency of the "carrier signal".


Information Signal
Radio Frequency Carrier Signal
FM
Modulator
Frequency Modulated Carrier Signal
Darker = Lower Frequency
Lighter = Higher Frequency

In most cases, FCC rules and procedures will determine the frequency and modulation that the station will use. Most commercial broadcast stations are authorized to use only one frequency for their transmitter and are issued a station identifier that must be transmitted periodically along with the information they broadcast. The 3 Transistor Short Wave Radio in this article is designed to receive and decode information from Amplitude Modulated (AM) radio frequency carrier signals between 3MHz and 30MHz.


Voice Transmitter Block Diagram
Antenna
AF
Amplifier
Modulator
RF
Amplifier
Microphone
RF = Radio Frequency
AF = Audio Frequency
RF
Oscillator
Ground

Not all broadcast stations are limited to a single frequency. For example, Ham radio operators are allowed to broadcast on any frequency within the spectrum set aside for their use. Many Ham operators have multiple transmitters and antennas at their station and can conduct several conversations on different frequencies simultaneously.

A radio receiver performs the opposite function of a radio transmitter. The radio receiver must be sensitive enough to respond to the very small signals created when electromagnetic waves from the transmitting antenna pass by the receiving antenna. Because there are usually many broadcast stations on different frequencies, the radio receiver must be able to select one frequency from the many available. And then the radio receiver must be able to decode the modulated RF carrier and extract the information placed there by the broadcast station.


Tuner
KNLE
KNCT
KKMJ
KHFI
KROX
KOOC
Frequency Band
Selective enough to separate near-by stations.
Sensitive enough to detect this station...
Yet not sensitive enough to overload on this station.

The simplest TRF radio, the crystal AM radio, does not have the ability to amplify a radio broadcast signal. Therefore it's sensitivity is entirely dependent on the quality of the antenna and ground. A long wire antenna hung outside as high as possible with few trees or buildings nearby, combined with a copper ground rod driven at least 24 inches into moist soil works best. Without an antenna the crystal radio usually picks up nothing, so bigger is better.

Regenerative and Superheterodyne radios provide RF and AF amplification and are much more sensitive than the crystal radio. Although both work best with a good antenna, the Regenerative radio can get by with a short wire antenna strung indoors without a ground. And most superheterodyne radios can pick up several stations with only a small internal antenna.

Selecting one frequency from many is the function of the tuner. All radios have some form of tuner even if they are only designed to work on a single frequency. The tuner most often used in the radios covered by this article is known as the Parallel Resonant LC circuit. This circuit is a powerful electronic filter composed of only two components: A capacitor and an inductor connected together in parallel. The perfect Parallel Resonant LC circuit allows one and only one frequency to enter the radio while blocking all other frequencies. The frequency that is allowed to pass through is determined by the following simple formula:

Parallel LC Circuit





$$Fc = \frac{1}{2\pi\sqrt{LC}}$$

This circuit appears in all radio types, especially the superheterodyne where it performs station tuning and multi-stage signal filtering. As the formula suggests, the center frequency can be changed by adjusting either the inductance L or the capacitance C. An RF tuner typically uses a variable capacitor with a fixed inductor. A tuned RF coupler or filter typically uses a variable inductor and fixed capacitor.

Variable
Capacitor



Variable
Inductor

Once a station is selected by the tuner, the received RF signal must be demodulated. Demodulation extracts the information (music, news, data) superimposed in the RF carrier by the radio transmitter. An electronic circuit that performs demodulation is usually called a "detector". A simple AM detector can be constructed with three components as shown below.



If you review the illustration on AM modulation earlier in this article you will notice that the information signal superimposed on the RF carrier appears in two places: One at the top of the carrier and the other a mirror image at the bottom of the carrier. If both of these information signals were to be extracted simultaneously they would cancel each other out. To prevent this, the diode's job is to eliminate one of the information signals from the carrier. Because a diode allows electrical energy to flow in only one direction, it blocks either the top signal or the bottom signal depending on which direction the diode is installed.



Once the mirror image of the information signal has been eliminated, the last step is to remove the RF carrier. To accomplish that a special circuit called an "RC Low Pass Filter" is needed that will pass the low frequency information signal but block the high frequency RF carrier. A simple RC Low Pass filter used in radio circuits is composed of a Capacitor and a Resistor connected in parallel. The cutoff frequency of the filter is determined by the simple equation below.





$$Fc = \frac{1}{2\pi R C}$$

The diode detector is used in the TRF, regenerative, and superheterodyne radios. It does not offer the highest sound quality but it is the simplest and least expensive. By assembling the building blocks just described, a simple TRF "crystal radio" can be constructed from just a few simple components as indicated in the schematic below.



L1 – Antenna Coil, 650uH (www.amplifiedparts.com, Part No. 005496)
C1 – Variable Capacitor, 10-140pF (www.uxcell.com, Part No. 443DF)
D1 – Germanium Diode, 1N34A (www.amazon.com, Part No. 1N34A)
C2 – Polyester Capacitor, 22nF 100V (www.uxcell.com, Part No. ux2118)
R1 – Resistor, 10K 5% 1/2W (www.uxcell.com, Part No. ux0149)
Crystal Earphone (www.amplifiedparts.com, Part No. 005101)

All components can be purchased from Amazon or from the indicated web site. The circuit above, with a good antenna, easily receives several AM broadcast stations within 550KHz and 1700KHz. The sensitivity and selectivity of this TRF radio can be improved by removing the AM detector, filter, and earphone from the L1a coil winding and adding an RF amplifier, AM detector, AF amplifier, and earphone/speaker to the L1b coil winding.

How This Radio Project Came To Exist

Radio Shack began offering 7 electronic kits in 1968 that included all parts, hardware, and instructions in a plastic box. The circuit offered in the kit was assembled by the customer on a perforated prototyping board. The popularity of these kits resulted in an expansion of the product line to 22 kits in 1969, but the perforated board was replaced with a plastic box, called a "pbox", that served as the shipping container, the project breadboard, and the project enclosure all in one. This "space age" pbox turned out to be much easier for young people to work with, reduced the cost of the kit, and made the finished circuit easy to use and interesting to look at.


EEEEEE
RS3
PICTORIAL
SCHEMATIC

Science Fair™ AMERICA'S FAVORITE ELECTRONIC PROJECT KITS

INTRODUCING the Unique "P-Box"...

Each Science Fair kit is designed by Radio Shack engineers to let you build "like a Pro" — *by breadboarding*. Teachers help us write the instructions — *to let you learn as you build*. We include the extra parts that other kits omit. The result: a handsome product with *real utility*, at amazingly low cost. The entire package is useful: the clear top cover becomes the "bottom", the bottom becomes the perfboard chassis "top". We call it the *P-Box*. It's so great we've applied for a patent!

New Space-Age-Material "P-Box"
Withstands Soldering Without Damage!

With the P-box's remarkable new material, you can also use the direct heat and pressure of a soldering iron to cleanly cut any size openings. Permits remounting of parts and circuit changes. Be your own engineer! Add . . . Change your Science Fair™ Kits at will!

Each Kit is Complete – No Extras To Buy!

All necessary parts, detailed pictorials and schematic diagrams are included with each kit. Kits are designed with practical, straight-forward circuitry and are supplied with first quality components to insure top performance and lasting operation.

Ear-Piercing Electronic Siren Kit

- *Loud, Automatic "Rise-Fall Sound!*
- *Adjustable For Use On Bicycles!*

5^{95}

Simple micro-switch, when actuated, turns oscillator on at full blast.

28-107, Siren Kit, Wt. 1 lb. .... Net 5.95
23-468, AA Battery (4 Req. for portable use) .... Each .10
270-383, Battery Clip (for AA batteries above) .... Net .45
23-006, 6V Lantern Battery (Normal Use) .... Net 1.19
23-541, 6V Lantern Battery (Heavy Duty) .... Net 2.59

3-Transistor Short Wave Radio Kit

- *Tune in London, Moscow, Paris, Tokyo . . . The World!*
- *Complete with Earphone — Just Connect to Battery!*

7^{95}

The airwaves sing with signals from around the world, and they can all be yours! You'll marvel at the amazingly clear long range reception this kit provides. Its power comes from a regenerative high-gain detector with 2 high-gain audio amplifier stages. Complete with crystal earphone.

28-110, Wt. 1 lb. .... Net 7.95
23-464, 9 Volt Battery .... Each .29

2-Transistor Radio Kit

- *Tunes in the entire AM Broadcast Band!*
- *A Great Educator in Basic Solid State Electronics.*

3^{95}

You'll love hearing your favorite news, sports and music programs on a solid state radio you've built yourself! All it takes is one hour to easily assemble your radio. Use it as a tuner; installs anywhere. All parts, instructions, included.

28-102, Wt. 1 lb. .... Net 3.95
23-464, 9V Battery .... Net .29

FM Wireless Microphone Kit

- *"Broadcast" Your Voice Through any FM Radio!*
- *Great for Intercom, Paging, Party Fun, Too!*
- *Range: Up to 200 Ft. Response: 50-10,000 Hz!*

6^{95}

You can speak through this easy-to-build transmitter and be heard anywhere on the 88-108 MC FM dial! Speak long range from garage or shop, even listen to records over FM radio. Mike is sensitive enough to pick up sounds several feet away. All parts, instructions included. Put yourself "on the air" without wires!

28-109, Ship. wt. 1 lb. .... Net 6.95
23-464, 9 Volt Battery .... Each .29

18 More Science Fair™ Kits From Our Constantly Growing Selection!

1 Tube DC Radio Kit
Tunes in the entire 540-1600KC AM Band.
28-100, Radio Kit, 1 lb. Net 3.95
23-468, 1½V "AA" Bat. Net .10
23-097, 22½V Battery Net 1.35
3^{95}

Electronic Organ Kit
Plays real music on a seven note scale! Variable control changes musical key.
28-101, Wt. 1 lb. Net 5.95
23-464, 9V Battery Net .29
5^{95}

Wireless AM Mike Kit
Transmits through any AM radio up to 20 feet away!
28-103, Wt. 1 lb. Net 3.95
23-464, 9V Battery Net .29
3^{95}

AC/DC Power Supply Kit
Use with Science Fair Kits or any 6-9V project. Completely SAFE!
28-104, Wt. 1 lb. Net 6.95
6^{95}

3-Way Code Oscillator Kit
Learn Morse code the easy, fun way! Variable pitch—complete with speaker.
28-105, Wt. 1 lb. Net 3.95
23-468, 1½V Battery Net .10
3^{95}

"OTL" Audio Amplifier Kit
Hear hi-fi sound from tuners, mikes, and phono cartridges! Clean, powerful output!
28-106, Wt. 1 lb. Net 4.95
23-468, 1½V Battery Net .10
4^{95}

Bell/Buzzer Code Key
Teaches theory of electro-magnetism, multi-vibration and current flow!
28-112, Wt. 1 lb. Net 1.49
23-468, "AA" Battery Net .10
1^{49}

Stereo Amplifier Kit
Build you own stereo system around this powerful dual (OTL) amplifier.
28-113, Wt. 1 lb. Net 8.95
23-464, 9V Battery Net .29
8^{95}

Stereo Preamp Kit
Use with magnetic phono cartridges or as mike mixer. AVAILABLE SEPT. 16, 1968
28-114, Wt. 1 lb. Net 7.95
23-464, 9V Battery Net .29
7^{95}

Telephone Pickup Kit
Wireless magnetic pickup amplifier transmits both side of conversation thru speaker.
28-116, Wt. 1 lb. Net 6.95
23-464, 9V Battery Net .29
6^{95}

Fire Alarm Kit
Hear shrill alarm when temperature rises above 120°. Complete with heat sensor.
28-117, Wt. 1 lb. Net 4.95
23-464, 9V Battery Net .29
4^{95}

Super Snooper Kit
Hear through walls or voices at distances up to 200 ft. AVAILABLE SEPT. 16, 1968
28-120, Wt. 1 lb. Net 6.95
23-464, 9V Battery Net .29
6^{95}

VOM Meter Kit
All purpose electronic tester. Complete with comprehensive instruction manual for use and theory. Incl. battery.
28-122, Wt. 1 lb. Net 4.95
6^{95}

Metronome Kit
Produces steady beat (click) continuously adjustable to cover all musical ranges.
28-118, Wt. 1 lb. Net 3.95
23-464, 9V Battery Net .29
3^{95}

Extension Speaker Kit
Works with any 8Ω audio amplifier. Ideal for use with other Science Fair™ Kits. Incl. 6' cable.
28-123, Wt. 1 lb. Net 1.95
1^{95}

Photo Electric Nite Lite Kit
Turns light on automatically when room is darkened. One "C" cell required.
28-126, Wt. 1 lb. Net 3.95
23-467, "C" Cell Net .15
3^{95}

2-Way Intercom Amplifier Kit
Sensitive Pair-a-Phase amplifier for 2-way conversations at amazing distances.
28-127, Wt. 1 lb. Net 5.95
23-464, 9V Battery Net .29
5^{95}

Light-Operated Alarm Kit
Produces loud alarm when light source is interrupted. 4 1½V batteries required.
28-128, Wt. 1 lb. Net 4.95
23-468, 1½V Batt. Net .10
4^{95}

www.RadioShackCatalogs.com

By the early 80's, however, Radio Shack had become a struggling consumer electronics retailer and most of the kits and component parts were discontinued. While rummaging around in a local Radio Shack store after school I happened to find a 3 Transistor Short Wave Radio kit in a bargain bin, bought it, and assembled it with great pleasure.



3 TRANSISTOR

SHORTWAVE RADIO KIT

Tune in world-spanning SWL bands 2 to 30 megacycles hear London, Moscow, "hams", ships, planes! Regenerative solid state circuit. Headphone included. May be used as radio or tuner. New P-Box® construction.

KIT NO. 28-110

$7.95

Requires one 9V Battery 23-464 (Not included)

INCLUDES: PICTORIAL/SCHEMATIC/NUMBERED INSTRUCTIONS

I remember being amazed how well the radio worked using only the 10ft antenna wire supplied in the kit. Unfortunately, I do not remember what happened to the kit after it was completed. Recently I was designing and building a 40 meter SSB receiver and experimenting with software defined radio, and was describing to a friend the complexity of a modern radio receiver. It was then I thought of my old radio kit and how well it was able to operate with only three transistors and a 9V battery. Yes it was fiddly and hard to tune and you had to hold your hand in just the right place to stay in tune, but it could really pick out a long distance station. But then again, maybe my memory was off. I was a kid back then and it WAS the 80's so maybe it didn't really work as well as I thought. If only I could build it again. Alas, pbox kits had fallen into the abyss of the occasional outrageous eBay auction.

But... If I could find the original schematic perhaps it would be possible to redesign the kit to use silicon transistors. Maybe use some better knobs. I always felt like the original kit could have used some better knobs. And those original spring clips tarnished quickly. I began searching for information on the Radio Shack pbox kits and found a web site run by Steven Vornsand at www.sparktron.com (http://www.sparktron.com) that contained complete information on as many of the kits as were known to exist. A Google search turned up two companies that sold a compact variable capacitor (www.uxcell.com (http://www.uxcell.com)) and crystal earphone (www.amplifiedparts.com (http://www.amplifiedparts.com)) that were critical components for the vintage-like operation of the radio design. So my first step was to reset the bias for the AF amplifier and AM detector which used old germanium transistors. Simulation and prototype construction revealed that the updated circuit with 2N3904 transistors worked slightly better than the expected performance of germanium transistors in the original circuit. The next step was to confirm that the 2N3904 could also be used in the regenerative RF amplifier section without change. Simulation and prototype construction also revealed a better than expected result. For tuning, I discovered that by eliminating the scaling capacitors from the original design the variable capacitor from Uxcell could then be used without having to change the winding dimensions of the air core tuning inductor. Last, I added an earphone jack (the AmplifiedParts earphone comes with a 1/4" plug) and some mini dual-position barrier strips to connect power, inductor, and antenna. Just for fun, I packaged up all the parts like a kit and assembled the final version presented in this article.

After building the radio I've successfully received WWV on 5, 10, 15, and 20 Mhz with good copy. I've picked up all the well-known short wave KW transmitters from around the globe. And I've picked up SSB on 7Mhz and 14Mhz. SSB can be received but the detector is not designed to clearly demodulate it. I remember that happening with the original kit.

I'm extremely happy with how the 3 Transistor Short Wave Radio looks and how well it pulls in distant stations.

How The 3 Transistor Short Wave Radio Works

The 3 Transistor Shortwave Radio in this article is a regenerative radio designed to tune from 2Mhz through 30Mhz depending on the tuning coil used by the operator. The schematic for the radio with the major building blocks highlighted is illustrated below:


9V+
C6
.01µF
R5
33K
C7
47µF
R8
12K
C9
.1µF
R12
2.7K
C11
10µF
Tuning
C5
L1
5pF-140pF
Air Variable
25 Turns
(See Manual)
C8
.047µF
R7
100K
Pot
Volume
ANT
C4
15pF
R4
100K
Q1
2N3904
C3
47pF
RF Amplifier/
AM Detector
500 Ohm
Pot
Regen
C1
.01µF
R1
33K
R2
R3
1K
C2
47pF
GND
R6
2.2K
2N3906
Q2
2N3906
Q3
AF Amplifier
R9
22K
R10
47K
R11
10K
PHONE
PHONE
9V-

Variable capacitor C5 and tuning coil L1 comprise the Tuning section. L1 is a fixed inductor wound according to the assembly manual for the frequency band of interest.

The RF Amplifier/AM Detector section is actually a Colpitts Oscillator with an added variable resistor R2 that serves as the regeneration control. Resistors R1 and R4 provide base voltage to Q1 so that it's collector is fixed at approximately 3V. This collector voltage was chosen so that the RF Amplifier/AM Detector will continue to operate properly as the 9V battery reaches the end of it's life. The large values of R1 and R4, and the bootstrap bias configuration they are connected in, were chosen so that the RF Amplifier/AM Detector will have a high input impedance which improves the selectivity and sensitivity of the radio. Capacitors C1 and C6 were included to bypass RF around resistors R1 and R5 respectively which improves the gain of the RF Amplifier circuit. The collector output of Q1 is fed back to the emitter of Q1 through capacitors C2 and C3. Normally this positive feedback would cause the RF Amplifier/AM Detector to continuously oscillate. However the regeneration control provides an adjustable amount of negative feedback at the emitter of Q1 that counteracts the positive feedback. By carefully adjusting the amount of negative feedback on the emitter of Q1, the circuit can be made to provide extremely high gain just before oscillation occurs, and at the same time remove most of the RF Carrier signal and the unwanted image of the audio signal. This behavior is the reason the regenerative radio works so well.

The AF Amplifier is a simple two-stage direct coupled Common Emitter amplifier for driving the crystal earphone. Transistor Q2 provides a gain of approximately 5 and together with R10 and C9 performs additional filtering of the carrier signal. Transistor Q3 provides a gain of approximately 100 (the transistor current gain at .5mA). Capacitor C11 is provided to bypass audio frequencies around resistor R12 and improve the gain of Q3. Together, Q2 and Q3 provide an additional gain of approximately 500 after the RF amplifier. The value of R12 was chosen so that the collector voltage of Q3 would be set at approximately 1/2 battery voltage which ensures that the Detector and AF Amplifier will continue to operate properly as the 9V battery reaches the end of it's life.

Capacitor C7 and resistor R6 are wired together as a simple RC Low Pass Filter to prevent RF noise at the RF amplifier from bleeding into the AF amplifier via the battery connections.

How to build the 3 Transistor Short Wave Radio

To build the radio described in this article, you will need the revised assembly manual I've created which include the design and layout changes I've made.

> Click Here to obtain the assembly manual < (/images/swradio/swradio.pdf)

Here's a few other things:

1. The transistors for the radio can be purchased from Amazon.com or Radio Shack (assuming they are still in business in your area). I highly recommend the excellent Joe Knows Electronics semiconductor kit. It includes the transistors you need for this radio project and over 150 different types of transistors and diodes for just $22. And it includes a set of documents that are really good reading for the beginner. Check out www.joeknowselectronics.com (http://www.joeknowselectronics.com). You will not be sorry.
2. The resistors for the radio kit can be purchased from Amazon.com or Radio Shack. Radio Shack has a good selection of 1/4W resistors in a big 500 piece bundle for about $15.00 if you have a store nearby. Joe Knows Electronics also has a nice 800 piece package of 1% resistors for $12.00 if you don't mind ordering online. Joe's is a really good and well organized kit even if 1% resistors are a bit of tolerance overkill for this radio project.
3. I strongly recommend ordering NP0 ceramic disk capacitors from www.mouser.com (http://www.mouser.com) or www.digikey.com (http://www.digikey.com) as they will far outperform most anything you can get on Amazon.com. The Joe Knows Electronics capacitor kit is an extremely good buy for every other capacitor at 645 pieces for $13.00. Don't bother with Radio Shack for capacitor kits as they are mostly junk values you will never use.
4. I purchased several crystal earphones from www.amplifiedparts.com (http://www.amplifiedparts.com) on Amazon.com and they work great despite the poor reviews. Whatever quality problem they had in the past seems to have been ironed out.
5. The variable capacitor (and a lot of other rather old and interesting parts) can be found at www.uxcell.com (http://www.uxcell.com) which seems an unlikely domain for radio stuff but they do have a lot of radio stuff that's interesting. I've created a diagram of the variable capacitor **>> here << (/images/swradio/variable-cap.pdf)** that will help you figure out how to wire it in the radio.
6. The case for the kit I built is a Hammond 1591GSBK ABS Project Box from Amazon.com with a piece of vector breadboard cut to fit on the top and spray painted with high temperature automotive flat red. I like the look of red on black, and the red color of the breadboard matched the red color of the original pbox kit. It's completely up to you how you want to house and color the kit you build.
7. The knobs I used are Radio Shack knobs I've had in inventory for decades. Use anything you think is cool that will fit on the pot/varicap shafts.
8. You will need to be creative on how you mount the variable capacitor on the vector board. I used a piece of 1/32" sheet metal cut to size with a Dremel tool grinding wheel and then drilled the holes to mount the variable capacitor with a power drill. Then I bent the end of it 90 degrees to form an L shape. This is the most challenging part. But I am sure you can overcome this minor obstacle being the resourceful person you naturally are.
9. You will need to be creative on how you mount the tuning knob to the variable capacitor. The shaft on the varicap is only about 1/4" long so you will need something to extend it. I found a plastic cylinder with a hole drilled through it that was about 1" long at my local Ace hardware store. They have a really nice selection of odd hardware that is very useful. Again... be resourceful and look for a solution in unexpected places that will work. That's some of the fun of a project like this.
10. The 2-position barrier strips are available from Radio Shack in a pack of four. These are a great value at the price so if your local Radio Shack hasn't yet been turned into a Sprint cell phone shop you should definitely buy all of the packs on the peg. I know I did.

When it comes to wiring, try to be as neat as I've indicated in the assembly manual. You don't have to be the world's best soldering artist but there's no good reason to do the work half-way. Go all out and make your radio look as good as you can. Here's what mine looks like from below:



In hopes of helping out, I've included a parts legend so that you can see where the components are supposed to go when the breadboard is turned over. When it comes to RF work, keep it short and keep it neat is good advice. Do what I did above and your radio will exceed your expectations.

One final note:

Any radio is only as good as it's antenna and the environment it is in. In my area, everybody and his extended family has a wireless router, 4 cell phones, three LCD TV's, and who knows what else making more electronic noise than a chicken coop surrounded by a family of foxes (Sorry, I couldn't help but include at least a little bit of classic Southern humor). A good antenna as described in the Assembly Manual is essential for getting the best performance from this radio project. I brought my radio out to rural Anacoco, Louisiana and attached a 10ft wire antenna to a clothes line, and received more stations than I had time to listed to. I was amazed at how well this little radio performs. If you don't know what a clothes line is, you probably don't live in rural Louisiana, and that's totally OK. Lets just say an electrically quiet environment also helps.

I hope you have as much fun working on this project as I did. Good luck and good listening!


0
1
2
3
4
5



REGEN
PARTS LIST
TUNE
R2
C5
C6
R5
Desc
Quantity

50 Comments www.netzener.net 1 Login

♡ Recommend 5 Share Sort by Best

Join the discussion…

LOG IN WITH

OR SIGN UP WITH DISQUS ?

Name

Germain Guérin • 24 days ago

Aug 2000 *QST* - Copyright © 2009 American Radio Relay League, Inc. - All Rights Reserved

By Rick Littlefield, K1BQT

A Wide-Range RF-Survey Meter

Find and measure the presence of RF energy over a 500-MHz range with this inexpensive, easy-to-build meter.



JOE BOTTIGLIERI, AA1GW

This handy RF-survey meter measures signal levels from −70 dBm to +10 dBm over a 500-MHz frequency range. The detector's wide response and pocket-size portability make it useful for design work and bench-testing, RFI hunting, EMR hazard detection, fox-hunts, surveillance sweeps and many other tasks around the shack and in the field—and it's cheap and easy to build!

Circuit Description

The heart of this project is U1, Analog Device's AD8307 wideband detector IC (see Figure 1). This eight-pin device is a specialized instrumentation chip that accurately reads RF levels over a huge 92-dB signal range, then generates a 0.5 to 2.5-V dc log-output signal to drive a signal-strength indicator. It works a bit like the RSSI (received signal-strength indicator) feature found on many FM receiver ICs, but covers a frequency range spanning VLF to over 500 MHz with a virtually flat response.[1] The IC's logarithmic output is important because it permits us to use a linear-scale voltage display to indicate signal strength in decibels (dB) or decibels referenced to a milliwatt (dBm)—just like a spectrum analyzer.

U1's output feeds an LM3914 LED driver (U2) that controls the meter's 10-segment color-coded LED array. The first LED lights with no signal present to function as a power-on and battery status indicator. The remaining nine LEDs illuminate sequentially, in 10-dB increments, as signal input increases over U1's 90-dB measurement range. U2 is configured in the bargraph mode, which means the LEDs illuminate collectively as the reading increases. This mode draws a bit more operating current than the single-LED mode, but yields a far more colorful and easy-to-read display. To compensate for increased current drain, a momentary press-to-test power switch is used to conserve power anytime measurements aren't being taken. I chose the solid-state LED array over an electromechanical meter because it delivers sufficient accuracy for casual survey work, and because it is virtually bulletproof.

Do you need greater resolution? The AD8307's accuracy is within 1 to 2 dB over its entire dynamic range and could be used to drive a more sophisticated display consisting of a dc-amplified large-scale meter or a recalibrated DVM module. For more complete technical information, data sheets and application notes are available at Analog Device's Web site: **http://www.analog.com/logamps**.

Construction

Nearly all of the parts required to build this project are readily available at your local RadioShack store or can be ordered via RadioShack's Web site **http://www.radioshack.com**. PC boards are available from FAR Circuits,[2] and single quantities of the AD8307s can be purchased from me.[3]

Assembling the meter is simple. The only tricky operation I encountered was mounting the LEDs at the correct height to mate with the panel openings. I solved this problem by making a small spacer-gauge from a scrap of PC board and slipping it under each LED during soldering. Spacing may vary slightly, depending on the LED manufacturer. The LED array is much easier to make if all the diodes are manufactured by the same company and have identical case styles. When mounting capacitors, lay C5 on its side so it clears the front panel. Use caution when installing U1. The AD8307 is static-sensitive, so use a wrist strap, a grounded soldering iron and standard CMOS-IC handling precautions.

Testing and Final Assembly

Perform the initial testing and calibration before mounting the PC board in its case. Attach a fresh 9-V battery to the snap clip. If you don't have a precision signal generator available, apply power and adjust the **ZERO** trim pot (R2) so only the first red LED illuminates. This will provide a rough calibration, and your meter will be

---

[1] Notes appear on page 44.

Aug 2000 *QST* - Copyright © 2009 American Radio Relay League, Inc. - All Rights Reserved

A Current Probe for the RF-Survey Meter

This little meter can be a useful accessory for the home experimenter. Microwattmeters can be quite expensive, even if they're used equipment. For example, this meter can be used to indicate the power from an LO in a receiver or transmitter design.

Microwattmeters also have other uses. With a small whip antenna (ie, a "rubber ducky"), the meter can be used as a relative field-strength indicator. With a rubber ducky, W1AW's signal registered at about half scale as I wandered, meter in hand, around ARRL HQ and the grounds. (HQ staff are used to seeing Lab personnel running around doing all sorts of weird things.) Be careful not to place the meter too close to an antenna, though; it is possible pick up too much RF and possibly damage the meter.

Several companies now sell hand-held current probes based on technology similar to that used in this project. Those probes have a current probe composed of a small clamp-on ferrite bead wrapped with a few turns of wire. The meter then can be used to accurately measure small RF currents and as a relative indicator of the amount of RF noise present on computer cables, the outside of a coaxial cable, telephone wiring, etc.

The commercial units I've seen have the ferrite probe mounted directly on the meter. Although this is handy, it can make the meter awkward to use in tight quarters. To measure noisy cables, I want something a bit more portable. I considered using various spring-type clamps available at hardware outlets, but they all seemed far too springy. As I strolled through the tool department at Lowe's, the Vise Grip clamp shown in Figure A caught my eye. The flat parts of the clamp seemed perfectly suited to the task I had in mind. The ferrite beads with plastic covers used here are available from Palomar Engineers, PO Box 462222, Escondido, CA 92046; tel 760-747-3343; **palomar@compuserve.com, http://www.palomar-engineers.com/** and from RadioShack (RS 273-104).

Table 1

Signal levels falling within the survey meter's range span a 90-dB range.

Power (dBm)	*Power (W)*	*Approximate Potential Across 50 Ω*
+10	10 mW	1 V
0	1 mW	300 mV
–10	100 µW	100 mV
–20	10 µW	30 mV
–30	1 µW	10 mV
–40	100 nW	3 mV
–50	10 nW	1 mV
–60	1 nW	300 µV
–70	100 pW	100 µV

To build the probe, first trim the latch on the ferrite bead's plastic housing so that the sections no longer snap together. Use a few dabs of epoxy to hold each half of the bead to the Vise Grip clamp, as shown in Figure B. (Be careful not to get any glue on the ferrite material.) The clamp's flat sections are perfectly suited for this arrangement; other clamps don't have these flats. Once the glue sets, carefully pry out one ferrite section from the plastic housing. Wrap three to five turns of small enameled wire (#28 will do) on the bead half, leaving about 3/8 inch of wire for leads. Using a small dab of glue to hold it in place, press the bead back into its housing.

Remove about 3/16 inch of insulation from each of the probe's wire ends and solder them to a short length of RG-58 coaxial cable. Cover each lead connection with a length of heat-shrink tubing or insulated sleeving. Install a BNC male connector at the cable's other end. I used a couple of small plastic ties to secure the coax to the clamp; see Figures A and B. (For photographic purposes, I didn't add the heat-shrink tubing.) The probe is now ready to use.

To use the probe, adjust the Vise Grip clamp carefully so that the probe's ferrite sections *just* close when the clamp is squeezed. (Excessive closing pressure may damage the ferrite sections. Once the proper adjustment point is reached, consider locking the adjustment screw in place with epoxy or using a jam nut.) Clamp the probe over the cable you're checking. With four turns of wire on the bead, the cables on several computers at HQ just lit the meter's yellow LEDs. Significantly noisier computers lit the meter's red LEDs, indicating that those cables could be a source of RFI. If desired, you can calibrate the probe/meter combination using a signal generator and a 47-Ω resistor to create a known current.

Microwattmeters can be useful pieces of test equipment for the RF designer. New microwattmeters cost several thousand dollars. This project can get you nearly the same performance at a lot lower cost.—*Ed Hare, W1RFI, ARRL Laboratory Supervisor*



Figure A—A handy probe is made by attaching the two halves of a modified ferrite core to a Vise Grip clamp. Plastic ties secure the cable to the clamp.



Figure B—Close up view of the modified ferrite core wound with a few turns of enameled wire.

reasonably accurate for most survey tasks.

If you have access to a signal generator, install two short leads on the BNC connector and tack-solder them temporarily to the PC-board-input connections. With power applied and nothing connected to the BNC connector, adjust R2 so the first LED illuminates. Then, set the generator for CW output at 100 MHz and connect its patch cable to the BNC jack. Reset R2, as needed, so the last LED just illuminates with +10 dBm of signal applied. When calibrated, reducing the generator's output in 10-dB increments should extinguish one LED per step. If the bargraph reading doesn't change reliably with each step change between +10 and –60 dBm, reset R2 slightly until it does. Note that the low-level green LED (–70 dBm) may remain on continuously because of stray RF pickup on the generator cable.

Once alignment is complete, remove the BNC connector and install the PC board in its case. Secure the PC board in position by the **POWER** switch, omitting the switch's lock washer when installing. Make sure all LEDs are seated in the case openings before fully tightening the switch's mounting nut. Install the BNC connector in its panel and, using short leads, permanently connect it to the PC board.

Operation

Avoid connecting this meter to signal sources more powerful than +20 dBm (100

Aug 2000 *QST* - Copyright © 2009 American Radio Relay League, Inc. - All Rights Reserved


S1
Test
BT1
9 V
C4
0.1
R1
390
C5
10 µF
16 V
C1
0.1
J1
Input
C2
0.001
D2
D3
2 × 1N4148
R2
100 k
CAL
D1
5.1 V
500 mW
U2
LM3914
DS1
8 INP 7 VPS 6 ENB 5 INT
INM COM OFS OUT 1 2 3 4
U1
AD8307
R3
22 k
R4
4.7 k
C1
0.1
n.c.
C3
0.1
1
2 V−
3 V+
4 RLO
5 SIG
6 RHI
7 REF OUT
8 REF ADJ
9 MODE
18 17 16 15 14 13 12 11 10
R5
4.7 k
R6
3.9 k
C7
0.1
DS10
Red (Power On)
Green (−70 dBm)
Green
Green
Yellow
Yellow
Yellow
Red
Red
Red (+10 dBm)
Except as indicated, decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); resistances are in ohms; k = 1,000.
n.c. = Not connected

Figure 1—Schematic of the RF-survey meter. Unless otherwise specified, resistors are ¼-W, 5%-tolerance carbon-composition or film units. Part numbers in parentheses are RadioShack; numbers with 900 prefix are for RadioShack's on-line catalog (http://www.radioshack.com). Equivalent parts can be substituted; n.c. indicates no connection.

C1, C3, C4, C6, C7—0.1 µF disc ceramic
C2—0.001 µF disc ceramic
C5—10 µF, 16 V electrolytic or tantalum
DS1, DS8-DS10—3 mm LED, red (900-6085)
DS2-DS4—3 mm green LED (900-6086)
DS5-DS7—3 mm yellow LED (900-6087)
D1—1N5231B, 5.1 V, 500 mW Zener diode (900-3088)
D2, D3—1N4148
J1—BNC chassis mount connector (RS 278-105)
R2—100 kΩ, 6-mm horizontal-mount trim pot (RS 271-284)
S1— SPST momentary, normally open switch (RS 275-1571)
U1—Analog Devices AD8307
U2—National LM3914 (900-6840)
Misc: Case—2¾×4⅝×1-inch (HWD) box with 9-V snap clip (RS 270-211)

mW) without first installing an attenuator or sample tap to reduce the input to a safe level. To operate your meter, press the TEST switch and observe the bargraph display. If the lowest segment fails to illuminate, check the battery condition before proceeding. The meter draws approximately 20 mA (depending on how many LEDs are lit), so frequent use will necessitate periodic battery replacement.

When making measurements, remember this is a basic survey tool designed for gathering ballpark indications rather than precise data. Also, as with any broadband device, it cannot discriminate between narrowband and wideband energy sources or tell you the frequency of an applied signal. Finally, remember that the dBm is a unit of RF power referenced to a 50-Ω load. The unterminated input impedance of U1 is approximately 1 kΩ at 100 MHz, so readings taken across unknown loads will be *relative* indications that are comparable in dB, but not absolute values in dBm.

Summary

This simple hand-held project uses a low-cost instrumentation IC to detect the presence of RF energy over a 500-MHz range. Approximate signal intensity is displayed on an easy-to-read LED display, and a wide range of sampling attachments may be used for picking up signals. I find I use it often, both on the bench and in the field, whenever I need a quick "reality check" for the presence of RF. It's especially useful for tracking down RFI sources, as Ed (W1RFI) Hare's sidebar, "A Current Probe for the RF-Survey Meter," illustrates.

Notes

[1] Rick Littlefield, K1BQT, "The Analog Devices AD8307 92-dB Logarithmic Amplifier," *Communications Quarterly,* Summer 1999, pp 77-80.

[2] A PC board is available from FAR Circuits, 18N640 Field Ct, Dundee, IL 60118-9269, tel 847-836-9148 (voice and fax). Price: $4 plus $1.50 shipping for up to four boards. Visa and MasterCard accepted with a $3 service charge; **http://www.cl.ais.net/farcir/**.

[3] Contact the author for information.

Rick Littlefield, K1BQT, is an Extra Class licensee and active ham since 1957. An avid builder, RF-product designer and author, he's written for a wide range of Amateur Radio publications since 1969, and was inducted into the QRP-ARCI Hall of Fame in 1996. Rick holds a Master's Degree from the University of New Hampshire and currently works as a technical writer in the electronics industry. You can contact Rick at 109A McDaniel Shore Dr, Barrington, NH 03825; **k1bqt@aol.com**.

NEW PRODUCTS

SURACE-MOUNTED DEVICES PROJECTS MANUAL

◊ Howard W. Sams and Company and Prompt Publications present *SMD Electronic Projects*, by Homer Davidson. This 320-page book covers 30 electronics projects, all employing surface-mount components.

Projects include an earphone radio, a crystal receiver, a shortwave receiver, an IC radio, a shortwave converter, an FM radio, an active antenna, an RF amplifier, a sideband adapter, a code oscillator, an electronic timer, a signal injector, an audio generator, a crystal checker, various recorders and 15 more.

Parts lists, schematics, wiring hookup diagrams, board layouts, photos and drawings help to illustrate each of the projects. Troubleshooting procedures are also provided.

Price: $29.95. For a more complete description of this book and a tremendous assortment of additional electronics-related publications, visit **http://www.hwsams.com** or contact the publisher directly: Howard W. Sams and Company, 2647 Waterfront Pkwy E Dr, Indianapolis, IN 46214; tel 317-298-5789; fax 800-552-3910.

Next New Product

The HF Current Probe: Theory and Application

KENNETH WYATT
Wyatt Technical Services
Woodland Park, Colorado, USA

This article describes one of the most valuable tools in the EMC engineers "bag of tricks" – the high-frequency current probe. Current probes are invaluable for measuring high-frequency common-mode (or "antenna") currents flowing on wires or cables. Experience has proven that poorly terminated (bonded or filtered) cables are the number-one cause for radiated emissions failures at a test facility. By measuring the common-mode (CM) currents (sometimes referred to as "antenna" currents) on these cables it's possible to troubleshoot and apply fixes to a product right there in your development lab. You can also predict, to a good degree of accuracy, whether a given cable current will pass or fail in the measurement chamber. This will save you tons of time trying to apply fixes at the test facility while the clock is ticking away your test time. I'll also show you several ways to create do-it-yourself (DIY) probes that are quick to make and very useful in a pinch.

COMMON-MODE CURRENTS

Let's consider CM currents and how they are generated, because it is not intuitive as to how current may travel the same direction through both the signal and signal-return wires in a cable or PC board. Referring to Figure 1, note that due to finite impedance in any grounding system (including circuit board signal/power return planes), there will be a voltage difference between any two points within that return plane. This is denoted by V_{GND1} and V_{GND2} in the figure. This difference in potential will drive CM currents through common cabling or circuit traces between circuits or sub-systems. In addition, unbalanced geometries - for example, different lengths or path routings for high-speed differential pairs - can create voltage sources that drive associated CM currents. Finally, routing a high-speed clock trace across a split in the return plane or referencing it to multiple planes, can also be a source of CM current. Because the current phasors in Figure 1 are additive, the resulting radiated phasor may be quite large compared to those generated by differential-mode (DM), or signal currents, which are opposite in direction, and so tend to cancel. Therefore, CM emissions tend to be more of an issue than DM emissions.

CURRENT PROBES: THEORY OF OPERATION

The RF current probe is an "inserted-primary" type of radio frequency current transformer. When the probe is clamped over the conductor or cable in which current is to be measured, the conductor forms the primary winding. The clamp-on feature of this probe enables easy placement around any conductor or cable. This is essentially a broadband high-frequency transformer. High-frequency currents can



Figure 1. *Common-mode currents in a circuit loop. The source is a digital signal (with harmonics) and we'll assume a resistive load. Because the phasor current in the far wire is in the same direction as the phasor current in the near wire, the resultant phasor is relatively large compared to that produced by differential-mode current phasors. In this case, lowering the harmonic content (by slowing the digital rise/fall-times) or diverting/blocking the CM current is very important in limiting radiated emissions.*

be measured in cables without physically disturbing the circuit.

Since the current probe is intended for "clamp-on" operation, the primary shown in Figure 2 is actually the electrical conductor in which CM currents are to be measured. This primary is considered as one turn since it is assumed that the CM currents flow through the conductor and return to the source via a return conductor such as a frame, common ground plane, or earth. On some current probe models the secondary output terminals are resistively loaded internally to provide substantially constant transfer impedance over a wider frequency range.

COMMERCIAL CURRENT PROBES

While commercial current probes are pricey, the advantage is that they can open up and snap around a cable, rather than having to be threaded onto the cable to be measured. See Figure 3. They are also a lot more rugged and can take a lot of abuse as compared to the "do-it-yourself" (DIY) versions below. Finally, they are also accurately characterized, allowing very precise measurements of cable currents.

DIY CURRENT PROBES

In a pinch, you can make your own current probe. Examples of several DIY probes are shown in Figures 4 and 5. I typically try to find a ferrite toroid or clamp-on core that offers good high-frequency characteristics in the 10 to 1000 MHz range. Winding a few (not too critical) turns and terminating with a coax connector is all you need. Keeping the turns as far apart as possible (as in Figure 4) will reduce inter-winding capacitance and yield better results at the higher frequencies. This is one of the largest drawbacks in performance of the clamp-on ferrites (as in Figure 5).

TRANSFER IMPEDANCE

The CM current (Ic) in microamps in the conductor under test is determined from the reading of the current probe output (V) in microvolts divided by the current probe transfer impedance (Zt).

$$I_C = V/Z_T \qquad (1)$$

Or, in dB

$$I_C(\mathrm{dBuA}) = V(\mathrm{dBuV}) - Z_T(\mathrm{dB\Omega}) \qquad (2)$$

The typical transfer impedance of the current probe throughout the frequency range is determined by passing a known RF current (Ic) through the primary test conductor and noting the voltage (V) developed across a 50-Ohm load. Then,

$$Z_T = V/I_C \text{ (in standard units)} \qquad (3)$$

Or

$$Z_T(\mathrm{dB\Omega}) = V(\mathrm{dBuV}) - I_C(\mathrm{dBuA}) \qquad (4)$$

The Fischer F-33-1 probe is a commonly used troubleshooting tool and has a flat frequency response from 2 to 250 MHz (Figure 6). The transfer impedance is about 5Ω (approximately +14 dBΩ on the graph), therefore, a 1 uA current will produce a 5 uV output voltage from the current probe.

PROBE CALIBRATION

The accurate calibration of RF current probes is a complex process. Characterization is a more correct term to use than calibration. The probe must be properly characterized to reflect how the user uses the probe. Probe manufacturers usually sell a calibration fixture that attempts to maintain a 50Ω impedance. A 50Ω load is connected to the output port and a calibrated RF generator (or network analyzer) is connected to the input port. The probe to be characterized is clamped around the fixture and the frequency is swept while measuring



Figure 2. *The basic current probe (high-frequency current transformer).*



Figure 3. *Examples of commercial current probes.*



Figure 4. *Examples of DIY current probes based on a large toroid core. These photos were taken prior to installing the E-field shield which consists of a layer of copper tape over the windings, leaving a small gap around the inside of the toroid. 14 turns of Teflon-insulated wire wound around a Würth Electronik #74270097 ferrite core (4W620 material) was used, which is useful from 10 to 1000 MHz.*

the probe output.

My test setup was a little more rudimentary (Figure 7), but for troubleshooting purposes, it's good enough. I used a short piece of stiff wire across the output port with a 50Ω resistive load in series. I then adjusted the generator for zero dBm – a convenient amount. This is equivalent to an output voltage of 224 mV (or 73 dBuA of current) into 50Ω. The actual generator output doesn't matter, so long as the resulting probe voltage is large enough to be seen readily in the receiver or spectrum analyzer. I monitored the probe output with a Thurlby Thander TTi PSA2701T handheld spectrum analyzer.

Knowing the current through the wire in dBuA and the probe output in dBuV, the transfer impedance may be plotted graphically by subtracting: V(dBuV) – Ic(dBuA) (expressed in dB). In this case, ZT(dBΩ) = V(dBuV) – 73. While this may be useful for educational purposes, I wouldn't be too inclined to use the DIY probes to predict "pass/fail", as described further down. However, because they compare favorably to the commercial probes as far as output voltage, I believe (and have proven in practice) that they are completely suited for troubleshooting. You only need to know whether an EMC design fix made the cable current better or worse.

PREDICTING PASS/FAIL

It is possible to predict whether a particular cable will pass or fail radiated emissions by measuring the CM current at the offending frequency, reading off the transfer impedance of the probe, Zt (dBΩ) in Figure 6, and solving for Ic (using Equation 2 above). Plugging Ic(Amps) into Equation 5 will calculate the E-field level in V/m. The length of the cable is L(m) and the offending harmonic frequency is f(Hz). Use a test distance, d, of either 3 or 10m to predict the outcome at those test distances.



Figure 5. *Examples of DIY current probes based on clamp-on ferrite chokes. I used a couple sample Steward (now a unit of Laird Technologies) chokes – a round one (model 28A3851-0A2) and a square one (model 28A2024-0A2). They each had 7 turns of Teflon-insulated wire wound around one-half and glued down on the inside to hold the windings. I later epoxied a PC board-style BNC connector to the outside, making sure there was enough epoxy to hold the outer turns together. Type 28 material was used, which is useful from 10 to 1000 MHz.*



Figure 6. *Transfer impedance (ZT) graph of an F-33-1 current probe (courtesy of Fischer Custom Communications). The x-axis is frequency, while the y-axis is dBΩ. Use this to calculate the value of Ic (Equation 2), given the measured voltage at the probe terminals* (V_{dBuV}) *and ZT.*



Figure 7. *I used a short wire and 50Ω load (two parallel 100Ω resistors) across the generator output for probe characterization. Obviously, there are shortcomings at higher frequencies, due to the inductance of the wire. In fact, the system impedance starts to go capacitive at 100 MHz and it's difficult to keep a fixed 224 mV across the load resistor with frequency.*

$$\left|\hat{E}_{C,\max}\right| = 1.257\times10^{-6}\frac{\left|\hat{I}_C\right| fL}{d} \qquad (5)$$

Once you've determined a particular cable has CM currents that may cause a RE failure, you should to examine the connector where the cable is attached to the product enclosure. Very often, I find poor or non-existent bonding between the connector shield and enclosure shield. These points must be bonded well to permit the CM currents to flow back to their source within the product, avoiding associated cable radiation. Please refer to my previous articles on troubleshooting radiated emissions for more information (references below).

REAL-WORLD TROUBLESHOOTING EXAMPLE

As previously mentioned, one of the most common sources of radiated emissions is due to poorly bonded connectors mounted on shielded product enclosures. This occurs especially if the connectors are circuit board mounted and penetrate loosely through the shielded enclosure. Poorly bonded connectors allow internally generated CM currents to leak out and flow on the outside of I/O, mouse or keyboard cables. This will also allow ESD discharges inside the product – more bad news. If these currents are allowed out of the enclosure, the attached cables will act as radiating antennas – often resonating around 300 MHz, due to their typical 1m length.

This was the case for a new digitizing oscilloscope prototype I worked on recently. The I/O connectors were all soldered onto the PC board and the board was fastened to the rear half of the enclosure. The connectors simply poked up through cutouts in the rear metal shield.

While using a current probe to measure the CM current flowing on the outside of the USB cable under test, I simply jammed the screwdriver blade of my Swiss Army knife between the connector bonding fingers and metal chassis enclosure and was able to drop the overall cable currents by 10 to 15 dB.



Figure 8 *Transfer impedance (ZT) graph of a commercial current probe versus the DIY toroidal probe. The x-axis is frequency, while the y-axis is dBΩ. Note that the commercial probe is only designed and characterized to 250 MHz, so the data above that, while interesting, is probably not valid. The DIY probe, as well, performs poorly above 200 MHz and frankly, the wire loop used to introduce a "calibrated" current (while as short as possible) affects the measurement, as well.*



Figure 9. *Probe output voltage (V_{out}) graph of a commercial current probe versus the DIY toroidal probe. The x-axis is frequency, while the y-axis is dBuV. This shows that the probes are very comparable in output voltage versus frequency. For troubleshooting purposes, absolute accuracy is not required - just consistency in measurements. All one really needs to know is, "did the fix I implemented make the CM current go up or down?" The DIY probe works well for this.*



Figure 10. *Probe output voltage (V_{out}) graph of a commercial current probe versus two DIY toroidal probes and two different clamp-on probes. The x-axis is frequency, while the y-axis is dBuV. This shows that all these probes are very comparable in output voltage versus frequency and therefore, useful for troubleshooting purposes. Just don't try using the DIY probes to determine "pass or fail" predictions. Commercial probes are better-suited for that.*

The solution was to fabricate a custom shim with spring-fingers that would slip over all the connectors creating a firm bond between the connector ground shell and inside of the shielded enclosure. More and more low-cost products are relying on PC board mounted I/O connectors as a cost-cutting measure. Any time you see this, be prepared to carefully examine the bonding between the connector ground shell and the shielded enclosure.


Looking from 500 to 1000 MHz
Start:500.000MHz Stop:1000.000MHz
M1:562.5000MHz -70.6dB
Sweep:Normal Atten:Off
Markers: M1 active
M1:562.5000MHz -84.0dB
Sweep:Normal Atten:Off
Markers: M1 active
Before
After
Some harmonics dropped by 10-15 dB!
Test setup:
Current probe on USB cable.
Connection between connector ground shell and chassis enclosure made with screwdriver blade.

Figure 11. *Cables should be tested individually. Here, I have a current probe clamped around the cable under test and am monitoring the harmonics with a simple hand-held spectrum analyzer. As I ground the connector shell to the chassis with the Swiss Army screwdriver blade, the harmonics were reduced 10-15 dB!*

TROUBLESHOOTING TIPS USING CURRENT PROBES

Here are a few troubleshooting tips using current probes.

1. When evaluating the harmonics on a cable by using a current probe, if sliding the probe back and forth changes the harmonic levels, part of the coupling may be near-field, rather than conducted.

2. When using a pair of current probes; one on each of two cables, if the harmonics are the same in each, the source is in the middle. If one cable has stronger harmonics, then you'll want to work on that side first. See Figure 12 below.

3. Measuring the currents on two suspect legs of a dipole should read the same. Placing the two suspect legs through the same current probe should cause a big decrease due to current cancellation. See Figure 12 below.

4. When measuring video cable currents and large cable movements cause big changes in amplitude, the coupling is likely inductive - otherwise, it's more likely conductive.

5. If you suspect inductive coupling, the phase at the victim will be 180-degrees from the source. This may be observed on an oscilloscope with H-field probes or current probes. Try syncing the scope trigger at the source using a scope probe.

My colleague, Doug Smith, has many more examples on how to use current probes for measuring cable and PC board resonances, injecting pulses for troubleshooting, interpreting the relative phase of common-mode currents and troubleshooting ESD issues. Refer to the references below.

SUMMARY

Use of a current probe is vital during the troubleshooting process. Poorly bonded cable connectors can be readily identified and fixed. The radiated E-field from a product I/O cable may be calculated by measuring the high-frequency common-mode currents flowing in the cable. All this may be performed right at the designer's workbench and without the expense of a third-party test facility or shielded chamber.

REFERENCES - PAPERS

- [1] Mat Aschenberg & Charles



Figure 12. *When measuring two cables from a system and the harmonic currents are approximately the same (point 1 is the same as point 2), the source is at the center (the EUT) and the two cables are acting as a dipole antenna. You may notice a peak in harmonic strength at the half-have length of the two cables combined. If the harmonic currents are larger in one side or the other, then you'll want to troubleshoot just that cable.*

Grasso, Radiation from Common-Mode Currents – Beyond 1 GHz (Three Methods Compared)

- [2] Dave Eckhardt, Homebrew Clamp-On Current Probe, private correspondence (January 2009), Email: davearea51@wildblue.net.
- [3] Jasper Goodblood, Electromagnetic Compatibility, 1990, Prentice Hall, pages 31-34.
- [4] Michel Mardiguian, EMI Troubleshooting Techniques, McGraw-Hill, 2000, pages 39-49.
- [5] Montrose & Nakauchi, Testing for EMC Compliance, 2004, Wiley Interscience, pages 116-124, 143-145, and 159-161.
- [6] Henry Ott, Electromagnetic Compatibility Engineering, Wiley, 2009, pages 690-693.
- [7] Henry Ott, Measuring Common-Mode Currents on Cables, www.hottconsultants.com/techtips/tips-cm.html
- [8] Clayton Paul, Introduction to Electromagnetic Compatibility (2nd Edition), Wiley Interscience, 2006, pages 518-532.
- [9] Ridao, Carrasco, Galvin and Franquelo, Implementation of low cost current probes for conducted EMI interference measure in Power Systems, EPE 1999 (Lausanne).
- [10] H. Ward Silver, Hands-On Radio column, Detecting RF – Part 2, QST, August 2011, page 54-55.
- [11] Doug Smith, Current Probes, More Useful Than You Think, IEEE EMC Symposium 1998, http://emcesd.com/pdf/iprobe98.pdf.
- [12] Doug Smith, The Two Current Probe Puzzle, http://emcesd.com/tt061999.htm.
- [13] Doug Smith, Using Current Probes to Inject Pulses for Troubleshooting, http://emcesd.com/tt2007/tt120307.htm Part 1, http://emcesd.com/tt2009/tt030309.htm Part 2.
- [14] Doug Smith, Using Current Probes to Measure Cable Resonance, http://emcesd.com/tt2008/tt010108.htm.
- [15] Doug Smith, Measuring and Interpreting the Relative Phase of Common Mode Currents, http://emcesd.com/tt2008/tt030208.htm.
- [16] Doug Smith, Using a Comb Generator with a Pair of Current Probes to Measure Cable Resonance, http://emcesd.com/tt2009/tt110709.htm.
- [17] Doug Smith, Using Current Probes to Inject Pulses for Troubleshooting (Board Resonances), http://emcesd.com/tt2010/tt010110.htm.
- [18] Doug Smith, Predicting Cable Emissions from Common Mode Current, http://emcesd.com/tt2006/tt030106.htm.
- [19] Douglas Smith, High Frequency Measurements and Noise in Electronic Circuits, Van Nostrand Reinhold, 1993, pages 41-44, 159-182, 192-209.
- [20] Allen Wolff, Building a Ferrite Core Antenna Current Probe, Technical Correspondence, QST, August 2009, page 53.
- [21] Kenneth Wyatt, Troubleshooting Radiated Emissions Using Low-Cost Bench-Top Methods, Interference Technology (ITEM) – EMC Directory & Design Guide 2011, May 2011, page 10-21, http://www.interferencetechnology.com/uploads/media/Wyatt_DDG11.pdf.
- [22] Kenneth Wyatt, Troubleshooting Radiated Emissions – Three Case Studies, InCompliance Magazine, October 2011, http://www.incompliancemag.com/index.php?option=com_content&view=article&id=818:troubleshooting-radiated-emissions-three-case-studies&catid=27:testing&Itemid=136.

REFERENCES - SUPPLIERS

- [23] Fischer Custom Communications (FCC), Phone: (310) 303-3300, Email: sales@fischercc.com, Web: www.fischercc.com. They provide a very wide range of HF current probes – their specialty.
- [24] Laird Technologies, Web: http://www.lairdtech.com/Products/EMI-Solutions/. They offer a complete line of ferrite cores and chokes.
- [25] Pearson Electronics, Phone: (650) 494-6444, Email: sales@pearsonelectronics.com, Web: www.pearsonelectronics.com. They have a good selection of probes.
- [26] Rhode & Schwartz USA, Phone: (888) 837-8772, Email: info@rohde-schwarz.com, Web: www.rohde-schwartz.us. They have a very limited selection.
- [27] Solar Electronics, Phone: (800) 952-5302, Email: sales@solar-emc.com, Web: www.solar-emc.com. They have a limited selection.
- [28] Teseq USA, Phone: (732) 417-0501, Email: usasales@teseq.com, Web: www.teseq.us. They have a very limited selection.
- [29] Thurlby Thander Instruments, Phone: +44-1480-412451, Email: sales@tti-test.com, Web: http://www.tti-test.com/contact-tti.htm. They offer a low-cost handheld spectrum analyzer for under $2,000 USD.
- [30] Würth Electronics Midcom, (605) 886-4385, midcom@we-online.com, www.we-online.com. I used one of their large ferrite cores for my DIY current probe.

KENNETH WYATT, SR. *EMC Engineer, Wyatt Technical Services LLC, holds degrees in biology and electronic engineering and has worked as a senior EMC engineer for Hewlett-Packard and Agilent Technologies for 21 years. He also worked as a product development engineer for 10 years at various aerospace firms on projects ranging from DC-DC power converters to RF and microwave systems for shipboard and space systems. A prolific author and presenter, he has written or presented topics including RF amplifier design, RF network analysis software, EMC design of products and EMC troubleshooting techniques. He has been published in magazines such as, RF Design, EMC Design & Test, Electronic Design, InCompliance, Interference Technology, Microwave Journal, HP Journal and several others.*

Wyatt is a senior member of the IEEE and a long time member of the EMC Society where he serves as their official photographer. He is also a member of the dB Society and is a licensed amateur radio operator. Contact Wyatt at ken@emc-seminars.com. His website is www.emc-seminars.com.

16 Practical VHF/UHF Antennas

VHF and UHF antennas differ from their HF counterparts in that the diameter of their elements are relatively thick in relationship to their length and the operating wavelength, and transmission line feeding and matching arrangements are used in place of lumped elements and ATUs.

THE (VHF) DIPOLE ANTENNA

At VHF and UHF, most antenna systems are derived from the dipole or its complement, the slot antenna. Many antennas are based on half-wave dipoles fabricated from wire or tubing. The feed point is usually placed at the centre of the dipole, for although this is not absolutely necessary, it can help prevent asymmetry in the presence of other conducting structures.

The input impedance is a function of both the dipole length and diameter. A radiator measuring exactly one half wavelength from end to end will be resonant (ie will present a purely resistive impedance) at a frequency somewhat lower than would be expected from its dimensions. Curves of 'end correction' such as **Fig 16.1** show by how much a dipole should be shortened from the expected half wavelength to be resonant at the desired frequency.

The change of reactance close to half-wavelength resonance as a function of the dipole diameter is shown in **Fig 16.2**.

In its simplest form, dipole antennas for 2m and 70cm can be constructed from 2mm diameter enamelled copper wire and fed directly by a coaxial cable as shown in **Fig 16.3**. The total element length (tip to tip) should be 992mm for 145MHz operation and 326mm to cover the band 432 to 438MHz. The impedance will be around 70 ohms for most installations, so that a 50-ohm coaxial cable would present a VSWR of around 1.4:1 at the transceiver end.

A more robust construction can be achieved using tubing for the elements and moulded dipole centre boxes, available from a number of amateur radio antenna manufacturers and at radio rallies. The dipole length should be shortened in accordance with Fig 16.1 to compensate for the larger element diameters. Construction ideas and UK sources of materials can be found at [1].

Note that this simple feed may result in currents on the outside of the cable, and consequently a potential to cause interference to other electronic equipment when the antenna is used for transmitting. This can be reduced or eliminated by using a balun at the feed point.



Fig 16.1: Length correction factor for half-wave dipole as a function of diameter



Fig 16.2: Tuning and reactance chart for half-wave dipoles as a function of diameter



Fig 16.3: Simple dipole construction for 2m and 70cm

Fig 16.4: Simple Yagi antenna structure, using two directors and one reflector in conjunction with a driven element



THE YAGI AND ITS DERIVATIVES

The Yagi Antenna

The Yagi antenna was originally investigated by Uda and subsequently brought to Western attention by Yagi in 1928 in a form similar to that shown in **Fig 16.4**. It consists of a driven element combined with an in-line parasitic array. There have since been many variations of the basic concept, including its combination with log-periodic and backward-wave techniques.

To cover all variations of the Yagi antenna is beyond the scope of this handbook. A great number of books and many articles have been published on the subject, and a wide range of theoretical and practical pages can be found on the Internet with a simple search.

Many independent investigations of multi-element Yagi antennas have shown that the gain of a Yagi is directly proportional to the array length. There is a certain amount of latitude in the position of the elements along the array. However, the optimum resonance of each element will vary with the spacing chosen. With Greenblum's dimensions [2], in **Table 16.1**, the gain will not vary more than 1dB from the nominal value. The most critical elements are the reflector and first director as they decide the spacing for all other directors and most noticeably affect the matching. Solutions may be refined for the materials and construction methods available using one of the many software tools now freely available from the Internet, and discussed elsewhere in this handbook. These tools can be used to assess the sensitivity of a given design to alternative diameter elements and dimensions.

The optimum director lengths are normally greater the closer the particular director is to the driven element. (The increase of capacitance between elements is balanced by an increase of inductance, ie length through mutual coupling.) However, the length does not decrease uniformly with increasing distance from the driven element.



Fig 16.5: Length of director position in the array for various element thicknesses (*ARRL Antenna Book*)

Fig 16.5 shows experimentally derived element lengths for various material diameters. Elements are mounted through a cylindrical metal boom that is two or three diameters larger than the elements.

Some variation in element lengths will occur using different materials or sizes for the support booms. This will be increasingly critical as frequency increases. The water absorbency of insulating materials will also affect the element lengths, particularly when in use, although plastics other than nylon are usually satisfactory.

Fig 16.6 shows the expected gain for various numbers of elements if the array length complies with **Fig 16.7**.



Fig 16.6: Gain over a half-wave dipole (dBd) versus the number of elements of the Yagi array (*ARRL Antenna Book*)

Number of elements	R-DE	DE-D1	D1-D2	D2-D3	D3-D4	D4-D5	D5-D6
2	0.15 -0.20						
2		0.07 -0.11					
3	0.16 -0.23	0.16 -0.19					
4	0.18 -0.22	0.13 -0.17	0.14 -0.18				
5	0.18 -0.22	0.14 -0.17	0.14 -0.20	0.17 -0.23			
6	0.16 -0.20	0.14 -0.17	0.16 -0.25	0.22 -0.30	0.25 -0.32		
8	0.16 -0.20	0.14 -0.16	0.18 -0.25	0.25 -0.35	0.27 -0.32	0.27 -0.33	0.30 -0.40
8 to N	0.16 -0.20	0.14 -0.16	0.18 -0.25	0.25 -0.35	0.27 -0.32	0.27 -0.32	0.35 -0.42

DE = driven element, R = reflector and D = director. N = any number. Director spacing beyond D6 should be 0.35-0.42

Table 16.1: Greenblum's optimisation for multielement Yagis



Fig 16.7: Optimum length of Yagi antenna as a function of number of elements (*ARRL Antenna Book*)

The results obtained by G8CKN using the 'centre spacing' of Greenblum's optimum dimensions shown in Table 16.1 produced identical gains to those shown in **Fig 16.8**. Almost identical radiation patterns were obtained for both the E and H planes (V or H polarisation). Sidelobes were at a minimum and a fair front-to-back ratio was obtained.

Considerable work has been carried out by Chen and Cheng on the optimising of Yagis by varying both the spacing and resonant lengths of the elements [3].

Table 16.2 and **Table 16.3** show some of their results obtained in 1974, by optimising both spacing and resonant lengths of elements in a six element array.

Table 16.3 shows comparative gain of a six element array with conventional shortening of the elements or varying the element lengths alone. The gain figure produced using conventional shortening formulas was 8.77dB relative to a λ/2 dipole (dBd). Optimising the element lengths produced a forward gain of 10dBd. Returning to the original element lengths and optimising the element spacing produced a forward gain of 10.68dBd. This is identical to the gain shown for a six-element Yagi in Fig 16.6. Using a combination of spacing and element length adjustment obtained a further 0.57dBd, giving 11.25dBd as the final forward gain as shown in **Table 16.3**.



Fig 16.8: Radiation pattern for a four element Yagi using Greenblum's dimensions

A publication of the US Department of Commerce and National Bureau of Standards [4], [5] provides very detailed experimental information on Yagi dimensions. Results were obtained from measurements to optimise designs at 400MHz using a model antenna range.

The information, presented largely in graphical form, shows very clearly the effect of different antenna parameters on realisable gain. For example, it shows the extra gain that can be achieved by optimising the lengths of the different directors, rather than making them all of uniform length. It also shows just what extra gain can be achieved by stacking two elements, or from a 'two-over-two' array.

The paper presents:

(a) The effect of reflector spacing on the gain of a dipole.

(b) Effect of different equal-length directors, their spacing and number on realisable gain.

	h_1/λ	h_2/λ	h_3/λ	h_4/λ	h_5/λ	h_6/λ	Directivity (referring to λ/2 dipole)	Gain (dBD)
Initial array	0.255	0.245	0.215	0.215	0.215	0.215	7.544	8.78
Length-perturbed array	0.236	0.228	0.219	0.222	0.216	0.202	10.012	10.00

$b_i1 = 0.250\lambda$, $b_i2 = 0.310\lambda$ (i = 3, 4, 5, 6), $a = 0.003369\lambda$

Table 16.2: Directivity optimisation of six element Yagi-Uda array (perturbation of element lengths)

	h1/λ	h2/λ	h3/λ	h4/λ	h5/λ	h6/λ	b21/λ	b22/λ	b43/λ	b34/λ	b35/λ	Directivity (referring to λ/2 dipole)	Gain (dBD)
Initial array	0.255	0.245	0.215	0.215	0.215	0.215	0.250	0.310	0.310	0.310	0.310	7.544	8.78
Array after spacing perturbation	0.255	0.245	0.215	0.215	0.215	0.215	0.250	0.289	0.406	0.323	0.422	11.687	10.68
Optimum array after spacing and length perturbations	0.238	0.226	0.218	0.215	0.217	0.215	0.250	0.289	0.406	0.323	0.422	13.356	11.26

Table 16.3: Directivity optimisation for six-element Yagi-Uda array (perturbation of element spacings and element lengths)

Length of Yagi (λ)	0.4	0.8	1.20	2.2	3.2	4.2
Length of reflector (λ)	0.482	0.482	0.482	0.482	0.482	0.475
Length of directors (λ):						
1st	0.424	0.428	0.428	0.432	0.428	0.424
2nd	-	0.424	0.420	0.415	0.420	0.424
3rd	-	0.428	0.420	0.407	0.407	0.420
4th	-	-	0.428	0.398	0.398	0.407
5th	-	-	-	0.390	0.394	0.403
6th	-	-	-	0.390	0.390	0.398
7th	-	-	-	0.390	0.386	0.394
8th	-	-	-	0.390	0.386	0.390
9th	-	-	-	0.398	0.386	0.390
10th	-	-	-	0.407	0.386	0.390
11th	-	-	-	-	0.386	0.390
12th	-	-	-	-	0.386	0.390
13th	-	-	-	-	0.386	0.390
14th	-	-	-	-	0.386	-
15th	-	-	-	-	0.386	-
Director spacing (λ)	0.20	0.20	0.25	0.20	0.20	0.308
Gain (dBD)	7.1	9.2	10.2	12.25	13.4	14.2

Element diameter 0.0085λ. Reflector spaced 0.2λ behind driven element. Measurements are for 400MHz by P P Viezbicke.

Table 16.4: Optimised lengths of parasitic elements for Yagi antennas of six different boom lengths

(c) Effect of different diameters and lengths of directors on realisable gain.

(d) Effect of the size of a supporting boom on the optimum length of parasitic elements.

(e) Effect of spacing and stacking of antennas on gain.

(f) The difference in measured radiation patterns for various Yagi configurations.

The highest gain reported for a single boom structure is 14.2dBd for a 15-element array (4.2λ long reflector spaced at 0.2λ, 13 graduated directors). See **Table 16.4**.

It has been found that array length is of greater importance than the number of elements, within the limit of a maximum element spacing of just over 0.4λ. Reflector spacing and, to a lesser degree, the first director position affects the matching of the Yagi. Optimum tuning of the elements, and therefore gain and pattern shape, varies with different element spacing.

Near-optimum patterns and gain can be obtained using Greenblum's dimensions for up to six elements. Good results for a Yagi in excess of six elements can still be obtained where ground reflections need to be minimised.

Chen and Cheng employed what is commonly called the long Yagi technique. Yagis with more than six elements start to show an improvement in gain with fewer elements for a given boom length when this technique is employed.

As greater computing power has become available, it has been possible to investigate the optimisation of Yagi antenna gain more extensively, taking into account the effects of mounting the elements on both dielectric and metallic booms, and the effects of tapering the elements at lower frequencies. Dr J Lawson, W2PV, carried out an extensive series of calculations and parametric analyses, collated in reference [6], which

	70.3MHz	Length 145MHz	433MHz
Driven elements			
Dipole (for use with gamma match)	79 (2000)	38 (960)	12 3/4 (320)
Diameter range for length given	1/2 - 3/4 1/8 - 1/4 (12.7 - 19.0)	(6.35 - 9.5)	1/4 - 3/8 (3.17 - 6.35)



	70.3MHz	145MHz	433MHz
Folded dipole 70-ohm feed			
l length centre-centre	77 1/2 (1970)	38 1/2 (980)	12 1/2 (318)
d spacing centre-centre	2 1/2 (64)	7/8 (22)	1/2 (13)
Diameter of element	1/2 (12.7)	1/4 (6.35)	1/8 (3.17)



	70.3MHz	145MHz	433MHz
a centre/centre	32 (810)	15 (390)	5 1/8 (132)
b centre/centre	96 (2440)	46 (1180)	152 (395)
Delta feed sections (length for 70Ω feed)	22½ (570)	12 (300)	42 (110)
Diameter of slot and delta feed material	1/4 (6.35)	3/8 (9.5)	3/8 (9.5)
Parasitic elements			
Element			
Reflector	85 1/2 (2170)	40 (1010)	13 1/4 (337)
Director D1	74 (1880)	35 1/2 (902)	11 1/4 (286)
Director D2	73 (1854)	35 1/4 (895)	11 1/8 (282)
Director D3	72 (1830)	35 (890)	11 (279)
Succeeding directors	1in less (25)	1/2in less (13)	1/8in less
Final director	2in less (50)	1in less (25)	3/4in less
One wavelength (for reference)	168 3/4 (4286)	81 1/2 (2069)	27 1/4 (693)
Diameter range for length given	1/2 - 3/4 (12.7 - 19.0)	1/4 - 3/8 (6.35 - 9.5)	1/8-¾ (3.17 - 6.35)
Spacing between elements			
Reflector to radiator	22 1/2 (572)	17 1/2 (445)	5 1/2 (140)
Radiator to director 1	29 (737)	17 1/2 (445)	5 1/2 (140)
Director 1 to director 2	29 (737)	17 1/2 (445)	7 (178)
Director 2 to director 3, etc	29 (737)	17 1/2 (445)	7 (178)

Dimensions are in inches with millimetre equivalents in brackets.

Table 16.5: Typical dimensions of Yagi antenna components. Dimensions are in inches with metric equivalents in brackets



Fig 16.9: Charts showing voltage polar diagram and gain against VSWR of Yagi and skeleton-slot antennas. In the case of the six Yagi antennas the solid line is for conventional dimensions and the dotted lines for optimised results discussed in the text.

although specifically addressing HF Yagi design, explain many of the disappointing results achieved by constructors at VHF and above. In particular, the extreme sensitivity of some designs to minor variations of element length or position are revealed in a series of graphs which enable the interested constructor to select designs that will be readily realisable.

The keen constructor with a personal computer may now also take advantage of modelling tools specifically designed for optimisation of Yagi antennas and arrays, eg [7], although some care is needed in their use if meaningful results are to be assured. The Internet is a good source for Yagi antenna design and optimisation programmes, many of which can be obtained free of charge, or for a nominal sum.

From the foregoing, it can be seen that several techniques can be used to optimise the gain of Yagi antennas. In some circumstances, minimisation of sidelobes is more important than maximum gain, and a different set of element spacings and lengths would be required to achieve this. Optimisation with so many independent variables is difficult, even with powerful computing methods, as there may be many solutions that yield comparable results.

Techniques of ‘genetic optimisation’ have been developed and widely adopted, which can result in surprising, but viable designs [8], [9]. The technique requires the use of proven computer-based analysis tools such as NEC, MININEC or their derivatives. The required parameters (gain, sidelobe levels, input impedance) are described and weighted according to their importance to the designer, together with the permitted variables.

A figure of merit is defined, which incorporates the weighting of the desired parameters. An initial structure is input, which is then analysed, its performance recorded, and an incremental change made to one of the variables. The process is repeated whilst the figure of merit continues to improve. However, unlike conventional optimisation methods, where local optimisation may obscure a better result that may also be available, a random process selects the variable(s) to be changed until a reasonably large seed population has been generated. Selection, crossover and mutation processes are then used to filter out poor designs and retain better ones, with each successive generation possibly containing better designs than the preceding one, if the selection algorithms have been well constructed. This technique is readily available to amateurs with home computers [10], [11], [12]

Dimensions for Yagi antennas for 70, 145 and 433MHz are shown in **Table 16.5**. The table also includes dimensions for feeding two stacked Yagi antennas with a *skeleton slot feed*, described later in this chapter.

Typical radiation patterns, gains and VSWR characteristics for a range of different Yagi antennas are shown in **Fig 16.9**. The figure also contains information on skeleton slot Yagis, discussed later in this chapter.

Long Yagi Antennas

The NBS optimisation described above has been extended by American amateurs [13]. Tapering of the spacing was studied by W2NLY and W6QKI who found [14] that, if the spacing was increased up to a point and thereafter remained constant at 0.3-0.4λ, another optimisation occurred. Both these are *single optimisation* designs.

Günter Hoch, DL6WU, looked at both techniques and decided that they could be applied together. The director spacing was increased gradually until it reached 0.4λ and the length was tapered by a constant *fraction* from one element to the next. The result is a highly successful *doubly optimised* antenna [15], [16].


©RSGB RC1910
Twin reflectors
Driven element
First director
200mm
120mm
55mm etc

Fig 16.11: Twin reflector details

Number of elements	10	13	14	19	23
Gain (dBd)	11.7	13	13.3	15	16
Horizontal beamwidth	37°	30.5°	30°	26.5°	24°
Vertical beamwidth	41°	33°	32°	28°	24.5°

Table 16.6: Performance of 10/13/14/19/23 element 435MHz Yagis


Inter element spacing
Element length
Cumulative spacing fom driven element
330 Reflector 130 or 120
130 325 Driven element 0
55 295 Directors 55
125 290 180
150 285 330
175 280 505
195 275 700
210 275 910
220 270 1130
230 270 1360
10 el
240 265 1600
250 265 1850
260 265 2110
13 el
260 260 2370
14 el
270 260 2640
280 260 2920
280 260 3200
280 258 3480
280 258 3760
19 el
280 258 4040
280 255 4320
280 255 4600
280 250 4880
23 el
©RSGB RC1909
All dimensions in millimetres

Fig 16.10: Element lengths and spacings for 10/13/14/19/23 element 435MHz Yagi

Great care is required in constructing these antennas if the predicted gain is to be realised. This means following the dimensions and fixing methods *exactly* as laid out in the designer's instructions. Details for building a number of long Yagi antennas for VHF and UHF can be found through links at G3SEK's website [17].

F5JIO Long Yagi for 435MHz

This antenna can be built with 10, 13, 14, 19 or 23 elements according to the space available (**Fig 16.10**). Its performance is shown in **Table 16.6**.

An extra 0.2dB gain and some reduction of backlobes can be obtained by fitting twin reflectors (**Fig 16.11**), but note that the spacing between the driven element and the reflector is reduced from 130mm to 120mm.

The 23 element version requires a boom length in excess of 5010mm, and must be solidly constructed and supported. The boom is made from 20 x 20mm square aluminium tubing, and all elements from 8mm diameter (round) tubing. All elements except the driven element must be *insulated* from the boom and mounted so that their centres are 8mm above its upper surface. Dimensions for the driven element and cable balun construction to provide a feed impedance of 50 ohms


All dimensions in millimetres
©RSGB RC1912a
325mm
Aluminium shim
4mm
8mm
Folded dipole
8mm outside dia
tubing
Plastic box
Aluminium boom
50mm
3
3
Balanced
feedpoint
8
5
5
Stripped
(x2)
Braid
pigtails
Tinned
solder
tags
Plastic box
½λ
Coax balun
235mm
245mm
½λ = 251mm URM111

Fig 16.12: 435MHz long Yagi driven element and balun

Table 16.7: Balun cable length calculation

λ/2@435MHz = 300,000/435 x 2 = 345mm (in air)
In URM111: 16mm of stripped end (@v=0.9) =18mm (electrical)

Cutting length = 345mm-18mm (@v=0.72 (PTFE insulation) = 235mm (unstripped)

Note: Use v=0.66 for Polyethylene insulation

are shown in **Fig 16.12**. Balun cable lengths and calculations are shown in **Table 16.7**. The cable should be a 75-ohm miniature PTFE insulated type, such as URM111 or equivalent. A small weatherproof box should be fitted over the ends of the element, inside which the balun cable may also be coiled. The driven element may be made from 9.5 x 1.6mm flat aluminium bar which is easier to bend and drill.


ℓ+5%
λ/4
ℓ
λ/4
1
2
INSULATOR
50Ω FEED
(a)
ℓ
ℓ
1
STUB
2
INSULATOR
(b)

Fig 16.13: Quad antenna structure and electrical dimensions

Quad Antenna

The Quad antenna can be thought of as a Yagi antenna comprising pairs of vertically stacked, horizontal dipoles with their ends bent towards each other and joined, **Fig 16.13**. The antenna produces horizontally polarised signals, and in spite of its relatively small physical size a forward gain of 5.5 to 6dB can be obtained with good front-to-back ratio. Additional quad or single element directors can be added to the basic two element array in the same manner as the Yagi.

Typical dimensions for lightweight wire 51, 71 and 145MHz Quad antennas are given in **Table 16.8**, and a photograph of the 145MHz version is shown in **Fig 16.14**. This variant has equal size loops and uses a stub to tune the reflector. The boom is made from 15mm copper tubing with a T-piece in the centre for fixing to the mast or rotator. The element supports are made from 10 or 12mm square wooden dowelling fixed to square pieces of plywood using nuts and bolts. The plywood centres are fixed to the boom using L-brackets and hose clamps. A 50-ohm coaxial cable can be connected directly to the driven element. A 1:1 balun will minimise currents on the outer of the cable, preventing distortion of the radiation pattern and potential EMC problems.

Quads may be stacked or built into a four square assembly in the same way as the basic Yagi (see below).

Table 16.8: Design dimensions for 51, 70 and 144MHz quad antennas

Band	Element spacing, mm	Reflector sides, mm	Driven element sides, mm
51MHz	840	1560	1500
71.5MHz	600	1210	1080
145MHz	294	548	524



Fig 16.14: Wire quad antenna for 145MHz



Fig 16.15: General arrangement for a multi-element quad antenna

Multi-element quad (Quagi)

The multiple element quad antenna or "Quagi" can offer a better performance with reduced sidelobes compared with the average simple Yagi, whilst retaining a simple robust form of construction (**Fig 16.15**). Dimensions for a four element, 145MHz antenna are given in **Table 16.9**. Generally the maximum number of elements used is five. Where more gain is needed, a pair may be stacked vertically or horizontally, although for maximum mechanical strength the vertical arrangement is to be preferred.

The whole structure may be made up of aluminium tube (or solid rod for the elements). The only insulator necessary is at the feed point of the driven element. In construction, it is best to make each element from one piece of material. A 3/8in aluminium rod will bend to form corners much more readily than tube that would also need a 'filler'. The corner radius should be kept small, and allowance must be made for the resultant 'shortening' of element length, ie side of the quad element.

For mechanical simplicity (and appearance) it is a good idea to arrange for all the element heights to be the same, and vary the width.

Fixing the elements to the boom and the boom to the mast is conveniently done with standard TV antenna fittings. Although suitable blocks or clamping arrangements can be made by the constructor, they often tend to be unnecessarily heavy. Purchased TV fittings can be more cost-effective than obtaining raw materials and there is also much less effort involved in construction. There are also several antenna manufacturing companies catering for the radio amateur who sell tubing, mast clamps and small components for securing elements to booms. They can often be found at rallies and amateur radio events, or advertise in the pages of *RadCom*.

If preferred, the reflector may be made the same size as the driven element, and tuned with a suitable stub. If vertical polarisation is required, instead of horizontal, then the feeder can be attached to the centre of one of the vertical sides of the driven element. (The same 'side' must always be used for correct phase relationship within stacked arrays.)

The relative performance of multi-element quad and Yagi antennas is shown in **Fig 16.16**, demonstrating that the shorter quad structures can provide gains comparable with longer Yagi antennas. This may be of benefit if turning space is limited (eg inside a loft). However, there is no such thing as a free lunch, and in general, the weight and wind loading of the multi-element quad antenna will be slightly greater than its Yagi counterpart.

Height H	21 (533)	21	21	21
Width reflector WR	24½ (622)	24½	24½	24½
Driven WDe	20½ (520)	20½	20½	20½
Director 1 WD1	-	18 (457)	18	18
Director 2 WD2	-	-	16 (406)	16
Director 3 WD3	-	-	-	14 (356)
Spacing				
Reflector to Driven	7 (178)	19 (483)	20 (508)	20
Driven to Director 1	-	12 (305)	14½ (368)	14½
Director 1 to Director 2	-	-	14½	14½
Director 2 to Director 3	-	-	-	14½
Approx gain (dBd)	5	7	10.5	12.5

Element diameters all 3/8in (9.35mm). Feed impedance in all cases is 75 . Dimensions are in inches with millimetre equivalents in brackets.

Table 16.9: Dimensions for a multi-element quad antenna for 144MHz



Fig 16.16: Comparative directivity of the Yagi and Quad as a function of overall array length. Although measured with circular loops, performance with square loops is comparable (*ARRL Antenna Book*). Note the gains are in dBi, not dBd


170 mm
180 mm
180 mm
CD1030
Reflector
Driven element
Director 1
Director 2
Wire dimensions refer the circumference of the elements
780mm
700mm
640mm
632mm
Jubilee clip
Connector block
Boom
Wire element
Coax
Element to boom detail
Stiff copper or steel wire (one each side of boom)
Jubilee clips
Boom
Mast
Boom to mast connector detail
Jubilee clip
Wire element
Boom
Element to boom join detail

Fig 16.17: Four element quad loop Yagi for 435MHz

The Loop Yagi

At frequencies above 433MHz, the construction of multiple quad antennas can be considerably simplified by bending the elements into circular loops. High gains can be achieved by using large numbers of elements, and the relatively simple construction allows gains up to around 20dBi to be realised with manageable boom lengths [18].

A practical horizontally polarised four element loop Yagi antenna for 435MHz is shown in **Fig 16.17**. 2mm diameter enamelled copper wire elements are fixed to a tubular metal boom using hose clamps. A three terminal, plastic mains power connector block is used to connect the coaxial cable and provide the method for fastening the driven element to the boom. the enamel insulation is removed from the ends of the driven element to a distance of 20mm at one end and 50mm at the other. The 50mm end is folded into a loop and passed back into the connector block. The parasitic elements should be made 40mm longer than the dimensions shown, and the enamel removed from the last 20mm at each end. These ends should be bent at right angles and the remaining wire formed into a loop. The bent ends should be soldered together to simplify assembly. The boom and mast can be connected together using thick wire loops as shown, or the boom could be made from copper water pipe with a T-piece to connect to the support mast if preferred. A gain of around 9dBi should be achieved.

ANTENNA ARRAYS

Array Principles

The gain achievable with any antenna structure is ultimately limited by the fundamentals of its operation. However, higher gains can be achieved by using several antenna elements in an *array*. The array can comprise antennas *stacked* vertically above each other, or arranged side by side in *bays*, or a combination of both. These are *broadside* arrays, where most of the radiated power is projected at right angles to the plane in which the array elements lie. An array can also be formed where the main beam is projected along the array of elements; these are *endfire* arrays, of which the HB9CV and Yagi antennas are examples.

An array of elements has a narrower beamwidth, and hence a higher gain than the individual antennas. The maximum achievable gain could be N times greater than one element fed with the same power ($10\log_{10} N$ decibels) if there are N elements in the array. However, more complex feed arrangements can reduce the VSWR bandwidth and introduce losses, reducing the array gain. Arrays need care in construction and attention to detail, especially at UHF and above, but the results reward the effort expended.

Antenna array theory can be found in almost any book devoted to antennas. However, a good treatment with many radiation pattern examples can be found in Refs [19] and [20].

Disadvantages of Multi-element Arrays

High gain cannot be achieved by simply stacking many elements close together. If we consider a dipole collecting power from an incident field for delivery to a load (receiver), it can be thought of as having a collecting area or effective aperture that is somewhat larger than the dipole itself. The higher the directivity of the antenna, the larger the effective aperture, as given by the relationship:

$$A_{eff} = \frac{\lambda^2}{4\pi} D$$

where D is the directivity of the antenna
λ is the working wavelength

If the effective apertures of adjacent antennas overlap, the incoming RF energy is shared between them, and the maximum possible directivity (or gain) of the elements cannot be attained.

The generalised optimum stacking distance is a function of the half power beamwidth of the elements in the array, and is given by:

$$S_{opt} = \frac{\lambda}{\left[2\sin\left(\frac{\phi}{2}\right)\right]}$$

where ϕ is the half power beamwidth and S_{opt} is in wavelengths. Note that this is usually different for the E and H planes, so that the spacing of the elements is also usually different in each plane.

Also, when antennas are placed close together, *mutual coupling* between elements occurs. This leads to changes in the current distribution on the elements, changing both the radiation pattern and the feed point impedance of each element. The changes to the feed impedance often result in unequal powers being fed to the elements of the array, with consequential loss of gain.

Optimum stacking rules are based on the assumption of minimum mutual influence, which can be difficult to predict for complex antennas such as Yagis. However, antennas with low sidelobe levels are less susceptible than those with high sidelobes, as might be expected intuitively.

The coupling and effective aperture overlap problems cannot simply be solved by arbitrarily increasing the separation of the elements. As the element spacing increases beyond one half wavelength, *grating sidelobes* appear, which can reduce the forward gain. The grating lobes are due solely to the array dimensions, and can be seen by plotting the array factor for the chosen configuration.

Arrays of Identical Antennas

A parasitic array such as the Yagi can be stacked either vertically or horizontally to obtain additional directivity and gain. This is often called *collinear and broadside* stacking.

In stacking it is assumed that the antennas are identical in pattern and gain and will be matched to each other with the correct phase relationship, that is, 'fed in phase'. It is also assumed that for broadside stacking the corresponding elements are parallel and in planes perpendicular to the axis of the individual arrays. With vertical stacking it is assumed the corresponding elements are collinear and all elements of the individual arrays are in the same plane.

The combination of the radiation patterns can add but can also cancel. The phase relationships, particularly from the side of the Yagi, are very complex. Because of this complexity the spacing to obtain maximum forward gain does not coincide with the best sidelobe structure. Usually maximum gain is less important than reducing signals to the sides or behind the array.

If this is the case, 'optimum spacing' is one that gives as much forward gain as possible as long as the sidelobe structure does not exceed a specific amplitude compared with the main lobe. There will be different 'optimum' spacings according to the acceptable sidelobe levels.

Fig 16.18 gives typical optimum spacing for two arrays under three conditions:

(a) optimum forward gain with sidelobe down 10dB,

(b) sidelobe 20dB down and

(c) virtually no sidelobe.

The no-sidelobe case can correspond to no additional forward gain over a single antenna. **Fig 16.19** shows the optimum stacking spacing for four-unit arrays.

The maximum forward gain of two stacked arrays is theoretically +3dB, and +6dB for four stacked arrays. More complex arrays could produce higher gain but losses in the matching and phasing links between the individual arrays can outweigh this improvement.

When stacking two arrays, the extra achievable gain is reduced at close spacing due to high mutual coupling effects. With two seven-element arrays a maximum gain of about 2.5dB can be achieved with 1.6λ spacing; with two 15-element arrays it is also possible to achieve the extra 2.5dB but the spacing needs to be 2λ.

The use of four arrays, in correctly phased two-over-two systems, can increase the realisable gain by about 5.2dB. Using seven-element Yagis produced a total gain of 14.2dB. With 15-element optimised Yagis a total gain of 19.6dB was obtained. (This was the highest gain measured during the experiments by Viezbicke [4].) The effects of stacking in combination with the physical and electrical phase relationship can be used to reduce directional interference.

An improvement in front-to-back ratio can be accomplished in vertical stacking by placing the top Yagi a quarter-wavelength in front of the lower Yagi as shown in **Fig 16.20**. The top antenna is fed 90° later than the bottom antenna by placing additional cable in the upper antenna feed run. The velocity factor of the cable must be taken into account.



Fig 16.18: Optimum stacking spacing for two-unit arrays. The spacing for no sidelobes, especially for small beamwidths, may result in no gain improvement over a single array element (*ARRL Antenna Handbook*)



Fig 16.19: Optimum stacking spacing for four-unit arrays (ARRL *Antenna Handbook*)


λ/4
A
B
A is ¼ wavelength longer than B
transmitter

Fig 16.20: Improving front to back ratio of stacked Yagi antennas with offset vertical mounting



Fig 16.21: Four Yagi antennas stacked and bayed

A Coaxial Cable Harness for Feeding Four Antennas

Four identical antennas such as Yagis can be mounted at the corners of a rectangle as a stacked and bayed array as shown in Fig 16.21, with separations determined by their beamwidths as described above. Whilst feed harnesses can be purchased with the antennas, they can also be constructed using standard coaxial cables and connectors, as shown in Fig 16.22. Each antenna and all cables must have an impedance of 50 ohms. The two feeders L1 and L3 connected in parallel result in 25 ohms at Point A. This is transformed to 100 ohms by the cable between A and B, which must be an odd number of quarter wavelengths long. The two 100-ohm impedances connected in parallel at point B result in a 50-ohm impedance presented to the transceiver feeder. Feeders L1-L4 may be any convenient length, provided that they are all identical.

Skeleton Slot Feed for Two Stacked Yagis

A serious disadvantage of the Yagi array is that variation of the element lengths and spacing causes interrelated changes in the feed impedance. To obtain the maximum possible forward gain experimentally is extremely difficult. For each change of element length it is necessary to readjust the matching either by moving the reflector or by resetting a matching device.

However, a method has been devised for overcoming these practical disadvantages. It involves the use of a radiating element in the form of a skeleton slot. This is far less susceptible to the changes in impedance caused by changes in the length of the parasitic elements. A true slot would be a slot cut in an infinite sheet of metal. Such a slot, when approximately λ/2 long, would behave in a similar way to a dipole radiator. In contrast with a dipole, however, the electric field produced by a vertical slot is horizontally polarised.


Yagi 1
Yagi 2
C = Double-ended socket adaptor
L1, L2, L3, L4 = Equal lengths
L5, L6, = Odd multiple of ¼ wavelength
L1 50Ω
L2 50Ω
Coax plugs
A T connector
L5 50Ω
B T connector
L6 50Ω
A T connector
C
C
C
L3 50Ω
50Ω
L4 50Ω
Yagi 3
To transceiver
Yagi 4
CD1728A

Fig 16.22: Coaxial feed harness for four antennas



Fig 16.23: Development of the skeleton-slot radiator



Fig 16.24: Dimensional relationships of a skeleton-slot radiator. Both S and W may be varied experimentally, and will not change the radiation characteristics of the slot greatly. See text

Table 16.10: Dimensions for six-over-six slot fed Yagi antenna for 145MHz

Element	Length, in (mm)	Element spacing, in (mm)
A	34 (864)	A - B, 14.25 (362)
B	34 (864)	B - C, 14.25 (362)
C	34 (864)	C - D, 14.25 (362)
D	34 (864)	D - E, 34.25 (870)
E	40 (1016)	D - Slot, 14.5 (368)
Boom	70 (1720)	

The skeleton slot was developed during experiments to find how much the 'infinite' sheet of metal could be reduced without the slot antenna losing its radiating property. The limit was found to occur when there remained approximately λ/2 of metal beyond the slot edges. However, further experiments showed that a thin rod bent to form a 'skeleton slot' (approximately 5λ/8 by 5λ/24) exhibited similar properties to those of a true slot.

The way a skeleton slot works is shown in **Fig 16.23**. Consider two λ/2 dipoles spaced vertically by 5 /8. Since the greater part of the radiation from each dipole takes place at the current maximum (ie the centre) the ends of the dipoles may be bent without serious effect.

These 'ends' are joined together with a high-impedance feeder, so that 'end feeding' can be applied to the bent dipoles. To radiate in phase, the power should be fed midway between the two dipoles.

The high impedance at this point may be transformed down to that of the feeder cable with a tapered matching section/transmission line (ie a delta match). Practical dimensions of a skeleton-slot radiator are given in **Fig 1.5.24**.

These dimensions are not critical, and may be varied over a modest range without affecting the radiating characteristics of the slot. However, the feed impedance is very sensitive to dimensional changes, and must be properly matched by altering the length and shape of the delta section after completing all other adjustments.

It is important to note that two sets of parasitic elements are required with a skeleton-slot radiator and not one set as with a true slot. One further property of the skeleton slot is that its bandwidth is greater than a pair of stacked dipoles.

Radiation patterns and VSWR data for some typical slot-fed Yagi antennas are shown in Fig 16.9 earlier in this chapter.

Details of a practical 'six-over-six' skeleton slot Yagi antenna are shown in **Fig 16.25** with essential dimensions listed in **Table 16.10**.

Skeleton Slot Yagi Arrays

Skeleton-slot Yagi arrays may be stacked to increase the gain but the same considerations of optimum stacking distance as previously discussed apply. The centre-to-centre spacing of a pair of skeleton-slot Yagi arrays should typically vary between



Fig 16.25: A six-over-six skeleton slot fed Yagi antenna for 145MHz



Fig 16.26: A high gain 432MHz antenna consisting of four 8-over-8 slot-fed Yagi antennas arranged in a square formation

1λ and 3λ depending on the number of elements in each Yagi array. A typical 4 x 4 array of 8-over-8 slot-fed Yagis for 432MHz is shown in **Fig 16.26**.

Quadruple Quad for 144MHz

This collapsible antenna was designed for portable use [21], but is equally useable as a fixed antenna for use indoors or in a loft, and can achieve gains of between 10 and 11dBi (8 - 9dBd) on 2 metres. It is effectively a stacked quad using mutual coupling instead of a phasing harness to excite the outer elements. Constructional details are shown in **Fig 16.27**.

Each section has a circumference of around 1.04 wavelengths, which is not as would be expected for conventional quads. The dimensions are the result of experiments to obtain the best front to back ratio and least sensitivity to adjacent objects, which can be important for portable or loft operation, ensuring that the antenna will work without extensive adjustment.

Note that the antenna was designed for low-power (1 watt) operation; the ferrite bead must not be allowed to saturate magnetically, or harmonic generation may occur. The bead may also become hot and shatter. For higher power operation, ferrite rings could be considered for the balun transformer, or a sleeve balun constructed as appropriate.

Yagi Antenna Mounting Arrangements

The performance of Yagi antennas can be greatly degraded if they are not correctly installed and the feeder routed to minimise unwanted interaction with the antenna. Many commercial designs have fixed clamping positions which have been optimised to minimise coupling into the support mast. However, there are a number of precautions that can be taken when installing any Yagi antennas, whether operating in the same band as an array, or operating in several different bands.

Antenna performance may be completely destroyed if the mast is installed parallel, and through the Yagi antenna as in **Fig 16.28a**. The mast should be mounted at right angles to the antenna elements to minimise coupling between the elements and the mast, **Fig 16.28c**. If the antenna is to provide vertical polarisation, it should be offset from the main support mast with a stub mast if possible, **Fig 16.28b**. Mechanical balance can be restored (and the Yagi-mast separation increased) by using a symmetrical stub mast and a second antenna for the same band (bayed array), or for another frequency.



Radiation direction
4·5mm dia
Plastic block
3·5mm brass tube
3·5mm dia
558
516
516
2·5mm dia
Do not solder
λ/4 516mm
516
516
3·5mm dia
Solder
2064
2064
Do not solder
Stranded wire 2·0 to 2·5mm outside dia
516
516
240Ω Twin-lead
λ/4 ~420mm
X
X
open
Front to back 23dB
11 to 12dB
4-quad array
Dipole
516
516
−12dBD
λ/4 516mm
60Ω coaxial cable
Dimensions are in millimetres
120Ω twinlead
uhf ferrite core
X
X

Fig 16.27: Quadruple Quad. The match point xx should be found experimentally and will be approximately 200mm from the open end (*VHF Communications*)



Fig 16.28: Yagi mounting methods (a) the wrong way, antenna couples strongly with the mast, destroying performance (b) best arrangement for vertically polarised antennas, offset from the mast at least λ/4 with a horizontal tube (c) mast should be fastened mid way between elements, but not next to the driven element (d) put highest frequency antenna at top of a multi-band stack


Element length
A
B
C
Coaxial feeder
A ....coaxial screen attach point
B ....coaxial screen attach point
C ....coaxial centre conductor attach point
V4-11A

Fig 16.29: Typical log-periodic antenna. Note that the bottom transmission line is fed from the coaxial outer while the top line is fed from the centre conductor (*Ham Radio*)

The mounting clamp should be placed mid-way between elements, and well away from the driven element. This is usually achieved by clamping near the mechanical balance point of the antenna.

However, it is more important to keep the mast and clamp away from the adjacent elements than to mechanically balance the antenna. In theory, the mast could be clamped to the antenna behind the reflector element(s). This is rarely done with antennas operating at wavelengths greater than 23cm because of mechanical constraints.

At 23cm and above, a 50mm (2in) pipe mast running through the antenna will seriously degrade its performance, even if the elements are at right angles to the pipe. Performance will not be so badly affected if the (horizontally polarised) antenna is right at the top of the mast, with the minimum amount of pipe required for clamping projecting through the elements. A smaller diameter pipe, eg 25mm (1in) for the mount will also reduce these effects, and is generally mechanically adequate to support higher frequency antennas.

The feed cable should be arranged to lie in a plane at right angles to the Yagi elements, or be taped below and along the boom until it can be run down the support mast.

In the case of circularly polarised antennas, for example, crossed Yagi antennas fed in phase quadrature, the elements should be arranged at 45 degrees to the support mast when the antenna is viewed along its boom. There will be some degradation of circularity, but it can be minimised if the support mast is not an odd multiple of quarter wavelengths long. The feed cable should be taped to the boom and dressed on to the support mast with the minimum bend radius for which the cable is designed.

Stacking Yagi Antennas for Different Bands

The optimum spacing between identical antennas to create higher gain arrays is discussed earlier in the chapter. However, in many cases, it may be desired to put several antennas for different bands on a common rotating mast.

If the antennas are all pointing in the same direction on the mast, they should be separated sufficiently to ensure that their effective apertures do not overlap (see formula earlier in this chapter) to avoid interaction and mutual degradation of their radiation patterns. To a first approximation, the antenna gain may be used in place of the directivity in the formula. Yagi antennas may be stacked more closely together if alternate antennas point in directions at 90 degrees to each other. The separation may then be reduced so that the effective aperture of the lowest band antenna of any pair is not physically encroached by the higher frequency antenna. Closer spacings may be possible without excessive interaction, but need to be investigated on a case by case basis using antenna modelling software or careful experiment.

THE LOG PERIODIC ANTENNA

The log-periodic antenna **Fig 16.29** was originally designed and proven at the University of Illinois in the USA in 1955 [22].Its properties are an almost infinite bandwidth, governed only by the number of elements used and mechanical limitations, together with the directive qualities of a Yagi antenna [23].

Table 16.11 and **Table 16.12** show typical dimensions for element spacing and length for log-periodic arrays. These are derived from a computer-aided design produced by W3DUQ [24]. Other frequency bands can be produced by scaling all dimensions.

The tabulated parameters have a 5% overshoot of the working frequency range at the low end and a 45% overshoot at the high-frequency end. This is done to maintain logarithmic response

	21-55MHz array						50-150MHz array						140-450MHz array					
Ele-	Length		Diameter		Spacing		Length		Diameter		Spacing		Length		Diameter		Spacing	
ment	(ft)	(mm)	(in)	(mm)	(ft)	(mm)	(ft)	(mm)	(in)	(mm)	(ft)	(mm)	(ft)	(mm)	(in)	(mm)	(ft)	(mm)
1	12.240	3731	1.50	38.1	3.444	1050	5.256	1602	1.00	2.54	2.066	630	1.755	535	0.25	6.7	0.738	225
2	11.190	3411	1.25	31.8	3.099	945	4.739	1444	1.00	2.54	1.860	567	1.570	479	0.25	6.7	0.664	202
3	10.083	3073	1.25	31.8	2.789	850	4. 274	1303	1.00	2.54	1.674	510	1.304	397	0.25	6.7	0.598	182
4	9.087	2770	1.25	31.8	2.510	765	3.856	1175	0.75	19.1	1.506	459	1.255	383	0.25	6.7	0.538	164
5	8.190	2496	1.25	31.8	2.259	689	3.479	1060	0.75	19.1	1.356	413	1.120	341	0.25	6.7	0.484	148
6	7.383	2250	1.00	25.4	2.033	620	3.140	957	0.75	19.1	1.220	372	0.999	304	0.25	6.7	0.436	133
7	6.657	2029	1.00	25.4	1.830	558	2.835	864	0.75	19.1	1.098	335	0.890	271	0.25	6.7	0.392	119
8	6.003	1830	0.75	19.1	1.647	500	2.561	781	0.50	12.7	0.988	301	0.792	241	0.25	6.7	0.353	108
9	5.414	1650	0.75	19.1	1.482	452	2.313	705	0.50	12.7	0.889	271	0.704	215	0.25	6.7	0.318	97
10	4.885	1489	0.75	19.1	1.334	407	2.091	637	0.50	12.7	0.800	244	0.624	190	0.25	6.7	0.286	87
11	4.409	1344	0.75	19.1	1.200	366	1.891	576	0.50	12.7	0.720	219	0.553	169	0.25	6.7	0.257	78
12	3.980	1213	0.50	12.7	1.080	329	1.711	522	0.375	9.5	0.648	198	0.489	149	0.25	6.7	0.231	70
13	3.593	1095	0.50	12.7	0.000		1.549	472	0.375	9.5	0.584	178	0.431	131	0.25	6.7	0.208	63
14							1.403	428	0.375	9.5	0.525		0.378	115	0.25	6.7	0.187	57
15							1.272	388	0.375	9.5	0.000		0.332	101	0.25	6.7	0.169	52
16													0.290	88	0.25	6.7	0.000	
Boom	25.0	7620	2.0	50.8	0.5	12.7	16.17	5090	1.5	38.1	0.5	152	5.98	1823	1.5	38.1	0.5	152

Table 16.11: Spacing and dimensions for log-periodic VHF antennas

Element	Length		Diameter		Spacing	
	(ft)	(mm)	(ft)	(mm)	(ft)	(mm)
1	0.585	178	0.083	2.1	0.246	75
2	0.523	159	0.083	2.1	0.221	67
3	0.435	133	0.083	2.1	0.199	61
4	0.418	127	0.083	2.1	0.179	55
5	0.373	114	0.083	2.1	0.161	49
6	0.333	101	0.083	2.1	0.145	44
7	0.297	91	0.083	2.1	0.131	40
8	0.264	80	0.083	2.1	0.118	36
9	0.235	72	0.083	2.1	0.106	32
10	0.208	63	0.083	2.1	0.095	29
11	0.184	56	0.083	2.1	0.086	26
12	0.163	50	0.083	2.1	0.077	23
13	0.144	44	0.083	2.1	0.069	21
14	0.126	38	0.083	2.1	0.062	19
15	0.111	34	0.083	2.1	0.056	17
16	0.097	30	0.083	2.1	0.000	0
Boom	1.99	607	0.5	12.7		

Table 16.12: Spacing and dimensions for log-periodic UHF antenna (420-1350MHz)


Coaxial centre conductor bolted through boom end
Coaxial screen extended to mid-point of boom spacing
Boom
DS
Boom
DM
DM
DS
Coaxial screen bolted to boom
Mast
Coaxial screen bolted through boom end
50Ω feeder
Boom end with shortest element
DS....dielectric spacers DM....dielectric mast insulators
V4-10B

Fig 16.30: Log-periodic antenna mast mounting and feeder arrangements (*Ham Radio*)

over the complete frequency range specified as the log-periodic cell is active over approximately four elements at any one specific frequency. The logarithmic element taper (α) is 28° for all three antennas. They have a forward gain of 6.55dBd, with a front-to-back ratio of typically 15dB and a VSWR better than 1.8:1 over the specified frequency range.

Construction is straightforward. The element lengths for the highest-frequency antenna allow for the elements to be inserted completely through the boom, ie flush with the far wall. The two lower-frequency antennas have element lengths calculated to butt flush against the element side of the boom, and a length correction factor must be added to each element if through-boom mounting is used.

The supporting booms are also the transmission line between the elements for a log-periodic antenna. They must be supported with a dielectric spacer from the mast of at least twice the boom-to-boom spacing. Feed-line connection and the arrangement to produce an 'infinite balun' is shown in **Fig 16.30**. Any change in the boom diameters will require a change in the boom-to-boom spacing to maintain the transmission line impedance. The formula to achieve this is:

$$Z_0 = 273 \log_{10} D/d$$

where D is the distance between boom centres and d the diameter of the booms. Mounting arrangements are shown in Fig 16.30. The antenna can be oriented for either horizontal or vertical polarisation if a non-conductive mast section is used. The horizontal half-power beamwidth will be typically 60° with a vertical half-power beamwidth of typically 100°.

THE AXIAL MODE HELIX

The axial mode helix antenna provides a simple means of obtaining high gain and a wide-band frequency characteristic. When the circumference of the helix is of the order of one wavelength, axial radiation occurs, ie the maximum field strength is found to lie along the axis of the helix. This radiation is circularly polarised, the sense of the polarisation depending on whether the helix has a right or left-hand thread. The polarisation can be determined by standing behind the antenna. If a clockwise motion would be required to travel along the helix to its far end, the helix will generate and receive Right Hand Circularly Polarised (RHCP) waves.



Fig 16.31: The axial mode helix antenna. The plane reflector may take the form of a dartboard type wire grid or mesh. The dimensions given in Table 13 are based on a pitch angle of 12 degrees. The helix tube or wire diameter is not critical, but it must be supported by low loss insulators



Fig 16.32: Kraus's theoretical gain and realisable gain for a helix antenna of different lengths. The antenna has a circumference of 1.06λand α = 13°

Band	Dimensions				
	D	R	P	a	d
General	0.32	0.8	0.22	0.12	
144MHz	25 1/2 (648)	64 (1626)	17 3/4 (450)	8 3/4 (222)	1/2 (12.7)
433MHz	8 3/4 (222)	22 (559)	6 (152)	3 (76)	3/16 - 1/2 (4.8 - 12.7)
1296MHz	3 (76)	7 (178)	2 (50)	1 1/8 (28)	1/4 - 1/8 (3.2-6.4)
Turns	6	8	10	12	20
Gain	12dBi	14dBi	15dBi	16dBi	17dBi
Beamwidth	47°	41°	36°	31°	24°

Dimensions in inches, millimetres are given in brackets. The gain and beamwidth of the helical antenna are dependent upon the total number of turns as shown above.

Bandwidth = 0.75 to 1.3λ

$$\text{Feed impedance} = 140 \times \frac{\text{circumference}}{\lambda} \text{ ohms}$$

(Note: λ and circumference must be in the same units.)

$$\text{Beamwidth (degrees)} = \sqrt{\frac{12{,}300}{\text{No of turns}}}$$

Table 16.13: General dimensions for 144, 433 and 1296MHz helix antennas

A helix may be used to receive plane or circularly polarised waves. When signals are received from a transmitting helix care must be taken to ensure that the receiving helix has a 'thread' with the same hand of rotation as the radiator, or significant signal will be lost due to *polarisation mismatch*.

The properties of the helical antenna are determined by the diameter of the helix *D* and the pitch *P* (see **Fig 16.31**). It is also dependent on radiation taking place all along the helical conductor. The gain of the antenna depends on the number of turns in the helix.

The diameter of the reflector *R* should be at least λ/2, with the diameter of the helix *D* about λ/3 and the pitch *P* about 0.24λ. A detailed description of the way in which the antenna radiates, and the relationships between pitch and diameter for different antenna characteristics are described by its inventor, J D Kraus in [25].

A helix of this design will have a termination / feed impedance of about 140 ohms. A 50-ohm impedance can be obtained by shaping the last quarter turn from the feedpoint to lie close to the reflector by reducing the pitch of the helix over the last turn. Gain of the antenna is proportional to the number of turns in the helix, and may be enhanced slightly by tapering the open end towards the centre.

At higher frequencies an additional 1dB can be obtained by replacing the flat reflector with a cup that encloses the first turn. However, the theoretical gains published by Kraus and others are optimistic. (**Fig 16.32**) Maximum realisable gains are given by following formula for helix lengths between 2 and 7 wavelengths.

$$G_{max} = 10.25 + 1.22L - 0.0726L^2 \text{ dBi}$$

where *L* is the length of the antenna in wavelengths.

A typical antenna with a seven turn helix has a gain of approximately 12dBi over a 2:1 frequency range. To fully utilise this gain it is necessary to use a circularly polarised antenna (eg a helix of the same sense) for both transmission and reception. If a plane-polarised antenna, such as a dipole, is used there will be an effective loss of 3dB due to polarisation mismatch.

General dimensions for helix antennas are shown in **Table 16.13**.

A Practical Helix Antenna for 144MHz

The greatest problem to be overcome with this type of antenna for 144MHz operation, with a helix diameter of 24½in, is the provision of a suitable support structure.

Fig 16.33 shows a general arrangement in which three supports per turn (120° spacing) are used. Details of suitable drilling of the centre boom are given in **Fig 16.34**.

The helix may be made of copper, brass, or aluminium tube or rod, or coaxial cable. This latter alternative is an attractive material to use, being flexible with the braid 'conductor' weatherproofed. If coaxial cable is used the inner conductor should be connected to the outer at each end, and the jacket well sealed to prevent moisture ingress and corrosion.

The reflector is located at a distance *a* behind the start of the first turn, and is supported by crossed supports from the central boom. Material for the reflector can be any kind of metal mesh such as chicken netting. Radial spokes alone are not sufficient and will



Fig 16.33: General arrangements of support structure for a five-turn helical antenna for 144MHz. The antenna is right hand circularly polarised



Fig 16.34: 144MHz helix first side drilling dimensions (a), reflector holes are drilled at right angles; (b) and (c) are drilled at intervals of 120 and 240 degrees respectively from (a). (d) cutting and filing dimensions for the element stand-offs

reduce the gain by 1-2dB, unless connected together with wires in dartboard fashion.

It is not essential that the central boom should be constructed of non conductive material. Metal booms may be used provided that they are centrally placed along the axis of the helix. This can lead to a simple construction using square aluminium tubing, as sold for self-construct shelving in some DiY centres. Corners and end fixtures can also be used to fasten the boom rigidly to the reflector without having to resort to machining or fabricating brackets. A square section also simplifies the mounting of the insulators, which can be made from Delrin or other plastic rod, and secured through the boom by a long screw or bolt with a single hole at the far end through which to thread the helix. The number of insulators will depend upon the rigidity of the helix material. At 433MHz, supports every 1.25 turns are adequate for a helix made from copper tubing.

Although probably too heavy for 144MHz designs, copper tubing for small-bore central heating is suitable for 433MHz helices. It is readily obtainable in DiY centres in malleable coils that can be easily shaped over a suitable former. Draw a line with a wax pencil or paint along adjacent turns whilst they are still on the former, which if sized correctly, will allow the turns to be drawn out to the correct positions whilst the marks remain in a straight line. This helps considerably when ensuring the turns diameter and pitch are maintained along the length of the helix. The ends of the tube should be hammered flat and soldered up to prevent the ingress of water.

The last fractional turn of the helix closest to the reflector should be brought very close to the reflector as it approaches the connector, to bring the impedance of the helix to 50 ohms. Helix antennas for higher frequencies are easier to construct than Yagi antennas of comparable gain and require little adjustment. Detailed instructions for building 435MHz and 1296MHz helix antennas for satellite communications have been published in [26] and [27].

HAND-HELD AND PORTABLE ANTENNAS

Normal Mode Helix

The normal mode helix antenna comprises a length of spring wire wound such that the diameter of the spring is less than 0.1λ, and typically of order 0.01λ. Such antennas become resonant when their axial length is around 0.1λ, and can be designed to offer manageable impedances at the base. The resonance occurs over a relatively narrow band, and is heavily influenced by any jacket or sleeve fitted over the helix, and by the nature of the groundplane (if any) against which it is fed. The current distribution along the length of the helix is similar to that of a whip antenna, but compressed into the much shorter length of the helix.

For hand-held radios, the length of the helix is dimensioned such that the current distribution is similar to that expected on a 5/8λ whip, ie the current maximum occurs about one third of the overall height above the feed point. This helps to maximise the radiation efficiency of the antenna, whilst also minimising effects of the variability of the ground plane (hand held radio) and body proximity on both the input impedance and radiating efficiency.



Fig 16.35: A typical commercial helical antenna with screw mounting facility



Fig 16.36: Details of a home-made helical whip for 145MHz. A BNC plug could also be used

A $3/4\lambda$ whip over a moderate ground plane has a resistive match very close to 50 ohms. If this whip is coiled into a helical spring it will match to approximately 50 ohms and resonate at a lower frequency, partly due to capacitance between the coil turns.

If the spring is trimmed to the original frequency the result will be an antenna of about 0.1λ overall height. The actual length of wire is between $1/2\lambda$ and $5/8\lambda$ at the working frequency. Electrically it is still a resonant $3/4\lambda$ antenna. Near-base capacitance also modifies the matching under certain frequency and ground plane conditions.

If the turns are very close together, the helical antenna will resonate at a frequency approaching the axial length, because of strong coupling between the turns. There is an optimum 'spacing' between turns for best performance. A 145MHz helical antenna typically has a spacing between turns equal to twice the diameter of the wire used.

The helical whip is very reactive off-resonance. It is very important that it is resonated for the specific conditions that prevail in its working environment.

Fortunately, it is often only necessary to change the number of turns to resonate the spring over such diverse conditions, ie a large ground plane or no ground plane at all. The resistive part of the impedance can vary between 30 and 150 ohms at the extremities.

Under typical 'hand-held' conditions (**Fig 16.35**), although to a small extent depending on the frequency of operation, the spring can offer something close to a 50-ohm impedance match. **Fig 16.36** shows the number of turns required for a typical 9mm diameter helix for $3/4\lambda$ resonance.

As the helical is reduced in length two effects occur. First, the radiation resistance is lower than the equivalent linear whip so the choice of a good conducting material is important to reduce resistive losses. A plain steel spring compared with a brass or copper-plated helix can waste 3dB of power as heat. Secondly, the physical aperture of the helical whip is around one third that of a $\lambda/4$ whip, which would imply a loss of 4.77dB.

Results obtained from copper-plated, Neoprene-sheathed helical antennas, correctly matched to a hand-held transmitter at 145MHz, provided signals at worst 3dB and at best +1dB compared with a $\lambda/4$ whip. A $\lambda/4$ whip with minimal ground plane would offer signals about 6dB compared to a $\lambda/2$ dipole.

A helical antenna, resonant and matched, on a $\lambda/2$ square ground plane can give results 2-3dB below a $\lambda/2$ dipole. An alternative arrangement using a bifilar-wound helix gives identical results (within 0.2dB) to a $\lambda/2$ dipole.

A Vertical Dipole for Portable Operation

A practical dipole for portable operation on in either the 2m or 6m band [28] is shown in **Fig 16.37**. The upper and lower sections together form a centre-fed half wavelength dipole. The feed cable is wound into a resonant choke to present a high impedance to the lower end of the dipole to reduce currents on the outside of the feed cable. Constructed from RG58CU cable or similar, the antenna can be rolled up into a small space for travel, then unrolled and suspended from a suitable support for operation.

3870mm of RG8CU cable is required for 145MHz operation. 470mm of the outer sheath and braid is stripped off, leaving the insulator and inner core to form the upper radiator. Measure out the length of the lower radiator from where the insulator is exposed to mark the starting point of the choke. Wind 4.6 turns on 32mm diameter PVC pipe to from the choke. Feeding the cable through holes in the centre of end caps on the pipe allows the antenna to hang tidily. A ring terminal or solder tag soldered to the tip may be used for hoisting the antenna on nylon line or similar.

Tuning should be done outdoors, with the antenna positioned well away from objects that could affect the resonant frequency. Trim short pieces from the tip of the antenna to obtain a VSWR better than 1.3:1 (in 50 ohms) across 144 - 146MHz. If a longer feeder is required, the length below the choke should be a multiple of one half wavelength (680mm to compensate for the velocity factor of the dielectric) to minimise de-tuning.

A 6m variant can be constructed using 7280mm of RG858CU cable. 11.8 turns of cable should be wound on a 50mm diameter PVC tube to form the choke. Any additional feeder should be a multiple of 1980mm.

HB9CV Mini Beam

The HB9CV mini-beam, because of its compact and straightforward construction, is suitable for both base station and portable use, and can be particularly useful in confined spaces such as lofts. Similar antennas are the lazy-H and ZL Special often used on the HF bands. The HB9CV version has one or two mechanical advantages that make it particularly suitable for VHF portable use.



Fig 16.37: The "feedline vertical" antenna


External thread
Nuts
Internal thread
340
380
20
12
6 dia
X.... insulated supports
144
5 spacing
X
X
130
950
290
10 dia
15
6 dia
290
1030
BNC or PL259 panel mounting socket
Wing-nut for mounting on mast
120
Series compensating capacitor
1·5mm dia plastic insulated or tinned copper wire
Screw with solder tag or soldered directly to the element
251 spacing
4 dia
4 dia
Director
Reflector
Material..... brass
Dimensions are in millimetres
V4-30

Fig 16.38 A collapsible HB9CV antenna for the 144MHz band (*VHF Communications*)


Reflector
Director
Approx 6 to 8mm dia aluminium tube or rod
Solder tag
Series tuning capacitor 3 to 30pF compression trimmer
5mm spacing
18swg tinned copper wire
Approx 20mm square aluminium tubing boom extended at this end to form a handle
Feed-through or stand-off insulators
Clearance hole in boom, tapping hole in element
5mm spacing
Solder tag
Direction of radiation
Self-tapping screw or nut and bolt to lock the element
5mm spacing
5mm spacing
BNC or similar coaxial socket
Hole through boom to give good fit for the element
V4-31

Fig 16.39: Alternative boom and feed arrangement for the 144MHz HB9CV antenna



Fig 16.40: HB9CV antenna radiation patterns. Antenna 10m above ground

Fig 16.38 [29] and **Fig 16.39** show two methods of construction for the HB9CV antenna. Note that a series capacitor of 3-15pF is required to adjust the gamma match/phasing combination to a VSWR of about 1.3:1 referred to 50Ω. The element spacing, and in particularly the transmission line spacing (5mm in this case), is critical for optimum impedance matching and phasing, and therefore gain and front-to-back ratio.

The principle of operation is as follows. If two dipoles are close spaced (typically 0.1 - 0.2λ) and fed with equal currents with a phase difference corresponding to the separation of the dipoles, 'end-fire' radiation will occur along the line between the dipoles in one direction, and almost no radiation will occur in the reverse direction as explained earlier in this chapter in the section on arrays.

The different element lengths found on most HB9CV antennas improve the VSWR bandwidth, not the directivity as might at first be thought by comparison with a two element Yagi antenna.

The end at which the beam is fed defines the direction of radiation. A theoretical gain in excess of 6dBd should be possi-



Fig 41: HB9CV antenna radiation patterns. Antenna hand-held, 1-2 metres above ground


All dimensions in millimetres
290
370
130
14
14
137
10mm dia
274
PVC tape over end for safety
14
6·5
Insulator detail
2mm dia enamelled copper wire
4mm plug inner
Flexible steel measuring tape
Elements detail
12mm
5·1mm dia
Feed point
312
CD1285

Fig 16.42: Construction details of lightweight HB9CV antenna for 144MHz

ble. Depending on construction techniques, gains of 4 to 5dBd with front-to-back ratios of 10 to 20dB tend to be obtained in practice. The radiation patterns shown in **Fig 16.40** and **Fig 16.41** are for the antenna of Fig 16.38. This antenna has a typical gain of 5dBd. Note the difference obtained when mounted at 10m (30ft) above the ground compared with hand-held measurements 1-2m above the ground. The latter height is typical for the antenna being used for direction finding.

Lightweight HB9CV for 144MHz

The compact size of the HB9CV design makes it eminently suitable for direction finding contests, EMC or interference probing, and portable work. The need for a very lightweight directional antenna for EMC investigations led to the design shown in **Fig 16.42**.

The boom and stub elements are made from thin walled brass tubing, soft soldered or brazed together. The removable elements are made from an old 12mm wide spring steel measuring tape soldered on to 4mm ‘banana’ plugs, although replacement tapes without housings can be purchased from good tool shops. The sharp ends must be protected by at least one layer of PVC tape or similar material. The feedline insulator where it passes through the boom can be made from Delrin or a scrap of solid polythene insulator from coaxial cable. The series matching capacitor in the example shown is 13pF, but should be adjusted for minimum VSWR, and the end of the coaxial cable and exposed connection to the capacitor should be sealed with silicone rubber compound if outdoor use is envisaged. The antenna can be supported on a simple wooden mounting using small ‘Terry’ spring clips to grip the boom.

MOBILE ANTENNAS

The choice of an antenna for mobile VHF and UHF use is dependent on several factors. As the frequency increases the aperture of the antenna decreases, and propagation losses increase. This means that higher antenna gains are required for UHF than VHF to overcome the losses of both aperture and path.

Considerable reduction of beamwidth in the vertical plane is needed to achieve gain whilst retaining an omnidirectional pattern in the horizontal plane. A compromise has to be made to obtain maximum gain in the best direction that gives minimum disruption of signals when mobile.



Fig 16.43: Two ways of feeding a helical antenna on a groundplane: (a) shunt feed, (b) series feed

For example an omnidirectional antenna of 6dBd gain will have a typical half-power beamwidth in the vertical plane of under 30°. The narrow disc shaped beam that is produced can result in considerable variation in transmitted and received signal strength as the vehicle or antenna tilts. This is particularly the case where signals are reflected from nearby objects.

The choice of polarisation is not only dependent on compatibility with stations being received and the optimum for the propagation path. The aesthetics, mechanical complexity, safety and the mounting position of the antenna on the vehicle must be considered.

High-gain, relatively large, antennas suffer gain reductions with probable loss of omnidirectionality if the antenna is not roof mounted. The difference in mounting an antenna on the wing or boot of a car compared with mounting it on the top dead centre of the car roof can be at least 3dB. Variation of the radiation pattern can occur due to close-in reflections and surface-wave effect across the vehicle, as well as restriction of the 'line of sight'.

Normal Mode Helix on a Groundplane

The normal-mode helical (spring) antenna, when vehicle mounted, offers a gain approximately 2 to 3dB less than a dipole, but the overall height is reduced to the order of 0.1λ. An acceptable match to 50 ohms can often be obtained by simply adjusting its resonant length. Alternatively, a small inductance or capacitor across the base or an input tapping on an 'earthed' helical, as shown in **Fig 16.43**, will provide the required matching. The design and limitations of the normal mode helix were discussed earlier in this chapter under the heading of hand-held antennas.

Fig 16.44: The λ/2 antenna and its grounded λ/4 counterpart. The missing λ/4 can be considered to be supplied by the image in ground of good conductivity





Fig 16.45: Decibel radiation pattern of a λ/4 monopole over a λ/2 square groundplane at 145MHz

Quarter-wave Whip

This is the simplest and most basic mobile antenna. The image of the vertical λ/4 section is 'reflected' in the ground plane, producing an antenna that is substantially the same as a dipole, provided that the ground plane is infinitely large and made of a perfectly conducting material (**Fig 16.44**). In this case, all of the radiation associated with the lower half of the dipole is radiated by the top half, resulting in a 3dB improvement in signal strength in a given direction for the same power input to the antenna.

In practice the size of the ground plane and its resistive losses modify the pattern. The full 3dB is never realised. Measurement of a 5GHz monopole on an aluminium ground plane of 40 wavelengths diameter showed a gain of 2.63dBd. **Fig 16.45** and **Fig 16.46** show optimum patterns of a λ/4 whip measured on a ground plane of λ/2 sides and 1λ sides. Although the pattern is raised from the horizontal, on a medium sized ground plane the loss of horizontal gain is relatively small (20° and 1dB at 0° in Figure 45, but 40° and 6dB at 0° in Fig 16.46). However, as the groundplane size increases, the main lobe continues to rise until the situation of **Fig 16.47** pertains.

When a vertical radiator is mounted over a ground plane as described, the input impedance is typically halved. For the λ/4 whip or monopole, the input impedance is typically 36Ω - jX, that is to say approximately half the resistance of the dipole but with an additional reactive component. With 50 ohm cable impedance this would produce a standing wave ratio at the antenna base of about 1.5:1.

The simplest way to overcome this mismatch is to increase the length of the whip to produce an inductive reactance to cancel the capacitive reactance normally obtained. In practice an increase in length also raises the resistive value of the whip and a close match can usually be obtained to a 50-ohm cable.



Fig 16.46: Decibel radiation pattern of a λ/4 monopole over a 1λ square groundplane at 145MHz



Fig 16.47: Radiation pattern of whip on large groundplane showing elevation of the main lobe

At VHF (145MHz) the λ/4 whip's simplicity and limited height (about 49cm/19in) is often an accepted compromise. At 70MHz the physical dimensions (about 102cm/40in) are such that size is the usual limit, making a 1/4λ whip preferable to a 'gain' antenna. The effective aperture of the antenna at this frequency is compatible with path loss conditions, and the ground-plane size, when roof-mounted on a vehicle, is such that the radiation angle is fairly low. However, the shape of the radiation pattern can result in a gain reduction of 3dB to each side of the vehicle.

Half-wave and Five-eighths-wave Antennas

Ground-plane techniques described for the 1/4λ whip can be used for vertical gain antennas. If the 1/2λ dipole is extended in length, maximum forward gain (before the pattern divides into several lobes) is obtained when the dipole is about 1.2λ. This corresponds to a maximum length of 5/8λ for a ground-plane antenna.

A natural extension to the 1/4λ whip is the 1/2λ whip. However, such a radiator fed against a ground plane has a high input impedance. On the other hand, a 3/4λ radiator fed against a ground plane has a resistive input close to 50 ohms. Unfortunately, the resultant radiation pattern in the elevation plane is less than optimum.

If the 1/2λ whip could be made to look like a 3/4λ radiator then it would be possible to obtain a 50-ohm resistive input. A series coil at the ground-plane end of a 1/2λ radiator can be used to resonate at 3/4λ, but the input is still of fairly high impedance and reactive. If, however, the coil is shorted to the ground plane, tapping up the coil will provide the required


λ/2
Radiating element
(102cm)
Hinge or screw-mounted whip
≃6 turn inductor adjusted for resonance with match tapping at 2 turns before moulding
Series capacitor ≃15pF
Epoxy resin moulding
Ground plane (vehicle surface)
Mounting screwed bush
50Ω coaxial cable
V4-8

Fig 16.48: A home-built mobile antenna and mount


5/8 λ
Radiating element
(126 cm)
PVC sleeving on a copper-plated drawn-steel rod
Series coil
6 turns at approx 3/16" dia
Standard hinged-base mounting
V4-9

Fig 16.49: A typical commercial 5/8λ mobile antenna and mount

match/input point. The addition of a capacitor in series with the input will compensate for the remaining reactive component. **Fig 16.48** shows details of such an antenna.

As the aperture of the antenna has been doubled compared with the 1/4λ whip, the gain over the whip approaches 3dB. Achievement of this figure requires minimum losses in the radiating element, ie it must be copper-plated or made from a good conducting material.

The maximum radiator size of 5/8λ for a single-lobe pattern can also make use of the impedance characteristics of the 3/4λ radiator.

Construction is simpler than for a 1/2λ antenna. If the radiating element is made 5/8λ long, and a series coil is placed at the ground plane end, an input impedance very close to 50 ohms can be obtained. With correct materials a gain close to 4dBd can be achieved from the further increase in effective aperture. The radiation pattern is raised more than that of a 1/2λ antenna, so the improved gain of the 5/8λ may not always be realised. However, the simplicity of construction is an advantage.


Centre element
D
Radiating element
A
0·425λ
5/8 λ
Sleeve
d
Sleeve to element diameter ratio typical 2:1 or greater
A
Reactance sleeve
0·2λ
Ground plane surface
50Ω coaxial cable
V4-10A

Fig 16.50: The reactance-sleeve 5/8λ monopole (*Ham Radio*)

Fig 16.49 gives details of the series 5/8λ whip. One other advantage of this antenna is that over a wide range of mounting and ground-plane conditions it will self-compensate for impedance and resonance changes. It is preferable for both the 1/2λ and 5/8λ antennas to be 'hinged', particularly if roof-mounted, to enable folding or 'knock down' by obstructions, eg trees and garages.

Various gain figures have been reported for the 5/8λ whip antenna. Unfortunately not all antennas use optimum materials. Resistive steel wires or rods produce heating loss, and the use of a glass fibre-covered wire changes the resonant length by as much as 20%. The radiator therefore has to be cut shorter than 5/8λ, with an accompanying loss of aperture.

The construction of the series coil is important. Movement of the coil turns will change the antenna's resonance, giving apparent flutter. Some transceivers with VSWR-activated transmitter close-down will be affected by change of resonance of the antenna. This can make the power output of the transmitter continually turn down or be switched off, producing what appears as extremely severe 'flutter' on the transmission.

Several of the '5/8λ ground-plane antennas' discussed in various articles are in fact not truly antennas of this nature.

One of these devices worth considering for its own merits is that shown in **Fig 16.50**. It consists of a 5/8λ vertical element with a reactive sleeve of 0.2λ at the ground-plane end. The gain obtained from this antenna is typically 1.8dBd. As can be seen, the actual radiating element A-A is shorter than a 1/2λ antenna.

Another antenna family, with similar properties but different in construction, includes the 'J' and Slim Jim. These are described later in this chapter.

Seven-eighths-wave Whip

This mobile antenna is derived from the Franklin collinear shown later in this chapter. It consists of two 1/2λ elements coupled by a series 'phasing' capacitor. One effect of the capacitor is to resonate the combined elements at a lower frequency than that of a single 1/2λ element. However, reducing the length of the top element tunes the arrangement back to the original frequency.

The base impedance above a perfect ground plane is 300-400 ohms with some capacitive reactance. A series loading coil


0·341λ
0·439λ
2p2
Phasing capacitor
Base matching coil
15p
50Ω
CD423

Fig 16.51: The 7/8λ whip antenna. This is effectively two shortened half-wave elements in series with a series phasing capacitor between them. The assembly shown is that of a commercial form of the antenna. The dotted lines show the approximate current distribution

in combination with an L-matching section gives a good match to 50-ohm coaxial feeder. The match is maintained with quite modest ground plane size (1/4λ radials or 1/2λ diameter metal surface). This makes the 7/8λ whip suitable for vehicle mounting or for use as a base-station antenna.

The final length of the two radiator elements is somewhat dependent on their diameters and the design of the series capacitor and matching unit. Fig 16.51 shows the general appearance and dimensions of a commercial version of the 7λ/8 whip, together with typical circuit components and current distribution in each element.

The theoretical gain of this antenna is 4.95dBi (2.8dBd) over a perfect ground plane. The professionally measured gain, with the whip on a 1m ground plane, was slightly over 4.7dBi for the full 144MHz band. The radiation pattern in the E (vertical) plane was predominantly a single lobe (torus/doughnut) peaking at 4° above the horizon and with a 3dB beamwidth of 38.5°.

Fig 16.52: The mechanical construction of the Omni-V (dimensions are in millimetres)


550
111
MATERIAL...... 12·7 DIA x 1.2MM SEAMLESS 4 OFF REQUIRED
102
12·7
25·4
1"
END CAPS
4 HOLES 4·8 DIA
MARK CASTINGS WITH SAW-CUT FOR 45° POSITION
M5 BOLT x 102 LONG LOCKWASHER
WINGNUT LOCKWASHER M5 SCREW x 32LG 46 MPC
45°
16 MPC M5 SCREW x 32 LONG
λ/4 STUB
46 MPC
M5 WINGNUT
16MPC
'Q' BARS
TUFNOL ROD 12·7 DIA x 48 LONG DRILLED AND TAPPED 12·7 x 47·6 DEEP AT BOTH ENDS
19
4·8 DIA HOLES
PLAN VIEW
940
MATERIAL..... 9·5 DIA x 1MM SEAMLESS 4 OFF REQUIRED
END CAP
END CAP AT BOTH ENDS
19
MED Z
HI Z
END CAPS
4·8 DIA HOLES
'Q' BARS
SIDE ELEVATION
600Ω
PVC COVER
MATERIAL.... 9·5 DIA x 1MM SEAMLESS 2 OFF REQUIRED
1041
1041
1067
600Ω
M5 SCREW x 19 LONG LOCKWASHER 8 MPC 47 MPC (PAIR) RUBBER WASHER M5 WINGNUT
533
'Q' BARS
12·7
32 DIA x 1·4MM 1829 LONG
889
λ/2 BALUN
BRACKET JBL 29/2
300Ω
COAX CLIPS
M5 SOLDER TAGS
RUBBER 'O' RINGS M5 FULL NUTS SLOTTED NUT 9·5 LONG
CUT 'V' TO SUIT PHASING BARS
FEEDER
M33
λ/2 BALUN
M5 SCREWS 32 LONG



Fig 16.53: Formation of the Omni-V antenna



Fig 16.54: The horizontal radiation patterns for an Omni-V antenna and its bi-directional counterpart



Fig 16.55: Chart showing gain and VSWR as a function of frequency for the Omni-V and the bi-directional antenna

OMNIDIRECTIONAL BASE STATION ANTENNAS

Omni-V for 144MHz (Horizontally Polarised)

This antenna consists of a pair of λ/2 dipoles. The centres of the dipoles are physically displaced to produce quadrature radiation with the ends of each dipole supported on a λ/4 shorted stub. A pair of Q-bars are tapped down the stubs to a point where the impedance is 600Ω as shown in **Fig 16.52**. When the two units are fed in parallel, they produce an impedance of 300Ω at the centre. A 4:1 balance-to-unbalance coaxial transformer is fitted to the centre point of the Q-bars to enable a 75Ω coaxial feeder cable to be used. A 50Ω feed can be arranged by repositioning the Q bars on the antenna stubs to provide a tap at 400Ω on the stubs. This can be achieved by monitoring the VSWR on the coaxial feeder whilst adjusting the Q bar position by small but equal amounts on both stubs. The balun should, of course, be constructed from 50Ω coaxial cable (transforming from 200Ω in the balanced section) for a match to 50Ω. The general arrangement is shown in **Fig 16.53** showing how the antenna may be arranged to give either an omnidirectional or bi-directional radiation pattern, and typical radiation patterns for either case are shown in **Fig 16.54**. **Fig 16.55** shows the gain and VSWR of these antennas as a function of the centre frequency.

Quarter-wave Groundplane Antenna

This is one of the simplest omnidirectional antennas to construct and usually yields good results. However, some unexpected effects may occur when the antenna is mounted on a conductive mast, or if RF current is allowed to flow on the outside of the feeder.

In its simplest form, the ground plane antenna comprises a quarter-wavelength extension to the inner of a coaxial cable, with several wires extending radially away from the end of the outer of the coaxial cable, **Fig 16.56(a)**. The input resistance will be quite low, in the order of 20 ohms, although this may be transformed to a higher impedance by using a folded monopole radiator as shown in **Fig 16.56(b)**. Equal diameter elements provide a 4:1 step-up ratio to around 80 ohms, and a smaller diameter grounded leg can reduce the input impedance to 50 ohms. The feedpoint impedance can be modified by bending the groundplane rods downwards from the horizontal, **Fig 16.56(c)**. If the radiating element and the groundplane rods are all λ/4 in length, the input resistance is approximately:

$$R = 18(1+\sin\theta)^2 \quad \text{ohms}$$

where θ is the groundplane rod angle below the horizontal, in



Fig 16.56: Quarter wave groundplane antennas



Fig 16.57: Radiation patterns of quarter-wave groundplane antenna, (a) with and (b) without a metallic mast

degrees. A 50 ohm resistance is achieved when θ is 42 degrees.

The ends of the groundplane rods are sometimes joined together with a conductive ring to provide additional mechanical stability. The ring increases the electrical size of the groundplane, and the length of the radials can be reduced by about 5%.

The few rods forming the groundplane usually do not prevent current flowing on any conductive supporting mast, or on the outside of a coaxial feeder. The mast or feeder can become a long radiating element which may enhance or destroy the radiation pattern of the antenna, dependent upon the magnitude and phase of the mast currents relative to that on the antenna. An example of this is shown in **Fig 16.57(a)**, where the monopole and groundplane is mounted on a 5λ mast (about 10 metres). The corresponding radiation patterns without mast or cable influences are shown in **Fig 16.57(b)**. The effects of ground reflections have been ignored in both cases.

Some antenna designs make use of these currents to enhance the gain of the monopole, and sometimes have a second set of groundplane rods further down the mast, tuned to present a high impedance to reduce currents flowing below that point. The mast currents can be reduced a little by using more radials in the groundplane or extending their length to around 0.3λ.





Fig 16.58: Shape and dimensions of the radiator wire

Fig 16.59: Matching section and resonant groundplane radials

An open circuited choke sleeve can be more effective than radial wires for mast current control. This technique is used in the skirted antenna described later in this Chapter.

A Dual-band Whip for 145/435MHz

This base station antenna, devised by Bert Veuskens, PA0HMV acts as an end fed antenna on 145MHz with a gain of 0dBd, and two stacked 5λ/8 radiators with a gain of about 5dBd at 435MHz [30]. The radiator is made from 2mm copper wire, formed as shown in **Fig 16.58**. The coil at the base and a series capacitor provides the matching network at 145MHz. The folded stub section at the centre ensures the upper and lower 5/8λ sections radiate in phase at 435MHz. A groundplane comprising four short radials resonant at 435MHz is fixed to the input connector, see **Fig 16.59**. No groundplane is required for operation at 145MHz, although the coaxial feed can be coiled close to the connector to choke off any current on the outside of the cable. The whole assembly is fitted inside a section of PVC tube for support and protection from the weather.

Assembly

A list of materials is given in **Table 16.14**. The corners of the coaxial socket are filed off to make it a snug fit in the 28mm copper pipe, and a hole is required for the earthy end of the matching coil as shown in **Fig 16.60**. The radials should be cut slightly too long to allow for trimming after assembly. A jig to hold the radials and connector in place during soldering is essential,

Copper or brass mounting tube, 28mm OD x 220mm
PVC tube, 32mm OD, 28mm ID, x 1.2m
Jubilee clip, 32mm, preferably stainless steel
N-type 50Ω socket, PTFE dielectric, with square flange
Brass rod or tubing, 3mm OD x 720mm for radials
Bare or enamelled copper wire, 2mm (14SWG) 1.6m
Copper/brass tube or inner from connector block to butt-joint radiating elements (discard screws)
Tubular trimmer capacitor, 10pF or RG58 cable per Figure 61. Ensure that the capacitor can handle the transmitter power safely.
Silicone rubber sealing compound or bathroom sealant

Table 16.14: Materials required for 145/435MHz omni antenna



Fig 16.60: Details of the coaxial socket and attachment of radials



Fig 16.61: RG58 coaxial cable capacitor. Note that the length may need to be adjusted for best match

Fig 16.62: Phasing stub bending detail



and can be made from a piece of chipboard. After soldering, each radial should be trimmed to 173mm measured from the centre of the socket.

The rotor terminal of the trimmer capacitor, or the centre conductor of the RG58 coaxial cable capacitor (**Fig 16.61**) should be soldered to the centre pin of the connector next. Prepare the matching coil by straightening and stretching 60cm of the antenna wire. If enamelled wire is used, scrape off the enamel at one end and at the capacitor tapping point before winding up and shaping on a 19mm former of tube, rod or dowel as shown in Fig 16.59. Solder the end of the coil into the hole drilled in the flange of the coaxial socket and connect the free end of the matching capacitor to the coil, four turns above the soldered end. Approximately 200mm of the lower radiator should be projecting upwards, coaxially with the coil.

With the remaining wire, shape the phasing section as in **Fig 16.62** using a 9.5mm drill bit as a former. Trim the lower wire end so that it makes up the 450mm length shown in Fig 16.58 with the wire on the coil when the ends are butted together. Prepare a polystyrene foam disc to centre the wire within the PVC support tube and slide onto the radiator wire below the phasing stub. Butt-splice the two wires together by soldering them into a short piece of copper tubing or the inner part of a small cable connector with the screws removed.

Cut the top wire to 460mm. Fit a second foam centreing disk on to the top wire. Four slots, 90 degrees apart, 7mm deep and 4mm wide are cut at one end of the copper pipe to clear the groundplane radials. This pipe will be used to clamp the finished antenna to the top of its mast with U-bolts and saddles.



Fig 16.63: Mounting tube and PVC cover details showing slots to clear radials

Tuning

Pass a short 50-ohm cable through the copper pipe and connect it to the N socket. Push the pipe over the socket until the groundplane radials are resting in the bottom of the four slots in the tube. Set up the antenna without its cover tube well clear of objects that could de-tune it, but low enough for the top to be accessible. Trim the top element for minimum VSWR in the 70cm band at a frequency 3MHz higher than required, eg 438MHz for 435MHz operation. The PVC cover tube will reduce the frequency by this amount when it is installed. Fix the two centreing discs in place with a drop of epoxy glue, at 170mm below the end of the top wire and halfway between the top of the coil and the bottom of the phasing stub for the lower wire.

Slide the PVC cover tube (**Fig 16.63**) over the antenna until the radials are fully seated in the slots, check that the minimum VSWR is below 1.5:1 and at the desired frequency in the 70cm



Figure 15.64: Photograph of finished antenna installed on mast



Figure 15.65: Skirted dipole antenna with mast choke



Fig 16.66: Gain sleeve dipole

band. Raise the PVC tube just enough to allow access to the trimmer/cable capacitor and adjust for minimum VSWR at 145MHz. Push the PVC tube down again and secure with the Jubilee clip below the radials. Cap and seal the top and weatherproof the slots with sealant to keep rain out, whilst leaving a hole to prevent condensation from being trapped. The finished amntenna is shown in **Fig 16.64**.

The Skirted Dipole Antenna

The skirted dipole antenna (**Fig 16.65**) does not require groundplane radials, and can be mounted in a cylindrical radome for better appearance and lower wind induced noise. The skirt forms the lower part of a half wave dipole, and being one quarter wavelength long, presents a high impedance at its lower end, reducing unwanted currents on the mast. The current is further reduced by a second choke, with its open, high impedance end placed one quarter wavelength below the dipole skirt for best effect. The radiation pattern of this antenna closely resembles that of a half-wave dipole in free space.

Gain sleeve dipole

The *gain sleeve dipole* (**Fig 16.66**) is derived from the 1.8dBd shunt-fed 5/8λ antenna described in the section on mobile antennas.

The radiating element B-B is a 1 element fed part way along its length with a 0.2λ series short circuited stub to provide the transformation to 50 ohms and phasing. The impedance of asymmetrical antennas was investigated by R W P King [31], and has a number of applications in the design of groundplane antennas with elevated feedpoints. Having approximately twice the aperture of the λ/2 dipole, a gain of typically 2.5-3dBd is achieved.

Mechanical construction is open to interpretation but 'beer can' or plastic water pipe formats offer two solutions. Note that the mounting point should be at A-A and not on the 0.25λ sleeve.

The Discone

The discone is often used where a single omnidirectional antenna covering several VHF/UHF bands is required. A single antenna is capable of covering the 70, 144 and 432MHz bands or 144, 432 and 1296MHz. However, as the antenna can operate over roughly a 10:1 frequency range, it will more readily radiate harmonics present in the transmitter output. It is therefore important to use a suitable filter to provide adequate attenuation. The radiation angle tends to rise after the first octave of frequency and this is the normal acceptable working range. If correctly constructed, a VSWR of less than 2:1 can be obtained over the octave range. One characteristic of the basic discone is a very sharp deterioration of the VSWR at the lowest frequency of operation.

The discone consists of a disc mounted above a cone, and ideally should be constructed from sheet material. However, with only a little loss of performance the components may be made of rods or tubes as illustrated in **Fig 16.67**. At least eight or preferably 16 rods are required for the 'disk' and 'cone' for reasonable results. Open mesh may be used as an alternative to sheet metal or rods.

The important dimensions are the end diameter of the cone and the spacing of this from the centre of the disc. These are instrumental in obtaining the best termination impedance, ie 50 ohms [32].

Fig 16.68 shows the key dimensions, which must satisfy the following requirements:



Fig 16.67: General arrangement of skeleton form of discone



Fig 16.68: Key dimensions of discone antenna



Fig 16.69: Details of discone hub assembly

A The length of the cone elements are $\lambda/4$ at the *lowest* operating frequency (2952/*f* MHz inches).

B The overall disc diameter should be 70% of $\lambda/4$.

C The diameter of the top of the cone is mainly decided by the diameter of the coaxial feeder cable. For most purposes 0.5in will be suitable.

D Spacing between top disc and the cone top is 20% of *C* or 0.1in for 50 ohms.

The detail given in **Fig 16.69** of the 'hub' construction will be suitable for any design using a 50-ohm feeder cable and may be taken as an example. A suitable insulator can be made with a potting resin or turned from nylon, PTFE or other stable low loss material.

The low frequency coverage can be extended by fitting a whip antenna to the centre of the disk. The antenna then operates like a quarter wave whip on a skeleton groundplane (the cone providing the groundplane). The VSWR can be optimised at a particular frequency below discone cut-off by adjusting the length of the whip, or several whips can be fitted, resonating at different frequencies, in the style of multi-band dipoles. This can be useful if the antenna is used for other purposes in addition to amateur band coverage. **Fig 16.70** shows the calculated elevation radiation patterns for a conventional discone at 145, 435 and 1296MHz, together with those of a discone of the same dimensions fitted with a 850mm whip to provide 70MHz coverage.

Collinear Dipole Arrays

Communication with mobile stations is best achieved with a vertically polarised omnidirectional antenna, as there is no need to point the antenna in the direction of the mobile. However, a fixed station is not as constrained by mechanical considerations as a mobile, and can thus be fitted with longer, higher gain antennas. This can be achieved by stacking dipoles vertically above one another in a collinear array, and feeding them with cables of equal lengths, as shown for the GB2ER repeater antenna later in this chapter. Another method of achieving gain with simpler feed arrangements is discussed below.

The current on a length of wire several wavelengths long will be distributed as shown in **Fig 16.71(a)**. The wire shown is 2λ long. Radiation at right angles to the wire will be poor, as the successive half wavelength current maxima are in opposite phases, and if the currents were equal, there would be perfect cancellation of the radiation from the oppositely phased pairs of current maxima. However, if all the current maxima were in phase, the radiated fields would add, and a high gain could be achieved. **Fig 16.71(b)**.

There are several ways of achieving this phase reversal. The simplest is to insert an anti-resonant network or a non-radiating half-wavelength of transmission line as a phasing section between the half-wave radiating elements, **Fig 16.71(c)**. The half wavelength transmission line can be realised as a quarter wavelength of ribbon cable, which can be wound around the insulator between the radiating elements (see the section on mobile antennas).



Discone alone

Discone with 850mm whip

Fig 16.70: Discone elevation radiation patterns, with and without whip for low-frequency operation. Top radials are 305mm, skirt radials 915mm and whip 850mm in length. The whip length was not optimised for 70MHz.



Fig 16.71: Current distribution on a wire, and derivation of the collinear antenna



Fig 16.72: Realisation of collinear antennas

A more subtle approach uses radiating elements that are a little longer or shorter than one half wavelength. This helps the feeding arrangements, as end feeding a half wave dipole is difficult because of its very high impedance. The self reactance of the longer or shorter dipole is then used in the design of the phasing network between the elements to achieve the desired overall phase shift. The non-radiating transmission line can then often be replaced by a capacitor or an inductor in series with the residual element reactance, **Figs 15.72(a) and (b)**. Again, a transmission line stub can be used to synthesise the required reactance, which may be more convenient or cheaper than a lumped component if significant RF power handling is required, **Fig 16.72(c)**. Sometimes a parallel tuned circuit is realised as an inductor resonated by the self-capacitance of the insulator separating the radiating elements, and upon which it is wound.

A technique devised by Franklin that has been attractive to VHF antenna manufacturers folds parts of the radiating element to provide the phasing section as shown in **Fig 16.73(a)**. Provided that the folded sections are significantly shorter than the radiating elements, the gain is not significantly degraded, although the whole structure is sensitive to capacitive loading by any housing and insulators required. The radiation pattern is frequency sensitive, and the main lobe will squint upwards or downwards as the frequency changes from the nominal. Whilst these folded element designs look attractive for home construction, adjustments to optimise both the radiation pattern and input impedance are very difficult without proper measuring facilities. Poor gain and broken radiation patterns result if the sections are not properly excited and phased.

All these designs are end-fed, which have practical disadvantages for longer, multi-element arrays. If identical sections are used, the end elements carry less current than those close to the feed, reducing the overall efficiency of the antenna. Whilst different length radiators and phasing elements can be used to equalise the current distribution, the design and adjustment is lengthy, and definitely requires good radiation measurement facilities. If the array can be centre fed, any residual phasing errors tend to cancel out, and for a given length, the performance tends to be better because of a more uniform current distribution. **Fig 16.73(b)** shows one means of achieving centre



Fig 16.73: Franklin collinear antennas, end-fed and centre fed



Fig 16.74: The J antenna

feeding with a Franklin array. Note the use of the quarter wave choke section at the base of the array, which is essential to prevent current flowing down the outer of the coaxial cable and destroying the performance of the antenna. The practical gain limit of the singly-fed collinear antenna is around 10dBi.

Practical collinear antennas in radio amateur use tend to use variations on Fig 16.72. The radiating elements may comprise combinations of lengths up to 5/8λ, with or without ground planes. The presence of a good groundplane increases the gain as the image or reflection effectively doubles the length of the array (see also the section on mobile antennas). However, good results can be achieved with collinear antennas directly mounted on pipe masts, especially if care is taken to minimise unwanted currents flowing on the mast.

The J Antenna

Collinear antennas, by virtue of their operation as end-fed structures, have high feed point impedances. A good feed arrangement, valid for both ground-plane and mast mounted antennas, is the use of a quarter-wave short-circuited transmission line, as described in the chapter on antenna fundamentals.

Fig 16.74 shows such an arrangement to end feed a half wave dipole mounted over a groundplane. The matching section should not radiate, and the overall effect is that of a half wave radiator raised λ/4 above the groundplane. Either leg of the quarter wave section can be fed, leading to the structure in **Fig 16.74(b),** which is identical to **Fig 16.74(a)** in terms of current distribution, and hence radiation performance. The evolution can be taken a stage further by removing the groundplane and feeding either leg of the quarter wave section as in **Fig 16.74(c)**; this is the 'J' or 'J-pole' antenna, which may use different diameters of tubing for the radiator and stub.

The 'Slim Jim' antenna provides an elegant solution for a simple, mechanically robust antenna made from a single piece of tubing as shown in **Fig 16.75**. This antenna, described in [33] comprises a folded, open circuit 1/2λ radiator above a 1/4λ transformer section, and is a derivative of the 'J' antenna. The folded stub characteristics of the radiator provide some control over the reactive element of the input impedance. The two ends of the tube can be joined by an insulator, eg a piece of stiff plastic tubing, to provide weather proofing and enhanced mechanical rigidity. Either balanced or unbalanced feeds can be used, tapped on to the 1/4λ transformer section at the point that provides the best match to the feeder. Coaxial feeders should be strapped or bonded to the quarter wave section to reduce unwanted currents on the outer of the cable. The antenna has a maximum gain of around 2.8dBi (0.6dBd) in free space, although the main lobe is tilted up about 10 degrees. The main lobe can be brought to the horizontal by reducing the length of the upper section to about 0.4 wavelengths. This reduces the peak gain to around 2.5dBi (0.3dBd), and can make the feed impedance capacitive.



Fig 16.75: The basic Slim Jim, showing direction of current flow and phase reversal (*Practical Wireless*)

Phasing sections and additional elements can be combined to produce a collinear form for the 'J' as shown in **Fig 16.76(a)**. This antenna and that of **Fig 16.76(c)** have been used successfully to produce low-angle radiation for the GB3SN 144MHz repeater.

A variation of the techniques described, using coils as with the original Marconi concept, is shown in **Fig 16.77(a)** for 432MHz and **Fig 16.77(b)** for 144MHz. The expected gain is between 6 and 7dBd.

Materials required for Fig 16.77(a) are as follows:

- One 2.5cm diameter 10cm long glassfibre tube.
- One 4.0mm diameter 1.2m long glassfibre rod.
- Four 2.0mm diameter 20cm long glassfibre rods.
- Length of braiding from 'junk' large coaxial or multicore cable.
- Length of 1.2mm wire for matching coils.
- Approximately 5cm square of singled sided PCB.

First, adjust the bottom 5/8λ element to give minimum VSWR by moving the tapping point on the bottom coil (approximately four turns). A fine adjustment can be made by altering the length of the first 5/8λ element.


Nylon spacers
V4-22
Plastic water-pipe for cover
λ/2
s
λ/2
λ/4
Phasing transformer
Bifilar coil resonant to λ/4
Glass-fibre or plastic cover
λ/2 or 5/8 λ
Bifilar coil resonant to λ/4
3/4 λ
Matching section
λ/4 adjust for final match
Three helical or λ/4 radials
λ/4
Epoxy resin
Mounting point
Coaxial matching transformer
Nominal 50 or 70Ω coaxial cable
50Ω coaxial down cable
50Ω coaxial down cable
(a)
(b)
(c)

Fig 16.76: A collinear form of 'J' antenna. (a) the addition of λ/4 sections as suggested by Franklin. (b) Use of a coaxial short-circuit λ/4 transformer to give an unbalanced input. The tapping point of the matching transformer is approximately 0.15λ from the 'earthy' end. (c) A variant of (b) with radials, With both (b) and (c) the λ/4 phasing transformer has been 'wound up' as a bifilar coil (each coil being wound in the opposite hand). While the inductive component is cancelled, the mutual capacitance of the windings makes them physically shorter than λ/4

Next fit the centre matching coil and the top element. To obtain the best results, both elements should be the same length and approximately 5/8λ. Further improvement in VSWR is obtained by adjusting the centre matching coil (the coil is spread over 1/4λ).

The matching coil provides the phase change necessary to feed the top element and so adjustment is quite critical. If the matching coil has to be 'squeezed up' to obtain a good VSWR, the coil has too many turns. The opposite is true if the coil has to be greater than 1/2λ for a good VSWR.

To prevent the collinear going 'off tune' once set up, the elements are secured to the centre glassfibre rod and the matching coil taped with self amalgamating tape. Provided care is taken in setting up, a VSWR close to 1.1:1 can be obtained.

Materials required for Fig 16.77(b) are as follows:

- Two 12.7mm diameter by 1206 ±12mm, 5/8λ elements (adjustable).
- Four 495mm rods for the ground plane.
- One 6.4mm diameter by 762mm insulated rod.
- One 25mm diameter insulated tube (a cotton reel can be used).
- 1.6mm wire for matching and phasing coils.

The diagram shows extra insulated tubing over the matching and phasing coils to give more mechanical strength and weatherproofing.

Setting up is carried out as follows. First, adjust the length of the bottom 5 /8 element to give minimum VSWR.

Secondly, fit the phasing coil and the top element. The top element must be the same length as the set-up, bottom element. Next obtain the best VSWR by 'adjusting' the turns of the phasing coil.


V4-29
4mm dia glassfibre rod covered with braid
5/8λ
16 turns of 1·2mm wire wound on 4mm dia glassfibre rod
1/4λ
≃1·2m
Braid
5 turns of 1·2mm wire wound on 4mm dia glassfibre rod. Tap at approx 4 1/4 turns
5/8λ
25mm dia glass-fibre
BNC Socket
1/4λ
(a)
5cm² single-sided pcb
Adjust length
Braid
5/8λ
70 to 72 turns of 1·2mm wire wound on 6·4mm dia insulated former
1/4λ
About 3050mm
Adjust length
Plastic tubing for mechanical strength and and weather-proofing
5/8λ
4 1/2 turns on 25·4mm dia former. Tap 2 1/2t for 75Ω and 2t for 50Ω
25·4mm dia insulated tube
BNC socket
4 x 489mm ground-plane radials
1/4λ
(b)

Fig 16.77: (a) A 432MHz collinear antenna (b) A 144MHz collinear antenna (*UK Southern FM Journal*)

The coil provides the phase change necessary to 'feed' the top element. It consists of a length of 1.6mm wire, (about 1λ), coiled up to give 70-72 turns on a 6.4mm diameter former. The λ/4 spacing between the two elements is more critical than the number of turns. 68 turns gave a satisfactory VSWR with the prototype.

Some difficulty may occur in setting up the phasing coil. If more than seven turns have to be removed, go back to the first adjustment stage to ensure the bottom 5/8λ element is correctly matched. If the bottom element is not correctly set up the collinear will not tune up. Careful adjustment should produce a VSWR of 1.1:1 at the chosen operating frequency.

A technique, widely used for commercial systems, combines λ/2 dipoles fed in phase from a single source, or alternatively with an appropriate variation of feeder cable length between dipoles to provide phasing.

The disadvantage with this form of antenna array is that some interaction occurs between cables and radiating elements. However, the disadvantage is balanced by the ability to modify the radiation pattern shape by simple adjustment of dipole spacing or phasing cable length.

The example given in **Figs 15.78, 15.79 and 15.80** is probably the simplest to set up and was devised for the GB3ER 432MHz band repeater. If the cables are made to be an odd number of quarter wavelengths long, an equal current feed to each dipole is assured.


350mm λ/2
1
325mm λ/2
25mm dia
650mm λ
50mm dia
2
12mm dia
Standard television antenna insulator with coaxial inner to top half. The coaxial cable is routed through the horizontal tube. Seal cap connections with silicone grease.
9
'Y'.... 50mm 'U' bolt
'Z'.... 25mm 'U' bolt
Y
Z
Z
Y
10
100mm x 100mm x 5mm thick mild steel plate
C3207

Fig 16.78: Mechanical details of GB3ER collinear


50Ω coaxial cable from transmitter
C1
2 to 10p
L
C2
2 to 10p
1
2
3
4
5
6
7
8
9
10
Ten 50Ω coaxial cables to dipoles
C3209

Fig 16.79: Matching Unit of GB3ER collinear


1
2
3
4
5
6
7
8
9
10
10 x UR43 or UR76 coaxial cables to dipoles
Solder all screening to ground plane
A
All centre conductors
L
C2
A
Copper surface of printed circuit board
Solder to ground plane
C1
A......ceramic insulating pillars
C1 and C2.... 2 to 10pF trimmers
A
Solder to ground plane
URG7 'tail' to main feeder
All coaxial cable entries must be water-tight
Die-cast box
C1
L
A
A
A

Fig 16.80: Matching unit layout for GB3ER collinear


Driven elements
λ/4 50Ω coaxial cable
λ/4 72Ω coaxial cable
0·3λ
90°
Reflectors
72Ω coaxial cable to transmitter

Fig 16.81: A crossed dipole antenna for 145MHz

ANTENNAS FOR SATELLITE COMMUNICATION

For the radio amateur, satellite ground station antennas fall into two groups. The first group comprises *steerable antennas*, which enable the passage of the satellite to be tracked across the sky. The second group consists of *fixed antennas*, which have essentially hemispherical radiation patterns to receive the satellite signals equally from any direction. These antennas do not need to be steered to receive signals during the satellite's passage. The tracking antennas are usually of high gain, while the fixed antennas are usually of low gain, due to their hemispherical coverage. Fortunately, signal losses between ground and the satelite in line-of-sight are relatively low. With no obstructions, low-gain antennas of the fixed variety are often acceptable for reception of amateur or weather satellites, helped by the higher radiated powers available from current low-earth orbiting amateur satellites.

As many satellites rotate or change their orientation with respect to the ground station, both groups of antennas are designed to provide circular polarisation. Amateur convention calls for the use of Right-Hand circular polarisation for earth/space communications. However, the downlink may have either Left or Right handed polarisation according to the satellite and frequency in use.

Of the higher-gain tracking antennas, the crossed Yagi and the helix antenna are the main ones used. The crossed Yagi is probably the easiest to construct and most readily available commercially. Construction details for these antennas were described earlier, and polarisation switching schemes are discussed at the end of this chapter.

Crossed Dipole or Turnstile Antenna

Fig 16.81 shows a simple arrangement of crossed dipoles above a ground plane for 145MHz. This type of antenna can be scaled for use at 29, 145 or 432MHz. Mechanical problems may make the reflectors inadvisable in a 29MHz version. The height above ground can be about 2m for 145MHz and 3m for 29MHz.

Typical dimensions are:

29MHz	driven elements (λ/2)	188in	4775mm
145MHz	driven elements (λ/2)	38in	965mm
	reflectors	40.5in	1030mm
	spacing (0.3λ)	24.5in	622mm

The phasing line comprises λ/4 of 72-ohm coaxial cable. The matching section for a 72-ohm feed is λ/4 of 50-ohm cable. When calculating the length of the λ/4 sections, the velocity factor of the cable must be taken into account. Typically this is 0.8 for cellular and semi-airspaced cables, and 0.66 for solid dielectric cables, but verification of the figure for the particular cable used should be obtained. As an example, a matching section of RG59/U would be 13in (330mm) in length. Omit the transformer section for 50-ohm operation. This will result in an input VSWR of less than 1.4:1.

For a centre-fed crossed dipole, it is advisable to have a 1:1 balun to ensure a consistent pattern through 360° of azimuth. Dependent on the spacing between the dipoles and ground plane, the radiation pattern can be directed predominantly to the side, for satellites low on the horizon, or upwards for overhead passes.



Fig 16.82: Elevation radiation pattern for a whip antenna sloping 30 degrees on a large groundplane. The pattern for a vertical whip is also shown for comparison.

By drooping the dipole elements at 45°, with a spacing of approximately 0.4λ between the dipole mounting boss and the ground plane/reflectors, better coverage towards the horizon can be obtained. As ground reflections affect horizontal and vertical polarisation differently, low-to-horizon flight paths will not produce circular polarisation. This is due to 'ground scatter' of the satellite signal when it is low on the horizon, and ground reflections locally at the ground-based antenna.

Circular polarisation is normally produced by feeding one dipole 90° out of phase to the second dipole, and can be achieved by having an extra λ/4 of cable on one side of a combining harness.

An alternate approach to this method of phasing is to use the phasing properties of a capacitive or inductive reactance.

Suppose, for example, that the length and diameter of the dipoles are set to give a terminal impedance of 70Ω - j70Ω (capacitive). If a second, crossed dipole is set to be 70Ω + j70Ω (inductive) the combined terminal impedance of the arrangement becomes 35Ω ± j0, ie 35 ohms resistive. As the two dipoles are connected in parallel, the current in each dipole is equal in magnitude. However, due to the opposite phase differences of 45° produced by the capacitive and inductive reactances, the radiated fields are in phase quadrature (a 90° phase difference) which results in circularly polarised radiation.



Fig 16.83: Construction of 435MHz hairpin antenna and groundplane

Hairpin or Sloping Antennas

As technology has advanced, so has the radiated power from low earth orbiting amateur radio satellites increased, to the extent that communications can be established using handheld radios if the satellite is well above the horizon. Accordingly, it can be worth constructing very simple antennas to get started with satellites.

A vertical whip on a ground plane produces a null along the axis of the whip. However, if the whip is bent over by about 30°, the overhead null is filled without degrading the azimuth pattern too severely (**Fig 16.82**). For 145MHz operation, the whip should be around 480mm in length, and adjusted for best match according to the size of the groundplane.

At 435MHz, a *hairpin* construction from 2mm diameter wire (or even a wire coat hanger) is somewhat more rugged, and can offer wider bandwidths because of the transforming action of the folded dipole. The connector/feed point joint should be potted or sealed with silicon rubber or flexible epoxy resin if the antenna is to be used outdoors, to prevent moisture entering the cable (**Fig 16.83**). The antenna can be tuned, without seriously degrading the radiation pattern, by adjusting the spacing between the wires or by changing the slope of the hairpin a few degrees, or a combination of both.

Eggbeater Antennas

This omnidirectional antenna produces excellent circularly polarised signals over a wide range of elevation angles if carefully constructed. It comprises a pair of crossed circular loops, slightly over one wavelength in circumference, and fed in phase quadrature. The only disadvantage is the high terminal impedance of each loop (approximately 140 ohms, which requires a transformer section to match to 50 ohms [34].

Performance has been further optimised for satellite operation by K9OE by using square loops and adding tuned reflectors as a groundplane [35]. This antenna can be built with an excellent match to 50 ohms without recourse to special impedance cables.

The general arrangement is shown in **Fig 16.84**. The loops are constructed of rod, tubing, or 2mm enamelled copper wire for 70cm, bolted to a 22mm plastic water pipe coupler. Critical dimensions



Fig 16.84: General construction arrangements for K5OE Eggbeater II antenna



Fig 16.85: Feed point construction detail and phasing line connections for Eggbeater antenna



Fig 16.86: Elevation radiation pattern for 70cm Eggbeater antenna. The azimuth pattern is essentially omnidirectional. Note the figures are in dBi

Design frequency	w	h1	L	h2	Loop wire dia	Phasing cable length
137MHz	540	665	1065	1080	5	390
145.5MHz	510	625	1000	1010	5	370
435MHz	170	210	335	330	2	124

Table 16.15: K5OE Eggbeater antenna critical dimensions in mm. Phasing cable lengths are for solid PTFE dielectric, and should be measured between where the inner dielectric clears the braided coaxial outer



Fig 16.87: K5OE Eggbeater II without weatherproofing

are shown in **Table 16.15**. The tops of the loops are supported by a section of (plastic) water pipe that fits into the coupler, and capped to prevent water ingress. One loop should be set 5 - 10mm higher than the other so that the top of the loops can cross without touching. Instead of the 95-ohm RG62 cable described by K5OE, the phasing section can be made from two pieces of 50-ohm cable, each one quarter-wavelength long, with the outers connected together at each end. This makes a 100-ohm balanced wire transmission line, which can be coiled or folded up if required. All four braids can be connected together if the connections are conveniently close together (e.g. the 70cm variant). The antenna is Left Hand Circularly Polarised (LHCP) if the connections are as shown in **Fig 16.85** when the antenna is viewed from below. To change the polarisation to RHCP, transpose the two phasing cable connections at *one* end only.

For many purposes, a 50-ohm coaxial feeder can be connected directly as shown. Five or six turns of feeder closely wound can provide a balun and choke against current on the outside of the cable if required. A ferrite bead fitted on the feed cable close to the connection can be effective, and there is space for a low noise amplifier inside the water pipe between the coupler and the tuned reflectors if the antenna is to be used only for reception.

Calculated radiation patterns for the 435MHz variant are shown at **Fig 16.86**. **Fig 16.87** shows the antenna construction.

Quadrifilar Helix or Volute Antenna

The quadrifilar helix (QFH) or volute is a four-element helical antenna which can be used to give either directional gain or hemispherical circular polarised coverage as originally described by Kilgus [36][37]. The general form of a QFH is shown in **Fig 16.88**.

Radiation patterns produced for several combinations of turns and resonant lengths are shown in **Fig 16.89(a) to (d)**, and generally produce better circularly polarised signals at low elevation angles than a turnstile with drooping arms. A range of dimensions and resulting radiation patterns is discussed in [38].



Fig 16.88: A quarter turn volute with split sheath or slot balun (*Microwave Journal*)

The QFH can make use of a phasing line or the reactance method (as previously discussed for the turnstile antenna) to produce circular polarisation. The number of 'turns' or part turns of the radiating elements combined with their length can be used to produce various radiation patterns. Elements that are multiples of λ/4 have open-circuit ends, while the elements that are multiples of λ/2 can be short-circuited to the mounting structure.

Good radiation patterns for communication with low earth orbiting satellites (LEOs) can be produced by QFHs with diameters less than 0.1λ and one quarter turn per loop. This makes antennas for 145MHz possible without large support structures or incurring high wind load penalties [39] [40]. Both these designs make use of the reactance method (as previously discussed for the turnstile antenna) to produce circular polarisation, and constructional details must be followed exactly if impedance measuring test equipment is not available to adjust the element lengths.

The radiation pattern of a quarter turn QFH antenna is shown in Fig 16.90.

'Long' QFH with multiple turns can produce even better low angle coverage, but are generally only suitable for 435MHz or above because of their length.



Fig 16.89: Volute radiation patterns, co- and cross- circular polarisation (a) 3/4 turn λ/4 volute. (b) 3/4 turn λ/2 volute. (c) 3/4 turn 3/4λ volute. 3/4 turn 1λ volute (*Microwave Journal*)

CONTROL OF ANTENNA POLARISATION

Vertical polarisation is the most popular for FM and mobile operation in the UK. This means that a fixed station with antennas optimised for horizontal polarisation can only operate effectively if two antennas or a means of changing polarisation is available.

Space communication, where control of polarisation at the spacecraft end of the link can be difficult, has stimulated the use of circular polarisation. Its fundamental advantage is that, since reflections change the direction of polarisation, there can be far less fading and 'flutter' from reflections.

The use of circular polarisation at only one end of the link, with horizontal or vertical linear polarisation at the other end of the link, will result in a loss of 3dB. However, changes of polarisation



Fig 16.90: Quarter turn slim quadrifilar helix antenna and elevation radiation pattern. Each loop is approximately 1λ in circumference. Support pole not shown



Fig 16.91: General arrangement of a crossed Yagi antenna

caused by propagation often result in better reception of linearly polarised signals with a circularly polarised antenna. Conversely, if circular polarisation is used at both ends of the link, but the two stations use oppositely polarised antennas, the loss of signal due to polarisation mismatch can be 10dB or more.

It has been usual to standardise on Right-Hand Circular polarisation (RHCP) in the northern hemisphere for fixed communications. Space communications may use either Right or Left Hand Circular polarisation according to the frequency used and the satellite of interest. The handedness of circular polarisation is defined by the direction in which the electric vector rotates as the wave travels away from the observer. Thus, if in following the conductor of a helix antenna along its length away from the observer, the motion is clockwise, the antenna polarisation is said to be Right Handed.

The helix antenna produces Right or Left-Handed circular polarisation dependent upon whether the antenna element is wound clockwise or anti clockwise. Horizontal or vertical linear polarisation is also possible from helix antennas by using two helices and suitable phasing arrangements.

A compromise arrangement for receiving circular-polarisation signals is to use slant polarisation. To obtain this, a single Yagi is set at an angle of 45°. This enables horizontal and vertical signals to be received almost equally. At first sight one would expect a loss of 3dB for H and V polarised signals compared with an appropriately aligned Yagi. However, long-term practical measurements have shown when averaged that this arrangement gives a 6dB improvement with typical mixed polarised signals. In addition this arrangement it is only a little affected by the mounting mast, unlike a vertical polarised Yagi.

The simplest way of being able to select polarisation is to mount a horizontal Yagi and a vertical Yagi on the same boom, giving the well-known *crossed Yagi* antenna configuration (Fig 16.91). Separate feeds to each section of the Yagi brought down to the operating position enable the user to switch to either horizontal or vertical. It is perhaps not generally realised that it is quite simple to alter the phasing of the two Yagis in the shack and obtain six polarisation options. These are two slant positions (45° and 135°), two circular positions (clockwise and anti-clockwise) and the original horizontal and vertical polarisation.

The presence of the mast in the same plane as the vertical elements on a Yagi considerably detracts from performance, but a simple solution is to mount the antennas at 45° relative to the vertical mast. With appropriate phasing, vertical and horizontal polarised radiation patterns can be obtained that are unchanged by the presence of the mast.

If a crossed Yagi is mounted at 45°, with individual feeders to the operating position, the polarisation available and the phasing required is as follows:

(a) Slant position 45° and 135°. Antennas fed individually.
(b) Circular positions clockwise and anti-clockwise. Both antennas fed 90°+ or 90° - phase relationship respectively.
(c) Horizontal and vertical polarisation. Both antennas fed with 0° or 180° phase relationship respectively.

Phasing is simply the alteration of the length of the feeders of each crossed Yagi to change the polarisation. Where a 90° phase shift is required, $\lambda/4$ of cable is inserted and, where a 180° phase shift is required, $\lambda/2$ cable is inserted. The polarisation switch must switch in the appropriate $\lambda/4$ 'impedance transformer' and correct phasing by connecting the appropriate length(s) of cable.

Mast-head Multiple Polarisation Switch for 145MHz

There are several disadvantages in locating the polarisation switch in the shack. Two feeders are required from the antenna to the equipment, and RF losses may be significant if the antennas are positioned on a mast. Whilst it is technically feasible to improve signal to noise performance by installing twin preamplifiers at the antennas, the problems of equalising gain and ensuring relative phase stability are formidable. An alternative solution is to place the polarisation switch close to the antennas, which minimises the feeder losses, and to utilise a single preamplifier (with transmitter bypass arrangements if required) immediately after the switch to improve the system signal to noise ratio before despatching the signals to the receiver via a single feeder.

The polarisation switching circuit (Fig 16.92) offers a fair compromise between cost, complexity and performance. A pair of half crystal-can double pole changeover relays (Table 16.16) insert extra lengths of line into the feeds of a 50-ohm crossed Yagi anten-



Fig 16.92: Masthead antenna polarisation switch

Characteristic	145MHz	435MHz
Insertion loss	<0.2dB	<0.3dB
Mismatch	<1.03:1	<1.2:1
Isolation between normally open and moving contact	42dB	30dB
Isolation between moving contacts	39dB	28dB

Table 16.16: Half crystal can relay measured characteristics

Polarisation	RLA	RLB
Horizontal	Off	Off
Vertical	Off	On
LHCP	On	Off
RHCP	On	On

CD1283



Fig 16.93: Rear view of crossed antenna with polarisation table. The radiated wave propagates into the paper.



Fig 16.94: Relay and phasing/matching cable mounting details



Fig 16.95: Simple switch and phasing line to produce reversible circular polarisation

na mounted at 45 degrees to its support mast, to provide four polarisations (**Fig 16.93**). The antenna cable lengths must be cut to compensate for any phase differences between the antennas due to physical offset in the direction of propagation. Under ideal conditions with perfectly matched antennas, the four main polarisations will be achieved. If the antennas are not well matched to 50-ohm, the power division will not be equal, and mixed polarisation will result for each relay setting. If the VSWR is less than 1.2:1, the depolarisation will not be serious.

The relays are mounted on 1.6mm double sided copper clad glass fibre PCB with 50-ohm microstrip tracks for the RF circuits (**Fig 16.94**). RF interconnection and phasing lines are made from 3mm PTFE cable (URM 111 and T3264) which provides a good trade-off between losses and size for coiling up within a diecast weatherproof box. Polythene dielectric cables could possibly be used if soldered very quickly, but this is not recommended. The cable ends must be kept as short as possible as shown in Fig 16.94. The polarisation unit will handle 100 watts of CW or FM, provided that the antenna system VSWR at the relay is better than about 1.5:1.

If a transient suppression diode is to be fitted across the relay coil, it should be bypassed with a 1nF capacitor, or rectified RF pickup during transmission may cause the relay to change state. Experience has shown that it is better to dispense with the diode at the relay altogether if high transmitter powers are involved.

Circular Polarisation Feed and Reversing Switch

The following simple arrangement generates remotely selectable Right or Left hand circular polarisation from a crossed Yagi antenna, or two separate, identical Yagi antennas with their elements set at right angles to each other. It will work well provided that both antennas are closely matched to 50 ohms, and it uses readily obtainable cables, adaptors and connectors throughout (**Fig 16.95**). It should be mounted close to the antenna(s).

The electrical length of the two antenna cables must be an *odd* number of quarter wavelengths. λ/4 should be sufficiently long to make the connections for 2m operation, and 3λ/4 for 70cm. Higher multiples of λ/4 will reduce the VSWR and polarisation bandwidths of the antenna. If longer antenna cables are necessary, equal lengths of 50-ohm cable should be used to connect the antennas to the λ/4 75-ohm sections at the relay.

The 50-ohm impedance of the antenna is transformed by the quarter wave sections to 100 ohms at the T-piece. A quarter wavelength of RG62 (95-ohm) cable provides the phasing needed to produce circular polarisation, and the common relay contact, in either position, 'sees' two 100-ohm loads in parallel, ie 50 ohms, for presentation to the downlead.

Suitably weatherproofed PL239 connectors will work for 2m operation, but type N connectors should be used for 70cm. The electrical length of the connectors and tee-pieces must be taken into account when cutting the quarter wavelength cables.

For 1.3GHz and above, use separate circularly polarised antennas and a change-over relay if selectable polarisations are required.

REFERENCES

[1] http://www.vhfman.freeuk.com/radio/antennas/html. General construction notes and sources of materials (UK)

[2] 'Notes on the Development of Yagi arrays', C Greenblum, *QST* and other ARRL publications, edited by Ed Tilton, W1HDQ

[3] 'Yagi-Uda Arrays', Chen and Cheng, *Proc IEEE*, 1975

[4] 'Yagi Antenna Design', P Viezbicke, *National Bureau of*

Standards Technical Note 688, 1976
[5] http://www.boulder.nist.gov/timefreq/general/pdf/451.pdf. Copy of P Viezbicke's *Technical Note 688* in PDF format
[6] *Yagi Antenna Design*, Dr J L Lawson, W2PV, ARRL, 1986
[7] Yagi Optimiser YO, B Beezley, 3532 Linda Vista Drive, San Marcos, Ca 92069. Tel (619) 599-4962
[8] 'How good are genetically designed Yagis?', R A Formato, WW1RF, *VHF Communications* Vol. 2/98 pp87-93
[9] 'A genetically designed Yagi'" R A Formato, WW1RF, *VHF Communications* Vol, 2/97 pp 116-123
[10] http://www.si-list.org/swindex2.html. YGO2, YGO3 Yagi Genetic Optimiser software
[11] http://www.g8wrb.org/yagi/optimise.html. A particular Yagi optimisation study
[12] http://ic.arc.nasa.gov/people/jlohn/Papers/ices2001/pdf
[13] 'How to Design Yagis', W1JR, *Ham Radio*, Aug 1977, pp22-30
[14] 'Long Yagis', W2NLY and W6KQI, *QST* Jan 1956
[15] 'Extremely long Yagi Antennas', G Hoch, DL6WU, *VHF Communications*, Mar 1982, pp131-138; Apr 1977, pp204-21
[16] 'DL6WU Yagi Designs', *VHF/UHF DX Book,* ed I White, G3SEK, DIR Publishing / RSGB 1993
[17] http://www.ifwtech.co.uk/g3sek/diy-yagi. Various long Yagi designs with construction details and other information
[18] 'The JVL LoopQuad', *Microwave Handbook,* Vol 1, M W Dixon, G3PFR, (ed) p4.7ff, RSGB
[19] *Antennas*, J D Kraus, 2nd edn, McGraw-Hill, 1988, Chap 4
[20] *Antenna Theory, Analysis and Design*, Constantine A Balanis, Harper and Row, 1928 pp204-243
[21] 'A Quadruple Quad Antenna - an Efficient Portable Antenna for 2 Metres', M Ragaller, DL6DW, *VHF Communications* 2/1971, pp82-84
[22] 'Analysis and Design of the Log-Periodic Dipole Antenna' *Antenna Laboratory Report No.52*, University of Illinois
[23] 'Log-Periodic Dipole Arrays', D E Isbell, *IRE Transactions on Antennas and Propagation* Vol AP-8, May 1960, pp260-267
[24] W3DUQ, *Ham Radio*, Aug 1970
[25] *Antennas*, J D Kraus, 2nd edn, McGraw-Hill, 1988 pp265-319
[26] 'Helical Antennas for 435MHz', J Miller, G3RUH, *Electronics and Wireless World* Jun 1985, pp43-46
[27] 'A Helical antenna for the 23cm Band', Hans-J Griem, DJ1SL, *VHF Communications* 3/83 pp184-189
[28] 'Feedline Verticals for 2m & 6m', Rolf Brevig LA1IC, *RadCom* Mar 2000 p36
[29] 'The HB9CV Antenna for VHF and UHF', H J Franke, DK1PN, *VHF Communications* Feb 1969
[30] 'Eurotek', E David, G4LQI, *RadCom,* Sep 1999 pp31-32
[31] 'Asymmetrically Driven Antennas and the Sleeve Dipole', R W P King, *Proc IRE,* Oct 1955 pp1154-1164
[32] 'Designing Discone Antennas', J J Nail, *Electronics* Vol 26, Aug 1953, pp167-169
[33] 'Slim Jim Antenna', F C Judd, G2BCX, *Practical Wireless*, Apr 1978, pp899-901
[34] 'Eurotek' *RadCom* May 1996 p59 & 61, Circular loop Eggbeater antenna
[35] http://members.aol.com/k5oejerry/eggbeater2.htm. 'Eggbeater II omni LEO antennas'
[36] 'Resonant Quadrifilar Helix Design' C C Kilgus, *Microwave Journal*, Vol 13-12, Dec 1970, pp49-54
[37] 'Shaped-Conical Radiation Pattern Performance of the Backfire Quadrifilar Helix', C C Kilgus, *IEEE Trans Antennas and Propagation* May 1975, pp392-397
[38] http://www.ee.surrey.ac.uk/Personal/A.Agius/qha_perf.html
[39] http://www.pilotltd.net/qha.htm. Construction details for a very slim quadrifilar helix antenna for 2m or 137.5MHz. Note that the elements are twisted just a quarter of a turn.
[40] http://web.ukonline.co.uk/phqfh/qfh.pdf. Conventional half-turn QFH for 137MHz with very detailed assembly instructions

Alan's Lab
me and my geeky hobbies

Multimeter RF Power Add-On

2007-09-09

Being able to quickly measure RF power from -10 dBm to + 30dBm is extremely useful. This simple 50 Ohm load with inbuilt diode peak voltage detector fits the bill. Unfortunately it must be calibrated carefully and isn't direct-reading, but a simple table of Voltage or Current measured to delivered dBm can be constructed and kept near the unit.



I wrote a short program to generate a table of the Voltages, RMS, Peak and Peak-to-Peak that represent -20 dBm to +30 dBm. The formulae might be simple, but the table is useful for ball-parking, and was used to calibrate the meter at DC.

Calibration at DC isn't perfect, RF will read slightly differently as the dynamic properties of the diode vary. However it is extremely easy to just dial up DC voltages on your bench PSU and write down the corresponding reading on the multimeter.

If you use 75 Ohms more than you use 50 you might build and calibrate yours for that impedance. The load resistors will tend to dominate the frequency response, but the detector itself does affect the high-frequency return loss. The resistors and layout I used are only really suitable to low VHF, but for my immediate uses that is sufficient.

Build yourself a diode probe too (there is a 470p chip capacitor hidden under the wires).

© 2000 - 2009 Alan Yates - All Rights Reserved.



Unlike the power meter the diode probe is designed to only load the circuit very lightly, measuring the peak RF voltage at the point under test. As the impedance of the particular point in question will vary it can only use used for relative measurements so there is little point calibrating it.

Notes

The diode is a 1N5711.

The 10 nF capacitor directly across the meter plugs is to prevent RF from upsetting the meter (smaller values using ceramic or chip caps might be more appropriate at higher frequencies). The budget meter show is actually very resistant to RF interference compared to some of my other multimeters, my old DSE Q-1418 did not like the RF at all once more than a few dBm was delivered. (Meter show is a Jaycar QM-1500, about $8 AUD. For the price you may as well just dedicate one to this service.)

The 1 KΩ resistor in series is to limit short-circuit currents to something that won't zap the diode. It is small enough to be effectively ignored when looking at the peak voltage with the high input resistance of a modern multimeter. It also allows you to use a current measurement instead, either with a mechanical VOM or bare meter movement, or with the multimeter. Your multimeter might work better in this mode. It can't hurt to produce a calibration for current too, so you can compare the measurement of voltage and current if something looks weird. (i.e. If you have your doubts about RF upsetting the meter due to an unexpected resonance.)

4 comments.

Attachments

title	type	size
RF Power Table Generator Source in PHP5	text/plain	1.082 kbytes

© 2000 - 2009 Alan Yates - All Rights Reserved. XHTML | CSS | CSS toggle

The Fredbox

2007-05-26

I first heard about The G3XBM Fredbox transceiver via Solder Smoke. As soon as I saw it I just had to give it a go. It is a very simple and elegant design. Of course it offers no bells or whistles, just a fixed TX and RX frequency, and a flea-power output on TX, but it has a special charm in its simplicity and the retro usage of AM on VHF.

Transmitter

I built the transmitter side first. BF199s were selected as a good candidate for the RF devices, but I lacked a crystal in the range specified in the original article. Instead, I used a common 16.384 MHz crystal and redesigned the circuit to be two triplers rather than two doublers. This crystal is a common "computer" crystal, but places the TX frequency in the high-end simplex segment. This is a bit too close to the pager-splattered end of the band for my liking, and doesn't match the band-plans. For now this is OK, I'll get a custom crystal cut eventually.

I didn't use shielded cans or variable inductors for the transmit coils (as specified by the article), rather I used fixed inductances wound on T37-6 toroid cores with bare 0.71 mm tinned copper wire. My LC resonance calculator and nH inductance meter were enormously helpful in making the selection and testing of the tripler and output stage resonators. Each stage was tuned with trimmer capacitors.

It was amazingly easy to get the TX-side working, I just built each stage from the crystal to the final amp in turn, testing as I went. Each stage is well behaved and peaks nicely.

Peter VK2TPM could hear the signal at his QTH several kilometres away when I connected the half-finished TX board into my flower-pot antenna. The DC input power was about 23 mW, and no special attempt was made to match the output into the load, in fact the series trimmer in the matching network was absent at this point, just a fixed 12 pF capacitor was used for DC blocking.



Upon finishing the TX circuit I did experience a bit of RF pick-up in the microphone amplifier 2nd stage. A 1 nF capacitor to ground discouraged its RF gain and eliminated the problem. The 2nd AF amp stage is located immediately adjacent the crystal oscillator stage and was picking up RF directly. The effect was not audible, but was visible on the spectrum analyser as weak 16.384 MHz sidebands either side of the carrier. This wasn't causing feedback, just high-frequency modulation of the signal. If nothing else it proved the bandwidth of the modulator, which is perhaps a surprise considering the 100 nF decoupling on the modulated rail, however the output impedance of the series modulator emitter is so low it could deliver a few tens of mVs of HF ripple into that kind of load.

Receiver

© 2000 - 2009 Alan Yates - All Rights Reserved.

As easy as the Transmitter was, the Receiver was hard. It fought me every inch of the way. I spent an entire day trying to work out why it was simply not super regenerating from about 130-160 MHz. It turned out to be a 10 nF decoupling capacitor on the cold-end of the detector resonator. The article specified 1 nF, and I originally intended to use this value, but I had a strip of 10 nF mono's on the bench, so I used them. At build time I did consider why 1 nF was specified in the first place, I figured it was avoid the exact problem that would befall my unit, decoupling resonance. (Lesson #1: Trust the original builder and your initial instinct.) When the unit wouldn't oscillate properly I assumed that I had damaged the capacitor on install - this is a pretty common fault, so I tested it in-place by ensuring it would shunt a HF signal (my standard decoupling cap test), it passed this test just fine. (Lesson #2: Test at the frequency of operation.)

My hubris about "modern components" being superior and likely "purely capacitive" at VHF turned out to be completely wrong. It took *hours* to work it out, but eventually I determined the entire decoupling network was resonant near the operating frequency. Much foul language later and I replaced the cap with a ceramic 1 nF, with its "flashing" broken off and scraped right back to the disc to minimise the lead length. This cured the problem.

For the longest time I had assumed it was the source coil - and in fact the first source RFC I used (a molded choke) was being operated above its self-resonant frequency and prevented any oscillation at all. I replaced it with a few turns on a ferrite bead which seems just fine now.

A couple of other minor annoyances/mistakes were worked through (like picking larger inductances and making the entire circuit so sensitive to stray capacitance it was a nightmare to tune - DUH!).



Eventually the unit super-regenerated right through the region of interest and the LNA stage was constructed. Initially I put the LNA drain coil too close to the detector coil and they over-coupled. This meant as I tuned through resonance on the LNA drain it would pull the detector so much it would shut down. Bugger! Moving the coils apart a little reduced this effect to acceptable levels, but the core of one still effects the other a little. I'm happy with the current coupling, and it is actually useful to help tuning the LNA resonator. As you rock it through resonance it will pull the detector, and by observing the wiggle on the spectrum analyser you can tell you've got it tuned up. The AGC action of the detector makes it hard to tune for maximum smoke otherwise, as the AF output doesn't change much at all even when the front-end isn't tuned up properly. Once you've got it nearly right you can use a weak signal to tune for best signal to noise.

© 2000 - 2009 Alan Yates - All Rights Reserved. XHTML | CSS | CSS toggle



Note the pagers above the 2 metre band in this spectrogram. The hump in the noise floor is the receiver super-regeneration side bands. The smaller peak in between is the output of the Fredbox transmitter, the leakage from the unshielded prototype on my desk operating into a 47 Ohm load. It is rather disturbing that the pager signals are *larger* than this local signal just a foot or two from the spectrum analyser antenna.



I used J310s for the receiver FETs, and a 2N3904 for the audio amp. Although the main design requirement for Roger appears to have been flea-power, I think a better AF amplifier that can drive modern low-impedance headphones would be preferable. Only Jaycar now carries crystal earphones with a nice soft silicone ear piece. The one I used comes from DSE and it is hard-plastic - not very nice on the ear. I really hate these kind of earphones anyway, I'll probably be rebuilding it for a low-Z output at some point, but it does work pretty well as-is.

BTW: While I was in the "Special Hell" of decoupling resonance I took the RX down to the FM broadcast band, and up to the VHF-hi TV band. It works wonderfully in both, which isn't a surprise. However, by adjusting the drain-source feedback (then a trimmer, now fixed) I

© 2000 - 2009 Alan Yates - All Rights Reserved. XHTML | CSS | CSS toggle

Hall's regen on the FM band. The topology is more forgiving however, allowing grounding of the tuning cap. I also built several different oscillator topologies in desperation before I identified the decoupling fault, in one I got a Colpitts-like oscillator working with emitter coupled feedback to a tapped capacitor across the tank. This is something I should have thought about a *long* time ago, I'll probably build yet another FM broadcast regen using this topology for the detector, it seemed quite easy to control just by manipulation of the base voltage.

Boxing It Up

I am still tossing up between a cast Aluminium box, a custom box folded out of Aluminium sheet, or an Altoids tin. The circuit is small enough to just fit inside an Altoids tin but it probably won't fit with a battery. I'll pick up a centre-off momentary-one-side switch over the next week and finish off the radio one way or the other.



Note the use of an old telephone receiver as the microphone. It is nearly as large as the entire TX board. I'll have to find my electret mics, I know I have a bag of them somewhere that I got from a Rockby sale.

I'm strongly considering rebuilding the radio, perhaps through-the-hole to minimise its size. Although my prototype isn't too large as-is, it would be nice to neaten it up. Maybe I'll build it with fixed caps and variable inductors to save space too, although shielded cans are about the same size. It *might* be possible to tune the multiplier stages with stretched coils and fixed caps, this would make it much more compact and save money too if it ends up being kitted...

More TX Power

I am considering running the unit on 12 Volts to get a bit more RF out, and perhaps building in a small amplifier to get it up to 1 Watt region. This would probably involve a rebuild of the TX side to use a 2N4427 or similar final device, and a more robust series modulator transistor. This won't be efficient, but is probably easier to get going than a linear amp which would need careful drive adjustment.

I'll probably conduct some experiments around using a 2N7000 or VN10KM as the output device. The math suggests they may operate on 2 metres. I've already got them working on 6 metres in a brief experiment last month (must document that).

Comments

Working with VHF is fun! I find it a great learning experience, especially when you get problems like the resonant decoupling cap. That kind of thing really pushes your understanding of the physics and teaches you a lot.

I know a lot of HAMs won't touch anything above the bandwidth of their oscilloscopes. I can understand the frustration when something doesn't work, especially when you can't see why, but it really isn't that much worse at VHF. With just a diode probe you can achieve a lot. It does help enormously if you have VHF test equipment, for example I likely would have never noticed the HF modulation problem had I not had a spectrum analyser (although the HF was visible on the collector of the modulator drive amp, and most of us have a CRO that can see fine near 16 MHz).

A wavemeter can be helpful, if a bit retro, especially for making sure your multipliers are tuned up right and for looking for spurs. You can build one quite easily, it only needs to be a resonator with a detector and a LED or meter as a read-out. I'm a big fan of the biased 1N5711 through the decoupled bottom of the tank coil topology. For super-sensitivity you can use a MPSA18 as a DC amplifier. With a signal generator or dipper and a counter or scanner/receiver you can easily calibrate it. It can be used like a poor-man's spectrum

© 2000 - 2009 Alan Yates - All Rights Reserved.

My only advice when you get stuck is to trust the physics, do the math and follow your instinct when nothing is making sense. Rebuild parts of the circuit and test them independently. Measure what is actually happening and try to figure out what kind of misbehaviour in the circuit would cause the observed of behaviour. That will often solve an otherwise intractable problem.

Update 2007-06-05

I took the Fredbox boards to the local Homebrew Group meeting. I had both halves hooked up and talking across the room. Peter VK2TPM had brought along a digital audio recorder and did an interview with many of us in attendance. You can hear what I said about The Fredbox on Soldersmoke 62, and even a brief snippet of audio going through The Fredbox.

Also on the recording are Peter VK2EMU talking about the 80 meter challenge, John VK2ASU talking about his transmitter modules for the challenge (and an interesting diversion into IRF510 gate-modulation with some input from Brian VK2TOX - something I was thinking about back here, apparently Drew Diamond VK3XU has already produced a design doing just this). Mike VK2BMR also talks about his great VSWR/power meter project. His unit was absolutely beautiful, I was very much taken by the excellent job he did of cutting the PCB stock that made up the external directional coupler box, essentially flawless, perfectly square workmanship.

Update 2007-06-09

I've built a weak-signal source for aligning the receiver. One of the biggest weaknesses of the Fredbox receiver is that it drifts in frequency quite significantly with Vcc variations. Powered by a 9 Volt battery near the end of its life, it may drift enough to make the receiver completely off-frequency despite its poor selectivity. If I build this circuit again I'll probably put in a stabilized supply for the detector stage to avoid this problem.

© 2000 - 2009 Alan Yates - All Rights Reserved.



The signal source is a Pierce oscillator driving a tuned circuit which selects the VHF harmonic of interest. Because of the oscillator topology the crystal isn't pulled down as much as in the Fredbox circuit. The difference is fairly minor for my purposes, the poor selectivity of the receiver makes the difference in frequency of no real consequence. There is no active (or passive) multiplier, so the tuned circuit is merely extracting the harmonic energy from the oscillator. The harmonic energy available is very small, which is perfect for the application, giving an almost undetectable signal 1 metre away.

Update 2007-06-10

I've boxed up the Fredbox. As discussed earlier I went with the Altoids tin, despite this not allowing the battery to also fit inside the enclosure. I tossed up soldering an additional tin to the back to hold the batteries, but for now I've gone with the 9-volt battery snap just hanging out. It will work well with 6xAA battery holders which can just be held to the box with a rubber band.

© 2000 - 2009 Alan Yates - All Rights Reserved. XHTML | CSS | CSS toggle


SWEDA
VK2ZAY
The Fredbox
MADE IN
NET WT 1.76 OZ (50g)
147•5336 MHz

For the RF connector I chose an RCA. I can hear all the VHF engineers cringing, but for the purposes of this prototype it works just fine. The Antenna is a half-wave of wire helical which is quarter-wave resonant (with some pruning). The former is a piece of centre conductor and insulator from RG-213 coax. The centre conductor was left in place and is soldered into the RCA plug centre conductor, adding some capacitive loading and shortening the length of wire needed for resonance. I have no idea if this is good or bad, but it works.


SWEDA
147•5336 MHz

© 2000 - 2009 Alan Yates - All Rights Reserved.

I didn't find my stash of electret microphones, so I ended up just soldering the telephone receiver into the top of the Altoids tin. Ugly as hell, but also kinda unique. It looks somewhat like those Vietnam-war era VHF-low walkie-talkies.

I couldn't find a momentary-one-side toggle switch, so a centre-off on-both-sides switch was used instead. A special dummy load/diode peak-voltage probe was assembled for the final alignment. The carrier power ended up being near 25 mW on 12 Volts, on 9 Volts 10 mW just like Roger says in the article.

Update 2007-06-11

The 2N7000 on 2 metres experiment was a failure, it simply doesn't produce useful power beyond 90 MHz or so. However, it is very usable below 70 MHz. My input network was far from optimal, so perhaps with some more work it would be possible to get it working higher up, and I haven't tried an VN10KM in the same circuit.



I've also been fiddling around with grounded-base class-C multipliers. (Not just decoupled, biased base, the base actually soldered directly to the ground plane.) At first this seems a little weird, but if you pull the emitter low with a link-coupling to the previous stage collector current will flow. The advantage is excellent reverse isolation, which might help with stability with less than ideal layouts and devices. Such a topology was apparently quite common years ago with the 2N918.

1 comment.

© 2000 - 2009 Alan Yates - All Rights Reserved.

The DC-80

A Direct Conversion Receiver for 80 Meters with "subharmonic" VFO in the "Polyakov" style

July 15, 2009 by Rick Andersen, KE3IJ
[Revised February 23, 2010]

NOTE: I have revised this article to include some pictures of my prototype, originally ugly-construction-only, now installed in a Mouser Electronics plastic enclosure. I have also done away with the 600 Hz CW filter; the inductor picked up too much 60 Hz AC hum for my liking, even after I took measures to kill the hum. Instead of the previous 100mH inductor and .68uF series capacitor, there is now a single 10uF electrolytic cap connecting the output of the diode detector to the input of the audio amp transistor Q2. Rather than rewrite the article, I decided to ~~cross out~~ the revised sections, followed by yellow-highlighted comments on the revisions.

You may have noticed that almost all my receiver projects on these webpages, up to now, have been based on some variation of a **Regenerative Detector**, usually a Colpitts derivative. Most QRP designs over the last 30 years, on the other hand, have favored the ***Direct Conversion*** approach, which essentially means that we inject our incoming RF signal into one port of a mixer (usually a double-balanced diode ring) while injecting a tunable VFO into the other port, with *the VFO being at just about the same frequency as the signal we want to detect.* In such an arrangement, the **beat-** or **difference-** or **INTERMEDIATE-frequency (I.F.)** is reduced to (or close to) 0 Hz -- i.e., the beat frequency is at **baseband** and is the same as the **audio intelligence**, now demodulated. So, although we can describe the Direct Conversion circuit as a sort of "superheterodyne" whose local oscillator matches the RF input frequency and therefore has an I.F. of zero, it's more common to interpret it as a "non-superhet" without any I.F. at all -- we convert the incoming signals *directly to baseband* (audio); hence the name "Direct Conversion" (also called a *Synchrodyne* detector). This is not too different from a Regen detector, in self-oscillation, very close to the incoming signal frequency, producing an audible beat note. (Another name for a Regen is an *Autodyne* detector.) In fact, it can be said that the main difference between the two is that a Direct Conversion receiver has a separate Variable Frequency Oscillator (VFO) and RF input which are then combined in a mixer; in the Regenerative receiver, the mixer/detector/oscillator are all rolled up in one stage, into which the RF is coupled. And the Regen has legendary sensitivity, but it's also more sensitive to outside influences on the oscillating detector.

While the Direct Conversion (DC) receiver is thus conceptually very simple, it also comes with its own baggage (otherwise known as "Gotchas!") that can potentially make or break a homebrew receiver, causing an unnecessary amount of hair-pulling during the debugging phase.

I've tried designing a few DC receivers over the years. In the breadboard stage on the bench, they would often appear to work great... until I put them into enclosures or hooked them up to an electrically-unbalanced antenna like an end-fed wire. That's when the trouble usually began.

The two gotchas that most often caused me to go running back to my first-love (Regen receivers) were ***microphonics*** and ***common-mode hum***, which can dampen any enthusiasm you might have for DC receivers pretty quickly. Not to say that Regens don't have idiosyncracies of their own that must be dealt with or lived with. Choose your poison. But as I often say, that's the price we minimalists have to pay for our bare-bones toy radios. But we're not fatalists; we do try to come up with tricks to minimize the gotchas ;-)

"Microphonics" simply means that, since most or all of the approximately 100 dB gain of the receiver is in the audio stages [in contrast to a superhet, where most of the gain occurs at I.F., e.g., 455 KHz in an AM table radio], the receiver becomes very sensitive to mechanical vibration, like a microphone. So when you tap the case or touch a knob, you hear a thump with a bit of bell-like resonance to it. Any wiggling of the box that causes a micro-wiggle of the turns of the VFO's coil also gets amplified; turning a speaker amplifier up too loud may also induce acoustic vibration of the enclosure and cause audio feedback that can howl like a guitar amp if not controlled.

"Common-mode hum" is a much more difficult buggar to deal with. It's a nasty-sounding, raspy 120Hz hum that appears at various points across the tuning dial, usually at the frequency you're most interested in. The mechanism that produces it has to do with the receiver's own oscillator signal radiating back into the DC power leads and being rectified in the mixer -- or something like that (look it up in a textbook on DC Receivers; I never get the explanation quite right!).

It is exacerbated by connecting your DC radio to an unbalanced antenna system, particularly end-fed long wires, Zepps, etc., whose improper installation or inadequate RF grounding might also lead to RF in the shack while transmitting. A related symptom is that your receiver snaps, crackles, and pops with every electrical transient in the house wiring, like a refrigerator compressor turning on, lights being turned on and off, etc. Sometimes you may also find a tendency for the receiver's VFO to be "pulled" excessively as you rock your antenna tuning and loading capacitors back and forth through resonance (I use a resonant antenna tuner, rather than a PI network. I like the extra rejection of out-of-band signals that a resonant tuner gives me -- essentially, it's a bandpass filter in addition to being an impedance-matcher).

So what's a DC enthusiast to do? Well, the gurus' advice to us is to:

1) switch to a balanced antenna like a center-fed dipole (I use an 80 meter full wave horizontal loop nowadays; no more trouble with electrical pops and clicks originating in household appliances)

2) try to run your QRP equipment on batteries rather than AC-powered DC supplies or "wall-warts" (I use batteries almost exclusively, yet I could still hear common-mode hum at various spots on the dial. Also, I've found that most DC power supplies that are considered "well-regulated" are just a disaster when used to power the DC receivers I've built. With all that audio gain, what little 120Hz ripple residue there is, riding on that "pure" DC output, gets highly amplified by the receiver's audio stages.)

3) put "common-mode choke" toroids in the DC power leads to present a high impedance "open circuit" path to the common-mode hum energy (didn't work very well when I tried it)

So.

This is where I can begin my story that led to the new DC receiver described in this article, which I've named the "**DC-80**."

Some years ago I was sitting at the bench, trying to design a DC receiver for 80 meters, a band I tend to favor (relatively easy to design simple equipment for this band). For my "VFO" I was using a bench RF signal generator in the usual way: tuning it between 3.5 and 4.0 MHz, which worked just fine except for the microphonics problem that I outlined above.

At some point, whether by accident or intentionally -- I can't remember -- I switched the signal generator to a lower frequency range, turned the tuning dial, and was somewhat surprised to hear some very crisp, clear SSB banter in the phone portion of... what?... the 160m band?... because the dial was set at 1.9 MHz or so. Then I realized that the front end preselect filter I had installed between my antenna wire and my diode product detector, was tuned for the *80 meter band*.... were these 160m signals blasting through the 80m filter THAT loud and clear?...

Within a few minutes of listening to the SSB'ers yammering, I was able to identify them as operating on 75 meters, not 160! I pondered this for a minute, then thought "Oh! Maybe I'm mixing a harmonic of the 1.9 MHz generator signal, not the fundamental itself, with my incoming 75m SSB stations... The second harmonic (a.k.a. "first overtone") of 1.9 MHz is 3.8 MHz, and 3.8 MHz is in the 75 meter phone (voice) band! This is kind of neat!"

Well, what was also neat was that I couldn't hear any microphonics at all, with my VFO being at precisely 1/2 normal frequency. And, being set at "160 meters" frequencies rather than directly at "80 meters", the tuning knob was less "touchy", less prone to drift, too. Very cool.

And it got late that night and I hit the sack, and that's where I left my little discovery, until recently.

The Polyakov Detector

In June of 2008, I had an email conversation with Jerry, K9UT, who had built my AGC-80 Regen and wanted me to think about a 40 meter version of that project. He also mentioned that he had been reading about DC receivers whose VFOs were set to operate at 1/2 the normal frequency, and the benefits of that configuration. As I was working on my AGC-80/40 at the time, I filed his remarks away in the back of my mind and forgot about them for the time being.

Over the past few months of 2009, I've been reading here and there about a neat little circuit called the ***Polyakov detector***, which is the circuit that I think Jerry was referring to. Also called the "Russian mixer", it is described by RA3AAE (and/or others), in its simplest form, as two antiparallel diodes (i.e., two diodes soldered together in parallel, but with their cathode bands in opposite directions). Rather than needing any broadband transformers driving them, the simplest version of the circuit has them driven by incoming RF, on one end, through a 100pF capacitor. The other end is sometimes broken apart so that a 500 ohm pot [for nulling out AM 'blanketing'] can be inserted between the two diodes' right ends; the tap of the pot goes to another 100pF cap which is the VFO injection cap (VFO energy enters the diodes through this cap); simultaneously, audio energy (the beat frequency between incoming RF and VFO) is sent out from the same point and into an R-C low pass filter which removes the RF energy and mellows the audio somewhat. From there the audio is amplified, etc. (Other, more elaborate variants of the circuit do involve broadband transformers with multiple windings.)

Further Internet surfing informed me that this circuit concept has been around for a while, and the part that makes the Polyakov detector unique is that the VFO driving it is supposed to be running at ***half** the desired RF input frequency*... the Internet sources call this a "subharmonic" mixer. And the hams and QRP tinkerers are talking excitedly about the Polyakov circuit because it apparently solves the microphonics, frequency-pulling, and "touchiness" problems of the DC receiver, to some extent, because the VFO is running at only half the usual frequency; hence, it is more stable!

While I was in that netherworld between reading about it, and getting up the gumption to go down to the shack and actually try *building* one, I pondered the actual mechanism...

Was it really the '2nd harmonic' of the VFO at 1.9 MHz that was mixing with the incoming signal at 3.8 MHz, which was the 'magic' behind this circuit's performance? Why does 2nd harmonic mixing automatically "isolate" the VFO fundamental frequency from the RF signal in such a way as to suppress microphonics, etc.? Anyway, does the presence of a 2nd harmonic mean that the VFO signal is "dirty"? Because I would expect the 2nd (and subsequent) harmonics to be several dB down in amplitude, from the fundamental, and that the injection level wouldn't necessarily be adequate for that nice, loud, crisp detection I heard during my lab bench experiment. If my VFO is too "clean", will the circuit fail to detect?

Or does even the "cleanest" VFO output sine wave get mutilated by the mixer diodes -- i.e., Does this "2nd harmonic" really originate in the mixing process of the diodes themselves, via their nonlinearity? The explanations of the Polyakov circuit that I saw attempted to correlate the dual-directionality of the two diodes with the "doubling" effect, sort of like a full wave rectifier.

Then I pondered another question I've always thought about, but have never seen a clear answer to: If I mix two frequencies in a diode mixer, unbalanced, I know I will get four freq's out: f1, f2, f1+f2, and f1-f2. The question is, do all these new frequencies also automatically mix with one another, generating higher-order mixer products (I believe they do)... so where does this stop? It would seem that the original mix would "snowball" into a near-infinite number of new frequencies being generated in the mixer...but each new frequency having less amplitude, so that the majority of the snowball would be down in the mud, for all practical purposes.

...which brought me to another thought: Hold on a minute; maybe this isn't about "harmonics" at all; instead, maybe this is about *pure **heterodyne** mixing!* After all, if I mix a 4 MHz input with a 2 MHz VFO, both being pure sine waves with no harmonics contaminating them, then our sum and difference frequencies are going to be 4+2 = 6 MHz, and 4-2 = what?...2 MHz!

In other words, the beat frequency between any frequency and its half-frequency, is *another copy of that same "half-frequency"* (i.e., its "phase conjugate"). So maybe a Polyakov mixer is not really a "subharmonic" mixer after all; maybe it is simply exhibiting a regular ol' heterodyne process where the "beat" happens to match the lower of the 2 input frequencies. In other words, a "superhet" whose local oscillator is half the input frequency, and whose "I.F." is therefore *equal to the "local oscillator" frequency*. And when THOSE TWO frequencies beat in the diode, 2 MHz minus 2 MHz = 0....Lo and behold, the output is baseband -- in the audio range!

To test this idea, I built the simple RA3AAE circuit. Then I modified it in at least 3 ways, which led to the DC-80 receiver described later in this article. The test was: Will any other, NON-Polyakov mixer perform in the same way, with *f* and *f/2* applied to their input ports?

The Polyakov circuit

It didn't seem to matter where the 500 ohm pot was set; the AM bleedthrough was still there, although centering the pot lowered the overall volume of *all* signals, desired and undesired. I'm unimpressed so far. I did try a different null pot value (1k), put it on the other end of the diodes where the RF comes in, and various other things. It worked, but not as advertised, or so it seemed to me.

A Single Diode

I took out one of the diodes. Guess what? As long as there was a resistor to ground for continuity through the diode, the circuit worked as a "normal", single-diode AM detector...*even though the VFO was running at half-frequency.* This leads me to believe that my "heterodyne" idea is correct, and that it's not necessary to have two diodes connected antiparallel, to get the "doubling" effect [which is a misnomer, in my opinion]. AM bleedthrough, however, was objectionable, which is why decently-designed Direct Conversion receivers usually use a double-balanced, 4-diode ring mixer, along with a diplexer (impedance-matcher which properly terminates the RF and suppresses it from getting into the audio amp, which can cause unwanted "AM blanketing" detection in the audio transistors' base-emitter junctions).

A 2-Diode Product Detector

Next, I tried an old product detector configuration I'd seen in the ARRL Handbooks: Solder two diodes in *series*, but in opposing polarities; put RF in the left side, take audio from the right side, and drive the junction in the middle (through a cap) with VFO energy. Well, you need terminating resistors on each diode to make this one work right. Once again, the 2-diode product detector worked well as a 3.8 Mhz detector whose VFO was running at 1.9 MHz. But still some AM bleedthrough.

A New 4-Diode Detector

Finally, I tried something that I haven't seen anyone do before: Strap another 2-diode product detector in parallel with the first, but with the relative polarities of the second set of diodes *opposite* to those of the first set. So now we have 4 mixer diodes, not chasing each other as in a ring mixer, but as 2 "series" product detectors, of opposite polarity, in parallel (see the schematic of the DC-80, below). It can also be described as 2 Polyakov detectors connected together with the VFO injection at the junction between them. (The 500 ohm balance pot is eliminated.)

I call this a ***4DPD*** [4-diode product detector] **mixer**.

And it works very well. With VFO at half the RF input frequency. So when I call this a DC receiver with a "subharmonic VFO in the Polyakov ***style***" up in the title of this article, I'm aware that it's not an actual Polyakov receiver; instead, it's based on the spirit of the Polyakov mixer, especially with its half-frequency VFO. A run-of-the-mill doubly-balanced ring diode mixer, it ain't. But it performs nicely just the same.

So, no disrespect intended toward our Russian friends, but I think the benefits of this "new and improved" Polyakov Direct Conversion approach stem from the unique heterodyne products of a 2:1 frequency ratio between RF input and VFO, not on the bidirectional transfer curves of two antiparallel diodes. At least that's my take on it, and I'll gladly retract this opinion if the facts warrant it in the future.

I learned a couple of other things in designing the new DC-80 receiver: Terminate the antenna preselector bandpass filter with a 51 ohm resistor, at the input of the diode mixer (see schematic). This seems to reduce AM bleedthrough and makes little difference in overall volume level (I thought the reduction from RA3AAE's 500 ohms down to 50 ohms would kill all my audio output. It doesn't. There's something to be said about designing around a stated impedance level, like 50 ohms.)

Also, I learned that the first audio transistor ought to be configured as a common-base circuit, whose input impedance is also low (close to 50 ohms). Not only does this seem to help with the rejection of AM bleedthrough, but it makes a surprising difference in the quiescent noise level of the audio amp, with the antenna disconnected! Some of the other projects on my webpages would probably be better performers if I had known this before this particular project taught it to me. I deliberately reconfigured Q2 as a common-emitter amp with the signal going into the base in the "normal" way we think of transistor amps being wired.....

...as a common emitter amp, the receiver was quite noticeably noisy (a constant hiss) with the antenna disconnected. When I went back to the common-base setup, with audio going into the emitter, the amp quieted down to a whisper without antenna, yet was amply loud and crisp when SSB or CW signals were coming through, with antenna connected.

I'm also happy to report that there are neither microphonics, nor any common-mode hum, discernable in this receiver -- although I have not yet enclosed it in a box, which may rain on my parade, based on previous experience. The only problem I encountered was some genuine, non-raspy 60 Hz AC hum getting into the 100 millihenry inductor that I use for the CW filter. ~~I mounted it upside down so that its top was glued to the copper ground plane floor of the circuit, and I tightly twisted the short length of hookup wire coming off that inductor and connecting to the CW filter toggle switch. There was a big reduction in hum once I twisted those switch wires together. There remains a slight hum when the filter is switched to the "CW" position.~~ I eventually eliminated the inductor, .68uF cap, and CW filter switch and replaced them with a single 10uF electrolytic cap connecting detector output to audio amp input (emitter of Q2). IGNORE the CW Filter section of the schematic diagram, below.

PLEASE ALSO NOTE: Two other changes I made to the schematic below: 1) Change the 470pF ceramic cap across Q3's base resistor to a .0027uF. This compensates for the lack of 600 Hz CW filtering which I removed. 2) I removed the Volume Control pot shown in the schematic, for lack of real estate in the small box I finally ended up with. I connected the audio output cap directly to the audio output jack. A cable plugged into the jack connects to one of the infamous beige-colored Radio Shack Amplified Speakers, which is my preferred method of dealing with audio amp requirements.

Schematic Diagram of the DC-80 Receiver

Let's get into the nitty-gritty of the new Direct Conversion receiver. The schematic, below, is relatively simple, but to make things easier I have broken it up into 5 sections, outlined by the thin blue blocks superimposed over the schematic itself.


DC-80 DIRECT CONVERSION RECEIVER
7/15/09, 2/23/10 by R. Andersen, KE3IJ
L1 = 12t #28 on T50-2 toroid
50 Ohm Antenna
BNC jack
80m Bandpass filter
L1 = 1.3uH
.001uF
.0022uF
.001uF
.0022uF
4-diode Product Detector
51 Ohms
.1uF
600 Hz CW filter
100mH
(twist)
.68uF
10uF
ON/OFF
9v battery
+9v
100uF 16v
Audio Output to amp
4.7k
.0027uF
~~470pF~~
4.7k
.47uF
10uF
Q2
220k
Q3
1k
220k
10uF
Audio Preamplifier
Volume 10k
Red Core L.O. transformer (CAL adj)
N.C.
N.C.
N.C.
100pF
+9v
VFO 1.79-2.0 MHz
47k
.1uF
c
b
Q1
e
220pF
2.2k
+9v
Fine
10k
Plastic variable tuning cap 140pF
1 Meg
10pF
100pF
220pF
Detector diodes = 1N4148 / 1N914
Fine Tuning diode = 1N4001
Q1,2,3 = 2N3904 NPN Silicon
e b c

Referring to the schematic above, let's go through a description of each section:

Front End Preselector

If I can get away with avoiding large-turn coils up front, I do it. The 80-meter band front-end "preselector" filter described here was also shown as an alternate filter in my AGC-80 series of articles. It's essentially a "Pi" lowpass filter combined with series input and output capacitors, whose combination gives a sharp *bandpass* response. I designed the filter using an old version of *MicroCap* circuit analysis software which shows me a plot of the frequency response as I vary the parts values. I'm pretty sure this filter is my own invention; I haven't seen it used anywhere else. It works for me.

This configuration allows me to use fairly large caps -- .001uF and .0022uF (which are the same as saying 1000pF and 2200pF) -- along with a fairly small inductor -- 1.3 microhenrys -- which is easy to wind. Just take about 8 inches of #28 enamelled copper magnet wire (Radio Shack sells a bag of 3 sizes) and wind 10 to 12 turns on an Amidon T50-2 red-gray toroid core....which Electronix Express sells as part number 152750-2. Adjust the spacing of the turns on the coil for peak reception. Drip some melted candle wax over the windings to hold them in place, once you've squeezed or spread them for the loudest volume on an incoming signal.

The caps I use, by the way, are the green mylar caps that Electronix Express sells (I call them "chiclet" caps, because they remind me of the litte green cubes of spearmint gum that go by that name). I believe plain old ceramic caps would work, too, but I have always used the mylar "chiclets" in my designs.

The 80m filter is intended to be used with a 50 Ohm antenna impedance, and it is terminated in a 51 Ohm resistor in the radio circuit. If you want to scale the filter up or down (40m or 160m bands), you just need to calculate the capacitances and inductance from the standard formulas, and knowing the reactance values of the components, which are constant for a 50 ohm system, keeping the reactance ratios the same for all bands. The reactances are: 42 Ohms for the .001uF series caps, and 19 Ohms for the shunt caps to ground. The toroidal coil's inductive reactance is 31 Ohms.

The standard formulas are as follows:

Inductance L = Reactance XL divided by (2pi x Frequency) **L=XL/(2pi F)**

Capacitance C = 1 divided by (2pi x Frequency x Reactance Xc) **C=1/(2pi F Xc)**

So, for example, if we wanted a front-end filter for ***40 meters***, using 7.2 MHz mid-band for F,

1) the series caps at Xc = 42 Ohms would be calculated as **1/(2pi x 7.2E6 x 42)** which comes out as 5.263E-10 Farads on the calculator. Multiplying that by 1E12 converts the answer to picoFarads.... = 526pF. Since that isn't a standard value, I might try a 470pF or 560pF cap instead, and modify the turns on the coil later, if necessary.

2) For the shunt caps at Xc = 19 Ohms, the same formula gives me a capacitance of 1163pF, so I'll substitute a 1000pF = .001uF cap for that.

3) For the toroid coil, with XL = 31 Ohms, the equation would be **31/(2pi x 7.2E6)** or .000000685 Henrys, which, when multiplied by by 1E6 to convert to microHenrys, gives 0.685uH for our inductance.

But how do I know how many turns this equates to on the toroid? Well, lacking an exact formula, I can reason that, since I doubled my frequency to get from the 80 meter to the 40 meter band, and my original inductance of 1.3uH has just about been cut in half, at 0.685uH, then maybe I ought to put about half the number of turns on the toroid....I'll try 6 turns, and adjust the spacing for a peak later on when I'm testing out the receiver.

Yes, this is "designing by the seat of my pants" but it's OK; it works well enough; don't sweat it.

Notice that the coil is already less than 1uH at 40 meters. This tells me that my 'special' pi-bandpass design won't work well for any other high bands; for 20 meters I would need to change the filter design to something more conventional. But it should be OK for 160, 80, and 40.

Since my design has such easily-obtainable parts and low coil-turns, and has 50 Ohm impedance levels throughout, this also means you can cascade two of these filters in series, if you want even more out-of-band rejection. Again, simple, non-critical, and intuitive.

On another subject relating to the receiver front end:

The RA3AAE-style receiver schematic showed a transistor RF amplifier up front, before the diode mixer. I had a front-end RF amp when I first built the RA3AAE circuit, along with its 500 ohm impedances in the mixer. Bottom line, the increased gain up front invited noticeable AM bleedthrough, no matter what I tried to do to minimize it. When I remembered an ARRL publication stating that, on 80 meters at least, a well-designed DC receiver doesn't need an RF amp, I took mine out, feeding the output of my antenna preselect filter right into the diode mixer, with a 51 Ohm termination resistor to ground at that point. The result was that I was still able to receive loud signals and the AM bleedthrough was cut way down, almost to the point of disappearing, although you can still hear it occasionally when tuning to a blank spot on the dial.

4-Diode Product Detector

I've already described my experiments with the Polyakov configuration and other variations, so I'll just stick to a description of the detector stage here.

The bandpass preselect filter, just described, sees a matching termination in the 51 Ohm resistor that shunts the input of the 4DPD diodes to ground. This helps kill the "AM broadcast blanketing" that plagues simple receivers. The resistor also provides a DC path to ground between the "pumping" action of the VFO input cap, and the diodes.

The diodes, which are plain vanilla 1N4148 (=1N914) switching diodes -- nothing fancy, nor did I make any attempt to "match" them -- can be seen either as a left-hand Polyakov antiparallel pair, joined to a right-hand Polyakov pair, with the VFO injecting its signal in the middle of the two; or, one can view the arrangement as an "upper" 2-diode product detector, joined with a "lower" 2-diode product detector of opposite polarity, in parallel, with the VFO driving both their midpoint junctions simultaneously. When the polarity of the VFO signal is positive, one pair of diodes conducts. When the VFO goes negative, the other pair conducts. Same thing as a Polyakov, but done a little differently. However you want to view this 4-diode arrangement, IT WORKS. In fact, it sounded a bit louder to me when I strapped the 2nd pair of diodes into the circuit, as if it were more efficient.

The VFO signal is coupled into the center of the detector through a 100pF ceramic cap.

The output is taken off the right side of the diode array, with a 0.1uF cap to ground, which bypasses the RF output of the mixer and leaves only our baseband audio. I tried putting another 51 Ohm resistor in series with that cap to ground, in an attempt to imitate one of the "diplexer" circuits I found online in a "DC 'Popcorn' Receiver" schematic, but there was noticeable AM bleedthrough(!) When I removed the resistor and put the bypass cap straight to ground, the AM stuff disappeared. Go figure.

For those of you whose 'common sense' tells you that 0.1uF is much too large a cap to use -- that it will make the audio sound too mellow... -- Surprise! -- it's not like that when you're living in a 50 Ohm world! That 'common sense' only works when your "background" impedance is up around 1K to 10K. The signal is still quite "tinny" at the output of the 4DPD, and needs some more mellow-out filtering later on, in the audio amp. (I bring this up because I once came across a pair of pundits critiquing one of my radio circuits on some blog somewhere. They applied the standard "f=1/(2piRC)" roll-off formula to my component values and concluded that my audio must be as mellow as jello because my bypass cap appears to be way too big. Not in a low-impedance circuit, though. Hasn't it ever occurred to you to wonder why the coupling cap feeding the 8-Ohm speaker in an audio amp has to be way up there around 470uF or more? You need to dump more charge through a smaller resistance in order to get the same power.)

But I digress.

"Subharmonic" VFO

We leave the mixer/detector output for now and travel down to the VFO.

As any good Ham knows, the VFO can make or break a receiver. So let me say right here: *I wanted a quick and dirty, functional VFO; simple and cheap.* So I used only a single stage, with no buffer. I basically took a Clapp Oscillator design and used the perfect "coil" for that oscillator, at 1750 - 2000 KHz..... one of those little oscillator cans with the red screwdriver-adjustable cores, which tunes the Local Oscillator (L.O.) in an AM broadcast radio. Voila! No coils to wind with dozens of turns at 160 meters. Because -- remember -- we are running the VFO *Polyakov*-style, at 1/2 the RF input frequency.

To make things simple for me and for you, I also borrowed the variable tuning capacitor from cheap transistor AM radio design -- one of those little plastic-cased tuning caps with the 3 leads coming out the side. Unlike the metal-plate 365pF variables of the days of yore, these plastic "polycaps" have a total capacitance of around 140 - 170 pF for the RF section, 60pF or so for the L.O. section [intended for a superhet receiver]. I soldered the two cap sections in parallel (the outer leads) while grounding their bottoms through the center lead. Then I also have a 100pF cap in parallel with the whole thing, and series connected 220pF's as the feedback caps in the base-emitter circuit of the 2N3904 transistor, Q1. These values were obtained by experiment and could be improved upon. In fact, the whole VFO was hastily designed and could be improved upon. It's a bit drifty in frequency, but it works! Without taking any "dBm" measurements, it provided a very adequate injection level from the first moment I turned the radio on, as evidenced by the crisp, loud signals I'm able to hear, and by the relative lack of "spurs", "tweets", and unwanted intermodulation products.

So there! If you don't like it, make it better! I'm admitting that I scrimped where I probably should have been a lot more careful.

2/23/2010 Revision: Added a Fine Tune "Clarify" Control

The right-most knob on the front panel of the encased DC-80, which you'll find farther down the page, is the Fine Tune pot. It operates like the Bandspread tuner in old shortwave radios, and like the "Clarifier" knob on some old CBs. In a nutshell, the 140 pF plastic tuning cap tunes the whole 500 KHz -- 3.5 to 4.0 Mhz -- of the 80 meter band. With no gear reduction, one half-twist of the knob covers the whole band in one fell swoop, and the tuning rate is too fast for comfortable operation. I've added a parallel "fine tune" which is a 10k potentiometer controlling a reverse-biased rectifier diode, used as a varactor tuning diode. The 0-9v at its wiper is isolated from the VFO through a 1 Megohm resistor, and lightly coupled to the top of the plastic Main Tuning cap via a 10pF ceramic cap.

To operate, start with the Fine Tune knob set in the center of its range. Tune in a station with the Main Tuning cap, and tune for a 'zero-beat' with CW signals, or, tune for a deep growl on SSB voice signals. Now, turn the Fine Tune left or right until the "growling" SSB voice "clarifies" to a normal pitch. If tuning CW, tune to the desired beat note.

Since one of the distinctive traits of a simple Direct Conversion receiver (or Regenerative receiver, for that matter) is that it lacks *single signal* capability (i.e., you are able to hear the signal on **both** sides of "zero-beat"), you will be able to tune SSB voice signals either "correctly" or "backwards"--- if you're on the "left" side of zero-beat, the voices will sound garbled and impossible to understand [because of audio spectrum inversion of the sidebands]. Turn the Fine Tuning control clockwise through zero-beat, and you will end up on the "right" side and will be able to hear intelligible speech, although it will vary from a deep/low sound to a high "chipmunk" sound; somewhere in the middle of that range you will hear a normal-sounding voice. The Fine Tune pot helps you clarify that voice with a slower tuning rate.

~~Switchable CW Filter~~

~~Back up to the output of the mixer/detector:~~

~~I use one of the small, cylindrical blue inductors from Electronix Express in a series bandpass filter, as my very simple CW filter [the inductor also blocks any RF that the 0.1uF bypass cap may have missed]. The choke (as they call it) has a value of 100 milliHenrys, with a DC resistance of around 100 Ohms (they must have a lot of turns of very fine wire inside). That 100 Ohms knocks the Q down, making a rather broad filter, but it's adequate for such a simple filter. The other component making up this filter is a mylar cap whose value I have listed on the schematic as 0.68uF; this value, along with the 100mH choke, gives a resonant peak at around 600 Hz. If you prefer a 750 Hz peak as many QRPers do, change the cap to 0.47uF.~~

~~A toggle switch is wired across the 100 mH choke. When the switch contacts are OPEN, the choke is in circuit and you're in 600 HZ "CW" filtering position. When the switch is CLOSED, the choke is short-circuited and the audio signal travels straight from the detector output to the 0.68uF cap, which doubles as a blocking/coupling cap for the input of the audio amp, Q2. With the choke out of circuit, the audio is unfiltered and quite "bright" [tinny-sounding], to be mellowed out just slightly in the audio preamp circuit, described in the next section.~~

~~One "gotcha" that I experienced with the 100mH choke inductor was that it picked up a healthy amount of 60-cycle AC hum from the soldering iron. I mounted it upside-down, gluing it to the copper ground plane on which I built the prototype (see picture near the end of article). The hum got worse when I wired the CW Filter switch across its leads. I then twisted the two switch wires together, which killed most (not all) of the hum. Your mileage may vary, so keep the physical distance short between the choke and the panel-mounted CW Filter switch, and twist the two wires leading to the switch, tightly, down their length.~~

Quiet Audio Preamp

Well, a lot quieter than some I've built, anyway.

As usual, I built this receiver without an audio power amp. Instead, I route the output to a Radio Shack Amplified Speaker (steadily rising in price; now about $14.99 I think; I'd like to believe that all my articles extolling the virtues of this little amp has caused business to boom for Tandy Corp.; at any rate, I remember these little beige boxes costing around $11.99 back when I started this website) and lately I've been plugging a computer speaker into the aux output of the Radio Shack amp for better sound.

As I've described elsewhere in this article, I discovered that this receiver's quiescent noise, heard when there is no antenna connected, was drastically reduced when I compared Q2 wired in a common-base configuration, with Q2 wired in a common-emitter configuration. I'm not sure of the correct explanation, other than to say that in the common-base circuit, the input impedance is low, giving a good match to the 50 ohm level designed into the receiver front end.

~~The same 0.68uF cap [or 0.47uF alternate] that serves as the capacitive element in the L-C CW Filter, also serves to couple the weak audio from the detector into the emitter circuit of Q2, a 2N3904 like I always use.~~ I now use a 10uF electrolytic here.

The cap serves to block DC at the same time; there is approximately 1 volt DC at the top of the 1K emitter resistor, and we don't want that bias to affect the diodes in our mixer. So we "cork it up" with that cap, which serves to "couple" AC (audio), while "blocking" DC (Q2's emitter voltage). [I used to tell my electronics students that a cap passing AC while simultaneously blocking DC is like waving at someone through a glass window: They can see an image and movement (change; AC) but if you try to blow a stream of air at them, the glass blocks the flow (flow; DC). I'm sure that that explanation caused less brain damage than a friend of mine did when he used to play mind games with his young boy by shaking his head up and down when he meant "No", and side to side when he meant "Yes". The kid is probably doing prison time by now.]

A 220k resistor supplies positive current to Q2's base, while a 10uF electrolytic cap bypasses any audio on the base, to ground. Doing this forces the collector to output an amplified version of the audio variations coming in at the emitter. The amplified audio is picked off Q2's collector and 4.7k collector load resistor, coupled to the next stage through another 10uF electrolytic, and sent into the base of Q3 for further audio amplification. Q3 is grounded at its emitter (a common-emitter configuration) while the base is supplied with DC bias through another 220k resistor. Both stages connect their base resistor to the collector; this is known as "collector biasing" and is a form of negative feedback that automatically sets the transistors' bias at the optimum operating point in their bias curves.

Notice that there's a ~~470pF~~ .0027uF cap across Q3's base bias resistor. This is a bit of "mellowing" for the tinny-sounding audio I mentioned earlier; a simple low-pass filter to take some of the edge off the highs... so that the piercing whistle of W1AW's code practice signal doesn't drive you batty even when tuned 8 KHz away!

But note that when the CW Filter switch is "off" -- shorted, actually -- the only filtering that the audio sees is that of the 0.1uF cap at the detector output, and this ~~470pF~~ .0027uF cap across Q3's base bias resistor. So the guys on SSB and AM phone sound sharp and right there in the room with you... and static crashes are that much more noticeable, ~~whereas in the CW position, static is greatly reduced by the action of the 600 Hz bandpass filter, and the extremely high-pitched CW tones are mostly filtered out.~~

~~At the collector of Q3 we couple the audio out to a 10K potentiometer (Volume Control), which is a variable resistance voltage divider whose wiper connects to the audio output jack. High-impedance crystal or magnetic headphones may be connected here, although I prefer to connect my amplified speaker here instead. You may ask why I put in a volume control, if the Radio Shack amp already has one at its input? The reason is that there is a lot of amplification (audio gain) from Q2/Q3, and the Radio Shack amp was actually being overloaded, during the peak of the SSB yakking hours in the evening, even with the amp's volume control turned almost all the way down. This made me happy, because as a seat-of-my-pants designer, I knew that enough audio to overload the Radio Shack amp was certainly enough to drive most headphones to at least adequate volume. (Since I don't have a pair of decent 2000 ohm headphones, I have to make educated guesses about how the receiver will sound to someone who does have them ;-)~~ I left the Volume Control out of the revised version because it would not fit in the small enclosure from Mouser (although they do sell larger versions of the box). I made the decision to simply send the strongly-amplified audio to the rear audio jack, and to let the volume control on the Radio Shack Amplified Speaker suffice as my gain control. If you decide to build the DC-80 in a bigger box, you may decide to put it back into the circuit.

A Picture of the Prototype

It's ugly! -- it's scary! -- it's coming to a theater near you -- it's not in an enclosure yet! -- but here it is. I've marked the major components with labels or with black magic marker on the copper-clad board. If you build it and it starts giving you trouble in an enclosed box like some of my earlier DC receivers did, you have the right to box my ears and pommel me. But I wanted to get the new design up as soon as I could. If you look closely at the picture of my prototype, you can see that there's really not much to it, that it should work as well as it does. This 1/2 frequency VFO thing really seems to have breathed new life into the lowly Direct Conversion Receiver. Build one of your own, and if you don't think it performs, look at it as a learning experience.



2/23/2010 UPDATE: The DC-80 in an Enclosure

Mouser Electronics to the rescue! I found a cute little "bone-white" plastic box in the Mouser catalog, part number 616-79160-510-039, which is a small 4" x 6" x 1.5" high plastic box with top and bottom pieces, plus removable front and rear plastic panels that fit in grooves between top and bottom sections. The top and bottom are held together with long screws that go in through the bottom. The enclosure comes with 4 press-on adhesive rubber feet. Only $7.70 + shipping at the time of this update in February 2010.

Here are some photos of the DC-80, rebuilt on a small copper ground plane and mounted in the Mouser box:





PARTIAL Parts List

I'm not gonna give you part numbers for every resistor and cap in the circuit. The resistors are 5%, 1/4 watt types and most of the caps are the green mylars. The big cylindrical caps with polarity markings are electrolytics and should have a DC working voltage over 10v. The VFO injection cap happens to be a 100pF ceramic. You can go to the Electronix Express website and browse their online catalog for yourself. But the 'unique' or unusual parts are listed here, for your convenience and abatement of confusion.

I've decided to give Electronix Express a big plug in this article, since I've dealt with them before and found that they almost always have the kinds of components I need for QRP radio projects -- like the inductors and variable capacitors. Sometimes a few of their parts are back-ordered and take a while to arrive, but for the most part, my orders arrive at my door within a week. (I used to teach Electronics at ITT-Tech, and Electronix Express -- under their alternate name, RSR Electronics -- was our source for electronic parts and kits used in our Lab courses.)

Front End

Antenna connector - BNC female, panel mount. You'll notice in the picture that my prototype doesn't use one, but uses alligator clips instead. Well, when I put it in a box, I'll use a BNC connector, OK?

L1 = 1.3uH coil. Wind 12 turns #28 magnet wire on a T50-2 toroid core (Electronix Express # 152750-2) and adjust turns spacing for loudest signals in the middle of the band (windings cover about 1/3 of the core).

Caps = green mylar types at Electronix Express

Detector

Diodes = 1N4148 / 1N914 silicon switching diode

VFO

Q1 is 2N3904 NPN silicon, like I use in most of my projects.

Transformer is the red core Local Oscillator "can" that is used in most transistor radios. Electronix Express # 16IFR, or Mouser/Xicon 42IF100-RC.

CALIBRATION: Set a nearby receiver to 2.000 MHz, and, with the DC-80's tuning cap turned fully clockwise (top of band; least capacitance), use a screwdriver to adjust the red core until a loud "whoop!" is heard in the 2 MHz receiver. This sets the top of your DC-80 at 4.000 MHz (top of the 75M band), with the VFO running at half the RF input frequency. Re-calibrate if the bottom of the 80m CW band falls out of range, if needed (i.e., the receiver may not tune the entire 3.5 - 4 MHz band, depending on parts tolerances, etc.)

Tuning capacitor is Electronix Express p/n 14VCRF10-280P, the typical AM transistor radio plastic tuning cap with 3 leads. In this receiver we connect the two end leads together (connects to L.O. transformer) while grounding the middle lead.

~~CW Filter~~

~~Inductor is a 100 millihenry cylindrical choke, Electronix Express # 150100M.~~

~~CW Filter switch is SPST toggle or slide switch, whichever floats your boat.~~

Audio Preamp

Q2 & Q3 are 2N3904 NPN silicons, like I use in most of my projects.

Volume Control = 10k Ohm potentiometer with ON/OFF switch, Electronix Express # 18PMS10K

Power & Miscellaneous

9 volt battery

Battery clip

100uF, 16vDC electrolytic capacitor (bypasses entire receiver, preventing motorboating oscillation)

Final Comments

~~The receiver needs a "Fine Tuning" control. This could be a small-value variable cap strapped across the Main Tuning cap in parallel with it.~~ The single, miniature plastic variable cap knob has no gear reduction or vernier action (obviously) and it's hard to properly "clarify" SSB voice signals. There's also some body capacitance effect with the circuit unenclosed. Tuning is pulled off frequency when you've zeroed in on a station and then taken your hand away.
Added a Fine Tune "Clarify" Pot; see above.

There is still some discernable AM bleedthrough, but not much at all. It's much easier to mentally screen it out with this receiver, compared to, say, a *Pixie* or other simple Direct Conversion receiver which lacks a double-balanced diode ring mixer up front.

The receiver could also use some form of AGC, like I use in the AGC-80 series. But, as I said, this prototype was meant to prove the 1/2 VFO frequency concept of the Polyakov-style mixers; these other comments are refinements for another day.

If you decide to put one of these simple receivers together, I'd like to know how yours works out. Email me at rick@ke3ij.com

---

Back

Ugly/Ground Plane Construction

The Method I Use in Building My Simple Receivers

Oct. 7, 2006 by Rick Andersen, KE3IJ

Occasionally I get emails from readers who want to know how I build these simple radio receiver circuits on an "L-shaped chassis" without cutting and scoring the copper, what I mean by "L-shaped chassis," or "what's all this about 10 megohm resistors?", etc. I tend to forget that not everybody has done this before, and I usually take it for granted that the reader is an accomplished "basement-tinkerer" and should therefore be able to just look at a schematic diagram and then come up with his own layout and method of construction. Sorry if I have annoyed anyone -- that wasn't my intention.

When I first design a circuit, I make what a friend of mine used to refer to as a "spider" (or, "spider-web")-- basically just construct the circuit by soldering the components together, lead by lead, into a reasonable facsimile of the schematic (no chassis or pc board necessary-- the stiffness of the soldered leads themselves hold the "spider" circuit together). This method is quick, and allows me to modify things fairly easily. It also grows rather quickly into a "haywire monstrosity" if I allow it.

Sometimes I do use a piece of copper-clad pc board as a ground plane, even during the "spider" stage, as the photo below illustrates:



A "haywire" mess of my "AGC-80" Regen receiver in its early, experimental stage

To make things a bit clearer to you who have never built projects in this way before, I have attempted a free-hand diagram using Microsoft "Paint", which I converted to a .gif file and which you see below.

In the top-center of the diagram is the schematic for a simple common-emitter audio amplifier stage. The left side of the diagram illustrates how one might translate that schematic into an actual circuit on the copper-clad pc board. At right is a diagram of the "L-shaped Chassis." This is the style in which I build most of my circuits.

Basically, I use 2 pieces of 5x7 inch copper-clad pc board, available in the USA at **Radio Shack** [free plug]. One piece lies flat (the bottom piece), which is what I have shown in the diagram. I build my circuit on this bottom piece, using the copper floor as my ground connections ("ground plane"). Any resistors, caps, etc., that go to ground in the schematic, are literally soldered to this bottom ground plane and stood upright. At their top ends, the rest of the circuit is soldered, suspended up above the ground plane. Anywhere that I think I need some mechanical stability, I use a vertical 10 Megohm resistor, which acts to prop up and support the rest of the wiring above the ground plane. For most of the circuits I build, 10 Megohms is much higher a resistance value than any of the resistors in the circuit itself; therefore, the circuit pretty much ignores the 10M "posts", electrically, and they remain simply a mechanical "standoff insulator". The 2nd piece of copper clad board is drilled for switches, potentiometers, tuning caps, and earphone jacks, etc., and then is soldered at right angles to the flat bottom piece, making an "L-shaped chassis". It also helps to solder triangular pieces of copper-clad board as mechanical braces, at the corners where the front panel is soldered to the bottom ground plane.


Example Circuit:
+ 9v
2k
33k
OUT
C1
IN
Q1
+ C2
22uF
10K
1K
Use 10 Meg wherever a sturdy "post" is needed
9v Battery
IN
C1
33k
2k
10Meg
10K
Q1
22uF
C2
1K
Solder to "ground plane"
Copper-clad pc board
Copper surface
Front Panel
Bottom Ground Plane
Triangular Reinforcement

Below is a photo of my 2006 creation, the "AGC-80", a Regen receiver for the 80 Meter ham band with audio-derived AGC. There's an article on this receiver elsewhere on this website; meanwhile, notice that it is built in the same way outlined above-- an "L-shaped" chassis made of a bottom piece of copper-clad board, soldered to a vertical piece of the same kind of board which is the front panel. [I also added a back wall to hold the antenna jack, and a right wall to hold the audio output jack, as well as a triangular reinforcement piece of copper-clad, at bottom-left between the front panel and bottom piece, although you can't see it in this photo.]

To the right of the AGC-80 is the infamous Radio Shack/Archer little beige Amplified Speaker that I'm always mentioning. I may knock Radio Shack for other reasons [for example, that they have pretty much left us hobbyists behind, and have become just another consumer electronics store] but I will always say good things about their little $12.95 beige-colored Amplified Speaker. It works like a charm for the kind of projects I build. I also run an audio cable out of the Radio Shack amp to a bigger speaker, for better-quality sound-- in the photo you can see a white "Optimus" computer speaker pressed into this service. While the Radio Shack's speaker does a fine job, the Optimus sounds quite a bit louder and way nicer. Of course, you may argue that a *real* Electronics Geek rolls his *own* audio amp rather than rely on a commercially-made, external one. Well, I'm often too impatient to build the audio power amp myself, after having spent hours or days getting the RF part of the radio to work the way I want. Also, homemade audio amps tend to oscillate (squeal, motorboat, howl) in mysterious ways once lovingly installed on the same circuit board as the RF circuitry.... After a while one grows tired of trying 50 ways to make it happy, and would rather just hook up an Amplified Speaker and be done with it.

To each his own.



Please realize that you don't have to follow this method of construction (usually called "Ugly Construction" by hams), but I would advise you to make sure there is some equivalent of a copper ground plane in most of your radio projects... it helps to shield the circuit from outside influence (particularly when connected to earth ground) and contributes to stability.

I hope this has helped to give you a little better idea of the methods I use!
73 de Rick, KE3IJ

[Back](http://www.ke3ij.com/construct.htm)

WØBTU Beverage Receiving Antennas

How to build your own one- or two-wire Beverage antennas that work great.

- What is a Beverage antenna?
- Why would you want one?
- Are they difficult or critical to put up?
- A Simple one-wire Beverage antenna
- Two Directions From Just One Antenna!
- Wire spacing for bi-directional Beverages
- Beverage antenna materials
- How High should a Beverage be? | How Long?
- Improved Beverage antenna Matching Transformers
- Terminating resistors
- Proper Grounds for Beverage antennas
- Coaxial cable to feed a Beverage
- Calculating Beverage antenna impedances
- No room for a Beverage?
- BOG: Beverages On the Ground
- Transmitting on a Beverage antenna
- Frequency range of Beverage antennas
- Beverage antennas near other objects and each other
- Misc. Beverage antenna information
- Buy Beverage matching transformers
- Sound recordings of Beverages

SHARE

What Is a Beverage antenna?

The Beverage antenna is simply a straight wire, usually several hundred feet long and about 8 feet high. It is a VERY effective antenna that will enable you to hear extremely weak DX signals that are buried in noise or covered up by other interference. It was invented and patented many years ago by Dr. Harold H. Beverage, who worked for RCA. Mine are "magic" antennas! On a scale of one to ten, the "wow factor" is an 11.



BACK TO TOP

Why would you want one?

Because you will hear LOTS of weaker signals that you won't hear on your vertical, inverted-L, dipole, or most other antennas; not to mention a worthwhile reduction of unwanted signals and noise from undesired directions. The S/N (signal-to-noise) ratio of a Beverage is far superior to any vertical, dipole, or loop, as well as most compact receive-only antennas.

If you have the space, you should consider at least one Beverage antenna, even just a simple single-wire Beverage. (If not, there are alternatives to a full-size Beverage.)

Even a short Beverage antenna is better than no Beverage! Although Beverages are typically at least one wavelength long on the lowest band, even a half-wave (or even shorter) Beverage antenna can *very* often out-hear any vertical, dipole, or loop.

The Ultimate SWL Antenna.

The Beverage antenna is the ultimate SWL (Short Wave Listener) antenna. Period. They are not just for amateur radio operators. Or do you like crystal radios? You haven't lived until you've connected your crystal radio to a Beverage antenna. (And no, it's NOT cheating to do that! :-)

Beverages are extremely broadband antennas.

Beverage antennas do not require re-tuning to QSY or switch bands, because they are non-resonant. The design we use covers 100 KHz to 30 MHz without retuning a thing or even having to adjust the signal level.

The 580' bi-directional Beverages we made from electric fence wire work absolutely fantastic for receiving weak DX signals on 160 meters, but they also work extremely well on 80, 60, and 40 meters, and often on 30 and 20 meters (and rarely, even up to 10 meters) as well. On any HF band, we rarely listen on the dipole or vertical antenna that we're transmitting on, except to see how much better we can hear on the Beverages antennas.

We sometimes play with them on the AM broadcast band. Even during the daytime, there are very few frequencies where we cannot listen to at least one radio station. And on some frequencies, we can select up to four different AM stations on the same frequency as we switch among four different directions.

Recently, we've been listening on VLF, down as low as 150 kHz, to Foreign AM broadcast stations.

BACK TO TOP

Are They Hard to put up?

No. It has been said that Beverage antennas "want to work". In other words, their construction is not critical. If they are not exactly in a straight line, or if their height varies a little (such as if you have to cross a ravine, or go up and down a hill — even a steep hill — they will still work great. They can even be run through a thick woods, using trees as supports, without affecting their operation.

And neither do they cost hundreds of dollars.

BACK TO TOP

A Simple, Single-Wire Beverage antenna

All you really need for a simple Beverage receiving antenna is a long single wire, 6 to 10 feet high, between one-half and one wavelength long (or more, up to a point) at the lowest desired frequency. The far end should be pointed more or less in the direction you want to receive signals from. (For example, you might try a Beverage pointed NE towards Europe.)

You'll need coax (almost any old coax) feeding the near end, a simple matching transformer, a termination resistor at the far end —pointed in the desired direction— and grounds at both ends, like the diagram above. Much of the information on this page that applies to bi-directional Beverages also applies to a one wire Beverage antenna.

W8JI has a good tutorial on single-wire Beverages.

BACK TO TOP

The WØBTU Reversible-Direction Beverage antennas

01/14/2010

I have two 2-wire, switchable bi-directional Beverage receiving antennas. Both are 580' long and are supported on 10' high posts 100' apart.

Some photos are here. NOTE: Those photos need updating; the present Beverage antenna transformers at WØBTU use the Amidon BN-73-202 ferrite cores as shown below.

We (W0BTU and XYL KD0LAJ) built them for 160 meters, but they work well from VLF (well below the low end of the AM broadcast band) to 20 meters or more.

Looking from the air, our Beverages cross like an X, covering:

- NE (Europe, N. Africa)
- SE (S. America, Caribbean, S. Africa)
- SW (Australia and Oceania)
- NW (Japan, AK).
- Aerial photo

We can turn a knob (photo below) and instantly select any of those four directions that we want to listen towards.

BACK TO TOP

There Is More Than One Way to build a 2-wire Beverage antenna.

There are different ways to make bi-directional (switchable direction) Beverage antennas. Here are what I think are the best ways:

- One Beverage here (SE-NW) has the direction and termination switching arrangement using a remote relay (at the Beverage antenna's feedpoint) to switch directions with a single run of coax.

- The other Beverage here (NE-SW) has no remote relays; instead, there are two runs of coax running all the way from the antenna to the operating position; and the direction switching relays and terminating resistors are there.

Neither method requires a separate control cable to switch directions. The 12 volts DC direction switching voltage is sent up

NW
NE
SW
SE
BEV ANT
TX ANT
RX ANT
SPARE RX ANT
ICOM IC-751A
DRAKE R-4C
RECEIVER

the same coax that the received signal comes down. This only requires two .1 uF disc ceramic blocking capacitors and two RF chokes, which are made from approximately 7 turns of #26 magnet wire through an Amidon FB-73-801 ferrite bead. (We use Belden® heavy-armored Polythermaleze® insulated wire for these chokes to prevent shorted turns, as there is no room for a protective liner inside this bead and these cores are conductive.)

We have had a number of requests for schematic diagrams of our reversible Beverage antennas. Here are diagrams for both types.

- The feedpoint box schematic for our NE-SW Beverage is similar to the one in ON4UN's book which uses two coax feedlines (show to the right).
.
- Control Panel Schematic for both W0BTU two-wire Beverage antennas
- Below is the schematic of the remote feedpoint box on our SE-NW Beverage, which uses a single coax feedline (click to zoom).


T4
T5a
n2
n1
n1
n2
T1
n2
n1
T1 & T4 - 6.25:1
T5a - 1:1
(A)
J2
J1
75 ohm feedlines


OHMITE OY
470
2
R1
K1 B
K1 A
BIFURC
T1
1:1
SEC
PRI
C2
.1
C3
.1
33 K
33 K
GDT
GDT
TIP
TIP
W0BTU BI-DIRECTIONAL BEVERAGE ANTENNA
© 2011 Comtech Research LLC. All rights reserved
580' BEV
T3 - 1:1
GD
GD
SEC
PRI
See http://www.w0btu.com/Beverage_antennas.html for details
COIL
FRAME
K1
C4
MOV
RFC
T2
6.25:1
SEC
PRI
C1
.1
F
CONTROL IN
SIGNAL OUT
TIP
GROUND

**NOT SHOWN ABOVE: GDT added between coax shield and ground.
Protects K1, RFCs, T2, etc. from lightning surge current on coax shield.**

- Original Beverage antenna remote direction switch (about 1980, based on a drawing from W8JI)

How do two-wire reversible direction Beverages work? Greg, ZL3IX has written an excellent explanation: (4.7 MB files)

- PDF format (2.7 MB)
- Microsoft Word .doc format
- Open Office .odt format

BACK TO TOP

EZNEC plots @ 1.83 MHz - W0BTU 580' Bi-directional Beverage antennas



How Far Apart should the Beverage antenna wires be?

There is no need to use wide spacing between the two wires in any bi-directional Beverage antenna! Some people still use 6" or even 12" wide spacings. *Don't.* That wide spacing makes no electrical sense at all, and is subject to imbalance from nearby objects. One-inch (approx.) spaced 450 ohm window (ladder) line works most of the time, if you don't want to make your own ladder line like we did.

When deciding how far apart AND how high we are going to make our Beverage, we need to keep the following important point in mind:

> For two-wire reversible Beverage antennas, the **line impedance** (of the open-wire line) should equal **the antenna impedance** (between the line and ground, also called the *common mode impedance*).

We used "galvanized" (probably plated with cadmium rather than zinc) steel electric fence wire labeled "17 gauge", and calculated the diameter (.061") vs. spacing (1.10") so that the line impedance was equal to the antenna impedance at 10' high. If you construct your Beverage so that those two impedances are significantly different, then you need to change the impedance ratios of the matching transformers.

> For example, if we use 145 ohm line (surplus twisted pair telephone line), which at 6 feet above ground has a common mode (both wires to ground) impedance of about 480 ohms, then we would need to change the 1:1 transformer to about 3.33 to 1 for optimum performance (F/B ratio) of our Beverage. (The required ratio of other transformers would change also.)
>
> However, since we want to use matching transformers with binocular cores (due to their superiority over toroids or beads), using other than 1:1 line-to-antenna Z ratios can present some challenges.
>
> - Practical Z ratios are somewhat limited. Chart of turns ratios (PDF)
> - Some impedance ratios require so many turns that winding them can present winding challenges (too many wires to fit inside the core). This also can add unwanted inter-winding capacitance.
> - In transformers where balance is important, we should have an even number of turns on the center-tapped winding. Sometimes, with certain Z ratios, trying to accomplish that also requires many more turns.
> - Using half-turns (to try and obtain a certain Z ratio) are usually a no-no; that can cause significant losses.

Before we just put up any old pair of wires, then, we need to make sure that we can make a good set of matching transformers without these issues cropping up later.

BACK TO TOP

Calculating Impedances vs. Dimensions Is Easy

- Line impedance: The impedance of the open-wire line that the bi-directional Beverage antenna is made of. This depends mainly on two things:
  1. The diameter of the wires
  2. The spacing between the wires
- Antenna impedance: the impedance of both those wires *to ground*. This depends mainly on three things:
  1. The diameter of the wires
  2. The spacing between the wires
  3. The distance from the wires to the earth.

Here's some spreadsheets that you might find useful for calculating these impedances, in Excel or Open Document (Open Office) format. They were invaluable to me in designing the open wire line for my Beverage receiving antennas, so that I could use 1:1 reflection transformers. They also take into account whatever dielectric is between the wires, air or plastic. You can open the .ods file with the free Open Office spreadsheet.

www.w0btu.com/files/antenna/OpenWireZ(2).xls
www.w0btu.com/files/antenna/OpenWireZ.ods
www.w0btu.com/files/antenna/OpenWireZ.xls
www.w0btu.com/files/antenna/OpenWireZ%20telephone%20wire%201.ods

We fabricated our own open wire line out of plated steel electric fence wire, which is *very* strong. Using the known values of
(1) The wire diameter (.061") and
(2) The desired height above ground (10'), I then **used a spreadsheet above to calculate the spacing at which the antenna impedance equaled the line impedance** (1.10"). I then made some plastic spacers with two ~.066" diameter holes 1.10" apart; this spacing made the common mode and differential mode (line) impedances nearly equal (about 410 ohms).

Headless nails driven into a small piece of wood, clamped to a drill press table, makes easy work of drilling many spacers. When drilling the second hole, place the first hole onto a nail nearly the same size as the holes.

Impedance Equation page

BACK TO TOP

What Materials to use for the Beverage antenna?

They can be made from almost any conductor, be it copper, steel*, aluminum, 450 or 300 ohm ladder (window) line, twisted-pair line, and even coax.

**If using magnetic steel, it should be plated with a non-magnetic material of sufficient thickness.*

A major consideration is strength, and that's only one of the reasons **we use plated steel electric fence wire**. We have animals (deer) and falling tree limbs. The galvanized electric fence wire, 10' high, has never broken even when a very heavy limb fell from the top of a tree onto the end of one of them. Take a look at these photos, and you'll understand:

Photo 1 | Photo 2 | Photo 3 | Photo 4 | More photos

That branch weighed several hundred pounds (and it was coated with thick ice) and fell all the way from near the top of the tree, where the Beverage broke its fall. No 450 ohm line ladder line would have held up like that!

Earl Cunningham, K6SE (SK) swore by galvanized electric fence wire for Beverage antennas.
He said copper was inferior, it did not produce as good a F/B ratio. (I agree, but we never obtained the 60 dB F/B ratio on sky wave signals that Earl claimed.) Reason being, the signal from the feed end has to travel the length of the antenna twice, further attenuating the unwanted signal. Earl once put up copper, but took it down and replaced with with galvanized electric fence wire. Sometimes losses are an advantage. Lossy wire also makes the termination less critical.

I've recently read where someone complained that their electric fence wire rusted rather quickly. But I (and many other satisfied users) have never experienced that. Not with any brand I ever purchased, made in the USA.

There is NO need to use insulated wires for a Beverage antenna, unless you are using a BOG (where the antenna is actually touching the earth or the wet vegetation just above it).

It is not recommended to make a transmitting antenna out of lossy, high permeability steel wire.

What about Window Line?

You could use ready-made insulated 450 ohm window ladder line (the kind with the rectangular holes punched between the wires every so often) and save yourself the trouble of making your own open-wire line for your Beverage antennas. Lots of hams do.

However, some potential problems to consider with window line:

1. It has a lot more wind load and might flop around and break in the wind, especially if it's too loose. Twisting it might help. Ask someone who uses it for their long Beverages (we don't).
2. The line impedance changes **a lot** when it's wet, icy, or even covered with snow. (Covered with enough ice, the line impedance could drop well below 100 ohms!) *That can severely affect the pattern and front-to-back ratio of your Beverage.*

The so-called "450 ohm" brown insulated window line I have here is actually about 420 ohms dry (which is OK).

BACK TO TOP

How High should a Beverage antenna be?

Although they can be lower and still work just fine, they should be high enough to walk under. Mine are 10' high, which is about the maximum height for a Beverage if you want to use it on the higher bands. Unlike transmitting antennas, higher is not better, but rather, worse.

There's a rumor that there is somehow a benefit to sloping the ends down to the earth gradually in, say, the last 60 feet at each end. (The reasoning was that the vertical drop at each end might pick up unwanted signals off the side). *Don't do it*. That adversely affects the antenna's impedance and could actually hurt performance. And besides, it's a safety hazard.

> "There really isn't a logical reason to slope the ends of a Beverage. After all, six feet of vertical drop is six feet, no matter if the drop is over 50 feet or straight vertical." --W8JI

BACK TO TOP

How Long should a Beverage antenna be?

Typically, they are made about one wavelength long. But even a short Beverage is better than no Beverage. Although Beverages are typically at least one wavelength long on the lowest band, even a half-wave (or even shorter) Beverage can very often out-hear any wire, vertical, or dipole you might be using. For example, if you only have room for a 200' - 250' Beverage on 160 meters, it may well surprise you what it can do for you.

I chose 580' because it is about one wavelength on 160 meters, my primary band of interest. That length gives a 3 dB beamwidth of almost 90 degrees. Therefore, the entire 360 degrees of the compass is covered in just four directions. If you are only interested in covering certain areas of the world, you should think about making them longer, as that will narrow the beamwidth.

It has been said that it is a waste of time and counterproductive to make your 160 meter Beverage longer than two wavelengths long (over 1160' on 160 meters). That may very well be true in most locations. But that really depends on the ground conductivity. K5RX reports that with his exceptional ground conductivity, his three-wavelength-long Beverage is the best one he has. And he has plans to extend it another 300' soon to 2100'. (Jim reports that just one ground rod at K5RX measures about 10 to 15 ohms resistance.)

I use them on 80, 60, 40, and 20 meters --where they are very long in terms of wavelengths-- and they work VERY well there, even though our ground conductivity is likely not as good as K5RX's.

Just keep in mind that the longer the Beverage, the narrower the beamwidth!

BACK TO TOP

Beverage Antenna Transformers

We cannot just connect our coax directly to a Beverage antenna. A transformer is required for the following reasons:

1. In either single- or bi-directional Beverages, to match the low impedance of the coax to the high impedance of the Beverage antenna
2. In bi-directional Beverages, a reflection transformer is required to receive signals off the feed end.
   A second feedpoint transformer is also required to receive the push-pull signal from the opposite end, sent down the antenna from the reflection transformer.
3. To isolate the feedline from the antenna, in order to avoid common-mode pickup of unwanted signals and noise on the coax shield.



The **transformers are the most critical component in any Beverage antenna** design, especially bi-directional Beverages. You see a lot of different Beverage antenna transformer designs in different books, magazine articles, and all over the Internet, and the main goal of writing this page was to clear the dust and get to the meat of good Beverage transformer design. They are not difficult at all to make. Here's how.

A Beverage antenna feedpoint transformer MUST have separate windings (as opposed to an autotransformer) to prevent reception of undesired common-mode signals and noise.
We wind them with different colors of #24 or #26 gauge magnet wire, which makes it easier to tell which windings are which after they are wound through the core.

For a 6.25:1 impedance ratio Beverage antenna transformer, using the core below:

```
Primary (Hi-Z Bev.): Five turns brown #26 magnet wire
Secondary (75 ohms): Two turns green #26 magnet wire
```

If you use 50 ohm coax, then make a 9:1 transformer by using six turns on the primary instead of five.

Note that one turn is through both holes as shown in the photo.

Impedance ratio chart (PDF)





There are a number of popular Beverage antenna transformer designs floating around, some of which are so lossy that they need a preamp to hear the weakest signals. I used to make them from stacks of Amidon FB-73-801 ferrite beads. However, we now use Fair-Rite 2873000202 (Amidon BN-73-202) ferrite binocular balun cores, which are far superior and much easier to make. They seem so small (only 9/16" long), but do they ever work! **This binocular core design provides significantly lower loss, greater bandwidth, and freedom from core saturation than any toroids or beads will.** Normally, a preamp is NOT needed.

Shown to the left is a 2873000202 / BN-73-202 binocular core with a special liner that we use, ready for winding and labeling. Among other advantages, the irradiated polyolefin HST liner protects the magnet wire from touching the conductive core, abrading the insulation, and degrading the performance of the Beverage antenna.

Reflection Transformers

If you erect a bi-directional Beverage, just make sure you use a reflection transformer like T5a in the schematic from ON4UN's book. That's exactly the way mine are wired, and they work great.

Forget about the skimpy design that grounds only one wire, but leaves the other wire floating! That inferior arrangement may work sometimes (depending on the length of the wires and the frequency you happen to be listening on), but a reflection transformer is so simple to make. You have to make two anyway (at the feedpoint); why not a third one at the far end? You will see a better front-to-back ratio using a reflection transformer.

On the reflection transformer (and sometimes on another feedpoint transformer), one winding uses two pieces of magnet wire, twisted together as shown. (Note that they're slightly different colors). The twisted bifilar winding helps ensure that the signal levels are not unbalanced (very important on a two-wire Beverage antenna).

1:1 Beverage transformer after winding. This can be made into either a 1:1 center-tapped feedpoint transformer or a 1:1 reflection transformer. - Secondary: 4 turns #26 green - Primary: 2 turns #26 twisted bifilar-wound (total 4 turns).	This is a 1:1 reflection transformer that we make and use, per N1EU's design info. One winding is made from two bifilar turns of #26 twisted pair, and the other winding is four turns of green #26 magnet wire. The green wire is connected to ground, and the other two wires connect to the Beverage antenna.







None of these Beverage antenna transformers require Faraday shields.

You can now order these transformers from us

Click photos for larger image



The control box to the left —containing the Beverage antenna matching transformers, relay, etc.— is the newest one, and it's currently installed on my SE-NW Beverage antenna. (Click to zoom.) This design turned out to be the best one we ever made. It has better sensitivity and F/B ratio of any single-coax Beverage antenna switch box that I have ever made. (That could be because of a different termination resistor value.)

I have received many inquiries over the years about these enclosures from both amateur radio operators and antenna manufacturers. This one is a Hammond NEMA 4 watertight enclosure, P/N 1554D2GYCL (clear lid), 4.7"L x 2.6"W x 2.4"H. The one below and on the right is Hammond P/N 1554D2GYSL (smoked lid, same dimensions). Both are polycarbonate, completely waterproof, UV resistant, have gasketed lids with 2-piece tongue-and-groove construction, and are designed for outdoor applications. The one with the clear lid can be obtained from Mouser, and the one with the clear smoke lid can be purchased from Newark. (In units exposed to the sun, the temperature inside the enclosures would likely be lower with the smoked lid. Suit yourself.)

Since we use non-hermetically-sealed direction switching relays (because we need bifurcated/paralleled heavy-duty contacts and grounded frames for maximum reliability), it's very important to keep out moisture! We once had a relay freeze up in the winter, from condensation in an enclosure that was not sealed like these are.
The secret to keeping moisture out includes properly filling all the connectors with non-hardening, clear silicone dielectric compound. As the weather changes, that compound moves in and out of the connectors like a piston, providing a near-perfect hermetic seal that prevents the humid air outside from mixing with the dry air inside the enclosure.

We do NOT use vents, like some people incorrectly insist on. There has been no evidence of moisture ingress (such as condensation on the clear covers) whatsoever.

I also have some smaller Hammond 1554B2GYCL enclosures for the reflection transformers. However, there is nothing about the reflection transformers that would be harmed by moisture ingress, so I usually just use prescription pill bottles or other



types of enclosures without a hermetic seal.

Some components inside:

- 1:1 and 6.25:1 transformers (shown above) with isolated windings.
- Heavy-duty ceramic Bourns 90 volt Gas Discharge Tubes (between each wire to ground, and between the coax shield and ground) to help protect the components from getting damaged from nearby lightning strikes. We have not lost a transformer (or any other component) since we began using these. (Because of these, we could probably use a much lighter-duty termination resistor than we do.)
- 33K drain resistors to greatly extend the life of the GDTs.
- 4PDT P&B/Tyco relay. The coil has a .1 uf capacitor and a low voltage MOV in parallel with it. The contacts that select the direction are paralleled for increased reliability, since we are switching a dry circuit. This relay was also chosen because it is possible to ground the frame (which we do).
- Single 470 ohm Ohmite Type OY non-inductive termination resistor, paralleled with another resistor to obtain the proper value of termination resistance.
- Bright green clear LED connected to one of the relay contacts, so that we can see if the relay closes from a distance. It can be seen from several hundred feet away at night (it's so bright, it's like a green laser with less than 6 mA of current!). I added it because after lightning blew out my old transformers (before I added the lightning protection), I thought I had a bad feedline connection somewhere (I did; I got a bad batch of F connectors). And it came in handy when I first put it into operation.

NOTE: The solder lug on the coax F connector is NOT grounded! It was simply used in lieu of a flat washer. Any coax shield ground must be kept separate from the antenna ground for common-mode isolation.

The control box to the right is for my NE-SW Beverage. (Click to zoom.)

Since there are two runs of coax feeding it, it's much simpler than the one above. The switching and termination take place in the control panel next to the radios, rather than remotely. It contains:

- Two 6.25:1 transformers:
  - One balun, center-tapped
  - One unun
- Heavy-duty ceramic gas discharge tubes (GDTs) to protect the transformers from nearby lightning strikes.

Those two extra black tip jacks were for grounding the Beverage antenna in advance of a thunderstorm. Since adding the GDTs, I no longer use them; I just leave the antenna plugged into the control box all the time.

There are also GDTs in the reflection transformers for lightning protection, as well.

See the following links for other information on the general design of the transformers we use. More info on building good Beverage transformers is here:

- http://www.w8ji.com/beverages.htm
- http://n1eu.com/topband/BeverageXfmrs.htm
- Reversible Beverage antenna at ZL3IX (pdf)

BACK TO TOP

Terminating Resistors



Although a terminating resistor is optional on a single-wire Beverage, it is *highly recommended* unless you need to receive off both ends at once. Adding the resistor will greatly reduce noise and QRM from unwanted directions.

A 470 ohm resistor will usually do just fine. For a single-wire Beverage, you can subtract the ground resistance from the required value.

> Some people go to great lengths to get the value of this resistor just right (and there's nothing wrong with that). It's even possible to remotely adjust the value of the termination resistor. (Another link here). However, the actual termination resistance value is not really all that critical. (Having said that, the F/B ratio of a Beverage antenna is directly related to the return loss.)

We use Ohmite type OY metal composition resistors, 470 or 75 ohms, 2 watts. They are FAR more rugged than others for withstanding destructive surges caused by lightning strikes (either cloud-to-cloud or ground-to-cloud strokes) in the vicinity. Mouser Electronics # 588-OY-470-E, only $1.20 each. (If you enjoy having to replace blown termination resistors, then use something else. :-)

BACK TO TOP

What About the Grounds at each end?



Normally, a few short (~50') ground radials and a couple of ground rods at each end of the Beverage have proven to be effective. Works for me and lots of other happy Beverage antenna owners.

Check out W8JI's number of radials and ground rods vs. ground resistance measurements.

Just keep in mind that if you are using a bi-directional Beverage and it doesn't seem to hear well off the feed end, then you may need to improve the ground at the far end (at the reflection transformer). When I put up my first 2-wire bi-directional Beverage (with different transformers than I use now), I occasionally had to 'help' the ground conductivity at the reflection transformer end. Although there were two copper ground rods and three radials, the only thing that made it work right when receiving signals from the feed end direction was to pour a hot, very concentrated solution of magnesium sulfate (Epsom salts) around the ground rods. (The ground was frozen at the time.) *The Beverage antenna's reflection transformer ground is more critical.* For a single-wire Beverage, the ground at the end is not as critical.

That's no longer necessary, as I've added more radials and the ground rod conductivity has improved after a few months. But if you have a problem with very weak reception off the feed end of your two-wire Beverage, it would be cheap and easy for you to try. Epsom salts are available at about any drug store or grocery store.

> Note that the signal strength off the feed end of a bi-directional Beverage can be weaker. That's normal, and a non-problem.

- The feed ends (where the coax connects) of my Beverages have two ground rods and three or four 50' long surface ground radials.
- The far ends (reflection transformer ends) have two ground rods and up to seven 50' long surface ground radials. NOTE: You should avoid running radials directly underneath your Beverage antenna.

One ham had a problem with the rock being very close to the surface, and wondered whether cut-off ground rods driven in at an angle would help. If that is your situation, consider a ground screen at the ends (or more radials) as opposed to relying on shortened ground rods.

We do NOT ground the coax shields at the Beverage reflection transformer box, nor do we switch them. The only thing you want to ground at the feed end of your Beverages is the transformer winding connected to the Beverage.

Ground rods: I use 5/8" x 8' copper-clad steel ground rods. However, if the soil here in this part of SW Missouri weren't so full of rocks, I would use 1" copper water pipe instead because it's a lower resistance ground.

BACK TO TOP

Which Coax to feed your Beverage antenna with?

I use 75 ohm, flooded Commscope® quad-shield RG-6 coaxial cable. (The shield is four layers of aluminum: braid-foil-braid-foil; the inner foil bonded to the dielectric). It was designed for CATV use, and because the CATV industry uses so much of it, 1000' spools of it can be obtained very inexpensively!

Beside the low cost, it also has other advantages. "Flooded" means that there is a sticky substance permeating the shield. That sticky stuff is there for the purpose of keeping out water if the coax should get cut, nicked or nibbled on by little animals. It only takes one little invisible cut to let water soak the shield for some distance on either side of the cut. Corrosion of the braid will follow in short order. If water gets inside non-flooded coax, this will not only increase loss, but worse, can cause noise! The noise can sound like static, and can keep your Beverage antenna from working like it should.

The RG-6 coax feeding my Beverage antennas runs along a fence in the grass for almost 600'. I don't require ferrite chokes to prevent unwanted signal pickup. The coax shield is grounded ONLY at the station end, NOT at the antenna.

Crimp-type "F" coax connectors with o-ring seals are fine. You don't need BNC, N, or UHF (which are not waterproof) connectors. To keep water out, fill them with clear silicone dielectric compound before assembly. Home Depot and DX Engineering sell the good snap-on F connectors.

BACK TO TOP

If there's no room for a Beverage antenna

For receiving, a Beverage is simple and easy and very good. If you do not have the room for even a very short Beverage, there are a number of alternative receiving antennas. Look at the Slinky Beverage, BOG, K6SE's Terminated Delta Loop (KAZ), Waller Flag, K9AY, Flag, EWE , or Loop antennas. The Waller Flag has the pattern of a one-wavelength-long Beverage and can be even mounted on a tower and rotated. It requires cascaded, antenna-mounted preamps and careful attention to minimizing unwanted common mode signals.
I have very little experience with any of these; Google is your friend.

Even better than those is an array of loops or phased short verticals. An array of short verticals arranged in a circle is maybe even better than Beverages, but they are much more complex.

> Having said that...
> More than one person has e-mailed me privately and stated in no uncertain terms that their Beverage antennas were definitely superior to their circular array of short verticals. Others on public pages we've seen say just the opposite. In any case, either one is usually superior to a vertical or dipole.

Some people have had good success with loaded or Slinky Beverages. I have no experience with them, but I'd sure like to try a short Slinky.

> http://www.w8ji.com/slinky_and_loaded_beverages.htm

> "No room for a traditional Beverage? Then try a Slinky. I had 5 of the large ones in series over 150' for almost 20 years and it was a solid performer; very quiet likely due to the steel wire loss and a preamp was used. At that time it was my only option for due East/SE where a lot of good DX comes from and I worked a lot that locals couldn't hear, rear rejection was excellent. A K9AY wasn't even close." --KM1H

BACK TO TOP

The BOG: Beverage On the Ground

The very first Beverage antenna made by Dr. Harold H. Beverage himself was in fact a BOG. The **B**everage **O**n the **G**round is described in ON4UN's *Low Band Dxing* 4th edition. I'm convinced that they can work very well on some bands, based on a number of experiences that we've read on the Topband reflector and feedback from our customers.

Recent tests by other hams using even short (approx. 140' long) BOGs show they can often significantly improve the S/N ratio on 40, 80, 160, and the AM broadcast band —as compared to an inverted-L with a good ground radial system— by greatly reducing local RFI from power line noise, etc.

The impedance, velocity factor, and signal levels are a lower than a Beverage antenna several feet in the air, depending on ground conductivity. A very short BOG may possibly need a preamp. KM1H's experience

The lower velocity factor has several effects, one of which is that a BOG can be considerably shorter than an elevated Beverage.

Either a wire laying on the ground or made from coax (so-called 'snake antenna', not a BOG), there's a right way and a wrong way to build one. They can be made either single- or bi-directional.

I once knew a ham who, during a local thunderstorm one Field Day night, used a BOG (or was it a piece of coax?) antenna to receive for 75 phone. He could hear little through the QRN on the dipole he was using, but the receiving antenna on the ground really worked, according to him and others who were present.

You should bury BOG ground radials (if you use any), because they can pick up unwanted signals..

BOG matching transformers and terminating resistors

BACK TO TOP

Is it practical to use a Beverage as a transmitting antenna?

Sometimes it is! I had a lot of fun trying that, and could work many places --even DX-- on the NE Beverage that I couldn't work on a 35' high multiband dipole.

Check out this thread:

http://forums.qrz.com/showthread.php?288071-receive-antennas-only&p=2195483#post2195483

Carl, KM1H kind of lit a fire under me when he said he successfully used his Beverages to transmit. My own experiences on the different bands are outlined there. (To summarize: with 100 watts on SSB, it worked awful on 160, a little better on 80, still better on 40, and not bad at all on 20.)



This is the little transformer I used for both receive and transmit on my unterminated NE/SW Beverage antenna. It handles 800 watts (on SSB) from 80-10 meters. I even used it for a rather long AM QSO with 200 watts carrier. It's amazing how low-loss this tiny little transformer is! Check out these power vs. temperature tests I performed on that transformer with 800w carrier, more than enough time to tune up. The temperature didn't rise to anywhere near the Curie temperature of the core material (310 degrees F.)

I added a half-dozen radials between 25' and 50' long on the ground at the feed end, and started getting unsolicited reports about how much louder my signal was.

The signal from the Beverage is best to the NE USA and Europe, due to its low angle. Closer in, signals are somewhat weaker. It's more of a DX antenna.

BACK TO TOP

What bands are Beverage antennas good for?

Basically, the non-resonant Beverage covers the entire radio spectrum, from VLF to the upper end of the HF (short wave) region. [It is an extremely broadband antenna](#).

They were first used on VLF and MW and first popularized for amateur radio use on the 160 meter band. Still, they continue to be thought of as an antenna that is really not of much use above 80 meters.

Not so. A recent poster on the Topband reflector stated, "If you think they work good on 160, you should try them on 40!"

This lit a fire under me to try them on 40 meters. He was certainly right!

Here are the patterns of my Beverage antennas @ 7.15 MHz:



```
Azimuth Plot                              Cursor Az      0.0 deg.
Elevation Angle  21.0 deg.                Gain           1.4 dBi
Outer Ring       1.4 dBi                                 0.0 dBmax
                                                         0.0 dBmax3D

3D Max Gain      1.4 dBi
Slice Max Gain   1.4 dBi @ Az Angle = 0.0 deg.
Front/Back       29.04 dB
Beamwidth        39.6 deg.; -3dB @ 340.2, 19.8 deg.
Sidelobe Gain    -9.24 dBi @ Az Angle = 45.0 deg.
Front/Sidelobe   10.64 dB
```



```
Elevation Plot                      Cursor Elev    22.0 deg.
Azimuth Angle    0.0 deg.           Gain           0.5 dBi
Outer Ring       0.5 dBi                           -0.01 dBmax

Slice Max Gain   0.5 dBi @ Elev Angle = 22.0 deg.
Beamwidth        22.7 deg.; -3dB @ 9.2, 31.9 deg.
Sidelobe Gain    -3.77 dBi @ Elev Angle = 49.0 deg.
Front/Sidelobe   4.27 dB
```



[The EZNEC+ file can be downloaded here](#). [Other EZNEC files](#)

With the narrow beamwidth of the main lobe and only four directions to choose from, I expected to miss many stations outside the main lobe. However, I was very pleasantly surprised, because in practice, I can almost always hear better on the Beverages than I can on my multiband dipole or 40 meter monoband ground plane. (I do wish I had one pointed due west, though; I think I would hear the USA west coast better on 80 meters and above.)

> I did find a "problem" with using Beverages on most bands: when working stations with similar antennas and power, I can hear the other guy very well; but since the station at the other end of the QSO doesn't have a Beverage (or other low-noise RX antenna), he experiences the same QSB, etc. as I do when I listen to him on my transmitting antenna. (Hearing that well is a good problem to have. ;-)

But what really is the practical frequency range of Beverage antennas? I recently got a private e-mail that in one rare instance, his Beverage antenna outperformed his array of stacked Yagis on 10 meters! Don't expect that, but they have been reported to work very well on 20 meters on a number of occasions. They are almost always better than my dipole on 20.

Here it is on 80 meters:



BACK TO TOP

What about erecting Beverages near other objects, or near other Beverage antennas?

Beverages should not be erected over metal fences. Why? A Beverage requires a poorly conductive ground (poor compared to the wire itself) under it to work right.

http://lists.contesting.com/archives//html/Topband/1997-04/msg00080.html
http://lists.contesting.com/archives/html/Topband/2010-11/msg00006.html

Having said that, ZL3IX successfully built one above an apparently ungrounded metal fence. He explains how he did it near the end of http://www.g3xrj.com/RxArray_files/2wire_bev/2wire_bev.htm.

If it can be avoided, don't run them parallel with other conductors (metal fences, power lines) for long distances. Try and run them at an angle to avoid coupling to them.

Beverages, being non-resonant, usually do not readily interact with each other. This is why we can have cross-fire or end-fire Beverage antenna arrays, because the antennas do not couple to each other to any significant degree. (Mine cross at about 90 degrees to each other, are only about 7 inches apart where they cross, and do NOT affect each other.)

Multiple Beverages Using a Common Ground

Feeding more than one Beverage antenna from the same point using a common ground is a bad idea. The reason is that signals from all of the Beverages --not just the one you have selected to listen on-- pass through that ground simultaneously. And since that ground has resistance, there is a very real potential of sharing signals between Beverages. If this happens, you might hear undesired signals (and noise) from unwanted directions picked up by the other Beverage(s). The front-to-back and/or the front-to-side ratio will seem degraded. The higher the resistance of the ground, the more noticeable this effect will be. Note the following references:

Different Beverage Antennas from One Hub

Never run different Beverage antennas from a single spot, using a single ground rod (or ground system). In such a case you will, via the common ground rod resistance, cross-couple part of the signals from one Beverage into another Beverage.

If you want to run different Beverages from one point, run the master feed line to a switching box (head end of the master feed line), and fan out to various feed points, each of which is fed via a separate feed line, in such a way that the ground rods of these feed points are separated at least 5 meters from one another.

Never bring multiple antennas to one feedpoint, especially when they share one common ground. I've noticed a definite deterioration in pattern with multiple feedpoints arranged with only ten feet of spacing, even when they had separate ground systems. One set of Beverages installed with 5-10 foot of feedpoint separation has noticeably poorer patterns than other identical length antennas with wide separation at the feedpoint.

From http://www.w8ji.com/beverages.htm

From the the ARRL's *Low Band DXing* by John Devoldere, ON4UN (5th edition)
p. 7-76

Conclusion: **Never share grounds between antennas.** If you really need to feed more than one Beverage from a single location or hub, then you should make provisions to remotely disconnect and properly terminate the unused antennas.

BACK TO TOP

Misc. Beverage antenna notes and information

What Direction to point our Beverage antennas?

If you are located in the USA, DON'T orient your Beverages either due North, South, West, or East *unless you have a very good reason to!* **They should point either Northeast, Northwest, Southwest, or Southeast. Here's why.**

If you look at an azimuthal map (or use software like DX Atlas) from most locations in the USA, you'll see that —generally speaking— Beverage antennas pointing due East, West, North, or South are NOT pointing in the optimum direction!

- North is over the poles, and any aurora (which occurs much of the time) destroys propagation in that direction.
- There's usually not much to hear when we point either due South or due North.
  - EXCEPTION: If you live in an area of the US where there is a high population density both north and south of you, such as near the coasts. A North/South bi-directional Beverage might then be quite useful, especially if you are not that interested in working DX.
- Almost all of Europe (and a portion of N. Africa) is **Northeast**, NOT East!
- Australia, New Zealand, Mexico, Central America, and most of Oceania is **Southwest**, not West.
- Japan and Alaska is **Northwest**, and NOT West.
- Most of the Caribbean and South America is **Southeast**, not South.
- Africa —depending on the country you want— varies all the way from Northeast, through East, to Southeast.

For working stations in the USA, orienting your Beverage antennas NE-SW and SE-NW has the following advantages for reducing QRM:

- Pointing NE nulls out the southern coastal states such as Florida.
- Pointing SE nulls out the northern coastal states such as New England, New York, as well as eastern Canada.
- Pointing SW nulls out Oregon, Washington, western Canada, etc.
- Pointing NW nulls out California, Arizona, etc.

If you DO need to point N, E, S, or W, perhaps the best thing to do is erect a separate Beverage —perhaps a single-wire one— *in addition to* your NE-SW and SE-NW Beverages. An azimuthal projection map centered on your QTH will tell you where you need to point your Beverage antennas.

How to tension the two wires equally:



- Only three pulleys are required to tension both wires equally by pulling on a single rope.
- This arrangement gives a necessary 1:2 mechanical advantage, if one man is to tension this antenna sufficiently.

Q: What are the negatives of the 2 wire vs individual single ones?

A: The negatives? I think the positives outweigh any perceived "negatives"! The "negative" is all about the single wire design, because you're restricting yourself. With two wires instead of just one, you could switch between both directions, using the same supports! For 2-wire Beverages, only half the required amount of supports and real estate are required to cover both directions. Complexity (that could be argued against) and perhaps cost. And some types of open-wire line might not last as long as a single wire, depending on what you use. That's about it. The two-wire Beverage does not have a degraded pattern or F/B ratio.

A two-wire Beverage, like this one allows operation in either direction.

On mine, there's a relay, one or two termination resistors, an RF choke, and a capacitor at the feed end, besides the two transformers. Putting +12VDC on the coax switches one Beverage from SE to NW. Two Beverages cover 4 directions.

Don't you think that's simpler? No extra control cable needed. You can use the coax as a control cable if needed. That's what I do on one Beverage here to switch directions. Signal and DC on the coax, easily isolated with a couple of simple RF chokes and capacitors. You can see them in the photos of my Beverages. (Schematics above).

Originally Posted by KA0GKT
> A Beverage works best over poor ground, so I would think that running a return under the antenna may reduce the effectiveness of the antenna by at least a little.
Answer: You bet it will. There is a popular book about Beverages that suggests doing that, but just because something is in a book doesn't mean that it is technically sound.

From: Milt, N5IA <n5ia@zia-connection.com>
Date: Wednesday, June 23, 2010, 9:59 PM

"In *the most simple explanation* of the theory of operation of the Beverage antenna you must understand that the single wire above (or on) the ground is 1/2 of an unbalanced transmission line. The earth conductivity is the other "wire" in the transmission line.

When the earth 1/2 of the "transmission line" becomes very conductive, the whole array approaches being an actual 2-wire transmission line (perfectly balanced). When that happens there is near ZERO signal received.

The more unbalanced the line is, the more signal level is impressed on the wire which can be detected by proper impedance matching to a coaxial feedline going to your receiver. That is why the Beverage works well over poor earth."

> I recently built a two-wire switchable-direction Beverage based on the
> description in ON4UN's Low-Band DXing (4th edition).
> Currently, I am using two coax runs to the shack but will eventually use a single coax that is
> switched between the low impedance sides of the two transformers.
>
> I followed the schematic in ON4UN's book except for two grounds which I omitted:
>
> 1) Figure 7-98A on page 7-70 shows two grounds on the far end of the
> Beverage. One is the ground on winding n2 of the transformer, which I
> included in my Beverage. However, the schematic shows a second ground (to
> the left of T5n1), which is connected to one of the two beverage conductors.
> What is the purpose of this ground?



Fig 7-98—At A, open-wire two-direction Beverage antenna. This uses reflecting transformers to obtain both reflections and proper impedance matching (see text for details). At B, an autotransformer is used for the same purposes.

***This is a typo, and that ground should not be there*.**
The only ground at the right (far) end of the Beverage should be on the primary of the reflection transformer (T5a, n_2).

It appears that this drawing was originally Fig. 7-23 on p. 7-22 of the 3rd edition of the same book. When it was modified for the 4th edition, there was a ground that should have been removed. I'm looking at both drawings, and it it's easy to see how such a graphics editing error crept into the new edition. Nobody's perfect.

> 2) Figure 7-98A also shows a grounded connection between coax J2 and coax
> J1. What is the purpose of this ground? Since I am using separate windings
> on my transformer, I don't think it makes sense to connect these coax
> grounds to the ground rod for T1n_1.

I agree. On my Beverages, **the coax shields are only grounded at the station end; and neither do I connect the shields at the antenna as shown.**
The ground connection shown connecting the shields of J2 and J1 in Fig. 7-98 — if used at all— should NOT be connected to the same ground as the primary of T1n_1, in order to ensure common-mode isolation.

I have found, like others have, that it is often unnecessary to terminate the unused cable in the above design. But I do anyway.

Figure 7-98 above is from the CD-ROM that came with the 4th edition.
Copyright (c) 2004 ARRL

This is not to imply that ON4UN's book is not worth having. It is! It contains some GREAT information about Beverage and other receiving antennas.
Having said that, it should be pointed out that the Beverage transformer winding instructions using the 73 material binocular core in the 5th edition appear to be a departure from earlier editions (and proven designs by many others). Some of us take issue with the need for so many more turns of fine PTFE insulated wire for use with Beverage antennas.

I'm using a relay at the feed end of the Beverage that selects the transformer (either T1 or T4) and switches the terminating resistors across the secondaries of the transformers, rather than the primaries as is usually done. Don't think it matters.

Who can verify that used motor oil will keep my Beverage antennas from accumulating ice? I know I read it somewhere. I was ready to coat them using a paint roller, but the ice storm never came.

Read this important info about external receiving antenna overload at http://forums.qrz.com/showthread.php?t=266646&highlight=beverage

---

If you do a Google search for "beverage antenna", you will find a lot of information on them. (Some good, and some not so good.)

I also have an as-yet unsorted collection of Beverage antenna information at http://www.w0btu.com/files/beverage/

You would appreciate the 4th and 5th editions (they are both good to own) of *Low Band DXing* by ON4UN, John Devoldere, even if you're not interested in working DX.

- Beverage antenna EZNEC files
- http://n1eu.com/topband/BeverageTips.htm
- 160 Meters
- 160 Meter reflector *If you're interested in 160, a subscription to this list is a must.* Archives
- More links
- Buy Beverage matching transformers

This page was created because there was no single source for all the information necessary to build a good two-wire bi-directional Beverage receiving antenna, either in print or on the web.

It was initially compiled from different posts I have made on QRZ.com, eHam.net, the Topband mailing list, and direct email. We have since added much more; and we are still adding information, photos, and detailed schematics, with the goal of enhancing this practical, comprehensive how-to web page about Beverage receiving antennas. Thanks for visiting.

Comments, questions, and suggestions are always welcome. Contact us

LINKING: You are welcome (and encouraged) to add a link to this page from your site. However, kindly link to http://www.w0btu.com/Beverage_antennas.html, and not to the individual files referenced here. Thank you.

A special thanks to George D. Brown, W8YET (SK) and Tom Rauch, W8JI for instilling in me the enthusiasm for the Beverage antenna. Many years ago, Tom kindly explained to me what I needed to build my first Beverage. And I believe that using 73 material as well as the binocular core for Beverage antenna transformers was Tom's invention (among other things).

Home | Sound files comparing Beverages to main TX antenna | Buy matching transformers | Top of page




Rate this page
The DXZone
HAM RADIO INTERNET GUIDE
--- ▼ Rate it
(with 10 = top)

Copyright © 2011-2015 Comtech Research LLC. All Rights Reserved.

http://www.w0btu.com/Beverage_antennas.html - Last Edited March 27, 2015

Energy Projects

Electrodynamic Tether Photos

Deployment of the Tether Satellite



Boom Deploy



Initial Deploy



Satellite Deployed



Closeup of boom showing tether



Close up of end of boom

Tether Break



The tether deployed to one mile

Shortly after the breakreak



The tether coils as it moves away from the Shuttle





The base of the tether boom. The area looks more like a Tesla Laboratory than the space shuttle hanger bay.

After the Break

The following three images are those displayed for the public showing the white specks that appearall around the tether after it has broken free. NASA calls these "dust and debris" particles, though Mission control in the audio portion of the videos state that they see a "lot of stuff swimming around" and that the tether is wider than expected.

If you compare these images to the ones we captured from a hard to find high resolution copy of the video on this page you will see a remarkale difference. The video is a must see.

Video Clip
STS-75 'The Tether Incident' Feb 1996
Editors Note: This video has been removed several times by Youtube. Currently it is available again. If it does get removed again, email me and I can send you a copy as we have it on disk now. Contact me at webmaster
This one is from the hand held Infrared Camera and is not as clear as the other one was STS-75 Alternate Copy

Comments:

What is most interesting to note is that most of the video clips above are taken from this video, yet NASA does not show the video itself. The copy on Youtube is a transmission intercept copy. However the fact that the NASA info site DOES use those clips gives credibility to the video that it is indeed a NASA film - Zorgon

Tethered Satellite System (TSS-1R)
Source of Clips: NASA STS-75 Mission Pictures

Kennedy Space Center STS-75 Mission Fact Sheet

"Critters" from STS-75

The Report After the Fact

NASA/TP—2003-21228
Low Earth Orbit Spacecraft Charging Design Guidelines

Below are a few keynote excerpts from the PDF file. The entire 367 page document is available below for those with technically savy who want to read the entire paper...

Excerpt 1:
In the case of the TSS-1R tether, its 20 km length produced a maximum of about 3500 V potential between its most positive and negative ends, since it wasn?t oriented perfectly perpendicular to the velocity vector and the Earth?s magnetic field. A satellite at its upper end collected electrons, and an electron gun at the lower end emitted electrons to complete the circuit. When the electron gun was not in operation, a large resistance prevented the Shuttle from being biased thousands of volts negative of its surrounding plasma. However, there remained a large voltage between the tether lower end and the Shuttle orbiter. This enormous bias eventually led to a continuous arc on the tether (see The Continuous Arc, section 4.2.3.1 below), which broke, freeing the satellite and ending the experiment. During the arc, the satellite collected over 1 Amp of electron current to keep the arc going. Probe theory (Cohen et al, 19870010625 N) is usually used to calculate the total current collected by a wire with distributed potentials. However, before the break, TSS-1R demonstrated that a satellite at a high positive potential could collect an anomalously large electron current. See Zhang, et al (20000110580), Stone and Raitt (19990084046 and 20000025437), and Stone, et al (19980202347)

Excerpt 2:
Sustained arcs (continuous arcs) - These are the events that have been attributed with the destruction of on-orbit solar arrays. Generally, the process begins with a fast transient (a so-called trigger arc). Under some conditions, the transient develops into an arc that is fed directly by the entire array, effectively becoming a short-circuit. Such events invariably involve large quantities of energy and can be severely damaging to cells, interconnects or power traces.





Excerpt 3:

When the structure or array capacitance electrically connected to the arc site is sufficiently large, the initial transient arcs themselves can be large enough to produce significant damage. In Figure 9, we see an anodized aluminum plate that has undergone repeated arcing in the laboratory with the ISS structure capacitance attached. Its thermal properties have been completely destroyed, along with most of the insulating surface layer of aluminum oxide.

Excerpt 4:
The most famous sustained arc event of all led to the breakage of the TSS-1R electrodynamic tether, and the loss of the attached satellite. The image below shows the burned, frayed and broken tether end still attached to the Shuttle after the break. **Incidentally, the tether continued arcing long after it and its satellite were drifting free, until finally it went into night conditions where the electron density was insufficient to sustain the arc.** Noel Sargent (2002) has investigated whether the TSS-1R arc was seen to disrupt Shuttle communications. Although he has found no record of disturbed communications during the event, for most of the time the arc was shielded by metallic structures from the communications antennas, and when the tether broke, the arc was many meters from the receiving antennas. It remains to be seen whether sustained arcs produce radio noise severe enough to be a communications problem.

Comments:
This is official confirmation that the tether continued to produce plasma energy long after it broke free, accounting for the "fluorescent bulb" glowing effect viewed after. We believe this concentrated collection of plasma energy is what attracted the "swarm" of "critters" to a "feeding frenzy"

To get the full PDF file you can download [LEO_Charging_Guidelines_v1.3.1.zip]



Tether Optical Phenomena Experiment (TOP)

Using a hand-held camera system with image intensifiers and special filters, the TOP investigation will provide visual data that may allow scientists to answer a variety of questions concerning tether dynamics and optical effects generated by TSS-1R. In particular, this experiment will examine the high-voltage plasma sheath surrounding the satellite...

In one mode of operation, the current developed in the Tethered Satellite System is closed by using electron accelerators to return electrons to the plasma surrounding the orbiter. The interaction between these electron beams and the plasma is not well understood...

Associate Investigator: Stephen Mende, Lockheed Martin

SOURCE

The Report After the Fact

...



The most famous sustained arc event of all led to the breakage of the TSS-1R electrodynamic tether, and the loss of the attached satellite. Figure 8 shows the burned, frayed and broken tether end still attached to the Shuttle after the break. Incidentally, the tether continued arcing long after it and its satellite were drifting free, until finally it went into night conditions where the electron density was insufficient to sustain the arc.

.....



Figure 8 – The end of the remaining TSS-1R tether

...

It is thus possible that an astronaut, grounded to ISS by his tether or conductive tools, could undergo an arc at only –50 V. A sneak circuit analysis showed that such arcs could put 1 Amp of current through an astronaut's heart. Since 0.1 Amp is enough to cause heart stoppage, it is imperative that if the ISS plasma contactors are inoperable during astronaut EVAs, a method be used to prevent ISS astronaut workplaces from floating more than 50 V negative.

...

For many ISS surfaces, peak arc strengths of hundreds of Amps have been calculated. Arcs this strong will melt the arc site and spew molten metal through space. Plasma chamber tests of this kind of arcing are spectacular indeed! Arcs on one anodized surface have been seen to trigger arcs on nearby line-of-sight surfaces.

...

Finally, an arc on an electrodynamic tether may become continuous. The infamous arc on the TSS-1R tether that led to its break and the loss of the satellite was a continuous (sustained) arc with its power supplied by the tether.

...



Had TSS-1R used a tether of greater resistance, the threshold arc current could not have been maintained. For example, a total tether resistance of ten thousand ohms would have limited the arc current to less than 0.4 Amps, less than the sustained arc threshold. Alternatively, if the satellite electron collection capability had been limited to less than ½ Amp, the arc could not have been sustained. Of course, these measures would have severely restricted the power or propulsion that could be obtained by tether operation and could not be tolerated on an experiment that was not just a proof-of-concept. An arc detection circuit could have also been used to shut the tether down at the satellite end when very large currents were first detected. One should never assume that a high voltage power system will not arc.

...



Ionized gases can be emitted by plasma sources such as hollow cathode plasma contactors or from neutral gas sources at high positive potentials. Locally, the plasma density can be greater than the ambient plasma density and similar plasma interactions can occur with high voltage components. On ISS, the Plasma Contacting Units (PCUs), when operating, produce a local xenon plasma of much greater density than ambient. It has been estimated that the invisible plasma ball produced is some eight meters in radius before its density decreases below the ambient plasma density in LEO. Arcing and current collection from such a plasma could occur in much the same way as with an ambient plasma, implying that solar arrays and other active sites should be kept out of induced plasma plumes.

...

Electrodynamic Tethers ~ Menu
Critters ~ Critters 01 ~ Critters 02 ~ Critters 03

Copyright Notice

All pictures and photos on this page, unless otherwise noted, have been gathered from pubic domain sources or are available under GNU License. Further documentation is available on our Copyright Page and our Legal Department.

Article Quotes all have links to their appropriate source and are noted. All other text not so noted is available under the terms of the GNU Free Documentation License

All information on this page is used only for non profit educational purposes. All reasonable attempts have been made that no credits are missed, but with a work of this size omissions may occur. If you see anything of yours that has not been properly credited or wish to have removed please contact the Webmaster

Menu



Webpages © 2001-2006
Blue Knight Productions

STS 75 TETHER INCIDENT

-

Tether Deployed
Tether Satellite being deployed from the Shuttle Bay of STS-75

-
- 

213506108 DAY:056

Tether Activated

Tether Satellite begins to glow as it gathers electricity from the Ionosphere

..


213809089 DAY:056



Tether Breaks Free

**Tether Satellite cable fries the connection and breaks free... still producing energy.
The glow increases and the cable gets wider. (More on this later)**

-

Tether Broke Free

Tether Satellite worth 100 million has overloaded the circuits within minutes of being activated because the NASA Scientists under estimated the potential. The tether in just a few moments of operation produced 10 times the anticipated power and they forgot to install a circuit breaker.

-

NOTES:
Add "Critter" Portion
Add Video
Add FLV Viewer

TETHER BROKEN FREE AND DRIFTING AWAY

Tether Drifting Away

At this point the STS 75 Astronauts switched to Infrared camera. What you are seeing is the Tether at about 80 nautical miles away from the Shuttle. Notice that it has straightened out and has become much wider. This is commented on by Mission Control as they say its wider than expected.

It is also at this point that the plasma collected by the tether that is "still glowing like a fluorescent bulb" (according to a NASA report issued after the event (See Below)) attracts the "Critters" or UFO's as most people call them. To see more about the "Critters" VISIT HERE In the image include below you can see the Tether Satellite at the tip. By this time the Tether is almost as wide as the Satellite itself.

Going behind the tether you see one of the "Critters" It is CLEARLY behind the tether. This is what NASA calls "dust and debris" The purpose of this paper is to show the tether however, not the "Critters". If you want to know more about them either email us or check out the pages linked to above.

STS-75 - 'The Tether Incident'

Tether Swarmed by "Critters"

Matt (Matyas) had written me that he has found documents hinting at a Tether in operation near Jupiter. He is still following that up, but it seems the Cassini Spacecraft has found one or more in the vicinity of Saturn

Cassini Spacecraft Image

Is this the lost Tether Satellite? Or is there another one in operation near Saturn?


Tether Satellite

Tether Near Saturn

Judging by the scale of Saturn, it would seem this is NOT the lost Satellite, but a much larger one. The STS 75 Tether was 12 miles long... This one is huge

(Note Dates and Size are being calculated)

[Source: Original Image NASA Cassini/ Huygens W00028414.jpg]



Cassini Spacecraft Image
Tether Near Saturn

..

Cassini Spacecraft Image
Tether Near Saturn

Source: Original Image NASA Cassini/ Huygens W00026015.jpg

Cassini Spacecraft Image

Source: Original Image NASA Cassini/ Huygens N00008771.jpg

~ MENU ~

US006116544A

United States Patent [19]

Forward et al.

[11] **Patent Number: 6,116,544**

[45] **Date of Patent: Sep. 12, 2000**

[54] **ELECTRODYNAMIC TETHER AND METHOD OF USE**

[75] Inventors: **Robert L. Forward**, Houston, Tex.; **Robert P. Hoyt**, Seattle, Wash.

[73] Assignee: **Tethers Unlimited, Inc.**, Seattle, Wash.

[21] Appl. No.: **08/929,271**

[22] Filed: **Sep. 12, 1997**

[51] **Int. Cl.**^{7} **B64G 1/00**

[52] **U.S. Cl.** .... **244/158 R**; 244/166; 244/172

[58] **Field of Search** .... 244/158 R, 164, 244/166, 172

[56] **References Cited**

U.S. PATENT DOCUMENTS

4,097,010	6/1978	Colombo et al.	244/158 R
4,824,051	4/1989	Engelking	244/158 R
4,923,151	5/1990	Roberts	244/158 R

OTHER PUBLICATIONS

"Tethers Open New Space Options" by Ivan Bekey, *Astronautics & Aeronautics*, 1983.

Primary Examiner—J. Woodrow Eldred
Attorney, Agent, or Firm—Arthur M. Dula

[57] **ABSTRACT**

The present invention comprises an electrodynamic tether structure and a method of use. The structure of the tether taught by the present invention is a short, wide, interconnected multiwire (compared to the long, narrow single wires of the prior art) conductive tether whose area maximizes electrodynamic drag while simultaneously minimizing the Area-Time-Product swept by the tether during its operating life. The preferred tether length is two kilometers to five kilometers. The preferred tether mass is one percent to five percent of the spacecraft mass. The method of operation comprises orienting the tether structure at an angle to the local vertical to maximize electrodynamic drag on the host spacecraft and minimize tether instability. The angle of 35.26 degrees is preferred.

26 Claims, 12 Drawing Sheets




Hoytether
Survival Probability
1/e survival probability
Hoytether
1-week survival
probability > 99%
Single-line tether
survival probability
83%
Baseline
single-line
tether
SURVIVAL PROBABILITY %
100
80
60
40
20
0
Time (Years)
0
0.5
1
1.5
2
2.5
3
3.5
4

FIG. 1a


ELECTRODYNAMIC THRUST

FIG. 1b



Enrico Lorenzini, SAO, NASA ProSEDS Mission (July 1997),
NASA/MSFC Grant NAG8-1303

FIG. 1c



FIG. 2a


209
207
205
203
201
211
213

FIG. 2b


209
207
205
211
219
213
217
215
221

FIG. 2c


309
307
310
305
311
303
313
301
315

FIG. 3



Area-Time Product for Mean and Extremes of Exospheric Temperature

(m = 1000 kg, Cd = 2.0 ; 1% Tether, 1 km x 25 cm; power = 1077 watts)

(5% Tether, 1 km x 25 cm; power =5385 watts)

FIG. 4



Conventional Solid Rocket Motor System

Percent Increase in Orbital Mass vs. Altitude and I' (Isp = 288 sec)

FIG. 5


τ
τ = 35.26°

FIG. 6



FIG. 7


τ
τ

FIG.8



FIG. 9



FIG. 10


1100
1008
1002
1006
1004

FIG. 11


F_GB
T_GB
F_GB sinτ
m_B
L sinτ
L cosτ
L
F_GT
T_GT
F_GT sinτ
m_T
F_E cosτ
L/2 cosτ
τ
E
F_E
T_E
I
B
E cosτ
v
M

FORCES AND TORQUES ON AN UPWARD DEPLOYED CONDUCTING TETHER DUE TO THE MOTION OF THE HOST SPACECRAFT THROUGH THE MAGNETIC FIELD OF THE EARTH.

FIG. 12

ELECTRODYNAMIC TETHER AND METHOD OF USE

TECHNICAL FIELD

This invention relates generally to apparatus and methods useful for changing the state vector of a space object when the space object is moving relative to a magnetic field. More specifically, the present invention relates to an apparatus and method of using a conducting tether to produce an electrodynamic force to deorbit a satellite from its orbit around a celestial body, such as the Earth, which has an associated magnetic field.

RESERVATION OF RIGHTS

This application is subject to certain rights of the U.S. government as a result of contracts between the U.S. government and the inventors.

BACKGROUND ART

The present invention has its principal utility in outer space, primarily for deorbiting satellites at the end of their useful life to mitigate the harm and reduce the liability created by the proliferation of space debris. In order to obtain a better understanding of the present invention it is helpful to understand the prior art of space tethers, especially tether dynamics and tether electrodynamics. The present invention may be more readily understood through a review of the experimental prior art and a mathematical analysis of electrodynamic space tethers.

Prior Art Tethers:

A tether was originally a rope or chain used to fasten an animal so that it grazed only within certain limits. Tethers have been used for decades in space to attach astronauts to their spacecraft.

In 1974 Professor Guiseppe Colombo, holder of the Galileo chair of astronomy at the University of Padua in Italy, proposed using a long tether to support a satellite from an orbiting platform. U.S. Pat. No. 4,097,010, which issued to Professor Colombo and Mario Grossi on Jun. 27, 1978, teaches a satellite connected by means of a long tether to a powered spacecraft. Colombo actively pursued the design of a tethered satellite system.

Several NASA experiments, such as the two Small Expendable Deployer System (SEDS 1 & 2) experiments and the Plasma Motor Generator (PMG) experiment used tethers in space. SEDS used a nonconducting tether. The PMG used a 500-meter conducting tether. The Tethered Satellite System flights in 1992 and 1996 (TSS-1 & 1R) used a 20,000-meter conducting tether.

On the TSS-1 mission the tether deployed only 260 meters (853 feet) before the deployer failed. On the TSS-1R the tether was deployed 19,500 meters. In the SEDS-2 flight, a 0.8-mm diameter, 20,000-meter long braided single-line tether was deployed to study tether dynamics and lifetime. Orbital debris or a meteoroid severed this tether in less than four days.

In the TSS-1R flight, the conducting single-line tether was severed after five hours of deployment. This failure was caused by an electric arc produced by the 3,500 volts of electric potential generated by the conductive tether's movement through the Earth's magnetic field.

The Tether Physics and Survivability (TiPS) satellite consists of two end masses connected by a 4,000-meter long non-conducting tether. This satellite was deployed on Jun. 20, 1996 at an altitude of 1,022 kilometers (552 nautical miles). Its tether is an outer layer of Spectra™ 1000 braid over a core of acrylic yarn. The yarn will "puff" its outer braid to two millimeters to "give it a larger cross section to improve its resistance to debris and small micrometeoroids", according to the National Reconnaissance Office (NRO), which is a sponsor of the TiPS mission. As of Jun. 21, 1997 the TiPS tether had survived one year.

References:

1. Joseph A. Carroll, "SEDS Deployer Design and Flight Performance", paper WSEDSA-1 at the 4th International Conference on Tethers in Space, Washington, D.C., April 1995.
2. James E. McCoy, et. al. "Plasma Motor-Generator (PMG) Flight Experiment Results", pp.57–84, Proceedings of the 4th International conference on Tethers in Space, Washington, D.C., April 1995.
3. W. John Raitt, et. al. "The NASA.ASI-TSS-1 Mission, Summary of Results and Reflight Plans, pp. 107–118, Proceedings of the 4th International conference on Tethers in Space, Washington, D.C., April 1995.
4. Joseph C. Anselmo, "NRO Orbiting Spacecraft Studies Tether Survivability", Aviation Week, page 24, Jul. 1, 1996.

These experiments all used single line tethers.

The following reference is illustrative of the current state of the art in space tethers: Paul A. Penzo and Paul W. Ammann. Tethers in Space Handbook—Second Edition. NASA Office of Space Flight, NASA Headquarters, Washington, D.C. 20546. See also the hundreds of references in the 33 page bibliography at the end of the handbook.

The "Hoytether"™, an Improved, High-Reliability Tether:

In 1991, one of the present inventors, Robert Hoyt, invented a lightweight net-like structure that provides many redundant load-bearing paths. A number of primary load bearing lines running the length of the structure are connected periodically by diagonal secondary lines. The disclosed embodiment of this invention has the secondary lines firmly connected by knots to the primary lines. The secondary lines are connected only to the primary lines. At either end of the disclosed structure, a support ring enforces the cylindrical spacing between the primary lines. The secondary lines are designed with a small amount of slack. These secondary lines are only put under load if a primary line fails. This specific tether structure was disclosed to the public in 1992 (Forward, R. L., "Failsafe Multistrand Tether Structures for Space Propulsion", AIAA paper 92–3214, 28th Joint Propulsion Conference, Nashville, Tenn., 1992 (hereinafter "1992 Hoytether structure"). This structure was named a "Hoytether". The term "Hoytether" is used throughout the remainder of this specification for this type of tether structure.

The present invention uses an improved Hoytether, which was invented by the same inventors as the present invention. This improved Hoytether is the subject of a copending PCT application. The Hoytether is discussed briefly in this specification to aid understanding of the present invention.

The 1992 Hoytether design teaches that the normally slack secondary lines have half the cross-section (0.707 the diameter) of the primary lines. There are twice as many secondary lines as primary lines, thus the mass of the secondary lines is equal to the mass of the primary lines. In an undamaged Hoytether, the primary lines carry the entire load, while none of the secondary lines are under load.

While the survival probability of a single-line tether decreases exponentially with time, the Hoytether can maintain a high, i.e. greater than 99 percent, survival probability

for periods of months or years (forward and Hoyt, "Failsafe Multiline Hoythther Lifetimes", Paper AIAA 95–2890, 31st Joint Propulsion Conference, July 1995).

References:

1. Robert L. Forward, Failsafe Multistrand Tethers for Space Propulsion, Forward Unlimited, P.O. Box 2783, Malibu, Calif. 90265, July 1992, Final Report on NASA Contract NAS8-39318 SBIR 91-1 Phase I.
2. Robert L. Forward and Robert P. Hoyt, Failsafe Multistrand Tether SEDS Technology Demonstration, Final Report on NAS8-40545 with NASA/MSFC (Jun. 14, 1995).
3. Robert L. Forward and Robert P. Hoyt, "High Strength-to-Weight Tapered Hoytether for LEO to GEO Payload Transfer" Final Report on contract number NAS8-40690 with NASA/MSFC (Jul. 10, 1996).

The Hoytether is essentially a tri-axial net structure, with 'primary' lines running along the length of the tether and two sets of 'secondary' lines connecting these primaries diagonally. They can be made by hand and connected with knots as is taught by the 1992 Hoytether structure. Because knotted connections severely limit the strength of a structure, it is desirable to use a knotless fabrication technique to achieve interconnections that have strengths approaching the limits of the constituent material. As these tethers may be many kilometers long; fast and inexpensive mechanical methods are required for their practical fabrication.

Hoytethers may be made by mechanical braiding, i.e. three-dimensional braiding, such as 3-D rotation braiding using braiding machines such as those developed by the Herzog Company in Germany (August Herzog Maschinenfabrik GmbH & Co., Postfach 2260.26012, Oldenburg, Germany. The specialized loom developed by the Nichimo Company of Japan (Nichimo Company Ltd., 2-6-2 Ohtemachi, Chiyoda-Ku, Tokyo, Japan) is used to produce "Ultracross" knotless fishing nets in which the individual strands are braided as a 4-braid line, and the strands are interbraided where they cross. This produces netting that has slipless interconnections that are very strong, approaching the maximum capability of the fiber. Such a loom could, with some modifications, produce the present invention's structure. Only two such machines exist, one in Japan, the other in Washington State. Unfortunately neither can work with the small line diameters needed to practice the preferred embodiment of the present invention. See generally, Ko, F. K., "Braiding", in *Engineered Materials Handbook, Vol.* 1., *Composites*. ASM International, Metals Park, Ohio, 1957. Pp. 519–528.

The most common 3-dimensional braiding machines are 4-step braiders based upon the designs of Maistre (German Patent P230-16986, issued 1973) and Forentine (U.S. Pat. No. 4,312,261, issued 1982). Braiding is accomplished by using pneumatics or solenoids to push the parts of the braiding machine to the proper positions. This is a slow process and making a Hoytether kilometers long with these machines would be very time consuming and expensive. The composites division of Albany International (Albany International Research Company, 777 West Street, Mansfield, Mass.) also produces a 3-D braiding machine. This machine uses modular braiding components that arc assembled breadboard fashion on a large wall.

Although braiding is the preferred technique, alternate fabrication methods such as Raschel knitting and crocheting can be used successfully. Multikilometer long Hoyththers are presently being produced for the inventors by the vendors Culzean Fabrics and Flemings Textiles using an electronically controlled crochet machine produced by Comez in Italy.

Space Tether Systems:

The prior art teaches the use of tethers in space applications. U.S. Pat. No. 5,163,641, issued on Apr. 9, 1990 to Yasaka, teaches the use of a powered spacecraft connected by a tether to a satellite. This tether is disconnected to change the state vector of the satellite. The state of the art of energy and momentum transfer using space tethers is discussed in Ivan Beckey's article "Tethering, a new Technique for Payload Deployment", Aerospace America, March 1997, at pages 36–40. Beckey concludes, "Tethers can perform the same functions as propulsive upper stages of direct payload injection, but at lower weight and cost per pound." U.S. Pat. No. 4,923,151, issued Mar. 1, 1988 to Roberts, Wilknson and Webster, teaches a tether power generator for earth orbiting satellites. U.S. Pat. No. 4,580,747, issued Mar. 15, 1983 to Pearson, teaches use of a long tether extending downward into the atmosphere from a satellite. The state vector of the satellite is changed by forces acting on a lifting body connected to the end of the tether. U.S. Pat. No. 4,824,051, issued Jan. 12, 1987 to Engelking, teaches passing an electric current through a conductive tether attached to a satellite to provide propulsive force to alter the orbit of the satellite. U.S. Pat. No. 5,082,211, issued Jan. 21, 1992 to Werka, teaches use of a tether to deorbit space debris. U.S. Pat. No. 4,727,373, issued Mar. 31, 1986 to Hoover, teaches an orbiting stereo imaging radar system having two spacecraft in synchronous parallel orbits connected by a tether.

Tether Dynamics:

In order to understand the forces that cause a tethered satellite to move upward and away from an orbiting satellite, for example, it is first necessary to explain briefly how a satellite remains in orbit. An orbiting satellite is acted on by the force of gravity which pulls it toward Earth, and by a centrifugal force, which pushes it away from Earth. The centrifugal force" (actually inertia) results from the motion of the satellite around its circular orbit. This is the same force that one can experience by swinging a ball around on the end of a string. A satellite is maintained in its orbit when it travels at the natural speed for its altitude and, as a result, the centrifugal force is equal to the gravitational force.

At the typical orbital altitude of 250 kilometers for a low-Earth orbit satellite, for example, a speed of approximately 7.6-km per second is required to create sufficient centrifugal force to balance gravitational attraction on the satellite. If the altitude is changed, the two opposing forces will no longer be in balance unless the satellite also changes its speed. A higher orbital altitude requires a slightly lower speed so the satellite will take longer to complete an orbit. Because of this, if two free-flying satellites are in orbits at different altitudes, the lower satellite will circle the Earth in less time than the satellite in the higher orbit.

If two satellites, at different altitudes, are connected to each other by a tether, they are forced to travel around their orbits together—in the same period of time, which is longer than the natural period of the lower satellite but shorter than that of the upper satellite. The lower satellite will, therefore, slow down below the natural speed for its orbit and will tend to fall to a lower orbit because the centrifugal force will now be less than the gravitational attraction of the Earth. An upward force in the tether that makes up the difference between centrifugal and gravitational forces holds it in place, however.

Correspondingly, the upper satellite will be accelerated above its natural orbiting speed (increasing its centrifugal force above the gravitational attraction) and will tend to move to a higher orbit. It, too, is held in place by an additional force (downward) in the tether. In other words,

the net force downward on the lower satellite is balanced, through the tether, by the net force upward on the upper satellite. The effect of unbalanced forces on the two satellites is, therefore, to create tension in the tether. During the TSS-1 & 1R experiments, the inertia of the tethered satellite causes the satellite to rise above the orbiter as the tether is reeled out. Very close to the orbiter, there is little difference in the two orbits, and the tension force is insufficient to overcome friction in the deployer mechanism; therefore, until the satellite reaches a separation of approximately 1000-meters, the tension is augmented by small tether-aligned thrusters on the satellite. Beyond this point, the tension in the tether is the only force required.

By experimenting with a ball hung on a piece of elastic cord (a paddleball, for example) it is possible to simulate all the different types of oscillations that are possible on a space-based tether system. The elastic cord, representing the tether, may compress and stretch, causing the ball to bounce up and down (longitudinal oscillation). It also may move in a circular (skip-rope) motion or may develop wave-like motions (transverse oscillations). Even if the string itself remains straight, it is possible to get the ball swinging back and forth about its attachment point on the paddle like a child on a swing rope (pendulous motion).

Each type of motion occurs with a particular frequency, which depends on the length and tension of the tether. When the frequencies are different, the motions do not interact; however, at some tether lengths, the frequencies of two or more types of oscillation can become very close. At this point, energy can be transferred from one typc of motion to another, a phenomenon known as resonance. For instance, the transverse oscillations in the tether may cause the satellite to swing back and forth in pendulous motion.

Many different factors may cause oscillations; the movements of the satellite or Shuttle are but two of these. For an electrodynamic tether, the skip-rope and pendulous oscillations are of particular interest. If a current is passed through a tether, the current will interact with Earth's magnetic field, resulting in a force that may produce skip-rope and pendulous oscillations. Because it is necessary to maintain control of the satellite, much study has gone into identifying the different types of possible motions and the methods used to control them.

One way to control the magnitude of those motions that cause a change in tension or transverse motion at the end of the tether is to have an end mass connected to the Hoytether that maintains a controlled tension on the tether, working much like a spring-loaded 'dog leash'. This may be as simple as a coiled spring, or as complex as an active control system that measures the tension and transverse forces on the tether and adjusts the applied tension according to a local or remotely operating algorithm.

Electrodynamic Effects of Conductive Tethers:

Electric potential is generated across a conductive tether by its motion through the Earth's magnetic field. Electromagnetic forces acting on a conductive tether in orbit can make the tether system behave like an electric motor or generator, thereby exerting a useful force to alter the state vector of the tether and any mass attached to it.

Electrodynamic tether propulsion is unlike most other types of space propulsion in use or being developed for space application today—there is no hot gas expelled to provide thrust. Instead, the environment of near-Earth space is being utilized to propel a spacecraft or upper stage via electrodynamic interactions.

A charged particle moving in a magnetic field experiences a force that is perpendicular to its direction of motion and the direction of the field. When a current flows through a long, conducting tether the electrons flowing through the tether experience this force due to the fact that they are moving along the wire in the presence of Earth's magnetic field. This force is transferred to the tether and to whatever the tether is attached (like a spacecraft, satellite, space station or upper stage). It can be an orbit-raising thrust force or orbit-lowering drag force, depending upon the direction of current flow. Operation in one mode allows boost from LEO to higher orbit while reversing the current flow provides negative thrust for deboost. The principle is much the same for an electric motor; reverse its operation and it acts as a generator. The current passing through the tether is returned through the ionosphere to complete the current loop with collection and emission occurring on opposite ends of the tether.

The PMG experiment demonstrated that a conducting tether can be used as both a motor and a generator. The TSS experiments, especially TSS-1R showed that very large voltages (about 3500 volts) can be generated by a sufficiently long tether.

Uses of an electrodynamic tether as an orbit raising and lower propulsion system has many advantages over competing systems:

a. It is nearly propellantless. Most other systems expel hot gases and require extensive resupply. To emit current, the electrodynamic tether propulsion system may use plasma contactors developed as a part of the International Space Station Program. These contactors consume less than 20 kg of xenon gas per year with a 50% duty cycle. The electrodynamic tether propulsion system can also use field emitter arrays, which emit electrons without the use of any gas.

b. It can change both altitude and inclination. The Earth's magnetic field is non-uniform and can therefore provide both in- and out-of-plane forces for inclination changes as well as altitude changes. This is of particular interest to payloads requiring polar orbits in that they can be launched on a small launch vehicle into a lower inclination orbit and have it raised in space by the proper phasing of current through the tether.

A demonstration of the propulsive capabilities of electrodynamic tethers was recently approved for a flight test in 1999. The Propulsive SEDS or ProSEDS mission, will fly as a secondary payload on a Delta II launch vehicle and deploy a 5-km conducting tether using the existing SEDS deployer concept. The ProSEDS experiment will be followed by the Electrodynamic Tether Upper Stage (EDTUS) experiment that will demonstrated the use of electrodynamic forces to change both the altitude and inclination of the experimental spacecraft. FIGS. **1**B and **1**C show the calculated electrodynamic thrust at several inclinations and the reentry time sensitivity of the ProSEDS tether, respectively.

One application for long-life conducting electrodynamic tethers is as a "Terminator Tether™" for removing from orbit unwanted Earth orbiting spacecraft at the end of their useful lives. When the mission of the satellite is completed, the Terminator Tether™, weighing a small fraction of the mass of the satellite, would be deployed. The electrodynamic interaction of the conducting tether with the Earth's magnetic field will induce current flow in the tether conductor. The resulting energy loss from the heat generated by the current flowing through the ohmic resistance in the conducting tether will remove energy from the spacecraft, eventually causing it to deorbit, thus reducing the amount of orbital space debris that must be coped with in the future.

In the following analysis, it is shown that the amount of energy loss generated by an electrodynamic tether is essen-

tially independent of its length or area, and instead is primarily proportional to the tether mass and the physical properties of the conductor metal chosen. In the typical example calculated, a 1000-kg spacecraft can be deorbited from a 1000-km high Earth orbit by a 10-kg mass tether in a month, while a 1-kg tether can deorbit a 1000-kg spacecraft in less than a year.

To the knowledge of the inventors, Joseph P. Loftus of NASA/JSC first proposed the general concept of using an electrodynamic tether to deorbit spent satellites. (Joseph P. Loftus <JLoftus@ems.jsc.nasa.gov>, personal communication via email to Robert Forward, Monday Jun. 10, 1996 15:50:10.) In order to show that the Loftus deorbit concept was not obvious to those skilled in the art of electrodynamic tethers, Forward contacted the leading expert, Joseph Carroll, of Chula Vista, Calif., who built and participated in the flight test of the PMG. After being told of the Loftus concept in a telephone conversation, his reply in an Email message dated Aug. 5, 1996, was "such a system would be feasible . . . by it is still not obvious to me that it would be useful . . . "

Loftus was considering the use of electrodynamic drag from a conducting tether to achieve this goal of bringing the unwanted spacecraft down from its high orbit (where atmospheric drag is negligible) to a 200-km orbit, where atmospheric drag would rapidly finish off the task of removing the unwanted spacecraft from orbit. The tether Loftus was considering was a single-line, conducting tether, typically 1-mm in diameter, 1-km long, and, if made of aluminum, 2-kg in mass. He would include means at the ends of the tether to contact the ambient space plasma around the Earth to complete the current loop.

Unfortunately it is probable that space impactors would sever the 1-mm diameter, 1-km long single-line tether proposed by loftus within a 1/e lifetime of four months. This would produce orbital debris rather than removing it. The motivation for this work is the NASA Safety Standard NSS 1740.14 "(Guidelines and Assessment Procedures for Limiting Orbital Debris." The relevant portion of the Standard starts on page 6-3: General Policy Objective-Postmission Disposal of Space Structures. Item 6-1: "Disposal for final mission orbits passing through LEO: A spacecraft or upper stage with perigee altitude below 2000 km in its final orbit will be disposed of by one of three methods." The method of interest is the atmospheric reentry option, Option a: "Leave the structure in an orbit in which, using conservative projections for solar activity, atmospheric drag will limit the lifetime to no longer than 25 years after completion of mission. If drag enhancement devices are to be used to reduce the orbit lifetime, it should be demonstrated that such devices will significantly reduce the area-time product of the system or will not cause the spacecraft or large debris to fragment if a collision occurs while the system is decaying from orbit."

The NASA standard applies only to NASA spacecraft and even then only to completely new spacecraft designs. New versions of existing designs are to make a "best effort" to meet the standard, but will not be required to change their design to do so. The Department of Defense has adopted the NASA standard with the same provisos. An Interagency Group report has recommended that the NASA standard be taken as a starting point for a national standard. It is NASA's recommendation to the Interagency Group that the safety requirement be phased in only as spacefaring nations reach consensus internationally, which is being done through the International Debris Coordination Working Group whose members are Russia, China, Japan, ESA, UK, India, France, Italy, and the US.

Thus, although the NASA Safety Standard in its present form is not the "Law", the existence of the standard means that some time in the future a similar requirement may be imposed on all spacecraft. This could result in major growth in future space tether business, with a sale to every non-geostationary spacecraft being "mandated" by government safety regulations, somewhat as the sale of seat belts and airbags for every car are mandated.

In fact, three of the companies planning to set up "constellations" of low to medium orbit communications: Teledesic, Iridium and Odessey have committed their companies to abide by the spirit of NASA Safety Standard 1740.14 by using one means or another to deorbit their spacecraft before they reach end of life.

Problems with Prior Art Tethers:

All electrodynamic tether designs proposed by the prior art teach that the tether should be operated at a right angle to the magnetic field through which the tether is moving. This is a problem because the electrodynamic force acting on the tether causes the tether to align itself with the magnetic field force lines. To overcome this problem the prior art teaches the use of a large ballast mass attached to the end of the tether and/or use of a very long (tens to hundreds of kilometers) tether. The large ballast mass is expensive to take to orbit because it replaces useful payload. The long tether sweeps a larger Area-Time-Product during its useful life and thus is more likely to impact other space objects, either debris or another spacecraft.

Another problem common to all proposed prior art tethers is tether instability. If the tether produces a large electrodynamic drag force, which is desirable because a large drag force will cause the satellite to deorbit quickly, then the tether will be dynamically unstable. This instability can cause the tether to lose its effectiveness, act uncontrollably and even wrap around the satellite or otherwise malfunction. Experts skilled in the art of tether design have opined that this dynamic instability is inherently unavoidable in any electrodynamic tether system. The prior art solution, such as that presently being used in the ProSEDS experiment, has been to use a large ballast mass to increase the stabilizing gravity-gradient force and/or to limit the electrodynamic drag of the tether to less that the maximum that could be produced. In the ProSEDS experiment, the conducting electrodynamic tether is five kilometers long. To insure stability, it will be augmented by a 20–35 kilometer long non-conducting tether, which to further have stability will have a 40 kilogram ballast end mass.

Yet another problem of all proposed prior art electrodynamic tether systems is how to radiate away the energy produced by the tether's operation. A satellite moving at an orbital velocity of 18,000 miles per hour has a kinetic energy of over 10,000 calories per gram. To put this amount of energy in an understandable perspective, it may be noted that when nitroglycerine explodes it produces about 1,500 calories per gram. Prior art designs of electrodynamic drag tethers teach the use of the electrical energy generated by the tether to charge batteries or operate electronics, with the excess energy being converted into heat by a resistive load. This excess heat must be radiated to the space environment or it will melt the resistive load. Thus the resistive load, and/or its associated radiator structures, must be massive and replace useful payload.

DISCLOSURE OF THE INVENTION

The present invention comprises an electrodynamic tether structure and a method of use. The principal industrial utility of the present invention is to deorbit satellites in Earth orbit

at the end of their useful life. This embodiment of the present invention is sometimes referred to in this specification as a "Terminator Tether™" because it terminates the orbital lifetime of the host spacecraft. The structure of the tether taught by the present invention is a short, wide, interconnected-multiwire (compared to the long single wires of the prior art) conductive Hoytether whose area maximizes electrodynamic drag while simultaneously minimizing the Area-Time-Product swept by the tether during its operating life. The preferred tether length is two to five kilometers. The preferred tether mass is one to five percent (1%–5%) of the spacecraft mass. The method of operation comprises orienting the tether structure at a 35.26-degree trailing angle to the local vertical to maximize electrodynamic force on the tether while avoiding tether instability and allowing use of a small tether end mass.

The present invention also teaches that the satellite-tether system may be rotated around its common center of mass to centrifugally produce tension force in the tether structure to oppose forces causing tether instability. The angle of the conductive tether structure of the present invention with respect to the velocity vector of the host spacecraft may be controlled by the method of the present invention so it interacts with the encountered magnetic field to induce a maximum current flow in the tether. This produces maximum electrodynamic drag. All or a portion of this electric power may be stored and then controllably applied to the conductive tether to produce an induced electrodynamic force. This induced electrodynamic force may by used to enhance the drag force, to rotate the tether-satellite system and/or to provide satellite propulsion, i.e. to change the state vector of the satellite for any useful purpose, e.g. to avoid collision or to change the host spacecraft's orbit to an orbit more favorable for more rapid deorbiting.

The present invention also teaches a tether structure that also functions as a thermal radiator and/or plasma contactor. An embodiment of the present invention using conducting elements of the satellite, e.g. the solar arrays, as electrodynamic tether structures is also disclosed.

BRIEF DESCRIPTION OF THE DRAWINGS

The present invention may be better understood with reference to the following drawings:

FIG. **1***a* is a graph comparing the survival probability of a single line tether as taught by the prior art to the Hoytether used by the present invention.

FIG. **1***b* is a graph showing the level of electrodynamic thrust for a 10 kilometer, 10 kilowatt tether at various altitudes and inclinations.

FIG. **1***c* is a graph showing reentry time sensitivity of a five kilometer ProSEDS tether for several conditions of current flow in the electrodynamic tether.

FIGS. **2***a*, **2***b* and **2***c* show the Hoytether structure used by the preferred embodiment of the present invention.

FIG. **2***d* shows the Hoytape structure used by the preferred embodiment of the present invention.

FIG. **3** is a block electrical diagram of an electrodynamic tether system.

FIG. **4** is a graph showing a graph of the Area-Time product for three separate levels of exospheric temperature (for neutral drag calculations) and for two separate assumptions regarding tether mass and power drawn from the ambient plasma (for the Terminator Tether™ calculations).

FIG. **5** is the percent additional mass required in orbit to drop the perigee of a circular orbit at altitude, at, to a value of 200 kilometers using standard chemical rocket as taught by the prior art for deorbiting unwanted spacecraft.

FIG. **6** is a deorbit tether system shown operating with its electrodynamic tether at a trailing 35.26-degree angle to the encountered magnetic field, as is taught by the preferred embodiment of the present invention.

FIG. **7** shows an embodiment of the present invention in which the electrodynamic tether—satellite system is rotated about its center of mass to avoid tether instability.

FIG. **8** shows an embodiment of the present invention wherein the tether is powered to provide induced electrodynamic force.

FIG. **9** shows an embodiment of the present invention wherein the solar power system structure of the satellite is used as an electrodynamic tether.

FIG. **10** shows the use of a portion of the tether structure as a thermal radiator and plasma contactor.

FIG. **11** shows the braiding of an ohmic resistive load into the tether structure.

FIG. **12** is a force diagram showing the forces and torques on an upward deployed conducting tether due to the motion of the host spacecraft through the magnetic field of the Earth.

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENT

The principal industrial utility of the present invention is the deorbiting of satellites in Earth orbit, which necessarily can happen only in outer space. Until the present invention is reduced to actual practice by use with satellites in outer space and a body of practical experience is thereby obtained, the present invention can only be constructively reduced to practice, such as by this written specification and its associated drawings, diagrams and graphs and by reference to electric measurements made on conducting tethers in space by the PMG and TSS experiments. The inventors provide herein a detailed discussion of the theory of the present invention to help those skilled in the art of aerospace and tether engineering to understand the present invention and to make and use the best embodiment of the present invention known to the inventors at the time this specification was prepared, without undue experimentation.

Although the present invention is discussed in this specification in its preferred embodiment as a means of deorbiting satellites, it must be emphasized that discussion of this specific use in no way limits the broad scope of the present invention. The present invention can be used to change the direction and speed, i.e. the state vector, of any space object providing that object is in motion relative to any magnetic field. This magnetic field may be that of the Earth or of any other celestial body, for example Jupiter or the sun.

In this specification the material forming the structure of the electrodynamic tether is specified as being a conductor. For example, a metal, such as copper or aluminum wire could be used. Likewise, nonmetallic conductor, such as carbon nanotubes, or a conductive polymer could form the conductive structure of the tether.

FIG. **1***a* shows the survival curve for a Hoytether as used by the present invention vs. the survival curve of a prior art single line tether. The survival probability curve of the Hoytether as a function of time does not conform to the well known "1/e decay" shape of a single-line tether. The Hoytether can maintain a high level of survival probability, about 99 percent, until it nears its 'lifetime'. Its survival probability then drops rapidly to zero. A detailed mathemati-

cal analysis of the difference between Hoytether and single tether survival probabilities is given in Appendix E "Small Impactor Survival Probabilities of Hoytethers" and Appendix F "Large Orbital Debris Survival Probabilities of Hoytethers", both contained in the Final Report of NASA Contract NAS8-40545. The resulting cut probability with time for the Hoytether has a "bingo curve" shapes. In a bingo game, at least five numbers must be called before anyone can win, and usually many numbers have to be called before one of the bingo cards gets five in a row. In the Hoytether at least four cuts must happen at the same level before any failure occurs, and many cuts have to be made before any one of the levels has all four lines cut. The bingo curve has the property that the probability of survival stays very high for periods short compared to the lifetime. The probability of survival is greater than 99% for periods shorter than 10% of the lifetime. This is much better performance than the 1/e curve of a single line tether, where the probability of survival is only 90% at 10% of the 1/e lifetime.

FIG. **1***b* shows the calculated level of electrodynamic thrust, in Newtons, produced by a ten kilowatt, ten kilometer single conductor tether at altitudes between 200 and 1400 kilometers and at orbital inclinations between zero degrees and eighty degrees.

FIG. **1***c* is a graph showing the reentry time sensitivity calculated for a five kilometer ProSEDS single conductor tether at altitudes between 200 and 500 kilometers with current flow in the tether between on flow and one ampere.

FIGS. **1***b* and **1***c* are the work of Enrico Lorenzini of the Smithsonian Astrophysical Observatory from his study "Performance Evaluation of the Electrodynamic Tether Tug", NASA/MSFC Grant NAG8-1303 (Nov. 12, 1966). They show that experts in the field believe that the present invention will have industrial utility, as the current flow of one ampere in FIG. **1***c* decreases the deorbit time for the calculated case from more than 180 days to less than 20 days.

FIG. **2***a* is an isometric drawing showing the generally cylindrical structure of the Hoytether. In FIG. **2***a*, primary lines **201** and **203** are shown connected via secondary lines **211**. In FIG. **2***b*, which is a schematic illustration of the structure shown in FIG. **2***a*, primary lines **201**, **203**, **205**, **207** and **209** are connected, each to their respective adjacent primary lines, by a plurality of secondary lines **221**. These connections, for example as shown at interconnection **213**, are made by knotless, slipless interconnections, such as Soutache braiding of twisted connections.

FIG. **2***c* shows the Hoytether structure of FIG. **2***b* but with a severed primary line **205** at breakpoint **215**. The second level of secondary lines **217**, shown as bold lines in FIG. **2***c*, redistribute the load from the severed primary line **215** at point **217** back to line **215** at points **219** and **221**, above and below the break, respectively.

For the electrodynamic tether, a preferred embodiment would be to unroll the tubular Hoytetherr™ into a flat Hoytape™ as shown in FIG. **2***d*.

FIG. **3** generally shows the arrangement of functional elements of an electrodynamic tether system. Of course such a system must have a means of attachment to the spacecraft, a deployer, the tether itself, some form of space plasma cathode contactor, some form of space plasma anode contactor, a power dissipation system, and a communication and control system. Each of these individual elements are known in some form to those skilled in the art of aerospace engineering. Thus the present inventors do not feel it is necessary to describe them in detail in this specification.

In FIG. **3**, a space object **301**, i.e. a satellite in Earth orbit, or any other space object either natural or man made, is physically connected to the tether system. The tether system comprises a deployer **303** from which a conductive Hoytether **305** having a bare segment **307** extends upward from space object **301**. The positively biased anode end **309** of tether **305** collects electrons from the ionosphere as space object **301** moves in direction **310** across the Earth's magnetic field. These electrons flow through the conductive structure of the Hoytether to the power system interface **311**, where it supplies power to an associated load, not shown. The electrons then flow to the negatively biased cathode **313** where electrons are ejected into the space plasma **315**, thus completing the electric circuit.

In order to allow those skilled in the art to better appreciate the broad scope of the present invention, the inventors will now provide an example using specific tether and system values to compare the Terminator Tether™ to prior art means, ie a rocket, for deorbiting a satellite.

Terminator Tethers™:

When an Earth orbiting conducting space tether moves through the magnetic field of the Earth, an electric field is generated in the tether that is proportional to the velocity of the conductor, the magnetic field strength of the Earth, and the angle between the conducting tether and the magnetic field lines. From data obtained during the various electrodynamic experiments that have been conducted in space to date, such as the PMG, TSS-1, and TSS-1R experiments, a typical value of the generated emf per unit length of tether of E=100–200 Volts/kilometer can be assumed. The electric potential V developed at the ends of a tether of length L is then V=EL. For a tether of length L=10 km, the electric potential developed is V=1000 V. For calibration, the 20-km long TSS-1R tether, at the moment of failure, was developing a potential of 3500 volts, which is 175 volts/km.

The mass of a conducting tether of length L, cross-sectional area A, and densin, d is given by m=dLA. Typical values for the density are d=2700 kg per cubic meter for aluminum and 8900-kg per cubic meter for copper. For a typical aluminum tether of mass m=10 kg and length L=10 km, the cross-sectional area will be A=0.37 mm squared. If this were a solid-wire single-line tether, the diameter of the wire would be D=0.69 mm (21.5 gauge). If this were an 18 line tubular Hoytether, the diameter of the lines in the Hoytether would be D=0.16 mm (34 gauge).

The resistance of a conducting tether of length L and cross-sectional area A is given by R=rL/A, where r is the resistivity of the conductor in nano-ohm-meters (nΩ-m). Typical values for the resistivity are r=27.4nΩ-m for aluminum and 17.0 -nΩ-m for copper. For the m=10 kg aluminum tether of length L=10 km and cross-sectional area A=0.37 mm squared at 20 degrees C, the end-to-end resistance is 750 Ω. This value of resistance is the essentially the same whether the conductor area is concentrated into a single-line tether or divided up into many lines as in a multiline Hoytether.

The current I generated in the conducting tether by the electric potential V between the ends of the tether applied across the tether resistance R is I=V/R. For the 10 kg mass aluminum tether of length L=10 km, electric potential V=EL=1000 volts, and resistance R=750 Ω the current is I=V/R=1.33 Amps. Currents near these values were measured in the TSS-1R experiment at the time of failure. At the time of failure of the TSS-1R tether, none of the plasma contactors on the Space Shuttle or the Italian Satellite were operating. Thus the current was being collected by the conductive surface area of the Space Shuttle and the Italian

Satellite at the two ends of the tether. The Space Shuttle area is quite large, so it was not the limiting factor in current collection. The diameter of the Italian Satellite was 1.6 m, which would give it an effective plasma contact area of about 8 square meters. This shows that, if the plasma contact area of the ends of a conductive space tether can be make large enough, then ampere level currents can be extracted from the ambient space plasma without the use of space plasma contactors.

The power dissipated as ohmic heating in the tether is given by P=IE. For an aluminum tether of mass m=10 kg, resistivity r=27 nΩ-m, and density d=2700 kg/cubic meter, subjected to an electric field of E=100 V/m, the power dissipated in the ohmic losses of the conductor is P=IV=1330 Watts. For a 1 kg mass tether, it would be still a considerable 133 Watts of dissipation.

There will no doubt be additional dissipation of energy in plasma ohmic losses, plasma wave generation, and plasma ion acceleration, but the ohmic losses in the conducting tether alone are sufficient for the task of deorbiting an unwanted spacecraft massing 100 to 1000 times more than the tether.

The decay time of a metric ton spacecraft moving from a 1000 km altitude orbit to a 200 km altitude orbit with an energy difference of dU=3.3GJ, when its energy is being dissipated at a power of P=1330 W by an aluminum tether massing just 10 kg, or 1% the mass of the spacecraft, is about one month. This is a remarkably short time, and indicates that the concept of using a conductive tether to deorbit a spacecraft is indeed feasible. If the aluminum tether massed only 1 kg, or 1/1000th the mass of the spacecraft it was deorbiting, then the decay time would rise to 10 months, still a reasonable value.

In reality, of course, the actual decay time will be longer than this. If the electrodynamic drag force is very large, and becomes larger than the gravity gradient forces pulling on the ends of the tether (which force is proportional to the mass of the tether), then the tether will tend to align itself along the magnetic field lines instead of across them, and the drag force will decrease because of the small angle between the conductor length and the magnetic field lines. The tether will then settle into an angle determined by the balance between these two forces.

Is the Terminator Tether™ theoretically a better means than atmospheric drag or a rocket engine for deorbiting satellites at the end of their useful life?

In the formula for da/dt (change in altitude per change in time), using the assumptions of near-circular spiral trajectories, the Area-Time-Product (Z), the criteria by which NASA judges compliance with Safety Standard 1740.14, is given by:

$$Z = A\int dt = -\frac{m}{C_D}\int \frac{da}{\rho(a)\sqrt{\mu a}},$$

where ρ(a) is simply the density as a function of semi-major axis. Thus, for a static atmosphere, the problem of area-time product is reduced to quadrature. Note that the area-time product depends only on the density profile and the ratio of spacecraft mass to drag-coefficient and is linearly related to that ratio.

The basic altitude-dependence of the atmospheric density, represented here by ρ(a) can be expressed in a low-order power series of ln(density)=f(ln(altitude)), so that it will be possible to develop a representation of the log—log relationship between altitude and density. The three static levels of atmospheric density are modeled as 5th order polynomials in the natural log of the altitude and are representative of well known atmosphere models, for example, Jacchia, L. G., "Thermospheric Temperature, Density, and Composition: New Model," SAO Special Report 375, March 1977. 2. Anon., Marshall Space Flight Center, "Long-Range Statistical Solar Activity Estimation," Atmospheric Sciences Division, 1989.) The values of exospheric temperature are reasonable (about 2-sigma) high and low solar activity values of 1400 and 800 kelvins respectively. The mean value is taken to be 1100 kevins.

FIG. **4** shows a graph of the Area-Time product for three separate levels of exospheric temperature (for neutral drag calculations) and for two separate assumptions regarding tether mass and power drawn from the ambient plasma (for the Terminator Tether™ calculations). The density profiles for the three values of exospheric temperature represent the extremes and mean values to be expected during the next several decades. The exospheric temperature goes through a cycle of about an 11 year period with maximum about 1400 kelvins and minimum about 800 kelvins.

The tether calculations include an inherent assumption that the Terminator Tether™ transfers all the energy extracted from the ambient space plasma into drag that decreases the orbital energy of the spacecraft at a rate given by the power drawn by the tether. Thus, the change in energy for a spacecraft of mass m at an initial altitude h is given by the expression:

$$\Delta E = -m\left\{\frac{\mu}{2(R_e+h)} - \frac{\mu}{2(R_e+250)}\right\},$$

and the time required to effect this change in energy of the mass, m, is just

$$\Delta t = \Delta E/P,$$

where P is the power drawn by the tether from the ambient plasma charge.

The curves for 1% and 5% tethers do not include the effects of atmospheric drag because the electrodynamic drag is orders of magnitude greater than the neutral atmospheric drag. At altitudes greater than about 700 km, the electrodynamic drag is 200 to 3000 times greater than the neutral drag forces.

It is clear, from FIG. **4** that the Terminator Tether™ concept is far superior to neutral drag in removing spacecraft from orbit, no matter how much additional area is added to the passive spacecraft to increase the atmospheric drag. The analyst should note that FIG. **4** is proportional to mass; that is, the Area-Time-Product values should be multiplied by the mass of the spacecraft and divided by 1000 kg. This is true for the neutral drag and Terminator Tether™ curves alike. The power levels assumed for the 1% and 5% tethers are only 80% of their theoretical values. This is done to provide a 20% margin on the power available from the ambient plasma and electrodynamic gradient.

Conventional rocket mechanisms can remove spacecraft from orbit, but this mechanism is apparently not viable from mass considerations when these factors are compared with the capabilities of the Terminator Tether™. A satellite owner may decide to satisfy the NASA safety requirements by adding a small solid motor and the associated hardware, software, sensors and structure to make the package independent, to be used to deorbit the spacecraft in case the main spacecraft power, attitude, or propulsion system fails.

The requirements of such a rocket motor system are more stringent than those attributed to ordinary spacecraft. The

rocket motor deorbit system must operate when some or all other systems of the spacecraft have failed. These more stringent requirements are balanced by lesser requirements of performance. The backup system must simply deorbit the spacecraft; it does not have to perform all the other duties of the spacecraft. But the backup system must know when to fire under all kinds of anomalous situations, including tumbling, offset of center of mass (because of loss of parts due to collisions), and lack of knowledge of the orbital position.

FIG. **5** shows the percent additional mass required by the rocket motor system to drop the perigee of a circular orbit at some initial perigee altitude to a value of 200 km. The atmospheric drag at this 200 km perigee altitude will remove any spacecraft (in the range considered) from orbit in a few revolutions. The contours of constant stage propellant mass fraction, λ, range from low values of 0.5 through reasonable values of 0.65 to 0.7, up to the values associated with the best solid motors ($\lambda \nabla 0.93$) without adding any extra hardware to the emergency stage. An effective, independent stage to provide a retro deltaV of from 50 to 325 m/s will almost certainly have a λ of the order of 0.6 to 0.75. If the emergency stage is required to perform its own attitude determination, the stage propellant mass fraction may be as low as 0.55 or 0.50. Note that the additional mass, shown in FIG. **5**, must also be lofted to orbit in the first place, to provide the mass on orbit for the originally intended service. The stage propellant mass fraction, λ, is a key stage performance parameter that describes the ratio of the mass of propellant to the mass of the stage. That is $\lambda = m_p/(m_p + m_l)$, where m_p is the mass of the propellant and m_l is the mass of everything else in the stage (not including the payload or any stages above or below the stage being considered). Typical independent small rocket stages have values of λ from 0.60 to 0.75. The curves of stage propellant mass fraction are shown as straight lines (a minor approximation) and are included only from 0.5 to 0.95, the extremes of reasonable design practice.

These calculations that show, beyond any reasonable doubt, that the Terminator Tether™ concept is far superior to conventional mechanisms such as drag enhancement devices or small rocket deorbit propulsion systems. The superiority is measured in terms of Area-Time-Product, NASA's measure of the likelihood of collision with other spacecraft in the path of the descending spent member of a constellation. Tether calculations were made using conservative assumptions that the power extractable from the ambient plasma and electrodynamic gradient is only 80% of the theoretical power available to a perfect tether crossing the magnetic field lines at a right angle, i.e. normally.

The following analysis is presented by the inventors to help those skilled in the art to better understand the present invention when it is used as a Terminator Tether™ for removing from orbit unwanted non-geostationary Earth-orbiting spacecraft at the end their useful lives. The primary result of that analysis is that the electrical power P in the tether that is converted into heat by the resistance of the tether and radiated away into space will remove energy from the spacecraft, causing it to rapidly deorbit, thus reducing the amount of orbital space debris that must be coped with in outer space. Tether electric power P is given by:

$$P = (vB)^2 m/2rd$$

where m is the mass of the conducting tether, r and d are the resistivity and density of the conducting material, and v is the velocity of the spacecraft's motion through the Earth's magnetic field B. For a m=10 kg tether of aluminum with resistivity of r=27.4 nΩ-m and density d=2700 kg/m^3, moving at a velocity v=7037 m/s relative to the Earth's horizontal magnetic field B=26.5 μT, the power dissipated is P=2350 W! This energy loss in the form of heat must necessarily come out of the kinetic energy of the host spacecraft. For a typical example, a 1000 kg spacecraft in a 1000 km high orbit subjected to an energy loss of 2350 J/s from a 10 kg tether (1% the mass of the host spacecraft) will be deorbited in a few weeks.

Power levels of the magnitude estimated in the previous paragraph have been measured in a real orbital space experiment, the TSS-1R mission carried out on the Shuttle Orbiter in 1995. In that experiment, a large Italian spacecraft, 1.6 m in diameter, was deployed upward from the Shuttle Orbiter at the end of a conducting copper wire tether covered with electrical insulation. As the tether was slowly deployed upwards, a series of measurements were made of the open circuit voltage induced in the tether by its motion through the Earth's magnetic field. The voltage between the end of the tether and the Orbiter ground varied from zero volts at the start to 3500 V when the amount of tether deployed approached its maximum length of 20 km. Periodically, the end of the tether was connected either to one of two different electron guns, which supplied contact to the surrounding space plasma, or to the Orbiter ground. The bare surfaces of the Shuttle Orbiter proved to be a surprisingly good plasma contactor via a combination of ton collection and secondary electron emission. The current flow through the tether was deliberately limited by control circuits and the current capacity of the electron guns to about 0.5 amperes, but power levels of 1800 Watts were reached.

The tether was intended to have a fully deployed length of 20 km, but at a deployed length of 19.5 km, when about 3500 V was being induced at the end of the tether inside the Orbiter reel mechanism, a flaw in the insulation allowed an electrical spark to jump in an uncontrolled manner from the tether to the Orbiter ground. With no control circuits to keep the current level down to 0.5 amperes, the current flow jumped to 1.1 amperes, and the total power generated was P=3850 Watts Most of this energy went into the electrical arc, which burned through the tether, causing it to break and halting the experiment. This experiment showed that large areas of bare conducting material, such as that provided by the 8 square meter area of the Italian spacecraft at one end of the tether and the very large surface area of the Shuttle Orbiter spacecraft at the other end of the tether, can collect and emit amperes of current, while thousands of volts of potential can be generated by sufficiently long tethers moving at orbital speeds.

Thus, both theory and experimental data collected in the space environment indicate that significant amounts of electrodynamic drag force can be obtained from a low mass conducting tether attached to a host spacecraft, provided the ends of the conductor can exchange sufficient numbers of electrons with the surrounding space plasma.

Experimental data from the TSS-1R data also produced the amazing result that the efficiency of a bare metal surface in "contacting" the space plasma is many times better than the standard theory would predict. The 8 square meters of bare surface area of the Italian spacecraft were sufficient to collect the 1.1 A of electron current. This amount of area is easily replicated by a few hundred meters of bare wire, considering that the effective collection diameter around the wire is the Debye length, which is a few centimeters at the typical values for space plasma density and temperature.

Because of this result, that a bare wire can easily collect electrons, Les Johnson, Nobie Stone, Chris Rupp, and others

at NASA Marshall Space Flight Center have formed a team, which includes the present inventors, which is embarked on a new flight experiment. The experiment is scheduled for a piggy-back flight on a Delta II launch of an AF Global Positioning Satellite in early 2000. The goal of the experiment is to demonstrate that electrodynamic drag from a wire moving at orbital speeds through the Earth's magnetic field will create a large enough electrodynamic drag force to deorbit the Delta II second stage, whose mass is greater than 1000 kilograms, in a few weeks. This is essentially a demonstration of the Loftus electrodynamic drag deorbit concept and the first step in the development of a Terminator Tether™.

The ProSEDS (Propulsion Small Expendable-tether Deployer System) mission will use a 5 km long copper wire conductive tether massing 18 kg connected to a 20–35 km long nonconducting tether, which is in turn connected to a 25–40 kg ballast mass. The total of 25–40 km of tether length and the 25–40 kg ballast mass on the end will provide enough gravity gradient force to keep the tether aligned near the zenith, so that the direction of the current in the tether is at right angles to both the direction of the spacecraft motion in the nominal EW direction and the Earth's near-equatorial magnetic field in the nominal NS direction.

An important feature of the ProSEDS experiment is that it is designed to be completely self-powered. It uses a battery to initiate deployment and to power up the plasma contactor, but once current is flowing through the tether, some of the power is tapped off and used to recharge the battery. The battery, in turn, powers the current control electronics, the telemetry, system, and the plasma contactor. The ProSEDS mission will not be designed to allow ground control changes in operation, primarily because of the increase in complexity and cost associated with that option.

The present invention is the use of a small, low-mass deployer/controller package containing a large collecting area, short length, multiline space tether, such as a Hoytape mesh made of aluminum wire, as a "Terminator Tether™" for a constellation spacecraft. The Terminator Tether™ would be deployed when the host spacecraft is no longer working or no longer wanted. The electrodynamic drag from the Terminator Tether™ would rapidly remove the unwanted spacecraft from the constellation and a few weeks later complete the deorbit of the host spacecraft from space by burnup in the upper atmosphere of the Earth. For a Terminator Tether™ to be of maximum usefulness for constellation spacecraft, it would be desirable to minmize the mass and the length of the tether. A lower added mass means more mass for revenue producing transponders, while a shorter tether length means a lower collision cross-section Area-Time Product during deorbit.

FIG. **6** shows a spacecraft **600** having a state vector **602** that causes the spacecraft to move across magnetic field lines **601**. Spacecraft **600** has a conductive tether **603** attached to it by tether deployer and control system **605**. The outer end of tether **603** is attached to tether end mass **607**. Spacecraft **600** also has an attached electron emitter means **613**.

In FIG. **6**, spacecraft **600** has a velocity and direction defined by state vector **602**. As spacecraft **600** moves it causes conductive tether **603** to cut magnetic field lines **601**. As this happens the distal end of the conductive tether collects electrons, shown as arrows **611**, from the space plasma. Electrons **611** move through the conductive tether **603**, are passed through a resistive load, not shown, in control system **605**, and are emitted back into the space plasma as electrons **615** from electron emitter **613**. This produces an electrodynamic drag in the direction shown by arrow **609**.

As is discussed in detail in the electrodynamic drag analysis below, especially in that sections of the analysis titled "Optimization of Tether Angle", the maximum electrodynamic drag of the tether is achieved when the angle, shown as the Greek letter τ in FIG. **6**, is 35.26 degrees, trailing, to the direction of the magnetic field lines. This angle may be maintained by a feedback control circuit that maximizes the electrodynamic drag of the tether system, as is discussed in detail below. The tether structure **603** is a Hoytether having a length of about 2 to 5 kilometers. The use of the 35.26 degree angle to the magnetic field reduces the tether instability, allowing the use of a short tether which will have a small Area-Time-Product. This will minmize the possibility that the tether will impact another space object during its use.

In FIG. **7**, spacecraft **700** has a state vector **702** across magnetic field lines **704**. Conductive tether **706** is attached to spacecraft **700** by tether deployer and control system **708**. The distal end of tether **706** is attached to a tether end mass **710**. Spacecraft **700** has an electron emitter means **714**.

Functionally, electrons **712** flow from the space plasma into conductive tether **706**, are passed through a resistive load in control unit **708** and are emitted into the space plasma by electron emitter **714** as free electrons **716**. As is discussed in detail in the analysis below, this produces an electrodynamic drag on satellite **700**, which causes it to deorbit.

In FIG. **7**, spacecraft **700** is rotating with an angular velocity indicated by arrow **718**. This rotation causes a centrifugal force **720** to place tension on conductive tether **706**. This force **720** places tension on the tether **706** in a direction that counters tether instability. The Tether **706** may be at any angle to the magnetic field while the rotation of the tether-satellite system is producing this useful tension. FIG. **7** shows the angle to be 35.26 degrees, which is optimum, but any angle will work.

FIGS. **8***a* and **8***b* show a powered Terminator Tether™. In FIG. **8***a* the spacecraft **800** has a state vector **802** that causes it and its associated conductive tether **806** to move across magnetic field **804**. Tether **806** has an end mass **808** that is proximate a plasma contactor **810**. Just as was discussed in the embodiment of the present invention shown in FIG. **6** and FIG. **7**, an electric current moves through the circuit formed by the space plasma, the plasma contactor **810**, the conductive tether **806**, and the electron emitter **815**, thence back into the space plasma as electrons **816**. This creates an electrodynamic drag on the tether in the direction shown by arrow **818**.

In FIG. **8***b*, similar numbers indicate similar structures. In FIG. **8***b*, however, an electric power source, not shown, in spacecraft **800** provides electrons to conductive tether **806**. The electrons are emitted from the end **812** of the tether **806**. Electrons are collected to from the space plasma **814** by contactor **815**, thus completing the electric circuit. The result is an electrodynamic force on tether **806**, and therefore on spacecraft **800**, in the direction show by arrow **820**.

Spacecraft **800** in FIG. **8***b* may be rotated as is taught in the embodiment of the invention shown in FIG. **7**, above, to allow the control system to time the application of electric current to the tether **806** to cause force **820** to be exert force in any desired direction along the circle made by the rotating tether. This allows the state vector of the spacecraft to be modified to raise or lower the spacecraft's orbital altitude, or to otherwise usefully change its orbital elements.

FIG. **9** show an embodiment of the present invention wherein the conductive structure of a satellite is used as the tether. In FIG. **9**, a spacecraft **900** which has a state vector

901 and is moving across magnetic field **903**, has two attached solar panels, **902** and **904**. Solar panels **902** and **904** have conductive aluminum frames **908** and **906**, respectively. Frame **906** is electrically and mechanically connected to plasma contactor **912**. Frame **908** is electrically and mechanically connected to electron emitter **910**. As spacecraft **900** moves across magnetic field **903**, electrons from the space plasma **914** flow through contactor **912** and frame **906** to the body of spacecraft **900**, where the current flows through a resistive load, not shown, and then into frame **908** and electron emitter **910** to the space plasma **916**, thus completing the circuit. This creates an electrodynamic drag on spacecraft **900**. If the power output from solar panels **902** and **904** was directed to flow into the frames, **906** and **908**, then the electrodynamic interaction with the space plasma would cause a useful force to be impressed on spacecraft **900**, as was discussed in connection with FIG. **8** above. The spacecraft may be rotated and/or oriented to a desired angle with the magnetic field lines, as was also discussed above.

FIG. **10** shows an embodiment of the present invention wherein the plasma contactor and the resistive load are structurally part of the conductive tether. In FIG. **10** spacecraft **1000** has a state vector **1001** that causes it to pass through magnetic field **1003**. Spacecraft **1000** has a tether control and deployment system **1005** that is connected to a conductive tether **1007** having an end mass **1013**. A contactor portion **1015** of the conductive tether **1007** near end mass **1013** is adapted to contact the space plasma so as to receive or emit electrons. This may be the bare wire strands of a wide Hoytether, or it may be any other plasma contactor means that can be conveniently made electrically part of the Hoytether structure, such as points or metal fuzz. A second resistive portion **1009** of tether structure **1007** is adapted to be a resistive load. This may be done by making a portion of the tether structure from a material, such as nichrome steel wire, that has suitable electrical resistance The large surface area of the Hoytether provides an excellent radiator structure into the three degree Kelvin radiation sink of outer space.

FIG. **11** shows an alternative embodiment of the load resistance/radiator structure of the present invention. In FIG. **11**, a biline Hoytether **1002** is attached to its control and deployer system **1100** on a spacecraft, not shown, and to a tether end mass **1004**. A resistive load, **1006** is woven into the Hoytether structure, whereby this load **1006** and the section of the Hoytether **1002** into which it is woven act together as a thermal radiator allowing photons **1008** to radiate into the thermal sink of outer space.

The following detailed analysis of the present invention will help those skilled in the art to better understand and use the present invention.

Electrodynamic Drag Analysis:

The following is an optimization analysis of the electrodynamic drag produced by a conducting tether deployed from a host spacecraft that it is to deorbit. The force and torque diagram used in the analysis is shown in FIG. **12**, which shows the forces and torques on an upward deployed conducting tether due to the motion of the host spacecraft through the magnetic field of the Earth.

Physical Constants and Assumptions:

The analysis that follows will use the following physical constants and assumptions:

Newton's gravitational constant $G=6.67\times10^{-11}$ $m^3/kg\text{-}s^2$.

Mass of Earth $M_e=5.976\times10^{24}$ kg.

Radius of Earth near equator $R_e=6378$ km.

Assumed host spacecraft altitude h=622 km.

Assumed host spacecraft orbital radius a=7000 km.

Host spacecraft orbital velocity $w=\omega a=[GM_e/a\ ]^{1/2}=7546$ m/s.

Vertical gravity gradient at spacecraft $2\Gamma=2GM_e/a^3=2.32\times10^{-6}\ s^{-2}$.

Centrifugal gradient at spacecraft $\omega^2=GM_e/a^3=1.16\times10^{-6}\ s^{-2}$.

Combined gradient at spacecraft $3\Gamma=3GM_e/a^3=3\omega^2=3.49\times10^{-6}\ s^{-2}$.

Magnetic field of Earth (tilted dipole approximation):

Magnitude $B_o=35\ \mu T=0.35$ gauss.

Angle between magnetic pole and spin pole 11.5°.

Field components at spacecraft with altitude a and angle β between radius vector of spacecraft and magnetic equatorial plane.

Horizontal $B_H=B_o(R_e/a)^3\cos\beta=26.5\ \mu T\cos\beta$.

Vertical $B_V=2B_o(R_e/a)^3\sin\beta=52.9\ \mu T\sin\beta$.

Electrodynamic Tether Constants and Assumptions:

The electrodynamic tether is assumed to be made of a conducting metal, and have a length L, density d, resistivity r, and cross-sectional area A that is constant along the length of the tether. If the tether is a single round wire of diameter D, then the cross-sectional area is $A=\pi D^2/4$. Because of the micrometeorite and space debris hazard, however, it is likely the tether will be made up of redundantly interconnected multiple lines whose individual cross-sectional areas add up to A. Given these assumptions, the tether mass is then $m_T=dLA$, while the end-to-end tether resistance is $R_T=rL/A=rdL^2/m_T$.

Specific Conductivity Parameter:

The choice of the metal conductor to be used in a space tether is determined by a combination of low resistivity (high conductivity) and low density, with cost, strength, and melting point as secondary considerations for certain applications. Copper has a resistivity r=17.0 nΩ-m, a density d=8933 kg/m, and a "specific conductivity" of 1/rd=6,585 m^2/Ω-kg. Aluminum has a resistivity r=27.4 nΩ-m, which is significantly greater than that of copper, but it has a much lower density of d=2700 kg/m^3. As a result, aluminum's "specific conductivity" of 1/rd=13,500 m^2/Ω-kg is twice the conductivity per unit mass of copper. Silver, because of its higher density and higher cost, is not competitive as an electrodynamic space tether even though its resistivity of 16.1 nΩ-m is slightly better than that of copper. An alternate candidate material would be beryllium, with a resistivity r=32.5 nΩ-m, density d=1850 kg/m^3, and a "specific conductivity" of 1/rd=16,630 m^2/Ω-kg, slightly better than that of the much cheaper aluminum. Beryllium also has a higher melting point at 1551 K than aluminum at 933 K, so some of its alloys may be a preferred material for some electrodynamic applications despite its higher materials cost. Unfortunately, despite decades of metallurgical research by the nuclear power industry, highly ductile alloys of beryllium have not been found, so it is difficult to pull beryllium into wire. As a result, because of its high specific conductivity, low cost, and ready availability in ductile wire form, it will be assumed for this analysis that the electrodynamic tether will be made of aluminum wire.

Typical Resistance Values:

To be economically competitive, the mass of the tether needs to be a small fraction of the mass of the host spacecraft it is required to deorbit. Since a typical constellation spacecraft has a mass of about 1000 kg, a typical Terminator Tether™ with a mass that is 2% of the host spacecraft mass would consist of a deployer/controller package with a mass $m_D=10$ kg, containing an aluminum tether with a mass $m_T=10$ kg with a volume of $LA=m_T/d=3.70\times10^{-3}\ m^3$. If this 10 kg of aluminum were formed into a tether with a length

of $L=2$ km and a cross-sectional area of $A=1.85$ mm^2, then the end-to-end resistance of the tether would be $R=rL/A=rdL^2/m_T=29.6\ \Omega$ A longer tether would have a proportionately smaller cross-sectional area and a higher resistance; for example, a 5 km long tether with the same mass would have a resistance of 185 Ω.

Orbit Inclination Assumption:

In order to make the remainder of the analysis mathematically tractable, it will be assumed that the orbit of the host spacecraft is circular and above the magnetic equator, so that the angle between the radius vector to the spacecraft and the magnetic equatorial plane is $\beta=0$ degrees. In this orbit, the velocity v of the spacecraft with respect to the magnetic field is the orbital velocity w less the rotational velocity of the magnetic field at the orbital radius a due to the once per day rotation of the Earth, or:

$$v=W-2\pi a/1\text{day}=(7546-509)\text{m/s}=7037\text{m/s}$$

This equation also shows why electrodynamic drag will not be useful for removing geostationary spacecraft from orbit. At the geostationary orbital radius of a=42,200 km, the relative velocity of the spacecraft and the rotating magnetic field of the Earth is zero.

With this assumption of an orbit above the magnetic equator, the vertical component of the Earth's magnetic field is zero and the horizontal component of the Earth's magnetic field is at right angles to both the local vertical and the direction of motion of the spacecraft. The total magnetic field seen by the host spacecraft and its Terminator Tether™ is then orthogonally horizontal and has the magnitude:

$$B=B_H=B_o[R_e/a]^3\cos\beta=26.5\mu\text{T}.$$

Where for simplicity the subscript H will be dropped for the remainder of this analysis.

This orbit, with its inclination of 11.5° with respect to the spin equator, will not stay in the plane of the magnetic equator, but will vary ±11.5° above and below it as the Earth rotates, causing a variation in magnetic field strength of ±0.5 μT, as well as a slight variation in angle. This 2% variation is negligible in terms of the other uncertainties in this analysis. It is not until the orbital inclination of the host spacecraft orbit reaches 60°, where $\cos 60°=0.5$, that there is a significant drop in the expected magnitude of the electrodynamic drag forces calculated in this analysis.

Electromagnetic Drag Effects in Polar Orbit:

In many medium Earth orbit communication satellite constellations, there are a significant number of spacecraft at high inclinations and in nearly polar orbits. The high inclination spacecraft, with inclinations between 60° and 78.5°, will all have orbits that stay between the magnetic poles. Although the amount of electrodynamic drag will be significantly less than that experienced by spacecraft with orbits at lower inclinations, the direction of the induced electric fields in the tether will always be in the proper direction. If the tether is vertically upward, the outer tip of the tether will be positively charged and the bare wire in the tether will pull electrons out of the surrounding space plasma, while the electron emitter at the host spacecraft end will eject the electrons back into the space plasma to complete the circuit.

For spacecraft in near polar orbits with inclinations between 78.5° and 90°, however, there will be much more drastic variations. First of all, for a spacecraft in a 90° orbit that happens to pass directly over the magnetic poles, there is no horizontal component of the magnetic field when it is passing over one of the magnetic poles, so no voltage is generated in the tether during that part of the orbit, while the horizontal component of the magnetic field near the magnetic equator, while strong in magnitude, is along the spacecraft velocity vector, so no voltage is generated in the tether in that part of the orbit either. As a result, there will be negligible electrodynamic drag experienced by the host spacecraft during that particular orbit. The Earth is rotating, however, and the magnetic pole is rotating with it. A few orbits later, the host spacecraft will be passing over the Earth's spin pole at a point where the horizontal component of the magnetic field is exactly at right angles to the direction of motion of the spacecraft, so the full voltage is generated in the tether. When passing over the spin pole, the spacecraft radius vector is at an angle of 11.5° from the magnetic pole and at an angle $\beta=78.5°$ away from the magnetic equatorial plane. With these assumptions, the magnitude of the horizontal component of the magnetic field at the Earth's spin pole is a respectable:

$$B=B_o[R_e/a]^3\cos 78.5°=5.28\mu\text{T}$$

or 20% of the maximum value experiences by spacecraft orbiting above the magnetic equator. This value will drop slightly as the orbit continues, then build back up as the spacecraft passes over the opposite pole. As the Earth continues to rotate, bringing the magnetic pole again under the orbit, and the interaction of the tether with the horizontal component of the magnetic field again drops to zero. The average coupling of a tether to the Earth's magnetic field over all polar trajectories has been calculated to be 12.3 percent.

A problem experienced only by spacecraft with orbit inclinations greater than 78.5°:

The spacecraft will no longer be traveling from west to east with respect to the magnetic field axis, but will have a retrograde motion as it moves through the magnetic field. As a result, the voltage generated by the motion of the tether through the Earth's magnetic field will switch direction. The outer tip will be negatively charged and will attempt to collect ions, which is a much less efficient process than collecting electrons.

There are a number of solutions to this problem. The first is to increase the mass and length of the tether supplied to a spacecraft assigned to a polar orbit, so that higher voltages, currents, and drag are generated during the limited times the spacecraft is passing over the poles in the right direction. The second is to supply a tether with plasma contactors at both ends that can emit electrons from either end, allowing the current to flow either way, depending upon which direction the spacecraft is passing around the magnetic pole. The third is to utilize the first number of passes to torque the orbit of the spacecraft until the orbit inclination has been shifted below 60°, then turn on the electrodynamic drag full time to deorbit the spacecraft from this more favorable orbit inclination. This orbit torqueing maneuver is accomplished by activating the electrodynamic drag mechanism only when the magnetic field orientation is such that a strong out-of-plane component of force is created. This orbit torqueing maneuver can be augmented by switching to a propulsion mode, where power saved in the batteries during the drag force mode is pumped back into the tether when the magnetic field is in the opposite direction, applying electrodynamic propulsion to torque the orbit even further. With the tether at a large and stable trailing orientation, the coupling to the magnetic field can be significant to a vertical tether.

In summary, spacecraft in near-polar orbits might take longer to bring down, and might have to utilize specially designed Terminator Tethers™ that might cost and mass

more than the simpler Terminator Tethers™ usable in lower inclination orbits, but a Terminator Tether™ can still remove a spacecraft from a polar orbit when desired.

The inventors now present a detailed analysis and optimization of a typical Terminator Tether™ attached to a typical host spacecraft in a typical low inclination orbit.

Electromotive Generation of Voltage and Current in the Tether:

When an object is moved at a velocity v through a magnetic field B, an electric field is generated in the frame of reference of the moving object given by:

$$E=v\times B=vB$$

where the magnetic field B of the Earth, being mostly tangent to the Earth's surface in the north-south direction, is at right angles to the velocity vector v of the spacecraft, assumed to be orbiting in a generally west-east direction. The direction of the electric field E will be at right angles to both v and B, or along the local vertical. It should be noted that this electric field exists in the moving frame of reference because a moving magnetic field creates an electric field. No object actually has to be there, but if it is, then the relative motion of the magnetic field of the Earth will not only apply magnetic forces to whatever material the object is made out of, but electric forces too.

Note also that the velocity used in this equation is the relative velocity between the object and the magnetic field. Because the Earth's magnetic field rotates with the Earth, the motion of the magnetic field must be subtracted from the orbital velocity of the object to obtain the relative velocity.

Voltage generation in a Conducting Tether:

If the moving object is a long conducting wire of length L, the electric field E, generated in the wire produces a voltage V between the opposite ends of the wire given by:

$$V=E\bullet L=EL\cos\tau=vBL\cos\tau$$

where τ is the angle between the length vector L of the tether and the electric field vector E, assumed to be in the vertical direction at right angles to the velocity vector v in the plane of FIG. **12** and the magnetic field vector B out of the plane of FIG. **12**. A typical value for the voltage level built up in a vertically oriented tether with length L=5 km and $\tau=0$, moving at a velocity of v=7037 m/s through the Earth's horizontal magnetic field of strength 26.5 μT, is 932 V, or 0.186 V/m. Spacecraft in higher inclination orbits would experience somewhat smaller electric fields. For calibration, the voltage measured between the ends of the 19.5 km long TSS-1R tether was 3500 V, or 0.175 V/m.

Contacting the Space Plasma:

Although a voltage will build up between the ends of the conducting tether, no current will flow unless the circuit is completed. The circuit cannot be completed with another wire, for it too will have a similar voltage generated in it by the moving magnetic field. Fortunately, empty space is not empty, and in near-Earth regions not too distant from the Earth's atmosphere there exists highly electrically conductive space plasma, kept partially ionized by radiation from the Sun. The electron and ion density varies from the dark to light side, with altitude, with season, with sunspot cycle, with contamination level, etc. but it typically varies from 10^{11} to 10^{13} electrons/cc.

Fortunately, it has been found that if a bare conductive surface such as the spherical Italian spacecraft in the TSS-1R experiment, or the long bare wire to be used in the ProSEDS experiment, or a multiline conducting wire Hoytape mesh, is charged to a few hundred volts, the bare conductor will readily pull electrons out of the space plasma. So all that is needed to complete a connection to the space plasma at the positively charged (upper) end of the tether is a sufficient large area of uninsulated conductor.

It is more difficult to eject electrons from a wire or to collect positive ions from the space plasma. Although it is conceivable that a very large area at the other end of the tether could collect enough ions to complete the circuit as was demonstrated during the TSS-1R mission when the Shuttle orbiter was found to be an adequate plasma contactor for over an amp of current, the present method chosen is to use an electron emitter of some sort, either a hot cathode, a plasma cathode or contactor, a field-emission device, or something similar. Once provisions have been made at both ends of the tether to allow the flow of electrons out of one end of the tether and into the other end, and the altitude of the host spacecraft is not too high, then there will be sufficient conductivity in the space plasma surrounding the host spacecraft to allow current to flow through the tether.

Current Flow In The Tether:

The amount of current I flowing through the tether depends upon the total resistance R in the circuit. This resistance will consist of three components, the effective resistance of the plasma, the resistance of the tether, calculated earlier as $R_T=rL/A=rdL^2/m_T$, and a control resistor R_C, which will be varied as needed to optimize the Terminator Tether™ performance. There will also need to be a parasitic load on the current in the form of a charging device to charge some batteries. The batteries in turn will be used to power the control and communication circuits, and drive the electron emitting devices at the negative end of the tether. A well-designed Terminator Tether™ will thus be completely self-powered, except for an initial charge in the batteries to provide electrical power for the deployment and startup procedure. For simplicity of analysis it will be assumed that this battery charging load, which absorbs power like a resistor, but which stores it and uses it later instead of dissipating it immediately as heat, is included in the control resistor R_c. Normally, this load would act as a "base resistance" below which the control resistor could not be lowered, but since the charging circuit can be turned off when desired, and operations continued without interruption using the power stored in the batteries, it will be assumed that the control resistor can be taken to near zero value in those circumstances where the space plasma conductivity is low, or the magnetic field is in the wrong orientation and the voltage being generated in the tether is not large. Under these circumstances, lowering the control resistor to near zero allows a much higher current to flow for a given generated voltage, thus increasing the power being dissipated in the tether and maintaining a high level of electrodynamic drag on the host spacecraft.

A properly designed Terminator Tether™ will have plenty of bare metal area for electron collection at the positive end, while the electron emitters at the other end are efficient in terms of emitting large electron currents at low voltages and therefore low powers, while at the same time the mass, length, and area of the conducting tether have been made such that the resistance of the tether is moderately high. Under these conditions, the effective resistance of the space plasma will be much less than the design resistance of the tether. To make the mathematics more tractable it will be assumed that the plasma resistance is can be neglected and that the voltage available to drive the tether is the full voltage generated by the moving magnetic field. Although voltage will be needed to power the electron emitter, what-

ever its form, it will be assumed that the required voltage and power will be supplied by the batteries. The batteries in turn will be powered by the battery charging circuit, whose effective resistance is included in the control resistor (except for those short periods when the plasma or magnetic field interactions are weak).

Given all these assumptions concerning the total resistance in the circuit, the current I flowing through the tether is then given by:

$$I=V/R=vBL\cos\tau/(R_C+rdL^2/m_T)$$

A typical current level can be estimated by assuming that the control resistance R_C should be about the same size as the tether resistance R_T, which for an aluminum tether with resistivity r=27.4 nΩ-m, density d=2700 kg/m^3, length L=5 km, and mass m_T=10 kg, is R_T=185 Ω, giving a total resistance, including the control resistance R_C, of R=370 Ω. Thus the current flowing though a tether of length L=5 km, generating a voltage of V=932 V, would be I=V/R=2.52 A.

Power Dissipation Analysis:

The induced current I flowing through the tether resistance R_T will generate heat in the wire, which will be radiated into space and lost. That radiated energy must come from somewhere. There is also power taken out of the current flow by the battery charging circuit and ultimately dissipated. In order to conform to energy conservation laws, this power and energy must come from a decrease in the total kinetic and potential energy of the host spacecraft, causing it to deorbit. Set forth below is a detailed, optimized force analysis which will calculate the drag force on the host spacecraft. In this section, by using some simplifying assumptions, it is possible to produce a general argument based on energy conservation laws, which will illustrate the broad scope of the present invention.

For this energy conservation analysis it will be assumed that the plasma resistance is small compared with the tether resistance, and that the control resistance is equal to the tether resistance:

$$R_C=R_T=rL/A=rdL^2/m_T$$

Assume that the ballast mass at the end of the tether is a large piece of the defunct host spacecraft, such as a solar panel, antenna, or battery pack, so that the gradient force is large and the tether is always oriented along the vertical so that the angle τ=0°. Also assume the spacecraft is in an orbit above the magnetic equator and thus is moving at right angles to the Earth's magnetic field, so that the angle between the orbital velocity vector and the magnetic field vector is 90°, and the electric field vector is in the vertical direction, aligned perfectly with the tether length vector. Under these ideal conditions, the voltage between the ends of the tether is given by:

$$V=E\bullet L=(v\times B)\bullet L=vBL$$

The current in the tether is then just:

$$I=V/(R_C+R_T)=vBm_T/2rdL$$

The power dissipated as ohmic heating in the tether is then given by:

$$P=IV=(vB)^2m_T/2rd$$

This equation shows the interesting result that the power dissipated does not depend upon the length or the area of the tether (within reason), but only the mass of the tether m_T, the resistivity r and density d of the tether material, and the velocity v of the conducting tether through the Earth's magnetic field B.

For a typical aluminum tether of mass m_T=10 kg, the power dissipated is an impressive P=2350 W. Even if only a small fraction of this power is dissipated in a real system, the kinetic energy of the host spacecraft would suffer a significant energy loss with time.

Orbital Energy Extraction Analysis:

The total energy U of a spacecraft of mass M in orbit around the Earth consists of two components, its positive orbital kinetic energy and its negative gravitational potential energy. If a circular orbit of altitude h and radius $a=R_e+h$ is assumed, then the total energy of the spacecraft moving at a velocity $w=(GM_e/a)^{1/2}$ is:

$$U=+Mw^2/2-GMM_e/a=-GMM_e/2a$$

The system will be dissipating energy in the tether to decrease the energy U of the unwanted spacecraft from its relatively low negative value in a high Earth orbit to a greater negative value in a lower Earth orbit. To give a specific example, an unwanted spacecraft with a mass of M=1000 kg (a metric ton) in an orbit with an altitude of h=1000 km and a high orbital radius of $a(H)=R_e+h=7371$ km, then its (negative) total energy is:

$$U(H)=-GMM_e/2a(H)=-27.1\text{ GJ or }-27.1\text{ MJ/kg}$$

It is desired to lower the spacecraft to an orbit with an altitude just outside the atmosphere of h=200 km or a lower orbital radius of $a(L)=R_e+h=6571$ km, where atmospheric drag will finish the job. The total (negative) energy of a metric ton spacecraft at 200 km altitude is:

$$U(L)=-GMM_e/2a(L)=-30.4\text{ GJ}$$

Thus, the amount of energy needed to be dissipated in order to move the 1000 kg spacecraft from a 1000 km orbit with a total energy U(H)=−27.1 GJ down to a 200 km orbit with energy U(L)=−30.4 CJ is:

$$dU=U(H)-U(L)=3.3\text{ GJ.}$$

The decay time T of a metric ton spacecraft moving from a 1000 km altitude orbit to a 200 km altitude orbit with an energy difference of dU=3.3 GJ, when its energy is being dissipated at a power of P=2350 W by a typical aluminum tether massing just 10 kg or 1% the mass of the spacecraft, is found to be T=dU/P=16 days.

The actual decay time will be longer than this. If the electrodynamic drag force is very large, and becomes larger than the gravity gradient forces pulling on the ends of the tether, then the tether will tend to align itself along the magnetic field lines instead of across them, and the drag force will decrease because of the small angle between the conductor length and the magnetic field lines. The tether current will need to be controlled until the angle of the tether settles into an angle determined by the balance between these two forces. These electrodynamic torque vs. gradient torque dynamic interaction effects are discussed in the next section.

Force and Torque Balance Analysis:

It is now possible to calculate the forces and torques on the tether. It is also possible to use the fact that the electrodynamic and gravity forces and torques on the tether must balance each other out to calculate and teach some optimum values for some of the Terminator Tether™ parameters.

Electrodynamic Force and Torque:

As discussed above, both theory and experiment show that: provided the conducting tether is moved rapidly through the Earth's magnetic field in order to generate a voltage across it, and provided good contact is made with the space plasma, the conducting tether will have a current flowing through it. When a wire (moving or not) carrying a current I is embedded in a magnetic field B, there will be an electrodynatnic force F_E generated on each element of the wire. The electrodynamic force will be at right angles to the magnetic field vector and the length vector of the wire element, with a magnitude given by:

$$F_E=J\times B=ILB$$

where B is the horizontal component of the magnetic field, which is perpendicular to the assumed magnetic equator orbit plane, while the tether length vector L is assumed to lie in the orbit plane. If, as will be the case most of the time, the electron current is leaving the space plasma and entering the tether along the length of the tether, then IL needs to be replaced with an integral of the current along the length of the tether.

Note that the electrodynamic force amplitude or direction is not directly dependent on the motion of the tether through the Earth's magnetic field. The electrodynamic force would be the same if the tether were not moving and the current was being supplied by a battery. Since the current I is a function of the orbital velocity, however, there is a secondary dependence of the electrodynamic force magnitude on the orbital velocity, but not its direction. The electrodynamic force is always at right angles to the conductor, and stays at right angles to the conductor as the angle τ varies, as shown in FIG. **12**.

Assuming that the electrodynamic drag force is applied uniformly along the length of the tether, it is possible to make the simplifying assumption that the integrated force is effectively applied at right angles to the center of mass of the tether at the point L/2 as shown in FIG. **12**. The electrodynamic torque on the tether is then:

$$T_E=F_EL/2=IBL^2/2=vB^2L^3\cos\tau/2(R_C+rdL^2/m_T)=vB^2L^3\cos\tau/2R$$

Gravity Gradient Forces and Torques:

When a tether and its ballast end mass are deployed from a host spacecraft, the gravity gradient force field of the Earth, combined with the orbital centrifugal gradient force field, will cause the tether to deploy either up or down from the host spacecraft. The direction desired depends on which end of the tether is connected to the electron emitter. Normally, the electron emitter will be on the end attached to the host spacecraft, in which case the desired direction of deployment will be upward so that the induced voltage in the tether will produce an excess of electrons at the electron emitter end of the tether. The desired upward direction is chosen by having the deployer eject the ballast mass in the upward direction. Once the ballast mass has been started in that direction, the centrifugal force due to the orbital motion of the ballast mass will cause the ballast mass to continue to accelerate in the upward direction until it is brought to a halt by the full deployment of the tether.

If there were no electrodynamic or atmospheric drag, the equilibrium direction of the tether would be exactly along the vertical, since the combined gradient field is a maximum in that direction. Because a significant amount of electromagnetic drag is expected, the actual angle of the tether with respect to the local vertical will be at some angle τ, lagging behind the spacecraft motion in the plane of the orbit, as shown in FIG. **12**. In the following analysis shows that there is an optimum angle for τ that produces the largest electrodynamic drag force on the host spacecraft without producing tether instability.

The combined vertical gravity gradient and centrifugal gradient field 3Γ acting on the ballast mass m_B at the end of the tether of length L will produce a gradient force F_{GB} given by:

$$F_{GB}=-3_{\Gamma}m_BL\cos\tau$$

The strength of the force depends not only on the ballast mass m_B and the strength of the gradient field 3Γ, but also the component along the radial direction of the distance of the ballast mass from the center of mass, which is L cos τ. This force acts in the vertical direction along the radius vector leading from the ballast mass away from the center of the Earth. The amount of gradient force is not large. For a ballast mass of m_B=10 kg and a tether length of L=5 km, the gradient force is about 0.175 N.

As can be seen in FIG. **12**, the component of this gradient force that is at right angles to the tether, given by $F_{GB}\sin\tau$, will produce a torque T_{GB} on the tether that tends to restore the tether toward the vertical, lessening the angle τ.

$$T_{GB}=LF_{GB}\sin\tau=-3_{\Gamma}m_BL^2\sin\tau\cos\tau$$

The tether mass m_T also contributes to the gradient force and torque. If it is assumed that the tether has a uniform cross section, then it is possible to replace the distributed mass of the tether with an equivalent point mass m_T placed at the center of mass of the tether, which is the point L/2 along the tether, and a distance L/2 cos τ in the radial direction. The gradient force due to the tether mass is then:

$$F_{GT}=-3/2_{\Gamma}m_TL\cos\tau$$

While the gradient torque is:

$$T_{GT}=-L/2F_{GT}\sin\tau=-3/4_{\Gamma}m_BL^2\sin\tau\cos\tau$$

The total gradient torque attempting to restore the tether to its vertical orientation is then:

$$T_G=T_{GB}+T_{GT}=3_{\Gamma}(m_B+m_T/4)L^2\sin\tau\cos\tau$$

It is important to notice the variation of the total gravity gradient torque as the tether angle τ is varied. Since the gradient force is always in the radial or vertical direction, there is no torque on the tether when the tether is vertical, as is the case when there are no aerodynamic or electromagnetic drag forces. Once the drag forces become important and start to apply torque to the tether, increasing the tether angle τ, those drag torques causing an increase in tether angle τ will be opposed by a rising gradient torque which will attempt to decrease the tether angle. For small tether angles, the gradient torque increases first linearly with τ, then as sin τ, since cos τ is near unity for small τ, then at τ=45° the gradient torque reaches its maximum, where sin τ=cos τ=0.707 and sin τ cos τ=0.50. When this angle is reached, the tether is a point of catastrophic instability, for if there is a further increase in the electrodynamic drag force, causing the angle τ to become greater than 45°, the gradient torque, instead of growing stronger to counteract the increased drag torque, will become weaker and the tether angle will go rapidly to 90°.

To restore control to the tether angle if the instability occurs, it will be necessary to turn off the electrodynamic drag forces by shutting off the current flow through the tether. The τ=90° position for the tether and ballast mass is

a gravitationally unstable orientation. After a time, slight fluctuations in the gravity field will allow the gradient force to slowly take over and restore the tether to the vertical orientation, which, unless it can be controlled in some way, is equally likely to be up or down. It would therefore be desirable to maintain control of the tether angle so as to avoid the tether angle getting into the region of instability.

Torque Balance on the Tether:

The angle τ of the tether is determined by a balance between the electrodynamic torque T_E attempting to increase the angle τ and the gradient torque T_G attempting to decrease the angle τ. Balance is achieved when the two torques are equal:

$$T_E=T_G=T_{GB}+T_{GT}$$

or:

$$vB^2L^3 \cos \tau/2R=3_{\Gamma}(m_B+m_T/4)L^2 \sin \tau \cos \tau$$

Simplifing and rearranging yields an equation giving us the angle τ at which torque balance occurs:

$$\tau=\arcsin[vB^2L/6_{\Gamma}(m_B+m_T/4)R]$$

The physical interpretation of this equation is that the maximum electrodynamic force that can be sustained on the tether is limited by the gradient force on the tether. It is possible to increase the electrodynamic force by decreasing the total resistance R of the tether (for example, by using a tether with a larger mass and a lower tether resistance), but if the tether resistance is too low, then the quantity in brackets becomes greater than unity and this equation has no solution, indicating that the tether has reached an angle where instability sets in.

To maintain control of the tether angle, it will be necessary to vary the control resistance of the tether to compensate for variations in magnetic field strength and direction, plasma density (which affects the plasma resistance), and other factors, and thereby maintain the tether at an intermediate angle where both the electrodynamic and gradient forces are at an appreciable level and balance each other.

Optimization of Tether Angle:

At first glance, it might seem that the optimum angle for the tether would be 45°, since at that angle the gradient torque is largest and therefore can counteract a larger electrodynamic drag force. However, since the 45° angle is the point where instability sets in, it is desirable to set the tether angle at some value below 45°. The optimum angle is that which maximizes the horizontal or drag component of the electrodynamic force. This optimum angle τ is derived from the equation for the horizontal component of the electrodynamic force, or the electrodynamic drag force, since it opposes the host spacecraft motion:

$$F_{ED}=F_E \cos \tau=6[m_B+m_T/4]\Gamma L \sin \tau \cos^2\tau$$

By setting the partial derivative $\square F_{ED}/\square\tau=0$ and solving, it is possible to calculate that the optimum angle for the tether that gives the maximum electrodynamic drag force F_{ED}, while still keeping the tether torques balanced and under control, is $\tau=\arctan(0.707)=35.26°$. With this angle selected and maintained by varying the control resistor R_C to compensate for variations in plasma contact resistance and variatins in the strength and direction of the Earth's magnetic field B seen at the spacecraft, the tether experience the maximum stable value for the electromagnetic drag force of:

$$F_{ED}(\max,\tau=35.26°)=2.31[m_B+m_T/4]\Gamma L$$

There are many ways to provide the sensing information needed to provide the feedback signals to the control resistor, but the simplest is to merely measure the drag acceleration on the host spacecraft with a set of accelerometers, and maximiize the force in the direction opposite to the host spacecraft motion. Another method would be to measure the current in the tether, and knowing the tether resistance and the amount of control resistance, calculate the power being extracted and maximize that value. Alternate methods would be to use an optical position sensor or GPS receivers at both ends of the tether to measure the angle of the tether or the position of the ballast mass with respect to the host spacecraft.

To make an estimate of the magnitude of drag force attainable, assume that a typical aluminum tether with a length of L=5 km, a tether mass of m_T=10 kg and a ballast mass of m_B=10 kg is being used. Then the maximum gradient force limited electrodynamic drag force is F_{ED}=0.167 N. The power being dissipated in the canoical tether at the angle τ, with $R_C=R_T=rdL^2/m_T=185\ \Omega$ is given by:

$$P=IR=[vBL \cos \tau]^2(R_C+rdL^2m_T)$$

which for an angle τ=35.26° results in a power dissipation of 1570 W. Thus, the thrust level per unit power obtained by the typical Terminator Tether™ would be about 0.106 N/kW. This number is comparable to the value of 0.148 N/kW estimated for the much heavier and longer TSS-1R tether.

Reconciliation of Energy and Force Analysis:

By a force and torque balance analysis an optimum angle for the tether has been discovered at which it is possible to obtain a maximum in the drag component of the electrodynamic force. There is also an additional component of the electrodynamic force, the component in the vertical direction, $F_{EV=FE} \sin(\tau)$, which is downward for an upwardly deployed tether. This component of force combines with the gravity force of the Earth to effectively allow the host spacecraft to orbit a little faster than normal for that orbital altitude. It does not contribute to the deorbiting of the host spacecraft. But since this vertical component of force is created by current running through the tether, and that current is creating heat and dissipating energy as it passes through the tether, there might be some concern that the force and torque balance analysis above does not conform to the law of conservation of energy.

The inventors will now show, in a very general manner, that no matter what the tether angle, the electrical power being dissipated in the tether is exactly equal to the power being lost by the slowing of the host spacecraft.

The "deorbit power" P_D that must be removed from a spacecraft moving at a velocity v when that motion is opposed by a drag force F_{ED} is:

$$P_D=v\bullet F_{ED}=vF_E \cos \tau=vILB \cos \tau=I[vBL \cos \tau]$$

But, since the voltage V induced across the tether of length L and tilt angle τ moving at a velocity v through a horizontal magnetic field B is

$$V=E\bullet L=EL \cos \tau=vBL \cos \tau$$

Therefore:

$$P_D=IV=P_E$$

And the deorbit power P_D extracted from the slowing of the spacecraft by the drag component of the electrodynamic

force is always exactly equal to the electrical power P_E being dissipated as heat in the tether circuits, independent of the tether angle.

Optimization of Tether Mass Distribution:

If it is not possible to use a piece of the host spacecraft as ballast mass, then the mass of the ballast must be included in the Terminator Tether™ mass. It would be desirable to minimize the total Terminator Tether™ mass, since every kilogram saved means that another kilogram's worth of revenue-producing transponders can be added to the working payload of the host spacecraft. Given a total mass for the Terminator Tether™ and the mass of the deployer/controller unit, it is possible to optimize the mass distribution between the ballast mass and the tether mass to obtain a minimum total Terminator Tether™ mass. A well-designed Terminator Tether™ will also have most, if not all, of the deployer mass incorporated into the ballast mass.

Assume that the total Terminator Tether™ mass consists of the deployer/controller mass m_D, the tether mass m_T, and the ballast mass m_B, with $m_B > m_T > m_D$. Of the three mass components in the Terminator Tether™, two of them affect the electrodynamic drag performance. If it is assumed that the ballast mass is a factor X larger than the tether mass, or $m_B = X m_T$, the maxinum drag force that can be obtained is now:

$$F_{ED}(\max) = 2.31 m_T (X+0.25) \Gamma L$$

If it is assumed that the control resistor has been adjusted so that this maximum value for the electrodynamic drag force is maintained as the motion of the spacecraft along its orbit moves the spacecraft into regions with different magnetic field strengths and plasma densities, then for the angle $\tau = 35.26°$, $\cos(35.26°) = 0.817$, and the maximum electrodynamic drag force in terms of the electrodynamic parameters will be:

$$0.817 vB^2L^2/(R_C + rdL^2/m_T) = F_{ED}(\max) = 2.31 m_T (X+0.25) \Gamma L$$

or canceling out terms and rearranging:

$$(X+0.25) = 0.353 vB^2L/\Gamma m_T (R_C + rdL^2/m_T)$$

It is now possible to make the further simplifying assumption that to maintain control of the tether, the control resistor needs to be roughly the same size as the tether resistance or $R_C \approx rdL^2/m_T$. Using this assumption produces an equation for the optimum value for the ratio X of the ballast mass to the tether mass:

$$\begin{aligned} X = vB^2/\Gamma rdL - 0.25 &= -0.25 + \frac{vB^2}{12 \sin\gamma \cos\gamma \Gamma rdL} \\ &= -0.25 \frac{\Lambda}{L} \end{aligned}$$

Where Λ is the "effective electrodynamic length".

If the tether is short, so that L is small, this equation indicates that the ballast mass must be increased to increase the gradient force, since it is the gradient force which determines the upper limit to the amount of electrodynamic drag force that can be generated without losing control of the tether.

Assuming the usual values for the Earth's magnetic and gradient fields, the velocity of the host spacecraft through the magnetic field, and the resistivity and density of aluminum, this equation becomes:

$$X = 10.9/L - 0.25$$

where L is in kilometers.

For a typical tether of length L=5 km, X=1.93. If the total mass for the Terminator Tether™ is 20 kg, or 2% of the host spacecraft mass, and the mass of the deployer is 10 kg, then the remaining 10 kg should be distributed so that 6.59 kg is in the ballast mass while 3.41 kg is in tether mass.

Optimization of Tether Length:

If the ballast mass consists of a piece of the host spacecraft, then the mass of the ballast does not have to be considered in the optimization of the Tether system. In this case, the optimum distribution of the Tether mass is to put as much mass as possible into the tether, with a minimum in the deployer/controller package. Under this assumption, the optimum length of the tether is determined by the desire to keep the Area-Time Product of the host spacecraft plus Tether to a minimum.

In a long tether of length L, the effective "collision" cross-sectional area is not the area of the tether, but the larger area produced by multiplying the length of the tether by sum of the width of the tether plus the width of the "target" spacecraft that would be damaged by the tether hitting it. Thus, to decrease the "area" portion of the Area-Time Product, it would be desirable to shorten the tether, making it thicker, and perhaps slightly wider, at the same time, thus keeping the same tether mass and electron collection area, and thereby maintaining the drag force and keeping the decay time at the same level. The result will be a shortening of the Area-Time Product.

If the tether is shortened too much, however, the smaller voltage generated across the shorter tether will leave less voltage margin for the operation of the plasma contactors and the battery recharge system. Since the maximum voltage that can be generated is about 200 V/km, and typical plasma contactors and battery, chargers take 25–100 V to operate, a minimum length for a Tether would be roughly 2 km. Host spacecraft operating in polar orbits, where the conditions for voltage generation are not as good, may require a tether length of 5 km or more.

Since many watts of heat power will be dissipated in the control resistor, means must usually be provided to radiate the heat away into space. One low-mass method of accomplishing this is to make the control resistor (or resistors) in the form of a long, electrically insulated, high resistivity wire similar to those used in electric blankets, but designed to operate at a higher temperature, and during the fabrication of the electrodynamic tether, incorporate the high resistivity wire (or wires) into the end of the tether closest to the control circuit by weaving or braiding the insulated high resistivity wire in with the uninsulated aluminum wire of the electrodynamic tether. The surface area of a long wire is very large, so in this extended wire configuration, exposed to the space all around it, the hot control resistor wire can self-radiate its power into cold space without incurring the mass penalty of a separate radiating surface.

Implementation:

The basic optimum structure for a Terminator Tether™ would be one of the many types of Hoytethers. A multiline (6–12 primary line) Hoytape™ will provide the largest contact area with the plasma, since both sides of the tape would be able to pass current to the plasma. If the spacing between the primary lines is chosen to be larger than twice the Debye length of the plasma, then the effective current collection area per unit length of the Hoytape is proportional to the width of the Hoytape mesh, not the diameter of the wires in the mesh. Thus, a Hoytape not only provides an assured longer life for the Terminator Tether™, but very short lengths will also provide a very large current collection areas.

The deployer for the tether can deploy the Terminator Tether™ either down or up or both. The deployer can stay

attached to the spacecraft as was done in the SEDS missions, or perhaps a better alternative would have the deployer ejected from the spacecraft, with one end of the tether still attached to the spacecraft, reeling out tether as it leaves. The empty deployer would then act as a ballast mass at the end of the Terminator Tether™, which would improve the performance.

The "Remora Remover"

In addition to attaching Terminator Tethers to spacecraft before launch, it is possible to consider a missile-like application. This "Remora Remover" missile would use a Terminator Tether™ carried by a seeker missile similar to the small "hit-to-kill" missiles developed by the Space Defense Initiative Office that deployed a net loaded with oriented metal rods. The Remora Remover missile would hunt down a spacecraft that needs to be removed from space, but instead of hitting the spacecraft, the missile would be programmed to rendezvous with the spacecraft and attach itself to the host spacecraft using a hooked net, harpoon, or adhesive "sucker". The Remora Remover missile would then deploy the Terminator Tether™, which would bring down both the spacecraft and the missile.

The inventors have presented two analyses, backed up with data obtained from space flight experiments. One analysis was based on generalized energy conservation laws while the other analysis use force and torque balance arguments. Both analyses show that optimized aluminum wire tethers 2 to 5 km in length and massing just 1% to 5% of the mass of the host spacecraft can deorbit the host spacecraft in the order of a few weeks, thus mitigating the long-lived orbital debris hazard created by a constellation spacecraft after their end-of-life.

Power Augmented Operation of the Tether:

It is well known in the aerospace literature that if a spacecraft has a power supply and a conducting tether hanging from it, and the spacecraft is in an orbit or trajectory that takes it near a body, such as the Earth or Jupiter, which has both a magnetic field and a region of moderate density electron-ion plasma, and electrical current is pumped from the power supply through the tether and back through the plasma, that the current flowing through the tether will interact with the magnetic field of the body, producing forces on the tether and thence on the spacecraft, changing its orbit or trajectory. These forces can be used to increase or decrease the spacecraft altitude and/or inclination. The amount of altitude or inclination change is proportional to the ratio of the power available from the power supply divided by the mass of the spacecraft and varies with altitude. The unpowered Terminator Tether™ is a simple example of such a system, in which only altitude decrease is possible, although small amounts of both inclination increase or decrease are possible at the same time. Some typical references to this prior art are: Les Johnson, "Propulsive Small Expendable Deployer System Mission (ProSEDS)", Proceedings of the OAST 8th Advanced Propulsion Workshop, JPL, Pasadena, Calif., 20–22 May 1997; and Les Johnson, Joe Carroll, Robert D. Estes, Enrico Lorenzini, Brian Gilchrist, Manuel Martinez-Sanchez, Juan Sanmartin, and Irwin Vas, "Electrodynamic Tethers for Reboost of the International Space Station and Spacecraft Propulsion, AIAA Paper 1996.

Since the Terminator Tether™ of the invention is normally associated with a satellite that has a power supply in the form of a solar panel combined with a storage battery, the Terminator Tether™ can be operated in the "powered propulsion" mode if desired. Such a mode would be useful when attempting to avoid a collision between the Terminator Tether™ and another spacecraft. In such cases, the power from the solar panel, augmented by the power stored in the battery, can be used to temporarily operate the Terminator Tether™ in the propulsion mode instead of the normal drag mode. This would enable to Terminator Tether™ to raise its altitude and/or increase or decrease its inclination to avoid a collision.

In addition, the Terminator Tether™ could be operated in the "power-augmented drag" mode. In this mode, there will be a current induced in the tether by the motion of the spacecraft through the magnetic field, which will cause a drag force on the spacecraft. This induced current would then be augmented by additional current in the same direction generated by the solar panel and the storage batteries in the power supply. The increased current will cause an increased drag force. If there is a significant vertical component of the magnetic field there will also be an increased force normal to the orbital plane, which will cause an increased rate of change of inclination.

When the Terminator Tether™ is operated in the "powered propulsion" or "power-augmented drag" mode, the conditions for stable optimum operation will be essentially the same as in the "unpowered drag" mode. The reason the conditions stay the same is that the maximum tether force than can be effectively utilized is limited by the strength of the gradient force, which has not changed, since the length and mass of the tether and the ballast mass has not changed for these different modes of operation. As a result the optimum operational angle for the tether is still 35.26 degrees, and the optimum ratio of ballast mass to tether mass for different tether lengths and tether material is still determined by the analysis of the invention as is set forth above.

In the analysis given above, where the optimum tether angle was found, the tether was assumed to be in the plane of the orbit and lagging behind the spacecraft motion, since in the "unpowered drag" mode, that would be its normal position, although if the component of the magnetic field along the orbit were high, there would be some tilt of the tether out of the plane of the orbit, producing a force tending to change the inclination of the orbit. In either of the "powered" modes of operation of the Terminator Tether™, however, the tilt of the tether could be forward toward the motion of the spacecraft or strongly tilted to one side or the other of the orbital plane. In all these cases, if the electrodynamic force is allowed to become too large, and the tether angle exceeds 45 degrees, the restoring force of the gradient field will drop off and the tether angle will go unstable. As a result, the optimum angle for the tether that will give the maximum stable force, whether it is a maximum drag force, and maximum propulsion force, or a maximum inclination change force, will be 35.26 degrees, and the optimum ratio for the mass of the tether versus the mass of the ballast will be the same as for the unpowered drag case.

The analysis that gave the optimum angle as 35.26 degrees assumed that the tether would be oriented like a rigid rotor. In reality, variations in forces along the tether will probably cause the tether to hang in a slightly curved shape, where the optimum angle may not be exactly 35.26 degrees from the local vertical. The optimum angle of the tether as it leaves the host spacecraft in such a case is where the drag force is largest.

The present invention is discussed in this disclosure in terms of its space applications as a Terminator Tether™ useful for the removal of unwanted satellites. It should be understood, however, that the present invention is useful in any application where a space object can use a conductive tether to produce electrodynamic force through interaction

with a magnetic field. The invention, therefore, should be limited not by this description, but only by the appended claims and their equivalents.

What is claimed is:

1. A method of operating a conductive tether attached to a space object, said conductive tether being oriented at an angle to magnetic field lines of an external magnetic field and said conductive tether moving across the magnetic field lines of said external magnetic field at said angle to producing an electric current in said conducting tether and a resulting electrodynamic force acting on said tether and said attached space object comprising,

Controlling the amount of electric current flowing in said conducting tether to vary the angle between the conductive tether the field lines of the external magnetic field and the electrodynamic force acting on said tether and attached space object.

2. A method as in claim **1** wherein said angle is less than 45 degrees.

3. A method as in claim **1** wherein said angle is 35.26 degrees.

4. A method as in claim **1** wherein said angle is controlled to average 35.26 degrees over time.

5. A method as in claim **1** wherein said angle is controlled to average 35.26 degrees over the length of the tether.

6. A method as in claim **1** wherein the space object and the tether connected to it are rotated about their center of mass while the conductive tether interacts with the external magnetic field.

7. A method as in claim **1** wherein the angle of the conductive tether to the external magnetic field is controlled by sensing a measurable parameter of the space object/conductive tether system.

8. A method as in claim **7** wherein the parameter is current flow in the conductive tether.

9. A method as in claim **7** wherein the parameter is the electrical power dissipated in the conductive tether and the current control system.

10. A method as in claim **7** wherein the parameter is the relative position of the space object and the position of the far end tip of the tether.

11. A method as in claim **7** wherein the parameter is the acceleration of the space object.

12. A method as in claim **6** wherein the parameter is the state vector of the space object as measured by the Global Positioning System.

13. A method as in claim **1** including the step of applying electric power to the conductive tether to change the state vector of the space object.

14. A method of operating a conductive tether attached to a space object, said conductive tether being oriented at an angle to the local vertical between said space object and a celestial body having a magnetic field having magnetic field lines external to said conductive tether; said conductive tether moving across said magnetic field lines of said external magnetic field at an angle to the local vertical to produce an electric current in said conducting tether and a resulting electrodynamic force acting on said tether and said attached space object comprising,

Controlling the amount of electric current flowing in said conducting tether to vary the angle between the conductive tether the local vertical between said space object and said celestial body to vary the electrodynamic force acting on said tether and attached space object.

15. A method as in claim **14** wherein said angle is less than 45 degrees.

16. A method as in claim **14** wherein said angle is controlled to average 35.26 degrees over time.

17. A method as in claim **14** wherein the space object and the tether connected to it are rotated about their center of mass while the conductive tether interacts with the external magnetic field.

18. A method as in claim **14** wherein the angle of the conductive tether to the external magnetic field is controlled by sensing a measurable parameter of the space object/conductive tether system.

19. A method as in claim **18** wherein the parameter is current flow in the conductive tether.

20. A method as in claim **18** wherein the parameter is the acceleration of the space object caused by the electrodynamic force acting on the space object.

21. A method as in claim **18** wherein the parameter is the change in the state vector of the space object as measured by the Global Positioning System.

22. A method as in claim **14** including the step of applying electric power to the conductive tether to change the state vector of the space object.

23. A method as in claim **14** wherein the celestial body is the Earth and the magnetic field is the Earth's magnetic field.

24. A method as in claim **14** wherein the celestial body is the sun and the magnetic field is the Sun's magnetic field.

25. A method as in claim **14** wherein the magnetic field is the vector sum of the magnetic fields from all celestial bodies in the solar system.

26. A method as in claim **14** wherein the conductive tether is a Hoytether.

* * * * *



I have a fondness for quality multi-turn wirewound pots, in the same way that I used to like using high quality air-spaced variable capacitors in my projects. Similarly, the way that a regular one-turn pot feels when operating is important to me. The pot that I originally was going to use for the AF gain felt a little "scratchy" in the way it rotated, so I bought one from Radio Shack that feels silky smooth. Even the first BNC connector that I used for the antenna socket (which was left over from an earlier project) was a cheap component, and I noticed that plugging and unplugging the antenna took more force and fiddling than it should have, so I used a new higher quality part (Mouser # 161-9323). If this seems like a little too much attention to detail, let me explain. The connectors and controls are the way that you, the operator, interface with the radio. Higher quality components used here will greatly improve your experience of the radio. What would you rather use – a radio that takes force and fumbling to connect the antenna, has hard to adjust tuning due to the use of a cheaper one-turn pot, and a volume control that turns roughly, or a radio with controls and connectors that operate and rotate smoothly? These kind of things make a big difference. It might seem illogical to spend so much more on connectors and controls than on the rest of the circuit, but given how positively they can impact the user experience, it's an investment worth making. I was hoping that this receiver would become a permanent part of my station, so spending a little more wasn't a problem.

You'll notice in the next picture that I used two 10-turn pots. One was for the tuning, and the other for regeneration. In the QST article, N1BYT details his method of using a one-turn pot with a separate preset to set the regeneration range on the main regen control. I'm sure that this works very well, but I happened to have an extra 10-turn pot available and was wanting an excuse to use as many of these wonderful things as possible, so I omitted the preset (R6 in the article) and used a 10-turn for the regen control. You do get a "whizzing" sound when adjusting the regen if you use a wirewound. To eliminate this, you can bypass between the wiper and ground for both audio and RF with a 10uF and 0.1uF connected in parallel. I've left mine as is for the time being, as I quite like the whizzing sound! *(Edit: The novelty of the whizzing sound wore off swiftly, so I placed a 33uF cap between wiper and ground at the regen pot. It took care of things nicely.)*



Daniel N1BYT's original design for the WBR didn't use a volume pot in front of the LM386, relying just on the 1K RF attenuation pot in the antenna lead. I decided that I wanted a little more audio gain in order to drive a loudspeaker, so I used the audio chain from N1BYT's OCR II receiver, but connected a 10uF electrolytic between pins 1 and 8 of U2 to get the maximum gain of 200 out of the LM386 IC. Running the LM386 with maximum gain, and also fed with a preamp, I wanted to be able to control the gain of the AF stage as well as being able to attenuate the RF input, hence the extra pot. The toggle switch will be used to switch audio filtering at a later stage.

The enclosure build had gone so well that I started hoping that the performance of the receiver, when I built it, would be good enough to justify putting so much time and effort into the case. In retrospect, I probably should have built and tested the circuit first before deciding whether it was worthy of an enclosure. Luckily it was.

I built the circuit Manhattan style using pads from W1REX at QRPMe. I talked about the MeSQUARES in an earlier post and liked them so much that I ordered a sheet of MePADS from Rex. MePADs are Manhattan pads for IC's, as you can see in this picture. I had already broken off the pad I was going to use in this project:


QRPme
DIP8
SOIC8
SOIC14/16
QRPme SOIC 14/16/18
R2
R1
QRPme SOL16
QRPme DIP 14/16/18-A
QRPme DIP 14/16/18-B
INCHES
PICAS (6 & 12 PT)
EP-18

As you’re building with these pads, if you find that you’ve glued one in the wrong place (I use Super Glue in the gel form), just slip a sharp utility blade underneath the pad and it comes right off. No need to fear a bad circuit layout, as you can change it if you make a wrong move.

The first part of the circuit to be built was the detector and regeneration circuit. I didn’t have an MV104 dual tuning diode as specified in the original article, so used two back to back MV209’s, which you can see in the following picture, along with Q1 and Q2, the 2N3904 regeneration transistor and the MPF102 regenerative detector respectively:



Now I’ve added a few more components, including the 78L05 voltage regulator, which is hiding behind the grey 2.2uF electrolytic in the foreground:



The completed circuit. At this point, I hadn’t added the 10uF electrolytic between pins 1 and 8 of U2 (LM386). The 2N3904 audio preamp is just below the LM386 audio IC:



Some more views of the completed circuit. I knew that I was giving myself plenty of space to work with, but didn't realize that there would be so much of it left over. This is rather handy though, as it allows room for some low-pass audio filtering that I want to add later:







All very well and good, but would it work, and how well? The next picture shows the board installed in the case. I added a 10K trimpot in place of R12 in order to adjust the tuning coverage of R11, the main tuning potentiometer. You can see the orange trim-pot near the front left-hand side of the board. It was only just now looking at this picture, that I realized I had left out C22, the 0.1uF capacitor in the antenna lead:



The same shot from a slightly higher angle:



By adjusting trimmer capacitor C8 and the trimmer resistor in place of R12, I achieved coverage of approximately 6970 – 7311 KHz. The extra 11KHz at the top of the band was important to me so that I can listen to the BBC World Service on 7310. Vatican Radio broadcasts in English daily at 0250 utc on 7305, so the extra coverage above the top end of 40 allows me to receive that also. Adjust C8 to set the top end of your coverage, and the trimmer in place of R12 to set the bottom end of the coverage. The tuning rate is a bit higher at the bottom end of the band than the top, being about 50KHz/turn in the CW sub-section.

I spent a few days enjoying the radio in this state before making a top cover for it. The RF attenuation control doesn't take the input signal completely down to zero. No doubt this has a lot to do with my decision to use an unshielded piece of copper wire to connect the antenna socket at the back of the rig with the 1K pot. N1BYT does this in his receiver pictured in the QST article. I liked it because it's a reminder of the days when complete radios were wired using this technique, but I think I'll probably replace that wire with a length of co-ax (after fitting C22 inline with the antenna lead) from the BNC to the 1K pot. That should allow attenuation of the input down to zero (or very close). *(Edit: I just did, and it does.)*

A top cover for the receiver:



The completed WBR Receiver (darn those front-panel fingerprints!) –



The space left at the top right-hand side of the front panel was in case I found a way to hook up a frequency counter to the regenerative detector while in oscillation in order to provide a frequency readout. I have heard of people achieving this with the WBR by placing a pick-up coil near the main tank coil. Still not sure whether I'll pursue this.

Some of the things I've heard on this wonderful little radio in the first few days of owning it are the Vatican Radio transmitter in Sackville, New Brunswick on 7305 and Radio Australia (it was great hearing their Waltzing Matilda sign-on melody). I also heard FO8RZ in French Polynesia on 7001 and immediately switched over to the Norcal 2N2/40 to work him with 4 watts! One of the reasons for building this receiver was in order to listen for AM activity on 40 (amateur, as we all know that there is plenty of broadcast activity there!) and I was happy this morning to hear W6LHQ running 200W of AM from his QTH in Modesto, CA on 7293KHz. This is one great thing about a regenerative detector – it will receive SSB and CW as well as AM. I believe it can receive FM too via the slope detection method, though I haven't had a chance to try this out.

The Wheatstone bridge circuit in the tank is an elegant way to resolve the problem of oscillator radiation from the antenna that is common in simple regens, without resorting to adding a stage of RF preamplification, and it works very well. I made no particular effort to match C5 and C6, so either I was lucky, or the circuit is forgiving, because I have encountered no issues with re-radiation. Without re-iterating the summary of this receiver's performance that I gave in the second part of the 4th paragraph of this write-up I'll just say this; I was hoping that this regen's performance would be good enough for me to have it as a permanent part of my station, and it is.

The next step will be to replace the antenna input wire with a length of co-ax, and then build some audio filtering. At that point, I'll make some recordings of the audio and post a YouTube video.

I'm also thinking about bread-boarding another version of this receiver to encompass a larger portion of the shortwave spectrum. I have some MV108 varactors, and am thinking that the wider capacitance swing of one of those could give me broad coverage of a large part of the HF spectrum, with a fine tuning control provided by another diode. It would be great to have a regen to give me continuous coverage of, say, 3 – 10MHz, or even higher.

Lots of fun and experimentation to come. Many thanks to N1BYT for this fine little receiver.

Notes added after above post was written –

*Current consumption is low too – I measured around 12-13mA in regular use.

*A number of other builders have experienced problems with low sensitivity with their WBR's. LA3ZA found that substituting a 0.22uH inductor for Z1, the 1″ length of stiff wire between the center-tap of the coil and the ground plane, did the trick. In the QRP-tech group on Yahoo, Steve AA7U did some experimenting and found 1uH was the optimum value for him. Other builders have not had these issues with theirs. My suggestion would be to build it as in the original design, adding the inductor if it seems necessary.

*As mentioned earlier, I added an audio pre-amp stage to my WBR, as suggested by N1BYT in the original article. The schematic of the simple stage I added can be seen in this post.

Poor Man's Electronics Web Page

Random Wire Antenna Project Links:

- Back to main page
- How to build it
- How it works
- Computer program
- Homebrew arrestor

Random Wire Antenna

Homebrew lightning arrestor:


Pill bottle
to receiver
Use 2 screws, file to a point,
double nut as shown, and adjust
gap to about 1/4"



Lightning arrestor made from pill bottle

How to make it

Drill a hole in the bottom and in the lid of a 2-1/2" long by 1-1/4" dia. pill bottle. File the ends of two 3" #20 machine bolts into a sharp point. Then lock them in place on each end of the pill box with double nuts. Adjust the gap to about 1/4".

Strip about 3/4" of #14 copper stranded wire and loop it under the outside nut. Do this on both ends. The wires should connect to the antenna lead-in on one side and the ground lead wire on the other side.

Seal around the lid and connections with clear silicone caulking to make the unit water tight.

How it works

Electrical field intensity is a function of the amount of voltage divided by the surface area over which it acts. The diameter of the tip of the screws when filed down is quite small, so the surface area is quite small. Since field intensity is greater for a smaller area, it will take a relatively small voltage to raise the field intensity inside the pill bottle to the point where the air across the gap will ionize.

Once the air has ionized, it becomes a conductor; that is, a short circuit, and will bypass the static charges to ground.

Copyright © 2007 - Prof. W.S. Walker, West Virginia State University - All Rights Reserved.

Contact me





BEST BUY
Affordably awesome.
Shop Now
© 2018 Best Buy

You may have noticed that corded phones don't need to be plugged into an electrical outlet. That is because they get all the power that they need to operate directly from the phone line itself. The phone company sends this power directly to your house through a pair of dedicated wires that connect to your phone jack. When the phone is not in use, this is a constant DC signal (about 50-60 volts). When the phone rings, the signal is a 20 hertz AC signal (about 90 volts). When in use it is a modulated DC signal (between 6 and 12 volts).

The phones lines even have power during a blackout in most cases. This is because the phone company maintains their own backup power system. Your phone lines may be powered even if you don’t have a land line service set up.

Add Tip Ask Question Comment Download

Step 2: Check the Phone Line With a Multimeter

advertisement








BEST BUY
Affordably awesome.
Shop Now
© 2018 Best Buy

2 More Images

(https://cdn.instructables.com/FXBA/3AX/HEI4EJC0/FXBV3AXHEI4EJC0.LARGE.jpg)

Before you try to tap into the electricity in the phone line, you should check it with a multimeter to see what you are working with.

Start by cutting open a phone cord and separating the internal wires. In most cases you will have one red wire and one green wire. Strip the insulation off the ends. Then plug the cord into a phone jack and use a multimeter to measure the output voltage. At my house, I measured an open-circuit (no load) voltage (http://en.wikipedia.org/wiki/Open-circuit_voltage) of 52 volts DC.

Then I hooked up various resistors to see what the output would be with different loads. I determined that the supply voltage isn't regulated. This means that the voltage changes depending on the resistance of the circuit that it is powering. After some calculating, I worked out that the base signal coming out of my phone jack pretty closely resembles a 52

Volt DC source (http://en.wikipedia.org/wiki/Voltage_source) with a 628 ohm internal resistance (http://en.wikipedia.org/wiki/Internal_resistance).


BEST BUY
Affordably awesome.
Shop Now
© 2018 Best Buy

Basically this means that I can run a 12V circuit at 64mA, a 9V circuit at 68mA, or a 5V circuit at 75mA. This isn't a lot. But it is enough to charge a cell phone.

Add Tip Ask Question Comment Download

Step 3: Construct a Simple Voltage Regulator Circuit



(https://cdn.instructables.com/FXB/5YW1/HEI4EJY4/FXB5YW1HEI4EJY4.LARGE.jpg)








BEST BUY
Affordably awesome.
Shop Now
© 2018 Best Buy



(https://cdn.instructables.com/FI0/TZ31/HFLXD34Z/FI0TZ31HFLXD34Z.LARGE.jpg) (https://cdn.instructables.com/FM8/5BNH/HFI4FPVJ/FM85BNHHFI4FPVJ.LARGE.jpg) (http FZV/UA2B/HFI4FPKY/FZVUA2B

We know that the phone needs 5 volts in order to charge. But we don't know how much current it draws or it's equivalent load resistance (http://en.wikipedia.org/wiki/Electrical_load). So we can't charge the cellphone directly from the phone line. We need to use a voltage regulator (http://en.wikipedia.org/wiki/Voltage_regulator) to bring the output of the phone line down to 5 volts and keep it there. A LM7805 5 volt regulator should work fine.

To make this simple phone line adapter you will need the phone cord that we have been working with, the 5V voltage regulator and a USB connector cable with a female end. Just connect the red wire from the phone line to the first lead on the regulator and connect the green wire from the phone line to the second lead. Then connect the black wire from the USB cable to the second lead on the regulator and connect the red wire from the USB cable to the third lead on the regulator. If you can't solder the wires together (because the power is out), you can just wrap the wires around each lead. If you do this, you should bend the leads of the regulator away from each other. This will help you avoid accidentally crossing the wires.

This simple regulator circuit is able to safely convert the base phone signal into something that can be used to charge your phone. However, many voltage regulators are not able to handle the AC signal that they would receive if the phone rang. So if you are worried that you might receive a call while your regulator is hooked up to the phone line , then you may wish to add a diode between the red wire from the phone line and the first pin on the voltage regulator. This will protect your circuit from problems that may be caused by reverse polarity.

Affordably awesome.
Shop Now
© 2018 Best Buy

Add Tip Ask Question Comment Download

Step 4: Use Other Regulators for Other Output Voltages





(https://cdn.instructables.com/FV8/KSP4/HFLXD373/FV8KSP4HFLXD373.LARGE.jpg) (https://cdn.instructables.com/FTV/X2E9/HEI4ETY0/FTVX2E9HEI4ETY0.LARGE.jpg)

A 7805 regulator will work if you need an output of 5 volts but other kinds of voltage of voltage regulators are also available. Other voltages in the 78xx series include 6V, 8V, 9V, 10V, 12V, 15V, 18V, and 24V. In addition to these fixed value regulators, there are also variable regulators that let you set the voltage level with the use of a few external components. One such variable voltage regulator is the LM317 (http://www.ti.com/lit/ds/symlink/lm117.pdf). These are what you would use if you needed a different output voltage.

Step 5: Finished Phone Line Adapter Tool



(https://cdn.instructables.com/FTI/TCMG/HFLXD3ZQ/FTITCMGHFLXD3ZQ.LARGE.jpg)

Plug the phone cord into the nearest phone jack. Then plug your phone and charging cable into the USB cable. Your phone should begin charging. In a few minutes, your phone should have enough power to make a call.

Add Tip Ask Question Comment Download

BEST BUY

Affordably awesome.

Shop Now

© 2018 Best Buy


Make:
2:21 / 3:06
CC
Up next
AUTOPLAY

DIY Hacks & How To's: Emergency Power from a Land Line

My Home Page

Amateur Radio
Operating Conditions
Antennas
Accessories
Projects & Kits
Data Modes
Information
Portable
QSL
RSGB Ltd
Links
QRM
Bits 'n' Bobs
Contact

Mini Site Map

MDS975 Home

Feedback

G Whip Antenna Products
Get on the air with TOP QUALITY BRITISH

M0MTJ | Operating Conditions | Antennas / Aerials | /P Portable Operating | Accessories | Projects & Kits | Useful Information
Contact MØMTJ | Contact M6ORS | Links to Amateur Radio Sites | RSGB | QSL | The Amateur Radio Mini Site Map
WSPR Weak Signal Propagation Reporter | Operating in Cyprus | All Latest Site Updates
News, Photographs, Developments, Events and 'Bits 'n' Bobs' | Operating in Cyprus | All Latest Site Updates

Donate

Components available from Bowood Electronics:
Bowood Electronics
www.bowood-electronics.co.uk

> Back to the Main Projects Page <

Projects 1 | Projects 2 | Projects 3 | Projects 4 | Projects 5 | Projects 6 | Projects 7 | Projects 8 | Projects 9 | Projects 10 | Projects 11 | Projects 12

"A complex system that works is invariably found to have evolved from a simple system that worked." *- John Gall*

PROJECTS (05)

Hands Free Mobile Microphone Interface Unit for the Yaesu FT-7900 and other mobile rigs - by MØMTJ

Icom, Kenwood, Alinco, Yaesu FT-7900 / FT-7800 / FT1500 / FT1802 / FT1900 / FT2800 / FT-2900 / FT8800 / FT8900 FT-857 FT-897 FT-817 FT-450 FT-900

For The Icom ID-5100 Hands Free Microphone Interface -
Please see Projects Page 12 here >>



Here's a little 'home brew' construction project that will be very useful in the car or van, certainly adding to safety of operating when mobile

Rather than use a standard hand mic, this simple unit will allow you to keep your hands safely on the steering wheel by using a small electret microphone element fixed near the sun visor or other convenient position and a separate PTT switch.

The basic circuit is for powering an electret condenser microphone, including suitable filtering and the PTT circuit that is required for the FT-7900 and similar transceivers - this will not be required for other models.

The basic circuit and electret microphone will be all that is needed for many transceivers. For example, the Yaesu FT-857 and 897 transceivers are designed to be used with a lower output dynamic hand microphone, so the significantly higher output of the electret condenser mic' ensures that the transceiver has plenty of gain for both a closely positioned mic and a more distant mic, positioned on the sun visor.

When using the mic on the sun visor the audio level is reduced due to the increased distance. In this position some transceivers may not have enough gain to provide sufficient audio output. Therefore, in a second version, I decided to add a simple microphone amplifier to the interface unit so that the audio level can be boosted and adjusted to an appropriate level using a preset potentiometer. This also includes some audio filtering.

The connection for the FT-857 and FT-897 is shown below, for these transceivers the microphone amplifier will not be needed, only the simple electret microphone powering circuit is required.

Connections are described below for the Yaesu FT-857, FT-897 and also the differing connections for the FT-7800 and FT-7900, which is the same for other, similar, Yaesu transceivers such as the FT1500, FT1802, FT1900,

G-WHIP ANTENNAS

Site Search

Find

powered by FreeFind

FT2800, FT-2900, FT8800, FT8900.

Other models and brands (Icom, Kenwood etc) will simply need a different microphone plug and appropriate wiring - this is covered below.

Basic vs Amplified ? I would recommend using the non-amplified interface version if possible, due to the risk of RF feedback from using the amplified version. I find that the amplified version works well on my Yaesu FT-7900 both in the car and in the shack, but it does cause RF feedback in the Yaesu FT-857 and Icom IC-706.

However, when building the non amplified version, I would cut out the same size piece of strip-board and mark and all the strip break points, as shown in the details below. Then the additional components can be added at a later date should you wish to upgrade from the basic interface to the amplified version.

Safety

Using the hands free microphone avoids a one-hand-on-the-wheel style of operation while holding a fist mic' up to one's mouth - for some reason whenever I am operating mobile I may see two or three patrol cars driving by.

Microphone and Push To Talk Switch

Microphone


PC Internet type headset microphone / earphone
(Only the mic jack plug is shown)

The microphone position depends upon personal preference, and options could include an 'ear set' similar to those often used for hands free operation of a mobile phone or PC Internet phone such as Skype, or a 'home brew' microphone made from an electret microphone capsule. These are widely available from electronic component suppliers.

For my initial experiments I used a P.C. type headset on an 'ear hook', pictured right. Later I tried a separate omnidirectional and also a cardioid microphone element. Almost any type of electret condenser microphone capsule could be used, but it may be wise to experiment with different types to find the one that provides the most satisfactory output level and sound quality. A directional cardioid type may improve audio quality compared to an omnidirectional type as the directionality may help reduce background noise - though the orientation of a cardioid microphone is quite critical.

In my final design I favoured the cardioid capsule fixed to a piece of fairly thick insulated copper wire extracted from some twin & earth mains cable to form a simple 'home brew' goose-neck. The copper wire 'goose-neck' is attached between the sun visor hinge and grab handle mounting point by simply twisting it neatly in place. All straightforward and very cheap to accomplish. I have received favourable audio reports with the mic in this position. In M6ORS's car the short goose-neck wire is simply twisted around the grab handle mounting and forms a very neat microphone - shown below.

Note: If using a cardioid type, the rear of the capsule should remain open and unobstructed to maintain good sound quality and the directional effect. A 1nF capacitor is fitted across the two terminals to reduce the possibility of RF feedback.

A suitable length of thin screened audio cable is connected to the microphone and is terminated in a 3.5mm stereo Jack plug (audio/power to tip and ground to top, larger, ring). The cable is run from the microphone, concealed behind the door rubber surround, routed under the seat, then concealed under the edge of the centre console and finally connected to the Interface Unit which is mounted under the dashboard.


1nF capacitor
Thick insulated copper wire
Screened audio cable
9.7mm electret microphone insert
www.mds975.co.uk
MØMTJ

Cardioid electret condenser microphone element fixed to the short wire boom.
Note: if using a cardioid type, the rear of the capsule should remain open and unobstructed.



Detail: Showing how the small 9.7mm diameter electret condenser microphone element is taped onto the short wire boom which is made from a piece of Twin & Earth wire. Also shows the 1nF capacitor.
Note: if using a cardioid type, the rear of the capsule should remain open and unobstructed.

Push To Talk Switch

I found a small ABS enclosure measuring 75mm x 50mm x 20mm and fitted a non-locking button (on-off switch) and a locking (SPST) toggle switch to it. The locking toggle switch can be used for longer overs, while the non-locking button can be used for brief overs.

The two switches are wired together and connected to a suitable length of thin screened audio cable terminated in a 2.5mm Jack plug which is plugged into the Interface Unit.

The PTT switch box can be mounted onto the dashboard, centre console with a sticky pad or BluTac or to the gear lever with a re-usable nylon cable tie or Velcro type cable tie.

Time Out Timer - TOT

If using a locking switch it would be a very wise precaution to set the Time Out Timer (TOT) on the rig to a suitable interval. I set the TOT on my radio to 5 minutes.



PTT Switch mounted onto centre console with BluTac - MØMTJ



PTT switch attached to gear lever using a velcro cable tie.
Hands free microphone interface unit can also be seen - MØMTJ



Hands free microphone interface unit mounted underneath dashboard using a re-usable cable tie from SotaBeams MØMTJ

Using An Electret Microphone Capsule Element

My first attempt at connecting an electret condenser microphone to the FT-7900 had mixed results. I used the standard method of powering the electret microphone element using the 8 volts supplied from the transceiver via Pin 3 of the modular connector. This was fed via a 2.2k Ohm resistor to the capsule. The audio was fed back to Pin 5 via a DC blocking capacitor of 0.47μF. The audio was fine, but with perhaps a little too much bass prominence, but this could easily be adjusted by reducing the value of the DC blocking, coupling capacitor C5002 in the Yaesu diagram. However there was a noticeable amount of background noise that was absent when using the MH-48 microphone with the FT-7900.

It was obvious that the additional filtering and de-coupling components that are included in the MH-48 microphone circuit, which are shown in the Yaesu MIC-UNIT schematic at the foot of this page, are essential for clean audio so these are included in the final circuit and should not be omitted.

After building up the circuit, using the components specified in the MH-48 microphone (minus R5016 and C5009 which are unspecified), the audio was clean with the background noise now absent.

cardioid electret microphone insert, 2 terminal. ESR 201-025 http://www.esr.co.uk **Specifications:**	
Frequency Response	100 - 16kHz
Sensitivity	3.2mV/Pa/1kHz
Load Resistor	680Ω
SNR	>60dB
Coupling Capacitor	0.1-4.7μF
Power Supply	1.5 - 10VDC (0.5mA)
Dimensions	5 x 9.7mmØ

omnidirectional electret microphone insert, 2 terminal. ESR 201-018 & 201-019 **Specifications:**	
Frequency Response	50 - 16kHz
Sensitivity	7.9mV/Pa/1kHz
Load Resistor	2.2kΩ
SNR	>58dB
Coupling Capacitor	0.1 - 4.7μF
Power Supply	1.5 - 10VDC (0.5mA)
Dimensions	6.7 x 9.7mmØ

The Hands Free Microphone and PTT Interface Unit
Basic version for FT-857 & FT-897 and similar transceivers

A small interface box allows an electret condenser microphone and different types of PTT switches to be connected to the transceiver. The interface box contains the necessary circuitry to allow these to work efficiently with the radio.

Two jack sockets allow the connection of the microphone and PTT switch. A 3.5mm stereo jack socket is used to connect the electret microphone, while a 2.5mm mono jack socket is for the PTT switch. Two different sizes of jack sockets are used in order to help prevent reversing the two connectors with unwanted consequences.

The use of a stereo 3.5mm socket ensures that a microphone fitted with either a mono or stereo jack plug can be used. If a mono jack socket is used there could be a chance that a microphone with a stereo type plug would not work, or perhaps the chance of an unwanted short circuit. Using a stereo jack socket avoids this doubt.

The simple circuit shown below. The best value for the capacitor * may be found by a little experimentation. Try values between 0.47μF and 0.047μF. I find that a value of 0.22μF or 0.1μF is the most suitable for the FT-857D for example.

The current drawn should be less than 5mA. Most transceivers with power to the microphone socket can supply up to 10mA. A low current LED could be included to indicate power on, as long as the current draw is minimised to a couple of milliamps - with the LED that I used a current limiting resistor of 4.7k to achieve this. Measure with a good multimeter or AVO.

N.B. PTT Circuit: For many radios, such as the FT-857 & FT-897, the IN4148 and 15k resistor (specified in the FT-7900) should be omitted.


MØMTJ
Basic hands free microphone interface circuit
2.5mm
IN 4148
15K
PTT
Audio output
0.047µF *
0.1µF
1.8K
2.2K
+ve
IN4001
1K
3.5mm
ZENER
0.001 µF
100pF
0.001 µF
+
4.7 µF
Ground

Basic microphone interface circuit - non amplified version that should be good for most purposes

* 0.47µF, 0.22µF or 0.1µF or 0.047µF.



Stripboard break positions viewed from top



Stripboard break positions viewed from underside





The non amplified hands-free microphone interface circuit under construction.
The layout of all the necessary components can be seen.
This one will be for the Icom ID-5100 -
See Projects Page 12 for the ID-5100 specific information >>

* Coupling capacitor is 0.33µF (the blue component shown just above the 4.7µF electrolytic capacitor)
(I have installed 4.7k resistor, located just to the right of the 1N4007 diode, in readiness for the inclusion of an LED power indicator, although the LED was not initially installed. The resistor would be used to reduce the current draw)



Another version of the Hands Free Electret Condenser Microphone Interface

* Coupling capacitor is 0.22µF

(The l.e.d. power indicator is connected via 4.7k resistor to reduce the current draw)

This non-amplified version is for a Yaesu FT-857

Powering The Electret Condenser Microphone

As mentioned above, an electret condenser microphone element requires a DC voltage to operate. In the diagram above it can be seen that this voltage is fed from the positive supply via the 2.2k, 1.8k and 1k resistors. A Zener diode is also included to set the voltage supplied to the microphone element. I happened to have a 4.3V zener diode in the resource receptacle ('junk box') so I used that, which is fine as the the electret microphone elements that I used could operate up to 10 volts while PC type headsets may be designed with up to about 5 Volts in mind.

This DC voltage must also be blocked from the audio output, this is accomplished by the capacitor * that feeds the audio to the transceiver (marked as C2 above, C5002 in the Yaesu schematic, and with a red asterisk * in the finalised diagram below). The audio is fed to pin 2 of the NE5534 operational amplifier via a 2.2k resistor. This capacitor can also be adjusted in value to tailor and improve the audio a little:

Increasing the value will tend to increase the response to bass frequencies, while reducing it will reduce the response. Initially I used a value of 1µF but there was rather too much bass response apparent. Reducing the value to 0.33µF improved the audio quality, but it still wasn't quite as crisp as that produced by the Yaesu MH-48. This was probably due to the different type of capsule used and that it was not enclosed in a housing. Audio quality was much improved when using a value of 0.047µF. Experimentation is encouraged to find the most appropriate value for individual circumstances - try values between 0.47µF and 0.047µF. See 'more about the simple filter below.

In the final circuit I settled upon a value of 0.047µF (47nF). It was also very noticeable that when the omnidirectional microphone capsule was placed in a small enclosure - even cupped hands - that the audio quality immediately sharpened up. If using an Omnidirectional capsule try sliding it into the tube of a large felt tip pen of the same diameter, just 1 or 2 millimeters at a time and notice how the audio quality changes. It *may* have a beneficial effect on audio quality. However, I found the effect with a cardioid microphone capsule to be entirely detrimental so that was abandoned.

The audio output level from the electret condenser element should be sufficient for most transceivers when used close. The FT-857 / 897 should have the Mic Gain level backed right down to about 20, otherwise the transmitted audio will be over-modulated / over-deviated and distorted. For a distant mic (sun visor), the FT-857 / 897 may need the Mic Gain set to about 50 to 80 - dependent upon distance.

Microphone Connector Detail - RJ45 Modular Plug

Shown below is the wiring arrangement for the modular microphone connector used in the Yaesu FT-857 FT-897 FT-817 FT-450 FT-900



Yaesu FT-857 FT-897 FT-817 FT-450 FT-900 Microphone plug connector
Reference G3WPW : http://www.qsl.net/g4wpw/date.html



Yaesu FT-857 FT-897 FT-817 FT-450 FT-900 Microphone plug socket
Reference G3WPW : http://www.qsl.net/g4wpw/date.html

PIN1 = Fast Scan
PIN2 = Ground
PIN3 = PTT
PIN4 = MIC
PIN5 = MIC Ground
PIN6 = + 5Volt
PIN7 = UP
PIN8 = Down

More microphone Pin-Outs and wiring diagrams here: http://www.qsl.net/g4wpw/date.html

ICOM Wiring Scheme

I use the basic (non amplified) interface, as described above, with my Icom IC-706mk2g with good results and no problems. However for interest and completeness, I have included the circuit diagram for a typical Icom electret condenser microphone. In this case, the Icom HM-103.

Therefore, if you prefer, you could build the electret condenser interface to the circuit shown below. I have not (at this stage anyway) included any physical board or wiring layout or details - so that would be up to you to devise!


•HM-103 SCHEMATIC DIAGRAM
MICROPHONE
2k
MICROPHONE CABLE
MICROPHONE PLUG
10μ
4700p
0.33μ
MIC ELEMENT
4700p
2.2k
12345678
DOWN
UP
470
PTT
RECEIVE
TRANSMIT

Microphone Connector Detail - RJ12 / 6P6C Modular Plug

Shown below is the wiring arrangement for the modular microphone connector used in the Yaesu FT-7900 / FT-7800 / FT1500 / FT1802 / FT1900 / FT2800 / FT-2900 / FT8800 / FT8900.

For wiring arrangements for your transceiver, or other transceivers consult your operators manual or G4WPW's website here:
http://www.qsl.net/g4wpw/date.html


RJ11 TYPE
6 PIN MODULAR SOCKET
g4wpw
1 2 3 4 5 6
VIEW FROM FRONT OF TRANCEIVER

Yaesu MH-48 microphone plug connections for Yaesu FT-7900 / FT-7800 / FT1500 / FT1802 / FT1900 / FT2800 / FT-2900 / FT8800 / FT8900
Connection information from G4WPW
http://www.qsl.net/g4wpw/date.html

PIN 1 = SW2 (Yaesu colour green)
PIN 2 = SW1 (Yaesu colour brown)
PIN 3 = +8 VOLTS (Yaesu colour red)
PIN 4 = GROUND (outer screen / shield braid)
PIN 5 = MIC (Yaesu colour white)
PIN 6 = PTT (Yaesu colour blue)

On these Yaesu radios the Mic and PTT share a common ground, so if you run a single ground wire between the

radio and the interface unit it will be shared to both the PTT switching circuit and the microphone ground.
I used the shield of the cable as the ground conductor.

On some of the interface units that I have produced, I fitted a round mic socket using the Kenwood wiring scheme so that
the interface unit could be used with different radios - connected by specifically made, interchangeable, connecting cables.

* * * * * * * * * * * * * * * * *

Additional Amplifier

The Hands Free Microphone Interface Unit with additional microphone amplification - for FT-7800, FT-7900 etc

Again, as above, a small interface box allows any electret condenser microphone (not dynamic unless the electret powering is removed or blocked) and different types of PTT switches to be connected to the transceiver. The interface box contains the necessary circuitry to allow these to work efficiently with the radio together. *In this case there is the addition of a simple microphone pre-amplifier.*

As above, a 3.5mm stereo jack socket is used to connect the electret microphone, and a 2.5mm mono jack socket is used for the connection of the PTT switch.

The use of a stereo 3.5mm socket ensures that a microphone fitted with either a mono or stereo jack plug can be used. If a mono jack socket is used there could be a chance that a microphone with a stereo type plug would not work, or perhaps the chance of an unwanted short circuit. Using a stereo jack socket avoids this doubt.

Microphone Amplifier

Having tried a number of electret microphone elements I found that the audio volume was adequate on the FT-7900 when holding the mic at a distance of about 3 or 4 centimeters without amplification - similar to the volume supplied by the Yaesu MH-48 microphone.

When using the mic on a short boom or a microphone on a small ear hook headphone, this placed the microphone several centimeters further from the mouth. This noticeably reduced the audio volume available. In this case I felt it necessary to include the option of switching in two levels of amplification; one for a close mic and one for a more distant mic - although with a more distant microphone this would also amplify background noise. The amplification was accomplished using a simple operational amplifier circuit.

The op-amp circuit shown below worked very well. The value of C2 and C3 were chosen so that low frequency audio was not too excessive. I also chose a modest amount of gain, this being set by the values of R1 and R2 i.e:
22,000 Ohms ÷ 2,200 Ohms = gain of 10 x



A simple microphone amplifier using an NE5534 or equivalent Op-Amp
Needs to be used in conjunction with the electret condenser microphone circuit - see below

Powering The Electret Condenser Microphone

See above

Audio level

The level of the amplified audio is adjusted with the 1k preset potentiometer. This can be connected directly to the audio wire of the modular plug. However I also included a switch so that the amplifier could be switched out of circuit for when additional audio amplification is not needed - i.e. when the microphone is more closely positioned microphone.

The finalised schematic circuit diagrams below which show what is required in the way of electronic components for the complete circuit including the switch.

RF Feedback !

This circuit is suitable for FM rigs such as the FT-7800 and FT-7900 where the microphone is placed at some distance, such as on the sun visor and the additional audio amplification and low audio frequency cut off is useful. However when using with the FT-857 / 897 in an amplitude modulated mode (AM or SSB) there is the probability that the op-amp will pick up RF and cause feedback 'howl-around; severely deteriorating the audio.

In fact the FT-857 / 897 has plentiful audio gain, so the additional audio amplification is not only not required it is not desirable. The 'in / out' switch therefore allows the unit to be used with two different transceivers if required - i.e. with the microphone amplifier 'in circuit' when an FM rig is used, and 'out of circuit' when using an FT-857 / 897 or similar.

Incorporating Radio Frequency Chokes (RFC's) on the microphone input jack socket can help reduce RF feedback. Try using an RFC on both the audio connection to the circuit board and the ground connection. RFC's could also be added at the output of the operational amplifier.

Clip On Ferrites - If required, I have found that clip on ferrites to match the diameter of the connecting cable can work very well at reducing or eliminating RF feedback problems, acting as an RF Choke. More traditional ferrite rings could also be used.

Clip on ferrite chokes

FT-857 / 897 Audio Gain

Even without the additional amplifier, the output from the electret condenser microphone will be more than sufficient for a Yaesu FT-857 / FT-897 as these rigs have high microphone gain due to the standard hand held microphone being a lower output dynamic type which requires more amplification.

The FT-857 / 897 should therefore have the Mic Gain level backed right down to about 20, otherwise the transmitted audio will be over-modulated / over-deviated and distorted. For a more distant mic (sun visor), the FT-857 / 897 may need the Mic Gain set to about 50 to 80 - dependent upon distance.

In / Out Switching

The audio from the microphone can be routed directly to the transceiver's microphone plug (e.g. terminal 5 for the FT-7900 or terminal 4 for the FT-857 / 897) or, alternatively, to pin 2 of the NE5534 operational amplifier via a 2.2k resistor to add amplification, and then on to the microphone plug.



Schematic Circuit Diagram showing the original microphone interface. Op Amp is NE5534.

Click to enlarge

* 0.47μF, 0.22μF or 0.1μF or 0.047μF.

N.B. PTT Circuit: For some radios the 1N4148 and 15k resistor (specified in the FT-7900 and similar rigs) should be omitted.

The current drawn should be around 8mA or less. Most transceivers with power to the microphone socket can supply up to 10mA. A low current LED could be included to indicate power on, as long as the current draw is minimised to a couple of milliamps or less - with the LED that I used a current limiting resistor of 4.7k to achieve this. Measure with a good multimeter or AVO.

Layout

The sketch below shows the layout of all the components on a piece of 9 hole x 25 hole stripboard (Veroboard).

The ground wire "GND" is connected to the shield braid of the microphone cable which is connected to the microphone plug (For example, pin 4 of the FT-7900 modular plug or pin 5 of the FT-857 / 897 mic plug).


Microphone Interface Circuit - M0MTJ
PTT 2.5mm SOCKET
DIODE
15K
PTT
NE5534
+VE
1N4001
22K
22K
0.1uF
1K
1.8K
2.2K
0.1uF
A
B
2.2K
22K
1
2
3
4
8
7
6
5
C
0.47 uF
0.001 uF
100pF
ZENER
4.7 uF
0.001 uF
10 uF
1K
GND
3.5mm SOCKET mic GND
3.5mm SOCKET mic
A
C
Audio out to TXVR
B
Switch detail
Audio out to TXVR
C
B
A
M0MTJ

The PTT ground is connected directly between 2.5mm jack socket & output cable to microphone socket

Sketch showing the original stripboard layout of microphone interface
click to enlarge


3.5mm Stereo Plug Microphone
Ground
Audio & Power
Mic Amp Switch
In
Out
2.5mm Mono Plug PTT Switch
Modular Plug
Shield braid connected to Pin 4 of plug
M0MTJ

Layout of the hands free mobile microphone interface showing modular plug for a Yaesu FT-7900 - M0MTJ



Component Layout



Stripboard break positions viewed from top



Stripboard break positions viewed from underside

More About The Simple Filter *

When working mobile there will inevitably be a lot of low frequency noise and rumble; the correct value of this high-pass (i.e. low cut) filter will aid in reducing this part of the noise spectrum so that the low frequency noise does not overwhelm the transmission. I chose a roll off point of around 1.5 kHz.

C2 and R1 form a simple first order high pass input filter. A first order filter will reduce the amplitude of the signal by 6db (power reduces by half) every octave (halving or doubling of frequency) - that is -20dB per decade (factor of 10 of frequency). Using a value of 0.047μF (47nF) for capacitor * with the 2.2k Ohm resistor gives a gentle filter slope with a -3dB low frequency cut off point of 1539 Hz.

fc = 1/(2πRC) Where fc is cut-off frequency in Hertz, R is resistance in Ohms and C capacitance is in Farads. (1μF = 0.000001F)

0.047μF capacitor: 1 ÷ (2 x 3.14 x 2200 Ohms x 0.000000047 Farads) = 1539 Hertz

0.1μF capacitor: 1 ÷ (2 x 3.14 x 2200 Ohms x 0.0000001 Farads) = 723 Hertz

0.22μF capacitor: 1 ÷ (2 x 3.14 x 2200 Ohms x 0.00000022 Farads) = 329 Hertz

0.47μF capacitor: 1 ÷ (2 x 3.14 x 2200 Ohms x 0.00000047 Farads) = 154 Hertz



Hands Free Microphone Interface with interchangeable microphone connection cable to facilitate connection to different transceivers: On some of the interface units that I have produced, I fitted a round mic socket using the Kenwood wiring scheme so that the interface unit could be used with different radios - connected by specifically made, interchangeable, connecting cables.

This unit has In / Out switching and an l.e.d. power indicator (via 4.7k resistor)
* Coupling capacitor is 0.22µF



Hands Free Microphone Interface
Built for use with a Yaesu FT7800 / FT7900 or FT-857

Parts Required For The Complete Interface

Parts List
Microphone and PTT Circuit
http://www.bowood-electronics.co.uk

Electret Condenser Microphone Insert / Capsule to
produce microphone or boom of individual design.
Rubberised electret microphone holder if required
OR
PC Headset of choice with electret mic

Small ABS Enclosure
Stripboard / Veroboard
Non locking on-off push switch / button for PTT
Housing for PTT switch / button
SPST (on-off) switch for locking PTT
Modular plug 6 conductor (6P6C / RJ12)
Multi-core (3 or 4) screened mic cable
Thin screened audio cable
1 x 3.5mm Stereo Jack Plug
1 x 3.5mm Stereo Jack Socket
1 x 2.5mm Mono Jack Plug
1x 2.5mm Mono Jack Socket
1 x 8 pin male chassis mount microphone connector (optional if removable cable is required)
1 x 8 pin female in-line microphone connector (optional if removable cable is required)

Semiconductors

1N4001 Diode
4.3v Zener Diode
1N4148 Diode (Not required for some radios such as FT-857 / FT-897 / FT817 etc)

Multilayer Resin Dipped Ceramic Capacitors
1 x 100pF (101) - C5001
3 x 0.001µF (102) - C5005, C5006 & C5008
1 x 0.1µF (104) - C5003
1 x 0.047µF (473) or 0.1µF (104) or 0.22µF (224) - C5002 (C2) - see text

Electrolytic Capacitors
1 x 4.7µF 35v

Resistors
1 x 1.0k Ohm - R5003
1 x 1.8k Ohm - R5002
1 x 2.2k Ohm - R5001
1 x 15k Ohm - R5017 (Not required for some radios such as FT-857 / FT-897 / FT817 etc)

Parts for Microphone Amplifier Stage

http://www.bowood-electronics.co.uk

DPDT Switch (for In / Out selection)
DIL Socket for the Op Amp I.C.
Hook up wire
(Stripboard / Veroboard)

Semiconductors
NE5534 Op Amp (or TL071CN or UA741CN etc)

Multilayer Resin Dipped Ceramic Capacitors
1 x 0.1µF (104)
1 x 0.47µF (474)
1 x 0.047µF (473) or 0.1µF (104) or 0.22µF (224) - see text

Electrolytic Capacitors
1 x 10µF 35 Volt

Resistors
1 x 2.2k Ohm
3 x 22k Ohm
1 x 1k Ohm Preset Potentiometers (VR1)

Total Cost for the parts:
Approximately £15.00 for 'basic' interface without PTT Switch box (Including approx postage cost)
Approximately £20.00 for 'basic' interface with PTT switch box and 4 metre long mic cable. (Including approx postage cost)
Approximately £22.00 for 'amplified' interface with PTT switch box. (Including approx postage cost)

Many equivalent or similar components may already be in the 'junk box' which could give a significant cost saving.
(March 2013)

Components available from Bowood Electronics:

Bowood Electronics

www.bowood-electronics.co.uk


MØMTJ
HIGH LOW
MØMTJ
MIC
PTT
www.mds975.co.uk

Hands free microphone interface unit - MØMTJ


PC Internet type headset microphone / earphone
(Only the mic jack plug is shown)
MØMTJ

Further Refinements ?

The other feature that could be considered for inclusion could be an integral Time Out Timer, perhaps a switch based on a 555 timer.

For The Icom ID-5100 Hands Free Microphone Interface -
Please see Projects Page 12 here >>

Alternative Level Switching Arrangement


MØMTJ
Microphone interface circuit diagram
1N4148
15K
2·5mm
⑥
PTT
2·2K
0·047µF *
0·1µF
③
+VE
2·2K
22K
1N4001
1·8K
47K
3·5mm
1K
2
7
6
3
4
ZENER
+
0·001 µF
100pF
0·001 µF
4·7 µF
10µF
22K
1K
0·1µF
⑤
Output
④
GND

Microphone Interface - Schematic Circuit Diagram. Op Amp is NE5534. (For FT-7900)
Click to enlarge

N.B. PTT Circuit: For some radios the 1N4148 and 15k resistor (specified in the FT-7900 and similar rigs) should be omitted.

Switching

Shown below is the detail of the switching that can be included to provide the option of two amplification levels, for a close mic and a distant mic. This should be suitable for FM only rigs, but for multi-mode rigs (e.g. FT-857 / 897) the better method which can route the audio directly from the microphone, bypassing the amplifier, is shown above.


MØMTJ
Optional switching arrangement for audio level adjustment
Ⓒ
0·1µF
⑤
Output
2
7
6
3
4
Ⓐ
Ⓑ
1K
VR1
1K
0·1µF
VR2
Ground
④

Alternative switching arrangement that I used on one version



Stripboard hole positions viewed from top



Stripboard hole positions viewed from underside


MØMTJ
Microphone interface circuit layout
PTT 2·5mm SOCKET
DIODE
15K
⑥ PTT
NE5534
③ +VE
1N4001
47K
22K
0·047µF
0·1µF
1k
1·8K
2·2K
2·2K
22K
ZENER
100pF
0·001 µF
4·7 µF
0·001 µF
10 µF
1 2 3 4
8 7 6 5
④ GND
A
B
C
0·1 µF
1K
3·5mm SOCKET MIC GND
2·5mm SOCKET GROUND
3·5mm SOCKET MIC
B
C
A
⑤ Output
DPDT switch
VR2
0·1µF
1k

Sketch showing the stripboard layout of microphone interface (for FT-7900)
click to enlarge

N.B. PTT Circuit: For some radios the 1N4148 and 15k resistor (specified in the FT-7900) should be omitted.


www.mds975.co.uk
1K 220
MØMTJ

Component Layout


MØMTJ Hands free microphone interface unit
High level
Low level
HIGH LOW
MØMTJ
Modular plug
Hot glue
2.5mm PTT & 3.5mm Mic sockets
Multi-core shielded microphone cable
www.mds975.co.uk

Hands Free Mobile Microphone Interface Unit - MØMTJ

Bowood Electronics

References

See the relevant parts of Yaesu's schematic diagrams below:


J5001
P0090400
SW2
SW1
8V
GND
MIC
PTT
1
2
3
4
5
6
MIC-UNIT
R5001
2.2K
C5002
0.33 35V
R5002
1.8K
C5003
0.1 35V
R5003
1k
MC5001
EM-125L
C5006
0.001 B
D5008
DTZ2.0A
R5016
***
C5004
4.7 16V
C5005
0.001 B
C5001
100p CH
C5009
***
C5008
0.001 B
C5011
***

Yaesu MH-48 microphone - Audio section
(**Note**: I omitted the unspecified components R5016 and C5009)
(C5002 should be changed to a 0.047µF [473] capacitor - although a value up to 0.1µF [104] could be depending the amount of LF roll-off desired)


N5090036
S5002
N6090051
LOCK SW
3
2
1
JP5001
JP5002
JP5003
JP5004
JP5005
PTT
S5005
N7090127
R5017
15K
D5009
BAS316

Yaesu MH-48 microphone - PTT section

“Anyone who has never made a mistake has never tried anything new.” - *Albert Einstein*

> Back to the Main Projects Page <

Projects 1 | Projects 2 | Projects 3 | Projects 4 | Projects 5 | Projects 6 | Projects 7 | Projects 8 | Projects 9 | Projects 10 | Projects 11 | Projects 12

top of page ^

Bowood Electronics

Links to Electronic Component Suppliers >>

ESP - Elliott Sound Products

Elliott Sound Products
ESP, the home of DIY audio articles, projects and shortform kits.
Professional results for the Do-It-Yourself enthusiast

DISCLAIMER: If you attempt any of these projects proceed with due caution with regard your own safety, the safety of others and the safety of the equipment that you are working with!

I cannot be held responsible for any accidents, injuries or damage caused to any equipment that may result, howsoever caused.

M0MTJ | Operating Conditions | Antennas / Aerials | /P Portable Operating | Accessories | Projects & Kits | Useful Information

Contact MØMTJ | Contact M6ORS | Links to Amateur Radio Sites | RSGB | QSL | The Amateur Radio Mini Site Map

WSPR Weak Signal Propagation Reporter | Operating in Cyprus | All Latest Site Updates

News, Developments, Events, Photographs and other 'Bits 'n' Bobs'

MDS975 Home

Feedback

MAIL

Mike Smith - MDS975.co.uk © 2003 - 2017

M0MTJ

Ivan M6IAH / 2E0OUK Rich M6CQC / 2E0UKR

A 40m through 17m Mini End Fed Half Wave Antenna Coupler

Steve Yates - AA5TB


17m
20m
30m
40m
Short
Long


T-50-2
Core
5k Ω
Output
(Antenna)
50Ω
Input
(Rig)
20-160 pF
Polyvaricon
Primary
3 turns
24 AWG
Secondary
28 turns
24 AWG

HOME

E-mail
Last Update: January 5, 2010

A few years ago I built a little Rock-Mite transceiver for 40m. Since I enjoy using End Fed Half Wave antennas so much I built a small coupler to use with my Rock-Mite. The coupler converts the high impedance end of the End Fed Half Wave antenna down to 50 ohms. Since my unit was to be used in the field I wanted the option to forego using coax cable altogether. In the end, I ended up with a convenient little coupler that easily transforms the high impedance down to 50 and works from 40m all the way to 17m with only a single adjustment. It mounts directly to the rear of the transceiver.

As you can see by the above photo I used an old Pomona enclosure that I had laying around. The Pomona box originally had a jack BNC connector on one end and a plug BNC on the other. For this application I removed the jack and installed a banana plug jack. The coupler mounts directly to the rear of the rig via the BNC plug and the End Fed Half Wave antenna connects directly to the banana jack.

The circuit uses a 20 to 160 pF "polyvaricons" variable capacitor and a T-50-2 core wound with 28 turns of AWG 24 enameled wire for the secondary winding with one 3 turns of AWG 24 for the primary winding and shown in this photo. This works out to an impedance transformation of 50 ohms to 4356 ohms. I was trying for a 10:1 turns ratio but I optimized the secondary's number of turns so that the parallel tuned circuit would resonate in a more centered part of the capacitor's tuning range. It is hard to get 2.8 turns on the primary ;-)

Using the my favorite adjustment method I marked on the dial with a resistive match should occur at every band. When connected to an antenna, if the lowest SWR (peak noise on receive) doesn't occur at the predetermined point on the dial then the antenna is either too short or too long. A low SWR can still be achieved but common mode current (RF on the rig, operator, etc.) will be probable and everything you touch will cause the SWR to change. When things are properly adjusted this will not occur. If you are nervous about it go ahead and attach your favorite "counterpoise" to this coupler but my experience is that if the coupler and antenna are adjusted properly a discrete "counterpoise" isn't required due to the return side of this coupler being connected to the rig and accessories. Little current flows through the "counterpoise" when the antenna is resonant unless the "counterpoise" approaches 1/2 wave length itself.

In regards to loss, I connected two similar couplers end-to-end at 20m and measured a loss of 0.97dB. This equates to less then 0.5dB per coupler. Here is how I did it:

First, I connected the high impedance ends of the coupler on this page to those on my 20m coupler. I measured the transmitter power at 5W on 14.050 MHz without the couplers as shown here using my power meter and dummy load combo. Next, I inserted the two couplers into the line has shown here and measured the power again. This time I measured 4W. This calculates to a total of 0.97dB. Granted, my instruments are not lab grade or metrology calibrated devices but I am confident in the data based on comparisons that I have made in the past to such high grade instruments.

Related Links

- A Portable Station for 30 Metres - VA3RR shares his experience with the End Fed Half Wave Antenna (EFHWA) and coupler losses at the bottom of his page.
- Mitsumi Polyvaricons
- Polyvaricon Caps - Hendricks QRP Kits



40m through 17m End Fed Half Wave Antenna Coupler built by AA5TB


0.05 λ
C
End Fed Half Wavelength Antenna
"Counterpoise" Return
Secondary
Primary
50 Ω
Coaxial
Cable

WAX Group Version of the
40m through 17m End Fed Half Wave Antenna Coupler
With LED SWR Indicator

[RockMite40]



In the above schematic diagram, the Tayloe N7VE SWR kit from Hendricks QRP Kits http://www.qrpkits.com/swrindicator.html is connected between the transceiver and the Steve Yates AA5TB end fed half wave antenna coupler http://www.aa5tb.com/coupler2.html . Moving from right-to-left in the circuit:

- The half wave antenna wire is connected to the terminal labeled “5K ohm output (antenna)”. This is the red banana jack located on the top end of the Altoids box.
- The counterpoise (from the black banana jack located on the bottom end of the Altoids box) is connected to the “triangle symbol” ground point of the coupler circuit. This same ground is shared by the LED SWR bridge. The enclosure is also grounded by the BNC connector to this point.
- The 50 ohm output of the antenna coupler is connected to the “ANT” input of the LED SWR bridge circuit board.
- The points labeled “TX” on the LED SWR board connect to the BNC connector (located on the bottom end of the Altoids box). This is jumpered to the transceiver with a short piece of RG-58 coax with BNC connectors on both ends.

On the 40m band, for operation on 7030 and 7040 KHz:

- The antenna wire is 0.5 wavelengths long, or approximately 66 feet 6 inches long.
- The counterpoise wire is 0.05 wavelengths long, or approximately 7 foot 8 inches long.

Note that these lengths are for bare (un-insulated wire) – insulated wire may have to be shortened by as much as 2% to be resonant. Connect a 4K7 resistor to the antenna/ground terminals and adjust coupler for proper match. Next attach antenna and counterpoise, and adjust length of antenna until a proper match is obtained (without touching the tuning capacitor). The length of the counterpoise is not as critical.

A High Efficiency Rectenna Element using E-pHEMT Technology

C. Gómez, José A. García, A. Mediavilla, and A. Tazón.

Universidad de Cantabria. Dpto. Ing. Comunicaciones. Avda. Los Castros s/n, 39005 Santander, SPAIN.
Phone: (+34) 942 200918. Fax: (+34) 942 201488. Email: carmen@dicom.unican.es

Abstract — **In this paper, a high-efficiency rectifying antenna (rectenna) element, based on a novel E-pHEMT detector, is proposed. The slightly positive threshold voltage in this technology, allows its use on resistive detectors without applying an auxiliary gate bias. Based on an adequate selection of the DC load resistor, as well as the drain and gate impedance conditions, the losses on the RF to DC conversion process are reduced. A high gain aperture coupled patch is finally designed, assuring optimum impedance values at the fundamental and second harmonic. Using a rectenna loading of *47Ω*, a *85.4%* measured overall efficiency is achieved.**

I. INTRODUCTION

The rectenna term was first proposed by Brown in [1]. It consists of a receiving antenna combined with a rectifying circuit, which converts RF or microwave power into useful DC power. The rectenna is a key element in wireless power transmission systems, deserving a lot of attention by the community during the last years.

Applications include, among others, the reception of a microwave beam sent to the earth by a geostationary solar power satellite [2], distributed DC powering of actuators [3], or DC supplying of RFID passive tags [4]. In all the cases, the RF to DC conversion efficiency is the figure to improve, over the range of incident power or output voltage of interest. Different solutions have been reported, mainly based on combining dipole or patch printed elements [5, 6] with diode detectors.

Different FET detector circuits have been proposed based on the R_{ds} nonlinearity [7]. However, these solutions have not found application in rectenna elements, mainly due to the need for using an auxiliary DC gate biasing voltage in order to obtain a good conversion result.

In this paper, the use of an Enhancement mode Pseudomorphic High Electron Mobility Transistor (E-pHEMT) in a rectenna is proposed. Due to its slightly positive threshold voltage, high conversion efficiency is possible for an unbiased detector topology.

First of all, a brief analysis of the E-pHEMT behavior as a detector is presented, based on an accurate characterization of the device main nonlinearity. Then, details on the design of a highly efficient detector circuit are discussed, paying particular attention to the DC load value, as well as to the gate and drain optimum impedance conditions. Finally, a rectenna element is proposed, combining the results of the referred detector with a high gain aperture coupled linearly polarized patch.

II. SIMPLIFIED ANALYSIS OF THE E-PHEMT NONLINEAR CHARACTERISTICS

E-pHEMT devices are normally-off FET transistors. A small positive gate to source voltage is required to form a conducting channel between drain and source terminals, as can be easily appreciated from the I/V characteristic of a typical device, plotted in Fig. 1.



Fig. 1. $I_{DS}(V_{GS}, V_{DS})$ measured characteristic for an ATF-54143 E-pHEMT from Agilent Semiconductors.

Although care has to be taken with other nonlinear elements, the drain current source, $I_{ds}(V_{gs}, V_{ds})$, is the predominant factor determining the behavior of this kind of devices, while kept under normal operating conditions. A Taylor-series expansion of this nonlinearity up to the second order, around the biasing point, may help us introduce the particularities of an E-pHEMT behavior as a detector, at least when the applied RF excitation is small.

$$\begin{aligned} I_{ds}\left(V_{gs}, V_{ds}\right) &= I_{DS}\left(V_{GS}, V_{DS}\right) + G_m v_{gs} + \\ &+ G_{ds} v_{ds} + G_{m2} v_{gs}^2 + G_{md} v_{gs} v_{ds} + G_{d2} v_{ds}^2 + \dots \end{aligned} \tag{1}$$

In (1), the transconductance G_m and the output conductance G_{ds} represent the I_{ds} partial derivatives with the V_{gs} and V_{ds} control voltages, respectively. On the other hand, G_{m2}, G_{md} and G_{d2} are the input, cross and output second order coefficients.

Using a FET device for RF to DC conversion implies working the transistor without applying any external DC drain to source bias [7]. In such a condition, considering the device as approximately unilateral, a small RF voltage applied between drain and source terminals, v_{ds}, would be efficiently converted to a DC drain to source current if the corresponding second order term were maximum.

$$G_{d2} = \frac{1}{2}\cdot\frac{\partial G_{ds}}{\partial V_{ds}}\bigg|_{V_{GS},V_{DS}} = \max \qquad (2)$$

For higher input RF excitations, a Taylor-series description up to the second order becomes inadequate. A better figure could be then provided by substituting the G_{d2} value at the initial condition, by the average value of the same coefficient all along the excursion imposed by the sinusoidal excitation, $\overline{G_{d2}(t)}_{RF}$.

The G_{d2} coefficient has a peak when a FET device is biased at the pinch-off or threshold voltage. Once the RF input power is increased, the maximum value of the $\overline{G_{d2}(t)}_{RF}$ coefficient widens, being usually shifted towards lower values.

In normal depletion type of devices, being the pinch-off voltage a negative quantity, a negative DC auxiliary voltage in gate terminal is always needed for assuring an optimum conversion. This fact makes depletion devices inappropriate for rectennas.

In an E-pHEMT device, however, the threshold voltage is slightly positive. Following the typical $\overline{G_{d2}(t)}_{RF}$ evolution with the input power, its maximum might be expected to appear at $V_{GS} = 0V$ for moderate power levels. This analysis was made for an ATF-54143, using the experimentally extracted G_{d2} Taylor-series term. In Fig. 2, the measured G_{d2} value and the computed $\overline{G_{d2}(t)}_{RF}$ behavior are plotted, as a function of V_{GS} for different input power levels. For low power levels, both terms coincide. For higher power values, the movement of the optimum conversion point from the threshold voltage to $V_{GS} = 0V$ is easily appreciated.



Fig. 2. Measured G_{d2} value and computed $\overline{G_{d2}(t)}_{RF}$ evolution with V_{GS} and P_{in} for $V_{DS} = 0\ V$.

III. DETECTOR DESIGN

Based on the above simplified analysis, an E-pHEMT detector was designed at the *900 MHz* band, using the topology shown in Fig. 3.

A. Drain and Gate Impedances

The role of the impedance condition on the conversion efficiency was first evaluated, both at drain and gate terminals.

A directional coupler was placed between the RF port and the detector to measure the reflected RF power. In this way, the influence of $Z_d(2fo)$, $Z_d(3fo)$ and $Z_g(fo)$ could be studied in equality of conditions through the use of the net conversion efficiency [6].

$$\eta_c = \frac{\text{DC output power}}{\text{incident RF power} - \text{reflected RF power}} \qquad (3)$$

The drain impedance at the second harmonic was then adjusted, being significant its contribution to the efficiency figure. As it could be expected from previous diode works [5], the maximum was obtained for a small reactance value near a short-circuit. Such a reactance was implemented through a high Q series LC combination, see Fig. 3.

The effect of higher harmonics was also tested. The third harmonic drain impedance influence, however, was not as appreciable as the second one. As the best condition was found to be a very high reactive value, it was decided to use an open-circuit instead.

In the case of gate side, only the influence of the fundamental impedance was considerable. In this case, also a reactive value was found to be optimum, a value that resonates with the gate impedance of the transistor equivalent circuit. This reactance was assured through the use of a high Q coil, L_G. It is responsible for reflecting back all the incident power that could appear at gate terminal due to the feedback elements in the device equivalent circuit (R_s, C_{gd}).



Fig. 3. Schematic of the E-pHEMT detector circuit.

B. DC Load Resistance

The optimum DC load value was also searched for, trying to maximize efficiency. The results for different load resistances, in the best range, are shown in Fig. 4.



Fig. 4. Net efficiency for several R_L values.

The existence of an optimum value between *47 Ω* and *56 Ω* is evident. An increase of *Pin* above *10 dBm* resulted, however, in a reduction of the efficiency.

C. Impedance Matching.

Finally, with the optimum values for $Z_d(2fo)$, $Z_g(fo)$ and R_L, the input reflection coefficient was measured. A simple matching network was then added to transform to *50 Ω*, using a series coil at drain terminal L_D. Including this element, the maximum obtained overall efficiency, η_o, was of *73.2 %* at P_{in} = *10.5 dBm*, being this parameter defined as is shown in (4).

$$\eta_o = \frac{\text{DC output power}}{\text{incident RF power}} \tag{4}$$

This value could even be improved, if designing an antenna whose $Z_a(fo)$ were the conjugate of the detector impedance, while $Z_a(2fo)$ were resonant with the drain circuit. Thus, the losses in the employed lumped elements would be avoided.

IV. 900 MHZ ANTENNA DESIGN

An ACMSA (aperture coupling microstrip antenna) [8] was selected for the rectenna design, due to its potential to work with active circuits. In the classical solution, the input impedance is controlled by the size, shape, and position of the aperture, while its excess reactance can be compensated for by varying the length of the open-circuited stub. Another stub was added in our design, so that the 2^{nd} harmonic impedance could be also adjusted.

Apart from assuring the appropriate load conditions, the antenna should provide a high gain. In this kind of radiator, this is possible when using a low permittivity material as radiator substrate. In order to use air permittivity, an inverted type of patch was employed [9].

The radiation from the detector may be also kept under control, thanks to the ground plane separating the circuit and the patch substrates.

The impedances at the fundamental and 2^{nd} harmonic were *47 + j5 Ω* and *2.5 + j28 Ω*, respectively, with a *|S11(fo)|* of *–25 dB* and a bandwidth of *45 MHz*. The gain was also measured, reaching a value of *9 dB*.

In Fig. 5, plots of the measured real and imaginary values for the designed antenna impedance are shown.



Fig. 5. Real and imaginary parts of the antenna impedance.

V. RECTENNA MEASUREMENTS

The rectenna (FET rectifier + antenna) was finally implemented. The detector circuit was inserted in the feed side of the previously designed antenna. The detector RF input port was located just in the place where the impedances at the fundamental and 2^{nd} harmonic frequencies were optimum for its conversion efficiency.

Fig. 6 shows a photograph of the rectenna, with a zoom made over the E-pHEMT detector part. In order to guarantee a minimum error in the efficiency computation, a port for having access to the received power was also included.



Fig. 6. Photograph of the E-pHEMT based rectenna.

In Fig. 7, the measured rectenna overall efficiency is plotted.

A highest value of *85.4%* overall efficiency was obtained at an input power level as low as *11.5 dBm*. This value is competitive with the figures obtained from diodes. Being able of obtaining a high efficiency for a small input power level, the power to be transmitted may be reduced or the operating distance may be increased.



Fig. 7. Measured rectenna overall efficiency vs. the received power.

VI. CONCLUSION

A novel high efficiency rectifying antenna, using E-pHEMT technology, has been developed. The particularities of the device nonlinear behavior have been used to implement an unbiased transistor detector. A high gain patch has been designed, also providing the optimum impedance conditions for maximum conversion efficiency. The proposed rectenna provides a maximum efficiency of *85.4%* at *900 MHz* with an input power of *14.12 mW*.

ACKNOWLEDGEMENT

The authors would like to thank the Spanish Ministry of Science and Technology (MCyT) by the financial support provided through project TIC 2002-04084-C03-03, as well as the European Commission assistance through TARGET Network of Excellence. J. A. Garcia is finally grateful to the Ramón y Cajal Program from MCyT.

REFERENCES

[1] W. C. Brown et al., *U. S. Patent 3 434 678*, Mar. 25, 1969.
[2] W. C. Brown, “Status of the Microwave Power Transmission Components for the Solar Power Satellite,” *IEEE Trans. Microwave Theory Tech.,* vol. MTT-29, no. 12, pp. 1319-1327, Dec. 1981.
[3] L. W. Epp, A. R. Khan, H. K. Smith, and R. P. Smith, “A compact dual-polarized 8.51-GHz rectenna for high voltage (50 V) actuator applications,” *IEEE Trans. Microwave Theory Tech.,* vol. 48, no. 1, pp. 111-120, Jan. 2000.
[4] B. Strassner, and K. Chang, “Passive 5.8-GHz radio-frequency identification tag for monitoring oil drill pipe,”, *IEEE Trans. Microwave Theory Tech.,* vol. 51, no. 2, pp. 356-363, Feb. 2003.
[5] T. Yoo, J. McSpadden, and K. Chang, “35 GHz rectenna implemented with a patch and a microstrip dipole antenna,” *IEEE MTT-S Int. Microwave Symp.*, pp. 345-348, June 1992.
[6] J. McSpadden, L. Fan, and K. Chang, “Design and experiments of a high-conversion-efficiency 5.8-GHz rectenna,” *IEEE Trans. Microwave Theory Tech.,* vol. 46, no. 12, pp. 2053-2060, Dec. 1998.
[7] F. Carrez, and R. Stolle, “Novel low-cost, low-power modulator/demodulator using a single GaAs field effect transistor”, *IEE Proc. Cicuits Devices Syst.*, vol. 145, no. 3, pp. 165-169, June 1998.
[8] D. M. Pozar, “Microstrip Antenna Aperture Coupled to a Microstrip Line,” *Elect. Lett.,* vol.21, no.2, pp. 49-50, 1985.
[9] J. F. Zurcher, “The SSFIP: a global concept for high-performance broadband planar antennas,” Elect. Lett., vol. 24, no. 23, pp. 1433-1435, 1988.

PIXIE II



built by WA6OTP

This is my first attempt at the pixie II.
This 330 milli watt transceiver was introduced
to me by WE6W, ED and I built it to see how it works.....
Boy does it... fun!

This rig has worked,
ND6T, W6DVO, W5NUI, WE6W, KK7GR, KB7UMO, W6ARK,
WR6C, WA6CW, KB6BYU, WI6O, K6TBW, KW6AR, N6JUG,
WN6HYX, KV6G.

QRP IS FUN RADIO

Pixie Schematic
Pixie Schematic in PDF

Parts List

Return To Our Home Page

Amateur Radio MØMTJ

MDS975.co.uk HOME PAGE

My Home Page

Amateur Radio
Operating Conditions
Antennas
Accessories
Projects & Kits
Data Modes
Information
Portable
QSL
RSGB Ltd
Links
QRM
Bits 'n' Bobs
Contact

WSPR
Weak Signal Propagation Reporter

PORTABLE

Site Map

MDS975 Home

Feedback

PLT QRM

Site Search

☐

Find

powered by FreeFind

M0MTJ | Operating Conditions | Antennas / Aerials | /P Portable Operating | Accessories | Projects & Kits
Useful Information | Contact MØMTJ | Contact M6ORS | Links to Amateur Radio Sites
RSGB | QSL | The Amateur Radio Mini Site Map
News, Developments, Events, Photographs and other 'Bits 'n' Bobs' | WSPR Weak Signal Propagation Reporter

AERIALS (ANTENNAS) 7

Antennas 1 | Antennas 2 | Antennas 3 | Antennas 4 | Antennas 5 | Antennas 6 | Antennas 7

Index To Other Antenna Pages:
Antennas 1 : Aerials used by M0MTJ
Antennas 2 : Including ideas for compact antennas for Top Band /160 metres
Antennas 3 : Felix Scerri VK4FUQ discusses Loop Antennas, baluns, masts & other antenna related topics
Antennas 4 : Many antenna ideas from various sources particularly for multi-band operation & also gives information about
antenna trimming, knots for wire antennas and useful antenna rigging accessory ideas.
Antennas 5 : Half Wave End Fed antennas for 144 MHz VHF / 430 MHz UHF and 50 MHz 6 Metre band & J-Pole Aerials
Antennas 6 : Simple and effective H.F. Antenna ideas - Ground Plane and the All Band Doublet Aerial
Antennas 7 : Experimental Omni-Directional - Circularly (Mixed) Polarized Antenna for VHF / 2 Meters.

"Everything should be made as simple as possible, but not simpler." - *Albert Einstein*

MØMTJ - Experimental (Almost) Omni-Directional - Circularly (Mixed) Polarized Antenna for 144 MHz / VHF / 2 Meters.



Introduction and Background

This is an experimental project that may lead to further development in the future, but even as presented below, it does work and may prove very useful.

I have therefore included this page of information so that you may can construct the aerial and develop these ideas further - either just out of interest and for the sake good old traditional Amateur Radio experimentation or for more permanent and practical uses!

The idea was sparked by the fact that I had been toying with the idea of removing the rotator and dual-band horizontal Yagi from my lightweight push-up aluminium mast to reduce mass and visual impact. I certainly did not want to lose access to the horizontally polarized portions of the 2 Metre (144 MHz) or 70cms (432 MHz) bands, so decided upon trying an Omni-Directional, horizontally polarized aerial.

The question was which antenna would I use to replace the rotatable dual-band Yagi?

Due to the weight of the rotator, the lightweight aluminium mast could not safely be pushed up higher than about 6 meters. Therefore, the Yagi on the stub mast was never much higher than 6 or 7 metres above the ground. A lighter weight omnidirectional aerial, without the heavy rotator, would allow the past to be pushed up to, perhaps, 8 or 9 meters. Maybe even to its full 10 meters on a fine day!

My thinking is that this additional height may compensate slightly for the loss of gain from the Yagi. The additional height would also benefit my vertical Coaxial Dipole for 6 Meters (50 MHz) which sits at the top of this mast. A small bonus.

I decided that I would try simple Halo antennas (HAlf wave LOop) and Big Wheel antennas for 2 Meters and 70cms.

Circularly Polarized, Omnidirectional Antenna for VHF 2 Meters / 144 MHz

.
However, before embarking on those particular experiments and possible future changes, I wanted to experiment with mixed polarization, or more correctly in this case, Circular Polarization - the subject of this project and article.

Why? - Well, when the IBA (Independent Broadcasting Authority) began building transmitters for their Independent Local Radio (ILR) in 1973, they specified that mixed polarized aerials should be used used at each of their VHF/FM transmitter sites, starting with Croydon for LBC and Capital Radio in London, then Black Hill for Radio Clyde in Glasgow and Lichfield for BRMB in Birmingham and the many other sites that followed. The aerial systems were either described as "Mixed", "Slant" or "Circular".

The reason that mixed polarization was chosen was to improve reception on car radios and portable radios that generally used a vertical or slanted telescopic rod aerial. The BBC, at the time, used horizontal polarization for VHF/FM radio which was good for permanently installed roof-top receiving aerials, but provided poorer reception for listeners with portable sets and car radios. Some years later the BBC followed the IBA and began converting that majority of their transmitter sites to mixed polarization to improve reception and reduce mobile 'flutter' effects.

I thought that I would like to experiment with mixed polarisation and took some inspiration from some of the more recent, and simpler, antennas that have been installed at commercial radio ("ILR") transmitter sites. Two examples are shown below, both from the Radio Wave transmitter site at Blackpool Tower. The original aerial and its more recent replacement.



Original SBS transmitting aerial for
Radio Wave Blackpool 96.5 MHz
Photo from MB21.co.uk



The newer antenna viewed from below
Photo from MB21.co.uk

What's Needed

4 x 500mm lengths of 4mm diameter aluminium rod
2 x Dipole Centres

G Whip Antenna Products
Get on the air with TOP QUALITY BRITISH G-WHIP ANTENNAS

6 x Solder Tags with 3mm diameter hole
2 x Dipole Mounting Boxes - e.g. IP54 85 x 45 x 40mm
2 x Stainless Steel Nuts, Bolts and Washers M4 x 20mm
2 x Stainless Steel Nuts, Bolts and Washers M4 x 14mm
4 x Stainless Steel Self Tapping Screws No. 4 (2.9mm) diameter by 9.5mm long
1 meter of 20mm or 25mm Diameter PVC Pipe
8 x Pipe Clamps to suit diameter of boom and diameter of supporting mast
4 x Stainless Steel Nuts, Bolts and Washers
2 x End Caps to suit diameter of PVC boom (i.e. either 20mm or 25mm)
1 x SO239 Chassis Mount Socket
500mm length of small diameter coaxial cable, e.g. RG188 A / U - 50 Ohms PTFE coaxial cable
1 x piece of PVC tube for choke balun - 16mm diameter x 30mm long
1 x length of coaxial cable for phasing section
Some small self tapping screws to fix the pipe clamps to the boom

These items will be available from many and various sources, but Nuxcom is a good supplier - http://shop.nuxcom.de/

The antennas essentially comprise of two Crossed Dipoles, set a 90 degrees from each other. In the first photo, the antenna can be seen to have one dipole positioned vertically and the other horizontally. The second photograph shows that the to dipoles are again set at right angles, but one slopes 45 / 225 degrees and the other at 315 / 135 degrees.

The two dipoles are connected to each other, but have to be fed with the current to each dipole 90 degrees out of phase. This is called phase quadrature. It is a very common method used for other types of antenna, such as the Turnstile which is often used for communication with satellites where circular polarization must be used.

One dipole is connected directly to the coaxial cable. (I used Westflex 103 coaxial cable, for lowest loss, to feed the antenna). The second dipole has to be fed via a 1/4 wave (90 degrees) matching section. I had an off-cut of RG58, so used this for my initial experiment.

A quarter wave at 145.00 MHz is 300 / 145 = 2.068m / 4 = 51.7 cm. However the Velocity Factor (VF) of the cable has to be taken into account because radio waves travel more slowly through transmission lines than the do through free space.

Ideally I should have measured the VF with my antenna analyzer, however I took the typical VF of RG58 as being 0.66. So 51.7cm x 0.66 = 34.1cm. I cut the cable to 34.1 cm and used this to connect the two dipoles together.

Initially I cut the 4mm diameter aluminium rod into four 50cm long pieces and mounted them into the two dipole mounting boxes using the Nuxcom Dipole Centres. A small hole has to be very carefully drilled into the end of each rod to align with the fixing hole of the dipole centre. Then very carefully screw the 2.9mm stainless steel self tapping screws into each hole being sure not break off the head of the screws. When tapping these holes it is best to ease back and forth until the hole is successfully tapped.

The dipole centres and pipe clamps are fixed to the box with the 20mm diameter M4 hex bolts, washers and nuts.

The second pipe clamp is fixed to the box with the 14mm long M4 stainless steel hex bolt, washer and nut.

Each mounting box is fixed to the boom by clipping on the pipe clamp. The two dipoles are mounted at right angles (90 degrees) to each other, approximately 335mm apart. Once the final adjustments have been made and the positions along the boom are decided, the clamps are held firmly in place by screwing them to the boom, as can be seen in the photographs below.

Each dipole is then carefully bent into a semi-circle.

The SO239 socket is then fitted to the box and the choke balun is wound and one end of the coaxial cable soldered to the socket and the other end fitted with the solder tags. The small 2.9mm x 9.5mm stainless steel self tapping screws are then used to fix the tags to the dipole centre.

Now connect this dipole to an antenna analyzer (or SWR meter) and check the point of resonance. I decided to centre the aerial on 144.3 MHz. Almost certainly the dipole will be too long. I had to cut off 1mm of rod from each end.

Once complete, do the same for the other dipole so that they are exactly the same size.

Next, the phasing cable is prepared, as mentioned above. A suitable diameter hole is drilled in the end of the box opposite the SO239 socket and the phasing cable passed through this and soldered on to the two tags, as can be seen in the photograph below.

A similar small hole is then drilled into the other dipole mounting box and the other end of the phasing coaxial cable is passed through this, two solder tags are soldered on to the end and then fixed into place on the dipole centre using the small self tapping screws.

Now connect the antenna analyzer again, using a few metres of low loss coaxial cable, and mount the antenna in some free space, preferably outside on a pole about two or three metres above the ground a. It will almost certainly be found that the point of resonance is now two low, so each dipole will now need to be carefully trimmed, cutting small and equal amounts off each of the four ends until the point of resonance is around 144.3 MHz.

It should be possible to obtain an SWR of 1.5:1 or less across the 2 Meter band - to achieve this it may be necessary to move one of the dipole mounting boxes further away, or closer together to the other. Also, it may be necessary to bend the dipole rod of each dipole element inwards, or outwards slightly. I was able to achieve an SWR of 1:1 with an impedance of 50 Ohms according to the antenna analyzer.

Once the adjustment were complete, I used 20 meters of Westflex 103 to connect the antenna to the Icom IC-706 mk2g. A similar length of the same cable is used to connect the 5 element horizontal Yagi to the radio. A low loss coaxial switch was used to make instand comparisons between each antenna.

I raised the experimental antenna to 8 meters above ground level on the telescopic pole and began to make some comparisons.

My guess was that the experimental omni-directional circular polarized antenna would be noticeably inferior to the much higher gain, horizontal, directional Yagi.

The Yagi has a quoted gain of 8.4dDBd (i.e. gain with reference to a standard dipole - not dBi).

A standard straight dipole has a gain of 0 dBd. However if it used horizontally and is bent into a circle to produce a roughly omni-directional radiation pattern, then the gain must be reduced, so I assumed that the 'gain' must now be negative, perhaps -1 or -2 dBd.

Additionally, being as this is a circularly (mixed) polarised antenna, the power is essentially divided in half across the horizontal plane and the vertical plane. i.e. another 'loss' of 3dBd.

Therefore the gain of the antenna may be assumed to be -5dBd (minus 5 dBd), i.e. about 1 S point down on a simple straight linearly polarized aerial and about 13 dBd down compared to the Yagi - i.e. about 2 or 3 S points worse.

Here, at my QTH in Staffordshire, the Kent beacon on 144.430MHz on my 5 element Yagi is just audible, although there is no S Meter reading. I therefore did not expect to be able to hear it on the experimental antenna as it is so weak, but to my surprise, the beacon was still there - obviously a bit weaker, but still audible. That was an encouraging start!

I therefore went ahead and made some QSO's with other stations who were using both vertical and horizontal polarization and also made some comparisons purely on receive.

I therefore went ahead and made some QSO's with other stations who were using both vertical and horizontal polarization and also made some comparisons purely on receive.

I haven't recorded enough data to draw truly meaningful conclusions. It's not scientific either. However, my impression from what I have recorded and from other general use is that the performance is broadly in line with my expectations - i.e. about 2 or 3 S points, or around 12dB, down on the Yagi.

Station	**Location**	**QSO or RX**	**Mode**	**Other station's Aerial**	**Rprt Sent (Yagi)**	**Rprt Rec'd (Yagi)**	**Rprt Sent (Omni)**	**Rprt Rec'd (Omni)**
G3XEV	Sedgley	QSO	SSB	V2000 Vertical	S2-3	S7	S6-7	S7
2W0JYN	Rhos	QSO	SSB	3 Ele Horiz Yagi	S6	S9	S5	S7
2W0JYN	Rhos	QSO	SSB	Vertical Colinear	S1	S1	S0	S0
G8WEG	SW B'Ham	RX	FM	Unknown (Vert?)	N/A	N/A	S9+20	N/A
MW0WML/p	GWNW012	QSO	FM	Vertical Dipole	N/A	N/A	S9+10	S8
G7HEM	Stourbridge	QSO	SSB	6 Ele Horiz Yagi	S7	S9	S2	S3
N/K	Burton	RX	SSB	Unknown (Horiz?)	S9	N/A	S5	N/A

With particular thanks for John G3XEV and Steven 2W0JYN for their assistance with these initial tests!

I hope this information is useful and may encourage you to experiment further and make some much better scientific comparisons!

If you have any comments, please do email them to me via the contact page here.



Detail showing the inside of the first dipole mounting box with SO239 socket and choke balun

Nuxcom Dipole Centre for 4 mm dipole rods
10 mm space between dipole rods
Three holes: One in the middle for fixing the box on the boom. The other two for connecting the cable to the dipole rods.
Length: 36 mm
Space in the between rods: 10 mm
Outer diameter: 8.4 mm
Inner diameter: 4,1 mm
Material: Polyamid
http://shop.nuxcom.de/



Detail showing the inside of the second dipole mounting box



Detail showing how the dipole mounting box is fixed to the plastic pipe with pipe clamps and firmly secured in place with small self tapping screws.



Right angled mast to boom clamp made from four plastic pipe clamps



Right angled mast to boom clamp made from four plastic pipe clamps



Antenna under initial test and adjustment at approximately 2 metres a.g.l.
The coaxial cable is low loss Westflex 103
(My HF Doublet antenna, fed with open wire balanced line can be seen in the background on the left)


MFJ
POWER
144.29 MHz 1.0
R= 50 X= 2 SWR
MFJ HF/VHF SWR ANALYZER
MODEL MFJ-259B
SWR
IMPEDANCE
GATE
MODE
27-70
10-27
70-114
4-10
114-170
1.8-4
TUNE
FREQUENCY
MHz
MØMTJ

After adjustment to element lengths and dipole positions along the boom arm, the antenna shows a good match.




MØMTJ


MØMTJ


MØMTJ


MØMTJ



The Test 'Rig' comprised of a heavy duty Spiderbeam 12m fibreglass telescopic pole with the antenna mounted approximately 8 meters a.g.l.

If you have any comments, please do email them to me via the contact page here.

Antennas 1 | Antennas 2 | Antennas 3 | Antennas 4 | Antennas 5 | Antennas 6 | Antennas 7



SOTA Beams
Lightweight 2 metre &
70cms Yagis, Dipole,

G Whip
Antenna
Products

G-Whip Antenna Products
Get on the air with
TOP QUALITY
BRITISH
G-WHIP
ANTENNAS
End Fed Zepps and
many more designs
and products

Accessories & Poles
www.sotabeams.co.uk

PLA-PLT Latest News
Keep up-to-date on this important issue

Radio Interference?:
PLT & PLA: Radio Interference
British Telecom, BT Home Plug
P C World, Powerline Adapters
YouView, Belkin Linksys
Netgear Devolo, BT Vision - BPL
Radio Interference
PLT Page 1

Antennas 1 | Antennas 2 | Antennas 3 | Antennas 4 | Antennas 5 | Antennas 6

Top of page ^

M0MTJ | Operating Conditions | Antennas / Aerials | /P Portable Operating | Accessories | Projects & Kits | Useful Information

Contact MØMTJ | Contact M6ORS | Links to Amateur Radio Sites | RSGB | QSL | The Amateur Radio Mini Site Map

WSPR Weak Signal Propagation Reporter

News, Developments, Events, Photographs and other 'Bits 'n' Bobs'

MDS975 Home

Feedback

Mike Smith - MDS975.co.uk © 2003 - 2016

M0MTJ

Amateur Radio; Ham Radio; Radio; Ground Plane Vertical; Sloper; HF Antenna; Dipole;
Doublet; Antenna - The Best Multi-Band Antenna for Easiest Construction, Quickest Deployment and Lowest Cost

Amateur Radio MØMTJ

MDS975.co.uk HOME PAGE

My Home Page

Amateur Radio Operating Conditions
Antennas
Accessories
Projects & Kits
Data Modes
Information
Portable
QSL
RSGB Ltd
Links
QRM
Bits 'n' Bobs
Contact

WSPR
Weak Signal Propagation Reporter

PORTABLE

Site Map

MDS975 Home

Feedback

QRM from PLT

Site Search

Find

powered by FreeFind

M0MTJ | Operating Conditions | Antennas / Aerials | /P Portable Operating | Accessories | Projects & Kits | Useful Information
Contact MØMTJ | Contact M6ORS | Links to Amateur Radio Sites | RSGB | QSL | The Amateur Radio Mini Site Map
News, Developments, Events, Photographs and other 'Bits 'n' Bobs' | WSPR Weak Signal Propagation Reporter

"Everything should be made as simple as possible, but not simpler." - *Albert Einstein*

AERIALS (ANTENNAS) 4 - Notes and Queries

Antennas 1 | **Antennas 2** | **Antennas 3** | **Antennas 5** | **Antennas 6** | **Antennas 7**

Index To Other Antenna Pages:
Antennas 1 : Aerials used by M0MTJ
Antennas 2 : Including ideas for compact aerials for Top Band /160 metres
Antennas 3 : Felix Scerri VK4FUQ discusses Loop Antennas, baluns, masts & other antenna related topics
Antennas 4 : Many antenna ideas from various sources particularly for Multi-Band operation & also gives information about...
antenna trimming, knots for wire antennas and useful antenna rigging accessory ideas.
Antennas 5 : Half Wave End Fed antennas for 144 MHz VHF / 430 MHz UHF and 50 MHz 6 Metre band & J-Pole Aerials
Antennas 6 : Simple and effective H.F. Antenna ideas - Ground Plane and All Band Doublet
Antennas 7 : Omni-Directional - Circularly (Mixed) Polarized Antenna for VHF / 2 Meters.

Multi Band Aerial Options | Useful Aerial Rigging Accessories | Aerial Trimming Chart | Useful Knots | A few antenna related Links

As G4ILO notes: An antenna may have two of the attributes: Small; Efficient or Broadband (works over a wide frequency range without retuning) but never all three.

Marconi spins in his grave every time a ham buys an aerial instead of building it ! *(W1GFH)*

THE QUEST FOR MULTI - BAND OPERATION - In A Limited Space

The aerial is arguably the most important part of any station. No matter what transceiver is being used it is the aerial that is the last and most vital link in the chain and needs to be efficient and effective to radiate the signal to best best effect. Some amateurs are quite content to operate on one or two bands while others might want to be able to operate on many or even all of the amateur HF bands. When I gained my licence I definitely fell into the latter camp!

It seems, then, that the holy grail of many amateurs is the perfect multi-band aerial!

Luckily N4UJW has designed a new limited space 160m through to 70cm marvel antenna the plans of which can be found here:
http://www.hamuniverse.com/antwish.html

Having experimented with various types of antenna I am of the opinion that, perhaps along with many other amateurs, for simplicity a resonant dipole is the most efficient and effective of aerial. A resonant dipole it is only a single band aerial of course, but it is extremely cheap and very simple to make - and it's a very efficient radiator. So one could make a dipole for every band of interest and simply swap aerials to work different individual bands. Unfortunately the aerial described by N4UJW does not exist and compromises, such as lack of bandwidth or poor radiation efficiency, have to be made.

The principal of lowering a dipole cut for one band, removing it and hoisting another dipole cut for a different band in to place sounds pretty straightforward, but would the process become frustrating after a while. I think it could, so what about an antenna that will allow operation on several bands?

G Whip Antenna Products
G-WHIP
Antenna Products
Top Quality
British Manufacture

The Quest For A Multi - Band Aerial

Here is a collection of commercial and 'home brew' (DIY) antenna ideas that will allow multi-band operation, many of which could also be used in a location that offers limited space. Perhaps this only scratches the surface, but hopefully will provide a good starting point and fuel the mind in a quest for a good multi-band HF aerial. Do check out the manufacturer and supplier websites given on this page for lots more options and details.

Home Brew! It has been said that no radio amateur should ever buy an aerial - especially a wire aerial! Joe Tyburczy WB1GFH also comments about suitable antenna installing weather on his web pages:

"When you put up your antenna is also crucial. I must mention here the importance of what many early hams called "antenna weather". That is, snow, sleet, freezing rain, or combination of all the above. It has been proven time and time again that any antenna installed in conditions better than abysmal will not function worth a darn. Or, put another way, it takes bad weather to put up a decent antenna. Dark and cold New England winter days are ideal for this activity. Any antenna erected on such a day will inevitably produce miracles." Joe Tyburczy WB1GFH

Most of what is available commercially could be 'home-brewed' if one has the time and a few suitable mechanical skills.

It's worth bearing in mind that Joe Tyburczy's $4.00 Special may well be more effective than a commercial antenna costing $400.00. Perhaps the equally inexpensive Zepp Antenna could produce far greater Value For Money than shelling out £$hundreds on a commercial antenna?

I give no particular recommendation here, but a good rule of thumb is not to believe the marketing hype of any commercial company supplying antennas.

A good place to start is, I think, the classic All Band Doublet Antenna, which is mentioned several times below. Plenty of links are also provide further down this page.

As important as not believing any of the marketing hype is remembering the words of the Star Ship Enterprise's Chief Engineer Mongomery Scott; (paraphrasing) *You cannae change the laws of physics!* - Size matters. A coil loaded 5 foot long aerial probably won't be that much good on the H.F. bands. Indeed, a a 5 meter long antenna may be perfect for the 10 metre band but it won't be a great antenna on 20m, and certainly even less effective on 40m and 80m

So, before falling for all the marketing hyperbole its wise to read up on a little antenna theory and do some lengthy research into the antennas being considered before making an expensive decision.

Below are a few clues and ideas listed in no particular order - some of the antennas will be great while some of the commercial designs shown below may promise great things but fail to meet high expectations.

There is no "miracle antenna". If one understands the theory and the compromises made with shortened, under-sized, multi-band (and often very expensive) antennas there may not be so much disappointment. However most will be compromised in one way or another, so if one is happy to live with those compromises, understand what they mean, and are happy to have a lighter bank balance then that's fine!

Low SWR across all the bands does not indicate a good antenna. My dummy load has very low SWR across all the bands but it is most certainly not a good antenna!

Someone telling you that the antenna that they're using is great and that they've worked the world doesn't mean it really is a good antenna - it's just 'hearsay'. One could quite possibly work around the globe on a coat hanger in the right conditions - it doesn't suddenly make a coat hanger the great antenna that should be widely heralded!

The best way to learn about antennas is to go out and make some - well actually go out and make many antennas.

Here are a few ideas. Some that are easily 'home brewed' and some commercial ideas that could be adapted to 'home brewing'. I don't have any particular recommendation, but I hope that this list will provide some good food for thought. (Some of the commercial antennas may be okay, some may be awful).

Remember; ***Marconi spins in his grave every time a radio amateur buys an aerial instead of building it !***

The Doublet Antenna - the classic all band / multi-band Aerial

The Doublet Antenna is my favourite Multi-Band aerial. The main benefits of a Doublet Antenna are that it can be used on whatever frequency it is cut for, and higher frequencies. Usefully, there can be some useful gain on higher frequencies, although there will be some petal shaped lobes on the higher frequency bands.

In fact my 20 meter long Doublet for the 40meter band to the 6 metre band also works quite well on 80 meters! Not only a very good starter antenna for those looking to work as many bands as possible, but also an aerial that would be useful and efficient for years and years to come.

Ladder line or open wire feeder must be used (NOT coaxial cable). Ladder Line or open wire ensures low loss at High Frequencies so that as much of your precious transmitter power as possible will be radiated. Likewise receive efficiency should be maximized. Assuming that the aerial is successfully balanced, the feeder should not radiate, even when there is (inevitably) high SWR

High SWR is not an especially bad thing and will not reduce the aerial's performance, but note that high SWR on the balanced feeder does increase feeder loss compared to a when matched - but the losses will be a lot less significant then if coaxial cable were to be used. This ensures that efficiency should be better so that all the power that reaches the antenna wires will be radiated - save for any losses in the antenna tuning unit (AMU) or the balanced feeder cable.

Remember: Ladder Line = Lower Loss - Read more about my M0MTJ Doublet Antenna HERE >> and more notes on this page here >>



The Classic All Band DOUBLET ANTENNA - Read More about my M0MTJ All Band Doublet Aerial Here >>>

The G5RV and more about Doublets & Dipoles

The G5RV - (Even Louis Varney himself said that a Doublet would be better!)

Why the G5RV continues to remain popular is a mystery. The 'legendary' name, perhaps? That it can be 'thrown up' without too much thought? The fact that it' cheap and cheerful? Well, cheap anyway. There has been much written about the G5RV and the overall conclusion is that it's not a very good multi-band antenna. Certainly it will work quite well on, perhaps, a couple of bands, but there are better alternatives, especially when one considers the wide availability of remote automatic antenna matching units (remote auto 'a.t.u.'s) that will greatly assist in minimizing antenna feeder losses.

Perhaps the best thing that can be done with a G5RV is cut off the coax, re-size the top wires and turn it into a true Doublet Antenna - or, better than that, don't buy a G5RV in the first place and simply make (home brew) a true All Band HF Balanced Doublet Antenna.

The G5RV and its derivatives such as the Western HF-10 and the ZS6BKW are a bodge. In fact, Louis Varney G5VA himseld stated that a much better alternative to any of these 'G5RV' designs is to run the open-wire line from the center of a dipole all the way to a balanced antenna tuner!! This aerial arrangement will work on ANY band from 80 metres through to 10 meters.

The G5RV is, therefore, not the most efficient aerial and, as users report, may not always be the easiest to use, but because it is coax fed, it remains an ever popular choice because it's easy to feed the coax cable from the antenna's location back to the shack. Unfortunately this easy (lazy?) approach means lots of loss due to high SWR on the coaxial cable.

One may say, Oh well, there's perhaps only 2 or 3 S points in it. (Cough!). A difference of 3 S points is the difference between radiating 100 watts or only radiating 1.6 watts. Um, - I'm sure we'd soon complain if our shiny, new 100 watt transceiver only produced 1.6 watts!!

QRP and lower power portable operators should be especially keen to minimize antenna system losses so that as much power as possible is radiated. Losing 3 S points from a 5 watt FT-817 results in only 0.08 watts. QRP operators may likely favour resonant, single band antennas for greatest efficiency.

Coaxial Cable is only 'low loss' when the antenna impedance is similar to the cable's designed impedance of 50 Ohms, or near 1:1 SWR (or at least less than 2:1). Coax cable is therefore fine for a Dipole antenna that is designed to be resonant on one band of choice, which will have a reasonably low SWR across that band, but coax' is entirely unsuitable when one wants to use the aerial on several bands. The G5RV will be used an multiple bands and will therefore present widely varying impedance values (and SWR) depending on the band of operation and so the power losses will be significant.

Note: The antenna's true impedance (SWR) must be measured at the antenna's feed point (i.e outside and up in the air) not at the radio end of the cable, in the shack, where the coaxial cable's losses will mask the true SWR reading. Unfortunately 50 Ohms, or a near 1:1 match, will not be encountered on any band on a G5RV. The best band will be 20 metres at typically 2:1 (100 Ohms), but on any other band the impedance will be very much higher. One might expect rersults like these: 80 metres 3:1 to 5:1, 40 meters 5:1, 30 metres 20:1 or more, 17 metres 15:1 or more, 15 metres 6:1 to 12:1, 12 meters 3:1, 10 meters 10:1 to 20:1.

1000 Ohms into 50 Ohm coaxial cable will result in a massive dumping of your power - lost as heat in the coaxial cable instead of being radiated as a useful signal. However, high SWR is not in itself a bad thing - it's just that the correct type of feeder and impedance transformation method needs to be used. The *incorrect* feeder is coaxial cable - the correct type of feeder is balanced Line or Ladder Line feeder. This can be the typical slotted 300 Ohm type or the 450 Ohm 'window line' which are commercially available. Even better, make your own open wire, balanced line feeder. Spacers can be bought commercially or 'home brewed'. The spacing for this parallel line should be about 2 to 3 inches (50 to 80 mm) - the width of the spacing is not particularly critical, but whatever width is chosen should be maintained as accurately as possible along the length of the feeder - i.e. it should be parallel.

The Doublet can take more time and effort to tune, prune and adjust. It will also need a good antenna matching unit (so-called "ATU") and low loss balun, but the reward will be more effective performance due to the much reduced loss in the balanced line feeder system.

Doublet Aerials - a better alternative to a G5RV

Check out the The classic All Band Doublet and the NorCal Doublet for very simple, effective and versatile antennas for multi band operation:

The ALL BAND Doublet Antenna

This could very well be the first antenna that one should try in order to get on at least one band very efficiently but also several other bands with the use of a good ATU.


80 Meter Multiband Doublet
With Open Wire Feed
Covers 80 Thru 10 Meters
12 - 14 Gauge stranded harddrawn wire
Total length, insulator to insulator, about 130 feet. Not Critical!
Feed with 600, 450, or 300 ohm open wire, (ladder or window type) any length to shack to tuner. NOT COAX!
Mount in any configeration as high as possible. NOTE: 130 foot length can be doubled for 160 meter operation.
Center and end insulators and strain relief can be homebrew or purchased.
See next picture below for alternate shack entry details
N4UJW

All Band Doublet - http://www.hamuniverse.com
See My All Band Doublet Antenna here

The all band Doublet antenna is nothing more than a 1/2 wave dipole cut for your lowest operating frequency and fed with twin lead, ladder line, open wire, etc to a tuner that will accept a balanced line connection. IT MUST NOT BE FED WITH COAXIAL CABLE !

It can be designed for use from 160 through to 10 meters very easily using the standard 1/2 wave dipole formula:

468/freq MHz = total length (ft)
The exact length is not critical!

If there is insufficient room for a lower frequency version (160m or 80m), then the Doublet can be designed to the shorter wavelength of the 40 metre band and used up to the 10 metre band. (Do not attempt to operate on a lower frequency than 7 MHz in that case since this could damage the a.t.u.) It may be possible to connect the ends together and tune it against earth - if you have a good enough earth - and use lower frequency bands. For best results a doublet should be mounted as high as possible (as with many aerials) and can be erected as a flat top or inverted V.

A Doublet Antenna needs a good antenna matching unit with a wide impedance matching range (obviously not the one in the radio!). Preferably this should be a balanced antenna matching unit, but an unbalanced matching unit can also be used together with a good low loss current / Guanella balun, such as the extremely high quality items available from G-Whip Antennas. I use a 4:1 G-Whip guanella current balun with my Doublet, but many users recommend using a 1:1 ratio current balun - again, this is a case for individual experimentation.

A more detailed description of the Doublet Antenna can be found here >>

External Links

The All Band HF Doublet can also be found on Ham Universe: http://www.hamuniverse.com/hfdoublet.html

Introducing The All Band Doublet by the late L.B. Cebik W4RNL: http://www.cebik.com/content/edu/edu6.html
N.B. Create a free account at http://www.cebik.com

The Norcal Doublet







The Norcal Doublet Antenna: http://www.norcalqrp.org/norcaldoublet.htm

The Norcal Doublet is a simple antenna that is 44 feet (13.4 metres) long, 22 feet (6.7 metres) per side. The Norcal pages report "...that the antenna would have basically the same radiation patterns on all bands from 40 - 10 meters. This would be very handy to have for field operation..... You will need the following materials: 50 feet of 4 core stranded computer cable; 1 #0 Fishing Swivel; 1 Cable tie; 2 pieces of fishing cord."

The antenna can be hung from trees or cheap telescopic 'roach' / Sota poles. Doubling the size would allow operation on 80 metres and even 160 metres by shorting the twin feed together at the transmitter end and feeding it against a good earth as a 'Marconi' type antenna.

An effective multi-band "4 Dollar Special" by Joe Tyburcy - W1GFH (An Inverted Vee Doublet Antenna - super cheap - super effective - multi-band)

Joe Tyburczy, W1GFH provides some sensible insight and advice, he writes: *"I am a big fan of "balanced line" (twin lead, open wire line, etc.) vs. coax. By using balanced line and a tuner you can have one, single-element antenna that works well on all bands. You can't do that as easily with coax. The basic "W1GFH $4 SPECIAL" shown below is a variation on the type of versatile skyhook I've been using for years......Now at this point, some of you may be looking at the diagram and muttering, "Jeez Joe, that's just a dipole fed with twin lead and used with a tuner". Well of course it is. Virtually all antennas are "di-poles" (i.e. "two sides") in some form or another. This one just happens to be made from low-cost materials......I won't go into the theory here, but trust me: balanced feed line, properly used, does not "leak" RF and is less lossy than coax. I've tried the commercial 450-ohm ladder line, but prefer 300-ohm TV twin lead, and the cheaper the better. Radio Shack TV twin lead is ideal. Home Depot has some good stuff, too. Forget all the obsessive junk about standing waves, impedance and velocity factor. What you really need to concentrate on is getting an interesting set of antenna insulators."*

Read Joe's excellent article in its entirety here: http://www.qsl.net/wb1gfh/antenna.html


Center and end Insulators: Hacksaw 3" sections from acrylic adjusting rod used on mini-blinds. Drill two 1/8" holes for wire. (Cost: $0)
Support
33 to 65 ft. of junk wire on each leg. (A 500 foot roll of #18 insulated cost me $3 at a local surplus store)
300 ohm twinlead. Cheap, brown indoor-type. 30 foot hunk bought at a local yard sale. (Cost: $1)
Stake
Tuner GND
Balanced line output (4:1 balun)
Groundwire to a lousy 4 foot ground rod.
TUNER
3 feet of coax
RIG

4 Dollar Special by W1GFH
http://www.qsl.net/wb1gfh/antenna.html

Inverted L - 80 metres to 10 metres

A typical Inverted L antenna will be trapped for 40m/80m using a 7.1 MHz trap. It is essentially one half of a W3DZZ dipole so can be accommodated very much more easily into a small plot or garden - especially as part of the antenna is running vertically up a wooden or fibreglass (non conductive) pole. This should allow it to be fitted into quite a small garden such as mine. It's a very useful antenna in this respect, and because there is a good length of wire in the air, it radiates quite well.

The Inverted L is also a very effective aerial because it has the benefit of both vertical and horizontal radiation. While Inverted L's might make good TX aerials, like ground mounted vertical aerials they do have the potential to be a little noisy on RX. This will depend upon local circumstances and noise sources. However the fact that the feed point will generally at the bottom of the garden, well away from the house may help to keep QRM to a minimum.

The Inverted L is extremely easy to 'home brew'. Spectrum Communications can also supply the complete aerial as shown below. It should give excellent performance on 80m and 40 metres, with 20 metres also being good but also allowing use on 15m and 10m and possibly one or two of the WARC bands.

If you fancy home-brewing the complete antenna, except for the 7 MHz trap, traps are available to buy commercially from suppliers such as Spectrum Communications and Sotabeams who supply very neat and lightweight devices,

Use a Remote Automatic Antenna Coupler : The use of a good Automatic Antenna Coupler, such as the CG Antennas CG-3000, at the feed-point with a simple inverted L wire will provide a very good Multi-Band aerial that could be used on all bands between 160m and 10m and should be very simple to deploy.


TRAPPED INVERTED L ANTENNA
19′7″
7·1 MHz
TRAP
INSULATED POLE
33′
COUPLING BOX
COAX
SUPPORT & EARTH STAKE
80 – 10 metres, with a small garden.

Spectrum Communications Inverted L - benefits from both vertical and horizontal radiation
http://www.spectrumcomms.co.uk

More about Inverted L Aerials:

The Inverted L for 40m/80m is shown below is essentially one half of a W3DZZ dipole fed against ground using one 7.1 MHz trap. It's a very compact antenna and is simple to construct. It is most efficient, of course, on 80 metres and 40 metres, but can also be used, with an a.t.u., on 20m, 15m and 10m.

Find out how to make one here: http://www.users.icscotland.net/~len.paget/5%20band%20Inverted%20L.pdf


Monofilament
7MHz trap
6.55m
9.9m
Timber or non-metallic support
Antenna
Connector block segment
Earth rod
Tenby clip
Coaxial cable
Coaxial cable
WT2286
Earth rod

The basic layout of the Inverted L Antenna by Len Paget GM0ONX (Practical Wireless)

Adding 160m / Top Band to an Inverted L

The 160 metre Top Band can be added to this aerial by connecting a 3.5 MHz trap at the end of the 80 metre wire (where to monofilament joins the 6.55m section of wire below) with another length of wire on the other side, increasing the overall length of the antenna.

Find out how to do it here: http://www.users.icscotland.net/~len.paget/Inverted%20L%20adding%20top%20band.pdf


8.54m
3.5MHz trap
Insulated support pole
Insulator
6.55m
7MHz trap
9.9mm
Insulated support pole
Connection to earth and to the antenna conductor (see text for more detail)
Coaxial cable feeder
WT2599
40m / 80m / 160m Inverted L
By Len Paget GM0ONX
Practical Wireless Magazine

Adding Top Band to an Inverted L by Len Paget GM0ONX (Practical Wireless magazine)

160m Top Band 'Inverted L' Wire Antenna

At the time of writing I am using a 40m/80m Inverted L aerial and in an attempt to get on Top Band I have also been experimenting with a shortened 160m antenna in an inverted L configuration that uses a wire about 19 metres long - about half the size of a full size inverted L for 160 Metres.

A Top Band aerial of this type also needs a very good ground / counterpoise and can suffer the disadvantage, like ground mounted vertical aerials, of being rather noisy on RX . The drawing below shows the general idea. Read more here >


Pulley
Egg insulator
Aluminium pole
Aerial wire
12m
Telescopic fibreglass fishing pole - 6m high fixed to wooden post
Inductor
Pulley
1m
5.5m
Counterpoise ground radials
Connection box
Fence
Halyard
Coax to shack
Wooden post
Earth rod
Top Band Aerial by MØMTJ

General layout of Top Band Aerial with fibreglass pole retracted to a height of 2 metres
Wire lengths are approximate: Inductor 5cm dia with approx 40 turns of enamelled copper wire

Full Wave Loops and Delta Loops - An easy to install and effective antenna for multi band operation

Easy and low visual impact - a full wave loop: With a larger garden a full wave loop could be easily accommodated horizontally without the neighbours even noticing. A garden with a perimeter of 40 metres would easily accommodate a full wave loop for the 40 metre band and would work up to 10 metres or even 6 metres with an 'ATU'. A garden with a perimeter of 80 meters would accommodate a full wave loop for the 80 metre band and would work up to 10 metres.

Small Loop for 20 metres to 10 metres: A loop for 20 metres or 17 meters is relatively compact and could easily be installed in small 'postage stamp' sized gardens. A loop antenna could be triangular, square (Quad) or circular, but a square loop (and indeed a circular loop) would need more supporting points than a delta (triangular) loop, so a Delta loop is likely to be the easier option.

The loop is really a single band antenna cut for one wavelength on the band of interest, however it can also work quite well as a cheap and easy to install multi-band H.F. aerial. A loop consisting of a 17 metre length of thin antenna wire, for example, will work well on 17 metres but may also give 15m, 12m and 10m with an ATU. My own loop is made from an 16 metre length of wire, tuned for the 17m band, but can work on higher bands. A 40 metre loop will be considerably larger, but it might still possible to accommodate in many fairly compact gardens. Performance will depend on height and orientation.

Feeding the loop at the top or bottom will give horizontal polarisation, while placing the feed point on the side will give vertical polarisation. The apex can be at the top or the bottom, but performance should be better with the apex at the bottom with the flat wire across the top - however for ease it may be more convenient to support a Delta Loop on a single pole, meaning that the apex would be at the top.

Ideally a loop should be fed with balanced line back to the shack, connected to a balanced line ATU or other ATU via a 4:1 balun. Alternatively use a 4:1 balun at the antenna end and run 50 ohm coax back to the ATU / txvr - though losses will be greater doing it by this method if the coaxial cable is quite long.

If one can install a separate antenna for the lower frequency bands of say 160m, 80m and 40m, then a Loop Antenna could be a good partner to allow operation on the higher bands of 20 metres to 10 meters or even 6 metres.

A loop should be really very easy to install using a single support pole and very cheap too! All that's needed is the supporting pole, some cheap wire, a 4:1 balun which can be 'home brewed' and some thin cord and insulators which should not be an eyesore either.



Diagram from the excellent article by W5SDC
http://w5sdc.net/delta_loop_for_hf.htm

Band	Length of antenna wire at mid band in metres
10	10.617
12	12.282
15	14.432
17	16.90

20	21.502
30	29.622
40	42.842
80	82.234
160	161.223

Delta or Quad Loop Antenna - An ideal multi band antenna solution?


SUPPORT ROPES
SUPPORT ROPES
RANDOM DELTA LOOP
CIRCUMFERENCE COVERAGE
75' 20 METERS & UP
150' 40 METERS & UP
280' 80 METERS & UP
GREAT FOR DX !
THIS ANTENNA MUST BE USED WITH A TUNER ! IF YOU HAVE A TRUE BALANCED TUNER, YOU CAN ELIMINATE THE 4:1 BALUN AND RUN BALANCED LINE ALL THE WAY TO THE TUNER.
450 OHM BALANCED LINE ANY LENGTH NEEDED
WORKS WELL AT LOW HEIGHTS !
CAN BE INSTALLED HORIZONTAL FOR OMNI DIRECTIONAL COVERAGE OR MOUNTED LOW AND HORIZONTAL FOR NVIS WORK
THE RANDOM DELTA LOOP IS A DIRECTIONAL ANTENNA WITH RADIATION BROADSIDE TO THE LOOP, ORIENT FOR DESIRED DIRECTION OF COVERAGE
4:1 BALUN
COAX - 25' OR SHORTER
KC8AON 2001

A Multi Band Wire DX Loop Antenna by KC8AON
http://www.i1wqrlinkradio.com/antype/ch10/chiave1827.htm



Delta Loop by Arthur M0PLK (SQ2PLK)
Details at http://pdxa.one.pl/articles.php?article_id=17
Available at http://ham-radio.urbasket.eu and http://www.vpa-systems.pl/

Using fibreglass fishing poles (Sota Poles) two 7 metre long poles can be erected in an inverted V shape and used to support a 20 metre delta loop which will be usable on 20m to 10m and also adaptable for use on the 40 metre band.

The two aerial wires used are connected directly to a 4:1 balun which is, in turn, connected to an ATU such as the Z-11 Pro or Z-100 via coaxial cable. See this page which shows the W6ZO delta loop to get for the general idea of what will be achieved. The finished aerial will be very much like the commercially available ProAntennas DMV-Pro.



W6ZO Delta Loop - fed with 4:1 Balun - 40m to 10m
http://www.fros.com/KI0GU/w6zodelta.htm

The Loop Antenna. Ideal - cheap, easy, multi-band, simples! -
Lots of links to other Loop Antenna information on the links page here

Omni Directional Multi-Band Horizontally Polarized Delta Loop

If all that can be erected is a single pole, masts or telescopic pole, here is an option that will provide a horizontally polarized signal on 20 / 17 / 15 / 12 / 10 metres - the Sandpiper Aerial Technology GM3 (designed by GM3VLB). A similar idea, providing omni-directional horizontally polarized signals, is the G3TPW Cobwebb Antenna from Steve Webb.

These look like good ideas, though I have yet to make one to test.

G Whip Antenna Products
G-WHIP
Antenna Products
Top Quality
British Manufacture

Site Search
Find
powered by FreeFind



Sandpiper GM3VLB Antenna
http://www.sandpiperaerials.co.uk/

COBWEBB ANTENNA http://www.g3tpw.co.uk http://www.karinya.net/g3txq

G3TPW Cobwebb Antenna from Steve Webb - photo by G3TXQ
http://www.g3tpw.co.uk http://www.karinya.net/g3txq

Resonant Vertical Antennas

Low SWR: Having a low v.s.w.r. across the whole of HF may seem, at first glance, to be a good thing - but my dummy load has a very low v.s.w.r. from HF to UHF, it does not make it a good antenna! As far as aerial systems are concerned, having a low v.s.w.r. across the whole of HF is probably not the best way to judge an antenna - a wide band low v.s.w.r. could indicate a fault with the aerial or feeder system - or just that lossy matching transformer that is gently heated up by the power applied from the transmitter!

A low v.s.w.r. is a good thing in a resonant antenna. It will help demonstrate the antenna's point of resonance - but the v.s.w.r. will rise either side of resonance. So:



The next commercial option is an antenna that is truly resonant on a number, but perhaps not all, bands. The Hustler and Butternut varieties are very well known and offer well reported good performance.

Some vertical antennas use traps to achieve multi-band performance and as such are essentially one half of a trap dipole, fed against ground. A consideration is that the traps themselves, particularly if multiple traps are used, will introduce losses to the antenna system. It should also be noted as an additional consequence of using traps on a ground mounted vertical antenna, is that the highest frequency element will inevitably be positioned at the lowest position on the aerial - not a good position to be, especially for local ground wave radiation where signals will more easily be screened by local structures. Ground conductivity also needs to be good for verticals to operate efficiently.

The Hustler 4-BTV, 5-BTV & 6-BTV aerials are examples of multi-band verticals that use traps; many amateurs report great success with Hustler aerials - and it is very low profile too, indeed an amateur friend of mine uses a Hustler with great success and has even modified an additional top resonator so that the aerial can be used on 160 metres..

Other manufacturers of resonant vertical antennas, using varying design methods, include GAP, Cushcraft, Diamond, HyGain, and the well known British names Moonraker and Sandpiper.

Advisory: These are perhaps a good idea for limited space situations, but the shorter versions will not work well on the lower HF bands. A 6 metre tall antenna cannot possibly work terribly well on 40m or 80m, but may work well on the 20 metre band and above. However one could easily 'home brew' an equally effective antenna for a fraction of the cost of a commercial antenna.

Sandpiper Aerials

Sandpiper Aerial Technology offer an enormous range of amateur radio antennas from HF to UHF. For HF working Sandpiper offer numerous options including simple multi band resonant antennas supported on fibreglass telescopic poles using either changeable or plug-in coils for different bands to the famous V range and shorter and more compact MV range and the Portable MV antenna on its own tripod base. The V and MV ranges use a rather innovative design, seen above right. The V and MV antennas are available in versions that cover all the HF bands - or as cheaper versions that just cover the particular bands of interest. http://www.sandpiperaerials.co.uk/

Vertical antennas will be quite short when compared to the wavelengths of some of the longer wavelength bands (particularly 40m, 80m and 160m) and so will not radiate as efficiently as a full size resonant aerial. The bandwidth will also be quite narrow. Setting up a multi band antenna to be resonant at the required portion of each band can sometimes be a little time consuming, but for the convenience it might be a price worth paying. A vertical antenna will generally have a low angle of radiation which is a good thing for long distance DX but verticals can be very noisy on RX compared to a balanced dipole and as previously alluded to, radiation efficiency will be very low when compared to a full size single band resonant antenna. Attractive options?

Alternatives: My favourite way of experimenting with aerials is using a 10 metre long fibreglass telescopic fishing pole as the support. These fibreglass poles are lightweight and easy to carry, put up and take down, ideal for supporting lightweight v.h.f. and u.h.f. yagis, wire dipoles and doublets and also for supporting vertical wire aerials.

The telescopic pole must be made from fibreglass, not carbon fibre which is electrically conductive.

One great design is by Dave G4AON who writes on his web page: "There seems to be a myth among many newly licensed radio amateurs that an antenna works better if it costs a lot of money..... The antenna shown here costs around one tenth the price of a commercial vertical, yet it will perform as well as (and in many cases better than) a trapped vertical antenna. This antenna is based on a 10 Metre long fibreglass fishing pole.....the poles will collapse inside the sections unless each joint is secured with PVC tape, for more permanent installations glue could be used.

...The wire lengths are calculated from the formula L = 234/F, where F is the frequency in MHz and L is the wire length in feet. These lengths work out to around 33' 3", 23' 2" and 16' 7" for the 7, 10 and 14 MHz bands. The lengths for 7 and 10 MHz were more or less correct, however probably due to interaction between the wires the 14 MHz wire needed lengthening by around 4" for minimum SWR. Wire size is not critical, but it is probably better to avoid the thinnest "hookup" wire. Note, ground conductivity/loss and elevated/buried radials make a significant impact on both the performance and tuning of a ground mounted vertical. In the case of buried radials the vertical may resonate significantly lower in frequency than expected."

The antenna shown on the right is made for triple band operation on 7 MHz, 10 MHz and 14 MHz by the use of parallel wires, but an aerial based on a fibreglass pole could be single, dual, triple or even - at a push - quadruple band.

The more bands included the more difficult it will be able to trim to tune for resonance (as with a fan dipole) so to keep interaction to a minimum the wires should be quite well spaced. Like all quarter wave verticals aerials a good ground plane will be needed.

See G4AON's excellent full article here: http://www.qsl.net/g4aon/vertical/

Horizontal Resonant Wire Aerials

The great advantage of a vertical antenna is that they have a very small footprint, i.e. they can be installed in the corner of many small plots and gardens. True resonant verticals can properly cover many, if not all, the HF bands. However to be reasonably effective a vertical needs a very good ground and also must be quite tall, in the order of 6 to 9 meters in many cases (about 19 to 30 feet). This may cause objections from the XYL. Another disadvantage might be that a vertical has little near vertical incidence skywave radiation (NVIS), a consideration for the lower HF bands, so after the local ground wave coverage there will be little or no signal until after about 500 miles, not good for inter G working. (ref. G8JNJ) - So try some Dipole Antennas:

Dipole Antennas

The dipole antenna is possibly the simplest and cheapest antenna to make. It it cut for single band operation where it should make a very efficient radiator. The simple wire dipole should be quite discrete, though not entirely invisible, but should not raise too many objections from the XYL or neighbours.

For some dipole ideas see this page:
http://www.qsl.net/ta1dx/amator/practical_dipole_antenna.htm

How to make a basic dipole by Marshall N1FN : http://www.morsex.com/dipole/index.htm

Also see this detailed and useful page: http://www.dxzone.com/cgi-bin/dir/jump2.cgi?ID=7499

Calculator:
http://www.sean1226.pwp.blueyonder.co.uk/design_your_own_antennas%201.htm

TRAP Dipoles:

The next type of antenna to consider might, then, be a horizontal or sloping wire antenna. Perhaps the most familiar multi band wire aerial is the trap dipole. The traps, in simplest terms, divide a wire dipole into two or more resonant sections so that two or more bands can be covered.

As far as commercial options go then there are quite a number. Tony Nailer of Spectrum Communications produces a great deal of useful equipment and accessories including some well designed and well made trapped dipole aerials based on the very effective W3DZZ design. In particular the Full Size G4CFY resonant on 80m and 40m and also allowing operation on 20m, 15m and 10m, also the Half Size G4CFY resonant on 40m and 20m and additionally allowing operation on 15m and 10m.

Visit http://www.spectrumcomms.co.uk/G2DYM.htm for more information.


G4CFY Trap Dipole 80 - 10 metres
Based on W3DZZ design. Side view.

70, or 90, or 108,
or 128, or 140 ft
75Ω twin feeder.

Spectrum Communications G4CFY Trapped Dipole
http://www.spectrumcomms.co.uk

Spectrum Communications G4CFY Trapped Dipole
http://www.spectrumcomms.co.uk

More about Coaxial Trapped Dipoles

A trapped dipole for 40m and 80m offers the advantage of being somewhat shorter than a full size single band 80m resonant dipole plus it offers 40m as a resonant band plus the possibility of working on 20m, 15m and 10m. There are several designs available on the web for this type of aerial so Google W3DZZ. One of the most comprehensive sets of instructions is by Len Paget G0ONX. Fine out more here:
http://www.users.icscotland.net/~len.paget/GM0ONX%20trap%20dipole.pdf

This would be my choice if I had the space, though since a dipole is a balanced aerial it would make more sense to use balanced twin feeder (as in the Spectrum Communications implementation of this design) rather than coaxial cable which is an un-balanced and more lossy feeder.



Fig 1: The overall layout of the W3DZZ antenna.

The W3DZZ Trapped Dipole - a balanced aerial, so use balanced twin feeder!

Here is a variation on the W3DZZ antenna by the Maidstone Amateur Radio Society that adds a dedicated 10 meter (28MHz) resonant element as a 'fan'.


W3DZZ MkII
32.9M Top
16.45m
7Mhz Trap
7Mhz Trap
Several dozen 6mm ferrite beads
28 Mhz Twigs (2.7M) ~ 1mm wire & fishing line supports
16.77m 75 ohm Sat TV coax
50 ohm coax to tx

W3DZZ Dipole Aerial design by the Maidstone Amateur Radio Society
http://www.btinternet.com/~shaun.scannell/club/w3dzz.htm

Moonraker supply a whole range of wire trap dipoles covering from 2 to 5 HF bands (MTD1; MTD2; MTD3; MTD4; MTD5; MTD6). Diamond also produce trapped wire antennas, the W-721, W-728 and W735. Comet and Diamond each produce similar interesting 5 band wire dipoles that utilize both traps and a fan arrangement - the Diamond W8010 and the Comet CWA-1000. If space really is limited then look out for KZJ Communications (dongo1950 on ebay) - he produces 'Limited Space Inductive Dipoles'. These are inductively loaded and shortened dipoles so they will have reduced efficiency, of course, but are very nicely made, so might be very useful in a tight spot.

Alpha Delta Communications produce a couple of substantial parallel dipole models: http://www.alphadeltacom.com

To obtain good efficiency and achieve a low angle of radiation, desirable for longer distance DX, a horizontal dipole needs to be installed at a good height - over 20 feet would be desirable and it is quite common to install horizontal dipoles at around 30 to 40 feet above ground level. This might be a problem at some QTH's, it certainly is at mine!

Allan Copland, GM1SXX comments: "The dipole will operate well on the band it has been sized for , if placed at a suitable height, but will also operate as a' three-half-wave' aerial at three times the frequency and so on, so it's not strictly a single band aerial. An 80M dipole (132 feet typical) will work nicely on 30 metres (three half waves) but not on 40m (two half waves)… because on 40M the feed-point is at a voltage node and not at a current node, for easy feeding. Most aerials are current fed.

The radiation pattern changes when a dipole is not used on its design frequency. The pattern will break up into multiple 'petals'. This can be either a disadvantage or an advantage depending on what you expect from it. Since most of us use co-ax, an UN-BAL should really be used to connect the unbalanced feeder to the balanced aerial, but how many people actually bother? Not many I suspect. It's possible of course to use a balanced feed-line system instead with a dipole and just have a delta match (no centre insulator… none needed). There are many choices and permutations, but in general, dipoles are centre fed at a point of current maximum (and minimum voltage).

A normal dipole is current fed but of course can be voltage fed instead. This is what's done in the EFHWA or Fuchs aerial where a resonant half wave wire is fed at one end (max voltage / min current) from an L/C tank, against a very short counterpoise wire.

Fan Dipoles (a.k.a. Parallel) Dipoles:

Another design of multi band wire dipole is the fan dipole, or parallel dipole. A fan (or parallel) dipole will have, perhaps, two, three or four individual resonant dipoles with the arms arranged in a fan shape.

A fan dipole is a very handy way of using a dipole that will be resonant on several bands - typically three or four. The fan dipole (a.k.a. Parallel Dipole)

See M0WYM's page for a QRP Fan Dipole design: http://www.radiowymsey.org/FanDipole/fandiploe.htm

See this page for construction details: http://www.hamuniverse.com/multidipole.html


HF MULTI-BAND DIPOLE
80m 119.2
40m 64.4
20m 32.75
10M 16.1
copperweld wire
insulators
Nylon rope
or monofilament
NOTE PULLEY ON EACH END
Tension ropes each side
COAX TO RADIO
N4UJW

Tension rope is not tied to pully rope in picture. It is tied near location of pully rope down on supports within easy reach. It is tied last after final SWR adjustment and the antenna is in it's final position.

Suggested total lengths:
80 meters - 120 feet
40 meters - 65 to 66 feet
20 meters - 34 feet
10 meters - 17 feet

These lengths are not exact. Some tuning may be required. Use the standard formula 468 / freqmhz for total feet for each band (freq) of interest. Adjust each length longer or shorter as needed.

Fan Dipole shown on Ham Universe

KI4NRH built a really neat fan dipole shown in the photograph below:


KI5NRH Fan Dipole

Fan Dipole by ki4nrh


KI5NRH Fan Dipole

Fan Dipole by ki4nrh
http://forums.qrz.com/showthread.php?t=159953

Link Dipoles

Link Dipoles (a.k.a Jumpered Dipoles) facilitate multi band operation by simply connecting the jumpers (one on each side of the aerial) to achieve the desired resonant band. Perhaps a bit bothersome for frequent band changes, but a very simple and effective aerial and very handy for portable operation, not to mention efficient for QRP.


Band 3
(Lowest Frequency)
Band 2
Band 1
to Support
to Support
Inner Jumpers Closed (Outer Open) for Operation on Band 2
Nonconductive Support Line (Typical)
Coax
(A)

Link Dipole - ref ARRL

Sloper Aerials

Alternatively a dipole can be installed as a sloper; one end fixed to a high point on the house or building, or a tall post maybe 8 to 10 metres high, with the other end attached to a lower point such as a post maybe 3 or 4 metres high. This will give the aerial some directivity.


"Forward Direction"
90°
Anchor Stake
Coax Feeder

Sloper configuration of a wire dipole

Inverted V Aerials

Another option maybe to support the dipole at its centre on a tall pole, or roof apex, with each end sloping downwards to lower fixing points. This will give the aerial an upside down V shape. As with a sloper, the Inverted V arrangement will give the aerial some directivity - a different radiation pattern compared to a straight horizontal dipole.


G4CFY Inverted V
Side view.
T PIECE
33'
33'
7.1 TRAP
7.1 TRAP
19' 7"
19' 7"
GUY
GUY
70, or 90, or 108,
or 128, or 140 ft
75Ω twin feeder.

Spectrum Communications G4CFY Trapped Dipole in "Inverted V" configuration
http://www.spectrumcomms.co.uk

The Classic Doublet Antenna Again. This time in an Inverted V formation:

Using an Inverted V can help fit a dipole into a slightly restricted space. The Inverted V arrangement can be used for single band resonant dipoles, trapped dipoles and fan dipoles. The Doublet must be fed with Ladder Line or Open Wire balanced feeder for efficient Multi-Band operation.


Wooden Mast (or Tree Limb)
Insulating Block
65'
65'
>90°
Insulator
>10' for Safety
Open–Wire Feeder (300–600 Ω)
End Anchor
to Transmatch
Multiband "Inverted V"
(A)
to Feed Line
From Trans 50 Ω
SWR Bridge
500 pF
150 pF
150 pF
Transmatch

At A, details for an inverted V fed with open-wire line for multi-band HF operation. A Transmatch is shown at B, suitable for matching the antenna to the transmitter over a wide frequency range. The included angle between the two legs should be greater than 90° for best performance. [ref: QSL.net]

Vee Configuration

Comet and Diamond produce Vee antennas that can be mounted on the side of a building at roof height, or on a pole, telescopic pole or other suitable support. These are trapped dipoles in an upright V configuration, not made of wire but of aluminium tubing for solid construction. Typically covering 40m, 20m, 15m and 10m. The Comet model is H-422V. The Diamond Model is HFV5 which also covers 6m.

These are shortened antennas so cannot be expected to have high performance on the lower HF bands, but if space is restricted the RF compromise may one that has to be taken.

Comet H-422V
http://www.cometantenna.com


Diamond HFV5 Antenna

Diamond HFV5 Antenna
http://www.diamond-ant.co.jp/english/amateur/antenna/ante_2base/ante_base7.html

Thoughts from Martin G8JNJ on multi-band wire antennas:


Approx 2 x 14.25m of wire cut to bring antenna to resonance at 14.1MHz
Approx 7m wire attached to side of pole resonant on 10.4MHz
Approx 12.6m of 450 ohm ladder line cut to be a wavelength long at 22.54MHz
10m GRP fishing pole supporting one end of antenna
Approx 20 turns of 50 ohm coax wound on 0.1m diameter pipe at bottom of 450 ohm feeder. Adjust for resonance on 1.9MHz when when feeders are strapped by switching box. Also acts as choke balun for HF bands when used in normal configuration
Heliax coax to remote ATU and transceiver
Switching unit & 1:1 balun
Tuned groundplanes approx 0.6 x ¼ Wavelength stapled to fence spaced 0.25m apart
4:1 Balun
Tuned groundplanes for 160 & 80m approx 0.6 x ¼ Wavelength stapled to fence at 2m height of 2m spaced 0.5m apart
ZS6BKW / G0GSV antenna configuration with switching unit for 160m operation
© M. Ehrenfried – G8JNJ 4/1/208 V1.0

Multiband Wire Antenna by Martin G8JNJ
http://g8jnj.webs.com/

Linear Loading

Linear loading a dipole can reduce the length to help fit a ling dipole into a shorted space by essentially folding back some of the dipole elements. Here is a design by K4VX for a 7MHz Linear Loaded Dipole: http://www.arrl.org/files/file/Technology/tis/info/pdf/0207040.pdf

End Loaded Dipole

End loading can also help reduce the size of antennas, particularly useful for dipoles used on the 80m and 160m bands.

An end loaded dipole will produce an antenna that is H shaped. There are several commercial designs available produced in designs that cover a single band and others that cover multiple bands. The version shown below is only 3 metres tall so will be suitable for very unobtrusive, low profile use. It is the ProAntennas Multi-band I-PRO: 20m 17m 15m 12m 11m & 10m which uses a capacity hat with some loading at the centre.
http://www.proantennas.co.uk/

Other similar antennas were available from Force12 Antennas in the form of, amongst others, the Sigma 5 and Sigma GT5. The Sigma design used T-bars at each end of the vertical dipole for loading technique and off-center loading coils. http://www.force12inc.com This was supplied supplied in the UK by Vine Antennas at one time http://www.vinecom.co.uk . Transworld Antennas also have produce antennaa using a similar concept - the TW2010 Adventurer and Backpacker http://transworldantennas.com

K9AY Notes that: "I have come to the conclusion from my experiments, readings and observations, that a capacity hatted vertical dipole, a few feet over ground, is less compromised than a 1/4 w/l vertical of the same height fed against a less than perfect ground. Let's face it, most amateur's ground systems are mediocre at best. Also, the dipole is easier and cheaper to rig, and is two dimensional..Very important in my situation, as I cannot run out radials on my neighbours property. Or, to quote W4RNL.."Since only a handful of hams can ever have 160-meter antennas high enough to yield a low angle DX signal, more practical are vertical arrays such as yours. Vertical dipoles with hats (or Tees) save a plethora of wire needed by monopoles." http://www.dxzone.com/cgi-bin/dir/jump2.cgi?ID=7466


Dipole
End loaded dipole
Off centre fed End loaded dipole
Vertical
Off centre fed End loaded dipole

Information by K9AY


= resonant length
= 468/f
= 468/f
= Less than 468/f
= Less again than 468/f

The smaller the radiating element, and the larger the capacity hat, the smaller will be the resonant length . (compared to 468/f)

Information by K9AY


Top Capacity Hat wire
60 ft Timber Mast
= insulators
Top & bottom capacity hat wires are 66 ft for 80m and 130 ft for 160m approximately.
Vertical wire connects to the centre point of both Capacity hats
45ft Vertical Wire
Choke Balun at Feedpoint
Bottom Capacity Hat wire
Fence
Coax to Shack

Interesting concepts from K9AY

End Fed Half Wave Antenna

The End Fed Half Wave Antenna (EFHWA) is fed at a voltage node via a parallel resonant circuit against a ‘short counterpoise’, it is a favourite of backpackers and outdoor types. It can be considered as a half wave dipole that’s end-fed at a voltage node rather than the current node, as is more usual. This is a very handy arrangement for portable QRP work.

EFHWA Link: http://www.aa5tb.com/efha.html


0.05 λ
C
End Fed Half Wavelength Antenna
"Counterpoise" Return
Secondary
Primary
50 Ω
Coaxial
Cable
AA5TB
Ideal End Fed Half Wave Length Antenna

End Fed Half Wave Antenna by AA5TB
http://www.aa5tb.com/efha.html

"I suspect that nothing new or radical has happened in the field of radio aerials in a VERY long time, like at least many tens of decades. Most of the new wonder aerials are really a con. Choke off the feed-line and then see how good they really are. Prime among the baddies is the CFA. It doesn't really work, at least if you place a choke in the feed-line. With any real aerial, there should be minimal radiation from the feed system… so a choke should really make no difference at all, but for the CFA it does! The CFA is not alone, there are others. The popular G5RV is another design with a radiating feed, deliberately so, but of course G5RV planned it that way. He wasn't cheating… merely being a bit devious, to make it multi-band".

"Lots of stuff to pass on to my fellow radio club members, most of whom are of the 'if it's not expensive, it can't be any good' school of thought when it comes to aerials. Nothing of course could be further from the truth! Aerials are one area where it makes a lot of sense to build our own." : Website of GM1SXX - www.observations.biz

Thanks for your email Allan. It's a good idea to point out that an antenna could be pressed into use on odd multiples of its resonant frequency, hence a 3.6MHz antenna for 80m could be useful near the 30 metre, 10.1MHz, band - near to the third harmonic of 3.5 MHz although, as you observe, the radiation pattern may be quite distorted from the traditionally expected dipole pattern and be more petal shaped. The same goes for a 7.1 MHz antenna for 40m being usable on its third harmonic of 21.3 MHz for the 15m band - a 40m dipole being three half waves an the 21 MHz band.

I have not experimented with a full size 80m dipole, but I would guess that it might be useful at 5 times 3.6Mhz in the 18 MHz / 17m band?

The point made about feeding a familiar dipole at the current node rather than the voltage node is obviously very important and, I imagine, sometimes overlooked.

PLANS: Download the pdf plans produced by G0KYA here > More from G0KYA here: http://g0kya.blogspot.com

W3EDP Antenna



Frank, G3YCC comments on his website: The W3EDP needs a simple matching unit is needed to couple the wire to the rig and a counterpoise is required for some bands, however there is room for experimentation. It has been shown that different lengths or removal of the counterpoise altogether, can improve performance, as described in RadCom, August 1996 by G3LCK.

The Tuning capacitor in the AMU can be a 365 - 500pF broadcast type or a miniature version is OK for QRP use.

Counterpoise lengths: 3.5 & 7.0Mhz - 17ft ; 14Mhz - 6.5ft ; 28Mhz - none

Tuning Unit: Values for coils in the unit, based on a 2 inch former and 16 swg wire:
3.5Mhz 21 turns ; 7.0Mhz 7 turns ; 14.0Mhz - 5 turns.

K3HRN Notes: "Some folks have told me the modifications below make the antenna something other than a W3EDP. I can tell you that it works very well with 5 watts. Create a "bundle" of counterpoise wires, 1/4 wave length for each band you will use. Attach the bundle to the tuner in place of the counterpoise pictured above. Be cautious, 1/4 wave length elements can have high RF voltages present, even at QRP power levels. I've been able to work 160-10, including WARC bands with this type of antenna".

W3EDP or Zepp ?

It's the antenna favoured by VA3QV for all band Portable QRP operating!

VA3QV uses this home-brewed antenna with a small LDG Z100 antenna tuner for portable QRP work.


The "W3EDP" Antenna
As Homebrewed by VA3QV
Http://www.va3qv.wordpress.com

Note

This is not drawn to any sort of scale but it you follow the plans shown it should work. I have built one using 300 ohm twin lead, I have built one using 450 ohm Ladder Line and my last one was built using "Spreaders" (open Ladder Line Style)

Using my FT 847 and a LDG Z100 Auto-tuner this has Loaded up and made contacts on 10m to 160m SSB (including 12m and 17m) To be honest never tried it on 30m.

73bob October 17 2009

Homebrew antenna by VA3QV
http://va3qv.wordpress.com

Ye Olde Zepp

Marconi spins in his grave every time a ham buys an aerial instead of building it ! (W1GFH)

Here is a wonderful olde worlde style cartoon from WB1GFH that certainly inspires antenna experimentation with antenna designs:


Ye Olde WB1GFH
FOUR-DOLLAR SPECIAL
APPROVED BY BOARD OF FIRE UNDERWRITERS
AS LONG AS POSSIBLE
TUNER
AERIAL WIRE
NAIL-ON KNOB
JUNKY 300 OHM TWINLEAD
NAIL-ON KNOB
"IT REALLY WORKS!"
GROUND CLAMP
DAMN GOOD GROUND

Superb. I love it!

See more inspiration from Joe Tyburczy, W1GFH, here: http://www.hamuniverse.com/fourdollarspecialw1gfh.html

End Fed Zepp "Zepp"

The End Fed Zepp consists of a 1/2 wavelength horizontal radiator wire connected to one conductor of a length of parallel open wire feeder, 300 ohm or 450 ohm twin feeder. The feeder is often quoted as being 1/4 wavelength long.


Half Wavelength from Formula
Solder
Spacer
Open-Wire Feeder

Basic design of an end fed Zepp

G Whip Antenna Products manufacture and supply a version of the Zepp antenna. Geoff G4ICD explains: "The end fed Zepp shown below has no counterpoise, just a tuned circuit in the feedpoint plus a half wave radiator. This is a most interesting antenna and can be used on other bands with the use of an Antenna Matching Unit."

G Whip Antenna News
New Products.
WWW.GWHIP.CO.UK
G Whip Antenna Products
MADE IN BRITAIN
G Whip Antenna Products

A high quality End Fed Zepp style antenna: This variation uses a tuned circuit rather than a tuned twin feeder.
Supplied by G Whip Antenna Products of the UK
www.gwhip.co.uk

The end fed zepp is a popular antenna often used to save space and gets its name from the fact that it was used as an end fed wire trailing out from the rear of Zeppelin airships. It consists of a 1/2 wavelength horizontal radiator wire connected to one conductor of a length of parallel 300 ohm or 450 ohm twin feeder, often quoted as being 1/4 wavelength long.


Half Wavelength from Formula
Solder
Spacer
Open-Wire Feeder



Zepp Antenna by K4EFW
http://www.hamuniverse.com/n4jaantennabook.html

K4EFW notes: "...A half-wave resonant antenna can be fed from its end. When fed this way, it is also known as an end-fed zepp. An end-fed zepp will work on its fundamental frequency and on odd and even harmonic frequencies. The end of a half-wave antenna has very high impedance, and an antenna fed this way is said to be voltage fed. Feeding a half-wave resonant dipole in the center means it is current fed. The normal way of feeding the end-fed antenna is with ladder-line. One side of the ladder-line is connected to one end of the antenna and the other side of the ladder-line is connected to nothing. To secure the unconnected side of the ladder-line, it is connected to a short wire running between two insulators. Since the antenna is connected at its high impedance point, no current flows into an antenna, but there will be a large current in the center of this antenna. No current flows from the open side of the feed-line because it is at a zero current point. The end-fed zepp can be matched by cutting the ladder-line to a quarter wavelength with the bottom end of the ladder-line shorted. A certain distance above the short is a 50-ohm feet-point and it can be fed directly with coax. You will have to find the 50-ohm point by trial and error. This method of feed makes it a single band antenna". Quoted from K4EFW.

Here is a commercial product made by G-Whip Antennas of the UK offering their version of a Zepp antenna design: http://www.gwhip.co.uk/

Martin G8JNJ highlights a very interesting antenna designed by Mike G7FEK here:-

The G7FEK antenna goes several stages further than the simple single band End Fed Zepp. G7FEK has produced a design for Multi-Band operation claimed to offer much improved performance over a half sized G5RV or 'Windom' antenna while additionally providing access to the 80 Metre Band.

G7FEK Limited Space Antenna

G7FEK Multi-band "Nested Marconi" Antenna - 2008 Version (rev 5)

A 46 ft multi band antenna for small gardens that works well on 80 meters
Main bands (@~50 ohm) are 80m / 40m / 30m / 17m / 15m / 12m
Other bands (see text): 20m / 10m


38 ft (11.7m)
8 ft (2.5m)
Tune this end for resonance on 3.7 MHz
Tune this end for resonance just below 7.1 MHz
Support the antenna only at the ends if possible.
Avoid using a metal mast directly alongside the vertical.
If you need support at the feeder, use a fibreglass mast.
(The Shack End)
24 ft (7.4m)
(Bottom of Garden)
Twin feeder or ladder line.
Impedance is not important. Spacing should not be too small. (>20mm)
Short both ends of vertical elements together and connect to coax inner
50 Ohm Coaxial
Counterpoise or earth connected to coax outer - see text

G7FEK Limited Space Multi-Band Antenna


nylon string
16.5 ft optional wire for 14 MHz see text.
High Z
High Z
Low Z
Difficult match to main antenna as Hi-Z but energy is easily coupled at 14 MHz with additional Low Z optional element

Adding 14MHz to the G7FEK Limited Space Multi-Band Antenna

The G7FEK design will allow operation on 80m / 40m / 30m / 17m / 15m / 12m with the possibility to add the 20m band.

G7FEK Plans: Download the plans for the G7FEK antenna from G7FEK's website here or from this website here

Tuner Design For Half Wave Vertical and Similar Length End Fed Antennas by G4FGQ

http://www.radioaficion.com/HamNews/articles/8218-tuner-design-for-half-wave-vertical-a-similar-length-end-fed-antennas.html

Off Centre Fed Dipole (OCFD) - so called 'Windom' Antenna

The "Windom Antenna" was described by Loren G. Windom W8GZ. It could be an ideal wire aerial for use in restricted spaces for multi-band operation. It may also be an good candidate for portable work.

It is a wire antenna, similar to a dipole, but unlike a dipole or doublet which is fed at the exact centre, a Windom or Off Centre Fed Dipole, as the name suggests, has the feed point off center.

Current versions of the Windom are not actually Windom antennas at all - instead they are fed with coaxial cable and have a balun placed at the feed point. These are Off Centre Fed Dipole antennas - OCFD. They are similar in appearance to a true wire Windom, but they are different.

As with all aerials the aerial should be as high as possible. With the feed point at between 20 and 40 feet above ground the typical claimed impedance will be somewhere in the region of 200 Ohms so a 4:1 balun will typically be required. At greater heights, and depending upon the exact position of the feed point, the impedance may be higher and a 5:1 or 6:1 balun might be a better choice although balun losses will be greater.

The point at which a Windom is fed in the original design, which used an open wire to feed the aerial, was 15 percent off-centre. The current designs, which are fed with coaxial cable, are typically fed about 33 percent off centre, so one leg is 67 percent of the total length and the other leg is 33 percent of the overall length of the aerial.

The bands that are covered depends upon the overall length of the aerial:

11 metres long (approx) should cover 20m, 15m and 10m and the WARC bands with a tuner.

21 metres long (approx) should cover 40m, 20m, 15m and the 10m bands and WARC with a tuner.

41 metres long (approx) should cover 80m, 40m, 20m, 15m and 10m and WARC with a tuner.

80 metres long (approx) should cover 160m, 80m, 40m, 20m, 15m and 10m and WARC with a tuner.

Cut the aerial for the lowest band to be used. In imperial measurements using a familiar formula:
The longer leg will be 468 divided by the frequency and multiplied by .67 = length in feet
The shorter leg will be 468 divided by the frequency and multiplied by .33 = length in feet

OCFD Formulas:

The offset proportions differ according to which sources one refers. Some sources suggest 33% / 67% but other dimensions are also to be found:

62.2% for one side and 37.8% for the other leg. So:
The longer leg will be 468 divided by the frequency and multiplied by .622 = length in feet
The shorter leg will be 468 divided by the frequency and multiplied by .378 = length in feet
[Source: New Caroline Windom - http://www.hamuniverse.com/k4iwlnewwindom.html]

Other ideas:

The proportions of 69% / 37% are used by Buxcomm who say that "One third plus two thirds will not work. Use the formula below, as is: Do not be concerned with the off-set of the feed point, as this formula takes into consideration, the correct off-set for feeding the (BUXCOMM) Windom.for the other leg." **So:**
The longer leg will be 468 divided by the frequency and multiplied by .69 = length in feet
The shorter leg will be 468 divided by the frequency and multiplied by .37 = length in feet
[Source Buxcom: http://www.buxcomm.com/windom_files/WINDOM.htm]

Given the fairly simple formula it should be quite easy to make an OCFD Windom - however a Windom can be purchased at very reasonable cost commercially, for example from M0CVO at http://m0cvoantennas.webs.com alternatively G-Whip Antennas of the UK supply extremely high quality, high efficiency 4:1 baluns (and other baluns) that could be used at the centre of any Off Centre Fed Dipole - just add the correct wire lengths to each side.

Geoff G4ICD / GJ4ICD of GWhip highlighted his website which has an interesting page with comments concerning the quality and construction of balun products. This feature on the G-Whip site can be seen here: http://www.g4icd.co.uk/baluns.htm

Here is a photograph of the very high quality G-Whip OCFD antenna product www.gwhip.co.uk :

An 'Off Set Centre Dipole' - OSCD - Fed made by G Whip Antennas
G-Whip Antennas - www.gwhip.co.uk

M0CVO ANTENNAS
HW-20HP Multi-band Antenna, 20 - 6m,
400W, 50Ω
Designed and manufactured by M0CVO
Made in England

HW-20HP Off Centre Fed Dipole - produced by M0CVO
6.76 metres long one side and 3.38 metres on the other side.
http://m0cvoantennas.webs.com

M0CVO produces a couple of off centre fed dipoles, the HW-40HP and the HW-20HP. Both antennas handle 400 watts - the HP designation refers to high power.

The M0CVO HW-20HP is 10.14m in length and covers 6 bands - 20, 17, 15, 12, 10 & 6m, no ATU, and is said to also work on 30m & 40m with an ATU. Can be mounted as a horizontal, inverted vee or a sloper. VSWR is said to be 1.4 on 20m, 2.8 on 17m, 1.1 on 15m, 1.0 on 12m, 1.0 on 10m and 1.5 on 6m. The antenna is6.76 metres long on one side and 3.38 metres long on the other side. This uses a 66.6% / 33.3% formula.

The HW-20P was reviewed by Steve Nichols, G0KYA, in the January 2012 edition of RadCom.

The HW-40HP is 20.28m in length and will operate on 40, 20 and 10m without an ATU and 80, 60, 15, 6 and WARC Bands with an ATU. (Presuably one leg is 13.52 metres long and the other 6.76 metres if it follows the same 66.6% / 33.3% formula as the HW-20HP).

Here is a graphic of an Off Centre Fed Dipole typical of those available in the USA:


L1
L2
BUX BALUN
BUXCOMM 3/16" UV resistant Dacron Rope
BUXCOMM 3/16" UV resistant Dacron Rope
RG8X
RG=50 ohm coaxial cable
{BUXCOMM (C) 1995-}

BUX COMM, "WINDOM" or off-center fed flat-top wire antenna

Fact: Antenna feed-point impedance increases as antenna heigth above ground increases;

Given the above fact, a windom at
20 to 40 feet above ground Z=200 ohms, use a 4:1 BALUN
40 to 55 feet above ground Z=250 ohms, use a 5:1 BALUN
55 to 70 feet above ground Z=300 ohms, use a 6:1 BALUN

When ordering, please specify BALUN ratio.

Visit: www.WindomAntenna.com
or www.HamRadioExpress.com

Covers Ten (10) Ham bands without an antenna tuner.
BUXCOMM Model 802134


10 band BUXCOMM Windom installed as an "Inverted V"
4:1 BALUN
110 degrees
Short Leg
Long Leg
35 ft.
8 ft
8 ft
(C) 1992 BUXCOMM

Typical BUXCOMM 802134 or 802134 "HP" Windom installed as an Inverted V.

Windom total length is 134 ft, when installed as an Inverted V, distance required is 118 ft.

http://www.buxcomm.com


34'
13'
21'
Matching Unit
10' Vertical Radiator
Line Isolator
RG-8X to Transmatch

Carolina Windom for 20 metres to 10 metres
http://www.radioworks.com/ccwcover.html


4:1 Balun 1-30MHz - MØUKD

M0UKD - 4:1 balun. It is 17 bifilar turns on a half inch ferrite rod. 50Ω - 200Ω, 1-30MHz
http://www.m0ukd.com/Carolina_Windom/index.php



M0UKD Line isolator - 10 turns RG8 on a half inch ferrite rod
http://www.m0ukd.com/Carolina_Windom/index.php


NEW CAROLINA WINDOM
By Len Carlson, K4IWL
66 Feet
4 : 1 Balun
25 Feet
41 Feet
10 Feet RG58
Line Isolator (Choke)
Coax To Transceiver
Not to scale

Windom design for 40m 20m 15m and 10m by K4IWL
http://www.hamuniverse.com/k4iwlnewwindom.html

More information on this general subject at BucksCom: http://www.packetradio.com/windom.htm **or** http://www.buckscom.com/pdfzips/windom.pdf

Commercial Suppliers:

G-WHIP Antennas (UK) : http://www.gwhip.co.uk
M0CVO OCFD Antennas (UK) : http://m0cvoantennas.webs.com

In the U.S.A:
Bux Comm Windom Antennas : http://www.buxcomm.com
Buck Master OFC Dipole Antennas : http://hamcall.net/
Alpha Delta : http://www.alphadeltacom.com
Carolina Windom : http://www.radioworks.com/ccwcover.html

See some Windom - Off Centre Fed Dipole - designs at these links:
http://users.erols.com/k3mt/window/windom.htm
http://www.dxzone.com/cgi-bin/dir/jump2.cgi?ID=7478
http://www.radioelectronicschool.net/files/downloads/ocfdipole.pdf
http://www.hamuniverse.com/k4iwlnewwindom.html
http://www.g4nsj.co.uk/windom.shtml
http://www.m0ukd.com/Carolina_Windom/index.php

Semi-Permanent Antenna Installations

If it impossible to install a permanent aerial, then another option is to use an antenna designed for portable or mobile work deploying it only as and when necessary in the back yard or garden - perhaps supported with a portable tripod and/or guy ropes.

From the ideas above it should be possible to rig up a semi-permanent or removable antenna for low visual impact.

There are also very many portable antennas produced commercially that might be very useful to utilize on a semi-permanent basis. Commercially bought antennas can be very expensive indeed, especially when compared to 'home brew' aerials, but examples that immediately spring to mind for consideration include: The DMV-Pro, I-Pro, G Whip or G Whip Backpacker, the TW2010 from Transworld Antennas, the Sigma5 from Force 12 and aerials from SuperAntennas. Sandpiper Aerial Technology offer a very good choice of aerials such as the MV and MV-Portable, Buttie or Walkabout mk11 at very attractive prices. http://www.sandpiperaerials.co.uk There are very many other compact and portable antenna systems that are widely available. Check out all the amateur radio dealers for more ideas.



The DMV-Pro Antenna from ProAntennas (shown above) could be used in a back garden whenever required as could the company's I-Pro antenna. The DMV-Pro uses two fibreglass arms that allow the wire aerial to be supported in a number of different configurations such a "V" shaped, "L" shaped, "M" shaped and Delta. The aerial elements are fed to a 4:1 balun using low loss twin feeder, the balun is then connected to an auto ATU, such as the LDG Z-11 Pro, which is connected to the transceiver using coaxial cable. A versatile idea that could also be implemented on a DIY basis with a little experimentation! http://www.proantennas.co.uk

Geoff G4ICD / GJ4ICD mentions the original design, the JJ1VKL published in CQ ham radio Sep' 2000 in Japan. "This one goes back to 2000 and is now copied by several antenna manufacturers in the UK" It is an HF multi-band Delta loop antenna for 3.5-50MHz
http://www.geocities.jp/yoshiki_ja/deltae.htm





An Original Delta Loop design by JJ1VKL
Read more here: http://www.geocities.jp/yoshiki_ja/deltae.htm



Delta Loop by Arthur M0PLK (SQ2PLK)
Details at http://pdxa.one.pl/articles.php?article_id=17
Available at http://ham-radio.urbasket.eu and http://www.vpa-systems.pl/

STEALTH / COVERT / HIDDEN or DISGUISED ANTENNAS:

Ideas from **G4ILO** - Stealth Antennas: http://www.g4ilo.com/stealth.html

VK2ZOI - "Flowerpot" Antennas

Some ideas by VK2ZOI about producing inconspicuous antennas - perhaps disguised as a plant in a flower pot! There are ideas for 6 metre, 2metre and 70cm antennas including a dual band 2,/70cm design.


UPVC conduit cap
Fishing line
Top of radiator element
345 mm
457 mm
25 mm conduit
Coax inner
235 mm
Sleeve on outside of conduit
447 mm
324 mm
Intact length of coax
Top of coil
9 turns on 25 mm former

VK2ZOI Flowerpot Antenna projects
http://vk2zoi.com

All Band HF Vertical Antennas (non resonant) - 'Untennas'

So this is where the search for a multi-band antenna begins. It's a difficult task especially if space is limited. First considerations might lie with the commercially available options that are available. Commercially manufactured aerials are available at widely varying price points - perhaps from under £100 to many many £100's

One of the first commercial multi-band antennas that many keen new amateurs come across is something like the Comet CHA250B, or the Diamond BB7V or Moonraker GP2500 (pictured right). These are broad-band antennas and look like large CB antennas with a matching network at the base. Such antennas claim to allow operation of all bands between 80 metres and 6 metres with acceptably low v.s.w.r. Sounds like the perfect multi-band solution, especially as Comet and Moonraker are well known names that make excellent products.

These multi-band antennas have their critics though: Sure enough, they exhibit a seemingly acceptably low v.s.w.r. across the whole of HF, but low v.s.w.r. isn't everything. Ctitics do, in fact, call these types of broadband antennas glorified dummy loads - a bit unfair possibly, but maybe they have a point when most of your transmitter's precious power is wasted as heat rather than radiated as a useful RF signal!

The only way a simple, single vertical radiator can be made to work on across such a wide range of frequencies is by having a broad band matching transformer at the base of the radiator. This will inevitably result in the absorption of some - or much of the transmitter's power - the power loss represented by the heating up of the coils/transformer rather than actually being radiated as a useful signal by the antenna's vertical element.

Such antennas could present a loss of around 6 - 12 dB compared to a resonant antenna - how do do fancy putting all 100 of your precious watts in to the antenna and only getting 6.31 watts of effective power radiated?

Maybe that's a bit simplistic, so Martin G8JNJ has many superb articles analyzing the CHA250B and similar antenna designs here: http://g8jnj.webs.com/cometcha250b.htm

The article Anatomy Of The Comet CHA250B by VK5ZBD can be found here:
http://www.radiomanual.info/schemi/ACC_antenna/Comet_CHA-250BX2_anatomy.pdf
(Formerly found at this site http://www.vk5zdb.com/CHA250BXII.htm)

G8JNJ is also developing a better version of this type of antenna here:
http://g8jnj.webs.com/broadbandhfvertical.htm

I admit that, due to limited space, I considered this type of antenna when first starting out - but in the end dismissed them due to the extreme inefficiency and power loss problems. They should not be entirely discounted however, because if this really is all that can be accommodated at one's QTH then at least such an aerial will at get you on the air - and on all bands - at least in some sort of fashion. Many amateurs use these aerials with success, so they do have a place. Have a look and decide for yourself.

Other similar types of broad-band antenna:

There are a number of very similar designs (i.e. longish vertical radiator, with a transformer / unun at the base) available from some other British suppliers:

The G Pro-Whip 'Widebander' antenna (see http://www.gwhip.co.uk/);
The ProWhip Portable Antenna (see http://www.prowhipantennas.co.uk/);
Snowdonia Radio Company (SRC) - various types of wideband antennas (see http://www.snowdonia-radio-company.co.uk)

All these antennas appear to be based around an UNUN (typically 9:1) matching transformer at the base of the aerial. These aerials cost considerably less than those previously mentioned. The G Pro Whip and Pro Whip Portable offer particularly convenient portable operating opportunities as they are based on one of my favourite methods of antenna support - a long telescopic fibreglass (fishing) pole. Really neat!

For the 'fishing pole' types, essentially there is a vertical radiating wire of about 7 to 10 meters long, a 10m long horizontal counterpoise wire and the 9:1 unun at the base. This makes for a simple and attractive installation proposition (but remember the penalty of power losses) - all these aerials will be easy to install for permanent, semi-permanent use and easily removable or portable operating.

Considering the 10 meter vertical type, the performance on 40 meters (1/4 wave) should be quite reasonable, with reduced performance on other bands.

G-WHIP ANTENNA PRODUCTS
PRO

G-WHIP G Pro Whip antennas (now discontinued)
by Geoff Brown G4ICD
2011/2 - See G-WHIP'S WideBander Antenna as an alternative
http://www.gwhip.co.uk/

Buy (or build) a 9:1 UNUN and Make Your Own:

If you already have a 10m telescopic fibreglass fishing pole and some wire, then you could easily wind a 9:1 unun, or even buy one from suppliers such as G WHip Antenna products for a reasonable cost. So, you could make your own aerial with 10m vertical radiator working against the 10m counterpoise and fed to the ATU via the 9:1 unun at the aerial's base - just for fun, for experimentation, analysis or for permanent installation or portable work. (The telescopic pole must be fibreglass not carbon fibre)

Martin G8JNJ, suggests that a slightly better way to home-brew a broadband HF aerial might be to cut a vertical aerial for about 8.5 MHz, i.e. not a resonant 1/4 wave on any amateur band, but optimised to present a moderate impedance on as many bands as possible. In which case the vertical wire would be about 8.8 metres long, working against the counterpoise, and fed to the a.t.u. via an unun - perhaps 6:1 or 9:1 - this is all open to further research and experimentation! See http://g8jnj.webs.com/currentprojects.htm

G0KYA has also written lots of interesting articles about antennas and several pieces about using a 9:1 unun and a length of wire. He found that a wire length of 19.8 metres offered a good compromise for a multi band aerial. Read G0KYA's blog here: http://g0kya.blogspot.com/search/label/antennas

More : http://g0kya.blogspot.co.uk/search/label/antennas

Interestingly 2W0SAK of Snowdonia Radio Company recommended an antenna wire length of 7.13 metres with their 9:1 unun - or for better efficiency a wire that is 19.8 metres long which would be run out horizontally. Both the 7.13 m and 19.8 metre lengths should cover the 80m to 10m bands.

Freq Coverage	Wire Length	or try
7 - 29 (50) MHz	2.74 m	6 m
3.5 - 29 (50) Mhz	7.13 m	9.8 m or 16.1 m
3.5 - 29 (50) MHz	19.8 m	21.9 m or 26.8 m
1.8 - 29 MHz	29.0 m	29.9 m
1.8 - 29 (50) MHz	39.6 m	36.6 m

High Quality Baluns and UnUns Available From www.gwhip.co.uk - either boxed and ready to use or just the core and quality windings suitable to put into own box or project.


MULTIBAND RANDOM WIRE UNUN (UNBALANCED TO UNBALANCED)
FOR USE WITH RIGS WITH BUILT IN AUTOTUNERS
RANDOM WIRE ANTENNA
23' LONG FOR 10 THRU 40M COVERAGE
50' LONG FOR 10 THRU 80 METER COVERAGE
GROUND CONNECTION
SHORT COAX TO CONNECT UNUN
TO SO-239 CONNECTOR
SO-239, 50 OHM
TO RADIO
T130-2 CORE
15 TO 19 BIFILAR
TURNS INSULATED
WIRE
MOUNT IN A WEATHERPROOF
PLASTIC ENCLOSURE

Above is a neat design for an "Untenna" KC8AON - Link: http://www.angelfire.com/electronic2/qrp/unun.html

For a jack of all trades try a high quality GWhip "Widebander Antenna"

G0KYA writes a very useful piece in his blog:

http://g0kya.blogspot.com/search/label/antennas



In the next round of tests I used the same 9:1 Un-Un wound using PVC covered cable and a T200-2 toroid. Note in the photograph that the PVC tape is only used to keep the turns neatly arranged.

If you want to build your own follow these instructions:

Building a 9:1 unun
To understand how to construct an unun lets build a 9:1 version. You will need a T-200 (red) toroid and three pieces of wire, each 24 inches (60cm) long . It will also help if you a small plastic box with an SO239 socket mounted at one end and with two wing nuts or mounting posts at the other. In the UK you can buy a small plastic box from Maplin which is watertight with a rubber seal, yet inexpensive.
It will help if the wires are different colours, although that isn't critical if you have a multimeter available. It just makes it a lot easier to follow these instructions.
For the sake of this explanation I'll assume that you are using green, red and black pieces of wire.
Put the three pieces of wire together and wind them carefully onto the T130-2 toroid. Place the wires (left to right) green-black-red, and wrap nine turns on to the toroid.
Try not to let the wires overlap.
You should end up with a toroid with three wires extending from the left winding and three wires extending from the right.
Now twist and solder the left black wire with the right red wire. This can be covered with PVC tape once complete.
Now twist the left green wire with the right black wire. Strip the ends of the two wires, twist and solder them together leaving the length about 2” long from the toroid.
Finally trim and strip the remaining right green wire and solder another 5” piece of green solid wire to it.
Now take the left green wire and right black wires that you twisted together and connect them to the centre pin of the SO239 socket – this is the input side and will connect to your radio via a length of coax.
One of the green wires is now soldered to the ground connection of the SO239 socket. The other end of the wire you soldered on (which is connected to it) becomes the earth connection for the unun and typically goes to a ground stake and ground radials.
This leaves the remaining red wire which connects to the other wingnut and will become the connection for the antenna.
If you are worried about the wires unravelling you can either use PVC tape to hold them in place or plastic cable ties.
So how do we use an unun? Lets look at a typical example.

This time I erected a 10m high fishing pole and attached a 65ft quarter wave antenna for 80m in an inverted L fashion. That is, 10m up and then 9.8m out to the nearby summerhouse.

This was arranged away from the house and fed with 12m of RG8 coax, a single earth stake and two 20ft radials at the feed point..

Here are the SWR readings at the end of the coax:
3.5MHz – SWR 3:1
3.65MHz – SWR 4.2
3.8MHz – SWR 5.9
7.10MHz - SWR 13.6:1
10.1MHz – SWR 2.5:1
14.2MHz – SWR 3.3:1

18.14MHz – SWR 1.8:1
21.2MHz – SWR 2.4:1
24.9MHz – SWR 1.9:1
28.5MHz – SWR 1.2:1

From this you can see that by shortening the wire to 65ft from the original 85ft you gain 80m, but lose 40m. The rig (FT2000) would quite happily tune seven bands with its internal ATU. Here are the quick comparison results against my 80m Windom and parallel-fed dipoles in the loft for 40m, 20m, 17, and 10m.

80m
Not as good around the UK as the Windom - probably due to the maximum current being in the vertical section. Modelling shows the antenna to be down about 10dB on a low dipole.
30m
Lithuania similar. Other EU and Italy similar. Bulgaria down 2 S points
17m
Similar – inverted L has slight edge at times. Slightly noisier
15m
Better than Windom by about 1 S point.
10m
Much better than Windom, dipole and mag loop around Europe via Es, by about 2 S points. Slightly more noise (+ 1 S point).

From this I can see that I need to do more tests, especially on 20m, but for an all-in cost for the antenna of about £15-£20 it shows promise. If you have a tree then the up and out idea with a 65ft wire looks quite good. A way to get 40m back would be to put a 40m trap in the wire at the 10m mark. If you don’t fancy making your own UnUn you can buy the whole antenna from the Snowdonia Radio Company for £35 inc P&P – see http://www.snowdonia-radio-company.co.uk/srcproducts.html [From a collection of excellent articles from G0KYA] Link to SRC: http://www.snowdonia-radio-company.co.uk

GWhip Antennas, and ProWhip Antennas all supply this type of antenna as a commercial item.

CONCLUSIONS?

Arguably the most effective, simplest and, indeed, cheapest way to attain multi-band operation is by using a full size resonant dipole for each band of interest - perhaps having a couple suspended at any one time and swapping aerials when other bands are needed.

As mentioned in the introduction this is a little inconvenient which is why the holy grail of so many amateurs is one antenna that that will do everything - perfectly. As we have seen such an aerial does not exist, and never will due to those pesky laws of physics. Compromises will always have to be made; compromises of efficiency, size, number of bands and bandwidth per band etc - nevertheless there are enough options available to be able to choose a configuration of antenna or antennas that should be able to make the best use of precious transmitter power for a particular circumstance.

My two key criteria are that the antenna should be truly resonant on the band(s) of interest and that the radiating elements should be as near to full size as possible, relative to the wavelength(s) being used, to ensure the best possible efficiency (i.e. lowest loss of power). This means full size quarter wave vertical or full size half wavelength long trapped dipole.

I don't especially like aerials that are shortened by using a loading coil, but accept that such an arrangement is sometimes necessary for the longer wavelength bands. Top Band is a real problem in average size gardens. Where the is a coil, a trap, or transformer there will be some loss or reduced efficiency introduced into the antenna system. I do find that using a trap is an excellent compromise - the 80m / 40m Inverted L and the 20m / 10m trapped dipole work especially well. If I could not use the Inverted L, my next favourite option is the Loop or a fan (Parallel) dipole.

All the pros and cons have to be weighed up to find the best compromise for particular operating circumstances. I hope that this page has given new operators some ideas to take away and mull over, but remember those words from Joe Tyburczy WB1GFH that this page started with:

"When you put up your antenna is also crucial. I must mention here the importance of what many early hams called "antenna weather". That is, snow, sleet, freezing rain, or combination of all the above. It has been proven time and time again that any antenna installed in conditions better than abysmal will not function worth a darn. Or, put another way, it takes bad weather to put up a decent antenna. Dark and cold New England winter days are ideal for this activity. Any antenna erected on such a day will inevitably produce miracles."

Some Further Reading:

Understanding Antennas For The Non-Technical Ham
A Book By Jim Abercrombie, N4JA
basicantennas.pdf

More Antenna Ideas by other amateurs (.doc)

ARRL document Multi Band Dipoles Compared (.pdf)

High Quality Baluns and UnUns Available From www.gwhip.co.uk

Useful Aerial Rigging Accessories



Line-Lok guy runners from ClamCleats - fantastic for guying antenna masts quickly and successfully
http://www.cleats.co.uk http://www.clamcleat.com

Reusable Nylon Hose Clip / Reusable Circular Clamps
Useful for securing telescopic fibreglass poles - e.g. holding each section in place in windy weather or to use as a guying ring (spider)
(Herbie Clips) (Kaf-flex Nylon Clamps)
http://www.malpasonline.co.uk
http://news.thomasnet.com
http://www.hclfasteners.co.uk/acatalog/Herbie-Clip.html
http://www.cheapham.com/products/S9V31-Replacement-Clamps.html
http://rotocon.homestead.com/shoponline2.html

OTHER THINGS THAT MAY BE NEEDED:

POLE(S) Aluminium, fibreglass or wood ; POLE TO POLE CLAMPS ; MET POST(S) ; NYLON CORD or PARA CORD ; SPIDERS / 3 or 4 WAY GUY RINGS ; PULLEYS ; SNAP HOOKS ; DEE SHACKELS ; GROUND STAKES for anchoring guy ropes ; DOG BONE or EGG INSULATORS ; DIPOLE CENTRES ; EARTHING STAKE ; V BOLTS ; ROPE GRIPS ; THIMBLES ; SLEEVE JOINER(S) ; T&K BRACKETS ; TRIPOD or other GROUND MOUNTING HARDWARE ; STAINLESS STEEL M6 Nuts Bolts and Washers ; SPADE and / LUG TERMINALS ; SELF AMALGAMATING TAPE ; HEATSHRINK ; WEATHERPROOFING SEALANT ; STAINLESS STEEL JUBILEE CLIPS.

TRIMMING AERIALS

Antenna Trimming Chart

This following information below could be very useful indeed when constructing aerials and is compiled by DX Zone / Radio Works from the web page at: http://www.dxzone.com/cgi-bin/dir/jump2.cgi?ID=13444

Use this chart as an aid in trimming the length of your antenna. It gives you an idea of the change in wire length needed to move antenna resonance a specific number of KHz.

* Dimensions are for each leg of a half-wave dipole
* For quarter-wave antennas (i.e. verticals) use the dimensions directly from this chart
* Full-wavelength antennas (loops) - multiply the chart dimensions by four (4) and change the overall length of the antenna by that amount.

Lengths are estimates. Many factors will affect their exact value.

To move	80/75 m	40 m	20 m	15 m	10 m
-500 kHz	+8' 4"	+2'	+8"	+3"	+1.5"
-400 kHz	+6' 8"	+1' 9"	+6.5"	+2.5"	+1.25'
-300 kHz	+5'	+1' 4"	+5"	+1.75"	+1"
-200 kHz	+3' 4"	+10"	+3.25"	+1.25	+5/8"
-100 kHz	+1' 7"	+5"	+1.5"	+1/2"	+3/8
00 kHz	0	0	0	0	0
+100 kHz	-1' 7"	-5"	-1.5"	-1/2"	-3/8"
+200 kHz	-3' 4"	-10"	-3.25"	-1.25	-5/8"
+300 kHz	-5'	-1' 4"	-5"	-1.75"	-1"
+400 kHz	-6' 8"	-1' 9"	-6.5"	-2.5"	-1.25'
+500 kHz	-8' 4"	-2'	-8"	-3"	-1.5"

Example:

You have measured the SWR of your 40 meter dipole at various frequencies across the band. You have determined that the SWR is lowest at 7.00 MHz. You actually want the lowest SWR to occur up in the sideband portion of the band, so you need to move resonance up in frequency about 200 KHz.

According to the chart, to move +200 KHz on 40 meters, you will have to shorten each leg of the dipole 10" (-10"). The overall length of the antenna is shortened a total of 20 inches.

Lengthening or shortening the antenna is done at the end insulators. To shorten the antenna, unwind the antenna wire as it wraps around itself at the end insulator. Move the insulator several inches toward the center of the antenna. Re wrap the antenna wire to secure the end insulator. Do not cut the wire. Wrap it back around the antenna wire. You may need to increase the antenna later. [From Radio Works / DXZone]

KNOTS FOR SECURING WIRE ANTENNAS

I have found the Bowline to be one of the most useful, it is strong and easy to tie. A Bowline will not slip in any circumstances and, usefully, the more load that is put on it, the tighter it gets.



The Bowline Knot

A Bowline can be used to tie two ropes together and should be used to tie a support rope to a pulley, dipole centre and other antenna items.

It's important to use the correct knot for the job when fixing up wire antennas. I find the Bowline is a very useful for fixing end, egg and dog-bone insulators to the ends of the wire and/or ropes.

The Buntline Hitch is an excellent knot as is the Round Turn & Two Hitches, Anchor Bend (Anchor Hitch) knots which are very good for tying a rope to a pole or a mast.

The Bowline is most useful for fixing end, egg and dog-bone insulators to the ends of the wire and/or ropes.

A Double Sheet Bend can join two pieces of rope together - even if they are of unequal size.

'Animated Knots' will show you how to do them. Visit http://www.animatedknots.com

More websites with knot information : http://www.netknots.com/ http://www.southee.com/Knots/Index.htm

The correct knot will ensure that the antenna will be as strong as possible.

LINKS

Understanding Antennas For The Non-Technical Ham - A Book By Jim Abercrombie, N4JA :
PDF Book: http://www.hamuniverse.com/basicantennas.pdf
HTML page: http://www.hamuniverse.com/n4jaantennabook.html

G4ILO - Stealth Antennas: http://www.g4ilo.com/stealth.html

All Band Doublet Antenna by M0MTJ :
http://www.mds975.co.uk/Content/amateur_radio_antennas_06.html#All_Band_Doublet_Antenna

All Band Doublet Antenna : http://www.hamuniverse.com/hfdoublet.html

All Band Doublet Antenna by AI4JI : http://www.ai4ji.com/Projects/antennas/doublet.htm

All Band Doublet Antenna by G3RWF: https://rsars.files.wordpress.com/2013/01/80-10m-doublet-antenna-g3rwf-11.pdf

All Band Doublet Antenna by W4NEQ: http://w4neq.com/htm/doublet.htm

All Band Doublet Antennas and Baluns by G4POP: http://g4pop.blogspot.co.uk/2008/10/doublet-antennas-and-baluns-my-friend.html

All Band Doublet Antenna by VK6YSF: http://vk6ysf.com/allbandhfdipole_Mk2.htm

All Band Doublet Antenna by M0DAD : http://www.delboyonline.co.uk/m0dad/doublet_all_band_antenna.htm

Introducing the "All-Band" Doublet: What the Student and the Instructor Should Keep in Mind by L. B. Cebik, W4RNL :
http://ftp.unpad.ac.id/orari/library/library-sw-hw/amateur-radio/ant/docs/Introducing%20the%20All-Band%20Doublet.htm

M0WYM - QRP Fan Dipole: http://www.radiowymsey.org/FanDipole/fandiploe.htm

Multi Band Dipoles Compared: http://www.arrl.org/tis/info/pdf/9611073.pdf http://www.dxzone.com/cgi-bin/dir/jump2.cgi?ID=7499

Practical Dipole Antennas Compared: http://www.qsl.net/ta1dx/amator/practical_dipole_antenna.htm

What Antenna For H.F? by Wrexham ARS: http://www.qsl.net/wars/construct/hf_ant.htm

Multiband Loft Dipoles: http://www.qsl.net/g0kya/multibanddipole.pdf

My Top Five Backyard Multi-Band Wire HF Antennas by L. B. Cebik, W4RNL:
http://www.users.on.net/~bcr/files/backyard%20wire%20antennaes.pdf

More Links

Loop Antennas - Delta Loops and Square (Quad) Loops and more:

Delta Loops for HF - "You'll love lower noise and relative gain over a dipole"
http://w5sdc.net/delta_loop_for_hf.htm

One Stealthy Delta - This HF antenna keeps a low visual profile while attracting plenty of attention on the air. An excellent and amusing article by Steve Ford, WB8IMY
http://www.sgcworld.com/Publications/Articles/237qst0502.pdf

Random length multi-band delta loop antenna – A good antenna for when a dipole isn't enough by KC8AON
http://www.i1wqrlinkradio.com/antype/ch10/chiave1827.htm

An Easy to Install Vertical Loop for 80-6 Meters by John Reisenauer, Jr. KL7JR
http://www.hamuniverse.com/kl7jreasyvertloop.html

40m-10m DELTA LOOP ANTENNA - GU3WHN
http://www.rsars.org.uk/ELIBRARY/ANTENNAS%20DOCS/40m-10m%20%20DELTA%20LOOP%20ANTENNA%20-%20GU3WHN%20iss%201.3.pdf

M0PLK Multiband Delta Antenna - By Arthur M0PLK (SQ2PLK)
http://pdxa.one.pl/articles.php?article_id=17 available at http://ham-radio.urbasket.eu and http://www.vpa-systems.pl/

H5ANX Mk4 Delta Loop Design by Sajid Rahim
http://www.eham.net/articles/10738

Multiband H.F. Delta Loop by IW5EDI:
http://www.iw5edi.com/ham-radio/?dl2hcb-multiband-delta-loop,28

SGC Stealthy H.F. Delta Loop:
http://www.sgcworld.com/Publications/Articles/237qst0502.pdf

KL7JR Easy H.F. Delta Loop:
http://www.hamuniverse.com/kl7jreasyvertloop.html

H.F. Loop Antenna from Radioworks:
http://www.radioworks.com/nloop.html

W6ZDO Portable H.F. Delta Loop Project:
http://www.fros.com/KI0GU/w6zodelta.htm

Loop Antenna Notes by "Yukon John" KL7JR
http://www.hamuniverse.com/kl7jrloopnotes.html

Build a Multi-Band Mono Delta Loop for 40, 30, 20 and 15 Meters by Jose I. Calderon (DU1ANV)
http://www.para.org.ph/membersarticles/DU1ANV/Multi-Band%20Mono%20Delta%20Loop%20ant.pdf

DL2HCB Multiband Delta Loop
http://www.iw5edi.com/ham-radio/?dl2hcb-multiband-delta-loop,28

The Delta Loop (Skywire) Antenna - Legends, Theory and Reality
http://dk5ec.de/deltaloop-eng.htm

Loop Antenna notes and ideas from Radioworks
http://www.radioworks.com/nloop.html

Delta Loops by GW7AAV
http://www.cqhq.co.uk/2009_05_01_archive.html

More Delta Loop links:
http://www.i1wqrlinkradio.com/antype/delta_loop.html

Magnetic Loops:

Small Transmitting Loop Antennas (Magnetic Loop Antennas) by Steve Yates - AA5TB
http://aa5tb.com/loop.html

Fibreglass Telescopic Fishing Poles

http://www.sotabeams.co.uk

http://www.skyblueleisure.co.uk/acatalog/Telescopic_Poles.html

see: Bowmanarcher on ebay

Line-Lok guy runners for support pole guy ropes by ClamCleats (excellent) :
http://www.clamcleat.com/cleats/cleats.asp?menuid=7

Other Aerial Supports

http://www.tecadi.de/

Commercial Antennas

GWhip Antenna Products: http://www.gwhip.co.uk/

Spectrum Communications: http://www.spectrumcomms.co.uk

Sandpiper Aerial Technology: http://www.sandpiperaerials.co.uk

SOTA Beams: http://www.sotabeams.co.uk/

W.H. Westlake - for wire, cable, feeder, connectors & components: http://www.whwestlake.co.uk/

Moonraker: http://www.moonrakerukltd.com

AERIAL PARTS Of Colchester: http://www.aerial-parts.co.uk

SRC - Snowdonia Radio Company: http://www.snowdonia-radio-company.co.uk

Cobwebb Antenna: http://www.g3tpw.co.uk

ProAntennas: http://www.proantennas.co.uk

ProWhip Antennas: http://www.prowhipantennas.co.uk/

Hustler Antennas from DX Engineering. 4-BTV, 5-BTV & 6-BTV compact antennas: http://www.dxengineering.com

Butternut Antennas from Bencher Inc: http://www.bencher.com/ham/

Cushcraft Antennas from MFJ: http://www.cushcraftamateur.com

Comet Antenna: http://www.cometantenna.com

Diamond Antenna: http://www.diamond-ant.co.jp/english/amateur/antenna/ama_antennas.html

Hygain Antennas from MFJ: http://www.hy-gain.com

Alpha Delta Communications - Dipole and Parallel (Fan) Dipole Multi-Band Antenna Designs http://www.alphadeltacom.com/

WIMO Antennas and Accessories: http://www.wimo.com/cgi-bin/verteiler.pl?url=wireantennas_e.html

GAP Antennas: http://www.gapantenna.com

True Ladder Lines and Wire Antennas: http://www.trueladderline.com/index.html

Radio Wavz - wide range of amateur radio antennas: http://www.radiowavz.com

Radio Works - amateur radio antenna manufacturer and supplier: http://www.radioworks.com/

Force 12 Antennas (Sigma5) : http://www.force12inc.com

Transworld Antennas (TW2010 Adventurer) : http://transworldantennas.com

Superantennas: http://www.superantennas.com

Amateur Radio Suppliers

RADIOWORLD http://www.radioworld.co.uk/

ROCKET RADIO http://www.rocketradio.co.uk/

SPECTRUM COMMUNICATIONS http://www.spectrumcomms.co.uk/

MOONRAKER http://www.moonrakerukltd.com/

HAYDON COMMUNICATIONS http://www.haydon.info/

KZJ Communications (DeeComm) (Haydon West Midlands) a good shop on EBAY at http://stores.ebay.co.uk/kzjcommunications

WATERS & STANTON http://www.wsplc.com/

MARTIN LYNCH & SON http://www.hamradio.co.uk/

DIODE COMMS http://www.diodecomms.co.uk

NEVADA RADIO http://www.nevadaradio.co.uk/

LAM COMMUNICATIONS http://www.lamcommunications.net

ANCHOR SUPPLIES http://www.anchorsupplies.com

VINE ANTENNAS: http://www.vinecom.co.uk/

Projects and Information

Flower Pot Antenna - http://vk2zoi.com - and interesting link to an interesting antenna design that was very kindly sent to me by Phil M6MRP

G4ILO - Stealth Antennas: http://www.g4ilo.com/stealth.html

M0WYM - QRP Fan Dipole: http://www.radiowymsey.org/FanDipole/fandiploe.htm

See Multi Band Dipoles Compared: http://www.dxzone.com/cgi-bin/dir/jump2.cgi?ID=7499

See Practical Dipole Antennas Compared: http://www.qsl.net/ta1dx/amator/practical_dipole_antenna.htm

The ALL Band HF Doublet on Ham Universe: http://www.hamuniverse.com/hfdoublet.html

Multi-band Inverted V $4 Special by Joe Tyburczy, W1GFH: http://www.qsl.net/wb1gfh/antenna.html
http://www.hamuniverse.com/fourdollarspecialw1gfh.html

The Norcal Doublet Antenna: http://www.norcalqrp.org/norcaldoublet.htm

N4JTE - 6 Band Ribbon Dipole by N4JTE
http://n4jte.blogspot.com/2009/04/n4jte-6-band-ribbon-antenna-35.html

http://g8jnj.webs.com/

http://www.astromag.co.uk/vertical/

http://www.hamuniverse.com/multidipole.html

http://www.hamuniverse.com/fourdollarspecialw1gfh.html

http://n4jte.blogspot.com/2009/04/n4jte-6-band-ribbon-antenna-35.html

http://www.dxzone.com/cgi-bin/dir/jump2.cgi?ID=20420

http://www.tc006a8364.pwp.blueyonder.co.uk/brats/radio_07/advanced/mathequat_1.htm

http://www.tdars.org/library/TechTopics/tech22.html

http://www.rsgb.org/tutors/advanced/pdf/maths_primer.pdf

http://www.users.icscotland.net/~len.paget/Mini%20quad.pdf

http://www.users.icscotland.net/~len.paget/5%20band%20Inverted%20L.pdf

http://www.users.icscotland.net/~len.paget/Inverted%20L%20adding%20top%20band.pdf

http://www.btinternet.com/~shaun.scannell/club/w3dzz.htm

http://homepage.ntlworld.com/lapthorn/70cms.htm

http://mw0idx.co.uk/2mPortPockBeamGW0VMW.html

http://www.dxzone.com

http://www.arrl.org/tis/info/pdf/0207040.pdf

http://www.dxzone.com/cgi-bin/dir/jump2.cgi?ID=7466

W2BLC - Amateur Radio Antenna Ideas: http://www.w2blc.us/linkant.htm

End Fed Antennas

GWhip End Fed Antennas:
http://www.gwhip.co.uk

Cross Country Wireless designed and manufactured End Fed Antenna
http://www.crosscountrywireless.net/end_fed_antenna.htm
http://www.crosscountrywireless.net/CCW_End_Fed_Antenna_Operating_Manual_v1.1.pdf

Hy End Fed antennas - single and multi band end fed antennas by PA3EKE.
http://www.hyendfedantenna.nl http://www.pa3eke.nl
Review of Hy End Fed antenna by PC4T: http://dutchhamradio.blogspot.com/2010/09/hy-end-fed-antenna.html

Par End Fedz Antennas - now manufactured and supplied by Larry, AE4LD of LNR Precision End Fedz:
http://www.lnrprecision.com

W3EDP and Other Antenna Links

http://va3qv.wordpress.com/tag/w3edp-antenna/

http://va3qv.wordpress.com/2009/10/18/good-results-with-re-worked-w3edp/

http://ve3clq.blogspot.com/2011/01/w3edp-antenna.html

http://bv3fg.tripod.com/ant/end_fed.htm

http://ham-antennas.blogspot.com/2011/02/dl2hcb-multiband-delta-loop.html

http://sv3auw.blogspot.com/2009/11/sloper-7mhz.html

Back to Aerial Types....

More "thinking out loud" notes and queries which I intend to edit and condense (honestly!):

Multi Band HF Antennas

Covering ALL the HF bands with separate antennas dedicated to each band would take up a large amount of space which many of us don't have. Either we must decide on a limited number of favourite bands and put up a specific antenna for these or try to find a multi band antenna that covers all the bands of interest.

The perfect HF multi band is many an amateur radio operator's holy grail. If you haven't already seen it, you can read more about an All Band Antenna Marvel covering 160m to 70cms on this external link: Hamuniverse ALL BAND N4UJW Antenna

So, multi-band antennas necessarily involve compromises which usually translate into lower efficiency i.e. the antenna will not effectively radiate all the power that is fed to it. There will be losses, some large and some not so large depending on the design and the number of bands that the antenna is attempting to cover. The 80m / 40m Inverted L, mentioned above, is down by about 2dB on 80m when compared to a full size 80m inverted L. That's not too bad, but it does still mean a theoretical best case scenario of about a 40% loss of power! So if 100 watts of power arrives at the antenna (disregarding additional feeder losses) then only 63 watts will be radiated - actually less due to any feeder and other losses.

If these compromises are accepted then there are a number of different multi-band antennas that can be considered. Having a small plot I have had to consider many such designs, some are vertical antennas some are horizontal wires, some are commercial products and some can be 'home brewed'.

Home brewing a wire antenna is relatively straightforward since wire is easy to obtain and work with. A wire antenna is typically installed horizontally above the ground, although it may also be installed as an Inverted V or as a Sloper.

A wire antenna is easy to adjust for resonance and often reasonably straightforward to suspend in the air using existing structures, buildings, trees or simple wooden posts.

Home brewing a vertical antenna might present slightly more difficult mechanical and engineering challenges to produce a stable and, perhaps, visually acceptable device.

Standard Wire Dipole

In my own circumstances I could probably fit in a couple of dipoles up to about 15 metres (45 feet) in length. For a straight dipole, such a short length would preclude 160m, 80m and even 40m. So dipoles that could fit in a fairly small space would give two of the bands between 30m and 10m.

Loaded Dipole

Loading a dipole with a centre or end inductor on each arm would maintain its electrical length while reducing the antenna's physical length. This would allow the antenna to be resonant on the required band and enable the longer wavelength bands to be used even though efficiency will be less than a full size, un loaded, dipole.

A loaded dipole will be relatively easy to construct, the most time consuming part being the winding of the inductor coils and their subsequent adjustment to obtain the desired physical length at the correct resonance. An antenna analyzer is a very useful piece of test equipment for speeding up these adjustments.

Trapped Dipole

The use of traps can effectively split the antenna into two or more resonant sections. Using one trap on each arm of a dipole will transform a single band dipole into a dual band dipole. Using two traps on each arm will enable the dipole to be resonant on three bands. A four band trapped dipole would use three traps etc. Traps also shorten the overall physical length of the dipole which might be seen as an advantage, however traps tend to be lossy and short antennas obviously do not radiate as efficiently as their full size counterparts. Once again the compromise for covering more bands, and in less space is effective radiated power loss.

Traps can be quite tricky to home brew, though it is entirely possible. As an alternative traps can be purchased pre-made from some amateur radio suppliers such as Spectrum Communications. The other time consuming part of d.i.y. construction a trapped dipole will be adjusting the antenna wires so that the aerial is at resonance on each band. Again an antenna analyzer is a very useful piece of test equipment for speeding up these adjustments.

Fan or Parallel Dipole

An alternative to using traps is to use the fan dipole (parallel dipole) method. This essentially connects two or more full size dipoles together at the centre feeder point. For example, whereas a single band dipole would have one pair of 'arms' a four band fan dipole will have four pairs of 'arms' arranged in a fan like pattern. The fan dipole will be very straightforward to physically construct although it will be quite tricky to get each dipole to the correct resonance for each band since each arm will interact with its close neighbour. Again an antenna analyzer is a very useful piece of test equipment for speeding up these adjustments.

The Fan / Parallel dipole should be a very efficient and effective radiator since all the dipole elements are full size, however its bandwidth on each band might be be narrower than a trapped dipole, though it should be less lossy.

Most designs of Fan / Parallel Dipole (even commercial ones) seem to opt for coaxial feeder. Personally I don't think that this is a good idea. I would use twin feeder to feed this type of design (probably 72 ohm twin or similar) for three reasons.

1. Twin feeder is far and away less lossy than coax, so when an antenna has reduced bandwidth and one is forced to operate with a higher vswr than might be considered ideal, the subsequent feeder losses in coax will be very high indeed compared to to losses in twin feeder which will be much lower.
2. A dipole is a balanced antenna, and coaxial cable is an un-balanced feeder - not a good match...
3. Using un balanced coax with a balanced antenna would customarily demand the use of a balun at the centre of the dipole which is another point that could induce power loss.

For all those three reasons twin feeder seems to be the better, more efficient option.

Combination of Trap, Inductive Loading and Fan arrangement

There is no reason why a combination of a techniques might not be employed to produce a multi band dipole. Just as one example, a fan dipole with two pairs of arms could be made to cover four bands by using a pair of 7.1MHz traps in one pair of arms to create a 80m / 40m dipole and load the end of the dipole with an inductor to shorten its physical length. A second trapped dipole could be added to cover 20m and 10m using a 28MHz thereby making a fan dipole with two pairs of 'arms'.

Loop / Delta Loop

A loop antenna is remarkably easy to make and install and in my experience very easy to match using a good ATU. A relatively small loop made up of an 17 or 18 meter length of thin wire is light weight and should be visually inconspicuous and will work from the 30 metre to the 10 or even 6 metre band. A neat multi band solution that could be put up and taken down, as required, reasonably quickly.

Commercially Manufactured Options: Just a few designs that may be attractive for use on a small plot.

Wire Dipoles:

Interesting parallel dipole with end loading:

Alpha Delta Model DX-EE Parallel Dipole (40-20-15-10) - A Fan Dipole only 12 metres long. Reasonable design, though fed with coax. (I'd build one and use twin feeder.)

Similar design from Alpha Delta, but too big for my plot:
Alpha Delta Model DX-CC Parallel Dipole (80-40-20-15-10) - Fan Dipole design, 25 metres long.

Some interesting trap dipole designs:

Diamond W8010 - Trapped Fan Dipole for 80m, 40m, 20m, 15m and 10m only 19.2 metres long.

Comet CWA-1000 - Trapped Fan Dipole for 80m, 40m, 20m, 15m and 10m Similar to Diamond W8010 19.8 m long.

[Thinking out-loud: Could take the 80m segments and 7MHz traps off the ends of both the W8010 or CWA-1000 to produce a shorter antenna covering 40m, 20m, 15m and 10m that would only be about 13.6 metres long?]

KZJ - Restricted Space Inductive Dipole (trapped?) Straight - For 80m, 40m, 20m and 10m only 16.5 metres long.
KZJ - Restricted Space Inductive Dipole (trapped?) Straight - For 160m 80m, 40m, 20m and 10m 22.3 metres long.

Top quality designs:
Spectrum Communications 80m + 40m Dipole fed with twin feeder and will cover other bands up to 10 meters.
Spectrum Communications 40m + 20m Dipole fed with twin feeder and will cover other bands up to 10 meters.
Spectrum Communications 80m + 40m Inverted L. Will cover other bands up to 10 meters.

Verticals:

Usually very short when compared to the wavelength being used so power loss may well be very high. Might be useful in very restricted spaces where nothing else really will fit in. A vertical antenna can provide better low angle radiation which can provide better long distance DX.

G Whip G Pro wide band whip antenna - perfect resonance on the 40m band and 80m to 10m with 'A.T.U.'
Sandpiper V10 and derivatives. Depending on bands covered, between 4.2 m and 6 metres tall.
Sandpiper MV10 and derivatives. Depending on bands covered, between 2.5 m and 4.2 metres tall.
Butternut HF9-V covers 80m, 40m, 30m, 20m, 17m, 15m, 12m and 10m. - 7.9 metres tall
Diamond CP6 covers 80m, 40m, 20m, 15m, 10m and 6m. - 4.6 metres tall.
Diamond CP5-H covers 40m, 20m, 15m, 10m and 6m. - a mere 3.6 metres tall.
Comet / Maldol HVU-8 80m, 40m, 20m, 15m, 10m, 6m, 2m, 70cms. - tiny at only 2.6 metres tall.
GAP Eagle DX 40m, 20m, 17m, 15m, 12m, 10m. - 6.4 metres tall.

Antennas 1 | Antennas 2 | Antennas 3 | Antennas 5 | Antennas 6 | Antennas 7

G-Whip Antenna Products
Geoff G4ICD offers a multitude of high quality solutions for portable, mobile and permenant base installations

M0MTJ | Operating Conditions | Antennas / Aerials | /P Portable Operating | Accessories | Projects & Kits | Useful Information

Contact MØMTJ | Contact M6ORS | Links to Amateur Radio Sites | RSGB | QSL | The Amateur Radio Mini Site Map

WSPR Weak Signal Propagation Reporter

News, Developments, Events, Photographs and other 'Bits 'n' Bobs'

MDS975 Home

Feedback

Mike Smith - MDS975.co.uk © 2003 - 2016

M0MTJ

Amateur Radio; Ham Radio; Radio; Transceivers; HF; VHF; UHF; Data Modes; Morse Code; RTTY; PSK31; SSTV; FSTV; Amtor; Sitor Antennas; Aerials; Cable; Coaxial Cable; Twin Lead; Masts; Poles; Propagation; Computer; PC; USB Computer Interface; Microphone Loudspeaker; Filters; Noise Reduction; DSP; Digital Signal Processing; Morse Key; SWR ; Inverted L; Inverted V; Dipole; Doublet.

Amateur Radio MØMTJ

MDS975.co.uk HOME PAGE

My Home Page

Amateur Radio Operating Conditions
Antennas
Accessories
Projects & Kits
Data Modes
Information
Portable
QSL
RSGB Ltd
Links
QRM
Bits 'n' Bobs
Contact

WSPR
Weak Signal Propagation Reporter

PORTABLE

Site Map

MDS975 Home

Feedback

PLT QRM

Site Search
Find
powered by FreeFind

M0MTJ | Operating Conditions | Antennas / Aerials | /P Portable Operating | Accessories | Projects & Kits | Useful Information
Contact MØMTJ | Contact M6ORS | Links to Amateur Radio Sites | RSGB | QSL | The Amateur Radio Mini Site Map
News, Developments, Events, Photographs and other 'Bits 'n' Bobs' | WSPR Weak Signal Propagation Reporter

AERIALS (ANTENNAS) 5

Antennas 1 | **Antennas 2** | **Antennas 3** | **Antennas 4** | **Antennas 6** | **Antennas 7**

Index To Other Antenna Pages:
Antennas 1 : Aerials used by M0MTJ
Antennas 2 : Including ideas for compact antennas for Top Band /160 metres
Antennas 3 : Felix Scerri VK4FUQ discusses Loop Antennas, baluns, masts & other antenna related topics
Antennas 4 : Many antenna ideas from various sources particularly for multi-band operation & also gives information about
antenna trimming, knots for wire antennas and useful antenna rigging accessory ideas.
Antennas 5 : Half Wave End Fed antennas for 144 MHz VHF / 430 MHz UHF and 50 MHz 6 Metre band & J-Pole Aerials
Antennas 6 : Simple and effective H.F. Antenna ideas - Ground Plane and All Band Doublet
Antennas 7 : Omni-Directional - Circularly (Mixed) Polarized Antenna for VHF / 2 Meters.

The VK2ZOI "Flowerpot Antenna" - A physically end fed Half Wave "Coaxial Dipole" for 2 metres and 70 centimetres

For 2m and 70cm FM I use a mounted on a lightweight aluminium telescopic pole on the apex of the hose. The base of the antenna (the bottom of its radiating element) is approximately 11 metres above ground level. This antenna is based on the Controlled Feeder Radiation principle (CFR) and is described by VK2ZOI on his website. Also known as a "Coaxial Dipole". My version is described below.

Also seen in the photograph are the ropes that support the H.F. wire aerials.

G Whip Antenna Products

Get on the air with TOP QUALITY BRITISH G-WHIP ANTENNAS

Home brew dual band vertical antenna for 2 metres and 70 cms
(Coaxial Dipole / Controlled Feeder Radiation Antenna / 'Flowerpot Antenna')

VK2ZOI has produced some extremely interesting and potentially very useful dipole antenna designs. The designs could form the basis for a great home-brew antenna project since it is physically end fed and can also be made into a dual band aerial for 2 metres and 70 centimetres, so forming the basis of a viable alternative to buying an expensive commercially manufactured 'white stick' antenna.

The final dual band version works very well and can form the basis of a viable alternative to commercially made 'white stick' antennas, because there's nothing better than using your own home-brew antenna!

Physically, the feeder cable enters the antenna at the bottom end, so it looks like an end fed aerial. VK3TWO / VK6TWO describes it as a "Coaxial Dipole". 'Electrically' it is a simple dipole. The RF is travelling 'inside' the bottom 'element' and doesn't 'feed' the antenna until where the coax is cut - in the centre of the antenna, as shown in the diagram below. Where the outer braid is cut (electrically the centre feed point), the RF then radiates like a simple dipole, via the top radiator (coax core), and via the outside of the coax - the bottom half of the dipole. The top radiator is thinner than the lower radiator (hence why the lower radiator is slightly shorter than the upper radiator).

The coiling of the coax is simply forming an RF choke (high impedance point), to stop the RF continuing down the outside of the braid, thus electrically it 'appears' to be the end of the radiating element.



http://vk2zoi.com/articles/half-wave-flower-pot/

I purchased a 3 metre length of 25mm diameter conduit from B&Q, our local DIY centre and ordered some 25mm end caps and heatshrink from ebay. I already had some good quality RG58 for the feeder and main 2 metre radiating element and some aluminium foil for the 70cm sleeve dipole.

First of all I cut the RG58 cable to form the 2m radiating section and choke coil. Because the UK's 2m allocation of 144 to 146 MHz is narrower than the 144 to 148 MHz available in Australia, I varied slightly from the design shown. The centre of the UK's 2m band is about 1% longer in wavelength, so I decided to make both the top and bottom measurements 1% longer.

I therefore stripped 460 mm of the outer sheath and braid from the cable to form the top 1/4 wave element of the dipole. I then measured down 450 mm and marked the point where the lower 1/4 wave element would finish and the choke coil would start.

Next I attached a thin nylon cord to the top of the top radiator, the coax inner.

I then cut the 3 meter length of 25 mm conduit down to about 2.3 metres and drilled a hole where the coil would start, wound 9 turns of RG58 cable from that hole and marked the position of the lower hole. I then removed the coaxial cable and drilled the second, lower, hole.

I then pushed the radiating section of RG58 into the top hole and fed it up towards the top of the tube, stopping when the marker tape reached the hole. I then wound the coil and pushed the remainder of the RG58 through to lower hole and fitted a PL259 plug on the end.

I pulled the top of the radiator wire tight using the nylon cord and pushed the end cap on. The antenna was then ready to be tested on the 2 metre band. I found that the resonant frequency was rather too high, just above 146 MHz, so I pushed an additional 10 mm of coaxial cable into the upper section of the tube - therefore making the lower 1/4 wave section of the dipole 460 mm long - the same as the top section. I tightened up the choke coil winding again and performed another test.

This time the resonant point was just over 145.000 MHz - near enough the centre if the UK's 2 metre band. That was perfect, so the 70 cm sleeve element was then added - this is a 235 mm long tube of kitchen foil positioned exactly at the centre (feed) point of the 2 meter dipole within the tube.

The SWR was tested and found to be acceptable across both the 2m and 70cm bands.

I then fitted the end cap, applied the heatshrink to the coil and to the aluminium foil sleeve. I noticed that when the antenna tube was moved around the cable inside rattled around making a noise that may be rather annoying to anyone near its final location.

To help hold prevent the cable from rattling I pushed up 4 or 5 small pieces of foam material up the tube from the bottom to rest at various positions along its length. With these pieces in place the cable was certainly silenced, however it may have had a deleterious effect on the SWR.

With the antenna now in its finished physical state I naturally checked the SWR again to compare against the performance in its semi-complete state. I was pleased to find that the SWR was still fine across the 2m band, in fact the SWR was a little lower. However the SWR at the edges of the 70cm band was considerably higher - 1.8 at 440 MHz and about 2.2 at 430 MHz.

I conjectured that the heatshrink covering the foil sleeve dipole may have caused the change in response so I removed it, but the SWR was little different and the bandwidth on 70cm was now disappointingly narrower than expected and hoped for.

Although I cannot say for certain, because they cannot now be easily removed, but it may be possible that the pieces of foam may be the culprits for the difference.

While the bandwidth could not be improved, I decided to move the centre point of resonance down a little by increasing the length of the sleeve element from 235 mm to 245 mm. With that adjustment the SWR was now approximately 1.6 at 430 MHz but rising to 2.0 at 440 MHz. (Unfortunately I forgot to note the exact figures down in all cases).

When the antenna was connected to the 20 meter length of Westflex-103 back to the shack, the SWR reading were as follows:

2 Metres - SWR		70cms - SWR	
144.00	1.3	430.00	1.2
144.50	1.2	431.00	1.4
145.00	1.2	432.00	1.4
145.50	1.2	433.40	1.0
146.00	1.2	434.00	1.3
		435.00	1.8
		436.00	1.6
		437.00	1.0
		438.00	1.5
		439.00	2.0
		440.00	2.1

The SWR readings in the shack for 2 meters are lower than at the feed point, which is presumably due the losses in the feeder. The SWR readings for 70 cms look rather erratic, with a strange peak at 435 MHz, while the 430 MHz figure is lower than at the feed point of the antenna, and the 439 and 440 MHz figures are disappointingly higher than hoped for. The peculiar readings are likely due to feeder effects.

However the SWR at 433.4, in the FM simplex portion of the band, is very low.

The completed antenna was mounted to the aluminium mast by utilising brackets of the Watson W50 antenna. The brackets had to be reversed so that the narrower diameter of the 25mm tube could be held in place by the V Bolt, while the circular section that previously fitted over the base of the W50 now slid over the mast, which was coincidentally a similar diameter.

I made a small addition to the design in the form of a second small 150mm length of of the 25 mm conduit glued to a coupler section. This is slid into place at the bottom of the antenna to provide additional weather protection to the joint between the W-103 feeder and the RG58 of the antenna - which itself is covered in self amalgamating tape.

Shown in the table below are some signal comparisons with the Watson W-50 antenna; both were mounted on the same mast in the same position and at a height of approximately 7 metres above ground level. Becuase the S-Meter of the transceiver is not calibrated in absolute values, the figres are for relative comparison only - also bear in mind that a typical S Point represents 6dB - therefore the accuracy of these readings will be coarse and might be considered to be +/- 3dB - that's a rather wide variation.

Despite the relative crudeness of these comparisons, the results do seem to indiacte that the VK2ZOI antenna is marginally or slightly better than the W-50 on 2 metres and marginally worse on 70cms. I am quite pleased with this result and beleive that this antenna really could replace the need to buy an expensive commercially manufactured antenna.

My only concern with this type of antenna is that there is no path to ground from the top element, as there would be with a folded dipole or a J-Pole type antenna. This may be a cause for concern as far as static build up is concerned.

Signal comparisons		
	Watson W-50	**"Flowerpot Antenna"**
2 Metres		
Station A	S7	S9
Station B	S5	S6
Station C	S4	S4
Station D	S9	S9
Station E	S6	S6
Station F	S0	S1
Station G	S2	S2
Station H	S2	S3
Station I	S6	S6
70 cms		
Station J	S0	S1
Station K	S5	S5
Station L	S5	S4
Station M	S0	S0
Station N	S9	S9
Station O	S6	S6
Station P	S7	S6

Please see the photographs below for a visual explanation of this project. Mike, MØMTJ. 05/03/2013



First stage of construction of the 2m / 70cm dual band antenna
Cutting the 25mm diameter conduit to the desired length and drilling
the two holes allowing the coil to be wound. MØMTJ


Heatshrink
Red marker tape
MØMTJ

Heatshrink applied to the centre of the dipole section and red insulation tape added to mark the bottom of the dipole where the coil starts. MØMTJ


Inner of coaxial cable
Thin nylon cord
Notch
Blob of glue
Heatshrink
MØMTJ

Thin cord attached to top of the inner conductor of the coaxial cable, which forms the top 1/4 wave section of the dipole with a piece of heatshrink and a blob of glue. MØMTJ


Edge of red marker tape just visible through hole
MØMTJ

The line isolator choke is formed by winding 9 turns of the RG58 coaxial cable around the 25mm diameter conduit tubing. MØMTJ



The thin cord that holds the 1/4 wave radiator in place is located in the notch and will be trapped in place when the end cap is fitted. MØMTJ



After testing, the coil was covered in heatshrink to prevent water entering the plastic tube.

MØMTJ - www.mds975.co.uk

The foil sleeve dipole for 70cms is covered in heatshrink.



Oops. Lesson learned. When applying heat to the heatshrink I held the tube above the ground and the plastic of the tube started to go soft and bend out of shape. The buckle in the tube can be seen in this photograph.
Lesson: When applying heat, keep the tube flat on the ground or work bench and roll the tube along as the heatshrink shrinks into place ensuring that the tube does not distort or bend.



25 mm end cap sealed in place by heatshrink.


MØMTJ - www.mds975.co.uk
Completed antenna

The completed antenna in place, mounted at the top of my aluminium push-up mast. The fixings used are the brackets from the Watson W-50 antenna which have been reversed so that the smaller diameter PVC tube is held in place by the V Bolts.


MØMTJ - www.mds975.co.uk
Bracket re-used from Watson antenna
N.B. position reversed to fit conduit tubing
Short additional length of conduit tube pushed on to main antenna tube with joiner to protect PL259 coaxial connectors
Aluminium mast
Westflex 103 coax

Photograph detailing the the fixings. The brackets are brackets are from the Watson W-50 antenna which have been reversed so that the smaller diameter PVC tube is held in place by the V Bolts.

For further detailed information and reading, please visit the excellent website of John Bishop VK2ZOI here: http://vk2zoi.com/articles/half-wave-flower-pot/

6 Metre Half Wave Coaxial Dipole - An end fed CFR Dipole antenna supported by a 3 metre long fibreglass fishing pole for 50 MHz

In 2014 I decided to remove the 4 Metre J-Pole antenna from my push-up mast due to the fact that the band is relatively quiet and that I only have the 5 watt Wouxon handheld transceiver for 70 MHz.

I decided that having a good, full size antenna, for the 6 Metre band would be more useful and potentially more rewarding since it can be used with a 100watt HF radio that covers 50 MHz.

The choice of antenna was an easy one. With the great success of the "flowerpot antenna", I decided to build a version for 6 Metres.

Similar designs of Coaxial Dipole antennas had also been featured in recent editions of the RSGB publication RadCom during 2012 and 2013. The antennas in RadCom are described as Controlled Feeder Radiation (C.F.R.) Dipole antennas - the tuned choke at the feed-point controlling, or choking off, the common mode current that would otherwise flow down the outside of the coaxial feeder cable causing E.M.C. issues on transmit, high S.W.R. reduced efficiency and noise on receive. See references below

The advantage of this design is that it can be physically end fed, so there is no feeder cable to route away from the centre of the dipole. Electrically, however, the feed point is at the centre of this dipole aerial, as explained earlier.

Rather than fit the antenna inside a PVC pipe, as with the previous dual band 2m / 70cm antenna described above, I decided to use a lighter weight and less conspicuous 3 metre long fibreglass fishing pole as the support. The completed radiating element simply being taped to the fishing pole.

I cut a length of MIL spec RG58 cable, about 4.5 metres long, to form the bottom half of the radiating section and the choke coil, leaving enough to form a short length (about 30 cm) of cable below the choke coil on to which is soldered a PL259 plug.

The choke consists of 15 turns of the RG58 coaxial cable wound on a 50mm diameter plastic former cut from the empty tube of a cartridge gun that previously contained silicone sealant - allowing a 30cm tail on to which the PL259 plug is fixed on one side and and about 1.31 metre length on the other side that will form part of the radiating element.

The half wave radiator therefore consists of a quarter wave bottom section of the RG58 cable and a quarter wave top section consisting of a length of multi-strand (single conductor) P.V.C. covered antenna wire.

A quarter wavelength at the mid point of the 6 Metre band is: 300 ÷ 51 MHz = 5.88 metres ÷ 4 = 1.47 metres

Due to velocity factor the actual length of the quarter wave sections will be shorter. With the materials that I used, I found that a factor of about 87% was about right, the 1/4 wave length being 1.29 metres.

The top tip of the bottom 1/4 wave section of the coaxial cable is stripped of about 2 cm of outer sheath and braid leaving the length of braided section, measured from where it exits the coil, 129 cm long. The inner conductor is then stripped of 1cm of insulation. This is effectively the centre point of the dipole. To this point is soldered the 129 cm length of the P.V.C. covered aerial wire to form the top half of the antenna. In practice, use a slightly longer length of wire, and then fold over the excess to for the 129 cm length - this can then be used to adjust for lowest SWR at 51 MHz.

The length of the radiating section was therefore about 260 centimetres, plus about 13 centimeters for the coil former giving a total length of 273 cm. This allows about 27 cm of the bottom section of a 3 metre fishing pole to be used to fix to a supporting pole or mount - e.g. to the top of an aluminium mast.

Drill four small holes in the choke former so that when the fishing pole is placed through the centre of the former it can be fixed to the pole using two cable ties.

The radiating section (coax and PVC covered wire) is fixed to the top section of the fishing pole with good quality insulating tape.

The aerial can now be temporarily fixed to the mounting pole using suitable brackets - taking care not to crush the delicate fibreglass! Connect the PL259 plug to the antenna feeder cable using an SO239 back-to-back coupler and test the SWR with an antenna analyzer or SWR bridge. The lowest SWR should be centred on 51MHz and be low - less than 1.5. My reading was 1.2.

If the point of lowest SWR is significantly away from 51 MHz and/or the SWR at the band edges is too high (i.e. over 2) then length of the radiator will need to be adjusted. If the point is too low in frequency, the antenna is too long and will need to be shortened. If the point is too high in frequency, the antenna is too short and will need to be lengthened.

Adjustment can be achieved by pulling the coax through the coil to make it longer, or pushing the coaxial cable back into the coil to make it shorter. Also ensure that the coil winding are adjusted to that they remain tight and neat. The top PVC covered wire section will also need to be lengthened or shortened accordingly by adjusting the folded over section.

Note that in practice, to obtain the very lowest SWR, the top PVC covered wire section may need to be slightly longer by perhaps 1 or 2 centimetres. This is probably due to the fact that the velocity factor of the PVC covered antenna wire is a little greater than the coaxial cable.

Once the antenna is adjusted correctly, ensure that the wires are securely taped to the fishing pole. Connect the permanent antenna feeder to the aerial using the SO239 coupler and weatherproof the joint thoroughly using self amalgamating tape. Use the very best quality coaxial cable possible to ensure lowest loss. I use Westflex 103, but consider MIL Spec RG8 or RG213 as the minimum standard.



50 MHz Coaxial Dipole / Controlled Feeder Radiation Antenna / 'Flowerpot Antenna'
A physically end fed fed half wave dipole antenna for 6 Metres



Choke Coil - 15 turns of the RG58 coaxial cable on a 50mm diameter former

VHF Band II Broadcast Band antenna for 88 to 108MHz - Physically end fed, Coaxial Dipole / Controlled Feeder Radiation Antenna (CFR Dipole) for VHF broadcasts

I used a 2 metre long length of 25mm white plastic pipe, strengthened with with a 2 metre length of 21.5mm overflow pipe pushed up the inside.

The radiating element is made from good quality 75 Ohm coaxial cable. Since VHF/FM broadcast tuners are designed to be fed with 75 Ohm coaxial cable, use high quality, low loss double shielded satellite grade coaxial cable for the feed between the aerial and the radio tuner. Use satellite F type connectors and joiners for lowest loss.

The top half of the radiating section is 670mm of the centre conductor (or a length of multi-strand PVC covered wire). The bottom half of the dipole is 650mm of the complete coaxial cable - choked off at the bottom by the coil section. The top part is held in place by a a short length of thin nylon cord, trapped in place by the top PVC cap. The cap itself is sealed on the outside by some self amalgamating tape.

The choke coil is 22 turns of the 75 Ohm coax wound around the 25mm pipe. Tightly spacing the windings of the coil will minimize the bandwidth covered but provide the lowest SWR at the centre point. A looser winding of the coil will widen the bandwidth covered, but lowest SWR achived will be a little higher.

Once the tuning of the radiating elements, coil winding and band coverage has been checked with an Antenna Analyzer, the coil section should be covered with heat shrink, taking great care not to overheat and deform the plastic pipe.

The actual final dimensions (as shown below) may well need some adjustment in length due to differences in cable and type of pipe used. However, with the dimensions shown, I achieved a minimum SWR of 1.3 at 97.4 MHz. The band edges at 88MHz and 108MHz were at an SWR of around 3.8 to 4.0 - which is probably OK for broadcast band reception. The frequency of lowest SWR can can be changed, if desired, by changing the lengths of the radiating sections - slightly longer for a lower frequency and slightly shorter for a higher frequency.



Coaxial Dipole for the 88 to 108 MHz Band II Broadcast Band
An effective, cheap and simple vertical antenna that is fed at its base

RSGB RadCom Articles:

The Controlled Feeder Radiation Dipole. Peter Dodd. RadCom, September 2012, page 22.

More On The CFR Dipole and Coax Chokes. Peter Dodd. RadCom, October 2012, page 54.

VHF CFR Dipoles and More on Common Modes Chokes. Peter Dodd. RadCom, January 2013, page 24.

The HAK Chokes Coaxial Dipole. Encouraging results from 2m to 20m. Peter Grant. RadCom, April 2013, page 22.

Join the RSGB to receive your monthly RadCom magazine: http://rsgb.org/main/publications-archives/radcom/

VK3TWO / VK6TWO Comments:

Many years ago when I was working for a Service Centre, by accident we broke a commercial white stick antenna whilst using it for a task it wasn't intended for. I found that inside the fairly expensive commercial antenna the basis for the design was very similar to the coaxial dipole (as I call them).

Our local repeater club calls them "pogo sticks", which I can only assume is due to the coax coil resembling the spring of a pogo stick. This design had RG213 being fed inside an aluminium tube (the bottom radiator), and the outer braid was then terminated to this. The inner of the coax, then terminated to an identical aluminium tube which was of course the top radiator. Where this design largely differs, is that there was also a 1/4 wave stub of coax running parrallel with the bottom radiator (note that this was for single band operation, not dual band). The whole lot then slid inside the typical white tapered fibreglass housing. I didn't cut open the bottom mounting section to see how it was choking the RF, but I assume it had a handful of ferrites inside the metal base (an alternative way of making the RF choke).

The repeater group has built probably hundreds of these and sells them for $40 at local hamfests. We had a 'Jig' made so that all of the measurements were 'pre-marked' etc, and allowed us to mass manufacture them. Last year, we had planned the typical 'working bee' to make about 30 of them, but this time we had a very expensive Anritsu Sitemaster at our disposal. We discovered that the whilst the design we'd used for decades had a good SWR, it actually was far from optimal. With a heap of 'trial and error' (and with excellent visibility of what was really going on via the Anritsu - not just SWR) we were able to fine tune the design.

From memory, we actually needed more turns of the coax than we had been using (10.5 turns from memory), and our cutting measurements altered slightly. As to be expected, the number of turns was largely dependent on the size of the conduit being used, even changing from 25mm to 30mm etc.

We took several screenshots of the final SWR plots etc. These showed that the bandwidth of this antenna as VERY wide from an SWR point of view. I'll see if I can dig some of them up for you if you'd like.

73, Heath, VK3TWO / VK6TWO
MEngSc, GDipCompSc, DipEE
www.spooktech.net

http://www.warg.org.au - The West Australian Repeater Group Inc (WARG) is the largest amateur radio club in Western Australia (VK6).

D.I.Y. J-Pole Antennas - A really simple, quick and very cheap 'home brew' project J-Pole Antennas

J-Pole antennas for 2 meters, 4 metres, 6 metres and 10 metres :

While experimenting with antennas in the garden in the summer of 2012 I thought that it would be good to have a hand-held radio in the shed to do some monitoring and make a few contacts. To improve upon the performance of the 'rubber duck' antenna I quickly made a J-Pole antenna for the 2 metre band.

It is made from a 47cm length of 450 ohm Wireman ladder line as the 1/4 wave matching section, plus a 97cm length of stranded wire as the 1/2 wave radiator. It is fed with 3 metres of Mil spec RG58 c/u coaxial cable that is soldered to the 1/4 wave matching section's impedance matching point at 3.5 cm from the bottom. The coax feeder is wound around some PVC tube to form a choke. The completed antenna is taped to a 2.2 metre long fibreglass fishing pole that I purchased from Poundland (for £1.00). It took about 20 minutes to make followed by some testing and adjustment with the antenna analyser. The fishing pole is lashed to the shed with some cable ties.

This simple antenna works pretty well, but being so low down signal strengths are not huge, but it's pleasing to get on the air with something so simple and cheap!



The Shed Antenna - a 2m J-Pole by M0MTJ
Note the simple choke balun at its base made by winding 8 turns
of the coaxial cable around a small off cut of white PVC water pipe.



The feed point of a J-Pole antenna made from Wireman 450 ohm ladder line.
For the 145 MHz antenna this feed point is 3.5 cm from the bottom of the ladder line section which is on the right hand side in this photograph. The coaxial cable used in this case was Mil spec RG58 c/u. But any good quality, low loss 50 ohm coaxial cable could be used. The wire radiator section is connected to the same conductor of the ladder line as the coaxial cable's centre conductor. For my antenna, fixed to a fibreglass fishing pole, the radiator wire was 97cm in length.



Photograph showing the point where the PVC covered wire that forms the half wave radiator section is soldered onto the top of the 450 ohm ladder line that forms the quarter wave matching section.

Inspired by DK7ZB. The J-Pole is a very effective antenna and being made of wire it is very light weight making it quite easy to fix in different positions. If you have problems installing a permanent antenna then making a wire antenna that can be easily supported on a lightweight push up telescopic fishing pole can make an ideal alternative.

The formulas to make a J-Pole antenna from 450 Ohm Wireman ladder line in this way are:

Length of 1/4 wave impedance matching section (450 ohm ladder line) Wavelength x 0.223
Length of 1/2 wave radiator (any reasonably strong PVC covered stranded wire) Wavelength x 0.471
The point at which the coax is connected to the 450 ohm ladder line will be about 5 to 10% of the length of the ladder line section up from the bottom.

The wavelength at mid point of the 2 metre band (145.00 MHz) is found by the quick calculation 300 ÷ 145 = 2.068 metres

So, to make a practical antenna:

The 1/4 wave section of 450 ladder line will be 2.07 x 0.223 = 0.47 metres long
The 1/2 wave wire radiator will be worked out as 2.07 x .471 = 0.975 metres long
The connecting point of the coax will be about 3.5 cm from the bottom of the 1/4 wave section. The optimal point may have to be found by some experimentation - as will the best length for the wire radiator.

The length of the wire radiator will be affected by surroundings. For example I fixed the wire to a fishing pole. The proximity of the fishing pole has the effect of electrically lengthening the wire; so using a 97.5cm length of wire fixed to a pole I found that it resonated (as expected) at a lower frequency, it therefore had to be shortened until the point of resonance (indicated by lowest SWR) was around 145.00 MHz. This should be done in the antenna's expected final position since the J-Pole is quite sensitive to its surroundings, so if these checks are done near the ground, once it is raised into its final position the SWR will have changed and the adjustments will have to be done again.

I found that 3.5 cm was good for the 2 metre band antenna, but for the 10 metre band version of the antenna a little more experimentation was required:

The VSWR reading may not be especially low, even though the point of resonance for the wire radiator may have been found. For the 10 metre band antenna at this this stage was about 1.7 indicating that the connection point of the coaxial cable to the 450 ladder line needs to be adjusted. The ladder line is used as an impedance transformer, transforming the very high impedance (hundreds of ohms) of the half wave wire radiator down to the 50 ohms required by the transceiver and the coaxial feeder cable. This connection point therefore affects the impedance of the antenna, the higher up the matching section it is the higher the impedance will be, and visa versa.

Once the length of the wire radiator has been set, the connection point can be moved up and down the ladder line until lowest SWR is achieved. A few centimetres of the PVC insulation has to be carefully scraped away from the copper conductor on each side of the ladder line using a craft knife. The inner conductor of the coaxial cable is quickly tack soldered on the side that is connected to the 1/2 wave wire radiator. The coaxial cable's braid is quickly tack soldered to the opposite side of the ladder line at this point, ensuring that both points are equal distance from the bottom. At this point temporary croc clips could be used, but I preferred a quick solder joint.

With radiator trimmed for resonance, the connection point of the coaxial cable can then be moved up or down the ladder line little by little; un-soldering and re-soldering the coax to the ladder line until a lowest possible SWR is achieved, indicating that the antenna is near the ideal 50 ohm impedance.

Once the ideal point is found the coaxial cable can be properly and permanently soldered to the ladder line.



6 Metre Band J Pole on the antenna analyser - it's getting close!

Each J-Pole took about 20 minutes to physically make out of the wire components. However the testing and adjusting took a bit more time. I used an antenna analyser which saved having to key the mike every time when using a basic VSWR bridge and causing unnecessary QRM, but even so, hoisting the fishing pole up and down numerous times took a little more time:

10 Meter J-Pole. For the 10 metre band J-Pole antenna this took perhaps another 20 or 30 minutes until I was satisfied with the adjustments. It may take a little longer if using an SWR meter.

6 Meter J-Pole. For the 6 metre band antenna the radiator wire had to be trimmed a little and the feed point adjusted to 6 cm, taking about 10 additional minutes to complete.

4 Metre J-Pole. For the 4 metre band, centred on 70.37 MHz

2 Meter J-Pole. For the 2 metre band antenna the wire radiator took a couple of attempts to get it to the correct length when attached to a fishing pole, but the feed point was spot on first time at 3.0 cm, again taking about 10 additional minutes to complete.

Here are some suggested dimensions for the 2 metre, 6 metre and 10 metre band versions, when supported by a fibreglass fishing pole:

Wire J-Pole Antennas	1/2 Wave Radiator	1/4 Wave Section	Feed Point
2 Metre Band Antenna	0.975 m	0.47 m	3.0 cm

4 Metre Band Antenna	**1.90 m**	**0.95 m**	**6.1 cm**
6 Metre Band Antenna	**2.815 m**	**1.33 m**	**6 cm**
10 Metre Band Antenna	**4.96 m**	**2.45 m**	**15 cm**

N.B. The 1/2 wave wire radiator section will be shorter than calculated when fixed to a fibreglass pole or other object.

To re-cap, the 1/2 wave section should be adjusted for resonance and the feed point position adjusted for minimum VSWR.

Sealing and waterproofing. Once the antenna is complete and has been checked and tested all the bare joints should be sealed against the weather with liquid electrical tape and self amalgamating tape. The coax should also be secured against the ladder line with a nylon cable tie as a strain relief to prevent the soldered feed point joints from breaking.

These J-Pole Antennas were inspired by DK7ZB - http://www.qsl.net/dk7zb/J_Pole/wiremanjpole.htm

---

Antennas 1 | Antennas 2 | Antennas 3 | Antennas 4 | Antennas 5 | Antennas 6 | Antennas 7



SOTA Beams
Lightweight 2 metre &
70cms Yagis, Dipole,
Accessories & Poles
www.sotabeams.co.uk

G Whip
Antenna
Products

G-Whip Antenna Products
Get on the air with
TOP QUALITY
BRITISH
G-WHIP
ANTENNAS
End Fed Zepps and
many more designs
and products

PLA-PLT Latest News
Keep up-to-date on this important issue

Radio Interference?:
PLT & PLA: Radio Interference
British Telecom, BT Home Plug
P C World, Powerline Adapters
YouView, Belkin Linksys
Netgear Devolo, BT Vision - BPL
Radio Interference
PLT Page 1

Antennas 1 | Antennas 2 | Antennas 3 | Antennas 4 | Antennas 5 | Antennas 6 | Antennas 7

Top of page ^

M0MTJ | Operating Conditions | Antennas / Aerials | /P Portable Operating | Accessories | Projects & Kits | Useful Information

Contact MØMTJ | Contact M6ORS | Links to Amateur Radio Sites | RSGB | QSL | The Amateur Radio Mini Site Map

WSPR Weak Signal Propagation Reporter

News, Developments, Events, Photographs and other 'Bits 'n' Bobs'

MDS975 Home

Feedback

MAIL

Mike Smith - MDS975.co.uk © 2003 - 2016

M0MTJ

Amateur Radio; Ham Radio; Radio; Transceivers; HF; VHF; UHF; Data Modes; Morse Code; RTTY; PSK31; SSTV; FSTV; Amtor; Sitor Antennas; Aerials; Cable; Coaxial Cable; Twin Lead; Masts; Poles; Propagation; Computer; PC; USB Computer Interface; Microphone Loudspeaker; Filters; Noise Reduction; DSP; Digital Signal Processing; Morse Key; SWR ; Inverted L; Inverted V; Dipole; Doublet.

WORLD DX RADIO GROUP
SUGAR DELTA®
MARTIN
Mexico
10SD156
SDIOTA
ISLANDS ON THE AIR
SUGAR DELTA ON AIR
SD
OFFICIAL WEB SITE
TESLA COIL

I N I C I O
ALGUNAS QSL´s INTERESANTES. (MY DXCC)
.:::LA AURORA BOREAL EN VIVO:::..
COMO SE COMPORTA LA MAGNETOSFERA..
..::- MAPA DXCC -::..
...:::CLUSTER DX.:::...
DIAGRAMAS DE ANTENAS
PREDICCION DEL CLIMA, TORMENTAS, LLUVIAS.
COMPARACIONES Y DIMENSIONES ESTELARES.
Propagación de las ondas de radio
REPARACION DEL TELESCOPIO HUBBLE EN 2010
My DXCC Flag & World Map.
BALUNES DE ACOPLAMIENTO.TEORIA, USO Y CONSTRUCCION.
FOTOGRAFIAS
CABLES COAXIALES
POLARIZACION HORIZONTAL, VERTICAL Y CIRCULAR.
MANUALES DE RADIOS , MICROFONOS Y ELECTRONICA.
CLIMA ESPACIAL, INDICES DE PROPAGACION.
SISMOS...TERREMOTOS EN MEXICO

DIAGRAMAS DE ANTENAS


Straler 215 cm Frequentie 27.205 Mhz
Nylon koord
Nylon koord
RG 58
RG 62
De 2 kabels in de PL 259 plug schroeven
PL 259

DIVISION 10 Mexico

Martín

Bienvenidos a mi blog...vivo actualmente en el estado de Guanajuato en el centro de México.. mis coordenadas geograficas son:
Longitud:-101.66473 W (-101° 39' 53'' W)
Latitud: 21.10992 N (21° 6' 36'' N)
QTH locator : DL91EC
Soy radioaficionado, oncemetrista y en un futuro no muy lejano espero obtener mi licencia opara operar otras bandas y soy tambien SWL (radioescucha de la onda corta) a traves de SDR.
Este blog esta dedicado a todos ustedes mis amigos que que a lo largo de los años han sido mis maestros en el arte del DX y la radioexperimentacion, gracias a todos ustedes estoy en este hobby que me ha dejado enormes satisfacciones...


Antena "Bigode de Gato" 80 - 40 - 20 mts
A = 80 mts
A
C = 20 mts
B= 40 mts
2mts cabo 75OHMs
Cabo coaxial de 52 OHMs
Legenda:-
A = 80mts - 19.10 de cada lado
B = 40mts - 15 mts comprimento
C = 20 mts - 5 mts comprimento
isolador de PVC - 10 cm
PY5 GG - Ribas


Antena Borboleta - 7 Elementos - VHF
69 cm
38 cm
D 5
C - Cada elem. 1.76 mt
71 cm
39 cm
D 4
C - 1.81 mt
74 cm
40 cm
D 3
C - 1.87 mt
76 cm
41 cm
D 2
C - 1.92 mt
78 cm
43 cm
D 1
C - 1.98 mt
86 cm
47 cm
REF
C - 2.18 mt
1
2
3
82 cm
45 cm
IRRAD
C= 2.08 mt
Legenda:-
1 - Gamma match - dist. 3.5cm
2 - Comprim = 35.5 cm
3 - Corpo cap. interno = 32cm, fixo elemento
35.5 cm
Conector
32 cm
3.5 cm
Elemento
Placa deslizante
37 cm
31 cm
43.5 cm
54 cm
62 cm
68.5 cm
Frente
R
Ir
D1
D2
D3
D4
D5
Góndola = 3.00 mts
PY5 GG _ Ribas

BIENVENIDOS...

CONDICIONES DE DX

10SD156 MARTIN SPACE WEATHER


Conditions for 0120z
Solar Flux 75
Sunspots 22
A-index 7
K-index 1
GEOMAG: VERY QUIET
A7.0
80M-40M CLOSED POOR
30M-20M FAIR POOR
17M-15M POOR CLOSED
12M-10M CLOSED CLOSED
Aurora 5.2 FALLING
0120z
12GW
K-index [Boulder 3hr]
10
8
6
4
2
0
03
06
09
12
15
18
21
00
Solar Flux & Sunspots
90
72
54
36
18
0
16
18
20
22
24
26
28
orcadxcc.org

*






2017/10/28 13:00


Antena dipolo "Múltipla"
10-11-15-20-40 e 80 mts
C = 22.20 mts
1.10 mt
10.00 mt
10.00 mt
1.10 mt
Bobina
Bobina
2mts cabo 75OHMs
Cabo coaxial de 52 OHMs

Nota:- Uso obrigatório de acoplador

2 bobinas de cano de PVC 3/4' com 12 cm cada, enrrolado com 200 espiras de fio nº 14 esmaltado AWG

Isolador porcelana ou outro isolante

PY5 GG - Ribas


5,70 mt
Refletor
B >C = 2,20 m
5,37 mt
C
A >B =1,8 m
5,06 mt
Irradiante
B
Gôndola - 4,00 mt
Diretor
A

A - B - C > 3 parafusos

PY5GG/PX5G 0654 - Ribas


aia.lmsal.com


Visible Sunspot Regions
2680
SolarHam



Flare probabilities for NOAA Active Regions at 30-Sep-2017 00:46:38.800



WX Mexico y Hemisferio Norte


1531mm
2000 mm
1531mm
DIRETOR
1300 mm
1684 mm
2000 mm
1684mm
IRRADIADOR
525
1700 mm
1850mm
2000 mm
1850mm
REFLETOR


0.10
2.25
1.279
1.985
0.10
5.624
5.24
5.016
4.944
tX->
Gamma
ANTENA BC4YRN
Frecuencia: 27.305 Mhz.
Visitame: http://www.qsl.net/xe3rn
email : xe3rn@hotmail.com

CLIMA EN MEXICO


CGSMN GOES 13 IR4 (0:37 Z) 29/Oct/2017
CONAGUA

CLIMA EN HEMISFERIO NORTE


GOES-COMPOSITE VISIBLE - OCT 28 17 15 45 UTC

IONIZACIÓN ATMOSFERICA




Ionosphere Layers
DAY
NIGHT
500 km
480 km
460 km
440 km
420 km
400 km
380 km
360 km
340 km
320 km
300 km
280 km
260 km
240 km
220 km
200 km
180 km
160 km
140 km
120 km
100 km
80 km
60 km
40 km
20 km
0
HST 560 km
Hubble Space
Telescope
Starfish Prime
H-bomb 1962
F2
F layers usually
good for reflecting
HF for long DX
F
ISS 350 km
Int Space Station
F1
Aurora above 80 km
Red = Nitrogen
Green = Oxygen
E Normally reflects up to
10 MHz for short DX
E
E
D
D layer
absorbs HF
Ozone layer 13-20 km

Steve Holland VA7SSE

INDICES DE PROPAGACION

28/10/2017 > SSN: 023 | Area: 60 | SF: 76 | A:5-K:2 | Xray: A8

X-Ray Flux


1/4 LAMBDA
1/4 LAMBDA
STAGNARE
STAGNARE
CAVO DISCESA

LA FORMULA PER IL CALCOLO DEI BRACCI 144/MHZ PER I 27,600 1/4= 2.60 POI QUANDO MONTATO SI ACCORCERA' PER PORTARLO IN RISONANZA

SE IL CAVO E' 52 OM LA STESSA IMPEDENZA SARA' NEL PUNTO DI CONNESSIONE

LE MISURE SONO PER UNA ALTEZZA DI 1/2 ONDA CIOE' ATTORNO AI 5,30 METRI, IO POSIZIONANDOLO A 2,75 (1/4) HO DOVUTO ACCORCIARE I BRACCI DI CIRCA 15 CM PER LATO. IL TUTTO E' DOVUTO ALLA RESISTENZA DI IRRADIAZZIONE DOVUTA DALLA RIFLESSONI DEL SUOLO.I VANTAGGI DI QUESTO DIPPOLO SONO UNA IMPEDEZA IDENTICA AL CAVO DI ALIMENTAZZIONE E DALLE PROVE FATTE UN RENDIMENTO MOLTO SUPERIORE AL SEMPLICE DIPOLO(SE NOTATE IN MEZZO NON E' DIVISO QUINDI LA LUNGHEZZA E' UN ONDA INTERA) IO HO RALIZZATO IL TUTTO IN CAVO 50/20 OTTIMO SOTTO TUTTI I PUNTI DI VISTA.PER SOSTEGNO UN CAVO DI NAILON LO STESSO DEI TIRANTI DELLE MIE ANTENNE.73 BUONI DX.


C
Refletor
B >C = 1,66 mts
2,75 mt
1,95 mt
B
Irradiante
A > B = 1,27 mts
2,61 mt
B 1
1,86 mt
B1>C=1,46 mt
A
Diretor
1,75 mt
Coaxial
2,47 mt



Aurora Boreal y Austral


Aurora Forecast
OVATION-Prime Model
Forecast For: 2017-10-29 01:25 UT
Hemispheric Power: 12.60 GW
(Typical Range 5 to 150 GW)
Probability of Visible Aurora
10%
50%
90%
Model Run at: 2017-10-29 00:56 UT
Observation Time: 2017-10-29 00:55 UT


Aurora Forecast
OVATION-Prime Model
Forecast For: 2017-10-29 01:25 UT
Hemispheric Power: 12.18 GW
(Typical Range 5 to 150 GW)
Probability of Visible Aurora
10%
50%
90%
Model Run at: 2017-10-29 00:56 UT
Observation Time: 2017-10-29 00:55 UT

RADIOAFICIÓN:
EL HOBBY CIENTÍFICO MÁS GRANDE.

Gracias por tu Visita

+ −

REVOLVERMAPS

/TRADUCTOR/ /TRANSLATE/

Select Language ▼

Powered by Google Translate


Gôndola > 3.80 mts
80 cm
8 cm
RF
Irr
D1
D2
D3
D4
D5
D6
D7

Elementos:- (Colocar 2 cm a mais no comprimento de cada elemento, deixando 1 cm nas pontas e furar)

Medidas dos Elementos já com 2 cm

RF = 59.0 cm de comprimento

Irr = 57.0 cm de comprimento
D 1 = 55.5 cm de comprimento
D 2 = 54.5 cm de comprimento
D 3 = 53.0 cm de comprimento

D 4 = 52.0 cm de comprimento
D 5 = 51.0 cm de comprimento
D 6 = 50.0 cm de comprimento
D 7 = 49.0 cm de comprimento


DIRECTOR 1
DIRECTOR 2
IRRADIANTE
REFLECTOR

Señales de radio


S-1-3-5-7-9-20-40-60 dB
PWR-10-25-50-100W
SWR 1-1.5-3-∞
ALC

SAN MAXIMILIANO KOLBE (SP3RN) patrono de los Radioaficionados.



El día 14 de Agosto, es la festividad de San Maximiliano María Kolbe Dabrowska SP3RN, patrono de los Radioaficionados, en conmemoración de la fecha de su muerte.

DIVISIONES // PREFIX

Sugar Delta Prefix ▼

CODIGO FONETICO

Codigo I.C.A.O.. ▼

ARCHIVO SD.

ARCHIVO SD. ▼

MI CANAL EN YOUTUBE




Folded Halfwave Dipole
L
4:1 BALUN
LA8OKA
Martin Storli
http://www.arcticpeak.com
arcticpeak@yahoo.no
L= 299,8 x 0,5 x 0,95 / Frequency in MHz
Cut for resonance!
Coax to shack


HB9CV 27.000 mhz
DIR
5,1 mt
leng1
1,6 mt
Dist
0,05 mt
300 ohms FEEDPOINT
TwinLead
12 a 25 mms
spac.
1,38 mt
1,5 mm
isolated wire
ALUMINIUM TUBING
leng2
1,7 mt
REF
5,5 mt


cm135
cm 410
airpin in filo di circa
30 cm


alimentazione
idea in tubo di rame


700
100
770
100
250
50
840
1110
RG-58
Ferda
OK2FJ

Direcional Quadra Cúbica de 2 elementos


2,895m
2,10m
refletor
2,82m
1,99m
isolante
irradiante
refletor
irradiante
1,60m
mastro

*Usar fio 14.

-Refletor - Circuito fechado
-Irradiante - Circuito aberto


asymétrique
1
2
A
3
4
symétrique
5
6
A'
1
2
3
5
6
4

Balún 1:1


40
L
96
C
382
Radiat.
382
40
L
C
96
A
*Cavallotto
12 cm
*
Direttore
353
96
C
31
L
353
C
96
L
31

Pianta dell'antenna (quote in cm)

L = 13 spire serrate, filo rame Ø 1,2 mm unipolare isolato in plastica (circa 2 μH);
C = circa 20 pF; 19,5 cm cavo coassiale RG 174-U


guaina termorestringente
F_o = = 21,040 MHz
aperto
RG 174
siliconare

Trappola

Balun



18 spire serrate di cavo RG58-U (50 Ω) su tre cilidri di ferrite (del tipo per radiolina per OM). Il tutto è incapsulato in una guaina termorestringente


YU1QT WIRE MOXON 3el. Monoband for 27 MHz
wire Copper in PVC; 2,5mm sq (1,8mm.dia, #14) =
NYLON ROPE 2mm =
Fishing rod's (7m long,without two last segment's)=
3,95m
DIRECTOR
0,46m
1,59m
source
DRIVER
0,63m
outlook
A - A
1,26m
0,69m
REFLECTOR
SOURCE SHEMATIC
DRIVER ELEMENT WIRE CENTER
TERMINAL STRIP
TEFLON MADE
COAX KABL
50 Ohm
WIRE ELEMENT
END
OUTLOOK : A - A
CABLE TIE
4" + add. in wire length, tilted back
for eventual post adjusting
NEXT ELEMENT
ROPE.


D
RA1
RA2
RA3
RF
D = Ø 10 e 12 mm
tutti gli altri
Ø = 10, 12 e 16 x 1 mm
Unire al centro
con Ø 40 x 2 mm
il boom
boom in
due pezzi
Ø 35 mm x 2 mm
90°
A
B
C
balun
52 Ω
quote
misurate dal
centro degli
elementi
161,0
74,5
76,5
91
258,3
262,8
267,4
272,0
294,8
N.B.: isolare i semidipoli dal boom
RA1
RA2
RA3
x
y
k
w
52 Ω
balun
linea aperta (scaletta)
distanziatori in plastica (teflon od altro)
3 cm
isolare la linea dal boom
conduttore Ø 5mm
doppio cavetto RG59 (75 Ω e fatt. vel. = 0,66)
k
w
x
y
lungh. λ/4 per fattore di velocità (0,66) =
= m 1,73 per cavo RG59 e freq. 28,6 MHz
cavo
52 Ω
35 cm
15 cm
angolari
di alluminio
per Ø 42 mm
o Ø 35 mm


HB9CV 27.000 mhz
DIR
5,1 mt
leng1
1,6 mt
Dist
0,05 mt
300 ohms FEEDPOINT
TwinLead
12 a 25 mms
spac.
1,38 mt
1,5 mm
isolated wire
ALUMINIUM TUBING
leng2
1,7 mt
REF
5,5 mt


Straler 215 cm Frequentie 27.205 Mhz
Nylon koord
Nylon koord
RG 58
RG 62
De 2 kabels in de PL 259 plug schroeven
PL 259


G0KSC
28MHz 3el 50Ohm LFA Yagi
(NOT TO SCALE)
3.047m
1.829m
0m
RE
Feedpoint
.609m
0.706m
DE 1
DE 2
1.691m
DE
Plastic Insulators
16mm - 5/8 inch diameter tube
D1
Mid Section
3.450m
Outer Section
10mm - 3/8 inch diameter tube
13mm - 1/2 inch diameter tube
Boom Thickness - Builders Preference
Boom Length : 3.450m
Wind Survival: 115 mph (elements)
Feed system: 1 feedline with 1:1 balun
Direct 50 ohm feed
NOT FOR COMMERCIAL USE
Copyright, G0KSC 2010
www.g0ksc.co.uk


G0KSC
28MHz 4el 50Ohm LFA Yagi
(NOT TO SCALE)
3.2m
0m
RE
Feedpoint
0.359m
DE 1
DE 2
1.372m
G0KSC Insulators
Aluminium Mount plates
D1
Outer Section
2.398m
Inner Section
Boom Thickness - Builders Preference
D2
5.020m
16mm - 5/8 inch diameter tube
20mm - 3/4 inch diameter tube
Boom Length : 5.020m
Wind Survival: 120 mph (std)
Feed system: 1 feedline with 1:1 balun
Direct 50 ohm feed
NOT FOR COMMERCIAL USE
Copyright, G0KSC 2010
www.g0ksc.co.uk


1531mm
2000 mm
1531mm
DIRETOR
1300 mm
1684 mm
2000 mm
1684mm
IRRADIADOR
525
1700 mm
1850mm
2000 mm
1850mm
REFLETOR


ANTENA HELICOIDAL p/ 40m.
TAPON para que no entre agua.
Con el propio soldador, hacer estas hendiduras para poder fijar los 4 radiales del sombrero capacitivo
35cm
35cm
50Ω
A 1/2"
35cm cada uno del centro.
Arrollamiento uniforme de 4mts Ø 1'5mm
2'5m
Arrollamiento de 2m. Ø 1mm
I x 1/2"
A 1/2"
1m
1m
PY5ZCL
Antonio
IRADIANTE
RADIAL 1 y 2
Agujero para ventilación
SO-239
TAPON
SUPERFICIE TAPON
50Ω
Tal y como comenté, la tengo montada en el balcón y sólo 1 radial.
Particularmente, no tenía a mano el SO-239 y utilizé un trozo de C.I. con el siguiente diseño, y sin tapón.
To shack.


4.51 director 2
L A R G O T O T A L
4.25
1.79
4.98 director 1
1.088
5.26 dipolo
1.36
4.45 reflector


4.96 director 1
L A R G O T O T A L
3.27
1.87
5.34 dipolo
1.40
5.51 reflector


4.92 director 2
L A R G O T O T A L
5.43
2.73
5.13 director 1
1.60
5.14 dipolo
110
5.48 reflector


4.96 director 1
L A R G O T O T A L
3.81
1.63
5.24 dipolo
2.17
5.36 reflector


4.92 director 3
L A R G O T O T A L
7.61
2.72
4.96 director 2
1.96
5.00 director 1
1.41
5.18 dipolo
1.52
5.48 reflector


5.00 director 4
2.72
5.10 director 3
2.61
L A R G O T O T A L
10.43
4.96 director 2
2.17
5.24 director 1
1.41
5.40 dipolo
1.52
5.64 reflector


5,286 Dipolo
1.219
5.492 reflector


4.2164Mtrs Dipolo
1.83mtrs
5.3086mtrs reflector

medidas en metros
diametro del gama 10 mm el caño de aluminio con un cable coaxil sin malla de un largo aprox de 50 de calbe y 70 de aluminio

luego agustrar con elemento dipolo, diametro de los elementos 20 mm 14 mm 10 mm boom cuadrado de 30 x 30 mm


QUAD PARA 10 Y 11
A = 11,24m
copper wire
fiberglass stick
A = longitud total del alambre de cobre
r = longitud del palillo de bambú
d = longitud del alambre de cobre (1 lado)
PVC stick
r = 1,99m
d = 2,81m
1,8m 75 Ohm coax
fiberglass tower
RG coax to TX


QUAD PARA 20
A = 21,48
copper wire Ø 4mm
fiberglass stick
A = longitud total del alambre de cobre
r = longitud del palillo de bambú
d = longitud del alambre de cobre (1 lado
PVC stick
d = 5.37
1,8m 75 Ohm coax
fiberglass tower
RG coax to TX


QUAD PARA 15 METROS
A = 14.32
copper wire Ø 4mm
fiberglass stick
A = longitud total del alambre de cobre
r = longitud del palillo de bambú
d = longitud del alambre de cobre (1 lado)
PVC stick
d = 3.58
1,8m 75 Ohm coax


20 METROS DELTA LOOP
A= 23.13
A = longitud total del alambre de cobre
r = longitud del palillo de bambú
d = longitud del alambre de cobre (1 lado)
d = 7.71
1,8m 75 Ohm coax
fiberglass tower
RG coax to TX


15 METROS DELTA LOOP
A= 14.2
A = longitud total del alambre de cobes
r = longitud del palillo de bambú
d = longitud del alambre de cobre (1 lado)
5.8
4.20
d = 4.20
1,8m 75 Ohm coax
fiberglass tower
RG coax to TX


QUAD PARA 10
A = 10.72
copper wire
fiberglass stick
A = longitud total del alambre de cobre
r = longitud del palillo de bambú
d = longitud del alambre de cobre (1 lado)
PVC stick
d = 2.68
1,8m 75 Ohm coax
fiberglass tower
RG coax to TX


8 Vueltas
15,2 cms


A LA ANTENA
FERRITE
1
2
1
2
AL RECEPTOR


M4-M6 Bolts
Insulator
Soldered joint
RG Coaxial cable
Enclosure Case
Balun Transformer
Crimp Joint
SO-239 Chassis Mount

Figure 5



« Bambi » Antenna

ANCHO — 455 cm.
ALTO — 224 cm

112 cm
112 cm
224 cm
ALTO
227.5 cm.
227.5 cm.
455 cm. ANCHO

e antenna brace will be made of 2 ngths of plastic tube, these ones

metres) and attach it at the top th side so as to finish at the bottom.


C
Refletor
B > C = 1,66 mts
2,75 mt
1,95 mt
B
Iradiante
A > B = 1,27 mts
2,61 mt
B 1
1,86 mt
B1 > C=1,46 mt
A
Diretor
Coaxial
1,75 mt
2,47 mt


cap
A
T
cap
A
reflector
B
driven element
butt connector
no glue
D
T
C
X
C
T
D
D
no glue
D
G
3/16" hole thru 1/4" from end
nylon cable ties hold corners
(see figure 2 for detail)
PL-259 w/ RG-58 adapter

Figure 1: Exploded View

Skypperbeam project


* Misure/Freq. in cm
Front side
6690,3/Fr
6690,3/Fr
Director element
3006,3/Fr
3006,3/Fr
Fed point
6754,4/Fr
6754,4/Fr
Driven element
2565/Fr
2565/Fr
7129,7/Fr
7129,7/Fr
Reflector element
Copper wire 1,5mm
Teflon wire

Structure is a cross with 4 fiberglass roods lengh 1,05 more lengh of dipole.
of necessary for obtain an "inverted umbrella" shape.
For to jam the wire to the fiberglass roods, use plastic "T"element for garden use.
Also the central cross is with plastic cross, with 2 connepted "T" element for
electric plane use.


DIRECTOR
DRIVEN ELEMENT
VERTICAL
GAMMA MATCH
GIZMOTCHY


Ⓒ
Ⓑ
ANTENA "HB9CV"
CONSTRUCCIÓN SEGÚN
EB1HBK
Ⓐ
OTRA FORMA DE SUJETAR Ⓐ
CLEMA DE REGLETA ELÉCTRICA
UNIR Y SOLDAR
ABRAZADERA METÁLICA
VARILLA DE COBRE
EL SEPARADOR ES UN TROZO DE COLA TERMOFUSIBLE
UNIÓN SOLDADA Ó ACOPLAMIENTO POR CAPACIDAD
Ⓒ
TUBO DE COBRE
CLEMA SOLDADA AL CLIP
Ⓐ
BRIDA
CLIP HECHO CON HOJALATA
VARILLA DE ALUMINIO ANODIZADO
SOPORTE PARA MÁSTIL Ó MANO (SE PUEDE GIRAR VERTICAL/HORIZONTAL)
Ⓑ
UNIÓN SOLDADA O POR VARILLA ROSCADA


1570
2000
1570
Directeur = 5140
2200
3440
1730
2000
1730
Dipôle = 5460
80
SO239 - CV100 Pico F
700
1240
495
Réflecteur = 5700
80
1850
2000
1850



Quarter Wave Antenna, de CE1UIC

Formula for all the elements
L = (75 / Frequency in MHz) * 0.96
To calculate the length of the elements for other bands use the above formula.
Example 6-meter band (50MHz):
(75 / 50) * 0.96 = 1.44 meter

Dimensions for the 2meter band
L1 = 49 cm (cut for best SWR if needed)
L2...L5 = 49 cm

Dimensions for the 70cm band
L1 = 16 cm (cut for best SWR if needed)
L2...L5 = 16cm
Note: use N-connector instead of a PL-connector on UHF

Note:
L1...L5 = 1.5mm inox or steel

L1
1/4λ
1.5mm inox or steel
Hardened glue (from a glue-pistol)
120°
L2 & 3
1/4λ
L4 & 5
1/4λ
PL259
boom
aluminum tube 18...20mm
L1
L2
L4
L3
L5
boom



40
L
96
C
382
Radiat.
382
40
L
C
96
A
*Cavallotto
12 cm
*
353
Direttore
353
96
C
31
L
C
96
L
31
A
guaina termorestringente
RG 174
siliconare
F_o = = 21,040 MHz
aperto

Pianta dell'antenna (quote in cm)

L = 13 spire serrate, filo rame Ø 1,2 mm unipolare isolato in plastica (circa 2 μH);
C = circa 20 pF; 19,5 cm cavo coassiale RG 174-U

Trappola

Balun

18 spire serrate di cavo RG58-U (50 Ω) su tre cilidri di ferrite (del tipo per radiolina per OM).
Il tutto è incapsulato in una guaina termorestringente


∡ 30×30
400
isolare gli elementi
dalla crociera
n° 4
fori filett.
o bulloni saldati
350
rinforzo
interno
∡ 30 x 30
②
Particolare parte
superiore
⌀ 50
tubo leggero


YU1QT WIRE MOXON 3el. Monoband for 27 MHz
wire Copper in PVC; 2,5mm sq (1,8mm.dia, #14) =
NYLON ROPE 2mm =
Fishing rod's (7m long,without two last segment's)=
3,95m
DIRECTOR
0,46m
1,59m
source
DRIVER
0,63m
outlook
A - A
1,26m
0,69m
REFLECTOR
SOURCE SHEMATIC
DRIVER ELEMENT WIRE CENTER
TERMINAL STRIP
TEFLON MADE
COAX KABL
50 Ohm
WIRE ELEMENT
END
OUTLOOK : A - A
CABLE TIE
4" + add. in wire length, tilted back
for eventual post adjusting
NEXT ELEMENT
ROPE.


used measures = cm
1 meter = 39,3700787 inches
inches = x m / 0,0254
inches = x cm·10^-2 / 0,0254
284,834
201,408
277,921
196,520
269,625
190,654
261,536
184,934
163,268
141,499
163,268
RG-213 Coax
1KW Balon 1:1


THE ASSEMBLED SCANNER
H
G
E
J
D
F
A
"U" Bolt
G
D
B
H
G
E
J
F
G
L
D
E
J
F
G
L
H
G
L
Mast (Not Supplied)
RG 8/U or
RG-58/U (Not Supplied)
To Transceiver
3 or 4 wire cable
(Not Supplied) to
control box
'OMNI'-stub
cable with
plastic cap
on end (on
some models
only)
Printed in U.S.A.
27P3084 5/77


+
294 Ohms
294 Ohms
Mic Plus
12 Ohms
294 Ohms
294 Ohms
—
Mic Minus
2
Balanced XLR
3
1
7
1
6
8
2
GND Shield
5
3
4
Line-Level Output
(From mixer, EQ, etc.)
8 Pin Mic Connector (Icom)
©2009 NU9N


+
294 Ohms
294 Ohms
Mic Plus
12 Ohms
294 Ohms
294 Ohms
—
Mic Minus
2
Balanced XLR
3
1
7
1
6
8
2
GND Shield
5
3
4
Line-Level Output
(From mixer, EQ, etc.)
8 Pin Mic Connector (Icom)
©2009 NU9N


294 Ohms
294 Ohms
+
Mic Plus
12 Ohms
—
Mic Minus
2
Balanced XLR
3
1
7
1
6
8
2
294 Ohms
294 Ohms
GND
Shield
5
3
4
Line-Level Output
(From mixer, EQ, etc.)
8 Pin Mic Connector (Kenwood)
©2009 NU9N




EIFFEL antenas

135/174 MHz

ANTENA FIJA
OMNIDIRECCIONAL
DE VHF

VHFO - 5dB

CARACTERISTICAS ELECTRICAS

Potencia máxima .... [illegible] Watts
Ganancia 7,1dBi
R.O.E. Máximo 1,5:1
Rango de Frecuencia .... 135-174 MHz
Impedancia de entrada .... 50 Ohms
Protección contra descargas .... Irradiante a masa

CARACTERISTICAS MECANICAS

Resistencia máxima al viento .... 180 Km/h
Material provisto .... Tubos de aluminio templado (Aleación 6162 T-10 CAMEA)
Peso .... 1 Kg
Conector .... SO 239
Tornillos .... Bronce niquelado

Armado General

Para el armado general de la antena de acuerdo a la frecuencia a utilizar ver tabla de medidas A, B, y C expresadas en mm.

Frecuencias en Mhz	A	B	C
135	1511	1389	247
137	1492	1365	241
140	1460	1333	235
142	1441	1314	231
145	1409	1282	228
147	1390	1263	223
150	1368	1236	222
152	1339	1219	219
155	1320	1200	216
157	1296	1175	212
160	1271	1155	209
162	1161	1120	206
165	1141	1110	201
167	1121	1086	197
169	1095	1072	192
171	1077	1057	185
174	1053	1037	178

5-1



ANTENA RINGO - VHF

fMhz	A	B	C
135	1511	1384	247
136	1501	1374	243
137	1492	1365	241
138	1482	1354	239
139	1470	1344	237
140	1460	1333	235
141	1450	1324	233
142	1441	1314	231
143	1431	1304	229
144	1421	1294	228
145	1410	1283	227
146	1400	1273	226
147	1390	1263	225
148	1380	1255	224
149	1369	1246	223
150	1359	1238	222
151	1349	1228	220
152	1339	1219	219
153	1330	1210	218
154	1322	1202	217
155	1314	1193	216
156	1305	1184	214
157	1295	1175	212
158	1287	1168	211
159	1278	1162	210
160	1270	1155	209

LAS MEDIDAS SON
APROXIMADAS Y
ESTÁN EXPRESADAS
EN MILÍMETROS




70 cm 5/8
de onda
435 MHz
Ganho:
3dB (5,15 dBi)
427 mm
L: 5 voltas de fio rígido
de 2 mm
ø 5 mm diâmetro
10 mm de comprimento
163 mm
Conector "N"
arearf.blogspot.com


HF 20M/15M/10M DELTA LOOP ANTENA
75 Ohm Coaxcial
50 Ohm Any Length To TRX

	Panjang elemen	75Ohm
10M Band (28.500Mhz)	3 X 3.58 m	1.78 m
15M Band (21.200Mhz)	3 X 4.82 m	2.20 m
20M Band (14.200Mhz)	3 X 7.19 m	3.32 m


2,67 METROS
2,67 METROS
ALUMINIO DE 5/8 X 1/16
1,52 METROS
BARRA DE ALUMINIO PARA FIXAÇÃO
0,38 METROS
0,10 METROS
GAMMA MATCH
2,54 METROS
2,54 METROS
1,02 METROS
2,41 METROS
2,41 METROS
1,02 METROS
2,29 METROS
2,29 METROS
1,02 METROS
ALUMINIO 1 ½ X 1/16
2,18 METROS
2,18 METROS
1,02 METROS
2,07 METROS
2,07 METROS
GONDOLA QUARADA 1 ½ X 1/16
BY: PY1MK DESING


STILO TELESCOPICO 1,4 – 1, 5 MT
20 Spire filo dia.1mm su Supporto dia. 15 mm
20 Spire filo dia.1mm su Supporto dia. 15 mm
Ant. esterna
80 spire filo dia. 0,8 mm
A
B
Cond. Variabile 150-250 pf
T 200 rosso
Commutatore Min. 12 posizioni
8a spira
led
Toroide con 15 sp. Filo dia 0,5 mm
RTX
Deviatore levetta
4a spira
RADIALE
A e B = inizio e fine avvolgimento sul toroide !
ANTENNA PSEUDO “ MIRACLE “ 1,8 – 30 Mhz
I3PVE - 2012 – 3a versione con wattmetro a led

TUNE
RF
A


The original WINDOM
My Favorite Multi-Band Antenna
136 Ft.
L 1
Long Leg
BUX COMM Model 806136
PVC covered
L 2
Short Leg
PVC covered
"A"
"A"
"B"
BUX
BALUN
"B"
25 to 50 feet above ground
"C" Coax
To TRANSCEIVER

A = NyTYTE end and center Insulator (s)
B = 4 to 1 BALUN suspended by center Insulator (not shown).
C = 50 ohm coax cable. (NOT INCLUDED)
L1= Power-Flex. 41 strands of tinned copper.
L2=Power-Flex. 41 strands of tinned copper
NOTE: Tye-Tails at "A" & "B" included in wire length.
Keep Tye-tails as short as possible (3" or less).
Operating CW and SSB on 80, 40, 20, 15, 10, & 6 meters.


A
B
C
B
A
DIRECTOR
3000
IRRADIANTE
2340
REFLECTOR
2050
2050

DIRECTOR	A	B	C	TOTAL
FONIA	840	300	5000	7280
CW	840	300	5160	7440
IRRADIANTE				
FONIA	940	300	5240	7720
CW	950	300	5410	7910
REFLECTOR				
FONIA	850	300	5440	7740
CW	850	300	5690	7990

DETALLE DEL ACOPLADOR: ESTÁ COMPUESTO POR 2 RAMAS CENTRALES SIN MALLA DE CABLE RG213

EL ENCAPSULADO CENTRAL ES DE MATERIAL AISLANTE Y LLEVA UN CONECTOR HEMBRA S0239
SE RECOMIENDA QUE EL CABLE DE ALIMENTACIÓN EN EL EXTREMO DE CONEXIÓN, TENGA UN BALUM COMPUESTO POR 4 ESPIRAS SIN ESPACIAR DEL MISMO CABLE SIN NUCLEO Y 100 MM DE DIÁMETRO PRECINTADO PARA MANTENER LA FORMA, TODO EL CONJUNTO SE AMARRA AL BOOM.

NOTA: TODAS LAS MEDIDAS ESTÁN EN MILÍMETROS


Isoladores
5cm
(os dois centrais)
Isolador
PVC
5cm
Isolador PVC 5cm
Coaxial 50Ohms
ligar no Rádio

Antena de tamanho reduzido para 40M

Esta Antena foi construida para 40 metros mas o modelo pode ser aproveitado para todas as demais bandas, bastando-se calcular o tamanho especifico para cada uma delas Usa-se a fórmula 142.5 / freq(mhz)

Comprimento total (fio azul no desenho) de cada lado da antena de 40M é de 10,06m

10,06 de cada lado da antena, compreendendo-se do isolador Central até o outro na parte superior da Antena

Tubos de PVC, com 21cm de comprimento usados para manter os fios da antena alinhados e separados. São 8 pedaços de 21 cm de tubo de PVC de 3/4
Furar as pontas e transpassar o fio de forma continua, de acordo com o desenho.

Transpassar os fios e para manter o PVC alinhado prender com pequenos pedaços de fio de cobre encapado ou não


D
C
C
"B"
NO CORTE EL CENTRO
E
E
A
A
Linea bifilar
300 ohms
Linea bifilar
300 ohms
CONECTE A MALLA
SOLAMENTE
COAXIAL ES RG-58
ó RG-8
XE3RLR
AL TRANSMISOR


VHF Portable Multiband Dipole, de ON6MU
telecopic antennas
L1
S
L2
shoke
75mm
plastic box 50x75x22
telescopic antenna
14cm...85cm
7
50mm
RG174
ferit shoke
BNC
14cm
14cm


TAPON
48-3/4"
9"
2"
1/2"
ESTE TUBO CONTINUA ARRIBA
EL LARGO TOTAL ES 78-3/4"
TAPON
1-1/2"
23"
ABRAZADERA
2-3/4"
3"
8"
CABLE RG-58
MASTIL
Antena 2 mts
DISEÑO - John Conklin - WDOO
ADAPTACION - Antonio Pontòn - WP4NAL





MORE ICOM MICROPHONE INFO

MODEL	PIN NUMBERS							
	1	2	3	4	5	6	7	8
IC740	mic	9 volts	n/c	n/c	ptt	earth	mic earth	n/c
IC730	mic	8 volts	up/down	n/c	ptt	earth	mic earth	n/c
IC740	mic	8 volts	up/down	squelch	ptt	earth	mic earth	n/c
IC745	mic	8 volts	up/down	squelch	ptt	earth	mic earth	n/c
IC751	mic	8 volts	up/down	squelch	ptt	earth	mic earth	audio out
IC505	mic	8 volts	up/down	squelch	ptt	earth	mic earth	n/c
IC560	mic	9 volts	up/down	squelch	ptt	earth	mic earth	n/c
IC255	mic	9 volts	up/down	n/c	ptt	earth	mic earth	n/c
IC260	mic	9 volts	up/down	n/c	ptt	earth	mic earth	n/c
IC290	mic	8 volts	up/down	squelch	ptt	earth	mic earth	n/c
IC25	mic	8 volts	up/down	squelch	ptt	earth	mic earth	n/c
IC251	mic	9 volts	n/c	n/c	ptt	earth	mic earth	n/c
IC271	mic	8 volts	up/down	squelch	ptt	earth	mic earth	audio out
IC45	mic	8 volts	up/down	squelch	ptt	earth	mic earth	audio out
IC490	mic	8 volts	up/down	squelch	ptt	earth	mic earth	tone
IC451	mic	9 volts	up/down	squelch	ptt	earth	mic earth	n/c
IC471	mic	8 volts	up/down	squelch	ptt	earth	mic earth	audio out
IC120	mic	8 volts	up/down	squelch	ptt	earth	mic earth	audio out


MULTI- BAND DIPOL
9A7 BFX
3.7 MHz
7.05 MHZ
14.2 MHZ
18.1 MHz
21.2MHz
28.5 MHz
2.464 m
3.38 m
3.89 m
5.03 m
10.06 m
18.44 m
Cu licna žica Ø2 mm sa PVC izolacijom
4 cm
PVC izolator Ø 12-15 mm
PVC ploča
PVC zaštitna kutija
RG 58/59
šelna
cijev -nosač

Mogućnost podizanja i spuštanja dipola pomoću kolotura u slučaju nepovoljnih vremenskih uvjeta.

Napojni kabel se priključuje direktno bez baluna, a moguća je i ugradnja baluna omjera 1:1
Krajeve antene od zemlje podići na minimalnu visinu od 2m.


A = •—
B = —•••
C = —•—•
D = —••
E = •
F = ••—•
G = ——•
H = ••••
J = •———
K = —•—
I = ••
L = •—••
M = ——
N = —•
O = ———
P = •——•
Q = ——•—
R = •—•
S = •••
T = —
U = ••—
V = •••—
W = •——
X = —••—
Y = —•——
Z = ——••
1 = •————
2 = ••———
3 = •••——
4 = ••••—
5 = •••••
6 = —••••
7 = ——•••
8 = ———••
9 = ————•
0 = —————
TITI
TATITA
TITATATATA
TITI
TATITATI
TATITI
14,050
AP
10000 PF
BC328
BC237
C
B
E
B
C
E
PILA 9 V
+
-
100 K
Trimmer 100 K
TASTO
BC328
BC237
E B C


Antena dipolo "Múltipla"
10-11-15-20-40 e 80 mts
C = 22.20 mts
1.10 mt
10.00 mt
10.00 mt
1.10 mt
Bobina
Bobina
2mts cabo 75 OHMs
Cabo coaxial de 52 OHMs

Nota:- Uso obrigatório de acoplador

2 bobinas de cano de PVC 3/4" com 12 cm cada, enrrolado com 200 espiras de fio nº 14 esmaltado AWG
Isolador porcelana ou outro isolante

PY5 GG - Ribas


0,247 m.
"D"
7.87m.
"A"
2.61 m
"B"
"C" 0.256 m
Aprox.
unos 60cm
abrazaderas para manguera o
para mofle
Esta calculada para Frec. 27.300


Antena Borboleta - 7 Elementos - VHF
69 cm
38 cm
D 5
C = Cada elem. 1.76 mt
71 cm
39 cm
D 4
C = 1.81 mt
74 cm
40 cm
D 3
C = 1.87 mt
76 cm
41 cm
D 2
C = 1.92 mt
78 cm
43 cm
D 1
C = 1.98 mt
86 cm
47 cm
REF
C = 2.10 mt
1
2
3
82 cm
45 cm
IRRAD
C = 2.08 mt
Legenda:-
1 - Gamma- match - dist. 3.5cm
2 - Comprim = 35.5 cm
3 - Corpo cap. interno = 32cm, fixo elemento
35.5 cm
Conector
Elemento
3.5 cm
32 cm
Placa deslizante
37 cm
31 cm
43.5 cm
54 cm
62 cm
68.5 cm
Frente
R Ir D1 D2 D3 D4 D5
Gôndola = 3.60 mts
PY5 GG _ Ribas


5,70 mt
Refletor
B >C = 2,20 m
C
5,37 mt
A >B =1,8 m
5,06 mt
Irradiante
B
Gôndola - 4,00 mt
Diretor
A
A - B - C > 3 parafusos
PY5GG/PX5G 0654 - Ribas


+
294 Ohms
294 Ohms
Mic Plus
12 Ohms
294 Ohms
294 Ohms
—
Mic Minus
2
Balanced XLR
3
1
7
1
6
8
2
GND Shield
5
4
3
Line-Level Output
(From mixer, EQ, etc.)
8 Pin Mic Connector (Icom)
©2009 NU9N


HILO LARGO
Caja plástica
TIERRA
C
A
C
A
B
B
Conector PL259
RECEPTOR


A
B
Length is 1/2 of
C
no rompa el centro
D
E
coleta de alambre de cobre o tv
Conecte solo la malla
coleta de alambre de cobre o de TV
Coax is RG 58
area aisla con silicon caliente
Coax al Trasmisor

Largo Total A - E = 5.187mts

la mitad de B-D = 1.801

las coletas 79.25 cmm


7.77 M.
15.55 M.
7.77 M.
15.55 M.
ANTENAS
G5RV
4.80 M
10.80 M
COAXIAL 50 OHMS
ADOLFO - LU2AFG

Linha aberta:
escala de 3 a 5 cm
de separação

31,10 m - para 80-10 Mts
15,54 m - para 40-10 Mts.
Uma terceira possibilidade é usar 15,55m para cada lado da antena e no lugar da linha aberta, usar fio paralelo comum de 2X1mm com um comprimento total de 9,60m


EA1HBX L.Javier Fitera (c)2011
Antena coaxial BAZOOKA monobanda
L1 Exterior total = 300 / frec.Mhz (metros) = λ / 2 * 0,95
equiv.aproximado 140,2 / Frec Mhz
cable stándard o alma vivo coaxial, opcional doble bazooka escalerilla cortocircuitada 300 ohm en ambos extremos
L1
RG 58/213
dejar alma del vivo sin cortar,separar 3 cm de malla para soldar el coaxial de alimentación
soldar vivo con malla
soldar vivo de alimentación a malla radiante
soldar malla coaxial a malla coaxial del radiante
soldar vivo con malla
Longitud ramas laterales = L1 - L2 /2
L2
Longitud ramas laterales = L1 - L2 /2
cajita intemperie estanca
cable stándard o alma vivo coaxial, opcional doble bazooka escalerilla cortocircuitada 300 ohm en ambos extremos
L2 interior coaxial (metros) = 300 / frec.Mhz = λ frec / 2 * F.vel.cable coaxial (0,66 RG58/213)
equiv.aproximado 99,06 7 frec.Mhz
Detalle conexión central
No tocar el alma del vivo
cortar 3 cm malla
vivo a malla radiante
Malla a malla radiante
coaxial de bajada
Mástil de sujección,o sujetar por extremos con aisladores
Alimentación coaxial stándard RG 58/213 al equipo

-De los cálculos de L2, restar 2 cm de cada extremo del coaxial radiante para cortocircuitar vivo y malla soldando en cada extremo.
-El cable del extremo puede ser de cable stándard 2,5 mm2, vivo de coaxial,o escalerilla cortocircuitada en ambos extremos

EJEMPLOS MONOBANDA 40 MT:
- cortar extremos para ajuste fino-
L1 =300 /7,100 /2 * 0,95 = 20.07 Metros
L2= 300 /7,100 /2 * 0.66 = 13,94 metros
Ramas laterales = 20,07 -13,94 /2 = 3.06 mt por lado apróx.


W3DZZ
Isolador central e laterais de PVC com 5cm de largura
Fio 8 ou 10 Flexivel ou rigido
Bobina
Bobina
6,70
10,06
Distância entre o isolador central e a bobina = 10,06m
PVC
2,5 polegadas
Distância entre a bobina e isolador lateral = 6,70m
Coaxial 75ohms
60cm
PY1FW / PU1LHP
Tenório / Bira

Capacitor da bobina: 56PF ou fazer com cabo coaxial da seguinte forma: Cabo coaxial RG213 (grosso) com 60cm de comprimento. Descascar uma das pontas e ligar a malha de um lado da bobina e o vivo do outro lado da bobina. Importante: o cabo deve ficar dentro do cano de PVC da bobina.

Bobina: PVC de 2,5" (polegadas) de diâmetro e aprox. 60cm de largura.
Fio 12 (1mm) encapado
13 voltas completas

Se você não possuir cabo coaxial de 75 ohms, utilize fio paralelo número 8, usado para extensão de tomadas de rede elétrica, enrole bem para que ele fique trançado e pronto! Você terá uma linha de 75 ohms perfeita para ligar a antena no rádio.

Antena multibanda de 10 até 80 metros

ANTENA PARA RADIOESCUCHAS (SWL)


R
I
I
Coax to transmitter
I = Insulator
S = Support stake
R = Rope
I
R
S

6-8 "Slipole" or "sloper."


a
L
L
Coaxial cable to transmitter
$L \approx \frac{220}{F_{MHz}}$ Feet
Insulated support
R
S
I
I
R
S
I = Insulator
S = Support stake
R = Rope

6-7 Inverted-vee dipole.


House
Screw eyelet
Insulator
30 to 150 feet antenna wire
Mast, tree or other support
Rope
Downlead
Insulator
Screw eyelet
Lightning arrestor
Antenna wire
Window
Ground tab
Doorspring or counterweight
RX
Ground wire
Ground rod

13-5 Longwire SWL antenna.



BOW TIE LOOP

TOTAL 246' WIRE - COAX FED

DIMENSIONS CAN BE MOVED AROUND AS LONG AS YOU KEEP 246'

HANG VERTICAL



144-148 MHZ 4 ELEMENT QUAD

ELEMENT	HOLE TO HOLE DIA. FOR 1/4" DIA. DOWLES	CIRCUMFERENCE OF #14 OR #16 WIRE
REFLECTOR	30 1/8"	86 1/8"
DRIVER	28 9/16"	81"
DIRECTOR #1	27 1/2"	77 15/16"
DIRECTOR #2	25 5/8"	74"

DETAIL C: THREAD WIRE THRU HOLE IN 1/4" DOWEL

DETAIL B: FEED POINT AS SIDE FOR VERTICAL; BOTTOM FOR HORIZONTAL POLAR.

CUT / SPREAD PLASTIC 'T'. INSERT BOOM TO BALENCE POINT. GLUE OR PIN LAST.

CUT DOWN EN OF VERTICAL DO TO FIT INSIDE O THREADED PLA ADAPTER / GLU

DETAIL A: 1/4" DOWLING. GLUE AT CENTER POINT



ANTENA "G5RV"

80 m a 10 m

AVISOS IMPORTANTES !

1. Esta antena é de "banda-larga", ou seja, tem **sua ressonância** em uma **"ampla"** (e bota "ampla" nisto !) **gama de frequências**,
2. **Deve ser utilizado, *obrigatòriamente*: um Acoplador de Antenas !**
=> Não a utilize sem um, pois seu equipamento poderá ser danificado
3. Altura Mínima de Instalação: 10 (dez) metros;
4. Apesar de **muita gente** usar Coaxial de 50 ohms e/ou "Fita de TV":
=> Isto ****não condiz****, com o ****artigo original**** de **"Mr Louis Varney"** !
=> A nossa experiência, **não os recomenda**, de modo algum !
=> Podem haver **sérios** problemas de RFI/TVI !
5. Instale a linha-aberta o mais LONGE possível de mastros, torres, de Antenas Parabólicas e Antenas de TV **externas**, bem como dos Fios de Telefone ! Tanto dos **seus**, quanto dos **vizinhos** !
6. Esta antena possue algumas vantagens em relação à Dipolos, porém **não é** uma antena "silenciosa". Se quer silêncio, vá para VHF/UHF !
7. Apesar de não ser muito "normal", a instalação desta antena na forma de "V" Invertido, não irá produzir resultados "espetaculares" (bons...) !
8. Ninguém disse que o **ângulo entre as "pernas"** de uma antena em formato de "V" Invertido, deve ser **exatos** 90° (noventa) graus !
Você pode usar, de **110°** até cerca de **160°**, **sem nenhum problema** !
9. Os dois lados são simétricos, ou seja, com as mesmas dimensões;
=> O comprimento total (**de ponta-a-ponta**) é de **31 m**..

Linha-Aberta:
Material: Fio de Cobre (2 mm^2)
Espaçamento: 5 (cinco) cm
Material dos Espaçadores: **Isolante** (não use PVC ou "Fita de TV");
Sugerimos: **Nylton, Delrin, Polistireno**, etc
=> O **acrílico,** deteriora-se ("esfarela") **quando exposto ao tempo** !
Comprimento: **Entre 4.90m e 10.90m**
=> Valor Nominal (aproximado): **10,35 m**

Ligação Direta da Linha-Aberta ao Cabo Coaxial:
=> Não utilize nenhum tipo de "Balun" !
=> Exceto, se desejar, um "**Choque de RF**" (lê-se "chôque", **e não** "chóque"):
De 6 a 8 espiras do próprio cabo coaxial, em uma forma isolante (plástico,etc) com aproximadamente 15 cm de diâmetro, não "embolando" as espiras !
Distribua de modo uniforme, nesta forma (como uma "bobina"), e as **fixe**.
Atenção ! Para 15 cm x 6 espiras, serão necessários, cerca de 7 (sete) metros, **a mais**, de cabo coaxial ! Este **valor**, deve estar situado, entre um mínimo de **5,50 m,** e um máximo de **8,50 m**, sendo que estes comprimentos, são **muito mais importantes**, que o próprio **diâmetro da forma** !
=> **Não utilize em hipótese alguma**, uma forma não-isolante (de metal...) !

Cabo Coaxial (75 Ohms) ao Equipamento:
Tipo: **RG-6** ou **RG-59** ("fino"), ou **RG-11** ("grosso");
=> Comprimento Mínimo de Cabo Coaxial: **21 (vinte e um) metros**
=> Portanto: **21m + 7m** (do "Choque") são **28 m, no total,** de cabo coaxial

73 & DX ! de, PP5VX

Dezembro 2006
Revisão I


DIPOLO STANDARD HORIZONTAL SIMÉTRICO
EA1HBX (c) L. Javier Fitera
resumen esquemático DIPOLOS
1/2 λ
Z= alta,
V= alta,
I= baja
Z= baja, I = Alta
73 ohm
Z= alta,
V= alta,
I= baja
1/4 λ
1/4 λ
ROE min: 1,5:1 sobre 50 ohm
chokebalun 1:1
punto alimentación coaxial
1/2 λ
patrón polar
Al equipo
52 ohm
DIPOLO V INVERTIDA
1/4 λ
1/4 λ
chokebalun 1:1
punto alimentación coaxial
ROE min 1:0 sobre 50 ohm
Longitud total 1/2 λ
patrón polar

Los conductores tienen efecto capacitivo con respecto al suelo del entorno,lo que hace variar la resonancia.

En posición horizontal se obtiene directividad

Chokebalun 1:1 = unas vueltas con el coaxial núcleo de aire o sobre anillos de ferrita
Cancela las corrientes de vuelta de RF (i3) y evita alargar la longitud fisica por el polo de la malla

Poner aisladores en extremos y soporte central, estirar bien los cables antes de cortar los conductores, la intemperie los dilata con el calor y encogen con el frio

En V invertida se hace omnidireccional

NOTAS del AJUSTE en la práctica:

-Si la antena está baja altura = la resonancia baja de frecuencia (efecto capacitivo)= corta extremos de los conductores unos cm.

-Si la antena resuena a una frecuencia más alta= antena corta= aumenta extremos de los conductores unos cm.

-Si la antena resuena en una frecuencia pero el valor de roe es alta= uno de los conductores es más largo que el otro o el chokebalun no es efectivo,el coaxial está influyendo

Longitud de onda λ = 300 / Frecuencia Mhz - la fórmula principal -

Longitud del dipolo = λ / 2 (media onda) * factor de velocidad del cable (0,95 hasta cierto diámetro de los conductores)

Longitud de cada conductor = longitud del dipolo / 2 (cuarto de onda cada uno)

Medidas para cables desnudos. Si se utilizan cables recubiertos, tienen efecto de dieléctrico que modifican la sintonía principal calculada y se necesita retocar, así como la altura de uso de la antena con respecto al escenario del entorno y el suelo.


6.7 m
12.2 m
2.45 m
12.2 m
6.7 m
1.8 m
RLN
1.8 m
1.8 m
RLN
1.8 m
4:1
BALUN
COAX TO RECEIVER
LEGEND
RLN
RL
NETWORK
END
INSULATOR
INSULATING
SPREADER
390 OHMS
18 µH
RL
NETWORK


Antena FDx80m - Dipolo de tamanho reduzido sem o uso de bobinas para a banda de 80M
comprimento total de 17,2m
menor que uma Dipolo de 1/2 onda para 40m
HAM
Radió BR
Pedaços de
fio rigido encapado
usado para evitar
que o fio da antena
saia da posição
Isolador
Central
10cm de
largura
5,60m
Isolador
da ponta
da antena
Nylon
PY1UAP
3,00m
Separadores:
O furo do meio
fica distante
15cm dos furos
das extremidades
Usar PVC
de 1/2 polegada
para os isoladores
das pontas e para
os separadores
30cm
entre o primeiro
e o terceiro furo
Soldar a malha
do coaxial
Soldar o vivo
do coaxial
Cabo Coaxial 50 ohms
Isolador das pontas
5cm de comprimento
Disposição do Fio. Lado direito da antena
Fio: Ideal 2,5mm
Pode-se usar também
de 1,5mm, mas, diminui
a largura de banda
10cm
15cm
Isolador
Central
30cm
Acrilico
Placa de Fibra
ou placa de PVC


A
B
C
D
E
F
G
Puente p/ 80 m
Puente p/ 40 m
Balun 1:1
Leyenda
A= 10.000 mm
B= 85 mm
C= 42,5 mm
D= 100 mm
E= 740mm
F= 42,5 mm
G= 1400 mm
DETALLES DE CONSTRUCCION
Placa aislante 120 x 120 mm
Separador aislante
Cada 500 mm
Detalle del extremo
Placa aislante 120 x 40 mm
X
Cuerdas de sujeción
Bridas de fijación del separador
Detalle X
DIB/FECHA:
ERM/19-05-2009
REV/FECHA:
CLIENTE:
NOMBRE:
Antena MORGAIN para
las bandas de 40 y 80 metros
EA4DCU
NÚM. DE PIEZA:
NÚMERO PLANO
1/20090519


Log-periodic Antenna 10 to 20 meters
Boom Details
Rear
Veroboard plate 2 3/4 x 1 1/4 x 1/10''
Nylon plate 8 x 4 x 1/2''
Screw 1/4''
Front
1 1/4''
Ø 3/4''
Ø 1/2''
1/2''
1/4''
1/2''
1 1/4''
1 1/4''
50Ω coax inside the boom
1 1/4''
40''
38 1/8''
33''
28 1/4''
24 3/4''
21 1/4''
18 1/8''
1/2''
96''
206 1/4''
Coax Connection
1 1/4''
Assembly Details
Front
Coax Connection
Septembrer 7th, 2007 - Philippe Groux, VA2PHI


Log-periodic Antenna 10 to 20 meters
Ø 1/4''
Ø 1/2''
Ø 3/4''
228 1/2''
170 1/2''
125 1/2''
98''
Rear
Front
1 1/4''
200 5/8''
146 1/2''
110 1/4''
83 7/8''
Septembrer 7th, 2007 - Philippe Groux, VA2PHI



How to hang a BALUN without damaging BALUN Antenna terminals.

"WRONG"
Do not support BALUN by Antenna Wire/Elements.

Use Eyebolt to support BALUN from Center Insulator.

BUXCOMM
E
F
F
B
C
A
G
D
D
BUXCOMM

"RIGHT"

A= BALUN Support Eyebolt,
B= Center Insulator Eyebolt Support
C= Support Link between Center Insulator and BALUN Eyebolt
D= Antenna Terminals/BALUN Connectors
E= Center Insulator
F/F=Loop antenna wire element(s) through insulator holes ,
G= Fold back wire element onto itself, secure with Ty-Wrap and cover with tape.
Visit: www.HamRadioExpress.com



EA1HBX (c) L. Javier Fitera
resumen esquemático DIPOLOS

DIPOLO STANDARD HORIZONTAL SIMÉTRICO
1/2 λ
Z= baja, I = Alta
73 ohm
Z= alta,
V= alta,
I= baja
Z= alta,
V= alta,
I= baja
1/4 λ
1/4 λ
ROE mín: 1,5:1 sobre 50 ohm
chokebalun 1:1
punto alimentación coaxial
1/2 λ
patrón polar
Al equipo
52 ohm
DIPOLO V INVERTIDA
patrón polar
1/4 λ
1/4 λ
chokebalun 1:1
punto alimentación coaxial
ROE mín 1:0 sobre 50 ohm
Longitud total 1/2 λ

Los conductores tienen efecto capacitivo con respecto al suelo del entorno,lo que hace variar la resonancia.

Poner aisladores en extremos y soporte central, estirar bien los cables antes de cortar los conductores, la intemperie los dilata con el calor y encogen con el frío!

En posición horizontal se obtiene directividad

Chokebalun 1:1 = unas vueltas con el coaxial núcleo de aire o sobre anillos de ferrita
Cancela las corrientes de vuelta de RF (i3) y evita alargar la longitud física por el polo de la malla

En V invertida se hace omnidireccional

NOTAS del AJUSTE en la práctica:

-Si la antena está baja altura = la resonancia baja de frecuencia (efecto capacitivo)= corta extremos de los conductores unos cm.

-Si la antena resuena a una frecuencia más alta= antena corta= aumenta extremos de los conductores unos cm.

-Si la antena resuena en una frecuencia pero el valor de roe es alta= uno de los conductores es más largo que el otro o el chokebalun no es efectivo,el coaxial está influyendo

Longitud de onda λ = 300 / Frecuencia Mhz - la fórmula principal -
Longitud del dipolo = λ / 2 (media onda) * factor de velocidad del cable (0,95 hasta cierto diámetro de los conductores)
Longitud de cada conductor = longitud del dipolo / 2 (cuarto de onda cada uno)
Medidas para cables desnudos. Si se utilizan cables recubiertos, tienen efecto de dieléctrico que modifican la sintonía principal calculada y se necesita retocar, así como la altura de uso de la antena con respecto al escenario del entorno y el suelo.



6.7 m
12.2 m
2.45 m
12.2 m
6.7 m
1.8 m
RLN
1.8 m
1.8 m
RLN
1.8 m
4:1
BALUN
COAX TO RECEIVER
LEGEND
RLN
RL
NETWORK
END
INSULATOR
INSULATING
SPREADER
390 OHMS
18 μH
RL
NETWORK


Antena FDx80m - Dipolo de tamanho reduzido sem o uso de bobinas para a banda de 80M
comprimento total de 17,2m
menor que uma Dipolo de 1/2 onda para 40m
HAM Radio BR
Pedaços de fio rígido encapado usado para evitar que o fio da antena saia da posição
Isolador Central 10cm de largura
5,60m
Isolador da ponta da antena
PY1UAP
Nylon
3,00m
Separadores:
O furo do meio fica distante 15cm dos furos das extremidades
Usar PVC de 1/2 polegada para os isoladores das pontas e para os separadores
30cm entre o primeiro e o terceiro furo
Soldar a malha do coaxial
Soldar o vivo do coaxial
Cabo Coaxial 50 ohms
Isolador das pontas 5cm de comprimento
Disposição do Fio. Lado direito da antena
Fio: Ideal 2,5mm
Pode-se usar também de 1,5mm, mas, diminui a largura de banda
10cm
15cm
Isolador
Central
30cm
Acrílico
Placa de Fibra
ou placa de PVC


Puente p/ 80 m
A
D
E
Puente p/ 40 m
G
C
B
F
Balun 1:1
Leyenda
A= 10.000 mm
B= 85 mm
C= 42,5 mm
D= 100 mm
E= 740mm
F= 42,5 mm
G= 1400 mm
DETALLES DE CONSTRUCCION
Placa aislante 120 x 120 mm
Separador aislante
Cada 500 mm
Detalle del extremo
Placa aislante 120 x 40 mm
X
Cuerdas de sujeción
Bridas de fijación del separador
Detalle X
DIB/FECHA.
ERM/19-05-2009
REV/FECHA.
CLIENTE:
NOMBRE:
Antena MORGAIN para las bandas de 40 y 80 metros
NÚM. DE PIEZA:
NÚMERO PLANO
1/20090519
EA4DCU



BEAN TIN antenna

S Sutherland, GM4BKV, shows us how to re-cycle our rubbish and produce a cheap and effective 15m antenna into the bargain

Aerial projects have, from time to time, been initiated by some rather strange events and this project is no exception — in fact this particular design arose as a consequence of updating our bathroom! One of the items left over from this epic event was the shower curtain rail, comprising two aluminium rods which fitted inside one another à la telescopic aerial.

RAW MATERIALS

One of the two rods had a spring and disc assembly which locked it into place, the combination being designed so that it could be fixed horizontally between two walls by means of spring tension. Having decided that a spare length of aluminium tubing must be useful for *something* I had kept it, never imagining that it would one day take to the air!

The project was prompted by hearing the numerous Soviet radio amateurs who operate on the 15m band with nothing more than a simple ground plane aerial - probably because they are cheap and easy to build - so it was decided to home-brew my own version.

CONSTRUCTION

The components needed are simple, inexpensive and easy to obtain, consisting of:

3 Jubilee clips
2 Exhaust system 'hangers' for Ford cars
3 Lengths of aluminium tubing, each piece of different diameter
1 70cm length of copper tube
1 Baked-bean tin
1 Co-axial chassis socket
2 Metal L-brackets
1 Piece of wood 160 × 15 × 6cm
Wire for radials
Pegs to hold the radials

Taking the widest of the aluminium tubes first, cut six to eight equally spaced slots down into one end and then do likewise with the second widest tube. Insert one tube inside the other and place the jubilee clip over the slotted area as shown in **Fig 1** and attach the remaining aluminium tube in the same way. Next, adjust the overall length of the assembly so that it measures exactly 3.3 metres in total, then lock the tubes together by means of the jubilee clips.

Take one of the car exhaust system hangers, place it on the base of the empty baked-bean tin and draw around the outside. Now cut a hole in the tin which is slightly *smaller* than the circle you have just drawn, then ensure that all the ragged edges are rubbed down using a suitable file. Push the hangers over the end of the copper tube and then push the bean-tin over the hangers. When completed, this assembly serves to electrically isolate the vertical element from the rest of the aerial and provides a degree of weather protection for the feeder termination.

The next job is to connect the centre pin of a co-axial chassis socket onto the bottom end of the copper tube. This can be achieved in a number of ways - such as using a (very!)large soldering iron to connect the two together, or alternatively by attaching a piece of stout copper wire to a suitable solder tag (the other being soldered to the co-ax socket centre pin) and then bolting the solder tag firmly on to the tube. In either case the metal should be cleaned thoroughly before operations begin, in order to make a satisfactory join. Regardless of the fixing method, it is also advisable to fit a static bleed resistor across the inner and outer of the co-axial socket - a 100k, 2W component being perfectly adequate.

The next step is to attach the six wire radials to the bean tin, so first cut the wire into 3.3m lengths. Make six equally spaced marks around the outside of the can, as near to the bottom as possible, tin the can at these points to aid attachment and then solder each radial wire into position (see **Fig 2**).

Fig. 1 (above, left) Tube clamping technique

Fig. 2 (below) Aerial base and radial attachment detail

Fig. 3 (above, right) Aerial support method

MOUNTING

Cut two 10cm pieces from the length of wood for use as stand-off brackets, then measure the width of the lowest aluminium tube and cut two slightly under-size holes in each of the stand-offs - the fit should be tight enough to support the aerial. Screw a metal bracket to each of the wood stand-offs and then secure these to the large piece of wood. Push the copper tube through the bracket holes (**Fig 3**) and then attach the rest of the aerial to the tube using a jubilee clip.

Dig a hole about 20cm deep, place the mount in it and refill the hole, pressing the earth down with your foot. Then, using suitable pegs, spread out the radial wires and secure them firmly as these not only fulfill an electrical function but also serve as supports for the antenna structure. When correctly installed, the base of the antenna should be about a metre above ground so that the radials are at an angle of 20° to the horizontal.

AERIAL TUNING

Tuning is achieved simply by varying the overall length of the vertical element, this is done by loosening the lowest jubilee clip and sliding the two tubes inside one another. SWR measurements will reveal when the antenna is presenting the best match and in practice it was found quite easy to obtain a 1:1 SWR.

CONCLUSION

The original antenna was fed with ordinary 50Ω co-axial cable, and using 100W I have been able to work DX as far afield as Chile, Japan, India, Tasmania, Canada and several parts of the USA. Apart from the satisfaction of working distant stations there is no doubt that a great deal of fun and pleasure can be obtained from such a home-brew project - after all it is *one* way of getting rid of old bean tins! ☐

Fig. 4 Sketch of finished aerial




164
179
177
142
106b
106c
181
10
104
166
86
140a
138
136
134
146
140c
151
147
168
140d
152
150
140b
170

FIG. 4


BALUN
4:1
50'
50'
2'
FEED POINT
20'
20'
53'
53'
3" LOOP

BOW TIE LOOP

TOTAL 246' WIRE - COAX FED

DIMENSIONS CAN BE MOVED AROUND AS LONG AS YOU KEEP 246'

HANG VERTICAL



ANTENA “G5RV”

80 m a 10 m

AVISOS IMPORTANTES !

1 .Esta antena é de “banda-larga”, ou seja, tem **sua ressonância** em uma **ampla** (e bota “ampla” nisto !) **gama de frequências**,

2. **Deve ser utilizado, *obrigatóriamente*: um Acoplador de Antenas !**

=> Não a utilize sem um, pois seu equipamento poderá ser danificado

3. Altura Mínima de Instalação: 10 (dez) metros;

4. Apesar de **muita gente** usar Coaxial de 50 ohms e/ou “Fita de TV”:

=> Isto ****não condiz****, com o ****artigo original**** de “**Mr Louis Varney**” !

=> A nossa experiência, **não os recomenda**, de modo algum !

=> Podem haver **sérios** problemas de RFI/TVI !

5. Instale a linha-aberta o mais LONGE possível de mastros, torres, de Antenas Parabólicas e Antenas de TV **externas**, bem como dos Fios de Telefone ! Tanto dos **seus**, quanto dos **vizinhos** !

6. Esta antena possue algumas vantagens em relação à Dipolos, porém **não é** uma antena “silenciosa” Se quer silêncio, vá para VHF/UHF !

7. Apesar de não ser muito “normal”, a instalação desta antena na forma de “V” Invertido, não irá produzir resultados “espetaculares” (bons ..) !

8. Ninguém disse que o **ângulo entre as “pernas”** de uma antena em formato de “V” Invertido, deve ser **exatos** 90° (noventa) graus !

Você pode usar, de **110°** até cerca de **160°**, **sem nenhum problema** !

9. Os dois lados são simétricos, ou seja, com as mesmas dimensões;

=> O comprimento total (**de ponta-a-ponta**) é de **31 m**..

73 & DX ! de, PP5VX

Dezembro 2006
Revisão I

Linha-Aberta:

Material: Fio de Cobre (2 mm^2)

Espaçamento: 5 (cinco) cm

Material dos Espaçadores: **Isolante** (não use PVC ou “Fita de TV”);

Sugerimos: **Nylton, Delrin, Polistireno**, etc

=> O **acrílico,** deteriora-se (”esfarela”) **quando exposto ao tempo** !

Comprimento: **Entre 4.90m e 10.90m**

=> Valor Nominal (aproximado): **10,35 m**

Ligação Direta da Linha-Aberta ao Cabo Coaxial:

=> Não utilize nenhum tipo de “Balun” !

=> Exceto, se desejar, um “**Choque de RF**” (lê-se “chôque”, **e não** “chóque”): De 6 a 8 espiras do próprio cabo coaxial, em uma forma isolante (plástico,etc) com aproximadamente 15 cm de diâmetro, não “embolando” as espiras ! **Distribua de modo uniforme**, nesta forma (como uma “bobina”), e as **fixe**.

Atenção ! Para 15 cm x 6 espiras, serão necessários, cerca de 7 (sete) metros, **a mais**, de cabo coaxial ! Este **valor**, deve estar situado, entre um mínimo de **5,50 m,** e um máximo de **8,50 m**, sendo que estes comprimentos, são **muito mais importantes**, que o próprio **diâmetro da forma** !

=> **Não utilize em hipótese alguma**, uma forma não-isolante (de metal...) !

Cabo Coaxial (75 Ohms) ao Equipamento:

Tipo: **RG-6** ou **RG-59** (”fino”), ou **RG-11** (”grosso”);

=> Comprimento Mínimo de Cabo Coaxial: **21 (vinte e um) metros**

=> Portanto: **21m + 7m** (do “Choque”) são **28 m, no total**, de cabo coaxial.

Power Antenna Co
1:1 Current / Choke Bal
5KW: 160 to 10 Mete
number: BL 10-163


UPPER ELEMENT
48-3/4"
9"
2"
INSULATOR
1/2"
PHASING STUB
LOWER ELEMENT
MATCHING STUB
1-1/2"
67-3/4"
19"
2-3/4"
3"
8"
CLAMP TO MAST


N1LO MOBILE HF ANTENNA
80-10m
CAPACITY HAT STAINLESS SPRING WIRE
.020"
.041"
32"
0.125" STAINLESS WHIP FROM K40 CB ANTENNA
48"
MONOFILAMENT STAYS TO FRONT OF VEHICLE
24"
112"
AIR-CORE LOADING COIL, 40 TURNS @ 3.75" DIAMETER 14-GAUGE COPPER, 7.5 TURNS/INCH, W/ BANANA JACKS SOLDERED AT TAP POINTS
6.25"
HEAVY COAX BRAID JUMPER WITH MALE BANANA PLUG
39"
46"
4 LENGTHS, 14 GAUGE COPPER IN PARALLEL, SPIRAL WRAPPED AROUND FIBERGLASS SHAFT
HAMSTICK FIBER-GLASS BOTTOM, WITH COVER AND WINDINGS REMOVED
.375 × 24 MALE THREAD
2-17-2001 N1LO


1/2" Riggid Copper Pipe
Cap ends with 1/2" caps
and solder.
Designed & Drawn by BucK4ABT
Use extreme caution when
soldering using open-flame torches.
OBSERVE ALL SAFETY PRECAUTIONS
ASSOCIATED WITH GAS TORCHES.
Always solder out doors and away
from flamable or combustibles. BucK4ABT
ADJUST SCREW
FOR LOWEST
VSWR.
3.0" center to center.
58.0 "
1" X 6-32
BRASS SCREW
6-32 BRASS
NUT "LOCK."
6-32 BRASS NUT
SOLDERED INSIDE
1/2" COPPER CAP.
BucK4ABT
Connect Coax
Center Here!
19.0"
2-3/4"
Connect
Shield Here!
20 INCHES
APPROX.
SO-239
BUXCOMM
"V BALUN"
2 inch Stainless Steel
Hose Clamps
BucK4ABT
Designed & Drawn
by BucK4ABT
(C) 1985
Two Meter J-POLE WITH VSWR ADJUSTMENT.


ASTRA
5/8
ANTENNA
PVC End Cap
1/2 Inci
ALOY Hollow 1/2 Inci
20 Inci
Kayu Penyapu 5 Inci
Di Tebuk Lubang
3/4 Inci Pemisah Antenna 2 Tiang Aloy
ALOY Hollow 1/2 Inci
52 Inci
Cable RG58
10 Inci
ALOY Hollow 1/4 Inci
28 Inci
Di Bengkok 45% 24 Inci
Panjang 10 Inci Dari Tiang
Utama
Hose Clip
Copping Board (Papan Potong Sayur)
Drill Lubang Ikut Size Tiang ALOY
PVC 1/2 Inci
Bahan
1 Batang - Aloy 1/2" - 52 Inci
1 Batang - Aloy 1/2" - 20 Inci
4 Batang - Aloy 1/4" - 28 Inci
2 Unit Hose Clip
1 Batang - Kayu Penyapu - 5 Inci
2 Unit Copping Board
1 Batang PVC 1/2" - 24 Inci
1 Unit PVC End Cap 1/2"
SWR METER@SX100025 Watt
144.000 - 1:3
145.000 - 1:2
146.000 - 1:1
147.000 - 1:2
148.000 - 1:3



5/8 vertical groundplane antenna for 50 MHz, By ON1DHT

Omnidirectional pattern
4.7dBi gain
2 MHz Bandwidth at 1.5 SWR
1:1 SWR on center frequency
50 OHm impedance
200 W max power

± 90cm T3
160cm T2
160cm T1
4x100cm
R1...4
principle
T1
Isolator
L1
coax
L2
R1 & 2
R3 & 4

T3 = 10mm Ø (tune for best SWR by sliding it in or out T2)
T2 = 15mm Ø
T3 = 20mm Ø
R1...4= four tubes of 1 meter or 2 tubes of 2 meter crossed Ø 8mm or Ø 10mm
All alu tubing

L1 = 7 t 0.8mm, coil Ø 10mm
L2 = 5 t 0.8mm, coil Ø 10mm



3 el yagi for 28/21 MHz

Director
243 cm
31 cm D
173 cm B
180 cm A
110 cm
244 cm
173 cm D
180 cm C
110 cm
254 cm
Radiator
31,5 cm D
174 cm B
200 cm A
Antenna element
Traps
X mm
Gamma matching
25 pF
25 pF
55 cm (28 MHz)
105 cm (21 MHz)
224 cm
Al-angle
8 mm Plexiglass
Tube bracket
55 mm VP-tube (37 mm diam)
20 cm
270 cm
Reflector
33,5 cm D
180 cm B
220 cm A

A = 20 * 1,5 mm
B = 16 * 1,5 mm
C = 13 * 1 mm
D = 10 * 1 mm

Trap X = direktor = 46 mm (29,6 MHz)
Trap X = radiator = 41 mm (28,3 MHz)
Trap X = reflektor = 37 mm(26,6 MHz)

Plastic box with 2 coax connectors attached to the al-angle



BUXCOMM Model 802134

Tye-Tail
Windom Short Element
Strain Relief Eyebolts
Suspension Eyebolt
Windom Long Element
Tye-Tail
BUXCOMM
AWG14 stranded/insulated copper
AWG14 stranded/insulated copper
End Insulator
End Insulator
Ultra Wideband Vestigial BALUN
Antenna Terminal -- Minus BLACK
Antenna Terminal + Plus,RED
Model BCIMM41 BALUN
BUXCOMM MasterMatch Balun (sealed enclosure) (Internally doped with EPOXY)
BucK4ABT
SO239

BUXCOMM BALUN Integrated BALUN & Center Insulator, housed in UV resistant case.
* Indicates Heat-Shrink and sealed terminal(s).
** Use CS104 (Coax Seal) on all terminals & connections.


W3DZZ
Isolador central e laterais de PVC com 5cm de largura
Fio 8 ou 10 Flexível ou rígido
Bobina
Bobina
6,70
10,06
PVC
2,5 polegadas
Distância entre o isolador central e a bobina = 10,06m
Distância entre a bobina e isolador lateral = 6,70m
Coaxial 75ohms
60cm
PY1FW / PU1LHP
Tenório / Bira

Bobina: PVC de 2,5" (polegadas) de diâmetro e aprox. 60cm de largura.

Fio 12 (1mm) encapado
13 voltas completas

Capacitor da bobina: 56PF ou fazer com cabo coaxial da seguinte forma: Cabo coaxial **RG213** (grosso) com **60cm** de comprimento. Descascar uma das pontas e ligar a malha de um lado da bobina e o vivo do outro lado da bobina. Importante: o cabo deve ficar dentro do cano de PVC da bobina.

Se você não possuir cabo coaxial de 75 ohms, utilize fio paralelo número 8, usado para extensão de tomadas de rede elétrica, enrole bem para que ele fique trançado e pronto! Você terá uma linha de 75 ohms perfeita para ligar a antena no rádio.

Antena multibanda de 10 até 80 metros


15.55 m
15.55 m
ALAMBRE DE COBRE No 12
AISLADOR CERAMICO
CABLE BIFILAR 300 OHMS
10.35 m
ANTENA MULTIBANDA
G5RV
(80,40,20,15,10 Mts)
XE1JHJ
Dibujo : Arturo G.
CABLE COAXIAL 50 OHMS
AL TRANSMISOR


20-40-80 meter Dipole Antenna
1,47 m
4,80 m
6,30 m
6,30 m
4,80 m
1,47 m
L1
L2
L3
L4
1:1 BALUN
TA3AHS
TA AMATOR TELSİZ
RG 213

L1-L4 : 20 mm Plastik karkasa, 1mm telden 145 spir.

L2-L3 : 20 mm Plastik karasa, 1 mm telden 50 spir.


The 1/4 Wave Ground Plane
Any Mobile Whip 102" is best but even a 4' helical will work!
Old Mobile antenna bracket
Four pieces of wire 102" long
Masting
Coax
Nylon Cord, Rope or heavy Fishing Line
Masting
102" Metal Rod or Tubing
Plexiglass, PC Board, Heavy Nylon or even Wood may be used a mounting bracket.
Just No Metal!
Four pieces of wire 102" long
Coax
Nylon cord, Rope or very heavy fishing line


L2
L3
Angle at "C" and "D" should not exceed 90 degrees.
C
D
4:1 BUX 4:1 BALUN
L1
L4
"A"
"B"
12 ft or more above ground.
12 ft or more above ground.
ground or other surfaces.
ground or other surfaces.
RG8X
RG=50 ohm coaxial cable

EXAMPLE: BUX COMM Model 802136 WINDOM Total length: L1, L2, L3, & L4 = 136 ft

L1 & L4 can be any length, *See NOTE: >* but ends at "A" & "B" must be at least 12 feet above ground or other surface. All parts of: L1, L2, L3, & L4 should not come in contact with any object or vegetation.

L1 or L4 can be up to 8 ft. long. However, their lengths must not extend the total length of 136 feet for: L1, L2, L3, and L4 !

BUX COMM, "WINDOM" or off-center fed flat-top wire antenna installed on property with limited space.

Ten HAM band coverage without antenna tuner.

This configuration performs as well with our 160 - 6 meter version, (model 166260). Our BUX WINDOM can also be installed as an "Inverted Vee" but each end must be at least 12 feet above ground or other surface.


impedanse transformer
A
B
A
0.25λ
E
F
F
a
b
c
a+b+c= 1λ
brass
B
C
A
B
B
dielectric
A
E
F
E
short circuiter . brass
insulator
mast
cable
length compensation


Refletor
110 cm.
Emissor
Diretor 1
92 cm.
Diretor 2
92 cm.
Diretor 3
92 cm.
Direção
20 cm.
34 cm.
34 cm.
21 cm.

Antena direcional 146 mhz de 5 elementos VHF


balun relacion 1:1
entrada y salida de la bobina
cable de luz de 2´5mm
10´20
bigote para ajustar 40m
50Cms
10Cms
tubo pvc para bobina
75mm exterior
120mm largo
37 espiras cable esmaltado
de 1´5 o 1´75 de bobinar
bobina
1´50
50Cms
50Cms
bigote para ajustar 80m
aislador
cable sin alimentacion
tubo pvc 75mm exterior y 120mm largo
bobina con 37vueltas sin separacion
bigote para 80m
esquema de mi dipolo
EC5AHM/EB5DZO
SE PUEDEN PONER BIGOTES
PARA OTRAS BANDAS
bigote para ajustar 40m
en estos 2 puntos la bobina empieza y acaba
con dos terminales soldados y cogidos al
tornillo que une dipolo,bobina y bigote
para 40m


Atenuación y blindaje de un coaxial
señal de interferencia externa
Segunda cubierta cobre o aluminio
Material aislante entre vivo y malla
Forro externo de protección
Malla del coaxial
Interferencia atenuada
conductor externo de blindaje
Conductor central del coaxial
xe3rlr


ANTENA JAULA
40 Metros
40 cm
CE5MSW
VICTOR HUGO
9 metros
18 cms
9 metros
9 metros
18 cms
9 metros
40 cm
40 cm
40 cm
40 cm
cola ajuste
RG 8 ó RG58
cola ajuste

MATERIALES

Cable Nº 12
Trozo de PVC Aislante Central
Cable coaxial RG 8 ó RG 58
10 escalerillas Plástico 20 x 2 cms.

El autor y creador de esta antena Victor Hugo CE5MSW, la usa con excelentes resultados de recepción y transmisión.
El es moderador los días Lunes en la Rueda de la Amistad, 7.168 y vive en la comuna de Chiguayante.

Dibujo y Publicación: XQ5CL (Concepción)


Antena Subterranea
Tubo PVC o manga plástica
Alambre de cobre o varilla
Alambre de cobre o varilla
Bobinas de carga 3 iguales
alambre de cobre o varilla
Cinta de 300 ohms
Ver texto y fotos para mas detalles


Tubo de aluminio
Tubo de aluminio
Tubo de aluminio
XE3RLR
tramo A
TRAMPA T1
Tramo B
TRAMPA T2
Tramo C
2.59 mts largo
0.519 mts
0.799 mts de largo
AISLANTE CENTRAL DEL BRAZO LADO DERECHO
C
Capacitor
Tubo de aluminio
material aislante
Tubo de aluminio
punto de conexión
punto de conexión
L
bobina

DETALLE PARA LA CONSTRUCCIÓN DE LAS TRAMPAS T 1 Y T 2

XE3RLR Javier


20-40-80 meter Dipole Antenna
1,47 m
4,80 m
6,30 m
6,30 m
4,80 m
1,47 m
L1
L2
1:1 BALUN
L3
L4
OR TELSİZ
RG 213
L1-L4 : 20 mm Plastik karkasa, 1mm telden 145 spir.
L2-L3 : 20 mm Plastik karasa, 1 mm telden 50 spir.


Dipolo rígido tribanda 10, 15 y 20 m
C
C
Trampa 2
B
Trampa 2
B
XE3RLR
Trampa 1
Trampa 1
A
A
90°
Abrazaderas aisladas
aisladores de neupremo
brazos de antena
punto de alimentación
Placa de aluminio de 1/4"
Balun transformador de impedancias
Mástil para elevar antena
coaxial 50 ohms


SO 239 – Presa da pannello
Stilo telescopico da 55 cm
Stilo telescopico da 55 cm
Dipolo
Vite
Vite
Supporto isolante
P
a
l
o
RTX
Bobina composta da tre spire serrate di filo di rame smaltato con un diametro di 1,2 mm avvolte su un diametro di 1,7 cm


2.28m
2.57m
2.57m
2.28m
Balun
40mm dia
160mm
50 ohm
Balanced
Balun
GM4JMU
Shortened
Dipole
40mm
Ferrite
Toroid
Unbalanced


This inner connects to this outer
inside the tube
Outer
Inner


lg
isolateur
e
drisse
entretoise
court-circuit
ligne d'alimentation
300 Ω


lg
e
d
Court-circuit
ligne d'alimentation
300 Ω







Elemento exitado lado derecho


punto de alimentación del balun
Abrazaderas "u" 1 1/2"
Tubo aluminio de 1"
Tubo 7/8" 22 mm
Trampa 1
aislante 7/8"
Tubo 7/8" 22 mm
Tubo aluminio 3/4"
Trampa 2
aislante 7/8"
Tubo 7/8" 22 mm
Tubo aluminio 3/4"
Tubo aluminio 5/8"
Manguera aislante 1 1/4"
A
25 cms
7cm
20 cms
11.9 cms
20 cms
14 cm
30 cms
23 cms
C
Tapón hule
26.9 cms
2.34 mts
B

Elemento exitado lado izquierdo


Tubo aluminio 5/8"
Tubo 7/8" 22 mm
Tubo aluminio 3/4"
Trampa 2
aislante 7/8"
Tubo aluminio 3/4"
B
Trampa 1
aislante 7/8"
Tubo 7/8" 22 mm
Tubo aluminio de 1"
punto de alimentación del balun
Abrazaderas "u" 1 1/2"
Tapón hule
C
Tubo 7/8" 22 mm
Tubo 7/8" 22 mm
A
Manguera aislante 1 1/4"
26.9 cms
23 cms
30 cms
14 cm
20 cms
11.9 cms
20 cms
7cm
25 cms
2.34 mts

XE3RLR Javier

Dipolo rotativo 10, 15 y 20 mts.


UPPER ELEMENT
48-3/4"
9"
2"
INSULATOR
1/2"
PHASING STUB
LOWER ELEMENT
MATCHING STUB
1-1/2"
67-3/4"
19"
2-3/4"
3"
8"
CLAMP TO MAST


Irradiante
Director
Reflector
y
x
s
s
Reflector
Irradiante
Director
z
x
S
S
Longitudes
Director = Irradiante - 5%
Irradiante = 142,5 / Frecuencia (Mhz)
Reflector = Irradiante + 5%
S = 0,2 * Longitud de Onda
Diagrama de radiación
Antena Yagi de 3 elementos


DIAGRAMA BÁSICO DO ACOPLAMENTO "GAMMA MATCH"
boom
34,4 cm
"Curto circuito" ajustável
Tubo de alumínio
Conector
BOOM


6cm
120cm
5cm
80cm
Feed loop
Nylon chord
4cm
Cable connector
1800mm booms
50Ω coax feeder
Note: *1 See text
Nylon chord
5cm
SM0VPO
25pf capacitor (Jackson 805)
80 meter Frame Antenna


1/2" Riggid Copper Pipe
Cap ends with 1/2" caps
and solder.
Designed & Drawn by BucK4ABT
Use extreme caution when
soldering using open-flame torches.
OBSERVE ALL SAFETY PRECAUTIONS
ASSOCIATED WITH GAS TORCHES.
Always solder out doors and away
from flamable or combustibles. BucK4ABT

ADJUST SCREW FOR LOWEST VSWR.
3.0" center to center.
1" X 6-32 BRASS SCREW
6-32 BRASS NUT "LOCK."
6-32 BRASS NUT SOLDERED INSIDE 1/2" COPPER CAP.
BucK4ABT
58.0 "
19.0"
2-3/4"
Connect Coax Center Here!
Connect Shield Here!
BUXCOMM "V BALUN"
SO-239
20 INCHES APPROX.
2 inch Stainless Steel Hose Clamps
BucK4ABT
Designed & Drawn by BucK4ABT (C) 1985
Two Meter J-POLE WITH VSWR ADJUSTMENT.


102"
102"
NYLON CORD OR ROPE
SHIELD
CENTER
NYLON CORD OR ROPE
Plastic, Plexiglass or PC board Insulator
50 OHM OR 75 OHM COAX


15,55 m
15,55 m
ALAMBRE DE COBRE No 12
AISLADOR CERAMICO
CABLE BIFILAR 300 OHMS
ANTENA MULTIBANDA
G5RV
(80,40,20,15,10 Mts)
10,35 m
XE1JHJ
Dibujo : Arturo G.
CABLE COAXIAL 50 OHMS
AL TRANSMISOR


The 1/4 Wave Ground Plane
Any Mobile Whip 102" is best but even a 4' helical will work!
Old Mobile antenna bracket
Four pieces of wire 102" long
Masting
Nylon Cord, Rope or heavy Fishing Line
Coax
Masting
102" Metal Rod or Tubing
Plexiglass, PC Board, Heavy Nylon or even Wood may be used a mounting bracket.
Just No Metal!
Four pieces of wire 102" long
Coax
Nylon cord, Rope or very heavy fishing line


Antena T2FD
R
L
A
6:1
50 Ohm Rx/Tx



Figure 1.12. Broadband monopole antenna at WWV.


41'
3 &1/2" Heavy Duty
Light-weight Insulator.
End Insulator
3 &1/2" Heavy Duty
Light-weight Insulator.
AWG14
stranded/insulated
copper
A1
Suspension
Eyebolt
A2
AWG14
stranded/insulated
copper
BUXCOMM (C) 1999
22" At Tye-Tails
BUXCOMM
HF, 3 to 30 MHz
"PHAN-DIPOLE"
PowerRated @ 1000 watts SSB
BUXCOMM
BUXCOMM
ULTRA
Wide Band
PhanDipole
BALUN
1.56:1
1.5 kW
BucK4ABT
16" MOL
At Element Ends
AWG14
stranded/insulated
copper
B1
Solid Brass
Terminals
Output to antenna
Solid Brass
Terminals
Output to antenna
B2
AWG14
stranded/insulated
copper
3 &1/2" Heavy Duty
Light-weight Insulator.
PL259
50 ohm Coax
RF INPUT.
SO239
3 - 1/2" Heavy Duty
Light-weight Insulator.
End Insulator
PHAN-DIPOLE Mounted Vertically >
< Support Mast.<
> Support Mast. >
3/16" Dacron Rope
"A1"
Insulator
"B1"
Coax
Input
Special NVISX
Antenna BALUN
and common-point
assembly.
"A2"
"B2"
Insulator
ALL END INSULATORS SHOULD
BE AT LEAST 8 FT ABOVE GROUND.
Insulator
Center support mast 12 to 14 ft
3/16" Dacron Rope
3/16" Dacron Rope
ALL END INSULATORS SHOULD
BE AT LEAST 8 FT ABOVE GROUND
Insulator
3/16" Dacron Rope
(C) G E Rogers Sr 1991

PHAN-DIPOLE Mounted Horizontal (NVIS Configuration)

Although the BUXCOMM Phan-Dipole is designed for vertical installation, it may also be mounted horizontally and used as an "NVIS" antenna. In either installation, the Phan-Dipole performs well as a compact HAM station or MARS antenna.

Center support mast may be made of two, 6 ft sections of Sked 40 PVC. Use 2" sked 40 PVC couplings to join two, 6 ft sections of Sked 40 PVC.

Tye-down stakes, Dacron rope, and center support mast, not included. Power Rating = 500 watts.


A - 1 / 4 Wavelength of 75 Ohm Coax
B - 1 / 4 Wavelength of 50 Ohm Coax
Barrel Connector
B
To Horizontal Polarization (Lag)
A
To Vertical Polarization (lead)
A
Female "T" Connector
50 Ohm Coax To Radio
Not to scale


2.28m
2.57m
2.57m
2.28m
Balun
40mm dia
160mm
50 ohm
GM4JMU
Shortened
Dipole
Balanced
Balun
40mm
Ferrite
Toroid
Unbalanced


73 Ohm
6.98 dBi
8.92 dBi
112
9.17 dBi
130
9.32 dBi
145
9.33 dBi
≈150
insulators
mast


73 Ohm
6.98 dBi
8.92 dBi
112
9.17 dBi
130
9.32 dBi
145
9.33 dBi
≈150
insulators
mast




ALE - AUTOTUNER V-FAN-DIPOLE
DIPOLE WIRES #16 - #12 STRANDED
A
B
C
NOT TO SCALE
SEE DESIGN CHART FOR LENGTHS
A
B
C
DIPOLE SUPPORT ROPES
CENTER INSULATOR
AUTOTUNER MOUNTING HEIGHT = 8FT OR HIGHER
#6-#10 INSULATED WIRE TO HOT LUG OF TUNER
#6-#10 INSULATED WIRE TO GROUND LUG OF TUNER
WATERPROOF ENCLOSURE
GROUND LUG OF TUNER
COPPER GROUND STRAP
SUPPORT POLE, WALL OR FENCE
FERRITE CLAMP MULTIPLE WRAPS FOR CONTROL AND DC CABLE
SAFETY GROUND ROD
© 2007 HFLINK
1:1 CURRENT BALUN IN COAX CABLE
CONTROL AND COAX

AUTOTUNER FAN DIPOLE DESIGN CHART

LOWEST FREQ		1.8MHZ	3.5MHZ
DIPOLE LEG LENGTHS:	A=	98FT	49FT
	B=	59FT	29FT
	C=	38FT	14FT



Multi-Band Mystery Antenna

(it has 6 major lobes on 20 meters)

Design By John P. Basilotto, W5GI

During 2003 Field Day a local club member brought this article in from CQ magazine describing this antenna. The article states it has 6 major lobes on 20 meters, and may have some gain on one or two of the bands. The following chart shows how this antenna loads on each of the bands.

Freq.	SWR	R	X
3.550	1.5	42	34
3.650	2.5	98	61
3.850	3.5	48	61
3.950	4	22	36
7.000	1.9	95	12
7.200	3	22	25
10.100	5.2	22	50
14.000	1.7	37	19
14.200	1.5	42	18
14.300	1.6	43	22
18.150	1.9	93	13
21.300	2.9	120	46
24.900	1.9	35	23
28.350	1.8	33	20
29.500	2.6	53	55
50.110	2.3	51	37
52.500	1.2	57	7

16'-6"
16'-6"
16'-6"
16'-6"
16'-6"
16'-6"
450 ohm ladder line
31 ft 10 in
RG-213 or equivalent
50 ohm coax any length



0.5 λ
0.25 λ
0.25λ
cable
The balancing


ELEVATION
90°
80°
70°
60°
50°
40°
30°
20°
10°
Sur
Este
Oeste
Norte
AZIMUT
90°
100°
110°
120°
130°
140°
150°
160°
170°
190°
200°
210°
220°
230°
240°
250°
260°
270°



144 MHz - 6 Elem. nach DG2KCK - DL6WU Design

Gewinn ü. Dipol: 9,4db - Vor/Rück >19db
Öffnungswinkel: Hor. 45,6° - Ver. 54°

Längen in mm			Abstände in mm
Boom 25 x 25			
Reflektor	R -	1032	AR - 390
Strahler	S -	980	--
Direktoren	D1 -	935	A1 - 165
	D2 -	930	A2 - 375
	D3 -	925	A3 - 450
	D4 -	915	A4 - 525

Ref
1032
Dipol
980
Dir 1
935
Dir 2
930
Dir 3
925
Dir 4
915
A_R
A_1
A_2
A_3
A_4
0
390
165
375
450
525
1905
a)
Lambda /2 x V
980
10
40
D < 0,05 Lambda
b)
980
12
c)
Lambda /2 x V
960
Konni - Dipol
145 MHz
10
40
D < 0,05 Lambda

Boom 1935 x 25 x 25mm
Elemente 10mm
DG2KCK13082012135932

a) - Aufbauschema
b) - Faltdipol (Detailzeichnung)
c) - gestreckter Dipol (Detailzeichnung)
d) - Konni - Dipol - Boom 20 x 20
Elemente in der Länge 5mm kürzen

d) - Konni - Dipol Boom 20 x 20

Frequenzbereich	Öffnungswinkel h/v
144 - 146 MHz	45,6° / 54°
Anzahl Elemente 6	Gewinn - 9,4 dBd
	V/R - >19 dB
Länge 193,5 cm	Gewicht 1,2 kg
Windlast bei 120 km/h-66 N	


G3JVL 5/8
6M Vertical
1/2" Dia
17.7"
22.04"
42.9"
49.20"
5/8" Dia
3/4" Dia
45.27"
49.20"
7/8" Dia
49.2"
Overall length
aprox 155 inches
Detail of bottom plate
and ground-plane
Radials aprox
49.2 inches
Aluminum
Plate
Turned nylon or
similar insulator
10-turns 16swg - one
end connected to tube,
the other grounded.
Tap 5-turns from
grounded
end
Nylon or
simular
insulator coil
form attached
to bracket
Tag
PL259 socket


VERTICAL 3/8
40m Band
15,55 m WIRE 2,5 mm
Radial 5,07 m
RG 58



147 MHz 4 Element Quad

Best Method
All radials are center notched to fit together at the center.
Drill 1/8" hole
Solder ends here
Reflector
1X1" wood
Screws
Main Boom
2X2" wood boom
Driven Element
Director 1
10 db gain less than 4 feet!
Hole Spacing
Element Spacing
Driven Element
Solder Coax leads to wire elements
Caution: do not allow coax to short!
©2010 Bill Smith N6MQS all rights reserved www.rfsearch.com
artSci
Where ART and Science work for you

	Wire Length	Hole Spacing	Element Spacing
Reflector	86-1/8"	30-1/8"	20-1/4"
Driven Element	81"	28-5/16"	12-5/16"
Director 1	77-13/16"	27-1/4"	12-7/8"
Director 2	74"	25-7/8"	

Hints: After beam is assembled, find the balance point and drill holes for U bracket.

Horizontal or Vertical polarization is changed by feeding the driven element from side or bottom.
Use side feed for Vertical polarization!

The center conductor of the coax will travel around the driven element wire and short to the coax shield!! All Quads do this.

Parts List

1 - 2" X 2" X 48" wood
8 - 1" X 1" X 36" wood
1 - 2" U clamp with nuts and washers
8 - 1.5" wood screws
30 feet of 14 gauge wire
Coax cable



K1LZ 160 Meter Delta Loop Antenna

By K3LP – 10/23/08

Total Length: $\frac{1005}{f\ (mhz.)} = \frac{1005}{1.830}$

Total Length: 540'

1/3λ = 540 x 0.33 = 180'

1/4λ = 540 x 0.25 = 135'

0.08λ = 540 x 0.08 = 43.2' or 43' 2 ¼"

Helium Ballon
1/3λ
180'
1/4λ
135'
1/4λ RG-11, 75 Ohm Coax, 135'
0.08λ
Connect to 50 ohm coax (RG-8, RG-58) via Barrel Connector
1/3λ
180'
Support Rope between two towers
120' above ground (approx.)
1
100' Tower on hill
150' Tower on hill


SUPPORT ROPES
SUPPORT ROPES
RANDOM DELTA LOOP
GREAT FOR DX !
450 OHM BALANCED LINE
ANY LENGTH NEEDED
4:1 BALUN
COAX - 25' OR SHORTER
KC8AON 2001

CIRCUMFERENCE	COVERAGE
75'	20 METERS & UP
150'	40 METERS & UP
280'	80 METERS & UP

THIS ANTENNA MUST BE USED WITH A TUNER ! IF YOU HAVE A TRUE BALANCED TUNER, YOU CAN ELIMINATE THE 4:1 BALUN AND RUN BALANCED LINE ALL THE WAY TO THE TUNER.

THE RANDOM DELTA LOOP IS A DIRECTIONAL ANTENNA WITH RADIATION BROADSIDE TO THE LOOP, ORIENT FOR DESIRED DIRECTION OF COVERAGE

WORKS WELL AT LOW HEIGHTS !

CAN BE INSTALLED HORIZONTAL FOR OMNI DIRECTIONAL COVERAGE OR MOUNTED LOW AND HORIZONTAL FOR NVIS WORK


The WH2T Mini Super Loop Antenna
INSULATORS
Not Drawn To Scale
49'9"
49'9"
29' 10" Ladder Line
String
59 ft
59 ft
Graphic by Dr.Ace - WH2T
BALUN
50 Ohm Coax Any Needed Length


A
B
C
B
A
DIRECTOR
3000
IRRADIANTE
2340
REFLECTOR

DIRECTOR	A	B	C	TOTAL
FONIA	840	300	5000	7280
CW	840	300	5160	7440
IRRADIANTE				
FONIA	940	300	5240	7720
CW	950	300	5410	7910
REFLECTOR				
FONIA	850	300	5440	7740
CW	850	300	5690	7990

DETALLE DEL ACOPLADOR: ESTÁ COMPUESTO POR 2 RAMAS CENTRALES SIN MALLA DE CABLE RG213



EL ENCAPSULADO CENTRAL ES DE MATERIAL AISLANTE Y LLEVA UN CONECTOR HEMBRA S0239
SE RECOMIENDA QUE EL CABLE DE ALIMENTACIÓN EN EL EXTREMO DE CONEXIÓN, TENGA UN BALUM
COMPUESTO POR 4 ESPIRAS SIN ESPACIAR DEL MISMO CABLE SIN NUCLEO Y 100 MM DE DIÁMETRO
PRECINTADO PARA MANTENER LA FORMA, TODO EL CONJUNTO SE AMARRA AL BOOM.

NOTA: TODAS LAS MEDIDAS ESTÁN EN MILÍMETROS

MULTIBAND RANDOM WIRE UNUN (UNBALANCED TO UNBALANCED)
FOR USE WITH RIGS WITH BUILT IN AUTOTUNERS


ANTENNA
GROUND CONNECTION
SHORT COAX TO CONNECT UNUN
TO SO-239 CONNECTOR
SO-239, 50 OHM
TO RADIO
10 BIFILAR TURNS ON FT 140 - 61 TOROID

MOUNT IN A WEATHERPROOF
PLASTIC ENCLOSURE


Vertical Delta Loop with Load Coils
support rope
coil 1
coil 2
support rope
Copyright © 2011 Paul Weise
Guanella 1:3 Balun 150 Ohm
Amidon FT 140-43
Amidon FT 140-43
Balun 1:3
TRX
TRX

Two coils in the upper corners of the Inverted Loop.
These points were chosen for mechanical reasons.
I put the antenna wire on PVC-tubes, and tried.
One coil has 19 µH, the other 164 µH for 1.800 MHz


110 cm.
92 cm.
92 cm.
92 cm.
20 cm.
34 cm.
34 cm.
21 cm.


2 ELEMEN YAGI BOOM PENDEK
40m
Total length 20,40 m
25 cm
1.1/2"
1.1/4"
1.1/8"
1"
7/8"
3/4"
1/2"
3/8"
150 cm
B
DE
S = 2,5 m
1.1/2"
1.1/4"
1.1/8"
1"
7/8"
3/4"
1/2"
3/8"
D
FB
by yd0lou



ANTENNE YAGI / 4 EL

4565
Directeur 2
3110
5115
Directeur 1
1500
5290
Dipôle
450
80
620
1000
5555
Distance du gamma à 80mm du dipôle
Réflecteur

Type YAGI / 4EL – Bande passante 400Khz (27.4– 27.8) avec 1.6 ros aux ext.
Longueur du Boom 5.80m section 50 – éléments centraux 25/21 – Extr.. 20/16
Gain in free space 7.00 Db (F/B 45dB)

DETAIL DU GAMMA MATCH

1 Tube diamètre 20mm longueur 370mm
1 Tube diamètre 10mm longueur 480mm
1 Tube PVC 16x10x340 Monter à l'intérieur du tube de 20x370
Position de la patte en alu 450mm (contact réglage / CR)
Position de la tige de 10 sortie 250mm par rapport au tube de D20x370
Longueur total du gamma LT: 620mm et distance par rapport au dipole 80mm
Patte 1 support gamma équipé d'une PL259
Patte 2 de support et de contact CR / 450mm par rapport au centre de la PL259

450mm / CR
Boom D50
1
DIPOLE : 5290mm
2
PATTE EN ALU
Tube D20 - L370
Tube isolant 16x10x250
PATTE EN ALU
80 mm
Tube D10 – L480
LT 620
PL 259
L 250 mm



3·5MHz loop skywire - 'λ' = 272ft
7MHz loop skywire - 'λ' = 142ft
λ/4
λ/4
λ/4
λ/4
Open Wire feed line
Height 40ft above ground (approx)
Shack



HF 20M/15M/10M DELTA LOOP ANTENA

	Panjang elemen	75Ohm
10M Band (28.500Mhz)	3 X 3.58 m	1.78 m
15M Band (21.200Mhz)	3 X 4.82 m	2.20 m
20M Band (14.200Mhz)	3 X 7.19 m	3.32 m

75 Ohm Coaxcial
50 Ohm Any Length To TRX



Direction of Forward Gain
Director
2A 14.10m
1 mm Insulated Wire
B
B
F
F 2.35m
H 8.52m
L
Support Lines
C
C 1.93m
A
A 7.05m
Radiator
Radiator
D
D 0.96m
Fishing Rod
G
G 2.35m
E
E 3.38m
50 Ω Coax
2A
Reflector
1 mm Insulated Wire
QS1003-Hedman01

MHz	A	B	C	D	E	F	G	H	L
28	5' 11.6"	1' 10.8"	1' 6.9"	0' 9.4"	2' 11.8"	1' 10.8"	2' 8.3"	6' 11.4"	6' 11.0"
21	7' 11.6"	2' 6.3"	2' 1.2"	1' 0.6"	3' 11.6"	2' 6.3"	3' 6.9"	9' 3.0"	9' 2.6"
14	11' 11.3"	3' 9.7"	3' 1.8"	1' 6.9"	5' 11.2"	3' 9.7"	5' 4.6"	13' 10.9"	13' 9.7"
7.1	23' 10.5"	7' 7.3"	6' 3.6"	3' 1.8"	11' 10.5"	7' 7.3"	10' 9.1"	27' 9.8"	27' 7.4"
	7.05m	**2.34m**	**1.92m**	**0.98**	**3.38m**	**2.34m**	**3.32m**	**8.50m**	**8.44m**


Antena direccional de 6 elementos para os 11 metros
QRA: Rafael ESTAÇÃO: Rato - PX2Y2117 - Mococa-SP
4º diretor
2,15m
1,30m
3º diretor
2,26m
1,30m
2º diretor
2,38m
1,30m
1º diretor
2,51m
1,30m
irradiante
2,65m
1,20m
refletor
2,79m


5/8 wave 10 meter wire vertical
RADIATOR: 20.6 FEET (247.2")
CONNECT RADIATOR & CENTER CONDUCTOR OF COAX CAPACITOR TO TOP OF COIL HERE
1/2" PVC
SOLDER ALL CONNECTIONS
MATCHING COIL: 5 TURNS 1/4" COPPER TUBING 3" I.D. 3.5" LONG END TO END
CONNECT CENTER CONDUCTOR OF FEEDLINE AT 2 TURNS FROM BOTTOM OF MATCHING COIL
CONNECT BOTH COAX SHIELDS, BOTTOM OF MATCHING COIL & RADIALS TOGETHER
RADIALS: 103" EACH USE 2, 3 OR 4 RADIALS
COAX CAPACITOR: 7.5" LONG PIECE OF RG-8X DO NOT CONNECT BRAID & CENTER CONDUCTOR TOGETHER AT BOTTOM
FEEDLINE CHOKE: 10 TURNS OF COAX 3" DIAMETER
JUST HANG IT FROM A BRANCH


m = Feet (′) × .03048
104′
Nylon Rope
52′
12′
Nylon Rope
22′
50 - Ω Coaxial Cable to Station
75 - Ω RG - 59 Coaxial Cable 1/4 λ Transformer


ALE - AUTOTUNER INVERTED-V FAN DIPOLE
HOISTING PULLEY
CENTER INSULATOR
SEE DESIGN CHART
A
NOT TO SCALE
DIPOLE WIRES #16 - #12 STRANDED
A
B
C
C
B
DIPOLE SUPPORT ROPES
#6-#10 INSULATED WIRE TO HOT LUG OF TUNER
#6-#10 INSULATED WIRE TO GROUND LUG OF TUNER
AUTOTUNER
WATERPROOF ENCLOSURE
GROUND LUG OF TUNER
COPPER GROUND STRAP
FERRITE CLAMP MULTIPLE WRAPS FOR CONTROL AND DC CABLE
1:1 CURRENT BALUN IN COAX CABLE
SAFETY GROUND ROD
©2007 HFLINK
SUPPORT POLE OR TOWER

AUTOTUNER FAN DIPOLE DESIGN CHART

LOWEST FREQ		1.8MHZ	3.5MHZ
DIPOLE LEG LENGTHS:	A=	98FT	49FT
	B=	59FT	29FT
	C=	38FT	14FT


1.29 Meter
19.46Meter
8.57Meter
3.51Meter
19.46Meter
RG - 213
<--(Senterlederen åpen og isolert vekk)
9.6 Meter
2.5Kvadrat PN
15.94Meter
2.5Kvadrat PN
Målene er til avstemt frekvens 3.700Mhz
Antennen er bredbåndet og har nesten ingen swr på hele 80m båndet.
Alle sjøter må tettes med krympestrømpe så de er 100% sikre mot at vann ikke kan trenge inn i antennen.
T-konektor type UHF kan med fordel brukes i matepungtet !

80-Meter DX Special,
an antenna optimized for the phone portions of the 3.5-MHz band. The coax segment lengths total to one quarter-wavelength. The overall length is the same as that of a conventional inverted V dipole.


2 el sloping Delta loop for 28.3 MHz
4.0 m
3.54 m
3.77 m
4.0 m
Coax connected to radiator
Mast
4.0 m
3.54 m
Z = 150 ohm
3.77 m
4.0 m
From above
Support line 27 cm
1.74 m RG59 75 ohm coax
2.3 m
2.5 m
8 dBd F/B = 8 dB
2.82 m
2.82 m
From side
50 ohm coax
5 m
1 mm cu wire
4 fishing rod 2.82 m long
Mast
Support line


2 el yagi for 21, 24, 28 MHz

Trap	Freq MHz	Coil diam	Coax diam	Coax length	Coil length
A	28.25	40 mm	5 mm	51.9 cm	1.75 cm
B	24.95	40 mm	5 mm	57.2 cm	1.93 cm
C	27.6	40 mm	5 mm	52.8 cm	1.8 cm
D	24.2	40 mm	5 mm	58.4 cm	2 cm

Traps data using VE6YP Coaxial Trap Design

B
A
D
C
17.5 cm
7 cm
230 cm
4-5 dB
F/B 8-12
18 cm
11 cm
180 cm
Plastic box
230 cm
A
B
488 cm
Reflector
C
D
7 cm
17.5 cm
1 mm insulated wire
11 cm
18 cm
Fishing rod
50 ohm coax
Cable ties
Bent cable tie
Bent cable ties


D2
D1
DE
balun 1 turn 3" diam >
< 3"x3/16 Lucite plate
3 3/4"
< tip DE
< tip R
pole mount >
plastic tube spacer gap = 7/8" >
< coax RG 8X
5 3/4"
1/2" radius bend
R
<------------------------------ 29.0" center to center ------------------------------>

MOGI 145/432 Mhz antenna
6 db gain 15-20 db f/b

Dave Rank KO6RS
rank @cruzio.com

Ron Skelton W6WO
rskelton@surfnetusa.com

Moxon Rectangle 29"x10 9/16"

1/4" Al rod construction
D1 = 13 3/16" D2 = 12 1/16"

Element spacing from DE
D1 = 15/16" center to center
D2 = 3.5" "
R = 10 9/16" "

tip DE to center DE 3 3/4"
tip R to center R 5 3/4"

<< DE gap 1/8" at coax attachment point

For 445 Mhz operation shorten D1 and D2 by a ratio 432/445

Use 4-40 screws and solder lugs on tips of DE for coax attachment

Use black nylon wire clips to support 1/4" Al elements and rigid polyethylene tubing for spacer

Moxon Yagi Dual band Antenna Z=50 ohm SWR 1.1 on 432 and 144 Mhz


тапа
гумен диск
400
кожух
N=6.5 t
D=8 mm
L=25 mm
480
d=2.5 mm
N=6.5 t
D=8 mm
L=25 mm
480
N=4.75 t
D=10 mm
L=20 mm
d=1.5 mm
отвод - 3,2 нав
шпула
гайка М5
180
радиали
N-конектор
супорт

Фиг.1


45 cm
40 cm
34 cm
34 cm
103 cm
97 cm
95 cm
88,4 cm
87,4 cm
ELEVAÇÃO
3 - 5º
MASTRO
ANTENA DIRECIONAL YAGI 5 ELEMENTOS
VERSÃO - PAPA-LÉGUAS
RG 213 (15 CM)
Alu. 3/8 tube
15 cm de cano
GAMMA
SO239
2 cm
boom
ABRAÇADEIRA
ELEMENTO IRRADIANTE
SPECIFICATIONS
Gain 7,5 dB
Imp. - 50 Ohms
Polarisation - Ver / Hor
FRQ. - 144 a 148 MHz
PY2KR


DUAL – BAND VERTICAL
80m / 40m
Built on a Spiderbeam
18m Fiberglass Pole
18m
80m radiator identical to radiator of the 80m Vertical on 18m Pole.
1m
10.1m
40m radiator
Ground radials are required.
Feedpoint
12m



Fig. 3: Vertical polar pattern of the 70cm prototype

Fig. 2: Constructional details

Ends of uprights & cross strap flattened before securing with 4BA screws.
Most bracket cut & drilled to suit U clamps & aerial elements.
C
D
A
B
Feed connections (see text)
Plastic box
15
15
Insulator (ptfe) 80 long
10
10
1/4λ conductive shorting bar (see text)
Thread 0BA (or similar) mount with 'Nyloc' nuts or lock washers on both sides.
All elements 6 dia aluminium rod
Standard TV aerial U clamps
Mast
50Ω to Tx
WRM123

Section	70cm Band	2m Band
A. Half-wave elements	323mm ± 2mm	958mm ± 5mm
B. Elements and stub line spacing, centre-to-centre	19mm ± 2mm	25mm ± 5mm
C. Total stub length	390mm ± 2mm	1168mm ± 5mm
D. Shorting bar stub section, from junction of driven elements	Approx 175mm (see text)	Approx 469mm (see text)

All dims in mm.



Maria Maluca

Aufbauschema DC6NY
Dipl.Ing. Helmut OELLER

6560
1500
1500
1500
Ø16×1,5
Ø12×1
1500
1500
Ø20×1,5
40×40×1,5
1460
Ø16×1,5
Ø24×1,5
Ø20 PABC
1000
750
750
1000
1500
750
15
750
1500
Ø12×1
Ø20×1,5
7560


Boon 1.444 metres of plastic conduit
21.5 mm (3/4") pipe clip riveted to the boon
4 metre band Delta Loop
By GW7AAV
Total length of Wire 4.332 metres
Block connectors
66 cm of 75 ohm coax matching section
100 mm of 40 mm white PVC drain pipe
50 ohm coax to TX/RX


YU1QT design 40m square shape Yagi at S51EQ's home

Coax directly connected to X X points
Alluminium tubbing 40mm/2mm wall
X
X
DE
476cm
Isolating plate
241cm
Fine adjustment tails 40cm free falling
Rope
Boom alluminium tubbing 50/2,5mm wall
561cm
(RED) Cu PVC coated wire 1,5mm2 attached to poles with cable ties
294cm
600cm
REF
Alluminium tubbing 40mm/2mm wall
Fishing pole 6m long last element not used filled with PurPen x 4

Measurments on antenna with MFJ259B
"On the face of the place"

Frequency	R	X	SWR 1:
6,95	29	19	1,9
6,98	34	12	1,6
7,00	39	12	1,4
7,03	44	15	1,3
7,05	49	19	1,5
7,08	58	25	1,5
7,10	63	31	1,7
7,13	70	35	1,8
7,15	75	37	1,9
7,18	82	43	2,1
7,20	86	47	2,2

Measured with antenna 11m above ground!

Built by S51EQ S55M & S51KW
Questions abt ant to s55m@siol.com
Pictures at www.s55m.com picture gallery


l = 12м
l = 7 м
Изоляторы
L1
C2.1
C1.1
RX/TX
C1.2
L2
C2.2
мачта
мачта

Linear loaded antennas using 450 ohms ladder line


A cm
Ends shorted and soldered
B cm
1 mm insulated wire
450 ohms ladder line
50 ohms coax
3 mm plexiglass
450 ohms ladder line
6 cm
1 mm insulated wire
4,5 cm
50 ohms coax



QRG	7020 Khz	7390 KHz	14150 KHz	14950 KHz	13480 KHz	28250 KHz	30600 KHz	26185 KHz
A	701 cm	701 cm	345 cm	345 cm	345 cm	172 cm	172 cm	172 cm
B	331 cm	270 cm	151 cm	124 cm	195 cm	69 cm	51 cm	86 cm
Use	Radiator	Director	Radiator	Director	Reflector	Radiator	Director	Reflector



5/8 vertical groundplane antenna for 50 MHz, By ON1DHT

Omnidirectional pattern
4.7dBi gain
2 MHz Bandwidth at 1.5 SWR
1:1 SWR on center frequency
50 OHm impedance
200 W max power

± 90cm T3
160cm T2
160cm T1
4x100cm
R1...4
principle
T1
Isolator
L1
coax
L2
R1 & 2
R3 & 4

T3 = 10mm Ø (tune for best SWR by sliding it in or out T2)
T2 = 15mm Ø
T3 = 20mm Ø
R1...4= four tubes of 1 meter or 2 tubes of 2 meter crossed Ø 8mm or Ø 10mm
All alu tubing

L1 = 7t 0.8mm, coil Ø 10mm
L2 = 5t 0.8mm, coil Ø 10mm



Yagi 2 elementi 18.100MHz di IZ3GAK

136
170
200
170
136
Ø 2
Ø 2,5
Ø 3
A
radiatore
166
S
B
114
170
200
direttore
170
114

A = 812cm (radiatore) B = 768cm (direttore) S = 166cm (misure teoriche)

Gamma Match

Le misure indicate sono specificatamente per il mio gamma match
potrebbero essere differenti sipratutto se usate diametri e distanze diverse

Esattamente al centro
dell'elemento radiatore
12cm circa
Ø 1,8
138
Ponticello mobile
50Ω
a circa 104cm

MATERIALE:
- 2 x 200 Ø 3
- 4 x 200 Ø 2,5
- 4 x 160 Ø 2
- 1 x 138 Ø 1,8
- 1 x 180 Ø 3 boom



ARMADO GENERAL Y AJUSTE

1ª Paso: Ubicar en la tabla adjunta la medida del reflector (R), irradiante (I) y directores (D1 a Dn1)
2ª Paso: Tener en cuenta que en antenas de numerosa cantidad de elementos el BOOM viene en dos partes.
3ª Paso: Armar el BOOM colocando un caño suplementario de 5/8" entre los dos tubos principales y afirmarlos con tornillos.
4ª Paso: Ubicar los soportes de elementos y colocar los elementos con las medidas cortadas según tabla.
5ª Paso: Alinear los elementos sobre un mismo plano ajustando el tornillo allen del soporte.
6ª Paso: Corte el conductor a la medida (E).
7ª Paso: Armar el adaptador gama como indica la figura insertando el conductor en el caño asegurándolo con un termocontraible.
8ª Piso: Intercalar un medidor de ROE entre la antena y el equipo.
9ª Piso: Deslizar el puente gama de un lado a otro lentamente hasta obtener un ROE < 1.5: 1.

EIFFEL
ANTENAS

ANTENAS PARA COMUNICACIONES
FIJAS - MOVILES - HF - VHF - UHF - CELULARES

Planta Industrial, Adm. y Ventas: Gelly y Obes 2300 - (1618) - El Talar - Pdo. de Tigre - Bs. As.
(Alt. Panamericana Km 29) - Tel. 736-0854 - FAX: 736-0850

⑪



EIFFEL antenas

138/174 MHz

ANTENA FIJA DIRECCIONAL DE VHF SERIE LIVIANA

VHFDA/L

3-7dB, 5-9 dB, 7-11dB

921-975,5-1037,5 177,5

TABLA DE MEDIDAS EN MM.

3 ELEMENTOS				7-5 ELEMENTOS				MEDIDAS MM		
FREC	D1	I	R	Dn	D1	I	R	E	A	B
138	976	1018	1097	957	963	1029	1080	180	437	335
139	964	1009	1082	942	951	1017	1067	180	437	335
140	952	1000	1067	927	919	1005	1054	180	437	335
141	946	996	1059	919	933	1000	1046	180	437	335
142	940	991	1052	912	927	993	1041	180	437	335
143	930	983	1046	904	919	986	1036	180	437	335
144	925	978	1041	894	910	980	1028	180	437	335
145	917	973	1034	886	901	975	1021	175	437	335
146	909	965	1029	876	892	967	1016	175	437	335
147	901	960	1024	869	961	1008	1008	175	437	335
148	895	952	1016	864	876	955	1003	175	437	335
149	889	947	1011	853	868	947	995	175	437	335
150	883	940	1003	843	859	942	968	175	437	335
151	876	935	998	836	850	936	981	175	437	335
152	869	930	991	828	843	930	975	175	437	335
153	861	925	986	820	834	923	969	175	437	335
154	853	919	980	813	826	916	962	175	437	335
155	848	912	973	805	818	909	955	170	437	335
156	841	907	968	800	810	904	949	170	437	335
157	832	902	960	795	802	897	942	170	437	335
158	826	894	955	790	795	890	936	170	437	335
159	820	889	950	782	789	884	930	170	437	335
160	813	884	945	777	784	876	924	165	437	335
161	805	876	937	772	779	871	916	165	437	335
162	800	871	932	767	774	864	911	165	437	335
163	792	864	927	759	769	856	904	165	437	335
164	787	859	919	752	762	850	899	165	437	335
165	780	853	914	747	757	844	892	160	406	307
166	772	848	907	742	752	838	886	160	406	307
167	767	841	902	737	746	831	879	160	406	307
168	759	836	894	731	741	825	872	160	406	307
169	752	828	889	724	736	817	864	155	406	307
170	747	823	884	719	730	812	858	155	406	307
171	739	818	879	714	723	805	850	150	406	307
172	732	813	871	709	718	800	843	150	406	307
173	724	808	866	701	714	793	838	140	406	307
174	719	800	858	696	708	787	833	140	406	307

CARACTERISTICAS ELECTRICAS

Potencia máxima	200 Watts
Ganancia	9dBi para VHFD3/L 11dBi para VHFD5/L 13dBi para VHFD7/L
Ganancia 2 antenas en fase	12dBi para VHFD3/L 14dBi para VHFD5/L y 16dBi para VHFD7/L
Ancho de Banda	2% MHz
R.O.E. máximo	1,5: 1
Impedancia de entrada	50 Ohms
Polarización	Vertical u horizontal
Protección contra descarga	Irradiante a masa

CARACTERISTICAS MECANICAS

Conector	SO-239
Material provisto	Tubos de aluminio templado (Aleación 6162-T10 CAMEA)
Elementos	Tubo aluminio 1/4 (6,35 mm) x 1,5 mm de pared
Boom	Tubo de aluminio ø 3/4 (19.05 mm) x 1,5 mm de pared
Soportes	Función de aluminio inyectado, con grampas de acero galvanizado
Resistencia al viento	180 Km/h.
Peso aproximado	0,8 Kg para VHFD3 1,3 Kg para VHFD5 1,5 Kg para VHFD7

⑪

Página Principal

Suscribirse a: Entradas (Atom)

VIENTOS DOMINANTES



10sd156 EN TWITTER

Follow @10SD156

Entradas populares

- 
  ANTENA DOBLE BAZOOKA, DISEÑO CONSTRUCCION Y EFICIENCIA

  La antena dipolo es dicho por muchos como la antena perfecta para una frecuencia específica.En su mayor parte, esto es cierto. Si dese...
- Que hay dentro de una antena IMAX 2000?

  ¿Alguna vez te pregustaste que es lo que había dentro de la antena Imax 2000? Después de la disección y corte de la antena de 99 Antron y...
- 
  Balun y acopladores de antena (varios tipos)

  GAMMA MATCH 10,15 y 20Mts Este es un simple adaptador Gama, para antenas direccionales. Se adhiere al irradiante, una segunda varilla par...
-
  ASI SE ESCUCHA LA AURORA BOREAL.

  Ondas de Radio Naturales: Cuando las erupciones solares han alcanzado el campo magnético de la Tierra, los cielos en los dos polos se ilumin...
- BREVE HISTORIA DE UN BEST SELLER, LA ANTENA A-99

  Cuando su vecino de 16 años de edad, compra una vieja estación base CB

DX Fun Cluster

DXFUN WEB CLUSTER

Telnet connection (dxfun.com port:8000)
www.dxfuncluster.com

All bands | 6 | 10 | 12 | 15 | 17 | 20
30 | 40 | 60 | 80 | 160 | VHF | UHF

K7VIT	14269.0	**LO7H**	01:02
K1RV	7190.1	**6Y1LZ**	01:02
WR4F	7154.9	**EF3T**	01:02
RY0CAA	7081.0	**UA0C**	01:01
ZL2RX	21370.0	**A31MM**	01:02
BI4JCM	21245.0	**BI4IV**	01:01
LZ1KFM	3739.9	**SP6DZ**	01:01
WT9U	1846.0	**KF8PD**	01:01
K3IE	7229.0	**TM3R**	01:01
LA5PRA	14264.0	**JR1GSE**	01:01
KL7RA	21220.0	**BD7DM**	01:01
ON3MDS	3603.3	**OT5X**	01:00
K2AX	7181.9	**IR2L**	01:01
KL7RA	21231.9	**AH2R**	01:00
KA1IOR	3720.7	**K1KP**	01:00

Enlaces recomendados

- 4SD132 Mark
- Ciclo Solar
- Cluster.Dk
- CN2R Marruecos.
- CRAEG
- Delta Alfa Dx Arventure radio Club
- DXista Veracruzano
- Entre Ondas SWL
- FMRE Fed Mex de Radexperim. MX
- G.R.I. AlfaTango
- IARU
- Impresion de QSL´s

Páginas visitas en total

4 7 9 9 4 7

Vis. Hoy	30	Visitas	172 619
Paginas Hoy	49	Paginas	233 772

Navaho y le pide que (el gurú local el que sabe todo acerca del CB,...

-
  ANTENA DELTA LOOP PARA LA BANDA DE 11 MTS (FRECC 27.500 Mhz)
  Antena DELTA LOOP (De onda completa)   2 elementos sintonizada en la frecuencia de 27.500 MHz (banda de 11 mts): Dimensiones de...
- 
  ANTENAS SUBTERRANEAS.
  Usadas por Rusos y Americanos en Comunicaciones Tácticas. Dice una frase que nada es nuevo bajo el sol. Y podemos aplicar esta frase al t...
- 
  Una interesante antena para 11 metros...
  En esta oportunidad traigo una antena que pertenece a las EH Planas , esta variante para 11 metros calculada para 27.500 la he diseñado ...
-
  10SD156 Martin -- 201PT054 Roger Polinesia Francesa.
  Distancia 6752 kilómetros o 4196millas ó 3646 millas náuticas
- 
  tORMENTA SOLAR.
  Uno de los fenómenos solares más importantes desde la perspectiva de la Tierra es la eyección de masa coronal (CME) , el equivalente solar d...

- Joe 2AT041
- JON 34SD127
- Jorge XE2X
- OptiBeam Antenas
- Prefix Locator
- QRZ.COM Data Base
- QRZ11 Forum
- RCS Radio Club Satélite
- SDR Univ de Twente Holanda Live.
- Shack Pix
- Sugar Delta
- XE1GR Juan Pablo



ES	30,102	AO	16
MX	27,351	AE	16
AR	18,056	HK	16
US	15,876	VN	15
CL	7,819	KW	12
CO	6,038	RE	12
VE	5,555	NA	12
PE	3,919	KG	11
BR	3,765	MK	11
UY	2,554	NC	10
EC	2,373	TN	10
FR	1,577	CY	10
IT	1,516	MQ	10
DE	1,119	AL	9
PR	1,104	MD	9
BO	1,096	GP	9
DO	1,073	JM	9
PT	1,060	IS	8
CR	957	GF	8
PL	939	MZ	7
RU	785	LB	7
CU	726	HT	7
PY	699	JO	6
GB	671	PK	6
GT	669	CM	6
NL	569	BZ	5
RO	532	ME	5
BE	520	CI	5
PA	516	PF	5
SV	510	AW	5
ID	504	PS	5
CA	434	TT	5
CN	355	BM	5
JP	342	BB	4
NI	335	BS	4
GR	318	NG	4
HN	306	QA	4
CZ	226	MG	3
UA	206	SR	3
FI	195	IQ	3
AU	164	BL	3
HU	149	AZ	3
TH	148	MN	3
SE	132	MM	3
TR	130	SM	3
DK	115	BD	2
CH	115	LK	2
HR	112	RW	2
SK	107	CW	2
BG	98	AM	2
RS	97	KE	2
SI	94	BJ	2
NO	91	SN	2
IE	75	OM	2
AT	73	VG	2
KR	63	AN	2
MY	60	UZ	1
AD	55	BW	1
IN	50	LY	1
LT	50	KH	1
PH	42	GY	1
BA	39	BH	1
ZA	39	GW	1
KZ	38	SS	1
IL	37	SY	1
TW	33	FO	1
MA	29	LI	1
EE	28	YE	1
LU	26	SD	1
EG	26	CV	1
MT	26	MF	1
DZ	25	GI	1
GE	25	ML	1
SA	20	JE	1
NZ	19	SB	1
LV	19	ST	1
BY	18	MU	1
SG	17	BN	1

FLAG counter

10SD156 M@RTIN -:- La información aquí expuesta es confines didacticos y de conocimiento.. Tema Viajes. Con tecnología de Blogger.

"MUrDuck" VHF "rubber duck" Portable Antenna

RE-A144V1P

de ON6MU

You can make your own 2-meter "rubber duckies" that will likely perform much better than many commercial units. I compared my design with two other "rubber duckies" of the TH215 and ICT7 which outperformed them both. With the "duckie" of the ICT7e as much as 10dB. It does not has a gain compared to a 1/4wave antenna ofcourse, but compared to most standard "rubber duckies" its average "gain" is about 6dB (or more). This has several reasons:

- You can tune it for optimal SWR/performance and to the centre frequency you desire (factory duckies are mass-produced and their SWR isn't always good. The TH215 antenna had an SWR of 1:1,4 and the ICT7 dualband antenna was 1:1,6 SWR)
- The coil is much much better and has a higher Q (less loss)
- The effective antenna length is 24 cm (about 10 inches = 1/8wave)
- Performs much better and cost way less then a commercial one!
- Can handle more power (isn't that important for HT's, but nevertheless...an advantage.)
- Better radiation pattern
- You can build a replacement antenna that delivers a lower SWR and more RF output than the one that came with your radio, and you can do it for 10euro or less and a couple of hours of fun! And...It's educational, it's HAM-radio and what's more fun then using your own homemade antenna and to see it out-perform most commercial "duckies" HI.

This design is based on using a maximum applied RF power of 15 W at 144 to 148 MHz.

To test and tune you need:

- A accurate SWR/Power meter and field strength meter
- A HT or low power transceiver and some coax with the proper connectors

BNC

Half finished

TH215 duckie

Results in practice, tested at five different positions:

Position	ICT7e ant (10cm)	MUrDuck 1/8 wave	Kenwood 1/4 telescopic ant
A	S 4	S 9+	S 9+6dB
B	S 7	S 9+12dB	S 9+15dB
C	S 3	S 8	S 9
D	S 5	S 8	S 9
E	S 9+6dB	S 9+20dB	S 9+30dB

Transmitter: Icom ICT7e @ 0,5 watt
Location: City, inside building, 1Km

Receiver: Kenwood TM255
Location: City, 2x5/8 comet @ 18mASL

Conclusion: Our "MUrDuck 1/8 wave duckie" performs much better then the standard Icom ICT7e dualband duckie but does not beat a the quarter wave Kenwood dualband telescopic antenna. Although the results between the quarter wave and the "MUrDuck" are very close, the measurements between the factory ICT7e duck-antenna are quite impressive!
Note: the S-readings are not calibrated readings!!!

What you need to build the MUrDuck (RE-A144V1P):

- some copper electrical installation wire of 1mm diameter
- some "left-over" 3cm 5/8" PVC pipe
- a piece conducting material of 25cm in length,
  like: thick flexible electrical installation wire, RG58, Aircell+, 5mm(or more)earthwire,...
- a male BNC-connector (I used a BNC to Cinch connector)



Wind 5 turns of 1mm wire around a coil form of 10mm diameter, keeping the turns about 0.5mm apart. This will fit snugly into the 5/8" PVC tube.

The is coax soldered to the coil and the coil is soldered to the centre pin of the BNC. Solder it to the coax (if you use a coax as antenna): The center conductor and the shield of bothe sides of the coax is connected together. Cut if needed (optimal SWR). Mine was cut to 24 cm.



To Test

For optimal performance, use a VHF SWR/power meter and a field-strength meter to tune the antenna. If you don’t, your
homemade antenna may still work at least as well as the factory antenna. I used a Daiwa SWR meter and a "homebrewed" field-strength meter positioned about eight feet away from the transceiver. Connect your new antenna to the SWR/power meter using the proper combination of connectors.

(A right-angle SO-239 adapter and a PL-259-to-female BNC adapter worked for me.)

Attach the radio’s antenna output to the SWR meter’s transmitter input with a 60cm (or shorter) length of coaxial cable.
Adjust the field-strength meter’s location and its antenna for a mid-scale reading.
Connect your commercial rubber ducky to the SWR/power meter and check the antenna’s performance; log your measurements.
Those are the numbers you’re going to beat. We’re looking for minimum SWR, maximum power and maximum field strength.

Now, attach your homemade antenna to the SWR meter. Check the antenna’s SWR and field strength. Gently adjust the
vertical position of the whip until there is an improvement in the readings if needed. Try squeezing the coil turns closer to each other which influences the SWR too. Continue making adjustments until the readings are optimized.

Once you are satisfied, run a bead of glue around the base of the whip. Place
the 3cm 5/8" PVC pipe over the coil, overlapping both ends of the coil form and leaving enough space to push in the BNC connector and room to fill the rest up with glue of a glue-gun.



You can see the BNC-connector which is pushed in the PVC-pipe by carefully heating up the end of the 3 cm long PVC 5/8" tube. After checking the SWR it's filled with glue from a glue-gun which gives it the solid-state and durable finish (and watertight).

I've managed to get the SWR to 1:1!

A few last things to note. A small antenna such as a rubber duck antenna (or even a mag-mount antenna) attached directly to a radio will give different results based on the size of the radio, what's connected to it, and the things around it. The reason for this is that the antenna tuning is affected by the "counterpoise", which in the case of a rubber duck is the radio itself. (If the antenna is outside or better isolated from the radio, the readings should be the same.) Since things like rubber ducks won't be the same with an outboard SWR meter connected or the same as an antenna analyzer might show, the only way to know what the SWR is for a particular radio and frequency with a particular configuration of power supply, microphone, people etc, is to read the SWR off the radio. Of course if that's not accurate, you're not getting the right information.

More of interest:
AdChoices RF Connectors Receiver RF Transmitter RF Power Meter

The Telescopic MurDuck
RE-A144V2P

Same principle, but using a telescopic antenna of 30 cm in length. Being telescopic it can be used for more then one frequency. I also put a 3 pF capacitor inside the coil and soldered on both ends of the coil (making it parallel resonant). The "block" frequency lies way out of the VHF or UHF HAM bands. 144...148 or 420...440mc are easily passed through, making it dualband. The frequency that's being blocked is about 290 Mc +/-.
Instead of a BNC connector I used a SMA connector.



Coil dimensions: 6.5 turns, 4mm inside diameter, 0.6mm wire (+/- 100nH)
Inside the coil: a 3pF capacitor

finished

I used a SMA connector for use with my Yaesu VX-1. The included "petite" rubber duck isn't worth much. This has made a huge difference not only for VHF/UHF, but also outside the ham-bands as this little VX-1 thingy has wide reception.

To test and tune your telescopic dualband antenna the same principles described above (MurDuck) applies here too.

The tank resonance formule: 2*pi*F= 1/sqrt(L*C) => 291 Mc block frequency

Have fun and my best 73"

Guy, ON6MU
http://www.qsl.net/on6mu

Home
www.qsl.net/on6mu

ON6MU

While not strictly a compendium on baluns, W2FMI does review the amateur literature, both fact and fanciful, on the subject. He also presents the results of his experiments plus workable designs that we can build.

More On The 1:1 Balun

BY JERRY SEVICK*, W2FMI

My most recent *CQ* article entitled "More On The 4:1 Balun"[1] presented some new 4:1 designs as well as an evaluation of the designs which have appeared in our amateur radio literature over the years. If you read the article, you saw that I was very critical of the information made available to amateurs. In fact, it was shown that a very poor design was converted into a "peerless" design by making three simple changes. The number of bifilar turns was changed from 10 to 14, the cross-sectional area of the toroid was doubled by stacking two together, and the wires were covered with Teflon tubing, resulting in the optimum characteristic impedance of the coiled transmission line. These changes made very significant improvements in both the low- and high-frequency responses of the 4:1 balun.

This article can be said to be a complement to the 4:1 balun article. In this case it treats the much more popular 1:1 balun. It begins with my view on when to use a balun. Even though much of what has been written here is taken from my Summer 1992 article in *Communications Quarterly*,[2] it is presented again here, since some of you don't subscribe to that journal. As before, highlights are also given on what has been available in the professional and amateur radio literature on the understanding and design of the 1:1 balun.

This information is then followed by some of my latest designs. Of special interest might be the one I call the "economy" model. Economy, in this case, refers to economy in labor. I hope some of these baluns are constructed and compared with the "expensive" (in labor) models also described in this article.

The article finally closes with a short summary of the significant points brought forth in this essay. As will be seen (again), the information available to radio amateurs has been sorely lacking over the past 25 years (at least)!

When To Use A Balun

Baluns have taken on a more significant role in the past few decades with the advent of solid-state transceivers and Class B linear amplifiers, which have unbalanced outputs—that is, the voltage on the center conductor of their output chassis connectors varies (plus and minus) with respect to ground. In many cases coaxial cables are used as the transmission lines from these unbalanced outputs to antennas such as dipoles, inverted Vees, and Yagi beams which favor a balanced feed. In essence, they prefer a source of power the terminals of which are balanced (voltages being equal and opposite) with respect to actual ground or to the virtual ground which bisects the center of the antenna. The question frequently asked is whether a 1:1 balun is really needed.

To illustrate the problem involved and to give a basis for my suggestions, I refer you to fig. 1. Here we have, at the feed point of the dipole, two equal and opposite transmission-line currents which have two components each—I_1 and I_2. Also shown is the spacing (s) between the center conductor and the outside braid. Theoretically, a balanced antenna with a balanced feed would have a ground (zero potential) plane bisecting this spacing. However, since a coax-feed is unbalanced and the outer braid is also connected to ground at some point, an imbalance exists at the feed point, giving rise to two antenna modes. One is with I_1 giving a dipole mode, and the other is with I_2 giving an inverted-L mode.

If the spacing (s) is increased, the imbalance at the feed point becomes greater, giving rise to more current on the outer braid and a larger unbalance of currents on the antenna's arms. Several steps can be taken to eliminate or minimize the undesirable inverted-L mode (eliminate or minimize I_2). The obvious one is to use a well-designed balun, which not only provides a balanced feed, but also minimizes (by its choking reactance) I_2 if the coaxial cable does not lie in the ground plane which bisects the center of the dipole. The other step is to ground the coaxial cable at a quarter-wave (or odd-multiple thereof) from the feed point. This discourages the inverted-L mode, since it wants to see a high impedance at these lengths instead of the low impedance of a ground connection.

Experiments with baluns were conducted on a 20 meter half-wave dipole at a height of 0.17 wavelength, which gave a resonant impedance of 50 ohms. VSWR curves were compared under various conditions. When the coaxial cable was in the ground plane of the antenna (that is, perpendicular to the axis of the antenna), the VSWR curves were identical with or without a well-designed balun no matter where the outer braid was grounded. Only when the coaxial cable was out of the ground plane was a significant difference noted. When the cable dropped down at a 45 degree angle under the dipole, a large change in the VSWR took place. This meant the inverted-L mode was appreciable.



Fig. 1–Illustration of the various currents at the feed point of a dipole. I_1 is the dipole current and I_2 is the inverted L (imbalance) current.

It should also be pointed out that the direction of I_2, the imbalance current, can depend upon the side on which the coaxial cable is out of the ground plane of the dipole. For example, if it comes down under the right side in fig. 1 (that is, the angle between the horizontal arm and the coax is less than 90 degrees on the right side and more than 90 degrees on the left side), then the direction of I_2 can be reversed by the imbalance in the induced currents on the outside of the braid. By the same token, by having the coaxial cable come down on the other side, the value of I_2 is only increased in magnitude.

Feeding a Yagi beam without a well-designed 1:1 balun, however, is a different matter. Since most Yagi designs use shunt-feeding (usually by hair-pin matching networks) in order to raise the input impedance close to 50 ohms, the effective spacing (s) is greatly increased. Furthermore, the center of the driven element is actually grounded. Thus, connect-

---

*32 Granville Way, Basking Ridge, NJ 07920



Photo A– The two basic forms of the 1:1 balun which first appeared in the professional literature. The two-conductor Guanella balun is on the left and the three-conductor Ruthroff balun is on the right.

ing the outer braid (which is grounded at some point) to one of the input terminals creates a large imbalance and hence a real need for a balun. An interesting solution, which would eliminate the matching network, is to use a step-down balun designed to match 50 ohm cable directly to the lower balanced-impedance of the driven element.[3]

In summary, if one concurs with the theoretical model of fig. 1, my experiments performed on 20 meters, and the reports from radio amateurs using dipoles and inverted Vees without baluns, then it appears that 1:1 baluns are really needed for (a) Yagi beam antennas where severe pattern distortion can take place without one and (b) dipoles and inverted Vees that have the coaxial cable feed lines out of the ground plane that bisects the antennas or that are unbalanced by their proximity to man-made or natural structures. In general, the need for a balun is not so critical with dipoles and inverted Vees (especially on 40, 80, and 160 meters) because the diameter of the coaxial cable connector at the feed point is much smaller than the wavelength.

If my model—which assumes that a part of the problem when feeding balanced antennas with coaxial cable is related to the size of the spacing (s), shown in fig. 1—is correct, then the possibility exists for using ununs for matching into balanced antennas with impedances other than 50 ohms and with small values of s. For example, half-wave dipoles at a height of about a half-wave, quads and center-fed 3/2-wave dipoles which all have impedances close to 100 ohms, could very well be matched to 50 ohm cable by a 2:1 unun.[4] As was shown, they are considerably easier to construct than 2:1 baluns.[5] Furthermore, Genaille[6] has recently shown considerable success in using ununs in this kind of application.

In closing this section I would like to comment on an article published by Eggers, WA9NEW,[7] concerning the use of a balun with a half-wave dipole. While at North Carolina State University, he conducted an experimental investigation of pattern distortion without a balun at 1.6 GHz in an RF anechoic chamber (which simulates "free space"). Briefly, his results showed that with a balun (a bazooka type), the radiation pattern compared very favorably with the classic "figure-eight" pattern. Without the balun, the radiation pattern was severely distorted.

Even though the author expressed difficulty in obtaining accurate measurements at this very high frequency, I have a question regarding the validity of performing the experiment



Fig. 2– Two versions of the 1:1 balun: (A) The Guanella balun and the basic building block; (B) The Ruthroff balun as originally drawn.

Introducing the...

HIGH SIERRA

HF Mobile Antenna

Based on W6AAQ's famous DK3("screwdriver") antenna...with some improvements.



High performance, proven design. Heavy duty construction. All machined parts--stainless steel hardware!

Continuous coverage from 3.5MHz to 30MHz. All without setting foot outside your car, motorhome, or RV!

Exclusive "decoupler" eliminates need for contact fingers...very reliable!

Built-in matching device. Low SWR over entire range. No antenna tuner required!

Rainshield & base mount hardware kit included!

$289 (plus S & H)

High Sierra Antennas
P.O. Box 2389
Nevada City, CA
95959, USA
Tel: (916) 273-3415
Fax: (916) 273-7561

Write for brochure

CIRCLE 50 ON READER SERVICE CARD

ICOM

IC-728 HF Xcvr./Gen. Cov. Rcvr.	$899.00
IC-735 HF Xcvr./Gen. Cov. Rcvr.	1054.00
IC-737A HF Xcvr./Gen. Cov. Rcvr.	1469.00
PS-55 AC Power Supply	226.00
AT-150 HF Automatic Antenna Tuner	439.00
SM-8 Desk Microphone	111.00
SP-7 Base Station External Speaker	68.00
SP-10 Mobile External Speaker	43.00
SP-20 Base Station Ext. Spkr. W/Audio Filters	162.00
IC-R1 Communications Receiver	469.00
IC-R7000 Communications Receiver	1249.00
IC-R7100 Communications Receiver	1319.00
IC-228H 2-Meter, FM, 45 Watt Xcvr.	369.00
IC-229H 2-Meter, FM, 50 Watt Xcvr.	389.00
IC-3230H 2-Mtr./440-MHz., FM, 45W/35W	649.00
IC-2GAT 2-Mtr., FM, Handheld With T-T	294.00
IC-4GAT 440-MHz., FM, Handheld With T-T	294.00
IC-2GXAT 2-Meter, FM, Mini Handheld W/T-T	294.00
IC-2SRA 2-Mtr./50-905-MHz., FM, Mini H-H/T-T	499.00
IC-W2A 2-Mtr./440-MHz., FM, Mini H-H W/T-T	474.00
BP-4 Battery Case	20.00
BP-5 10.8 VDC, 425 mAH., Ni-Cad Batt. Pack	73.00
BP-7 13.2 VDC, 425 mAH., Ni-Cad Batt. Pack	87.00
BP-8 8.4 VDC, 800 mAH., Ni-Cad Batt. Pack	87.00
CM-96 8.4 VDC, 1200 mAH., Ni-Cad Batt. Pack	99.00
BP-83 7.2 VDC, 600 mAH., Ni-Cad Batt. Pack	65.00
BP-84 7.2 VDC, 1000 mAH., Ni-Cad Batt. Pack	87.00
BP-90 Battery Case	20.00
BP-130A Battery Case	21.00
BP-157A 7.2 VDC, 900 mAH., Ni-Cad Batt. Pack	54.00
BP-160 7.2 VDC, 700 mAH., Ni-Cad Batt. Pack	43.00
BC-35U Desktop Charger; BP-2, 5, 7, 8, 96	95.00
BC-72A Desktop Chg.; BP-81, 82, 83, 84, 85, Int.	104.00
BC-79A/AD-28 Dsktp. Chg.; BP-132A, 157A, 160	131.00
CP-11 Cigarette Lighter Cable W/Noise Filter	29.00
CP-12 Cigarette Lighter Cable W/Noise Filter	21.00
CP-13 Cigarette Lighter Cable W/Noise Filter	22.00
HM-46 Speaker/Microphone	40.00
HM-54 Speaker/Microphone	55.00
HM-65 Speaker/Microphone For IC-2SRA/W2A	42.00
HM-70 Speaker/Microphone For IC-2SRA/W2A	42.00
HS-51 Headset, PTT & VOX	67.00
HS-60 Headset, PTT & VOX, For IC-2SRA/W2A	76.00

BENCHER

BY-1 Iambic Paddles, Black Base	$64.95
BY-2 Iambic Paddles, Chrome Base	79.95
ZA-1A 1:1 Balun, 3.5 To 30-MHz.	34.95

CUSHCRAFT

R5 14, 18, 21, 24, 28-MHz. Vertical	$267.00
R7 7, 10, 14, 18, 21, 24, 28-MHz. Vertical	357.00
ARX-2B 2-Meter, Ringo Ranger II Vertical	49.00
ARX-220B 220-MHz., Ringo Ranger II Vertical	49.00
ARX-450B 450-MHz., Ringo Ranger II Vertical	49.00
AR-270 2-Meter/440-MHz., Ringo Vertical	61.00
AR-270B 2-Meter/440-MHz., Ringo Vertical	88.00
ARX-270U 2-Mtr./440-MHz., Fiber. Ringo Vert.	188.00
A50-5S 50 To 54-MHz., 5-Element Beam	119.00
124WB 144 To 148-MHz., 4-Element Beam	49.00
A148-10S 144 To 148-MHz., 10-Element Beam	56.00
13B2 144 To 148-MHz., 13-Element Beam	95.00
224WB 222 To 225-MHz., 4-Element Beam	47.00
225WB 222 To 225-MHz., 15-Element Beam	98.00
A449-6S 440 To 450-MHz., 6-Element Beam	40.00
A449-11S 440 To 450-MHz., 11-Element Beam	57.00

ASTRON

RS-7A 13.8 VDC, 7 Amp Int., 5 Amp Cont.	$49.50
RS-12A 13.8 VDC, 12 Amp Int., 9 Amp Cont.	71.50
RS-20A 13.8 VDC, 20 Amp Int., 16 Amp Cont.	88.50
RS-35A 13.8 VDC, 35 Amp Int., 25 Amp Cont.	141.50
RS-12M Same As RS-12A, With Meters	82.50
RS-20M Same As RS-20A, With Meters	108.50
RS-35M Same As RS-35A, With Meters	159.50
VS-35M Same As RS-35M, Adj. Volt./Curr.	171.50

UPS/Insurance Charges Are Additional
MC And VISA Orders Are Accepted
Prices Subject To Change Without Notice

LaRue Electronics

1112 GRANDVIEW STREET
SCRANTON, PENNSYLVANIA 18509
PHONE (717) 343-2124

CIRCLE 65 ON READER SERVICE CARD



Photo B– Two versions of Turrin's design: on the left, the 1:1 balun that has appeared in the amateur radio literature; on the right, a 1:1 balun that has been readily available in kit form from Amidon Associates, Inc.

in the first place. From the photograph in the article it appears that conventional coaxial cable and connectors were used in the experiment. If we assume an effective diameter of 0.375 inches for these components, then scaling up to 3.5 MHz (457.14 fold) results in a coaxial cable with a diameter of 14.28 feet! I am quite sure that the large spacing (s) of 7.14 feet would bring about a noticeable imbalance, resulting in appreciable pattern distortion even at 3.5 MHz.

Highlights of Significant Articles on 1:1 Baluns

Although there have been many articles published in the professional and amateur literature, I have selected a few that I thought had the most impact on 1:1 baluns for amateur radio use. As you will see, even though I consider some of the amateur articles significant, their impact upon the use and understanding of these devices has not always been positive. In fact, in some cases just the opposite has been true.



Fig. 3– (A) A pictorial of Turrin's 1:1 balun, and (B) a schematic of his balun.

In The Professional Literature

As I noted in a recent *CQ* article,[5] there are actually only two significant articles in the professional literature that provide the fundamental principles upon which the theory and design of this class of transformers are based. It can be said that succeeding investigators only really extended the works of the authors of these two articles.

The first presentation on broadband matching transformers using transmission lines was given by Guanella in 1944.[8] He coiled transmission lines forming a choke such that only transmission-line currents were allowed to flow no matter where a ground was connected to the load. His single, coiled transmission line resulted in a 1:1 balun. It is shown on the left in fig. 2(A). Prior to this RF baluns were achieved by the use of quarter- and half-wave transmission lines, and as a result, had narrow bandwidths. Guanella then demonstrated broadband baluns with impedance transformations of 1:n^2 where n is the number of transmission lines he connected in a series-parallel arrangement.

Several important points should be made regarding Guanella's 1:1 balun shown in fig. 2(A). With sufficient choking reactance so that the output is isolated from the input and only transmission-line currents flow, by grounding terminal 5 (actually or virtually like the center of a dipole), terminal 4 becomes $+V_1/2$ and terminal 2 becomes $-V_1/2$, resulting in a balanced output. This type of balun has lately been called a "current" or "choke" balun. A significant feature of this model is that a potential gradient of $-V_1/2$ exists along the length of the transmission line. This gradient, which exists on both conductors, accounts for practically all of the loss in these transformers, since the loss-mechanism is voltage-dependent (a dielectric-type loss). All transmission-line transformers have some sort of voltage gradient along their transmission lines and are thus subject to the same type of losses. Furthermore, the theory and loss-mechanism are the same whether the transmission lines are



Fig. 4– The input impedance versus frequency, when terminated with 50 ohms, for the Turrin, rod-type, and Amidon 1:1 baluns.

coax or twin-lead or coiled around cores or threaded through ferrite beads. Additionally, it was shown[3] that higher-impedance baluns or baluns subjected to higher VSWRs have more loss because the voltage gradients are also larger.

The second and other significant article on broadband transmission-line transformers was by Ruthroff in 1959.[9] His 1:1 balun, which is shown originally drawn in fig. 2(B), used an extra winding to complete (as he said) the path for the magnetizing current. Even though his schematic drawing appeared to look like a trifilar winding, his pictorial in the article clearly showed that the third winding (5–6) was on a separate part of the toroid. With an equal number of turns, it forms a voltage divider with winding (3–4) placing terminal 4 at $+V_1/2$ and terminal 2 at $-V_1/2$. Ruthroff also presented in his classic paper his forms of the 4:1 balun (which are also different from Guanella's), a 4:1 unun, and various hybrids. Photo A shows the two basic forms of the 1:1 balun which first appeared in the professional literature. The two-conductor Guanella 1:1 balun is on the left and the three-conductor Ruthroff balun is on the right. As was mentioned before, the Guanella balun recently has been called a "current" or "choke" balun.

Before going on to the significant articles in the amateur radio literature, some mention should be made of the differences between the two basic forms shown in photo A. Guanella's 1:1 balun came to be known as the *basic building block* for this whole class of broadband transformers. This term was coined by Ruthroff as he showed its 1:1 balun capability when the load was grounded at its center (terminal 5) and as a phase-inverter when the load was grounded at the top (terminal 4). By connecting terminal 2 to terminal 3 and connecting the bottom of the load to ground, Ruthroff then demonstrated his very popular 4:1 unun. I called this type of arrangement the "boot-strap" connection. Furthermore, by grounding terminal 2, there is no potential drop along the transmission line and therefore no need for magnetic cores or beads. This arrangement, which turns out to be an important function for extending the high-frequency performance of this class of transformers, I call the "phase-delay" connection.

Thus, with the flexibility shown by Guanella's basic building block, a 1:1 balun is now realized which not only presents a balanced power source to a balanced antenna system, but can also prevent an imbalance current (an inverted-L antenna current) by its choking reactance when the load is unbalanced or mismatched or when the feedline is not perpendicular to the axis of the antenna.

Interestingly enough, except at the very low end of the frequency response of the Ruthroff 1:1 balun where autotransformer action can take place, his balun takes on the characteristics of the Guanella balun. The reactance of the third winding becomes great enough to make it literally transparent. This is not the nature of the trifilar-wound (voltage) balun, which is sensitive to unbalanced and mismatched loads over its entire passband, since it is actually two tightly coupled transmission lines. This distinction was not recognized by most of those who published in the amateur radio literature.

In The Amateur Radio Literature

R. Turrin, W2IMU—1964. The first presentation in the amateur radio literature on 1:1 baluns using ferrite cores was by Turrin in 1964.[10] Turrin, who was a colleague of Ruthroff at Bell Labs, took his small-signal design (which used No. 37 or 38 wire on toroids with ODs of 0.25 inch or less) and adapted it to high-power use. This was done by using thicker wire, larger cores, and (very important for high efficiency[3]) low-permeability ferrite. Ruthroff used lossy manganese-zinc ferrites with permeabilities of about 3000, since efficiency was not a major consideration.

Fig. 3 shows a pictorial and a schematic of Turrin's design. As you can see, the third wire (winding 3–4) is placed between the two current-carrying wires (windings 1–2 and 4–5). Photo B shows (on the left) his actual design using a ferrite core and a popular design (on the right) using a powdered-iron core that has been readily available in kit form. Both baluns use 10 trifilar turns of a single-coated wire such as Formex or Formvar on a toroid. Turrin's design uses a ferrite toroid with an OD of 2.4 inches and a permeability of 40. The kit balun uses a powder-iron toroid with a 2 inch OD and a permeability of only 10. Both baluns are specified to handle 1000 watts of power from 1.8 MHz to 30 MHz.

Fig. 4 shows the response curves for these two baluns when terminated with 50 ohm loads. Also shown is the response curve for a popular 1:1 rod-type balun which uses the



Photo C– A typical rod-type balun.

Introducing two of the best reasons to use packet radio



The PackeTen™ Network Switch

The PackeTen Network Switch is a stand-alone, five-port, low power CISC/RISC packet switch/router designed exclusively for use with AX.25, TCP/IP, and NET/ROM® wireless networks.

- Port speeds as high as 4Mbps possible with throughput into the mega-bit range
- Multiple RS-422, RS-232, and integral modems eliminate the need for complex node-stacks
- Integral conference bridge supports 100 channels with 40 users on each



The PackeTwin™ System

The PackeTwin System is a complete wireless communications system for IBM® compatible PCs that provides ideal access to 9600 baud packet radio networks.

- Available with an on-board G3RUH 9600 baud modem and palm-size outboard 2W UHF radio *(1200 baud available)*
- Uses the PC's DMA channels to support data rates as high as 1Mbps—eliminating the asynchronous COM port bottleneck
- Second channel operation using RS-232 or RS-422 interface
- Includes free communications software

For information, contact your distributor or...

Gracilis
The new name in Packet Radio

Gracilis, Inc.
623 Palace Street
Aurora, IL 60506
Ph: (708) 801-8800/FAX: (708) 844-0183
Email: info@gracilis.com

VISA MasterCard

All trademarks are property of their respective owners

CIRCLE 43 ON READER SERVICE CARD



Photo D– A Reisert, W1JR, 1:1 balun.

cant article on 1:1 baluns was published by Reisert in 1978.[12] He proposed winding some of the smaller (but still high-powered) coaxial cables around a 2.4 inch OD ferrite toroid with a permeability of 125. The windings also included a cross-over which is shown in fig. 5 and photo D. In addition, he recommended various numbers of turns depending upon the low-frequency requirement. For example, 12 turns to cover 3.5 MHz, 10 turns for 7 MHz, 6 for 14 MHz, and 4 turns for 21 and 28 MHz. Since the characteristic impedance of the coaxial cable is the same as the coax feed line, the balun only introduces a foot or two of extra length to the feed line. This is true in the HF and VHF bands. The coaxial cables recommended in the article were RG-141/U, RG-142/U, and RG-303/U.

From the articles that followed in the amateur radio literature it became apparent that few recognized all of the important features of his balun, which were:

1. An efficient, low-loss ferrite was used.

2. The baluns had sufficient choking reactances for the various low-frequency requirements.

3. The characteristic impedance of the coiled transmission line was the same as that of the feed line, thus eliminating the extra transformer action of a length of transmission line with a different characteristic impedance.

4. The balun is a form of Guanella's two-conductor 1:1 balun which is not prone to core flux and hence saturation and the generation of spurious frequencies. It is also not susceptible to mismatched and unbalanced loads such as the Turrin and "voltage" baluns.

After constructing several of his baluns and comparing them with other Guanella designs, I found that the cross-over winding had virtually no effect up to 100 MHz (the limit of my equipment). My second comment is with regard to his VSWR comparison with a rod-type balun when feeding a triband Yagi beam on 20 meters. His balun had a lower VSWR (practically 1:1) at the best match point. The rod-type balun had a best VSWR of about 1.3:1 but at a slightly higher frequency. He attributed the higher (and somewhat flatter) VSWR curve of the rod-type balun to its greater ohmic loss. Since the rod-type baluns I have investigated used the same low-loss ferrite that Reisert did, I suspect that the differences in the VSWR curves were mainly due to the mismatch loss introduced by the rod-type balun.

G. Badger, W6TC—1980. Badger published an in-depth, two-part series in 1980 on air-core baluns and ununs in *Ham Radio* magazine.[13,14] I am sure it was instrumental in advancing the technology of this class of wideband transformers. A recent article by Bill Orr, W6SAI, also shows that there are many other radio amateurs who see the advantages of air-core transformers.[15]

What are the claims for air-core baluns over their ferrite-core counterparts? The first and foremost claim is that they don't suffer the consequences of saturation, which leads to spurious frequencies, heating, and ultimate damage. Second, they are not subject to arcing from the windings to the core.

And what are the claims for the ferrite-core baluns over their air-core counterparts? Simply put, they have wider bandwidths and are more compact.

What especially came to my attention after reading Badger's two-part series was his experimental data on harmonic distortion due to saturation in a ferrite-core 1:1 balun. Although many have expressed concerns regarding saturation in ferrite-core baluns, Badger's data could very well be the only results available. He used the two-tone test method, which combined two RF sources of 2.001 and 2.003 MHz, amplified it to 2 KW PEP, and then fed it through a commercial 1:1 rod-type ferrite balun. The



Photo E– The Maxwell, W2DU, "choke" 1:1 balun.

data showed considerable distortion in the 3rd order and the 9th order distortion products. In other words, appreciable non-linearity took place at this high-power level.

Several questions come to mind regarding these measurements. What was the low-frequency response of the commercial 1:1 rod-type balun he used? From my measurements on a rod-type balun (fig. 4), I found a drop in the input impedance and an inductive component at 2 MHz. This indicates flux in the core and a problem when using this balun at 2 MHz. Since many rod-type 1:1 baluns have been used over the years, it would have been instructive if he had also made these measurements at 4 and 7 MHz. They would have given the readers a safe lower-frequency limit for these baluns.

Also, why didn't Badger make similar measurements on Reisert's 1:1 balun, which he included in his articles? As noted earlier, I consider Reisert's 1:1 balun a very good design! I am sure that no distortion products would have been found at 2 MHz with it. The end result is that Badger chose a very poor ferrite-core design for making his comparisons. This helped contribute to an undeserved reputation for the ferrite-core balun.

Badger also suggested placing an insulated wire in parallel with the coax winding on Reisert's 1:1 balun. He called this a compensating winding, which provided a superior balanced output. The schematic is shown in fig. 6. Later experiments by the author and others have shown that a well-designed, two-conductor (Guanella) 1:1 balun has a completely satisfactory balanced output for antenna applications. Furthermore, it does not suffer from an unbalanced and/or mismatched load and core saturation. Incidentally, Badger's schematic of fig. 5 now adds up to *four* different versions of the 1:1 balun. They are the two-conductor version of Guanella's and the three, three-conductor versions of Ruthroff, Turrin, and (now) Badger.

Badger and Orr also mentioned the Collins balun in their articles. It is made up of a dummy length of coax which is wound as a continuation of the original coiled coax winding. Interestingly, it is connected as a Ruthroff 1:1 balun (fig. 2[B]), which also uses a third winding. Since there is appreciable coupling between the two coiled windings, the Collins balun should also be susceptible to mismatched and/or unbalanced loads. Badger claimed it was by far the best 1:1 balun he had ever used. Again, it would have been very informative if he had compared it with the Reisert balun (without the compensating third wire).

M. W. Maxwell, W2DU—1983. One of the more significant articles on 1:1 baluns was published by Maxwell in 1983.[16] He introduced what he called the "choke" balun. It was formed by placing high-permeability ferrite beads over about one foot of small (but high-powered) coaxial cables similar to the ones used in the Reisert balun. Photo E shows the W2DU "choke" balun removed from its housing.

Maxwell compared his balun with (what he termed) a "transformer-type" balun by measuring the input impedances versus frequency when the outputs were terminated in 50 ohms. Since the "transformer-type" balun didn't yield a true 1:1 impedance transfer ratio, he claimed it was because of losses, leakage reactance, and less than optimum coupling. Since he gave no description of the "trans-

Spider™ Antenna
U.S. Patents 4349825, 4460896 Made in U.S.A. ™

Presenting the family of Spider™ Multi-Band Antennas

Four amateur bands (10, 15, 20, and 40 meters) at your command without having to change resonators or retune — just band switch your rig. Also available are the 75, 12, 17 and 30 meter bands. Needs no antenna tuner. Custom made with highest quality workmanship and materials.

Wherever you roam, on Land or Sea . . . or even at Home

On Land
Suitable for use on any motor vehicle from a compact automobile to a motor home or trailer. Work four bands without stopping to change resonators.

Or Sea
The Spider™ Maritimer is for use on or near the ocean. Highly polished stainless steel and nickel-chrome plated brass. Commercial marine frequencies (8, 12, 16 and 22 MHz) are also available.

At Home
If you live in an apartment, condominium or restricted area, the Spider™ may well be the answer to your antenna problems.

DIPOLE

MULTI-BAND ANTENNAS
7131 OWENSMOUTH AVENUE, SUITE 263C
CANOGA PARK, CALIFORNIA 91303
TELEPHONE: (818) 341-5460

DUPLEXERS
★ QUALITY ★ SERVICE ★ PRICE
WE'VE GOT IT ALL!

Our Bandpass-Reject Duplexers with our patented B_pB_r Circuit® Filters provide superior performance. . . especially at close frequency separation.

PHONE 817-848-4435
FAX 817-848-4209

WACOM
PRODUCTS, INC.
P.O. BOX 21145 • WACO, TX 76702

CIRCLE 141 ON READER SERVICE CARD

Oklahoma Comm Center

Orders & Price Quotes
1-800-7OKHAMS
1-800-765-4267
ALINCO
ALINCO ELECTRONICS INC.

DJ-580T
2M/440MHz
Handheld
DJ-F1T(H)
2M, HT
(5W Version)
DJ-G1
2M,HT
Spect. Analyzer
DJ-180T
2 Meter
Handheld
DR-600T
2M/440MHz
Mobile
DR-130T
2 Meter
Mobile
DR-570T
2M/440MHz
Mobile
DR-1200T
2 Meter
Data Radio

FREE SHIPPING
UPS SURFACE On Purchases of $50 or More (except Power Supplies and Antennas)

Local & Information
(405) 748-3066
FAX (405) 748-3077
13424 Railway Drive
Oklahoma City, OK 73114
COD
Oklahoma owned and operated.
Not affiliated with any other store

RF POWER AMPLIFIERS

NEW! 400 WATTS AVG. (144-148 MHz)

Model	Pin (W)	Pout (W)	Ic (A)	Gain/NF (dB) (dB)	(13.8 V) Type
50 MHz					
0503G	1-5	10-50	6	15/0.6	LPA
0508G	1	170	28	15/0.6	Standard
0508R	1	170	28	–/–	Repeater
0510G	10	170	25	15/0.6	Standard
0510R	10	170	25	–/–	Repeater
0550G	5-10	375'	60	15/0.6	HPA
0550RH	5-10	375	60	–/–	Repeater HPA
0552G	25-40	375	55	15/0.6	HPA
0552RH	25-40	375	55	–/–	Repeater HPA
144 MHz					
1403G	1-5	10-50	6	15/0.6	LPA
1406G	25	100	12	15/0.6	Standard
1409G	2	150	25	15/0.6	Standard
1409R	2	150	24	–/–	Repeater
1410G	10	160	25	15/0.6	Standard
1410R	10	160	24	–/–	Repeater
1412G	25-45	160	20	15/0.6	Standard
1412R	25-45	160	19	–/–	Repeater
1450G	5	350	56	15/0.6	HPA
1450RH	5	350	56	–/–	Repeater HPA
1452G	25	350	50	15/0.6	HPA
1452RH	25	350	50	–/–	Repeater HPA
1454G	50-100	350	40	15/0.6	HPA
1454RH	50-100	350	40	–/–	Repeater HPA
220 MHz					
2203G	1-5	10-40	6	14/0.7	LPA
2210G	10	130	20	14/0.7	Standard
2210R	10	130	19	–/–	Repeater
2212G	30	130	16	14/0.7	Standard
2212R	30	130	15	–/–	Repeater
2250G	5	220	40	14/0.7	HPA
2250RH	5	250	40	–/–	Repeater HPA
2252G	25	220	36	14/0.7	HPA
2252RH	25	250	36	–/–	Repeater HPA
2254G	75	220	32	14/07	HPA
2254RH	75	250	32	–/–	Repeater HPA
440 MHz					
4403G	1-5	7-25	4	12/1.1	LPA
4410G	10	100	19	12/1.1	Standard
4410R	10	100	18	–/–	Repeater
4412G	20-30	100	19	12/1.1	Standard
4412R	20-30	100	18	–/–	Repeater
4448G	5	100	22	12/1.1	HPA
4448R	5	100	22	–/–	Repeater HPA
4450G	5-10	175	34	12/1.1	HPA
4450RE	5-10	175	34	–/–	Repeater HPA
4452G	25	175	29	12/1.1	HPA
4452RE	25	175	29	–/–	Repeater HPA
4454G	75	175	25	12/1.1	HPA
4454RE	75	175	25	–/–	Repeater HPA

MODEL 1410G
STANDARD

MODEL 1450G
HPA

All amplifiers (non-rptr) are linear, all-mode with fully automatic T/R switching and PTT capability. The receive preamps use GaAs FET devices rated at .5 dB NF with +18 dBm 3rd order IP. LPA, Standard and HPA amps are intermittent duty design suitable for base and mobile operation. Repeater amps are continuous duty, class C.

Amplifier capabilities: High-power, narrow or wideband; 100-200 MHz, 225-400 MHz, 1-2 GHz, Military (28V), Commercial, etc. – consult factory. A complete line of Rx preamps also available.

RX Preamplifiers

Band	Model	NF (dB)	Gain (dB)	Connector
50 MHz	0520B	.5	25	BNC
50 MHz	0520N	.5	25	N
144 MHz	1420B	.5	24	BNC
144 MHz	1420N	.5	24	N
220 MHz	2220B	.5	22	BNC
220 MHz	2220N	.5	22	N
440 MHz	4420B	.5	18	GNC
440 MHz	4420N	.5	18	N
1.2 GHz	1020B	.9	14	BNC
1.2 GHz	1020N	.9	14	N

Consult your local dealer or send directly for further product information. All Products Made in USA.

TE SYSTEMS

TE SYSTEMS **TEL. (310) 478-0591**
P.O. Box 25845 **FAX (310) 473-4038**
Los Angeles, CA 90025

CIRCLE 130 ON READER SERVICE CARD



Photo F– Two versions of Reisert's 1:1 balun. The balun on the left uses the cross-over shown in fig. 5. The balun on the right is continuously wound. Both have the same electrical performance in the HF band.

former-type" balun, I assumed it was the popular rod-type balun shown in photo C. As you can see in fig. 4, this balun has a poor low-frequency response. Furthermore, it is really optimized for a load of 47 ohms and not 50 ohms.

But what Maxwell failed to realize was that his balun was a form of Guanella's two-conductor balun. That is, it is both a choke (a lumped element) and a transmission line (a distributed element). Additionally, Guanella's theory applies whether the transmission lines are coiled (about a core) or beaded or twin-lead or coaxial cable. From Ruthroff's classic paper,[9] which extended Guanella's work,[8] we became aware of the voltage drops along the lengths of the transmission lines. And from very accurate insertion loss measurements,[3] we learned that the losses were mainly in the magnetic medium and that they were related to the voltage levels and the permeabilities. Maxwell didn't take into account these latter findings. He used lossy high-permeability beads (2500) and assumed that the main loss was in the transmission line. He claimed that the CW pow-



Photo G– My high-power design of a bifilar toroidal (Guanella/current) 1:1 balun mounted in a 4"L × 3"W × 2.25"H Bud aluminum box.



Fig. 5– A pictorial of the cross-over used in Reisert's 1:1 balun.

er-handling capability of his balun is 3.5 KW at 50 MHz and 9 KW at 10 MHz—the same as the coaxial cable itself. I seriously question these power ratings. Ironically, it is very likely that Maxwell's balun had *more* real loss than the so-called "transformer-type" balun!

R. W. Lewallen, W7EL—1985. There is very little doubt that Lewallen's interesting article[17] in 1985 contributed significantly to the better understanding and design of 1:1 and 4:1 baluns. In it he coined the (now very popular) terms "voltage" and "current" baluns. The "voltage" balun, which is a three-conductor balun, has output ports which have voltages that are balanced to ground. It is brought about (see fig. 5) by the voltage-divider action of windings (5–6) and (1–2). Since we have two tightly-coupled transmission lines in the passband with the same potential gradients, terminal 6 is at $+V_1/2$ and terminal 4 is at $-V_1/2$, where V_1 is the input voltage. The "current" balun, on the other hand, is a two-conductor balun which causes equal and opposite currents on the output ports for any form of load impedance.

Lewallen conducted a series of experiments on 10 meters to compare the performances of "voltage" and "current" baluns under balanced and unbalanced conditions. In the unbalanced (nonsymmetrical) condition the dipole was lengthened by five inches on one side and shortened by five inches on the other side. He then obtained a figure of merit for both baluns (as well as for the case without a balun) defined as the ratio of the average magnitude of the currents at the feed point over the magnitude of the imbalance (the inverted L) current. The magnitudes of the currents were obtained by current-probe toroids. Measurements were made at the antenna feed point and at a half-wave (physically) from it.



Fig. 6– Schematic of Badger's 1:1 balun with a compensating winding (1–2). Winding (3–4) is the outer-braid of the coax and winding (5–6) is the inner conductor.

The "current" balun consisted of 15 turns of very small RG-178U coax on a FT82-61 core (a ferrite toroid with an OD of 0.825 inches and a permeability of 125). The "voltage" balun had 10 turns of RG-178U coax with a No. 26 wire in parallel (closely coupled) on the same toroid. The schematic is shown in fig. 5.

Lewallen concluded (and I agree) that his experiments clearly showed that the "current" balun gave superior performance at every measured point in each experiment. However, the "voltage" balun still improved the balance over the no-balun case. He also concluded that other experiments should be performed in order to better compare the two forms of the balun. One is the difference when the feed line is placed nonsymmetrical with respect to the antenna (to induce an imbalance current into the feed line). Others include the optimum point in the feed line to place the balun and the various kinds of core and beaded baluns.

Although Lewallen's article pretty much speaks to Badger's proposal of adding a third wire to Reisert's balun for better balance (avoid it), there are some comments and questions I have regarding his experiments and findings. They are:

1. Why didn't he use Reisert's balun as the "current" balun and Badger's suggested third-wire design as the "voltage" balun? These would have been more realistic designs for comparisons. Instead, he used very small structures, which will find very little use, and as such have higher frequency capabilities. Also, since the "voltage" balun only had 10 turns (and hence a shorter transmission line and a poorer low-frequency response), it was favored in the comparisons on 10 meters. Had he used transmission lines of equal lengths, the differences between the two baluns would have been even more dramatic.

2. It would also have been very useful if Lewallen had made comparisons between a "current" balun that could handle the full legal limit of amateur radio power (again, like the Reisert balun) and "voltage" baluns such as the rod-type balun and the toroidal Turrin balun which have been readily available for nearly three decades.

3. Additionally, comparisons should not be limited to only 10 meters. Since "voltage" 1:1 baluns are configurations of coupled transmission lines with various characteristic impedances, their performances with mismatched and unbalanced loads are more sensitive to the higher frequencies than their "current" balun counterparts. Therefore, making similar measurements on 20 meters would also provide more useful information.

4. Even though Ruthroff's classic 1959 paper[9] has been the industry standard over the years, his 1:1 balun design has been practically nonexistent in the amateur literature. Turrin mentioned its advantage over his first design in his second article.[11] However, Turrin's first design has prevailed in our amateur literature. Since Ruthroff's design has the third conductor on a separate part of the toroid, it has the balanced output mentioned by Badger[13] but still retains the flexibility of the Guanella[8] balun. In other words, as the frequency is increased, the choking action of the third wire makes it practically transparent. This enables it to handle any form of load impedance. It would have been informative if Lewallen had pointed this out and also noted that Ruthroff's 1:1 balun, although looking like a "voltage" balun, is really a "current" balun.

5. Lewallen and the others who have published in the amateur radio literature failed to reference the first presentation on what is now known as "current" or "choke" baluns. It was by Guanella in 1944.[8] Even though Guanella used coiled transmission lines without a magnetic core, his theory on how these devices work is still applicable today.

J. S. Belrose, VE2CV—1991. The last article on 1:1 baluns that I thought was worth mentioning was by Belrose in 1991.[19] In it he described the W2DU balun by Maxwell and how his technique of threading coaxial cable through ferrite beads could easily be applied to 4:1 and 9:1 baluns.

What immediately caught my attention in this article were the editor's comments, which had *highly* complimentary remarks regarding the beaded-coax balun. In essence it said, "In this breakthrough article, W2DU's peerless 1:1 current-balun design serves as the basis for excellent ferrite-bead-choke current baluns capable of 4:1 and 9:1 impedance transformation."

If one reads the article carefully, however, it becomes apparent that Belrose did not say this. His words were, "The current balun of the *type* developed by Walt Maxwell, W2DU—a balun consisting of ferrite beads slipped over a length of coaxial cable—is the best so far devised." He did not say that W2DU's balun was "peerless." In fact, in the article he said just the opposite. He pointed out that the main disadvantage of the W2DU balun is that the beads are lossy at HF and that heating becomes a concern when the transmitting power exceeds 125 watts! For high power (1 KW CW) Belrose recommended Roehm's designs,[20] which use lower permeability (850) beads nearest the balun's balanced output (where most of the heating takes place).

I do, however, question two of the advantages he claims for the W2DU balun. They are:

1. Its excellent power-loss and impedance-versus-frequency characteristics are much superior to those of a bifilar current balun wound on a ferrite toroid.

2. It has excellent power-handling capability, and can function quite satisfactorily when working into highly reactive loads. This is so because the magnetic flux produced by currents flowing on this balun's wires cannot saturate its ferrite beads.

The first advantage listed above by Belrose was obtained by comparing the input impedance and power loss versus frequency of the W2DU balun with a commercial balun when they were terminated in 50 ohms. The commercial balun is a bifilar-wound toroidal type used in a differential-T tuner. What Belrose failed to realize was that the commercial balun had heavily insulated wires resulting in a characteristic impedance greater than 100 ohms. Thus, he was actually comparing a 50 ohm transmission line with a longer line that had a characteristic impedance in access of 100 ohms! As expected, his input impedance versus frequency curve for the commercial balun was even more severe than that of the Turrin balun shown in fig. 4.

The second advantage listed above is based upon the premise that the magnetic flux produced by currents on the W2DU balun's

International Listings
1994
radio amateur
callbook
$29.95
North American Listings
1994
radio amateur
callbook
$29.95
NEW!

1994 CALLBOOKS

THE QSL BOOK!

Continuing over a 70 year tradition, we bring you two new Callbooks for 1994 with more features than ever before.

The 1994 North American Callbook lists the calls, names, and addresses for more than 500,000 licensed amateurs in all countries of North America, from Panama through Canada, including Greenland, Bermuda, and the Caribbean Islands, plus Hawaii and the U.S. possessions. 1,592 pages. Item # 087158 (paper) $29.95

The 1994 International Callbook lists more than 500,000 licensed amateurs in countries outside North America. Its coverage includes South America, Europe, Africa, Asia, and the Pacific area (exclusive of Hawaii and the U.S. possessions). 1,720 pages. Item # 087190 (paper) $29.95

Every active amateur needs the Callbook! Fully updated and loaded with extra features, the 1994 Callbooks will be published in December 1993. Order now from your dealer or send in the coupon below.

Please send me _______ copy(ies) of ***The 1994 North American Callbook*** (Item # 087158, $29.95) and _______ copy(ies) of ***The 1994 International Callbook*** (Item # 087190, $29.95).

I have enclosed my check/money order for $_______. (Please add sales tax in CA, DC, IL, MA, NJ, NY, OH, PA, TN, VA & Canada, and $3.00 per book for postage and handling for U.S. shipments and $7.00 for all shipments outside the U.S.)

Or call and charge on your credit card. MasterCard, VISA and American Express cards accepted. Please be sure to include shipping instructions. Prepayment required and must be in U.S. funds.

DRAT 1093

RADIO AMATEUR callbook
P.O. Box 2013 Lakewood, NJ 08701
1-908-905-2961 (Phone) 1-908-363-0338 (Fax)

CIRCLE 90 ON READER SERVICE CARD



Photo H– Two "economy" versions of the high-power bifilar toroidal (Guanella/current) 1:1 balun. The one on the right uses Reisert's cross-over technique.

wires cannot saturate the ferrite beads while the windings of a bifilar-wound toroidal current balun can saturate the core. This is wrong because the magnetic flux of a two-conductor type balun such as the beaded-coax *or* the bifilar-wound toroidal balun is generated by the imbalance (inverted L) current and hence is *much* less than the transmission-line currents. This is especially true with sufficient choking reactances. This impression could very well come from the perception that the toroidal-type balun still transmits the energy to the output circuit by flux linkages.

For high-power beaded-coax baluns, Belrose referred to the designs by Roehm,[20] who increased the power capability of this type of balun by using lower permeability beads near the balanced output. He also increased the length considerably. For operation from 80 meters to 10 meters, he used 28 inches of beaded coax. For 160 meters to 10 meters, he used 36 inches of beaded coax. With Belrose's suggestion of connecting beaded coaxes in parallel on the low-impedance side and in series on the high-impedance side to obtain a broadband 4:1 transformation ratio, it would require transmission lines with characteristic impedances of 100 ohms. This means, for a high-power 4:1 balun using beaded transmission lines, about 56 inches of beaded line would be required for the 80 to 10 meter operation and 72 inches for the 160 to 10 meter coverage. For a 9:1 balun these lengths would even have to be increased by 50 percent!

The question that remains is what would Belrose have said or done if he had compared the W2DU balun of Maxwell's with the W1JR balun of Reisert's. He certainly couldn't claim the advantages listed in his article for the W2DU balun. Would he still have said that the type of balun developed by Maxwell is the best so far devised? I doubt it.

J. Sevick, W2FMI—1994. In keeping with the preceding format, I thought it best to present my latest 1:1 balun designs at this point. (Kits and finished units are available from Amidon Associates, Inc., 2216 East Gladwock Street, Dominguez Hills, CA 90220.) Except for one balun that appeared in the June 1993 issue of *CQ,* the others are presented here for the first time. Since I have favored Reisert's design throughout this article, the first baluns described here are my versions of his technique of coiling small (but high power) coaxial cable around a low-permeabilty ferrite toroid. For my wire versions I could have used all sorts of adjectives to describe them, such as Guanella, two-conductor, choke, and current. But in the process of writing this section, I thought Belrose's adjectives were the most direct. Using his words, I call my wire versions of the 1:1 balun simply *bifilar toroidal baluns.*

Photo F shows two versions of Reisert's balun. The one on the left uses the cross-over shown in fig. 5. Since no difference in performance at HF was noticed without the cross-over, a continuous-wound one is also shown on the right. The main advantage in the HF band with the cross-over winding is purely mechanical. Having the input and output connections on opposite sides of the toroid is not only more convenient, but it also offers a much stronger method of mounting.

For operation from 1.8 MHz to 30 MHz, 10 turns of small coax such as RG-303/U, RG-142B/U, or RG-400/U are wound on a 2.4 inch OD ferrite toroid with a permeability of 250. If the use is limited from 3.5 MHz to 30 MHz, then a permeability of 125 is recommended, since it would yield a slightly higher efficiency at the high end. If one wants the highest possible efficiency and limits the operation from 14 MHz to 30 MHz, then a permeability of 40 is recommended. With loads grounded at their centers, these conditions were found to give ample margins (handle a VSRW of 3:1 without any appreciable flux) at their low-frequency ends.

For ease of winding, I found the TY-RAP CABLE TIES *very* useful. Two were used at



Photo I– Two low-power versions of the bifilar toroidal (Guanella/current) 1:1 balun capable of handling the output of practically any HF transceiver. The balun on the left has the cross-over.



Photo J– Two medium-power versions of the bifilar toroidal (Guanella/current) 1:1 balun capable of handling the full legal limit of amateur radio power when the VSWR is less than 2:1. The balun on the left has the cross-over.

each end. Also removing the covering on the outer braid helps. Since about 24 inches of cable is wound on the toroid, starting with at least 32 inches is recommended. Of the three cables noted above, I found RG-303/U cable the easiest to wind and connect. Although it only has a single-thickness braid (the others have double-thickness braids), its power rating is still the same—9 KW at 10 MHz and 3.5 KW at 50 MHz.

The next high-power design is shown in photo G mounted in a 4"L × 3"W × 2.25"H Bud CU 234 aluminum box. It has 10 bifilar turns of No. 12 H Thermaleze wire on a 2.4 inch OD ferrite toroid. As with the Reisert versions before, a permeability of 250 is recommended for 1.8 to 30 MHz, 125 for 3.5 to 30 MHz, and 40 for 14 to 30 MHz. One wire is also covered with two layers of Scotch No. 92 polyimide tape in order to raise the characteristic impedance to 50 ohms. With this added insulation, the voltage breakdown of this twin-lead transmission line compares very favorably with RG-8/U cable (4000 volts). In order to preserve the spacing, the wires are also clamped together about every 1/2 inch with strips of Scotch No. 27 glass tape 3/16 inches wide and a little over 1 inch long.

Two "economy" versions of the high-power bifilar toroidal balun are shown in photo H. The one on the left shows the windings crowded on one-half of the toroid. The one on the right has the same positions of the input and output connections by using the cross-over. Their performances are identical. Both baluns have 10 bifilar turns of No. 14 H Thermaleze wire on a 2.4 inch OD ferrite toroid. The choices of permeability, which trade-off bandwidth for efficiency, are the same as those used in the two previous high-power designs. As was mentioned at the beginning, the word "economy" refers to economy in labor.

This balun, which also handles the full legal limit of amateur radio power, has a small trade-off in high-frequency response. Since no extra insulation is used, the characteristic impedance of two tightly-clamped No. 14 H Thermaleze wires is 45 ohms. With one layer of Scotch No. 92 tape it increases to 50 ohms. But for most of the HF band, the difference in performance between baluns using transmission lines of 45 and 50 ohms should be negligible. Even without the extra insulation the voltage breakdown should compare very favorably with the smaller, high-power coaxes used in the Reisert versions (1900 volts).

Photo I shows two low-power versions of a bifilar toroidal balun capable of handling the output of practically any HF transceiver. One has a cross-over winding and the other a continuous winding. They both have 10 bifilar turns of No. 16 H Thermaleze wire on a 1.25 inch OD ferrite toroid with a permeability of 250. Since efficiency is not a major problem in low-power use, I found no reason to suggest the other two versions, which use lower permeabilities. It is interesting to note that two tightly clamped No. 16 H Thermaleze wires have a characteristic impedance close to 50 ohms. Therefore, this small balun (particularly with its short leads) has a very good high-frequency response.

Photo J shows two medium-power versions of a bifilar toroidal balun capable of handling the full legal limit of amateur radio power under controlled conditions—when the VSWR is less than 2:1. Being smaller than its larger (2.4 inch OD) counterpart, its heat-sinking capability, and hence power rating, is less. As before, one balun uses a cross-over while the other does not. Each has 8 bifilar turns of No. 14 H Thermaleze wire on a 1.5 inch OD ferrite toroid. The ferrite permeabilities and expected bandwidths are the same as with the other high-power baluns. Since the average magnetic path length in the core is about two-thirds that of the 2.4 inch core, only 8 bifilar turns are required in order to produce a similar low-frequency capability. Even though the characteristic impedances of their bifilar windings are 45 ohms, their responses on 10 meters should be somewhat better than the "economy" models, since the lengths of their transmission lines are shorter (18 compared to 24 inches).

And now a few words on what sort of efficiency one can expect in trading-off low-frequency response by using lower permeability ferrite cores. From earlier studies[3] it was found that the efficiency (with sufficient choking so only transmission line currents flow) is related to the permeability, the voltage drop along the length of the transmission line, and the frequency. The higher the permeability and/or voltage, the greater the loss. Additionally, the higher the permeability, the greater is the loss with frequency. It was also found that a permeability of less than 300 was necessary in order to obtain the very high efficiencies of which these devices are capable.

From the results of the studies, here are some efficiencies that might be expected from ferrites under matched conditions:

1. With 250 material, an efficiency near 99 percent at 1.8 MHz and 97 percent at 30 MHz.

2. With 125 material, an efficiency near 99 percent at 3.5 MHz and 98 percent at 30 MHz.

3. With 40 material, an efficiency of 99 percent at 14 MHz and at 30 MHz.

When a balun is exposed to a high impedance resulting in a VSWR of 2:1, the voltage, and hence loss, increases by about 40 percent. With a VSWR of 4:1 the loss doubles. With a VSWR of 10:1 the loss is more than threefold. Since limited data was obtained in this study,[3] these increases in losses with increases in VSWR could very well be greater.

Summary

In preparing this article I was quite surprised to still see the ferrite- and powdered-iron-core 1:1 balun designs that have been available in the literature and elsewhere since 1964. They not only had poor low- and high-frequency responses, but they were also susceptible to flux in the cores at their low-frequency ends. Furthermore, since they only used single-coated wires, they were also prone to voltage breakdown. No doubt, these designs were responsible for the poor reputation that the balun has had for many years.

It wasn't until 1978, when Reisert published his article, that a balun became available with all of the attributes of a good design, namely:

a) Is efficient because it uses a low-permeability core.

b) Has sufficient choking reactance to meet its low-frequency requirement.

c) Is not prone to flux in the core (and hence, saturation) since it has no third winding.

d) Has a 50 ohm characteristic impedance and thus maintains a 1:1 transformation ratio with a 50 ohm load.

e) Has a good voltage breakdown capability (1900 volts).

f) Can handle a mismatched and/or unbalanced load.

Succeeding investigators, however, failed to see the advantages of his design and proposed their own. Surprisingly, they belonged to two distinct groups. One favored "air-core" baluns and the other "choke" (beaded-coax) baluns.

The main argument given by the "air-core" followers was that their balun would never experience the problems with saturation while the "ferrite-core" balun would. The Reisert balun, however, is a current/choke type balun which could only have flux in the core by the imbalance (inverted L) current, which is much smaller than the transmission-line currents. In fact, with any degree of choking reactance by the coiled transmission line, the imbalance current is essentially negligible. Therefore, saturation is not a concern with a balun such as Reisert's. But in all fairness, it should be pointed out that with the 4:1 current/choke and voltage baluns it is a different story. All three of these types of baluns have a "magnetizing inductance" in their low-frequency models and hence a possibility of saturation with a poor design.

The advocates of the "choke" 1:1 balun claim that their beaded-coax balun can't saturate, while the bifilar (current) toroidal balun can. This is entirely wrong, since they are basically the same kind of structure—neither has a third conductor which could allow a flux-causing current at the very low-frequency end. But of all of the attributes listed above for the Reisert balun, the first one has the "choke" balun at a disadvantage in the HF band. Since its transmission line is not coiled about a toroid, it does not have the multiplication factor of N^2 (due to mutual coupling), where N is the number of turns, while the toroidal balun does. Therefore, higher-permeability beads are required in order to obtain sufficient choking reactance. This results in lower efficiency.

And finally, I am quite sure that some readers of this article will disagree with my views and/or think they have better designs than those of the Reisert baluns and the ones I presented here. If so, I encourage them to respond in print. In this way we will all benefit from the new information.

References

1. Jerry Sevick, W2FMI, "More on the 4:1 Balun," *CQ,* February 1994, pages 28–36.

2. Jerry Sevick, W2FMI, "Baluns Revisited," *Communications Quarterly,* Summer 1992, pages 13–18.

3. Jerry Sevick, W2FMI, *Transmission Line Transformers,* 2nd edition, Amateur Radio Relay League, Newington, Connecticut, 1990.

4. Jerry Sevick, W2FMI, "The 2:1 Unun Matching Transformer," *CQ,* August 1992, pages 13–18.

5. Jerry Sevick, W2FMI, "A Balun Essay," *CQ,* June 1993, pages 50–59.

6. Richard A. Genaille, W4UW, "How to Build a Multi-Tap Unun," *CQ,* May 1992, pages 28– 32.

7. Bruce Eggers, WA9NEW, "An Analysis of the Balun," *QST,* April 1980, pages 19–21.

8. G. Guanella, "Novel Matching Systems for High Frequencies," *Brown-Boveri Review,* Volume 31, September 1944, pages 327–329.

9. C. L. Ruthroff, "Some Broad-Band Transformers," *Proceedings of the IRE,* Volume 47, August 1959, pages 1337–1342.

10. Richard H. Turrin, W2IMU, "Broad-Band Balun Transformers," *QST,* August 1964, pages 33–35.

11. Richard H. Turrin, W2IMU, "Application of Broad-Band Balun Transformers," *QST,* April 1969, pages 42, 43.

12. Joe Reisert, W1JR, "Simple and Efficient Broadband Balun," *Ham Radio,* September 1978, pages 12–15.

13. George Badger, W6TC, "A New Class of Coaxial-Line Transformers, Part 1," *Ham Radio,* February 1980, pages 12–18.

14. George Badger, W6TC, "A New Class of Coaxial-LIne Transformers, Part 2," *Ham Radio,* March 1980, pages 18–29, 70.

15. Bill Orr, W6SAI, "Radio Fundamentals: The Coax Balun," *CQ,* November 1993, pages 60–65.

16. Walt Maxwell, W2DU, "Some Aspects of the Balun Problem," *QST,* March 1983, pages 38–40.

17. Roy Lewallen, W7EL, "Baluns: What They Do and How They Do It," *The ARRL Antenna Compendium,* Volume 1, Amateur Radio Relay League, Newington, Connecticut, 1985, pages 12–15.

18. Jerry Sevick, W2FMI, "Baluns for Antenna Tuners," *CQ,* November 1993, pages 50–59.

19. John Belrose, VE2CU, "Transforming the Balun," *QST,* June 1991, pages 30–33.

20. Albert Roehm, W2OBJ, "Some Additional Aspects of the Balun Problem," *The ARRL Antenna Compendium,* Volume 2, Amateur Radio Relay League, Newington, Connecticut, pages 172–174. ■

Check out our NEW

$40 Special To Charge You Up...

Periphex Power Packs for Longer QSO Time

replacements for	regular price
FNB-26 YAESU 1000ma	$ 60.00
BP-84S ICOM 1400ma	$ 63.00
PB-7S KENWOOD 1400ma	$ 59.00
EBP-24S ALINCO 1500ma	$ 62.00

Now Only $40 Each

SEE US AT DAYTON

- One Year Warranty
- Matched cell construction
- Case re-build service
- Long life, extended operating time
- Made for HAMS, by HAMS

Buy your radio from the manufacturer. Buy the battery pack from Periphex— where batteries are our only business!

Add $4.00 Shipping & Handling for first battery. $1.00 for each add'l battery - U.S. only
Connecticut residents add 6% tax.

Available from your dealer...

PERIPHEX inc.

the only thing low about our charge is the cost...

1-800-634-8132

115-1B Hurley Road • Oxford, CT 06478 • (203) 264-3985 • FAX (203) 262-6943

CIRCLE 84 ON READER SERVICE CARD

Correction To February Article

In the February issue of *CQ* on page 28, "A Subsequent Look At 4:1 Baluns," also by W2FMI, fig. 2 was incorrect. The pictorial representation of the 4:1 Ruthroff (voltage) balun is as shown here.



BUILDING A DIY VIDEO TRANSMITTER



WHAT YOU NEED

- Blank PCB Copper Plate (jameco.com part #169279)
- Capacitors: 2x 0.1uf
  1x 100u
  2x 6-70pf Variable Caps (jameco.com part #32855)
- Resistors: 27kOhm
  10kOh
- Transistor-MPSA18 (jameco.com part #210681)
- 1k potentiometer
- Small amount (~4”) of magnet wire 24 AWG or close (jameco.com part #2098419)
- Sand paper
- Stranded hookup wire
- Hacksaw or dremel tool
-Headphones with 1/8” plug (from iPod or MP3 player)
- Hot glue or super glue
- Soldering Iron
- CRT “tube” TV with an antenna (the transmitter won’t transmit to newer flat screen TV’s)





INTRODUCTION

This micro video transmitter was designed by the DIY radio and micro TV artist Tetsuo Kogawa. His website (http://anarchy.translocal.jp/) is full of great info on DIY radio, and all credit for this circuit goes to him.The transmitter can be used to transmit a relatively clear video signal or abstract visualizations, depending on the desired output. It will usually function at a distance of about 20 feet. If you have any previous experience with electronics or circuit building, you will notice that this method of building is different. The circuit is constructed on top of a copper “ground plate” which is common in radio applications. This tutorial uses step-by-step sketches and photos created based on Tetsuo Kogawa’s design.

BUILDING THE TRANSMITTER

1. PREPARING THE COPPER PLATE

- Take the bare copper plate and cut off 1inch of material using a dremel tool or hacksaw.
- Use this material to cut out 6 square ½ in. x ½ in. pieces.
- Arrange the 6 pieces on the larger copper plate as shown in the image below…





****NOTE**** Be sure to arrange them so that all the component leads will be able to reach the squares. Look ahead to see what components will go where so you know exactly how to space them.

- Once you have them arranged, put a dab of hot or super glue on the bottom of each square and stick them in place on the copper plate.

2. ADDING THE 100uF CAPACITOR (the cylinder with “100uF” written on the side)

- Melt a blob of solder onto the two squares furthest to the right. To do this, apply your iron to each square to transfer heat for an extended period of time until the solder flows onto the surface.


apply blobs of solder


reheat solder blobs and put the capacitor into place

- Bend the legs out of the 100uf capacitor and straddle them between the two squares making sure that the leads are only touching the two small squares (not touching the ground plate).
- Cut the excess off of the leads.
- One at a time, re-heat the solder blobs and place the capacitor leads into them, allowing them to cool down until they stay in place.





*****NOTE***** - This capacitor is polarized meaning that it has to be facing in the appropriate direction. Make sure you solder the NEGATIVE lead to the LOWER of the two squares. The negative side has the shorter lead and a vertical stripe along the side of the capacitor.

3. ADDING THE .1uF CAPACITORS (the two discs with “104” written on them)

- These capacitors will be positioned between the upper and lower left most squares and the ground plate. Melt a blob of solder on these two squares and two blobs on the ground plate beside each. (Reference the pictures for exact positioning).
- Re-heat the blobs and position the capacitors accordingly as in step 2.





4. ADDING THE RESISTORS (10k and 27k)

- Solder the 10k resistor (brown, black and orange stripes) between the bottom left square and ground.
- Solder the 27k resistor (red, violate and orange stripes) between the two left squares.





5. ADDING THE COIL

- Cut about 4” of the magnet wire (24 AWG or close)
- Use the plug from your headphones to wrap the wire around. Make 5 turns.



- With the wire still wrapped around the headphone plug, take a small piece of sand paper and rub off the colored insulation of each end until the bare copper is exposed (If the copper is not exposed, you won’t be able to make a connection).

- Solder the coil into place bridging the two squares as seen below





6. ADDING THE VARIABLE CAPACITORS

NOTE Once the component leads start to pile up on each other on each square, it helps to add additional solder.

- The first variable capacitor will be soldered between the top square of the three that make up the bottom triangle and the ground plate.

- Solder the “nose” of the capacitor (the lead that is different from the other two) to the square, and the other two side leads to the ground plate.

NOTE You will have to bend the leads in a certain way in order to get everything positioned properly. Just play around with it till you get it.

- The second variable capacitor will bridge between top and right squares of the triangle. Only two leads are needed here so use your clippers to remove one of the side leads, leaving the nose and only one side. (See the pic below)



The variable capacitors soldered into place…





7. ADDING THE TRANSISTOR (MPSA18)

NOTE This transistor is sensitive to heat and can be destroyed by the heat from your iron. Be sure to follow the necessary precautions below. But don't worry if you do kill one, they are only ~$.10 a piece.

- The three leads of the transistor all do specific things and must go to the appropriate places. Here is a pic of the orientation of this transistor…

C=Collector B=Base E=Emitter


flat edge
C
B
E

- Each lead from the transistor will be soldered to the three different squares that make up the triangle, so you will have to bend the leads accordingly.
- The B lead (base) goes to the left square of the triangle, the C lead (collector) goes to the top square, and the E lead (emitter) goes to the right square, as in the image below.


B
flat edge
C
E

- Before you solder the transistor in place, you need to have a "heat sink" attached to protect it. This will draw some of the heat from the transistor to something else. To do this, simply take an alligator clip and attach it to the lead you are soldering…


place alligator clip between soldering iron and transistor to act as a heat sink

- Solder each lead in place attaching the clip lead to each one before doing so.





8. ADDING THE 1k POTENTIOMETER

- Put a bit of super glue or hot glue on the bottom of the potentiometer and stick it to the upper right corner with the leads facing towards the left of the plate.
- Take a small amount of stranded hookup wire and strip both ends. Solder one side to the upper most lead and the other side to the ground plate.
- Repeat the process by connecting the middle lead of the potentiometer to the upper most of the two right squares. Then connect the lower lead of the potentiometer to the right most square of the triangle.





9. ADDING THE INPUT WIRES

- Cut two small lengths (~4-5”) of your stranded wire and strip both sides
- Solder one of the wires to the ground plate (this will be the ground input from your video source)
- Solder the other wire to the bottom square of the two right squares. (This will be the signal input from your video source)





10. ADDING THE BATTERY INPUT WIRES

- Just like the last step, cut two shot pieces of wire and strip both ends.
- Solder one of the wires to the ground plate (this will be the negative input from your 9volt battery).
- Solder the other wire to the upper left square (this will be the positive input from your 9volt battery).





11. ADDING THE ANTENNA

- Cut about 2 feet of wire and strip one end.
- Solder the wire to the right most square of the triangle.


Ant.
~2ft long
9v
-
+
B
C
E
sig.
Vid In
gnd.



OPERATING

- Find a video source (DVD player, VHS player, iPod etc.) that has a composite video output.
- Use an alligator clip lead to connect the ground from your video source to the ground input of the transmitter. Using another alligator clip lead, attach the signal output from your source to the signal input of the transmitter.
- Use two more alligator clips to connect the positive and negative of a 9v battery to the positive and negative battery inputs of the transmitter.
- Turn on a CRT “tube style” TV and tune it to channel 2 or 3.
- Turn your potentiometer to somewhere around 50%
- Using a small screwdriver, tune the upper most variable cap slowly until you see the TV make a flicker or change.
- Tune the second variable capacitor until you start to see some strong signal coming through
- Tune the potentiometer and the two variable capacitors until you get the imagery you wan

Send any comments, questions or suggestions to yaktronix.online@gmail.com



WINDOM antenna 160/80/40/20/10 metri, W8GZ

OCFD (off center fed dipole)

download MINIRING Core CALCULATOR

Nel 1929 il Radioamatore Americano Lorenz Windom W8GZ progetto un antenna dipolo alimentata fuori centro il che consente di ottenere una IMPEDENZA quasi costante su TUTTE le bande Ham 160, 80, 40, 20 e 10 metri. Alimentando il dipolo "fuori centro" fa in modo che l'antenna possa essere utilizzata convenientemente, con ROS accettabile su tutte le bande, o meglio "armoniche pari" rispetto alla frequenza per cui e' stata calcolata. La WINDOM ha una impedenza tipica di 300 Ohm, adatta quindi ai TX operanti all'epoca, per poterla utilizzare con i nostri moderni RTX con uscita 52 Ohm, si interpone un trasformatore di impedenza Balun 6:1 per una impedenza di 50 Ohm, oppure un Balun 4:1 per una calata in cavo coassiale a 75 Ohm. Anche in questo caso potete realizzare il BALUN nei modi a voi piu' confacenti, in aria su supporto cilindrico plastico, su bacchetta di ferrite, oppure il classico arci conosciuto toroide rosso T-200-2. La WINDOM e' un classico nel mondo radioamatoriale, antenna facilissima da costruire ed ha il grosso vantaggio di poter operare tutte le BANDE RADIOAMATORIALI con un solo elemento RADIANTE, come radiatore, normalissimo filo elettrico da 1,5 mm. Software MiniRing Calculator per chi vuole calcolarsi da solo i BAL-UN o UN-UN con toroidi/ferriti/in aria by DL5SWB

Buona autocostruzione, 73 IVO I6IBE


bande 160/80/40/20/10 metri
OCFD (off center fed dipole)
BALUN 6:1
coax 50Ω
balun 6:1
OCFD (off center fed dipole)
Antenna WINDOM
ANTENNA WINDOM
I6IBE
2014


ISOLATORE
26,5 mt
13,1 mt
ISOLATORE
BALUN 4:1 6:1
Z=300 Ohm
versione
80/40/20/10 metri
coax 52/75 Ohm
all' RTX
ISOLATORE
53,1 mt
26,1
ISOLATORE
BALUN 4:1 6:1
BALUN 4:1 discesa CAVO 75 Ohm
BALUN 6:1 discesa CAVO 52 Ohm
versione
160/80/40/20/10 metri
Z=300 Ohm
I6IBE
ivo Brugnera
all RTX
coax 52/75 Ohm


16 spire bifilari filo 1,5 mm
su supporto plastico cilindrico 2,5 cm
presa alla 13ªspira (80%)
AVVOLGIMENTO BIFILARE
BALUN
6:1
alla
WINDOM
300 OHm
13ªspira
SO239
INGRESSO 50 Ω
Sbilanciato
I6IBE
alla WINDOM
160-80-40-20-10 metri
bilanciato
I6IBE Ivo
SO239 sbilanciato
BALUN 6:1


16 spire filo ∅ 1,5
su tubo plastica ∅ 2,5
AVVOLGIMENTO BIFILARE
BALUN
4:1
alla
WINDOM
300 Ohm
I6IBE
SO239
all'RTX
cavo RG59 75 Ohm
BALUN 4:1
alla WINDOM
160-80-40-20-10 metri
bilanciato
I6IBE Ivo
SO239 sbilanciato
cavo RG59 75 Ohm


ISOLATORE
misure 80/40/20/10
26,5 mt
13,1 mt
ISOLATORE
51,3 mt
26,1 mt
misure 160/80/40/20/10
I6IBE
BALUN 4:1 or 6:1
supp. CILINDRICO
16 spire BIFILARI
tubo plastica 3 cm
filo elettrico 2 mm
RTX
qualsiasi lunghezza
cavo 52 Ohm
cavo 75 Ohm
bocchettone
PL




Toroide T200-2
Filo RAME SMALTATO 1mm
I6IBE
I6IBE BalUn 6:1


11 spire BIFILARI
presa 9 spira


I6IBE BalUn 6:1


2ll2
WINDOM
I6IBE
I6IBE
SO 239
ALL'RTX
BALUN 6:1
Balun 6:1
per antenna
WINDOM
2ll2
WINDOM





Software for Radio Amateurs

mini Ring Core Calculator

Version 1.2

2005-06

Copyright: Wilfried Burmeister, DL5SWB
Freeware

THE END


Calculating Resonant Circuits
L
C
f
µH
pF
MHz
kHz
Resistance of Copper Wire
Length
D
Resistance
m
mm
Ω
Determine AL and µi
Turns
Inductance
wound
measured
Calculating core parameters
OD
ID
h
Coating
Ae
le
mm²
Σ(le/Ae)
1/mm
AL =
nH/N²
µi =
xxx
mini Ring Core Calculator 1.2
Info
Tools
Language (Sprache)
Units
Help
Cu
m
in ft
Iron Powder T ..-..
Ferrite FT ..-..
SIFERIT
Ferroxcube
Unknown Cores
Air Cores
Calculating number of turns (solenoid)
Inductance
Length
Turns
Length (wire)
cm
max. D (wire)
Calculating inductance (solenoid)
Inductance of straight wire
nH
=>
XXX
Software for Radio Amateurs
mini Ring Core Calculator
THE END
OK
Metric Conversion
inch <-> meter
in
American Wire Gauge -> mm
°F -> °C
°F
°C

Resistance of Copper Wire: @ 20 °C

Determine AL and µi: Coating 0.00 mm

Inductance of straight wire: ● with skin effect ○ without skin effect

mini Ring Core Calculator
Version 1.2
2005-06
Copyright: Wilfried Burmeister, DL5SWB
Freeware

Metric Conversion: # 20 AWG 0.031959 in = D = 0.812 mm



10 MILLIWATT QRSS BEACON TRANSMITTER FOR 30 METER KEYED BY A WEBBROWSER

(2010)

KLIK HIER VOOR DE NEDERLANDSE VERSIE



The beacon transmitter of 10 milliwatt with Light Dependend Resistor (LDR).
The beacon transmitter is keyed by the LDR.

Experiments with very low power QRSS beacon transmitters
There is a group enthusiastic radio amateurs that is doing experiments with very low powers. That is possible by using a low CW speed (QRSS speed). Most of the activities can be found in a band of only 100 Hz, namely 10140.0 to 10140.1 kHz in the 30 meters amateur band. Signals are decoded with a special software program. My beacon transmitter could only be frequency modulated with a square wave with a frequency shift of 4 to 5 Hz. But for the serious work, in morsecode the call, QTH locator or transmit power had to be transmitted. But how can that keying with morsecode be realized?



The LDR is placed in front of the monitor screen. The white square
on the screen blinks on/off in the rhythm of the morsecode.
This is done by a HTML program running in a webbrowser.

Keying with a webbrowser

It was not easy to find a simple solution for keying the beacon transmitter with morsecode. Mostly, a micro controller circuit is used. But how can you key the transmitter with a PC? A printerport and RS232 port are history. It can be done with a special interface for the USB port. But which software do you have to use for that? And that works of course only with Windows-XP, but not with Vista...

Then I had the idea to use software that you can find on every PC, namely a webbrowser! We make a simple HTML program that does blink a square on the monitor screen white/black in the rhythm of the morsecode. In front of that square, we place a light dependent resistor that keys the beacon transmitter. That works for all operating systems, Windows 95 to Windows 7 and newer, Linux, MAC-OS, the webbrowser controls everything! And we do not have to buy or hack and install software. And everyone can modify the program with a simple ASCII text editor (Notepad) to his own demands. It does not have to be a fast program and the timing is not critical. A dot lasts 3 second and a dash 9 seconds. Is that dot or dash a little longer or shorter, nobody will notice that.



QRSS beacon morse code transmission
Dotlength (>500): 3000 ms

Morse:

```
.--. .- ..--- --- .... ....  .---- ----- -- .--
-
```

The HTML program running in a webbrowser, here Google Chrome.
The white square blinks on/off in the rhythm of the morsecode.

The program

The program is using Javascript, that has to be enabled in the webbrowser. But normally that is already the case, most HTML applications on internet do use Javascript.

Click here to see the HTML program running, that will make clear to you how it works.

Click here to download the zipped version of the HTML program.

Click here to download a zipped version that transmits in time synchronized 10 minute intervals.

You can modify the program by means of an ASCII text editor like Notepad. In one of the first lines after "Data", you have to fill in the desired morsecode. And after dottime the keying speed in milliseconds (normally 3000 ms for a dot). By means of style sheets, two squares are defined, a white square and a black square. And by means of a timer interrupt routine named "function NewTime()" and the function "innerHTML" for modification of a part of the screen, everything is controlled. After that the morsecode is transmitted, the HTML program is loaded again and run by the webbrowser. During a transmission, it is possible to modify the HTML program. I can do that from any location, as together with the webbrowser, a FTP program is also running on the PC. But there are other possibilities for that. And on the PC, also the program ARGO with simple receiver is running, so that I can see from a remote location if everything is going well.


+5V
120k
10140kHz
100p
100p
BC547
120k
1k8
10p
74HC00
1
2
3
4
5
6
&
NAND 1
NAND 2
1M
33k
Testpin 2.5V
47nF
NAND 5
NAND 6
NAND 7
NAND 8
270
270
270
270
22
(0 for 0.1-10mW)
1nF
1nF
(820 for 0.1-10mW)
Shift
1/10mW
(22k)
1M
12
13
11
9
10
8
NAND 3
NAND 4
120k
330k
100µ-200µ
Cs
(100p)
Cp
(47p)
BB112
NTC
68k
150k
1M
68k
8k2
+5V
74HC00
0.68µH
0.68µH
1k
330p
680p
330p
+5V
(33k)
10k
10k
LDR
1µ
BC547
10µ
+5V
7805
100µ
0.1µ
0.1µ
100µ
1N4007
12
+12V

Select the value of the 22k resistor for 5 Hz shift
Select the value of CS and Cp for temperature correction
Exchange the NTC and 68k resistor for a negative temperature correction
Select the value of the 33k resistor for proper operation of the LDR
Connect pin7 of each 74HC00 to ground
Connect pin14 of each 74HC00 to +5V
Connect a capacitor of 0.1 uF between pin 7 and 14 of each 74HC00

Circuit diagram

big diagram

Description of the circuit diagram of the transmitter
A crystal oscillator with a BC547 transistor is buffered by NAND1 and NAND2 and amplified by NAND5 to 8. The circuit with NAND3 and NAND4 is a square wave oscillator. When the switch is opened, the transmitter is frequency modulated by this square wave. But also in amplitude. During the positive half of the square wave, NAND5 to 8 are all switched on and the transmit power is 10 mW. During the negative half of the square wave, only NAND8 is active and the transmit power is only 1 mW (or 0.1 mW, depending on the used resistor values). When the switch is closed the transmitter is keyed by the LDR. The capacitors of 1 uF and 10 uF do suppress the flickering of the screen and other interferences.
During the transmission of a dot or dash, the transmit power is 10 milliwatt. During spaces, the transmit power is 1 milliwatt (or 0.1 mW, depending on the used resistor values) and the transmit frequency is lowered with 4 to 5 Hz.

Temperature stabilization
The frequency has to be very stable. It is quite difficult to adjust the beacon transmitter on a frequency of 10140.0 tot 10140.1 kHz and to avoid drift due to temperature changes. A temperature correction circuit was made with a NTC resistor and a varicap. The drift could be reduced considerably. For a positive frequency drift correction, you have to connect the NTC in accordance with the diagram. For a negative correction, the NTC resistor and 68k resistor have to be exchanged. Of course you can also take a NTC resistor with a different value. Exchange the 68k resistor then for one with the same value as the NTC. Increasing of Cs and reducing Cp increases the correction, reduction of Cs and and increasing of Cp does reduce the correction. Finding the correct value is done by of trying out various values of Cs and Cp while cooling down and warming up the transmitter.

The Light Dependent Resistor (LDR)
It is important to keep a distance of at least 0.5 cm between the screen and the LDR. Otherwise, the high voltage of the screen can disturb the LDR. The flickering of the screen has also to be filtered out. And you have to avoid interference from daylight by screening the LDR and screen with a piece of cardboard or so. By using a LDR we have a full galvanic isolation between the PC and the 10 milliwatt beacon transmitter! Of course you can modify the program so that you have a second square with second LDR to switch other things like power or switching between transmission and reception.



The circuit mounted in a plastic housing on an unetched piece of PCB.
An extra coil in series with the crystal was necessary to tune to the correct frequency.

Construction
The circuit is mounted in a plastic housing on an unetched piece of PCB. That is simple, quick and it is easy to change the circuit. That last advantage is very important, the final design was modified considerably. The transmitter is supplied by an AC/DC adapter.

Results
It is a strange experiment. The 10 milliwatt transmitter is switched on and... The needle of the power meter does not move! And it is even a QRP power meter! But how do you get reception reports? Quite soon I received an e-mail with screenshot from Dusan, YT1DL. Dusan many thanks, with this report the experiment was already 100% successfull! Not only the high shift with dots and dashes with 10 milliwatt was visible, also the lower shift with pauses between the dots and dashes of 1 milliwatt was visible! Dusan does not use the program ARGO but Spectran.



Spectran Version 2 (build 216) - Audio source : Line 2 (Virtual Audio Cable)

20:05:03 18.3.2010

Peak at 120.79Hz (-37.9dB) 20:04:57

Spectran
Setup
Mode
Palette
Filters
Capture
About
○ Record
Ticks : ○ 1 ● 10 ○ 30 ○ 60 seconds
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
-110
-120
-130
100
150
200
250
Vol
Gain
Speed
Base
Hz
Average
Humid
Denoiser
BandPass
BandRej.
CW Peak
Auto brig.
PassThru
180
170
160
150
140
130
120
110
100
90
Contrast
Enable
Spectran, by I2PHD and IK2CZL
Compact View
Stop
Show Controls
Exit

Reception report from Dusan YT1DL, received by e-mail.

Not only the 10 mW, but also the 1 mW shift (pauses, 4-5 Hz lower) is visible.

But there are other possibilities to collect reception reports. There are amateurs who have their receivers coupled to internet. The reception results are continuously refreshed. You can see these results on internet (Search via Google for "QRSS grabbers"). The results here below are obtained via these QRSS grabbers. Totally, the beacon transmitter has transmitted during 3 days.



Reception report of the QRSS grabber of G4CWX in Bristol.
Also here the 1 mW shift (pauses, 4-5 Hz lower) is visible.



Reception report of the QRSS grabber of I2NDT in Bergamo.
Also here the 1 mW shift (pauses, 4-5 Hz lower) is visible.

BACK TO INDEX PA2OHH

A 9:1 Balun For Your End Fed Antenna

End-Fed antennas do have their place in radio and other communications work. Like everything else, antennas come in many forms and flavors. It's up to the designer to select the best design for the job at hand and to utilize that design in the most efficient way.

* * * A Bad Rap? * * *

- End-Fed antennas are NOT balanced systems; but neither are verticals, ground planes, discones, windoms, zepps, Marconis, half-slopers, et al. Additionally, the low-impedance antenna port of your transmitter/receiver is not balanced.

- End-Fed antennas are noise magnets. Really? That's because most hams and SWL-ers don't bother to interface them properly.

- End-Fed antennas have wild impedance swings. So do all antennas, but not at the design frequency - there, at the design frequency, the terminal impedance is quite predictable.

To make the best use of an End-Fed antenna, it should be fed with a transformer. Here are some photos of one of my 9:1 baluns. However, when using it with an End-Fed antenna it is wired as a (so-called) "unun" transformer (unbalanced to unbalanced). The raw End-Fed antenna will go through impedance swings as high as 5K Ohms, or more, at even multiples of its 1/4 wavelength design frequency. At every odd multiple it will be at a more civil impedance of between 36 and 90 Ohms. Using the transformer, the magnitude of the impedance swings is greatly reduced. This is due, in part, to the ratio balancing of the transformer's turns (windings), and to a few complex reactance and other physics attributes that I won't try to cover here. Additionally, the unun will eliminate (virtually) all "common mode" currents on the feedline. This is important for eliminating the pickup of local electrical noise from homes and power distribution lines. The coax, being connected to ground through a DC path will eliminate all but the differential currents ... pretty cool, huh? Finally, since the antenna is connected directly to Earth ground through the secondary of the transformer, static buildup cannot occur - the antenna is a dead (DC) short to ground. This is important to sensitive, solid state radios.

The 9:1 transformer provides: 1. a much flatter broadband impedance response, 2. a static elctricity-free antenna system (no buildup), 3. common mode noise immunity (if space wound as shown).

An Important Note on this Design

I selected the separate (spaced, opposite or complementary) winding format over bifiler or twisted-pair winding in order to minimize the coupling effects of stray capacitance between the primary and secondary windings. This symmetry is important to the quality of common mode noise rejection, which is one of the balun's attributes - and should be exploited as such.

Construction of the 9:1 balun/unun: I used an old plastic box and a type 75 toroid core. My windings, in this case, are for transmitting, using No. 10 and No. 14 solid copper wire. For SWL-ing a smaller core can be used along with No. 18 or smaller wire. The turns ratio is 3:1 for a transformation of 9:1. The impedance is the square of the turns ratio (Z=T^2). The antenna terminals are brass speaker terminals and the low impedance side is a standard SO-239. The grounds of the two windings have been isolated but, can be strapped together by the screw contacts (shown in the top photo). The entire assembly was potted with marine fiberglass. Note that I also added a hanger strap for convenience.

Testing the 9:1 balun/unun:

Properly designed and constructed toroid transformers are not lossey!!!

On the test bench with a 52 Ohm source and a 450 Ohm load the transformer shows a loss of no more than 0.6 dB with about 0.45 dB being average, and the low reading of 0.2 dB.

Installation of the 9:1 balun/unun:

The End-Fed is connected to one terminal of the "high" winding and the other terminal is connected to a good "EARTH" ground. One or more copper rods or pipes driven, at least, 4 feet into the earth near the dwelling entry point (2 or 3, is better, being spaced about 4 feet apart). The coax is connected to the SO-239 and fed to your radio. The best place for the balun for receive-only antennas, is mounting it directly to the primary ground rod and keeping the ground conductors as short as possible. Use a heavy copper wire (not steel or aluminum) or, better yet, low inductance conductors which have an *aspect ratio* that is other than "round." The higher the aspect ratio, the better, like flat copper braid or copper sheet metal strap. This, in effect, will give you an inverted "L" antenna (of sorts), depending on the length of the vertical element. For transmitting, it's best to place the transformer at the actual feed point, up, and away, from possible contact by humans and pets. Of course, extra care must be taken to properly ground the balun by running the ground conductor down the tree, house, etc. If your antenna is attached to your tower and ground-BONDED to the household grounding system, as mine is, then you are home free ... just be sure your tower itself is properly grounded ... *you'd be crazy if it wasn't suitably grounded the day you put it up!!!*

A word about grounds.

We are talking about RF (signal) ground on this page. These are the grounds that provide the antenna counterpoise (true ground plane), and afford static bleed to NOT allow lightning's near field (DC component) induction, or just general DC static electricity buildup on he wire, to pass along to your radio. *A balun will not stop the RF component of near-field strikes, although the inductive component of the windings and ferrite will lessen its amplitude.*

These grounds ARE NOT about electrical service safety. Smart people tie their radio grounds to a common point "service ground" ("BONDING") with heavy gage wire, I do - and this is fine if ALL the other ground measures discussed here have been met. Simply put: electrical service ground is NOT a substitute for a good RF Earth ground, which is required for a good antenna system. In fact, your service ground will probably be a very bad RF ground and a good source of (household / neighborhood) noise, if not outright dangerous to you and your equipment. *Remember, the "neutral" wire in your circuit breaker box travels outside of your home and all around the neighborhood ... it's a noise magnet and (going from pole-to-pole) a potential* *lightning rod!!!* Best to consult with a licensed electrician about "bonding" the entire household, IE: electrical service, cable service, telephone lines, and RF grounds.

Technically speaking, that addition of outside antennas may modify or invalidate you home's fire insurance coverage. If in doubt, contact your insurance agent. Also, consult with a licensed electrician to be sure you conform to all NEC and local electrical codes for the proper BONDING of ALL service grounds, and ground systems, within and about your home.

RF Grounding With a Balun Feed

Transformer coupling and properly grounding your end-fed antenna will offer you four benefits: (1) Greater signal levels across a larger bandwidth (impedance smoothing), (2) Less electrical noise pickup from local sources (common mode rejection), (3) Greater protection to your equipment (constant static bleed and near-strike (DC only) shunting). Shown here are 4 possible ways to connect your transformer (balun wired as an unun) to the antenna and the radio. (Note that the first example uses a coax connector at the transformer and the subsequent figures show the coax as being hard wired - both are acceptable and are options for your particular requirements.) The sketches are pretty much self explanatory. Technically, they are shown in the order of functional preference.

If you have trouble reading these sketches, you may "right click" them to your clipboard and paste them to a .jpg viewer. Please give full credit if reused elsewhere.

Here is a graphical illustration of a typical installation. The details will be different, but the principles are the same. The primary point is to mount the xfmr as close to the system ground as possible. Mounting it directly to the first ground rod is text book-ideal. An alternate would be to eliminate the vertical component of the antenna and mount the xfmr to the insulator above it and run a heavy ground up to it. This will depend on how much the vertical wire is exposed to near-field electrical noise from your home.

Here is an example of good RF "ground farm" practice. As opposed to many socio-religious beliefs, in this case, more is better! There will be a point of diminishing returns, but generally speaking, one ground rod is not going to be optimal. Experimental and empirical testing is the only way to determine what will be best for you. You may get a relative ground conductivity test as shown below. Most electrical service entry points are grounded to the fresh water (cold water) feed pipe. Homes with plastic well pipes will have some other code-complient grounding system. Either way, you should consider "bonding" your ground farm with the house/utility grounds. (And you'll need a licensed electrician to properly perform this kind of system upgrade.) Regarding RF grounding: some soils will indicate a few dozen ohms/foot and others will offer thousands of ohms. You'll have to do some measurements with an ohm meter to get a "feel' of what your ground farm will be like. But remember, this is only a "test indication" that will give you a "feel" of your soil quality. You will also learn how conditions change with seasons and weather.

Disclaimer: Remember, you are dealing with earth (signal) grounds only. Never tamper with, or intrude upon, or compromise your electrical service grounds in any way. If in doubt, consult your utility company and/or a licensed electrician for bonding information. Also, lightning is completely unpredictable. A direct strike or a close near-strike may damage your equipment, start fires, or cause personal injury, or death. Use common sense and be careful !


RADIO
OUTSIDE GND. ROD
COAX TO RADIO
SHACK GND.
EARTH
METHOD
1. ALL GNDS HOME RUN TO EARTH.
2. XFMR. COMMON GND. TO EARTH.
3. TERMINAL GND. (AT SHACK)
4. LONELY GND. (NOT SAFE, PROB. NOISY)

~ 9:1 UNUN TRANSFORMER ~
CONNECTION PERMUTATIONS

NOTE THAT THESE ITERATIONS ARE LISTED BY THE SAFEST FIRST & LEAST SAFE LAST, (LIGHTNING ATTRACTION). (PERFORMANCE/NOISE REDUCTION IS PROBABLY IN THE SAME ORDER.) SHACK GND. SHOULD BE AS SHORT & DIRECT AS POSSIBLE — FLAT COPPER CONDUCTOR IS BEST (BRAID, STRIP) BUT HEAVY WIRE USUALLY SUITABLE. (12GA COPPER SHOULD BE MIN. SIZE.)

4·18·05 N1KPR


ELIMINATE "LIGHTNING-ATTRACTING" STATIC BUILD UP & REDUCE COMMON MODE ELECTRICAL NOISE BY PROVIDING A CONTINUOUS BLEED TO GROUND THROUGH A 9:1 TRANSFORMER.
SCREW EYE/HOOK
INSULATOR
END FED (INV. "L")
450-600 Ω
(THEORET.)
PULLEY
9:1
TRANSFORMER
-UNUN-
COAX TO SHACK 50-75 Ω
GROUND ROD
COUNTER WEIGHT
BOND THE UNUN GROUNDS DIRECTLY TO THE GROUND ROD OR GROUND SYSTEM
N4YR 3 05

TYPICAL "GROUND FARM" INSTALLATION


COPPER WATER PIPE (½, ¾, 1")
OR BRASS, COPPER, BRONZE ROD
→ NOT COPPER CLAD STEEL ←
12 GA. COPPER
OR LARGER
PIPE WITH
1/4" HOLES
EVERY 6"
'D'
'D'
1.5 × D

D= FROST LINE ++ (MIN: 36", TYP: 48"–60", BEST: 96")
DIMENSIONS ARE GUIDELINES ONLY
DEPENDING ON SOIL CONDITION, 2–3 MAY BE SUFFICIENT
SANDY & CLAY SOIL USUALLY CONTAIN LESS ELECTROLYTES.

NLKPR 5/65


~ SOIL CONDUCTIVITY ~
SERVICE ENTRANCE
ELECTRICAL SERVICE
ELECT. METER
GROUND RODS
COLD WATER FEED FROM ST.
OHMS
OHMS
N1KPR 6.05

The above sketch is just for illustrative purposes to point out that soil is not a very good conductor of electricity, no matter where you live, and no matter what kind of chemicals you "seed" the soil with. The above test will give a good indication of just how resistive soil can be and an interesting exercise to conduct during various seasons and/or weather conditions. Of course DC ohms measurements are pretty meaningless at RF frequencies where electrical current flow behaves much differently, but you will gain a "feeling" for what grounding is all about and why *Ground Bonding* is so important

Magnetic Long Wire UnUn 9:1



These are usually called a *Magnetic Longwire Balun*. Its really an impedance transformer (9:1) to feed a high impedance long wire (~450 ohm), down to a 50 ohm unbalanced coaxial input. I have heard them called an UnUn which seems more appropriate. I almost bought one of these for around £30, but then decided to make one. The toroid is a T130-2 Iron Powder core, with 3 x 9 turns of 18SWG enammeled copper wire, and the connections can be seen below.

The T130-2 Torroid Core




450Ω
To Wire Antenna
A1
B1
C1
A2
B2
C2
50Ω
To Radio
or Tuner
Ground Rod or
Counterpoise
9:1 UnUn - John M0UKD


GND
NC
Long Wire
50 ohm
Input





Long wire and Un-Un part 1

I have been playing with a 4:1 unbalanced-unbalanced transformer and a long wire. The theory is that the Un-Un reduces the impedance at the feed point to a point that your internal ATU can cope with.

My first tests were with my 85ft end fed and were not too encouraging. These are the SWR results I got using an MFJ analyser:

1.9MHz >30
3.6MHz: 10
7.1MHz: 3.0
10.1Mhz: 5.7
14.150MHz: 2.4
18.1MHz: 2.9
21MHz: 2.6
24.93MHz: 2.0
28MHz: 5.7

from these you can see that the rig would be able to match the long wire on five bands. On test it would not match on 80m, although when run as a W3EDP through my external ATU it works well.

I then wound a 9:1 Un-Un (sometimes referred to as a magnetic long wire Balun) and tried again. Here are the results:

3.6MHz – SWR 28:1
7.10MHz - SWR 1.9:1
10.1MHz – SWR 3.6:1
14.2MHz – SWR 1.9:1
18.14MHz – SWR 3.8:1
21.2MHz – SWR 2.5:1
24.9MHz – SWR 3.5:1
28.5MHz – SWR 8.6:1

While 40, 20 and 15 metres were quite good I can't really recommend this as a multiband solution.

In all then, it is too long and not really worth playing with.

Long wire and Un-Un part 2



In the next round of tests I used the same 9:1 Un-Un wound using PVC covered cable and a T200-2 toroid. Note in the photograph that the PVC tape is only used to keep the turns neatly arranged.

If you want to build your own follow these instructions:

Building a 9:1 unun

To understand how to construct an unun lets build a 9:1 version. You will need a T-200 (red) toroid and three pieces of wire, each 24 inches (60cm) long . It will also help if you a small plastic box with an SO239 socket mounted at one end and with two wing nuts or mounting posts at the other. In the UK you can buy a small plastic box from Maplin which is watertight with a rubber seal, yet inexpensive.

It will help if the wires are different colors, although that isn't critical if you have a multimeter available. It just makes it a lot easier to follow these instructions.

For the sake of this explanation I'll assume that you are using green, red and black pieces of wire.

Put the three pieces of wire together and wind them carefully onto the T130-2 toroid. Place the wires (left to right) green-black-red, and wrap nine turns on to the toroid.

Try not to let the wires overlap.

You should end up with a toroid with three wires extending from the left winding and three wires extending from the right.

Now twist and solder the left black wire with the right red wire. This can be covered with PVC tape once complete.

Now twist the left green wire with the right black wire. Strip the ends of the two wires, twist and solder them together leaving the length about 2” long from the toroid.

Finally trim and strip the remaining right green wire and solder another 5” piece of green solid wire to it.

Now take the left green wire and right black wires that you twisted together and connect them to the center pin of the SO239 socket – this is the input side and will connect to your radio via a length of coax.

One of the green wires is now soldered to the ground connection of the SO239 socket. The other end of the wire you soldered on (which is connected to it) becomes the earth connection for the unun and typically goes to a ground stake and ground radials.

This leaves the remaining red wire which connects to the other wingnut and will become the connection for the antenna.

If you are worried about the wires unraveling you can either use PVC tape to hold them in place or plastic cable ties.

So how do we use an unun? Let’s look at a typical example.

This time I erected a 10m high fishing pole and attached a 65ft quarter wave antenna for 80m in an inverted L fashion. That is, 10m up and then 9.8m out to the nearby summerhouse.

This was arranged away from the house and fed with 12m of RG8 coax, a single earth stake and two 20ft radials at the feed point..

Here are the SWR readings at the end of the coax:
3.5MHz – SWR 3:1
3.65MHz – SWR 4.2
3.8MHz – SWR 5.9
7.10MHz - SWR 13.6:1
10.1MHz – SWR 2.5:1
14.2MHz – SWR 3.3:1
18.14MHz – SWR 1.8:1
21.2MHz – SWR 2.4:1
24.9MHz – SWR 1.9:1
28.5MHz – SWR 1.2:1

From this you can see that by shortening the wire to 65ft from the original 85ft you gain 80m, but lose 40m. The rig (FT2000) would quite happily tune seven bands with its internal ATU.

Here are the quick comparison results against my 80m Windom and parallel-fed dipoles in the loft for 40m, 20m, 17, and 10m.

80m
Not as good around the UK as the Windom - probably due to the maximum current being in the vertical section. Modeling shows the antenna to be down about 10dB on a low dipole.

30m
Lithuania similar. Other EU and Italy similar. Bulgaria down 2 S points

17m
Similar – inverted L has slight edge at times. Slightly noisier

15m
Better than Windom by about 1 S point.

10m
Much better than Windom, dipole and mag loop around Europe via Es, by about 2 S points. Slightly more noise (+ 1 S point).

From this I can see that I need to do more tests, especially on 20m, but for an all-in cost for the antenna of about £15-£20 it shows promise. If you have a tree then the up and out idea with a 65ft wire looks quite good. A way to get 40m back would be to put a 40m trap in the wire at the 10m mark.

HyEndFedAntenna
Hy End Fed ANTENNA
Multi-Band
40M / 20M / 10M
Load: 200W PEP
WWW.HyEndFedAntenna.nl
MADE BY PA3RK & PA3EKE
Hy End Fed ANTENNA
Multi-Band
80-40-20-(15)-10
Load: 200W PEP
WWW.HyEndFedAntenna.nl
MADE BY PA3RK & PA3EKE
3 Band
5 Band
made by PA3EKE & PA3RK

Type	Length	Power	Bandwidth /SWR
M O N O B A N D			
Monoband 40 meterband	20,0 mtr	300 Watt PEP	200 kHz / < 1:2.0
Monoband 30 meterband	14,1 mtr	300 Watt PEP	200 Khz / < 1:1.5
Monoband 30 meterband	14,1 mtr	300 Watt PEP	200 Khz / < 1:1.5
Monoband 20 meterband	10.0 mtr	300 Watt PEP	300 kHz / < 1:1.5
Monoband 17 meterband	7,87 mtr	300 Watt PEP	400 kHz / < 1:1.5

Monoband 10 meterband	5,0 mtr	300 Watt PEP	700 kHz / < 1:1.5
Monoband 11 meterband	5,25 mtr	300 Watt PEP	700 kHz / < 1:1,5
QRO monoband 40 mtr	20,0 mtr	800 Watt PEP	200 kHz / < 1:1.6
QRO monoband 20 mtr	10,0 mtr	800 Watt PEP	350 kHz / < 1:1.6
Super QRO mono 40mtr	20,0 mtr	2500 W PEP	250 kHz / < 1:2.0
Super QRO mono 20mtr	10,0 mtr	2500 W PEP	300 kHz / < 1:1.5
MULTIBAND			
Multiband **40, 20, 10 mtr** **Tri Band**	11,85 mtr	200 Watt PEP	40m 100 kHz / < 1:2.0 20m 300 kHz / < 1:1.5 10m 500 kHz / < 1:1.5
Multiband **40, 20, (15), 10 mtr** **Four Band**	20,0 mtr	200 Watt PEP	40m 200 kHz / < 1:1,5 20m 300 kHz / < 1:2,0 15m 450 kHz / < 1:3,0 10m 1000 kHz / < 1:2,0
Multiband **80,40,20,(15), 10 mtr** **Five Band**	23,0 mtr	200 Watt PEP	80m 100 kHz / < 1:2,0 40m 200 kHz / < 1:1,5 20m 300 kHz / < 1:2,0 15m 450 kHz / < 1:3,0 10m 1000 kHz / < 1:2,0
ALLBAND			
Allband (line Iso recommended) **160mtr ~ 6mtr**	7m>52m	200 Watt PEP	160m~6m +/- /<1:3
Line Isolator			

The matchboxes for the 3, 4 and 5 HyEndFed Multibanders have the same size.

The difference is the length of the wire and the size of the coil. The 4 band HyEndFed multibander has no coil in the antenna wire.


HY END FED
ANTENNA
Freq: 14.2 MHz
Load: 300W PEP
WWW.HyEndFedAntenna.nl
MADE BY PA3RK & PA3EKE
HY END FED
ANTENNA
Multi-Band
40M / 20M / 10M
Load: 200W PEP
WWW.HyEndFedAntenna.nl
MADE BY PA3RK & PA3EKE
Monoband
Matchbox
Multiband
Matchbox

HyEndFed
Antenna
NN2X
www.HyEndFedAntenna.nl
pa3eke & pa3rk

HyEndFedAntenna
3 Band
5 Band
made by PA3EKE & PA3RK

Monoband
HyEndFedAnte
HY END FED
ANTENNA
Freq: 14.2 MHz
Load: 300W PEP
20300
WWW.HyEndFedAntenna.nl
MADE BY PA3RK & PA3EKE

HyEndFed
Antenna
Freq: 7.1 MHz
Load: 600 - 800 Watt PEP
Single wire length 20,0 M, no grounding needed
40800
Made by PA3RK & PA3EKE
WWW.HyEndFedAntenna.nl


HyEnd AllBand Antenna System
160m t/m 6m band
Impedantie aanpassing unit
Antenne lengte tussen 7m en 51m
Coax lengte minimaal 10m
Line Isolator, onderdrukt ruis en storing
Fijn aanpassing mbv (interne) tuner. SWR op de meeste banden < 1:3

Building a Dummy Load

and

Measuring Power Accurately

by Ken, K4EAA

Building the Dummy Load

This is a take-off on a Dummy load that I've built in many different forms over the years. It uses a number of non-inductive resistors in parallel to achieve 50 Ohms over a wide frequency range. It is submerged in oil to allow somewhat extended operation during tuning or repair procedures. The advantages are: (1) It's cheap, (2) It provides a very pure 50 Ohm resistive load through 30MHz and beyond, (3) You can easily add power measurement and rig testing capability.

This one is conservatively designed for rigs that have power output levels up to 130W, such as the Kenwood hybrid lineup. I built it into a one-quart paint can, readily available at Ace Hardware for about 89 cents. I've used it for about a year now. A few hundred of your service rigs that you have sent to me have been loaded up into this dummy, and it is still like the day it was built. I know, because I had to take it apart to take these photos! It still measures 49.9 Ohms, even after all those rigs, all that power!

Note: The normal failure mode for resistors is to go UP in resistance value. If you think you have "fried your dummy," check it's resistance value - If it is much higher than 50 ohms, you have successfully cooked it. This dummy load will be very hard to destroy.

The parts required to build it are the Ace Hardware one-quart paint can or similar, twenty 1K 3W metal film or metal oxide resistors, a small brass sheet, also available at Ace, and an SO-239 connector, preferably single hole mount. Mine was built with a BNC connector, because all my home-brew rigs use BNC, but you'd probably find it more convenient using the SO-239, for your PL-259 plugs.

To add the optional power measurement capability, you'll also need a pair of red and black banana jacks or binding posts, and a BAV21 signal diode or similar, 7 cents quantity one at Mouser.

Construction Details

Drill a hole in the center of the paint can lid that will accomodate your connector. Cut out two pieces of brass sheet using tin snips to a size that will easily fit into the paint can. It's quick to just cut two squares and the snip the corners off, forming an approximation of an octagon. Stack these brass octagon sheets and drill 20 holes staggered around the periphery. Nothing is critical, you simply want to keep the resistors spaced apart a bit in the oil bath. After drilling the brass sheets, including a hole for your SO-239 connector in the center at the top, and a small hole for the lead for the center conductor on the bottom sheet, you can solder the resistors in place.

Note on easy assembly - Solder all 20 resistors to one plate, and then, starting at one corner, and working toward the opposite corner, cut the lead lengths starting from your minimum length, to progressively longer as you work towards the opposite corner. This will allow you to insert a few leads at a time as you combine the two plates. If they are all the same length, it will be very hard indeed to thread the 20 resistor leads into the bottom plate! You can find the resistor kit for sale **HERE**

Here is a photo of a completed assembly connected to the paint can lid.



Here is another picture of the assembly, showing the connector and the optional binding posts. I used a BNC connector, but you probably want to use an SO-239.



For those of you that wish to add power monitoring capabilities, you have to add two binding posts by drilling two additional holes, and mounting the posts. The following picture shows two 1N4148 signal diodes wired in series from the center conductor to the red binding post. I recommend the BAV21 250V signal diode. I used the two 1N4148's after checking their reverse breakdown, because I had lots of them. The "goop" around the base of the binding posts is some silicone bathroom caulk added to keep the oil from weeping through the mounts. The black binding post simply attaches to ground.



Next, we fill the quart paint can with mineral oil, which is a safe (You can actually drink it! - No PCB's for our dummy!), inexpensive, and readily available. The mineral oil works very well for conducting heat away from our resistors - It enables us to use 60W worth of resistors safely with a 130W rig.

Mineral Oil, U.S.P.
Lubricant
Laxative

Lastly, we complete assembly by attaching the lid to the mineral-oil filled paint can.

Now we'll find out how to use the optional diodes and binding posts that we've included in the dummy load..

Measuring Power Accurately

The signal from your transmitter or transceiver is an almost perfect sine wave. We know this because the harmonics are at least 40 dB down from the carrier. When we measure the peak voltage from the detector (the BAV21), we are measuring within one percent of the true peak value of our carrier, not including the diode drop; we will add that back in later.

For power measurements, I recommend that a 0.01uf disk ceramic of at least 250V rating be connected between the binding posts. This will charge to the peak voltage applied to the 50-Ohm load, less the diode drop. You can then measure this voltage with your DVM.

Let's assume you measure 99.6V with your DVM. Add 0.4V for the forward drop across the BAV21 for a total peak voltage reading of 100V. The diode drop is a constant, always add 0.4V to your reading! (*This assumes you are using a DVM or scope with an input impedance of 10 Megohms. For 100V DC, the forward current will be 10ua, for a forward drop of 0.4V*)

Since this is a peak voltage, we need to divide by the square root of two to get RMS voltage. Take your calculator and divide by 1.414.

100 divided by 1.414 equals 70.72 Vrms.

To calculate power, we take the RMS voltage, square it, and divide by the load impedance, which in our case is ALWAYS 50 Ohms!

(70.72)^2 / 50 = 100W

So the output power, dependant on the accuracy of your DVM, is nearly 100W. If your DVM is accurate, say within 1% on DC voltage measurements, you have nailed your rig's output power within 2%, or 2W!

That's good. Consider a Bird Wattmeter. Their specified accuracy, when new & calibrated, is 5.0% of full-scale when the measurement is at 1/2 scale. So, for example, a 200W element used to measure the 100W output of your rig can fall within 10W, so your 100W rig might measure 90w to 110W and still be within the calibrated accuracy specification. That's 20W of ambiguity. On the other hand, when power is measured by looking at the peak voltage, accuracy is a function of your DVM accuracy, plus the distortion in your output signal, the total of which may be on the order of 2% - - That's a 98W to 102W measurement, substantially more accurate!

One More Time

We'll do this once more, just for drill. Assume you measure 49.6V across the 0.01uf capacitor. Add 0.4V for the diode drop, for a total of 50V peak. Divide by the square root of 2, or approx. 1.414. That gives us about 35.4Vrms. Square and divide by 50 Ohms, and we get 25W. Half the voltage, one-fourth the power.

If you place your power meter inline while you are taking this measurement, you can then calibrate it to your calculated power output measurement. I use these measurements, together with a calibrated Fluke DVM, to calibrate my power meters, and then I know my power measurements into my dummy load, or any 50 Ohm resistive load, are quite accurate.

Other Measurements

Once you have the rectified output signal available from your dummy load, you can make other measurements. By selecting a filter capacitor and a parallel resistor across your binding posts to tailor your time constant, you can check the CW keying waveform across your binding posts, for instance. Here is the schematic for the load.



Power Resistor Kit

HOME | ABOUT HYBRIDS | HYBRID MODELS | STEPS TO RESTORE | REPAIR EXAMPLES | SERVICE RATES | Equipment SALES

Some Additional K4EAA Site Links

Web www.k4eaa.com

ken@k4eaa.com

Please Note: The above address is a GIF image, to foil spammer robots.
You will have to type that address into your email client. Thanks for your understanding, Ken.

All Photos and content copyright 2005, 2006 K4EAA, Ken Kemski.

International Journal on Recent and Innovation Trends in Computing and Communication
Volume: 3 Issue: 1

ISSN: 2321-8169
309 – 312

Design of Antenna System to harvest RF Energy for Generating Electricity

Arghya Sahoo, Neelaveni Ammal
Dept. of Electronics and Communication Engineering
SRM University, Kattankulathur
Chennai, India
e-mail: argha.me@gmail.com
e-mail: neelaveni.m@ktr.srmuniv.ac.in

Abstract— Electromagnetic energy harvesting holds a promising future for energizing low power devices in wireless communication circuits. Here we present a RF energy harvesting system that can harvest energy from the ambient surroundings from the radio frequency of 1.42 GHZ to 2.28 GHZ. The harvesting system is aimed to provide an alternative source for generating electricity. The system design consists of a high gain square shaped patch antenna, a RF-DC conversion module and a battery. For a received signal gain (max) of 32.15dBm (1.64 W) at the antenna modules produce a DC output voltage of 6.5 V across 100 kΩ load.

Keywords*-RF Energy, Harvesting System, High gain antenna.*

*****

I. INTRODUCTION

RF energy harvesting requires capturing free flow of energy at the frequencies of interest and converting that energy into usable DC voltage. Ambient RF energy is captured by the use of an antenna and channeled into the input of RF-DC conversion module (a voltage multiplier circuit) through an appropriate matching network. The energy conversion module converts the captured RF energy into DC voltage. The conceptual block diagram for energy harvesting system is shown in Fig.1. In [1], work was carried out at 900 MHz 50 Ω impedance and used resonance circuit transformation in front of the Schottky diode which yields a DC output voltage of over 0.3 V for an input power level of -26 dBm (2.5 µW). A DC voltage of 0.8 V was achieved with no load from RF input power level of -20 dBm (10 µW) at 868.3 MHz through simulation [2]. A Cockcroft-Walton multiplier circuit was used and produced 1.0 V DC voltage into a 200 MΩ load for an input power level of 1.0 µW at a fixed frequency of 2.4 GHz [3]. Using an integrated zero bias detector circuit with Bi-CMOS technology, [4] achieved a DC output voltage of 1 V into a 1 MΩ load for an input power level of 1.0 mW.

This module can function as an AC to DC converter that not only rectifies the AC signal but also elevates the DC voltage level. The output voltage obtained from the energy conversion module can be used to energize the electronic devices. The antenna used is capable of having a high gain within the frequency of 1.42 GHZ to 2.28 GHZ. The maximum output power gain of the antenna is 32.15dBm (1.64 W) which is having an equivalent AC voltage of 4.462 V. The RF-DC circuit is capable of rectifying the voltage and also increase the DC level upto 6.5 V across 100 kΩ load.

This research work is focused to overcome the difficulties in earlier works and the output voltage from energy harvesting system is used to energize few electronic devices.


Antenna
Circuit (RF-DC Conversion Circuit)
Battery or Electrical Storage Device

Fig 1. Conceptual block diagram for energy harvesting system.

Section 2 of this article discusses on the theoretical background of the antenna and the RF-DC circuit. Section 3 presents the methodology which contains simulation and implementation procedures of the antenna and the circuit. Section 4 provides the results and analysis. Section 5 concludes the article with the research findings.

II. EASE OF USE

The design used in this article for the antenna is being derived from the square shaped patch concept and the energy conversion (RF-DC) circuit module is derived from the function of a full wave peak rectifier with diodes. The multiplier circuit used in this module contains stages of capacitors and diodes that can be used to generate DC output voltage.

A. *Antenna Modelling*

The antenna was designed using planar concept having a square shaped patch design on the substrate. The substrate used is FR-4 epoxy. FR-4 glass epoxy is a used due to its versatile high-pressure thermoset plastic laminate grade with good strength to weight ratios.

With near zero water absorption, FR-4 has most considerable mechanical strength. The antenna has a bandwidth of 860 MHZ. The antenna design is shown in Fig.2.



Fig 2. Antenna model square shaped patch design.

B. *Circuit Modelling*

The voltage multiplier circuit was designed using zero bias Schottky diode 10BQ015 from Agilent and ceramic capacitors. Zero biased diode HSMS-750 can also be used. This diode has been modeled for the energy harvesting circuit which comes in a one-diode configuration. For the rectifier circuit fast recovery diodes 1BH62 are being used. The circuit design is being shown in Fig.3.



Fig 3. RF-DC Circuit for the system.

A voltage multiplier is a few-stages voltage multiplier. The output voltage of a voltage multiplier have almost one and half times the peak input voltage due to their high impedance, caused in part by the fact that as each capacitor in the chain supplies power to the next, it partially discharges, losing voltage doing so.

The bridge rectifier is used to convert the voltage output of the multiplier to high dc voltage output.

III. METHODOLOGY

After completion of analytical design of the antenna and the circuit, modelling and simulation was carried out using HFSS software and Multisim Software environment respectively.

The modelling and simulation of the antenna is done using HFSS software. The model consist of a square shaped patch antenna of dimension (46mm X 46mm) over a substrate of dimension (70mm X 70mm) of FR-4 epoxy resin. The center frequency is taken at 1.8 GHZ. The antenna is capable of radiating and receiving the frequency of 1.42 GHZ to 2.28 GHZ having 860 MHZ bandwidth. The antenna has a high gain. The simulation shows the maximum output power gain of the antenna is 32.15dbm (1.64 W) which has an equivalent rms voltage of 4.462 V. The antenna model is shown in Fig.4.



Fig 4. Antenna model using HFSS software.

The modelling and the simulation of the circuit is done using Multisim software environment. The model consist of a voltage multiplier and a rectifier. The voltage multiplier consists of zero biased schottky diodes and ceramic capacitors. The rectifier consists of fast recovery diodes.

Here schottky diodes 10BQ015 zero biased were used. These diodes can work upto 2.4 GHZ. For the rectifier fast recovery diodes 1BH62 were used. The components used are shown in Table 1 below.



Sr. No.	Components	Name in the Circuit	Types	Ratings	Specifications
1	Diodes	D1, D2, D3, D4	Schottky	HSMS-750	Zero biased schottky diode, 3GHz.
		D5, D6, D7, D8	Fast Recovery	1BH62	100V, 1A, Fast Recovery Diodes
2	Capacitors	C1, C2, C3, C4, C5	Ceramic Capacitors	Y5V-0603	1 nano Farad, 10V.
3	Resistors	R1			50 Ohms
		R2			100 Ohms
		R3			100 kilo-Ohms

Table 1. Components used in the circuit.

The input is taken as 4.462 V with 1.8 GHZ frequency, which after simulating using the circuit gives a stable output of 6.5 V DC across 100 kΩ load. Since the antenna output port is directly fed into the input port of the circuit through SMA connectors, the voltage across the antenna port output is taken as the input for the circuit. The circuit design and simulation (in Multisim) is being shown in Fig. 5 and Fig.6 respectively.



Fig 5. Circuit design using Multisim Software.



Fig 6. Simulation (DC Current) of the circuit using Multisim Software.

A sub miniature SMA connectors are used to connect the ports of the antenna with the circuit.

The circuit components consist of active and passive components. Special handling precautions have been taken to avoid Electro Static Discharge (ESD) while assembling the surface-mount zero bias Schottky diodes. Also special attention has been given to mount other components and the SMA connectors on to the PCB.

A. *Abbreviations and Acronyms*

ESD – Electro Static Discharge.
SMA – Sub Miniature version A.
PCB – Printed Circuit Board.
RF – Radio Frequency
DC - Direct Current
HFSS – High Frequency Structural Simulator.

B. *Units*

- “dBm” (Decibel milliwatt) used as unit of Power Gain of the antenna.
- “GHz” (Giga Hertz) used as unit of frequency of the antenna.
- “*vi*” (Reference Voltage) used to compute Voltage power gain.

C. *Equations*

$$\text{Gain (in dBm)} = 10 \log_{10} \frac{P}{1mW} \quad (1)$$

Where *P* = output power of the antenna.

$$\text{Gain (in dBm)} = 20 \log_{10} \frac{Vo}{Vi} \quad (2)$$

Where *vo* = output voltage of the antenna

IV. RESULTS AND ANALYSIS

The simulation of the antenna is performed using the high frequency structural software (HFSS). The antenna works within the frequency of 1.42 GHZ to 2.28 GHZ. The return loss is maximum at 1.8 GHZ having -38.41 dB. The working frequency of the antenna is shown in the Fig.7.



Fig 7. Return Loss of the antenna.

The antenna has a high gain having a maximum output power gain of 32.15dbm (1.64 W). The gain is given using rectilinear graph in Fig.8.



Fig 8. Rectilinear graph showing gain in dbm.

For calculation of the output AC voltage of the antenna, we have used certain formulae:

$$\text{Gain (in dBm)} = 10 \log_{10} \frac{P}{1mW}$$

Where P = output power of the antenna.

$$\text{Gain (in dBm)} = 20 \log_{10} \frac{Vo}{Vi}$$

Where v_i = reference voltage = 0.775 V.

After calculation,
We get output voltage of 4.462 V.

The simulation of the circuit is performed using Multisim Software environment.

The input to the circuit is given as 4.462 V with 1.8 GHZ frequency, after simulating it gives a stable output DC voltage of 6.5 V and 44.5mA across 100 kΩ load. The DC current and DC voltage simulation is shown in Fig.6 and Fig.9 respectively.



Fig 9. Simulation (DC Voltage) of the circuit at 1.8 GHZ.

The hardware of the circuit is shown in Fig.10.



Fig 10. Hardware of the circuit.

The results clearly shows that the designed RF to DC conversion module can be successfully used for RF energy harvesting.

ACKNOWLEDGMENT

I would like to express the deepest appreciation to my guide, Mrs. M. Neelaveni Ammal, Assistant Professor (Sr.G.), who has the attitude and the substance of a genius. She continually and convincingly conveyed a spirit of adventure in regard to research and an excitement in regard to project. Without her guidance and persistent help, the project would not have been possible.

REFERENCES

[1] Ungan, T., Reindl, L.M.: "Concept for harvesting low ambient RF sources for microsystems". http://www.imtek.de/content/pdf/public/2007/powermems_2007_paper_ungan.pdf, acessed 20th March 2010.

[2] Yan.H., Macias, J.G., Montero, Akhnoukh A., De Vreede, L.C.N. and Burghartz J.N.: "An integration scheme for RF power harvesting", Proc. STW Annual Workshop on Semiconductor Advances for Future Electronics and Sensors, Veldhoven, Netherlands, November 2005. Pages 64-66.

[3] Jiang wang, Liang Dong and Yuzhuo, Fu: "Modeling of UHF voltage multiplier for radio triggered wake-up circuit", International Journal of Circuit Theory and Application, 2010, DOI:10.1002/cta.692.

[4] Stefan von der Mark and Georg Boeck.: "Ultra low power Wake-up Detector for Sensor Network", SBMO/IEEE MTT-S International Microwave & Optoelectronics Conference (IMOC 2007), Brazil, 865-868.

[5] Emmanuel B., Gaubert J, Pannie P, Gaultier J.M..: "Conception of UHF voltage multiplier for RFID circuits and systems", IEEE North-East Workshop, Gatineau, Que, Canada, June 2006, 4224-0417-7.

[6] Daniel W. Harrist.: "Wireless attery Charging System using Radio Frequency Energy Harvesting". Thesis, BS, University of Pittsburgh, July 2004.

[7] D. Bouchouicha, F.Dupont, M. Latrach, and L. Ventura.: "Ambient RF energy harvesting," in IEEE Int. Conference Renewable Energies Power Quality (ICREPQ'10), Mar.2010, pp.486-495.

[8] A.Sample and J.R. Smith,: "Experimental Results with two Wireless power transfer systems", in IEEE Radio Wireless Symp, Jan 2009, pp. 16-18.

[9] M.M. Tentzerisand, Y.Kawahara.: " Novel Energy Harvesting Technologies for ICT applications", in IEEE Int. Symposium. Appl. Internet, 2008, pp. 373-376.

[10] Wireless Identification and Sensing Platform (WISP), [Online]. Available: http://wisp.wikispaces.com/ .

Guide to Antenna Cables & Connectors

Cable Types

All cables lose some signal, the amount depends on the quality of both the cable and connector. As a general guide the thicker and less flexible the cable, the better the cable. Th
signal loss cables often have a number of layers designed to insulate and shield the inner core from external noise.

For a more detailed explanation of coaxial cable please see our Coaxial Cable Theory guide.

Accessory Cable - RG316

RG316 is a low loss, FEP jacketed miniature coaxial cable capable of withstanding operating temperatures up to 200°C. The cable's stranded silver-coated CCS inner conductor and silver-plated copper braid provide superior shielding and low attenuation losses, making it by far the preferred accessory/patch cable over similar 2.5mm cables such as RG174.



Electrical Specifications

Resistance: 50Ω
Capacitance: 96pF/m
Signal Loss: 0.79dB/m @ 850MHz, 1.27dB/m @ 2100MHz
Frequency Range: 0-3GHz
Maximum Recommended Length: 50cm (cellular bands)
Velocity of Propagation: 70%
Nominal Delay: 5.08ns/m
Voltage Withstand: 1200Volts DC

Mechanical Specifications

Weight/100m: 1.8kg
Minimum Bend Radius: 13mm
Conductor Material: Silver coated CCS (0.51mm)
Insulating Material: Teflon PTFE (1.52mm)
Outer Shield Material: Silver coated copper braid 95% Coverage (1.95mm)
Outer Jacket Material: Brown FEP (2.5mm)

Standard Cable - RG58U

The most common type of cable encountered. It's likely the cable supplied with your antenna is RG58, which is flexible, has reasonable performance characteristics, and is cheap.



Electrical Specifications

Resistance: 50Ω
Signal Loss: 0.46dB/m @ 850MHz, 0.76dB/m @ 2100MHz
Frequency Range: 0-6GHz
Maximum Recommended Length: 15m (cellular bands)
Velocity of Propagation: 77%
Nominal Delay: 4.19ns/m

Mechanical Specifications

Conductor Diameter: 0.9mm
Insulating Material: Gas-injected FHDPE
Outer Shield Material:
- (1) Aluminum Foil-Polyester Tape-Aluminum Foil 100% Coverage
- (2) Tinned Copper 90% Coverage

Outer Jacket Material: Polyethylene (5mm)

Low Loss Cable - LMR195

This cable is designed to be a weatherproof high performance alternative to standard RG58. LMR-195 maintains a 5mm diameter and trades flexibility for far superior electrical shielding (90dB) and much lower attenuation. LMR195 series cabling loses only 0.36dB per metre, compared to standard grade cables which lose 0.46dB/m at 850MHz.



Electrical Specifications

Resistance: 50Ω
Capacitance: 83.3pF/m
Signal Loss: 0.36dB/m @ 850MHz, 0.53dB/m @ 1800MHz

Mechanical Specifications

Weight/100m: 3.0kg
Operating Temperature: -40° ~ +85°C
Minimum Bend Radius: 12.7mm

Frequency Range: DC-6GHz
Velocity of Propagation: 80%
Nominal Delay: 4.17ns/m
Voltage Withstand: 1000Volts DC
Peak Power: 2.5kW

Conductor Material: Single Strand Solid Copper (0.94mm)
Insulating Material: Foam PE (2.79mm)
Outer Shield Material:
- (1) Bonded Aluminium Polyester Tape 100% Coverage (2.95mm)
- (2) Tinned Copper Wire 88% Coverage (3.53mm)

Outer Jacket Material: PVC Weather & UV Resistant (4.95mm ±0.15mm)

Super Low Loss Cable - LMR400

The highest grade antenna cable, recommended for any performance critical, industrial, and harsh environmental applications. It's exceptional performance is achieved with a much thicker diameter (10mm) and greatly reduced flexibility (72mm minimum bend diameter). Each manufacturer of LMR400 names their cable with different letters in front of '400', for example the Super Low Loss LMR400 series cable we manufacture is LCU400, ZCG Scalar's is RU400, Benelec's is LL400, and so on.



Electrical Specifications

Resistance: 50Ω
Capacitance: 78.4pF/m
Signal Loss: 0.12dB/m @ 850MHz, 0.20dB/m @ 2100MHz
Frequency Range: DC-16GHz
Velocity of Propagation: 85%
Nominal Delay: 3.92ns/m
Voltage Withstand: 2500Volts DC
Peak Power: 16kW

Mechanical Specifications

Weight/100m: 14.6kg
Minimum Bend Radius: 72mm
Conductor Material: Solid Copper (2.74mm)
Insulating Material: Gas Injected Foamed Polyethylene (7.24mm)
Outer Shield Material:
- (1) Sealed APA Tape 100% Coverage (7.37mm)
- (2) Tinned Copper Braid 98% Coverage (8.17mm)

Outer Jacket Material: Black Polyvinyl Chloride PVC (10.3mm)

Cable Connectors

Similarities between connectors and naming conventions can often make identifying connectors difficult. To make things easy follow this rule:
Male Connector - has the protruding metal centre pin
Female Connector - contains a hole that receives the male connectors metal pin, called the receptacle.

⊖ 7/16 DIN

7/16 DIN

7/16 series connectors are a threaded coupling connector designed for high wattage transmissions, requiring very low VSWR and minimal intermodulation. The name is derive contact dimensions - 7mm OD inner contact, 16mm ID outer contact. You'll commonly find 7/16 DIN connectors on 1/2 and 7/8" feeder cables connected to LTE and WCDMA 7/16 connectors are also popular in defence, broadcast and other microwave applications.



Female 7/16 Connector

Male 7/16 Connector

⊖ BNC

BNC

This is one of the most common antenna connectors, primarily used in VHF/UHF systems. The 'B' in BNC refers to the Bayonet twisting interface, with the female connector feat either side allowing connection to be achieved with only a quarter rotation. Ideally suited to RG58/59 and subminiature cables, BNC connectors offer good performance from D 50Ω or 75Ω resistance. All BNC connectors on our website are 50Ω.


Male BNC Connector


Female BNC Connector

⊖ F

F Type

Primarily used for cable TV, HFC, set-top boxes, cable modems, the F coaxial connector is a 75Ω connector often used in conjunction with standard RG59 and RG6 75Ω coaxial good performance characteristics up to about 1GHz and is not suitable for modern day broadband requirements.


Male F Connector


Female F Connector

⊖ FME

FME

This is the standard 50Ω connector for all mobile phone and wireless broadband antennas. The FME connector was selected for its excellent performance in the 0-2GHz freque connector diameter making it easy to fit in tight places. Rarely seen in any other RF applications, the FME connector is used almost exclusively for cellular telephony and data a


Male FME Connector


Female FME Connector

⊖ MC Card

MC-Card

The MC-Card connector is a microminiature 50Ω that features snap-on mating, suitable for RF devices operating between DC and 6GHz. This connector is often used as a subst
wireless and telecom applications due to its similar performance and physical dimensions.

Male MC-Card Connector

Female MC-Card PCB Connector

⊖ MCX

MCX

The MCX or, Micro Coaxial, connector is a 50Ω miniature coaxial connector designed for RF applications between DC and 6GHz. It has identical inner contact and insulator dim
common SMB connector, but a 30% smaller outer diameter, making it ideal for tight installations. This connector is often used for GPS, TV tuner cards, RF hardware, and is ofte

Male MCX Connector

Female MCX Connector

⊖ Mini-UHF

Mini-UHF

A minified connector based off the larger UHF connector, designed for space-limited RF applications. Like its larger counterpart, Mini-UHF series also have a variable impedanc
transmissions between DC and 2.5GHz. You will find this type of connector on many different RF applications, most prominently in UHF/VHF communications where its variable
50Ω mark for good quality connectors) isn't as important.

Male Mini-UHF Connector

Female Mini-UHF Connector

⊖ MMCX

MMCX

The MMCX or, Micro-Minature Coaxial, connector is a miniature version of the 50Ω MCX coaxial connector. It performs well between DC to 6GHz and has a snap-lock function rotation once connected. This connector is most often seen PCB mounted on PCMCIA cards, modems, and GPS devices.

Male MMCX Connector

Female MMCX Connector (PCB Bulkhead)

⊖ N

N Type

N connectors are the 50Ω connector of choice for most high quality antenna systems due to their wide performance band - DC to 11GHz. This large sized connector has a wide connectors but is easily tightened by hand. You will find this connector on most RF applications including radar, mobile base stations, electronic instrumentation, and of course antennas.

Male N Connector

Female N Connector

⊖ QMA

QMA

The QMA connector has a snap-lock mechanism designed for easier, faster and safer coupling. Often used to replace SMA, the connector can be seen in cellular base stations a This 50Ω subminiature coaxial connector has a frequency range extending up to 18GHz.

Male QMA Connector

Female QMA Connector

⊖ SMA

SMA

A smaller 50Ω connector, most often found on the back of desktop modems and as the physical interfacing screw thread of some smaller antennas. Some antennas come pre-t connector over the normal FME connector for hassle-free connecting to desktop wireless broadband modems, like the Bigpond Wireless Gateway series. SMA is designed for a applications and is suitable for communications DC to 18GHz.



Male SMA Connector



Female SMA Connector

⊖ SMB

SMB

Similar in size and performance to the SMA connector, SMB was designed with a snap-on interfacing. SMB connectors have a 50Ω or 75Ω impedance, and are suitable for RF a 4GHz. You will find SMB connectors in a wide range of areas from telecommunications through to industrial equipment. Gender of SMB connectors can often be confusing as t socket/jack body, with the female having the plug body.



Male SMB Connector



Female SMB Connector

⊖ SSMB

SSMB

This connector is the subminiature version of the SMB connector. It is a 50Ω impedance coaxial connector with good performance from DC to 12GHz. Like its larger brother, SS interfacing. Gender of SSMB connectors can also be confusing as like SMB, the male has the receptacle, with the female having the centre pin.

TELCOANTENNAS

Male SSMB Connector



Female SSMB Connector

⊖ TNC

TNC

Identical to the BNC design, but have a threaded connector. Operates better than the BNC connector at microwave frequencies. TNC are miniature, threaded weatherproof unit impedance and operate from DC to 11 GHz. Widely used in WiFi equipment, radar, and military/aerospace systems.

Male TNC Connector

Female TNC Bulkhead Connector

⊖ UHF

UHF

UHF series are a variable impedance connector designed for low frequency operations 600KHz to 300MHz. This very large connector is used almost exclusively for radio and UH cost design of UHF connectors often results in impedance varying between 30-40Ω causing significant reflections above 300MHz. Despite this, the connector remains popular w users.

W.TELCOANTENNAS.

Male UHF (PL259) Connector



Female UHF (SO239) Panel Mount Connector

SHOP ONLINE

VISIT US

GET IN TO

© 2017 Telco Antennas Pty Ltd

ABN: 30 145 543 951

Heads up! To help protect against fraud, your machine's IP (154.5.208.5) is being logged

Returns Poli

Fighting the pollution by public radio broadcast antennas

Un texte en français :	La pollution radio par les émetteurs FM
Een tekst in het Nederlands:	De radiovervuiling door FM-stralen
A petition:	www.petition-electrosmog.be

The electromagnetic pollution has now reached such a level that not only hypersensitive persons are being harmed. The debate most often focuses on cell phones, their relay antennas, Wi-Fi routers and similar technologies. It is often pointed out that domestic appliances like power saving lamps and cheap electronic devices, are harmful too. Recently, I came to the conclusion that I too had problems with electromagnetic radiations. Yet after a few months investigating, I was surprised to find out that far out the main cause of my problems was nothing I had heard about. A 100 MHz FM public radio broadcast antenna is located atop a local hospital and burns the whole city with an astounding force of 2 V/m (pike value).

I found other persons that are harmed. For example people who develop severe headaches or tiredness after a few hours working in a given place. They have no problems in other places, that are less exposed to the FM radio waves. It seems to me that people who live in strongly exposed habitations often develop psychiatric problems. My guess is that probably several thousand persons in the city are severely affected. Maybe tens of thousands are affected but without getting obviously sick.

Most puzzling is the fact that this hammering by radio waves is completely useless. It wouldn't change anything to the quality of the reception by the listeners in the city, if the force of the radio waves was divided by 100 or preferably 1,000. The purpose of those antennas is to emit far away in the countryside. That's why they are located atop hills or tall buildings and they have a huge power. But, due to their rudimentary construction, quite much of that power is wasted and hits the nearby city.

It is legal to hit the ground with such force. Whether I measure in rooms or in the open, it is at worst a little below the norms. Hence the problem is with the norms. They keep being too high, despite the efforts of many scholars and health organizations. The situation is catastrophic. If the people did understand the harm that is done to their children, revolts would break open.

Below is a picture of a cheap calculator that I transformed. It contains no more battery nor solar power cell. Instead it draws its energy from a 1 meter long antenna. Anyplace in the city center, in direct view of the emitter, the power of the radio waves is strong enough to feed the device. I made this because nobody was frightened by the figures I was reporting, except some friends that are into electronics. Everybody knows that a car can kill even at 30 km/h speed but almost nobody has any knowledge about radio waves figures. When I showed the calculator, everybody understood and some whitened. (The calculator also works in some classrooms where I tried it out. The emitter was visible through the windows... Should I warn the parents of the students that failed their exams?)

Powered by 000webhost

This didn't help anyway, so I invented another device: the "snake". The picture below shows six of them, an early version.



Powered by 000webhost

You just hang the snake in the flux of radio waves and the LED lamp at one end will bright up, clearly visible in daytime and enough to light and read a text at night.

The snake is less impressive than the calculator but it is much cheaper and easier to make and it can be sent in an envelope. I made tens of them and sent them to politicians, newspapers, universities... I gave some to local people, together with a user guide on a sheet of paper. Just like the calculator, the snake contains no battery. The lamp lights up solely on the power of the radio waves. The picture below shows a later version, that can be rolled up in an envelope that fits the conditions to be sent with only one stamp.

Powered by 000webhost



However mad it is to send such power on a city, nothing has been done yet against this. It's like an 19th century chemical plant sending its pollutants all around. Some complain but others argue that closing the factory would mean people laid off. Some then reply that being employed to feed children that die from ugly sicknesses may be nonsense... And so on, except for the fact that the chemical factory indeed had a purpose while the strength of the radio waves we're talking about, has no serious purpose at all.

Something common to all heavy sources of electromagnetic pollution is that it wouldn't cost much to make them harmless. For example, high tension power lines can be made harmless by feeding them DC current instead of AC current. This requires some more heavy electronics at the input and the output but the price of it is a detail in the whole. I studied the schematics of power saving lamps and simply noticed that they were conceived by people who do not understand the propagation of radio waves. Adding the necessary components to make the lamps radio-silent would almost not increase their prices. Enforcing proper norms will not change our way of life, it will just stop to favor the sociopathics amongst the industrials and lobbyists.

So, what can I do to help people understand the situation? They need to appropriate the scientific knowledge involved. Most assume that the necessary studies will be made by labs and then the governments will adapt the laws accordingly... That would be OK if it wasn't for the trillions of money involved. A minister in Belgium tried to prevent sugar dispensers in schools, she immediately got a made-up scandal on her shoulders. All she ultimately managed to get was to have some health advice notices glued on the sacred dispensers...

Flows of observations are now available, showing the effects of radio waves that match the norms: brains of rats destroyed, people unable to work, eggs that don't hatch, quarreling birds, increased risk of cancer, cows aging abnormally... I myself had seeds germinate and saw them die quicker when closer to a power saving lamp. Their strategy to cope with this is simple: "OK, there does exist scientific evidence of some danger... but there also does exist evidence that there is no danger at all! So let's balance the whole..." The norms are lowered but kept above what cell phone operators need for the current systems. The fact in itself of making a balance between scientific evidence is nonsense. Either a study proves a given danger and it can be verified, or bust. But anyway, what are those studies that tend to prove that there would be no danger? Lots of them are simply payed for by the cell phone industry... Yet some are perfectly serious, for example those concluding that radiations within the norms will not heat the brain or the body abnormally. This is perfectly true. There is no problem of scientific fairness involved with these studies. But, is a bullet harmless because it only very slightly heats your bones? A more sophisticated approach is to pick out studies that have borderline conclusions: "there may be a problem but it is not clear..." The study will be assumed to conclude that there is no problem at all, while it just was an inconclusive experiment like many are in science.

Powered by 000webhost

(When I'm exposed, I tend to compulsively perform simple tasks. What if a study examines if being exposed hampers the ability to perform that kind of tasks?)

Then, there is the problem that I'm going to make people sick. Indeed, electromagnetic hypersensitivity has a psychological component. Once people understand that they are victim to the radio waves and what symptoms the radio waves cause, they can overreact and become very sick when they start feeling the symptoms or just when they know there is a strong radiation force around. The radio waves induce a physiological stress, that hampers the proper functioning of the brain. When you add a psychological stress, due to the awareness of the problem, the summation of the two multiplies... Therapies for hypersensitive persons imply to dislearn them to overreact. Some friends of mine just refuse to start talking about electromagnetic sensitivity because they don't want to embark in the sickness. They do so with everything, meanwhile they eat very good food and have lots of pleasure in life. It works... with people with a strong health and a tad of selfishness.

When you are in a cold wind and you feel a pain in the neck, you know it is due to the wind and you take cover. Almost nobody can do this with the symptoms of an exposition to strong radio waves. You feel tired, some brain fog, like if your head was in a clamp, a headache, or simply you make stupid errors... You will blame yourself or the location, possibly the noisy people around... while in fact you are mainly undergoing electromagnetic sensitivity. The home of a friend is strongly exposed. After about twenty minutes I can nor more find my words and speak correctly, unless I wrap my head in aluminum foil. There is a fair chance that a while ago, I would have blamed my friend for being annoying (he is) to the point of making me speechless. There also is a fair chance that my friend is annoying because he hangs in that electromagnetic pollution everyday. Since he lives there, he became an alcoholic, lost his job, manages to keep no girlfriend... (Everything I mention here can have other causes. Quite often, such causes just add up. For example, the person blaming the noisy people around, would maybe have felt nothing if the noisy people weren't there. Like you don't feel your bad knee when you carry no bag.)

The impact of the electromagnetic pollution is severe. It is a far too heavy, and pointless, contribution to our burdens and losses. But how do you establish, scientifically, be it as an amateur, that there indeed is a problem? My initial approach can be an illustration of this. As my home is uninhabitable, I spend most of the day working in local libraries. I noticed that I could work quite well at some places and not at all at other places. Then I saw an article taped on a board, about the effects of cell phone and Wi-Fi radiations. Okay... I made a spreadsheet, with a row for each location and a note from 0 to 10 according to my ability to work there. Although I knew it was a weak approach, I then filled in each row the strength of the closest Wi-Fi router, as listed by my laptop. There was no correlation... but this proved not at all that the Wi-Fi was innocent. Weeks later I made a nonsensical but working little assembly that made the variability of the radio waves hearable. This time I got a correlation. Mild, but obvious. The ability to work is horizontally while the intensity of the radio signals is vertically:



It quickly became obvious that I was measuring no strong signal in the GHz bands. I had no doubt that there were cell phone and Wi-Fi emissions coming from all directions and echoing all around but their strength was obviously

Powered by 000webhost

weak. The problem was with lower frequencies. I accused the fluorescent lamps for a while, till I finally understood that there was only one strong source, hitting me everywhere; those 100 MHz public radio broadcasts. The picture below shows the final correlation. Only one dot disagrees with the theory:



I was heavily disturbed by the radio waves, simply unable to work, long before I started puzzling on the subject. This is a strong proof that the matter is not just psychological. Reciprocally, once I understood the psychological component, I tried to use it positively, to counterbalance the effects of the electrosmog. I did get some results but I was never able to work correctly in the most exposed places. It is by no means "just psychological". It is useless "to be willing to make a small effort". I did efforts that frightened other people. One thing that does clearly help is eating a lot of sugar (Organic jam on rice bread...) (by the way, is that why sugar dispensers are placed everywhere kids are supposed to think and learn, to counterbalance the effects of the nearby cell phone relay antennas?) Alcohol does also help and I'm afraid this is why people seem to become alcoholics in exposed habitations.

Also, it does sometimes happen that I feel like undergoing strong radio waves but when I pop out my measuring device, I measure nothing serious. I have a natural tendency to be knocked-out... The radio waves are far out my heaviest problem but they are not always responsible.

I started studying other sources of radio pollution. I had an obvious benefit of removing every power saving lamp in my home. I put ferrite cores on most power chords. On one power chord that I sometimes use to feed my laptop inside my shielded tent, I had to put ten ferrites till I felt no more direct effect. Something very interesting is that till then I had no problem when using my cell phone. You guessed correctly: I started having problems, to the point that I never more hold it against my ear. I always use an earplug linked to the cell phone by a wire with two ferrite cores. I suppose that since I started avoiding the exposure to strong radio waves (which significantly improved my life and ability to work), my brains are no more constantly knocked out. So they get knocked out if I hold my cell phone against my head. And I feel it. This is one more synergy between the public broadcasts emitters and the cell phone industry: one hides the other away. 'Want to prove that inhabitants close to a relay antenna are no worse than those further away? Do the experiment in a city that is strongly exposed to public broadcasts...

So: buy a measuring tool or have a friend assemble one for you. And start comparing your problems and those of the people around you, with the level of electromagnetic pollution. If you can, make large-scale experiments with tens of persons, under advice of somebody with knowledge in statistics (to build an expressive statistic yet completely false, is *easy*). We need many such experiments, till it becomes unbearable for local interlocutors to negate the problem and not to dim the emissions. Step by step, we need to conquer our world back. Some enterprises and some countries have already set their norms at responsible levels.

One very important parameter is the rate at which the problems build up and then disappear, when exposed. Some people claim that they instantly feel when their cell phone is going to ring. I never could verify this. A friend claims that his cat reacts when he is going to get a text message on his cell phone. I tried several times to see the cat change

Powered by 000webhost

behavior while making my cell phone emit close to him but I got nothing. So I suppose that the cat reacts to the tone of the cell phone and my friend brain-confuses the timing. (I don't pretend nobody can feel a text message arriving, I'm just saying that I never could verify.) What I'm sure about is that my problems need minutes to build up, most often some ten or twenty minutes, the problem possibly becoming really painful after an hour. Once the problem built up, it needs much more time to diminish, maybe four times more. I often had to sleep a whole night on it. One day I "burned" my brains by holding a very polluting power saving lamp about 3 decimeters away from my head. I only noticed the problem after half an hour. But then it was horrible, like if a flame had been sweeping inside my head. Really just like the ache of a burn wound. I had a strong nausea and headache, that calmed down only hours later. I identified a few persons whose problems are obviously due to the electromagnetic pollution, in all cases the same applies: it needs time to build up. This means you cannot simply walk in and out of an exposed zone and claim you feel no difference. Also, you cannot get into a safe zone and claim you feel no better. If you were already poisoned, you will stay that way a long while. The only sure approach is to stay really long in a safe zone, preferably spend the night there, then go working in a polluted area. Try to be aware of what happens to you. The next day go working in a safe zone and try to see the difference. (This is a goldmine to build inconclusive studies.)

Everybody is sensitive to electromagnetic waves. The question is about the level of the sensibility. That's why people who get seriously sick with the current levels of exposition are called "hypersensitive". They are more sensitive than the average, sometimes with very painful and debilitating consequences.

There is a whole ladder of symptoms. This is roughly the ladder for me, exposed to the 100 MHz FM broadcasts:

0.01	V/m	No problem
0.1	V/m	No more able to concentrate and work
1	V/m	head in a clamp, maybe difficulties to talk
10	V/m	Tried it once for 2 hours, had to stay the whole next day in bed with an awful headache.

The serious problems begin for me at 0.1 V/m. Yet I know some people that wouldn't be called hypersensitive and that get problems similar to mine at about 0.3 V/m. A friend spent with me the two hours under the 10 V/m radiation and claimed he endured no problem... but he made surprising errors on the way back. It is very difficult for me, in my city, to find locations where the force is around 0.01 V/m. Values between 0.1 and 0.3 are common. It is easy to find building with rooms reaching 1 V/m. The force is quite predictable, according to the location and the orientation of the building, how much it emerges out of other buildings... So, because many people are being affected and because the radiation is reasonably easy to measure or to estimate, making statistics linking common health problems with the level of exposition is quite doable.

Hypersensitive persons would be 1% of the population. The need to protect this minority is enough to stop those powerful broadcasts from reaching the ground. I don't understand why I have to add that everybody is being harmed, be it to a lesser degree. I met official people whose job is to help hypersensitive persons. They've seen their pain and anguish by themselves... but they feel clueless as to how to stop the emissions. It's a very strange situation, when even the people close to the steer and convinced of a problem, can't do anything to stop it.

It has been claimed that the hypersensitivity of some persons is caused by an accumulation of toxic metals or organic pollutants. In such cases, antioxidants can be of immediate help and detoxifications would greatly help. (Note that common medical analysis like looking for mercury and the like in samples of blood, urine or hair, will reveal nothing even under severe intoxication, because blood and hair renew constantly. Only a sudden intoxication can be revealed by such analysis. The toxics slowly accumulated in standing body cells like the brain... Best method seem to be to take a well-tuned quantity of chelating molecules and then perform an analysis of the blood or urine.)

Cell phone and Wi-Fi radiations are different, for several reasons: they don't spread the same way in the body, they are pulsated and their frequency make they will not target the same macromolecules in the body. It would seem that you need 3 times more force of FM broadcast waves than cell phone or Wi-Fi waves, to have a same global impact...

I was frightened when I understood that under those 2 V/m force of radiation, an electric current in the order of 1 mA oscillates through the body. Such a current at a high frequency of 100 MHz will interact with the body quite differently than a DC or low frequency AC current. You cannot make direct comparisons... Anyway, 100 mA of DC current can be enough to kill a person by electrocution. 1 mA of low frequency current is enough to feel the current as a tickle. What are the consequences of such a current on the chemical reactions in the liver, on the production of

Powered by 000webhost

hormones by glands everywhere in the body? What if the person being exposed is a pregnant woman, with the baby just at the worst place in the flux of current? The length of an "antenna" matters much to allow it to build up current. Teenagers have the "optimal" length for 100 MHz radio waves... One thing I'm sure about is that if the government decided that from now on the school kids will be latched electrodes on the body and a current of 1 mA send through several hours a day, whatever the frequency, the parents will not accept. But this *is* happening, through radio waves, and I could feel the neuroleptic-like effect of it. (By the way, this implies that those experiments that show brains of rats destroyed by cell phones waves within the norms, apply only to a lesser degree to human brains, because of the difference in size. Rats are close to the optimal length to be harmed by cell phone waves... The optimal wavelength to dammage teenagers is that of those 100 MHz public broadcasts...)

The radiations harm me more inside buildings than outside. I may get more sick under 0.2 V/m in a room than under 2 V/m directly exposed to an antenna. I don't know exactly why. Here are four possibilities:

- The roofs atop buildings act like prisms and send the waves towards the inhabitants beneath. Radio waves coming from above would be more harmful than when coming from aside.
- The radio waves resonate and echo inside the building and build up in metallic structures. This creates halos of proximity that will inject more power inside nearby living bodies. For example, while simply wrapping aluminum foil around my head, it is obvious that some designs of shielding will make me even more sick than using no aluminum at all. The same way, when some parts of the shielding of my tent wear off and stop to be conducting, I can get serious problems till I replace or complement the faulty area.
- Buildings contain their own sources of electromagnetic pollution. They add their effects to those of the pollution from the outside...
- Close to metallic structures, the electromagnetic field can become rotating. This because waves with equivalent strength come from different directions with different phase shifts.

Again, the four possibilities mentioned above are potentially very suitable to build experiments that demonstrate there is no problem. Perform the experiment in an anechoic place with the waves coming from aside and no other radiation than the one from the experiment... Just the opposite from real world situations but you can claim to be serious at avoiding parasitic variables...

If you want to find the FM emitters somewhere, fmscan.org is the reference I used till now.

This is the schematic of the "snake":



BAT62 detection diodes are no more produced. **BAT15** diodes work fine but they wear out; after a few months they stop functioning. **SMS7630** diodes are great but very little and mechanically fragile. **MMSD701T1G** diodes are sturdy and powerful; an excellent choice for a beginner. Such SMD diodes do also work for cell phone frequencies, which allows to test out a snake with a calling cell phone pushed against it. But any detection diodes that can manage 100 MHz will do.

The LED I'm currently using is the **L-7113SEC-H** . It lights up with a low tension and a very low current (the bluer a LED, the more tension it needs). Its color is red yet close to orange hence it is easily seen by the human eye (the eye is most sensitive to green, yellow and orange). The beam is quite narrow so when the LED is directed towards somebody's eyes it will appear quite bright.

For the lengths of 37.5 and 112.5 centimeters, any electric wire with two copper conductors will do. Audio signal wire is a practical solution. Use the shielding as one of the two conductors. The lengths of the two segments must not be precise. What matters is that the total length of the snake be 1.5 meters. Do not hesitate to try out if a little

Powered by 000webhost

longer or shorter snake gives better results.

A schematic of my current probes, that I connect to a standard multimeter, measuring Volts DC. The measure displayed by the multimeter must be multiplied by 10. When using a 200.0 mV scale, just read while forgetting the dot:



This is a picture of a device that tries to pack the whole in a neat gadget. The electronic circuit is a €7 digital Volts display with a scale of 200.0 mV. I soldered away the jumper that makes the dot be displayed. The antenna is only 7 cm long, so an RMS value is displayed (for roughly steady radio waves). The whole cost about €12. Hold the antenna perpendicular to the direction the waves come from and try to hold the device away from conducting objects like your body or metallic objects. You cannot closely trust such simple device yet it is very handy and adequate to compare the radiation level in different places:

Powered by 000webhost

Powered by 000webhost





Powered by 000webhost

Those probes and device, quite easily allow to know the direction some 100 MHz radiation come from. Hold the thing at some decimeters from your body, roughly at the height of the belly. Your body and the device form a directional antenna... When the device is towards the emitter, it will display up to twice the value, while when it is hidden from the emitter by your body, the measure will be very low.

If you measure something strong, yet by turning in different directions the device always shows approximately the same value, then you are probably undergoing low-frequency radio waves like short wave broadcasts.

If the emitter is close, like a power saving lamp or a wrongly build power supply, converge towards it simply using the fact that the closer you get, the stronger the measure.

Such measuring tools are handy to find out power chords and appliances that pollute, yet then the measure displayed doesn't mean much. Once you are really close to an emitter, the measuring device and the emitter interact and the power flowing through the measuring device can be tremendous even though the device is only weakly polluting. You are in the "halo of proximity" of the device... Best example is most quality laptops, which emit almost no radio waves. I never could notice a problem while using my laptop when it is plugged to nothing... Yet if I hold a measuring tool against the screen I get frightening data... A few decimeters further, where my head can be, the measuring tool tells there is nothing... So, the high figures close to the laptop indeed tell that strong currents flow through it, but competent people made things such that those currents harm nobody...

If you want a global measure, away from the effects of your body, hold the device above your head. Or place it on some plastic or cardboard box and walk some distance away.

The windows are a common entry point of radio waves and electric wires can be awfull ducts, yet in some cases I noticed that metallic structures unrelated with electricity, like the copper tubes of water heating radiators, were the main ducts of radio pollution towards a room.

Below is a device I assembled to focus on 1.8 GHz cell phone radio waves. Close to the nearby cell phone relay antenna, in direct view of it, I could not measure much more than 0.1 V/m (pike value). While this is still too much, it is by no means comparable to the frightening 2 V/m intensity of the FM broadcasts. I also went measuring in places where people complain about problems similar to mine. They thought the reason was the nearby cell phone relay antennas. But I could measure no significant intensity of cell phone radio waves at all, while the force of the FM broadcasts was above 0.2 V/m...

Powered by 000webhost



After about a year experimenting, the most simple protection I could come up with against 100 MHz broadcasts is a headband of aluminum, much the shape and size of a sweatband. I hide it inside a bonnet. I have no idea as to how and why it helps, aside from the general fact that any conducting structure will change something to the propagation of high frequency currents. Don't make it too high, a 3 to 4 centimeters height is OK. To try this out, you can just fold in a circle a 1 meter long wrap of aluminum and compress it to a flattened ring that fits your head. If you intent to re-use it, then you must strengthen it with lengths of tape before (inside) and after (outside) the ring is constituted. Make sure the tape does not hamper a perfect electric contact all around the ring. This protection is not perfect but it really helps.
When the field strength is above 0.1 V/m, I need a complementary vertical band in order to be able to work.
This also is a cheap way to make statistics. Compare days with the headband to days without the headband. In order to be scientific, you must ask somebody else to put the headband inside your bonnet every morning, at random. Every morning, the other person writes down if there was a conducting headband inside the bonnet or not. Every evening, you write a comment down to how your day was (headache? brain fog? errors? doomed day?) Then after a while you compare the two. At worst, if you have to do it alone, buy two identical bonnets, push a plastic headband inside one and an aluminum headband inside the other, and spend each day without knowing which one you picked. At the end of the day, write your appreciation down before checking and writing down which bonnet you picked.

Powered by 000webhost



A friend who is a physician points out that in many administrations, be they public or private, the employees are being persecuted. (That often happens when the work done by the administration is mostly useless and only serves to justify the social position and the salaries of a few people.) A statistic about the health impact of radio waves in such administrations could be of few significance, because the people have all kinds of health problems due to the harassment. The addition to this by the radio waves may be comparatively negligible. (Yet another way to build a statistic that shows few or no impact of the radio waves: perform it in a place where people bow under humilations...)

I was quite frightened to discover that the symptoms caused by radio waves, as I see them around me, are very close to those of "radiation poisoning". This is part of nuclear medicine. When a victim is exposed to a short and strong burst of radioactivity or any other ionizing radiation, its body will quickly react like if it had been poisoned. A "low" poisoning by radiations yields headaches, tiredness, difficulties to think... while stronger poisoning can lead to the person die in a few days like if it was heavily burn. The exposure to ionizing radiations is measured in "Gray". 1 Gy leads to a low poisoning. So I computed out how much energy a person gets from the local FM emitter, like the person I know that get sick at their desk. The result is 0.01 Gy for 8 hours of exposition, which is quite close.

Radio waves can induce all the typical problems caused by that ionisinig radiations but the energy levels involved can be quite different. For example, ionizing radiations cause burns without increasing the temperature of the body, while radio waves can only burn if they are powerful enough to heat the body. Radio waves can induce cancer but again the energy required is ways higher, like spending ten years using a cell phone against the head, several hours a day.

Body cells can be attacked by all kinds of means. Ionizing radiations lead to direct damage of the cell membrane. Radio waves disturb the molecular cell gates operate. The cell will always react the same way, as for poisoning: it will close the cell gates, to try to shun itself from the outside world and from the harm. This has many consequences. The cell is less able to fulfill its purpose inside the body. It uses resources to try to protect its internal parts. It will accumulate waste. That's why people get tired, less efficient or even sick. When the aggression made to the cell is deemed too strong, the cell will auto-destruct. That's the way radiations and chemicals can be used against cancer, making the cancer cell suicide.

The cells can be helped to better recover from the state of shock. Also they can be made to go less likely into the state of shock. Medication and health advice can be helpful for this.

A link has been proposed between autism and radio pollution. The growth of the human brain is very complex, with cells traveling from one side of the brain towards the other to find their place. This involves a tremendous amount of communication and coordination between the cells. What if those cells are too often put into a state of shock?

These are two scientific publications about the link between autism and radio waves :

http://www.ncbi.nlm.nih.gov/pubmed/16530334

http://www.ncbi.nlm.nih.gov/pubmed/14962625

Powered by 000webhost

Publications about how radio waves disturb cells :

http://www.ncbi.nlm.nih.gov/pubmed/10860806

http://www.ncbi.nlm.nih.gov/pubmed/12379225

Links

http://www.teslabel.be
http://www.clag.be
http://www.001.be.cx
http://www.criirem.org
http://www.next-up.org
http://www.robindestoits.org
http://www.beperkdestraling.org
http://www.stopumts.nl

A petition: www.petition-electrosmog.be

Eric Brasseur - October 3 2009 till October 16 2015

Powered by 000webhost

14th July 2012

LED RF POWER METER/INDICATOR



[http://2.bp.blogspot.com/_JLelwWSHq1A/TGQA0hdltHI/AAAAAAAAAAY/4suqfz03xbc/s1600/12082010593.jpg]
Friends, following picture is of a Simplest radio frequency(RF) indicator and meter that i have got yet.

PURPOSE OF CIRCUIT:

Circuit is used to indicate
whether or not the radio frequency Tx circuit in your hand oscillates.
If LED on the board is bright means your circuit is oscillating means you ROCK.

Need for the circuit:

Anybody who had messed with rf circuits will readily agree with me that whenever a rf circuit is turned on, the very first shout made by mind "is oscillator part of it working?"
(and next will be a prayer " O'God may this INDUCTOR be blessed not cursed!" , at least in my case :-)

Let suppose you are working on FM- Tx or AM-Tx ,they will always contain a sound preamplifier and oscillator section. preamplifier section may be tested with headphones or Power amplifier(like PC speakers) but how to test the oscillator section?
You may think of Radio receiver.
But whats your transmitting frequency ? what if you have low power Tx or frequency much below or above than radio could receive ? Tuning each band in search of your transmision will really be cumbersome,specially when you even dont know that whether transmission has begun or not?
You may readily be disappointed and think "sala inductor kharab hai".

Here comes usage of above circuit. No matter what frequency it is, if your oscillator part is working LED will glow.
This , at least, makes you optimistic about your circuit that yes it working, now i have just to vary coil spacing or value of tuning capacitor to get desired frequency.

Working of circuit:



[http://3.bp.blogspot.com/_JLelwWSHq1A/TGQOSsHOo8I/AAAAAAAAAAg/CeatTuKxcs0/s1600/The-led-power-meter-circuit.gif]
Basically circuit is designed to charge 100nF capacitor .
Circuit starts working when 5cm lead is attached to RF emitting source(like antenna,collector of oscillating transistor etc).

Now whenever positive cycle comes it creates a push in electrons present in wire which is transferred to capacitor through upper diode & for negative cycle a pull is produced which again makes electrons to flow in same direction thus charging 100nf capacitor.
LED is exactly connected to capacitor as if it is a charged battery.

100pf capacitor is used to create dc isolation.

Circuit Modification:

When i finalized circuit and tested my FM-Tx, LED glowed very weakly.
When i removed 470 ohm resistor, Led strength increased,but not satisfactory.

Accidentally when i touched cathode of LED, it became magically bright.Well it has got fair reason for that: it got better ground through my body.
Be careful brighter the led will draw more power from your transmitting circuit.

Moreover:

The circuit can work as strength meter if put your digital multimeter's test leads at terminals of capacitor.
That is multimeter will indicate voltage built across capacitor. higher voltage greater strength of you transmitter.

Posted 14th July 2012 by Abdul Sattar Noonari

Labels: 08es25, fm, Radio frequency tester, rf power meter, SATTAR NOONARI, transmitter tester

Download PDF Manual - Free
Download Free Manuals With AtoZManuals
free.atozmanuals.com/PDF/Manual

Nano-Crystal Electricity
When you see it for the first time, you'll think you stepped into a science fiction novel. strategictechinvestor.com

0 Add a comment

The Service Line

Build a Quality RF Sampler

by Don Jackson, W5QN

We know that it would be very handy to have an RF sampler to use with our Spectrum Analyzer (SA) or any other device with 50Ω input impedance.

You may ask why the frequency response need be as high as 90 MHz. For many HF measurements, we only need a 30 MHz response, but we may want to measure the harmonic content of a 30 MHz signal. In this case, we need a reasonably flat frequency response up to at least the 3rd harmonic, which is 90 MHz.

Let's summarize the specs for the sampler.

- 1500 Watt maximum input power
- Coupling Factor of 50 dB (for no damage to an SA)
- Frequency response from 2 MHz to 90 MHz
- Sample port source impedance of 50Ω
- Output port and sample port terminations are both 50Ω

We could purchase a commercial sampler, but they are quite pricey. So, let's look at building our own. David Knight's (G3YNH) article (http://www.g3ynh.info/zdocs/bridges/Xformers/part_1.html) has a great deal of design information, but his examples only consider circuits with a single terminating resistor of 50Ω. The use of a single resistor in the circuit is ok for many applications, but using two resistors (Rt and Rs) provides an additional degree of freedom in the design. This helps considerably, particularly with achieving good high frequency response. The schematic of the sampler is shown in Figure 1.



Figure 1 – Schematic Diagram

I set about deriving the equations for the sampler, expecting the result to be fairly complicated for determining values for the number of transformer turns, and the values for Rt and Rs. To my surprise, a page of equations boiled down to a very simple relationship:

Rt = 100*N*SQRT(Ps/Po)

Where N is the number of turns on the secondary of the current transformer, Po/Ps is the ratio of the main output power to the power at the sample port. The number of turns on the transformer primary is "1", since the main line simply passes through the center of the toroid core. The value for Rs is always (50 - Rt). Using this equation, and assuming N= 32 turns and Ps/Po is .00001 (-50 dB), we calculate Rt = 10Ω, and Rs = 40Ω. You may ask why two resistors are used instead of just a single 50Ω resistor. To answer this, let's solve the above equation for N:

N = (Rt/100)*SQRT(Po/Ps)

If Rt is 50Ω (Rs becomes zero) and Ps/Po is still .00001, N calculates to be about 158 turns. The number of turns has increased by almost a factor of 5. This is bad news for the high frequency response since the distributed capacitance is increased and the length of the wire is also increased.

Service Line (Cont'd)

That's enough background information. How do we build the sampler? One consideration is to make the physical distance between the input port and output ports as small as practical. The connection between these two ports is not a 50Ω transmission line, so the shorter we make the distance, the less inductance is present, and the better the high frequency performance. Although not super-critical, I found the shortest practical distance between the two Type-N connector flanges to be about .8". Therefore, that defined the width of the enclosure for my sampler. A width much smaller than .8" will make it difficult to install the toroidal transformer and Faraday shield. The length of the enclosure need only be long enough for Rs and a BNC connector. Figure 2 is an external view of the sampler, while Figures 3 and 4 are close-ups of the internals that will hopefully help you in construction. You might notice that my Rs is actually a parallel combination of 270Ω and 47Ω, which I happened to have in my junk box. A value of 39Ω will work fine though.



Figure 2 – Sampler External View

Figure 3 – Sampler Side View



The transformer is constructed by winding 32 turns of 30AWG enameled magnet wire on a Micrometals 44-2 powdered iron core. This core can be ordered online from Amidon Corporation. Wind a single layer of wire on the core, taking reasonable care to leave a little space between each winding. This will help minimize the distributed capacitance of the transformer.

The Faraday shield is an important feature in the design. We would like the sampler output signal to be dependent only on the magnetic coupling of the transformer. However, at higher frequencies, there is electrical coupling from the main line to sample port due to capacitance between the transformer windings and the main line. We want tight magnetic coupling in the transformer, but not the capacitive coupling. This is where the Faraday shield comes in. It provides electric field isolation without affecting the magnetic coupling. In G3YNH's article, he shows an implementation of the shield using 50Ω flexible coax. Note that only ONE END of the coax shield is connected to ground, so don't be fooled into thinking you have a 50Ω transmission line from input to output. However, his implementation is meant for lower frequencies than we want, so I used a slightly different implementation. My sampler uses a short piece of RG-402 (.141 inch O.D.) semi-rigid coax, which allows more precise control over construction of the Faraday shield. Cut a piece of RG-402 so that the center conductor of the coax can be soldered to the input and output connectors. (Do not solder the RG-402 in place yet.) You will find that the transformer is a bit of a loose fit over the RG-402. It is best if the transformer fits snuggly over the RG-402, so build up the gap by wrapping layers of Teflon pipe thread tape around the RG-402. The desired result is that the transformer will hold itself in place when inserted over the RG-402. If you like, you can add a drop of polystyrene "Q-Dope" (from GC Electronics) to hold the transformer in place. Set the transformer/Faraday shield assembly aside for the moment.



Figure 4 – Sampler End View

Install the input, output and sample port coaxial connectors onto your chosen enclosure. I used female N (Mouser 523-82-368) for the output connector and a male N (Mouser 523-49000) for the input, but you can use other suitable RF connectors. Now you can install Rt and Rs in place, taking care to make all connections as short as possible. A good method is to install an insulated standoff (with good RF characteristics) at the point where the transformer leads will be. Install a short ground lug under the standoff, where one of the transformer leads and the ground end of Rt can be soldered. At the top of the standoff, Rt, Rs and the other transformer lead will be connected. (Note: I didn't have a standoff short enough to fit, so I used the junction of Rt and Rs as a "standoff".) IMPORTANT! I learned the hard way that both Rt and Rs must be installed so that they have no parallel mechanical component with reference to the main line. Figures 3 and 4 will help understand the correct method. If you do not install them properly, the resistor will form a coupler to the main line. If you have the instrumentation, I suggest that you test your installation before proceeding with the sampler assembly, using the following method. Temporarily install a straight piece of wire between the input and output connector pins. (Do not place the transformer on this wire.) Connect a signal generator to the input port, and set it for a level around +10 dBm and a frequency of 30MHz. You should terminate the output port with a good 50Ω load. Connect a Spectrum Analyzer to the sample port. If the resistors are properly installed, you should see a signal at the sample port that is at least 90 dB lower than the signal generator level. On my sampler, I measured 104 dB. By the way, with Rt erroneously installed nearly parallel to the main line, the isolation was closer to 50 dB. Lesson learned!

Now it is time to install the transformer with the Faraday shield. Carefully drop it into place, soldering the center conductor of the RG-402 to the input and output connectors. Solder a short piece of braid from the shield of the RG-402 (nearest the INPUT port) to the ground lug. I used a piece of size .030" solder wick from Chemtronics for good conductivity and mechanical flexibility. Note that it is the connection of this braid that determines which of the N connectors becomes the input port.

Lastly, connect the transformer wires, one to the standoff, and one to the ground lug. You are now ready to perform some preliminary tests. The first is to ensure the coupling factor is close to 50 dB. Assuming Rt is accurate, the coupling factor is determined only by N, the number of turns on the transformer secondary. In my case, the coupling factor was within .1dB of the 50 dB design target. Another good test is what I call the "load/no load" test. Ideally, if you disconnect the 50Ω termination from the output port, the output at the sample port should drop to zero. This is because no current should be flowing in the main line, thus there should be no output at the sample port. However, due to a variety of things, but primarily capacitive coupling from the main line to the transformer windings, energy is present at sample port, even with no termination on the output port. This phenomenon worsens with increasing frequency, and is the main reason for the Faraday shield. As a test, connect a signal generator to the input port, set for 30 MHz and +10 dBm output. Terminate the sampler output port with 50Ω and measure the sample port output with a spectrum analyzer. Remove the termination and note the drop in the sample port output. As a reference, my experiments showed a 12 dB drop in a sampler without the Faraday shield installed. With the Faraday shield, the drop improved to about 38 dB. A final check on operation is to short the output port to ground. If the signal generator has a 50Ω source impedance, grounding the output should double the current, so the signal at the sample port should increase by about 6 dB.

There is a small amount of asymmetry to the design created by the grounding of the Faraday shield. What I mean by this is that the input and output ports are not perfectly interchangeable. Swapping the input and output ports reduces the high frequency response somewhat, but the response is still adequate for most monitoring applications. Figure 5 shows the high frequency response of my sampler with normal input/output connections.



RIGOL Ext Ref 12:15:22 2014-12-01 Local

Ref 0.00 dBm Att 10 dB Marker1 145.00 MHz -50.79 dB

Marker
145.000000 MHz
-50.79 dB

UserKey Set: System,

Center Freq 100.00 MHz Span 200.00 MHz
RBW 10.000 kHz VBW 3.000 kHz SWT 6.6666 s

Figure 5 – High Frequency Response of Sampler

The response at the sampled port is 1dB down from 50dB at a frequency of 145 MHz, which is easily good enough for HF work.

The low frequency response of the sampler is shown in Figure 6. The 1dB down frequency on the low end is about 580 kHz, very close to the calculated value.



RIGOL Ext Ref 12:48:40 2014-12-01 Local

Ref 0.00 dBm Att 10 dB Marker1 586.66 kHz -51.08 dB

Marker
586.666 kHz
-51.08 dB

UserKey Set: System,

Center Freq 1.0000 MHz Span 2.0000 MHz
RBW 3.000 kHz VBW 1.000 kHz SWT 666.66 ms

Figure 6 – Low Frequency Response of Sampler

Figure 7 below shows the insertion loss of the main line. Note that the scale is .1dB/division.



RIGOL Ext Ref 13:12:50 2014-12-01 Local

Ref 0.00 dBm Att 10 dB Marker1 90.000 MHz -0.06 dB

Marker
90.000000 MHz
-0.06 dB

UserKey Set: System,

Center Freq 100.00 MHz Span 200.00 MHz
RBW 30.000 kHz VBW 10.000 kHz SWT 666.66 ms

Figure 7 – Main Line Insertion Loss

Resistors Rt and Rs should be carbon film for good RF performance and small size. At 1500 Watts input, the power dissipated in Rt is only about 300 mW, even under the "worst case" condition when there is no termination at the sample port. So, a 500 mW resistor rating is fine. The power dissipated in Rs is considerably less than that of Rt.

Although calculations of magnetic flux density in the transformer core indicate it is operating well within the limits of the core, even at 1500 Watts, I do not have the equipment to quantify distortion that might be added by transformer core saturation affects. I've used the sampler to measure harmonics at the output of my 30L-1 and don't see any obvious problems. However, it would be great to measure the harmonic content of a 1500 Watt CW carrier using the sampler, then compare that to a measurement using a high power resistive attenuator. If anyone has the equipment to do that, I'd love to hear the results.

I created an Excel spreadsheet that allows you to choose different parameters for the sampler, including different powdered iron core sizes. It also calculates many other parameters should you be inclined to design a sampler with different characteristics. Let me know if you'd like a copy via email.

Have fun and treat that SA with care!
de Don, W5QN

CCA

Radio and Electronics Cookbook

Radio and Electronics Cookbook

Edited by
Dr George Brown, CEng, FIEE, M5ACN

Newnes
OXFORD AUCKLAND BOSTON JOHANNESBURG MELBOURNE NEW DELHI

Newnes
An imprint of Butterworth-Heinemann
Linacre House, Jordan Hill, Oxford OX2 8DP
225 Wildwood Avenue, Woburn, MA 01801-2041
A division of Reed Educational and Professional Publishing Ltd

A member of the Reed Elsevier plc group

First published 2001

© Radio Society of Great Britain 2001

All rights reserved. No part of this publication may be reproduced in any material form (including photocopying or storing in any medium by electronic means and whether or not transiently or incidentally to some other use of this publication) without the written permission of the copyright holder except in accordance with the provisions of the Copyright, Designs and Patents Act 1988 or under the terms of a licence issued by the Copyright Licensing Agency Ltd, 90 Tottenham Court Road, London, England W1P 0LP. Applications for the copyright holder's written permission to reproduce any part of this publication should be addressed to the publishers

British Library Cataloguing in Publication Data
A catalogue record for this book is available from the British Library

ISBN 0 7506 5214 4

RSGB
Lambda House
Cranborne Road
Potters Bar
Herts
EN6 3JE

Composition by Genesis Typesetting, Laser Quay, Rochester, Kent
Printed and bound in Great Britain

PLANT A TREE
BTCV
British Trust for Conservation Volunteers
FOR EVERY TITLE THAT WE PUBLISH, BUTTERWORTH-HEINEMANN WILL PAY FOR BTCV TO PLANT AND CARE FOR A TREE.

Contents

Preface ix

1. A medium-wave receiver 1
2. An audio-frequency amplifier 4
3. A medium-wave receiver using a ferrite-rod aerial 9
4. A simple electronic organ 12
5. Experiments with the NE555 timer 17
6. A simple metronome 21
7. What is a resistor? 24
8. Waves – Part 1 27
9. A beat-frequency oscillator 31
10. What is a capacitor? 34
11. Waves – Part 2 38
12. An LED flasher 41
13. Waves – Part 3 44
14. Choosing a switch 46
15. An aerial tuning unit for a receiver 49
16. A simple 2 m receiver preamplifier 52
17. Receiving aerials for amateur radio 54
18. The Colt 80 m receiver – Part 1 58
19. A crystal radio receiver 62
20. The varactor (or varicap) diode 64
21. A portable radio for medium waves 65
22. The Colt 80 m receiver – Part 2 70

23. A simple transistor tester 73
24. An introduction to transmitters 77
25. The Colt 80 m receiver – Part 3 81
26. A two-way Morse practice system 88
27. The Colt 80 m receiver – Part 4 91
28. A simple crystal set 95
29. A crystal calibrator 100
30. A simple short-wave receiver – Part 1 104
31. A fruit-powered medium-wave radio 106
32. A capacitance bridge 109
33. A simple short-wave receiver – Part 2 113
34. A basic continuity tester 117
35. A charger for NiCad batteries 119
36. An 80 metre crystal-controlled CW transmitter 123
37. A solar-powered MW radio 129
38. A receiver for the 7 MHz amateur band 133
39. Diodes for protection 137
40. An RF signal probe 140
41. An RF changeover circuit 142
42. A low-light indicator 146
43. A J-pole aerial for 50 MHz 149
44. Measuring light intensity – the photometer 153
45. A 70 cm Quad loop aerial 156
46. A UHF field strength meter 160
47. Christmas tree LEDs 162
48. An audio signal injector 166
49. Standing waves 168
50. A standing-wave indicator for HF 170
51. A moisture meter 174
52. Simple aerials 177
53. A breadboard 80 cm CW transmitter 182

54. A 7-element low-pass filter for transmitters 186
55. Radio-frequency mixing explained 189
56. A voltage monitor for a 12 V power supply 192
57. A 1750 Hz toneburst for repeater access 196
58. A circuit for flashing LEDs 201
59. Digital logic circuits 205
60. A resistive SWR indicator 210
61. An audio filter for CW 213
62. An electronic die 215
63. The absorption wavemeter 222
64. An HF absorption wavemeter 224
65. A vertical aerial for 70 cm 228
66. A UHF corner reflector aerial 230
67. A switched dummy load 234
68. A simple Morse oscillator 238
69. A bipolar transistor tester 240
70. The ‘Yearling’ 20 m receiver 245
71. Adding the 80 metre band to the Yearling receiver 251
72. How the Yearling works 255
73. A field strength meter 258
74. Preselector for a short-wave receiver 261
75. An audible continuity tester 265
76. An experimental 70 cm rhombic aerial 268
77. Water level alarm 272
78. A delta loop for 20 metres 275
79. A simple desk microphone 279
80. Morse oscillator 284
81. A simple 6 m beam 287
82. An integrated circuit amplifier 291
83. A novice ATU 293
84. CW QRP transmitter for 80 metres 297

85. An audio booster for your hand-held 303
86. A grid dip oscillator 306
87. A CW transmitter for 160 to 20 metres 312
88. Matching the end-fed random-wire aerial 315

Preface

Although we are surrounded by sophisticated computerised gadgets these days, there is still a fascination in putting together a few resistors, capacitors and the odd transistor to make a simple electronic circuit. It is really surprising how a handful of components can perform a useful function, and the satisfaction of having built it yourself is incalcuable.

This book aims to provide a wide variety of radio and electronic projects, from something that will take a few minutes to a more ambitious weekend's worth. Various construction techniques are described, the simplest requiring no more than a small screwdriver, the most complex involving printed circuit boards.

Originally published by the Radio Society of Great Britain, the projects were all chosen to be useful and straightforward, with the emphasis on practicality. In most cases the workings of the circuit are described, and the projects are backed up by small tutorials on the components and concepts employed. In the 21st century it may seem strange that few of the published circuits use integrated circuits (chips). This is intentional as it is much easier to understand how the circuit works when using discrete components.

Anyone buying the *Radio and Electronics Cookbook* will find that it will lead to hours of enjoyment, some very useful and entertaining gadgets, and increased knowledge of how and why electronics circuits work, and a great sense of satisfaction. Beware, electronic construction is addictive!

WARNING: This book contains construction details of transmitters. It is illegal to operate a transmitter without the appropriate licence. Information on how to obtain an Amateur Radio Licence can be obtained from the Radiocommunications Agency, tel. 020 7211 0160.

1 A medium-wave receiver

Introduction

Let us start off with something that is really quite simple and yet is capable of producing a sense of real satisfaction when complete – a real medium-wave (MW) radio receiver! It proves that receivers *can* be simple and, at the same time, be useful and enjoyable to make. To minimise the confusion to absolute beginners, *no* circuit diagram is given, only the constructional details. The circuits will come later, when you have become accustomed to the building process. In the true amateur spirit of ingenuity and inventiveness, the circuit is built on a terminal strip, the coil is wound on a toilet roll tube (as amateur MW coils have been for 100 years!), and the receiver is mounted on a piece of wood.

Putting it together

Start by mounting the components on the terminal strip as shown in **Figure 1**, carefully checking the position and value of each one. The three capacitors are all the same, and so present no problem. They (and the resistors) may be connected either way round, unlike the two semi-conductors (see later). The resistors are coded by means of coloured bands. You can refer to Chapter 7 if you have difficulty remembering the colours and their values.



Figure 1 Terminal strip – position of components

1. Brown, Black, Yellow	100 000 ohms	(R1, R5, R6)
2. Green, Blue, Brown	560 ohms	(R2)
3. Red, Violet, Brown	270 ohms	(R3)
4. Brown, Black, Orange	10 000 ohms	(R4)

The integrated circuit (the ZN414Z) and the transistor (the BC184) *must* be connected correctly. Check Figure 1 carefully before fitting each device.

Now wind the coil. Most tubes are about 42 mm diameter and 110 mm long. Don't worry if your tube is slightly different; it shouldn't matter. Make two holes, about 3 mm apart, about 40 mm from one end, as shown in **Figure 2**. Loop your enamelled wire into one hole and out of the other, and draw about 100 mm through; loop this 100 mm through again, thus anchoring the wire firmly. Now wind on 80 turns, keeping the wire tight and the turns close together but not overlapping. After your 80th turn, make another two holes and anchor the wire in the same way as before. Again, leave about 100 mm free after anchoring. Using another piece of enamelled wire (with 100 mm ends as before), loop one end through the same two holes which contain the end anchor of the last winding, wind two turns and anchor the end of this short winding using another pair of holes. Figure 2 shows the layout.



Figure 2 The layout of the parts on the wooden base

With some glass paper, remove the enamel from the ends of both pieces of wire which go through the same holes (i.e. the bottom of the large coil and the top of the small coil), then twist these bare ends together. Remove the enamel from the remaining ends of the coil. The coil is now finished!

The baseboard can be any piece of wood about 150 mm square. Fix the coil near the back edge using drawing pins and connect the wires from the coils to the terminal strip as shown in Figure 2. Using short pieces of PVC-insulated wire (and with assistance if you have never soldered before), solder one piece across the two outer tags of the variable capacitor, shown by the dotted line in Figure 2, and then two longer pieces to the centre tag and one outside tag. Connect these to the terminal strip. Then solder two more insulated wires on to the jack socket (into which you will plug your crystal earpiece), the other ends going to the terminal strip. The last two wires (one must be red) need to be soldered on to the battery box, their other ends going to the terminal strip also. Make sure the red wire goes to the *positive* terminal on the battery, and is connected to terminal 9. The other connection to the battery goes to terminal 10.

Attach the terminal strip to the baseboard with small screws or double-sided sticky tape. The other parts can be mounted the same way.

Listening is done ideally with the recommended crystal earpiece. Don't be tempted to use your Walkman earpieces; they are not the same and will not perform anything like as well. The receiver should work without an extra aerial, but one can be attached to terminal 1 if necessary. A long piece of wire mounted as high as possible is ideal. The *Audio-frequency Amplifier* project will enable you to use a loudspeaker with your receiver, using the signal from the jack socket. No circuit modifications will be needed!

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1, R5, R6	10 kilohms (kΩ)
R2	560 ohms
R3	270 ohms
R4	10 kilohms (kΩ)

Capacitors

C1, C2, C3	100 nanofarads (nF)
	500 picofarads (pF)

Semiconductors

ZN414Z, BC184

Additional items
- 12-way 2 A terminal strip
- 22 metres of 28 SWG enamelled copper wire
- A few short pieces of coloured PVC-insulated wire
- Crystal earpiece
- 3.5 mm jack socket
- 1.5 V AA-size battery and box
- Toilet roll tube
- Double-sided sticky tape or selection of screws

Tools required

Small screwdriver, soldering iron.

2 An audio-frequency amplifier

Introduction

This simple amplifier can be built by anyone who is able to solder reasonably well. It doesn't require any setting up and, provided our instructions are followed exactly, will work very well. The circuit diagram is included for the benefit of our more advanced readers, but it is not needed in the construction process. Please practise your soldering before you start, and don't use a printed circuit board (PCB) until you are confident that your soldering is up to scratch.

The amplifier can be used with other projects; it will provide plenty of sound from the MW Radio or from the Morse Sounder projects. It will usually be built into other pieces of equipment, so a box is not supplied with the kit. There is no reason why it shouldn't be put into a box and used as a general-purpose amplifier to help test other projects.

The components

Before you start, you should check that you have *all* the components to hand. A list and some helpful hints are given below.

1. PCB. The plain side is the *component side* and the soldered side is the *track side*. **Figure 1** shows the track side full size. Make the PCB from the pattern given in Figure 1. Otherwise, build the circuit on a matrix board.
2. Three resistors. Locate the gold or silver band around the resistor, and turn the resistor until this band is to the right. There are three coloured bands at the left-hand end of the resistor. Find the resistor whose colours are YELLOW, VIOLET, RED, and look at the resistor colour code chart which you will find in Chapter 7. From this, you will see that YELLOW indicates the value 4, VIOLET the value 7, and RED the value 2. The first two colours represent real numbers, and the last value is the number of zeros (noughts) which go *after* the two numbers. So, the value is 47 with two zeros, i.e. 4700 ohms. In this way, the resistor coloured BROWN, GREY, BROWN has a value of 180 ohms, and the last one, BROWN, RED, GREEN, has a value of 1 200 000 ohms. The ohm (often written as the Greek letter omega (Ω)) is the unit of resistance. If you do not yet feel confident in identifying resistors by their colours, use the Resistor Colour Codes given in Chapter 7.
3. Four capacitors. The two small 'beads' are tantalum capacitors and will be marked 4.7 μF or 4μ7, with a '+' above one lead. A tubular capacitor with wires coming from each end should be marked 220 μF, with one end marked '+' or '–'. This is called an *axial* capacitor because the wires lie on the axis of the cylinder. This is in contrast to the final capacitor, where both wires emerge from the same end. This is a *radial* capacitor, and will be marked 47 μF. Again, one lead will be marked '+' or '–'. Capacitors marked like this are said to be *polarised*, and it is vital that these are placed on the PCB the right way round, so take notice of those signs!
4. Two diodes. These are tiny glass cylinders with a band around one end, and may be marked 1N4148; this is their type number. Like polarised capacitors, they *must* be put on the PCB the correct way round!



Figure 1 The toil pattern of the PCB – looking from the track side

5. Three transistors. One should be a BC548 (or a BC182), the other two should be BC558 (or BC212).
6. One volume control with internal switch.
7. One loudspeaker. This is quite fragile – don't let anything press against the cone.
8. One PP3 battery clip with red and black leads.

Putting it together

Lay the PCB on a flat, clean surface with the track side downwards. It is always useful to compare the layout with the circuit diagram, given here in **Figure 3**. Although you can't see it, the D-i-Y Radio sign should be at the top. Compare the hole positions with those shown in **Figure 2**. Bend the resistor wires at right angles to their bodies so that they fit cleanly into the holes in the PCB. Push each resistor towards the board so that it lies flat on the board. Then supporting each one, turn the board over and splay out the wires *just* enough to prevent the resistor falling out. Then, solder each wire to its pad on the PCB, and cut off the excess wire. When you have more confidence, you can cut of the excess wire *before* soldering; it often makes a tidier joint.



Figure 2 Positions of the components on the printed circuit board (PCB)


LOUD-
SPEAKER
R2
4k7
TR3
BC548
C3
47μ
D2
1N4148
R1
180R
C4
220μ
9 V
D1
1N4148
INPUT
C1
4μ7
R3
1M2
TR2
BC558
VR1
25k
Log
C2
4μ7
TR1
BC548
S1 on
back of
VR1

Figure 3 The amplifier's circuit diagram

Now fit the four capacitors. Each must be connected the right way round, so look at each component, match it up with the diagram of Figure 2, bend its wires carefully and repeat the soldering process you performed with the resistors, making sure that the components are close to the board and not up on stilts! Fit the two diodes the correct way round, and solder then as quickly as you can – they don't like to be fried!

Mount the transistors about 5 mm above the PCB. Make sure the correct transistors are in the correct places, and that the flats on the bodies match up with those shown in Figure 2.

Mount the volume control so that the spindle comes out from the front of the board. Use a piece of red insulated wire to the pad marked + on the PCB, and a black piece to the pad marked –, and solder these to the tags on the back of the control, as shown in **Figure 4**. Connect the two leads from the battery clip to the other tags on the switch; Figure 4 will help you. Finally, use two pieces of insulated wire about 100 mm long, twisted together, to connect the loudspeaker to the PCB.


PP3 Battery Clip
RED
BLACK
0V (-)
on PCB
+9 V

Figure 4 Connections to switch on back of VR1

Box clever!

If you wish to put the amplifier into a box, there is no problem; almost any box that is big enough will do. All that is needed is one hole big enough to accept the bush of the volume control; the PCB will be supported by the volume control. The prototype was not fitted into a box, but mounted on an odd piece of aluminium, bent into an L-shape and screwed on to a wooden base. The loudspeaker was mounted on the aluminium panel by two small pieces of aluminium with 3 mm holes drilled in them, which acted as clips around the edge of the speaker. Drill a few holes in the panel in the position of the speaker to let the sound get out!

Your input signal can be connected to the amplifier with two short pieces of wire, but if the connection needs to be long, use screened cable, with the braid connected as shown in Figure 2.

If you decide to use a different loudspeaker, make sure that its impedance (the resistance value marked on the back of the magnet) is at least 35 ohms. Anything lower may damage TR2 and TR3, and will certainly run down your battery very quickly. You will be surprised at the uses you can find for this little amplifier!

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1	180 ohms (Ω)
R2	4.7 kilohms (kΩ)
R3	1.2 megohms (MΩ)
VR1	25 kilohms (kΩ) log with DPST switch

Capacitors: all rated at 25 V minimum

C1, C2	4.7 microfarads (μF)
C3	47 microfarads (μF)
C4	220 microfarads (μF)

Semiconductors

TR1, TR3	BC548 npn
TR2	BC558 pnp
D1, D2	1N4148

Additional items

- PCB
- Speaker >35 ohms
- PP3 battery clip and battery

3 A medium-wave receiver using a ferrite-rod aerial

Introduction

This design came from the Norfolk Amateur Radio Club, and enables you to build a simple Amplitude Modulation (AM) receiver for frequencies between 600 kHz and 1600 kHz. It should take you around 2 hours to build, and can be used with Walkman-type earpieces. **Figure 1** shows the circuit diagram.


On/Off switch
Radio chip
ZN416E
Coil
VC1
1
2
3
4
5
6
7
8
C1
C2
C3
C4
Headphones
Battery
+
−
Wrapped over ferrite rod
HOW IT WORKS
Coil + VC 1
Radio signal
Radio chip + C1, C2, C3 and C4
Sound signal
Headphones
Allows you to select or 'tune' the radio signal
Magnify the radio signal and change it into a sound signal
Change the sound signal into sound you can hear
Battery
Supplies electricity (energy) to keep it all working

Figure 1 Circuit and block diagrams of the radio

Description

The whole circuit is built on a 50 mm by 50 mm printed circuit board (PCB) designed to fit on the inside of the lid of a plastic box, and is stuck there using sticky pads, the shaft of the variable capacitor going through a hole in



Figure 2a The PCB, solder side



Figure 2b The PCB, component side

the lid. Only two pairs of leads are soldered to the board – one pair goes to the 1.5 V battery in its holder, and the other to the earphone socket. **Figures 2a** and **2b** show the printed circuit and the component layout double size for clarity. You are not obliged to build the circuit on a PCB.

Building it

1. **Check and identify components**. Tick the parts list.
2. **Carefully unwind the wire.** Use paper to make an insulating tube (called a 'former') around the centre of the ferrite rod and secure it with Sellotape. Now, close-wind *all* the wire (leave no gaps between adjacent turns) around the paper former. Secure the winding with more Sellotape, leaving 50 mm of wire free at each end for connection to the circuit. See **Figure 3a.**
3. **Solder in VC1.**
4. **Solder in the integrated circuit holder.** There is a notch in one end of the holder; this should face VC1. Solder also the wire link and the capacitors. Be careful to avoid solder 'bridges' between adjacent tracks on the PCB.
5. **Solder the battery leads.** These must be connected properly – the red battery lead to the + (positive) area and the black lead to the – (negative) area.
6. **Strip bare 1 cm of insulation from the ends of two wires**. Solder them between the PCB and the headphone socket (see **Figure 3b**). Use the end tabs on the socket. Using another pair of insulated wires connect the ON/OFF switch to the PCB tabs shown in Figure 2b.



Figure 3 Details of coil and headphone socket

7. **Fix the elastic band.** This goes through the holes at the top of the PCB, with the ferrite rod being slipped through the two end loops. (Note: although the coating on the copper wire is designed to melt away during soldering, it is quite common for difficulty to be experienced in obtaining a good soldered joint; to be on the safe side, remove the coating *before* soldering (with a small piece of sandpaper).) Carefully place the wire ends of the coil through the PCB just above VC1, and solder on the track side.
8. **Fit IC1 into its holder.** This should be done carefully, making sure that *all* the pins are located above their respective clips *before* applying any pressure! Make sure also that the notch on the IC (as shown in Figure 2b) matches the notch in the holder, and faces VC1.
9. **Put battery in its holder.** Listen for some noise in the headphones as VC1 is rotated. Make sure the headphone plug is fully inserted into its socket.
10. **Fix the working board to the lid.** Use the sticky pads and apply *gentle* pressure. Fit the tuning knob, the ON/OFF switch and the earphone socket.
11. **Test again.** If all is still working, fit the lid screws and admire your completed radio!

Parts list

Capacitors

C1, C2	0.01 microfarad (μF)
C3, C4	0.1 microfarad (μF)
VC1	500 picofarads (pF)

Semiconductor

IC1	ZN416E

Additional items
- Plastic box (recommended size 76 × 64 × 50 mm internal)
- 8-pin DIL socket for IC1
- Printed circuit board
- Tuning knob for VC1
- Wire link for PCB
- 2 m of 30 SWG copper wire, self-fluxing
- Piece of paper 25 × 50 mm, to make the coil former
- Ferrite rod 70 mm long by 10 mm diameter, approximately
- Battery, AA size 1.5 V, with holder and attached wires
- Miniature earphone socket (3.5 mm stereo jack)
- ON/OFF switch (push-button SPST latched or slide switch)
- 4 off 100 mm insulated connecting wires, for jack socket and ON/OFF switch
- Pair Walkman-type earphones
- Elastic band, to attach ferrite rod to PCB
- 4 off sticky pads for securing PCB to box lid

Kits

Ready-made PCBs may be available from Alan J. Wright, G0KRU, Hewett School, Cecil Road, Norwich NR1 2PL.

4 A simple electronic organ

Introduction

This project has nothing to do with radio but, let's admit it, *any* electronics project is good experience! Why not build this little organ – it will keep the children amused at least! It uses the popular NE555 integrated circuit, which contains a circuit which will periodically switch the voltage on the output pin between the supply voltage and zero. Just how frequently this switching occurs depends upon the components external to the integrated circuit. If this switching occurs several hundred or thousand times a second, the change in voltage produced will generate a musical note when connected to a small loudspeaker. The circuit is shown in **Figure 1**.


+9V
R1
7
4
8
P1
P10
IC1
6
3
2
1
S
(350Ω)
R2
C1
-

Figure 1 Circuit diagram

Putting it together

(a) Using a PCB. The job is very simple. The placement of components on the unsoldered side of the board is shown in **Figure 2** and the design on the copper track is illustrated in **Figure 3**. Put each component, in turn, on the board, making sure that it lies flat on the board with its tags or wires going cleanly through the holes provided for it; then, solder the wires to the board, cropping them before or after the soldering,


C 523
D 587
E 659
F 698
F# 740
G 784
A 880
B 988
C 1046
D 1174
Frequency (Hz)
Solder pins
P1
P2
P3
P4
P5
P6
P7
P8
P9
P10
R1
R2
IC1
C1
+
S
S -
Battery clip
9V
Loudspeaker

Figure 2 Position of components on the printed circuit board (PCB)



Figure 3 The connections

depending on your preference. If you choose to use a holder for your integrated circuit (highly recommended if your soldering is less than perfect), make sure that the end with a notch in it faces R1 and R2, as shown in Figure 2. Solder the two leads to the speaker to the tabs marked S (either way round), having looped them through the two holes to the right of the tabs in Figure 2. Looping them through the holes acts as a strain relief, ensuring that the soldered joints are not subjected to pulling and bending as you move the wires about. Do the same with the battery leads, the red lead going to the + tab and the negative lead to the – tab (which also has one speaker lead already attached to it). **Figure 4** shows this in detail. Treat the loudspeaker with care – the cone is quite fragile and must not be touched.



Figure 4 Battery plug and loudspeaker connections

(b) Without a PCB. This is more difficult, and you may need to enlist some help. Using some matrix board (such as Veroboard) is probably the best way of replacing the PCB. You could arrange your circuit in exactly the same way as in the PCB in Figure 3, using wires to replace the copper track.

A simple ‘keyboard’

The keyboard is a row of solder pins along the rear edge of the PCB, one for each note covering the range shown in Figure 2. A flying lead with a small spade on it is provided to touch any of the pins in turn, producing any one of ten different notes.

Testing

Check first that each component is in the correct place. When inserting the NE555 chip, first make sure that the end carrying the notch lies over the end of the holder with the notch; then, make sure each pin of the chip lies directly above the hole into which it fits, before pressing *gently* to insert the chip into the socket. Make sure the battery connections are correct, and insert the battery into the clip. Nothing should happen, except for a click from the loudspeaker; touching the spade on any of the pins should produce a coarse note from the speaker. If nothing happens, check everything again; don’t *assume* that wires go where you think they go!

After you get the first note, all the others should work, too, but they will sound off-tune at first. The organ needs tuning up by adjusting the 10 preset variable resistors P1 to P10. The approximate frequency to which each note should be tuned is given in Figure 2; if you can beg, borrow or steal a frequency counter, setting up is easy. If you have a piano, the organ can be tuned by comparison of the notes with those on the piano. The frequencies are given in Hertz (abbreviation Hz), and represent the number of times the IC switches on and off every second. If the sound coming from the loudspeaker is too loud or very distorted, then try putting an 330 Ω resistor (colour code orange, orange, brown) in series with the loudspeaker. This is done by taking the resistor and cutting its leads to about 5 mm; then, disconnect one speaker lead from the tab on the PCB (it doesn’t matter which). Solder one end of the resistor to the vacated speaker tab, and the free speaker lead to the other end of the resistor. This will limit the volume of sound from the speaker, and lengthen the life of your battery. If it is still too loud, try a resistor of a larger value, or use a smaller resistor to make it louder.

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1	2.7 kilohms (kΩ)
R2	1 Megohm (MΩ)
P1–P5	Preset resistor 100 kilohms (kΩ)
P6, P7	Preset resistor 50 kilohms (kΩ)
P8	Preset resistor 25 kilohms (kΩ)
P9, P10	Preset resistor 10 kilohms (kΩ)

Capacitor

C1	100 nanofarads (nF) or 0.1 microfarad (μF)

Integrated circuit

IC1	NE555 timer chip

Additional items

S	Loudspeaker >60 ohms (Maplin)
	1 off battery clip (for PP3 battery)
	1 off spade terminal
	12 off solder pins ‘Veropins’
	3 off 10 cm lengths of ‘hook-up’ wire

(This article is based on projects originally designed by Radio Scouting, Netherlands.)

5 Experiments with the NE555 timer

Introduction

Several of the projects in this book use the NE555 timer, an integrated circuit which is at the heart of many circuits whose processes are determined by time intervals. **Figure 1** shows the circuit diagram of an audio oscillator using the 555. The timing voltages (governing the frequency of oscillation) are produced by R1, R2 and C2; a voltage appears at pin 3 which ‘switches’ at this frequency between zero and a voltage close to the supply voltage, which in this case can be anywhere between 6 V and 14 V. The output current, when applied through R3 to a small loudspeaker, produces an audible tone, provided that there is a DC path between the two test leads.


Positive test lead
Negative test lead
R1 4k7
R2 39k
C2 22n
IC1 NE555
4
8
7
6
2
1
3
R3 330R
Loudspeaker
C1 100µ 25V
+
−
6 to 14 Volts DC
+
−
Pin 5 of IC1 is not used
Dot
Notch
There will either be a notch or a dot in the plastic body of IC1 which tells you which way round to mount it – mount IC1 as shown
1
2
3
4
8
7
6
5
IC1 looks like this
Markings (type number, manufacturer, country of origin, etc)

Figure 1 The circuit diagram

Construction

The simplest way to mount the components is on a piece of matrix board (Veroboard), available from any of the good suppliers. The prototype of this circuit used the type of board with copper strips along the underside; these strips are used like the copper tracks on a PCB, to join components together. Firstly, cut the four strips between the positions of the pins of the IC socket, as shown in **Figure 2**. You can buy a tool for this purpose, but a small twist drill (about 3 mm diameter) is just as good. Turn it between your fingers – if you use a drill you will end up with holes right through the board! Then solder in the IC socket (with the notch in the position shown), followed by the four links made with single-conductor insulated wire. Put in each component as shown, ensuring that C1 (an *electrolytic* or *polarised* capacitor) is connected correctly. When all the components have been soldered in, take the 555 chip and lay it on its socket, with its own notch lying above that of the holder. Then, making sure that each pin lies *directly* above its corresponding socket, press down *gently* on the chip, with the board supported on a flat surface.

Testing

Connect the circuit to a battery or small power supply, ensuring that the positive and negative leads are the right way round. Always use red and black leads here, then you are less likely to get it wrong! Switch on. Nothing


1 2 3 4 5 6 7 8 9 10 11 12 13
Positive test lead
Negative test lead
A
B
C
D
E
F
G
H
I
J
K
L
IC socket
1
2
3
4
8
7
6
5
IC1
R1
R2
R3
C1
+
–
C2
Positive lead to battery / power supply
This marking shows negative lead of C1
R2 is mounted vertically
Loudspeaker
Negative lead to battery/ power supply
Copper strips cut here between IC socket pins (E5, F5, G5 and H5)
Direction of the eleven copper strips (each strip must have thirteen holes)
Note that copper strips C, D and I are not used
L indicates insulated wire links

Figure 2 Veroboard layout. If you can read a circuit diagram, the project can be built using other methods

should happen until you short together the two test leads, when there should be a note from the loudspeaker. If this doesn't happen, switch off, disconnect the circuit and check your wiring and soldering. Is it exactly like Figure 2? Are the soldered joints round and shiny? If any are dull, then 'sweat' them briefly with a hot soldering iron until the solder runs, remove the iron, and check that they are as shiny as the rest. Check that there are no solder 'bridges' between adjacent tracks by holding your board up to a strong light. Then, reconnect, switch on and touch the test leads together. All should now work!

Uses of your circuit

1. As a Morse practice oscillator. Simply connect the two test leads to your key and, each time the key is pressed, you should hear a note from the speaker. The frequency of the note may be altered by putting a resistor in series with the key. To do this, remove one test lead from the key and select a resistor; connect one end of the resistor to the free test lead and the other to the empty terminal on your key. Selecting the value of resistor that you need will be a useful experiment in itself.
2. As a continuity tester. You can check fuses and lamp bulbs by connecting them across your test leads. If the speaker remains silent, the fuse or bulb has blown.
3. To indicate changes of resistance. Hold the ends of the test leads in each hand; you should hear a low note, because of the high resistance of your body. Squeeze the ends harder, and the frequency of the note should rise, because you are now making better contact. Repeat this with damp hands and the frequencies will be higher still.
4. As a thermometer. Connect the test leads to a thermistor (a device whose resistance changes with temperature) and warm it with a hair-dryer, or even in your hands, and you will hear the pitch changing with the temperature of the thermistor. A suitable 'bead' thermistor is available from Maplin (order code FX21).
5. As a diode tester. Use any diode, and connect the negative test lead to the end of the diode marked with the ring. This is the cathode of the diode. The other end, the anode, should be connected to the positive test lead, and a note should be heard from the speaker. This does not necessarily mean that the diode is working – yet. Reverse the connections and *nothing* should be heard. If this is the case, the diode *is* working.
6. As a light meter. Use a photoconductive cell (a device whose resistance changes with light intensity) connected between the test leads. A note should be heard. Shading the device with your hand will increase its resistance and the note should decrease in frequency. A suitable device is the ORP12 cell from Maplin (order code HB10).

There are many more applications. **Do not connect the test leads to other circuits that are switched on.** Your circuit, or the circuit you are connecting it to could be damaged. Think of a *passive* device or circuit (i.e. one *not* requiring a power supply or battery) where changes of resistance occur, and you have found another application!

Parts list

Resistors: all 0.25 watt carbon film types

R1	4.7 kilohms (kΩ) – yellow, violet, red
R2	39 kilohms (kΩ) – orange, white, orange
R3	330 ohms (Ω) – orange, orange, brown

Capacitors

C1	100 microfarads (μF) 25 V radial electrolytic
C2	22 nanofarads (nF) or 0.022 microfarad (μF) polyester type with 10 mm lead spacing

Integrated circuit

IC1	NE555

Additional items

Miniature loudspeaker (preferably 35, 40 or 80 ohm)
8-pin DIL socket for IC1
0.1 inch Veroboard (‘stripboard’), size 11 strips by 13 holes
PVC-covered stranded wire for test leads, loudspeaker and battery connections
PVC-covered solid wire for links on the board
A power source of between 6 V and 14 V, such as a 9 V battery (PP3)

Component sources

Cirkit
Tandy – many high street shops

6 A simple metronome

Introduction

A metronome is a device used by musicians to indicate the tempo of a piece of music. Until electronics came on the scene, this 'beating of time' was achieved in much the same way as a clock keeps time, i.e. with a pendulum device, the clicking of the escapement indicating the beats of the music.

Those of you who have already built the Morse Key and Buzzer from the designs in this book, will recognise the circuit of this metronome – it is exactly the same as was used to produce the note of the buzzer. This circuit is shown in **Figure 1**.

The circuit

Three components determine the speed at which the circuit oscillates – the speaker (LS), the resistors (VR1 + R1) and the capacitor (C1). VR1 is a variable resistor, so that the speed at which the oscillator operates can be varied. Compared with the component values of the Morse Buzzer (which operated at around 800 Hz), these components now give an oscillation frequency of around 1.25 Hz, which is far too low to be heard as a note. What we *do* hear, however, is a series of clicks, as the voltage across the speaker changes quickly from 0 to 9 V and back again.



Figure 1 The metronome circuit is rather like the Morse oscillator


4cm x 4cm of plain perforated board
(without copper strips)
S1
+9V
RV1
R1
TR2
e
b
c
LS
c
b
TR1
e
+ C1
–ve
LS
● indicates solder joint
-----indicates wires on underside of board

Figure 2 The component wires are pushed through holes in the circuit board and joined together underneath

Variation of speed could be achieved by varying resistance or capacitance. However, as you may already know, variable capacitors have values in the picofarad range, not the tens of microfarads used here, so it is very simple to employ a variable resistor (potentiometer) to control the oscillator. You could use a multi-way switch to switch in one of several capacitors, as well as having the variable resistor, but this was found to be an unnecessary complication. This design operates between about 100 clicks per minute and 200 clicks per minute.

Making the prototype

A single piece of plain matrix board (no copper strips) measuring about 40 × 40 mm is sufficient to hold all the components except the potentiometer and switch (see later). The case can be plastic or aluminium, and one measuring 65 × 100 × 50 mm is about right. Make sure there are holes in the case beside the speaker cone to let the sound out, and larger holes for the potentiometer and switch. If a potentiometer is used with a combined ON/OFF switch, then the extra hole for the switch is not necessary! It is advisable to construct the circuit *before* putting it in the box, so that it can be tested to ensure that everything is working. If it is, then you can exercise your ingenuity in mounting the speaker, battery and board inside the box. A final test can be made before starting the calibration process.

Calibration

There is no ‘easy’ way to do this. The frequencies involved are too low to be measured with the average frequency counter, so you will need to resort to using a stopwatch and counting the number of clicks per minute.

Parts list

Resistors: 0.25 watt, 5% tolerance

R1	10 kilohms (kΩ)	
VR1	47 kilohms (kΩ) linear potentiometer	

Capacitor

C1	33 microfarads (µF) electrolytic	

Transistors

TR1	2N3053	npn
TR2	2N2905	pnp

Additional items

S1	SPST	ON/OFF switch
LS	3 ohms (Ω)	loudspeaker
	Knob with pointer for VR1	
	PP3 battery and connector	
	Aluminium case, 65 × 100 × 50 mm	
	Matrix board (plain), 40 × 40 mm	

7 What is a resistor?

Introduction

Materials that carry electricity easily are called **conductors**. They include all metals and salt water, for example. We use wire as a conductor, and the ease with which it passes an electric current depends upon the material, its thickness and its length. Silver (symbol Ag), gold (Au), copper (Cu) and aluminium (Al) are the best metallic conductors. Most wires are made of copper, although the best conductor, weight for weight, is aluminium.

Materials that *don't* carry current (or, at least, do so very badly) are called **insulators**, and they include dry wood, rubber, plastic and glass among their number. Wires are often coated with a layer of insulator to prevent adjacent wires touching and causing an accident.

Resistors

If there wasn't such a thing as resistance, the subject of electronics wouldn't exist; only infinite currents would flow and voltages wouldn't exist either! We need to reduce the flow of current if we are to make current do something useful for us. Components that resist the flow of current are called **resistors**, and they are said to have a **resistance** which is measured in ohms (Ω), named after Georg Ohm, who formulated the law (also named after him) by which the voltage and current through a conductor are related. His law gave rise to the formula *everyone* remembers:

$$I = \frac{V}{R},$$

where I is the current flowing, measured in amps,
V is the voltage across the conductor, and
R is the resistance of the conductor, measured in ohms.

From this equation, you can see that, for a constant value of voltage, V, if the resistance goes up, the current will go down, and vice versa. The circuit symbols for resistors are shown in **Figure 1**. You will find the upper symbol in older magazines; it is still preferred by many engineers. The lower symbol is the prevalent standard symbol.

Resistors are made in several ways, the cheapest using carbon; another type is usually made from a ceramic cylinder (used only as a support) on which



Figure 1 Circuit symbols for resistors

is placed a very thin film of metal – the thinner the film, the greater the resistance. All resistors are coated with a thin film of insulation, for the same reason we discussed earlier.

The colour code

Each resistor has coloured bands on it which enable us to see what value of resistance it has. There are normally three (but sometimes four) at one end, and a single one at the other (see **Figure 2**). The colours indicate figures, according to the list below.

Colour	*Value*	*Colour*	*Value*
Black	0	Green	5
Brown	1	Blue	6
Red	2	Violet	7
Orange	3	Grey	8
Yellow	4	White	9



Figure 2 Some examples of resistor colour codes; top 4700 Ω (4.7 kΩ) and bottom 100 Ω

Using the colour codes is easy, once you see the logic behind it. Hold the resistor so that the single band is towards the right. The three colours on the left are read in the normal order from left to right. The first two bands *always* indicate numbers; the third band gives the number of zeros to add to the right of these two numbers. So, looking at the top resistor in Figure 2, yellow, violet, red means 4, 7, and two zeros, giving 4700 ohms! Looking at the lower resistor, brown, black, brown means 1, 0, and one zero, giving 100 ohms.

Remembering the order of the colours may be difficult at first. The colours from red to violet are the colours of the rainbow, in order, so if you know those, you're almost there! Around those colours are black and brown below the red, and grey and white above the violet, which you can imagine as getting brighter from black to white (well, almost!). It won't be long before you don't need to remember them at all.

The isolated band on the right-hand side is not part of the resistor's value; it indicates its *tolerance*, i.e. how close it might be to the indicated value. A brown band indicates ±1%, a red band ±2%, a gold band ±5% and a silver band ±10%. For example, a resistor marked as being 100 ohms with a ±5% tolerance will have an *actual* value somewhere between 95 ohms and 105 ohms.

8 Waves – Part 1

Introduction

Waves are responsible for most of the processes in life where energy is transferred from one place to another. Heat and light energy from the sun, for example, come to us as *electromagnetic waves*. Sound travels through the air as a wave; it is not the same sort of wave as light or heat, but it obeys many of the same properties. Damage is caused to coastal margins by the waves of the sea – again, another type of wave, but still obeying many of the same properties. Radio waves are of the same type as heat and light waves, as are gamma rays, X-rays, ultra-violet waves and infra-red waves. So, once we begin to understand what radio waves do, we are also learning about a huge chunk of physics at the same time! All these waves are part of the *electromagnetic spectrum*. The word ‘spectrum’ simply means a ‘range’, so what we have is a range of electromagnetic waves – that’s all!

Sensing things

Light waves are invisible, but our eyes can detect the *effect* they have on different materials because the waves produce an effect on the retina of the human eye which the brain can interpret. We cannot see heat waves either, but we can feel the *effect* they have on our skin. Gamma rays and X-rays are also invisible, but their detrimental *effects* on human tissue are well known. It is not surprising, then, that we cannot see radio waves. We cannot sense them, either, until we produce a device upon which they have an *effect*. That device is a **radio receiver**; it is able to process certain characteristics of radio waves, and make these characteristics audible by generating sound waves from the loudspeaker or headphones. Other characteristics of the same waves may be turned into light as a TV picture on a cathode-ray tube, or as a fax image on a sheet of paper.

Visible waves

Let’s start our description with some waves that we can actually see! When a small stone is thrown into a pond, we see circular water waves *radiating* from the point where the stone fell into the water, as **Figure 1** shows. (Notice that we use the word *radiating*, even with water waves; it is not a radio term, but one which describes any motion where the *radius* of a circle is increasing. In this case, it is the radius of the circular waves which is


Splosh!
Waves spread out in all directions

Figure 1 The waves move out from the point where the stone landed

increasing.) If you were to watch the water waves down at the water level, perpendicular to the direction in which they are travelling, you would see something like the illustration in **Figure 2**.

The horizontal line represents the water level before the wave started, and the vertical line represents the direction in which the water is displaced at any instant.

All waves are described in the same way

'Freezing' the motion of the water in this way allows us to define two very important characteristics of a wave, characteristics which we talk about every day – *wavelength* and *amplitude*. The wavelength of a wave is simply the distance (measured in metres) from any point on one wave to the same point on the adjacent wave. Look at the diagram and you will see what is meant by 'the same point on the adjacent wave'. The amplitude of a wave



Figure 2 A water wave, viewed in cross-section

is always measured from the centre (undisturbed) position of a wave to the peak (or the trough) of the wave. Both these positions are shown, the arrow indicating that the measurement is taken *from* the centre *to* the peak or trough. The amplitude of a wave is defined as the maximum displacement of the wave from the centre position – the direction (up or down) of that displacement does not matter. Waves of greater amplitude carry more energy with them.

If we now 'unfreeze' the wave, we will see it travel from left to right (or right to left, depending on where we are looking). The speed at which it moves is called its *velocity*, and is measured in metres per second.

Another useful word is *propagate*; it means *travel*. We talk about radio waves propagating from a transmitter to a receiver. This velocity of propagation (for electromagnetic waves) is very fast indeed – they will cover 300 million metres in one second. This is virtually incomprehensible, so think of a radio wave travelling around the earth – it can travel 7½ times round the earth in one second! We use the symbol c for the velocity of radio waves (which is the same as the velocity of light, of course – all electromagnetic waves travel at this speed through air and space).

The last thing we need to know about the wave is its *frequency*. Imagine a cork floating on the water in the path of the wave; it will bob up and down. If we were able to count the number of times it went through its highest position in one second, then that number would be its frequency. Any periodic motion like this is said to go through one *cycle* each time one complete wave passes a point (in this case, our cork). We are thus counting the number of cycles per second of the cork's motion. The unit of frequency is thus 'cycles per second'; this unit is now named after Hertz, a radio pioneer, and is abbreviated to Hz.

Our description of the wave is now quite simple – we need only four quantities:

(a) **Frequency** symbol f – unit, hertz (Hz)
(b) **Wavelength** symbol λ (Greek letter lambda, pronounced 'lamb-da') – unit, metre (m)
(c) **Amplitude** symbol a – unit depends on application
(d) **Velocity** symbol c – unit, metres per second (m/s or ms^{-1})

The basic formula

Whatever may happen to a wave while it travels through different media (vacuum, air, brick, wood, etc.), one thing and **only** one thing remains constant – its frequency. Its wavelength, amplitude *and* velocity may change, but its frequency never does. Three of the four characteristics already identified are connected by the simple relationship

$$c = f \times \lambda.$$

Remember that *c* is constant if the wave travels in air or in a vacuum. This means that waves having higher frequencies (*f* large) must have smaller wavelengths (λ small) and vice versa. You can imagine frequency and wavelengths being on opposite ends of a see-saw!

Divisions of units

Because the frequencies of radio waves are so high (despite them having the lowest frequencies in the electromagnetic spectrum!) we have a problem with writing them down. Do you write in your log book that you have just heard a station on 14 100 000 Hz? Of course not, you write it as 14.1 MHz, knowing that the prefix mega (M) means 'one million'. The prefixes which you need to know (when applied to frequency) are:

kHz	kilohertz	meaning	1000 Hz
MHz	megahertz	meaning	1 000 000 Hz
GHz	gigahertz	meaning	1 000 000 000 Hz.

Notice that the 'k' in kilohertz is a lower case letter. It is **incorrect** to write it as an upper case letter. 'K' is a computer-related prefix meaning **not** 1 000 but 1 024!

When we come on to discuss heat and light waves, we will use wavelengths rather than frequencies, because of the see-saw effect – as the frequencies get larger and larger, the wavelengths get smaller, and hence are numbers which are more manageable, both to talk about and to write down!

Bands

Gamma rays, X-rays, ultra-violet waves, light waves, infra-red waves are all part of the electromagnetic spectrum, but we divide them up because they have different properties. This is why we divide up our radio frequencies into different bands. The radio waves of top-band signals (around 2 MHz) have completely different properties compared with those in the 20 metre band, so we are dividing up the *radio spectrum* in the same way – by property.

9 A beat-frequency oscillator

Introduction

Many readers will know that, although they have a short-wave radio which covers at least one of the amateur bands (e.g. 7 MHz or 14 MHz), they are unable to listen to SSB or Morse signals. This is because the receiver lacks a Beat-Frequency Oscillator (BFO). We need the 'carrier' frequency of a BFO to replace the carrier that has been removed from the signal at the transmitter. When listening to Morse signals, the BFO signal 'beats' with the incoming signal to produce a note in the loudspeaker. If you are a musician, you will be familiar with the method of using 'beats' to tune one musical instrument from another; in the BFO, the beat frequency produced is the tone signal you hear.

In the more complex amateur radio receiver, a BFO is incorporated as part of the whole system. In our model, it is an external circuit that sits alongside your radio. The circuit diagram is shown in **Figure 1**.

Construction

Built on a small piece of matrix board about 80 × 50 mm, the circuit can be fitted inside a small plastic box. For once, we *don't* want to screen the circuit to prevent it interfering with other equipment; we *want* it to interact


+9V
R1
27k
TR1
2N2222A
b
c
e
2
3
6
4
C3
10µ
25V
+
9V
PP3
Battery
+
−
R2
4k7
C1
100n
R3
1k0
RV1
4k7
lin
C2
47n
R4
2k2
IFT1
collector
emitter
TR1
2N2222A
base
Viewed from
underside
4
2
6
3
IFT1
YHCS11100

Figure 1 Circuit diagram of the BFO



Figure 2 Matrix board layout shown from the component side. Adjust IFT1 carefully for the best results

with our receiver! This is why we use a plastic box. Maplin Electronic Components supply a suitable box, complete with the matrix board to fit inside (order code YU46).

Look at **Figure 2** carefully before you start to build the circuit, so that you can position the components correctly. Firstly, inspect the intermediate frequency (IF) transformer, IFT1, and remove its metal screening can very carefully. Again, this is to allow some signal to escape from our circuit and enter our radio. Having done this, solder the components, using the matrix board as a support. Underneath the board, the components are linked by single-conductor, insulated wire. Take particular care with the polarity of the electrolytic capacitor, C3, and the connections to the transistor, TR1 (see Figure 1).

The variable resistor, VR1, has a switch mounted behind the control itself, and the insulated leads to it from the battery should be about 10 cm long. Connect these before fitting VR1 into the case, so that the BFO can be calibrated (adjusted) correctly.

Calibration

After a final check that all the components have been fitted and soldered correctly, connect the battery, switch on, and hold the transistor between your fingers, to check that it is not getting hot. Place the circuit close to your receiver, and set RV1 to mid-position. Tune your receiver to find an amateur SSB transmission; the frequencies listed below will help you in knowing where to look. It may sound very strange, but don't worry. *Slowly* turn the core of IFT1 with a small, non-metallic screwdriver or with the correct 'trimming tool'. The core into which the blade fits is very fragile, so attempt this process with care. When the speech sounds as natural as you can get it, leave the core at this position, and use RV1 to make the speech sound natural.

Using the BFO

For best results, you may have to move the BFO nearer or further away from your radio. At the lower end of most bands (for instance just above 7.000 MHz or 14.000 MHz) you should be able to resolve Morse code (CW) signals. If you find that the BFO signal is a little weak, solder a 15 cm length of insulated wire to pin 2 of IFT1, and place it alongside your radio. This should improve signal intelligibility. When you are happy with the performance, switch off, drill a 10.5 mm hole in the box and fit RV1, followed by the matrix board assembly. Screw the base to the box, fit the knob, and the BFO is complete!

Where to listen

Band	**Frequencies (MHz)**
15 m	21.000–21.450
17 m	18.068–18.168
20 m	14.000–14.350
30 m	10.100–10.150
40 m	7.000–7.100
80 m	3.500–3.800

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1	27 kilohms (kΩ)
R2	4.7 kilohms (kΩ)
R3	1 kilohm (kΩ)
R4	2.2 kilohms (kΩ)
VR1	4.7 kilohms (kΩ), linear, with DPST switch

Capacitors

C1	100 nanofarads (nF) or 0.1 microfarad (μF), ceramic
C2	47 nanofarads (nF) or 0.047 microfarad (μF), ceramic
C3	10 microfarads (μF), 25 V radial, electrolytic

Additional items

TR1	2N2222A npn
IFT1	Toko type YHCS11100
Box	plastic, approximate size 100 × 70 × 45 mm
Board	matrix, to fit inside the box
Connector	for PP3 battery
Knob	for RV1

10 What is a capacitor?

Introduction

A capacitor is a device that stores energy in the form of electricity. Much less energy than a battery, and for a shorter time, however. The simplest form of capacitor takes the form of two flat metal sheets separated by air; connections are made to each plate, as **Figure 1** shows. If you imagine a pair of these plates, 30 cm square and separated from each other in air by 1 mm, the capacitance of this device would be almost exactly 80 picofarads (pF), i.e. 80 million-millionths of the unit of capacitance, the farad. Now this is quite a small value, you will agree, and it comes about because the farad is such a large unit. Nevertheless, as you will probably know, we may have capacitors of value 10 000 microfarads (μF) in our radio equipment, and they can be smaller than your little finger, so they are obviously not made the same way!



Figure 1

Large and small

We cannot go into the manufacture of capacitors here – after all, we are users of the devices, not the designers! First of all, beware of incorrect statements; the words 'capacitor' and 'capacitance' are *not* the same. For example, a large capacitor would be a description of one the size of a toilet roll. It need not have as large a capacitance as one the size of your little finger. A 'large capacitor' is one which is physically *big*, a 'large capacitance' refers to a capacitor which can store a larger amount of energy when a certain voltage is applied between its plates. The capacitors in a mains power supply are usually big **and** have large capacitances. High-power RF amplifiers may have large capacitors with small capacitances!

Electrolytics . . .

Electrolytic capacitors usually have capacitances of 1 μF or above. They differ from other capacitors in that they **must** be connected the right way round (i.e. they have positive and negative connections, just like a battery). They may explode if the connections are reversed!

. . . and the others

Other capacitors may be connected either way round, despite their names. We have *polystyrene*, *ceramic*, *silver-mica* and *tantalum*. Each has its own advantages and disadvantages, and the parts list for a project will always tell you which type is best.

Storing energy

If you were to connect a large capacitance across a 12 V power supply, nothing would appear to happen. Removing the capacitor from the supply and connecting it to a voltmeter would show that the capacitor has 12 V between its ends. This shows that, while the capacitor was connected to the supply, energy flowed from the supply into the capacitor. We say that the capacitor was *charged up* by the supply. If you are using an *analogue* voltmeter (i.e. one with a meter and pointer), you will notice that the indicated voltage slowly drops until, eventually, there is no voltage across the capacitor. This is because the capacitor has *discharged* its energy into the voltmeter. If you had used a smaller capacitance, the same would happen, except that the voltage would drop to zero more quickly – the capacitor stores a smaller amount of energy because its capacitance is smaller. Capacitors behave like other things in life – a small car can move more quickly than a large bus – a small piccolo emits a higher note than a flute – the voltages in a circuit containing a small capacitance will change more quickly than those in a circuit with large capacitance.

Varying the capacitance

Some capacitors are capable of having their capacitance changed manually; these are called *variable capacitors*. They work like the basic capacitor of Figure 1. Imagine moving the top plate of the pair a little to one side; the capacitance is determined, not just by the size of the two plates, but by their *area of overlap*. As this decreases, so does the capacitance. Such devices are limited in their capacitance, about 500 pF being the maximum value.

AC and DC

Because the plates of a capacitor do not touch each other, a direct current (DC) cannot pass between them. However, an alternating voltage on one plate can induce an identical alternating voltage on the opposite plate, and thus a capacitor appears to pass an alternating signal, even though currents as such, do not pass between the plates. This property of passing AC and not DC is very important, and a capacitor used in this way is called a *DC blocking capacitor* or, simply, a *blocking capacitor.* A blocking capacitor can be used at the same time, to couple a signal from one circuit to the next; here it would be known as a *coupling capacitor. Decoupling capacitors* are to be found where the capacitor is employed to remove an AC signal while retaining a DC component.

Finally . . .

Unlike resistors, the manufacture of capacitors renders them susceptible to excess voltage, so if you find a capacitor labelled 10 μF 16 V, it means that operating it above 16 V may fatally damage the device (and the circuit around it). This voltage is called the *working voltage* of the capacitor; on some electrolytics, you may find it expressed as *volts working* (i.e. 8 μF 450 V WKG).

Many smaller capacitors have their properties marked on them in a colour code, like resistors. **Figure 2** shows these codes, and their meaning, and the table below summarises the values of the colours.

Table 1

Colour	*Value*	*Voltage (tantalum capacitor)*	*Voltage (polyester capacitor)*
Black	0	10	–
Brown	1	–	100
Red	2	–	250
Orange	3	–	–
Yellow	4	6.3	400
Green	5	16	–
Blue	6	20	–
Violet	7	–	–
Grey	8	25	–
White	9	3	–


TC
1st
2nd
M
T
TANTALUM CAPACITORS
1st
2nd
M
V
+
Tip
1st
2nd
M
T
CERAMIC CAPACITORS
1st
2nd
M
T
V
POLYESTER CAPACITORS

Figure 2 Some capacitors have coloured bands or stripes, rather like resistors. The colour code, which is the same as the resistor code, is shown in Table 1. The band shown on the chart as '1st' is the first number of the capacitor's value in pico-Farads, '2nd' is the second number and 'M' is the Multiplier or number of noughts. For example, a capacitor reads from the top: Brown, Black, Yellow, Black, Red. Its value is One, then Nought, then Four more noughts = 100 000 pF (also referred to as 0.1 μF or 100 nF). Its tolerance (Black) is 20% and the working voltage (Red) is 250 V. The 'V' means the maximum working voltage. The band marked 'T' shows the tolerance, just like resistors, and the one marked 'TC' is only used on special capacitors designed to change their value with temperature

11 Waves – Part 2

Introduction

We left Part 1 with the concept that radio waves are divided up into bands which have different properties. Not *all* the properties are different, though. We need to discuss several wave properties, so we will start with what happens to waves as they propagate over long distances.

Getting weaker

Imagine a torch battery connected to a bulb by wires about 1 metre long. The bulb lights normally. If we now take the bulb 100 metres away from the battery and wire it up, we would expect the bulb to be somewhat dimmer, which is exactly what would happen. It happens because of the resistance of the wires – the wires do not form a perfect conductor. A similar situation occurs with radio waves.

All waves suffer from *attenuation* – they get weaker the further they travel. In cases of extreme attenuation, we need to apply some *amplification* before the attenuated wave can be used in a receiver.

Carrying information

When we speak over the telephone, the range of frequencies in our voices extends from very low frequencies up to about 15 or 20 kHz. In audio terms, this is quite a large *bandwidth* (meaning a wide band of frequencies). For communications purposes, however, most of this bandwidth is not needed, and in the telephone system (and in our transceivers), this is cut down so that it extends from about 200 Hz to 3 kHz, a reduction in bandwidth from 20 kHz to about 3 kHz. A bandwidth of 3 kHz has been found to be sufficient to convey speech intelligibly which, after all, is just what we need!

The radio waves coming from an amateur transmitter convey our speech signals over long distances. By themselves, the speech signals do not travel very far, so they have to be combined with a radio signal that *will* travel long distances. This extra signal is called the *carrier wave* (or just the *carrier*), because its job is to *carry* the speech signals along with it! The process of combining the speech (or Morse code) with the carrier is called *modulation*.

Wider and wider

Sending Morse code is achieved simply by switching (or *keying*) the carrier on and off. The bandwidth of the transmitted signal is only about 100 Hz. Speech, with its reduced bandwidth of 3 kHz, will produce a *single-sideband* (SSB) transmitted signal with a bandwidth of 3 kHz. If the same speech signal were used to produce an *amplitude-modulated* (AM) signal from the transmitter, it would have a bandwidth of about 6 kHz. Perhaps you can now understand why the bandwidths needed to produce hi-fi broadcasts need to be so large. TV signals need bandwidths running into tens of megahertz!

Waves need aerials

Radio waves are produced whenever changing currents flow through a wire, and when that wire is made in such a way as to maximise the *radiation* from the wire, it is called an *aerial* or *antenna*. The same piece of wire will receive radiation from other aerials; an aerial will transmit and receive. This is an important property of the aerial: when a current flows through it, electromagnetic waves are launched into the air; when electromagnetic waves in the air encounter the aerial, currents are produced in it.

From the simplest transmitting aerial, waves travel in all directions, like the waves on the pond that we considered in Part 1. They will travel a long way through air and space before they become too week to be received. They won't travel very far into the earth, however! The earth will *reflect* some of the wave and will *absorb* the rest. That portion of the wave which is reflected will again travel through air and space until it is totally attenuated.

Look at **Figure 1**; A represents a radio transmitter, with B1, B2 and B3 being receiving stations. The two arrows pointing 'downwards' from A represent two of the waves from A which just graze the earth's surface. Waves above



Figure 1 Stations between B2 and B3 receive the *ground wave*

these will travel on into space; waves below them will either be absorbed and reflected by the earth or received by aerials. B1 will not receive any signals from A, because it is below A's horizon. B2 and B3 can receive A's signals because they are *just* on A's horizon. Any stations between B2 and B3 will also receive A's signals, which are known as *ground-wave signals*. The wave at C represents one which is reflected by the ground and travels into space.

This description begs the question of how signals are received from stations well beyond the ground-wave range.

Mirrors in space

Suppose that there was something, out in space, that would reflect radio waves. Waves from A that travel out into space could be reflected off it and return to earth, enabling stations such as B1 to receive A's signals. The situation just described is illustrated in **Figure 2**.



Figure 2 Reception of A's signals at B1 using the *sky wave*

Just such a mirror in the sky really *does* exist. It is not man-made, of course! The earth is surrounded by the atmosphere, a mixture of many gases, such as nitrogen and oxygen. The energy contained in the radiation from the sun is more than sufficient to *ionise* these gases, thus making them into electrical conductors. When a gas is ionised, some of its electrons are physically stripped out of the atoms and are free to move about, just as the electrons of a metal do in a wire. Consequently, we can regard this part of the atmosphere (the part illuminated by the sun) as acting like a sheet of metal, which *reflects* radio signals! It is not a perfect reflector, but is sufficient to produce long-range (DX) radio propagation via the *sky wave* under the right conditions. (A more down-to-earth example of ionised gases conducting electricity can be found in the fluorescent tube and the neon sign – many gases glow when they are continuously ionised.)

This conducting region at the extremity of the atmosphere is called the *ionosphere*, and it exists in layers between 60 km and 700 km above the earth's surface. When the ionosphere is sufficiently ionised, it glows; this is the natural phenomenon known as the *aurora borealis*, or the *northern lights*.

The property of the ionosphere that enables radio waves to be reflected does not act in a uniform way; it is very selective about which waves it reflects, and which waves go straight through it and into outer space. In general, it reflects only those waves with frequencies below about 30 MHz – the HF bands!

In Part 3 we will look at families of waves.

12 An LED flasher

Introduction

The LM3909 is an integrated circuit (IC) which will flash a light-emitting diode (LED). Using only two extra components and a battery, the circuit is cheap and has a very low current drain from a 1.5 V cell. The circuit can be used as a novelty flasher, an indicator for a dummy alarm bell box, or it could be attached to a torch so that it could be found easily in the dark! The simple circuit is shown in **Figure 1**.



Figure 1 Circuit diagram of the LED Flasher. Pins 1, 3 and 7 of the IC are not used

Assembly

The circuit can be built on a small piece of Veroboard (the piece shown in **Figure 2** measures 15 holes by 10 strips). Using such a board, follow these instructions.

1. Depending on how far away you want the LED from the circuit board, solder a length of insulated wire to each lead of the LED. Use different colours of insulation – say, red and black, connecting the *red* lead to the *anode* (a) lead (the longer one) of the LED, and the black one to the *cathode* (k). Figure 2 shows these leads.
2. Cut the copper tracks as shown in Figure 2, using a 3 mm (1/8 inch) diameter drill, rotated between thumb and forefinger, or use the proper tool. Make *absolutely* sure that the tracks are completely broken!
3. Fit the IC holder in the correct position, using the cut tracks as guides, and make sure the small notch is facing towards the top of the board. Solder the pins to the copper tracks.
4. Mount the capacitor, positive end to the left, so that the positive lead is soldered to track F, which connects it to pin 2 of the IC; the negative lead is soldered to the right-hand side of track E, this being connected to pin 8 of the IC.
5. Solder on the battery leads, positive to the right, and the extended LED leads, positive downwards.



Figure 2 Board layout viewed from the component side. The tracks are cut under the board where shown

6. Check the circuit, and hold up the board to a bright light and look carefully for solder bridges between the tracks and pieces of copper swarf which may have escaped your inspection in 2 above! Remove whatever you find.
7. When all seems well, put the IC into the socket, ensuring that the notch or dot on the upper surface of the IC lines up with the notch on the holder. Line up each pin on the IC with the hole below it before pressing *gently* on the IC with the board supported on a firm surface.
8. Connect the battery; the LED should start to flash. The circuit is complete and working!

If you prefer, the whole circuit (battery included) can be mounted in a small plastic box, with the LED mounted on a clip and protruding through the panel. There are many other possibilities, and it is up to you to find an application for your own use.

Parts list

		Maplin code
LM3909	Integrated circuit	WQ39N
IC socket	8-pin DIL	BL17T
LED	5 mm diameter	WL27E
100 microfarad (μF)	Electrolytic capacitor (10 V)	FB48C
Battery holder	For AA-size cell	YR59P
Battery	1.5 V AA cell	

Small piece of Veroboard (15 holes by 10 strips)
Small plastic box (if required)
LED clip (if required)
Two lengths of coloured, insulated wire for LED (as required)

Availability

All parts can be obtained from Maplin Electronics Ltd.

13 Waves – Part 3

Introduction

When we talk about the spectrum being divided up into bands, this is just for our convenience; there are no natural divisions although, as we have seen, some of the properties of different bands really *are* different! Let's look at **Figure 1**, and see how the frequencies are divided up.

The divisions

- **Very low frequencies** (VLF) cover the range from a few kilohertz up to 30 kHz. Very long-range communication is possible, but at *very* small bandwidths. It is used for special purposes.
- **Long waves** (LW) are used for medium-distance commercial broadcasting and have frequencies from 30 kHz to 300 kHz.
- **Medium waves** (MW) are used for commercial broadcasting, and use frequencies from 300 kHz to about 1.5 MHz (1500 kHz). Typical range is about 200 km.
- **Short waves** (SW) encompass both the low-frequency (LF) and high-frequency (HF) amateur radio bands. There are nine narrow amateur bands in the SW spectrum between 1.8 MHz and 30 MHz. Some of these bands give round-the-world communication.
- **Very high frequencies** (VHF) span the range between 30 MHz and 300 MHz. Relatively short-range communication is possible. They were once used for broadcast TV before it moved to UHF. There are now three



Figure 1 Diagram of radio frequency spectrum

amateur bands here – 6 m, 4 m, and 2 m. Repeaters are used to extend the usable range of mobile stations. VHF waves are not usually reflected by the ionosphere, but when they are, ranges of several thousand kilometres are possible. Weather affects these waves on a regular basis, however. In addition to amateur users, the VHF part of the spectrum is also used by the police, the fire and ambulance services, weather satellites, and many others,

- **Ultra-high frequencies**, sometimes called *centimetre waves*, cover the range from 300 MHz to 1000 MHz (or 1 GHz). The only amateur band in this range is the 70 cm band, and we share it with radar, TV and cellular telephone users as well.
- **Microwaves** begin at 1 GHz and extend to about 400 GHz. They are *never* reflected by the ionosphere, are partially attenuated by buildings, and are reflected from aircraft and cars. Microwave absorption in the atmosphere is quite significant, and rain and fog can attenuate microwaves quite heavily.
- **Heat, light** . . . Above 400 GHz we run into the infra-red bands and on into the visible light and ultra-violet bands. We generally take 400 GHz as being the limit of what we class as radio waves.

Bandwidth again

Complex signals need more bandwidth than simple signals. Even if it were possible, we would not be able to transmit a single television channel in the whole of the MW broadcast band! When TV used part of the VHF band, only five channels were possible in the range from 45 MHz to 68 MHz. By moving TV to the UHF band, we now have 47 channels between 470 MHz and 855 MHz!

It's your choice!

The number of permutations you have amongst all the modes and all the bands is enormous! Only you can decide what you are interested in and what you want to learn about. That is the attraction of amateur radio!

14 Choosing a switch

Simple, but be careful!

A switch is the simplest electronic component, but care is needed in choosing the correct one for the job. Here is a list of the main characteristics of a switch, which will help you to select what you want.

1. **Rating**. This gives the maximum voltage and current that a switch can handle. For example, a 250 V 1.5 A switch will switch mains voltage at a current not exceeding 1.5 A. If the current is greater than 1.5 A, the switch may get hot and fail. If the voltage is too great, the switch may arc each time it is switched off, thus wearing away the contacts.
2. **Number of poles**. A single switch can control many circuits; the number of poles tells you *how many* different circuits it can handle. See **Figure 1**.
3. **Number of throws**. This tells you the number of positions each pole can have. This is best illustrated in Figure 1. The simplest ON/OFF switch is a Single-Pole, Single-Throw (SPST) switch. A Single-Pole,


SPST
Single-pole, single-throw
Single-pole, double-throw (also known as a changeover switch i e, SPCO)
Double-pole, double-throw (also known as a 2-pole, 2-way switch)
Push-button switch

Figure 1 Some circuit symbols for different types of switch

Double-Throw (SPDT) switch may also be used as an ON/OFF switch, but is used mainly to change between two parts of a circuit, and is commonly known as a Single-Pole Change-Over (SPCO) switch. Two or more SPCO switches can be operated at once; Figure 1 shows an example. The two switches are said to be *ganged*. See also 'Types of switch' below.

4. **Number of ways**. When a switch has more than one throw, we tend to use the word 'ways' instead. This means that if a switch has one pole and six throws, we would normally call it a '1-pole 6-way' switch. Such switches tend to be rotary switches, as are described below.

Types of switch

(a) **Push-button**. These are found on calculators, telephones, electronic games and most equipment with a digital display.

(b) **Rotary**. These are switches controlled by a knob, and are turned instead of moved up and down. **Figure 2** shows the rear of such a switch and its circuit symbol. The commoner types of rotary switch are: 1-pole, 12-way; 2-pole, 6-way; 3-pole, 4-way; 4-pole, 3-way; 6-pole, 2-way. All these switches have 12 click positions, as you may have guessed, but each one comes with an adjustable end-stop so that you can set the correct number of ways according to the contacts on the switch.

(c) **Slide**. This switch is common on the cheaper types of radio, mainly as an ON/OFF or band-changing switch. They are not very rugged, but are small and cheap to produce. Very small types are manufactured for use on PCBs.



Figure 2 The rotary switch can select several different circuits at once

(d) **Toggle**. Available as two-way types or three-way, with a centre-off position. Can be manufactured to handle very high currents.

(e) **Micro-switch**. These are devices which are usually operated indirectly, such as when the cover is removed from a high-voltage power supply, or when the door of a fridge is opened. The 'micro' part of the name doesn't refer to the size of the switch, but to the *small* movement that is required to activate it.



15 An aerial tuning unit for a receiver

Introduction

Any length of wire will act as an antenna (or aerial) but, to get the best results from a transceiver or receiver, an aerial tuning unit (ATU) is required. This matches the *impedance* of your aerial to the impedance at the aerial socket of your radio. Impedance is like resistance, and is measured in ohms, but it is used for alternating currents, and hence is common in audio and RF engineering. Most receivers have an impedance at the aerial socket of about 50 ohms (Ω); aerial impedance, on the other hand, can be anywhere between 20 Ω to over 1000 Ω, depending on its length and its height above ground.

Fortunately, you don't *need* to be able to calculate your aerial's impedance; all you need is a device that will perform the matching operation for aerials with a large range of impedances, and this is exactly what is described here! The subject of *matching* is a complex one, but all you need to know is that most signals will become clearer, and that there will be less noise and interference. Stations will become louder, so you will probably be able to reduce the setting of your RF gain control (always a good thing to do).

This design of ATU covers all amateur and broadcast bands from 10 m (28 MHz) to 80 m (3.5 MHz), and is very easy to build. The circuit is shown in **Figure 1**.



Figure 1 Circuit diagram of the Antenna Tuning Unit, showing the use of a 2-pole, 6-way rotary switch to select inductors (L) and capacitors (C)

Construction

1. Firstly, you will need a simple plastic case in which to house the ATU. The size should be approximately 85 × 145 × 50 mm.
2. Start by drilling two 10.5 mm holes in the front of the case; these are for the 6-way switch and the tuning capacitor.
3. Drill three 8 mm diameter holes in the left-hand side of the box, for the three sockets, coloured blue, yellow and green.
4. On the right-hand side of the box, drill two 8 mm diameter holes for the red and black sockets.
5. Now, fit the 6-way switch (SW1), the tuning capacitor (VC1), and all the sockets to the case. Check that the vanes of the capacitor rotate smoothly when the shaft is turned.
6. Wire up the inductors (coils). Figure 1 and the wiring diagram of **Figure 2**, will help with this. As you can see, each one side of each coil is connected to two switch connections, the other end going to VC1.
7. Solder in the fixed capacitors. One end of each goes directly to the ground socket (black), and the other end goes to the switch.
8. Solder a wire between the green and black sockets. The output from the ATU comes from the red socket, and this is connected to the two tags in the centre of the switch, as Figure. 2 shows clearly.
9. Finally, connect the blue and yellow sockets to the tuning capacitor, and the ATU construction is complete.



Figure 2 The internal view of the case shows the main tuning capacitor, VC1. This is a solid dielectric type, which has adjustable brass plates

In practice . . .

Figures 3 and **4** show two different ways of connecting your aerial to your ATU. In each case you will need to select each switch position in turn, and rotate the tuning capacitor through its full range while listening to a station. You should find that one switch position enables VC1 to produce a peak in the signal strength in the loudspeaker. At this point, your aerial and receiver are said to be *matched*. Stations in the same band will probably peak with VC1 at the same setting of SW1, but different bands will almost certainly require different positions of SW1.


ATU
Blue
Yellow
Green
Red
Black
Antenna input
RECEIVER
Ground

Figure 3 You may find that parallel tuning gives best results with your antenna


ATU
Blue
Yellow
Green
Red
Black
Antenna input
RECEIVER
Ground

Figure 4 In other cases, series tuning could be the most effective arrangement

Parts list

Capacitors (all rated at 16 V or more)

C1	220 picofarads (pF) polystyrene
C2	470 picofarads (pF) polystyrene
C3	1000 picofarads (pF) or 1 nanofarad (nF) polystyrene
C4	2200 picofarads (pF) or 2.2 nanofarads (nF) polystyrene

Inductors

L1	1.2 microhenries (μH)
L2	8.2 microhenries (μH)
L3	68 microhenries (μH)

Switch

SW1	2-pole 6-way rotary

Sockets
- 4 mm type, one each of red, black, yellow, blue, green

Additional items
- Plastic or metal case, e.g. Maplin type YU54
- Two large knobs for SW1 and VC1

16 A simple 2 m receiver preamplifier

Introduction

Designed specifically to complement the modified air-band portable (also described in this series), this can be used with some success on many receivers suffering from 'deafness' on VHF.

The circuit

An RF preamplifier is a device which improves the input signal to an existing receiver, enabling it to work more effectively. Because of the noise which is added to the signal by the preamplifier, *very* weak signals may not be usefully enhanced, but stronger signals will be improved considerably.



Figure 1 The integrated circuit is mounted upside down. Make sure you identify pin 1 which has a small dot next to it

This little circuit (shown in **Figure 1**) uses a GEC/Plessey integrated circuit type SL560C. With the addition of four capacitors, it is used between your aerial and the aerial input of the radio's PCB.

Putting it together

1. Use a small piece of prototype (matrix) board about 25 mm square. Use an 8-pin DIL socket for the integrated circuit (don't risk soldering the chip – it is seldom a risk worth taking). Figure 1 shows the connections to the socket, *looking from underneath*.
2. Make special note of the pin numbers, so that you know how to put the chip into the socket when you have finished. The positive and negative connections to the circuit are taken from the main PCB *after* the ON/OFF switch – so that the switch operates the preamplifier, too.
3. Unsolder the lead to the radio's telescopic aerial and connect it to the free end of C4, as shown. Then solder a short lead between the telescopic aerial and C2.
4. Sometimes it is possible to cajole your little preamplifier into the radio's plastic case, provided there is room and that you make sure that none of the soldered joints on your little board touch any of the metal inside the case when you replace the back and screw it on again.
5. If there is not enough room inside, then put the preamplifier into its own box, with battery and switch, and its own aerial. Keep the lead from the preamplifier to the aerial connection of the radio as short as possible – perhaps using screened cable.

Because your preamplifier is untuned, you will find not only that it helps with reception on 2 metres, but also that reception on the FM broadcast band is improved!

Parts list

Integrated circuit	
IC1	GEC/Plessey SL560C
Capacitors	
C1	1 nanofarad (nF) ceramic
C2, C4	10 picofarads (pF) ceramic
C3	10 nanofarads (nF) ceramic
Additional item	
Prototype broad approx. 25 × 25 mm	

17 Receiving aerials for amateur radio

Introduction

For any radio receiver to work well, it must have some form of antenna, or aerial. In almost all domestic transistor radios, the aerial is built into the set, either as a ferrite rod (which looks like a rod of dark grey metal) on which are wound coils of wire, or as a chromium-plated telescopic metal rod. Some radios have both forms of aerial, using the ferrite rod aerial for long waves (LW) and medium waves (MW) and the metal rod for very high-frequency (VHF) stations using frequency modulation.

There's broadcast reception . . .

No aerial is perfect, and these two types are *far* from perfect! As in most mass-produced equipment, *they serve their purpose*, which is not critical, and they allow the radio to be carried around easily, because they are not big and bulky. The broadcast stations are very powerful, usually quite close, and the circuits in the radio are quite sensitive, so the need for large aerials disappears.

. . . and there's amateur DX

Here we have an application which, in comparison with the broadcast situation, couldn't be much more different. The stations do not use much power, they may be half the world away, and the requirement for good aerials and very sensitive receivers is paramount. The aerials must be large and they must be as high as possible, away from buildings and trees, which cause reduction in signal strength, and away from man-made sources of interference.

You may not have thought about this but, in general, the larger an aerial becomes, the longer the cable (or 'feeder') must be in order to reach your shack and the receiver inside it. Cables reduce the received signal, so what your aerial gains by being large, the feeder (if you're not careful) will lose!

A simple aerial . . .

We now know that a 'good' aerial is essential. But what is a 'good' aerial? It depends on your purse, your property and your enthusiasm! One of the simplest (and, incidentally, one which is *not* subject to the cable loss problem discussed above) is the **Long Wire**, shown in **Figure 1**. This is, quite literally, a long piece of wire going from a chimney stack to a tree or pole



Figure 1 A tree at the bottom of the garden can provide a useful antenna support. Insulators can usually be obtained from Tandy stores or TV aerial suppliers

at the end of the garden. The longer it is, the better. Notice that the wire itself is *not* used to loop around the tree or chimney. Rope is used for both, and is secured to the end of the wire using an insulator of the ‘dog bone’ or ‘egg’ variety, to be found in profusion at rallies.

The wire is brought into the house through a window into the shack where the receiver is situated. The long wire aerial is best used with an aerial tuning unit (ATU), which is also described in this book. One of the advantages of the long wire is that it can be used on several frequency bands.

. . . and more complicated ones

Next up the ladder of complexity is the **dipole** (meaning two poles, or two elements). One form of dipole for lower frequencies would take the same basic form as the long wire, except that the feed to the receiver is taken, not from the end, but from the centre. The wire is essentially cut into two halves, and the two ends at the centre are connected to one end of a coaxial cable, which is then taken to the receiver. A smaller form of this is shown in **Figure 2**, which is conveniently mounted in a house loft. Aerials should always be mounted outside for best results, but will work when mounted inside, and the loft space is the logical situation.

The total length of the dipole should ideally be one-half of the wavelength of operation – hence the term ‘half-wave dipole’. For example, a dipole for use on 20 m should be about 10 m long. Dipoles are thus ‘single-band’ aerials. They can be modified for use on several bands, and then become known as ‘trapped dipoles’, having coils and capacitors at certain points along their lengths.


I .... insulator
I
TV coaxial cable
To shack
Wire fixed to roof timbers with tacks or drawing pins – use insulated (covered) wire

Figure 2 An indoor antenna should be mounted as high as possible

Indoor aerials

For flat- or apartment-dwellers, an indoor aerial is often the only solution, in which case the dipole of Figure 2 may be of great use. Other popular types include the **loop aerial**, of which several types are shown in **Figure 3**. The shape of the loop is of secondary importance, but it should be as large as possible.


Continuous wire loop – as large as possible
(a)
I
I.... insulator
TV coaxial cable
To shack
(b)
I
(c)
I
(d)
I

Figure 3 Try different shapes of loop antenna to see which works best

Ingenuity is called for when considering indoor aerials. A dipole can be mounted along a picture rail or pelmet. A vertical loop of aluminium foil can be stuck to an inside wall and covered with wallpaper! The designs are limited only by your imagination, and will give you hours of listening pleasure

Outdoor aerials

If you want to venture beyond the simple long-wire discussed earlier, then the erection of outdoor aerials can be a bit tricky; they can be more than a one-man job, and can involve seeking planning permission. Get some help advice from someone who has done it before – what about your local radio club? Plenty of designs for aerials appear in *RadCom*, so you should never be short of ideas!

18 The Colt 80 m receiver – Part 1

Introduction

This is the first of four parts detailing the design and construction of a simple radio capable of good reception of amateur radio signals on the 80 metre band. If you can solder and have some basic hand tools, at the end of Part 4 you will have a working receiver, in which you can take pride, and start some serious listening on 80 m! For testing, all you will need is another receiver and a multimeter.

Description

The radio will be built in three modules, or stages, as illustrated in **Figure 1**. Each of these is built on a printed-circuit board (PCB) or matrix board and can be tested in its own right. The case will need some holes drilled, and care will be needed to mount the PCBs in the case.

Get to it!

Surprisingly enough, when you are building a radio section by section (which is *always* the best way), it is easiest to start at the output and work


Simple tuner
Audio amplifier
(a)
Mixer board
Audio amplifier
VFO
(b)
Mixer board
IF board
Audio amplifier
VFO
(c)
© RSGB

Figure 1 Build your Colt and watch it grow. A simple crystal set (a) becomes a direct conversion receiver (b) and finally an 80 metre amateur band superhet (c)

towards the input, and you can test what you have done stage by stage. You will see what this means as you progress with your construction.

Every receiver needs some audio frequency (AF) amplification to make the sound signals big enough for you to hear. The circuit for the AF amplifier is shown in **Figure 2**. It uses the TDA7052 integrated circuit (IC) plus a handful of extra components. R1 in conjunction with C2 and C3 *decouple* the battery supply, preventing any audio signals getting through to it and affecting other parts of the radio, when they are connected. C1 acts to prevent high frequencies (above the 3 kHz bandwidth) going into the amplifier input. A volume control, VR1, is connected across the amplifier input, so that the amplifier can accept signal inputs over a wide range. **Figure 3c** shows the connections, which are made with screened cable. The


R1
22R
+9V
C2
100n
+ C3
220µ
16V
Input
1
VR1
2
TDA7052
5
+
Output
8
C1
100n
3
6
© RSGB X146

Figure 2 The Philips TDA7052 integrated circuit (IC) used in the audio amplifier needs very few extra components. It has a signal voltage gain of 100 times and the output is suitable for a loudspeaker or headphones

centre conductor of the left lead goes to the point marked 'input' in Figure 2, the braid being connected to the amplifier earth (0 V) tag. The right lead to VR1 goes to whatever signal source you have for testing – see later. VR1 is *not* mounted on the PCB.

The circuit is constructed on a small PCB or matrix board. Make sure that the electrolytic capacitor, C3, is soldered into the board the correct way – its positive and negative connections are shown in **Figure 3b** for reference. If you are **at all** concerned about soldering the IC into the board, enlist some help, *or*, obtain an 8-pin DIL socket, which you can solder in and then carefully insert the chip into the socket, making sure that is the correct way round. The markings on the chip are shown in **Figure 3a**.

The output leads from the amplifier go to a plastic 6.3 mm (¼ inch) mono jack socket, so that *neither* output lead is connected to the metal case. The amplifier will drive a pair of headphones or a small 8 Ω loudspeaker.

The battery leads must be the right way round also; the battery itself can be a PP3 or PP9, or you can use a small DC power supply.

Testing

First, check that all the components are in the right places, that your soldering is good, and that you have headphones or a loudspeaker connected. Set VR1 about halfway along its travel. Connect the battery.



Figure 3 It is important to check the component connections carefully. The diagram shows (a) top view of the IC, (b) electrolytic capacitor and (c) volume control (VR1) connected across the input of the amplifier

A slight hissing noise should be heard; touching the input lead to the amplifier (the centre of the three connections on VR1) should produce a loud buzz. Touching the shaft at the same time will make the buzz quieter. This is the quickest way of confirming that your amplifier *seems* to be working. The only real test is to give it something meaningful to amplify! See the design of our *Crystal Radio Receiver* for full details.

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1	22 ohms (Ω)
VR1	10 kilohms (kΩ) log

Capacitors

C1, C2	0.1 microfarad (μF)
C3	220 microfarads (μF) electrolytic 16 V

Integrated circuit

IC1	TDA7052 audio amplifier

Additional item

PCB	(see below)

Component suppliers:
Maplin

The next part . . .

The metal case will be marked out ready to receive the completed modules.

19 A crystal radio receiver

Introduction

Here's a quick project to fill in a winter's evening! It was originally designed as a piece of test gear for the *Colt* receiver, but can be successfully used by anyone as a first radio project. Another use for it would be as test gear for any audio amplifier project requiring an audio input for test purposes; this is ideal, as it does not require any power supply!

Details

The initial rough-and-ready test for the audio amplifier of the *Colt* receiver will have whetted your appetite; you will want to prove more conclusively that your amplifier works, and in a way that others in the household will appreciate. Buzzing noises are not convincing in this respect! You are going to put together a simple crystal set – the simplest type of radio that there is – and use it as a signal injector for your amplifier. In this way, you build a real medium-wave (MW) receiver which drives a loudspeaker, as an intermediate product of the construction of an 80 metre amateur band receiver!

The circuit diagram is shown in **Figure 1**. It has a 60-turn coil mounted on a small piece of paper or card wrapped round a ferrite rod. The coil has a connection made to its centre-tap (the middle turn of the coil). The tuning capacitor, VC1, is the most expensive part of the circuit but don't worry, it will be used in the final design of the receiver also! Connect the diode, D1, from the centre-tap to the input to the potentiometer of the amplifier circuit of the *Colt*. Be careful to connect the aerial to the *vanes* of VC1, and not to its *frame*, or you will experience some strange effects when you are tuning. If your amplifier is working correctly, you should be able to receive local stations on medium-waves quite well.

If you think the crystal set will be of use to you in the future as a signal injector, all you will need will be another variable capacitor! If you do not intend to use the amplifier, a small crystal earpiece will allow you to listen. Walkman-type headphones will *not* work!


VC1
VC1 vanes
30 turns
D1
OA91
Inner
L1
30 turns
To audio amplifier
VC1 frame
Screen

Figure 1 Both sets of moving vanes are joined as shown. L1 is wound on a ferrite rod with 32 SWG wire and centre-tapped. A single winding (no tap) can be used, joining D1 to the top of the winding

Parts list

Variable capacitor	
VC1	125 + 125 picofarads (pF) twin-gang
Ferrite rod	
About 100 mm to 140 mm long	
Diode	
D1	OA91 germanium diode
Additional items	
Wire	2 m of enamelled copper wire, between 23 SWG and 32 SWG
Earpiece	High-impedance crystal type (only needed if you are not using the amplifier)

20 The varactor (or varicap) diode

Introduction

Many of the circuits for receivers and transmitters presented in this series rely upon the variable capacitor as a means of tuning. Another method of varying capacitance (without any moving parts) is provided by the *varactor diode*, sometimes called a varicap diode. This is a component which changes its capacitance as the voltage across it is varied.

The details

Figure 1 shows how a varactor diode might be connected to demonstrate its operation. Its symbol is that of an ordinary diode, with a capacitor symbol next to it. A variable voltage is applied across it in such a way that the diode is *reverse-biased*. This means that virtually no current passes through it – the positive voltage is applied to the cathode. Varactors are cheaper than variable capacitors, and they are tiny in comparison, very suitable for today's miniature circuits. If A and B were connected across the tuning coil in a simple receiver (with a series capacitor to block the DC from the battery reaching the coil), the tuning operation would be accomplished by turning the knob on the 10 kilohm potentiometer.

Varactors are available with different values, from less than 20 picofarad (pF) for VHF applications to 500 pF for medium-wave radios. They are



Figure 1 The capacitance of the varicap diode (between A and B) increases as the voltage is reduced, using the variable resistor

tuned usually by voltages between 2 V and 9 V. For a real application of varactors, you should consult the circuit diagram of the *Yearling* 20 metre receiver, elsewhere in this book.

In some circuit designs, several circuits are all tuned to the same frequency in order to improve the overall *selectivity* (the ability of the circuit to reject signals very close in frequency to the wanted signal). Special dual- and triple-varactors are available for circuits like this. Having been made at the same time from the same materials makes their individual characteristics virtually identical. Like all other diodes, they must be correctly wired into the circuit – their *polarity* is important.

Changes in temperature will cause the capacitance to change which, if it were part of an oscillator circuit, would cause the oscillator to drift – you would have to keep retuning the radio! This can be corrected by using a special integrated circuit called a *phase-locked loop* (PLL). Modern TV sets and satellite receivers use varactors and PLLs in this way.

Some useful varactor types

Type No.	*Tuning range*		*Description*
	pF/V	*pF/V*	
BB204B	42/2.0	15/12	Dual VHF
BB212	560/0.5	22/8	AM tuning
KV1235	450/2.0	30/8.5	Triple AM
KV1236	450/2.0	30/8.5	Dual AM
MV1404	120/2.0	9/10.0	HF tuning

21 A portable radio for medium waves

Introduction

The ZN415E integrated circuit (IC) can be used to make a very efficient AM portable MW broadcast radio with a built-in loudspeaker. Here's how!

The circuit

Figure 1 shows the circuit diagram of the portable radio. It's not as complicated as it may appear, especially after you have got started. L1 is a coil of wire mounted on a ferrite rod, acting as an aerial; VC1 is a variable capacitor which works, with L1, to tune in different stations. IC1 contains circuits of its own which boost the selected signal and it includes a *detector* which extracts the audio signal from the incoming RF signal. Earphones could be connected to the output of IC1 (between pins 4 and 5), but the output would not be powerful enough to drive a loudspeaker.

More sound

This is where IC2, an LM386 comes in. This is a small audio *power* amplifier which produces audio signals with enough power to drive a small


TR1
BC548
e
c
b
R2
5k6
6V0
nc...no connection
S1
On / Off
1V9
1V3
LED1
anode
cathode
nc
8
C5
100µ
nc
1
6
IC1
ZN415E
IC2
LM386
C8
100µ
C9
100µ
B1
6V
L1
VC1
Tune
5
2
5
7
4
3
4
8
3
7
R1
68R
C7
100n
LS1
8R0
C1
10n
2
C3
100n
C4
10n
C6
10µ
R3
10R
C2
100n
Dot
Notch
Flat face (marked)
There will either be a notch or a dot in the plastic body – this tells you which way round to mount the IC
1
2
3
4
8
7
6
5
Marking
IC1 and IC2
Collector
Base
Emitter
TR1
Bend leads here
Anode (longer lead)
Cathode
LED1
Marking to show negative lead
C5, 6, 8 and 9
© RSGB

Figure 1 The circuit diagram of our easy-to-build portable radio. Take care to mount the ICs and LED the correct way round

loudspeaker, LS1. The radio uses a 6 volt battery, which is made by connecting four 1.5 volt AA cells in series (4 × 1.5 V = 6 V) using a battery holder designed for this purpose. Although a 6 V supply is ideal for IC2, it is far too great for IC1, which needs only about 1.3 V. This lower voltage is provided from the 6 V supply by TR1 (an npn transistor), R2 and LED1 (a light-emitting diode). When current passes through an LED (see the description of the LED in this series) a reasonably constant voltage of 1.9 V appears between the anode and the cathode. Because of the voltage (0.6 V) that *always* exists between the base and emitter of a working transistor, the voltage on the emitter is about 1.9 V – 0.6 V = 1.3 V, and this is used as the power supply for IC1.

To keep the radio as simple as possible, no volume control has been fitted. Instead, you can use the directional properties of the ferrite rod aerial (see the information on ferrites in this book) to reduce the volume by rotating the set about a vertical axis using the handle provided.

Putting it all together

1. Start by covering the ferrite rod with Sellotape, or alternatively wrap a piece of paper tightly around it, and secure it with Sellotape. Then, with at least 2 metres of 24 SWG enamelled copper wire, wind 75 turns tightly around the rod. To be safe, leave about 50 mm of wire at the ends of the coil, then wrap the whole coil with Sellotape to hold the turns in place, leaving only the ends free. Then, using a small piece of sandpaper, remove the enamel from the last centimetre of each end of the coil.
2. Most of the components are mounted on a piece of Veroboard (the type with parallel copper strips on one side). The piece used on the prototype measured 32 holes by 10 strips, as **Figure 2** shows. Before you start fitting components, cut the copper strips as shown. It is easier to do it now than when the board is littered with components! The strips may be cut with a 3 mm (⅛ inch) twist drill rotated between thumb and forefinger. Resist the temptation to use a hand drill – the idea is just to cut the copper, **not** to drill right through the board!
3. Solder the IC sockets and the other components on the board as shown in Figure 2. Make sure that the IC sockets are fitted with their notches towards the *top* of the board, as viewed in Figure 2. Do not insert the chips yet. Always keep the wires left over from cropping resistors and capacitors, they will come in handy at times like this: make the wire links that are clearly shown in Figure 2. Connect the electrolytic capacitors (C5, C6, C8 and C9), the transistor and the LED the correct way round; then check it again when you have done it!
4. Finally, solder lengths of stranded insulated wire to act as ‘flying leads’ for future connection to L1, VC1, LS1, S1 and the battery connector.
5. Apart from the battery holder, everything is mounted on the case *lid*. This makes assembly and testing much easier, and eases fault-finding if


© R508
Ferrite rod
S
L1 — 75 turns
S
S indicates Sellotape strip
L1, VC1 and S1 are not to scale
VC1
nc
G
A
S1
Red
+ to Battery holder
Red
A
B
C
D
E
F
G
H
I
J
c
b
e
TR1
R2
IC1
IC2
C1
C2
C3
C4
C5
C6
C7
C8
C9
LED1
anode
cathode
R1
R3
To LS1
Black
− to Battery holder
1 2 3 4 5 6 7 8 9 10 15 20 25 30 32
1 ← → 32 Direction of the ten copper track strips (each track must have thirty-two holes)
Track H is not used
⊗ Copper strips are cut here
IC1 and IC2 are mounted in IC sockets

Figure 2 Veroboard layout for the Portable Radio. Make sure that all the wire links are included

the need arises! At the speaker position, make one large hole or a series of small holes to let the sound out. The ferrite rod may be stuck to the lid, as may the loudspeaker. Drill holes of the correct size to fit the particular types of variable capacitor (VC1) and switch (S1) that you are using. The Veroboard may be held in position by Blu-Tack or double-sided sticky tape.

6. Before inserting IC1 and IC2, connect the battery and switch S1 on. The LED should glow dimly (you may have to shield it with your hand in order to see it). If you have a test meter, check that there is about 1.3 V between pins 6 and 4 of IC1. If the reading is around 6 V or there is no glow, you may have connected the LED the wrong way round! When everything seems normal, switch off and disconnect the battery. Insert IC1 and IC2, making sure that the pins are straight and lie immediately above their corresponding holes in the sockets, and that the notches line up with the notches in the holders. Then push *gently* downwards on each IC in turn until the chip is firmly seated in its socket.
7. Switch on! By rotating the tuning capacitor, VC1, you should now be able to tune in many stations, rotating the radio to give you some volume control.

Final touches . . .

The handle was made with part of an old leather belt, secured to the case with 'number plate' nuts and bolts from Halfords. The loudspeaker grille is the lid from a *pot-pourri* container, and some extra holes were drilled in the back to improve the sound. See what you can find to finish off your radio!

Parts list

Maplin order codes are given for most of the parts, but you should get used to using the 'beg, borrow or steal' technique, or to use your ever-expanding junk box.

		Maplin code
Resistors: all 0.25 watt, 5% tolerance		
R1	68 ohms (Ω)	M68R
R2	5.6 kilohms (kΩ)	M5K6
R3	10 ohms (Ω)	M10R
Capacitors		
C1, C4	10 nanofarads (nF) or 0.01 microfarad (μF) ceramic	BX00A
C2, C3, C7	100 nanofarads (nF) or 0.1 microfarad (μF) ceramic	YR75S
C5, C8, C9	100 microfarads (μF) electrolytic, at least 10 V	FF10L
C6	10 microfarads (μF) electrolytic, at least 25 V	FF04E
Semiconductors		
IC1	ZN415E radio chip	
IC2	LM386 audio power amplifier	UJ37S
LED1	3 mm green LED	WL33L
TR1	BC548 npn transistor	QB73Q
Additional items		
LS1	Miniature 8 ohm loudspeaker	WB08J
S1	Miniature SPST toggle switch	FH97F
Ferrite rod	Length approx. 100 mm	YG20W
	24 SWG enamelled copper wire	BL28F

Additional items (*continued*)

VC1	Tuning capacitor 140 to 300 picofarads (pF)	FT78K
	Tuning knob	FK41U
	8-pin DIL IC sockets (two required)	BL17T
	4 × AA-size battery holder (long)	HF94C
	PP3-type clip for battery holder	HF28F
	Plastic box approx. 158 × 95 × 54 mm	LH51F
	0.1 inch Veroboard, min. size 32 holes × 10 strips	JP46A

Plus

Stranded insulated conductor for flying leads
Multicore solder
Materials for handle and speaker grille
Double-sided sticky tape or Blu-Tack
Sellotape
Glue
Four AA-size 1.5 V batteries

22 The Colt 80 m receiver – Part 2

Introduction

In Part 1 we constructed the audio amplifier module for the system and tested it in a very simple way. If you did what was suggested and built the simple Crystal Set to use as a signal source, you will know just how well the amplifier works.

The case

Metal cases for the project are available from Maplin, telephone 01702 554 161 (code XB67). From the photograph on p. 72 you can see the way the components are mounted. The audio amplifier is seen at the top right of the base, to the right of the tuning capacitor VC1. The next in this series will deal with the variable-frequency oscillator (VFO) and VC1. The current part deals with preparing the case to receive the components.


Rear
I F board
Mixer board
VFO board
VC1 mounting screws
Audio amplifier board
© RSGB

Figure 1 Fixing holes for each module are best measured from each printed circuit board or matrix board


Front
Volume control
RF gain control
Headphone socket
Mounting for Slow-motion drive
On/Off switch
© RSGB

Figure 2 Position the slow motion drive to allow viewing of the tuning dial

Figures 1 and **2** show the markings for preparing the front panel and base. All the circuit boards and the tuning capacitor are mounted on the base using 10 mm stand-off pillars with 6BA bolts. The board locations are shown in Figure 1. The front panel control positions are shown in Figure 2, together with the small rectangular hole for viewing the tuning dial.

The best way to mark out the holes for the boards is to lie the boards flat on the base (before you've started soldering the components in) and marking the base through the holes in the boards. This minimises the scope for errors!

A *reduction drive* is used between the tuning knob and the capacitor shaft. This is simply a gear mechanism that slows down the capacitor shaft by a factor of six compared with the tuning knob, and makes tuning very much easier. The recommended variable capacitor also has a pulley wheel mounted on the shaft. Glued to this wheel will be a scale marked with frequency and is visible through the rectangular hole in the front panel.

The next part . . .

The variable-frequency oscillator and mixer will be added to the project.



23 A simple transistor tester

Introduction

Although transistors aren't used as much as they were before integrated circuits came along, a transistor tester is still a useful piece of test equipment to have around the shack. This design is about the simplest possible and will produce an indication of whether a transistor is giving any current gain; this does not necessarily mean that the transistor is perfect but that it is working to a certain extent. This tester will **not** test field-effect transistors (FETs). If you buy a bag of transistors at a rally, this tester is useful for giving a yes/no indication of which ones go straight in the bin and which are kept for further use.

How it works

Figure 1 shows the simple wiring circuit. In order to explain the working of the circuit, a circuit diagram is shown in **Figure 2**, with the npn transistor, TR1, under test shown as part of the circuit. The pnp/npn selector switch, SW1, is omitted for clarity.



Figure 1 Circuit diagram of the transister tester



Figure 2 Testing an npn transistor

Any current that flows through the transistor, TR1, must flow from the battery, through the meter, M1, and through the protective resistor, R2. R2 prevents excessive current flowing through the meter and damaging it. Even if there is a short-circuit between emitter and collector, the maximum current that will flow is given by the simple equation

$$I = \frac{V}{R},$$

where I is the current flowing in amps,
V is the battery voltage, and
R is the total circuit resistance in ohms.

Putting in the correct values, gives

$$I = \frac{9}{47\ 000} = 0.000191 \text{ A, or } 191 \text{ microamps } (\mu\text{A}).$$

The resistance of the meter, M1, will cut this down a little more, but it is within the indicating range (200 μA) of the meter.

As shown, with the push-button switch, PB1, *open*, a good transistor will not draw any current from the battery, and M1 will thus remain at zero. When PB1 is *pressed*, a *very small* current is injected into the base of the transistor. If the transistor is working, it will produce a much larger current between the collector and emitter, and this current will also flow through M1 and R2, giving a significant reading on M1, showing that all appears to be well. If an appreciable current flows when PB1 is *open*, then your transistor is suspect.

Don't be put off by the apparently complicated switch, SW1. It is there to allow the other type of transistor, the pnp type, to be tested. All it does is reverse the battery connections, so that the emitter goes to the *negative* battery terminal for testing an npn transistor, and to the positive terminal for a pnp type!

Most transistors in common use are of the npn type, which is why Figure 2 shows the testing of an npn type. The connections to the different transistor *encapsulations* (shapes) are given in any good component catalogue. Avoid the trial-and-error method to discover the connections to a transistor. This is unscientific, and can be very frustrating, particularly if the transistor is faulty in the first place!



Figure 3 This shows how to wire up the tester

Construction

The unit can be built into a small plastic box, the components being soldered directly to the fixed terminals of the meter and the two switches; no circuit board is necessary! Use different colours of wire for the three test leads, and make sure you know which is which! Check the connections against the wiring diagram of **Figure 3**. When you are confident that all is correct, connect the battery and make sure there is no reading on the meter when nothing is connected to the crocodile clips!

Find any transistor for which you know the connections and the type (npn or pnp). Set the npn/pnp switch accordingly. Connect the three clips, making sure that they do not touch each other. A small reading on the meter at this stage means the transistor is suspect; a large reading means it is not working and should be thrown away! Press PB1 and watch the meter; a reading greater than half of full-scale indicates a good transistor. If it is less than half, you may have a transistor with ‘low gain’; it may be usable for non-critical applications, but if you are in any doubt – throw it away!

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1	100 kilohms (kΩ)
R2	47 kilohms (kΩ)

Additional items

PB1	Push-button switch
SW1	DPDT (double-pole double-throw) switch
M1	Micro-ammeter – *not* less than 200 μA full-scale deflection
	Crocodile clips (3 needed)
	PP3 battery and connector
	Plastic box about 10 × 7 × 3 cm

Common types of transistor

BC108, BC109, 2N2369A

These are small-signal npn types, used in audio amplifiers. They are in metal cases (called TO18) and have a tab next to the emitter lead. Common types have a B or C suffix (e.g. BC109C). The C suffix indicates a higher current gain than those with a B suffix. The 2N2369A is specially designed for radio use at high frequencies.

2N3703, BC212L, BCY71
These are pnp transistors, and so must be used with the collector and base *negative* with respect to the emitter. These three types are used in small amplifiers and audio oscillators. The first two have plastic encapsulations (TO92), while the BCY71 has a metal case (TO18).

BFY50, BFY51, BFY52
For slightly higher powers, these are ideal. They have been used in novice transmitters up to 600 milliwatts (mW). The TO5 case is a scaled-up version of the TO18 case. They are all npn types.

2N3055, 2N3773, TIP35C
These are high-power transistors in bigger encapsulations. The thick metal TO3 case of the 2N3055 and 2N3773 is designed to bolt to a heat sink, a large piece of metal which conducts the heat into the air more rapidly than the transistor itself can. The TIP35C is made of plastic but has a thick metal tab by which it, too, can be bolted to a heat sink.

24 An introduction to transmitters

Introduction

We usually think of a transmitter as being a 'black box'. However, that is the form a transmitter takes for our use on the amateur bands. Many electrical circuits are transmitters, even though transmitting may not be their primary function!

Anything that emits electromagnetic energy at *any* frequency is a transmitter, from radio at the low-frequency end of the spectrum, to gamma rays at the high-frequency end. We all know that a magnet will attract certain metals and that a comb rubbed on your coat sleeve will pick up small pieces of paper. The former is an example of the effect of a magnetic field, the latter of an electric field. Electromagnetic fields are combinations of both types of field, and are produced whenever an electromagnetic wave is transmitted.

What frequency?

Many everyday objects have a natural frequency of oscillation. This is called their *resonant frequency*. A wine glass will ring when struck gently; an empty wine bottle will sound if you blow across the top; a guitar string will vibrate when plucked. These are all examples of resonance, and the resonant frequencies will **not** change unless the objects themselves are changed physically in some way. These are resonances in *sound*; we are primarily interested in electrical resonances.

The basic electrical resonant circuit is the combination of an inductor (coil) and a capacitor, as shown in **Figure 1**.



©RSGB X162

Figure 1 The basic electrical resonator. The energy in the circuit alternates between the inductor and the capacitor

A pulse of energy applied to this *tuned circuit* will make it *ring* (oscillate) at its resonant frequency. The energy in the circuit transfers between the inductor and the capacitor every cycle of the oscillation. Just like the wine glass, its oscillation dies away because it is losing some energy to its surroundings – it is transmitting! The frequency of the resonance depends on the values of *L* and *C*.

Keeping it going

If we want to keep the circuit oscillating, rather than having it die away, we must supply the circuit with just enough energy to replace the energy lost both by radiation and by losses in the circuit itself. Because of this, you will find in all oscillator circuits, a transistor, valve or FET working with the tuned circuit to provide this extra energy.

As it stands, of course, even with its transistor, our oscillator will not radiate very far. Connecting an aerial to it, and a Morse key to interrupt the power supply, it would become a very low-power CW transmitter. Add a couple more transistors to form a radio-frequency (RF) amplifier, and you have the basis of a simple low-power (QRP) transmitter.

Resonant circuits can also be made using quartz crystals; these work at the crystal frequency only, and this is marked on the crystal case.

A tiny spark transmitter

This is a simple piece of test gear that will increase your knowledge and understanding of resonance. You can use it to estimate the resonant frequency of most of the inductor/capacitor (LC) tuned circuits that you build. The circuit is shown in **Figure 2**. It operates around a relay. Any relay that operates from a 6 V to 9 V source and has contacts which are normally closed (i.e. closed when the battery is not connected). Fit the relay, a toggle switch and the battery in a metal box, and connected up as shown in the diagram. Some foam rubber inside the box may help to reduce the escaping noise of the relay. A small hole in the side of the box enables the 2-turn loop to emerge. This should be about 40 mm diameter, made with insulated wire. Switch on; there should be a loud buzzing noise from the relay. If not, you have probably chosen the wrong contacts on the relay!

When it is working, bring the loop close to the aerial of a radio – it should produce a loud noise from the speaker!

How it works

When you switch on, current flows through the relay contacts and through the relay coil. The relay operates and opens the contacts, causing the relay to 'drop out'. When it does, the circuit is completed again and the contacts are opened, and the cycle repeats. Each time the relay contacts open, there is a small spark between them, causing very rapid current surges through the wire loop. This makes the loop transmit RF energy, very briefly. In the early days of radio, this type of circuit was known as a *spark transmitter.*



Figure 2 The current path is interrupted when relay is energised as shown above

Make a tuned circuit

Use a discarded toilet-roll centre, and wind about 10 turns of enamelled copper wire round it, keeping each turn close to the next. Scrape off the enamel for about 1 cm at each end, and solder a 100 picofarad (pF) capacitor (or a variable capacitor of about the same value) between the ends. The resonant frequency should be about 10 MHz. If you have used fewer turns or a smaller capacitor, the frequency will be higher.

Measuring the resonant frequency

Set up the buzzer as shown in **Figure 3**, with the loop around one end of your coil. Then make a similar loop, solder it to the end of a piece of coaxial cable going to the aerial socket of a calibrated receiver. Set the buzzer going, tune the receiver around 10 MHz, and search for the maximum noise level from the speaker. When you have found it, move the two loops as far away as possible from the main coil. This is called reducing the *coupling* between the coils, and it may result in a slightly different, but more accurate, resonant frequency.



Figure 3 Experiment with the spacing between the loop and the tuned circuit

Parts list

Any small relay which operates between 6 V and 9 V
Metal box – do not use a plastic box!
9 volt battery and connector
On/off (SPST) toggle switch
Plastic foam, as required

25 The Colt 80 m receiver – Part 3

Introduction

In Part 2 we marked out the case ready for installation of the modules when they are completed. In this part, the building of the variable-frequency oscillator (VFO) and mixer will be described. This will produce a type of receiver known as *direct-conversion*, because it converts the radio-frequency (RF) signal directly into an audio-frequency (AF) signal which we can hear in a loudspeaker after amplification. A block diagram of the system is shown in **Figure 1**. The modifications needed to make a full superheterodyne receiver will be left until later.

The direct-conversion receiver covers the 80 metre amateur band and will receive both Morse (CW) and speech (SSB) signals. The audio amplifier was covered in Part 1, so your *Colt* is rapidly taking shape! By the time your construction has reached the end of this part, you will have a receiver ready to use, even if the project is not yet complete!

The direct conversion process

Like most things in radio, the principles of direct conversion are not difficult. From the aerial, the signal we want to hear is selected by the *tuned filter*, which rejects the signals we don't want. The signal then enters the


Antenna
Radio signals
Tuned filter
Mixer
Audio signal
$F_{AUDIO} = F_{VFO} - F_{RADIO}$
Audio amplifier
Audio (sound) signals
Loudspeaker
VFO signal
VFO
© RSGB

Figure 1 Stages of direct-conversion receiver

mixer, along with the signal from the *VFO*. The VFO produces a sine wave whose frequency can be varied across the whole of the 80 metre amateur band (3.5–3.8 MHz), by turning the knob on the tuning capacitor, VC1. The mixer produces, at its output, *two* signals; one signal is at the frequency of the **sum** of the signal and VFO frequencies, the other is at the **difference** of the two frequencies. It is the latter that we want. Let's look at the numbers involved. If the signal is at 3650 kHz and the VFO is at 3651 kHz, then the sum frequency is 7301 kHz, and the difference frequency is 1 kHz. If we feed the output of the mixer into our audio amplifier, the 7301 kHz signal is automatically removed (it is far too high to be considered an audio signal!) and the resulting 1 kHz signal is amplified and fed to the speaker, producing a note which we can hear!

Building the VFO

Figure 2 shows the circuit of the VFO. It is a tried and tested circuit, and should work first time. It uses a *field-effect transistor* (FET) for TR1, the oscillator itself. RFC is a *radio-frequency choke*, a coil of wire which will pass a direct current (DC) but which will prevent radio-frequency (RF) signals getting through.

All VFOs have a tuned circuit which, in this case, is formed by the coil L1 and the capacitors C1 and VC1. The frequency will also be affected to some extent by C2, C3, C4 and C5. Transistor TR2 is an *emitter follower*, a stage which gives no voltage gain but provides a good *buffer* stage, isolating the VFO from the effects of the stages that follow it. When building a VFO, the



Figure 2 The variable-frequency oscillator uses a field-effect transistor (FET)

parts must be securely mounted. If components move, so does the frequency! At worst, the oscillation will become unstable and the VFO will be useless. Keep the component leads as short as possible – this improves their mechanical stability as well as their electrical stability!

Mount the parts on the printed-circuit board (PCB) or matrix board and, when completed, the VFO should look like the one shown on the left in the photograph on p. 72. Make sure that TR1, TR2 and D1 are the right way round.

On completion, check the component positions then mount it in the case as shown in the photograph, to the left of the tuning capacitor when viewed from the rear. The VFO coil, L1, will need some adjustment, but that will have to wait until the mixer is built. Connections to the other boards are made with screened cable.

The mixer board

So far, we have an audio-frequency (AF) amplifier and a VFO; the addition of a mixer board gives us a complete direct-conversion receiver for 80 m. The mixer circuit diagram is shown in **Figure 3**. Let's follow the signal path.

- From the aerial, the RF signal goes to the gain control potentiometer, RV1. This reduces very strong signals, to prevent them overloading the mixer.
- To select the required band of signals, a *bandpass* filter is made up of RF transformers T1 and T2; these are tuned by C1 and C3, and are coupled together by C2.



Figure 3 The mixer board has a bandpass filter and stabilised supply

- After the filter, the signal is coupled into the integrated circuit (IC) mixer type NE602, by the capacitor C4. Capacitors C5 and C8 *decouple* the supply line, to prevent unwanted signals on the supply from disturbing the VFO operation. The use of the term *decouple* is exactly the opposite of *couple*; when two circuits are *coupled* together, the signal passes from one to the other; when two circuits are *decoupled*, signals **cannot** pass from one to the other.
- The NE602 works with a 6 V supply; it is produced here from the 9 V supply by the *Zener diode* ZD1 and the resistor R1. ZD1 operates at 6.2 V, and gives a steady output for the mixer. The audio output from the mixer appears at pin 4 or IC1. This is taken to the audio amplifier board via C9 and the volume control (see Part 1).

Care must still be taken to insert some components the right way round. These are the electrolytic capacitors, C8 and C9, the Zener diode, ZD1, and the integrated circuit, IC1. Check all component positions and make sure all your soldered joints are bright and shiny.

Putting it together

The interboard wiring, shown in **Figure 4**, uses screened cable; ideally, this should be thin coaxial cable, but screened microphone cable is suitable. The diagram shows how the two controls, the RF Gain and Volume, are connected to the boards. The leads marked '+9 V' are all connected to the battery supply via a miniature on/off toggle switch. Double check all connections before connecting the battery.

Setting the VFO

Very little adjustment is needed to get the receiver going. Firstly, the VFO must be adjusted to cover the required band, in this case 3.5–3.8 MHz.

If you have a frequency counter, connect it to the output of the VFO. If you haven't, read this part anyway so you understand the process, then another means of setting the VFO will be given especially for you! Rotate VC1 until the vanes are fully meshed. Very carefully, adjust the core of the VFO coil (L1) with a plastic trimming tool so that the frequency approaches and settles at 3.500 MHz. When you rotate VC1, the frequency should increase to **at least** 3.800 MHz at the far end of its travel.

In the absence of a frequency counter, borrow a communications receiver, set it for SSB reception (USB or LSB) on exactly 3.500 MHz. Set VC1 with the vanes fully meshed and turn the core of L1 in both directions until you hear a whistle in the communications receiver. Rotate the core so that the whistle reduces in frequency. It will eventually fade out at around 200 Hz;


Screen connections
RF gain
Antenna
Variable frequency oscillator
+9V
Screen connections
Volume
Speaker
Audio amplifier
+9V
Mixer
+9V
©RSGB X168

Figure 4 Make sure that interconnections between the boards are correct, including cable screens

turn the core a little further and then leave it at that position. Rotate VC1 right to the other end of its travel, and search for the whistle with the tuning knob of the communications receiver. Check that the VFO frequency is at least 3.800 MHz.

Then, whichever method you are using for frequency measurement, mark the dial with frequency steps of 50 kHz. Setting and calibration are finished!

Setting the mixer

Again, there are various ways of doing this. If you have a signal generator, inject a signal at a frequency within the 80 m band, and adjust the cores of T1 and T2 sequentially for maximum output.

If you haven't a signal generator, connect an aerial to the mixer input, set the RF Gain to maximum (fully clockwise), and find a consistent signal. Adjust the volume control to a comfortable level. Rotating the core of T2 with your trimming tool, maximise the output. Then do the same with T1, although this will have much less effect. Find another station, and check that the positions of the cores aren't too different for a maximum signal.

You may find that your receiver benefits from the insertion of an aerial tuning unit (ATU) between the aerial and the input, to compensate for the impedance of your aerial not being 50 Ω. A design for such an ATU is presented in another part of this series. If the signals are still weak, connect the ATU to the junction of C1 and C2 via a 100 pF capacitor.

Try listening!

Remember that 80 m is a variable band. During daylight hours, your will hear Morse signals at the lower end of the band, and some British and closer continental stations between 3.7 and 3.8 MHz. In the evenings, stations up to 1000 miles away should be heard. Look for Novices around 3.7 MHz!

Parts list – VFO board

Resistors: all 0.25 watt, 5% tolerance		
R1	100 kilohms (kΩ)	
R2, R5, R6	100 ohms (Ω)	
R3, R4	10 kilohms (kΩ)	
RV1	1 kilohm (kΩ) linear	
Capacitors		
C1	12 picofarads (pF) polystyrene	
C2	100 picofarads (pF) polystyrene	
C3	470 picofarads (pF) polystyrene	
C4, C5	1 nanofarad (nF) polystyrene	
C6, C8, C9	10 nanofarads (nF) polystyrene	
C7	100 picofarads (pF) min. ceramic	
VC1	140 + 140 picofarads (pF) variable	
Semiconductors		
TR1	MPF102	FET
TR2	BC182	npn
D1	1N914	silicon
Inductors		
L1	Toko KANK3334	
RFC	1 mH	RF choke

Parts list – mixer board

Resistors: 0.25 watt, 5% tolerance

R1	1 kilohm (kΩ)
VR1	1 kilohm (kΩ) potentiometer (linear)

Capacitors

C1, C3	47 picofarads (pF) min. ceramic
C2	3.3 picofarads (pF) min. ceramic
C4	100 picofarads (pF) min. ceramic
C5	100 nanofarads (nF) min. ceramic
C6, C7	10 nanofarads (nF) min. ceramic
C8	220 microfarads (μF) electrolytic 16 V
C9	1 microfarad (μF) electrolytic 16 V

Integrated circuit

IC1	Philips NE602 or NE602A

Additional items

T1/T2	Toko KANK3333
	On/off switch
	Miniature toggle switch

The next part . . .

The IF amplifier and the Beat-Frequency Oscillator will be added to convert the *Colt* into a superheterodyne receiver.

26 A two-way Morse practice system

Introduction

It is said that the pleasure of sending and receiving Morse code more than compensates for the learning effort needed. Transmitters for Morse code can be much simpler than those needed for any of the speech modes.

Many people choose to learn sending and receiving on their own. It can be much more fun if you have someone to learn with you, and it is for this reason that the following project arose. It comprises just one small circuit, and you build an identical circuit for each of the people who want to learn with you. All the individual circuits are connected with their output leads in *parallel*, as the two-way circuit of **Figure 1** shows.

A simple circuit

This diagram shows two identical circuits, as would be used if two people wanted to learn together. The circuit centres around our old friend the NE555 integrated circuit (IC). As it is connected here, it works as an *astable multivibrator*, a daunting name for what is essentially an oscillator. Each circuit is self-contained, having its own battery, Morse key, sounder and


© RSGB
STATION A
STATION B
RV1 100k
R1 10k
R2 10k
C1 22n
C2 47n
R3 1k0
IC1 555
9V
+
8
4
7
6
2
1
5
3
Morse key
E1
E1 . High impedance ear-piece
Twin inter-connecting cable

Figure 1 The circuit diagram shows two stations, but you could connect several more if needed

plastic box. The Morse key makes and breaks the power supply to the circuit, thus turning on and off the note emitted by the earpiece. The frequency of the note is controlled by the variable resistor RV1, resistors R1 and R2, and the capacitor C1. The range given by RV1 is approximately from 500 Hz to 2200 Hz.

R3 protects the output of the IC against accidental shorting either to the 0 V or to the 9 V supply rails. For best results, a crystal earpiece or high-impedance headphones should be used. You could try Walkman-type headphones, but the volume may be too low for you.

The units may be interconnected with thin twin cable (the sort used for wiring doorbells) and can be comfortably separated by 25 m, more than enough to communicate between rooms, or even with a neighbour!

In use

When an operator presses his key, the note is heard by himself and by everyone else who is connected. If more than one key is pressed at the same time, two or more notes are heard by everyone! It helps if each person adjusts his own potentiometer, RV1, to give a note which is different from the others. When one operator stops sending, the other can start immediately, without pausing to change from transmit to receive. In practice, this technique is known as *full break-in*.

The current drawn by the circuit is only 10 milli-amps (mA) when the key is down, meaning that the life of a typical PP3 battery will be virtually its shelf-life! No switch is needed, because the key acts as the switch. The current drain will be even less if the NE555 is replaced by an ICM7555 IC. It has exactly the same pin connections as the NE555, so no circuit modifications are needed.

The circuit board

The circuit is constructed easily on a small piece of Veroboard of the copper-strip type. **Figure 2** shows the layout of the prototype, the board measuring 18 holes by 10 strips. **Be aware that there is no row 'I' when you are transferring mental images of where the parts are to real positions on the board!** Break the copper tracks where shown with a 3 mm ($\frac{1}{8}$ inch) twist drill, rotated carefully between thumb and forefinger. Hold the board up to a bright light to make sure that the tracks are completely broken and that there are no fragments of copper swarf shorting adjacent tracks. Then, solder in the wire links shown in Figure 2, followed by the resistors, RV1, and the capacitors, C1 and C2. Solder the battery connector leads to tracks A and G, G being positive. Use insulated wire to connect from the board to the jack sockets used as connectors for the key and the earphones. If you use


© RSGB
1 2 3 4 5 6 7 8 9 10 12 14 16 18
A B C D E F G H J K
9V PP3
Morse key
Ear-piece
Inter-connection
R3
R2
R1
C1
C2
IC1
VR1
Cut in copper track
Solder
Insulated wire link

Figure 2 The Morse Duet is an easy project to build on stripboard (Veroboard)

different sized jack sockets (i.e. 2.5 mm and 3.5 mm) you won't plug the earphones into the key socket! A two-screw terminal strip is useful to connect the cable runs between operators.

The key

The circuit is designed to be used with a *straight key* (one that moves up and down). It is a requirement of the UK Morse test that a straight key is used, so it is very sensible to learn sending with a straight key before you try anything more complex! You will find many to choose from at rallies.

Parts list

		Maplin order codes
For each board, you will need:		
Resistors: all 0.25 watt, 5% tolerance		
R1, R2	10 kilohms (kΩ)	M10K
R3	1 kilohm (kΩ)	M1K0
RV1	100 kilohm (kΩ) min. preset (horizontal mounting)	UH06G
Capacitors		
C1	22 nanofarads (nF) ceramic, 25 V	WX78K
C2	47 nanofarads (nF) ceramic, 25 V	RA47B

Integrated circuit	
IC1 NE555	QH66W
Additional items	
8-pin DIL socket	BL17T
Jack plug and socket 2.5 mm	HF76H, HF78K
Jack plug and socket 3.5 mm	HF80B, HF82D
Battery type PP3	
Battery connector	HF28F
Plastic box with lid 114 × 76 × 38 mm	LH14Q
Veroboard 0.1 inch with copper strips 18 holes × 10 strips	JP46A
Terminal strip (two section)	FE78K
Crystal earpiece	LB25C
Morse key	

27 The Colt 80 m receiver – Part 4

Introduction

In Parts 1 to 3 of this series, the design of an 80 metre direct-conversion receiver has been described. In this final part, we are going to change the circuit to operate as a superheterodyne receiver, or *superhet*. Most radio receivers are superhets, and they change the incoming signal to another frequency, known as the *intermediate frequency*, or IF, before producing an audio signal. The use of a superhet in a good receiver is mandated by the requirements for good *sensitivity* and *selectivity.*

Sensitivity and selectivity

Figure 1 shows the block diagram of the receiver. If you look closely, you will see that it is two similar circuits, one after the other. The incoming



Figure 1 This is how the different stages of the Colt go together to make a superhet receiver

signal is filtered and fed to a mixer where it is combined (mixed) with the signal from the variable-frequency oscillator (VFO). This oscillator operates at a frequency which is 455 kHz higher than the incoming signal from the aerial, and the mixer output is therefore at a frequency of 455 kHz. If you are not sure about this, please refer to the section 'The direct conversion process' in Part 3 of this project. This new frequency is called the *intermediate frequency*, or IF. This frequency doesn't change; the tuning is accomplished by the VFO, and the mixer output is *always* at 455 kHz. The extraction of the audio signal from the IF signal is identical with the direct conversion process which is used in your existing receiver.

This may seem a long-winded way of doing things, but it has its advantages. A receiver must have a good *sensitivity*, or gain, so that it can receive very weak signals. In very general terms, it is easier to handle low-frequency signals than it is to handle high-frequency signals. We are changing our signal frequency from around 3.6 MHz down to 0.455 MHz (455 kHz), which is much lower and can be filtered and amplified relatively easily. A second advantage is that it is easier to provide gain at a fixed frequency than at a variable frequency. Remember that the IF is fixed, and providing gain is, again, relatively simple.

Our receiver also needs good *selectivity*, the ability to separate (or select) one station from another very close to it in frequency. This requirement is significantly simplified by the fact that the IF is fixed, and a good filter in the IF circuits can do wonders for the rejection of adjacent-frequency stations! Several stages of IF amplification and filtering are possible in more adventurous designs.

The filtered signal at 455 kHz passes to another mixer which has an associated oscillator, usually called a *beat frequency oscillator* (BFO). When receiving CW (Morse) signals, the BFO is usually tuned about 1 kHz above or below the IF (i.e. at 454 or 456 kHz) to produce a 1 kHz beat note as the audio signal. This signal is then amplified and fed to a loudspeaker or headphones.

The circuit

Figure 2 shows the circuit of the IF section shown in the photograph on p. 94; this section is added to the existing circuit to make it a superhet. The existing mixer board (described in Part 3) is used as the first mixer. Between it and the audio amplifier is connected the new IF board.

The signal output from the first mixer (at 455 kHz IF) is fed into a *crystal filter*, the most expensive part in the whole receiver. It provides the selectivity which makes the Colt such a good receiver. Another NE602 mixer/oscillator chip follows the filter. The oscillator section is controlled by the tuned circuit in T1, the frequency of which can be altered by rotating the core inside the coil. Once set, it remains fixed.



Figure 2 The IF board is connected between the mixer and audio amplifier

At this stage you should have built the first mixer and the audio amplifier, and proved that they *both* work by using the circuit as a direct-conversion receiver. When you have finished constructing and checking the IF board, you will need to add it to your existing circuits.

Adjusting and testing

There are three pairs of connections to the IF board – the 9 V supply leads, the input leads and the output leads. The IF board should be mounted on the metal baseplate, along with the other boards. **In making the following connections, make absolutely sure that the braid of each piece of coaxial**

cable is soldered to the correct connection on each board. The same applies to the polarity of the 9 V leads. Disconnect the screened lead which presently goes from the first mixer board to the AF amplifier at the amplifier end. Connect it instead to the *input* of the IF board. Connect a new piece of screened cable from the IF output to the vacated AF input. Now connect the 9 V supply leads to the same points as the supply leads from the other boards. Check these newly made connections.

You should have confidence at this point that things should be right. After all, you *have* tested the direct-conversion process and you *know* it works. All that you are now testing is the IF board. This is the attraction of building a receiver in modules, working from the speaker backwards, and testing as you go!

The VFO and BFO need to be correctly adjusted. Mesh the vanes of the tuning capacitor and, using the same frequency measurement method as you did originally, set the VFO frequency to 3.955 MHz (which is 3.500 MHz + 0.455 MHz, if you hadn't guessed!). The BFO can be set using a frequency counter, but it is just as good to set it by listening to SSB or CW signals. A high-pitched hissing sound should be heard in the speaker. As you rotate the core, the pitch should reduce, go through a minimum, then increase again. Set the core at the minimum pitch position. You may want to readjust the two cores a little as your listening skills improve but, once you are happy, they will never need to be altered again!

In conclusion . . .

You should now have built a superhet receiver capable of excellent results. It uses the same type of circuit as that found in far more advanced receivers.



The superhet is far more sensitive than the direct-conversion type, and can weed out those elusive DX stations. You may have found that a station will appear at two places on the dial of the direct-conversion receiver; you will have no such problem with the superhet.

Parts list

Resistor

R1	1 kilohm (kΩ), 0.25 watt, 5% tolerance

Capacitors

C1, C2	10 nanofarads (nF) min. ceramic
C3, C6	100 nanofarads (nF) min. ceramic
C4	22 nanofarads (nF) min. ceramic
C5	1 microfarad (μF) 16 V electrolytic
C7	220 microfarad (μF) 16 V electrolytic

Integrated circuit

IC1	NE602

Additional items

ZD1	Zener, 6.2 V 0.5 watt
FL1	Crystal filter, Murata CFM455J
T1	Tuned inductor, Toko YHCS11100AC

28 A simple crystal set

Introduction

There are many designs of crystal set – they are all ‘simple’, and even the most seasoned radio amateur will build one of these every so often because it is something that never ceases to amaze! Although using modern components, the design is a period piece!

Design and construction

The circuit diagram of **Figure 1** shows the simplicity of the circuit. The prototype was constructed on a wooden baseboard with an aluminium front panel, although this could be made of wood if you prefer.

Winding the coil always causes the most groans but when finished, gives the most satisfaction. The construction of the coil is detailed in **Figure 2**. A discarded toilet roll centre is an ideal *former* on which to wind the coil. The coil will take up about 7 cm of the length of the tube, so assuming the tube is about 11 cm long, the ends of the coil will be about 2 cm in from each end of the tube.

The aerial coil, the *primary winding* of this radio-frequency (RF) transformer, is made from about 30 turns of 26 SWG enamelled copper wire, wound on the matchstick ribs. These ribs should be about 2 cm long, and are glued on **top** of the end of the secondary coil *after* the secondary coil has been wound. The *secondary winding* has 140 turns with *taps* every 10 turns for 70 turns. This coil covers most of the length of the cardboard tube. To make your coil-winding easier, here are some tips for completing the coil and still having some hair left at the end!

- Support the reel of wire on a dowel rod or pencil, clamped in a vice or held rigid in a vertical position by some other means. Don't leave it to trail around on the floor.
- Have a small piece of sandpaper handy to remove the enamel from the copper wire, starting with the end coming from the reel. Remove about 1 cm only, until the shiny copper is visible all round the end of the wire.



Figure 1 Circuit diagram of the crystal set


C
Taps every 10 turns
Primary or antenna coil, 30 turns
A
Approx 40mm dia
6 matchstick ribs glued in position
Secondary or tuning coil, 140 turns closewound with 26swg. or similar, enamelled copper wire
D
B

Figure 2 The coil is mounted on a cardboard tube as shown. Exact size is not too important. Try different taps for best results

- This part is the most difficult of all. Seasoned coil winders may have their own favourite ways of doing this, but for first-timers, play it safe and do it this way! Have a second bobbin (or a piece of stout card) ready, on which you will need to wind the wire loosely while you prepare the taps. Then, starting from the free end of the wire, measure 125 cm and, at this point, remove about 2 cm of the enamel with the sandpaper. Bend the wire firmly back on itself in the middle of the bared area, and *tin* (cover with solder) the exposed copper. This is your first tap. Then repeat this six more times at 125 cm intervals, thus giving you seven taps; wrap the wire as you go, on to the second bobbin or piece of card. After the seven taps, you are half-way down your coil so, to begin winding it in earnest, wind the wire carefully from the second bobbin or card **back** on to the original reel of wire.
- Looking at Figure 2, make two small holes about 3 mm apart, about 2 cm down from the top of the tube, where wire C will be entering. Poke the end of the wire into one hole, then bring it out again through the other; leave about 10 cm of wire on the free end. Loop this wire in and out once more, thus anchoring the wire firmly.
- Then, begin winding; keep the wire tight and make adjacent turns touch neatly. As you pass each tap, make sure it sticks outwards while avoiding flexing the wire too much; the wire is inherently weak at each tap.
- When you reach the last 10 cm of wire, stop. Put two more holes, like the first, beside your stopping point, and anchor the end, D, of the coil in the same way as you did with end C. The secondary winding is complete. Take a break *after* you have completed the next step!

- Prepare the six matchsticks for supporting the primary coil and glue these every 60 degrees around the end of the coil at D. Remove the enamel from the free end of the new copper wire on your reel and, using your favourite quick-drying cement, put a drop over the wire on one of the matchsticks, leaving 10 cm free as before. If you are using 26 SWG enamelled copper wire, its diameter is 0.46 mm, so 30 turns should occupy 14–15 mm of the 20 mm matchstick length. This will allow you to position the glued point such that the coil will be roughly in the centre of the matchsticks. When the glue has set, wind the 30 turns and anchor this end of the coil in the same way. Then remove the enamel at the end of the 10 cm lead.

Assembly

The coil former can be screwed to the baseboard at each end, *before* the front panel is screwed to the baseboard! As the photograph on the next page shows, the tuning capacitor is mounted in the centre of the front panel. Five solder tags (or drawing pins as a last resort) should be screwed into the baseboard. The two to the left of the photograph are the connections to the earphones, the two along the rear edge have the diode, D1, soldered to them. One end of the diode (and, for once, you can connect the diode either way round!) is connected to one earphone tag. The other end has a flying lead of about 10 cm attached to it and terminated in a crocodile clip which is used to connect to one of the taps on the coil. The fifth tag secures the end, A, of the primary coil, to which you will attach the aerial. The earth tag on the tuning capacitor, C1, serves as an anchor point for the ground connections to B and D and to the other earphone tag.

Use

The longest piece of wire you have available to use as an aerial should be connected to the aerial tag just mentioned. If you can connect the earth tag of the tuning capacitor to a good electrical earth, this will help also. You should be able to hear something as you turn the tuning knob. Try adjusting the tapping connections on the coil – change only one at a time, or you will never find the optimum positions. You now have a fully operational crystal set!

Simple it may be, but this circuit illustrates some important principles which are used even in the most expensive receivers. Firstly, the coil, L1, and the capacitor, C1, form a *tuned circuit* which *resonates* at the frequency of the station you have tuned in. This *selects* the signal you want to hear. The *modulation* on this signal is removed by the *detector*, D1, and fed to the earphones, which act as *transducers*, turning the electrical energy into sound energy which you can hear. It doesn't need a battery or other power supply either!



Parts list

Capacitors

C1	Variable capacitor of between 200 and 500 picofarads (pF) maximum
C2	100 picofarads (pF) min. ceramic

Additional items

D1	Germanium, type OA47 or OA90
	High impedance crystal earphone (not Walkman type)
	Tuning knob
	Wooden base, approx. 110 mm square
	Aluminium (or wood) front panel, approx. 80 × 100 mm
	Cardboard tube (toilet roll centre), about 110 mm long, 40 mm diameter
	Reel of 26 SWG enamelled copper wire for both windings of L1

29 A crystal calibrator

Introduction

A crystal calibrator is a device that produces oscillations of a precise frequency which are rich in *harmonics*. A harmonic is an integer multiple of the fundamental frequency; for example, if our fundamental frequency was 100 kHz (as it is in this circuit), there would be harmonics of this frequency at 200 kHz, 300 kHz, 400 kHz, and so on. These harmonics can be used, when picked up by any receiver, to calibrate that receiver, as the harmonics are quite accurate in frequency (see later for an assessment of accuracy). However, a gap of 100 kHz between harmonics is rather wide for most purposes, so we reduce this frequency to 25 kHz, so that the harmonics are then 25 kHz apart, thus producing a much more useful set of *marker points*. A calibrator such as this is often called a *crystal marker*, producing these marker points from 25 kHz to beyond 30 MHz.

The circuit

The circuit diagram is shown in **Figure 1**. The circuit around TR1 is the fundamental oscillator, and its frequency is controlled by the quartz crystal, X1. Even crystal oscillators are not 100% accurate, and the small trimmer capacitor, TC1, is able to ‘pull’ the frequency to one which is nearer the


© RSGB
R5 2k2
R6 150R
TC1 6–60p
R1 180k
X1 100 kHz
3
7
C2 1n0
R4 1k0
TR2 2N3904
D1 5V1 0W4
C4 100n
SW1 On/Off
R2 15k
b c e
TR1 2N3904
C1 2n2
C3 1n0
R3 6k8
2 3 4 6 7 10
1
IC1 74LS73
9
5 12 11
C5 12p
Output (Phono socket)
+
9V PP3 Battery
−
TR1
X1
TC1
Base view of crystal socket (B7G)
e b c
Base view of transistor 2N3904
D1 5V1 0W4 Zener diode
7 1
8 14
IC1 7473 or 74LS73

Figure 1 Circuit diagram of the calibrator which uses easily obtainable components

correct one. TR2 is a *buffer* stage, which isolates the oscillator from the rest of the circuit. It acts as a switch, and applies a good signal (switching between 0 and 5 V) to the input of IC1.

IC1 is an integrated circuit which can be connected to do several things. It is connected here to divide the incoming frequency by a factor of 4, producing on pin 9 an output frequency of 25 kHz.

The combination of R6, C4 and D1 produces a supply of 5 V for IC1; it would be damaged if the battery voltage were applied to it. You will no doubt be ready to assemble the circuit, so here is some information for you.

Construction

If possible, always build a circuit in individual stages, which you can test as you go along. It is not always easy in small projects like this, but even the crystal calibrator can be split into two for construction and testing.

It is an ideal project for assembly on Veroboard of the copper-strip type; the prototype layout is shown in **Figure 2**, on a board measuring 11 holes by 24 strips. First of all, remove the copper strip at the locations shown, using a 3 mm drill rotated between the fingers. Hold the board up to the light to ensure that there are no pieces of copper swarf bridging adjacent strips, and that the copper is completely removed where it should be! Assemble the circuit from left to right, but do not wire up anything around IC1. Be aware that the diagram shows the board *from the component side*. Although you


© RSGB
Crystal
pin 7
TC1
11 holes x 24holes
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24
A B C D E F G H I J K
C2
TR1
D1
R2
R3
C3
IC1
7
8
14
R4
R1
TR2
R6
C1
C4
R5
−ve
+9V via SW1
Out 25kHz to phono socket
⊗ indicates break in copper track
indicates insulated wire link on copper track side

Figure 2 Stripboard, such as Veroboard, should be cut as shown to approx. 62 × 28 mm

can use virtually any kind of crystal, you will need to mount it firmly. If you use a small one, it can be soldered directly in position on the board. With one in a valve envelope, you will need a B7G valveholder. Be prepared to mount the circuit in a **metal** container; the prototype used an (empty) tin of tuna! The valveholder mounts well on any metal case.

Disconnect the aerial of your receiver, and replace it with about 30 cm of wire laid near your oscillator circuit. Connect the battery and switch on. Tune the receiver around until you can hear a whistle on SSB. Rotate the tuning knob to reduce the frequency of the whistle and, as the whistle becomes too low to hear, you have reached one of the calibration markers, and your frequency will be an integer multiple of 100 kHz. If you are already using a calibrated receiver, you will be able to verify this. Going up or down in frequency should locate another marker 100 kHz away, and so on right through the receiver's tuning range. If the signals coming from the circuit are very weak, switch off the calibrator and connect another 30 cm piece of insulated wire to the collector of TR2, and lay it close to (but *not* touching) the wire from the aerial connector. Switch on an try again; you should not now have a problem! If you have access to a multimeter, check that the voltage at the collector of TR1 is very close to 5 V. If it is close to 9 V, you have connected the diode, D1, the wrong way round!

Having verified that the oscillator is working, you can now wire up the integrated circuit socket, being careful to put the notched end of the socket pointing towards R4, the collector resistor for TR2.

Check your connections around IC1, and when you are satisfied that they are correct, line up IC1 with its socket, making sure that the notched ends are together, and press down *gently* to insert the IC into its socket. Insert the 30 cm piece of insulated wire into the output socket, connect the battery and switch on. You should still hear whistles in your receiver, but now they should be 25 kHz apart, rather than 100 kHz apart.

All that now remains to be done is to mount the circuit rigidly inside whatever casing your have chosen. Make sure that none of the connections under the board touch the metal case, and secure the valveholder, on/off switch and output connector to the case. You now have a completed crystal calibrator.

Calibration

The simplest way to calibrate your circuit is with a frequency counter. Most clubs will have one of these and, if not, will know someone who has! Connect it to the collector of TR2, where the frequency should be 100 kHz. Do *not* connect it to any part of the circuit around TR1, or you may alter the frequency you are trying to measure! If the frequency is not exactly 100.000 kHz, rotate TC1 until it is (or is as close as you can get it). Now your calibrator is as accurate as the counter with which you have calibrated it.

Accuracy

Despite your best efforts at calibration, by whatever means, your crystal will *never* have a constant frequency. Such a thing is a scientific impossibility. It is usual to express the accuracy of a crystal in parts-per-million (ppm), and it is governed by many things, principally its temperature. You will be *very* fortunate if your circuit maintains an accuracy better than about ±10 ppm. Expressed in figures, it means that the true frequency can be anywhere between 99.999 kHz and 100.001 kHz, i.e. within 1 Hz of the correct frequency.

Although this may seem more than adequate, it is as well to remember that the accuracy degrades as the frequency increases. At 1 MHz the error will be ±10 Hz and at 10 MHz it will be ±100 Hz. At 30 MHz it will be 300 Hz. Even so, this should be acceptable for most non-critical applications.

Parts list

Resistors: all 0.25 watt, 5% tolerance		**Maplin code**
R1	180 kilohms (kΩ)	M180K
R2	15 kilohms (kΩ)	M15K
R3	6.8 kilohms (kΩ)	M6K8
R4	1 kilohm (kΩ)	M1K0
R5	2 kilohms (kΩ)	M2K0
R6	150 ohms (Ω)	M150R
Capacitors		
C1, C2, C3	1 nanofarad (nF) or 1000 picofarads (pF)	WX68Y
C4	100 nanofarads or 0.1 microfarad (μF)	YR75S
C5	12 picofarads (pF)	WX45Y
TC1	60 picofarads (pF) trimmer	WL72P
Semiconductors		
TR1, TR2	2N3904 npn	QR28F
IC1	7473 or 74LS73N dual JK flipflop	YF30H
D1	5.1V 500 mW Zener	QH07H
Additional items		
100 kHz crystal		
B7G valveholder (found at most rallies)		
14-pin DIL IC socket		BL18U
Phono socket		YW06G
PP3 battery connector		HF28F
PP3 battery		
On/off switch		FH00A
Veroboard		JP47B
Metal case as required		

30 A simple short-wave receiver – Part 1

Introduction

No apologies for yet another design of short-wave radio. This is the beauty of our hobby – there is always something new to try. Not all circuits operate in the same way; not all circuits work equally well; sometimes a simple design suits the operator better than a complicated design. So here is another one for your consideration; it's a good project for a novice, *and* a good one-evening project for someone more experienced.

A basic description

Figure 1 gives the block diagram of the receiver, which employs a *regenerative detector*, one of the earliest techniques by which excellent *selectivity* (the ability to separate two stations very close in frequency) could be combined with good *sensitivity* (the ability to pick up very weak stations) using a very simple circuit. The receiver falls into the category known as *tuned radio frequency* (TRF), meaning that the whole circuit (prior to the extraction of the modulation from the carrier) operates at the incoming radio frequency. In other words, it is *not* a superhet.

As you can see, the regenerative detector has what is called a *feedback loop*, which feeds a small amount of the output signal back to the input. You have heard the effects of feedback with a public address system, when the microphone gain is too great – everything becomes very loud and then bursts into a deafening squeal! This is exactly what the feedback does here, except that it is carefully controlled, thus providing both gain and selectivity. The resulting audio is then amplified for use with headphones.



Figure 1 Just two simple stages make up the circuit

The circuit

The circuit of **Figure 2** shows the complete system. TR1 is an untuned *field-effect transistor* (FET) stage, and is used to match the aerial to the next stage. Occasionally, a regenerative detector produces unwanted signals, and TR1 also prevents them from reaching the aerial and being transmitted! The smaller of the two windings on T1 (the *primary* winding) will match a low-impedance aerial, the capacitor input matching a high-impedance aerial.

Ignore TR2 for the moment – the next stage in the signal path is TR3, the detector, using another FET. The tuned circuit is formed by T2, VC1 and VC2 (remember TR1 is untuned). The primary winding on T2 taking the output from TR1. The reason for having two variable tuning capacitors, one large, the other small, is that the large capacitor is the main tuning capacitor, while the small one is used as a *bandspread* control (for very fine tuning). The tuned signals are then detected (converted to audio frequencies) by TR3.


©RSGB
C1 27p
Hi-Z
Antenna
Lo-Z
T1
R2 270R
C2 100n
TR1 2N3819
g d s
R1 330R
C4 10n
T2
C5 33µ
VR1 10-turn Pot
C3 10n
R3 22k
VC2 200/200p
VC1 10p
R4 47k
C6 10n
C7 68p
C8 330p
C9 330p
TR2 BC182
R5 270R
R6 3k3
C10 10n
R7 4k7
TR3 2N3819
C11 33µ
C12 10n
D1 6V2
R8 27k
R9 470k
C14 10n
C13 10n
C15 1n0
A
B
C
0V
R10 330R
+9V
R11 270R
C16 10µ
R12 4k7
TR4 BC182
C18 100n
VR2 10k
R13 2k7
C17 10µ
C20 10µ
IC1 LM386
1 2 3 4 5 6 7 8
R14 10R
C21 150µ
C23 150µ
C22 100n
R15 10R
R16 1k0
LS 8Ω Loudspeaker
0V

Figure 2 The circuit diagram showing the 10-turn potentiometer VR1. This is the regeneration control for the circuit

TR2 is a *Q-multiplier* stage. It is a Colpitts-type oscillator which uses C8 and C9 to give feedback and produce the oscillation. C7 couples the tuned circuit (and the input to TR3) to TR2. The tuned circuit thus controls the frequency of oscillation of TR2 and the signal passed on to TR3.

The secret of the ease of operation of this receiver is VR2, a 10-turn potentiometer (or *helipot*). The resistance wire is wound in the form of a helix, giving a much greater wire length than in a normal potentiometer, and the shaft must be turned ten times to cover the whole length. Helipots are very useful when very fine adjustments have to be made. Here, VR2 sets the regeneration (or *reaction*) level, depending on the type of signal you are receiving, as will be discussed in Part 2.

TR4 provides the first stage of audio amplification and, after the volume control, VR2, the audio amplifier integrated circuit, IC1, will drive a small loudspeaker or headphones.

In Part 2, the construction will be discussed, together with the choice of aerial, the parts list, and advice on using the receiver.

31 A fruit-powered medium-wave radio

Introduction

This is a one-evening project that will result in a working medium-wave (MW) radio, and will also teach you a little about the way electricity can be generated from the right metals and a little (safe) acid. All you need are three lemons or other citrus fruit, three pieces of copper and three pieces of zinc (or galvanised metal) for your power supply.

Construction

Figure 1 shows the circuit and **Figure 2** its layout on a simple ‘plug-in’ prototype board. The six pieces of metal are connected as shown, to wire the three lemons in series; use ordinary wire between each lemon and the next. If you have a meter to measure the total voltage, it should be about 1.8 V. Use a standard ferrite rod, and wind on it about 40 turns of single-conductor PVC-insulated wire.


Antenna input
VC1
Tuning
capacitor
Earpiece
socket
V+
Coil wound on ferrite rod
V–
Interconnecting tracks are shown dotted
C1
D1
R1
R2
TR1
c
b
e

Figure 1 Most parts are plugged into the board as shown – soldering is not required


Wire antenna
R1
10k
Crystal
earpiece
D1
C1
1n0
OA91
diode
R2
1M0
b
c
e
TR1
BC107
transistor
Coil
wound on
ferrite rod,
40 turns,
10mm dia
VC1
between 250p
and 500p
CT
ZT
+
–
Lemon
batteries
CT copper
terminal
ZT zinc
terminal

Figure 2 Three lemons power the radio, which gives good results for such a simple circuit

Wire up the circuit on the board as illustrated in Figure 2. Soldering is not required with this type of board – just plug in the components and the wires. Only one transistor is needed. The tuning capacitor, VC1, selects the station you want to hear, and D1 helps to remove the carrier from the RF signal. The resulting audio signal is fed to TR1, a small transistor audio amplifier, which makes the signal big enough to drive a crystal earpiece comfortably. Walkman-type earphones will not work, so invest in a crystal earpiece which you can use in several other projects, too! If you use a smaller capacitor than that specified for VC1, you will need more turns on the aerial coil.

Tests on the prototype indicated that the radio will run for about a week on three lemons!

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1	1 megohm (MΩ)
R2	10 kilohm (kΩ)

Capacitors

C1	1 nanofarad (nF) min. ceramic
VC1	250–500 picofarad (pF) variable

Semiconductors

TR1	BC107 npn (or BC108, BC109C)
D1	OA90, OA91 germanium (not silicon)

Coil

L1	2 metres of single-conductor insulated wire on a standard ferrite rod

Additional items
Plug-in prototype board, e.g. Maplin YR84F
Wire aerial at least 3 m long
Crystal earpiece
Three juicy fruits



32 A capacitance bridge

Introduction

It is always valuable to have a means of measuring capacitors amongst your test gear. Universal LCR bridges (i.e. systems that can measure inductance, capacitance and resistance) can be found at most rallies, and you can work your way up to owning one of these. In the meantime, a piece of home-made equipment gives you experience as well as resulting in a useful measuring instrument.

The circuit described here is called a *capacitance bridge*, because it balances the effects of one resistor/capacitor pair against another; if one capacitor has an unknown value, then the other can be calculated. The basic bridge circuit is shown in **Figure 1**. To avoid having calculations to perform, this instrument will be calibrated by using capacitors of known values. The bridge is a useful way of performing measurements, because a knob is turned until there is a null in the signal from an earpiece or loudspeaker. The ear is very precise in being able to perceive nulls, which makes the bridge easy to use and reasonably accurate. At the null, the bridge is said to be *balanced*.

How does it work?

Figure 2 is the circuit diagram for this capacitance bridge. Transistors TR1 and TR2 form an oscillator. This is the audio oscillator shown in Figure 1, and produces an alternating voltage which is fed to the bridge. RV1 (in the collector lead of TR2) replaces both R1 and R2 in Figure 1 – that part of



Figure 1 Simplified circuit of a capacitance bridge. R1 is adjusted for minimum sound


R1
10k
R2
100k
R3
100k
VR1
10k
lin
SK1
Phones
C3
100p
SW1
On/Off
C1
10n
C2
10n
Cx
C4
47µ
16V
9V
PP3
c
b
e
TR1
BC108
TR2
BC108
Crocodile clips
Case
Base view of BC108

Figure 2 Transistors TR1 and TR2 give an audio signal which is adjusted by variable resistor RV1

RV1 *above* the wiper represents R1, while that part *below* the wiper represents R2. The voltage on one side of the earpiece is determined by the ratio of these values, and is adjusted by rotating RV1. The voltage on the other side of the earpiece is determined by the ratio of C3 to Cx, where Cx is the unknown-valued capacitor. When these two voltages are the same, the bridge is balanced and there is no current through the earpiece.

Figure 3 shows the layout of the components on the matrix board of the prototype. It measures 10 holes by 14 holes, and is of the plain type, i.e. no copper strips. All earth connections are taken to a single solder tag. When


+9V via SW1
1
2
3
4
5
6
7
8
9
10
R1
R2
R3
C1
C2
TR1
TR2
c
b
e
To VR1
To crocodile clip
Solder tag (6BA bolt to case)
1 2 3 4 5 6 7 8 9 10 11 12 13 14
Perforated board 10 x 14 holes

Figure 3 Components are soldered together on a small prototype board


VR1
With pointer, knob and scale
−ve
C4
C3
SW1
+9V
Perforated component board
SK1
Plastic or Perspex isolator
Crocodile clips
Cx
©RSGB X184

Figure 4 Layout of the parts inside an aluminium box. The earpiece socket is insulated from the case

mounting the board inside a metal box, a long screw is used with extra nuts, to earth the board to the case while providing a stand-off, thus preventing any unwanted short-circuits between the board connections and the case. Be aware that a *crystal* earpiece must be used; low-impedance headphones of the Walkman type are not satisfactory. Solder two flying leads as shown in **Figure 4**, about 15 cm long, terminated in small crocodile clips for attaching to the unknown capacitor.

Calibration

After checking the circuit carefully, attach the battery and switch on; a buzzing noise should be heard in the earpiece. This is the first sign that everything should be OK. If there is no buzz, switch off and recheck the connections.

You will now need a range of close-tolerance (1%) silver-mica capacitors covering the range 10 to 1000 picofarads (pF). Arrange the capacitors in ascending order and connect them to your bridge in sequence. After having prepared a neat piece of card or paper mounted behind the knob on the front panel, mark the dial at the positions of the nulls for all the capacitors. You have now calibrated your capacitance bridge. If you are more likely to want to measure larger capacitors, replace C3 by a 1 nanofarad (nF) capacitor, and the bridge will measure up to 10 nF approximately.

Parts list

Resistors: all 0.25 watt, 5% tolerance	
R1	10 kilohms (kΩ)
R2, R3	100 kilohms (kΩ)
RV1	10 kilohms (kΩ) linear
Capacitors	
C1, C2	10 nanofarads (nF) ceramic
C3	100 picofarads (pF) silver mica or polystyrene
C4	47 microfarads (μF) 16 V electrolytic
Semiconductors	
TR1, TR2	BC108 npn
Additional items	
SW1	SPST on/off switch
	Battery connector, PP3 type
	Earpiece, crystal type
SK1	3.5 mm jack socket for earpiece
	Battery, 9 V PP3
	Matrix board, approx. 10 holes by 14 holes
	Aluminium case, approx. 10 × 8 × 5 cm

33 A simple short-wave receiver – Part 2

Introduction

In Part 1, the design of this receiver was discussed in some detail. Now we are going to put it all together and see how it works. The receiver is laid out on a printed-circuit board (PCB) or on a matrix board.

Construction

The layout of the components is shown in **Figure 1**. Identify each part separately, insert it into the holes in the board and solder carefully. Long leads may be cropped before or after soldering, depending on your skill and preference. All electrolytic capacitors, T1, T2 and IC1, must be connected correctly. The front-panel controls are connected to the PCB terminals shown in Figure 1.

The layout of the controls and the placing of the board inside the case are matters of personal preference. The size of the prototype front panel is shown in **Figure 2**. The prototype had a slow-motion drive fitted to VC2, the main tuning capacitor. This required the capacitor to be fitted on its own small panel. The bandspread control does not need any form of


150µ
150µ
150µ
1k0
10µ
LM386
100n
10R
10R
270R
4k7
2k7
10µ
10n
1n0
10n
100n
1n0
10µ
TR4
330R
D1
6V2
10n
470k
270R
27k
10n
TR3
10n
3k3
TR2
10n
22k
47k
68p
330p
330p
T2
33µ
4k7
270R
10n
33µ
TR1
27p
T1
10n
330R
Hi-Z
Antenna
Lo-Z
0V
+9V
LS
Volume control
VR2
10-turn Pot
VR1
Tuning capacitors
VC1, 2

Figure 1 Layout of the receiver circuit board



Figure 2 The case can be metal or made from PCB material

slow-motion drive. A tuning dial may be fitted behind the tuning knob on VC2 if required. The volume control, VR2, has its own on/off switch for the battery, which can be mounted behind the back panel, on which are mounted the aerial input sockets and the headphone/speaker socket. Check your soldering carefully, together with all the wiring between the board, the potentiometers and variable capacitors. When you are confident that everything is perfect, connect the battery and switch on.

The first tests

If you have a good aerial and are using an aerial tuning unit (ATU), use the low-impedance input. Excellent results are possible, though, with about 3 metres of wire connected to the high-impedance input. Set the volume control to give a gentle hiss in the headphones or speaker. Advance the reaction control to give a definite hiss. As you tune in an AM station, the hiss will change to a whistle; back off the reaction until the oscillation *just* stops. The receiver is now correctly set for AM reception.

On the amateur bands, the stations will be SSB or CW, and the reaction needs to be set *just above* the oscillation point, and will need slight adjustment from time to time for different qualities of signal. Juggling with the volume, reaction and tuning is part of the pleasure of using regenerative receivers!

In action

Practice is needed for best results. The regenerative receiver is renowned for its versatility in being able to be set up *exactly* for all types and strengths of signal. The basic receiver tunes from 6.5 MHz to 11 MHz approximately; this includes two amateur bands at 7.0 MHz and 10.1 MHz and two broadcast bands.

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1, R10	330 ohms (Ω)
R2, R5, R11	270 ohms (Ω)
R3	22 kilohms (kΩ)
R4	47 kilohms (kΩ)
R6	3.3 kilohms (kΩ)
R7, R12	4.7 kilohms (kΩ)
R8	27 kilohms (kΩ)
R9	470 kilohms (kΩ)
R13	2.7 kilohms (kΩ)
R14, R15	10 ohms (Ω)
R16	1 kilohm (kΩ)
VR1	10 kilohm (kΩ) linear 10-turn potentiometer
VR2	10 kilohm (kΩ) log potentiometer

Capacitors

C1	27 picofarads (pF)
C2, C18, C22	100 nanofarads (nF)
C3, C4, C6, C10, C13, C14	10 nanofarads (nF)
C5, C11	33 microfarads (μF) 16 V electrolytic
C7	68 picofarads (pF)
C8, C9	330 picofarads (pF)
C15	1 nanofarad (nF)
C16, C17, C20	10 microfarads (μF) 16 V electrolytic
C21, C23	150 microfarads (μF) 16 V electrolytic
VC1	10 picofarads (pF) variable
VC2	200 picofarads (pF) variable

Semiconductors

TR1, TR3	2N3819
TR2, TR4	BC182
IC1	LM386
D1	6.2 V 0.5 W Zener

Inductors

T1	3 turns primary, 15 turns secondary, wound on 2-hole ferrite bead, with 28 SWG wire
T2	2 turns primary, 17 turns secondary, wound on a T68-2 toroidal former, with 28 SWG wire

Additional items

- Printed-circuit board
- Battery connector
- PP3 battery
- 8-pin DIL socket
- 8 ohm speaker or headphones (Walkman type)
- Case to suit



34 A basic continuity tester

Introduction

This little device can be built on a plug-in breadboard, and is ideal for testing fuses and cables, as well as doubling as a signal source for testing amplifiers, etc. It can even be used for testing npn transistors by replacing either of the transistors in the circuit, and seeing if the circuit still works!

Simple and quick to build

Using a plug-in breadboard, this circuit is so simple it could almost be built when you need it, and then dismantled again! If you want the circuit to make a different sound, the components to change are R2, R3, C1 and C2. Always make sure that R2 = R3 and C1 = C2, or the sound may be excessively 'edgy' and lacking in volume.

Basically, the circuit is an oscillator which drives a little loudspeaker directly. The fuse or cable you are testing is connected between the crocodile clips. If there is a current path between the two clips, the current also flows through the circuit, thus operating the oscillator and producing a sound from the loudspeaker.


© RSGB
+9V
(Battery +)
Crocodile clips
LS1
R1
12k
R2
47k
R3
47k
R4
390R
R5
100k
C3
100n
C1 47n
C2 47n
Optional audio output
TR1
BC108
TR2
BC108
0V
(Battery –)

Figure 1 The circuit diagram of the continuity tester

If you want to use the circuit to produce a signal to test an amplifier, for instance, connect the croc clip which comes directly from the battery to the junction of R1, R2, R3 and R4. This supplies current to the circuit while, at the same time, bypassing the loudspeaker. Use the two components R5 and C3 between the oscillator and your amplifier. The loudspeaker is bypassed because you will want to listen to the output from your amplifier, *not* from the oscillator!

Remember, NEVER test any equipment which is still connected to the mains electricity supply. Avoid testing anything which is switched on and has its own power supply. You may damage both your tester ***and*** the circuit you are 'testing'!

Parts list

Resistors: all 0.25 watt, 5% tolerance	
R1	12 kilohms (kΩ)
R2, R3	47 kilohms (kΩ)
R4	390 ohms (Ω)
R5	100 kilohms (kΩ) optional
Capacitors	
C1, C2	47 nanofarads (nF) ceramic
C3	100 nanofarads (nF), 0.1 microfarads (μF) ceramic optional
Semiconductors	
TR1, TR2	BC108 npn
Additional items	
LS1	Loudspeaker (8 Ω)
	2 crocodile clips
	Prototype circuit board
	PP3 battery connector
	PP3 battery

35 A charger for NiCad batteries

Introduction

The cost of replacing dry batteries can be alleviated to a great extent by the use of rechargeable batteries such as those containing nickel and cadmium (called *NiCads*). They are more expensive than the batteries they replace, but they can be charged hundreds of times and thus prove cheaper in the long run.

NiCads produce only 1.2 V per cell, compared with the 1.5 V of ordinary cells, so before you rush out and buy lots of these, please make sure that the equipment on which you plan to use them will work on the reduced voltage! For example, if you are using four cells to give you a 6 V supply, NiCads will give you only 4.8 V, which is quite a reduction. Using six cells to replace a 9 V battery will give you only 7.2 V. Not all equipment is happy with these reductions!

However, we all use them when we can, and they save substantial amounts of money. Here is the circuit of a charger to keep them in prime condition.

Charging NiCads – the ampère-hour

NiCads require charging at constant current, which means that connecting one across a normal power supply (constant *voltage*) is useless and can destroy it. They need pampering to the extent of needing a long charge (around 16 hours) at a rate dependent upon the *capacity* of the battery. By the capacity of a battery, we mean how much energy it can store. You will probably know that energy is measured in joules. For the purposes of storing energy in batteries, the joule is *not* the ideal unit, so we use one that is! This unit is the ampère-hour (Ah), and must be interpreted with some realism. For example, if the battery is rated at 2 Ah, it will deliver a current of 0.5 amp for 4 hours, or 0.25 amp for 8 hours. Provided the current is not too high, the product of the current (in amps) and the time for which it will flow (in hours) before the battery is flat will always be around 2 Ah. A workable ‘rule of thumb’ for calculating the charging current is that its value should be around one-tenth of the numerical value of the capacity; so, for our 2 Ah battery, a charging current of around 200 mA (2 ÷ 10 = 0.2 A or 200 mA) would be used.

Constant voltage to constant current

Many integrated circuit (IC) chips are available for use as voltage regulators, i.e. they supply a constant voltage. Most of these can be persuaded to become constant current supplies with one external resistor!

The voltage regulator IC usually has only three connections – ‘input’, ‘output’ and ‘common’. It is designed (in the case of the LM7805) to produce a constant 5 V output between the ‘output’ and the ‘common’ connections, at currents of up to 1 A. If a resistor is connected between these, the IC will maintain 5 V across it. If you look at **Figure 1**, you will see the circuit performing this conversion.



Figure 1 Voltage regulator arranged to produce a constant current

For the previous example, we derived a charging current of 200 mA, so we now need to calculate the value of resistor that will produce this current. Using the equation which is derived from Ohm’s law:

$$I = \frac{V}{R}, \text{ from which } R = \frac{V}{I},$$

where R = R1, the resistance in ohms that we are calculating,
V is the voltage across R1 (5 V), and
I is the current flowing (200 mA).

So,

$$\mathrm{R1} = \frac{5}{0.2} = 25\,\Omega.$$

25 ohms is not a ‘common’ or ‘preferred’ resistor value, so we must choose the next *largest* value, which is 27 Ω. This reduces the current, but only slightly – it is now 185 mA. When calculating resistor values in power supply circuits, we must *always* check the power that they dissipate and make sure we specify and fit a suitable resistor.

Power (in watts) is the product of the voltage across and the current through a device, so in this case it is given by:

$$\text{Power} = V \times I = 5 \times 0.185 = 0.925\,\text{W}.$$

Rather than use a 1 watt resistor operating very near its limit, it is safer to use a 2 watt resistor operating well within its limits.

Looking again at Figure 1, we now have a constant-current source producing 185 mA, when R1 is a 27 Ω, 2 W resistor. For use with NiCads requiring charging currents other than 200 mA, you will need to repeat the two equations above, using a new value for *I*.

The full circuit and its assembly

This is shown in **Figure 2**, and can be broken down into two parts. The first is the AC to DC conversion produced by the mains transformer, T1, the bridge rectifier, BR1, and the smoothing capacitor, C1. The second is the constant-current section already discussed.



Figure 2 The complete circuit including mains components

The prototype was assembled on matrix board measuring 18 holes by 12 strips, although, as **Figure 3** shows, this is much larger than is strictly necessary. No strip cutting is needed, but make sure that IC1 and C1 are inserted correctly.

Warning! Before you attempt to wire up the transformer and the bridge rectifier, be aware that you will eventually be connecting the circuit to the mains supply, so there are three possibilities for you: (1) get a qualified friend to supervise your completion and testing of the circuit; (2) get your qualified friend to complete and test the circuit for you; (3) replace the transformer and bridge rectifier with a mains adapter.



Figure 3 The charger can be built on Veroboard

If you decide to use the mains adapter, its output is connected directly across C1, because T1 and BR1 are now no longer needed. Make sure the polarity (positive and negative) is correct and that the adapter output is set to 12 V.

A quick test

If you have built the mains version, make sure all connections are correct, and that there are no soldered joints which will touch other parts of the circuit. The box must be securely closed before tests begin. The RSGB cannot be held responsible for damage to equipment or batteries! The version using the mains adapter need not be closed during tests.

Switch on. With nothing connected to the output, the unit should run cold. If this is not the case, switch off and recheck your circuit. If all is well, switch on again and connect a DC multimeter (on the current range) across the output. It should indicate only a slight difference from the calculated value of 185 mA. You can now charge your NiCads!

Other charging currents can be set by having different values for R1, perhaps selectable by a rotary switch. Remember to make sure that the values of both resistance *and* power dissipation are correct, and don't exceed the 250 mA rating of the transformer (or the 1 amp rating of the IC if you are using a bigger transformer).

Parts list

		Maplin code
Resistor		
R1	As required – see text	
Capacitor		
C1	1000 microfarads (μF) 35 V electrolytic	FF18U
Semiconductors		
IC1	LM7805 5 V, 1 A regulator	CR14Q
BR1	W005 50 V, 1 A full-wave rectifier	QL37S
Transformer		
T1	9–0–9 V, 250 mA sub-min. transformer	YN15R
Additional items		
Case		FG41U
Veroboard, 18 holes by 12 strips		
Plug to suit NiCads		
Double-sided sticky tape as required		
Insulated wire for battery connections		

36 An 80 metre crystal-controlled CW transmitter

Introduction

A simple transmitter is ideally suited to anyone venturing into our marvellous hobby for the first time. If you are put off by the complexities and prices of the 'black boxes' then this is the transmitter you've been looking for!

The circuit

The complete circuit is shown in **Figure 1**. It is a single-transistor crystal oscillator which is *keyed* (switched on and off) by the Morse key in the +12 V supply rail. The circuit first appeared in *QST* (the American equivalent of *RadCom*) in 1982, and has since appeared in a modified form in the *ARRL Handbook*. The circuit can produce about 2 watts on 80 m, and can be constructed on a piece of plain matrix board; the prototype board measured 7 cm by 3 cm, and its layout is shown in **Figure 2**.

Note that a bare copper wire runs along the bottom edge of the board to act as an earth wire for the relevant components. The only 'difficult' part of the construction is the winding and wiring of T1. The main winding is 38 turns of 26 SWG enamelled copper wire, and there are two link windings of four turns each. Make sure that all windings are wound the correct way round the toroid – Figure 1 shows this and should be studied carefully. If the windings do not have the correct *sense* (i.e. a clockwise coil has been wound anticlockwise, or vice versa), or have been connected incorrectly to the rest of the circuit, the oscillator will not work!

When putting components on the board, wire in the crystal socket *without the crystal in it*. Crystals do not like to be subjected to the horrors of a soldering iron, so keep your crystal to one side during the construction process!


© RSGB
C2078
TR1
2SC2078
b c e
TR1
collector
+12V
4-turn
link
To VC1
38-turns
T1
4-turn
link
To L1
T1... 38-turns of 26swg wire wound
on T-50-2 toroid – 2 link windings of
4-turns (each) wound with 26swg wire
C1
1000p
(1n0)
C2
100p
Crystal
TR1
2SC2078
Ferrite
bead
b
c
e
C4
100p
D1
1N
4148
R1
12k
L1... 21-turns of 22swg
wire wound on
T-50-2 toroid
T1
VC1
100p
C3
100p
RF out to
changeover
switch
L1
C7a
680p
C7b
68p
C8a
680p
C8b
68p
C5
10n
+
C6
10µ
25V
Key
+12V

Figure 1 The simplest form of transmitter is a keyed crystal oscillator. Note that L1, C7 and C8 make up a *low-pass filter* which reduces unwanted *harmonics* (outputs at the transmitter frequency multiplied by 2, 3, 4, etc.)


7 x 3cm perforated board
To +12V via key
To changeover switch
L1
Crystal
C2
+
C6
C5
R1
RF out
C1
C7a
C8a
To crystal
T1
b
c
e
TR1
C7b
C8b
To TR1 base
VC1
D1
C4
C3 mounted on underside
------ wires on underside of board
Large heatsink for TR1
Ferrite bead on TR1 base lead
RG174 miniature coaxial cable or screened audio lead
To L1
To key
Changeover switch
To antenna socket on rear panel
+12V socket on rear panel
To receiver socket on rear panel
no connection
© RSGB

Figure 2 Component layout is straightforward on a 'matrix board' (it has holes but no copper strips). The dotted lines are the connecting wires. The lower part shows the connections for the transmit/receive switch

The output filter, which comprises C7, C8 and L1, is a *low-pass* filter, which helps reduce any *harmonics* present in your signal. Harmonics are integral multiples of your transmitter frequency, so if you are transmitting on a frequency, *f*, harmonics will be present at frequencies 2*f*, 3*f*, 4*f*, . . . and so on. L2 is another inductance using 22 SWG enamelled copper on a ferrite toroid. The changeover switch is external to the transmitter board, and is used to switch your aerial between the transmitter and the receiver; its wiring is shown in Figure 2.

Use a dummy load

A dummy load enables you to test your circuit without actually transmitting a signal. If you haven't such a thing already, it is easy to construct one to use with this transmitter. Don't use it for transmitters of more than 2 watts output, though. Use two 100 ohm, 1 watt resistors, connected in parallel across the end of a short piece of coaxial cable, terminated in a BNC, PL259 or N-type free plug, as shown in **Figure 3**. Plug this into the aerial socket on your transmitter, plug in your crystal and connect the transmitter to a 12 V supply. Have another receiver switched on and tuned to the crystal frequency. Although the radiation from your dummy load is minimal, it will



Figure 3 A simple 2 W dummy load can be made from two 100 Ω (ohm) resistors in parallel. The plug should match the socket on your transmitter

be enough to be picked up by a receiver in the same room. Send dashes with the Morse key, and adjust VC1 until the received note is *clean*. It should not sound rough, or have a *chirp* (change its frequency during a dash or dot). Avoid tuning for maximum power; this is seldom the correct setting!

You will need to put your completed transmitter in a metal box, using sockets for the power supply, aerial, receiver and Morse key. The sockets can be chosen to match your existing equipment.

Figures 4–7 are taken from the RSGB book *Practical Antennas for Novices*, and may give you some ideas on the type of aerial to be used with your transmitter.



Figure 4 A simple dipole can be very effective. For the 3.5 MHz band, length L is 40 metres and height H should be as large as possible. The far support S can be a tree, pole or building. Insulators I may be home made from strong plastic and the feeder F should be 50 Ω (ohm) coax cable



Figure 5 Your signal is radiated mostly from the centre of the dipole so the ends can droop or even be bent but the length may need shortening by a few centimetres because the ground and the bends will detune the dipole. Cords C are best made from strong plastic rope from a sailing or camping shop


© RSGB
20m
10m

Figure 6 An 'inverted-L' takes up less space than a dipole and doesn't need coax cable. Like the dipole, the end can droop or be bent to save space as in this case most of the radiation comes from the area around the top of the vertical part


Wire to antenna 1 (switched)
ATU
Transmitter/Receiver
SWR Meter
50Ω
50Ω
50Ω
Earth wire
Coaxial feeder to antenna 2 (switched)
© RSGB

Figure 7 Almost any length of wire more than 10 m or so long will work (though it will work better the longer and higher it is) but an Aerial System Tuning Unit (ASTU or ATU) will be needed



Parts list

Resistor

R1	12 kilohms (kΩ), 0.25 watt, 5% tolerance

Capacitors

C1	1000 picofarads (pF) polystyrene
C2	100 picofarads (pF) polystyrene
C7a, C8a	680 picofarads (pF) polystyrene
C7b, C8b	68 picofarads (pF) polystyrene
C3, C4	100 picofarads (pF) ceramic
C5	10 nanofarads (nF) polyester
C6	10 microfarads (μF) electrolytic 25 V
VC1	100 picofarads (pF) trimmer

Semiconductors

D1	1N4148
TR1	2SC2078 (see sources list)

Inductors

T1	38 turns 26 SWG enamelled copper on T–50–2 toroid, with two link windings of four turns
L1	21 turns 22 SWG enamelled copper on T–50–2 toroid

Additional items

- Ferrite bead
- Crystal (e.g. 3.579 MHz) and holder
- Metal box
- Socket for Morse key.
  This must be totally isolated from the metal of the box, as *both* connections can be at +12 V.
- Sockets for 12 V supply, aerial and receiver
- Switch – DPDT
- Heat sink for TR1
- RG174 miniature coaxial cable for signal leads (see Figure 2)

Component sources

Special components

2SC2078	Cricklewood Electronics Ltd, 40 Cricklewood Broadway, London, NW2 3ET.

37 A solar-powered MW radio

Introduction

What could be more ecologically friendly than a radio powered by the sun's energy? This design is quite standard, and if you have built any of the other medium-wave radios in this series, then this one should present few problems.

The solar panel

The solar panel is to the solar cell as the battery is to the cell; in other words a solar panel is several solar cells connected in series. The solar panel quoted for this radio will generate about 9 V at a current of around 30 mA on a sunny day. The circuit will operate on a supply of around 2 V, so bright sunshine is *not* necessary for satisfactory operation. The volume will be less, of course.

The circuit

The radio uses the ZN415E integrated circuit (IC), connected as shown in **Figure 1**, the complete circuit diagram. The signal is tuned in by the combination of L1 and VC1. L1 is made by winding about 35 turns of 24 SWG enamelled copper wire on a ferrite rod. A standard ferrite rod of 10 cm length and 1 cm diameter is used.

Signals selected by the tuned circuit are passed to IC1, which amplifies the signals and removes the audio component, which is then amplified further by IC2 for driving a small loudspeaker. The removal of the audio component is the process we call *detection*. In addition to this, IC1 provides *automatic gain control* (AGC), which helps to keep the audio signal constant, even when the incoming RF signal may vary due to fading.

The prototype board

Veroboard (also known as matrix board or stripboard) is ideal for the construction of the radio. The layout is shown in **Figure 2**. The board size is 11 strips by 30 holes (**please note that there is no row 'I', so take care with your counting!**). Using a 3 mm (⅛ inch) twist drill rotated between


R1
3k3
C2
220µ
D1
1N4148
D2
1N4148
C7
1000µ
nc
LS1
32 to 64R
Solar panel
L1
VC1
Tune
IC1
ZN415E
IC2
TDA7052
C1
10n
C3
100n
C4
100n
C5
10n
R2
100R
C6
10µ
VR1
1k0
nc
nc – no connection
Dot
Notch
There will either be a notch or a dot in the plastic body – this tells you which way round to mount the IC
IC1 and IC2
Diodes D1 and D2
© RSGB

Figure 1 The radio uses just two integrated circuits (chips) and operates at any voltage from 2 to 9 V


1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
A B C D E F G H J K L
R1
C2
C7
D1
C4
C3
IC1
C6
C5
R2
IC2
D2
C1
Solar cell + terminal
Loudspeaker
32 to 64R
Solar cell – terminal
Ferrite rod
L1 approx 35-turns
S
S
S indicates Sellotape strip
VC1
Tuning capacitor
VR1 Volume control
L1, VC1 and VR1 are not to scale
⊗ Copper strips are cut here
●——● indicates insulated wire links on the copper strip side
Track J is not used
IC1 and IC2 are mounted in IC sockets
© RSGB

Figure 2 Follow the layout carefully, making sure that all connections are neatly soldered

your thumb and forefinger, break the strips at the points marked with a cross inside a circle. Hold the board up to the light to ensure that the tracks *have* been broken and that there is no copper swarf shorting tracks together.

Firstly, solder in the 8-pin DIL sockets for the ICs, making sure that the notches in the sockets are facing upwards, as shown on the diagram. Then, solder in the wire links, resistors, capacitors and diodes, making sure that the electrolytic capacitors (C2, C6 and C7) and the diodes (D1 and D2) are connected the correct way round. Use different colours of wire for the connections to the volume control, VR1, to avoid incorrect connections. Note the wiring of the tuning capacitor (VC1) shown in Figure 2; a two-section type is used, and both sections are wired in parallel to give twice the capacitance of a single section.

There is no on/off switch – just turn the volume down when you are finished using the set! The solar panel can be mounted parallel to the top of the case, or angled to receive the maximum energy from the sun, as shown in the photograph. You could have a battery available as a standby source to use the radio after dark; any battery of between 6 V and 9 V will do. Wire it with a simple changeover switch, so you can switch between solar and battery power. Ask a friend for help with this if you are not sure how to do it.

You may need to adjust the number of turns on L1 to get the best results, but it should be possible to receive at least five stations at good volume with your sun-powered radio!



Parts list

		Maplin code
Resistors: 0.25 watts, 5% tolerance		
R1	3.3 kilohms (kΩ)	M3K3
R2	100 ohms (Ω)	M100R
VR1	1 kilohm (kΩ) log	FW21X
Capacitors		
C1, C5	10 nanofarads (nF) ceramic	BX00A
C2	220 microfarads (μF) electrolytic (10 V)	FB60Q
C3, C4	100 nanofarads ceramic	YR75S
C6	10 microfarads (μF) electrolytic (10 V)	FB22Y
C7	1000 microfarads (μF) electrolytic (10 V)	FB81C
VC1	140–300 picofarads (pF)	FT78K
Semiconductors		
IC1	ZN415E (or ZN416E)	UR70M
IC2	TDA7052	UK79L
D1, D2	1N4148	QL80B
Solar panel	9 V at 50 mA	RK23A
Additional items		
LS1	32–64 ohm miniature loudspeaker	YT28F
	Ferrite rod	YG20W
	24 SWG enamelled copper wire	BL28F
	Plastic box, approx. 220 × 140 × 70 mm	YN39N
	Veroboard, cut to size	JP47B
	8-pin DIL sockets, 2 required	BL17T
	Knobs, 2 required	FD67X
	Material for speaker grille	
	Connecting wire	

38 A receiver for the 7 MHz amateur band

Introduction

Listening on the 40 metre band (from 7.0 to 7.1 MHz) can be very rewarding – it is a popular haunt for HF Special Event stations, and at night there are signals to be heard from all over Europe. This receiver is designed purely for the 40 m band, and is ideal for those who have built the simpler receivers and are looking for something a little more challenging. The more experienced constructor may prefer to build this on prototype board.

The circuit and its construction

Figure 1 shows the circuit diagram. The receiver will work well with headphones or loudspeaker. Walkman-type headphones and speakers are ideal for use here.


C2 47µ 16V
C6 100n
+5V
Out
IC3
In
Com
+5V stab
+9V
C15 1000µ 16V
SW1
+9V (Battery+)
L1
C1 470p
VR1 4k7 lin
IC1
C5 100p
L2
IC2
R2 1k5
R3 1k5
R4 100k
IC4a
R6 12k
R7 12k
C13 47n
IC4b
C16 1µ0 16V
IC1 ... NE602
IC2 ... NE602
IC3 ... 78L05
IC4 ... TL072
IC5 ... TDA7052
C3 47p
C4 100p
X1
X1 — Crystal = 4·608MHz
C10 1n0
L3 10µ
C8 2n2
C11 10n
R5 220R
C12 470µ 16V
C14 10n
R8 10k
IC5
LS
0V (Battery −)
+5V stab
VR2 4k7 lin
VR3 47k lin
R1 100k
C7 100n
C9 1n0
D1 1/2 KV1236
INTEGRATED CIRCUITS IC1, 2, 4 and 5
8 7 6 5
1 2 3 4
Top view of pins
© RSGB
COILS L1 and L2
Base view
VARICAP DIODE
Cut here
36Z 112
0V
R1
Lettering side
IC3 78L05
+5V Out
0V Com
+9V In
Base view of pins
EXTERNAL DC CONNECTOR
PP3 9V
To SW1
To PCB
Rear view

Figure 1 The receiver gives good performance on the 7 MHz amateur band as well as being simple to construct and align

Signals arriving at the aerial are coupled into IC1 via gain control VR1, which also functions as the on/off switch. Tuning is provided by varying the voltage on the *varactor diode* (or varicap), D1. VR3 is the main tuning control, and VR2 is the *bandspread* (fine tuning) control. The varactor diode is supplied as a dual device, which must be cut down the middle *carefully* with a sharp knife; with the lettering upwards, the ground lead (0 V) is on the left-hand side, as Figure 1 illustrates.

Solder in the IC sockets first, followed by the coils. After this come the links, resistors, capacitors and varactor diode. Ensure that IC3, the voltage regulator, is wired correctly, and check the polarity of the electrolytics. The crystal, X1, is very fragile, so take extra care with it. The wiring of the three controls is shown in **Figure 2**.

Before putting the ICs in their sockets, connect up the battery and check the following voltages with the negative voltmeter lead connected to the negative terminal of the battery:

Pin 8	IC1	5 V
Pin 8	IC2	5 V
Pin 8	IC4	9 V
Pin 1	IC5	9 V

When all these have been found to be correct, switch off and put the ICs carefully into their sockets. Use wire of different-coloured insulation to wire up the front-panel controls.

The case can be a small plastic box of size 22 cm by 15 cm by 8 cm, with three 10.5 mm holes drilled in the front and two 8 mm holes in the side for the aerial and earth connections. On one side are a 6 mm hole for the speaker socket and an 11 mm hole for the optional external power supply.



Figure 2 Rear view of the variable resistors. Check the connections carefully to make sure the wires are fitted correctly

Testing and tuning

The aerial for the receiver should be between 30 and 70 feet of wire, mounted as high as you can make it, away from trees and buildings if possible. Connect the battery and switch on. Adjust L1 and L2 for the best results. Tune slowly with VR3; you should find CW stations at the lower end of the band (anticlockwise) and SSB stations at the upper end (clockwise). You may find that it is easiest to make these adjustments *before* mounting the board in the case with double-sided sticky tape or pads. If you are planning to use an external DC supply, make sure it is a safety approved stabilised 9 V type, and **disconnect the battery before you use such a supply!**

If you suspect that the tuning doesn't quite cover the lower CW end of the band, try increasing C9 to 1200 pF. If it is the upper SSB end which is missing, decrease C9 to 820 pF.

It is always advisable to use an aerial tuning unit (ATU) between your aerial and the receiver. A suitable design of ATU is included as a project in this book.

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1, R4	100 kilohms (kΩ)
R2, R3	1.5 kilohms (kΩ)
R5	220 ohms (Ω)
R6, R7	12 kilohms (kΩ)
R8	10 kilohms (kΩ)
VR1	4.7 kilohms (kΩ) linear, with SPST switch
VR2	4.7 kilohms (kΩ) linear
VR3	47 kilohms (kΩ) linear

Capacitors: all rated 16 V or more

C1	470 picofarads (pF) polystyrene 5%
C2	47 microfarads (μF) electrolytic
C3	47 picofarads (pF) polystyrene 5%
C4, C5	100 picofarads (pF) polystyrene 5%
C6, C7	100 nanofarads (nF) ceramic
C8	2.2 nanofarads (nF) polystyrene 5%
C9, C10	1 nanofarad (nF) polystyrene 5%
C11, C14	10 nanofarads (nF) ceramic
C12	470 microfarads (μF) electrolytic
C13	47 nanofarads (nF) ceramic
C15	1000 microfarads (μF) electrolytic
C16	1 microfarad (μF) electrolytic

Inductors	
L1	Toko KANK3335R
L2	Toko KANK3333R
L3	10 μH 5%, e.g. Toko 283AS–100
Semiconductors	
IC1, IC2	NE602 or NE602A
IC3	78L05 5 V, 100 mA
IC4	TL072
IC5	TDA7052
Additional items	
D1	Toko KV1236 cut into two sections (one half used)
X1	4.608 MHz (available from Cirkit)
	3 × silver knobs, one with pointer
	Plastic case approx. 22 × 15 × 8 cm
	Speaker 8–32 Ω, or headphones
	4 × 8-pin DIL sockets for IC1, IC2, IC4, IC5
	2 × 4 mm sockets (red and black) for aerial and earth
	3.5 mm chassis-mounting jack socket for speaker
	DC power socket for external supply (if required)
	Prototype board

Kits

A complete kit is available from JAB Electronic Components.



39 Diodes for protection

Introduction

Many semiconductor devices can be destroyed in an instant if their supply is reversed. With the use of batteries as power sources, it is quite common for the battery to be connected ‘the wrong way round’, and the scope for damaging equipment is significant and very real. Diodes can protect equipment in several ways, and you may do worse than to consider one of these approaches to protect your next expensive project.

Choose wisely!

All the diode circuits given here are so simple as to invite calamity. The circuits are not foolproof but, with a little care, will work first time. Remember that a semiconductor diode has a forward voltage drop of between 0.5 V and 0.7 V, depending on its type and the current flowing. This will be mentioned later.

The first thing you need to do is to insert a good multimeter *in series* with the circuit you want to protect; set the range to Amps DC, and switch on. Check that the circuit works properly. Then, decrease the current range on the meter until a good reading is indicated. Make a note of this current, as it is the normal running current of your circuit.

To choose a diode, you must consult the catalogues or data sheets and find one where the quoted *maximum forward current* exceeds the current you have measured; preferably it should be at least twice your measured current. Secondly, the diode will have a *peak inverse voltage* (PIV); this is the maximum voltage it can withstand when the cathode is made positive with respect to the anode, i.e when it is *reverse-biased* and not conducting. This voltage must be greater than your battery voltage, again by a factor of about 2. Except in the case of the bridge rectifier (see later), these criteria will enable the selection of a suitable diode to be made easily.

The series diode

The simplest and most obvious way to protect equipment is to insert a diode in the positive supply lead, as shown in **Figure 1**, with the diode passing current *only* when the supply is of the correct polarity. Because of the 0.6 V that exists across the diode, your equipment will normally operate on a



Figure 1 Series diode protection

slightly lower voltage. If you imagine reversing the supply to this circuit, you will see that the negative terminal of the battery is connected to the anode of the diode; the diode becomes reverse-biased and will not conduct any current, thus protecting the load. Your equipment will not operate when the battery connections are reversed.

The parallel diode

The circuit of **Figure 2** overcomes this voltage drop. It places the diode in parallel with the load (your equipment) but in a normally reverse-biased condition so that it draws no current when the battery is correctly connected. Reverse the battery connections, however, and a very large current will flow through the diode, thus blowing the fuse! For this technique to work successfully, the current drawn by the diode when the battery connections are reversed *must* be much greater than the maximum current drawn by the equipment, in order to blow the fuse. This is usually not a problem, however.



Figure 2 Parallel diode and fuse

The diode bridge

For sheer elegance, the circuit of **Figure 3** takes the biscuit! It uses four diodes connected in the form known as a *bridge rectifier*. Such rectifiers exist, and do not have to be made up from four discrete diodes.



Figure 3 The diode bridge

Follow the current round the circuit from the supply, assuming initially that the top wire is positive and the bottom wire negative. It flows from the positive supply

(a) through D2
(b) through the load (top to bottom)
(c) through D4

and back to the negative of the supply.

Now assume that the bottom supply lead is positive and the top lead negative. The current flows from the positive supply

(a) through D3
(b) through the load (top to bottom)
(c) through D1

and back to the negative of the supply.

So, whichever way round the battery is connected, the current will *always* flow the same way through your equipment!

The circuit does have a drawback, however. Whichever way round the battery is connected, there are always **two** diodes conducting the current at any time. In the first case it is D2 and D4; in the second case, D1 and D3. This means that there is a total voltage drop of about 1.2 V. If your equipment can tolerate that reduction in voltage, then you will not have a problem.

Decoupling

Whenever the supply rail to a piece of equipment, or even to an individual stage of a circuit, is broken for the insertion of a device that will drop voltage, strange things can happen. This is because the supply for any circuit is assumed to have a low resistance to DC and a low *impedance* to AC. (Impedance is the AC equivalent of DC resistance.) These two are not the same, and the insertion of a diode or diodes is certain to make a big difference to them both. To overcome any irregularities in the operation of the circuit you are protecting in any of the ways described previously, the protected supply needs to be *decoupled* with a capacitor.

If the circuit handles audio frequencies only, placing an electrolytic capacitor directly across the load in all three circuits should solve the problem. The parallel circuit of Figure 2 is less at risk than the other circuits. The size of the capacitor will be determined by the current taken by the circuit, and may need to be chosen within the range 100 μF to 10 000 μF, with a working voltage greater than the supply voltage.

If the circuit is mainly handling RF currents, placing a capacitor of 0.01μF across the load should prevent any problems. A second capacitor, also across the load, of between 10 μF and 100 μF may be needed. Again, the parallel circuit of Figure 2 is less at risk than the other two.

Don't be afraid to experiment, but confine your experimenting (at first) to small equipment and low currents, until you get a 'feel' for the technique.

40 An RF signal probe

Introduction

A radio-frequency (RF) diode probe is a simple device which, when used with a conventional multimeter, enables the measurement of RF voltages in a circuit. When constructed, this will be one of the most useful pieces of test equipment for the experimenter who revels in the construction of transmitters and receivers.

The circuit

Figure 1 shows the simple circuit diagram. It is *almost* the same as a common diode rectifier circuit, but with a simple change to make it more sensitive. The circuit is known as a *voltage-doubler*, and is often found in high-voltage supplies, with beefier capacitors and diodes, of course! Because we are dealing with high frequencies and smaller voltages, the diodes and capacitors can be physically very small. The diode circuit of D1 and D2 *rectifies* or *detects* the RF from the probe, and any remaining AC is removed (short-circuited to ground) by C2. This produces, at the output, a constant voltage proportional to the peak-to-peak RF voltage present at the input; the output voltage is fed to an ordinary multimeter (on a voltage range).


C1
10n
Probe
(Stiff wire)
D2
+
To multimeter
D1
C2
10n
Screen
Ground
lead
−
D1 and D2 are germanium diodes
C1 and C2 are 10nF ceramic capacitors
(Crocodile clip)
© RSGB

Figure 1 The diode probe can be made from four electronic components

Construction

Although the circuit layout is not critical, a description of the prototype is given here for your information. **Figure 2** has the details. The components are soldered to square pieces of copper-clad printed-circuit board (PCB) glued to a larger piece of PCB. The larger piece serves as a ground connection. Use a stiff copper wire as the probe, and an insulated flexible wire with a crocodile clip to connect the probe to the ground of the circuit under test.

Cut a piece of plain PCB, 30 mm by 45 mm and another of 15 mm by 45 mm. Cut the smaller piece into three measuring about 15 mm square. Stick the three small pieces to the larger piece, ensuring that there are small gaps between each, as Figure 2 shows. Solder the components in place. The connection to the multimeter should be thin coaxial cable or screened microphone cable. If you use unscreened cable, there may be RF pickup here which can lead to false readings.

Simple to use

Using the probe is simple. Connect it to the multimeter and set the meter to around 10 V DC – you may need to reduce this, depending upon the magnitude of the RF voltage you are trying to measure. Hold the probe by


To wire
probe
To
multimeter
D2
C1
D1
C2
Screen
Ground
lead
© RSGB

Figure 2 The components are mounted on a copper-clad PCB

its base, being careful *not* to touch any of the components. Connect the croc clip to a ground point on the circuit and touch the probe on the circuit point to be tested. If an RF signal is present, there should be a reading on the multimeter. That's all there is to it!

Parts list

Capacitors

C1, C2	10 nanofarads (nF), or 0.01 microfarad (μF) ceramic

Semiconductors

D1, D2	Any *germanium* signal diode, e.g. OA91 or AA119

Additional items
- Stiff copper wire
- Insulated flexible wire
- Copper-clad PCB
- Crocodile clip
- Coaxial or screened cable

Source

All components are available from Maplin.

41 An RF changeover circuit

Introduction

The simplest entry route to operating an HF station is to buy or build a receiver, and to add a simple CW (Morse) transmitter. In theory, this sounds so simple, yet in practice there is one significant hurdle to be overcome. How can they both share the same aerial? A manually operated changeover switch is the obvious solution, but it takes time to perform the switching operation, by which time someone else has squeezed in before you and contacted the DX station! This small circuit accomplishes the changeover automatically, as soon as the transmitter is keyed.

How it's done

The circuit is shown in **Figure 1**, and uses the signal from the transmitter to operate a relay. A relay is a switch which is operated electrically in the following way. A coil of wire with an iron core is used as an electromagnet. When current flows through the coil, it produces a magnetic field which, in turn, is used to pull a set of switch contacts. These contacts will be used to switch the aerial from transmitter to receiver and vice versa. The relay used here has a double-pole changeover (or DPDT, or DPCO) switch. If you are confused by the different types of switch, look at the basic descriptions elsewhere in this book. The *pole* of a switch is the part that doesn't move; in Figure 1, one pole is connected to L1 and the other to the aerial output. In a circuit diagram, the switch contacts are always shown in their *normal* state, i.e. when *no* current flows in the relay coil. The changeover switch is normally in the receive position, so we say the receive switch is *normally closed*, and the transmit switch is *normally open*. We choose to have the circuit in the receive position normally, because everyone spends a lot more time receiving than transmitting. The relay is energised only when you are transmitting.

There are three RF sockets – one for the transmitter, one for the aerial, and one for the receiver. When the transmitter is not in use, there is a direct connection (via the Rx normally closed contacts of the relay) between the aerial and the receiver. The transmitter (which is not keyed at this time) is connected to a 50 ohm dummy load, R1.

When the transmitter is activated by pressing the Morse key, an RF signal appears at the transmitter socket. The wire carrying the signal to the relay



Figure 1 RF activated relay

Tx contacts passes through a toroid (a ferrite coil former, looking like a black Polo mint), which has a five-turn coil wrapped around it. This five-turn coil picks up the signal, which is then detected by D1 and D2, and converted to a steady voltage. C1 removes any remaining RF and C2 provides *hang*. Without it, the circuit would detect the gaps between every dot and dash being sent, and switch the aerial over very rapidly and very frequently! This is *not* what we want. We need the relay to remain in the transmit condition at normal Morse keying speeds, and then return to receive when the sending is complete. The combination of C2 and R3 achieves this.

The voltage appearing across C2 is fed to a VMOS field-effect transistor (FET), TR1, which acts as an electronic switch. When a voltage appears across C2, the FET switches on and passes a current through the relay coil, changing the contacts from receive to transmit. The diode, D3, across the relay winding protects the FET from being damaged by the large reverse-voltage spike which occurs across the coil when the FET switches off.

Construction

This is very simple – a circuit board is not required. The prototype was built into an old 50 g tobacco tin. All ground leads are soldered directly to the tin, thus supporting the components automatically. Phono sockets were used for the aerial, receiver and transmitter; you could use whatever connectors matched the rest of your station. The 12 V supply is fed through the tin using a 1000 pF feed-through capacitor, C3.

The 'dummy load', R1, must be able to withstand the RF output power of the transmitter. For novice use, 4 watts is adequate. Two suggestions for making up R2 from standard resistors are shown in **Figure 2**. Six 330 ohm, 1 watt resistors in parallel have a combined resistance of 330/6 = 55 Ω at 6 W. Two 100 ohm, 2 watt resistors in parallel have a combined resistance of 100/2 = 50 Ω at 4 W.



Figure 2 Component details

Make sure all the contacts to the relay are correct; also ensure that TR1, C2, D1, D2 and D3 are correctly wired.

Winding the toroid, L1, is very simple. It is made from PVC-insulated hook-up wire. Each time the wire passes through the centre of the toroid counts as one turn. The wire from the transmit socket to the relay simply passes through the centre! Use thin 50 Ω coax for the leads to the three sockets.

What happens to the receiver?

On transmit, the receiver is not connected to the aerial, but is only the separation of the switch contacts (about 0.5 mm!) away from the transmit lead. The receiver *will* pick up the transmitted signal, and there is a possibility that this signal will be enough to damage the receiver's sensitive input circuits. This can be prevented with the simple addition shown in **Figure 3**. Two diodes are connected back to back across the receiver socket. These act as a *limiter*, reducing the amount of signal that can enter the receiver. Solder these directly between the receiver socket and the tin.



Figure 3 Receiver input protection

Warning

The wiring **must** be thoroughly checked. If the relay switch connections are wrong, there is a **great probability** that the full RF power will be applied to your receiver! You can check these connections as follows. With the 12 V supply connected, check that the relay energises (clicking sound heard) when the FET drain (d) is shorted to earth. Check the aerial and receiver connections with an ohmmeter or continuity tester. Disconnect the 12 V supply, and check that there is continuity between the centre pins of the aerial and receiver sockets. Reconnect the 12 V supply, short the FET drain to earth again (this will not damage the FET) and check that there is continuity between the centre pins of the aerial and transmitter sockets. If these tests show correct operation, disconnect the drain shorting wire (*most* important!) and your aerial auto-changeover is ready for use! Avoid using the device without the lid fitted.

Parts list

Resistors: 0.25 watt, 5% tolerance, unless otherwise stated

R1	50 ohms (Ω) – see text and Figure 2
R2	1 kilohm (kΩ)
R3	10 kilohms (kΩ)
Capacitors	
C1	100 nanofarads (nF), 0.1 microfarad (μF)
C2	47 microfarads (μF) 15 V electrolytic
C3	1000 picofarads (pF) feedthrough
Semiconductors	
D1, D2, D4, D5	1N914
D3	1N4001
TR1	VN10KM
Additional items	
L1	T37–43 toroid
	Relay 12 V DPDT (DPCO) relay
	Three sockets to suit (phono, SO239, etc.)
	Thin coax cable and hook-up wire

42 A low-light indicator

Introduction

This is a simple one-evening project that can be built for the pure fun of it, or to use as the basis of a more complex project to switch your shack lights on when it gets dark! In its prototype form, it simply flashes an LED when the ambient light level drops to a preset point.

Operation

The heart of the circuit shown in **Figure 1** is a *photo-conductive cell*, also called a *light-dependent resistor* (LDR), a device whose resistance changes according to the amount of light falling on it. In bright light, the resistance is low (about 1 kΩ), whereas in the dark, its resistance is very high (up to 10 MΩ). The cell is made from a semiconducting material known as cadmium sulphide (CdS), and is enclosed in a small plastic container. The semiconductor is laid on a flat insulating surface in the form of a small flat ribbon. The ribbon construction gives a good area of surface for a given


VR1
22k
pre-set
R1
220R
+
LED1
-
9V
PP3
battery
+
-Ve
R2
1k
B
C
E
TR1
2N3053
LDR
ORP12

Figure 1 Circuit diagram

©RSGB DY107

length of ribbon, and the length of the ribbon is maximised by laying it out in a zig-zag pattern, as can be seen diagrammatically in **Figure 2**. In the dark, CdS is an insulator; when light falls on it, electrons are released inside the CdS, making it conduct. The more light there is, the more electrons there are, and the resistance falls.

In this circuit, the LDR is connected across the 9 V supply in series with a variable resistor, VR1. In this arrangement, the voltage that exists across the LDR will be determined by the light level. As the light intensity increases, the resistance of the LDR falls, dropping a smaller voltage across it. The


LED
c
b
e
TR1 base
Flat
-
+
- to TR1 collector
+ to R1
Battery +
VR1
R1
+
LED
-
LDR
R2
c
TR1
b
e
Battery -

Figure 2 Component layout on tagstrip

©RSGB DY108

reverse happens when the light intensity falls – the voltage across the LDR increases. This voltage is used to drive an npn transistor, TR1, connected as an electronic switch. As the voltage on the base (B) rises, it will reach a point where TR1 will suddenly start to pass current, just as an ordinary switch does when pressed. The current flowing through TR1 also flows through a flashing light-emitting diode (LED), D1 and its series resistor, R1. D1 can be a steadily glowing type, if preferred. If you want to make the circuit switch the LED on at a different ambient light level, adjust VR1.

Construction

The prototype was made on an eight-tag tagboard (Figure 2). The resistors R1 and R2 can be laid on the tagboard for soldering, the rest of the components lying above or to the side of the board. Check the circuit after you have soldered everything on, then connect the battery. The LED should flash if you put your hand over the LDR, and VR1 can be adjusted to vary the point at which the LED lights. The project can be housed in a small plastic box with holes provided for the LDR and LED and an on/off switch if you want one.

Parts list

Resistors: all 0.25 ohm, 5% tolerance

R1	220 ohms (Ω)
R2	1 kilohm (kΩ)
VR1	22 kilohms (kΩ) linear pre-set

Semiconductors

LDR	ORP12
TR1	2N3053 npn
LED1	Flashing LED

Additional items

- Plastic box
- Tagboard with 8 tags
- PP3 battery connector

43 A J-pole aerial for 50 MHz

Introduction

For FM communication (i.e. voice and data) on the VHF bands, a vertical aerial is used to give all-round (non-directional) coverage. This is a half-wave aerial which can be fed at the end, thus removing the principal problem with the conventional vertical centre-fed half-wave dipole, which is that the feeder should leave the dipole at right angles. This is no problem when the dipole is horizontal, but can be difficult for the vertical dipole.

Basic facts

A feeder must be connected to an aerial at a point where the *impedance* (AC 'resistance') of the aerial closely matches that of the feeder. The difference between the two impedances gives rise to the voltage standing-wave ratio (VSWR), which is unity only when the two impedances are the same. With 50 Ω feeders, the feed point of a half-wave aerial is at the centre, where the aerial impedance is around the same value. At the end of a half-wave aerial, the impedance is high, so it is *not* a suitable point to connect a 50 Ω feeder.

Connection at this point can be effected using an RF transformer. RF transformers act in the same way as ordinary transformers, except that they are much smaller, and usually comprise wires of particular lengths adjacent to each other. **Figure 1** is a good starting point. It shows the aerial in its diagrammatic form. Notice that the aerial is in the form of an elongated letter 'J'; this shape gives rise to its nickname – the *J-pole*. The quarter-wave RF transformer is the lower 'U' section below the half-wave element. At the bottom of the U section, the impedance is zero (this may become clearer later) and at the top of the U section it is high, thus matching the aerial impedance. The coaxial feeder cable is connected part-way up the U section, where the impedance is around 50 Ω.

The practicalities

Figure 2 shows the aerial as constructed. As it is about 4.5 metres high, it may be too high for the average house loft, but is ideal for mounting outside, supported by a non-metallic pole or hung from a tree branch. The upper half-wave section is made from 1.5 mm insulated copper wire, as used in domestic mains wiring. The quarter-wave transformer below the half-wave section is made from 300 Ω balanced line ('ribbon cable'). The



Figure 1 Overall dimensions of the 6 metre J-antenna

wires at the bottom of the transformer section are stripped of their insulation, twisted and soldered. At the upper end, only one wire of the balanced line is soldered to the bottom of the half-wave section. The other wire of the pair is not connected and is left insulated.

At the feed point of the transformer, the insulation needs to be carefully stripped from the balanced line. You will need a standing-wave meter (VSWR meter) in the coaxial line between your transmitter and the aerial, and you will need to adjust the position of the feed point. 45 cm from the bottom was the best point on the prototype, but this position is dependent upon the immediate surroundings of the aerial, and *must* be done when the aerial is in its final operating position. **Warning: *Never* make adjustments to the feed point when the transmitter is on. Make a VSWR measurement, switch off, move the feed point, switch on again, make another measurement, and so on.** You will need to aim for the lowest VSWR you can – certainly better than 2:1. Having found the best position, wrap all the exposed wires with self-amalgamating tape, to seal them against the ingress of moisture.


©RSGB DY111
Nylon cord to support antenna
1·5mm diameter insulated wire antenna element
Soldered connection
Coaxial cable connected to ribbon cable (see text)
300 ohm ribbon cable matching section
Coaxial cable to transceiver
Coaxial connector
End of ribbon cable insulation removed and wires joined and soldered

Figure 2 Construction details

How it performs

Figure 3 shows a computer prediction of how the J-pole radiates. It is called a *polar diagram*, and shows the distribution of your transmitted power when viewed 'from the end of your garden'. Most of your signal is sent at a fairly small angle to the horizontal; very little signal goes upwards, which is a good thing, of course. This also shows why the J-pole (or any other vertical aerial) should not be called 'omnidirectional', which means it radiates in all directions. It is omnidirectional *only* in the horizontal plane.



Figure 3 This polar diagram computed for the J-pole

©RSGB X210

Safety

Where you mount your aerial is a matter of personal preference and the restrictions of height and space, but the following safety rules *must* be applied.

1. Never fix an aerial where it may come into contact with power lines or telephone lines.
2. When climbing a ladder to put up an aerial outside, make sure the ladder is safe and that it is secured.
3. Don't do this alone. Preferably have someone with you. If this is not possible, make sure someone knows where you are.

Parts list

3.00 metres	1.5 mm insulated copper wire
1.50 metres	300 ohm balanced line
As required	50 ohm coaxial cable
As required	Self-amalgamating tape

44 Measuring light intensity – the photometer

Introduction

Before the days of automatic 'point-and-shoot' cameras, a photographer would use a light meter or *photometer* to measure the light level, then manually convert this reading into shutter speed and lens aperture settings to ensure a correctly exposed negative. Modern cameras have quite sophisticated photometers, which control the shutter speed and iris settings automatically.

A short explanation

A simple photometer circuit is shown in **Figure 1**, and is based on a device called a *light-dependent resistor*, or LDR. As its name tells us, its resistance depends upon the amount of light falling on it. In bright light, the resistance is relatively low (about 1 kΩ), whereas in the dark, its resistance is very high (up to 10 MΩ). The cell is made from a semiconducting substance known as cadmium sulphide (CdS), and is enclosed in a small plastic container. The semiconductor is laid on a flat insulating surface in the form of a small flat ribbon. The ribbon construction gives a good area of surface for a given length of ribbon, and the length of the ribbon is maximised by laying it out in a zig-zag pattern. In the dark, CdS is an insulator; when light falls on it, electrons are released inside the CdS, making it conduct. The more light there is, the more electrons there are, and the resistance falls.



Figure 1 Circuit diagram of photometer

The photometer circuit

The circuit is simply a series connection of four things – the battery, the LDR, a variable resistor and a meter. A switch is also provided. The combination of the LDR resistance and that of VR1 determines the current flowing, which is indicated on the meter. Altering the resistance of VR1 sets the *sensitivity* of the photometer – you may want full-scale deflection of the meter needle for a bright light, or for a dim light.

It is simple to make, and a plug-in type matrix board is ideal to test the circuit, so that you can decide if you want to make a permanent version. Connect all the components in series; the only change you may want to make is the connection to VR1. If you find that the sensitivity control seems to work 'backwards', simply unsolder the wire from the end tag of VR1 and solder it to the opposite end tag. Problem solved!

In use

As soon as you connect up the battery, you will probably have a meter reading because of the daylight falling on the LDR. Shading it with your hand should reduce the reading. If the meter needle is hard over against the end-stop, turn VR1 until it indicates about half-scale. The LDR is very sensitive, and will read zero only in a dark room. If you put on a torch to see what the meter reading is, the LDR will detect the torch light, and will give a reading!

Here is a simple project where you can use the photometer in an experiment which has an analogy in radio. Draw a circle on a large (A3 or bigger) sheet of paper and divide it up into 30-degree sectors, as shown in **Figure 2**. Draw a series of smaller circles which divide the maximum radius into five. Look at the figure if you're not sure about this. Bring the LDR away from the circuit by using two long, flexible wires. The experiment must be performed in a darkened room (preferably in total darkness). Prepare a table with two columns, the left-hand one headed 'Angle (degrees)' and the right-hand one 'Meter reading'. Fill in the left-hand column 0, 30, 60 . . . and so on up to 360°.

Place the torch in the position shown, with its lens at the centre of the circle and pointing along the 0° line; switch it on. Place the LDR facing the torch and adjust VR1 until you have full-scale deflection of the meter needle. Suppose the meter indicates 10 units at this point. Enter this into your table in the 0° row. Keeping the torch the same distance from the circle centre, and pointing at it, move the LDR round all 30° positions and record the meter readings. Switch off the torch and take the sheet of paper and your tabulated results into daylight!

Lay the large sheet of paper on a table with your results beside it; then, at each 30° interval, plot the point along the radius corresponding to the meter



Figure 2 Torch light intensity pattern plotted at RSGB HQ

reading. Then, join up all the points and you have what is called a *polar diagram* of light intensity. The use of the word 'polar' implies that the readings have been taken in a circle and plotted that way.

Light waves and radio waves are both examples of *electromagnetic radiation*. The torch is designed to 'beam' its radiation in a particular direction, just like an aerial does. Hence the use of the word 'beam' for a directional aerial. If a similar polar diagram is drawn for a Yagi-type aerial, it will show the same general characteristics as does Figure 2, namely a main direction (or 'lobe') where most of the energy is concentrated, with evidence of *sidelobes*, indicated by 'lumps' on the otherwise smooth main lobe.

Also in this book you will find a project for the construction of a UHF field-strength meter, which you could use to carry out a measurement of the polar diagram of a UHF aerial.

Parts list

Resistor

VR1	50 kilohms (kΩ) linear

Semiconductor

LDR1	ORP12

Additional items
Meter, 50 or 100 μA
Battery clip for single AA cell
AA cell

45 A 70 cm Quad loop aerial

Introduction

This is a description of how to make an aerial for the 70 cm band which has gain compared with the 'rubber duck' or the dipole aerial. It can easily be dismantled and reassembled, making it ideal for contest use.

The principles

Most aerials which comprise several similar *elements* arranged along a *boom* are variations of the design originated by Yagi and Uda, and which takes the name (for historical reasons) of the former, and is know as the Yagi array. Let us suppose we have a Yagi aerial beaming left to right in front of us. The elements get progressively shorter from the left (look at almost any TV aerial to see this). All the elements on a Yagi aerial are classified as follows:

- The *reflector* – the leftmost element as we look at the array. It is the longest. Next to it is:
- The *driven element* – this is the element connected to the feeder, which in turn runs down to the transceiver. It is slightly shorter than the reflector.
- All the elements beyond the driven element are called *parasitic elements*, or *directors*. They are shorter than the driven element and usually get progressively shorter as we progress to the right along the boom. The directors are mainly responsible for the *directivity* (or *beamwidth*) of the array.

The progression from a simple dipole (a driven element in isolation) to a Yagi array is simple, but is nevertheless important. To make an aerial of two elements, a reflector (*not* a director) is added to the driven element. For three or more elements, directors are added to the two-element design. Adding more and more directors soon becomes impractical, the reduction in beamwidth (such as it is) does not warrant the extra expense, weight and wind resistance that is incurred.

Instead of using linear (straight) elements, as in the generic Yagi, this design uses loops. Designs using squares of wire instead of loops are known as *Quad* aerials, and HF designs require large X-shape frames to support the large squares of wire. At 70 cm, however, the use of wire loops is easier, and they are self-supporting.

Construction

This is quite simple. Any type of material (metal, plastic, wood) can be used for the *boom* (the support for the elements) and for the mast. The elements are made from 14 SWG enamelled copper wire. 16 SWG hard-drawn aerial wire, which is not enamelled, has also been used with success. Thinner wire might result in a rather ‘floppy’ aerial! The separate parts of the aerial are held together with *jubilee clips* (hose clips).

The driven element is secured to the boom with a jubilee clip and a three-connector plastic connector block as shown in detail in **Figure 1**, and in the photograph. Cut the wire for the driven element 70 mm longer than the 700 mm indicated in Figure 1. Then, using sandpaper, remove the enamel from one end to a distance of 20 mm, and from the other to a distance of 50 mm. After forming the loop of the driven element, bend both stripped ends through 90°, and insert them into the first to holes of the plastic connector block (Figure 1). Do not tighten the screws yet. Push both ends into the block as far as they will go, then bend the 50 mm end back on itself and pull the ends back through the connector block so that the end you have just bent goes into the third hole in the block. Now tighten the screws in the block and in the jubilee clip.

Each director and the reflector should be made 40 mm longer than the circumferences shown in Figure 1. Strip the enamel, as before, from the last 20 mm at each end. Form the wire into the loop, slip the ends under the jubilee clip (Figure 1) and tighten it. You may find that it helps to solder the stripped ends together before securing the jubilee clip.

The boom is fixed to the mast using jubilee clips and wire, as shown in Figure 1. Solder the feeder cable to the driven element, with the braid soldered to the end of the driven element which is connected to the boom (this applies to metal booms; with plastic or wooden designs, the feeder connections are not critical).


©RSGB DY112
170 mm
180 mm
180 mm
Reflector
Driven element
Director 1
Director 2
Wire dimensions refer to the circumference of the elements
780mm
700mm
640mm
632mm
Jubilee clip
Connector block
Boom
Wire element
Coax
Element to boom detail
Stiff copper or steel wire (one each side of boom)
Jubilee clips
Boom
Mast
Boom to mast connector detail
Jubilee clip
Wire element
Boom
Element to boom join detail

Figure 1 70 cm 4 element quad construction, with detail of how hose clamps are used in the construction

You will need a plug on the shack end of your feeder to suit the transceiver, aerial tuning unit (ATU) or the standing-wave meter (SWM) you are using. Always connect these in the order: transceiver – SWM – ATU – aerial.

Testing

Always test aerials outside and away from buildings (if possible!). This avoids getting misleading results.

Use a rubber duck, or whatever aerial you usually use, and tune around to find a repeater or beacon signal which is consistent. Note the reading on the S-meter. Then, connect your new Quad loop. Rotate it to give the strongest S-meter reading (don't forget it is directional). Verify that the meter reading varies as you rotate it. How does the S-meter reading compare with the original reading? Much depends on the siting of your original aerial; if you are comparing your Quad loop at ground level with a vertical on the chimney, you wouldn't expect your new aerial, even with its gain, to outperform a vertical which is well elevated!

Now a test on transmit is called for. The use of an SWR meter is essential here. Find a clear frequency and check that it *really is clear* before announcing your presence and carrying out the test. A reading of 1:1 is excellent, but any value less than about 1.8:1 would be acceptable. You can measure the directivity of your aerial using the field strength meter, also described in this series.

Materials

4 metres of 14 SWG enamelled copper wire
Material for boom and mast
15 amp connector block
7 Jubilee clips

The enamelled copper wire is available from AA&A Ltd, Sycamore House, Northwood, Wem, Shropshire SY4 5NN. Everything else is available from most hardware stores.



46 A UHF field strength meter

Introduction

It is always interesting, and often useful, to know just *where* the radiation is going from your aerial. How much of your radiated energy is going in the general direction of the station you are in contact with, and how much is being effectively wasted? Some of these questions can be answered with the use of a *field strength meter.* A field strength meter is simply a receiver, stripped down to its bare essentials, such that it responds only to the magnitude of the carrier. The use of a field strength meter assumes that the aerial under test is radiating a continuous carrier. Don't forget to find a clear frequency and identify your transmissions at least every quarter-hour, in order to comply with the terms of your licence.

Description

Two types of field strength meter are shown in **Figure 1**. You will recognise both circuits (Figure 1b particularly) as being types of 'crystal set' with a meter replacing the headphones. Figure 1a is a broad-band HF design (there is no tuning provision) and Figure 1b is tuned in the same way as the crystal set; with a loop of wire as an aerial, it will perform well in the VHF/UHF range.



Figure 1 Construction of the UHF field strength meter

A tuned field strength meter also doubles as an *absorption wavemeter* if it is well calibrated. Such devices are useful for detecting transmitter harmonics also. This design is intended for use in the UHF band, so it will have to be sensitive around 432 MHz.

Construction

The field strength meter comprises a loop of wire, 600 mm long, which acts both as aerial and as the tuning inductance, a diode, a capacitor, a connector block, a meter and a length of twin wire. All the components, with the exception of the meter, are fixed to a pole with a jubilee clip, as shown in **Figure 2**. The meter should have a sensitivity of between 50 μA and 100 μA, or a multimeter can be used. The multimeter is more flexible, as you can select different current ranges, giving you a range of sensitivities.

Using the field strength meter

Connect your meter to the ends of the twin wire from the pole. Place a hand-held transceiver about 2 metres away, and press Transmit. If there is no meter reading switch off the transmitter and check the wiring. If the needle attempts to go negative, simply reverse the wires to the meter. If the reading is too high, either move the transmitter further away, or increase the current range on the multimeter. Try changing the orientation of the transmitter aerial, and note how the signal varies.


Wire loop
(600mm long,
not critical)
100p
capacitor
Connector
block
Hose clip
Diode
OA79 or
OA91
Pole
Wires to
meter
©RSGB DY119

Figure 2 Assembly of the field strength meter

To measure the *polar diagram* (a graph of the signal strength against the angle between the aerial boom and the field strength meter, plotted on polar axes) of a beam aerial, mount the loop as far away from the aerial as you can, preferably at the same height, and rotate the aerial, say 15 degrees at a time, and record the signal strength, until the aerial has been turned through 360 degrees. If you need help plotting the graph, enlist the help of a friend who has done it before, or one who knows about polar graphs! If you have already built the Photometer project, you will have measured and plotted the polar diagram of the light intensity from a torch. Now you will see the great similarity!

Parts list

Capacitor	100 picofarads (pF)
Diode	Germanium, OA79 or OA91
Connector block	10 A, 3-way
Wire	600 mm of 16 SWG enamelled copper
	Length of twin cable for meter connection
Clip	Jubilee (hose) clip

47 Christmas tree LEDs

Introduction

A novelty ideal for the festive season, this circuit causes one LED at a time to light up around a small cardboard Christmas tree.

Warning

This circuit uses members of the integrated circuit family known as CMOS (complementary metal-oxide semiconductor). These use very little current and can be completed destroyed if they come into contact with the magnitudes of static electricity that most of us carry about when we walk on carpets and wear rubber shoes. You will never know if this wanton destruction has happened – all you will discover is that your circuit doesn't work and that you have tested *everything*. To avoid this problem do the following things:

1. **Before you open the little packet in which each IC is supplied, touch something which you *know* to be earthed – the metalwork of any equipment which is mains-earthed, for example. Then open the packet.**
2. **Let the IC fall gently on the bench – don't pick it out with your fingers. Touch your earthed metalwork again. Pick up the IC and insert it gently into its holder.**
3. **Repeat the process with the second IC.**

The circuit is safe from destruction while it is connected to the battery. However, when the battery is removed, the same care should be exercised with its handling, because there are no supply decoupling capacitors across each IC.

Description

Figure 1 shows the layout, and how the wires are connected from the circuit board to the LEDs around the tree. The circuit, shown in **Figure 2**, is quite complicated, so you need to be confident in your logical approach to circuit-building before you attempt this one! It uses two common integrated circuits (ICs). IC1 is simply an oscillator which provides timing pulses for IC2, which 'counts' up to a maximum of 10. The outputs of the counter are indicated by light-emitting diodes (LEDs); red, orange, yellow and green are common colours which you can use.

The circuit is built on a single piece of Veroboard measuring 29 holes by 12 strips. **Be aware that there is no strip labelled 'I', so don't make mistakes in your counting!**

First of all, cut the tracks in the positions shown in Figure 1 using a 3 mm ($\frac{1}{8}$ inch) twist drill rotated between thumb and forefinger. Then, solder in the IC sockets, the notches facing row M. Wire up and solder in the links and then the Veropins for the connections to the LEDs and battery. Having done this, the resistors and the capacitor should be fitted. When wiring the LEDs, each cathode (the lead adjacent to the 'flat' on the LED encapsulation) is connected to R4, and the anodes go to separate pins on IC2.

Testing

Hold up your circuit board to the light and check carefully for solder bridges between adjacent tracks. Then check again that the wiring is correct. Place the ICs in their holders, with the notched ends lining up with those on the holders. Connect the battery, and the LEDs should illuminate in sequence.

If you have no success, you are now wishing you had checked the circuit more carefully! Learn something from your mistake and it will not have


−ve
1
5
10
15
20
25
29
A
B
C
D
E
F
G
H
J
K
L
M
9V
PP3
battery
+ve
R3
R2
IC2
R1
C1
R4
IC1
Component side of board shown
= Pin
= Link
= Cut in copper track

©RSGB DY137

Figure 1 Christmas tree, component layout


C1
470n
Clock
+Ve
R1
680k
R2
10k
R3
10k
14 13 12 11 10 9 8
IC1
1 2 3 4 5 6 7
16 15 14 13 12 11 10 9
IC2
1 2 3 4 5 6 7 8
R4
470
Diodes on badge
D6 D2 D1 D3 D7 D4 D5

©RSGB DY138

Figure 2 Christmas tree, circuit diagram

been in vain! The first thing to check is that the LEDs are the correct way round. If that is OK, then check the positions where the tracks are broken (intentionally!). After that, are the wire links in the right places – had you forgotten there is no row ‘I’? Check *all* the wiring, then check *again* for solder bridges, and switch on again. One of these tests should have revealed a fault. If it *still* refuses to work, perhaps one (or both) of your ICs were damaged by static electricity, despite your precautions – or did you choose to ignore them?

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1	680 kilohms (kΩ)
R2, R3	10 kilohms (kΩ)
R4	470 ohms (Ω)

Capacitor

C1	0.47 microfarad (μF) min. metallised polyester film

Semiconductors

IC1	4011
IC2	4017

Additional Items

D1–D7	5 mm LEDs in choice of colours
	14-pin DIL socket for IC1
	16-pin DIL socket for IC2
	PP3 battery clip and battery
	Veroboard, Veropins
	Insulated wire for links

48 An audio signal injector

Introduction

An audio signal injector is a device used to test audio frequency circuits. It is simply an oscillator running at a frequency in the audio range, so that when its output is fed to the input of an amplifier, it will produce a sound in the loudspeaker if the amplifier is working. The oscillation is so rich in harmonics that the signal can also be heard (sounding rather different) when injected into an RF circuit.

The design

The circuit is shown in **Figure 1**, and is a basic *astable multivibrator*, a free-running oscillator producing a roughly rectangular-wave output. The two transistors, TR1 and TR2, operating as switches, switch on and off alternately at a frequency around 500 Hz. The prototype was constructed on plain matrix board (no copper strips), as illustrated in **Figure 2**.

Both transistors are type BC108, which are only a few pence each new, and can be found at almost any rally. You can add an on/off switch, or simply disconnect the battery when you are finished using it. To make the unit in one piece, the battery can be taped to the board, as the diagram shows.

The probe itself is made from a short piece of stiff insulated wire, soldered to a tag on the board; an earth lead is also soldered to the board, and terminated in a crocodile clip to attach to the ground lead of the equipment under test.



Figure 1 Circuit diagram of the signal injector


©RSGB DY131
+Ve red
10cm x 3cm perforated board
Solder tag and 6BA nut and bolt
Probe
Insulation
Tape
PP3 battery
R1
R2
R3
R4
C1
C2
C3
TR1
TR2
Crocodile clip
–Ve black
Wires under board

Figure 2 Component layout of the signal injector

Using it

After checking the wiring of the circuit, connect the battery. Find a transistor radio that is known to work. Carefully remove the case, switch on and apply the probe to the centre tag of the volume control. A *very* loud buzz should be heard from the speaker, indicating that the audio circuits of the radio are working. Using the injector to fault-find equipment you have made yourself is rather more instructive and rewarding, because you *know* where to inject the signal, and you should *know* what to expect when you do.

Warning

Do *not* work on any equipment connected to the AC mains. Work only on battery-powered circuits, for your own safety.

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1, R4	10 kilohms (kΩ)
R2, R3	330 kilohms (kΩ)

Capacitors

C1, C2, C3	10 nanofarads (nF) or 0.01 microfarad (μF) ceramic

Semiconductors

TR1, TR2	BC108

Additional items
- PP3 battery and connector
- Matrix board 10 cm by 3 cm
- 6BA solder tags
- Thick insulated wire for probe
- Crocodile clip

49 Standing waves

Introduction

Everyone has, or *should* have, a standing-wave ratio (SWR) meter as part of his/her array of test gear. Most people know how to use it, but what does it really do?

Before attempting to answer that question, we need to look at some aerial fundamentals. An aerial is a *transducer*, the word meaning 'to lead across'. We use it whenever one form of energy is converted into another form. A bulb is a transducer; it converts electrical energy in the filament to radiated heat and light energy. **Figure 1** shows the situation.

An aerial, or antenna, is also a transducer; it converts radio-frequency (RF) energy in the feeder (or *transmission line*, to give it its proper name) into radiated electromagnetic energy, in the manner shown in **Figure 2**. The aerial has resistance, just like the bulb filament, and if the filament had zero resistance, there would be no radiated energy. In the same way, if the aerial had no resistance, there would be no radiation from it.

Transmission lines should convey RF energy from transmitter to aerial with the minimum power loss. A common form of transmission line is the *coaxial*



Figure 1 The light bulb converts electrical energy to electromagnetic light energy



Figure 2 The antenna converts RF current to electromagnetic radio waves

cable. As you might expect, any feeder cable has a DC resistance caused by the resistance of the copper wire from which it is made. It also has an AC resistance, caused by the capacitance between the centre conductor and the braid, and by the inductance of the cable itself. This means that the feeder has an *impedance*, which is constant for the particular type of cable. This is what we call the *characteristic impedance* and, for the cables used in most amateur radio applications, it is 50 Ω.

If this impedance can be made the same as that of the aerial (it is already the same as the impedance of the transmitter output), then the transfer of energy will occur with minimum loss. If the aerial and cable impedances are *not* the same, then there is a *mismatch*, which causes some of the RF energy to be reflected back towards the transmitter. We now have a situation where RF energy is flowing along the cable from the transmitter to the aerial (the *forward* wave) and, at the same time, flowing from the aerial to the transmitter (the *reflected* wave). The two waves interact along the cable and form a stationary pattern of voltage and current. The pattern is known as a *standing wave*, and can be visualised from the waveforms in **Figure 3**. The ratio of the maximum voltage to the minimum voltage on a given wave defines the *voltage standing-wave ratio* (VSWR), or just *standing-wave ratio* (SWR) for short.

The SWR meter is easy to use. It is positioned in the feeder between the transmitter and the aerial tuning unit (ATU) if there is one, or between the transmitter at the aerial otherwise. Most meters have a single meter and a four-position switch. The transmitter is first keyed and, with the switch in



Figure 3 Standing waves on a transmission line

the 'calibrate' position, the sensitivity control is adjusted to give full-scale deflection on the meter. The switch is then changed to 'forward' to read the forward power, to 'reflected' to read the reflected power, and to 'SWR' to read the value of the standing-wave ratio. When there is no reflection (see Figure 3), the meter should read 1:1 or, simply, 1.

Most SWR meters remain in the feeder line while the transmitter is operating, so the condition of the aerial and feeder can be constantly monitored. Problems with the aerial (such as water entering the feeder at its junction with the driven element) are immediately shown up. Without the use of the SWR meter, the situation would slowly deteriorate over several months and you would be left wondering why so few stations were answering your calls!

50 A standing-wave indicator for HF

Introduction

The standing-wave ratio (SWR) meter shows how well the aerial system, including the feeder, is *matched* to the output of the transmitter. This design does not *measure* SWR, but it gives an indication of when the SWR is minimum for a given system of aerial and feeder. The design is usable on the HF bands from 1.8 to 28 MHz, and can be used at 50 MHz with reduced sensitivity.

How it works

There are two types of wave in any feeder: the *forward* wave, which travels from the transmitter to the aerial; the *reflected* wave, which travels back to the transmitter from the aerial. The presence of a reflected wave is evidence that some of your transmitted power is not being radiated, but is being returned to the transmitter to be lost as excess heat. When aerial and feeder are perfectly matched, there is *no* reflected wave, and all the power from the transmitter is radiated.

Referring to the circuit of **Figure 1**, a tiny fraction of the signal is removed by the transformer, T1, and by the capacitors, VC1 and C1. It is then detected by the germanium diodes, D1 and D2, and any residual RF removed by the capacitors, C2 and C3. The currents through the diode and meter (depending on the position of switch, S1) represent the forward and reflected signals. VR1 acts as a sensitivity control for the meter.

It pays to shop around for a suitable meter. Surplus types from tape recorders and hi-fi equipment are usually ideal for this purpose. A new one would cost several pounds. The more sensitive the meter, the more sensitive your indicator will be. Meter sensitivity is given by the current required to give full-scale deflection (FSD) of the pointer. One with an FSD of between 50 and 200 micro-amps (μA) is suitable for this circuit. The higher the FSD, the less sensitive the circuit.

Construction

The meter circuit and the sampling transformer (see **Figure 2**) are built and mounted on Veroboard of the copper-strip variety. It simplifies construction



Figure 1 Circuit diagram of the SWR meter



Figure 2 Component layout of the SWR meter

but reduces the operational range of the meter to below 30 MHz because of the capacitive coupling between strips. The board has 13 strips by 30 holes, although you can reduce this if you have a smaller case.

Firstly, cut the tracks at the three points shown. Then insert and solder Veropins for connections to the external components, the switch, variable resistor and the meter. Solder in the components starting with the resistors and followed by the capacitors and the diodes, ensuring that the diodes are inserted correctly.

Now you have to wind the transformer, T1, on a small toroidal ferrite core. Wind the secondary with 15 turns of 36 SWG enamelled copper wire, spaced evenly over about two-thirds of the former. The turns should not overlap, and considerable care must be taken; the wire is very thin, will kink easily and will break if you apply too much tension. The ‘primary’ is an 8 cm length of 50 Ω coaxial cable which passes through the toroid on its way between the input and output connectors. The braid of the cable is connected to the case at only *one* of the connectors (see Figure 1); this prevents the screen and the metal case between the two sockets forming a single, shorted turn.

The ends of the secondary winding must be carefully stripped of their enamel with sandpaper, before attaching the toroid to the board with cotton or nylon fishing line. On no account must wire be used for this!

Solder the secondary connections of T1 to the board and thread through the coaxial cable ready for soldering to the connectors.

The case used was an aluminium box (Maplin LF02C), but any suitable metal box could be used. Aluminium is preferable, as it is easily drilled with simple tools. Use standoff insulators to mount the board in the case. Once this has been done, the leads from the board to the chassis-mounted components can be soldered. So can the coaxial cable passing through the toroid. Make the lead from the input socket to VC1 as short as possible.

Setting up

You will need a 50 Ω dummy load and a transmitter to set up your indicator. Connect the transmitter to SK1 and the dummy load to SK2. Set the toggle switch, S1, to *forward* and the sensitivity control, VR1, to mid-travel. Switch on the transmitter, and set VR1 for maximum meter deflection. Switch to *reflected* and adjust VC1 until the reading is minimum (ideally zero). This completes the setting up!

Using the indicator

For setting up an aerial, connect your circuit between the transmitter and the cable leading to the aerial. With S1 in the *forward* position, key the transmitter and adjust VR1 for maximum reading on the meter. Switch to *reflected*, and then adjust your ATU to give minimum reflected power. If your adjustments are to be made to the aerial itself, to give minimum reflected power, you must make a note of the reflected reading, switch off the transmitter, make a change to the aerial, key the transmitter, and note whether the reflected power is greater or less than before. Then, make more changes to the aerial. **Never adjust your aerial with the transmitter on**. Make your adjustments on an unused frequency, and do it as quickly as possible, thus avoiding (or minimising) interference to other stations.

Parts list

Resistors: all 0.25 watt, carbon 5% tolerance
(or Maplin 0.6 watt metal film)

R1, R2	27 ohms (Ω)
R3	2.2 kilohms (kΩ)
VR1	10 kilohms (kΩ) linear

Capacitors

C1	220 picofarad (pF) disc ceramic 50 VDC
C2, C3	0.1 microfarad (μF) disc ceramic 50 VDC
VC1	20 picofarad (pF) trimmer

Semiconductors	
D1, D2	OA91 germanium
Additional items	
S1	Single-pole changeover (SPDT or SPCO)
SK1, SK2	Coaxial sockets to suit station standards
	Veroboard – 13 strips by 30 holes
	Veropins (7 off)
	Amidon FT 50–43 ferrite toroid
	Meter, less than 200 μA FSD
	36 SWG enamelled copper wire
	Short length of UR43 or RG58 coaxial cable
	Insulated stranded wire
	Aluminium box
	Standoff insulators for mounting the board
	Knob for the sensitivity control

51 A moisture meter

Introduction

Dry rot (*Merulius Lacrymans*) can strike havoc in buildings, causing the timbers to decay and crumble to dust – hence the term *dry rot*. Wood is attacked only if its moisture content rises above 20%.

Construction

The circuit of the moisture meter is shown in **Figure 1**. The two probes touch the wood, and the current that flows between them depends on the moisture content of the wood. If the moisture is sufficiently high, the current, after amplification, will be enough to light the LED.

The meter can be made on a piece of plain matrix board (no copper strips), as **Figure 2** shows. The board is big enough (10 cm by 2.5 cm) to accommodate the PP3 battery, taped on. No case is needed, unless you want


Probes
R1
100k
b
R2
15k
c
TR1
BC108
e
C1
100n
R3
180R
+
LED
−
TR2
BC108
+
PP3
9V
−
c
e
b
TR1 and TR2
base view
LED
Flat
−
+
Short
lead
©RSGB DY148

Figure 1 Circuit diagram of a moisture meter


Solder tag probes
bolted on with 6BA bolts
+9V
R3
R2
+
LED
−
c
TR1
b
e
c
TR2
b
e
R1
C1
Perforated board
10 x 2·5cm
Tape
PP3
battery
Snap
Solder wires
on tags
−ve
Battery secured with
rubber band or tape
+9V
−ve
©RSGB DY149

Figure 2 Moisture meter, component layout

to leave the meter in a damp location for a protracted period! Make sure that the transistors and LED are mounted correctly. In Figure 2, the connections as shown to TR1 and TR2 are illustrated as if the transistors were transparent. An on/off switch is not really necessary, as only a very small current flows when the probes do not touch anything. Use solder tags, screwed to the board, to act as probes.

After the assembly is completed, check your circuit one final time, and then connect the battery. Nothing should happen at first. If you lick your forefinger and hold it across the probes, the LED should light.

Using it

The prototype was compared with a commercial moisture meter, and the LED lit when the moisture was around 20%. This was quite fortuitous, as the point at which the LED lights depends both on the separation of the probes and on the gain of the two transistors.

In addition to searching for dry rot, the instrument may be used to monitor the moisture in the soil of household plants. In this case, probes made of 16 SWG copper (*not* enamelled) should be soldered on to the two tags, and should penetrate the soil to a depth of several centimetres, and R1 may require adjusting so that the LED extinguishes if the soil is too dry, and lights if the soil is sufficiently moist. If you wanted to leave the meter with the probes in the soil, an on/off switch *would* be necessary.

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1	100 kilohms (kΩ)
R2	15 kilohms (kΩ)
R3	180 ohms (Ω)

Capacitor

C1	0.1 microfarad (μF) polyester

Semiconductors

TR1, TR2	BC108
LED	Any shape or colour will do

Additional items
- PP3 battery and connector
- Solder tags (2 off) for probes
- Matrix board 10 cm by 2.5 cm

52 Simple aerials

Introduction

The performance of *any* receiver or transceiver, no matter how expensive it is, is limited by the aerial that feeds it. Two of the most frequently asked questions are:

- Which is the best sort of aerial to use?
- Where is the best place to locate an amateur radio aerial?

To answer these questions, you must ask yourself what sort of operation you want to do. Are you interested in local, chatty contacts on the lower bands or VHF, or are you more disposed towards long-distance (DX) contacts, and on what band?

A house with a moderately sized garden is assumed in the diagrams here, to illustrate the configurations of some simple aerials. You would not need all these aerials festooned around your house, because one or two would be sufficient for your needs. The problems incurred by properties with more restricted space will be covered later.

VHF aerials

For VHF operation, the aerial should be mounted as high as possible, either on a mast or on a chimney. For all-round coverage on FM and the local repeaters, a vertical colinear is a good choice. For SSB and CW DX operation, a horizontal rotatable beam is needed. If satellite working is envisaged, you will need to contemplate mounting an elevator on top of your rotator, so that your beam can point in *any* direction, including vertically upwards! An advantage of satellite working is that the aerials do not *necessarily* have to be up in the air, provided you have a relatively uncluttered site. Your rotator and elevator can be at ground level, which is good!

If the VHF aerial is mounted on the chimney, use a double mounting bracket, particularly if you have a beam and rotator. Keep the TV, broadcast FM and amateur aerials as far apart as possible, and keeping the feeders separated is also a good plan.

The dipole aerial

One of the simplest types of aerial for single-band operation is the half-wave dipole. (The name ‘dipole’ simply means ‘two poles’ or ‘two elements’, and



Figure 1 Layout for a dipole aerial

in this case the total length of the dipole is approximately half a wavelength at the operating frequency.) It is usually fed in the centre by coaxial cable as shown in **Figure 1**. The length of the dipole for the lowest frequency in each band is shown in **Table 1**. Normally, the length of the aerial will be 'trimmed' to be tuned to the centre frequency of the part of the band in which you will operate. This is done using the data in the right-hand column of Table 1. As an example, suppose you wanted your aerial to be resonant at 3.7 MHz. The table gives an overall dipole length of 42.86 m for 3.5 MHz. To resonate the aerial 200 kHz *higher*, then this length must be shortened by 2 × 0.595 m = 1.190 m. Your dipole would thus be 41.67 m long. Remember to allow extra wire for fixing the dipole ends to the insulators.

Table 1 Dipole lengths for lowest frequency of each band and the length to be trimmed from each to raise the resonant frequency by 100 kHz

Band (MHz)	*Dipole length (m)*	*Trim each end (mm/10 kHz)*
1.8	83.33	2190
3.5	42.86	595
7	21.43	150
10	14.85	70
14	10.71	35
18	8.33	20
21	7.14	15
24	6.03	12
28	5.36	10
50	3.00	6

On the lower-frequency bands, the lengths become rather large. In this case, you can ‘bend’ your dipole, as illustrated in **Figure 2**. The length of wire required to give an acceptable value of SWR (less than 2:1 on transmit) may need to be different from the calculated value, so be prepared to experiment!

Dipoles are single-band aerials, although they will often work acceptably on the third harmonic of their design frequency: a 7 MHz dipole often operates reasonably well on 21 MHz. It is possible to operate several dipoles in parallel, as **Figure 3** shows. Interaction between the elements can occur if the spacing between them is less than about 10 cm. A multi-band dipole, as shown in Figure 3, has the elements separated with plastic spacers, and drooping ends to produce maximum spacing between the elements’ ends.


End insulator
Insulated support
Nylon cord support
Centre insulator
Coax feeder
End insulator
Nylon cord supports
©RSGB DY152

Figure 2 Possible layout for a dipole aerial in a confined space


Spacers at ≈ 300mm centres
Centre insulator
Coaxial cable to rig
100mm or more between dipoles
©RSGB DY153

Figure 3 Multi-band dipole aerial

The long-wire aerial

This aerial is simple, cheap, easy to erect, and suits most houses and gardens, as **Figure 4** shows. Using an aerial tuning unit (ATU), an end-fed long wire can function on several bands when used with a set of radials or a counterpoise. **Figure 5** illustrates the setup. The length of the aerial will determine the bands which will be covered.


Nylon cord support
Insulators
Antenna wire
©RSGB DY154

Figure 4 Long-wire or inverted-L aerial


©RSGB DY155
Long wire antenna
Transmitter/receiver
SWR meter
ATU
50Ω
Safety earth
¼-wave counterpoise wires for each band

Figure 5 How to connect a radio to a long-wire aerial

A wire length of 10.5 m will work on the 40, 30, 17, 15 and 12 m bands.

A wire length of 15.5 m will work (with an ATU) on the 80, 40, 20 and 12 m bands and possibly (depending on your ATU) on the 17 and 15 m bands.

A wire length of 26.5 m will operate on all bands, but may be difficult to load on 10 m.

The wire lengths given here may need some adjustment because of the geometry of your particular house and garden. For receive-only purposes, the lengths are far less critical.

In general, you cannot get a good radio-frequency (RF) earth from a first-floor (or higher) shack. Unless a good RF earth exists within a small fraction of a wavelength of the transceiver, an *artificial ground* comprising a single $\frac{\lambda}{4}$ radial or counterpoise will be needed. You will need one counterpoise for each band you intend to use, and the wire can be concealed around the skirting-board of the shack, or under the carpet. Make sure that the free end

Table 2 Lengths of elements for vertical antennas, radials for verticals and counter-poises for end-fed long wire antennas

Band (MHz)	*Element length (m)*
1.8	39.66
3.5	20.40
7	10.20
10	7.14
14	5.1
18	3.96
21	3.4
24	2.95
28	2.55

of each counterpoise is well insulated; this point can carry a *very high voltage* when you transmit; anyone coming into contact with this can suffer very severe RF burns. Counterpoise lengths can be read from **Table 2**.

The vertical aerial

The single-band vertical aerial is sometimes used by DX operators because it has a low angle of radiation, which favours long-distance propagation. However, it must be sited clear of obstructions and must have a *good* counterpoise or radial system. Illustrations of the vertical aerial are shown, and the lengths of the vertical and radial sections are given in Table 2. The centre of the coaxial feeder is connected to the vertical section, and the braid to the counterpoise or radial system, which is made up of four or more wires buried just below the surface and joined together near the base of the aerial.

Cable entry to the house

Bringing coaxial cable into the house by an open window must be regarded as a temporary measure. Wooden window frames can be drilled, one hole for each feeder. Make the holes slope downwards from inside to out to prevent rain entering, and treat these with wood preservative. Leads from long-wire and inverted-L aerials should be kept separate from other cables.

Alternatively, a plastic pipe large enough to take all your feeders could be fitted into the brickwork (again, sloping downwards towards the outside). You may want to let a friendly builder do this for you.

53 A breadboard 80 m CW transmitter

Introduction

In the early days of radio, many circuits were built on a wooden baseboard, the parts being screwed down on the board. This was called breadboard construction, because it was a breadboard that was frequently commandeered for the process! Wives have always been generous in this respect, it appears!

This circuit was originally designed by GM3OXX, and became known as the *Oner*, because it was built on a circuit board one inch square! The circuit appeared in the G QRP Club journal *Sprat* and, since that time, many hundreds of *Oner* circuits have been built and used on the air. It is a well-proven circuit.

The transmitter has no tuned circuits in the power amplifier (PA) and thus has a rather high *harmonic* content. It **must** be used with the ***low-pass filter*** described elsewhere in this book. Without the low-pass filter, interference will be caused to other stations.

Simple aerial changeover switching is provided, which allows this circuit to be used with any of the 80 m receivers, such as the *Colt*, described in this book. It can also be used with any kit or commercial receiver for the 80 metre band.

The circuit

The transmitter circuit is shown in **Figure 1**. TR1 is a crystal oscillator, the frequency of which is controlled by crystal X1. A small trimmer capacitor, TC1, is added to allow the frequency of X1 to be varied by a small amount. If adjustment of this trimmer is made possible from the front panel, it is useful to adjust the transmit frequency to avoid other stations already on the crystal frequency. The collector load resistor, R2, of the oscillator transistor, TR1, determines the power output; a value of 3.3 kΩ seems to work well in producing an output of 3 watts.

TR1 is directly coupled to TR3, a VMOS transistor (a type of field-effect transistor (FET)). This acts as the power amplifier (PA) stage. TR3 should


ZTX651/
751
VN10KM
e
b
c
s
g
d
Viewed on flat
Net and transmit/
receive swtch
+12V
TR2
ZTX751
e
c
b
R2
R3
1k
Key
C1
100n
C2
100n
RFC
C3
100n
To filter &
Antenna
R1
100k
TC1
X1
b
c
e
TR1
ZTX651
d
g
s
TR3
VN10KM
Receiver
©RSGB DY140

Figure 1 Circuit diagram of the breadboard transmitter

give about 3 W output, which is then coupled to the output by C3. The radio-frequency choke (RFC) providing the drain load of TR3 is simply a few turns of wire on a ferrite bead.

TR2 is an interesting addition to the circuit. It is used as a switch to 'key' the PA, TR3. The transmitter *could* be built without TR2, just placing the Morse key between the top of the RFC and the 12 volt supply. Adding TR2 is helpful, because it means that one side of the Morse key can be grounded (always a good thing), and some degree of *shaping* of the output RF waveform is provided by R3 and C1. This makes the transmission sound a little better and reduces the possibility of spurious frequencies being generated and transmitted. TR2 is a pnp transistor; note that it is the *emitter* of this transistor which is connected to the positive side of the supply.

Some form of changeover switching is needed for the aerial. A double-pole changeover toggle switch can be used. See the chapter on switches, later on in this book. One pole is used to switch the aerial between transmitter and receiver; the other pole is connected in the 12 volt supply line, and is labelled RECEIVE/TRANSMIT – NETTING. Its use will be described later. In this simple circuit, the PA cannot work when the key is open, because the key breaks its supply (via the RFC). When the key closes, TR2 switches on and applies the 12 volt supply to the top of the RFC. C2 is a *decoupling* capacitor, which prevents any residual RF signals at the top of the RFC reaching TR2.

Building

The prototype was put together as follows. Take a piece of plain printed-circuit board (PCB) measuring 5 cm by 4 cm. Then, with a *new*, *sharp blade* in a junior hacksaw, draw the blade horizontally across the surface of the copper in order to make a pattern of 6 squares along the 5 cm side and 5 squares along the 4 cm side. No more pressure should be applied than is necessary to cut through the copper! All the parts will be soldered on these pads in a form of surface-mount construction. To do this, each active pad (i.e. one that is going to have a component soldered to it) needs to be *tinned*. This means coating the pad's surface with solder, and is carried out as follows. Place the hot tip of the soldering iron on to the pad, and hold it there for a second or so. Then, with the tip still in place, touch the end of your reel of solder *on the pad*, not the tip of the iron. The solder should flow evenly all over the pad, and you can remove the iron. The solder should solidify in a rounded, shiny blob! This provides a good surface for making soldered joints.

To join component leads to the pads, cut each lead about 1 cm long, and then bend the last 2 mm at right angles to the rest of the lead. As you did before, tin the 2 mm length of each lead. Place the tinned portion on to the pad, and place the tip of your iron *on the pad*, close to the lead. The solder on the pad and on the lead will melt and run together; remove the iron and *hold the component still* until the solder solidifies. When the joint has cooled, give the lead a gentle tug to make sure you have a good joint (a good *mechanical* joint is usually a good *electrical* joint, too!). Each transistor straddles three pads, so the centre lead will need to be shorter than the other two. Take care here to get the lead lengths right – if you do, you will be surprised how much more firmly the transistor is held than if you just botched the lead lengths by bending them to fit! Make sure the connections to the transistors are correct.

Winding the RFC is quite simple. Seven (or more) turns of thin (32 SWG) enamelled copper wire are threaded through a small ferrite bead. This requires care, because the bead is small and the wire is thin. Trim the ends to within about 1 cm of the bead, remove the enamel carefully with sandpaper and tin the bare ends, prior to soldering the choke to the board.

After completion of the wiring, check the circuit against Figure 1. Breadboarding a circuit like this has its advantages, but it can have disadvantages, too. One of these disadvantages is that it can make circuit checking difficult. For a simple circuit like this, it is not too bad! Check that no solder has run between the pads. Plug in your crystal for the 80 m band, and connect up the 12 V power supply. Do not connect the Morse key yet and do not switch on the power.

Testing and operating

Clear your workbench of all metallic objects, slivers of copper, bits of wire, etc., switch on your power supply. With an external receiver, listen on and around your crystal's frequency for a signal. Remember that the oscillator runs all the time and, because you haven't yet connected the Morse key, your receiver is close enough to pick up the signal from the oscillator. This confirms that your oscillator is running. Switch off.

Connect the station aerial to the transmitter's aerial socket, and the receiver to the transmitter's receiver socket. Connect the Morse key, put the Receive/Transmit–Netting switch in the receive position and switch on. You should be able to hear stations in the normal way. Now put the switch in the Transmit–Netting position. Signals in the receiver should almost disappear, as the circuit has disconnected the receiver's aerial.

Tune the receiver until you can hear your own crystal oscillator signal. This is known as *netting*, tuning your receiver and transmitter to the same frequency. Pressing the key will now transmit your signals when the switch is in the Transmit–Netting position; switch back to the receive position to listen for stations answering your call. As soon as you are happy that your circuit is functioning properly, **you must build the low-pass filter circuit** before using the transmitter regularly.

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1	100 kilohms (kΩ)
R2	See text
R3	1 kilohm (kΩ)

Capacitors

C1, C2, C3	100 nanofarads (nF), or 0.1 microfarad (μF)
TC1	3–60 picofarads (pF) trimmer

Semiconductors

TR1	ZTX651
TR2	ZTX751
TR3	VN10KM

Additional items

RFC	7 turns of 32 SWG enamelled copper on a ferrite bead
Switch	Double-pole changeover (DPDT or DPCO) toggle
Crystal	For 80 m band
Crystal holder	HC25 type
Sockets	According to station fittings



54 A 7-element low-pass filter for transmitters

Introduction

The simpler the transmitter, the more likely it is to radiate *harmonics* of its fundamental frequency. Harmonics are integral multiples of the frequency on which the transmitter is *designed* to operate. If you think you are transmitting on a frequency, *f*, for instance, you will also be radiating the harmonics of *2f*, *3f*, *4f*, . . . and so on. This results in your signals being heard on *several frequencies*, spread over a very wide frequency range. You are also contravening the terms of your licence. To avoid this, it is always advisable to use a *low-pass* filter between your transmitter and aerial. This is a filter which will *pass* your signal frequency, *f*, and all frequencies *below* it, but will *not pass* (attenuate) frequencies above *f* to any significant extent. The value of *f* is known as the *cutoff frequency* of the filter.

A design of 7-element low-pass filter

A 7-element low-pass filter (LPF) is so called because it has seven components, as the circuit diagram of **Figure 1** shows. Filters containing any odd number of elements are possible: a 3-element filter would



Figure 1 Circuit diagram of filter

comprise C1, L2 and C3 only, and is sometimes called a pi-network because the element disposition resembles the Greek letter pi (π); a 5-element filter would comprise C1, L2, C3, L4 and C5 only, and so on. In general, the more elements the filter has, the more effectively it attenuates signals above *f*.

The circuit of Figure 1 is designed to have an input and an output impedance of 50 Ω, which means that it can be placed in the aerial feed of any common transmitter. Filter design is a very complex business, and is best left to the experts. One such expert is W3NQN, who produced a number of computer designs of LPF using commonly available (*preferred value*) capacitors, and aimed specifically for use on amateur frequencies. The results of this work are condensed into **Table 1**. The inductors are wound on standard toroidal cores, and their details are included in the table.

Table 1 Filter component values for each brand

Band metres	*C1,7 pF*	*C3,5 pF*	*L2,6 turns*	*L4 turns*	*Core type*	*Wire SWG*
80	470	1200	25	27	T37-2	28
40	270	680	19	21	T37-2	26
30	270	560	19	20	T37-6	26
20	180	390	16	17	T37-6	24
15	82	220	12	14	T37-6	24
10	56	150	10	11	T37-6	22

Making the filter

The filter was made originally as an adjunct to the *Breadboard 80 m CW transmitter*, which you will also find in this book. It uses the same constructional technique, based on a single piece of plain, copper-clad



©RSGB DY141

Figure 2 Layout and construction of filter

PCB, with ‘pads’ created by using a sharp blade in a junior hacksaw. The cuts in the copper are shown in the layout diagram of **Figure 2**. There are two ways of mounting the components: the first way is to drill small holes in each pad, as shown in Figure 2, and mount the components through the holes in the normal PCB manner; the second way is to solder the components directly to the pads, in the way that was described for the *Breadboard transmitter.*

Winding the inductors is quite simple. All you need to remember is that each time the wire passes through the core counts as one turn. Cut off the spare wire at each end of each coil to about 1 cm, scrape off the enamel with sandpaper, and tin the exposed copper. See the transmitter description if you are unsure of how to do this. Note the wire links between each of the lower pads, forming a solid ‘ground’ for the elements. The prototype had a plug and socket on the ends, to match the transmitter and aerial terminations.

The type of capacitor used in the design is not critical; the polystyrene type works well.

55 Radio-frequency mixing explained

Introduction

Mixers find widespread use in electronic circuitry. Many of the projects in this book, together with every TV set and radio in the home, contain mixer circuits – a good indication of their usefulness.

Confused?

Audio mixers (as used in recording studios and radio broadcast stations) are used to **add** or ‘balance’ the signals from various sources such as microphones, CD players, etc. These have nothing whatsoever to do with radio-frequency (RF) mixers, and should never be confused with them.

RF mixers and beat frequencies

Instead of **adding** signals (as in the audio mixer), the RF mixer **multiples them together.** As you might expect, this has an entirely different effect. The two signals entering the mixer *beat* or *heterodyne* with each other to produce *signals on other frequencies*. One example of this occurs in sound, when two musical notes of almost the same frequency are heard together. Instead of hearing two separate notes, the listener hears one note whose *intensity* (*loudness*) appears to increase and decrease. This intensity variation is called a *beat*, and its frequency is equal to the difference in the frequencies of the two original notes. The technique is used by musicians to tune their instruments. If one note is known to be a correct frequency, the other can be tuned to it by making the beat frequency as close to zero as is possible.

Multiplying together

The process of mixing presupposes that we have a device which will automatically multiply two signals together. Fortunately, this is easy; so easy, in fact, that it often occurs when we do not want it! Multiplying is achieved by any device which is *non-linear*; this means a device whose output is not a constant factor larger than its input, something that can be achieved by many electronic devices and circuits.



©RSGB DY145

Figure 1 The effect of multiplying (or mixing) two signals together

Let us look now at what a mixer does in concrete terms. Suppose two signals, of frequencies *f*1 and *f*2 go into our mixer. These signals are shown in **Figure 1**. Putting numbers in, to make the situation clearer, suppose *f*1 is 1.000 MHz and *f*2 is 160 kHz. The beat frequency is the *difference* of these: 1.000 MHz – 0.160 MHz = 0.840 MHz, or 840 kHz. A mixer *also* produces an output at the *sum* of these frequencies; in this case the new frequency would be 1.000 MHz + 0.160 MHz = 1.160 MHz.

Suppose you fed the output of your mixer, operating with these input frequencies, into a receiver and tuned around to find what frequencies were present. You would find two signals, one at 840 kHz and one at 1.160 MHz, showing that the two ‘new’ frequencies were very real!

In addition to drawing out the waveform of the resultant signal, as in Figure 1, we can draw the inputs and outputs on a frequency axis, to form a *spectrum* of the signal components. This is done in **Figure 2**. The top two diagrams show the input signals at *f*1 and *f*2. The bottom diagram shows the output signals in relation to the input signals. Depending on the type of mixer used, one or both of the input signals would be removed.



Figure 2 The result of multiplying or mixing two signals together as seen on a spectrum analyser

A mixer in every radio

Basically, a mixer is used to change a signal from one frequency to another, something it does without altering the characteristics of the incoming signal. If the incoming signal is amplitude modulated (AM), then the frequency-changed signal would be AM also. The same applies to FM, SSB, CW, and all other modulation forms you can think of. This explains why mixers are often called *frequency changers*.

Frequency changing is the key process in the type of radio known as a *superheterodyne* (or *superhet*). By mixing the incoming signal with a variable-frequency *local oscillator* as **Figure 3**, shows, the signal can be converted to the fixed frequency of a filter and amplifier. This is useful


Incoming signal
Mixer
Fixed frequency amplifier and filter
Variable frequency 'local' oscillator
©RSGB DY147

Figure 3 The basic idea of a superhet receiver

because it is easier to make a very high-quality filter and amplifier at a single fixed frequency, than at a variable frequency.

All TV receivers and virtually all radio receivers (and transmitters) use mixers. Both the *Yearling* and *Colt* receivers (see the relevant projects) are superhets, and use mixers.

56 A voltage monitor for a 12 V power supply

Introduction

If for any reason, the stabilisation of your main 12 volt power supply unit (PSU) breaks down, it is possible that a voltage much higher then the nominal 13.8 V will be applied to your precious equipment. If you would like to know the instant that this occurred, and hence be able to switch things off before it was too late, then this circuit is what you need. It will give audible *and* visual indications if the voltage rises above 14.4 V, and a visual indication only if the voltage is reduced.

The circuit

The circuit uses three ICs and is shown in **Figure 1**. The circuit is powered by the PSU whose output is being monitored, and the circuit's immunity to supply line variations is secured by the 6 volt regulator, IC1. The heart of the circuit is IC2, an LM3914; it is a *bargraph driver*, which operates ten LEDs in a display resembling a thermometer – the string of lit LEDs increases in length as the voltage on pin 5 increases.

The input voltage range on pin 5 is 1.2 V maximum, making each LED correspond to one-tenth of this, which is 0.12 V, the *step size*. R1 and R2 act as a voltage divider, so that voltages of up to the maximum of 14.4 V may be applied to R1 without exceeding 1.2 V at pin 5. R3 sets the brightness of the LEDs and R4 determines the step size.

IC3 is an *opto-isolator*, a device containing an LED and a phototransistor in one package. This enables the piezoelectric sounder to operate without affecting the operation of the bargraph driver. The input to IC3 is provided by the voltage on D8, so that if any of the LEDs at or above D8 are lit, the



Figure 1 PSU monitor, circuit diagram

sounder will operate, indicating overvoltage. Despite the fact that some of your other equipment might be damaged by this overvoltage, the monitor circuit itself is unaffected.

Construction

The prototype was built on two pieces of Veroboard of the copper-strip variety. The main (circuit) board measured 15 strips by 25 holes, and the display (LED) board measured 4 strips by 30 holes. Track cuts are necessary in each board. The correct places are shown for the main board in **Figure 2**, but there is sufficient flexibility in the layout of the display board for a prescriptive layout not to be needed. All the anodes of the LEDs are connected to the same strip, which makes things comparatively simple!

For the main board, insert the Veropins and the wire links first, and solder them to the copper strips. Then fit the IC holders and the resistors. Fit the IC holders with their notches towards the top of the board. When fitting the voltage regulator, IC1, note than the centre lead (the ‘common’ lead in Figure 1) does *not* go to position A3; the track should be cut at A3, and the common lead soldered at B3. This is indicated in Figure 2.

Wire up the LED board with its ten LEDs and 11 connecting wires, each about 10 cm long. This length depends on how far away from the main


Note:
Cut in copper track
at A3 not shown
+ve supply
Component side of board
1
IC1
5
10
15
20
25
A
B
C
D
E
F
G
H
I
J
K
L
M
N
O
P
D1
D2
D3
D4
D5
D6
D7
D8
D9
D10
IC2
IC3
R1
R2
R3
R4
LS1+
Sounder
LS1–
0V supply
+ve supply
● = Pin
●—● = Link
= Cut in copper track
A3
D9, E9, F9, G9, H9, I9, J9, K9, L9
D15, E15, F15, G15, H15, I15, K15, L15
I19, J15, K15

Figure 2 PSU monitor, PCB layout

©RSGB DY158

board you are planning to mount the display. The LEDs should have different colours: three orange, four green and three red, to indicate ‘low’, ‘medium’ and ‘high’ voltage.

Now solder the other ends of these leads to the Veropins on the main board, making sure that the order is correct. Finally, connect the piezoelectric sounder to the main board; the polarity is important, so make sure the red lead goes to pin 4 of IC3 and the black lead to the ground rail. If you were careful to fit the IC holders with their notches in the correct positions, match these up with the notches on the ICs before pushing home the ICs *gently*. Check your circuit for solder bridges and unwanted pieces of copper swarf before screwing the small heat sink to the voltage regulator, IC1.

Testing

(a) **With a variable-voltage PSU**. Set the PSU for 10 V, connect the circuit and switch on. Increase the voltage slowly, and check that each LED lights up after the one before it. As the voltage exceeds about 14.4 V, the first red LED should light and the sounder should operate. If an LED does not illuminate, you should immediately suspect either a dry joint or an incorrect LED polarity. The voltage at which the first red LED lights can be adjusted by varying R1; increase R1 if the LED comes on too early; decrease R1 if the LED comes on too late.

(b) **Without a variable-voltage PSU**. For your 'variable supply', you can use several AA-type 1.5 V cells (or 1.2 V NiCad cells) in series. The voltages produced by a range of cells is shown in **Table 1** – because of the lower voltage of NiCad cells, more of them are needed to produce a given voltage.

Once the operation of the circuit has been checked, it can be fitted into a plastic or metal box. Only two connections are needed for the PSU. You may want to drill some holes in the case to increase the apparent loudness of the sounder.

Table 1 Test voltages available from batteries in series

No. of batteries	*Voltage, nicads*	*Voltage, dry cells*
7	8.4	10.5
8	9.6	12
9	10.8	13.5
10	12	15
11	13.2	–
12	14.4	–
13	15.6	–

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1	11 kilohms (kΩ) – see text
R2	1 kilohm (kΩ)
R3	1.2 kilohms (kΩ)
R4	18 kilohms (kΩ)

Semiconductors

IC1	L7806
IC2	LM3914
IC3	Opto-isolator – Maplin code WL35Q
D1–D3	3 mm LED, orange
D4–D7	3 mm LED, green
D8–D10	3 mm LED, red

Additional items

LS1	Piezoelectric sounder, wire leads
	6-pin DIL socket for IC3
	18-pin DIL socket for IC2
	Veroboard – two pieces for main and display boards, see text for sizes
	Veropins
	Heat sink for IC1
	Single-core insulated wire for links
	Insulated stranded wire for interconnecting the boards
	Case as required

57 A 1750 Hz toneburst for repeater access

Introduction

Repeaters across the UK and much of Europe need an access tone to switch the transmitter from standby ready for use. Commonly, this is a 1750 Hz tone of duration no greater than half a second. Although many UK repeaters may now be accessed using the *continuous tone-coded squelch system* (CTCSS – see the *RSGB Yearbook*), you may wish to access a repeater whose CTCSS frequency you don't know; in this case, using the universal 1750 Hz tone will gain you access. Commercial transceivers are usually fitted with an automatic toneburst, but if you are using a home-made design, then you may want to incorporate this little circuit.

Warning

This circuit uses a member of the integrated circuit family known as CMOS (complementary metal-oxide semiconductor). These use very little current

and can be completed destroyed if they come into contact with the magnitudes of static electricity that most of us carry about when we walk on carpets and wear rubber shoes. You will never know if this wanton destruction has happened – all you will discover is that your circuit doesn't work and that you have tested *everything*. To avoid this problem do the following things:

1. **Before you open the little packet in which the IC is supplied, touch something which you *know* to be earthed – the metalwork of any equipment which is mains earthed, for example. Then open the packet.**
2. **Let the IC fall gently on the bench – don't pick it out with your fingers. Touch your earthed metalwork again. Pick up the IC and insert it gently into its holder.**

The circuit is safe from destruction while it is connected to the battery.

Circuit description

The circuit is shown in **Figure 1**. The tone is generated by an integrated circuit oscillator (IC1), whose frequency is controlled by a *ceramic resonator*, XL1. Its frequency is very high, and is divided down to the 1750 Hz needed by the same chip. The ceramic resonator is designed to operate at 455 kHz, the intermediate frequency of many receivers. Because all divider circuits use powers of 2, we need the oscillator to run at 448 kHz so that when it is divided by 256 ($256 = 2^8$), we end up with 1750 Hz. Try it on your calculator:

$$\frac{448\ 000}{256} = 1750.$$



Figure 1 Toneburst module, circuit diagram

We use C1, C2 and R1 to *pull* the frequency of the oscillator away from 455 kHz to 448 kHz. The divider chain has eight *counters* in it, and each counter divides the frequency of the signal it sees by two, giving the final division of 256.

This counting process can be stopped at any time by taking the voltage on the *reset* pin (pin 12) up to the supply voltage. When the circuit is switched on by closing S1, pin 12 is at 0 V because C3 is discharged. The oscillator runs, producing the output frequency of 1750 Hz. As time progresses, C3 charges up through R2 and the voltage on pin 12 rises. When this has risen sufficiently, and in a time determined by the values of C3 and R2, the counter resets and stays in the reset state; no division takes place and there is no output. The duration of the toneburst is thus governed by C3 and R2.

When S1 is opened, the circuit is switched off, and C3 is discharged through D1 and R3, ready for the next toneburst. If you have used a repeater, you will know that a toneburst is needed **only** to activate a repeater in the standby condition; it is not needed once a contact has been established.

VR1 adjusts the amplitude of the tone fed to the microphone, and C4 prevents any voltage that may be present on your microphone connector from damaging the integrated circuit.

Construction

The prototype circuit was built on Veroboard of the copper-strip variety, measuring 20 holes by 14 strips. The layout is shown in **Figure 2**. Make the track cuts first, and check that there are no slivers of copper wedged between adjacent tracks. Then, solder in the IC socket (with the notched end



Figure 2 Veroboard component layout

facing towards track A), the wire links and the three Veropins. Having done this, solder in the resistors, capacitors and diode, making sure that D1 and C3 are the right way round! Using your best soldering technique, solder in the ceramic resonator quickly, to prevent heat damage. Recheck your circuit, check for solder splashes and bridges, and then gently insert IC1 into its socket, matching up its notch with that of the socket.

Testing

Set VR1 to half-way and connect a crystal earpiece to the output; apply power to the circuit. You should hear the tone, lasting for about half a second. If there is no tone, disconnect your circuit from the power supply, and check for dry joints in the vicinity of pin 12. Is the diode, D1, the correct way round? Is C3 the correct way round? Did you choose to ignore the CMOS safety precautions given earlier?

Once the circuit is working, you need to decide how you are going to connect it to your transmitter. Two options are shown in **Figure 3**. If you have access to a point in your transmitter circuit that has between 9 V and 12 V positive on it during transmit, you can use this to power your circuit. As the toneburst is needed only for repeaters, the switch, S1, disconnects it when not needed, as shown in Figure 3a. If you want the circuit to be self-powered, then a 9 volt PP3 battery may be used; Figure 3b shows this configuration.



Figure 3 Toneburst module: two alternative switching arrangements

The output from the circuit board is fed directly into the microphone socket, in parallel with the microphone itself; use thin coaxial or screened cable for this lead, or you may induce hum into the microphone circuit and suffer from RF breakthrough into the audio circuits. To adjust the setting of VR1, start with it at the zero output position and connect a dummy load to your transmitter. Slowly, increase the output while monitoring your transmitted signal on another nearby receiver. Make sure you do **not** increase the output so far that the signal sounds distorted. If you would prefer that the tone was on continuously while you made this adjustment, simply connect a wire across C3 remembering, of course, to remove it as soon as you have completed the test!



Parts list

Resistors: all 0.25 watt, 10% tolerance (or better)

R1	1 megohm (MΩ)
R2	150 kilohms (kΩ)
R3	12 kilohms (kΩ)
VR1	10 kilohms (kΩ) horizontal preset

Capacitors: all 16 V WKG or higher

C1, C2	1 nanofarad (nF) disc ceramic
C3	4.7 microfarad (μF) tantalum bead
C4	47 nanofarads (nF) disc ceramic

Semiconductors	
IC1	4060
D1	1N4148
Additional items	
XL1	XR455
	Veroboard (see text for size)
	Veropins (3)
S1	Switch (momentary action push-to-make SPST)
	16-pin DIL socket for IC1
	Single-core insulated wire for links
	Coaxial or screened cable for microphone connection

58 A circuit for flashing LEDs

Introduction

There are many occasions when one's attention needs drawing to the fact that something important has happened. A single red light coming on is seldom sufficient to attract attention, particularly if it is surrounded by other lights and indicators. The eye is known to be very sensitive to *changes* in its peripheral vision; such changes can be brought about by movement or by differences in light level – a flashing light, for example. So, a circuit that flashes a single LED or a pair of LEDs finds plenty of uses in the amateur station.

Warning

This circuit uses a member of the integrated circuit family known as CMOS (complementary metal-oxide semiconductor). These use very little current and can be completed destroyed if they come into contact with the magnitudes of static electricity that most of us carry about when we walk on carpets and wear rubber shoes. You will never know if this wanton

destruction has happened – all you will discover is that your circuit doesn't work and that you have tested *everything*. To avoid this problem do the following things:

1. **Before you open the little packet in which the IC is supplied, touch something which you *know* to be earthed – the metalwork of any equipment which is mains earthed, for example. Then open the packet.**
2. **Let the IC fall gently on the bench – don't pick it out with your fingers. Touch your earthed metalwork again. Pick up the IC and insert it gently into its holder.**

The circuit is safe from destruction while it is connected to the battery. However, when the battery is removed, the same care should be exercised with its handling, because there is no supply decoupling capacitor across the IC.

Basic description

LEDs can be made to flash (switch on and off) by driving them from sources that switch on and off. Such a source is an *astable multivibrator*. If you have built or read about *A basic continuity tester*, elsewhere in this book, you will have come across such a beast before. That circuit used an astable multivibrator made from two transistors. This new circuit achieves the same behaviour from a single integrated circuit, the CMOS 4011. To give it its full description, the 4011 is a *quad 2-input NAND gate*. Quite a mouthful, but all it means is that inside the chip are four NAND gates, each with two inputs.

A NAND gate needs a positive voltage (known as a *logic 1*) on *both* inputs in order to produce zero volts (known as *logic 0*) at the output. Two NAND gates can be connected, as are A and B in **Figure 1**, to make our astable multivibrator. The combination of A and B has been described as the most perverse circuit in electronics; as soon as the output goes to logic 1, the circuit decides that it would prefer to have a logic 0 there, and switches over. With logic 0 at the output, the circuit now prefers to have logic 1 there, and so it goes on! We are going to use this continuous switching backwards and forwards to flash two LEDs. The rate at which A and B 'change their minds' is the frequency at which our LEDs will flash, and is controlled by the charging and discharging times of C1 through R2 and C2 through R1. As the values of R1 and R2 are the same, and those of C1 and C2 are the same, the ON and OFF states of the circuit are the same.

Gates C and D do not contribute to the flashing action; they act as *buffers* to isolate the LEDs from the multivibrator circuit itself. You will find in electronics that an oscillator is seldom used to drive another device *directly*; there is usually a buffer between it and the stage it drives.



Figure 1 Flashing LEDs, circuit diagram

A characteristic of all multivibrators, astable or not, is that they have two outputs. In this case, those outputs are at pins 3 and 10, which are then buffered and appear at pins 4 and 11, respectively. When one output is at logic 1, the other is at logic 0, and vice versa. This means that LED1 is off when LED2 is on, and LED1 is on when LED2 is off, the two states switching backwards and forwards at the frequency of the oscillator.

Construction

Read the warning at the beginning of this article again. It is not intended to scare you off from building this, but is a genuine piece of advice which can save you time and irritation when all your labours result in a circuit that doesn't work! That extra bit of care can make all the difference!

Veroboard (the copper strip type) is used for the layout, shown in **Figure 2**. It measures 20 holes by 12 strips. **Be aware that there is no row 'I' in the layout, so don't miscount when you are placing components on the board!**

Firstly, cut the tracks using a 3 mm (⅛ inch) twist drill held between thumb and forefinger; check that there are no slivers of copper bridging any of the tracks, and that the tracks have been completely cut by the drill. Solder in the components carefully. Leave the IC in its carrier for the time being, and solder in the IC socket, with the notched end facing row A. On completion, check the circuit carefully. If you are happy that it is correct, follow the instructions given earlier and fit IC1 into its socket, matching up the two notches. Connect the battery and switch on. The two LEDs should flash on and off alternately. If only one LED flashes, you have probably connected the other one the wrong way round. Switch off, check and correct if necessary. If neither LED flashes, you must have a significant error in your circuit, which will need checking *again*! Or did you choose to ignore the handling precautions for the CMOS chip?


Component side of board shown
+ve via SW1
©RSGB DY178
1
5
10
15
20
A
B
C
D
E
F
G
H
J
K
L
M
R1
R4
IC1
C1
C2
R3
R2
+LEDs
LED 1 −ve
LED 2 −ve
−ve 9V
= Wire link
= Cut in copper track C16, C11, D5, D11, E11, F11, G11, G16, H5, H11, J6, J11, J17
+
−
a
k

Figure 2 Flashing LEDs, component layout

The board can be mounted near to the point where you want your flashing LEDs to be seen, although long leads to the LEDs are acceptable. The LEDs can be different colours – it's all up to you now!

Parts list

Resistors: all 0.25 watt, 10% tolerance or better	
R1, R2	4700 ohms (Ω)
R3, R4	1 kilohm (kΩ)
Capacitors	
C1, C2	47 microfarads (µF) 12 V WKG
Semiconductors	
IC1	4011
Additional items	
LED1, LED2	Any size of LED, any colour
S1	SPST on/off
	Plastic box if needed, 8.5 by 5 by 2.5 cm

Source

Components are available from Maplin.

59 Digital logic circuits

Introduction

Logic circuits form the backbone of even the most advanced computer, yet their basic operation can be demonstrated by a couple of switches, a battery and a bulb.

Logic using switches

Everyone reading this article will look at **Figure 1** and know immediately how it works and be able to write down something like 'When switch A and switch B are closed, the light will come on'. Without knowing it, you have written down a logic statement involving the so-called **AND** operation; the light comes on only when switches A **AND** B are ON. Below the circuit in Figure 1, is a table showing the only possible positions of the two switches and the state of the bulb for each position. This is called a *truth table*, and is frequently used in logic analysis.



A	B	Lamp
Off	Off	Off
On	Off	Off
Off	On	Off
On	On	On

©RSGB DY182

Figure 1 Switches and lamp AND gate

Figure 2 shows a different circuit. Here, the two switches are in parallel rather than in series, as was the case in Figure 1. Again, if you analyse the circuit in words, you would say that the light will be on when switch A **OR** switch B is ON. This is an example of the **OR** operation, and its truth table is shown in Figure 2. The statement above is not complete, however; can you see why? The truth table will show you. The light comes on if A is ON, **OR** if B is ON, ***OR*** if A **AND** B are both ON. That third condition is easy to miss, but don't worry about it!



A	B	Lamp
Off	Off	Off
Off	On	On
On	Off	On
On	On	On

©RSGB DY184

Figure 2 Switches and lamp OR gate

Believe it or not, some very complicated logic is possible (in theory) using switches and lights, but it is highly impractical and would be very slow. This is where electronic logic circuits come in.

Switches with no moving parts

You may have come across projects in this book where a statement is made such as '. . . the transistor is being used as a switch . . .'. Transistors *can* be used as switches, as were thermionic valves in the world's first programmable computer *Colossus*, at Bletchley Park. However, technology has moved on from valves, through transistors to *logic gates*, combinations of electronic switches designed specifically to perform logic functions.

These act on voltage levels as their inputs and produce changes in voltage levels as their outputs. A positive voltage is called *logic 1*, and corresponds to a switch being ON in our previous descriptions; a zero voltage is called *logic 0*, and corresponds to a switch being OFF. The output from a logic gate (normally labelled Q) is also logic 1 or logic 0, corresponding to our light being ON or OFF, respectively, in our switch analogy.

Many logic devices operate from a stabilised 5 V supply, and this determines the *ideal* voltages corresponding to the two logic states:

logic 0 ≡ 0 V,

logic 1 ≡ 5 V.

The world isn't an ideal place, so the *real* voltage ranges used by the logic gates are:

logic 0 ≡ 0.0 to 0.4 V,

logic 1 ≡ 3.0 to 5.0 V.

The **AND** circuit of Figure 1 is now called an **AND gate**, and requires logic 1 inputs on A **AND** B to produce a logic 1 at the output. **Figure 3** shows this. The truth table is identical with that of Figure 1 – logic 1 replaces ON and logic 0 replaces OFF. Now compare Figure 2 with **Figure 4** – circuits and truth tables for the **OR** function. Again, we have exact similarity.



Inputs		Output
A	B	Q
0	0	0
0	1	0
1	0	0
1	1	1

©RSGB DY183

Figure 3 Electronic AND gate



Inputs		Output
A	B	Q
0	0	0
0	1	1
1	0	1
1	1	1

©RSGB DY190

Figure 4 Electronic OR gate

There is another very common logic gate, which performs the **NOT** function. It is easy to understand. Just ask yourself the question 'What is **NOT** logic 0?', and the answer is obviously 'logic 1'. Similarly, logic 0 is **NOT** logic 1. A **NOT** gate simply changes the logic state of the input; it is also known (because of this behaviour) as an *inverter*. Its symbol and truth table can be found in **Fig 5**. Note the little circle on the output of the gate in Figure 5. In logic circuits, this symbol always implies inversion, or the presence of a **NOT** gate. Keep an eye open for it!

So far, the logic functions we have discussed have all been words which we use in everyday language, which has made the electronic interpretation of them relatively easy. Now we must introduce a function for which there is *no* analogy in normal speech – the **NAND** function. This means a



Input	Output
1	0
0	1

Figure 5 Electronic NOT gate

©RSGB DY185

combination of an **AND** gate and a **NOT** gate, and the sharp-eyed reader will have spotted the little circle added on to the normal **AND** gate symbol in **Figure 6**!

To make things easier to understand, the truth table in Figure 6 has four columns, not three as in previous tables. The third column is the standard **AND** output – compare it with the third column in Figure 3. That is the output from the **AND** gate *before* it encounters the little circle that inverts it, so the final output from the **NAND** gate is the output of the **AND** gate, inverted! The third and fourth columns are the inverse of each other.



Inputs		and	Output
A	B		Q
0	0	0	1
0	1	0	1
1	0	0	1
1	1	1	0

Figure 6 Electronic NAND gate

©RSGB DY186



Inputs		or	Output
A	B		Q
0	0	0	1
0	1	1	0
1	0	1	0
1	1	1	0

Figure 7 Electronic NOR gate

©RSGB DY187

We can add the inverting operation to the output of an **OR** gate also, producing a **NOR** gate! The symbol and its truth table are shown in **Figure 7**. Again, notice that the final output is that of the ordinary **OR** gate, inverted!

These new functions of **NAND** and **NOR** are used more than the **AND** and **OR** functions because it makes other circuits easier to design using combinations of these gates.

A taste of Boolean algebra

The design of circuits using combinations of logic gates usually begins with a little mathematics, where the functions to be implemented are analysed. The mathematics used is surprisingly simple, and is a slightly changed version of ordinary algebra called *Boolean algebra*, which allows manipulation of logic functions to be made. Normal algebra has operations in it such as addition, subtraction and multiplication and division. The mathematician Boole found that the logical **AND** operation could be handled by the algebraic operation of *multiplication* (symbols × or •), and the **OR** operation by the algebraic operation of *addition* (symbol +). The **NOT** operation involved a new symbol, that of a bar over the input being inverted, such as A.

So, our five basic logic operators can now be written in a mathematical form:

AND $Q = A \times B$

OR $Q = A + B$

NOT $Q = \overline{A}$

NAND $Q = \overline{A \times B}$

NOR $Q = \overline{A + B}$.

Using logic operations in a mathematical form enables the most complex logic to be designed, simplified and converted into circuit diagram form in a very efficient and rapid way. There are more logic operators than the five we have considered here but, in general, they can all be broken down into combinations of these gates alone!

60 A resistive SWR indicator

Introduction

When a transmitter produces some output power, we want to make sure that as much as possible of this power is radiated by the aerial. This often requires the use of an *aerial tuning unit* (ATU), which matches the aerial impedance to that of the transmitter.

How do you know when this matching has been achieved? The most usual way is to use a *standing-wave ratio* (SWR) indicator. If the impedance of the aerial does not match that of the transmitter output, some of your transmitter power (also known as the *forward* power) is reflected back along the aerial feeder and back into the transmitter, where it causes excess heating. The forward and reflected waves interact along the feeder to produce a wave whose position remains constant, and which is therefore called a *standing wave* or a *stationary wave*. An SWR meter simply indicates forward power and reflected power, and adjustments are made to your ATU until the reflected power is as small as possible (ideally zero, of course). If there is no reflected power then, by a process of elimination, all your forward power is reaching the aerial!

Sampling the RF

Whatever type of SWR indicator you use, it must use some sort of sampling circuit to pick up the forward and reflected waves. The project *A standing-wave indicator for HF*, elsewhere in this book, uses a toroidal transformer to separate the readings for the forward and reverse waves. This design differs in that it measures the voltages across resistors through which the RF current is passing. Its advantages are:

(a) it uses cheap parts – four resistors, two capacitors and a diode, together with a rotary switch, a surplus meter, a preset potentiometer and two sockets;
(b) within this SWR indicator, there is always a resistive path for the RF current from the transmitter, formed by R1, R2 and R3; this can prevent damage to simpler home-made transmitters, which may be damaged during adjustment of the ATU when using more conventional SWR indicators.

The only disadvantage of this form of indicator is that it must be switched out of circuit once the ATU has been adjusted for a particular band.

Construction

The SWR indicator is very simple to build, as most of the components can be mounted on the back of the 3-way rotary switch. This is shown in **Figure 1**. The switch is a 4-pole, 3-way rotary type, of which only two poles are used.



Figure 1 Resistive SWR meter, circuit diagram

Because the other switch contacts are not being used, they can be employed as support tags for other components. The ground wires are all soldered on to the metal frame of the switch. If your switch frame is of all-plastic construction, then a 12 SWG copper wire run around the switch will make a good earth connection to the metal case for the leads shown in Figure 1. The preset potentiometer used to control the sensitivity of the circuit can be mounted directly on the meter tag.

Resistors R1, R2 and R3 handle the RF power during the tuning-up process. If you have them, use 1 watt resistors; otherwise, you can use two 100 ohm half-watt resistors in parallel for each of R1, R2 and R3. The meter, M1, can be any DC type of sensitivity around 200 µA.

In use

First, find a clear frequency, and without the indicator in circuit, check that the frequency really *is* clear by asking and identifying yourself. If it is, connect the indicator between the transmitter and the ATU which, in turn, is connected to your aerial. Turn SW1 to the SET position and key the transmitter. Adjust VR1 until the meter reads full scale. Switch off the transmitter. Turn SW1 to the REF position and key the transmitter again. Adjust the ATU until the lowest reading is obtained on the meter. Switch off the transmitter. For the chosen frequency, you have adjusted your ATU for minimum reflected power and hence the lowest SWR. You will need to repeat the process when you change bands, and possibly when you change frequency within the same band. Switching SW1 to the OUT position, you are ready to transmit. You may have noticed that it is good practice to switch the transmitter off when operating SW1. Get into that habit!

Parts list

Resistors	
R1, R2, R3	47 ohm (Ω) 1 watt (or 2 × 100 Ω, ½ watt, see text)
R4	1 kilohm (kΩ) 0.25-watt
VR1	10 kilohms (kΩ) preset
Capacitors	
C1	1 nanofarad (nF)
C2	10 nanofarads (nF)
Semiconductors	
D1	1N914 or similar
Additional items	
SW1	4-pole 3-way rotary switch, of which only 2 poles are used
M1	200 μA DC
	Case

61 An audio filter for CW

Introduction

This is a simple passive circuit (it has no power supply) that adds some audio selectivity for Morse code reception and also includes a very simple noise limiter that gives a visual indication of when noise spikes are being removed!

The circuit

Figure 1 shows the complete circuit. The tuned circuit of C1 and L1 resonates very close to 800 Hz, so initially you will have to tune a signal in carefully until it sounds loudest – you will soon be able to do this without thinking. The two LEDs connected back to back across the signal path act as a noise limiter, reducing the amplitudes of static crashes and noise from car ignition systems, etc. The LEDs blink when they conduct – this is not necessary to the operation of the circuit, but adds a little colour to your listening! The noise limiter *does* make listening more comfortable, though.



Figure 1 CW filter, circuit diagram

Construction

The circuit layout is shown in **Figure 2**. Point-to-point wiring is used, with a small tag-strip being the only item used for the extra support of C2 and R1. The LEDs and SW1 support the other components. An aluminium box (**Figure 3**) is used to make the circuit tidy and usable.


Earth connection
D1
C2
PL to Rx
S1
Braid
J1 low Z phones (walkman wired mono)
D2
L1
R1
C1
Aluminium box 11 x 6 x 2·5cm
©RSGB DY203

Figure 2 CW filter, component layout


To Rx
©RSGB DY204
LED's
IN
OUT
Phones

Figure 3 CW filter, front panel

You must use low-impedance headphones for the circuit to perform properly. Plug the completed unit into the headphone socket of your receiver and adjust the volume so that the LEDs are just *not* blinking on normal audio. The unit should be switched out of circuit for speech listening; this is the purpose of the toggle switch, SW1.

Parts list

Resistor

R1	10 ohms (Ω), 0.25 watt, 10% tolerance

Capacitors

C1	470 nanofarads (nF)
C2	100 microfarads (μF) electrolytic, 16 V WKG

Inductor

L1	82 millihenries (mH)

Semiconductors

D1, D2	LEDs

Additional items

SW1	DPDT
J1	3.5 mm jack socket
PL	Jack plug to suit receiver
	Aluminium box, approx. 11 by 6 by 2.5 cm

Source

Components are available from Maplin.

62 An electronic die

Introduction

Throwing a die is a venerable way of generating a 'random' number between 1 and 6. A die is easy to lose, so here is an electronic die-throwing circuit which brings the technique up to date and serves as another application of logic circuits. If you need a reminder of the basics of logic, refer to *Digital logic circuits*.

Warning

This circuit uses members of the integrated circuit family known as CMOS (complementary metal-oxide semiconductor). These use very little current and can be completed destroyed if they come into contact with the

magnitudes of static electricity that most of us carry about when we walk on carpets and wear rubber shoes. You will never know if this wanton destruction has happened – all you will discover is that your circuit doesn't work and that you have tested *everything*. To avoid this problem do the following things:

1. **Before you open the little packet in which the IC is supplied, touch something which you *know* to be earthed – the metalwork of any equipment which is mains-earthed, for example. Then open the packet.**
2. **Let the IC fall gently on the bench – don't pick it out with your fingers. Touch your earthed metalwork again. Pick up the IC and insert it gently into its holder.**

The circuit is safe from damage while it is connected to the battery.

Description

The circuit is shown in **Figure 1**. IC1a and IC1b form an *astable multivibrator*, similar to that used in 'An LED Flasher' also in this book. It runs constantly, and its output is fed to IC2 via a single NAND gate, IC1c. The other input of IC1c is held at 0 V by R3 and C3. Whenever one input of a NAND gate is logic 0 (or 0 V), there can be *no output* from the gate, irrespective of what is happening at other inputs. So, despite the fact that the oscillator (or *clock*) is running all the time, its square-wave output never


+ve
SW1
R1
C2
+
R2
IC1 pin 14
12
11
13
IC1d
1
3
IC1a
2
+
C1
5
4
6
IC1b
7
1
3
14
4
9
10
IC2
16
+ve
SW2
9
10
15
8
IC1c
11
6
D5
D1
D3
D7
D6
D2
D4
5 8 12 13
C3
+
R3
IC1 pin 7
R7
R6
R4
R5
+
9V
–
©RSGB DY205

Figure 1 Electronic dice, circuit diagram

reaches IC2 until the ‘other’ input of IC1c is brought away from logic 0. This happens when SW2 is pressed. Pressing SW2 momentarily, as is normally done, charges up C3 to 9 V, putting a logic 1 on the second input of IC1c and allowing the clock signal through to IC2. As the switch is released, C3 begins to discharge through R3, gradually lowering the voltage on pin 8 of IC1c. As this voltage crosses 4.5 V (half the supply voltage), IC1c then treats this input as logic 0, which cuts off the clock signal from IC2 again. Thus, when SW2 is momentarily pressed, the clock signal is fed to IC2 for a short interval of time, before being blocked again.

IC2 is a binary counter, and the outputs that concern us are from pins 14, 11 and 6. Pin 14 is the *most significant bit* and pin 6 the *least significant bit*. See the panel for an explanation of what happens here.

To understand these outputs, you should be able to count in binary, using three bits. At the start of the counting process, all the bits have zero values, i.e. 000. The left-most bit is called the *most significant bit*, and the right-most bit is called the *least significant bit*. (When we write numbers normally, a number 1 in the left-hand position represents one hundred, 1 in the middle column represents ten, while the number 1 in the right-hand position means one. One hundred is a more significant number than one, hence the nomenclature.)

The three bits of our binary number have values, from left to right, of 4 (=2^2), 2 (=2^1) and 1 (=2^0). This means that a number 1 in the left-hand column signifies the normal number four, in the middle column it would represent two, and in the right-hand column, it would represent one. This should help you understand the patterns of bits which emerge as the clock waveform is counted, as the next paragraph explains.

As each cycle of the clock enters IC2, it increments its internal counter and the values of that counter are shown by the states of pins 14, 11 and 6. After the first pulse, these three pins would have states corresponding to 001; after the second, 010; after the third, 011; after the fourth, 100; after the fifth, 101; after the sixth, 110. This sequence of 3-bit numbers represents a binary count from 1 to 6 in ‘normal’ parlance. These six states are used to illuminate the conventional pattern of dots on a die, using LEDs.

As the clock cycles are counted, the LEDs flicker as the die is ‘rolled’. Resistors R4 to R7 are used to limit the current through the LEDs. When the counter stops, it can be in any of the positions shown in **Table 1**. Because of

Table 1 Dice number relative to counter output

Step	*Pins*			*Dice number*
	14	*11*	*6*	
1	0	0	1	4
2	0	1	0	2
3	0	1	1	6
4	1	0	0	1
5	1	0	1	5
6	1	1	0	3

the way in which the dots are grouped on the faces of a die, the wiring of the LEDs is simpler than it might otherwise be. You can see from Figure 1 that there are really only three sets of connections to the LEDs – one from each bit of the counter output. When pin 14 is at logic 1, four LEDs are lit, corresponding to the number four. For the number five, pins 14 and 6 will be at logic 1. For the number one, only pin 6 is at logic 1. For three, pins 11 and 6 are at logic 1, for six, pins 14 and 11 are at logic 1, and for two, only pin 11 is at logic 1. These conditions are summarised in Table 1.

Construction

Two pieces of Veroboard (of the strip type) are needed – one for the main circuit (**Figure 2**) and the other for the display LEDs (**Figure 3**). The display board is easier to build, so we will do that first. It measures 20 holes by 18 strips.

Cut the tracks as shown in Figure 3, using a 3 mm (1⁄inch) twist drill rotated between thumb and forefinger. Insert and solder the Veropins, resistors and the wire links. Then solder the LEDs in place, making sure their polarities are correct. The LEDs are mounted proud of the board (**Figure 4**, which will help when you come to fix the board into a case.

The main board measures 32 holes by 18 strips. As before, remove the tracks in the places shown in Figure 2. Note that track 'L' is *not* broken under the position for IC2. Solder in the IC holders and the links. Solder in R1 and R2 vertically, and R3 horizontally. Then solder in C1, C2 and C3; these all being electrolytics, check their polarities. Solder in the Veropins and prepare the connections to those components not on the main board, using stranded, insulated wire. Check the circuit carefully, and read the handling precautions given earlier before carefully inserting the two ICs.


To battery via SW1
+
To SW2
Component side of board
1
5
10
15
20
25
30
A
B
C
D
E
F
G
H
I
J
K
L
M
N
O
P
Q
R
R1
R2
C1
C2
IC1
IC2
R3
C3
To Pin A1 (display board)
To Pin G2 (display board)
To battery −
To Pin R1 (display board)
To SW2
To Pin F1 (display board)
= Pin
= Link
= Cut in copper track
E10, E18, F10, F18, G10, H10, H24, I10, I18, I24
J10, J18, J24, K10, K18, K24, L18, M18, M24
N24, O18, O24
©RSGB DY208

Figure 2 Main board, component layout


1
5
10
15
20
A
B
C
D
E
F
G
H
I
J
K
L
M
N
O
P
Q
R
D1
D3
D5
D7
D6
D2
D4
R4
R5
R6
R7
= Pin
Component side of board
= Link
= Cut in copper track
B10, G12, M10, N10
©RSGB DY206

Figure 3 Board for the six LEDs



Figure 4 D7 lead bending

Testing and use

When the circuit is switched on, it is likely that the centre LED only will be lit. Press SW2, the 'throw' switch. All the LEDs should flicker, even after the switch is released, but only for a second or so. Then a standard pattern should show, signifying numbers between one and six. If this does not happen, switch off and check your circuit again. Are there any missing links? Are there any obvious dry joints (usually dull instead of shiny)? Can you see any solder bridges between tracks? Did you choose to ignore the handling precautions? If none of these results in a working circuit, try some fault-finding.

- Disconnect the lead to D7 on the main board (marked 'to pin F1' on Figure 2). Touch the lead on to the positive supply rail. D7 should light. Now transfer this lead on to pin 4 of IC1. If it flickers, then the oscillator is running (which it should).
- Transfer this lead to pin 10 of IC2. D7 should flicker when SW2 is pressed, but should be on permanently when it is released. This means that the correct signals are reaching IC2 from IC1.
- If one of the chains of LEDs (i.e. D1 and D2, D3 and D4, D5 and D6) does not light, you may have one *or both* LEDs the wrong way round.

When the die is working, you may care to experiment with the values of R1 and R2, but you should keep their values the same, i.e. R1 = R2. The larger the values of these, the more slowly the die will appear to 'roll'.

Finishing touches

On completion of the project, you will want to mount it in a smart case; any plastic box is suitable for this, with the display board mounted so that the

LEDs protrude through the top and are fixed to it using LED clips. The way in which you mount both boards to the case is entirely up to you.

Parts list

Resistors: all 0.25 watt, 10% tolerance, or better

R1, R2	5600 ohms (Ω)
R3	15 kilohms (kΩ)
R4–R7	470 ohms (Ω)

Capacitors

C1, C2	1 microfarad (μF) electrolytic, 16 V WKG
C3	68 microfarads (μF) electrolytic, 16 V WKG

Semiconductors

IC1	4011
IC2	4029
D1–D7	LEDs, any size and colour

Additional items

SW1	On-off switch SPST toggle
SW1	Push-to-make, non-latching
	Veroboard, 2 pieces, see text for sizes
	Veropins, 10
	Stranded insulated wire for general wiring
	Single-core insulated wire for links
	PP3 battery clip
	PP3 battery
	Plastic box to suit
	LED mounting clips (7)
	Means of mounting boards to box

Source

Components are available from Maplin.

63 The absorption wavemeter

Introduction

The purpose of the absorption wavemeter is to check that a transmitter is radiating within the correct waveband, and to detect any spurious *harmonic* emissions. A harmonic frequency is an integral multiple of the carrier frequency – e.g. if the carrier is at a frequency *f*, the harmonics are at frequencies 2*f*, 3*f*, 4*f* . . . and so on.

It can also be employed as a relative field-strength indicator, being used in experimentation with aerials. What it *cannot* do is to measure the transmitted frequency accurately; all it can do is to place the signal within a particular band, say the 7 MHz or the 18 MHz band (or their harmonics).

How it works

You may recognise the circuit of **Figure 1** as a crystal set with a meter replacing the headphones. It is simply the parallel combination of an inductance with a variable capacitance, which constitutes a resonant circuit with a variable frequency. A dial on the variable capacitor can be roughly calibrated with frequency. The fixed capacitor across the meter helps to improve the meter reading by making it read the peak value of the carrier wave rather than the average value.



Figure 1 Absorption wavemeter circuit

When the wavemeter is situated in the vicinity of a relatively strong radio-frequency (RF) field, the inductor absorbs a small amount of energy from that field. If the circuit is resonant at the same frequency as that of the transmitter, an RF voltage is produced across the coil and is proportional to the strength of the RF field. The RF voltage is *rectified*, or *detected* (turned from AC into DC) by the diode and the second capacitor, and is displayed by the meter.

The tuned circuit

The formula for calculating the resonant frequency of a coil and capacitor is relatively simple. It is

$$f = \frac{1}{2\pi\sqrt{LC}},$$

where f is the resonant frequency (Hz),
L is the inductance (H), and
C is the capacitance (F).

If this formula puts you off, there is this slightly easier version:

$$f = \frac{159}{\sqrt{LC}},$$

where f is the frequency in **MHz**,
L is the inductance in **microhenries** (**μH**), and
C is the capacitance in **picofarads** (**pF**).

When a variable capacitor is specified, it is usual to quote its maximum capacitance, i.e. the value when the vanes are fully meshed. When the value of the capacitor is small, it is usual to quote its minimum capacitance also, the value when the vanes are fully open. If you use a variable capacitor of 10–100 pF with a 100 μH inductor, you will use the value of 10 pF to calculate the maximum resonant frequency, and the value of 100 pF to calculate the minimum resonant frequency, giving a tuning range of 1.6 MHz to 5 MHz. Check it yourself!

64 An HF absorption wavemeter

Introduction

An absorption wavemeter is basically a simple tunable detector circuit, such as would be used in a crystal set, but with the headphones replaced by a meter, in order to indicate the strength of the received signal.

The circuit

Figure 1 shows the circuit of the wavemeter. It is designed to cover all the HF bands from 1.8 MHz to 28 MHz in four switchable ranges. There is no built-in method of amplification, so a sensitive meter is needed in order to indicate sufficiently using the available absorbed energy. The meter does not need calibrating, it serves to produce only an indication of the absorbed power, *not* its absolute value.

An absorption wavemeter does not have outstanding selectivity, mainly because of the loading effect of the meter. This problem is ameliorated here (but only slightly) by the inclusion of R1 in series with the meter. It gives



©RSGB DY211

Figure 1 HF absorption wavemeter, circuit diagram

improved selectivity at the expense of a slight loss of sensitivity. The appearance of capacitor C1 across the meter is discussed in *The Absorption Wavemeter*, in the previous section.

Coils

These can be purchased (see the parts list) or hand-wound on short lengths of PVC water pipe or conduit, and the coil-winding details are given in **Table 1**. In theory, the 100 pF tuning capacitor would cover all the HF bands with only three coils, omitting the 22 μH coil. Sample calculations are explained in the previous article. However, its inclusion avoids the common problem of having some bands cramped at the extreme edges of the tuning scales.

Table 1 Close-wound coil values

L (μH)	No of turns	Span (mm)	SWG
PVC FORMER OF OUTSIDE DIAMETER 25 mm			
2.2	9	9	20
10	24	24	20
22	44	44	20
100	110	60	26
PVC FORMER OF OUTSIDE DIAMETER 20 mm			
2.2	10	10	20
2.2	9	5	26
10	32	32	20
10	24	12	26
22	63	62	20
22	41	21	26
100	134	70	26
PVC FORMER OF OUTSIDE DIAMETER 19 mm			
2.2	11	11	20
2.2	9	5	26
10	35	34	20
10	25	13	26
22	68	67	20
22	44	22	26
100	157	79	26

Construction

Hand-wound coils, using 19–25 mm PVC formers, have single-layer windings, with their ends secured by threading the wires through two small holes drilled in the formers at each end of each winding.

You may have wondered about the use of the two-pole switch SW1, as all the lower ends of the coils are grounded anyway. The answer lies in the ease of construction. Each coil can be mounted on the tags of the switch for support. If you are using the commercial coils, they are small enough to be accommodated on a miniature rotary switch; a larger rotary switch is required for hand-wound coils. The specification of a 6-way switch allows for the addition of extra frequency ranges at little extra cost. Rotary switches such as the 2-pole, 6-way variety have an adjustable end-stop which allows the number of ways to be set anywhere between 2-ways and 6-ways. Remove the nuts from the switch, and a ‘washer’ will fall out. It is not a washer, really, and has a little piece of metal bent over at right angles to the washer. This fits into one of 12 holes in the body of the switch, and prevents the shaft from turning through 360° and selecting the number of ways.

Calibration

This process needs a commercial amateur-bands transceiver, if it is to be done quickly and accurately.

- Connect the transceiver to a dummy load, and connect a piece of flexible wire from point A in Figure 1 and wrap two or three turns around the cable between the transceiver and the dummy load.
- Turn the transceiver power level control to minimum, and set the frequency at 1.81 MHz and the mode to FM or AM. Switch to transmit.
- With the wavemeter set to its lowest frequency range (i.e. 1.8–3.5 MHz), rotate the tuning capacitor until maximum deflection is obtained from the meter needle. Write the frequency on the inner ring of the wavemeter scale at that point.
- Switch off and retune the transmitter to 3.5 MHz. Repeat the above process.
- Repeat, using switch range 2 for 3.5, 7 and 10 MHz, range 3 for 7, 10 and 14 MHz, and range 4 for 14, 18, 21, 24 and 28 MHz.

An alternative source of calibration signal could be an HF signal generator, with a single-turn loop of wire at the remote end of its cable, and the wire from the wavemeter brought close to the loop.

Remember that the marks on the scale represent frequency *bands*, not precise frequencies.

Extending the range

If you would like to experiment with increasing the range to the lower VHF band, then 50 MHz should be achievable with an additional self-supporting coil (no former). Try three turns of 20 SWG enamelled copper wire of 25 mm ID (internal diameter). Wind it on some 25 mm PVC pipe, as before, then slide out the pipe! The same result could be achieved with four turns of 19 or 20 mm ID, or 12 turns of 7.1 mm ID.

Parts list

Resistor	
R1	2200 ohms (Ω) 0.25 watt, 10% tolerance
Capacitors	
C1	1 nanofarad (nF) min. ceramic
VC1	100 picofarad (pF) variable
Inductors	
L1	100 microhenries (μH)
L2	22 microhenries (μH)
L3	10 microhenries (μH)
L4	2.2 microhenries (μH)
Semiconductors	
D1	Germanium OA91 or 1N4148
Additional items	
SW1	Rotary 2-pole, 6-way
	Moving-coil meter, 50 or 100 μA FSD (any meter of this sensitivity will do)
	Plastic box, approx. 150 by 80 by 50 mm
	Connecting wire, coloured

65 A vertical aerial for 70 cm

Introduction

If the range of your hand-held transceiver is very limited, what you need is a vertical aerial mounted outside. This design is a half-wave dipole fed at the end instead of the middle. Because the impedance of the dipole is high at its ends (and low in the centre), a matching circuit is needed so that this high impedance can be matched to that of the low-impedance coaxial cable. All that is needed is a coil, which increases the *electrical length* of the aerial to ⅝-wavelength. (Note that the *electrical* length (i.e. the length as it appears to an RF signal) is not necessarily the same as the *actual* length.)

Construction

The aerial element and the coil are made from a single piece of 1.5 mm welding (brazing) rod, and the dimensions are given in **Figure 1**. Wind the coil around a 4 mm rod or the shank of a twist drill. The lower end is filed to a point and then soldered into the centre conductor of a 4-hole panel-mounting BNC socket. (Try to obtain a good-quality BNC socket with PTFE insulation – the insulation of cheaper sockets is easily damaged.) Trim the element to 427 mm (top of element to top of coil) *after* the wire has been soldered to the socket.

The base coil causes the aerial to be rather ‘whippy’, so a piece of 5 mm plastic knitting needle can be cut to the length of the coil and then forced into it.

The radials are made from four lengths of 3 mm welding rod. These are bent and soldered into the four mounting holes of the socket, and then cut to the lengths shown in Figure 1.

Testing

Using a standing-wave-ratio (SWR) meter connected between your aerial and the transceiver, measure the SWR (or obtain some indication of the reflected power) on transmit. If it is greater than 1.5, switch off the transmitter, trim about 3 mm off the end of the element, and try again. Repeat the process until the measured SWR (or the reflected power) is as low as you can get it.


Insert suitable bung to water proof
Antenna cover tube
Slots to accept radials
Coupler
Base tube
427mm
5 turns
163mm (all 4 radials)
©RSGB RC327

Figure 1 Construction of the 70 cm antenna

Installation

The aerial is made waterproof by enclosing it in a 22 mm diameter PVC waste water pipe. It is 'weldable', and available at plumbers' merchants, usually by the metre. A coupler is slotted to take the radials (Figure 1). File the BNC socket as required, so that it slides inside the coupler until the radials poke out of the slots. Cut a length of plastic tubing which is 30 mm longer than the aerial, and push it into the coupler. You will then need a plastic bung or screw-top to waterproof the top end.

Plastic welding solution is now applied to the joints, sealing the aerial inside the tube. The coupler has been weakened as a result of making the slots, so it is worthwhile applying PVC tape around this joint until the welding solution sets.

A support for the aerial is made from an off-cut of tube pushed into the lower end of the coupler and held with a self-tapping screw.

Parts list

1	4-hole panel-mounting BNC socket
1 m	3 mm brazing rod (may be available from a small garage)
1 m	1.5 mm brazing rod
1 m	22 mm PVC waste water pipe
1	22 mm straight coupler
	Plastic welding solution

66 A UHF corner reflector aerial

Introduction

The corner reflector is a well-known design and is capable of good performance on the VHF and UHF bands. At UHF, the practical implementation of the corner reflector is an ideal constructional project.

Some details

Expressed quite simply, the aerial consists of a $\frac{\lambda}{2}$ dipole (where λ is the standard symbol for wavelength, making a ‘$\frac{\lambda}{2}$ dipole’ a half-wave dipole).

Nothing new in that, you might say. However, the interesting feature is the reflector, which is not the usual single element, but a 90° metal 'corner', acting rather like a parabolic dish as used for satellite signal reception. The wind resistance of this type of reflector makes it impractical so, to reduce the 'windage' quite significantly, we make the 'corner' from closely spaced rods, as illustrated in **Figure 1**.



Figure 1 70 cm corner reflector antenna

©RSGB DY215

The reflector consists of a number of 0.6λ rods, spaced from each other by 0.1λ. The aerial frame can be made of metal or wood, but wood is easier to work with, and mounting the elements to the frame is simpler. The prototype was made with wood of 20 mm by 15 mm cross-section, as **Figure 2** shows. The wood was varnished for protection. The elements were made from 1.5 mm diameter copper wire, because a large reel of the wire happened to be available. The wire diameter is not critical; tubing could be used just as successfully. 14 SWG hard-drawn copper aerial wire would be even better than that used in the prototype.


0·5cm
17·5cm
17·5cm
1cm
Dipole driven element
41·4cm
21·2cm
Driven element
45°
45°
Driven element mount
90°
45°
2cm
4cm
3cm
6·9cm
10 holes spaced at 6·9cm
69cm
Reflector mount
©RSGB DY216

Figure 2 Driven element dimensions, together with boom dimensions for driven element and reflectors

Construction

This project is just as much a woodworking project as a radio project! Follow the instructions carefully, and you should have little trouble.

- Cut the booms for the reflectors, as shown in Figure 2. A mitre block is invaluable here in producing the 45° corners.
- Using the dimensions given on the diagram, mark the hole positions for the reflector elements, and then drill holes of a size which holds the elements firmly.
- Cut the driven element boom according to the diagram, and mark the point midway along the longer side, which will assist you later in positioning the driven element.
- Cut the back plate to size (about 120 mm by 80 mm). You may need to alter this size depending on the size of the U-bolt you will be using to clamp the aerial to the mast.

- If you want to be extra cautious in your construction, use the belt-and-braces approach, commonly known as 'screw-and-glue' to fix the booms to each other and to the back plate.
- Fix the reflector booms to the back plate first, then slide in the driven-element boom until it will go no further, then apply the wood glue and screw the two ends tightly to the reflector booms. Leave for the period prescribed by the glue manufacturers for the glue to harden.
- Varnish the whole structure.
- Cut the driven element to the correct size plus a couple of centimetres (the reason for this will be evident in the *Testing* section), and fix it to the centre of its boom (at the position you marked earlier) with a 'chocolate block' connector to which the coaxial feeder cable will eventually be connected.
- Cut and fix the reflector elements in place. If you find that these are a loose fit in the holes then, *for each element*, drill a pilot hole through the boom to intersect the hole for the element. File off the point of a woodscrew, and screw it gently into the pilot hole until it meets the element and grips it in place. You will now see why the point was filed off! Alternatively, you can glue the elements in place.

Testing

Place the aerial on a mast, clear of obstructions. Connect it to a transceiver with a length of coaxial cable, with a standing-wave-ratio (SWR) meter in circuit. Find a clear frequency, identify your transmission and ask if the frequency *really is* clear. If so, key the transmitter again and note the SWR. **Do not stand in front of any aerial when it is radiating!** The length of the driven element must be adjusted to obtain an SWR of less than 2. If you have to shorten the dipole, bend the ends over rather than cut them off. That way, if you go too far, your can lengthen them again! The dipole was initially cut too long intentionally, to allow for adjustment here! Bending the ends over also reduces the risk of physical damage to clothing, skin and eyes. You may like to consider applying the same technique to the reflector elements for that reason alone.

Moving on . . .

Once you have warmed to the idea of the corner reflector as an aerial, you might like to ring the changes regarding the reflector. How about replacing the 20 reflector elements with a wire mesh, such as garden centres sell as 'chicken wire'? Choose the finest mesh if there is a choice. Some extra support may be needed around the edges of the mesh, but you could go on to make a comparison of aerial gain between the two types, using the *UHF Field Strength Meter* described elsewhere in this book.

Materials

Stiff wire or thin-walled tubing for dipole and reflector
Frame – wood, 15 mm by 20 mm cross-section, lengths given in text
Back plate – stout plywood, dimensions given in text
U-bolt to suit mast
Wood screws
Wood glue
50 W coaxial cable for feeder
2-terminal 'chocolate block' for dipole connection to feeder
Varnish

67 A switched dummy load

Introduction

A dummy load is a pure resistor of value 50 ohms which can replace your transmitting aerial and enable you to operate the transmitter for test purposes without radiating a signal. It sounds simple enough, but there are two main problems. Firstly, it is impossible to delve into your junk box and emerge with a resistor that will dissipate 100 W PEP and still retain its marked resistance value. Secondly, a 'pure resistance' is very difficult to achieve. A pure resistance is a device which has resistance but no reactance. All common resistors have significant reactance at radio frequencies, particularly the wire-wound varieties, which have a helical (i.e. wound like a coil) construction. This is particularly annoying, because wire-wound construction is normally used for large-wattage resistors.

Although all resistors have *some* reactance, not all are quite as bad as the wire-wound type. Carbon film resistors are made by depositing a thin film of carbon on the surface of a small, hollow ceramic cylinder, the thickness of the film of carbon determining the value of the resistor. Provided the lead lengths are kept short, these resistors have a tolerably small reactance, and will be used in this project.

Bearing the load

A 2 W carbon film resistor is hardly going to withstand our 100 W PEP of SSB, so it is obvious that the design of our dummy load must be a little more complex than a single resistor and a switch, despite what **Figure 1** might suggest! In fact, it uses 20 resistors, each of value 1000 Ω (1 kΩ). How does this solve our problem?

Perhaps a little theory is in order here, but no more than is required by the Radio Amateurs' Examination.

When two *equal* resistors of value r are combined in parallel (i.e. side by side), the total resistance, R_T, is given by:

$$\frac{1}{R_T} = \frac{1}{r} + \frac{1}{r}.$$

Adding $1/r$ to $1/r$ gives $2/r$, therefore:

$$\frac{1}{R_T} = \frac{2}{r}, \quad \text{i.e. } R_T = r/2.$$

So, by connecting *two* equal resistors in parallel, we get a combined resistance which is *half* the individual resistances. If we combine *three* in parallel, we get a *third* of the resistance, and so on.

Here, we are connecting *20* resistors of 1 kΩ in parallel, so we will produce an overall resistance of *one-twentieth* of the individual resistance, i.e. 1000/20 = 50 Ω, which is what we set out to achieve!



Figure 1 Basic circuit diagram

This is not the only advantage, though. Each resistor is capable of dissipating 2 W, so 20 of them will safely dissipate 40 W, for short periods at least. This power dissipation is approximately the same as 100 W PEP of normal speech, so the design should be capable of use in an 'average' amateur station. The power-handling ability of any dummy load can be improved by providing a 'heat sink' which helps to conduct the heat energy away from the resistors, thus lowering their temperature. One popular heat sink is a can of transformer oil, into which the resistors are immersed. This design uses a rather more mundane heat sink, but which is adequate for the job in hand.

Figure 2 PCB resistor supports


10mm
©RSGB DY213
22mm
2 PCBs (single sided) 100 x 35mm, 20 holes
1 'earth' PCB with two 3mm holes

Figure 3 Switched dummy load, component layout


120 x 95 x 53mm
die cast aluminium box
To transmitter
To
antenna
S1
(10A - 2 way)
COM
PCB
A
A
'Earth' PCB
Bolt 'earth' PCB
to side of box
2mm gap
between
resistors
18swg aluminium
20 x 130mm
bent up each end
with two 3mm holes
Heat sink
compound
Twenty 1k 2W
resistors
Two 5 x 20 x 100mm
ceramic wall tile
Section A-A
©RSGB DY214

Pouring the heat away

Two basic PCBs are needed, the details being given in **Figure 2**. Both measure 11 × 35 mm. Each has a set of 20 holes of diameter about 1 mm to take the ends of the resistors. Only one of them has two 3 mm holes which are used for mounting the completed load. **Figure 3** shows how the heat sink is assembled. Solder one end of each resistor into the ‘earth’ PCB, and then mount this to the box using the two bolts as shown in the diagram. Between each rank of resistors is a ‘sandwich’ consisting of an aluminium strip and two pieces of ceramic wall tile, to act as a heat sink for the resistors. Heat sink compound is used to provide good thermal contact between the resistors and the tiles, and between the tiles and the aluminium strip. This is shown in the lower part of Figure 3. Thread the loose wires of the resistors through the holes in the second PCB, solder into place, and crop the protruding wires.

Switching

A changeover switch must be used so that the transceiver can be switched between the dummy load and the aerial without unscrewing connectors. For most purposes, an ordinary 10 A 230 V changeover switch will suffice, as found in many electrical shops and DIY stores.

Wire this into the circuit as shown in Figure 1 and Figure 3. Check your wiring. Put S1 in the ‘dummy load’ position. If you have a multimeter which includes an ohmmeter, measure the resistance across the socket, J1, before connecting it to the transceiver. It should be very near 50 Ω. With S1 in the ‘aerial’ position, there should be an infinite resistance across J1. Move your ohmmeter to read the resistance across J2. It should be infinite for both positions of S1. If all seems correct, close the box and your dummy load is ready for use!

Parts list

Resistors
  1000 Ω (1 kΩ) 2 W carbon film, 20 required
Additional items
  10 A 230 V changeover (SPDT) switch
  SO–239 sockets, 2 required
  Aluminium box 120 × 95 × 53 mm or similar
  Ceramic wall tile cut as required
  Aluminium strip, 18 SWG
  Nuts and bolts as required

68 A simple Morse oscillator

Introduction

This is an excellent project which uses the ‘junk box’ as its source of components. If you have trouble in finding the bits for this one, a good source of the components for this and many other similar projects is to be found with the parts list at the end of the project.

The circuit

This is shown in **Figure 1**, and uses an ‘unknown’ Plessey chip, which makes the overall circuit extremely easy to build. A 0.1 μF capacitor is connected between pins 7 and 8, a speaker (in the popular 8 to 25 Ω impedance range) is connected between pins 8 and 9. If a 9 V battery is connected with its positive terminal to pin 8 and its negative terminal to pin 1, 3 or 5, a tone will be produced in the speaker.

To make this circuit into a good Morse practice oscillator, it is necessary only to insert a Morse key into the supply rail from the battery.

However, there is another refinement which you may care to build into the circuit. The tone from the loudspeaker is different, depending upon which of pins 1, 3 or 5 you use. In the prototype, a single-pole changeover switch was used to select the tones from pin 1 or pin 3, and the Morse key would be connected to the circuit via a small jack socket. There is no need for an on/off switch, as the Morse key performs that function. The switch and the jack socket can be seen in the photograph.



Figure 1 Morse oscillator, circuit diagram

The case

Almost any small loudspeaker will do; the higher the impedance the better. The 'impedance' is the figure usually printed on the rear of the speaker magnet. It is a value given in ohms (Ω). For simple circuits like this, you will usually find that the higher the impedance (within reason), the louder the sound it will produce. Speakers from old transistor radios will work, although their impedances can be rather low sometimes.

Any case big enough to house the components and the battery will be suitable. The prototype used a 'Walkman'-type speaker and case, and is shown in the photograph.

To use the circuit, simply attach a 3.5 mm jack plug to your Morse key, and insert it into the socket. Nothing should happen until you press the key, when a tone should be heard from the loudspeaker.

Another application

Try soldering the two wires of a 'twisted pair' to the 3.5 mm jack plug. Touching the wires together produces a tone from the speaker. This simple circuit can then be used as a 'continuity tester'. Touch the two wires to the ends of a fuse. If there is no sound, then the fuse is blown. There are many other such tests you could perform with this device – to check whether there really *is* a connection between one end of a wire and the other, for example.



Warning

You must **never** make such tests on any equipment which is connected to the mains supply, even if it is switched off. If you want to make any such tests, make sure you are supervised by someone who understands what you are doing and is competent to advise and supervise you.

Parts list

Plessey oscillator chip
0.1 μF capacitor (disc ceramic)
Loudspeaker 8 to 25 Ω
3.5 mm jack socket (and 3.5 mm jack plug if needed)
Single-pole changeover switch

The Plessey oscillator chip is available from J. Birkett, 25 The Strait, Lincoln LN2 1JF, tel: 01522 520 767.

John Birkett may also provide a kit of parts (the chip, capacitor and loudspeaker).

69 A bipolar transistor tester

Introduction

This is a circuit which will test normal transistors, i.e. npn or pnp. It has the advantage of being able to test devices while they are still connected in their original circuits. However, when such tests are made, **the circuit containing the transistor under test must not be switched on**.

The circuit and how it works

The circuit runs from a 9 V battery such as a PP3 or six AA-type 1.5 V cells. Alkaline cells are to be preferred, as their electrolyte leakage properties are better. The circuit shown in **Figure 1** uses a single CMOS integrated circuit type 4001 or 4011. CMOS circuits require special handling precautions which are described in the project *Christmas Tree LEDs*, elsewhere in this book.


+9V
S1
IC1 pin 14
Ⓐ Used in text to explain
Ⓑ operation
R5 100R
D1 - D4 1N4148
C1 1µ
R1 5k6
R2 5k6
A
D1
D3
R4 100R
D2
D4
B
R3 100R
8
10
IC1a
9
+
C2 1µ
13
IC1b
12
11
1
IC1c
2
3
5
IC1d
6
4
D5
D6
IC1 pin 7
0V
Base
Collector
Emitter
©RSGB DY229

Figure 1 Transistor tester, circuit diagram

Inside the IC are four logic gates (see *Digital Logic Circuits*) which are all connected as inverters, which means that the output signal is always the logical 'opposite' of the input. The first two gates are connected as an oscillator; the circuit being the same as that used in *An Electronic Die*.

The output of the oscillator, at pin 11, is connected to the input of a buffer stage, IC1c, which helps to isolate the oscillator from the circuit that follows it. The buffer output appears on pin 3, which we shall label as *test point A* for future use. Another inverter, IC1d, follows this, its output at pin 4 being labelled *test point B*.

There are two LEDs connected back to back at the circuit output. These are D5 and D6, D5 being red and D6 being green. Whatever the output of the oscillator at any instant, one of the LEDs must be lit and the other unlit. With point A positive and point B zero, the red LED is lit, when A is zero and B is positive, the green LED is lit. Because the oscillator output is repeatedly switching from one polarity to the other, the lit LED is alternately red and green. They switch between the two colours much faster than we can see, so what we think we see are both LEDs lit together.

The two 100 ohm resistors, R3 and R4, provide the bias to the base of the transistor under test. When A is positive and B is zero, the base-emitter junction of the transistor will be forward-biased, and the transistor will switch on (if it is a working npn type). When the transistor is on, it effectively short-circuits D5 (the red LED) and it extinguishes. When point A is zero and B is positive, an npn transistor will be switched off and the green LED (D6) will light. Thus, for a working npn transistor, only the green LED is lit.

If the transistor under test is a pnp type, it will switch on when A is zero and B positive, thus short-circuiting the red LED (D6). When A is positive and B zero, the transistor is off and the red LED (D5) is lit. Thus for a working pnp transistor, only the red LED is lit.

To summarise, the states of the LEDs indicate the following conditions:

- Both LEDs apparently lit: no transistor connected, or transistor permanently open circuit.
- Neither LED lit: a collector-emitter short-circuit is almost certain.
- Red LED alone: pnp transistor in working order.
- Green LED alone: npn transistor in working order.

Construction

The prototype tester was built on a piece of Veroboard measuring 15 strips by 18 holes. Cut the tracks using a track-cutting tool or a 3 mm (⅛ inch) twist drill, as shown in **Figure 2**. Notice that, in this diagram, there is no


+ve
1
5
10
15
20
A
B
C
D
E
F
G
H
J
K
L
M
N
P
Q
R
Emitter probe and LEDs
−ve
Base probe
Collector probe
R1
R2
R3
R4
R5
C1
C2
D1
D2
D3
D4
Diodes
= Pin
= Link
= Cut in copper track C10, D10, E10, F10, G10, H10, J10, Q7
©RSGB DY230

Figure 2 Transistor tester, component layout

track ‘I’, so try to avoid miscounting when you translate diagram positions to real positions on the board. Hold the board up to a strong light to ensure that there is no copper swarf shorting adjacent tracks together, and that you have made the cuts in the correct places.

Having done this, insert and solder Veropins for all the connections to be made to components not on the board itself. Then solder in the IC holder and the wire links. Then insert the other components in the order resistors, capacitors and diodes D1–D4. Some resistors are mounted vertically so that their connections are on adjacent tracks. Double check the diode polarities – it is easy to make a mistake when wiring diodes in anti-parallel! Next, connect up the off–board components, again making sure that the LEDs have the correct polarity. The probe leads for the emitter, base and collector should be made from different colours of wire and terminated in probe clips (small insulated crocodile clips).

Check carefully for dry joints and errant blobs of solder. Plug the IC into its holder, ensuring that it is inserted the right way round, as shown in Figure 2.

Testing

Without a transistor in circuit, and the battery connected, both LEDs should be lit. Connect a known good npn transistor and verify that the green LED lights. Now simulate two transistor faults: disconnect the base lead and both LEDs should light; remove the transistor and connect the emitter and collector leads together. Neither LED should light.

Repeat the tests with a known good pnp transistor. The results should be the same, except that the correct indication should now be a lit red LED. On your computer, make a small label of the bulleted list above, to fit on your tester showing the states of the LEDs and what they mean. It will act as a useful *aide mémoire* when you use the tester in future.

Using

The circuit will test transistors in isolation or in an existing circuit, i.e. prior to use. You can check the lead identifications in component catalogues such as the Maplin catalogue. The tester is ideal for going through the large bags of unmarked transistors that you can buy for a song at rallies. You can sort them into three piles – npn, pnp and dud!

Parts list

Resistors: all 0.25 watt, 10% tolerance or better

R1, R2	5600 ohms (Ω)
R3, R4, R5	100 ohms (Ω)

Capacitors

C1, C2	1 microfarad (μF) electrolytic, 16 V WKG

Semiconductors

D1–D4	1N4148 general-purpose silicon diodes
D5	Red LED
D6	Green LED

Integrated circuit

IC1	CMOS 4001 or 4011

Additional items

- Veroboard, 15 strips by 18 holes
- Veropins
- PP3 battery and connector (or 6 × AA cells in PP3 clip holder)
- Switch, SPST
- Connecting wire
- One each of known working npn and pnp transistors for test purposes.

Source

Components are available from Maplin.

70 The ‘Yearling’ 20 m receiver

Introduction

Published to celebrate the first anniversary of *D-i-Y Radio*, this excellent receiver design forms a suitable ‘second receiver project’ for those who have successfully completed the MW receivers earlier in this series. The receiver is powered from a PP3 battery or from a mains adaptor, and can be built with the help of an experienced constructor, on a prototype board. The circuit diagram and some of the components used are shown in the separate diagram. Headphones or a loudspeaker can be used and, once the radio is completed, a few simple adjustments will make the *Yearling* spring to life!

Building the receiver

Before starting the constructional process, start by identifying all the parts. One by one, tick them off against the parts list. Are their values correct? The varactor diode is a twin type (see circuit diagram overleaf), and must be cut *carefully* down the middle, producing two devices, D1 and D2, with two wires each.

First, solder the IC sockets, followed by the coils (inductors); L1 is pink inside the top, and L2 is yellow inside. Then, solder in the varactors; the lettering on D1 should be next to coil L1, and the lettering on D2 should face resistor R7. After those, the capacitors, wire links and resistors should be soldered to the board. Take care to wire the voltage regulator, IC3, correctly. Solder in the crystal X1 as quickly and deftly as you can – crystals do *not* take kindly to having their leads bent and being fried with a soldering iron! Make sure that the electrolytic capacitors C2, C12, C15 and C16 are fitted the right way round. Most electrolytic capacitors have only the negative lead marked.

Figure 1 shows the rear of the front panel, illustrating the connections from the board and antenna socket to the controls. All normal connecting wires are 22 SWG or thereabouts, with insulation. Their lengths should be about 15 cm, except for the battery lead to the switch, which is about 8 cm. It is recommended that you use different-coloured wire for each connection to a control. **Figure 2** shows this. The variable resistor section of VR5, the AF gain control, uses single screened cable connected to 0 V (ground) at the

Amateur Radio

D-i-Y

Year


Antenna Socket

Variable Inductor


Crystal


L1
RV1
1k0
lin
1/2 KV1236
D1
C1
180p
Earth
X1....
Crystal – between
8·8 and 9·0MHz
INTEGRATED CIRCUITS
IC1, 2, 4 and 5
8 7 6 5
1 2 3 4
Top view of pins
C2
10μ
C6
100n
+5V
stab
IC1
NE602
C3
47p
C4
100p
C5
180
P
L2
IC2
NE602
IC3
78L
R3
1k5
R4
1k5
C10
330p
L3
10μH
C9
220p
C11
10n
R1
100k
RV2
47k
lin
C7
100n
RV3
1k0
lin
RV4
47k
lin
R2
10k
C8
100n
R9
100k
D2
1/2 KV1236

Resistor


Varicap Diode

Most radio amateurs enjoy building part
is Do-it-Yourself (D-i-Y) Radio, and it is
successfully built yourself. Licensed
allowed (by the Government) to use ho
can see how radio components are dra
circuit diagram for the

D-i-Y Radio, RSGB, Lambda House, Cra

– Do It Yourself

RADIO

rling

Polyester Capacitor

Electrolytic Capacitor


05
R5
100k
IC4a
TL072
2
3
1
8
R6
12k
R8
12k
C13
47n
+9V
IC4b
TL072
5
6
7
4
C15
100μ
16V
S1
+
9V
PP3
−
External
DC power
connector
+
C16
1μ0
16V
RV5
10k
log
+9V
R7
220R
C14
10n
IC5
TDA7052
1
2
3
5
6
8
To
Speaker
+
C12
100μ
16V
Earth
COILS
L1 and L2
4
1
2
6
3
Base view
VARICAP DIODES
Cut here
D1
367
112
367
112
D2
0V
R9
L1
C1
Lettering side
IC3
78L05
+5V
0V
+9V
Base view of pins
EXTERNAL DC CONNECTOR
+
PP3
9V
To S1
To
PCB
Rear view

AF Gain Control

t of their radio stations themselves, this
very satisfying to use a radio you have
d radio amateurs are the only people
me-built transmitters. On this page you
wn on a circuit diagram. This is the full
e *D-i-Y Radio* Yearling.

Fixed Inductor



Integrated Circuit

nborne Road, Potters Bar, Herts. EN6 3JE


VR3
To RV4
To PCB
(+5V stab)
VR2
To PCB
(+5V stable)
To PCB
(0V)
To PCB
(C7)
9V DC
to PCB
To DC power
connector
VR5/SW1
Cable
screen
To PCB
(RV5 ground)
To PCB
(RV5 middle)
To PCB
(C16)
VR4
To RV3
To PCB
(R2)
To PCB
(R9)
VR1
To earth
socket
To PCB
(0V)
To PCB
(L1)
To antenna
socket
©RSGB DY233

Figure 1 Rear view of the variable resistors. Check the connections carefully to make sure the wires fit the correct holes


Red
Green
Yellow

©RSGB DY234

Figure 2 It is helpful to use different colour insulated connecting wires. Wires between each variable resistor and the board should be twisted together to give a neat wiring outfit.

board end. Now fit the ICs into their sockets. Make sure that they are the right way round (see circuit diagram) and that each pin lies directly above its corresponding socket before applying *gentle* pressure with the back of the board firmly supported.

Check that all the connections are correct (don't *assume* this – check the ends of each wire against the circuit diagram) and that all your soldered joints are shiny. Lastly, drill the five 10.5 mm diameter holes for the main controls. On the side of the case, a 6.3 mm diameter hole is needed for the speaker socket, and 8 mm holes for the antenna and earth sockets. The external power socket requires an 11 mm diameter hole.

Adjusting it

Before you can make adjustments, and in order to hear *anything* on your *Yearling*, you will need to connect an antenna (aerial) to the antenna socket. About 8 metres of wire, preferably outdoors and as high as possible, is all you need to connect to the socket. Connect the 3.5 mm jack socket for the speaker, and a 3.5 mm jack to your speaker leads. Connect a battery and switch on.

1. Using a very small screwdriver or, better still, a non-metallic 'trimming tool', *gently* screw in the core of L2 as far as it will go, but *don't force it*. Then unscrew it by three turns anticlockwise.
2. Set VR1, VR2 and VR4 to mid-position and rotate the core of L1 anticlockwise until the hissing noise you hear reaches a maximum intensity. Then adjust L2 for maximum noise.
3. If you now tune carefully with the main tuning control, VR4, you should hear some amateur Single-Sideband (SSB) speech signals. You may have to adjust the bandspread (fine tuning) control, VR3, to make the speech sound normal.
4. Having verified that everything is working, switch off and mount the controls on the front panel and the sockets on the side. To do this, it is much safer to disconnect all the controls and sockets, mount them in their final positions, and then wire them up again.
5. Fit the front panel knobs, connect your aerial and switch on again, checking that everything is working. Then, locate the cluster of CW (Morse) signals to be found at the bottom of the 20 metre band, set the bandspread control to mid-position and slacken off the main tuning knob. Turn the knob (but *not* the control!) until the pointer lies a little clockwise of 14.0 MHz. The SSB signals should now lie roughly between the dial centre and 14.35 MHz. Tighten up the knob.
6. Finally, fix the board to the rear panel, and secure the battery (if you are using one). Attach the rear panel to the back of the box, and you are finished!

Listening!

Make a habit of keeping the bandspread control in its centre position when searching for stations; then you can adjust it either way to make the signals readable. Unless you have a very big aerial, it is best to have the ‘RF Gain’ control, VR1, at maximum. Use the ‘Antenna Tune’ control, VR2, to give the best signal, and control the volume with the ‘OFF/AF Gain’ control. You will find some excellent DX stations with your *Yearling* receiver, and it will serve you well.

Parts list

Resistors (all 0.25 W, 5%)

R1, R5, R9	100 kilohms (kΩ)
R2	10 kilohms (kΩ)
R3, R4	1.5 kilohms (kΩ)
R6, R8	12 kilohms (kΩ)
R7	200 ohms (Ω)

Capacitors (all rated at 16 V or more, tolerance *at least* what is quoted)

C1, C5	180 picofarads (pF) polystyrene 5%
C2	10 microfarads (μF) electrolytic
C3	47 picofarads (pF) polystyrene 5%
C4	100 picofarads (pF) polystyrene 5%
C6, C7, C8	100 nanofarads (nF) or 0.1 microfarad (μF) ceramic
C9	220 picofarads (pF) polystyrene 2%
C10	330 picofarads (pF) polystyrene 2%
C11, C14	10 nanofarads (nF) or 0.01 microfarad (μF) ceramic
C12, C15	100 microfarads (μF) electrolytic
C13	47 nanofarads (nF) or 0.047 microfarad (μF) polyester, 5%
C16	1 microfarad (μF) electrolytic

Variable resistors

VR1, VR3	1 kilohm (kΩ) linear
VR2, VR4	47 kilohms (kΩ) linear
VR5	10 kilohms (kΩ) log with switch

Inductors

L1	Toko KANK3335R
L2	Toko KANK3334R
L3	10 microhenries (μH), 5%

Semiconductors

IC1, IC2	Philips/Signetics NE602 or NE602A
IC3	78L05 5 V 100 mA regulator
IC4	TL072 Dual Op-Amp
IC5	Philips TDA7052 audio amplifier

Additional items

D1, D2	Varactor diode Toko KV1236 (cut into two sections – see text)
X1	Crystal 8.86 MHz type (from Maplin, etc.)
4 off	8-pin DIL sockets for IC1, IC2, IC4 and IC5
2 off	4 mm sockets aerial (red) and earth (black)
1 off	3.5 mm chassis-mounting speaker jack socket
1 off	DC power socket for external supply (if required)
4 off	Red knobs with pointers
1 off	Tuning knob with pointer (e.g. 37 mm PK3 type)
1 off	Printed-circuit board or prototype board
1 off	Plastic case approx 170 × 110 × 6 mm (e.g. Tandy number 270-224)
1 off	Speaker 8–32 Ω impedance (or headphones)

71 Adding the 80 metre band to the Yearling receiver

Background

You will have noticed that your *Yearling* receiver has a dial which shows coverage of the 80-metre amateur band (3.5–3.8 MHz). This band is used for local contacts during the day, and contacts up to about 1600 miles in darkness. Longer distances are possible, particularly in the middle of winter.

The modifications

Only a few extra parts are required, as you may have noticed from the parts list. A low-pass filter, FL1 (one which passes low frequencies and rejects higher frequencies), is switched into the circuit on 80 m. The circuit of the


Antenna
To PCB 'a'
To PCB 'b'
To PCB 'c'
VR1
RF gain control
Cx 100p
S1 switch
Cy 100p
Solder wire links as shown
To earth socket on case
To PCB 'd'
FL1 filter
©RSGB DY235

Figure 1 The circuit diagram shows the extra components for 80 m operation. Note the connections to the PCB ‘a’, ‘b’, ‘c’ and ‘d’


a
b
Cut track here
c
d
©RSGB DY236

Figure 2 The underside of the PCB. Wires are connected from the switch and filter as shown

switch and its connections is shown in **Figure 1**. Before making the modifications, dismantle the receiver so that you have easy (and safe) access to the case and the track side of the PCB.

1. The first thing to do is to drill a 6.5 mm diameter hole in the side of the case into which the switch fits.
2. Then, using a sharp Stanley knife or scalpel, carefully cut the track on the PCB as shown in **Figure 2**, making a gap about 1 mm wide.
3. Using 10 cm lengths of different-coloured insulated wire, make the four connections, a, b, c and d, to the PCB, as shown in Figure 2.
4. Solder the two links on the filter, and then make the connections to the switch, capacitors and PCB. You will have to disconnect the existing wire between the RF gain control, VR1, and pin 4 of L1 on the PCB.
5. Lastly, check your new connections carefully, then mount the switch in the new hole and fix the filter to the bottom of the case with a little glue, as shown in **Figure 3**. Reassemble the circuit, and replace the back of the case.

More testing!

Firstly, switch your new switch, S1, into the 20 m position, to check that the original circuit still works! If you find that the ‘Antenna Tune’ control peaks at a slightly different position, don’t worry.



Figure 3 Internal view of the Yearling case. The filter FL1 is attached to the base with glue

Now switch to 80 m, and tune around the anticlockwise end of the dial; you should hear some SSB stations, particularly in the evenings and at weekends, when may people are on the air. At the other end of the travel of the tuning control, you should hear CW (Morse) stations.

The Radio Society of Great Britain broadcasts amateur radio news every Sunday morning on or about 3.65 MHz; the table below has the details. Finally, a good antenna is more important than ever for 80 metre reception – aim for more height and length, and then consider the project concerned with making an Antenna Tuning Unit (ATU)!

Parts list

Capacitors (all rated at 16 V or more, tolerance 10% or better)

Cx, Cy	100 picofarads (pF) polystyrene

Filter

FL1	Toko 237LVS1110 low-pass filter

Additional items

SW1	2-pole 2-way (changeover) toggle switch
7 off	Short lengths of insulated wire of different colours

The RSGB news broadcasts, GB2RS – Sunday mornings

Frequency (MHz)	*Local time*	*Reception area*
3.650	0900	SE England
3.650	0930	Midlands
3.650	1000	SW England
3.650	1100	Yorkshire
3.640	1130	Aberdeen
3.660	1130	Glasgow

The Midlands transmission is repeated at 1800 (6pm) local time on 3.650 MHz. All frequencies are approximate in order to avoid interference, and use lower sideband (LSB). If you also have a 40 metre receiver, there are GB2RS news broadcasts on 7.048 MHz at 0900 local time from Northern Ireland and from 1100 local time from the north midlands.

72 How the Yearling works

Introduction

The *Yearling* was designed to provide an introduction to *Amateur Radio* on the 20 m amateur band. Let's look at how the different sections (or 'stages') of a radio work, and how they fit together to form a complete receiver. **Figure 1** shows a block diagram which you can follow and compare with the circuit diagram of your *Yearling* receiver.

The antenna (or aerial)

Connected to your receiver, it will pick up not only amateur signals, but all other signals as well! This means that the receiver has to select the one signal that interests you, while rejecting all the others. The following stages do just that.

The RF filter

This stage (centred around L1) selects the band of radio frequencies (RF) containing the signal you want, in this case, those having wavelengths around 20 m. Signals from the 40 m band, for example, would not get through.

The crystal oscillator

This is an oscillator circuit designed around a quartz crystal (X1), and has a very stable frequency. It produces a single, very pure frequency to feed into the mixer. A crystal having a frequency between 8.800 MHz and 9.000 MHz is suitable for this circuit. The oscillator and mixer functions are both carried out inside IC1.

The first mixer

Yes, this stage 'mixes' two signals together. In this case, the two signals are (i) from the aerial via the RF Filter, and (ii) from the crystal oscillator. Two



Figure 1 Block diagram of the Yearling, showing how the various stages fit together to make a complete radio receiver

bands of signals emerge from the mixer. The first is centred upon a frequency equal to the incoming signal frequency **added** to the crystal frequency, and the second is centred upon a frequency equal to the incoming signal frequency **subtracted** from the crystal frequency. Look at an example – if the signal is at 14 MHz and the oscillator at 9 MHz, then the mixer outputs will be 14 + 9 = 23 MHz and 14 – 9 = 5 MHz.

Intermediate frequency (IF) filter

It is the purpose of the IF filter (centred around L2) to select only one of these two bands of frequencies emerging from the mixer. In this case, it is the lower band of frequencies (around 5 MHz) which we select. This is because, in general, lower frequencies are easier to handle than higher ones.

Variable-frequency oscillator (VFO)

The VFO (part of IC2) enables us to tune into a particular station, and operates over a band of frequencies between 5 MHz and 5.35 MHz in this receiver. You will notice that IC1 and IC2 are the same type of chip, so that you will be expecting another mixer stage to be associated with the VFO. You are quite right!

The second mixer

This mixer obeys exactly the same rules as those of mixer 1. Sum and difference frequencies are produced, like this. Mixing is between the incoming IF signals (around 5 MHz) and the VFO signals (around 5 MHz), producing output frequency bands centred upon 10 MHz and 0 MHz. The use of the words ‘band of frequencies’ throughout this explanation is intentional. If all the signals were pure, there would be no bands; the bands are produced because of one thing – the modulation imposed on the pure frequencies at the transmitter. So, the 'bands' contain the one thing that we want to extract from the signal, and that is the speech or Morse code that the signal contains. The band of frequencies at 0 MHz is just that – the audio frequencies we want in the loudspeaker. Because of this, the audio frequency output of the second mixer is selected and passed on for amplification.

The audio preamplifier

Preliminary amplification of the minute audio signal which emerges from the second mixer is provided by IC4a, which will respond only to audio signals, automatically rejecting the 10 MHz signal.

The audio filter

The bandwidth of normal speech when transmitted by an amateur station is around 3 kHz, so there is no advantage to be gained in amplifying frequencies greater than this. IC4b is known as a low-pass filter, because it passes (lets through) lower frequencies and rejects higher ones.

The power amplifier

IC5 produces the final audio amplification and provides enough power (about 350 milliwatts (mW) to drive a small speaker.

How does it work on 80 m?

If you have fitted the 80 m modification to your receiver, you are probably wondering how the circuit works at this different frequency. Firstly, the filter which you fitted selects the 80 m band instead of the 20 m band. The only other slight difference lies in the way the first mixer stage works. Its job is to produce sum and difference frequencies from the incoming signal and crystal frequencies. On 20 m, it did this by subtracting the crystal frequency (9 MHz) from the incoming frequency (14 MHz) to produce an IF output of 5 MHz. On 80 m, the incoming frequency (3.5 MHz) is subtracted from the crystal frequency (9 MHz) to produce an IF output of 5.5 MHz, which is still within the tuning range of the VFO in the next stage.

73 A field strength meter

Introduction

Having a reliable field strength meter is always useful. There are two basic types – the tuned variety (also known as an absorption wavemeter) and the broad-band variety. A project centred on the tuned variety can be found in this book (*An HF absorption wavemeter*), and the way it works is also presented (*The absorption wavemeter*). This project describes an untuned or broad-band type which is every bit as useful as the tuned type, when it is the level of RF in which you are principally interested.

With the possible exception of the meter, you may have all the parts needed in your junk box. The prototype was distinguished by its meter, found at a rally, and marked 'Safe', 'Dangerous' and 'Explosive' on its scale.

How it works

The basic field strength meter uses the circuit of a crystal set, but with a meter replacing the headphones. A better design, which is used here, is that of a voltage doubler, giving more sensitivity. **Figure 1** illustrates the voltage doubler circuit.

The AC input shown will be our RF input, which will be explained soon. Diode D1 will pass the positive half of the signal and use it to charge up C1 to the peak value of the signal. D2 uses the negative half of the signal to charge up C2 to the same value. Because C1 and C2 are in series, the peak voltage appearing across *both* of them (which is the DC output voltage) is equal to *twice* the peak input voltage, hence the name voltage doubler. If you're wondering why DC is present at the output when AC comes in at the



Figure 1 Voltage doubler circuit

input, remember that capacitors pass AC (RF) but block DC; thus the RF is shorted out through C1 and C2, but the steady voltage (DC) remains across the two capacitors. The voltage is thus proportional to the size of the RF signal applied at the input.

The circuit

The voltage doubler is converted into a field strength meter using the circuit of **Figure 2**. A piece of wire serves as the aerial to provide an RF signal across the radio-frequency choke (RFC). A choke is an inductor which is large enough to prevent the RF passing through it – it 'chokes' the RF. This produces the maximum RF signal at the input to the voltage doubler, and the DC output from it is measured on the meter.



Figure 2 Field strength meter

The parts used are not very critical. The RF choke can have any value between about 1 mH and 2.5 mH. Almost any common diode such as the 1N914 or 1N4148 can be used for D1 and D2. The two capacitors could be any value between 1 nF and 100 nF (0.001 μF and 0.1 μF). The meter should be reasonably sensitive, with a full-scale deflection (FSD) in the range 50 μA to 100 μA. Look for VU meters at rallies – these are ideal.

Construction

The prototype circuit was made on matrix board. If you don't want to use pins with the board, simply push the component leads through the holes and make the connections on the underside of the board, either with the excess component leads themselves, or with ordinary connecting wire.

©RSGB DY228



Component side of board shown.
All connections are under board

Figure 3 Board layout and interconnections

Figure 3 shows how the parts are placed and connected. The matrix board can be mounted directly on the meter using its terminal bolts!

In use

Needing no power supply other than an RF signal, just connect it all up and leave it to work! A short length of insulated wire is enough to pick up some RF and display it on the meter. Using a 200 μA meter, about 3 metres of wire gave a good deflection on the meter. To increase deflection, the wire can be wrapped around the aerial lead, provided that the wire is PVC covered and doesn't come into contact with the aerial wire.

This requires a little experimentation. Try a long piece of wire first and adjust its position until the meter needle kicks whenever there is a transmission. It is very reassuring to see the meter moving during a transmission. Although SWR meters also indicate power, they are usually set to read reverse power, and show little or no movement during transmission.

Parts list

D1, D2	1N914, 1N4148 or similar
C1, C2	10 nF disc ceramic
RFC	Miniature axial choke (1 mH)
Meter	Surplus VU meter or similar
Matrix board or similar	

Components are available from Maplin.

74 Preselector for a short-wave receiver

Introduction

A preselector is a simple RF tuned amplifier which is inserted between the aerial and the receiver. It provides some extra gain and may improve the overall performance of the receiver. This project uses a Field-Effect Transistor (FET) amplifier in grounded-gate mode.

The design has a tuned circuit at both the input and output which, with excessive gain and poor construction, would produce only one thing – oscillation! So, to avoid this happening, we will have only a low gain, and use a circuit which provides good isolation between input and output. The grounded-gate FET amplifier fulfils both these criteria. It will also cover a frequency range from about 7 to 30 MHz, which includes most of the HF amateur bands.

The circuit

This is shown in **Figure 1**. The signal from the aerial arrives at an RF transformer, the secondary of which is tuned with capacitor VC1a. The output from the tuned circuit is taken from a tap on the secondary to the source of the FET. The gate is grounded (earthed) and the amplified signal appears at the FET drain, which is then fed to the primary of another RF transformer, which is tuned by VC1b. The output to the receiver comes from the secondary of the RF transformer.


C1
100n
Ant
Rx
L1
L1a
Tap
R2
15R
L2
L2a
R1
270R
s
d
VC1b
250p
VC1a
250p
g
TR1
MPF102
R3
100R
C2
100n
d s g
Twin gang
+9V PP3
via S1
MPF102
L1, L2 = 19 turns 26SWG
on T-50-6 toroid
(tap L1 4 turns from ground)
L1a, L2a = 3 turns
©RSGB DY256

Figure 1 HF preselector, circuit diagram

Notice that the two RF transformers are identical, but they are used 'back to back', with the secondary of the first and the primary of the second being tuned. They are tuned with identical capacitors, fitted on the same shaft of a variable capacitor. We say that the two capacitors are 'ganged'. Because L1 and L2 are the same, and VC1a and VC1b are the same, both RF transformers should be resonant at the same frequency, no matter what that frequency is.

Construction

The final layout should look something like that shown in **Figure 2**. The external connectors and controls being two SO-239 sockets for connection to your receiver and aerial, a tuning control and its associated scale, and an on/off switch.

The circuit can be put together on a plain matrix board, using pins to anchor the components, or simply by pushing the component leads through the board and making connections on the underside. The layout of the prototype is shown in **Figure 3**. Mounting the board to the aluminium box is accomplished with bolts, solder tags and stand-off insulators.

Check your construction against the circuit diagram and against the layout diagram. Wire in the PP3 battery clip, put the switch in the 'off' position, and fit the battery. Testing can be carried out without fitting the top of the box.



Figure 2 HF preselector, front panel layout

Testing

Don't fit your preselector yet. Tune your radio to a broadcast station, preferably a fairly weak one. Disconnect the aerial and fit your preselector between the aerial and receiver. Switch it on and rotate the tuning knob slowly. You should find a position where your original station is received more clearly than before. If it doesn't work at all, recheck your wiring. Is there a positive voltage on the drain of the FET? If not, work back towards the positive battery terminal. Is there a voltage at the junction of L2 and R2? Is there a voltage at the junction of L2 and R3? Is there a voltage at the junction of R3 and the battery lead? If there isn't a voltage at that point, then you have probably mounted your switch upside down, and it is off, not on! It's a common mistake.

Calibration

This is not obligatory, surprisingly enough. However, if having a frequency scale appeals to you, then using an RF signal generator (or using the services of a friend who has one) is the simplest solution. Feed in a weak modulated


VC1
Aluminium box
12 x 9 x 3cm
Perforated
board 5 x 4cm
Tap
VC1a
VC1b
In from
antenna
L1
L2
Out to
Rx
MC
L1a
L2a
MC
C1
R3
R3
C2
d
s
g
TR1
R1
Solder
tag under
– Black
S1
PP3
battery
+ Red

©RSGB DY258

Figure 3 HF preselector, component layout

signal from the generator to the preselector, and rotate VC1 until the signal is maximum. Mark this frequency on your dial. Repeat the process for the frequencies shown on the dial in Figure 2.

If you have a commercial transceiver, feed its output into a dummy load (such as the type described in *A Switched Dummy Load*, elsewhere in this book) using a distinctive modulating signal such as an idling RTTY signal. Set the receiver to the same frequency with the preselector out of circuit. Insert it into the aerial lead, and search for the signal with VC1 until it gives the maximum deflection on your S-meter, then mark the frequency on your dial.

Parts list

Resistors: all 0.25 W carbon film or better

R1	270 Ω
R2	15 Ω
R3	100 Ω

Capacitors

C1, C2	100 nF (0.1 μF) ceramic
VC1	250/250 pF polyvaricon

Inductors

L1, L2	19 turns 26 SWG enamelled copper on T.50.6 toroid L1 has a tap 4 turns from ground end L1a and L2a – 3 turns wound over previous winding

Semiconductors

TR1	MPF102 FET

Additional items

Matrix board	To fit aluminium box (see Figure 3)
Aluminium box	12 × 9 × 3 cm
Battery and connector	PP3 9 V
S1	SPST on/off switch
Knob	As required
SO239	Sockets – 2 required

75 An audible continuity tester

Introduction

This is not the only continuity tester in this book. This alone attests to their use, so you may well want to experiment with several designs, then come up with one of your own! The very simplest form of continuity tester is probably a battery and a bulb in series, with the circuit being closed by connecting it to a fuse or other object being tested for continuity. The bulb could be replaced by a buzzer to give an audible indication. The current taken by the buzzer could damage some components, however. An ohmmeter can also be used, and is very popular for the purpose, as it indicates whether the circuit is low, medium or high resistance. This project has the advantages of indicating whether there is no continuity, some resistance or good continuity, and making an audible sound, so that you don't have to move your eyes from the circuit while making the test.

The circuit

Using only one integrated circuit, four components and a battery, this is a particularly simple circuit, as **Figure 1** shows. IC1 is usually used to flash an LED from a 1.5 V source, and to have a low current consumption. By changing the component values, IC1 is made to oscillate at audio frequencies, and we can hear these through the loudspeaker, LS1. Low-impedance speakers can be used, but result in an increased current drain, so the higher the impedance, the better.



Figure 1 Continuity tester, circuit diagram

Construction

The layout of the circuit on Veroboard measuring 7 strips by 15 holes is shown in **Figure 2**. Start by making the four track cuts which will lie underneath the IC. Use a track cutter or a 3 mm (⅛ inch) twist drill rotated between thumb and forefinger for this. Solder the Veropins in place, followed by the wire link. Then solder in the IC holder, the resistor and the capacitors, making sure that the electrolytic capacitor, C1, is connected the correct way round.

Check, with the board against a bright light, that there are no shorted tracks, either by large blobs of solder or by copper swarf from the track-cutting process. Then insert IC1 into its holder the right way round. The probes can be ordinary connecting wire, the free ends being tinned with solder to prevent wire whiskers from touching components other than the one you are testing.

If you are happy that the circuit and the wiring appear to be correct, fit the battery into its clip. Nothing should happen until the probes are touched together, when you should hear a note from the loudspeaker. If nothing happens, all you can do is to recheck your circuit, as there is nothing else to go wrong!


= Pin
= Link
= Cut in copper track
C8, D8, E8, F8
©RSGB DY260
1
5
10
15
A
B
C
D
E
F
G
H
I
R1
C1
C2
IC1
8
4
5
+
To LS
To battery −ve
To LS and probe
Component side of board shown

Figure 2 Continuity tester, component layout

Any box can be used; there is no justification for a metal case, unless you want to make use of something, which is to hand, such as a tobacco tin. Alternatively, any suitable plastic box will do.

Use

The tester will give different pitch notes for resistances of different values. The higher the resistance, the higher the pitch from the speaker. Try it with small inductors, and you will learn to recognise the different tones produced by the IC.

Safety notice

Using the continuity tester on components *in situ* is not advisable, as the results could be misleading. It can be dangerous to make measurements *in situ* on equipment, which is operating. If you must make such tests, always disconnect the equipment form its power source first.

Parts list

Resistor

R1	1000 Ω (1 kΩ), 0.25 W carbon, 10% or better

Capacitors

C1	10 μF electrolytic, 16 V
C2	0.1 μF subminiature polyester or ceramic

Integrated circuits	
IC1	LM3909N
Additional items	
	Veroboard 7 strips by 15 holes
LS1	64 Ω miniature loudspeaker
	IC holder
	Veropins
	Connecting wire
	Test leads
	1.5 V AA alkaline battery

76 An experimental 70 cm rhombic aerial

Introduction

Most commonly used aerials can be classed as *resonant* or *standing-wave* aerials. There is another class known as *non-resonant* or *travelling-wave*. Resonant aerials, such as the dipole, are narrow-band; this occurs because resonance occurs only over a narrow band of frequencies. Travelling-wave aerials, on the other hand, can operate over a wide band of frequencies.

The *rhombic* is an example of a non-resonant or travelling-wave aerial. It is often employed for fixed commercial and military short-wave radio links. Made with wire, it has a diamond shape when looking down on it from above. The four corners are supported on four masts. It is a very effective aerial, and has good gain, a quality which can be judged from the *polar diagram* shown in **Figure 1**. This has been obtained from a computer program, and so is the perfect shape for a rhombic aerial.

Theory (but only a little)

A polar diagram shows graphically the ability of an aerial to radiate (or receive) more effectively in one direction at the expensive of the radiation in other directions. Figure 1 shows the polar diagrams of two aerials, a simple 70 cm dipole and the rhombic described in this project. The dipole has the



©RSGB DY262

Figure 1 The horizontal polar diagrams of the small rhombic antenna and a dipole compared

well-known figure-of-eight shape, showing a symmetrical angular behaviour about the direction of the aerial and about a direction perpendicular to the aerial. That of the rhombic, on the other hand, is quite irregular by comparison, but is still symmetrical about one axis only, not two. It's this asymmetry that gives the rhombic its gain, by virtue of its *front-to-back ratio*. This is the ratio of the power radiated forwards to that being radiated backwards. Notice the large *lobe* (lump) at the top of the polar diagram; this is the direction in which the aerial transmits best. The lobe in the opposite direction has been reduced significantly, allowing more power to be directed forwards, not backwards

Problems

The rhombic is not found in every amateur's back garden, despite its attractions. To work best each edge of the diamond shape should be about two wavelengths long. Hence, a rhombic for the 20 metre band could be about 80 m from tip to tip! Another disadvantage is that, because of its size, it cannot be rotated.

It will operate well over a range of frequencies. An HF rhombic could work on the 7, 10, 14, 18, 21 and 28 MHz bands. One for the lower VHF frequencies could operate on the 50, 70 and 144 MHz bands.

Its large size is less of a problem at UHF. A portable rhombic can be made for 70 cm which can be used with a hand-held transceiver. The aerial design to be described here will give a gain of up to 9 dB relative to a dipole. This is written as 9 dBd, the second 'd' meaning 'relative to a dipole'. This is equivalent to improving your signal by 1.5 S-points at the receiver or (and you may be surprised by this) by fitting a linear amplifier to your transceiver that would take 5 W input and produce 40 W output to a normal dipole! Consider the relative costs of the two approaches to producing the same received signal. You will also receive everyone else's signals 1.5 S-points better than before!

Unlike the popular Yagi aerial, this design has no critical dimensions and can be folded up for transport by car or bicycle. It has a fairly high input (or feed) impedance, being fed usually by balanced twin feeder. To feed it with standard 50 Ω coaxial cable, a matching transformer in the form of a *balun* is required. A balun will convert the *bal*anced (symmetrical) aerial impedance to the *un*balanced and lower impedance of the coaxial cable. The details of how to build the balun, which in this case is a half-wave transformer, are included in the constructional details.

Construction

The aerial frame is made up of 1 cm × 2 cm strips of wood fixed to a plywood centre using 30 mm long M4 bolts, as shown in **Figure 2a**. The outer bolts fixing the front and side supports can be removed for folding prior to transportation, as shown in **Figure 2b**.

The wires are fixed to the front and rear supports using screw connectors, sometimes called 'chocolate block' connectors. Detail X and Y of Figure 2 show how this is done. The side supports have holes in the ends through which the wire is threaded.

The aerial must be mounted in the horizontal plane using a small shelf bracket attached to the centre plate, using the same bolts that hold the rear support. The other half of the bracket may be mounted to a vertical mast using screws or jubilee clips (hose clips).

The balun

Cut a 23 cm length of coaxial cable; this is to be our half-wave transformer. Cut and remove 2 cm from each end of the sheath. Make the braid into a pigtail at each end. Cut and remove 1 cm of the inner insulator from each


300Ω resistor made from two
600Ω resistors in parallel
(see text)
X
Detail X
Wooden wire
supports
Wire routed
through support
8mm thick
x 210mm square
1mm insulated wire
Y
©RSGB DY255
(a)
Coaxial feeder
to transmitter
Braiding of
coaxial cables
joined together
Coaxial cable
(23cm long)
balun
Detail Y
10 x 20mm
wood
92cm
(x 2)
122cm
(x 2)
(b)

Figure 2 Construction of the UHF rhombic antenna

end, leaving 1 cm of the centre conductor exposed. Fasten this piece of cable to the chocolate block connector together with the coaxial feeder cable as shown in Detail Y of Figure 2. The braids of all three prepared ends are soldered together, but are not connected to anything else. The inner conductor of the feeder from the transceiver is soldered to one end of the centre conductor of the 23 cm piece, and is connected to one end of the rhombic by one side of the chocolate block. The other end of the half-wave transformer also goes to the chocolate block, where it is connected to the other side of the rhombic loop.

The opposite corner of the rhombic, as shown in Detail X of Figure 2, shows that the loop is broken at the chocolate block, and is 'terminated' by two 600 Ω resistors in parallel. This makes the aerial a broad-band travelling-wave device, and gives it its directivity and gain. There is a rule of thumb, which includes a safety factor, which says that the terminating resistor must be able to absorb one-half of the maximum transmitter output power. So, if you use two 2 W 600 Ω carbon resistors (*not* wire-wound resistors) in parallel, you can use a transmitter with an output of 8 W, which is more than adequate for 70 cm hand-helds.

Using the rhombic

Fit the aerial to a pole or mast in the horizontal plane, if you intend to use CW or SSB, but in the vertical plane if you want to concentrate on FM work. In the latter case, a wood or fibreglass pole is mandatory. Tune to a local repeater, whose signal strength you know. Rotate the aerial to face the repeater, and you should see that the signal strength is greatly improved! Verify the directional properties of the aerial by rotating it and observing the changes in signal strength on your S-meter.

77 Water level alarm

Introduction

This is a simple device which, when you have built it, you begin to wonder how you ever managed without it! It will sound a buzzer when the level of water reaches a particular point, which you can set and vary at will.

Detecting water

Water is not too difficult to detect electrically, because it is a conductor of electricity. Not a good one, but sufficiently so to carry enough current to control a warning circuit.

The circuit is shown in **Figure 1**. If you imagine a resistor placed between the ends marked 'water detector', the circuit is then recognisable as a transistor used as an electronic switch. Whether the switch is off or on depends on the value of this resistor. If the resistance is low, the transistor switches on and the buzzer sounds. If the resistance is high, the transistor switches off and the buzzer stops.


Water
detector
WD1
+
6V
buzzer
+V
9V
PP3
−ve
b
c
e
R1
10k
TR1
BFY51
c
b
e
TR1 base
©RSGB DY298

Figure 1 Circuit diagram of the water level detector

Construction

The unit is made in two separate sections – the detector board (**Figure 2**) and the main board (**Figure 3**). The main board is plain perforated board (without copper strips). The components are pushed through holes in the main board and connected together on the underside. The battery is held on with sticky tape. No on/off switch is used, as the circuit consumes virtually no current when it is not sounding the buzzer.

Unlike some buzzers, this type is polarised, and the red lead must go to the supply as shown in Figs 1 and 3.

The detector board is a piece of standard matrix board – the type with copper strips along one side. It measures 9 strips by 15 holes, and is wired in such a way that alternate strips are connected together, as Figure 2 shows. This gives a greater surface area for the water to touch, thus increasing the sensitivity of detection.


©RSGB DY300
1
5
10
15
A
B
C
D
E
F
G
H
I
To main
board
Wire
links
Copper strips on underside of board
Component side of board shown

Figure 2 Layout of the main board


Tie to relieve strain on wires
+ Red
Buzzer
Tape to hold battery
+ve
To detector
−ve Black
TR1
R1
−ve
Perforated board 3·5 x 10cm
9V PP3 battery
Wires under board
©RSGB DY299

Figure 3 Water detector constructed from stripboard

The two boards are connected by ordinary twisted pair, enabling the detector to hang over the edge of the water container, with the buzzer circuit safely out of the way. When positioning the detector board, the left-hand edge (as shown in Figure 2) should face downwards, with the connecting-wire edge facing upwards. When the water level rises, the water causes current to flow between adjacent strips, and the higher the water, the lower the resistance between them. Eventually, the resistance will be low enough to turn on the transistor and sound the alarm.

Parts list

Resistor

R1	10 000 Ω (10 kΩ), 0.25 W

Semiconductor

TR1	BFY51

Additional items

WD1	6 V miniature buzzer (polarised)
	Battery PP3
	Battery connector
	Strip board 9 strips by 15 holes
	Perforated board 3.5 × 10 cm

78 A delta loop for 20 metres

Introduction

HF aerials take up a lot of room when they are straight. Space can be saved by bending them and, at the same time, giving them properties which are quite different from their original linear forms. The delta loops shown in the accompanying diagrams have the shape of the Greek upper-case letter delta (Δ) upside down. It can be upright, except that it is more practical to have the feed point at the bottom than at the top.

Putting the loop together

This is the design for a loop to be used on the 20 metre band. It is a very popular band and carries most of the amateur radio DX traffic. The aerial is light in weight and operates best if the top section is at least 30 ft above the ground, with the feeder point being about 6 ft above ground. All you need is some good wire, some polypropylene rope, some insulators and a method of matching the output of this 75 Ω balanced aerial to the 50 Ω unbalanced coaxial input of your transceiver or receiver.

Each of the three sides must be 7.2 m long. Using tent pegs or six-inch nails, mark out the three corners on the lawn, making sure that each pair of pegs or nails is exactly 7.2 m apart. Put the wire around the nails, together with two insulators on the wire for the two top corners. These insulators can be of the ‘dog bone’ variety, or of the home-made type, using a piece of flat plastic with holes in each end. The use of these is shown in **Figure 1**. Located at the positions of two of the tent pegs or nails, they must be secured at those points by any convenient means.

Now attach a support rope to the free end of each of the insulators, ready for suspension, as shown in the diagrams, from any convenient supports (house, tower, tree, etc.). The top section of the loop could be taped to a continuous piece of rope between the two supports. You might like to try this if you think it is easier. Then, when you find some dog-bone insulators, you can change the design and see if there is any noticeable change of performance.

Connecting to the radio

If you are the proud possessor of an aerial tuning unit (ATU) with a balanced output, all you will need is a length of twin cable soldered to the


Delta loop
Twin 75Ω feeder any length or
18 gauge twin moulded speaker cable
Z match ATU with
twin balanced inputs
Transceiver
©RSGB DY302

Figure 1 Multiband version of the delta loop connected to the ASTU using 75 Ω twin feeder

ends of your delta loop and connected to the balanced output terminals on the ATU, as Figure 1 shows.

Another way is to buy a ferrite-cored 1:1 balun, and use it as indicated in **Figure 2**. This produces an aerial which will operate over the whole range of amateur and commercial short-wave frequencies, when used with an ATU.


Delta loop
Wide band ferrite 1 : 1 balun
50Ω coaxial cable direct to receiver
no tuner required
©RSGB DY303

Figure 2 Multiband version of the delta loop using 75 Ω coaxial cable. This arrangement requires an ASTU if used with a multiband antenna



Figure 3 Single band version of the loop antenna using a coaxial balun. The direction of maximum signal strength is indicated by the arrows

However, since this aerial is designed to be a single-band type, there is a simpler answer to the problem of matching the aerial to your 50 Ω coaxial cable – **Figure 3** shows this. Make a tuned balun with a length of plastic water pipe, 25 cm long and 4 cm diameter and a piece of good-quality TV aerial cable. TV aerial cable has a characteristic impedance of 75 Ω, compared with the 50 Ω of the coaxial feeder that we usually use with amateur radio equipment. Use the type with a brown sheath and a closely knit earth braid, not the type having an earth foil inside the sheath.

The length we need for the balun is 3.8 m, but always allow between 3 and 4 cm extra for preparing the ends. Drill two small holes diametrically opposed in the top of the tube; these will be used to anchor the two ends of the delta loop, as shown in Figure 3. Drill another single hole in the bottom end of the tube, which will be used to anchor a nylon line going to the ground to add stability to the loop. Then, after drilling a pilot hole, drill a 5 or 6 mm hole near the top end of the tube, as shown in **Figure 4**. Prepare both ends of the coaxial cable, then feed one end into the tube, far enough for its ends to be soldered to the ends of the loop when the assembly reaches that stage.

Now, close-wrap the cable around the tube until only about 3 cm remain. Holding the cable tightly, drill another 6 mm hole beside the free end of the cable and feed it into this hole. At this point, feed the two ends of the loop into the top two holes and twist it back on itself. Figure 4 shows how this is done. Then, solder the ends of the coaxial balun to the ends of the loop.


Delta loop wires
Cable ends joined inside the tube to hold coil in place
3·8m cable wound tightly onto former
75Ω television coaxial cable
50Ω radio coaxial cable to receiver
One connection to inner conductor. Join braids together. Insulate inner from braid with insulation tape
Nylon line to ground stake
©RSGB DY305

Figure 4 Construction of the balun

The bottom ends of the balun are then soldered to the 50 Ω coax which goes to your shack and to the transceiver.

Hoist the aerial into position carefully, being careful not to pull too hard on the support lines. Then, take the nylon line from the bottom of the balun to a peg in the ground. This adds stability to the aerial.

Using the delta loop

It is a directional aerial, as Figure 3 shows. It produces maximum power (and has maximum receive sensitivity) along a direction perpendicular to its own plane. Don't be too concerned with which direction it is pointing at first. Give it a try 'on the air' and see how it performs. Then you can contemplate how to point it in your favourite direction, to the USA, or Australia, for example.

Experimenting

You may want to enclose the balun in some sort of weatherproof container. Plastic ice cream containers are favourites for this sort of job. Seal all the holes where wires enter it with silicone sealant or self-amalgamating tape.

If you have used ordinary single-strand or multi-strand wire for your aerial, it will stretch over time under its own weight and that of the balun. Its operating frequency will fall slightly as a result. If you notice a significant difference, then dismantle it, remeasure and fix the sides and erect it again, perhaps facing a different direction. You can buy pre-stretched or hard-drawn wire for such purposes, if you feel that periodic tweaking of your aerial is a chore.

You can make a delta loop for different frequencies simply by scaling the lengths of wire for the loop and for the balun according to the design frequency. If your maths isn't quite up to this, enlist the help of someone well versed either in maths or aerial design!

79 A simple desk microphone

Introduction

A hand-held transceiver is usually the first type used by most novices. It is ideal when used out of doors, in the shack or mobile. However, using one in the shack with an outside aerial is not the best of solutions.

This article describes the design of a desk microphone which can be used either for transceivers using a common microphone and push-to-talk (PTT) line, or for those using a separate PTT line.

It is a simple design, using the barrels of two plastic pens, the lid of an old coffee jar, and the plastic sheath of a DIN plug.

Construction

The end caps and the ink tubes should be removed from two ball-point pens, leaving only the two plastic shells. One of them is used for the vertical microphone support, while the other is used to hold the microphone element.

The vertical support should have the pointed end shaped so that it holds the microphone support at a convenient angle, as **Figure 1** shows.

The base should be prepared next – see **Figure 2**. Four holes are required. Two, A and B, are small holes for the cable to be fed through. A third, C, is slightly larger and is used to take one of the plastic end caps. The fourth hole, D, is determined by the type of switch that you want to use for the PTT function.


Remove
shaded
area
©RSGB DY286

Figure 1 Vertical support made from ball-point pen shell


A and B
for cable
C for
stand
A
B
C
D
All holes
appropriate
D for
PTT
©RSGB DY287

Figure 2 The microphone stand base

Some epoxy resin such as Araldite Rapid is used to mount the separate parts. Mix only a small amount at a time, and glue each part of the base assembly and allow to harden before moving on. Be sure to read and follow the instructions for the use of the glue to prevent accidents.

Firstly, glue the end cap to the base, feeding it underneath and pushing it up through hole C. Then, the vertical pen body is placed over the protruding end cap and glued into place, making sure that the top (shaped) end is pointing in the right direction to hold the other plastic tube carrying the microphone. While the glue hardens, place the DIN plug sheath on the second pen body. Place and glue this pen body on the shaped top of the vertical support, making sure that the whole assembly is supported while the glue sets. What you should have now ought to resemble **Figure 3**, but without the microphone and wiring. Leave everything to set for 24 hours.

Any switch of the press-to-make variety can be used for your PTT switch, but choose one which does not apply too much force to operate! If you find the whole assembly is too light and slides over your table, some plasticine can be pushed into the base when all the wiring has been completed.


Old DIN plug body housing microphone
Screened cable to microphone
PTT switch
End cap
To set
©RSGB DY288

Figure 3 Complete microphone stand assembly

The circuit

A small electret condenser microphone is used, powered by a DC supply. Most hand-held radios use a single screened lead for both the PTT line and the microphone audio lead. In such cases, the circuit of **Figure 4** will operate the PTT function. Note that the PTT switch is in series with the audio lead from the microphone. If you find that the PTT switch does not switch your radio into transmit, reduce R1 from its normal value of 33 kΩ to 27 kΩ. You should find that the original value works with most hand-helds.



Figure 4 Wiring diagram for hand-held radios

For radios with a separate PTT lead, the circuit of **Figure 5** is used. However, a power supply is needed for the electret microphone. This can be a PP3 battery, or can (in most cases) be derived from the microphone socket on the transceiver. You will need to consult the makers' handbook for this information. Figure 5 shows the PTT switch wired in a 'ground-to-transmit' configuration, which is correct for most base-station transceivers. If you're in any doubt about what your radio needs, consult an experienced friend.



Figure 5 Wiring diagram for radios which use separate PTT lines

The last connections

The microphone element should be connected with screened cable. Tape (masking or insulating) should be wound around the electret insert until it is a snug fit inside the DIN plug sheath. Feed the screened cable through the barrel of the pen until it emerges from the far end. Poke it through hole B and make the connections under the coffee jar lid. The components can all be mounted on the PTT switch or on a small piece of Veroboard mounted under the top surface. The output lead emerges through hole A and is of sufficient length to reach your transceiver. A suitable plug needs to be fitted to it.

Parts list

Resistors: all 0.25 W carbon, 5% tolerance	
R1 (Figure 4)	33 000 Ω (33 kΩ)
R1 (Figure 5)	1000 Ω (1 kΩ)
Capacitors	
C1 (Figure 4 and 5)	0.1 microfarads (0.1 μF) disc
C2	10 microfarads (10 μF) electrolytic
Additional items	
S1	Push-to-make
Mic	Electret microphone (Maplin type FS34W)
Screened cable	As required
Plug	As required by your radio
Veroboard	If required
PP3 battery and clip	If required
Two old plastic ball-point pens	
Lid of coffee jar	
Plastic sheath from DIN plug	
Araldite or similar epoxy resin glue	

80 Morse oscillator

Introduction

This is not the simplest Morse oscillator to build, but it differs from the simple circuits in that it produces a pure note, not a coarse, rasping sound. People who have practised Morse using a non-sinusoidal oscillator sometimes find that they have trouble copying Morse code with a pure tone. As the pure tone is the correct way to receive Morse code, it is important that you should learn to listen to the code from a pure oscillator – so here's one!

The twin-T

There are many oscillator circuits, and there are many variations of the twin-T oscillator that we are going to use. **Figure 1** shows one version of a very useful circuit. All oscillators must have positive feedback in order to work. The feedback determines the frequency of the note produced by the oscillator.



b
BC109
e
c
R4
10k
Key
(via socket)
S1
+9V
PP3
TR1
BC109
R1
18k
R2
18k
C1
10n
C2
10n
C7
22μ
nc
4
7
6
2
IC1
LM386
5
3
8
1
C9
220μ
C4
100n
R3
4k7
C3
47n
RV1
10k
log
pot
(vol)
C5
22n
C6
10μ
C8
100n
R5
10R
LS
8Ω
©RSGB DY312

Figure 1 Circuit diagram of the sinewave oscillator and amplifier

Here, the feedback circuit looks like two letter Ts. If you look at Figure 1, one T is formed by R1, R2 and C3, the other by C1, C2 and R3 – hence the name ‘Twin-T’. Notice that the two Ts are connected in parallel between the collector and base of TR1, so any signal appearing at the collector is fed into both Ts. What emerges is then fed back into the base, producing in turn a signal at the collector. And so it goes on, producing a sine wave output.

The oscillator output is fed into an integrated circuit amplifier for output via a small loudspeaker.

Putting it together

The prototype was constructed on plain matrix board (the type *without* the copper strips), as shown in **Figure 2**. The components have their leads pushed through the holes in the board, and connections are made underneath.

Build the amplifier circuit first, using a socket for IC1. Connect the 9 V supply and touch pin 3 with an ordinary piece of wire. If a buzz is heard from the speaker, all should be well. If not, check your circuit and make changes until it does.

Build the oscillator circuit, and connect its output to the volume control VR1 via C4. Set VR1 half-way along its travel and switch on. A note should be heard from the speaker when the Morse key is depressed. The component values making up the twin-T determine the frequency of the note. Try varying them if you think your note is too high or too low. Whatever changes you make, either to the resistors or the capacitors, always ensure that R1 = R2 and that C1 = C2.


Plain perforated board 3·5 x 9cm
To +9V via key socket
To +9V via S1
------- Wires under board
R4
C7
C2
nc
8 7 6 5
C1
R1
R2
C6
IC1
C8
C9
LS
R3
C4
1 2 3 4
C5
R5
C3
6BA solder tag
Earth wire 24SWG tinned copper wire
RV1 (top)
RV1 (wiper)
RV1 (btm)
LS
©RSGB DY313

Figure 2 Component layout and interconnection diagram

Parts list

Resistors: all 0.25 W carbon film

R1, R2	18 000 ohms (18 kΩ)
R3	4700 ohms (4.7 kΩ)
R4	10 000 ohms (10 kΩ)
R5	10 ohms (10 Ω)

Capacitors

C1, C2	10 nF (0.01 μF)
C3, C8	47 nF (0.047 μF)
C4	100 nF (0.1 μF)
C5	22 nF (0.022 μF)
C6	10 μF electrolytic, 16 V WKG
C7	22 μF electrolytic, 16 V WKG
C9	220 μF electrolytic, 16 V WKG

Semiconductor

TR1	BC109

Integrated circuit

IC1	LM386

Additional items

VR1	10 kΩ log potentiometer with switch
LS	8 Ω loudspeaker

Matrix board 3.5 × 9 cm
Small jack socket for key input
Box
PP3 battery and clip

81 A simple 6 m beam

Introduction

The attraction of building your own aerials is an abiding feature of our hobby. You can *buy* almost any shape or size of aerial, but one you have made yourself can often work every bit as well as a commercial device costing ten times as much.

The design

This aerial, designed for use on the 6 m band, is essentially a two-element Yagi, with the elements bent in order to reduce the physical size. It is known


Total length of reflector 3 m
Elements fixed to spreaders using plastic insulating tape
Insulator A
Insulator A
Tail (see text)
Tail (see text)
Coax to Tx
Total length of driven element 2·98m
Feed point insulator B
©RSGB DY310

Figure 1 Plan view of the complete 50 MHz VK2ABQ antenna

as the VK2ABQ beam, and was designed originally for the 20, 15 and 10 m bands, principally because of its space-saving qualities. It is made using a wooden frame and wire elements, and is ideal for portable operation.

Tools ready?

The beam is shown in **Figure 1**. The driven element is the one whose centre is fed by the coaxial cable, and lies between the two insulators marked A and the feedpoint at B. The reflector is also anchored at the points A, and lies over the upper half of the frame.

The wooden centrepiece is used to support the cross-pieces and to mount the aerial on the mast, using a common shelf bracket. The cross-pieces, known as *spreaders*, can be wooden canes or dowelling, and are mounted to the centrepiece using cable clips and adhesive. **Figure 2** shows how this is done.

If the aerial is to be a permanent installation, the spreaders should be weatherproofed using a good-quality exterior varnish. The wire elements are PVC covered and fed through holes in the spreaders.



Figure 2 Centre support piece

©RSGB DY309

The end insulators are made of drilled perspex, and the wire passed through the two holes and twisted, as shown in **Figure 3**.

Note: if you have not drilled holes in perspex before, take care! The drill bit must be well-lubricated because it generates a lot of heat (enough to melt the perspex and jam the drill). Never turn the drill for more than a few seconds at a time, and moisten the bit in between. Start with a pilot hole and use bits of increasing size until the hole is the size you want.

Another perspex insulator is used to secure the feeder to the aerial, as shown in Figure 3. The feeder then passes directly to the centrepiece, where it is fastened with a cable clip and then passes down the mast.


1cm
1cm
2cm
1·6mm dia hole
Side view showing how wire is fixed
Insulator A
2cm
To transceiver
4·5cm
1·6mm dia hole
1cm
Top view showing connections
Insulator B

©RSGB DY311

Figure 3 Details of insulators

Adjustment

The driven element (A–B–A) in Figure 1 is fixed to the end insulators in such a way as to have 'pigtails' which are about 10 cm long. Using an SWR meter between the aerial and the transmitter, trim the pigtails equally at each end for minimum SWR in that portion of the 6 m band in which you plan to work. Make sure that the transmitter is off when you trim the ends, as high voltages can be present there. Always listen on the frequency before you transmit and, when you do, ask if the frequency is in use and identify yourself. Use as little power as possible.

The prototype had an SWR of 1.2 at 50.2 MHz and performed well. If you look at Figure 1, which is a view of the aerial from above, you will immediately see that when the aerial is horizontal, it radiates with horizontal polarisation in a direction from the top of the page to the bottom. A metal pole or mast can be used for horizontal polarisation, but if you intend to use the aerial for vertical polarisation, it is much better to use a wooden or fibreglass pole.

Portable use

If you plan to operate portable with this aerial, the only real modifications you need are to the centrepiece and how it supports the spreaders. Instead of using glue and cable clips, nuts and bolts through the spreaders and centrepiece would allow the spreaders to be 'hinged' closed for transport.

Materials

Centrepiece	Hardwood, 15 × 15 × 25 mm
4 spreaders	110 cm long (cane or 6 mm dowel)
Wire	1.5 mm PVC-covered copper
50 Ω coaxial cable	RG58 or similar
Cable clips	6 mm (12 off)
Varnish	Polyurethane for waterproofing
Tape	Self-amalgamating, to waterproof all soldered joints
Insulators	See text

82 An integrated-circuit amplifier

Introduction

A simple audio-frequency amplifier is a very useful building-block in many more advanced electronic circuits. It is also a very useful piece of test equipment. To have one spare in the shack can be a life-saver at times.

Planning

Get into the habit of planning your project. How do you want it to look when it is finished. Do you want it in a box? Do you want it 'open-plan', with all the components on view?

The 'minimalist' approach to any project is simply a front panel and a baseboard, on to which all the components are fitted. In this case, the front panel would accommodate the loudspeaker, the volume control and the input and output jack sockets, and the baseboard would support the circuit board. Once you have decided these things, and know the size of the board, speaker and volume control, you can decided how big the panel and baseboard should be.

The amplifier

Instead of building the amplifier from discrete components (i.e. transistors), as was done in the project *An audio-frequency amplifier* (which you will find elsewhere in this book), we are going to use an integrated-circuit (IC) amplifier. External resistors and capacitors are still needed but, compared with the number of components *inside* the chip, these are very few indeed!

The IC we are going to use is the TBA820M. The circuit may look complicated, but with the use of a matrix circuit board it becomes quite simple. **Figure 1** shows the circuit diagram and **Figure 2** the layout on the board. The external connections to the PCB are shown in **Figure 3**.

To avoid having a separate switch to switch off the power supply when the amplifier is not being used, a volume control which incorporates a switch is used.


+
12V
–
C7
680p
R4
51R
C5
0µ1
Input
from
volume
control
6
3
1
7
TBA
820
5
2
8
IC1
4
+ C1
100µ
+
C3
220µ
L/S
R1
10k
R2
120R
+
C2
100µ
+
C4
47µ
R3
1R
C6
0µ1

©RSGB DY331

Figure 1 Audio amplifier, circuit diagram


Input
L/S
+12V
100µ
0µ1
120R
220µ
10k
100µ
56R
680p
220µ
47µ

©RSGB DY332

Figure 2 Audio amplifier, component layout

©RSGB DY333


To battery
positive connection
Volume
control
VR1
To battery
negative connection
Input
AF amp
PCB
+ supply
Input from
earlier stages of
the receiver
Speaker

Figure 3 Connecting the circuit board to the speaker, volume control/switch and battery

What power supply?

If the amplifier is to be used only for short periods, as a test instrument, for example, then it can be run from a PP3 battery, which can be mounted on the baseboard. If you intend to use it often, then a connection to an external power supply is preferable. For this option, you may want to consider fixing two terminals to the baseboard for this connection.

83 A novice ATU

Introduction

Having an aerial tuning unit (ATU) is always useful. It is used for adjusting the aerial impedance, as 'seen' by the transceiver, to be the same as that of the transceiver itself, usually 50 Ω. This process is called *matching*, and ensures that the receiver and the power amplifier (PA) stage of the transmitter work efficiently.

This design is due to the late Doug DeMaw, W1FB, and uses readily available components. It will handle up to about 5 W, and operates over the frequency range 1.8 to 30 MHz.

Circuit evolution

The basic circuit of one type of ATU is shown in **Figure 1**. On transmit, the input signal at L1 is coupled into L2, which forms a resonant circuit with C1. The signal across the resonant circuit is fed to the aerial by C2. The combination of L2 and C1 helps to remove signal harmonics, because they are not at the resonant frequency and are shunted to earth. On receive, only those signals which are within the pass-band of L2 and C1 will pass into the receiver. This improves receiver performance by rejecting many out-of-band signals which the simpler receiver doesn't like.



Figure 1 Basic circuit of the ATU

For this design, the all-important resonant frequency is chosen to be in the 80 metre band. If we want to make the circuit operate on other bands, we need to change either L2 or C1. It is easy to change L2 by using a set of switched inductors (L3–L5) as shown attached to S1 in **Figure 2**. Forget about S2 and L6 for the moment.



Figure 2 L6 added for 160 m

When S1 is in position 1, the circuit reverts to that of Figure 1. S2 should be brought into circuit only when S1 is in position 1. Looking at the way the circuit is drawn, you can see that when S2 is in position 2, we have two coils in series, which is equivalent to adding more turns to L2. More turns means more inductance, which lowers the resonant frequency still more, and gives coverage of the 160 m band.

Rather than having to remember to flick S2 to the correct position *and* move S1 to position 1 when we want to operate on 160 m, both functions can be combined into one rotary switch with two wafers. This circuit is shown in **Figure 3**.


L6
2
3
4
1
S1b
Input
L1
L2
C1
C2
Output
1
S1a
4
2
3
L3
L4
L5
©RSGB DY325

Figure 3 Two-pole switch for all bands

In all positions of S1a *except* position 1, the extra coil, L6, is shorted out. The two halves of the switch, S1a and S1b, move together, as the shaft is turned, so both halves are in position 1 at the same time, position 2 at the same time, and so on. The two switches, S1 and S2, are said to be *ganged*.

Construction

L1 is formed by winding four turns of 22 SWG enamelled copper wire over L2, as in **Figure 4**. L2 already exists on the purchased former. After scraping the enamel off the ends of the wire (with a sharp knife or sandpaper), one end of L1 must be soldered to one end of L2, as shown in Figure 4. The free end of L1 goes to the transceiver aerial socket.

All components except the capacitors are assembled on the switch. Note that the rotor of C1 is earthed, but neither side of C2 is earthed. This means that the metal shaft of C2 is not earthed, and touching it will detune the ATU. Using a plastic knob for C2 will minimise this effect. If you decide to use a metal box, take precautions to ensure that no part of C2 is in electrical contact with the box.


L1
(4 turns of
22SWG wire)
To input
socket
L2
(as purchased)
L1 connected
to L2 here.
This is now
the earth end
for both coils
This pin
to S1b
©RSGB DY326

Figure 4 L1 is wound over L2 as shown

The capacitors are mounted using M2.5 screws. Make sure that the screws do not foul the vanes of the capacitor. If your screws are too long, a few washers between the box and the capacitor will solve the problem!

In use

The best indication of a good match is obtained with a standing-wave meter between the ATU and the transceiver. The controls are adjusted alternately to ‘feel’ your way to a better and better match.

For receive-only use, the same alternate adjustments are used, watching for the maximum signal strength on the S-meter or, for a very weak signal, making the signal from the loudspeaker as large as possible.

Parts list

Capacitors	
C1, C2	350 pF variable
Inductors	
L1	See text
L2	27 μH
L3	10 μH
L4	2.2 μH
L5	1 μH
L6	65 μH
Additional items	
SO239 sockets (2 off)	
S1	2-pole 6-way rotary
Box	as required
Plastic knobs (2 off)	
Stick-on feet (4 off)	
M2.5 screws for capacitors	
Screws, nuts and washers for mounting the input and output sockets.	

84 CW QRP transmitter for 80 metres

Introduction

This is a relatively simple transmitter design having an output of 1 W. The design is not new, having been described before in other amateur radio publications. The components are all available new and the total cost should not exceed £15.

The circuit

Like other simple transmitters (see *An 80 Metre Crystal-Controlled CW Transmitter* and *A Breadboard 80 m CW Transmitter* elsewhere in this book) this one is crystal controlled. This assures frequency stability, but limits the usefulness of the transmitter. The key to increased frequency coverage without a conventional Variable Frequency Oscillator (VFO) is the use of a low-cost 3.58 MHz *ceramic resonator*. The 'pulling' range of a 3.58 MHz ceramic resonator covers the UK novice 80 m sub-band and some of the CW segment below 3.525 MHz.

A ceramic resonator is like a crystal, but not quite as stable in frequency. Its main advantage is its large pulling range.

The block diagram is shown in **Figure 1**. It is very similar to a crystal-controlled transmitter, and includes an oscillator, buffer and final amplifier.


©RSGB DY340
+12V Tx
Tx
Rx
+12V DC
BC640 transistor switch
+12V
key down
4069
3·58MHz
Oscillator
Buffer
VN10KM power amplifier
Tx
Rx
Antenna
1·5W out 3·5MHz
To receiver
Ceramic resonator
Frequency adjust

Figure 1 Block diagram of the ceramic resonator controlled 80 m CW transmitter

This amplifier is keyed, the oscillator remaining running all the time. This improves frequency stability because the oscillator is not being continuously stopped and started by the key. It is switched off while receiving, though, to avoid interference with the received signal. Transmit/receive switching is accomplished by a panel-mounted switch controlling both the aerial, oscillator and buffer switching.

Figure 2 shows the transmitter circuit diagram. An unusual aspect of this transmitter is the use of a digital CMOS integrated circuit (IC) type 4069 for the buffer and oscillator stages. The IC houses six inverters, four of which are used in the circuit. One is used as the oscillator, two are used for the buffer stage, and the fourth provides an output for a direct-conversion receiver, should one be added at a later date.

The frequency of the oscillator is changed by varying the capacitance in the ceramic resonator circuit. This is provided by VC1.

The power amplifier (PA) is a small MOSFET (metal oxide semiconductor field-effect transistor), TR1. This is capable of providing an output power of 2 W but, in this circuit, it is run conservatively to give 1.5 W. The output can be varied by changing the resistance (R5 + R6) in the gate circuit. Attempts


©RSGB DY341
1
14
4069
7
8
VN 10k
s g d
BC 640
e c b
6V8
To direct conversion receiver (see text)
O G A
Variable capacitor connections
R
x
12V
6·8V regulated
y
T
S1a
R3 270R
C1 100n
D1 6V8
C6 10n
c
e
C10 10n
R5 1M5
TR2 BC640
Key
C4 1n
1
2
3
14
4
11
10
7
IC1 4069
b
R7 1k
C11 100n
Rx
R1 10M
9
8
RFC2 10μH
R6 1M5
R
Ant
XC1 3·58MHz
R2 2k2
C5 10n
d
5
6
g
s
C7 100n
RFC3 2·2μH
T
S1b
RFC1 8·2μH
TR1 VN10KM
13
12
R4 1M
C8 560p
C9 820p
C2 100p
C3 47p
VC1 10-160p
Oscillator
3·518 - 3·558MHz
Buffer
Power amplifier
Pi network

Figure 2 Circuit diagram of 80 metre transmitter

to raise the output power by decreasing the values of these resistors may result in immediate MOSFET failure.

A pi-network (C8, RFC, C9) provides impedance matching to 50 Ω, together with harmonic suppression. Like all inductors in this transmitter, the pi-network inductor is a pre-wound RF choke. A pi-network is so called because the components are arranged in the shape of the Greek letter pi (π).

Keying is carried out by a pnp transistor switch, TR2. Closing the key earths the base and supplies 12 V to the collector of TR2 and to the drain of the MOSFET, TR1, allowing the PA to operate.

Construction

You must house your transmitter in a metal box, to avoid hand-capacity effects and the radiation of spurious frequencies. Size is not important, provided it is large enough to accommodate the transmitter without cramping the components. You may want to allow space for future additions such as a direct-conversion receiver, break-in keying, sidetone or a small power amplifier. A good size is 5 × 15 × 15 cm. You can make your own box, buy it, or even use a biscuit tin!

Front and rear panel connectors can be fitted first. The choice of these is a personal matter, but a good working choice would be:

(a) Power socket – 2.1 mm panel socket – centre pin positive.
(b) Key socket – ¼ inch jack socket.
(c) Aerial and receiver connectors – panel-mounting SO239 type.

Particular attention must be paid to the mounting of the variable capacitor, VC1. Make sure the hole for the shaft is amply big enough, and if you use screws to mount the capacitor on the front panel, then make sure they are not too long, otherwise they will touch the vanes of the capacitor! Mounting can be by means of glue, sparingly applied and kept well away from the shaft.

A board size of about 6 × 10 cm is adequate. Component layout on the board is suggested in **Figure 3**. The prototype used ordinary matrix board, which is preferable to stripboard for a design like this; stripboard has undue capacitance between adjacent strips. Component leads are fed through holes in the board and are connected underneath. Make sure that leads and connections are rigid because, if they can move, there is always the danger of short-circuiting, and capacitance changes.

To facilitate construction, servicing and testing, it is advisable to use Veropins for connections to the variable capacitor, transmit/receive switch,


Matrix board 6 x 10cm
T/R switch
y
x
BC640
e
b
c
12V
100p
3·58MHz
ceramic
resonator
10M
1
6V8
100
n
270
R
1M5
1k
100n
10n
Key
socket
100n
10μH
47p
2k2
1n
1M5
2·2μH
T/R switch
8·2μH
g
d
4069
10n
s
10n
VN10KM
1M
560p
820p
O
G
A
Frequency
adjust
● Solder joint
● PC circuit board pin
©RSGB DY342

Figure 3 Component layout of the 80 metre transmitter. The transmit/receive switch is not mounted on the board and is not shown in this diagram

aerial and power sockets. Use screws and spacers to mount the circuit board to the box. Mounting the board horizontally assists troubleshooting.

Use a socket for the IC, and observe the CMOS handling precautions given in *An Electronic Die*, elsewhere in this book. When soldering the leads to the ceramic resonator, do it quickly – excessive heat damages the device. The earth lead running acoss the bottom of the board must be connected to the metal case by a short length of stout wire.

Testing

After carefully checking your wiring, both against the circuit diagram and the layout diagram, it is time to test your circuit. You will need a multimeter, an 80 m SSB receiver and a 50 Ω dummy load. A good design of dummy load can be found in the project *A Switched Dummy Load*, also in this book. An RF power meter and frequency counter will also be useful, although if your receiver has a digital frequency readout and S-meter, the latter two items are not really necessary. You will also need a 12 V 1 A power supply unit (PSU) to power the transmitter.

Switch the transmitter to receive and switch on the transmitter. No current should be consumed. Switch to transmit and check that pin 14 of IC1 is 6.8 V positive. With the dummy load connected to the aerial socket, press the key. The voltage on TR2 collector should now be 12 V, dropping to zero when the key is released.

Now check the operation of the oscillator. In transmit mode, you ought to be able to find a strong carrier signal with the receiver, even though the dummy load is connected. Adjusting the variable capacitor should change the frequency. At the lower end of the frequency range, you may find that the oscillator is unreliable in starting, because the circuit is attempting to pull the resonator too low in frequency. If this is the case, set the trimmer at the back of VC1 to minimum capacitance. If your version of VC1 has two trimmers, and you don't know which one to set, set them *both* to minimum capacitance. If there is still a problem, reduce the value of RFC1 to 6.8 or 4.7 μH.

In all probability, the unmodified circuit of Figure 2 will not require any of the changes outlined here. A coverage of 3.518 to 3.558 MHz should be possible, while preserving good frequency stability and reliable oscillation.

A signal probe (see *An RF Signal Probe*, elsewhere in this book) is useful for checking the operation of the oscillator and PA. Alternatively, an RF power meter or the receiver's S-meter can be used. With the PA running, the unit should draw between 200 and 300 mA. If TR1 becomes too hot to touch after a few seconds of transmitting, increase R5 or R6 to limit the transistor's heat dissipation. A small 6.3 V bulb connected across the aerial output is a simple way to check that the PA is working. An orange/white glow when the key is pressed is indicative of correct operation.

The final test is to monitor keying 'quality'. With your dummy load connected, press the key and listen to the note on the receiver's loudspeaker. Then operate the key, sending a string of dits, for example. What you hear should be free of chirps and clicks, as well as being stable in frequency. This test is sometimes better performed with no aerial connected to the receiver, thus preventing receiver overload and its associated plops. No problems should be encountered here.

Frequency tuning

A peculiarity of ceramic resonators is that, every now and again, their frequency changes abruptly by 100 Hz or so, then remains stable for some time. This is certainly noticeable in the received signal, but does not detract from the QSO and no characters are lost as a result. Try to keep the area around the ceramic resonator cool, to avoid temperature variations.

Parts list

Resistors: all 0.25 W, 5% tolerance

R1	10 megohms (MΩ)
R2	2200 ohms (2.2 kΩ)
R3	270 ohms (270 Ω)
R4	1 megohm (1 MΩ)
R5, R6	1.5 megohms (1.5 MΩ)
R7	1000 ohms (1 kΩ)

Capacitors

C1, C7	100 nF
C2	100 pF
C3	47 pF
C4	1 nF
C5, C6, C10	10 nF
C8	560 pF
C9	820 pF
VC1	10–160 pF variable

Inductors

RFC1	8.2 μH
RFC2	10 μH
RFC3	2.2 μH

Semiconductors

IC1	4069
TR1	VN10KM
TR2	BC640
D1	6V8 Zener

Additional items

Matrix board (see text)
14-pin DIL socket
Pointer knob
Sockets (see text)

85 An audio booster for your hand-held

Introduction

The audio output from many hand-held transceivers and receivers usually leaves much to be desired, so this little amplifier was designed to increase the output at minimal expense.

All that is needed is a separate amplifier and bigger loudspeaker. This is accomplished using a single integrated circuit (IC), a few components, and a loudspeaker from the junk box. This circuit will enable the output from your hand-held to be heard easily in a car.

The circuit

This is shown in **Figure 1**. It uses only those components necessary to operate the IC amplifier. VR1 is the preset volume control, and varies the signal coming from the 'External speaker' jack on the hand-held before feeding it into the IC for amplification. C1 blocks any constant voltage present on the input.


TDA 2003
5
4
3
2
1
R4
470R
Red
LED
Input from handheld radio
+12V
C5
220n
C6
100μ
25V
3 amp fuse
On/Off switch
VR1
1k0
C1
10μ
25V
1
2
5
4
3
IC1
TDA2003
C4
1000μ
25V
R1
15R
1W
R2
220R
C3
220n
C2
470μ
25V
R3
2R2
Speaker
4R (6W)
−ve

©RSGB DY376

Figure 1 Circuit diagram of the audio amplifier. The power is derived from the cigarette lighter socket and the fuse is in-line with the lead

The IC output comes from pin 4 and is fed via the electrolytic capacitor, C4, to the loudspeaker. The circuit is provided with an on/off switch, fuse and LED to indicate when the circuit is switched on.

Construction

The box is made of aluminium. This is necessary to help to dissipate some of the heat generated by the IC. Do not build the circuit inside a plastic box unless you take special precautions! The IC has a metal mounting tab with a hole, specifically designed to be mounted to a metal box or other metal heat sink. Apply plenty of heat sink compound between the tab and the box, tighten the nut and bolt, and then wipe off any excess compound. The box will get slightly warm in operation.

The size of the box is not specified. You may want to decide on this when you find a loudspeaker. Choose one which will be able to handle 6 W


Heat sink
TDA 2003
1 2 3 4 5
Wires under perforated board
Plain perforated board 4cm x 6cm
Input screen lead
+12V (C6 & fuse) (LED & On/Off switch)
R1
C1
C3
C5
C4
VR1
R2
C2
R3
To speaker
Solder tags underside
−ve
©RSGB DY377

Figure 2 Layout of the components within the box

output. Drill all the holes in the box first. Holes for the speaker, input phono socket and the LED. The amplifier can be constructed on ordinary matrix board, which can be mounted inside the box with screws and spacers.

The layout is shown, for your guidance, in **Figure 2**. The components are mounted by pushing their leads through the holes in the board and making connections on the underside. The preset volume control, VR1, is set such that the hand-held's volume control is sufficient to control the final output over a good volume range. Use a screened lead from the 'External speaker' jack socket to the phono plug.

An external power supply is needed for this circuit. The normal dry battery which we usually use for small projects in this book will *not* work here, so you will need a proper mains power supply producing a stabilised 12 V. If you are going to use the unit principally in a car, then the cigar lighter socket can supply this voltage easily. Do make sure that the polarity is correct before you switch on!

When you plug the jack plug from your booster into the 'External speaker' socket on your hand-held, its internal speaker will be muted, so don't think that something dire has gone wrong! Adjust VR1 for a good volume range on your booster, when the volume control is turned on the hand-held.

Parts list

Resistors: all 0.25 W, 5% tolerance, unless otherwise stated

R1	15 ohms (15 Ω) 1 W
R2	220 ohms (220 Ω)
R3	2.2 ohms (2.2 Ω)
R4	470 ohms (470 Ω)
VR1	1000 ohms (1k Ω)

Capacitors

C1	10 μF 25 V
C2	470 μF 25 V
C3, C5	220 nF (0.22 μF) Mylar
C4	1000 μF 25 V
C6	100 μF 25 V

Semiconductor

LED	5 mm Red

Integrated circuit

IC1	TDA2003

Additional items
  Heat sink compound
  Nuts and bolts
  Loudspeaker 4 Ω 6 W
  3 A fuse
  On/off switch (SPST)
  Matrix board 4 × 6 cm
  Solder tags
  Plugs and screened cable for connecting lead
  Aluminium box

86 A grid dip oscillator

Introduction

When an inductor and a capacitor are connected, whether in series or parallel, they form a circuit with a natural (or *resonant*) frequency. The circuit stores energy, and this energy is being constantly shifted from the inductor to the capacitor and back again.

The dip oscillator is a simple instrument used to measure the resonant frequency of a tuned circuit without having to make any direct connection to the circuit. The circuit is more commonly known as the *grid dip oscillator* (GDO), from the days when the active device in the circuit was a valve. The FET or Field-Effect Transistor operates in a way which is very similar to that of the valve, so it is not quite a misnomer to call this instrument a grid dip oscillator, too.

The circuit

The GDO uses a calibrated, tunable FET oscillator in the circuit of **Figure 1**. It has a frequency range of 1.6 to 35.2 MHz in four ranges using a set of plug-in coils, shown in **Figure 2**. When the oscillator coil, L1, is placed near an external resonant circuit, some of its RF energy is coupled into the external circuit. A gain in energy of the external circuit must mean a loss of energy in the GDO circuit, resulting in a change of current through TR1, which is measured by the meter, M1.

The current through TR1 is of the order of 5 to 8 mA, but the change of current may be only a few microamps. To measure a very small


RFC
1mH
RF out
C8
1n
C9
100n
C1
22p
C4
100p
R2
56R
R4
5k6
L1
VC1
2x
365p
*
R7
1k
*
R8
5k6
*
C10
6p8
RV1
1k
lin
TR1
J304
C3
100p
M1
100μA
meter
+
−
R6
4k7
S1
C2
22p
D1
1N4148
R1
100k
R3
1k
C5
100n
C6
1n
C7
100n
R5
560R
LED
+
9V
−
* These components only required if you want
to couple the GDO to a frequency counter
©RSGB DY380

Figure 1 Circuit of an FET GDO. The coils are wound on DIN speater plugs, which provide both a plug-in base and a coil former


L1 winding
(see caption)
2-pin DIN
loudspeaker
plug
©RSGB DY390

Figure 2 Details of coil construction:
Range 1: 1.6–4.0 MHz 55 turns of 30 SWG
Range 2: 3.3–7.9 MHz 27 turns of 30 SWG
Range 3: 6.3–4.0 MHz 14 turns of 26 SWG
Range 4: 11.9–4.0 MHz 7 turns of 24 SWG.

change superimposed on a much larger standing current, the method of *offset* can be used.

One connection to the meter goes to the source of the FET, while the other goes to a variable offset voltage set by VR1. M1 has a full-scale deflection (FSD) of 100 μA. If the current through TR1 changes, the voltage across R3 changes. When there is no resonance, the voltage at the wiper of VR1 is set to be very slightly greater than that across R3, and there is a 75% FSD meter deflection. When the voltage across R3 decreases very slightly, due to external circuit resonance, a significant ‘dip’ in the meter deflection is produced, hence the name of the instrument.

The circuit is not difficult to make on standard matrix board. Provided you can follow a circuit and translate it into a good component layout, then this project is probably only an evening’s work.

The most important part of the GDO is the tuning capacitor and its associated frequency-calibrated dial. New, air-spaced tuning capacitors can cost you up to £20, so it is worth delving around in junk boxes, or scouring the tables at a local boot sale or rally. The tuning capacitor from an old transistor radio should be perfect. It may even have a slow-motion drive and a dial which can be remarked for the project.

Choose a coil plug and socket arrangement that is practical. Think about crystal holders or phono plugs and sockets. The prototype shown in Figure 1 and Figure 2 used 2-pin DIN plugs, with the coil wound on the outside of the plastic plug cover. Figure 2 shows the coil construction and the winding details.

If you use a variable capacitor, VC1, with a value different from that shown in the parts list, then the frequency ranges will be different. This does not matter, as it will be taken into account during calibration.

Position VC1 so that the dial will be easy to see and to operate, while locating the coil socket as close to it as possible. **Figure 3** shows the traditional layout of the GDO.

Calibration

Because the GDO also radiates a very small amount of energy, a general coverage receiver can be used to calibrate the dial. Don’t try to aim for great accuracy and clutter the dial with marks and figures! If you include C10, R7 and R8 in your circuit, you can connect a frequency counter directly to the GDO and leave it in circuit all the time.

The GDO in use

Always try to place the external tuned circuit with its coil coaxial with the plug-in coil, as shown in Figs 1 and 3. If the coils are at right angles, the GDO may not produce any resonance. Set the offset control to give about 75% FSD and slowly tune L1 through its whole range. If no dip occurs, you may have the wrong coil plugged in. When you eventually find a dip, move the external coil further away until only a minute dip is seen. You may have to retune the dip meter as you do this, but it gives a much more accurate reading of frequency.

Remember that you cannot ‘dip’ a coil by itself – there must always be a capacitor present.


Coil
Capacitor
Parallel tuned circuit
Plug-in coil
VC1 with calibrated dial to read frequency
GRID DIP METER
M1 100μA meter
RV1 meter zero control
S1
Power on LED
©RSGB DY381

Figure 3 Layout of a typical GDO. The dial, meter and the location of the coil to the circuit under test can all be viewed at the same time. It is shown measuring resonance of a tuned circuit

Aerial resonance

Figure 4 shows how to check the resonance of a dipole aerial. Disconnect the coax feed at the aerial and place a short piece of wire, terminated with crocodile clips, across the centre insulator to short together the two ends of the aerial. By placing the GDO close to the shorting link, a dip should be seen on the meter while VC1 is turned. Alternatively, a loop in the element can be made around the coil, as in Figure 4, or the shorting link can be made long enough to loop over the coil. The latter method does not require tampering with the mounting and tensioning of the dipole wires.


Coax
disconnected
Loop in antenna
element held
by tape
*
*
Crocodile
clip
* Remove insulation to
allow clips to make
a good connection
Insulator bridged
by wire link
GRID DIP METER
©RSGB DY391

Figure 4 A wire antenna element can be looped into a single turn coil for increased coupling to the GDO

Parts list

Resistors: all 0.25 W, 5% tolerance

R1	100 000 ohms (100 kΩ)
R2	56 ohms (56 Ω)
R3	1000 ohms (1 kΩ)
R4	5600 ohms (5.6 kΩ)
R5	560 ohms (560 Ω)
R6	4700 ohms (4.7 kΩ)
R7	1000 ohms (1 kΩ)
R8	5600 ohms (5.6 kΩ)
VR1	1000 (1 kΩ) linear

Capacitors

C1, C2	22 pF
C3, C4	100 pF
C5, C7, C9	100 nF (0.1 μF)
C6, C8	1 nF (1000 pF)
C10	6.8 pF
VC1	2 × 365 pF

Semiconductors

TR1	J304 or similar
D1	1N4148
LED	

Additional items

L1	See Figure 2
RFC	1 mH
S1	SPST
M1	100 μA

Source

Components are available from Maplin.

87 A CW transmitter for 160 to 20 metres

Introduction

This very small transmitter is designed to work on any band from top band (160 m) to 20 m, with an RF output of 1 W. It will work on higher frequencies but with a reduced output.

The circuit

The three-transistor circuit is shown in **Figure 1**. It comprises a crystal oscillator using a BC182 transistor which drives a 2N3866 power amplifier (PA) keyed by a ZTX750 PNP transistor. The oscillator and PA are coupled by a capacitor and resistor; this provides a very small amount of positive bias to the PA.

The oscillator can be used as a basic crystal oscillator but, by including a variable series capacitor as shown in Figure 1, the crystal frequency can be 'pulled' slightly, making the oscillator a *variable crystal oscillator* (VXO).

Construction

The PCB layout is shown in **Figure 2** and in the photograph. Although the prototype was built around a PCB, this circuit is equally amenable to


33k
100R
100n
BC182
100p
Xtal
100p
1k
1k
Optional variable capacitor
ZTX750
100n
RFC
100n
100n
2N3866
1k
+ 47μ
33R
33R
100n
+12V in
To Rx
To antenna
Key
©RSGB DY396

Figure 1 Transmitter circuit diagram


Output
+9 to
+12V
33k
100
R
100n
10n
RFC
100n
Electrolytic
47μ
100n
ZTX750
1k
Optional
variable
capacitor
BC182
2N3866
1k
100p
100p
100n
100n
Xtal
1k
33R
33R
Key
©RSGB DY397

Figure 2 Component placing on the PCB. The external connections are also shown

construction on a matrix board. Populating the PCB is very simple, and you can expect to be able to do this in about one hour. The radio-frequency choke (RFC) is made by winding 10 turns of 33 SWG wire on a ferrite bead. The enamel coating of the wire is intended to vaporise when soldered into the board, thus obviating the need to remove the enamel manually with a knife or sandpaper. However, if you do have problems with the PA either not working or keying intermittently, it is suggested that you investigate the RFC connections immediately!

If you decide to make the VXO version, you will have to cut the track between the crystal and earth, and connect the variable capacitor (250 pF) across the break.

In use

After performing the usual checks on the accuracy of your circuit building and the wiring of the external components, it is time to connect a 12 V battery between the points shown in Figure 2. Do not switch on yet. An aerial needs to be connected to the output via an ATU and a crystal, of frequency matching that of the aerial, fitted. The variable capacitor should give you a tuning range from about 14.058 to 14.064 MHz. ‘Netting’ (the process of tuning your transmitter to the same frequency as that of a received station) is achieved simply, because the oscillator is always running, and the leakage of the signal (despite the fact that the PA is not powered) is sufficient to bring the two frequencies to zero beat.





Warning

Note that the transmitter has no filtering; harmonics are not suppressed. It is strongly recommended that you use this transmitter in conjunction with the excellent low-pass filter described in the project *A 7-element low-pass filter for transmitters*, described elsewhere in this book.

88 Matching the end-fed random-wire aerial

Introduction

Many amateurs who do not have the space (or money) for a multi-band beam aerial, make use of the simplest possible alternative – the longest piece of wire that they can erect, with its end connected to the transceiver or receiver by an aerial tuning unit (ATU).

The length of the wire is not of major importance. Any length between 10 m and 80 m, with bends if necessary, will suffice. A good earth connection to the radio is just as important. Bends in the aerial wire can have some interesting effects on the directional properties of the aerial; V- or L-bends, or even a square shape are permitted. The only thing *not* permitted is to fold the wire back on itself in a tight hairpin bend!

Longish wire aerials

The term ‘long wire’ is usually used (incorrectly) to describe an end-fed aerial. How long is a piece of string? It depends what you mean by ‘long’. In aerial parlance, it means ‘long with respect to one wavelength’. Again, this depends on the band you are using. A long wire at 20 m is somewhat different from a long wire at 160 m. However, if you have sufficient real estate for a long wire on the 160 m band it must, by definition, be a long wire on all the other bands, too!

This should put you on your guard when analysing published data about feed-point impedance and the directional properties of a long wire aerial. Such theoretical data relate to a *real*, *ideal* long wire which is straight, horizontal, very high above perfect (conducting) ground, and not obstructed in any way. So your aerial doesn't quite match these criteria? Join the club!

Don't let this dampen your ardour when it comes to evaluating what the longish wire can do for you. The following should explain why.

Feed-point impedance

The impedance at the end of a longish-wire aerial can vary from a few tens of ohms to several thousand ohms, depending on the frequency in use and the wire length. It is also affected by factors such as bends, height above ground, proximity to buildings and wire diameter.

The actual value doesn't matter, provided we can make the aerial *appear* to have a 50 Ω impedance at the aerial socket of the transmitter. This process is what we call *impedance matching*, or simply *matching*. It maximises the power transfer from the transmitter to the aerial, and from the aerial to the receiver.

That is why an aerial tuning unit, or ATU, is almost (but not necessarily) obligatory.

The ATU

Many commercially produced HF receivers and transceivers have single 50 Ω coaxial sockets as their one and only means for connecting an external aerial. This means that an external aerial should have a 50 Ω feed impedance if it is to work efficiently, and it rules out most of the aerials being used by amateurs on the HF bands. Some means is necessary to change the aerial feed impedance to 'match' that of the transceiver. Such impedance-matching, or Z-matching (because Z is the symbol for impedance, just as L is the symbol for inductance) is the rôle of the ATU.

These can be bought and will accommodate either an end-fed or a coax-fed aerial. They can be bought ready for use or in kit form. Whether you want one for receiving only, or for use with a low-power (QRP) or high-power (QRO) transmitter, will determine what you need and how much you pay.

A simple single-band ATU

The simplest form of ATU is shown in **Figure 1**. It is simply a parallel LC (coil and capacitor) circuit, resonant at the chosen frequency, with taps on the coil for the aerial and the coaxial feed to the transceiver. If we assume the circuit is resonant, a high impedance exists at the top of the coil, and a low impedance at the bottom.

We said earlier that the end-fed longish wire presented an impedance which was high (or at least higher than 50 Ω). This explains why the aerial is tapped to the coil near the top, where the impedance is high, and the 50 Ω coax is tapped near the bottom, where the impedance is low.



Figure 1 Parallel tuned circuit as single-band ATU for end-fed longish-wire antenna

Because the feed-point impedance of the aerial changes with frequency, so must the point at which the aerial is tapped to the coil to achieve impedance matching. The value of C must be changed also, to ensure that the circuit is resonant, and the 50 Ω tap will require tweaking also.

Setting up an ATU is quite simple. Make up an LC parallel-tuned circuit consisting of 50 turns of enamelled copper wire on an empty 35 mm film plastic container (or similar), tuned with a 500 pF variable capacitor. Make sure the enamel is removed from the ends of the wire before soldering.

Solder the inner wire of the coaxial cable from the radio to the first or second turn of the coil from its grounded end. Then solder the braid to the grounded end. Connect the aerial about one-third of the way down the coil from the top, removing the enamel at the connection point.

Adjust the variable capacitor for maximum noise or signal strength in the receiver. Then, try different tapping points from the aerial, to maximise the signal again. This matches the aerial impedance to that of the tuned circuit. Repeat the process with the coax tap, thus matching the impedance of the radio and the cable to that of the tuned circuit.

You will no doubt find that the tapping process on the coil was not easily accomplished, especially when the enamel must be removed at each tapping point without shorting adjacent turns together. It is therefore logical to produce a design where the taps have been prepared during the winding of the coil, and are selected with a rotary switch. To this end, the following multi-band design is described.

A multi-band ATU

The same type of coil design around a 35 mm film container is used (see **Figure 2**). The tapping points can be prepared in advance by a little judicious planning. Dismantle your original coil and measure the length of wire on it. It will be a little more than a calculation of $50 \times \pi D$ would suggest (where D is the diameter of the film container), due to the lack of tension in the coil and the wire diameter itself. You will need aerial tapping points at turns 1, 2, 3, 5, 10, 15, 20, 25, 30, 35, 40 and 45, corresponding to all the bands from 28 MHz to 1.8 MHz. The coaxial cable tap is fixed at turn 2 (an acceptable compromise). All the turns are counted from the earthy end.

Cut another piece of enamelled copper the same length as you used originally. Then, with the aid of an ordinary calculator, work out the positions of the points where the enamel must be removed for the taps. For example, turn 15 will have to be made $\frac{15}{50}$ of the way along the wire, turn 20 tap made at $\frac{20}{50}$ of the way along. So, if the length of wire is, say 4.7 metres, the two taps in question will be made at $\frac{15}{50} \times 4.7 = 1.41$ m and $\frac{20}{50} \times 4.7 = 1.88$ m from one end. This must be repeated for each of the tap positions, and the enamel removed ready for the wire to be soldered to it. With a



Figure 2 Simple multi-band ATU for end-fed longish-wire antennas

soldering iron, tin each tap point while the copper is shiny, thus ensuring a good, low-resistance connection. Do not solder on the taps yet.

The coil can now be wound as before. The taps can be soldered on, taking the lead from each one to the wafer of a single-pole 12-way rotary switch, the pole being connected to the aerial.

The tuning of the ATU is carried out by the same 250 pF capacitor, with a single-pole 5-way rotary switch used to select the band. Its tapping points will need to be chosen manually, using the method described earlier. Don't attempt to make new tapping points on the coil for this – use the taps available on the wafer of the other rotary switch, and find which is optimum for each band.

Notes

- For the aerial, use PVC-covered stranded tinned copper, of size 16/0.2 mm or 24/0.2 mm.
- Make the wire as long as possible, but anything over 10 m should be OK.
- Keep the wire as high as you can, in the clear and away from obstructions.
- Don't worry about bends, but don't use hairpin bends.
- Use a good insulator to attach your aerial – anything plastic will do.
- Anchor the wire near the point of entry to the building, but use a U-bend to prevent ingress of water.
- The wire can be brought in through the corner of a window, the PVC acting as an insulator. If you must drill a hole in the brickwork, make sure it slopes upwards from outside, so that water is deterred from entering.
- Use a good RF earth (as opposed to an electrical earth) such as half a dozen bare copper wires buried under the lawn in a fan shape. They should be joined together at the point of the fan and strapped to the earth connector of your ATU.

Radio a cristallo e dintorni - Le Radio di Sophie - Crystal sets

Radio a cristallo doppio circuito per O.M.

Un progetto di Luciano Loria



Il circuito più semplice, ed anche molto efficace, per la realizzazione di una radio a cristallo, consiste di un circuito LC accordato sulla frequenza da ricevere e da un rivelatore (cristallo di galena, diodo al germanio).
Vediamo cosa accade se questo circuito si raddoppia: due bobine, due condensatori variabili, due diodi.



Materiale occorrente

L1; L2 = 90 spire filo rame smaltato Ø 0,3 mm
su tubo isolante Ø 3 cm
CV1; CV2 = variabile in aria 350 + 350 pF
C1 = condensatore ceramico 220÷330 pF
D1; D2 = diodo al germanio (AA117)

Schema elettrico

Nello schema elettrico notiamo che L1, CV1, D1 costituiscono un primo circuito di sintonia e di rivelazione, così come L2, CV2, D2 che costituiscono il secondo circuito; questi sono accoppiati tramite il condensatore ceramico C1 da 220/330 pF. Per ottenere risultati apprezzabili, ed una migliore selettività*, occorre che le due bobine siano montate con i rispettivi assi ortogonali fra loro (vedere foto).

* La selettività dipende anche da C1, per aumentarla si può diminuire la capacità fino a circa 33pF.

NOTE COSTRUTTIVE

Evitare, per la costruzione, l’uso di telai metallici, anche le bobine non vanno sistemate troppo vicine al variabile.

Il condensatore variabile ha due identiche sezioni comandate da un alberino unico; L1 e L2 sono avvolte su tubo di cartone di derivazione casalinga, infatti, si tratta del tubo dove sono avvolte le pellicole trasparenti o d’alluminio per cucina.

Il contenitore trasparente, sempre nell’ambito di un riciclaggio intelligente dei materiali che si trovano in ogni casa, è l’astuccio di certe famose praline al cioccolato (nella foto è visto senza il coperchio).

Naturalmente occorrono, anche: una buona antenna filare esterna; una presa di terra efficace; una cuffia ad alta impedenza; in tal caso l’ascolto, della stazione locale in OM, è garantito e risulta migliorato rispetto a quello ottenuto con il circuito base.

luciano.loria@gmail.com

Torna alla Pagina delle radio a cristallo

Heathkit CR-1 Crystal Radio and Miller 595 Tuner Information


HEATH COMPANY
BENTON HARBOR, MICHIGAN
ANT.
0
100
200
Heathkit
CRYSTAL RECEIVER
MODEL CR-1

This page gives the circuit and pictoral description of the famous Heathkit CR-1 crystal radio.
It was a double tuned crystal radio from the 1950's with a series tuned primary that had a 365 pf variable capacitor and selectable additional capacitance on the center selector switch. In my opinion, it would have been more logical to have made the center switch for varying the inductance and using a tapped primary coil.



Here is a picture of the inside of the original CR-1.



Another photo showing the inside of the original Heathkit CR-1. Note the rectangular pinkish mica capacitors, the configuration of the central antenna switch, the "cable knit" appearance of the coil windings, and the long screws holding the panel to the threaded stubs that are recessed deep into the cabinet.

Anyway the coils, marked as "transformer" in the diagram, were both wound on a ferrite rod and the secondary coil was part of a tank with the 365 cap and the germanium diode for the detector circuit. They do not give details of the coil construction but with a little experimentation you can get into the BC band tuning range.

Here is the original circiut:


ANTENNA
TRANSFORMER
CRYSTAL DIODE
CR1
L1
L2
DET
C2
365 MMF
100
0
200
PHONES
HEADSET
ANT.
C1
S1
SWITCH
C3
C4
365
MMF
350
MMF
350
MMF
GND.

HEATHKIT CRYSTAL RECEIVER SCHEMATIC
MODEL CR-1

This shows the pictoral diagram of the inside of the set:


ANT.
ANT. SWITCH
COLORED
DOT
DET.
1
2
3
CRYSTAL
DIODE
350
MMF
350
MMF
ANT.
GND.
PHONES

PICTORIAL 1

First Prototype

In my first building project replica I used a toroidal core instead of a rod. An Amidon FT 114-61 was my choice for the core, and 45 turns of 24 GA enamel wire for the secondary gets the detector tank in the ballpark. (Amidon's webpage is http://www.amidoncorp.com). I used 30 turns of the same wire would on the same toroid for the primary with taps at 3, 6, 9 15, 24, and 32 turns. I used the center selector switch to vary the inductance of the primary instead of switching in additional capacitors.

The little box is a Radio Shack part #270-1805 that is just about exactly the same size as the original enclosure. The front panel is made of aluminum, so it serves as a common ground, but the antenna and one of the headphone binding posts need to be insulated from it using little fiber washers to prevent those binding posts from making electrical contact with the panel.

The radio was originally sold either with or along side a pair of 4000 ohm Trimm Acme headphones. They were only middle of the road for sensitivity and a good old pair of Brandes Superior or Western Electric 509-W's would be much more sensitive.



Here is a shot of the main parts on the floor. The rotary switch, diode, and box are from Radio Shack. The variable caps were obtained from the Xtal Set Society. The coil is described above and I got the old mica capacitors from my junk box. I ended up using a different coil and no padder capacitors though.

One challenge was to tap a couple of the holes on the front face of the variable caps to allow them to be mounted to the front panel using 6-32 screws. Care must be taken to avoid damaging the capacitor and to keep the metal shavings out of the ball bearing mechanism.



OK, here is the completed CR-1 clone.
This first attempt has the binding posts spaced a bit too close. I didn't have an original to copy, just pictures. I also tried a couple of different coil configurations and the one I settled on has 45 turns of 24 GA wire for the tuned secondary, and the primary is tapped as noted above.



Inside it is pretty simple. Just the 2 variable caps, the rotary switch wired up to the toroidal coil, and the diode can be seen from the capacitor to the binding post on the far left.
I hooked it up and counted 6 local stations in the first minute in the daytime, and with a good pair of headphones got 7 locals and another 4 out of state stations on the first night.

If I ever get a hold of an original, I will post a comparison of the performance.
OK, I got a loan of the original Heathkit CR-1 and here is what I found.
The original CR-1 has a much more definite double tuned effect than my spinoff. The 2 knobs for tuning the ANT and DET circuits seem to track pretty closely with each other and both need to be tuned to the same frequency farily sharply to get reception. It is easy to miss a station by not having the tuners coordinated. I found it best to move the DET dial a little then sweep the ANT knob back and forth a little to zero in on the station if there was one there.
The circuit gurus emailed me and correctly predicted that my circuit would pretty much function as a single tuned circuit. The inductance tap switch mainly varied the selectivity and I found the 9 turn tap to be good for both sensitivity and selectivity. There was some noticeable tuning effect of the ANT variable cap at the high frequency end of the dial but the DET tuner did most of the tuning. It was, however, very sensitive and tuned very sharply anyway. In fact the volume was louder across the entire frequency range than the on the original CR-1, and I was able to get a couple of weaker stations that I couldn't reach on the real CR-1. So overall I am very happy with the performance but I will try another one to try and clone the coil and performance of the original a little more closely.

Next Version



After a lot of advice and many coils later, I think I got pretty close to the original performance. The secret is the coil. I am told the original has 2 small ferrite cores in it rather than 1 long one so, I experimented with different sizes of cores combined with different numbers of turns on the coil and then zeroed in on the correct spacing between the 2 cores. The spacing between the coils could be measured from outside but the stuff inside the cardboard tube was impossible to discover without damaging the coil. It looks like the core is about 1/4 inch diameter and extends just to the outer edges of the coil windings when you look into the ends of the tube. If anyone knows the exact original specifications please let me know. Anyway, I was able to pick up the same stations with this version as with the original.

After many attempts and examination of an original coil and X-ray here is what I ended up with. I used 21/44 Litz wire for the windings. The antenna coil was about 140 turns with a 9/16 inch slug inside that part for about 335 uH inductance. The space between the coils was 10 mm or about 7/16 inch. The detector coil had about 90 turns with a 9/16 inch long slug inside that and measured 240 uH. On some of the coils, I tried bringing out a tap about 30 turns from the stator end of the winding for the detector tap. Hard to say if this made and noticeable difference, not much if any. This coil seemed to duplicate the performance of the original in both sensitivity and selectivity. Any closer spacing of the coils and you get too much coupling and the tuning gets very broad.



Here is a front label that I made on some thin acetate plastic, printed the Heathkit logo on it, and glued on to the front of the aluminum panel. I sold a few of these clearly presented as home made clones, though I have occasionally seen my radios show up for sale on Ebay advertised as a genuine Heathkit, which should be obvious that they are not. Note the short flat Phillips head screws, the lettering which is clearly different than the original, and the coil inside is clearly hand wound as opposed to the tidy machine winding of the originals. Also note the round modern ceramic chip capacitors and the multiposition switch. If you run across one of my radios being passes off as an original, you can refer the seller to this page, but the radio itself, unless damaged, should work just as well as the real thing, and there were only a dozen or so ever made, so they are quite rare indeed!

Addendum 5/29/01
Unravelling the secrets of the CR-1 coil, or The CR-1 coil Exposed


30
40
50
60
70
80
90
100
110

This is an actual X-ray of a Heathkit CR-1 coil. As you see, it has the 2 coils each with its own separate ferrite slug. The best I can measure, each slug is about 13 mm or about 1/2 inch long by 1/4 inch diameter. The separation between the slugs is 7/16 inch. It looks like the slug in the larger (antenna) coil is not quite centered under the coil. I am not sure if this was intentional or not. Anyway it was helpful to know how it was made so one might get a better idea of how to make a duplicate.
The Amidon R61-025-400 core can be cut into the 1/2 inch lengths for use in constructing a coil like this one. I will post further information as I progress with this project. Thanks Mike!

Link to Miller Tuner Page (sorry this linked site has been removed, but will try to relocate it)
This is a link to a page with more information about another famous crystal radio, the Miller 565 / 595 Tuner. This was my next project. The modified schematic is shown below.


C1
DUAL
365
μμfd
C6
C5
D1
IN34
TO HEADPHONES OR
AUDIO
AMPLIFIER
GROUNDED
TERMINAL
CATH
C4
200
pfd
R1
100,000Ω
ANTENNA
GROUND
L4
L1
L2
L
1
L3
C2
0.1
μfd
C3
0.05
μfd
NEGATIVE MUTUAL COUPLING COIL

Figure 1-3. BAND PASS CRYSTAL RECEIVER

Parts List:
Part Description Source, Part#
C1 2 gang 365 pf tuning capacitor from Xtal Set Society
C2 0.1 uf capacitor Mouser 5989-250V.1
C3 0.05 uf capacitor Mouser 5989-250V.047

C4 200 pf capacitor Mouser 140-50P2-201K
C5 10 pf capacitor Mouser 140-50N2-100J
C6 15 pf capacitor Mouser 140-50N2-150J
R1 100K ohm resistor Mouser 293-100K
L1 Tuning coil 1 Core from Amidon FT 82-61, see text below for winding
L2 Tuning coil 2 Core from Amidon FT 82-61, see text below for winding
L3 Negative mutual coupling coil, see text below for construction
L4 270 uH peaking coil Mouser 43LR274
L5 (marked L in schematic) 2500 uH RF choke Mouser 542-70F253
D1 1N34A Germaniun Diode
Miscellaneous hardware:
Perforated Circuit Board Radio Shack 276-1396A
Solder Tabs Mouser 534-7312
Machine Screws 6-32
Washers size 6
Tuning Knob or Dial
Cabinet Radio Shack part #270-1807
Wire for the coils and hookup
Binding posts or Fahnstock clips

The secret of this set is in the construction of the coils.

L1 and L2 are straight ferrite rods wound with Litz wire. The best reproduction of this was to use an Amidon 2 inch by 1/4 inch diameter ferrite rod of material 61, and wind on 85 turns of Litz wire. I had some 21 strand by 44 GA wire and this worked well. I actually measured the inductance of the finished coils and adjusted the windings to get them exactly the same, to the uH, about 250 uH.

L3 is the real secret of this set. After trying several different core forms for this, the best seemed to be a ¼ inch hardwood dowel about 2 inches long. Wind 2 strands of the 30 GA wire onto the form together, side by side, close wound for somewhere between 20 and 31 turns and secure. Take the left end of strand A and the right end of strand B and join them together for the bypass to the grounded capacitor. The remaining free ends go to the points indicated on the circuit.

I am told you can get the actual flyer from the Miller Company.

This circuit and the construction details are published in the Newsletter of the Xtal Set Society in a 2 part article starting in Jan 2002. You can see the construction details and alignment instructions there.

Back to Scott's Crystal Radios

BENJAMIN AND DAVID GOLDENBERG 'S VERY-FINE

OLD-TIME CRYSTAL RADIO

Parts List:

Item	Qty.
PVC pipe, 1" outside diameter (3/4” size) x 4" long	1
Aluminum or steel sheet metal, 0.5” wide x 5” long	1
Coil wire (#24 magnet wire)	36 ft
Hook-up wire (#22)	25 ft
Crystal earphone (GC electronics, cat. no. 30-5302)	1
Jack for the earphone plug	1
Crystal diode (1N34A)	1
Capacitor, 470 picofarad	1
#8 sheet metal screws	8
8-32 machine screw, 1" long	1
8-32 nuts	2
flat washers	6
Ring terminal	1
Board, 3/4" thick, approximately 7" x 9"	1

What else you need:

Vise-Grip pliers
Wire cutters
Soldering iron and solder
Drill, with 1/8", 3/16” and 3/8” bits
File or motorized grinder (e.g. Moto-Tool)
Screwdriver
Scotch tape

Instructions

I. CONSTRUCTION OF SPECIAL PARTS.

The following steps involve making a few special parts for the radio. Some of these steps are most easily performed using power tools and some involve soldering. This work should be done by someone old enough and knowledgeable enough to handle these tools safely. Once these parts are made, however, the rest of the project requires only hand tools and can be completed by nearly anyone.

1. Coil Form

The coil form is a piece of PVC pipe, 1” in diameter (outside) and 4” long. (For reasons fully understood only by plumbers, pipe of this diameter is referred to as 3/4”.)

To facilitate mounting the coil to the board, drill two sets of holes, on opposite sides of the form. On one side of the form, drill two holes, 3/16” in diameter and 3/8” from the ends. Directly opposite from these holes, drill two more holes 3/8” in diameter. Screws will be placed through the smaller holes, while the larger ones make it easy to reach the screws with a screwdriver.

2. Slider

Drill two 3/16” holes in the piece of sheet metal, each 1/4” from an end. After the holes are drilled, place a bend in the metal 3/4” from each end, as shown in the figure on page 3. Use a vise or pliers to bend the metal. Use a file to smooth all of the edges and corners of the metal.

CAUTION: Drilling sheet metal can be very dangerous! If the bit catches on the metal, you can have a very sharp edge flying through your hands. Hold the metal firmly with a pair of pliers (preferably Vice-Grip type), not with your hands! Also, place a piece of wood under the metal as you drill. This will help keep the metal from tearing and grabbing the bit as the passes through.

3. Pointed screw for slider

Using either a file or a grinder, grind a point on the 8-32 machine screw. The point doesn’t need to be very sharp; about like the tip of a medium ball-point pen is ideal.

4. Earphone jack with wires.

Cut two pieces of hook-up wire 2” long. Remove 1/4” of insulation form one end of each wire and solder the wires to the terminals of the earphone jack. Remove 1/2” of insulation from the other ends of the wires.

Note: Headphone jacks often have more than two terminals. Make sure that the terminals you solder to are the ones that will be connected to the tip and side of the plug when it is inserted.

5. Ring terminal with two wires.

Cut two pieces of hook-up wire, one 7” long and the other 2”. Remove 1/4” of insulation from one end of each wire. Solder the two wires to the ring terminal. Remove 1/2” of insulation from the other ends of the wires.

6. Board

Tape the layout template (the last page of this document) to a board, approximately 7” x 9”, and drill a 1/8" hole at each position marked with a cross.

II. ASSEMBLY

1. Wind the coil.

The coil is made by wrapping the #24 magnet wire onto the coil form, which is made from a piece of PVC pipe. The magnet wire is the wire that looks like it has no plastic insulation on it. But, it is actually coated with a thin layer of enamel. This coating must be removed from the ends of the wire before making any connections.

The best way to wind the coil is with two people, one to hold the wire taught (the holder) and the other to wind it onto the coil form (the wrapper). First, thread the end of the coil wire from the outside of the form through one of the large holes and out the end of the form. Leave about 4" of wire going out the end. Hold onto the other end of the wire and begin wrapping it around the form, starting right next to the hole. After you have wound a few turns on, push the wire together so it is nice and neat and put a piece of Scotch tape over it. The coil should look like this:



Now, the "holder" should hold the spool of wire loosely while the "wrapper" walks across the room unwinding the wire. Then, the holder should hold the spool very tightly so that the wrapper can wind the wire onto the pipe evenly. Each turn should be wrapped on right next to the previous turn, but shouldn't overlap. As the wire is wrapped on, the wrapper slowly walks across the room keeping the wire tight. When the wrapper reaches the holder, hold the wire that has been wrapped onto the form tightly, while the holder lets the wire on the spool unwrap. The wrapper then walks back across the room unwinding the wire from the spool, and the same procedure is repeated.

When the coil is within about 1/8" of the holes at the other end of the coil, stop winding. Put a piece of Scotch tape on the end of the wrapping, and cut the wire a few inches from the end of the coil. Thread the end of the wire through the large hole in the form.

2. Attach the coil to the board.

Use two of the #8 sheet metal screws to attach the coil to the board, using holes B and C that you drilled. Place the screws through the small holes in the coil form from the inside. You can then use the large holes on the other side of the form to reach the screws with a screwdriver. Make sure the coil is attached snugly to the board.

3. Assemble the slider.

Find the slider, the 8-32 screw and the two 8-32 nuts. Thread one of the nuts onto the screw until it is about 3/8" from the head of the screw. Put the screw through one of the holes in the slider and thread the other nut on, so that the slider looks like this from the side:



Tighten the second nut against the slider and the first nut with a wrench.

4. Attach the slider to the board.

Find a sheet metal screw, a washer and the ring terminal with two wires attached to it. Put the screw through the ring terminal, the washer and finally the open hole in the slider assembly (from the top of the slider as shown above). Attach the entire assembly to the board with the screw at hole E. Tighten the screw so that it is snug but still allows the slider to move back and forth. The pointed end of the machine screw at the other end of the slider should press firmly against the wire on the coil. If necessary bend the slider so that it makes firm contact with the coil but can still move.

Move the slider back and forth on the coil to scrape the enamel insulation from the coil wire where the pointed end of the machine screw touches it. The screw should be able to make an electrical contact with the coil wire at any position along the length of the coil.

5. Put the remaining screws in the board.

Screw the remaining sheet metal screws into holes A, D, F, G and H, with a washer on each screw. Do not tighten the screws yet.

6. Wire the components of the radio together.

Use the circuit drawing as a guide. For each connection, make sure that the insulation is removed from the end of the wire. Wrap the bare ends of the wires around the screw between the screw head and the washer underneath.

a. Wrap the two wires from the earphone jack around screws F and H. Do not tighten these screws yet.

b. Take the short wire from the slider and wrap the bare end around screw F (which should already be attached to one of the earphone jack wires). Do not tighten the screw yet.

c. Take the long wire from the slider and wrap the bare end around screw A. Do not tighten this screw yet.

d. Find the crystal diode, the small cylinder with two bare wires attached to it. Wrap one of the wires around screw H (attached to the other earphone jack wire), and tighten the screw.

e. Take the other wire from the diode and wrap it around screw G. Do not tighten this screw yet.

f. Find the capacitor, the small disc with two bare wires attached to it. Wrap one of the wires around screw F and tighten the screw.

g. Wrap the other wire from the capacitor around screw G, but do not tighten this screw yet.

h. Cut a piece of hook up wire about 6" long and remove about 1/2" of insulation from each end. Wrap one end around screw G and tighten the screw. Wrap the other end of the wire around screw D, but do not tighten this screw yet.

i. Take the wire from the right hand end of the coil and remove the insulation from about 1/2" from the end of the wire. To remove the insulation, either lightly scrape the wire with a knife or use a small piece of sandpaper. Wrap the bare end of the wire around screw D, but do not tighten the screw yet.

7. Connect the radio to ground.

In order to work, the crystal radio must be wired to a good ground connection. Often, the easiest way to make a ground connection is to use the grounding circuit for the house's electrical system. Cut a piece of hook-up wire long enough to reach from the radio to a nearby electrical outlet. Remove 1/2" of insulation from each end of the wire. Wrap one end around screw A of the radio and tighten the screw. On the electrical outlet, loosen the screw that holds the plate on the box. Wrap the other end of the wire around this screw and tighten it.

CAUTION: Be sure not to let the wire or anything else touch the 120 V socket!

Alternatively, you can use a cold water pipe to connect the radio to ground. Remove a few inches of insulation from the wire from screw A of the radio and wrap the bare end around a cold water pipe.

8. Connect an antenna to the radio.

Use the rest of the hook-up wire to make an antenna. Remove 1/2" of insulation from one end of the wire and wrap it around screw D. Tighten the screw. Unwind the wire from the spool and try to place it as high as possible in the room.

In areas with many powerful radio stations nearby, an inside antenna should be adequate to receive a few stations. If you have trouble hearing anything, it may help to set up a long outside antenna. Radio Shack sells a kit with the necessary wire and other parts (cat. no. 278-758).

9. Try the radio!

Plug the earphone into the jack. Listen to the earphone and slowly move the slider across the coil. Try to find the position where a station is loudest. You should be able to hear a few different stations with the slider at different positions.

10. If the radio doesn't work, check the following:

a. Make sure all of the connections are correct and that the insulation has been removed from the wires where they are wrapped around screws. Also check that there aren't any short circuits between the screws or bare wires.

b. Make sure that you scraped the insulation from the coil wire with the slider so that the slider can make good contact with the coil.

c. Make sure that you have a good ground connection. Try a different electrical outlet or a cold water pipe.

d. Place the antenna higher up or try a longer wire.

to ground
A
coil
slider
E
F
capacitor
G
diode
H
to antenna
D
earphone jack
to earphone


A
B
C
D
E
F
G
H

A Pretty Good Crystal Set

By Al Klase, N3FRQ, http://www.skywaves.ar88.net/

OK! It's time to build a crystal set. This time it's going to be a good one.



Countless millions of crystal radios have been built over the last 100 years, but the performance of most of these leaves a lot to be desired. The design of this radio goes back to about 1990 when I was a den leader for my son's Cub-Scout pack. I wanted the guys to have the experience of listening to a radio they had built with their own hands. However, we were in the deep suburbs of Philadelphia (actually half way to Reading). There were no strong local stations, so an average crystal set combined with the sort of makeshift antenna most families would erect, wasn't going to get the job done. The result was the Den Two Crystal Radio. (See "Crystal Set Projects," The Xtal Set Society, 1997.) This radio was based on a spider-web coil that 10-year-old hands could wind with a little supervision. It was sensitive enough to hear distant sky-wave stations at night, and selective enough that you could usually listen to just one station. Seven were constructed and at least six of those went into service at home. Everyone was duly impressed. We even had reports of hearing Radio Japan! (That was from Ontario, however.) We'll use the same circuit with a better solenoid-style coil.

First, lets deal with the headset. Look around for a traditional pair of 2000-ohm 'phones. That's the DC resistance, they'll have an AC impedance of about 10,000 ohms. Test the 'phones by putting them on your head, holding on to one of the tips and touching the other to an electrical ground such as a water pipe or the screw on an outlet plate. You should hear a click or maybe a hum. If not, they probably won't be sensitive enough for our purposes. Check the DC resistance with an ohm meter, it should be in the range of 1-5 K-ohms. Sometimes the cords are open.

An acceptable alternative to a vintage headset is one of the crystal (ceramic) ear plugs available from Mouser.com for about two bucks. It's best to install a 50-100K resistor in parallel with these 'phones to provide a DC load for the detector to eliminate audio distortion.

Modern low-impedance headsets with a matching transformer might work if you have a lot of signal strength, but most are designed to sacrifice sensitivity for flat frequency response.

Next, comes the detector. Stick to a germanium diode or the base-emitter junction of a germanium transistor for openers. A digital voltmeter in the diode position will indicate the forward voltage drop. Germanium devices will show 0.2-0.3 while silicon will indicate 0.5-0.7 volts. You can use a modern silicon device, but you'll be giving up a lot of sensitivity. The basic germanium diode is the 1N34A, but the part number doesn't mean much. They vary widely. Dump out the junk box, try them in a radio, and pick the best one. You can move on to mineral detectors and cat's whiskers after you have a working radio.

Now you'll need an antenna, the higher, longer, and more in the open the better. Sixty feet long and forty feet high would be excellent, but wire in the attic will probably suffice, especially if you're a "city mouse." A wire to a hose clamp around a water pipe or a connection to the screw on an outlet plate (AC safety ground) will complete the antenna-ground system.

Now it's time to build the simplest possible radio: Clip-lead the diode across the headset and then connect one side to the antenna and the other side to ground. You should hear something, quite possibly three stations at once.

To make this kludge into a serviceable radio we'll add a tuned "tank" circuit consisting of a coil and a variable capacitor. The target value for the cap is 365 pico-farads (mmF or pF), but a 500 pF unit as found in some of the old battery sets will work nearly as well. You could also use the large half of the two-gang cap from a junked all-American five radio, etc.

The coil is wound on a 4-inch styrene pipe coupling from the "home center." Wire is generally expensive and hard to buy retail. I've specified #20 insulated bell wire, also from the "home center" because it is easily available. The down side is that it's twisted pair that needs to be unwound, and they make you buy 500 feet, for about 30 bucks, when you only need 85 feet for the project. Any plastic insulated wire between #26 and #20 will do, but you'll probably need to adjust the total number of turns after you get the radio going to cover both ends of the broadcast band. The best option, for maximum performance, is silver-plated Teflon-insulated hook-up wire if you have any in the junk box, but even common vinyl-insulated tinned stranded wire will work all right. Close-wound magnet wire is a bad bet, as eddy currents in the adjacent turns cause considerable loss.



Winding the coil: Tie one end of an 85-foot length of wire to a solid support. Drill two small holes 3/8 of an inch from the end of the coil form. Keep the drill and wire cutters handy. Put a strip of thin cardboard about 3/8 inch wide and 3 inches long in your shirt pocket. Lace the end of the wire into one hole and out the other, leaving about a foot protruding from the form. Grasp the coil form firmly and pull the wire taught against the tied off end. Wind 5 turns on the coil keeping the wrie close-wound and tight. Place the end of the cardboard strip under the 5th turn. Wind four more turns, sneaking them under the strip. Wind the 10th turn over the strip. Continue winding placing the 20th and 30th turns on top of the cardboard. Wind 18 more turns for a total of 48. Clip the wire leaving about a foot to terminate the coil., drill two more holes in the form, and lace the end of the wire through them.

Use a utility knife to whittle away the insulation where the 5th, 10th, 20th, and 30th turns cross the cardboard. Wrap and solder a piece of bare wire at each of these sites to form the coil taps.

"Beadboard" the radio with clipleads or tack-solder joints to make sure everything works before committing to a physical design. The radio in the picture is built on an 8-inch square piece of ¾" plywood with an 8 x 6-inch front panel of tempered hardboard. Layout is not critical, but keep the coil in the approximate orientation shown so it can be coupled to the antenna tuner to be described in "PGXS – Phase II."


365 pF
COIL:
48 turns
#20 insulated wire
4.5" diameter
Tapped at 5, 10, 20,
and 30 turns.
NJARC - Pretty Good Xtal Set
Al Klase - N3FRQ - 2/28/2006

M0DAD RADIO WEBSITE

Basic Crystal Radio Set

I have been very interested in crystal radios for many years, I can remember building my first set back in my schooldays in the early 1980s. It was the first and still is the most basic of all radio receivers , If you are new to radio and have never seen one of these sets you will be very amazed at how easy it is to build a working radio needing so few components. What also may surprise a newcomer is that it does not need any battery or power to work, The only power it uses is taken from the transmitter of the station you are listening to, In other words it pulls the power from the radio wave.

The biggest craze of building and listening to crystal sets was at its peak in the 1920s. The old style sets used a real mineral crystal for the detector, The most popular being the galena and a fine bit of wire called a cats whisker which you would have to touch the crystal in the correct place to find the best reception where the radio station would come in. During world war II the underground people of Europe used crystal sets to listen to prohibited broadcast stations, Because of there simplicity to build. It is now getting harder to obtain all the original parts like the high impedance headphones, But I will show you how to build the modern day circuit using readily available parts.

My basic crystal radio project is aimed at the absolute beginner or younger generation, to try and interest them in the radio hobby as many amateur radio operators began there interest in radio with building the crystal set. The circuit can be soldered or built using chock block connectors for safety if a young person is doing this project.

CIRCUIT


ANT
DIODE
0A91
COIL 80T
VARIABLE CAPACITOR
EARPIECE
EARTH

HOW THE CIRCUIT WORKS

First of all there are many different signals from stations which will be traveling down the long wire antenna, The coil and capacitor together form a tuned circuit, And because the capacitor is a variable type you can change the resonant frequency of the tuned circuit by rotating the tuning knob on the capacitor. Only signals from stations on or near the resonant frequency can pass through the tuned circuit, The other remaining frequencies are bypassed to earth. The passed signals then go through the germanium diode (detector) which rectifies the positive half cycles changing it to DC current and then sending it to the crystal earpiece or high impedance headphones.

BOARD LAYOUT


COIL 80 TURNS
Antenna
EARTH
E
A
DIODE
EARPIECE

PARTS

I personally find it a lot more fun to salvage all the parts from an old radio as it will cost you nothing, But just for this project I have listed all the parts that you will need and where to buy them from.

Variable capacitor, available from Maplin Electronics (UK) Code FT78K

Diode: Maplin Electronics 0A91, Code QH72ZP, 0A90 Code QH71N or any germanium point contact diode such as an OA70,OA71, or 1N34.

Chock block connectors Maplin Electronics (UK).

Crystal earplug, avail able from Maplin Electronics (UK) Code LB25C

26 s.w.g. Enameled copper wire.

Coil former: An empty card board toilet roll or an off cut piece of plastic waste pipe.

Base: Any piece of soft scrap wood about 4"x 5"

PVC coated wire for links.

A roll of any kind of wire PVC coated or copper wire for antenna and an earth connection.

CONSTRUCTION

Start the construction with the coil by securing the former (toilet roll, or PVC pipe) and then winding 80 turns of 26 s.w.g enameled copper wire around. When finished secure the windings with sticky tape or glue, Then scrape the wire enamel off both ends of the coil with a knife or sand paper until you can see a shiny tip. The coil can be secured to the wood base with two drawing pins.

Now the most difficult part is over , you can secure a couple of chock block connectors in front of the coil and the two behind the capacitor then wire the circuit as in the board layout, It is straight forward, but make sure you get the capacitor the correct way, the earth and antenna pins are marked e and a on the bottom, There is no connection to the pin marked o. The diode has a glass body with a band on to show the flow of the conducting current. Strip the plastic coating off the end of the crystal earpiece leads and insert them into the two rear chock blocks.

You are now ready to connect the antenna, Just string up the longest length of wire you can, run it from the set through a window and secure it to an insulated pole, tree or fence as high and as long as you possibly can to achieve the best results. If it is impossible for you to have an outdoor wire, String a wire several times around a room ceiling or an attic, It will still receive some stations but at reduced volume.

You will need an earth, run a wire from the set to a cold water pipe, connect it to the pipe or to a water tap with a crocodile clip, Or if you want a more permanent arrangement you can run a wire outside and connect it to an earth rod driven into the ground, This can be a length of copper pipe or brass rod as long and deep into the ground as you can. It is said that you must have a good earth for a crystal set to work, In practice I found it works slightly better but have also achieved good results without any earth.

OPERATING THE SET

This is the best part, When you are finished building the circuit connect the earth and antenna wires, pick up the earpiece and have a listen, You should be able to hear noise, turn the screw on the variable capacitor until you tune into a station, You should be able to hear several stations on the MW band, Depending on your location, length and how high the wire antenna is, Because this is a basic circuit you will soon notice that the set has poor selectivity, This means that sometimes you can hear two or more stations coming in together and may find it difficult to separate the one you want to listen to, That is if you can at all. If you can only receive one or two stations and the screw on the variable capacitor is fully turned, try unwinding about 4 or 5 turns off the coil. One of the most difficult requirements is having the patience, Some stations will come in loud and then may fade out altogether after a wile, If you leave it on the same frequency they can sometimes return as the propagation changes.

FAULT FINDING

If it does not work, Check your wiring with that of the board layout, And make sure all leads are not slack.

You must make sure you have a germanium point contact diode, other diodes will not work.

Make sure you have a proper crystal earpiece or high impedance headphones, Do not be confused with the standard white coloured magnetic earpiece, Unlike the standard 8 or 16 ohm earphones of today crystal earpieces are into the mega ohms, So if you used the wrong type it would be like trying to run your washing machine on a PP3 9 volt battery.

EXPERIMENTING

When I built this crystal set for the web site I hooked a wire to a radiator for an earth, strung a 60 FT length of PVC coated wire through a window down to the rear garden fence, The first station I heard was quite a surprise, Radio Korea, Other stations where Virgin Radio - 1215 KHz, Talk Sport 1071 KHz, Magic 1152 KHz, BBC Radio 5 Live 693 KHz, BBC Radio 4 - 603 KHz, So it had a good range through the medium wave broadcast band.

Do not be afraid to experiment, Due to the simplicity of the set you wont break it, You can try changing the diode around, Try other coils with different number of windings, The more turns should take you lower in frequency, and the smaller number higher, try a ferrite rod as a former or salvage a ready made coil from an old broken radio. Experiment with different lengths of antenna wire. I also find these sets work better with a higher quality air spaced variable capacitor which you can buy from a radio rally or you could try J. Birkett suppliers of electronic components who always stocks them at reasonable prices, TEL NO. +44 (0)1522 520767. The company is UK based and may not export, but I am sure that you will know of local electronics suppliers for such parts.

I hope you have enjoyed reading about the crystal set and if you have built the one from this page e mail me and let me know how it went. If this page has interested you and you would like to build more sets check out my other web pages or web links page.

BACK TO M0DAD HOMEPAGE

A Simple Crystal Radio Set

Whether you are a beginner or a seasoned expert, you would probably agree that there is nothing quite like using this simple design to make a crystal radio and enjoying it, listening to stations both near and far. Add to this the "something for nothing" advantage of not having to power this set with batteries or AC line and you can see why this simple design will be used and enjoyed for a long time to come. Almost like magic... Let' build one!


A1
C1
D1
L1
C2
R1
High
Impedance
Headphones
G1

A Simple Crystal Design

Components:

- **A1- 50-100 foot longwire antenna**
- **C1 - 50 pf ceramic capacitor OSE p/n CD-5**
- **C2 - 365 pf variable capacitor OSE p/n BC14400**
- **D1 - 1N34A diode OSE p/n 1N34A**
- **G1 - Ground (see instructions below)**
- **L1 - 100 turns of #20 AWG enamel coated copper wire OSE p/n MW20, adjustable tap (see instrctions below)**
- **R1 - a 100k ohm resistor OSE p/n RQ100K**
- **Crystal Earphones OSE p/n CE748**
- **Fahnestock clips OSE p/n 2090**


A1
To Antenna
Fahnestock
Clips
C1
L1
D1
C2
R1
To
Headphones
G1
To Ground

Layout on a "Breadboard" for the Simple Crystal Tuner

Looking at the diagram above, one can see how easily the crystal set can be laid out on a breadboard setup.

- **A1 - this is the antenna. In this case it is a "random length" longwire antenna, usually about 50-100 feet, but in some areas a shorter length will work. In general (especially on the AM broadcast band) the longer the better, but 100 feet should work quite well. A safety note on setting up an antenna - Never, never, NEVER string up an antenna or any of its components where it can possibly come in contact with power lines! If it falls on a power line, the results can be FATAL!!!**
- **C1 - a 50 pf (picofarad) ceramic capacitor. This allows the signal to reach the receiver, but will stop any DC (direct current) charge.**
- **C2 - 365 pf variable capacitor, or your tuning capacitor. The base is attatched to the ground end of the coil and the tab sticking out of the side is the connection toward the antenna.**
- **D1 - a 1N34A diode - this is the "detector" part of your radio.**
- **G1 - This is your ground, in rough terms, creates a counterpoise for your antenna. Depending on your situation, you can use a metal cold water pipe or a metal rod driven into the ground (usually 8 feet, but I have gotten away with a shorter one). Do NOT use a pipe that may be attatched to any gas appliance, which includes a hot water pipe!**
- **L1 - The tuning ground coil,100 turns of #20 AWG enamel copper wire on a length of paper towel roll (It works out to about 4 inches). The ground is attatched to one end as well as the middle , which can be made by scraping off the top so that the metal wire is exposed and using a slider contact(adjustable tap), or if you are adept at making taps, place the taps every 10 turns or so. It is variable by moving the slider or the connection at the taps up and down, shorting out the unused portion of the coil and changing its value. Using double-stick tape helps the coil from slipping when winding it and when it's in use.**
- **R1 - a 100k (kilo-ohm, a value of resistance) resistor. This helps raise the impedance of the headphones somewhat. You can get away without using it, but it does help.**
- **High impedance headphones - The best one to use is a set of 2000K ohm impedance headphones, but a cheaper alternative is a 1000k crystal earpiece.**
- **Fahnestock clips - Simple spring clips that can be screwed into a base such as wood and allow one or more wires to be attatched together.**

---

portable
DX
pedestrian mo
contests
vk3ye dot com
CW
antennas
shortwave
CB
videos
HF

Return to VK3YE amateur radio projects

A simple crystal set for free power radio

Of any electronic project, the crystal set would have to rate as one of the most popular. Many amateurs are on the air today because of their early construction of a crystal set. Most practical electronic books for beginners include at least one crystal set project. Unfortunately, some of these circuits take simplicity too far and deliver mediocre performance, often by omitting key components such as the tuning capacitor, or failing to provide coil taps.



This article describes a crystal set of medium complexity. It features coil taps for the antenna and diode to make it useful for both country and metropolitan listeners. The taps allow the set to cover 160 metres if desired. All parts are easily obtainable, making it a good choice for the beginner. The endless possibilities for experimentation also make crystal sets interesting novelty projects for experienced constructors. The schematic is shown here:


Ant
Inductor
(see fig 2)
OA95
10 - 415pF
Tuning
1000pF
Disc ceramic
Headphones
High impedance
Earth

VK3YE Crystal Set

Schematic & Layout diagrams

Press Back button to return to main article

Figure One: Schematic diagram of crystal set


Tuning
Cap tap
Diode tap
90
78
66
54
42
30
18
6
84
72
60
48
36
24
12
0
Antenna
Antenna tap
Headphones
Earth
55 mm

Figure Two: Rear view of front panel, showing coil details

(from Amateur Radio February 2001, page 20)

Obtaining the parts

Tuning capacitor

A large air-spaced type, covering about 10 to 415 picofarads is preferred. These capacitors were common in valve and early transistor radios and often appear at hamfests. Their long shafts make it easy to attach large tuning knobs. When purchasing one see that the shaft turns freely, but is not loose. Ensure that the plates are straight and do not touch when meshed - use a multimeter (preferably with audible continuity function) to test this. Avoid capacitors with 3/8 inch shafts unless nothing else is available â€“ knobs for these are not obtainable, and an old valve radio dial drum will need to be used instead.

If a large capacitor is unavailable, a small plastic dielectric unit is suitable (such as stocked by Jaycar and online). The lower maximum capacitance (160 pF) means that more coil turns are required to provide coverage of the lower end of the broadcast band. This can be partially overcome by connecting the 60 and 160 pF sections in parallel (link the 'A' and 'O' tabs). The main disadvantage of these capacitors is their short shafts, which makes it harder to attach most types of knobs.

Vernier Drive and dial

The use of a vernier reduction drive is not necessary. However, its inclusion makes tuning easier, particularly on the higher frequencies. These are rare new but sometimes come up at hamfests. If your drive lacks a dial, one can be fashioned from a plastic or metal disc, such as a jar lid or salvaged computer hard disc. Glue the dial directly to the skirt of the tuning knob if you lack a vernier drive.

Diode

This is the most easily obtainable and cheapest component in the project. A germanium diode, such as a 1N60, 0A90, 0A91, 0A95 or 1N34A will be suitable. The purists still make their own diode detector with a 'cats whisker' and lump of galena, but modern diodes provide more stable and repeatable performance.

Headphones

The very old high impedance headphones are required for this circuit. A minimum of two kilohms is suggested. Medium impedance headphones (approx 600 ohms) will also work, but are less sensitive.

High impedance headphones have become difficult to obtain. Alternatives include:

1. Old-style telephone earpiece. Quite sensitive. Found in the old Telecom corded phones.

2. Crystal earpiece. These are sensitive, easy to obtain and inexpensive. You may need to connect a 100k - 470k resistor in parallel for it to work properly.

3. Piezo transducer. Believe it or not, these actually will work as an earphone. Some sizes even fit snugly in the outer ear in a similar manner to modern earpieces, such as used with mobile phones. The main drawback with transducers is their peaky audio response. Â In some cases it may be necessary to wire a 100k - 470k ohm resistor across the earphone connections for correct operation.

4. 1k to 8 ohm audio transformer and standard low-impedance headphones. Works well, but not as sensitive as a crystal earpiece.

5. Cheating! Use a transistor or IC amplifier kit to run a speaker. This approach eliminates the 'free radio' advantage of the crystal set, but provides louder reception in weak signal areas and allows speaker listening.

Coil and Coil former

This needs to be a cylinder about 55 millimetres in diameter and 150 mm long. The length needs to be long enough to accommodate all ninety coil turns used, with enough left over for mounting to the front panel. Plastic pipe, shampoo container or similar will suffice. Though enamelled copper wire can be used for the winding, the prototype used thin plastic-covered stranded insulated wire.

Front panel

All parts are mounted on a 6mm-thick polyethylene chopping board, which forms the front panel. A hacksaw was used to cut the panel to fit inside the wooden case. Use the thinnest chopping board available so that the many screw-mounted sockets used can be fastened properly. The front panel pictured was cut to 240 mm square.

Case and handle

Use non-metallic material for the enclosure. The box used in the prototype was originally a speaker bought cheaply at a school fete. The lid (which held the speaker) was removed, and the rest of the box painted. The top carry handle is optional and came from a hardware store.



Construction

Commence construction once all components have been obtained. Plan how the parts will fit behind the front panel. The diagram and pictures above show the arrangement used in the prototype. The coil is fastened with stand-offs and the variable capacitor is screwed to an aluminium L-shaped bracket. 4mm binding posts with banana sockets are used for the antenna and headphone connections, and 2mm micro sockets for the coil tapping points.

Start by winding the coil. This consists of ninety turns of thin stranded insulated wire close wound on a plastic tube approximately 55 millimetres in diameter. A large number of tapping points are provided so that the user can vary the set's frequency coverage, and antenna and diode coupling. This makes it possible to obtain the best compromise between volume and selectivity for a particular station.

Figure Two shows the coil construction. Start from the earth end (identified as '0' in the diagram). Make two holes in the former to anchor the end of the wire. Wind six turns and then an extra half-turn. With a knife remove about 1cm of insulation, taking care not to cut the wire. Form the bare wire into a loop and lightly coat with solder. Do not apply excessive heat - the wire insulation easily melts. Wind another five and a half turns and make another tap. Repeat for the remainder of the coil until approximately ninety turns have been wound. Add more turns and taps if using a smaller variable capacitor than specified. Again make two small holes in the former to anchor the wire.

Place the completed coil aside and start work on the front panel. Mount the 4mm banana binding post terminals for the antenna, earth and headphones, as shown in Figure Two. Drill holes and mount the 2mm terminals for the coil taps and the antenna, diode, variable capacitor taps. The tuning capacitor can also be fastened at this time.

Two sets of screws and spacers can be used to mount the coil to the rear of the front panel. A 10mm separation between the coil and the panel is adequate. Solder in the various components and connecting wires as per Fig 2. Use insulated wire for the connections between the sockets and to the variable capacitor. Tinned copper wire can be used for the short links between the coil taps and the 2mm sockets. Use insulated wire for the three jumper leads. The jumpers should be sufficiently long to be able to make connections with all taps along the coil.

This completes the construction. The panel can now be inserted into the box. In the unit pictured, the front panel is recessed â€“ this protects the banana sockets and dial and makes the set more rugged. It also allows attachment of a hinged lid if required.

Parts List

* 10 â€“ 415 pF variable capacitor x1 (see text)

* 0.001 uF disc ceramic capacitor x1

* 1N60 germanium diode x1

* Vernier dial or drive x1 (optional)

* 2mm micro socket x19

* 2mm micro plug x6

* Banana socket (red) x2

* Banana socket (black) x2

* Insulated wire 20m

* Tinned copper or bell wire 1m

Other items: case and handle; polyethylene chopping board; Coil former â€“ 55mm dia, 150 mm long; screws, nuts, washers and spacers; mounting bracket for variable capacitor.

How it works

To receive signals, a radio circuit must perform three functions: selection, detection and reproduction.

The inductor and variable capacitor form a tuned circuit. The role of the tuned circuit is to select one of the many signals present at the antenna. The size of the inductor and capacitor determines the frequencies that can be tuned. The capacitor is made variable to allow the full range of AM broadcast band frequencies (531 to 1602 kHz) to be received.

The diode detector converts the selected radio frequency signal to an electrical current varying at audio frequencies.

The headphones convert this audio frequency energy to sound. The principle is similar to a relay â€“ the signal cause current to flow in a winding that forms an electromagnet. The magnetism generated vibrates the metal diaphragm, thus creating sound. Crystal earpieces perform the same function, but rely on the piezo-electric effect.

Unlike in a conventional radio, which uses amplifying devices such as transistors and integrated circuits, crystal sets are powered by the signal from the incoming station, so no batteries is required. If provided with an efficient antenna and earth, crystal sets can receive signals thousands of kilometres away.

Antenna and earth

A crystal set requires a wire antenna to operate properly. The longer and higher it is the better. A length of at least 10 metres in urban areas, and 20 â€“ 30 metres elsewhere should provide reception in most cases. The antenna should always be installed away from power lines for safety reasons and to reduce interference pick-up. An existing amateur or TV antenna can also be effective, especially if the coaxial feedline is used as part of the antenna. This is achieved by connecting both the outside and the inside of the coaxial connector to the receiver's antenna terminal.

An earth provides stronger signals, and is essential in remote areas. In homes with copper water pipes, this can simply be a lead to the nearest cold water tap. In newer homes, where plastic pipes are used, an outside ground stake can be used instead.

For long distance reception (hundreds or thousands of kilometres) more than usual effort needs to be taken when installing the aerial and earth. Reference One suggests a length of about 100 metres and a height of at least 12 metres. A series of buried radials is suggested for the earth, rather than the water pipe suggested above.

Operation

Connect antenna, earth and earphones. Install the three jumper leads. Set the capacitor tap to near the top of the coil (either the 78th or 90th turn) and the diode and antenna taps to approximately midway along the coil.

In a quiet room, adjust the tuning control and listen for a station. If several stations are audible, move the diode or antenna taps nearer the earth end (lower numbered turns) of the coil. This increases the set's selectivity and makes it possible to separate stations. In a capital city it should be possible to separate at least nine or ten stations. Optimum tap settings vary across the broadcast band â€“ lower frequency stations are often best received with higher tap settings. In rural areas volume is normally more important than selectivity, so the taps can be moved near the top of the coil.

Reception of AM operators on the 1.8 MHz (160 metre) amateur band is possible by moving the capacitor tap lower down the coil, to the 54th or 66th turn. Performance will be well down on a superhet or regenerative receiver, and SSB signals cannot be resolved. Whether you hear amateurs or not depends on your antenna system and the extent of activity from nearby operators. Here in Melbourne 160 metre AM activity includes the Monday to Saturday AM morning net starting at 11am.

In many areas there are narrowcast stations between the top of the official AM broadcast band and 160 metres. Because of their low power these stations will be weaker than the mainstream broadcasters. However these stations are excellent tests of your receiver and antenna system.

Video demonstrations of this project

Conclusion

A crystal set of moderate complexity has been described. It is the minimum required to provide good reception of local stations in urban and rural areas. However numerous refinements to increase sensitivity, selectivity or audio output can be made. These include:

1. Double tuned circuits (with variable coupling between them) to improve selectivity

2. Use of a tuned trap to null out interfering signals

3. Attention to the construction of coils to provide the highest possible Q

4. Addition of an impedance matching network to provide efficient power transfer between the antenna and the tuned circuit

5. Use of a large loop antenna for the coil to allow reception of signals without an external antenna and nulling of unwanted signals

6. Voltage doubler diode detector circuit using two diodes to increase volume

7. Use of DC bias (from a DC voltage applied to the diode) or RF bias (from a locally generated RF signal on the receiving frequency) to improve sensitivity, or, in the case of the latter, to provide CW and SSB reception.

8. Use of a Q multiplier to increase sensitivity and allow CW and SSB reception.

Should you decide to experiment with these changes, it would be desirable to keep this set as a reference and build a second receiver as a test bed for the experiments.

Obtaining the parts

Suitable parts were discussed in detail above. Many if not all can be bought online, with examples presented below.

Variable capacitor and knob

Part II: Diode Test Data Report

Back to Lab..

Test Results

Over a period of several weeks in 2013 I ran I-V characterization measurements on a good number and variety of diodes, crystals and my two tubes to see how very thing stacks up. The following presents the resulting curves, diode photos, and some puzzling questions/conclusions I churned up in the process. These Characteristic Curves carry the voltage out to 2.0 Volts, well beyond any signal strength one might expect to receive with a crystal set. This is important to note because the curves themselves are dominated by the diode series resistance. After each discussion I then include my spreadsheet with the detail DX-level analyses that provide the critical information about diode "n", (Ideality factor) "Is", (Reverse Saturation current) and "Ro", (Zero-bias Diode resistance). These are the data the set designer requires.

I start off with the realization that when one orders diodes, it is by no means certain what one will get. This seems especially true for the supposedly ubiquitous 1N34A. Unless you see the part number actually on the diode, you probably need to test it to know what it really is. So, lets take a look!

Germanium Diodes



1N34A series


1N34A


1N34A-g


1N34A r


1N270 37


D18

1N270-277 series


1N277


1N23



(277) 1N34A b



1N270



1N141



D9E



GAZ 51



OA5

ITT Diodes, Something special here.



FO-215



AA-143

One oddball Ge diode, not sure what it is for..

Here we see a set of Germanium diodes and photos of the diodes under test. Immediately you should notice two sets of curves, what I call the "1N34A" set and the "1N270-277" set. In this analysis, the second set appears clearly superior in sensitivity and deservedly so. In the photos it is clear that one bunch of diodes I purchased as 1N34A were in fact better 1N277, the black band and thin gold contact wire as well as common curve unite these. "True" 1N34A's have a more robust contact wire. I also purchased a 1N270 and received pretty orange diodes with the number "37" stamped on it, a fairly robust contact wire and a curve that most closely resembles a 1N34A, go figure. Mercifully, I DID manage to get some bona-fide 1N34A's with the part number on the diode, as well as a single bona-fide ITT 1N270 diode with the part number. These are my base for comparison.
In addition to the standard Germanium Diodes tested above, I also have latched my hands on a few "other" germanium diodes for the fun of testing. These include two vintage Russian types, a D9E (in the 270 class) and a D-18 (transitional between 270 and 1N34A). Additionally, I acquired a few FUZZ diodes popular, I suspect, with the guitar gadget crowd. These are larger packages in metal cases so I cannot see how the internal contact is made other that they are stated to be gold bonded point contact type. Clearly these are highly sensitive diodes in my 270 class, the OA5 looking best of the lot. Interestingly, I recently purchased from good Mr. Peebles a few of his "Holy Grail" ITT FO-215 diodes. My measured characteristic for one of these is a dead lay down on the gold-bonded OA5. From the photos, these are in different packaging with the FO-215 in a traditional glass casing. What makes the FO-215 so great is the fact that its resistance Rd is an interesting 150k ohm or so which matches very well with typical moderate Q tank circuits. Interestingly, I find that an old Russian D18 diode has very similar characteristics to the FO-215 and so must also be placed into the "Holy Grail" class of germanium diode. Take your pick!

Spreadsheet for calculation of Germanium diode n and Is (modified from Mike Tuggle's spreadsheet)



Spreadsheet for calculation of diode n and Is					Tuggle Method from "Cal_n_Is.xls"					
Diode		n	Is	Ro	Temperature		Vd2	Id2	Vd1	Id1
under test			nA	k Ohm	dF	dC	V	uA	V	uA
FO-215	ITT	1.0993	196	144	80.7	27.1	0.03574	0.49730	0.05123	1.00250
FO-215	ITT	1.1050	175	163	80.9	27.2	0.03882	0.50990	0.05735	1.13850
GAZ 51	Tesla	1.5152	617	64	83.1	28.4	0.02356	0.50850	0.03782	1.00240
GAZ 51	Tesla	1.1379	140	211	82.9	28.3	0.04491	0.50280	0.06275	1.03850
1N23	53p	1.3455	472	74	81.8	27.7	0.02525	0.50460	0.04050	1.04320
1N23	14p	1.2546	240	135	82.0	27.8	0.03665	0.50490	0.05325	1.00390
1N270	ITT	1.2790	915	36	82.4	28.0	0.01432	0.49660	0.02437	0.99860
1N141	blue	1.1795	726	42	85.1	29.5	0.01642	0.51540	0.03075	1.25650
1N141	blue	1.2570	1402	23	84.5	29.2	0.01024	0.51750	0.01795	1.02980
1N695	ITT	1.1160	83	342	71.2	21.8	0.05650	0.52880	0.07335	1.02800
1N695	ITT	1.0930	73	379	70.8	21.6	0.05965	0.55890	0.07423	0.99800
AA143	ITT	1.1220	218	130	71.2	21.8	0.03420	0.50930	0.0495	1.02790
AA143	ITT	1.1575	242	121	71.2	21.8	0.03275	0.49950	0.05024	1.10580
1N270	blue	1.6610	2310	19	82.4	28.0	0.00835	0.49630	0.01635	1.07150
1N270	blue	1.2590	857	38	82.5	28.1	0.01505	0.50440	0.02829	1.18850
D310	russia	1.0059	1215	21	83.6	28.7	0.00915	0.51170	0.01695	1.11490
1N277	black	1.4990	2293	17	81.5	27.5	0.00765	0.50180	0.01402	1.00250
1N277	black	1.6042	2296	18	81.6	27.6	0.00821	0.50400	0.01639	1.11620
OA 5	Tesla	1.8490	3384	14	83.4	28.6	0.00664	0.50370	0.01255	1.01480
OA 5	Tesla	1.4810	1996	19	83.3	28.5	0.00865	0.50550	0.01645	1.07020
D9E	russia	1.5350	2414	16	81.1	27.3	0.00748	0.50250	0.01522	1.13280
D9E	russia	1.4200	2161	17	80.6	27.0	0.00755	0.49570	0.01402	1.01000
D18	russia	1.2040	194	160	82.5	28.1	0.04004	0.50910	0.05913	1.10500
D18	russia	1.2706	193	170	82.9	28.3	0.04215	0.50250	0.06415	1.16550
1N34A	red	1.3220	993	34	83.6	28.7	0.01401	0.50250	0.02475	1.05390
1N34A	red	1.3430	833	42	83.3	28.5	0.01675	0.51570	0.02765	1.01250
GD 402A	russia	1.7080	1360	33	83.6	28.7	0.01365	0.49200	0.02785	1.19350
GD 402A	russia	1.5535	970	41	83.4	28.6	0.01719	0.51780	0.03185	1.17270
1N34A	green	1.3210	1554	22	82.9	28.3	0.00945	0.49530	0.01695	0.99850
1N34A	green	1.3030	1185	28	83.1	28.4	0.01175	0.49420	0.02135	1.04750
1N34A	green	1.5740	1389	29	82.7	28.2	0.01237	0.49350	0.02327	1.07190
1N34A 37	orange	1.0955	1458	19	83.3	28.5	0.00861	0.51740	0.01495	1.01250
1N34A 37	orange	1.3550	1370	26	83.6	28.7	0.01091	0.49990	0.01925	1.00190
1N34A	bonafide	1.8220	2153	22	81.6	27.6	0.00995	0.50780	0.01911	1.08050
1N34A	bonafide	1.2500	1392	23	82.2	27.9	0.00995	0.50250	0.02014	1.20570
1N141	germanium	1.2795	292	114	85.4	29.7	0.03316	0.50000	0.04992	1.01950
1N141	germanium	1.1795	726	42	85.1	29.5	0.01642	0.51540	0.03075	1.25650
1N141	germanium	1.2570	1402	23	84.5	29.2	0.01024	0.51750	0.01795	1.02980
1N141	germanium	1.3090	1339	25	84.7	29.3	0.01075	0.49870	0.01915	1.01450
1N91	fwd	2.0000	16564	3	71.4	21.9	0.00788	2.88500	0.01526	5.83110
1N91	rev	2.0000	12442	4	71.6	22.0	0.00827	2.74150	0.01976	5.94010
1N91	fwd	2.0000	18868	3	71.2	21.8	0.00741	3.05400	0.01354	5.79000
1N91	fwd	2.0000	22098	2	71.2	21.8	0.00661	3.33300	0.01180	5.80500
1N91	fwd	2.0000	20144	3	71.2	21.8	0.00703	3.18400	0.01305	5.92800

The above spreadsheet is based on measurements of the diodes shown above. For the determination of Is and n, I chose at random two examples from my collection of various diodes, (all germanium in this case) and measured via a modified version of the methodology outlined by Ben Tongue and Mike Tuggle. For this work I have chosen to set Id2 about 0.5uA and Id1 about 1.0uA and then read the needed voltage. This is the inverse of the normal method but the justification is that for any diode regardless of forward voltage drop the measurement is made at the same part of the LOG I vs V characteristic. This allows comparison between all diodes. I have included the actual room temperature in the calculations in order to eliminate this variable as a source of doubt or error. All the measured parameters as well as the determined results are presented in order to facilitate repeatability.

A final note on the plots above. You will have noticed that I sub-divide germanium diodes into a "1N34A" class and a "1N270-277" class. This is a result of looking at their I / V characteristics on a plot of 1 - 2V DC versus 0 - 10mA scale. At such a scale the slope of the characteristic for the 1N270 class remains much steeper than that for 1N34 type diodes. As this is not seen as a distinguishing feature at the small-signal scales looked at here, I judge the chief difference between the two types lies in the diode series resistance Rs. This impacts strong-signals but is of no concern for small-signal DX work. Just so you know.

Schottky Diodes



HP5082-2835


1SS98


1N5711


SD103A


? 1N34A


1N60

BAT46



1N5819


1SS16


1SS99

Schottky diodes are very sensitive diodes that work excellently in crystal radios. Their construction and theory are different and I confess to not fully understanding these components. Still, from the characteristic curves, they are excellent! Again, note that you don’t always get what you bargain for. Here I found what was supposed to be 1N34A's to be some sort of Schottky of unknown pedigree. The 1N5819, while having the lowest forward voltage drop, has a rather very high Junction Capacitance and will not perform well. Posts on the RaidoBoard Crystal Radio Forum however highly recommend the 1N5711 for crystal sets although the characteristic curve doesn’t look that fabulous. Many web pages out there on Shottky diodes, I recommend you do your homework. Of all the schottky's, I note that Ben Tongue recommends most highly the HP5083-2835. The high resistance Ro makes them useful for DX sets with very very high Q tanks. Even so the diodes need to be paralleled with up to 4 or 5 diodes to match correctly the Rd with the tank Rp. I have found these somewhat hard to find and expensive, especially when one requires using several in parallel. I recently measured a few 1SS98 diodes and I discover them to have characteristics extremely similar to the HP and I feel they deserve more attention. Sadly, on ebay they seem to be just as difficult to find and expensive. No free ride!

Spreadsheet for calculation of Schottky diode n and Is (modified from Mike Tuggle's spreadsheet)



Spreadsheet for calculation of diode n and Is Tuggle Method from "Cal_n_Is.xls"

Diode		n	Is	Ro	Temperature		Vd2	Id2	Vd1	Id1
under test			nA	k Ohm	dF	dC	V	uA	V	uA
1N5711	blue	1.0733	6	4816	80.2	26.8	0.12323	0.4917	0.14261	0.9979
1N5711	blue	1.0683	6	4541	80.0	26.7	0.12115	0.4917	0.13981	0.9757
1SS98		1.0753	12	2302	83.8	28.8	0.10430	0.5001	0.12383	1.0208
HP 5082-2835		1.0713	12	2206	80.2	26.8	0.10215	0.4961	0.12215	1.0384
1SS98		1.0626	13	2188	83.8	28.8	0.10245	0.5081	0.12085	1.0036
HP 5082-2835 * 4		1.0713	48	574	80.2	26.8	0.10215	0.4961	0.12215	1.0384
1N5711 * 8		1.0683	48	572	80.0	26.7	0.12115	0.4917	0.13981	0.9757
SD103A	50pF	1.0435	109	247	83.4	28.6	0.04648	0.5021	0.06305	1.0201
SD103A	50pF	1.0443	112	241	83.3	28.5	0.04611	0.5053	0.06185	0.9934
BAT 46		1.1185	141	204	80.0	26.7	0.04304	0.4878	0.06032	1.0055
BAT 46		1.1839	172	177	80.7	27.1	0.04173	0.5048	0.05839	0.9972
1N60		1.1040	161	176	80.0	26.7	0.03989	0.4955	0.05729	1.0508
1N60		1.0884	178	158	80.4	26.9	0.03743	0.4988	0.05311	1.0065
1N34A ?	schottky	1.1104	317	90	80.4	26.9	0.02710	0.5019	0.04068	1.0003
1N34A ?	schottky	1.2359	482	66	80.4	26.9	0.02269	0.5016	0.03615	1.0197
1N5819	100pF	1.1881	750	41	80.6	27.0	0.01551	0.4957	0.02586	0.9975
1N5819	100pF	1.1425	807	36	80.7	27.1	0.01453	0.5155	0.02541	1.1074
1SS99	4.8n	1.3760	1840	19	82.2	27.9	0.00885	0.5205	0.01575	1.0265
1SS99	6.2n	1.3450	1815	19	82.2	27.9	0.00875	0.5201	0.01685	1.1335
1SS16	NEC	2.2700	4101	14	81.5	27.5	0.00684	0.5083	0.01385	1.0947
1SS16	NEC	6.2400	14288	11	81.3	27.4	0.00564	0.5099	0.01165	1.0733

The above spreadsheet is based on measurements of the diodes shown above. For the determination of Is and n, I chose at random two examples from my collection of various diodes, (all schottky in this case) and measured via a modified version of the methodology outlined by Ben Tongue and Mike Tuggle. For this work I have chosen to set Id2 about 0.5uA and Id1 about 1.0uA and then read the needed voltage. This is the inverse of the normal method but the justification is that for any diode regardless of forward voltage drop the measurement is made at the same part of the LOG I vs V characteristic. This allows comparison between all diodes. I have included the actual room temperature in the calculations in order to eliminate this variable as a source of doubt or error. All the measured parameters as well as the determined results are presented in order to facilitate repeatability.

Note in the above data that both the BAT-46 and the 1N60 diodes appear to have excellent properties for crystal radio work. In fact they have very similar parameters overall. Looking at the photos you should also note that the two types of diode look suspiciously exactly alike. The BAT 46 has it correct markings but the 1N60 is unmarked. You never know what you get!

Silicon Diodes



1N914


1N4148





Silicon diodes have good characteristics, but an unacceptably high forward voltage drop making them a very poor choice for crystal radio unless used with bias. The 1N4736A is a Zenner diode.

Spreadsheet for calculation of Silicon diode n and Is (modified from Mike Tuggle's spreadsheet)



Spreadsheet for calculation of diode n and Is							Tuggle Method from "Cal_n_Is.xls"			
Diode		n	Is	Ro	Temperature		Vd2	Id2	Vd1	Id1
under test			nA	k Ohm	dF	dC	V	uA	V	uA
1N914		1.9510	5.4	9.3E+03	82.0	27.8	0.22733	0.4895	0.26229	0.9855
1N914		2.0236	6.9	7.6E+03	82.9	28.3	0.22354	0.4857	0.26423	1.0653
1N4148		1.9950	5.8	8.9E+03	83.1	28.4	0.23194	0.5117	0.27037	1.0841
1N4148		2.0041	5.6	9.3E+03	83.3	28.5	0.23177	0.4803	0.27346	1.0801
1N4007		1.5139	0.6	6.4E+04	83.3	28.5	0.26320	0.5041	0.29137	1.0355
1N4007		1.5140	0.5	7.8E+04	83.3	28.5	0.26951	0.4885	0.29807	1.0133
6A10		1.5680	2.1	1.9E+04	83.3	28.5	0.22129	0.4902	0.25023	1.0026
6A10		1.5368	2.0	2.0E+04	83.3	28.5	0.22021	0.4942	0.24764	0.9871
1N4736A	Zener	1.1505	0.00002	1.9E+09	83.4	28.6	0.51439	0.4961	0.53702	1.0609
1N4736A	Zener	1.1365	0.00001	2.5E+09	83.4	28.6	0.51663	0.5017	0.53648	0.9853
KB 130	russian	1.1403	0.00005	5.8E+08	83.4	28.6	0.47531	0.5012	0.49587	1.0061
KB 130	russian	1.1649	0.00007	4.4E+08	83.4	28.6	0.47567	0.4929	0.49746	1.0155
UK H	russian	1.9443	8	6.3E+03	83.6	28.7	0.20333	0.4486	0.24405	1.0175
UK H	russian	1.7727	4	1.3E+04	83.1	28.4	0.22717	0.5148	0.25707	0.9916
UK I	russian	1.7807	0.1770	2.6E+05	83.1	28.4	0.36493	0.4888	0.39684	0.9775
KD 401A	russian	1.5115	0.1679	2.3E+05	83.3	28.5	0.31083	0.4752	0.33924	0.9828
KD 401A	russian	1.3846	0.0233	1.5E+06	83.3	28.5	0.35841	0.5152	0.38382	1.0472
D 220	russian	1.2586	0.1010	3.2E+05	83.4	28.6	0.27732	0.5039	0.30100	1.0427
D 220	russian	1.2447	0.0599	5.4E+05	83.6	28.7	0.29013	0.4877	0.31682	1.1167
D 223A	russian	1.1983	0.0030	1.0E+07	83.4	28.6	0.37171	0.4857	0.39716	1.1036
D 223A	russian	1.1954	0.0036	8.6E+06	82.9	28.3	0.36418	0.4732	0.38845	1.0378
UK J	russian	1.4617	4	9.8E+03	82.7	28.2	0.18415	0.4985	0.21154	1.0334
UK J	russian	1.3988	2	2.0E+04	82.7	28.2	0.20325	0.4978	0.22879	1.0108

The above spreadsheet is based on measurements of the diodes shown above. For the determination of Is and n, I chose at random two examples from my collection of various diodes, (all silicon in this case) and measured with a modified methodology to that outlined by Ben Tongue and Mike Tuggle. In this case, with the radically different forward voltage drop of these diodes from Germanium or Schottky diodes, I have kept the Id values constant (about Id2=0.5uA and Id1=1.0uA) and varied Vd. I have included the actual room temperature in the calculations in order to eliminate this variable as a source of doubt or error. All the measured parameters as well as the determined results are presented in order to facilate repeatability.

Light Emitting Diodes


LED Characterization
Red 1.8v
Green 2.1v
Yellow 2.0v
Amber 2.1v
Gn-Wht
mA
10
9
8
7
6
5
4
3
2
1
0
0.50
1.00
1.50
2.00
2.50
3.00
V

Red 1.8v


Green 2.1v



As long as I am measuring various and sundry diodes, I figure I ought to include that most ubiquitous of modern diode, the LED. Found everywhere, these diodes are rapidly becoming the low-energy light source of choice for many lighting applications. I have read occasionally of someone asking whether these ought to be useful for radio applications as well. To this question the answer is generally a resounding "No!". The turn-on voltage is waaay above any reasonable value expected to be delivered by an antenna to a crystal set. Still, this simple answer avoids the actual question, what in fact does the characteristic curve of a LED really look like? Where is the turn-on voltage with respect to the published junction voltage, (assuming you can find that).
To provide just such a look I visited my local electronics store and bought a small handful of LED's, most with the junction voltage listed and took them home to measure. Typical LED junction voltages seem to range from about 1.8v to 2.1v or more. The turn-on voltages look closer to 1.6v-1.7v. Anyone used to working with Carborundum crystals or silicon diodes will be used to biasing their rectifier to get good sensitivity. These LED's once on have a very sharp rise and with a proper bias should work quite well as detector diodes. As a bonus you will get a sweet glow as well. OK, not as cool as the glow of a vacuum diode, but certainly more sensitive!

Spreadsheet for calculation of Light Emitting Diode n and Is (modified from Mike Tuggle's spreadsheet)



Spreadsheet for calculation of diode n and Is Tuggle Method from "Cal_n_Is.xls"

Diode	n	Is	Ro	Temperature		Vd2	Id2	Vd1	Id1
under test		nA	k Ohm	dF	dC	V	uA	V	uA
Red	2.1547	3.3E-08	1.7E+12	80.7	27.1	1.30114	0.4995	1.33895	0.9875
Red	2.0720	9.7E-09	5.5E+12	80.7	27.1	1.31649	0.5038	1.35690	1.0745
Amber	1.5627	1.9E-13	2.1E+17	80.4	26.9	1.42768	0.5046	1.45571	1.0131
Amber	1.6163	6.4E-13	6.5E+16	80.2	26.8	1.42525	0.4963	1.45532	1.0229
Yellow	1.5860	5.1E-14	8.0E+17	80.4	26.9	1.50347	0.5065	1.53292	1.0422
Yellow	1.3763	1.2E-16	2.9E+20	80.7	27.1	1.51826	0.5003	1.54291	1.0031
Green	2.0490	1.2E-09	4.2E+13	80.7	27.1	1.41068	0.5116	1.44647	1.0082
Green	2.0650	1.2E-09	4.3E+13	80.4	26.9	1.42153	0.5075	1.45762	1.0009
Water Green	3.2709	1.7E-09	4.8E+13	80.4	26.9	2.22240	0.5085	2.27970	1.0045
Water Green	1.9273	8.6E-16	5.8E+19	80.9	27.2	2.03170	0.5099	2.06510	0.9993
White-Gn	1.4366	3.5E-16	1.1E+20	80.9	27.2	1.54780	0.5143	1.57610	1.1050
White-Gn	3.0358	1.1E-05	6.9E+09	80.7	27.1	1.37740	0.5111	1.43020	1.0043

The above spreadsheet is based on measurements of the diodes shown above. For the determination of Is and n, I chose at random two examples from my collection of various diodes, (all led's in this case) and measured with a modified methodology to that outlined by Ben Tongue and Mike Tuggle. In this case, with the radically different forward voltage drop of these diodes from Germanium or Schottky diodes, I have kept the Id values constant (about Id2=0.5uA and Id1=1.0uA) and varied Vd. I have included the actual room temperature in the calculations in order to eliminate this variable as a source of doubt or error. All the measured parameters as well as the determined results are presented in order to facilitate repeatability.

Crystal Galena and Pyrite Diodes



The above curves demonstrate the wide variation in properties and qualities that can be found in natural crystals of galena or pyrite, the two most common and best quality natural stones. In each crystal test I first poked around the crystal for some time to 1) determine a typical sensitivity for the crystal in question and 2) to locate the best hot spot with which to test. This turns out to be a non-trivial exercise on the diode test setup. In a crystal radio one need only listen for the loudest spot. With the test setup one needs test both the forward and reverse current in order to determine if the whisker is on a hot spot or not. Very tedious work! (In retrospect, if I were starting over making a test jig, I would definitely add a DPDT switch to readily change between forward and reverse current measurements. I'd probably toss in a rheostat for fine adjustments as well).

For many crystals there are limited number of possible hot spots, but these may be hot indeed. For most of my "Steel Galena" samples (Tintic Utah, or Leadville Colorado) there are numerous hot spots under virtually every place I touch the probe, but in general the sensitivity is good to so so. These crystals are very kind to work with in terms of finding spots and avoiding frustration. Mirror galena on the other hand may have quality hot spots, but any hot spots at all are rare and frustratingly difficult to locate. Here my Philmore detector crystal shines with an almost ideal "Galena" response. To chase down this rabbit I purchased some lovely mirror galena from Sweetwater Missouri. I broke off a few appropriate-size chunks to pot in woods metal and test. At first I was very excited with the high currents I was seeing at moderate voltages. Figured I had struck gold. When these crystals failed miserably to rectify anything in my radios, I re-measured things in both forward and reverse directions. These crystals obey Ohm's law and act like typical resistors, not suitable for radio work at all.

For my pyrite crystals the work has been especially tedious and frustrating. With one of the crystals one "hot spot" alternated, entirely on its own, between hot and bad while I was making the measurements. I would start over and over, sometimes getting interesting readings then suddenly it would drop to low values and I'd start over, back and forth. I present this data as best as I have measured, and I don't intend to go back! You see at least one of the crystals, my "China 1", (from a lead/silver mine in Hunan) gave a sweet classic-looking curve. More to the point, "ideal" curves for natural minerals are difficult to come by. Most crystals you use will be less than ideal. The good news is that, while listening to your set, poking about for a good spot is far easier than what I have gone through to produce these curves. Your ear will take care of you!



In the photo I indicate groupings based on an easy measure of performance. I note the current in milliamps for each set where the plate voltage is set at 0.5V. The greater the current the better are your chances to get a sensitive crystal, assuming Ohm's Law is not followed! Crystals in the "dead zone" on the left will have their woods metal re-melted for new detector crystals and the bad ones tossed, its tough love for crystals. I find that easily half the potted crystals I make are tossed this way, and only a few can be considered superlative.

My measurements and discussion on vacuum diodes has moved to my section "Diodes III" under the Lab Menu.

Return..

Back to Main....

Sunday, 09-Jul-2017 00:50:33 CDT

Comments and/or Correspondance to: kj-smith@sbcglobal.net

.::. Sitemap .::. International Pix .::. Western US Pix .::. Pinhole Pix .::. Crystal Radio .::.
.::. Snapshots .::. Thoughts .::. Beer Labels .::. Petrology .::. Life List .::. Ionosphere.::.

Global DX'ter

Back to Radio..



Finally, a shortwave set comes off the design bureau and out into the world. This is a type of set I have been planning and pondering on for some time. With many crystal radio design possibilites this will certainly not be the only SW set I plan, but it is my first effort, my chance to "do it" on shortwave. For a first effort I settled on a fairly simple design, a single-tuned rig with some degree of control, but not overly much. I took as my base a design by Rainer Steinfuehr on his Crystal Reciever World site. This design features a high Q spider coil with two taps, and adjustable capacitance on both the antenna and tuning circuits. It made a rather lovely small set indeed.

The specifics of the design were entirely my own and were based on the frequency range I wished to target and the specifications of the materials I had available for the project. In partictular, I had available small good-quality 10 - 115 pF variable caps for which my clever elder brother had lathed lovely 1/4 inch shaft extenders for use with standard tuning knobs. My target spectrum was about 5 to 18 MHZ as that is where the dominant international BC action takes place. With luck that would also allow receiving WWV at 10 and 15MHz as well. Digging into the design spreadsheets, it seemed an inductor with 7 to 9 mH would best deliver the goods. I made a spider form from a circlar cut of 1/8 inch Delrin plastic and wound 11 turns of 18awg magnet wire, carefully soldering taps at 3 turns and 8 turns from the ground (center) of the coil. I ended with 9 turns on the final set with testing giving me a 7.6 mH coil. The final schematic presented below.


4460
4460
A
G
PHONES
Global DX'ter
Kevin Smith
06 / 2010


Global DX'ter
6 - 18 MHz
10-115 pF
1N277
n
t2
sw1
b
sw2
10-115 pF
t1
L1
form ID 0.6in
9t, 18awg, 7.6 uH
t1 3t, 3.8 uH
t2 8t, 5.8 uH
kjs 2010

Initial testing on the set was dismal. NO RECEPTION. There followed many hours of double checking all wireing, solder joints, fidelity to the schematic, etc. Everything checked out, no good. Time to seek professional help, which happily corresponded to my annual visit home. There my radio engineer brother took the radio and gave it his close attention, puzzled over it as had I, and concluded a defective part somewhere. This he soon found in the tuning capacitor which had had a connection slip off its set point. This easily corrected, the radio seemed ready for testing. Unfortunately he did not have an antenna handy (he works in uhf+ research stuff) so all I could do was hook the set to a signal generator and test its performance, summarized below.



The plot above charts the received signal strength (p-p mV) versus input frequency for the four possible switch configurations (Detector on tap 1 or 2, Antenna on selective [top of coil] or broad [on tap t1]. These four conditions were tested with the tuning cap fully meshed (low frequency) and fully open (high frequency) to give an idea of the actual tuning range as compared to the calculated range. All measurements were made with no load on the output, and the antenna trim cap in the full meshed position. Other conditions not shown were also tested.

The results indicate that placing the antenna low on the coil, on the T1 position gives the best sensitivity and selectivity in tuning. The detector, a 1N277 germanium diode placed high on the coil at T2 also gives dramatic increase in sensitivity. What I found then, was a farily sensitive but, to be truthful, woefully un-selective set tuning from 6 to about 17-18 MHz. Still, not bad for a single-tuned shortwave rig.

Final thoughts. Upon returning to my home base, I quickly hooked the set to my longwire to make first impressions of actual reception. In midday I was able to pick up a spanish language format broadcast and two english language religous format stations and a brief encounter with WWV. At night the bands are flooded with competing stations, success! Note that all this with my handy dandy Radio Shack mini-amplifier. When I connected a crystal earphone and used my poor hearing, there was nothing as expected. One pity is the ongoing presence, even on this set, of KGOW 1.65MHz forever audible in the background. I consider the set a success as I was not expecting selectivity in a single-tuned rig. Still, with the bands dominated by religous and spanish broadcasts, I cant say it differs much from the local Houston AM fare. Oh well...


PHONES
DET
Sel
ANT
Sen


Sen
ANT
Sel
T1
DET
T2
A
4460
4460
PHONES

Kevin Smith
06 / 2010
Global DX'ter

[Return..](#)

[Back to Main....](#)

Monday, 19-Mar-2018 22:40:58 CDT

Comments and/or Correspondance to: kj-smith@sbcglobal.net

.::. Alsace .::. Life List .::. Ionosphere .::. Crystal Radio .::. Snapshots .::. Thoughts .::.
.::. Sitemap .::. Beer Labels .::. International Pix .::. Western US Pix .::. Pinhole Pix .::. Petrology .::.

Wavetrap, a useful gadget

[Back to Radio..](#)

This little gadget is most handy for crunching those local behemoths that always seem to be directing their strongest signals right in your direction. My wave trap is a bit of a combination of 1) Osterhoudt's QRM coil, 2) a design I found online on Owen Pool's excellent web site, and 3) a bit of my own seeing as how I had some, but not all of the ingredients needed from both traps. That is, I used what I found in the junk box.

The trap is formed on a stiff cardboard paper core with 1 1/4 inch outside diameter. On this I drilled holes for winding the tank coil, 110 turns of #30 awg enameled wire. Both Poole and Osterhoudt recommend #32, but 30 is what I had. Over this I would a coupling coil, 15 turns space wound of #22 awg enameled wire. Tuning of the tank is completed with a 410 pF var cap.

Tuning is sharp and deep, it takes a bit of getting used to, but then, schezzam!!!.. problem station gone! I luv it.

Wave Trap



Return..

Back to Main....

Sunday, 09-Jul-2017 01:03:30 CDT

Comments and/or Correspondance to: kj-smith@sbcglobal.net

.::. **Sitemap** .::. **International Pix** .::. **Western US Pix** .::. **Pinhole Pix** .::. **Crystal Radio** .::.
.::. **Snapshots** .::. **Thoughts** .::. **Beer Labels** .::. **Petrology** .::. **Life List** .::. **Ionosphere**.::.

S. Gernsback's
Radio Encyclopedia

S. GERNSBACK'S

RADIO ENCYCLOPEDIA

SIDNEY GERNSBACK
PUBLISHER
NEW YORK

All rights reserved including that of translating
into foreign languages including the Scandinavian

Copyright 1927
by
SIDNEY GERNSBACK

Printed in the United States of America

A

"A" BATTERY—An appliance for furnishing electrical current to light the *filaments* of a *vacuum tube*, and cause emission of *electrons* (see *Theory of Vacuum Tube Operation*). This battery may be in any of several forms, the two in popular use being the storage type (see *Storage Battery*), and the dry cell (see *Dry Cell*). Fig. 1 shows method of connecting the "A" Battery in a vacuum tube circuit.


VACUUM TUBE
TUBE SOCKET
+
−
STORAGE BATTERY
RHEOSTAT
+
−

Fig. 1. Method of connecting the "A" battery to a vacuum tube in radio receiving circuits. The lower diagram shows the "A" battery as represented in schematic drawings


−
+2V
+6V
EVEREADY STORAGE A BATTERY
SYMBOL
+
−

Photos by courtesy of National Carbon Co., Inc.

Fig. 2. A storage battery such as used for "A" battery current supply

In Fig. 2 a popular type of storage battery is shown. Batteries of this type come in many individual forms, the usual voltage being standardized at 6 volts. However, for use with certain tubes, 2 and 4 volt storage batteries are available. For general radio work, using the low-consumption tubes, the battery, as shown in Fig. 2, can hold a charge of from 60-80 ampere hours. (*See Storage Battery.*)

The other common form of "A" Battery is the dry cell, usually having a difference of potential (voltage) of 1.5 volts. Fig. 3 illustrates a popular type of dry cell. In connecting a number of cells for use with a vacuum tube, the method of connecting will depend on the voltage rating of the particular tube. If the tube is rated at 1.5 volts, a single dry cell may be used as in Fig. 4, or several may be connected in *parallel* (*q.v.*) shown in Fig. 5, the total voltage however, being only the voltage of one cell. Three dry cells connected in *series* (*q.v.*) will give 4½ volts, Fig. 6. A connection for dry cells, known as *series-parallel* or *multiple* (*q.v.*), is shown in Fig. 7. This connection will also produce 4½ volts and at the same time increase the life of the cells. Four dry cells connected in series will give six volts for use with a standard six-volt tube, Fig. 8. Dry cells are only used with six-volt tubes where the tube has a current rating of ¼ ampere, and seldom more than one tube is used in this manner due to the relatively high discharge and consequent short life of the battery.


SYMBOL
+
−
No. 711
EVEREADY
RADIO
"A" BATTERY
NATIONAL CARBON CO. INC.

Fig. 3. A dry cell "A" battery

A storage battery can be used for the "A" Battery current with a 4-volt tube if the connection is made as in Fig. 9. Here a standard 6-volt storage battery is tapped at the four volt terminal.


VACUUM TUBE
SOCKET
+
−
DRY CELL
1½ VOLTS
RHEOSTAT

Fig. 4. This circuit shows how one dry cell is used as the "A" battery for types of tubes requiring 1½ volts filament current


VACUUM TUBE
TUBE SOCKET
−
1½ VOLTS
+
RHEOSTAT
DRY CELL
DRY CELL
DRY CELL

Fig. 5. Several dry cells may be connected in parallel for increased amperage or longer life of the "A" battery


VACUUM TUBE
SOCKET
+
4½ VOLTS
−
DRY CELL
DRY CELL
DRY CELL
RHEOSTAT

Fig. 6. Three dry cells connected in series give 4½ volts, serving as the "A" battery for the U.V.199 or C299 type of tube


VACUUM TUBE
SOCKET
4½ VOLTS
+
−
DRY CELL
DRY CELL
DRY CELL
DRY CELL
DRY CELL
DRY CELL

Fig. 7. A series—parallel connection of three dry cells for longer life of the "A" battery with 4½ volt tubes


VACUUM TUBE
SOCKET
+
−
DRY CELL
DRY CELL
DRY CELL
DRY CELL
RHEOSTAT
6 VOLTS

Fig. 8. Four dry cells connected in series gives 6 volts for low consumption tubes


VACUUM TUBE
SOCKET
4 VOLTS
−
+
STORAGE BATTERY
RHEOSTAT

Fig. 9. Showing method of tapping at 4-volt terminal of a 6-volt storage battery for type U.V.199 or C299 tubes or other 4-volt tubes

Another connection for low voltage tubes can be made as illustrated in Fig. 10. Here only one cell of the storage battery is used. This cell can be used until exhausted when the other cells can be used in the same manner. When the three cells are exhausted, the storage battery may be charged by means of a *charger* (*q.v.*).



Fig. 10. How a single cell of a 6-volt storage battery may be employed to furnish "A" battery current for 1½ volt tubes

ABAMPERE—A unit of current used in special theoretical work. It has a value of 10 *amperes* (*q.v.*) and is not generally used in electrical work.

ABBREVIATIONS, AMATEUR—The transmitting amateurs of the United States use their own peculiar abbreviations in their inter-communication work. These are used to lessen the interference between transmitting stations as it permits conversation in a much quicker manner. The abbreviations generally used are listed below. Simplified spelling is always resorted to, words being spelled according to their sounds. Some such words are given, but others are so obvious that they are not listed. There are also the standard "Q" signals adopted by the International Radiotelegraphic Convention, to be found in official publications and given under the heading "Abbreviations, International Radiotelegraphic Convention."

ACCW—A transmitter using rectified alternating current as the plate supply.

AFTRN or P.M.—Afternoon.

AMMTR—Ammeter.

ARRL—American Radio Relay League.

BCL—Broadcast listener, one who does not have a transmitting station.

BC STATION—Broadcast Station.

BFRE—or B4—Before.

BLO—Blow.

BOTTLE or V.T.—Vacuum Tube.

C—See or Call.

CGE—Cage.

CM—City Manager of A. R. R. L.

CTPSE—Counterpoise.

CUL—See you later or call you later.

CW—Continuous wave transmitter.

DCCW—A transmitter using direct current as the supply for the plate.

DM—District Manager of A. R. R. L.

DOPE—Information, or in another sense, a varnish for coating inductance coils.

DS—District Superintendent of the A. R. R. L.

DX—Distance, receiving or transmitting.

FB—Fine Business.

FONE—Phone.

GA—Good afternoon.

GLD—Glad.

GM—Good morning.

GN—Good night.

FRQ—Frequency.

HAM—Being a term for the transmitting amateur.

HI—High or I am laughing—it's funny, according to use in sentence.

HI LOS—High loss.

HR—Here.

HV—Have.

KCK BCK—Kick back.

KONGRATS—Congratulations.

KY—Key.

LW LOS—Low loss.

LW WVE—Low waves.

MGHT—Might.

MIKE—Microphone.

MSG—Message.

NITE—Night.

OM—Old man.

OP—Operator.

OPS—Operators.

ORS—Official Radio Station.

OT—Oscillation transformer.

OW—Female operator.

PEEP-PEEP—Continuous wave transmitter.

QCW—Listen for my CW transmitter.

QCW?—Shall I listen to your CW transmitter?

QRMER—An operator who persists in interfering with other stations after being warned to stop.

QSR—I will relay the message.

QSR?—Will you relay the message?

QSS—You are fading.

QSS?—Is my signal fading?

RDO—Radio.

RECVR—Receiver.

RELY—Relay.

ROCKCRUSHER—Spark transmitter.

SA—Say.

SIGS—Signals.

SPIKE—Message file.

SPK—Speak.

SUREFIRE—Something positive in action.

THG—Thing.

THT—That.

TLL—Till.

TM—Traffic manager of A. R. R. L.

TMR—Tomorrow.

TRAFFIC—The handling of messages among the stations.

U—You.

UNLIS—Unlicensed.

UR—Your.

VLTMTR—Voltmeter.

WL—Will.

WRLS—Wireless.

WVL—Wavelength.

"X" LICENSE—Experimental License.

YL—Young lady.

"Z"—Special license.

73—Best regards.

ABBREVIATIONS — RADIO — ELECTRICAL—A letter or group of letters of the alphabet arranged so that there is a definite electrical meaning when used in radio telegraphy or telephony. These abbreviations are the means by which technical writings are simplified, *i.e.*, Alternating Current is simply A.C. when used in general telegraphy. As most of the latest radio text books use these abbreviations, the following are given to aid the reader in understanding the various abbreviations:

A.C.—Alternating Current.

A.F.—Audio Frequency.

B.E.M.F.—Back Electromotive Force.

B. & S.—Brown & Sharpe Wire Gauge.

B.S.W.G.—Birmingham Standard Wire Gauge.

C.—Capacity.

C.G.S. — Centimetre-gramme-second (*q.v.*).

C.W.—Continuous Waves.

D.C.—Direct Current.

D.C.C. — Double Cotton Covered (Wire).

D.S.C.—Double Silk Covered.

E.—Induced Pressure (See Abvolt).

E.M.F.—Electromotive Force.

H.F.—High Frequency.

H.F.C.—High Frequency Current.

I.R.E.—Institute of Radio Engineers.

L.—Inductance (in Formulae).

L.F.—Low Frequency.

L.F.C.—Low Frequency Current.

M.A.—Milliampere.

Mfd.—Microfarad.

P.D.—Potential Difference.

R.—Electrical Resistance.

R.F.—Radio Frequency.

R.P.M.—Revolutions per Minute.

R.P.S.—Revolutions per Second.

S.G.—Specific Gravity.

S.H.M.—Simple Harmonic Motion.

S.S.C.—Single Silk Covered.

S.W.G.—Standard Wire Gauge.

W/L—Wavelength.

X's—Atmospherics.

ABBREVIATIONS, INTERNATIONAL RADIO TELEGRAPHIC CONVENTION—All messages and conversations are not transmitted in regular form, various forms of abbreviations being widely used to increase the speed of transmission and to reduce cost. It also has the tendency to decrease the interference as messages are sent swiftly in half the time. In wireless telegraphy, abbreviations have been adopted as international, and today there are very few ships or shore stations that do not use at least part of them daily. Below we give the International Radiotelegraphic Abbreviations as adopted at The International Radiotelegraphic Convention. An example of the use of the abbreviations is as follows:

A station wishing to learn the name of a ship which is seen off the coast, sends in code the letters QRA?, which means, what is the name of your ship? The station or ship answers with the letters, QRA S.S. Lapland, thus in a few seconds the question had been answered.

Abbreviation	*Question*	*Answer or Notice*
CQ	—.—.—.—.—	Signal of inquiry made by a station desiring to communicate.
TR	— .—.	Signal announcing the sending of particulars concerning a station on shipboard.
	— —. .— —	Signal indicating that a station is about to send a high power.
PRB	Do you wish to communicate by means of the International Signal Code?	I wish to communicate by means of the International Signal Code.
QRA	What ship or coast station is that?	This is ....
QRB	What is your distance?	My distance is ....
QRC	What is your true bearing?	My true bearing is.........degrees.
QRD	Where are you bound for?	I am bound for.............
QRF	Where are you bound from?	I am bound from............
QRG	What line do you belong to?	I belong to the............Line.
QRH	What is your wave length in meters?	My wave length is..........meters.
QRJ	How many words have you to send?	I have .... words to send.
QRK	How do you receive me?	I am receiving well.
QRL	Are you receiving badly? Shall I send 20? ..—. for adjustment?	I am receiving badly. Please send 20. ..—. for adjustment.
QRM	Are you being interfered with?	I am being interfered with.
QRN	Are the atmospherics strong?	Atmospherics are very strong.
QRO	Shall I increase power?	Increase power.
QRP	Shall I decrease power?	Decrease power.
QRQ	Shall I send faster?	Send faster.
QRS	Shall I send slower?	Send slower.
QRT	Shall I stop sending?	Stop sending.
QRU		I have nothing to transmit. I have nothing for you.
QRV	Are you ready?	I am ready. All right now.
QRW	Are you busy?	I am busy (or, I am busy with.... Please do not interfere).
QRX	Shall I stand by?	Stand by. I will call you when required.
QRY	When will be my turn?	Your turn will be No. ....
QRZ	Are my signals weak?	Your signals are weak.
QSA	Are my signals strong?	Your signals are strong.
QSB	Is my tone bad? Is my spark bad?	The tone is bad. The spark is bad.
QSC	Is my spacing bad?	Your spacing is bad.

(When an abbreviation is followed by a mark of interrogation, it refers to the question indicated for that abbreviation)

ABSCISSA—A term in geometry adapted to radio use in making *curves* to show various values. The abscissae are the horizontal lines, and the ordinates are the vertical lines. In the diagram, the line AY is the axis of *ordinates* (*q.v.*) and the line AX the axis of abscissae. Fig. 2 shows a simple curve indicating the relation between voltage and current (amperes) in an *arc* (*q.v.*). The volts are given as ordinates and the amperes are shown as abscissae.



Fig. 1. Indicating axis of abscissae by the line A to X

The distance of any point from the axis of ordinates, measured on a line parallel to the other axis represents the value of the quantity and locates a point on the curve. Where abscissae and ordinates are known, it is a simple matter to plot a series of points and then draw the curve through these points. (See *curve.*) Thus, in Figure 2, the curve shows the operation of the arc to be such that when the voltage is zero, the current is 20 amperes; when the voltage is 60, the current is 6 amperes, etc.



Fig. 2. A simple curve to illustrate the relation between volts and amperes

ABSORPTION, ELECTRIC—(See *Soaking-in.*)

ABSORPTION MODULATION—In the production of modulated (see *modulation*) waves, used to transmit speech in radio, it is necessary first to produce *undamped* (*q.v.*) waves of high or *radio frequency* (*q.v.*). Then other waves of low or *audio frequency* (*q.v.*) are superposed or run together with them. Now, if we insert a *microphone* (*q.v.*) in the *aerial circuit* (*q.v.*) of the transmitting station, providing that the *resistance* (*q.v.*) of that instrument is such as to reproduce accurately the vibrations of the voice or music, it is possible to vary the current output of the system producing the high frequency currents, so as to transmit the voice vibrations. If the microphone has resistance comparably low with the aerial or *antenna resistance* (*q.v.*), then the high frequency power output is handled (apportioned) equally between the aerial and microphone. The result is the production of fairly well modulated waves. There are, however, better methods of modulating the waves for which see *Modulation.*

ABVOLT—The *CGS unit* (*q.v.*) indicating the pressure or induced E.M.F. (*electromotive force*) (*q.v.*) set up between the ends of a wire one centimeter long, moving with a speed of one centimeter per second across the magnetic lines of force (*flux lines*) (*q.v.*) of a uniform magnetic field of unit intensity or flux density. An abvolt is therefore a very small unit and 100,000,000 (10^8) are required to equal one volt. In all formulae for determining the output or E.M.F. that can be expected to be produced by a certain *alternator* (*q.v.*), the result is in abvolts, and the complete formula usually provides for obtaining the actual volts. This is done by dividing the result in abvolts by 100,000,000 or 10^8 as it is generally expressed. (See *Alternator* also *abampere.*)

A. C.—Abbreviation for Alternating Current. (See *Alternating Current.*)

ACCELERATION—The rate at which the speed of a body in motion increases within a certain period of time. If we assume a train running at a certain rate of speed when the brakes are applied, the speed will decrease, and if measured over a period of one second, there will be a definite amount of decrease or a rate of decrease. This is known as *negative* acceleration or *deceleration.* When the train is speeded up there will be a definite change (increase) in velocity. The rate of change of velocity per unit of time is the acceleration. (*See Velocity* also *Frequency.*)

ACCEPTOR—A supplementary combination of *inductance* (*q.v.*) and *capacity* (*q.v.*) tuned to the frequency of the desired signal and connected in series in the receiving antenna. Generally, a *coil* (*q.v.*) and *condenser* (*q.v.*) of a value to correspond with a certain given wavelength—thus literally to "accept" the desired signal. (See also *Rejector.*)

A series combination of *inductance* (*q.v.*) and *capacity* (*q.v.*) connected in series with a high-frequency C.M.F. When tuned to resonance with the impressed E.M.F., the impedance drops to a low value, limited by the resistance of the system

ACCUMULATION OF ELECTRICITY—The process of storing electrical energy as (1)—a *storage battery* (*q.v.*) in which electric charges are placed to be later withdrawn and expended at will for various purposes, or (2)—the collection of energy by a *condenser* (*q.v.*) wherein the *electrons* (*q.v.*)

or minute charges of electricity are stored up momentarily on the plates or electrodes of the *condenser* (*q.v.*) and then released into the circuit.

ACCUMULATOR—(See *Storage Battery.*)

ACID—An active chemical compound formed by combining hydrogen with various acid radicals. Acids are much used in radio, particularly in *storage batteries* (*q.v.*). The most commonly used acid in this connection is sulphuric acid—a compound or union of hydrogen, sulphur and oxygen in certain definite proportions as indicated by the chemical symbol H_2SO_4. (See *Flux, Soldering.*)

ACIDIMETER or ACIDOMETER—An instrument used to determine the *specific gravity* (*q.v.*) of an acid solution. It is similar to a hydrometer and used in the same manner. Much used for testing strength or purity of acids or solutions. Operates on the principle that the strength of an acid will be directly proportional to the quantity of carbonic acid gas which it will liberate from a carbonate of soda or potash. (See *Hydrometer.*)

ACLINIC LINE—An imaginary line on the earth's surface assumed as passing through points where there is no magnetic inclination or dip of the needle of a compass. (See *Agonic Line.*)

ACOUSTICS—The science of sound or the study of the cause and effect of vibrations which effect the hearing. Generally speaking, the production and transmission of sound.

ACOUSTIC WAVE—The term occasionally used to denote a *sound wave.*

ACTINIC RAY—A light ray or beam of invisible *radiant energy* (*q.v.*). Rays of light, generally considered as lying at the blue or extreme left of the *spectrum* (*q.v.*) and being of such short *wavelength* as to be invisible to the eye. These rays have the power to induce or bring about chemical action. The most powerful actinic rays are the violet (X Ray) and the *ultra-violet.*

ACTIVE CONDUCTOR—(See *Conductor.*)

ACTIVE MATERIAL—The spongy part of a plate of a storage battery. The part which changes in nature and appearance due to the flow of electric current and having the ability to redevelop the current by a secondary chemical change.

ACTIVE PRESSURE—The active *electromotive force* (*q.v.*) or the pressure which produces a current. The term is used to distinguish this pressure from one impressed on the circuit.

A component in phase with the current in an *alternating current* (*q.v.*)

ACTIVE SPARK—A spark produced from energy contained in a charged condenser, which produces active *oscillations* (*q.v.*).

Thus, the spark discharge from a coil without any method of storing energy will be "inactive." When a condenser is inserted in such manner as to allow it to store up energy and then discharge, the resultant spark will be "active."

Fig. 1 shows a simple spark coil circuit with the secondary discharging across a gap. This is an Inactive Spark. Fig. 2 represents the same coil with a condenser in the circuit to store up the energy before discharging across the *gap* (*q.v.*). This is an Active Spark.



Fig. 1. Showing how an inactive spark is produced



Fig. 2. The active spark is produced by means of a condenser in the circuit as shown

ADAPTER, AERIAL—A device for utilizing an electric light line as an aerial for the reception of radio signals. Essentially, two or more fixed mica condensers of comparatively high capacity, in series with two metal legs attached rigidly to a standard plug for insertion in socket of electric light fixture. Terminals are provided for connection to receiving apparatus. The illustration shows one of the popular types of Aerial Adapters which consists of merely a condenser to prevent the voltage of the line from passing directly to, or through, the instruments.



Illustration by courtesy of Dubilier Condenser and Radio Corp.

ADAPTER, TUBE—A device similar in form to a vacuum tube socket. Usually comprises a cylindrical form or shell of either metal or insulating material with legs identical with the tips or legs of a vacuum tube. A receptacle is allowed for the insertion of a tube, and the lead from each tip recess is so connected to a leg or tip at its base, as to permit the use of a non-standard base tube in a standard *socket* (*q.v.*). The illustration shows adapter for U.V. 199 or C-299 type of tube. When it is desired to employ a tube having a non-standard base in a set already equipped with standard sockets, without the necessity of changing the sockets, an adapter may be used. (See *Socket.*)



Illustsation by courtesy of Pacent Elec. Co., Inc.

ADHESION, ELECTRIC—Affinity of one body for another due to dissimilar charges of electricity passing through or being carried by them. The electrical equivalent of magnetic attraction.

ADJUSTABLE CONDENSER—(See *Variable Condenser.*)

ADJUSTABLE GRID LEAK—A form of *grid leak* (*q.v.*) that can be easily adjusted over a wide range of values without removal from the circuit. The illustration shows one type of Adjustable Grid Leak.



Illustration by courtesy of Allen-Bradley Co.

ADJUSTABLE RESISTANCE—(See *Variable Resistance.*)

ADMITTANCE—The inverse of *impedance* (*q.v.*). In an *alternating current* (*q.v.*) the Admittance acts in the opposite manner to impedance. A circuit having low impedance is said to have relatively high Admittance.

AERIAL—A system of wires suspended in the air or in any form in which they may be insulated or kept free from surrounding objects, used for the purpose of receiving or transmitting impulses as in radio transmission and reception. The term Aerial is actually identical with *Antenna*, but due to the general English definition of Antenna, authorities are gradually coming to distinction between transmission and reception Aerial systems by referring to a receiving device of this nature as an Antenna, and when used to transmit, as an Aerial.

There are different types and forms of Aerials, varying mainly according to purpose and facilities. The standard and perhaps more commonly used receiving Aerial consists of a single wire as in Fig. 1 or several wires as in Fig. 2. The wire used is usually of copper, as this metal combines low resistance with economy, strength, and durability. The theory of the action of the waves either received by or transmitted from an Aerial system will be found under the heading "Electromagnetic Waves."



Fig. 1. A single wire aerial in the form of an inverted L. If a long wire is used, the lead-in may be connected in the center, forming a T type


THE 'T' TYPE AERIAL IS SIMILAR IN CONSTRUCTION BUT WITH THE LEAD IN TAKEN IN THE CENTER.
INSULATOR
PULLEY
ROPES TO PREVENT SWINGING OF AERIAL
AERIAL WIRES NOT SMALLER THAN NO. 14 B.&S.
GUYS
TO THE RADIO SET.
FLAT TOP INVERTED 'L' AERIAL

Fig. 2. Method of erecting a multi-wire aerial. This type of aerial may be made in either the inverted L or T form as shown

The exact type and extent of an Aerial will depend entirely on the available facilities and the particular purpose for which it is intended. These various forms will be taken up under their respective headings. In the receiving Aerials, Figs. 1 and 2, a certain definite *wavelength* (*q.v.*) is obtained by arranging a certain length to the wires of the Aerial system including the *ground* and *lead-in.* (See *Fundamental Wave-Length of Aerials.*) In the single wire Aerial, the lead-in is usually taken from the end nearest the receiving apparatus, but where a particularly long Aerial is to be used, it is customary to attach the lead-in to the centre of the suspended wire. The former is known as an *inverted L* type and the latter as a *T* type Aerial. These designations will apply as well where a number of wires are used as in Fig. 2.

Generally speaking, an Aerial should be as high above the ground as possible, of course within practical limits. From 25 to 100 feet is the most practical height to use. Where the Aerial is suspended at a substantial height the incoming waves will be less likely to be obstructed by surrounding trees or buildings, and in the case of transmission the same factor will apply, inasmuch as the waves may be obstructed in their transmission, if buildings or trees closely surround the Aerial.



Fig. 3. Showing one method of installing an indoor aerial. While this illustrates a multi-wire type, a single wire run around the moulding of the room may give excellent results

The insulation of an Aerial is of particular importance, and especially so in the case of a transmitting Aerial. The reason for insulating an Aerial is to prevent the currents from escaping to the ground by way of trees, buildings, or the masts to which the Aerial is attached.

Fig. 3 shows a method of arranging an indoor Antenna system where it is not possible to use the out-door type. The construction may be essentially the same as the usual form of outdoor Aerial and can be arranged in a number of different ways. Very often a wire is merely suspended around two sides of a room and insulated from the moulding. One end will be connected as a lead-in to the receiving apparatus. In constructing an indoor Antenna, it is well to remember that the effective length of the Antenna is not much greater than the direct distance from the receiving set to the farthest point of the Antenna.

Fig. 4 shows a different type of Aerial known as the *Cage* type. The illustration shows an inverted L, and the T arrangement. Fig. 5 shows a *Fan Aerial* and Fig. 6 the *umbrella* type. The illustration, Fig. 7, shows one type of *loop Aerial* (*q.v.*) and Fig. 8 the same general type in somewhat different form. Owing to the fact that the theory of operation of a *loop Aerial* is somewhat different than the ordinary types, it will be described more fully under the heading "Loop Aerial." Fig. 9 illustrates a form of *Aerial Adapter* which is arranged to allow the electric light wires to be used as an Aerial. (See *Adapter Aerial.*) Fig. 10 shows an *underground Aerial* system designed by Dr. Rogers and which is not appreciably affected by atmospheric disturbances. (See *Strays.*) This form of Aerial, however, is generally impractical due to the difficulties in construction.

Aerials for transmitting may be of the same general types as receiving Antennas arranged outdoors, with the exception as explained previously, that heavy insulators must be used owing to the high voltage employed. Aerial for transmitting will depend for size on the wave-length desired.

Fig. 11 illustrates several types and arrangements of *counterpoise* (*q.v.*).

In the case of the receiving Aerial a single wire may be from 75 to 150 feet in length, or if a number of wires are used, the over-all length may be considerably less. (See *Fundamental Wave-length.*)


WOODEN HOOP
12" TO 18" DIAMETER
PULLEY
INSULATOR
CAGE AERIAL
COMPOSED OF 6 WIRES
LEAD IN
6" TO 10" IN DIAMETER COMPOSED OF 4 OR 6 WIRES
LEAD IN INSULATOR
INSULATOR
METALLIC GUY WIRES
"T" TYPE CAGE AERIAL

Fig. 4. Cage aerials are usually employed for transmitting purposes. The inverted L and T types are erected as shown


FAN AERIAL
PULLEY
PULLEY
INSULATOR
INSULATOR

Fig. 5. The fan aerial has its wires spread apart at the farthest point, forming a fan


UMBRELLA TYPE AERIAL
INSULATORS
AERIAL WIRE
LEAD IN
DISTANCE OF INSULATOR TO GROUND SHOULD BE NOT LESS THAN 1/3 HEIGHT OF MAST
INSULATOR
INSULATOR
ROPE
GUYS

Fig. 6. The umbrella type of aerial derived its name from the arrangement of its wires in the form of an umbrella


Loop Aerial for Directional Reception
Detail of Joint
Wood
Bakelite or other insulating material
Binding Posts

Fig. 7. The selenoid type loop aerial


Spiral Loop
Notches
Wires
Sectional View of Loop Arms
Binding Posts

Fig. 8. The spiral type loop aerial


Lines
Condenser in Plug
Light Line Aerials

Fig. 9. Method of employing the electric light line as an aerial with an aerial adapter. Above is shown the diagram of the condenser in connection with the aerial circuit of a radio set



Fig. 10. Showing how wires are buried in the ground for aerials





Fig. 11. Different methods of arranging counterpoises for either transmission or reception

AERIAL CAPACITY—(See *Capacity of Antenna.*)

AERIAL CIRCUIT—Consists of *aerial* and *earth* or *ground,* including all *coils* or *inductances, condensers,* etc., which may be connected with the aerial and earth and forming a direct path between those points.

AERIAL SWITCH—A device to transfer the *aerial* and *ground* connections from the transmitting circuit to the receiving circuit or vice versa. Its



Fig. 1. A simple Aerial Switch

object is to separate the high tension current of the transmitter from the low tension of the receiver. The switch is usually installed in a convenient position so that the operator may change from transmitting to receiving by one motion of the hands. A simple form of aerial switch is illustrated in Fig. 1. The circuit for same is shown in Fig. 2. A more efficient circuit is the one shown in Fig. 3. This circuit requires another blade to control the primary current to the transformer. The latter circuit is most satisfactory as it entirely disconnects the current to the transformer, doing away with the possibility of dangerous shocks to the operator. The switch commonly used in such circuits is shown in Fig. 4.



Fig. 2. Circuit for a simple Aerial Switch



Fig. 4. An Aerial Switch with an extra blade

The switches used in the various commercial wireless stations are of course more complicated. There is a need to control many circuits with the simplest possible method. In order to do this it was found more convenient to only change the aerial connections, and allow the ground connection to both the receiver and transmitter to remain permanently. This of course necessitates a small air gap in the aerial for the transmitter. This is called an *anchor gap* (*q.v.*). This small appliance allows the transmitter to be connected continuously to the aerial as the high voltage from the transformer discharges across the small air gap, as provided for in the *anchor gap* (*q.v.*). Fig. 5 shows the circuit when this type of aerial transfer is to be used. When the switch handle is pushed down it makes connections with the receiver, when it is raised, the transmitter is ready to be used as the primary current is connected also.

AERIAL TUNING CONDENSER—A *condenser* (*q.v.*), usually variable, connected in the *aerial circuit* (*q.v.*) for the purpose of adjusting the natural period of the receiving circuit to the period of the incoming waves (see *Wavelength*) or signals coming from the *aerial.* In the illustration is shown an Aerial Tuning Condenser.



Fig. 3. Circuit for the Aerial Switch shown in Fig. 4 on page 7



Fig. 5. An Aerial Switch employed in conjunction with an Anchor Gap as explained on page 7

Any *capacitive* (*q.v.*) means of establishing or varying the *oscillation constant* (*q.v.*) of the receiver.



A variable condenser such as commonly used for an Aerial Tuning Condenser (see page 7).

AERIAL WIRE—The wire forming the *aerial* (*q.v.*). Copper is generally used for this purpose as it offers very little *resistance* (*q.v.*) to the feeble currents in receiving.



The illustrations show various types of wire as used for aerials. Among them there are the solid copper wire, copper clad steel wire, stranded wire, braided wire and brass or copper strip.

AERO-FERRIC INDUCTANCE—The *inductance* (*q.v.*) of coils wherein the *magnetic circuit* (*q.v.*) is completed through both air and iron.

AEROPLANE ANTENNA—Receiving or transmitting *antenna* (*q.v.*) used on an aeroplane. The commonest form is a suspended wire shown as A in the illustration. The *ground* or *counterpoise* (*q.v.*) in this case may be another wire suspended on and insulated from the fuselage as indicated at B. When the plane is in flight, the hanging wire trails up and backward, depending on the speed of the plane and the size of the weight used. This type of antenna will be slightly *directional* (*q.v.*) in the direction the plane is traveling. If it is impractical to use a trailing wire antenna for any reason, a loop or coil of wire may be used, the results of course being less satisfactory. The metal frame of the plane is often used as a *counterpoise* (*q.v.*)



A. F.—Abbreviation for *Audio-Frequency* (*q.v.*)

AFTER-GLOW—Fluorescent phenomena in a *vacuum tube* after current has been withdrawn.

AGONIC LINES—Lines imagined as passing through points on the earth's surface where the magnetic inclination or dip of a magnetic needle (compass) is zero. (See *Aclinic Lines.*)

AGING, VACUUM TUBE—Gradual diminishing of the brilliancy of a tube due to the deterioration of the *filament* (*q.v.*) and the coating or deposit on the bulb. A tube is said to be Aging when it gradually loses its power to emit *electrons* (*q.v.*)

AIR CONDENSER—*Condenser* utilizing air as the *dielectric*. The majority of variable condensers used in radio work employ the air dielectric, that is, the space between plates is merely an air gap. Most *fixed condensers* (*q.v.*) use some substance such as mica, or sheets of waxed paper as a dielectric.

AIR CORE TRANSFORMER—A *transformer* used in radio, having no metal core, *the lines of force* having their path through air. (See *Amplifier, Radio Frequency.*)

ALBIZ, Count—Managing Director of the Compañia National de Telegrafia sin Hiols in 1910, of Scotch origin.

He was born in Madrid in 1858 and received a schooling at the Madrid University and London University College. He was a Tory member of Parliament.

ALEXANDERSON, Ernst Fredrick Werner (1878)—Radio engineer and inventor. Born at Upsala, Sweden, January 25th, 1878, he was educated at the High School and University of Lund, Sweden, at the Royal Institute of Technology, Stockholm, and at Berlin. In 1902 he joined the General Electric Company, and has been for some years their consulting engineer. He holds the post of chief engineer to the Radio Corporation of America, and

Photo by courtesy of General Elec. Co.

E. F. W. Alexanderson

is a member of the American Institute of Radio Engineers. Alexanderson has read many papers on electrical subjects before the chief technical societies of America.

Alexanderson is famous for his work on *high-frequency alternators* used in Radio telegraphy. The Alexanderson alternator is connected directly or *inductively* to the aerial and earth, and constitutes the simplest possible connection for producing *continuous* or *undamped waves*. It is a machine of great speed and many *field poles*, and frequencies as high as 200,000 *cycles* are obtained. For long distance work, employing very *long wavelengths*, this high-frequency alternator is largely used. Alexanderson is also responsible for the *magnetic amplifier*, patented in 1913, and has carried out successful experiments on *duplex wireless telephony*. In the Alexanderson *microphone transmitter* the *modulation* is mainly effected by variations in the tuning of the *aerial circuit*.

ALEXANDERSON ALTERNATOR—A type of *high-frequency alternator* (*q.v.*) which produces *continuous oscillations* (*q.v.*)

ALLOY—A compound of two or more metals. (See *Woods Metal*.)

ALTERNATING CURRENT—An electric current that does not flow steadily in one direction—as from *positive* to *negative*—but completely reverses its direction or *polarity* (*q.v.*) at certain definite intervals. In other words, the current flows first in one direction and then reverses and flows in the opposite direction—these changes being referred to as changes of *phase* (*q.v.*). An electric current is either *direct* (*q.v.*), alternating, or *pulsating*. The latter is an alternating current that has been rectified. (See *Rectified Current*.) Practically the only direct current that is employed or appears in a radio receiver is that supplied by the *"A"* and *"B" Batteries* (*q.v.*). In an alternating current, the change in direction or polarity takes place in a steady, even manner.



Fig. 1

An understandable analogy for alternating current is its comparison with a pendulum. In Fig. 1 the pendulum is supposed to be the alternating current or impulse. Now when the bob is swung from its natural (neutral) position A, which may be considered as zero value of voltage or current, it will move to a maximum point, either B or C. If we assume B to be the *positive* side, then the bob will move to B which will be the maximum positive *amplitude* (*q.v.*). It will then fall back to zero again, and with the power behind it, the momentum in this case, will rise on the other side to C, which is the maximum *negative* amplitude. The bob will then fall back to A once more and will have undergone a complete change of direction and values; it will have gone through a *cycle* (*q.v.*). That is to say, it will have risen from zero A to positive maximum B, then back to A, rising on the other side to negative maximum C and back to A. Now the length of time required for this complete cycle (see *Alternation*), is known as the *time period* of vibration or *phase change*. If, for example, it required one-sixtieth of a second for this change to take place, then we say that the *frequency* (*q.v.*) is sixty cycles, because obviously, a change requiring one-sixtieth of a second will occur sixty times in one second.



Fig. 2



Fig. 3

The action of alternating currents may also be likened to that of ocean tides. In Fig. 2 the curved line represents the water in motion and is to be compared with current in motion in an alternating circuit. For the sake of clarity, we can assume that the tide rises and falls between two shore lines, A and B. At 12 noon the tide is at zero or "ebb" and there is no motion in either direction. Now the flow starts toward shore line A and gradually rises toward that side until at 3 P. M. it has reached its maximum height. In the case of an alternating current, we may consider that at 3 P. M. the current has reached maximum value on the positive side or in a positive direction. It then reverses and falls toward zero until at 6 P. M. it has reached the zero point. In the case of the current, it will have become zero. Motion again starts in the other direction and the tide rises once more, but in the opposite direction, toward shore line B. By 9 P. M. it will have reached maximum height in this direction, or in the case of the current it has reached maximum value or *amplitude* (*q.v.*) at D on the negative side. It then falls back again to zero, and at 12 midnight has come back to its original starting point, having gone through all stages of value or height from zero to maximum at one shore and then back to zero; then from there to maximum at the other shore and back to zero. The action of the alternating current then will have been to flow from zero to positive maximum, back to zero and reversing, from zero to maximum on the negative side, then back to zero. It will have completed one cycle. The time required for the tide to go through these changes E to F is 12 hours and is known as the *time period* or *period* (*q.v.*). Therefore, the time required for a complete change in the case of alternating current will be referred to as the period. The number of times that these changes take place within a certain time limit is known as the *frequency* (*q.v.*)

The current value in Fig. 3 is assumed to be 10 amperes, and the current values at any moment are shown as *ordinates* (*q.v.*), (vertical) while the time is shown in the *Abscissas* (*q.v.*) (horizontals). If the above curve is to be assumed as representing the Sine wave of an Alternating current having a frequency of 60 cycles per second, the total time in the chart would be one-thirtieth of a second. Thus, Time A to C would be one-sixtieth second, the Time of one complete cycle. A B is a positive Alternation and B C a negative Alternation, D and E represent maximum current values in each direction.

If the above Sine Wave is to be used as an example of a high frequency oscillation as in radio, the Time of one cycle can be assumed as about $\frac{1}{1,000,000}$ second. (See *Frequency-Oscillation - Sine - Phase - Characteristic of Alternating Current.*)

The frequency of an alternating current depends on the number of poles (field magnets) and the speed of rotation when the A.C. is generated by an alternator. (See *Alternator.*)

ALTERNATING CURRENT, THEORY OF PRODUCTION OF—Electric current in motion along a conductor always has a magnetic field (*magnetic flux*) surrounding it. If this current is passed near a number of turns of wire, the lines of flux will link with the wire turns in the circuit. The number of flux lines through a coil will depend upon the current. A change of current will change the number of linkages. If two turns of wire are used, the circuit will link twice with the same magnetic flux. Thus, a change in the current or a change in the number of turns of wire will alter the linkages.



Fig. 1

Now in the case of Fig. 1, the magnet being placed near the coil causes lines of force to pass through the coil. Each turn of wire will link the flux lines. Now any *change* in these linkages between the flux lines and wire turns will produce an E.M.F. (*electro motive force*) in the circuit of the wire turns. This is called an "induced current" because it is induced by the change in linkages. In Fig. 1, we have a coil of wire in a circuit with some sensitive measuring instrument for minute currents, in this case a *galvanometer*. Near it we have a bar magnet. When this magnet is moved toward or within the coil, a current is induced in the circuit by reason of the change in linkages. This current is *always* in a direction to *oppose* the change that causes it. (See *Lenz Law.*) "Whenever an induced current arises by reason of some change in the linkages, the magnetic field about the induced current is in such direction as to oppose the change." When the magnet is moved toward the coil, the change in linkages creates or induces a current that flows in the circuit in such manner as to make A act as a North pole. As the North pole of the magnet is toward this point A, the similar poles will oppose each other according to the simple law of magnetic attraction and repulsion. Now if we attempt to withdraw the magnet, the change will alter the linkages again, this time creating an induced current that makes A act as a South pole, thus *attracting* the magnetic North pole and opposing in the opposite manner, the change in linkages that have created the current.



Fig. 2



Fig. 3

We already know that if a conductor is moved across a magnetic field, an E.M.F. is induced in the conductor. The action is the same whether the conductor is moved across the magnetic field or vice versa. In Fig. 2, a magnet is shown in position on an axis—C D for rotation within the loop A B. As the magnet is rotated, the North pole passes across A, an E.M.F. is created toward F in the same direction. As the position of the magnet reverses in rotation and S passes A while N passes B, a current is induced in the *opposite* direction, both times in accordance with the law previously stated. Thus, if a meter is connected between the ends of the loop at E F and the magnet rotated, a current will be registered. With each half turn of the magnet, this current will reverse its direction. Therefore, we have produced an alternating current that changes direction with each reversal of the position of the magnets. This is the simple *AC generator* or *alternator*. The illustration, Fig. 4, shows a standard type of low frequency alternator.



Fig. 4

ALTERNATION—In an alternating current, is the rise from zero to maximum *amplitude* and back to zero on either side, i.e., *positive* or *negative* directions. Two alternations—one positive and one negative—make a complete *cycle.* (See *Alternating Current.*)

ALTERNATOR—A machine for the purpose of changing mechanical energy into electrical energy. Fig. 1 shows an alternator in its elementary or simplest form—merely a conductor, B C moved across a *magnetic flux* (*q.v.*) (Note: For a complete explanation of the production of alternating currents, see *"Alternating Current, Theory of Production of."*) Here the conductor B C is moved to the right *across* the magnetic flux shown as dotted lines between N and S, the poles of the magnets. As the conductor moves across the flux lines of the magnet, an *electro-motive force* (*q.v.*) *or electric* current is set up or induced in the conductor, this force being in such a direction that the current produced will create a flux or magnetic field, in the same direction as the flux on the side of the conductor that comes first into contact with the flux lines N S on moving the conductor. In this case E.M.F. (electromotive force) is in the direction B to C in the conductor. In order to establish a circuit and utilize the current pro-



Fig. 1



Fig. 2

duced in this manner, it is only necessary to attach wires to both ends of the conductor as shown by the dotted loop. Now at this moment the conductor is being traversed by a current having a definite polarity, that is to say, it is flowing in one direction only. When the direction of the flux lines N S are reversed, as by reversal of the magnet, or the conductor is turned so that the other end comes into contact with the flux lines, then the direction of the current in the conductor will reverse and it will flow in the opposite direction. In other words, with every reversal of the position of the conductor in its relation to the magnetic flux N S, or the reversal of the direction of the flux lines, with respect to the conductor, the E.M.F. that is created will change its direction of flow. (See *Alternating Current.*)

In an alternator it has been shown that the result is approximately the same whether the magnet is rotated or the conductor is rotated through the magnetic flux. In either case the moving member is known as the *rotor* (*q.v.*) and the stationary member is called the *stator* (*q.v.*). The magnets producing the flux lines may be stationary or they may revolve; in either case they are referred to as the *"field"* (*q.v.*).



Fig. 3

It has been shown that with every change in the relative position of the field magnets and the *armature* (*q.v.*), irrespective of which member is the rotating one, a change of direction of the induced E.M.F. takes place. Then it is apparent that in order to increase the number of changes, that is, to increase the *frequency* (*q.v.*), it is only necessary to use (1) a greater number of field magnets, or (2) have the armature or conductor pass the magnets more frequently by means of greater speed in the rotating member, or by means of both. Now each of these changes is an alternation (see *Alternating current*) and two such changes will be a *cycle* (*q.v.*). Let us suppose that the moving member of a certain alternator has a rotary speed of 720 revolutions per minute and there are 10 poles or magnets. As frequency is figured by the changes per second, it will be necessary to reduce this number to the revolutions per second. Thus, there will be 12 revolutions per second. This figure multiplied by the number of *poles* (*q.v.*), which we assume as 10, indicates 120 alternations per second. As there are two alternations to each *cycle* (*q.v.*), the frequency in this case will be 60 cycles. The equation is as follows:

$$F = \frac{P}{2} \times \frac{N}{60}$$

where F is the frequency, P, the number of poles and N the speed of rotation per minute. The exact voltage or E.M.F. obtained will depend on the number of poles and the speed of rotation, and also on the distribution of the field windings and total flux from all the poles or magnets. In designing alternators the effective E.M.F. (electromotive force) is expressed by the formula:

$$E = \frac{K P \phi N Z}{10^8}$$

E is the effective electromotive force of the alternator.

K represents the E.M.F. factor of the alternator. This factor depends upon certain charcteristics of the poles and also the distribution of the windings on the armature.

P is the number of poles of the field magnates.

ϕ is the number of lines of magnetic flux that flow from one pole across the gap to the armature—known as the useful magnetic flux per pole; (see *Maxwells*).

N is the speed of rotation of the rotor in revolutions per second.

Z is the total number of conductors on the surface of the armature.

10^8 represents the number 100,000,000—the calculation given would be determined in *abvolts* (*q.v.*), $\frac{1}{100{,}000{,}000}$ volt and it is therefore necessary to reduce it to volts by division.

In the "revolving field" alternator, as explained above, the field magnets are rotated and the conductor remains stationary. The windings in which the E.M.F. is produced, are placed in slots in the inner surface of the stator, the stator and the windings composing it being the *armature.*

In the alternators of the revolving armature type, the conductors or armatures are the rotating member and the field magnets remain stationary. Fig. 2 shows the revolving armature type of alternator in diagrammatic form. A small direct current *generator* (*q.v.*) may be used to excite or build up the field. That is to say, a current is sent through the field magnets (windings in this case) for the purpose of increasing or building up the *flux density* (*q.v.*). This is known as an *"exciter"* (*q.v.*). The exciter may be mounted directly on the end of the rotating shaft of the alternator, or mounted separately and connected to the alternator rotor shaft by means of a belt. This permits a heavy field to be built up by the electro-magnets used in place of the ordinary magnet shown in Fig. 1. If the machine is to be *single phase* (*q.v.*) there will be two *collector rings* (*q.v.*), the two phase type will have four rings, and the three phase six rings. The illustration Fig. 2 shows the general design of a single phase alternator. In this case there will be of course only two rings to collect the E.M.F. set up by the machine. Fig. 3 illustrates the general scheme of armature winding for a two phase machine. Here there are actually two separate E.M.F.'s set up by the separate windings and the ends of each of these windings are connected to collector rings as shown. In the three phase arrangement there may be three separate windings and six collector rings.



Fig. 4



Fig. 5

The use of the revolving armature type for comparatively small voltages is due, as mentioned previously, to the fact that they are easily constructed, and also the advantage that the exciter need not be an external source, but may be a separate winding with a *commutator* (*q.v.*) mounted on the main shaft. The revolving field type of course allows much greater space for the armature winding, inasmuch as the stationary member is not limited to any particular space, whereas the moving member must be arranged as small as possible to do away with mechanical troubles. Thus, the stationary armature can be wound and properly insulated for great voltages. For this reason the revolving field is generally used in high power work. Another point of importance is that where the armature revolves, the windings must be made very carefully as the centrifugal force due to rapid rotation of the members places a great strain on them.

One of the widely used forms of alternator for extremely high frequencies, is the Alexanderson, named after its originator, *Ernst Alexanderson* (*q.v.*), a noted engineer. This machine is of the inductor type. It is a well-known fact that magnetism is more readily established through iron than through air, and therefore when iron is placed in the air gap of a magnetic circuit, the lines of force or flux lines are greatly increased. Then when the iron is withdrawn, the flux lines fall to their original value. We have seen that as changes of flux take place throughout a magnetic circuit an electromotive force is induced in a coil or conductor (armature) surrounding the magnetic circuit. Now, if iron is periodically inserted into and withdrawn from the magnetic field, an alternating current will be set up in the coil surrounding the field. This principle is made use of in the inductor alternator and the field and armature thus remain stationary, contrary to the usual form of an alternator. Now if we arrange to have pieces of iron moved rapidly in the gap between field and armature, changes of flux will take place. Obviously, it is easy in this manner to create many changes of flux within a certain time, and therefore the alternating current set up (E.M.F.) will have a high frequency as seen by the explanation of this phenomena given previously. These moving pieces are so arranged that they practically close the gap between field and armature with only enough clearance to prevent the rotating member striking the stationary members. This is briefly the principle of the Alexanderson alternator. Fig. 4 shows the general plan of an inductor alternator. On the right shows the scheme of winding in slots around the entire form, and as there are necessarily many windings in order to obtain the high frequency, they are generally single turns of wire, each turn having a separate slot. On the left is given a general idea of the arrangement of the rotor, which in this case, as explained previously, is neither field nor armature, but iron teeth arranged on the periphery of the moving disk. The field is increased or excited in the usual manner by means of a source of direct current. In the assembly, the relation of the moving disk to the field and armature is shown. Fig. 5 is a commercial type of Alexanderson Alternator having a frequency (*q.v.*) of 100,000 cycles used for high power radio transmission (*q.v.*).

ALTERNATOR, SINGLE PHASE—(See *Alternator.*)

ALTERNATOR, POLYPHASE—(See *Alternator.*)

AMMETER OR AMPERE METER—An instrument for measuring current in amperes in a circuit. Is connected in series with a circuit. Exists in a variety of forms. The operation of the most commonly used type depends upon the fact that the force a magnet exerts depends upon the number of *ampere turns* (*q.v.*). Therefore, the greater the current sent through its coils, the greater will be its attraction for a balanced armature. Fig. 1 shows a common form of ammeter.



Photo by courtesy of Weston Elec. Inst. Co.

Fig. 1

AMMETER, THERMAL — Commonly known as "*Hotwire Meter.*" Also called "Aerial Ammeter" and "Radio Frequency Ammeter." Operates on the principle of thermal expansion, i.e., the tendency of a wire to expand with heat of current passing through it. Is used to measure current in amperes at extremely high voltages as in radio transmission. Figure 2 shows a Thermal Ammeter which is generally employed in radio work.



Photo by courtesy of Weston Elec. Inst. Co.

Fig. 2

AMP.—Abbreviation for *Ampere.*

AMPERE—The practical unit of the rate of flow of electricity. It is the unit current, or the rate of flow when one *coulomb* (*q.v.*) flows each second. The value or strength of electric current is almost invariably given in amperes. This unit is used to express the flow of a definite quantity of electricity in a second. If, for example, ten coulombs pass a given point in a circuit in one second, then we say that the current in that circuit is ten amperes. (See *Coulomb, Milli-ampere, Micro-ampere.*)

AMPERE, Andre Marie—A distinguished French physicist, born 1775, died 1836. Noted for his researches in the field of *electro-dynamics.*

AMPERE-HOUR—Commercial unit of quantity. Is that quantity which flows in one hour through a circuit carrying a current of one *ampere.* It is equal to 3,600 coulombs.

AMPERE, INTERNATIONAL—Symbol a—is defined as the unvarying electric current which deposits silver at the rate of 0.00111800 gram per second from a specified solution of nitrate of silver in water.

AMPERE'S RULE FOR DEFLECTION OF NEEDLE—"If one swims with the current and looks at the plus (+) or *north seeking pole* of a magnetic needle it will be deflected to the left, while the negative (—) or *south seeking pole* will be urged to the right."

AMPERE'S THEORY OF MAGNETISM—The theory advanced by *Ampere* that an *electric current continually circulates around each molecule of a magnetic substance and that the process of magnetization is one of arranging these currents in such manner that they all take the same direction.*

AMPERE TURNS—Expressed by the product of number of turns of, and the number of amperes flowing through, the coils of an electro-magnet. Thus, one ampere turn would be one ampere flowing through one turn. The ampere turn is very frequently used as a unit of *magneto-motive force* (*q.v.*) due to the ease with which it can be obtained.

AMPERE VOLT OR VOLT AMPERE—The expression sometimes used to denote *watts* (*q.v.*). For example 1 volt ampere will be one watt, as watts are equal to the product of the volts and amperes in D.C. circuits. (See *Efficiency,* also *Watts.*)

AMPLIFICATION CONSTANT — The factor expressing the maximum voltage *amplification* (*q.v.*) that it is possible to obtain with a given vacuum tube. Thus, if a certain tube will permit amplification of eight times the original voltage, the amplification constant is said to be 8. (See *Vacuum Tube.*)

AMPLIFICATION FACTOR—The ratio of the change of instantaneous voltage, between filament and plate of a *vacuum tube* to a small change of instantaneous voltage between filament and grid for a given constant plate current:

$$y = \frac{\delta\,\mathrm{Vp}}{\delta\,\mathrm{Vg}}$$

The ratio of power (radio signals), voltage or current output of an amplifying device to the power, voltage or current delivered to the input terminals. Generally speaking the degree of increase in amplitude or volume by insertion of an amplifying device in the circuit. (See *Amplification Voltage.*)

AMPLIFICATION, VOLTAGE — In a *vacuum tube* the ratio of the voltage apparent between the terminals of an impedance in series with the *plate,* to the voltage impressed on the *grid.* (See *Amplifier.*)

AMPLIFIER—One of the most important features of the *vacuum tube* (*q.v.*) is its ability under certain conditions to amplify or increase the intensity of electric currents. Such tubes are generally referred to as amplifier tubes and an amplifier is understood to be one or more such tubes with the necessary associated circuits to accomplish amplification.

X—In the accompanying diagram a circuit of a typical one stage *audio frequency* (*q.v.*) amplifier is shown in conjunction with the *detector circuit* (*q.v.*). In this case the *radio frequency signals* (*q.v.*) are impressed at the points A-B from the aerial and ground circuit. The resulting signals at points C-D are audio frequency or voice frequency because they have undergone a change or *rectification* (*q.v.*). Now, if we consider only the solid lines, the circuit will be an ordinary detector circuit and the signals at C-D can be heard by merely connecting the phones at that point in place of the primary of the transformer—P-B. However, by sending these currents through the transformer and impressing them on the second tube it is possible to obtain signals at points E-F of much greater volume and yet having the same general characteristics or sound. The signals or currents will have undergone amplification—the effect of the amplified tube on a local source of power increase the amplitude, but the form or nature of the signals or waves will be the same. (This statement is not entirely true as amplification is generally accomplished only at the expense of some slight changes in the nature of the waves). They will, however, sound about the same in the phones at E-F as they will when the phones are placed at C-D, the volume at E-F being greater due to the amplification. (See *Distortion*). Now it must not be assumed that an amplifier in itself actually has the ability to increase power without some assistance. It is no more possible to obtain something for nothing in electricity than it is in mechanics. What actually takes place is that the amplifier tube and associated circuits control local power—in this case the voltage of "B" battery—in such a manner as to boost or amplify the power of the signals without materially changing their nature. Therefore, an amplifier may be considered as a device which modifies the effect of a local source of power in accordance with the variations of input power, and produces an increased output power or a means of stepping-up or increasing the amplitude or volume of a signal or series of signals. (See *Amplifier Action or Vacuum Tube.*) (See *Amplifier, Audio Frequency, Amplifier Radio Frequency,* also *Transformer.*)



A single stage radio frequency amplifier as used in conjunction with a tuner and detector
Showing the method of amplifying rectified signals at audio frequency

AMPLIFIER ACTION OF VACUUM TUBE—The tendency of a vacuum tube to increase the power or voltage of incoming signals under proper conditions. In the illustration is shown a simple vacuum tube circuit. The incoming signals are impressed on the tube at points A and B. Now it has been noted that small changes of voltage at the *grid* (*q.v.*) will produce much greater changes at the *plate* (*q.v.*). (See *Vacuum Tube, Theory of Operation.*) In other words, the constant changes in value of the incoming signals that are impressed at A-B will produce comparatively larger changes in the current at the plate and therefore larger changes of voltage in the output circuit at C-D. These changes will of course manifest themselves in the form of signals in the phones placed at C-D. Now if these voltages are impressed on a *resistance* (*q.v.*) of suitable value—such as the primary of an amplifying transformer—they can be sent to another tube and again amplified. (See *Amplifier, Audio Frequency.*) In other words the amplifying action of a vacuum tube means the ability of that tube to use input power—the power of the signals delivered to the tube—to control a local source of power such as the "B" battery voltage used on the plate of the tube, and deliver increased power. The signals to be increased or amplified in this manner may be *Radio Frequency* (*q.v.*) or *Audio Frequency* (*q.v.*), each instance requiring a different type of *amplifier* (*q.v.*). The radio frequency signals are amplified by means of a tube and suitable apparatus (transformer or resistance) before they have been changed to audio frequency. The signals that have been *rectified* (*q.v.*) or changed to audio frequency may be amplified by means of a similar arrangement of somewhat different type. The latter would be known as audio frequency amplification. The increase in power is accomplished without any material change in the nature of the signals or wave form (*q.v.*)

AMPLIFIER, INTERMEDIATE FREQUENCY—An arrangment of a *radio frequency amplifier* to increase the strength of signals at the *intermediate frequency* (*q.v.*) as used in a *Super-Heterodyne receiver.* This is usually a radio frequency amplifier using *transformer coupling* (*q.v.*) the transformers being designed to cover extremely high wave-lengths. (See *Super-Heterodyne,* also *Transformer.*)



A single stage radio frequency amplifier as used in conjunction with a tuner and detector

AMPLIFIER, RADIO FREQUENCY — An amplifier used to increase the volume of the incoming signals at *radio frequency* (*q.v.*) before they have been *rectified* by the detector. In the illustration is shown a single stage of radio frequency amplification. This is the transformer coupled type. In this case the incoming signals of radio frequency are increased in strength and then passed on to the detector tube VT2. If further amplification is desired, more stages may be used, the number being held within certain limits due to *distortion* (*q.v.*). If more than three stages are used, it is often difficult to control the *feed-back effect* (q.v.) and efficiency is cut down.

AMPLITUDE—The current or voltage on an A.C. or H.F. circuit at any instant.

The greatest vertical distance above or below zero of the crest or trough of a wave is the maximum amplitude of the wave. In the accompanying illustration the numerals at the left (*ordinates q.v.*) may be assumed to be volts, current (amperes), or voice vibrations. A is the zero point; B the maximum *positive,* C the maximum *negative,* and D the length of the wave. Thus, A. B will be the maximum *positive* amplitude, A C the maximum *negative* amplitude, and D the wave length. B is known as the crest or Node—C is the trough or antinode.

X—Now if in a certain train or group of waves, the amplitude of one wave is less than the one immediately preceding it, there is said to be *damping* (*q.v.*), the degree of this damping or diminishing in amplitude being referred to as *decrement* (*q.v.*). Thus, if we assume that in Fig. 1 the current or amplitude of the first wave is 10 amperes, and the next wave has an amplitude of only 5 amperes, then the damping or decrement is 50 per cent, because the amplitude has decreased that much. Similarly, if the first wave amplitude were 10, and the second were 9 amperes, then the decrease



Line wave showing two cycles of an alternating current, indicating the amplitude and damping

Super Regenerative and *Super Heterodyne.* The principle of regeneration is one that has revolutionized the art of radio reception and broadcasting. The vast majority of present day receivers use regeneration in one form or another. Basically, regeneration is the process of returning a certain portion of the unrectified or radio frequency (*q.v.*) current from the plate circuit. of the detector tube to the grid circuit. This has the effect of reducing the resistance of the grid circuit and thus permitting more ready passage of the weak impulses. The result is not only to greatly increase the sensitivity of the detector to weak signals, but actually to step up or amplify the volume of the received signals. In Fig. 1, coils L1 and L2 are the aerial tuning units in conjunction with the variable condenser, C1; C2 and C3 are variable condensers of low capacity; L3 is the plate control for regenerative action; T is the telephone receiver, G, P and F are respectively the grid, plate and filament elements of the tube; R the filament rheostat, and A and B the batteries for filament and plate. In the illustration Fig. 2, C1 is the aerial tuning condenser, L1 the primary coil of a standard vario coupler; V1 the grid variometer and V2 the plate or regeneration variometer. L2 is the secondary of the vario coupler, and the balance of the elements are as in Fig. 1, GL being the customary grid leak and condenser. Regenerative receivers have come into some disfavor owing to their tendency to radiate annoying signals into the antenna, and also the howling within the set when not properly adjusted. While regeneration in some form or other is used in the majority of receivers, it is not widely used now in its original state. (See *Neutrodyne, Tuned Radio Frequency,* etc.)

There are many types of regenerative set, some extremely simple and others more complicated. The original Armstrong regenerative circuit is shown in Fig. 1. Fig. 2 shows a more modern application of the regenerative principle and at the same time a more complicated one. (See *Regeneration, Super Regeneration* and *Super Heterodyne.*)



Fig. 1. The Original Armstrong Circuit.



Fig. 2. The Armstrong 3-Circuit Regenerative Receiver.

ARRESTER—A device used for by-passing heavy electrical discharges in the atmosphere in the vicinity of the antenna when they strike the antenna. It ordinarily consists of a small gap between two metallic points connected in series with the antenna and ground in order to protect the apparatus and property against danger. (See *Lightning Arrester.*)

A. R. R. L.—Abbreviation for American Radio Relay League.

ARTIFICIAL ANTENNA — See *Mute Antenna.*

ARTIFICIAL MAGNET—A magnet produced by magnetizing a piece of steel that previously had no magnetic attraction. May be produced by rubbing a *natural magnet* or another artificial magnet across a piece of hard steel in the same direction a number of times. (See *Electro-magnet.*)

ASSUMED DIRECTION OF CURRENT FLOW—The direction which an electric current is assumed to take in its flow. Current is generally considered as leaving the *positive* terminal of its source, flowing through the circuits external to the source, and thence to the *negative* terminal of the source. The direction of flow within the source itself is from the negative to the positive terminal. (See *Theory of Current Flow.*)

ASTATIC COILS—Coils wound in such a manner that, when connected together, they neutralize each other's effect and produce no external *magnetic field.* They are used in the measurement of *inductance.*

ASYMMETRIC CONDUCTOR — One that permits the flow of greater current in one direction than in another. Non-symmetrical as to conductivity.

ASYMMETRICAL EFFECT—The lack of symmetry in the directional effect in a loop or frame aerial due to lack of symmetry in construction. (See *Loop Aerial.*)

ASYNCHRONOUS—A term used in referring to AC (Alternating Current) motors or generators and also to *dischargers* used in radio transmission. As applied to alternating current machines it is signified that the speed of rotation of the machine does not have any definite relation to the *frequency* of the currents produced—thus, out of *synchronism.* (See *Synchronous.*)

An asynchronous radio circuit is one which is not tuned to, or in syntony with, the frequency of the *oscillations* impressed on it. (See *Aperiodic.*)

ASYNCHRONOUS ROTARY DISCHARGE—A spark discharge produced at electrodes of a *rotary discharger* (*q. v.*) for transmitting radio signals, in which the spark rate or number of sparks per second has no relation to the *frequency* of the *alternating current.* (See *Spark Discharge.*)

ASYNCHRONOUS SPARK GAP—See *Spark Gap.*

ATMOSPHERIC ABSORPTION — The portion of the total reduction of radiated power due to atmospheric conductivity, reflection and refraction. The amount of energy loss in radio transmission due to atmospheric factors. This applies only to *electromagnetic waves* (*q.v.*) in *motion in the ether* and should not be confused with the reception losses due to atmospheric disturbances.

ATMOSPHERICS — See *X's, Strays, Static.*

ATTENUATION—of the electric or magnetic intensity or of the average energy density in electric waves refers to the reduction in strength with increase of distance traversed due to absorption or equivalent losses, as distinguished from the reduction in strength due to geometrical divergence. In free space, the geometrical divergence of waves from a small source involves a diminution of the average energy density in accordance with the inverse square law; plane waves (e. g., along wires) suffer no reduction by divergence, but undergo attenuation due to resistance and other line faults. (See *Attenuation, Geometrical Divergence*).

ATTENUATION, GEOMETRICAL DIVERGENCE—The gradual decrease in strength of electromagnetic waves (radio signals) as the distance which they have traversed increases. The effect on the waves as they travel through the air is essentially the same as in the case of light waves. Now if a beam of light is viewed one mile from its source it will have a certain intensity, but if it is viewed again from a distance of two miles the intensity will be much less. In the case of radio waves, the intensity is said to decrease as the square of the increased distance traveled; that is to say, if they have a certain power at a distance of five miles from the transmitter, the same waves at twice the distance or ten miles will be found to have a strength only one-quarter as great. Similarly, if the waves travel fifteen miles or three times the distance, the signal strength will be only one-ninth that of the same waves at a distance of five miles from the transmitter.

AUDIBILITY—The measure of strength of received radio signals as heard in a telephone receiver connected to the radio receiving apparatus. A radio telegraph signal which is at all audible can be read, i.e., the dots and dashes distinguished from one another; radio broadcast programs heard with at least some degree of clarity.

AUDIBILITY (Radio Telegraph) — A measure of the ratio of the telephone current producing a signal in a telephone receiver to that producing a barely audible signal. (A barely audible signal is one which just permits the differentiation of the dot and dash elements of the letters sent in code.) In the simple shunted telephone method of measuring signals the audibility is defined as:

$$\frac{s+t}{s}$$

where s and t are the *impedances* of shunt and telephone respectively.

AUDIBILITY FACTOR—A measure of signal strength obtained by observing the *resistance* to be placed in shunt with the telephones of a receiving station to reduce the signals to unit audibility. Approximately, the audibility factor is proportional to the power absorbed from the signal waves by the receiving apparatus. Unit audibility is the strength of signal at which dots and dashes can just be discriminated.

AUDIBILITY METER — A device for comparison of the strength of received signals, either from different stations or with different circuits by means of a variable *resistance* shunted (placed) across the phones. This resistance is decreased until the signals are just audible in the phones. Now, if another station is tuned in, or the circuit changed in some manner, the signals may either be entirely inaudible or they may be much louder, this giving an idea of the *comparative* strength without actual measurement. A popular type of Audibility Meter is shown in the above illustration.



Photo by courtesy of General Radio Co.

An Audibility Meter.

For measurements with an audibility meter, the following shunt formula is used:

$$K = \frac{s+t}{s}$$

Where s is the *impedance* of the *shunt* resistance and t the impedance of the phones, then K is the audibility constant. In general practice a *series* resistance is devised to compensate for the reduction in resistance of the shunt circuit, this keeping the impedance of the plate circuit constant.

AUDIO AMPLIFIER—An *amplifier* used to increase the volume of signals of *audio frequency* (*q. v.*). Audio amplifiers are connected in the circuit of the detector in place of the phones (input) as shown in Fig. 1. This is the standard two stage audio amplifier. The separate stages each consist of a *vacuum tube, a transformer, socket* for the tube and a control *rheostat*. If desired one rheostat may be used for both amplifier tubes as the *filament* current (*q. v.*) can be the same if the tubes are of a similar design. This is known as "transformer coupled amplification." Another much used method is known as "resistance coupled amplification."



Fig. 1. A standard two stage Audio Amplifier employing phone jacks for detector, first stage, and second stage Audio Amplifiers.



Fig. 2. A one stage Audio Amplifier connected to a crystal receiving set.

Fig. 2 shows one stage of audio frequency amplification connected to a crystal receiving set. There are numerous variations of audio amplification. (See *Push-Pull Amplification*, also *Resistance Coupled Amplifier*, and *Power Amplifier*.)

AUDIO FREQUENCY — A frequency corresponding to normally audible sound waves, i.e., between 40 and 10,000 per second. The limits of audibility are given variously from 16 to 20,000 cycles, but for ordinary usage may be taken as from 40 to 10,000 cycles per second. In audio frequency amplification as used in conjunction with the tuning and detector apparatus of the radio receiving set, the volume of the received sound is amplified or increased over that of the originally rectified sound waves. (See *Radio Frequency;* also *Amplifier.*)

AUDION—The name given by Dr. L. De Forest to a *vacuum tube detector* which possesses a glowing *cathode* and has a steady E. M. F. (*Electromotive force*) permanently applied between *anode* and hot *cathode* and two cold *anodes*. (See *Vacuum Tube.*)

AUSTIN, Louis Winslo, Ph.D.—Born in Ordwell, October 30th, 1867. Graduated at Middlebury College and studied at Clarke University and the Universities of Strasburg and Berlin. Noted for the fact that he is head of the U. S. Naval Telegraphic Laboratory, Washington, D. C., and for his work in measuring high frequency currents.

AUTO-COHERER — A coherer having automatic action to release the particles that cohere when circuit is established. Now obsolete. (See *Coherer.*)

AUTODYNE RECEPTION—See *Self-Heterodyne Reception.*

AUTO INDUCTIVE COUPLING—See *Coupling.*

AUTOMATIC INTERRUPTER—A vibrating electro-mechanical device to make and break an electric circuit by using the energy passing through it. The most common example is that of a *spark coil.* An interrupter may be used for several purposes. In the case of a spark coil it is used to produce sparks for transmission of signals. In another form it may appear in a mechanical battery *charger*, in this instance being used to interrupt the *alternating current* and permit passage of the current in one direction only. A *buzzer* uses a type of interrupter—a vibrating device producing a buzzing sound having a pitch dependent on the rapidity with which the vibrations take place.

AUTOMATIC TRANSMITTER—An apparatus for operating a sending *key* mechanically. (See *Wheatstone Transmitter.*)

AUTOPLEX—A type of radio receiver employing one vacuum tube, operating along the lines of the *Super-regenerative* principle and designed to operate a Loud-speaker. The circuit comprises two standard variometers, a 1500 turn duo-lateral coil, and the usual vacuum



Circuit of the Autoplex radio receiver.

tube, socket, batteries, etc. It is extremely critical in operation, but if carefully assembled will give excellent volume under good conditions. Illustration shows the circuit diagram of the Autoplex receiver.

AUTO-RECEIVER—A device for the automatic reception and recording of radio signals. It is essential in the reception of signals transmitted by an Automatic transmitter (see *Wheatstone Transmitter*) as the speed is too high to permit reception by ear. There are three general classes of automatic receiver: a *resonance intensifier* in conjunction with an inking arrangement; a *phonographic recorder* and a recorder using *photographic means.* In the latter method, a powerful beam of light is projected on to a mirror which is arranged to respond to the signals in approximately the same manner as a mirror *galvanometer.* In the phonographic type, the signals are reproduced on a drum. (See *Resonance Intensifier, Photographic Recorder,* also *Phonographic Recorder.*)

AUTO TRANSFORMER—A device for changing voltage in a circuit carrying alternating currents. A form of *transformer* having but one winding, any part of which may be used as the *primary* and any part as the *secondary.* In Fig. 1 the two windings P and S are continuous, although different sizes of wire may be used according to the purpose for which intended. In this case the voltage taken from the secondary D E will be less than the voltage impressed at A B, because the secondary has fewer turns of wire than the primary. Now in Fig. 2, this conditions is reversed, and as the primary has only a few turns of wire and the secondary has a comparatively large number, the voltage obtained from D E will be greater than that impressed at A B. The voltage ratio is approximately proportional to the ratio of wire turns. Thus, if the primary has 100 turns of wire and a pressure of 100 volts is placed at A B, then the voltage at D E would be within certain limits about equal to the number of turns of the secondary. In other words, if the number of turns on the secondary is one-third the number of turns on the primary, then the voltage at D E will be approximately one-third that impressed at A B. The main advantage of the autotransformer is that a saving is accomplished by having the primary and secondary windings combined. The chief disadvantage is that where extremely high voltages are used there is always danger of the two windings becoming crossed or shorted. (See *Short.*) For this reason they are used mainly for comparatively low voltages. One of the most common forms is the step-down type, known as a "bell-ringing transformer." These are used to cut down the voltage of an electric light line to suitable value for use with small toys or bells. If the transformer is used to increase the voltage, it is known as a "step-up" transformer. (See *Transformer—Radio, Audio.*)



Fig. 1.



Fig. 2.

AUTO TRANSFORMER COUPLING—See *Coupling.*

B

B—Abbreviation for Baumé, the scale used in a *hydrometer* (*q.v.*)

B. A. AMPERE—The standard ampere fixed by the British Association for the Advancement of Science.

BACK COUPLING—See *Reactance Coils.*

BACK ELECTRO-MOTIVE FORCE—An *Electromotive force* (E.M.F.) which opposes the original electromotive force. The more common term is "*Counter E. M. F.*" In many arrangements of electrical circuits there will be an electromotive force set up in such manner as to oppose the impressed voltage or force. This will be true in the case of a *choke coil* in which any variation in the pressure or electromotive force applied to the coil will result, under proper conditions, in the production of a back or counter-electromotive force that will oppose the change in the original force.

This phenomena is frequently found in electrical circuits; at times introduced for a purpose and at others self-introduced, and therefore demanding consideration in design of apparatus. The rotation of the *armature* of a motor creates a counter E. M. F. opposed to the impressed E. M. F. and upon which the driving power of the motor depends. When an external E. M. F. is impressed on a circuit in which there exists a local E. M. F., the flow of the current through that portion of the circuit containing the local E. M. F. will result in an increase or decrease of energy depending on whether the local E. M. F. is opposed to, or in the same direction as, the external E. M. F. (See *Counter Electromotive force.*)

BACK OSCILLATION—When the *condenser* of a transmitting circuit of the spark type discharges across the *spark gap* some of the *high frequency* current may flow back through the secondary of the transformer instead of taking its normal path across the gap. This back flow is usually referred to as *Back oscillation* or kick back, and is apt to break down (see *Breaking Down of Insulation*) the insulation of the transformer if not prevented or controlled. Back oscillation is retarded ordinarily by means of coils of wire having a certain arbitrary *inductance* value. When the high frequency discharge from the condenser has any tendency to break through, the *reactance* of these coils becomes so great that they act in effect as insulators. As the capacity and inductance of these coils might create an *oscillatory circuit* of the same *natural period* as the primary oscillator, they are shunted with non-inductive carbon resistances. These coils are termed "*choke*" coils.

BAKELITE—An insulating material having widespread use in radio. It possesses great strength and has a high *dielectric* (insulating) value together with the ability to withstand high temperatures. This material is furnished in many forms and under a variety of trade names, being considered one of the best of the insulating compounds.

Chemically known as *Oxybenzylmethylenglycol anhydride.* It is produced by the union under heat and pressure of phenol and formaldehyde together with a small percentage of some alkaline agent. Is heat resisting up to about 500 degrees Fahrenheit—disintegration setting in somewhere above that point.

BALANCED CIRCUIT—An electric circuit arranged in such manner with relation to adjacent or neighboring circuits as to do away with the effect of *mutual induction* (*q.v.*).

BALANCED DETECTORS—A term applied to an arrangement of opposed rectifying *detectors* for reducing the effects of strong *strays* in receiving apparatus. The detectors must be balanced for violent *electro-motive forces,* but not balanced for the moderate E. M. F.'s due to the signals. Actually, a method of eliminating stray impulses in reception.

BALANCED METALLIC CIRCUIT—A circuit through conductors (wire or any metal) in which the total resistance is the same on each side of the circuit. (See *Circuit.*)

BALANCED ROTARY CONDENSER—A variable condenser having some arrangement for keeping the plates accurately balanced in rotation at all points. Fig. 1 shows a form known as the "balanced plate" type. In this case the plates are so arranged that half the movable plates are on one side and half on the other side of the shaft. This maintains the balance of the part. Fig. 2 shows another method known as "counter-balanced." The weight of the balance is the same as that of the movable plates and its position on the other side of the shaft serves to maintain balance. The idea is to prevent the plates slipping due to lack of balance and thus keep the setting at the desired point after adjustment.



Fig. 1. A "Balanced-Plate" type Rotary Condenser.



Fig. 2. A Counter-Balanced Rotary Condenser and illustration showing how the counter balance is attached to shaft.

BALANCING—Any method of eliminating interference by reducing the *amplification* of the undesired signals while permitting full amplification of the desired signals. (See *Interference Eliminator.*)

BALANCING AERIAL—An aerial system designed to permit reception of signals from distant points without interference from a powerful nearby transmitter. The system involves the use of two aerials, one for balancing, the other for receiving. The receiving aerial is tuned to the wavelength of the desired signals, while the balancing aerial is tuned to the wavelength of the nearby station (the interfering signals).

In operation the receiving circuit is coupled to each aerial *electro-magnetically,* and is acted on by both series of *oscillations* (distant and nearby waves). By careful adjustment of *coupling* and phase relation of the *induced currents,* the interfering wave may be balanced out in effect and the desired oscillations received.

BALDWIN RECEIVER — Perhaps the most sensitive type of telephone receiver thus far developed. It employs what is known as a "balanced armature," the signals being produced by the vibrations of a *diaphragm* which is not acted on directly by the magnets. The illustration shows the general plan of a receiver of this type. The *armature* (A) is of soft iron and is pivoted between two U-shaped soft iron pieces (M1, M2) mounted on the ring-shaped horseshoe magnet (M) as indicated. The armature is acted on by the magnets in response to incoming signals and the movement of this element in turn acts on the mica diaphragm (D) by means of a fine brass wire (C). The usual windings (R) are placed between the two pole pieces, the armature being mounted in a central slot. These receivers are much used both for headphones and for loud-speaker units. In the latter case the mica diaphragm is generally made heavier to handle the more powerful vibrations due to the *amplification* of the signals.



Principle plan of the Baldwin Receiver unit.

When no fluctuating impulses (signals) flow through the windings (R), there is no *magnetic stress* on the armature (A), because this member is suspended centrally between the pieces (M1) and (M2), the magnetic attraction of which are equal. Now when a fluctuating impulse flows through the windings (R) it produces a magnetic flux which combines with the flux of the permanent magnet (M) and the total flux is distributed asymmetrically or unevenly on both sides of the armature. The result is a rocking vibratory movement to this member which is in turn communicated by the juncture wire (C) to the diaphragm (D), producing the audible signals. (For a comparison of this action with the conventional telephone receiver action, see *Telephone Receiver.*)

BALKITE BATTERY CHARGER—An electrolytic battery charger which makes use of a sulphuric acid solution and tantalum as the valve metal. Used for charging *storage batteries* from *alternating current.* See illustration.



Photo by courtesy of Fansteel Products Co.

A Balkite Battery Charger.

Note: The name Balkite is derived from the name of the man who perfected the process of extraction of tantalum from its ores.

BALLAST TUBE—An automatic means of regulating the *filament current* of vacuum tubes. The device is enclosed in a glass tube and is arranged to permit passage of a certain fixed amount of current. The ballast element is a wire whose *resistance* changes with the current through it, due to the change of resistance with the temperature of the wire. When the *electromotive force* increases beyond normal, the increased current raises the temperature and hence the resistance, so that the current is held to the normal value.

B. and S.—Abbreviation for Brown and Sharpe Gauge (*q.v.*).

BAND OF FREQUENCIES—A continuous range of *frequencies* extending between two frequencies. (See *Band of Wavelengths;* also *Band Pass Filter.*)

BAND PASS FILTER—A *filter* arrangement designed to permit passage of all *frequencies* extending between two definite frequencies but excluding all other frequencies. (See *Band of Frequencies.*)

BAND OF WAVE-LENGTHS—A continuous range of *wave-lengths* extending between two definite wave-lengths. For example, the usual broadcast band of wave-lengths is approximately 250 meters to 550 meters.

BANKED BATTERY—A *battery* that has its *cells* connected in *parallel.*

BANK WINDING—A form of winding for coils in which the turns are staggered so that two or more layers may be used without having large distributed capacity losses. The illustration shows method of bank winding for two layers. Note that in this form the *electrostatic capacity* between any two turns is only that between adjacent turns, representing only a small part of the total winding, whereas on the usual form of winding the adjacent turns would represent a good portion of the total *inductance* and hence the effect of distributed capacity would then be much greater. (See *Distributed Capacity.*)



Method of bank winding wire on a coil form.

BARRETER—A receiving instrument consisting essentially of a small mass of conducting material that is heated by the passage of an *oscillatory* current, and arranged so that the consequent alteration of electrical *conductivity* affects an indicating instrument, such as a telephone receiver or *galvanometer.*

BASKET COIL—Variometers—couplers, etc. (See *Basket Wound.*)

BASKET WOUND—A method of winding coils, such as variometers or variocouplers. The winding is a latticework of wires in skeleton form, the object being to save weight and eliminate large losses such as occur in the types using a great deal of solid insulating material. The illustration shows a popular form of basket variometer.



Photo by courtesy of Amer. Radio & Research Corp.
A Basket Wound Variometer.

BATTERY—In the electrical field, a group of *primary or storage cells, dynamos*, or *condensers* grouped together to form a single unit. The term is often used incorrectly to refer to a single cell—as "dry battery," the correct name for which is "dry cell." Thus a group of condensers joined together as one unit is termed a battery, also a number of dynamos arranged as a single unit for the production of electrical energy. (See *Dry Cell*, also *Battery of Alternators, Storage Battery, "A," "B" Battery*, etc.)

"B" BATTERY—An appliance for obtaining electricity of sufficient voltage to supply the plate of a *vacuum tube*. There are two types of "B" batteries, viz., the *dry cell* type and the storage types. In order to obtain the high voltage required for vacuum tube plates, many small cells are connected in series. The usual method is to connect them together and seal in a square package. Often taps are brought out so that various voltages may be obtained for *critical* vacuum tubes. The most popular voltages which dry cell "B" batteries give are 22½ and 45 volts. The storage "B" battery is similar to the ordinary storage battery with the exception that the cells are much smaller, but contain more cells in series. These can be charged in the same manner as the "A" or *storage battery*. In Fig. 1, we have a popular type of "B" battery. This is tapped in order that different voltages may be obtained.

EVEREADY
RADIO

Photo by courtesy of National Carbon Co., Inc.
Fig. 1-A. A popular type of "B" Battery of 22½ volts.



Photo by courtesy of Burgess Battery Co.
Fig. 1-B. A "B" Battery showing the contents of small cells.



Fig. 2. Manner of connecting a "B" Battery in the circuit of a vacuum tube detector.

The manner of connecting up the "B" batteries in radio receiving is shown in Fig. 2. Here one battery of 22½ volts is used. In Fig. 3, three batteries are connected in series so that 67½ volts are obtained.



Fig. 3. "B" Battery of 67½ volts connected in an amplifier circuit.

A common "B" battery may be used for the detector tube and the amplifier as shown in Fig. 4.



Fig. 4. How a common "B" Battery may be used both for detector and amplifier.

If separate batteries for each tube are desired, the circuit should be connected as in Fig. 5. This lengthens the life of the "B" battery as the drain on the battery is much less, i.e., only one vacuum tube is operated on each battery.



Fig. 5. Method of employing separate "B" Batteries for the detector and amplifier.

BATTERY OF ALTERNATORS—In ordinary electrical work such as house lighting, several *alternators* for the production of alternating current may be used together as one source of power. Also in high-power radio transmission, several *high-frequency alternators* may be used together to produce added power. (See *High-Frequency Alternator.*)

BATTERY TESTING INSTRUMENTS—The various devices used for determining the condition of batteries used as radio apparatus. (See *Ammeter, Voltmeter*, also *Hydrometer.*)

BEAT FREQUENCY—The *frequency* or number of vibrations per second of a series of *oscillations* representing the difference between two other series having different frequencies. It is numerically equal to the difference between the original two series of oscillations. Thus, if we have a series of oscillations having a frequency of 100,000 *cycles* per second, and combine it with another series having a frequency of 90,000 or 110,000 cycles, the *beat frequency* will be 10,000 cycles or the difference between the other two frequencies.

X. The frequency of recurrence per second of either maxima of addition or minima of opposition of two superposed periodic phenomena having the same nature but of different frequencies. The time measure of vibration of a beat or heterodyne. (See *Heterodyne*, also *Beats.*)

BEATS—When two sets of *oscillations* of different *frequencies* occur in the same system, the difference in the frequency or rapidity of vibration causes a new set of oscillations having a frequency equal to the difference between the original two sets. This may be accidental as in the case of certain types of receivers such as the *regenerative* type, in which case the beat oscillations are undesired and cause interference or disturbances in the set. Then again a beat frequency may be purposely introduced as in the case of the *Super-Heterodyne receiver*. Here we have the natural incoming oscillations from the antenna combined with a series of oscillations produced locally in the system. The result is a new set of oscillations where the incoming series and the locally produced series are not of the same frequency. (For more complete explanation see *Super-Heterodyne Receiver.*)

X. Where two *periodic phenomena* are *super-posed* or run together and the frequencies differ, the gradual change in *phase difference* produces a condition wherein the *amplitudes* are in opposition at one instant and in concurrence at a later instant with the various intermediate stages during the interval. (See *Heterodyne*, also *Beat Frequency*.)

BEG OHM—A *resistance* of one billion *ohms*. (See *Megohm*.)

BELIN, EDOUARD—French scientist, the inventor of what is considered the first practical system of radio transmission of photographs. The device can be used for sending photos by cable or telephone lines as well as radio. (See *Transmission of Photographs by Radio*.)

Brown photo.
Edouard Belin.

BELL, Alexander Graham (1847-1922)—Scottish scientist. Born in Edinburgh, March 3rd, 1847, he was educated at the High School and University and graduated as a doctor of medicine. In 1870 he went to Canada, and in 1872 became professor of vocal physiology in the University of Boston. In 1876 he exhibited his apparatus for the transmission of sound, afterwards developed into the telephone. Bell was experimenting with an electric invention by means of which he hoped to make speech visible to the deaf. A delicate metal reed was caused to vibrate by spoken speech and to transmit an electric current to the opposite end of a wire, where the vibrations of the first reed were reproduced in a second reed by a magnet. He found that it was possible to transmit not merely vibrations of the original reed, but to reproduce the sound itself in the vibrations of the second reed. In 1878 he invented the photophone, to enable sound to be transmitted by variations on a beam of light, and later a phonograph. Bell was the author of many scientific papers, was awarded the Albert Medal of the Royal Society of Arts in 1902 and the Hughes Medal of the Royal Society in 1918. He died Aug. 2nd, 1922.

Alexander Graham Bell.

BELLINI, Dr. Ettore—Born in Foligno, Italy, April 13th, 1876. Educated at the University of Naples. Noted as Electrical Engineer to the Royal Italian Navy, and chief of the Naval Electrical Laboratory at Venice. Joint inventor with Captain Tosi of the "Radiogoniometer" (*q. v.*), a device for finding the direction of transmitted radio signals.

BELLINI-TOSI AERIAL — See *Goniometer*.

BELLINI-TOSI DIRECTION FINDER —See *Goniometer*.

BEZEL — In mechanics, generally a groove and flange made to receive a beveled edge. In its adaptation to radio some liberty was taken with its real meaning. Its significance in this sense is a small metal ring having a wire mesh or glass center. It is fitted into a circular hole in the panel of a radio receiver and used as a peep hole to enable the operator to know at all times the conditions of the tubes, whether or not they are properly lighted.



A Bezel on the panel of a radio receiving set.

BILLI CONDENSER—A variable *condenser* of low *capacity*, consisting of two brass tubes, one of which is arranged to slide in and out of the other for the purpose of varying the capacity. Such condensers were much used before the days of broadcasting, in conjunction with any circuit using a crystal and battery for detector. This type of condenser has long been obsolete in the United States.

BINDING POST—A screw and nut arrangement used on electrical units and radio apparatus to make convenient connections from an external source to the desired point within the apparatus. Binding posts are provided, for instance, to make handy connections from batteries to the set and from the aerial and ground leads. The illustration shows a popular type of binding post.


Photo by courtesy of The H. H. Eby Mfg. Co.
A group of Binding Posts as used on electrical and radio apparatus.

BI-POLAR—Having two *poles*. Usually a *dynamo* or motor whose *armature* rotates between a *field magnet* having only two poles. The most modern types are of the Multi-polar variety. (See *Bi-polar Magnetic Field*.)

BI-POLAR ARMATURE WINDING—An *armature* wound in a manner to permit its use with a dynamo having a bi-polar magnetic field.

BI-POLAR MAGNETIC FIELD — The magnetic field (*q.v.*) created between two magnetic poles. The illustration shows a common form of bi-polar magnet for a dynamo. Bi-polar magnetic fields are now used as a rule only for direct current machines of low power, such as those under 5 *Kilowatts*. (See *Dynamo*, also *Generator*.)



A Bi-Polar Magnet of a dynamo.

BI-TELEPHONE RECEIVER—A headset with two receivers or phones as generally used in radio. In the early days of radio transmission it was the custom to use only one phone.

BLONDEL, Andree—French electrical expert. Born at Chaumont, France, in 1863, he graduated at Paris University, and studied electric waves, on which subject he early contributed a number of papers to various scientific journals. In 1893 he invented the *oscillograph*, an instrument somewhat similar to a mirror *galvanometer*, for showing curves of *oscillating* or *alternating currents*. This invention opened up a fresh field in the study of alternating currents. In the same year Blondel explained for the first time mathematically the effect of inertia in the shunting of *alternators*. He is responsible for a system of acoustically syntonic wireless telegraphy, and for directed waves produced by a double aerial. In 1902 he patented a method for producing electric oscillations for wireless telephony, and has written many papers on microphonic control for transmitters, wireless telephony, the singing arc, etc.

BLONDLOT, Professor Prosper Rene—French wireless expert. Born at Nancy, France, in 1849, studied at

Paris, and became professor at the faculty of sciences, Nancy, and afterwards Honorary Professor and Correspondent of the Institute of France. Professor Blondlot is famous for his studies of electro-magnetic waves, particularly with regard to their speed, and the laws of *propagation* of wireless waves in various media.

BLOWER MOTOR—A motordriven fan used to deliver a high pressure blast at the *spark gap* to prevent *arcing.* (See *Spark Gap,* also *Spark Discharger.*)

BLOWOUT—See *Magnetic Blowout.*

BLUE GLOW — A condition within a *vacuum tube* when the vacuum has become poor. After continued use a tube will often hold a small percentage of gas, which causes a blue glow when current is passed through it. A tube in this condition is a poor *detector* or *amplifier* and should be replaced. The condition should not be confused with the glow often caused by an excessive voltage. In this latter case decreasing the voltage to the normal value will generally permit the tube to be operated efficiently. The blue glow in this case is due to *ionization* of the residual gas by the excessively high *potential* impressed across the elements of the tube.

BOARD OF TRADE UNIT — B.O.T. 1,000 Watt Hours. One and a third Horse Power.

BODY CAPACITY—The effect of the human body when tuning a radio receiving set. The hand when placed on or near the controls very often throws the receiver out of balance with the incoming signals. In the case of very *sharp tuning* this effect is more in evidence and is likely to cause howls due to *self-oscillation.* The howling is due to the production of an audible *beat frequency* in the system, caused by the combination of the local *oscillations* with the incoming signal oscillations. The remedy may be to shield the panel with metal foil or in some cases to merely alter the direction of the leads from the *tuning condenser.* The experienced operator seldom pays much attention to the phenomena, as a little practice enables the listener-in to compensate for the effect. To make this more clear, if, when tuning the set, the withdrawal of the hand from the dial *detunes* the set or throws it out of balance, it is due to the fact that the hand has acted as a certain amount of *capacity* in the circuit, and naturally its withdrawal is equivalent to a change in the condenser setting. A simple system is to turn the control beyond the point of maximum volume, then when the hand is withdrawn the capacity will drop to its proper value. This can be mastered very readily. If the tuning condenser is connected across the secondary, i.e., one side to the grid, and the other to the grid return, the stator plates of the condenser should be connected to the grid of the tube. If metal foil or thin copper sheeting is used for shielding it should be connected to the ground post of the set.

The tendency of the human body to insert an arbitrary capacity in the circuit. The phenomena is especially noted where maximum volume is obtained only by very critical control close to the oscillating point, in which case the circuit may be thrown out of resonance.

BOLITHO CIRCUIT—A *super-regenerative circuit* patented in England in 1919 by Captain J. B. Bolitho. The circuit was originally intended to operate a relay device. The circuit has been adapted to use as an *amplifier* for radio reception.



Diagram of the Bolitho Circuit.

In the illustration the phones may be replaced by a loud speaker or relay. In operation, T1 is held at a point just below that where *oscillation* sets in by means of T2 which is excited by an oscillator O in the plate circuit and coupled by means of coil L4 to the tuned grid circuit through L2 and L3, the coupling, as explained, being so arranged that the tube is always just below the oscillating point. A *reaction coil* L4 is placed in the plate circuit of T2 in such manner as to oppose the magnetic linkage between coils L2 and L3. The *frequency* of the generator O is lower than that of the received signals. As indicated, the grids of both tubes T1 and T2 are joined together and the tube T2 maintains the circuit in a receptive condition when tube T1 is tuned just below the oscillating point.

The oscillator O makes the *plate* of T2 alternately *positive* and *negative* with the following effect: When the plate of T2 is negatively charged there is no current in coil L4, this coil therefore not affecting coils L2 and L3, and permitting tube T1 to build up self oscillation. When the plate is made positive by the action of the oscillator, current flows through coil L4, and as it is coupled in opposition to coils L2 and L3 it neutralizes the coupling between L2 and L3 and prevents transfer of energy between the grid and plate circuits of the tube T1. This tends to stop the self oscillation and makes the circuit receptive to the energy (signal) produced by outside signals in the aerial coil L1. The frequency, of course, is determined by the frequency of the oscillator O. The system is especially adapted to the reception of continuous wave signals. (See *Super-regenerative circuit,* also *Feed-back* and *Regenerative circuits.*)

BOLOMETER — Type of *Wheatstone Bridge* having an easily heated *resistance,* such as a very fine wire in one arm. (See *Wheatstone Bridge.*)

BOOSTER—An expression signifying a small *dynamo* used in conjunction with main dynamo to temporarily raise, when necessary, its normal *pressure.* It is generally driven by a motor supplied with energy from the main generator and thus becomes in effect a *continuous current transformer.* Frequently used for charging *accumulators* of a generating plant. The term "Boost" is also used to denote increase or a stepping-up of any electrical quantity. (See *Amplification.*)

BORNITE — A *crystal rectifier* much used in radio reception. It is a natural sulphide of iron and copper, having a metallic blue lustre. This mineral is used in combination with zincite or copper pyrites as a crystal detector. Such combinations are generally known as "crystal to crystal" detectors to distinguish them from the ordinary variety using one mineral and a wire contact.

BORON—A non-metallic chemical element used in radio as one of the electrodes for the *T. Y. K. Arc.* Chemical symbol B, atomic weight 11.0, specific gravity 2.6.

B. O. T.—The customary abbreviation for *Board of Trade Unit.* The unit represents 1,000 *watt hours.* (See *Board of Trade Unit.*)

BOX AERIAL—A term occasionally applied to loop aerials. (See *Loop aerial,* also *Frame Aerial.*)

BRADFIELD INSULATOR — A particular form of *Lead-in Insulator,* consisting of an ebonite tube provided with zinc cone and ebonite spark discs, for breaking up continuous streams of rain running down outside which might cause the aerial to become grounded. The whole is held in position, half way through roof of operating room, by means of a stuffing box. The aerial is led in by means of a conducting rod through center of tube. (See *Petticoat insulator.*)

BRANLY COHERER — Early form of *Marconi Coherer.* (See *Coherer.*)

BRANLY, EDOUARD—French radio expert. Born at Amiens, France, Oct. 23rd, 1844. He was educated at Paris and afterwards became Fellow of the University, doctor of physical science, and doctor of medicine. Branley early made a study of electro-magnetic waves, and in 1890 and 1891 patented methods of operating a local relay circuit from a distance by means of wireless waves. In 1900 he was awarded the Grand Prix by the International Jury of Superior Precept Instruction for his exhibition of radio-conductors.

In 1890 Branly published an account of his very extensive series of observations on the electrical conductivity of loosely packed metal filings, and he made the extremely important observation that an electric spark at a dis-

Edouard Branly.

tance had the power of suddenly changing the electric *conductivity* of loose masses of powdered *conductors*. To Branley is due the *coherer* named after him.

BRAUN, FERDINAND — Professor at the University of Strasburg, and one of the leading world authorities on Radio transmission. As early as 1899 Braun was granted a patent for *closed oscillating* systems with an *inductively coupled* antenna. The system was claimed by Braun to possess a much greater efficiency than the directly coupled systems. The Braun transmitting set, as manufactured by Siemens and Halske, consisted of a large coil worked into an *electrolytic interrupter*, a set of *Leyden jars*, enclosed *spark gap*, *oscillation transformer* wound with insulated wire placed in oil, and for the receiving set the standard type of *coherer relay* and Morse register. In 1899 Braun established communication between Cuxhaven and Heligoland, using aerial wires 90 feet high, and the inductive coupled aerial connection for transmitting. In 1903 Braun joined with Slaby, von Arco, and Siemens to form the Telefunken system of transmission. Professor Braun was awarded the Nobel prize with Marconi in 1900, for his work in wireless. Braun has devised a method of directional wireless which depends upon the interference of *electric waves* travelling in the same direction but different in *phase*. Three simple vertical wire aerials are set up in positions corresponding to the angular points of an equilateral triangle, and *oscillations* are created in these which differ from one another in phase. In 1897 Professon Braun published a description of his cathode ray tube, and afterwards pointed out, in 1902, how such a tube could be used to trace the forms of alternating current waves.

BRITISH STANDARD WIRE GAUGE —The standard wire gauge of Great Britain. The table shows the various diameters in thousandths of an inch (mils.).

WIRE GAUGES IN MILS.

GAUGE	New British Standard
0 000 000	500
000 000	464
00 000	432
0 000	400
000	372
00	378
0	324
1	300
2	276
3	252
4	232
5	212
6	192
7	176
8	160
9	144
10	128
11	116
12	104
13	92
14	80
15	72
16	64
17	56
18	48
19	40
20	36
21	32
22	28
23	24
24	22
25	20
26	18
27	16.4
28	14.8
29	13.6
30	12.4
31	11.6
32	10.8
33	10.0
34	9.2
35	8.4
36	7.6
37	6.8
38	6.0
39	5.2
40	4.8

BREAK or BREAKER — See *Circuit Breaker.*

BREAKDOWN POTENTIAL or BREAKDOWN VOLTAGE—The voltage necessary to *break down* or puncture a *dielectric*. The ability of any *insulating* material to resist breakdown is an important matter. An insulator or dielectric material is usually given a certain rating or point above which it is likely to fracture. Thus, a condenser may have a breakdown rating of 500 volts. That is to say that voltages up to 500 and slightly over may be handled with safety, but any large increase above that figure may result in puncture of the material by the excessive potential or voltage. The relation between dielectric strength and breakdown voltage is shown in the following formula:

$$V = cd\ \tfrac{2}{3}$$

Where d is the thickness of dielectric in millimeters

V the potential difference in volts

c-a constant representing the potential difference required to cause a dielectric breakdown of a sample of the material 1 mm. thick. (See *Dielectric Strength.*)



Fig. 1. A bank of 250-watt transmitting tubes in a Radio Broadcast Station. Note the small receiving tube for comparison of size.

BREAKING DOWN OF DIELECTRIC— In a *condenser*, the gradual weakening of the *dielectric* or insulating sheets which eventually causes them to permit direct passage of the current. For example, if a force of 1000 volts is applied for a considerable period to a condenser that has been designed for a maximum of 500 volts, the insulating material between the plates would probably be punctured by the current. (See *Break-down Potential.*)

BREAKING DOWN OF INSULATION —The same effect as referred to under *Breaking Down of Dielectric.* The insulation weakens and permits the ready passage of electric currents. (See *Break-down Potential.*)

BRIDGES—See *Capacity Bridge*, also *Wheatstone Bridge.*

BRIDGING—A term occasionally used for *shunt* (q.v.) connections. Thus, a grid condenser is generally shunted or bridged by a *grid leak.*

BROADCAST—Transmission of music, news and other matters of general interest and entertainment by means of *radio telephony.* (See *Broadcasting, General Treatise on Methods.*)

BROADCASTING, GENERAL TREATISE ON METHODS—The application of radio telephony to the transmission through the ether of musical programs, speech or any form of news or entertainment, in such manner that it can be readily received by anyone possessing a radio receiver sufficiently sensitive and capable of being tuned to resonance with the particular waves being sent out. While broadcasting in its present world-wide scope is a comparatively new enterprise, it has actually been used to a more or less degree since the practical development of the wireless telephone. As near as records can be determined, the first actual broadcasting was done in 1912. It was, however, not until after the world war that it began to develop into an industry of prominence. Now it occupies a place of very definite importance in everday life; carrying news and entertainment into the remote corners of the earth, far removed from telephone or telegraph communication.

The fundamental principles of broadcasting are essentially those of radio transmission, with the addition of means of combining the speech or music vibrations with the regular radio waves. First we have to consider the radio waves of high-frequency—alternating current that changes in direction many thousands of times each second. These high frequency waves are known as the carrier waves. The frequency of these waves varies according to the length of the waves (wavelength), in the case of American broadcasting stations, being between 250 and 550 meters in most cases, which means a frequency range of approximately 550,000 to 1,200,000 cycles.

Now by means of a microphone, a device similar in principle to the mouthpiece of an ordinary telephone, but designed to handle large currents, the air pressure waves, i.e., speech or music, are converted into variations of electric current. By use of suitable amplifying apparatus, the strength of the electric waves radiated from the antenna is varied to correspond electrically to the acoustic or sound variations due to the speech or music being impressed on the microphone. The speech or music waves are low frequency waves, generally ranging between 100 and 4000 per second. Thus, while the carrier wave oscillations are of high frequency, the variations in it are low frequency, corresponding to the ordinary speech or music vibrations.

The process of varying the radiated wave in accordance with the sound waves is known as *modulation*. This adjustment is of the utmost importance, as defects here result in distorted or improperly modulated sound waves and the reproduction cannot be perfect. The reception of broadcast programs is essentially the same as that of ordinary radio signals, with the exception that care must be used at the receiving end to preserve the form of the original vibrations. When dot and dash signals are received, the tone is of comparatively little importance, whereas with voice or music it is essential that the tone quality be retained.

In broadcasting the high frequency oscillations are produced by means of a tube or group of tubes, practically identical with those used for reception, but designed to handle large currents and voltages. The majority of American stations use vacuum tubes of 250 watts power rating, one or more of them being used to obtain the total power required. These tubes are shown in the illustration, Fig. 1.

When a program is being broadcast, the action is somewhat as follows: The artists are disposed before the microphone with due regard to the effect of certain instruments. That is to say, one type of instrument may be placed near the microphone, while another must be placed farther away, owing to the differences in tone and volume. This is done to prevent any one tone or range of tones from predominating. These speech or music currents are converted into electrical variations by the microphone and then increased many times in power or amplitude by means of a speech amplifier system, comprising vacuum tubes and the necessary associated circuits.

These amplified currents are applied to the grid of a control tube or bank of tubes and result in large variations in the plate current of the tubes. (See *Theory of Vacuum Tube.*) The control tubes are supplied with filament current from storage batteries or special low voltage D. C. generators, and the high voltage applied to the plates of the tubes is furnished by generators. This power will vary in most cases from about 1,000 to 5,000 volts. In some broadcasting stations, the power is obtained through high voltage direct current generators, while in others, the alternating current supply is stepped up or transformed through high voltage transformers and then rectified by means of special vacuum tubes.

The high frequency waves are applied to the antenna system tuned circuits and carefully modulated in accordance with the variations of the speech or music being transmitted. The action of the transmitter and the effect of the modulation must be carefully observed at all times during the transmission of programs. (See *Harmonic Suppressor*, also *Oscillograph.*) Fig. 2 shows the studio of a modern broadcasting station. It is interesting to note that these studios are very carefully arranged and the walls cushioned to prevent troublesome acoustic effects. There must be no reverberation—echoes—or the transmitted program would be distorted by the additional or repeated tones. Fig. 3 shows the main control panels. Fig. 4 illustrates the power generating system of a typical broadcasting station.

The radio waves generated and radiated from the broadcasting station travel away from the antenna at tremendous speed—that of light waves, or about 186,000 miles per second. These waves radiate off into space in


Fig. 2. Studio of a modern Radio Broadcast Station.


Fig. 3. Main control panels of a Radio Broadcast Station.


Photos by courtesy of Station WRNY (New York)

Fig. 4. A section of the generator room with power plant in a Radio Broadcast Station.

much the same manner as light waves, but a certain portion apparently follow the curvature of the earth. When these waves impinge on a receiving aerial they follow the path of least resistance, and being then in the nature of electrical impulses, they follow the aerial and lead-in wire to the receiving set, and thence to the ground. The receiver is arranged in such fashion that it corresponds electrically to the antenna circuit of the transmitting station. That is to say, the receiver is placed in resonance with the particular signals desired. The usual system of detecting, either with a simple crystal or by means of vacuum tubes, may be followed by special amplification which will make the signals audible on a loud speaker. In many cases the signals are amplified in their original form (radio frequency amplification), then rectified by the detector and further increased in volume at audio frequency. (See *Modulation*, *Speech Amplifier*, *Electromagnetic Waves*, *etc.*)

BROAD TUNING—A term used to designate the lack of *selectivity* in reception or in transmission, the use of several *waves* rather than a sharp, pure wave. If a receiving set is of such a nature that it is difficult or impossible to receive the desired signals without hearing any other, the set is said to be "broadly tuned." (See *Tuning*, also *Selective Tuning*.)

BROKEN CIRCUIT—See *Open Circuit*.

BROWN AMPLIFYING RELAY—An arrangement whereby the comparatively weak signals received by a *crystal detector*, usually of the *carborundum type*, may be *amplified* or increased in intensity, either to allow a recording machine to be used or merely to make the signals more readily audible in the ear phones. The device consists essentially of an arrangement for controlling and stepping up the vibrations in conjunction with a small *battery* or *dry cell*.

One example of such a relay is shown in the illustration. In this case the soft iron *cores* cc are *magnetized* by the *permanent magnets* mm, the poles of which are marked n and s. R1 is a fine wire winding such as is ordinarily used in ear phones and R2 is a larger winding placed over the main magnets mm. Directly above the soft core cc with the windings R1 is placed a steel vibrating tongue V having a contact D which touches lightly contact G. Contact G is of a special alloy of osmium and iridium and the contact D is a carbon button, which in contact with G forms a *microphone*. The winding R2 is joined with the telephone P and the battery B, all in series with the microphonic contact. When current (signal current) enters the leads A—E through the windings R1 the result is a change of *flux* in the core of the magnet which vibrates the tongue V. This in turn varies the current of the battery B and causes correspondingly greater sounds in the ear phones P. Several of these relays may be connected together to permit a much greater *amplification* of the original signals.



The Brown Amplifying Relay Circuit.

BROWN & SHARPE GAUGE—The American wire gauge adopted as standard for wires for electrical purposes. Commonly known as B. & S. The various sizes run from 40 to 0000, 40 having a diameter of .00314 inch, and 0000 being .46 inches in diameter. We refer to wire having a diameter of .00314 inch as being 40 B. & S. gauge. (*See page 26 for table.*)

BROWN, Sidney George—Born in Chicago, U. S. A., in 1873, of English parents, he was educated at Harrogate and London University. An early study was made by him of the subject of submarine telegraphy. During these investigations he invented the magnifying relay for cables. Another important invention was the cable drum relay. In the year 1898 he invented the magnetic shunt. Since that time many of his activities have been directed to the solution of problems in telephone and wireless telegraphy.

In particular the radio experimenter will know the telephone receivers bearing his name and the important developments of the *microphone relay*. In the field of land telegraphy and telephony, his activities have resulted in the invention of such items as the carbon telephone relay system, which is largely used on land trunk lines for the transmission and reception of telephony.

He is a Fellow of the Royal Society and Vice-President of the Radio Society of Great Britain. His writings on technical subjects are extensive, and numerous valuable patents have been taken out by him, including the vacuum tube *oscillation generator* in 1916 and ionic electric relays in 1918.

BRUSH—A device for collecting current from the *commutator* (*q.v.*) of a *dynamo* or supplying current to the commutator of a motor. Brushes are made in a great variety of forms, the most common being carbon blocks or brass or copper gauze. The illustration shows two different types.



Two different types of Brushes. At the left is shown a carbon brush, and at the right a copper gauze brush.

BRUSH ANGLE—The angle formed by a brush in its contact with the *commutator*. The angle is usually 45°. If the brushes do not bed properly, sparking is apt to occur.

BRUSH DISCHARGE—A faintly luminous discharge which takes place on the surface of *conductors* charged to *high potential*, due to *ionization*. This effect can be noted at times on the *antenna* of a powerful transmitting station. (See *Corona*.)

BRUSH HOLDER—Metal clamp capable of adjustment which holds the *brush* in position on the *commutator* of a dynamo or motor. (See *Brush*.)

BRUSH LOSS—The loss in *watts* or power due to the friction of the brushes against the *commutator*. This loss is at a minimum when the brushes make perfect contact at the proper angle.

BRUSH PRESSURE—A term used to designate the pressure with which the brushes bear on the *commutator* of a dynamo machine and also referring to the voltage or *electrical pressure* delivered at the brushes.

B. S. G.—Abbreviation for British Standard Gauge of Wire, commonly known as B. S. (See *British Standard Wire Gauge*.)

B. T. U.—Abbreviation for "British Thermal Unit," being the commonly used heat unit. The amount of heat required to raise the temperature of a pound of water one degree Fahrenheit at ordinary atmospheric pressure.

BUCHER, Elmer E.—Born Akron, Ohio, Nov. 11, 1885. Educated at high school and private tutors. An American pioneer, Experimental Engineer with De-Forest Wireless Telegraph Company in 1903; constructed several high power stations in Middle West and Gulf Coast and later for United Wireless, which absorbed the Deforest Company. Organized training school for United Wireless and instituted first radio schools for Y. M. C. A. in New York City. Supervised commercial operations and conducted research work for United Wireless; later instructing engineer Marconi Wireless Tel. Co. Technical Editor "Wireless Age" 1913 to 1917. Appointed Commercial Engineer for newly formed Radio Corporation of America in 1920, and since 1922 has been in charge of general sales for that corporation. Author of numerous standard works on radio, including "Practical Wireless Telegraphy," "Wireless Experimenters' Manual," "Vacuum Tubes in Wireless Communication," and many others. Holds numerous U. S. patents on radio systems and devices.

BUCKLED DIAPHRAGM—Warping of the *diaphragm* of a phone as used in radio. Excessive voltages if applied direct to the head-phones will often bend the diaphragms. Any such defect may seriously impair the operation of the part and when it is noted that a diaphragm is bent or warped through rough usage or the application of too great voltages, it is best to replace it immediately.

BUCKLING OF PLATES—During discharge of a *storage battery* the plates gradually expand, owing to the fact that lead sulphate has about twice the volume of the same quantity of lead peroxide. Should this expansion or discharge take place too quickly, the plates will bend or buckle. (See *Storage Battery*.)

BUNSEN BURNER—A form of gas burner frequently used in radio construction for heating the soldering iron where electricity is not available. By special arrangement of the parts, the gas is combined with the proper amount of air before it reaches the burning part. This is done by driving the gas through a tube with small holes drilled to allow the air to be sucked in. This method promotes complete combustion and gives a non-luminous flame that heats the soldering iron without

THE BROWN & SHARPE (B. & S.) COPPER WIRE GAUGE—Below is a comprehensive copper wire table, which is the standard one in use in the United States. The resistance and cross-sectional areas of various sizes of conductors are given, so that considerable calculating can be done with the data at hand. A mil means 1-1000 (one thousandth) of an inch. Hence a wire with a diameter of 9 thousandths of an inch could also be stated as having a diameter of 9 mils. The area of cross-section of the wire in circular mils is found by squaring the diameter in mils; thus the 9 mil conductor would have 9 times 9, or 81 circular mils area. This is the end area of the wire, of course, and is used in all electrical figuring. If the resistance per 1,000 feet of a certain size wire is, say, 50 ohms, then 500 feet of the same size wire would have a proportionately less amount of resistance, or ½ of 50 ohms, that is, 25 ohms. The resistance per foot is found by dividing the resistance in ohms per 1,000 feet by 1,000. This wire table is for bare copper wire. Conductors, according to the B. & S. standard gauge, halve their sectional area in circular mils (Cir. Mils) for every 3 gauge sizes smaller wire; and double their sectional area in Cir. Mils for every 3 gauge sizes increase.

Gauge Number.	SIZE.		WEIGHT AND LENGTH.			RESISTANCE.			Carrying Capacity, 2,000 Amperes p. sq. in. section.
	Diameter in Mils.	Square of Diameter or circular Mils.	Grains per Foot.	Pounds per 1000 Feet.	Feet per Pound.	Ohms per 1000X Feet.	Feet per Ohm.	Ohms per Pound.	Amperes.
0000	460.000	211600.0	4477.2	639.60	1.564	.051	19929.7	.0000785	430
000	409.640	167804.9	3550.5	507.22	1.971	.063	15804.9	.000125	262
00	364.800	133079.0	2815.8	402.25	2.486	.080	12534.2	.000198	208
0	324.950	105592.5	2236.2	319.17	3.133	.101	9945.3	.000815	165
1	289.300	83694.49	1770.9	252.98	3.952	.127	7882.8	.000501	130
2	257.630	66373.22	1404.4	200.63	4.994	.160	6251.4	.000799	103
3	229.420	52633.53	1113.6	159.09	6.285	.202	4957.3	.001268	81
4	204.310	41742.57	883.2	126.17	7.925	.254	3931.6	.002016	65
5	181.940	33102.16	700.4	100.05	9.995	.321	3117.8	.003206	52
6	162.020	26250.48	555.4	79.34	12.604	.404	2472.4	.005098	41
7	144.280	20816.72	440.4	62.92	15.893	.509	1960.6	.008106	32
8	128.490	16509.68	349.3	49.90	20.040	.643	1555.0	.01289	26
9	114.430	13094.22	277.1	39.58	25.265	.811	1233.3	.02048	20
10	101.390	10381.57	219.7	31.38	31.867	1.023	977.8	.03259	16
11	90.742	8234.11	174.2	24.89	40.176	1.289	775.5	.05181	13
12	80.808	6529.93	138.2	19.74	50.659	1.626	615.02	.08237	10.2
13	71.961	5178.39	109.6	15.65	63.898	2.048	488.25	.13087	8.1
14	64.084	4106.75	86.87	12.41	80.580	2.585	386.80	.20830	6.4
15	57.068	3256.76	68.88	9.84	101.626	3.177	306.74	.33133	5.1
16	50.820	2582.67	54.67	7.81	128.041	4.582	243.25	.52638	4.0
17	45.257	2048.19	43.33	6.19	161.551	5.183	192.91	.83744	3.2
18	40.303	1624.33	34.37	4.91	203.666	6.536	152.99	1.3312	2.5
19	35.390	1252.45	26.50	3.786	264.136	8.477	117.96	2.2392	1.96
20	31.961	1021.51	21.60	3.086	324.045	10.394	96.21	3.3438	1.60
21	28.462	810.09	17.14	2.448	408.497	13.106	76.30	5.3539	1.28
22	25.347	642.47	13.59	1.942	514.933	16.525	60.51	8.5099	1.08
23	22.571	509.45	10.77	1.539	649.773	20.842	47.98	13.334	.80
24	20.100	404.01	8.55	1.221	819.001	26.284	38.05	21.524	.63
25	17.900	320.41	6.77	.967	1044.126	33.135	30.18	34.298	.50
26	15.940	254.08	5.38	.768	1302.083	41.789	23.93	54.410	.40
27	14.195	201.49	4.26	.608	1644.737	52.687	18.98	86.657	.31
28	12.641	159.79	3.39	.484	2066.116	66.445	15.05	137.283	.25
29	11.257	126.72	2.69	.384	2604.167	83.752	11.94	218.104	.20
30	10.025	100.50	2.11	.302	3311.258	105.641	9.466	349.805	.16
31	8.928	79.71	1.67	.239	4184.100	133.191	7.508	557.286	.13
32	7.950	63.20	1.33	.190	5263.158	168.011	5.952	884.267	.098
33	7.080	50.13	1.06	.151	6622.517	211.820	4.721	1402.78	.078
34	6.304	39.74	.847	.121	8264.463	267.165	3.743	2207.98	.062
35	5.614	31.52	.658	.094	10638.30	336.81	2.969	3583.12	.049
36	5.000	25.00	.525	.075	13333.33	424.65	2.355	5661.71	.039
37	4.453	19.83	.420	.060	16666.66	535.33	1.868	8922.20	.031
38	3.965	15.72	.315	.045	22222.22	675.22	1.481	15000.5	.025
39	3.531	12.47	.266	.038	26315.79	851.789	1.174	22415.5	.020
40	3.144	9.88	.210	.030	33333.33	1074.11	.931	35803.8	.015

depositing soot as in the case of an ordinary luminous flame.

BURSTYN, Dr. W.—Born in Austria, 1877. Educated at Vienna University. Noted as: Developer of the *quenched spark system* in radio transmission, upon which he worked in conjunction with Baron Lepel in 1907 to 1912.

BUS BAR—A single bar, usually copper, which serves as a common connector for a number of pieces of apparatus. Also referred to as Omnibus Bar.

BUS BAR WIRE—Square copper wire, usually tinned, much used in making radio connections. This wire is generally furnished in lengths of two or two and a half feet and is particularly efficient for radio work, as it offers a low *resistance* connection, makes a neat appearance, and is suitable for soldering at joints.

BUSHING — Pieces of insulating material, usually fibre or rubber composition, used to *insulate* parts of radio apparatus or in mounting machine screws or shafts of *condensers* and other devices. The term is also applied to brass or other metal bearings through which the shaft of a piece of apparatus is run.

BUTT JOINT—A method joining two lengths of wire together by placing them end to end or at right angles and soldering the joint. The illustration shows a common butt joint.



Showing how a Butt Joint is made.

BUZZER—An electric call signal device that makes a buzzing noise caused by the rapid vibrations of a contact breaker in a circuit using a small *battery* or *cell.* (See *Testing Circuit.*)



Diagram of a Buzzer circuit.

As the *current* flows from the posts A B the *electro-magnets* C and D are energized and draw down the vibrator spring F. This breaks the contact between E and F and as the current no longer flows the magnets release the spring F, which returns to its normal position and establishes the circuit once more. This making and breaking of the circuit takes place so rapidly that the vibrator makes a buzzing or humming sound, the speed with which it vibrates determining the pitch of the note. (See *Frequency*, also *vibration.*)

BUZZER EXCITER—A method of using a *buzzer* to produce local signals in a crystal receiving circuit to permit sensitive adjustment of the *detector.* The illustration shows a common method of producing signals to test the receiving set in this manner. In this case a small coil having a few turns of wire is placed in the buzzer circuit as indicated and a similar one is placed in the ground lead of the receiving set. When the button is depressed the buzzer is set in vibration and a transfer of energy takes place between L1 and L2. This causes an *oscillating* impulse (*q.v.*) to flow through the receiver circuit. The detector can then be adjusted to the most sensitive point at which it can be left until outside signals are heard. Another but less efficient method of exciting the circuit is to connect a short length of wire from the contact point of the buzzer to the ground connection of the receiving set. The former system is much more practical and furnishes better test signals.



Buzzer Exciter.

Coil L1 being placed in *inductive relation* to coil L2, which is in the antenna circuit, undergoes a change of *flux* when the buzzer is *excited.* This sets up a *difference of potential* across coil L2 which charges the antenna ground system and produces oscillation at a definite *frequency* according to the adjustment. Now if the secondary circuit is tuned to resonance with the primary circuit, the signals will be audible in the phones when the detector is properly adjusted. Also called *Buzzer Wave Generator.*

BUZZER MODULATION—See *Modulation.*

BUZZER PRACTICE SET—A combination of a *buzzer* and signalling key arranged on a baseboard used for the purpose of practicing signalling.

B. W. G.—The abbreviation for Birmingham Wire Gauge—a system of gauging wire used in England. (See *B & S Gauge*, also *British Standard Wire Gauge.*)

BY-PASS CONDENSER — See *Condenser*, also *Filter.*

C

C—The chemical symbol for carbon. When printed in *italics*, it is also the symbol for *coulomb* in electrical practice. It is the international symbol for *capacity.*

CABLE—A number of wires stranded together, used to carry electrical currents, heavily insulated and often covered by a sheath or outer coating of lead, rubber, gutta percha, or braided silk or cotton. The term is used very often in a broad sense to signify any heavy wire or strand of wires that may be insulated more thoroughly than is ordinarily the case. (See *Conductor*, *Stranded Wire*, etc.)

CADMIUM—A chemical metallic element somewhat resembling zinc. In color, white with a bluish tinge. It is useful in fusible alloys because of its property for uniting readily with other metals, having a low melting point. Its electrical conductivity is about 25% of that of silver. It is very useful in the construction of a crystal detector, the molten metal holding the crystal firmly and as it melts at a low temperature the heat will not affect the sensitivity of the crystal. Cadmium is also used in making cells, notably the *Weston Cell.* (See *Weston Cell.*)

CAGE ANTENNA—An aerial having a number of wires arranged in cylindrical form, suspended either vertically or as a horizontal top. So named because of its resemblance to a cage. (See *Aerial.*)

CALCULATION OF CAPACITY—The mathematical or comparative determination of *capacity.* There are various formulas in use for calculating capacity under various conditions, such as for capacity of various types of condensers, or the capacity of a circuit. Rough approximations of capacity of condensers might be obtained by direct comparison with a known value. Other formulas are used for the calculation of antenna capacity. For determining the capacity of flat condensers, such as fixed condensers used for transmitting or receiving circuits, the following formula is generally used:

$$C = 0.0885\,K\,\frac{S}{r}$$

In this case, C is the capacity in micro-micro farads; to obtain result in the usual units of micro-farads, divide the result by one million. S is the surface area of one plate in square centimeters; r is the thickness of the dielectric in centimeters and K a constant depending on the material between the plates of the condenser. (See *Dielectric Constants.*)

CAL-ELECTRICITY — Electricity produced in the secondary of a transformer due to changes in temperature of the core. This current is in addition to the current normally induced in the secondary. (See *Transformer*, *Core*, also *Core Losses.*)

CALIBRATION — A process whereby instruments such as *galvanometers* ammeters, *wavemeters*, etc., are made to indicate certain values. Before such



Fig. 1. Fig. 2.
Calibrating a Meter

instruments can be made use of, it is necessary to mark the dials in such a manner that the indicator showing on the dial or scale will have a definite meaning in terms of electrical values. Thus, a voltmeter before calibration is shown in Fig. 1. When it is placed across a battery, the pointer will move to some position on the white space, but without indicating any definite value. Now by testing with another meter which is already marked or calibrated in volts, we find, for example, that when the pointer is at the middle point in its swing, it indicates 10 volts. Similarly various other positions are found to indicate more or less voltage by comparison with the standard. This is shown in Fig. 2. It will be understood that one of the small switches must be open at all times. The reading of the calibrated meter is taken with the other meter out of the circuit (switch open), then the reading is marked on the other meter at the point indicated with the calibrated meter out of the circuit. Such a method would, of course, be inefficient and it is shown only to give a rough idea of the purpose and meaning of calibration. Another example of calibration is in the case of a dial on a receiver. Fig. 3 shows the usual form of dial used in tuning a receiving set. The dial is marked off to scale, from 1 to 100, the numbers having no particular significance. Now if we find that when the tuning dial is set at 20 it is adjusted for a wavelength of 260 meters, we can put that figure in place of the 20. The same procedure can be followed throughout the entire range of the dial, and when thus marked in terms of a definite quantity—wavelength in meters in this case—the dial is said to be calibrated.



Fig. 3.

A dial as used on radio receiving sets may be Calibrated according to different wavelengths.

The actual method to be followed out in calibrating will depend on the equipment available and the accuracy desired. If a standard of comparison is available, it saves a great deal of work. Thus, a voltmeter can easily be calibrated by means of a standard meter, already calibrated, and a source of steady voltage controlled by a rheostat. An ammeter can be calibrated in the same manner by using a standard ammeter, and a wavemeter can be calibrated from another wavemeter of known values.

Calibration may be done in such a manner that the readings require mathematical solution to determine their value in terms of actual volts, amperes, meters and so on, or it may be *absolute*, in which case the readings are directly in terms of the quantity and require no solution. (See *Voltmeter Calibration, Wavemeter Calibration*, also *Rough Calibration.*)

CALIDO—An alloy containing nickel and chromium with a small percentage of iron. The melting point is very high, about 1550 degrees centigrade. Calido wire is much used as a *resistance*, particularly for heating devices. The chief characteristics are as follows: maximum working temperature 1100 degrees centigrade; microhms per cubic centimeter at 20 degrees centigrade, 100; temperature coefficient per degree centigrade, 0.00034; specific gravity, 8.2.

CALLAND CELL—A primary cell used in French telegraph work. It is a form of gravity cell having a negative electrode of copper and a positive electrode of amalgamated zinc, the electrolyte being zinc sulphate. Crystals of copper sulphate are used as a depolarizer. (See *Gravity Battery.*)

CALORIE—The unit of heat in the C. G. S. (Centimeter-Gram-Second) (q.v.) system. It is equivalent to the amount of heat necessary to raise the temperature of one gram of water from 0° to 1° centigrade. (See *Thermal*, also *C. G. S.*)

CALORIMETER—In electrical practice, an instrument used to measure the heat generated in a conductor carrying an electric current.

CAMBRIC, VARNISHED—Varnished muslin used as an insulating material. Also known as Empire Cloth. (See *Spaghetti.*)

CANAL RAYS—When an electric discharge takes place between the *anode* and a perforated *cathode* in a vacuum tube, fine pencils of light are seen to pass through the perforations in the cathode. These rays are called *canal rays*, and consist of positively charged particles. They produce phosphorescence on the wall of the tube.

Canal rays travel at a lesser velocity and in the opposite direction to the cathode rays. This fact and also the fact that the rays are deflected by powerful electric or magnetic fields in the opposite direction to cathode rays, is taken as proof that they consist of positively charged particles. (See *Cathode Rays.*)

CAPACITANCE—A term very often used as synonymous with *capacity*. Due to the fact that capacity may refer to the current carrying ability of a conductor and also to electrostatic capacity, it has been suggested that capacitance be used to refer only to *electrostatic capacity* of a body or device. Capacity would then refer to *current carrying ability*. (See *Capacity*, also *Electrostatic.*)

CAPACITATIVE REACTANCE—That part of the *reactance* of a circuit carrying alternating current which is due to the *capacity* in the circuit. (See *Reactance* also *Impedance.*)

CAPACITATIVE COUPLING — See *Coupling.*

CAPACITY—Generally speaking, the quantity of electricity in any form which a body is able to store or contain. The term is usually qualified to denote the particular case, such as *electrostatic capacity*, which is a measure of the ability of a condenser to store up energy in the form of electrostatic charges; also *current-carrying capacity* of a conductor, which is considered as the ability of a wire to carry a certain amount of electric current without overheating. The tendency in electrical literature is to use the term capacitance as applying to the electrostatic capacity of a condenser. Thus, a certain condenser may have a capacitance of 2 micro-farads. The unit of electrostatic capacity is the *farad*. This is understood as the capacity of a condenser that will store one *coulomb* of electricty under an electromotive force of one *volt.* When V is expressed in volts, C in farads, and Q in coulombs, $C = Q/V$.

CAPACITY CIRCUIT—An electrical circuit in which the *capacity* is very large compared with the *inductance*. The inductance may be considered negligible.

CAPACITY CONVERSION FACTORS—In the calculation of *capacity*, as the capacity of a condenser, there are several different units. For instance, a *farad* is a large unit of capacity and is equal to one million *microfarads*, or conversely, a microfarad is equal to one millionth of a farad. In the same way a farad is equal to one billionth of an *abfarad*. The four units used in capacity measurement are the *farad*, *micro-farad*, *micromicrofarad*, *statfarad* and *abfarad*. The following table gives the conversion factors for these various units:

$$1 \text{ abfarad} = \begin{cases} 10^{9} \text{ farads} \\ 10^{15} \text{ mfds.} \\ 9 \times 10^{20} \text{ stfds.} \end{cases}$$

$$1 \text{ farad} = \begin{cases} 10^{-9} \text{ abfd.} \\ 10^{6} \text{ mfds.} \\ 9 \times 10^{11} \text{ stfds.} \end{cases}$$

$$1 \text{ mfd.} = \begin{cases} 10^{-15} \text{ abfd.} \\ 10^{-6} \text{ farads} \\ 9 \times 10^{5} \text{ stfds.} \end{cases}$$

$$1 \text{ stfd.} = \begin{cases} 1/9 \times 10^{-20} \text{ abfd.} \\ 1/9 \times 10^{-11} \text{ farad} \\ 1/9 \times 10^{-5} \text{ mfd.} \end{cases}$$

$$1 \text{ mmfd.} = 10^{-6} \text{ mfd.}$$

In the table above, farad is abbreviated Fd.; abfarad is shown as abfd.; microfarad is mfd., micromicrofarad is mmfd. and statfarad is stfd. In dealing with large figures containing many ciphers the amount is shown as 1,000,000 is 10^6 and $\frac{1}{1{,}000{,}000}$ is 10^{-6}, etc. (See *Capacity, Farad*, also *Unit.*)

CAPACITY EARTH or CAPACITY GROUND—A substitute for the usual ground connection where the wires or plates are buried beneath the ground or attached to a water or steam pipe. It is in effect a second aerial, and is placed either under the regular aerial or to one side. It is more used in radio transmission than in reception. (See *Counterpoise.*)

CAPACITY ELECTROSTATIC — See *Capacity* also *Electrostatic Capacity.*

CAPACITY FREQUENCY FACTOR—The relation between the apparent capacity of a condenser and the *electrostatic capacity*. (See *Capacity, Condenser* also *Electrostatic.*)

CAPACITY OF CONDENSERS IN PARALLEL—When several condensers are connected in parallel the resultant capacity is the sum of the individual capacities. It is written:

$$\text{Capacity} = C_1 + C_2 + C_3, \text{etc.}$$

It will be evident that the resultant capacity of condensers connected in parallel is just the reverse of case for resistances, where the total resistance is less than that of the smallest individual resistance in the parallel connection. (See *Resistance Measurement* also *Capacity of Condenser in Series*, also *Condensers in Series* and *Condensers in Parallel.*)

CAPACITY OF CONDENSERS IN SERIES—When several condensers are connected in series with each other the resultant capacity is always less than the capacity of the smallest condenser in the group. The capacity of condensers in series is given as follows:

$$\text{Capacity} = \cfrac{1}{\cfrac{1}{C_1} + \cfrac{1}{C_2} + \cfrac{1}{C_3}, \text{ etc.}}$$

The resultant capacity is thus the reciprocal of the sum of the reciprocals of the several capacities. (See *Condenser, In Series.*)

CAPACITY MEASUREMENT OF ANTENNA—A simple method for the measurement of the capacity of an antenna as given by Austin follows: The illustrations show the general arrangement. The inductance L in Fig. A is a coil that will increase the wavelength (natural) of the antenna system 4 or 5 times; C is a calibrated variable condenser and W a standard wavemeter. In operation the coil L is connected in the antenna circuit, the buzzer is used to excite the antenna circuit and the wavelength is measured by w. The coil L is then taken out of the antenna circuit and shunted by the condenser C. The condenser C is then varied until the wavelength of the combined coil L and condenser C is the same as that obtained before with the coil in the antenna circuit but without the variable condenser. The capacity of the condenser now will be approximately that of the antenna, ignoring the distributed inductance of the antenna system. Fig. A shows the first operation, the measurement of the antenna with the coil in the circuit, and Fig. B shows the measurement of the wavelength of the coil and condenser. (See *Mutual Capacity, Wavemeter, Natural Wavelength,* also *Distributed Capacity.*)



FIG. A

The first operation in the measurement of the antenna. The wavemeter is shown below.



FIG. B

Circuit for the measurement of wavelength of coil and condenser.

CAPACITY MUTUAL—See *Mutual Capacity.*

CAPACITY RESISTANCE—The resistance to alternating currents offered by a body possessing electric capacity. (See *Capacity,* also *Resistance.*)

CAPACITY SWITCH—Any switch used in a circuit to introduce or cut out capacity (condenser).

CAPACITY (UNIT OF)—The unit of capacity is the farad. A condenser has a capacity of 1 farad when 1 coulomb is required to raise its potential from zero to 1 volt. Since the farad is very large, its millionth part, or the microfarad is generally used.

CARBON—A non-metallic chemical element used for many purposes in electricity and radio. It exists in three forms, two crystalline and one non-crystalline. The first two are diamond and graphite, the third charcoal. Carbon is used as an electrode in electric arcs, as one of the poles in certain types of primary cells, as a material in place of wire for various forms of resistance, and as brushes in motors and generators. (See *Diaphragm, Carbon.*)

CARBON RHEOSTAT—A rheostat or variable resistance using carbon in place of the customary wire. In its simplest form a carbon rheostat may be merely a piece of carbon having a sliding contact. This is shown in Fig. 1. Owing to the relatively high resistance of carbon used in this manner, such a controlling resistance will generally be termed a *potentiometer* (q.v.) and used as such.

The most practical form of a carbon rheostat is known as a carbon pile rheostat. This type uses a number of flat pieces of carbon of relatively low resistance placed together and arranged with a knob and screw in such manner that the pressure can be varied. This change in pressure alters the resistance of the mass and allows control of the current for vacuum tubes. The same principle is used for very high resistances as well as for low values. The principle will be seen from the illustration Fig. 2.



Fig. 1.—A carbon rheostat with a rotary sliding contact.



Fig. 2.—A carbon pressure type rheostat.

CARBORUNDUM—An abrasive material, a product of the electric furnace, composed of silica and carbon. It is used in radio as a crystal rectifier, although the strides of radio have practically rendered it obsolete, many other better crystals being in use. The chief difficulty with its use as a rectifier or crystal detector was the fact that for efficient operation it required a cell or battery and potentiometer to regulate the current flowing through it. The simple crystal circuit using a carborundum detector is shown in the illustration. C is a tuning coil, D the carborundum crystal and contact, P a potentiometer and T the head phones. (See *Rectifier,* also *Detector.*)



Diagram of a radio circuit employing a carborundum crystal detector.

CARDBOARD TUBING—Tubing made of laminations of paper pasted together. They are used for home made coils of all descriptions, and while not as efficient as the composition tubing, can be used for many purposes without any great loss. As a general rule it is better to use some of the numerous compositions, such as bakelite or rubber compounds.

CARPENTIER, JULES—French radio expert. Born in Paris, in 1854, he joined the Ecole Polytechnique in 1871, and in 1876 was appointed principal stores engineer of the Lyons Railway Company, making a special study of electricity. For his work in electricity he obtained in 1881 the cross of Chevalier of the Legion of Honor. One of the early pioneers of radio in France, he founded the Compagnie Generale Radiotelegraphique, afterwards absorbed in the Compagnie Generale de Telegraphie sans Fil. Carpentier is a member of the Academie des Sciences, Commander of the Legion of Honor, and President of many scientific societies.

CARRIER WAVE—The *continuous wave* (q.v.) of radio frequency generally thought of as carrying the voice or music waves from the radio broadcasting station. Actually it is a radio wave of high frequency, which is altered in amplitude by the music or speech transmitted. In action, this continuous wave has another wave super-imposed on it. This other wave having wave form and amplitudes determined by the voice or other sounds being transmitted. The illustration shows the carrier wave, the waves representing speech or music and the combination of the two. This effect of varying the amplitude or strength of a continuous wave by means of some sort of program is known as *modulation.* (q.v.) The wave representing the speech or music is imposed on the carrier wave resulting in the combined wave which reaches the listener and is translated by suitable apparatus into approximately the same sounds that are transmitted. (See *Modulation, Broadcasting*, also *Speech Vibrations.*)

CARRYING CAPACITY—See *Current Carrying Capacity.*

CARTRIDGE FUSE—A fuse in which the fuse wire is surrounded by some non-inflammable substance, enclosed in a cartridge-like tube and having brass lugs soldered to caps at ends. Used to prevent the hot wire from "flying" when fused. (See *Fuse.*)

CASCADE—A term applied to pieces of apparatus connected together in series, particularly vacuum tubes. In this case, the arrangement would be such that each vacuum tube would amplify the signal output of the preceding tube. The tubes will be so connected that the output of one is introduced as input to the next and so on the total result being greatly increased signal strength from the output of the last tube. This term may apply to either radio frequency or audio frequency amplification. (See *Amplifier, Radio Frequency,* also *Audio Frequency.*) A simple cascade arrangement is shown in the illustration. Fig. 1 is a circuit with two stages of cascade radio frequency amplification, and Fig. 2 a circuit using two stages of audio frequency amplification with the usual detector tube in each case. A combination of both radio frequency and audio frequency stages of amplification might also be used, the term cascade amplification also applying here.



Fig. 1.—Circuit diagram showing two stages of cascade radio frequency amplification and detector.



Fig. 2.—Diagram of detector and two stage cascade audio frequency amplifier.

CATHION or CATION—The charged particles which appear at the cathode or move toward it through the electrolyte of an electrolytic cell. (See *Anode.*)

CATHODE or KATHODE—A *negative electrode.* The term is often applied to the filament of a vacuum tube to distinguish it from the anode or plate. (See *Cell, Electrolysis,* also *Anode.*)

CATHODE RAY TUBE—A vacuum tube having a high vacuum, that is from which practically all air has been exhausted, used in the production of cathode rays. These tubes in their modern form are used for many purposes in studying the nature and form of electric waves. The illustration shows one of the latest types of tube, known as the *Cathode Ray Oscillograph.* This tube is used for the following purposes: examination of the wave forms of various rectifiers, study of wave forms of different types of generators, study of vacuum tube characteristics, examination of the characteristics of X-ray and other types of tubes, examination of radio frequency waves modulated as in broadcasting, measurement of hysteresis and dielectric loss in various materials, study of phenomena in arcs and sparks, together with numerous other associated effects. The development of this tube is one of the marvels of science, enabling the research engineer to virtually see the electric wave, and to study exhaustively, electric phenomena otherwise invisible.



A cathode ray tube with socket.

The Western Electric modification of the Braun Cathode ray tube or oscillograph, is a three electrode glass tube about 30 centimeters (about twelve inches) long, in the form of a cylinder an inch and three-quarters wide, spreading out in conical shape, the tube being about three and a half inches wide at the top. The *cathode* is a filament coated with active oxides and arranged to emit the number of electrons required for the cathode rays, at a dull red heat. The *anode* or plate is a small platinum tube set very near the filament. Between the filament and the anodes is a small circular screen having a hole just a little smaller than the circular filament. A battery of several hundred volts is connected between the filament and plates with the positive terminal connected to the plate. The electrons emitted from the hot filament are controlled by this field in the same manner as in an ordinary vacuum tube. A small portion of these electrons pass completely through the tubular anode and constitute the *cathode* rays. These rays are passed between two pairs of deflecting plates set at right angles to each other, and fly against the large end of the tube. This end is covered with a fluorescent mixture which renders the rays visible. These rays are deflected in various ways. For example, if an alternating current is applied the visible spot on the screen will be drawn out into a line. (See *Electron, Vacuum Tube,* also *Wave Analysis.*)

CATHODE RAYS—The stream of electrons or electrical particles sent out from the *cathode* or filament of a vacuum tube. These rays are negatively charged. (See *Cathode, Electrons, Vacuum Tube* also *Oscillograph.*)

CAT-WHISKER—The fine wire used with certain crystal detectors to make contact with the crystal. Usually a springy metal such as phosphor bronze wire.

"C" BATTERY—One or more small cells having a voltage generally between 2 and 10 volts, used in the grid



Fig. 1.—A 4½ volt "C" battery. This type of battery has a common positive terminal and is tapped at negative terminals for 3 and 4½ volts.



Fig. 2.—A diagram showing how the "C" battery is connected in the audio frequency amplifier.

circuit of an amplifier tube for the purpose of impressing a negative potential on the grid of the tube. The method of connecting it in the circuit is shown in Fig. 2. Fig. 1 shows a typical 4½ volt "C" battery. (See also *Grid Bias* and *"C" Battery Curve.*)

"C" BATTERY CURVE—In order to show the effect of a "C" battery on the consumption of current from the "B" battery in an audio amplifier, a *curve* (q.v.) may be drawn as in the illustration. In this case the test was made with a type UV 201A tube used as a one stage *audio frequency amplifier* in



Test conducted on UV201A tube using single stage audio amplifier with conventional circuit.
Plate Voltage—Abscissae.
Plate Current in milliamperes—ordinates.
A—Consumption curve without "C" Battery.
B—Consumption curve with "C" Battery.
(Note: 1.5 ma. at 45v plate rising to 5.75 ma. at 90v plate without "C". With "C" Battery consumption maximum is 2¼ ma. at 90v.)

a conventional circuit. It is readily apparent on referring to the lines A and B that when the "C" battery is in use the consumption of current by the plate is much less than without it.

CELL—A cell is one of the four chief sources of electric energy. In a cell the energy is created by an *electro-chemical* process, using in its simple form two unlike metals immersed in a dilute acid or alkaline solution. In the illustration Fig. 1 the common form of electric cell is shown. C is a strip of *carbon* and Z a strip of *zinc*. These are placed in the jar in a conducting solution of sal ammoniac. If the exposed terminals from the carbon and zinc strips are connected together by a piece of wire, current will flow from one side of the cell to the other through the wire. The current flows from the carbon or *positive* pole to the *negative* or zinc pole through the wire, completing the circuit through the solution from zinc to carbon. (See *Current, Direction of Flow.*) The cell described is known as a *primary cell.*



Fig. 1.—Common form of electric cell.

In Fig. 2 a simple *storage cell* or *secondary cell* is shown. In this case there are two lead plates immersed in a dilute solution of sulphuric acid. A source of primary current (primary cell) may be connected to the secondary cell in the manner shown in Fig. 3 and after being connected for a certain length of time it will be found that the energy of the primary cell has been transferred to the secondary cell and stored in it. This process of placing electric charges in a secondary cell is known as *charging*, and the current stored up in it is known as the *charge*. Now, if the wire is connected from one terminal to the other it will be found that electric energy can be withdrawn in a similar manner to that of the primary cell. A secondary cell may contain several plates and several of these cells may be connected together to form a storage battery. (See *Storage Battery, Current, Production of,* also *Anode* and *Cathode.*)



Fig. 2.—Storage or secondary cell.


LEAD PLATES
PRIMARY CELL
C
+
Z
−
PEROXIDE OF LEAD THIS PLATE BECOMES THE POSITIVE POLE OF CELL

Fig. 3.—Primary cell connected to secondary or storage cell.

CELL, SECONDARY—When a *primary cell* is connected to a *storage* or *secondary cell*, the current from the primary cell flows into the secondary cell and in effect deposits energy in that cell. Then when the charging source (the primary cell) is withdrawn, the secondary cell can be used in practically the same manner as the primary cell. A wire connected from one terminal to the other will permit passage of current. The action of storing up energy in a storage cell is approximately as follows: When the charging current flows from plate to plate through the solution in the secondary or storage cell, the plate connected to the *positive* (+) *pole* (carbon or copper) of the primary cell, receives a brown coating of *peroxide of lead.* At the same time the other plate becomes spongy or porous. Now as one plate has received a coating while the other remains unchanged as far as its surface is concerned—it acts as a primary cell if the charging source is taken away and the two terminals connected. It now has all the essentials of an ordinary chemical cell. As long as the coating of peroxide of lead remains on the surface of one of the plates, the cell will be capable of delivering current.

When the coating has been worn off or eaten away the cell is said to be in a discharged condition. It will then be necessary to go through the same process of connecting a primary source to the terminals in order to again deposit peroxide of lead on one plate. It will therefore be evident that when the *storage cell* is charged, *current* is not actually stored in it, although in effect it has received potential energy. What has actually occurred is that the current supplied to the cell during the charging process has produced electrochemical changes, making the plates dissimilar and thus producing a difference of potential. (See *Current, Production of*). The *voltage* or *electromotive force* of primary cells varies from .06 to 1.5 volts according to the nature of the elements used and the grade of the *electrolyte* (q.v.). Secondary or *storage cells* of the lead plate type produce from 2.1 to 2.6 volts. (For more complete explanation of the theory and action of a secondary cell, see *Storage Battery.* See also *Electro Motive Force, Current* and *Voltage.*)

CELL, THEORY OF PRIMARY—It has been explained under the heading *Cell,* that a primary cell produces electrical energy by chemical action. More specifically the action of a simple cell is as follows: When the copper and zinc, or carbon and zinc placed in a cell are connected together by a conductor, (wire or other conducting object) the acid in the case of a sulphuric acid solution, attacks the surface of the zinc plate and forms a compound known as zinc sulphate. While this sulphate is being formed some of the hydrogen contained in the sulphuric acid is liberated in the form of bubbles which appear on the copper plate. Some of these bubbles escape into the surrounding air by rising to the surface of the solution, but others cling to the surface of the copper plate and gradually cover it with a film of hydrogen. It may be said here that the decomposition of the zinc plate in the acid solution furnishes the *electro-motive force* required to cause the flow of current between the plates, through the solution and through the conductor. Now, hydrogen is a non-conductor, and as the hydrogen gradually covers the copper plate, the surface of the plate in contact with the solution gradually decreases. The flow of *current* from zinc plate to copper plate in the solution is thus gradually diminished, until eventally we can imagine the copper plate as being entirely covered with hydrogen and no longer in contact with the solution. In addition to this insulating action of the hydrogen, it tends to set up a current within the cell in the opposite direction to the normal flow of current produced by the chemical action. A cell in this condition is said to be "polarized," and various means have been used to cut down or eliminate the *polarization effect.* The purpose of these various means is to prevent the hydrogen bubbles clinging to the surface of the copper plate, thus allowing them to escape to the top of the solution and thence into the surrounding air. (*See Polarization, Current, Voltage, also Storage Cells.*)

CENTIMETER—A measure of length in the metric system. It is one hundredth part of a meter, or approximately .3937 inch. It is used as the unit of length in the Centimeter Gram Second System (q.v.).

CENTIMETER GRAM SECOND or C. G. S. A system of units of measure employed in practically every branch of engineering, particularly in electrical practice. It is a decimal system, the centimeter being the unit of length, the gram the unit of weight and the second the unit of time. All other units are derived from these three. When the magnitude of a quantity is spoken of, it refers to the relative magnitude of the quantity when compared with some other quantity of the same nature. The magnitude used as a standard of comparison is termed a unit. Thus, if the length of a body is measured in feet, as for example, ten feet, it means that the magnitude of the body is ten times unity or ten times one foot. Similarly a *current* of ten *amperes,* is a current of magnitude ten times as great as the unit quantity—one ampere. Now an ampere is the practical unit of rate of flow of electric current. The unit has a certain definite value. (See Ampere.) The magnitude of any other similar quantity measured in amperes will mean a value equal to a certain number of units. In addition to the C. G. S. system of units, there is a practical system. This is commonly used for ordinary calculations. Under this system, the following are the main units: The *volt* is the practical unit of *electro-motive force;*—the force required to maintain a flow of current of one ampere through a resistance of one ohm. The unit of *current strength* or rate of flow of current is the *ampere;*—the strength of current maintained by a force of one volt through a resistance of one *ohm.* The unit of *resistance* is one *ohm,* and is the resistance of a *conductor* or *circuit* that will permit the passage of a current of one ampere under the force of one volt. The unit of *quantity* is the *coulomb,* which is the quantity of current flowing in a circuit when one ampere passes a given point during one second of time. The *watt* is the practical unit of *electrical power,* being the power of a current of one ampere flowing in a circuit under the pressure of one volt.

It will thus appear that the practical system is actually based on the C. G. S. system. Calculations of an involved nature necessarily make use of the C. G. S. system, and when multiples or sub-multiples are used they are expressed in Greek and Latin prefixes. For example, a million ohms is 10^6 ohms and is expressed as a *meg-ohm.* "Meg" being derived from *mega millian.* Similarly a millionth of an ampere is expressed as a *micro-ampere* or 10^{-6} AMPERE. The various units under the C. G. S. and practical systems are taken up in detail under the respective headings, as *JOULE. ERG, DYNE* and so forth. (See also *Inductance (Unit of); Capacity (Unit of); Electrostatic Units and Electromagnetic Units.*)

C. E. M. F.—The abbreviation for *counter electromotive force* (q.v.).

C. G. S. UNIT OF CURRENT—The absolute *electromagnetic unit of current.* It is the current which when passed through a conductor bent into a circle of one centimeter radius will attract or repel a unit magnetic pole placed at its center, with a force of one *dyne* (q.v.).

CERUSITE—A kind of mineral used as a rectifier in some types of *crystal detectors.* It is a carbonate of lead having a whitish-grey color. This mineral is not as good a rectifier as some of the others, but has the advantage of more uniform sensitivity over practically its entire surface. (See *Crystal Detectors.*)

CHALCOPYRITE—A crystal used in a *pericon detector,* which is composed of zincite and chalcopyrite in contact with each other. It is a combination detector suitable for use where it is subject to jarring, since it has nearly uniform characteristics over its entire surface. It works without the aid of an electric battery.

CHARACTERISTICS—A term broadly applied in electricity to refer to any distinguishing feature in electrical apparatus. In radio usage the term is generally applied to *vacuum tubes.* The characteristic of a tube is understood as the relation between the potential (voltage) at the *grid* (q.v.) and the resulting current obtained from the *plate.* (q.v.) It may also occasionally refer to other features of a tube, such as its current requirements or amplifying quality as distinct from the ratio of *grid voltage* to *plate current.* (See *Characteristic Curve, Vacuum Tube Characteristics;* also *Plate Current.*)

CHARACTERISTIC CURVE—A diagram showing graphically in the form of a curved line the relation of changing values. Thus, in the case of a *vacuum tube,* a change in the *grid* voltage produces certain changes in the *plate* current (q.v.) and these changes may be plotted as curves. The temperature of a wire carrying current increases with increase in the *current* passing through it, and this increase may be shown by a curve. (See *Vacuum Tube Characteristics.*)



Characteristic chart of vacuum tube grid and plate voltage.

CHARGE—The presence of electricity in a body. Is usually defined as an excess or deficit of *electrons* (q.v.) on an insulated body. In the case of a *condenser* (q.v.) after it has accumulated electrical energy it is said to be in a charged condition, or to have an *electro-static charge.* The charge in a *condenser* is measured in *coulombs.* (q.v.) A *storage battery* is said to contain a charge when it has been connected to a source of direct current for a length of time, and the hydrometer test shows the electrolyte at proper specific gravity.

CHARGE, SPACE—See *Vacuum Tubes,* also *Space Charge.*

CHARGED BODY—Any body that has accumulated electrical energy. (See *Charge.*)

CHARGER, STORAGE BATTERY—Any means of controlling the current delivered from a primary source for the purpose of charging *storage batteries* or other *secondary cells.* Chargers are made in many forms and are designed for either direct or alternating current. Direct current chargers consist of certain resistances, with the necessary meters and switches. A simple form of direct current charger is shown in the illustration. In constructing a direct current charger there are several important details that must be



Charging storage battery from direct current source.

taken into consideration. The plates of a storage battery require certain charging rates in amperes, depending on the size and number of the plates. That is to say, the manufacturer specifies that when charging, a certain number of amperes must be passed to the battery from the charging source for a definite number of hours. This figure may be decreased but not increased. As an example, some storage batteries will take a charge of five amperes without injury to the plates, which rate would be ruinous for other batteries. Now the question of obtaining the proper amount of charging current arises. The majority of house lighting systems have a voltage of from 110 to 125 volts. (Reference is now made only to direct current systems, alternating current chargers being taken up later on.) According to *Ohm's Law* (q.v.) the current flowing in a circuit is directly proportional to the *voltage* and inversely proportional to the *resistance*. Voltage is the product of resistance times the current, the resistance in ohms and the current in amperes. Therefore if we desire a current of five amperes from a source of 110 volts, it is necessary to have a resistance of a value in ohms which, when multiplied by the current in amperes,—five in this case—will produce 110. Conversely, we can divide the voltage—110 by the current—5 to obtain the correct resistance. This would indicate a resistance of 22 ohms. There is another factor which enters into the problem however, the back pressure, or Counter Electromotive Force exerted on the charging source by the battery. In the case of a six volt storage battery, this will be six volts. This must be subtracted from the voltage of the charging source to obtain the effective value. Thus, the effective value in this case would be 110 — 6 or 104 volts. Then as explained before, dividing the voltage by the current required, we find that it is 104 ÷ 5 or approximately 21 ohms. Then by placing a resistance of 21 ohms in the circuit, as shown in the illustration, and connecting the battery as indicated, a charge of five amperes can be applied to the battery. The same result can be obtained by placing an ordinary electric lamp in series in place of the resistance. (See *Lamp Bank.*) The *internal resistance* of the battery is very small compared to that of the line resistance, and can be ignored. A point to remember is that the voltage of the charging source must always be higher than that of the storage battery, because, as explained above, the back or *counter electromotive force* of the battery, must be subtracted from the voltage of the charging source to indicate the effective voltage. Thus, if the battery exerts a counter electromotive force of six volts and the charging source is only six volts the counter force would be equal to the charging force and there would be no charging current. When *direct current* is not available and *alternating current* is used to charge the battery, it will be necessary to change it to direct current. For this purpose it is essential that some form of *rectifier* be used. This rectifier may be of a chemical, mechanical or electrical type. These various forms will be taken up under their separate headings. (See *Rectifier, Balkite, Tungar, Rectigon, Electrolytic Rectifier, Tube Rectifier.*)

CHARGING—The act of expending electrical energy to place a charge in or on a battery or body. The term is used generally to indicate the process of impressing electrical energy on the *storage battery* elements for the purpose of making the battery a secondary source of electricty. (See *Charger, Chemical Rectifier* also *Tube Rectifier.*)

CHARGING BOARD—A term used synonymously with *charging panel* to denote an arrangement for controlling the current used for charging *storage batteries*. It generally consists of an insulated panel with various *switches, fuses* and *resistances* thereon to limit the amount of current delivered, and at the same time furnish a ready means of connecting and disconnecting the various circuits connected through it. The fuses act as safety devices and break the circuit when too great a current is delivered. (See *Fuse, Switch, Charger.*)

CHEMICAL RECTIFIER—Device for changing alternating current to direct current. (*See Electrolytic Rectifier.*)

CHLORIDE BATTERY A type of storage battery for heavy duty operation. The positive plate is made of lead with a number of holes pierced in it and each filled with a coil of pure lead. This coil is forced into the holes during manufacture and is said to enable the battery to withstand heavy discharge without damage to the plates. (See *Storage Battery.*)

CHLORIDE CELL—A cell (q.v.) which uses in most cases, a positive plate having lead as the active material, the negative plate being made of metallic zinc. A solution of chloride of zinc is used, from which the name is derived. (See *Chloride Battery.*)

CHOKE OR CHOKING—The action of a device in a circuit wherein it tends to choke, or hold back, certain forms of current or certain *frequencies* while permitting others to pass freely, or to oppose fluctuations in the strength of the current passing through it in the circuit.

CHOKE COIL—A coil of wire possessing considerable *self-inductance* and relatively little *resistance*. These coils are used in various ways and for a variety of purposes. When connected in a direct current circuit, and possessing the proper value, they have a tendency to prevent any fluctuations in the current and thus keep the current smooth. An example of its use is with a *loudspeaker*. A *condenser* will permit passage of *high frequency (alternating) currents* such as we find in radio reception, but will effectively block direct currents. On the other hand a choke coil will pass direct current without offering any appreciable resistance, but will retard the *modulated currents* (q.v.) It will be apparent then that by a proper combination of the two (Choke Coil and Condenser) as in the illustration, the direct currents can be shunted around the loud speaker and thus prevent injury to it, while the necessary modulated currents are allowed to pass through without difficulty. Another use for the Choke is in a circuit carrying alternating currents. In this case the choke will limit the current in the circuit without loss, whereas an ordinary resistance, while it would limit the current, would dissipate a certain amount of energy. Chokes may be made with iron cores of the open or closed type, for *low frequency currents*, or may only have air for the core when used in *high frequency* circuits. The closed core type is the more common form. The formula most commonly used in determining the inductance of a choke coil in *henries* is as follows:

$$L = \frac{1.257 \times \mu \times A \times N^2 \times 10^{-8}}{l}$$

Where L is the inductance in henries.
μ is the permeability. (This varies from about 1000 to 2000 in most cases).
A is the effective area of iron cross section (square centimeters).
N is the number of turns of wire.
l is the length of iron path (in centimeters).



Method of using choke coil in connection with loud speaker.

CHOKE, HIGH FREQUENCY — A choke coil of high *self-inductance* (q.v.) used in transmitting circuits to prevent puncture of the secondary windings of the *transformer* (q.v.). When the condensers in a transmitting circuit are charged or discharged, a back pressure is exerted on the windings of the transformer supplying the high voltage. The illustration shows the position of these choke coils in the transmitting circuit. (See *Back Oscillation.*)



Position of choke coils in transmitting circuit.

CHOPPER—A device used in the aerial circuit of a *continuous wave* (q.v.) transmitter to break up the continuous trains of waves into separate groups and thus permit them to become audible. In the case of reception of ordinary *damped waves* (q.v.) the head phone produces signals that have a frequency of vibration equal to the number of wave trains per second. When the transmitted waves are con-



Showing how chopper is used to interrupt signals from continuous wave transmitter.

tinuous there is obviously no interval, that is, there are no groups of waves and they are therefore inaudible in the usual receiving apparatus. The *chopper* is only necessary when *crystal detectors* are used for reception. (See *Ticker, Beat Reception and Continuous Wave Transmission.*)

CIRCUIT—The path followed by an electric current passing from its source through a wire conductor or series of such *conductors*, and back again to its starting point. A *closed circuit* is one that is continuous and will permit the passage of current. An *open circuit* is one that is not continuous and, being broken or open at some point, will not permit passage of the current. The term is used very commonly, and broadly covers any system for the conducting of electric current from its source, through some electrical instrument or appliance and back to the starting point.

CIRCUIT BREAKER—Generally speaking, any device for automatically breaking or opening a circuit and thus preventing flow of current through the circuit. More specifically, it may be a device similar to a *switch*, used to automatically open the circuit when the current falls below a certain point, or rises above a certain fixed value. Thus an *overload circuit breaker* is an arrangement which will automatically open the circuit if the current becomes too great. This is shown in Fig. 1. It is a simple form and consists of an *electro magnet* which requires a certain force to operate it. When the current in the circuit reaches a certain point, the magnet operates, pulling down the bar "A" against the action of the spring "P," and thus breaking the circuit. As long as the current is not more than that fixed by the requirements of the circuit—the magnet being arranged in accordance with the particular requirements — the current flows, the breaker operating to open the circuit only when more than the desired current is introduced into the circuit. In the illustration we can consider "S1" and "S2" as the source of current, "M" as an electro-magnet in series with the motor "D," and "A-B" a switch, in which "A" has attached to it a piece of soft iron. Now if the current required for the motor is ten amperes, the magnet can be so designed that it will not act on the bar "A" until 15 amperes flow through it. Thus, as long as the current is less than this, the circuit is continuous, but if the current is increased to 15 amperes, the magnet operates and attracts the bar "A," breaking its contact with "B" and thus opening the circuit. In Fig. 2 a simple *underload breaker* is shown. In this case the operation is the reverse of that of the *overload breaker*. Here the bar "A" is held down in contact with "B" by the magnet "M" thus keeping the circuit closed through the motor "D". Now assume that the motor requires ten amperes and the magnet requires the same amount to hold the bar "A" in place against "B". If then the current in the circuit falls below ten amperes, the magnet can no longer hold the bar "A" against the action of the spring "P" and it rises, breaking the contact between "A" and "B" and thus opening the circuit. These circuits are of course only assumed for the purpose of illustrating the theory of circuit breakers. Actually the system is generally much more elaborate. Circuit breakers are used for many purposes—chiefly to prevent any sudden increase or decrease of current in a circuit, and to control the flow of current for charging batteries. (See *Charger-Storage Battery.*)



Fig. 1. Overload Circuit Breaker.



Fig. 2. Underload Circuit Breaker.

CIRCUIT, BROKEN—A circuit that is not continuous, having been opened either purposely, or due to some defect in the circuit. The term is usually applied where the circuit is opened by the breaking of a wire, or through a faulty contact.

CIRCUIT, OPEN — A circuit which is open and through which current cannot flow, or a circuit which is normally open but which can be closed at will by pressing a key or button. A common example of open circuit is in the case of an electric bell circuit. The illustration shows such a circuit. Normally it is open and current does not flow to the bell, but on pressing the button B, the circuit is closed and current passes to the bell. (See *Circuit*, also *Closed Circuit.*)



Open circuit which can be closed by pressing button "B".

CIRCUITS, PARALLEL — Circuits starting at a common point and ending at a common point. The illustration shows three *parallel circuits*. Actually each one is a part of the whole circuit. (See *Parallel Resistances.*)



Three parallel circuits.

CIRCULAR MIL—The cross-sectional area of conductors (wires) is usually designated in terms of circular mils. A circular mil is the area of a circle having a diameter of one thousandth of an inch. Thus a wire having a diameter of one quarter of an inch is said to have an area of 250 circular mils. (See *Square Mil.*)

CLEAT—A form of porcelain *insulator* used in house wiring. They are generally arranged in two parts, with corresponding grooves in which the wire is held, and are nailed or otherwise fastened to the wall. Cleats are about the cheapest form of insulator and where the voltages used are low, are quite as effective as the more elaborate types. Cleats are much used in radio work, both for insulating lead in wires coming from the aerial, and for insulating the aerial itself.

CLERK-MAXWELL, JAMES—Born at Edinburgh, Scotland, in 1831, and educated at Edinburgh and Cambridge University, he became Professor of Natural Philosophy at Aberdeen, 1856-69, and Professor of Physics and Astronomy at King's College, London, 1860-65. In 1871 he became the first holder of the new chair of experimental physics at Cambridge, where he died, November 15, 1879. Clerk-Maxwell was recognized in his later years as one of the greatest authorities on physics of his time, and his fame has been steadily increasing since his death. Radio owes Clerk-Maxwell a deep debt. Electricity was the chief study of his lifetime, and his first important paper on the theory of *electromagnetism* was communicated to the Royal Society in 1867. In 1873 he published his "Electricity and Magnetism," a work on the subject which has never been surpassed. In it he formulated his famous *electro-magnetic theory* of light and his theories on electric waves, which developed into the modern system of wireless telegraphy and telephony through the experiments of Hertz.

James Clerk-Maxwell.

CLIMAX—A high resistance nickel steel alloy, used extensively in *rheostats* (q.v.). It is one of the cheapest and most practical alloys for low-temperature resistance wire. Its chief properties are as follows: Maximum working temperature 540 degrees centigrade, resistance in microhms per cubic centimeter at 20 degrees centigrade, 87.2; temperature coefficient per degree centigrade, .00054, and having a specific gravity of 8.14.

CLIPS—A clamp connector used for various purposes in radio receiving and transmitting circuits. (See *illustration.*) In a receiving set a clip may be used at the end of a flexible wire for the purpose of varying the connection to the various "B" battery taps; clips are very frequently used in making the connections to the storage "A" battery, and for many other purposes about the receiving set. One of their principal uses in the transmitter is in connection with the leads to the oscillation transformer. Flexible leads with clips attached come from the other units of the transmitter and are clamped at will along the various turns of the oscillation transformer until the point giving the desired wave length or highest radiation reading is found.



Type of clip in general use.

CLOCKWISE—A term used to indicate that the rotating part of an electrical machine or instrument moves from left to right (when facing it), or as the hands of a clock. In the illustration the needle or pointer of the meter moves in a clock-wise direction. In an electrical measuring instrument this is always true where the zero point is at the left part of the dial. The opposite is known as *counter-clockwise*. When looking at the *armature* of a motor or generator, if the rotating part moves from left to right it is said to have a clock-wise motion.



Indicator needle moves from left to right in clockwise motion.

CLOSE COUPLING The arrangement of two coils acting as *primary* and *secondary*, placed close together in such manner that the coupling or electrical relation between them is close. In the illustration the secondary coil is shown entirely within the primary. In other words the transfer of energy will be large in this case as the coupling is close. If the secondary is withdrawn a certain distance from the primary, the effect is referred to as loosening the coupling, and the coils are then said to be *loose coupled*, the transfer of energy from one to the other being considerably less than in the case of close or *tight coupling*. (See *Coupling.*)



Loose coupler with secondary placed to produce close coupling.

CLOSED CIRCUIT—A circuit which permits the continuous flow of electricity. The illustration shows an ordinary dry cell connected in circuit with a small lamp. In Fig. 1A the circuit is closed and current is permitted to flow to the lamp. In Fig. 1B the circuit is open and no current can flow. A closed circuit is therefore an electrical circuit that is continuous. (See *Circuit*, also *Open Circuit.*)



-1A-

Circuit closed.



-1B-

Circuit open by means of switch.

CLOSED CIRCUIT CELL—A cell that can be used in a closed circuit for a considerable length of time without the impairing effects of *polarization* (q.v.) An *open circuit* cell is one that can only be used intermittently, as for example, with an electric bell where the circuit is only closed for a brief period. If an open circuit cell is used in a circuit that remains closed for some time, polarization sets in and ruins the cell in a very short time. An open circuit cell might be used with the *test buzzer* (q.v.) because in this case the circuit is closed intermittently as the key is depressed. (See *Cell.*)

CLOSED CORE—A core (q.v.) used in *transformers*, *chokes*, etc., which is continuous, forming a *closed magnetic path*. The illustration shows the difference between a closed core and an open core. In the open core type, one end is the north pole, the other the south pole, whereas in the closed core, there are obviously no poles. The closed core type is occasionally referred to as a *non-polar* core. (See *Core*, *Transformer*, also *Choke.*)


N
S
MAGNETIC PATH THROUGH AIR & IRON
MAGNETIC PATH ENTIRELY THROUGH IRON

Open core above on left. closed on right.

CLOSED CORE TRANSFORMER—A *transformer* (q.v.) having a *closed core*. In the illustration the magnetic path, or core, is continuous, being made of strips of uniform size. This form of core is known as *"laminated."* An efficient transformer is generally made with a closed core. A transformer may be for a variety of purposes, such as *step-up, step-down, audio frequency* or *radio frequency*. (See *Transformer.*)



Closed core transformer.

C. M.—Abbreviation for circular mil. (q.v.)

Cm.—The abbreviation for *centimeter*, the unit of length in the C. G. S. system (q.v.).

COCKADAY CIRCUIT — A popular radio receiving circuit devised by the American experimenter, Lawrence M.



Fig. 1. Original 3 tube Cockaday Circuit.

Cockaday. It includes several radical features not found in the usual systems. Receivers using this circuit are generally made in three, four or five tube types. The chief value of this circuit lies in its extreme selectivity. It is usually referred to as a four circuit receiver, owing to the addition of a sensitizing circuit to the regular three circuit regenerative system. The diagram for the three tube receiver is given in Fig. 1. Here the primary or aerial tuning circuit is seen to have a single turn of wire, L1, wound around another coil L2, which is shunted by a variable condenser C1, thus forming a separate closed, tunable circuit, coupled very loosely with the antenna circuit. The primary, or antenna circuit, has in addition to the single turn, a bank wound coil L3 connected in the ground side of the open circuit and tapped to permit coarse tuning. Thus, the primary is coupled inductively to the separate closed circuit, which in turn is inductively coupled to the grid or secondary circuit containing a coil L4 shunted by the condenser C2, allowing tuning.

The tone of the music is varied by means of the novel arrangement using a condenser C4 connected to a three point switch. When the switch is placed in the center position the condenser is eliminated from the circuit and the wiring is standard. With the switch on the top tap, the grid of the tube is connected to the ground, thus by-passing a portion of the oscillations and giving a smooth soft tone with a certain loss of volume. With the switch arm on the bottom tap, the grid of the last tube is connected to the plate circuit, thus producing a different note due to the added grid-plate capacity. Coil L2 in the grid circuit is tuned by means of C1, which is a variable condenser of .0005 mfd. capacity.

A peculiarity of the circuit is that the length of the antenna has no bearing on the tuning. This is due to the *semi-aperiodic primary* and the fact that the sensitizing or pick-up coil is only one turn of wire, the inductance of which, compared to the whole inductance of the aerial circuit, is so small that any change in the over-all inductance has little, if any, effect.

This circuit, while originally having three tubes, has been arranged in conjunction with a standard *push-pull audio amplifier*, as shown in Fig. 2, making a five tube set with great power and possessing the characteristic of the original circuit with increased amplification. (See *Push-pull, Cockaday Coil* also *Regenerative Receiver.*)



Fig. 2. Cockaday Circuit with push-pull amplifier.

COCKADAY COIL—The coil used in the *Cockaday circuits.* It comprises four windings, i.e. tapped primary, separate closed circuit coil, grid or secondary winding and a single turn looped around the closed circuit coil. (See *Cockaday Circuit.*)

CODE—Telegraph codes consist of characters formed by combinations of dots, dashes and spaces which represent letters, numerals, and punctuation marks. These characters are sent out by the radio operator with the aid of electrical impulses, and by using suitable receiving apparatus the receiving operator hears the incoming signal and is thus able to interpret the various combinations of dots and dashes and reproduce the original message. The Morse Code of characters came into general use in wire telegraphy shortly after the establishment of that means of communication. In this system, which is also called the "American Morse Code," some of the characters are made up with so-called spaces which are part of the group signal, and are necessary in distinguishing those characters. The International Morse code is a modified form of the American Morse code, and no spaces are used in the characters of the International Code. The International Morse Code is used all over the world for radio telegraphy, and for wire telegraphy in almost every country except the United States, Canada and parts of Australia. The American Morse, owing to the fact that there are fewer dashes in the characters, is about

LETTERS	MORSE	CONTINENTAL
A	● ▬	● ▬
B	▬ ● ● ●	▬ ● ● ●
C	● ● ●	▬ ● ▬ ●
D	▬ ● ●	▬ ● ●
E	●	●
F	● ▬ ●	● ● ▬ ●
G	▬ ▬ ●	▬ ▬ ●
H	● ● ● ●	● ● ● ●
I	● ●	● ●
J	▬ ● ▬ ●	● ▬ ▬ ▬
K	▬ ● ▬	▬ ● ▬
L	▬▬	● ▬ ● ●
M	▬ ▬	▬ ▬
N	▬ ●	▬ ●
O	● ●	▬ ▬ ▬
P	● ● ● ● ●	● ▬ ▬ ●
Q	● ● ▬ ●	▬ ▬ ● ▬
R	● ● ●	● ▬ ●
S	● ● ●	● ● ●
T	▬	▬
U	● ● ▬	● ● ▬
V	● ● ● ▬	● ● ● ▬
W	● ▬ ▬	● ▬ ▬
X	● ▬ ● ●	▬ ● ● ▬
Y	● ● ● ●	▬ ● ▬ ▬
Z	● ● ● ●	▬ ▬ ● ●
&	● ● ● ●	
1	● ▬ ▬ ●	● ▬ ▬ ▬ ▬
2	● ● ▬ ● ●	● ● ▬ ▬ ▬
3	● ● ● ▬ ●	● ● ● ▬ ▬
4	● ● ● ● ▬	● ● ● ● ▬
5	▬ ▬ ▬	● ● ● ● ●
6	● ● ● ● ● ●	▬ ● ● ● ●
7	▬ ▬ ● ●	▬ ▬ ● ● ●
8	▬ ● ● ● ●	▬ ▬ ▬ ● ●
9	▬ ● ● ▬	▬ ▬ ▬ ▬ ●
0	▬▬▬	▬ ▬ ▬ ▬ ▬
.	● ● ▬ ▬ ● ●	● ● ● ● ● ●
,	● ▬ ● ▬	● ▬ ● ▬ ● ▬
:	▬ ● ▬ ● ●	▬ ▬ ▬ ● ● ●
;	● ● ● ● ●	▬ ● ▬ ● ▬ ●
?	▬ ● ● ▬ ●	● ● ▬ ▬ ● ●

Morse and Continental Codes.

5% more rapid than the International Morse. The American Morse and International (Continental) Codes are given herewith.

COEFFICIENT—In algebra, a number or multiplier of a *symbol*. Thus in the expression 5Y, the coefficient is 5. In electricity, and in its radio application, it is a number expressing the relation or ratio between quantities, one of the quantities generally being unity (1) as a basis or standard for the coefficients. For example, let us assume a copper wire is carrying an electric current, the *resistance* of the wire at 32 degrees Fahrenheit being one *ohm*. If we consider the resistance of the wire at 32 degrees to be unity, or one, then its resistance at any other temperature will be some number or coefficient times one.

To make this clearer, let us take the ratio of an inch to a foot. An inch is one-twelfth, or approximately .0833, of a foot. Any number of inches multiplied by this fraction will give another number in feet. Therefore we say that the coefficient, or multiplier, of an inch as compared to a foot is .0833. A coefficient is thus any number by which a quantity must be multiplied to give another quantity.

In radio the most common cases of coefficients are the following. The *coefficient of coupling* is the ratio between the *mutual inductance* (q.v.) (between the two coils, *primary* and *secondary*) and the square root of the product of the total *self-inductances* (q.v.) in the two circuits containing the coils. Similarly, the coefficient of amplification is the ratio of the effect produced with an *amplifier* (q.v.) to the effect produced without an amplifier. (See *Mutual Induction Coefficient*, also *Self-induction Coefficient*.)

COHEN, LOUIS, Ph. D.—Born in Russia, Dec. 16, 1876. Educated at Armour Institute of Technology, University of Chicago and Columbia University. Noted for his formulae and tables for the calculation of alternating current problems. He has written a book on the subject. Has evolved many formulas for the measurement of inductance and capacity. Has secured a number of patents on radio apparatus.

COHERER—A device formerly employed for detecting *radio waves*. In its original form it consisted of two metal rods separated by a narrow space in a glass tube and the gap between the rods filled with nickel and silver filings. It was found that when the *electromagnetic waves* or signals were passed through the coherer the particles of filings clung together and became *conductors*. Then by using some device such as the tapper hammer of an electric bell to strike the glass tube, again separating the particles after each signal, it was possible to keep the coherer constantly in a state of change between a *conductive* and a *non-conductive* condition, thus making the signals audible. There were many variations of this type of *detector*, which, however, is now obsolete. (See *Marconi Coherer*.)



Coherer used in radio receiving circuit.

COIL—A term having very broad application in electricity and radio. It may be used to designate any arrangement of a number of turns of wire, usually copper, and used for almost any purpose in the production of electric and magnetic effects or phenomena. The most common significance of a "coil" in radio is in reference to a number of turns of insulated wire wound on various forms and used for *tuning* (q.v.). The term *inductance coil* is generally used, although actually, any coil of wire will have inductance. Coils come in countless numbers and variety for many purposes. A coil may be used not alone for tuning—that is to adjust a receiver or transmitter to resonance with incoming or outgoing signals; it may be used to connect two circuits, in which case it is known as a *coupling coil*; it may be used with a *core* (q.v.) of iron wire, or laminated pieces, as a *choke coil* (q.v.) or it may be used in connection with *high frequency* apparatus, such as used by physicians. Coils are generally referred to by individual names indicating their construction or use. (See *Inductance, Tuning Coil, Vario-coupler, Choke Coil, Honey Comb Coil, Pancake Coil, Spider Web Coil, Lorenz Coil, Duo Lateral Coils*.)

COIL ANTENNA—Or Loop Aerial. An antenna (aerial) constructed by winding the wire around a square form. The coil (or loop) antenna, because of its comparatively small size, is often mounted on a frame work which may be rotated. If one end of the coil is pointed toward the broadcasting station, the antenna (aerial) will pick up its signals with maximum intensity, but if the coil is rotated from that position the signals from that station grow weaker, until when the plane of the loop is at right angles with the intercepted signals no sound will be obtained. It is a part of the radio compass used at sea. (See *Loop-Aerial*.)

COLLECTOR RINGS—Insulated metal rings attached to the *armature* (q.v.) of an *alternator* (generator of alternating current) in such fashion that the alternating currents can be collected and communicated to the *brushes* without change, these rings are used to collect alternating current from that type of generator and brushes are used to collect direct current from a direct current generator.

COLLODION—A solution used by surgeons to cover slight abrasions or wounds, forming a protective coating similar to skin. It has been adapted to radio use as an insulating coating and is used as a binder on coils of various forms. It has been found more efficient than shellac for this purpose. A solution of pyroxylin or soluble guncotton in ether, with a certain amount of alcohol, depending on the purpose for which intended. When used as a coating for coils it serves as an insulator and also to hold the coils in place, but it should be sparingly applied.

COMBINATION DETECTOR—A detector composed of two different crystals in contact, instead of one crystal with a fine wire to search out the sensitive spots. Some combination detectors are composed of silicon and antimony; zincite and bornite; lenzite and cerusite, and zincite and chalcopyrite. These detectors all function without a battery and are simple to operate.

COMMON CONNECTIONS—A term often applied to a connection that joins several points. For example, in most radio receivers the binding posts for battery connections are arranged so that the "B—" and the "A+" or "A—" are connected to the same point. That is to say the post is a common connection for these leads. The term is also applied to a battery, as a *"B" battery*, which is used for both *detector* and *amplifier*. It is then known as a common "B" battery. The other method would, of course, be to use separate batteries for the detector and amplifier.

COMMUTATOR—In general electrical use, a device for reversing the direction of electric currents in a circuit. A *commutator* as used with a *generator* usually consists of a number of pieces called *segments*, mounted on a circular form but carefully insulated from each other. The illustration shows a common form. In the case of an ordinary motor, the commutator is employed to distribute the current to the windings and in a direct current generator it serves to furnish a direct current to the brushes although the current collected from the windings of the *armature* is alternating.



Front and side view of Commutator.

COMPASS, RADIO — See *Direction Finder, Goniometer*, also *Bellin-Tosi Direction Finder*.

COMPONENT—A part of the whole. In mechanics it is one of the parts of a stress or strain (mechanical force). In electricity, *component currents* are the several currents into which a single current may be assumed to be separated, so that if assumed to be acting together they would produce the equivalent effect of the actual current. Thus also, component *E. M. F.'s* (*electromotive forces*) are understood as the several components into which any electro motive force may be divided. *Impedance* (q.v.) is said to consist of two components, the actual resistance and the apparent resistance present in the opposition offered to the flow of current termed the *reactance* (q.v.) by a circuit. For instance, the total current in the plate circuit of a vacuum tube responding to high *frequency grid voltages* may be considered as made up of two components, viz., a steady or constant current and a high frequency component superimposed on it.

COMPRESSED AIR CONDENSER—A condenser which uses compressed air as the *dielectric* or insulating material between the plates. This type of condenser is used chiefly in transmitting circuits. (See *Condenser*.)

COMPOUND MAGNETS—A combination of several *permanent magnets.* (See *Magnets, Compound.*)

COMPOUND WOUND—A *dynamo* or *motor field magnet* wound with two *field windings,* one of which is connected in series, the other in parallel with the *armature* (q.v.).

CONDENSER—In electricity or radio practice a *condenser* consists of two or more conducting surfaces placed in relation to each other and separated by an insulating medium such as air, impregnated paper, mica, etc. The conducting surfaces are generally referred to as *plates* or *electrodes* (q.v.) and the insulating material is known as the *dielectric* (q.v.). Condensers are used in radio for a variety of purposes, their broad use being to allow tuning. In action, a condenser permits charges of electricity known as *electrostatic charges* (q.v.) to be stored up and released periodically, according to the frequency desired. They may also be used to exclude certain types of energy. (See *Condenser, By Pass,* also *Filter.*) The action of a condenser may be compared to that of a spring when placed under a mechanical strain. In the illustration Fig. 1A a flat spring S is shown in a normal position, NB. In 1B a weight W is placed on the surface of the spring. This weight will force the spring down from its normal position to one of the positions (a), (b), (c) or (d), according to the force exerted and the strength of the spring. If a heavier weight is then placed on the spring it will depress still further until we can imagine a point P in Fig. 1C at which the elasticity of the spring is used up and the opposition is such that it will no longer depress and comes to rest. When the weight is removed the spring will fly back into normal position, Fig. 1D, and in doing so will vibrate back and forth a number of times, thus producing, or rather, returning the energy that was stored in it during the moment of stress.

Considered as analagous to a *condenser,* in the above case the weight can be likened to the electrical charge applied to the condenser, the *resistance* of the spring may be considered somewhat similar to the *capacity* of the condenser, or the power returned on release of the spring may be regarded as the electrical power released by the condenser when the charging force is removed. The capacity of the condenser then will be seen as the ability to store up energy placed in it.



Spring analogy of a condenser.

In the case of the spring, if too great a force is exerted, it may break down or as would actually happen, the elasticity would be lost. The same applies in the case of a condenser. If the charging force is too great, it may exceed the dielectric strength of the condenser and result in puncturing the insulating material between the plates. (See *Breaking Down of Dielectric.*) The energy obtainable from a charged condenser will be equal to the charge placed in it providing there is no leakage or other loss. In a well-designed condenser the leakage will be so negligible that it need not be taken into consideration.

The relation between the charge in a *condenser,* the *voltage* applied and the *capacity of the condenser* is expressed as $Q = C \times E$, where Q is the quantity of the charge in *coulombs,* E the potential in *volts* and C the capacity in *farads.* (See *Capacity, Condenser, Variable; Condenser Fixed; Condenser Transmitting,* also *Condenser Curves.*)

CONDENSER, AIR—See *Air Condenser.*

CONDENSER, ANTENNA—See *Aerial Tuning Condenser.*

CONDENSER, BY-PASS—A condenser, usually of the fixed (q.v.) type arranged in a circuit in such manner that currents of a certain frequency will pass freely around any obstructing object, as, for instance, a high resistance element necessary to the circuit. An example of the use of a condenser in this manner is shown in the case of a "B" battery where the battery has a high internal resistance. A fixed condenser is placed across the terminals of the battery without injury to it and offers a path of low resistance for the high frequency radio currents.



By-pass condenser across "B" battery.

CONDENSER CURVES—Curves showing the relation of variations in wave-length, frequency, and capacity with rotation of the dial of a variable condenser. Three types of condensers are shown here, the *compression,* Fig. 1, the *straight line capacity,* Fig. 2, and the *square law,* Fig. 3. In Fig. 1A is shown the relation of capacity and wavelength changes when the dial of a sample compression condenser was rotated. The condenser was shunted across a fixed coil. It will appear that the increase in capacity is gradual at the lower part of the range but increases very rapidly at the upper ranges. This is due mainly to the relation of the curvature of the upper plate to the lower plate as will be seen from the illustration, Fig. 1. These condensers are very satisfactory on about the lower two-thirds of their range, but through the remainder of their range a very slight adjustment of the knob causes an extremely large change in capacity, making them very difficult to handle near their maximum capacity. Fig. 2 shows the shape of the variable plates in the straight line capacity condenser and Fig. 2A illustrates the relation of wave-length and capacity changes with rotation of the dial. Here the capacity depends upon the overlapping area and is therefore proportional to the angle of rotation of the movable plates. The capacity curve appears as a practically straight line running diagonally across the chart. The wave-length, however, changes rapidly at the lower range and very gradually at the upper range as indicated by the wave-length curve. Fig.



Fig. 1. Compression type condenser.



Fig. 1A. Curve for compression type condenser.



Fig. 2. Straight line condenser.



Fig. 2A. Curve for straight line condenser.

3 shows the shape and disposition of rotor and stator plates of a condenser so designed as to read directly in wave-length from the settings of the dial.



Fig. 3. Square law condenser.

This is known as a square law condenser, and the relational curves are shown in Fig. 3A. Here we find the wave-length curve a straight line and directly proportional to the angle through which the dial is turned. The line indicating the square root of the capacity √C is a straight line, and as the wavelength is the product of the square root of the capacity multiplied by a constant (varying with the individual condenser) the wavelength curve must also be a straight line.



Fig. 3A. Curve for square law condenser.



Fig. 3B. Showing effect of straight line condenser on dial reading.

Such condensers are much used in wave meters (q.v.). Condensers are also made so that the frequency curve is a nearly straight line, varying more or less directly as the angle of rotation of the plates. Fig. 3B illustrates the result when an ordinary straight line capacity condenser is arranged with a dial calibrated directly in meters. It appears that the readings are bunched at the lower range (A to B) and spread out at the upper ranges (C to D). The reason for this can readily be seen by glancing at the curve Fig. 2A.

CONDENSER, FIXED—A *condenser* which has a fixed or constant capacity, allowing no variation of the value. (See *Condenser*, also *Condenser, By-Pass.*)

CONDENSER, GRID—A condenser, generally of low capacity, of the fixed or variable type, used in series with the grid of the *detector tube* to prevent excessive charges from affecting the *grid*. These condensers generally have a capacity between .00025 and .0005 *micro farads*. Due to the blocking action of these condensers, a high resistance, known as a *grid leak* (q.v.) is placed across the condenser or from the grid to filament, thus allowing the accumulated charges to leak off the grid of the tube in time for the grid to be free for the succeeding electric charge. The grid leak may be considered as a valve controlling the amount of energy that the detector can efficiently take care of without overload. (See *Grid Leak.*)



Grid leak and condenser.

CONDENSER, IN PARALLEL—A condenser arranged in a circuit in such manner that the current is divided between it and the other condenser or coil with which it is connected. The illustration shows a *variable condenser* connected in parallel with a coil, both placed in series between aerial and ground and forming a tuned primary or aerial circuit. (See *Parallel Connections.*)



Coil and condenser in parallel.

CONDENSER, IN SERIES—A condenser connected in a circuit with other condensers or coils in such manner as to form a continuous path, allowing the current to pass through each unit without dividing. The illustration shows a condenser connected in series with a *tuning coil*, aerial and ground, thus forming a tuned primary or aerial circuit. (See *Condenser, in Parallel*, also *Series Connections.*)



Coil and condenser in series.

CONDENSER, MICA—A condenser, usually of the fixed type, employing sheets of mica as the dielectric or insulating material between the plates. The condensers of small capacity used in receiving circuits are generally made with mica as a dielectric, but owing to its cost and thickness it is seldom used in low-power, high-capacity condensers. Mica is also used in condensers for high-power work such as transmitting, when the capacity is low. (See *Condenser.*)

CONDENSER, PHONE—A fixed condenser of comparatively low capacity used across the *telephone receivers* to allow a by-pass for a certain portion of the currents and thus prevent undue strain on the phones. (See *Condenser, By-Pass.*)

CONDENSER, TRANSMITTING—See *Condenser, Mica.*

CONDENSER, VARIABLE—Any condenser so arranged as to allow variation of its capacity. This may be accomplished in many ways, the usual method being to have the plates divided so that one series is movable with respect to the others, the capacity changing with the rotation of the variable plates. (See *Condenser.*)

CONDUCTANCE — Sometimes called the conductivity. The quality of a given conductor in virtue of which it facilitates the flow of an electric current. A *conductor* (q.v.) is a body having large *conductance* and an *insulator* (q.v.) is one having negligible conductance. *Conductance* is thus the opposite of *resistance*. The unit of conductance is the *mho*, the reciprocal of *ohm*. The symbol is obviously derived from ohm, reversed. It is the conductance of a column of mercury 106.3 cm. (centimeters) long, 1 square mm. (milimeter) in cross-sectional area and of a weight of 14.4521 grams.

CONDUCTIVE COUPLING—The association of one circuit with another by means of inductances (coils) mutual to both circuits.

CONDUCTIVITY, SPECIFIC—The reciprocal of Specific Resistance; being a standard of reference for comparing the conductances of different substances. (See *Specific Resistance, Conductance.*)

CONDUCTOR—Any substance that offers small *resistance* to the passage of electric currents may be termed a *conductor*. This term is the opposite of *insulator*, but there is actually no line of demarcation between the two, since any insulator will permit the passage of current when sufficiently high voltages are used. For all practical purposes, however, a conductor is considered as material that presents little difficulty to the passage of current. The most common conductor is copper, usually in the form of wire. An idea of the relative conductivity (power of carrying electric current possessed by various substances, pure copper being taken as standard) of various substances can be gained from the table following. The materials on the left are comparatively good conductors given in the order of their conductivity, while those on the right are poor conductors and generally used for resistances. (Note: A *resistance* is used to retard the flow of electricity without necessarily stopping it entirely, whereas an insulator is used to stop the passage of current.)

Silver
Copper
Brass
Gold
Aluminum
Zinc
Platinum
Iron
Nickel
Tin

German Silver
Platinum Silver
Manganin
Mercury
Graphite or carbon

There are, of course, many other substances that can be classed as good conductors, or as poor conductors, but the above are more generally known and used. It is a peculiar fact that while good conductors become less conductive as their temperature is raised, insulators lose a certain amount of their insulating properties as their temperature is raised. As too great current in a conductor will cause heat, and as explained above, cause lessening of conducting ability, it will be obvious that for the fullest efficiency a conductor will necessarily be arranged to carry the required current without undue heating. It is understood also that conductors in any part of a radio circuit should be carefully gauged as to size and the effective cross-section of the conductor determined, in order to offset the losses due to heating. It must not be assumed from the foregoing that the larger the wire the greater the efficiency—in fact a large wire is often less satisfactory than a small one in high frequency circuits.

When the conductor is to carry direct current the only consideration is to have the wire large enough to prevent heat losses and at the same time not be too bulky. Where the conductor is to carry *high-frequency* (q.v.) currents there are other factors to consider. High frequency currents are said to travel only on the outside of the wire (see *Skin Effect*) and therefore it is possible to use very fine wire for this purpose when the very low current values obtaining in reception are in question. A phenomenon that must be given attention, however, is that of *distributed capacity* (q.v.). (For more complete explanation of this subject see *Low-loss Coils*. See also *Bus bar.*)

CONNECTING UP or HOOKING UP—These general terms are used in radio to refer to the process of wiring a receiver or any particular part of a receiver or other circuit.

CONSTANT—A quantity or magnitude, which does not vary, derived from actual experiment, which is included as a factor in most formulas for the purpose of bringing theoretical calculations into agreement with experience. Constants are much used in radio calculations. As an illustration, different dielectric or insulating materials used in a condenser have different constants which must be taken into consideration when calculating the capacity of the *condenser*. Thus, as a dielectric, air at ordinary pressure is taken as the standard, the constant being stated as 1. Flint glass has a high dielectric value, its constant being stated as 10.10, other materials varying according to their comparison with air as a standard. (See *Dielectric.*)

CONSTANT CURRENT—An unvarying *current*. The term "constant" is applied to *voltage* when it is steady and unchanging, to *resistance* when it is fixed and unvarying, or to almost any value that does not change.

CONSUMPTION, CURRENT — The term usually employed to denote the current required or consumed by any part of an electrical circuit or by the circuit itself. A resistance in a circuit consumes a certain amount of energy because it dissipates it as heat energy. A filament in the case of a vacuum tube, requires a certain amount of current to heat it to brilliancy. If the filament thus requires one-quarter of an ampere we say its current consumption is one-quarter ampere. (See *Plate Consumption.*)

CONSUMPTION, PLATE—The current required to energize the plate of a vacuum tube. (See *Plate Consumption.*)

CONTACT BREAKER—A contrivance for quickly and automatically making or breaking an electrical circuit normally existing between two contacts. (See *Circuit Breaker.*)

CONTACT DETECTOR—A form of crystal detector in which a small wire, or "catwhisker," as it is called, makes contact with the crystal in the detector and acts as a *rectifier* of the *high frequency waves* received from the broadcasting station. (See *Crystal Detector —Theory of Operation.*)

CONTACT POINTS, or SWITCH POINTS—Generally refers to a small flat-headed machine screw used as a contact point for a *switch*. The illustration shows the types mostly used.



Various contact points.

Leads from various points of a tapped coil may be connected to the several contacts in order to permit variation of the *inductance*. A "contact point" may also mean any point in an electrical circuit at which contact is made to close the circuit.

CONTACT RECTIFIER—See *Contact Detector.*

CONTACT RESISTANCE—When two connecting surfaces in a circuit carrying electrical energy do not make absolute or perfect contact, a certain amount of *resistance* (q.v.) results. In any part of a radio circuit where two wires or *conductors* are joined to form a circuit, it is essential that they make a positive contact. The wires used for connections in a radio receiver are generally soldered or fastened tightly by nuts or bolts, or machine screws in order to form a good contact. If this is not done, energy may be wasted, due to the resistance at the point of contact.

CONTINUOUS OSCILLATIONS—Each oscillation or vibration being of the same amplitude as the preceding one. (See *Sine wave.*)

C. W.—Abbreviation for continuous wave (q.v.).

CONTINUOUS DIRECT CURRENT—A *direct current* which flows steadily without interruption or reversal. The current supplied from a battery for radio use is continuous direct current, while that portion of the *high frequency alternating current* which is rectified by a *vacuum tube* detector is called *pulsating direct current*, as there is an interval of time between the rectified half of each incoming wave, due to the other half not being rectified. (See *Current, Pulsating Direct, Pulsating Current,* also *Rectification.*)

CONTINUOUS WAVES—Also called *Undamped* or *Sustained waves* and usually referred to as *C. W. Electromagnetic waves*, the separate oscillations (each vibration) of which are of constant or unvarying amplitude. In Fig. A a series of *oscillations* (q.v.) are shown. It will appear that one oscillation or *cycle* is of the same amplitude as the preceding one—the amplitude (q.v.) being considered as the height of the wave above the straight line representing time or its depth below that line. Each loop above the line or below it represents an *alteration* (q.v.) (the increase in current to maximum and back to minimum in either direction)—the loops above the line being considered as *positive alternations* and those below the line as *negative alternations*. Now it is evident from the sketch that each succeeding alternation has the same strength (amplitude) as that preceding it, and the same is true of the complete cycle, consisting of one alternation in each direction. Thus the waves are continuous, or constant, as far as amplitude is concerned. Now in Fig. B the amplitude is not constant—it decreases with each succeeding alternation and hence with each succeeding cycle (two alternations). After a comparatively few oscillations the current has decreased to zero, that is, the oscillations have died out completely. In this case the percentage of decrease in amplitude from one cycle to another is known as *decrement* or *damping*. Thus continuous waves may be considered as waves in which, with any train or group of oscillations, each succeeding oscillation has the same amplitude as that preceding it.



Series of undamped and damped waves.

CONTINUOUS WAVES—KEY MODULATED—Continuous waves (q.v.) which have been broken into dots and dashes of the telegraphic code by means of a *telegraphic key*, these signals being made audible at the receiving end by the use of an oscillating receiver.

CONTINUOUS WAVES—MODULATED AT AUDIO FREQUENCY—The process of variation of the frequency (vibration) of waves radiated by a broadcasting station in accordance with the sound waves is known as modulation. Frequencies from 10,000 down to about 32 are audible to the human ear and are known as audio frequencies. Hence continuous waves which are modulated at *audio frequencies* are waves which have been modulated (varied) by having the voice or music impressed on the *microphone* at the broadcasting station, which in turn causes the strength of the radiated electric wave to vary so as to correspond electrically to the sound vibrations at the microphone.

CONTINUOUS WAVE SIGNALS—See *Continuous Waves.*

CONTINUOUS WAVE TRANSMISSION—System of radio telegraphy using waves as described under "Continuous Waves."

CONVECTION CURRENTS—When a hot and a cold body are separated by a fluid which is free to circulate, heat is transferred from the hot to the cold body by currents of the fluid itself flowing from one to the other; similarly, all parts of a fluid which is being heated quickly come to approximately the same temperature. This transfer of heat by currents of the fluid itself is called "convection." In electricity "Convection Currents" are currents arising from the motion of charged particles thrown off in electrified streams, i.e., the flowing of charged air particles in streams from the pointed end of a highly electrified conductor, sometimes called "electric wind."

CONVENTIONAL—This term is much used in radio to denote a form established by custom. A conventional circuit for some particular purpose is understood as a circuit which has been generally used and which is generally considered as standard. Broadly, the most common form or use of anything. The conventional method of amplifying signals of *audio frequency* is by means of *audio frequency transformers.* Any other means is unconventional, although it may produce similar results.

CONVERSION FACTORS—A numerical factor which gives relation between the magnitude of a quantity expressed in terms of one system of units, and the same quantity expressed in terms of any other system of units. For example, the yard is regarded in the United States as 3600/3937 meter (a meter is approximately 39.37 inches). We say, therefore, that the conversion factor between the yard and the meter is 3600/3937 because any number of yards multiplied by this figure or factor will give the result in meters. (See *Capacity Conversion Factors.*)

CONVERTER—A term applied generally to any mechanical, electrical or electro-chemical device which will convert or change one form of energy to another. More specifically in electricity the term is used in reference to (1) a dynamotor designed with two *armatures,* mounted on one shaft, one being a motor armature driven by the original current, the other armature generates new current; this is also called a "motor-dynamo" and it can transform continuous (direct) current to higher or lower voltages, or, (2) a rotary electrical device used to change direct to alternating current or vice versa. (See *Rotary Converter.*)

COORDINATES—A thing of the same rank with another thing may be termed a coordinate. For example, lines by means of which the position of any point as of a curve may be defined with respect to certain fixed lines. In the illustration Fig. 1 lines known as axes of coordinates are shown. Such a system as this will be the basis for curves (q.v.) showing the relation between varying values. If we assume the horizontal line X as the axis of abscissas, all distances measured parallel to this line will be known as abscissas; distances measured parallel to the vertical line Y being referred to as ordinates. The line A-B is parallel to the axis of abscissas X and is therefore an abscissa. The line B-C is parallel to the axis of ordinates and is referred to as an ordinate. Now if we place a number of lines parallel to each axis (ordinates and abscissas) and assign to each of them a certain value, such as amperes, to each abscissa, and volts to each ordinate, a line can be drawn through a number of points to represent the various values of each quantity as related to the other. Thus, in Fig. 2 we have a purely hypothetical curve representing the assumed value of current in amperes under assumed voltages. In the example, the curve at point A shows approximately three amperes under a pressure of ten volts. This imaginary curve is, of course, shown merely for the purpose of illustrating the meaning of coordinates, ordinates, abscissa, etc. (See *Abscissa, Characteristic curve,* also *Graph.*)



Fig. 1. Axis of coordinates.



Fig. 2. Curve showing assumed value of current in amperes under assumed voltages.

COPPER PYRITES—Sometimes referred to as *Chalcopyrite.* It is used in radio reception as one of the elements of a *crystal rectifier* (detector) generally in conjunction with zincite or tellurium.

COPPER SULPHATE—A salt of copper. Also known as blue vitriol or copperas. A copper sulphate solution is sometimes used as a preservative for wooden aerial masts. It is used in certain forms of primary cells (devices for transforming chemical action into electric current) and also produces sulphuric acid when subjected to *electrolysis* (q.v.).

CORD, PHONE—The cord or flexible wire used to connect a *headset* (phone) or *loudspeaker* to the terminals of a receiver. Phone cord is usually copper tinsel wrapped around a cotton cord, the whole covered by braided silk or cotton threads. It cannot be used to carry high currents, but is efficient for the comparatively low currents flowing through the phone circuit of a radio receiver. Some phone cords are also formed of a number of fine copper wires covered with a suitable insulating material.

CORE—The central portion of a piece of certain electrical apparatus. Thus the center of a coil will be the *core,* irrespective of its nature, whether air or iron. The core of a *choke coil* (q.v.) is usually made of a bundle of soft iron wires or strips of iron. The core of the closed type is called a *laminated core,* being made up of laminations or layers of the core metal. (See *Choke or Choking Transformer, Closed Core.*)

CORE LOSSES—The losses due to the *stray currents* (q.v.) set up in an iron core while under the stress (strain) of a *magnetic field* (q.v.). Also losses due to *hysteresis* and *eddy-currents.* (See *Magnetic flux, Eddy current,* also *Hysteresis.*)

CORE TRANSFORMER (Iron)—A transformer having the wire wound over an *iron core,* the iron forming a path for the *magnetic lines of force,* as distinguished from a *transformer* in which there is no iron core—called *air core.* (See *Transformer.*)

CORONA—The Latin word meaning crown, originally applied to the crown shaped lights occurring in the *aurora borealis.* In electrical parlance it refers to the luminous discharge which occurs along high tension transmission lines or the aerial wires of a high power radio transmitting station. (See *Brush Discharge;* also *Corona Loss.*)

CORONA LOSS—The energy loss due to corona discharge. (See *Corona;* also *Brush Discharge.*)

CORRECTION FACTORS—A formula for the measurement of certain values is generally made by using certain conditions or types of apparatus as a standard. For example a formula for calculating the inductance of a coil is made by using a particular type and shape of coil as the standard. Therefore the formula will be essentially correct for this type of coil, assuming that its shape and other characteristics are the same. If, however, the nature of the coil to be tested differs from that of the standard coil in some way not covered by the formula, a system of correction must be used to adjust the formula to the particular case. Thus, the formula for inductance of coils takes into consideration the size of the wire or the number of turns, the length of the coil, its diameter and so on. However, it does not take into consideration the ratio between the length of the coil and its diameter. For this purpose a correction factor (necessary consideration) is needed to correct the result of the formula to fit the individual occasion. This correction factor is generally referred to as a *constant* (q.v.), its value being determined generally from a chart prepared to cover various ratios of length to diameter.

CORROSION—Chemical action which causes destruction of the surface of a metal. In the case of iron it is generally rust, corrosion of copper being due to oxidation, or perhaps the action of stray currents causing *electrolysis* (q.v.). This effect is very often noted in the case of an aerial wire where the wire is necessarily exposed to the action of the atmosphere, rain, etc. The effect is particularly important and undesirable where the lead in wire is joined to the aerial.

If the two wires are not soldered securely or at all, corrosion may set in, which will produce in time a high resistance connection and waste the valuable energy of the incoming signals. This is the main point of danger in an aerial system and the best protection is to solder the joint carefully. As a matter of fact the remainder of the wire may corrode to a considerable extent without disastrous effect. In the case of copper, the wire very quickly corrodes when exposed. For this reason insulated wire is sometimes used for the aerial. As the current received by an aerial travels only on the outer surface of the wire (see *Skin Effect*), and a corroded surface is not a particularly efficient conductor, there seems to be some basis for the use of insulated wire for this purpose. Another instance of corrosion is in a soldered joint within a receiving set. All soldered joints should be carefully wiped to remove any trace of *acid flux* (q.v.), which may remain to produce a destroying chemical effect on the wire and cause loss of energy. (See *Electrolysis*, also *High Resistance Joint.*)

COULOMB—The practical unit for electrical quantity. It is defined as the quantity of electricity delivered by a current of one *ampere* flowing for one second. Therefore a *coulomb* of electricity will pass each second in a circuit having one *ohm* of resistance and a pressure of one *volt.* It is also used to express the quantity of electricity which a condenser having one *farad* of capacity will absorb when placed under a pressure of one volt. (See *Capacity, Electro-static, Volt, Ampere Hour, Practical Units, CGS Units.*)

COUNTER ELECTROMOTIVE FORCE—Commonly known as *Counter E. M. F.* It is an opposing electromotive force which tends to resist or act against the original electromotive force. It may be introduced in a circuit to prevent any fluctuation of the original force. (See *Back Electromotive Force*, also *Choke Coil.*)

COUNTERPOISE—A *counterpoise* is generally a second aerial suspended either below the main aerial or to one side of it. It is used more often in transmitting stations in place of the usual ground connection, but is occasionally also used in reception where it is impossible to obtain an efficient ground. (See *Aerial.*)

COUPLE, THERMO ELECTRIC—See *Thermo-Couple.*

COUPLED CIRCUITS—The term generally used to refer to circuits that are joined by *coupling.* (q.v.) In the illustration the *primary circuit* (the aerial ground and tuning devices) is coupled or joined to the *secondary circuit* by *inductive* coupling. That is to say, the signals impressed on the *primary circuit* are transferred to the *secondary circuit* by means of *inductive coupling;* when the lines of magnetic force around the primary coil cut the secondary coil, a voltage is set up in this coil which causes a current to flow in the secondary circuit, and it is then said the coils are "inductively coupled", there being no connecting wires between them. Signals might be transferred to the secondary circuit by any of several means, but in each case the method of joining the two for the purpose of effecting a transfer of energy is referred to as "coupling the circuits." (See *Coupling.*)



Circuit in which primary and secondary are joined by inductive coupling.

COUPLER—See "Coupler—(Loose)" and "Coupler—(Vario)".

COUPLER—(LOOSE)—A tuner used in a radio receiver, consisting of a primary and secondary coil so constructed that the secondary coil slides on rods in and out of the primary coil. When the secondary is entirely within the primary the coupling is said to be "tight," and as the secondary is withdrawn from the primary the coupling becomes "loose," depending upon the distance which the coils are separated.

COUPLER—(VARIO)—Form of tuner used in a radio receiver, having primary and secondary coils arranged in such a manner that the secondary rotates on a shaft within the primary. The degree of coupling is governed by the variation of the angle between the axes of the two coils.

COUPLING—The relation of one coil of wire carrying alternating currents to another in which energy is set up by the first coil. It is used to define the intimacy between the primary and secondary windings of various types of *oscillation transformers, couplers* and *tuning devices.* This transfer of energy may be produced in several ways, as by *inductive coupling, conductive coupling* or *electro-static coupling.* The more common method is to place the primary and secondary coils in close proximity and produce the energy in the secondary through induction. The illustration Fig. 1 shows a simple two slide tuning coil which is divided into a primary and secondary by *conductive* coupling. Here the transfer of energy from the aerial and ground, or primary circuit, to the secondary circuit (detector and phones) is accomplished with little loss of energy as the circuit is through wire conductors. This is also known as *direct coupling.* Now in Fig. 2 a simple form of *loose-coupler* is shown. This device is made in numerous forms, the principle of operation however, being the same in all cases. Here one coil, the secondary in this case, is made to fit into the larger coil which is the primary. The energy flowing in the primary coil induces or sets up a similar current in the secondary by reason of its proximity. The energy in the secondary, however, will not be as great as in the case of Fig. 1 where it is transferred directly through a wire conductor. The coupling shown in Fig. 2 will on the other hand, permit much closer adjustment to the desired signals.



Fig. 1.—Two slide tuner divided into primary and secondary circuits by conductive coupling.



Fig. 2.—Circuit in which primary and secondary are inductively coupled by loose coupler.

The other method is known as *capacitive* or *electrostatic coupling.* This is shown in Fig. 3. Here the secondary coil is not in direct inductive relation to the primary, in fact it might well be almost any distance away were it not for the loss in efficiency due to long connections. The connection between the primary and secondary coils is by means of condensers. The transfer takes place through these and is determined by the setting of the condensers. It will appear that from a standpoint of maximum transfer of energy, the direct or *conductive coupling* system is best. The factor of tuning enters here however, and must be considered. In order to eliminate undesired signals the various systems of coupling are resorted to. It is known that *selectivity*—the ability to tune out undesired signals while receiving the desired signals—is often obtained only at the expense of a certain amount of energy or volume. It is a safe assumption therefore, that if there is any such thing as maximum efficiency in tuning apparatus, it must be a general term covering both selectivity and volume.

Coupling in its various forms is intended to refer not only to receiving circuits but to transmitting circuits as well. Its application in transmitting is covered under the heading *Spark transmission* (q.v.).



Fig. 3.—Electrostatic coupling between primary and secondary by means of variable condensers.

COUPLING COEFFICIENT — The closeness of *coupling* is specified by a quantity representing the ratio of the *mutual inductance* between two coils to the square root of the product of the two *self inductances.* In its practical sense coupling coefficient refers to the inductive relation of two coils. Coupling coefficient is defined as the ratio

$$\frac{Xm}{X.\ X_2}$$

Where Xm is the mutual or common reactance X is the total inductive or capacitive reactance in the primary circuit and X_2 the similar reactance in the secondary circuit. (See *Coupling, Mutual Inductance.*)

COUPLING, DEGREE OF—The extent of relationship between coupled circuits. In a great number of circuits the coupling is arranged so that it may be adjusted either close or loose, as the requirements of the reception may be. Variable coupling may be obtained either by varying the distance between the two coils of a *loose coupler*, or by changing the angle between the coils of a *variocoupler*. (See *Coupling*.)

COUPLING TRANSFORMER—(OSCILLATION TRANSFORMER) — This is the "tuner" of the transmitting circuit. It consists of primary and secondary windings usually of flat strips of copper, or copper ribbon, instead of wire, in order to reduce losses due to *skin effect* (q.v.). The primary coil receives the energy in the form of alternating currents from the generating device; these currents set up lines of force which interlink with the windings of the secondary coil connected in series with the antenna system, and in this manner the energy of the oscillation (alternating) current is transferred to the radiating system (aerial and ground) and thence into space. The purpose of the oscillation transformer is to produce a sharp wave which is readily tuned at the receiving end and causes a minimum of interference. The greater the distance between the primary and secondary coils the more sharp the wave becomes.

A device serving the same purpose in a receiving set, i.e. to enable the receiver to separate sharply the received signals, is sometimes called a receiving transformer, although commonly known as a tuner, coupler, vario-coupler, etc.

C. Q.—Abbreviation of inquiry made in code by a radio telegraph station desiring to communicate with another station. (See *Abbreviations*.)

C. Q. D.—The original Distress Signal (q.v.) established in 1904 by the Marconi Company. The origin of this signal is said to have developed from the use by telegraphers on land lines sending the C. Q. call when they wished everyone on their circuit to listen to the message being transmitted.

The signal C. Q. D. is now obsolete, having been replaced by S. O. S. at the International Radio Telegraph Convention held at Berlin, Germany, in July, 1908.

CRITICAL—A term often used in reference to the tuning qualities of a radio set, and, less frequently, to indicate a *vacuum tube* that *oscillates* too freely. If a receiving set is not critical in adjustment it is said to tune broadly, that is to say, not sharp in tuning. A critical set has a very narrow margin of control in tuning—the particular signals being receivable within only a very few points on either side of their true wave setting on the tuning dials. If a set is difficult to tune it is termed "too critical". This means that it tunes too sharply and it is difficult to get proper results, due to the possibility of passing by signals unnoticed when turning the dials. Obviously there is a middle point wherein a set may be selective and yet not too difficult to tune. If a vacuum tube goes into *self-oscillation* (q.v.) too readily it is said to be critical. This effect is not desired in a tube except in rare instances. (See *Resonance, Tuning, Broad, etc.*)

CRITICAL CURRENT—The current required to bring about some particular effect in an electrical circuit. In radio use, a common example is the exact amount of current needed by the filament of a vacuum tube to bring it close to the *oscillating point* (q.v.) without actually going into oscillation. (See *Critical*.)

CRITICAL POINT OF CURVE—The peak or point of maximum value in a curve showing the relation of any varying values. The illustration shows the curve indicating relation between voltage and signal strength in two types of vacuum tubes. The points marked "Peak" in each curve represent the critical points of the curves at which maximum audibility is obtained, any further increase in voltage not increasing the audibility. (See *Characteristic Curve*, also *Curve*.)



Illustration showing peaks or critical points of curve.

CROOKES, SIR WILLIAM (1832-1919)—English chemist and physicist. Born in London June 17th, 1832, Crookes was educated at the Royal College of Chemistry and afterwards became assistant in the meteorological department of the Radcliffe Observatory, Oxford. In 1855 he obtained a chemical post at Chester.



Sir William Crookes.

Crookes early began that series of brilliant researches which has left its mark on the scientific progress of the nineteenth century. In 1861 he isolated the new element *thallium*, during the investigation of the atomic weight of which he made the discovery of his *radiometer*. This led to his researches on the phenomena of electric discharges through highly exhausted tubes, or *Crookes tubes*. The illustration shows such a tube. When a current is passed through it. cathode particles travel along it. His discoveries on these phenomena led directly to the development by Sir J. J. Thomson of the now generally accepted *electron theory*. (q.v.) In 1883 he began his study of the rare earths, and in 1892 he forecast Radio telegraphy on the strength of Lodge's and Hughes' experiments.



Crookes' tube.

Knighted in 1897, Crookes was awarded the Royal medal in 1875, the Davy medal in 1880, and the Copley medal of the Royal Society in 1904, and the O.M., in 1910. He died in London, April 4th, 1919.

CRYSTAL—A general radio term for a mineral used as a *detector* (q.v.) of radio signals. The Physicist F. Braun noted in 1874 that certain pairs of crystals when arranged so that only a small area of surface was in contact, offered high resistance to the passage of currents in one direction while permitting them to pass readily in the other. This was really the birth of the crystal detector, although radio was not then developed. There are a great many different minerals that will act as detectors for radio signals, some of which operate with a wire, or other metallic contact, others which require a combination of minerals, one in contact with the other. There are also numerous *synthetic crystals* such as *carborundum*. Then again some of the more common natural crystals are subjected to treatment by heat, or other means, to change their nature or to make them more sensitive.

The following crystals are most used in radio reception: *galena, silicon, molybdenum, carborundum, zincite, bornite, chalcopyrite,* and *cerusite*. All of these are taken up under their respective headings. (See *Crystal Detector*, also *Combination Detector*.)

CRYSTAL DETECTOR—A combination of a *crystal rectifier* with contact and supports, used to detect *radio frequency oscillations*. Detectors of this nature are made in a great variety of styles, and use various kinds of crystals. In the more widespread form



Fig. 1. Crystal detector using contact wire, or "cat-whisker."

the crystal detector consists of a crystal with rectifying properties, held in a cup or spring grip and arranged with a contact wire as shown in the illustration Fig. 1. This may be elaborated upon by supplying a series of flat springs to obtain very fine adjustment of the contact. Fig. 2. shows a combination detector, using two crystals, in contact with each other. This form has several advantages over the wire or *cat-whisker* (as the contact wire is called) type, chief among them the fact that it will withstand severe shocks without losing its adjustment. Fig. 3 illustrates a popular form of fixed crystal detector, in which the contact seldom requires adjustment. This type is of advantage providing it can be made sufficiently sensitive. (See *Carborundum, Vacuum Tube,* also *Crystal Receivers.*)


Fig. 2. Combination crystal detector.

Fig. 3. Fixed crystal detector.

CRYSTAL DETECTOR—THEORY OF OPERATION—Theory of operation of a device used to detect radio waves, usually comprising a crystal in combination with a metallic contact, or, in some cases, two crystals arranged to rest against each other. In action this device serves to rectify the incoming signals, that is to say, it changes their nature from an alternating current to pulsating direct current. The incoming waves or signals consist of a series of alternations, the current flowing first in one direction, then reversing and flowing in the opposite direction along the circuit of the receiver. The changes of direction take place many times each second and would not be audible in the head phones in their original state. The crystal, as used in radio reception, has the peculiar property of furnishing a ready path for the flow of current in one direction while offering high resistance to its passage in the other. Now an *alternation* (q.v.) is a rise in current from minimum to maximum in one direction and back to minimum or zero, repeating the process in the other direction. Two of these alternations, one in a positive direction and the other in the negative direction constitute a *cycle.* (q.v.) If the crystal will permit the passage of current in one direction only, it is apparent that only half of each cycle can pass through; the other half of each cycle being lost or blocked out by the action of the crystal.

The illustration "A" gives a graphic representation of the *radio frequency oscillations* as they move over the aerial circuit. The curves above the line show the current in a positive direction while those below the line show it in the opposite or negative direction. If the signals or waves in this state were sent through a telephone receiver or head phone in a radio receiving set no sounds would be reproduced. Then again if the incoming oscillations were continuous, of unvarying strength, the rectified current would merely act on the diaphragm of the phone and hold it in a certain position as long as the signal persisted. This of course would not create any audible or intelligible sounds. If, however, the incoming oscillations were in the forms of groups or trains of waves, in any one of which the successive oscillations were less than the previous ones, the current would be rectified as shown in B and the result would be a series of pulses in the phone as indicated in C. These pulses would occur as often as the trains of oscillations occur (for more complete explanation of the difference between continuous and damped waves, see Damped Waves, also Continuous Waves). It will therefore appear that a *crystal detector* can only be used to receive *damped waves.* When the rectified portion of a damped wave train reaches the phones, the *diaphragm* is depressed and held until the train has died out, at which point the diaphragm is released until another train reaches it. This creates the audible signals and the number of trains occcurring each second will determine the number of depressions of the diaphragm and hence the pitch of the audible signals. (See *Crystal Receiver, Crystal Detectors,* also *Tickler.*)



Rectifying process of radio signals.

CRYSTAL RECEIVERS—A crystal receiver is the complete set of apparatus for receiving broadcast programs or *spark transmission* (signals), employing a crystal as the *detector* or *rectifier.* The set comprises a crystal detector, tuning device and phones, together with the usual aerial and ground arrangement. In its simplest form it may be merely a crystal detector, coil of wire and phones as in Fig. 1.

Fig. 2 shows a more efficient form, using a two slide tuning coil. This method permits closer adjustment of the receiver to the particular signals desired. A still more efficient form is the *inductively coupled* type shown in Fig. 3. This method allows a very close adjustment and considerably reduces interference. The kind of detector to be used in any of the above types of receiver is immaterial as long as it is sufficiently sensitive. Such an arrangement as shown in Fig. 3 is very inexpensive to construct and when used within ten to twenty miles of the broadcasting station gives excellent results. A very simple arrangement for use with a crystal detector is shown in Fig. 4. This circuit uses a standard *variometer* and eliminates the necessity for a *condenser,* thus having only one control in addition to the adjustment of the crystal.



Fig. 1. Simple crystal set with single slide tuner.



Fig. 2. Crystal receiver using double slide tuner.



Fig. 3. Selective crystal receiver with loose coupler for tuning.



Fig. 4. A variometer is used as the tuning element in this crystal set.

CRYSTAL RECTIFIER—A device for changing an alternating current in a radio receiver into a pulsating direct current. This action is fully explained in "*Crystal Detectors (Theory of Operation).*"

CURRENT—A term used in electrical practise to signify the rate at which electricity flows from point to point in a circuit. The current in a circuit may be likened to the water flowing in a pipe. In this case the water would represent the electricity, the force or pressure represents the voltage, the pipe can be compared to the conductor or wire through which the electricity flows, and the current can be likened to the discharge from the pipe over a given period of time, that is the cubic feet of water per second. For practical purposes the unit of current is considered as the *Ampere.* This is the rate of flow of electricity when one *coulomb* (q.v.) passes a given point in the circuit each second. It will thus be apparent that while the ampere is often considered as the amount of current in a circuit, in reality it is the rate of flow of the electricity, the *coulomb* being the definite unit of quantity. Electric current is of course invisible. The only means of determining when there is current in a circuit is by observing its effect and it is always apparent by one or more of a number of effects. For example, if current is flowing in a wire or other conductor and a compass is placed near the conductor in such a position that the axis on which the needle revolves is parallel to the axis of the wire, the needle will be deflected. If the current reverses and flows in the opposite direction in the wire, the needle will be deflected in the opposite direction. The effect of current is also apparent by reason of the heat which it generates in passing through a wire conductor. If the wire is comparatively small and the current correspondingly large, the heat may be sufficient to be noticeable by placing the hand on the conductor. When the current is small, it can be detected by means of delicate instruments. This heating effect is made use of in various types of *ammeters*. The effect of current may also be noted in an incandescent lamp. In this case the current is made to flow through a fine wire inside a globe from which the air has been extracted, and the heat generated by the passing current causes the filament, or fine wire, to glow.

It is a well-known fact that heat causes expansion and this expansion of a fine wire is the principle on which one type of current measuring device operates.

Current is divided broadly into two divisions, *direct* and *alternating*. These two classes may again be separated into several further groups such as *high* and *low frequency alternating*, *continuous* and *pulsating*. Each phase or characteristic of current is taken up more in detail under its particular heading in this encyclopedia. (See *Current, Direction of Flow,* also *Current, Production of.*)

CURRENT, ALTERNATING—A current which does not flow steadily in one direction but changes its direction in the circuit periodically. (See *Alternating Current.*)

CURRENT CARRYING CAPACITY OF WIRE—The amount of current which a wire or other metallic conductor will carry without over-heating. Whenever current flows through a conductor, heat is generated. The amount of heat will be directly proportional to the resistance of the conductor and the square of the current in it. Now the resistance of a conductor depends on its cross-sectional area, length, and also its nature. It is therefore correct to state that the heating will depend on the amount of current flowing and the cross section and length of the wire. Obviously, a large wire will carry more current without over-heating, than will a small wire. Thus, it is necessary when choosing wire for a conductor to carry a certain amount of current, to select a wire of a cross section sufficient to carry the desired amount of current without undue heating.

The following formula for determining the current carrying capacity of various sizes and kinds of wire uses a certain factor T, which is the permissible rise in temperature above surrounding medium—such as air, earth or water. Where d is the diameter of the conductor in inches, T—the permissible temperature rise in degrees centigrade, N the resistance of conductor in ohms per mil-foot at final temperature, and I the current in amperes, then for solid conductors:

$I = \dfrac{K\sqrt{Td^3}}{r}$ and for stranded conductors: $I = 0.85\,K\dfrac{\sqrt{Td^3}}{r}$

K is a *constant* (q.v.) depending upon the condition of the surface of the wire and upon the amount of heat convection due to air currents. Values of the constant K for air differ according to different authorities from 800 to 1000, the former referring to still air and the latter to open air.

Table of current carrying capacities follows:

Wires and Cables, Insulated: Carrying Capacities, in Amperes, allowed by The Regulations of The National Board of Fire Underwriters for Interior Copper Conductors.

(For Aluminum 84 Per Cent of These Currents is allowed.)

Single Conductor Cables or Each Conductor of Multiple Conductor Cables.

A. W. G.	Area in Circular Mils	Table A. Rubber Insulation	Table B Varnished cloth	Table C. other insulation
18	1,624	3	....	5
16	2,583	6	....	10
14	4,107	15	(18)	20
12	6,530	20	(25)	25
10	10,380	25	(30)	30
8	16,510	35	(40)	50
6	26,250	50	60	70
5	33,100	55	65	80
4	41,740	70	85	90
3	52,630	80	95	100
2	66,370	90	110	125
1	83,690	100	120	150
0	105,500	125	150	200
00	133,100	150	180	225
000	167,800	175	210	275
	200,000	200	240	300
0000	211,600	225	270	325
	250,000	250	300	350
	300,000	275	330	400
	400,000	325	390	500
	500,000	400	480	600
	600,000	450	540	680
	700,000	500	600	760
	800,000	550	660	840
	900,000	600	720	920
	1,000,000	650	780	1000
	1,100,000	690	830	1080
	1,200,000	730	880	1150
	1,300,000	770	920	1220
	1,400,000	810	970	1290
	1,500,000	850	1020	1360
	1,600,000	890	1070	1430
	1,700,000	930	1120	1490
	1,800,000	970	1160	1550
	1,900,000	1010	1210	1610
	2,000,000	1050	1260	1670

Varnished cloth smaller than No. 6 may be used by special permission only.

CURRENT, CONVECTION—See *Convection Current.*

CURRENT, CRITICAL — See *Critical Current.*

CURRENT DENSITY—The number of amperes passing through a wire conductor per square inch of area of the conductor. For example, if a conductor is a wire or bar of copper having a cross section of one square inch and ten amperes are passed through it, the current density will be ten amperes per square inch.

CURRENT, DIRECT—Current that flows steadily, and only in one direction. (See *Direct Current.*)

CURRENT, DIRECTION OF FLOW (ASSUMED) — In electrical practice the *assumed direction of flow* of current is often referred to. This refers to the fact that direct current is assumed to flow from the *positive pole* of a battery, or other source of electrical energy, to the *negative pole* and thence back through the battery from negative to positive. This assumed action is shown in the illustration Fig. 1, where the arrows indicate the assumed direction of flow. Now while the current is stated as flowing from positive to negative outside the source, it is the generally accepted theory that the electron stream moves in the opposite direction, or from negative to positive. In other words, the current as we use the term, flows backward along the path of electrons. (See *Electron Flow.*) This reverse action of current and electrons is shown by the illustration Fig. 2 This apparent anomaly


ELECTRONS DRIFT IN THIS DIRECTION
−
+
CURRENT FLOWS IN THIS DIRECTION
CONDUCTOR

Fig. 2. Showing reverse action of current and electrons.

can be likened to a salmon swimming up a rapid. The movement of electrons can be compared to that of the the water in the rapids and while the fish actually swim against the stream, and the electric current flows against the electron flow, the water and the electron stream nevertheless furnish the path of motion in each instance. The reason for the contradiction lies in the unfortunate arbitrary choice of positive and negative poles long before electrons were known. (See *Electron.*)



Fig. 1. Illustration showing the assumed direction of current flow in a dry battery.

CURRENT, EDDY—See *Eddy Currents.*

CURRENT, HIGH FREQUENCY—A current that changes direction many times each second. In radio usage, currents having a frequency over ten thousand cycles per second are considered as *high frequency* or *radio frequency currents.* (See *Frequency, Radio Frequency* also *Low Frequency.*)

CURRENT, HIGH TENSION—Alternate term *High Pressure.* When the voltage, tension or pressure, in a circuit is comparatively low, the current is said to be a low pressure or *low tension current.* When the voltage is high, the current is said to be of high tension or pressure. Thus, as applied to radio usage, a dry cell or storage battery giving, respectively, one and a half and six volts for a certain type, are said to produce low tension or low pressure current. A "B" battery (q. v.) giving from 22½ to 45 volts (the usual value) furnishes *high tension* or *high pressure current.* While there is not a very great difference in voltage between a small "B" battery and an "A" type storage battery, the ratio of voltage to current in a "B" battery is far greater than in the ordinary case of the "A" battery and this must be taken into consideration. In general electrical practice the terms are not so arbitrary, and high tension currents might be taken as those above a pressure of several thousand volts.

CURRENT, LOW FREQUENCY—An alternating current that changes its direction of flow a comparatively few times per second. In commercial electrical work any frequency up to about 500 cycles per second is considered as low frequency current. In radio phraseology *audio frequency* (q.v.) currents are termed low frequency. For ordinary radio practice low frequency may be considered as any frequency below about 10,000 cycles. (See *Oscillation* also *Oscillatory current.*)

CURRENT, OSCILLATORY—See *Oscillatory Current.*

CURRENT, PRIMARY—A current which flows directly from its source, such as a cell or generator. The current obtained from any source through a direct conductive circuit is termed a primary current. (See *Secondary Current,* also *Induced Current.*)

CURRENT, NATURE OF ELECTRIC—As explained under the heading *Current,* electric current is manifest or understood by its effects. It may be apparent through the production of heat or light, by producing mechanical action such as required to operate a bell or move an electric motor, or, again, by producing chemical changes (See *Electrolysis*), and still further in its disastrous effects on the human body when the current has sufficient intensity. Without any actual or visible form of manifestation it can best be understood from the *electron* basis. It will be understood that an *electron* (q.v.) small as it is, contains a charge of electricity. When a sufficient number of electrons are in motion in a conductor (Note: current consists of electrons in motion) the current becomes large enough to be measured. As an instance of this fact a current of one ampere intensity (one coulomb per second) requires that about 10^{19} electrons flow past a given point in the circuit each second. When the electrons are not progressing along a conductor, no current flows in the circuit. If no current is being carried by the conductor, the electrons may move about, but they do not progress along the conductor.

CURRENT, PRODUCTION OF ELECTRIC—An electric current is produced in a conductor by applying an *electro-motive force* (voltage) at points of the conductor or by maintaining a difference of *potential* (q.v.) between two points. In the first example we can assume a metal ring or closed coil of wire through which a magnet is pushed or perhaps in the core of which a magnet is being excited, or in the general sense any complete circuit through which the number of magnetic lines of force are being varied. In the second instance the difference of potential may be due to a *primary cell* (q.v.). Thus, the first case can be understood as referring to any mechanical means of producing current, such as *generators.* The other general method is by use of a *voltaic cell,* that is, by chemical action. There are four important methods of producing an *electro-motive force.* The first is by friction, the apparatus used in this connection being termed a static machine; the second is by chemical action, as a primary or secondary cell; third, by mechanical motion, i.e., *dynamos* and *generators,* and fourth, by thermal action—known as a *thermo-junction* which is the wiring of two unlike metals in a conductory circuit so that by heating one of the points of joining an electric current will be set up in the circuit. (See *Static Electricity, Generator, Thermo Couple,* also *Current and Electro-Motive Force.*)

CURRENT, PULSATING DIRECT—When an alternating current is rectified by means of any device which permits current to pass only in one direction, the resultant current will move only in one direction, hence it is known as a *direct current* but unless both negative and positive halves of the *cycle* (q.v.) are rectified or changed to direct current, the resultant current will appear as a series of pulses in one direction. The most common application of this is found in the case of a *crystal rectifier,* or *detector* as used for receiving radio signals or broadcasting.


AERIAL
ORIGINAL ALTERNATING HIGH FREQUENCY CURRENT
RECTIFIED CURRENT
CRYSTAL
LOWER HALF OF EACH CYCLE NOT RECTIFIED
GROUND
PHONES

Diagram showing how crystal detector converts alternating high frequency current into pulsating direct current.

When the incoming waves, or high frequency *oscillations* (Q.v.), are impressed on the detector, due to its peculiar properties they can only pass through it in one direction. In other words, granting that the incoming signal, or current, reverses its direction a great many times each second, it will be obvious that at any instant in the *cycle* (q.v.) current is moving in a certain definite direction, as from positive to negative, or vice versa, as stated, due to the peculiar properties of the detector the incoming signal current can only pass through the detector when the current is flowing in the correct direction. This means that only half of the *wave* (q.v.) is passed through and rectified. The result is a series of direct current surges through the balance of the circuit, each surge of current being followed by a space or time interval while the opposite half of the *cycle* or opposite *alternation* (q.v.) is blocked by the uni-directional nature of the crystal. These surges are then audible in the *head phones,* as they will actuate the *diaphragm* (q.v.) whereas a high frequency alternating current such as the original impulse from the broadcasting station would be inaudible. For a more complete explanation of this action see Rectifying action of crystal detector. (See also, *Rectifier, Full Wave Rectification and Rectifying Tube.*)

CURRENT, SECONDARY—A current produced by a *primary current* (q.v.) acting on a *secondary circuit* which does not receive its energy by direct connection with the primary source. The illustration shows both primary and secondary currents and the manner of production. It will be understood that the primary current in this case must be a varying current. (See *Induced Current,* also *Inductive Coupling.*)


PRIMARY CURRENT
INDUCED OR SECONDARY CURRENT
A.C. GENERATOR
NO ACTUAL CONNECTION BETWEEN PRIMARY AND SECONDARY CIRCUITS

Illustration showing primary and secondary currents and method of production.

CURRENT, THEORY OF ELECTRIC—Under Electromotive force it will be explained that voltage or pressure is the result of a difference of potential (the power possessed by a charge of electricity for doing work) between two points in a conductor. Electric current will flow from the point of higher pressure or *voltage* to the point of lower pressure, the flow continuing as long as the difference is maintained. This action is the same as with water, which will always seek to move from a high point to a lower point. The flow of current is thus an effort to equalize the two *potentials.* (See *Current, Assumed Direction of Flow,* also *Pressure and Voltage.*)

CURVE—A straight or curved line showing the relation between various electrical phenomena or the characteristics (relation of changing values) of an electrical instrument. (See *Characteristic Curve,* also *Sine Wave.*)

CURVE OF SINES—A curved line representing the vibration of a body that oscillates like a pendulum. The illustration shows a *curve of sines* which may be used to represent an alternating current. (See *Alternating Current,* also *Sine Wave* and *Simple Harmonic Vibration.*)



Sine curve.

CUT OUT—An electrical device to interrupt the flow of current through any particular piece of apparatus or instrument, either automatically or by hand; a switch.

CYCLE—In electricity, a period of time during which certain changes take place in an *alternating current,* (q.v.) the same changes occurring again in each successive cycle. We can imagine an alternating current as travelling along a wire in the form of a wave, one half of the wave being in one direction and the other half being in the opposite direction. That is to say, the current flows from positive to negative for one half of the cycle and then in effect, flows from negative to positive the other half of the cycle. (It will be understood that actually current always flows in the same direction, but the action of alternating current is due to a reversal of polarity at the source.) The difference between direct and alternating current is that, in the case of direct, the polarity always remains the same at the source and hence the direction of flow of the current is always in one direction, whereas with alternating current, the polarity changes twice each cycle due to changes at the source, and thus it flows in one direction for a certain fixed period, then reverses and flows in the opposite direction. In the illustration the current is shown as a *sine wave.* (q.v.) We assume that this represents an alternating current of 110 volts pressure such as in the average house lighting system. Now we consider the wave as a circle. The current flows in a positive direction toward its maximum value and at the 90 degrees it has reached the positive maximum. It then falls back to zero at 180 degrees and reverses, rising to maximum on the negative side, which it reaches at 270 degrees. It then falls back to zero at 360 degrees having completed a cycle or two alternations. The operation is repeated over and over a certain number of times each second. Thus, the rise and fall from A to B or 180 degrees is one *alternation,* the rise and fall from B to C is another alternation, the two alternations, one positive and one negative making a complete cycle. If sixty of these cycles occur each second we say that the frequency (q.v.) is sixty cycles. (See *Alternating Current, Phase, Sine Wave.*)



Curve showing action of 110 volts alternating current during one cycle.

CYMOMETER—The name given a type of *wave-meter* designed by Dr. J. A. Fleming. It is used to measure the wave-length of oscillatory (vibrating) circuits. (See *Wave-Meter.*)

CYMOSCOPE—A term used to designate any instrument which enables one to see the effect of electrical waves or to detect their presence. The original form was merely a loop of wire not completely closed as shown in Fig. 1. When held close to a transmitter of short waves a small spark will pass between the ends of the loop providing the *wave-length* is properly adjusted. This was the form used by Hertz (the discoverer of electro-magnetic waves which form the basis of radio telegraphy and telephony) in his early experiments. The more modern form is shown in Fig. 2 where a small lamp is made to light by holding the loop close to the transmitter. A complicated arrangement used to acually see the waves and study their form is called the *Oscillograph.* (See *Oscillograph,* also *Cathode Ray Tube.*)



Fig. 1. Early type of cymoscope used to indicate resonance in a circuit.



Fig. 2. More modern form of cymoscope.

D

D—The symbol of *electric displacement* (q.v.); also occasionally used as a symbol for diameter in electrical calculations.

DAMPED OSCILLATIONS — Electrical oscillations which die away, each succeeding oscillation in a group having lesser *amplitude* (q.v.) or strength than the preceding one. (See *Damped Waves.*)

DAMPED WAVES—Radio waves in the form of successive trains or groups, in each of which the amplitude or strength decreases with each successive wave. When electrical oscillations are caused by a single impulse, they do not continue indefinitely, but decrease in amplitude or die away. Thus, if oscillations are created in an antenna or other circuit by a discharge from a *condenser* (see spark discharge), each electric spark creates a train of oscillations which die away more or less gradually. Fig. 1 shows a pendulum which is given a momentary impulse. Now as this source of power is only momentary the pendulum will not swing from A to D indefinitely. If the first swing under the impulse carries the pendulum the entire distance A to D, the next swing will cover a lesser arc and so on until the movement has died out altogether.

Now in Fig. 2, the graphic illustration of a train of *damped waves* shows that each crest is a little lower than the one preceding it and after a short period the waves have died out alto-



Fig. 1. Pendulum coming to rest after being given a momentary impulse.



Fig. 2. Train of damped waves.

gether. These curved lines may be considered as an illustration of the path taken by the pendulum in its motion as shown in Fig. 1. The decrease in amplitude of one crest over that preceding is known as the damping, and the naperian logarithm of the ratio of amplitude of any oscillation to the one preceding it is known as the *logarithmic decrement.*

If the impulse of force causing the oscillations is steady—not intermittent—the result will be a sustained series of oscillations that will continue at constant strength or amplitude until the exciting force is withdrawn. Thus, in the case of the pendulum, we can very easily keep exciting it by an evenly exerted force and so insure that the swings will continue without diminishing, as in the case of a momentary impulse. Oscillations or waves that have constant amplitude are known as *Continuous Waves, Undamped Waves* or *Sustained Waves.* (q.v.) (See also *Decrement, Logarithmic;* also *Naperian Base.*)

DAMPING—A progressive decrease in amplitude or strength. (See *Damped Waves, Damping in Instruments.*)

DAMPING COILS—*Short circuited* (q.v.) coils used in electrical apparatus for the purpose of causing damping (i. e., decrease in the intensity of electrical oscillations). The reaction of induced currents in the shorted coil creates the damping effect. (See *Damping.*)

DAMPING DECREMENT—See *Decrement, Logarithmic.*

DAMPING FACTOR—The product of the *logarithmic decrement* (q.v.) and the frequency (rate of alternation) of a damped alternating current. (See *Decrement,* also *Amplitude.*)

DAMPING IN INSTRUMENTS—The term damping is applied in a mechanical sense as in the case of the needle of a measuring instrument such as a *galvanometer.* (q.v.)

In a delicate instrument for measuring current the needle is controlled by the current through the instrument, and when this current is withdrawn the needle is brought back to the neutral position by a fine spring. Now, unless some precaution is taken the needle will have a tendency to swing or vibrate when measurement is being taken. Various devices are used to bring the needle quickly to rest without undue vibration. If the needle comes to rest almost immediately it is said to be a highly damped or *dead beat instrument,* because the oscillations or vibrations die out rapidly the same as in the case of damped waves.

There are two principal methods of damping instruments. When the instrument is of the moving coil type, the coil is generally wound on a light aluminum frame which is mounted between the poles of a permanent magnet. A soft iron core fills the gap between the two poles, allowing space for free movement of the coil. The result is that the metal frame carrying the coil moves through a very strong *magnetic field* and *Eddy currents* (q.v.) are set up in the frame and serve to damp its motion. The other common method is to have a light metallic vane carried by the pointer in its motion and moving in an air chamber to stop vibration. While damping is highly essential in a measuring instrument, too high a degree of damping is not advisable. If there is a very slight tendency on the part of the needle to vibrate, it permits the operator to determine whether it is swinging freely. (See *Voltmeter, Wattmeter.*)

DAMPING MEASUREMENT—See *Decrement, Logarithmic.*

DAMPING WAVES—Term commonly used to denote the gradual decrease in amplitude of a train of oscillations as in radio transmission. If the oscillations persist at constant amplitude or strength, each oscillation being equal in amplitude to the one preceding, there is no damping. When the amplitude of each successive oscillation is less than that of the preceding one there is said to be damping and the oscillations will die out entirely, at a rate dependent on the degree of damping. If the oscillations die out very rapidly they are said to be highly damped; if they die out slowly the damping is said to be feeble.

DANIELL'S CELL—A two fluid *voltaic cell* containing a zinc plate immersed in dilute sulphuric acid, and a copper plate in a saturated solution of copper sulphate; the two solutions being separated by a porous cup. This cell has a constant voltage and shows only slight polarization. Was formerly much used in telegraph work.

D'ARSONVAL GALVANOMETER—A type of galvanometer in which a coil carrying the current to be measured is suspended in a *fixed magnetic field.* (See *Galvanometer.*)

DASH—The long stroke used in *Morse* and *Continental Code.* It is considered as equivalent in length to three dots. (See *Code.*)

D. C. C.—The customary abbreviation for double cotton covered wire.

D. C.—The abbreviation commonly used for *direct current.* (q.v.)

"D" COIL—Occasionally known as Figure Eight coil. A form of inductance, used particularly in tuned radio frequency circuits. The windings are in the shape of a figure eight, either in pancake form (flat wound) or wound on a slotted tube. Owing to the peculiar arrangement of the windings these coils have very little external field and thus can be used in radio frequency amplifiers without the usual oscillating due to conflicting fields. (See *Field, Inductance, Radio Frequency Coils.*)

DEAD BEAT INSTRUMENT—A measuring instrument arranged so that the needle comes quickly to rest with little or no vibration is said to be *dead beat* or highly *damped.* (See *Damping in Instruments.*)

DEAD CELL—A *cell* which has been discharged. (See *Cell.*)

DEAD CRYSTAL—A crystal used in a *crystal detector* (q.v.) that has lost its sensitivity. Very often a crystal becomes dirty or oily from contact with the fingers. In some cases they can be brought back to usefulness by cleaning with alcohol, or if the crystal is dead through causes other than dirt on its surface, it may be broken to present a new surface and thus find a new sensitive spot.

DEAD END EFFECT—The effect on a receiving circuit (oscillatory circuit) resulting from unused turns of wire in a coil. In the customary tuning coil or tapped coil a certain portion of the wire is not in use and this idle section, being in metallic connection with the main portion, but not actually in use, acts as a miniature oscillatory circuit. This tends to reduce the efficiency of the tuning unit as a whole. Dead end effect may be eliminated by using the entire coil at all times, doing the tuning solely by the variable condenser, or it may be reduced by the use of a *dead end switch* (q.v.). (See *Tuning Coil.*)

DEAD END SWITCH—A switch used to cut out unwanted turns of wire in a coil in order to eliminate or reduce the *dead end effect* (q.v.). Such a switch is generally arranged so that instead of taps being taken from various points on the coil, the winding is actually in sections and the switch blade connects into the circuit the desired number of sections.



Dead end switch.

DEAD SPACE—In the case of *beat heterodyne* reception if the two frequencies are brought together or the difference is very slight there will be no beat. This space where the two frequencies are identical, or very nearly so, is known as the *dead space.* (See *Beats,* also *Heterodyne.*) The beat resulting from the superposition of two waves differing in frequency is the difference or the sum of the two frequencies. For instance, if two waves are present in the same circuit, of 1,000 and 1,005 kilocycles respectively, the two beat frequencies will be 5 and 2,005 kilocycles. If, however, the two frequencies are made identical, the difference between the two will be zero, and the sum of the two will be twice the original frequency. In the one case, where we take the difference of the frequencies, the beat note is zero, or there is no beat note at all; in the other case, where we add the two frequencies, the resulting frequency is the *harmonic* (q.v.) of the original frequencies, which is the same as an octave in music. In the present instance, this note will not be heard at all as it is above the range of audibility.

DECADENT WAVE—A damped wave. A wave, or oscillation, in a train of *damped waves* (q.v) which is of lesser amplitude or strength than the one preceding it. (See *Damped Waves,* also *Undamped Waves.*)

DECAY OF CURRENT—The gradual dying out of current in an *inductive circuit* (q.v.) after the *impressed potential* has been removed. The presence of inductance in a circuit causes the current to lag in time behind the voltage producing it. As a result, when a highly inductive circuit is broken by opening a switch or by other means, the current still tends to flow for a short interval, and the *induced voltage* in the circuit may become very high. This is the reason why a spark often occurs when the switch in a highly inductive circuit is opened. As a result the current decays gradually after the impressed voltage is removed.

It will be noted that the *decrement* (q.v.) or the rate of decay of the oscillations directly affects the number of oscillations in the wave train that will be useful in transmitting signals. For instance, if a certain oscillation in the figure should represent the smallest voltage that will operate a detector, it is evident that all oscillations in the wave train that have smaller amplitudes will be useless. Consequently, the lower the decrement of the wave, the greater will be the number of oscillations before the amplitude becomes too small for useful purposes. This likewise means that a greater amount of the energy in the wave can be utilized.

DECOHERER—In the type of detector, now obsolete, known as the *coherer*, the incoming signals caused the particles of nickel and silver filings in the glass tube of the device to cohere or cling together. (See *Coherer.*) In order to place the coherer in its original state after each impulse, it was necessary to have some means of separating the particles. These were known as *decoherers* and were in many different forms, some as separate attachments, others as a part of the detector or coherer. (See *Detector.*)

DECOMPOSITION, ELECTROLYTIC—The decomposition of chemicals taking place in a cell due to the action of the electrolyte. (See *Cell*, also *Electrolyte.*)

DECREMENT—A term used to indicate the rate of decay or dying out of an electrical oscillation that is subject to *damping.* (q.v.) In the illustration is shown a series of damped waves. It will be noted that the distance from zero to the crest of wave (C-2) is less than the one preceding it (C-1). This distance represents the amplitude and the ratio of any amplitude to the one preceding it is constant, that is the decay or decrease in amplitude is constant. The *Naperian Logarithm* (q.v.) of the ratio—of one wave to the one preceding it—is called the *logarithmic decrement.* The damping of a train of waves is an important consideration as it affects the tuning qualities to a great extent. This is covered by a U. S. Government Statute Concerning Transmitting Stations, decreeing that the logarithmic decrement per complete *oscillation* must not exceed 0.2, which means that for each single spark discharge from the transmitter there must be not less than 24 complete oscillations in the *antenna system.* (See *Oscillations, Damping, Naperian Logarithm, Sharp Wave.*)



Damped waves gradually dying out.

DECREMETER—An instrument used to measure the *decrement* or degree of damping in an oscillatory current. Such meters are made in several different forms. Some types are direct reading in terms of the logarithmic decrement, while others require mathematical reduction from the readings of a dial. All decremeters operate on the basis of comparison of the resonance current in a tuned circuit with that in a circuit out of tune by a known or unknown percentage. (See *Logarithmic Decrement*, also *Damping.*)

DE FOREST, DR. LEE—Electrical engineer; b. Council Bluffs, Ia., Aug. 26, 1873. Grad. Yale (Sheffield Scientific), Ph. B., 1896; Ph. D., 1899. Inventor De Forest system wireless telegraphy and founder Am. De Forest Wireless Telegraph Co.; system originally adopted largely by U. S. Govt.; demonstrated to the British, Danish, German, Russian and Indian Govts., first used by the U. S. Signal Corps in the war manoeuvres and inst. in Alaska. 1905 invented the Audion or three-electrode vacuum tube. 1906-09 was the pioneer in Radio Telephony. First to broadcast music and opera. 1908 equipped the 24 battleships and destroyers of Admiral Evans for their historic round-the-world cruise. 1913 incorporated De Forest Radio Tel. & Tel. Co., which developed the audion amplifier and oscillator for commercial purposes. These De Forest devices completely revolutionized the radio art and made possible the Bell Tel. Transcontinental System. He was the father of radio broadcasting and all radio broadcasting apparatus is built upon his audion inventions. Since 1919 he has devoted his attention to the phonofilm, photographing sound waves directly on motion picture film. Pres. of the De Forest Phonofilms, Inc.; Dir. of De Forest Phonofilms, Ltd., London. 1921, Awarded Cross of Legion of Honor by the French Govt. in appreciation rendered by audion to the Allies during the war. 1922 awarded Elliott Cresson medal by Franklin Inst. 1922 awarded medal by Inst. of Radio Engineers. Fellow American Inst. of Elec. Engineers. Fellow Inst. of Radio Engineers. Mem of N. Y. Elec. Society; mem. of Nat. Geog. Soc.

Dr. Lee De Forest.

DE FOREST COILS—A type of coil named after *Lee De Forest* (q.v.). The wires are wound in a diamond shaped pattern in such manner that the turns of one layer cross the turns of the preceding layer at an angle, thus making the *distributed capacity* (q.v.) very small compared with the capacity of other types of coils. (See *Honeycomb Coils.*)

DEGREES, ELECTRICAL—In an alternating current curve each complete oscillation or cycle is shown as two loops, one above the line representing time, and the other below it, the entire cycle being considered as 360 *electrical degrees.* It is possible in this manner to show relations between current and voltage phases, amplitude at any point, etc. (See *Alternating Current*, also *Sine Wave.*)

The idea of electrical degrees comes originally from the *elementary electric generator*, with two-slip-rings taking off the alternating current, and having only two poles. During one-half revolution of the armature turns, the current increases from zero to a maximum and then back to zero again. During the other half revolution the current increases in an opposite direction from a zero value to maximum and then back to zero again. The curve shown in the figure represents the current variation during the complete revolution, a crosssection of the rotating armature wire being shown at A. The angles indicated on the line BC are laid off to any convenient scale, and the intersection of the ordinates from these points with horizontals drawn from the circle as shown, give the points on the curve.



Curve representing current variation during one revolution of the armature of a generator.

The same ideas hold when the generator has more than two poles; in this case a full 360 electrical degrees is taken to represent the armature motion from across two adjacent pairs of poles, so that a complete cycle of voltage or current is generated. In a four pole machine, therefore, a full revolution of the armature could be represented by 2 x 360 or 720 electrical degrees. This corresponds to 2 complete cycles. Or, looking at it the other way, 360 electrical degrees would represent a half revolution of the armature wire.

DEIONIZATION—The action of returning a mass of gas that has become *ionized* (breaking up of the atoms of gas into positive and negative ions being the elements to which and to whose motion, under the action of electric forces, is supposed to be due their electric conductivity) to its original state. In the case of a *spark gap* (q.v.) the ionization creates a conductive path which remains after the actual spark has passed, thus preventing sharply defined oscillations. There are various methods of deionization, including cooling, absorption, air-blast or magnetic field, all tending to deionize or place the spark gap in its previous condition to prevent an arc from following the discharge. This action is also known as *quenching.* (See *Quenched Gap.*)

DELTA—The fourth letter in the Greek alphabet. The capital letter delta (Δ) is used as a symbol for delta connection of *three phase alternating current generators or transformers.* The small or lower case delta (δ) is used as a symbol for *Logarithmic decrement.* (See *Decrement, also Delta Connection.*)

DELTA CONNECTION—Δ In a three phase *alternating current generator,* where three coils are mounted symmetrically around a shaft rotating in a *magnetic field,* the connection or grouping of the windings is called *delta* after the Greek letter which the grouping somewhat resembles. The illustration shows delta grouping in a three phase system. The sum of the instantaneous Electromotive Forces of the three coils is zero, or in other words the sum of the Electromotive Forces of any two coils is equal and opposite to that of the other coil, the *line voltage* thus being equal to the *phase voltage.* (See *Alternator, Polyphase.*)



Delta grouping in a three phase system.

DEMAGNETIZATION—The act of returning a body to an unmagnetized state or of reducing the degree of *magnetization.* In the case of phones used in radio reception the permanent magnets are often weakened or *demagnetized* by connecting them in the *electron-tube circuits* in the wrong way. (See *Magnetization,* also *Telephone Receiver.*)

DENSITY, CURRENT—See *Current Density.*

DENSITY, FLUX—See *Flux Density.*

DENSITY OF ELECTROSTATIC CHARGE—The *electrostatic charge* per unit area. (See *Electrostic Charge,* also *Condenser.*)

DEPOLARIZATION—In an electric cell hydrogen bubbles form on the surface of the positive electrode and unless some arrangement is made to counteract this effect, the usefulness of the cell will soon be impaired due to the insulating action caused by this film of gas, known as *polarization.* Usually some means of oxidizing is employed to act upon the hydrogen as fast as it is produced on the positive electrode, thus preventing or reducing the effect of *polarization.* (See *Cell,* also *Polarization,* and *Depolarizer.*)

DEPOLARIZER—The oxidizing agent or other means used in a cell to counteract the effect of polarization. Bichromate of potash or peroxide of manganese is commonly used for this purpose. (See *Dry Battery,* also *Polarization.*)

DETECTOR—A device for converting oscillating currents of high frequency (radio waves) into a form suitable for operating a telephone receiver or sensitive measuring instrument. It is often referred to as a *rectifier,* because it serves to change the incoming currents from *alternating* to *pulsating direct currents. Detectors* vary in type and efficiency, ranging from the now obsolete *coherer,* to the modern sensitive *regenerative vacuum tube.* The different types of detectors are taken up under their various headings. (See *Crystal Detector, Vacuum Tubes, Electrolytic Detector.*)

DETECTOR CIRCUIT—That part of the circuit in a radio receiver which contains the *detector* (q.v.). The *detector circuit* may be closely coupled to the balance of the receiving circuit by means of a tuning coil or it may be inductively coupled by using a variocoupler or loose coupler. (See *Coupling*).

DETECTOR, DAMPED WAVE—Any special type of detector, such as a crystal, etc., used for reception of *damped waves.* (q.v.). (See *Tikker,* also *Heterodyne,* and *Vacuum Tube.*)

DETECTOR, VACUUM TUBE—The *vacuum tube* used as a *detector* of *radio frequency* (*high frequency*) *oscillations.* A vacuum tube may be used to change or rectify the high frequency alternating currents received at the aerial to *pulsating direct currents* (q.v.) capable of operating a telephone receiver or recording device. Formerly vacuum tubes were made for an individual purpose, such as *radio frequency amplifier, audio frequency amplifier, or detector,* the amplifier tubes being highly exhausted and the detector tube having a low vacuum and requiring critical filament adjustment. Of late tubes have been developed to such an extent that no special tube is necessary for the detector circuit, all being adaptable for almost any purpose. Fig. 1 shows the ordinary circuit for a vacuum tube detector. This method is not much used now since the advent of regeneration, except where stages of radio frequency amplification are used ahead of the detector to amplify the incoming signals. In this case incoming signals are impressed on the grid "G" and the slight variations of potential at this point control comparatively large currents at the plate "P," actuating the telephone "T." (See *Vacuum Tube, Theory of Detector Action.*)



Fig 1. Non-regenerative vacuum tube circuit.

Used in this manner the tube is a considerable improvement over the crystal detector in point of sensitivity. However, by means of regeneration, the sensitivity may be increased many times. Fig. 2 shows a simple *regenerative circuit.* Here the unrectified currents passed through to the *plate* of the vacuum tube are fed back by means of the coil L2 and by being impressed again on the *grid,* further amplification can be attained. (For complete explanation see *Regenerative, Theory of Operation of Vacuum Tube, Detector, Pulsating Direct Current,* also *Crystal Detector.*)



Fig. 2. Simple regenerative circuit.

DETUNING—The opposite of *tuning* (q.v.) The process of varying the effective inductance or capacity or both, to throw the radio receiver out of resonance with the particular signals to which it is tuned. This may be done to decrease the volume of the signals or it may be employed to eliminate or reduce interference from some undesired signals. For example, a station operating with a wavelength of 400 meters might interfere with reception of a station operating on 360 meters, providing it has sufficient power, or the receiver is not particularly selective. If the radio receiver is detuned slightly below 360 meters, the desired signals will still come in, though at lesser volume, but the interfering signals will be lost entirely. Tuning is the act of *producing* resonance and detuning is the act of *destroying* resonance. In the case of a *heterodyne receiver* (q.v.) the heterodyne circuit is slightly detuned from the incoming oscillations, thus producing a difference in frequency or *beat frequency* (q.v.). (See *Resonance,* also *Dead-space.*)

DIAGRAM—A system of lines drawn to represent the circuit or connections for radio receivers or transmitters or associated apparatus, etc. Diagrams may be in any of several forms, the two common methods being known as schematic and perspective. In the schematic form, symbols are generally used to represent the various pieces of apparatus, whereas in the perspective form, drawings of the apparatus are used. Fig. 1 illustrates a typical schematic diagram of a simple crystal receiver. Here the tuning coils, de-



Fig. 1. Schematic diagram of a simple crystal receiver.

tector, phones and so on, are shown in the form of symbols. Fig. 2 shows the same circuit in perspective form, with the tuning coil and other parts actually pictured. Diagrams may be used to show connections for any electrical or radio circuits or for individual parts of instruments. (See *Hookup.*)



Fig. 2. Showing in perspective form the circuit given in Fig. 1.

DIAL—Devices used to control the movement of condensers or other moving parts of radio apparatus. Most dials are made of a composition such as Bakelite or hard rubber; some are made of metal. The periphery is generally spaced off in numbers from 0 to 100 or 180, for purposes of keeping a record of the positions at which the various stations are received. Dials may be arranged to have the readings refer to definite values by means of *calibration* (q.v.). (See *Dial Vernier.* See *Log.*)

DIAL, VERNIER—A term incorrectly applied to a dial arranged with slow-motion linkage in order to permit very fine adjustment. The illustrations show two types of vernier dials. Vernier dials are generally used on *variable condensers* and occasionally on other instruments, where close adjustment is necessary. They are particularly useful in the case of a *Super-Heterodyne receiver*, the oscillator control being critical, and the wavelength control as well, in certain cases. (See *Dial*, also *Critical.*)



This dial utilizes the slip tooth principle. 5 is the main dial. 6 turns the slip gears (3) and (4), which cause 2 to turn. 2 is mounted on the shaft (1A) fastened in the main dial (1). 5 is the scale, fastened to the condenser shaft.



A simple vernier dial using a pinion and internal rack.

DIAMAGNETIC MATERIAL—Substances not readily susceptible to *magnetism*. If a substance does not pass magnetic lines of force, but rather is repelled by a magnetic pole, it is said to be *diamagnetic;* its permeability, or ability to permit magnetism to pass through it, is considered negative or less than unity (air). Diamagnetic substances are apparently repelled from the poles of a magnet. If placed in a magnetic field they have a tendency to diminish the *magnetic induction* (q.v.). (See *Paramagnetic*, also *Permeability.*)

DIAPHRAGM—A thin disk, generally of soft iron used in *telephone receivers* and *microphones* (q.v.) to either produce or detect electrical pulsations by means of vibrations caused by an *electromagnet*. Variations in the current through the electromagnet cause corresponding vibrations in the diaphragm. While the common type of diaphragm is made of soft iron, there are numerous other materials used. Certain alloys have higher permeability, and therefore are more responsive to the attraction of the magnet. In one type of telephone receiver that is particularly sensitive, there are two diaphragms—one that is actuated directly by the electromagnet under the influence of a varying current and another of thin mica, coupled to it by a fine wire. Another type employs a small iron armature suspended on a pivot, and attached to a mica diaphragm by means of a delicate lever, at right angles to the armature. The vibrations of the armature in the magnetic field of the magnets are communicated to the diaphragm by means of this lever. (See *Baldwin Receiver.*) Another type is of metal with fine corrugations and still another is a mica or parchment disk with a piece of soft iron in the center. (See *Microphone, Telephone Receivers.*)

DIAPHRAGM, CARBON—A phone diaphragm in the form of a thin carbon disc. (See *Diaphragm.*)

DIELECTRIC—This term is rather broadly used in electrical work to indicate a non-conductor or *insulator.* A dielectric may be a solid, liquid or gas and is generally employed to separate two conducting surfaces. The most common instance of the application of a *dielectric* is in the case of a condenser. Here the plates are separated by a dielectric material, the nature of this material depending on the particular type and purpose of condenser. A *variable condenser* for receiving purposes generally employs air as the dielectric. That is, the two sets of plates are kept from actual contact while one is being rotated, by an air space. In *fixed condensers* the dielectric is usually waxed paper, mica, glass, oil or compressed air, depending on the purpose for which the condenser is to be used and the dielectric strength necessary. While we refer to a dielectric as a non-conductor or insulator, there is actually no dividing line between conductors and insulators, practically any dielectric permitting passage of a certain amount of current under the proper conditions. If a substance is a very good insulator it is said to have good dielectric properties, while one that is a poor insulator and permits leakage of current is a correspondingly poor dielectric. (See *Insulator, Conductor, Resistance*, also *Dielectric Coefficient and Constant.*)

DIELECTRIC ABSORPTION—The tendency of the dielectric in a condenser to apparently absorb a certain amount of the power applied to it. When a condenser is charged by a direct current source such as a battery, the instantaneous charge is often followed by a small charge or flow of current that steadily decreases as it flows into the condenser. This additional charge is in effect absorbed by the dielectric of the condenser. The reverse effect is obtained when the condenser is discharged, the instantaneous discharge being followed by a steadily decreasing additional discharge. It will be apparent, then, that if the condenser is charged from an *alternating current* source, such as by *radio frequency currents*, the dielectric will show a tendency to withhold a certain part of the charge, and as the charging and discharging goes on rapidly due to the rapid reversals of the current (see *High Frequency Alternating Current*), the dielectric will continue to hold back this portion of the power as long as the charging and discharging process persists.

This loss, due to the absorption in the dielectric, must not be confused with the losses due to faulty dielectric materials, wherein a certain portion of the current is allowed to leak away by conductance through or on the surface of the insulator. *Dielectric absorption* is often referred to as *dielectric viscosity* or *hysteresis* because of its similarity to viscosity in liquids. Viscosity is the property possessed by liquids to resist deformation. The usual method of measuring viscosities is by measuring the time taken by a known volume of the liquid, at a known temperature, in flowing through an aperture of known form and dimensions under a known pressure. Thus tested, water will flow rapidly, while cylinder oil is very sluggish, and hence is said to possess great viscosity. (See *Condenser*, also *Dielectric.*)

DIELECTRIC COEFFICIENT and CONSTANT—The specific *inductive capacity* of a dielectric. Generally speaking, its properties to act as a *dielectric.* In the *Centimeter Gram Second system* (q.v.) the *inductive capacity* and the *dielectric constant* are numerically equal, the constant being the dielectric value of the material as compared with air at ordinary pressure taken as the standard (1). The table of constants for the more important dielectric materials follows.

It will be seen that glass, oils and mica have the highest values, for which reason they are widely used. (See *Specific Inductive Capacity, Dielectric*, also *C. G. S.*)

TABLE OF DIELECTRIC CONSTANTS

Dielectric	*Constant*
Air at ordinary Pressure (Taken as the Standard)	1.000
Manila Paper	1.50
Celluloid	1.555
Parrafine (clear)	1.68 to 2.32
Beeswax	1.86
Parrafine Wax	1.9936 to 2.32
Parrafined Paper	3.65
Hard Rubber (Enonite)	2.05 to 3.15
India Rubber (pure)	2.22 to 2.50
Gutta Percha	2.46 to 4.20
Shellac	2.74 to 3.60
Olive Oil	3.00 to 3.16
Glass (Low Frequency value)	3.25 to 4.00
Glass (High Frequency value)	4.21
Mica (Pure Sheet)	4.00 to 8.00
Porcelain	4.38
Castor Oil	4.80
Flint Glass, very light	6.57
Flint Glass, light	6.85
Flint Glass, very dense	7.40
Flint Glass, double extra dense	10.10

DIELECTRIC CONSTANTS—See *Table of Constants* under *"Dielectric Coefficient* and *Constants."*

DIELECTRIC HYSTERESIS—When the *electric field* in a dielectric material is varied rapidly, as when the condenser is charged by *high frequency currents*, heat may be generated. This is due to *dielectric hysteresis which is* synonymous with *dielectric absorption* (q.v.)

DIELECTRIC STRENGTH—When an electric field is established in a dielectric, that is to say, a charge is applied to a condenser, and the field attains a certain intensity, the dielectric ceases to be an insulator and becomes, in effect, a conductor. This condition generally is accompanied by a puncturing of the dielectric material. When the charge applied to a condenser is too high the spark will burn through the dielectric and the condenser is then said to have broken down. In some cases the condenser may be permanently ruined by this action, and in others, the dielectric may be conductive at a certain voltage, while remaining effective as long as the voltage is held below the safety point. The particular voltage (critical voltage) or field intensity at which the breakdown of the dielectric occurs is called the dielectric strength of the material. (See *Dielectric*, also *Table of Dielectric Strength.*)

DIFFERENCE FREQUENCY—The frequency of oscillations produced by superposing oscillations of one frequency on oscillations of a different frequency. In Super-heterodyne receivers the action is based on the production of a difference or beat frequency. If the incoming oscillations from the antenna are combined with oscillations of a different frequency produced locally in the receiver, a new series of oscillations will be produced, these oscillations having a frequency numerically equal to the difference in frequency between the other two sets of oscillations. (See *Beat Frequency*, also *Super-Heterodyne.*)

DIODE—A thermionic vacuum tube having only two *electrodes*, namely *filament* and *plate*. The original vacuum tubes were known as *Fleming Valves* and contained a hot filament and cold plate but no grid as found in the three element vacuum tube now in general use. Several types of *diode* are still in use as detectors, their chief value lying in the fact that they require no careful adjustments as in the case of a *crystal detector*. (See *Triode, Vacuum Tube*, also *Fleming Valve.*)

DIPLEX RECEPTION OR TRANSMISSION — The simultaneous reception or transmission of two series of signals by or from a single operating station. The systems are so arranged that two messages may be sent or received at the same time without interfering with each other. (See *Duplex Signalling.*)

DIRECT CONDUCTIVE CIRCUIT—Any circuit having a direct conductive path and not depending on capacity or electromagnetic coupling. A metallic, conducting circuit.

DIRECT COUPLING—The coupling or relation between two or more coils or circuits, wherein the connection is *metallic*. In the illustration Fig. 1 is shown a two slide tuning coil. In this case A-B is the primary or aerial circuit and C-D the secondary or detector circuit. The two circuits are joined together by metallic connection.



Fig. 1. Double slide tuner which affords direct coupling between the primary and secondary circuits.



Fig. 2. Circuit in which primary and secondary are inductively coupled.

The illustration Fig. 2 shows essentially the same circuit, except that the primary and secondary are two separate coils. Here the two coils or circuits are joined by *inductive* coupling.

DIRECT COUPLED—Circuit in which primary and secondary circuits are metallically connected. Generally permits little selectivity. For this reason, *inductive coupling* is more generally used to permit close tuning or selectivity (q.v.). (See *Coupling, Inductive Coupling.*)

DIRECT CURRENT—See *Current, Direct.*

DIRECT READING—A term applied to various measuring or recording instruments which are so arranged as to show values directly without requiring mathematical reduction. *Voltmeters, Ammeters* and such instruments, used widely for showing the *voltage, current*, etc., of *batteries* or *cells*, are direct reading, showing the values directly in *volts* or *amperes*. A *decremeter* or *wavemeter* very often shows a reading that requires application of a formula to produce the desired quantity. (See *Calibration.*)

DIRECTION FINDER—See *Radio Compass.*

DIRECTIONAL—The effect of an aerial wherein waves are transmitted better, or entirely, in a certain direction, or received from a certain direction, depending upon the type and direction of aerial. (See *Transmitting Aerial*, also *Receiving Aerial.*)

DIRECTIONAL EFFECT OF ANTENNA—An effect of an antenna (aerial) for reception or transmission wherein signals from a certain direction are more readily received than from another direction, or in the case of transmission, the range being greater in a certain direction.

DISCHARGE—Generally speaking, a comparatively sudden passage of electricity. The term however, as applied to a *storage battery* will mean merely the effect of releasing the *electrical charge* stored up in it, in this case the discharge not being necessarily rapid. A *condenser* has the ability to hold charges of electrical energy and to release them suddenly when the proper contact is made. The term "discharge" as applied to a *transmitter* indicates the passage, usually in the form of a spark or succession of sparks, of the electrical energy across a gap between *electrodes*. The illustration shows spark discharge from spark coil. (See *Spark Discharge, Storage Battery*, also *Discharger.*)



Discharge from a spark coil.

DISCHARGER—Any device allowing a path for an electrical discharge. The term may be considered roughly a synonym for *spark gap*. Usually two or more *electrodes*, either stationary or rotary, spaced a short distance apart to permit the released electrical energy to bridge the space and thus complete an *oscillatory circuit*. (See *Disc Discharger Rotary Gap.*)

DISC DISCHARGER—A form of *discharger* employing one or two rotating discs carrying the sparking surfaces. With the advent of modern undamped transmission methods, these dischargers are gradually passing out. (See *Synchronous Discharger.*)

DISPLACEMENT CURRENT—A current which flows for a short interval in an insulating material or *dielectric* when an *electromotive force* is impressed across it, or when the intensity of the electromotive force impressed across it is increased or decreased. This *displacement current* will flow only when the impressed electromotive force is altered in intensity. After the initial current due to the sudden change in the electromotive force being impressed across the material, the dielectric material or insulating material will remain in a state of strain as long as the *charging force* persists without further change in intensity, and no further displacement current will flow. (See *Current*, also *Dielectric.*)

DISPLACEMENT, PHASE—See *Phase Displacement*, also *Phase Angle.*

DISRUPTIVE VOLTAGE—The voltage sufficient to disrupt or break down a sample of *dielectric* material under given conditions. Known also as *breakdown potential.* For example, if a *condenser* will stand an impressed potential or voltage of 500 volts without injury, but will be punctured by a potential of 1000 volts minimum, the disruptive voltage is said to be 1000. (See *Break Down Potential.*)

DISSOCIATION THEORY—A theory advanced by Arrhenius in 1887, explaining *electrolytic conduction* by the assumption that a substance in solution is dissociated or separated into *positive and negative ions*, these ions carrying their respective charges in opposite directions. (See *Electrolytic Action.*)

DISSONANCE—"Discord; disagreement"—Webster. The antonym of *resonance.* A term broadly applied in radio to indicate lack of resonance, or coordination of signals or impulses. When an alternating current is superimposed on another alternating current of different frequency, the resulting lack of resonance—*dissonance*—is known as a *beat.* (See *Distortion.*)

DISTORTION—Lack of purity or faithfulness in the reproduction of a vibration or series of vibrations. The most common application of the term in broadcast reception is in the case of reproduction by a loud-speaker. It will very often be found that music or speech is not perfectly reproduced, due to any of a variety of causes. Vacuum tubes may themselves cause distortion; too high potential applied to the plate of a tube may result in distortion; many transformers used in audio frequency amplifier circuits may distort notes of certain frequencies, or it may be due to *self-oscillation* or *regeneration* in the receiving set. This effect is also caused by inefficient transmitting (broadcasting) apparatus, or by lack of careful adjustment. The transformation of speech or music into electrical impulses and its subsequent transmission and reception are attended by many difficulties.

The control of wave form in broadcasting is known as *modulation.* (q.v.). If the transformation of speech or music into electrical impulses and its propagation into space is accomplished without materially changing or distorting the wave form from the original voice or music vibrations, the problem of accurate reproduction is entirely dependent on the receiving apparatus. Distortion may often be traced to the diaphragm of the loud-speaker, certain types being more efficient in this respect than others. (See *Loud-speakers.*) If the ordinary type of disc diaphragm is used, it may become bent and thus cause inequalities in the vibrations, producing distortion of the music or speech being reproduced. (See *Wave Form, Modulation,* also *Amplifier.*)

DISTRESS SIGNAL—At the International Radio Telegraph convention held at Berlin, Germany, in July, 1908, the call letters C Q D, established by the Marconi Co. in February, 1904, as the official distress call, were superseded by the letters S O S as the Marine distress signal.

S O S is the International distress call for ships and airships requiring assistance. The letters have no particular significance, being chosen mainly for their distinctive sound. In the International Morse code, S O S is composed of three dots, three dashes and three dots, thus: . . . — — — . . . an unusual combination which permits easy recognition among other messages and calls. When distress signals are heard, the nearest government transmitting station generally sends out immediate notification to all broadcasting stations in the vicinity to suspend operations until the ship has been located and assistance rendered.

DISTRIBUTED CAPACITY—The condenser effect in a coil of wire. Any coil of wire possesses *inherent capacity* to a certain extent, depending on its particular shape, size, etc. In the case of a coil of wire wound on a cylindrical form as indicated in the illustration Fig. 1, the passage of current through the coil sets up a *local magnetic field*, but also an *electrostatic field*, the latter being in the form of lines of force perpendicular to the conductor. Thus in effect, each two adjacent turns of wire act as a miniature condenser (Fig. 2).



Fig. 1. Coil showing effect of distributed capacity between winding.



Fig. 2.

There are numerous methods and forms for winding coils in order to do away as much as possible with this effect. (See *Low-Loss Coils.*)

DISTRIBUTED INDUCTANCE—In a long cable or any great length of wire used for electrical purposes, additional inductance (wire) distributed throughout the entire length to compensate for the inherent capacity of the line. (See *Distributed Capacity.*)

DOT—The short signal in the International Morse Code. (See *Code.*)

DOUBLE AMPLIFICATION CIRCUIT—Also known as *dual amplification circuit.* The arrangement whereby a vacuum tube or several tubes may be made to do double duty, acting as both *radio frequency* and *audio frequency amplifiers.* (See *Reflex.*)

DOUBLE COTTON COVERED WIRE—Abbreviation D. C. C.—Cotton covered copper wire widely used in radio work for coils and all forms of inductances. The insulating covering is composed of two distinct layers of cotton, wound on in opposite directions to prevent loosening. Such wire is obtainable in a variety of sizes according to the standard gauges. (See *Wire Gauge.*)

DOUBLE FREQUENCY OSCILLATIONS—Sometimes referred to as a *double humped wave.* An irregular wave resulting from two frequencies, generally due to too close coupling of the *oscillation transformer.* When the coupling between the open and *closed oscillatory circuits* is too tight, the *open circuit* very often oscillates at two frequencies, resulting in the radiation of an irregular or *impure wave.* The illustration Fig. 1 shows in graphic form, such an irregular wave. The two peaks of resonance explain the term double humped wave. Fig. 2 shows another curve illustrating two frequencies.

In this case however, the amplitude of the second wave is considerably less than that of the first or main wave. According to U. S. Government regulations, if the amplitude of the lesser wave is not more than 0.1 of the amplitude of the main wave, it is said to be pure. In other words, where there are two frequencies, but the strength of one less than one tenth that of the other, it is considered negligible as it cannot be expected to cause any appreciable interference. (See *Resonance, Amplitude, Decrement,* etc.)



Fig. 1. Resonance curve showing second wave of interfering nature.



Fig. 2. Resonance curve showing second wave of negligible proportion.

DOUBLE GRID TUBE—A vacuum tube having two distinct *grid* members in addition to the usual *filament* and *plate* elements. Such a tube is used in circuits where the customary "B" battery is not employed, the extra grid acting as a booster for the electron flow, the "A" battery furnishing a small positive potential to the plate. (See *Solodyne*, also *Theory of Vacuum Tubes.*)

DOUBLE MODULATION—Successive modulation of a *radio frequency alternating current* at two lower frequencies. The *intermediate frequency* is usually above *audio frequency* and the lowest frequency is customarily within audio limits or a combination of audio frequencies, as in the case of *radio* *telephony* (broadcast). (See *Modulation.*)

DOUBLE POLE SWITCH—A switch used in electrical practice and in radio installations having two poles or connections, thus permitting both sides of a circuit to be opened or closed simultaneously.

DOUBLE RANGE METERS—Meters used for electrical measurements, arranged to read to two scales. As an example, the voltmeter shown has two scale readings, one in fine degrees for a maximum of 7.5 volts, the other a coarser scale to a maximum of 150 volts. Three binding post connectors are furnished, one being a common positive for both scales. A meter for almost any measurement might be made to have double range, although such instruments are generally confined to measurement of current in amperes and pressure in volts—i. e., ammeters and voltmeters. (See *Meter.*)

Photo by Courtesy of Weston Electrical Instrument Co.

Double range meter, one range to 7½ volts, higher range to 140 volts maximum.

DOUBLE SLIDE TUNER—A tuning coil provided with two sliding contacts, generally used in crystal receivers.



Two-slide tuner.

The illustration shows a common type of two slide tuner. (See *Coupling Crystal Receiver*, also *Tuning.*)

DOUBLE THROW SWITCH—A switch so arranged that a circuit or a certain instrument is connected in either of two different positions by throwing the switch lever. The illustration shows a single pole double throw switch. (See *Switch.*)



Double throw single pole switch.

DOWN LEAD—More commonly known as *lead-in*. The wire running from the aerial to the receiving or transmitting apparatus, whereby the signal energy is either collected from, or fed to, the aerial. The illustration shows a typical down lead or lead-in for a receiving set. Obviously the chief difference between such a lead for receiving purposes and for connecting a transmitter to the antenna is the matter of insulation. The comparatively feeble impulses received or collected by the aerial when receiving require only ordinary care, whereas the high voltages used in transmitting require careful insulation and much heavier apparatus all around. (*For more complete details regarding insulation, etc., see Aerial.*)



A typical 4-wire aerial showing lead in and method of installing lightning switch.

DRIFT, AVERAGE ELECTRON—The assumed rate of flow or drift of *electrons* under average or specific conditions. (See *Electronic Flow.* Also *Current, Assumed Direction of Flow.*)

DRIVER—A term broadly used to denote any system used to produce *oscillations* (vibrations) of a local nature. More specifically any means of producing oscillatory currents as used to test or make measurements in radio circuits. A buzzer connected inductively to a circuit to produce oscillations in that circuit for the purpose of making measurements of *capacity, wavelength*, etc. Another means might be a circuit involving a vacuum tube and the necessary apparatus to make it oscillate at a given or variable frequency. The term may be used to signify the tube circuit used to produce local oscillations in the case of a *super-heterodyne* (q.v.). Here the driver produces a series of oscillations of a frequency different from the incoming oscillations, the difference between the two being known as the beat frequency. (See *Heterodyne, Local Oscillations, Buzzer, Excitor.*)

DRIVER CIRCUIT—The circuit of the apparatus used to produce oscillations for purposes of test or measurement, or, in the case of a super-heterodyne, to produce a beat effect. (See *Driver.*)

DRUM ARMATURE—A form of armature winding in the approximate shape of a drum. (See *Armature.*)

DRY BATTERY—A battery or group of cells not employing a liquid electrolyte, the cell being filled with a mixture of carbon, manganese dioxide and sawdust (or other absorbent) saturated with a solution of sal ammoniac, these forming a paste, as distinguished from Wet Battery. (See *Battery*, also *Cell* and *B Battery.*)

DRY CELL—See *Dry Battery.*

D. S. C.—The abbreviation for "Double Silk Covered" as applied to copper wire having two distinct layers of silk, wound generally in opposite directions. This wire is furnished in standard sizes according to the various wire gauges. (See *Brown & Sharpe Gauge.*)

DUAL AMPLIFICATION—The process of obtaining both *radio frequency* and *audio frequency amplification* from the same tube instead of using two separate tubes. (See *Double Amplification Circuit*, also *Reflex.*)

DUBILIER, WILLIAM—President and technical director; born, New York, July 25, 1888. Educated New York Schools, Technical Inst. and Cooper Union; Chief Engineer of Continental Wireless Tel. & Tel. Co.; 1910 President of Com. Wireless Tel. Co.; at present Technical Director of Dubilier Condenser and Radio Corp. of New York, The Dubilier Condenser Company Ltd. of London, The Deutsche Dubilier Kondensator Gesellschaft in Berlin, La Protection Electrique Capart-Dubilier in Paris. Has obtained over three hundred patents and applications of electrical devices, which have been purchased or licensed by many companies. Member American Institute Electrical Engineers, Inst. of Radio Engineers, Honorary Member of Societe Academique D'Historie Internationale. Member of Royal Society of Arts.

DUCON—Trade name of a device which can be fitted to any electric light socket and made to serve in place of the usual outdoor aerial. This attachment consists essentially of two condensers, so arranged as to prevent the passage of any direct current or low frequency alternating current from the lighting main to the receiving set, but at the same time to permit passage of the incoming radio signals, the electric light line acting, therefore, as an aerial. (See *Adapter, Aerial.*)

DUDDELL SINGING ARC—Also called *Musical arc.* An *arc* actuated by a source of direct current through a *resistance* and shunted by a *condenser* and *inductance* in series. An *oscillating current* is thus produced in the condenser circuit, the result being a singing note corresponding in pitch to the frequency of the oscillations in the condenser circuit. The schematic arrangement is shown by the illustration. (See *Arc Generator.*)



Schematic arrangement for operation of Duddell singing arc.

DULL EMITTER—The English term for vacuum tubes having *thoriated filaments* and operating with low current consumption. While the term is generally used to denote the tubes requiring only one or two dry cells to operate, it may apply as well to storage battery tubes where the current requirements are low. (See *Filament, Thoriated.*)

DUOLATERAL COILS—An alternate term for *honey-comb* coils; inductances wound in diamond-shaped layers to reduce the distributed capacity effect. (See *Honey-Comb Coils.*)

DUPLEX SIGNALLING or DUPLEX TELEGRAPHY OR TELEPHONY—The simultaneous transmission of signals or telephony in both directions between two stations. (See *Diplex Reception or Transmission*, also *Telephony.*)

DUST CORE—A form of core for certain types of transformers, employing iron filings or dust in place of the customary iron wire or laminations. Iron dust is used occasionally where simplicity of construction is desired, the assembly of such a core being obviously much easier than with wire or laminated types. (See *Core.*)

DX—The popular term for long distance; referring to the transmission to or reception from distant points of radio signals or broadcasting.

DYNAMIC CHARACTERISTIC — The curves obtained by impressing an alternating E. M. F. (electromotive force) on the grid of a vacuum tube, as distinguished from the curves obtained by application of a steady direct potential. When alternating potentials such as incoming signals are impressed on the grid of a tube, the curve resulting is apt to take an entirely different form from that of the curve showing *static characteristics* (q.v.). (See *Vacuum Tube characteristics.*)

DYNAMIC CONDENSER—A term occasionally applied to a *synchronous motor* used to improve power factor (in alternating current circuits, the ratio of the electric power in *watts* to the apparent power in *volt amperes* is known as the power factor). Used in this manner the motor has the effect of advancing the current phase in a manner similar to that of a condenser. (See *Angle of Lead or Lag.*)

DYNAMIC ELECTRICITY — A term sometimes used for electric currents to distinguish them from *static electricity* (q.v.).

DYNAMO—A machine for converting mechanical energy into electrical energy. Is also known as *generator*, but usually confined to machines for generating *direct* current. The action of a dynamo is based on the production of an *electromotive force* in a conductor moving in a magnetic field. Fundamentally a dynamo is a machine that generates alternating current, but instead of collecting this current by means of rings, which would cause alternating current to flow in the external circuit, a device known as an *armature* is employed in such a manner that the current collected by brushes and delivered to the external circuit is direct—that is, it flows more or less steadily in one direction. Thus the kind of current delivered for use depends on the method used to collect the currents generated. (For more complete explanation of the production of alternating current see *Alternating Current, Theory of Production.*) In the case of a dynamo, the essential parts are the *field magnets*, the *armature* and the *commutator*. Now in the case of an *alternator*, each end of the loop or armature is connected by a brush bearing against a collector ring and the end of each loop is always connected to the same brush. This *results in an external current that changes its direction with each reversal of direction of the induced electromotive force.* If the external current is to be direct it is necessary to have some means of collecting the current through one brush at the positive instant and the other at the negative instant. This is done by means of an armature, which is in effect a switching arrangement, so designed that it will reverse the connections of the external circuit at the instant of each reversal of current in the armature. The illustration shows a *shunt* wound dynamo. MM are the field magnets, FF the field windings, BB the brushes, A the armature and C the commutator. (See *Alternator, Armature, Generator.*)



Shunt wound dynamo.

DYNAMOMETER—A delicate and accurate instrument for the measurement of currents and voltages or both. Such instruments depend upon the action of a circuit carrying current upon another carrying the same current. Essentially it comprises two coils, one fixed and the other movable. This system of measurement is used in a *wattmeter*, where it is necessary to measure the instantaneous current and voltage, i.e., power. (See *Wattmeter*, also *Electro Dynamometer.*)

DYNAMOTOR—A direct current machine which acts either as a *motor* or *dynamo*. It has an armature with two separate windings and two separate commutators, one at each end of the armature. Either winding may be used as a motor and the other as the generator winding. Such a machine is used to convert high voltage direct current into low voltage direct current or vice versa, thus performing the same function with direct current as a power transformer performs for alternating current. (See *Converter.*)

DYNATRON—A form of vacuum tube generally used for producing oscillations as in radio telephony, wherein the phenomena of "*secondary electron emission*" is used. In this form of tube the electrons traveling at high speed from the hot filament or cathode are made to collide with a metallic surface. The collision of these electrons on the surface of the interposed element has the effect, under proper conditions, of jarring other electrons out of the metal. The secondary emission thus obtained depends upon the speed of the original electrons which collide with the metal surface. Normally, these secondary electrons will immediately re-enter the surface from which they were emitted, but if another electrode of higher potential is in the vicinity they will travel toward it in the same manner as the electrons are attracted to the plate of an ordinary three element tube. A standard tube can be connected as shown in the illustration to act as a dynatron. Here the filament F emits electrons, some of which pass through the grid G and collide with the plate P. This collision with the plate P may jar loose from the surface additional electrons, which normally would immediately re-enter P. However, as the grid G is held at a higher potential (higher positive voltage) than P, the electrons will be drawn toward it. A tube arranged in this manner may be used for practically any of the purposes of the standard tube, such as regenerative detector, detector of continuous waves or as a generator of high frequency oscillations, but it has not been shown to have any advantages in this respect, being used mainly as an *oscillator* (q.v.). (See *Electron Emission, Vacuum Tube*, etc.)



Showing how a standard vacuum tube can be connected to act as a dynatron.

DYNE—The unit of force in the absolute or CGS system of units. It is defined as the force which, acting on a mass of one gram for one second, will impart to the mass a velocity of one centimeter per second. (See *CGS System*, also *Force.*)

E

E—Common symbol for *Electromotive force* (q.v.).

EAR CUSHION—Pads or cushions of soft rubber used in conjunction with head-phones to prevent unpleasant pressure against the ears and also to exclude outside sounds when listening in.

EARTH—An alternate term for *ground*, where the earth or any metallic connection thereto is used as a return in transmission or reception of *electromagnetic waves*. (See *Ground.*)

EARTH CURRENTS—See *Ground Currents.*

EARTH, DEAD—See *Ground.*

EARTH DETECTOR—See *Ground Detector.*

EBONITE—See *Insulating Materials.*

EBURIN—An insulating compound used for *strain insulators* (q.v.). (See *Insulating Materials.*)

EDDY CURRENT LOSS—The portion

of the total loss in electrical apparatus due to *Eddy Currents* (q.v.).

EDDY CURRENTS—Currents induced in the mass of a solid *conductor* due to the action of a varying *magnetic field.* The most common example of eddy currents will be found in the case of a *dynamo* or *generator*. Here the useful current generated in the *armature* is produced by the motion of the armature in the magnetic field. At the same time currents are generated in the iron core due to its motion in the magnetic field. As all currents generated in an electrical machine are produced at the expense of a certain amount of energy, and since the Eddy currents cannot be gathered or put to useful account in this case, they represent a loss. This loss usually is apparent in the form of heat. If the core is made up of solid metal it will be obvious that a good closed path is offered for eddy currents produced. Now if the core is composed of a number of sheets or *laminations*, insulated by thin layers of paper or by an insulating scale (see *Transformer Steel*) the path for the eddy currents is partially broken and the effect is reduced. Eddy currents are produced in the core of a transformer due to the same action—the variation of the magnetic field in which the core is located. In order to reduce the effect, laminated cores are employed as in the case of many generating machines. Eddy current loss is often given as the loss in watts per pound of core material at 10,000 *gausses* (q.v.) and 60 cycles for a sheet 0.0141 inch or 0.0358 centimeter thick. While eddy currents are usually productive of losses they are put to useful account in certain types of instruments. For example, the eddy currents produced in the metal frame of a moving coil meter may be employed to *damp* or retard the free *oscillations* of the needle. (See *Damping of Instruments.*) Eddy currents are also used in a form of speed indicator where the reaction of eddy currents created in a moving disk are made to deflect a pivoted, spring controlled, magnetic needle. (See *Core Loss, Hysteresis*, also *Foucault Currents.*)

EDDY CURRENT COEFFICIENT—The coefficient or numerical multiplier, generally termed K_1, used in calculations of eddy current loss. Its numerical value depends upon the *specific resistance* (q.v.) of the iron used in the core of the machine in question, the character or *wave shape* of the induced voltage, the distribution of *magnetic flux* (q.v.) in the core material, the degree of insulation between sheets, where *laminations* are used, and upon the *flux distribution* (q.v.) due to the shape of the magnetic circuit. Its value will also vary according to the units used in the computation.

EDDY CURRENT LOSS, FORMULA FOR CALCULATING—A common formula for calculation of eddy current loss is the following: $P_\epsilon = \epsilon V(xfB)^2$. Here the loss is expressed in watts as P_ϵ, V is the volume of core metal in cubic centimeters, x the thickness of the sheets in centimeters, f the *frequency* in cycles per second, B the *flux density* (q.v.) in *gausses* and ϵ the eddy current coefficient.

EDGE EFFECT—The effect on the capacity of a condenser due to the curving of the lines of stress at the edge of the plates. This effect is not very pronounced where there is considerable *dielectric* surface (insulating material) extending beyond the edge of the plates. (See *Distributed Capacity.*)

EDISON BATTERY—A number of Edison cells grouped together in one case to supply various currents and voltages as in radio. The illustration shows an Edison "B" battery, used to supply potential to the plates of vacuum tubes. (See *"A" Battery, "B" Battery, Plate, Filament*, also *Storage Battery.*)



Photo by Courtesy of
Edison Storage Battery Co.

Edison "B" battery with portion of case removed to show interior construction.

EDISON CELL—A storage cell employing electrodes of nickeled steel and a solution of potassium hydrate for the electrolyte as distinguished from the usual type of storage cell using lead plates and dilute sulphuric acid as the electrolyte. The chief point of superiority of this type of cell is its comparative ruggedness, due partially to steel construction and also its freedom from the usual ills of cells employing acids and lead plates. The positive electrode in the Edison cell is made by tamping nickel hydrate and alternate layers of pure flake nickel into perforated steel tubes under pressure. The negative electrode is made by pressing iron oxide into flat perforated steel pockets. A number of these pockets are forced into a steel grid to form the complete negative plate. (Note: The *negative* electrode connection on the outside of the cell is referred to as the *positive* pole because it is positive in its relation to the external circuit. Similarly the *positive* electrode connection will be known as the *negative* pole.) The potassium hydrate or hydroxide which takes the place of the acid solution used in the lead plate type of cell acts as a preservative of the steel elements. This naturally means greater life; in fact, it is not subject to the chemical deterioration of other cells. The illustration shows a cell with part of the sides cut away to show the interior construction. (See *Edison Battery.*)



Photo by Courtesy of
Edison Storage Battery Co.

Edison cell with part of case cut away to show how constructed.

EDISON, THOMAS ALVA—Born 1847. An inventor famous for his experiments in applied electricity. He began life with newspaper work which he soon abandoned for telegraphy, making many original inventions in duplex systems of operation. After a varied experience in that line he came to New York in 1871, where his talents were recognized and he had opportunity to profitably develop his ideas. The duplex telegraph was made a success the following year, and two years later the quadruplex; and thereupon he began manufacturing on a large scale for the Western Union Telegraph Co. In 1876 he gave up his factory, and established his experimental station at Menlo Park, N. J., where for several years he worked upon the problem of the incandescent electric light, exhibiting a successful bamboo filament lamp in Paris in 1881. He invented the phonograph in 1878. He superintended the construction of the first incandescent lighting station in New York in 1882. Moving his laboratory to Orange, N. J., he established there a large plant for electrical experiment and invention and as a result of his labors there he has taken out 400 patents. Among his inventions may be further named: a type of dynamo, a microphone, the chemical electrical meter, an electric pen, the mimeograph, the magnetic ore separator, dead beat galvanometer, the electric torpedo, a telephone transmitter, and a storage battery. His chief fame rests with his development of the telegraph, his invention of the incandescent lamp and the phonograph.

Thomas A. Edison

EDISON EFFECT—The blackening of the inner surface of an electric light bulb during use. Edison noticed that after the lamp had been burned for some time a coating of black formed on the inner surface and increased in density, becoming finally almost opaque. Edison's experiments, followed by those of *Professor Fleming* (q.v.) resulted in the development of the *Fleming valve* (q.v.)., it having been determined that the black coating was due to the discharge of *electrons* from the hot *filament*. (See *Vacuum Tube, Electron Emission*, etc.)

EFFICIENCY—A very flexible term in electrical practice. Generally speaking, the ratio of useful output of any piece of apparatus to total input. Efficiency is customarily expressed in terms of percentage. Thus, broadly, a piece of apparatus may produce as useful output 80 per cent of the total input. (See *Power Factor.*)

EFFECTIVE ELECTROMOTIVE FORCE—The square root of the mean square of the full alternating current wave. Usually abbreviated R. M. S. (root—mean—square). The effective value of the E. M. F. (electromotive force) is thus taken as the square root of the mean of the squares of the *instantaneous values* over a complete period. (See *Instantaneous Values.*)

EGG INSULATOR—A name applied to a certain type of *strain insulator* due to its egg-like form. The illustration shows such an insulator. The two connections to the insulators are so arranged that the wires will still be looped together in the event that the insulator breaks. (See *Insulator*, also *Insulation of Aerial.*)



An egg insulator.

ELASTICITY—A property of matter which permits it to resist any change in shape or bulk and permits it after such a change to return to its original state. This property of materials by virtue of which they are enabled to return to their original state after the force causing the distortion has been removed is a very important one in all branches of engineering. Its chief application in radio is in the matter of aerials and aerial guy wires. While the average aerial installation does not represent any serious problems in stress, the large aerial systems of commercial stations must be carefully designed in this respect. For example, a guy wire of one material may have more elasticity than one of similar size in another material. The amount which the wire will stretch under a certain load may be determined by use of a table giving the elasticity of various metals. (See *Electric Elasticity.*)

ELECTRIC ABSORPTION—An effect in *condensers*. That quality of a condenser by means of which it absorbs or "soaks up" a charge of electricity, and conversely, retains part of the charge when the condenser is momentarily discharged. This effect is more apparent in cases where a solid *dielectric* material is used. In fact, *air condensers* (q.v.) are said to have little electric absorption. The reason for this is that mica or other solid dielectrics are strained to a greater extent than air dielectric after the condenser has received a charge. (See *Soaking In*, also *Dielectric Absorption.*)

ELECTRIC DISPLACEMENT—A term proposed by Maxwell to denote a quantity expressing the state or condition of a dielectric in an electric field in accordance with the supposition that such a field is created by the transfer of positive electricity to one end of the field of force and negative electricity to the other end of the so-called *tubes of force* (q.v.). (See *Displacement Current*, also *Electrostatic Induction*, and *Flux Density, Electrostatic.*)

ELECTRIC ELASTICITY—In a dielectric material, the property which permits it to arrest passage of a *displacement current* (q.v.) due to electric stress. It is equivalent to the electric stress divided by the electric strain. (See *Dielectric*, also *Displacement Current.*)

ELECTRIC FIELD—The area surrounding an electrified body in which the electrical influence of that body can be measured or noticed. Also any area or region in which there is an electric force either steady or varying in intensity. For example, the *dielectric* or insulating surface of a *condenser* (material separating the plates) contains an electric field. Similarly, an electric field always surrounds a wire or other conductor carrying electric current. (See *Field, Magnetic; Field, Electromagnetic; Field, Electrostatic;* also *Flux.*)

ELECTRIC INDUCTION—The transfer of an electric state from a charged or electrified body to a non-electrified body without electrical contact. (See *Induction.*)

ELECTRICITY—The term given to an invisible form of energy. Electricity is not tangible to the human senses, but its effects can readily be detected. The phenomenon of electricity is regarded as due to the separation and independent movement of constituent parts of atoms—known as *electrons*. While electricity is really an intangible thing so far as the human perceptions are concerned, it is known to science not only through its effects or manifestations of energy, but has actually been reduced to quantities. The mass of electricity has been determined, as has also the *rate of flow*, etc. We have units which are used for the basis of all calculations in electricity. Thus, *voltage* is regarded as the propelling force; the quantity of electricity is given in *coulombs*, the *current* or rate of flow of electricity is given in *amperes*, etc. Each term for the various phases of electricity is based on a certain unit which represents definite values under given conditions. The universally accepted theory in chemistry is that all matter is made up of molecules, which in turn are composed of one or more atoms. These atoms now are regarded as comprising minute solar systems made up of positive and negative electrical particles. (For more complete explanation of the *electron theory* see *Electron Theory;* see also *Magnetism, Current, Voltage.*)

ELECTRO-CHEMICAL CONDENSER—See *Electrolytic Condenser.*

ELECTRO-CHEMICAL EQUIVALENT—The amount of a substance liberated by *electrolytic action* (electrolysis) by the passage of one *coulomb* (q.v.) of electric current. It represents the weight in grams of each element of an *electrolyte* (q.v.) which is deposited by one coulomb of electricity. It has been determined that one coulomb will liberate .00001035 grams of hydrogen, which is therefore used as the electro-chemical equivalent of hydrogen. Electro-chemical equivalents are much used in applying the law of electrolysis. This law states that the amount (weight) of an *ion* liberated at an *electrode* each second during *electrolysis* is equal to the strength of the *current* (amperes) multiplied by the electro-chemical equivalent. The corresponding equivalents of other elements compared to hydrogen may be determined by multiplying the figure .00001035 by the atomic weight of the other element in grams and dividing the result by the *valency* (q.v.) of the element in question. (See *Electrolysis*, also *Electrolyte.*)

ELECTRO-CHEMICAL SERIES—A table of metals arranged in accordance with the *potential* they produce in a particular *electrolytic* solution.

ELECTRO-CHEMISTRY—The science dealing with chemical changes due to electricity or effected by means of electricity. (See *Electrolysis*, also *Cell*, and *Storage Batteries.*)

ELECTRODE—The conductor through which electric current enters or leaves an electrical device. That is to say the pole or terminal of the current carrying conductors separated by a medium through which electric current can flow from one to the other. The most common usage of the term is in referring to the *positive* and *negative* poles (q.v.) of a *primary* or *storage cell*. In the case of a *dry cell*, the two electrodes are the carbon rod or block in the center and the zinc container in most cases. In radio it is used to designate the *filament* and *plate* elements of a vacuum tube. The filament is termed the *cathode*, or *negative electrode* and the plate is the *positive electrode* or *anode*. The illustration shows an ordinary *dry cell* or *primary cell* with the two electrodes designated as positive and negative. (See *Anode, Cathode, Battery, Electrolysis, Positive Electrode* and *Negative Electrode.*)



Dry cell showing positive and negative electrodes.

ELECTRODYNAMIC—Term used to denote electric currents or the forces exerted by one current upon another.

ELECTRO-DYNAMICS—A branch of the science of electricity dealing with electricity in motion; the study of the force exerted by electric currents upon each other. This branch of electricity was first accorded serious attention when the French scientist, *A. M. Ampere* (q.v.) announced the result of his investigations in collaboration with D. F. J. Arago. Ampere stated in 1820 that *parallel conductors* through which electric currents were flowing in the same direction had a tendency to be attracted to each other and to be repelled when the currents were flowing in opposite directions. The subject is discussed under its various separate headings. (See *Ampere, Electricity, Magnetism.*)

ELECTRO-DYNAMOMETER—A device for measuring the *current* and *voltage* in a circuit; that is, the actual power in a circuit. It is a form of *wattmeter* (q.v.) designed to indicate the power in *watts*. It is of particular importance in measuring the power in *alternating current* circuits. In the case of *direct current*, the watts in the circuit are the product of the volts multiplied by the amperes, the result being the actual power. In the case of alternating current, however, the product of the volts and amperes is not necessarily, in fact, seldom, the true power or watts. Here we have the problem of true watts and apparent watts, or volt-amperes. If a voltmeter and an ammeter are connected in a circuit and read separately, the readings indicate the maximum voltage and the maximum current or amperage. The product of these two values is the power in watts in a direct current circuit. If the current is an alternating one, the true watts or actual power will be the product of the *instantaneous values* (q.v.) of voltage and current. Under certain conditions in a circuit carrying alternating currents, the current may lag behind or precede the voltage. In other words, the maximum value of current is not reached at the same moment as the maximum value of the voltage. In this case the true watts can only be determined by obtaining the values of volts and amperes at the same instant, i.e., instantaneous values. The electro-dynamometer shown in the illustration gives the instantaneous values, or rather their product, and thus indicates the power or true watts. Here the heavy lines represent the current or moving coil and the light lines the stationary or voltage coil. (See *Dynamometer*, also *Wattmeter.*)



Electro-dynamometer with the current or moving coil shown by heavy lines and the stationary or voltage coil by light lines.

ELECTROLINES—A term advanced by *Professor J. A. Fleming* (q.v.) to designate the lines of electric force radiating from an electron. These lines are pictured as analogous to long straight wires extending in all directions from the center of a small sphere. (See *Electron,* also *Electromagnetic Waves.*)

ELECTROLYSIS—The decomposition of a comopund substance, generally a liquid, into its component parts by the action of an electric current passing through it. While electrolysis is an undesired effect in certain phases of electrical power work, causing composition of grounded structures, its application to radio is mainly in the case of cells for producing an *electromotive force* or to furnish current for lighting tubes. The constituent elements of a chemical compound such as used in a wet cell or any device using an electrolyte for the production of electric current, are known as *ions* (q.v.). These ions, which are separated during electrolysis, are of two kinds. The electro-positive ions are known as *cations*, and the electro-negative ions are known as *anions*. The electro-positive ions appear at the cathode or negative electrode during electrolysis and therefore are of positive origin. The electro-negative ions appear at the positive electrode and are therefore of negative origin. This is easily understood when the ions are considered as moving from the positive electrode or to the negative. Thus the ions appearing at the negative electrode must have come from the positive electrode and are therefore considered electro-positive in nature. The illustration shows the action of the ions in a typical *primary cell* (q.v.). The ions are considered as carrying the current through the electrolyte—each ion carrying a fixed charge of electricity of positive or negative nature. An ion is capable of carrying only a certain fixed charge of electricity and therefore any increase in the current will necessarily be accomplished by an increase in the number of ions. (See *Primary Cell, Electrolyte, Electrolytic Detector, Interrupter* and *Condenser.*)



Illustration showing the action of ions in a primary cell.

ELECTROLYTE—The liquid decomposed during electrolysis, as the exciting fluid or solution in a wet cell or primary cell. The liquid used in any primary, secondary or electrolytic cell. (See *Cell*, also *Storage Battery.*)

ELECTROLYTIC ACTION—The decomposition of a chemical compound (electrolyte) into its constituent elements—ions, by the passage of an electric current through it. (See *Electrolysis, Ions*, also *Cell.*)

ELECTROLYTIC BATTERY CHARGER—A device for converting alternating current such as supplied for house lighting purposes, to direct current for the purpose of charging storage batteries. Essentially one or more cells containing an electrolyte and two metal electrodes, generally lead and aluminum, so arranged that current can only pass in one direction, thus making it uni-directional and suitable for charging batteries. Such chargers are arranged to rectify either one-half of the alternating current cycle, or both halves of the wave. (See *Charger, Storage Battery, Electrolytic Rectifier,* also *Electrolytic Cell.*).

ELECTROLYTIC CELL—An arrangement of two *electrodes* in an electrolyte through which electric current can be passed to produce electrolysis. The electrolyte is decomposed or separated into ions by the action of the current, and at each of the electrodes one of the substances of which the electrolyte is composed accumulates. Such a cell is often used to measure electric current, as the amount of a substance deposited on the electrode depends directly on the amount of current passed through the electrolyte. (See *Electrolysis.*)

ELECTROLYTIC CONDENSER—A form of condenser making use of two electrodes placed in an electrolyte and used for alternating current circuits of high voltage and low frequency, low voltage and high frequency or high voltage and high frequency. The action of such an arrangement as a condenser depends on the fact that upon the passage of certain forms of alternating currents through it, a gas is formed around the electrodes, causing *polarization* (q.v.) and opposing the current. This polarization creates a very good insulating medium and a condenser of such nature can be made to have very high capacity. An electrolytic condenser may be used to prevent any sudden surge of pressure due to lightning or other causes. The polarization is instantaneous when any surge of voltage takes place and thus forms an automatic safety device which operates instantly and returns to its normal characteristics as a condenser as soon as the surge has passed. (See *Capacity*, also *Condenser.*)

ELECTROLYTIC CONDUCTION—The action in an electrolyte wherein the ions that have been separated carry positive and negative electric charges in opposite directions to the electrodes. (See *Electrolysis.*)

ELECTROLYTIC DETECTOR A device which converts high frequency currents into direct current pulsations capable of operating a telephone receiver. It is an extremely sensitive detector of electromagnetic waves (radio signals). The illustration shows a simple form as originally used in place of the customary crystal detector. A fine platinum wire dips into a



Electrolytic detector originally used in place of a crystal detector for radio reception.

cup of acid solution, generally either nitric or dilute sulphuric. The fine wire is lowered until it just touches the acid solution and must be very carefully adjusted as it has a tendency to curl up, its diameter being usually but one five thousandth of an inch or less. The high frequency currents can pass in only one direction through the detector which gives the rectifying action and makes the signals audible in the head phones. There are several theories regarding the action of an electrolytic detector, the most probable one being that the contact of the wire on the surface of the acid solution gives the effect of a very small *electrolytic condenser.* (q.v.) When the high frequency currents are passed through the detector there is a polarization action which causes high resistance to current in one direction but not in the other. (See *Detector,* also *Polarization.*)

ELECTROLYTIC INTERRUPTER—A device using electrodes immersed in an electrolyte for the purpose of interrupting or breaking up the flow of current. It is used mainly for induction coils for producing high voltages. The common form comprises a lead plate as a cathode or negative element and a platinum wire extending beyond a glass or porcelain tube in which it is tightly imbedded, both immersed in an electrolyte of dilute sulphuric acid. When current passes through, bubbles form on the platinum electrode causing temporary stoppage of the current. The bubbles are automatically dissipated and the current flows again, this operation occurring at rapid intervals and giving as many as 1000 interruptions per second. (See *Interrupter,* also *Induction Coil.*)

ELECTROLYTIC RECTIFIER—A device for changing alternating current into direct current by use of electrodes placed in an electrolytic solution. The action of such electrolytic cells or rectifiers is to permit current to pass only in one direction, thus suppressing one half of each cycle and producing a direct current. The illustration shows one of the customary arrangements for electrolytic rectification, being an electrolytic cell with two electrodes, one being aluminum and the other a lead electrode. One or more lamps are placed in series or shunt in the circuit to permit the proper current flow. The positive pole of a storage battery is connected to the aluminum plate as shown and the lead electrode connects to the other side of the alternating current line and back to the negative side of the battery. At one instant current flows in the normal direction through the battery, but when the current reverses and flows in the opposite direction through the electrolytic cell, oxygen is given off at the aluminum electrode and forms a thin film of aluminum oxide which acts as an insulator and prevents the passage of the current in that direction. Thus with one cell one half of each alternating current cycle is stopped or cut off when the aluminum electrode is made positive and the result is an intermittent direct current suitable for charging batteries. Such rectifiers are also used for supplying current to the filaments of vacuum tubes, or voltage to the plate members of the tubes, particularly for transmitting. (See *Electrolytic Rectifier Full Wave,* also *Balkite Battery Charger.*)



Customary method of electrolytic rectification.

ELECTROLYTIC RECTIFIER FULL WAVE—This system is much used for charging storage batteries from an alternating current house lighting supply. Four cells are used in this instance. The electrolyte may be a solution of hydrolchloric or sulphuric acid, or a saturated solution of sodium phosphate or bicarbonate of soda. Each cell has two electrodes, one iron or aluminum and the other lead. The positive pole of the storage battery is connected to the lead electrodes of two cells and the negative pole is connected to the aluminum electrodes of two cells. By this means both halves of the alternating current cycle are rectified to direct, pulsating current. This is known as *full wave rectification* (q.v.) (See *Charger, Storage Battery, Balkite Battery Charger,* also *Rectifier.*)

ELECTRO-MAGNET—A magnet using a curved or straight piece of soft iron or other magnetic material so arranged as to become magnetized by the passage of electric current through a coil of wire surrounding it. The illustration shows one of the commonest forms of electro-magnet. This type is used in a bell or buzzer to draw down the vibrator bar and break the circuit. (For explanation of action see *Buzzer.*) When the current is withdrawn from an electro-magnet, the magnetic force or attraction ceases. Electro-magnets are used for a variety of purposes in radio, such as for test buzzers, head phones, relays, etc. (See *Magnet,* also *Magnetic Lines of Force.*)



One of the common forms of electro-magnets.

ELECTROMAGNETIC CONTROL—The control of various switches and other apparatus by means of *electromagnets,* usually through an auxiliary contact at a distant point. (See *Remote Control,* also *Electromagnet.*)

ELECTROMAGNETIC FIELD—The space understood to be filled with *electromagnetic lines of force.* (See *Flux,* also *Lines of Force.*)

ELECTROMAGNETIC FLUX—The distribution of the lines of force through an electromagnetic field. (See *Flux,* also *Lines of Force.*)

ELECTROMAGNETIC IMPULSE—An impulse or electromagnetic disturbance conveyed to the ether from a conductor carrying high frequency currents. Another term for the electromagnetic waves involved in radio. (See *Electromagnetic Waves.*)

ELECTROMAGNETIC INDUCTION—The production of electric currents through a change in a *magnetic field* (q.v.). Its production is due to a change in the number of lines of force which are linked with a conducting circuit. The simplest example of this means of producing current is shown in the illustration. Here a conductor is arranged to be moved in the immediate vicinity of a magnet, causing a change in the number of lines of force that link the conductor and creating an induced current. This current will persist only so long as the conductor continues to be moved in the magnetic field. That is to say when there is no longer any change in the magnetic lines of force linking the conductor, there will be no current induced. The discovery of electromagnetic induction and formulation of its laws was primarily due to the scientist *Faraday* (q.v.). Faraday's law governing electromagnetic induction follows: "The induced electromotive force around any circuit is the rate of the decrease of the total flux of magnetic induction through the circuit." (See *Induction, Flux,* and *Lines of Force.*)



Simple method of producing electric currents by causing changes in the magnetic field.

ELECTROMAGNETIC INSTRUMENTS—Electrical measuring instruments such as voltmeters, ammeters, etc., which depend for their action on the exertion of electromotive forces upon iron armatures. (See *Ammeter, Thermal;* also *Voltmeter.*)

ELECTROMAGNETIC MICROPHONE—A type of microphone in which the sound waves due to speech or music cause vibrations of a suspended coil in a magnetic field, inducing in the coil minute waves of electromotive force corresponding in form to the original sound waves. A form of microphone used in radiophone (broadcasting) transmission when purity of sound is an important consideration. Such a microphone requires that the induced currents be heavily amplified. (See *Microphone*, also *Speech Amplifier.*)

ELECTROMAGNETIC RADIATION—The propagation or radiation of electromagnetic waves through the ether. (See *Electromagnetic Waves*, also *Ether.*)

ELECTROMAGNETIC ATTRACTION—The attraction existing between unlike poles of electromagnets. This attraction is identical with that of two unlike poles of ordinary magnets. (See *Magnetic Attraction and Repulsion.*)

ELECTROMAGNETIC REPULSION—The tendency of two like poles of electromagnets to act against or repel each other. (See *Magnetic Attraction and Repulsion.*)

ELECTROMAGNETIC SWITCH—A switch for breaking electrical circuits by the action of an electromagnet. (See *Electromagnet*, also *Remote Control.*)

ELECTROMAGNETIC THEORY OF LIGHT—The theory and consequent scientific proof that radio waves and light waves are practically identical in nature. Light waves travel at a tremendous speed through the ether, approximately 186,000 miles per second, which is also understood to be the velocity of electromagnetic or radio waves. (See *Electromagnetic Waves.*)

ELECTROMAGNETIC UNITS—The fundamental or absolute units employed in electricity as a basis for calculations and on which the practical units are based. The effects of electricity, and hence electricity itself, can be measured in two ways. The first is the measurement of the quantity of electricity by the force it exerts upon another stationary quantity of electricity. This is known as the *electrostatic system.* The second is by measuring the force which a given quantity of electricity exerts upon a *magnetic pole* when flowing through a nearby conductor. This is referred to as the electromagnetic system. Fundamental or absolute units are derived from the fundamental units of *length, mass* and *time.* These units are the *centimeter of length, the gramme of mass* and the *second of time.* The term centimeter-gramme-second, referring to this system, is abbreviated C.G.S. system. The practical units of electricity are known as *volts, amperes*, etc., and are based on the absolute units. (See *Electrostatic, Units, C.G.S. System*, also *Ampere, Erg, Dyne* and *Coulomb.*)

ELECTROMAGNETIC WAVES—The term applied to the energy radiated from an *antenna* in radio transmission. So called because it is understood to travel in the form of waves. One-half the energy of such a wave is electrical and the other half electromagnetic. *Electromagnetic waves* travel with the speed of light waves or approximately 186,000 miles per second. These waves are of extremely high frequency—that is, their direction changes many thousand times each second. This will be better understood by means of the illustration showing the arrangement of the electric and *magnetic fields* around a radiating antenna. Here the lines represent the electric field and the shaded portion the magnetic field. The lower loops or "feet" of these waves are assumed to pass over the surface of the earth which is a conductor. Thus when electromagnetic waves are being radiated from an antenna, circular distributions of electric charges are in the earth's surface around the antenna, these charges being alternately negative and positive, the bands of charge spreading out or radiating from the antenna in the manner shown in the illustration. These waves are subject to various influences which have a tendency to refract or reflect the waves much in the manner of light waves.



Illustration showing the arrangement of the electric and magnetic field around a radiating antenna.

As these waves move out from the antenna they gradually increase in height, although the distance between the "feet," i.e., from one wave to another, remains the same. This distance is known as the wave-length. (See *Reception of Electromagnetic Waves*, also *Wave-length, Radiation Transmission.*)

ELECTROMETER—An instrument used for measuring potential differences (voltages) and, under certain conditions, power in *watts.* The operation of the instrument depends upon the attraction or repulsion of electrostatic charges and it may be used for either direct or alternating current measurements. (See *Voltmeter, Electrostatic.*)

ELECTROMETRY—The practice or science of electrical measurement. (See *Meter, Voltmeter.*)

ELECTROMOTIVE FORCE—Symbol E or e—abbreviation E.M.F. The force or electrical pressure which starts and maintains a current of electricity through a conductor. Electromotive force is commonly referred to in terms of volts and is abbreviated E.M.F. The electromotive force in electricity is analogous to the difference of level which produces pressure in pipes carrying water and forces the water to flow. Electromotive force is produced by a difference of potential, and this in turn sets up the flow of current. The illustration *Fig. 1A* shows a simple primary cell or electrolytic cell, and *Fig. 1B* is the analogous action of two tanks holding water, connected by a pipe and so arranged that the water level in one tank is higher than in the other, thus having a difference of level and creating pressure which makes the water flow. The water in tank A being at a higher level than in the other, the pressure causes the water to seek its common level and it flowed into tank B through the pipe. This flow continues as long as there is difference of level. In the case of the cell *Fig. 1A* there are two electrodes, one of which is at a higher potential than the other. That is to say, one is in a state of higher electrification than the other, causing a difference of potential and producing an electromotive force. This force is in the direction from the point of greater potential to point of lesser potential as in the case of the water, and causes a flow of current in that direction. Here the flow is from B to A in the electrolytic solution and from A to B externally through the conductor C. Thus as long as there exists a difference of potential, current will flow in an attempt to equalize the potentials. (This statement holds true only under ideal conditions. See *Polarization.*) This flow of current in the illustration *Fig. 1A* is according to *Ohm's law* (q.v.), i.e., a difference of potential of one volt will cause one ampere to flow through the external circuit when the resistance of the circuit is one ohm. (See *Ampere, Ohm, Volt, Resistance.*)



Fig. 1-A. A simple primary or electrolytic cell.



Fig. 1-B. Water in tank "A" seeks its level by discharging into tank "B" in a manner analogous to the flow of electric current where a potential difference exists.

ELECTRON—The smallest negative charge of electricity known. An English investigator, Dr. Johnstone Stoney, is credited with having named the electron, although it was so named by him in anticipation of its being isolated and measured. The actual proof of the earler assumptions was due to Sir J. J. Thomson and others, who actually measured, and in all effect weighed, the minute particles of negative electricity. (See *Electron Theory.*)

ELECTRON FLOW—The theory of movement of free electrons along a conductor through which an electric current is flowing. (See *Electron*, also *Current, Assumed Direction of Flow.*)

ELECTRON EMISSION—The emission or discharge of electrons or minute particles of negative electricity from a heated body, particularly in a vacuum. The emission of electrons in a vacuum tube is the basis of operation of all vacuum tubes as used in radio. (See *Electron Theory*, also *Vacuum Tube, Theory of Operation.*)

ELECTRON THEORY—The assumption that the atoms of all substances contain one or more particles of negative electricity, which is of course paramount to saying that all matter is electricity. These particles are known as electrons, and while the assumption is referred to as a theory, it has been rather definitely proven by numerous experiments, and electrons have actually been measured. Under the electron theory it is assumed that the charge carried by a single electron is the smallest possible charge which can exist in nature and that no charge of electricity exists or can be produced which is not an integral multiple of this charge. (Note: This is merely a mathematical way of stating that any charge of electricity is equivalent to the combined charges of a certain number of electrons.) Probably the most accurate conclusion regarding the charge carried by an electron is due to experiments carried on by Prof. A. E. Millikan of the University of California. His measurements state this charge of a single electron as being 4.77×10^{-10} electrostatic unit, which is 1.59×10^{-19} of a *coulomb* (q.v.). While the mass or weight of an electron is said to vary with its velocity, assuming a velocity of less than one-tenth that of light, the mass will be 8.9×10^{-28} grams. This is approximately one seventeen hundredth of the weight or mass of an atom of hydrogen. For purposes of calculation the electron is assumed to be in the shape of a sphere. The radius has been estimated at approximately 10^{-13} centimeter. When it is considered that a centimeter is somewhat less than half an inch it is readily seen that an electron is an infinitesimal affair.



Illustration showing the electron, or negative particle, revolving around the proton or positive nucleus.

The figures as to velocity of electrons vary somewhat with different authorities, but it is probably about 100 kilometers (approximately 62½ miles) per second at a temperature of zero degrees centigrade, the speed increasing as the temperature rises. Electrons may be understood as comprising minute solar systems of their own. In the illustration the *electron* or negative particle is shown revolving around the *proton* (q.v.) or positive nucleus in the manner of a planet revolving around the sun. This represents a normal atom of hydrogen, the simplest of all atoms, which, as shown, is composed of a single positive nucleus and a single electron revolving around it. In the case of an atom of helium there is a doubly charged positive nucleus, or proton, and two negative electrons revolving around it. Other atoms have as many as 92 electrons.

All vacuum tubes used in radio operate on the basis of the emission of electrons from a heated filament within the tube. These electrons are being emitted from the hot filament at all times during operation of the tube. When the incoming signals are such as to charge the grid negatively they are repelled and held back to the filament, thus offering no path for the signals. When the incoming signals have reversed their polarity, as they do thousands of times each second, the grid will be positively charged and the electrons will be aided in their travel to the plate, thus forming a conductive path for the currents. This, of course, results in the elimination of one-half of each cycle of the incoming currents or oscillations. That is to say, they are rectified to direct pulsating currents. (See *Amplifier, Vacuum Tube, Theory of Operation* and *Space Charge.*)

ELECTRON RELAY—A term occasionally applied to a three element tube (vacuum tube). This alternate term is obviously derived from the fact that the vacuum tube makes use of the path of electrons and in effect acts as a relay. (See *Electron.*)

ELECTRON TUBE—Any tube using a high vacuum and depending for operation on the emission of electrons from a heated *cathode.* (See *Electron,* also *Vacuum Tube.*)

ELECTRONEGATIVE—Having the property of being attracted to the positive pole of an electrolytic cell. The electronegative component. (See *Anion,* also *Cathion.*)

ELECTROPOSITIVE—Having the property of being attracted to the negative pole of an electrolytic cell during electrolysis. The electropositive component. (See *Anion,* also *Cathion.*)

ELECTROSCOPE—A device for detecting minute differences of potential (voltages). Such a machine will not measure the voltage but merely indicate its presence. The simplest form of electroscope is shown in the illustration. Here a ball B, composed of the pith of some wood, preferably elder due to its extreme lightness, is suspended by a thin silk thread from an insulated stand. The object under investigation is moved near the pith ball, which will be repelled or attracted by the object if the object is in a state of electrification; but will remain motionless if no difference of potential exists. (See *Voltmeter, Potential, Difference of.*)



Simplest form of electroscope.

ELECTROSE—An insulating composition much used in electrical power work and for radio purposes. It has very high compressive strength, is hard and tough without being brittle, and is moisture, water and oil proof. Electrose is used extensively for antenna insulation. (See *Insulator*).

ELECTROSTATIC—The term used to designate EMF's (electromotive forces) or potentials, charges, etc., and the resultant forces. That is to say, electricity at rest or stationary in a body in order to distinguish it from the forces due to *electro-dynamics* (q.v.).

ELECTROSTATIC CAPACITY—The amount of electricity which a condenser or similar body is capable of storing. If a condenser is capable of receiving and storing one *coulomb* of electricity under a potential of one *volt* it is said to have an electrostatic capacity of one *farad,* which is the unit of electrostatic capacity. The electrostatic capacity of a condenser depends on several factors, mainly the size of the plates and the nature and thickness of the dielectric material (insulating sheets). (See *Capacity,* also *Condenser.*)

ELECTROSTATIC CHARGE—The presence of electricity in the form of electrostatic lines of force in a body such as a charged conductor. (See *Charge.*)

ELECTROSTATIC COUPLING—The association or coupling of circuits one to another by means of electrostatic action, i.e., condensers. Any capacitive association of one circuit with another. (See *Coupling.*)

ELECTROSTATIC FIELD—A region wherein forces are present and exerted due to the presence of electric charges. It is the area immediately surrounding a charged body. (See *Field, Electromagnetic,* also *Field, Electrostatic*).

ELECTROSTATIC FLUX—Lines of force making up an electrostatic field. (See *Field, Flux,* also *Flux, Electrostatic*).

ELECTROSTATIC FLUX DENSITY—The density or number of electrostatic lines of force in a unit area of an electrostatic field. (See *Electrostatic Field,* also *Flux Density.*)

ELECTROSTATIC FORCE—The force due to interaction of electric charges. (See *Electrostatic Field,* also *Electrostatic Flux Density.*)

ELECTROSTATIC INDUCTION—The production of a charge in a body due to the presence of an opposite charge in a nearby conductor, or synonymous with displacement in the case of a condenser. Electrostatic influence or induction is the basis on which condensers operate. In the illustration *Fig.* 1 is a simple circuit containing a source of potential, which in this case is a battery. As the circuit is closed through the key a momentary flow of current takes place. This flow of current is accompanied by a condition of electric strain in the insulating material of the condenser. The electrically strained dielectric or insulating material exerts a back pressure against the pressure or force of the battery, and when this back pressure is equal to the original battery pressure the flow ceases. The strain in this dielectric is known as *electric displacement* and this displacement can be transmitted or passed on to neighboring parts of the medium and thence into space. Under the proper conditions this displacement and the magnetic field which accompanies it may be detached from the circuit and move independently in space. This is the fundamental process in the radiation of *electromagnetic waves* (q.v.). Now, in *Fig.* 2, A and B represent two conductors, both insulated. If conduc-



Fig. 1. A simple circuit for illustrating electrostatic induction.

tor A has a positive charge and is brought close to conductor B, although not in actual contact with it, the result is a displacement of electric charge which results in the near side of conductor B becoming negative, while the opposite side assumes the same sign (positive) as conductor A. Actually B has received no charge, but has been placed in a state of strain due to electrostatic induction between it and the conductor A. Due to the negative charge induced on B, the positive potential difference of A has been decreased and in order to maintain the constant potential it must be given a further supply of electricity. In this manner it is actually possible to store the electricity by electrostatic induction between two conductors or plates, by reason of the strain in the insulating medium—air in the case of the two conductors—which in turn passes the displacement on to conductor B. (See *Conductor*, *Capacity*, *Electrostatic*, also *Induction.*)



Fig. 2. Illustration of displacement of electric charge due to proximity of charged conductors.

ELECTROSTATIC LEAKAGE—The gradual loss through leakage, of the electrostatic charge in a body, due to the fact that perfect insulation is impossible to obtain. (See *Electrostatic Induction.*)

ELECTROSTATIC LINES OF FORCE—The lines of force traversing an electrostatic field. That is to say the *electrostatic flux* (q.v.).

ELECTROSTATIC STRAIN—The strain or state of stress in which a body is placed when in an electrostatic field. In a condenser, the strain experienced by the *dielectric* (q.v.) when the condenser is in a state of charge. (See *Condenser*, also *Capacity*, *Electrostatic*).

ELECTROSTATIC SYSTEM—The electrostatic system of C.G.S. units. One of the absolute unit systems in electrical practice. (See *C.G.S.*, also *Electrostatic Units* and *Electromagnetic Units.*)

ELECTROSTATIC UNITS—A system of measurement used in electrical engineering based on the unit of electric quantity under the *C.G.S. system* (q.v.). This unit quantity of electricity is the quantity of electricity which, placed on a small sphere will repel an equal quantity of electricity of the same sign (both negative or both positive) on a similar sphere with a force of one *dyne.* (q.v.) when the centers of the respective spheres are one centimeter apart. With this definition it is assumed that the spheres are in a vacuum, otherwise the distance between centers would vary according to the dielectric or insulating medium. (See *C.G.S.*, *Electromagnetic Units*, also *Conversion Factors.*)

ELECTROSTATIC VOLTMETER — A meter for measuring voltage, depending for its action on the electrostatic action between a fixed and a moving plate connected respectively to the two poles or terminals between which the source of potential is connected. (See *Electrostatic Force*, also *Voltmeter.*)

ELECTROSTATIC WATTMETER — A type of wattmeter depending on the electrostatic action between two sets of fixed and moving plates. (See *Electrostatic Force*, also *Wattmeter.*)

ELECTRO-THERMAL METER — The term sometimes applied to a *hot-wire ammeter* (q.v.) or voltmeter operating on the principle that the heat generated by the passage of an electric current through a constant resistance will be equal to the square of the current. (See *Thermal Ammeter.*)

ELEMENT—A term primarily applied in chemistry to the substances which are not subject to decomposition by electric analysis (see *Electrolysis*). These elements are hydrogen, helium, etc. The term is also used quite generally to denote components such as the electrodes in a primary cell or the plate, grid and filament members of a vacuum tube. (See *Cell*, also *Vacuum Tube.*)

EMANATE—"To flow forth or proceed, as from a source."—Webster. Thus, emanating, issuing from, as the emanation of electrons from a hot filament in a vacuum tube. The throwing off of electrons. (See *Electron Emission.*)

E.M.F.—The abbreviation for electromotive force. The practical unit of E.M.F. is the volt. (See *Electromotive Force*, also *Volt.*)

EMISSION—The act of sending forth. Used chiefly to designate the emission of electrons from the filament of a vacuum tube as used in radio. The flow of these electrons between filament and plate is controlled by the grid. (See *Electron Emission*, also *Vacuum Tube, Theory of Operation.*)

EMISSION CURRENT—In a vacuum tube for transmitting it is the product of the tube current multiplied by the plate voltage and is generally given in watts. Generally speaking, the power for which the tube is designed. (See *Transmitting Tube*, *Power Rating*, also *Vacuum Tubes.*)

EMISSIVITY OF FILAMENT — The ability of a filament to emit electrons when heated by an electric current. (See *Electron*, also *Vacuum Tube.*)

EMPIRE CLOTH OR PAPER—A closely woven cambric coated with two or more films of an oxidized oil, or a tough paper treated with some oxidized oil. Empire products serve as insulating materials for transformers, condensers and various other devices requiring thin insulating sheets. In a transformer for relatively high voltages, insulated paper is used between the layers of windings and in certain types of fixed condensers it is used as a dielectric material. The cloth has a higher breakdown strength; that is, it will stand higher voltages than paper. (See *Breakdown Potential*, also *Dielectric.*)

ENAMELED WIRE—Wire, generally copper, covered with a coating of enamel as an insulating covering and to protect it from moisture and corrosion. (See *Magnet Wire.*)

ENDODYNE—A term occasionally used to describe reception of radio signals by means of locally generated oscillations such as in the case of the *heterodyne* (q.v.), but wherein these oscillations are created by a circuit or system that is part of the receiving circuit and not a separate arrangement. (See *Self Heterodyne.*)

ENERGY—The capacity for doing work in an electrical sense. Energy is something furnished to a body by means of work done on it. Thus, if a ball is thrown, the operation of throwing is the work, and the ball itself in traveling performs work, the means of doing this work being the energy. There are two kinds of energy, *potential*, as in the case of electricity, and *kinetic*, the energy of a body due to motion. Kinetic energy belongs properly in the realms of mechanics and so will be passed over here with only this brief mention.

When we speak of a difference of potential in a primary cell, it means in effect that the body or cell has potential energy. That is to say, the energy is present although not active. If, now, a wire is connected across the two terminals of the cell, the difference of potential will cause electric current to flow from one pole to the other. Actually, in a cell of this type, we have chemical energy stored up. When a circuit is completed, the stored chemical energy is converted into electrical energy or creates the difference of potential, which in turn causes current to flow and electrical *work* is thus done. (See *Potential*, also *Voltage* and *Generator.*)

EPSTEIN HYSTERESIS TESTER—A device for measuring *hysteresis* and *Eddy current loss* in a sample of sheet iron by using an alternating current wattmeter. The device is used for determining the properties of samples of iron, particularly those to be used for transformers. (See *Eddy Currents*, also *Transformer*, *Hysteresis* and *Wattmeter.*)

EQUIVALENT RESISTANCE — The value which a resistance would be required to have in order to permit the same quantity of current to flow with the same applied electromotive force (voltage) as in the case of a piece of apparatus wherein there are other factors besides pure resistance to determine the amount of current. (See *Impedance*, also *Reactance.*)

ERG—The fundamental unit of mechanical work under the *C.G.S. system* (q.v.). This is defined as the work done by a force of one *dyne* (q.v.) when the body producing the force and the body on which the force acts are one centimeter apart. (See *Joule*, also *Practical Units.*)

E.S.U.—Abbreviation sometimes used for *electrostatic units* (q.v.). (See *Electromagnetic Units.*)

ETHER—or AETHER—The term used to denote the supposed or hypothetical medium by means of which electromagnetic and light waves are propagated. (See *Ether Waves.*)

ETHER WAVES—Term sometimes applied to electromagnetic or radio waves on account of the assumption that they travel through the supposed medium ether. The assumption of an all-pervading medium such as ether has been the basis of the major part of the extensive research work carried on with light and electromagnetic waves for many years. Various experiments have shown beyond reasonable doubt that there is some such medium, capable of conducting or rather permitting passage of light waves and radio waves. So accurate has this work been that it has been proven beyond question that light waves travel through the ether with the tremendous velocity of 186,000 miles per second (approximately). It has also been determined that radio waves travel at this same speed through the ether. It has further been proven that radio waves all travel at the same identical velocity, regardless of their length, form and other factors. (See *Electromagnetic Waves*, also *Theory of Propagation of Electromagnetic Waves.*)

EXCITER—A small direct current dynamo used for the purpose of exciting the field magnets of an alternating current generator. Such a device is generally a part of the main machine and mounted on the main shaft, but it may also be a separate unit. The purpose is to furnish current to the field magnets (electromagnets) to create a magnetic flux. (See *Alternator*, also *Generator.*)

EXPLORING COIL—A coil of insulated wire wound on a rotating form as an integral part of a direction finder or *goniometer.* (See *Direction Finder*, also *Goniometer.*)

F

F—The abbreviation for *dielectric field intensity* (see *Field*, also *Dielectric*), also used as the symbol for the unit of *magneto-motive force*, the *gilbert* (q.v.). The small or lower case f is sometimes used to denote the *farad*, the practical unit of *electrostatic capacity* (q.v.) and also as a symbol for *frequency* (q.v.).

FADING—The tendency of radio signals to decrease in volume or amplitude, or to fade. The strength of a signal is seldom the same at different hours of the day or night, generally being stronger during the dark hours of the night. This has been attributed to a variety of causes, the most plausible being that the air is more free of disturbances during the night and thus permits more ready passage of the waves through the ether. The difference between the strength of signals in the daytime and at night is sometimes very pronounced, but the phenomenon of fading is usually noticed only when distant signals are being received. It has been fairly definitely established that fading of signals is due to the reflection of the transmitted waves. (See *Wave Distortion*, also *Reflection and Refraction.*)

FALL OF POTENTIAL—See *Potential Drop.*

FAN AERIAL—An aerial, usually for transmission, constructed in the shape of a fan. (See *Aerial.*)

FAN CONNECTOR—A small triangular or fan-shaped piece of metal arranged with several holes along one edge, with set screws for fastening in each the several wires of the lead-in of a multi-wire aerial. The lower apex is fitted with some sort of connecting device to permit a single wire to be led in to the receiver. (See *Lead-In.*)

Illustration by
Courtesy of Radio Specialty Co., Inc.

Fan Connector—The leads from each wire of a multi-wire aerial go to the wide portion and are held by the set screws: the lead to the set goes to the small end.

FARAD — The unit of *electrostatic capacity.* It is the practical unit of capacity and is defined as the capacity of a condenser that is capable of being charged to a potential difference of one volt by a charge of one ampere for one second; i.e., one *coulomb* (q.v.). "Farad" is a contraction of the name of the distinguished English scientist *Michael Faraday* (q.v.). Inasmuch as the farad is too large a unit for practical purposes, the *micro-farad*, or one millionth of a farad, is commonly used. (See *Electrostatic Capacity*, also *Condenser.*)

FARADAY, MICHAEL. Born 1791, died 1867. An English scientist famous for his discoveries in chemistry, electricity and magnetism. He first produced the rotation of the magnetic needle around the electric current in 1821, based upon Oersted's discovery of electromagnetism in 1820; he discovered electromagnetic induction (1831), a principle upon which is founded the development of dynamo machinery; specific inductive capacity (1838); magnetic polarization of light (1845); diamagnetism (1846). He was a brilliant experimenter, and contributed greatly to the knowledge upon which is based present-day practice of electricity.

Michael Faraday.

FEEBLY DAMPED—In spark transmission, signals that are only slightly damped. Where each succeeding oscillation in a train of oscillations is of slightly lesser *amplitude* (q.v.) than the one preceding it, the signals are said to be slightly damped to distinguish them from signals that are highly damped and thus die out quickly. (See *Damping*, also *Damped Waves.*)

FEED—In electrical parlance, to furnish with a current of electricity. (See *Feed-Back.*)

FEED-BACK—A term applied in radio to the coupling of one circuit to another, whereby a portion of the current present in one circuit is fed back or returned to the other circuit. The common use of the term is in reference to regeneration, where a certain portion of the radio frequency current present in the plate circuit of a detector is returned to the grid circuit of the tube by some form of coupling between the two circuits. It may also apply to the tendency of high-frequency currents to become transferred from one circuit to another due to undesired coupling between two or more circuits. The illustration shows a simple feed-back or regenerative circuit. The incoming signal energy is transferred from the primary of the coupler to the secondary by means of inductive coupling and tuned by the condenser C. A grid condenser and leak GC are placed in the grid circuit in the customary manner. A feed-back or reaction coil T is placed in the plate circuit and inductively coupled to the main coil. A portion of the radio frequency current in the plate circuit or output circuit is transferred back to the grid circuit by the coupling effect between the coil T and the secondary of the coupler. This serves in effect to reduce the resistance of the grid circuit and produces more current in the output or plate circuit, thus acting as a form of amplifier. (See *Regeneration, Tickler.*)



Regenerative circuit in which the coil "T" returns, or "feeds back" to the grid circuit a portion of the radio frequency current in the plate circuit, resulting in increased amplification.

FEED-BACK COIL—An inductance coil placed in the plate circuit of a regenerative receiver and arranged in inductive relation to the grid coil (secondary of tuner) for the purpose of effecting feed-back or regeneration. (See *Feed-Back*, also *Regeneration.*)

FEED-BACK COUPLING—Any process by which the plate circuit of a detector is coupled to the grid circuit to allow a portion of the output current to be transferred back to the grid circuit to produce regeneration. (See *Feed-Back*, also *Regeneration.*)

FEED-BACK EFFECT — The effect of feeding back of currents from one circuit to another as in the case of a *regenerative circuit* (q.v.). Generally the expression "feed-back effect" refers to an undesired feed-back. This may be the action of radio frequency components of the currents present in one part of a circuit being fed back to another part of the circuit due to the coupling effect of various coils or other devices used in the circuit. (See *Feed-Back*, also *Regeneration.*)

FEED-VOLTAGE MODULATION — A process of modulating or varying the amplitude of a radio frequency alternating current to correspond to any wave form of speech vibrations as in radio broadcasting. The system involves the introduction of additional power into the circuit of the radio frequency generator until the desired wave form variations are obtained. This is done particularly in the case of a vacuum tube transmitter, in which case the voltage supplied to the plate of the tube is altered (increased or decreased) to accomplish the purpose. (See *Modulation.*)

FERRO-MAGNETIC MODULATOR—A device for modulating or varying the amplitude of radio frequency current to correspond in wave form to the speech or music vibrations in broadcasting. The system makes use of what is known as the *hysteretic energy absorption* of iron, or in some cases utilizes the variation of inductance of iron-core coils. (See *Modulation*, also *Ferro-magnetic Substances.*)

FERRO-MAGNETIC SUBSTANCES — Elements or compounds such as iron, nickel, cobalt and others which are strongly attracted by magnetic fields of force. Such substances vary widely in their magnetic properties when subjected to temperature changes. Soft iron loses its magnetization almost immediately on removal of the magnetizing source, and for this reason it is used as a pole piece in an electromagnet. (See *Electromagnet*, also *Magnetism* and *Magnetic Properties.*)

FESSENDEN, REGINALD AUBREY. —Canadian-American Radio expert. Born at Milton, Canada, October 6, 1866, and educated at New York and Port Hope, Ontario. Fessenden became inspecting engineer for the Edison Company, New York, and afterwards professor of physics and electrical engineering at Western University, 1892. Professor Fessenden is the author of a well-known system of wireless, and below are briefly described some of the patents bearing his name.

In 1906 and 1907 Fessenden invented a number of microphone transmitters which carried heavy currents for long periods, and also a heavy current telephone relay which allowed the controlling of heavy currents by means of small currents originating in an ordinary microphone circuit or coming from a telephone line. One of these transmitters was called by Fessenden a trough transmitter. It consisted of a soapstone annulus to which were clamped two plates having platinum-iridium electrodes. Through a hole in the center of one plate passed a rod attached at one end to a diaphragm, and at the other to a platinum-iridium spade. The two outside electrodes were water-jacketed. This form of transmitter required no adjusting, all that was necessary being to place about a teaspoonful of carbon granules in the center space. It was able to carry as much as 15 amperes continuously without articulation falling off, and had the advantage that it never packed. By a combination of the trough transmitter and a differential magnetic relay, Fessenden produced a transmitting relay for magnifying very feeble currents. An amplification of fifteen times is possible without any loss of distinctness. Fessenden is also responsible for a duplex system of Radio telephony, and the *heterodyne* method of reception is due to him. Fessenden has written largely on radio subjects, and is one of the leading authorities on both transmission and reception.

Reginald Aubrey Fessenden.

FIBER—or **FIBRE**—A term used for a variety of substances, composed of fine slender thread-like materials, particularly a composition of vulcanized or compressed paper. It is much used in radio as an insulating material for panels and connection blocks. It is not as efficient as insulating medium as bakelite or some forms of rubber composition, but is durable, cheap and comparatively easy to drill. (See *Bakelite.*)

FIELD—The space occupied by electric or magnetic lines of force. (See *Electric Field.*)

FIELD DENSITY—The strength of an electric or magnetic field. It is measured by the number of electric or magnetic lines of force contained in a given cross-sectional area. (See *Density. Flux,* also *Electric Field* and *Field, Magnetic.*)

FIELD, ELECTRIC—The space traversed or occupied by electric lines of force. (See *Electric Field.*)

FIELD, ELECTROMAGNETIC — The total area traversed by electromagnetic lines of force. The region in which electromagnetic lines of force are exerted. (See *Field*, also *Electrostatic Force.*)

FIELD, ELECTROSTATIC—The region in which electrostatic forces are present or exerted. The total area traversed by electrostatic lines of force. (See *Field,* also *Electrostatic Flux.*)

FIELD MAGNET—An *electromagnet,* usually a core of soft iron surrounded by a winding of insulated wire, employed in generating machines to produce a strong magnetic field. As the *armature* of a *generator* revolves the conducting surfaces pass through the *magnetic field* created by the *field magnets.* This field may be merely the ordinary magnetic force due to permanent magnets, but is usually due to the powerful magnetic lines of force resulting from passage of electric current through electromagnets. (See *Alternator*, also *Alternating Current, Theory of Production* and *Electromagnet.*)

FIELD, MAGNETIC—The region through which magnetic flux passes. Usually refers to the space (air) through which the magnetic flux lines pass as distinguished from the activity in the iron path tself. (See *Field*, also *Magnetic Flux.*)

FIELD REGULATOR or RHEOSTAT—Any device for varying the magnetic strength of the field magnets in a dynamo or electric motor, by which variations certain changes may be accomplished in the operation or performance of the machine. A field rheostat is often used in an electric motor to vary the strength of the field and thus either increase or decrease the speed of the machine without the necessity of changing the applied voltage. If the strength of the field (magnetic) is reduced by insertion of resistance, the armature or rotating part speeds up in an attempt to generate the same *counter-electromotive force* (q.v.), which means greater speed. On the other hand, if the resistance is removed—that is, the strength of the field increased—the fact that the armature is running through a stronger field reduces the speed of rotation, the same counter-electromotive force being present. The use of a field regulator or rheostat in connection with a generator is for the purpose of varying the output voltage without the necessity of altering the speed of the machine. The illustration shows the connection of a field rheostat or regulator in the circuit of the *shunt wound generator* (q.v.). (See *Generator, Rheostat, Resistance.*)



Illustration showing method of connecting a field rheostat or regulator in the circuit of a shunt wound generator.

FILAMENT—A fine wire, one of the elements of a vacuum tube, which is heated to throw off electrons. The term is also used to refer to the fine wire used in an incandescent lamp. The filament of a vacuum tube is generally made of tungsten and is supported by glass pillars within the tube in such manner as to be insulated from the other elements. Filaments are made to be heated with various voltages from 1.1 to 6 volts in most receiving tubes, but much higher in the case of high power transmitting tubes. The filament may consume considerable current as in the old styles of six-volt tubes which consumed one ampere. The modern tubes have thoriated filaments, tungsten treated with thorium, which permits maximum efficiency with a minimum of current consumption. When the filament is heated in the vacuum tube, by having the proper amount of voltage applied, electrons are thrown off and fill the space between filament and grid and grid and plate as shown in the illustration. (See *Electron Theory*, also *Vacuum Tube, Theory of Operation.*)



When an "A" battery is connected to the filament terminals, heating the filament, electrons are thrown off and fill the space between filament, grid and plate.

FILAMENT BATTERY—The battery or cell used in lighting the filament of a vacuum tube. These range from a *dry battery* (q.v.) having a voltage of one and a half volts, to storage batteries of six volts. Filament batteries are connected across the filament of a vacuum tube in the manner shown in the illustration. The rheostat is inserted to permit the supply of current to the filament to be varied and thus change the operation of the tube. (See *Filament*, also *Vacuum Tube, Theory of Operation.*)



Method of connecting "A" battery in series with rheostat to regulate filament of vacuum tube.

FILAMENT CONSUMPTION — The amount of current consumed by the filament of a vacuum tube. The current requirements of vacuum tubes are always stated by the manufacturer, either in amperes or fractional amperes, or in the case of extremely low consumption, in thousandths of an ampere (milliamperes). Some typical examples are the UV201A and C201A types, which require one-quarter ampere at five volts; the WD11 and 12 and C11 and 12 types, which require one-quarter ampere at approximately 1.1 volts, and the UV200 and C200 tubes, which require one ampere at six volts. Of the so-called standard types, the UV199 and C199 tubes consume the least current, requiring but sixty milliamperes or .06 ampere, with from three to four and a half volts. The statement that a certain tube consumes one-quarter ampere indicates that in operation one-quarter ampere is consumed each hour, this current being supplied by dry cells or storage batteries known as the *"A" battery* (q.v.).



The current produced by the dry cell battery, flowing through the rheostat and filament, is consumed by the filament, at a rate depending upon the type of tube.

It will be apparent from the above that the more current consumed by the filament the greater will be the drain on the dry cells or storage battery. For this reason, and also to lengthen the life of the filaments, it is well to operate the tubes at the lowest efficient brilliancy. The brilliancy of the filament may be controlled by adjustment of the filament rheostat. In the illustration the usual "A" battery, which in this case is a dry cell, is shown connected to the filament of a vacuum tube with a rheostat in series between one filament connection and the negative terminal of the dry cell. Now as the arm of the rheostat is moved from A toward B resistance is introduced into the circuit between the filament and dry cell. As this resistance increases the current in the circuit of the filament will decrease according to *Ohm's Law* (q.v.); i.e., Current = Voltage ÷ Resistance, the current in amperes or fractional amperes and the resistance in ohms. (See *Ampere, Current, Filament Resistance or Rheostat* and *Vacuum Tube.*)

FILAMENT CURRENT — The current used to light the filament of a vacuum tube. Different tubes require different amounts of current; that is, one tube may consume a small fraction of an ampere and another may require a full ampere. Of the tubes most commonly used, the UV199 type uses the least current, this tube requiring only .06 of an ampere each hour. The WD11 and 12 types require one-quarter ampere per hour and also the UV201A, while the now obsolete UV200 and UV201 required a full ampere. The 199 type operates with filament voltage of 3 volts, although it is often used with three dry cells in series which deliver 4½ volts; the WD11 and 12 require 1.1 volts each, which is usually furnished by a dry cell, while the UV201A type is operated with a six-volt storage battery. (See *Vacuum Tubes, Types of*, also *Vacuum Tube, Theory of Operation.*)

FILAMENT, FORMULA FOR ELECTRON FLOW—The extent of electron emission—that is, the number of electrons—emitted from a hot filament in a vacuum tube is subject to certain definite laws. In ordinary practice the actual number of electrons are not referred to, the ability of the filament to emit electrons being measured in fractional amperes of output current. Thus a tungsten filament having a diameter of .0125 centimeters operating with a power dissipation of 3.1 watts per centimeter of length has been found to emit a current of .03 amperes. This result was obtained with a filament having a clean surface and with no absorbed gas on its surface. The formula for electron flow most commonly used is as follows:

$$I_B = AT^{1/2}\,\epsilon - \frac{b}{T}$$

I_B is the electron current in milliamperes per square centimeter of filament surface, T is the absolute temperature and A and b depend on the metal used for the filament.

FILAMENT RESISTANCE or RHEOSTAT—A device placed in the filament circuit of a vacuum tube, connected between the filament battery and either filament lead on the tube socket for the purpose of reducing or controlling the filament voltage. The illustration Fig. 1 shows one type of filament rheostat which is used to permit variation of the filament current. Fig. 2 shows the manner of connecting such resistance in the filament circuit of a vacuum tube. Fig. 3 illustrates a type of filament control known as an automatic rheostat. In this form of filament resistance a fine wire is placed in a glass tube filled with an inert gas. The wire has the property of increasing its resistance rapidly with any increase in the current passing through it. It is thus possible to arrange such a device to pass only a fixed amount of current for any type of vacuum tube. The device is thus not only an automatic rheostat, but also a safety valve which prevents excessive current reaching the filament and injuring it. These controls are coming into widespread use due to these features and the fact that they reduce the number of controls necessary to operate a receiver. Fig. 4 shows a resistance which is used in series with a rheostat having small resistance in order to enable its use with tubes requiring less current to operate. (See *Filament*, also *Vacuum Tube.*)



Illustration by Courtesy of The Cutler-Hammer Mfg. Co.

Fig. 1. A type of rheostat used to control the flow of current to the filament of a vacuum tube.



Fig. 2. Showing method of connecting a rheostat in "A" battery circuit of a vacuum tube.

Illustration by Courtesy of the Radiall Co.

Fig. 3. A type of automatic rheostat.



Illustration by Courtesy of The Cutler-Hammer Mfg. Co.

Fig. 4. Resistance used in series with a rheostat having a small resistance in order to enable its use with tubes requiring less current.

FILAMENT, THORIATED—A filament or heating element of a vacuum tube in which a certain amount of *thorium* (q.v.) has been incorporated. The introduction of this rare metal into the filament in small quantities gives it the property of emitting electrons at a relatively low temperature. From a practical standpoint this permits a vacuum tube to be operated with a low *filament consumption* (q.v.). A common example of the use of thorium in filaments is that of the UV201A or C201A vacuum tubes, which operate with a filament voltage of 5 volts and consume but one-quarter ampere of current, giving essentially the same results as the former type UV201 and C201 tubes which consumed one ampere. The value of thorium used in this manner is readily appreciated, the current consumption being materially lessened and the life of the tube conceivably lengthened. (See *Thorium Treatment of Filaments*, also *Vacuum Tubes, Type UV201A and C201A.*)

FILTER—In radio, a device arranged to permit passage through an electrical circuit of currents of certain frequency or *frequencies* (q.v.) while excluding others of different frequencies, or any device for producing smooth direct current from a generating source such as a *direct curent dynamo*, or for smoothing out *rectified direct current.* Filters of one sort or another are much used where rectified direct curent or direct current from a generator is to be used for operation of tubes in radio transmission or reception. In the case of rectified direct current, that is the current derived from any device for changing alternating to direct current, there is always present a tendency on the part of the current to surge or ripple. In other words, it is not smooth and of constant voltage, or there may be present a generator hum which will seriously interfere with proper operation of a tube. The illustration shows the conventional method of filtering rectified direct current for use as plate supply with vacuum tubes in receiving sets. This system may also be used in connection with the output of a direct current generator or dynamo. A filter circuit may be arranged to pass a band of frequencies (see *Band Pass Filter*) or it may be made to pass either high or low frequency current. (*See Filter, High Pass;* also *Filter, Low Pass.*)



Conventional method of filtering rectified direct current for use as plate supply of a vacuum tube.

FILTER, BAND PASS—See *Band Pass Filter.*

FILTER CONDENSER—The condenser, either fixed or variable, forming a part of a circuit for filtering. (See *Filter*, also *Acceptor, Wave Trap* and *Rejector.*)

FILTER, HIGH PASS—A filter circuit arranged to permit current above a certain frequency to pass freely while blocking out or attenuating all frequencies below it. (See *Filter*, also *Filter, Low Pass.*)

FILTER, LOW PASS—A filter circuit arranged to permit currents below a certain frequency to pass freely while blocking currents of higher frequency. (See *Band of Frequencies*, also *Filter, High Pass.*)

FIXED COILS—Inductance coils as used in radio circuits, having no mechanical means of variation, such as in a *Variocoupler or movable coil.* (q.v.) The majority of tuned radio frequency receivers employ fixed coils, shunted by variable condensers. These are known as *tuned radio frequency transformers.* (q.v.) (See *Coupler, Loose*, also *Coupler, Vario.*)

FIXED CONDENSER — A condenser having a certain definite or fixed value of capacity. Any condenser that is not variable. (See *Condenser*, also *Condenser, Variable.*)

FIXED RESISTANCE—Any resistance device having a fixed or non-variable value. (See *Rheostat*, also *Potentiometer.*)

FIXED DISCHARGER—A fixed *spark gap.* (q.v.) A spark gap used in transmission of radiotelegraphic signals in which the electrodes or sparking surfaces are not moved during operation. (See *Disc Discharger.*)



A type of fixed spark gap.

FLAME MICROPHONE—A type of microphone for radio telephone transmission, wherein the height of a coal gas flame is varied by and according to the speech fluctuations and the resulting pulsations made audible by means of a selenium cell and phones. (See *Microphone*, also *Selenium Cell.*)

FLASH SIGNALLING— See *Code*, also *Morse Light.*

FLAT-TOP AERIAL or ANTENNA—An aerial, generally composed of a number of wires placed adjacent to each other equally spaced on a spreader, or hoop, and suspended parallel with the earth. A flat-top aerial may be of the kind known as the *T type aerial* (q.v.) or in the form of an inverted L. (See *Aerial.*)

FLAT TUNING—A term sometimes applied where the *resonance curve* (q.v.) has a flat top, that is where the peak of resonance is not sharply defined. The effect is known as *broad tuning.* (q.v.) (See *Resonance*, also *Tuning.*)

FLEMING, JOHN AMBROSE. British radio expert. Born in Lancaster, November 29, 1849, he was educated at University College, London, the Royal School of Mines, and St. John's College, Cambridge.

From 1873-74 Fleming was demonstrator at the Royal College of Chemistry, and in 1877 he began work under Clerk-Maxwell at the Cavendish Laboratory, Cambridge. There he carried out a series of experimental researches on the British Association Standards of Electrical Resistance. In 1881 Dr. Fleming was appointed the first professor of mathematics and physics at University College, Nottingham, but the following year he joined the Edison Electric Light Company, and on the amalgamation of the Edison and Swan Companies, he was appointed advising electrician, a post he held for twenty years. In 1885 Fleming was appointed to the newly founded professorship of electrical engineering at University College, London, and he was entirely responsible for the design and equipment of the new electrical and engineering laboratories which were opened in 1893. In 1892 he was elected Fellow of the Royal Society.

Dr. Fleming has been very closely associated for many years with radio telegraphy and telephony, and has since 1899 acted as the scientific advisor to Marconi's Wireless Telegraph Company. He is well known as the inventor of the thermionic two electrode vacuum tube, or glow-lamp detector, which was one of the greatest steps forward in radio telephony.

Dr. Fleming has written a very large number of papers and books on wireless telegraphy and telephony, and his "Principles of Electric Wave Telegraphy" is the standard treatise on the subject. He has also published an "Elementary Manual of Radio Telegraphy and Radiotelephony"; "The Wonders of Wireless Telegraphy"; "The Thermionic Valve and Its Development"; "A Pocket Book for Wireless Telegraphists," and other books. As a lecturer at the Royal Society of Arts he has obtained a world-wide reputation for his lectures on electric oscillations and electric waves, Hertzian wave telegraphy, high-frequency measurements, etc. He has given many lectures on wireless at the Royal Institution.

John Ambrose Fleming.

Fleming was awarded the Hughes gold medal of the Royal Society in 1910 as an acknowledgement of the value of his work in electrical science and engineering, and he has twice been awarded the Institution Premium of the Institution of Electrical Engineers, the highest award for communicated papers, and he is an Albert Gold Medallist of the Royal Society of Arts awarded to him for the pioneer invention of the thermionic valve.

FLEMING'S RULE—A rule for determining the direction of the *induced current* (q.v.) in a circuit. Hold the right


DIRECTION OF MAGNETIC LINES OF FORCE
INDUCED ELECTROMOTIVE FORCE
MOTION OF CONDUCTOR

Method of using the right hand in determining the direction of the induced current.

hand as shown in the illustration with the thumb, forefinger and middle finger as nearly as possible at right angles to each other. If the thumb is then pointing in the direction of motion of the conductor and the forefinger points along the direction of the magnetic lines of force, the middle finger will then point in the direction of the induced electromotive force. (See *Induced Current*, also *Electromotive Force.*)

FLEMING VALVE—The forerunner of the modern vacuum tube. It was invented in 1904 by Professor J. A. Fleming and was for a short time used as a detector in place of the customary crystal or coherer types. The value of the discovery of the Fleming valve lies chiefly in its influence on the course of radio development, as in itself it was not nearly as efficient as a good crystal detector. As a result of the discovery of the Fleming valve, however, many leading scientists bent their efforts toward the discovery of better methods of detecting radio waves, culminating in the three element vacuum tube designed by Dr. Lee De Forest.



Fig. 1. The Fleming valve, which contained but two elements; i. e., filament and plate. It was the forerunner of the modern vacuum tube.

The Fleming valve consists essentially of an incandescent lamp using a filament of carbon, tungsten or tantalum which can be rendered incandescent by an electric current. The filament is sealed in a glass tube which is highly evacuated, that is from which practically all air has been excluded. Surrounding the filament, but separated from it is a metal cylinder, both ends of the filament and the plate being attached to outside connections by means of leads sealed in the tube. The illustration, Fig. 1, shows the general arrangement of such a tube. The operation of the tube is due to the emission of electrons from the heated filament. It was demonstrated by several investigators that a filament made of certain metals has the property of throwing off minute particles of negative electricity or electrons when heated to a relatively high temperature. It was also found (see *Electron*) that these electrons are thrown off in greater profusion when the filament is placed in high vacuum. It was also found that the escape of negative electrons from the filament would in time leave it positively charged, this charge having an attraction for the negative electrons and preventing their escape from the filament. Hence it was necessary to apply a charge of negative electricity to the filament. The electrons were now found to escape in great number, but had the effect of forming a *space charge* (q.v.) of negative electricity around the filament, which in time served to repel the escape of any more electrons. To counteract this tendency a strong positive charge was applied to the metal plate surrounding the filament. This made the plate positive in respect to the electrons and served to attract them away from the filament. The stream of electrons thus affords a path for current to flow from filament to plate, and the action of the tube as a detector of high frequency waves depends on this principle. If the tube is connected as indicated in the illustration, Fig. 2, it will serve to rectify the incoming signals, that is change them from high frequency alternating currents, to pulsating direct current. The action is as follows: The aerial is connected to the secondary circuit by means of a standard coupler. The coils, marked L2, are the primary and secondary of this coupler; C1 and C2 are variable condensers, F the filament of the Fleming valve, B the battery for lighting the filament of the valve and also to supply voltage to the plate, T a pair of headphones, P a 400 ohm potentiometer and R a standard filament rheostat. The incoming signals in the form of high frequency currents, change direction many times each second. Thus, at one instant the plate will have a positive charge while the next instant it will have a negative charge as a result of the changes in direction of the currents impressed across the tube from the antenna circuit. While the plate is positive, electrons will be attracted away from the filament, which at that instant will be negative with respect to the plate. The current thus flows for an instant, stopping when the impressed current changes its direction and makes the plate negative. In this manner we have a flow of current from filament to plate in one direction in the form of surges appearing at every other alternation or change of current. The diaphragms of the phones will respond to these uni-directional surges and will give out sounds almost identical with the original signals transmitted. The tube thus serves as a rectifier of the incoming signals and is known as a detector of high frequency waves, or oscillations. The Fleming valve principle is used in rectifying tubes for changing alternating current to direct current for charging batteries, its use as a detector for radio reception having died out almost entirely. (See *Charger, Storage Battery, Detector, Tungar, Rectigon,* also *Vacuum Tube.*)



Fig. 2. Method of connecting a Fleming valve in a radio receiving circuit.

FLEWELLING CIRCUIT—A modification of the Armstrong Super-regenerative circuit, designed by the American experimenter, Flewelling. In this system, the tendency toward *self-oscillation* (q.v.) is retarded by the use of fixed condensers which are arranged to have a *damping* (q.v.) effect on the grid of the detector tube, automatically controlling the oscillations of the tube. The circuit controls the self-oscillation of the tube without the necessity for the separate control tube used in the Armstrong circuit. The illustration shows the original Flewelling circuit. It is essentially a standard regenerative circuit with certain necessary modifications.

The coils L1 and L2 give magnetic coupling between the plate circuit and the grid circuit. C1 is a variable condenser for tuning and condensers C2, C3 and C4 are of the fixed type and afford a path of relatively low *impedance* (q.v) for the high frequency currents. C5 is the customary grid blocking condenser across which a grid leak is shunted. The usual telephone receivers T, the plate battery B and the filament battery A are included in the circuit in the customary manner. The coils L1 and L2 may be two honey-comb coils having respectively 50 and 75 turns. The tuning condenser C1 should be .0005 mfd. for the broadcast band of wave-lengths and the loop may be almost any form.



The Flewelling circuit.

In operation three forms of current pass through the plate circuit including the coil L2, namely, the direct current from the plate battery B, the unidirectional surges of rectified current due to the action of the tube as a rectifier and the high frequency currents transferred through the medium of the magnetic coupling of the two coils L1 and L2. The battery current is present only in the plate circuit, the condensers C2, C3 and C4 blocking the direct current from the grid circuit. These condensers also block the rectified currents but afford two paths for the high frequency currents or oscillations. The condensers C2, C3 and C4 have definite values, respectively .005, .005 and .006 micro-farads, to allow a by-pass through the grid to the filament, thus causing accumulation of electrons on the grid and stopping oscillation of the tube. The charge then leaks off by means of the grid leak connected across C5, the tube then building up oscillations again and continuing the process during operation. The high resistance connected across C3 is variable and permits control of the by-pass of high frequency current of the grid. Careful adjustment is necessary to obtain maximum signal strength without distortion. (See *Armstrong Circuits, Regenerative Circuit,* also *Super-Regenerative Circuit.*)

FLEX—Term used in Great Britain and occasionally in this country to refer to a number of small wires twisted or stranded together to form a single flexible conductor. (See *Flexible Wire.*)

FLEXIBLE LEAD—Any conductor, particularly the connections from rotary parts of couplers or condensers, in which the conductor is made up of a number of fine wires in such a way that the necessary bending in operation of the unit will not snap the wire as would be the case with a solid conductor. (*See Pig-tail*, also *Flexible Wire.*)

FLEXIBLE WIRE—Any conductor composed of a number of fine wires to permit constant handling and bending without breaking. (See *Flexible Lead.*)

FLOAT, BATTERY — Term sometimes applied to the bulb or float in a hydrometer for testing the condition of storage batteries. (See *Hydrometer.*)

FLOW OF CURRENT—An expression used to denote the passage of electric current along a conductor. (See *Current, Direction of Flow (Assumed)*, also *Current.*)

FLOW OF MAGNETIC FLUX—The passage of lines of magnetic force through any magnetic circuit. (See *Flux*, also *Field, Magnetic.*)

FLUCTUATING CURRENT—An electric current that does not have steady value, rising and falling in strength or pressure. A current that is not constant. (See *Constant Current*, also *Voltage, Constant.*)

FLUORESCENT SCREEN—A screen or surface coated with fluorescent matter, used to exhibit shadows cast by rays from various types of tubes. Its application in radio is chiefly in the *Cathode Ray Tube.* (q.v.)

FLUX—A very broad term in physics. The three more common examples of flux are: (a) to denote *electrostatic or magnetic flux* (q.v.); (b) a substance used in soldering for the purpose of making the solder flow readily and making it adhere to the parts being united, and (c) in metal smelting, a mineral—customarily chalk or limestone—added to the charge in the furnace to absorb mineral impurities and dispose of them in the form of slag. *Flux* is also used to refer to the amount of heat or light flowing or passing through a given distance or area in a given time. (See *Electrostatic Flux, Flux Density*, also *Flux, Magnetic.*)

FLUX DENSITY—The number of lines of force per square centimeter of sectional area of a magnetic path. The unit of magnetic flux in the C.G.S. (Centimeter Gram Second) or electromagnetic system of units is the Maxwell. It is generally referred to as a "line." As a magnetic flux is merely the effect of magneto-motive force, we can take the rule that the magnetomotive force is 1.257 x ampere turns as the rule for determining the intensity or density of magnetic flux. (See *Flux; Field, Magnetic*, also *Ampere Turns* and *Maxwells.*)

FLUX DISTRIBUTION—The distribution of lines of force in a magnetic or electrostatic field of force. (See *Field*, also *Flux.*)

FLUX, ELECTROSTATIC — Another term for electric displacement as in the case of a condenser. The density of electrostatic flux refers to the intensity of an *electrostatic field.* (q.v.) (See *Flux Density, Field, Electrostatic*, also *Electric Displacement.*)

FLUX LEAKAGE—Any loss or dissipation of magnetic or electrostatic flux. (See *Flux, Electrostatic*, also *Flux, Magnetic.*)

FLUX LINES—The lines of force in a field of force in which electrostatic or electromagnetic force is exerted. An alternate term for *lines of force.* (q.v.)

FLUX, MAGNETIC—The term broadly used to denote the grouping of magnetic lines of force in a *magnetic field.* (q.v.). The most common example of magnetic flux is in the case of an ordinary bar magnet as shown in the illustration Fig. 1. Here the lines of force or magnetic flux create a magnetic field indicated by the dotted lines. The number of lines of force in a field of unit area is used as a basis for determining the density of the flux. (See *Flux Density.*) This effect or magnetic flux field is also present when a current of electricity is allowed to circulate around a coil of wire, the larger the current and the greater the number of turns, the more powerful the flux created. The illustration Fig. 2 shows a coil of wire through which current is assumed to be passing, the dotted lines indicating the flux field. (See *Choke Coil, Transformer, Magnet*, also *Flux, Electrostatic* and *Magneto-motive Force.*)



Fig. 1. Bar magnet, showing how the lines of force, or magnetic flux, create a magnetic field as indicated by dotted lines.



Fig. 2. Coil of wire through which current is assumed to be passing, the dotted lines indicating the flux field.

FLUX MAGNETISM — The magnetic flux, or total number of lines of force passing through a magnetic circuit. It is equal to the product of the magnetic density (see *Flux Density*) and the cross sectional area of the magnetic path. It is also referred to as magnetic flow. (See *Magnetic Flow.*)

FLUXMETER—A device for measuring flux density. The Grassot fluxmeter uses an *exploring coil* (q.v.) in conjunction with a special form of moving coil galvanometer. The coil is suspended on a silk fiber and its movements actuate a pointer across a scale. (See *Flux, Magnetic.*)

FLUX, SOLDERING — See *Soldering Flux, Flux.*

FOCUS or FOCI—The point or points at which converging lines meet. The magnetic foci are the points on the earth's surface in the vicinity of the magnetic poles, where the magnetic force of the earth is the greatest. Essentially a mathematical term.

FORCE—An influence exerted upon a body so as to produce a change or a tendency to change its state of rest or motion. This is mechanical force. In electricity we have its electrical analogy—*electromotive force.* This is the force which causes motion of electricity and sustains the electric currents against the resistance of a circuit. (See *Electromotive Force.*)

FORCE, MAGNETO-MOTIVE—The force which produces magnetic flux as in the case of a magnet moving through a magnetic circuit. The abbreviation is M. M. F. and its unit is the *gilbert.* (q.v.) (See *Magneto-motive Force.*)

FORCED OSCILLATIONS — Electrical vibrations or high frequency oscillations which are imposed upon an *oscillatory circuit* without being in tune or resonance with the natural period of vibration of the circuit. The opposite of a free oscillation in which case the circuit oscillates freely on its own account at the same frequency as the imposed or incoming oscillations or one of the *harmonics* (q.v.) of this frequency. Free and forced oscillations may be present in the same oscillatory circuit, the forced oscillations being set up during the first stages of induction of free oscillations. (See *Free Oscillations*, also *Oscillatory Circuit.*)

FORM FACTOR—The ratio of the *root-mean-square value* (q.v.) to the algebraic mean ordinate taken over one alternation (half cycle), starting with zero value of current. It is the ratio of the r.m.s. value of an alternating electromotive force, current, etc., to its true mean value. (See *Wave Analysis.*)

FORMULA — A principle or rule expressed in mathematical terms or chemical symbols. Formulae are much used in radio to state a problem as, for example, a formula for calculation of wave-length, which is written: Wave-length$=1884\sqrt{LC}$. This states the problem or rule for the determination of wave-length. Here we have certain values represented by symbols. The capacity is represented by C, the inductance by L, the wave-length in meters being the product of the square root of the product of these two multiplied by the factor 1884. (See *Measurement of Wave-length.*)

FOSTER BRIDGE—A form of *Wheatstone Bridge* (q.v) of the slide wire variety designed to permit comparison of two low value resistances that are nearly equal. It was devised by Professor Carey Foster and is used to determine the difference between two resistances as distinguished from the usual bridge for measuring the resistance of a single unit. (See *Wheatstone Bridge.*)

FOUCAULT CURRENT—Another name for *eddy currents*, the *electro-magnetic currents* due to the circulation of induced current in the mass of a conductor. Foucault first proved that these currents were productive of losses of energy as they cannot be utilized except in certain forms of meters. (See *Damping of Instruments.*) Alternating currents tend to set up eddy currents in metal masses near them. Thus in the case of a transformer, eddy currents are produced in the iron core due to the induced currents circulating through its mass. These currents are wasteful and means are therefore used for reducing them. The core of a transformer may be made of numerous flat pieces called laminations, which serve to prevent the free movement of eddy currents in the core. (See *Eddy Currents*, also *Transformer* and *Core Losses.*)

FOUR ELEMENT or FOUR ELECTRODE TUBE—A vacuum tube having four elements instead of the usual three. The standard tube has three elements, namely, grid, filament and

A four element vacuum tube.

plate. The four element tube has an additional grid element. The illustration shows one form of tube having a double grid arrangement. Such a tube can be used for high and low frequency amplification and as a detector simultaneously or it may be used in conjunction with the Solodyne system, which does not use the customary B battery to supply potential to the plate element. (For more complete explanation of the action of a four element tube in the latter manner see *Solodyne*). (See also *Vacuum Tube.*)

FOURTH CIRCUIT—A method of controlling oscillation of a regenerative detector used in the *Cockaday Circuit.* (q.v.)

FRAME AERIAL—An alternate name for *loop aerial,* a type of aerial consisting of a number of turns of wire wound on an insulated frame and used in place of the regular outdoor aerial with sensitive receiving sets. (See *Loop Aerial.*)

FREE ALTERNATING CURRENT—Term applied to alternating current assumed to be produced by the application of a single impulse of electricity to an *oscillatory circuit.* (q.v.) See *Free Oscillations.*)

FREE ELECTRONS—Name given to the outer electrons of an atom, which become detached under various chemical transformations and are assumed to participate in electrical effects or phenomena. Free electrons are so named to distinguish them from the bound electrons of the proton or positive nucleus of an atom. (See *Electron,* also *Proton.*)

FREE MAGNETISM—The portion of magnetism which does not follow the magnetic path through the metal of a magnetized body, but leaves the surface of the magnet. Sometimes referred to as *surface magnetism.* (See *Magnetism.*)

FREE OSCILLATIONS — Oscillations having the natural frequency of the circuit in which they occur. (See *Forced Oscillations.*)

FREQUENCIES—The plural of the term denoting the number of complete cycles per second in an alternating current. In referring to vibrations, particularly audible or so-called *voice frequencies,* the term is used to imply all frequencies that are normally considered audible. (See *Frequency.*)

FREQUENCY—A term adapted from academic English to use in electrical practice. Thus, the number of times a certain action is repeated per unit of time. In the case of an *alternating current* (q.v.) the current reverses its direction of flow at certain definite intervals. If the reversing process takes place 120 times per second—that is 60 reversals from negative to positive and vice versa—the frequency of the current is said to be 60 cycles. In ordinary commercial practice the majority of alternating current generators produce an alternating current or E.M.F. having a frequency from 25 cycles per second to 60 cycles per second. In radio transmission the alternating current or E.M.F. (Electro Motive Force) has an infinitely higher frequency—the reversals taking place many thousands of times each second. (See *Alternating Current, Theory of Production,* also *Alternation, Cycle* and *Periodicity.*)

FREQUENCY, AUDIO—In radio, a frequency within the limits at which audible sounds are produced. It is generally considered as a frequency less than 10,000 cycles per second, although some authorities refer to frequencies up to 16,000 or 20,000 cycles as being within the limits of audibility. For ordinary practice, the human ear is capable of hearing sounds only up to about 2,500 cycles per second. In receiving sets the audio frequency currents appear only in the circuits carrying the rectified currents, although some types of super-heterodyne receiver use an intermediate frequency as low as 30,000 cycles per second, these signals then being rectified and made audible in the telephone receivers. (See *Frequency Circuit, Audio,* also *Frequency, High.*)



In the diagram above, the heavy lines to the right of the dotted line indicate the audio-frequency circuit of a radio receiver.

FREQUENCY, ALTERNATOR OF—The frequency of an alternating current dynamo or alternator is expressed in cycles per second. With each complete revolution of the *armature* a complete *cycle* or double *alternation* of current is generated. (See *Alternator.*) It is therefore a simple matter to determine the frequency of alternating current generated when the number of revolutions per second and the number of field poles or magnets is known. The frequency will be $f=\frac{N \times S}{2}$, N being the number of field poles and S the number of revolutions per second. The divisor 2 is used to convert the result in *alternations* per second to cycles per second, one cycle representing two alternations. (See *Alternating Current, Theory of Production of,* also *Frequency.*)

FREQUENCY BAND—A term used to denote all the frequencies lying within a certain minimum and maximum limit. Thus, in broadcasting, the frequency band will be the frequencies corresponding to the wave-lengths within the broadcast band. This will be generally between 550,000 and 1,500,000 cycles, or a wave-length band of approximately 200 to 550 meters. (See *Band of Frequencies.*)

FREQUENCY CARRIER—In radio broadcast transmission, the radio frequency (high frequency) wave with which the audio frequency speech variations are superposed. (See *Broadcasting, General Treatise on Methods,* also *Carrier Wave.*)

FREQUENCY CHANGER—A device for converting currents at a certain frequency into currents of a higher or lower frequency, without change of phase or voltage. A frequency converter. Generally an *alternator* driven by a *synchronous motor.* The term is also applied erroneously to certain forms of super-heterodynes. (See *Ultradyne.*)

FREQUENCY CIRCUIT, AUDIO—Any circuit in a radio receiver or transmitter which carries currents within the arbitrary limits of audibility. In the diagram shown herewith, the heavy lines are the connections of the audio frequency circuit. In this part of the circuit only currents of audio frequencies are present. (See *High Frequency Component of Plate.*)

FREQUENCY CIRCUIT, RADIO—The circuits in a receiver in which only high or radio frequency currents are supposed to be present. (See *Feed-Back, Audio Frequency,* also illustration in connection with *Frequency Circuit, Audio.*)

FREQUENCY, FUNDAMENTAL—The frequency of the fundamental wave. (See *Fundamental Frequency.*)

FREQUENCY, GROUP—The frequency of the separate trains of waves in radio communication. (See *Group Frequency,* also *Wave Train.*)

FREQUENCY, HIGH—Frequencies over certain definite limits, generally from 10,000 to 20,000 cycles per second in radio usage. Commonly used as synonymous with radio frequency. It is the opposite of low or audio frequency. (See *Frequency,* also *Audio Frequency, Limits of Audibility.*)

FREQUENCY, LOW—Frequencies below certain limits, generally 10,000 or 20,000 cycles per second. (See *Frequency; Limits of Audibility.*)

FREQUENCY METER—A device for indicating the frequency of an alternating current in cycles per second. The most simple form uses a system of tuned, vibrating reeds. The illustration shows a frequency meter of the



Illustration by Courtesy of Jas. G. Biddle.
A vibrating reed type of frequency meter.

reed type. These reeds may be arranged to respond to various frequencies in a similar manner to the reeds in various musical instruments. These reeds are acted upon by an alternating current magnet. When the magnet is acted upon by an alternating current sent through the windings, the reed nearest to that frequency will vibrate in sympathy with the vibration due to the alternating magnetic effect on the magnet. Such meters and also those of the *induction type* are used for comparatively low frequencies such as occur in commercial lighting systems. For measurement of the high frequencies used in radio communication somewhat different systems are used.

FREQUENCY, RADIO—An alternating current or electromotive force above certain definite limits, generally above 10,000 or 20,000 cycles per second. The line of demarcation between *audio frequency* and *radio frequency* is not very sharply defined, as, in radio usage frequencies that are actually inaudible to the human ear may yet be referred to as audio frequencies. The term is used to differentiate between the rectified or audio currents and the high frequency oscillations such as are impressed on the antenna in receiving or transmitting. (See *Audio Frequency*, also *Frequency, Low.*)

FREQUENCY, UNIT OF—Frequency of alternating currents is expressed in cycles per second and is generally written f. (See *Frequency*, also *Cycle.*)

FREQUENCY, VARIATION OF POWER FACTOR WITH—When a condenser is charged and *dielectric absorption* (q.v.) takes place, it is always accompanied by a loss of power which is apparent in the form of heat produced in the condenser. This loss of power varies with the frequency of the current impressed on the condenser and it is therefore said that the *power factor* (q.v.) varies with the frequency. (See *Condenser, also Dielectric Absorption.*)

FULL LOAD CURRENT—The current delivered from any electrical source, such as a dynamo or generator operating at its maximum load. The maximum current obtainable from an electric source.

FULL WAVE RECTIFICATION — In rectifying alternating current, the process of rectifying both the positive and negative alternations or half cycles. The majority of rectifiers for charging storage batteries rectify only a half wave, or half cycle, and thus do not utilize the full alternating current cycle. (See *Rectifier, Full Wave*, also *Charger, Storage Battery.*)

FULLER CELL—A type of primary cell formerly much used in telephone, telegraph or any intermittent work. (See *Cell, Open Circuit.*) A zinc electrode cast in the shape of a cone is at the end of a soft copper wire and rests at the bottom of a porous cup immersed in a dilute solution of sulphuric acid. The carbon electrode is in an outer jar in a bichromate solution. (See *Cell.*)

FUNDAMENTAL FREQUENCY — The frequency or number of cycles per second of the fundamental wave. (See *Frequency*, also *Fundamental Wave.*)

FUNDAMENTAL UNITS—Units based on the fundamental quantities of length, mass and time. Under the *C. G. S. system* the unit of length is the centimeter; of mass, the gram; and time, the second. The absolute system of units. (See *Centimeter-Gram-Second.*)

FUNDAMENTAL WAVE—In an alternating current, the component of the wave form that is a pure sine wave of the principal frequency. Upon this principal frequency the various higher frequencies (harmonics) may be superposed. A fundamental wave when combined with other frequencies which are a whole multiple of it produce the harmonious note. These terms are derived from acoustics in which the fundamental is the pure sound wave or pure note. (See *Sine Wave of Alternating Current or EMF.*)

FUNDAMENTAL WAVELENGTH — Term used to denote the wave-length at which the inductance and capacity of a coil or antenna would be in resonance. In referring to antennas the fundamental wave-length is the wave-length corresponding to the frequency at which free oscillations will occur. This is often referred to as the natural wave-length and the corresponding frequency is referred to as the natural frequency of the antenna.

For practical purposes the fundamental wave-length of an aerial (antenna) may be computed from the dimensions. Where no loading inductance is used, a single wire flat top antenna (T or inverted L type) will have a fundamental wave-length approximately four times the distance from the ground connection to the extreme end of flat or horizontal portion as measured in meters. Thus, if the antenna is of the L type with a top one hundred feet long and a lead-in and ground connection sixty feet long, the fundamental wave-length will be about 4×(100+60)×1.1, the result being given in feet. Now as wave-length is always stated in meters it will be necessary to divide this result by 3.28 which is the rough conversion factor from feet to meters. The multiplier 1.1 adds ten per cent to the figures for necessary correction of length. If the antenna is of the T type, the length of the flat portion would be considered as half of the total horizontal length or 50 feet instead of 100 feet. The illustration shows method of measuring length. (See *Wave-length Calculation for Antennae.*)





FUSE—A device used in electrical circuits to prevent the passage of excessive currents. Generally a strip of fusible metal, commonly lead with a small percentage of tin, enclosed in a fiber or insulated and fireproof container and inserted in the circuit. When the temperature, due to excessive current, reaches a certain limit, the fuse "blows" causing a break in the circuit. It is thus possible to limit the current flowing in a circuit to a definite maximum in order to protect instruments from excessive charges. The most common use is in commercial lighting and heating systems where the current on any line is generally limited to ten or twenty amperes for the protection of the lines leading in to the building.



Fig. 1. A common type of fuse used in lighting, heating and power circuits.



Illustration by Courtesy of Radio Equipment Co.

Fig. 2. A fuse used to protect the filament of a vacuum tube from damage by excessive voltage.

G

GALENA—A natural crystal sulphide of lead. Chemical symbol PbS. It is an ore of lead, grey in color and showing brilliant metallic lustre when fractured in cubical form. Galena crystals are used either alone or in conjunction with other minerals as *crystal rectifiers* (*detectors*) in radio reception. When used in combination it is generally in conjunction with *graphite* or *zincite*. Used alone, the contact may be a fine wire or *cat whisker*. (q.v.) (See *Crystal Detector.*)

GALVANIC BATTERY—The term, now obsolete, formerly applied to a primary battery or group of primary cells.

GALVANI, LUIGI. Born 1737, died 1798.—An Italian physician and physiologist noted as the discoverer of galvanic or current electricity. While dissecting the legs of a frog, they came by accident into contact with dissimilar metals which caused muscular action in them. Galvani thought that he had discovered electricity in animal matter. Volta attributed the action to the metallic contact and thereupon constructed his voltaic pile, the forerunner of the primary cell.

GALVANOMETER—An extremely sensitive instrument used for detecting and measuring electric currents and also for indicating the direction of the current in a circuit. In its simplest form it consists of a small iron needle pivoted in the center of a hollow coil of wire. The needle is controlled by the earth's field and points north and south when at rest. When an electric current is passed through the galvanometer winding the needle is deflected over a graduated scale the extent of the deflection depending on the force of the current. The instrument is arranged in such a manner that the needle will be deflected in one direction when the current flows through the windings in a certain direction, and when the current is reversed the needle will be deflected in the opposite direction. Thus when the connections are known the direction of the current is accurately indicated as well as its strength. The galvanometer is one of the most sensitive current measuring devices, the deflection of the needle being due to the electro-magnetic field created by the passage of electric current through the coil of wire. (See *Ammeter* or *Ampere Meter*, also *Galvanometer, D'Arsonval* and *Galvanometer, Mirror.*)



Illustration by Courtesy of the Roller-Smith Co.

A galvanometer which is used for measuring electric currents, and also for indicating the direction of flow of current in a circuit.

GALVANOMETER CONSTANT—Generally speaking, a number used to change the galvanometer reading to ordinary units. The instrument measures extremely small currents and this number times a certain function of the galvanometer reading gives the value in customary units. Technically, the strength of the field produced at the center of the coil of a galvanometer by the unit of current to be used. (See *Constant.*)

GALVANOMETER, D'ARSONVAL—A form of galvanometer having a dead beat indicator (see *Dead Beat Instrument*) in which the indicating coil is suspended in the field of a powerful horseshoe magnet. It is one of the most sensitive forms of galvanometer. The name was derived from that of the designer, A. D'Arsonval. (See *Galvanometer.*)

GALVANOMETER, MIRROR—A type of galvanometer, the moving coil or indicator of which carries a mirror which reflects a beam of light from a fixed lamp. It is so arranged that the lamp is provided with a lens and the beam is so reflected that a visible spot of light is seen on a scale and deflected when the moving element (carrying the mirror) swings with the passage of current. In the beam of light is a sharp image of fine wire stretched in front of the lamp. This type of galvanometer may also be arranged so that the reflection of a fixed scale may be observed in the mirror by means of a small telescope arrangement. (See *Galvanometer.*)

GAMMA—Γ—The third letter in the Greek alphabet. (See *Gamma Type Antenna.*) The lower case *Gamma* γ is used as a symbol for *conductivity.* (q.v.)

GAMMA TYPE ANTENNA—An alternate name for the inverted L type of antenna, so called because the third letter in the Greek alphabet, Γ, resembles an inverted "L," and a single wire antenna with lead-in from one end is in the shape of an inverted L. (See *T Type Aerial.*)

GAP—See *Spark Gap*, also *Lightning Gap.*

GAP, AIR—Term applied to the gap between sections of an iron core as in a transformer for the purpose of preventing *saturation.* (q.v.) Also applied to speak dischargers where a space is provided between the electrodes across which the spark jumps in operation. The term is used as well in referring to the radial depth of the space between surfaces of the rotor and stator in generating machines or motors. (See *Spark Gap*, also *Rotary Gap.*)

GAP ARRESTER—A form of *lightning arrester* (q.v.) in which small air gaps are provided between non-arcing metal electrodes. (See *Arrester.*)

GAP, MICROMETER—A small gap designed to protect apparatus from excessive potentials. (See *Safety Gap.*)

GASEOUS—Anything of the nature of a gas, having no natural physical boundaries but accommodating itself to the shape of the container, expanding to the dimensions of any space in which it may be confined.

GASEOUS TUBE—A term sometimes applied to a vacuum tube in which a certain amount of gas is present. Such tubes under ordinary conditions are not efficient as amplifiers in vacuum tube circuits, the minute gas atoms presenting a more or less effective obstacle to the free passage of the electrons. (See *Vacuum Tube, Theory of Operation.*)

GAS RECTIFIER—The term applied to a vacuum tube which is only partially exhausted of its residual gas. They are also known as *soft* tubes and are generally used as detectors although the tendency now is toward *hard* or highly evacuated tubes due to their adaptability to all purposes in radio receivers whereas the soft tubes do not function well as *amplifiers.* (See *Vacuum Tube.*)

GASSING—When the charging current is continued after a storage battery has taken a normal charge the free liberation of oxygen and hydrogen takes place. This is manifest in the form of gaseous emanation or liberation of bubbles from the electrolyte. The same effect may be noted when a battery is charged at higher rate than the normal charging rate stated by the manufacturer, and under certain conditions may occur at the later stages of charging, even when the battery is not fully charged. In a storage battery that is in good condition it is a fairly accurate indication of a full charge. (See *Charging*, also *Rate of Charging.*)

GAUGE, WIRE—The various systems of measurement used for denoting the physical dimensions of wire. The standard gauge in the United States is known as the B & S or Brown and Sharpe gauge. (See *Brown & Sharpe Guage.*)

GAUSS—The term adopted by the American Institute of Electrical Engineers as applying to the *magnetic flux density.* (q.v.) It is written B or ℬ and is also used in conjunction with the *Gilbert* to denote magnetizing force, one gauss being one gilbert per Centimeter. It is incorrectly used to apply to *magneto motive force.* (See *Centimeter Gram Second or C. G. S.*)

GENERATOR—Any machine for producing electric energy. Usually a device for converting mechanical power into electrical energy. It may apply to a vacuum tube used to generate oscillations as in transmission or for *heterodyne action.* (See *Heterodyne*, also *Vacuum Tube Generator.*)

GERNSBACK, HUGO—Born 1884. Educated Ecole Industrielle, Luxembourg; Technikum, Bingen, Germany. President, The Experimenter Publishing Company, Publishers of Radio News, Science and Invention, Amazing Stories and Radio Internacional. President of The Consrad Company, Publishers of Radio Review, Radio Listeners' Guide and Call Book, and Money Making. Editor of Radio News, Science and Invention, Amazing Stories. Author of "Radio for All," "Wireless Telephone," "Ralph 124C-41+."

Hugo Gernsback.

GERNSBACK, SIDNEY—Born 1876. Educated College of Luxembourg, Lycee de Nancy, France. Vice-President and Treasurer of The Experimenter Publishing Company, Publishers of Radio News, Science and Invention, Amazing Stories, and Radio Internacional. Vice-President and Treasurer of the Consrad Company, Publishers of Radio Review, Radio Listeners' Guide and Call Book, and Money Making. Editor of Radio Re·

view, Radio Listeners' Guide and Call Book, and Money Making. Author of "A Thousand and One Formulas," "Wireless Course in Twenty Lessons," "Experimental Electricity Course," "Radio Encyclopedia."

Sidney Gernsback.

GILBERT—Symbol *F*, is the unit of magneto-motive force adopted by the American Institute of Electrical Engineers. (See *Magneto-motive Force.*) It is equivalent to $4\pi/ 10$ or .7958 ampere turns. (See *Ampere Turns.*)

GLASS PLATE CONDENSER—A condenser, generally of the heavy duty fixed type, consisting of alternate layers of metal or foil and thin glass sheets as the *dielectric.* Glass plate condensers are mainly used for transmitting, glass having a very high dielectric constant. Such condensers may be immersed in oil to stand higher potentials without breaking down. (See *Condenser,* also *Dielectric Coefficient and Constant.*)

GLASS SILENCER—A glass tube having wooden ends with holes just permitting discharge electrodes or rods to pass, used in conjunction with spark coils and gaps to enclose the sparking surfaces and thus dampen the noise of the sparking. (See *Spark Gap.*)

GLOW DISCHARGE—See *Corona.*

GLIDING THEORY—A theory regarding the propagation of electromagnetic (radio) waves, which assumes the waves as following the curvature of the earth and not being subject to reflection due to objects in their path or by any reflecting surface above the earth. This theory has been discarded; due to observations of phenomena of transmission it now is generally assumed that there must be a reflecting surface high in the atmosphere. However, it is considered probable that the waves do not extend very high as a general rule, the exceptions being the cases of extreme distance transmission in certain directions. In the upper atmosphere, due to the rarification of the atmosphere *ionization* (q.v.) is very pronounced and the air may become a fairly good conductor. This conducting region or layer may impose severe obstacles to the electromagnetic waves and thus limit them to a certain restricted zone. In the majority of cases this ionized region may thus be regarded as damping or absorbing the waves, and in others it may conceivably intensify or concentrate them in one direction, producing instances of transmission over extreme distances with low power. For more complete discussion along these lines see *Heaviside Layer,* also *Refraction and Reflection of Electromagnetic Waves.*

GOLD LEAF ELECTROSCOPE—A very sensitive device for determining the presence and nature of an electric charge. It comprises, essentially, two strips of gold foil joined at one end by a conductor and suspended in a glass jar. When an electric charge is present the two strips of foil have a tendency to repel one another and thus, by diverging, indicate the presence of the charge. (See *Galvanometer.*)

GOLDSCHMIDT ALTERNATOR—One of the first practical *alternators* for generating *high frequency currents* suitable for *continuous wave* radio transmission. It was designed by *Rudolph Goldschmidt* in 1912 and was used mainly in Europe. This machine operated on a frequency step-up principle. A single phase alternating current was first produced, the frequency being about ten thousand cycles. This was about the highest possible frequency obtainable with an ordinary type of alternator. By means of a *cascade* effect, obtained by an arrangement of tuned circuits connected to stator and rotor of the alternator, a much higher frequency could be impressed on the antenna to radiate continuous waves. The machine had a number of disadvantages which limited its commercial value, chiefly the fact that the air gap between rotor and stator was necessarily very small—a difficult matter with a bulky machine, the rotor of which weighed several tons. (See *Alternator, Continuous Waves,* also *Goldschmidt, Rudolf.*)

GOLDSCHMIDT, RUDOLF—Born March 19, 1876, at Neu-Buckow, Mecklenburg, Germany. After finishing his education at Wiemar Municipal School, he studied engineering at Charlottenburg and Darmstadt Technical High School. In Darmstadt he obtained his degree as electrical engineer in January, 1898, and then became assistant to Professor Kittler. In 1900 he obtained the college and travelling scholarship, which enabled him to visit engineering works in Belgium, England and France. Later in the same year he was appointed engineer in the laboratory of the Allgemeine Elektrizitaets Gesellschaft in Berlin. In 1901-2 he occupied the position of chief laboratory engineer and designer to Kolben & Co., Ltd. in Prague. He came to England in connection with the Willesden Electricity Supply Station and was later appointed chief engineer to Messrs. Crompton & Co., of Chelmsford. In 1905 he joined the Westinghouse Company in Manchester. After private preparation he passed the German abitur-examination and obtained the degree of Dr. Eng. In 1907 he returned to Germany as lecturer at Darmstadt Technical College. Here he practiced as a consulting engineer, and also pursued the development of several inventions, chiefly occupying himself with the invention and design of high-frequency alternators for wireless telegraphy. In 1911 he became manager of the "Hochfrequenz-Machinen Aktiengesellschaft fur drahtlose Telegraphie" in Berlin, a company formed for the utilization of his inventions in wireless telegraphy. In this position he established two large wireless stations at Eilvesen, Province of Hanover, and Tuckerton, New Jersey, for wireless communication between Germany and America.

GOLDSMITH, ALFRED NORTON—Elec. and Radio Engr.; b. New York, N. Y., Sept. 15, 1887; B.S., Coll. of the City of New York, 1907; Ph.D., Columbia Univ., 1911; cons. radio expert, U. S. Dept. of Justice, 1912; cons. radio engr., Atlantic Communication Co., 1914; cons. engr., Gen. Elec. Co., 1915-17; dir. of research, Marconi Wireless Telegraph Co. of America, 1917-19; associated professor of electrical engineering, College of City of New York, since 1924; dir. of research dept., Radio Corp'n of America, 1919-1922; Chief Broadcast Engineer, Radio Corp'n of America, since 1922; editor, Proceedings of the Institute of Radio Engrs., since 1912. Made investigations in simplex and duplex radio telegraphy and telephony, transmission of canal rays, precision measurements in radio eng. Author: "Radio Telephony" (Wireless Press), 1918; "Radio Measurements," "Radio Frequency Changers" (Proc. Inst. Radio Engrs.), 1915; "World Communication" (Jour. A. I. E. E.), 1921. Technical director, U. S. Signal Corps School of Communication, 1917-18; U. S. Naval Radio School, 1917-18. Fellow, A. I. E. E., I. R. E., American Association for Advancement of Science. Hon. mem., Radio Club of America, Radio Society of Great Britain, Am. Physical Soc.

Dr. Alfred N. Goldsmith.

GONIOMETER—A device used in radio reception to determine the direction from which the electromagnetic waves (signals) are coming. The term is also used at times to designate any system of directional transmission or reception. The device was originally designed as an aid to navigation.

The original goniometer was designed by Messrs. Bellini and Tosi (see *Bellini, Dr. Ettore,* also *Tosi, A.*), but numerous changes have since been made, notably by Marconi and his associates, to adapt it to the requirements of ships at sea. The form most used is based on the original Bellini-Tosi machine and is essentially a special form of *oscillation transformer* used in conjunction with a special aerial or loop. As an example of the use of a goniometer in connection with ships at sea, suppose a ship is in distress at a point about two hundred miles off the eastern coast. Perhaps the ship's radio apparatus is working, but for some reason the mariner does not know the ship's position. The radio signals are then received, let us say, by three different land stations at widely separated points. The receiving stations use their goniometers and determine more or less accurately the direction from which the signals are coming. The three stations compare notes on the respective directions and any one of them can readily plot out lines running on a chart from each station in the directions indicated by the goniometers. Then by simple triangulation the location of the ship can be figured, enabling other ships in the vicinity to be instructed accordingly and go to their rescue. There are, of course, many other uses that occur in everyday practice. Goniometers are also much used by radio inspectors to locate stations that are interfering, using an unlicensed transmitter, or are otherwise not complying with the regulations.



Fig. 1 shows the general arrangement of a goniometer and Fig. 2 shows the loops to which coils L and L-1 are connected.

The illustration Fig. 1 shows the general arrangement of the instrument. Here, coils L and L1 are the main windings of the goniometer. They are wound in two sections with condensers C and C1 inserted between the sections of the two windings for purposes of tuning. Coil L2 is the *exploring coil.* This is connected to the receiving apparatus, which is the customary detector circuit. Coils L and L1 are connected to the two loop aerials shown in Fig. 2. Here it will appear that the loops are placed at right angles, their relation in this respect being variable. In operation the coils L and L1 have minimum *mutual induction*, as they are placed at right angles. The exploring coil L2 can be rotated through a complete circle and the pointer indicates the angle with relation to the fixed coils. When one of the two loops points in the direction of a transmitting station it will pick up the signals, the other being at that moment inoperative, as it is at right angles to the first, as previously explained. If the exploring coil L2 is now turned until maximum signal strength is obtained, the pointer will be in the direction of the plane of the loop. If the advancing wave strikes the two loops simultaneously at any angle, a resulting magnetic field will be set up in the coils L and L1 of the goniometer, the field having a direction at right angles to the direction from which the waves are advancing. Now when the exploring coil L2 is turned to allow maximum signal strength due to this field (permitting maximum inductive transfer), the pointer will be in the direction of the transmitting station. The direction indicated by the pointer is, of course, not the geographical direction, but this can readily be determined by means of a compass. It also appears from the foregoing description that the pointer will indicate two directions, which, however, will be on the same geographic plane. In other words, the pointer may be, for example, exactly north and south.

GRAMME ARMATURE—A form of ring type *armature* (q.v.) used in generators, named for its originator. (See *Generator.*)

GRANULAR CARBON—The carbon grains used in a telephone transmitter to vary the resistance between the electrodes. The highest grade is made by carbonizing pure anthracite coal in an electric furnace, after which it is screened and graded. (See *Microphone, Carbon.*)

GRANULAR COHERER—A form of *coherer* (q.v.) used in the early days of wireless. It employed carbon granules between two electrodes, the whole enclosed in a glass tube. (See *Detector.*)

GRAPH—The presentation in diagrammatic form of facts, formulae, etc., particularly in the electrical and mechanical fields. Graphs are much used in radio to give graphic illustrations of various functions, such as the relation of currents and voltages. For this purpose ruled and squared paper is used. One of the most common and useful forms of graph is known as a characteristic curve of a vacuum tube. These curves may show the relation of changing values, such, for instance, as the relation of grid voltage to plate current, indicating certain of the operating characteristics of the vacuum tube. (See *Characteristic Curve*, also *Sine Curve.*)

GRAPHITE RESISTANCE—A form of resistance composed of graphite, used in any of several ways in radio circuits. The most common usage is in the form of a *grid leak* (q.v.). Here it may take the form of a thin sheet of paper coated with graphite or a glass tube filled with graphite and some binding medium. Such resistances are also used in *resistance coupled amplifiers* (q.v.), in which case they are interposed between the plate and "B" battery and couple the successive stages of amplification. (See *Resistance*, also *Resistance Coupled Amplifier.*)

GRASSOT FLUXMETER—An instrument used to measure the strength of magnetic fields and the regions around magnetic poles. It is of particular value in measuring the relative strengths of various magnets. The instrument comprises a very sensitive galvanometer of the moving coil type with a special exploring coil. This coil is introduced into the magnetic field to be measured and readings of the proportionate strength of the field are obtained directly from the scale of the galvanometer, which is appropriately divided. The field strength is obtained by dividing the deflection value in *Maxwell turns* (q.v.) by the area of the search or exploring coil in square centimeters and the number of turns of the coil. (See *Galvanometer*, also *Flux Density.*)

GRAVITY BATTERY—A combination of gravity cells. A group of cells, each cell having two different electrolytes which remain separated without use of a diaphragm due to their difference in specific gravity. (See *Gravity Cell.*)

GRAVITY CELL—A type of *primary cell* (q.v.) in which the specific gravity of one electrolyte is less than the other, which causes this lighter electrolyte to float on top of the heavier fluid. One of the typical examples of gravity cells is the *Daniell's Cell* (q.v.). (See *Secondary Cell.*)

GRID—Generally, any system of wires placed parallel to each other and in the same plane, as a mesh. Specifically in radio usage, the fine network of wires interposed between the filament and plate elements in a vacuum tube. It may be in the form of a flat network of wires or in the form of an oval cylindrical mesh completely surrounding the filament and in turn surrounded by a similarly shaped plate of metal. The illustration shows the form taken by a typical grid member in a modern type of vacuum tube. Here the plate is not shown in order to permit the grid member to show more clearly.

In receiving circuits the grid acts as a valve to control the flow of electrons from hot filament to cold plate. When signals are impressed on the aerial they are tuned by the customary agencies and passed to the *grid circuit* (q.v.). As the incoming signals are in the form of *high frequency oscillations* (q.v.) changing their polarity (direction) many thousands of times each second, it will be apparent that the grid is altered rapidly from positive to negative and back. As the electrons flowing from the filament are negative, the grid will thus have a tendency to retard or increase the flow. That is to say, at the instant the grid is positive it will attract more electrons, but when it is momentarily negative the like charges will repel each other and less electrons will flow, some of them being held back to the filament. (See *Grid Battery, Grid Bias*, also *Vacuum Tube, Theory of Operation of.*)



Showing the form taken by a typical grid in a modern vacuum tube.

GRID BATTERY—A battery of small cells connected in the grid circuit of a vacuum tube to place a negative or positive bias or charge on that element. The illustration Fig. 1 shows a small four and one-half volt battery inserted in such a manner that a negative potential is impressed on the grid. In this case the *characteristic curve* (q.v.) of the tube is assumed to indicate that more difference in current occurs between points B and C than between A and B in Fig. 2. For this reason a negative potential is applied as shown in Fig. I. (See *Grid Bias.*)



Fig. 1. Method of a 4½ volt battery to impress a negative potential on the grid of a vacuum tube.



Fig. 2. Characteristic curve of a vacuum tube indicating more difference in current occurs between "B" and "C," than between "A" and "B."

GRID BIAS—A potential of a few volts, generally from four to six, applied to the grid of a vacuum tube to influence its operation by making it more or less negative. The grid bias is usually negative and determines the point of the *characteristic curve* at which the tube will operate. In a sensitive receiver, and particularly where a tube is used as an *amplifier* (q.v.), it is essential to obtain as great a change of grid current as possible. (Note: The greater the change of grid current, the greater the change in plate current and hence the more powerful will be the output.) By applying a negative potential on the grid it is possible to hold it at the point of maximum response. (See *Grid Battery,* also *Vacuum Tube, Theory of Operation of.*)



Diagram in which heavy lines at left show the grid circuit of the detector, while those on right indicate audio amplifier grid circuit.

GRID CIRCUIT—In a receiver employing vacuum tubes, the part of the circuit containing the grid of the tube or tubes, but generally referring to the tuning circuit or that part of the system which contains the tuning elements. In the illustration is shown a standard arrangement of a regenerative detector and one stage of audio-frequency amplification. The heavy lines at the left of the diagram represent the tuning circuit or detector *grid circuit,* while the section with heavy lines at the right is the grid circuit of the amplifier tube. The grid circuit of a detector tube may generally be distinguished by means of the grid leak and condenser (so marked in the illustration), which controls the incoming signals and permits the tube to function as a rectifier. (See *Detector, Grid Control,* also *Grid Condenser* and *Grid Leak.*)

GRID CONDENSER—A small fixed condenser, generally from .00025 to .0005 microfarad capacity, inserted in the circuit of a detector tube between the tuning coil and the grid member of the tube. The illustration shows the manner of connecting the grid condenser in a conventional detector circuit. This condenser insulates the grid from the filament by breaking the path F to G and permits the tube to act as a rectifier or detector. A resistance (called *grid leak*) is usually placed across this condenser to allow the accumulated charges on the grid to leak off. (See *Grid Leak,* also *Grid Control* and *Vacuum Tube, Theory of Operation of.*)



Showing how grid condenser is connected in a detector circuit.

GRID CONTROL—The general term used to designate the various devices and associated connections placed in or allied with the grid circuit of a vacuum tube for the purpose of controlling to a greater or lesser extent the potential of the grid, or to tune or control the incoming oscillations. In the case of a vacuum tube used as a rectifier (detector) the grid condenser and grid leak are placed in series with it. (Note: the grid leak is often connected from the grid directly to the filament instead of across the grid condenser, the operation, however, being approximately the same in either case.) Here the controls permit the tube to function as a detector of the incoming oscillations. Where the tube is used as a radio-frequency (high-frequency) amplifier, the radio-frequency transformer or other amplifying unit controls the grid of the following tube by influencing the fluctuating potential differences impressed on it. (See *Amplifier, Radio-Frequency.*) The most important example of a grid control is by using some means to control the potential applied to the grid, such, for example, as a grid bias or grid battery. (See *Grid Bias, Grid Battery,* also *Vacuum Tube, Theory of Operation of.*)

GRID CURRENT—The current present in the grid circuit of a vacuum tube. This is generally very small, perhaps of the order of fifteen to twenty *microamperes* (q.v.). (See *Plate Current,* also *Grid Bias.*)

GRID LEAK—A high resistance placed in the grid circuit of a vacuum tube to permit the electrons forming the grid current to leak off after each charge, thus preventing their accumulating on the grid in such numbers as to stop the flow from the filament. The electrons being negative, a surplus of them on the grid member of the tube would act as a barrier to the free flow of other electrons from the filament through the grid to the plate, thus diminishing the plate current toward zero. It will be understood that a heavy negative charge on the grid will repel a like or negative charge, in this case the negative electrons being thrown off by the hot filament.

The grid leak may have a value ranging from about 250,000 ohms to several million ohms. The value of a grid leak is generally stated in *megohms*—one megohm being one million ohms. Thus a grid leak of 250,000 ohms resistance would be referred to as a ¼-megohm leak and, similarly, one having a resistance of two million ohms would be referred to as a two-megohm grid leak.

Such resistances are furnished in many forms, the most common being a strip of paper impregnated with graphite or some similar high resistance preparation, placed in a glass tube and sealed to prevent moisture from affecting the value. The illustration, Fig. 1, shows a tubular type of grid leak.

Courtesy of Chas. Freshman Co.

Fig. 1.—A tubular type of grid leak.

For experimental work a fairly satisfactory grid leak can be made by the simple expedient of drawing a line on a piece of cardboard with a soft pencil—the graphite mark acting as the resistance. At each end of the cardboard is placed a binding post in contact with the graphite, each binding post being connected to opposite sides of the grid condensers. Variable grid leaks, the resistance of which can be changed at will, are also furnished in an infinite variety of types, two of which are shown in Fig. 2. (See *Variable Grid Leaks,* also *Grid Control* and *Resistance.*)

CHAS. FRESHMAN CO.

Courtesy of Chas. Freshman Co.

Fig. 2.—Two types of variable grid leaks with condenser incorporated.

GRID POTENTIAL, MODULATION OF—In the transmission of *undamped waves* (q.v.) generated by a vacuum tube, the process of varying or modulating the potential of the grid element of the tube with respect to the filament. In this method an alternating potential may be applied to the grid circuit, the frequency of this varying potential being within the audio band —possibly about 500 cycles—supplied by a generator of that freqnency. (See *Modulation.*)

GRID POTENTIOMETER—A potentiometer—a variable resistance unit—Fig. 1, used in the grid circuit of a vacuum tube for the purpose of controlling the potential applied to the grid. The conventional method is to place the potentiometer across the "A" battery with the center or variable contact arm connected to the grid of the tube in place of the usual connection to either positive or negative filament lead. This is shown in the illustration, Fig. 2, Here the customary circuit is shown for the "A" battery to light the filament of the tube. Pri. and Sec. are respectively primary and secondary of the transformer (either radio-frequency or audio-frequency) and C the center arm of the potentiometer. The center arm may be moved either to the right or left, permitting either negative or positive potential to be applied to the grid. This system is much used in amplifying tube circuits to control the action of the tube as an amplifier. Another method would be to connect one of the ends of the potentiometer to the negative lead of the "A" battery and the center arm to the grid leak. In this way the potentiometer would be acting as a pure variable resistance, the potential applied to the grid being always negative, but susceptible of variation within the limits of the ressitance and the voltage of the "A" battery. (See *Grid Bias, Grid Battery,* also *Grid Control.*)



Courtesy of the Cutler-Hammer Co.

Fig. 1.—A type of potentiometer.



Fig. 2.—Method of connecting potentiometer in grid circuit.

GRINDER—Term occasionally applied to one of the various forms of atmospheric disturbance known under the general heading of *static.* This form of static is more prevalent in warm weather and does not appear to have its origin in local electric storms. Its effect is to produce rattling sounds of no definite pitch. (See *Strays,* also *Static.*)

GROUND—The earth considered as an electric conductor. In radio it is considered as the return circuit for electromagnetic waves. (See *Ground Connection,* also *Theory of Propagation of Electromagnetic Waves.*)

GROUND CLAMP—A strip of metal, generally copper, having some sort of arrangement for fastening rigidly to a water or steam pipe to form the ground connection for a radio receiver. The illustration shows a conventional form of clamp. (See *Ground Connection.*)



A ground clamp for fastening the ground lead to a water or steam pipe.

GROUND CONNECTION—In radio reception or transmission, the connection between the earth and the apparatus whereby the currents set up by the electromagnetic waves are returned to the earth as one side of the assumed circuit. The ground or earth connection from a radio receiver or transmitter should be as short as possible and preferably a heavy wire as shown in the illustration. Such a connection for receiving purposes may be one or more heavy metal plates sunk in the ground and connected by a heavy wire to the apparatus. The more common method is to connect the set to a convenient water or steam pipe, such pipes being almost invariably well grounded, especially the former. (See *Earth,* also *Ground* and *Transmission.*)


LEAD IN
WALL
GROUNDS AND LIGHTNING PROTECTION
INSULATING TUBE
RADIO SET
INSULATORS
LIGHTNING ARRESTER
A
G
PROPER INSTALLATION OF THE LIGHTNING ARRESTER ACCORDING TO THE N.B.OF F.U
6' MINIMUM
GROUND WIRE Nº 14 OR LARGER

Illustration showing by means of a heavy line, the ground connection of a radio receiver.

GROUND CURRENTS—Electric currents present in the ground due to the grounding of commercial electric machines. These currents very often prove a disturbing factor in radio reception. (See *Ground.*)

GROUND DETECTOR—A device for indicating an accidental ground on a power transmission line or for any conducting systems for electric currents. (See *Detector,* also *Ground.*)

GROUND RESISTANCE—See *Resistance of Ground Connection.*

GROUND SWITCH—A switch, generally of rugged construction, connected to the aerial, ground and apparatus in such manner that at one position the aerial is connected to the set, which in turn is connected to the ground, and in the other position the aerial being connected directly to the ground to protect the set from excessive static when not in use. (See *Lightning Switch,* also *Aerial Switch, Down Lead.*)



Switch having a break distance of not less than 4 inches.

GROUND WIRE—The wire connecting a receiving or transmitting set to the earth. The underwriters specify not less than No. 14 B & S gauge copper wire. (See *Ground Connection.*)

GROUNDED ROTOR—See *Rotor, Grounded Connection.*

GROUP FREQUENCY—The number of separate trains or groups of waves per second in a damped or undamped system of radio transmission. This frequency is to be distinguished from the frequency of the individual waves. Thus in a spark transmitter, for example, the condenser in the transmitting circuit will be momentarily charged and discharged. The discharges will occur in the form of trains of oscillations, each oscillation having a certain definite frequency, but the trains or groups occurring at definite intervals, the frequency of these intervals being called the group frequency. (See *Frequency,* also *Spark Transmission* and *Undamped Waves.*)

GUARD LAMP—An incandescent lamp having a straight filament, sometimes shunted across the armature and field leads of a rotary converter used in radio transmission. Its purpose is to protect the windings from injury due to the inducing of oscillatory surges from the high-frequency circuits. (See *Rotary Converter.*)

GUTTA PERCHA—An insulating material derived from the milky secretion of certain trees, used as an insulation for submarine cables on account of its ability to resist the action of salt water. It is used to a lesser extent as a general insulating medium for wires, but owing to its scarcity and limited field of usefulness, rubber or rubber compounds are more widely used. (See *Insulating Materials.*)

GUY WIRE—Wires used to brace aerial masts for receiving or transmitting stations. Such guys are generally heavy galvanized wires attached to the mast at various points and extending radially downward and anchored to surrounding rigid objects or by means of some form of anchor in the ground. (See *Aerial.*)

H

H—The chemical symbol for *hydrogen.* In electrical and radio usage it is the symbol for *magnetizing force* or *magnetic field intensity*, adopted as such by the International Electrotechnical Commission and by the American Institute of Electrical Engineers. It has also been adopted by the I. E. C. as the symbol for *Henry* (q.v.). (See *Magnetic Field.*)

HALF WAVE RECTIFICATION—The process of changing alternating currents to pulsating direct currents wherein only one-half of the full alternating current wave or cycle is rectified, the other portion being blocked by the action of the rectifier. In the illustration is shown a typical half wave rectification process. The upper graph shows the sine wave representing an alternating current, such as supplied from an ordinary alternating current house lighting system. Here A-B represents one complete cycle or two alternations, one positive and the other negative. In the lower graph is shown the form taken by the current after passing through a half wave rectifier. It now appears as a pulsating or intermittent direct current, only the upper or positive alternations having passed through the rectifier. The shaded portions below the line represent the negative or unused alternations. (See *Full Wave Rectification, Sine Wave of Alternating Current or E M F,* also *Charger, Storage Battery.*)



The upper graph represents an alternating current, and the lower graph shows the form taken by the current after passing through a half wave rectifier.

HALF WAVE RECTIFIER—Any system for rectifying or changing alternating currents to pulsating direct currents, wherein only half of the full alternating current wave is used. Essentially such a device is a uni-directional conductor, permitting current to pass in one direction only and submerging or blotting out the surges in the opposite direction. A typical example of a half wave rectifier is the crystal detector used in simple receiving circuits. Here the nature of the crystal is such that the currents are permitted to pass only in one direction. In half wave rectifiers used for charging storage batteries the effect is much the same. Where tubes such as the Tungar or Rectigon are employed, one tube is more commonly used, allowing the current to flow in one direction but submerging half of each cycle. (See *Rectifier, Full Wave,* also *Rectifier and Charger, Storage Battery.*)

HAMMER BREAK—A magnetically operated device for making and breaking contact in an electrical circuit. Hammer breaks are essentially the same as a vibrator or buzzer break but are made to withstand heavy currents without undue arcing, and hence are much slower in action. (See *Buzzer,* also *Spark Coil.*)

HAMMOND, JOHN HAYS, JR.—Inventor. Born San Francisco, Calif., April 13, 1888. B.S., Sheffield Scientific School (Yale), 1910; Sc.D., George Washington University. Inventor of type of torpedo for coast defense, controlled by wireless energy from coast fortifications, which was recommended to Congress for exclusive purchase by U. S. by Board of Ordnance and Fortifications, U. S. A.; invented system of automobile torpedo firing; alumino-thermic incendiary projectiles employed by Allied armies in World War; radio system of control of ships, employed on U. S. S. Iowa for target practice; a system of coastal patrol by aeroplane; a system of selective radio telegraphy, adopted by the U. S. Navy, U. S. Signal Corps, and U. S Army; system of aerial coast surveying adopted by the Bartlett Expedition for Polar exploration. President Radio Engineering Company of New York; director Hammond Radio Research Labs.; director Radio Corp. of America; consulting engineer to Radio Corp. of America and General Electric Co. Has licensed the American Tel. & Tel. Co., and the Radio Corp. of America under his electrical patents in U. S. and S. A. for commercial purposes only, U. S. Gov't retaining option on military uses. Has applied for over 224 patents in U. S. and Europe relating to Radio Telegraphy and Telephony and Wirelessly controlled torpedoes and various improvements in pipe organ mechanisms. Formerly member Advisory Board, U. S. Naval Board of Inventors, member Advisory Com. Langley Aerodynamic Lab. of Smithsonian Inst., co-operating with Third Naval Dist.; member Conf. Com. on National Preparedness (Sub.-Com. on Finance); Gov. Aero Club America (mem. Aerodynamic, Tech., Pub. Safety and Map and Landing Places Coms.); v.-p. Am. Soc. Aeronautic Engineers; mem. Inst. Radio Engineers (ex-treas., etc.), Am. Inst. E. E., Royal Soc. Arts (London); asso. mem. Am. Soc. M. E.; hon. mem. Nat. Inst. of Inventors, Harvard Aeronaut. Soc.; Fellow Am. Geog. Soc.; U. S. del. Radio-Telegraphic Com., London, 1912.

John Hays Hammond, Jr.

HAND CAPACITY—See *Body Capacity.*

HARD DRAWN WIRE—In radio usage generally confined to hard drawn copper wire, i. e., copper wire that has been hardened by repeated drawing without being annealed. It is used chiefly for aerials. (See *Aerial.*)

HARD TUBE—A vacuum tube is said to be hard when it has been evacuated of all gases to a high degree. The opposite is a soft tube, one in which the vacuum is not of a very high order and more or less gas particles are present. Hard tubes are used for amplifiers, both audio and radio frequency, while the soft tubes are used mainly as detectors or oscillators. Hard tubes may be used with high plate voltages, whereas soft tubes require comparatively low plate voltages, the tubes having a tendency to turn blue (see *Blue Glow*) under the influence of high plate potentials. (See *Detector,* also *Amplifier.*)

HARMONIC CURRENT—An alternating current which can be represented by a simple harmonic or sine curve. It may be considered as an alternating current, the waves of which are sinusoidal or uniform. (See *Simple Harmonic,* also *Sine Curve.*)

HARMONIC MOTION—A term signifying any periodic oscillatory motion, as, for example, the vibration or beating of a pendulum. The illustration shows the manner of indicating simple harmonic motion. The distance A-B represents 360 degrees of a circle, or, if it is assumed to represent a sine wave of alternating current, it will represent one complete cycle. Curves representing harmonic motion are used extensively in radio engineering to illustrate, in graphic form, the oscillations of an alternating current. (See *Sine Wave,* also *Simple Harmonic Vibration* and *Oscillations.*)



Illustration showing method of indicating simple harmonic motion.

HARMONICS—Oscillations to which a circuit will respond in addition to the basic or fundamental oscillations. The effect is similar to that in sound, where, for instance, the primary or fundamental tone struck by an instrument may be accompanied by notes or tones of a higher pitch. In sound these harmonics are principally the third, fifth, seventh and the octave. In radio, a circuit may respond to oscillations of a frequency either higher or lower than the fundamental frequency, as, for example, one third, one fifth or one seventh, or, again, double or treble the original frequency. As a concrete example, with a fundamental wave-length of 240 meters, the harmonics might be

40 meters or 80 meters. The corresponding frequencies would be approximately 1,250,000 cycles, 7,500,000 cycles and 3,750,000 cycles. (See *Harmonic Suppressor, Side Bands,* also *Harmonic Motion, Oscillations, Wave-length.*)

HARMONIC SUPPRESSOR—A device used in radio transmission and in laboratory work, for the purpose of eliminating undesired frequencies (wavelengths). Essentially such a device is a *filter* (q.v.) so arranged as to suppress or eliminate certain frequencies or *harmonics* (q.v.). In radio broadcasting it is particularly essential that all undesired frequencies or *harmonics* be suppressed. Basically the system involves a special coil shunted by a condenser and tuned to the frequency of the interfering wave, the main tuning circuit at the same time being adjusted to the desired frequency. (See *Broadcasting, General Treatise on Methods,* also *Transmission* and *Radio Telephony.*)

HAZELTINE NEUTRODYNE RECEIVER—The radio receiver designed by Professor Hazeltine, employing the Neutrodyne circuit. Essentially these are five-tube receivers employing two stages of tuned and neutralized radio-frequency amplification with the conventional detector and two audio-frequency stages. In addition to the five-tube Neutrodyne receiver there are numerous types involving the Neutrodyne principle in conjunction with *reflex systems.* (See *Neutrodyne.*)

HEAD TELEPHONE OR HEADPHONES—Telephone receivers arranged with a band to fit over the operator's head, thus leaving him free use of both hands. Head-phones are used in commercial radio work, the operator being free to handle a key or the controls of the receiver or transmitter. They are also used in broadcast reception where the strength of signals is not sufficient to permit the use of a loud speaker, and also in some cases to tune in distant signals before attaching a loud speaker. (See *Watch Case Receivers.*)

Illustration by courtesy of C. Brandes, Inc.
A type of headphone used extensively in radio reception.

HEAVISIDE, DR. OLIVER. — Born in London on May 13, 1850, Dr. Heaviside was engaged in telegraph work for a few years, but after 1874 he lived in retirement studying Clerk-Maxwell's theory and applying it to telegraph and wireless problems. Elected a Fellow of the Royal Society in 1891, he was also Faraday Medallist of the Institution of Electrical Engineers and Hon. Ph.D. of Gottingen University. The name of Dr. Heaviside is primarily associated with the theory, propounded by himself, of the existence of a permanently ionized layer in the upper atmosphere capable of deflecting electro-magnetic waves and thus permitting wireless communication round the earth.

HEAVISIDE LAYER—An assumed layer or stratum of the atmosphere supposed to exist from fifty to one hundred miles above the earth's surface according to the Heaviside Theory. Heaviside's theory supposes this stratum to consist of heavily ionized gas which is conductive and acts as a gigantic reflector of electromagnetic waves (radio waves). It is this layer which is supposed to reflect the electric waves and force them to follow the curvature of the earth. This theory partially explains—if true—why radio signals are transmitted over great distances instead of being radiated off into space and lost. It has been accorded the support of many eminent scientists. Elihu Thompson has propounded an alternative theory which assumes the waves as attached to the earth and gliding along over the surface. (See *Gliding Theory.*)

HEAVISIDE LAYER THEORY—The theory of an upper ionized stratum from fifty to one hundred miles above the earth's surface, which is assumed to act as a reflector of radio waves and thus force them to follow the curvature of the earth. None of the theories thus far advanced has been proven, but it has been definitely established that these waves do follow the curvature of the earth. (See *Heaviside Layer,* also *Gliding Theory.*)

HEDGEHOG TRANSFORMER—A type of audio transformer so called because of its peculiar construction. The core is cylindrical in shape and consists of a great number of soft iron wires around which is a bobbin holding the primary and secondary windings. After the windings are completed the wires forming the core are bent back over the form and held in place, completely surrounding the windings. (See *Audio-Frequency,* also *Transformer.*)

HEIGHT OF AERIAL—The elevation of an aerial system as used in radio transmission or reception. The effective height is roughly considered as the height above the earth or surrounding objects. The range of a station having constant power is dependent upon the height of the aerial, other factors of radiation being unchanged. In other words, increase of height increases the range within certain limits. (See *Radiation from Antenna,* also *Transmission.*)

HEISING, RAYMOND A.—Electrical Engineer, born Albert Lea, Minn., August 10, 1888. Educated University of N. D., Elec. Engineer, 1912; University of Wisc., M.S., 1914 Grad. Work in Physics, Research and Development of Radio Tel. since 1914; Trans-Atlantic test in 1915; for Army and Navy use during War, aeroplane, chaser, intership communication; since War continued research and development ship to shore use, trans-Atlantic test, 1923. Author of several technical papers; numerous inventions widely used in present broadcasting stations.

HEISING MODULATION—A system of modulating radio currents for radio transmission, such as broadcasting, developed by *R. A. Heising.* The fundamental principle is shown by the illustration. Here the customary antenna and ground are connected with a high-frequency alternator, A; the field of the alternator, FW, is connected to the grid return and filament of the vacuum tube circuit, and through the "B" battery BB to the plate P of the tube. The microphone circuit comprises a microphone M connected to the primary of a transformer T through the battery MB. The secondary of the transformer is connected to the grid G of the vacuum tube and the filament F. R is the usual rheostat to control the filament of the tube and AB is the filament lighting battery. In operation the speech or sound vibrations are impressed on the microphone M, thus varying the resistance of the current flowing from the battery MB and through the transformer T. This serves to vary the potential of the grid G, and as this potential changes, the current in the plate circuit will also be varied, the same characteristics being maintained. As the field winding FW is in the plate circuit, it is evident that the antenna current will be modulated in accordance with the variations of the speech or sounds introduced at M. (See *Grid Control,* also *Modulation* and *Broadcasting, General Treatise on Methods.*)



Circuit illustrating the fundamental principle of the Heising system of modulation.

HELIOGRAPH—An instrument involving a movable mirror, by means of which the sun's rays are reflected and made use of as a signalling device. In practice it is usually arranged with a blind or shade to cover the mirror at rapid intervals by pressing on a key device. In this manner the flashes may be made at definite intervals, as in the case of the Morse light. (See *Code,* also *Morse Light.*)

HELIX—The shape assumed by a line or wire wound in a single layer around a cylinder. Generally speaking, a *solenoid* (q.v.). A device in the form of a helix was formally used in transmitting circuits to vary the inductance, or, practically speaking, the wavelength. It usually was a number of turns of heavy copper or aluminum wire wound on an insulating form. Clips were provided to permit a variation in the contact point and hence any necessary change in the value of the inductance. (See *Oscillation Transformer.*)

HENRY, JOSEPH—Born in 1797, died in 1878. An American Physicist, noted for his researches in electromagnetism. He developed the electromagnet which had been invented by Sturgeon in England, so that it became an instrument of far greater power than before. In 1831 he employed a mile of fine copper wire with an electromagnet, causing the current to attract the armature and strike a bell, thereby establishing the principle employed in modern telegraph practice. He was made a professor at Princeton in 1832 and during his experimenting there he devised an arrangement of batteries and electromagnets embodying the principle of the telegraph relay which made possible long distance transmission. He was the first to observe magnetic self-induction, and performed important investigations in oscillating electric discharges (1842), and other electrical phenomena. In 1846 he was chosen secretary of the Smithsonian Inst. at Washington, an office which he held until his death. As chairman of the U. S. Lighthouse Board he made important tests in marine signals and lights.

Joseph Henry.

In meteorology, terrestrial magnetism and acoustics he carried on important researches. Henry enjoyed an international reputation and is acknowledged to be one of America's greatest scientists.

HENRY—The unit of inductance, named after the American physicist, Joseph Henry, who first produced high-frequency oscillations in 1832. A coil of wire is said to have an inductance value of one henry when a current passing through it changes at the rate of one ampere per second and an electromotive force of one volt is produced. As the henry is too large a unit for practical purposes, the thousandth part of a henry, known as the *milli-henry*, or the millionth part, known as the *micro-henry*, are more commonly used. Another much-used term is the centimeter, which is the thousandth part of a micro-henry. The abbreviation for henry is H, and for micro-henry μH. (See *Centimeter Gram Second, Centimeter*, also *Inductance.*)

HERTZ, HEINRICH RUDOLF—Born 1857, died 1894. A German physicist noted as the discoverer of electromagnetic waves (1888) which form the basis of wireless telegraphy. He found that waves produced by the spark of a simple device called the oscillator could be detected by a loop or square of wire known as the resonator, and he was able to show the reflection, refraction, diffraction and poralization of the waves. These remarkable discoveries demonstrated the practical possibilities of radio-telegraphy. He also made valuable experiments with electric phenomena in vacuum tubes.

Heinrich Rudolf Hertz.

HERTZIAN WAVES—Term occasionally applied to radio or electromagnetic waves, they being named after Dr. Heinrich Rudolf Hertz owing to his extensive researches into electromagnetic waves. (See *Hertz*, also *Clerk-Maxwell*, and *Ether Theory.*)

HETERODYNE—The term originally applied by Fessenden to a method of reception of electromagnetic waves, wherein the principle of *Beats* (q.v.) was employed. It is derived from the words "hetero," meaning other or different, and "dyne," meaning power.



Fig. 1.—The original form of heterodyne receiver.

In its original conception by Fessenden, before the widespread use of vacuum tubes, it was used in conjunction with crystal receivers for the reception of *undamped waves* (q.v.). The heterodyne principle involves production of a local series of oscillations which are tuned to a frequency differing from the frequency of the incoming oscillations from the antenna. The difference between the two is known as the *beat frequency*. (See *Beats*, also *Heterodyne Receiver.*)

HETERODYNE RECEIVER—A receiver for electromagnetitc (radio) waves employing the *heterodyne* principle. The illustration Fig. 1 shows the original form of heterodyne receiver, wherein the local oscillations were produced by means of a direct current arc gap and associated circuits, and combined through a coupling medium, with the oscillations in the antenna circuit. Here the heavy lines represent a conventional crystal receiver circuit. L1 and L2 are respectively primary and secondary of a vario-coupler, C is a variable tuning condenser, D the crystal detector and T the head phones. If the dotted line is assumed as a connection to the ground, this will constitute a complete receiver. For the heterodyne purpose, however, a special coil L3 is employed in the ground circuit. Coupled to this is the secondary L4. C1 is another tuning condenser and A is an arc gap fed by 110 volts direct current. In operation the circuit represented by the light lines acts as a generator of undamped oscillations, these oscillations being supplied to the antenna circuit and the frequency varied by means of the condenser C1 and the coil L4. If the receiving tuner is tuned to a certain wave-length corresponding to incoming signals, and the generator system tuned to a different frequency, the difference between the two frequencies will be a *beat* frequency which will be present in the detector circuit. This new series of oscillations will be rectified by the detector D and will be audible in the head phones, T. The action of this system is shown by the series of curves given in Fig. 2. Here the incoming oscillations (signals) from the antenna are shown in graph 1 at the top of the illustration. These oscillations are of continuous amplitude or *undamped* (q.c.). Graph 2 shows the local oscillations. If we assume that the distance from A to B represents the time, it will be apparent that there are more oscillations per unit of time in the case of the incoming signals—



Series of graphs showing the action of a heterodyne receiver.

hence the second graph indicates that the local oscillations have a lower frequency. Graph 3 represents the *beat* resulting from interaction of the two upper series of oscillations and the frequency corresponds to the numerical difference. When the two upper groups of oscillations are opposed, the beat current is zero, and when they are in phase, or assisting each other, the beat current is maximum. When rectified by the crystal detector action the beats take the form shown in graph 4, the lower half of each cycle having been submerged. The telephone current of a periodic nature is indicated by the bottom graph, the original signals being represented in the phones by a series of contractions of the diaphragm. (See *Heterodyne*, also *Beats* and *Super Heterodyne.*)

HETERODYNE, SELF—See *Self-Heterodyne.*

HETERODYNE WAVE-METER—A wave-meter—device for measuring the wave-length of coils, circuits or incoming and outgoing signals—which utilized the heterodyne principle. Briefly the action is as follows: It has already been explained under Heterodyne Receiver that when the local oscillations and the incoming oscillations are opposed, the beat current is zero. It follows, then, that with a pair of phones connected in the circuit, the beat signals will be audible only when the two frequencies are different. Now if a suitable means is present for varying the frequency of the local oscillations, in practice a combination of coil and condenser, the local circuit can be tuned to a point where the two frequencies concur or are similar and no beat is audible. As the frequency is proportional to the capacity and inductance in a circuit, and as wave-length can easily be figured when the frequency of the local generating system is known, the wave-length of the incoming signals must be that of the local circuit when the beat is zero. The condenser dial on the heterodyne wavemeter can thus be calibrated directly in meters and a nearly true reading of the wave-length of incoming signals obtained. (See *Beats*, also *Heterodyne* and *Wave-meter.*)

HIGH FREQUENCY—A very general term applied to alternating electric currents. As a rule, alternating currents having frequencies above one thousand *cycles* (q.v.) per second are referred to as high frequency currents. When the frequency is extremely high, of the order of hundreds of thousands of cycles, the current is usually referred to as high frequency, oscillatory current. There is no definite level or line of distinction between high and low frequency currents. In radio practice, the audio frequency currents are generally considered below twenty thousand cycles per second and known as low frequency currents. The radio frequency or frequencies above twenty thousand are considered as the high frequency currents, although here again there is no definite level or line of demarcation between the two areas. (See *Audio Frequency*, also *Radio Frequency* and *Frequency.*)

HIGH FREQUENCY ALTERNATING CURRENT—See *High Frequency Current.*

HIGH FREQUENCY ALTERNATOR—An alternating current machine or alternator, designed to produce currents having high frequencies, generally above one thousand cycles per second. Such machines are used in high power radio telegraph transmission (not broadcasting) producing undamped or continuous waves. (See *Alternator*, also *Alexanderson Alternator.*)

HIGH FREQUENCY AMPLIFICATION—The process of stepping up or amplifying currents of high frequency. In radio circuits, the high frequency currents are known as radio frequency oscillations. In radio circuits the audio frequency (low frequency) currents and the high or radio frequency currents are usually in different parts of a circuit. When we consider alternating currents having a frequency above, say, twenty thousand cycles per second as radio frequency, and those below that limit as audio frequency, it is easy to consider the radio frequency currents as existing in all stages between the aerial and the detector. Beyond the detector, the alternating currents having become uni-directional surges, we can consider these currents as being audio frequency currents.

Thus we have a definite dividing line in any radio receiver using but one detector, the detector or rectifier marking the transition from radio frequency to audio frequency. Thus, any means of amplifying the signals before they reach the detector will be known as high frequency amplification. (See *Audio Frequency*, also *Amplifier.*)

HIGH FREQUENCY BUZZER—A *buzzer* (q.v.) designed to produce a very high note. The term "high frequency" in this case merely indicates that the pitch or frequency (vibration) is high in comparison with the ordinary buzzer, the sounds of course being actually of audible frequency. The general scheme of such a buzzer is about that of the ordinary type as used in conjunction with electric bells or signal systems, the armature, however, being very thin and thus permitting rapid make and break for the current. Such buzzers are used extensively in connection with crystal receivers for the purpose of testing and also for code practice. (See *Buzzer* also *High Frequency* and *Armature.*)

HIGH FREQUENCY COMPONENT OF PLATE—The high frequency currents present in the plate circuit of a vacuum tube receiver, as distinguished from the audio or low frequency currents. (See *Feed-Back*, also *Plate Component, High Frequency*, and *Regeneration.*)

H.F.C.—Abbreviation used abroad and occasionally in the United States for high frequency current. The more common term is radio frequency current and no abbreviation is used as a rule. (See *Radio Frequency Current*, also *High Frequency.*)

HIGH FREQUENCY CURRENT—Alternating currents having frequencies above certain limits, as, for example, the radio frequency currents employed in radio transmission, which are usually of a frequency above one hundred thousand cycles per second. (See *High Frequency*, also *Low Frequency* and *Radio Frequency.*)

HIGH FREQUENCY OSCILLATION—The term oscillation is generally applied to an alternating current of very high frequency. Thus radio frequency currents, which may run into hundreds of thousands of cycles per second, are called high frequency oscillations. (See *Oscillation.*)

HIGH FREQUENCY RESISTANCE—Resistance to the passage of alternating currents of high frequency. Said of wires, coils, circuits and apparati. The resistance of a certain conductor or part of an electrical circuit, as in radio, may be comparatively higher in the case of high frequency currents than to alternating currents of a low frequency. This is due to the "*skin effect*" (q.v.) it being a phenomenon of radio frequency (high frequency) currents that they have a tendency to concentrate near the surface of the conductor. For this reason, small wires are more apt to have high radio frequency resistance, as obviously the surface on which the currents can travel is restricted. (See *High Frequency*. also *Skin Effect* and *Resistance.*)

HIGH PASS FILTER—An arrangement of electric circuits designed to permit ready passage of high frequency alternating currents while at the same time presenting high resistance or impedance to alternating currents of low frequency, generally within certain definite limits. (See *Filter* also *Filter, High Pass.*)

HIGH PRESSURE—A term occasionally used to denote high potentials or voltages. (See *High Tension*, also *High Potential.*)

HIGH POTENTIAL—One of the several terms used to indicate high voltage. (See *High Potential Battery*, also *High Voltage.*)

HIGH POTENTIAL BATTERY—Another term for "B" battery, the battery used to supply potential to the plate of a vacuum tube. The term "high potential" is used here, only in a comparative sense, the voltage of the battery being high in proportion to that of the filament or "A" battery. High potential batteries for radio usage are generally furnished in blocks of 22½ or 45 volts. (See *High Voltage, High Tension* and *"B" Battery.*)

HIGH RESISTANCE—The property of any circuit whereby it offers considerable opposition to the flow of electric currents. There is no very distinct line of demarcation between high and low resistance. One of the common applications of the term is in the case of a *grid leak* or grid resistance. Here the resistance may be upward of a half million ohms, running into several million ohms in certain cases. An example of low resistance elements is that of a *rheostat* for controlling the filament current. Here the resistance is relatively low, rarely more than thirty ohms. The average resistance of the magnet windings in headphones (as used in radio) is one thousand ohms. The term "high resistance" is also used in a comparative sense in respect to various instruments or parts of radio circuits. Here the resistance in most cases should be as low as possible, and therefore a resistance of even a few ohms may be referred to as *high*. While resistance to direct currents is generally the feature of resistance coils and units, the opposition to currents of an oscillatory nature (high frequency alternating currents) may be of the utmost importance, and it is often the case that a circuit has little direct current resistance but very high resistance or *impedance* (q.v.) to high frequency currents. (See *Resistance, Impedance*, also *Skin Effect.*)

HIGH RESISTANCE JOINT—Any connection between two wires or conductors which offers resistance to the passage of current due to defective contact or imperfect connection through solder or any other medium. When bare wires are joined they should be carefully scraped and soldered. Too much solder is a bad feature, as the resistance of solder is naturally far higher than that of the copper wire. (See *Corrosion*, also *Soldered Joints.*)

HIGH RESISTANCE TELEPHONES—Headphones or telephones used in radio reception, having high resistance windings. In the ordinary telephone receiver used with the commercial telephone systems, the windings of the telephone magnets have a relatively low resistance, generally less than one hundred ohms. Such phones would not be sufficiently sensitive for radio usage, the average resistance in this case being about one thousand ohms. The resistance here refers to the ohmic resistance of the many turns of wire wound around the magnets. This resistance is not a required feature, the factor of importance being the number of turns. Inasmuch as space is a factor to be considered, it is necessary to use very fine wire in order to permit use of the thousands of turns essential. The resistance of this fine wire is of course high. Where very high resistance windings are used—and this indicates small wire—it is sometimes advisable to use a by-pass for the heavy plate potentials to protect the windings. (See *Ampere Turns*, also *Output Transformer* and *High Resistance*.)

HIGH SPEED RECEPTION AND TRANSMISSION—The reception or transmission of radio messages by automatic means in order to obtain much greater speed than would be possible under the manual system or hand opereating and recording. The general practice is to record the messages to be transmitted on a tape by means of a punching machine. They are then sent automatically through a high speed automatic transmitter and received automatically at the same high speed by a machine which punches the messages or records them on some form of tape or sheet. The more common of these methods is the *Wheatstone Transmitter*. (q.v.).

HIGH TENSION—One of the numerous terms used to denote high voltage. "B" batteries as used in radio reception are generally known as high tension batteries to distinguish them from the low voltage storage battery or dry cells used to light the filaments. Abbreviation H. T. mostly used in magazines and books printed in England.

HIGH TENSION BATTERY—Term applied to "B" batteries used in radio reception to supply potential to the plates of the vacuum tubes. These batteries usually are in blocks of twenty-two and a half or forty-five volts. (See *"B" Battery*.)

HIGH TENSION CIRCUIT—Term occasionally applied to the part of a radio circuit in which high potentials are present, as in the plate circuit of a vacuum tube. Here the "B" battery is in the circuit. (See *High Tension*, also *"B" Battery*.)

HIGH TENSION INSULATOR—Insulators of large dimension and rugged design, possessing unusual insulating properties in order to withstand high voltages. As a rule such insulators are made of high grade porcelain and arranged with annular ridges or "petticoats" to give greater surface and reduce the possibility of surface leakage. The illustration shows a form of high tension or high potential insulator. (See *Insulator*, *High Tension*, also *Petticoat Insulators*.)



A high potential insulator.

HIGH VACUUM—A term applied to vacuum tubes when they have been highly exhausted of air. That is, an almost perfect vacuum. When a vacuum tube has a very good vacuum—has been highly evacuated of gases—it is generally called a "hard" tube. A high vacuum is essential in tubes to be used as amplifiers or for transmission. (See *Vacuum Tubes, Theory of Operation*.)

HIGH VOLTAGE—A very indefinite term, used in ordinary electrical practice to denote voltages above 600, but applied in radio practice to much lower potentials, as, for example, a "B" battery, which is generally referred to as a high voltage battery in spite of being generally below 100 volts. The term used in this sense is one of comparison with the low voltage of a storage or other type of "A" battery. (See *Voltagee*, also *Potential*.)

HIGHLY DAMPED WAVES—An expression applied to waves or trains of waves wherein the amplitude or strength of each succeeding oscillation or train of oscillations is greatly decreased. If the progressive decrease in amplitude or strength is very gradual, that is, if the waves die out slowly, they are said to be feebly damped, but if they die out rapidly they are referred to as being highly damped. (See *Damped Waves*, also *Decrement* and *Amplitude*.)

HOGAN, JOHN V. L.—American radio expert. Born at Philadelphia, Pa. He was educated at Sheffield Scientific School, Yale University, where he made a special study of physics and mathematics. In 1906 he became assistant to Dr. Lee De Forest, and in 1909 he joined the National Electric Signalling Co. In 1914 he was appointed chief research engineer to the International Radiotelegraphic Company. Hogan has written many articles on radio and is a past president of the Institute of Radio Engineers, member of the American Institute of Electrical Engineers, of the American Association for the Advancement of Science, of the Radio Club of America and other societies.

John V. L. Hogan.

HOMOPOLAR—Synonymous with unipolar. Having but one pole. Said of a dynamo having its conductor or armature rotating around a single pole of a field magnet. (See *Multi-Polar*.)

HONEYCOMB COIL—A coil used in radio, having a peculiar construction, somewhat similar to a honeycomb. The illustration shows a typical honeycomb coil used as an inductance in receiving circuits. The object of this staggered winding system is to reduce the self-capacity between wires to a minimum without reducing the inductive value. The chief value of such a winding method is that it permits the retaining of high inductance value in a limited space, without undue *high frequency resistancee* (q.v.). (See *Inductance*, *Distributed Capacity* and *High Frequency Resistance*.)



Honeycomb coil used in radio reception.

HOOK UP—The general term in the United States to designate the diagram for any complete radio receiver or transmitter, or for any specific part of such a circuit. Thus, when we refer to a hook-up for Radio receiver, we mean a diagram, either schematic (using symbols for the parts) or perspective (showing pictures of the parts) which gives the various parts necessary and the manner of connecting them to each other to form the complete circuit. Similarly we may use the term "hook-up" to describe a sketch or circuit for connecting various instruments such as *ammeters*, or *voltmeters*, *wavemeters* and the like. (See *Circuit*, also *Diagram*.)



The upper diagram is in schematic form and shows a single tube regenerative receiver, and the lower diagram is in perspective form and shows a crystal receiving set.

HOOPER, STANFORD C.—American Naval wireless expert. Born August 16, 1884, at Colton, California, and educated at San Bernardino, California. He joined the Southern Pacific Company as a telegraph operator. In 1901 he entered the Naval Academy at Annapolis, and entering the Navy was advanced to Commander in 1918. From 1910-11 he was instructor in electrical engineering, physics and chemistry at the U. S. Naval Academy, and in 1912-13 Fleet Radio Officer of the United States Atlantic Fleet. During the great war he was responsible for the supply of wireless instruments, etc., for the American Navy, and he was also responsible for the construction of many of the larger American wireless stations including those at Annapolis, San Diego and Pearl Harbor. Hooper was one of the chief men concerned with the radio-compass system now used in the American Navy.

HORIZONTAL AERIALS—Aerials—overhead wire systems—for the reception or transmission of radio signals, wherein the major portion of the aerial is horizontal—parallel to the earth's surface. Typical examples are the "T" and inverted "L" aerials. In the former type, the flat portion suspended horizontally between two supporting structures and a lead-in wire is attached to the center and thence to the apparatus. In the latter type, the lead-in is attached to either end, giving a shape somewhat similar to an inverted L, from which the name is derived. The more common term is "flat top." This term is now somewhat ambiguous, as single wire aerials are used more or less extensively for receiving purposes, whereas formerly a system of several horizontal wires was employed. (See *Flat Top Aerial or Antenna*, also *Aerial T Type* and *Inverted* Γ *Aerial.*)


PULLEY
INSULATOR
ROPES TO PREVENT SWINGING OF AERIAL
AERIAL WIRES NOT SMALLER THAN NO. 14 B.&S.
GUYS
TO THE RADIO SET.
HORIZONTAL AERIAL

A horizontal aerial of the inverted "L" type.

HORN, LOUDSPEAKER—A device, generally in the shape of a horn, used in conjunction with a heavy duty telephone receiver or loudspeaker unit, to reproduce loudly the signals or music from a radio receiver. In operation, the horn has attached to it at its small end a unit or telephone receiver. When the diaphragm of the unit is actuated by the signals, speech or music, the column of air in the open tube is displaced, creating audible sounds which can be heard at a distance or throughout a room. Assuming other conditions equal, the volume will be more or less in proportion to the size of the norn, or more specifically to the amount of air displaced by the signals. When a telephone receiver is used without horn, the opening above the diaphragm being unconfined, only a small column of air is displaced and the volume will not be great under ordinary circumstances. When a horn is attached, however, the sound being confined will displace a relatively greater amount of air—depending mainly on the shape and size of the horn—and the volume will be measurably greater. (See *Loudspeaker*, also *Acoustics* and *Loudspeaker Units.*)



Three types of horn loudspeaker.

HORSE POWER—The unit of power used in the United States and Great Britain. It is defined as the power required to lift 550 pounds to a height of one foot in one second, or similarly, 33,000 pounds to that height in a minute. The term "foot-pounds" is derived from this value. Thus, one horsepower is the power required to perform 550 foot-pounds of work per second of time. (See *Horse Power, Electrical.*)

HORSE POWER, ELECTRICAL—The unit of electrical work similar to the mechanical horse power. It is actually mechanical horse power expressed in *watts* (q.v.). One electrical horse power is equivalent to 746 watts. In the *centimeter gram second* (q.v.) system of units, the unit of work is the *erg.* This unit is too small for ordinary usage and the customary unit is the watt, which is equal to 10^7 ergs per second. The unit used in electrical power work is still larger; it is the *kilowatt* or one thousand watts. (See *Units*, also *Watts.*)

HORSESHOE MAGNET—A *magnet* (q.v.) in the shape of a horseshoe or letter U, both poles being brought nearer together so that they may act on the armature or "keeper." Generally a magnetized steel bar which retains its magnetism for a long period. The illustration, Fig. 1, shows a permanent horseshoe magnet. Such magnets are also used with external power, then being termed *electromagnets.* In this case the magnet is made of soft iron. The illustration, Fig. 2, shows a horseshoe *electromagnet.* Here the magnetic attraction is supplied by application of an external electric force to the windings WW, and the magnet being of soft iron, loses its magnetic attraction almost immediately upon withdrawal of the electric current, magnetizing force. (See *Telephone Receiver*, also *Electromagnet.*)



Fig. 1. A permanent horseshoe magnet.



Fig. 2. A horseshoe electromagnet.

HOT-WIRE AMMETER—An ammeter, or instrument for measuring electric current amperes, which depends for its action on the expansion of a fine wire under the influences of the heat produced in it, by the passage of the electric current to be measured. In the illustration the current to be measured is passed through the fine resistance wire A-B. P is a pointer moving over a graduated scale, and attached at its other end to a coiled spring S, which in turn is attached to the wire A-B by the silk thread T. The tendency of the spring is to move the pointer to the right, but owing to the pull of the thread in the normal position of the wire A-B, the pointer rests at zero at the left of the scale. As current is passed through the wire A-B, it heats and expands, thus permitting more or less slack to occur in the thread T and allowing the spring S to move the pointer over the scale toward the right, As soon as the current is withdrawn, the wire cools and contracts to its former size, thus again restoring the tension to the thread and returning the pointer to zero. Hot Wire ammeters are used extensively for measurement of currents at *radio frequency*, that is, extremely high frequency as in radio transmission. The average ammeter using a coil of fine wire would not be adaptable to this use, as the high voltage, high frequency current would burn out the coil. In addition to this. the length of these windings would affect the circuit and probably throw it out of *resonance* (q.v.). (See *Ammeter* or *Ampere Meter, Frequency, Resonance,* also *Instrument Shunts.*)



Illustration showing operation of a hot wire ammeter.

HOT WIRE INSTRUMENTS—Current measuring instruments which utilize the tendency of a fine wire to sag or expand under the heat caused by passage of an electric current through it. Such instruments may be used for direct or alternating current. (See *Hot Wire Ammeter.*)

HOT WIRE OSCILLOGRAPH — See *Oscillograph.*

HOT WIRE TELEPHONE—See *Thermal Telephone.*

HOT WIRE WATTMETER—An instrument used to measure combined volts and amperes, i. e., watts in a circuit. It comprises essentially a mirror, which is deflected according to the difference in expansion of two fine wires. (See *Hot Wire Instruments,* also *Wattmeter.*)

HOUR METER, AMPERE—An instrument used extensively in connection with storage batteries, to measure the input or output in amperes per hour. (*Ammeter* or *Ampere Meter.*)

HOUSE MAINS—A term much used in connection with storage battery charger and battery elimination devices. The term implies the main circuit of any standard house lighting system, either direct or alternating current. Thus in the case of a rectifier for charging storage batteries from alternating current, a lead is provided for connecting to the house mains, offering a means for introducing the required current into the device. (See *Current Direct,* also *Alternating Current* and *Chargers, Storage Battery.*)

HOWLING—The general term used to imply any undesired sounds produced in or by a radio receiver. Howling is usually caused by *feed-back effects* (q.v.). The most common example of howling is in the case of a regenerative receiver. Here the detector tube may have a tendency to generate its own oscillations As long as these oscillations are equal in frequency to any incoming signals there will be no howling, but should these local oscillations differ in frequency from the incoming series of signals, the result will be a howl resulting from the *beats* (q.v.) established owing to the difference between the two sets of oscillations. This is essentially the principle of *heterodyne* or "beat" reception, but in the case of a heterodyne, the effect is utilized, whereas in the case of a regenerative receiver it is undesirable. Interaction between various parts or different parts of a circuit may often lead to howling. (See *Feed-Back,* also *Regeneration, Reflex, Beats* and *Re-Radiation.*)

H. P.—Abbreviation sometimes used in radio for *high potential* or *high pressure.* In mechanics it is the standard abbreviation for *horse power.*

HOZIER-BROWN DETECTOR—A form of electrolytic detector, which, however, does not use a liquid electrolyte. It consists of a small pellet of lead oxide held more or less rigidly between two electrodes, one platinum and the other lead. (See *Detector,* also *Electrolytic Detector.*)

HYDROGEN—A gaseous chemical element. The symbol is H and its specific gravity is taken as 1, that of air being 14.4. It is colorless, tasteless and odorless and is the lightest known body. Hydrogen is a constituent of water, which is composed of one atom of oxygen and two atoms of hydrogen according to the chemical formula for water, H_2O. Hydrogen is used in radio transmission in connection with *arc generators.* (q.v.) (See *Poulsen Arc.*)

HYDROMETER—An instrument used to measure the *specific gravity* (q.v.) of a liquid. In radio it has an extensive use in connection with storage batteries. Various types of hydrometers are used to indicate the specific gravity of the electrolyte of a storage battery and hence in a manner, to indicate the state of charge of the battery. The illustration shows the standard form of hydrometer using a weighted float. In the illustration the float is shown inside the barrel of the instrument. In operation the bulb B is compressed and the tube T inserted in the open vent of a storage battery. When pressure on the bulb is released some of the electrolyte is drawn up inside the barrel and the float rises more or less within the barrel in proportion to the specific gravity or density of the electrolyte. With the hydrometer held in the manner shown, that is, upright, the numbers just at the level of the liquid in the barrel indicate the specific gravity. Thus, if the reading is 1250° or higher the battery is considered in fairly good operating condition —full charge being 1280° to 1300°. If the reading is below 1200° it indicates the need of charging, these levels not being arbitrary, a discharged condition being indicated by a reading of 1150° or lower. The use of a hydrometer is generally advisable and the reading accurate under ordinary conditions. If, however, water has just been placed in the battery, the reading may not be accurate for several hours due to the fact that the water and acid may not mix immediately. (See *Storage Battery Tests,* also *Electrolyte.*)



Hydrometer used to test the specific gravity of liquids.

HYGROSCOPIC EFFECT — The effect in any substance which permit it to absorb moisture. In the case of forms or tubes for radio coils and inductances this feature is particularly undesirable, as obviously, moisture lowers the dielectric value of the form and may cause it to warp. (See *Bakelite,* also *Tubing.*)

HYSTERESIS—The tendency of magnetization to lag behind the magnetizing force as, for instance, in an iron core in a *transformer* (q.v.). When the core of such a transformer is undergoing rapid reversals of magnetism, there is often an expenditure of energy which is not useful and which is converted into heat, thus representing a loss in power. This effect is more noticeable with certain qualities of iron. In other words, when rapid reversals of magnetism take place in a poor quality of iron core it may display a certain sluggishness. This is actually the lagging of the magnetic flux behind the magnetizing force producing it. This loss of energy is assumed due to the work required to alter the position of the molecules of the iron composing the core and the less energy expended in this manner the less the hysteretic losses. In designing transformers or armature cores, hysteresis must be taken into consideration and the iron must be of high quality to hold these losses at a minimum. (See *Eddy Currents,* also *Core, Transformer.*)

HYSTERESIS COEFFICIENT — The amount of energy wasted or lost in the process of magnetizing and de-magnetizing a unit volume of magnetic material is referred to as the hysteresis coefficient of that material. (See *Hysteresis,* also *Coefficient.*)

HYSTERESIS LOOP—Graphic illustration of losses due to hysteresis in any sample of core material. Loops are plotted in graphic curves of cycles of magnetization. (See *Curve,* also *Hysteresis.*)

HYSTERESIS LOSSES — The energy wasted or lost through hysteresis. (See *Hysteresis.*)

HYSTERETIC LAG — The lagging of magnetization due to the effect of hysteresis. (See *Hysteresis,* also *Magnetization.*)

I

I—The abbreviation adopted by the *International Electrotechnical Commission* (q.v.) and American Institute of Electrical Engineers, to denote current in amperes. The small or lower case (i) may also be used where the capital letter is not advisable. (See *Current.*)

I ARMATURE—An armature used in generating machines, having a core resembling the letter I in shape. (See *Armature,* also *Core.*)

I.C.W.—The customary abbreviation for "interrupted continuous waves." This is a system of radio transmission wherein the waves are modulated at a constant low frequency. (See *Interrupted Continuous Waves,* also *Modulation.*)

IDLE CURRENT—A name often applied to the component of an alternating current which contributes nothing to the power. This is also known as the *wattless component* (q.v.) or the *wattless current* (q.v.). It represents the component which, being in quadrature with the electromotive force in the circuit, thus has no active value—adds nothing to the total power. (See *Current,* also *Electromotive Force* and *Alternating Current.*)

I.E.C.—The abbreviation for *International Electrotechnical Commission,* the body which suggested the international electrical and magnetic abbreviations and symbols. (See *Symbols,* also *Units.*)

IMPACT OR SHOCK EXCITATION—The method of producing *free oscillations* (q.v.) in a circuit by means of an exciting current of short duration compared to that of the resultant oscillations. The term is a general one and broadly covers the various methods of generating oscillations in which an oscillatory circuit is thrown into electrical vibration at its natural or fundamental frequency by means of an electromotive shock or exciting force of short duration. Also covers the term *Impulse Excitation.* (See *Oscillations,* also *Fundamental Frequency.*)

IMPACT TRANSMITTER—Apparatus for transmitting radio waves wherein the transfer of energy from the primary or exciting circuit to the oscillatory circuit takes place during one pulse or vibration of the exciting current. (See *Impact or Shock Excitation,* also *Transmitter.*)

IMPEDANCE—The total resistance to the flow of alternating current in a circuit. Impedance combines the ohmic resistance and the apparent resistance due to self-induction. When a direct electromotive force is impressed on a circuit, the current flowing in that circuit depends directly on the ohmic resistance of the circuit. The formula is according to Ohm's law $I = \frac{E}{R}$, I representing the current in amperes, R the resistance in ohms and E the electromotive force in volts. Now if this direct electromotive force is replaced by an alternating EMF (electromotive force) and the ohmic resistance remains the same, the total resistance of the circuit to the alternating EMF will nevertheless be greater than in the case of direct current. Now the ohmic resistance is still the same but we have added to it the apparent resistance due to the self-induction of the circuit. In other words the inductance of the circuit has a marked effect on the current flowing in the circuit. What actually occurs is that the self-induction sets up a *counter-electromotive force* (q.v.) which continues to act against the impressed EMF as long as the flow of current persists. The result is a reduction in the current flowing in the circuit, the EMF having been, in effect, reduced, and hence according to the law above, $I = \frac{E}{R}$, the current is less. This added resistance, due to self-induction, is referred to as *reactance* and the flow of current in an alternating current circuit is thus governed by the ohmic resistance and the reactance. The application of the term "apparent resistance" to describe the added resistance due to self-induction, is a concession to the fact that it is not actually resistance in the proper sense of the word. In a direct current circuit, the resistance actually wastes or dissipates a certain amount of energy. In the alternating current circuit, the ohmic resistance has the same effect. The reactance, however, does not dissipate energy. It merely reduces the effective EMF by means of the counter EMF and thus necessitates the application of a higher impressed voltage in order to maintain the same flow of current.

This is one of the major advantages of alternating over direct current. Alternating current can be transformed readily and can also be readily controlled by means of a reactance or choke coil, which by creating a counter EMF limits the current flowing in the circuit without dissipating any great amount of energy. (See *Alternating Current, Current Direct, Choke Coil,* and *Reactance.*)

IMPEDANCE COIL—A coil of wire or inductance coil, generally wound on an iron core, used in alternating current circuits to limit the current flowing in the circuit. In action such a coil serves through the medium of its self-induction, to create a counter electromotive force which acts against the impressed EMF (electromotive force) and thus reduces the current in the circuit according to ohm's law that the current is equivalent to the EMF in volts, divided by the resistance in ohms. An impedance coil is also known as a choke coil although the two may have somewhat different meanings. For example, a choke coil might be used in either direct or alternating current circuits, whereas an impedance coil as its name indicates, offers impedance, an effect only present in alternating current circuits. The simplest formula for impedance of a coil is the following: Impedance $= \sqrt{R^2+P^2L^2}$. Here it is assumed that the current takes the form of a *sine wave* (q.v.), then R is the resistance of the coil, L the coefficient of self-induction in henries and p is 2 π times the number of alternations per second. (See *Choke Coil, Alternating Current, Current Direct, Reactance, Impedance,* also *Impedance Coupled Amplifier.*)



Schematic diagram of an impedance coupled audio frequency amplifier. *(See Impedance Coupled Amplifier.)*

IMPEDANCE COUPLED AMPLIFIER —A system of amplifying radio signals, voice or music, whereby the successive stages are coupled or joined by means of impedance coils. This system is much used in audio amplifiers, the amplification being much more uniform over the necessary range of frequencies than in the case of the ordinary audio frequency transformer. This is also known as choke coil coupling or choke coil amplification. The illustration on the preceding page shows a typical impedance coupled amplifier for audio frequency currents. It will be noted that three stages are used. This is necessary owing to the lower amplification per stage. Using this system, then, three stages are necessary in place of the customary two stages of transformer coupled amplification. In the illustration, which is a schematic diagram of the circuit for such an amplifier, the impedances 1, 2 and 3 are in the form of *auto transformers.* (q.v.) R1, R2 and R3 are grid leaks ranging in value between one quarter megohm and one and one-half megohms. C1, C2 and C3 are stopping condensers of about 1 micro-farad capacity each. The variations in potential are transferred successively from stage to stage, the amplification factor being roughly the sum of the individual factors of the tubes. In other words the ratio of the windings of the impedances is one to one, or unity, and therefore no voltage amplification takes place. The resistances are the usual grid leaks and the condensers C1, C2 and C3 are to block the high plate voltages from the grids of the succeeding tubes. (See *Tuned Impedance,* also *Amplifier* and *Vacuum Tube Amplifiers, Theory of.*)

IMPEDANCE FACTOR—The ratio of the impedance to the ohmic resistance in an alternating current circuit. (See *Impedance,* also *Resistance.*)

IMPEDANCES, MATCHED — Arrangement of an amplifying circuit and the choice of an audio transformer or loudspeaker with due regard for the impedance of the circuit. Thus if the impedance of a certain amplifier tube is 10,000 ohms, and the resistance of a loudspeaker unit being used is 2,500 ohms, then for maximum response when used with an *output transformer* (q.v.) the impedance of the primary of the transformer should be equivalent to the total or 12,500 ohms. (See *Matched Impedances.*)

IMPREGNATED INSULATING MATERIALS—Cloth or paper impregnated with an oily or resinous substance to render it moisture proof and improve the insulating properties. Cardboard is sometimes treated in this manner and used for tubing to wind inductance coils. (See *Empire Cloth or Paper,* also *Insulating Property.*)

IMPRESSED ELECTROMOTIVE FORCE—The term used to distinguish the EMF (electromotive force) impressed on or applied to a certain part of an electrical circuit from the counter or back-electromotive force due to constants of the circuit. The term is sometimes used where a direct current is applied in a circuit, but it should be confined to use where a counter EMF (electromotive force) is present. (See *Counter Electromotive Force,* also *Choke or Choking* and *Reactance.*)

IMPRESSED FIELD — An electric or magnetic field of force impressed on or applied to a body or region (area) for the purpose of producing other fields of force. (See *Field.*)

IMPULSE—Electrically, an electromotive force which produces an impulsive rush or discharge of electricity. The term is used to distinguish between this form and an electromotive force producing a steady flow of current. (See *Current,* also *Electromotive Force.*)

IMPULSE E.M.F.—The more specific term designating an EMF (electromotive force) which produces an impulsive rush or discharge of electricity. It is defiined technically, as having a maximum value which is large compared with its average value, the average value being taken over a time equivalent to the *time-constant* (q.v.) of the circuit on which the EMF is impressed. (See *Current, also Electromotive Force.*)

IMPULSE EXCITATION—Method of exciting or starting oscillations in a circuit, such as the aerial circuit of a transmitter, by a sudden surge of impulse EMF (electromotive force) rather than by application of oscillations of the frequency of the circuit.



Connections of buzzer for generating damped oscillations suitable for testing by impulse excitation.

This system of impulse or shock excitation may be used for transmission and also has application in connection with testing or comparing of wavemeters. The illustration shows a buzzer connected with the necessary components to form a source of high frequency oscillations. This system is capable of producing through coupling from the coil L, currents by shock excitation. These currents can be used in a variety of ways for testing purposes. In operation the condenser is charged to the voltage of the battery at the instant the buzzer contact is open and when the contact closes, discharges through the coil L thus furnishing a series of oscilations to surge through the coil and by inductive coupling to any other coil placed in proximity to it. (See *Buzzer Exciter.*)

INCANDESCENCE — The glowing of any substance when brought to a white heat. The term is used in radio to signify the condition of the heated cathode or filament in a vacuum tube. In order to produce *electrons* (q.v.) it is necessary to cause the filament to become white hot, the condition being known as incandescence. (See *Filament.*)

INCONDUCTIVITY—A little used term signifying the condition of a substance by virtue of which it will not act as a conductor for electric currents. (See *Conductivity, Specific.*)

INDEPENDENT UNIT—A unit of a quantity, such as length, mass or time, chosen arbitrarily and without having any relation to any other unit. (*Centimeter Gram Second, or C. G. S.,* also *Fundamental Units.*)

INDICATING INSTRUMENTS — Any instrument or device which indicates values, as for example, a *voltmeter* or *ammeter.* (q.v.) (See *Instruments, Measuring.*)

INDIRECT CURRENT—Term for alternating current—now obsolete. (See *Alternating Current.*)

INDUCED CURRENT—The current in a circuit due to an induced EMF (electromotive force). The current produced by an EMF induced in a circuit due to a change in the magnetic flux linking the circuit with another. (See *Induced EMF,* also *Induction.*)

INDUCED E.M.F.—The electromotive force induced in a conductor or body. The phenomena of induced EMF (electromotive force) is the basis of operation of generating machines. Here a conductor is rotated or moved in a field of force, the action causing a change in the flux lines linking the circuits or the conductor. An EMF may also be induced by placing a coil in inductive relation to another coil through which alternating current is passing. Here the transfer is caused by induction. (See *Induction.*)

INDUCTANCE—The broad term used to designate any wire wound coil as used in radio practice for tuning units, inductive couplers and any variety of purpose. Actually the term is derived from self-induction or self-inductance, a property of a coil of wire by virtue of which it sets up a counter EMF (electromotive force) which serves to oppose the original EMF passing through it. When a certain circuit has inductance, it is to say that a number of turns of wire possessing self-induction are present in the circuit. The greater the inductance in a circuit the greater its opposition to the passage of an alternating current. The unit of inductance is the Henry. This is defined as the self-induction of a circuit or coil when the induced EMF is one volt with the inducing current varying at the rate of one ampere per second. (See *Alternating Current, Henry,* also *Inductance Coils.*)

A type of antenna inductance used in radio transmission.



INDUCTANCE, ANTENNA — Inductance (coil) placed in antenna circuit of transmitting set for purpose of increasing wavelength of the open or antenna circuit to any desired level. It is generally referred to as an antenna loading inductance or loading coil. In high power transmitting stations it is very often the case that the natural period or fundamental wavelength of the antenna is not as great as the intended operating wavelength. In this case a loading inductance is used to bring it up to the desired value. In some instances the fundamental wavelength is too high, in which case a condenser is placed in series to reduce the wavelength and then a few turns of inductance placed in series with the condenser and antenna for the purpose of tuning. Such inductances must be of a very rugged nature when high power is used, generally consisting of a comparatively few turns of heavy copper ribbon mounted on high tension insulators. The illustration shows a common form of antenna inductance used in radio transmission. (See *Loading Inductance,* also *Tuned Antenna.*)

INDUCTANCE COILS—Any coil of wire wound in such a manner as to possess the property of self-induction. Such a coil may be in almost any conceivable form, providing the turns are separated or insulated from each other. Inductance coils are a very necessary part of radio circuits, being used in conjunction with condensers to obtain resonance or desired wave-length. Such coils can also be arranged as separate circuits and placed in inductive relation to each other, thus permitting energy present in one to be transferred through induction to the other. The most common example of inductance in a receiving set is that of a tuning coil or vario-coupler. The illustration shows several forms of inductances known as tuning inductances. (See under separate headings as follows: *Inductance, Loading, Tuning, Tapped,* also *Inductance, Units of.*

Honeycomb type inductance coils.

Low-loss air-wound inductance coil made especially for tuned radio frequency work.

INDUCTANCE, DISTRIBUTED—Added inductance distributed throughout the length of a cable or telephone line to compensate for the capacity of the line. (See *Distributed Inductance.*)

INDUCTANCE, LOADING—Literally an inductance to load a circuit. The term is used to designate any inductance coil or unit used in series with the antenna for the purpose of increasing the wave-length of the circuit. (See *Inductance, Antenna.*)

INDUCTANCE, MEASUREMENT OF—Any process or means of determining the inductance value of a coil or circuit. The usual method is by formula. (Fully described under *Measurement of Inductance.*)

INDUCTANCE, MUTUAL—Symbol M. The number of linkages of flux lines or the flux that is common or mutual to two circuits which are adjacent to each other or inductively coupled. It is generally defined as the amount of the *flux* (q.v.) which is common to two linked circuits per unit of current flowing in the inducing circuit. In the illustration circuit A contains an inductance L_1 which is being traversed by an alternating electromotive force. Circuit B contains merely an inductance L_2 and a measuring device, M. Now, as the alternating E.M.F. passes through coil L_1 it sets up a field of force, or rather flux lines as shown. These lines link with the coil L_2 and an alternating E.M.F. is set up. Now, suppose that the inducing current flowing in circuit A is changing at the rate of one ampere per second and an E.M.F. of one volt is induced in the circuit B, or rather in coil L_2. We then say that the mutual inductance of the two circuits will be one henry. This is the same unit used for self-inductance and in fact, mutual inductance and self-inductance are virtually the same thing.

The effect of mutual inductance must be taken into consideration when measuring the fundamental wave-length, capacity or inductance of an antenna. That is to say, where a number of parallel wires are used, the mutual inductance between them must be taken into consideration as well as other values or constants. (See *Self-Inductance, Mutual Inductance, Induction, Coupling* and *Induced E.M.F.*)



Diagram which illustrates the mutual inductance between coil L_1 in circuit A and coil L_2 in circuit B.

INDUCTANCE, REACTANCE—Symbol x—The *reactance* present in a coil possessing self-inductance. The self-inductance in such a coil opposes the flow of alternating current due to the back *electromotive force* set up as a result of the changing magnetic field of the current. *Inductance reactance* (or *inductive reactance*) is the term used to define this opposition. *Inductance reactance* acts similarly to *resistance* (q.v.) in that it opposes the flow of an electric current. It is measured in *ohms* (q.v.), just as *resistance* is measured. It should be noted, however, that *inductance reactance* only opposes the flow of alternating currents, whereas resistance opposes the flow of both direct and alternating currents. Furthermore, resistance in offering opposition to current flow consumes power, while *inductance reactance* merely takes up energy from the circuit momentarily while current is increasing and thereafter gives it back while the current is decreasing.

The combined opposition offered to the flow of alternating current by the resistance and the inductance reactance of a circuit is called the *impedance* (q.v.) of that circuit. The voltage drop due to resistance is in *phase* (q.v.) with the current. The voltage drop due to *inductance reactance* is 90 degrees in advance of the current.

Expressed as a formula, $x = \sqrt{Z^2 - R^2}$, where x is the inductance reactance, Z is the impedance and R is the resistance, all measured in ohms.

Knowing the *frequency* (q.v.) of the alternating current and the inductance of the circuit through which this current flows, it is possible to calculate the *inductance reactance* by using the formula $x = 2\pi fL$, where π is a constant equal to 3.1416, f is the frequency in *cycles* per second, and L is the *inductance* of the circuit in *henry's* (q.v.). This formula is sometimes abbreviated by substituting the symbol ω (omega) for $2\pi f$. From the formula it can be seen that the *inductance reactance* increases directly both with the inductance of the circuit and with the frequency of the current flowing. (See *Current,* also *Electromotive Force, Resistance, Reactance.*)

INDUCTANCE, RECEIVING—Broadly, any form of inductance used in receiving circuits. The term thus includes all types of coils for tuning purposes, such as couplers, tuned transformers, variometers, etc. The illustration shows a common form of tuning inductance. Here the coil L is an inductance in the aerial circuit and L_1 the coil in the secondary circuit. Here the energy from the aerial traverses coil L and by induction is transferred to coil L_1. (See *Tuning Coil, Vario-Coupler, Receiving Circuit.*)



A form of tuning inductance sometimes used in radio receiving sets.

INDUCTANCE, SELF—Symbol L—An alternate term with self-induction for the *inductance* (q.v.) due to the field of force produced by the circuit itself. It is virtually the same as mutual inductance. For example, in a coil of wire being traversed by alternating currents the adjacent turns may act upon each other on the principle of mutual induction between two separate adjacent circuits. The induced currents are the result of self-induction. (See *Self-Induction,* also *Mutual Inductance* and *Induction.*)

INDUCTANCE, TAPPED—Any type of inductance having taps for connecting at different points on the coil in order to vary the inductance value. The illustration shows a form of tapped inductance. Here the taps at different portions of the coil are connected to switch points and the switch lever permits instant change to any of the available values. (See *Inductance Coils,* also *Tuning Coil.*)



A tapped inductance which permits inductance to be added or taken out of the circuit by rotating the lever switch.

INDUCTANCE, UNITS OF—The measuring units for inductance. The practical unit is the henry (H), the value of inductance which, if current varies at the rate of one ampere each second, results in an *induced electromotive force* (q.v.) of one volt. When we speak of an induced E.M.F. of one volt, the volt is used as a practical unit. Under the electromagnetic system of units, the absolute unit of induced E.M.F. is known as the abvolt. This unit is very small, 100,000,000 of them being required to equal one volt. We thus say that the volt of induced E.M.F. is equal to $1x10^8$ abvolts. The electromagnetic unit of E.M.F., or the abvolt, is defined as the E.M.F. induced in a conductor cutting one line of magnetic force each second. As we have shown that one volt is equal to $1x10^8$ abvolts of induced E.M.F., and since one ampere is equal to $1x10^{-1}$ abamps of current (see *Units, Electromagnetic*) then the unit of inductance or one henry $= \dfrac{1x10^8}{1x10^{-1}}$ or) $1x10^9$ abhenrys. The unit of inductance (the henry) being too large for practical purposes, the *milli-henry* (one-thousandth henry) or the *micro-henry* (one-millionth henry) are commonly used. Occasionally the *centimeter* is used as a measure of inductance, being the thousandth part of a micro-henry or a *milli-micro-henry*. The milli-henry is written as $1x10^{-3}$ henry, the micro-henry as $1x10^{-6}$ henry, and the centimeter as $1x10^{-9}$ henry. (See *Induced Current, Induced E.M.F., Induction, Electromagnetic,* also *Units.*)

INDUCTANCE, VARIABLE—Any coil possessing self-inductance and being arranged in such a manner that the value of the inductance can be changed at will. The simplest form of variable inductance is the sliding contact tuner. This is merely a coil of wire of any predetermined value (maximum) mounted and arranged with a sliding contact moving over the wires, which are bared of insulation at a certain point to permit contact. By using the sliding contact as one connection and either end of the coil as the other lead, the effective value of the inductance in the circuit may be varied within the limits of the coil itself. Other forms of variable inductance include the variometer, vario-coupler and various modifications. The illustration shows the two more common forms of variable inductance. (See *Inductance,* and *Inductance Coils.*)



A sliding contact tuner formerly used in radio receiving sets.



Illustration by courtesy of Radio Specialty Co.
Variable inductance known as a variocoupler.

Illustration by courtesy of Radio Specialty Co.
Another type of variocoupler.

INDUCTANCES IN PARALLEL—Coils possessing the property of self-induction or self-inductance, connected in parallel or shunt to each other. The illustration shows two standard coils connected in a circuit in this manner. The effective inductance is less than that of either coil alone. (See *Inductance Coils.*)



Diagram showing connection of two inductance coils in parallel in a circuit.

INDUCTANCES IN SERIES—Coils possessing the property of self-induction, connected in series in a circuit. The illustration shows two coils connected in series in a circuit. Here the effective inductance value is the sum of the separate inductances. (See *Inductance Coils.*)



Diagram showing two inductance coils in series in a circuit.

INDUCTION—The influence exerted by one field of force (electromagnetic or electrostatic) on another or on a conductor. Whenever a magnetic field interlinked with an electric circuit is changed, an *electromotive force* (q.v.) is induced in that circuit. The magnetic field is considered to originate from the heart of the conductor, spreading out concentrically from the conductor as the current increases and shrinking back into the center of the conductor as the current decreases. In either case, the conductor is cut by the magnetic field, and in accordance with the *law of electromagnetic induction* (q.v.) an electromotive force is induced in the circuit proportional in amount to the rate of change of the magnetic field and acting in a direction which would, by producing a current, tend to oppose the change.

A bothersome type of electromagnetic induction sometimes occurring in radio takes place when a radio aerial is run parallel to a high-tension line or even a trolley line. The varying field of force about the high-tension line sets up, by induction, a corresponding field in the parallel aerial, thus causing a disturbing hum in the loud speaker. Such a condition can usually be eliminated by running the aerial at right angles to the power line. By doing this, induction between the two conductors is reduced to a minimum.

Electrostatic induction is a rearrangement of an electrostatic field whereby a body in the neighborhood of a charged body will have an opposite charge induced on it. An *induction machine* (q.v.) known as the Wimshurst utilizes the principle of electrostatic induction.

INDUCTION BRIDGE—Also called inductance bridge. A balance arranged similarly to a *Wheatstone Bridge* (q.v.), used in induction measurement. (See *Induction, Measurement of Inductance,* also *Induction Density.*)

INDUCTION COIL—A form of transformer, having a primary winding arranged with a means of making the direct current applied to it, pulsate.



A typical form of induction coil showing diagram of connections, vibrator, core, battery, condenser and key.

Essentially a transformer with open magnetic circuit, carrying a pulsating direct current which induces a high voltage, alternating current in the secondary by means of the step-up effect of the windings. The illustration shows a typical form of induction coil and the associated circuits for producing high voltages. Here, there are two windings, a primary and a secondary, over and insulated from a core, composed of a number of soft iron wires. The primary is arranged with a key, K, and a battery, B, to supply direct current to the circuit. When the key is depressed the current flows through the primary circuit, including the contact C and the vibrator V. The core becomes *saturated* (q.v.) or magnetized and attracts the armature or spring V. As this spring is drawn toward the core it breaks the contact between the spring and the contact post. This, of course, breaks the circuit from the bat-



A form of spark coil.

tery and the flow of current stops, resulting in the collapse of the flux through the core. When the magnetic attraction ceases the spring goes back into normal position and the contact is once more complete, allowing current to flow through the windings. This make-and-break process is more or less rapid and is repeated continuously. By induction, an alternating E.M.F. (electromotive force) is created in the secondary windings, and as these windings have many more turns than the primary winding the induced E.M.F. will be proportionately greater. If the breaks occur at a rate of from thirty to one hundred per second, the key can be used to interrupt the primary current and produce at the secondary terminals a high voltage suitable for spark transmission. (See *Induction, Transformer, Spark Coil.*)

INDUCTION COIL, PRIMARY — The simplest form of induction coil. It consists of an iron core wound with a relatively large amount of low resistance copper wire, which is well insulated. The iron core increases the effect of self-induction and the size or length of the core and the number of turns of wire determine the efficiency of the coil. Such coils are used extensively for low tension ignition. (See *Induction Coil.*)

INDUCTION COIL, SECONDARY — A type of induction coil employing a primary and secondary winding. The primary is wound over an iron core and the secondary is generally wound over the primary. (See *Induction Coil.*)

INDUCTION DENSITY—A term occasionally used to refer to the density of flux in a magnetic or electromagnetic field of force. It is synonymous with flux density, under which heading it will be found more fully defined. (See *Induction, Electromagnetic,* also *Gauss,* and *Induction, Magnetic.*)

INDUCTION, ELECTROMAGNETIC — The production or *inducing* of electric currents in a conductor when it is moved in a magnetic field of force in such manner as to cut magnetic lines of force. The simplest example of this phenomena is the Faraday experiment in which he discovered that a wire with its ends joined, when moved rapidly in the field of a magnet, would result in current being induced in the wire or conductor. All dynamo electric machinery is based upon this principle of electromagnetic induction, as are also alternating current transformers and various other electrical devices.

In the illustration is shown the theory of production of current by electromagnetic induction. Fig. 1 shows a coil of wire placed in a uniform magnetic field of force between two magnets. Here the coil is assumed to have been moved from A to B in the same plane. This is known as a *motion of translation,* and the field being uniform at all points the same number of lines pass through the coil at both points. Therefore no current is induced in the coil and a sensitive instrument placed across the leads, C, C, would show no current present. In Fig. 2 the same coil is shown at A in its original position. Here, however, it is rotated, and when in position B it is apparent that less lines of force pass through it. We have thus fulfilled the conditions for inducing current, and if the instrument is placed across the leads, C, C, the presence of electric current will be indicated. If the motion of rotation is continued the number of lines of force passing through the coil will continue to increase and decrease and current will be produced in the coil as long as the motion persists. From the above it will appear that current can be induced either by rotating the coil around any axis in its plane, or by tilting it in its motion across the field. The coil of wire in this case is known as an *inductor* because the current is induced in it. It is also referred to as a *conductor* when describing the production of alternating currents.



Fig. 1. Coil of wire in a uniform field moving parallel to direction of the field.



Fig. 2. Same coil, showing cutting of field due to the rotation of the coil.

Now it was stated that current is induced in the inductor whether the lines of force through it are *increased* or *decreased* by its motion through the field. We can reduce the action to two simple rules. First, the relative motion between an inductor and a magnetic field must be such that the number of lines passing through the inductor are altered, i.e., increased or decreased. Second, the electromotive force induced in the inductor circuit will be proportional to the rate of increase or decrease in the number of magnetic lines embraced by the inductor circuit. We know from the *Lenz Law* (see *Alternating Current, Theory of Production of*) that current will flow in the inductor in a direction dependent upon whether the lines of force through it are being increased or decreased, and as the inductor is being rotated continuously the current will change direction with each change in the number of lines. (See *Alternating Current, Alternator, Electromotive Force, Fleming's Rule, Laws of Electromagnetic Induction, Lenz's Law.*)

INDUCTION, ELECTROSTATIC — The production of an electric charge in a body due to the presence of a nearby conductor having an opposite charge. The effect is known as a displacement of electric charge. (See *Electrostatic Induction,* also *Induction.*)

INDUCTION INSTRUMENTS—Measuring instruments used in electrical and radio practice, which make use of the principle of electromagnetic induction. Such instruments are used for measuring alternating currents, the torque or actuating force for the indicator being produced by the effect of a rotating field on a metal disc or drum which is not connected to the circuit carrying the currents. The instruments operate on the same basic principle as the *induction motor* (q.v.).

INDUCTION MACHINE — A machine wherein the primary and secondary windings rotate with respect to each other. Examples of induction machines are induction motors, certain types of frequency converters and induction generators. An entirely different kind of induction machine is one which generates low potentials, utilizing the principle of *electrostatic induction* (q.v.). The most common form of this type is known as the Wimshurst (q.v.).



A common type of induction machine known as the Wimshurst.

INDUCTION, MAGNETIC — The communication of magnetism to a metal by the presence of a magnet without any actual contact. The effect of the presence of a magnet in the neighborhood of a piece of magnetic material is to induce magnetic poles in it. (See *Magnetism, Magnetic Poles, Induction,* also *Induction, Electromagnetic.*)

INDUCTION MOTOR — An alternating current motor in which the input current is passed through the field coils only, the armature not being connected to the external circuit. Here the armature is rotated by currents induced by the varying field set up through the field coils. The induction motor is the most widely used of the alternating current types, maintaining a practically constant speed from no load to full load and being simple and rugged in construction. This type of motor has two windings, the primary and secondary, and two members called stator and rotor. The primary winding is usually on the stator and the secondary winding, which is therefore customarily on the rotating member, is not connected electrically to the primary. Current to operate the rotor is induced in the secondary windings by the magnetic action of the current circulating in the primary windings. (See *Alternating Current,* also *Induction, Electromagnetic.*)

INDUCTION, MUTUAL—The interference or mutual effect between two electric or magnetic fields, due entirely to their proximity and without electrical contact. The mutual induction or electromagnetic influence of one circuit upon another is measured by the coefficient of mutual inductance or induction. (See *Mutual Induction,* also *Mutual Induction Coefficient,* and *Mutual Inductance.*)

INDUCTION REACTANCE—The value in ohms of the inductance in an electrical circuit as distinguished from the capacity or capacitive reactance. It is the part of the total impedance in an alternating current circuit that is due to the presence of inductance in the circuit. (See *Inductance Reactance, Ohm, Impedance.*)

INDUCTION REGULATOR—A system of regulating the voltage in alternating current circuits, employing a choke coil with removable core, or some form of variable ratio transformer which will assist or oppose the current by readjustment of the ratio. (See *Choke Coil, Reactance,* and *Variable Ratio Transformer.*)

INDUCTION SCREEN—A metal screen or shield placed between two electrified or magnetic bodies to reduce the effect of induction between them. A common example of this in radio usage is the placing of a sheet of metal between two coils, the sheet being generally grounded, or the provision of a metal *shield* (q.v.) entirely around each coil. This reduces the interaction of the fields of the coils, which leads to losses or howling, especially in *tuned radio frequency amplifiers* (q.v.). (See *Shielding.*)

INDUCTION UNIT—The *henry,* defined as the induction in a circuit when the electromotive force induced in that circuit is one *international volt* (see *volt*) while the inducing current varies at the rate of one ampere each second. (See *Henry,* also *Self-Induction.*)

INDUCTION VOLTMETER—See *Induction Wattmeter,* also *Induction Instruments.*

INDUCTION WATTMETER—An instrument for measuring the power delivered to a circuit. The induction type wattmeter operates on a principle used in the induction motor, a magnetic body attached to a pointer being rotated by a changing magnetic field. (See *Induction Motor,* also *Wattmeter.*)

INDUCTIVE CAPACITY—Generally referred to as the specific inductive capacity in rating the dielectric qualities of a substance. It is the quality of any dielectric substance by reason of which it permits electrostatic induction through it. The term is more or less synonymous with *Dielectric Constant,* the latter, however, being generally given in terms of a numerical value representing its comparative specific inductive capacity with some material taken as a standard. (See *Dielectric Coefficient and Constant,* also *Specific Inductive Capacity.*)

INDUCTIVE CIRCUIT—An electrical circuit possessing inductance but not capacity. (See *Inductance,* also *Capacity.*)

INDUCTIVE CONNECTION—A connection between two circuits entirely through the property of induction and without any metallic contact. The two coils, primary and secondary, of a vario-coupler as used in radio receiving circuits, are said to have inductive connection where the windings are separate. Thus, the primary coil will be in one electrical circuit and the secondary coil will receive energy from it by means of induction. (See *Induction, Coupling, Vario-Coupler.*)

INDUCTIVE COUPLER—The inductances or coils placed in inductive relation or inductively connected with each other for the purpose of transferring energy by electromagnetic coupling. Any device consisting of a primary and secondary inductance and used to transfer energy from one circuit to another by means of induction. (See *Coupler, Induction, Vario-Coupler.*)

INDUCTIVE COUPLING—The coupling or connection between two circuits by means of electromagnetic induction.



The utilization of a vario-coupler to inductively couple the aerial system with the rest of a receiving circuit.

The most common example of inductive coupling is in radio receiving circuits where coupling coils are used to associate the primary or aerial circuit with the secondary circuit. In the illustration L_1 is the primary of a vario-coupler and L_2 the secondary. The primary is inserted between the ground and aerial and the secondary is connected to the grid and filament of the detector tube. The variable condenser C_1 tunes the primary circuit, the primary coil also being variable by means of taps if desired. The variable condensed C_2 tunes the secondary inductance and the condenser and grid leak GL are the customary elements in the detector grid circuit. As the high frequency currents traverse the primary circuit, passing through coil L_1, lines of force are set up as shown and some of these lines embrace the secondary coil L_2, inducing similar currents in the secondary or vacuum tube circuit. The balance of the circuit is not shown for obvious reasons. This type of coupling between circuits is much more selective than the straight coupling or conductive coupling. (See *Coupling,* also *Conductive Coupling.*)

INDUCTIVE DISTURBANCE—The disturbing effects sometimes experienced in radio broadcast or telegraph reception due to induction from nearby power or telephone lines. This sometimes occurs when an aerial is strung close to and parallel with a line carrying high voltages, and occasionally is experienced with telephone wires near the receiver. (See *Induction.*)

INDUCTIVE DROP IN VOLTAGE—The drop or diminution of voltage in an alternating current circuit due to the presence of inductance. Inductance in a circuit carrying alternating current tends by reason of the self-induction to set up a counter-electromotive force which opposes the original E.M.F. (electromotive force), thus reducing the effective voltage in the line. (See *Inductance,* also *Inductance Reactance.*)

INDUCTIVE EMF—The electromotive force due to induction. That is to say, the electromotive force induced in a circuit. (See *Induction, Induced EMF.*)

INDUCTIVE REACTANCE—The reactance or portion of the total impedance in a circuit, due to the presence of self-inductance. (See *Inductance Reactance,* also *Impedance.*)

INDUCTIVE RESISTANCE—A resistance element possessing inductance, as for example a resistance coil, which also has the property of self-inductance. (See *Resistance,* also *Inductance.*)

INDUCTIVE RISE—The rise in voltage noted in transformers or other alternating current apparatus due to the presence of a *leading current* (q.v.). (See *Inductance,* also *Transformer* and *Angle of Lead or Lag.*)

INDUCTIVITY—Another term used alternately with dielectric constant and conductive capacity, referring to the dielectric properties of materials. (See *Dielectric Coefficient or Constant,* also *Inductive Capacity.*)

INDUCTOR—The coils or conductors in which current is induced through electromagnetic induction, as in an induction motor. Any conductor in which current is induced due to a change in magnetic flux may be called an inductor. (See *Induction, Inductor Alternator,* and *Induction Motor.*)

INDUCTOR ALTERNATOR—An alternator for producing high frequency currents. It employs the *armature* and *field windings* on projections inside the *stator,* the rotor consisting of a drum carrying a magnetic material. By using a *rotor* of solid steel, very high speeds and consequently high frequency currents are obtainable. The *Alexanderson Alternator* (q.v.) is an inductor type alternator. (See *Alternator,* also *Inductor.*)

INDUCTOMETER—A device or instrument used to measure self or mutual inductance. The basic principle depends on the relation of two coils, a primary and secondary, one of which can be moved in its relation to the other, the inductance, either self or mutual, being registered on a scale calibrated in units of inductance. (See *Inductance, Mutual,* also *Inductance, Self.*)

INERTIA—In physics, the property of a body which tends to keep it in a state of rest or to resist any change of motion. (See *Inertia, Electric.*)

INERTIA, ELECTRIC—Term occasionally applied in place of *self-inductance* (q.v.). When a current flows in a circuit possessing inductance and the circuit is broken, current continues to flow for a short time. It thus appears that in this instance the resistance alone will not stop the flow of current on the instant of breaking the circuit, an interval of time being required as in the act of bringing to rest a moving material. (See *Inertia, Inductance, Self,* also *Resistance.*)

INERTIA, ELECTROMAGNETIC—The same as electric inertia, being, in effect, the energy required to start or stop a a current in a circuit possessing self-inductance. (See *Inertia.*)

INFERRED ZERO—A term used in connection with certain instruments having extremely high sensitivity, where the zero is removed from the scale. In a galvanometer, for example, the zero position on the scale may be merely assumed, an electrical or mechanical force being applied to bring the zero off the scale entirely, only a part of the full range of the full scale being utilized. (See *Galvanometer.*)

INFLUENCE—A broad term signifying action at a distance, as by electrostatic induction, without any actual physical contact. It is considered as the effect of a charged body on a neutral body or conductor coming within its field. (See *Field*, also *Induction.*)

INFRA-RED RAYS—The heat waves or rays which lie between light waves and electromagnetic (radio) waves. The infra-red lies at the extreme low frequency end of the invisible spectrum, the wave-length being extremely high and the frequency conversely low. (See *Wave*, also *Ether Waves.*)

INFRA-SATURATION PART OF CHARACTERISTIC—In a characteristic curve of a vacuum tube, this is the portion over which the tube is operable, or the operating portion of the curve. (See *Characteristic Curve*, also *Vacuum Tube, Theory of Operation.*)

INITIAL MAGNETIZATION—The initial stages of magnetization as distinguished from the effect after saturation has been approached or reached. (See *Saturation, Magnetic.*)

INPUT—Generally speaking, the energy absorbed by a machine as distinguished from the output energy. (See *Input Voltage*, etc.)

INPUT CIRCUIT OF VACUUM TUBE—Vacuum tube circuits are generally divided into three separate classes or circuits. The first is the circuit including the filament, i.e., the "A" battery circuit through the filament. The second is the circuit between filament and grid and the third is the circuit between filament and plate. The filament grid circuit is called the input circuit because the incoming oscillations are impressed on this circuit. The filament plate circuit is known as the output because the rectified or amplified currents are taken from across the plate and filament. The illustration shows both input and output circuits, the former in heavy lines and the latter in light lines. The input circuit of a tube is also known as the *grid circuit.* (See *Grid, Filament, Plate*, also *Vacuum Tube, Theory of Operation.*)



Input and output circuits of a vacuum tube receiver. Heavy lines show the former, light lines the latter.

INPUT VOLTAGE—The voltage impressed on a circuit or machine as distinguished from the output voltage. (See *Input.*)

INSTANTANEOUS CURRENT—The value of current in an alternating current circuit measured at any instant, as distinguished from the average current value. (See *Instantaneous Values.*)

INSTANTANEOUS VALUES—The actual value of an alternating current, E.M.F. (electromotive force), etc., measured at any instant. This value may be anything from zero to maximum or peak It must be remembered that in an alternating current the current and voltage are both variable factors, rising to a maximum in one direction, then falling to a minimum, and then rising to a maximum in the other direction. Thus, a wattmeter measures the actual value of current and voltage at each instant and the instantaneous torque at each instant is proportional to the instantaneous power. The average torque acting on the moving element during each cycle of the current and voltage is then proportional to the average power. If we measure an alternating current with an ammeter, and then measure the voltage with a volt-meter, the product of the two will be the apparent power, (apparent watts). It should be noted that these instruments measure effective and not instantaneous values. In order to ascertain the true *watts* (q.v.), it is necessary to multiply the apparent watts by the power factor. A wattmeter measures true watts. (See *Effective Electromotive Force, Power Factor*, also *Wattmeter.*)

INSTANTANEOUS VOLTAGE OR PRESSURE—The voltage or pressure in an alternating current circuit measured at any instant, as distinguished from the average value of E.M.F. (electromotive force). (See *Instantaneous Values.*)

INSTRUMENTS, MEASURING—In electricity or radio, any device or instrument for recording or indicating values, such as an ammeter for indicating the current in amperes, or a voltmeter to indicate the electromotive force in volts. (See *Ammeter* or *Ampere Meter, Voltmeter, Wattmeter.*)

INSTRUMENT SHUNTS—In electrical measuring instruments, a branch conductor, generally of relatively heavy wire or metal strip, joining the meter circuit at two points and forming a parallel circuit, thus dividing the current and protecting the delicate windings of the instrument. (See *Shunt*, also *Ammeter*, or *Ampere Meter, Hot Wire Ammeter.*)

INSULATE—To provide a protective covering or shield for a part or conductor, preventing flow of electricity from it or the passage of electricity through it. A conductor of electric currents is generally insulated to prevent the flow of the electricity through contact with other parts or conductors except where contact is intended to be made. (See *Insulated Wire.*)

INSULATED WIRE—Wire, generally copper, covered with insulating material to prevent leakage of the electric current. Standard insulated wire of the heavier gauges is usually covered with a layer of rubber and an outer covering of braided cotton. (See *Lead-In*, also *Insulation.*)

INSULATING COMPOUND—Liquid or easily liquifiable mixture of some insulating material, used in radio to coat cardboard tubes and to cover any open point of contact in an otherwise insulated conductor or part. Coils are very often coated with shellac or some other liquid and quick-drying substance. This serves to hold the windings in place and also acts as a protective covering. A very valuable application of an insulating liquid is shown in the illustration. Here an inductance is wound on a form of stiff paper or cardboard tube and after being completed is coated with one or two treatments of collodion or similar liquid. (Shellac introduces losses through the medium of *distributed capacity.*) The form is then cut away and the coil remains self-supporting as shown. This method produces a coil having the least possible dielectric and distributed capacity loss for a cylindrical shape. (See *Dielectric, Inductance Coil, Low Loss Coils, Collodion.*)



Air core coil made rigid by use of insulating compound.

INSULATING MATERIALS—Non-conducting substances, for example, glass, hard rubber or porcelain, which do not conduct electric currents. Strictly speaking, there are no perfect insulating materials. The most perfect insulators are certain gases, although at low pressure these may act as very good conductors. The more common insulating materials in radio are the following: mica, glass, bakelite and hard rubber, the insulating values being in that order. When we speak of the insulating property of a material we are actually referring to its resistance, a good insulator offering infinite resistance to the passage of electric currents and poor ones being relatively good conductors. The term *specific resistance* is used extensively in connection with the insulating properties of materials. This term is defined as the resistance of a piece of material of unit length and unit cross-sectional area at a given temperature, the value being given in ohms. (See *Dielectric Coefficient and Constant, Table of*, also *Ohms, Resistance* and *Insulate.*)

INSULATING PROPERTY—The ability of any material to *insulate* electric currents. Accepting mica as an insulator, we say that its insulating properties are superior to glass or hard rubber. (See *Insulating Materials*, also *Dielectric Coefficient and Constant* and *Insulation of Aerial.*)

INSULATION—Broadly any material or gas used to insulate electric currents. In radio, insulation plays a most important part, providing protective coverings or separators between conductors of the electric current and between the conductors and the ground. Insulation is really a material or gas having extremely high specific resistance; the better the insulating property, the higher the resistance to passage of electricity. There is no clearly defined line of demarcation between an insulator and a conductor, a poor insulator being to some extent a conductor. (See *Bakelite, Conductor, Dielectric Coefficient and Constant, Insulations of Aerial, Panel.*)

INSULATION OF AERIAL—The means used in connection with an aerial for reception or transmission of radio waves, to prevent leakage or ground-

Aerial Insulator.

ing of the currents. The insulation of an aerial for reception purposes should be given very careful consideration. The wires may be suspended by means of small glass or porcelain insulators and the lead-in rubber covered wire, entering the building through a *lead-in insulator* (q.v.). The aerial for transmission must be accorded specially careful attention as far as insulation is concerned. The bare wires must be suspended with heavy duty insulators, capable of withstanding high voltages without *"breaking down."* The lead wire must be conducted into the building through a high-tension insulating tube or other lead-in device to prevent leakage of the current to the ground. (See *Aerial, Insulation of Aerial* and *High Tension Insulators,* also *Lead-In Insulator.*)

INSULATION RESISTANCE—The actual resistance in ohms, generally megohms, of the insulation of any conductor or piece of apparatus. If we assume two conductors, carrying separate currents and crossed so that the only protection would be the actual insulation of the wires, the insulation resistance would be the actual resistance in megohms from one path to the other. Conceivably a small current might leak from one conductor to the other, this current, of course, depending on the resistance of the insulation. The term "insulation resistance" is more easily understood when it is considered that an insulator or insulating material is merely a very poor conductor, or one having extremely high resistance to electric currents, there being actually no perfect insulator. (See *Insulation, Insulated Wire,* also *Conductor* and *Resistance.*)

INSULATION TESTER—An instrument or set of meters for testing the resistance of an insulator in fractional ohms, generally megohms. (See *Insulation Resistance.*)

INSULATOR — Any substance having insulating properties. *Insulators* are used to keep electric currents flowing in predetermined paths. It is necessary to use insulators on all electric circuits in order to prevent *grounds, leakage* and *short circuits.* Insulators are of the utmost importance in radio. At the transmitting end, where high voltages as well as high frequencies are used, the insulators must be specially designed to prevent leakage. A typical installation of insulators in use on the aerial system of a modern broadcasting station utilizes a 12-inch pyrex insulator at each end of each wire between the spreaders. A standard porcelain strain insulator is used every 14 feet on each guy wire. At each end of each guy wire a standard 24-inch porcelain insulator is used.



Illustration by courtesy of Corning Glass Works.

A typical small antenna insulator, showing corrugated surface.



A corrugated ball insulator.

Insulators used on receiving antennas are made of porcelain, pyrex, rubber and composition. These are usually about 4 inches in length. Sometimes porcelain tubes are used as insulators to bring a *lead-in* (q.v.) into a building, but these have been generally superseded by flat *window lead-ins.*

INSULATOR, LEAD IN—The insulating tube through which a lead wire from a radio aerial enters a building, used to prevent grounding or leakage of the current by contact with another conducting surface. (See *Lead-In Insulator.*)

A flat window lead-in which permits entrance of lead-in into building without the necessity of boring holes.



Lead-in insulators of conventional type.

INTEGRATING DETECTOR—The name sometimes given to any detector which yields a response proportional to the total energy received from a spark train rather than to the maximum value of the current or voltage in the train.

INTEGRATING INSTRUMENTS — Meters so designed as to record the total quantity of electricity (ampere hours) or the total energy (watt-hours) passing in a circuit in a given time. (See *Ammeter* or *Ampere Meter,* also *Integrating Wattmeter.*)

INTEGRATING WATTMETER—An instrument which measures and records the total amount of electrical energy being consumed in a circuit. These instruments are also known as *recording watthour meters* (q.v.), *integrating watthour meters,* and sometimes are simply referred to as *watthour meters* (q.v.).

Broadly speaking the *integrating wattmeter* is a type of small motor whose rotations are counted by means of a worm on the armature shaft engaging a set of cogs working a counter. The construction is such that the average *torque* (q.v.) exerted by the motor is proportional to the average power taken by the load. In other words, the motor rotates at a speed directly proportional to the energy being expended. For direct current work, *integrating wattmeters* are either of the commutator type, such as the Thompson, Westinghouse and Duncan meters or of the no-commutator type, such as the Sangamo. The commutator type instruments operate on the *dynamometer* (qv.) principle. Meters of the no-commutator type are essentially motors whose armatures always cut the same direction flux. That is to say, they are essentially *homopolar* (q.v.) motors. The principle of operation of these meters is the law of motor action which states that a conductor, free to move and carrying a current whose direction of flow is at right angles to a fixed magnetic field, will be moved out of this field, and in a direction at right angles both to the direction of current flow and to the field. For alternating current work, *integrating wattmeters* are of the *induction* (q.v.) type. The principle of operation of these meters is identical to that of *induction motors* (q.v) having shunt and series windings stationary and so related and located as to produce a rotating field acting upon a closed rotable secondary. In the induction meter the secondary consists of a light aluminum disc. These meters may be either of *single phase* (q.v.) or *polyphase* (q.v.) construction. (See *Electro-dynamometer.*)

INTEGRATOR—A device which automatically, by means of clockwork, adds up and records on a dial items of calculation or measurement. The system used in a recording or integrating wattmeter. (See *Integrating Wattmeter.*)

INTENSIFICATION — Broadly an intensifying or increasing of the density of electric current, but specifically in radio it refers to the tendency of radio signals to increase in intensity under certain conditions. The phenomena of intensification is naturally closely related to fading, as obviously the intensification process must necessarily follow or be followed by a fading process. The tendency toward intensification is more pronounced toward night and generally on the shorter wavelengths, it being noted that quite often signals from a distant station will be increased in volume or intensity as much as fifty per cent or more between the late afternoon and late evening. While the periodic *fading* of signals and the subsequent increase in volume over regular periods, usually of a few minutes' duration, may be considered as *fading* and *intensification,* it is preferable to think of fading as one operation together with the subsequent increase in volume, and the term *intensification* as referring strictly to the change to greater volume that takes place toward night. (See *Fading,* also *Phenomena of Electric Wave Propagation.*)

INTENSITY OF ELECTRIC CURRENT—A term more or less in use to imply the strength of an electric current in amperes, the symbol I for current being derived from it. (See *Ampere, Current Density,* also *Intensity of Field.*)

INTENSITY OF FIELD—The intensity or strength of the force exerted in a magnetic field. It is measured by its action or effect on a unit pole placed at any point in the field, the intensity of the field, of course, varying at different points. (See *Flux Density, Intensity of Magnetic Flux.*)

INTENSITY OF MAGNETIC FLUX—The strength of the force exerted in a magnetic field. (See *Intensity of Field,* also *Flux Density.*)

INTENSITY OF MAGNETIZATION—The density of force per unit cross-sectional area of a magnetized material. The extent of the magnetizing effect on a material placed in a magnetic field of force. This applies only to material in a magnetic circuit and should not be confused with the lines of force due to a field arising from the presence of neighboring currents or magnets. (See *Magnetization,* also *Intensity of Magnetic Flux.*)

INTERFERENCE—The interruption or interference with desired electromagnetic waves by undesired or extraneous waves. The interference of undesired broadcast or radio-telegraph signals with the desired signals. Also, broadly, the detrimental effect of power lines and other electric circuits on radio communication. Interference is encountered chiefly in receiving sets having poor *selectivity* (q.v.). In some instances interference may be due to the fact that another transmitter is operating on the desired wave-length, and being sufficiently close as to make it practically impossible to obtain clear signals from the desired station. Ordinarily, and where the effect is due to lack of sharp resonance or tuning, certain changes can be made in the receiver to sharpen the tuning, or if the disturbance is due to the transmitting stations and the receiver is normally sharp, various circuits can be employed to filter out the undesired signals. (See *Interference Preventer*, also *Wave Trap.*)

INTERFERENCE ELIMINATOR—A device or system as shown in the illustration for reducing or preventing reception of undesired signals in radio work. Practically all *interference eliminators* make use of a separately tuned inductance across the aerial and ground and in parallel with the receiving set. The inductance is usually tuned by means of a variable condenser which allows it to be tuned to the wave-length of the interfering signal. The interference can thus be by-passed to the ground. *Interference eliminators* of the kind described are generally known as *wave traps* (q.v.). A special form of interference due to atmospheric and electrical disturbances is known as *static* (q.v.). (See *Static Eliminator.*)



A wave trap or interference eliminator which dispenses with the ground connection.

INTERFERENCE PREVENTERS—Any arrangements either within the receiving set, or external to the set, for limiting or preventing interference. In addition to *interference eliminators* (q.v.) and static *eliminators* (q.v.) various other methods are utilized in radio to prevent interference. Thus the arrangement of a receiving set to give sharp tuning and great selectivity, results in the prevention of much interference. A method of preventing interference which has been used, is the utilization of filter circuits which can be tuned to pass any desired frequency and exclude all others. The use of the *loop aerial* (q.v.) results in great selectivity. The loop has a very pronounced directional effect and this in itself acts to narrow the field of stations offering possible interference. For example, if stations of very nearly the same wave length are in opposite or different directions and are sending at the same time, the loop permits selection of the station wanted, with no interference from the others.

INTERMEDIATE CIRCUIT—A closed circuit consisting of two inductance coils shunted by a variable condenser. One coil acts as primary to the secondary coil of the detector circuit and the other coil acts as secondary to the primary of the aerial circuit. A circuit such as this is sometimes referred to as a *multiple tuner intermediate* circuit and may be used as an interference eliminator.



A multiple tuner intermediate circuit.

INTERMEDIATE FREQUENCY—This is a frequency higher in number of oscillations than *audio frequency* (q.v.) but lower than *radio frequency* (q.v.). It is generally around 30,000 cycles or 10,000 meters wave-length. In the *super-heterodyne* (q.v.) the incoming signal is converted from the broadcast frequency to the so-called *intermediate frequency* at which it can be amplified by means of fixed winding transformers to almost any extent desired. The method of converting the incoming signal in a *super-heterodyne* from radio frequency to *intermediate frequency* is by the *beat* method. In this case an oscillating circuit controlled by means of a variable condenser so as to obtain any desired frequency, is brought into interference with the first detector and produces a *beat note* (q.v.) for the *intermediate frequency* which has all the characteristics of the original signal. In this way, no matter what the frequency of the intercepted signal may be, the intermediate frequency amplification is always carried on at a fixed wave-length, thus making for high efficiency. (See *Beat Frequency; Beats.*)

INTERMEMEDIATE FREQUENCY AMPLIFIER—An arrangement of tubes and transformers for stepping up the current, used in the *super-heterodyne* (q.v.) circuit. The intermediate frequency amplifier is located between the first detector and the second detector. (See *Intermediate Frequency.*)

INTERMEDIATE TRANSFORMER—The name given to the transformers used in the *intermediate frequency amplifier* (q.v.) of the *super-heterodyne* circuit. *Intermediate transformers* are often referred to as *intermediate frequency transformers.* They are *radio frequency transformers* (q.v.) but have an iron core and instead of tuning to a maximum of 550 or 600 meters they are designed to cover wave-lengths of 10,000 meters or higher. (See *Intermediate Frequency.*)

INTERMITTENT CURRENT—A current which flows irregularly or which is interrupted at intervals, or without continuity. The current obtained from a *magneto generator* (q.v.) is an interrupted or *intermittent current.* Such a current may be either alternating or direct. A magneto generator constructed to give direct current is equipped with a two segment commutator having a stationary brush in contact with it. (See *Pulsating Current.*)

INTERNAL RESISTANCE—Resistance within an electric source. In the case of a primary cell such as a dry battery, the internal resistance causes an interference with the flow of current. This varies in amount with the construction and materials of the battery.

INTERNATIONAL MORSE CODE—This is also known as the *Continental code.* (See *Code.*)

INTERPOLE—A small magnetic pole placed between the main field poles of an electric generator for the purpose of obtaining better commutation. Interpole windings are connected in series with the armature winding and the load. The action of the interpole is exactly analogous to the shifting of the brushes, but when interpoles are used, brush shifting is dispensed with and the magnetic flux is shifted instead.

INTERRUPTED CONTINUOUS WAVES—abbreviation I.C.W.—These waves are obtained by the modulation at audio frequency, during signalling, of an otherwise *continuous wave* (q.v.). (See *Continuous Waves Key Modulated,* also *Continuous Waves Modulated at Audio Frequency.*)

INTERRUPTED WAVES—abbreviation I.W.—Interrupted waves are waves produced by modulation at audio frequency, of otherwise continuous waves. (See *Interrupted Continuous Waves.*)

INTERRUPTER—A combination of an electro-magnet with a vibrating armature which carries a contact point on a piece of spring steel fastened to the armature. When the electro-magnet attracts the armature the contact points are drawn apart thus interrupting the circuit. This action is only momentary for the spring again brings the circuit back to its original condition. The most important use of the interrupter in radio is as a *rectifying valve* (q.v.) in mechanical chargers. A typical vibrator panel is shown in the illustration. The armature, A, is the moving element. This carries at its outermost end a heavy Tungsten contact, B, which is caused to vibrate in synchronism with the supply current, by the actuating coil, C. When the current from the transformer is of the correct polarity and value the actuating coil attracts the armature, closing the charging circuit to the battery through the fixed contact, D. The contact end of the armature, A, vibrates within the air gap of the pole shoe, G.



The vibrator panel of an efficient type of mechanical charger.

A common use of the *interrupter* is in the ordinary electric bell. In this apparatus, the electromagnet pulls the armature carrying the spring and contact point, breaking contact and opening the circuit. This immediately de-energizes the magnet since its coils are in series with the circuit. The spring tension pulls the armature back to its original position thus again closing the contact. As soon as the contact is closed, the electromagnet is again energized and it again attracts the armature, opening the circuit. This action keeps on indefinitely as long as a difference of potential is maintained at the terminals of the bell.

The *interrupter* is used in the *induction coil* (q.v.) for breaking up the direct current into a series of impulses, thus producing an intermittent current. (See *Circuit Breaker.*)

INTERRUPTER, ELECTROLYTIC—A jar containing diluted sulphuric acid as the electrolyte, a large sheet of lead as one electrode and a platinum needle point introduced through a glass tube as the other electrode. If these electrodes are connected through an inductance to a source of current supply, the current in the circuit will be rapidly interrupted. *Electrolytic interrupters* are suitable for radio transmitters using small spark coils and are also used in X-ray work. (See *Electrolytic Interrupter.*)



A simple type of Wehnelt interrupter. The positive pole of the direct current supply is connected to the brass part C, while the negative pole is attached to the lead rod. L is a fibre handle; E is a threaded rod, which is constructed to fit the threaded handle, but slotted so as to engage the pin F and prevent it from turning; H is a copper or platinum rod; D is a brass tube; M. is the overflow hole in the fibre tube, into the lower end of which a portion of an old spark plug porcelain part has been driven; finally C is a small brass block as shown. This is the adjustable type of Wehnelt interrupter, since the fibre handle can be operated to allow more or less surface to be exposed to the acidulated water.

INVERTED "L" AERIAL—A flat top aerial (antenna) in which the down lead is tapped off one end of its horizontal span. (See *Length of Aerials, Horizontal Aerial.*)

INVERSE DUPLEX CIRCUIT—A circuit in which the vacuum tubes are utilized both for radio frequency and for audio frequency amplification as in the *reflex* (q.v.) circuit with this important differentiation that the first radio frequency tube is utilized as the second audio frequency tube and the second radio frequency tube is used as the first audio frequency tube. In the ordinary reflex circuit the first radio frequency tube is also the first audio tube and the second radio frequency tube is the second audio tube. The *inverse duplex* circuit has the advantage over the reflex in that the tubes which are reflexed operate more efficiently since the relatively weak radio currents pass through the same tube as the stronger audio currents and vice-versa. The *inverse duplex circuit* is the invention of David Grimes.


1ST. STAGE R.F. AMPLIFICATION
2ND. STAGE R.F. AMPLIFICATION
DETECTOR
1ST STAGE AUDIO AMPLIFICATION
2ND. STAGE AUDIO AMPLIFICATION

Diagram showing the current path and reflexing in an ordinary reflex circuit.


1ST. STAGE R.F AMPLIFICATION
2ND. STAGE R.F. AMPLIFICATION
DETECTOR
2ND. STAGE AUDIO AMPLIFICATION
1ST. STAGE AUDIO AMPLIFICATION

Diagram showing method of reflexing in an inverse duplex circuit.

ION—An atom of matter carrying an *electron* or an *atom* deprived of electrons. *Monad-ion* refers to a unit charge, *dyad-ion, divalent* carries two units, the *triad-ion* carries three unit charges. The positive *ion* is an *atom* minus an *electron.* A negative *ion* is an *atom* plus an *electron.* (See *Anion,* also *Cathion, Electron, Electron Theory.*)

IONIZATION—sometimes spelled **IONISATION**—The splitting up of *molecules* into *ions* (q.v.). *Ionization* may apply either to a chemical compound or to a gas. When a electric current is passed through an *electrolyte* (q.v.) the constituents of the electrolyte which are liberated or deposited at the *electrodes* (q.v.) are called *ions* and this process is called *ionization.* Gases at or near atmospheric pressure are normally good insulators. They are said to undergo *ionization* when they are made conductive, that is when they allow the flow of electricity. A gas may be made conductive by passing *X-rays* (q.v.) through it, by the action of ultra-violet light, by subjecting it to radium rays, by passing it close to a flame or hot piece of metal or by forming in it a brush discharge or *corona* (q.v.). Gases which have been made conductive carry current because of their dissociation into *ions,* which carry positive or negative charges of electricity. (See *Electrolysis, Electrolytic Action,* also *Valve Detectors.*)

I.R. DROP.—The voltage drop due to the resistance in a current-carrying conductor. It is directly proportional to the current flowing in the circuit multiplied by the resistance of that circuit.

I²R LOSS—The power loss in any circuit due to the resistance offered to current flow. It is proportional to the square of the current flowing in the circuit multiplied by the resistance of the circuit. Whenever current flows there is an I^2R loss. This is measured in *watts* (q.v.) or *kilowatts* (q.v.).

IRON PYRITES—Formula FeS_2—This is a mineral, a disulphide of iron, found in large quantities. It was formerly used in radio as a crystal detector mineral but has been almost entirely superseded by vacuum tube detectors. *Iron pyrites* is flaked with shiny spots which have the appearance of gold, and for this reason it is sometimes called "fools gold." *Iron pyrites* is very hard and brittle. The present commercial use of *iron pyrites* is in the production of sulphuric acid. Ferrous Sulphide, FeS, has also been employed in the past as a radio detector. This substance is chemically formed by fusing equivalent quantities of sulphur and iron together. The resultant substance has a smooth surface. (See *Crystal Detector.*)

ISOCHRONOUS—A term applied to two or more oscillatory circuits, meaning that they have the same *natural frequency* (q.v.). Stated in another way, two or more radio frequency circuits are isochronous when they are in electrical *resonance* (q.v.). Circuits are said to be in resonance when they have the same *oscillation constant* (q.v.). The *oscillation constant* of a circuit is equal to the square root of the product of the inductance multiplied by the capacity of that circuit. Circuits having equal oscillation constants will have the same discharge frequency.

ISODYNAMIC LINES—Lines on a magnetic map connecting all parts of the earth where the magnetic intensity is the same. In other words, these lines pass through points of equal horizontal component of the earths magnetic field.

ISOGONIC LINES—Lines on a magnetic map passing through points of equal *declination.* Lines connecting all points of equal variation of the magnetic meridian from the geographic meridian.

ISOTHERMS—Lines on a meteorological chart joining all points having the same temperature.

ISOTROPIC CONDUCTIVITY—Equal conductivity in every direction. A conductor is said to be *isotropic* when it offers the same resistance to the flow of an electric current in every direction through its mass.

J

JACK—An arrangement of spring terminals as shown in the illustrations which can be connected together or separated thus closing or opening circuits through the insertion of a *plug* which also forms a part of the circuit. The *plug* (q.v.) has a tip and a sleeve at one end (that is at the end inserted into the jack) and at the other end it has the two terminals for connecting the apparatus to be cut into the circuit. As an example, the terminals of the plug may be connected to a *loud speaker* (q.v.). The jack in this case is of the *open circuit* variety. That is to say, the springs of the jack are separated when not in use and the circuit is normally open. When the plug is inserted, the tip of the plug makes contact with one spring and the sleeve makes contact with the other thus closing the circuit through the *loud speaker*. In cases where the plug is used to open a circuit, that is to make the *jack* springs break contact with each other, the *jack* is called a *closed circuit jack* since its spring terminals are normally making contact. In cases where the jack is used not only to put the loud speaker in the circuit, but also to act as a filament switch, it is known as an *automatic filament control jack.* Jacks which are used to control a single circuit only, are referred to as *single circuit jacks.* Those controlling two or more circuits simultaneously are known as *multiple circuit jacks. Jacks* are usually mounted on a panel so that the plug can be inserted from the outside of the panel while the spring terminals are concealed behind the panel.



Illustration by courtesy of Radio Specialty Co.

Illustration at left shows one-spring open circuit jack. At the right is a three-spring jack.



Illustration by courtesy of Radio Specialty Co.

The jack shown at the left is a four-spring double circuit jack. At the right is a five-spring automatic jack.

JAMMING—An expression denoting interference at a receiving station caused by a transmitting station not desired to be heard. More specifically, such interference, prevents the reception of signals, *jamming* the receiving station by drowning out with stronger signals or noises the station desired.

JANET, PAUL—Born in Paris, January 10, 1863. Educated at Lycee Louis-le-Grand and at the high school. He was Professor of Physics at the University of Paris and University of Grenoble. Professor Janet was the author of several important works, and first to make the experiments in electrical resonance successful. The results of these experiments are applied in present day wave meters.

JAR—A unit of electrostatic capacity. It is mainly used in the British Naval service. One *jar* equals 1000 *centimeters* which equals .0011 *microfarads* (q.v.).

JIGGER—A term generally accepted to denote an *oscillation transformer* (q.v.). Used for transforming trains of oscillations from one circuit to another. Dr. J. Erskine Murray refers to high frequency oscillations as *Jigs. Jiggers* are also known as *magnetic coupling transformers* (q.v.). They are also sometimes referred to as *auto-jiggers.*

JOULE—symbol J—The practical unit of electrical energy. It is equal to 10^7 *ergs* (q.v.). The *joule* is also the unit of electrical work. It is equal to the work done or the heat generated by a *watt second* (q.v.); or an *ampere* (q.v.) flowing for a second through a resistance of one *ohm* (q.v.). Expressed another way the *joule* is the work done by one *coulomb* (q.v.) flowing under the pressure of one *volt* (q.v.). One *joule* is equal to .73732 foot pounds, or .24 calories (q.v.).

JOULE EFFECT, or JOULEAN HEATTING—This occurs when an electric current traverses a resisting conductor. The rate of generation of heat in the conductor by a steady current equals the square of the current multiplied by the resistance.

JOULES EQUIVALENT—The amount of energy equal to a heat unit.

JOULES LAW—The heat produced in an electric circuit is directly proportional to the square of the current, to the resistance of the conductor and to the time of current flow.

K

KANALSTRAHLEN—A German word meaning Rays of Canal. It has been found that by perforating the cathode of a tube producing *cathode rays* (q.v.), faint luminous streaks will come through these perforations in a direction opposite to that of the *cathode* rays. These are called *kanalstrahlen.* They communicate a positive charge to an insulated conductor. In terms of the *electron theory* (q.v.) they are positively charged *ions* (q.v.) The cathode particle is an electron traveling in one direction, and the kanalstrahlen particle traveling in the opposite direction is what remains of the atom which has lost an electron.

KATHODE—This is a negative *electrode* (q.v.). (See *Cathode,* also *Electrolysis.*)

KATHODE OF CELL—The positive pole of a cell. This is indicated by the plus (+) sign. (See *cell.*)

KATHODE RAYS—The stream of *electrons* (q.v.) thrown off by the *kathode* of a vacuum tube. These produce a glow when they strike the walls forming the tube. They can be deflected by a magnet. (See *Cathode Rays.*)

KATION—The charged particles or *ions* (q.v.) moving in the direction of the *cathode* (q.v.). (See *Cathion.*)

KEEPER—The piece of iron used to close a magnetic circuit to protect it from external disturbances. The term *keeper* is generally used to refer to such a piece of iron when used with a permanent magnet such as a horseshoe magnet. In the case of the piece of iron which closes the magnetic circuit of an electromagnet, this is more often referred to as an *armature* (q.v.). The *keeper* may be used with a straight bar magnet also. In this case, two bar magnets are laid side by side with unlike poles adjacent and two keepers are used, one at each end. The use of a keeper avoids the demagnetizing effect of *leakage lines* (q.v.). (See *Horseshoe Magnet.*)



At left is shown keeper used with a horseshoe magnet. At right two keepers are shown used with two bar magnets.

KELVIN, LORD (William Thomson) was born at Belfast in 1824; he entered Glasgow University as a student at 10 years of age; graduated at Cambridge in 1845. When only 22 years of age he was called to occupy the chair of natural philosophy in the University of Glasgow, a chair which he adorned by his genius for fifty years. He was for 40 years or more regarded as the acknowledged leader of British science on its physical and mathematical side. His great inventions in telegraphy, his magnetic compass and sea sounding apparatus brought him fame and fortune. He was knighted in 1866; and in 1892 was raised to the peerage as Baron Kelvin of Largs; he died on December 17, 1907.



Lord Kelvin (William Thomson)

KELVIN'S BRIDGE—A method of measuring low resistance in which the voltage drops, produced by the same current in the resistance under test and in a standard low resistance slide wire are balanced against each other. This *bridge* is a modification of the *Wheatstone Bridge* (q.v.) and was designed by Lord Kelvin to eliminate the errors introduced when measuring resistances much less than one *ohm* (q.v.). In the case of the *Wheatstone Bridge,* such resistances could not be measured accurately on account of the errors produced by the terminal and contact resistances.

KELVIN'S ELECTROSTATIC VOLTMETER—A voltmeter used for measuring high, and in some cases low, alternating current voltages. It is constructed on the principle of an air condenser. One type of electrostatic voltmeter is a high potential instrument having the needle made of a thin aluminum plate suspended vertically on delicate knife edges, with a pointer extending from the upper part to a scale. Two quadrant plates, metallically connected together, are placed on either side of the needle and parallel to its face. These serve as one terminal of the circuit to be measured. The needle acts as the opposite terminal. When there is a difference of potential between the needle and the plates, the needle is deflected out of its neutral position. The value of the scale indications can be changed by hanging calibrated weights on the bottom of the needle.

KENOTRON—A type of *vacuum tube rectifier* (q.v.) in which the vacuum is extremely high and the discharge is carried almost entirely by electrons, not by gas ions. In these tubes, the plate current is always less than that actually emitted by the hot filament. *Kenotrons* are made sufficiently large to rectify several kilowatts.



Illustration by courtesy of Radio Corp. of America
A kenotron tube.



Illustration by courtesy of Radio Corporation of America.
Stages in the construction of a kenotron.

KENNELLY, A. E.—Anglo-American radio expert. Born at Colaba, Bombay, December 17, 1861, he was educated in England, Belgium, France and Italy. In 1875 he became a telegraph operator in the employ of the Eastern Telegraph Company, and in 1886 became the principal electrical assistant to Thomas Alva Edison in the laboratories at Orange, N. J., a post he held until 1892.

He was engineer-in-chief with E. J. Houston, of the Thomson-Houston Company, for the laying of the cables from Vera Cruz to Campeche, 1902. Since 1902 he has been Professor of Electrical Engineering at Harvard University, and since 1914 professor of the same subject at Massachusetts Institute of Technology.

Kennelly has written a large number of books on electricity and radio, and is the author of one of the standard elementary text-books on same. He has written a very large number of papers on radio, and he is an authority on alternating currents.

He is past president of the American Institute of Electrical Engineers, was president in 1916 of the Institute of Radio Engineers, and vice-president of the International Electrical Congresses, held in Paris and Turin. He is a member of many scientific societies, and has received many honorary degrees. In 1921 he was appointed a delegate to the Interallied Radio Technical Committee in Paris.

KEY—A form of switch for conveniently and quickly opening and closing a transmitting circuit, in the act of transmitting signals. An *operating,* or *telegraph,* so-called *Morse key* is a form of *tapping key* designed especially for the rapid sending of signals by the dot and dash code. A tapping key has one contact carried by a springy strip of metal. In signalling, this key is depressed by the fingers, thus closing the circuit by bringing the contact together with a fixed contact. A standard type of *transmitting key* (q.v.) such as used in sending wireless messages is shown in the illustration. These keys must necessarily be made with larger contacts and of more solid construction than those used to interrupt the smaller currents used in wire telegraphy.

A standard transmitting key.

KEY, ANTI-CAPACITY—This is in reality a form of switch. (See *Switch.*)

KEY, HIGH-SPEED—A transmitting key usually operated from side to side instead of downwards, which makes



High speed key.

contact both on the right and on the left side. Such a key requires only half the travel of the ordinary transmitting key and thus facilitates high-speed manual transmission of code signals.

KEY SWITCH—A type of switch adapted for operation by a removable portion in the form of a handle or key. In radio work, *key switches* are sometimes used to lock a receiving set so that it cannot be operated unless the filament circuit is closed by the insertion and turning of the key. Key switches are generally operated by a hollow slotted key, although there are other types on the market. The slot in the key fits a projection or pin on the spindle or shaft of the switch which carries the movable contact. When the key is inserted in the socket and turned, it turns the shaft and brings the movable contact against a fixed contact. *Key switches* are also used for turning on or off electric lights and for locking or unlocking the ignition systems of automobiles.

KILO—Symbol K—A prefix placed before the name of a unit to indicate the multiple 1000 or 10^3. In cases where standard units are too small for convenient use, it is customary to utilize this prefix as, for example, in stating the voltage of a high tension transmission line. This would often be given as 10 kilovolts (K.V.) rather than as 10,000 volts. In like manner, in referring to large amounts of power, it would be preferable to give the amounts in kilowatts rather than in watts. Thus the better way to express 10,000,000 watts would be to divide by 1,000, thus converting to 10,000 kilowatts.

KILOAMPERE-TURN—One kiloampere-turn is equivalent to 1,000 ampere-turns. In referring to the magnetic circuits of electrical machinery it is usual to specify the magnetomotive-forces in kiloampere-turns rather than in ampere-turns. (See *ampere-turns*, also *magnetomotive-force.*)

KILOCYCLE—1,000 *cycles*—Two immediately succeeding half waves of an alternating current constitute a *cycle* (q.v.). The number of *cycles* per second is called the *frequency* (q.v.). In house-lighting and similar circuits, where a comparatively low frequency is used, it is usual to refer to the *frequency* in cycles per second. However, in radio circuits, where currents as high as 300,000,000 cycles per second are used, it is preferable to divide by 1,000, thus converting to *kilocycles.* If the wave-length in meters is known, it is a simple matter to determine the frequency in *kilocycles.* This is calculated as follows: The speed of light is 186,000 miles per second and experiments have shown that this is practically the same as the velocity of electromagnetic or radio waves. Expressed in meters this is equal to 300,000,000 (appx.) meters per second. Assuming that a transmitting station is using a wave-length of 500 meters, the frequency will be obtained in cycles per second by dividing the velocity of the waves by the

KILOCYCLES TO METERS, OR METERS TO KILOCYCLES

Meters	Kilocycles	Meters	Kilocycles	Meters	Kilocycles	Meters	Kilocycles	Meters	Kilocycles	Meters	Kilocycles	Meters	Kilocycles
10	29980	720	416.4	1430	209.7	2140	140.1	2850	105.2	4120	72.77	6400	46.85
20	14990	730	410.7	1440	208.2	2150	139.5	2860	104.8	4140	72.42	6450	46.48
30	9994	740	405.2	1450	206.8	2160	138.8	2870	104.5	4160	72.07	6500	46.13
40	7496	750	399.8	1460	205.4	2170	138.1	2880	104.1	4180	71.73	6550	45.77
50	5996	760	394.5	1470	204.0	2180	137.5	2890	103.7	4200	71.39	6600	45.43
60	4997	770	389.4	1480	202.6	2190	136.9	2900	103.4	4220	71.05	6650	45.09
70	4283	780	384.4	1490	201.2	2200	136.3	2910	103.0	4240	70.71	6700	44.75
80	3748	790	379.5	1500	199.9	2210	135.7	2920	102.7	4260	70.38	6750	44.42
90	3331	800	374.8	1510	198.6	2220	135.1	2930	102.3	4280	70.05	6800	55.09
100	2998	810	370.2	1520	197.2	2230	134.4	2940	102.0	4300	69.73	6850	43.77
110	2726	820	365.6	1530	196.0	2240	133.8	2950	101.6	4320	69.40	6900	43.45
120	2499	830	361.2	1540	194.7	2250	133.3	2960	101.3	4340	69.08	6950	43.14
130	2306	840	356.9	1550	193.4	2260	132.7	2970	100.9	4360	68.77	7000	42.83
140	2142	850	362.7	1560	192.2	2270	132.1	2980	100.6	4380	68.45	7050	42.53
150	1999	860	348.6	1570	191.0	2280	131.5	2990	100.3	4400	68.14	7100	42.23
160	1874	870	344.6	1580	189.9	2290	130.9	3000	99.94	4420	67.83	7150	41.93
170	1764	880	340.7	1590	188.6	2300	130.4	3020	99.28	4440	67.53	7200	41.64
180	1666	890	336.9	1600	187.4	2310	129.8	3040	98.62	4460	67.22	7250	41.35
190	1578	900	333.1	1610	186.2	2320	129.2	3060	97.98	4480	66.91	7300	41.07
200	1499	910	329.5	1620	185.1	2330	128.7	3080	97.34	4500	66.63	7350	40.79
210	1428	920	325.9	1630	183.9	2340	128.1	3100	96.72	4520	66.33	7400	40.52
220	1363	930	322.4	1640	182.8	2350	127.6	3120	96.10	4540	66.04	7450	40.24
230	1304	940	319.0	1650	181.7	2360	127.0	3140	95.48	4560	65.75	7500	39.98
240	1249	950	315.6	1660	180.6	2370	126.5	3160	94.88	4580	65.46	7550	39.71
250	1199	960	312.3	1670	179.5	2380	126.0	3180	94.28	4600	65.18	7600	39.45
260	1153	970	309.1	1680	178.5	2390	125.4	3200	93.69	4620	64.90	7650	39.19
270	1110	980	305.9	1690	177.4	2400	124.9	3220	93.11	4640	64.62	7700	38.94
280	1071	990	302.8	1700	176.4	2410	124.4	3240	92.54	4660	64.34	7750	38.69
290	1034	1000	299.8	1710	175.3	2420	123.9	3260	91.97	4680	64.06	7800	38.44
300	999.4	1010	296.9	1720	174.3	2430	123.4	3280	91.41	4700	63.79	7850	38.19
310	967.2	1020	293.9	1730	173.3	2440	122.9	3300	90.86	4720	63.52	7900	37.95
320	936.9	1030	291.1	1740	172.3	2450	122.4	3320	90.31	4740	63.25	7950	37.71
330	908.6	1040	288.3	1750	171.3	2460	121.9	3340	89.77	4760	62.99	8000	37.48
340	881.8	1050	285.5	1760	170.4	2470	121.4	3360	89.23	4780	62.72	8050	37.25
350	856.6	1060	282.8	1770	169.4	2480	120.9	3380	88.70	4800	62.46	8100	37.02
360	832.8	1070	280.2	1780	168.4	2490	120.4	3400	88 18	4820	62.20	8150	36.79
370	810.3	1080	277.6	1790	167.5	2500	119.9	3420	87.67	4840	61.95	8200	36.56
380	789.0	1090	275.1	1800	166.6	2510	119.5	3440	87.16	4860	61.69	8250	36.34
390	768.8	1100	272.6	1810	165.6	2520	119.0	3460	86.65	4880	61.44	8300	36.12
400	749.6	1110	270.1	1820	164.7	2530	118.5	3480	86.16	4900	61.19	8350	35.91
410	731.3	1120	267.7	1830	163.8	2540	118.0	3500	85.66	4920	60.94	8400	35.69
420	713.9	1130	265.3	1840	162.9	2550	117.6	3520	85.18	4940	60.69	8450	35.48
430	697.3	1140	263.0	1850	162.1	2560	117.1	3540	84.70	4960	60.45	8500	35.27
440	681.4	1150	260.7	1860	161.2	2570	116.7	3560	84.22	4980	60.20	8550	35.07
450	666.3	1160	258.5	1870	160.3	2580	116.2	3580	83.75	5000	59.96	8600	34.86
460	651.8	1170	256.3	1880	159.5	2590	115.8	3600	83.28	5050	59.37	8650	34.66
470	637.9	1180	254.1	1890	158.6	2600	115.3	3620	82.82	5100	58.79	8700	34.46
480	624.6	1190	252.0	1900	157.8	2610	114.9	3640	82.37	5150	59.22	8750	34.27
490	611.9	1200	249.9	1910	157.0	2620	114.4	3660	81.92	5200	57.66	8800	34.07
500	599.6	1210	247.8	1920	156.2	2630	114.0	3680	81.47	5250	47.11	8850	33.88
510	587.9	1220	245.8	1930	155.3	2640	113.6	3700	81.03	5300	56.75	8900	33.69
520	576.6	1230	243.8	1940	154.5	2650	113.1	3720	80.60	5350	57.11	8950	33.50
530	565.7	1240	241.8	1950	153.8	2660	112.7	3740	80.17	5400	55.52	9000	33.31
540	555.2	1250	239.9	1960	153.0	2670	112.3	3760	79.74	5450	55.01	9050	33.13
550	545.1	1260	238.0	1970	152.2	2680	111.9	3780	79.32	5500	54.51	9100	32.95
560	535.4	1270	236.1	1980	151.4	2690	111.5	3800	78.90	5550	54.02	9150	32.77
570	526.0	1280	234.2	1990	150.7	2700	111.0	3820	78.49	5600	53.54	9200	32.59
580	516.9	1290	232.4	2000	149.9	2710	110.6	3840	78.08	5650	53.07	9250	32.41
590	508.2	1300	230.6	2010	149.2	2720	110.2	3860	77.67	5700	52.60	9300	32.24
600	499.7	1310	228.9	2020	148.4	2730	109.8	3880	77.27	5750	52.14	9350	32.07
610	491.5	1320	227.1	2030	147.7	2740	109.4	3900	76.88	5800	51.69	9400	31.90
620	483.6	1330	225.4	2040	147.0	2750	109.0	3920	76.49	5850	51.25	9450	31.73
630	475.9	1340	223.7	2050	146.3	2760	108.6	3940	76.10	5900	50.82	9500	31.56
640	468.5	1350	222.1	2060	145.5	2770	108.2	3960	75.71	5950	50.39	9550	31.39
650	461.3	1360	220.4	2070	144.8	2780	107.8	3980	75.33	6000	49.97	9600	31.23
660	454.3	1370	218.8	2080	144.1	2790	107.5	4000	74.96	6050	49.56	9650	31.07
670	447.5	1380	217.3	2090	143.5	2800	107.1	4020	74.58	6100	49.15	9700	30.91
680	440.9	1390	215.7	2100	142.3	2810	106.7	4040	74.21	6150	48.75	9750	30.75
690	434.5	1400	214.2	2110	142.1	2820	106.3	4060	73.85	6200	48.36	9800	30.59
700	428.3	1410	212.6	2120	141.4	2830	105.9	4080	73.49	6250	47.97	9850	30.44
710	422.3	1420	211.1	2130	140.8	2840	105.6	4100	73.13	6300	47.59	9900	30.28
										6350	47.22	9950	30.13

length of a single wave, which in this case would be equal to 300,000,000 (appx.) divided by 500, equalling 600,000 cycles per second or (reduced to kilocycles by dividing by 1,000) 600 kilocycles. On the preceding page is given a chart for converting kilocycles to meters, or meters to kilocycles.

KILOLINE—This is equal to 1,000 *lines of force*, or 1,000 *maxwells* (q.v.). The *maxwell* or the *line of force* is the unit used to measure *magnetic flux*. (See *Line of Force, Maxwell, Magnetic Flux.*)

KILOVOLT — abbreviated K.V. — The kilovolt is equal to 1,000 volts.

KILOVOLT-AMPERE — Abbreviated K.V.A. or kv-a.—The product of the effective volts across the terminals of a circuit by the effective amperes flowing in that circuit, divided by 1,000. Alternators are rated in *kilovolt-amperes* because their load determines the power factor. Thus with a zero *power factor* (q.v.) the *true power* (q.v.) in kilowatts would equal zero even if the alternator were delivering maximum amperes and maximum volts. At 50% power factor the kilowatt capacity would be half that at 100% power factor. On the other hand the kilovolt-ampere capacity remains the same no matter what the power factor.

KILOWATT — abbreviation K.W.—The kilowatt is a unit of electrical power having the value of 1,000 watts. One kilowatt equals 1,000 watts. To reduce the power expressed in kilowatts to watts, it is necessary to multiply the number of kilowatts by 1,000. Most electrical formulas use watts rather than kilowatts. Therefore, in solving such formulas, where the power is given in kilowatts, it is necessary to multiply this by 1,000 before using it in the formula. For example, suppose the power expended in an electrical circuit carrying 100 amperes is 20 kilowatts. The voltage will equal the power in watts divided by the current in amperes. This is $\frac{20 \times 1{,}000}{100} = 200$ volts. Motors are often rated in kilowatts instead of horsepower. For practical calculations, the horsepower rating of a motor is equivalent to four-thirds of its kilowatt rating. (See *watts.*)

KILOWATT-HOUR—The energy expended when work is done for one hour at the rate of one kilowatt. It is possible to calculate the energy expended in an electrical circuit over a certain period of time, knowing the current in amperes and the resistance of the circuit. Using the following formula the energy expended will be obtained in kilowatt-hours:

$$\text{Work performed or energy expended} = \frac{\text{Current}^2 \times \text{Resistance}^* \times \text{Time}^\dagger}{3{,}600{,}000} = \text{kilowatt-hours.}$$

KIMURA SHUNKICHI—Japanese radio authority. Kimura was born in 1866, and educated at the Scientific College of the Tokyo Imperial University, his special study being physics, which he continued to study at Harvard and Yale Universities, United States.

In 1901 Kimura entered the Japanese Navy and first began to study wireless telegraphy, particularly for naval use. In 1906 he was appointed the Japanese delegate to the International Wireless Telegraph Conference, Berlin, and after his retirement from the Navy, 1912, he became the director of the Nippon Radio Telegraph and Telephone Company. Kimura has written largely on radio subjects for various scientific journals.

KINETICS—That branch of dynamics dealing with forces that produce or change motion. Energy is usually classified either as *potential* or *kinetic.* When energy is available for the production of work it is referred to as potential energy. Energy at work is *kinetic energy* (q.v.). The term *kinetic* refers to motion.

KINETIC ENERGY—The work a body is able to do by reason of its motion. The unit of energy is the *erg.* This unit is also used to measure work. (See *Erg.*) It should be noted that *kinetic energy* is stored in the magnetic field. It requires more energy to start a current in a circuit having great inductance than in one having small inductance. This greater amount of energy is stored in the magnetic field and is returned to the circuit when the current decreases to zero.

KINRAIDY SPARK GAP—A form of *quenched spark gap* (q.v.) consisting of two water-cooled flat terminals close together and between which discharge occurs.

KIRCHOFF'S LAWS—These are two in number. First Law: The sum of the currents flowing to a point, in any electrical circuit, is equal to the sum of the currents flowing away from that point. Second Law: In any closed electrical circuit, the sum of the impressed *electromotive forces* (q.v.) will equal the sum of the *voltage drops* (q.v.). This statement requires modification, in so far as "addition" of voltages is concerned. Voltages are added provided that they are in the same direction, but must be subtracted if in opposite directions. These two laws depend on *Ohm's Law* (q.v.) and constitute a further application of that law to more complicated electrical circuits. In addition to simple electrical circuits, conductors may be connected in various complicated networks, all of which come under the heading of *divided circuits*. By means of *Kirchoff's Laws*, the current in any part of a divided circuit may be found, if the resistances of the various parts, and the electromotive forces are given.

KITES AS AERIAL SUPPORTS—During the early experiments with wireless, kites were successfully employed by Marconi as aerial supports.

KLEIN, RENE HENRI—Anglo-French radio expert. Born at Soults-sous-Foret, France, in 1880, he first became interested in wireless telegraphy in 1908. He was the founder and first honorary secretary of the Wireless Society of London, 1913-20, and became a vice-president of the society. He was one of the inventors with H. L. McMichael of the synthetic galena crystal Radiocite, and has written many articles on wireless subjects.

KNIFE SWITCH—A switch in which the movable arm wedges in between two parallel spring clips. Knife switches may be either of the *single pole* (s.p.) or *double pole* (d.p.) types and also may either be *single throw* (s.t.) or *double throw* (d.t.). Knife switches are often referred to as *Lever* switches They are used on direct current circuits up to 250 volts and on alternating current circuits up to 500 volts (See *Ground Switch; Double Throw Switch.*)

KLEMENCIC THERMAL JUNCTION—A device consisting of two thin sheets of brass, designated in the illustration as A, A. These are 4 inches by 11.8 inches and are placed about 1 inch apart. Soldered to one plate is a fine platinum wire and to the other plate is a fine platinum-nickel wire. These two wires are connected together at J to form a *thermal junction* (q.v.) and are then led off at right angles and are soldered at their other ends to the leads R, R, of a sensitive *galvanometer* (q.v.). This resonance system is fixed at the focal line of a suitable cylindrical metallic reflector. When electric waves, with the electric force parallel to A A fall on this receiver, electric oscillations between A and A produce heating at the junction J which is the point of contact between the two dissimilar metals. In consequence, the heat developed gives rise to a thermoelectromotive force at the junction and consequently to a current in the galvanometer. This instrument can be used to detect and measure electric waves.



Schematic diagram showing Klemencic thermal junction.

KOEPSEL PERMEAMETER—An instrument used for measuring the *permeability* (q.v.) of an iron or steel bar. In its principle of operation, this device is a movable coil milli-voltmeter in which the permanent magnet is replaced by an electromagnet. The sample to be tested forms a part of this electromagnet. The flux produced in the sample and in the pole pieces of the instrument is measured by a movable coil similar to those used in direct current voltmeters. The coil is supplied with energizing current from a small dry battery. Deflections are indicated by a pointer on a dial, the scale being calibrated directly in magnetic densities.

KOHLRAUSCH'S LAW—This law states that the rate of motion of each atom in a solution undergoing electrolysis for a given liquid is independent of the element with which it may have been in combination.

KOLSTER, FREDERICK A.—American radio authority. Born at Geneva, Switzerland, January 13, 1883, he was educated at Cambridge, Mass., and Harvard University. From 1902-08 he was assistant to J. S. Stone, the radio expert, and from 1909-12 to Dr. Lee de Forest. He was appointed chief of the Radio Section of the Bureau of Standards, a post he held until 1921, when he became research engineer to the Federal Telegraph Company.

Kolster has written a large number of articles on radio subjects, including those on the "Effects of Distributed Capacity in Coils," "Reinforced Harmonics in Radio Transmission," etc. He is the inventor of the Kolster decremeter, of a radio compass, of directional radio systems, etc., and is a member of the American Institute of Radio-Engineers.

---

*Ohms. †Seconds.

KOOMANS, NICHOLAS—Dutch radio authority. Born at Delft, 1879, he was educated there as a mechanical and electrical engineer. In 1908 he received his doctorate for his dissertation "Regarding the Influence of Self-Induction in Telephone Conducting Wires." He was one of the founders of and editor of the "Monthly Review of Telephony and Telegraphy," and was also one of the founders of the Dutch Society for Radio Telegraphy. Koomans is a member of the International Electrotechnical Commission and professor in physics and theoretical electrical engineering at the school of the Dutch Post and Telegraph Administration.

KORDA AIR CONDENSER—A variable *condenser* (q.v.) using air as the *dielectric* (q.v.) consisting of two sets of semi-circular plates, one set being connected together and fixed in position and the other set being also connected together but capable of being rotated about a central axis. Rotating the movable plates brings a greater or less area of the two sets of plates into interlapping positions, thus permitting the capacity of the condenser to be varied. This condenser was patented by Korda in Germany in 1893.

KORN, ARTHUR—German radio expert. Born at Breslau, Germany, 1870, Korn was educated at Leipzig and Paris and became professor of physics at the University of Munich, 1903-8, and afterwards professor at the Polytechnical High School, Charlottenburg, Berlin.

Korn is well known for his experiments on and the invention of a method of transmitting photographs by telegraphy, the first photograph being telegraphed from Munich to Berlin in 1907 by his methods. He is the inventor of a system of telautography and wireless phototelegraphy, and the author of a number of standard books on electricity.

L

L—The symbol of *inductance* (q.v.) or the *coefficient* of *self-induction.* In general, the co-efficient *L* by which the rate of change of current in any circuit must be multiplied to obtain the value of the self-induced *electromotive force* (q.v.) is called the *coefficient* of *self-induction* or simply the *inductance.* (See *Self-induction, coefficient.*)

LAG—One *alternating current* quantity reaching its maximum at a later time than a second alternating current quantity. As an example,—the current is said to *lag* behind the impressed voltage when maximum current occurs after maximum voltage. In other words, the current and voltage in such an alternating current circuit are out of *phase* (q.v.). In the above example, since the current *lags* behind the voltage, the voltage is said to lead the current. *Inductance* (q.v.) in an alternating current circuit will cause the current to *lag* behind the impressed voltage. *Capacity* (q.v.) in such a circuit will cause the current to *lead* (q.v.) the impressed voltage. The word *lag* may be applied to magnetic quantities as well as electrical quantities. Thus, one magnetic flux may *lag* behind another as in the case of an induction motor where the induced *magnetic flux* (q.v.) *lags* behind the impressed magnetic flux. Another type of magnetic *lag* is the retardation of magnetic effects behind their causes, due to *hysteresis* (q.v.) in the magnetized substance. (See *Lead,* also *Leading Current.*)

LAMINATED—Composed of a number of thin plates, one on top of another. Examples of laminated construction are *laminated brushes, laminated cores laminated conductors,* etc.

LAMINATED CORE—An arrangement of soft iron plates or stampings forming the core of a transformer, or of an armature of a motor or generator. Cores are laminated in this way, principally to reduce *eddy current* (q.v.) losses. In the case of an armature core, this must be laminated parallel to the direction of rotation (in other words, perpendicular to the axis of rotation). Laminations are insulated from each other by means of japan, varnish, shellac or simply rust.

LAMP BANK—A bank of incandescent lamps arranged so that they can be connected in series or parallel. *Lamp banks* are used in laboratories in conjunction with electrical machinery under test. In this case, the lamps act as the *load,* the more lamps being connected in *parallel,* the greater the amount of current being drawn. *Lamp banks* are sometimes connected in *series* in a circuit for the purpose of reducing voltage. An example in this connection is the use of a lamp or bank of lamps in charging a 6-volt storage battery from a 110-volt direct current source. Lamp banks are sometimes called *lamp panels* or *lamp batteries.*



Use of lamp bank in charging storage battery.

LANGMUIR, IRVING—American radio authority. Born at Brooklyn, New York, January 31st, 1881, he was educated at the School of Mines, Columbia University, and was for some time assistant to Professor Nernst at the University of Gottingen. In 1906-9 he was instructor in chemistry at the Stevens Institute of Technology, and in the latter year he became a research assistant to the General Electric Company, at Schenectady. He has carried out a series of brilliant researches on apparatus used in wireless telegraphy and telephony, on electron discharge apparatus, atomic and molecular structure, etc.

Langmuir has paid particular attention to high-vacuum valves, and is the inventor of the Langmuir valve. To him is due the discovery that by treating the tungstic oxide used in the construction of tungsten filaments with certain compounds of thorium the filament becomes thoriated tungsten and the electronic emission is enormously increased. These filaments are the ones used in dull emitter valves, the electrons being given off at comparatively low temperatures Langmuir is the author of many papers to scientific and technical journals, including those on pure electron discharge, thermionic currents in high vacua, etc. He is also well known for his mercury condensation pump for high vacua.

LAP WINDING—An armature winding in which the opposite ends of each coil are connected to adjoining commutator segments. As a result the windings lap back and upon themselves forming loops. *Lap winding* is also called *loop winding, parallel winding* and *multiple winding.* In the elementary form of *lap winding* the method of connection to the commutator bars is as follows: One side of a coil is connected to a commutator bar, and the other side of the coil, which is located 180 electrical degrees (the distance from the center of a north pole to the center of the adjacent south pole) away, has its end connection brought back and soldered to the next adjacent commutator segment. This method of overlapping the ends is continued all the way around the armature until all the slots have been filled and the circuit has been closed on itself. The coils must all be symmetrical. This means that if there is a forward throw of a certain num-



A typical lap winding shown in developed view. In the winding shown each inductor is connected at the rear of the armature to one five slots away. Thus 3 is connected to 8, 5 to 10, etc. After having made one complete "element"—as, for example, A-1-6-B—the winding forms a second "element," B-3-8-C, which laps over the first. This is continued around the armature until the winding closes on itself.

ber of slots on the first coil, all the other coils must have the same forward throw. In like manner all the return throws must be the same. In the *lap wound* generator there are as many paths for the current as there are poles. Hence the name *parallel* or *multiple winding*. This necessitates the use of as many sets of brushes as there are poles. An increased number of paths in parallel means increased current capacity. In the case of a motor, the greater the number of armature paths between brushes, the greater will be the speed, other conditions remaining equal.

LAW OF ELECTROMAGNETIC INDUCTION—Also known as the "*Law of Generator Action*" and as "*Faraday's Law.*" If there is relative motion between an electrical conductor and a magnetic field, such that the conductor cuts *flux*, an *electromotive force* (q.v.) will be induced in the conductor. The amount of the induced electromotive force will depend upon the strength of the magnetic field, upon the speed of cutting, upon the length of the conductor cutting the field and upon the direction of motion between the conductor and the field. Thus the stronger the magnetic field, the greater the induced electromotive force. The induced electromotive force will also increase with increased speed of cutting and with increased conductor length. When the conductor cuts the flux at right angles, the induced electromotive force is maximum. If the flux is cut in any other direction, the induced electromotive force will be less. The induced electromotive force decreases from maximum to zero as the angle of cutting decreases from 90 degrees to zero degrees. If a conductor is of such length and moves in such a direction, and at such a speed, as to cut 100,000,000 lines of force in one second, one *volt* (q.v.) will be induced in it. Expressed as an equation the induced electromotive force (in volts) will equal the flux cut (in *lines* or *maxwells*) divided by the product of the time (in seconds) times 100,000,000. This equation refers to the average value of the electromotive force induced in a single conductor. If a number of conductors are used the same electromotive force will be induced in each. If the conductors are so connected that their electromotive forces add up, the total average electromotive force can be found by multiplying the above equation by the number of conductors.

LATOUR, MARIUS—French radio expert. Born in October, 1875, he was educated at the University of Paris and the Ecole Superieure d'Eléctricité, Paris. He was for many years consulting engineer to the General Electric Company, and he specialized in the construction of high-frequency machines. Latour is the designer of the so-called S. F. R. alternator, in which there are a smaller number of stator slots than usual.

During the World War Latour was engaged in research work under General Ferrie, and he invented a system of elimination of the interference produced in telephone lines by neighboring high-tension power lines which has been installed throughout the greater part of France. Latour is the inventor of the now widely used system of high-frequency multiplex telegraphy and telephony, using the three-electrode valve for generation and reception. He is a member of many scientific societies, including the Institute of Radio Engineers, and of the American Institute of Electrical Engineers. He has written many articles on radio for scientific and technical journals, and is the inventor of a great many important radio developments covering practically the whole range of the art.

LEAD—Pronounced LEED—One alternating current quantity reaching its maximum at an earlier time than a second alternating current quantity. Thus in an alternating current circuit, the current is said to *lead* the voltage if maximum current occurs before maximum voltage. If the current reaches its maximum 90 *electrical degrees* ahead of the voltage, current and voltage are said to be in *quadrature* (q.v.) with current *leading* and voltage *lagging*. (See *Degrees, Electrical*, also *Leading Current* and *Lag.*)

LEAD SULPHATE—Formula $PbSO_4$—A white insoluble salt which is found in native form in the ground and which can be formed artificially by adding sulphuric acid to a soluble lead salt. The active elements of a lead *storage battery* (q.v.) consists of (PbO_2) *lead peroxide* on the positive plate and (Pb) *spongy lead* on the negative plate, with dilute *sulphuric acid* (H_2SO_4) as the *electrolyte* (q.v.). The final result, on discharge of such a battery is the formation of *lead sulphate* on both the positive and negative plates. This is a part of the process of producing current. After a normal discharge, the sulphate is finely crystalline and of such nature that it is easily reduced by the current flowing through the battery on charge. If charging is neglected and the battery is allowed to stand in a discharged state, the sulphate gradually ceases to be crystalline. It fills the pores of the plates and finally makes the active material hard and dense, thus lengthening the time required for a charge. A battery in this condition is said to be *sulphated*. If sulphating proceeds too far, it will result in *buckling* of *plates* (q.v.), loss of active material, greatly decreased capacity, lower efficiency and an increased internal resistance. A moderately sulphated battery can be restored by means of a prolonged charging at a moderate rate. In a badly sulphated battery, a number of successive charges and discharges may be necessary.

LEAD-IN—The wire leading from the aerial to the radio apparatus. *Lead-in* wire, as used for receiving sets, is usually rubber covered wire although bare antenna wire can be used provided it is properly insulated from the walls of the building. A poorly insulated lead-in will greatly reduce the efficiency of the finest antenna. (See *Down Lead.*)

LEAD-IN INSULATOR—Any form of insulator used for passing aerial lead-in through window, wall or roof. These insulators are usually made of porcelain, electrose or insulated copper strips. (See *Insulator, lead-in*, also *Window Lead-in.*)

LEADING CURRENT—An alternating current which reaches its maximum value at an earlier time than the voltage. When an inductance is inserted in an alternating current circuit, the self-induced *electromotive force* (q.v.) will combine with the *impressed* electromotive force and the resultant of the two will be the active electromotive force which causes the current flow. The current will always be exactly in *phase* (q.v.) with and proportional to the resultant electromotive force. The induced electromotive force is 90 degrees behind the current and therefore behind the resultant electromotive force, which is in phase with the current. The impressed electromotive force will lead the current and will be higher than the resultant electromotive force by an amount which at each instant is equal to the counter-electromotive force of the inductance. When a condenser is inserted in an alternating current circuit the current will charge the condenser. As the amount of current stored in the condenser increases, the electromotive force of the condenser increases also until the impressed and the condenser electromotive forces are equal. The condenser electromotive force, being a counter pressure, the current flow will cease when the two electromotive forces balance. The current being zero at this point and the condenser electromotive force a maximum, it follows that the condenser electromotive force is 90 degrees in advance of the current and hence of the resultant electromotive force which is in phase with the current. The impressed electromotive force lags behind the current which in this case is a *leading current* and moreover the impressed electromotive force is greater than the resultant electromotive force. It follows that if either capacity or inductance be placed in an alternating current circuit, the phase of the current with respect to the impressed electromotive force will change and the current flow will be reduced. Capacity sets up an electromotive force 90 degrees in advance of current flow, while inductance sets up an electromotive force of 90 degrees behind current flow. These two effects tend to neutralize each other when the proper amount of inductance and capacity are connected in series in a circuit and when they are just equal, no electromotive force other than the impressed is left to act on the circuit, the resultant and impressed electromotive forces are identical and there is no phase displacement. This is said to be a *resonant* (q.v.) circuit. (See *Lead, Lag*, also *Inductive Rise.*)

LEADS—Wires conveying or "leading" current from one point to another in a circuit. The conductors in any system of electrical distribution are referred to as *leads*. Sometimes the term *lead* is applied to the flexible wire or cable conveying current to or from a piece of apparatus.

LEAK—See *Grid Leak.*

LEAKAGE LINES—Also termed *leakage flux*—That part of the total magnetic flux in a magnet, transformer, generator, etc., which fails to complete the closed magnetic circuit and hence is dissipated or wasted. (See *Keeper.*)

LEAKAGE, SURFACE—The flow of electricity across the surface of insulators. Its amount depends on the material and preparation of the surface and the humidity of the atmosphere and is recorded by measuring the surface *resistivity* (q.v.). Several methods are employed to reduce *surface leakage*. Porcelain *insulators* for outdoor use are often of the *petticoat* type so that a portion of the surface of the insulator remains dry during a rain or snowstorm. Another method very generally used in radio work to reduce surface leakage, is the use of corrugated surfaces on insulators. This method increases the length and hence the resistance of the surface across which leakage is likely to take place.

LENGTH OF AERIAL—The distance from the aerial binding post at the instrument to the farthest point of the antenna system, measured to any of its extremities. Only one component wire of a system is taken into consideration even if two, three or four are used. In a *T aerial* only half of the horizontal span must be added to the length of the down lead. In the *umbrella* type, the length of one radial lead is added to the down lead.

LENZ'S LAW—An induced current always tends to stop the motion which produces it. Stated in another way, whenever current flows in a conductor, due to electromagnetic induction, the action between the magnetic field which is being cut and the field around the conductor is always such as to tend to oppose further motion of the conductor. The following is still another way of stating *Lenz's Law*: The field due to the induced current always acts to prevent a change of the original field.

LEYDEN JAR—A condenser consisting of a glass jar with an outer and an inner coating of tinfoil covering the bottom and the sides nearly to the neck.



A small leyden jar.

A brass rod terminating in an external knob passes through a wooden stopper and is connected to the inner coating by a loose chain. This condenser received its name from Leyden, the city in Holland in which it was invented.

L. F. C.—Abbreviation for *Low Frequency Current*. (See *Frequency, Low*, also *Frequency*.)

LIGHT — Radiant energy or visible *radiation* which affects the eye so that objects become visible. Light consists of *ether* vibrations varying between 400 billions per second producing waves 271 ten-millionths of an inch in length and giving red light, up to 750 billions per second producing waves of 165 ten-millionths in length, giving violet light. Faster or slower vibrations produce waves not visible to the human eye. Shorter waves are called *ultraviolet rays*, while those immediately above the red rays are known as *infra-red rays.* The speed of light waves is identical with that of other electromagnetic waves and electricity, and is 186,000 miles or 300,000,000 meters per second.

LIGHT LINE AERIAL—A device which acts as an aerial for a radio receiving set and which utilizes the electric lighting system by means of a plug to which a condenser is attached. The plug is inserted in any lighting socket and the aerial connection of the receiving set it attached by means of a flexible lead to one terminal of the condenser. (See *Adapter, Aerial.*)

LIGHTNING ARRESTER—(Also called *lightning protector.*) A device for protecting radio or other electrical apparatus from lightning or from atmospheric discharges. Radio *lightning arresters* are provided with two terminals, one being connected with the aerial and the other directly to a ground. Between these terminals is a medium which offers practically no resistance (or technically speaking, which offers low *impedance* (q.v.)) to the flow of very high frequency currents such as lightning discharges. However, this medium acts as an insulator to the normal operating currents. Hence, during the ordinary reception of radio signals, the currents flow past the *arrester* to the receiving instrument but they are unable to pass through the insulating medium of the *ligtning arrester* to the ground. When there is a lightning discharge, the arrester offers the shortest and most direct path to the ground and hence the dangerous current never reaches the apparatus but proceeds directly to the ground through the *lightning arrester*. The more popular designs of lightning arresters are of three types: vacuum, non-air-gap and air-gap. The vacuum type is the more sensitive of the three, due to its having a low functioning voltage. In a usual form, it consists of two terminals in a sealed glass chamber from which air has been partially exhausted. This type of arrester can be discharged repeatedly without impairing its efficiency. The non-air-gap type of arrester involves the use of a carborundum stone, with a special clay binder. This type of arrester has a rectifying action similar to that used in a carborundum detector. The air-gap type of *lightning arrester* depends for its efficiency on a closely spaced air-gap which offers a low break-down voltage. The Underwriters requirements call for the use of an approved lightning protective device on all radio receiving sets where outside aerials are used. Further requirements are that such arresters shall operate on 500 volts or less. (See *Arrester.*)



A carborundum type lightning arrester consisting of a block of carborundum held between two pieces of high resistance carbon.



Vacuum type of lightning arrester for indoor work.



Sectional view of vacuum type lightning arrester used for outdoor work.

Outdoor vacuum type lightning arrester shown above in sectional view.

LIGHTNING GAP—This refers to the *air gap* or *vacuum gap* in a *lightning arrester* (q.v.). This gap is connected across the aerial and ground leads to the receiving set. When the potential in the aerial rises above a certain value (usually 500 volts or less) a spark jumps the gap, discharging the excessive energy to the ground without damage to the radio apparatus. (See *Gap Arrester.*)

LIGHTNING SWITCH—A single pole, double throw knife *switch* (q.v.) used for grounding the antenna during a storm, or in some cases at all times when the apparatus is not in use. The upper terminal of the switch is usually connected to the aerial, the central terminal to which the switch arm is connected, leads to the radio set and the lower terminal is connected to the ground. In most installations, the *lightning switch* is mounted outside the building in which the radio apparatus is located. (See *Ground Switch.*)



Lightning switch combined with vacuum type lightning arrester.

LIKE CHARGES—Bodies which carry like *electrostatic charge* (q.v.) exert a repulsion against each other.

LIKE POLES—Like magnetic poles repel one another. This is one of the *laws of magnetism*. (See *Magnetism, Laws of.*)

LIMITING VOLTAGE OF BRUSH DISCHARGE—The potential at which a brush discharge passes into an arc or spark. Brush discharges and arcs may be reduced in radio transmitting apparatus by eliminating sharp points or edges on conductors and by coating the edges of metal plates with paraffin. (See *Brush Discharge*, also *Corona.*)

LIMITING VOLTAGE OF GLOW DISCHARGE—The potential at which the glow gives place to the *brush discharge* (q.v.) in a high tension line or in a radio transmitting aerial (q.v.). (See *Corona.*)

LIMITS OF AUDIBILITY—The limiting *frequencies* (q.v.) at which audible sounds are produced. These range from 500 to 1000 cycles per second up to as high as 10,000 cycles per second. *Audio frequencies* (q.v.) are sometimes defined as those conveniently heard in the telephone. (See *Frequency, High*, also *Frequency, Low.*)

LINE—A conducting wire between terminals in a system of electric communication or distribution. The positive wire is sometimes specifically referred to as the *line* and the return wire as *earth*. In many cases the earth or ground is used in the place of a return wire.

LINE OF FORCE—A theoretical conception used to map out a magnetic field and to show the direction along which the magnetism acts. *Lines of force* are conceived as forming closed loops and the path they traverse is called the *magnetic circuit* (q.v.) The positive direction of the *lines of force* is arbitrarily taken as that in which the north-seeking end of a compass moves. *Lines of force* are represented in diagrams by curves so drawn that the direction of the tangent at any point is the direction of the *magnetic force* (q.v.) at that point. The closeness of the lines is used to indicate the intensity of the force. The *line of force* is also used to indicate and map out an *electrostatic* (q.v) field in the same way as it is used for the magnetic field. The *line of force* is also called the *line of flux* or the *line of induction*. This latter term is used especially where the line of force is being considered in respect to its electrical effect. In some cases it is simply referred to as a *line*. Thus a line (*of force*, or *of flux*, or *of induction*) is an electromagnetic unit of magnetic flux and is equal to 10^{-8} *webers* (q.v.). In the practical system of measurements, the *maxwell* (q.v.) equal to one *line*, is the unit of *magnetic flux* (q.v.). When 100,000,000 *maxwells* are cut by a single conductor, in one second, one *volt* (q.v.) will be induced. (See *Law of Electromagnetic Induction*, also *Electromagnetic field.*)

LINEAR OSCILLATOR—See *Oscillator, Linear.*

LINE RADIO—Also known as *Wired Wireless*—A system of communciation devised by Major General George O. Squier which permits the transmission of electromagnetic waves along a wire or conductor. Instead of the waves spreading out in all directions, as in ordinary broadcasting, the waves travel along a predetermined path, viz: the conductor. It is possible to transmit either code or speech by *wired wireless*. Vacuum tubes are used as oscillators at the transmitting end and a specially designed vacuum tube set is used as the receiver. When code transmission is desired, a telegraph key is inserted in the circuit to intermittently stop and start the oscillating waves. This produces dots and dashes and in this way it is possible to send code using undamped radio frequency waves. When it is desired to telephone, the key is omitted and the radio frequency or *carrier waves* (q.v.) are produced continuously except when they are varied or modulated in amplitude corresponding to the voice of the speaker at the transmitting end. The wave which passes from the transmitting end of the wire to the receiving end is of radio frequency and is called the *carrier wave*. In a way, this wave is analogous to the wire which carries the voice current in wire telephony. *Line radio* can be transmitted over ordinary telephone or telegraph lines at the same time as these lines are being used for their ordinary purposes and without any interference whatsoever. High-tension lines are also used for transmission of *wired wireless*.



A liquid barreter.

LIQUID BARRETER—An electrolytic detector which utilizes a very fine platinum wire dipped to a small depth in nitric or sulphuric acid. These detectors were formerly used to some extent in receiving wireless code messages. The electrolytic detector of the *barreter* type was invented and named by *Fessenden* (q.v.). The illustration shows a liquid barreter. In the glass jar is a platinum glass-anode, lead cathode and sulphuric acid electrolyte.

LITZENDRAHT—abbreviated Litz—A German word, meaning braided wire. A high frequency conductor built up of a number of very fine conducting strands. The individual strands are enameled and the conductor is usually so constructed that each strand comes to the surface or very near the surface at regular intervals. In the most effective form of conductor the strands are braided so as to form a woven tube. The strands are usually covered by a single braided silk wrapper. The use of *litz* tends to reduce *skin effect* (q.v.). This type of wire has been found to be especially effective when used in the construction of *loop antennas* (q.v.).

LOADSTONE—also spelled *Lode-stone*—Iron ore which shows magnetic properties. The name loadstone is derived from a word meaning leading stone and refers to the property of a compass of pointing to the north magnetic pole. The loadstone is also referred to as a *natural magnet.* (See *Magnetite*, also *Magnet.*)

LOADING—Adding capacity or inductance to a circuit. *Inductance coils* (q.v.) called *loading coils* are used to increase the inductance and condensers are used to increase the capacity. A loading coil may be used to increase the *wave length* (q.v.) of an antenna by placing it in series between the *lead-in* (q.v.) and the receiving set. In the case of a transmitting antenna, the loading coil may be used to tune the aerial for *resonance* (q.v.) at a desired frequency. An example of the use of loading, is that of the addition of a loading coil to a receiving set for the purpose of enabling the set to receive higher wave lengths.

LOADING INDUCTANCE—An inductance coil used to increase the wave length of a circuit. This term usually refers to an inductance coil used in connection with a radio receiving set for increasing its receptive wave length range. Sometimes the term *loading coil* is applied to a unit consisting of an inductance coil, mounted beneath a panel in a small cabinet. On the outside of the panel is a contact arm and a number of studs. These latter lead to taps taken from the inductance coil. By moving the contact arm from one stud to another it is possible to vary the loading of the circuit as desired. A loading coil connected in series with the aerial will increase the natural wave length of the aerial. (See *Loading*, also *Inductance, Antenna.*)

LOCAL ACTION—Electrochemical action within a cell, usually at the positive plate, which does not add to the useful output. In primary cells, zinc is the material usually employed for the positive plate. This zinc practically always contains impurities such as carbon, iron, etc. When the zinc is immersed in the electrolyte, there is a difference of potential between the zinc and the impurities and small local currents flow from the zinc through the electrolyte to the impurities and back to the zinc again. These currents serve no useful purpose and moreover use up the zinc and the electrolyte. *Local action* can be practically eliminated by coating the surface of the zinc with mercury. This is called *amalgamation*. In secondary cells or *accumulators* (q.v.) local action is due to the action which takes place between the lead of the positive and the coating of lead sulphate.

LOCAL OSCILLATIONS—Oscillations set up in the vicinity of a receiving set for test purposes or within the set, as in the *super-heterodyne*, to produce oscillations differing in frequency from the incoming oscillations so as to establish a beat frequency. *Local oscillations* may be produced by means of a buzzer. This is a method frequently used in testing. The use of such oscillations enables a manufacturer of radio receiving sets to test these sets for selectivity, etc., without waiting for actual broadcasting. In the *super-heterodyne* (q.v.) local oscillations are produced by a suitably arranged vacuum tube. (See *Driver.*)

LOCUS—The path of a movement graphically represented by a curve. In mathematical language, the *locus* of an equation is the curve that contains all the points whose co-ordinates satisfy the equation. The circle is defined as the *locus* of all points in a plane equidistant from a fixed point in the plane called the center.

LODGE, SIR OLIVER—British Physicist and radio pioneer. Born at Penkhull, near Stoke-upon-Trent, June 12th, 1851, Oliver Lodge went to the Newport Grammar School at the age of eight, but at fourteen was taken into business to help his father. He worked in the evenings for the intermediate examination in science at the University of London, and eventually took first-class honors in physics. In 1872 he went to University College, London, and in 1877 took his D.Sc. in electricity and became demonstrator, and afterwards assistant professor in physics at University College.



Sir Oliver Lodge.

In 1881 he was appointed first professor of physics at Liverpool, and in 1887 he was made a Fellow at the Royal Society. In 1888 he received the honorary L.L.D. of the University of St. Andrews, the first of a long series of such distinctions. In 1900 he was appointed the first principal of the University of Birmingham, a post from which he retired in 1920. In 1902 he was knighted. Sir Oliver Lodge is one of the foremost physicists of his time, and his brilliant series of researches into electrical phenomena, which he has made his special study have had a profound effect in all branches of that subject. To him, indeed radio owes as much as to any man, for he dealt with fundamentals when the whole subject of electromagnetic radiation was in its infancy. He was led to study the surging and oscillating character of an electrical discharge along wires as a result of his investigations as to the best means of protection against lightning.

One very remarkable experiment of his is now well known under the name of Lodge's resonating jar, now used as a measurer of wave length. In these experiments Lodge was really dealing with the electromagnetic waves discovered by Hertz in 1888. Lodge early recognized the vast importance of the discovery by Hertz, which so brilliantly confirmed the theories of Clerk-Maxwell, and he threw himself into work of investigating these ways with an energy which made him the foremost British physicist on the subject at the time. All this was pioneer work before Marconi and others came along and built upon the solid foundations which Lodge had prepared.

It was during this early period that Lodge discovered his coherer, and with this detector devised the first practical wireless telegraph, sending signals over a distance of several hundred yeards. In May, 1897, Lodge took out his fundamental patent for tuning—a patent that was successfully upheld in the law courts, and extended for seven years by Lord Parker. The patent was acquired by the Marconi Company in 1911. Sir Oliver Lodge has been a pioneer in many other directions. His theories and experiments in connection with the ether, of which he is the leading exponent, are well known, and he has carried out a number of interesting researches on the passage of electricity through liquids. Sir Oliver was the first to devise a simple and direct experiment to show the speed and direction of travel of the constituents of a salt in solution when broken up by a current of electricity. For his researches on electric waves and the passage of light through a moving medium, Sir Oliver Lodge received in 1898 the Rumford Medal of the Royal Society, one of the highest honors the society bestows.

Sir Oliver Lodge has won a well-deserved reputation for the clearness and simplicity with which he is able to explain many of the difficult and fundamental truths of physics, and this clarity of expression is well shown in the many articles he has written.

LODGE DISC DETECTOR—An imperfect contact detector consisting of a steel disc rotating with its sharp knife edge just touching some mercury having a film of oil on it. When an oscillation passes through the circuit, momentary cohesion sets in between the disc and the mercury, but this is immediately broken by the revolving motion of the disc. In this way, oil re-insulates the disc at the completion of each passage of oscillations. Using this type of detector, code signals can be recorded with great precision on a *Morse* tape using a syphon recorder. The *disc detector* is in reality a specialized form of *coherer* (q.v.).

LOG—A list of dial readings of a radio receiving set with corresponding call letters of the broadcasting stations received at these readings. A radio set is said to *log* when the same stations always come in at exactly the same dial readings. Thus on a three dial set, if WEAF comes in at 61, 60 and 60 and always comes in at these identical readings using the same aerial, the set *logs*. All present day sets are constructed so that stations can be accurately logged. Sometimes the term log is used to refer to a graph or chart on which dial settings are plotted against wave lengths of stations recorded. A graph is a diagrammatic representation by means of lines, of the relation between several quantities. Figure 1, gives a simple illustration of this. Suppose it is desired to obtain a general idea of how the radio business varies from year to year or from season to season. On a piece of paper, ruled both vertically and horizontally, as in Figure 1, the months and years are marked at the bottom horizontally. The vertical lines then represent the months and the bottom horizontal line is called the *axis of time*. These vertical lines are known technically as *ordinates*. The vertical line to the extreme left is called the axis of ordinates and after it has been marked as shown in Figure 1, to represent dollars, it may be referred to as the *axis of dollars*. The horizontal lines are known as *abscissas*, the bottom horizontal line being the *axis of abscissas*. Assume that a certain radio concern did $10,000 worth of business in the month of January, 1924. Looking upward along the vertical line representing this month, until the horizontal line representing $10,000 is reached, a point is put at the intersection of these two lines. Suppose that in the following month, February, 1924, the firm does $12,000 worth of business. The point is found as before by following the line February, 1924, up to the line indicating $12,000. Each horizontal line in the figure represents $1,000, so that this point should be found two lines higher than the one marked for $10,000. This can then be continued indefinitely, plotting the amount of business for each month. Assume that in the summer there is a lull in business. The decline starts, say, in the month of May. The business done amounted to $8,000. By glancing at the chart it is possible to ascertain a number of facts which stand out much clearer than where columns of figures are given. Thus the seasonal character of the business is apparent at a glance. It can also be seen readily that the business was better in 1925 than in 1924, etc. Radio logs are plotted in exactly the same way. Each point must be obtained individually in order for the curve to be absolutely accurate, although in many cases a few well chosen points are sufficiently satisfactory. In Figure 2, the dial setting is marked along the bottom of the chart. The scale is here chosen at one division on the chart equal to 5 divisions of the dial. If preferred the scale could be chosen so that one division on the chart would equal one division on the dial as shown on chart on the following page, which is a typical log of an actual set. Proceeding, it is first necessary to find out the limits of the chart. The limits of the horizontal scale are already known, i.e., zero to 100 on the dial. Looking over the list of broadcasting stations, it is found that they all have wave lengths which fall, roughly between 200 and 600 meters. Therefore it is not necessary to make the vertical scale include wave lengths outside of this range. Consequently the vertical scale is started at 200. Counting upward, two divisions on the chart are taken, for convenience, as equal to 50 meters. Having done this, actual readings are next taken on the radio set. Suppose that the first station tuned in is WEAF and that this is tuned in at 85 on the dial. This station has a wave length of 492 meters. Looking along the bottom of the chart for 85, the vertical line is then followed until the position of 492 meters is reached. This is slightly below the 500 line on the chart, Figure 2, and is indicated by the letter A. Next suppose that WOO, having a wave length of 509 meters is tuned in at 90 on the dial. This, then gives the point marked B. Then another station is tuned in, indicated by the point C,



FIG. I

Log showing variation of a business.



FIG.3

A three-dial radio log using only one chart.



FIG.2.

A radio log.



FIG.4

Radio log showing curve drawn so as to touch as many points as possible.



Fig. 5—A three-dial radio log using three separate charts.

Various stations are thus located by points on the chart until enough points are obtained to draw the curve. If the points do not give a smooth curve, it is necessary to approximate a curve, that is to draw it so as to pass through as many of the points as possible. This has been done in Figure 4.

Sometimes points are obtained that do not seem to have any meaning, such as the point A in Fig. 4. This point may have been subject to inaccuracies in reading the dial, or perhaps the operator did not read the wave length correctly from the list of stations. There is always the possibility, also, that he did not plot the point properly. He has plotted the point A as 251 meters at a setting of 20 when it might have been 335 meters at 20 on the dial, in which case it would have fallen directly upon the curve. If none of these difficulties can be found with the point A it can be discarded, however, because it is an absurd point, as the 12 other points, which determine the curve, will testify. Generally it is not good practise to discard points, but the experimenter must learn to use his good judgment.



An example of a station log chart.

In single-control sets, where only one dial is employed it is only necessary to have one of these radio log curves. In receivers, such as the Neutrodyne or any two-stage radio frequency amplifier, where three dials are employed, it is generally necessary to log each dial separately. The reason for this is, that although these sets are supposed to tune to stations with identical dial settings, many of them do not do so, a difference as great as 10 divisions on the dial often being found. A three dial log is shown in Fig. 5. Separate charts may be used for each dial, or, for convenience, as has been done in Fig. 3, the three charts may be combined into one. If the difference between the dial settings is very small, say only a division or two, one curve will be sufficient.

Many things can be learned from studying the curves obtained. Take for instance, Fig. 2. This is practically a straight line at the higher wave lengths, changing from about 500 meters to about 400 in 55 divisions of the dial. In the remaining 35 divisions of the dial the wave length changes from 400 to 250. In the first case there was a range of 100 meters for 55 divisions and in the latter case a range of 150 meters in 35 divisions. This is because the curve bends downward. At the low dial settings a small change in the dial reading means a relatively large change in wave length, while at the upper end of the dial the same change in dial reading will mean a relatively small change in wave length. The reason why the stations are so crowded at present, at the small end of the dial, is then very apparent, i.e.:

To illustrate, a station operating on a 200 meter wave corresponds to a frequency of 1500 kilocycles (1 kilocycle equals 1000 cycles), and a station on 200 meters corresponds to a frequency of 1,363.5 kilocycles. In other words the difference in wave length is only 20 meters whereas the difference in kilocycles in 136.5. These two wave bands are at the low end of the present broadcast wave band. Now at the high end of the band we find a wave length of 600 meters corresponds to 500 kilocycles, and a wave of 580 meters corresponds to 517.2 kilocycles, or a difference of but 17.2 kilocycles for the 20 meter difference in wave length. At the lower end of the broadcast band between 200 and 220 meters we found a difference of 20 meters equalled 136.5 kilocycles. This indicates that as the wave length becomes lower the difference in frequency becomes very high.

To bring this most strongly to the mind, go down to the extremely low wave of 5 meters. Here the frequency is found to be 60,000 kilocycles. Going up to 25 meters, this corresponds to 12,000 kilocycles, so that for this difference of 20 meters there is the tremendous difference of 48,000 kilocycles.

The accompanying illustration, Fig. 6 will explain the matter very clearly. In changing the dial setting from 100 to, let us say, 90, the wave length is changed roughly from 600 to 580 meters. This is a change from 500 to 517 kilocycles. On the other end of the dial from zero to about 10 we have a change of wave length of roughly 200 to 220 meters, an approx-mate change of from 1500 to 1363 kilocycles. In the first case on the upper part of the dial we have only made a change of 17 kilocycles in the frequency. On the lower end of the dial we have made a change of 137 kilocycles.


KILOCYCLES
METERS
1363.5
517.2
1500
500
0
10
20
30
40
50
60
70
80
90
100
200
220
580
600
1500
1363
137 KILOCYCLES DIFFERENCE
517
500
17 KILOCYCLES DIFFERENCE
137 / 10 KILOCYCLES = 14 WAVE CHANNELS (APPROX.)
17 / 10 KILOCYCLES = 2 WAVE CHANNELS (APPROX.)

Fig. 6—This illustration shows clearly why stations are crowded on the dial at the lower wave lengths.

According to the frequency allocation as made by the Government, which places broadcast frequencies 10 kilocycles apart, on the upper 10 divisions of the dial there is room for approximately 2 frequency channels whereas on the lower 10 divisions of the dial there is room for roughly 14 frequency channels. This shows very clearly that we would have to be able to separate 14 stations on the lower 10 divisions whereas we have only 2 to separate on the upper 10 divisions of the dial.

So it will be understood why turning the dials but a degree or two at the low setting causes a relatively large change in frequency, tuning in perhaps several stations within one degree of the dial, while at the higher settings, due to the small difference in frequency, as stated, on the higher waves, it may be necessary to turn the dials two or three degrees on either side of the peak of the broadcast wave before it is tuned out. (See *Dial.*)

LOGARITHM—abbreviation LOG—The power to which a number (defined as a base) must be raised in order to equal a given number. As an example, given the number 100, assume that it is desired to determine the *logarithm* of this number to the base 10. (When 10 is used as a base, the *logarithms* obtained are said to belong to the *common* or *Briggs system.*) Then the exponent or power which will raise 10 to the value of 100 is known as the *logarithm* of 100. Obviously, 10^2 equals 100, therefore 2 is the logarithm of 100. *Logarithms* are used in the processes of multiplication, division, raising to powers and taking roots. The whole number, or integer part of a logarithm is called its *characteristic* and the fractional part, is referred to as its *mantissa*. The characteristic of a number greater than unity is positive and is one less than the number of figures to the left of the decimal. The characteristic of a number less than unity is negative and is one greater than the number of ciphers between the decimal and the first significant figure. A *table of logarithms* gives the mantissas only, the characteristic being determined as indicated above.

Logarithms are also used which have as their base the number 2.718 +. These are called *natural* or *Naperian logs*. The base number is usually represented by the symbol ε (epsilon). The natural logarithm of any number may be found from a table of common logarithms by dividing the common log by the logarithm of 2.718 or simply by multiplying the common log by 2.30259. The symbol l_n is often used for the natural logarithm and the abbreviation *log* without a subscript is usually used for the logarithm to the base 10. (See *Naperian Log*, also *Mantissa*, and *Log Table.*)

LOGARITHMIC CURVE—A curve which has no definite minimum in a decreasing curve, or no definite maximum in an increasing curve. A *logarithmic curve* may be further defined as a curve whose ordinates increase arithmetically while its abscissas increase geometrically. A series of damped electrical oscillations diminish according to a logarithmic law and hence a curve drawn tangent to the successive maximum displacements will be a *logarithmic curve.*

LOGARITHMIC DAMPING—See *Damping.*

LOGARITHMIC DECREMENT—The *Naperian logarithm* (q.v.) of the ratio of any maximum to the next following maximum, with the current in the same direction in a decaying wave train. In other words the logarithm of the ratio of two maxima, one cycle apart. The rapidity with which the oscillations decay depends not only on the resistance of the circuit, but on the inductance as well. The greater the resistance and the smaller the inductance, the more rapid is the damping and the rate at which the oscillations increase. If the resistance, inductance and capacity of the circuit have fixed values, each successive maximum of current is the same fraction of the preceding maximum as the latter is of the maximum immediately preceding it. Thus, if the second maximum is 75 percent of the first maximum, the third will be 75 percent of the second, etc. The numerical value of the rate of decrease in this case is .75 and the natural logarithm of .75 is the *logarithmic decrement* or simply the *decrement.* (See *Decrement*, also *Damped Waves.*)

LOG TABLE—A tabulated arrangement of logarithms which gives the *mantissas* (q.v.) only. The numbers whose logarithms are to be looked up are arranged for convenience in consecutive order. (See *Logarithm.*)

LOMBARDI, DR. LUIGI—Italian radio authority. Dr. Lombardi was born at Dronero, August 21, 1876. He graduated from the Royal Engineering School at Turin, Italy. He was Professor of Electricity at the Zurich Polytechnical School, Zurich, Switzerland, and also at the Royal Polytechnic School, Naples, Italy. Dr. Lombardi published many scientific papers including a study of condensers for transmission and he also invented a special high-tension electrical condenser.

LONGITUDE—The distance east or west of a meridian passing through Greenwich, England, measured in degrees, minutes and seconds.

LOOP ANTENNA—*Loop Aerial*—Also called *Coil Aerial* or simply *Loop*—A receiving or transmitting *aerial* (q.v.) consisting essentially of one or more turns of wire connected to the radio set so as to form a closed circuit. The *loop* acts as a simple inductance coil. The ordinary radio aerial acts as a huge condenser with the aerial system as one plate of the condenser and the *ground* or *counterpoise* (q.v.) as the other. Electromagnetic waves reaching the aerial set up an alternating electromotive force between the wires forming the upper plate of the condenser and the ground or lower plate of the condenser. This action takes place through *electrostatic induction* (q.v.). In the *loop aerial, electromagnetic induction* (q.v.) sets up an induced electromotive force thus causing alternating current to flow to the detecting apparatus. While coil antennas may be used for transmitting, their use in this connection is rather limited. On the other hand, the use of the loop for radio receiving is widespread. The greater the area enclosed



A typical loop antenna.

by a loop the greater the amount of energy it will receive. Loops more than two feet in diameter are usually constructed so as to be collapsible. A common type of loop shown in the illustration is 36 inches high and 28 inches wide. It consists of twelve turns of wire wound in the same vertical plane and held in place by polished hard rubber strips. It has a heavy cast base permitting rotation of the loop as desired. This loop folds up so as to fit into a four inch tube. In another type of loop, sometimes called the *box type*, the wires are wound so as to lie in the same horizontal plane instead of the vertical plane. The use of *Litzendraht* (q.v.) for winding loops has been found to add to their efficiency. Loops are commonly used on *super-heterodyne* (q.v.) sets, *reflex* (q.v.) sets and in some *tuned radio frequency* (q.v.) sets. These latter generally require an extra stage of amplification, although tuned radio frequency sets having only five tubes (detector, two stages of radio frequency and two stages of audio frequency) will operate on a loop and give especially good results when used with the new power tube. As a general rule, it may be stated that any set which will give good results with a loop, will give better results, insofar as distance is concerned, with an outside aerial. For this reason loop operating sets are quite generally constructed with extra binding posts for connecting aerial and ground. The loop is connected directly into the grid circuit, while the aerial and ground are connected to the circuit through an inductance such as an *oscillo-coupler* or antenna coupler. Loops may be used with satisfactory results inside of buildings. Where a compact, portable and selective aerial is desired, the loop is especially useful. The use of the loop, results in a marked directional effect and also has a tendency to reduce *static* (q.v.) and other forms of *interference* (q.v.). Loops are employed in wireless direction finders or *radio compasses* (q.v.) and are also used as aerials in submarine and aeroplane work. Where the loop is used as an aeroplane antenna it may be wound on the wings of the plane or it may be wound on a small frame and placed in the rear of the plane. (See *Coil Antenna*, also *Frame Aerial*.)


Loop Aerial for Directional Reception
Detail of Joint
Binding Posts
Bakelite or other insulating material

A box-type loop.

LOOPS—The points of greatest amplitude in a wave train. Sometimes called *antinodes*. The term *loop* is also used in describing the electrostatic field spreading out from a charged aerial. Each time an aerial is charged (for example by an induction coil) and discharged across a spark gap a group of gradually decaying oscillations is produced in the aerial called a *train* of oscillations. The interval of time which elapses between a flow of the electricity in the aerial in one direction, and a succeeding similar movement is called the *periodic time* and the reciprocal of this is called the frequency. For example, if the periodic time is one-millionth of a second, the frequency is one million. The diagram shows the manner in which *semi-loops* of electric force represented by the dotted lines move away from the aerial which is represented by the short black line.



Semi-loops of electric force represented by the dotted lines moving away from the aerial represented by the short black line.

LORENZ COIL—A form of low loss inductance coil, having an air core and of cylindrical shape, being wound in a single layer, with turns slightly kinked to make the coil self-supporting. (See *Coil, Inductance Coils*, also *Low Loss Coils*.)

LOUD SPEAKER—A sound producing device for converting audio frequency currents into sounds loud enough to be heard by an assemblage of people. Nearly all *loud speakers* utilize an electromagnet in order to directly or indirectly cause a diaphragm to vibrate.



At the left is shown a cone-type speaker having a single diaphragm; at the right one with a double diaphragm.

The audio frequency currents flow through the windings of the electromagnet and the vibrations of the diaphragm correspond to the minute changes and fluctuations of the current thus accurately reproducing sounds. In loud speakers which utilize a metallic diaphragm, the electromagnet directly actuates the diaphragm. In other types, the diaphragm may be of mica, as in the Baldwin unit type, or of parchment or wood as in the cone type speakers. In these speakers, the electromagnet actuates an armature which in turn actuates the diaphragm through a lever action. In certain loud speakers, the electromagnet is of very powerful type and has a very small coil of fine wire attached to a diaphragm but not touching the poles of the magnet. The small coil is connected to the radio set or amplifier and the fluctuating audio frequency currents pass through it. These currents force the coil out of the strong magnetic field in the air gap. In moving, it moves the diaphragm to which it is attached. Speakers of this nature are sometimes called electrodynamic speakers. They are also referred to as power speakers. Such speakers give plenty of volume and in certain makes are reasonably good in tonal quality but they have the disadvantage that the electromagnet must be energized from a source of current such as the storage battery. A loud speaker has been developed in England called the Crystavox for use with crystal sets. This consists essentially of an electromagnetically operated speaker connected with a microphonic relay. The relay is actuated by a storage battery. Its function is to magnify the incoming signals from the crystal set, passing them along with increased strength to the electromagnet of the loud speaker. Still another type of speaker which has been used to a limited extent abroad, dispenses entirely with the electromagnet as the actuating source of diaphragm vibration. In this type, electrostatic principles are involved. An agate cylindrical drum, over which a band of copper or similar metal is wound, is revolved at a uniform rate by a small motor or by clockwork. To one end of the band a diaphragm is fastened mechanically. The other end of the band is secured by a fairly stiff spring. Current from the receiving set is led to the cylinder by means of a brush contact and as the current fluctuates the attraction of the band to the cylinder fluctuates with it and the drag on the diaphragm due to the rotation is increased and decreased. The use of the motor constitutes the most serious disadvantage in this type of loud speaker.

Having discussed the various *types* of loud speakers, from the standpoint of principles of operation, the more important of these will now be considered from the constructional standpoint. The early forms of directly actuated metallic diaphragm, electromagnetic loud speakers consisted essentially of a watch-case telephone receiver, or a pair of receivers attached to a horn. The purpose of the horn was to concentrate and redistribute the sounds caused by the vibration of the diaphragm. One of the first improvements was to modify the shape of the horn so as to make it conform more nearly with correct acoustical principles. Another improvement was to introduce an adjustment by means of which the air gap could be varied. In some cases this was accomplished by moving the magnet closer to the diaphragm and in others by moving the diaphragm itself. This adjustment provided a means of getting greater sensitivity on distant stations (by drawing diaphragm closer to the magnet) and of preventing sticking of diaphragm or rattling, on local stations. The ordinary metallic diaphragm has *one* frequency to which it will respond most strongly. This is called its *resonant* frequency. Special speakers


HIGH AND MEDIUM TONE SPEAKER
LOW TONE SPEAKER
PAPER CONE
TO SET
IDEAL LOUD SPEAKER LAYOUT, COVERING BOTH HIGH AND LOW TONE REGISTERS

A high and a low pitched speaker connected in parallel for simultaneous operation.



A loud speaker of the horn type having curved cast metal neck and spun brass bell.

called *tuned receivers* have been designed in England which permit the resonant frequency to be varied. In one type, the variations of the magnetic field operate a vibrating reed attached to a non-magnetic diaphragm. The resonant frequency can be varied by adjusting the position of the vibrating reed with a set screw. Another method of getting rid of resonant points in diaphragms has been to use corrugated instead of flat diaphragms. In some of these diaphragms the center is left flat, the remainder of the diaphragm being corrugated with concentric circles either evenly spaced or spaced in section at radii bearing a ratio to each other corresponding to prime numbers. In some cases conical diaphragms with corrugated edges are used. The material as well as the shape of the horn have been found to materially affect the sound reproduction. Horns are constructed of metal, fibre, composition, hard rubber, wood, etc. In general the horn should be of a material which will not give out metallic sounds. The tone arm which carries the speaker unit at one end and the horn at the other is usually constructed of cast metal such as a lead alloy or aluminum. The requirement here is that it must be of an acoustically "dead" material. In some cases the speaker unit and sound chamber are concealed in an artistically designed cabinet thus forming a *cabinet speaker*. Loud speaker units are also made especially for use in conjunction with the sound chamber of a phonograph. These are referred to as *phonograph attachments*. They are ordinarily attached to the phonograph tone arm being put in place of the phonograph reproducer. Some phonographs are now made with provision for attachment of the speaker unit without removal of the reproducer. There is also an attachment on the market for use in connection with a phonograph which has provision for conveniently changing over from the reproducer to the speaker unit or vice versa. Cone speakers may be of the single cone variety or of the double cone style. In these speakers a metal rod extends from the magnet armature and is rigidly fastened to the center of the cone. The most common type of cone speaker has a parchment diaphragm. This seems to give excellent reproduction especially for tones in the lower register. Its points of disadvantage are that it is affected to some extent by moisture and temperature change and furthermore seems to bring out static interference more clearly than some other types. Another type of cone speaker uses a teak wood diaphragm. Some of these speakers have a small fastening screw at the point of attachment between the rod and the diaphragm. This is provided so that tension can be removed from the diaphragm during shipment and also if the speaker is to remain in a room where change in temperature may take place. A cylindrical parchment speaker which utilizes the same principle as the cone speaker, has recently been placed on the market. Its chief point of difference is that the parchment is not under tension as in the case of the cone speaker. Large volume loud speakers are provided with power amplifiers which are often an integral part of the speaker itself. One of the most recent loud speakers is contained in a large cabinet and contains apparatus for utilizing ordinary lighting circuits for operating the set and speaker. The power amplifier unit is also contained within the speaker cabinet and the design of the speaker is such that it can handle any volume without distortion. The rectifier is arranged to supply not only the necessary voltages for the power amplifier but also plate voltage for practically any type of receiving set. (See *Horn, Loudspeaker,* also *Distortion.*)



A loud speaker unit used as a phonograph attachment.

LOUDSPEAKER UNIT—The sound reproducing unit attached to the tone arm of the horn type speaker or to the diaphragm of the cone type speaker. Various types of units are described under the heading *Loudspeakers.*

LOW FREQUENCY—See *Low Frequency Current.*

LOW FREQUENCY CURRENT—An alternating current of less than 10,000 cycles. In radio work the alternating currents used are often classified as *low* frequency currents and *high* frequency currents. While there is no fixed value separating high and low frequencies, 10,000 cycles is generally taken as the dividing line. Thus audio frequency currents are considered as low frequencies and radio frequency currents are high frequencies. The term *low frequency* current as applied to power and lighting circuits refers to circuits having frequencies of 25, 60, etc., cycles per second. (See *Current, High Frequency.*)

LOW FREQUENCY IRON CORE INDUCTANCE—A variable inductance having an open-ended iron wire core. This inductance is used with spark transmitters to place the primary transformer circuit in resonance with the alternating current frequency.

LOW LOSS COILS—*Inductance coils* (q.v.) having low resistance and specially wound so as to reduce to a minimum condenser effect and hence dielectric losses. The term low loss has been used rather loosely but for practical purposes coil losses should be taken as referring to self-capacity, often called *distributed capacity* (q.v.) ohmic resistance, *skin effect* (q.v.) in the wire due to the effects of frequency and leakage and absorption in or through the insulating materials upon which the coil is built or with which the wire is covered. While it is impossible to obtain a coil having pure inductance only, it is feasable to design the coil so that the various losses will be reduced to a minimum. Often, it has been found that a design which will greatly reduce one type of loss will result in an increase of another. The illustrations show various types of low loss coils together with curves showing comparative efficiency tests. Figure 1 shows the results of an investigation regarding the distributed



Various types of low loss coils including: 1. Bell wire coil; 2, Naxon; 3, Marco: 4. All-American; 5. Orbit; 6, Turney; 7, Sickles: 8, Aerocoil; 9, Erla; 10, Wavemeter coil; 11, Thorola; 12, Pathe; 13, Freshman; 14, Coast Coil: 15. Summitt; 16, Quadroformer; 17, Bruno.

capacity of various coils. This was obtained by making measurements of the inductance of the coils. If the self-capacity of the coil is very small, the self-inductance will not change perceptibly as the frequency changes. On the other hand, if the self-capacity amounts to anything, the curve showing the relation between inductance and frequency will bend upward as the frequency increases, and the greater the capacity of the coil, the more sharply will the curve bend. The curves shown in Figure 1 do not give any idea of what value the self-capacity may have, but simply show whether the inductance varies or not, which is one method of determining how harmful is the effect of the distributed capacity. The more sharply the curve bends upward the less desirable is the coil. In general, the smaller the size of the wire (for sizes smaller than about No. 16 B & S) the higher the resistance. The larger the wire and the thinner the insulation, the greater is the skin effect. The greatest inductance is obtained for a given amount of wire when the coil has a true cylindrical shape. The skin-effect in multi-layer coils is much greater than in single-layer coils. The effect of coil capacity and absorption or leakage in insulation is small compared with the skin-effect except in multi-layer coils, where the distributed capacity may become very great. To keep the physical size of toroidal coils within practical limits the diameter of the turns must be relatively small, so that many more turns are required to obtain a given inductance.



The efficiency of a coil is indicated by the height of its curves on this graph.



Fig. 1.—The curvature of the graphs indicate the presence of distributed capacity in the coils.



Additional examples of low loss coils: 17, Marwol; 18, Eastern Coil; 19, Workrite; 20, Walbert; 21, Andrews; 22, Bremer Tully; 23, Cotocoil; 24, Kresge Lorenz coil.

LOW TENSION — abbreviation L. T. — A comparatively low voltage. A circuit supplied by a low voltage battery such as the filament circuit of a vacuum tube is called a low tension circuit. In electrical engineering work, any circuit of 600 volts or under is considered to be a low tension circuit.

LUGS—Metal projections used for permanently connecting conductors with electrical apparatus. In one type of lug, the metal is bent over at one end to form a tube into which the conductor can be soldered, while the other end is flat and has a hole drilled to receive any desired terminal.

Typical lugs.

M

MAGNET—A piece of iron or steel having the power to attract other pieces of iron and to attract or repel other magnets. Natural magnets are known as *Loadstones* (q.v.). (See *Electromagnet*, also *Permanent Magnet* and *Temporary Magnets.*)

MAGNET WIRE — Insulated wire for the construction of magnet coils. In radio extremely fine wire is used to wind the coils of the electromagnets used in headsets and loud speaker units. The most common insulation used in radio work for magnet wire is enamel. Other types of magnet wire utilize a single cotton covering, a double cotton covering or a silk covering. (See *Enameled Wire.*)

MAGNETIC ATTRACTION AND REPULSION—The mechanical force tending to draw together two magnetic poles of unlike polarity, or to force apart two magnetic poles of like polarity.

MAGNETIC BLOWOUT—An electromagnet with its pole pieces placed so that the direction of the magnetic field will be at right angles to the movement of the ions in an electric arc. The coil of this magnet is energized in some cases in series with the line and acts to expel or blow out the arc. In the series arrangement, the blow-out action is stronger, the larger the current to be interrupted. For small shunted arcs, permanent magnets are often used. The operating principle of the blowout coil depends upon the fact that in a magnetic field, an electric current tends to move across the lines of force or in other words to cut them. In the illustration, the pole pieces are shown so placed that the general direction of the lines of force is at a right angle to the flow of the ions in the arc. The electromagnetic action causes the arc to move outside the field. This increases the length of the arc, thus rapidly breaking it. Magnetic arcs are used in connection with *keys* (q.v.) used for interrupting a large current, in certain types of *lightning arresters* (q.v.) and also in motor controllers..



A magnetic blowout.

MAGNETIC CIRCUIT — The path traversed by magnetic lines of force. A magnetic circuit may be entirely through iron, as in the case of a closed core transformer or partly through iron and partly through air as in the case of a motor or generator. (See *Line of Force.*)

MAGNETIC COUPLING—See *Coupling.*

MAGNETIC COUPLING TRANSFORMERS—See *Coupling Transformer*, also *Jigger.*

MAGNETIC FIELD — The whole space over which a magnet exerts influence. The space traversed by the magnetic flux. Wherever magnetism is present the space in the immediate vicinity is called a magnetic field. (See *Electromagnetic Induction.)*

MAGNETIC FLOW—The passage of magnetic lines through a magnetic circuit. This term is sometimes used in the place of magnetic flux. (See *Flux Magnetism.)*

MAGNETIC FLUX—Symbol ϕ—The total magnetism present at any cross-section perpendicular to the lines of force. Magnetic flux is analagous to current flow. That is to say, it is convenient to consider a flow of magnetism in the same way as electricity is considered to flow. The unit of magnetic flux in the c.g.s. (centimeter gram second system) electromagnetic system is the *maxwell* (q.v.) or simply the *line*. The unit of magnetic flux in the practical system is also the *maxwell.* (See *Line of Force, Alternator,* also *Flux, Magnetism.)*

MAGNETIC FLUX DENSITY—The number of lines of force per unit cross-sectional area of a magnetic path. The *gauss* (q.v.) is the unit of magnetic flux density. It is equal to one *line* (q.v.) per square centimeter.

MAGNETIC FORCE—The force with which a magnet attracts or repels any piece of iron or steel. The intensity of a magnetic field at any point as measured by the force which it would exert upon a unit magnetic pole if placed at that point.

MAGNETIC FORCE DUE TO CURRENT—A magnetizing force due to current flow which can be determined mathematically for any point in the surrounding medium. Consider any closed stream line of electric current surrounded by a medium having uniform magnetic properties. It can be demonstrated that each elementary length of the current stream line, dl, contributes to the magnetizing force H, at any point T an amount dH =

$$\frac{(I \sin \Theta)\ dl}{r^2}$$

where I is the current flowing along this stream line, r is the distance from T to dl, and Θ (theta) is the angle between r and dl. The direction of dH is perpendicular to the plane of r and dl. The total magnetizing force at T is the vector sum of dH for all the elementary lengths into which the current stream line is divided.



Diagram illustrating method of determining magnetic force due to current.

MAGNETIC HYSTERESIS—The opposition which minute particles of a magnetic material offer to being magnetized or to having their magnetization changed. It is sometimes referred to as molecular friction or as *magnetic lag.* (See *Hysteresis.)*

MAGNETIC INDUCTION—See *Induction,* also *Diamagnetic Material.*

MAGNETIC INDUCTIVE CAPACITY—symbol μ (mu)—Also termed Magnetic Inductivity—Names sometimes used instead of *Permeability* (q.v.). The ratio between the number of lines of force per unit area passing through a magnetizable substance and the magnetizing force which produces them. Stated another way, it is the ratio of flux density to magnetizing force. It can be considered as a measure of the ease with which magnetism passes through any substance. The magnetic inductive capacity of air is taken as unity. The term magnetic inductive capacity is analogous to *specific inductive capacity* (q.v.) which is the ratio of the dielectric constant of a material to that of a vacuum.

MAGNETIC INTERRUPTER—A device energized by an electromagnet for interrupting a circuit. (See *Interrupter.)*

MAGNETIC KEY—An electromagnetic adjunct to a wireless transmitting key for reducing or eliminating sparking due to the self-induction of the heavy currents which are interrupted. A form of magnetic key is shown in the illustration. Underneath the lever arm of the key is placed a spring to which an iron armature C and a platinum contact A_1 are attached. If the key and hence the spring are pressed down contact A_1 touches contact A_2 and the path of the current is completed. The current passes not only through the key, but also through the winding of the electromagnet. If the key is released so as to move upward, the contact A_1 still remains touching A_2, as the magnetic action due to the current continues to hold down the armature C and hence the spring with the contact A_1. Not until the alternating current reaches a zero value is the armature released. This releases A_1 from A_2, at an instant of zero current and hence there is no spark.



A magnetic key.

MAGNETIC LEAKAGE—Magnetic flux which serves no useful purpose. There are no substances which will prevent the passage of magnetic flux. This fact introduces a certain amount of difficulty into practical magnetic circuit calculations, since it is impossible to confine all the flux into a predetermined magnetic path. Since there is no magnetic insulator there will always be a certain amount of *leakage flux.* However this can be reduced to a minimum by proper design of the magnetic circuit. Magnetic Leakage is also referred to as *Stray Flux.*

MAGNETIC LINES OF FORCE—See *Line of Force,* also *Electromagnet.*

MAGNETIC MOMENT—The product of the strength of pole of a magnet and its virtual length. The torque exerted by a magnetic field upon a magnet depends upon the magnetic moment.

MAGNETIC NEEDLE—A light, thin steel magnet mounted on a pivot or suspended so as to be free to move. It takes a position pointing to the magnetic north.

MAGNETIC POLES—Points on a magnet where the lines of force leaving or entering the iron are concentrated. In a magnetic needle, that end which tends to point north is called a north or positive pole; that end which tends to point south is called a south or negative pole. A unit magnetic pole is defined as one which, when placed at a distance of one centimeter from a like pole of equal strength, will repel it with the force of one dyne. The north magnetic pole of the earth is situated in latitude 70 North and longitude 97 West. The south pole is located at latitude 70 South and longitude 102 East. It should be noted that the magnetic poles do not coincide with the geographical poles. (See *Induction, Magnetic.)*

MAGNETIC PROPERTIES—Materials are classified according to whether or not they offer a good path for the magnetic lines of force. Substances of comparatively low *reluctance* (q.v.) are termed *magnetic.* They are also often referred to as *ferro-magnetic.* They include iron, steel, nickel, cobalt, manganese, chromium, magnetite, certain alloys of copper, manganese and aluminum (called Heusler Alloys), and certain other oxides. The magnetic laws governing these substances can best be set forth by means of magnetization curves. Substances having high reluctance are termed *non-magnetic.* For commercial purposes, air is the most important non-magnetic substance. However, practically all substances, with the exception of the ferro-magnetic ones, follow the same magnetic laws as air. While the reluctance of a non-magnetic substance is constant, the reluctance of magnetic substances varies, as the amount of *flux* (q.v.) in the substance changes. Although air and all other substances, with the exception of the ferro-magnetic ones are classed as non-magnetic substances, and are poor conductors of magnetic flux, when compared to iron, etc., nevertheless they are by no means magnetic insulators. There are no substances which will absolutely prevent the passage of magnetic flux. (See *Ferro-Magnetic Substances.)*

MAGNETIC PYRITES—See *Pyrites.*

MAGNETIC STORM—Sudden and irregular variations of the earths magnetic field. Magnetic storms are sometimes coincident with the appearance of sun spots. These storms often disrupt telegraph service and also cause much interference with radio communication.

MAGNETISM—A phenomena exhibited by certain materials which is characterized by the attraction or repulsion of soft iron or of conductors carrying electricity. Magnetism is one of the manifestations of electricity, since a current flow is always associated or linked with a *magnetic field* (q.v.). (See *Free Magnetism, Magnet,* also *Magnetic Properties.)*

MAGNETISM, LAWS OF—Like magnetic poles repel one another; unlike magnetic poles attract one another. The force exerted between two magnetic poles is proportional to the product of their strengths and is inversely proportional to the square of the distance between them. (See *Like Poles.)*

MAGNETITE — symbol Fe_3O_4 — A mineral composed mainly of magnetic oxide of iron. When found in magnetized condition it is known as a *loadstone* (q.v.) or a natural magnet. It is a black brittle substance having a specific gravity of 5.2.

MAGNETIZATION—(also spelled *Magnetisation*)—The process of communicating magnetism. The act of rendering iron, steel, etc., magnetic. According to Ewing's theory, a substance which is magnetized has its molecules rearranged so that they assume symmetrical positions, each molecule lying in line with or parallel with its neighbor. In this rearranged position each molecule adds its separate magnetic force to every other one and the cumulative effect of this is that the substance exhibits the property of a magnet. (See *Demagnetization.*)

MAGNETO GENERATOR—A small generator consisting essentially of an armature rotating between permanent magnets, usually of the horse-shoe type. Magnetos are mainly used for motor ignition, medical coils, bell ringing and for firing high explosives. (See *Intermittent Current.*)

MAGNETOMOTIVE FORCE OR DIFFERENCE OF MAGNETIC POTENTIAL—abbreviation m.m.f.—The force causing magnetic flow. *Magnetomotive force* is the magnetic cause, while *flux* (q.v.) is the magnetic effect, just as in electrical terms, *electromotive force* (q.v.) is the cause and current is the effect. The c.g.s. (centimeter gram second) unit of magnetomotive force is the gilbert (q.v.). The unit ordinarily employed in practical calculations of the magnetic circuit is the *ampere-turn* (q.v.). (One ampere-turn is equal to 1.2566 gilberts.) An ampere-turn consists of a current of one ampere flowing through one complete turn of a conductor. The expression "turn" means that the conductor is wound in a solenoid. That is to say, it is wrapped around a core which may consist of air or of any other substance. The same magnetic field will result from ten ampere-turns consisting of ten amperes flowing through one turn, as from ten ampere-turns consisting of one ampere flowing through ten turns. (See *Force, Magnetomotive.*)

MAGNIFIER, OR RELAY—An apparatus for intensifying the variations of a current. The term *magnifier* has been incorrectly used for *amplifier* (q.v.). One type of *magnifier* used in radio is the microphonic relay (see loud speaker) by means of which the minute currents in a crystal set can be magnified so as to actuate a loud speaker. In the ordinary telephone repeater, a microphone is acted upon by the receiver of the first line circuit so as to introduce a local circuit which acts inductiveley on the second line wire. Relays are also used in wire telegraphy to boost weak line currents by means of strong local batteries. (See *Relay.*)

MANTISSA — The decimal part of a *logarithm* as differentiated from the integral part or characteristic. For example in the logarithm 1.23578, 1 is the characteristic and the decimal .23578 is the mantissa. (See *Logarithms.*)

MARBLE—The name given to any limestone sufficiently compact to permit being polished. Pure marble is white, the presence of oxides giving the different colors. Marble is used extensively for switchboard work and when so used must be free from metallic veins. Where circuits carrying 1000 volts or more are used, the switchboard should be saturated with an insulating varnish and baked. Inasmuch as the marble shows oil spots, it is sometimes stained black and given a finish called a *marine finish.*

MARCHANT, EDGAR WALFORD. British radio expert. Born in 1876, he was educated at University School, Hastings, and Central Technical College and London University. In 1897 he was appointed superintendent of the laboratory and workshops of Lord Blythswood at Renfrew, where he carried out many experiments in wireless telegraphy. He became chief assistant at Finsbury Technical College, 1900, under Professor Silvanus P. Thompson, and the following year was appointed lecturer in electro-technic at University College, Liverpool. In 1903 he was appointed the first professor of electrical engineering at the university.

Marchant was for some time closely associated with W. Duddell in developing the oscillograph, and the two read a joint paper on the study of the electric arc by the aid of oscillographs to the Institution of Electrical Engineers, of which institution Marchant became vice-president. He is also a vice-president of the Radio Society of Great Britain. He has written many papers on radio, and contributed an article to the proceedings of the Royal Society on the magnetic behaviour of iron under oscillatory discharge of a condenser.

MARCONI FILINGS COHERER—Also called Marconi Coherer—A detector of electric waves consisting of fine nickel and silver filings contained in a suitable glass tube between two electrodes consisting of two silver plugs. These two plugs are connected to platinum wires brought out through the sealed ends of the tube, which is carefully exhausted of its air. The metallic filings in a loose condition have feeble conductivity for the current from a single dry cell. If a very weak electric oscillation is passed through the coherer, the filings cling together or cohere and hence conduct electricity better and they will then pass sufficient current from a single dry cell to operate a telegraphic relay. To bring these filings back to a non-conductive condition, the tube is tapped by an electromagnetic tapper, similar to an electric bell with the gong removed. The Marconi coherer is now obsolete. (See *Coherer.*)



The Marconi filings coherer.

MARCONI, GUGLIELMO—Italian-Irish radio pioneer. Guglielmo Marconi was born at Bologna, Italy, April 25, 1874. and was educated at the Leghorn Technical School, under Professor Rosa. From his earliest years he was keenly interested in communication by means of Hertzian waves, and began his brilliantly successful series of experiments in June, 1895. These first experiments were carried out on his father's estate near Bologna. Marconi soon found that the Hertzian form of resonator gave only feeble signals at a distance, and he substituted a vertical wire, with the result that in 1895 he was able to transmit signals to a distance of one and a half miles. About the same time he improved the Branly coherer, which he was using as a detector, and invented an electric tapping device to decohere the filings.

This early apparatus of Marconi, from which has sprung the far-flung wireless chain of to-day, consisted of a coherer, a relay, a decoherer, and a Morse printing instrument, all working from storage batteries. Between the coherer and the relay Marconi interposed choke coils, and this had a very marked effect on the receptivity of his set. By close attention to the details of his system he was able to carry on his signals at greater ranges than had up to this time been accomplished by other experimenters.

The transmitting apparatus used by Marconi in these early efforts consisted of a large spark gap to which the aerial and earth wires were connected. The high-tension current for the spark was provided through an induction coil from batteries. The spark gap consisted of a ball discharger comprising four brass balls. The two middle balls were separated by a small space filled with vaseline oil, the actual spark jumping from the two end balls to the middle ones and through the vaseline, producing a high-frequency spark.

Marconi came to England in 1896, where he took out the first patent ever granted for a practical system of wireless telegraphy. He made a number of experiments at Westbourne Park, and demonstrated his system before Sir William Preece and other high officials at the Post Office. In the following year he increased the range of his set to nine miles using a 29 in. spark coil and kites to raise the vertical aerials. In July, 1897, in demonstrating before the Italian Government, he covered 12 miles between warships, and he began to instal a number of his sets for lighthouses, and the success of his experiments led to stations being erected for the corporation of Trinity House.

Guglielmo Marconi.

In 1899, the first proof of the advantages of wireless over other forms of communications came with the saving of the lives on board the ship R. F. Matthews, which ran into the East

Goodwin lightship. The latter was equipped with one of Marconi's transmitting sets and was able to communicate with the South Foreland lighthouse and summon assistance.

The genius of Marconi lies not so much in his inventions, as in his far-sightedness in being the first man to realize the immense commercial possibilities of radio, and to make the best use of all the scientific effort of his time to further the object he had in view.

Marconi has received innumerable honors from all countries. He holds the honorary degrees of universities all over the world, and the freedom of a large number of cities. In 1909 with Professor Braun, he was awarded the Nobel Prize for Physics, and in 1914 he was given the Honorary Knighthood of the Grand Cross of the Victorian Order. He has been awarded the Albert Medal of the Royal Society of Arts, the Gold Medal of the Institute of Radio Engineers of New York, the John Fritz Gold Medal for the invention of wireless telegraphy, and the Franklin Gold Medal of the Franklin Institute. He was the Italian delegate to the Peace Conference, and signed on behalf of Italy. He is chairman of the board of directors of the Marconi Company.

MARINE TYPE CHARGING PANEL—A switchboard equipped with resistance coils, carbon filament pilot lights, voltmeter and necessary switches. Manipulation of the switches allows the battery to be placed on charge or on the line. By throwing a switch on this board, it is also possible to work the wireless transmitter either from the ship's generator or from the storage battery.

MASS—The quantity of matter which a body contains. Physical quantities such as force, velocity, etc., are expressed in terms of length, *mass*, and time. The unit of length is the centimeter; of mass, the gram; and of time, the second. Hence this system of measurement is known as the C.G.S. (centimeter gram second) system. The gram is equal to 15.432 grains and represents the mass or quantity of a cubic centimeter of water at 4 degrees centigrade.

MASTER-OSCILLATOR SYSTEM—A radio telephone transmitting circuit in which a small extra *audion* (q.v.) is used to supply the power to excite the grid circuit. This extra oscillator or exciter is referred to as the master-oscillator. The master-oscillator system has several advantages over the self-excited system. Changes in antenna constants, such as might be caused by a swaying aerial or *lead-in* (q.v.) do not affect the transmission where the former system is used. In addition the master-oscillator system is more convenient to work with and the adjustment for maximum output for different wave lengths and antenna resistances is more easily made.

MASTER-OSCILLATOR SYSTEM AMPLIFIER—In the master-oscillator system, the power tube acts as an amplifier of the power supplied by the small extra exciting, or master-oscillator. The exciter must develop sufficient power to supply the losses in its own oscillating circuit and those of the grid circuit of the power tube.

MASTS, ERECTION OF—High powered stations generally use latticed steel masts. In some cases tubular metal masts in telescoping sections are used. Wooden masts have been used to quite an extent. For portable outfits, these are made in sections which can be fitted together like a fishing rod. Guy ropes or wires are necessary in practically every instance. In erecting a mast, it is usual not to make the installation too rigid, but rather to allow some freedom of movement so that the mast may sway slightly in the wind. Where a one-wire aerial is being erected this may be fastened to any support available. In marine construction, the ship's masts are used to support the aerial, the wires being stretched between the two booms or spreaders. from which halyards run to the masts. (See *Aerial.*)



A method of erecting a tall mast using tackle and hoisting pole.

MATCHED IMPEDANCES—Circuits balanced or matched so that the total impedance of one circuit will equal the impedance of another circuit with which it is coupled. (See *Impedances, Matched.*)

MAXWELL—symbol φ—The unit of *magnetic flux* (q.v.). It is also known as the *line* (q.v.). One maxwell is equal to one line of force. (See *Flux Density*, also *Kiloline.*)

MAXWELL'S CORKSCREW RULE—If the direction of travel of a right-handed corkscrew represents the direction of current in a straight conductor, the direction of rotation of the corkscrew will represent the direction of the magnetic lines of force.



Illustration of Maxwell's corkscrew rule. When current flows from C to D, magnetic lines encircle the wire in the direction of the curved arrow MN.

MAXWELL'S LAWS—The magnetic fields surrounding parallel currents in the same direction will react upon each other in such a way that the conductors will tend to move together. In the case of parallel currents in opposite directions, the fields between the two conductors will be in the same direction and will merge together, thus tending to push the conductors apart. The magnetic fields around two conductors at an angle will react upon each other in such a way as to tend to bring the conductors parallel, and with the currents flowing in the same direction.

MAXWELL'S LAW OF MOTOR ACTION—A conductor carrying a current whose direction of flow is at right angles to a magnetic field, will tend to move out of this field.

MAXWELL'S RULE—Every portion of a circuit is acted upon by a force urging it in such a direction as to make it enclose the greatest possible number of lines of force.

MAXWELL TURNS—The deflection value in a ballistic galvanometer or *fluxmeter* (q.v.). This depends upon the number of turns in the exploring coil and the instantaneous value of the flux in maxwells linked with this coil. (See *Grassot Fluxmeter.*)

McLACHLAN, NORMAN W.—British radio authority. Born at Longtown, Cumberland in 1888, and educated at Carlisle Grammar School and the George Watson and the Heriot Watt Colleges, Edinburgh, and Liverpool University. He was appointed lecturer in Engineering and Mathematics at Newcastle-on-Tyne in 1909. In 1913 McLachlan was appointed supervisor of classes in engineering subjects in the Liverpool Technical Institutes, and after the Great War, during which he was engaged in aeronautical research and the study of anti-submarine devices, he made a special study of magnetos at the National Physical Laboratory, Teddington. Appointed research engineer to the Marconi Company, he is the author of many papers on wireless and electrical subjects in the journal of the Institution of Electrical Engineers and other scientific journals, including those on Characteristic Curves of a Poulsen Arc., the Magnetic Behaviour of Iron at very High Frequencies; and Theory of Iron-cored High Frequency Transformers. He has taken out a number of radio patents.

MEASUREMENT OF INDUCTANCE—Some methods of measuring inductance (also applicable to the measurement of *capacity*) are various bridge methods; by measuring the voltage, current, power, and frequency; and by the wave meter method. Connections in one bridge method for measuring inductance are similar to those in the ordinary *Wheatstone Bridge* (q.v.). A coil having a known inductance is balanced against the inductance to be measured. A device called a *Secohmmeter* is in use to increase the sensibility of bridge measurement of inductance. The Secohmmeter serves the purpose of making an alternating current to use in measurements of self-induction and of commutating such portion of this current as flows in the galvanometer circuit to a direct current. When a source of alternating current of known frequency is available the following method is convenient. Place the inductance across the alternating current mains, measure the power absorbed, the current flowing, the voltage across the unknown inductance and the frequency of the circuit. Then the inductance L is equal to the reactance, x, divided by

2 π times the frequency. Expressed as a formula

$$L = \frac{X}{2\pi f} = \frac{\sqrt{\left(\frac{E}{I}\right)^2 - \left(\frac{\text{Power}}{I}\right)^2}}{2\pi f}$$

The inductance L should be expressed in henries. This method gives results of fair accuracy but is not adapted to measurements of low values of inductance. Small inductances are more usually measured by bridge methods. In the wave meter method, a condenser is discharged through a spark gap in a circuit containing a known capacity and by means of a wave meter measuring the wave length. The expression for the number of oscillations in a closed circuit containing both inductance and capacity is given by the formula

$$n = \frac{1}{2\pi\sqrt{CL}}$$

and the wave length is equal to the velocity of propogation divided by the number of waves and calling λ the wave length we have

$$\lambda = V \text{ times } 2\pi\sqrt{CL}$$

In this last equation everything is known but the inductance which can be calculated. (See *Inductance*, Measurement of.)

MEASUREMENT OF WAVE LENGTH—The usual method of measuring an unknown wave length is by means of a wavemeter. Other apparatus required in this connection is a hot wire ammeter indicator in a coupled circuit, or crystal detector and telephones. Also an antenna excited oscillating circuit supplied by electron tube. A wavemeter placed in inductive coupling with a coil or antenna carrying radio current will show decided increase of current in its own coil and condenser when it is tuned to resonance with the source. The wave length is read directly from the wavemeter setting for resonance or from a calibration curve. A receiving set can be used to measure the wave lengths of received waves if it is first standardized in terms of wave lengths. The operator listens in through the head set attached to the receiving set. As the wavemeter condenser knob is turned the loudest sound is heard when the wavemeter circuit is tuned to the same wave length as that for which the receiving set is adjusted. The wave length is then read from the wavemeter scale or calibration curve. Continuing in this manner, the receiving circuit can be calibrated as a wavemeter by setting it at many different adjustments and reading the wave lengths at resonance each time. The wave length of the waves emitted by an antenna, when no added inductance or capacity is inserted in the antenna circuit, is known as its fundamental wave length. For a single vertical wire grounded antenna the fundamental wave length is slightly greater than four times the length of the wire. The approximate constant often used is 4 2 and this applies also to "L" or "T" type aerials with vertical lead in wire, the total length being measured from the transmitting apparatus up the lead-in wire and over to the end of the flat top. It is of course, more accurate to measure the wave length radiated from an antenna directly by use of a wavemeter. The wavemeter coil needs merely to be brought near the antenna or lead-in wire and the condenser of the wavemeter adjusted to give maximum current in the wavemeter indicator. The wave length corresponding to the wavemeter setting is then the length of the waves radiated by the antenna. The fundamental wave length of the antenna may be determined by gradually decreasing the number of turns in the *loading inductance* (q.v.), measuring the wave length for each setting of the loading coil and plotting a curve showing the wave length coresponding to the various numbers of turns of the loading coil. The fundamental, then, is the wave length corresponding to zero turns and is found at the point where the extension of the curve cuts the wave length axis. (See *Measurement of Inductance*, also *Formula.*)

MECHANICAL MIXTURE— A mixture of two or more elements which leaves them essentially the same. This is sometimes incorrectly called a mechanical compound. Sugar and sand mixed together give an example of a mechanical mixture. A *chemical compound* is formed when two or more substances combine chemically to form another substance having different characteristics. Thus iron filings and sulphur can be combined to form a third substance unlike either of the original two.

MEG OR MEGA—symbol M—The prefix placed before the name of a unit to denote one million times (10^6) that unit, as for example *megohm* (q.v.) *mega-volt, megerg*, etc.

MEGGER—An instrument for measuring insulation resistance or in general any resistance by the direct deflection of a pointer on a scale. The "Evershed" type is made in two forms (1) the *megger* insulation testing set and (2) the bridge-megger testing set which combines the functions of type (1) with those of a *Wheatstone Bridge* (q.v.). Both types consist of an ohmmeter of the moving coil type combined in one box with a hand driven generator for providing the necessary testing voltage and current. When the handle of the generator is not being turned, the pointer is entirely free and will rest anywhere on the scale. The general principles underlying the construction and operation of the megger are shown in the illustration. As can be seen, the megger is a combination of a *magneto generator* (q.v.) shown at the right, with an ohmmeter shown at the left, in a magnetic circuit common to both and consisting of two pairs of field poles braced by strong bar magnets, NS, NS, and forming two bi-polar field magnets in series. In the right hand one, and rotated by a folding handle and spur gearing D, is the armature of the generator, with its brush gear B, and terminal bars marked + and —. In the left hand field is the current coil A, pressure coil P, and compensating coil C of the ohmmeter, connected to resistances Q and R, a *guard plate* G, and the only two external terminals L and E (marked Line and Earth on the actual instrument). The bridge-megger testing set is available for use both as an insulation testing set and as a specialized Wheatstone Bridge. It differs from the ordinary megger in outward appearance only by the addition of two pairs of terminals and of two switches, one of which is the *ratio* switch of the Wheatstone Bridge and the other one is a two-way change over-switch. This latter when set to "Megger" prepares the instrument for measuring insulation resistance or high metallic resistance by coupling the two windings of the constant voltage generator in series and making the two front terminals, marked Line and Earth, the only two available for connection. When the change-over switch is set to "Bridge" the instrument is ready for Wheatstone Bridge work, the two windings of the generator now being connected in parallel in order to increase the current obtainable from it. In this case the ohmmeter part is changed into a galvanometer for the bridge and the arms of the bridge are switched into their appropriate places in the circuit and connected to the terminals marked R and X at the end.



A diagrammatic illustration of a megger.

MEGOHM—One million ohms. This unit is usually employed in the measurement of insulation resistance. It is also used in measuring *grid leaks* (q.v.), etc. See *Ohm*, also *Begohm.*)

MEGOHMITE, also spelled Megohmit—An insulating material similar to micanite, obtainable in several forms, one of which is known as *hard megohmite* and is made of thin sheets of mica built up of shellac. *Flexible megohmite* consists of sheets of mica stuck together by vegetable adhesives. Flexible megohmite covered with Japanese paper is called mica paper while flexible megohmite covered with linen, is called *mica linen.*

MEISSNER, ALEXANDER.— Austrian radio expert. Born at Vienna, 1883, he was educated at the Technical High School and University of Vienna. He joined the Telefunken Company in Berlin, 1907, and is one of the leading authorities in Germany on radio. To him is due a large number of wireless inventions, including the Telefunken compass, musical quenched sparks, interference preventers, the direct current cathode valve relay for the reception of Morse Code, etc. In 1913 he invented the generation of oscillations by means of the three-electrode valve. He holds many patents, including spark gap for impulse excitation, quenched-spark signalling in conjunction with G. Von Arco, etc., and he is the author of many papers for scientific journals and societies on the subject.

MERCURY ARC RECTIFIER (MERCURY VAPOR CONVERTER)—A device for changing alternating current to direct current, which depends for its action upon the unidirectional conductivity of the mercury arc in an exhausted vessel. An idea of the principle of operation of the mercury arc rectifier may be obtained from the illustration. Assume an instant when the terminal H of the supply transformer is positive, the anode A is then positive and the arc is free to flow between A and B, B being the mercury cathode. Following the direction of the arrows still further, the current passes through the lead J, through the reactance coil E and back to the negative terminal G on the transformer. A little later when the impressed electromotive force falls below a value sufficient to maintain the arc against the counter electromotive force of the arc and the lead. the reactance E which heretofore has been charging, now discharges, the discharge current being in the same direction as formerly. This serves to maintain the arc in the rectifier until the electromotive force of the supply has passed through zero, reverses and builds up to such a value as to cause A' to have a sufficiently positive value to start an arc between it and the mercury cathode B. The discharge circuit of the reactance coil E is now through the arc A'B, instead of through its former circuit. Consequently the arc A'B is now supplied with current, partly from the transformer and partly from the reactance coil E. The new circuit from the transformer is indicated by the arrows enclosed in circles. The amount of reactance inserted in the circuit reduces the pulsations of the direct current sufficiently for all ordinary commercial purposes. The mercury rectifier is used in small sizes for charging storage batteries from alternating current circuits and in the larger sizes for operating direct current arc lamps from alternating circuits and also in electric traction work in the place of rotary converters in the substations or even on the train itself.



Illustration showing action of mercury arc rectifier.

MERCURY INTERRUPTER (MERCURY JET INTERRUPTER)—A contact breaker in which contact is made between moving metallic contacts and a jet of mercury provided by a small centrifugal pump driven by the same motor as the contacts. When the primary winding of an induction coil is supplied with a continuous current it is necessary to interrupt the current in order that a secondary voltage shall be induced in the secondary winding. The mercury interrupter offers a satisfactory method of accomplishing this. In one type of mercury interrupter a stream of mercury is forced from a jet against a metal plate. The stream of mercury is interrupted by a toothed wheel of insulating material so that the electrical circuit is periodically made and broken between the mercury and the metal plate. In some forms of mercury interrupters, the jet itself revolves, the mercury impinging against a fixed metal plate. The mercury interrupter is used in operating X-ray bulbs from an induction coil where the source is direct current. A form of mercury interrupter is shown in the illustration. A is a tooth-shaped wheel made of insulating material. This wheel is driven by a small motor and the number of revolutions can be varied within wide limits. A small centrifugal pump forces the mercury upon the jet B, while the revolving wheel A interrupts the contact of the mercury with the plate C. The wheel A can be raised or lowered, thereby enabling the duration of contact of the mercury with the plate to be varied without altering the number of interruptions in a given time.



A type of mercury interrupter.

MESH GROUPING—A method of connecting coils in a polyphase circuit whereby they form a closed circuit and have the line wires attached to the points of junction between the coils. The term mesh is used interchangeably with delta. (See *Delta Connection.*)

METER—An instrument used to make measurements. (See *ammeter* or *amperemeter, double range meters, integrating wattmeter, voltmeter, wavemeter, wattmeter.)*

METER (*Measure*)—A unit of length in the *metric system* (q.v.). One meter is equal to 100 centimeters or 39.37 inches. It is equal to the length of a standard platinum bar, kept in Paris, and representing approximately a ten-millionth part of a quadrant of the earth's meridian measured from the equator to the pole through Paris. Wireless waves are measured in meters. The length of a wave is the distance, usually measured in meters between two points in the successive waves where the disturbance is at a maximum or at a minimum or between any two points of equal disturbance. There is a fixed relationship between the length of a single wave, the frequency of oscillation and the velocity of the wave. Thus if 3,000,000 waves pass a given point in one second, each wave must be 100 meters long, since the velocity of radio waves is equal to 300,000,000 meters per second.

METER-AMPERES—The product of the antenna current in amperes at the point of maximum current and the antenna effective height in meters, for any radio transmitting station. It constitutes a factor for indicating the radiating strength of radio transmitting stations.

METRIC SYSTEM—A system of measurement in which the meter is the fundamental unit of length and in which all the units both fundamental and derived are divided decimally and higher units are formed in multiples of ten. (See *Centimeter Gram Second.)*

MFD—Abbreviation for *Microfarad* (q.v.)

MICA—An anhydrous silicate of aluminum and potash or sodium. Mica has very high insulating qualities and can withstand high temperatures. Mica obtained in the natural state is separated into laminations which are sorted and graded. These are then cemented together to form plate or flexible mica of any desired thickness or purity. Mica is used in radio work as the dielectric of small fixed condensers. It is also used as the sound producing diaphragm in certain types of head sets and *loud speakers* (q.v.).

MICABOND CLOTH—India sheet mica faced on one side with muslin and on the other side with Japanese insulating paper bonded together with a special binder. It is used for insulating field coils and transformer coils.

MICABOND PAPER—India sheet mica faced on one side with Japanese insulating paper of one grade and on the other side with paper of a different grade.

MICABOND PLATE—Mica sheets bonded together with orange shellac. Various grades of plate are made some of which are used for magnet spools, others for insulating of commutator segments, while still others are used in electric irons.

MICANITE—A form of reconstructed mica. Canadian amber mica and white India mica are used.

MICRO—A prefix placed before the name of a unit to denote one-millionth part of that unit, as for example *microfarad* (q.v.).

MICRO-AMPERE—One-millionth of an ampere. A unit used in measuring extremely small currents. (See *Ampere.)*

MICROFARAD—abbreviation Mfd.—A unit of electrical capacity equal to one-millionth of a farad. Since the farad is too large for most practical measurements, the microfarad is generally used. (See *Farad,* also *Jar.)*

MICROHM—A unit of resistance equal to one-millionth of an *ohm* (q.v.).

MICROMETER—An instrument for making minute measurements. Usually controlled by an accurate screw of fine pitch.

MICROMETER SPARK GAP—A minute adjustable spark gap of about four-hundredths of an inch placed in the aerial circuit of a multiple tuner to allow heavy charges to pass readily to earth by sparking across its points.

Courtesy of Western Electric Co.

An example of the microphone used in modern broadcasting.

MICROPHONE—A sound magnifier. The ordinary form of microphone consists essentially of a diaphragm set in vibration by the sound waves and causing by its motion variation in the resistance of a mass of loosely packed carbon granules. This variation in resistance causes corresponding variations in the current through the instrument so that at every instant the form of the current corresponds to the variations in sound. This type of microphone is often referred to as a *Carbon Microphone*. The telephone transmitter is a form of microphone, and the microphone (nicknamed *Mike*) used in radio broadcasting is merely a larger and more sensitive variation of the same instrument. (See *Electromagnetic Microphone.*)

MICROPHONE, CARBON—See *Microphone*, also *Granular Carbon*.

MICROPHONE TRANSMITTER—See *Microphone*.

MICROPHONIC JOINT—A loose contact between two solid conductors, so mobile that feeble vibrations vary its resistance.

MICROPHONIC RELAY—An instrument for magnifying the variations of a given current by passing it through an electromagnet that acts on the diaphragm or reed of a microphone. The resistance variations are repeated in the current produced by a constant voltage in a circuit in series with the *microphone* (q.v.). In general a microphonic relay can be described as a microphone combined with a telephone so that a message transmitted over the telephone is repeated by the microphone over another line.

MIL—A unit of length equal to one-thousandth part of an inch.

MIL-FOOT—A wire one foot long having a diameter of one mil. Unit resistance may be measured in *ohms* (q.v.) per mil-foot. This refers to a conductor having a cross-sectional area of a *circular mil* (q.v.) and a length of one foot.

MILLI—The prefix placed before the name of a unit to indicate one-thousandth part of that unit, as for example *milli-ampere* (q.v.).

MILLI-AMPERE—One-thousandth of an *ampere* (q.v.). Sometimes abbreviated to *milli-amp.*

MILLI-MICRO—A prefix denoting one thousand millions. (10^{-9}). The term *Billi* is an alternate prefix.

MILLI-VOLT—One-thousandth of a volt.

MILS, CIRCULAR—See *Circular Mils.*

MIRROR GALVANOMETER—A galvanometer for measuring very small currents which utilizes a reflected beam of light for a pointer. In one type of mirror galvanometer a fixed nearly circular magnet is used and a coil of wire is suspended in its field. When the current flows through the coil it tends to turn the coil so as to set its axis in the direction of the magnetic force. This movement can be observed by means of a beam of light reflected from a mirror fixed to the coil. (See *Galvanometer.*)

MINERALLAC—An insulating compound made in several different grades all of which are impervious to water and show no alkali or acid reactions.

M.M.F.—Abbreviation for *Magnetomotive force* (q.v.).

MODULATED CURRENTS—Currents which have their amplitude periodically varied as in the case of the carrier current used in radio telephony which is varied or modulated in accordance with the vibrations of a microphone. If a sound wave actuates a microphone, its inward and outward displacement, varying the resistance in the aerial circuit, results in a high frequency current in the aerial of variable amplitude, called a modulated high frequency current. The illustration shows an extremely simplified diagram of the apparatus in a broadcasting station. The initial impulse that starts a radio signal towards the receiving set is furnished by the voice of the speaker or singer or by some other sound originating in the studio. This sound strikes the microphone, the operating element of which is a thin metal disk or diaphragm. The sound waves cause this diaphragm to vibrate. In doing so, the disk causes changes to take place in the electrical circuit. Pulsations of current are set up, the pulsations corresponding in strength to the variations of the spoken word, music or other sound as the case may be. These fluctuations are quite weak when they first come from the microphone and therefore they must be strengthened. They go through what is known as a voice amplifier which utilizes vacuum tubes to make the current stronger. The next piece of apparatus to consider is the *oscillator* (q.v.). This consists of one or more vacuum tubes, connected in a circuit of such a type that the tubes, when lighted and properly furnished with a high voltage direct current, will generate another current, alternating in character, which is said to be oscillating at radio frequency. Upon this current so generated, the voice current is impressed or super-imposed. This process is called *modulation* (q.v.). The current from the oscillator is known as the *carrier wave* (q.v.) current and when voice currents are impressed upon it, it is known as modulated radio frequency current. This current flows in the aerial and there sets up radio waves.

MODULATION—Variation of current or wave form to conform to sound waves or to other predetermined forms. Various forms of modulation are dot and dash modulation, chopper modulation, buzzer modulation and *speech modulation* (q.v.). (See *Distortion*, *Double Modulation*, also *Modulation Frequency Ratio.*)



Graph of a modulated carrier wave.

MODULATION, DOUBLE—See *Double Modulation.*

MODULATION FREQUENCY RATIO—The ratio of modulation frequency to wave frequency. An alternating current is said to be *modulated* when the amplitude of its oscillations is varied periodically. The frequency at which the variations occur, that is to say the *modulation frequency* is necessarily less than the frequency of the alternating current which is being modulated. The nature of the variations may assume practically any form. As examples, there are dot and dash modulation, chopper modulation, buzzer modulation and *speech modulation* (q.v.).

MOLECULE—The smallest group of *atoms* of an element or compound which can exist by themselves. A familiar analogy states that if a drop of water could be magnified to the size of the earth, its component molecules would be the size of base-balls.

MOLYBDENITE—symbol MoS_2—A lead gray sulphide of Molybdenum. It is used as a rectifier detector in contact with copper.

MOLYBDENUM—Symbol Mo—A silver white metal found in nature as *molybdenite* (q.v.), a sulphide of molybdenum. When pure this metal is ductile and can be forged. It is used chiefly as an alloy to produce extremely hard steel. Molybdenite is used as a *crystal* (q.v.) in the detection of radio waves.

MORSE LIGHT—A search light used to signal code messages by means of intermittent flashes. (See *Code.*)

MORSE INKER—An instrument for recording Morse code signals in the form of dots and dashes on a moving paper band. In one form of Morse recorder, the attraction of the armature raises an inked wheel against the paper ribbon and thereby prints upon it the dots and dashes of the message.

MOSCICKI CONDENSER—A condenser in which the dielectric thickens out at the edges. It is essentially a form of *Leyden Jar* (q.v.) composed of a glass tube, especially thickened at the neck where the dielectric stress is greatest, coated inside and out with metal foil. The design of this condenser is such as to minimize *brush discharge* (q.v.) or *corona* (q.v.) effect at its edges.

MOTOR—A device for transforming electrical energy into mechanical energy. Motors may be designed for operation on direct current, on alternating current or on either direct or alternating current. These latter are known as *universal* motors. Direct current motors are classified as shunt, series and compound. This classification is arrived at according to the manner in which the field windings are connected. In the shunt motor the field winding is connected in parallel with the brushes (that is with the armature winding). In the series motor the field winding is connected in series with the armature and the line. Compound motors have a shunt winding in parallel with the brushes and a series winding in series with the armature and the line. Compound motors may be further classified as differentially compounded and cumulatively compounded. A differentially compounded motor is one in which the series field winding is so connected as to oppose the shunt field. A cumulatively compounded motor is one in which the series field aids the shunt field. The speed of the shunt motor is nearly constant, falling slightly as the load increases. The speed of the series motor decreases as the load increases. The differential motor may be constructed so that an absolutely constant speed will be maintained at all loads. The speed of the cumulative motor decreases rapidly as the load is increased. Alternating current motors are of the series type, the induction type, commutator type, synchronous type and repulsion type. There are a number of special classifications of alternating current motors such as single phase induction, polyphase induction, repulsion induction, etc. An ordinary direct current series motor used on alternating current will operate but at a low power factor, with a large eddy current loss and with violent sparking at the commutator. In order to adapt the series motor for universal use, it must be specially designed, the field structure being *laminated* (q.v.) in order to avoid *eddy currents* (q.v.) and the field coils having only a few turns to avoid too great *self-inductance* (q.v.) and consequently low *power factor* (q.v.). Sparking at the brushes can be avoided to a certain extent by designing the motor for a small field flux and with but a few turns in series in each armature coil.

MOTOR-ALTERNATOR—A *motor generator* (q.v.) set consisting of an *alternator* (q.v.) driven by a direct or alternating current motor. Such a set may be used for converting from direct to alternating current, or for frequency changing.



Motor Alternator set installed at Station WRNY.

MOTOR-GENERATOR—A generator or generators driven by an electric motor. Motor generators are used for converting alternating current to direct current or vice versa, for changing from one voltage or from one frequency to another or to obtain a variable from a fixed voltage.

MOVABLE COIL—Inductance coils which can be moved or rotated so as to vary the inductance. Examples of movable coils used in radio are vario couplers, loose couplers, etc. (See *Coupler, Loose; Coupler, Vario,* also *Fixed Coils.*)

MULLARD, S. R.—British radio authority. Born in 1884, he was educated as an electrical engineer and was ultimately appointed head of the research laboratory of Edison & Swan, Ltd., where he developed the Pointolite arc lamp. During the World War, he served in the Royal Air Force and became head of the wireless section laboratory at the Imperial College of Science for the Air Ministry. He carried out a series of researches on vacuum tubes and in 1920 founded the Mullard Radio Valve Company.

MULTIPLE—As applied to an electric circuit, a divided circuit. Two conductors are said to be connected in multiple or *parallel* (q.v.) when their two ends are joined together.

MULTIPLE SERIES—See *Series Parallel.*

MULTIPLIER—A resistance placed in series with a voltmeter for limiting and controlling the amount of current flowing through the voltmeter windings. This resistance may be either internal (enclosed by the voltmeter case) or external.

MULTI-POLAR—Having more than two poles. Usually a generator or motor whose field magnet has more than two poles. Small machines may be made with two poles, *bi-polar* (q.v.), but all others have a number of poles, that is to say they are *multi-polar.* The use of multi-poles results in a lighter machine and incidentally there is a saving of field copper and a reduction in sparking. If there are too many poles, however, there will be excessive *leakage flux* between the poles. (*See Homo-polar.*)

MUSICAL SPARK—A spark giving a regular distinct musical note. This may be produced by a high speed rotary discharger, a *quenched gap* (q.v.) or an arc.

MUSICAL SPARK SIGNALS—Signals in which the sparks occur at regular intervals of time and fast enough to give a musical note. Usually the spark rate is between 100 to 1200 discharges per second.

MUTE ANTENNA—A local circuit or resistor used in testing transmitting apparatus. The mute antenna in this case is substituted in the place of the actual antenna. It is also referred to as a *dummy aerial, phantom antenna, mock antenna,* or *artificial antenna.*

MUTUAL CAPACITY—The capacity effect of one conductor upon another one in the same electrostatic field. The mutual capacity is not the same as the capacity of the two wires regarded as the two plates of a condenser, one positively charged while the other is charged negatively. It really represents a decrease in the capacity of one of the wires with respect to earth caused by the presence of the electrostatic field of the other. The total capacity of the two wires is diminished by the overlapping of the two individual fields. (See *Capacity Measurement of Antenna.*)

MUTUAL INDUCTANCE—Symbol M—The magnetic flux that is common or mutual to two inductively coupled circuits. The mutual inductance of two circuits is the change in the interlinkage of flux that takes place in one circuit for a change of unit current in the other. This is also called the *coefficient of mutual induction* or the *mutual induction coefficient.* The units of mutual inductance are the same as those of *self-inductance.* (See *Inductance, Mutual; Self-Inductance, Induction, Coupling, Induced E.M.F., Induction, Mutual; Coefficient,* and *Mutual Induction Coefficient.*)

MUTUAL INDUCTION—The interaction between two current-carrying coils, not having direct metallic connection. The reactance of a coil such as shown in the illustration at A_1 is reduced by the proximity of another coil, A_2 if the circuit of the latter contains no external source of electromotive force, such as an alternator. The reason for this lessening in the primary reactance is that the flux excited by the first coil induces a current in the secondary coil and this current opposes the action of the primary current. As a result the total *magnetomotive force* (q.v.) the *flux* (q.v.) and consequently the *counter-electromotive force* (q.v) induced in the first coil are reduced. The effect of the secondary coil depends upon its distance from the primary coil and upon the amounts of the resistance R_2 and reactance X_2. If both coils are mounted on the same iron core, the action is greatly increased. In some instances mutual induction is desirable, as in the case of coupled radio circuits, or even in the ordinary transformer. In other cases, mutual inductance may be undesired as in the case where a radio antenna parallels a power line. (See *Induction, Mutual; Mutual Inductance,* also *Mutual Induction Coefficient.*)



Diagram illustrating mutual inductance. The reactance of the coil A_1 is reduced by the proximity of coil A_2, since the circuit of A_2 contains no source of electromotive force. The effect of the secondary coil depends not only upon its distance from the primary coil but also upon R_2 and X_2. The presence of the iron core greatly increases the action.

MUTUAL INDUCTION COEFFICIENT—Another name for *mutual induction* (q.v.) That coefficient by which the rate of change of the current in a circuit must be multiplied to give the electromotive force induced in an adjacent circuit. From the principle of conservation of energy, it can be shown that the mutual inductance of a circuit A with respect to a second circuit B equals the mutual inductance of B with respect to A. (See *Mutual Inductance, Inductance, Mutual; Self-Inductance, Induction, Coefficient,* also *Coupling.*)

N

NAGYAGITE—A mineral containing lead, gold, antimony, sulphur, and tellurium. It receives its name from the location of its discovery near Nagyag in Transylvania. It is also known as black or leaf tellurium, and has been used as a crystal rectifier in conjunction with zincite.

NALLY, Edward Julian—American radio pioneer. Born April 11th, 1859, in Philadelphia, he joined the Western Union Telegraph Company in St. Louis and worked his way up in the telegraph service until in 1913, he was appointed vice-president and general manager of the Marconi Wireless Telegraph Company of America. Nally was one of the first to see the possibilities of wireless, and under his control the first commercial wireless communication was established between the United States and Japan, in 1914, and in 1920, he founded the first commercial wireless service between the United States and Great Britain, and afterwards to other countries. He was appointed the first president of the

Radio Corporation of America, and is a member of many scientific and other societies.

Edward Julian Nally.

NAME PLATE—A metal plate affixed to a radio set or other apparatus, giving the maker's name, trade name of apparatus, serial number or other details concerning the machine.

NAPERIAN BASE—The base of the so-called natural system of *logarithms* (q.v.). It is usually represented by the symbol ϵ (epsilon) and is numerically equal to 2.718 appx. (See *Damped Waves.*)

NAPERIAN LOG—See *Naperian Logarithms.*

NAPERIAN LOGARITHMS—Also called *Natural Logarithms.* Logarithms to the base ϵ. Logarithms constitute a tabular system of numbers, by which the operation of multiplication can be performed by addition, division by subtraction, involution by a single multiplication, and evolution by a single division. John Napier, Laird of Merchiston, Scotland, is generally regarded as the inventor of logarithms. The logarithms set forth by Napier were those of trigonometric functions. Later on Napier's logarithms were adapted to positive integers, using as a base the number 2.718 appx. and these logarithms are now called natural or Naperian logarithms. (See *Decrement,* also *Logarithms.*)

NATIONAL ELECTRIC CODE—A uniform code of rules, based upon the requirements of fire underwriters, for the electric wiring and electric installations in buildings. Unless these rules are compiled with fire insurance will not be issued or if issued previously will be voided. The National Electric Code contains a section covering special requirements for radio installations. The code is revised annually to meet new conditions and requirements. Copies of the code can be obtained from local insurance agents or from the National Board of Fire Underwriters at New York or Chicago.

NATURAL ELECTRIC WAVES—Wireless waves due to natural causes such as lightning discharges. When received in the radio apparatus, they are called *strays* (q.v.), *static* (q.v.), atmospherics, *X's* (q.v.), and various other names. There are many different causes for these stray waves. Some produce a grinding noise in the loud speaker, others a hissing noise often associated with snow or rain. Nearby lightning produces a sharp snap. Another type of strays cause loud crashes in the speaker.

NATURAL MAGNET—A substance which possesses in a natural state the properties of a magnet. Such a substance is the *lodestone,* a magnetic oxide of iron also called *magnetite* (q.v.). (See *Loadstone.*)

NATURAL FREQUENCY—The frequency at which free oscillations occur in a circuit. If L, C, and R are respectively the inductance, capacity and resistance of a circuit, then free oscillations in the circuit will have the frequency

$$f=\frac{1}{2\pi}\sqrt{\frac{1}{LC}-\frac{R^2}{4L^2}}$$

This is the natural or *fundamental frequency* of the circuit. The natural frequency of an aerial is the frequency corresponding to the natural wave length. (See *Natural Wave Length,* also *Measurement of Wave Length.*)

NATURAL RECTIFIER—A mineral which possesses the property of conducting an electric current in one direction only. (See *Crystal,* also *Crystal Detector.*)

NATURAL WAVE-LENGTH—Length of the wave emitted by an aerial when no added inductance or capacity is inserted in the aerial circuit. This is also known as the *fundamental wave length* (q.v.). By putting *inductance coils* (q.v.) (*loading inductance*) (q.v.) in the aerial circuit, longer waves may be radiated, while condensers put in series with the antenna enable it to produce shorter waves than the aerial would ordinarily radiate. The use of a series condenser is avoided wherever possible since it has the effect of decreasing the total capacity of the aerial circuit and thereby decreasing the amount of power which can be given to the antenna. The addition of some inductance has a beneficial effect, since the decrement of the aerial is thereby lessened and a sharper wave results. (See *Measurement of Wave Length; Wave Length.*)

NAUTICAL MILE—abbreviation *Naut*—A marine unit of distance. Equivalent to one minute of longitude at the equator. This unit is also sometimes referred to as a *Telegraph Naut.* It is equal to 1.1528 statute miles (the statute mile being equal to 5,280 feet). The term *nautical mile* is used especially in submarine cable work. and also in matters pertaining to navigation. The term *naut* is differentiated from *knot* in that the former refers to a distance whereas the latter refers to a rate or unit of speed.

NEGATIVE CARRIER*—An electron combined with neutral gas molecules. When the velocity of the electrons in a vacuum tube is less than the value necessary to cause ionization by collision, the electrons attract the neutral gas molecules and so form heavy negative carriers. The ease with which this formation of negative carriers takes place depends on the nature of the gas. Such gases as argon and mercury vapor do not readily form negative carriers, while hydrogen and oxygen combine with electrons more easily. The effect of this negative carrier formation is to counteract the reduction of the negative space charge occasioned by the heavy positive ions formed by collision ionization. The positive ions are ions of the gas from which one or more electrons have been removed. The ions therefore have very nearly the same weight as the gas atoms. The negative carriers, on the other hand, may consist of an atom or molecule to which has been attached an electron. It is also possible that the attraction between an electron and the neutral gas molecules can result in the formation of clusters consisting of more than one molecule held together by the electron. These negative carriers, therefore, move as slowly as, and often more slowly than, the positive ions and consequently have a relatively great effect in counteracting the tendency of the positive ions to reduce the negative space charge of the electrons. (See *Electron Theory,* also *Ion.*)

NEGATIVE CORPUSCLE—The natural unit of negative electricity. The *electron* (q.v.). It is more usual to refer to the negative corpuscle simply as the *corpuscle.* This was the name given by Sir J. J. Thomson to the carriers of electricity shot off from the cathodes in vacuum tubes. The corpuscle was found to have a charge equal to the electron and a mass which is $\frac{1}{1845}$ of that of the hydrogen atom.

NEGATIVE ELECTRODE—In a *primary cell* (q.v.) the *cathode* (q.v.) which is the carbon, copper, etc., electrode, is the *negative electrode,* while the *pole* of this electrode is the positive pole, since it is positive in relation to the external circuit. In a *secondary* or *storage cell,* the spongy lead plate, which is the anode during discharge, is called the *negative electrode* and its pole the *negative pole.*

NEGATIVE ION—An atom, which is the smallest particle of an element capable of existing, plus an *electron* (q.v.) (See *Anion, Cathion, Electron Theory,* also *Ion.*)

NEGATIVE POLE—The south-seeking end of a magnet. In a generator, the terminal into which the current returns from the external circuit. In a storage cell, the terminal of the negative plate. In a primary cell, the pole of the positive plate.

NEGATIVE RESISTANCE—A current path within a vacuum tube or an arc in which current decreases as voltage increases. The emission of electrons from cold electrodes under the impact of electrons (known as *secondary electron emission* (q.v.) or *delta rays*) results in a negative resistance or *falling characteristic.* The presence of secondary electrons can be shown by referring to the illustration. The plate P is kept at a constant positive potential with respect to the filament F by means of the battery B. When there is no difference of potential between the filament and the grid G, the cur-



At the left is a hook-up for demonstrating negative resistance. The curve at the right shows the decrease of grid current although grid potential is increased.

(*Van der Bijl—The Thermionic Vacuum Tube.)

rent in the circuit FGA is very small, since practically all the electrons emitted from the filament are drawn through the openings of the grid and thrown on to the plate. If the potential of the grid (positive with respect to the filament) is increased, the current to the grid at first increases, as shown by the part OC in the accompanying curve. When the grid potential reaches a certain value, the current as indicated by the ammeter begins to decrease, drops down to zero at D and then reverses its direction of flow. The reason for this is that while the difference of potential between the filament and the grid is small, the electrons that strike the grid enter it, but as the positive grid potential is increased the electrons on striking the grid emit *secondary electrons* from it and these are drawn to the plate which is maintained by the battery B at a positive potential, with respect to the grid. The net current as shown by the ammeter is the sum of the electrons entering the grid and those leaving it. When the velocity with which the electrons strike the grid increases beyond a certain value, one primary electron can knock out more than one secondary electron from the grid and the current in the filament-grid circuit reverses. When the positive grid potential is increased to such an extent that the grid becomes positive with respect to the plate, the secondary electrons are no longer drawn away to the plate, but are driven back to the grid so that the reversed current in the grid circuit again decreases as shown at E on the curve, and finally assumes the original direction. Hence, considering the current as indicated by the ammeter and the voltage between filament and grid, it can be seen that over the portion of the curve CDE, the current decreases as the voltage increases. Therefore CDE represents a *negative resistance* characteristic. It has been found that a device which possesses a negative resistance can function as an amplifier and also as a generator of continuous oscillations.

NEGATRON—An English vacuum tube containing a filament, a grid and two plates. This tube was devised by J. Scott-Taggart, who used it for obtaining *negative resistance* (q.v.) characteristics. The two plates are fixed one on each side of the filament. The accompanying illustration shows a typical negatron. The bulb is tubular in shape and the four electrodes are plainly shown. The grid, in this tube, is a metal rod.



A negatron tube, showing the two plate construction.

NEON LAMP—An incandescent lamp in which a reddish light is produced by the incandescence of neon gas at low pressure. This lamp has very low current consumption and has been applied to pilot lights, signs, etc.



Neon Lamp

NEON TUBE—A vacuum tube containing the gas neon at low pressure used in the Fleming *Cynometer* (q.v.) etc. In this instrument, which is used to measure the frequency of electric waves, wave lengths, etc., a capacity formed by one brass tube sliding over another can be varied simultaneously with an inductance consisting of an air core solenoid and arranged so that the point at which resonance takes place is indicated by the glowing of the *neon tube* and can be read from a calibrated scale.

NERNST LAMP—An incandescent lamp in which the incandescent body consists of a strip of material composed of a mixture of oxides of metal such as zirconium, magnesium and other refractory oxides. The incandescent portion of the lamp is called the *glower* and is conductive only at a high temperature. Consequently it has to be heated by an auxiliary heating coil. The heating coil is automatically cut out of the circuit when the current starts to flow through the glower.

NEUTRAL BODY—A body void of electrification. A charged body which loses its electrification is said to be *discharged* or *neutralized.* All matter is capable of electrification.

NEUTRAL LINE OF MAGNET—The middle portion between the two magnetic poles of a bar magnet, where there is no manifestation of magnetism.

NEUTRAL WIRE—A middle wire, in a *three wire system* (q.v.) of power distribution, which is kept at a potential mid-way between the positive and the negative mains. In the three-phase system of alternating current distribution, the conductor connected to the neutral point of a "star" or "Y" connected alternator is also known as the neutral wire. The neutral wire is here also known as the *common return.*



A three wire system with unbalanced load, showing neutral wire.

NEUTRODYNE—See *Neutrodyne Circuit*, also *Hazeltine Neutrodyne Receiver.*

NEUTRODYNE CIRCUIT—A circuit used in radio reception in which radio frequency amplification is used for neutralizing the effects of capacity of the tube and its socket. Figure 1 shows a portion of a receiving circuit. In this diagram the tube capacity is represented by a condenser shown in dotted lines. By studying this circuit, it can be seen that a closed oscillatory circuit exists, made up of the inductances and capacities in the plate and grid circuits. Just as radio frequency currents can pass through condensers in a receiving set, so they can pass through or across the vacuum tube from the plate to the grid, which forms a condenser. This condenser effect is the reason why radio frequency amplifiers oscillate. A difference of potential occurs in the plate side of the coil in the plate circuit. Instead of this being handed on to the next tube for additional amplification, a portion of this potential leaks through the capacity of the tube and its socket and affects the grid in such a way that trouble is experienced with self-oscillation. In the neutrodyne circuit, the



Fig. 1. A portion of a receiving circuit. Dotted line shows tube capacity represented by an equivalent condenser.



Fig. 2. A typical neutrodyne set.

inter-element capacity of the amplifier vacuum tubes is neutralized by means of special condensers called *neutrodons*. The capacity of these is very low, being approximately equal to the internal capacity of a vacuum tube. By reason of this equality, any tendency of a large amount of radio frequency current to pass back through the tube through the grid is defeated and instead is neutralized by the combination of the neutralizing capacities, the inter-element capacity of the vacuum tubes and the secondary windings of the tuned radio frequency transformers. This effect is in reality a bucking one, since the current is made to take two paths. Each neutralizing condenser must be adjusted so that its capacity will equal that of the vacuum tube it is connected with. Since it is impossible for a neutrodyne circuit to oscillate, there is no radiation of energy from the set, with consequent disturbance of other receiving sets in the vicinity.

The neutrodyne circuit was invented by Professor L. A. Hazeltine. The typical neutrodyne receiving set uses five tubes, employing two stages of tuned and neutralized radio frequency amplification, with detector and two audio frequency stages. (See *Hazeltine Neutrodyne Receiver.*)

NICHROME WIRE—A nickel-chromium-steel alloy wire, which is able to withstand a bright red heat in the atmosphere without oxidizing. Nichrome is practically non-corrosive. It has a very high melting point, about 1550 degrees Centigrade and is used extensively in electrical heating appliances and resistance elements.

NIGHT EFFECT—Changes in the strength of radio signals noticeable especially at night. This effect is also known as *fading* (q.v.). Fading does not generally occur in the immediate vicinity of the transmitting station. It seems to happen more often on wave lengths below 400 meters. A certain station is being received with normal intensity, when suddenly the sounds become very faint and in a few minutes they may again become normal or may even become stronger than usual. In some cases the variations from strong signals to weak take place every few minutes while in other cases there may be an interval of several hours. It has been observed that fading takes place over land more often than in radio transmission at sea.

NOBLE, Sir William—British engineer. Born in 1861 and educated at Gordon's College, Aberdeen, he thereafter entered the Aberdeen telegraph office. In 1893 he was appointed engineer for the northeast area of Scotland, rising rapidly in the service until he became chief engineer in 1919. He retired from the Post Office in 1922, and became a director of the General Electric Company and of the British Broadcasting Company. Sir William Noble has written many articles on telegraphy and telephony and is considered to be an authority on these subjects.

NODES—In a wave form, such as shown in the illustration which represents an alternating current sine wave, the zero points. Thus in the alternating current sine wave, the points of zero current or potential, at A, C, E, and G, are nodes, and the points B, D, and F are the anti-nodes or *loops* (q.v.).



Sine wave illustrating nodes and anti-nodes.

NODEN VALVE—An *electrolytic rectifier* (q.v.) which allows only current in one direction to pass through it. This rectifier utilizes an aluminum rod or cylinder as a cathode and the anode may be of iron, lead or of carbon. Ammonium phosphate is used as the electrolyte. The principal of operation of this rectifier depends upon the fact that the current in the positive direction is stopped at the aluminum plate through the formation of an insulating crust of aluminum phosphate and aluminum oxide. These two substances present an extremely high resistance to the passage of the current in the positive direction, but the compounds dissolve again upon reversal of the current. By suitably combining two or more cells, both the half waves of an alternating current can be rectified. In Fig. 1 is shown the principle upon which the Noden Valve acts, and Fig. 2 shows a hook-up for connecting four cells to obtain full wave rectification. (See *Electrolytic Rectifier Full Wave*, also *Rectifier.*)



Fig. 1. Diagrammatic illustration of the principle of the Noden valve.



Fig. 2. A hook-up for connecting four Noden cells to obtain full wave rectification.

NON-CONDUCTOR—See *Insulator.*

NON-INDUCTIVE COIL—A coil having negligible inductance. Such a coil may be wound by doubling the wire upon itself and then winding the two parallel halves side by side.

NON-OSCILLATORY—Free from oscillations or vibrations. Without periodicity, that is to say, *aperiodic* (q.v.). A current which is uniform in direction and flow and free from oscillations is said to be a non-oscillatory current. A non-oscillatory circuit is one in which an impressed potential will produce current that gradually diminishes in amplitude without reversing its direction of flow. This is also called an *aperiodic circuit* (q.v.). Such a circuit can have no natural period of oscillation.

NON-PERIODIC—See *Aperiodic*, also *non-oscillatory.*

NON-RADIATIVE ANTENNA—A combination of capacity and inductance equivalent to that of an aerial, used to test transmitting apparatus without radiating waves. (See *Mute Antenna.*)

NORTH MAGNETIC POLE—A point on the earth at a latitude 70 degrees North, longitude 97 West. The north magnetic pole does not coincide with the north (geographic) pole. (See *Magnetic Poles.*)

NORTH POLE—See *Magnetic Poles*, also *North Magnetic Pole.*

NO-VOLT RELEASE—An electro-magnetically controlled device, inserted in the field circuit of a motor so that it holds the handle of the motor starter in place on the last stud, but if the supply current fails, the magnet becomes de-magnetized and allows the spring attached to the starter handle to pull the handle back to the "off" position. This prevents damage to the windings of the motor, in case the current comes on again, since it is then necessary to start up the motor in the usual way, using the starter and gradually increasing the voltage by cutting out the limiting resistances provided in the starter. (See *Overload Release.*)

NULL METHOD—An electrical method of testing in which adjustments are made so that zero deflection is obtained in a galvanometer, as for example when using a *Wheatstone Bridge* (q.v.). This is sometimes referred to as the *zero method.* (Null is also a German word meaning zero.)

O

OCTAHEDRITE—Chemical Symbol TiO_2—Titanium dioxide, an eight sided crystal which has been used as a crystal detector for detecting and rectifying radio currents. (See *Crystal.*)

OERSTED—The unit of *reluctance* (q.v.). The reluctance or in other words, the magnetic resistance offered by a cubic centimeter of vacuum. Unit *magneto-motive-force* (q.v.) will generate a unit of *magnetic flux* (q.v.) through unit reluctance. The oersted was named after the Danish physicist, H. C. Oersted.

OHM—Symbol Ω (Omega)—The unit of electrical resistance. It is the ratio of unit *electromotive force* (q.v.) to unit current. The ohm is the basis of the entire electrical system of units and the volt and the ampere are defined in relation to it. Very elaborate apparatus is required in order to determine the ohm absolutely. However, resistances can be compared easily and once the standard is determined it is a simple matter to make duplicates. In accordance with an act of Congress, the ohm was adopted as a legal unit and defined as follows: The unit of resistance shall be what is known as the international ohm, which is substantially equal to one thousand million units of resistance of the centimeter-second-gram system of electromagnetic units and is represented by the resistance offered to an unvarying electric current by a column of mercury at the temperature of melting ice, 14.4521 grams in mass, of a constant cross-sectional area and of the length of 106.3 centimeters. Stated in English units, the ohm is specified as the resistance offered to an unvarying electric current by a column of mercury at the temperature of melting ice (32 degrees Fahrenheit), 0.5050 of an ounce in mass (approximately 3/100ths of a pound), of a constant cross-sectional area and of a length of 3.487 feet.

OHMMETER—An instrument used to measure resistance directly in ohms. It is particularly adapted for measuring high resistances, although certain types of ohmmeters are made for measuring lower resistances. In one form of ohmmeter, the moving system is deflected by forces due to currents in two coils at right angles to one another. These carry currents in one case proportional to the current through the conductor under test, and in the other case proportional to the potential drop across it. This is in effect, a special form of *galvanometer* (q.v.) and when combined with a hand driven generator gives the conventional *megger* (q.v.) The bridge type ohmmeter depends on the *Wheatstone Bridge* (q.v.) principle. In this instrument, however, the rheostat resistance remains constant and the bridge arms are formed by a wire, called a *slide wire*, resistances being varied by means of a moving contact as shown in the illustration. This type of instrument is often referred to as a *slide wire ohmmeter*. While a straight slide wire is used in some types, in others the wire is wound on an insulating cylinder. In the Weston direct-reading ohmmeter, there is a permanent magnet and a moving coil having two windings and an adjustable magnetic shunt. Provisions are made for connecting an unknown resistance and an auxiliary battery in the circuit of the instrument. A checking plug is provided for checking the accuracy of the instrument before use. When the key is closed, the battery current is divided between two windings. The magnetic force exerted on the one winding, which is in series with a fixed resistance, tends to deflect the pointer up the scale, while the force exerted on the other winding tends to return it to zero. With the correct battery voltage the magnetic shunt may be adjusted to bring the pointer to full scale position. When the plug is shifted to the low range position, a resistance equal to that of the low range is removed from the circuit whose magnetic force tends to deflect the pointer towards the zero position. By connecting a resistance equal to that of the low range across the "unknown" binding posts, the previous condition is restored and the pointer will go back to the full scale position. For values of resistance lower than this the opposing force will be greater and hence the coil will be brought back to a lower position on the scale. At zero resistance across the "unknown" binding posts, the magnetic forces of the two windings will balance each other, thus causing the coil to stand at zero on the scale. The Vawter indicating ohmmeter is of the galvanometer type and utilizes two coils carried by a shaft and moving in the field of a permanent magnet. A specially shaped core is used to give the desired scale characteristics. By making connections to the coils through spirals of negligible torque, the position of the pointer does not depend upon the value of the current nor on the strength of the permanent magnet.



Diagram of connections of a slide wire ohmmeter.

OHMIC COUPLING—See *Resistance Coupling.*

OHMIC DROP—The fall in potential which occurs when an electric current flows through a resistance. (See *IR Drop.*)

OHMIC LOSS—Power or energy loss due to the resistance which an electrical circuit offers to the flow of current. (See *I^2R Loss.*)

OHM'S LAW—Current flowing in a conductor will increase directly with increase of voltage and will decrease directly with increase of resistance. In other words, voltage is the cause, while current is the effect. The effect is directly dependent upon the cause and inversely dependent upon the opposition offered to the cause. Ohm's law is the fundamental law of electrical engineering. Ohm's law can be stated as an equation as follows:

$$\text{Current (in amperes)} = \frac{\text{Voltage (in volts)}}{\text{Resistance (in ohms)}}$$

or

$$\text{Voltage} = \text{Current} \times \text{Resistance}$$

$$\text{Resistance} = \frac{\text{Voltage}}{\text{Current}}$$

The above three equations all mean the same thing and serve to express in various forms, the idea set forth above. Ohm's law can be applied to every conductor, provided that the conductor stays at a constant temperature, that there is no internal electromotive force in the conductor and that the distribution of the stream lines in the conductor remains unchanged. Ohm's law is easy to understand and easy to apply. Thus in a particular circuit, a certain voltage causes a certain current to flow. Double the voltage will cause double the current to flow, if the resistance is the same. If the resistance is doubled, however, the same voltage will result in only half the current flow. Double voltage and double resistance results in unchanged current flow. Ohm's law applies to a portion of an electrical circuit as well as to the entire circuit. Care must be taken when applying the law to only part of the circuit, to consider only the resistance, current and voltage of that part.

OMNIBUS BAR—A conducting bar of copper, mounted in back of a switchboard, or panel and serving as a common connector for two or more pieces of apparatus. This term is more usually shortened to *bus bar* (q.v.)

OMNIGRAPH—An intrument which sends code (dots and dashes) mechanically. It is usually operated by clockwork and is connected with a buzzer. It employs metal disc records each of which has a series of notches which correspond to the dots and dashes of the telegraph code. The omnigraph is used by beginners in learning the code and is also used to test the speed of reception of applicants for radio operators' licenses.



The omnigraph—an instrument which sends code mechanically.

ONDOGRAPH—An instrument for autographically recording the wave forms of varying currents, especially currents which are alternating rapidly. This form of curve tracer was invented by Hospitalier.

ONDOMETER—Another name for a *wave meter* (q.v.)

OPEN ANTENNA—According to the report of the Institute of Radio Engineers standardization committee, this is a condenser antenna, that is to say an antenna consisting of two capacity areas. Antennas may be subdivided into two general classes, those which act principally as condensers, usually simply called antennas, and those which act principally as inductances. These latter are *loop antennas* (q.v.), *coil antennas* (q.v.), etc. When electric waves reach a condenser antenna, they set up an alternating electromotive force between the wires forming the upper plate of the condenser and the ground or the other lower plate of the condenser. As a result of this alternating electromotive force, alternating current will flow in the antenna system. (See *Aerial.*)

OPEN CIRCUIT—An electrical circuit which does not offer a complete path for the flow of electricity. There may be one or more breaks in the path. An open circuit is often referred to as a *broken circuit*. Open circuits often cause trouble in radio apparatus. They may be due to the burning out of a winding, to a connection coming off a terminal, to a soldered connection breaking loose or to similar causes. The method of testing for an open circuit is to connect a battery and a headset in series with the circuit in question. If there is no click in the headset, there is evidently a break in the circuit.



An open circuit primary cell.

OPEN CIRCUIT PRIMARY CELL—A *primary cell* (q.v.) designed for intermittent use and normally kept on open circuit. Such cells usually have a *depolarizer* (q.v.) which acts slowly. In certain cases, no depolarizer whatsoever is employed. Open circuit cells are designed for use during short intervals of time only and must stand for long periods on open circuit, during which the hydrogen is gradually taken away from the negative plate. The operation of the open circuit cell will not be satisfactory if the rest periods are not long enough or are not at frequent intervals.



An open-core transformer.

OPEN-CORE TRANSFORMER—A transformer in which the (useful) magnetic circuit is partly through iron and partly through air, instead of entirely through iron as in the *closed-core transformer* (q.v.). It is sometimes referred to as a *polar* transformer. In one type of open-core transformer the arrangement is similar to that of an *induction coil* (q.v.), a hollow iron core, filled with soft iron wires being employed to concentrate the magnetic field.

OPPOSING ELECTROMOTIVE-FORCE—See *Back Electromotive-force.*

OPTOPHONE—An instrument utilizing a telephone receiver controlled by the variations of resistance of a *selenium cell* (q.v.) by means of which the blind are enabled to read ordinary type, through the sense of hearing.

ORDINATE—A mathematical term used in radio in making *logs* (q.v.) or other curves. Defined in mathematical language, the ordinate is that one of the coordinates of a point which is drawn parallel to a line (called the axis of ordinates) to the point from the other axis (called the axis of abscissas) or from the plane of the other axis of coordinates, assumed as a basis of reference. This definition will be clearer if reference is made to the accompanying illustration. The dotted line drawn from the point A to the axis of abscissas is the ordinate of the point A.



The dotted line is an ordinate.

OSCILLATING CURRENT—An alternating current of high frequency, consisting of a succession of waves of constant length. In some cases, the term oscillating current refers particularly to a current where the amplitude is decreasing in constant proportion due to damping. (See *Oscillation, Oscillation Frequency,* also *Logarithmic Decrement.*)

OSCILLATING IMPULSE—*An oscillating current* set up for the purpose of producing electric waves.

OSCILLATING PERIOD—The time of one complete *oscillation* (q.v.).

OSCILLATION—Periodical surging first in one direction and then in the other. Electrical oscillations are the surgings backward and forward of current periodically, as, for example, in the case of a condenser being discharged in an oscillating circuit. The oscillating action in a discharging condenser is as follows: In the case of a condenser, positively charged, upon being discharged through an inductance, the charge rushes out of the condenser, the current increasing in strength until it reaches a maximum. Then, due to self-induction the current prolongs itself, and it continues until its energy is changed back into an electric charge of an opposite sign, current flowing into the condenser which is then charged negatively. The condenser again discharges giving a maximum current in the opposite direction. the current thereafter flowing back into the condenser with the same direction charge as at first. This action constitutes one complete swing or oscillation and the current continues to oscillate, each time becoming weaker and weaker as the energy is dissipated into heat and also partially into electric waves. It is important to note that the propagation of electric waves could not be accomplished without electrical oscillations. Thus at the transmitting station, the electrical oscillations are converted into electric waves and at the receiving station, the waves are re-converted back into oscillations.

OSCILLATION CONSTANT—The square root of the product of the capacity and the inductance of a circuit. The *natural period* of a circuit is determined by its inductance and capacity in the same manner as the natural period of a steel spring clamped at one end in a vise is determined by its mass and elasticity. Where a simple aerial is used it is an easy matter to calculate the length of a wave radiated from it, provided the oscillation constant has been found. The velocity of electric waves is approximately 3 x 10^{10}cm. per second, and hence the length of the wave radiated is about 60 times the oscillation constant where the wave length is measured in meters. (See *Aerial Tuning Condenser,* also *Isochronous.*)

OSCILLATION FREQUENCY—The number of complete oscillations or cycles flowing in a circuit per second. The oscillation frequency of a circuit varies inversely as the square root of the product of the inductance and capacity. The frequency is inversely proportional to the wave length, hence the addition of either *capacity* (q.v.) or *inductance* (q.v.) to the oscillatory circuit will result in an increase of *wave length* (q.v.). (See *Frequency.*)

OSCILLATION POINT—That current value, known as the *critical current* (q.v.), at which the vacuum tube or tubes in a radio receiving set start to oscillate.

OSCILLATION TRANSFORMER—A high-frequency air-core transformer used for transferring electrical oscillations from one circuit to another. Either one or both the windings may be tuned to the frequency of the oscillations. The transformer used for coupling the oscillator of a transmitting set to the aerial is an example of an oscillation transformer. (See *Coupling, Inductive Coupler,* also *Transformer.*)

OSCILLATION VALVE—See *Oscillator,* also *Vacuum Tube.*

OSCILLATOR—A device or apparatus for producing electrical *oscillations.* The *vacuum tube* (q.v.) under correct conditions may be used to produce sustained oscillations of a definite amplitude and frequency. In order for a vacuum tube to act as an oscillation generator it must be capable of amplifying, part of its output energy must be returned to the input, an oscillation circuit must be combined with the tube, which possesses inductance, capacity and resistances of values such that the tube will oscillate with the desired frequency and finally the tube must have certain characteristics which when combined with the constants of the oscillatory circuit, will determine the amplitude of the oscillations. Oscillations may also be produced by means of a high frequency alternator and by a direct current generator and electric arc. (See *Alternator,* also *Alexanderson.*)

OSCILLATOR, HERTZIAN—Two insulated rods, with axes in line, with their nearer ends forming a spark gap and their outer ends bearing plates or balls to give the system the required capacity. The overall length is usually less than 6½ ft. and the whole constitutes an open oscillator. A Hertzian oscillator is sometimes called a *dipole.* When the rods are brought near each other but not in actual contact and the conductors are connected to the terminals of an *induction coil* (q.v.) a succession of sparks can be caused to jump the gap and these set up electric waves in the *ether* (q.v.).



Typical Hertzian Oscillators.

OSCILLATOR, LINEAR—The straight wires connected on either side of the spark gap of an induction coil, traversed by oscillations. Linear oscillators are of the open type. As used by Hertz, they consisted of two rods, having a spark gap between their adjusted ends, while their outer ends terminated in plates or balls in order to increase the capacity of the system.

OSCILLATOR, RIGHI—In this type of oscillator, the spark gap is established between two metal spheres placed between two smaller spheres. (See *Oscillator,* also *Oscillator, Hertzian.*)

OSCILLATOR, THERMIONIC—A vacuum tube used to generate continuous oscillations. (See *Oscillator.*)

OSCILLATORY CIRCUIT—A circuit possessing *inductance* (q.v.) and *capacity* (q.v.), the electrical constants being such that an oscillatory current can be set up. The accompanying figure shows a simple oscillatory circuit, consisting of a condenser, an inductance and a spark gap. When a source of high potential is connected across the spark gap and the latter is properly adjusted, the condenser is charged and there is a spark across the gap. Provided that there is not too much resistance in this circuit, there will be set up an *oscillating current* (q.v.) of high frequency, decreasing in amplitude according to a fixed ratio. Such a current can be used to set up electric waves. Oscillatory circuits are of two general classes, closed as shown in the illustration and open, as in the case of an aerial system. An aerial which has no tuning condenser or inductance in its circuit still has distributed inductance and capacity, whereas an aerial having a tuning inductance and a condenser in its circuit, has a combination of concentrated and distributed inductance and capacity.



A simple oscillatory circuit.

OSCILLATORY CURRENT—See *Oscillating current.*

OSCILLION—Name which has been applied to the *vacuum tube* (q.v.) especially where used as an oscillation generator.

OSCILLOGRAM — A picture, graph or record of a wave form usually obtained by means of an *oscillograph* (q.v.).



An oscillogram obtained by means of a tuning fork.

The illustration shows an oscillogram obtained on smoked glass by means of a tuning fork. (See *Oscillagraph.)*

OSCILLOGRAPH — An instrument for recording photographically or showing visually the wave form of alternating currents or of other rapidly changing currents or voltages. The essential parts of such an instrument are a moving coil mirror galvanometer, a rotating or vibrating mirror and a moving photographic plate or film. Figure 1 illustrates the principle of the oscillograph and shows the curves it produces. The oscillograph was invented by M. A. Blondel in 1893. By means of the oscillograph the wave form of a current may be shown as a curve and its characteristics may thus be examined and studied. In order to form the curve, it is necessary to have simultaneous motion in two directions. The vibrator of the oscillograph which consists of a delicate coil of wire, with mirror attached, is made extremely light so that the moving system will have as little inertia as possible. The coil is placed in a powerful magnetic field and when an oscillating current is passed through it, it oscillates in synchronism with the current. A spot of light focused on the mirror is made to fall on a screen at the predetermined distance from the vibrator. This spot of light traces out a straight line on the screen. Substituting a photographic film for the screen and arranging the film so that it will move in a vertical path across the moving beam of light (which is assumed to be moving from right to left across the screen) a curve is traced on the film. The commercial form of oscillographs are provided with apparatus whereby the curve may be examined without the necessity of photographing it. In these the beam of light is reflected from a rotating or vibrating mirror in such a way that it receives a horizontal and an up and down motion and is focused onto a curved plate of glass. Tracing paper may be stretched over the glass so that the image of the spot of light traces a visible curve on it. The curve being repeated very rapidly appears to be standing still and hence it is possible to trace over it with a pencil or even to place a piece of photographic paper on the curved glass and make a record of the curve in this way. The motion picture camera has been applied to the oscillograph and is useful where longer records are required. It should be noted that oscillographs which utilize a moving coil, such as the Duddell or Blondin types. will work over a band of frequencies up to a maximum of about 300 cycles per second. Inasmuch as the oscillations common in radio work are of much higher frequency than 300 cycles, it has been found necessary to use an oscillograph whose moving parts are without appreciable weight. The use of electrons as moving parts has solved this problem. A Frenchman, Alexander Dufour has applied the Braun tube to the construction of an oscillograph which has no appreciable inertia and which is capable of operating at a frequency up to a million cycles per second. This device uses only minute amounts of energy in its operation and therefore does not disturb the original circuit. It is able to register both voltage and current simultaneously and is so arranged that a single impulse is sufficient for a photographic impression. The Dufour oscillograph consists essentially of two glass tubes fitted by means of a ground joint into a bronze chamber. The upper glass tube carries a cathode and an anode and the other tube has one pair of deflecting plates for electrostatic deflection of the electron stream. Two sets of coils perpendicular to each other are used for magnetic deflection and these are placed outside the tube and slightly below the deflecting plates. In order to photograph the oscillations, a drum is used which is provided with a film magazine allowing six films to be taken in succession. When visual examinations of the oscillations are to be made, a fluorescent screen is turned up into position covering the opening into the interior of the drum thus preventing the films from being exposed when using the screen. After the films are put into the drum, this is placed within the bronze chamber and locked into position. An air-tight door is used to close the opening and the film changing mechanism is operated by means of external controls. Glass windows on either side of the bronze chamber allow the fluorescent screen to be seen. The accompanying sketch shown at Figure 2, gives a diagrammatic representation of the operation of the Dufour oscillograph.



Fig. 1. The principle of operation of the oscillograph is shown at A. At B are shown diagonal and straight paths traced by the beam of light falling on a moving photographic plate. The type of curve which an oscillograph traces for alternating currents is shown at C.



Fig. 2. A diagrammatic representation of the Dufour oscillograph.

OSMOSIS, ELECTRIC—When an electric current is passed through an electrolyte having an anode on one side of a porous diaphragm and a cathode on the other side, there is a tendency for the liquid to pass through the diaphragm towards the cathode raising the level of the liquid on the cathode side. This phenomenon is known as electric osmosis.

OTOPHONE—A device for the hard of hearing, which utilizes an extremely sensitive microphone connected to a two-stage vacuum tube amplifier. The instrument uses dry cell tubes and the batteries are contained in the case with the microphone. A small telephone receiver completes the outfit.

OUDIN RESONATOR — A device used for obtaining high-frequency brush discharges. Discharges of this nature are used in the investigation of resonance effects and also in medical work. The accompanying diagram explains the principle of the Oudin resonator.

B D is an uninsulated coil of copper wire wound on an insulating core with each turn separated from the next adjacent one. At B, the helix is connected to an induction coil and it is tapped by means of a sliding contact at C. The sliding contact is connected through a condenser to the induction coil H, with a spark gap G in parallel in the circuit as shown. The circuit BGFC is a closed oscillatory circuit receiving its excitation from the induction coil H. The circuit C D E is an open circuit in contact with the oscillatory circuit. By moving the sliding contact, C, a point is reached where a brush discharge appears at E, thus indicating that electric oscillations are being set up in the open circuit. (See *Brush Discharge, Corona,* also *Oscillator.*)



Connections of the Oudin resonator.

OUTPUT—The useful energy given out by a machine, circuit, vacuum tube or other device. (See *Input; Output, Transformer; Output Circuit of Vacuum Tube.*)

OUTPUT CIRCUIT OF VACUUM TUBE—The filament-plate circuit as differentiated from the filament-grid or input circuit. (See *Input Circuit of Vacuum Tube.*)

OUTPUT, TRANSFORMER—The product of the voltage at the secondary terminals of a transformer by the current flowing in the secondary winding. The output of any transformer is always less than the input by an amount equal to the losses. The *efficiency* of a transformer is the ratio of its useful output to the total *input.* (q.v.)

OVERLOAD RELEASE—An electromagnetic device which is used to cause a motor starter handle to return to the off position when the current exceeds a pre-determined overload value. The overload magnet is usually arranged so that too strong a current will result in short-circuiting the no-volt release thus switching off the driving current. One form of overload release consists of a magnet in series with the line and the armature. This magnet is arranged to attract a pivoted iron keeper whenever excessive current flows. The pivoted arm, when attracted by the magnet, makes connection between two contacts, themselves connected so as to short circuit the holding magnet when the circuit is closed. Therefore, when more than the allowable current is drawn from the line, the overload magnet attracts its pivoted keeper which closes the circuit short-circuiting the holding magnet. The contact arm is then released by the holding magnet and the arm is pulled back to the off position, thus cutting the motor off the line. Another form of overload release utilizes an electromagnet to attract a pivoted arm, arranged so that this will break the circuit between the motor and the line. This results in operating the no-voltage release. (See *No-Volt Release.*)



Overload Release.

OVERTONE CURRENTS—Alternating currents which have harmonic frequencies of a higher value than the fundamental or first harmonics.

OVERTONES—Higher harmonics associated with the first harmonic. This term particularly refers to sound waves. In various musical instruments, different overtones are brought out and this results in each instrument having its own tone characteristic.

P

PACKING—(referring to a *microphone*). The tendency of carbon granules in a microphone to settle or pack. In this position they are no longer sensitive and do not readily respond to the vibrations of the diaphragm. Packing may be caused by irregularity in the sizes of the carbon granules. It may be remedied by gently tapping the microphone.



Front and side view of a pancake coil.

PANCAKE COIL—A flat inductance coil. Coils of this type are used in radio receiving sets as radio frequency transformers, also as antenna couplers and oscillator couplers. They may be *basket wound* (q.v.), spider wound, etc. In wireless transmitting apparatus, aerial tuning inductances, loading inductances, and oscillation transformers (illustrated) are frequently of the pancake coil type. (See *Inductance, Antenna.*)

PANEL—A board of insulating material carrying the controlling or measuring devices of an electric circuit. The panel for controlling the charging of storage batteries is called a *charging panel.* A panel carrying generator controls is referred to as a *generator panel.* Where only a single panel is used this is usually called the *switchboard.* The usual switchboard comprises a number of panels. Switchboard panels are commonly made of marble. The usual varieties available are white Italian, pink or grey Tennessee and blue Vermont marbles. Plain slate is sometimes used for panels where the voltage is not too high. When the panels do not require a finish, soapstone is sometimes used. The front of a radio receiving set on which the dials and rheostat controls, etc., are mounted is also called a panel. These panels are usually made of Bakelite, hard rubber, composition or similar insulating substances, although a number of sets are being made with metal panels. The horizontal panel on which the sockets and transformers are usually mounted is known as the *sub-panel* (q.v.).

PANNILL, Charles Jackson—American radio pioneer. Born in Petersburg, Virginia, May 13, 1879. He entered the American Navy, 1898. In 1902 he took a post under Professor R. A. Fessenden and carried out a series of wireless experiments at Hampton Roads, later inaugurating wireless communication between New York and Philadelphia. Pannill was the first man to install wireless on the battleships of the U. S. Navy. Afterwards he carried out a series of communication experiments between various parts of the United States and erected a number of wireless stations. He joined the Marconi Wireless Telegraph Company in 1912 and became a radio adviser to the United States Government, 1914, and assistant director of Naval Communications, 1916. Pannill is a fellow of the Institute of Radio Engineers and a member of the Washington Society of Engineers.

PAPER CONDENSER—A fixed condenser, usually made of tin foil and utilizing a dielectric of paraffin-waxed paper. The 1 microfarad by-pass condenser is a typical example of a paper condenser. (See *Condenser, By-pass.*)

PARALLEL—See *Parallel Connection.*

PARALLEL CONNECTION—Two or more parts of an electrical circuit so connected that the current divides between them. This is also known as a *multiple* (q.v.) connection, *divided circuit,* or *shunt* circuit. Where a number of parts of a circuit are connected in parallel, the same potential is impressed on each part. The current flowing in each branch will depend upon the impressed voltage and the resistance of each branch. (See *Circuit, Parallel.*)

PARALLEL RESISTANCES—Resistances connected so that their terminals have the same difference of potential between them. The greater the number of resistances in parallel, the less will be the total resistance of the circuit. If there are three resistances in parallel of ½, ⅓ and ⅕ ohm, respectively, then the total resistance is equal to the reciprocal (one divided by a number) of the sum of the separate reciprocals. In this case the sum of the reciprocals is 2 plus 3 plus 5 equal to 10 and the reciprocal of this is equal to one-tenth, so that the total resistance of this parallel circuit is one-tenth of an ohm. It can be seen that the total resistance of any circuit having a number of resistances in parallel is less than the resistance of any *one* of the branches. (See *Circuits Parallel*, also *Parallel Connection.*)

PARALLEL RESONANCE—When a concentrated capacity and a concentrated inductance are connected in parallel between terminals to which an alternating electromotive force is applied, and the inductance or capacity or frequency is varied, the condition of parallel resonance exists when the current supplied by the source is a minimum. It should be noted that in series resonance, the total current supplied by the source flows through both the inductance and the capacity whereas in parallel resonance the current supplied by the source is the vectorial sum of the two currents, one flowing through the capacity and one through the inductance.

PARAMAGNETIC—Having a permeability greater than unity. Magnetic as opposed to diamagnetic. The term *paramagnetic* is used in some cases to apply to substances which have only a slightly greater permeability than air such as liquid oxygen, the rare metal erbium, etc. If used in this sense it does not include *ferro-magnetic substances* (q.v.). (See *Diamagnetic material.*)

PARTIAL—An acoustical term denoting any one of the natural vibrations of which a body is capable. An electrical *oscillator* (q.v.) possessing distributed capacity and inductance has, theoretically, an infinite number of possible frequencies, each of which is called a *partial.* The lowest frequency is called *the fundamental.* (See *Harmonics, Harmonic Current, Overtones,* also *Overtone Currents.*)

PARTITION INSULATOR—An ebonite tube having a metallic rod running through its center with wing nuts at each end. It is used for continuing a circuit through a wall or partition.

P.D.—Abbreviation for *potential difference.* (See *Potential, Difference of.*)

PELTIER EFFECT—The change in temperature, either heating or cooling, at the junction of two unlike metals, depending upon whether an electric current originating from an external electromotive force, is sent through the junction in one direction or the other. The Peltier effect is the opposite of the *thermo-electric* effect.

PERCENTAGE COUPLING—The coefficient of coupling between the primary and the secondary of an oscillation transformer in a wireless transmitting system. When the primary winding is placed close to the secondary, the coupling is said to be *close* or *tight.* When the two windings are apart the coupling is said to be *loose.* With the ordinary spark gap in the closed circuit, if the primary and the secondary windings are closely coupled a broad wave will be radiated from the aerial system. If they are loosely coupled, a *sharp* wave will be radiated.

PERIKON DETECTOR—A crystal rectifier utilizing a piece of zincite in firm contact with a piece of chalcopyrite. (See *Combination Detector,* also *Crystal Detector.*)


A Perikon detector.

PERIOD—The time required for one complete *cycle.* (q.v.) Referring to an *alternating current* (q.v.) it is the time required for the current or electromotive force to pass through the various values from zero to a positive maximum back to zero again, then to a negative maximum and finally to zero.

PERIODIC—A vibration is said to be periodic if all the phenomena are repeated regularly at equal intervals of time. This time is called *periodic time* or the *period.*

PERIODICITY—A synonym for frequency, or for angular velocity.

PERMANENT MAGNET—Hardened steel which when magnetized retains its magnetism after the removal of the magnetizing force. The usual method of making permanent magnets is to place the steel in a powerful electromagnetic field. They can also be made by stroking with another magnet. Permanent magnets are used in all electromagnetically operated headsets and *loud speakers.* (q.v.) (See *Magnet, Electromagnet,* also *Temporary Magnets.*)

PERMEABILITY—The *permeance* (q.v.) existing between the opposite faces of a cube of the substance each side of which is one centimeter in length. Since the permeability of air is assumed to be unity, the permeability of any substance is the ratio of the flux that passes through it to the flux that would exist in air if the magnetomotive and flux path remained unchanged.

PERMEANCE—That property of a magnetic circuit which allows the flow of magnetic flux. Its reciprocal is *reluctance* (q.v.) which is the property of a magnetic circuit by which it resists the flow of magnetic flux.

PERMITTANCE—A synonym for *capacity* (q.v.) or *capacitance* (q.v.). This property is possessed by every electrical circuit, but does not manifest itself unless there is a change in voltage. The greater the permittance of a circuit, the greater will be the opposition offered to a change in voltage.

PERMITTIVITY—See *Dielectric Coefficient and Constant, Inductive Capacity,* also *Inductivity.*


A petticoat insulator. Shown in cross-section at the right.

PETTICOAT INSULATOR—An insulator having two or more flanges or petticoats arranged one on top of the other for the purpose of reducing leakage and preventing accumulation of moisture. Petticoat insulators are usually made of porcelain. Insulators used on low tension lines are also of the petticoat type, in such cases being constructed of glass. (See *High Tension Insulator,* also *Insulator.*)

PHANTOM AERIAL—See *Mute antenna.*

PHASE—A particular state in a regularly recurring cycle of changes. In simple harmonic motion, uniform circular motion, or in periodic changes of any magnitude varying according to a simple harmonic law (as for example an alternating current) the point or stage in the period to which the rotation, oscillation or variation has advanced, considered in its relation to the position or instant of starting or to some other standard position. This relationship is usually expressed in angular measure. Defined in electrical terms, phase is the distance, usually measured as an angle, of the base of any *ordinate* (q.v.) of an alternating wave from any chosen point on the time axis. This distance represents the phase of the ordinate with respect to the point. In any sinusoidal alternating current quantity, the phase at any instant may be shown by the corresponding position of a *vector* (q.v.) revolving about a point with such an angular velocity that its projection at each instant upon a chosen reference line is proportional to the value of the quantity at that instant. As an example, consider a conductor rotating in a magnetic field. The induced electromotive force, in one complete revolution, passes through the following values. It starts at zero and rises to a maximum positive value, then falls to zero and rises to a maximum positive value in the reverse direction, finally falling to zero again. The transitions through these various values constitute a *cycle* (q.v.). The time of this transition is called a *period,* the number of cycles per second being the *frequency* (q.v.). The angle at any instant through which the conductor has rotated since the electromotive force changed its sign from negative to positive is the *phase angle.* This is ordinarily designated by the Greek letter Φ (phi). If ω (omega) is the angular velocity of the rotating conductor and f the frequency, then $\omega = 2\pi f$ (since there are 2π radians in a complete revolution). If the time in seconds which has elapsed since the conductor last passed the point of zero electromotive force be represented by t, then the phase Φ at that particular instant is equal to $\omega t = 2\pi ft$. Periodic variations are conveniently expressed by sine curves and the relative phases are indicated by the relative positions of the *nodes* (q.v.) and *loops* (q.v.).


ALTERNATING CURRENT WAVE SHOWN BY SINE CURVE
PHASE ANGLE
CYCLE
TIME OF CYCLE-PERIOD
CYCLES PER SECOND-FREQUENCY
Phase displacement, cycle, etc., illustrated by means of sine curves.

Magnitudes having maximum and minimum values occurring simultaneously are said to be *in phase.* If they do not occur simultaneously, they are *out of phase.* When the corresponding maximum or minimum values of two sinusoidal alternating quantities of the same frequency occur at different instances, the two quantities are said to differ in phase by the angle between their nearest negative maxima or their nearest positive maxima or any other nearest corresponding values. The quantity whose maximum value occurs first is said to *lead* (q.v.) the other. The quantity whose maximum value occurs later is said to *lag* (q.v.). Where one quantity lags behind another by 180 degrees, the values are said to be of *opposite phase.* An alternating current may be *single phase* or *polyphase.* Another term for polyphase is *multiphase.* In a three-phase alternating current system the three separate currents differ in phase from each other by 120 degrees. In a polyphase system, if the various phases each carry or supply equal current, the system is said to be *balanced.*

PHASE ANGLE—See *Phase.*

PHASE DISPLACEMENT—The difference in phase or the phase angle between two alternating quantities, such as voltage and current, of the same frequency. Such quantities do not pass through their respective maximum positive quantities or through their zero values at the same time. The instantaneous values of any sine-shaped wave can be represented as being proportional to the sine of an angle, a complete cycle being equal to 360 degrees. When two quantities are out of phase, the respective angles corresponding to each quantity at any given instant are unequal, the difference between the two angles being called the *phase displacement* or the *phase difference.* In the accompanying illustration, the current and voltage relationship in an alternating current circuit are shown by the two sine curves. As can be seen, the current and voltage are out of phase, the phase displacement being equal to the angle Φ, in this case 90 degrees ($\frac{\pi}{2}$ radians). The current reaches its maximum value at a later time than the voltage. In this case the current *lags* behind the voltage by the angle Φ, the voltage leading the current by this angle. Since the angle of lag of the current is 90 degrees, the current and voltage are said to be in *quadrature.* In an alternating current circuit having pure inductance and no resistance (a theoretical circuit, since all electrical conductors possess resistance), the current would lag by 90 degrees as in the example given. (See *Lag, Lead, Leading Current,* also *Phase.*)



Sine curves of current and voltage, showing difference in phase.

PHENOMENA OF ELECTRIC WAVE PROPAGATION—Electric waves are created by electric *oscillations* (q.v.). They are often referred to as *radio waves.* Electric waves, light waves and radiated heat waves are included in the general term *electromagnetic waves* (q.v.). The velocity of electric waves is the same as that of light waves, 300,000,000 meters per second or 186,000 miles per second (appx.). Electric waves used for radio work have frequencies from about 10,000 to 3,000,000 cycles per second. Since the velocity of electric waves is known, it is possible to calculate the length of a wave if the frequency is known. Thus if the electric wave has a frequency of 10,000 cycles per second, the wavelength is found by dividing the velocity in meters per second by the frequency in cycles per second, which gives in this case a wavelength of 30,000 meters. Electric waves are in reality a combination of electromagnetic and electrostatic disturbances in space. The displacements are at right angles to the motion of the wave train. The electric field and the magnetic field are at right angles and travel together. They spread out or expand from the point of disturbance just as water waves spread out from a point where a stone strikes the surface of the water. Electric waves are propagated from an aerial when certain forms of alternating current flow in the aerial. Since the frequency of the propagated wave corresponds to the frequency of the current in the aerial, high frequency current must flow in the aerial to produce the high frequency electric waves used in radio. Such current may be produced by a high-frequency generator, by a direct current generator and an electric arc, or by means of vacuum tubes. The latter offer the simplest means of producing the rapidly reversing currents. Electric waves may be classified as *continuous* and *discontinuous.* Examples of the former are the waves produced by a high frequency alternator, an oscillating vacuum tube or a Poulsen arc. Examples of the latter are the waves produced by condenser discharges in a spark circuit. In these the amplitude of the waves diminishes in each wave train and the waves are referred to as *damped* waves. The high frequency current used to produce continuous waves used in radio telephony is *modulated* in accordance with the vibrations of a *microphone* (q.v.). As a result modulated waves are sent out from the aerial and these correspond in wave form to the variations of the sound waves. The sensitive apparatus at the distant receiving set picks up or intercepts the modulated electric waves, reconverts them to high frequency electric currents which are rectified into direct currents capable of actuating a 'phone and usually amplified so that they have energy enough to operate a loud speaker. (See *Oscillator, Carrier Wave,* also *Modulated Currents.*)

PHILLIPS, Raymond—British radio expert. Born October 6, 1879, he was educated at Edgebaston, Birmingham Schorne College, Buckinghamshire, and Windsor High School. For three years he was engaged on railway constructions and repairs, with special application to electric railways. In 1902 he invented a system of automatic train control and a number of appliances for electric railways which were widely adopted. In 1905 he took up the study of wireless and specialized in the control of mechanisms at a distance by electric waves. In 1910 he patented a system for controlling airships by radio and by means of a working model demonstrated how an airship could be thus controlled. During the World War he was inspector of ordnance machinery and in 1921 was appointed a member of the Inter-Allied Commission of Control in Germany. He is the author of many articles on the control of machines by electric waves.

PHONOGRAPHIC RECORDING—This refers to the amplifying of code signal currents by means of relays in tandem until the sounds produced in a telephone receiver are loud enough to cut a distinct record on the wax of a phonograph. The signals can be received at high speed and thereafter read at low speed. Instead of a phonograph a telegraphone may be used.

PHOTO-ELECTRIC EFFECT—A change in the electrical conductivity of a gaseous or solid substance when radiations of certain wavelengths come in contact with them. This refers particularly to rays of the visible spectrum and ultra-violet and infra-red rays.

PHOTOGRAPHIC RECORDER—A device for recording high-speed wireless messages by recording the deflections of a sensitive galvanometer on a moving photographic film. (See *Auto-Receiver.*)

PICKARD, Greenleaf Whittier—American radio expert. He was born at Portland, Maine, on February 14, 1877, and was educated at Westbrook Seminary, Lawrence Scientific School, Harvard and Massachusetts Institute of Technology. He made a special study of wireless telegraphy and telephony and has taken out many United States and foreign patents for radio inventions. He is noted for his pioneer work in radio telephony. Pickard began radio work in 1899 at Blue Hill observatory, Milton, Massachusetts, under a grant from the Smithsonian Institute. He was on the engineering staff of the American Telephone and Telegraph Company from 1902 to 1906. Later he was connected with the Wireless Specialty Apparatus Company as consulting engineer. He has an extensive practice as a patent expert in radio patent litigation. Pickard is a fellow of the American Institute of Electrical Engineers, a Member of the American Chemical Society and also is a Member of the Society of Chemical Industry.

Greenleaf Whittier Pickard.

PIG-TAIL—A flexible braided or stranded copper conductor used to carry the current to the rotor of a condenser or a coupler. Pig-tails are also used on the carbon brushes of motors and generators. (See *Flexible Lead.*)

PITCH—Frequency of vibration of a sound. A shrill note is said to be of high pitch, a bass note of low pitch. The pitch of an armature winding refers to the distance from the center of a winding to the center of the next winding.

PLAIN AERIAL—An aerial having the transmitting or receiving circuit connected directly to it without the utilization of inductive coupling or any intermediate tuned circuit. An example of a plain aerial is one used to transmit code, having a spark gap in series with the aerial and the ground.

PLATE—The anode or positive electrode of a vacuum tube. The vacuum tube plate is usually made of nickel. The shape of the plate varies according to the type and construction of the tube. In some tubes the plate is tubular; in others flat. When the cathode or filament is heated, it emits electrons which pass to the grid or through the grid to the plate, depending upon the grid charge. In power tubes (transmitting) it is necessary to use some cooling device to conduct away the heat dissipated at the plate. In some cases a liquid bath or a blast of air is used or the plate may be constructed so that it can be cooled by water circulation. Other methods of preventing overheating of these tubes are increasing the area of the plate as for example increasing the diameter of a tubular plate, or blackening the surface of the plate to increase its heat emissivity.



Vacuum tubes, showing construction of plates.

PLATE BATTERY—A battery, usually referred to as the *"B" Battery* having its positive terminal connected to the plate of the three-electrode vacuum tube and its negative terminal leading to the filament. The purpose of this battery is to keep the plate voltage positive with respect to the filament so that the electrons will be attracted sufficiently to the plate. Plate batteries are usually dry cells although there are a number of storage plate or "B" batteries on the market, both of the acid and the alkaline types. It is possible to dispense with the plate battery by using a *"B" eliminator*, which is connected to the ordinary house-lighting circuit. (See *"B" Battery.*)

PLATE CIRCUIT—The circuit connected to the *plate* (q.v.) or anode of a three-electrode vacuum tube.

PLATE COMPONENT, HIGH FREQUENCY—The radio frequency current flowing in the *plate circuit* (q.v.) of a vacuum tube. (See *High Frequency Component of Plate.*)

PLATE CONSUMPTION—This refers to the current consumed in energizing the plate of a vacuum tube. Increasing the grid voltage tends to increase the plate consumption. An increasing plate voltage also increases the plate current, but tends to decrease the relatively small grid current. (See *Consumption, Current;* also *Consumption, Plate.*)

PLATE CONTROL—The vacuum tube starts oscillating at a plate voltage which will depend on the adjustments of the circuit. When the plate voltage is raised, the oscillation current becomes greater, increasing in direct proportion.

PLATE CURRENT—The current in the *plate circuit* (q.v.) of the three-electrode vacuum tube. The current passing between the plate and the heated cathode or filament.

PLATE IMPEDANCE—The total resistance offered to alternating current between the filament and the plate in a vacuum tube. It is often referred to as the *tube impedance.* The impedance is independent of the alternating current input voltage.

PLATE VOLTAGE—The voltage of the plate of a vacuum tube above the filament. The potential difference between the plate and the filament. This term is usually used to refer to the voltage of the *"B" battery* (q.v.) connected to the plate, as for example, if the 22½-volt terminal of the "B" battery is connected to the plate of the detector tube, the plate voltage is said to be 22½ volts. Soft tubes, formerly used as detectors, operated best at this voltage. Most of the amplifier tubes now used as detectors operate best with 45 volts on the plate, although these tubes vary individually, some operating better with slightly increased voltage and others with a voltage less than 45. The plate voltage generally used on the amplifiers is 90 volts. The new power reception tubes use plate voltages up to 135 volts.

PLIODYNATRON—A special vacuum tube, designed by A. W. Hull, having two grids instead of one. This tube utilizes the normal amplifying property of the vacuum tube to obtain a very high voltage amplification, as high as 1,000 fold. When such high amplification is obtained, however, the operation is unstable and extremely careful adjustment is necessary.

PLIOTRON—A name given to a highly evacuated vacuum tube used for transmitting purposes. Large pliotrons are capable of developing as high as 500 watts output since they are so highly exhausted that several thousand volts may be applied to the plate and also since they can carry a plate current of nearly one-half an ampere.

PLUG—A connecting device used extensively in radio and telephone work for making connection or "plugging in" *loud speakers* (q.v.), head sets, power supply, microphone transmitters, etc. The plug has an insulating handle and the metal contact tip is designed to fit into a standard *jack* (q.v.). A flexible wire fits into terminals in the plug, the other end of the wire being connected to the apparatus such as the loud speaker, etc. The plug connection terminals may be of the conventional small binding post type or they may consist of internal spring clips.



Cross-section of plug.

PLUG-IN COIL—An interchangeable coil, often of the honey-comb type, which can be plugged into a socket, thus permitting it to be quickly and conveniently put into or taken out of a circuit. Plug-in coils are used in some cases in receiving sets designed for operation on widely varying wave bands.

PLUG-IN TRANSFORMER—*A plug-in coil* (q.v.) specifically used as a radio frequency transformer.

POLARITY—In magnets the differentiation between *North Pole* and *South Pole.* In electrical devices or circuits, the difference between *positive* and *negative poles.* It is often necessary to determine which is the positive pole or terminal of a direct current circuit, and which the negative. There are various methods of indicating polarity. A voltmeter or an ammeter will show the direction of current flow. An extremely simple method of determining polarity is to place the two terminals in a glass jar containing salt water or some other electrolyte. A much greater number of bubbles will be observed to collect around the terminal of negative polarity. A piece of used blue print paper can be utilized to indicate polarity. It is simply necessary to moisten the paper and place the terminals on it, at a distance of about ¼ of an inch apart. The paper will be whitened at the negative terminal.

POLARIZATION—In a primary cell, the current liberates hydrogen from the electrolyte in passing through it. The hydrogen is carried to the negative plate with the current and collects there. It thus increases the internal resistance of the cell. This makes it harder for the current to pass through it and as a result the electromotive force available at the terminals is materially lowered. In addition there is a slight difference of potential between the negative plate and the hydrogen and this acts in opposition to the electromotive force of the cell. This further reduces the effective voltage of the cell. The entire effect is known as polarization. Polarization may be carried to such an extent that current can no longer flow from the cell. It may be counteracted or prevented by the use of *depolarizers* (q.v.). There are three different kinds of depolarizers. Chemical depolarizers are placed in the cell near the cathode. Substances such as manganese dioxide, potassium bichromate, nitric acid or cuprous chloride are used. When the hydrogen reaches the depolarizer it combines with it to form a new compound. Electrochemical depolarizers depend for their action upon the use of a substance which will liberate a metal such as copper at the cathode instead of hydrogen. Thus with no hydrogen present there is no polarization. Of course it is necessary to use the proper electrodes and the correct electrolyte to obtain this result. Mechanical depolarizers merely blow or sweep the hydrogen away from the cathode. Being the least effective of the three methods, the latter is seldom used. (See *Local Action.*)

POLARIZATION, ELECTRIC—The state of a dielectric when subjected to electrostatic forces. Electric polarization is synonymous with electric displacement.

POLARIZED RELAY—A relay in which a magnetized swinging arm is placed between poles of two electromagnets. When current passes, one pole must change, so that the arm is attracted by one and repelled by the other. A polarized relay is much more sensitive to weak currents than the ordinary relay.

POLES—See *Magnetic Poles.*

POLYPHASE—Referring to an alternating current system in which the circuits are divided up into two or more branches having their currents displaced in phase from each other. The term *multiphase* has the same meaning as polyphase. (See *Phase.*)

POLYPHASE ALTERNATOR—An alternating current generator wound in such a way that it supplies two or more currents which differ in *phase* (q.v.) from each other by definite phase angles. The usual form of polyphase alternator is the three-phase alternator.

PORCELAIN CLEAT—See *Cleat.*

POSITIVE ELECTRODE—In a primary cell, the zinc plate or *anode* (q.v.) is the *positive electrode,* while the *pole* of this electrode is the *negative pole* (q.v.) because it is negative in relation to the external circuit. In a storage cell, the lead peroxide plate, which is the cathode during discharge, is called the *positive electrode* and its pole the *positive pole.*

POSITIVE TERMINAL POLE—The pole or terminal out of which current is considered to flow. This is more or less of a handy convention, but is contrary to the present day knowledge of electrical flow inasmuch as electrons move from negative to positive.

POTENTIAL—See *Potential, Electric.*

POTENTIAL, DIFFERENCE OF—abbreviation P.D.—Difference of electrical level. Theoretically the potential difference between two points in an electric field is measured by the work done by the electric field on a unit point charge of positive electricity moved from one point to another without disturbing the field. Potential difference is measured in volts. It may refer to any two points in a circuit, even though there is no source of electromotive force between these points. When applied to circuit between two points not possessing a source of electromotive force, the potential difference between the two points under consideration is equal to the product of the current flowing times the resistance of the circuit between the two points. In the case of an open circuit, such as the terminals of a cell, the potential difference is equal to the electromotive force. (See *Potential, Electromotive force,* also *Volt.*)

POTENTIAL DROP—The fall in voltage in a circuit due to the resistance of the conductor. (See *Potential, Electric;* also *Potential, Difference of.*)

POTENTIAL, ELECTRIC—Electrical pressure, or the degree of *electromotive force* (q.v.). Potential is electrical level. Electrical potential can be compared with the "head" of water. Thus it is customary to measure the height or head of water above sea level, which is taken as an arbitrary base. In a somewhat similar manner, the potential of the earth is taken as zero and all potential is measured from this as an arbitrary base. With this understood, it is no longer necessary to refer to the degree of electromotive force, but simply to the electromotive force or the potential. See *Potential, Difference of,* also *Volt.*)

POTENTIAL ENERGY—Energy of position. When energy is available for the production of work, it is referred to as potential energy. Energy at work is *kinetic energy* (q.v.).

POTENTIAL RECTIFIER—A *crystal* (q.v.) or other form of rectifier which requires an initial current to pass through it to become sensitive.

POTENTIOMETER (Potential Divider)—A resistance connected across a battery or other source of electromotive force and equipped with a slider so that the voltage on another circuit may be varied from zero to the full potential of the battery. Where a gas content detector vacuum tube is used, the purpose of the potentiometer is to permit a close adjustment of the *plate battery* (q.v.) potential. The potentiometer is shunted around the filament heating or "A" battery, its resistance being so high that its power consumption is practically negligible. In tuned radio frequency sets, a potentiometer is used to control the tube oscillation. The advantage of being able to make a system oscillate is obvious, as the greatest amplification is obtained when the circuits are operated just at the point before self-oscillation starts. This condition is easily found in operation, since the instant self-oscillation starts, a whistle is heard in the phone or loud speaker when tuning to any station it is desired to receive. The use of a potentiometer to control oscillations in a tuned radio frequency circuit is illustrated in the diagram shown at Fig. 1. Potentiometers used in radio apparatus are usually made either from high resistance wire or from carbon granules. In electrical engineering work, the term potentiometer means, in general, an arrangement of circuits for measuring potential difference.


AERIAL
RADIO FREQ. TRANSF.
GRID LEAK AND COND
P
S
VARIABLE COND.
~COMBINATION UNTUNED AND TUNED R.F. AMPLIFIER USING A POTENTIOMETER TO CONTROL OSCILLATION.~
POTENTIOMETER
'A' BATT.
GROUND

Fig. 1. Tuned radio frequency circuit showing use of potentiometer to control oscillations.



Fig. 2. A simple form of potentiometer used for electrical measurements.



Illustration of a radio potentiometer, showing symbol at the right.

Using certain accessories, laboratory potentiometers can be used to measure voltages over all ranges, and by applying's *Ohm's law* (q.v.) the measurements obtained can be used to determine a wide range of current values.

The simplest form of potentiometer used for electrical measurements is shown in Fig. 2. AC is a resistance in which a constant current from the battery B is flowing. F is a regulating resistance used to compensate for the variations of the electromotive force of the battery. The current in AC is checked for constancy by noting that the drop in potential between the two points selected in it is equal to the electromotive force of a standard cell. The standard cell is connected in the circuit GHJ at J and the regulating resistance is adjusted until the sensitive galvanometer shows no deflection. With the assumption that AC has a uniform resistance throughout its length, and the current in it remaining constant, it is obvious that any other voltage not greater than the drop between A and C can be measured by connecting it in the circuit at J and shifting the points G and H until the galvanometer again comes to a balance.

A direct reading scale may be placed between A and C. For ordinary potentiometer measurements, the drop between A and C is made about 1½ volts as this is approximately the electromotive force of a standard Clark cell.

POULSEN ARC—An arc usually burned in hydrogen between a rotating carbon cathode and a water-cooled copper anode in a magnetic field. This arc is connected to an oscillating circuit, and due to its instability it maintains continuous oscillations which are utilized for the production of continuous waves for radio telegraphy and telephony.

POULSEN, Valdemar—Danish radio pioneer. Born in Copenhagen, November 23, 1869; he was educated at Copenhagen University and in 1893 he joined the Copenhagen Telephone Company. In 1903 he invented his famous system of arc transmission. Poulsen is a fellow of the Danish Society of Sciences. In 1900 he was awarded the Grand Prix at Paris.

POUNDAL—A unit of force. That force which acting on a mass of one pound gives it a velocity of one foot per second. It is equal to the weight of a pound mass divided by the acceleration of gravity; equal to 13,825 dynes or approximately half an ounce.

POWER—The rate of doing work. A certain amount of work may be done in a day or in a week. In the former case, more power is expended than in the latter case. Mechanical power is measured in *horse power* (q.v.). One horse power is equivalent to 33,000 foot-pounds per minute. Since power is the rate of doing work, the expression for power must contain a time element and a work element. Work is a measure of a force exerted through a distance. Hence the foot-pound measures work. Electrical power is the product of voltage times amperage. It is measured in *watts* (q.v.). (See *Kilowatt.*)

POWER AMPLIFIER—See *Power Amplification.*

POWER AMPLIFICATION—Amplification by means of apparatus consisting of a combination of power vacuum tubes, designed to carry larger currents than the ordinary tubes and specially designed transformers. Power amplifiers provide additional audio amplification and are used in connection with radio receiving sets where great volume is required as in the case of apparatus used for public address systems and for use with power operated loud speakers. (See *Amplifier.*)

POWER AMPLIFICATION COEFFICIENT—The ratio of the plate output power to the grid input power of a vacuum tube. This value may be as high as 10,000. The output power of a vacuum tube comes from the plate battery. When the grid is operated at low or negative voltage, the input power needed to produce the changes in grid voltage may be made very small compared with the output power of the tube.

POWER, APPARENT—The product of the voltage and the current in an alternating current circuit expressed in volt-amperes. This expression does not take into account any difference in *phase* (q.v.) between the voltage and the current. Thus in an extreme case (theoretical) where an alternating current flows in a purely inductive circuit, the current will lag behind the voltage by a phase angle of 90 degrees. In such a circuit, the *true power* (q.v.) would be zero, since the cosine of the phase angle between the current and the voltage would be zero, whereas the apparent power might be quite high and a heavy current might be flowing in the circuit. Apparent power is ordinarily expressed in *kilovolt-amperes* (q.v.). (See *Power Factor.*)

POWER FACTOR—The ratio of the *true power* (watts) in an alternating current circuit to the *apparent power* (volt-amperes). Where the wave form of the alternating current is sinusoidal, the power factor is equal to the cosine of the angle between the voltage and the current. Expressed as an equation, power P is equal to the product of the current I and the component of the impressed electromotive force which is in phase with the current, E cos Φ, where Φ is the angle of phase displacement between the current and the voltage ($P = IE \cos \Phi$). Expressed in another way, the power factor is the fractional amount which, if multiplied by the effective values of the current and the voltage, will give the value of the power expended. (See *Effective Electromotive force, Power, Apparent,* also *Power, True; Kilovolt-ampere, Kilowatt.*)

POWER, TRUE—The product of the *apparent power* and the *power factor* (q.v.) in an alternating current circuit. A wattmeter will measure true power, inasmuch as it takes into account the *phase displacement* (q.v.) between the current and the voltage. A voltmeter and an ammeter cannot be used to measure power, however, since the product of the two readings only gives the apparent power.

POWER TUBE—See *Vacuum Tube, Power.*

PRACTICAL UNITS—In the practical system of electrical units, the ohm, the ampere and the volt are the fundamental units. While the practical system is based originally on the Centimeter Gram Second systems, it is in no way dependent upon these systems for practical use. When used with the fundamental units of length and time, all other electrical as well as magnetic units can be derived from the fundamental units of the practical system. At the recommendation of the Chicago International Electrical Congress in 1893, the fundamental electrical units of the practical system were adopted as legal units in the United States by an act of Congress, July 12, 1894.

P R B—International Radiotelegraphic Convention abbreviation. Followed by question mark it means, "Do you wish to communicate by means of the International Signal Code?" Without the question mark it means, "I wish to communicate by means of the International Signal Code." (See *Abbreviations, International Radio Telegraphic Conventional.*)

PRESSURE—See *Potential, Electric.*

PRESSURE, ELECTRICAL—The term is synonymous with *voltage* (q.v.) or *electromotive* force (q.v.). Electrical pressure is the cause of current flow. It is measured in *volts* (q.v.). The flow of electricity along a conductor is analogous to the flow of water through a pipe. In order to make water flow, a pump is often used to force the water or in other words to apply pressure. Similarly, electrical pressure must be applied in order for an electric current to flow.

PRIMARY CELL—A device for transforming chemical energy into electrical energy. It consists of two different conductors placed in a liquid which acts chemically on one conductor, or more on one conductor than on the other, thus keeping a difference of potential between them. While the cell is being discharged either one or both of the conductors is used up and the liquid is also consumed. In many types of primary cells these can be replaced. The liquid is called an *electrolyte* (q.v.). In some cases an acid is used while in others a salt solution is the *electrolyte.* (q.v.) (See *Cell, Cell Secondary; Cell, Theory of Primary; Electrolysis, Local Action, Polarization,* also *Storage Cells.*)

PRIMARY CIRCUIT—A circuit supplying current to another which is called the secondary circuit. The two circuits are usually coupled by means of a transformer, the primary winding being in the primary circuit and the secondary winding being in the secondary circuit.

PRIMARY CURRENT—See *Current, Primary.*

PRIMARY ELECTRONS—The main stream of electrons given off by the hot filament of a vacuum tube, as differentiated from *secondary electrons* (q.v.) which may be detached from the plate by the impact of the primary electrons. (See *Negative Resistance.*)

PRIMARY TUNING INDUCTANCE—A variable inductance in the primary circuit of a radio transmitter. It is also referred to as the *aerial tuning inductance.* The aerial inductance coil may be continuously variable utilizing a sliding contact which bears on an edgewise copper strip or it may be of the drum type, in this case being made of stranded copper cable. (See *Inductance Coils,* also *Pancake Coils.*)

PRINCE, Charles Edmond—British radio expert. Born in 1874 at Cape Town and educated at Clifton and Faraday House, he joined the Marconi Wireless Telegraph Company in 1907, where he was concerned chiefly in research work on wireless telephony. In 1909 he carried out experiments in Italy and Switzerland with the first Marconi Field Station and made a number of valuable improvements in the Bellini-Tosi direction finder. In the World war, he joined the Royal Flying Corps and in 1915 he installed the first radio telephone on aircraft.

PRINTER, MORSE—See *Morse Inker.*

PROTON—A unit of positive electricity. The smallest quantity of positive electricity capable of existing in a free state. A minute particle or quantity of positive electricity carried by the nucleus of a hydrogen atom. See *Electron Theory,* also *Free Electrons.*

PULSATING CURRENT—A periodic current, that is to say a current passing through the successive equal cycles of values, the average value of which is not zero. A pulsating current is the sum of an alternating and a direct current. A current which varies regularly in magnitude is said to be pulsating while if it remains the same in magnitude it is called continuous. (See *Continuous Direct Current,* also *Current, Pulsating Direct.*)

PULSATING DIRECT CURRENT—See *Pulsating Current.*

PUPIN, Michael—American radio authority. Born in Hungary, October 4th, 1858, he came to the United States at the age of 10, and was educated at Columbia University. He also studied at Cambridge University, England. In 1891 he was appointed professor of mathematical physics at Columbia University, where he carried out an important series of researches in radio telegraphy and telephony. He is the holder of a large number of patents relating to telephony and radio, has done valuable research work on reso-

Michael Pupin.

nance and has developed radio circuits of extreme selectivity.

PUSH-PULL AMPLIFICATION—A method of connection in a vacuum tube receiving set, for supplying more power to the loud speaker than that ordinarily obtainable from a one or two stage audio amplifier. In the push-pull amplifier two tubes are used in the final stage of the amplifier, connected in such a way that they are used alternately on the two halves of each audio frequency cycle. A push-pull amplification circuit is shown in Figure 1. The first tube at the left gives the first stage of amplification and the other two in combination give the second stage. An ordinary audio frequency amplifier transformer is connected to the grid and filament of the first tube. Special transformers are usually used for the other two transformers. These have connections brought out from the center point of one of the windings as shown. The transformer between the two stages has a split secondary while the last transformer has a split primary. In cases where a tapped wound transformer is not available, two transformers can be used instead. In this case the two primary windings are connected in series and the two secondary windings are also connected in series. Figure 2 shows the method of connecting two transformers for this purpose, a connection being made to the mid-point between the secondary windings. It is essential that the two windings in series be connected so that they are continuous in the same direction around the transformer cores. In theory, the push-pull amplifier uses one tube during one half of the cycle and the other tube during the other half of the cycle. While the terminal of the secondary transformer winding leading to the grid of the tube is at a positive potential with respect to the middle of the winding, the tube is effective. During the remaining half of the cycle when the terminal is negative with respect to the tap, the tube is not operating. The action however is such that one tube is effective at all times. Although ordinary amplifier tubes can be used in the push-pull amplifier circuit it is desirable to use special power tubes which have a high amplification coefficient.



Fig. 1. Diagram of a push-pull amplification circuit.



Fig. 2. Method of connecting two transformers where a tapped wound tranformer is not available.

PYRITES—Compounds of iron or copper and sulphur. Three of these are *Ferrous Sulphide* (FeS), *Bisulphide* (FeS_2), and an intermediate known as *Magnetic Pyrites* (Fe_3S_4). Pyrites crystals have been used in radio as detector crystals. (See *Crystal*, also *Crystal Detector*.)

PYRON DETECTOR—A *crystal detector* (q.v.) having an iron pyrites crystal and a copper or other metallic contact point.

Q

Q SIGNALS—International Radiotelegraphic Convention abbreviations. When the signal is followed by a question mark it asks the question. Otherwise the answer is indicated. A list of these abbreviations and their meanings follow:

Abbrev'n	*Question*	*Answer*
QRA	What ship or coast station is that?	This is . . . .
QRB	What is your distance?	My distance is . . . .
QRC	What is your true bearing?	My true bearing is . . . degrees.
QRD	Where are you bound for?	I am bound for . . .
QRF	Where are you bound from?	I am bound from . . . . .
QRG	What line do you belong to?	I belong to the . . . Line.
QRH	What is your wave length in meters?	My wave length is . . . . meters.
QRHH	What tune shall I adjust for?	Adjust to receive on tune . . . .
QRJ	How many words have you to send?	I have . . . . words to send.
QRK	How do you receive me?	I am receiving well.
QRL	Are you receiving badly? Shall I send 20 . . . — . for adjustment?	I am receiving badly. Please send 20 . . . — for adjustment.
QRLL	Request permission to test . . . minutes.	Permission to test granted.
QRM	Are you being interfered with?	I am being interfered with.
QRN	Are the atmospherics strong?	Atmospherics are very strong.
QRO	Shall I increase power?	Increase power.
QRP	Shall I decrease power?	Decrease power.
QRQ	Shall I send faster?	Send faster.
QRS	Shall I send slower?	Send slower.
QRT	Shall I stop sending?	Stop sending.
QRU		I have nothing to transmit. I have nothing for you.
QRV	Are you ready?	I am ready. All right now.
QRW	Are you busy?	I am busy (or, I am busy with . . . . Please do not interfere).
QRX	Shall I stand by?	Stand by. I will call you when required.
QRY	When will be my turn?	Your turn will be No. . . . .
QRZ	Are my signals weak?	Your signals are weak.
QSA	Are my signals strong?	Your signals are strong.
QSB	Is my tone bad? Is my spark bad?	The tone is bad. The spark is bad.
QSC	Is my spacing bad?	Your spacing is bad.
QSD	What is your time?	My time is . . . .
QSF	Is transmission to be in alternate order or in series?	Transmission will be in alternate order.
QSG		Transmission will be in a series of 5 messages.
QSH		Transmission will be in a series of 10 messages.
QSJ	What rate shall I collect for?	Collect . . . .

Abbrev'n	*Question*	*Answer*
QSK	Is the last radiogram cancelled?	The last radiogram is cancelled.
QSL	Did you get my receipt?	Please acknowledge.
QSM	What is your true course?	My true course is ..... degrees.
QSN	Are you in communication with land?	I am not in communication with land.
QSO	Are you in communication with any ship or station (or: with ....)?	I am in communication with .... (through .....
QSP	Shall I inform .... that you are calling him?	Inform .... that I am calling him.
QSQ	Is ..... calling me?	You are being called by ....
QSR	Will you forward the radiogram?	I will forward the radiogram.
QSS	Are my signals fading?	Your signals are fading.
QST	Have you received the general call?	General call to all stations.
QSU	Please call me when you have finished (or: at . . o'clock).	Will call when I have finished.
QSV	Is public correspondence being handled?	Public correspondence is being handled. Please do not interfere.
QSW	Shall I increase my spark frequency?	Increase your spark frequency.
QSX	Shall I decrease my spark frequency?	Decrease your spark frequency.
QSY	Shall I send on a wave length of .... meters.	Let us change to a wave length of .... meters.
QSZ		Send each word twice. I have difficulty in receiving you.
QTA		Repeat the last radiogram.
QTC	Have you anything to transmit?	I have something to transmit. I have one or more radiograms for ......
QTE	What is my true bearing?	Your true bearing is .... degrees from ......
QTF	What is my true position?	Your true position is .. latitude ..... longitude.

QUADRANT—A term formerly in use as the unit of *inductance* (q.v.), now called the *henry* (q.v.). Inductance has the same dimensions as length and this unit is equivalent to 10^9 cm., this being approximately the length of one quadrant of the earth.

QUADRANT ELECTROMETER—A sensitive *electrometer* (q.v.) which in its calibrated form is known as an *electrostatic voltmeter* (q.v.). In the usual type, the "needle" consists of a thin aluminum plate suspended on delicate knife edges, with a pointer extending from the upper part to a scale. Two pairs of quadrant plates, having opposite faces metallically connected together, are placed on either side of the movable plate and parallel to its face. Each pair is insulated from the other pair. When the pairs of quadrants are subjected to a difference of potential, the needle, if highly charged, will be attracted into one pair or repelled out of the other. (See *Kelvin's Electrostatic Voltmeter.*)

QUADRATURE—The differing in *phase* (q.v.) of two alternating current quantities by 90 degrees. For example, when the current lags behind the impressed voltage by 90 degrees, as in the case of pure inductance in a circuit, the current and the voltage are said to be in quadrature. (See *Lag, Lead,* also *Leading Current.*)

QUANTITY OF ELECTRICITY—When referring to static electricity, it is the amount of the charge. Referring to electricity in motion, or an electric current, it is the amount of current flowing in a given time. Quantity of electricity is measured in *coulombs* (q.v.). The coulomb is the quantity of electricity which has passed when a current of one ampere flows for one second. The symbol which is usually used to signify quantity of electricity is Q.

QUANTOMETER—A type of ballistic galvanometer in which the swing of the movable system is proportional to the quantity of electricity passing through the instrument. A *galvanometer* (q.v.) of this type is used for magnetic testing as in the case of the *fluxmeter* (q.v.).

QUARTER PHASE—A two-phase alternating current system. An alternating current system having two currents differing in phase by 90 degrees or in other words by one-quarter of a cycle.

QUARTZ LAMP—A mercury vapor lamp which utilizes a tube of quartz instead of a glass container. Increased current densities can then be employed, since higher temperatures can be used with quartz than with glass.

QUARTZ OSCILLATOR—The piezo-electric quartz plate may be used as a *resonator* (q.v.) or as an *oscillator* (q.v.). When used as an oscillator it may be used either as a *master oscillator* controlling the frequency of a radio transmitting station's output or as a frequency indicator. All three of these uses are applicable to the work of maintaining station frequencies constant. The applicability of the piezo oscillator as a frequency indicator in broadcasting stations has been tested carefully by the United States Bureau of Standards, and found to be useful and satisfactory. This method gives a means of maintaining an extremely accurate check of the transmitting station frequency. (See *Master-Oscillator System,* also *Frequency Meter.*)

QUENCHED GAP—See *Quenched Spark Gap.*

QUENCHED SPARK—See *Quenched Spark Gap.*



A typical quenched spark plug.

QUENCHED SPARK GAP—A spark discharger in a wireless telegraph transmitting circuit in which the spark is deionized to prevent the gap remaining conductive after the spark has passed. In this way only a few sharply defined oscillations are permitted to occur. The particular advantages of the quenched spark gap is that it enables the aerial to oscillate at its own frequency regardless of the period of the spark system. In one form of construction, a number of heavy copper plates are used, separated by micanite, fiber insulating washers or other insulating material. These are placed in an iron rack and compressed by means of a pressure bolt. The inside edge of the washer rests upon a groove which is cut in each plate. This makes it impossible for the spark to discharge over the edge of the washer. In order to make the discharge surface airtight, the washers are specially treated and as a result this helps in quenching the primary oscillations and makes the discharge noiseless. A small motor driven blower is mounted at the base of the spark discharger for the purpose of forcing air through the base of the rack against the cooling flanges of the plates. (See *Deionization, Musical Spark, Kinraidy Spark Gap,* also *Quenched Spark Transmitter.*

QUENCHED SPARK TRANSMITTER—A radio telegraph transmitter which employs a quenched spark gap. The quenched spark transmitter is not used for very high powers as it is not satisfactory for such use. In this case, a form of disc discharger is usually used. The quenched spark transmitter, however, has no moving parts and is noiseless in operation. In addition it gives large values of antenna current because closer coupling is possible. (See *Quenched Spark Gap.*)

QUICK BREAK SWITCH—A switch provided with auxiliary contacts which are released after the main contacts. The auxiliary contacts are separated rapidly, regardless of the speed with which the switch handle is pulled. This action is obtained by the tension of a spring connected between the main switch blade and the auxiliary blade, as shown in the illustration.



Quick Break Switch. Note the auxiliary spring-controlled blade.

QUIESCENT AERIAL—In a radio telephone transmitter, an aerial operated in such a manner that the carrier wave is suppressed when transmission is not actually taking place.

R

"R"—Symbol for *resistance* (q.v.)

RADIANT ENERGY—Energy transmitted through space by means of vibrations of the ether, such as electromagnetic energy, light or heat. (See *Actinic Ray.*)

RADIANT HEAT—Infra-red *radiation* (q.v.) as for example radiation from substances at temperatures insufficient to cause visible light rays.

RADIATING CIRCUIT—An electrical circuit which emits energy in the form of ether waves. In a transmitting system, the aerial circuit. Any circuit which radiates energy is a radiating circuit.

RADIATION—The transference of energy in waves through space which is not necessarily occupied by matter. Transference of energy through *ether* (q.v.). Electric or electromagnetic radiation refers to the radiation by means of electromagnetic induction. The radiation field is transmitted by wave motion. Various types of electromagnetic waves may be sent out by a radiating system. In one system the waves are known as *damped waves* (q.v.), in another *undamped waves* (q.v.) are used.

RADIATION EFFICIENCY—The radiation efficiency of an antenna at a given wave length is the ratio of the power radiated to the total power delivered to the antenna (resistance).

RADIATION FROM ANTENNA—In the case of a simple vertical antenna, electromagnetic waves are radiated in semi-loops since the lower end of the aerial is grounded. Fig. 1 gives an idea of the way in which the intertwined electric and magnetic fields radiate from the antenna. It should be noted that the electric and the magnetic fields are in planes which are at right angles to each other. The electric lines are shown in elevation while the magnetic lines appear in plan, with the wave form common to both being shown between. At any single point in space, the lines separate and come together like a bellows. After the wave has travelled a certain distance, the lines can be regarded as sections of planes and the electric lines can be represented by the diagram shown in Fig. 2. The magnetic lines can be shown by the same figure, provided this is considered to have been rotated about its horizontal axis through an angle of 90 degrees. Regardless of whether the aerial is of the open or closed coil type, the radiation will take place in the same general way, *loops* (q.v.) being formed and detached as described. (See *Electromagnetic Waves,* also *Height of Aerial.*)



Fig. 1. Electric and magnetic fields about a vertical wire aerial.



Fig. 2. Electric lines of force shown after the wave has travelled some distance from the aerial.

RADIATION RESISTANCE—The ratio of the total power radiated by an antenna to the square of the effective current at the point of maximum current. The property of an antenna by means of which radiation of energy takes place. Some of the power supplied to a circuit, carrying radio currents, is radiated in the form of electric waves. The radiation is a measure of the useful work obtained from the circuit. The greater the power radiated in comparison with the power dissipated in the circuit itself, the better will be the transmission. At any frequency, the power radiated is proportional to the square of the current flowing, hence the radiative effect may be regarded as causing artificially, an increase in the effective resistance of the circuit. This resistance increase is known as "radiation resistance" and is directly proportional to the square of the frequency or inversely proportional to the square of the wave length. (See *Antenna Resistance.*)

RADIATION TRANSMISSION—See *Radiation from Antenna.*

RADIO—The transmission of intelligence by means of electromagnetic waves through the ether. Radio falls under two general classifications; *radio telephony* (q.v.) and *radio telegraphy* (q.v.). (See *Radio Channel, Radio Communication, Radio Control,* also *Radio Frequencies.*)

RADIO-ACTIVITY—The emanation of energy by certain substances, such as radium, caused by a continuous detachment of electrons from the substance.

RADIOCAST—A term sometimes used instead of *Broadcast* (q.v.). To transmit speech, music or other sounds by *radio telephony* (q.v.).

RADIO CHANNEL—A band of wave lengths or frequencies of a width sufficient to permit of its use for radio communication without the radiation of subsidiary waves of more than a certain intensity at wave lengths or frequencies outside of such a band.

RADIO COMMUNICATION—The transmission of intelligible signals by means of electromagnetic waves. The signals may be in the form of code as in radio telegraphy or in the form of speech or music as in radio telephony. They may be transmitted through the *ether* (q.v.) without the use of intervening conductors as in ordinary radio, or along conductors as in *wired wireless* (q.v.).

RADIO COMPASS—A simple form of radio *direction finder* especially used for marine work. The radio compass depends for its principle of operation upon the directional effect of a coil antenna. Hence a coil antenna mounted on a vertical axis so that it can be rotated freely, is an essential part of the radio direction finder. By rotating the coil while a particular station is transmitting, it is possible to fix the line of direction of the station. The coil may be mounted so that the maximum signal will be received when the transmitting station lies in the plane of the coil. The device may also be set for minimum signal reception in which case the transmitting station lies in a direction perpendicular to the face of the coil. It is possible to obtain a much sharper determination of direction by setting the coil on the minimum position and hence this method is generally used for direction finder work. (See *Goniometer.*)

RADIO CONTROL—The control of motor driven devices such as marine vessels, trains, torpedoes, automobiles, etc., by means of special radio receiving apparatus designed to respond to radio impulses. E. P. Glavin's radio controlled automobile is an example of the radio controlled vehicle. *John Hays Hammond, Jr.* (q.v.) has invented radio controlled torpedoes, radio controlled ships and also radio controlled air craft.

R.F.—Abbreviation for radio frequency.

RADIO FREQUENCIES—Frequencies higher than those corresponding to normally audible sound waves. (See *Frequency, Radio; Frequency, High; Audio Frequency;* also *Frequency, Low.*)

RADIO FREQUENCY COILS—*Inductance coils* (q.v.) used to carry radio frequency currents or to couple radio frequency circuits. Radio frequency *transformers* (q.v.) may be of either iron core or air core types although the air core transformers are more generally used. (See *Low Loss Coils,* also *"D" Coils.*)

RADIO FREQUENCY CURRENT—An alternating current having a frequency of from 20,000 to 2,000,000 cycles per second. There is no hard and fast rule regarding the upper and lower limits, since much higher or much lower frequencies may still be considered as radio frequency currents. (*See High Frequency Current.*)

RADIO FREQUENCY SELECTIVITY—The radio frequency selectivity of a simple element of a receiving system is the ratio of resonant response (in terms of effective voltage or current measured at the indicator) to the nonresonant response when the radio frequency portions of the elements of that system are detuned by one percent of the resonant frequency. In this case, a simple element refers to a combination of an inductance, a capacitance and optionally a resistance.

RADIO FREQUENCY SIGNALS—Currents flowing in a radio receiving circuit up to the point of rectification. The currents flowing in the antenna circuit are radio frequency currents corresponding to the currents flowing in the transmitting aerial. (See *Amplifier, Radio Frequency.*)

RADIO GONIOMETER—See *Goniometer.*

RADIOGRAM—A message sent in code by radio. A radio telegraphic message.

RADIOPHARE—A radiotelegraphic "lighthouse" intended to aid navigation by emitting characteristic signals. By estimating the bearings of two charted radiophares, the mariner may determine the position of his ship.

RADIO TELEGRAPHY—The transmission of messages by means of electromagnetic waves using dot and dash code signals. A transmitter furnishes a source of high frequency alternating current which oscillates rapidly in the antenna system thus sending out electromagnetic waves. These are intercepted at the receiving station by the receiving aerial. At the receiving aerial, the electromagnetic waves are changed back into alternating current which is rectified by a detector in the receiving apparatus, then amplified and made audible in a *head telephone* (q.v.) or *loud speaker* (q.v.). Of course, a means of interrupting the current to produce dots and dashes must be present in the transmitter and suitable tuning devices are used in both the transmitter and the receiver.

RADIO TELEPHONY—The transmission of speech, music or other sounds by means of electromagnetic waves. In the standard systems of radio telephony continuous waves are used of a much higher frequency than those of audible sounds. The amplitude of these is modulated by the connection of a microphone in the transmitting circuit. The receiving apparatus is similar to that employed in radio telegraphy and is arranged so that the head set or loud speaker responds to the modulations of the waves and reproduces the sounds as originally produced at the transmitter.

RADIO TRANSMISSION—The sending of signals, speech, music, or other sounds by means of electromagnetic waves. The transmission of intelligence through the ether. (See *Radio Communication, Radio Control, Radio Telegraphy,* also *Radio Telephony.*)

RAT-TAIL—A single wire, or a group of wires used to connect the main part of an aerial with the *lead-in* (q.v.) wire.

RATIO—Relative values of quantities of the same kind, or number of times one quantity is contained in the other.

RATIO OF TRANSFORMATION—The ratio between the primary and secondary windings of a transformer. This determines the ratio of the primary to the secondary voltages. Thus if a transformer has a ratio of transformation of 3 to 1, then the secondary will have three times as many turns as the primary and the secondary voltage will be, approximately triple that of the primary voltage.

RATIO OF UNITS—The ratio of the unit pole in the electromagnetic system to the unit pole in the electrostatic system, or of the unit charge in the electromagnetic system to the unit charge in the electrostatic system. Its numerical value is approximately 3×10^{10}.

RAYLEIGH, John William Strutt—British physicist. Born at Langford Green, Essex, November 12th, 1842. He was educated at Trinity College, Cambridge. In 1879 he was appointed Cavendish professor of experimental physics in succession to Clerk-Maxwell, a post he held until 1884. In 1887 he became professor of natural philosophy at the Royal Institution and was appointed president of the Royal Society in 1905. In 1908 he was appointed Chancellor of Cambridge University, and died June 30th, 1919. Rayleigh was considered by many to have been one of the most brilliant experimental physicists of the nineteenth century. He not only had a remarkable power of mathematical analysis, but was equally skillful in carrying out the experimental proofs of his theoretical researches. Many of his experiments were made with home-built apparatus. He threw a fresh light on nearly every branch of physics, from the theory of gases to wave theories and electric and magnetic problems. Due to the care with which he carried out his experiments, he was the first to detect the presence of neon in the atmosphere, this being the forerunner of the discovery of a number of inert gases in the atmosphere. The Rayleigh balance for absolute current measurement is as well known as it is important. Lord Rayleigh was one of the original members of the Order of Merit. In 1882 he was awarded the Royal Medal, in 1899 the Copley Medal of the Royal Society and in 1904 the Nobel Prize for physics.

REACTANCE—That property of an electric circuit, aside from its ohmic resistance, which tends to oppose the flow of an alternating current. Mathematically, reactance is defined as the square root of the difference between the square of the *impedance* (q.v.) and the square of the effective resistance of a given portion of an electric circuit. Expressed as an equation reactance $x = \sqrt{z^2 - r^2}$ where z is the impedance and r the resistance of the part of the circuit under consideration. Reactance due to capacity in a circuit is capacity or condensive reactance. The reactance of a condenser of capacity C to an alternating current (of sine wave form) of frequency f is expressed by the equation $X_C = \frac{1}{2\pi fC}$. Reactance due to inductance in a circuit is *inductive reactance* (q.v.). The reactance of an inductance coil of inductance L to an alternating current (of sine wave form) of frequency f is expressed by the equation $X_L = 2\pi fL$. Reactance is measured in *ohms.*

REACTANCE COIL—REACTION COIL—Terms used in England to describe the *tickler coil* (q.v.) used in regenerative sets to couple back part of the energy in the plate or output circuit to the input circuit.



The current represented by vector OA may be considered as divided into two components, OC in phase with the voltage, and CA the reactive component.

REACTIVE COMPONENT—The component of an alternating current used to overcome the reactance of the circuit. This component acts at an angle of 90 degrees from the voltage. It is also known as *wattless current* (q.v.).

REACTIVE CURRENT—See *Reactive Component.*

REACTIVE DROP—The portion of the voltage drop in an alternating current circuit, due to the reactance.

REAL POWER—See *True Power.*

RECEIVER—A term rather loosely applied to cover the entire radio receiving apparatus within a station. Also sometimes used as a synonym for *Detector* (q.v.)

RECEIVING AERIAL—A wire or group of wires suspended at a suitable height and connected to a radio receiving set. The purpose of the receiving aerial is to intercept the electromagnetic waves. It should be placed well above surrounding buildings if possible, and should be well insulated from the ground. (See *Aerial,* also *Directional.*)

RECEIVING CIRCUIT—Any electrical circuit used in connection with the reception of radio. The more important vacuum tube receiving circuits are the *super-heterodyne* (q.v.), the *neutrodyne* (q.v.), the *reflex circuit* (q.v.), the *regenerative circuit* (q.v.) and the *tuned frequency circuit* (q.v.). There are various modifications and combinations of these circuits.

RECEPTACLE—A form of socket into which a plug is inserted for making electrical connections.

RECONSTRUCTED MICA—See *Micanite.*

RECORDER—A telegraphic instrument which automatically records messages sent over a telegraph system.

RECORDING WATTHOUR METER—An instrument for measuring and recording the total amount of electrical energy being consumed in a circuit. (See *Integrating Wattmeter.*)

RECTIFICATION—The changing of alternating current to direct current. In the usual radio receiving circuit rectification is accomplished by means of the vacuum tube, although the ordinary crystal detector rectifies the alternating current also. Before a storage battery can be charged from an alternating current source, the current must first be changed to direct current. Hence the battery charger designed to work on alternating current must be equipped with a rectification device, or rectifier (q.v.).

RECTIFIED CURRENT—An *alternating current* (q.v.) which has been changed to uni-directional or direct current either by preventing alternate waves from flowing or by reversing their direction. (See *Rectified Signals, Rectification,* also *Rectifier.*)

RECTIFIED SIGNALS—Radio signals which have passed through a detector, such as a vacuum tube or a crystal. Rectification of the oscillations results in audible or audio frequency currents which can be heard in a telephone receiver. (See *Rectification, Rectifier, Rectifying Tube,* also *Rectifying Action of Crystal Detector.*)

RECTIFIER—An apparatus for converting alternating current to unidirectional or direct current. Examples of rectifiers are certain crystals used as crystal detectors, the commutators of direct current motors and generators, vacuum tubes, electrolytic devices used for charging batteries, etc. (See *Rectified Signal, Rectification, Rectifying Tube, Rectifying Action of Crystal Detector, Rectified Current, Rectifier, Full Wave, Full Wave Rectification,* also *Half Wave Rectifier, Electrolytic Rectifier, Mercury Arc Rectifier, Charger, Storage Battery; Chemical Rectifier; Tungar; Rectigon.*)

RECTIFIER, FULL WAVE—A device for converting alternating current to direct current, in which both the positive and negative alternations are utilized. This differs from the half-wave rectifier which rectifies by suppressing alternate waves. (See *Full*

Wave Rectification, also *Half Wave Rectifier.*)

RECTIFYING ACTION OF CRYSTAL DETECTOR—The crystal detector has the property of allowing radio frequency alternating currents to flow through it in one direction only. In other words the alternating current is rectified. (See *Crystal Detector-Theory of Operation, Crystal Detector, Crystal Rectifier, Rectified Signals, also Rectified Current.*)

RECTIFYING TUBE—A vacuum tube used to convert alternating current into direct current. Rectification can be accomplished by a two-electrode tube, having filament and plate. In this case the electron flow is from the hot filament to the plate. A two-electrode vacuum tube made especially for rectifying purposes is known as the *kenotron* (q.v.). Another recent type of rectifying tube, known as the *helium tube* (trade name, *Raytheon*) utilizes a different operating principle, known as the "short path" principle, whereby the rarefied gas acts as an insulator between points which are in close proximity. This is in apparent contradiction of the observed phenomenon that the smaller the distance between two points the more readily a spark will jump between them due to the ionization of the gas. However, if the distance is small enough and a suitable gas is used at a low enough pressure, an electron may encounter no gas molecules in its path between the points and there will be no ionization by collision. Consequently, the inert gas helium, may be made to act as a perfect insulator at low pressures. Furthermore, it has been found that when a larger electrode of a gas conduction tube is negative, there is a greater current flow than when the smaller electrode is negative and that the smaller the positive relative to the negative electrode, the smaller is the back current and hence the more complete is the rectification. Figure 1 shows a typical helium tube, while Figure 2 illustrates its construction. The two small positive electrodes *A*, *A*, are carried through two small glass tubes imbedded in a lava insulating block *L* so as to project very slightly into a lava cup *C* whose wells constitute the negative electrode, being connected to the negative terminal through the base. The diameters of the small wires and the diameters and positions of the holes whereby they enter the cup are so proportioned as to give the necessary short path to the negative electrode. The cup *C* contains helium gas at such low pressure as to prevent gaseous conduction. This gives an insulation of great reliability and long life and makes possible extremely small anode surfaces which reduce the back current to a negligible quantity.



Fig. 1. A Raytheon tube.



Fig. 2. Construction of the Raytheon tube.

RECTIFYING VALVE—This usually refers to a *rectifying tube* (q.v.) although it may refer to an *electrolytic rectifier* (q.v.)

RECTIGON—The trade name of a storage battery charger which utilizes the vacuum tube rectifier principle. (See *Charger, Storage Battery*, also *Rectifying Tube.*)

RED MAGNETISM—An obsolete term for the lines of force coming from the north pole of a magnet.

REDUCE WAVE-LENGTH OF AERIAL—The wave-length of an antenna may be reduced by the use of series condensers. However, this method should be avoided where possible, since it results in a loss of power. Shortening the aerial is a preferable method of reducing wave-length.

REFLECTING GALVANOMETER—See *Mirror Galvanometer.*

REFLECTION—Radio waves are reflected and also refracted when they pass into a region of different dielectric constant. A perfect conducting sheet would reflect all of the wave energy striking it. A conductor parallel to the direction of motion of a wave serves to guide the direction of the wave. The reflection and other modifications of radio waves serves to explain *fading* (q.v.) and other irregularities of broadcast signals. It has been found that broadcast signals will have most uniform intensity when long waves are used and during the daytime. Moreover, transmission will be better over a uniform conducting surface, such as the ocean. It is assumed that the space through which a radio wave travels is bounded by the surface of the earth and by an upper region which during the day is a fairly good conductor. The transmitted waves are guided by the two conducting mediums but in addition are assisted materially by reflection especially during the time that the air is partially ionized by the radiation of the sun.

REFLECTION COEFFICIENT—(Of a surface of discontinuity between two media.) The ratio of the reflected field intensity near the surface to the incident field intensity near the surface.

REFLEX—See *Reflex Circuit.*

REFLEX CIRCUIT—A radio receiving circuit invented by Marius Latour in which the vacuum tubes are made to perform double duties as both radio and audio frequency amplifiers. The incoming radio frequency current is amplified at radio frequency, rectified by a detector (which may be a crystal detector) and then amplified at audio frequency, using the same tube.



A typical reflex circuit using one tube and a crystal detector.

A typical four tube reflex set uses the second and third tubes as amplifiers simultaneously for both the radio and the audio frequency amplification. As a result the four tubes are made to produce the effect of six. Reflexing may be accomplished in a number of different ways. In some cases all the tubes are made to work twice. In other cases, only a part of the tubes are used for dual amplification. A variation of the reflex circuit, is the *Inverse Duplex Circuit* (q.v.). In this system the incoming signal reaches the first tube where it is amplified at radio frequencies and passes to the second tube, where it is again amplified at radio frequencies. From the second radio frequency tube, it is passed to the detector tube, where it is converted to audio frequency. The current then flows back to the second radio frequency tube which is now used as an audio frequency amplifier. Thence it flows to the first radio frequency tube which acts as the second stage of audio frequency amplification.

REFRACTION—The refraction of electric waves is analogous to the refraction of light. The electric (radio) waves are refracted when they pass into a region of different dielectric constant. That is to say, their direction is slightly altered. (See *Fading, Gliding Theory,* also *Reflection.*)

REFRACTION AND REFLECTION OF ELECTROMAGNETIC WAVES—See *Reflection,* also *Refraction.*

REGENERATION—The amplifying properties of the three-electrode vacuum tube can be used to obtain what is termed *regeneration.* Since it is possible to have greater output energy than input energy, part of the output may be returned to the input side, thus resulting in amplification of energy or in regeneration. By *feeding back* the correct amount of energy and in the right phase relation a constant reamplification may be obtained, and the tube can be made to act as a generator of sustained oscillations. (See *Armstrong Circuits, Feed-Back, Feed-Back Coil, Feed-Back Coupling, Feed-Back Effect,* also *Regenerative Circuit.*)

REGENERATIVE—See *Regenerative Circuit.*

REGENERATIVE CIRCUIT—A method of connecting up vaccum tubes for radio reception in which the amplified variations of the plate circuit are superimposed inductively on the grid or imput circuit thus producing a reinforcing effect which results in increased sensitivity. (See *Armstrong Circuits.*)

REGENERATIVE COUPLING—A radio receiving system designed to increase amplification in a vacuum tube, by coupling the plate or output circuit back to the grid or input circuit thus producing regeneration. (See *Feed-Back, Feed-Back Coil, Feed-Back Coupling, Feed-Back Effect,* also *Regenerative Circuit.*)

REINARTZ CIRCUIT—A selective regenerative circuit devised by John L. Reinartz in which a *spider-web* inductance coil is used, the coil acting as primary, secondary and tickler. Capacity *feed-back* (q.v.) is accomplished by means of a variable condenser. In the improved Reinartz a variocoupler is used, connected as a variometer, in addition to the condenser feed-back.



Diagram showing Reinartz circuit

REJECTOR—See *Rejector Circuit.*

REJECTOR CIRCUIT—A circuit consisting of a combination of inductance and capacity for filtering out or preventing the passage of currents of certain frequencies. This circuit is used in connection with a radio receiving set to obtain greater selectivity. The inductance and the capacity are arranged in parallel to form a resonant circuit. The constants of this circuit are chosen so that at the particular frequencies to be filtered, the capacity current will exactly equal the inductive current, thus giving zero resultant current. The primary application of the rejector circuit is as an *interference eliminator* (q.v.) or *wave trap* (q.v.). Figure 1 shows the application of the rejector circuit applied to a radio receiving set. The circuit shown is a combination *acceptor-rejector* circuit. The rejector circuit is shown in heavy lines. The inductance and the capacity are connected in parallel with each other and with the acceptor circuit and this latter is inductively coupled to the receiving set circuit. Both the acceptor and the rejector circuits are tuned to the wave length of the receiving aerial. By using more than one rejector and acceptor circuit increased selectivity can be obtained. A rejector circuit used to filter out undesired spark signals is shown in Figure 2. A small inductance of about ten turns is employed in this circuit and this is inductively coupled to a closed tuned circuit and wired in series with the aerial, and the aerial terminal of the set. If a spider-web coil is used in the closed circuit, a suitable value for broadcast wave lengths is a 50 turn coil, placing the aerial coil in such a position as to get closest coupling. The variable condenser should have a capacity of .0005 mfd. (See *Acceptor.*)



Fig. 1. An acceptor-rejector circuit used as a wave trap.



Fig. 2. A rejector circuit designed to filter out undesired spark signals.

RELAY—An electromagnetic device by means of which contacts in one circuit are operated by a change in conditions in the same circuit or in one or more associated circuits. (See *Magnifier.*)



A telegraphic relay.

RELUCTANCE—Magnetic resistance. The reluctance of a magnetic circuit is analogous to electrical resistance. All magnetic circuits offer reluctance to flux. The name *rel* is widely used as the unit of reluctance. The rel is the reluctance of a magnetic circuit which will have one line of force in it, upon application of one *ampere-turn.* The rel can also be specified as the reluctance of a cylinder of air, or of any other non-magnetic material, one square inch in cross-sectional area, and 3.19 inches long. The flux through a magnetic circuit is equal to the *magnetomotive force* (q.v.) divided by the reluctance. (See *Magnetic Properties.*)

RELUCTIVITY—The *reluctance* (q.v.) per unit length and per unit cross-section. The reluctance per inch^3 or per cm^3. Reluctivity may be defined as specific magnetic resistance. It is the reciprocal of *permeability.* (q.v.).

REMANENCE—The term applied to the magnetism remaining in a magnet after the magnetizing force is removed.

REMOTE CONTROL—A control system whereby a radio transmitting or receiving apparatus may be operated at any desired distance from the apparatus. The chief advantage of remote control lies in the fact that the high tension apparatus and the tall aerial masts may be located in outlying districts whereas the studio can be located at any desired, convenient point. In addition it is possible to broadcast concerts, theatrical entertainments, prize fights, etc., direct from the scenes of action by utilizing remote control.

REPEATING COIL—A transformer of unity ratio used in telephone practice.

RE-RADIATION—The relaying of a radio wave through the action of a receiver employing regeneration. This phenomenon is most commonly observed in receivers of the *super-heterodyne* type.

RESIDUAL CHARGE—The residuary electricity retained by a condenser after discharge. This is also known as *electric residue* or *soakage.* After the condenser is discharged in the ordinary way, the residual charge permits a second discharge, smaller than the first. (See *Soaking in.*)

RESIDUAL MAGNETISM—The magnetism retained by a piece of iron, after the magnetizing force is withdrawn. After a mass of iron has become magnetized, some of the magnetism will remain, even though the magnetizing force has been taken away. The amount of residual magnetism depends on the quality of the iron. Pure wrought iron, in general, retains very little residual magnetism, whereas wrought iron which has gone through a hardening process, or which contains a large percentage of impurities and also cast iron possess a much larger amount of residual magnetism.

RESINOUS ELECTRICITY—An obsolete term for negative charges of electricity, adopted because of the fact that resinous bodies become negatively charged by friction. (See *Vitreous.*)

RESISTANCE—Symbol Ω (Omega)—Every conductor of electricity offers opposition to the flow of electricity. Resistance is a property of the conductor itself. It increases with increased length of conductor, decreases with increased cross-sectional area, and is greater or less depending upon the material of the conductor. Resistance is measured in *ohms.* (q.v.). The ohm is equal to 10^9 C.G.S. electromagnetic units.

RESISTANCE BOX—A box containing a number of wire coils of known resistances connected in various combinations, by means of switches or plugs, to produce any desired total resistance.


A resistance box.

RESISTANCE COUPLED AMPLIFIER—A type of *amplifier* (q.v.) which utilizes high resistances for interstage coupling.



Fig. 1. The introduction of the non-inductive resistance in the plate circuit of the tube is the first step for explaining the principles involved.

Resistance coupled amplification is generally used only for audio frequency amplification although it may be used for radio frequencies above 1000 meters. The chief advantage of resistance coupling consists in the purity of tone obtainable and the absence of distortion. In addition radio receivers of this type are comparatively inexpensive to build. It should be noted, however, that with resistance coupled amplification, the amplification per tube is much less than with transformer coupled amplification and furthermore the drain on the "B" batteries is also much greater.



Fig. 2. In this circuit there must be two sets of batteries, but even then the grid of tube No. 2 will have a positive bias, which is undesirable.

Of course, where a "B" eliminator is used "B" battery consumption is not a consideration. The resistances used for resistance coupling are non-inductive and may have resistances of from .1 megohm to 2 megohms. Figure 1 shows an elementary circuit utilizing a non-inductive resistance in the plate circuit of the tube. When a signal is impressed upon the grid circuit of this amplifying tube, there is a corresponding voltage set up in the plate circuit. The resistance R in the plate circuit causes a voltage drop to take place in two places in the tube.



Fig. 3. The resistance coupled amplifier circuit with the introduction of a grid leak and condenser. The reasons for this are explained in the accompanying text.

The total resistance of the plate circuit is equal to the internal resistance of the tube added to the resistance R, and if the "B" battery has 90 volts and if R is equivalent to the tube resistance at that moment the voltage drop across the tube will be 45 volts with the same drop across R. Theoretically it is possible to vary the voltage drop across R from zero to almost 90 degrees. Discounting the small resistances of the "A" and "B" batteries, a changing voltage will occur across the filament and plate when the grid potential varies, and also across the resistance R. Naturally these last variations depend upon the tube resistance and upon the value of the resistance R. These variations will be largest when R has a greater resistance than that of the tube. The resistance or impedance of the tube is constantly in a state of change and can assume very high values. For this reason the value of R should be equal to the higher values of the tube impedance in order to maintain maximum effectiveness. As used with ordinary amplifier tubes, a value of 100,000 ohms has been found to give satisfactory results. The next step is to apply the voltage variations across R to the grid circuit of the next tube. In Figure 2, the resistance R lies in the grid circuit of tube 2 as well as in the plate circuit of tube 1. Hence the magnified changes in tube 1 are transferred from R to the grid and filament of tube 2, thus the latter tube will be affected directly by the output circuit of the first tube and thus there will be amplification in both tubes thereby causing a resultant magnified signal to be heard. However, in such a hook-up, the same "A" and "B" battery cannot be used since this would mean that there would be a positive charge on the grid of tube No. 2, which would then be unable to function. Naturally, it would be impracticable to use a circuit having so many batteries, so a means must be found whereby it is possible to have a power supply consisting of but one filament battery and one plate battery for any given number of tubes in an amplifier. In order to do this the grids of the tubes must be separated electrically from the high voltage of the plates of the preceding tubes, but only as far as the steady voltage is concerned, while the fluctuating voltage of these plates must be impressed on the grids of the following tubes. This is done by introducing condensers between the two resistances. These effectively block the direct currents while they afford easy passage to alternating currents. Figure 3 shows the introduction of the condenser between the plate resistance and the grid resistance. Inspection of this diagram shows that although tube No. 1 remains the same, the plate instead of being connected directly to the grid of tube No. 2 is separated from the latter by means of the condenser C. If voltage fluctuations now occur across the resistance R, they will also be effective across the grid and filament of tube No. 2, because R exerts its influence between plate and filament of tube No. 1. As the condenser, C, conducts the variations very easily, the voltage fluctuations against R are then effective across the filament and grid of tube No. 2. It is necessary that tube No. 2 be provided with a grid leak, R_1 for the accumulated negative charges to leak off the grid to the filament. This grid leak at the same time serves the purpose of a by-pass for voltages, occurring due to possible leaks in the condenser C, which would tend to make the grid positive, thus allowing a grid current to flow and stopping the perfect action of the tube as an amplifier. Since the grid leak R_1 is a direct shunt across the grid and filament of tube No. 2, it must have a relatively high value in order to retain the highest possible amplification. R_1 should have a value lying between 500,000 and 2,000,000 ohms. If this resistance is made variable, it will be possible to control the resulting amplification completely. The value of the condenser C, must be chosen so that its resistance to the flow of alternating current will be as low as possible. Figure 4 shows three stages of resistance coupled amplification with a "C" battery used to give proper grid bias. The value of the resistance R, in the plate circuit of the tubes is 100,000 ohms and the value of the resistance in the grid circuits is 1,000,000 ohms (1 megohm). The condenser C has in each case a capacity of 0.05 mfd. The value of the "C" battery is about 4½ volts, but this should be determined by experiment for best results.



Fig. 4. Diagram showing three stages of resistance coupled amplification.

RESISTANCE COUPLING—RESISTIVE COUPLING—The transference of electrical energy from one circuit to another, by means of resistance common to both. (See *Resistance Coupled Amplifier.*)

RESISTANCE, HIGH FREQUENCY—The increased resistance of a conductor to high frequency currents, due to concentration of current at the surface of the conductor. This phenomenon is known as *skin effect* (q.v.) Skin effect becomes more pronounced, the greater the frequency of the impressed electromotive force. Skin effect also increases with increased cross-section of the conductor, with increased conductivity of the conductor and with increased magnetic *permeability* (q.v.). As a result of skin effect, the actual resistance of a conductor to alternating currents is greater than to direct currents.

RESISTANCE OF GROUND CONNECTION—The connecting wire leading from the radio apparatus to the ground should be of low resistance. If possible, the ground should be made by burying a copper plate in moist earth. The usual way to obtain a ground is to fasten a copper strap or *ground clamp* (q.v.) around a water or a steam pipe.

RESISTANCE (RADIATION)—This is the ratio of the total energy radiated (per second) by the antenna to the square of the root-mean-square current at a potential node (generally the ground connection).

RESISTANCE, RADIO FREQUENCY—The ratio of the heat produced per second, in watts, to the square of the root-mean-square current (radio frequency), in amperes, in a conductor.

RESISTIVITY—See *Resistivity of a Material*, also *Resistivity, Surface.*

RESISTIVITY OF A MATERIAL—SPECIFIC RESISTANCE—Symbol ρ (rho)—The resistance in ohms of unit length and unit cross-section of the material under consideration. Resistivity may be measured in ohms per inch cube or per centimeter cube, but more commonly it is measured in ohms per *mil-foot* (q.v.). The material of a conductor has an important bearing upon its resistance. Thus a unit length and unit cross-section of aluminum has about one and one-half times the resistance of copper having the same dimensions. Platinum has about six times the resistance.

RESISTIVITY, SURFACE—Referring to an insulating substance, surface resistivity is the resistance between two opposite edges of a surface film, 1 centimeter square. Surface resistivity depends to a considerable extent on humidity.

RESONANCE—A condition which exists in an electrical circuit where the frequency of the applied electromotive force is the same as the natural frequency of the circuit. Resonance is the cumulative effect produced by a periodic force in a circuit, so adjusted in frequency that the effect can attain the highest value. The effect measured is usually the current and the circuit when adjusted for maximum current, is said to be in resonance with the force, or with the circuit from which the force comes. The effect of resonance is to bring the current into phase with the electromotive force. Resonance in a circuit has the effect of bringing the reactance due to the inductance (inductive reactance) in exact opposition to the reactance due to capacity (capacity reactance). The total reactance is therefore zero and therefore the impedance is equal to the resistance. When two or more circuits have the same natural frequency they are said to be in resonance. Resonance of a circuit to a given exciting alternating electromotive force is that condition due to variation of the inductance or capacity in which the resultant effective current (or voltage) in that circuit is maximum. Instead of varying the inductance and the capacity, the frequency of the exciting field may be varied. The condition of resonance is determined by the frequency at which the current or voltage is maximum.

RESONANCE CURVE—A curve showing the relationship between the current induced in an oscillatory circuit and the frequency of the inducing current. In the case of two oscillating circuits placed near each other so that oscillations in one circuit will induce oscillations in the other, the induced oscillations will be weak or strong depending whether or not the second circuit is in tune with the first one. The capacity and the inductance of the second circuit can be varied until it is exactly in tune with the first at which time maximum current will flow in it. The resonance curve is obtained by measuring the current in the second circuit for various noted oscillation constants, and plotting the curve with the ordinates representing the current and the abscissae the corresponding natural frequency of the second circuit. The diagram shows a typical resonance curve. The peak of the curve is the point where the two circuits are in tune, or in other words, the point of resonance.



A typical resonance curve.

RESONANCE INTENSIFIER—An automatic receiver used for the reception of high-speed radio telegraph signals.

RESONANCE TRANSFORMER—Any loose-coupled tuning inductance having a primary and secondary each with a variable condenser in the circuit. Tuning the secondary circuit brings it in resonance with the primary, thus enabling signals to be heard with greatest volume.

RESONANT—See *Resonance.*

RESONATOR—A device for detecting by resonance, oscillations produced by an oscillator. This term is also used to refer to the sound box employed with the telegraph sounder.

RESONATOR, ACOUSTIC—A vessel containing a volume of air which can easily be set into vibration by sound waves or by the oscillation of a solid object. Typical forms are cylindrical or spherical and the ear is applied to a small tube opening into the air chamber.

RETARDATION COIL—A reactance coil used in a circuit for the purpose of selectively reacting on currents which vary at different rates.

RHEOSTAT—A variable resistance used to control current flow. Rheostats may be made of resistance wire or of carbon or for special purposes liquids may be used. In radio work, rheostats are connected in series with the filaments of vacuum tubes and the "A" battery in order to control the amount of current flowing in the filaments.

A rheostat constructed of resistance wire.

R. M. S.—Abbreviation for *Root Mean Square* (q.v.)

ROBERTS, Joseph Harrison Thomson—Born in 1890, he was educated at Liverpool and Cambridge Universities. He carried out many physical researches at the Cavendish Laboratory, Cambridge, and did a great deal of work on thermionics and other radio problems. He is a doctor of science and a Fellow of the Institute of Physics. He has several radio patents to his credit and is an expert in electrical, optical and acoustical sciences.

ROBINSON, James—British radio inventor. Born in 1884, he was educated at Durham and Gottingen Universities. He was appointed lecturer in physics at Durham University, 1906-07, lecturer in physics Sheffield University, 1910-12, and lecturer in physics at the East London College, London University, 1912-15. Robinson is known chiefly for his direction finding apparatus. He is a member of the Radio Society of Great Britain.

ROBINSON, Samuel S.—Rear-Admiral, U.S.N. He was born May 10th, 1867, and was educated at the United States Naval Academy, from which he graduated. He wrote the Manual of Wireless Telegraphy for Naval Electricians, and was in charge of the Bureau of Equipment, Navy Department.

ROOT MEAN SQUARE—The square root of the mean value of the square of an alternating current or voltage. An alternating current whose root-mean-square value is one ampere has the same heating effect as a direct current of one ampere. Root mean square is also referred to as *effective* or *virtual value.* The root mean square is derived as follows. In electrical measurements, it is necessary to compare direct and alternating currents. Moreover, the same units of measurement, the *ampere* (q.v.) and the *volt* (q.v.) are used in referring to both direct and alternating currents. However, in a direct current, a certain voltage will produce a steady current, whereas in an alternating current, both the voltage and the current are constantly varying both in magnitude and direction. The common basis of measurement is found in the value of the alternating current which will produce the same amount of heat as a certain direct current. Heating effect, according to *Joules Law* (q.v.) is directly proportional to the square of the current. Hence, in an alternating current varying according to a sine law, it is necessary to square each ordinate, find the mean or average value of these squares, and then extract the square root of this mean. Stated in concise terms, it is necessary to find the root mean square. An alternating current having a *maximum* value of one ampere would have a root mean square value of .707 amp. (See *Form Factor.*)

ROOT-MEAN-SQUARE VALUE—See *Root-Mean-Square.*

ROTARY CONDENSER—A synchronous motor used on a power line to advance the *phase* (q.v.) of the current. As a result there is an improvement in the *power factor* (q.v.). The action of the synchronous motor is similar to that of a condenser, whence the name rotary condenser.

ROTARY CONVERTER—A device for converting alternating current into direct current or vice versa. The rotary converter is also known as a *synchronous converter.* It is built like a direct current generator, except that it has certain commutator segments or conductors in the armature, connected to slip rings. Two, three, four, or six rings may be used. When the armature is rotated there is an alternating voltage between the rings. If the converter is driven by a motor or by an engine, it may be used as a *double current generator,* direct current being obtained from the brushes and alternating current from the slip rings (collector rings). When the collector rings are supplied with alternating current, the converter runs as a synchronous motor and direct current can be obtained from the brushes on the commutator. It should be understood that there is only one set of windings on the rotary converter which act simultaneously as alternating current motor and direct current generator. A converter which is used to convert direct current to alternating current is called an *inverted converter.* In the *single-phase* converter, there are two slip rings connected to the windings by as many equally spaced taps as there are poles. In the three-phase converter, three rings are used, with three equally spaced taps for each pair of poles. The single phase rotary converter must be brought up to synchronous speed by external power as it will not start itself. The polyphase converter will start itself from the alternating current side, but since it draws a very great lagging current, it should be started whenever possible from the direct current side. (See *Converter.*)

ROTARY CURRENT—A term infrequently used to denote *polyphase* (q.v.) current.

ROTARY DISCHARGER—A rotating disc discharger used in wireless transmitters in which the sparks occur between metal studs mounted on a motor driven disc. (See *Disc Discharger.*)

ROTARY FIELD—A magnetic field rotating in space. It may be due to rotating windings or stationary windings properly spaced through which polyphase currents are flowing.

ROTARY GAP—A form of rotating spark gap utilizing two or more rotating discs carrying studs between which the sparks pass. Spark gaps of this type were formerly used in wireless telegraph transmitters. (See *Discharger,* also *Disc Discharger.*)

ROTARY HYSTERESIS—Hysteresis (q.v.) produced by a rotating field as distinguished from that produced by a changing field.

ROTARY SPARK GAP—See *Rotary Discharger.*

ROTARY TICKER—A *ticker* (q.v.) in which the interruptions are produced by the chattering of a springy brush on a rapidly rotating metal wheel.

ROTOR—The rotating part of any electrical apparatus. It may refer to the revolving portion of a *motor* (q.v.) or *generator* (q.v.) or to the rotable part of a variable *condenser* (q.v.). The rotor in a direct current motor or generator is the armature. In an alternator or an alternating current motor, the rotor may be either the armature or the field.

ROTOR, GROUNDED CONNECTION—This refers to the grounding of the rotors of variable condensers in a radio receiving set. This is often done to eliminate hand capacity. Sometimes the rotors are connected to the shielding, which is grounded.

ROUGH CALIBRATION—Meters such as voltmeters, ammeters, etc., are often calibrated by comparison with standard instruments. In case such instruments are not available, it may be necessary to use less accurate methods. As an example of rough calibration, an experimental wave meter could be calibrated roughly by tuning in on various broadcasting stations whose wave lengths are known. (See *Calibration.*)

RUHMKORFF COIL—See *Induction Coil.*

RUTHERFORD, Sir Ernest—British physicist. Born at Nelson, New Zealand, he was educated at Canterbury College, Christchurch, New Zealand University, and Trinity College, Cambridge. From 1898 to 1907 he held the position of MacDonald professor of physics at Manchester University. In the latter year he was appointed Cavendish professor of physics and director of the Cavendish laboratory at Cambridge. Rutherford is an extremely brilliant physicist and has carried out a series of researches on the ultimate composition of matter. Many of these experiments have confirmed the researches of J. J. Thomson and others. Some of Sir Rutherford's experiments have revolutionized the theories of matter. He has received many honors for his brilliant researches including the Nobel prize for chemistry awarded to him in 1908. He has written extensively on radio activity, his books including "Radioactivity," 1904; "Radioactive Transformations," 1906; "Radioactive Substances and their Radiations," 1913; as well as many papers for technical journals. Sir Ernest was knighted in 1914.

S

SAFETY GAP—A spark gap which is connected in parallel with a condenser or other apparatus, and which protects the apparatus from excessive voltage. When the voltage exceeds a predetermined limit, the gap breaks down, thus passing the current around the apparatus. (See *Gap, Micrometer.*)

SAL AMMONIAC—A term commonly used for ammonium chloride. This substance is a white crystal, very soluble in water, and is used as an electrolyte in primary cells and also in many electroplating processes. (See *Cell.*)

SATURATED—The magnetic condition of a substance when increase of magnetizing force produces no further increase in flux density. A point is reached in every magnetic material, where further increase of magnetic intensity will not produce any increase of flux density. At this point, the material is said to be saturated. Cast iron becomes saturated at a lower flux density than steel or wrought iron.

SATURATION—See *Saturated.*

SATURATION, MAGNETIC—See *Saturated.*

SECONDARY CELL—A unit consisting of a positive and a negative electrode immersed in an *electrolyte* (q.v.) which becomes active only after the passage of an electric current. The electrodes are of metal or of a metallic compound. An electric current, flowing into a secondary cell causes certain chemical actions to take place whereby electrical energy is transformed into chemical energy. This process is termed "charging." After the cell is charged, the reverse action takes place and chemical energy is transformed into electrical energy. In this case, the cell is able to deliver an electric current to an outside circuit. This process is termed "discharging." The secondary cell is also known as an *accumulator* or *storage cell.* However, the cell does not store electricity. It merely holds or stores the chemical energy for immediate transformation into electrical energy. It is usual practice for several positive plates to be connected in multiple to form one positive electrode and for several negative plates to be connected in parallel to form a single negative electrode. The *storage battery* consists of two or more storage cells. The operation of the storage cell depends upon the fact that certain metals immersed in an electrolyte may differ in potential. In the secondary cell, no electrical action takes place until after charging. Thereafter, chemical action maintains a difference of potential until the stored energy has been retransformed. While the negative electrode is used up to a certain extent during the process of discharging, it is replaced electrochemically during the charging process, due to the flow of current through the electrolyte in the opposite direction to that of discharge. The two principal types of storage cells are the lead cell and the nickle-iron-alkaline (or Edison Cell). In lead cells, the negative electrode is made of spongy lead and the positive electrode is of lead peroxide. The electrolyte is dilute sulphuric acid. The following chemical action takes place within the lead cell. When the cell is charged, hydrogen is released at the negative plate, and oxygen at the positive plate. The oxygen combines with the lead of the positive plate to form lead peroxide while the hydrogen reduces the oxide in the negative plate. When the cell is discharged, both electrodes are changed to lead sulphate and the liberated hydrogen combines with the oxygen to form water. Care must be taken not to allow the cell to discharge too far as in this case, too great an amount of lead sulphate may form and this may cause buckling of the plates or may make it very difficult to recharge the cell. The indications of a completely charged cell are increased gassing of electrolyte together with a stop in the rising of the voltage and the specific gravity. In the Edison-type secondary cell, the active materials are of nickel and iron. Nickel hydrate forms the active material of the positive plate, while iron oxide forms the active material of the negative plate. The electrolyte is a 21 per cent. solution of potassium hydrate combined with a small amount of lithium hydrate. The chief advantage of the *Edison cell* (q.v.) is that it can be left idle indefinitely in a fully charged, semi-charged, or fully discharged state without any harm to the cell. In addition it is lighter and smaller than the same capacity lead cell. The unit used for measuring the capacity of storage cells is the *ampere-hour* (q.v.). This is based on the rate of discharge normally used in measurement, the eight-hour rate. As an example, an 80 ampere-hour storage battery will furnish a continuous current of 10 amperes for 8 hours. If the battery is discharged at a more rapid rate, it will not have the rated capacity.

SECONDARY CURRENT—The current flowing in the secondary windings of inductive apparatus. Current induced in a secondary winding due to the action of *primary current.* (See *Current, Primary.*)

SECONDARY ELECTRON EMISSION—See *Secondary Electrons*, also *Secondary Emission.*

SECONDARY ELECTRONS—Electrons emitted by the plate of a vacuum tube when struck by the electron stream from the filament. (See *Negative Resistance*, also *Secondary Emission.*)

SECONDARY EMISSION—Electron emission in which the exciting agency is bombardment of the emitting material by electrons. The emission of electrons from cold electrodes under the impact of other electrons. (See *Negative Resistance.*)

SELECTIVE—See *Selectivity.*

SELECTIVITY—The sharpness with which a radio receiving set can be tuned to a particular wavelength. A selective set is one which tunes sharply, whereas a non-selective set tunes broadly. Too long an aerial will often result in making a set tune broadly. A short aerial makes the receiving set more selective but reduces the volume.

SELECTOR—A tuning device connected in a radio receiving circuit for the purpose of eliminating undesired stations. (See *Wave Trap.*)

SELENIUM CELL—A cell constructed of a thin layer of the metal selenium. This metal is extremely sensitive to light. In its crystalline form, it is a conductor of electricity, its conductivity varying with the amount of light allowed to fall on it. As a result it is possible to regulate the flow of current in a circuit by varying the light. The selenium cell thus offers a means of transmitting pictures by wire or radio. Selenium cells are also being used in experimental devices for the transmission of motion pictures and for obtaining *television* (q.v.).

SELF-CAPACITY—The capacity of a circuit or a portion of a circuit. Every electrical circuit possesses inherent capacity, which varies in degree, depending upon the shape, size, etc., of the circuit. Self-capacity is also referred to as *distributed capacity* (q.v.). In general self-capacity is detrimental, especially in radio circuits, since it introduces losses. By using special forms of windings, the self-capacity of coils can be greatly reduced. (See *Low Loss Coils.*)

SELF-EXCITED GENERATOR—A generator which depends upon its own current for its field excitation. Such a generator must build up its magnetic field and hence its voltage, gradually. In order to get a start, it depends upon the *residual magnetism* (q.v.) present in the iron of the poles. There are three types of self-excited generators, the *shunt generator* (q.v.), the *series generator* (q.v.) and the *compound generator.* (See *Compound Wound.*)

SELF-HETERODYNE—A system of reception of continuous wave signals by the production of audio frequency beats, through the use of a device which is both a radio frequency generator and a detector of the audio frequency beat currents produced.

SELF-INDUCTANCES—See *Inductance, Self.*

SELF-INDUCTION—Inductance due to the field produced by the circuit itself. Changes in current are always accompanied by self-induction. When the current is decreasing, the electromotive force of self-induction is in the same direction, thus tending to prevent the decrease. When the current is increasing, the electromotive force of self-induction tends to prevent the increase. (*See Inductance, Self; Mutual Inductance*, also *Induction.*)

SELF-INDUCTION COEFFICIENT—The ratio of the number of lines of induction produced by a current flowing in the circuit divided by the current in the circuit. The coefficient of self-induction of a conductor of finite cross-section may be defined as the ratio of twice the energy of the magnetic field produced by the current flowing to the square of the current. The following factors affect the coefficient of self-induction of a circuit: the cross-section and shape of the conductor, the size and shape of the circuit, the permeabilities of the surrounding medium and of the conductor itself. Where the skin effect is large, the frequency of the current and the specific resistance of the conductor will also affect the coefficient of self-induction.

SELF-OSCILLATION—The tendency for the vacuum tubes in a radio receiving set to act as generators of radio frequency oscillations. (See *Body Capacity*, also *Bolitho Circuit.*)

SENSITIVE SPOTS—Points on the mineral of a crystal detector which show a greater response to incoming oscillations than others. Dust, grease, or dampness reduce the sensitivity of these spots and therefore the crystal should be properly protected.

SEPARATELY EXCITED GENERATOR—A generator in which current for producing the magnetic field is obtained from some source external to the generator itself. This source is either another generator or else a storage battery. Separately excited generators are generally used only for special work such as battery charging, electroplating and testing.

SERIES—See Series Connection.

SERIES CONNECTION—When two or more parts of an electrical circuit are so connected that the same current flows through them they are said to be in *series* and the circuit is called a *series circuit*, the connection being a *series connection.* In order to connect primary or other cells in series, it is necessary to connect the positive terminal of one to the negative terminal of another, etc. In this case, the total voltage of the battery equals the sum of the separate voltages.



The three dry cells are here shown connected in series.

SERIES GENERATOR—A generator in which the exciting winding is connected in series with the armature and the load. This type of generator is of small commercial importance being used mainly for certain constant current systems.

SERIES MOTOR—A commutator-type motor having the field and armature windings connected in series. Ordinarily, the series motor is a direct current motor, but with minor modifications, such as lamination of the field as well as armature, this motor can be used for alternating current also. With the applied voltage constant, the greater the load, the less will be the speed of a series motor. As the load is lessened, the motor will speed up, and if the load is entirely removed, it will "run away." The *torque* (q.v.) characteristic is the most important feature of a series motor. Instead of varying directly with the current as in the shunt motor, the torque increases with the square of the current.

Hence, if the current is doubled, the torque will be increased four times, while if the current is quadrupled, the torque will be increased sixteen times. For the same current, the torque of the series motor is higher than that of the shunt and in addition, the series motor has a much better starting torque.

SERIES-PARALLEL—This refers to a circuit which is a combination of a *series circuit* and a *parallel circuit.* The term *series-parallel* is generally used to indicate a series circuit having certain minor branches in parallel; the term *parallel-series* denotes a parallel circuit having certain minor branches in series. The illustration shows a series parallel circuit having two dry cells in parallel and three dry cells in series. The push button and the bell are also in series. (See *Parallel Connection, Series Connection,* also *"A" Battery.*)



A series-parallel circuit. The three dry cells are connected in series with each other and with the bell and the push button. They are also in series with the other two dry cells, these latter being in parallel with each other.

SERIES RESONANCE—When a single lumped capacity and a single lumped inductance are connected in series between terminals to which an alternating electromotive force is applied, and the inductance or capacity or frequency is varied, the condition of series resonance exists, when the current is a maximum. (See *Resonance,* also *Resonance Curve.*)

SHARPNESS OF RESONANCE—A quantity expressing the fractional change of current in a simple series circuit for a given fractional change in either capacitative or inductive reactance.

SHARPNESS OF TUNING—See *Selectivity.*

SHARP WAVE—A wave in which the energy radiated is confined to a single frequency of oscillation. Tight coupling of the oscillation transformer tends to give a broad wave, whereas loose coupling gives a sharp wave. (See *Decrement.*)



Graph showing difference between sharp and broad waves.

SHIELDED TRANSFORMER—An audio or a radio frequency transformer surrounded by a metal casing. Shielding of radio frequency transformers prevents interference from external fields and also keeps body capacity from affecting the tuning. Audio frequency transformers are shielded mainly to prevent interaction between the flux from the transformer and other parts of the radio set.



Typical shielded transformers.

SHIELDING—Metallic screening placed around radio apparatus to prevent interference from stray electromagnetic or electrostatic fields. In radio sets, the inside surface of the panel is often shielded by means of a metallic lining, thus eliminating body capacity. It is usual to ground the shielding. In sets having more than two stages of radio frequency amplification complete shielding is essential. (*See Induction Screen.*)

S.H.M.—Abbreviation for *Simple Harmonic Motion* (q.v.).

SHOCK EXCITATION—See *Impact Excitation.*

SHORT—See *Short Circuit.*



The dotted line between A and B represents a conductor short-circuiting the dry cell.

SHORT CIRCUIT—A short circuit refers to a condition of an electrical circuit whereby an external path of low resistance is connected across the source of electrical energy. A short circuit is accompanied by an increase in current flow, although this current is no longer usefully employed. Apparatus may be protected from short circuits by means of *circuit breakers* (q.v.) or *fuses* (q.v.).

SHORTENING CONDENSER, or ANTENNA TUNING CONDENSER—A condenser connected in series with the antenna and the ground, for the purpose of diminishing the natural wave length.

SHUNT WOUND GENERATOR—A generator in which the field winding is shunted across the armature terminals. The resistance of the shunt winding is made high enough so that only a small percentage of the load current flows through it.

SHUNT WOUND MOTOR—A motor in which the field winding is connected in parallel with the brushes (and the armature winding). The speed of a shunt motor is practically constant, but falls to a slight extent as the load is increased. The drop in speed may be only a few per cent between no load and full load, for large motors, while for small ones it may be as high as 15 per cent. As the load on a shunt motor is increased, the torque which the motor develops will increase and the armature current will also increase in almost direct proportion.



A sine curve is shown at the right. At the left a coil is shown rotating in a magnetic field. As the coil cuts the magnetic lines it generates the varying electromotive force represented by the sine curve.

S.I.C.—Abbreviation for *Specific Inductive Capacity* (q.v.).

SIDE BANDS—A group or band of frequencies formed by the interaction of the *Carrier Wave* (q.v.) and the modulations above and below the main carrier wave frequency. (See *Harmonics.*)

SIGNAL, STRAY RADIO—See *Strays.*

SILICON—A metalloid occurring widely in nature. It is a component of most of the rocks forming the earth's crust. Silicon crystals are used as detectors in radio work. (See *Crystal*, also *Silicon Detector.*)

SILICON DETECTOR—A *crystal detector* (q.v.) using silicon as its crystal. The silicon is used in a crystalline state and a *cat-whisker* (q.v.) is generally used to locate the *sensitive spots* (q.v.) and make contact.

SIMPLE HARMONIC—Referring to a *simple harmonic motion* (q.v.). If a point moves at a uniform rate around a circle and the point be projected in a straight line in the plane of the circle, the back and forth motion of the projected point is referred to as *simple harmonic motion.* True simple harmonic motions are the motions of a pendulum, a vibrating tuning fork, particles of water in a wave, etc. Other motions which are not precisely simple harmonic motions may be treated as resulting from several such motions. Examples of these are motions occurring in alternating currents in light waves, in electric waves and in sound waves.

SIMPLE HARMONIC MOTION—Abbreviation S.H.M.—The motion executed by the foot of a perpendicular let fall on the diameter of a circle from a particle moving with uniform velocity in that circle. The piston rod of a steam engine, turning a crank uniformly approximates a simple harmonic motion.

SIMPLE HARMONIC VIBRATIONS—The vibrations of a body such as a tuning fork which follow the law of *simple harmonic motion* (q.v.). (See *Angular Velocity*, also *Simple Harmonic.*)

SINE CHARACTERISTIC OF ALTERNATING CURRENT—See *Sine Curve*, also *Sine Wave.*

SINE CURVE—A curve whose perpendicular at any point is proportional to the sine of the angle corresponding to that point. The sine curve is used to represent the changes in direction and strength of an alternating current or voltage. The coil illustrated at the left in the accompanying diagram generates a sine wave current as it revolves through the magnetic field shown by the arrows. When the coil is moving parallel to the magnetic flux, no electromotive force is induced and hence current flow is zero. As the coil is rotated in a clockwise direction, it cuts the flux at a greater and greater angle, until the maximum is reached when the flux is cut at a right angle. This gives a gradually increasing electromotive force (and hence current) until maximum is reached, then when the angle at which flux is cut decreases, the electromotive force decreases until the coil again moves parallel to the flux, at which point electromotive force is again zero. Then when the coil starts to cut the flux in the opposite direction, electromotive force is reversed, increasing to a maximum and then decreasing to zero thus completing the *cycle* (q.v.). Current or electromotive force in one direction (positive) is represented by the height of the ordinates of the sine curve above the line, while current in the reverse direction is represented by the height of the ordinates below the line. The horizontal distances (abscissae) represent time generally measured in phase angles (position of coil at any particular instant). (See *Alternating Current,* also *Curve of Sines.*)

SINE WAVE—As referring to an alternating current, a sine wave or a simple alternating current, is a current whose wave shape is sinusoidal. The wave shape is the shape of the curve obtained when the instantaneous values of the current are plotted against time in rectangular co-ordinates. The wave shape is independent of the frequency and of the scale to which the curve is plotted.

SINE WAVE OF ALTERNATING CURRENT OR E.M.F.—See *Sine Wave.*

SINGING ARC—See *Duddell Singing Arc.*

SINGING SPARK—A spark used in a wireless telegraph transmitter which produces a singing note in the receiving head set. A spark which occurs at regular intervals and at an audible frequency such as that obtained in a quenched spark system of wireless telegraphy.

SINGLE CIRCUIT TUNER—A regenerative receiving circuit in which the antenna and grid circuits are conductively coupled. *Feedback* (q.v.) is obtained by placing the plate circuit in inductive relation with the primary.

SINGLE-PHASE—This term is used to refer to an alternating current, an alternating current system of distribution, or to alternating current apparatus. A single phase system or circuit is one energized by a single alternating electromotive force. A single phase circuit is usually supplied through two wires. The currents in these two wires counted outwardly from the source, differ in phase by one-half a cycle (180 degrees). In the single phase generator the voltage per phase is the same as the voltage between the lines and the current per phase is the same as the current per line. Since there is a great saving of copper in the use of three phase transmission of power, three phase generators are more frequently used than single phase machines. (See *Alternator.*)

SINOIDAL VIBRATION—See *Simple Harmonic Motion.*

SIPHON RECORDER—A moving coil galvanometer originally used for recording messages sent over long submarine cables. The received currents are passed to a coil suspended in a strong magnetic field. This coil carries a fine glass syphon which discharges ink onto a moving paper tape. In cable signaling, dots and dashes are usually indicated by opposite deflections which result in a wavy line being produced on the tape.

SKINDERVIKEN TRANSMITTER BUTTON—A small carbon grain microphone (q.v.) button less than an inch in diameter and about half an inch high containing a polished metallic button affixed to a mica diaphragm and a surrounding case of brass, the space between the case and the polished button being partially filled with a good grade of carbon granules. The button is very sensitive to sound waves when it is attached to any form of a diaphragm, thus making it applicable wherever a sensitive telephone transmitter should be used. Fig. 1 shows the external appearance, full size, of the Skinderviken button. This transmitter button has a number of applications in radio work and can be used in connection with speech amplifiers, telephone transmitters, detectaphones, etc. It can be made to transmit in any position, either horizontal or vertical. It is small enough to be readily concealed. Fig. 2 shows how radio music can be re-transmitted to distant points and incidentally amplified at the same time. The microphone button is shown fastened to a cone and mounted in front of the loud speaker. The leads from the button are connected in series with several dry cells and another loud speaker at a distant point. Fig. 3 shows how the transmitter button can be attached to an ordinary receiver to produce the same effect. In this case also, the leads are connected in series with several dry cells and with a low resistance phone at the distant end. In Fig. 4 the transmitter button is shown in use as a grid leak in a regenerative circuit. Where it is desired to get greater sensitivity and volume for either radio telephone transmitting or for ordinary phone transmission the system illustrated in Fig. 5 will be found highly suitable.



Fig. 1. Skinderviken Transmitter Button.



Fig. 2. Retransmitting radio programs.



Fig. 3. Retransmission from ear phone.



Fig. 4. Button used as grid leak.



Fig. 5. Combining buttons to form sensitive microphone.

Fig. 6 shows the construction of a hand microphone for transmitting sets or for inter-departmental telephone circuits. A very simple circuit closer is mounted in the handle of the microphone which in this particular case is simply an ordinary piece of wood hollowed out to receive the switch and the wires. This wooden handle is then fastened to the rubber case of a telephone receiver. The coils and magnets in the telephone receiver are removed, a small hole is drilled or punched in the diaphragm, and the transmitter button is fastened as indicated in the diagram.



Fig. 6. Construction of hand microphone.



Fig. 7. Method of fastening a button to ear 'phone.

Another method of fastening a transmitter button to a telephone receiver is illustrated in the diagram in Fig. 7. Here the transmitter button is mounted on a brass strip which is bent so that the center of the button will rest upon the diaphragm of the telephone receiver fixed to the base. A threaded rod and nut regulate the pressure of the button against the diaphragm. In the event that it is not desired to make any changes to a pair of telephone receivers, the transmitter button can be fastened in the shell of an old receiver, B in Fig. 8, and the head phone may be rested on the shell. For



Fig. 8. A simple form of amplifier.

use with a Baldwin receiver, a microphone transmitter button is fastened to it in the following manner: The diaphragm of the Baldwin receiver is first removed, and a thin rod is soldered to the lever, as indicated in Fig. 9. The transmitter button is then soldered to the rod as shown. Another way of making a loud speaker set from an ordinary one-tube receiving set is illustrated in Fig. 10. Where a phonograph is available, the hook-up illustrated may be employed, placing the reproducer of the phonograph on the receiver, which should be placed in a suitable position on the turntable. Inasmuch as the movement of the diaphragm of the seventy-five ohm receiver is an up and down one, the reproducer of the phonograph should be turned as it would be for "hill and dale" records. A tiny drop of solder should be dropped upon the diaphragm of the seventy-five ohm receiver and a small nick placed in the center of the solder for receiving the needle of the phonograph reproducer.


BALDWIN DIAPHRAGM REMOVED. THIN ROD R SOLDERED TO PHONE LEVER L AND TO BUTTON
L
R
FLEXIBLE WIRE
3 VOLT
BINDING POSTS
75

Fig. 9. Button attached to Baldwin 'phone.


1500 OHM
4 VOLTS
PHONOGRAPH REPRODUCER AND HORN
OUTPUT
75 OHM

Fig. 10. Loud speaker operation from 1-tube set.


MICROPHONE TRANSFORMERS
HIGH RES PHONES AND BUTTONS
6 VOLT BATTERY
LOUD TALKER

Fig. 11. An effective radio amplifier.

Very often it is desired to further amplify the music or sounds picked up by a transmitter button. For this purpose, microphone transformers, or as they are better known, modulation or telephone induction transformers, are employed. In Fig. 11 this instrument is illustrated, together with the circuit for its use. Here the incoming radio signals are made to operate the microphone fastened to the receiver. The current which the microphone passes then goes through the primary of the microphone transformer, the secondary of which is connected to another receiver similarly fitted with another transmitter button. The output of the second microphone transformer is then connected to a loud speaker. A diagram for using but one stage of amplification through transformers is illustrated in Fig. 12. For the better class of work, however, it is desirable to use a standard vacuum tube amplifier as illustrated in Fig. 13. Here the microphone button is placed in series with the primary of a modulation transformer, and in series with several dry cells or flash light batteries. The secondary of the modulation transformer then connects to the grid and filament, the same as it would in a standard vacuum tube amplifying circuit. The music from the output is, of course, very loud.


BUTTON
MICROPHONE TRANSFORMER
HIGH RES PHONE
6 VOLT BATTERY

Fig. 12. A single stage amplifier.


A
H
B
C
D
P
S
P
S
E
F
G
K
-TWO STAGE AMPLIFICATION~

Fig. 13. A 2-stage vacuum tube amplifier.


TO AMPLIFIER

Fig. 14. A tuning fork oscillator.

A very splendid oscillator is illustrated in Fig. 14. Here a tuning fork of standard frequency is mounted on a suitable holder in a cigar box. Two low resistance coils, about five to seventy-five ohms, are then placed under one prong of the tuning fork. These are connected in series with the transmitter button fastened in the cigar box, which serves as a base for mounting the tuning fork. The batteries may be concealed in the cigar box. Thus when the tuning fork is struck, it will continue to vibrate as long as the current is applied to the microphone. To use this as an oscillator, a pair of magnets from a telephone receiver and the permanent magnets are mounted near the other vibrating prong. The current constantly being changed by means of the vibrating bar of steel produces a standard frequency, which when amplified can be used for making radio measurements of different kinds. Fig. 15 shows the transmitter button connected in a radio circuit for use as a detector of radio waves. Fig. 16 shows a method of making a code practice device. An audio frequency howl is produced which will enable an instructor to teach an entire classroom the radio code. Sometimes the key, instead of interrupting the circuit, merely shunts a small portion of the current passing through the transmitter button, and for this purpose the key would have to be placed directly across the transmitter button and in series with a small resistance. Fig. 17 shows how the transmitter button may be used in Heising modulation. Fig. 18 indicates its adaptation to the variation of grid voltage of the oscillator tube and Fig. 19 shows how the transmitter button may be hooked up to modulate the output current. These last three figures indicate the use of transmitter buttons in vacuum tube transmitters.


TO AERIAL
TUNING COIL
PHONES
BUTTON
TO GROUND
~DETECTOR~

Fig. 15. Transmitter button used as radio detector.


FIBER RING
5 OHM RECEIVER
DRY CELL
DRY CELL
DRY CELL
½" HOLES
IRON DIAPHRAGM
AIR SPACE
KEY
CAP WITH ENLARGED HOLE

Fig. 16. A code practice machine.


TO OSCILLATOR
+"B"-
-"A"+
+"C"-

Fig. 17. Use of button in Heising modulation system.



Fig. 18. Method of varying grid voltage of oscillator tube.



Fig. 19. Method of modulating output current.

SKIN EFFECT — The name given to the crowding of alternating or oscillatory currents into the surface layers of a solid conductor. This phenomenon increases with increased frequency. As a result the resistance of solid conductors is much higher at high than at low frequencies. (See *High Frequency*, also *High Frequency Resistance.*)

SLABY-ARCO-SYSTEM — A system of wireless telegraphy which used a quenched spark gap. This system is now obsolete.

SLABY-ARCO-VACUUM COHERER — A filings coherer enclosed in a sealed glass tube from which the air has been extracted.

A Slaby-Arco vacuum coherer.

SLIP RINGS — Metallic rings, separated by insulators, from which collecting brushes pick up current generated by an alternator. Slip rings take the place of the commutator used on the direct current generator.

SLOTS—Channels cut in the armature core discs and into which the windings fit.



Details of armature slot.

SLUDGING OF TRANSFORMER OIL —The thickening of the oil used for cooling in large transformers. A muddy deposit is formed due to oxidation. The presence of metallic copper in contact with the oil is considered to hasten this action catalytically.

SOAKING-IN—An increase in a condenser charge above its initial value, which takes place gradually if the potential is kept applied. Soaking-in takes place due to a change in the *dielectric* (q.v.).

SOAKING-OUT — A gradual continuation of the discharge of a condenser after the first rapid discharge. In this case, the dielectric is returning to its original state.

SOCKET—A receptacle for holding and making electrical connections with a vacuum tube, an incandescent lamp, or a connection plug. Vacuum tube sockets are made of bakelite, hard rubber, porcelain, pyrex and other suitable *dielectrics* (q.v.). They are usually molded. One type of socket is composed of a shell of insulating material, or in some cases of metal. Four contact blades extend within the base of the socket, for making contact with the prongs of the tube. These blades may be of strong phosphor bronze. Their outer ends are attached to binding posts. It is important that the base supporting the binding posts and contacts be of good insulating material such as bakelite or hard rubber. Modern sockets are of the *spring* or *shock absorbing* type. This construction protects the tube and does away with microphonic sounds. One type of spring socket consists of two molded bakelite parts, the outer one square with a binding post at each corner and the inner one circular with holes for the tube prongs and steel spring contacts fastened underneath the holes.

A metal shell socket.



Shock absorbing or spring-type socket.

The circular molding is suspended within the square one by means of two rubber pads. Other types of shock absorbing sockets use spring suspension instead of rubber.

SOFT IRON INSTRUMENTS — Ammeters, voltmeters and other measuring instruments which depend upon the magnetic force between a current carrying coil and a movable core of soft iron to produce the deflection of the needle or pointer. The movement of the iron may be controlled by a spring or by gravity. These instruments may be used for either direct or alternating current measurements. They are not as accurate as instruments of the dynamometer type.

SOFT TUBE — A vacuum tube which contains a gas content instead of being highly evacuated. Soft tubes were formerly recommended for use as detector tubes but at present have been superseded for this use by the ordinary amplifying tube.

SOLDER—An alloy of lead and tin used for making good electrical connections.

SOLDERED JOINT — A connection between two metallic surfaces, cemented together by means of solder. Where the joint is between two electrical conductors, it must be made both mechanically and electrically secure.

SOLDERING — The process of joining together two or more conductors or other metallic surfaces by means of solder, so as to give a good electrical or mechanical connection, or both. After the surfaces to be united are carefully cleaned, a flux is applied to dissolve the oxides which occur on the surface of the parts to be joined with solder.

SOLDERING FLUX—A substance used to dissolve the oxides on the surfaces of the metals to be soldered. When these oxides are dissolved, the flux enables the solder to enter the minute pores of the metal surface, effectually sealing it against the penetration of oxygen. Fluxes range in character from very strong acids to very mild acid bearing substances. For radio use, it is necessary to use a flux which is non-corrosive and which in its use will leave a residual matter that will have no tendency to collect moisture, dust, or other foreign material. Rosin has been found to be very suitable as a flux in radio soldering. (See *Flux, Soldering.*)

SOLENOID — A coil of wire of helical form used as an electromagnet, generally to attract a movable iron plunger, which is drawn within the solenoid when the current flows through the windings. The solenoid never has a fixed core. A coil wound on a cylinder so as to give uniform magnetic field within it when traversed by a current is often called a *straight solenoid.*



A typical solenoid.

SOLODYNE—A radio circuit which dispenses with high-tension or "B" batteries and which utilizes a double grid vacuum tube. The solodyne principle is also known as the *Unidyne.* The theory of the solodyne is as follows: The small plate current due to the electron emission from the lighted filament passes through the tickler coil which feeds back to the main grid circuit in the usual way, the primary of a step-up transformer, through the telephone receivers, and then back again to the filament of the tube. The electron stream passing from the filament to the plate inside the tube must pass the two grids. The first of these, which may be referred to as the additional grid, is primarily made positive by connecting it directly to the positive terminal of the "A" battery. This in itself tends to assist the electron stream, to reduce the resistance of the vacuum of the tube. But the additional grid is assisted in its work by having impressed upon it the stepped up voltage from the plate circuit, due to the transformer, the secondary of which is in direct connection with the additional grid. Thus a building up process is introduced, every possible electron primarily due to the electron emission of the filament of the tube being made use of and ultimately passing through the telephone receivers to be reproduced in the form of audible signals. The main grid functions in the usual manner, except that this too, can be made to help the additional grid as well, by giving it a strong positive bias. A typical Solodyne circuit is shown in Figure 1. In this circuit L and L^1 may be honeycomb coils or a variocoupler. In Figure 2 is shown the Cowper Solodyne circuit which utilizes standard tubes. In this diagram, the numbers printed near each coil indicate the size of honeycomb or duo-lateral coils to use in each circuit. (See *Four Element Tube.*)



A Solodyne circuit. L and L^1 may be honeycomb coils or a vario-coupler.

SOUTH MAGNETIC POLE—Situated in Latitude 70 South and Longitude 102 East. The South Magnetic Pole does not coincide with the geographic South Pole.

SOUTH POLE—When referring to a magnet, the pole which tends to point to the south when the magnet is freely suspended.



The Cowper circuit uses no "B" battery and is quite stable in operation.

SOUNDER—An instrument used for receiving telegraph signals which utilizes the attraction of an armature by an electromagnet to make sounds as the armature hits against stops at the beginning and end of each current impulse. The sounds thus produced form the characteristic dots and dashes of the telegraph code and can be easily read by the experienced telegraph operator.



Telegraph sounder.

SOUND WAVE—A wave of alternate condensation and rarefication through an elastic body such as air, water, etc. Sound waves travel at the rate of 1090 feet per second in air.

SOUTH SEEKING POLE—See *South Pole.*

SPACE CHARGE—The difference between the number of electrons and positive ions in unit volume, multiplied by the charge per ion. This is also called the volume density of electrification. Let us consider the distribution of electrons in a vacuum tube, between the hot filament and the plate. An electron close to the surface of the plate is attracted to the plate by two forces, attraction from the plate and repulsion from the electrons located between it and the filament. An electron close to the surface of the filament, however, is repelled by the electrons between the plate and itself, although it receives some attraction from the plate. It may either move towards the plate or go back to the filament. This will depend upon whether the plate voltage is high enough to result in a force of attraction sufficiently great to overcome the repulsive force of the space charge.

SPACE CURRENT—Current which flows between the cathode and the anode in a vacuum tube. Space current is the result of the motion of electrons through space. It does not follow the same laws which govern the flow of current in a metallic circuit, deviating from Ohm's law to a certain extent, depending upon the relation between the impedances of the tube and the metallic portion of the circuit and also upon the nature of the discharge.

SPAGHETTI—A varnish-impregnated cloth tubing used to insulate bare conductors. (See *Cambric, Varnished.*)

SPARK—See *Spark Discharge.*

SPARK COIL—An *induction coil* (q.v.) used to produce *spark discharges* (q.v.).

SPARK DISCHARGE—A passage of electrical current between two conductors across a previously non-conducting space. The discharge is accompanied by light, heat and sound. It may take place through a liquid, a solid or a gas but whenever it occurs, it means that there has been a breaking down of the dielectric stress. A spark passing through a solid will puncture it. The passage of a spark through a liquid does not affect the dielectric properties of the liquid. On the other hand, a spark passing through a gas, usually ionizes the gas for a period of time after the passage of the discharge and as a result a continuous arc may follow the first spark. An *oscillating current* (q.v.) may produce a rapid train of sparks which persists until the oscillations are damped out. (See *Sparking.*)

SPARK DISCHARGER—A form of *spark gap* (q.v.) such as a *rotary discharger* (q.v.) or a fixed gap, such as a *quenched spark gap* (q.v.). (See *Discharger*, also *Disc Discharger.*)

SPARK GAP—A break in an oscillating circuit which acts as an automatic safety valve to the condenser. Since the air between the gap has a high resistance, the condenser cannot discharge until the potential is sufficient to break down its insulation, thus permitting only heavy discharges to take place. (See *Quenched Spark Gap, Fixed Discharger*, also *Safety Gap.*)



A rotary spark gap.

SPARKING—The production of spark discharges, especially when an inductive circuit is broken. Sparking at the brushes of a motor or generator is caused by armature reaction and self-induction. Sparkless commutation can be obtained by shifting brushes or by the use of *interpoles* (q.v.). Sparking is injurious to contact surfaces and should be avoided if possible. Sparking between contacts of induction coil vibrators is usually reduced by placing a condenser across the gap.

SPARK MICROMETER—A graduated adjustable spark gap for determining sparking distances for various voltages, etc. This device also permits the approximate measurement of high voltages provided the sparking distances for the particular type of terminals, are known.

SPARK RATE, SPARK FREQUENCY, or GROUP FREQUENCY—The number of sparks per second occurring in a spark system of wireless telegraph transmission. It refers to the *Group Frequency* of the wave train rather than to the waves themselves.

SPARK RECORDER—An instrument for recording telegraph signals, in which sparks from an induction coil pass through and mark a paper tape carried on a drum which turns under a metallic pointer. The use of a spark recorder dispenses with the use of ink, thus doing away with the friction of the pen on the paper.

SPARK TRANSMISSION—A wireless telegraph transmitting system which uses a succession of spark discharges in an oscillating circuit, to produce oscillations. These traverse an aerial system and a series of short trains of damped waves are emitted.

SPECIFIC GRAVITY—abbreviation S.G.—The weight of a body compared with that of another, having equal bulk, considered as a standard. The standard for liquids and solids is water, while hydrogen or air is the standard for gases. The specific gravity test of the radio storage battery is an important means of testing the condition of the battery. A *hydrometer* (q.v.) is used for this purpose.

SPECIFIC INDUCTIVE CAPACITY—symbol k—abbreviation S. I. C.—A measure of the degree to which a body permits electrostatic induction through it. The ratio between the capacities of two condensers, one employing the material under consideration as the dielectric and the other using an air or vacuum dielectric. The Specific Inductive Capacity of a material is the *inductivity* (q.v.) of that material relative to that of air. (See *Inductive Capacity* also *Dielectric Coefficient or Constant.*)

SPECIFIC RESISTANCE—The resistance in ohms, of unit length and unit cross-section of a conductor. (See *Resistivity of a Material*, also *Resistivity, Surface.*)

SPECTRUM—An image formed by rays of light or other radiant energy in which the parts are arranged according to their refrangibility or wave length. The image may be visible or invisible. The arrangement is such that all parts of the same wave length fall together, while those of different wave lengths are separated from each other forming a regular series. The spectrum produced by the light of the sun passing through a triangular glass prism and falling on a screen is one of the most common forms. The various colors, since they are unequally refracted, are spread out into a band, showing the seven rainbow colors. The red is at one end (that of the least deviation), while the violet is at the other end.

SPEECH AMPLIFIER—An audio frequency amplifier designed especially for public address systems, where addresses are to be heard over a comparatively wide area. By means of speech amplifiers, it is possible for one speaker to address an unlimited number of listeners.

SPEECH MODULATION—The modulation of radio frequency currents, as utilized in radio telephony. The production of speech modulated waves calls for a source of undamped waves and a method of causing variations in the current output of this source which will accurately correspond to the vibrations of the voice. The source of undamped waves may be a high-frequency alternator or an electron tube generator, the latter being in most common use. The radio frequency antenna current may be varied by inserting a speech-controlled variable resistance, such as a microphone, in the antenna circuit at the transmitter. The microphone may be put in the direct current power supply of the generating system, so that the radio frequency output of the system will be varied as the power input is varied. (See *Modulation*, also *Modulation Frequency Ratio.*)

SPEECH VIBRATIONS—The wave corresponding to a given sound. There are various methods of obtaining graphically, the picture of the wave form of any particular sound. One method is to make a phonograph record of the sound and then as the sound is reproduced from the record, to magnify the movement of the needle, using a lever to trace the form of the waves.

SPIDER WEB COIL—A form of inductance coil in which the wires are wound on a frame consisting of radiating arms similar to the spokes of a wheel. The wire is wound in successive turns in and out around the arms, starting from the center, until it reaches the ends of the arms. An odd number of turns are used so that alternate turns will follow the same wave; that is to say, adjacent turns will be on opposite sides and separated by an arm. Coils of this type have comparatively low distributed capacity and in addition have the advantage of being extremely compact. Figure 1 illustrates the frame on which the wire is wound. This is known as the *spider.* A spider cut from ⅛th inch bakelite, as shown in Figure 2, can also be used, although, owing to a smaller number of divisions, the latter does not have such a large inductance as the former. In winding, the wire is fastened around one of the pegs and is then taken in and out around the pegs, as shown in Figure 3. When starting the second turn, the wire will be around the pegs the opposite way to the first turn, and all successive odd-number turns will be on the same side as No. 1, while all successive even number turns will be on the same side as No. 2. The finished coil is shown in Figure 4. Spider web coils are also known as *basket wound* (q.v.), *basket woven*, or *stagger wound* coils.



Details of spider web coil construction.

SPLICE—A method of joining two or more conductors by interweaving or entwining the strands, in a similar manner to that of splicing a rope.



A strong splice.

SPREADER—A spar or pole used on an aerial, where two or more wires are used, to keep these wires properly spread out and parallel to each other.



Aerial showing use of spreader.

SQUARE MIL—A square mil is the area of a square, one mil, or 0.001 inch on each side. (See *Circular, Mil.*)

SQUIER, MAJOR-GENERAL SIR GEORGE OWEN—American radio authority. He was educated at the Johns Hopkins University and became a research student under Professor Rowland and Sir William Preece at the British General Post Office. In 1904 he published his famous paper on the absorption of electromagnetic waves by living vegetable organisms and showed how trees could be used for the reception of radio messages. In 1911 he read a paper on multiple telephony before the American Institute of Electrical Engineers. In 1912 he was awarded the Elliot Cresson Gold Medal for his researches in multiplex telephony and in 1919 the Franklin Medal of the Franklin Institute. Major-General Squier was awarded

Major-General George Owen Squier.

the K. C. M. G. for distinguished services during the World War. He is a member of the National Academy of Sciences and the International Electrotechnical Commission. He is the inventor of *Line Radio* (q.v.) which is also known as *Wired Wireless, Wire-Radio Telephony, Guided Wave Telephony,* and *Carrier Current Telephony.*

SQUIRREL CAGE INDUCTION MOTOR—A type of induction motor having a rotor consisting of copper bars connected to rings at each end so as to form a short-circuited system. There are no windings in this type of rotor nor are there any external connections through slip rings. These motors are used for constant speed work, where starting is necessary only at infrequent intervals. The squirrel cage motor draws a large starting current, but has a relatively small starting torque. It is possible, however, by properly designing the rotor so as to have enough resistance, to use small motors of this type for loads requiring frequent starting, rapid acceleration and high starting torque.

SQUIRREL CAGE ROTOR—See *Squirrel Cage Induction Motor.*

STAR GROUPING—A method of connecting up polyphase apparatus or circuits. One end of each phase is connected to a common point, usually called the neutral point. This method of connection is called a "Y" grouping, in the case of a three-phase system.

STATIC—An irregular disturbing noise, heard in the radio loud speaker or head set due to atmospheric discharges, lightning and similar phenomena. A common form of static produces an intermittent crashing sound. Other types cause grinding noises or hissing sounds. Nearby lightning is usually accompanied by a sharp snap in the loud speaker. Various methods have been devised for eliminating or reducing static, although it cannot be said that any of these has been entirely successful. The combination of coil and ground aerials results in the reduction of static; also the use of *beat reception*, using continuous waves as in certain methods of wireless telegraphy. Static is also referred to under various other names, such as *strays, atmospherics, X's,* etc.



Arrangements of a static reducing device employing repeater circuits.

STATIC CHARACTERISTIC—The curves obtained by the use of a steady direct-current potential for showing the performance, efficiency, etc., of a vacuum tube. The static characteristics of the tube itself are obtained when the resistance of the external circuit is very small in comparison to the plate resistance of the tube. In cases where the external circuit contains reactance, the true characteristic could not be obtained using direct current. In this case, an alternating electromotive force is impressed on the grid and the curves obtained are known as *dynamic characteristics* (q.v.).

STATIC ELECTRICITY—Electricity which is stored in a circuit, manifesting itself in the form of charges at high potential. Electricity, as produced by frictional or influence machines.

STATIC ELIMINATORS—A device for eliminating or reducing the effect of *static* (q.v.). Various circuits have been proposed for accomplishing static elimination. Some of the most recent and successful of these are the McCaa anti-static circuits described in the July, 1925, issue of RADIO REVIEW, on page 63. There are two types of McCaa circuits, one applicable to radio telegraphy and the other to radio telephony. Both have for their object the reduction of signal static ratio. The wiring diagram shown is that of a standard five-tube neutrodyne receiver plus a McCaa anti-static device of the receiver type. In this diagram Ta is the repeater tube, Tb and Tc are the two radio-frequency amplifier tubes, Td is the detector tube and Te and Tf are the two audio-frequency amplifier tubes. The circuit from tube Tb on is unchanged and is the same as any standard neutrodyne receiver. The input circuit of tube Tb, however, and also the antenna circuit, have been altered to make possible the installation of the anti-static device.

For the neutroformer which usually couples the first tube of a neutrodyne to the antenna circuit, the coils Lo, Ls and Lp have been substituted. These coils may either be homemade coils or honeycomb coils. If honeycomb coils are selected each may have fifty turns. The coupling between Ls and Lp should be fixed so that the coils are about an inch apart and some arrangement should be made for changing the coupling between Lo and Ls. If homemade coils are used each coil should have approximately sixty turns of No. 22 d. c. c. wire on a three-inch diameter tube and they should be coupled the same as the honeycomb coils.

The coils Lr and Lc are also coupled and may be either 50 and 10 turn honeycomb coils, respectively, or 60 and 10 turn homemade coils wound on a three-inch diameter tube with No. 22 d. c. c. wire. The coupling between these coils is not variable. After the proper value of coupling has been found by experiment it may be made permanent.

Coils Ld and Lq are also shown coupled in the diagram. They may be 50 and 75 turn honeycomb coils, respectively, or 60 and 90 turn homemade coils wound on a three-inch diameter tube with No. 22 d. c. c. wire. The coupling between these coils is also fixed after the proper value has been determined by experiment.

The proper values for the various capacities used in this circuit are as follows: Co., .001 mfd. (43 plate); Cs, .000035 mfd. (17 plate); Cr., .00035 mfd. (17 plate); Cd, .00035 mfd. (17 plate).

In building this set it is advisable to place both the anti-static device and the receiver in the same cabinet. This cabinet must be shielded and the shield should be connected to the ground. It is also advisable to shield the anti-static device from the receiver proper. The batteries should also be shielded either by placing them inside the cabinet or in metal boxes which are connected to the ground. The wires from the batteries to the set may be effectively shielded by using BX cable, the outside covering of which should also be connected to the ground. For the phone wires special phone cords which are shielded with a flexible copper braid are desirable.

STATOR—The stationary plates of a rotary condenser. The fixed portion of a motor or a generator, which carries a winding. In induction motors, that portion of the motor which is fixed in position and which carries the winding connected to the external circuit. (See *Rotor*, also *Alternator.*)

STATOR PLATES—The plates of a condenser which remain stationary in position as differentiated from the plates which rotate. (See *Shielding*, also *Stator.*)

STOPPING CONDENSER—A condenser which opposes or prevents the flow of direct current, but which allows alternating current to flow in a circuit.

STORAGE BATTERY—See *Secondary Cell.*

STORAGE BATTERY TESTS—The testing instrument most commonly used in storage battery work is the *hydrometer* (q.v.). The purpose of the hydrometer is to determine the state of the charge of the battery, as indicated by the *relative* specific gravity of the electrolyte. The specific gravity of a fully charged battery is not a fixed value but depends entirely upon the standard specific gravity employed by its manufacturer which may be anywhere from 1.250 to 1.300. The user should always ascertain the correct specific gravity for the make of battery before attempting to test it with a hydrometer. A voltmeter may be employed as a means of testing a storage battery provided it is of the proper type and is used correctly. It must be accurate with sufficient length of scale to read tenths of a volt clearly. Voltmeters are obtainable which may be used for both the "A" and "B" batteries whether dry or storage. It is not possible to test the storage "A" battery with cheap types of so-called pocket voltmeters. It must be kept in mind that a voltmeter reading on a storage "A" battery is of value only when the battery is either charging or discharging, except when the battery is practically dead. A voltmeter reading taken when the battery is not connected to the circuit, either charging or discharging, may be misleading. If a reading is taken with the filaments lighted and the voltmeter indicates a full six volts, the battery is charged. Under the same conditions, if the voltmeter lags appreciably below six volts the battery should be charged in order to keep it in the best condition. When it falls to 5.4 volts the battery is discharged and cannot possibly operate the set with any degree of satisfaction. When the battery is connected to the charger and the voltmeter shows from 7.5 to 7.8 volts the battery is fully charged. It is possible to test roughly without instruments. If neither a hydrometer nor a voltmeter is handy it is possible to recognize the necessity for charging by the fact that the amplifying rheostats have to be moved forward of the normal working position, indicating low voltage and that the battery must be charged. When the battery is on the charging line, being charged at the ordinary rate of the commercial charger, and all of the cells of the battery are bubbling, this is an indication that the battery is charged. An interesting meter has recently been placed on the market which should prove of considerable use to owners of storage batteries. It is an ammeter of special design which is to be connected in series with the storage battery on charge. There is a third terminal on back of the instrument by means of which the same instrument can be used to measure the current consumption of the filaments. By pressing a small button in the center of the meter, the needle swings over to the right-hand portion of the scale and indicates whether the battery is fully charged, half charged or low.

STORAGE CELL—See *Secondary Cell.*

STRAIN INSULATOR — An insulator used under tension, as for example the insulators to which the guy wires of an aerial are attached. The simplest form of strain insulator consists of a cylinder or ball having an eye-bolt at each end. Where the aerial guy is fastened to a strain insulator, the purpose of the insulator is to prevent the guy from having a natural wave length nearly the same as the wave length of the antenna. A common form of strain insulator is of nearly spherical form and is so grooved as to carry the two wires firmly, without permitting them to come into contact.



A strain insulator.

STRANDED WIRE — A wire made up of a number of smaller wires, twisted or braided together. An uninsulated, large stranded wire is generally referred to as a bare cable. Stranded wires are of four general classes; (1) wire braid, (2) bunched wire, (3) rope-lay cables, (4) concentric-lay cables. Wire braid is used to afford protection to the insulation of various types of cable. In flat form, it is used as a flexible lead. Bunched wire is a type of cable also referred to as a cord. This form of cable is very flexible, since the individual wires are small. Rope-lay cables are made up of a central core of stranded wire, having one or more layers of stranded wire wound helically about it. Concentric-lay cables are formed in the same way as the rope-lay type, except that the core and layers are of individual solid wires instead of stranded. Stranded wire is very often used in radio work as aerial wire. It has the advantage of being more flexible than solid wire and it also has a lower resistance at high frequencies because of *skin effect* (q.v.). A greater cross-sectional area is available in the stranded conductor than in the solid conductor of the same weight, for carrying current. If used for radio frequency currents, however it is essential that the individual strands be enameled if the lower resistance is to be attained.



Stranded wire.

STRAY CURRENTS—Currents induced by stray magnetic fields such as eddy currents. Such currents always result in an energy loss. In electric railway systems, the currents returning through the earth, through piping, etc., rather than through the path provided are known as stray currents.

STRAY FLUX—Magnetic flux which is not usefully employed. The *leakage flux* or *leakage lines* (q.v.) which stray from the closed magnetic path provided in a transformer or other electromagnetic or magnetic apparatus. (See *Magnetic Leakage.*)

STRAYS—Atmospheric disturbances which manifest themselves as noises in the radio loud speaker or head set. (See *Static.*)



This is the rear view of the Callies Super. Note particularly the long wave transformers at the rear of the set and how they support the sub-panel.

SUB-PANEL—A secondary panel in a radio set, mounted at an angle with the main panel. The sub-panel usually carries the transformers, sockets, grid condenser and grid leak. Sub-panels are made of bakelite or composition, hard rubber, etc. (See *Panel.*)

SUPER-HETERODYNE—See *Super-Heterodyne Receiver.*

SUPER-HETERODYNE RECEIVER—A circuit used in radio reception in which the wave lengths of the incoming signals are increased to several thousand meters, by the aid of a local source of oscillations. It is a recognized fact that radio signals at "radio frequencies," that is, the original signals as they are impressed on the receiving set from the aerial, must be amplified or built up in some way to operate the detector. However, signals at low wave lengths such as in use for broadcasting, cannot be amplified very efficiently at radio frequencies. By changing the waves from the ordinary broadcast band between about 200 and 550 meters to wave lengths of from 4,500 to 10,000, it is possible to obtain more complete amplification. As a result the receiver is more sensitive and greater distance can be received. In the super-heterodyne receiver, a *difference frequency*, termed a *heterodyne note*, is created. This is done by an arrangement for generating oscillations locally. When the incoming oscillations are combined or superimposed with the local oscillations in such a manner that there is a difference in frequency, this difference will be in the form of a new set of oscillations. If the receiver is arranged in such a form that the new set of oscillations has a comparatively low frequency, the wave length will be correspondingly high. In a standard super-heterodyne receiver the action can be imagined as follows: the signal energy from a certain transmitting station is gathered on an antenna or loop aerial. These signals are tuned in by means of a condenser in the case of a loop aerial, or by a regular tuning device such as a coupler and condenser in the case of an outside antenna. The energy thus obtained is passed through to the grid member of a vacuum tube, which is known as the first detector tube. (In some cases the energy is first amplified by a radio frequency amplifier, consisting essentially of a vacuum tube and a radio frequency transformer). At this point in the circuit, between the tuning device and the first detector, the apparatus for producing the heterodyne action is located. This part of the outfit consists of a vacuum tube with coupled coils in the grid and plate circuits, with a variable condenser (the heterodyne condenser) connected across them, having a suitable value for obtaining any desired local frequency. In this way, the difference between the incoming oscillations and the locally generated oscillations may be adjusted to a prearranged value or frequency. In inductive relation to the grid and plate coils, another coil is arranged, referred to as a *pick-up* coil. The energy obtained from the first detector tube signals having a frequency equal to the difference between that of the incoming signals and the local oscillations, is sent to a *filter transformer* or *tuned filter*. The construction of this filter and the number of windings used is of the utmost importance, as it determines the frequency of the new set of oscillations and will permit the passage of no other frequency than the desired band. This is a very essential feature, as it is necessary to pass only the desired frequency in order to permit maximum transfer of energy. The energy at this predetermined frequency is then passed to the *intermediate frequency amplifier* (q.v.). After being amplified or built up by the intermediate frequency amplifier consisting of tubes and transformers, the energy is then passed to the second detector tube and rectified or changed from radio frequency. The audio frequency signals are now amplified by one or two audio frequency amplifiers consisting of amplifying tubes and transformers and the resulting signals, speech or music


OSCILLATOR
LOUD SPEAKER
FIRST DETECTOR
INTERMEDIATE FREQUENCY AMPLIFIER
SECOND DETECTOR
AUDIC FREQUENCY AMPLIFIER
TUNER

Fig. 1.—This shows the general arrangement of the units of a typical super-heterodyne receiver.


LOOP AERIAL
GRID LEAK & CONDENSER
2 MEG.
.00025 MF.
SPECIAL TRANSF.
AMPLIFIERS
2 MEG.
.00025 MF.
50,000 OHMS
R.F.T.
R.F.T.
R.F.T.
2ND DET.
A.F.T.
L1
L2
.001 MF.
OSC.
.001 MF.
.001 MF.
.0015 MF.
1ST DET.
"C" 4V.
.001 MF
22½V.
+"B" 45 TO 90 V.
POT. 400 OHMS
"A" BATT.

Fig. 2.—Wiring diagram of a standard 7-tube super-heterodyne.



The photograph above shows an eight-tube super-heterodyne set of extra fine quality. Each of the heteroformers are shielded in nickel-plated metal shields. The two variable condensers for tuning the aerial and oscillator circuits should he of the straight line frequency type. The two audio frequency transformers are extra large concert type, the first stage of audio being all that is necessary for average reception on a loud speaker.

are used to operate the loud speaker. Figure 1 shows the general arrangement of the various sections or units of a typical Super-Heterodyne receiver. To go a little more fully into the action of the receiver, let us suppose that a certain station is broadcasting on a wave length of 400 meters. Every wave length is equal to a certain frequency.

That is to say, every wave has a certain number of vibrations per second. The frequency of a wave 400 meters in length will be about 750,000 cycles or 750 kilocycles. By adjusting the wave length condenser, the aerial or loop circuit is placed in resonance with this particular wave length or frequency. This energy is passed through the oscillator pick-up coil and the local oscillations super-imposed on it.

The oscillator condenser, let us say, has been adjusted to permit the oscillator circuit to produce oscillations of a frequency such that the difference between the incoming oscillations and the local ones will be in resonance with the windings of the tuned filter. For instance let us suppose that the tuned filter is arranged for tuning to 10,000 meters, which corresponds to 30,000 cycles.

Now the oscillator circuit must be tuned either 30,000 cycles above or below the incoming wave frequency. In other words, if the incoming wave frequency is as stated—750,000 meters, the oscillator circuit will be tuned to either 780,000 or 720,000 cycles so that the difference between the two frequencies will be 30,000 cycles. No matter what the frequency of the incoming oscillations, the local oscillating circuit will be tuned in a manner to produce the definite difference of 30,000 cycles. These signals will then be passed to the intermediate frequency amplifier and built up before being passed to the second detector tube for rectification.

After this, the signals that are now of audio frequency can be further amplified or built up by the audio frequency amplifier. The two operations that are of the utmost importance in receiving with the super-heterodyne are first, the tuning of the incoming signals and second, the adjustment of the oscillator circuit to produce the difference between two frequencies according to a definite plan. Figure 2 shows the hook-up of a typical Super-Heterodyne receiver.

SUPER-REGENERATION—See *Super-Regenerative Circuit.*

SUPER-REGENERATIVE CIRCUIT—A radio receiving circuit which permits reception under conditions of operation, which in an ordinary regenerative set would result in howling. In the regenerative set, which is tightly coupled, the signal strength increases to a maximum, and thereafter a still further increase in regeneration will result in greatly increased signal strength for a minute fraction of time, followed by violent oscillations. In the super-regenerative circuit, the signals are received at the point of very high amplification by suitably controlling the set. The great advantage of the super-regenerative circuit is the enormous amplification obtainable. Another advantage is the fact that radio code signals are not amplified to the same extent as radio telephony. The super-regenerative circuit was devised by Major Armstrong. The *Flewelling Circuit* (q.v.) is a modification of the Armstrong circuit. (See *Armstrong Circuits.*)



Flivver Armstrong Super-Regenerative circuit.

SURFACE MAGNETISM—A synonym for *Free Magnetism* (q.v.).

SUSTAINED WAVES—Continuous or undamped waves. Waves in which similar current cycles follow each other continuously instead of being broken up into groups like *damped waves* (q.v.). The sustained waves may be interrupted by means of a sending key and thus used for sending radio telegraph messages or they may be modulated and thus utilized in radio telephony. Sustained waves are obtained by the use of high frequency alternators, arc condensers, or thermionic electron tubes (vacuum tubes). The use of sustained waves has made radio telephony practicable. Sustained waves permit sharper tuning, require less energy at the transmitter than in the case of undamped waves, and permit the use of "beat" reception and other sensitive methods of reception. (See *Continuous Waves.*)

S.W.G.—Abbreviation for Standard Wire Gauge. The full name of this wire gage is the *British Standard Wire Gauge*. It is also referred to as the *New British Standard*, the *Imperial Wire Gauge*, and the *English Legal Standard.* It is the legally adopted standard of Great Britain. The following table shows a comparison between the American Wire Gauge (B. & S. Gauge and the Standard Wire Gauge:

Gauge No.	*American Wire Gauge Dia. in Mils*	*Standard Wire Gauge Dia. in Mils*
10	102	128
11	91	116
12	81	104
13	72	92
14	64	80
15	57	72
16	51	64
17	45	56
18	40	48
19	36	40
20	32	36
21	28.5	32
22	25.3	28
23	22.6	24
24	20.1	22
25	17.9	20
26	15.9	18
27	14.2	16.4
28	12.6	14.8
29	11.3	13.6
30	10.0	12.4
31	8.9	11.6
32	8.0	10.8
33	7.1	10
34	6.3	9.2
35	5.6	8.4
36	5.0	7.6
37	4.5	6.8
38	4.0	6.0
39	3.5	5.2
40	3.1	4.8

SWITCH—A device for conveniently making or breaking an electrical circuit. Switches must be designed to carry their rated current without overheating or undue voltage drop, to handle overloads, to prevent arcs on being opened and to properly insulate live parts when switch is open. The most common form of switch is the *knife switch* (q.v.). A switch which opens or closes but one circuit, that is operating in only a single position, is called a *single throw switch.* One operating when thrown in either of two positions is called a *double throw switch* (q.v.). A switch which controls only one side of a circuit is a *single pole switch;* both sides of a circuit, a *double pole switch.* The abbreviation for a single pole, single throw switch is S. P. S. T. The abbreviation for a double pole, double throw switch is D. P. D. T., etc. There are various types of switches ranging from *oil switches* used to handle enormous currents to the small push button or snap switches for turning on or off electric lights. Among the switches used in radio work may be mentioned the *ground switch* (q.v.), *aerial switch* (q.v.), *quick break switch* (q.v.) and *anti-capacity switch.* This latter usually consists of a small handle with a cam attached to its other end which serves to press together or release spring contacts. The electrostatic capacity between the springs is low, due to the construction used. The *plug* (q.v.) and *jack* (q.v.) constitute a form of switch extensively used in radio equipment. The *push-pull switch,* operating as its name implies, is often used to control the filament lighting circuits of radio receiving sets.



Various types of switches.

SWITCHBOARD—In its broadest sense, this term is applied to any collection of control, operating and measuring apparatus mounted on a panel or panels for the purpose of starting, stopping or otherwise controlling an electrical installation. In a small electrical plant, all control and switch gear may be mounted on a single structure, which is referred to as the switchboard. Switchboards are used at the radio broadcasting station to carry the various meters, control rheostats, switches, etc. (See *Panel.*)

SWITCHGEAR—Apparatus used in connection with the control of an electrical installation, such as switches, rheostats, starters, circuit breakers, etc.

SYMBOLS—Conventional signs used in radio hook-ups to represent various electrical and radio apparatus. The use of symbols has been standardized and results in clearer and more easily drawn diagrams. A table of symbols is given below:

Table of Radio Symbols

	ANTENNA				VOLT-METER				SWITCH FILAMENT	
	LOOP ANTENNA				CRYSTAL DETECTOR				SWITCH S.P. S.T.	
	"A" BATTERY DRY CELL				GRID LEAK FIXED				SWITCH S.P. D.T.	
	"A" BATTERY STORAGE				GRID LEAK VARIABLE				SWITCH D.P. S.T.	
	"B" BATTERY				JACK SINGLE CIRCUIT				TRANS-FORMER AUDIO FREQ.	
	BUZZER				JACK DOUBLE CIRCUIT				TRANS-FORMER RADIO FREQ.	
	CHOKE COIL AUDIO FREQ.				JACK FILAMENT CONTROL				TRANS-FORMER TUNED RADIO FREQ.	
	INDUCTANCE COIL FIXED				NO CONNECTION				VACUUM TUBE	
	INDUCTANCE COIL TAPPED				POTENTIO-METER				VARIO-METER	
	CONDENSER FIXED				RECEIVERS TELEPHONE				VARIO-COUPLER	
	CONDENSER VARIABLE				RHEOSTAT				LIGHTNING ARRESTER	
	CONNECTION				RESISTANCES				GROUND	

SYNCHRONOUS—As applied to alternating currents, these are said to be synchronous when of the same *frequency* (q.v.) and exactly in *phase* (q.v.).

SYNCHRONOUS DISCHARGER—A rotary gap discharger driven by a synchronous motor from the same line supplying the transformer in a radio telegraph transmitting system or a rotary gap mounted on the shaft of the alternator supplying the 500 cycle or higher frequency current. (See *Disc Discharger.*)

SYNTONY—The relationship between two oscillating currents when one resonates to the waves produced by the oscillations of the other.

T

TABLE OF DIELECTRIC STRENGTH—A table showing the voltages at which certain thicknesses of various materials will break down or puncture. The following table has been obtained from Pender's Handbook for Electrical Engineers:

MATERIAL	DIELECTRIC STRENGTH Specimen thickness mm.	Kv. per mm. (a)
Ambroin	0.84	6.0
Asbestos paper	1.2	4.2
Asphalt (Byerlyte)	3.6	14.0
Bakelite, C-1		up to 27.5
Bakelite, wood molding mixture		17.7 to 21.6
Bakelite, asbestos molding mixture		up to 9.8
Bakelite, Continental	3.2	15.7
Bakelite, Micarta-213		up to 31.4
Bakelite, Micarta-21D		5.9
Bakelite, Micarta-21H		15.7
Bakelite-Dilecto-X	3.2	25.6
Bakelite-Dilecto-XX	3.2	25.6
Celluloid (clear)	0.25	12 to 28
Celluloid (colored)	0.25	10.2 to 18.9
Condensite (molded)	5.7	19.7
Condensite (celoron)	5.7	29.5
Conite	0.13	15.7
Copal	3.0	3.2
Empire cloth, canvas	.41	28.9
Empire cloth, linen	.15	54.0
Empire cloth, muslin	.38	48.0
Empire cloth, silk	.15	48.0
Faturan	3.	10
Fiber, vulcanized, including hard fiber all colors	0.79	8.9 to 16.7
	3.2	4.9 to 10.8
	6.4	3.9 to 8.9
	12.7	3 to 5.9
Galalith (white)		6 to 8.5
Glass (ordinary)		8 to 9
Hermit		2 to 3
Jute (impregnated)	6	1.2
Lava		3 to 10
Litholite	4.5	4.5
Marble		6.5
Mica	6	21 to 28
Micabond, plate	1.6	37.5
Micabond, flexible	1.6	23.1
Micanite, plate	1.6	37.5
Micanite, flexible	1.6	23.1
Minerallac		39.4
Paper	0.13	8.7
Paraffin (parawax)		11.5
Porcelain	20	8
Pressboard (oiled)	0.25	39.3
Pressboard (oiled)	1.58	29.2
Pressboard (oiled)	3.17	21.1
Pressboard (varnished)	0.25	26.3
Pressboard (varnished)	1.58	15.5
Pressboard (varnished)	3.17	9.5
Presspahn		5.2 to 9.3
Redmanol (molded)	5.1	11.8 to 18.5
Redmanol (laminated)	0.8	41 to 51
Rubber (hard)	0.5	70
Slate	10.3	1.3
Vulcabeston	1.9	31.5 to 7.1
Wood (maple), paraffined	15.2	4.6

(a) To obtain volts per mil, multiply kilovolts per millimeter by 25.4.

"T" ANTENNA—A flat top antenna in which the down lead is taken from the center of the horizontal portion. (See *Aerial*, also *Flat Top Aerial.*)

TAILS—Name given to small iron wires forming core of *induction coils* (q.v.).

TANGENT GALVANOMETER—A type of galvanometer in which the strength of the currents which pass through the coil is proportional to the tangent of the angle of deflection of the magnetic needle in the center of the coil. In construction, the tangent galvanometer consists essentially of a small magnetic needle suspended in the center of a large circular coil made of the few turns of insulated wire. Attached to the needle is a light aluminum pointer which allows the deflections to be read on a horizontal scale. The coil is placed in the magnetic meridian with the needle and the coil in the same plane. When the current passes through the coil, the pointer is deflected and the angle of deflection recorded. Knowing the constant of the galvanometer, it is possible to calculate the current in absolute units or in amperes by multiplying the constant by the tangent of the angle recorded.

TANGENT OF AN ANGLE—In a right angle triangle having the given angle as one of its angles, the tangent of the angle under consideration is equal to the ratio of the side opposite the angle to the base of the triangle.



The tangent of angle A is the ratio of side a to side b.

TAP-TAPPING—The connection made to an intermediate point in a winding thus permitting the number of turns in the circuit to be varied at will. Variometers, variocouplers and other coils are made with taps, also transformers, armatures of rotary converters, etc.

TAPPED—See *Tap*, also *Tapped Inductance.*

TAPPER—An electromagnetic device, similar to an electric bell, but with gong removed, arranged so that a hammer gently taps a coherer thus decohering filings after the passage of incoming oscillations. This device was formerly used as a detector of wireless telegraph signals.

TAPPING-BACK—The application of a light blow to a filings coherer to decohere the filings. (See *Tapper.*)

TELEFUNKEN SYSTEM—A wireless telegraph system employing a *quenched spark gap* (q.v.) and giving a singing spark of rather high note. This system has been developed and used by the Germans.

TELEGRAPH—Any system of transmitting intelligence from one point to another over a distance. The word was at one time applied to visual systems such as wig-wagging and semaphore, but at the present is used only to refer to electrical systems. The one exception to this rule is the use of the term to refer to signals sent either mechanically or electrically from the bridge of a ship to the engine room.

TELEGRAPHONE—A magnetic phonograph in which speech currents or signal currents are recorded as permanent magnetic impressions on a moving steel wire. Instruments such as this have been used for recording telephone conversations and also in high speed automatic wireless telegraph transmission. (See *High Speed Reception and Transmission.*)

TELEGRAPH NAUT—A nautical mile of 2,029 yards or 1.1528 statute miles. (See *Nautical Mile.*)

TELEGRAPHY, RADIO—See *Radio Telegraphy.*

TELEPHONE CONDENSER—In radio work, this is a fixed condenser shunted across the head set or loud speaker. Used in this connection, the condenser is also referred to as a by-pass condenser since it offers a path of low resistance to the radio frequency currents. By-pass condensers are usually made of tin foil with a mica or paper dielectric. Condensers used for ordinary telephone work are also referred to as telephone condensers.

TELEPHONE RECEIVER—An electromagnetic instrument by means of which variations of current are caused to reproduce sound waves corresponding to words spoken into a transmitter at a distant point. The essential features of the telephone receiver are an electromagnet, a permanent magnet and a diaphragm held in a suitable case. The diaphragm is supported by the rim of the case, at a short distance from the face of the magnet and it is attracted by the magnet when it is energized by the current flowing in the windings. The steady magnetic flux of the permanent magnet draws the diaphragm to the pole pieces, leaving a small gap between, so that the diaphragm is held under tension. The currents passing through the electromagnet are modulated in accordance with the transmitted speech. These change the tension of the diaphragm due to the change in magnetic pull and as a result the diaphragm vibrates giving forth speech or music. The telephone receivers used in radio work are of the *watch case* type. (See *Head Telephone or Head-Phone.*)



A cross sectional view of a telephone transmitter showing details of construction.

TELEPHONE TRANSMITTER—A sound-wave operated or vibration-operated device designed to produce electromagnetic waves or vibrations which correspond to the sound waves or vibrations actuating it. The standard transmitter used in ordinary telephone work is known as the "solid-back" transmitter. A gong-shaped back supports the transmitter and carries all the parts. A mouth piece of hard rubber is screwed into the front. Just to the rear of the front is placed an aluminum diaphragm which fits into a receptacle cut out for it. An insulated cushion seat of rubber is placed above and below the diaphragm. The diaphragm is held securely by damping springs having soft rubber cushions at their tips, so that it can only assume forced vibrations. An auxiliary diaphragm of mica is used which is fastened to the front electrode of the transmitter button. Both the front and the rear electrodes are made of carbon discs, between which carbon granules are placed in a cylindrical chamber lined with varnished paper. A rigidly connected pin communicates the vibrations of the diaphragm to the front electrode. The movement of the electrode varies the pressure on the carbon granules, thus giving the required variation of resistance which in turn varies the current. The *microphone* (q.v.) used in radio broadcasting is a modification of the telephone transmitter.

TELEPHONE, TUNED—See *Tuned Telephone.*

TELEPHONY, RADIO—See *Radio Telephony.*

TELEVISION—Electric vision at a distance. The transmission by wire or by radio of vision—that is to say the ability to see objects at any distance by changing the light waves to electric currents or to electromagnetic waves, transmitting these to the distant receiving point, and then retransforming them back to the original light waves. Television is still in the experimental stage. Of course, the sending of pictures by radio has been accomplished by Capt. Ranger, in this country, Belin in France, Karolus in Germany, Baird in England, and several others. Both Belin and Baird have been working on the problem of television and are reported to be nearing success. In this country, Mr. C. Francis Jenkins, of Washington, D. C., has constructed a non-commercial (that is in its present stage) machine which will send motion pictures by radio. This is practically the last word in the present development of television. It is possible to broadcast a film picture with this device at the rate of sixteen pictures per second showing the moving outlines as silhouettes, but without the intermediate tones. The method by which a photograph is transmitted by radio in the Jenkins system may be illustrated by the example of a coin covered by a thin sheet of paper on which serried pencil lines are drawn. The design of the coin appears in lines varying in intensity. The variations in the lines may be transformed into pulsing electric current by means of a light sensitive cell passing over the lines in question. Place the lines end to end and the current can modulate a carrier wave. The forming of the continuous line presented a difficulty which was solved in the following way. The inventor proceeded along the line that a prism bends a ray of light and that an image will appear upon a photographic lens placed before a picture. From this it follows that a prism placed near a lens will cause the image to be displaced sideways, the extent of the displacement being dependent on the angle of the prism. If the prism could change its angle, the result would be motion on the part of the image. The prism used is circular, with rapid change of form across the prismatic section. Around the circumference of the disc, the prism changes in thickness according to a graduated scale. Revolving the disc causes the image to move in a straight line. When the end of the prism passes the lens, there is instantaneous snapping back of the picture and the journey is repeated. If a small hole be made in the screen, the light from a given point on the picture will pass through and can be made to operate a light sensitive cell at the back of the screen. When the image is made to move down over the screen by the prismatic ring, the aperture will admit light of varying intensity, according to the light value along a line crossing the picture. This means that the light falling on the photo cell as the image travels will represent a line across the picture from top to bottom. This leads to the creation of the successive lines that make up the picture as a whole. The image is moved along from side to side by means of a second prismatic ring working along at right angles to the first, but at much lower speed. This second prism makes but one revolution during the time that the first makes one hundred, producing the hundred lines assumed to be necessary for making the picture. The cell used may be selenium or thalium oxide. The former requires twenty minutes to cover the picture, the latter six. It is obvious that to reproduce the picture at the other end the process must be reversed, the lines being replaced side by side by means of a pair of prismatic discs similar to those at the transmitting end. As noted above, the main difference between sending photographs and motion pictures is in the necessary speeding up. For this purpose, Mr. Jenkins uses a potassium light-sensitive bulb, the action of which is much more rapid than that of either selenium or thalium oxide. The cell is composed of a bulb with its inner surface coated with metallic potassium. The bulb has a high vacuum. The device has two electrodes, one being a wire through the stem, ending in a loop in the center of the bulb; the other passing through the side of the bulb and connecting with the potassium deposit. Absence of the potassium from a small part of the surface forms a "window" opposite the last named contact. Application of a positive potential to the central electrode, attended by connection with the potassium coating, permits no current to flow as long as no light enters the bulb. The admission of light frees electrons from the potassium, in numbers proportionate to the strength of the light. In this way a current flows through the bulb when light enters the "window." In this cell, there is no appreciable lag due to the amazing speed of the electrons.



The cylinder is covered with plane mirrors. revolving downward on the side toward the lantern. One ray' at a time from 1/25,000 of the area of the image, passes through the opening in C. The fixed mirrors D and F send it back to the mirror G, opposite B on the cylinder, and it is finally reflected against H in a position corresponding exactly to the portion of the image from which it was first taken. The effect of continuous vision is produced.

The sending station has a motion picture projector, a small machine used to cut up the image, a light-sensitive cell, and a transmitter. The receiving station has a radio receiving set, a machine for reassembling the picture, and a screen for the reproduction of the image.

The lamp required for the receiving station must be able to pass swiftly from darkness to extreme brilliancy, and the ordinary filament lamp could not attain the tremendous speed involved. The lamp used by Mr. Jenkins is the creation of Professor McFarlane Moore, and is capable of handling complete cycles at the rate of 75,000 to the second. This lamp has a glass bulb containing two concentric cylinders, the larger almost filling the bulb, and the smaller almost filling the larger. The inner cylinder has a small axial hole, drilled almost to the bottom and forming a deep cup. The principle of this lamp is much the same as that of the Amrad "S" valve.

It is a truism that the fundamental principle of cinema pictures is that the human eye continues to see an image



This apparatus is diagrammed above: the projecting lantern at the right: the drum of mirrors, center; and the adjusting stands for diaphragm and fixed mirrors in front. At the left a continuous image appears on the screen, although only 1/25,000 of it is actually projected at any instant.

after that image itself has disappeared. In the case of an electric spark lasting one ten thousandth of a second, the image lasts for at least one-sixteenth of a second as visualized by the eye. Mr. Jenkins assumes that if 10,000 dots of light and shade flash successively on a screen with sufficient speed, the eye will see the picture to which the dots belong even though but one dot is on the screen at a time. He, therefore, aimed at flashing the 10,000 dots on the screen within the space of one-sixteenth of a second.

Theoretically, this feat might be accomplished by halving the slow disc revolving rate to 960 revolutions per minute, keeping the faster disc at a rate exactly one hundred times greater. But the glass disc would be shattered by the centrifugal force before the attainment of a speed of 96,000 revolutions per minute.

Mr. Jenkins gets over this difficulty by the use of forty-eight lenses attached to a large aluminum disc rotating in front of the prismatic disc, thus giving the effect of a slow-moving lens. Each of these forty-eight lenses makes a line across the plate, which thus becomes the screen of the motion picture apparatus. This makes it possible to reduce the speed to one forty-eighth of that which would otherwise be required, that is, to one of 2,000 revolutions per minute.

At the receiving station, the modulated wave is received by a set but slightly different from many in common use. The last amplifier tube is one of 5 watts. By the use of the McFarlane Moore light already described, the modulations in the plate circuit of the last valve are transformed into light, and the rays are distributed over the screen by prismatic and lens discs similar to those used at the sending station. In actual practice, the picture appears on a screen about 6 in. by 8 in. More powerful lamps would allow of larger pictures.

The process described is for sending photographic pictures. But it can be adapted for the sending of direct views without the intervention of photography.

All that is done in this case, is to remove the projector and focus the lens so that it will throw the view as an image.

So far as radio features of the transmission are concerned, there is little to be explained. At the receiving station the circuit resembles the superheterodyne. The picture is at 75 kilocycles frequency and does not interfere with broadcasting.

The carrier wave may be modulated with voice frequency, so that the voice can travel with the picture, which enables vocal explanations to be given simultaneously with the flashing of the film or actual scene being transmitted.

TEMPORARY MAGNETS—Magnets which lose their magnetic properties as soon as the magnetizing force is removed. Soft iron displays the properties of a temporary magnet and hence is ideal for use as the core of electromagnets. (See *Magnet*, *Electromagnet*, also *Permanent Magnet*.)

TERMINAL—A binding post or other fitting attached to the electrodes, ends of windings or other parts of electrical apparatus so as to permit the external circuit to be connected to the apparatus.

TESLA COIL—An oscillation transformer for producing high potential discharges from oscillations of low potential. The *Tesla Coil* or *Tesla Transformer*, as it is sometimes called, is somewhat similar to the ordinary transformer, although it is much more heavily insulated and has the ends of the secondary connected to a condenser which discharges across a spark gap, thus increasing the rapidity of the oscillations, which then pass into a secondary induction coil. This second coil has no iron core. The Tesla Coil consists essentially of a primary winding having a relatively small number of turns of heavy wire and a secondary having a large number of turns of fine wire. An air, glass, or ebonite dielectric separates the primary and the secondary. Due to the sufficient thickness of the dielectric, there is no possibility of a direct discharge between the two windings. Both the primary winding and the secondary winding consist of but one layer each. The primary winding forms part of an ordinary oscillation discharge circuit. A high frequency electromotive force is induced in the secondary winding, due to the high frequency oscillating currents which flow in the primary winding thus setting up an oscillating magnetic field. Due to the high ratio between the windings of the primary and the secondary, very high voltages are set up in the secondary, in some cases as high as a million volts, and hence a very powerful brush discharge can be obtained.



Tesla coil.

TESLA, NIKOLA—American electrical and radio expert. Tesla was born at Smiljan, in Jugo-Slavia, 1857, and was educated at Graz and Prague Universities. He entered the Austrian Telegraph Service and in 1884 he came to the United States where he became an assistant to Edison. He specialized in the study of high frequency and high potential alternating currents. Tesla is noted for his many revolutionary inventions which include polyphase alternating current systems, the rotating field alternating current motor, arc lighting, the *Tesla transformer* (q.v.), and radio apparatus of many kinds including *radio control* (q.v.) devices.

Nikola Tesla.

TESTING CIRCUIT (BUZZER)—A circuit in which a buzzer is used for the purpose of testing or of locating faults in radio apparatus. A buzzer connected in series with a dry cell can be used for locating open circuits and also for testing for short circuits. A buzzer connected in series with a battery and an inductance coil, so as to form a closed circuit and having the inductance coil placed so as to be coupled with the antenna coil of a crystal detector receiving set, can be used to determine the most sensitive point of contact of the crystal. A *tuned buzzer tester* is sometimes used in connection with radio direction finder systems.

THEORY OF CURRENT FLOW—While it is assumed for convenience, that an electric current flows along a conductor from the positive terminal of the source and back to the negative terminal, modern theory is that the electrons actually travel in the opposite direction. Whenever there is a flow of electricity in a conductor, it is believed that extremely small particles of electricity, called *electrons* (q.v.), pass along this conductor. Matter is made up of atoms, which in turn are composed of electrons. The electrons are minute particles of negative electricity revolving around a positive particle. All electric current flow is based upon the motion of electrons within a conductor.

THEORY OF DETECTOR ACTION (OF VACUUM TUBE)—The vacuum tube used as a detector performs a two-fold purpose—it rectifies the current so that it is capable of actuating a telephone receiver and in addition it amplifies or strengthens the current. The rectification takes place due to the fact that the electron flow is only possible from the filament to the plate, but not in the reverse direction. The radio frequency currents applied to the grid regulate tl. number of electrons passing from the filament to the plate, the variation being exactly in accordance with the variations of the radio frequency current. (See *Detector*, *Vacuum Tube*.)

THEORY OF OPERATION OF VACUUM TUBES—The operation of the three-electrode vacuum tube depends upon the emission of electrons from the hot filament to the plate and the control of the flow of these electrons by means of the potential variations applied to the grid. The vacuum tube consists of an evacuated bulb containing a tungsten filament treated with thorium, an anode or plate, which may be in the form of a cylinder or plate, and a grid consisting of a wire grating inserted between the filament and the plate. When the filament is heated it gives forth electrons which are attracted to the plate under the influence of a difference of potential by which the plate is maintained positive with respect to the filament. The grid is an automatic control, regulating the flow of electrons from filament to plate. Potential variations applied to the grid serve to vary the electron flow between the filament and the plate. The circuit in which the vacuum tube is used may be divided into two parts, the input circuit connecting the filament to the grid through the secondary of a transformer or other method or applying potential changes to the grid, and the output circuit between filament and plate. The vacuum tube may be used as a detector or rectifier, as an oscillator or generator of high frequency oscillations, as an amplifier, as an electrostatic voltmeter, as a voltage and current regulator, a power limiting device, etc.

THEORY OF PROPAGATION OF ELECTROMAGNETIC WAVES—Waves are due to vibrations transmitted through a continuous elastic medium. Electromagnetic waves are due to vibrations caused by an oscillating electric charge in a circuit (the transmitting aerial circuit). The current flowing in the aerial is oscillating (surging back and forth) at an enormously high frequency and in addition to its induction field, the aerial has associated with it a *radiation field* which spreads out in all directions from the aerial. The strength of the radiation field decreases in inverse proportion to the distance from the aerial. At any given point the strength is directly proportional to the frequency. The transmission of electromagnetic waves is considered as due to the motion of the lines of force. There is a displacement of electricity along these lines against the elastic force of the medium, termed for convenience the *ether* (q.v.). Displaced electricity continuously tends to go back to its position of rest under the action of the elastic forces. There is pressure at right angles to the lines of force in addition to the tension along them. The pressures may be considered as due to the repulsion between the displaced charges of the same sign in neighboring lines of force.

THEORY OF RECEPTION OF ELECTROMAGNETIC WAVES—As electromagnetic waves cut across a receiving aerial, the electric field intensity along the aerial alternates in value. There is an alternating potential between the aerial and the ground which gives rise to the flow of an alternating current. Another explanation is based on the principle of induction. The magnetic and electric fields, in cutting the aerial, induce electromotive forces which cause current to flow. This is radio frequency current and it is passed to the grid of the detector tube and rectified as explained under *Theory of Detector Action* (*of Vacuum Tube*). (See *Electromagnetic Waves.*)

THEORY OF VACUUM TUBE OPERATION—See *Theory of Operation of Vacuum Tubes.*

THERMAL—Pertaining to heat. There are various electrical and radio devices which depend upon heating or thermal properties. The *thermal ammeter* (q.v.) is described under the heading *Hot-Wire Ammeter.* The *thermal detector* is taken up under *Barreter* and *Liquid Barreter.*



A thermal detector. By means of the change of resistance of a conductor, due to heating, electro-magnetic waves are detected. R_1 and R_2 are two rectangles of very fine iron wire.

THERMAL AMMETER—A current meter, in which the current or a fixed proportion of the current in question, passes along a fine wire. This heats the wire, causing it to expand or sag. This deflects a pointer or mirror across a calibrated scale. The thermal ammeter can be used for measuring direct or alternating currents. (See *Electrothermal Meter,* also *Hot-Wire Ammeter.*)

THERMAL DETECTOR—A radio *detector* (q.v.) which depends for its operation upon the heating of a fine wire by the passage of electrical oscillations. (See *Barreter.*)

THERMAL JUNCTION—**THERMOELECTRIC JUNCTION**—The contact *point* or joining point of the two dissimilar metals of a *thermo-electric couple* (q.v.). (See *Klemencic Thermal Junction.*)

THERMAL TELEPHONE—A telephone receiver in which the movements of the diaphragm are regulated by the variations of expansion of a wire heated by the telephone currents thus reproducing sound waves. In another type of thermal telephone, the diaphragm is dispensed with, sound waves being reproduced directly through the expansion and contraction of air in contact with the heated wire. This device is also known as a *thermal receiver* or a *hot-wire telephone.*

THERMIONIC EMISSION—The emission of a stream of negative electrons from a heated filament (cathode) in a vacuum tube.

THERMO-ELECTRIC COUPLE—**THERMO-COUPLE**—A pair of dissimilar metal pieces placed in contact and connected by electrical conductors in a closed circuit. When the junction of the two dissimilar metals is heated, an electric current will flow.



A current is caused to flow by heating the junction of two dissimilar metals. If the end at B is heated the direction of flow will be as shown by the arrows.

THERMO-ELECTRIC CURRENT—A current which is caused to flow due to an electromotive force set up at the junction of two dissimilar metals when these metals are at different temperatures. (See *Peltier Effect.*)

THERMOPILE—A device for magnifying the effect of the thermo-couple by connecting a number of these in series and exposing one set of alternate junctions to the heat, thus causing the electromotive forces to add up.



At the left is shown method of joining thermopile junctions to multiply the effect. At the right is a sensitive thermopile.

THOMSON EFFECT—The phenomenon of the appearance or disappearance of heat when a current flows from a cold towards a hot part of a conductor. If copper is unequally heated, heat is liberated at a point when the current and the heat flow in the same direction and is absorbed when they flow in opposite directions. The Thomson effect is measured by a quantity termed "the specific heat of electricity."

THORIUM—A rare metal which in certain compounds in radio-active. This metal has a specific gravity of eleven and an atomic weight of 232.5. Thorium is used for coating Welsbach mantles and is also used in connection with the coating of the tungsten filaments used in vacuum tubes. (See *Filament, Thoriated,* also *Thorium Treatment of Filaments.*)

THORIUM TREATMENT OF FILAMENTS—A compound of thorium, thoria (ThO_2) is used extensively in the manufacture of filaments for vacuum tubes. Sometimes thorium nitrate is used for this purpose. The filament so treated is termed thoriated tungsten. Since the rate of electron emission from a thoriated tungsten filament at a given temperature is several thousand times greater than in the case of the ordinary tungsten filament, it is possible to use the former at a much lower temperature. (See *Filament, Thoriated.*)

THREE CIRCUIT TUNER—A *regenerative circuit* (q.v.) in which the primary, the secondary or grid circuit, and the plate circuit are capable of being tuned in resonance with each other.

THREE-ELECTRODE THERMIONIC TUBE—An evacuated bulb or vessel containing a combination of a heated cathode, a relatively cold anode and a third electrode for controlling the current flowing between the other two electrodes. (See *Triode,* also *Vacuum Tube.*)

THREE-ELECTRODE TUBE—The three element thermionic vacuum tube having a filament or cathode, a plate or anode, and a grid. This tube can be used with minor modifications as a *rectifier* (q.v.) or *detector* (q.v.) of radio signals, an *amplifier* (q.v.), an *oscillation generator* (*oscillator* (q.v.)), an *electrostatic voltmeter* (q.v.), as a *power limiting device,* etc.

THREE WIRE SYSTEM—In direct current work, a system of transmitting electrical energy, which utilizes three wires, one of which is maintained at a potential, midway between the other two. A part of the load is connected between one wire and the neutral and part between the other wire and the neutral. As a result the neutral wire only carries current equal to the difference in the loads. The main advantages of this system are a saving in copper and availability of double voltage. Thus 110 volts may be required for lights, whereas 220 may be wanted for electric motors. In alternating current work reference is sometimes made to a two-phase three wire system. In this system there are two single phase currents which differ in phase by 90 degrees. Each current has a separate outgoing wire, but unites in a common return wire. (See *Neutral Wire.*)



THE EDISON THREE WIRE SYSTEM

TICKER or TIKKER—A form of interrupter or an equivalent apparatus, used in sustained wave telegraphy. It is really a commutator interrupter. In a commercial type illustrated, a disk is mounted on a motor shaft. The disk has a number of teeth filled in between with fibre or other insulating material. The radio frequency currents flow from one brush to the other through the disk which interrupts them at the rate of from 300 to 1000 times per second. A charge is built up in the condenser C_a by resonance with the aerial system and this discharges into the telephone condenser C_b at regular intervals. The telephone condenser then discharges through the head set, thus producing a single sound corresponding to the charge accumulated. Since the tikker discharges the condenser, C_a at different places on the cycle of the incoming oscillations, the note produced is not uniform and is hard to read through atmospheric interference. (See *Chopper*.)



A simple Poulsen ticker. This is used to interrupt circuits of a receiving tuner at a uniform rate per second.

TICKLER—TICKLER COIL—A coil placed in the plate circuit of a regenerative receiver and coupled inductively in the grid coil in order to obtain regeneration. (See *Feed-Back, Feed-Back Coil, Feed-Back Coupling, Regenerative Circuit, Regenerative Coupling*, also *Regeneration*.)

TIME CONSTANT—The ratio, in an electric circuit, of the inductance in henries to the resistance in ohms. It is the time, in seconds, required for a current to attain 63.2 per cent of its ultimate value as given by Ohm's Law. (See *Impulse E.M.F.*)

TONE WHEEL—An apparatus used in the reception of wireless telegraph signals in continuous wave systems, utilizing a wheel in which the conducting teeth are separated by insulating material. A brush is used to make contact with the wheel. The tone wheel is similar in principle to the *tikker* (q.v.) except that it converts the incoming oscillations to audio frequency currents, thus doing away with the non-uniform note of the tikker. In addition to this the tone wheel utilizes more of the incoming energy than does the tikker. The tone wheel is run at such a speed that the frequency of the interruptions differs slightly from that of the incoming oscillations thus giving *beats* (q.v.) which produce audio frequency currents which can be heard in the telephone receiver. Since the tone wheel mechanically converts radio frequency currents into audio frequency currents it is sometimes called a *frequency transformer*.

TORQUE—The moment of a system of forces tending to produce rotation. It is usually measured in foot-pounds. Torque may also be defined as that which produces or tends to produce torsion. Thus if a force acts at a tangent to the periphery of a circle, thus producing a turning moment about the center of the circle, the product of the force and the radius of the circle is called the torque.

TRAIN RADIOPHONE—Communication by means of radio between moving trains and ordinary land-line telephone systems. Such a system is in operation commercially in Germany on trains operating between Berlin and Hamburg. The voice frequency currents from the telephone are impressed on a carrier wave by a method similar to the *Heising Modulation* (q.v.) system. Each train has a special wave length assigned to it. The modulated wave is emitted through a four-wire antenna, strung along the roofs of two coaches. The nearby telegraph wires pick it up and carry it to the receiving sets, located in stations along the line. The ground for the system is obtained through contact of the car wheels with the rails. In reverse order, the voice frequencies of messages from the telephone at the other end are used to modulate a carrier wave (using a different frequency) at the nearest train-telephone switchboard. They are then transmitted over the wires and inductively to the train. An arrangement is provided to prevent interference between the sending and the receiving sets.

TRANSFORMER—A type of induction apparatus, usually stationary, having primary and secondary windings, ordinarily insulated from each other. These are wound about an iron core. The function of the transformer is to change the electrical energy either increasing or decreasing the voltage, current, frequency or phase. Transformers can only be used in connection with alternating currents. Transformers for changing voltage have a different number of turns in the primary than in the secondary. In the step-up transformer, the primary usually consists of a small number of turns of comparatively heavy wire, while the secondary consists of a larger number of turns of fine wire. The ratio of the primary and secondary windings determines the ratio between the input and the output voltages; thus a 10 to 1 step-up transformer could be used to step a primary voltage of ten to a secondary voltage of 100. There are various methods of classifying transformers, namely, according to their operating characteristics, according to their method of cooling, or to their construction. Transformers which are meant to give a constant voltage on the secondary side are known as *constant potential transformers*. Those meant to give constant current are called *constant current transformers*. Transformers may be air cooled, water cooled or oil cooled. In some cases a natural air draft is used as in transformers of the smaller types. Larger transformers may be designed with special ducts through which blowers force a current of air. Oil cooled transformers may have the cores and windings immersed in oil, or the oil may be circulated through external coils. Water cooled transformers are immersed in oil, but have pipes carrying running water submerged in the oil. According to construction, transformers are of the core type and the shell type. The core type transformer is used more for high voltage, low capacity work, while the shell type is used for low voltages and high capacities. Transformers find a wide application in radio apparatus. *Audio transformers* are used to couple audio frequency circuits as for example in the case of an audio frequency amplifier. Audio transformers have an iron core and may be *shielded* or *unshielded*. *Radio frequency* transformers are used to couple radio frequency circuits. They are usually of air core type, although in special instances iron cores are used. Transformers are also used in alternating current chargers, in "A" and "B" battery eliminators and in power sets which operate directly from alternating current houselight-ing circuits. (See *Charger, Storage Battery, Audio Amplifier, Coupling Transformer, Jigger, Intermediate Transformer, Inductive Coupler, Oscillation Transformer, Air Core Transformer, Core Transfomer, Ratio of Transformation*, also *Shielded Transformer*.)



Two standard types of transformers.

TRANSFORMER COUPLING—A method of transferring the electrical energy of an alternating current from one circuit to another inductively by means of a transformer, one of whose windings is connected in one circuit, the other winding being connected in the second circuit. Radio frequency circuits are usually coupled by *radio frequency transformers, audio frequency transformers* being used to couple audio circuits. (See *Coupling*, also *Amplifier, Intermediate Frequency*.)

TRANSFORMER STEEL—A special steel usually containing a high silicon content used for stamping out transformer laminations. (See *Eddy Currents*.)

TRANSFORMER, TUNED—See *Resonance Transformer*.

TRANSMISSION—As applied to radio communication, this is the sending of signals, speech or music from one point to another by means of electromagnetic waves. (See *Radio Telephony, Radio Telegraphy, Theory of Propagation of Electromagnetic Waves*.)



A pencil of light traverses the picture which is attached to the glass drums and is analyzed by a slow rotating action as well as a backwards and forwards movement of the carrier.

TRANSMISSION OF PHOTOGRAPHS BY RADIO—Various methods have been devised and are now in use for the transmission of photographs by radio. Among these may be mentioned the systems of *Belin* (q.v.), *Baird*, and *Jenkins*. The principles underlying the Jenkins system are explained under the heading of *Television.* Using the system developed by Capt. R. H. Ranger, photographs were transmitted by radio from Honolulu to New York, a distance of 5,136 miles. Recently commercial picture transmission service has been inaugurated between New York and London using the Ranger apparatus. Two distinct methods have been applied for analyzing the picture in the process of transmission. One arrangement consists of producing an image as a non-conducting deposit upon a metal foil which is traversed by a stylus, while the other method makes use of an opaque image deposited upon a transparent film which is traversed by a beam of light, the light interruptions being recorded by a light sensitive cell. The Ranger system makes use of this latter method. The image is photographically recorded upon a celluloid sheet large enough to accommodate easily a picture of half-plate size. In the case of sketches and written messages the image for transmission is made directly by writing upon a piece of transparent film with a dense black ink. The image is then secured to the face of a glass cylinder, and by means of a lamp, focussing lens and reflecting prism, a narrow pencil of light is passed through the film. The cylinder is mounted on a carrier which is caused to be moved backward and forward so that the beam of light is concentrated in turn on all parts of the picture. A rotary motion is applied, as well as the transverse motion, the cylinder being given a slight rotation when it completes each transverse motion. The beam of light is passed through a special photo-electric cell. This consists of a spherical globe, coated on the inside with potassium hydroxide, which is very sensitive to light. The coating is connected to the grid of a vacuum tube, while an "electron collector" near the center of the tube is joined to the plate of the first amplifier. When no light is falling on the deposit on the inner surface of the globe, the grid acquires a negative charge, stopping the flow of electrons between filament and plate, and hence no current flows in the external circuit. The ray of light, however, causes an electron stream to flow between the coating and the collector, and since the coating is connected to the grid, the electron flow constitutes a discharged circuit, so that the grid becomes less negative. The first amplifying tube is a direct current potential amplifier, and is resistance coupled. The grid and plate connections of the amplifier are connected across a condenser which becomes discharged with the fall in the grid to plate resistance of the valve brought about by the grid potential fluctuations. A charging circuit is connected to the condenser and is controlled by a valve, the grid circuit of which operates by variations of the potential across the condenser. The charging current is fed through the plate circuit of this valve, in which a relay is connected, which working through other mechanical relays in cascades, controls the radio transmitter. Wave trains from the transmitting station after detection and amplification, are applied to the picture recorder. The recording mechanism, in order that it may be sensitive to exceedingly small currents, comprises, a small moving coil, in a magnetic field created by three electromagnets. The coil of wire, in moving in the field, as the received fluctuations are applied through its windings, operates a stylus while travelling across the surface of the paper. The stylus traverses the paper in perfect synchrony with the carriage of the transmitter, the paper being lifted each time the stylus completes a forward and backward movement across the paper. A small flashing neon lamp is used to indicate the correct speed adjustment of the driving motor.



The recording mechanism of the receiver. Three electromagnets produce the magnetic field in which a moving coil controls the stylus.

TRANSMITTER—An apparatus for sending out electrical messages. As applied to radio telegraphy or radio telephony, the transmitter refers to the entire sending apparatus. The term transmitter is often used to refer to a *telephone transmitter* (q.v.). (See *Automatic Transmitter*, also *Wheatstone Transmitter.*)

TRANSMITTING AERIAL—A wire, or more usually a group of wires, suspended at a suitable height and connected to a radio transmitting set. The purpose of the aerial is to facilitate the radiation of the electromagnetic waves generated by the high frequency oscillating current which flows in the aerial. (See *Directional*, also *Receiving Aerial.*)

TRANSMITTING JIGGER—An *oscillation transformer* (q.v.) having a variable secondary, permitting of various degrees of coupling, by adjustment, between the two circuits. (See *Jigger*).

TRANSMITTING KEY—A telegraph key, used in the sending of radio code messages. This key must be of rather heavy construction since it handles larger currents than those used in ordinary wire telegraphy. Pressing the key, closes the circuit, and by holding the key down for a longer or a shorter period, the dots and dashes of the continental code are reproduced. (See *Code, Key, Key High Speed.*)

TRANSMITTING TUBE, POWER RATING—The useful power output from an oscillating tube is the power expended by the oscillating current in the resistance of the output circuit. The power input to the tube, not counting that expended in heating the filament, is the product of the plate supply voltage and the average plate current during an oscillation.

TREMBLER—A springy metallic blade carrying a soft iron armature. The spring makes contact with a fixed contact point, but when current passes through the electromagnet, the armature is attracted and the contact is broken. The spring then resumes its normal position, re-establishing the contact and the same process is repeated again and again. (See *Interrupter.*)

TRIGGER BATTERY—A term (seldom used) denoting a small battery inserted in the grid circuit to give the grid its initial charge when a tube is being used for radio transmission. In this connection, the battery is used to replace the potentiometer. (See *Grid Battery,* also *Grid Bias.*)

TRIODE—A name used to designate the three-electrode type of *thermionic tube.* Other names sometimes applied to the same device are *audion* (q.v.), *audiotron, aerotron, electron relay* (q.v.), *electron tube* (q.v.), *pliotron* (q.v.), *thermionic valve, oscillion* (q.v.), *vacuum tube* (q.v.), etc. (See *Three-Electrode Thermionic Tube.*)

TRUE POWER—The product of the *apparent power* and the *power factor* (q.v.) in an alternating current circuit. (See *Power, True,* also *Power, Apparent.*)

"T" TYPE AERIAL—See *"T" Antenna.*

TUBE OF FORCE—A theoretical conception, similar to *Line of Force* (q.v.) used in mathematical considerations of electrostatic or electromagnetic fields.

TUBE RECTIFIER—A vacuum tube or gas filled tube used to change or rectify alternating current to direct current. The principle of the vacuum tube rectifier is the fact that the electrons will flow from the hot filament to the plate, but not in the reverse direction. Tubes are made for half-wave or full-wave rectification. (See *Rectifying Tube.*)

TUBE, THREE ELEMENT—See *Triode,* also *Three-Electrode Thermionic Tube.*

TUBE, TWO ELEMENT—See *Fleming Valve.*

TUBING—In general, this refers to the bakelite or hard rubber forms used to wind inductance coils on. Another type of radio tubing is defined under *Spaghetti.*

TUDOR ACCUMULATOR—A storage battery having special positive plates formed by the *Plante* process and negative plates of the *Faure* or pasted type. The Tudor positive is of the cast-lead type. This plate has no central web and is made by casting pure soft lead in a mold. Casting is advantageous since it permits the distribution of the metal in the plate without limitations in the manufacturing process. After the plate is removed from the mold, its surface consists of a large number of short vertical ribs which run entirely through the plate. These are bound together by short transverse ribs for the purpose of giving strength to the plate. This gives a large surface and since there is no central web, the electrolyte is enabled to circulate through the plate thus working the active material uniformly.

TUNED ANTENNA—A transmitting aerial, having a loading inductance or a variable condenser or both in series with it, for the purpose of changing the antenna wave length.

TUNED IMPEDANCE—This refers especially to a circuit, or to a method of radio frequency amplification in which a tuned inductance connected in parallel with a variable condenser is used as the method of coupling rather than transformer or resistance coupling. (See *Impedance Coupled Amplifier.*)

TUNED RADIO FREQUENCY—See *Tuned Radio Frequency Circuit.*

TUNED RADIO FREQUENCY AMPLIFIER—A combination of a *radio frequency transformer,* a variable condenser and an amplifying vacuum tube in a radio receiving circuit for the purpose of increasing the intensity or amplifying the radio frequency signals.

TUNED RADIO FREQUENCY CIRCUIT—A radio receiving circuit employing radio frequency amplification in which the radio frequency amplifier circuits may be tuned to the desired wave lengths by varying the inductance or the capacity, or both although the usual method of tuning is by means of a variable condenser in parallel with the secondary of the radio frequency transformer. A typical five-tube tuned radio frequency circuit is shown in the accompanying illustration. This consists of two stages of tuned radio frequency amplification, a detector and two stages of audio frequency amplification.



A standard five tube tuned radio frequency circuit.

TUNED RADIO FREQUENCY TRANSFORMERS—An air core *transformer* (q.v.) shunted by a variable condenser used in a *tuned radio frequency circuit* (q.v.). (See *Fixed Coils,* also *Low Loss Coils.*)

TUNED TELEPHONE—One in which the diaphragm is adjusted to vibrate at the same frequency as the current impulses to be indicated. In addition the telephone circuit may have its inductance and capacitance chosen to have the same electrical frequency, and a tuned acoustic resonator may intervene between the diaphragm and the ear.

TUNED TRANSFORMER—See *Resonance Transformer.*

TUNGAR—A trade name for a two-electrode vacuum tube especially designed for rectifying purposes. Tungar tubes are made in two ampere and five ampere capacities. They are used in *chargers* (q.v.) and also in radio sets operating directly from the lighting socket without the use of batteries. (See *Rectifying Tube.*)

A typical rectifier tube of the Tungar type. The screw-base allows it to be inserted in a standard lamp socket from which current is obtained for the filament. Connection is made to the graphite disc by means of a Fahnestock connector which clips on to the wire post projecting from the other end of the tube.

TUNING—The process of regulating the inductance and the capacity of a radio circuit in order to be in unison with a desired wave length.

TUNING, BROAD—Reception of a signal over a wide range, that is on a number of wave lengths, rather than on a single one. A receiving set which tunes broadly cannot be used where the broadcasting stations are transmitting on wave lengths near to one another. Too long an aerial may result in a receiving set tuning broadly. (See *Selectivity.*)

TUNING COIL—A coil of wire so arranged that each turn is electrically insulated from its neighbor and with a device by which contact may be made to bring any desired number of turns into the circuit so as to increase or decrease the inductance of a radio circuit so as to tune it to the desired wave length. A variable *inductance* (q.v.) used for tuning an oscillatory circuit. (See *Lengthening Coil.*)

T.Y.K. ARC—A transmitting arc used for radio telephony invented by W. Torikata, E. Yokoyama and M. Kitamura of Japan. This arc uses magnetite and brass electrodes instead of copper-carbon electrodes. A circuit diagram of the T.Y.K. system is shown in the illustration. The materials used for the electrodes are such that a high resistance film forms on their surfaces. This requires a temporary high voltage to start the discharge. This is accomplished as follows: An armature, A, is attached to one of the electrodes. The two electrodes are in contact, and a steady current is caused to flow in the circuit, through the spark induction coil B. This attracts the armature A, drawing the electrodes apart. The break of the spark coil current at its interrupter induces a high electromotive force which, acting through the coil and the spark gap in series, breaks down the film on the gap electrodes. The power supplied to the gap is 500 volts and 0.2 ampere. A condenser of approximately .05 mfd. is used in the primary oscillating circuit.



Circuit diagram of the T. Y. K. arc.

T.Y.K. sets have been used only in small units, having a range of 30 or 40 miles.

Several unusual features appear in the circuit shown in the accompanying illustration, which gives the circuit diagram of the T.Y.K. arc.

U

ULTRA-AUDION—A name sometimes applied to the vacuum tube used in connection with *beat* reception for supplying local oscillations. In general, however, the name ultra-audion applies to a circuit for radio reception. (See *Ultra-Audion Circuit.*)

ULTRA-AUDION CIRCUIT—A type of circuit used for long wave radio reception which uses a form of regeneration, without calling for the introduction of auxiliary equipment in the circuit. A typical ultra-audion circuit is illustrated. It will be noticed that while one terminal of the secondary goes to the grid, the other terminal, which usually goes to the filament, in this case goes to the plate. Thus there is a direct plate-filament circuit which does not involve the plate and filament batteries in the usual manner.



Diagram of an ultra-audion regenerative circuit.

ULTRADYNE—A modification of the *super-heterodyne circuit* (q.v.), which uses the modulation method to produce beats. In this method the incoming signal is caused to modulate the oscillations produced locally in a similar way to that in which the speech or music modulate the carrier wave of a broadcast station. It is claimed that this method is simpler than the ordinary super-heterodyne and also more sensitive to weak signals.

The circuit of the improved model L-2 Ultradyne, incorporating regeneration is shown below. The long wave intermediate transformers are accurately tuned to a wave length of 3000 meters. Referring to the diagram, it will be noted that a special form of oscillator, comprising a grid and plate coil, are used together with an oscillator tuning condenser connected across the grid coil. The first tube, which is usually the detector in the standard super-heterodyne circuit, is known as the modulator tube. (See *Super-Heterodyne Receiver.*)

UMBRELLA ANTENNA—An antenna, the conductors of which form elements of a cone with the apex at the top to which the *down lead* (q.v.) is connected.

UNDAMPED—See *Undamped Alternating Current,* also *Undamped Waves.*

UNDAMPED ALTERNATING CURRENT—Periodic current (i.e., current passing through successive equal cycles of values) whose average value is zero.

UNDAMPED OSCILLATIONS—Oscillations which are sustained. *Undamped alternating current* (q.v.). Oscillations such as are generated by a *vacuum tube oscillator* or by an *arc generator.*

UNDAMPED WAVES—Continuous waves. Waves in which similar current cycles follow each other continuously instead of being broken up into groups. (See *Sustained Waves, Decadent Wave,* also *Damped Waves.*)

UNITS—Specified amounts of physical quantities used as a basis of measurement. (See *Practical Units.*)

UNITS, ELECTROMAGNETIC—See *Electromagnetic Units.*



This shows the hook-up of the Ultradyne super-het. This set is not radically different from the average super-heterodyne. The heteroformers are of the tuned air core type and the filter is shown at the input side of the circuit. Aerial and ground as well as loop may be used with this set and instead of the first detector the inventor uses a tube known as the "modulator."

V

VACUUM TUBE—An evacuated bulb, or one containing a rare gas and having three elements, filament, plate and grid. (See *Three-Electrode Thermionic Tube, Triode,* also *Dynatron.*)



A group of dry-cell vacuum tubes. The first two differ only as to the type of base; both are intended to be operated from a 4½-volt "A" battery, that is, three dry-cells connected in series. The filaments draw very little current, as can be determined from the chart. The last three tubes also have identical characteristics, but are designed to fit different types of sockets. These tubes operate from a single 1½-volt dry cell and draw approximately ¼ ampere of current. The filaments are oxide-coated and very rugged.

VACUUM TUBE AMPLIFIER, THEORY OF—The vacuum tube may be used as an amplifier or magnifier because of the fact that under proper conditions, a small variation of the electromotive force applied between the filament and the grid produces a very large variation in the current flowing in the plate circuit. It is usual to use several amplifying tubes together, suitably coupling the plate of one tube to the grid of the next, thus increasing the amplification to the desired value.

VACUUM TUBE CHARACTERISTICS Performance curves of vacuum tubes. These are obtained experimentally by keeping the filament current constant and applying various known voltages between the plate and the filament and between the grid and the filament and reading the resultant currents that flow to the plate and the grid. The various values obtained are then plotted on cross-section or graph paper. Such curves are convenient for determining the operating characteristics of a particular vacuum tube under consideration. (See *Characteristic Curve.*)

VACUUM TUBE GENERATOR—The vacuum tube can be used to produce sustained oscillations without the necessity of supplying potential variations to the grid from an external source. This can be accomplished as a direct result of the amplification properties of the vacuum tube, since the energy of the output circuit is greater than the energy of the input circuit and part of this output energy may be returned to the input to produce constant reamplification.

VACUUM TUBE, POWER—A tube of special design, made for use in the last audio stage of a radio receiving set, which will handle greater current than the ordinary amplifying tube, thus resulting in more volume and at the same time clearer and more satisfactory tone reproduction. Power tubes now on the market require higher plate voltages than conventional tubes, ranging from 135 volts upwards. The amount of grid bias or "C" battery ranges from approximately 4½ volts to 45 volts, depending upon the type of power tube. Tubes suitable for developing considerable power, in radio transmission are also referred to as power tubes.

By increasing the surface area and hence the filament emission or by increasing the degree of evacuation of the bulb, thus allowing a higher plate voltage, the output of the tube may be increased. A form of transmitting power tube is described under the heading *Pliotron.* The illustration below shows one of the new power tubes used for reception.

LAST AUDIO STAGE
UX-171
CX-371

A new storage-battery type power amplifier tube, for use in the last stage audio amplifier only. This tube takes the same filament voltage and filament current as the No. 112 tube but employs a "B" voltage of 180 and 40½-volt "C" battery. Special means should be provided for handling its heavy output.

VACUUM TUBE RECTIFIER—A vacuum tube designed or used to change alternating current to direct current. (See *Rectifying Tube, Kenotron,* also *Tube Rectifier.*)

VACUUM TUBE, THEORY OF OPERATION—See *Theory of Operation of Vacuum Tubes.*

CHART OF VACUUM TUBE TYPES AND CHARACTERISTICS

TYPE	USE	"A" battery volts (Supply)	Filament Terminal Volts	"A" Battery Current Amperes	"B" Battery Volts Det.	"B" Battery Volts Amp.	Negative "C" Battery Volts	Voltage Amplification Factor	Output Resistance Ohms
UV. UX-199 C. CX-299	Det. or Amp.	4.5	3	.06	45	90	4.5	6.25	15,000
UV. UX-200 C. CX-300	Det. only	6	5	1.0	16 to 22½				
UX-200-A CX300-A	Det. only	6	5	.25	Max. 45				
UV. UX.201-A C. CX. 201-A	Det. or Amp.	6	5	.25	45	90 to 135	4.5 9.0	8 8	12,000 11,000
UX-120 CX-220	Pow. Amp. (Lst. stg. only)	4.5	3	.125		135	22.5	3.3	6,600
UX-112 CX-112	Det. or Amp.	6	5	.5	22½ to 45	135	9.0	Var.	Var.
UX-171 CX-371	Pow. Amp. (Lst. stg. only)	6	5	.5		180	40.5		
UX-210 CX-310	Pow. Amp. Oscillator	6	6	1.1		90 to 425	4.5 to 35	Var.	Var.
WD-11 C-11	Det. or Amp.	1.5	1.1	.25	22½	90	4.5	5.6	14,000
WD. WX-12 WX. CX-12	Det. or Amp.	1.5	1.1	.25	22½	90	4.5	5.6	14,000
3VB-199 3VBX-199	Det. or Amp.	4.5	3	.06	20	80	4.5	6.0	
3V-A 3VAX	Det. or Amp.	4.5	3	.12	20	90	4.5	6.5	
5V-A 5VAX	Det. or Amp.	6	5	.25	20	100	4.5 to 9.0	9.4	9,400
5VC 5VX	Pow. Amp. or Det.	6	5	.5	22½	90 to 157½	6 to 10.5	8.6	5,900
99 99X	Det. or Amp.	4.5	3	.06	22½	90 to 150	3 to 12		
O1A O1X	Det. or Amp.	6	5	.25	22½	90 to 150	3 to 12		
MU-20	Audio Amp.	6	6	.25		90 to 150	4.5 to 10.5	20	40,000
MU-6	Pow. Amp. (Lst. stg. only)	6	6	.5		90 to 150	4.5 to 10.5	6	5,000
B-6	Det. only	6	5	.25	16 to 22½				
A	Det. or Amp.	6	5	.25	20	120	4.5 to 9		
B C	Det. or Amp.	4.5	3	.06	20	80	4.5		
E	Pow. Amp. (Lst. stg. only)	4.5	3	.125		135	22.5		
F	Pow. Amp. (Lst. stg. only)	6	5	.5		90 to 180	4.5 to 9		
G	Audio Amp.	6	5	.25		90 to 180	4.5 to 9		
DC—	Det. or Amp.	4.5	3	.06	45	90	4.5	6.3	16,500
DC—	Det. or Amp.	6	5	.25	45	90	4.5	8.5	10,000
DC—	Pow. Amp. (Lst. stg. only)	4.5	3	.125		112 to 135	13 to 22.5	3.3	6,300
DC—	Pow. Amp. (Lst. stg. only)	6	5	.5		90 to 157.5	6 to 10.5	8.0	8,500

VACUUM TUBES, TYPES OF—Vacuum tubes are of various types and designs depending upon the work which they must do. They may be divided into two general classes, receiving tubes and transmitting tubes.



A new type of detector tube which has greater sensitivity than former types, due to the use of an alkaline vapor. It can be used as a detector in any type of receiving circuit.

Tubes for receiving purposes are designed either for dry cell operation or else are of the storage battery type. They may be further classified as detector tubes, amplifying tubes or power tubes. There are many special types of tubes, such as *kenotrons* (q.v.), *pliotrons* (q.v.), etc.



These power amplifier tubes are designed for use in the last stage of an audio frequency amplifier. On the left is a dry cell tube which requires a 4½-volt "A" battery. The center tube employs exceptionally high "B" battery voltage, and is usually employed with an amplifier that operates from the house current. This tube can also be used for transmitting purposes. The right-hand tube is of the storage battery type and has a very rugged filament. It makes an excellent detector tube as well as a power amplifier.

VALENCY—The property possessed by elements in combining with or replacing other elements in a certain definite proportion. Also referred to as *valence*. (See *Electro-Chemical Equivalent.*)

VALVE—This generally refers to a vacuum tube used as a detector or rectifier. The name *valve* is used in many foreign countries to refer to the thermionic vacuum tube, as used for any purpose.

VALVE DETECTOR—See *Valve.*

VARIABLE CONDENSER—A condenser having rotable or movable metal plates and an air dielectric. Both the stationary and rotating plates may be made of brass, copper or aluminum. Bakelite, fibre or composition are used to insulate the stationary from the movable plates. Turning the movable plates either increases or decreases the capacity of the condenser. Variable condensers are primarily used in radio for *tuning* (q.v.). They are constructed so as to have straight line frequency characteristics either by undercutting a portion of the movable plates or else by making these of a variable thickness.

VARIABLE GRID LEAK—A variable high resistance unit designed to be placed in the grid circuit of a vacuum tube used as a detector. Certain types of variable grid leaks may have their resistance varied from ¼ megohm to 10 or more megohms by merely tightening a thumb-screw. (See *Grid Leak*, also *Adjustable Grid Leak.*)

VARIABLE RATIO TRANSFORMER—A transformer in which the ratio between the primary and the secondary windings can be varied, usually by means of suitably located taps.

VARIABLE RESISTANCE—Both the *rheostat* and the potentiometer used in radio work, are variable resistances. Variable resistances are usually of high resistance wire type, with a sliding contact so that the resistance can be easily altered.

VARIO COUPLER—A tuner formerly used in radio receiving sets, having a primary and a secondary coil inductively coupled, with the secondary arranged so as to be rotable within the primary. The amount of coupling depends upon the variation of the angle between the axes of the two coils.



A standard form of vario coupler.



A variometer.

VARIOMETER—A tuner, similar to the vario-coupler, except that the primary and secondary coils are electrically connected.



The characteristics of these vacuum tubes are given in the vacuum tube chart on page 187. The first tube is of the dry-cell type, requiring a 4½-volt "A" battery for lighting the filament. 3V-A is a standard 5-volt tube. 5VX is a power amplifier which can be used in the last stage of any audio-frequency amplifier. There is no necessity of changing any of the wiring in the set for the addition of more "B" battery, as binding posts are included on the tube itself. 5VA has a sponge rubber ring included as a part of the base which tends to absorb all vibrations which might otherwise cause the tube to become noisy. The next type of tube is for use as a detector only. The last is the well-known 201-A type, which can be employed as a detector or an amplifier.

VECTOR—A graphical illustration used in mathematical calculations, consisting of a line with an arrow-head at one end, used to show by means of its length, direction and the angle between itself and another vector or vectors, the magnitude, direction and phase angle of alternating current quantities.

VELOCITY—The distance passed through in a certain time. Velocity is measured in feet per second, miles per hour, etc.

VIBRATION—A to and fro motion. An oscillating or swinging motion.

VITREOUS—Consisting of or pertaining to glass. (See *Resinous Electricity.*)

VOLT—The practical unit of *electromotive force* (q.v.). The volt is a measure of the electromotive force which will cause a current of one ampere to flow through a resistance of one ohm. It is equal to 10^8 absolute electromagnetic units (Abvolts).

VOLTAGE—The electrical pressure or the electromotive force between two points in an electrical circuit, measured in volts.

VOLTAGE, CONSTANT—A steady unvarying electrical pressure or electromotive force, as differentiated from a pulsating or fluctuating voltage.

VOLTAGE DROP—The fall in potential caused by the resistance of the conductor through which the current is flowing. The longer the conductor, the greater will be the voltage drop. The greater the cross-section of the conductor, the less will be the voltage drop.

VOLT-AMPERES—The product of volts as measured with a voltmeter, by the current as shown on an ammeter, in an alternating current circuit, gives the apparent power, or in other words the apparent watts. (See *Instantaneous Values.*)

VOLTMETER—An instrument for measuring voltage drop or potential difference. Most of the voltmeters used in radio work operate on the moving coil principle. (See *Galvanometer.*)

A plug-in type of voltmeter.

Panel-type of voltmeter.

VOLTMETER CALIBRATION—A method of correctly marking the voltage readings on the scale of a voltmeter or of checking up the voltmeter readings to make sure that they are accurate. The usual method of calibration is to check the voltmeter reading by comparison with a standard voltmeter. (See *Calibration.*)

V.T.—Abbreviation for *vacuum tube.*

VULCANITE—(EBONITE)—A hard black substance produced by vulcanizing rubber with about 25 per cent sulphur. It is readily polished and has excellent insulating properties.

VULCANIZED RUBBER—Pure rubber, mixed with five per cent sulphur and baked at a temperature of about 150 degrees Centigrade. Vulcanized rubber must not be allowed to come into contact with copper, which is chemically attacked by the sulphur.

W

WALL TUBE—See *Partition Insulator.*

WATCHCASE RECEIVER—A telephone receiver having a shape somewhat similar to a watch. Watch case receivers are compact in construction and are the usual type used in the radio telephone *head set.*

WATT—The unit of electric power. One *Joule* (q.v.) per second. To find power in a direct current circuit, multiply voltage by amperage. The *Kilowatt* (q.v.) equals one thousand watts. Seven hundred and forty-six watts are equivalent to one electrical horsepower.

WATT HOUR—The commercial unit of electrical work. The work done in one hour by a current of one ampere flowing between two points of a conductor having a difference of potential of one volt.

WATT-HOUR METER—An integrating meter which measures energy in watt-hours or in kilowatt-hours. (See *Integrating Wattmeter.*)



A direct current watt-hour meter.

WATT, INTERNATIONAL—symbol W—The energy expended per second by an unvarying electric current of one International ampere under an electrical pressure of one International volt. IW = 1 Joule per second = 10^7 ergs per second.

WATTLESS COMPONENT—WATTLESS CURRENT—The component of an alternating current which is in quadrature with the voltage. (See *Reactive Component.*)

WATTMETER—An instrument designed to measure the power being expended in an electrical circuit. The most common form of direct current wattmeter is of the dynamometer type. This has two coils, one fixed and one movable, one coil being connected so as to exert a force proportional to the current flowing in the circuit, and the other coil exerting a force proportional to the electromotive force. The *induction* type of wattmeter is in general use for alternating current circuits. (See *Electro-Dynamometer, Dynamometer,* also *Induction Wattmeter.*)

WATT SECOND—A unit of electrical energy, representing the energy expended by one watt flowing for a second. The watt second is the same as the *Joule* (q.v.) and is usually applied to the measurement of heat developed by an electric current.

WAVE—A periodic alternation of an alternating current. As applied to an electric or electromagnetic disturbance, an electric wave is an undulatory movement of the ether, radiated from conductors carrying electrical oscillations.

WAVE ANALYSIS—A study of the wave form of an alternating current or other type of wave. The wave form of commercial alternating current used for lighting purposes approximates a *sine curve* (q.v.). A convenient instrument for the analysis and study of alternating current wave form is known as the *oscillograph* (q.v.).

WAVE ANTENNA—A horizontal antenna, the physical length of which is approximately equal to the length of signaling waves to be received, and which is so used as to be strongly directional.

WAVE DISTORTION—Alteration in the wave form of a wave after it has traversed a considerable distance. (See *Distortion.*)

WAVE FORM—Referring to an alternator, the "shape" of the curve of the current generated.

WAVE FREQUENCY—See *Frequency.*

WAVE LENGTH—symbol λ (lambda)—The distance between two successive *antinodes* (q.v.) in the same direction. In referring to the wave length of electrical oscillations in a circuit, this means the length of the waves in free space that would have a frequency corresponding to the given oscillations. Electromagnetic waves used in radio work have frequencies of from 10,000 to 3,000,000 cycles per second. Since these waves have a velocity of approximately 300,000,000 meters per second, it is possible to calculate the length of a wave by dividing the velocity by the frequency. In other words meters per second divided by cycles per second gives length of the wave in meters. Thus a wave having a frequency of 100 kilocycles (100,000 cycles) will have a wave length of 300,000,000 divided by 100,000 or 3,000 meters.

WAVE LENGTH ALLOCATIONS—In order to prevent radio transmitting stations from interfering with each other, or creating interference at a receiving station, various wave length bands have been allotted to each type of service. The following table shows the present short wave assignments and the service for which they are used:

Wave-length in Meters	*Service*
109–105	Relay broadcasting only.
105–85.7	Public toll service, Government mobile, and point-to-point communication by electric power supply utilities, and point-to-point and multiple address message service by press organizations only.
85.7 –75.0	Amateur, Army mobile, naval aircraft, and naval vessels working aircraft only.
75.0 –66.3	Public toll service, mobile Government point-to-point and point-to-point public utilities.
66.3 –60.0	Relay broadcasting only.
60.0 –54.5	Public toll service only.
54.5 –52.6	Relay broadcasting only.
52.6 –42.8	Point-to-point only.
42.8 –37.5	Amateur and Army mobile only.
37.5 –33.1	Public toll service, mobile, Government point-to-point, and point-to-point public service utilities.
33.1 –30.0	Relay broadcasting only.
30.0 –27.3	Public toll service only.
27.3 –26.3	Relay broadcasting only.
26.3 –21.4	Public service, mobile, and Government point-to-point.
21.4 –18.7	Amateur only.
18.7 –16.6	Public toll service, mobile and Government point-to-point.
16.6 – 5.35	Experimental.
5.35 – 4.69	Amateur.
4.69 – 0.7496	Experimental.
0.7496– 0.7477	Amateur.

Radio broadcast stations work within the wave length band of 200 to 545 meters at intervals of 10 kilocycles. 600 meters is reserved for distress signals. The higher wave lengths are allocated to various marine, government, university, aircraft and other uses.

WAVE LENGTH CALCULATION FOR ANTENNA—For the ordinary vertical wire grounded antenna, the fundamental wave length is slightly greater than four times the length of the wire. A constant suggested is 4.2 and applies approximately also to flat top antennae having vertical lead ins. For other calculations see *Fundamental Wave Length.*

WAVE LENGTH, FUNDAMENTAL—See *Fundamental Wave Length.*

WAVE LENGTH, NATURAL—In a loaded antenna (that is with series inductance or capacity) the natural wave length corresponds to the lowest free oscillation. (See *Natural Wave Length.*)

WAVE LENGTH OF STATIONARY S. H. M. WAVES—On a straight wire, the smallest distance between two points where the disturbance is of the same amplitude and phase; or, since consecutive loops (q.v.) are in opposite phases, the wave length is double the distance between consecutive loops or consecutive *nodes* (q.v.). (See *S.H.M.*)

WAVEMETER—A radio instrument for measuring frequency. A calibrated resonator of variable frequency, capable of easy excitation by the oscillation under test, combined with a means of indicating the attainment of resonance. The calibration may be given directly in wave lengths or frequencies or both.



Photo by courtesy of General Radio Co.

The selectivity of the radio set may be greatly increased by the use of this wavemeter as a radio filter.

WAVEMETER CALIBRATION—Wavemeters may be calibrated by comparison with a standard wavemeter. An accurate method of calibrating a wavemeter, known as the *Three-Way Method* is shown in the accompanying diagram. In this illustration A is the standard wavemeter, B the wavemeter to be calibrated, and C is a condenser and coil of size permitting resonance with A. To calibrate, the buzzer should be put in operation, varying the capacity of the condenser C^1 until L^1C^1 is in resonance with L^2C^2 as noted in the head set. The wavemeter B should then be put in inductive relation to C and the condenser C^3 varied until the wavemeter A resonates with C. The wave length of B is now the same as A. This procedure should be carried out over the whole range of the condenser C^3.



Diagram showing three-way method of wavemeter calibration.

WAVE MOTION—A disturbance of the equilibrium of a medium or body, extended or propagated from point to point with a continuous motion, each particle vibrating only on each side of its position of equilibrium, while each phase of vibration moves onward. Examples of wave motion are the propagation of electromagnetic waves, or the waves on the surface of a body of water.

WAVES, CONTINUOUS—See *Continuous Waves.*

WAVES, CONTINUOUS, KEY MODULATED—See *Continuous Waves, Key Modulated.*

WAVES, CONTINUOUS, MODULATED AT AUDIO FREQUENCY—See *Continuous Waves at Audio Frequency.*

WAVES, ELECTROMAGNETIC—Periodic electromagnetic disturbances progressive through space. (See *Wave.*)

WAVES, SUSTAINED—See *Sustained Waves,* also *Continuous Waves.*

WAVE TRAIN—A series of waves. An example of a wave train is the series of disturbances set up by each spark in a spark system of radio telegraphy.

WAVE TRAP—A device consisting of a variable condenser and coil, usually connected in the antenna circuit of a receiving set, to eliminate interference from undesired stations. (See *Filter, Filter Condenser, Acceptor,* also *Rejector.*)

WAVE-WOUND—A class of drum armature in which connections produce a "stepping forward" in a zig-zag wavy line all the time. Also called *Series* and *Two Circuit Windings.*

WEBER—The *Practical Unit* (q.v.) of magnetic flux. The engineers' unit is the "line" which is also the electromagnetic unit. 1 Weber is equal to 108 electromagnetic units (or "lines"). The Weber is produced by a current of one ampere flowing through a circuit having one henry of inductance.

WEHNELT BREAK—An *electrolytic interrupter* (q.v.).

WEIGHT—The force with which the earth attracts a body. A body varies in weight according to its distance from the centre of the earth, although its mass remains constant.

WESTON CELL—The present standard cell. It consists of mercury with a paste of mercurous and cadmium sulphates which form the cathode. The Weston cell has an anode of 12.5 per cent cadmium amalgan in an electrolyte of saturated solution of cadmium sulphate. It has a constant electromotive force of 1.0125 volts at 20 degrees Centigrade. (See *Electromotive Force,* also *Cadmium.*)

WHEATSTONE BRIDGE—An instrument for measuring resistance in which the current from a battery divides into two parallel circuits, each



Diagram illustrating principle of the Wheatstone Bridge.



Post-Office type of Wheatstone Bridge.

divided into two "arms" capable of being adjusted so that there is no difference of potential between the dividing points on both sides. The point of zero difference of potential is indicated by the absence of deflection of a galvanometer placed across the dividing points. The ratio of the resistance of the two parts of the arms is then the same, so that if the resistance of three of the arms is known, that of the fourth arm (i.e. the resistance to be measured) can be determined.

WHEATSTONE TRANSMITTER—An apparatus for delivering telegraphic currents to a line at high speed. Control is effected by aid of a moving perforated paper tape, prepared according to a code.

WHIPPING—The binding of string or small wire round the end of a rope or multiple wire to prevent the ends from fraying out.

WIMSHURST—A type of Induction or Influence Machine consisting, in a simple form, of two discs of insulating material revolving in opposite directions. These carry a number of equal sectors which form combined inductors and carriers. There are usually two collectors and two pair of brushes. (See *Induction Machine.*)

WINDOW LEAD-IN—A form of insulator for passing an aerial *lead-in* through a window. In some cases porcelain tubes are used as window lead-in's. A common form of window lead-in consists of a flat copper conductor covered with woven cotton insulation.

WIRED WIRELESS—A method of transmitting radio messages, in which the waves are guided by wires instead of radiating freely through the ether. (See *Line Radio.*)

WIRE GAUGE—A device for measuring the diameter of a round wire in accordance with a predetermined scale. The gauge commonly used in this country is the Brown and Sharpe (B. & S.) or American gauge.

WIRELESS TELEGRAPHY—Also known as **RADIO TELEGRAPHY** (q.v.).—A system of telegraphy, utilizing electromagnetic waves set up by oscillating currents as the means of transmission. The waves generated at the transmitting station spread out from the *aerial* (q.v.) in all directions. They are intercepted by the receiving aerial, detected by a rectifying device such as a crystal or vacuum tube, amplified and delivered to a head set or loud speaker. A key is used at the transmitter to control the duration of the waves so that they will correspond to the dots and dashes of the *continental code* and these dots and dashes are reproduced in the phones at the receiving station.

WOLLASTON WIRE—Platinum wire, drawn extremely fine by the process of coating fine platinum wire with ductile material, drawing the whole down together, and (if required) removing the coating by dissolving it off.

WORK—The action of a force upon a body to overcome resistance. Work is measured by the product of the force exerted and the distance moved. Work may be measured by *ergs* (q.v.), *foot-pounds, horsepower*, etc.

WOOD'S METAL—A soft metallic alloy having a low melting point. This alloy consists of two parts of lead, one part of tin, four parts of bismuth, and one part of cadmium, all by weight. This metal has been used extensively for setting detector crystals in their cups, so as to make a good electrical contact.

X, Y, Z

X—Symbol for *Reactance* (q.v.).

"X" RAYS—Also called *Roentgen Rays.* Electric waves of much higher frequency than light, produced by the striking of *cathode rays* upon a solid substance. These rays are not deflected by electric or magnetic fields and possess the property of penetrating solid substances which could not be penetrated by ordinary light rays. The use of the "X" Rays permit photographs to be taken of bones or other parts of the human body which could not be seen in any other way.

X'S—Disturbances of an erratic nature heard from time to time in the 'phones or loud speaker of a radio receiving set, due to storms, electric disturbances, etc. (See *Atmospherics, Natural Electric Waves, Static,* also *Strays.*)

YAGI SPARK GAP—A form of spark gap originated by H. Yagi. It is a quenched spark gap, the electrodes of which are aluminum and brass. The gap functions in an atmosphere of coal gas.

"Y" GROUPING—See *Star Grouping.*



A three-phase "Y" connection.

YOKE—A piece of soft iron used in certain forms of electromagnets to yoke two parallel cores together magnetically. The cores of the ordinary electric bell are fastened together at one end by means of a yoke.

YOKOJAMA, EITARO—Japanese radio expert. He was born in 1883 and was educated at the Engineering College of the Tokyo Imperial University. While at college, he specialized in radio. He was appointed to the Electro-technical Laboratory of the Japanese Ministry of Communications, to carry out research work in wireless telegraphy and telephony. He was one of the inventors of the T.Y.K. oscillation gaps for radio telephony, for which he received many distinctions. In 1910 he was appointed head of the Radio Section. Yokojama, who is one of the most brilliant Japanese radio experts, is a member of the Institute of Radio Engineers and of many other scientific societies.

ZEEMAN EFFECT—Doubling of the spectrum lines of light sources when placed in a strong magnetic field.

ZENNECK, J.—German wireless expert. He was born April 15th, 1871, at Wurtemberg and was educated at Tuebingen. In 1895 he was appointed assistant in the Physical Institute in Strassburg, a post he held until 1899, when he carried out a series of tests in radio telegraphy in the North Sea. In 1905 he was appointed assistant professor of physics at the Institute of Technology, Brunswick and was appointed professor at Munich in 1913. Professor Zenneck has written a number of authoritative books on wireless and also a large number of articles on electro-magnetic oscillations.

ZERO BEAT RECEPTION—The detection of continuous modulated waves using a local source of high frequency current having a frequency equal to that of the incoming wave. When this continuous voltage is impressed on the incoming modulated voltage, (both of the same frequency) the output of the detector contains a current of audio frequency similar in character to the modulated current at the transmitter.

ZERO METHOD—A method of measurement in which various adjustments are made until the current flowing through a galvanometer is reduced to zero, as in a *Wheatstone Bridge* (q.v.). (See *Null Method.*)

ZINC—A metallic element. Its chemical symbol is Zn. In color, zinc is bluish-gray. It is practically non-corrosive in the atmosphere, is capable of taking a high polish, is unaffected by water, but is soluble in nitric acid and in soda and potash solutions. Pure zinc is attacked very slowly by sulphuric acid, but this feature is one of the greatest in the application of zinc in radio work and in electrical work generally.

Zinc is one of the most important components of most dry cells. It forms the negative terminal in most "B" batteries. Zinc in rod form is used in most forms of wet cells.

ZINCITE—An oxide of zinc. Zincite crystals can be distinguished by their red color, often broken up by orange-yellow streaks. This crystal, in combination with several other crystals makes a very excellent detector for radio purposes. The *perikon detector* (q.v.) is a combination of zincite and chalcopyrites. Zincite is also used in combination with bornite, galena, copper, iron pyrites, tellurium and silicon.

ZIRCONIUM—One of the metallic elements. Its chemical symbol is Zr, and its atomic weight is 90.6. Zirconium is an iron-gray powder in one form, or it may be made to crystallize. The crystals look like antimony, are very brittle and extremely hard, being capable of scratching glass and rubies. Zirconium resembles thorium in many of its chemical properties. For the control of the vacuum in high vacuum tubes, a small quantity of thorium or zinconium is included in the tube. These metals combine with hydrogen, oxygen, nitrogen, etc., to form compounds of very low vapor pressure.

SUPPLEMENT

CLASSIFIED INDEX TO S. GERNSBACK'S RADIO ENCYCLOPEDIA

In the following index various co-related subjects have been gathered together for the convenience of the reader or student, under appropriate headings. Thus, under the heading of "Circuits," every circuit contained in the Encyclopedia is listed. Other important subjects are similarly treated. Where the reader is interested in but a single item such as, for example, "Bolitho Circuit," this can be found more conveniently by referring to the Encyclopedia itself, which, of course, is arranged in alphabetical order. All separate and unrelated headings or subjects should be looked up in this manner, that is by referring directly to the Encyclopedia, as these are not listed in the index.

A

Page

AERIAL, (6)
  Balancing 21
  Circuit 9
  Fan 65
  Frame 71
  Height of 79
  Horizontal 83
  Insulation of 91
  Insulator 92
  Inverted "L" 94
  Length of 100
  Light Line 101
  Plain 125
  Quiescent 129
  Receiving 131
  Switch 9
  Transmitting 154
  Tuning Condenser 9
  Wire 10

ALTERNATING CURRENT, (11)
  Theory of Production 12
  Undamped 156

ALTERNATOR, (12)
  Alexanderson 11
  Definition 12
  Goldschmidt 74
  High Frequency 81
  Inductor 90
  Laminated Core 99
  Polyphase 126
  Single Phase 139
  Synchronous Motor 148

AMPLIFICATION
  Audio Frequency 19
  Cascade 32
  Constant 14
  Factor 14
  Impedance Coupled 86
  Radio Frequency 15
  Resistance Coupled 134
  Voltage 14

AMPLIFIER, (14)
  Action of Vacuum Tube 15
  Audio 19
  Intermediate Frequency 15, 93
  Radio Frequency 15
  Resistance Coupled 134

ANTENNA, (6)
  Aeroplane 10
  Cage 29
  Capacity Measurement 31
  Gamma type 73

Page
  Inductance 80
  Non Radiative 118
  Resistance 16
  Tuned 155
  Tuning Condenser 138
  Umbrella 156
  Wave 159
  Wave Length Calculation for 160

ARC
  Characteristic 16
  Duddell Singing 56
  Generator 16
  Generator System 16
  Magnetic Blowout for 108
  Poulsen 126

B

BATTERIES, (22)
  "A" 3
  Accumulator 136
  "B" 22, 125
  "C" 32
  "C" Curve 32
  Cell 33
  Charger, Balkite 21
  Chloride 35
  Daniell's Cell 50
  Electrolytic Cell 60
  Filament 67
  Float 70
  Galvanic 72
  Gravity 75
  Grid 75
  High Potential 81
  High Tension 82
  Of Alternators 22
  Parallel Connection 3
  Plate 125
  Primary Cell 127
  Secondary Cell 33, 136
  Series Connection 3
  Series-Parallel Connection 3
  Storage 3, 136
  Testing Instruments 22
  Theory of Primary Cell 34
  Trigger 155

BIOGRAPHIES
  Alexanderson, Ernst F. W. 10
  Appleton, Edward Victor 16
  Arco, Graf George Von. 17
  Armstrong, Edw. H. 17
  Austin, Louis Winslo 19
  Belin, Edward 23
  Bell, Alexander Graham 23

Page
  Bellini, Dr. Ettore 23
  Blondel, Andree 23
  Blondlot, Professor Prosper Reno 23
  Branly, Edward 24
  Braun, Ferdinand 25
  Brown, Sidney George 27
  Carpentier, Jules 31
  Clerk-Maxwell, James 36
  Cohen, Louis 39
  Crookes, Sir William 45
  De Forest 51
  Dubilier, William 56
  Edison, Thomas Alva 58
  Faraday, Michael 65
  Fessenden, Reginald Aubrey 66
  Fleming, John Ambrose 68
  Gernsback, Hugo 73
  Gernsback, Sidney 73
  Goldschmidt, Rudolph 74
  Goldsmith, Dr. Alfred N. 74
  Hammond, John Hays, Jr. 78
  Heaviside, Dr. Oliver 79
  Heising, Raymond A. 79
  Henry, Joseph 80
  Hertz, Heinrich Rudolph 80
  Hogan, John V. L. 82
  Hooper, Stanford C. 83
  Janet, Paul 95
  Kelvin, Lord William Thompson 96
  Kimura, Shunkichi 98
  Kolster, Frederick A. 98
  Koomans, Nicholas 99
  Korn, Arthur 99
  Langmuir, Irving 99
  Latour, Marius 100
  Lodge, Sir Oliver 102
  Lombardi, Dr. Luigi 105
  Marchant, Edgar Walford 110
  Marconi, Guglielmo 110
  McLachlan, Norman W. 111
  Meissner, Alexander 112
  Mullard, S. R. 115
  Nally, Edward Julian 115
  Noble, Sir William 118
  Pannill, Charles Jack 122
  Phillips, Raymond 124
  Pickard, Greenleaf ttier 124
  Poulsen, Valdemar 126
  Prince, Charles Ed d 127
  Pupin, Michael 127
  Rayleigh, John W am Strutt 131
  Roberts, Joseph rrison Thompson 135
  Robinson, Jame 135
  Robinson, Sam S. 135
  Rutherford, S Ernest 136
  Squier, Majo eneral George Owen 143
  Tesla, Nikol 151
  Yokojama, aro 161
  Zenneck, J 161

C

CAPACITY, (30) Page
Calculation 29
Amt. of 34
Circuit 30
Condenser 40
Condenser Curves 40
Condensers in Parallel 30, 41
Condensers in Series 31, 41
Conversion Factor 30
Definition 30
Distributed 55
Earth 30
Electrostatic 63
Farad 65
Frequency Factor 30
Ground 30
Measurement of Antenna 31
Mutual 115
Resistance 31
Switch 31

CIRCUITS
"A" Battery 3
Armstrong Circuit (Original) 18
Armstrong 3-Circuit Regenerative Receiver 18
Armstrong Super-Regenerative 147
Audio Amplifier 19
Audio Frequency 71
Autoplex 19
Balanced 20
Balanced Metallic 20
"B" Battery 22
Bolitho 24
Breaker 36
Broken 36
Buzzer 29
Buzzer Exciter 29
Cascade N. F. and detector 32
Closed Circuit 37
Cockaday 37
Cockaday, with push-pull amplifier 37
Coupled circuits 44
Crystal 31, 46
Definition 36
Detector 52
Direct Coupled 54
Fourth 71
Heising 79
Heterodyne 79, 80
Impedance Coupled 85
Interference Eliminator 93
Inverse Duplex 94
Neutrodyne 117
Open 36
Parallel 36
Receiving 131
Reflex 132
Regenerative 65
Reinartz 133
Resistance Coupled 134
Series 3
Series Parallel 3
Short 138
Single Stage Radio Frequency amplifier 15
Super-Heterodyne 145, 146
Super-Regenerative, Armstrong 147
Three-Wire 117
Tuned Radio Frequency 155
Two-stage Audio Amplifier 19
T. Y. K. Arc 156
Ultradyne 156
Page
Vacuum Tube, Non-Regenerative 52
Vacuum Tube, Regenerative 52

COHERER, (39)
Autocoherer 19
Branley 24
Definition 39
Granular 75
Lodge Disc Detector 108
Marconi Filings 110
Slaby-Arco-Vacuum 141

CONDENSER, (40)—See also Capacity
Aerial Tuning 9, 138
Air 10
Balanced Rotary 21
Billi 23
By-Pass 40
Compressed Air 39
Curves 40
Definition 40
Electrolytic 60
Filter 68
Fixed 41
Grid 41, 76
In Parallel 41
In Series 41
Korda Air 99
Leyden Jar 101
Mica 41
Moscicki 114
Paper 122
Phone 41
Rotary 136
Shortening 138
Stopping 144
Telephone 149
Variable 41

COILS (39)
Antenna 39
Astatic 18
Basket 21
Choke 35
Cockaday 38
"D" 50
Damping 50
Definition 39
Duolateral 56
Exploring 65
Feed-Back 65
Fixed 68
Honey-Comb 82
Impedance 85
Inductance 87
Induction 88
Jigger 95
Loop Antenna 105
Lorenz 106
Low Loss 107
Movable 115
Pancake 122
Plug-In 125
Primary Induction 89
Radio Frequency 130
Reactance 131
Reaction 131
Retardation 135
Repeating 133
Spark 142
Spider Web 143
Tesla 151
Tickler 153
Tuning 155
Page
Vario Coupler 44, 158
Variometer 158

COUPLING, (44)
Coefficient 44
Close 37
Conductive 41
Coupled Circuits 44
Degree of 45
Definition 44
Direct 54
Electrostatic 63
Feed Back 65
Inductive 90
Regenerative 133
Transformer 45, 153

CRYSTALS
Bornite 24
Carborundum 31
Cat-Whisker for 32
Cerusite 34
Chalcopyrite 34
Definition 45
Detector 45
Galena 72
Iron Pyrites 94
Molybdenite 114
Nagyagite 115
Quartz Oscillator 129
Receiver 46
Rectifier 46
Silicon 138
Theory of Operation 46
Zincite 161

CURRENT, (46)
Alternating 11, 47
Anode 16
Assumed Direction of Flow 18
Audio frequency 19
Carrying Capacity of Wire 47
C. G. S. Unit of 34
Constant 42
Consumption 42
Continuous Direct 42
Convection 42
Critical 45
Decay of 50
Definition 46
Density 47
Direct 47
Direction of Flow (Assumed) 47
Displacement 54
Eddy 58
Electron Theory 62
Emission 64
Flow of 70
Fluctuating 70
Foucault 70
Free Alternating 71
Full Load 72
Grid 76
Ground 77
Harmonic 78
High Frequency 48, 81
High Tension 48
Idle 85
Intermittent 98
Leading 100
Low Frequency 48, 107
Modulated 114
Nature of Electric 49

Page

- Oscillating 120
- Oscillatory 120
- Overtone 122
- Primary 48
- Production of Electric 48
- Pulsating 127
- Pulsating Direct 48
- Radio Frequency 130
- Reactive 131
- Rectified 131
- Rotary 136
- Secondary 48, 137
- Space 142
- Stray 145
- Theory of Alternating 11
- Theory of Electric 49
- Theory of Flow 151
- Undamped Alternating 56

D

- DETECTOR, (52)
  - Balanced 20
  - Barreter 21
  - Carborundum 31
  - Circuit 52
  - Coherer 39
  - Combination 39
  - Crystal 45
  - Crystal, Theory of Operation 46
  - Cymoscope 49
  - Damped Wave 52
  - Disc, Lodge 103
  - Electrolytic 60
  - Hozier-Brown 84
  - Liquid Barreter 102
  - Lodge Disc 103
  - Marconi Filing Coherer 110
  - Perikon 123
  - Silicon 138
  - Theory of Detector Action 151
  - Thermal 152
  - Ticker 153
  - Tikker 153
  - Tone Wheel 153
  - Vacuum Tube 52, 157, 158
  - Valve 158
- DIELECTRIC, (53)
  - Absorption 53
  - Coefficient and Constant 53
  - Frequency 54
  - Constants, Table of 54
  - Hysteresis 54
  - Strength 54
- DISCHARGE
  - Brush 27
  - Corona 43
  - Oscillatory 120
  - Oudin Resonator for 121
  - Spark 142

E

- ELECTRIC
  - Absorption 59
  - Adhesion 6

Page

  - Displacement 59
  - Elasticity 59
  - Field 59, 66
  - Induction 59
  - Electricity 59
  - Osmosis 121
  - Potential 126
- ELECTROLYTIC
  - Action 60
  - Battery Charger 60
  - Cell 60
  - Condenser 60
  - Conduction 60
  - Decomposition 51
  - Detector 60
  - Interrupter 61, 94
  - Rectifier 61
  - Rectifier, Full Wave 61
- ELECTROMAGNETIC
  - Attraction 62
  - Control 61
  - Field 61, 66
  - Flux 61
  - Impulse 61
  - Induction 61, 89
  - Inertia 90
  - Instruments 61
  - Microphone 61
  - Radiation 62
  - Repulsion 62
  - Switch 62
  - Theory of Light 62
  - Units 62
  - Waves 62, 160
- ELECTROMOTIVE FORCE, (62)
  - Active Pressure 6
  - Back 20
  - Breakdown Potential 25
  - C. E. M. F. 34
  - Counter 44
  - Current, Resistance Relationships (Ohms Law) 119
  - Definition 62
  - Induced 86
  - Kirchoff's Laws 98
  - Potential, Electric 126
  - Pressure, Electrical 127
  - Volt 159
  - Voltage 159
  - Voltage, Constant 159
  - Voltage Drop 159
- ELECTRON (62)
  - Flow 62
  - Emission 62
  - Relay 63
  - Theory 62
  - Tube 63
- ELECTROSTATIC, (63)
  - Capacity 63
  - Charge 63
  - Coupling 63
  - Field 63, 66
  - Flux 63, 70
  - Flux Density 63
  - Force 63
  - Induction 63, 89
  - Leakage 64
  - Line of Force 64
  - Strain 64

Page

  - Systems 64
  - Units 64
  - Voltmeter 64
  - Wattmeter 64

F

- FEED BACK, (65)
  - Armstrong's Circuits 17
  - Coil 65
  - Coupling 65
  - Definition 65
  - Effect 65
  - Regeneration 133
  - Regenerative Circuit 133
  - Reinartz Circuit 133
  - Tickler 153
- FIELD, (66)
  - Density 66
  - Electric 66
  - Electromagnetic 66
  - Electrostatic 66
  - Magnet 66
  - Magnetic 66
  - Regulator 66
- FILAMENT, (66)
  - Battery 67
  - Consumption 67
  - Current 67
  - Formula for Electron Flow 67
  - Rheostat 67
  - Resistance 67
  - Thoriated 67
- FLUX, (70)
  - Density 70
  - Distribution 70
  - Electrostatic 70
  - Leakage 70
  - Lines 70
  - Magnetic 70
  - Magnetism 70
- FREQUENCY, (71)
  - Alternator of 71
  - Audio 19, 71
  - Band 71
  - Carrier 71
  - Changer 71
  - Circuit, Audio 71
  - Circuit, Radio 71
  - Cycle 49
  - Definition 71
  - Fundamental 71
  - Group 71, 77
  - High 71
  - Low 71
  - Meter 71
  - Periodicy 123
  - Radio 72
  - Unit of 72
  - Variation of Power Factor with 72

G

- GALVANOMETER, (73)
  - Constant 73
  - D'Arsonval 73
  - Mirror 73, 114

GRID, (75) Page
Battery 75
Bias 76
Circuit 76
Condenser 41, 76
Control 76
Current 76
Leak 6, 76
Potential, Modulation of 76
Potentiometer 77

GROUND, (77)
Clamp 77
Connection 77
Currents 77
Detector 77
Switch 77
Wire 77

H

HETERODYNE, (80)
Beats 22
Dissonance 55
Driver 56
Local Oscillations 102
Receiver 80
Self- 137
Super-Heterodyne Receiver 145
Wave Meter 81

HIGH FREQUENCY, (71, 81)
Alternator 81
Amplification 81
Buzzer 81
Choke 35
Current 48, 81
Component of Plate 81
Oscillation 81
Resistance 81, 135

I

IMPEDANCE, (85) Page
Coil 85
Coupled Amplifier 86
Factor 86
Matched 86
Tuned 155

INDUCTANCE, (86)
Antenna 86
Coils 87
Distributed 87
Loading 87
Measurement of 87
Mutual 87
Parallel 88
Reactance 87
Receiving 87
Self 87
Series 88
Tapped 87
Units of 88
Variable 88

INDUCTANCE COIL
Basket Wound 21
Choke 35
Page
Definition 87
Duolateral 56
Honey-Comb 82
Lorenz 106
Spider Web 143
Tuning 155
Vario Coupler 44, 158
Variometer 158

INDUCTION, (88)
Bridge 88
Coil 88
Coil, Primary 89
Coil, Secondary 89
Density 89
Electromagnetic 89
Electrostatic 89
Instruments 89
Machine 89
Magnetic 89
Motor 89
Motor, Squirrel Cage 144
Mutual 89
Reactance 90
Regulator 90
Screen 90
Unit 90
Wattmeter 90

INDUCTIVE
Capacity 90
Circuit 90
Connection 90
Coupler 90
Coupling 90
Drop in Voltage 90
E. M. F. 90
Reactance 90
Rise 90
Resistance 90

INSULATING MATERIALS, (91)
Bakelite 20
Compound 91
Definition 91
Dielectric Constants 5
Ebonite 57, 159
Eburin 57
Electrose 63
Impregnated 86
List of 149
Mica, ... 113
Micabond Cloth 113
Micabond Paper 113
Micabond Plate 113
Micanite 113
Property 91
Table of Dielectric Strength 149
Vulcanite 159
Vulcanized Rubber 159

K

KEY, (96) Page
Anti-Capacity 96
Definition 96
High-Speed 96
Magnetic 109
Modulated Continuous Waves 42
Switch 97
Transmitting 154

M

MAGNET, (108) Page
Artificial 18
Compound 40
Definition 108
Electro- 61
Horseshoe 83
Natural 116
Negative Pole 116
North Pole 118
Permanent 123
South Pole 142
Temporary 151
Wire 108

MAGNETIC
Attraction and Repulsion 108
Blowout 108
Circuit 108
Field 66, 108
Flow 109
Flux 70, 109
Flux Density 109
Force 109
Force Due to Current 109
Hysteresis 109
Induction 109
Inductive Capacity 109
Interrupter 109
Key 109
Leakage 109
Needle 109
Poles 109
Properties 109
Storm 109

O

OSCILLATIONS
Back 20
Constant 120
Damped 49
Definition 120
Forced 70
Free 71
Frequency 120
High Frequency 81
Impact Excitation 85
Local 102
Logarithmic Decrement 105
Master Oscillator System 111
Oscillion 121
Oscillogram 121
Oscillograph 121
Point 120
Poulsen Arc 126
Resonator 135
Tesla Coil 151
Transformer 45, 120
Undamped 156
Valve 120

OSCILLATOR, (120)
Hertzian 120
Linear 120
Magnetic Blowout for 108
Master 111
Negatron 117

Page
  Righi 120
  Quartz 129
  Thermionic 120

P

PLATE, (125) Page
  Battery 125
  Circuit 125
  Component, High Frequency 125
  Consumption 42, 125
  Control 125
  Current 125
  Impedance 125
  Voltage 125

R

RADIATION, (130)
  Definition 130
  Efficiency 130
  Electromagnetic 62
  From Antenna 130
  Gliding Through 74
  Heaviside Layer 79
  Resistance 130, 135
  Theory of Propagation of Electromagnetic Waves 152
  Theory of Reception of Electromagnetic Waves 152

RADIO, (130)
  Activity 130
  Channel 130
  Communication 130
  Compass 130
  Control 130
  Frequency 72
  Telegraphy 130, 161
  Telephony 130
  Transmission 130

RADIO FREQUENCY, (72)
  Ammeter 14
  Amplifier 15
  Circuit 71
  Coils 130
  Current 130
  Resistance 135
  Selectivity 130
  Signals 130

REACTANCE, (131)
  Capacitative 30
  Coil 131
  Inductance 87

RECTIFIER, (131)
  Electrolytic 61
  Full Wave 131
  Half Wave 78
  Potential 126

RESISTANCE, (134)
  Antenna 16
  Box 134
  Contact 42
  Coupled Amplifier 134

Page
  Coupling 134
  Definition 134
  Field Regulator 66
  Graphite 75
  High Frequency 81, 135
  Litzendraht 102
  Of Ground Connection 135
  Ohm 118
  Ohmic Drop 119
  Ohmic Loss 119
  Ohm's Law 119
  Radiation 135
  Radio Frequency 135
  Variable 158

RESONANCE, (135)
  Curve 135
  Intensifies 135
  Parallel 123
  Series 137
  Transformer 135

S

SWITCH, (147) Page
  Aerial 9
  Board 147
  Capacity 31
  Dead End 50
  Double Throw 56
  Electromagnetic 62
  Gear 148
  Ground 77
  Jack 95
  Key 96
  Key, Anti-Capacity 96
  Knife 98
  Lightning 101
  Plug 125
  Points 42
  Quick Break 129

T

THEORY OF CURRENT FLOW, (151)
  Detector Action (of Vacuum Tube) 151
  Electric Current 49
  Magnetism 14
  Operation of Crystal Detector 46
  Operation of Vacuum Tubes 151
  Primary Cell 34
  Production of Alternating Current 12
  Propagation of Electromagnetic Waves 152
  Reception of Electromagnetic Waves 152
  Vacuum Tube Amplifier 157

TRANSFORMER, (153)
  Air Core 10
  Auto 20
  Closed Core 37
  Coupling 45, 153
  Hedgehog 79
  Intermediate 93
  Open Core 120
  Oscillation 45, 120
  Output 122
  Plug-In 125

Page
  Resonance 135
  Shielded 138
  Steel 153
  Tuned Radio Frequency 155

TRANSMISSION
  Aerial, Cage 8
  Automatic 19
  Broadcasting, General Treatise on Methods. 25
  Carrier Wave 31
  Chopper 31
  Fading 65
  Fan Aerial 65
  Feed-Voltage Modulation 65
  Ferro-Magnetic Modulator 66
  Flame Microphone 68
  Frequency Carrier 71
  Heising Modulation 74
  Key 96, 154
  Key, High Speed 96
  Jamming 95
  Jigger 95, 154
  Microphone 113
  Modulation 114
  Of Photographs by Radio 154
  Phenomena of Electric Wave Propagation 124
  Quartz Oscillator 129
  Queenland Gap Transmitter 129
  Radio 131
  Radio Telephony 131
  Radio Telegraphy 130
  Remote Control 133
  Spark Coil 142
  Spark Rate 142
  Speech Modulation 143
  Synchronous Discharger 148
  Telefunken System 149
  Television 150
  Tesla Coil 151
  Theory of Propagation of Electromagnetic Waves 152
  T. Y. K. Arc 156

TUNING, (155), See also Coil; Condenser
  Broad 155
  Coil 155
  Condenser, Aerial 9
  Inductance Coils 87
  Inductance, Variable 88
  Interference Eliminator 93
  Interference Preventers 93
  Rejector Circuit 133
  Selectivity 137
  Sharp 137
  Static Eliminators 144
  Syntony 148
  Wave Trap 160

U

UNITS, (156)
  Ampere 14
  Ampere-Hour 14
  Ampere, International 14
  Ampere Turns 14
  Ampere Volt 14
  B.A. Ampere 20
  Beg Ohm 23
  B. O. T. 24
  B. T. U. 27

Radio a Cristallo per Onde Corte

Un progetto di Leonardo Mureddu

Per coloro che amano l'ascolto di stazioni lontane e misteriose, le bande delle Onde Corte offrono senza dubbio una serie infinita di emozioni. Infatti i fenomeni della propagazione privilegiano proprio queste bande di frequenza, comprese tra i 5 e i 20MHz (con lunghezza d'onda compresa tra i 20 e i 60 metri), trasportandole a distanze intercontinentali grazie ad una serie di riflessioni che avvengono tra il suolo e la parte alta dell'atmosfera (ionosfera). Può quindi capitare di ricevere distintamente in Italia, magari solo per pochi minuti, trasmissioni provenienti dall'Australia, dalla Cina o dall'America. Le trasmissioni ad onde corte non vennero introdotte subito nella storia della radio, anzi per tutti gli anni '20 le grandi compagnie continuarono a scommettere sulle onde lunghe per le trasmissioni intercontinentali, e sulle onde medie per le trasmissioni a diffusione locale. Fu solo negli anni '30, con lo sviluppo delle grandi reti di comunicazione a scala planetaria che le onde corte furono scelte come veicolo privilegiato per le trasmissioni tra la madrepatria e le colonie o l'esercito in guerra, e per le comunicazioni tra nazioni alleate. I migliori ricevitori radio erano quindi dotati di numerose gamme d'onda in grado di sintonizzare e ricevere trasmissioni da tutto il mondo. Al giorno d'oggi le frequenze delle onde corte, sebbene ormai quasi del tutto dimenticate e spesso assenti nei sintonizzatori domestici, sono ancora molto frequentate e ricche di programmi in tutte le lingue.



La costruzione di un ricevitore a cristallo per le onde corte è un'impresa tutto sommato abbastanza facile e può dare grandi soddisfazioni, specie a chi si diletta nei cosiddetti "DX", ossia l'ascolto di trasmissioni provenienti da grandi distanze.

Schema di principio

Il progetto che presento qui è molto semplice e non ha grandi pretese, ma può servire come base di partenza per la sperimentazione di apparecchi più complicati ed efficienti. La tecnica usata è un po' diversa da quella usata per le onde medie, perché le frequenze più elevate richiedono alcuni accorgimenti costruttivi per minimizzare le perdite. Lo schema è molto simile a quello di qualunque ricevitore per onde medie. Ciò che cambia è l'induttanza della bobina e la tecnica costruttiva. Il ricevitore è costituito da un trasformatore d'ingresso con secondario accordato e presa intermedia per il rivelatore. Con i valori indicati (6 microhenry per l'induttanza e 250 pF per il condensatore variabile) si copre quasi tutta la gamma delle onde corte, da 5 a 15 MHz.



Note costruttive

Per ottenere risultati soddisfacenti occorre attenersi a poche regole, tra cui la più importante è quella di realizzare un montaggio compatto utilizzando filo rigido grosso per i collegamenti tra i vari componenti. Nel prototipo mostrato qua sopra è stato usato del filo di rame smaltato da 1mm di diametro per realizzare sia le bobine che i collegamenti. Il rame smaltato è da preferire al rame nudo o a quello stagnato, per via dell'*effetto pelle*. Infatti lo smalto preserva dall'ossido la superficie del filo su cui avviene la conduzione. Per lo stesso motivo non è consigliabile l'uso di filo rigido isolato in PVC. E' bene realizzare il montaggio su una basetta isolante, in modo da ridurre le perdite per effetto di prossimità. L'uso di un condensatore variabile ad aria è fortemente consigliabile, ma si possono ottenere risultati accettabili anche con un condensatore miniatura con dielettrico in poliestere (per radio a transistor). Sono da evitare assolutamente i vecchi condensatori con dielettrico solido (bakelite o altro), perché presentano troppe perdite alle alte frequenze. La bobina di sintonia è realizzata con 14 spire di filo da 1mm su un buon supporto da 4cm di diametro; le spire sono distanziate in modo da avere una lunghezza totale di circa 3cm. La presa per il rivelatore è realizzata alla quinta spira. La bobina d'antenna, avvolta sullo stesso supporto, è costituita da 6 spire dello stesso filo, anche queste leggermente distanziate. Sarà bene dotare il condensatore variabile di una manopola piuttosto grossa, dal momento che in onde corte la sintonia è sempre alquanto critica.

Collaudo

Collegata l'antenna (la stessa usata per le onde medie) e la terra, ruotate lentamente la manopola di sintonia: dovrebbe essere possibile captare con chiarezza alcune stazioni in varie lingue. La selettività dovrebbe essere sufficiente a separare trasmissioni vicine in frequenza. Noterete che qualunque stazione ricevuta è soggetta ad un affievolimento progressivo, fino a scomparire del tutto per poi riapparire o venire sostituita da un’altra stazione. Questo fenomeno si chiama “evanescenza” (in inglese “fading”), è tipico delle onde corte ed è dovuto alla propagazione delle onde ionosferiche, che sono soggette a fenomeni di interferenza.

Invito gli appassionati a proporre modifiche e miglioramenti, che accoglierò molto volentieri in queste pagine.

L.M.

Torna alla Pagina Principale

Crystal Set Mobile

By Al Klase – N3FRQ – December 2006

Back in the 1990’s there was a Yahoo Internet “club”, devoted to crystal radio development called “The Ferrite Core.” One of the perennial topics of conversation was the difference between operating a crystal set near high-power stations as opposed to a more rural setting. Someone, who had read Aesop’s Fables likened this to “The City Mouse and the Country Mouse.” The country mouse needed a sensitive radio hooked to a large antenna, but could faintly hear distant stations without a lot of interference. The city mouse’s crystal set could drive a loudspeaker using only the bed springs for an antenna, but he couldn’t hear much beyond the city limits.

I’ve spent most of my life as a country mouse, but recently I’ve been frequently finding myself in Jersey City. Indeed, crystal set operation is very different there. Short antennas work pretty well, and even my nearly-deaf rocket radio picks up multiple stations. It’s even possible to operate a properly designed set with the antenna terminal connected to ground with the headphone cord and listener serving as the actual antenna.

I decide to apply what I learned down town to a couple of radios I was building as Christmas presents. The circuit is very similar to the NJARC Pretty-Good Crystal Set, but the coil is wound on a ferrite toroid to save space, and there are additional antenna taps on the “high end” of the coil to better accommodate short antennas.

I recently found myself in Maywood, near Hackensack, with some time to kill while Peggy rehearsed before a Sunday-afternoon concert. I took the city mouse for a walk in a nearby park. With 20 feet of wire, 5 feet in the air, and the ground wire clipped to a metal park bench, I could comfortably choose from five or six stations. I could still hear the Jets game on WABC, with just the ground connected to the antenna terminal.



Still having some time to waste, I picked up a four-foot stick as I returned to the car. I grounded the set to the ignition key, and extended the antenna wire out the sunroof with the stick. Sure enough, the Jets were still ahead. I wound the rest of the wire around the stick as a loading coil.

The ugly stick

After an enjoyable concert (The Four Seasons and a Brandenburg Concerto w/harpsichord), I listened to the crystal set down the turnpike through the Meadow Lands, past all the towers, all the way home. I think most were on night-time power by now, as none were obnoxiously loud. I need to try that again, in broad daylight, with a speaker.


13
13
13
5
3
3
365 pF
68K
IF USING
CRYSTAL PHONE
COIL:
50 turns
#26 enamled wire
FT-82-61 torroid
Tapped at 3, 6, 11,
24, and 37 turns.
SkyWaves City Mouse
Crystal Radio
Al Klase - N3FRQ - 12/11/2006

all about
CRYSTAL SETS

by
Charles Green


ANT
A
C
D1
TAPS
L1
C2
S1
PHONES
B
C1
GND

How-To-Build Simple
Crystal Set Radios

621.3841
G795A
c.1

allabout books no. 101

all about
CRYSTAL SETS

by

Charles Green



How - To - Build Simple Crystal Set Radios

FIRST EDITION

All rights reserved, including the
right of reproduction in whole or
in part in any form.

Copyright © 1984 by Charles Green

Published by Allabout Books
P.O. Box 22366
San Diego, CA 92192-2366

ISBN 0-930003-00-4



PREFACE

In the beginning of this century, when radio was called "Wireless", most of the early experimenters used a crystal set to receive radio signals.



The crystal set is still the simplest type of radio receiver. A catwhisker (made from a thin wire) touching a sensitive spot on a piece of galena or silicon mineral crystal and a tuning coil, form the basic parts of this radio.



Radio signals from a nearby station are picked up via antenna and ground connections to the crystal set. The galena or silicon crystal detects the signals and the resultant audio is heard with headphones. No battery or electrical power is required.

This book tells you about crystal sets and shows you how to build them.

Charles Green

CONTENTS

1

THE CRYSTAL DETECTOR....................................4
- How-it-Works, 4
- Detection of Radio Waves, 6
- Tuning the Crystal Set, 7
- Capacitor, 8
- RF Coil, 8
- Tuned Circuit, 9
- Antenna and Ground, 10
- Headphones, 11

2

SIMPLE RECEIVER PROJECTS..............................12
- Simple Crystal Set, 12
- Slider Tuned Crystal Set, 17
- Ferrite Coil Crystal Set, 23
- Spiderweb Coil Crystal Set, 27

3

ADVANCED RECEIVER PROJECTS............................32
- Dual-Tuned Crystal Set, 32
- Selective Crystal Set, 37
- Carborundum Crystal Set, 43

4

COMPONENT PROJECTS....................................48
- Book Tuning Capacitor, 48
- Rotary Switch, 53

5

WORKSHOP..54
- Soldering, 54
- Project Construction Tips, 55
- Mounting Minerals, 56

INDEX...57

1

THE CRYSTAL DETECTOR

A crystal detector of radio waves can be either a traditional catwhisker and natural mineral crystal, or a modern semiconductor diode.



SEMICONDUCTOR DIODE



CATWHISKER DETECTOR

Certain natural minerals such as galena (lead sulphide) and silicon have electrically sensitive surface spots. In the beginning of this century, experimenters discovered that electrical current would flow into the sensitive spot on a mineral crystal from a catwhisker, but would not pass readily (high resistance) from the crystal to the catwhisker. This unique feature was used to detect (rectify) radio waves and extract the audio modulation.

HOW-IT-WORKS

There are two general types of crystal detctors;

- . Point contact diode
- . Junction diode

Both types use semiconductor material such as silicon, germanium, or galena. The basic semiconductor junction diode is made of two portions of the material "doped" in manufacturing by adding controlled amounts of chemicals. The doped portions have opposite electrical properties:

"P" TYPE, with an excess of positive electrical charges (holes).

"N" TYPE, with an excess of negative electrical charges (electrons).

Junction Diode



The boundary between the two doped portions is called a PN junction. The area on both sides of the PN junction is called the space charge region. When a positive voltage is applied to the "P" material (and negative voltage to the "N" material), the space charge region becomes narrow and electron current flows through the PN junction.



FORWARD BIAS



REVERSE BIAS

When the voltage polarities are reversed, negative to "P" and positive to "N", the space charge region widens (increasing the effective resistance of the PN junction) and the electron flow is very small (back current). If an ac voltage is applied to the PN junction, it will act as a rectifier (or radio wave detector).

Point Contact Diode

The point contact diode uses a "catwhisker" of thin wire contacting the surface of doped "N" semiconductor material. The pointed end of the wire produces a high intensity electric field in the area of the semiconductor surrounding the wire. When an electric current flows from the wire to the semiconductor material, a small region of "P" material forms around the area of the point contact. Thus a PN junction is formed which operates in the same way as the junction diode.



The sensitive spots of galena and silicon crystals used in traditional catwhisker detectors have naturally doped areas of semiconductor material, and operate in the same way as the point contact detector.

DETECTION OF RADIO WAVES

At the transmitting radio station, a microphone converts sound waves into electrical audio signals. The audio signals then modulate the transmitted radio waves.





MODULATED RADIO WAVES ⟶

the crystal detector

The transmitted radio waves are intercepted by the receiving antenna and small rf currents are induced in the antenna wire. The rf currents (high frequency ac) flow through the detector to ground. As previously explained, the crystal detector will pass current in only one direction, therefore, pulsating dc voltages (detected audio signals) are developed by the crystal equivalent to the audio modulation of the transmitted radio waves.



The detected audio signals flow through the headphone coils and affect the intensity of a magnetic field. This causes the steel discs of the headphones to vibrate and produce audible sound waves.

TUNING THE CRYSTAL SET

The antenna intercepts all radio waves in the area, and the signals will be heard jumbled up in the earphones. A nearby radio station may be received with the other stations heard in the background.



In order to receive a radio station properly, the crystal set must be tuned to the frequency of the transmitter. A tuned circuit composed of an rf coil (inductance) and a capacitor, is connected between the antenna/ground circuit and the detector.

Capacitor

The modern capacitor is evolved from the old Leyden jar. It consists of two or more metal sections separated by a dielectric (air, paper, or plastic). The capacitor stores energy in the form of an electrostatic charge in its dielectric. A variable capacitor (used in a tuned circuit) has movable metal sections that adjust the amount of capacity.





A capacitor will allow pulsating dc current or ac current to flow through it, but will block steady dc current. A capacitor has an oppositon or "reactance" to ac that varies with frequency. The higher the frequency, the lower the reactance of a given value of capacity. Capacity is measured in micro-farads (uF) or micro-micro-farads (picofarads) (uuF or pF).

RF Coil

An rf coil is made of insulated copper wire wound on a plastic or cardboard tube. When electric current flows through the coil, a magnetic field is created. This magnetic field resists any change in electric current flow. This opposition or "reactance" to ac varies with frequency. The higher the frequency, the higher the reactance of a given value of rf coil inductance. Inductance is measured in millihenrys (mH) and microhenrys (uH).





Tuned Circuit

A tuned circuit is composed of a capacitor and an rf coil. As previously described, the reactances of a capacitor and an rf coil change with frequency (but in opposite ways). At a particular frequency, the two reactances will cancel each other out. This condition is called "resonance". The impedance of a parallel tuned circuit is at its highest at resonance. Radio signals at the resonant frequency will be greatly magnified, while signals at other frequencies will be shunted to ground (rejected).





The resonant frequency of a tuned circuit can be changed by adjusting the capacitance (using a variable capacitor), or by varying the inductance (using a slider or taps on the rf coil). A ferrite core can also be used to change the inductance of a coil. The selectivity of a tuned circuit is dependent upon the quality (Q) of the components and the inductance /capacity ratio (L/C ratio). A high-Q tuned circuit is more selective than a low-Q circuit. A tuned circuit with a high L/C ratio (large inductance and small capacity) is more selective than a low L/C ratio circuit.



ANTENNA AND GROUND

A simple crystal set depends upon the strength of the radio waves received by the antenna to produce audio in the earphones. If you live in a strong signal area (a nearby radio transmitter), a crystal set can produce loud audio in earphones with only an inside antenna. But in lower signal areas, a good outside antenna with a ground connection is required.



If you are fortunate enough to be able to put up an outside antenna, the basic rule of thumb is the higher, the better reception. Check your local electronics store for an antenna kit. You can construct an antenna using a glass or plastic insulator at each end of a length of copper wire (insulated or bare). Make the antenna as long as possible. It does not have to be in a straight line to work.

CAUTION

ANTENNA INSTALLATION
NEAR ELECTRICAL POWER
LINES IS DANGEROUS.

Make sure that your antenna is far enough away from any power line, so that it will not touch a wire if it falls.

Connect a length of insulated wire between the end of the antenna and your crystal set antenna terminal. This antenna lead-in wire can be fed into your house through a window.

If you can not erect an outside antenna, run a length of insulated wire as long and high as possible through your house or apartment. It will work, but not as well as an outside antenna because of the shielding affect of the house walls.

Connect a ground lead to a cold water pipe. Make sure that it is a metal pipe. Or, you can buy a ground rod from your local electrical supply store and drive it into the ground near your house. Then connect your crystal set ground lead to the rod. For safety install a lightening arrestor between the antenna lead and ground (see the instructions with the device).

HEADPHONES

Headphones (also called earphones, or headset) are required to hear the received audio from a crystal set. The standard headphones are made with dual coils of fine wire connected in series in each phone. Horseshoe magnets are built into each phone case to provide a magnetic field. A disk of thin sheet iron (diaphragm) is mounted near the top of the coils. The phones are connected in series with a set of flexible leads terminated in metal "phone tips".



Detected audio signals flow through the coils and affect the intensity of the magnetic field from the horseshoe magnet. This changes the magnetic attraction of the diaphragm, and causes it to vibrate and produce audible sounds.

The total resistance of the series headphone coils is used as a measure of audio sensitivity. A resistance of 2000 ohms is sufficient. More sensitive headphones have a resistance of over 5000 ohms and are used to hear very weak signals.

The 2000 ohm headphones can be obtained at electronic parts mail order houses.

2

SIMPLE RECEIVER PROJECTS

SIMPLE CRYSTAL SET

Look at the schematic diagram. The crystal set uses a tunable ferrite coil L1, and a crystal diode D1. This type of tuning coil is called a "loopstick". The ferrite core is screwed into the coil form and increases the inductance of L1, thus tuning the receiver to a lower frequency.



CONSTRUCTION

As shown in the illustration, the crystal set components are mounted on a 5 1/2-inch by 2 1/2-inch by 3/4-inch wood base. Layout and install the crystal set parts in the locations shown. The loopstick L1, is mounted with a metal strip supplied with it. Push the snap-in end of L1 into the large hole of the metal strip. Then bend 1/2-inch of the other end of the strip to form a bracket and mount it on the base with a wood screw. If the metal strip is not available, make one out of sheet metal approximately 2-inches long by 1/2-inch wide. Then drill a hole to fit L1 at one end, and a small hole to fit a wood screw at the other end.

Mount the four fahnestock clips and solder lugs with wood screws in the locations shown in the illustration.

WIRING

Use hookup wire to connect the crystal set components as shown in the schematic and illustration. The loopstick L1 may have three terminals. One of the terminals is a tap, which is not used in this circuit. Make sure that you connect only to the terminals at the start and end of the loopstick coil.


ANT
DI
LI
PHONES
GND

SIMPLE CRYSTAL SET


LI
DI
GND
PH
ANT

List of Materials

D1 - Germanium diode
(1N34A or equiv.)
L1 - Loopstick
(see text)
4 - Fahnestock clips
BASE - 5 1/2 X 2 1/2 X
3/4-inch wood section
PHONES - 2000-ohm headphones
MISC. - Solder lugs, wood screws,
knob and bracket to fit L1,
hook-up wire.

Install a small knob on the end of the L1 adjustment screw. Make sure that the screw turns freely with the knob. Position the 1N34A diode as shown before soldering the leads.

Experiment 1

Connect the antenna, ground, and 2000-ohm headphones to the crystal set terminals. Rotate the L1 knob counter-clockwise as far as it will go. Do not turn past this point, or you may break the ferrite rod inside the coil form. The ferrite is now outside of the coil winding. This is the highest frequency point of the tuning range of L1.

Slowly turn the L1 knob clockwise and listen for received radio stations. When the L1 knob is turned fully clockwise, the ferrite will be completly inside the coil (increasing the inductance) and it will be at the lowest frequency point of the tuning range.

Experiment 2

Connect capacitors, with values from 50 mmf to 300 mmf, in parallel with L1. Then tune L1 and note how the frequency range has changed.

AMPLIFIER CONNECTION

The simple Crystal Set (and the other receiver projects) can be connected to an amplifier in place of earphones. This amplifier can be a single channel input of your home stereo.

Parts values are not critical; C1 is approximately .005 mfd, and the volume control R1 can be any value from 1000 ohms to 10,000 ohms. Use shielded wire between R1 and the amplifier input jack.


TO
CRYSTAL
SET
C1
R1
TO AMPLIFIER
GND

Amplifier Connection

Schematic Symbols


RESISTOR
POTENTIOMETER
CAPACITOR
VARIABLE CAPACITOR
CRYSTAL DIODE
RF COIL
FERRITE RF COIL
HEADSET
ANTENNA
GROUND
+
BATTERY
SWITCH

List of Materials

D1 - Germanium diode, type 1N34A, 1N60, 1N82A, or equiv.
L1 - Slider-tuned coil (see text)
4 - Fahnestock clips (terminals)
BASE - 6 x 3 x 1/2-inch section of wood (see text)
PHONES - 2000 ohms headphones
MISC. - Coil form (see text), No. 24 enameled copper wire, 3/32 inch dia. brass rod, brass ball slider (see text), solder lugs, two small brackets, hook-up wire, wood screws, machine screws and nuts.


ANT
JI
B
DI
J3
C
LI
PHONES
A
J4
J2
GND


L1
A
D1
B
JI
J3
C
ANT
J2
J4
GROUND
PHONES

SLIDER TUNED CRYSTAL SET

SLIDER TUNED CRYSTAL SET

In the early days of radio, slider tuned coils were used in crystal sets. This method of tuning the inductance uses an adjustable metal contact (slider) that moves over the coil. The slider makes contact with individual coil wires to tune in the radio stations.



The enamel insulation of the coil wires in the slider path is removed for good electrical contact.

You can experiment with a slider tuned coil by building this crystal set. As shown in the illustration, the coil is mounted upright on a 6-inch by 3 1/2-inch by 1/2-inch wood base. A semiconductor diode is used for a detector.

TUNING COIL CONSTRUCTION

Look at the drawing of the tuning coil L1 construction details on the next page. The tuning coil is wound on a cardboard or plastic mailing tube section, 2 5/8-inches in diameter and 5-inches long. Make sure that you select a rigid, thick-walled tube for a coil form. The tube used in our model has a 3/16-inch wall. The coil form must be rigid to hold the slider ball and rod assembly.



Before winding the coil, drill all the holes in the form as shown in the drawing, and then install the solder lugs. Position the solder lug ends toward the coil form edges.



The coil is wound with No. 24 enameled copper wire. Remove the enamel from the wire end with sandpaper and then solder the wire to the lug. Start winding the coil, keeping the turns as tight and close together as possible. Wind the wire to the front of the bottom solder lug B. Remove the enamel and solder the wire end to the lug.

A brass ball approximately 3/8-inches in diameter is used as the moving contact slider. This brass ball can be found at your local electrical supply store. It is a type of ball that is used as a top nut for small table lamps. Drill a hole through the ball so that it will slide over a length of 3/32-inch diameter brass rod. Bend the brass rod at each end (after placing the ball in the center of the rod), to fit through the holes in the coil form as shown in the drawing. Cut the rod 1-inch down from the bend at each end.



Insert the brass rod with the slider ball into the coil form holes. Then place a small washer and spring on one end of the rod (inside the coil form). Solder a nut on the end of the rod to hold the spring in place. Do the same to the other end of the rod. After soldering, slide the ball over the wires and check that it slides smoothly. Use sandpaper to remove the enamel insulation of the wires in the path of the ball slider. Connect a wire between the soldered nut on the bottom end of the brass rod and the solder lug near the rod.

BASEBOARD

All of the crystal set components are mounted on a wood baseboard as shown in the drawings. Cut the baseboard to size; a 6-inch by 3 1/2-inch section of 1/2-inch thick wood (maple is used in our model). Sand the edges after cutting. It is not necessary to paint or stain the baseboard.

Mount the four terminals and solder lugs as shown in the drawing. Label the four terminals with either rub-on lettering or cemented paper tags. Install two brackets on opposite sides of the bottom of the coil, and mount it on the baseboard with the lugs toward the terminals.

WIRING

Bare No.22 wire was used to wire our model, but any kind of hookup wire can be used. Connect the wires between the solder lugs as shown in the drawing, except do not connect the antenna terminal lug wire to the coil terminal at this time. Connect the crystal diode between the solder lugs as shown.

Experiment 1

This experiment will show how an untuned crystal detector functions.



Connect the untuned detector circuit as shown in the drawing, and then hook-up your antenna and ground leads. Connect 2000-ohm headphones to the circuit and listen to the detected radio waves.

You will probably hear a strong local radio station, with other, weaker radio station transmissions all jumbled together.

Experiment 2

Reconnect the baseboard wires to the circuit of the Slider-Tuned Crystal Set as shown in the drawing. Listen to the detected radio waves as you tune the coil by sliding the brass ball over the sanded wire path. You should be able to receive the radio stations much better than the untuned detector circuit of Experiment 1.

LOADING COIL



An additional slider tuned coil, L1, can be used as a Loading Coil to increase the electrical length of your antenna. This may allow better reception of the lower broadcast band frequencies. Connect L1 in series with the antenna lead to the receiver, and tune it for best reception.

WAVE TRAP



L1 can also be used in a Wave Trap circuit to tune out a strong local signal, and allow easier tuning of weaker stations. C1 is a 365 mmf variable capacitor connected in parallel with L1. Adjust L1 and C1 so that the interfering station is at minimum.


D1
L1
SEC
PRI
TAP
PHONES
GND
ANT
C1

FERRITE COIL CRYSTAL SET


L1
D1
ANT
TAP
C1
PHONES
GND

List of Materials

C1 - 365 mmf variable capacitor.
D1 - Germanium diode (1N34A or equiv.).
L1 - Ferrite coil (see text).
4 - Fahnestock clips.
2 - wood sections; 6 X 1/2-inch square (see text).
BASE - 8 1/2 X 6-inch sheet plastic (see text).
PHONES - 2000-ohm headphones
MISC. - plastic tube section for L1 primary winding (see text), solder lugs, machine screws and nuts, wood screws, bracket for C1 (see text), knob for C1, hookup wire.

FERRITE COIL CRYSTAL SET

This crystal set has a large ferrite core coil L1 of a type that is normally used for a built-in antenna in portable radios. This type of coil has a very high "Q" and may be more selective than an air-core coil. As you can see in the schematic, a primary coil is wound around the ferrite coil. The original winding is used as the secondary.



The primary coil (connected to the antenna and ground) can be moved close to, or away from, the secondary (original winding connected to D1). This variable coupling is used to control the selectivity of the crystal set.

PRIMARY COIL

The primary coil is wound on a 1-inch section of plastic tube that can fit loosely over the ferrite rod. A 1/2-inch diameter plastic tube is used on the receiver shown in the illustration. Wind 12-turns of hookup wire evenly over the tube and twist the ends together to prevent movement. Leave 4-inch leads from the primary coil winding. Slide the primary coil over the center of L1.

BASEBOARD

The crystal set components are mounted on a 8 1/2-inch by 6-inch section of sheet plastic. The thickness of the plastic is not critical, but it must be rigid enough to hold the parts without bending. A 6-inch long 1/2-inch square wood section is installed under each end of the baseboard. A section of wood can be used for the baseboard with wood screws to mount the parts, in place of machine screws and nuts.

The model shown uses a plastic variable tuning capacitor, but an air type capacitor can be used for C1 instead. Make a metal bracket approximately 1-inch wide by 1 1/4-inch high and a 1/2-inch right angle mounting foot from sheet aluminum. Drill a hole in the top of the bracket to fit C1 and two holes in the mounting foot to fit small machine screws. Locate the components on the baseboard as shown in the illustration and then drill mounting holes. If you have a cardboard or plastic mounting supplied with ferrite coil L1, you can mount it on the baseboard. If not, L1 can be taped loosely on top of the baseboard. Th ferrite coil L1 in our crystal set was obtained from an old radio. Install the components on the board with solder lugs, machine screws, and nuts.

WIRING

Connect the parts with hookup wire as shown in the illustration. Use the schematic diagram as a guide. Make sure that the ground lead from L1 secondary passes inside the primary coil. Also check that the primary coil slides freely over the L1 winding. Install a knob on the C1 shaft, and mark the terminal designations on the baseboard.

Experiment 1

Hookup the antenna, ground and 2000-ohm headphones to the crystal set terminals. Slide the primary coil over the center of the L1 winding. Tune C1 for radio stations. Then slide the primary coil towards the ground end of L1 while tuning C1. Note the difference in selectivity.

Experiment 2

Change the number of turns of the primary winding and repeat Experiment 1.

Operating Tips

After operating a crystal set for some time, you may notice a difference between day, evening, and night reception of radio stations. This is due to the two ways that radio signals travel between the transmitting antenna and a receiving antenna.

(a) The ground wave; which moves along the surface of the earth.
(b) The sky wave; which travels upward and is reflected by the ionosphere.

The reception of broadcast stations is dependent upon the time of day. During daylight hours, stations are received primarily by ground wave transmission. At night, the broadcast stations will be received via sky wave transmission. Also, some radio stations change to a lower power at night. Reception in the evening may be more difficult as the fading ground wave is interfered with by reflected waves. But later, it may be possible to hear far-away stations transmitted by sky wave.

Your geographical location to radio stations is very important for reception, as a crystal set receiver does not amplifiy signals. It is entirely dependent upon the strength of the radio waves. If you are in a deep valley surrounded by high mountains, reception will be difficult. If you live in a flat plain, with no obstacles to radio transmission, reception may be very good.

An outside antenna is necessary for for best reception. If possible, try erecting an extra antenna at a right angle to the original one, and switch it in to provide a directional effect for increased signal strength. Keeping a log of received stations for a week may be helpful in determining the radio reception conditions in your area.


ANT
D1
L1
taps
C1
PHONES
GND

List of Materials

C1 - 365 mmf variable capacitor.
D1 - Catwhisker crystal detector
    (or 1N34A or equiv. diode).
L1 - Spiderweb coil (see text).
4 - Fahnestock clips.
2 - small alligator clips
BASE - 8 X 6 X 1/2-inch section
    of wood (see text).
MTG. POST - 5 x 3/4 x 3/8-inch
    wood section (see text).
PHONES - 2000 ohms headphones.
MISC. - Coil form (see text),
No. 22 enameled copper wire,
solder lugs, hook-up wire,
wood screws, machine screws,
and nuts.


L1
TAPS
ANT
D1
C1
GND
PHONES

SPIDERWEB COIL CRYSTAL SET

SPIDERWEB COIL CRYSTAL SET

The spiderweb coil is a tuning coil that is wound on a flat wheel form that has an uneven amount of spokes. This type of coil was also used as a loop antenna in early radios.



Our receiver uses a tapped spiderweb coil that is tuned by a variable capacitor. As shown in the illustration, the spiderweb coil is mounted at the rear of a 8-inch by 6-inch by 3/4-inch wood base. A catwhisker crystal detector and a variable capacitor are mounted near the front of the wood base.

SPIDERWEB

The spiderweb coil is wound on a 6-inch diameter flat form that has nine vanes. Make a tracing of the spiderweb coil form template on the next page. Then use carbon paper to transfer the tracing to a section of 1/8-inch fibreboard or sheet plastic. Cut the coil form out with a jeweler's saw, and drill a center hole to fit a small wood screw.



Spiderweb Coil Form Template

Wind the coil with No. 22 enameled copper wire, starting from the center and winding outward. Leave about 5-inches of the starting end of the wire free. It will be used as a connecting lead. Feed the wire behind a vane and over the front of the next vane as you wind. Wind the wire closely and evenly on the form. It is not necessary to count the turns. Wind the wire to about 1/4-inch from the end of a form vane. Then drill a small hole near the vane end, and bend a solder lug through it. Solder the wire end to the lug.

On one of the vanes, count down five wires and then carefully lift it outward. Remove about 1/4-inch of the enamel with a section of sandpaper and then bend the end of a solder lug aound the bared wire. Solder the lug to the wire, then cut off remaining portion of the lug (away from the bentover end). Repeat this every five turns until you have a total of six lug taps on the coil. Stagger the lugs away from each other to keep them from shorting.

BASEBOARD

As shown in the illustration, the Spiderweb Coil Crystal Set parts are mounted on a wood baseboard. Cut the 8-inch by 6-inch baseboard from a section of 1/2-inch thick wood. White pine was used in our model. Sand the surface of the wood after cutting.

Make the spiderweb coil mounting post by cutting out a 5-inch by 3/4-inch by 3/8-inch wood section. Then cut a notch in the center of the rear of the baseboard to fit the wood section. Install the wood section in the notch with small wood screws.

Mount the parts on the baseboard as shown in the illustration with small wood screws. If the mounting holes of the tuning capacitor C1 are on the bottom, drill matching holes in the baseboard and use flathead machine screws to hold the capacitor.

Install solder lugs with the four terminals, and mount the spiderweb coil to the mounting post with a wood screw through a center hole in the coil form. The coil should be positioned with the lugs facing forward (on the left side of the coil form).

WIRING

Connect the crystal set components with hookup wire as shown in the illustration. Use 6-inch lengths of insulated stranded wire to the two small alligator clips.

Experiment 1

Connect antenna, ground, and 2000-ohm headphones to the crystal set. Then connect the D1 alligater clip lead to the antenna terminal. Set the tuning capacitor C1 to minimum capacity (rotor blades all the way out). Connect the antenna clip lead to the tap on L1 near the center of the form.

Adjust the crystal detector D1 catwhisker to a sensitive spot and tune C1 for a radio station. It may be easier to tune for stations if you temporarily connect a crystal diode (1N34A or equiv.) in place of the catwhisker crystal detector.

After a station is heard, you can disconnect the diode and probe for a sensistive spot on the crystal with the catwhisker. Change the antenna clip lead to other L1 taps and continue tuning C1 for radio stations.

Experiment 2

Disconnect the D1 clip lead and reconnect it to a tap on L1 close to the center of the coil. This will load L1 more lightly than if the detector was connected to the top of the coil. Repeat the tuning procedure of Experiment 1 and note the difference in selectivity and volume of the received radio stations. Then tune in a radio station and move the D1 clip lead to other taps on L1. There will be a particular tap point for optimum selectivity and volume for each received station.

STATION LOG

DATE	TIME	DIAL	STATION	NOTES

3 ADVANCED RECEIVER PROJECTS

DUAL TUNED CRYSTAL SET



This crystal set circuit uses two variable capacitors C1 and C2. As you can see in the schematic drawing, C1 tunes the ground circuit, and C2 tunes a tapped coil L1. The taps of L1 are connected via the rotary switch S1.

TUNING COIL

Look at the drawing of the coil form construction details on page 34. The tuning coil L1 is wound on a section of 1/8-inch wall plastic tube, 2-inches in diameter, and approximately 4-inches long.

Drill holes in the form and install three solder lugs with machine screws and nuts. Position the solder lug ends towards the coil form ends as shown.


ANT
A
C
D1
TAPS
L1
S1
PHONES
C2
B
C1
GND
S1
TAPS
D1
PHONES
L1
B
A
ANT
C2
GND
C1

DUAL TUNED CRYSTAL SET

List of Materials

C1,C2 - 365 mmf variable capacitors.
D1 - Germanium diode (1N34A or equiv.).
L1 - Tuning coil (see text).
S1 - 1-pole, 10-position rotary switch (see text).
4 - Fahnestock clips.
1 - Small alligator clip.
BASEBOARD - 5 x 8 x 3/8-inch wood section (see text).
PHONES - 2000-ohm headphones.
MISC. - Coil form (see text), No. 24 enameled copper wire, solder lugs, hook-up wire, wood screws and nuts, knobs, bracket for S1.

The coil L1 is wound with No. 24 enameled copper wire, and is tapped every five turns for a total winding of 75 turns.

Drill a small hole in the coil form approximately 1 1/4-inch from the "A" lug. Remove the enamel from the end of the No. 24 wire and then feed the wire end through the hole. Solder the wire to lug "A".





Wind five closely spaced tight turns around the coil form. Then bend back and twist together 1/2-inch of the wire to make a tap. Position the tap outward and then continue winding the coil, keeping the turns as tight and close together as possible. Make a tap every five turns and then drill a small hole in the coil form after the 75th turn. Feed the wire through the hole, remove enamel, and solder the end to lug "B".

BASEBOARD

The Dual-Tuned Crystal Set is built on a wood baseboard as shown in the illustration. Cut the 5-inch by 8-inch baseboard from a section of 1/4-inch thick plywood. Sand the edges and surface of the baseboard to remove any splinters. Drill holes in the baseboard and install the parts with small machine screws and nuts in the locations shown in the illustration. Drill mounting holes at each end of the tuning coil L1 and position it on the rear of the baseboard with the coil taps toward the front. The illustration shows a commercial rotary switch, but a wooden rotary switch can be used for S1 instead. (See page 53 for construction details.)

Install the four fahnestock clips (used as antenna, ground and headphone terminals) with solder lugs. Mount an additional solder lug on the baseboard midway between S1 and L1.

WIRING

Connect the crystal set parts with hookup wire as shown in the pictorial illustration and the schematic diagram. Use the center solder lug as a junction point for leads from C1, C2 and S1 as shown in the illustration. Connect the leads from S1 to the taps on L1 in numerical sequence; every 5 turns for 7 taps. Then connect the last three leads every 10 taps. Insert the lead ends into the taps and hold them with a drop of solder. This will make it easier to move leads to other L1 taps. Use a 5-inch length of stranded hookup wire for the alligator clip lead connected to D1 at solder lug C.

Experiment 1

Connect 2000-ohm headphones, antenna and ground leads, to the crystal set terminals. Then connect the D1 clip lead to the L1 "A" solder lug.

Set S1 to each tap position in turn and tune C1 and C2 for received radio stations. If all of the local stations can not be heard, experiment with different connections to the L1 taps. More turns may have to be added to L1 (with additional five-turn taps) to receive stations at the lower frequency end of the broadcast band.

Experiment 2

Remove the D1 clip lead from "A" and then connect it to the "B" solder lug on L1. Repeat the tuning method of Experiment 1 and note if the crystal set is more selective. This is possible, because L1 is now connected as an rf transformer. You can also connect the D1 clip lead to each of the S1 taps and note if there has been any improvement in reception.


F
B1
E
A
D
G
C
B
ANT
CI
A
C2
GND
DI
PHONES
B
ANT
CI
GND
C2
I
J
LI
L2
DI
PHONES
I
H

SELECTIVE CRYSTAL SET


ANT
DI
LI
L2
C2
PHONES
CI
GND

SELECTIVE CRYSTAL SET

This receiver uses two spiderweb coils in a two-circuit tuner for good selectivity and sensitivity. As you can see in the schematic diagram, the antenna-ground rf input circuit is tuned by L1-C1 for maximum signal gain. L1 acts as the primary winding of an rf transformer, with L2-C2 as the tuned secondary. Coupling between L1 and L2 is variable for best selectivity. L2 is connected to a catwhisker crystal detector and the audio signals are fed through the phone jack to 2000-ohm headphones.

As shown in the illustration, the crystal set parts are mounted on the rear of a black plastic panel. This type of layout is similar to the type of construction of the old-time crystal sets.



SPIDERWEBS

Both L1 and L2 spiderweb coils are made exactly the same way. L1 and L2 are wound on 17-vane coil forms 3 5/8-inches in diameter. The coil forms in our receiver are made from 1/16-inch sheet plastic of the same type used for printed circuit boards (but without the copper foil). Any kind of rigid sheet plastic should be suitable for the coil forms.

Make a tracing of the spiderweb coil template. Then use carbon paper to transfer the tracing on a section of 1/16-inch thick sheet plastic. Cut out the vanes with a jeweler's saw. Drill two holes as shown, and install the two solder lugs.



COIL FORM TEMPLATE FOR L1–L2

Wind as much No.22 enameled wire as possible on each coil form. Solder the wire to a solder lug before winding a coil. Then wind the wire over a vane and under the next vane. Wind the wire closely and evenly on the form. It is not necessary to count the turns. Solder the wire end to the remaining solder lug

CONSTRUCTION

The panel used in our receiver is a 7 3/4-inch by 4 1/2-inch section of 1/4-inch thick black acrylic plastic. The size is not critical, but it should be large enough to mount all of the parts as shown in the illustration.

Layout and drill the mounting holes of the components on the panel. Make sure that C1 and C2 are positioned so that the edges of the tuning knob dials are more than 1/2-inch apart. Install the catwhisker crystal detector assembly, antenna and ground terminals, and the phone jack in the locations shown.



As you can see in the illustration, L1 is installed on the end of a variable coupling metal rod. This 1/4-inch diameter rod is 3-inches long with a flat side. Drill and tap a small hole close to the end of the rod. The rod used in our model came from a discarded volume control. Cut a 2-inch long by 1/2-inch wide by 3/8-inch thick wood section and drill holes to fit the rod, two mounting screws, and a hole for the rod set screw. Locate and mount the wood section in the center of a spiderweb coil L1 so that the rod will be 3/4-inch down from the edge of the top vane.

Hold L1 behind the panel and using the free end of the rod, locate the panel hole. Position L1 midway between C1 and C2, and make sure that the top edge of the coil is below the top of the panel. Drill a hole to fit the rod bushing in the panel hole location. The panel bushing in our model was removed from a discarded volume control.

Drill a hole to fit the bushing in one end of a 2-inch by 1/2-inch section of sheet aluminum. Bend the other end of the section to fit against the flat side of the rod. Install the metal section and the bushing in the panel hole.

Insert the rod into the bushing and make sure that the metal section end fits close to the flat side to prevent rotation of the rod. Install a knob on the rod end and make sure that the rod can be pushed in and out easily. If necessary, put a small amount of grease on the flat side of the rod.

Install the remaining spiderweb coil L2 on a wood section that is mounted on the rear of the panel with two spacers. The spacers should be long enough for L2 to be located 1/4-inch behind L1 with the rod pushed all the way in. The 5 1/2-inch by 1-inch by 1/4-inch wood section in our model is supported with screws installed through 1 1/2-inch metal spacers into tapped holes in the rear of C1 and C2. The screws and bushings can be made longer and mount into panel holes in your receiver.

Install a wood section on the bottom rear of the panel to keep the receiver upright. A 5-inch by 3-inch section of 1/4-inch thick wood is used in our receiver.

SET WIRING

Connect the receiver components with hookup wire as shown in the illustration and schematic diagram. Use flexible stranded wire for connections to L1. Make sure that the L1 leads do not touch any component as the variable coupling rod is moved in and out.

Install knobs on C1, C2, and the variable coupling rod. Then place the crystal in the detector assembly.

OPERATION

Connect antenna and ground leads to the receiver terminals. Plug in a set of 2000-ohm headphones into the panel phone jack. For easier initial operation of the receiver, temporarily connect a germanium diode (1N34A or equivalent) across the D1 connecting lugs. Make sure that the catwhisker is not touching the crystal at this time.

Push the variable coupling rod half way in and tune C1 and C2 for a station. Adjust the variable coupling rod and retune C1-C2 for best reception. Check operation over the entire broadcast band. It may be necessary to add or subtract turns of wire on L1-L2 for complete coverage. After checking operation with the germanium diode, remove it and try using the catwhisker crystal detector.

List of Materials

C1,C2 - 365 mmf variable capacitor.
D1 - Catwhisker crystal detector assembly.
L1,L2 - Spiderweb coils (see text).
2 - Terminals.
1 - Phone jack.
PHONES - 2000-ohm headphones.
MISC.- Plastic sheet for spiderweb coils, solder lugs, machine screws and nuts, wood screws, hookup wire.
CONSTRUCTION MATERIALS (See Text).
A - knob
B - Panel
B1- Bushing
C - Aluminum section
D - Rod
E - Wood section
F - Setscrew
G - L1 coil form
H - Wood section
I - Spacers (2)
J - Wood section


X
C1A
D1
J3
ANT
J1
L1
R1
(−)
C1B
C2
Y
C3
BAT
(+)
J4
9 TAPS
GND
J2
J5
C4
PHONES
J6
Y
X
L1
TAPS
J2
D1
J1
C4
J6
C2
C3
J5
C1
A-B
J4
R1
J3

List of Materials for Carborundum Crystal Set

C1A-C1B - Dual 365 mmf variable capacitor.
C2 - 365 mmf variable capacitor.
C3 - 0.1 mf capacitor.
C4 - 1000 mmf capacitor.
D1 - Carborundum crystal and catwhisker detector assembly (see text).
J1 to J6 - Fahnestock clips.
L1 - Tuning coil (see text).
R1 - 5,000-ohm potentiometer (linear taper).
BAT - 6-volt battery
PHONES - 2000-ohm headphones.
MISC. Coil form (see text), No.24 enameled copper wire, 1/2-inch long spacers, perfboard strip (see text), push-in clips, solder lugs, knobs, hook-up wire, 1N34A diode (or equiv.), wood for base and D1 detector assembly (see text), wood screws, machine screws and nuts, alligator clips **X-Y**, brackets for L1 and R1.

CARBORUNDUM CRYSTAL SET

Materials other than galena, silicon or germanium have the property of detection. In the beginning of radio, carborundum (the name given to a compound of silicon carbide) was also used as a detector. The required heavy catwhisker pressure made it suitable for the early radio stations on ships, as it did not fall out of adjustment. It would also handle the strong signal energy from nearby spark transmitters without burning out. But what makes this type of crystal detector different, is the necessity for a bias battery.

A crystal detector has a high current flow with voltage applied so that it conducts in the forward direction (catwhisker to crystal), and a very low current flow in the reverse direction. The amount of current flow in the forward direction depends upon the characteristics of the crystal material and the applied forward voltage.



TYPICAL CRYSTAL DIODE CURRENT

The graph compares carborundum with germanium and silicon crystal detectors. Germanium minimum conduction voltage is about 0.3 V. Silicon is 0.6 V, and carborundum is 3 V. The high carborundum minimum conduction voltage is the reason a bias battery is used to move the threshold down so that weak radio signal voltages can be detected.

TUNING COIL

As shown in the illustration, the tuning coil L1 is wound on a cardboard (or plastic) mailing tube section 2-inches in diameter and 2 3/4-inches long.



TUNING COIL ASSEMBLY

Locate and drill a hole 1/4-inch from each coil form end for machine screws to fit the two spacers. Also drill holes for two mounting brackets at one end. Then drill a small hole near each spacer hole to feed the wire on the form before you start winding.

Wind the coil with No. 24 enameled copper wire. Tap the coil every 10 turns for a total of 9 taps. An easy way to make the taps is to twist the wire together for a half inch and position the free end out. Make all the coil taps in the area between the two spacer holes. Thread the free end of the wire through the small hole at the end of the form near the spacer hole. Make sure that all of the turns are tightly wound and close together. Use a section of sandpaper to remove the enamel from the tap wire ends. Then tin the ends.

Mount 9 push-in clips in a 1/2-inch by 2 1/4-inch perf board section. Locate and drill holes on the board and install it on the coil form with two solder lugs, 1/2-inch spacers, machine screws, and nuts. Solder the coil taps to the ends of the push-in clips. Connect the coil leads to the solder lugs and mount the two 1/2-inch brackets on the coil form.

DETECTOR

The crystal detector assembly is vertical, (as shown in the illustration) instead of horizontal as in most catwhisker detectors. Begin construction by cutting the 2 1/2-inch diameter base and 2-inch by 4-inch vertical section from 1/4-inch thick wood.



DETECTOR ASSEMBLY

Locate and install the two fahnestock clips on the base with solder lugs and small wood screws. Mount the vertical section on the edge of the base with wood screws (or cement). Locate and install the catwhisker holder with a solder lug, machine screw and nut near the top of the vertical section.

Temporarily position the crystal holder on the base so that the catwhisker will touch the center of the crystal. Locate and mount the crystal holder in this position with a solder lug and machine screw and nut. Connect the detector assembly with hookup wire as shown in the illustration. Solder a short section of coiled steel spring wire to the end of the positioning rod to serve as a catwhisker. Cut the end of the wire diagonally to give it a sharp point.

BASEBOARD

The receiver parts are installed on a 8-inch by 7-inch by 3/4-inch wood base. Wherever poossible, small wood screws are used to hold the components on the base.

Begin construction by laying out and installing the parts in the positions shown in the illustration. It will be necessary to make a metal mounting bracket to fit R1. C1A-B and C2 are mounted with machine screws in the tuning capacitor frames through countersunk holes in the base. Install solder lugs in the rear frame of both tuning capacitors. Also mount solder lugs with all of the terminals. Install knobs on the tuning capacitors and R1.

WIRING

Use hookup wire to connect the crystal set parts as shown in the schematic and illustration. Connect 5-inch leads of flexible stranded insulated wire to each alligator clip. Solder one lead to the stator lugs of C1A-B and connect the other lead to D1. Connect C3 and C4 as shown and keep their leads as short and direct as possible.

Experiment 1

Connect your antenna to J1, ground to J2, and 2000-ohm headphones to J5 and J6. Temporarily connect a germanium diode (1N34A or equiv.) in place of the carborundum crystal detector D1. The diode will make it easier to check out the receiver.

Do not attach the battery
to J3-J4 at this time, or
the diode may be damaged.

Connect **X** C1A-B clip lead to the top tap of L1, and **Y** D1 clip lead to the second tap from the top. Tune in a radio station with C2 and then adjust C1A-B for best volume. Change the position of the clip leads and retune C1A-B and C2 for best reception. Check operation of the receiver over the entire broadcast band.

Experiment 2

Tune the receiver to a radio station and then disconnect the germanium diode. Do not disturb the receiver tuning. Install a carborundum crystal into the D1 assembly. Set R1 to mid range, and connect a 6-volt battery to the receiver; negative lead to J3, positive lead to J4.

Adjust the D1 catwhisker for a sensitive spot on the carborundum crystal. Then set R1 for best volume of received signal. Retune C1A-B and C2 and change the clip leads on the L1 taps as necessary for reception of radio stations.

Note

Carborundum that will work as a detector may be hard to find. Grinding wheels are not suitable as a source, because the carborundum is usually in fine particles mixed with other material. Best bet is to contact collectors of antique radio parts. But you can use this receiver to experiment with minerals for semiconductor operation. See the Workshop Section for information on mounting mineral sections for detector experiments.

4 COMPONENT PROJECTS

BOOK TUNING CAPACITOR

During the roaring 20's,the Crosly Radio Corporation used a type of tuning capacitor that had two plates hinged together on one edge. The dielectric was a sheet of mica between the two plates. This type of tuning capacitor was called a Book Condenser.

The tuning capacitor shown in the illustration is similar to the Crosly Book Condenser. It uses aluminum foil plates cemented to fixed and movable wood sections, and a plastic sheet dielectric (cut from thin transparent plastic notebook protector material).



Adjusting the tuning knob causes a metal cam to rotate and control the movement of a spring loaded wood section. This varies the capacity between the two foil plates. As the plates are brought closer together, the capacity increases. As they are separated, the capacity decreases.



BOOK TUNING CAPACITOR

List of Materials

A - 3 x 3 1/2 X 3/8-inch wood section
B - 3 x 1 3/4 x 3/8-inch wood section
C - 3 x 3 1/8 x 3/8-inch wood section (one end beveled 45 degrees - see text).
D - 3/4 - inch diameter wood dowel, 2 1/4 inches long.
E - 3 1/2 x 3 -inch sheet plastic (See text).
F - 2 triangular 1-inch metal sections
G - 1/4-inch metal rod, 3 -inches long.
H - Metal cam (see text).
I - Machine screw (see text)
J - Bushing 3/8-inch long (to fit rod G).
K - Tuning knob (to fit rod G).
L - 2 springs 1/4-inch diameter by 1 1/4-inch long.
M - 4 solder lugs.
MISC. Small wood screws, nails, aluminum foil, machine screws, nuts, solder lugs and washers.

CONSTRUCTION

Start construction by cutting the wood sections from 3/8-thick wood to the sizes shown in the drawing. Section C has a 45 degree bevel at one end. This acts as a pivot point for the movable section. Drill and countersink a hole to fit a flathead machine screw in the places shown on sections A and C. Do not install the screws at this time.

Cement aluminum foil on the top of section A and on the bottom of section C. Then cut and remove a 1/2-inch strip of foil from the front edge of section A. Cut a 1/8-inch strip from the remaining edges. Also cut away a 1/8-inch strip from all the edges of the foil on section C.

Carefully slit the foil on top of the machine screw hole on section A and press the foil gently inside the hole. Install the flathead machine screw into the hole, making sure that it is in contact with the foil. Fasten the screw with a washer and nut. Make sure that the screw does not turn and rip the foil. Install a solder lug and nut on the free end of the screw. Repeat this operation with section C.

Cut the sheet plastic E to size and place it on top of section A. Then place section B on top of the plastic sheet and install it on the end of section A with wood screws. Install the two metal sections F with small nails.

Saw the metal rod G to size and tap one end to fit a machine screw. Cut the dowel D to size and center drill it to fit the rod G. Cut a flat on one side of the dowel.

Make a tracing of the cam H template and cement it on a section of heavy gauge sheet aluminumm. Cut the cam to size and drill a hole to fit the rod machine screw in the location shown. Install the cam with a lock washer on rod G. Insert the free end of the rod into dowel D. Place section C on top of the plastic sheet E on section A. Then temporarily position dowel D with rod G in the center of section B. Rotate the cam so that its long end touches the top of section C. Mark the placement of the dowel on section B. Drill a hole in section B to fit dowel D. Cement the dowel in place.

Locate and install solder lugs with wood screws on sections A and C as shown in the drawing. Bend over the ends of the solder lugs and install two springs L in the lugs.

Mount tuning knob K and bushing J on the free end of rod G. Adjust the knob and check that section C moves in and out with the cam rotation. changing the capacity between the foil plates.

You may have to experiment with the cam diameter for best operation of section C. File the cam edges in small increments only and recheck the operation often. Use very light springs to keep section C from pressing against the cam and moving it.

Reverse the cam on rod G to alter the direction of capacity (clockwise or counterclockwise). The capacitor can be installed vertically on a receiver project with a small metal bracket mounted on the bottom side of section A.



ROTARY SWITCH

List of Materials

A - 2 1/4 diameter x 3/8-inch wood section.
B - Flat head machine screws.
C,L - Solder lugs.
D - Nuts to fit B.
E - Machine screw 1 1/4-inches long.
F - 1/4 diameter x 1/2-inch long bushing (to fit E).
G - Switch arm 1 x 1/4-inch (sheet brass, see text).
H,K,M - Nuts to fit E.
I,J - Washers to fit B.
N - Small woodscrew.

ROTARY SWITCH

In the early days, radio experimenters could not buy parts that are readily available today. They had to build their radio components from wood sections and common hardware.The rotary switch ilustrated is similar to a type constructed for use with tapped coils of crystal sets.

The rotary switch shown uses flat head screws for contact points that are mounted on a wood section. The switch arm is cut from sheet brass and is installed on a machine screw.

CONSTRUCTION

Refer to the drawing of the rotary switch. Begin construction by cutting the 2 1/4-inch diameter section A from 3/8-inch thick wood. Locate, drill,and countersink the holes for the flathead machine screws B. The rotary switch shown has 10 machine screws, but you can space the hole locations for the number of switch contact points desired. Allow a space between the starting and ending contact points for the woodscrew N. This woodscrew is used as a stop for the rotary arm G. Locate and drill a center hole for the machine screw E. Install the screws B in section A with solder lugs C and nuts D. Install the woodscrew N.

Measure and cut the rotary arm G from a section of sheet brass. The arm should be long enough to reach the contacts. Make sure that it is not too wide, or it may short out to a nearby contact. Make a dent or "dimple" on the contact end, and drill a hole for screw E on the other end. Bend the rotary arm as shown in the drawing. Install screw E into bushing F, and arm G, and tighten the assembly with nut H. Place washer I on the screw and install screw E into the center hole of A. loosely fasten the screw with washer J and nut K. Then rotate the bushing F and arm G. Adjust the tightness of nut K as required to allow rotation of G with only a slight "drag". Install solder lug L on screw E with nut M, and bend the lug towards the screw end. Install knob O on bushing F, and recheck operation of the arm G. It should touch all of the contacts B and stop at screw N.

The rotary switch is used as shown in the Dual-Tuned Crystal Set Construction Project. Make sure that extra lead length is allowed for connection to the solder lug L. Bend the lead into a "pig-tail," so that it will not break as the solder lug L is rotated.

5

WORKSHOP

The construction projects in this book can be built with common hand tools found in an average home workshop.

Useful Hand Tools

Safety glasses or face shield
Steel rule
Square
Hack saw
Wood saw
Screwdrivers
Pliers
Wirecutters
Tin snips
Center punch
Files
Hammer
Soldering Iron

Wear safety glasses or face shield while working. Observe common sense safety precautions.

SOLDERING

Make sure that the part to be soldered is clean. Use only rosin core solder. Prepare the soldering iron tip as follows:

File each surface of the tip to remove oxidation. Plug in the iron and let it heat until you can melt solder on the tip (before the copper tip turns blue or bronze color). Melt enough solder until all sides of the tip are coated. Then wipe off excess solder with a damp sponge or cloth.

Make sure that the bare wire lead to be soldered is free of oxide. It is best to tin it first by melting a bit of rosin core solder on the lead end. Crimp the lead in the part hole to keep it from moving during soldering. Hold the iron tip under the part until it is hot enough to melt solder. Apply only enough rosin core solder to cover the surface of the part. Remove the iron. Do not move the part or wire while it is cooling.

PROJECT CONSTRUCTION TIPS

Tape a sheet of graph paper over a project wood section. Mark locations of the parts on the paper. Center punch mounting hole centers through the paper. Use a compass to draw circles the same size as the holes. Then drill holes through the paper.

Lettering on the projects can be done with a labelmaker that prints on strips of adhesive coated plastic. You can also use decals or dry transfer lettering sheets.

Small metal brackets can be made from heavy gauge sheet aluminum. Layout and drill the mounting holes and then cut it to size with a tin snips. Form the bracket by using a heavy mallet and a vise.

Tuning Capacitors, Knobs, and Dials

Old radios are a good source of components. The radios generally use two tuning capacitor sections ganged together. The receivers previously described will operate with one of the capacitor sections (365 mmf). You can cut out cardboard discs and cement them to radio knobs and use them as dials with the tuning capacitors. Mark the dials with dry transfer lettering, or black drawing ink.

Panels and Cabinets

The layout and construction of crystal sets is not critical. They can be fitted into many different types of wood cabinets. You can use almost any type of non-metallic box, but metal boxes are not recommended as sheet metal close to the tuning coil may lower its "Q". Black sheet plastic used for the front panel with white dry transfer lettering will give your receiver project an antique look.

MOUNTING MINERALS FOR CRYSTAL DETECTORS

Minerals (galena, etc) for experimentation as crystal detectors, will work best when mounted in a metallic base. For temporary mounting (while testing), wrap aluminum foil tightly around the sides and bottom of the mineral. Then place it into a sheet metal ring or cup that will fit into the detector assembly.

After testing, the mineral can be permanently mounted in a metal slug. Drill a shallow hole of a diameter equal to the detector assembly crystal in a block of wood. Fill the hole with melted solder. While the solder is still molten, carefully place your mineral section into the center. Hold the mineral in place with tweezers or long nose pliers until the solder cools. Then pry the metal slug out of the wood. Be sure that the top of the mineral section is free of solder.

INDEX

Advanced receiver projects,32
Amplifier connection,14,15
Antenna lead-in,10
Antenna,10

Book tuning capacitor,48
Boundary,5
Bias,5

Capacitor,8
Capacity,8
Carborundum crystal set,43
Carborundum,43
Catwhisker detector,4,6
Catwhisker,6
Component projects,48
Construction tips,55
Crystal detector assembly,45
Crystal detector,4

Detected audio signals,7
Detection,4,6
Diode electron flow,5
Dual spiderweb coils,37
Dual-tuned crystal set,32

Earphones,11
Enamel insulation,17
Electron current flow,5

Ferrite coil crystal set,23
Ferrite coil,12
Ferrite rod,23

Galena,4
Germanium,4
Ground lead,10
Ground wave,25
Ground,10

Hand tools,54
Headphones,7,11
Headset,11

Junction diode,4,5

Knobs and dials,55

Lettering,55
Loading coil,21
Loopstick,12

Modulated radio waves,6
Mounting minerals,56

N type material,4
Natural crystal,4

Operating tips,25

P type material,4
PN junction,5
Panels and cabinets,5
Parallel tuned circuit,9
Point contact diode,4,6
Primary coil,23

Reactance,8
Receiving radio waves,7
Resonant frequency,9
Rf coil,8
Rotary switch project,53

Schematic symbols,15
Secondary coil,23
Selective crystal set,37
Selectivity,9
Semiconductor diode,4
Silicon,4
Simple crystal set,12
Simple receivers,12
Sky wave,25
Slider tuned coil,17
Slider tuned set,17
Soldering,54
Space charge region,5
Spiderweb coil set,27
Station log,31

Tapped coil,32,44
Tapped spiderweb,27
Transmitted waves,6,7
Transmitting station,6
Tuned circuit,7,9
Tuning crystal set,7

Untuned detector,20

Variable capacitor,8
Variable coupling,39

Wave trap,21
Workshop,54

About the Author

Charles Green has been involved in the design and construction of electronic equipment for industry and the U.S. Government for 30 years. Much of his experience has been as a technical writer preparing operation and maintenance manuals. His continuing interest is in constructing radios and he has had over a hundred articles published in hobbyist magazines over the past two decades.

A sun-powered transistor amplifier makes this a—

Space-Age Crystal Set

By D. S. Halacy Jr.

LIGHT-POWERED RADIO plays indoors under artificial light, too. Performance is boosted by connecting antenna to TV aerial or telephone-dial finger stop; a short length of wire, with alligator clips at the ends, helps.

THIS tiny radio puts satellite technology in the palm of your hand. Like radios in artificial moons, it's powered by the sun—or any other light.

Basically, it's a 1960-model crystal set. A rugged sealed-in-glass diode has replaced the shaky catwhisker and galena crystal. The usually faint crystal-set signal is magnified many times by a transistor, in turn powered by a high-efficiency silicon solar cell.

This unit—and other parts—can probably be obtained locally for less than five dollars. All are standard parts, stocked by most retail and mail-order shops. In a pinch you can substitute the less-efficient International Rectifier B2M selenium cell for the quarter-round section of a Hoffman silicon solar battery.

First steps. Best place to begin construction is with the case for the radio—a small plastic box. You may find one in the medicine chest or at the druggist's. Start the necessary holes with a hot ice pick, then file or ream to size Keep try-

Author Halacy is an expert on the. sun. A couple of years ago he wrote Fabulous Fireball, *a book that tells the story of the sun and solar energy. Last fall. Macmillan also published his* Fun with the Sun. *a book describing how to make seven solar-energy projects at home. The present, article is an outgrowth of his research for the latter book.*



WIRING IS SIMPLE: five components, 10 soldered joints. Schematic shows circuit. Use flexible stranded hookup wire, and keep hot iron away from plastic case. Paint, lettering, are optional.

CELLOPHANE TAPE
SUN BATTERY
ANTENNA
TUNING CONDENSER
RED WIRE
CK722 TRANSISTOR
RED DOT
E
B
C
PHONE JACK
IN34 DIODE
SOLDER LUG
LOOPSTICK
6-32 MACHINE SCREW AND NUT FILED FLUSH
PLASTIC BOX 3/4" x 1 3/8" x 2 3/4"
TELESCOPING WHIP ANTENNA
IN34
BASE
COLLECTOR
EMITTER
CK722
BROAD-CAST BAND LOOP-STICK
365 MMF. TUNING CONDENSER
+
−
SOLAR CELL

ing the part as you enlarge the hole, to insure a snug fit.

The case can be painted or left transparent. The one pictured has a finish of Day-Glo spray paint, applied to the outside of the case. The paint softened the plastic slightly and created a wrinkled finish.

The hinged top is left clear and a piece of painted bond paper cut to fit inside. This paper was lettered, and cut to accept the dial shaft and solar battery. The lettering is pure whim—there's no trademark or commercial name.

After painting, go ahead with the assembly. Set the antenna mounting base through the bottom hole, put on the nut, cut off excess threads, and file smooth. Add a 6-32 screw and nut to the other side if you expect the radio to stand up.

Condenser and battery. Install the tuning condenser in the hinged top by first removing the dial and the small flathead screws. Remove both hex nuts; use one on the outside to hold the condenser in place. Then mount the dial and twist the silver center screw thumb tight. Place the solar battery in position over the opening in the bond paper, and fasten it in place with a strip of cellophane tape.

Bend the loopstick mounting bracket as shown, snap the loopstick in place, and fasten the bracket with a 6-32 screw and

[Continued on page 230]

Space-Age Crystal Set

[Continued from page 171]

nut. Install the phone jack, and the radio is ready for wiring.

Use stranded hookup wire; it can take the flexing imposed by opening and closing the case.

Pitfalls for amateurs. The wiring shown in the drawing is straightforward and follows the circuit schematic. If you're familiar with electronic wiring, you'll probably find some short cuts. If you're a beginner, stick to the diagram. If you run into trouble, don't hesitate to remove the parts, do the soldering outside, and then replace them.

Use care when soldering the diode and transistor—excess heat will damage them. Sidestep part of the risk by soldering to the lugs of a transistor socket, then slipping the transistor in place. You'll have to clip the transistor's leads to make it fit.

Bend the diode's leads to fit before soldering it between the base of the transistor and the loopstick.

Close the case when you've finished soldering, plug in the earphone, and listen. There's no on-off switch: The battery never wears out.

You should pick up stations at their proper position on the dial as indicated by the point of the battery or a dot on the lid. If the calibration is too far off, make a hole in the end of the case in line with the slotted screw on the loopstick. Turning this screw one way or the other will shift the stations enough to align the dial.

Outdoors, you'll find you don't have to point the Solar Mite at the sun—there is plenty of incident light for satisfactory operation. Keep the whip upright for maximum volume.

For stronger signals. Touching the silver center of the tuning dial may give you a stronger signal, since your body acts as a ground. Also try wetting your finger before touching the dial.

While the Solar Mite will play on the whip antenna, for peak performance connect the whip to your TV antenna. If you don't have an outdoor antenna of any kind, clip a lead on the finger stop of a telephone dial. You'll find that the radio works well enough to bring in a strong station even in the dark—acting as a crystal set without the help of its transistor amplifier.

No. 96

CRYSTAL SET CONSTRUCTION

SIMPLE INSTRUCTIONS FOR MAKING NINE CRYSTAL SETS

by B. B. BABANI

There is to-day a marked revival of interest in crystal receivers, and this book has been specially prepared to introduce the home constructor to the design and building of the various types. The text is simple and free from technicalities, so that even the young reader may confidently embark on the construction of any of the receivers shown.

CONTENTS

1. AERIALS.
2. EARTHS.
3. CRYSTAL DETECTORS.
4. COILS.
5. THE BEGINNERS' CRYSTAL RECEIVER.
6. FRAME AERIAL RECEIVER.
7. LONG DISTANCE RECEIVER.
8. HIGH GAIN RECEIVER.
9. HIGH SELECTIVITY RECEIVER.
10. BATTERY AIDED CRYSTAL RECEIVER.
11. MEDIUM AND LONG BAND RECEIVER.
12. ULTRA SENSITIVE ALL WAVE RECEIVER.
13. AN ADVANCED CRYSTAL DIODE RECEIVER.

THERE ARE 12 DIAGRAMS

LONDON: BERNARDS (PUBLISHERS) LIMITED


VARIABLE CONDENSER
TUNING COIL
CRYSTAL DETECTOR
TUNING COIL WITH TAPPINGS
FIXED CONDENSER
SINGLE POLE DOUBLE THROW SWITCH
BATTERY POSITIVE SIGN
SINGLE POLE SINGLE THROW SWITCH
BATTERY NEGATIVE SIGN
DOUBLE POLE SINGLE THROW SWITCH
AERIAL
"TWO-GANG" VARIABLE CONDENSER
EARTH
WIRES CONNECTED
WIRES NOT CONNECTED
PHONES
FRAME AERIAL
SOCKET AND PLUG

FIG. I SYMBOLS USED IN THE CIRCUITS DESCRIBED.

1. Aerials.

One of the essentials for satisfactory reception with crystal sets is an efficient aerial. Four different types are suggested and are shown in Fig. 2.

There are several important points to be noted when erecting an aerial for a crystal set.

(1) See that it is suspended as high as possible and is not screened by tall buildings, obstructions, etc.

(2) The aerial itself and the lead-in from the aerial must be adequately insulated. Be sure that the porcelain or plastic insulators do not permit the aerial or lead-in to touch the building, tree, or post from which they are suspended. The lead-in should be brought into the house through an insulated rod.

(3) It is exceedingly important to use insulated copper wire, either single or multi-stranded, for both the aerial and the lead-in.

2. Earths.

An adequate and efficient earth contributes to the good performance of any well-designed crystal set and Fig. 3 shows the best method of obtaining an efficient earth where there is a garden or patch of ground available at a short distance from the receiver.

Obtain a 3-ft. length of ½-in. galvanised iron pipe and at one end drill a hole right through. Insert a bolt with spring washer and locking nut in the hole. Connect the earth lead-in wire to the bolt; the other end of the lead-in to the earth connection on the receiver. Leave both ends of the pipe open. Insert the end opposite the bolt into the ground vertically until only 3-in. are showing above the surface of the surrounding earth.

It is important to see that the surrounding ground is kept damp, if necessary by occasionally pouring a pint or two of water down the open projecting end of the pipe.

Ready-made copper earthing rods with a pointed end for easy hammering into the earth are sometimes obtainable from radio dealers.

Should a garden not be available, an alternative earth is a cold water pipe coming from a rising main. Simply file very lightly the pipe at the back of the tap and wind the copper wire earth lead-in round the filed part and cover the joint with insulating tape.

In no circumstances should a gas pipe be used for an earth.

3. Crystal Detectors.

Most radio dealers can supply very efficient permanent or semi-permanent crystal detectors of proprietary makes. However, there are always available quite a number of ex-Government surplus units which are called crystal valves and, though these were originally designed for a very different use in service equipment, they are easily adaptable and will give extremely efficient results when used in circuits designed for them. To enable the constructor to purchase suitable types for this purpose—and they cost very little—the following list gives the Government reference numbers.

CV 101, CV 102, CV 103, CV 111, CV 112, CV 113, CV 226, CV 241, CV 246, CV 247, CV 253, CV 291, CV 351, CV 361, CV 364, CV 367, CV 727, CV 749, and CV 1785.

One of the satisfactory proprietary makes of this class of crystal detector is the BTH CS7A, which, incidentally, is the commercial equivalent of the CV 253.

For all these Government types, one connection should be made to each end by arranging a holder to fix them into or by carefully soldering the appropriate connecting wires to each end.


'INVERTED-L' AERIAL

60'
INSULATOR
INSULATOR
AS HIGH ABOVE GROUND AS POSSIBLE
POLE OR TREE
LEAD-IN
EARTH PIPE

PLATFORM AERIAL

4' BROOMSTICKS WITH THREE INSULATORS
LEAD-IN

'CAGE' AERIAL

4 TOY HOOPS, EACH DRILLED WITH TEN RADIAL HOLES
INSULATOR
INSULATOR
TEN SEPARATE AERIAL WIRES JOINED AS SHOWN TO LEAD-IN

'T' AERIAL

MINIMUM 30 FEET
LEAD-IN MUST NOT TOUCH ROOF
AERIAL WIRE
FITTING AERIAL INSULATOR
LEAD-IN
SUPPORT WIRE OR ROPE

FIG.2 AERIAL SYSTEMS

4. Coils.

In Fig. 3 two methods are shown of fixing the coil to the chassis. However, the ingenious constructor may evolve another arrangement.

The important thing to remember is that the coil should be fixed so that it is completely insulated from the metal chassis that may be used.

It is also important to remember that if a metal chassis is used, one must see that all components and wiring, with the exception of earth connections, are adequately insulated from this chassis so as to make sure that no short circuits take place. It is recommended that all crystal sets should be built on a panel, and that both panel and chassis should be of bakelite, paxolin or perspex, as these three materials are efficient insulators in themselves.

5. The Beginners' Crystal Receiver.

The popularity of the crystal receiver among beginners is undoubtedly due to the very modest outlay necessary, and the ease with which such receivers may be built. It is not always appreciated that, to obtain worth while results,


POUR WATER DOWN PIPE OCCASIONALLY
WING-NUT & BOLT
2"
EARTH
1" COPPER OR GALVANISED IRON PIPE
EARTH CLIP
TO RECEIVER
EARTH SYSTEMS
INSET SHOWS METHOD OF TAPPING COILS
WINDING
6 B.A. BOLTS AND NUTS
COIL FORMER
SPACER
SPACER
PANEL OR BASEBOARD
STRIP OF WOOD
WOOD SCREW
HORIZONTAL MOUNTING
VERTICAL MOUNTING
COIL MOUNTING METHODS

FIGURE 3

far more care in avoiding losses is necessary than with a three or four valve receiver. One reason for this is the fact that the crystal receiver can offer no help by way of amplification and it is therefore dependent on an efficient aerial/earth system, low loss design within the receiver itself, and the use of sensitive headphones. The experience gained is well worth the time expended since, when more ambitious receivers are attempted, the constructor will remember the benefits gained by efficient construction and installation with the result that each receiver attempted will be an instrument capable of giving a first class performance.

Losses within the receiver itself may be considerably reduced by efficient coil design. Unfortunately, selectivity is a factor which must not be overlooked; it is this factor which governs the sharpness of the tuning and permits the separation of adjacent powerful stations. The greater the selectivity, the greater the ease with which signals may be separated; but at maximum selectivity the received signals are at minimum strength. In Fig. 4, the coil is tapped at four points, which enables the best point between selectivity and sensitivity to be chosen. The nearer the aerial tap to the earth end of the coil, the greater the selectivity. The pre-set condenser C1 also aids selectivity; at minimum capacity the selectivity is high, and *vice versa*.

Used in conjunction with the coil taps, the constructor should have no difficulty in selecting a condenser setting and tapping point which permit the reception of strong signals and at the same time effect the required separation of powerful stations.

The coil is constructed on a former 3-in. diameter × 2-in., and consists of 50 turns 36 S.W.G. enamelled wire close wound and tapped at every tenth turn. These taps are brought out in the form of loops twisted firmly so that there is no actual break in the winding continuity. After completion the winding may be painted with Durafix to prevent any movement, and the taps and two free ends cleaned with emery cloth to remove the enamel. The layout and wiring is shown in Fig. 4. The headphones should have a resistance of some 4,000 ohms or more and should be of reputable manufacture. Any of the aerials previously described are suitable for use with this receiver.

C2 .0005 variable condenser.
C1 .0002 pre-set condenser.
C3 .001 mica condenser.
1 Crystal detector, semi-permanent pattern.
2 oz. 30 S.W.G. enamelled copper wire.
1 Coil former 3-in. dia. × 2-in.
1 Ebonite or Bakelite panel 6-in. × 5-in. × ¼-in.
4 terminals, connecting wire, etc.

6. Frame Aerial Receiver for Local Station use on Medium wave bands.

This receiver was specially designed for constructors who are within 5 to 10 miles of a powerful station and who have no facilities for constructing a good outdoor aerial.

The frame itself consists of two ¾-in. × ¾-in. square section wooden rods each 36-in. in length. These are placed together at their centre line to form a cross; they are fastened by a nut and bolt and these in turn pass through an upright piece of wood ½-in. × 1-in. section 2-ft. in length. This upright support is then screwed into a baseboard 8-in. × 8-in. × 1-in. thick. At each of the arms of the 36-in. cross a 4-in. strip of ½-in. square section wood is placed. Reference to Fig. 5B will give the details of the construction of this aerial quite clearly.

It will be noted that approximately 85-ft. of 20 S.W.G. double cotton-covered wire are required for the inductance to cover the medium wave broadcast band. The wire should be wound around the four crossbars, thereby creating


AERIAL
C2
·0002 MFD.
L1
C1
·0005 MFD.
DETECTOR
C3
·001 MFD.
PHONES
EARTH
TAPPINGS
C2
L1
AERIAL
PHONES
DETECTOR
C3
EARTH
PHONES
C1

FIG. 4 THE BEGINNER'S CRYSTAL RECEIVER.

a square wire frame, and each turn of the wire should be spaced approximately ⅛-in. The best way to effect this spacing accurately is to file on the 4-in. crossbars a number of small nicks at ⅛-in. intervals. The two ends of the wire should then be brought down on the two terminals which may be screwed into the square baseboard and two leads taken from there to the crystal set itself.

The actual set may be constructed on a small ebonite, paxolin or perspex panel 8-in. × 5-in. which may be screwed to one side of this base supporting piece of wood, thereby making the set virtually self-contained except for the earphones. Fig. 5A shows the circuit of the receiver.

To obtain the best results with this receiver, the aerial should be rotated by hand until the signals become loudest.

1 Semi-permanent crystal detector.
C1 1 .0005 mfd. variable condenser.
C2 1 .0005 mfd. fixed condenser.
1 condenser dial marked 0 to 100 or 0 to 180.

1 pair of high sensitivity earphones.
85-ft. to 90-ft. of 20 S.W.G. double cotton covered wire. (8oz.)
Sufficient connecting wire for wiring purposes.

7. Long Distance Receiver.

This receiver has been specially designed to achieve high sensitivity. With a sufficiently good outdoor aerial effective reception has been obtained up to 150 miles.

The circuit is quite straightforward, as can be seen from Fig. 6 and the only special point is in winding the coil L1.

This coil consists of a 2½-in. diameter former on which are wound a total of 51 turns using 24 S.W.G. double cotton wire. Starting at one end, tap every two turns until there are eight taps; wind a further 15 turns and tap; then a further 10 turns and tap; finally, add 10 turns to end the winding. The wire should be close wound, *i.e.*, with turns touching.

To obtain the best results, the two crocodile clips A and B should be tried on the various coil taps until the loudest reception is obtained. It may be found in use that the loudest reception of any particular station causes another station to be heard at the same time; care should, therefore, be taken to select the appropriate tapping point to separate any two powerful stations that may interfere with one another.

4 oz. 24 S.W.G. DCC copper wire.
Coil former 2½-in. dia. × 3-in.
C1-2 single variable condensers .00035 mfd.
2 Condenser dials marked from 0 to 100 or 0 to 180.

1 Permanent crystal detector.
C3 .001 fixed condenser.
1 pair of high sensitivity earphones (preferably between 4,000 ohms and 8,000 ohms impedance).
2 Crocodile clips.

8. High Gain Receiver.

This receiver has been designed to give good reception up to 50 miles distance from any normal power broadcasting station in the medium band. It is a very selective circuit and will therefore enable the user to separate closely situated stations.

It will be noticed in the circuit (Fig. 7) that the variable condenser C1, has an on/off switch S1 to throw it out of circuit if necessary. It is used to increase the selectivity of the receiver and, in operating, it should be tried with this condenser either in or out of circuit on the various tappings on the coil L1.

L1 consists of 90 turns of 22 S.W.G. double cotton covered wire wound on a 2-in. diameter former and tapped every ten turns. L2 separately wound on a 2-in. former, consists of 90 turns of 22 S.W.G. double cotton covered wire, also tapped as L1. The components required are given on page [illegible]


FRAME AERIAL
C1
C2

FIG. 5A FRAME AERIAL CRYSTAL RECEIVER


GUIDES
36"
WINDING
HEAVY BASE
4"
DETAILS OF WOODEN GUIDES
CROSSBAR JOINTING METHOD

FIG. 5B. DETAILS OF FRAME AERIAL


10T
B
10T.
L1
15T.
TAP AT 2T. INTERVALS
A
C1
C2
C3
2½"
L1

FIG. 6 LONG-DISTANCE CRYSTAL RECEIVER

C1-2 Single variable condensers .00035 mfd.
S1 Single pole single throw switch.
C5 .0001 preset condenser.
1 Permanent crystal detector.
C3-4 .001 mfd. fixed condenser.
1 Pair of high sensitivity earphones.
8 oz. 22 S.W.G. DCC.
2 Dials for variable condenser marked 0 to 100 or 0 to 180.

9. High Selectivity Receiver.

This circuit (see Fig. 8) is for use in high saturation strength areas where it is desired to separate powerful stations. The circuit is not complicated and is extremely effective.

It will be noted that C1 and C2, each .00035 mfd. capacity, are 2 gang unit.

The only special point in this set is the design of coils L1, 2 and 3, which are constructed as follows: L1, 60 turns of 22 S.W.G. double cotton covered wire on a 3 × 4 inches former tapped every five turns; L2, 15 turns of 22 S.W.G. double cotton covered wire on a 3 × 6 former; and L3, 85 turns of 22 S.W.G. double cotton covered wire wound on the same former as L2, the two windings being separated by approximately ½-in. (see Fig. 8).

Note that the aerial lead is brought down to one of the tappings on wire L1. This should be tried on each of the tappings and the one giving the required selectivity should be used.

C1-2 2-gang variable condenser .00035 mfd.
2 3-in. formers for coils L1-2-3.
8 oz. 22 S.W.G. DCC.
C3 .0005 fixed condenser.
1 Semi-permanent crystal detector.

10. Battery-aided Crystal Receiver.

Fig. 9 shows a design which utilises a 9-volt grid bias battery to improve performance.

The charge built up in the .02 mfd. fixed condenser is changed to a positive current when it passes through the coil L1. This, in turn, is superimposed on the positive charge that is commencing to be rectified by the crystal detector and thereby increases the signal strength.

Coil L1 consists of a 4-in. diameter former wound with 85 turns of 24 S.W.G. double cotton covered wire tapped at 5, 25, 45 and 65 turns from the earth end. The earth end and these four taps are brought out to five small sockets and the connection from the earth is taken to a small socket. The plug should be tried in each of the five positions to find which one gives the greatest signal strength.

The 9-volt battery is connected across the .02 mfd. condenser and special care should be taken to see that the battery is connected correctly, *i.e.*, negative pole to earth.

1 Permanent crystal detector.
1 4-in. dia. × 3-in. former.
8 oz. 20 S.W.G. DCC copper wire.
C1 Variable condenser .0005 mfd.
C2 Fixed condenser .005 mfd.
C3 Fixed condenser .02 mfd.
1 pair of high sensitivity headphones.
1 Clix plug.
5 Clix sockets.
1 9-volt grid bias battery.

11. Medium and Long wave band Receiver.

This set has been designed for reception on two wave bands.

Care must be taken in winding the coils L1, 2, 3 and 4. These are wound on a single 3-in. diameter former. L1 consists of 30 turns of 28 S.W.G. DCC tapped at 8, 16 and 24 turns. L2, 60 turns of 32 S.W.G. DCC. L3, 40 turns of 28 S.W.G. DCC, and L4, 80 turns of 32 S.W.G. DCC. All are close wound and are separated from each other as follows: between L1 and L2, 3/16-in.;


S1
C5
L1
C1
C2
L2
C3
C4

FIG. 7 HIGH-GAIN CRYSTAL RECEIVER


L1
C1
C2
C3
L2
L3
1/8" SPACING
L2
L3

FIG. 8 HIGH SELECTIVITY CRYSTAL RECEIVER


5 SOCKETS
PLUG
C1
C2
C3
+
9V. G.B. BATTERY
-

FIG. 9 BATTERY-AIDED CRYSTAL RECEIVER

between L2 and L3, 1-in.; and between L3 and L4, 3/16-in. See Fig. 10.

C1-2 single variable condensers .0005 mfd.
2 Variable condenser dials marked 0 to 100 or 0 to 180.
1 Clix plug.
3 Clix sockets.
S1 Single pole double throw switch.
C3 .001 mfd. fixed condenser.
1 Pair of high sensitivity earphones.
1 3-in. dia. × 8-in. former.
2oz of both 28 and 32 S.W.G. double cotton covered wire to make these 4 coils.
1 Permanent crystal detector.

In use, the plug should be tried in each of the three sockets to find the point which gives the best results. The switch is used as a wave band change switch.

12. Ultra Sensitive All Wave Receiver.

The receiver shown in Fig. 11 is for long distance reception. It is a novel circuit and, though apparently complicated in construction, it is really very simple to assemble with the minimum of tools and labour.

It will be seen from the circuit diagram that there are two banks of sockets, five black and six red. When using this set the appropriate black and red plugs should be inserted in whichever of the similar coloured sockets give the best results. The coil is quite easy to construct and consists of a primary winding which is inserted at the earth end of the secondary winding. For the medium wave band, the secondary winding L2 consists of 54 turns of 20 S.W.G. enamelled or cotton covered wire. This coil has four taps in addition to the starting point and the end connection, and these taps are taken at six turns, 14 turns, 27 turns and 40 turns from the earth end. The taps are taken out and a connection is made to an appropriate socket, as shown in the diagram.

The coil is wound on a 3-in. diameter former which may be a paper tube, bakelite, paxolin or perspex, and spacing is approximately 17 turns to the inch.

For short wave work down to about 30 metres, L2, the secondary coil, will consist of the same diameter former wound with 15 turns of the same gauge wire, the four taps being taken at 3, 6, 9 and 12 turns from the earth end.

L1, the primary coil, is used for both wave bands and consists of 11 turns of similar gauge wire to that used for L2, wound on a 2-in. × 1-in. former, the winding to be spaced the same as L2. The coil is then inserted at the earth end of whichever secondary coil L2 is being used.

The crystal detector may be one of the semi-permanent types freely available to-day; the old-fashioned cat's whisker pattern; or one of the silicon permanent detectors which are sold by many surplus dealers.

The 'phones should be of a standard type 4,000 ohms impedance although 'phones of other values will probably operate quite satisfactorily with this powerful receiver. It should, however, be stressed that the better the headhones used, the more satisfactory the reception.

Coils for other wave bands may be experimentally designed by the constructor, remembering that four tappings are advisable for the secondary coil L2.

A long aerial is very desirable with this receiver, placed as high as possible. It is recommended that a minimum length of 70-ft. be allowed, to include the aerial and lead-in.

The values of the components are shown in the following components list. The constructor should experience no difficulty in obtaining excellent results from this cleverly designed receiver.

C1 .0005 variable condenser.
C2 .002 fixed condenser.
1 semi-permanent crystal detector.
1 coil former 3-in. dia. × 4½-in.
1 coil former 2-in. dia. × 1-in.
¼ lb. 20 S.W.G. enamelled or DCC copper wire.
6 red wander plug sockets.
6 black wander plug sockets.
1 red and 1 black wander plug.

Headphones, terminals, connecting wire


C1
L2
L3
S1
L4
C2
C3
3"
L1
3/16"
L2
1"
L3
3/16"
L4

FIG. 10 MEDIUM AND LONG-WAVE CRYSTAL RECEIVER


RED PLUG
BLACK SOCKETS
BLACK PLUG
C1
L1
RED SOCKETS
L2
C2

FIG. 11 ULTRA-SENSITIVE ALL-WAVE CRYSTAL RECEIVER



FIG. 12 ADVANCED CRYSTAL DIODE RECEIVER

13. An Advanced Crystal Diode Receiver.

The modern crystal diode of the radar type does not require any adjustment and thus has a distinct advantage over the ordinary crystal detector which needs delicate adjustment—even the semi-permanent type.

Such crystals are now obtainable on both the regular and the surplus markets, and a popular type is the B.T.H. CS7A silicon crystal (also coded as CV 253).

A rather different circuit from the usual crystal set arrangement is needed to suit the characteristics of a crystal diode. The diode must be tapped on to the tuning coil, and it is found that the tuning circuit itself gives best results if a series-tuned acceptor circuit is used. The circuit of a radar crystal receiver is shown in Fig. 12. The type of aerial used with this circuit has a very great bearing on the behaviour of the receiver for, in effect, the tuned circuit, with a series resistance equivalent to the reflected crystal load resistance, is in series with the capacitance of the aerial to earth and the aerial's effective series resistance.

At resonance—when the combination is tuned to any particular signal—the inductance resonates with the capacitances of the tuning condenser and the aerial in series, and the final effect is that the reflected load of the crystal, in series with the coil's R.F. resistance, is paralleled across the aerial's series resistance.

For maximum power transfer, the crystal load resistance must be made equal to the sum of the aerial series resistance and the coil R.F. resistance, and so the method in which the crystal is tapped into the tuning coil, and the exact capacitance required to tune the receiver to any required signal, must depend to a very great extent on the aerial itself.

At the same time the crystal resistance varies with the signal strength, the resistance being high for weak signals and dropping by as much as 50 per cent. and more for strong signals, so that this effect also has a bearing on the correct coil tap. The output impedance of the crystal also varies similarly, affecting the matching of the headphones into the crystal diode, and so for any set of conditions, the receiver requires to be matched up to both the aerial and the signal being received for best results. This would mean a series of coil taps and (theoretically, not practically) a matching transformer between the diode and the headphones; but in practice it will be found that a receiver using standard parts can be built up to give very good results under various conditions.

It has been shown already that the tuning of the receiver depends to a great extent on the characteristics of the aerial, and while a .0005 mfd. variable capacitor is shown in Fig. 12 as the tuner, the constructor must be prepared to experiment with different capacitance values until the required station is tuned in. The range of reception given by the receiver is quite good, if a really long and high aerial, and a good earth connection, are used; but no more than the local station signal can be expected, and the tuning therefore must be adjusted to suit the station frequency.

It must be mentioned that the headphones are shown parallel connected. High resistance headphones of the 4,000 ohm type must be used, and if two of these are connected in parallel rather than in the more usual series method, they will provide a roughly accurate match to the crystal. If more than one pair of headphones are to be connected in, then the pairs of headphones may be left series connected in the usual manner, the sets of headphones being connected in parallel.

The capacitor across the headphone terminals completes the crystal R.F. circuit, and any value between about 0.001 and 0.005 mfd. will serve. The higher capacitance will, of course, by-pass some of the higher audio frequencies, so that if good steady reception is obtained some experiment with this condenser is also worth while.

C1, .0005 mfd. variable condenser.
C2, .005 mfd. fixed condenser.
4oz. 26 S.W.G. enamelled copper wire.
M.R.1 CV 253 Crystal diode.
Coil former 1½-in. dia. × 4½-in.

Coil details are as follows: 150 turns of 26 S.W.G. tapped at 20, 25, 30, 35, 40 and 45 turns from the earth end. At each tapping-point the wire should be twisted up into a loop and the winding then continued without breaking the wire; when the coil is completed and the ends anchored the tapping loops can be bared.

BERNARDS RADIO BOOKS

No.		Price
56.	Radio Aerial Handbook	2/6
57.	Ultra-Shortwave Handbook	2/6
58.	Radio Hints Manual	2/6
64.	Sound Equipment Manual	2/6
68.	Frequency Modulation Receivers' Manual	2/6
73.	Radio Test Equipment Manual	2/6
83.	Radio Instruments and their Construction	2/6
96.	Crystal Set Construction	1/–
99.	One Valve Receivers	1/6
100.	A Comprehensive Radio Valve Guide, Book 1	5/–
103.	"Radiofolder" A. The Master Colour Code Index for Radio and T.V.	1/6
104.	Three Valve Receivers	1/6
107.	Four Valve Circuits	1/6
108.	Five Valve Circuits	2/6
121.	A Comprehensive Radio Valve Guide, Book 2	5/–
123.	"Radiofolder" F. The Beginners' Push-Pull Amplifier	1/6
126.	Boys' Book of Crystal Sets and Simple Circuits	2/6
129.	Universal Gram Motor Speed Indicator	1/–
134.	F.M. Tuner Construction	2/6
135.	All Dry Battery Portable Construction	2/6
138.	How to Make F.M. and T.V. Aerials, Bands 1, 2 and 3	2/6
141.	Radio Servicing for Amateurs	3/6
143.	A Comprehensive Radio Valve Guide, Book 3	5/–
145.	Handbook of AM/FM Circuits and Components	2/–
146.	High Fidelity Loudspeaker Enclosures	5/–
147.	Practical Tape Recording Handbook	5/–
148.	Practical Transistor Receivers, Book 1	5/–
149.	Practical Stereo Handbook	3/6
150.	Practical Radio Inside Out	3/6
151.	Transistor Superhet Receivers	7/6
155.	Portable Transistor Radio and Radiogram	2/6
156.	Transistor Circuits Manual, No. 1	2/6
157.	A Comprehensive Radio Valve Guide, Book 4	5/–
158.	Radio, Television, Industrial Tubes, Semiconductor and Diodes Equivalents Handbook (208 pages)	9/6
159.	Realistic High Fidelity	5/–
160.	Coil Design and Construction Manual	5/–
161.	Radio, Television and Electronics Data Manual	3/6
162.	High Fidelity Stereo Gramophone	5/–
163.	Transistor Circuits Manual, No. 2	2/6
164.	High Fidelity Tape Recorder for the Home Constructor	2/6
165.	Hartley on Hi-Fi, Book 1, Radio Tuners	5/–
166.	Public Address Systems	2/6
167.	Transistor Circuits Manual, No. 3	2/6
168.	Transistor Circuits Manual, No. 4	2/6
169.	Hi-Fi Transistor F.M. Tuner for the Home Constructor	3/6
170.	Transistor Circuits for Radio Controlled Models	7/6
171.	Super Sensitive Transistorised Pocket Set Construction	3/6
172.	International Radio Stations List	2/6
173.	Practical Transistor Audio Amplifiers	3/6
174.	Transistor Subminiature Receivers Handbook	5/–
175.	Transistorised Test Equipment and Servicing Manual	3/6
176.	Transistor Audio Amplifiers Manual	6/–
177.	Modern Transistor Circuits for Beginners	7/6
178.	Comprehensive Radio Valve Guide, Book 5	6/–
179.	Transistor Circuits Manual No. 5	5/–
180.	British Semiconductor Survey	15/–
181.	22 Tested Circuits Using Micro Alloy Transistors	5/–
182.	"At A Glance" Radio Valve & T.V. Tube Equivalents	3/6
183.	How to Receive Foreign T.V. Programmes on your Television Set by simple Modifications	5/–
	Resistor Colour Code Disc Calculator	1/6
	Engineers' Reference Tables	1/6
	International Radio Tube Encyclopaedia—3rd Edition	63/–

THE BOY'S BOOK
of
CRYSTAL SETS

BY

W. J. MAY

⁂

BERNARDS (PUBLISHERS) LTD.
THE GRAMPIANS
WESTERN GATE
LONDON W.6

General Editor
WALTER J. MAY

First Published—March, 1954
Second Impression—June, 1954
Third Impression—April, 1955
Fourth Impression—January, 1956
Fifth Impression—February, 1957
Sixth Impression—August, 1957
Seventh Impression—March, 1958
Eighth Impression—October, 1958
Ninth Impression—April, 1959
Tenth Impression—December, 1959
Eleventh Impression—April, 1960
Twelfth Impression—October, 1960

⁂

Printed by V. Cooper & Partners, Ltd., Flitcroft St., W.C.2
for Bernards (Publishers) Ltd., The Grampians, Western Gate, London, W.

PREFACE

The Publishers make no apology for reviving interest in the crystal set. For too long the technical press has immersed itself in an orgy of complex superheterodyne receivers and television equipment, all of which is necessarily expensive. In the 1920's, crystal set construction was a fascinating and inexpensive pastime indulged in by the majority of boys of that day. Today this pleasurable hobby can be even more attractive, the introduction of the germanium crystal diode and high performance coils, has opened up new paths which will capture the interest of boys of all ages. Perhaps most important of all, not only can a receiver capable of impeccable reproduction be produced without any technical knowledge; but the cost is no greater than that of a few visits to the cinema

⁂

CONTENTS

	Page
Preface - - - - -	4
Introduction - - - -	5
Receiver No. 1 - - - -	12
Receiver No. 2 - - - -	13
Receiver No. 3 - - - -	14
Receiver No. 4 - - - -	16
Receiver No. 5 - - - -	19
Receiver No. 6 - - - -	20
Receiver No. 7 - - - -	23
Receiver No. 8 - - - -	24
Receiver No. 9 - - - -	26
Receiver No. 10 - - - -	27
Receiver No. 11 - - - -	30
Receiver No. 12 - - - -	31

INTRODUCTION

Before any attempt is made to construct a receiver, it is necessary to examine the problems which surround the crystal set, so that the best can be obtained from any of the designs attempted.

Firstly, it must be understood that the crystal set as it is to-day does **not** provide any amplification. It relies entirely on what is fed into it via the aerial and earth system and gives a very faithful replica of the original transmission.

From this it will be obvious that the aerial and earth system must be as efficient as possible if the final results are to be in any way outstanding. This because these are the only means by which the signals are fed to the receiver.

Secondly it is necessary to understand the nature of the transmitted signal, then it will be easy to understand the working of the set and to appreciate the function of each of the components.

When crystal sets first became popular, very little information was generally available, at least, not in a form that school-boys could understand.

We all built sets of all shapes and sizes, with coil designs that had to be seen to be believed, but very few of us had much idea of how they worked.

I well remember the case of a cousin of mine who, in those days acquired a magnificent variable capacitor or condenser as it was then called, this instrument had a most impressively engraved dial of polished ebonite, brass vanes and nickel plated end plates. Having observed similar dials on several highly priced commercial receivers in the town, he at once ripped out the somewhat tattered coil from the family receiver and replaced it with this device. The profound silence which ensued caused considerable amazement and dismay until a better informed adult explained the mysteries of L and C to him. Readers of this manual, however, will be better informed and there is no risk of failure with any of the designs described provided the instructions are carefully followed.

The Signal

To commence, we will assume that an orchestra is playing in a broadcasting studio. Since the principle of radio transmission is electrical it is necessary to change the sound produced by the orchestra into an electrical equivalent. This is carried out by the microphone, which picks up the sound and changes it into minute electric currents.

As they appear at the output of the microphone they are too small to be of use and accordingly are passed through a high power amplifier. These amplified currents could now be transmitted, but unfortunately, as we shall learn, owing to the inherent nature of the signal in this state, transmission over any useful distance would be impractical.

When the music from the orchestra is transformed into electrical currents they are in the form of alternating currents, usually called A.C., that is they rise to a maximum in one direction, fall to a minimum, rise to a maximum in the opposite direction and then fall to minimum again. This process is repeated over and over again. One complete rise and fall in each direction is called a cycle and is drawn in Fig. 1. Every time a note is struck on a piano, vibrations are sent out which reach the ear enabling you to hear it. These vibrations are also spoken of as cycles, they rise and fall in intensity the same way as an alternating current. The number of cycles radiated by any given note over a period of one second are referred to as its frequency. Middie C on the piano sends out 261 cycles every second and is known as having a frequency of 261. The microphone also "hears" the note and in the case of middie C produces minute A.C. at 261 cycles. This can be drawn as in Fig. 2, the only difference between Fig. 1 and 2 is, that the time factor is given so that the frequency can be identified. The higher the pitch of a note the higher the frequency and the lower the pitch the lower the frequency. On a piano the frequency of the top note is 3515 cycles and that of the lower 27 cycles. Those of you who have listened to an organ in a concert hall will have noticed that when a very deep note was played, it sounded like a growl to the ear, but the vibrating fre-



FIG 1



FIG 2



FIG 3



FIG 4

quency could be distinctly felt through the seat. Higher notes have too high a frequency to be observed in this manner.

The range of sounds which can be detected by the human ear are known as audio or low frequencies. From this you will understand that a low frequency amplifier is one which amplifies sound.

So that the transmitter will carry the programme over a useful distance it is necessary to radiate high frequencies. Now, as explained, the programme to be transmitted consists of low frequencies, and to overcome the difficulty, the transmitter generates A.C. of high frequency and combines it with the low frequencies. It will now be understood that the transmitted signal consists essentially of two different parts, a high and a low frequency content.

Fig. 3 gives a representation of the high frequency signal generated by the transmitter. In the case of the London Home Service, the frequency is 908000 cycles.

When referring to a high frequency signal on the medium or long wave-band it is usual to express the frequency in thousands of cycles, thus 908000 cycles becomes 908 kilo-cycles, which in turn may be abbreviated to 908 k/cs. It might at first be thought that by adding the low frequency or L.F. signal to the high frequency or H.F. carrier a form such as in Fig. 4 would result, such a combination is useless, and, so that the original L.F. content can be satisfactorily extracted by the receiver, the L.F. signal must vary the amplitude or output power of the H.F. signal as in Fig. 5.

It is in this form that the signal arrives at the receiving aerial. The aerial in itself is incapable of discriminating between one signal and another, and countless signals will be collected by the aerial at any one time. Many of these are too weak to be of use but the stronger ones must be sorted out since there is no point in receiving several programmes at once.

Fig. 6 shows the basic circuit of the input to a crystal. The coil L possesses a quality known as inductance, and the capacitor C, that of capacitance. If the coil had no capacitance whatever across it, all signals arriving at the aerial would be effectively short circuited to earth. As a matter of interest, it is impossible to obtain this state of affairs since even without any additional capacitor any coil **must** contain a certain amount of self capacitance.

By combining a coil and capacitor as in Fig. 6 a peculiar effect is observed, at one particular frequency, the signals are not short circuited to earth, but are developed across the coil. In other words the combined effect of L and C no longer provides a short circuit, **but only at one particular frequency.** If the value of C is altered the effect will be observed at a different frequency; likewise by altering L the frequency at which the effect will take place can be changed. There is a name for this phenomena, the frequency at which it occurs with any given L and C combination is known as the **resonant frequency.**

The values of the coils and capacitors shown in this manual have been carefully chosen so that resonance will be obtained at all frequencies where stations are broadcasting. Broadcasting stations work in bands of frequencies, those of major interest to crystal set constructors are the medium wave-band 1200 k/cs—600 k/cs and the long wave-band 300 kc/s—150 k/cs.

Usually a variable capacitor is used with a fixed inductance to cover one band and an additional coil switched in to increase the inductance to cover the other. In this way the L and C combination can be adjusted to provide resonance at the desired frequency of any given station. In other words you can **select** the station you want by varying C, that is turning the dial of the variable capacitor. This procedure is referred to as tuning. Having selected or tuned the required station it still remains necessary to change the form of the signal back to that of the original transmission. This process is called detection or de-modulation.

Examination of Fig. 5 will show that the signal has been duplicated, in other words, as it rises in one direction it also rises equally in the other. In this form the signal is useless since each half of the signal cancels the other, and if this signal is applied to a pair of headphones silence will result. Obviously some provision must be made to get rid of the unwanted half of the signal, and it is here that the crystal detector must be considered. This device will pass current in one direction only, ignoring any signal in the opposite direction, so that if the signal of Fig. 5 is passed through such a crystal, that of Fig. 7 will result. There is still the H.F. content to be reckoned



FIG 5



FIG 6



FIG 7



FIG 8

with, fortunately this is easily dealt with, a capacitor connected across the headphone terminals effectively disposes of this, leaving only the audio or L.F. content, as shown in Fig. 8. This audio content, which is a faithful replica of the original transmission is fed to the headphones. These in turn reverse the process of the microphone and transform the electrical currents into sound waves acceptable to the human ear.

Briefly then, your requirements are as follows:—

(1) A good aerial and earth installation, to make the most of the available signals.
(2) A receiver containing:—
    (a) Some form of coil and capacitor (L & C) combination to select or tune in the wanted station.
    (b) A crystal to get rid of the unwanted half of the signal (detection).
    (c) A fixed capacitor across the headphones to get rid of any remaining carrier.
(3) A pair of sensitive high resistance headphones.

Aerials

By this time the intending constructor will be able to appreciate the necessity of a good aerial. It is a point which cannot be over-emphasised. Assuming that you are in the fortunate position of being able to erect an outdoor aerial there are two main considerations, height and length.

One of the best that can be used is the inverted L shown diagramatically in Fig. 9.

It should be erected as high as is practical, every foot counts. The horizontal wire, that is the aerial proper, should have a minimum length of 60′ to which of course the length of the down lead is added. Where it is impossible to erect an aerial with an ideal horizontal length, a compromise must be effected.

Fig. 10 shows a three wire spreader aerial which gives quite a good effective length.

Suitable wire for a receiving aerial will not set any problems, stranded copper about 7/22 gauge is the best. 7/22 means that it consists of 7 strands of 22-gauge wire. This wire may be obtained covered, and for the present purpose is better than the plain or enamelled kind.

Note that insulators are used between the actual aerial wire and its anchoring supports, it is important that these are used, otherwise leakage will occur which will of course spoil its efficiency. Fig. 11 and 12 show how the wire may best be attached to two of the most common types of insulator available. Fig. 11 is of porcelain and is usually referred to as an egg insulator, whereas Fig. 12 shows a more modern (and more expensive) type in glass. If you are using the glass pattern, one is usually sufficient at each end of the aerial, but with the egg type two should be used. No doubt many readers will not be in a position to erect an out-door aerial, and must necessarily be content with an indoor installation.

The next best thing to a good out-door aerial is a replica constructed in a loft. If this form of construction is used, care must be taken when feeding the down lead to avoid close contact with the wall of the house. At the point where the lead feeds under the eaves, a length of rubber tubing can be used to cover the wire. The lead is fed through one of the small spaces left for ventilation purposes. A general idea is given by Fig. 13.

A less elaborate but quite effective aerial can be obtained by using a bed-spring. A length of 7/22 copper insulated wire is connected between the receiver and the spring. The spring should first be cleaned with emery cloth. Remove about 2″ of insulation from the wire and bind it tightly round the prepared spring. The joint may be covered with insulating tape which is obtainable from all electrical stores for a few pence.

Such aerials are quite popular since so many crystal sets are built for bedroom use.

When an aerial is required in the living room, the picture rail can be conveniently used. Insulated screw-eyes are fixed at intervals of about 3 feet along the rail, the wire is firmly anchored to one of them, and stretched right round the room until you arrive back at the starting point. By use of one of the insulated screw-eyes, the wire is secured and the down lead fed to the receiver. The idea is illustrated in Fig. 14.

Soldering

Before leaving the subject of aerials, a few words on soldering will not come amiss. Down leads on outdoor aerials should be soldered, and the same applies to loft types. Apart from aerial leads; earth leads and all the connections in the receiver will require soldering.

For the type of soldering necessary in radio construction an electric iron is the best solution. One of the small types marketed by Adcola or Henleys will be found admirable for the job. These are excellent for actual set construction but are hardly large enough for soldering the down lead to an outdoor type of aerial. Here the heat is dissipated much more quickly and a larger iron is required in order to get the solder to flow.

Ordinary irons which may be heated by a gas flame can be obtained very cheaply from most ironmongers' stores. Assuming the use of such an iron, first heat the iron until the copper bit is giving off a green coloured flame, the iron is now at the correct operating temperature. The bit is now discoloured or oxidised and its tip

✓


60'
INSULATORS
TO RECEIVER

INVERTED 'L' AERIAL

FIG. 9


START
30'-40'
FINISH
INSULATORS
WOODEN SPACING POLES APPROX. 4' LONG.
TO RECEIVER

'SPREADER' AERIAL

FIG. 10


AERIAL
INSULATOR
TO RECEIVER
SUPPORTING WIRE OR ROPE.

METHOD OF FITTING PORCELAIN INSULATOR

FIG. 11


INSULATOR
SUPPORTING WIRE
AERIAL
TO RECEIVER

METHOD OF FITTING GLASS TYPE INSULATOR.

FIG. 12


FIT LENGTH OF RUBBER TUBING OVER AERIAL HERE
AERIAL
INSULATOR
TO RECEIVER

LOFT AERIAL.

FIG. 13


INSULATED SCREW EYES.
START
FINISH
TO RECEIVER

'PICTURE RAIL AERIAL.'

FIG. 14

should be quickly cleaned with an **old** file which should be kept specially for the purpose. A better idea is to obtain a small block of sal-ammoniac and rub the tip of the hot iron on it. This will clean the tip of the bit perfectly. Next take a length of cored solder such as Ersin Multicore, and melt a little on to the prepared tip faces, now smooth it evenly over the surface with a piece of old rag (be very careful not to burn your fingers) the iron is now "tinned" and ready for use. When heating the iron, be very careful not to let the bit overheat or get red hot, otherwise the tinned surface will be destroyed and the whole process will have to be gone through again.

An electric iron will not overheat, and the tinning will last much longer than with ordinary types, and since the heat does not deteriorate there is less likelihood of making faulty joints.

Having obtained a tinned iron, the process of soldering joints is remarkably simple and anyone with a little patience can acquire the art in a very short time.

To solder two copper wires together: clean the wire with emery cloth, apply a prepared iron and some cored solder to it, the solder will flow evenly over the wire thus tinning it. Repeat the process with the remaining wire and then twist the two together. Now apply the iron to the joint from the underside and the cored solder to the joint on top. Solder will flow evenly over the joint. Remove both iron and solder and allow to set. The solder will harden or set in a few seconds but during this period the joint must not be touched or moved, as otherwise the joint will be "dry" and quite useless mechanically or electrically. On radio components, tags for soldering are already tinned though if they are old, or discoloured it is best to re-tin them. Normally, however, it is only necessary to twist the connecting wire to it and apply the iron and solder as explained.

Remember: **never** apply the solder to the iron and then the iron to the joint, always apply the iron **and** the solder to the joint. It is however a good thing to apply a little solder to the iron tip even when it is perfectly tinned just before making a new joint.

One final "DON'T," you will have noticed that the solder referred to is "cored," that is, it contains resin and other substances through its centre, plain solder as used by electricians and plumbers will not do, as it is the resin or flux


EARTH LEAD
COPPER EARTH TUBE
SOIL
COKE & SOOT MIXTURE.
A
EARTH LEAD
COKE
SOIL
PERFORATED TIN CONTAINING MIXTURE OF SAL AMMONIAC & COKE
B
EARTH LEAD
SOIL
PERFORATED TIN CONTAINING SAL AMMONIAC.
C

FIG. 15.

as it is called which makes the solder flow evenly and permits a good electrical joint.

Equally important do not attempt to use a separate flux or soldering fluid with plain solder or to "help" the cored solder; since these are almost certain to cause eventual corrosion and will destroy any components that have been contaminated.

Earths

The provision of a good earth is just as important as the rest of the installation.

Much disappointment would be avoided if this fact were not lost sight of, to avoid any slip up in this direction I am proposing to outline several well tried and efficient earth systems.

If it can be obtained, an earth rod, specially designed for the purpose provides the basis of a good earth connection. These were very popular some years ago when the majority of receivers were either crystal or battery operated, but in these days of modern mains driven sets they are not often used and consequently not always readily available.

Fig. 15 shows how it is used. First excavate a hole to a depth of three feet and fill with a mixture of soot and coke. Drive in the earth rod, which is a hollow copper tube, perforated. The lead to the receiver is connected at the top, and should be of covered 7/22 gauge, as used for the aerial system. Though not obvious it is important that this lead-in should be in covered wire, otherwise a number of indifferent earth contacts are likely to be made at various points along its length until it reaches the set. This is very undesirable and will spoil the efficiency of the system. It is essential to keep the soil surrounding the rod moist, which is one reason why the tube is hollow, and care must be taken to pour water into the tube at intervals.

A very efficient earth is the percolative type also popular at one time. Due to the chemicals used, it will extract moisture from its surroundings, thus maintaining a permanently moist earth.

It should be installed as in Fig. 15b.

The container is of copper or zinc, anything else will quickly rust away, again a good quantity of coke is used. Fill the container with a mixture of sal-ammoniac and coke, and then bury in coke as illustrated. This earth will not require further attention. It is possible to use powdered calcium chloride instead of sal-ammoniac but unless a chemist can be persuaded to make some up it is better to stick to sal-ammoniac.

If a zinc container is not available and you do not use or cannot easily get coke, Fig. 15c should be used. This makes a better earth than many so-called "earths" that I have come across. Obtain as large a tin as possible, make a number of holes as shown. Solder the lead in the bottom and fill it with sal-ammoniac. Replace the lid and bury in the ground. The tin will eventually rust away, but the replacement cost is negligible.

If it is quite impossible to make direct contact with the ground, a water pipe must be pressed into service. This should be a main pipe feeding straight to ground and not a hot water pipe or one fed from a tank. Scrape the pipe clean and twist the lead in tightly around it, a copper clip is even better. Do not attempt to solder on to the water pipe; since cold water is flowing through the pipe, it is extremely unlikely that your soldering iron will heat up the water supply sufficiently to allow a sound electrical joint, though you may spring a leak.

No attempt should be made to utilise gas pipes; the possibility of causing a fire is certainly very remote but, they make incredibly bad earth connections due to a number of joints made before true ground is reached. These joints are at best only semi-conductors, at least from an electrical standpoint.

Headphones

Since the late war there have been a large number of head-phone sets available on the surplus market. These may be roughly divided into two types, high-impedance and low-impedance. For the crystal sets detailed in this book high-impedance 'phones are required and the low-impedance pattern will not be suitable unless a matching transformer is used. As this is likely to cost more than the rest of the installation including the set, it will be as well to avoid them.

High-impedance types have an impedance of 2000Ω to 4000Ω whereas the low-impedance types are usually 600Ω.

The remaining consideration is weight; often cheap headphones are very heavy and uncomfortable to wear, every endeavour should be made to obtain 'phones as light in weight as possible.

Crystals

All the sets shown in this book have been designed to work with modern germanium crystals rather than the older galena crystal.

These germanium crystals require no adjustment, which, in itself, removes the main objection to this class of receiver. Suitable crystals are available from the following manufacturers and on the surplus market: Mullard, G.E.C., Brimar, Westinghouse and B.T.H. They are of robust construction, some in glass, others in ceramic or plastic, but must not be subjected to heavy knocks, otherwise the contact point may become dislodged.

From the information given, you should now be able to install an excellent aerial and earth system, and have some idea of how the crystal set works, so it is time to pass on to the actual receiver construction.

CONSTRUCTION 1

If you examine the following circuits you will find that each one is different. In most cases the difference lies in the coil design and/or the method by which the crystal and aerial is tapped into it. Each of these circuits has its own particular advantage to suit different conditions and the ideal circuit in some localities is not necessarily the best in others. It is not just a matter of a given circuit giving louder results than another, if it were there would be no point in showing more than one.

The main problem is to obtain adequate selectivity without reducing the volume level.

A receiver is said to be selective when it tunes sharply, a set with poor selectivity allows the stations to spread over the dial and when used near a transmitter will receive the local stations mixed together, which of course is useless.

Consider Fig. 16a, this is a very simple receiver, with no special attempt to provide any great amount of selectivity. In areas where signal



FIG. 16a



LID SHOWN BROKEN AWAY TO REVEAL POSITION OF COMPONENTS.

FIG 16b

strength is not high, or a short aerial is used, it will probably be ideal.

It would have been quite easy to increase the selectivity by providing a tap on the coil for the aerial as in Fig. 17a, but unfortunately, as the selectivity is increased overall volume is likely to decrease, so that unless you live close enough to the transmitter to have a large signal available and therefore need the selectivity, the circuit of Fig. 16a will be quite satisfactory.

Capacitor C1 is to prevent the aerial damping the circuit too heavily because this would flatten the tuning unnecessarily, however with small aerials it may be better to take the aerial direct to the black tag on L1. The signals are selected or tuned by L1 and C2, X1 is the crystal and C3 the capacitor across the 'phones to prevent unwanted carrier or R.F. reaching the 'phones.

A practical diagram (Fig. 16b) is provided showing the layout and all the wiring. You will require nuts and bolts to fix the coil, about ½", 4BA size will do, the other parts have locking nuts provided. An old 2-oz. tobacco tin makes a very good container and keeps the size down. Note that the metal box is connected to earth. With the exception of AC/DC receivers the metal work on any receiver or amplifier is connected to earth.

When S1 is open as in the diagram, the set will tune in long-wave stations, but when closed the medium wave-band will be received.

Components List, Fig. 16a

C1	100pF mica capacitor.
C2	500pF tuning capacitor, solid dielectric.
C3	1000pF mica capacitor.
X1	Germanium crystal.
L1	Crystal Set Coil. R.E.P.
S1	Single Pole toggle switch.
4	Insulated wander-plug sockets and plugs.
1	2-oz. tobacco tin (or similar container).

Make sure that the wander-plug sockets are of the insulated type, otherwise the metal case will join all the sockets together electrically.

Try to follow the theoretical diagram when wiring, a little practice will soon enable you to wire up a set without a practical diagram, which is a great advantage because often only the theoretical diagram is given when circuits are detailed in the technical press.

Fig 28 on page 34 gives a list of symbols used on the theoretical diagrams, so that you can readily identify the components.

2

Fig. 17a circuit is similar in many respects to that of Fig. 16a. The difference is purely one of selectivity, tuning will certainly be sharper, and even with comparatively inefficient aerials the design will put up a very good performance. There is no reason why the construction should not follow the same lines as the previous receiver but, by enlarging the set a little and using an air spaced tuning capacitor, the efficiency is improved. Observe that the colour coding on the coil, an R.E.P. Dual Range (Blue Box) is different from that of the Crystal set coil used on the previous design, and make sure it is correctly wired in.

C1 is a mica compression capacitor, often referred to as a "trimmer" and because it is adjustable, permits the set to be matched to aerials of varying lengths. Construction is carried out on a square panel of bakelite, perspex or wood, as shown in Fig. 17b. Perspex being clear like glass presents a most attractive finish, provided the set is neatly wired. It must be drilled slowly, however, otherwise the generated heat of the drill will make the hole wander, and spoil the panel.

After the set has been wired and tested a small wooden container can be made to house the completed set.

When carrying out reception tests, a little experiment is well worth while, to get the best out of the set. Try removing the germanium crystal from the green tag on L1 and connecting it to yellow, at the same time removing the lead from C1 to yellow and connecting it to green. Once the best arrangement has been found the wiring



FIG. 17a

can be left permanently in that position. Note that two tags on the coil are unused, this is intentional because on this circuit the extra winding connected to these tags is not required. With the switch S1 closed, the coil will cover the medium wave-band, and when open, long wave stations can be received. It is customary to abbreviate the expression medium wave-band to M.W. and long wave-band to L.W.

Components List, Fig. 17a

C1	100pF mica trimmer capacitor.
C2	500pF variable capacitor (air spaced).
C3	1000pF mica capacitor.
L1	Dual Range Coil R.E.P. (Blue Box).
S1	Single Pole toggle switch.
X1	Germanium Crystal.
4	Terminals or wander-plugs and sockets.
	Perspex, bakelite or wood for mounting panel.



FIG. 17b

3

The design shown in Fig. 18a and 18b is more flexible than either of the preceding sets. That is, it can be varied to suit local conditions to a greater extent than the first two sets. This is made possible by the large number of taps provided on the coil.

You will notice that in this instance the coil is home-constructed on a cardboard former and is much larger than commercially produced coils. Coils wound in this manner are called **solenoids**, the turns are wound on side by side; in this case to a depth of some three inches. The diameter of the coil is made purposely large so as to obtain high efficiency. Modern commercial coils are invariably wave-wound and quite often are litzendraht which is the German for litz wire. This wire is made up of a number of strands of fine copper wire, each strand is enamelled to insulate it from the others, the whole is then silk covered. Litzendraht is more efficient than solid copper wire, and by using this and wave-winding, manufacturers can produce an efficient coil which is also small. Unfortunately wave-wound coils cannot be produced without a complex winding machine and home-constructed coils must take the solenoid form. It would be possible to use litzendraht but it is not easy to obtain by the reel, it is most expensive, and is difficult to handle. This last point is because at termination points, each strand must be cleaned of its enamel before a joint is made, and if one strand is broken, its advantage over plain copper wire is lost. How-



60 TURNS 24 D.C.C. TAPPED EVERY 10 TURNS.

DETAILS OF COIL.

INSET SHOWING METHOD OF TAPPING COIL.

FIG. 18 a

ever, by using a former of reasonably large dimensions an efficient coil can be produced cheaply using ordinary copper wire.

The wire must be firmly secured at the start and finish of the windings. Pierce three small holes about ¼" apart ½" from the end of the former. Pass the wire through the first from the outside, return it through the second and pass it back again through the third. Leave some 6" of wire at the end to make off the connection. It will now be possible to wind the turns on tightly without wire slipping.

Count on ten turns and make a loop 1" long. The method of preparing loops is shown in Fig. 18a, loops or taps should always be made in this manner, never by baring the wire and soldering a further length of wire to it. Carry on with the winding, making off the taps every ten turns as directed until the coil is complete.

Construction is carried out on a wooden baseboard and front panel. Secure the coil to the base-board as shown on Fig. 18b, mount the remaining components and proceed with the wiring.

When testing out, it will be found that the further the aerial is tapped down the coil towards the earth end, the greater the selectivity. A position should be found which permits separation of local stations without excessive loss of sensitivity.

The crystal tap is adjusted for best results and different settings of C1 tried out, when choosing the best position for the aerial tap.

Components List, Fig. 18a

C1	450pF padder.
C2	500pF variable capacitor.
C3	1000pF mica capacitor.
L1	See text and Fig. 18a.
X1	Germanium Crystal.
2	Crocodile Clips (to connect leads to coil taps).
4	Wander-plugs and sockets.



METHOD OF FIXING COIL

VIEW ON FRONT PANEL

FIG. 18 b

4

A most unusual design is reproduced in Fig. 19a.

It first appeared in America about three years ago, and it certainly does offer some advantage over more conventional sets. The tuning circuits are duplicated and two crystals are used, so the circuit may be described as a full-wave receiver. Signals received will certainly be louder than with simple sets, but care must be taken with the coil winding, as with the other receivers using home-made coils, otherwise results will be disappointing. Be very careful to ensure that all three windings are in the same direction, this is very important.

The distance between each winding should be ⅛". After the coil has been wound it is a good plan to warm it before a fire and paint the windings with "Durafix." Heating the coils makes the "Durafix" run freely. This substance sets quite hard and there will be no risk of the windings loosening. A small quantity of enamelled wire will cover the requirements of this coil, a 2 oz. reel will provide more than sufficient.

Before wiring in the germanium crystals, examine them carefully, note that one end is coloured red or in some cases marked with a positive sign thus +. You will notice, the sign is the same as the addition symbol used in arithmetic.

It is essential that both the red or positive ends are connected together, note that this is clearly marked on Fig. 19b. The receiver cannot work if



DETAILS OF COIL.

ALL COILS WOUND IN SAME DIRECTION.

FORMER CAN BE BAKELITE, OR WAXED CARDBOARD TUBE.

FIG. 19a

one of the crystals is connected the reverse way round.

A baseboard and panel form of assembly is used for this set which looks quite attractive if housed in a small polished cabinet. Dimensions are not at all critical but Fig. 19b gives a general idea of the layout that should be used. To avoid any unnecessary losses the coil should be mounted on perspex.

Obtain two strips of perspex 5½" long by ½" wide, drill fixing holes at both ends of each strip. It is best to clamp the two together when drilling these holes. Place one strip on the board in position, then put the coil and remaining strip over the first one and screw down. The coil will be clamped neatly and rigidly into position.

Twin socket bakelite strips are used to carry the aerial/earth and 'phone connections, if desired terminals mounted on pieces of bakelite could be used. These socket strips can be purchased from most shops selling components. If feet are not provided, drill two holes and screw into the edge of the base-board. Tag-strips are used to anchor some of the wires from the coil, and the germanium crystals. These also can be purchased for a few pence. At least two tags are necessary on one, and three on the other, though if the strips have more tags than required it is of no consequence. C3-C4, the ganged tuning capacitors have trimmers fitted, this should be stipulated when purchasing, and when first operating the set these small trimming capacitances are set about half-way. The idea of these trimmers is, that they compensate for any difference between the self-capacity of the tuning coils. With the switch S.1 open, that is in the OFF position, turn


C1
3
S1
'PHONES
E
A
C1
C3
C2
TO FIXED VANES ON C1
TO MOVING VANES ON C1
C4
3
4
1
2
5
6
X1
X2
1
'PHONES
RED
E.
A.

FIG. 19 b

✓

in a station at the high-frequency end of the band, that is with the vanes of C3-C4 towards the disengaged position. Adjust C1 for maximum volume, without interference from other stations. Now adjust the trimmers for loudest headphone strength. It may be necessary to run over the adjustments several times for best results. Once they are correctly set, the trimmers require no further adjustment. The tuning coil covers the M.W. band, 1500 kc/s. to 600 kc/s., as the capacitor C3-C4 is advanced and the vanes start to mesh, the frequency to which the receiver tunes **decreases** so that with the vanes disengaged the set is tuned to 1500 kc/s. approximately and at full mesh, 600 kc/s. Switch S1 is used as follows, for stations **lower** in frequency than 850 kc/s it should be in the ON position with the contact closed, but for stations **higher** in frequency, it is in the OFF position. As an example both the London Home Service and London Light Programme transmitters on the M.W. band operate at a higher frequency than 850 kc/s. If any doubt exists as to the operating frequency of a given station, reference should be made to the Radio Times which quotes both wave-lengths and frequency. If you know the wave-length in metres, it is simple to find the frequency. Divide 300,000 by the wave-length in metres, the dividend equals the frequency in kilocycles, i.e., 300,000 ÷ 300 metres=1,000 kc/s. In the same way, dividing 300,000 by the frequency in kilocycles will produce the wave-length in metres.

To use the receiver, tune in the signal by C3-C4, adjust C1 for maximum volume without allowing stations to overlap.

Components List, Fig. 19a

C1	300pF solid dielectric variable capacitor.
C2	1000pF mica capacitor.
C3-4	500pF twin gang variable capacitor.
L1-2-3	See text and Fig. 19a.
X1-2	Germanium Crystal.
2	Tag-strips.
2	Twin socket strips.
S1	Single Pole toggle switch.

5

Whenever crystal sets are discussed, constructors are apt to think in terms of medium-wave reception. When you consider that at least 98% of published circuits are designed for this band (sometimes with the long-wave band thrown in as an afterthought) it is understandable. However, if you can provide a good outdoor aerial (and an equally good earth) there is a lot of fun to be had listening to the short-wave bands. This receiver is designed specially for short-wave reception.

A metal chassis is used for construction, these can be obtained ready made in aluminium from most good supply houses. It can be quite small and on the original model a 6″ x 4″ was used. Low loss components are used so as to obtain greatest efficiency on the short wave bands. The coil is a commercial product which plugs into a 4-pin base. Best results were obtained on the 3mc/s to 7mc/s band though coils covering other bands are available.

Note that the tuning capacitor C1 is smaller than normally used and has a maximum capacitance of 140pF.

Coil type 706/R covers the 3mc/s to 7mc/s band, but the set is equally satisfactory on the M.W. band, and to cover this coil type 706P should be used. This coil has an iron dustcore which can be adjusted to make the coil cover the required band. The effect of the core is as if turns were being added or removed from an ordinary coil. When dealing with the short waves it is customary to refer to the frequencies in terms of mega-cycles (mc/s) rather than kilo-cycles. One mega-cycle is equivalent to 1000 kilo-cycles, that is 1,000,000 cycles.

Layout and wiring can be clearly followed from Fig. 20b and a theoretical diagram is shown in Fig. 20a. Care should be taken when arranging a mounting for the aerial terminal. The best plan is to cut a 1″ hole in the chassis, mount the aerial terminal on a piece of perspex and screw into the chassis. This avoids any unnecessary losses between aerial and chassis. The earth terminal is screwed directly into the chassis.



FIG. 20 a



FIG. 20 b

Wiring as shown in Fig. 20a is likely to give the best results, but other arrangements are possible and to get the best out of the set they should be tried.

Refer to Fig. 20a. The aerial is connected to pin 3 on L1, C1 to pin 2 and X1 the crystal to pin 4. If you have a long aerial try this combination—Aerial to pin 4, C1 to pin 2, and the crystal to pin 3. Connections to pin 1 are not altered. In a few cases the following arrangement may prove best. Crystal and C1 to pin 2, aerial to pin 3, pin 4 left free and again pin 1 is unaltered.

Tuning on the short-wave bands is more critical than on the medium waves so tune very slowly over the band and remember signal strength is likely to vary from day to day.

Components List, Fig. 20a

C1	140pF variable capacitor Eddystone 586.
C2	1000pF mica capacitor.
1	Coil holder Eddystone 707.
L1	3m/c—7m/c coil Eddystone 706/R.
1	Engraved tuning dial.
1	6"x4"x2½" chassis.
2	Terminals (Aerial-Earth).
1	Twin socket strip ('phones).
X1	Germanium Crystal.

6

Fig. 21a-b is yet another design from America and appeared in Radio Craft some years ago, designed by Mr. W. J. Spain. The original used a silicon crystal which preceded the development of the germanium. Results are certainly very good though of course on the model built here, a germanium crystal was used. Selectivity can be adjusted to suit all conditions and even at short distances from local stations. Good volume can be obtained without the programmes overlapping. Home made coils are used and for best results a 75′ outdoor aerial is desirable.

Baseboard and panel construction is used, which can conveniently be housed in a small wooden cabinet.

Operation is a little more complicated than some of the other designs, but the results certainly merit the extra trouble taken. As with the other receivers much of the success obtainable is due to the coils and these must be carefully made otherwise results will be disappointing.

Layout and wiring can be followed quite easily from Fig. 21b and requires no special comment.

First make the coils. L1 is a tapped coil, the taps should be made in the same way as shown in Fig. 18b. It consists of 90 turns of 22 D.C.C. (double cotton covered) copper wire tapped at the following number of turns, 5, 10, 15, 25, 30, 40, 50, 60, 70 and 80. The former used has a diameter of 2". L2 is also wound on a 2" diameter former, this coil however is not tapped, it consists of 110 turns of 38 D.C.C. or enamelled copper wire. Great care must be taken when handling this wire, it is quite fine and in the hands of the inexperienced will easily break.

After wiring has been carried out the set can be put into operation.

Selectivity is controlled by S2, in position B tuning is broad but in position A it can be quite sharp.

When searching for a station switch S2 to B. Tune the station and switch S2 to A. The frequency range is controlled by the position of the tap on L1, a good plan is to start with the 5 turn tap on L1.

Components List, Fig. 21a

C1	500pF variable capacitor.
C2	500pF variable capacitor.
C3	1000pF Mica Capacitor.
X1	Germanium Crystal.
L1 & L2	See text.
S1	Single Pole toggle switch.
S2	Single Pole 2-way toggle switch.
2	Twin socket strips (Aerial/Earth and 'Phones).



FIG. 21 a


S1
X1
S2
B
A
RED
C 1
C 2
'PHONES
C 3
TO SUITABLE TAPPING
L2
L1
AERIAL
EARTH

FIG. 21 b

Keep S1 open and C1 for tuning, adjusting the tap on L1 for best results. Very powerful signals are best brought in with S1 closed. When using C1 and adjusting the taps on L1, switch S2 is kept in the A position.

It will be found that C2 acts as a fine control on C1. One division of the tuning dial on C1 is roughly equal to a movement of 20 divisions on C2.

Note that the coils are mounted at right angles to one another and that in this instance wood has been used as far as possible, an aluminium or other metal chassis is not suitable.

7

A very useful receiver for both medium and long-wave reception is possible with the circuit of Fig. 22a-b. A home-made coil is used. On the original a 1¼" diameter former was used but in fact this is not very critical and a 1½" former could be used. An interesting point is the construction of the long-wave coil section. Solenoid coils as used for the medium wave-band are not efficient if the length is too great relative to the diameter. Now as the long-wave section has 300 turns, if wound as a solenoid the winding length would be very great and a lot of efficiency would be lost. To overcome the difficulty the coil is pile wound. If the whole coil were to be wound in one pile it would still be inefficient because of the capacity formed in the winding, but by dividing it into five sections a coil of reasonable efficiency results. The same remarks concerning winding apply to this coil as to all the others in

Components List, Fig. 22a

C1	300pF Mica Capacitor.
C2	500pF Variable Capacitor.
C3	1000 Mica Capacitor.
X1	Germanium Crystal.
L1-2	See Text.
S1	Single Pole Toggle Switch.


C1
1
2
3
4
5
L1
L2
S1
C2
C3
X1
RED
1¼" DIA.
①
②
③
④
⑤
L1
L2
4"
L1. 112 TURNS OF 30 S.W.G., D.S.C. OR D.C.C. TAPPED AT 56 TURNS,② & 84 TURNS,③, WINDING FROM TOP OF FORMER.
L2. 300 TURNS OF 30 S.W.G. D.S.C. OR D.C.C. PILE WOUND. 60 TURNS TO EACH PILE.
DETAILS OF COIL
ALL COILS WOUND IN SAME DIRECTION.
FORMER CAN BE BAKELITE OR WAXED CARDBOARD TUBE.

FIG. 22a



FIG. 22 b

this book, and readers should not, by this time, encounter any difficulties.

The design provides good selectivity with good sensitivity, and provided the set is not required to operate within a few miles of a powerful transmitter, no trouble will be encountered from interference between adjacent stations.

A wooden base-board and front panel is best for this design, and the wiring and layout can be clearly followed from Fig. 22b. Switch S1 is open for long-wave reception and closed for the medium-wave band.

Coil mounting can be on the same principle as for the full-wave design Fig. 19a-b.

8

If you look at all the other circuits shown in this book you will find that in each case the tuning capacitor and tuning coil are in parallel, this is by no means essential and the circuit of Fig. 23a shows a series arrangement that is the tuning capacitor is between the coil and earth instead of being wired up across it. This design also appeared in **Radio Craft** a few years ago.

An interesting point is that the coil is a conversion adapted from another type of component. To make this coil you must obtain an old I.F. transformer as used in superheterodyne receivers.

You will require one designed to work anywhere between 450 and 470 kc/s. Some of the very early ones worked at 110 kcs/ but these are unsuitable.

The I.F. transformer must also be of the type tuned by an iron dust core at each end.

Dismantle the transformer, remove the parallel capacitors and mounting wires so that you are left with two coil bobbins and their former. Be very careful when un-soldering the wires from the supports because the coils are usually wound in litzendraht and must remain intact. Remove 25% (approximately) of the turns from one coil which we will call the secondary, and completely remove the iron dust slug from this coil, now cut the former in half, and mount as in Fig. 23a. Warm the coils with heat from your soldering iron or from a fire and gently slide the coils into position at the ends of the former as in Fig. 23a. The wax will set again holding the coils in their new position.

Note that the wires from the coils are connected to tags on the mountings. These are pieces of bakelite, and usually the original end pieces used on the I.F. transformer can be used.

A word about soldering litzendraht. Do not attempt to use emery paper. Prepare the end of wire by removing the outer silk covering and dip the end in methylated spirits. Ignite with a match and after about five seconds wipe with a cloth held between finger and thumb. This will quench the flame and will remove all traces of enamel from the wire. It is a good plan to experiment with the odd length of wire removed from the secondary coil. If the coils prove to be constructed of ordinary copper wire, it can of course be prepared with fine emery cloth in the normal manner.

Components List, Fig. 23a

C1	500pF variable capacitor.
X1	Germanium Crystal.
L1	See Text.
4	Plugs and sockets or terminals.

Wiring is straight forward as can be seen from Fig. 23b and requires no explanation.

Operation is as follows, selectivity is controlled by varying the distance between coils with the wing nut, and to an extent by the position of the primary iron dust core. Remember that the aerial and earth installations are as important with this set as with any other crystal receiver. No parallel capacitance appears necessary across the 'phones, the set works quite happily relying on the self-capacitance of the head-phones.



FIG. 23 a


TUNING CONTROL
C1
SEC.
PRI.
RED
X1
PHONES
AERIAL
EARTH
SELECTIVITY CONTROL
— FRONT VIEW —

FIG. 23 b

9

So as to give a truly varied selection of circuits, some of the sets have been designed around commercial coils whilst others use coils which must be home-constructed.


C1
GREEN
X1
L3
YELLOW
RED
MED
BLUE
LONG
RED
C2
L1
L2
C3
MAUVE
BLACK

FIG. 24 a

Most enthusiasts like to build their own coils but when it is a question of something really small combined with efficiency a commercial coil is the obvious choice.

Fig. 24a-b uses a tobacco tin or a similar container just as the design shown in Fig. 16a.

This receiver however is a little more selective and is more suitable than the earlier design, if you are near a transmitter or have a very long aerial. Take great care to connect the coil according to the colours shown on the diagrams. Sockets are used for wave-changing, this cheapens the cost a little and they are just as efficient.

Components List, Fig. 24a

C1	100pF Mica capacitor.
C2	500pF variable capacitor solid dielectric.
C3	1000pF Mica capacitor.
X1	Germanium crystal.
L1-2	R.E.P. dual range coil. Blue box.
6	Insulated wander-plug sockets.
5	Wander Plugs.
2oz.	Tobacco tin or similar container.



LID SHOWN BROKEN AWAY TO REVEAL POSITION OF COMPONENTS.

FIG. 24 b

10

In certain cases, signals from the local transmitter are too powerful to permit a crystal set with a normal coil to be of much use. I myself live in Hertfordshire a few miles from the London transmitters, and find a more elaborate circuit is necessary. Now in radio circles it is a well-known fact that the greater the number of tuned circuits, the greater the overall selectivity. Look at Fig. 25a, you will see that the usual L and C tuning arrangements have been duplicated. This type of circuit is known as a Band-Pass Filter. There are many kinds of such filters, this particular type is an inductively-coupled filter, note that energy from the first half (L2) is conveyed to L3 by way of two small inductors L1 and L4.

Tuning is quite sharp and the "feel" of the set is quite different from that of single coil designs. A small chassis is ideal for construction. 6"x4"x2½" was used on the original, though it could have been smaller.

Fig. 25b gives the layout and wiring.

Take particular notice that L1-2-3 is mounted horizontally and at right angles to L4-5-6, this is to prevent the coupling from being too "tight" which would ruin the idea of the filter. A good aerial and earth is of course necessary. It may be found on test that the selectivity is too great



FIG. 25 a.

and that volume has suffered. This can be ingeniously overcome by connecting a very small capacitance between the two Green tags on the coils. The simplest way is to connect it across the fixed vane connections on C2-C3. Values for this extra capacitance are a matter for experiment usually a value between 10pF and 47pF is sufficient. A small 50pF trimmer could be used and adjusted to suit. The ideal setting is to enable powerful adjacent stations to be received just short of overlap so that as much volume as possible is obtained.

There is one point to be observed with the ganged capacitor. It should be of the type fitted with trimmers though of course, there is no reason why you should not fit them yourself. These are to allow for differences between coils to be balanced out, and consist of a small variable capacitance across each main section.

When setting up the receiver, first set each trimmer at half way and tune in a station near the high-frequency end of the band (vanes nearly out) adjust the trimmers for maximum volume. If extra coupling capacity is added as described, try adjusting them further.

Once properly set up, no further adjustment is necessary.

Components List, Fig. 25a

C1	100pF Mica capacitor.
C2-3	2 x 500pF variable capacitor (see text).
C4	1000pF Mica capacitor.
L1-2-3	Dual Range Coil R.E.P. (Blue Box).
L4-5-6	Dual Range Coil R.E.P. (Blue Box).
X1	Germanium Crystal.
S1a-b	2 pole single throw toggle switch.
4	Terminals or plugs and sockets.


TUNING CONTROL
AERIAL
EARTH
WAVECHANGE SWITCH
'PHONES

FRONT OF COMPLETED RECEIVER.


MOVING VANES
C2 & C3
EARTH
AERIAL
C4
'PHONES
RED
X1
TO FIXED VANES ON C3
TO FIXED VANES ON C2
BLUE
YEL
BLACK
L 4,5,6.
GREEN
RED
MAUVE
S1a & b
C1
BLK
MAUVE
RED
L1,2,3.
BLUE
YELLOW
GREEN

EXPLODED UNDER-CHASSIS VIEW

FIG. 25 b

11

Another band-pass circuit is shown in Fig. 26a. This time home-made coils are used. This filter is not inductively coupled but entirely capacitive, relying on C3. As in the previous circuit it must be adjusted to give just sufficient " broadness " to the tuning to provide adequate volume without station overlap. To avoid unwanted coupling a screen is mounted between the coils, this is necessary because due to the size of the coils they would be bound to couple quite tightly without it. Such precautions were not necessary with the circuit of Fig. 25a, as the commercial coils are much smaller physically and the risk of unwanted coupling reduced.

The coils for this receiver are for medium wave reception only, this keeps the size down. Coil winding procedure has already been fully explained, and covers all the requirements of these coils. Base-board and panel construction is used, and for more accurate tuning since the coils are home-made, separate tuning capacitors are recommended. Fig. 26b gives the layout and practical wiring.

Components List, Fig. 26a

C1	100pF Mica capacitor.
C2	500pF variable capacitor.
C3	50pF Mica trimmer.
C4	500pF variable capacitor.
C5	1000pF mica capacitor.
L1-2	See text.
X1	Germanium Crystal.
4	Terminals or plugs and sockets.

For those who do not wish to bother with these a ganged capacitor can be used, but tuning may not be as good as with separate ones. The screen mounted between the coils is of aluminium or copper and should be about 1" higher than the coils and the same length as the baseboard depth.



FIG. 26a


2½" DIA
2"
1
3
2
KEEP LEADS 5" LONG. CUT TO LENGTH ON CONSTRUCTION
50 TURNS OF 28 S.W.G. ENAMELLED COPPER WIRE.
CENTRE TAP

COIL DETAILS.


C4
C3
C2
TOP OF COIL
3
1
L2
SCREEN
2
3
1
L1
2
TOP OF COIL
SCREEN MADE OF ALUMINIUM OR COPPER & TO BE 3" HIGH
C1
C5
X1
RED
'PHONES
E
AE

FIG. 26 b

12

Fig. 27a-b uses a band-pass filter for tuning, and the coils are home-constructed.

With this design a ganged capacitor is quite suitable as the coils tune quite accurately. It is essential that the coupling condenser C3 is **non-inductive,** there will be no difficulty in obtaining a new component of this pattern but it is as well to avoid old components which may not employ this form of construction.

Receivers using this type of filter are used to the best advantage when situated a short distance from a powerful transmitter and if selectivity is not important this particular design is not the most suitable.

Both medium-waves and long-waves are catered for: consider L1-2-3, this is the first half of the filter.

L1 is the aerial coupling coil, with S1 closed, the medium-waves are received. This coil is inductively coupled to L2 and L3. Again with S2 open L2 and L3 combined cover the long-waves and when S2 is closed the medium waves are covered.

Tuning for this half of the filter is by means of the capacitor C1, which is one half of the ganged capacitor. A screen is erected between the two sets of coils comprising the filter, and coupling is effected by C3, an earth return for the coils is provided by R1.

L4 and L5 operated in a similar manner to L2 and L3, tuning is by means of C2, the remaining section of the ganged capacitor. You will realise that the coils must be accurately wound otherwise tuning will not remain constant between the two sections over the band.

The ganged capacitor should be fitted with trimmer capacitors when purchased so that the two circuits can be balanced.

You will have noticed that this circuit uses three sets of switch contacts. A three-pole two-way wafer switch is the best choice otherwise either two or even three separate switches are necessary. All the necessary coil details are given in the diagrams, the tap on L4 is made in the same way as shown for other coils in the manual. One other component used only on this design, is the resistor R1, its size is not important because the current flowing is so small it can be ignored.

A ¼ watt rating is adequate, its precise value is not critical so that a 20% tolerance component is quite suitable.

Resistors are coded by colours and the 1000Ω type you require will bear the following sequence. At one end will be painted three coloured rings.

Components List, Fig. 27a

C1-2	500pF 2 gang, variable capacitor.
C3	0.05mfd. non-inductive paper capacitor.
C4	1000pF mica capacitor.
R1	1000 ohm resistor.
X1	Germanium Crystal.
S1-2-3	3-pole 2-way wafer switch.
L1-2-3 & L4-5	See text.
4	Terminals (Aerial, Earth and 'Phones).
	Sheet copper or aluminium for screen.



FIG. 27a


L2-L4
58 TURNS No.30 S.W.G. ENAMELLED WIRE. CENTRE TAPPED.
L1. 75 TURNS No.36 S.W.G. ENAMELLED WIRE-PILE WOUND.
L3-L5
174 TURNS No. 36 S.W.G. ENAMELLED WIRE - WOUND IN 3 PILES OF 58 TURNS
2" DIA
3/8
3/4"
1/2"
1/8"
1/4
1/8
5/8"
3 1/4"
1
2
3
4
5
6
7
8
L2-L4
L1
L3-L5
CENTRE TAP
COIL DETAILS.
KEEP LEADS 6" LONG & CUT TO LENGTH ON CONSTRUCTION
ON COIL L4 & L5. OMIT WINDINGS 4 TO 6
MOVING VANES ON C1 & C2
S3
S2
S1
C1 & C2 GANGED
TO FIXED VANES ON C1
TO FIXED VANES ON C2
SOLDER TAG
R1
C3
SCREEN MADE OF COPPER OR ALUMINIUM & TO BE 4 1/4" HIGH.
RED
X1
C4
L4, L5.
L1, L2, L3.
'PHONES
SCREEN
AERIAL
EARTH

FIG. 27 b


VARIABLE CAPACITOR
TUNING COIL WITH TAPPINGS
CRYSTAL DETECTOR
SINGLE POLE DOUBLE THROW SWITCH
FIXED CAPACITOR
SINGLE POLE SINGLE THROW SWITCH
DOUBLE POLE SINGLE THROW SWITCH
AERIAL
EARTH
'TWO GANG' VARIABLE CAPACITOR
WIRES CONNECTED
WIRES NOT CONNECTED
'PHONES
RESISTOR
TUNING COIL.

SYMBOLS USED IN THE CIRCUITS DESCRIBED.

FIG. 28

The first one is BROWN which represents 1, the first figure of the value, the second BLACK, this indicates the second numeral is nought, and the third colour is RED which tells us that two further ciphers or noughts are added to give the total value. From this you can see, we have 1 plus a nought equalling 10, plus two further noughts which total 1000. Some earlier types of resistor were painted differently, the whole body colour represented the first figure, one tip was coloured to represent the second figure, and a painted dot in the centre gave the number of ciphers to be added.

There are no other special points regarding construction except perhaps that if a long aerial is used, a small 100pF capacitor might be tried in the aerial lead to prevent damping the first tuned circuit.

When setting up the receiver, tune to a station at the high-frequency end of the M.W. band and set the trimmers for loudest volume, no other adjustments are necessary.

CONCLUSION

The twelve receivers described are representative of the best crystal set designs available to-day. Their construction will provide many hours of useful enjoyment, and the results will give lasting pleasure.

A final word about components, if no actual maker is specified, any good class component can be used. Switches, fixed and variable capacitors and crystals, are available from numerous manufacturers all of which are invariably of excellent quality. Where a particular manufacturer's product is called for, the specification should be adhered to. The commercial coils specified are freely available from most supply houses specialising in components for constructors, but in case of difficulty write to Bernards (Publishers) Ltd., The Grampians, Western Gate, London, W.6, who will, on receipt of a S.A.E. be pleased to supply the address of your nearest stockist. Coil formers are not always easy to obtain and in this case advice should be sought from Post Radio Supplies, 395, Queensbridge Road, London, E.8, who will be pleased to help in any way possible.

* *

CHAPTER THREE

Crystal Sets

Crystal sets are simple to build and cheap! With six feet of aerial this set will pick up the BBC programmes at good strength; with fifty feet of aerial the volume is really loud. Build the set with care, remembering that reception depends entirely upon aerial and earth.

These crystal set designs are chosen as the first in our constructional series because of their simplicity and cheapness. The most popular receiver for years was the 'crystal set', the theoretical design of which was precisely the same, in effect, as that shown in Fig. 7, our first design. Those old crystal sets, however, used large coils of thick wire and detectors consisting of a piece of crystalline substance 'tickled' by a small cat's whisker, which was only a piece of thin wire wound up into a small spring. Today we use a miniature coil and a germanium diode detector.

Germanium is one of the modern metals which have been developed for industrial purposes in recent years. A small flake of it is sealed into a tiny glass tube, with its cat's-whisker contact cemented permanently into place (Fig. 6).



Figure 6 The Germanium Diode Detector

A crystal set has no power to amplify the signals which it receives via the aerial and the crystal detector merely converts the radio signals into currents capable of actuating the diaphragms of our headphones and producing sounds thereby.

It follows, therefore, that the strength of the sound we receive in the headphones depends on the size of the aerial we have – a larger aerial picking up 'bigger' signals – and the efficiency of the detector in converting them ('rectifying' them is the proper term) into 'sound' signals.

The germanium diode is much better as a detector in every way than the old crystal detector and is completely stable in use. The modern crystal set, therefore, must not be confused with that of fifty years ago; it is best to discard the term 'crystal set' really in favour of 'germanium diode receiver'. The receiver in the Fig. 7 circuit is small and compact and very simple to make. With a good aerial it will give an extremely loud headphone signal from two or, possibly, three stations. It is essential to have a good aerial with a crystal set, and a good earth as well if this is possible. In North London, I could receive both the BBC Radio 2 (Light) and Radio 4 (Home) services with about 6 feet of wire. With 50 feet of aerial in the loft I could obtain Radio 1, 2, 3 and 4, with Radio 2 and 4 at extremely loud volume. The trouble then is that it is difficult to separate Radio 2 from Radio 4, and each programme has a slight background of the other.

From this you see that on medium and long waves *small aerials mean good selectivity (i.e. power to separate stations) but small signals*, whereas large aerials give large signals but poor station separation. If you live in a country district a long way



Figure 7 Crystal Set Theoretical Diagram



Figure 8 Crystal set Wiring Diagram

Components required:
·0005 mfd. solid dielectric variable capacitor (C.2)
On-off switch
DRR2 coil (Repanco)
·0002-mfd. fixed capacitor (C,1)
Germanium diode (Osram GEX 35 or Mullard OA 81)
4 terminals or 2 double mounts
Crocodile clip
Wood, wire, etc.
Tuning knob

from a BBC transmitter, and can erect a large aerial in the open air, you will probably get good results from the simple receiver; but if you live under twenty miles from a station for best results you need a more selective set.

Firstly, then, to build the set shown theoretically in Fig. 7 with a wiring diagram in Fig. 8, you need a piece of three-ply wood about 2½ inches square. If you have a particular box or cabinet to build the set into, and this requires a slightly larger size, it does not matter at all. You must drill holes for those components which are mounted on the panel; and these are the tuning capacitor in the centre, above and below it the 'A/E' and 'phones' terminals or terminal mounts. If you use the latter, the terminals affixed to them must protrude through holes to the other side, but terminals will automatically pass their shanks through the panel. The particular coil specified has a long-wave section and this requires an 'on-off' switch to short-circuit the long-wave section of the coil when medium waves only are required. As some of the holes may be a little larger than the drill you have available, an easy way to make them is to drill them out as large as possible and then 'reamer' them to size with the tang of a file or other tool.

After mounting those parts which require fixing to the panel, the soldering-up can be started; it will be found that remaining small items can be soldered into place and held into position by the wiring. Earlier remarks on soldering and wire to use may be referred to here, particularly the importance of clean joints made with a hot iron. Avoid 'dry joints' which look good but can be pulled apart quite easily and beware of applying a hot soldering iron for too long to the tags of components. In particular, do not let the iron get too near to the diode or remain too long on its connecting wires.

When soldering to the coil, be careful that the heat of the iron does not unsolder the wires already connected to the tags. Once the wiring has been completed and checked over, the headphones may be joined to the appropriate terminals, with aerial and earth also connected to their correct points.

Headphones must be of the 'high-resistance' type, i.e. 2000 or 4000 ohms impedance. If you have a pair of headphones which are low-resistance type, or yours are marked LR or 120 ohms, you can use them by interposing a special transformer (obtainable quite cheaply) between the set and the phones. Most dealers have these transformers.

After connecting the external apparatus, make sure the switch indicates the waveband required, that is, points *short-circuited*, cutting out the long waveband, if you want to receive on medium waves, and *open* if you want the whole coil in circuit for long-wave reception. Turn the knob slowly and you should pick up the stations available. A push-pull switch may not be available but any small on-off switch will do.

The coil specified is a Repanco DRR 2 and is really a coil with a reaction winding which is normally used in a one-valve or two-valve receiver. I have specified it for the crystal set because, in accordance with our promise of progressive set-building, it can be used for the receiver described in Chapter 4. In the design as given, using the DRR 2 coil, the 'reaction' winding is wired up so that it may be used as an aperiodic aerial winding which will give you a variation in selectivity. For this reason the lead from the aerial (through C.1) terminates in a crocodile clip.

This may be attached either to 'yellow' on the coil or 'red', in order to give the best position for the aerial in use. Try also fixing the diode to 'yellow' instead of to 'fixed vanes'.



Figure 9 Crystal Set Wiring Diagram (home-made coil)

The second crystal receiver is very cheap and simple to make and uses the *BOP* coil which I first made up for use in two transistor receivers described in *Boy's Own Paper* in 1963. It is very easily wound on a ferrite rod which is 4 inches long and ¼ inch in diameter. At the end of this chapter I repeat the instructions which we gave in *BOP* for winding it. The receiver in Fig. 9 can be put together easily in any handy box and will tune medium waves only, so that if you must get your Light programme on long waves, you would do better to make the design in Fig. 8. Components for this ferrite-rod coil design should be the same as those listed below Fig. 8 except for the coil, of course, which will not be required, nor will the on-off wavechange switch or the crocodile clip. The ·0002 mfd. condenser (capacitor) will help selectivity if it is wired between the aerial terminal and centre-tap on coil. By the way, use two thicknesses of good writing paper or very thin card for making the coil. The wire should not be too close to the ferrite rod itself. You can experiment with this coil quite a lot, if you wish, by putting different windings on it. Readers have told me they have even been using it for short-wave reception in a transistor receiver by using fewer turns and adding a reaction winding. For this crystal receiver, it might be found better to use a tuning condenser of only 200 pf (i.e. ·0002 mfd.) instead of the ·0005 mfd. one specified.

If you build these crystal sets, remember that reception is *entirely* dependent upon the aerial and earth in use. If these are poor, good signals cannot be expected. *Poor signals cannot be amplified or adjusted to make them louder*. A crystal set connected to an amplifier such as the 'small high fidelity' described later makes a very satisfactory arrangement for local station reception. For 'reaching out' and for louder signals a valve detector is required. Do not take your crystal set to pieces unless you have no alternative. The next design shown in Fig. 10 uses the large home-made coil of Fig. 4.



Figure 10 Diode 'Crystal Set'

Components required:
Coil: see text (home made type)
C.1. ·0005 mfd variable capacitor
C.2. ·001 mfd fixed capacitor
Diode: any suitable of good quality
R.1.: 1000 ohm resistor
Phones, wire, wood, etc.

The crystal set shown in Fig. 10 is very simple to make. Fix your coil on a small piece of wood in the manner shown. On one side of that piece of wood fix a small panel on which are mounted the tuning capacitor and two small terminals or a socket strip for phones. Also required will be a small on-off switch for wavechanging. Connect 2 on the coil to one side of diode and fixed plates on the tuning capacitor. Other side of diode to phones. Other side of phones to 4 on coil and 4 on coil also goes to one side of on-off switch plus 6 on coil and moving plates on capacitor. Other side of on-off switch to 3 on coil. Across the phones terminals connect a ·001 mfd. capacitor and if you are using a crystal earpiece you will also need a 1kΩ resistor there. For ordinary headphones (high-resistance) no resistor is needed. The aerial can be attached to a 'crocodile' clip and tried for best results on 1, 2 or 5 on coil. Earth can be clipped to 4 or 6, or you can add two more terminals to the panel for A & E. Your set should now work well and, having fixed a small knob to the shaft of the capacitor, you can tune in the available stations.

Figures 11 and 12 are rather special crystal set designs and I am indebted to Messrs Repanco Ltd, whose copyright designs they are, for allowing me to use them here. The coil featured is the DRR2 which they make and the first circuit is for a headphone crystal receiver which uses 2 diodes and 1½ volt cell. It is rather

CHAPTER 2

Crystal Sets

Crystal sets are simple to build and *cheap! With six feet of aerial this set will pick up the BBC programmes at good strength; with fifty feet of aerial the volume is really loud. Build the set with care, remembering that reception depends* entirely *upon aerial and earth.*

THESE Crystal Set designs are chosen as the first in our constructional series because of their simplicity and cheapness. The most popular receiver for years was the 'crystal set', the theoretical design of which was precisely the same, in effect, as that shown in Fig 4, our first design. Those old crystal sets, however, used large coils of thick wire and detectors consisting of a piece of crystalline substance 'tickled' by a small cat's-whisker, which was only a piece of thin wire wound up into a small spring. To-day we use a miniature coil with a dust-iron core and a germanium diode detector.

Germanium is one of the modern metals which have been developed for industrial purposes in recent years, and is actually processed from soot-scrapings obtained from certain factory chimneys! A small flake of it is sealed into a tiny glass tube with its cat's-whisker contact cemented permanently into place (Fig. 3).

A crystal set has no power to amplify the signals which it receives via the aerial and the crystal detector merely converts the radio signals into currents capable of actuating the diaphragms of our headphones and producing sounds thereby.



Fig. 3. The Germanium Diode Detector



Fig. 4 Crystal Set Theoretical Diagram

It follows, therefore, that the strength of the sound we receive in the headphones depends on the size of the aerial we have—a larger aerial picking up 'bigger' signals—and the efficiency of the detector in converting them ('rectifying' them is the proper term) into 'sound' signals.

The germanium diode is much better as a detector in every way than the old crystal detector and is completely stable in use. The modern crystal set, therefore, must not be confused with that of thirty years ago; it is best to discard the term 'crystal set' really in favour of 'germanium diode receiver'. The receiver in Fig. 4 circuit is small and compact and very simple to make. With a good aerial it will give an extremely loud headphone signal from two or, possibly, three stations. It is essential to have a good aerial with a crystal set, and a good earth as well if this is possible. At my own home, which is ten miles from the BBC (Brookmans Park) transmitters in North London, I can receive both the BBC Home and Light service with about 6 feet of wire. With 50 feet of aerial in the loft I can obtain Home, Light and Third, the first two at extremely loud volume. The trouble then is that it is difficult to separate Home from Light, and each programme has a slight background of the other.

* * *

From this you see that on medium and long waves *small aerials mean good selectivity* (*i.e. power to separate stations*) *but small signals*, whereas large aerials give large signals but poor station separation. If you live in a country district a long way from a BBC transmitter, and can erect a large aerial in the open air, you will probably get good results from the simple receiver; but, if, like me, you live under twenty miles from a station, for best results you need the more selective set shown in our second design.

Firstly, then, to build the set shown theoretically in Fig. 4 with a wiring diagram in Fig. 5, you need a piece of three-ply wood about 2½ inches square. If you have a particular box or cabinet to build the set into, and this requires a slightly larger size, it does not matter at all. You must drill holes for those components which are mounted on the panel; and these are the tuning capacitor in the centre, above and below it the 'A/E' and 'Phones' terminals or terminal mounts. If you use the latter the terminals affixed to them must protrude through holes to the other side, but terminals will automatically pass their shanks through the panel. The particular coil specified has a long-wave section and this requires an 'on-off' switch to short-circuit the long-wave section of the coil when medium waves only are required. As some of the holes may be a little larger than the drill you have available an easy way to make them is to drill them out as large as possible and then 'reamer' them to size with the tang of a file or other tool.



Fig. 5. Crystal Set Wiring Diagram

Components required:
·0005 mfd. solid dielectric variable capacitor (C.2)
On-off switch
QCD 2 Coil (Osmor)
·0002 mfd. fixed capacitor (C.1.)
Germanium diode (Osram GEX 35 or Mullard OA 60)
4 terminals or 2 double mounts
Wood, wire, etc.
Tuning knob
For better selectivity Teletron HAX coil can be used. Connections are given with coil.

After mounting those parts which require fixing to the panel, the soldering-up can be started; it will be found that remaining small items can be soldered into place and held into position by the wiring. Earlier remarks on soldering and wire to use may be referred to here, particularly the importance of clean joints made with a hot iron. Avoid 'dry' joints which look good but can be pulled apart quite easily and beware of applying a hot soldering iron for too long to the tags of components. In particular do not let the iron get too



Fig. 6 Crystal Set Theoretical Diagram

Components required:

Midget ·0005 mfd. variable capacitor (C.3/4) dual gang
·00005 mfd. fixed capacitor (C.1)
2 Teletron Coils type BA 2
50 mmfd. (i.e., ·00005 mf.) variable trimmer (C.2)
Germanium diode (Osram GEX 35 or Mullard OA 60)
4 terminals or 2 terminal mounts
Knob or small dial

near to the diode or remain too long on its connecting wires.

When soldering to the coil be careful that the heat of the iron does not un-solder the wires already connected to the tags. Once the wiring has been completed and checked over, the headphones may be joined to the appropriate terminals, with aerial and earth also connected to their correct points.

Headphones must be of the 'high resistance' type, i.e. 2000 or 4000 ohms impedance. If you have bought a pair of Government surplus 'phones which are low-resistance type, or yours are marked LR or 120 ohms, you can use them by interposing a special transformer (obtainable quite cheaply) between the set and the 'phones. Most dealers have these transformers.

After connecting the external apparatus, make sure the switch indicates the waveband required, that is, points *short-circuited*, cutting out the long waveband, if you want to receive on medium waves, and *open* if you want the whole coil in circuit for long-wave reception. Turn the knob slowly and you should pick up the stations available.

The selective receiver in my next design is shown theoretically in Fig. 6, and fully wired in Fig. 7. It costs a little more than the set just described, but if a large aerial is available is well worth having because of the large signal the aerial brings in, which



Fig. 7 Crystal Set Wiring Diagram

allows splendid reception. This set is built on a baseboard with a front panel; a piece of five-ply wood about 3 inches square will serve for the baseboard with a similar-sized piece of three-ply for the panel. Again the sizes are not critical if you have any particular cabinet in mind. The panel stands upright along the edge of the baseboard to which it is fixed by two or three round-headed wood screws.

* * *

The dual capacitor used must be a type with feet which can be screwed to the baseboard, and if there are connexions underneath it which will be difficult to reach with a soldering iron, once it is fixed to the board, short lengths of wire should be soldered to them before fixing. A hole at suitable height must be made in the panel to allow the spindle of the capacitor to protrude through for sufficient length to fix on the knob or dial. The 'A/E' and 'Phones' tags (or terminals) must be fixed on either side of the panel.

Wiring-up is quite simple and the diagram explains it clearly. Once it is completed the 'phones and aerial and earth may be connected up. The thirty pf. trimmer should be open (i.e. unscrewed) about half-way and the capacitor dial slowly rotated. A station should be received and the cores of the coils may be adjusted for maximum volume. It is best not to use a screwdriver for this but a special trimming tool or a piece of wood suitably sharpened to a chisel-point. A large plastic knitting-needle rubbed to a suitable shape on a piece of glasspaper makes a very useful tool for trimming. If there is difficulty in finding a station, the aerial wire may be connected temporarily to the fixed vanes of the gang capacitor where they are connected to the diode, when both stations will probably be heard together. It should be easy to resolve the tuning point of one or other, when the aerial may be put back on its correct terminal. Leaving the set so tuned, adjustment of the cores may now be carried out until the station comes in at maximum volume. Careful manipulation of them together with any slight tuning adjustment necessary should bring in both stations separately and clearly.

If you build these crystal sets remember that reception is *entirely* dependent upon the aerial and earth in use. If these are poor, good signals cannot be expected. *Poor signals cannot be amplified or adjusted to make them louder*. A crystal set connected to an amplifier such as the 'Small High Fidelity' described later makes a very satisfactory arrangement for local station reception. For 'reaching out' and for louder signals a valve detector is required. A simple one-valve battery set is my next design.

CHAPTER THREE

Crystal Sets

Crystal sets are simple to build and cheap! With six feet of aerial this set will pick up the BBC programmes at good strength; with fifty feet of aerial the volume is really loud. Build the set with care, remembering that reception depends entirely upon aerial and earth.

These crystal set designs are chosen as the first in our constructional series because of their simplicity and cheapness. The most popular receiver for years was the 'crystal set', the theoretical design of which was precisely the same, in effect, as that shown in Fig. 7, our first design. Those old crystal sets, however, used large coils of thick wire and detectors consisting of a piece of crystalline substance 'tickled' by a small cat's whisker, which was only a piece of thin wire wound up into a small spring. Today we use a miniature coil and a germanium diode detector.

Germanium is one of the modern metals which have been developed for industrial purposes in recent years. A small flake of it is sealed into a tiny glass tube, with its cat's-whisker contact cemented permanently into place (Fig. 6).



Figure 6 The Germanium Diode Detector

A crystal set has no power to amplify the signals which it receives via the aerial and the crystal detector merely converts the radio signals into currents capable of actuating the diaphragms of our headphones and producing sounds thereby.

It follows, therefore, that the strength of the sound we receive in the headphones depends on the size of the aerial we have – a larger aerial picking up 'bigger' signals – and the efficiency of the detector in converting them ('rectifying' them is the proper term) into 'sound' signals.

The germanium diode is much better as a detector in every way than the old crystal detector and is completely stable in use. The modern crystal set, therefore, must not be confused with that of fifty years ago; it is best to discard the term 'crystal set' really in favour of 'germanium diode receiver'. The receiver in the Fig. 7 circuit is small and compact and very simple to make. With a good aerial it will give an extremely loud headphone signal from two or, possibly, three stations. It is essential to have a good aerial with a crystal set, and a good earth as well if this is possible. In North London, I could receive both the BBC Radio 2 (Light) and Radio 4 (Home) services with about 6 feet of wire. With 50 feet of aerial in the loft I could obtain Radio 1, 2, 3 and 4, with Radio 2 and 4 at extremely loud volume. The trouble then is that it is difficult to separate Radio 2 from Radio 4, and each programme has a slight background of the other.

From this you see that on medium and long waves *small aerials mean good selectivity (i.e. power to separate stations) but small signals*, whereas large aerials give large signals but poor station separation. If you live in a country district a long way



Figure 7 Crystal Set Theoretical Diagram



Figure 8 Crystal set Wiring Diagram

Components required:
·0005 mfd. solid dielectric variable capacitor (C.2)
On-off switch
DRR2 coil (Repanco)
·0002-mfd. fixed capacitor (C,1)
Germanium diode (Osram GEX 35 or Mullard OA 81)
4 terminals or 2 double mounts
Crocodile clip
Wood, wire, etc.
Tuning knob

from a BBC transmitter, and can erect a large aerial in the open air, you will probably get good results from the simple receiver; but if you live under twenty miles from a station for best results you need a more selective set.

Firstly, then, to build the set shown theoretically in Fig. 7 with a wiring diagram in Fig. 8, you need a piece of three-ply wood about 2½ inches square. If you have a particular box or cabinet to build the set into, and this requires a slightly larger size, it does not matter at all. You must drill holes for those components which are mounted on the panel; and these are the tuning capacitor in the centre, above and below it the 'A/E' and 'phones' terminals or terminal mounts. If you use the latter, the terminals affixed to them must protrude through holes to the other side, but terminals will automatically pass their shanks through the panel. The particular coil specified has a long-wave section and this requires an 'on-off' switch to short-circuit the long-wave section of the coil when medium waves only are required. As some of the holes may be a little larger than the drill you have available, an easy way to make them is to drill them out as large as possible and then 'reamer' them to size with the tang of a file or other tool.

After mounting those parts which require fixing to the panel, the soldering-up can be started; it will be found that remaining small items can be soldered into place and held into position by the wiring. Earlier remarks on soldering and wire to use may be referred to here, particularly the importance of clean joints made with a hot iron. Avoid 'dry joints' which look good but can be pulled apart quite easily and beware of applying a hot soldering iron for too long to the tags of components. In particular, do not let the iron get too near to the diode or remain too long on its connecting wires.

When soldering to the coil, be careful that the heat of the iron does not unsolder the wires already connected to the tags. Once the wiring has been completed and checked over, the headphones may be joined to the appropriate terminals, with aerial and earth also connected to their correct points.

Headphones must be of the 'high-resistance' type, i.e. 2000 or 4000 ohms impedance. If you have a pair of headphones which are low-resistance type, or yours are marked LR or 120 ohms, you can use them by interposing a special transformer (obtainable quite cheaply) between the set and the phones. Most dealers have these transformers.

After connecting the external apparatus, make sure the switch indicates the waveband required, that is, points *short-circuited*, cutting out the long waveband, if you want to receive on medium waves, and *open* if you want the whole coil in circuit for long-wave reception. Turn the knob slowly and you should pick up the stations available. A push-pull switch may not be available but any small on-off switch will do.

The coil specified is a Repanco DRR 2 and is really a coil with a reaction winding which is normally used in a one-valve or two-valve receiver. I have specified it for the crystal set because, in accordance with our promise of progressive set-building, it can be used for the receiver described in Chapter 4. In the design as given, using the DRR 2 coil, the 'reaction' winding is wired up so that it may be used as an aperiodic aerial winding which will give you a variation in selectivity. For this reason the lead from the aerial (through C.1) terminates in a crocodile clip.

from a BBC transmitter, and can erect a large aerial in the open air, you will probably get good results from the simple receiver; but if you live under twenty miles from a station for best results you need a more selective set.

Firstly, then, to build the set shown theoretically in Fig. 7 with a wiring diagram in Fig. 8, you need a piece of three-ply wood about 2½ inches square. If you have a particular box or cabinet to build the set into, and this requires a slightly larger size, it does not matter at all. You must drill holes for those components which are mounted on the panel; and these are the tuning capacitor in the centre, above and below it the 'A/E' and 'phones' terminals or terminal mounts. If you use the latter, the terminals affixed to them must protrude through holes to the other side, but terminals will automatically pass their shanks through the panel. The particular coil specified has a long-wave section and this requires an 'on-off' switch to short-circuit the long-wave section of the coil when medium waves only are required. As some of the holes may be a little larger than the drill you have available, an easy way to make them is to drill them out as large as possible and then 'reamer' them to size with the tang of a file or other tool.

After mounting those parts which require fixing to the panel, the soldering-up can be started; it will be found that remaining small items can be soldered into place and held into position by the wiring. Earlier remarks on soldering and wire to use may be referred to here, particularly the importance of clean joints made with a hot iron. Avoid 'dry joints' which look good but can be pulled apart quite easily and beware of applying a hot soldering iron for too long to the tags of components. In particular, do not let the iron get too near to the diode or remain too long on its connecting wires.

When soldering to the coil, be careful that the heat of the iron does not unsolder the wires already connected to the tags. Once the wiring has been completed and checked over, the headphones may be joined to the appropriate terminals, with aerial and earth also connected to their correct points.

Headphones must be of the 'high-resistance' type, i.e. 2000 or 4000 ohms impedance. If you have a pair of headphones which are low-resistance type, or yours are marked LR or 120 ohms, you can use them by interposing a special transformer (obtainable quite cheaply) between the set and the phones. Most dealers have these transformers.

After connecting the external apparatus, make sure the switch indicates the waveband required, that is, points *short-circuited*, cutting out the long waveband, if you want to receive on medium waves, and *open* if you want the whole coil in circuit for long-wave reception. Turn the knob slowly and you should pick up the stations available. A push-pull switch may not be available but any small on-off switch will do.

The coil specified is a Repanco DRR 2 and is really a coil with a reaction winding which is normally used in a one-valve or two-valve receiver. I have specified it for the crystal set because, in accordance with our promise of progressive set-building, it can be used for the receiver described in Chapter 4. In the design as given, using the DRR 2 coil, the 'reaction' winding is wired up so that it may be used as an aperiodic aerial winding which will give you a variation in selectivity. For this reason the lead from the aerial (through C.1) terminates in a crocodile clip.

This may be attached either to 'yellow' on the coil or 'red', in order to give the best position for the aerial in use. Try also fixing the diode to 'yellow' instead of to 'fixed vanes'.



Figure 9 Crystal Set Wiring Diagram (home-made coil)

The second crystal receiver is very cheap and simple to make and uses the *BOP* coil which I first made up for use in two transistor receivers described in *Boy's Own Paper* in 1963. It is very easily wound on a ferrite rod which is 4 inches long and ¼ inch in diameter. At the end of this chapter I repeat the instructions which we gave in *BOP* for winding it. The receiver in Fig. 9 can be put together easily in any handy box and will tune medium waves only, so that if you must get your Light programme on long waves, you would do better to make the design in Fig. 8. Components for this ferrite-rod coil design should be the same as those listed below Fig. 8 except for the coil, of course, which will not be required, nor will the on-off wavechange switch or the crocodile clip. The ·0002 mfd. condenser (capacitor) will help selectivity if it is wired between the aerial terminal and centre-tap on coil. By the way, use two thicknesses of good writing paper or very thin card for making the coil. The wire should not be too close to the ferrite rod itself. You can experiment with this coil quite a lot, if you wish, by putting different windings on it. Readers have told me they have even been using it for short-wave reception in a transistor receiver by using fewer turns and adding a reaction winding. For this crystal receiver, it might be found better to use a tuning condenser of only 200 pf (i.e. ·0002 mfd.) instead of the ·0005 mfd. one specified.

If you build these crystal sets, remember that reception is *entirely* dependent upon the aerial and earth in use. If these are poor, good signals cannot be expected. *Poor signals cannot be amplified or adjusted to make them louder*. A crystal set connected to an amplifier such as the 'small high fidelity' described later makes a very satisfactory arrangement for local station reception. For 'reaching out' and for louder signals a valve detector is required. Do not take your crystal set to pieces unless you have no alternative. The next design shown in Fig. 10 uses the large home-made coil of Fig. 4.



Figure 10 Diode 'Crystal Set'

Components required:
Coil: see text (home made type)
C.1. ·0005 mfd variable capacitor
C.2. ·001 mfd fixed capacitor
Diode: any suitable of good quality
R.1.: 1000 ohm resistor
Phones, wire, wood, etc.

The crystal set shown in Fig. 10 is very simple to make. Fix your coil on a small piece of wood in the manner shown. On one side of that piece of wood fix a small panel on which are mounted the tuning capacitor and two small terminals or a socket strip for phones. Also required will be a small on-off switch for wavechanging. Connect 2 on the coil to one side of diode and fixed plates on the tuning capacitor. Other side of diode to phones. Other side of phones to 4 on coil and 4 on coil also goes to one side of on-off switch plus 6 on coil and moving plates on capacitor. Other side of on-off switch to 3 on coil. Across the phones terminals connect a ·001 mfd. capacitor and if you are using a crystal earpiece you will also need a 1kΩ resistor there. For ordinary headphones (high-resistance) no resistor is needed. The aerial can be attached to a 'crocodile' clip and tried for best results on 1, 2 or 5 on coil. Earth can be clipped to 4 or 6, or you can add two more terminals to the panel for A & E. Your set should now work well and, having fixed a small knob to the shaft of the capacitor, you can tune in the available stations.

Figures 11 and 12 are rather special crystal set designs and I am indebted to Messrs Repanco Ltd, whose copyright designs they are, for allowing me to use them here. The coil featured is the DRR2 which they make and the first circuit is for a headphone crystal receiver which uses 2 diodes and 1½ volt cell. It is rather

CHAPTER 2

Crystal Sets

Crystal sets are simple to build and *cheap ! With six feet of aerial this set will pick up the BBC programmes at good strength; with fifty feet of aerial the volume is really loud. Build the set with care, remembering that reception depends* entirely *upon aerial and earth.*

THESE Crystal Set designs are chosen as the first in our constructional series because of their simplicity and cheapness. The most popular receiver for years was the 'crystal set', the theoretical design of which was precisely the same, in effect, as that shown in Fig 4, our first design. Those old crystal sets, however, used large coils of thick wire and detectors consisting of a piece of crystalline substance 'tickled' by a small cat's-whisker, which was only a piece of thin wire wound up into a small spring. To-day we use a miniature coil with a dust-iron core and a germanium diode detector.

Germanium is one of the modern metals which have been developed for industrial purposes in recent years, and is actually processed from soot-scrapings obtained from certain factory chimneys! A small flake of it is sealed into a tiny glass tube with its cat's-whisker contact cemented permanently into place (Fig. 3).

A crystal set has no power to amplify the signals which it receives via the aerial and the crystal detector merely converts the radio signals into currents capable of actuating the diaphragms of our headphones and producing sounds thereby.



Fig. 3. The Germanium Diode Detector



Fig. 4 Crystal Set Theoretical Diagram

It follows, therefore, that the strength of the sound we receive in the headphones depends on the size of the aerial we have—a larger aerial picking up 'bigger' signals—and the efficiency of the detector in converting them ('rectifying' them is the proper term) into 'sound' signals.

The germanium diode is much better as a detector in every way than the old crystal detector and is completely stable in use. The modern crystal set, therefore, must not be confused with that of thirty years ago; it is best to discard the term 'crystal set' really in favour of 'germanium diode receiver'. The receiver in Fig. 4 circuit is small and compact and very simple to make. With a good aerial it will give an extremely loud headphone signal from two or, possibly, three stations. It is essential to have a good aerial with a crystal set, and a good earth as well if this is possible. At my own home, which is ten miles from the BBC (Brookmans Park) transmitters in North London, I can receive both the BBC Home and Light service with about 6 feet of wire. With 50 feet of aerial in the loft I can obtain Home, Light and Third, the first two at extremely loud volume. The trouble then is that it is difficult to separate Home from Light, and each programme has a slight background of the other.

* * *

From this you see that on medium and long waves *small aerials mean good selectivity* (*i.e. power to separate stations*) *but small signals*, whereas large aerials give large signals but poor station separation. If you live in a country district a long way from a BBC transmitter, and can erect a large aerial in the open air, you will probably get good results from the simple receiver; but, if, like me, you live under twenty miles from a station, for best results you need the more selective set shown in our second design.

Firstly, then, to build the set shown theoretically in Fig. 4 with a wiring diagram in Fig. 5, you need a piece of three-ply wood about 2½ inches square. If you have a particular box or cabinet to build the set into, and this requires a slightly larger size, it does not matter at all. You must drill holes for those components which are mounted on the panel; and these are the tuning capacitor in the centre, above and below it the 'A/E' and 'Phones' terminals or terminal mounts. If you use the latter the terminals affixed to them must protrude through holes to the other side, but terminals will automatically pass their shanks through the panel. The particular coil specified has a long-wave section and this requires an 'on-off' switch to short-circuit the long-wave section of the coil when medium waves only are required. As some of the holes may be a little larger than the drill you have available an easy way to make them is to drill them out as large as possible and then 'reamer' them to size with the tang of a file or other tool.



Fig. 5. Crystal Set Wiring Diagram

Components required:
·0005 mfd. solid dielectric variable capacitor (C.2)
On-off switch
QCD 2 Coil (Osmor)
·0002 mfd. fixed capacitor (C.1.)
Germanium diode (Osram GEX 35 or Mullard OA 60)
4 terminals or 2 double mounts
Wood, wire, etc.
Tuning knob
For better selectivity Teletron HAX coil can be used. Connections are given with coil.

After mounting those parts which require fixing to the panel, the soldering-up can be started; it will be found that remaining small items can be soldered into place and held into position by the wiring. Earlier remarks on soldering and wire to use may be referred to here, particularly the importance of clean joints made with a hot iron. Avoid 'dry' joints which look good but can be pulled apart quite easily and beware of applying a hot soldering iron for too long to the tags of components. In particular do not let the iron get too



Fig. 6 **Crystal Set Theoretical Diagram**

Components required:
Midget ·0005 mfd. variable capacitor (C.3/4) dual gang
·00005 mfd. fixed capacitor (C.1)
2 Teletron Coils type BA 2
50 mmfd. (i.e., ·00005 mf.) variable trimmer (C.2)
Germanium diode (Osram GEX 35 or Mullard OA 60)
4 terminals or 2 terminal mounts
Knob or small dial

near to the diode or remain too long on its connecting wires.

When soldering to the coil be careful that the heat of the iron does not un-solder the wires already connected to the tags. Once the wiring has been completed and checked over, the headphones may be joined to the appropriate terminals, with aerial and earth also connected to their correct points.

Headphones must be of the 'high resistance' type, i.e. 2000 or 4000 ohms impedance. If you have bought a pair of Government surplus 'phones which are low-resistance type, or yours are marked LR or 120 ohms, you can use them by interposing a special transformer (obtainable quite cheaply) between the set and the 'phones. Most dealers have these transformers.

After connecting the external apparatus, make sure the switch indicates the waveband required, that is, points *short-circuited*, cutting out the long waveband, if you want to receive on medium waves, and *open* if you want the whole coil in circuit for long-wave reception. Turn the knob slowly and you should pick up the stations available.

The selective receiver in my next design is shown theoretically in Fig. 6, and fully wired in Fig. 7. It costs a little more than the set just described, but if a large aerial is available is well worth having because of the large signal the aerial brings in, which

Fig. 7
Crystal Set
Wiring Diagram



allows splendid reception. This set is built on a baseboard with a front panel; a piece of five-ply wood about 3 inches square will serve for the baseboard with a similar-sized piece of three-ply for the panel. Again the sizes are not critical if you have any particular cabinet in mind. The panel stands upright along the edge of the baseboard to which it is fixed by two or three round-headed wood screws.

* * *

The dual capacitor used must be a type with feet which can be screwed to the baseboard, and if there are connexions underneath it which will be difficult to reach with a soldering iron, once it is fixed to the board, short lengths of wire should be soldered to them before fixing. A hole at suitable height must be made in the panel to allow the spindle of the capacitor to protrude through for sufficient length to fix on the knob or dial. The 'A/E' and 'Phones' tags (or terminals) must be fixed on either side of the panel.

Wiring-up is quite simple and the diagram explains it clearly. Once it is completed the 'phones and aerial and earth may be connected up. The thirty pf. trimmer should be open (i.e. unscrewed) about half-way and the capacitor dial slowly rotated. A station should be received and the cores of the coils may be adjusted for maximum volume. It is best not to use a screwdriver for this but a special trimming tool or a piece of wood suitably sharpened to a chisel-point. A large plastic knitting-needle rubbed to a suitable shape on a piece of glasspaper makes a very useful tool for trimming. If there is difficulty in finding a station, the aerial wire may be connected temporarily to the fixed vanes of the gang capacitor where they are connected to the diode, when both stations will probably be heard together. It should be easy to resolve the tuning point of one or other, when the aerial may be put back on its correct terminal. Leaving the set so tuned, adjustment of the cores may now be carried out until the station comes in at maximum volume. Careful manipulation of them together with any slight tuning adjustment necessary should bring in both stations separately and clearly.

If you build these crystal sets remember that reception is *entirely* dependent upon the aerial and earth in use. If these are poor, good signals cannot be expected. *Poor signals cannot be amplified or adjusted to make them louder*. A crystal set connected to an amplifier such as the 'Small High Fidelity' described later makes a very satisfactory arrangement for local station reception. For 'reaching out' and for louder signals a valve detector is required. A simple one-valve battery set is my next design.

Emtech ZM-2 Antenna Tuner Kit



(Click on any picture to get larger, high-resolution version)

built by Monty Northrup, N5ESE

NOTE: 'N5FC' is my former call.
This project was constructed while that call was valid, and you may observe references to it.

The Emtech ZM-2 Antenna Tuner is a nifty little portable transmatch for QRP (low power). It utilizes the well-known Z-match circuit, which is especially useful for balanced antennas (like dipoles and loops). Since it's a very inexpensive kit (around $50), and because there's an constant clatter about it on the QRP-L mail list, and because I travel a lot and need the miniature equipment, I figured it would be worth investigating.

Construction Notes

This is a pretty easy project to put together. The kit has about 20 parts. Give yourself half-a-Saturday. The instructions come printed on 10 letter-sized sheets, and include step-by-step assembly. There are two transformers to wind on toroid cores. The first (and larger one) is shown below. The instructions contain pretty good black-and-white drawings, but because they have so many taps, it would be pretty easy to get confused. A color picture might help:



Click on above image for larger version

T2, the SWR-bridge auto-transformer, the smaller toroid, is a little simpler to wind, but no drawing is provided. Still, the word-description is adequate, and no problems were encountered winding this coil. It can be seen in the internal views (shown below) as the bright-green toroid winding.

All the components are mounted on the single (and rather thin) aluminum panel. The kit-buyer must drill this panel, and a template is provided for locating holes. Be sure to use pilot drills and go slowly, because using a standard electric hand drill and high-speed bits has the potential to really mess up this front panel. But, hey!

That's what homebrewing is all about. I used a "step-drill" (sometimes called a "Unibit") mounted on a drill press and using a wood backing; this method gave me clean holes. Emtech provides a sticky-back laser-printed front panel label, which you can place on the drilled aluminum panel to get a pretty nice visual effect. I put some transparent self-adhesive laminate over mine, to keep it from getting dirty. After placing the label, you use an hobby knife to cut holes in the paper to match the holes you drilled in the panel.

After drilling the front panel and placing the label, you mount all the obvious parts onto the panel (LED, switches, capacitors, connectors). All the controls and connectors mount on this one panel, and during operation, it can feel a little crowded, but it seems to work. Once you've mounted the parts onto the panel, you flip it over and begin melting solder. The front panel components are used as mounting points for nearly everything, but the diode and resistor must be mounted 3-D style (mid-air solder joints). This is kinda flimsy, but the components don't have a lot of mass, and it works. If you don't feel good about it, you may want to add some kind of standoff terminals to make the connections more solid. Here's a picture of the construction just before mounting the larger transformer T1:



Click on above image for larger version

One thing to notice is that I've placed small foam blocks (from scrap packing material) to mount the transformers so that they'll stay in place. Here, we used the XYL's hot-glue gun to stick these down (and we'll do the same to mount the toroids). Here's another detail of the input circuit, showing the 3-D components and the SWR transformer T2 mounted on a little piece of foam:



Click on above image for larger version

Finally, here's a view of the completed assembly (internal), with T1 hot-glued in place. Nothing left here but to drop the entire thing into the black-plastic enclosure, and hook it up for a test.



Click on above image for larger version

Testing and Tuneup

For testing, I'll place a standard SWR meter between the transmitter and the new ZM-2 tuner, so I can see how well this little baby does its job. I won't trust it until I see for myself that it's working.

The first antenna I tried was my old reliable twinlead-fed 40 Meter dipole. I use this antenna on all bands 40 through 10, tuning it with an MFJ-971 T-match. I transferred the twinlead to the binding posts of the ZM-2, and proceeded to tune-'er-up. First, I switch to "TUNE". This places the 50-ohm bridge circuit between the transmitter and the antenna. Then, I listen. I twist both knobs for maximum noise, easily heard. Then I key the Ten-Tec Scout (5 watts, of course). Hey! The LED lights! Twist two knobs slightly, and 5 seconds later I have my null, as indicated by the dimming LED. It dims to black, easily visble. Wow! that was way too easy, and much easier than the T-match circuits I've used. Let's make a contact. Whoops, I forgot to switch from "TUNE" to "OPERATE" (not much power gets to the antenna in "TUNE"). Hey, switched to "OPERATE", and it works!

We then tested the unit on the remaining bands (30, 20, 15, 10). On these bands, the null was not to black; nearly so on some, barely noticeable on others. But in all cases, the null produced a 1:1 SWR, as measured by the "cheat" SWR Meter. After making a contact on each band, we declared the ZM-2 usable.

Eventually, we tested the ZM-2 on several other antennas. It works quite well on my Notebook Antenna and DCTL Antenna (both balanced antennas). I was unable to tune the Notebook on 10 meters, which I found somewhat odd. But, that's tuners for you! (I've never found a tuner that worked well for every antenna and all bands).

I have not yet tried it with an end-fed antenna. A switch is provided for grounding one side of the T1 output link, so that the tuner can be used with an unbalanced antenna. It should work fine for a quarter-wave end-fed, but may not have enough range for a half-wave end-fed wire. (Anybody out there ever try that?)

Summary, and My Impressions

This one's a keeper! I find myself reaching for this tuner anytime I have a notion to experiment with antennas (which is often). It works well, giving a good match to most every antenna. I've not tried it on 80 meters, and I only found one antenna on 10 meters that refused to match, but all other bands worked great. The LED doesn't always go out when matched, and sometimes I wonder if I'm getting a good match. But after adjusting the LED for minimum, and checking the SWR with an independent meter, I'm convinced it's working. Sometimes, the null is so narrow that it's really easy to miss it altogether, and very hard to set it to minimum. These behaviors are likely antenna-dependent, and maybe band -dependent. I wonder if a variable resistor in series with the LED might allow the null to be more appparent during tuning? Occasionally, I'll forget that I have to switch from "Tune" to "Operate", and wonder why I'm getting no answers to my calls (although, once I did get an answer in "TUNE" mode). Oh, well...

It's nice having a balanced tuner without having to worry about balun mis-matches and losses. And the small size and weight make it just about perfect for travel and portable QRP. Plus, this thing is just *doggoned cute*!

72 / 73, and have fun! -- monty

Return to N5ESE home page

Overseer: Monty Northrup ... ... leave e-mail ...

Visit our regular (non-ham, but very popular) homepage

End Fed Half Wave Antenna Coupler


DANGER!
High Voltage RF!
End Fed
Half Wave
T1
50Ω
Counterpoise /
Coax Ground
Switch
Counterpoise
7-30MHz End Fed Half Wave Coupler - M0UKD.com
15-
370pF
DANGER!
High Voltage RF!
MØUKD

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Accept Read More


End Fed
Half Wave
T1
Pri: 2t
Sec: 16t (1.5µH)
1:8 turns ratio
1:64 impedance ratio
50Ω to 3200Ω
T1
15-350pf
50Ω
Counterpoise /
Coax Ground
Switch
Counterpoise
7-30MHz End Fed Half Wave Coupler - M0UKD.com
MØUKD


21.25
Calculate

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.
Read More



Freq	21.2 MHz
SWR	**1.062**
Z	3015 at 0.11 deg. = 3015 + j 5.808 ohms
Refl Coeff	0.02984 at 178.15 deg. = -0.02983 + j 0.0009624
Ret Loss	30.5 dB

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.
Read More



This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.
Read More

drywipe marker
horizontally



This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More



This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.
Read More




DANGER!
High Voltage RF!
MØUKD

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More

Share this... 734 0

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.
Read More

GENETIC CODE CHART

“DNA-AMINO ACID DICTIONARY”

DNA Codons and the Amino Acids (symbols and abbreviations) for which they code.

DNA codon	AA sym	AA abr
AAA	K	lys
AAC	N	asn
AAG	K	lys
AAT	N	asn
ACA	T	thr
ACC	T	thr
ACG	T	thr
ACT	T	thr
AGA	R	arg
AGC	S	ser
AGG	R	arg
AGT	S	ser
ATA	I	iso
ATC	I	iso
ATG	M	met
ATT	I	iso

DNA codon	AA sym	AA abr
CAA	Q	gln
CAC	H	his
CAG	Q	gln
CAT	H	his
CCA	P	pro
CCC	P	pro
CCG	P	pro
CCT	P	pro
CGA	R	arg
CGC	R	arg
CGG	R	arg
CGT	R	arg
CTA	L	leu
CTC	L	leu
CTG	L	leu
CTT	L	leu

DNA codon	AA sym	AA abr
GAA	E	glu
GAC	D	asp
GAG	E	glu
GAT	D	asp
GCA	A	ala
GCC	A	ala
GCG	A	ala
GCT	A	ala
GGA	G	gly
GGC	G	gly
GGG	G	gly
GGT	G	gly
GTA	V	val
GTC	V	val
GTG	V	val
GTT	V	val

DNA codon	AA sym	AA abr
TAA	-	stop
TAC	Y	tyr
TAG	-	stop
TAT	Y	tyr
TCA	S	ser
TCC	S	ser
TCG	S	ser
TCT	S	ser
TGA	-	stop
TGC	C	cys
TGG	W	trp
TGT	C	cys
TTA	L	leu
TTC	F	phe
TTG	L	leu
TTT	F	phe

Published by
Vigyan Prasar
C-24, Qutab Institutional Area
New Delhi - 110 016
(Regd. office : Technology Bhawan, New Delhi - 110 016)
Phones : 6864022, 6864157, 6965980 Fax : 6965986
E-mail : vigyan@hub.nic.in
Internet : http://www.vigyanprasar.com

A Guide to Ham Radio
(A comprehensive Guide book for the Ham Radio Enthusiasts)

Copyright : © 2000 by Vigyan Prasar

Compiled by : Shri Sandeep Baruah, VU2MUE (Ex-VU2MSY)

ISBN : 81-7480-068-9

Printed in India by Rakmo Press Pvt. Ltd. C-95, Okhla Industrial Area, New Delhi - 110020

FOREWORD

Considering the utility and potential of ham radio not only in emergencies, but also as a means of triggering and promoting interest in science and technology, the National Council for Science and Technology Communication (NCSTC) and Vigyan Prasar have been making efforts to popularise ham radio in India. This hobby has the potential of involving a large number of the young and energetic citizens of our country in a process of "learning by doing" in the field of electronics as well as wireless communication technology.

Vigyan Prasar is in the process of building up a countrywide science club movement under which a science club network has already been functioning (called the **Vigyan Prasar NET**work of Science Clubs, **VIPNET**). These **"Science Clubs"** for the children, if hooked through a network of ham radio stations, will enhance the interaction among them and other science enthusiasts. It will also provide an opportunity to the club members to do on-the-air voice communication without much cost. It may be recalled that ham radio operators played an important role during the Bharat Jan Vigyan Jatha (1987) in coordinating and monitoring the movements of Jatha, besides organising demonstrations of ham radio for the public. **Vigyan Prasar runs the amateur radio station VU2NCT on behalf of NCSTC which is located in the Technology Bhawan, New Delhi.** Some years back, Vigyan Prasar had developed a low cost 7 MHz QRP transceiver. Vigyan Prasar also runs a VHF Ham Repeater Station (VU2DLR) for the mobile operators in Delhi.

"Catch them young" is a phrase very popular with educationists. The present education system provides ample scope for organisations like ours to contribute towards strengthening and supplementing the learning experiences of children by designing well focussed programmes, especially in electronics, that encourage self-learning via electronic kits and toys; and initiation into hobbies like amateur radio etc. Efforts in this direction are underway at Vigyan Prasar. This study material has been put together to help ham radio enthusiasts in their preparation for the Amateur Station Operator's Certificate (ASOC) examination conducted by the Ministry of Communications for awarding of amateur radio operator's licence. Readers may also visit the ham radio section of the Vigyan Prasar homepage (URL: **www.vigyanprasar.com**) for more information.

Narender K. Sehgal, VU3NKS
Director, Vigyan Prasar

ACKNOWLEDGEMENT

We are grateful to Shri Sahruddin, VU2SDN, President of the Amateur Radio Society of India (ARSI), for going through this compilation more than once at the manuscript stage and making critical and valuable suggestions which have been incorporated. While preparing the radio and electronics theory portion of the study material, various books were consulted and the compilation has drawn heavily from the following:

1. Electronic Communication
   by Robert L. Shrader, W6BNB (McGraw Hill, Inc.)
2. Electricity and Electronics Today
   by W.J. Haynie, III, (EMC Corporation, USA)
3. Radio Technology
   by Ashok Saxena (Sudha Publications Private Ltd.,New Delhi)
4. Electronics Made Simple
   by Henry Jacobowitz (Doubleday & Company, Inc. New York)
5. Guide to Amateur Radio in India
   by Saad Ali, VU2ST (Amateur Radio Society of India)
6. Basic Radio (Volume-I to VI)
   by Marvin Tepper (D.B. Tarapoorevala & Sons Ltd. Mumbai)
7. Understanding Electronics
   by R.H. Warring (Jaico Publishing House)
8. Electronics volume-two
   by Harry Mileaf (D.B. Taraporevala Sons & Co. Pvt. Ltd.)
9. Web site: www.scimedia.com
10. ARRL Handbook-1993

CONTENT

Part-I: Introduction to ham radio

PAGE

A. What is Ham Radio? 1

B. Why an Amateur Radio Operator is called a ham? 2

C. What is the minimum qualification to become a ham? 3

D. What is an amateur radio call-sign? 3

Part-II: Amateur Radio Rules & Regulation

A. Detailed procedures related to application for a ham radio licence. 4

B. Different grades of licencing examinations and licences. 5

C. The Indian Wireless Telegraphs (Amateur Service) Rules, 1978. 6

D. Syllabus of Amateur Station Operator's Certificate (ASOC) Examination. 29

E. Question and answer section on amateur radio rules & regulations 33

F. Radio telephony operating procedure. 41

G. Radio telegraphy operating procedure. 43

Part-III: Radio Theory and Practice

A. Elementary theory of electricity & magnetism 46

B. Thermionic emission & valves 76

C. Semiconductor devices 79

D. Radio receivers 85

E. Transmitter 96

F. Radio wave propagation 102

G. Aerials 109

Part-IV: Learning the International Morse Code. 117

Part-V: Safety measures in a ham radio shack. 121

Annexure-I: List of Wireless Monitoring Stations 124

Annexure-II: Call-sign Prefixes of Amateur Radio Stations of different countries allotted by the International Telecommunication Union (ITU) 125

Annexure-III: A Sample Question Paper for the Amateur Radio Licencing Examination 136

Annexure-IV: Nomenclature of the Frequency and Wavelength Bands used in Radio Communication 138

Part-I

Introduction to Ham Radio

A. What is Ham Radio?

Ham radio operators are a group of people nurturing a special interest in wireless communication technology. People from all the spheres of life are found among the ham radio operators. They operate their wireless transceivers (a combined unit of radio transmitter and receiver) during their spare time for the sheer joy, thrill and excitement involved in doing a worldwide radio communication. Unlike the broadcast radio stations (to whom we usually tune our radio receivers to listen to), ham radio is a two-way communication system. Ham radio operators can put their voice on-the-air to be listened into and at the same time replied back by their fellow radio operators around the world, usually with very low power devices.

Despite the existence of other communication facilities, ham radio operators run their own wireless communication network with entirely personal effort, out of the love for this medium of communication. There are some hams who, build their own wireless transceivers (a combined unit of transmitter and receiver) and transmit their voice signals throughout the world to be replied back by their fellow hams. These are the experiment oriented hams who try to achieve some sort of a perfection in developing electronic circuits for radio frequency work, or at a lower level, they may like to assemble a piece of wireless equipment designed by their fellow experts, modify it in their own way to improve its performance till they are satisfied with its performance. Hams located in the other parts of the world reply back exchanging information about the quality and strength of their radio signals.

They exchange personal as well as technical information, which are not related to business or commerce, politics and religion. Though a ham cannot use his radio station for any pecuniary gain, a creative mind can still find numerous utility of ham radio. It is a pursuit, which attracts people from all the spheres of life. There are hundred and thousands of people who are laymen so far as their knowledge of electronics is concerned, yet, they are expert ham radio operators. It is an exciting way to discover new friends and disseminate knowledge on-the-air. One interesting fact about ham radio communication is that hams don't have to pay any money to the authority for their on-the-air conversation.

With the availability of low cost easily replicable circuits of radio transmitters and receivers, the number of ham radio operators increased to millions. The growth of electronics communication technology is also considered to be going hand in hand with the progress of ham radio. The advancement in the field of electronics and the flourishing growth of electronics industry in countries like Japan has been very often attributed to the presence of large group of dedicated ham radio operators (to the tune of 13,50,127).

Though ham radio is a highly **specialized technical hobby**, it requires **no special qualification** (except that the person going to be a ham has attained 12 years of age). However, it demands immense interest in radio communication and sufficient enthusiasm to operate a radio station of your own. Ham radio, also known as

"**Amateur Radio**" does not provide any pecuniary gain. However, what you gain from being a ham is more than what money can give and for that you got to be imaginative! Many of the foremost radio and electronics engineers and technicians operate as amateurs during times when they are not occupied professionally. Seeing the growth of ham radio population around the world, many professional companies started manufacturing ham radio equipment to meet the needs of the vast group of ham radio operators, who prefer readymade professionally built equipment instead of homemade ones. So, what had once been a hobby for somebody, turned out to be a profitable industry for some others. Hams never accept money for their on-the-air communication.

Young students can learn the principles of electronics through practical experimentation by assembling wireless transmitter and receiver kits in the ham radio clubs established in their schools. Without a valid ham licence, it is illegal to operate wireless equipment. In India, the **Central Board of Secondary Education** (CBSE) has also taken some initiative to include 'ham radio' in their course curriculum under the scheme of Work Experience. **The Member of Parliament Local Area Development Scheme** has also included 'Ham Radio' as one of its projects. As per the directive of the **Ministry of Programme Implementation, a Member of Parliament (MP) can spend money to establish ham radio stations in the schools located in his area.** If these schemes are fruitfully utilised, many youngsters would be able to take interest in ham radio which they may also make into career. There are many activities people perform out of their scientific curiosity or to satisfy their inquisitive mind. Many people are attracted towards ham radio for this reason also.

B. Why an Amateur Radio Operator is called a ham?

As per the Florida Skip Magazine (1959), the word "HAM" was coined in **1908** from the station CALL of the first amateur wireless station operated by some amateurs of the **Harvard Radio Club**. They were Albert S. **Hyman**, Bob **Almy** and Poogie **Murray**. At first they called their station "**Hyman- Almy-Murray**". Tapping out such a long name in code soon became tiresome and called for a revision. They changed it to "**Hy-Al-Mu**", using the first two letters of each of their names. **Early in 1901** some confusion resulted between signal from amateur wireless station "Hy-Al-Mu" and a Mexican ship named "HYALMO". **They then decided to use only the first letter of each name and the station CALL became "HAM".**

During those days of unregulated radio, amateur radio operators picked their own frequency and call letters. Then as now, some amateurs had better signals than commercial stations. **The resulting interference came to the attention of US congressional committees in Washington DC and the Congress proposed a legislation to critically limit the amateur radio activity. In 1911, Albert Hyman chose the controversial Wireless Regulation Bill as the topic for his thesis at Harvard.** His instructor insisted that a copy be sent to Senator David L. Walsh, a member of one of the committees hearing the Bill. The Senator was so impressed with the thesis that he asked Hyman to appear before the committee. Albert Hyman took the stand and described how the little station was built and almost cried when he told the crowded committee room that if the BILL went through they would have to close down the station because they could not afford the license fee and all the other requirements which the BILL imposed on amateur stations. **Congressional debate**

began on the Wireless Regulation Bill and little station "HAM" became the **symbol for all the little amateur stations in the country crying** to be saved from **the menace and greed of the big commercial stations who didn't** want them **around.** The BILL finally got to the floor of Congress and every speaker talked about the "**....poor little station HAM.**" That's how it all started. The whole story can be found in the US Congressional Record. Nation-wide publicity associated the station "HAM" with other amateur radio operators. From that day to this, and probably until the end of time in radio; an amateur radio operator is a "HAM".

C. What is the minimum qualification to become a ham?

No educational qualification is specified to become a ham. Anybody who has **attained 12 years of age** can become a ham radio operator after passing the **Amateur Station Operator's Certificate (ASOC) Examination** conducted by the **Ministry of Communications, Govt. of India.** You have to send a "**Birth Certificate**" or the "**High School Leaving Certificate**" (which mentions your date-of-birth) as a proof of your age.

There are four different grades of Amateur Wireless Telegraph Station Licence. Those between the **age group of 14-18 years** can apply for **Grade-I, Grade-II, Restricted Grade or a Short Wave Listener's licence** (listening to the ham radio operators without this licence is considered illegal). Those between the **age group of 12-14 years** can apply for **Grade-II, Restricted Grade or a Short Wave Listener's Licence.** The application for the grant of such licences should be accompanied by a certificate from the head of the educational institution recognized by a board or university in India, attended by the consent of the applicant or from his legal guardian that the applicant is interested in and is competent to conduct experiment in wireless communication.

D. What is an amateur radio call-sign?

Each **amateur radio station (ham radio station)** has its own unique "**name**" allotted by the authorities. In amateur radio, **the unique name assigned to a ham radio station and its owner** helps you to know **its operator** as well as **the country** to which he/she belongs. A particular ham radio station is authorized to be operated by that particular ham radio operator only. However, other licensed ham radio operators are also eligible to operate his station, provided, the owner of that particular station is physically present during the operation. **A person who does not hold a ham radio licence is not authorized to operate a ham radio station.** This also means that only a single station with a particular call-sign can exist in a particular location. A person having a ham radio call-sign is not authorized to set up more than one ham radio station.

A call-sign consists of a set of letters and numbers, assigned by the authority. For example **VU2XYZ** is a call-sign which belongs to a particular ham in India. No other hams anywhere in the world can have this call-sign! Similarly, **4S7VK** is a call-sign which belongs to a ham from Sri Lanka. In a call-sign, the first 2 (or 3) characters are called the **prefix.** So, there might be a ham with the call-sign 4S7XYZ in Sri Lanka. Similarly, a call-sign like VU2VK may exist in India! Each country has its own prefix. The knowledge of prefix helps us in identifying the country of origin of a particular amateur radio transmission (List of prefix at Annexure-II).

When a ham radio station is set up on board a ship, the call-sign should be followed by the suffix /MM. So, VU2XYZ would become VU2XYZ/MM (**maritime mobile**) when it operates from a ship. If it operates from a vehicle, then the call-sign becomes VU2XYZ/M (**mobile**).

Part-II

Amateur Radio Rules & Regulation

A. Detailed procedures related to application for a ham radio licence

An examination is held for licensing of Amateur Stations. It is conducted by the **Wireless Planning and Co-ordination wing (WPC) of the Ministry of Communications,** New Delhi at 22 **Wireless Monitoring Stations** (Annexure-I) located throughout the country. You should apply to the 'Officer-in-Charge' (OC) of the Monitoring Station nearest to your hometown. Basically the examination consists of a **100 marks question paper** (50 marks related to basic radio/electronics theory as per the syllabus and 50 marks related to Amateur Radio Rules & Regulations) which is of **one, two** or **three hours** duration as per the "grade" of licence you intend to appear. There are 4 grades. You can apply for more than one grade at a time, provided, separate application forms along with the prescribed examination fees, for each grade in the form of **Demand Draft** issued from a "**State Bank of India**" branch drawn **in favour of** the "**Pay & Accounts Officer (Headquarters), Department of Telecommunications, New Delhi-110 001, payable at SBI New Delhi Service Branch (Code No. 7687)** are **sent to** the **"Officer-in-Charge" of the Wireless Monitoring Station (in no case** application be forwarded to WPC Wing, New Delhi) where you will be appearing for the ASOC examination.

The particulars of the "Venue" and "Date" etc. of the examination will be communicated by the Officer-in-Charge of the concerned Wireless Monitoring Station on receipt of completed application form with the requisite examination fees

Following should accompany the application:

(1) **Nationality Certificate**/Character Certificate in the prescribed proforma (find the proforma in "Indian Rules & Regulation" section of this book) from a gazetted officer.

(2) **2 copies of recent passport size (3 x 4 cms) photographs** duly signed by you on the front side.

(3) Examination fees in the form of **Bank Draft (DD) drawn from a SBI branch** of appropriate amount.

(4) **Personal particulars** (4 copies) in the prescribed proforma (find the proforma in "Indian Rules & Regulation" section)

(5) An **attested copy of birth certificate or School Leaving certificate** as a proof of your age (the minimum age requirement to appear for the examination is 12 years)

After the declaration of the result, a copy of the result and your "Personal particulars" will be forwarded by the Wireless Monitoring Station to the WPC Wing of the Ministry of Communications, New Delhi. The WPC Wing, New Delhi will then inform the concerned Department of the Ministry of Home Affairs for a 'Security Clearance/Police Verification'. After the police verification report is received with a clearance, the WPC Wing will write to you that you will be awarded an "Amateur Wireless Telegraph Station Licence" on payment of the requisite "Licence fee". Remember that **'Examination Fee'** and **'Licence fee'** are different and the **'Licence fee' should be sent only when asked for.** This time, **the mode of payment is same** as above, but you have to send it directly to:

The Assistant Wireless Adviser to the Govt. of India,
WPC Wing, Ministry of Communications,
Amateur Radio Section,
Dak Bhawan, Parliament Street,
New Delhi-110 001

B. Different grades of licencing examinations & licences

(1) **Restricted Grade Amateur Station Operator's Licence** (if you pass Restricted Grade licensing Examination): Permits **short distance terrestrial communication** using a power output of **10 Watts** (dc input power) in the Very High Frequency (VHF) & Ultra High Frequency (UHF) bands. The frequencies allocated in these bands ranges from **144 to 146 MHz** and **434 to 438 MHz**. Modes of communication allowed are: **Radio Telephony**(Voice) using **Amplitude Modulation** (AM), **Single Side Band** (SSB), SSB Suppressed Carrier, SSB reduced carrier and **Frequency Modulation** (FM). **It is advisable not to go for this Grade of licence because communication is limited to a very short distance** (a typical possible range may be 35 km only depending on the height of the antenna or the type of terrain). **This type of licence is useful in a place where there are large number of ham radio operators.**

(2) **Grade II Licence** (if you pass Grade-II licensing examination): Permits **worldwide long distance communication** in **AM, SSB, FM** using a power output of **50 watts** in different allotted **short wave bands (high frequency-HF bands ranging from 1.8 to 30 MHz)** including the **VHF/UHF bands** mentioned above. **But entitlement for authorization of voice communication (radio telephony) is on the basis of providing proof of having made 100 contacts with other amateur radio stations using Morse Code (Called Continuous Wave-CW communication).** This means that you have to send back your original licence to the WPC wing for "Voice endorsement" along with the photocopies of your log book (see Rules & Regulation Section).

(3) **Grade-I:** (if you pass Grade-I licensing examination): Power output is **150 watts** in short waves (in the allotted HF bands), **25 watts in VHF & UHF** (Ultra High Frequency). An additional UHF spectrum from 1260 to 1300 MHz including a range of frequencies in Super High Frequency (SHF: 3300-3400 & 5725-5840 MHz) spectrum is available to this category of licensees. With this licence **you can directly use voice** including Morse Code. Other advanced modes like **Radio Tele-Typing (RTTY), Amateur Radio Teleprinting Over Radio (AMTOR), Packet Radio (-an**

advanced technique of digital data communication through computer connected to a wireless transceiver), **PSK31** (the latest digital communication mode in which a computer equipped with a sound-blaster card can be directly connected to a wireless transceiver for data reception and transmission), **Amateur Television** (ATV using Slow Scan Telecast: SSTV) are also allowed. You are also permitted to work amateur radio communication satellites with this licence.

(4) **Advanced Grade:** Same as Grade-I licence but allowed to use **400 watts** of power in selected sub-bands. **This is the highest grade licence in India.** Every ham radio enthusiast in India aspires to get it.

Practical Test

There is a practical test on Morse Code sending and receiving (except for Restricted Grade Licence where this test is not required). This is a 10 minutes duration test to examine the candidate's proficiency in sending and receiving Morse Code. To learn Morse code, a Morse Code Practice Oscillator can be assembled along with a Morse Key and a Morse Code learning Cassette can be found useful (See Morse Code learning Section of this book).

C. The Indian Wireless Telegraphs (Amateur Service) Rules, 1978

GOVERNMENT OF INDIA
MINISTRY OF COMMUNICATIONS
(WPC Wing)

Notification
The Indian Wireless Telegraphs (Amateur Service) Rules, 1978

G.S.R No. 1499/78- In exercise of the powers conferred by section 4 and section 7 of the Indian Telegraph Act, 1885 (13 of 1885), the Central Government hereby makes the following rules for the conduct of wireless telegraphs in the amateur service, established, maintained, and worked by persons licenced under the said Act.

1. Short title and commencement

(1) These rules may be called the Indian Wireless Telegraphs (Amateur Service) Rules, 1978.

(2) They shall come into force on the 1st January, 1979.

2. Definitions

In these rules, unless the context otherwise requires-

(a) 'Act' means the **Indian Telegraph Act, 1885** (13 of 1885);

(b) '**Amateur service**' means a service of self training, inter-communication and technical investigations carried on by amateurs that is, by persons duly authorized under these rules interested in radio technique solely with a personal aim and without pecuniary interest; 'amateur station', and 'station' shall have the meaning respectively assigned to them in the Convention;

(c) **'Convention'** means the **International Telecommunication** Convention, Malaga-Torremolinos, 1973, for the time being in force and the Radio Regulations and the Additional / Radio Regulations annexed thereto but does not include any portion of the said Convention or Regulations regarding which the Central Government makes any reservation;

(d) 'Licence' means a licence granted under section 4 of the Act for an amateur wireless telegraph station.

3. Necessity for licence

No persons shall establish, maintain and work an amateur wireless telegraph station, except under and in accordance with the terms and conditions of an appropriate licence under these rules.

4. Categories of licence

There shall be five categories of licences, namely :

(i) Advanced Amateur Wireless telegraph Station Licence
(ii) Amateur Wireless Telegraph Station Licence, Grade - I
(iii) Amateur Wireless Telegraph Station Licence, Grade - II
(iv) Restricted Amateur Wireless Telegraph Station Licence
(v) Short Wave Listener's Amateur Wireless Telegraph Station Licence.

5. Eligibility for Licence

(1) A licence may be granted subject to such conditions contained in Annexure I to these rules

(i) to a person-
(a) who is **a citizen of India**;
(b) who is **not less that 18 years of age**;
(c) who qualifies the Amateur Station Operator's Examination for the award of licence or holds either of the following certificate of proficiency, namely:
(i) Radio-communication Operators' General Certificates;
(ii)First or Second Class Telegraph Operators' Certificates:
Provided that the holder of a Special Radio Telegraph Operator's Certificate may also be considered eligible for the award of Amateur Wireless Telegraph Station Licence Grade II.

(iii) To a bonafide amateur radio society, club, a school, college, institute or university in India, which has the aim of participating in the 'amateur service': Provided that the licence shall be issued in the name of an authorized official of the society, club, school, college, institute or university in India, holding a category of licence appropriate to the transmission to be conducted by the station, including amateur radio beacon transmissions.

(2) Notwithstanding anything contained in sub-clause (b) of clause (i) of sub-rule (1), the central government may grant, to bonafide experimenters between the ages of 14 and 18 years, Amateur Wireless telegraph Station Licence, Grade I and to those between the ages of 12 and 18, Amateur Wireless Telegraph Station Licence, Grade II or Restricted Amateur Wireless Telegraph Station Licence or Short Wave Listeners' Amateur Wireless Telegraph Station Licence: Provided that the application for the grant of such licences shall be accompanied by a certificate from the head of the educational institution, recognized by a board or university in India,

attended by the applicant or from his legal guardian that the applicant is interested in and competent to conduct experiment in wireless telegraphy.

(3) Notwithstanding anything contained in sub-clause (c) of clause (i) of sub-rule (1), the Central Government may recognize, subject to any conditions it may prescribe from time to time, such other Radiotelegraph Operators' Certificates or Amateur Station Operators' Certificate as are issued by a competent authority in India or any other country as equivalent to qualifications referred to in aforesaid sub-rule, for the purpose of grant of a licence under those rules.

6. Application for licence

(a) an individual, or

(b) an amateur radio society or club or a school, college or an institute or an university in India

-shall be made to the central government in Annexure II or Annexure III respectively to these rules, together with all the subsidiary forms and documents duly filled in and completed in all respects.

7. Eligibility for admission to Amateur Station Operator's Examination

No person shall be eligible for admission to an examination for the grant of licence unless-

(a) such a person fulfils the provisions contained in sub-clause (a) of clause (i) of sub-rule (1) and either sub-clause (b) of clause (i) of sub-rule (i) or sub-rule (2) of rule 5;

(b) such person pays the fees on the following scale, namely:

(i) Advanced Amateur Station Operator's Examination	Rs. 25.00
(ii) Amateur Station Operator's Grade I Examination	Rs. 20.00
(iii) Amateur Station Operator's Grade II Examination and Restricted Wireless Telegraph Station Examination	Rs. 10.00

(c) a period of at least one month has elapsed since he last appeared in an examination and failed.

8. Examinations

(1) The examinations for the grant of a licence shall be held at a place and on a date as may be notified by the Central Government from time to time.

(2) An application for licence in Annexure II to the rules shall be submitted not later than the 15th of the month preceding that in which it is desired to take the examination.

(3) Any person admitted to the examination and found guilty of impersonation or of submitting fabricated documents or documents which have been tampered with or of making statements which are incorrect or false or of suppressing material information or of using or attempting to use unfair means in the examination hall or otherwise resorting to any other irregular or improper means for obtaining admission to, the examination may, in addition to rendering himself liable to criminal prosecution, be debarred either permanently or for a specified period from appearing in any of the examinations held for the award of licence under these rules:

Provided that no order under this sub-rule shall be made unless the person concerned has been given a reasonable opportunity for making a representation against the action proposed to be taken.

(4) If any person is found guilty of any malpractice referred to in sub-rule (3) after the grant of a licence to such person, the central government may, in addition to prosecuting him cancel the licence so given:
Provided that the central government may, pending the cancellation of the licence, suspend or endorse such licence:
Provided further that no order under this sub-rule shall be made unless the person concerned has been given a reasonable opportunity for making a representation against the action proposed to be taken.

9. Grant of Licence

Every category of licence shall be in the form set out in Annexure III to these rules.

10. Observance of conditions of licence, Convention and rules under the Act

(1) Every licenced amateur wireless telegraph station shall be established, maintained and worked in accordance with:

(a) the conditions contained in Annexure I to these rules;

(b) the provisions of the Convention;

(c) the rules made by the Central Government under section 7 of the Act for the conduct of wireless telegraphs in so far as they are applicable.

(2) Notwithstanding sub-rule (1) the Central Government may modify, vary, cancel or revoke any of the conditions of licence contained in the said Annexure I at any time either by specific notice in writing to the licencee, or by means of a general notice published in the Official Gazette or in a newspaper published in New Delhi.

(3) The licencee shall at his own expense, give effect to any variations in the conditions of licence,

11. Period of validity

A licence granted under these rules shall be issued for a period of 2 years or 5 years, as the case may be, commencing on the date of issue of the licence and expiring on the last day of the month preceding the month of issue.

12. Fee for licence

(1) A licence fee on the following scale shall be paid to the Central Government on receipt of instructions from that Government and in the manner directed by it –

Category of licence	Fee for 2 years	Fee for 5 years
(i) Advanced Amateur Wireless Telegraph Station Licence	Rs. 50/-	Rs. 125/-
(ii) Amateur Wireless Telegraph Station Licence, Grade I	Rs.40/-	Rs.100/-
(iii)Amateur Wireless Telegraph Station Licence, Grade II; Restricted Amateur Wireless Telegraph Station Licence; Short wave Listener's Amateur Wireless Telegraph Station Licence	Rs.25/-	Rs.60/-

The licence fee shall not be refundable on ground of licensee's inability to establish or make use of the licensed amateur wireless telegraph station or for adjustments towards higher category of licence.

(2) No holder of a licence shall be entitled to a refund of fees paid therefore on the ground of his inability to establish or make use of the licensed amateur station.

13. Authorized frequency bands, power and emission

A holder of licence shall use, as appropriate to the licence, such frequency bands, power and classes of emission as are set out in Annexure V of these rules:

Provided that the central government may by special or general order make changes in the usage of frequency bands, power and types of emission where that Government is satisfied, that it is expedient to do so keeping in view, among others, the provisions of the convention need for enforcement of better technical standards in respect of equipment and national and international radio interference pattern.

14. Renewal of licence

(1) On the expiry of the validity of a licence, it may be renewed for a period of two or five years, as the case may be, if the licencee-

(a) makes an application for renewal, not earlier than 2 months but before the date of expiry;

(b) has actively operated an amateur wireless telegraph station during the validity of his licence and provides a certificate to the effect that he has made contacts with other amateur stations on at least 40 occasions per year, and in case of short wave listener, has intercepted amateur station on at least 40 occasions per year;

(c) Pays, a fee on the following scale, namely:

Category of licence	Fee for 2 years	Fee for 5 years
(i) Advanced Amateur Wireless Telegraph Station Licence	Rs. 50/-	Rs. 125/-
(ii) Amateur Wireless Telegraph Station Licence, Grade I	Rs.40/-	Rs.100/-
(iii) Amateur Wireless Telegraph Station Licence, Grade II; Restricted Amateur Wireless Telegraph Station Licence; Short wave Listener's Amateur Wireless Telegraph Station Licence	Rs.25/-	Rs.60/-

(2) The licence fee shall not be refundable on ground of licensee's inability to establish or make use of the licensed amateur wireless telegraph station or for adjustments towards higher category of licence.

(3) The document showing the renewal of licence issued by the Central Government shall be kept along with the licence to which it refers.

(4) It shall not be obligatory for the Central Government to issue a notice that the licence is due for renewal.

15. Surcharge for late renewal

In case the holder of licence does not apply for its renewal prior to the date of expiry of the licence referred to in sub-rule (1) of rule 14, he may apply for the renewal of licence subsequently also but within a period of two years after the date of expiry of the licence on payment of a surcharge at the rate of Rs. 10/- for every half year or part thereof. The licence in such a case, shall be renewed from the date of expiry of licence.

16. Register for wireless telegraphy apparatus

Every licensee shall maintain a register in respect of all wireless telegraphy apparatus established, maintained and worked by him at the amateur station in the form set out in Annexure VI of these rules.

17. Location of Amateur Station

The location of the amateur station shall be specified in the licence along with the usual residence of the licensee endorsed therein and it shall be operated only from the place so fixed.

Provided that the central government may permit the change of location if the licensee applies for it in writing giving particulars of the change and submits the licence for endorsement, and pays a fee of rupees five.

18. Portable and mobile amateur station

The central government may in addition to an amateur station licensed for a specified location issue a special authorization to establish, maintain and work an amateur station as a mobile station installed on board a motor vehicle or as a portable station or for the purpose of exhibiting the operation of amateur station at jamborees or for specific technical investigations in radio if -

(i) Application for such authorization is made at least 10 weeks in advance indicating, amongst other, the period for which the authorization is required, area of operation and the purpose;
(ii) The applicant holds an Advanced Amateur Wireless Telegraph Station Licence or an Amateur Wireless Telegraph Station Licence Grade I;
(iii) The applicant pays an additional fee of Rs. 10.

(2) The special authorization shall, in addition to the conditions specified in rule 10, be subject to conditions, namely:

(i) The special authorization shall not be issued for a period more than 90 days and may be extended for a further period of 90 days on request and on payment of fee of Rs.10/-;
(ii) The licencee's amateur station at the fixed location and the mobile station shall not communicate with each other;
(iii) The suffix 'MO' shall be added to the call-sign already authorized to the licensee, such call-sign shall be followed by the location of the station;

(iv) such other conditions as the central government may determine from time to time.

(3) The special authorization may be withdrawn or the conditions contained therein varied at any time by the central government.

19. Amateur Station on board ship

(1) Without prejudice to rule 17, the Central Government may on receipt of an application authorize establishment, maintenance and working of an amateur station on board a ship registered in India. Applications for such authorization shall be accompanied by a written approval of the master or owner of the ship concerned.

(2) The establishment, maintenance and working of amateur station on board ships shall, in addition to the conditions specified under rule 10, be subject to such other conditions as the Central Government may determine from time to time and such conditions, among others, shall include the following, namely:

(i) The amateur station on board ship shall be operated only while the ship is in international waters or Indian territorial waters. Its operation within the territorial waters of another country shall be in conformity with laws and regulations of the country concerned.

(ii) It shall not be operated whilst the ship is in any harbour in India;

(iii)The call-sign allotted to such stations shall have suffix 'MS' followed by the call-sign of the ships in case of radiotelegraphy/official name of the ship in case of radiotelephony.

(iv)The amateur station on board a ship shall be independent of ship radio communication, radio navigation and other safety services radio equipment and shall be operated in such a manner as not to cause harmful interference to these services of the ship. The amateur station shall have source of electrical energy independent of the ship station and shall also be electrically independent of it.

(v) The amateur station on board a ship shall discontinue operation at any time on request of an officer of the Central Government, the master or radio officer of the ship or any land station.

20. Loss and Issue of Duplicate of Licence and Document showing the Renewal of Licence

(1) A person whose Licence or the document showing the renewal of licence has been lost, mutilated or destroyed shall notify the same to the central government. An application in Annexure VII of these rules for the duplicate shall be made to the central government embodying a statement of the circumstances involved in the loss, mutilation or destruction of the licence or the document showing the renewal of licence for which a duplicate is required. If the licence or the document showing the renewal of licence has been lost, the applicant must state the circumstances in which it was lost and that reasonable search has been made for it, and further that in the event it be found, either the original or the duplicate shall be returned for cancellation. The mutilated licence or the document showing the renewal of licence for which the duplicate is required should be forwarded along with the application for cancellation.

(2) The central government may issue duplicate copy of any licence or the document showing the renewal of the licence and the following charges shall be levied for such issue:

(i) For duplicate of licence - Rs. 10

(ii) For duplicate of the document showing the renewal of licence- Rs. 5

21. Revocation of licence

(1) The central government may, at any time, revoke the licence-

(i) On the breach of any of the conditions of licence contained in Annexure I; or

(ii) In default of payment of any fees payable under these rules;
Provided that, before revoking a licence, the licensee shall be given a reasonable opportunity of making a representation against the action proposed to be taken.

(2) The licensee shall not be entitled to any compensation arising out of revocation of his licence nor will any part of the fees paid for the licence shall be refunded for the period a licence stands revoked.

22. Transfer of licence

A licence shall not be transferable:

Provided that the central government may permit the transfer of a licence granted to an authorized official of an amateur radio society or club or a school, college or an institute or an university in India in favour of his successor if such successor holds a category of licence appropriate to the transmissions to be conducted by the amateur station.

23. Operation of licenced amateur station

No person other than the licensee shall be permitted to operate the licensed amateur station:

Provided that -

(a) In the presence of the licensee himself, the station may be operated by another person holding a valid licence of comparable or higher category. The licensee, however, shall be personally responsible for the observance of these rules as if he operates the station.

(b) In case of a licence issued to an authorized official of an amateur radio society, club, school, college, institute or university in India, the station may be operated by-

(i) a person who holds a licence equivalent or of higher category;

(ii) a person who holds a lower category of licence, where he operates the station on the frequency bands, emissions and power allocated to his category.In each of the cases aforesaid the licensee shall be responsible for the observance of this rule.

24. Surrender of licence

A licence which is revoked or which has become invalid and licensee does not desire to renew it shall be surrendered to the central government for cancellation and record.

25. Dual holding of licence

No person shall be granted more than one licence at the same time: Provided that the central government may exempt a person, holding a licence is his name for amateur radio society or a school, college or an institute or an university in India, from the operation of this rule.

26. Admission of foreign nationals in examination and grant of licence

(1) Notwithstanding anything contained in these rules the central government may, subject to such terms and conditions as it may impose from time to time, admit a person, who is not a citizen of India, to an examination for the grant of a licence or grant him a licence if otherwise qualified.

(2) The conditions under sub-section (1) shall, among others, include the following, namely:

(i) The country of which the applicant is citizen, grants reciprocal facilities to Indian nationals:
Provided that it shall not apply where the central government considers that reciprocal facilities are not necessary;

(ii) The applicant is above the age of 18 years.

(iii) The applicant is holder of an appropriate category of amateur station operator's certificate or licence issued by a competent authority in any other country and recognised by the central government.

(iv) The licence under this rule shall be initially granted for a period of one year or for the period of validity of visa, for which the applicant's passport is endorsed, whichever is less, on payment of a proportionate licence fee as prescribed in Rule 12 subject to a minimum of fees payable of one year.

27. Penalty for breach of these rules

Any breach of these rules, other than a breach, which is an offence under section 20 or 21 of the Act, shall be punishable with fine, which may extend-

(i) when the person is licenced under the Act, to Rs.1000 and in the case of continuing breach a further fine of Rs.200 for every day after the first during the whole or any part of which the breach continues;

(ii) when a servant of the person so licenced or another person is punishable for the breach one fourth of the amounts specified in clause (i).

28. Repeal and saving

(1) On the commencement of these rules, the Indian Wireless Telegraphy (Amateur Service) Rules 1958, shall cease to be in force,

(2) Notwithstanding such cesser-

(a) where before such commencement any person had passed the Amateur Station Operators Certificate Grade I or Grade II Examination, such person shall not be required to pass any such examination under these rules;

(b) where, before such commencement any person was granted Amateur Wireless Telegraph Station Licence Grade-I, or any such Licence was renewed and the period for which such Licence was granted or renewed extends beyond the commencement of these rules, then, such Licence shall continue to be in force for the period specified in the licence.

Annexure I

CONDITIONS
FOR
THE CONDUCT OF
AMATEUR WIRELESS TELEGRAPH STATION

[See rules 5 & 10]

1. Use of the Amateur Station

(1) The amateur station shall be used as part of self-training, intercommunication and technical investigations in radio techniques solely with a personal aim and without pecuniary interest:

Provided that when the station is licensed to an amateur radio society or club, or a school, college or an institute or a University, the use of the station shall be confined to technical investigations and training in radio communication techniques without pecuniary interest.

(2) The station may also be used for the purpose of receiving transmissions in the standard frequency service to facilitate operation of the station within the authorized frequency bands.

(3) Except as provided in these rules, the licensee shall not assign, under-let or otherwise dispose of or admit any person to participate in the benefits of the licence.

II. Messages

(1) (a) Radio communications may be exchanged with other stations similarly authorized. The amateur stations are forbidden to communicate with amateur stations of countries whose administrations have notified the International Telecommunication Union of their objection to such radio communication.

(b) Transmissions shall be made in plain language and limited to messages of a technical nature relating to tests and to remarks of personal character (excluding business affairs or transactions) in which the licensee, or the person with whom he is in communication, are directly concerned and for which, by reason of their unimportance, recourse to the public telecommunication service is not justified.

(c) Special recordings for reproducing sinusoidal tone or tones within the audio frequency spectrum that may be either constant or steadily changing in frequency may be used.

(2) The licensee is forbidden to transmit-

(a) Messages like the reproduction of broadcast programmes or tape recordings or transmissions of entertainment value or music;

(b) False or misleading calls, or signals, news, advertisements, communications of business, statements on topics of political or industrial controversy;

(c) Superfluous signals or any matter which is indecent or of obscene character or of a seditious tendency or which is grossly offensive or such as is likely to arouse racial, religious, or communal animosity; and

(d) Messages for pecuniary reward or any messages for, or on behalf of third parties;

(3) Notwithstanding clause (a), sub-condition (1) and clause (d), sub-condition (2) the licensees in case of failure of normal telecommunication facilities, are permitted to handle third party messages, pertaining to natural calamities such as earthquake, flood, cyclones and wide spread fires, originating from and addressed to a

competent civil authority namely, (a) district magistrates or deputy commissioners or collectors of the district and (b) any other officer authorized by authorities mentioned at (a) above. The licensee shall inform by letter addressed to the licensing authority regarding the use of his amateur station for such purposes on each such occasion.

III. Frequencies, Emission and Power

The amateur station shall be operated on frequencies that are within the frequency bands authorized to respective categories of licences under rule 13 and on such classes of emissions and power not exceeding that specified in the said rule.

IV. Frequency control and measurement

(1) The transmitting apparatus shall be tuned as accurately as possible to ensure that no energy is radiated on any frequency outside the limits of the authorized frequency bands.

(2) The licensee shall have at the licensed amateur station a reliable frequency measuring equipment to verify, each time the frequency of the transmitter is changed and whenever it is necessary to check the transmitted frequency that emissions are within the authorized frequency bands. The licensee shall take all steps necessary to maintain the accuracy of the frequency measuring equipment.

V. Non-Interference

(1) The amateur station shall be so designed, constructed, erected, maintained and worked as not to cause interference with any wireless telegraph service functioning, within or without India, in accordance with the provisions of the convention or the wireless signaling between any fixed, land or mobile stations of Indian land, naval or air force or between such stations and any station abroad:

Provided that in the event of interference being caused by the station the licensee shall discontinue or restrict transmissions, pending adjustment of the equipment, on request from-

(a) The Central Government; or
(b) Any land station.

(2) The licensee shall deploy all necessary means to ensure that the radiated frequency in free from harmonics, key clicks, hum and other forms of spurious emissions.

(3) The licensee shall ensure that the transmitter is not over modulated.

(4) The use of class B emissions (damped waves) is forbidden.

VI. Log (Diary of the radio service)

(1) A chronological record of all transmissions emanating from or received at the amateur station shall be kept in bound book (not loose leaf) showing the following:

(a) Date and time of each transmission;
(b) A summary of the communications exchanged;
(c) A brief description of the experiments and tests undertaken;
(d) The call-sign of station or stations with which messages have been exchanged, times of establishing and terminating communication with each station and the frequency and type of emission employed in each case:
(e) Time of opening and closing down the amateur station;

(f) In case of portable or mobile amateur station the particulars of temporary location.

(2) All times in the log shall be stated in the Indian Standard Time.

(3) No gaps shall be left between entries in the long and they shall be made and initialed at the time of receiving and transmitting.

(4) In case the station is operated by a person other than the licensee (see rule 23), the licence shall ensure that log is signed by that person indicating his name, call-sign and licence number.

(5) Licensee shall preserve the log for a period of one year from the date of last entry therein before it is destroyed:
Provided that no log shall be destroyed for such further period as the Central Government may direct.

(6) The form of log is shown in the Table attached to these conditions.

VII. Wireless Telegraphy Apparatus

(1) The amateur station shall be equipped for reception as well as transmission except in the case of Short Wave Listeners Amateur Wireless Telegraph Station Licence when it shall be equipped for the former only.

(2) The wireless telegraphy apparatus and other accessory equipment used or intended to be used by the licencee shall be so arranged as not to endanger the safety of licensee or other persons.

(3) The wireless telegraph apparatus shall be kept in a safe condition and housed in such manner as to preclude access to unauthorized persons.

(4) The transmitter shall be of a type that has frequency stability comparable to that of a crystal control.

(5) Meters of standard accuracy shall be installed to measure the D.C. power input to the anode circuit of the final radio frequency stage of the transmitter.

(6) The aerial used or intended to be used shall be so erected, fixed, or placed a not to cross above or fall on to any power, telegraph or telephone line. If required, the licensee shall take necessary steps to guard, to the satisfaction of the owner or owners concerned, so as to prevent any damage being done in the event of a break occurring in the aerial. The aerial installation shall not cause hazard to flight of aircraft and their heights shall be within the limits specified by the Director General of Civil Aviation in India from time to time. The licensee shall, if so directed, install and maintain beacon lights on and paint the mast of the station at his own cost.

VIII. Secrecy of Correspondence

If any message which the licensee is not entitled to receive is, nevertheless received, the licencee shall not make known or allow to be made known its contents, its origin or destination, its existence or the fact of its receipt to any person (Other than duly authorized officer of the Central Government or a competent of legal tribunal) and shall not reproduce in writing, copy or make any use of such message or allow the same to be reproduced in writing, copied or made use of.

IX. (1) General Radiotelegraph and Radiotelephone Procedure

(a) Before transmitting, the station shall take precautions to ensure that its emissions will not interfere with transmissions already in progress. If such interference is likely the transmission shall not commence till there is an appropriate break in the communications in progress.

(b) The call sign endorsed in the licence shall be sent for identification at the beginning and at the end of each period of transmission. When the period of transmission exceeds 10 minutes the call sign shall be repeated. Licencee shall not make transmission without identification or with false identification.

(c) Prolonged calls and transmissions shall be avoided.

(d) When it is necessary to spell out call sign, certain expressions, difficult words, abbreviations, figures etc., the phonetic alphabet and figure code given in the Convention shall be used.

(2) Call and Reply Procedure

(a) The call shall consist of The call sign of the station called not more than three times; The word DE (in case of radiotelegraphy) and the words 'This is' (in case of radiotelephony) and the call sign of the calling station, not more than three times.

(b) The reply to call shall consist of the call sign of the calling station, not more than three times; The word DE (in case of a radiotelegraphy) and the words 'This is' (in case of radiotelephony) the call sign of the station called, not more than three times.

(c) The call may be sent three times at intervals of two minutes; thereafter it shall not be repeated until an interval of 10 minutes during which the operator shall list in the frequency band in which the call has been made.

(d) In case of general call to all stations the signal 'CQ' (in case of radiotelegraphy) and the words 'Hello all stations' or the signal 'CQ' (in case of radiotelephony) shall replace the call sign of the station called in the calling procedure.

(3) End of Transmission and Work

(a) Transmissions of a message shall be terminated by the signal AR (in case of radio, telegraphy) and by the word 'Over' (in case of radiotelephony).

(b) The end of work between two stations shall be indicated by each of them by means of the signal VA (in case of radiotelegraph) and by the word 'OUT' (or VA spoken as Victor Alfa) in case of radiotelephony.

(4) Tests:

(a) When it is necessary to make test signals either for the adjustment of a transmitter or a receiver or for any experiment, such signals shall not be continued for more than 3 seconds and shall be composed of series of VVV followed by the call-sign of the station emitting the test signals. In case of radiotelephony series of VVV shall be replaced by the figures 1,2,3,4... spoken in the figure code.

(b) For tests exceeding 30 seconds an artificial aerial shall be used.

(c) Emission of carrier wave is forbidden unless such wave is subjected to intelligible modulation.

X. Inspection

(1) Any officer authorized by the Central Government in that behalf in writing by them, may at all reasonable times enter the station solely or jointly with any other person or persons for the purpose of inspecting and may inspect, examine or test any apparatus conduct of such inspections and tests and make available the licence, the station log or other records for examination by the inspecting officer.

(2) The licencee when called upon to do so by the Central Government shall arrange to forward the licence, the logbook, or any other record or date for examination by that Government.

XI. Powers to take possession of the Amateur Station and to order interception of message:

(1) On the occurrence of any public emergency, or in the interest of the public safety, the Central Government or a State Government or any officer specially authorized in this behalf by the Central Government or a State Government may, if satisfied that it is necessary or expedient so to do, take temporary possession (for so long as the public emergency exists or the interest of the public safety requires the taking of such action) of the Amateur Station.

(2) On the occurrence of any public emergency or in the interest of the public safety, the central government or a State Government or any officer specifically authorized in this behalf by the Central Government or a State Government may, if satisfied that it is necessary or expedient so to do in the interests of the sovereignty and integrity of India, the security of the State, friendly relations with foreign states or public order or for preventing incitement to the commission of an offence, for reasons to be recorded in writing, by order, direct that any message of class of messages relating to any particular subject, shall not be transmitted or received or shall be intercepted by the station or shall be disclosed to the Government making the order or an officer thereof mentioned in the disclosed to the Government making the order or an officer thereof mentioned in the order.

(3) The licencee shall not be entitled to any compensation in respect of the exercise of the powers conferred by sub condition (1) and (2) of this condition.

XII. The licencee shall indemnify the Central Government against all actions, claims and demands which may be brought or made by any person, body corporate or company in respect of any injury arising from any act licenced or permitted by the licence.

XIII. A copy of the Indian Wireless telegraphs (Amateur Service) Rules, 1978 shall be kept at the Amateur Station.

Table

[See Condition VI(6)]

Specimen Form of Log

Sl. No. of Contact	Date	Time	Frequency & Type of Emission & power input to final stage (FEP)	Station Called by	Station heard or worked (RST)	Report Received (RST)	Time of Termi-nating QSO	Time of Record Experiment & tests /summary of communication	QSL Card (Sent/ received)	Initials

Under the above rules, a licence may be granted, subject to certain conditions to a person, who is a citizen of India and not less than 18 years of age (subject to relaxation indicated at para 1 below) and who qualifies Amateur Station Operators's Examination Certificate of Proficiency issued by this Ministry i.e. (I) Radio Communication operator's General Certificate; (ii) First or Second Class Radio Telegraph Operator's Certificate; (iii) The holder of a special radio telegraph

Operator's Certificate may also be considered eligible for the award of Grade II licence.

The following categories of licences are issued:
(The fees for examination are shown alongside)

(i) **Advanced** Amateur Wireless Telegraph Station Licence	Rs. 25/-
(ii) **Amateur** Wireless Telegraph Station licence **Grade I**	Rs. 20/-
(iii) **Amateur** Wireless Telegraph Station Licence **Grade II**	Rs. 10/-
(iv) **Restricted** Amateur Wireless Telegraph Station Licence	Rs. 10/-
(v) **Shortwave Listener's** Amateur WirelessTelegraph Station Licence	No examination

The central government may grant to bonafide experimenters between the agees of 14 and 18 years, Amateur Wireless Telegraph Station Licenc Grade I and to those between the ages of 12 and 18 years, Amateur Wireless Telegraph Station Licence Grade II, Restricted Amateur Wireless Telegraph Station Licence or Shortwave Listeners Amateur Wireless Telegraph Station Licence.

The examination for the award of various categories of Amateur Wireless Telegraph Station Licence are held at various Monitoring Stations of this ministry, as per the syllabus contained in the above mentioned rules. **A person desiring to appear in these examinations should apply on the prescribed application form (enclosed) to the nearest monitoring station along with the prescribed examination fee. In no case the application may be forwarded to WPC, Ministry of Communications, New Delhi.**

The examination fee varies from Rs. 10/- to Rs.25/- depending upon the category of examination. After a decision is taken to grant the licence, an additional fee of Rs. 25/- to Rs.50/- as the case may be, will be required towards the grant of licence. **The fees are required to be paid in the form of bank draft obtainable from any branch of the State Bank of India and drawn in favour of Pay & Accounts Officer (Headquarters), Department of Telecommunications, New Delhi 110001 (code 7687).**

The particulars of the venue and date, etc. of the examination will be communicated to the candidates by the officer-in-charge of the concerned monitoring station on receipt of the complete application form with requisite fee.

Following should accompany the application:

1. Nationality Certificate/Character Certificate in the prescribed proforma enclosed.
2. 2 copies of photograph duly signed on front side. The size of the photograph must be 3x4 cms.
3. Examination fees, in the form of bank draft, of the appropriate amount. The draft should be obtained from any branch of State bank of India and drawn in favour of **'Pay & Accounts Officer (Headquarters), Department of Telecommunications'**. It should be payable at State Bank of India, New Delhi Service Branch (Code No. 7687).
4. Result Sheet, duly filled in (in duplicate).
5. Personal particulars (in quadriplicate) in the prescribed proforma.

Annexure-II

APPLICATION FROM AN INDIVIDUAL FOR A LICENCE TO ESTABLSISH, MAINTAIN AND WORK AN AMATEUR WIRELESS TELEGRAPH STATION IN INDIA.

(See rules 6 & 8)

1. Name (In Block letters):

....

(Last name) (First) (Middle)

2. Father's/Husband's Name and address : ....

....

3. (a) Address (Present)

....

....

(b)Address (Permanent)

....

....

4. (a)Date of Birth (b)Place of Birth (c)Nationality (d)Occupation

5. (a) Category of Licence applied for (b) exact location of the Station

6. (a) If you are exempted from appearing in any part of the examination, give details of your qualifications

(b) If you wish to appear for the qualifying examination, give the preferred centre and date of examination

Centre Month of Examination

(c) Do you hold any other licence earlier, if so give details

Licence No.____________________Call-sign, if any____________________

(Duly filled in application form should be submitted to the concerned Wireless Monitoring Station only)

DECLARATION

I hereby solemnly declare that the foregoing facts are true and correct and nothing is false therein and nothing material has been concealed therefrom. I also agree that in case any information given by me herein before is found false at a later date, the licence, if granted, will be cancelled.

I further solemnly give an undertaking that I will not either directly or indirectly divulge to any person, except when lawful authorized or directed to do so, the purport of any message which I may transmit or receive by means of any wireless apparatus operated by me or which may come to my knowledge in connection with the operation of said apparatus.

I have carefully read and understood the rules contained n the Indian Wireless Telegraphs (Amateur Service) Rules, 1978 and undertake to abide by them and observe the conditions of the licence. The licensed station shall not be made accessible to any unauthorized person at any time.

Signature of witness:	Signature of applicant
Name (in block letters)	Name (in block letters)
Address:	
Date:	Date:
Place:	

Note :

1. An attested copy of birth certificate or school leaving certificate must be accompanied along-with the application.
2. Enclose a certificate in support of nationality in the prescribed Performa, indicated in Appendix III from one of the officers listed therein.

Annexure-III

APPLICATION FOR A LICENCE TO ESTABLISH, MAINTAIN AND WORK AN AMATEUR WIRELES TELEGRAPH STATION BY AN AMATEUR RADIO SOCIETY OR CLUB OR A SCHOOL, COLLEGE OR AN INSTITUTE OR A UNIVERSITY IN INDIA

(See rules 6 & 8)

1. Name and address of the Amateur Radio Society/Club/School/Institute etc.

2. Particulars of authorized official of the Society/Club/School etc. in whose favour licence is desired

Name Designation

Date of Birth Place of Birth Nationality Occupation

3. (a) Category of licence applied for (b) exact location of the station

4. Particulars of Amateur Wireless Telegraph Station Licence held by the authorized official

Category of Licence Licence No. Date of Issue

5. Particulars of the Amateur Radio Society or club, school etc.

(a) If registered, given its particulars:

(b) In case of school, college or institute, give the name of Board or University by which it is recognized.

(c) Give in brief its aims and objectives:

(d) If affiliated to any radio amateur organization, give its particulars:

(e) Give the names of office bearers:

(f) Mode of operation of the station including its normal hours of working :

6. Particulars of Apparatus to be used:

Category of Apparatus/ Manufacturer's name /Type No/ Frequency Range /RF power output/
Transmitter :
Receiver :
Frequency Measuring Device :

DECLARATION

I hereby solemnly declare that the foregoing facts are true and correct and nothing is false therein and nothing material has been concealed therefrom. I also agree that in case any information given by me herein before is found false at a later date, the licence, if granted, will be cancelled.

I further solemnly give an undertaking that I will not either directly or indirectly divulge to any person, except when lawful authorized or directed to do so, the purport of any message which I may transmit or receive by means of any wireless apparatus operated by me or which may come to my knowledge in connection with the operation of said apparatus.

I have carefully read and understood the rules contained n the Indian Wireless Telegraphs (Amateur Service) Rules, 1978 and undertake to abide by them and observe the conditions of the licence. The licensed station shall not be made accessible to any unauthorized person at any time.

Signature of witness: Signature
of applicant

Name (in block letters) Name (in block letters)
Address:
Date: Date:
Place:

Note :
1. An attested copy of birth certificate or school leaving certificate must be accompanied along with the application.

2. **Enclose a** certificate in support of nationality in the prescribed Performa, indicated **in Appendix** III from one of the officers listed therein.
3. **Attach a** copy of the rules and regulations or constitution.
4. **Attach the** minutes of the relevant meeting.

PERSONAL DETAILS OF THE APPLICANT

(To be submitted with **three extra copies** on separate sheet)

1.Full Name (In Block letters): ____________________________

2.Date & Place of Birth: ____________________________

3. Age: ______ Years________Months.

4. Height: ___________cm

5. Colour of: (i)Eyes__________(ii)Hair_______________

6. Complexion: ____________________________

7. Any special peculiarities of mark: ____________________________

8. Present Address: ____________________________

____

9. Permanent home address: ____________________________

____

10. Nationality: ____________________________

11. Occupation (Major work or profession for which you receive money or activity which occupies the majority of your time) ____________________________

____

____

____

12. Father's name and home address (if dead, give last address)Aliases if any: ____________________________

____

____

13. Type of license applied for: ____________________________

14. Proposed location of station: (Details of house No., Street No., Road No.) ____________________________

____

____

Dated:____________

Signature of the applicant

(Full name giving expansion of initials)

NATIONALITY CERTIFICATE

Certified that I have known Shri/Smt./Km. ______________________________,
Son/Daughter of Shri______________________for the last______________
Years and that to the best of my knowledge and belief he/she bears a good moral character. He/She is of ______________nationality.
He/She is not related to me.

Address: Signature

NOTE:

This certificate should be from one of the officers listed below:

1. Gazetted Officers of Central or State Governments.
2. Members of Parliament or State Legislatures.
3. Sub-divisional Magistrate/Officer.
4. Tehsildars or Naib/Deputy Tehsildars, authorized to exercise magisterial powers.

ANNEXURE IV

[See rule 9]

Licence No.

GOVERNMENT OF INDIA
MINISTRY OF COMMUNICAITON

LICENCE TO ESTABLISH, MAINTAIN AND WORK AN AMATEUR WIRELESS TELEGRAPH STATION IN INDIA.

Having satisfied, by examination or otherwise, that Shri .... possesses the requisite technical qualifications as prescribed under the Indian, Wireless Telegraphs (Amateur Service) Rules, 1978, the Central Government in exercise of the powers conferred under the authority of section 4 of the Indian Telegraph Act, 1885 (13 of 1885), hereby grant to him an .... to establish, maintain and work a wireless telegraph transmitting and receiving station, detailed below, during the term of period commencing on the day of the date hereof and terminating on the ....19 .... when this licence becomes invalid unless renewed further by way of a document showing the renewal of Licence.

The licence is governed by the Indian Wireless Telegraphs (Amateur Service) Rules, 1978, Particulars of the Station :

Location: Call-sign:

Issued by the Government of India in the
Ministry of Communication
New Delhi :
Dated :

Deputy/Assistant Wireless
Adviser to the Govt. of India
in the presence of .... Date ....

Signature of Licencee
Date ....

Latest amendment to the Indian Wireless Telegraph (Amateur Service) Rules, 1978, vide Notification dated 4th October, 1985.

In pursuance of the provisions of rule 13 of the Indian Wireless Telegraph (Amateur Service) Rules, 1978 the Central Government hereby authorises the following frequency bands, emission and power to the holder of Amateur Wireless Telegraph Station Licence. This supercedes the frequency bands, emission and power prescribed in the Annexure-V to the above said rules in pursuance to Notification No, R-11014/14/82-L.R. dated 23rd May, 1983.

ANNEXURE V

Frequency bands, emission and power

Category of Licence	Frequency bands	Emission	Maximum D.C. input power unless otherwise specified
(a) Restricted Amateur Wireless Telegraph Station Licence. See Note (v) below.	144-146 MHz 434-438 @	A3E, H3E, J3E, R3E, F3E	10 Watts (terrestrial service only authorised)
(b) Amateur Wireless Telegraph Station Licence Grade II. See Note (vi) below.	1820-1860 kHz* 3500-3700 kHz 3890-3900 kHz 7000-7100 kHz 14000-14350 kHz 18068-18168 kHz $ 21000-21450 kHz 24890-24990 kHz $ 28000-29700 kHz	A1A, A3E, H3E, J3E, R3E	50 Watts
	144-146 MHz 434-438 MHz @	A1A, A2A, A3E, H3E, R3E, J3E, F1B, F2A, F3E	10 Watts (terrestrial service only authorised)
(c) Amateur Wireless Telegraph Station Licence Grade I. See Note (vi) below.	1820-1860 kHz* 3500-3700 kHz 3890-3900 kHz 7000-7100 kHz 14000-14350 kHz 18068-18168 kHz $ 21000-21450 kHz	A1A, A2A, A3E, H3E, R3E, J3E, F1B, F2A, F3E, F3C, A3C, A3F	150 Watts

Category of Licence	Frequency bands	Emission	Maximum D.C. input power unless otherwise specified
	24890-24990 kHz $ 28000-29700 kHz		
	144-146 MHz 434-438 MHz @ 1260-1300 MHz @ & 3300-3400 MHz @5725-5840 MHz @	-do-	25 Watts for terrestrial service. Amateur Satellite Service is permitted in the appropriate sub-bands in accordance with Radio Regulations and in those cases the maximum output RF power (e.i.r.p.) is 30 dbw.
(d) **Advanced Amateur Telegraph Station Licence. See Note (i) below**	1820-1860 kHz* 3500-3700 kHz 3890-3900 kHz 7000-7100 kHz 14000-14350 kHz 18068-18168 kHz $ 21000-21450 kHz 24890-24990 kHz $ 28000-29700 kHz	A1A, A2A, A3E, H3E, R3E, J3E, F1B, F2A, F3E, F3C, A3C, A3F	150 Watts
	144-146 MHz 434-438 MHz @ 1260-1300 MHz @ & 3300-3400 MHz @ 5725-5840 MHz @	-do-	50 Watts for terrestrial service. Amateur Satellite Service is permitted in the appropriate sub-bands in accordance with Radio Regulations and in those cases the maximum output RF power (e.i.r.p.) is 30 dbw.

---

* On primary shared basis as per the relevant provisions of Radio Regulations.
$ The authorisation is on non-interference and non-protection basis.
@ On secondary basis as per the relevant provisions of Radio Regulations.
& 1260-1270 MHz for Earth to space satellite service only.

The above authorisation is subject to site clearance as per the procedure prescribed by the Standing Advisory Committee on Radio Frequency Allocation (SACFA) as applicable.

Note: (i) Following sub-bands of frequencies are authorised with enhanced R.F. power to holder of Advanced Amateur Telegraph Station Licence

3520-3540 kHz 3890-3900 kHz 7050-7100 kHz 14050-14150 kHz 14220-14320 kHz 21100-21400 kHz	All emissions as authorised	400 Watts

(ii) For A3F emission, the transmission shall be restricted to call-sign of the station, location and other particular of the amateur station. They shall be limited to point to point test transmission employing a standard interlace and scanning with a bandwidth not more than 4 kHz.

(iii) DC input power is the total direct current power input to the final stage of the transmitter.

(iv) In case of Short Wave Listener's Amateur Licence, the holders are permitted to listen to all the bands authorised to Amateur Service.

(v) The syllabus for the examination of the Restricted Amateur Wireless Telegraph Station Licence shall be same as per Part I of Amateur Station Operator's Grade II examination.

(vi) The holder of Amateur Wireless Telegraph Station Licence, Grade II shall be entitled for authorisation of radio telephony emission on his providing proof of having made 100 contacts with other amateur stations using CW (Morse Code).

Note: The 10.100 MHz to 10.150 MHz band is released on non-interference basis for a period of 6 months w.e.f. 1 August, 2000.

D. Syllabus of Amateur Station Operator's Certificate (ASOC) Examination for the award of Amateur Station Operator's Licence

The ham radio licensing examination is conducted to ascertain that the person going to be a ham radio operator is equipped with the knowledge and proficiency which is necessary to communicate using a wireless transceiver without causing interference to the other radio communication services. The course covers basic electronics and radio theories as well as the existing national and international rules related to amateur radio communication in radiotelephony (voice) and radio telegraphy (Morse Code). The person who wants to become a ham should at the same time be able to show his proficiency in Morse Code sending and receiving. The examination is conducted at the 22 Wireless Monitoring Stations (Annexure-I) located throughout the country. The examination is held for four different categories of licence. They are the :

(1) Advanced Grade Licence
(2) Grade I Licence
(3) Grade II Licence
(4) Restricted Grade Licence.

Anyone above 12 years of age can obtain Amateur Radio Station Operator's Licence after passing the examination/s mentioned above. **It is also possible to establish an Amateur Radio Club Station with a licensed ham in charge of it.**

The application form for Amateur Radio Station Operator's Certificate Examination can be obtained from :

The Assistant Wireless Advisor to the Govt. of India,
Wireless Planning & Coordination (WPC) Wing, Amateur Radio Section,
Ministry of Communications, Dak Bhavan,
Parliament Street, New Delhi-110001

The application form can also be obtained from the Wireless Monitoring Station of the Ministry of Communications located nearest to your hometown. The filled-in Application Form along with all other necessary documents **should be sent to the Wireless Monitoring Station located nearest to your home town** or where you wish to appear for the examination.

Syllabus

Part-I

Section I

Radio Theory and Practice (**Applicants holding degree in telecommunication, or electronics and electrical communication, or a degree recognized by the central government as equivalent to the above degree shall be exempted from appearing in SECTION I of the test**).

Section II

National and International regulations applicable to the operation of amateur radio station and those relating to the working of station generally.

Part II - Morse Code

Section I

Morse code **receiving.**

Section II

Morse code **sending.**

Detailed Syllabus

Amateur Radio Operator's Grade I & II Certificate Examination

Part-I

Section I : Radio Theory and Practice

Elementary electricity and magnetism

Elementary theory of electricity, conductors and insulators, units, Ohm's law, resistance in-series and parallel, conductance, power and energy, permanent magnets and electromagnets and their use in radio work; self and mutual inductance; types of inductors used in receiving and transmitting circuits, capacitance; construction of various types of capacitors and their arrangements in series and/or parallel.

Elementary theory of alternating currents

Sinusoidal alternating quantities-peak, instantaneous, RMS, average values, phase; reactance, impedance; series and parallel circuits containing resistance, inductance, capacitance; power factor, resonance in series and parallel circuits; coupled circuits; transformers for audio and radio frequencies.

Thermionic valves

Construction of valves; thermionic emission, characteristic curves, diodes, triodes and multi-electrode valves; use of valves as rectifiers, oscillators, amplifiers, detectors and frequency changers, power packs, stabilization and smoothing.

Elementary theory and construction of semiconductor devices

Diodes and Transistors.

Radio receivers

Principles and operation of TRF and super-heterodyne receivers, CW reception, receiver characteristics-sensitivity, selectivity, fidelity; adjacent channel and image interference; AVC and squelch circuits; signal to noise ratio.

Transmitter

Principles and operation of low power transmitter; crystal oscillators, stability of oscillators.

Radio propagation

Wavelength, frequency, nature and propagation of radio waves; ground and sky waves; skip distance; fading.

Aerials

Common types of transmitting and receiving aerials.

Frequency measurement

Measurement of frequency and use of simple frequency meters.

SECTION II : Radio Regulations

(a) Knowledge of :
(i) the Indian Wireless Telegraph Rules, 1973; and
(ii) the Indian Wireless Telegraphs (Amateur Service) Rules, 1978.
(b) Knowledge of International Radio Regulations as relating to the operation of amateur stations with particular emphasis on the following:
Designation of Emission,
Nomenclature of the frequency and wavelength,
Frequency allocation to amateur radio service,
Measures against Interference,
Interference and tests, Identification of stations,
distress and urgency transmissions,

Amateur Stations,
Phonetic alphabets and figure code.

(c) Standard frequency and time signal services in the world.

(d) The following 'Q' codes and abbreviations which shall have meaning as assigned to them in the International Telecommunication Union (ITU) convention :

QRA, QRG, QRH, QRI, QRK, QRL, QRM, QRN, QRQ, QRS, QRT, QRU, QRV, QRW, QRX, QRZ, QSA, QSB, QSL, QSL, QSO, QSU, QSV, QSW, QSX, QSY, QSZ, QTC, QTH, QTR and QUM.

Telegraphic (Morse code) abbreviations: AA, AB, AR, AS, BT, C, CFM, CL, CQ, DE, K, KN, NIL, OK, R, TU, VA, WA, WB.

The written examination for Grade II licence is of one hours duration. The maximum number of marks is 100. **Candidates must secure at least 40 per cent in each section and 50 per cent in aggregate to pass.** The syllabus for Grade I licence is the same as that for Grade II licence, but the **written examination for Grade I licence is of two hours duration**. The maximum number of marks is 100 and candidates must secure at least **50 per cent in each section and 55 per cent in aggregate for a pass.**

Part II : Morse Code

(a) Section I : Morse Receiving (Speed: 5 words per minute)

The test piece will consist of a plain language passage of 125 letters, five letters counting as one word. Candidates are required to receive for five consecutive minutes at the speed of 5 words per minute from a double headgear headphone receiver, international Morse code signals from an audio frequency oscillator keyed either manually or automatically. A short practice piece may be sent at the prescribed speed before the start of the actual test. Candidates will not be allowed more than one attempt in each test. The test may be written in ink or pencil but must be legible. Bad handwriting and over-writing will render a candidate liable to disqualification. More than five errors will disqualify a candidate.

(b) Section II : Morse Sending (Speed: 5 words per minute)

The test piece will consist of a plain language passage of 125 letters, five letters counting as one word. Candidates are required to send on an ordinary key for five consecutive minutes at the minimum speed of five words per minute. A short practice piece may be allowed before the actual test. Candidates will not be allowed more than one attempt in the test. Efforts should be made to correct all errors. However, more than five uncorrected errors will disqualify a candidate. The accuracy of signaling, correct formation of characters and the correctness of spacing shall be taken into account.

A candidate is required to pass both in Part I and Part II. In the case of candidates qualifying in Part I only, the licence shall be restricted to radiotelephone operations in the VHF ham band only.

Morse Code test for Grade I

Receiving-(Speed: 12 words per minute)

The test piece will consist of a plain language passage of 300 characters which may comprise letters, figures and punctuation (punctuation are indicated below). The average words shall contain five characters and each figure and punctuation will be counted as two characters. Candidates are required to receive for five consecutive minutes at a speed of 12 words per minute. Other conditions are the same as applicable to Grade II Examination.

Punctuations

Full stop, Comma, Semi-colon, Break sign (BT), Hyphen and Question mark.

Sending-(Speed: 12 words per minute)

The test piece will be similar to Morse receiving test. Candidates are required to send for five consecutive minutes at a speed not less than 12 words per minute. Other conditions are the same as applicable to Grade II examination.

A candidate is required to pass both in Part I and Part II simultaneously.

Advanced Amateur Station Operators' Examination

Part I-Written Test

(a) Section 1: Radio Theory and Practice

In addition to the syllabus prescribed for Grade II Examination, following items shall be included in the syllabus of Advanced Amateur Station Operators' Examinations:-

(i) **Motors and generators:** Elementary principles and construction of alternators, motors and generators.

(ii) **Alternating current:** Construction of transformers, transformer losses, transformer as a matching device.

(iii) **Measuring instruments:** Moving coil and moving iron meters, frequency meters.

(iv) **Semiconductor devices and transistors:** Elementary principles of conduction and construction, symbols, biasing methods.

(v) **Power supplies:** Half-wave and full-wave rectifiers, smoothing and regulation, bridge rectifier.

(vi) **Modulation:** Principles of frequency modulation.

(vii) **Transmitters and receivers:** Elementary principles of transmission and reception of facsimile and television signals, elementary principles of transmitters and receivers employing single side band.

(viii) **Propagation:** Characteristics of ionosphere and troposphere. Properties of different reflecting layers, optimum working frequency, day and night frequencies.

(ix) **Aerials:** Principles of radiation, aerials for different frequency bands including aerials for microwave.

(x) **Space communications:** Elementary principles of communication via satellite.

(b) Section 2: Radio Regulations

Syllabus is same as prescribed for Grade II Examination. The test is of 3 hours duration. The maximum number of marks is 100 and candidate must secure at least 50 per cent in each section and 60 per cent in aggregate for a pass.

Part II- Morse Code

Syllabus is same as prescribed for Grade I Examination.

E. Question and Answer Section on Amateur Radio Rules & Regulations

Q. What do you mean by 'Amateur Radio Service'?

'Amateur Radio Service' is a two-way radio communication service available to persons who are licensed by the communication authority to carry out experimentation in the field of radio communication techniques. The Indian Wireless Telegraphs (Amateur Service) Rules 1978 defines 'Amateur Service' as "***a service of self training, inter-communication and technical investigations carried on by amateurs that is, by persons duly authorised under these rules interested in radio technique solely with a personal aim and without pecuniary interest***".

Q. What types of messages are forbidden to be transmitted from an amateur radio station?

A ham radio operator is allowed to transmit in plain language (Morse Code, RTTY, Packet radio etc. included) and his message shall be of a technical nature related to tests, remarks of personal character, which are not related to business affairs or transactions. He is forbidden to transmit:

(i) Messages like the reproduction of broadcast programmes or tape recordings or transmissions of entertainment value or music.

(ii) False or misleading calls, or signals, news, advertisements, communications of business, statements on topics of political or industrial controversy.

(iii) Superfluous signals or any matter which is indecent or of obscene character or of a seditious tendency or which is grossly offensive or such as is likely to arouse racial, religious, or communal animosity; and

(iv) Messages for pecuniary reward or any messages for, or on behalf of third parties (i.e. non-amateurs).

Q. Is third party communication allowed in India in 'Amateur Radio Service'?

Third party messages originating from a non-amateur or meant for a non-amateur are not allowed in India, except in case of failure of normal telecommunication facilities during earthquake, flood, cyclones, wide spread fires or during any other disasters. Under such circumstances, a ham radio operator can handle third party messages pertaining to disasters. Such messages should originate from or addressed to a competent civil authority namely, (a) district magistrates or deputy commissioners or collectors of the district and (b) any other officer authorized by the authorities mentioned at (a) above.

Q. What is 'Secrecy of Correspondence'?

If any message which the ham radio operator is not entitled to receive is, nevertheless received, the ham radio operator shall not make known or allow to be known its contents, its origin or destination, its existence or the fact of its receipt to any person (other than duly authorized officer of the central government or a competent legal tribunal) and shall not reproduce in writing, copy or make any use of such message or allow the same to be reproduced in writing, copied or made use of.

Q. What is a 'Ham Radio Net'?

A ham radio net is a voluntary radio communication network formed under the initiative of a few hams, which is maintained at scheduled time/times of the day (everyday or at scheduled days). The heart of the net is the 'net controller', who takes messages from the hams joining the net and pass it on to its respective destination. Different nets may have different objectives. For example **'Air NET India'** is the National Emergency Traffic (NET) net run by the **Amateur Radio Society of India** (ARSI). This net is conducted everyday from 7:00 PM or 7:30 PM on **14.150 MHz** ± QRM to handle any emergency medical traffic, other emergency traffic and to check the radio wave propagation condition. But one of the main objectives of this net is to provide the facility to the Indian hams to establish contact between two hams. A ham 'X' can pass on the request to the 'net controller' regarding his willingness to contact a ham 'Y'. The 'net controller' then helps both the station to make the contact on a mutually decided frequency. So every active hams should have the habit of checking into this kind of net regularly.

Q. What is a distress call?

A distress call is a call given from a ship, aircraft or vehicle indicating that the caller is threatened by grave and imminent danger, which requires immediate assistance. In **radiotelephony** transmission, the distress signal consists of the word ***MAYDAY*** (pronounced as the French expression ***'m'aider'***) spoken three times followed by the words THIS IS and the identification of the station seeking assistance. A distress message should be followed by the distress call.

It contains name of the ship, aircraft or vehicle, position, type of distress and the type of assistance asked for including any other relevant information to facilitate rescue operation.

In **radiotelegraphy**, the distress signal consists of the letters ***SOS*** sent in Morse Code characters - - - _ _ _ - - - (SOS). All these characters should be transmitted three times as a single signal where ***dashes*** are to be emphasized to enable distinguish them clearly from the ***dots.*** A typical distress message may look like: **SOS SOS SOS CQ CQ CQ DE** followed by the call-sign. When the distress traffic is over, the distress station should end its transmission with the Q-Code. It looks like: **SOS CQ CQ CQ DE 'call-sign' QUM SK.**

Q. What action should you take if you receive a distress call?

The distress call has **absolute priority** over all other transmissions. Hence it would be your utmost duty to

- listen to the distress call and stop your transmissions if you were previously occupying that frequency;
- acknowledge receipt of the distress message if the station in distress can copy your signal.
- At the same time, it would be your duty to ensure that your transmission does not interfere with transmissions of other stations, which may be better situated to render assistance.
- Even if you cannot render assistance, you should direct the attention of other stations in the nearby frequencies, because they might be in a position to render immediate assistance.
- You shall also try to inform the appropriate authorities, who might be able to conduct a rescue operation.

Q. What is an 'Urgency Signal'?

Urgency signal is a wireless message which indicates that the calling station has a vary urgent message to transmit concerning the safety of a ship/vehicle or that of a person but the message cannot be ranked as distress message. **Obviously, the urgency signal should be given priority over all other transmissions except distress call.**

In radio telephony, the word **PAN** is repeated three times pronouncing it as the French word ***'panne'***. Other procedures to be followed in this type of traffic is same as that in distress traffic.

In radio telegraphy, the urgency signal consists of the group **XXX** (_ • • _ _ • • _ _ • • _) sent slowly three times. Letters of each group should be clearly separated from each other. The urgency signal transmitted by a ship can be addressed to a specific station. However, a coast station can transmit its urgency signal to all the ship stations after the approval of a responsible authority.

Q. What is a 'Safety Signal'?

A safety signal is a message concerned with the safety of ships/vehicles indicating a meteorological warning (e.g. storm), danger to navigation warning or other navigational-aid message. Safety Signal is an important message because a delay in its transmission or reception can bring a disaster.

In radiotelephony, safety signal consists of the word **'SECURITY'** pronounced as ***'say-cure-ity'***.

In radio telegraphy, it consists of the three repetitions of the group **TTT** (_ _ _) sent slowly followed by the station call-sign. Letters of each successive group should be clearly separated from each other.

Q. What do you understand by the word 'phonetics' in amateur radio communication?

If we listen to a two-way amateur wireless conversation for the first time in our life, we would come across certain words, which perhaps we never heard before! There is every possibility that we mistake these words for some kind of secret codes! These words in fact are internationally used for plain language **(conversation in secret code language is not allowed in amateur radio communication)** conversation and are known as phonetics.

A ham radio operator has to face different types of hurdles during an ongoing communication. There may be static noise, signal fading, interference from other station operating at close frequencies, local noises in the radio room, unusual voice accents of the other operator, improper pronunciation of words etc.. During these and many other difficulties, it has been found that use of phonetics improves the intelligibility in communication. For example, the letter **'D'** is represented by the word **'Delta'** in phonetics while the letter **'B'** is represented by **'Bravo'**. To distinguish **'M'** from **'N'**, hams use the words **'Mike'** and **'November'** respectively.

Phonetic alphabet is useful when calling distant station or when the band is crowded, or when for any reason the station called is expected to have difficulty in copying voice signals. For example, the word 'Solstice' can be spelt using phonetic alphabet as ***Sierra Oscar Lima Sierra Tango India Charlie Echo.*** A person conversant in listening to such phonetics gets habituated in spontaneously writing down the exact word out of these phonetics! He feels more comfortable at writing down a message spelt out in phonetics rather than simple mentioning of each letters.

Phonetics are to avoid confusion and not to create confusion! Many letters of the alphabet sound similar unless very clearly heard. B may be heard as G or D or V. The word 'bed' may be heard as 'bet' or 'pet'. So, if we spell it out with phonetics like Bravo Echo Delta, the confusion easily gets eliminated! Good operating procedures include using the standard phonetic alphabet to help communicate more clearly. The recommended phonetics are those prescribed by the International Radio Regulations. The numbers are spelled differently to suggest a particular pronunciation. Also, nine was changed to "*niner*" to avoid confusion with the German word "*nein*" for "no".

When first making contact with another Ham, it is a good idea to say call signs in phonetics to give the other side a better chance of understanding them correctly.

Phonetics used by amateur radio operators

Letter	Word used as phonetics	Spoken as
A	Alpha	AL FAH
B	Bravo	BRAH VOH
C	Charlie	CHAR LEE
D	Delta	DELL TAH
E	Echo	ECK OH
F	Foxtrot	FOKS TROT
G	Golf	GOLF
H	Hotel	HOH TELL
I	India	IN DEE AH
J	Juliet	JEW LEE ETT
K	Kilo	KEY LOH
L	Lima	LEE MAH
M	Mike	MIKE
N	November	NO VEM BER
O	Oscar	OSS CAH
P	Papa	PAH PAH
Q	Quebec	KEH BECK
R	Romeo	ROW ME OH
S	Sierra	SEE AIR RAH
T	Tango	TAN GO
U	Uniform	YOU NEE FORM
V	Victor	VIK TAH
W	Whiskey	WISS KEY
X	X-ray	ECKS RAY
Y	Yankee	YANK KEY
Z	Zulu	ZOO LOO

Phonetics used against figures or marks

Figure or mark	Word used as phonetics	Spoken as
0	NADAZERO	NAH-DAH-ZAY-ROH
1	UNAONE	OO-NAH-WUN
2	BASSOTWO	BESS-SOH-TOO
3	TERRATHREE	TAY-RAH-TREE
4	KARTEFOUR	KAY-TAY-FOWER
5	PANTAFIVE	PAN-TAH-FIVE
6	SOXISIX	SOK-SEE-SIX
7	SETTENSEVEN	SAY-TAY-SEVEN
8	OKTOEIGHT	OK-TOH-AIT
9	NOVENINE	N0-VAY-NINER
Decimal point	DECIMAL	DAY-SEE-MAL
Full stop	STOP	STOP

Q. What are Q-codes?

A 'Q-code' consists of three letters starting with the letter 'Q'. Q-codes are devised to facilitate faster communication in Morse code. Instead of sending a long sentence, the amateur radio operator can just send a combination of three letters to represent a long sentence. If the amateur radio operator asks something to his fellow operator, then the Q-code is followed by a question mark. If the Q-code is used to represent a statement (not a question), then it is not ended with a question mark. For example, if you want to ask your friend on the air whether he is busy (Are you busy?); the Q-code will be 'QRL?'. If you want to say that you are busy, send 'QRL'. There are nearly 100 Q-Codes used by the marine radio operators. We have mentioned below the Q-codes required to be learnt by an amateur radio operator. Q-codes are very often used during the voice communication also.

QRA?	What is the name of your station?
QRA	The name of my station is ....
QRG?	Will you tell me my exact frequency (or, that of ......)?
QRG	Your exact frequency (or, that of .....) is ....kHz (or MHz).
QRH?	Does my frequency vary?
QRH	Your frequency varies.
QRI?	How is the tone of my transmission?
QRI	The tone of your transmission is: (1) Good. (2) Variable. (3) Bad.
QRK?	What is the readability of my signals (or, those of....)?
QRK	Readability is: (1) Unreadable. (2) Readable now and then. (3) Readable with difficulty. (4) Readable. (5) Perfectly readable.
QRL?	Are you busy?
QRL	I am busy (or, busy with ....). Please do not interfere.
QRM?	Are you being interfered with?
QRM	I am being interfered with.
QRN?	Are you troubled by static noise?
QRN	I am troubled by static noise.
QRQ?	Shall I send faster?
QRQ	Send faster (.... wpm)
QRS?	Shall I send more slowly?
QRS	Send more slowly.
QRT?	Shall I stop sending?
QRT	Stop sending
QRU?	Have you anything for me?
QRU	I have nothing for you.
QRV?	Are you ready?
QRV	I am ready.
QRW?	Shall I inform ...... that you are calling him on ......kHz?
QRW	Please inform .... That I am calling him on ..... kHz.
QRX?	When will you call me again?
QRX	I will call you again at ....hours.
QRZ?	Who is calling me?
QRZ	You are being called by.
QSA?	What is the strength of my signals (or those of ......)?
QSA	Your signals are (1) Scarcely perceptible. (2) Weak. (3) Fairly good. (4) Good. (5) Very good.

QSB?	Are my signals fading?
QSB	Your signals are fading.
QSL?	Can you acknowledge receipt?
QSL	I am acknowledging receipt.
QSO?	Can you communicate with ..... direct or by relay?
QSO	I can communicate with .... Direct or by relay through ....
QSU?	Shall I send or reply on this frequency (or, on ....kHz)(with emissions of class...)?
QSU	Send or reply on this frequency (or, on .... KHz) (with emissions of class ....).
QSV?	Shall I send a series of 'V's on this frequency (or, ... KHz).
QSV	Send a series of 'V's on this frequency (or, ...kHz).
QSW?	Will you send on this frequency (or, ... kHz)(with emissions of class ...)?
QSW	I am going to send on this frequency (or, ...kHz) (with emissions of class ....).
QSX?	Will you listen to ....(call-sign) on .....kHz?
QSX	I am listening to ... (call-sign) on .....kHz.
QSY?	Shall I change my transmission to another frequency?
QSY	Change your transmission to another frequency.
QSZ?	Shall I send each word or group more than once?
QSZ	Send each word or group twice (or, ... times).
QTC?	How many telegrams have you to send?
QTC	I have ..... telegrams for you (or, for ......).
QTH?	What is your position in latitude and longitude (or, according to any other indication)
QTH	My position is ...latitude ......longitude (or, according to any other indication).
QTR?	What is the correct time?
QTR	The correct time is .....hours.
QUM?	Is the distress traffic ended?
QUM	The distress traffic is ended.

Q. What are the designation of emissions allotted to amateur radio service?

The most common designation of emissions, which are allotted to hams, are:

A1A : Continuous Wave (CW) Double side-band telegraphy for aural reception which contains quantized digital information without the use of modulating sub-carrier. (allotted to Grade II , Grade I and Advanced Grade Licence holders). **This is the most commonly used mode for Morse Code communication in the ham radio bands**

A2A: Continuous Wave (CW) Double side-band telegraphy for aural reception, which contains quantized digital information with the use of modulating subcarrier.

A3E: Double side-band single channel analog transmission containing telephony (including sound broadcasting). **Commonly known as AM** (Amplitude Modulation).

H3E: Single side band, full carrier single channel analog transmission containing telephony (including sound broadcasting).

J3E: Single side band, suppressed carrier single channel analog transmission containing telephony (including sound broadcasting). **This is the most common mode of voice communication in the ham radio bands.**

R3E: Single side band, reduced or variable-level carrier single channel analog transmission containing telephony (including sound broadcasting).

F3E: Frequency modulated single channel analog transmission containing telephony (including sound broadcasting). **Commonly known as FM.**

F1B: Frequency modulated single channel telegraphy transmission containing quantized digital information for automatic reception.

F2A: Frequency modulated single channel telegraphy transmission containing quantized digital information for aural reception.

F2B: Frequency modulated single channel telegraphy transmission containing quantized digital information with modulating sub-carrier for automatic reception.

F3C: Frequency modulated single channel analog facsimile transmission.

A3C: Amplitude modulated double side-band single channel analog facsimile transmission.

A3F: Amplitude modulated double side-band single channel analog video transmission.

Each letter/digit of the designation of emission represents independent meaning as assigned to them.

Q. What are the frequencies allotted to a Grade-I licence holder in India? How much power is allowed to a Grade-I licence holder? Can a Grade-II licence holder use radiotelephony for communication?

The radio frequencies allotted to a Grade-I licence holder in India are:

Short wave/High Frequencies (HF) :
1820-1860 kHz
3500-3700 kHz
3890-3900 kHz
7000-7100 kHz
14000-14350 kHz
18068-18168 kHz
21000-21450 kHz
24890-24990 kHz
28000-29700 kHz

VHF/UHF/SHF:
144-146 MHz
434-438 MHz
1260-1300 MHz
3300-3400 MHz
5725-5840 MHz

In India, a Grade-I licence holder is allowed to use 150 watts in the HF bands and 25 watts in the VHF/UHF bands.

A Grade-II licence holder is not authorized to use radiotelephony. However, the holder of Grade II Licence shall be entitled for authorisation of radio telephony emission on his providing proof of having made 100 contacts with other amateur stations using CW (Morse Code).

F. Radio Telephony Operating Procedure

Once you get your ham radio licence and the call-sign, it is time for you to start transmission. Radio waves are now-a-days a precious commodity and so the ham should not misuse them for his/her own ends. It is the duty of the ham to know the correct operating procedure. If a newly licensed ham radio operator is ignorant about the correct operating procedures, he may create nuisance in the band. A ham should also be aware about the International Operating Code devised by Paul M. Segal.

Code for a ham radio operator

1. The ham is **considerate**. He/she never knowingly uses the air (radio waves) in such a way as to lessen the pleasure of others.
2. The ham is **loyal**. He/she offers his/her loyality, encouragement and support to his/her fellow hams, his/her local clubs.
3. The ham is **progressive**. He/she keeps his/her station (radio equipment) abreast of science. It is well-built and efficient. His/her operating practice is above reproach.
4. The ham is **friendly**. Slow and patient sending when requested, friendly advice and councel to the beginner, kindly assistance, co-operation and consideration for the interests of other; these are the mark of the ham spirit.
5. The ham is **balanced**. Radio is his/her hobby. He/she never allows it to interfere with any of his/her duties he/she owes to his/her home, his/her job, his/her school or community-and lastly his/her knowledge and his/her radio station are always ready for the service of his/her country and his/her community.
6. A ham is **patriotic**. His/her amateur radio station and skill is always ready for service to his/her country and community.

Calling another station

A call may be given to another station either in voice or using the Morse code. But before giving a call, it is the duty of the ham to check whether the frequency he/she is going to use is already in use by other ham/s or not. Even though a particular frequency seems to be idle, it may not be so. Because, there may still be a ham sending his message whose signals are in skip with us (see questions & answers related to radio wave propagation) and another ham at a different location is listening to him. Giving a transmission in the same frequency in such a situation may interfere with the ongoing communication. So, prior to transmission, it should be ascertained by sending the message-"Is the frequency in use?". This should be repeated two more times and if no reply is received, we can occupy the frequency. After occupying a frequency, we can give a **'General Call'** or a **'Directional Call'**. A 'General Call' is a call given to all the stations. This means that you will reply to anybody from any part of the world. The message sounds like –"**CQ CQ CQ this is Victor Uniform Two.... (your call-sign suffix in phonetics) calling CQ on 20 metre and standing by**". The 'CQ' message may be repeated for three time before giving the **'standing by'** message. As you 'stand by', listen carefully for any possible reply. If no reply is received, you can continue giving your CQ call. There is also a **'Directional Call'** which is **directed to a particular country** or **a particular station**. A call directed to a particular country is like-"**CQ Japan CQ Japan CQ Japan this is Victor Uniform Two ....**". This means that you will reply to stations from Japan only. A call may be directed to a particular station also. In this case, the country name is to be replaced with the intended station 'call-sign'. **A person with the true ham spirit does not adhere strictly to his directional call, and as such should not deny reply to a ham from another country replying to his directional call (in the above example) until and unless he is in real emergency. Also there is nothing official about a ham radio operation.** Ham radio operators also form net. When a net is going on, you can also join the net once somebody in the net 'pulls you' into the net. To indicate that you want to join the net, a short **'BREAK'** call may be given.

After establishing contact and offering the initial greetings, **a signal report** should be given to the other station. Your name **(Handle)** and location **(QTH)** should then be spelled out clearly in internationally accepted phonetics. If the other ham finds difficulty in copying your voice signal due to poor propagation condition or due to the difference in pronunciation, you should not loose patience and the message should be repeated if requested. You can also give the weather report (**WX report**) by mentioning the temperature in degrees Celsius. After this, discussion regarding the antenna system and equipment (called-**"Working condition"**) begins. Before closing the conversation with a particular station, **73** message (meaning **'Best of Regards'**) should be conveyed to the ham and his family and indication should be given whether you are closing down (**going QRT**) your station, you are changing your frequency (**QSYing**) or you are still occupying the frequency. This will help other stations to follow you in case they want to make a contact with you. If the conversation takes long time, both the stations should repeat their call-sign at least at ten minutes interval.

Signal Report in Radio Telephony

When on-the-air contact between amateur radio stations is established, both the stations exchange signal reports. This gives the idea about how strongly the ham radio stations are receiving each other. For telephony (voice), Readability and Signal strength scale is devised.

Readability Scale		**Signal Strength Scale**	
R1	Hardly perceptible; unreadable	S1	Unintelligible; barely perceptible
R2	Weak; readable now and then	S2	Weak signals; barely readable
R3	Fairly good; readable but with difficulty	S3	Weak signals; but can be copied
R4	Good; readable	S4	Fair signals
R5	Very good; perfectly readable	S5	Fairly good signals
		S6	Good signals
		S7	Moderately strong signals
		S8	Strong signals
		S9	Extremely strong signals

A 59 (5 and 9) report is the best report in radiotelephony. You should be honest in giving a signal report. Don't give a good report just to please your friend! There may be some problem in the antenna system of your friend's station due to which you are receiving him poorly. Or there may be some problem in the audio quality of your friend's transmission. Under such a situation, giving a false report will just misguide your friend and your friend may not be able to detect/rectify the fault in his/her system.

G. Radio Telegraphy Operating Procedure

In radio telegraphy contact using Morse Code, the RST (Readability, Signal Strength and Quality of Tone) system of reporting is followed by the ham radio operators. Throughout the world, Morse code is still used very affectionately by thousands of ham radio operators. They make conversation as fluently as they do in voice using Morse code. In the early days of radio, communication by radiotelegraphy was the primary means to exchange messages between radio operators at all radio stations, including amateur radio stations. In fact Morse Code has many advantages over voice communication in certain situations, as well as for the sheer joy involved in this art of communication, which we have discussed in the chapter on Morse code learning. In Morse code also, either general CQ call or directional call can be given. The calling format is as follows:

General call:

CQ CQ CQ DE VU2XYZ VU2XYZ VU2XYZ AR PSE K

Specific/Directional Call:

CQ/VU2ABC CQ/VU2ABC CQ/VU2ABC DE VU2XYZ VU2XYZ VU2XYZ AR KN

In Morse code, long words are usually avoided and hence only the abbreviated form of the words are sent. There are certain Internationally accepted Morse Code abbreviations which you should remember and use during communication. '**AR**' is synonymous to saying '**over**' in voice (A voice message should be ended with the word 'over to .....'). '**K**' is the invitation to transmit which is synonymous to saying '**go ahead**' in voice communication. A message ended with **KN** indicates that the message was directed to a particular station only. During an ongoing communication also, the message should be ended with '**KN**' which provides the information to the other stations that communication was already in progress between two stations. Each sentence of the message should be separated by '**BT**'. Given below is a typical Morse code message.

VU2XYZ DE VU2ABC BT TNX FER CALL BT UR RST RST IS 579 BT MY NAME IS ....ES QTH IS .... BT OK? AR VU2XYZ DE VU2ABC KN

When you finally close your conversation with a particular station, indication should be given, i.e. the message should be ended with '**VA**' (meaning '**over and out with ......**). A typical closing message may look like-............. **VU2ABC DE VU2XYZ VA.** This means that VU2XYZ is now free to communicate with other stations.

The RST System

Readability	Signal Strength	Tone
R1-Unreadable	S1-Faint, signals barely	T1-Extremely rough hissing note
R2-Barely readable, occasional words distinguishable	S2-Very weak signals	T2-Very rough AC note, no trace of musicality
R3-Readable with considerable difficulty	S3-Weak signals	T3-Rough. Low-pitched AC note, slightly musical
R4-Readable with practically no difficulty	S4-Fair signals	T4-Rather rough AC note, moderately musical
R5-Perfectly readable	S5-Fairly good signals	T5-Musically modulated note
	S6-Good signals	T6-Modulated note, slight trace of whistle
	S7-Moderately strong signals	T7-Near DC note, smooth ripple
	S8-Strong signals	T8-Good DC note, just trace of ripple
	S9-Extremely strong signals	T9-Purest DC note

Abbreviations used in Radio Telegraphy (Morse Code)

AA	Artficial antenna or All after	HRD	Heard
AB	All before	HV	Have
ABT	About	K	Go ahead (general request)
AGN	Again	KN	Go ahead (directional request)
ANI	Any	KCS	Kilocycles
ANT	Antenna	LID	Bad operator
AR	Over	MNI	Many
AS	Wait	MO	Master Oscillator
BK	Break	MCS	Megacycles
BC	Broadcast	ND	Nothing doing
BCL	Broadcast band Listener	NW	Now
BCNU	Be seeing you	NIL	Nothing
BT	Separation	OB	Old Boy (Young male operator: a novice)
C	Yes	OM	Old Man (a male operator)
CFM	Confirm	OK	All correct
CL	Closed	OP	Operator
CO	Crystal Oscillator	PSE	Please
CQ	General Call	PX	Press
CONDX	Conditions	QRP	Very low power
CU	See you	QSL	Received
CUL	See you later	R	Roger (Copied OK)

CK	Check	RCVD	Received
CANS	Headphone	RCVR	Receiver
DE	This is	RPRT	Report
DF	Direction Finding	RPT	Repeat the message
DX	Long distance	RX	Receiver
ECO	Electron Coupled Oscillator	SA	Say
ERE/HR	Here	SED	Said
ES	And	SIGS	Signals
FER	For	SWL	Short Wave Listener
FB	Fine Business	TKS	Thanks
FR	For	TNX	Thanks
FONE	Telephony (voice)	TX	Transmitter
CKT	Circuit	TU	Thank you
GA	Go ahead/Good afternoon	U	You
CLG	Calling	UR	Your/ You are
GE	Good evening	VA	End of work
GM	Good morning	VY	Very
CPSE	Counterpoise	WA	Word after
GLD	Glad	WB	Word before
GND	Ground	WX	Weather
GUD	Good	WID	With
HI	Laughter	WKD	Worked
HPE	Hope	WL	Will
HR	Here	WUD	Would
XMTR	Transmitter	YF	Wife
XTAL	Crystal	YL	Young Lady
XYL	Wife	73	Best of regards
88	Love & Kisses		

(The abbreviations with bold typeface are according to syllabus for licencing examination)

Ham terminology

RUNNING BAREFOOT:	A RF transmitter running without an external linear RF amplifier.
CHARLIE WHISKY	Morse Code
CRYSTAL CONTROL CEREMONY:	Marriage ceremony of a ham radio operator
EYE BALL QSO:	When a ham meets another ham in person
HANDLE:	Name of the ham radio operator
HARMONIC:	Daughter or Son of the ham radio operator (just as the harmonic frequency generated out of the fundamental frequency!)
HOMEBREWED EQUIPMENT:	A home made apparatus
JUNK MARKET:	The market where old/used/defective component or devices are found
LIMA LIMA:	A Telephone call (Landline!)
RIG:	Wireless apparatus of the ham radio operator
SHACK:	Radio room
SILENT KEY:	Death of a ham radio operator
TICKET:	The Amateur Wireless Telegraph Licence

Part-III

Radio Theory and Practice

A. Elementary Theory of Electricity & Magnetism

What is electronics?

Electronics is the field of manipulating electrical currents and voltages using passive and active components that are connected together to create circuits. Electronic circuits range from a simple load resistor that converts a current to a voltage, to computer central processing units (CPUs) that can contain millions of transistors. Electronic devices operate by the movement of electrons through conductors, e.g. wires, and electronic components.

What are passive components?

Resistors, inductors, transformers and capacitors are called ***passive devices***. They don't alter their resistance, impedance or reactance when alternating currents (ac) are applied to them.

What are active components?

Vacuum tubes, diodes, transistors eto. are called active devices. They change their resistance or impedance when varying voltages are applied to them and as a result can amplify, rectify, modify or distort ac waveforms. Passive devices normally don't distort waveforms.

Matter and electricity

All matter consists of atoms. Each atom is primarily composed of three fundamental particles called electrons, protons and neutrons. At the centre of the atom is the nucleus formed by the combination of **protons**, particles with **positive charge**, and neutrons, particles with no intrinsic charge. Orbiting around the nucleus are the **electrons**, particles that have a **negative charge**. All these three particles are responsible for the chemical and electrical properties of atoms. **The size of the whole atom is of the order of 10^{-8} cm**. Atoms of all element except hydrogen contain one or more than one neutron in their nucleus. **Hydrogen is the simplest atom with one positively charged proton and one negatively charged electron orbiting it.**



A hydrogen atom

One or more atoms constitute a molecule, which is the tiniest representative of a particular substance showing all the characteristics of that substance. For example, if it is possible to divide a drop of water again and again until it cannot be divided further but still be water, this tiniest particle will be the molecule of water. A molecule of water contains two atoms of hydrogen (H) and one atom of oxygen (O).

What is an electron?

Electrons are the negatively charged stable elementary particles, which revolve around the nucleus of an atom in several possible and 'allowed' orbits. The mass of an electron is 9 x 10^{-28} grams. Proton is about 1840 times heavier than electron. There is always attraction between unlike charges. Because electron is much lighter than proton, hence it is pulled towards the proton and is primarily responsible for electrical conduction.

What is charge?

It is the property possessed by some elementary particles causing them to exert forces of attraction or repulsion on each other. The types of forces exerted by charged particles are differentiated by the terms negative and positive, the natural unit of negative charge being possessed by the electron. The proton has an equal amount of positive charge. A body is said to be charged when it contains an excess or lack of electrons with respect to its proton content. The unit of charge is coulomb (C) and symbol is 'q'. One coulomb is equivalent to 6.28 x 10^{18} electrons.

What is current?

Electrons moving in one direction under the influence of an electric field constitute an electric current. Atoms of a metal form a crystal lattice, and in the spaces between the lattices are the free electrons moving chaotically, wandering aimlessly here and there. These electrons can be made to acquire an aim by connecting the metal plate to the two poles of a voltage source (e.g. a battery). They will move towards the positive pole of the battery, and an electric current will begin to flow in the metal. An electric current can also flow in a gas. A voltage applied across a gas-filled tube causes ionization of the gas: free electrons stream towards the plate with the positive potential, colliding with the atoms in their way and detaching electrons from their orbits. The positive ions move towards the opposite end of the tube.

What is voltage?

Voltage is also called potential difference or electromotive force-EMF. Potential difference is defined as the work required from some energy source in moving a unit positive charge between two points in an electric field. It is the electronic potential energy between two points, and is the driving force that causes charge to flow. Its unit is volt (V). One volt is defined as the potential difference that requires one joule of energy to move one coulomb of charge. **Voltage is always measured relative to some other point in a circuit, e.g. the potential across a resistor.** Voltage measurement made at a single point in a circuit is made relative to the earth (ground), which is assigned an "absolute" voltage of zero.

Types of Electricity

Direct Current (DC)

The direct current flows in one direction in a circuit. DC voltage has a fixed polarity (e.g. a battery or an electrical cell) and the magnitude of the voltage remains constant. In an electrical circuit, the flow of electric current is indicated by an arrow mark originating from the positive terminal of the battery towards the negative terminal of the battery. This is the conventional method of showing the direction of current flow. But the real direction of electron flow is from the negative terminal of the battery to the positive terminal.


Resistor
Direction of electron flow
Battery (DC voltage source)
−
+
Conventional direction of current flow

Alternating Current (AC)

Alternating current flows first in one direction for one-half cycle and then in the opposite direction during the other half cycle. The same definitions apply to alternating voltage. AC voltage switches polarity back and forth. AC voltage/current has a wave-form which represents the frequency of the source. The wave-form of the household ac is known as the 'sine' wave. The magnitude of the A.C. voltage changes with time. AC is obtained from A.C. generators.



A Sine wave cycle. The upper half denotes the positive cycle and the lower half denotes the negative cycle

Advantage of AC

Heat is developed in all type of electrical circuits due to the flow of electric current. The magnitude of the D.C. being constant produces more heat in a circuit compared to the heat produced by an A.C. In long distance transmission lines, large amount of power will be dissipated in the form of heat if D.C. is used which can be reduced by the use of A.C.

A.C. Voltage can be measured in four different ways.

Peak Voltage

The value or amplitude of an A.C. voltage never remains constant. With an initial voltage of zero, the amplitude rises to a peak value, after which it again falls back to zero. After reaching zero, the direction of the current changes and the voltage rises to its negative peak. Peak voltage measurement is necessary to ensure or know that the amplitude of the A.C. voltage does not exceed a limit.

Instantaneous Voltage

It is also called the **average voltage**. The voltages, if measured, at different points of the half cycle of the sine wave will be the instantaneous voltages. But practically it is not possible. So one way to denote instantaneous voltage is to take the average voltage. In a sine wave A.C. voltage, the average voltage can be found out by multiplying the 'peak voltage' by a constant (value of the constant can be worked out to be equal to 0.367).

Root-Mean-Square Voltage

Measuring an A.C. voltage involves the use of a meter which measures AC Voltage in terms of how much DC voltage it would take to have the same effect in a circuit. Since during most of the cycle the AC has a value less than the value at its peak, or for that matter, than of a constant DC voltage, it will not be able to produce as much heat (in a heating element) as produced by the same amount of DC voltage. Power being proportional to either E^2 or I^2 ($P=E^2/R=I^2R$), if all the instantaneous values of a half cycle of sine-wave current (or voltage) are squared and then the average, or mean, of all the squared values is found, the square root of this mean value will be 0.707 of the peak value. This root-mean-square, or rms, value represents how effective a sinusoidal AC will be in comparison with its peak value.

The RMS value is the value of voltage of an AC source, the power consumed by whom is the same as by a d.c. voltage. That is, it is the effective value (Veff) of a sine-wave voltage found from the formula: $V_{eff}=V_{max} \times 0.707$

Effective Voltage

In a domestic AC supply, 230 volts is actually the effective voltage (V_{eff}). The actual voltage or the peak voltage (V_{max}) of the supply is : $V_{max} = V_{eff} / 0.707 = 325$ volts. Or, to determine a peak value of AC that will be as effective as a given DC, it is necessary to multiply the effective value given by the reciprocal of 0.707 (1/0.707), which is 1.414.

Magnetism

What is a magnet?

A piece of iron, nickel, cobalt, steel, alloy (e.g. alloy made from non-magnetic copper, manganese and aluminum) etc. usually in the form of a bar having properties of attracting or repelling iron and other materials which contain iron is called a magnet. But what gives it its force is not completely known. One of the theories to describe magnetism is the theory of domains. It says that materials that can be made into magnets have many tiny crystal like structures called domains. Each domain is made up of many atoms. Each domain has a small magnetic force of its own. When the material is not magnetized, the domains are haphazardly arranged pointing in all directions so that their tiny forces cancel each other. To make the material into a magnet, the domains need to be lined up so that their individual magnetic forces all help each other pull the same way. When ***most*** of the domains line up, the magnet becomes strong. When all of the domains line up in one direction, the magnet is saturated. It cannot be made any stronger regardless of how much you try to magnetise it.

In a magnetic bar, there are two poles: North and South. They are marked as 'North' and 'South' poles because, when the magnetic bar is suspended horizontally, one of the ends will always point towards the Earth's geographical north and the other pole towards the Earth's geographical south. This is because of the fact that the Earth itself behaves like a huge magnet. In a magnet, the like poles repel and the unlike poles attract-a reason for the specific alignment of the magnetic bar. The magnetic bar is surrounded by the invisible lines of forces which originate from the 'North' pole and terminate in the 'South' pole.



A bar magnet

Ferro-magnet

Iron, nickel and cobalt (including the alloy mentioned above) are considered ferromagnetic. Ferro-magnetic materials are difficult to be converted to magnet but once magnetized under the influence of another magnetic field, they cannot be completely demagnetized. Ferromagnetic materials are used to make permanent magnets. **One of the strongest permanent magnetic materials is a combination of iron, aluminum, nickel and cobalt called "Alnico".**

Paramagnetic material

A material within which an applied magnetic field in increased by the alignment of electron orbits is called paramagnetic material. They are made up of non-ferromagnetic atoms. When placed in a magnetic field, they may weakly attempt to line up in the direction of the magnetic field. Paramagnetic materials always become completely nonmagnetic when an external magnetizing force is removed from them.

Use of Permanent magnets in Electronics

Electricity and electronics cannot be discussed by leaving apart 'magnetism' separately. Permanent magnets are used in electronics to make electric meters, headphones, loudspeakers, radar transmitting tubes etc. Temporary ferromagnetic materials (known as soft ferromagnetic material) are also equally important in electricity and electronics to make devices, which may be quickly magnetized and demagnetized. Soft ferromagnetics, such as silicon steel and soft iron are used to make electromagnets, generators and electric motors etc..

Electromagnets

The flow of an electric current through a wire creates a circular magnetic field around the wire. This magnetic field has the highest intensity near the conducting wire and the intensity gradually decreases as the distance from the wire increases. The direction of these magnetic flux lines can be found by the 'left hand rule'. If the conducting wire shown below is grasped by the left hand, the curled fingers point to the direction of magnetic flux lines and the thumb shows the direction of electron flow.



The left hand rule

If a straight conducting wire is made into a loop giving it a 'coil' shape, the small magnetic loops around the wire overlap each other resulting in a more stronger magnetic field around the whole coil. The strength of the magnetic field depends on the number of turns in the coil, amount of current in the coil and the permeability of the core material. Air has a permeability of 1. But iron is more permeable than air and is capable of transferring the magnetic flux line more efficiently. Based on this principle, electromagnets can be made. An electromagnet consists of a coil surrounding a soft iron core. The core remains magnetized so long as there is flow of current in the coil. The direction of the magnetic field in a coil can also be found by the 'left hand rule'. If a coil is grasped in left hand, the curled fingers point to the direction of electron flow, the thumb shows the direction of magnetic flux and N pole of the coil.

Electromagnets have many applications in electronics. Two of the most important uses of electromagnetism are in **transformers** and **motors.** Electromagnetic relays, electric bells, buzzers are commonly used electromagnets. Electromagnetic relays are used as switching devices in electrical and electronic circuits.



Symbol of an electromagnetic relay

Transformers

Transformer is a device which consists of two coils arranged in a way so as to generate a magnetic coupling effect (the coupling effect is enhanced by winding the two coils on a common iron core) and thereby transfer electrical energy (AC voltage) from one coil (called the *primary coil*) to the another coil (called the *secondary coil*). A transformer works on the principle of 'mutual inductance'. One of the most useful characteristics of a transformer is its ability to step-up or step-down of AC voltages. The step-up or step-down ratio will be proportional to the turns in each coil, i.e.,,

$$V_S = N_S/N_P \text{ X } V_P$$

Where, V_S = Secondary voltage
N_S = Number of turns on secondary
N_P = Number of turns on primary
V_P= Primary voltage

The currents flowing in the primary and secondary follow a similar relationship, but in opposite ratio, i.e.

$$I_S = N_P/N_S \text{ X } I_P$$

Where, I_S = Secondary current
I_P =Primary current

In other words, a step-up in voltage produces a step-down in current and vice versa.



Symbolic form of a step-down transformer

Transformers as Coupling Device

Transformers are very useful to use in radio or audio frequency circuits as coupling devices. As well as providing coupling, they can act as 'amplifiers' to step up an audio or radio frequency voltage (but not as *power* amplifiers); and even more important for impedance (see page 72) matching. By choosing the proper turns ratio the impedance of a fixed load can be transformed to any desired higher or lower impedance, within practical limits. This can be a particularly important requirement when coupling transistor radio stages.

For impedance matching, the following relationship applies:

$$\frac{N_P}{N_S} = \sqrt{\frac{Z_P}{Z_S}}$$

Where,

Z_P=Impedance of the transformer looking into the primary terminals
Z_S=Impedance of the load connected to the secondary of the transformer

Resistors

What are resistors?

A resistor is a device designed to have a definite amount of resistance-used in circuit to limit current flow or to provide a voltage drop. Resistance (R) is the retarding force in a material that impedes the flow of current. The potential (E) needed to achieve a current (I) through a material that behaves linearly, e.g. conductors and resistors, is given by Ohm's law:

E=IR

Where,
E=emf (in volts, V)
I=intensity of current (in amperes, A)
R=Resistance (in ohms, Ω)

So, if we know any two values, we can find out the other value. The above formula can rearranged as shown below:

$I = {}^{E}/_{R}$ or Current in amperes= volts/ohms

From this formula, it is evident that-"**Current varies directly as the voltage and inversely as the resistance**".

The formula can also be arranged to find out the resistance in a circuit if the voltage and current are known.

$R = {}^{E}/_{I}$ or Resistance in ohms= volts/amperes

Practical Resistors

The resistance of a material depends on four physical factors:

(1) The **type of material** from which it is made. For example copper and silver are very good conductors of electric current, but iron is six times lesser in its conductivity than them.

(2) The **length** (greater the length greater is the resistance).

(3) **Cross-sectional area** (greater the cross-sectional area larger the amount of free electron implying lesser resistance).

(4) **Temperature** (except for carbon and other semiconductor materials).

So each material has a specific resistance inherent in them. **The specific resistance of a material is the number of ohms in a 1 foot long 0.001 inch diameter** round wire of that material at room temperature. Silver has the least specific resistance, i.e. 9.75 Ω and nichrome is an alloy, which has specific resistance as high as 660 Ω.

Wire-wound resistor

Nicrome or german silver wires are wound on a tubular ceramic form to make wire-wound resistor. Wire-wound resistors are generally available in values from **1 ohms to 300 kiloohms**. Power ratings of this type of resistors vary from **1 to 50 watts**.

Carbon resistor

Powedered carbon is mixed with a binding material and baked into small, hard tubes with wire attached to each end to make carbon resistors. The percentage of carbon in the mixture determines the resistance value in ohms. Carbon resistors are generally available in values from **10 ohms to 22 megaohms**. Power ratings of this type of resistors vary from **1/8 watt to 2 watts**.

Colour codes of resistors

Carbon resistors are colour coded to indicate their values. Each resistor has four colour bands on its body. The first band (the band which is nearest to the end of the resistor) is the first number. The second band is the second number. The third band is the multiplier, i.e. number of zeros following the second number.

Colour	Band 1	Band 2	Band 3
Black	0	0	
Brown	1	1	0
Red	2	2	00
Orange	3	3	000
Yellow	4	4	0000
Green	5	5	00000
Blue	6	6	000000
Violet	7	7	0000000
Gray	8	8	00000000
White	9	9	000000000

Resistors having values lower than 10 Ω have three colour bands. The third band is either golden or silver in colour. A golden band indicates that the first two numbers are to be multiplied by 0.1. A silver band indicates multiplication by 0.01. The tolerance of three band resistors is 20%. If the golden or silver band is the fourth band respectively, then they indicate a tolerance of 5% and 10% respectively.



The value of this resistor is 62000 Ω or 62 kΩ

Questions:

1. A circuit has a resistance of 100 ohms and voltage applied across the circuit is 20 volts. What is the amount of current flowing through it?

   We have, $I={}^{E}/_{R}$ or $I=20/100=0.2$ A (ampere) or 200 mA (milliampere)

2. Find out the voltage required to produce 3 A of current through a 50 Ω (ohms) resistor.

   We have, $IR=E$ or $3 \times 50 = 150$ V (volts)

Power and Energy

As mentioned above, heat is developed in the load resistor as a result of current flowing through it. In absence of the load, a battery despite having the electromotive force (EMF), cannot produce movement of electrons and no electrical work is accomplished. When there is a load across the battery, movement of electrons take place. The product of the EMF (in volts) and movement of electrons (in amperes) gives us the amount of electrical work accomplished whose unit is watt (W).

$$P=EI$$

Where P=power (in watts, W)

E=emf (in volts, V)
I=current (in amperes, A)

So, 1 V causing 1 A to flow through a 1 Ω resistor produces 1 W of power.

The above formula can also be expressed as

$P=EI=(IR)I=I^2R$ (because the ohm's law states: $E=IR$)

Or

$P=EI=E({}^{E}/_{R})={E^2}/_{R}$ (because the ohm's law states: $I={}^{E}/_{R}$)

Questions:

1. Find out the heat dissipated by a 50 Ω resistor when 0.25 A of current flow passes through it.

   We have, $P=I^2R$ or $P=0.25^2 \times 50=0.0625 \times 50=3.125$ W

2. Find out the power dissipated by a 10,000 Ω resistor connected across a voltage source of 250 V.

   We have $P={E^2}/_{R}={250^2}/_{10,000}=6.25$ W

3. Find out the maximum voltage that may be connected across a 20 W, 2000 Ω resistor.

   We have, $P={E^2}/_{R}$

   Or, $E^2=PR$

   Or,

   $E=\sqrt{PR}$

   Or,

   $E=\sqrt{20 \times 2000}$

   $E=200$ V

4. Find out the maximum current that can flow through a 100 Ω 1 W resistor.

   We have,

$$I=\sqrt{\frac{P}{R}}$$

Or,

$$I=\sqrt{\frac{1}{100}}=0.1\text{ A or }100\text{ mA}$$

What are conductors?

Materials which allow the flow of electric current through them are called conductors. Metals are known to be good conductors, with copper and silver among the best. The conductivity of a particular material depends on the number of free electrons present in it. A conductor may be a very good conductor, a fairly good conductor or a poor conductor. So, a greater conductivity or conductance implies lesser resistance and a lesser conductivity implies greater resistance. So, conductance (conductance is expressed in **siemens**, S) and resistance (R) are the same thing but from opposite viewpoints. They are said to be reciprocal of each other, i.e.

R=1/S or **S=1/R**

So the Ohm's law can be expressed in terms of conductance by using 1/S in place of R in the three foremulas:

E=IR=I(1/S) or **E=I/S**

$$I=\frac{E}{R}=\frac{E}{1/S}=E\left(\frac{S}{1}\right)\quad\text{or}\quad I=ES$$

$$R=\frac{E}{I}\quad\text{or}\quad\frac{1}{S}=\frac{E}{I}\quad\text{or}\quad SE=I\quad\text{or}\quad S=\frac{I}{E}$$

Resistance in series and parallel

The circuit shown here is a simple circuit with one load or resistor across a voltage source (e.g. a battery).



A simple circuit with one resistor and a battery

The circuit shown below is a series circuit where three resistors are connected one after another. It is evident from the diagram that there is only one path through which current flows.



A series circuit with three resistors and a battery

The circuit shown below is a **parallel circuit** where each resistor has its independent path for the flow of current from the same source of voltage.



A parallel circuit with three resistors in parallel

The circuit shown below consists of two batteries and three resistors in series. In a series circuit the same amount of current flows through all parts of each circuit. The resistors are connected in series to obtain a greater resistance and it is equal to the sum of the values of each resistor, i.e. 40 Ω. Two batteries are connected in series in this circuit to obtain the highest possible voltage which is the sum of the values of each battery, i.e. 20 V.



A circuit with three resistors in series (total=40 ohms) and two batteries in series (total=20 V).

From the Ohm's law, the current flowing through this circuit will be:

$I = {}^{E}/_{R}$ or $I = 20/40 = 0.5$ A

Precaution

We should be careful while connecting batteries in series, because, the maximum current possible through the circuit is no greater than the greatest current that the weakest battery can deliver. If one of the batteries in the above example is weaker than the other and capable of passing only, say, 0.2 A, it will be overworked, may overheat and the voltage across the terminal will drop.

In this type of circuit, the voltage that can be obtained across each resistor is called the **'Voltage drop'**. From the Ohm's law, the voltage across each resistor can be calculated. The voltage drop across the 30Ω resistor is 15 V (0.5 x 30) and the voltage drop across the 5Ω resistor (each) is 2.5 V. Thus the sum of the voltage-drops is equal to the source voltage (2.5+2.5+15=20V).

Internal Resistance of batteries

The battery might possess an internal resistance which is to be considered while calculating the various quantities in a circuit. If a 10 V battery has 1Ω internal resistance and connected across a 9Ω load resistor, the amount of current flowing through the circuit would be 1 A. A voltage drop of 1 V will take place inside the battery and hence the 10 V battery will produce only 9 V across its terminals when connected to the 9Ω load. When the circuit is open (no currents flowing through it), the voltage across the battery would be 10 V.

Resistors in parallel circuit



A parallel circuit with two resistors in parallel

The circuit shown above is a circuit where two resistors are connected in parallel across the voltage source. Obviously, there are two paths for the flow of current. One part of the current flows through R_1 and the other part flows through R_2. Since total conductance S_t of a circuit is equal to the sum of all the conductances connected in parallel, the formula can be expressed as:

$S_t=S_1+S_2$

Or $S_t=1/R_1+1/R_2$

Or $1/R_t=1/R_1+1/R_2$

The above equation can also be expressed as shown below:

$$\frac{1}{1/R_t}=\frac{1}{1/R_1+1/R_2}$$

$$\text{or, } R_t=\frac{1}{\frac{R_1+R_2}{R_1R_2}}=\frac{R_1R_2}{R_1+R_2}$$

$$\text{in the above circuit, } R_t=\frac{10\times 10}{10+10}=5\,\Omega$$

Calculation in a complex circuit



A complex circuit

The circuit shown above seems to be a complex circuit. By looking at the arrangement of the resistors, their values can be computed in simple steps. As indicated above, calculate as per the steps shown [e.g. step (a), step (b).....]

Step (a): 15Ω & 5Ω resistors are arranged in parallel imparting a value equivalent to 3.75 Ω

Step (b): 3.75Ω+ 20Ω=23.75 Ω (arranged in series)

Step (c): 6.67 Ω (arranged in parallel)

Step (d): 23.75Ω & 6.67Ω are arranged in parallel. The equivalent value is 5.20 Ω

Step (e): 5.20Ω + 10Ω in series, i.e. 15.20Ω

Step (f): 10Ω and 15.20Ω are in parallel, i.e. 6.03Ω and finally, 10Ω + 6.03Ω are in series. The equivalent value is 16.03Ω.

What are insulators?

The materials, which do not allow the flow of electric current through them are called insulators. Glass, porcelain, dry air and dry wood are well known insulators.

Inductors

Physically an inductor is a coil of wire. The coil may be a single turn or part of a turn or it may have thousands of turns. The interior (core) may be air or it may contain iron or iron compounds.

Approximate formula for calculating inductance from physical characteristics:

L (microhenry)= $a^2n^2/(9a+10b)$.

Where:
L is inductance in microhenrys.
a is coil radius in inches.
b is coil length in inches
n is number of turns.

This formula assumes one layer and a core of air. Adding a ferrous core increases the inductance.

Self-Inductance

Self-inductance is the property of a circuit whereby a change in current causes a change in voltage. Self-inductance is also more simply known as inductance. If 'L' is the inductance, then increasing the value of 'L' increases the amount of voltage that is induced in response to a change in current. Decreasing the value of 'L' decreases the amount of voltage that is induced in response to a change in current.

Inductance is measured in units of henries (h). Commonly used engineering units for inductance are- henry (1 h), millihenry (1mh=1 x 10^{-3} h) and microhenry (1 μh=1x 10^{-6} h).

One henry is the amount of inductance that is required for generating one volt of induced voltage when the current is changing at the rate of one ampere per second.

Inductance is the property of a coil when it is subjected to AC voltage. It results from the fluctuation of the current flowing through the circuit. When the current through the coil builds up, an expanding magnetic field also builds up cutting the turns of the coil resulting in the formation of a counter voltage in the coil which opposes the flow of the original current. This property of the coil is known as inductance. Since DC voltage remains constant (except for the instant when the circuit is closed, i.e. the instant when the switch is made on), there is no fluctuation in the magnetic lines of force produced across the turns of the coil and counter voltage is not generated. So a coil offers very negligible resistance (that due to the physical resistance) to the flow of DC current.

Inductive reactance

Inductive reactance is the opposition to AC current flow that is caused by the presence of an inductor in the circuit. The symbol for inductive reactance is X_L. The unit of measure for inductive reactance is ohms (Ω). The amount of inductive reactance in a circuit is proportional to the ***applied frequency** (f)* and the ***value of the inductor***(L).



An inductor in an AC circuit

The equation for calculating the amount of inductive reactance in an ac circuit is given by:

$$X_L = 2\pi f L$$

where,
f is the frequency of AC voltage and L is the inductance

The total inductive reactance of a series X_L circuit is equal to the sum of the individual reactance.

Inductive reactance in series

$$X_{LT} = X_{L1} + X_{L2} + X_{L3} + \ldots X_{Ln}$$



Where X_{LT} is the total inductive reactance and X_{L1}, X_{L2},.... X_{Ln} etc. are the values of individual reactance.

Inductive reactance in parallel

$$X_{LT}=1/(1/X_{L1}+1/X_{L2}+1/X_{L3}+1/X_{Ln})$$



$$L_T = \frac{L_1 L_2}{L_1 + L_2}$$

Inductive reactance is an AC version of resistance. In fact, you can use Ohm's Law by substituting X_L for R:

$$V_L = I_L X_L$$

where:

V_L is the voltage across the inductor in volts
I_L is the current through the inductor in amperes
X_L is the amount of inductive reactance in ohms

The amount of inductive reactance (X_L) changes proportionally with the applied frequency (*f*):



-Increasing the value of *f* causes X_L to increase.
-Decreasing the value of *f* causes X_L to decrease.

The amount of inductive reactance (X_L) changes proportionally with the value of inductance (L):



-Increasing the value of L causes X_L to increase.
-Decreasing the value of L causes X_L to decrease.

Questions:

1. What is the value of inductive reactance for an 0.1 H coil that is operating at 1 kHz?

   Ans: 628 Ω

   Use the basic equation: $X_L=2\pi f L$

3. What value inductor is required for producing an inductive reactance of 10 Ω at 1.8 kHz?

   Ans: 88.5 • H.
   Use this form of the basic equation:

$$L=\frac{X_L}{2\pi f}$$

4. At what frequency will a 150 mH inductor have an inductive reactance of 150 Ω ?

   Ans: 159 Hz

   Use this form of the basic equation:

$$f=\frac{X_L}{2\pi L}$$

4. What is the total inductive reactance of a circuit when $X_{L1} = 150\ \Omega$ and $X_{L2} = 75\ \Omega$ are in series?

   Ans: 225 Ω

Equation to find out inductive reactance in a circuit with a number of inductors in parallel



Use one of these inverse equations to determine the total inductive reactance of a parallel inductor circuit:

$$X_{LT} = \frac{1}{\frac{1}{X_{L1}} + \frac{1}{X_{L2}} + \frac{1}{X_{L3}} + \ldots + \frac{1}{X_{Ln}}}$$

or

$$\frac{1}{X_{LT}} = \frac{1}{X_{L1}} + \frac{1}{X_{L2}} + \frac{1}{X_{L3}} + \ldots + \frac{1}{X_{Ln}}$$

where:

X_{LT} = total inductive reactance
X_{L1}, X_{L2}, X_{L3}, X_{Ln} = values of the individual reactance

The procedure for finding the total inductive reactance of a parallel inductor circuit is identical to finding the total resistance of a parallel resistor circuit.

The total reactance of two inductors in parallel can be found by applying the product-over-sum formula:

$$X_{LT} = \frac{X_{L1}\, X_{L2}}{X_{L1} + X_{L2}}$$

Capacitor

Capacitor is a device used to store electrical energy and then release it as current into the circuit. Its property is just the reverse of an inductor. The capacitance of a capacitor is measured in Farad.

A capacitor has a capacitance of 1 farad if a 1 Volt difference in potential results in the storage of 1 coulomb of charge.

1 coulomb = 6.28×10^{18} electrons

The capacitance is, **C=Q/E,**

Where, C is capacitance in farads,
Q is the charge in coulombs,
E is the voltage in volts.

Practically farad is a large unit. The smaller units are micro farads (μf) and pico farads (pf).

$$1 \text{ Micro Farad } (1\,uf) = \frac{1}{1{,}000{,}000} \text{ farad}$$

$$1 \text{ Pico farad } (pf) = \frac{1}{1{,}000{,}000{,}000{,}000} \text{ farad}$$

When two metallic plates or conductors are separated by an insulator, also known as a dielectric, they behave like a capacitor. The conductors can be long or short piece of metal plate or any other conducting material. The insulator between the two conductors which is known as dielectric can be air, mica, wax-impregnated paper ceramic etc. The properties of a capacitor:

1. It stores energy in the form of electrical field
2. Capacitance is the property of an electric circuit that tends to oppose a change in voltage.
3. It passes A.C. and blocks D.C.



Functioning of a capacitor

A capacitor when connected across a voltage source, an electrostatic field builds up between the metallic plates. The field builds up due to the accumulation of electrons on the negative plate and release of electrons from the positive plate until the capacitor voltage reaches its maximum. The capacitor will be in this charged state as long as it is connected to the voltage source. After removal of the voltage source, the capacitor can not loose its charge (theoretically, a perfect capacitor would hold the charge forever, but in practice, some of the charge leaks out), unless both the plates are connected with the help of a conducting path. When there is a conducting path, electrons from the negatively charged plate flow to the positive plate until both the plates are neutralized.



Capacitor in a DC circuit

Capacitor in a DC circuit

In DC circuits, the capacitor will allow current to flow till it becomes fully charged, however since no current can flow through the dielectric material of the capacitor, no current flows after the capacitor gets fully charged.

Capacitor in an AC circuit

The AC voltage or current is fluctuating in nature. It is not only fluctuating but also changing the direction of flow, i.e. the polarity of the AC voltage source keeps on changing resulting in charging and discharging of the capacitor. Unlike a DC circuit, here, current will continue to flow in the circuit (though the electrons don't cross the dielectric material of the capacitor).

Capacitor in a varying DC circuit

If the voltage source is a varying DC, then also there is continual charging and partial discharging of the capacitor resulting in an AC current flowing through the circuit. In fact, the capacitor blocks the DC, but passes the AC component.

Factors that affect capacitance

1. **Area of plates :** The larger the plates, the higher its capacity to store charges, i.e. **capacitance is directly proportional to the plate areas.**
2. **Space between the plates:** The closer the plates, higher is the capacity to hold charges, because, the electrostatic pull on the electrons collected at the negative side of the voltage source will be more. **Capacitance is inversely proportional to the spacing between plates.**
3. **Type of dielectric used:** Some materials are more dielectric than the others. Vacuum is the basic dielectric with which other materials are compared. It is said to be having a dielectric constant of 1. The dielectric constant of air is slightly more than this (1.0006). Dielectric constant is the ability of a material to permit the establishment of electric lines of force between oppositely charged plates. A dielectric (other than air) makes the positively charged surface of a capacitor repel more free electrons and negatively charged surface accept more electrons than when air is dielectric, thus increasing the capacitance. The dielectric constant of mica ranges from 5 to 9. Dielectric constant of glass is 4.2.**Capacitance is directly proportional to the dielectric constant.**

A formula to determine the capacitance of a two-plate capacitor is:

$$C_{pF} = \frac{0.225\,KA}{S}$$

Where
C= Capacitance in pF
K= dielectric constant
A= area of one of the plates, in inch^2
S= spacing between plates, in inches

The above formula is valid for a two plate capacitor. For a multiplate capacitor, the formula is:

$$C_{pF}=\frac{0.225\,KA(N-1)}{S}$$

Where N=number of plates in the capacitor



2-plate capacitor 3-plate capacitor

It is seen that a 3-plate capacitor has twice the plate area exposed and thus twice the capacitance.

Quantity of charge in a capacitor

The quantity of charge in a capacitor can be found from the formula:

Q=CE

Where,
Q = charge, in coulombs (C)
C = capacitance, in F
E = voltage, in V

If a $0.1\mu F$ capacitor is charged by a 10 V source, the electron difference will be:

$Q=0.0000001 \times 10 = 0.000001$ C or 10^{-6} C

10^{-6} C = $6.25 \times 10^{18} \times 10^{-6} = 6.25 \times 10^{12}$ electrons

If the charged capacitor is disconnected from the voltage source, it will still retain the electron difference on its plates (assuming that there is no leakage). Now, if a similar uncharged capacitor is connected across the charged capacitor, electrons flow from the charged to the uncharged capacitor and it will get charged to 5 V as a result of distribution of half amount of electrons into it. Since the other capacitor lost half of its electrons, its voltage will be reduced to 5 V (now, both the capacitors will be having a voltage of 5 V each) from 10 V. If both the capacitors are reconnected in series, the total voltage-drop across them would become 10 V.

Capacitive Reactance

Capacitive reactance is the resistance offered by a capacitor to the flow of AC through it. It is measured in ohms (μ). The formula to calculate capacitive reactance in a circuit is:

$$X_c = \frac{1}{2\pi f C}$$

Where X_c = reactance, in μ
f = frequency, in Hz
C = capacitance, in F

Questions:

1. Find out the reactance of a 0.002 μF capacitor to a frequency of 2,000 kHz.

Solution:

$$X_c = \frac{1}{2\pi f C} = \frac{1}{6.28\,(2{,}000{,}000)0.000000002} = \frac{1}{0.02512} = 39.81\ \Omega$$

Capacitors in parallel



Two similar capacitors have twice the capacitance of one alone

Capacitors can be connected in parallel to obtain a greater value. The formula is:

Total capacitance of capacitors in parallel, Ct= $C_1+C_2+C_3+\ldots..C_n$

While connecting the capacitors in parallel, it should be noticed that the voltage applied on them does not exceed the voltage rating of the capacitor with the minimum voltage rating.

Capacitors in series



Two capacitors in series

As shown above, when two capacitors are connected in series, the bottom & top plates of the respective capacitors are ignored and consequently combined effect of two capacitors of equal value is to simulate a single capacitor with half the value of a single capacitor, i.e. if two 10 μF capacitors are connected in series as shown above, we will get an effective capacitance of 5 μF. This is because the circuit sees only two plates (plate a & b) with a dielectric distance of twice that of a single capacitor (capacitance decreases when distance between plate increases). It is to be noted that when capacitors of different voltage ratings are connected in series, the voltage that can be applied to them can be equal or less than the total voltage obtained by adding voltages of each capacitor, alternatively, we can say that when capacitors in series are connected across voltage source, the sum of the voltage-drops across each of them will always equal the source voltage.

The formula to calculate the total capacitance of a number of capacitors connected in series is:

$$C_t = \frac{C_1 \times C_2 \times C_3 \times C_n}{\frac{1}{C_1} + \frac{1}{C_2} + \frac{1}{C_3} + \frac{1}{C_n}}$$

Types of capacitors

There are fixed value capacitor as well as variable value capacitors available for electronics work. Paper, mica, ceramic and polyester capacitors have fixed values.

Paper capacitor

Paper capacitors are made by rolling two metal foils with a strip of paper and then impregnating with a dielectric between them. For high voltage applications, several layers of papers are used to separate the metallic foils. They are not suitable for use at frequencies above 1 MHz, which virtually restricts their application to audio frequency (AF) circuits. They are available in capacities from **0.05 μF up to 1 or 2μ F** with working voltages from 200 to 1000 volts.

Mica capacitor

Mica is used as a dielectric between the metallic plates in this type of capacitors. These capacitors have excellent high frequency response.

Ceramic capacitor

In this type of capacitor, ceramic is used as a dielectric which has a high dielectric constant. Ceramic capacitors have good stability with regards to temperature and voltage changes. They are widely used in miniaturized audio frequency (AF) and radio frequency (RF) circuits. Their capacities ranges from **1pF** to **1 μ F** with high working voltage.



A disc ceramic capacitor



A tubular ceramic capacitor

Polyester film capacitor

In this type of capacitors polyester is used as a dielectric to impart a high breakdown voltage. Their capacities ranges from **0.01 μ F up to 2.2 μ F**. Their low inherent inductance makes them suitable for coupling and decoupling applications.

Polystyrene capacitor

These capacitors are made from metallic foil interleaved with polystyrene film, usually with fused polystyrene enclosure to provide high insulation resistance. They provide good stability and reliability at high radio frequencies because of their low inherent inductance and low series resistance. Their values range from from **10 pF** to **100,000 pF**, but working voltage generally falls substantially with increasing capacity (as low as 60 volts for a 100,000 pF polystyrene capacitor).

Electrolytic capacitor

An electrolytic capacitor consists of an aluminum-foil positive plate immersed in a solution called an electrolyte (ionizable solution capable of carrying current). The aluminum foil is the positive plate, and the electrolyte is the negative plate, if a liquid can be called a plate. To make an electrical connection to the liquid, another aluminum foil is placed in the solution. To prevent the two foils from touching each other, a piece of gauze is placed between them. The +ve foil is surrounded by a thin oxidized film formed due to application of a particular voltage which acts as the dielectric. Electrolytic capacitors can not be used in AC circuits. Their values range from **1 μ F to 4700 μ F** or more with working voltage ranging from 10 volts dc up to 500 volts.



← Symbol for an electrolytic capacitor

Variable capacitors

Variable capacitors are widely used in radio frequency work where it is required to change the value of the capacitor in order to tune the circuit to a particular frequency. Usually, air is used as a dielectric in this type of capacitor. The capacitance is made to vary either by changing the distance between the plates or by changing the plate area exposed. This type of capacitor may consist of two plate or more than two plates. Metallic gang capacitors and button trimmers are the most common example of variable capacitors. In a trimmer the two metallic plates are made to vary in their distance with the use of a screw.



A trimmer



Symbol for variable capacitor

Electrical Impedance

Electrical impedance is the total opposition to current flow in an AC circuit. It takes into account all sources of opposition. Since it is the total opposition, impedance is measured in ohms, just as resistance and reactances are. If an inductor and resistance are connected in series with a source of A.C., the impedance of the circuit is:

$$Z = \sqrt{X_L^2 + R^2}$$

If $X_L=4\Omega$ and $R=3\ \Omega$

Therefore,

$$Z = \sqrt{16+9}$$

$=5\ \Omega$



AC source

The impedance of a series R-L circuit can never be equal to or greater than the sum of X_L and R, nor can it be equal to or less than either X_L or R.

Inductance and Capacitance in Series

When an inductor and a capacitor are connected end to end, a series L-C circuit is formed. If the inductor is a pure inductor and capacitor, a pure capacitor, then the circuit has no D.C. resistance which is practically impossible. There is always some resistance present in the circuit. Inductor has inductive reactance, X_L and capacitor has the capacitive reactance, X_C. The net resistance present in the circuit is negligible.

If the circuit has an inductance L of 1 henry in series with a capacitor C of 10 μF and the applied voltage E is 100 volts and frequency is 50 Hertz.

Then,

Inductive reactance $X_L=2\pi fL= 6.28 \times 50 \times 1 = 314\ \Omega$

Capacitive reactance,

$$X_c = \frac{1}{2\pi f C} = \frac{1}{6.28 \times 50 \times 0.00001} = \frac{1}{0.00314} = 318.5\Omega$$

The impedance of such circuit is the difference of inductive reactance and capacitive reactance.

$Z=X_C-X_L=318.5-314 = 4.5\ \Omega$

If X_L is greater than X_C then the impedance is $X_L - X_C$.

Resonant frequency

Resonant circuits make it possible to select one frequency from all others. For example, there are hundreds of radio stations that broadcast signals strong enough to be received by your radio receiver. The tuning circuit of the radio receiver accomplishes the task of discarding all other signals but to allow only the desired signal to be processed. **The single frequency at which the circuit responds best is called the resonant frequency of the circuit.** Resonance occurs when the inductive reactance becomes equal to capacitive reactance or $X_L = X_C$.

It can be achieved by either varying capacitance or inductance. In a radio receiver, it is achieved by varying the value of the variable capacitor. A series resonant circuit offers very little resistance when the circuit operates at the resonant frequency. High current is permitted to flow through the circuit.

Parallel Resonant Circuit

In the circuit diagram shown below, the part of the circuit between the points 'a' and 'b' is called a 'tank' because the resonant frequency will be captured and held there while all other frequencies are allowed to flow through it. So if the AC source is producing AC current at the resonant frequency, that current is blocked by the tank. The current is not permitted to travel from 'a' to 'b' through the tank. But when the AC source is producing current at any other frequency, the current can flow from 'a' to 'b' with little opposition.


a
Radio frequency source
Symbol for inductor on a ferromagnetic core
The plate of the capacitor which is connected towards the negative terminal of the electronic circuit is often denoted by a curved line
b
Symbol for 'Ground connection' or negative terminal

A parallel resonant tank circuit

Tuning Circuit

In a radio receiver, the selection of the desired frequency out of hundreds of other frequencies is achieved by the use of resonant circuit. The resonant circuit basically consists of an inductor and a capacitor. The frequency of resonance is usually achieved by changing the capacitance of the variable capacitor.


Antenna
To other circuits
L_1
(Inductor)
L_2
Variable capacitor
Ground

A radio tuning circuit

In the tuning circuit shown above, all the frequencies captured by the antenna are passed to ground through the primary coil L_1. They will try to cause current flow in the tank circuit, but only the resonant frequency will be successful in creating a current flow. The information it carries will be sent to the other radio circuits while the non-resonant frequencies are practically ignored.

In the circuit shown above, the condition of series resonance is present but is not apparent. In this circuit the transformer secondary coil has a capacitor across it with a reactance of the secondary, forming a resonant circuit. At first glance it appears to be a parallel-resonant circuit. The primary coil, however, is inducing an AC voltage into each turn of the secondary coil. Theoretically, the secondary may be considered to have a source of AC inserted in series with its turns.

Filtering

Resonant circuits are used to filter out the desired frequency. A series resonant circuit allows to pass its resonant frequency while the parallel resonant circuit (called the tank circuit) blocks the flow of its resonant frequency


Passes higher frequencies but stops lower ones
Input
C_2
Output
C_1
High Frequencies only
Series resonant circuit filters out the resonant frequency to ground
L_1
Ground

High pass filter



Tank circuit traps the resonant frequency

Higher frequencies are bypassed by the capacitor to ground while due to high capacitive reactance, low frequencies easily finds their way into the the output

Low pass filter

'Q' of a circuit

The term 'Q' is applied to AC circuits in which inductance and capacitance are involved. It in fact express the 'quality' of the inductor or capacitor and since lesser the ohmic resistance of the coil (inductor), more perfect inductor the coil is, with little loss. 'Q' can be found from the formula:

$Q = X_i / R$ (in case of coil); where X_i = inductive reactance, R = Ohmic resistance.

Again,

$X_i = 2\pi f L$

Where,
f = frequency,
L = inductance

Therefore, $Q = 2\pi f L / R$; this shows that the same coil or inductor possesses high 'Q' at higher frequency.

Skin effect

A phenomenon called 'Skin effect' also causes loss of efficiency of a coil or inductor. It is observed that at higher frequencies, electrons flow nearer to the surface of the conducting wire; since the usable cross-sectional area lessens, the ohmic resistance increases resulting in a lower 'Q'.

Prevention of 'Skin effect'

(i) By using large diameter wire.
(ii) By silver-plating of the wire used.
(iii) Using fewer turns while making the coil, but increasing the core permeability; e.g. using powdered iron core.
(iv) By using 'Litzendraht wire', an insulated multistrand wire. Several thin strands have more surface for a given wire diameter than does a solid wire (Litz wire is effective only up to about 1 MHz)

B. Thermionic Emission & Valves

An electric current can also flow in a gas. A voltage applied across a gas-filled tube causes ionization of the gas: free electrons stream towards the plate with the positive potential, colliding with the atoms in their way and detaching electrons from their orbits. The positive ions move toward the opposite end of the tube.

The most common material used in the construction of a vacuum tube envelope is glass. The electrode leads pass through a glass bead sealed into an eyelet. The electrodes in a vacuum tube are supported by insulators such as mica and a variety of ceramics. The electrodes themselves are commonly made from metals such as nickel, copper, aluminum, molybdenum, and tungsten.

In thermionic valves the electrons move in a vacuum. An example of such a device is the diode. The envelope of a diode houses two main parts which are also called the anode (or plate) and the cathode. Near the cathode there is a filament or miniature electric heater which heats the cathode. Most tubes employ heater-cathodes. A heater-cathode consists of a metal cylinder coated with special oxides that liberate great quantities of electrons when heated to a relatively low temperature. In this case an "electron liquid", consisting of electrons that move chaotically in the very body of the cathode, between its atoms, begin to "boil". This phenomenon is known as 'electronic emission'. As a result of this emission, a cloud of "electron gas" is formed round the cathode. If the cathode is now connected to the negative terminal of a voltage source and the anode, to the positive terminal, the anode will begin attracting electrons from the cloud, "drawing" them away from the cathode, and a current will flow inside the diode. Freedom for the electron proves very short-lived: no sooner does it escape from the cathode it is immediately attracted by the anode.

A diode is in fact a one-way valve. When the negative terminal of the voltage source is connected to the anode and the positive terminal to the cathode, the electrons will not be able to escape the cathode, because it attracts them. But even those that do escape have nowhere to fly in particular: previously they were attracted by the anode, now it forces them back to the cathode. With such a connection no current flows through the diode. This property of the diode is employed for converting the alternating current to direct current which is called rectification. The current flowing through a diode is called the plate current. The flow of plate current can be controlled by two ways: by varying cathode temperature; and by changing the applied voltage (called the plate voltage). But cathodes are designed to operate most efficiently at one particular temperature. An increase in plate voltage results in an increase in plate current. But after a certain point, further increase in plate voltage will not cause any corresponding increase in the plate current. This point is called the saturation point.

Diode valve as a rectifier

As shown in the circuit given below, the source of plate voltage in the plate circuit is a transformer providing an alternating voltage to the plate. During one half cycle, the plate end of the transformer-secondary winding may be positive and the cathode end negative. On the next half cycle the plate end will be negative and the cathode end positive. As described above, the diode allows only one half cycle of the emf to produce current in the circuit. With ac plate voltage the plate current is pulsating dc. This one-way-gate effect is a main use of diodes. A diode is also called a rectifier.



A diode valve as a rectifier

Triode Valve

The introduction of a third electrode (control grid) between the cathode and the anode of a diode makes it a triode. In the triode, current is controlled by means of a voltage applied between the cathode and the grid. With a high negative grid potential (with respect to the cathode), the grid becomes a barrier for the electrons. They will "crowd" in the space between the cathode and the grid; the valve will be cut off, since no current will flow from the cathode to the anode. With a positive grid potential, the grid will help the anode, since its positive potential will be added to that of the anode. A heavy current will flow through the valve. However, with too high a positive grid potential the grid may turn from a helper of the anode into its competitor: some electrons will be drawn to it and will not reach the anode. In this case a harmful grid current appears in the valve. That is why in normal operation the grid is made to vary only more or less negatively.

Amplification factor of a triode valve

In the circuit shown below, the voltage (-Eg) in the grid circuit is –8 V. Plate voltage (+Ep) is 200 V. Plate current is 3mA. By increasing +Ep by 40 V it is found that plate current increases from 3 to 7 mA. Returning to the original values, Grid voltage (-Eg) is –8 V, +Ep=200 V, and Ip=3mA, it is found that if the –Eg value is reduced by 2 V, from –8 to –6 V, the Ip will again rise from 3 to 7 mA. This indicates that the same Ip change can be produced either by changing the Ep by 40 V or by changing the –Eg by 2 V. This controlling ratio of 40:2 is equal to 20. The tube is said to have a μ (mu) or amplification factor of 20. Thus the grid is found to be 20 times more effective in changing plate current than the plate voltage.


Anode or plate
+E$_P$
Grid
- 8 Volt (-E$_G$)
3 milliampere
A
Cathode
Filament
−
+
200 Volt

A triode amplifier circuit

Triode as an amplifier

In a theoretical circuit comprising a microphone, a transformer, a triode valve with a load resistance, the microphone induces a small ac voltage into the secondary of the transformer and between grid and cathode. With no signal applied to the grid and with 100 V from the plate supply, the dc voltage-drop across the load resistor Rl might be 75 V. As the input signal reaches a peak of 1V negative, the current in the plate circuit will decrease. The voltage drop across the plate-load resistor might decrease by 12 V, to 63 V across the Rl. As the grid voltage swings to 1 V positive, the plate current will increase, until there is a voltage drop of perhaps 87 V across the load resistor. As grid voltage varies from −1 V to +1 V (a 2 V peak to peak variation), the voltage across the load resistor varies between 87 and 63, i.e. 24 V. The voltage ratio of 2:24 indicates that across the plate load resistor, the voltage variation is 12 times more than the variation between the grid and the cathode.


Electron flow from plate ⟶
Microphone produces an AC voltage
1 Volt peak AC (0.707 rms)
24 Volt variatior across load (8.48 V rms)
R$_L$
−
+
100 Volt

A simple audio amplifier circuit using triode valve

Bias voltage

In the circuit described above, the grid was driven negative and positive alternately. But this creates distortion. To avoid the distortion, in a practical circuit, the grid may never be allowed to become positive and thus there is no grid current (Ig) from the cathode. This is accomplished by adding a dc voltage source in series with the grid-cathode circuit. The negative potential is applied to the grid through the transformer, and the positive potential to the cathode. The negative dc voltage added in series with the grid circuit is known as the bias voltage. If a negative 10 V bias is enough to produce plate-current cutoff with a given plate voltage, then a possible bias voltage would be half of this, i.e. 5 V for a class A amplifier. It can accommodate a peak ac emf of 5 V from the secondary of the grid-circuit transformer and neither cutoff the plate current nor drive the grid into positive region.

C. Semiconductors: Diodes & Transistors

In the early days of electricity there were only two groups of material: insulators and conductors. Insulators are materials which do not allow the flow of electric current through them. Glass, porcelain, dry air and dry wood are well-known insulators. Metals are known to be good conductors, with copper and silver among the best. The conductivity of a particular material depends on the number of free electrons present in it.

There is another group of material known as semiconductors. Semiconductors like germanium and silicon are bad conductors of electricity in their purest form. But when certain impurities (iridium or arsenic, which have a slightly different atomic structure from that of germanium or silicon) are added in the form of carefully controlled quantities, either an increase of free electrons or deficiency of electrons results. A semiconductor is called an **n-type semiconductor** where conduction takes place by reason of excess free electrons. A semiconductor is called a **p-type semiconductor** where conduction takes place due to freely moving 'holes' (positively charged) which replace electrons displaced by random electron movement in the material.



P-N junction diode with 'Forward Bias'

When pieces of p-type and n-type semiconductors are joined together, a p-n junction results. Flow of electric current through such a junction is possible only when the positive pole of the battery (voltage source) is connected to the p-type semiconductor and the negative pole to the n-type semiconductor. This is called the **"forward biased"** condition.



A forward biased semiconductor diode

In this condition, positively charged holes are repelled by the battery voltage towards the junction between p and n type material. Simultaneously, the electrons in the n-type material are repelled by the negative battery voltage toward the p-n junction. Despite the presence of a potential barrier at the p-n junction, which prevents electrons and holes from moving across and combining, under the influence of the electric field of the battery the holes move to the right across the junction and the electrons move to the left. As a result, electrons and holes combine and for each combination of that takes place near the junction, a covalent bond near the positive battery terminal breaks down, an electron is liberated and enters the positive terminal. This action creates a new hole which moves to the right toward the p-n junction. At the opposite end, in the N-region near the negative terminal, more electrons arrive from the negative battery terminal and enter the n-region to replace the electrons lost by combination with holes near the junction. These electrons move toward the junction at the left, where they again combine with new holes arriving there. As a consequence, a relatively large current flows through the junction. The current through the external connecting wires and battery is due to that of the flow of electrons. If, however, the polarity of the battery is reversed, i.e., the positive terminal is connected to n-type semiconductor and the negative terminal of the battery to the p-type semiconductor, the p-n junction will block the electron flow by building up a voltage barrier at the junction. The holes are now attracted to the negative battery terminal and move away from the junction because of the attraction of the positive terminal. Since there are effectively no hole and electron carriers in the vicinity of the junction, **current flow stops almost completely**. The diode is now in reverse biased condition. This type of device is called a "**solid state diode**" or a semiconductor diode.

Use of Semiconductor diode

By exploiting their property of one way flow of electric current, they can be utilized to convert alternating current to direct current (known as rectification). Without adequate filtering, the resultant d.c. is pulsating in nature. However, it will be appreciated that a diode will work in both a dc and an ac circuit. An example of the use of a diode in a dc circuit (say output side of a dc power supply) to eliminate any possibility of reverse polarity voltage surges occurring which could damage transistors in the same circuit.



A basic half-wave rectifier circuit

The circuit shown above is a basic half-wave rectifier circuit passing one half of each AC cycle as DC and suppressing the other half cycle. The purpose of the capacitor is to maintain the DC voltage output as far as possible by discharging on each 'suppressed' half cycle. The DC output in this type of circuit is not smooth having a 'ripple' at the AC frequency.



A centre tapped step-down transformer

A basic full-wave rectifier circuit

The circuit shown above is that of a simple full wave rectifier whose secondary voltage is halved (because of the center tapping), but the current that can be drawn is doubled. During the first half cycle S_1 is positive and S_2 is negative with respect to G. Current flows through the diode D_1 and not through D_2. During the second half cycle, S_1 is negative and S_2 is positive with respect to G. Current flows through the diode D_2 and not through D_1. Thus, during both the half cycles, 'A' remains positive and 'B' remains negative. The process is repeated and across the load a full wave rectified DC is obtained. The capacitor charges and discharges alternately to produce a smoother DC supply. The 'ripple' will still be there which will be equal to twice the AC frequency.

The usual form of full-wave rectifier circuit is the bridge rectifier shown below. This gives approximately the same no-load voltage as a half-wave rectifier with the advantage of full-wave rectification and better smoothing. A single high value electrolytic capacitor is used for smoothing.



A practical full wave power supply

Transistors

The simplest of the transistors are of two types-either **p-n-p** or **n-p-n**. Two p-n junction diodes can be sandwiched back to back to form a p-n-p or n-p-n junction transistor. But in a practical transistor, the center or n-type portion of the sandwich is extremely thin in comparison to the p-regions. In the 1st illustration, **both the p-n junctions are reverse biased.**



Non-conducting P-N-P junction

In this type of connection, holes in the each of p-region are attracted towards the negative battery terminal and the mobile electrons in the n-region are initially moved away from both junctions in the direction of the positive battery terminal. Due to the displacement of holes and electrons, **there will be no current flow in the external circuit.**

In the **2nd illustration,** one of the **p-n junctions is forward biased,** while the **other is reversed biased.** In a transistor, the middle layer (here n-region) is called the **base,** the forward biased p-n junction is called the **emitter** junction and the reverse biased p-n junction is called **collector** junction. Due to the positive potential at the emitter junction, the holes in the p-region cross into the n-region (the base). But this region is very thin and there are very few electrons with which holes can combine. So, majority of the holes drift across the base into the collector junction. About 5 per cent of them are lost in the base region as they combine with electrons. For each hole that is lost by combination with an electron in the base and collector areas, a covalent bond near the emitter electrode breaks down and a liberated electron leaves the emitter electrode and enters the positive battery terminal. The new hole that is formed then moves immediately toward the emitter junction, and the process is repeated. Thus, a continuous supply of holes are injected into the emitter junction, which flow across the base region and collector junction, where they are gathered up by the negative collector voltage. The flow of current within the p-n-p transistor thus takes place by hole conduction from emitter to collector, while conduction in the external circuit is due to the flow of electrons.



Basic connection of P-N-P Junction transistor

Because of the reverse bias no current can flow in the collector circuit, unless current is introduced into the emitter. Since a small emitter voltage of about 0.1 to 0.5 volt permits the flow of an appreciable emitter current, the input power to the emitter circuit is quite small. As we have seen, the collector current due to the diffusion of holes is almost as large as the emitter current. Moreover, the collector voltage can be as high as 45 volts, thus permitting relatively large output powers. **A large amount of power in the collector circuit may be controlled by a small amount of power in the emitter circuit.** The power gain in a transistor (power out/power in) thus may be quite high, reaching values in the order of 1000.

Current gain of transistor (α)

The ratio of **collector current** to **emitter current** is known as **alpha** (α), i.e.

$$\alpha = \frac{I_C}{I_E} = \frac{\text{Collector current}}{\text{Emitter current}}$$

It cannot be higher than 1. It is the measure of possible current amplification in a transistor.

Beta (β) is another constant defined as ratio of collector current to base current. If I_E is the emitter current, and $I_C/I_E = \alpha$, then I_B=base current= $1-\alpha$, i.e.,

$$\beta = \frac{I_c}{1-\alpha}$$

Transistor Symbols and Connection

When transistors are operated as amplifier, **three different basic circuit connections** are possible: (a) Common-base, emitter input; (b) common-emitter, base input; and (c) common-collector, base-input.

Regardless of the circuit connection **the emitter is always forward biased** and **collector is always reverse biased.**



Circuit symbol of NPN transistor



Circuit symbol of PNP transistor

Described below is a **'common emitter, base-input'** basic transistor amplifier circuit using a PNP transistor. The transistor is in **common-emitter configuration.** It needs two separate supply voltages--**one for base bias** and the **other for the collector.** In the first diagram, two separate batteries are used. But the voltages can also be provided by a single supply (**as shown in the second diagram**) taken to the common connection (the emitter) and the collector; and tapping the collector side to apply the necessary forward bias voltage to the base dropped a bias resistor.



A common emitter amplifier circuit using a PNP transistor with two power supplies



A common emitter amplifier circuit using a PNP transistor with a single power supply

In this type of amplifier circuit, the collector current is fed through an output load (R_2). The biasing voltage to the base is provided through the resistor R_1 is of the order of 0.1 to 0.2 volts for germanium transistors; and about 0.6 to 0.7 volts for silicon transistors. This type of biasing is called as *current biasing*. A relatively small *base* current can instigate a very much larger *collector* current (or, more correctly, a **small input power** is capable of producing a much **larger output power**). In other words, the transistor works as an amplifier. However, this type of circuit is not very stable. To provide stability, another type of base biasing is used, which is called voltage biasing. In the amplifier circuit shown below, with voltage bias, two resistors (R_1&R_2) are used as a potential divider. A resistor R_3 is also added in the emitter line to provide emitter feedback automatically to control the bias voltage under varying working conditions. This resistor is usually paralleled with a capacitor to provide further stabilization.



Voltage bias transistor amplifier circuit

D. Radio Receiver

A radio receiver is a device, which is used to receive **radio frequency transmission from a radio transmitter**. A radio transmitter transmits ***radio frequency*** (RF) signal generated at a particular frequency , on which the intelligence (e.g. any type of audio) is superimposed. Transmission of this audio information or ***audio frequency*** (AF) is possible only through the use of radio frequency. However, in reality the audio frequency (AF) does not get transmitted; instead, the sound content is literally carried on the back of the RF signal, the two together forming what is called a ***modulated signal***.

Modulated radio frequency can be produced in two different ways--**amplitude** or 'up-and-down' modulation, known as AM; and **frequency modulation** (FM). In FM broadcast, actually a very small variation in the RF signal frequency takes place about the station frequency. FM technique is usually followed in very high frequency (VHF) transmissions.

Amplitude modulation technique is easier and hence widely used for medium wave and short wave broadcasts. There are hundreds and thousands of broadcasts that take place in different radio frequencies or wavelengths. The relationship between wavelength and frequency is:

$$\text{Wavelength (metres)} = \frac{300000000 \text{ metres}}{\text{Frequency (in Hertz, Hz)}}$$

$$\text{Or, Frequency (in Mega Hertz, MHz)} = \frac{300}{\text{Wavelength (in metres)}}$$

Radio frequency (RF) generation

A basic oscillator which can produce oscillations at a particular frequency consists of a capacitor, a coil (inductor) and a DC voltage source along with a switch as shown below.


This 'Push-to-on' switch is instantly made ON and OFF
electron flow
DC voltage source
Instant application of a current pulse builds an expanding magnetic field around the coil

A basic Inductive-Capacitive (LC) oscillator circuit to produce damped oscillation

By making the switch 'ON' instantly and then releasing it to make 'OFF', a pulse of current finds it path to the capacitor as well through the inductor resulting in an expanding magnetic filed across the inductor while charging the capacitor simultaneously. The instant when the switch is made 'OFF', the capacitor discharges releasing the extra electrons on the top plate through the inductor to reach the other plate. The current thus produced is in the same direction as when the switch was made 'ON'. Thus it aids to maintain the expanding magnetic field produced during the instant when the switch was made 'ON'. The capacitor will reach a neutral state after the electron from the top plate neutralizes the bottom plate (the positively charged plate), i.e. the capacitor will be getting discharged in the process. As there is no supply of electrons from the DC voltage source (because the 'switch' is 'OFF'), and the capacitor is also fully discharged, so, the magnetic field around the inductor will now collapse resulting in a self-induced voltage. This self-induced voltage will make enough current to flow through the inductor to charge the capacitor in opposite direction. A similar process described above will now start and repeat over and over again producing damped oscillating currents until all of the energy is wasted by circuit resistance and other losses. This is called the **'flywheel effect'**. It is similar to what happens when a pendulum is started in motion. It tries to continue swinging at the same frequency until all of the starting energy is used up. The unique thing to notice here is that oscillations will maintain a particular frequency despite loosing their amplitude. This frequency is called the resonant frequency and the circuit described above is called a tank circuit. The frequency of resonance can be found from the formula:

$$f_r = \frac{1}{2\pi\sqrt{L\,C}}$$

In the electronic circuitry, a damped oscillation is not at all desirable from the practical utility point of view. So, the objective is to use a transistor or triode valve to provide the necessary gain (and not loss!) and feedback (the energy) to sustain the oscillations or to produce perfect sine wave frequency. Described below are two practical oscillator.

Hartley Oscillator



A Hartley oscillator circuit

In the Hartley oscillator circuit shown above, the frequency of oscillation is determined by the resonant frequency of the tank circuit consisting of C_1 and L_1. L_1 is tapped at its center to form two inductors : L_{1a} and L_{1b}. L_{1a} is effective in the base circuit of the PNP transistor and L_{1b} is in the collector circuit of the transistor. When B+ is applied to the collector through a RF choke, collector current begins to flow.

The resulting drop in collector voltage is coupled through C_3 and developed across L_{1b}. This serves as the initial excitation for the tank and causes circulating current to begin to flow in the tank. The circulating current produces a voltage across L_{1a}, which is coupled by capacitor C_2 to the base of the transistor. The amplified signal at the collector is coupled back to the tank circuit by capacitor C_3, and developed across L_{1b}. The feedback voltage developed across L_{1b} is in phase with the input voltage across L_{1a}, and so maintains the tank circuit oscillations.

Colpitts oscillator



A Colpitts oscillator circuit

The Colpitts oscillator is similar to the Hartley oscillator, **except that two capacitors are used in the tank circuit instead of a tapped coil.**The output frequency of a Colpitts oscillator is determined by the value of the tank inductance and the total capacitance of the two series capacitors. Capacitor C_1 is in the base circuit and C_2 is in the collector circuit. The AC tank voltage produced by the circulating current divides between the two capacitors. The voltage across C_1 is applied to the base of the transistor by coupling capacitor C_3 and base resistor R_1. The resulting collector signal is coupled back to the tank circuit by capacitor C_4 and developed across tank capacitor C_2. The feedback is in phase with the base voltage as a result of the 180-degrees phase shift introduced by the transistor, and the 180-degree shift caused by the ground tap between C_1 and C_2.

Tuning circuit of radio receiver

The job of a radio receiver is to receive only a particular radio frequency at a single time. For this, a sorting device known as the '***tuning circuit***' (see page 74) is used at the '***front end***' of a radio receiver.

Detection

After sorting out the desired frequency, a diode is used at the '**detector**' or '**demodulator**' stage of the receiver, where it rectifies out one half of the RF signal containing the audio information. This half cycle of the RF is still imposed with the

AF content. So the next step is to filter out the RF to receive or detect an undulating AF signal. These undulations follow exactly the same variations as the AF signal originally imposed on the transmitter RF signal at the transmitting station by a microphone.

A resistor and a capacitor acts as a filter for a specified frequency. So, a diode detector is to match a load (resistor) with the capacitor so as to form the required filter circuit, so that only the varying dc (undulating AF portion of the signal) is passed at the output from the detector stage. A basic diode detector circuit is shown here.


+
Diode
RF+AF signal
Coupling capacitor to eliminate 'noise' from volume control
Audio out
Capacitor to filter out residual IF (read description of a super-heterodyne receiver)
Variable resistor (volume control)
–

A diode detector circuit

AF Amplification

The audio signal thus obtained is then amplified in the audio amplifier stage of the receiver. There may be more than one stages of amplification but with the limitation of using only a certain number of stages of amplification after which distortion in the audio takes place.

The radio receiver described above is a very simple radio receiver which has a limitation in its detector stage. This type of receiver is called **Tuned Radio Frequency** receiver (TRF). The detector works most effectively with an RF input voltage of 1 volt or more. Signal obtained directly from an aerial circuit are most of the time more than a few millivolts in strength, and weaker the signal the less effectively they will be detected. So, the range of stations that can be picked up is limited, and no amount of amplification after detection can make up for this limitation.

This limitation or lack of sensitivity can be overcome by amplifying the incoming signal before detection, so that the detector is always working with good signal strength. This is accomplished by the use of an amplifier stage right at the beginning of the circuit or by **super-heterodyne circuitry**. By **comparing and contrasting a 'Tuned Radio Frequency (TRF) receiver'** with a **'Super-heterodyne receiver'**, we can better understand the advantages as well as functioning of a super-heterodyne receiver.

Difference between a Tuned Radio Frequency (TRF) receiver and a Super-heterodyne receiver.

A **TRF receiver** consists of the following stages:

(i) Antenna input stage
(ii) A few stages for RF-amplification
(iii) A detector stage for demodulation
(iv) One or more stages of AF amplifier



Block diagram of a simple Tuned Radio Frequency (TRF) Receiver

On the contrary, a **super-heterodyne receiver** consists of:

(i) RF Amplifier
(ii) Mixer or Converter
(iii) Local Oscillator
(iv) IF Amplifier
(v) Detector
(vi) Automatic Gain Control (AGC) Circuit.
(vii) AF Amplifiers

1. In a TRF receiver a series of loosely coupled tuned circuits are used to increase selectivity and each circuit are ganged (interconnected) so that they resonate at the same frequency. But in a super-heterodyne receiver, this principle is not followed, instead, the RF amplifier, mixer and local oscillator are ganged to produce an intermediate frequency (IF).
2. In a TRF receiver the high amplitude original frequency is demodulated at the detector stage. But in Super-heterodyne sets, the IF is demodulated.
3. In a TRF Receiver, no image frequency is produced. But image frequency is produced in super-heterodyne receiver.
4. In a TRF receiver, selectivity is not constant; the receiver is more selective at the low frequency bands, while less selective at the high frequency end. Because the detector and amplifiers of a super-heterodyne receiver can be designed to amplify only intermediate frequency (IF), this type of receiver is more selective and offer high fidelity (exact reproduction quality of the transmitted signal).
5. In TRF receiver, amplification is not constant over the tuning range. In super-heterodyne receiver amplification is constant since all the time it amplifies a constant frequency at the IF stages.

Functioning of a Super-heterodyne Receiver

The main objective of the super-heterodyne receiver is to produce an intermediate frequency (IF) by the process of heterodyning or beating. This can be accomplished when two frequencies are mixed to produce the beat frequency. In super-heterodyne receivers, the IF is usually **455 kHz which is selected because the broadcast band begins above that frequency**. So, if we imagine a situation when the RF amplifier is tuned to receive a 800 kHz broadcast signal, the local oscillator must be tuned to 1255 kHz, which will result in an IF of 455 kHz (1255-800 kHz=455 kHz).

Since we have to tune the RF amplifier section throughout the entire broadcast band, the frequency of the local oscillator must also vary in a manner that it always maintains a gap of 455 kHz. To achieve this condition, the Local Oscillator and RF Amplifier section are **'ganged'**, i.e. their tuning condensers are connected/ganged mechanically in such a way that when we tune the variable capacitor in the RF section, the variable capacitor in the local oscillator also changes its value, it 'tracks' the frequency to which the 'Aerial Circuit' is tuned and remain separated from the tuned frequency by 455 kHz up.

The Intermediate Frequency (IF), which is a considerably low frequency is being used, because-

(i) it is a suitable frequency to achieve amplifying efficiency.

(ii) It provides better selectivity.

(iii) It provides better sensitivity throughout the broadcast band.

(iv) It provides uniform sensitivity as well as uniform selectivity.



Block diagram of a Superheterodyne Receiver

Radio Frequency (RF) Amplifier section

This section performs two major tasks:

(i) it couples the antenna voltage to the converter of the receiver;

(ii) By selectivity, it accepts only the desired frequency and all others are rejected.

(iii) By amplifying the desired signal, the Signal-to-Noise ratio is increased in the converter stage for efficient operation.

Converter or Mixer Section

The main objective of the super-heterodyne receiver is to produce a constant Intermediate Frequency (most commonly used frequency being 455 kHz in commercial broadcast band radio sets). In the mixer stage, the local oscillator frequency and the selected station frequency is or combined, where, by the process of 'heterodyning', i.e. 'beating', the 'Intermediate Frequency (IF)' is obtained. If the RF Amplifier section selects and amplify a signal of 800 kHz, then the local oscillator produces a frequency of 1255 kHz. By mixing both the frequency at the mixer stage, a difference of frequency of the value 455 kHz is obtained (1255-800=455 kHz).

Intermediate Frequency (IF) Amplifier

The 455 kHz IF is fed to the IF amplifier through an IF transformer. The circuitry of the IF section is so designed and tuned so that it gives the optimum gain at that particular IF frequency.

Detector/Demodulator and 1st Audio Frequency Amplifier stage

The Amplitude Modulated (AM) IF is demodulated and detected. A diode working as rectifier solves this purpose (see page 89). The triode/transistor amplifies the audio signal and the volume control potentiometer system controls the intensity of sound.

AF Power Amplifier

This section further amplifies the audio signals which is finally fed to an output transformer which matches the impedance of output stage with the speaker (in modern transistor receivers, the necessity of output transformer is eliminated).

AGC or AVC in a super-heterodyne radio set

Automatic Gain Control is a most needed part of super-heterodyne circuitry. A disadvantage of manual gain control (volume control) with a receiver is that it can't provide constant output under all conditions. If a receiver is tuned from a weak signal to strong signal, its output must increase intolerably. This would then require readjustment of the volume control. Similarly, when a receiver is tuned to particular signal the output level can vary widely if the input signal strength fluctuates as a result of fading and adjustments of the volume control has to be done. Since such signal fluctuations are rapid, constant readjustment of volume control would be necessary which is impractical. This is where AGC or AVC comes into picture and is used in addition to the manual control.

All AGC or AVC (Automatic Volume Control) circuits perform two basic functions;

(i) The first of these is to develop a DC (Direct Current) which is proportional to the receiver input signal all the time.

(ii) The AGC voltage is applied to the RF and IF stage of the receiver where it serves as a Bias voltage.

In this way the AGC voltage controls the gain of RF and IF stages, and therefore the overall gain of the receiver. When the signal level at the receiver input increases, the AGC voltage increases proportionately. Consequently, a larger bias is applied to the IF and RF stages and their gain is applied to the IF and RF stages and their gain is reduced.

The receiver output thus remains relatively constant instead of increasing in accordance with the input signal strength and vice-versa.

In valve type RX (receiver), the grids of RF and IF portions valves are biases by negative voltage. While in a transistor it depends on transistor type.



An Automatic Volume Control (AVC) circuit

Squelch circuit

The squelch circuit or Q (**Quieting**) circuit is a circuit which is controlled by AGC or AVC voltage. The modern high gain receivers shows a disadvantage without it, that is, without a squelch circuit, annoying buzzing and cracking sounds are heard over the loudspeaker in absence of input signal. So a circuitry is arranged in such a way that AF gain is kept reduced in absence of input signal from the antenna.

With no signal there is no Negative AGC voltage, and the squelch tube allows current to flow through it then passing through R3 to the +250 V point. Thus R3 produces a DC voltage drop across it which is more negative at midpoint than at the bottom being in series with the amplifier grid circuit, tube past cutoff, preventing it from functioning.

When a signal is received, AGC or AVC voltage biases the squelch tube to 'cutoff', stopping plate current flow. Consequently, the voltage drop across R3 ceases, allowing the AF amplifier tube to act in a normal manner.

Image Frequency in a super-heterodyne receiver set

The intermediate stage (mixer + local oscillator) of a super-heterodyne radio set produces an Intermediate Frequency (IF) due to the beating of RF input frequency and Local Oscillator Frequency. This frequency is obtained by deducting the **RF input from the tuned circuit** from that of **Local Oscillator Frequency.** So, while receiving a 800 kHz RF signal, the Local Oscillator is made to oscillate at a frequency of 1255 kHz which results in an Intermediate Frequency (IF) of 455 kHz (which is accepted as a standard in almost all the Broadcast band receiver circuits); **but it is found that in case of comparatively less selective receiver, if a broadcast frequency 455 kHz up, from the 1255 kHz local oscillator frequency manages to intrude the RF tuned circuit even to a little extent, then another difference of frequency equal to intermediate frequency results**; viz. 1710-1255=455 kHz. But this '455 kHz' being generated from **a signal frequency having different audio information causes adverse effect at the audio end of the receiver**. The intelligence of both would be present in the speaker at the same time making the sound reproduction is unintelligible.

Prevention of Image Frequency

(i) By highly selective RF tuned amplifier;

(ii) By using an IF which is convenient to use and at the same time separation between desired and image signals is made large. Possibility of image frequency generation is greater in a receiver designed for an IF of 175 kHz than a receiver using an IF of 455 kHz.

'Selectivity' of a radio receiver

Selectivity is the measure of the ability of a radio receiver to select a particular frequency or particular band of frequencies and rejecting all other unwanted frequencies. But higher selectivity does not necessarily make a better receiver. For instance, a 'broadcast signal' consists of the carrier frequency and its two side bands. In a situation where a carrier frequency of 800 kHz is modulated with a 5 kHz (5000 Hz) tone, the sum of the carrier and the audio frequency results in the Upper Side Band (USB) of 805 kHz. The difference of carrier and audio frequency results in a Lower Side Band (LSB) of 795 kHz. So, for proper reproduction of the broadcast signal at a particular carrier frequency, the receiver must receive (select frequencies from 795 to 805 kHz. A receiver more selective than this would reject a part of the frequencies thus proper reproduction would be hindered.

Sensitivity of a receiver

It is the ability of a radio receiver to respond to the desired radio frequency signal effectively. Higher the ability of the receiver to respond to a weak signal, greater is its sensitivity.

What is a S-meter?

A S-meter is a visual indicator of signal strength. A simple S meter consists of a milliammeter in series with an RF or IF amplifier plate/collector circuit. With no signal, there is no AGC bias voltage and maximum plate current flows. With a signal, the AGC biases the tube, reducing the plate current and the indication on the meter. The stronger the signal, the lower the meter indication, signifying a strong strength.


I-F amplifier
Signal strength meter (S-Meter) indicates relative plate current in AGC controlled circuits
S-Meter
R$_K$
B+
AGC bias

A typical S-meter circuit

What is a Beat Frequency Oscillator?

To change the second detector from a rectifying or envelope detector to a heterodyne detector to receive A1A (Continuous Wave Morse Code), A2A (Modulated CW Morse Code), J3E (Single Side Band), the Beat Frequency Oscillator is turned on. It is a variable frequency oscillator using a Hartley, Colpitts or Armstrong circuit. It is tunable to the Intermediate Frequency and one or two kilohertz higher and lower. It heterodynes with any signal coming through the IF strip, producing an audible beat frequency in the detector. Both the BFO and LO (Local Oscillator) must have good frequency stability.

Why ham radio transmissions are not heard in ordinary radio receiver sets?

The radio sets available in the market for general public are designed to receive Amplitude Modulated (AM) or Frequency Modulated (FM) broadcasts only. But the ham radio operators use a very efficient mode of transmission called Single Side Band (SSB) transmission. The power of a ham radio station is also very low (usually not more than 100 watts) in comparison to the broadcast station (which use power in the kilowatts range). In fact many of the broadcast band radio receivers available in the market also covers some of the frequencies, which are allotted to the ham radio stations. A 4 band radio set (inclusive of the Medium Wave band) can be expected to cover some popular ham radio frequencies like 7 to 7.1 MHz (i.e. 7000 to 7100 kHz), 14 to 14.350 MHz (i.e. 14,000 to 14,350 kHz) and 21 to 21.450 MHz (i.e. 21,000 to 21,450 kHz). This kind of receiver can be improvised to receive ham radio transmissions with very little effort.

First, we will need an outdoor aerial. Because, these radio sets are not sensitive to receive low power transmissions. Majority of the hams use power below 100 watts (a broadcast station may use 4000 or 5000 watts of power or even more than that!). A novice ham radio operator may be found to be operating with a power as low as 0.5 watt!

Ham radio conversation if heard on an ordinary radio set sounds like the 'Duck quacking'. There is no intelligibility in the audio. As already mentioned, our ordinary radio sets are meant to receive AM signals only and not to receive SSB signals-a separate unit is required at the '**Detector**' stage of the AM receiver, which is nothing but a stable '**Frequency Generator**' (RF Oscillator), called the '**Beat Frequency Oscillator**' **(BFO)**. The BFO is used to introduce a '**Local Carrier Frequency**' (frequency of the carrier is 10 to 20 Hertz within that of the transmitter carrier frequency which is suppressed at the transmitter of the ham radio station willingly in order to save power). A BFO can also be used to make the un-modulated Continuous Carrier Wave (CW) transmissions (e.g. in Morse Code transmission) intelligible.

E. Radio Transmitters

Amplitude Modulation and %ge of modulation

Amplitude Modulation (AM) is a process in which the amplitude of a radio frequency current is made to vary and modify by impressing an audio frequency current on it.

A radio frequency current has a constant amplitude in absence of modulation and this constant amplitude RF carries no information, i.e. no audio intelligence and is of no use to radio telephone (voice communication), but has application in morse code communication.

So, to give intelligence to the RF current, audio signal is impressed/ superimposed on the RF current in a non-linear modulator circuit; as a result of which carrier current amplitude begins to rise to a maximum value above and below its original amplitude during the positive cycle of the audio signal and during the negative cycle of the audio signal, it falls to a minimum value.



This results in the carrier having two outlines of the audio signal, this is because the variation at instant in the amplitude of the carrier wave is directly proportional to the value of the modulating signal.

During amplitude modulation, two side band frequencies are also produced. Upper sideband frequencies equal to the carrier frequency plus audio frequency and lower side band frequency is equal to carrier frequency minus audio frequency. So the amplitude modulated carrier occupies a space in frequency spectrum, the width of which is equal to twice the highest modulating frequency.

Percentage of modulation

The degree of modulation in an AM wave is expressed by %ge of maximum deviation from the normal amplitude of the carrier RF wave.

The effect of such modulated wave is measured by a receiver's ability to reproduce the signal in distorted or undistorted manner.

Percentage of modulation=(Voltage$_{Max}$-Voltage$_{Min}$)/(Voltage$_{Max}$+Voltage$_{Min}$) x 100

Where Voltage$_{Max}$ is the maximum instantaneous value of the modulation and Voltage$_{Min}$ is the minimum value of the RF carrier.

Why over modulation is not desirable?

Over modulation is not desirable, i.e. modulation should not exceed 100 %, because if modulation exceeds 100 % there is an interval during the audio cycle when the RF carrier is removed completely from the air thus producing distortion in the transmission.



Distortion is produced due to the absence of RF carrier

• Over modulation

What are the Side-bands of an AM signal?

Side bands are the sum and difference frequencies produced at the transmitter by the modulating frequencies. For instance a 5 kHz (5,000 Hz) Audio tone might be used to modulate an 800 kHz carrier frequency. This would produce frequencies of 800 kHz, 805 kHz and 795 kHz. 800 kHz is the carrier and 795 and 805 kHz are the two side band frequencies.

What is Single Side Band (SSB) transmission?

At full modulation the carrier in an AM signal requires two thirds of the power but conveys no information. The second side band can be viewed as redundant (overlooking frequency-selective fading in an ionospheric transmission path, that may distort one side band at times). Interference between several carrier frequencies, resulting in steady audio whistles or 'beats' is another disadvantage of AM.

Power may be saved and the band occupied by an AM signal in the frequency spectrum can be halved if only one side band is transmitted without carrier. The result is single side band suppressed carrier signal, called simply single side band signal (SSB) transmission.

The carrier must be reintroduced at the receiver in such systems and closely adjusted to the original carrier frequency to avoid signal distortion. The introduced carrier carrier must be within 10 or 20 Hertz of the original carrier frequency for adequate intelligibility of voice signals, and stable oscillators are needed for generation of the local carrier.

For SSB the transmitter does not need to generate carrier power, and ratings are in terms of peak-envelope-power (PEP), the power capability at the peak of the modulating signal with linearity of the amplifier is maintained. For equal information content, and 100% modulation, the SSB signal requires only $^1/_6$ th power of the double side band signal. However, the situation is even more favourable to SSB when speech is transmitted. Speech is not a continuous sine wave, and its average power is low with respect to its peak requirements. A peak-to-average power ratio of 10:1 is often assumed for speech, and under that condition, a Double Side Band (DSB) AM signal would require 1.05 times carrier power, whereas for equal intelligibility the SSB signal would require only 0.05 units of power or $^1/_{21}$ as much.



A balanced modulator circuit using valve

Because of the lower power rating, circuit components designed for SSB equipment can be smaller and lower in cost.

For generation of a modulated signal without carrier, a **balanced modulator** is used. A filter then discards one side band.

Why 100% modulation should be aimed in voice transmission?

The power of a modulated wave is found from the formula:

$P_{mod}=(1+m^2/_2) \times P_{carr}$

Where P_{mod}=Power of the modulated wave,
M=degree of modulation,
P_{carr}=power in the carrier frequency.

The power in an amplitude modulated wave is divided between the carrier and the two side bands. The carrier power is constant, and so, the side band power is the difference between the carrier power and the total power in the modulated wave. The above formula is to find the power of the modulated wave when carrier is modulated by single sinusoidal tone.

If the carrier power=50 watts
%ge of modulation=100 or 1
degree of modulation=1

Then the power of the modulated wave,

$P_{mod}=(1+m^2/_2) \times 50={}^3/_2 \times 50 = 75$ **watts**

Since the carrier power = 50 watts; the two side bands have 25 watts in them, i.e.

${}^{25}/_{75} \times 100\% = 33.3\%$ of the total power with 100% modulation.

In case of 50% modulation with same carrier power we have,

$P_{mod}=(1+0.5^2/_2) \times 50 = 2.25/_2 \times 50 = 56.25$ **watts**

Now the side bands have only 6.25 watts (since 56.25-50 = 6.25)

Since all the intelligence being transmitted is contained in the side bands, the desirability of a high percentage of modulation is crystal clear. A comparatively low powered, but well modulated transmitter often produces a stronger signal at a given point than does a much higher powered, but poorly modulated, transmitted the same distance from the receiver.

Schematic diagram of our intended transmitter and its function in brief

RF Oscillator

This is the stage where the carrier frequency intended to be used is generated by means of Crystal Oscillator Circuitry or capacitance-inductance based Variable Frequency Oscillator (VFO). The RF oscillator is designed to have frequency stability and power delivered from it is of little importance, hence can be operated with low voltage power supply with little dissipation of heat.

Buffer Amplifier

The low power RF carrier output from the RF oscillator is amplified in this portion and it also keeps the RF oscillator and power amplifier circuits separate electrically imparting frequency as desired by the amateur can be done in this stage, when the carrier frequency multiplication technique is applied here. In it the Morse key for keying out carrier continuous wave can be accommodated.



Block diagram of a Single Side Band Transmitter

Modulator

Audio information is impressed upon the carrier frequency at this stage.

Balanced Modulator

In this type of modulator, while the audio information (voice) is impressed upon the carrier frequency, at the same time its output gives a signal without carrier frequency but yet with the two side band frequencies carrying the voice/audio information.

Side-band filter

It discards out any one of the side band.

RF linear Amplifier

RF power amplification is done here and this stage is coupled to the antenna system through antenna impedance matching circuitry. Care is taken at this stage so that no harmonic frequency is generated which will cause interference in adjacent band (splatter) on other bands.

Crystal oscillators

Crystal oscillators are used in most modern commercial radio transmitters, either telegraph or telephone. Quartz crystal oscillators are used because they do not drift more than a few hertz from the frequency for which they are ground. A variable Frequency Oscillator (VFO) tends to drift considerably more.

Crystals made from quartz are used in radio frequency oscillator circuits in order to impart stability to the frequency of oscillation. The function of the quartz crystals are based on the piezoelectric effect, i.e. generation of electricity by compressing or stretching the quartz. Conversely the quartz crystal can be made to expand or contract physically by applying a voltage across it (e.g. by placing it between two metallic plates where the voltage is applied).



Expansion and contraction of a crystal

At its resonant frequency a crystal behaves exactly like a tuned circuit. If a crystal between metal plates is shock-excited by either a physical stress or an electric charge, it will vibrate mechanically at its natural frequency for a short while and at the same time produce an ac emf between the plates. This is somewhat similar to the damped electron oscillation of a shock excited LC circuit.

The circuit shown in the next page is a TPTG (Tuned Plate Tuned Grid) circuit. When the switch is closed, the LC (Inductance-Capacitance) tank in the plate circuit is shock-excited into oscillation by the sudden surge of plate current. The ac developed across this LC circuit is fed back to the top crystal plate through inter-electrode capacitance, and to the bottom plate of the crystal through the bypass capacitor from the LC circuit. The crystal starts vibrating and working as an ac generator on its own. The emf generated by the crystal, applied to the grid and cathode, produces plate current (Ip) variations in the plate LC circuit.



A Tuned Plate Tuned Grid (TPTG) circuit

With both crystal and LC circuit oscillating and feeding each other in proper phase, the whole circuit oscillates as a very stable ac source. The plate LC circuit must be tuned slightly higher in frequency than the crystal to produce the required phase relationship between the two circuits to sustain oscillations.

Block diagram of a simple radiotelegraph transmitter


Antenna
RF Oscillator
Buffer amp.
Power amp.
Telegraph key
Power supply

Block diagram of a simple Amplitude Modulated (AM) transmitter


Antenna
VFO or Crystal oscillator
RF amplifier
RF Oscillator
Buffer Amp.
Driver stage
Power amplifier
Microphone pre-amplifier
Audio amplifier
Modulator

F. Radio Wave Propagation

The Role of Ionosphere in Radio Wave Propagation

Long distance propagation of radio waves depends on an invisible layer of charged particles, which envelops the Earth. This layer of charged particles known as the ionosphere has been in existence for millions of years. For those, who pioneered the long distance radio communication during the early part of the twentieth century, the ionosphere came as a boon. During the formative days of radio communication, radio scientists could not come to a definite conclusion about how radio waves propagated round the world. The father of radio, Guglielmo Marconi himself was at a loss to explain how, on 12th December, 1901, he established the first real long distance wireless communication between St. Johns, New Foundland, USA (now in Canada) and Poldhu in the Southern Tip of England, a distance of more than 3,000 kms across the Atlantic Ocean. At that time, it was known that except for very short distances, the radio waves did not follow the natural curvature of the earth. Earth's curvature is a direct block to line-of-sight communication. When enough distance separates two radio stations so that their antennas fall behind the curvature, the Earth itself blocks the transmitted signals from the receiver, because, electromagnetic waves travel in straight lines until they are deflected by something.

Oliver Heaviside in England and **A.E. Kennally** in America, in 1902, suggested that there must be some kind of reflecting medium in the upper atmosphere that caused the radio waves to be returned to Earth at considerable distances from the transmitter.

Under the action of solar radiation and the hail of meteorites, an ionized layer is formed in the upper part of the Earth's atmosphere. In this layer, the neutral air molecules are decomposed into ions and electrons and the whole layer presents a chaos of charged particles. Short wave radio signals (radio signals which fall in the range of 1.5 MHz to 30 MHz) are reflected from this layer just as light rays are reflected from the surface of a mirror, or sound wave from a barrier. likewise, this layer can be compared to the edge of a billiard table. Communication specialists use this layer like the edge of a billiard table: if the ball does not go straight into the pocket, it can be directed on the rebound! In the same way, the short wave signals radiated by distant radio stations get to our receiver on the rebound. They can continue traveling to several places round the world, for the Earth is also like the edge of a billiard-table.


250-400 km
(F2-layer)
200-250 km
(F1-layer)
100-125 km
(E-layer)
50-90 km
(D-layer)
500 kHz to 1500 kHz up to 250 km
1.5 to 30 MHz up to 4000 km
Lower short wave frequencies (e.g. 1.8 MHz) upto 2000 km
a
b
Transmitting antenna
The Earth

a. VHF signals travel up to the line of sight distance only.
b. Ground waves are stopped by the Earth's curvature.

Different layers of the ionosphere and propagation radio waves

The ionosphere is located above the troposphere, starting at an altitude of 50 kms above the surface of the earth and extending up to an altitude of 400 kms or more. The troposphere is the region of the earth's atmosphere immediately adjacent to the earth's surface and extending upward for some tens of kilometres. Radio waves are refracted or bent slightly, when traveling from one medium to another. **Refraction is caused by a change in the velocity of a wave when it crosses the boundary between one propagating medium and another.** If this transition is made at an angle, one portion of the wave-front slows down or speeds up before the other, thus bending the wave slightly. Radio waves are commonly refracted when they travel through different layers of the atmosphere, whether it is highly charged ionospheric layers 100 km and higher, or weather-sensitive area near the Earth surface. When the ratio of the refractive indices of two media is great enough, radio waves can be reflected, just like light waves striking a mirror.

The role of ionosphere in radio wave propagation can be discussed only in terms of the different radio frequencies available for communication and in the light of the existence of different ionospheric layers. Although the various methods used confirmed the theories of Heaviside and Kennally, there were differences between the results obtained by Professor Appleton and other investigators. It was discovered that there was not one, but more than one reflecting layers in the ionosphere. **The first trials with pulse waves in 1925 by Breit and Tuve in America** were successful in that the method proved to be much more practicable. Since **radio waves take 1 millisecond to travel 300 km**, the height of the layer established from the first echo in this case was found to be 300 km. The ionised layers were designated with letters of the alphabet by E. V. Appleton.

The lowest layer known at a height of about **50 to 90 km** being called the **D region** because this is not strictly a layer **but a relatively dense part of the atmosphere where atoms are broken up into ions by sunlight that recombine very quickly**. The amount of ionisation therefore depends on the amount of sunlight and the region has the effect of absorbing the energy from a radio wave, particularly at frequencies in the band of 3 to 4 MHz and frequently as high as 7 MHz. **High frequencies** (1.5-30 MHz) penetrate this layer, while low frequency (LF: 30-300 kHz) and medium waves are absorbed by this layer. To some extent LF and Very Low Frequency (VLF: 3 to 30 kHz) are reflected during daytime.

The **E-layer** extends from an altitude of 100 km. Though sunlight is an important factor for its existence, after sunset also it exists for some time. This layer is responsible for evening and early night time propagation of medium waves (500 kHz to 1500 kHz) up to a distance of about 250 km. Propagation of lower short wave frequencies, e.g. 2 MHz , up to distance of 2000 km at daylight time is due to this layer. It has little effect at night.

F_1 layer exists at an altitude of 200 km during daytime and its characteristics are very similar to E-layer which merges into F_2 layer at night. HF frequencies in the range of 1500 kHz to 30 MHz (i.e. 30,000 kHz) propagates through this layer during daytime.

F_2 layer is the most important layer, which exists at altitudes ranging from 250 to 400 km and HF long distance propagation round the clock is due to this layer. The behaviour of this layer is influenced by the time of the day, by season and by sunspot activity. **F_2 layer was formerly known as Appleton layer**. This layer has a high ionization gradient. This layer exists both in the daytime and nighttime. Since at such an altitude air density is extremely low, the free ions and electrons (due to the action of ultraviolet radiation from the Sun) cannot recombine readily and so can store energy received from the Sun for many hours; that is the reason **the refractive property of this layer changes only to a negligible extent during day and night**.

The path which the short wave signal follows through the F_2 layer is in reality a curved one. Degree of the curve depends on the angle of incidence of the wave, ionization gradient of the layer and frequency of the signal. Maximum distance for F_2 layer reflection is about 4000 km.

Radio wave propagation by multiple reflection

A strong enough radio signal can propagate by multiple reflections. Having returned to Earth from the ionosphere, the Earth's surface acts as a reflector and returns the signal back to the ionosphere, where it is reflected back to Earth yet again. In this way radio signals can travel around the globe almost instantly! Because, radio wave travels at a velocity of 3,00000 km per second in vacuum. Its velocity gets changed very negligibly in a different medium, which is insignificant, because the earth is a very small place with a radius of only 6000-km. Communication between any two points on the earth is thus almost instantaneous.

Propagation characteristics of different ham radio bands

The problem of variable propagation conditions can be partially overcome by using frequency diversity, in which an allotted wireless communication network is provided with several frequency assignments spanning the high frequency (short wave) band of frequencies. The radio operator can thus choose the channel that gives the best results at any given time. The 1800 kHz (1.8 MHz or 160 metre band) band suffers from extreme daytime D-layer absorption. Even at high radiation angles, virtually no signal can pass through the F layer and daytime communication is limited to ground-wave coverage. **At night, the D layer quickly disappears and world-wide 160m communication becomes possible via F_2-layer skip. Atmospheric and man-made noise limit propagation of this band. Tropical and mid-latitude thunderstorms cause high levels of static in summer, making winter evenings the best time to work long distance at 1.8 MHz.**

The **3500 kHz** (3.5 MHz or 80 metre band) is the lowest HF ham band, which is similar to 160 m in many respects. Daytime absorption is significant, but not quite as extreme as at 1.8 MHz. High-angle signals may penetrate to the E and F layers. **Daytime communication range is typically limited to 400 km, primarily via ground-wave propagation**. At night, signals are often propagated halfway around the world. As at 1.8 MHz, atmospheric noise is a nuisance, making winter the most attractive season for the 80 m. The **7000 kHz** (7 MHz or 40 metre) band is useful for daytime communication up to a distance of **800 km** via **E and F layers**. Long distance world-wide communication takes place in this band through F_2 layer. The **10 MHz** or 30 metre band is unique because it shares characteristics of both daytime and night-time bands. Communication up to **3000 km is typical during daytime**, and this extends halfway around the world. The band is generally open via F_2 on a 24-hour basis. The 10 MHz band is recently released to the Indian ham radio operators.

Skip distance, skip zone and dead zone

Skip distance, skip zone and **dead zone** are importantly associated with ionospheric propagation. If we take a simple case, where a radio receiver located at a distance of

200 kilometres away from the wireless transmitting station is unable to receive the radio signal, but another receiving station (the **intended station**) at a greater distance (say **1000** km) is able to receive the radio signal perfectly, **then distance of the intended receiver from the transmitter is termed as 'skip distance'.**

Despite being located closer to the radio transmitter, one of the receiving stations is not able to receive the radio signal. This is because of the fact that this receiving station is located in a **skip zone** or **dead zone. The ground waves transmitted from the transmitter are unable to reach this receiving station because of signal attenuation by the earth or are stopped by the Earth's curvature and the sky wave will not reach the receiver, because it bounces again more than 200 kilometers way.** So some **'blind zones'** are formed and if the receiver is located in that blind zone it will receive no signal or very weak signal.

The above situations are particularly pronounced in high frequency (HF) signals where ground waves fade away and skip distances may be a thousand kilometers or more. In such a situation, another station (who is not in skip with the station in blind zone) can relay the message to the receiving station located in the blind zone.


Ionospheric layer
Ionospheric layer
←Reflection during day
Reflection during night
Ground wave
Skip zone or 'No signal' zone
Multi-hop transmission due to reflection from the Earth's surface

Skip zone and multi-hop transmission

How do the hams overcome the variable propagation conditions of the ionosphere and the problem of skip?

The problem of variable propagation conditions can be partially overcome by using frequency diversity, in which an allotted communication network is provided with several frequency assignments spanning the High Frequency (HF) band of frequencies. The ham can choose the frequency that gives the best results at any given time. Similarly if a station is in skip at a particular frequency, another workable frequency can be found out.

What is line-of-sight propagation?

The radio frequencies above 30 MHz has the tendency to penetrate the ionosphere making them unsuitable for long distance propagation. So, the range of frequencies from **30 to 300 MHz** (also 300 MHz and above), which are placed under the **Very High Frequency** (VHF) category are mainly used for line-of-sight communication. The most common example of line-of-sight communication is the TV Telecast. Ham radio operators use VHF frequencies in the range of 144-148 MHz (as well as 50 MHz in some countries) for line of sight communication.

A TV transmission tower is made as tall as possible so that its signals can have a wide area of coverage. To receive a TV telecast, we have to turn our TV antenna (known as a Yagi antenna) towards the TV transmission tower. In areas where the TV transmission tower is located at a far away place from a viewer, the viewer has to increase the height of his TV receiving antenna. This means that both the transmitting and receiving antenna should literally see each other to make the communication effective. Otherwise there should be some means to redirect the signal back to the receiver. Artificial Satellites in space (which houses active electronic relaying device), terrestrial relay station and passive reflectors (the metallic plates we see above the hills) are employed to extend the VHF coverage. Line-of-sight communication is considered reliable within a short distance (or even for long distance communication if artificial communication satellites are employed), because instead of relying on the ionosphere (whose propagation conditions are not under human control), relay stations (known as repeater station) can be set up on tall towers. The relay station can cover a certain area most reliably round the clock. Different services employing VHF for communication also have their own repeater station.

Another advantage of VHF is that the size of the VHF equipment is very small (because of its low power as well as miniaturization in the circuit design). A VHF communication set is also popularly known as a Walkie-Talkie. We are certain that the above description is sufficient to clear any doubt about the range of a Walkie-Talkie !



A passive reflector

What are the two phenomenae significant in line-of-sight reception?

In case of line-of-sight reception, sometimes there may be **two components** of the signal. **One** is the **direct signal** and other may be **the signal reflected from the ionosphere** (e.g. in case of a 50 MHz signal, which rarely gets reflected by the ionosphere). Both the signals leave the antenna with the same signal phase, but travel different paths to the receiving antenna. These paths may be of different length. Because the reflected signal **suffers 180 degree phase reversal** at the point of reflection, the two signals may **aid or oppose** each other in the receiving antenna. The resultant signal may be stronger or weaker than the direct path signal alone, which is not desirable.

The problem arising out of the undesirable phase reversal phenomenon can be overcome by varying the height of the antenna.

What is the temperature inversion phenomenon as applicable to the line-of-sight communication?

The line-of-sight propagation is limited to the optical horizon and it is only about 75 km for frequencies above 30 MHz; but it is found that in the spring, or sometimes in summer, this line-of-sight propagation extends to about 500 kms. This is due to the presence of layer of hot, dry air above a layer of cool, moist air. The direct waves are bent back which otherwise pass over the receiving antenna.

What is 'Grey line' propagation as applicable to line-of-sight communication?

It has been observed that around sunspot maximum years at about 11-years intervals, the daytime F_2 layer, roughly 250-400 kms above the surface of the Earth, can often open long distance paths of frequencies up to and beyond **50 MHz**. In periods of low sunspot activity very few long-distance paths are open above 25 MHz. Radio amateurs, whose transmitters are so much less powerful than those used for broadcasting, have come to recognise the importance of what is called **'grey line'** propagation. This takes the form of reliable but brief long-distance paths that open between places where the times of dawn and dusk, dawn and dawn or dusk and dusk roughly coincide, giving rise to the possibility of extended 'one-hop' propagation due to layer entrapment brought about by tilts in the F-layer, as the lower F_1 and higher F_2 layers combine or separate.

What is a critical frequency?

The whole spectrum of radio frequencies suffer various degrees of refraction by the ionosphere. Waves which are very slightly refracted can not return back to the Earth and if not having adequate power, get absorbed into the ionosphere. Those having sufficient power can penetrate the ionosphere depending upon the degree of refraction. **The amount of refraction is inversely proportional to the frequency of the wave.** Obviously, **lower the frequency, greater is the refraction and higher the frequency, lower is the refraction.** Though a greater refraction should cause the frequency to be returned back to Earth, it does not happen always. During day time, the D layer (It is the lowest region of the ionosphere at a height of about 50 to 90 km. It is not strictly a layer but a relatively dense part of the atmosphere where atoms are broken up into ions by sunlight that recombine very quickly) absorbs most of these waves prohibiting their entry into the E and F layers and hence does not get reflected. **If the frequency of a wave transmitted directly upward is steadily increased, a point would be reached where the wave would pass right through the ionosphere. The frequency at which this occurs is called the *critical frequency*.** All frequencies higher than this will not be returned to Earth.

What is a beacon?

The beacon is nothing but a radio signal, usually in coded form transmitted from a particular station to identify itself. The usefulness of the beacons is that they provide indication of propagation conditions between any two locations worldwide. They also act as in-band frequency reference for wireless experiments experimenting with transmitters. They also provide reliable checking facility for beam antennae.

What are differences between fade-out and fading?

Fade-out

It is the gradual phenomenon, that take place with the change of time of the day. Fadeout of radio signal is related to the ionization gradient of the ionosphere, which decreases in absence of sunlight. Since ionization is intense during day light hours, higher frequencies of the short wave spectrum can be used during daylight hours. As the night approaches, signal strength at that higher frequency decreases. Using a frequency at the lower edge of the HF spectrum will yield satisfactory result against this fadeout.

Fading

As distinct from fade-out, fading is the constant variation of the received strength of radio wave. To the listener it appears as gradual rising and falling of the volume. The signal waxes and wanes and at times even drops below usable values. This phenomenon is manifested chiefly in long-distance transmission. It is caused by multiple reflections from the ionosphere which cause two or more waves from the same transmitter travel over different paths of different lengths and hence differ in phase and amplitude when they arrive at the receiving aerial.

G. Aerials

A General Note on Aerials

Aerial or antenna is a device, which acts as the mouth and ear of a radio transmitter or receiver respectively. Though we don't notice any external aerial in many of the commercial radio sets, they in fact, have aerials in built within the cabinets holding their electronic circuitry. But a ham radio operator is mainly concerned with an external outdoor antenna without which he can't expect to radiate radio energy into space from his radio transmitter. Similarly, without an external outdoor antenna, his radio receiver will not be able to pick up the radio waves speeding across the sky. A radio receiver might not need an external outdoor aerial to receive high power radio transmissions. But most of the ham radio transmitters use considerably low power (compared to the broadcast radio stations) which necessitates the use of outdoor aerials. A low power transmitter with an efficient antennae system or a less sensitive receiver with efficient antennae system can be made to work beyond imagination!

The aerials are usually made out of metallic rods or wires which are cut into specific lengths. The aerial should not be placed behind any obstruction, conducting materials such as tin-roof, ferro-concrete and to lesser extent foliage when wet. The aerial should be as high as practical above the ground and grounded objects such as metal roofs, power or telephone wires etc.

Different types of antenna system used by ham radio operators:

(1) Horizontal Dipole,
(2) Inverted -V dipole,
(3) Yagi beam,
(4) Ground plan vertical,
(5) Cubical quad

Horizontal dipole is a very popular antenna, which is also easier to construct and erect. Two supporting structures (e.g. two bamboo poles) are required to erect a simple horizontal dipole antenna, whereas an inverted 'V' dipole antenna requires only a single pole further simplifying the erection method. This single pole at the same time supports the feed-point of the dipole. A horizontal dipole antenna is directional in nature, but given an inverted shape (e.g. an inverted 'V' antenna), it becomes omni-directional. However, the ends of the inverted 'V' dipole should not come too close to lossy ground. The input impedance of this antenna with apex height of half wavelength long and apex angle of 127° is 50 Ohms (RG11 coaxial cable).

Working function of a horizontal dipole antenna

A horizontal dipole antenna is a resonant antenna, which is half-wavelength long. Resonant circuits are well-known in radio engineering as combination of coils and capacitors, which cause a signal gain at certain frequencies. The same is applied to a half-wave dipole antenna.


Insulator tied to the bamboo pole
Feedpoint of the inverted 'V' dipole
1/4 wave length long copper wire
50 ohms coaxial cable
Tie the coaxial cable to the bamboo pole
1/4 wave length long copper wire
Insulator
Insulator
Bamboo pole
Plastic rope
Plastic rope

An inverted 'V' dipole antenna


Feedpoint of the dipole
1/4 wave length long copper wire
1/4 wave length long copper wire
Insulator
Insulator
Insulator
Plastic rope
Plastic rope
Inner conductor of the coaxial cable is soldered to one end of the copper wire
Outer sheath of the coaxial cable is soldered to one end of the copper wire
75 ohms coaxial cable

A practical dipole antenna

It consists of two straight wire or rod sections, each $^1/_4$ wave long and positioned in one line (collinear). The antenna is fed in the centre by a coaxial cable having a characteristics impedance of 50 Ohms or 75 Ohms.

The maximum radiation direction is perpendicular to the axis from the middle point. The cause of directional radiation by a resonant $^1/_2$ wave dipole antenna is that the radiation intensity is proportional to the square of the current in the antenna, and in the dipole current is maximum at the middle; hence the maximum radiation line passes through the middle of the antenna perpendicularly.


Direction of maximum radiation
Maximum current
Maximum voltage point
Radiation intensity decreases in this direction
No radiation
No radiation
1/4 wave length long splitted rod
Maximum voltage point
1/4 wave length long splitted rod
Direction of maximum radiation

Characteristics of a half wave dipole antenna

Why half-wave dipoles are fed at the centre?

Most half-wave dipoles are fed at the centre, because in a half-wave resonant dipole, maximum current point is at the centre of the antenna and this is the minimum voltage point. It is easier to construct transmission lines for low voltage than for high voltage.

The other reason is that in a 1/2 wave dipole, the capacitive reactance and inductive reactance cancel each other (the antenna being resonant), leaving resistance only as net impedance. Under this condition, the antenna impedance is the resistance between any two points equidistant from the centre along the antenna length making it easier to match the transmission line impedance with the antenna impedance.

What is VSWR (Voltage Standing Wave Ratio)?

When the transmission line does not match the load impedance (antenna impedance), maximum transference of energy to the antenna is not possible. The energy fed down the line is transferred to the antenna only partially; in fact, some is reflected back, forming standing waves on the line. Every half-wave along the line, high-E (Voltage) and Low-I (Current) points appear. Halfway between these two points will be Low-E and High-I points.

The ratio of voltage across the transmission line at the high-E point to that at Low-E points is called the VSWR.

$$VSWR = E_{max}/E_{min}$$

Or,

$$SWR = I_{max}/I_{min}$$

The SWR is also equal to the ratio of the characteristic impedance of the transmission line to the impedance of the antenna (load), or vice versa. For example, if the line has a characteristic impedance of 300 ohms and antenna impedance is 50 ohms, the SWR is 300/50, or 6. A higher SWR indicates a greater mismatch between the transmission line and the antenna.

When the load (antenna) impedance matches the transmission line impedance, there will be no standing waves.

SWR=1:1 or 1

VSWR is greater than one for a mismatched system and equal to one for a perfectly matched system.

VSWR on a transmission line is caused by power being reflected back to the transmitter from the antenna. If P_F is the forward power and P_R is the reflected power measured in watts by a directional wattmeter, then VSWR can also be calculated by the formula:

$$VSWR = \frac{1+\sqrt{P_F/P_R}}{1-\sqrt{P_R/P_F}}$$

What is 'radiation resistance'?

When an antenna is excited into oscillation by a RF source, it radiates energy into space acting as a source of power. The antenna, which is the source of power must have an internal resistance or impedance.

We have-

Power, $\mathbf{P=I^2R}$,

Where I=current, R=resistance

Or, $\mathbf{R=P/I^2}$

So in case of the antenna, radiation resistance is the **ratio of the radiated power to the square of the centre current in the antenna.**

Radiation resistance is also defined as a **fictitious resistance**, which when substituted for the antenna would consume as much power as the antenna radiates.

Radiation resistance is also called **'Feed-point' impedance**; in case of a dipole antenna feed point impedance is nearly 73 Ohms.

Why impedance matching is necessary in an antenna and transmission line system?

Impedance matching is of utmost importance so far as energy transference from the transmitter to the antenna through the transmission line is concerned; because, mismatching will prevent maximum output being radiated, i.e. if the transmission line impedance doesn't match the antenna feed-point impedance, a part of the energy fed down the line will be reflected back from the antenna causing standing waves on the line; it makes the system inefficient.

Mismatching a transmission line to an antenna results in the line at the transmitter end appearing to have either inductive reactance (X_l) or capacitive reactance (X_c), which will detune the inductance-capacitance (LC) circuit to which it is coupled; mismatching should be avoided so that final stage of the RF amplifier is not detuned.

In many of the commercial wireless equipment, mismatching should be strictly avoided to prevent damage of the circuitry.

What is a current fed antenna?

There are many methods of feeding energy to an antenna. The antenna is said to be current fed when excitation energy from the RF-generator is introduced to the antenna at the point of high circulating currents. The example is **a $^1/_2$ wave dipole antenna.** In this case, the $^1/_2$ wave antenna is cut in two parts at the midpoint and energy is fed by co-axial transmission line.

In a dipole antenna maximum current flows through the middle point, hence it is current fed antenna with a characteristic feed point impedance of about 73 ohms, which is considerably small as compared to end point impedance of the antenna. Midpoint is the low-voltage point.

What is a voltage fed antenna?

When the excitation energy from the RF source is introduced at the point of maximum voltage, the antenna is said to be voltage fed antenna. The example is the $^1/_2$ wave unsplitted antenna excited by a resonant R-F line. Voltage changes at this point excite the antenna into oscillation. The impedance at the end of the antenna is high or it is the high impedance point.

Any multiple of a $^1/_2$ wave resonant antenna may be end-fed by using a tuned feeder system leaving one end of the feed-line unconnected. This antenna is also called Zepp (used earlier on Zeppelins) antenna.


Point of maximum voltage
1/2 wave unsplitted rod
Point of maximum current
Point of maximum voltage
RF transmission line
Antenna tuner circuit

Voltage fed dipole antenna

Different types of antenna system impedance matching procedure

(a) Using the **proper transmission line** for each particular antenna is a way of achieving impedance matching. For example, a $^1/_2$ wave horizontal dipole has a midpoint impedance of 73 ohms, so coaxial cable transmission line which has a characteristic impedance of 75 ohms (e.g. RG8) is used to feed the R-F energy into the antenna.

(b) **Delta match:** This type of matching procedure is used with an unsplitted $^1/_2$ wave dipole antenna; the dipole being resonant, its capacitive reactance (X_c) and inductive reactance (X_L) cancel each other, leaving resistance only as net impedance. Under this condition, the antenna impedance is the resistance between any two points equidistant from the centre and thus transmission lines having characteristic impedance of 300 to 600 ohms be used by getting two points of the antenna to feed where it offers a feed point impedance equal to transmission line impedance.
To do so, it is essential to spread out the feeders at the antenna end.
The formula used to make this type of matching are :
B= (0.25 x Wavelength)/2; where B is the distance between the two feed point which will offer 600 ohms impedance.
And C=(0.32 x wavelength)/2, where C is the vertical distance upto which spreader should be spread (the inclination).


1/2 wave unsplitted dipole
B
C
Flat 600 ohms transmission line

Delta fed dipole antenna

(c) **Stub Match** : A shorted stub of $^1/_2$ wave length or open stub of 1/4 wave can be connected to the splitted dipole. Here the low midpoint impedance of 73 ohms of the dipole is repeated at the close end of the stub; but there are cetain points on the stub which would offer as high as 600 ohms impedance yet matching with 73 ohms feed point.


1/4 wavelength long rod
1/4 wavelength long rod
1/2 wavelength long shorted stub
600 ohms transmission line
600 ohms point

Half wave shorted stub

(d) **Gamma Match**: Here outer sheath of the 75 ohms coaxial cable is connected to the middle point of the unsplitted dipole, while the inner conductor is connected to a point through a capacitor to cancel inductive reactance, so that antenna impedance at feed point is 75 ohms. Gamma match is slightly unbalanced.


1/2 wave dipole
Capacitor
Coaxial cable
75 ohms

Gamma match

(e) **T-Match**: In this type of impedance matching, two coaxial cables are held side by side and both their outer sheaths are connected to the midpoint of the unsplitted dipole, while two points are chosen on the dipole where inner conductors going parallel to each other (of the coaxial) are connected.


1/2 wave dipole
Capacitor
Capacitor
Coaxial cable
Coaxial cable

T match

(f) **1/4 wave transmission line impedance matching device**: A 1/4 wave line can act as an impedance matching device between high and low impedance

circuits if it has the proper intermediate impedance found from the formula: $Z = /Z_1.Z_2$
Where Z1 = antenna feedpoint impedance; Z2 main transmission line impedance. When we want to match a 300 ohms transmission line to a 70 ohms feed point impedance dipole antenna, then the 1/4 wave transmission line connected between both the system should have
Z= / 300 x 70 = 145 ohms

What is a Yagi antenna?

When a half wave dipole antenna consists of one or more parasitic arrays, the antenna becomes parasitic beam antenna, named as "Yagi" after its designer Proff. Yagi, Japan.

The antenna consists of mainly three elements, the **1/2 wave splitted dipole driven element (either folded or straight)**, in front of this driven element is the 5% shorter **director element**, back of the driven element is the 5% longer **reflector**. All the elements can be assembled on a **single conducting boom**. This antenna beams radio signals in the direction of the director and theoretically no signals to the backward direction. Yagi antenna is most commonly used for very high frequency (VHF) work. Because of shorter wavelengths, it is easier to construct a Yagi antenna for VHF work than the HF work. Instead of using a folded dipole (the driven element), as shown below in the diagram, the driven element can be kept unfolded (straight). In that case, the feed-point impedance of the antenna would be around 75 Ω.


Minimum radiation in this direction
Boom or support for elements (metallic or insulator)
1/2 λ folded dipole (Driven element)
Reflector element
Maximum radiation in this direction
Very little radiation in this direction
Director element
300 Ω transmission line
Minimum radiation in this direction

A 3 element Yagi beam antenna

Part-IV

Study material to learn Morse Code

The International Morse Code

The telegraphic code used for amateur radio telegraphic communication is the International Morse Code consisting of dot (.) and dashes (-). In Morse Code a dot (.) is made by pressing the telegraph key down and allowing it to spring back up again rapidly; and for making a dash (-), the key is held down for a bit longer period. It is said that a dash(-) unit is three time longer than a dot(.) unit. The Morse Code in fact consists of combinations of aurally distinguishable tones. A tone produced for short duration is a dot tone and a tone three times longer than this tone is a dash tone.



A Morse Key

To practice Morse Code sending, a novice can use a small device called the 'Code Practice Oscillator' (CPO). This is a small electronic circuit capable of generating a sinusoidal audio tone when a key (or switch) is made 'on' or 'off' manually. The circuit of a CPO shown below can be easily assembled by a novice.



A Code Practice Oscillator (CPO) circuit

It is advisable not to start practice sending the Morse code until the novice is proficient in receiving Morse code. For receiving practice, you have to rely on a ham radio operator who can send/generate Morse code using a CPO or you can try to find out Morse Code transmissions over your radio receiver. Morse code practice cassettes and multimedia computer software are nowadays available. Mere gaining confidence in sending does not qualify you to be an expert receiver! In fact you may not be able to receive a single letter in Morse code even if you gained a sending proficiency of 12 words Per Minute (WPM)! Remembering the Morse codes is an art by itself. It involves a rhythmic response in your mind. Try to remember the combination of dot (.) and dashes (-) by their sound and not as a group of printed symbols. For this purpose, a dot (.) is referred to as a *'di'* and a dash (-) as a *'dah'*. A *'di'* coming at the end of the combination is pronounced as *'dit'*

The letter 'R' is represented by '. - .' (*di dah dit*) in Morse code. The time taken to produce the sound equivalent to one 'di' or 'dit' (dot) is taken as unit time and called a dot unit. A 'dah' is approximately of three dot units length and the space between two sound elements of a letter is one dot unit, i.e. silence period is one dot unit. The space between two letters or characters is equal to three dot units. The space between two words is equal to five dot units. The word 'cat' can be represented as -.- (*dah di dah dit di dah dah*)



Morse Code speed

The minimum speed to qualify for a Grade II licence is 5 words per minute (5 wpm). 5 letters/characters constitute a word. A message containing 125 letters when sent in 5 minutes or when received in 5 minutes makes your speed 5 wpm.

$^{125}/_{5}=25$ words in 5 minute; i.e. 5 words per minute.

In fact Morse code devised by **Samuel F.B. Morse** (1791-1872) is a primitive type of digital communication which still works efficiently in this era of microprocessors and computers.

Morse code is also called CW, i.e. **Continuous Wave**, in the sense that a constant amplitude interrupted radio frequency wave is transmitted; interruption being made in conformity with the code.

Analog and Digital methods

The electrical telephone and telegraph are very simple examples which illustrates the difference between the analog and digital methods. In the telephone, the information is transmitted from one end to the other via a current which varies continuously as direct equivalent of sound waves striking the microphone-the analog approach. In the telegraph, the information is encoded (cyphered) and sent as a sequence of current/no current pulses illustrating the digital approach.

Why Morse code is still in use?

It was deemed important that ham radio operators prove an ability to transmit and receive in Morse Code signals. In the last 50 years, however, the **International Telecommunication Union (ITU)** has reviewed and modified the amateur Morse Code requirement at every international conference capable of changing it. In 1947 (Atlantic City) the ITU agreed that Morse proficiency should only be required when the operation took place on frequencies below **1000 MHz** (1 GHz). At WARC-59 (The 1959 World Administrative Radio Conference) this level was dropped to**144 MHz.** A further reduction was made at WARC-79 to its presents **30 MHz.**

Despite the capability of voice communication, Morse code is still in use. One important reason is that a vast group of the radio amateurs still adore Morse code. A **ham radio operator employing digital communication techniques (like Packet Radio, Radio Tele Typing-RTTY or AMateur Tele-printing Over Radio-AMTOR) in his ham radio operation treats Morse code with much the same affection he has for those modern innovations!**

A ham radio operator wearing his headphone and the Morse Key in hand can send messages silently without disturbing his family members who might be sleeping comfortably!

Another reason is that short wave radio telephone (voice) signals often suffer very rapid and deep fading; two frequencies separated by only a few hertz, fade at different times. To overcome this, modulated code tones are transmitted. The situation is now that under severe conditions of fading, the carrier frequency may fade out completely but one or the other side band may remain strong as a result a continuously readable signal is received. This is the reason that we hear a band full of exotic sounding CW call-signs at any time of day or night. When the a band appears to be dead, and we can barely copy phone signals, the band remains alive with many CW signals.

Why this be so?

(i) The answer is that to communicate human speech, a wider bandwidth is required than that of the CW signal. With a smaller bandwidth the 'signal to noise ratio' of the receiver is significantly improved, and the threshold at which signals can still be received above the noise level is therefore extended.

(ii) Also, it is possible for the human ear to be able to resolve CW signals which are only marginally above the noise level, whereas SSB signals of the same signal level could not be copied. It has been suggested that CW has an advantage of approximately 20dB over SSB signals. A narrow band-pass filter improves the CW reception.

How to learn Morse Code?

Many newcomers seek exemption from 'tiresome' Morse test for Short wave operation. This is unfortunate as the Morse code is the key to enter into the world of ham radio with a very little monetary investment. A novice can assemble a simple Morse code transmitter with lesser technical hurdles than that of a SSB Voice transmitter. Morse code can be learnt easily if we use certain techniques to remember the codes. Learning the Morse code can also be considered as an entirely personal venture embarked upon by alone. Following points should be kept in mind while learning the Morse code-

(1) Try to remember the codes from their sound.

(2) Don't begin with a practice to send. Sending is much easier compared to receiving.

(3) During receiving of a message, don't write down the '*dot*' and '*dash*' combinations. Directly write down the letters in running hand. Don't bother to know the content of the message. Just continue writing the letters one by one and leave a space when you are not sure about the letter. If you wait wondering about what the letter was, you would get stuck and in the process many letters would pass by you, which you would not be able to jot down.

THE INTERNATIONAL MORSE CODE

A	._	J	.___	S	...	1	.____
B	_...	K	_._	T	_	2	..___
C	_._.	L	._..	U	.._	3	...__
D	_..	M	__	V	..._	4	...._
E	.	N	_.	W	.__	5	.....
F	.._.	O	___	X	_.._	6	_....
G	__.	P	.__.	Y	_.__	7	__...
H	....	Q	__._	Z	__..	8	___..
I	..	R	._.			9	____.
						0	_____

PUNCTUATIONS

. (Period)	._._._	(AAA)
, (Comma)	__..__	(MIM)
? (Question mark)	..__..	(IMI)
; (Semicolon)	_._._.	(NNN)
- (Hyphen)	_...._	(BA)
Error sign	....	(8 dots)
Sentence separation indicator	_..._	(BT)
End of transmission of a message	._._.	(AR)
Invitation to transmit	_._	(K)
Wait	._...	(AS)
End of work	..._._	(VA)

Almost all the letters/characters and punctuation marks can be arranged in certain groups which can used to show the resemblance between/among the combination of *dot* and *dashes*. For example the letter 'A' (. _) is the opposite of 'N' (_ .). Similarly, the letters A, U, V and the character 4 can be made into a group which shows a definite sequence. Given below is a table of such combinations.

Groups of letters/characters, which show definite sequence/resemblance

A •_ U ••_ V •••_ 4 ••••_	T _ M __ O ___	N _• D _•• B _•••	E • I •• S ••• H •••• 5 •••••
W •__ G __•	Y _•__ Q __•_	K _•_ R •_•	P •__• X _••_
L •_•• F ••_•	A •_ N _•	D _•• U ••_	B _••• V •••_

Part-V

Safety Measures in a Ham Radio Shack

Electricity is one of the most magnificent discoveries that the mankind has achieved since the dawn of civilization. We are now wholly dependent on this wonder of science. Without electricity our life will become miserable and probably the life will come to a standstill. It is the backbone of an industrialized society without which progress of a society can't even be dreamt of. Functioning of all the fields of science are wholly dependant on the availability of electricity including your ham radio! While electricity has made our life full of comfort and ease, it has also the potentiality to create heavy destruction if we do not take adequate precautions against its potential ills. A casual attitude towards the electricity should always be avoided.

The ham should keep his wireless equipment in a protected place, so that, it can not be operated by any unauthorized person in his absence. All the equipment should be properly installed and precaution should be taken so that they don't create electrical hazards. For this and the safety of the other people in the house, equipment should have proper ground connection (an alternative path to the Earth). Though the switch board sockets have the facility to insert a three pin electrical plug (the male plug from our equipment), the wire connecting to the ground from the third hole of the socket may remain disconnected somewhere without our knowledge. This may create a risk to your life because the electrical equipment's current carrying wires are vulnerable to insulation breakdown due to many reasons. Under such circumstances, if a current carrying wire touches the metallic portion of the equipment, current will start flowing in that portion also. Under such a situation, if we touch an electrical gadget housed in a metallic enclosure, we may get electrocuted as well! In fact electrical currents seek for the paths of low resistance. In the above situation, if we are bare footed, then these electrical currents will find their easiest path to the Earth (Ground) through our body and simulate a close circuit situation. Our body will heat up (because the human body too offers resistance to the flow of current) and we will die!



A three pin plug should not be relied upon unless the electrical wiring of your house is properly checked

Electrical gadget covered by metallic enclosure should be properly grounded because a current carrying wire inside it may loose its insulation and thereby touch the metal cabinet making the enclosure unsafe

A wooden board can provide additional safety by insulating you from the ground!



a break in the ground connection line which remains unnoticed makes the three pin socket useless from the safety point of view

In a different situation where the metallic portion of the electrical gadget is properly grounded with the help of a good conducting wire (e.g. copper), even if we touch the current carrying metallic portion, most of the current will flow through that grounded copper wire only causing less damage to our body. A part of the current will still find their path to the ground through our body because we are still bare footed! So the highest safety measure is to wear shoes made of insulated material (which do not conduct electricity) and keep us separated from the ground (the Earth). In this situation, even if we accidentally touch the current carrying metallic portion of the electrical gadget, current will not able to find their path in to the ground through our body and we shall remain safe. In no case, the 'phase' (current carrying) and 'neutral' wires should be touched by your hand simultaneously. Doing so will create the most potential risk to your life, because, current from 'phase' to 'neutral' will now flow from one hand to the other hand (if you use both your hands to touch the 'phase' and 'neutral' !) through your body and you will be getting killed in the process!

So, always:

1. Check for **proper ground connection** in the electrical wiring of the house.

2. If possible connect an **extra conducting wire to the ground** (you can tightly tie the wire on to a water pipe) from the metallic enclosure of the electrical gadget.
3. **Don't touch electrical gadgets with wet hand.** Water reduces the resistance of the skin of our body and as a result electrical currents find their easy entry into our body!
4. Always wear **insulated shoes** (rubber, plastic etc.)
5. **A dry wooden board** can be kept on the floor which will provide additional insulation.
6. The electrical device should have **a 'fuse'** as per the current rating of the device. For example, if the equipment is designed to allow a current of 5 ampere, the 'fuse' should also be rated 5 ampere. Any more current due to short circuit will blow the fuse and inactivate the equipment. This will prevent further damage of the equipment and other electrical wiring will remain safe.
7. There should be **a main switch** (called the *"Big Switch"*!) at your easy reach. While closing down your ham radio operation, this switch should be pulled to disconnect all the equipment at the same time. That is why, in ham terminology, many operator's use the phrase ***"Pulling the Big Switch"*** to indicate that he is closing down his station!
8. Now-a-days, **miniature circuit breaker** switches (MCB) are also available. This type of switches provide safety to the electrical gadgets connected to the electrical sockets by automatically disconnecting them from the current in the event of a short circuit in the electrical wiring.
9. The **fuses in the electrical meter box should not be tempered with**. A blowing fuse indicates that an electrical gadget is drawing more current than its specification. Alternatively, you may be using too much of electrical gadgets in your house resulting in a current flow which exceeds your allotted rating. In such a situation, if you increase the thickness of the fuse wire to prevent it from frequently burning down, the whole electrical wiring of your house will at the risk of burning down.

Annexure-I

List of Wireless Monitoring Stations conducting Amateur radio licencing examination

Ahmedabad:
Officer-in-Charge,
Wireless Monitoring Station, A/101,
Amarkunj Aparrtments, Opp.
Gurukul,
Ahmedabad-380052

Ajmer:
Officer-in-Charge,
Wireless Monitoring Station,
Christianganj, Shantipura,
Ajmer-305 001

Bangalore:
Officer-in-Charge,
Wireless Monitoring Station, 18,
Padmanabha Nagar,
Banashakari,2nd Stage, Bangalore-
560070

Bhopal:
Officer-in-Charge,
Wireless Monitoring Station,
E-1/149,
Arera Colony,
Bhopal-462003

Calcutta:
Officer-in-Charge,
Wireless Monitoring Station,
Village-Gopalpur, P.O. Sarkarpool,
24-Parganas,
Calcutta- 743352

Darjeeling:
Officer-in-Charge,
Wireless Monitoring Station, 7,
Oak's Rose Bank Building, Holding
No. 560,
Darjeeling 734101

Dibrugarh:
Officer-in-Charge,
Wireless Monitoring Station,
Girdharilal Sardarmall's Building,
Mancotta Road,
Dibrugarh-786001

Delhi:
Engineer-in-Charge,
Regional Headquarter (N),
E-315, Pushpa Bhavan, Madangir
Road,
New Delhi-110 062

Gorakhpur:
Officer-in-Charge,
Wireless Monitoring Station, Avas
Vikas Colony, Surajkund,
Gorakhpur-273001

Goa:
Officer-in-Charge,
Wireless Monitoring Station, Near
Teachers' Training College, P.O.
Alto Betim,
Goa- 403112

Hyderabad:
Officer-in-Charge,
Wireless Monitoring Station, 1-1-
648/4
Gandhi Nagar,
Secunderabad-500380

Jalandher City:
Officer-in-Charge,
Wireless Monitoring Station, 327,
Mota Singh Nagar, Jullander City
144001

Jalna:
Engineer-in-Charge
International Satellite Monitoring
Earth Station, Indewadi Village,
Ambad Road,
Jalna-431203

Madras:
Officer-in-Charge,
Wireless Monitoring Station,
Perungudi,
Madras-600096

Mangalore:
Officer-in-Charge,
Wireless Monitoring Station, 3-1
Bijai,
Swarna Niketan,
Mangalore-575004

Mumbai:
Officer-in-Charge,
Wireless Monitoring Station, G
Road, Borivili (W),
Mumbai 4000092

Nagpur:
Officer-in-Charge,
Wireless Monitoring Station, C
Road, P.O. Koradi T.P.S.,
Nagpur 441111

Ranchi:
Officer-in-Charge,
Wireless Monitoring Station, P.
Harmo Housing Colony,
Ranchi-834012

Shillong:
Engineer Inspection,
Wireless Monitoring Station, La
Rynjah,
Shillong-793006

Srinagar:
Officer-in-Charge,
Wireless Monitoring Station, K
Rajbagh,
Srinagar-190008

Trivandrum:
Officer-in-Charge,
Wireless Monitoring Station,
T.C. 9/951-1, Panicker's Lane,
Sasthamangalam,
Trivandrum- 695010

Visakhapatnam:
Officer-in-Charge,
Wireless Monitoring Station,
6-20-9,
Chinna Waltair,
Visakhapatnam- 530023

Schedule of licencing examination:

Place	Month of Examination
Delhi, Mumbai, Calcutta & Madras	Every month
Ahmedabad, Hyderabad & Nagpur	January, March, June, August, October & December
Ajmer, Bangalore, Bhopal, Darjeeling, Dibrugarh, Gorakhpur, Goa, Jalandhar, Jalna, Mangalore, Ranchi, Shillong, Srinagar, Trivandrum, Visakhapatnam	January, April, July & October

Annexure-II

Call-sign Prefixes of Amateur Radio Stations of different countries allotted by the International Telecommunication Union (ITU)

Prefix	**Country**	**CQ Zone**
1AO	Sovereign Military Order of Malta	15
1S	Spratly Is.	36
1X	Chechnya (erstwhile USSR)	
2A-2Z	United Kingdom	14
3A	Monaco	14
3B6,7	Agalega & St. Brandon	39
3B8	Mauritius	39
3B9	Rodriguez Is.	39
3C	Equatorial Guinea	36
3C0	Annobon	36
3D2	Fiji, Conway Reef, Rotuma Is.	32
3DA	Swaziland	38
3DN	Fiji	32
3K3	European Islands between 30 Deg. E long. To 170 Deg. W long	
3V	Tunisia	33
3W, XV	Vietnam	26
3X	Guinea	35
3Y	Bouvet	38
3Y	Peter Is.	12
3Z	Poland	15
4F	Philippines	27
4JA-4JZ, 4KA-4KZ	Azerbaidjan	21
4J1, R1MV	Malyj Vysotskij Island	16
4K0	Drifting Ice Station (Russian Polar Stations)	
4K1	Antarctica (Russian Polar Stations)	
4K4	Asian Islands between 65 Deg E long. To 170 Deg. W long	
4K2	Franz Josef Land (Russian Polar Stations)	40
4LA-4LZ	Georgia	21
4P-4S	Sri Lanka	22
4U	ITU Geneva	14
4U	United Nations Headquarters	05
4X, 4Z	Isreal	20
5A	Libya	34
5B, P3, H2	Cyprus	20
5H, 5I	Tanzania	37
5N, 5O	Nigeria	35
5R, 5S	Madagascar	39

Annexure-I

List of Wireless Monitoring Stations conducting Amateur radio licencing examination

Ahmedabad:
Officer-in-Charge,
Wireless Monitoring Station, A/101,
Amarkunj Aparrtments, Opp.
Gurukul,
Ahmedabad-380052

Ajmer:
Officer-in-Charge,
Wireless Monitoring Station,
Christianganj, Shantipura,
Ajmer-305 001

Bangalore:
Officer-in-Charge,
Wireless Monitoring Station, 18,
Padmanabha Nagar,
Banashakari,2nd Stage, Bangalore-
560070

Bhopal:
Officer-in-Charge,
Wireless Monitoring Station,
E-1/149,
Arera Colony,
Bhopal-462003

Calcutta:
Officer-in-Charge,
Wireless Monitoring Station,
Village-Gopalpur, P.O. Sarkarpool,
24-Parganas,
Calcutta- 743352

Darjeeling:
Officer-in-Charge,
Wireless Monitoring Station, 7,
Oak's Rose Bank Building, Holding
No. 560,
Darjeeling 734101

Dibrugarh:
Officer-in-Charge,
Wireless Monitoring Station,
Girdharilal Sardarmall's Building,
Mancotta Road,
Dibrugarh-786001

Delhi:
Engineer-in-Charge,
Regional Headquarter (N),
E-315, Pushpa Bhavan, Madangir
Road,
New Delhi-110 062

Gorakhpur:
Officer-in-Charge,
Wireless Monitoring Station, Avas
Vikas Colony, Surajkund,
Gorakhpur-273001

Goa:
Officer-in-Charge,
Wireless Monitoring Station, Near
Teachers' Training College, P.O.
Alto Betim,
Goa- 403112

Hyderabad:
Officer-in-Charge,
Wireless Monitoring Station, 1-1-
648/4
Gandhi Nagar,
Secunderabad-500380

Jalandher City:
Officer-in-Charge,
Wireless Monitoring Station, 327,
Mota Singh Nagar, Jullander City
144001

Jalna:
Engineer-in-Charge
International Satellite Monitoring
Earth Station, Indewadi Village,
Ambad Road,
Jalna-431203

Madras:
Officer-in-Charge,
Wireless Monitoring Station,
Perungudi,
Madras-600096

Mangalore:
Officer-in-Charge,
Wireless Monitoring Station, 3-1-41,
Bijai,
Swarna Niketan,
Mangalore-575004

Mumbai:
Officer-in-Charge,
Wireless Monitoring Station, Gorai
Road, Borivili (W),
Mumbai 4000092

Nagpur:
Officer-in-Charge,
Wireless Monitoring Station, Chindwara
Road, P.O. Koradi T.P.S.,
Nagpur 441111

Ranchi:
Officer-in-Charge,
Wireless Monitoring Station, P.O.
Harmo Housing Colony,
Ranchi-834012

Shillong:
Engineer Inspection,
Wireless Monitoring Station, Lapalang,
Rynjah,
Shillong-793006

Srinagar:
Officer-in-Charge,
Wireless Monitoring Station, Kursu,
Rajbagh,
Srinagar-190008

Trivandrum:
Officer-in-Charge,
Wireless Monitoring Station,
T.C. 9/951-1, Panicker's Lane,
Sasthamangalam,
Trivandrum- 695010

Visakhapatnam:
Officer-in-Charge,
Wireless Monitoring Station,
6-20-9,
Chinna Waltair,
Visakhapatnam- 530023

Schedule of licencing examination:

Place	Month of Examination
Delhi, Mumbai, Calcutta & Madras	Every month
Ahmedabad, Hyderabad & Nagpur	January, March, June, August, October & December
Ajmer, Bangalore, Bhopal, Darjeeling, Dibrugarh, Gorakhpur, Goa, Jalandhar, Jalna, Mangalore, Ranchi, Shillong, Srinagar, Trivandrum, Visakhapatnam	January, April, July & October

Annexure-II

Call-sign Prefixes of Amateur Radio Stations of different countries allotted by the International Telecommunication Union (ITU)

Prefix	**Country**	**CQ Zone**
1AO	Sovereign Military Order of Malta	15
1S	Spratly Is.	36
1X	Chechnya (erstwhile USSR)	
2A-2Z	United Kingdom	14
3A	Monaco	14
3B6,7	Agalega & St. Brandon	39
3B8	Mauritius	39
3B9	Rodriguez Is.	39
3C	Equatorial Guinea	36
3C0	Annobon	36
3D2	Fiji, Conway Reef, Rotuma Is.	32
3DA	Swaziland	38
3DN	Fiji	32
3K3	European Islands between 30 Deg. E long. To 170 Deg. W long	
3V	Tunisia	33
3W, XV	Vietnam	26
3X	Guinea	35
3Y	Bouvet	38
3Y	Peter Is.	12
3Z	Poland	15
4F	Philippines	27
4JA-4JZ, 4KA-4KZ	Azerbaidjan	21
4J1, R1MV	Malyj Vysotskij Island	16
4K0	Drifting Ice Station (Russian Polar Stations)	
4K1	Antarctica (Russian Polar Stations)	
4K4	Asian Islands between 65 Deg E long. To 170 Deg. W long	
4K2	Franz Josef Land (Russian Polar Stations)	40
4LA-4LZ	Georgia	21
4P-4S	Sri Lanka	22
4U	ITU Geneva	14
4U	United Nations Headquarters	05
4X, 4Z	Isreal	20
5A	Libya	34
5B, P3, H2	Cyprus	20
5H, 5I	Tanzania	37
5N, 5O	Nigeria	35
5R, 5S	Madagascar	39

Prefix	Country	CQ Zone
5T	Mauritania	35
5U	Niger	35
5V	Togo	35
5W	Western Sarnova	32
5X	Uganda	37
5Y, 5Z	Kenya	37
6O	Somalia	37
6V, 6W	Senegal	35
6Y	Jamaica	08
7J-7N	Japan	25
7O	Yemen	21, 37
7P	Lesotho	38
7Q	Malawi	37
7S	Sweden	14
7T-7Y	Algeria	33
7Z	Saudi Arabia	21
8J	Japan	25
8P	Barbados	08
8Q	Maldive Is	22
8R	Guyana	09
8S	Sweden	14
8Z	Saudi Arabia	21
9A	Croatia	15
9G	Ghana	35
9H	Malta	15
9I, 9J	Zambia	36
9K	Kuwait	21
9L	Sierra Leone	35
9M2, 4	West Malaysia	28
9M6, 8	East Malaysia	28
9N	Nepal	22
9O-9T	Zaire	36
9U	Burundi	36
9V	Singapore	28
9X	Rwanda	36
9Y, 9Z	Trinidad and Tobago	09
A2	Botswana	38
A3	Tonga	32
A4	Oman	21
A5	Bhutan	22

Prefix	**Country**	**CQ Zone**
A6	United Arab Emirates	21
A7	Qatar	21
A8	Liberia	35
A9	Bahrain	21
AA-AL	USA	3, 4, 5
AM-AO	Spain	14
AT-AW	India	22
AP-AS	Pakistan	21
BS7	Scarborough Reef	27
BM, BO, BU, BV	Taiwan	24
BA, BD, BG, BT, BY	China	23, 34
C2	Nauru	31
C3	Andorra	14
C5	Gambia	35
C6	Bahamas	08
C8-C9	Mozambique	37
CA-CE	Chile	12
CE0	Easter Island, San Felix and San Ambrosia, Juan Fernandez Island	12
CE9	Antarctica	
CF-CK	Canada	1-5
CM, CO	Cuba	08
CN	Morocco	33
CP	Bolivia	10
CT	Portugal	14
CT3	Madeira Is.	14
CU	Azores	33
CV-CX	Uruguay	13
CY9	St. Paul Island	05
CY0	Sable Island	05
D2-3	Angola	36
D4	Cape Verde	35
D5	Liberia	35
D6	Comoros	39
DA-DM	Germany	14
DU-DZ	Philippines	27
E2	Thailand	26
E3	Eritrea	37
E4	Palestine	
EA-EH	Spain	14
EA6-EH6	Balearic Is.	14

Prefix	Country	CQ Zone
EA8-EH8	Canary Is.	33
EA9-EH9	Ceuta and Melilla	33
EI-EJ	Ireland	14
EK	Armenia	21
EL	Liberia	35
EP-EQ	Iran	21
ER	Maldova	16
ES	Estonia	15
ET	Ethiopia	37
EU, EV, EW	Byelorussia	16
EX	Kyrgyzstan	17
EY	Tajikistan	17
EZ	Turkmenistan	17
F, TM, TO-TQ	France	14
FG	Guadeloupe	08
FH	Mayotte	39
FJ, FS	Saint Martin	08
FK	New Caledonia	32
FM	Martinique	08
FO	Clipperton Is.	07
FO	French Polynesia	32
FP	St. Pierre & Miquelon Is.	05
FR, FG	Glorioso Is.	39
FR, FJ, FE	Juan de Nova (Europe)	39
FR, FT	Tromelin Is.	39
FR	Reunion Is.	39
FT8W	Crozet Is.	39
FT8X	Kerguelen Is.	39
FT8Z	Amsterdam & St. Paul Is.	39
FW	Wallis & Futuna Is.	32
FY	French Guiana	09
G, GX	England	14
GD, GT, MD	Isle of Man	14
GH, GJ	Jersey	14
GI, GN	Northern Ireland (UK)	14
GM, GS	Scotland (UK)	14
GU, GP	Guernsey	14
GW, GC	Wale (UK)	14
H4	Solomon Is.	28
HA, HG	Hungary	15

Prefix	**Country**	**CQ Zone**
HB	Switzerland	14
HB0	Liechtenstein	14
HC, HD	Equador	10
HC8, HD8	Galapagos Is.	10
HH	Haiti	08
HI	Dominican Republic	08
HJ, HK	Colombia	09
HK0	Malpelo Is	09
HK0	San Andres & Providencia	07
HL, DS, DT	South Korea	25
HO, HP, 3E, 3F	Panama	07
HQ, HR	Honduras	07
HS	Thailand	26
HV	Vetican	15
HZ	Saudi Arabia	21
IA-IZ	Italy	15, 33
IS0, IM0	Sardinia	15
J2	Djibouti	37
J3	Grenada	08
J4	Greece	20
J5	Guinea-Bissau	35
J6	St. Lucia	08
J7	Dominica	08
J8	St. Vincent & Grenadlines	08
JA-JS	Japan	25
JD1	Minami-Tori-Shima	27
JD1	Ogasawara Is.	27
JT-JV	Mongolia	23
JW	Svalbard Is.	40
JX	Jan Mayen Is.	40
JY	Jordan	20
K, W, NA-NZ, AA-AK	United States of America	3, 4, 5
KC6	Belau (Western Caroline Is.)	27
KG4	Guatanamo Bay	08
KH0	Manana Is.	27
KH1	Baker & Howland Is.	31
KH2	Guam	27
KH3	Johnston Is.	31
KH4	Midway Is.	31
KH5	Palmyra Jarvis Is.	31

Prefix	**Country**	**CQ Zone**
KH5K	Kingman Reef	31
KH6	Hawaii	31
KH7	Kure Is.	31
KH8	American Samao	32
KH9	Wake Is.	31
KL7	Alaska	1
KP1	Navassa Is.	08
KP2	Virgin Is.	08
KP3, KP4, WP	Puerto Rico	08
KP5	Desecheo Is.	08
LA-LN	Norway	14
LO-LW, AY, AZ	Argentina	13
LX	Luxembourg	14
LY	Lithuania	15
LZ	Bulgaria	20
M1, M0	United Kingdom	14
OA-OC	Peru	10
OD	Lebanon	20
OE	Austria	15
OF-OI	Finland	15
OH0	Aland Is.	15
OJ0	Market Reef	15
OK, OL	Czeck Republic	15
OM	Slovak Republic	15
ON-OT	Belgium	14
OX	Greenland	40
OY	Faroes	14
OZ	Denmark	14
P2	Papua New Guinea	28
P4	Aruba	09
P5	North Korea	25
PA-PI	Netherlands	14
PJ2, 4, 9	Bonaire, Curacao (Neth Antilles)	09
PJ5-8	St. Maarten, Saba & St. Eustatius Is.	08
PP-PY	Brazil	11
PP0-PY0	Fernando de Noronha, St. Peters & St. Paul Rocks, Trinidad & Martin Vaz	11
PZ	Surinam	09
S0	Western Sahara	33
S2	Bangladesh	22
S4	South Africa	38

Prefix	Country	CQ Zone
S5	Slovenia	15
S7	Seychelles	39
S9	Sao Tome & Principe	36
SA-SM	Sweden	14
SN-SR	Poland	15
ST	Sudan	34
ST0	Southern Sudan	34
SU	Egypt	34
SV-SZ	Greece	20
SV/A	Mount Athos	20
SV5	Dodecanese	20
SV9	Crete	20
T2	Tuvalu	31
T30	W. Kiribati (Gilbert Is.)	31
T31	Central Kiribati (British Phoenix Is.)	31
T32	East Kiribati (Line Is)	31
T33	Banaba Is. (Ocean Is.)	31
T5	Somalia	37
T7	San Marino	15
T9, 4N4, 4O4	Bosnia-Herzegovina	15
TA-TC	Turkey	20
TF	Iceland	40
TG, TD	Guatemala	07
TI, TE	Costa Rica	07
T19	Cocos Is	07
TJ	Cameroon	36
TK	Corsica	15
TL	Central Africa	36
TN	Congo	36
TR	Gabon	36
TT	Chad	36
TU	Ivory Coast	35
TY	Benin	35
TZ	Mali	35
UA-UI1, 3, 6, RA-RZ	European Russia	16
UA2	Kaliningrad	15
UA-UI8, 9, 0 RA-RZ	Asiatic Russia	
UJ-UM	Uzbekistan	17
UN-UQ	Kazakhstan	17
UR-UZ, EM-EO	Ukraine	16

Prefix	Country	CQ Zone
V2	Antigua Barbuda	08
V3	Belize	07
V4	St. Kitts & Nevis	08
V5	Namibia	38
V6	Micronesia (East Caroline Is.)	27
V7	Marshall Is.	31
V8	Brunei	28
VA, VE, VF, VO, VY	Canada	1-5
VK, VI, AX	Australia	29, 30
VK0	Heard Is.	39
VK0	Macquarie Is.	30
VK9C	Cocos-Keeling Is.	29
VK9L	Lord Howe Is.	30
VK9M	Mellish Reef	30
VK9N	Norfolk Is.	32
VK9W	Willis Is.	30
VK9X	Christmas Is.	29
VP2E	Anguilla	08
VP2M	Montserrat	08
VP2V	British Virgin Is.	08
VP5	Turks & Caicos Is.	08
VP8	Falkland Is.	13
VP8, LU	South Georgia Is. South Orkney Is., South Sandwich Is.	13
VP8, CE9, HF0, LU, RA1	South Shetland Is.	13
VP9	Bermuda Is.	05
VQ9	Chagos Is.	39
VR6	Pitcairn Is.	32
VS6, VR2	Hong Kong	24
VU2, VU3	India	22
VU7	Andaman & Nicobar Is. (India)	26
VU4	Laccadive Is. (India)	22
XA-XI, 4A-4C	Mexico	06
XA4-X14	Revilla Gigedo	06
XJ	Canada	1-5
XT	Burkina Faso	35
XU	Cambodia	26
XW	Laos	26
XX9	Macao	24
XY-XZ	Myanmar	26
YA, T6	Afghanistan	21

Prefix	**Country**	**CQ Zone**
YB-YH	Indonesia	28
YI	Iraq	21
YJ	Vanuatu	32
YK	Syria	20
YL	Latvia	15
YN	Nicaragua	07
YT, YU, YZ, 4N	Yugoslavia	15
YV-YY, 4M	Venezuela	09
YV0	Ares Is.	08
Z2	Zimbabwe	38
Z3, 4N5	Macedonia	15
ZA	Albania	15
ZB2	Gibraltar	14
ZC4	Cyprus (United Kingdom Sovereign Bases)	20
ZD7	St. Helena	36
ZD8	Ascension Is.	36
ZD9	Tristan de Cunha & Gough Is.	38
ZF	Cayman Is.	08
ZK1	North & South Cook Is.	32
ZK2	Niue	32
ZK3	Tokelau Is.	31
ZL, ZM	New Zealand	32
ZL7	Chatham Is.	32
ZL8	Kermadec Is.	32
ZL9	Auckland & Campbell Is.	32
ZP	Paraguay	11
ZR-ZU	Republic of South Africa	38
ZS0, 1	Penguin Is.	38
ZS8	Prince Edward & Marion Is.	38

List of Call-sign Blocks allotted by ITU

Prefix	**Country**	**Prefix**	**Country**	**Prefix**	**Country**
AAA-ALZ	USA	AMA-AOZ	SPAIN	APA-ASZ	PAKISTAN
ATA-AWZ	INDIA	AXA-AXZ	AUSTRALIA	AYA-AZZ	ARGENTINE
A2A-A2Z	BOTSWANA	A3A-A3Z	TONGA	A4A-A4Z	OMAN
A5A-A5Z	BHUTAN	A6A-A6Z	U.A.E.	A7A-A7Z	QATAR
A8A-A8Z	LIBERIA	A9A-A9Z	BAHRAIN	BAA-BZZ	CHINA
CAA-CEZ	CHILE	CFA-CKZ	CANADA	CLA-CMZ	CUBA
CNA-CNZ	MOROCCO	COA-COZ	CUBA	CPA-CPZ	BOLIVIA
CQA-CUZ	PORTUGAL	CVA-CXZ	URUGUAY	CYA-CZZ	CANADA
C2A-C2Z	NAURU	C3A-C3Z	ANDORRA	C4A-C4Z	CYPRUS
C5A-C5Z	GAMBIA	C6A-C6Z	BAHAMAS	C7A-C7Z	World Meteorological Organisation
C8A-C9Z	MOZAMBIQUE	DAA-DRZ	GERMANY	DSA-DTZ	SOUTH KOREA

Prefix	**Country**	**Prefix**	**Country**	**Prefix**	**Country**
DUA-DZZ	PHILIPPINES	D2A-D3Z	ANGOLA	D4A-D4Z	CAPE VERDE
D5A-D5Z	LIBERIA	D6A-D6Z	COMOROS	D7A-D7Z	SOUTH KOREA
D7A-D9Z	SOUTH KOREA	EAA-EHZ	SPAIN	EIA-EJZ	IRELAND
EKA-EKZ	ARMENIA	ELA-ELZ	LIBERIA	EMA-EOZ	UKRAINE
EPA-EQZ	IRAN	ERA-ERZ	MOLDOVA	ESA-ESZ	ESTONIA
ETA-ETZ	ETHIOPIA	EUA-EWZ	BELARUS	EXA-EXZ	KYRGYZ
EYA-EYZ	TAJIKISTAN	EZA-EZZ	TURKMENISTAN	E2A-E2Z	THAILAND
E3A-E3Z	ERITREA	E4A-E9Z	UNALLOTTED	HAA-HAZ	HUNGARY
HBA-HBZ	SWITZERLAND	HCA-HDZ	ECUADOR	HEA-HEZ	SWITZERLAND
HFA-HFZ	POLAND	HGA-HGZ	HUNGARY	HHA-HHZ	HAITI
HIA-HIZ	DOMINIC REP.	HJA-HKZ	COLOMBIA	HLA-HLZ	SOUTH KOREA
HMA-HMZ	NORTH KOREA	HNA-HNZ	IRAQ	HOA-HPZ	PANAMA
HQA-HRZ	HONDURAS	HAS-HSZ	THAILAND	HTA-HTZ	NICARAGUA
HUA-HUZ	EL SALVADOR	HVA-HVZ	VETICAN	HWA-HYZ	FRANCE
HZA-HZZ	SAUDI ARABIA	H2A-H2Z	CYPRUS	H3A-H3Z	PANAMA
H4A-H4Z	SOLOMON IS.	H5A-H5Z	UNALLOTTED	H6A-H7Z	NICARAGUA
H8A-H9Z	PANAMA	IAA-IZZ	ITALY	JAA-JSZ	JAPAN
JTA-JVZ	MONGOLIA	JWA-JXZ	NORWAY	JYA-JYZ	JORDAN
JZA-JZZ	INDONESIA	J2A-J2Z	DJIBOUTI	J3A-J3Z	GRENADA
J4A-J4Z	GREECE	J5A-J5Z	GUINEABISSAU	J6A-J6Z	ST. LUCIA
J7A-J7Z	DOMINICA	J8A-J8Z	ST.VINCENT/GRENADINES	J9A-J9Z	UNALLOTTED
KAA-KZZ	U.S.A.	LAA-LNZ	NORWAY	LOA-LWZ	ARGENTINA
LXA-LXZ	LUXEMBOURG	LYA-LYZ	LITHUANIA	LZA-LZZ	BULGARIA
L2A-L9Z	ARGENTINA	MAA-MZZ	UNITED KINGDOM	NAA-NZZ	U.S.A.
OAA-OCZ	PERU	ODA-ODZ	LEBANON	OEA-OEZ	AUSTRIA
OFA-OJZ	FINLAND	OKA-OLZ	CZECH REPUBLIC	OMA-OMZ	SLOVAK REPUBLIC
ONA-OTZ	BELGIUM	OUA-OZZ	DENMARK	PAA-PIZ	NETHERLANDS
PJA-PJZ	NETHERLAND ANTILLES	PKA-POZ	INDONESIA	PPA-PYZ	BRAZIL
PZA-PZZ	SURINAME	P2A-P2Z	PAPUA/NEW GUINEA	P3A-P3Z	CYPRUS
P4A-P4Z	ARUBA	P5A-P9Z	NORTH KOREA	RAA-RZZ	RUSSIAN FEDERATIONS
SAA-SMZ	SWEDEN	SNA-SRZ	POLAND	SSA-SSM	EGYPT
SSN-STZ	SUDAN	SUA-SUZ	EGYPT	SVA-SZZ	GREECE
S2A-S3Z	BANGLADESH	S4A-S4Z	UNALLOTTED	S5A-S5Z	SLOVENIA
S6A-S6Z	SINGAPORE	S7A-S7Z	SEYCHELLES	S8A-S8Z	SOUTH AFRICA
S9A-S9Z	SAO TOME & PRINCIPE	TAA-TCZ	TURKEYALA	TDA-TDZ	GUATEMALA
TEA-TEZ	COSTA RICA	TFA-TFZ	ICELAND	TGA-TGZ	GUATEMALA
THA-THZ	FRANCE	TIA-TIZ	COSTA RICA	TJA-TJZ	CAMEROON
TKA-TKZ	FRANCE	TLA-TLZ	CENTRAL AFRICAN REPUBLIC	TMA-TMZ	FRANCE
TNA-TNZ	CONGO	TOA-TQZ	FRANCE	TRA-TRZ	GABON
TSA-TSZ	TUNISIA	TTA-TTZ	CHAD	TUA-TUZ	IVORY COAST
TVA-TXZ	FRANCE	TYA-TYZ	BENIN	TZA-TZZ	MALI
T2A-T2Z	TUVALU	T3A-T3Z	KIRIBATI	T4A-T4Z	CUBA

Prefix	Country	Prefix	Country	Prefix	Country
T5A-T5Z	SOMALIA	T6A-T6Z	AFGANISTAN	T7A-T7Z	SAN MARINO
T8A-T8Z	PALAU REP.	T9A-T9Z	BOSNIA & HERZEGOVINA	UAA-UIZ	RUSSIAN FED.
UJA-UMZ	UZBEKISTAN	UNA-UQZ	KAZAKSTAN	URA-UZZ	UKRAINE
VAA-VGZ	CANADA	VHA-VNZ	AUSTRALIA	VOA-VOZ	CANADA
VPA-VQZ	U.K.	VRA-VRZ	HONGKONG	VSA-VSZ	U.K.
VTA-VWZ	INDIA	VXA-VYZ	CANADA	VZA-VZZ	AUSTRALIA
V2A-V2Z	ANTIGUA	V3A-V3Z	BELIZE	V4A-V4Z	ST. KITTS & NEVIS
V5A-V5Z	NAMIBIA	V6A-V6Z	MICRONESIA	V7A-V7Z	MARSHALL IS.
V8A-V8Z	BRUNEI	V9A-V9Z	UNALLOTTED	WAA-WZZ	U.S.A.
XAA-XIZ	MEXICO	XJA-XOZ	CANADA	XPA-XP7	DENMARK
XQA-XRZ	CHILE	XSA-XSZ	CHINA	XTA-XTZ	BURKINAFASO
XUA-XUZ	CAMBODIA	XVA-XVZ	VIETNAM	XWA-XWZ	LAO
XXA-XXZ	PORTUGAL	XYA-XZZ	MYANMAR	YAA-YAZ	AFGANISTAN
YBA-YHZ	INDONASIA	YOKA-YIZ	IRAQ	YJA-YJZ	VANUATU
YKA-YKZ	SYRIA	YLA-YLZ	LATVIA	YMA-YMZ	TURKEY
YNR-YNZ	NICARAGUA	YOA-YRZ	ROMANIA	YSA-YSZ	EL SALVADOR
YTA-YUZ	YUGOSLAVIA	YVA-YYZ	VENEZUELA	YZA-YZZ	YUGOSLAVIA
Y2A-Y9Z	GERMANY	ZAA-ZAZ	ALBANIA	ZBA-ZJZ	U.K.
ZKA-ZMZ	NEW ZEALAND	ZNA-ZOZ	U.K.	ZPA-ZPZ	PARAGUAY
ZQA-ZQZ	U.K.	ZRA-ZUZ	SOUTH AFRICA	ZVA-ZZZ	BRAZIL
Z2A-Z2Z	ZIMBABWE	23A-23Z	MACEDONIA	Z4A-Z9Z	UNALLOTTED
2AA-2ZZ	U.K.	3AA-3AZ	MONACO	3BA-3BZ	MAURITIUS
3CA-3CZ	EQUATORIAL GUINEA	3DA-3DM	SWAZILAND	3DN-3DZ	FIJI
3EA-3FZ	PANAMA	3GA-3GZ	CHILE	3HA-3UZ	CHINA
3VA-3VZ	TUNISIA	3WA-3WZ	VIETNAM	3XA-3XZ	GUINEA
3YA-3YZ	NORWAY	3ZA-3ZZ	POLAND	4AA-4CZ	MEXICO
4DA-4IZ	PHILIPPINES	4JA-4KZ	AZERBAIJAN	4LA-4LZ	GEORGIA
4MA-4MZ	VENEZUELA	4NA-4OZ	YUGOSLAVIA	4PA-4SZ	SRILANKA
4TA-4TZ	PERU	4UA-4UZ	UNITED NATIONS	4VA-4VZ	HAITI
4WA-4WZ	UNALLOTTED	4XA-4XZ	ISREAL	4YA-4ZZ	UNALLOTTED
5AA-5AZ	LIBYA	5BA-5BZ	CYPRUS	5CA-5GZ	MOROCCO
5HA-5IZ	TANZANIA	5JA-5KZ	COLOMBIA	5LA-5MZ	LIBERIA
5NA-5OZ	NIGERIA	5PA-5QZ	DENMARK	5RA-5SZ	MADAGASCAR
5TA-5TZ	MAURITANIA	5UA-5UZ	NIGER	5VA-5VZ	TOGOLESE REPUBLIC
5WA-5WZ	WEST SAMOA	5XA-5XZ	UGANDA	5YA-5ZZ	KENYA
6AA-6BZ	EGYPT	6CA-6CZ	SYRIA	6DA-6JZ	MEXICO
6KA-6NZ	S. KOREA	60A-6OZ	SOMALI	6PA-6SZ	PAKISTAN
6TA-6UZ	SUDAN	6VA-6WZ	SENEGAL	6XA-6XZ	MADAGASCAR
6YA-6YZ	JAMAICA	6ZA-6ZZ	LIBERIA	7AA-7IZ	INDONESIA
7JA-7NZ	JAPAN	7OA-7OZ	YEMEN	7PA-7PZ	LESOTHO
7QA-7QZ	MALAWI	7RA-7RZ	ALGERIA	7SA-7SZ	SWEDEN
7TA-7YZ	ALGERIA	7ZA-7ZZ	SAUDI ARABIA	8AA-8IZ	INDONESIA
8JA-8NZ	JAPAN	8OA-8OZ	BOTSWANA	8PA-8PZ	BARBADOS
8QA-8QZ	MALDIVES	8RA-8RZ	GUYANA	8SA-8SZ	SWEDEN
8TA-8YZ	INDIA	8ZA-8ZZ	SAUDI ARABIA	9AA-9AZ	CROATIA
9BA-9DZ	IRAN	9EA-9FZ	ETHIOPIA	9GA-9GZ	GHANA

Prefix	Country	Prefix	Country	Prefix	Country
9HA-9HZ	MALTA	9IA-9JZ	ZAMBIA	9KA-9KZ	KUWAIT
9LA-9LZ	SIERALEONE	9MA-9MZ	MALAYSIA	9NA-9NZ	NEPAL
9OA-9TZ	CONGO	9UA-9UZ	BURUNDI	9VA-9VZ	SINGAPORE
9WA-9WZ	MALAYSIA	9XA-9XZ	RWANDA	9VA-9ZZ	TRINIDAD & TOBA

Annexure-III

A Sample Question Paper for Amateur Radio Licencing Examination

SECTION-A

Radio Theory and Practice

1. What is Ohm's law? A resistor has the following colour bands: RED, RED, ORANGE & GOLD respectively. What is the value of this resistor?
2. State whether 'TRUE' or 'FALSE' and correct the 'FALSE' statements:
   - (a) When two resistors are connected in parallel, their resistance increases.
   - (b) A capacitor allows DC current to pass through it.
   - (c) When two capacitors are connected in parallel, their capacitance decreases.
   - (d) In a P-N junction diode, flow of current is possible only when the negative pole of the battery is connected to the p-type semiconductor and positive pole to n-type semiconductor.
   - (e) Centre tapped transformer secondary is not essential for a bridge rectifier circuit
   - (f) In a transistor amplifier circuit, the 'emitter' is always reverse biased and 'collector is always forward biased.
   - (g) In a PNP transistor, the 'collector' is applied with a negative voltage.
   - (h) SWR value is more than one for a matched system.
   - (i) A fourth band in a resistor is silver coloured. The tolerance of this resistor is 10%.
   - (j) Two capacitors with the values 5 mFd & 10 mFd are connected in parallel. The 5 mFd capacitor has a voltage rating of 10 volts and the 10 mFd capacitor has a voltage rating of 6 volts. We can apply 9 volts to this circuit without damaging the 10 mFd capacitor.
3. Draw the schematic diagram of the transmitter you intend to build for ham radio operation and explain the function of each stage in brief.
4. Explain the working function of the antenna you intend to use for ham radio transmissions.
5. Draw the block diagram of a super-heterodyne receiver. Explain the advantages of this type of receiver over the TRF receivers.
6. Write short notes on:

(a) Image frequency in a super-heterodyne receiver.
(b) Ionosphere.
(c) Single Side Band transmission.
(d) Percentage of modulation.
(e) Selectivity & sensitivity of receiver.
(f) Colpitts oscillator.
(g) Skip distance.
(h) Differences between 'fadeout' and 'fading'.
(i) A.G.C.
(j) B.F.O.

7. Describe briefly the following terms:

(a) Line of sight propagation
(b) Ionospheric propagation
(c) Ground wave propagation

SECTION-B

Rules & Regulations

1. What is a distress message? What action would you take if you receive a distress message?

2. Explain the meaning of the following:

   QRX 10 minutes, QSY 14.155 MHz, QRU?, QRV, QRL, KN, VA, AS, QSB, QRS.

3. Describe the procedure of establishing a contact with another amateur station using radiotelephony and radiotelegraphy.

4. What do you mean by 'Amateur Radio Satellite Service'?

5. State whether 'TRUE' or 'FALSE'. Correct the 'FALSE' statements.

   (a) In India, a Grade-I licence holder is allowed to use 400 watts of power in certain sub-bands.

   (b) In India, ham radio operators are allowed to use the frequency band 7000 kHz to 7300 kHz.

   (c) In India, an amateur radio operator can handle third party messages.

   (d) Amateur radio operators are allowed to use secret language for communication.

   (e) UV2ABC is an Indian call-sign.

   (f) An amateur radio station can not be operated by an unlicensed operator except in the presence of a licence holder.

   (g) An amateur radio operator is allowed to communicate with the administration during natural calamities.

   (h) QSP is a message passed by an amateur radio operator to a non-amateur operator.

(i) Before making a call, it is necessary to ensure that the frequency is not in use. If "TRUE', give reasons.

6. What are the amateur radio bands of frequencies below 30 MHz? What is the restriction for Grade-II licensees to use radiotelephony in these bands?
7. Is it permissible to use frequency modulated signals in H.F. bands? Give reasons for your answer.

Annexure-IV

Nomenclature of the Frequency and Wavelength Bands used in Radio Communication

As per the International Radio Regulations, the radio spectrum is subdivided into nine frequency bands, which are designated by progressive whole numbers in accordance with the following table. As the unit of frequency is the hertz (Hz , frequencies shall be expressed:

- in Kilohertz kHz, upto and including 3000 kHz;
- in megahertz MHz , above MHz, up to and including 3000 MHz;
- in gigahertz GHz, above 3 GHz, up to and including 3000 GHz.

For bands above 3000 GHz, i.e. centimillimetric waves, micrometric waves and decimicrometric waves, it would be appropriate to use terahertz THz.

However, where adherence to these provisions would introduce serious difficulties, for example in connection with the notification and registration of frequencies, the lists of frequencies and related matters, reasonable departures may be made.

Band Number	Symbols	Frequency Range lower limit exclusive, upper limit inclusive	Corresponding Metric Subdivision
4	VLF	3 to 30 kHz	Myriametric waves
5	LF	30 to 300 kHz	Kilometric waves
6	MF	300 to 3000 kHz	Hectometric waves
7	HF	3 to 30 MHz	Decametric waves
8	VHF	30 to 300 MHz	Metric waves
9	UHF	300 to 3000 MHz	Decimetric waves
10	SHF	3 to 30 GHz	Centimetric waves
11	EHF	30 to 300 GHz	Millimetric waves
12		300 to 3000 GHz	Decimillimetric waves

Note 1:
"Band Number N" extends from 0.3×10^N to 3×10^N Hz, e.g., Band No. 7 is the HF (High Frequency) band ranging from 0.3×10^7 to 3×10^7 Hz, i.e. 3000000 Hz (3 MHz) to 30000000 Hz (30 MHz)

Note 2:
Symbols and prefixes: Hz=hertz, k=kilo 10^3, M=mega 10^6, G=giga 10^9, T=tetra 10^{12}

<

Maximize client uptime. Level up your business.
Try SolarWinds® Backup LocalSpeedVault for the fastest possible data recovery.
solarwinds msp
START YOUR FREE TRIAL!

Maximize client uptime. Level up your business.
Try SolarWinds® Backup LocalSpeedVault for the fastest possible data recovery.
solarwinds msp
START YOUR FREE TRIAL!



Figure 8-1. Perrigo Etheric Wave Transformer

METHOD AND APPARRATUS FOR ACCUMULATING ELECTRIC ENERGY AND TRANSFORMING ETHER ELECTRIC ENERGY

Drawings by Geoff Egel ,Content Author unknown

In 1926. Harry E. Perrico claimed to have discovered a method to tap the energy from atmospherics. He even had a car which he converted to run on electricity. that was generated in his ether wave accumulator".

He applied for a patent December 31 1925 with serial number 78,715 being assigned. Perrigo's patent application Is considered a "classic" In patent law and Is listed under the classification of Perpetual Motion Machines and other Impossible Inventions.

Despite the Patent Office's attitude towards Perrico's invention, there were a number of reputable people who claimed to have witnessed his device In action producing useable electric power.

The existence of electromagnetic radiation, the modem term, or electric waves In the ether as it used to be called was known by Hertz, a research scientist who discovered the photoelectric effect

In 1887. Atmosphierics, an electrical disturbance in the atmosphere, were known to produce noises In the early radio telegraph stations, some being strong enough to drown out the received signal.


Side on view of Coil Sandwich
Side on view of three ayers toget ıer
Top View
Side View
details of Coils for Sandwich

> Perrigo deduced that here was a possible source of electrical power.

All that was needed was a method of transforming the existing radiation Into useable energy. Hie claimed to have developed a mechanism to intercept and collect from the general ether field electric wave energy and to transform it into useable electromotive force.

The basic method he used was an antenna arrangement which collected and resisted the Incoming energy raising It to a high enough current level where it could be run through a special electrical transformer to further intensify the available power.


top view
+
91
81
71
61
51
41
31
30
29
28
27
26
25
24
23
22
21
20
19
18
17
16
15
14
13
12
11
10
9
8
7
6
5
4
3
2
1
side view
wiring detaail of Perrigo Invention Top Antenna

Perrigo's antenna was derived from his experiments with various wire shapes, sizes and arrangements. One of his more successful attempts was to partially pound 100 roofing nails into a board a 10 x 10 array and wrap very fine wire around each nail,making it a small electromagnet.

Then by trial and error approach he connected the ends of the electromagnets to other nails in such a way that there was a maximum voltage between the wire and the nail.. His patent application mirrored this electrical connection scheme in a more refined electromechanical approach.

Two accumulator plates were made with 100 round protruding knobs in a square 10 X 10 array



igure 6-3 wiring detail of Perrigo Invention Bottom Antenna

The accumulator plates were then sandwiched together with an insulator material between them. The insulator had 100 holes matching the protrusions on the plates. Placed in each hole was a special coil wrapped around a bundle of wire . Once the accumulator plates were sandwiched ,a measureable electrical voltage existed between points A and B on plates one and two respectively.



A very complicated transformer was attached to these two points.

The plates were set on top of the transformer and Perrigo claimed this arrangement enhanced the energy accumulation process.

I have no idea of what materials the plate or protrusions were made The patent drawing would lead one to believe they are the same material.

It could be a metal or a nonconductor. such as wood or a combimation. The protrusions were connected by the same wiring scheme

Previously mentioned for the roofing nail model. The connections were different for the two plates.

(See diagrams for the plates connections

egel@main.murray.net.au

Geoff Egel 18 Sturt Street, Loxton ,5333, South Australia ,Australia

---

Join the Energy 21 newsgroup and mailing list today

FREEBIES

Latest Additions

---

nexar
FULL HD
Drive Stress-Free
Buy & Get A Full Rebate

Homebrew and Experimenters Group
HF 1:1 (Choke) Balun Kit (2007-02-28)



Here is the kit of parts supplied, although not shown, an “N” type connector is also supplied. While this connector may be more expensive we have found it more reliable and weatherproof than most others. It is worth purchasing the matching plug for your coax lead be it RG58 or RG213.

Parts.
Balun Core and length of RG58 Coax
Weatherproof Box (with “o” ring and screws)
“U” Bracket (stainless steel) with S/S nuts and bolts (to hang the box)
Large Hex S/S Setbolts, washers and nuts (to connect dipole wires to the balun)
Crimp Terminals to terminate the coax leads within the box
Small S/S Setscrews to secure the “N” connector to the box

Extras which may be needed
Small cable ties or electrical tape to secure the coax to the balun core.

Instructions
1. Check that you have all the components
2. Locate and drill holes in the box for the hardware , as indicated in the text the mounting centers should relate to the box as a whole NOT just the back part of the box.

Note. Most constructors also drill a small hole in the bottom edge of the box (adjacent to the “N” connector) to allow the box to breath and any condensation in the box to escape.

3. Mount the “U” Bracket and the “N” connector, on the “N” connector leave one of the front bolts loose so that coax shield can be secured later in construction.
4. Wind the coax onto the balun in a single layer and with turns evenly spaced around the core. Ten turns is standard for the HF bands, but you can add a couple more turns if most of your operation is in the lower frequency bands. The core has actually been tested up to 6m, perhaps

only 8 turns to bias it’s operation in the higher frequency HF bands and 6m. Use electrical tape or small cable ties to secure the coax to the balun.

5. Place wound balun core temporarily into the box and orientate the coax ends so that one end goes to the “N” connector and the other will go to the Dipole Terminals (not fitted yet).
6. Mark and/or cut to length the coax ends, make sure you leave enough length so that :
   a. The “N” connector end is long enough so that when the core and shield are separated, the shield is long enough to reach the loose connector mounting bolt.
   b. The Dipole Terminal end is long enough so that when core and shield are separated the core AND the shield are long enough to reach the terminals in the side of the case.
7. Terminate the coax (remove balun from box as necessary) :
   a. At the “N” connector end remove the unwanted cable sheath (careful so that you don’t nick the core of the shield), trim core to length and strip a short length of insulation off so that it fits into the “N” connector center spigot. Carefully twist the shield wire together to form a single wire, check it’s fit to the connector mounting bolt, trim to length and fit a crimp connector to the shield wire (short ends)
   b. At the Dipole Terminal end of the coax, remove sufficient cable sheath so that the core and the shield are the same length and reach the terminals easily. Strip a short length of insulation from the core and fit a crimp connector to it. Carefully twist the shield wire together to form a single wire, check it’s fit to the terminal bolt, trim to length and fit a crimp connector to the shield wire (long ends).
8. Check electrical continuity of core (one end to the other) and shield (one terminal to the other) and check that there are no shorts between the core and the shield. This can happen where you cut off the coax sheath, if you cut too deep the strands of the shield can find their way down to the centre wire of the core. You definatly don’t want an intermittent connection in your balun when it is hung up in the air.
9. Place the wound balun core back into the box and orient it so that the ends of the coax reach their appropriate terminations.
10. Put one of the Dipole Terminal bolts through one of the terminated long ends, then through it’s hole in the side of the box, then a washer and a spring/star washer, then a nut and tighten with your fingers.
11. Repeat this process for the other long end of the coax to the other side of the box.

Note. It does not matter which terminal the core or shield goes to so long as each terminal has a wire on it.

12. Now go to the short end of the coax and secure the terminated shield to the loose bolt on the “N” connector, again just hand tight for the time being.
13. Now before tightening everything up, we do a continuity check again

    a. Should be ZERO ohms between the center of the “N” connector and the terminated core lead going to one of the Dipole Terminals
    b. Should be ZERO ohms between the “N” connector body and the terminated shield wire going to the other Dipole Terminal.
    c. Should be OPEN CIRCUIT between the center spigot and the body of the “N” connector, also between the two Dipole Terminals.
14. Now tighten all the bolts and terminals up, nice and tight but don’t squash the plastic box and be careful not to “pull” the terminated ends of the coax.
15. Center up the balun core in the bottom section of the box and secure it with a few blobs of hot glue or Selastic ™ , when it has cooled/dried fit the “O” ring in the groove and fit the lid with it’s screws.


Cable to hang balun in the air
Blobs of hot glue or Selastic ™

Balun Choke Kit (some dimensions are exaggerated for clarity)
"N" connector has four bolts, two only shown in drawing



Above is a diagramic view of the kit when assembled and also a picture of a completed unit.

Using the Balun

Into an existing dipole antenna:

Simply drop the center of the antenna, remove the center insulator and terminate the dipole ends to the baluns Dipole Terminals. Terminate a length of coax (RG58 or RG213) with an “N” plug and fit it to the balun “N” connector. Using some heavy tape, plastic rope or a couple of cable ties around the box, secure the dipole wires to the box, this takes the strain off the Dipole Terminals. Raise the antenna again, terminate the other end of the coax and check the antennas operation (see tuning the antenna in the following section).

A new dipole antenna:

Basically an antenna should be as high in the air as you can practically get it. For a dipole you will need at least one high point to haul the balun box up to. The ends of the dipole sections should be just as high if you can. The box and the dipole ends should of course be spaced away from and insulated from any structure or pole/tree. Sorry the subject of designing an antenna and it’s placement is well beyond these simple instructions, do the best you can with the space and structures available. There is plenty of information in books, manuals and on the WEB.

Tuning the antenna:

For the band you wish to use determine the length of each section of the dipole and add a bit more length, say 5% or 10% more. Most use what is generally called insulated “building wire”, this is usually strong enough for at least an 80m dipole. Terminate and secure the dipole sections to the balun Dipole Terminals. Terminate a length of coax (RG58 or RG213) with an “N” plug and fit it to the balun “N” connector. Using some heavy tape, plastic rope or a couple of cable ties around the box, secure the dipole wires to the box, this takes the strain off the Dipole Terminals. Raise the antenna, terminate the other end of the coax and check the antennas operation (see tuning the antenna in the following section). Then using either an Antenna Bridge or a Transmitter (on low power) and a SWR meter check the operation of the antenna. You will most likely find it is too long, simply drop the ends and chop off a small section of each end (same length both ends), raise the ends again and test the antenna. Keep doing this and chopping off shorter and shorter lengths until the antenna is the correct length. If it is a permanent installation perhaps leave it a bit long and come back a few days later when the wire has settled in (stretched) and re-check it’s operation, adjusting if necessary. Don’t worry about the loose ends, just leave them hang there, so long as they are well up in the air.

Happy Homebrewing, please contact us if you have any problems.

M0UKD

MFJ-971 Portable Antenna Tuner Modifications

Ads by Google Mods Guitar Tuner Tuner Tuner Antenna

The MFJ-971 has the potential to be a great portable tuner. It is a small, compact tuner that has a sensitive SWR circuit allowing precise tuning with low power thanks to its 6w FSD setting and it has outputs for coax, wire and balanced feeder (although I won't talk about the MFJ 'heavy duty' 1:4 voltage baluns here!). To make it the almost perfect portable / QRP tuner, there were a couple of things that needed to be solved...

MFJ PORTABLE TUNER
TRANSMITTER
ANTENNA
INDUCTANCE
WATTS
FORWARD
REFLECTED
SWR
MFJ
MODEL MFJ-971

ANTENNA
TRANSMITTER
BALANCED LINE
JUMPER WIRE
INSTALL WHEN USING BALANCED LINE
MFJ ENTERPRISES, INC.
STARKVILLE, MS USA
METER LAMP
12VDC
A B
30 30
6 300

The problems I had with this tuner are:

1) No bypass switch

2) Not enough inductance to tune on 1.8MHz

The first thing that I would want in any tuner, is a bypass switch. Its nice to flick a switch and be able to receive on all bands and the lack of a bypass switch is frustrating. This was easily added by mounting a DPDT switch to the front panel, and connecting it appropriately, as seen in the pictures below.

Full SiC Modules ROHM
Constructed by Original SiC-MOS/SBD
Suited for replacemet of IGBT
www.rohm.com

Coil Bobbins
Inch and Metric coil bobbins 5000+
standard range available
www.milesplatts.co.uk

Isolators and Circulators
300MHz to 20GHz: Coax, Drop-in & WG
Fast Delivery, Manufactured in UK.
www.mcsmicrowave.co.uk



Usually, the signal comes off the PCB and straight into the 'transmitter' capacitor and the output of the 'antenna' capacitor goes to the coax/wire connection on the rear. The switch has been added to provide a way to bypass the tuner section. A drawing of the DPDT switch wiring is below.



OK, now that annoyance is out of the way, lets fix the top band issue. MFJ say *'The [MFJ-971] T-match tuner covers*

1.8-30 MHz'. It may well do, if you want to match a perfect 50Ω load on 1.8MHz! The inductor inside this tuner, although adequate for 80-10m, does not have enough inductance to be useful on 160m.

To overcome this problem, I included extra inductance by winding 29 turns of enamelled copper wire (any suitable insulated wire will do) on a T130-2 iron powder toroid, so when the tuner is on the 'L' inductance setting, the whole original inductor is used *plus* the extra inductance provided by the toroid. This does not affect any of the other settings from A-K.



The MFJ-949E inductor has 27 turns, 75mm long and 75mm diameter which is about 37μH.
The MFJ-971 inductor has 17 turns, 43mm long and 66mm diameter which is about 17μH.
Adding on the extra inductance means we have a max inductance of around 27μH which allows matching on 1.8MHz.
Air inductance coils can be calculated **here** and the T130-2 toroid **here**.

High Power Fiber Laser 15W single frequency with low noise 1064 and 1550 nm ranges www.nktphotonics.com/high_power

1553 Box/Flange Couplers Mfr of flight worthy, 1 to 8 stub, 4-hole mount bus couplers. www.databusproducts.com

Coil Winding Specialist Design and Manufacturing of Chokes, Inductors, Transformers, Coils, CTs www.coilws


Rotary switch ground point and 'L' setting
Rotary switch 'K' setting


Rotary switch 'K' setting
Rotary switch ground point and 'L' setting

The inductor switch picks up its ground from the bottom of the inductor and this is also the 'L' setting, meaning the whole coil is in use when 'L' is selected. The 'K' inductance setting is 2 turns up from this point. I cut the wire just after the 'L' tap and inserted the extra inductance. Now, when 'L' is selected, the whole original inductor is in use, plus the extra inductance of the toroid, making it suitable for use on 160m! Of course, the 'K' setting still uses the whole original coil (less 2 turns) so nothing is really lost. The wires cross to keep any magnetic fields circulating the same way between the 2 inductors. The toroid is then fixed with a nut & bolt and suitable insulation washers either side of the toroid.

The completed, modified, much improved MFJ-971 is seen below. Please let me know if you perform any of these modifications, I'd be interested to know what you think.

There is one small problem remaining and that is RF BURNS! The nuts that hold the variable capacitors in place on many MFJ tuners are at RF potential. Most of the time they are hard to come into contact with being tucked away behind the control knobs, however, on the MFJ-971 the knobs must be pulled forward a little otherwise the metal inside the knob comes into contact with the metal shaft causing the grub screws that hold the two control knobs on to be at a high RF voltage. This can give you RF burns whilst you are tuning, even at 5 watts. I hate to imagine what the result would be if you put the 'rated' 200w into this thing and touched a control! One problem with pulling the knobs forward a little is that then the nuts themselves are more visible, although anything is better than an RF burn! 73 de M0UKD.

DANGER
MFJ-971
May give you
RF Burns!



Ads by Google Mods Guitar Tuner Tuner Tuner Antenna

A Coax Switch



Cheap slide switch in a standard 54 × 50 × 26 mm box.

THE SWITCH



Fig » shows a proven inexpensive home-made antenna selection switch. If you question the use of a cheap slide switch and SO239 coax sockets, read on. Measurements in a physics lab showed there to be practically no reflection on HF and even on 70 cm the SWR was below 1.3 : 1! That is explained as follows:

- The contacts in the slide switch have larger contact surfaces than many a bought coaxial switch.
- The wiring and switch contacts, between the top and bottom of the metal case, act as the centre conductor of a coax of near 50 ?.

It is a standard box measuring 54 × 50 × 26 mm (l × w × h) and the wiring between the switch and the coax sockets is done in 2 mm silver plated wire.

POWER HANDLING CAPABILITY

If the switching is done with power off, the switch can stand 800 W. I have used this switch for more than 15 years and even with 1500 W there have been no problems.



While building this switch, you might as well add a test point, e.g. to connect a ‘scope’ or frequency counter. The capacitors of 10 and 220 pF make a capacitive voltage divider and the extra loading, 9.6 pF, does not affect performance on HF. In fact, on 10 m it improves the SWR as the extra capacity, in combination with the wiring it makes a filter which favours that frequency.



This shows how the switch is used in my station.

«Back
AØFRI

DIAMOND X510N MODIFICATION

UPD 14 feb 2013 With the correct drawning of the center element (tnx LW7DNJ).




Lower element X510N.
20mm
590mm
460mm
290mm
4.5 t
10mm id
12mm long
wire 2.5mm dia
8 t
6mm id
40mm long
wire 2.5mm dia
64 t
7.5mm id
240mm long
wire 2.5mm dia
7.5pF
4.5 turns
1cm id
tap 3t
2.5pF
Center element X510N.
70mm
110mm
230mm
380mm
450mm
8 t
6mm id
40mm long
wire 2.5mm dia
2 × 2pF
8 t
6mm id
40mm long
wire 2.5mm dia
64 t
7.5mm id
240mm long
wire 2.5mm dia
Upper element X510N.
70mm
390mm
410mm
490mm
8 t
6mm id
40mm long
wire 2.5mm dia
2 × 2pF
10t
6mm id
40mm long
wire 2mm dia

INTRODUCTION

When visiting a flea market I have been tempted by an offer to purchase a new Diamond X510N 2m/70cm antenna. For the price it was almost impossible to homebrew such a solid antenna. To handle the packaging the antenna is made in three elements.

The radiator (fig ») is mounted in a fibreglass radome, tapered like a fishing pole and finished with white lacquer. The coils are made with copper wire and aerial parts of 3 mm brass rods. To avoid rattling the radiator was (coaxial) fitted with foam plastic sleeves at approximately equal distances. The radiator is easily removed from the fibreglass poles and the sizes of the radiator elements are mentioned in the headline of this article. The total length of the antenna is 5.20 m. The antenna can bend in high winds and that disturbs the vertical polarization. So the transmitting and receiving signal strength is subject to instantaneous differences. In the Netherlands the X510X therefore is called a "calm weather" antenna. On the Internet enough positive information is published about this model, so I will confine only some details.

THE NAKED TRUTH


Lower element X510N.
Center element X510N.
Upper element X510N.
20mm
4.5 t
10mm id
12mm long
wire 2.5mm dia
590mm
8 t
6mm id
40mm long
wire 2.5mm dia
460mm
64 t
7.5mm id
240mm long
wire 2.5mm dia
290mm
230mm
8 t
6mm id
40mm long
wire 2.5mm dia
380mm
110mm
2 × 2pF
8 t
6mm id
40mm long
wire 2.5mm dia
450mm
70mm
64t
7.5mm id
240mm long
wire 2.5mm dia
390mm
8 t
6mm id
40mm long
wire 2.5mm dia
410mm
70mm
2 × 2pF
10t
6mm id
40mm long
wire 2mm dia
490mm



The Bottom of lower element until the 8 turns coil.

MATCHING


7.5pF
4.5 turns
1cm id
tap 3t
2.5pF

The base of the antenna is loaded with a coil of 4.5 turns and 1 cm inner diameter. The input is matched to 50 Ohm with a 7.5 pF - 2.5 pF capacitive voltage divider connected to the third winding of the coil. According to the specifications the maximum power is specified as 200 W. Not clear if that is true for both FM and SSB/CW. On the Internet one can read that no more than 35 to 50 W is recommended, which is understandable if you see the small 500 V/5 mm diameter ceramic capacitors.

Out of curiosity, the antenna was disassembled so it was only a small step to replace the capacitors. Given the limited space between the coil and the metal tube at the bottom, it was not possible to use transmit or kV capacitors. Therefore, I used 50 Ohm Teflon coaxial cable and cut the cable to the correct frequency using a capacitance meter. If you do not have the meter, a better choice is to buy good quality capacitors.


The two caps are replaced with caps made with lenght of coax cable
7.5pF
2.5pF
5mm







Another Teflon tube was slid over de quasi capacitors to reduce the stray capacitance. A preliminary test showed the SWR on the two bands was not more than 1.5, which is in line with the original specification.

The test was repeated on a 1.70 m pole in the backyard. See the corresponding SWR («fig) in the table. Later the antenna was mounted (fig») on the chimney and the SWR stays identical.



Freq.	144	145	146	430	435	440	MHz
SWR	1.4	1.2	1.0	1.35	1.5	1.35	MHz



By loosening the socket-head screw («fig), which is secured with an adhesive, you can remove the inside to the right. It is recommended first heat the screw with for example a soldering iron and then unscrew.

RESONANCE



Coils and capacitors in series (fig») with the internal radiators primarily determine the resonance of the antenna. I have not replaced the small capacitors, because the energy they have to deal is much less than at the base part of the antenna. To be sure the compression fittings/joint couplers in each element were soldered.

WETHER PROTECTION



MOTIP
STOSSTANGENSPRAY · PARE-CHOCS
BUMPERSPRAY

The radome is glued into the Feed Point section, but on the boundary (« see arrow below) of metal and polyester is not covered with paint. My experience with a Cushcraft R5 is that 2 component polyester resin can "evaporate" under the influence of sunlight.

The spot was sprayed with "bumper spray", a black non-metallic spray paint. All my antennas are treated with this product, because after years it proved to be a good protection.

The elements are assembled with joint brackets. For perfect waterproof the joints are covered with self vulcanizing tape and sprayed with silicone spray. The white paint was also protected with the silicone spray.

«Back
A0FR

Radio Direction_Finder RDF Projects Joe WB2HOL

Sourse URL: http://home.att.net/~jleggio/projects/rdf/rdf.htm

Table of Contents

SIMPLE Time-Difference-Of-Arrival RDF....2
555 Time-Difference-Of-Arrival RDF 7
TAPE MEASURE BEAM OPTIMIZED FOR RADIO DIRECTION FINDING....10
RDF2 YAGI WITH TAPE MEASURE ELEMENTS....16
THE FOX - 40 milliwatt transmitter....21
THE FOX - 250mw transmitter with TIMER....25
THE FOX750 - 750 milliwatt transmitter....27
Style of PC board construction....29
SIMPLE ADJUSTABLE PASSIVE ATTENUATOR....32
ACTIVE ATTENUATOR....35
The HANDI-Finder®....37
The HANDI-Finder® Experimenter’s Kit 39
Sense The Right Way To Go With The HANDI-Finder®....52
Frequently Asked Questions and Answers About T-hunting and RDF....56
Hardware Resources for RDF Home Builders....70
RF Sniffer with Tone Output....75
Audible S-Meter....76
The Montreal Audio FS-Meter 77

SIMPLE Time-Difference-Of-Arrival RDF

Joe Leggio WB2HOL

This T.D.O.A. RDF set is built into a die-cast Pomona box. I built it in October, 1989. As you can see from the photo, it has held up to lots of abuse as it gets knocked around in my RDF bag.

How it works

Time Difference of Arrival RDF sets work by switching your receiver between two antennas at a rapid rate. When both antennas are the same distance from the transmitter, the RF phase received by both antennas will be identical. If the two antennas are different distances from the transmitter the RF will have a different phase at each antenna. If we switch between the antennas 500 times a second, this phase change will be detected by an FM receiver as a 500 Hz tone.

By turning the antennas for a null in the tone, your two antennas will be perpendicular to the transmitter. Unfortunately, you can be facing the transmitter or facing away from the transmitter and get a null in the tone. By using a synchronous detector and processing the phase of the tone, it is possible to drive a center scale meter to indicate which direction to turn to face the transmitter.

If you have a null in the tone and turn slightly right, the meter should point to the left and direct you to turn left to face the transmitter. If instead, it points right as you turn right, you need to continue turning right to face the transmitter; you were facing away from it originally. (in other words, you need to turn 180 degrees around)

When you build this unit you must test it with *your specific receiver.* The audio circuits in a receiver sometimes invert the audio phase and if that is the case, the unit will read opposite of the true direction. If this happens to you simply turn the antenna unit around or reverse the connections to the meter.

If you look closely at the center of the antenna boom in the picture below, you will see my markings on the antenna for one of my HTs. (I used abbreviations, but it says "When using the Ten-Tec HT, this side of the boom should be on the bottom and away from the transmitter")

Circuit Description

This circuit is adapted from an idea which originally was described in QST in an article for a Double Ducky direction finder. It uses a CMOS 4066 as a synchronous detector. I used a CMOS 555 as a square wave oscillator to drive both the antenna switching diodes and the synchronous detector. I also added a stage of audio amplification to help drive a less sensitive meter. This unit was originally designed to be mounted directly on the antenna connector of my HT. This worked fine when I originally built it. Today, I have a Yeasu FT50R. It is smaller than the TDOA unit and has an SMA connector for the antenna. Somehow, I don't think it could support the weight.

Audio is input via a cable connected to the earphone jack of the HT. A small loudspeaker was mounted on the front of the T.D.O.A. RDF unit to allow me to hear the FOX. The loudspeaker is not illustrated in the schematic shown here. The T.D.O.A. RDF unit supplies voltage to the antenna unit through the center conductor of the coax. The voltage alternately causes the diodes connected to the antenna elements to conduct. As the diodes conduct, RF is able to flow from one of the antenna elements to the receiver The switching rate is set by the .01uf capacitor and the 47k resistor connected to pin 2 of the 555. If you would like a different tone, try adjusting the value of the 47k resistor.

This T.D.O.A. RDF unit uses a center scale meter to indicate which direction to turn in order to face the transmitter. I used a surplus meter movement in my TDOA RDF unit. It was not a center zero meter until I took it apart and moved the mechanical zero adjust lever to make it so. I would guess it was a 100 microamp meter movement originally. I think it was a signal strength meter from an old FM broadcast band receiver. A more sensitive meter would allow you to use less volume. I usually look for a 50 to 200 microamp zero center meter when building one of these units and can usually find a bargain at one of the ham radio flea markets I attend. I never spend more than five dollars for a surplus meter. The meter in this unit cost me about a dollar. I would guess that even a 500 microamp meter could be used. I would be less sensitive and require you to use a bit more volume.

The Printed Circuit Board

I used rub-on transfers (available from Radio Shack) to lay out the PC board in this unit. It does not have the audio amplifier stage which is present on the PC layout included on this web page. The amplifier is needed when using less sensitive meter movements.

The PC board layout is shown here looking at the bottom of the board as if you had X-ray eyes and could look through the board and see the parts on top. There is one wire jumper. It is at the lower right side of the PC board. The two transistors are 2N3904 or equivalent. The two diodes across the meter movement are 1N914 or equivalent. The three 25uf capacitors each have two different pads available for their leads. If you can obtain parts small enough to fit the set of pads spaced closer together, use them. There is nothing critical about the value of most of the parts. Anything plus or minus 20 percent of the value indicated will work. (don't add 20% to the 555 or the 4066. I doubt *that* would work!).

All of the resistors are 1/4 watt. The two diodes on the PC board are connected "back-to-back" The PC layout illustrates how the diodes should be mounted. The electrolytic caps should be rated for at least 10 volts. (assuming you are going to use a 9 volt battery). The 1.0 microhenry coil used to couple the output from the 555 to the antenna was fashioned by winding about 20 turns of number 22 AWG wire on a 3/16 inch drill bit. It was then slid off of the drill and mounted on the PC board.



The Antenna Unit

Details of the antenna are shown below. The four antenna elements should be fashioned out of stiff wire or metal rods. One club member recycled a broken TV antenna and used 19 inch segments of its elements. The schematic shows two antennas; you might be wondering why there are four antenna elements. The extra two are connected to the coax shield at the ends of the boom. These form a counterpoise for the two active elements.

The boom of the antenna must be less than 1/2 wavelength long. The longer the boom, (up to 1/2 wavelenngth) the more RF phase difference will be detected. I found that spacing the antennas about 1/4 wavelength apart gave the best results. Further apart resulted in more modulation but at the expense of portability. It also seemed a bit less sensitive to multipath errors when I used the shorter boom. The antenna unit pictured here has a 15 inch long boom.

The antenna must be constructed as symmetrical as possible. The lengths of coax from the center BNC connector must be identical. A difference of 1/2 inch will cause an error of several degrees. If you use 1/2 wavelengths of coax you only need one set of diodes where the coax connects to the BNC connector at the center of the boom. If you find it easier to mount a flange style SO-239 connector on the boom instead of a BNC, use it instead. You will then need a cable with an PL-259 at one end and a BNC connector at the other to connect the antenna to the RDF unit.



I have found that by mounting the antenna on a mast so it is up and in the clear will result in the most accurate bearings.(It is then away from reflections from your body and the ground) Whatever you do, make the unit collapsible so it can be stored when not in use.




1/4 wavelength antenna element
RDF ANTENNA MECHANICAL DETAIL
1N4007
820
RG58 Coax
1N4007
1N4007
1N4007
RG58 Coax
820
1/4 wavelength counterpoise element
Female BNC Connector

It is very important that the diodes on the antenna be connected as shown on the schematic. Most diodes have a band which shows which end is the cathode. The best diodes for use in the antenna are RF PIN diodes. I used 1SS103 PIN diodes I purchased at a flea market. An equivalent diode is the MPN 3404. In a pinch, you can substitute a 1N4007 power diodes. They have a similar internal diode structure to the PIN diodes and will work almost as well. The MPN 3404 is advertised at Dan's small parts

RDF Antenna Mechanical Details

My antenna unit is designed to fold for storage. Wing nuts are used to secure the elements in position. I used brass brazing rod for the antenna elements on my latest hand-held unit. Earlier units used straightened out coat hanger. On the unit pictured, I used 1/2 wavelength lengths of coax between the center PIN diode and the antenna elements. This allowed me to use only one pair of PIN diodes in the center. I coiled the coax and secured it to the boom mid way between the center BNC connector and the ends. RG-174 coax was used on the unit illustrated here to reduce weight. The resistor in the picture is a 1.5k. The schematic below shows 820 ohms. Remember, in this circuit, few part values are critical.

The antenna boom was made from a piece of scrap glass epoxy circuit board material about 15 inches long and about 1 1/4 inch wide. I peeled the copper from the board, mounted a BNC connector at the center, and used small ring terminals secured by screws as tie points.The PIN diodes are the small rectangular black parts with the red stripe at one end. The picture shows them soldered to the back of a chassis mount BNC connector.

When you build your antenna make sure you mark one side as being the side towards the transmitter. Also mark the TOP. The first time I used this antenna, I started out walking away from the fox instead of towards it because the antenna was being held upside down. (My antenna was visually as well as physically symetrical) What amazed me was the number of other hunters who followed me thinking I knew where I was going. For the second fox hunt, I had marked the antenna. I won that event using this unit.

The Schematic


+ 9 volts
2 Antennas - 19 inches long,
spaced 14 inches apart.
1N4007 diodes are the best substitute
if you are unable to get PIN diodes
made for switching RF.
82 K
R1
8.2 K
R3
AUDIO
INPUT
C1
25 uf
Q1
2N3904
C2
+
25uf
R5
680
10K
R2
R4
390
R6
12 K
12K
R10
Q2
2N3904
1/4
4066
6
8
9
10
11
12
5
4
3
2
1
13
METER
D1
D2
R11
680
R12
820
R13
820
D3
D4
D5
D6
COAX to Antenna Unit
+ 9 volts
R7
1K
R8
47 K
C3
.01 uf
U1
555
5
6
7
8
4
3
2
1
C4
+
25 uf
R9 100
C 5
.001
C6
.001 uf
L1 1.0 uh
C7
390 pf
To Receiver Antenna Input
WB2HOL RDF
9/93

555 Time-Difference-Of-Arrival RDF

by Joe Leggio WB2HOL

This T.D.O.A. RDF set is built on a Radio-Shack experimenters board. It was featured on the cover of the May,June,July 1993 issue of the South Eastern Repeater Association, Inc Repeater Journal.

It uses a single 555 timer wired to produce a square wave output at about 500 Hz. 1N4007 power rectifier diodes were used in place of PIN diodes to switch between two dipole antennas at a 500 Hz rate. If you substitute another lower voltage power rectifier, it will work, just not as well. Of course, if you have RF PIN diodes, use them. (the 1N4007 is the only diode in the 1N400X series to contain a PIN diode structure) Power is supplied by a 9 volt battery.

I mounted the 555 oscillator circuit at the center of a 15 inch long piece of wood which acts as a boom to support two dipoles. The dimensions are not too critical. I used small brass screws as tie points at the ends of the boom and used wing-nuts to allow the dipole elements to fold against the boom when the unit was not in use.

I did not bother to add a power switch. I simply used a rubber band to secure the 9 volt battery to the boom and disconnect the battery from the circuit when I'm not using it.

How it works

Time Difference of Arrival RDF sets work by switching your receiver between two antennas at a rapid rate. When both antennas are the same distance from the transmitter, the RF phase received by both antennas will be identical. If the two antennas are different distances from the transmitter the RF will have a different phase at each antenna. If we switch between the antennas 500 times a second, this phase change will be detected by an FM receiver as a 500 Hz tone.

By turning the antennas for a null in the tone, your two antennas will be perpendicular to the transmitter. Unfortunately, you can be facing the transmitter or facing away from the transmitter and get a null in the tone. This circuit does not give you the ability to know if you are facing the transmitter or facing away from it. You must use triangulation to determine the correct direction. Although I have not tried it, you may also add a switched phasing line to your unit as shown here. This will result in a non-symmetrical receive pattern and allow an indication of which direction to travel.

The best method to tell the front from the back when using a TDOA RDF unit is by using a T.D.O.A. with a synchronous detector and processing the phase of the tone. It is then possible to drive a center scale meter to indicate which direction to turn to face the transmitter.

The Antenna Unit



Details of the antenna are shown below. The four antenna elements should be fashioned out of stiff wire or metal rods. One club member recycled a broken TV antenna and used 19 inch segments of its elements. The schematic shows two antennas; you might be wondering why there are four antenna elements. The extra two are connected to the coax shield at the ends of the boom. These form a counterpoise for the two active elements. I found that 15 inch lengths of wire "coat-hanger" worked well as antenna elements for the unit pictured here. You can experiment to determine the optimal length and distance between the dipole elements. (until you run out of wire hangers, that is)

The boom of the antenna must be less than 1/2 wavelength long. The longer the boom, (up to 1/2 wavelength) the more RF phase difference will be detected. I found that spacing the antennas about 1/4 wavelength apart gave the best results. Further apart resulted in more modulation but at the expense of portability. It also seemed a bit less sensitive to multipath errors when I used the shorter boom. The unit pictured here has a 15 inch long boom.

The antenna must be constructed as symmetrical as possible. The lengths of coax from the center circuit board must be identical. A difference of 1/2 inch will cause an error of several degrees. Note that the layout of the antenna switching diodes on the experimenters PC board is symmetrical.

I have found that by mounting the antenna on a mast so it is up and in the clear will result in the most accurate bearings.(It is then away from reflections from your body and the ground) Whatever you do, make the unit collapsible so it can be stored when not in use. I used wing-nuts on the antenna elements to allow the unit to fold easily.

It is very important that the diodes on the antenna be connected as shown on the schematic. Most diodes have a band which shows which end is the cathode. The best diodes for use in the antenna are RF PIN diodes. I used 1SS103 PIN diodes I purchased at a flea market. An equivalent diode is the MPN-3404. In a pinch, you can substitute a 1N4007 power diodes. They have a similar internal diode structure to the PIN diodes and will work almost as well. The MPN-3404 is advertised at Dan's small parts





555 Time Difference of Arrival

RDF Unit

1991 - WB2HOL

1N4007
1N4007
1N4007
1N4007
820
820
+ 9 Volts
1k
33k
.047uf
5
6
7
8
4
3
2
1
555
555 Timer
47uf, 16v
+
1k
L1
470pf
To Receiver

L1 = 10 turns, # 24 AWG air-core wound on 1/8 inch form

TAPE MEASURE BEAM OPTIMIZED FOR RADIO DIRECTION FINDING

Joe Leggio WB2HOL

Description

This antenna evolved during my search for a beam with a really great front-to-back ratio to use in hidden transmitter hunts. This design exhibits a very clean pattern and is perfect for RDF use. It trades a bit of forward gain in exchange for a very deep notch in the pattern toward the rear. (You could optimize the design for more forward gain, but at the expense of a really good notch in the pattern toward the rear.) It is a design that can be constructed using only simple hand tools (no machine shop needed) and still perform well. It has been duplicated several dozen times by other local hams and has been successfully used as a club construction project.

When I designed this antenna I had one basic idea in mind. It had to be easy to get in and out of the car when hunting for a hidden transmitter. This would be accomplished by the use of steel "tape measure" elements. These elements could fold easily when fitting the antenna into my car and yet still be self supporting. I decided to use three elements to keep the boom from getting too long.



Another of my design goals was to use materials that were easy to obtain. I chose to use Schedule-40 PVC pipe and fittings available at my local hardware store for the boom and element supports. These kept the cost for the antenna very low. The element supports consist of PVC crosses and tees.

Since I had never seen any plans for an antenna using elements made from 1 inch wide steel "tape measure," I had to do the design myself. To assist in the design I used a shareware computer aided yagi design program written by Paul McMahon VK3DIP. It allowed me to optimize the antenna for the cleanest pattern combined with the best front-to-back ratio.

Performance Predicted by YAGI-CAD	
GAIN	7.3 dBd
Front-to-Back Ratio	>50 db
3 db Beamwidth	E = 67.5 degrees
3 db Beamwidth	H = 110 degrees

When I first built this beam I found it needed a matching network of some kind to have a low SWR. My first attempt was a Gamma match. This was unwieldy. The driven element could barely handle the weight and the Gamma match itself was not very flexible. The best matching network turned out to be a "hairpin match." This is simply a 5 inch length of wire that is connected across the feed points of the driven element. The antenna has some capacitive reactance without the matching network. The 5 inch length of wire has just enough inductance to cancel the capacitive reactance. This resulted in a better match than anything else I had tried.

The wire I used for the hairpin match was enamel insulated 18 gauge solid. Other hams who have duplicated this beam have used just about anything they had on hand. 14 gauge house wire works well, so does a length of 22 gauge hookup wire. It does not seem to matter if it is stranded or solid, use whatever you have available. This results in a very good match across the two meter band once you have adjusted the distance between the halves of the driven element for minimum SWR. (1 inch apart on my prototype).

I used a pair of shears to cut the tape measure elements to length. An old pair of scissors will probably do as well. No matter how you cut the elements be very careful. Those edges are very sharp and will inflict a nasty cut if you are careless. Use some sandpaper to remove the really sharp edges and burrs resulting from cutting the elements to size. I put some vinyl electrical tape on the ends of the elements to protect myself from getting cut. I encourage you to do the same. It will probably be best if you round the corners of the elements once you cut them. Wear safety glasses while cutting the elements. Those bits of tape measure can be hazardous.

The RG58 coax feedline is connected directly to the driven element. No matter what method you use to attach the feedline, make sure you scrape or sand the paint off the tape measure element where the feedline is attached. Most tape measures have a very durable paint finish designed to stand up to heavy use. You do not want the paint to insulate your feedline connection.

If you are careful, It is possible to solder the feedline to the element halves. Care must be taken since the steel tape measure does not solder easily and since the PVC supports are easily melted. You might want to tin the tape measure elements before mounting them to the PVC cross.

If you decide not to solder to the tape measure elements, there are two other methods that have been used to attach the feedline. One method employs ring terminals on the end of the feedline. The ring terminals are then secured under self tapping screws which hold the driven element halves. This method does not allow you to tune the antenna by moving the halves of the driven element. 6-32 bolts and nuts could be used if holes are drilled in the elements near the ends. If the bolt heads are placed nearest the PVC fitting, you could secure ring-terminals with nuts and lock washers. Another possibility is to simply slide the ends of the feedline under the driven element hose clamps and tighten the clamps to hold the ends of the coax. I know this is low-tech, but it works just fine.



Stainless steel hose clamps are used to attach the driven element halves to the PVC cross which acts as its support. This has the added benefit of allowing you to fine tune your antenna for lowest SWR simply by loosening the hose clamps and sliding the halves of the driven element either closer or further apart. By using the dimensions specified, I found that the SWR was 1:1 at 146.565 Mhz (our Fox-Hunt frequency) when the two elements were spaced approximately 1 inch apart. Figure 1 shows the method used to attach the driven element to the PVC cross.

I used 1 1/2 inch hose clamps to attach all the elements on my prototype beam. Others who have duplicated my design have used self tapping screws to attach the elements to the PVC crosses and tees. Performance is the same using either method. The screws are much less expensive but they do not hold the elements as securely. If you do not use 1/2 inch PVC fittings but instead use 3/4 inch, make sure the hose clamps you buy are large enough to fit.

If you wish a slightly neater looking beam, use the self tapping screws. If you do not mind spending a few more dollars for the hose clamps, use them instead. If I were to build another beam I would use screws for the director and reflector, and hose clamps for the driven element. That would give me the best of both methods.

Rubber faucet washers have been used by some builders between the tape measure element and the PVC fittings on the director and reflector. These allow for the tape to fit the contour of the PVC fitting and will make the antenna look better. Now you know what to do with those washers left over from the assortment you once purchased; You know the ones I mean, the washers that do not fit the faucets you have in your house. If you are an apartment dweller, ask around, these things are stashed in almost every homeowners basement or garage.


Reflector
41 3/8 inches
Driven Element
35 1/2 inches
(each half = 17 3/4 inches)
Director
35 1/8 inches
1/2 inch
Schedule 40
PVC Crosses
1 1/2 inch
Stainless Steel
Hose Clamps
1/2 inch
Schedule 40
PVC Tee
RG-58
Coax
1/2 inch
Schedule 40
PVC Pipe
Use tape on
cut edges for
safety.
8 inches
12 1/2 inches
Antenna elements are made of 1 inch wide steel
tape-measure.

Construction:

Cut a length of tape measure to 41 3/8 inches. It will be the Reflector element. Cut two lengths of tape measure to 17 3/4 inches. These will be used for the Driven element. Cut one length of tape measure to 35 1/8 inches. It will be used for the Director. Once you have cut the tape measure to length, put vinyl tape on the cut ends to protect yourself from the sharp edges. You will want to scrape or sand off the paint from one end of each of the driven element halves so you can make a good electrical connection to the feedline.

If you are planning to solder the feedline to the driven elements it is best to tin the elements first before attaching them to the PVC cross. If you don’t, the PVC will melt as you apply heat to the element. It would be a good idea to also take the time to form the wire used for the hairpin match into a “U” shape with the two legs of the “U” about 3/4 inch apart. Tin the ends of the hairpin if you plan on soldering it to the driven element. If you tin 1/4 inch of each end of the hairpin it will leave 4 1/2 inches to shape into the “U”.

You will need to cut two lengths of PVC pipe to use as the boom. One should be cut to 11 1/2 inches. It is used to form the boom between the Director and the driven element. The other piece of PVC should be cut to 7 inches. It will be used between the Reflector and the Driven element. Just about any saw will cut through the soft PVC pipe. I used a hacksaw. When we mass produced this antenna as a club project, we marked the pipe and used a portable jig saw to cut the lengths in assembly line fashion. It took longer to measure the pipe than to actually make the cuts. Since the pipe is available in ten foot lengths, you can make a few beams from a single 10 foot length. In any case, you might want to cut a few extras lengths for your friends. They will want to duplicate this once they see your completed antenna.

At this time you can pre-assemble the PVC boom, crosses and tee which will support the tape measure elements. I did not use any cement or glue when I assembled mine. The PVC pipe is secured in the fittings with a friction fit.

The hose clamps I used are stainless steel and have a worm-drive screw which is used to tighten them. They are about 1/2 inch wide and are adjustable from 11/16 inch to 1 1/2 inch diameter. Attach the tape measure elements to the PVC fittings as shown in the accompanying drawing. It is normal for the Reflector and Director elements to buckle a bit as it is tightened to the PVC Tee and Cross. You can eliminate this buckle if you use the washers and self tapping screws to attach these elements instead of the hose clamps. I do not think the beam will withstand as rough a treatment as when hose clamps are used.

How does it perform?

Once you have completed your beam you probably will be interested to see if it performs as well as the computer predicted. The SWR should be less than 2:1 across the entire two meter band. The front-to-back ratio is predicted to be very good with the antenna exhibiting a very deep notch in its pattern towards the rear. The YagiCad 4.1 program produced these antenna pattern graphs showing the pattern you should expect. If you would like to experiment a bit with this program, the yagi specification file for this tape measure beam is available for download here. Simply download the YAGI-CAD program and put the tape measure beam design file in the same directory. You will then be able to experiment with the design.

Note: under Windows95, only the first .yag file will show in the OPEN-FILE menu. You can either move all the other .yag files to a sub-directory or re-start the computer in MS-DOS mode. It works fine there. (I really do not know why this occurs but will blame Microsoft)



How does the tape measure beam "measure up?"

WB4SUV and WA6EZV used a storage scope connected to a copy of this antenna constructed by KC8FQY and provided the following picture of the actual antenna pattern. I am very happy to see that the computer prediction of a clean pattern with a really great front-to-back ratio was accurate. What do you think?



Summary

This beam has been used on Fox-Hunts, on mountain tops, at local public service events, outdoors, indoors in attics, just about everywhere. The SWR is typically very close to 1:1 once adjusted. Front to back performance is exactly as predicted. The null in the rear of the pattern is perfect for transmitter hunts. When tested using a sensitive field strength meter and a low powered fox transmitter, full scale readings were seen from a distance of ten feet. With the same field strength meter I was able to point the antenna away from the transmitter and move the reflector element to within a few inches of the transmitter antenna and still not see a reading. I don’t have the facilities to verify a 50 db notch as predicted by the Yagi-Cad software but It sure seems close. The flexible elements have taken a lot of abuse. My antenna has seen a lot of use and has held up quite well. Best of all, when on a fox-hunt, this beam is a breeze to get in or out of the car.

RDF2 YAGI WITH TAPE MEASURE ELEMENTS

Joe Leggio WB2HOL



Description

This antenna is an adaptation of the RDF2 two element, close spaced Yagi antenna described in the May, 1996 issue of 73 Amateur Radio Today Magazine.

The original design, developed by N6WZI and featured in the Homing In column of 73, used 1/4 inch solid aluminum rods for antenna elements. If you don't subscribe to 73, find someone who does and ask to see the original article.

My version of the RDF2 antenna uses 1 inch wide steel "tape measure" elements. This is one antenna you can take into the woods without having to worry about Yagi Eating Trees. The flexible elements also make it very easy to get this antenna in and out of the car.

You do not need a machine shop to build this antenna. You only need common hand tools. It is much easier to construct than the original design and can be assembled in about 30 minutes once you gather the needed parts.

Performance Predicted by ELNEC	
GAIN	4.7 dBi
Front-to-Back Ratio	>8 db
3 db Beamwidth	E = 36 degrees
3 db Beamwidth	H = 70 degrees

N6WZI's original design used a "hairpin" matching network made from a length of TV antenna twinlead. I made a similar "hairpin match" but instead used a 5 inch length of wire connected across the feed points of the driven element. The antenna has some capacitive reactance without the matching network. The 5 inch length of wire has just enough inductance to cancel the capacitive reactance.

The wire I used for the hairpin match was enamel insulated 18 gauge solid. This results in a very good match across the two meter band once you have adjusted the distance between the halves of the driven element for minimum SWR at the desired frequency. (3/16 inch apart on my prototype). Experience has shown that the wire guage used for the hairpin match is not very critical. Use what you have on hand. 14 guage house wire works well, probably any insulated wire which will hold its shape will work just fine.

I used a pair of shears to cut the tape measure elements to length. An old pair of scissors will probably do as well. No matter how you cut the elements be very careful. Those edges are very sharp and will inflict a nasty cut if you are careless. Use some sandpaper to remove the really sharp edges and burrs resulting from cutting the elements to size. I put some vinyl electrical tape on the ends of the elements to protect myself from getting cut. I encourage you to do the same. It will probably be best if you round the corners of the elements once you cut them. Wear safety glasses while cutting the elements. Those bits of tape measure can be hazardous.

Replacement tape measure blades are available for reasonable prices at larger hardware stores. I found a 30 foot replacement blade at Sears for less than five dollars. If you use a replacement blade, be very careful when removing it from the package. The blade I purchased had a hard plastic cover which, when twisted, allowed access to the end of the replacement tape measure element. When you twist the cover, make sure you keep your fingers away from the "razor sharp" end of the blade. (I probably could have assembled this antenna in even less time if I didn't have to go upstairs to the medicine chest to get a band-aid. This is experience speaking. The spring steel popped out, inflicting a nasty cut on my thumb. I'll probably heal in a week or so...)

The RG58 coax feedline is connected directly to the driven element. No matter what method you use to attach the feedline, make sure you scrape or sand the paint off the tape measure element where the feedline is attached. Most tape measures have a very durable paint finish designed to stand up to heavy use. You do not want the paint to insulate your feedline connection.

If you are careful, It is possible to solder the feedline to the element halves. Care must be taken since the steel tape measure does not solder easily and since the PVC supports are easily melted. You might want to tin the tape measure elements before mounting them to the PVC cross. I used a bit of rosin flux to help with tinning the element connection points.


Two Meter Tape-Measure RDF² Beam
12/97 WB2HOL - adapted from N6WZI design
Driven Element
each half = 18 5/8 inches
elements spaced 1/4 to 3/8 inch apart.
total overall length approx. 37 1/2 inches
Director
37 3/16 inches
1/2 inch
Schedule 40
PVC Cross
RG-58
Coax
1/2 inch
Schedule 40
PVC Tee
1 1/2 inch
Stainless Steel
Hose Clamps
Hairpin match
5 inch length
14 - 18 guage
1/2 inch
Schedule 40
PVC Pipe
Use tape on
cut edges for
safety.
4
inches
Antenna elements are made of 1 inch wide steel
tape-measure.

Stainless steel hose clamps are used to attach the driven element halves to the PVC cross which acts as its support. This has the added benefit of allowing you to fine tune your antenna for lowest SWR simply by loosening the hose clamps and sliding the halves of the driven element either closer or further apart. By using the dimensions specified, I found that the SWR was 1:1 at 146.565 Mhz (our Fox-Hunt frequency) when the two elements were spaced approximately 3/16 inch apart. Figure 1 shows the method used to attach the driven element to the PVC cross.

I used 1 1/2 inch hose clamps to attach all the elements on my prototype beam. if you do not use 1/2 inch PVC fittings but instead use 3/4 inch, make sure the hose clamps you buy are large enough to fit. Others who have duplicated my design have used self tapping screws to attach the elements to the PVC crosses and tees. Performance is the same using either method. The screws are much less expensive but they do not hold the elements as securely. In addition, the screws do not allow you to tune the antenna by sliding the halves of the driven element closer or further apart.

If you wish a slightly neater looking beam, use the self tapping screws. If you do not mind spending a few more dollars for the hose clamps, use them instead. If I were to build another beam I would use screws for the director, and hose clamps for the driven element. That would give me the best of both methods.

Construction:

Cut two lengths of tape measure to 18 5/8 inches. These will be used for the Driven element. Cut one length of tape measure to 37 3/16 inches. It will be used for the Director. Once you have cut the tape measure to length, put vinyl tape on the cut ends to protect yourself from the sharp edges. You will want to scrape or sand off the paint from one end of each of the driven element halves so you can make a good electrical connection to the feedline.

It is best to tin the elements first before attaching them to the PVC cross. If you don’t, the PVC will melt as you apply heat to the element. It would be a good idea to also take the time to form the wire used for the hairpin match into a “U” shape with the two legs of the “U” about 3/4 inch apart. Tin the ends of the hairpin to make it easier when soldering it to the driven element halves. If you tin 1/4 inch of each end of the hairpin it will leave 4 1/2 inches to shape into the “U”.

You will need to cut two lengths of PVC pipe. One should be cut to 3 inches. It is used to form the boom between the Director and the driven element. The other piece of PVC should be cut to 6 1/2 inches. It will be used as a handle so you can hold the antenna from the rear. Just about any saw will cut through the soft PVC pipe. I used a hacksaw. Since the pipe is available in ten foot lengths, you can make a few beams from a single 10 foot length. In any case, you might want to cut a few extras lengths for your friends. They will want to duplicate this once they see your completed antenna.

At this time you can pre-assemble the PVC boom, cross and tee which will support the tape measure elements. I did not use any cement or glue when I assembled mine. The PVC pipe is secured in the fittings with a friction fit. When assembled, the cross and tee will be 4 inches from center to center.

The hose clamps I used are stainless steel and have a worm-drive screw which is used to tighten them. They are about 1/2 inch wide and are adjustable from 11/16 inch to 1 1/2 inch diameter. Attach the tape measure elements to the PVC fittings as shown in the accompanying drawing. It is normal for the Director element to buckle a bit as it is tightened to the PVC Tee. You can eliminate this buckle if you use washers and self tapping screws to attach this element instead of the hose clamps but I do not think the beam will withstand as rough a treatment as when hose clamps are used.

How does it perform?

Once you have completed your beam you probably will be interested to see if it performs as well as the computer predicted. My prototype antenna does seem to have a pretty good front-to-back ratio. It is real easy to get a peak on the "S" meter. It does not hear cross polarized signals very well. This is an advantage as most reflections will not have the same polarization as the original transmitter. Gain seems to be between 3 to 5 dB less than the three element RDF beam I designed. This is probably an advantage when close to the transmitter. You will need a bit less attenuation. The short boom and light weight make this antenna attractive if you have to use it for any length of time. It is light enough for youngsters to carry without tiring. As long as you put vinyl tape on the ends of the elements, this antenna is pretty safe to carry. Descriptions of the N6WZI RDF2 Yagi performance when used on a foxhunt may be found at Jim Elmore's site.

Drawbacks

The curved, airfoil shaped, flexible elements will "flutter" and bend when in high wind situations. (Mobile flutter while stationary?) If you need additional support, you can add short lengths of PVC pipe to the TEE and CROSS and then tape the elements to the PVC pipe. I figure 6 to 12 inches of PVC would add lots of strength to the elements. The short boom does result in less gain than a more conventional Yagi. You may need more gain when starting on a foxhunt and still far from the fox transmitter.

THE FOX - 40 milliwatt transmitter

Joe Leggio WB2HOL

This two transistor 144 MHz transmitter uses a 48 MHz scanner crystal as an oscillator / tripler. A second transistor boosts the power output to 40 milliwatts. A 7-element filter is used to minimize output on the third harmonic. (I did not want it to be easy to RDF this on the 450 MHz third harmonic)



The scanner crystal I used was actually for a receive frequency 10.7 MHz higher than the two meter transmitter output. It was marked 156.21 MHz. (When you subtract the 10.7 MHz IF offset, it resulted in a transmit frequency of 145.51. Since this circuit is not the exact same circuit as the scanner, you may find that the crystal oscillates somewhere close to the marked frequency. The crystal marked as 156.21 MHz I used in this transmitter actually resulted in a signal on 145.53 MHz.)

I did get the salesperson at the local Radio Shack store a bit confused when I asked to look at his box of scanner crystals. The first thing he asked was which service I was trying to listen to... Police, Fire, Ambulance, etc.... When I said that I was looking for something for a homemade project and did not have a specific frequency in mind he understood. I did not try to tell him the crystal was to be used in a transmitter. He probably would have told me that I can't use a "receiver" crystal for a "transmitter."

As I looked at the available crystal selections, I simply took my calculator and subtracted 10.7 MHz from the marked receive frequency. I was lucky; several crystals ended up in places on the two meter band where a fox could transmit without interfering with other users. If you are not lucky, or live in an area where you must put your fox on a specific frequency, you can order a crystal through Radio Shack. Since there are still quite a few crystal controlled scanners out there, the odds are that someone in your town will have something you can use. Be aware, although most scanners use a 10.7 MHz IF, there are some with a 10.8 MHz IF. In that case, you may end up 100 kHz from where you expected.

You will need to wind several coils to build this transmitter. They are all self-supporting air-core coils made from enamel covered wire. If you follow the instructions illustrated here, you should not have any difficulty. The top of my workbench is littered with coils I have wound and tried in various circuits. I specifically avoided tapped coils or multi-winding coils to keep construction as easy as possible.

I use a simple diode detector across a 50-ohm dummy load to measure the power output while tuning up this transmitter. It is reasonably stable. It does not have a tendency to break into spurious oscillations. I did try about 5 or 6 different prototype circuits as I designed this transmitter; many were not stable. Their RF output did not smoothly change as the trimmer capacitors were adjusted but instead jumped as spurious oscillations occurred. I used an oscilloscope to monitor the output waveform and confirm the lack of spurious oscillations. This is not really necessary as you can usually hear the instability if you monitor the output signal with your 2-meter rig.

Style of PC board construction

I built all of the transmitters using copper clad PC board as a ground plane and 1/4 inch squares of PC board as tie points. The tie points were cemented to the ground plane using "crazy-glue." This technique made constructing the transmitter go very fast. It only took a drop of glue to secure the tie points. The glue set up in seconds. It made it easy to experiment with different circuits. In a pinch, a tie point could be removed or relocated by prying upward on its side with a screwdriver. I built three transmitters using this style of construction in the past month. All have worked exactly as expected. I used a pair of shears to cut a number of 1/4 inch squares of PC board material. I then used a wide file to remove any burrs created by the shear. This allowed the square of PC board material to lay flat against the PC ground plane. (Crazy-glue is not designed to fill voids. It works best when the surfaces to be glued fit together well) Be careful as you work with "crazy-glue." It is very effective at gluing fingers together.

I tried to use parts that could be obtained with little difficulty. You will need to wind several coils. I also kept these as simple as possible. The wire I used was recycled from old transformers.



Tie-points are made from 1/4 inch squares of PC board materialglued with "crazy-glue" to a solid ground plane of PC board.

Winding the Coils



Enamel wire is close-wound on a drill bit to form the coils for this transmitter. It is easier to cut the leads to the coil and strip the enamel from the ends prior to removing the coil from the drillbit used as the form.

All the coils are wound in a single layer using a drill bit as a winding form. To help you visualize how to form the coils, I have included an illustration showing how the coils are wound..

All of the coils are "close wound" with "air cores." I used a drill bit as a form and then slipped the coil off of the bit after I had cut the free ends to about 1/4 inch. I used a hobby knife to scrape the enamel paint from the ends of the wire before I removed the coil from the drill bit used as a form. This made the coils easy to solder. With any luck, you too will be able to wind your own coils for this project.

Two different gauges of enamel covered wire are used for the coils in this project. If you have wire reclaimed from an old transformer, or from an old television deflection yoke, you can determine its gauge by winding a single layer on a drill bit. You will be able to fit about 46 turns per inch if the wire is 24 gauge. You will be able to fit about 37 turns per inch if the wire is 22 gauge. If you can't find an old transformer with the correct gauge wire to recycle, the best places I have found to buy enamel covered wire are shops which specialize in rewinding electric motors. In a pinch, if you live in the USA, Radio Shack sells "magnet wire" in both 24 and 22 gauge. You will only need a few feet of each gauge wire for this project.

I used the same transistor for both the oscillator and the amplifier stage. It is important that the transistors you use in your transmitter have sufficient gain at 2 meters. The 2N5770 is one of many I could have used. Please note: a 2N3904 would probably work fine as the oscillator (at 48 MHz), it would not work well as the amplifier as it does not work well at 144 MHz.

The tune-up of this transmitter is easy. Simply adjust each of the trimmer capacitors for maximum RF output to the antenna. (The trimmer in series with the crystal is the only exception, it is used to trim the transmitter frequency, use a frequency counter to adjust it)

I packaged one version of this transmitter in a very well shielded cast aluminum box and powered it with a 9 volt battery. The output power was reduced at the lower voltage to about 25 milliwatts. Even at that power level, it can be heard for miles. As an experiment, I tried voltages as low as 5 volts. The power output was down to below 10 milliwatts but the transmitter stayed on the air! This design works well even as the battery gets weak.

Schematic


+12 volts
3 turns #22 AWG, 1/4 inch diameter
120
120
120
.001
.001
2 - 25 pf
L2
.001
.001
15k
L3
5 turns #22 AWG, 1/4 inch diameter
Q2
2N5770
33k
Q1
2N5770
7 turns #22 AWG, 1/4 inch diameter
5.6 pf
4.7k
2 - 25 pf
L4
RF Output - 40 mW
48 MHz
10k
47 pf
39 pf
.001
33
3 turns #22 AWG, 1/4 inch diameter
2-25 pf
2 - 25 pf
25 turns #24 guage, 1/8 inch diameter
L5
L6
L7
.001
220
10 pf
22 pf
22 pf
10 pf

2 Meter - 40 mW FOX TRANSMITTER - 4/98 WB2HOL

THE FOX - 250mw transmitter with TIMER

Joe Leggio WB2HOL

This FOX transmitter is equipped with a timer. It can be set to start transmitting up to 24 hours later.



The timer consists of a Radio Shack travel alarm. I disconnected the pizeo-ceramic beeper and used the signal to set a flip-flop built from a CMOS 4011. The output of the flip flop is connected to a switching transistor which supplies voltage to the CW ID. I used an R/C combination on the flip/flop so it would be reset when first powered up. A push button is provided so the flip/flop can be set manually (turning on the transmitter)

The transmitter consists of three stages: a 45 MHz oscillator, a tripler, and a "power" amplifier. I know the heat sink on the final is a bit of overkill at 250 milliwatts output. I used a 6 volt gell cell for power. This thing can go for days.

The CW ID consists of a CMOS 4011 clock and a CMOS 4020 binary counter connected to a 2k EPROM. One bit on the EPROM is used for the CW ID, a second is used to control the switching transistor which supplies power to the transmitter oscillator. It is set up to transmit once every few minutes and stay on the air for about one minute.

Normally, the travel alarm timer is attached to the outside of the 3x5 file card box with velcro. This makes it easy to change the clock battery when needed.

A word of advice. Do not try to take a device like this through the security gate at an airport. It looks too much like something you would see in a "Die Hard" movie. Please make sure it is plainly labeled as an Amateur Radio Transmitter Location Device (or some other official title) and put your name and address on it in case it is discovered by someone not familiar with fox hunting. They *might* think the FOX looks suspicious and call officials to investigate. (You might want to notify officials in advance about your FOX-HUNT. We usually do just to eliminate problems when neighbors call in reporting *strange* people in the neighborhood)


POWER
+12V
S1
1k
R2
4.7k
R1
U1
1
1/4
CD4011
2
3
1uf
+
From Travel Alarm Timer
R3
10k
Q1
2N3904
GND
GND
U1
5
1/4
CD4011
6
4
R4
4.7k
To Transmitter
2N3904
b
c
e
Q2
GND
S2
Transmitter Enable Pushbutton (momentary)
GND

THE FOX750 - 750 milliwatt transmitter

Joe Leggio WB2HOL

This three transistor 144 MHz transmitter uses a 48 MHz scanner crystal as an oscillator / tripler. A second transistor boosts the signal to 40 milliwatts, a third amplifies the power output to 750 milliwatts.



The scanner crystal I used was actually for a receive frequency 10.7 MHz higher than the two meter transmitter output. It was marked 156.21 MHz. (When you subtract the 10.7 MHz IF offset, it resulted in a transmit frequency of 145.51. Since this circuit is not the exact same circuit as the scanner, you may find that the crystal oscillates somewhere close to the marked frequency. The crystal marked as 156.21 MHz I used in this transmitter actually resulted in a signal on 145.53 MHz.)

I did get the salesperson at the local Radio Shack store a bit confused when I asked to look at his box of scanner crystals. The first thing he asked was which service I was trying to listen to... Police, Fire, Ambulance, etc.... When I said that I was looking for something for a homemade project and did not have a specific frequency in mind he understood. I did not try to tell him the crystal was to be used in a transmitter. He probably would have told me that I can't use a "receiver" crystal for a "transmitter."

As I looked at the available crystal selections, I simply took my calculator and subtracted 10.7 MHz from the marked receive frequency. I was lucky; several crystals ended up in places on the two meter band where a fox could transmit without interfering with other users. If you are not lucky, or live in an area where you must put your fox on a specific frequency, you can order a crystal through Radio Shack. Since there are still quite a few crystal controlled scanners out there, the odds are that someone in your town will have something you can use. Be aware, although most scanners use a 10.7 MHz IF, there are some with a 10.8 MHz IF. In that case, you may end up 100 kHz from where you expected.

You will need to wind several coils to build this transmitter. They are all self-supporting air-core coils made from enamel covered wire. If you follow the instructions illustrated here, you should not have any difficulty. The top of my workbench is littered with coils I have wound and tried in various circuits. I specifically avoided tapped coils or multi-winding coils to keep construction as easy as possible.

I use a simple diode detector across a 50-ohm dummy load to measure the power output while tuning up this transmitter. I did try about 5 or 6 different prototype circuits as I designed this transmitter; many were not stable. Their RF output did not smoothly change as the trimmer capacitors were adjusted but instead jumped as spurious oscillations occurred. This design is reasonably stable. It does not have a tendency to break into spurious oscillations. I used an oscilloscope to monitor the output waveform and confirm the lack of spurious oscillations. This is not really necessary as you can usually hear the instability if you monitor the output signal with your 2-meter rig.

Style of PC board construction

I built all of the transmitters using copper clad PC board as a ground plane and 1/4 inch squares of PC board as tie points. The tie points were cemented to the ground plane using "crazy-glue." This technique made constructing the transmitter go very fast. It only took a drop of glue to secure the tie points. The glue set up in seconds. It made it easy to experiment with different circuits. In a pinch, a tie point could be removed or relocated by prying upward on its side with a screwdriver. I built three transmitters using this style of construction in the past month. All have worked exactly as expected. I used a pair of shears to cut a number of 1/4 inch squares of PC board material. I then used a wide file to remove any burrs created by the shear. This allowed the square of PC board material to lay flat against the PC ground plane. (Crazy-glue is not designed to fill voids. It works best when the surfaces to be glued fit together well) Be careful as you work with "crazy-glue." It is very effective at gluing fingers together.



Tie-points are made from 1/4 inch squares of PC board materialglued with "crazy-glue" to a solid ground plane of PC board.



As I had already constructed several low power versions of this transmitter, I first glued squares of PC board material for the first two stages to the PC board ground plane. I then proceeded to add the components. I saved the output stage for last as I had not yet decided upon the interstage and output coupling curcuit design. The design I finally used was a combination of several from the ARRL handbook. I tried to use parts that could be obtained with little difficulty.

Construction is under way. The oscillator stage was constructed first and tested before proceeding.



Winding Coils



Enamel wire is close-wound on a drill bit to form the coils for this transmitter. It is easier to cut the leads to the coil and strip the enamel from the ends prior to removing the coil from the drillbit used as the form.Winding the Coils

You will need to wind several coils. I kept these as simple as possible. The wire I used was recycled from old transformers. All the coils are wound in a single layer using a drill bit as a winding form. To help you visualize how to form the coils, I have included an illustration showing how the coils are wound..

All of the coils are "close wound" with "air cores." I used a drill bit as a form and then slipped the coil off of the bit after I had cut the free ends to about 1/4 inch. I used a hobby knife to scrape the enamel paint from the ends of the wire before I removed the coil from the drill bit used as a form. This made the coils easy to solder. With any luck, you too will be able to wind your own coils for this project.

Two different gauges of enamel covered wire are used for the coils in this project. If you have wire reclaimed from an old transformer, or from an old television deflection yoke, you can determine its gauge by winding a single layer on a drill bit. You will be able to fit about 46 turns per inch if the wire is 24 gauge. You will be able to fit about 37 turns per inch if the wire is 22 gauge. If you can't find an old transformer with the correct gauge wire to recycle, the best places I have found to buy enamel covered wire are shops which specialize in rewinding electric motors. In a pinch, if you live in the USA, Radio Shack sells "magnet wire" in both 24 and 22 gauge. You will only need a few feet of each gauge wire for this project.

I used the same transistor for both the oscillator and the amplifier stage. It is important that the transistors you use in your transmitter have sufficient gain at 2 meters. The 2N5770 is one of many I could have used. Please note: a 2N3904 would probably work fine as the oscillator (at 48 MHz), it would not work well as the amplifier as it does not work well at 144 MHz.

You will need to use a heat-sink on the output transistor. I used a small press-on style. I gets warm to the touch after transmitting for a few minutes. If it gets very hot, you probably have something mis-tuned or the circuit is oscillating on it own If you follow the layout shown, you probably will not have any difficulty. If you try a different layout, be sure to keep the input and output coils of the various stages away from each other. It is too easy to create an accidental feedback path. If this occurs, the transmitter will be very unstable and almost impossible to tame. If you are experienced with VHF design, you may want to try winding the coils in toriod coil forms. Because toriods are self-shielding, you may be able to try other layouts without as much concern towards stability. Obviously, if you do this, you will have to determine the number of turns needed for the toriods. A grid dip meter would be helpful in that case.

When building the output stage, I realized that I needed to bend the base lead of the output transistor between the emitter and collector in order to install it properly. Although it did not affect performance, it did make soldering the transistor to the PC board pads a bit more difficult. If I build another version of this transmitter, I will lay out the board a bit differently so the transistor will fit better to the pads.

The tune-up of this transmitter is easy. Simply adjust each of the trimmer capacitors for maximum RF output to the antenna. (The trimmer in series with the crystal is the only exception, it is used to trim the transmitter frequency, use a frequency counter to adjust it)

Power output was between 750 milliwats and 900 milliwatts. I will probably add a three terminal voltage regulator so I can vary the output power for any specific hunt. As an experiment, I tried voltages as low as 5 volts. The power output was down to 100 milliwatts but the transmitter stayed on the air! This design works well even as the battery gets weak.

Schematic


+12 volts
120
120
120
.001
2 - 25 pf
L2
.001
.001
15k
Q2
2N5770
L3
15 uF 20v
+
.001
L5
RF Output - 750 mW
33k
Q1
2N5770
L4
2 - 25 pf
L6
2 - 25 pf
48 MHz
5.6 pf
4.7k
2 - 25 pf
Q3
2N4427
L7
10k
47 pf
39 pf
100
2 - 25 pf
2 -25 pf
L1
.001
33
GND
GND
GND
.001
220

L1 = 25 turns #24 AWG, 1/8 inch diameter

L2 = 3 turns #22 AWG, 1/4 inch diameter

L3 = 5 turns #22 AWG, 1/4 inch diameter

L4 = 7 turns #22 AWG, 1/4 inch diameter

L5 = 12 turns #24 AWG, 1/8 inch diameter

L6 = 5 turns #22 AWG, 1/4 inch diameter

L7 = 3 turns #22 AWG, 1/4 inch diameter

2 Meter - 750 mW FOX TRANSMITTER - 4/98 WB2HOL

SIMPLE ADJUSTABLE PASSIVE ATTENUATOR

Joe Leggio WB2HOL


RF ATTENUATOR
WB2HOL 8/93
Chassis Mount BNC
PL-259 Shell
UHF Bulkhead adaptor or UHF to BNC adaptor
Washer
BNC nut
X-RAY VIEW
3/8 inch insulated wire soldered to BNC terminal

This adjustable passive attenuator works as a "waveguide beyond cutoff." It can be constructed in about ten minutes from parts available locally.

This attenuator was the result of a search for an inexpensive attenuator which could be used on an HT to help beginners equip themselves for a hidden transmitter hunt. The 3/8 inch piece of wire will extend into the center conductor of the bulkhead adaptor forming a small capacitor. The coupling between the two conductors will vary as the PL-259 shell is turned further onto the bulkhead adaptor.

If you are able to find a BNC to UHF adaptor with a long threaded portion, you may use it instead of the bulkhead adaptor.

The maximum attenuation available depends upon the length of the wire soldered to the chassis mount BNC connector. A service monitor measured a loss of up to 36 dB. With the cost so low and construction so simple, many hams have made several with different length wires.

Although 36 dB may sound like a lot of attenuation it will not be suffucient when on most transmitter hunts. This passive attenuator project is aimed at the beginner who is armed with only an HT and is attempting to use the "body-fade" method of Radio Direction Finding. The passive attenuator can be put in-line with the existing rubber-duck antenna and adjusted so the signal no longer is full scale on the S-meter.

Tuning off frequency by 5 or 10 kc, listening for the third harmonic, using a foil wrapped tube as an RF shield around the HT, or even wrapping aluminum foil directly around the HT are all methods which will help to some degree. One or more of these techniques will reduce the signal to where a "S" meter reading peak (or null) gives you a clue to the direction where the transmitter might be found. (If you do wrap aluminum foil around your HT, put some tape over any exposed battery charging contacts. Otherwise, the foil may get a bit warm as it rapidly discharges the battery)

When closer to the fox, more signal will enter the HT through the case than through the antenna. At this point, other methods must be used to locate the fox transmitter. The most effective attenuator in most cases is an "active attenuator." They can offer over 100 dB of attenuation. Plans for one are available here.

Construction Details

This BNC to UHF adapter has a raised knurled portion of the barrel which prevents the PL-259 shell from being tightened completely. (The BNC and insulated wire do not "bottom out" when tightened all the way) You can file that section of the adaptor down and enjoy more range in available attenuation.



Looking in at insulated wire I soldered the wire to the BNC before mounting it in the PL-259 shell. I used a length of wire clipped from a 2 watt resistor. (Use any stiff wire) I then forced a small length of insulation stripped from another piece of wire onto it. By using this method, the insulation does not melt during assembly.

I used a "star" washer. It was just the right size. The washer prevents the BNC connector from falling through the PL-259 shell. The hardest part of the construction is tightening the nut on the BNC connector. I usually wedge a screwdriver in the shell to hold the nut and tighten the BNC from the outside.



ACTIVE ATTENUATOR

Joe Leggio WB2HOL



How it works

This active attenuator works as a simple mixer. A signal from a 1 MHz oscillator is mixed with the received signal in a 1N914 diode. The 1000 ohm potentiometer adjusts the level of the local oscillator fed to the mixer diode.

It is possible to get over 100 db attenuation using this device. This circuit is a variation of one first described in the November, 1992 issue of QST. That circuit was designed by PA0ZR. It used a L/C tuned 500 KHz oscillator.

I used a 1 MHz crystal oscillator and it made construction even simpler than the original unit.

This attenuator is used by tuning the receiver 1 MHz above or below the frequency of the transmitter. By adjusting the oscillator level fed to the mixer diode, the signal output to the receiver will be attenuated.

Note: You may also tune your reciever 2 MHz above or below the frequency of the transmitter and get even more attenuation. (thanks to VE3EFY for this tip)



Technical Hints

If you find that this circuit does not oscillate with your crystal you might need to add a small capacitor (anything from 5pf to 25pf) from the gate of the FET to ground. It may also help to reduce the 150pf capicitor connected from the drain to ground to 100pf.

These two capicitors, along with the crystal, provide a 360 degree phase shift from the drain to the gate of the FET. The circuit pictured in the schematic below is a Pierce oscillator and relies upon the gate-to-source capacitance of the FET to form part of its phase shift network. If there is not sufficient stray capacitance to ground from the gate of the FET, you may need to add the additional capicitor. VE3EFY reported that his oscillator would not function below 4.5 volts. He used a 9 volt battery to power his unit. The battery should last a long time, he measured the current drain to be 1.8 mA.

Construction

I built this unit "dead-bug" style. Most of the components were mounted and supported by their own leads on the back of the 1000 ohm potentiometer. The RF Choke connected between the output connector and ground was made by winding about 20 turns of 22 guage wire on a 1/8 inch drill bit. The coil was then slid off of the form and wired in place. If you want to use a commercially available coil, a value of 3.3uh should work just fine. That was the value specified in the original article.

I mounted the 150pf capicitor, the 1N914 diode, and the RF Choke on the inside panel of the attenuator box between the two BNC connectors. I also mounted a slide switch between the BNC connectors so I could conserve the batteries when the unit was not being used on a hunt.

Note: The MPF-102 Field Effect Transistor has an unusual pin-out compared to general purpose transistors. The GATE is not the lead in the center. The pin-out for the MOTOROLA MPF-102 is illustrated below. (The Radio-Shack MPF-102 I used had the same pin-out)


MOTOROLA
MPF102
1 DRAIN
3
GATE
2 SOURCE
1
2
3
CASE 29–04, STYLE 5
TO–92 (TO–226AA)

The Schematic


+ 3 Volts
Active Attenuator
6/96 WB2HOL
.047uf
1k
1 Mhz
D
G
S
150pf
MPF102
1.8 Meg
1k
4.7k
Antenna
150pf
1N914
Receiver
RF Choke

The HANDI-Finder®



The HANDI-Finder® is a HANdheld DIrection Finder which can be used to localize both AM and FM carrier-based sources using a single connection to the antenna input of an FM receiver tuned to the frequency of interest in the range of 45 to 450 MHz. It has been designed for bare-bone functionality as well as low power consumption, simplicity, and economy!

Because it is both an easy-to-build kit for the beginner and a convenient basis for further experimentation by those with more experience, it makes a great club project! Overall, it is a quick, inexpensive way to implement the concept of direction finding, and provides something relatively compact to keep readily available for locating sources of interference.

Except for adding a handle, fabrication is minimal. Two open-loop antennas are made from coat hanger wire bent into halves of a "bow-tie" shape and mounted directly to the circuit board, as illustrated in the "layout" drawing.

The coax downlead is connected to an FM receiver and detects the carrier regardless of whether the transmission mode is AM or FM. The unit is switched on (UP) and rotated for a null in the audio tone that it adds to the audio coming out the receiver. The signal direction is perpendicular to the plane of the antennas. There is 180-degree ambiguity, but this is not a problem in actual use because multiple "bearings" must be taken anyway in order to establish a "fix" on the location. Once close in, the operator works toward the general sense of the direction, and again the ambiguity is not a problem.

The 3-position switch is moved DOWN to stop the tone but still keeps the antenna activated for monitoring and standby purposes, --or it is moved to the CENTER position to shut off the unit. Refer to the extensive discussion in the manual which describes construction variations, and the concepts behind the design.

"Build the HANDI-Finder" appeared as an article in QST Magazine, May, 1993. All the information in that article and much more is included here! By clicking on the appropriate boxes in this web page, all the drawings and text that come with the kit can be printed out or downloaded from PDF files.

may be obtained by contacting:

Northern Ohio Amateur Radio Development

P. O. Box 271
Brunswick, OH 44212-0271 USA
Tel: 330-225-7373

The HANDI-Finder® Experimenter’s Kit

by Bob Leskovec, K8DTS

6th Edition,

The HANDI-Finder® is a HANdheld DIrection Finder which can be used to localize both AM and FM sources using only a single connection to the antenna input of a VHF-FM receiver tuned to the frequency of interest.

The basic HANDI-Finder® when equipped with open-loop wire antennas and a short handle, stores flat and ready-for-use in a briefcase. It works well with just an HT (handy-talky).

The HANDI-Finder® has been designed for low power consumption, simplicity, and economy. The goal was to provide an easy-to-build kit for the beginner and a basis for further experimentation by those with more experience. Overall, it is a quick, inexpensive way to introduce users of FM communications equipment to the principle of direction finding and give them something with which they can help locate sources of malicious interference.

A HANDI-Finder® Experimenter’s Kit has been put together to conveniently supply the essential parts necessary to build the control circuit powered by an on-board 9V battery. The user provides the coax, cable connector, and appropriate antennas. By using two open loop antennas made out of coat-hanger wire, the unit can be put into immediate use!

An equally valuable part of the kit is this instruction manual which describes variations in antennas, general construction and detailed discussions of the circuit and components, to encourage experimentation and ideas for improvements.

The HANDI-Finder® first came together in October of 1986, and continued to evolve.   A write-up later appeared in May, 1993 QST Magazine, entitled “Build the HANDI-Finder”.

TECHNICAL OVERVIEW:

The electronic circuit is based on a design credited to Tom Feierabend SO/CM 03N18 circa 1979 which appeared in a manual published in May, 1980 by Van Field, DCP XVIII, entitled “VHF Radio Direction Finding Manual for Coast Guard Auxiliary Use”.

A similar circuit, referred to as the “Double-Ducky” direction finder (DDDF) designed by David Geiser, WA2ANU, is described in July, 1981 QST and reprinted in the 1983 ARRL Antenna Handbook.

The USCG AUX-03N18 version uses an LM555 driving two successive stages of 7404 TTL to provide complementary buffered outputs. Since TTL requires a 5-volt power supply, yet another IC, a 7805 or 78L05 is needed, to regulate the stated 6-30 volt input range.

One problem is that the LM555 does not easily put out a symmetrical square waveform, which is useful in this application. The antenna assembly consists of two vertical ½-wave dipoles (37” long) mounted 8” apart on a boom. This assembly is rather bulky and quite a bit of mechanical fabrication is required.

The QST circuit uses only one IC, the LM567 Phase-Locked-Loop Tone Decoder. This is a complex chip that contains an oscillator and other circuitry, including an output circuit which does put out a symmetrical square wave. However it does not have simultaneous complementary outputs. In the DDDF the single output is connected to the diode switches through a non-polar capacitor, and some adjustment is required to achieve the proper switching level. Data sheet specifications show that the LM567C typically draws 12mA. The antenna assembly consists of two “rubber duckies” mounted 10” apart on a 4.25” X 18.5” ground-plane. While the ground plane requires much less work to fabricate than the USCG-AUX circuit, two “rubber duckies” must be obtained.

The HANDI-Finder® is a good example of integrated simplicity, wherein one simplification contributes to another.

First, it uses a single CD4047B CMOS IC, which contains both an oscillator and a divider flip-flop to automatically provide complementary symmetrical square wave outputs without special adjustments. Only a single resistor and capacitor are needed to set the frequency. While many have not heard of this IC, it continues to be available from standard suppliers like Digi-Key, Mouser, and Jameco.

Second, very little current is used to bias the switching diodes so the total current draw is only 1.7mA at 9V. Good service can therefore be provided by a common alkaline “transistor radio battery” and there is no need for wiring to an external source such as a 12V vehicular supply. This, in turn, eliminates the need for noise filtering. The operation of the circuit is not dependent on battery voltage, so a regulator is not required. Supply voltage for the CD4047 can be anywhere from 3-18 volts. Finally, since all the parts, including the battery are mounted on a single circuit board, the board is designed to also serve as the mounting base for the two open-loop antenna elements easily made out of bent wire. Thus, there are no ground-plane or vertical dipole elements to make, nor “rubber duckies” to buy, and no case to drill, until later if you really want to!

HOW IT WORKS:

All three circuits described above are based on the same principle. An electronic switch alternately connects two antennas to the coax cable downlead going to the antenna input of an FM radio receiver tuned to the frequency of interest. First one antenna is connected, then the other, etc., back and forth with equal intervals. This is done at an audio rate, well within the audio bandpass of the receiver, and usually in the range of 400 to 1500 Hz. A good frequency is 1000Hz.

Of the two antennas, if one is slightly closer to the source, it receives the wave front slightly earlier in time (phase) than the other. There is a phase difference in the signal received by one antenna compared to the other. Since the receiver is being switched between the two antennas, the switching action imposes phase modulation on the incoming signal. This is detected in the FM receiver and is heard at the audio output as a tone equal to the switching frequency. The amplitude of the audio signal corresponds to the deviation, which depends on the physical separation of the two antenna elements, up to ½ wavelength. In other words, if the antennas are farther apart the circuit will impose a higher percentage of modulation or a larger deviation, producing a louder tone, but the modulating frequency will stay the same.

If the antenna is rotated so that the plane of the two elements is perpendicular or broadside to the direction of the signal, both elements receive the signal at the same time (phase) and there is no longer a difference in phase. Hence, the audio tone disappears. This is perceived as a rather sharp null in the audio as the antenna array is rotated into position perpendicular to the direction of the signal.

This type of direction finder has the disadvantage that it exhibits 180-degree ambiguity. However, it has several advantages:

1) It works on a nulling principle rather than a peaking principle. The null is sharp and much easier to detect than the peak from a directional or beam antenna.

2) When you null the superimposed audio, you are not nulling the carrier. This is unlike a conventional loop antenna or cardioid array, which nulls out the carrier. The problem with carrier-null, is that as you get closer to the null, the signal you are trying to hear in order to null out, is getting harder to hear! Also, when you null the superimposed audio, you can still hear the audio coming from the source.

3) Since audio is being nulled, the operator does not have to watch a field-strength meter. He only needs to listen, which is something he can do while driving, riding a bike or walking.

4) Since this method uses phase information, it works well with strong signals, so no attenuator is required. (By comparison, the signal from directional gain antennas must be progressively attenuated to keep the receiver RF within the range of the S-meter.)

REFERENCE INFORMATION:

The HANDI-Finder® is an evolving project which underwent several changes (hopefully for the better) during the early stages. However, the basic circuit remains essentially the same. This manual might be supplied to help you work on an earlier unit, as far back as 1986. If you have a model that does not correspond to the pictorial description in this document, you should be able to identify the components with only minimal tracing of the etched circuit pattern.

Your unit may also have component values that differ from the schematic. If you did not buy a kit, you may have obtained the circuit board and documentation from separate sources that copy and distribute such things and try to make them “public domain”.

The circuit board versions are identified by a prefix letter “A”, a 6-digit date code (YYMMDD), and an optional suffix. (The suffix, if present, indicates very minor changes.) As of this writing, the numbers used are: A861003, A860102, A870122, A890422, A01110, and A031123.

In general, if the board has a date code earlier than the documentation, the component values in the documentation take precedence, provided the integrated circuit type is pin-compatible. If the board has a date code later than the documentation, and/or a different IC pinout, you would do well to send a self-addressed-stamped-envelope (SASE) to the distributor for an update of the layout and parts list. Of course, be sure to furnish the number on your board, so you will be sent the correct information. Please indicate whether the RALTEC® or other trademark is present and we will help you figure it out. Try contacting the author at ral@ralserve.net. (If you have trouble, you can also find the author’s current snail mail and e-mail addresses through the internet Ham-Call database.) For information, try the website handi-finder.com.

CHECKING THE COMPONENTS

If you received this instruction manual as part of a packaged kit along with the circuit board and loose components, unpack all the parts and check the quantities and values against the Component Parts List before you do anything else because some parts have the same value but different mounting positions and lead lengths. Before proceeding with actual construction, it is suggested that you read this manual to see if there are any changes you would rather incorporate right away. Then proceed with "ASSEMBLING THE KIT" which is located at then end of this discussion.

NO PILOT LIGHT:

Considering that a small transistor radio draws about 10mA, it can be seen that the battery will last quite a while if the user remembers to turn it off. Unfortunately a pilot light would be self-defeating, since it would draw 5-10 times the current of the circuit itself!

How many times have you forgotten to turn of your HT? After a while you finally learn to double check. With the HANDI-Finder® it should even be a little easier, because you will probably be disconnecting it from your radio or otherwise storing it at the end of a "DF'ing" session. That action should help remind you to check that the switch is off. Better yet, remove the battery. That's why we have included a top grade battery holder in the bare board version.

ON-OFF SWITCH STATUS INDICATOR:

For models prior to A890422, here are a couple of things to help you tell OFF from ON in the absence of a pilot light. First, the "ON is UP" convention has been followed. This is fairly commonplace on most equipment. Second, you can make a "passive" indicator by using a dot of bright paint, for example, typewriter correction fluid such as "whiteout". Push the slider to the ON position, then paint a small dot on the lower part of the slider that is now exposed. Let the paint dry thoroughly so it doesn't rub off. When you slide the switch to OFF, the painted part should be hidden; when ON, it should be visible. On Model A890422 and later the switch has 3-positions: OFF is in the center, UP is for DF'ing, and DOWN is for straight receiving or Standby. (Notice the design date is embedded in this code as YYMMDD.)

ON-OFF SWITCH MECHANICAL VARIATION:

There are a couple of subminiature slide switches available from "experimenter" sources such as Mouser and Digi-Key, but they differ slightly in the spacing and style of the connector pins. Circuit boards A861003 and A860102 used the CW Industries switch available from Digi-Key as SW103-ND.

Starting with circuit board A870122, the switch pads were made larger and the spacing changed to use the Mouser 10SM007 or 10SP001. The larger pads allow larger holes to be drilled to allow for the wider flat pins. If the switch you have does not go right in, do not force it. Study the problem and carefully enlarge the holes only where necessary. A small modeling file is handy for this purpose. Don't make the holes any larger than necessary, or you will have trouble bridging the gap and getting a good flow joint when soldering. When you do solder it into position, use ample solder and heat it enough so the solder surrounding each terminal flows evenly into a nice even form similar to an "Indian tepee." A890422 and later use a DP3T switch with 6 pins, which will not fit the previous models, but that gave the ability to add the "standby" position which is very useful.

BATTERY HOLDER:

The 9-volt battery holder is fastened at one end by soldering the two terminal tabs that pass through the board. The other end of the frame can best be fastened by using 1/8” diameter “pop-rivets”, but you may alternatively try hot-melt glue, epoxy, small screws, etc. However, make sure that whatever you use won’t protrude and prevent the battery from seating in the clip.

QUICK HANDLE:

The bottom area of the circuit board contains an area where the handle is attached. The unit can be mounted on either a short handle or directly to a mast, whatever you desire. To get going quickly, take any convenient piece of wood or metal, lay the end against the board, mark the holes, drill them through the handle, and attach with screws. If you use a round handle, you will either have to make a flat cutout along one side, or cut a slot in the end so that the board can slide in. A round handle is best. The most utilitarian handle is described next. .

PAINT-ROLLER HANDLE:

Find an inexpensive paint roller, but one with a handle which is threaded for an extension pole. (Home supply stores sell them typically for $1.39). Study how the handle is attached and determine the best way to remove it or otherwise adapt it so the HANDI-Finder® can be mounted on it.

Most of the handles available these days are plastic, force-fit directly to the metal roller rod. Use a hacksaw and cut off the roller assembly rod so that about 3” of rod is left protruding from the handle. File the rod enough to have a flat area, center punch, then drill two #6 holes to match up with the circuit board, and attach. The flat side should of course go against the board.

Next, shop around for your choice of a wood or metal paint roller extension pole, preferably the type which is made of 3 sections which screw together. You will thus have a very flexible system. You can use the unit with just the handle alone, or screw on up to three lengths of additional “mast”. You may even wish to obtain a second extension to have more lengths available. Be aware that some extension handles have different threads in the sections than they have at the roller end. In any event, the pieces are easily stored when disassembled.

UTILITY-DUSTER HANDLE:

There is a homemaker’s utility duster on the market called a WEBSTER® which can be found for as little as $4 in discount stores. Unfortunately, only a small percentage of stores seem to stock it. However, this is an amazing value for our purposes because it contains not only a 6-inch detachable handle, but includes a removable, telescoping, extension pole!

The dusting head consists of an 8-inch diameter half-spherical array of bristles embedded in the end of the short handle. This end is easily sawed off to allow for the HANDI-Finder®. The extension pole is about 36” in the collapsed position and 60” when extended.

HANDLE, CAUTIONARY NOTE:

Mount the handle against the component side and put the screws through with the heads on the solder side, to keep a low profile for the coax cable which will come down the solder side

The HANDI-Finder® works best when the first ¼ wavelength of coaxial cable downlead to the receiver is kept vertical or parallel to the center line of the circuit board. (Measure the ¼-wave from the bottom antenna terminal.) If it waves around, it can throw off the bearing. Therefore, when using the unit with a short handle, make sure to hold it straight and high so that the cable hangs straight down. When using the unit with a long handle it is preferable to attach the coax to the mast for the first ¼ wavelength. Use tape, nylon cable ties, etc.

RESISTORS vs. INDUCTORS:

The HANDI-Finder® was designed mainly out of the need to inexpensively provide Radio Amateurs with something they could use to help locate interference on the 2-meter repeaters. But the unit operates over a much wider range of frequencies because the chokes "traditionally" used in such RF circuits have been replaced by resistors.

Inductors are usually used to feed direct current into some point in a circuit where it is desired to allow an alternating current signal to pass without attenuation. At radio frequencies these are called "RF chokes". Circuits which operate in the 150MHz range, for example, usually use small coils with a value of 1.0 to 1.2 microHenries. Using the expression Xc = 2(3.14)fL, where "f" is the frequency in MHz and L is the inductance in microHenries, the corresponding reactance works out to about 1000 Ohms. At 1/3 the frequency, or 50 Mhz, this same inductor would have a reactance of only 333 Ohms. At UHF this inductance would mathematically exhibit a proportionately higher reactance, but other difficulties arise. Certain assumptions about the construction of the coil are no longer valid and the math becomes more complicated. Factors like the "capacitance between turns" and the length of the connecting leads can no longer be ignored. At some frequencies the coil looks like a high impedance, but at others it may look like a short circuit!

Thus, the frequency band over which the circuit can operate is limited by the chokes. Different sets have to be installed to operate over different ranges of frequencies. Normally it is necessary to use chokes because they have a comparatively low resistance at d.c. so there won't be any significant voltage drop. The key word here is "significant".

In this circuit, the switching diodes are biased by current. As long as enough current is supplied to do the job, it doesn't matter if a little voltage drop occurs across the connecting element. The chokes can simply be replaced by 1000 Ohm resistors. The currents are so small that the voltage drop is negligible. Further, for all the complications involved with determining how chokes will act at different frequencies, it is no less risky, and a great deal easier, to assume that a resistor will exhibit the same resistance over a much wider frequency range.

In this circuit R4, R5, and R6 would have "traditionally" been specified as 1.0uH chokes for operation in the 150 MHz region. As you can see, by using 1K resistors, operation at 150 MHz should not be affected, and operation over a wider range of frequencies should now be possible. The value of the resistors is not that critical. Values in the range of 1K-1.3K will do, but make them all the same value. Using carbon-film resistors, we also get some useful inductance, but since the resistance is high and distributed with resistance, these are inherently free of self resonance, and broadband becaue they are low Q.

However, if you wish to experiment with inductors, you can either make them or buy them. According to the USCG AUX article, you can make these with one layer of #28 close wound on a 1 Meg ½-watt carbon composition resistor. Actually there is nothing magical about the 1 Meg value, it is the physical size and shape that is more important. The intention is that the resistance be at least a factor of 100 times greater than the inductive reactance. Therefore any value above 100k is acceptable.

Mouser Electronics has a line of good quality subminiature RF chokes that are quite reasonably priced, roughly $.23 each. Consult their catalog for the "43LQ" series. The 1uH value is part number 43LQ106. Keep in mind they probably will not fit on the HANDI-Finder circuit board supplied with the kit.

WIDEBAND OPERATION:

The HANDI-Finder® should work over a wider range when resistors are used in place of inductors, but there will still be problems with resonances (series LC) and anti-resonances (parallel LC) for any given set of antennas. However, ignoring those effects, let us discuss the effect of antenna spacing. Remember, you want the vertical members of the two antennas as far apart as practical to get maximum modulation.

This will make it easier to tune for a null.

For a given set of antennas, the upper frequency limit should be that which corresponds to a ½ wavelength equal to the widest spacing of the vertical members.

If the usual wavelength formula is multiplied by 12 inches/ft, a new "constant" factor is obtained: dividing 5616 by the frequency in MHz will give the ½ wavelength in inches. For the open-loop antennas you will be instructed to make elsewhere in this manual, the spacing between opposing vertical sections is typically 17.5 inches. Turning our formula around, and dividing 5616 by 17.5 gives 321 MHz, which is also the frequency at which maximum deviation would be available. Some have reported operation to include the 70cm Ham Band.

Moving to 1/10 that frequency or 32 MHz, only 1/10 the modulation would be available, but the units should still function. So it would appear that operation over a 10:1 range might be possible.

COUPLING CAPACITORS:

At the lowest limit, it is important that the coupling capacitors have a reactance of 50 Ohms or less so as not to attenuate the signal by more than 3dB. If we choose that limit to be 27MHz the value of capacitance having 50-Ohm reactance is 117pF. Values of .001uF, or 1000pf will be one tenth that or 5 Ohms, and work just fine.

SCREW TERMINALS:

Antenna connections to the board are made using screw terminals. On early units, these are formed by installing a clip-type "tinnerman nut" which is slipped onto the circuit board edge at each designated point, and then threading in a 6-32 x 3/8" or ½" binder head machine screw. Only four are needed for any given configuration. Later units use regular hex nuts, serrated lock washers, and flat washers against the board to keep the lock washers from tearing up the copper foil.

When fastening small diameter or stranded wires to these, it is suggested that you first install crimp-on spade lugs or ring lugs on the end of the wire. If you must wrap the wire around the screw, do it under a washer and wrap it in the direction that the screw tightens (clockwise).

BE CAREFUL NOT TO OVERTIGHTEN. If you experiment a lot, the tinnerman nuts will strip and wear out. If you need to have things very tight, you can use 6-32 screws with regular hex nuts. However, do not put serrated lock washers against the surface of the board since they really dig in and cause problems. It is better to use a slightly longer screw with flat washers to protect the surfaces. If you are tempted to just solder directly to the board, don't do it! The heavy heat may cause the foil to delaminate. Further, if the antennas are bumped, the foil may be pulled off the board. If you want to have some sort of "rounded off" nut on the thread end, inquire about "acorn nuts" in the screw specialty section of most hardware stores.

ANTENNAS:

The HANDI-Finder® is quite versatile in the way it can be used with different kinds of antennas. First of all, you can get it running immediately without extensive fabrication because two simple wire antennas can be attached directly at the circuit board. For 150 MHz, take two EQUAL lengths of stiff wire about 19 to 20 inches long and bend each one into a neat square "U" shape. The bottom of the "U" should be about 6". Form the ends into a hook and fasten them to the screw terminals on the circuit board. Looking at the component side of the board, you will see there are three terminals along the left side and three along the right side. Fasten one end of one antenna to the very top terminal on the right side. Fasten the other end of that same antenna to very bottom terminal on the same side. Then repeat this procedure for the left side.

Note that the bottom terminals are merely mounting points. They are electrically isolated. On some board designs there are circuit pads to allow installation of a grounding jumper. DO NOT INSTALL THIS JUMPER! It is desired that the antennas be open loops. If you ground the bottom of the loop, you will create a closed loop that will cause a carrier null in the direction of the signal. This is not desirable. On later circuit boards provisions for grounding was eliminated to avoid confusion.

The wire you use should be thick enough to provide desired rigidity, but thin enough to allow fastening under the screw terminals. If it is too thick, you might be better to first solder on some spade lugs or similar terminations. Of course, it helps if the wire is a good conductor, but steel coat-hanger wire or welding rod will work satisfactorily. A better choice would be brass rod or brazing rod, between 1/16" to 3/32" thick. If you wish, you can make the loops even larger.

Note the ACTIVE ELEMENT of each antenna in this application is the vertical part of the open loop supported in space by the horizontal part. A greater separation of the vertical elements will produce a larger deviation and more audio. However, the longer a vertical element is, the more signal it will receive, provided there isn't some gross impedance mismatch. This shows up as more carrier, better quieting, or a stronger S-meter reading. Of course, when that vertical section is maintained in space by an unshielded horizontal section, determining the resonance or tuning gets very complicated. Also consider that the horizontal part does receive some signal, and this degrades the intended signal. Therefor, larger loops may work worse. Feel free to experiment; that is the whole object of this project!

Alternatively, the circuit board is designed to accommodate connections by coax cable to other kinds of antenna arrays. Just below the top antenna mounting screw on each side, is a ground screw. This is not used with the open loop antennas, but is used for the coax shield. Thus, if you do wish to make a "Double-Ducky" direction finder as described in the ARRL Antenna Handbook, you can connect the two equal-length coax cables to the HANDI-Finder® circuit board. Similarly, you can fabricate the dual half-wave vertical dipole array described in the Coast Guard Auxiliary Manual and run it with the HANDI-Finder® board.

One suggestion for a more extravagant system is to position two multi-element Yagi antennas with vertical orientation at opposite ends of a horizontal boom. Support the boom at its center on a vertical mast so that it can be rotated. Use equal lengths of coax from each beam and connect them to the HANDI-Finder® board which should be mounted in a protective enclosure at the center of the boom. The beams will give greater forward gain and reduce the 180-degree ambiguity. It is just a little hard to use with the mobile!

Since the antennas have no path to ground, there is no need for DC blocking capacitors. On A890422, the positions of C6 and C7 are jumpered out with board foils. If an application is encountered which requires DC blocking, slit each foil at each end carefully with a sharp hobby knife, then heat the center section with a soldering iron and peel it off the board with the knife. Holes are provided to install the capacitors. Refer to parts list. Later boards don't have this connection, and come with capacitors. Check the board. If you don't have the capacitors, then be sure to insert some jumpers.

NO ENCLOSURE

As you can now appreciate from these discussions, there are many ways you may end up using the circuit board and enclose it accordingly.

In its simplest "quick & dirty" constructed form, the unit can be put to immediate use. The long narrow profile was purposely selected to minimize wind resistance for the benefit of a vehicle operator who may be trying to hold on to the unit mounted on a narrow mast protruding through the drivers window.

You will discover that an enclosure will only increase the drag and may not be worth the effort! With only minimal care, these units have rattled around in many trunks and back seats without anything getting shorted out. The battery in one of the demo lasted over three years, even though it had been left "ON" for several weekends during that time!

However, you might want to consider that numerous sharp edges from component leads could snag cloth upholstery, or scratch leather and vinyl.

Where you really need to, the circuit board can be mounted to surfaces on standoffs using 6-32 screws through existing holes.

MOUNTING IN AN ENCLOSURE:

Model A890422 and later are designed so that it can be more easily modified to fit into a case. This is somewhat irreversible since it requires that the bottom part of the board be cut off, unless you can find a really long, flat plastic case. Some have come and gone off the market, so it is there is no particular model case that can be recommended. It is strongly suggested that the circuit be completely built up on the existing board and thoroughly checked out. After you are familiar with the unit's operation, you may NOT wish to put it in a case.

TRYING IT OUT:

It is best to start off with a "test" situation where you know the location of the source, and experiment with "getting a feel" for the null. The null itself is fairly sharp, but it does not always manifest itself as a total null in the audio tone. Sometimes, you will observe instead, a jump in tone one octave up or down. (Refer to the ARRL Antenna Handbook article for more discussion.)

At other times, you may hear a "buzz" or a fast "twiddle". This is usually due to multipath, so moving just a few feet may help clear up the null. Also, if there is a strong transmitter in the area, such as a 1kw paging system, 3 or 4 MHz away, you may experience more "de-sense" than normal when the HANDI-Finder® is switched on in the DF-ing mode. The sharp edges of the diode switching waveform cause it to be rich in harmonics, all of which modulate that strong RF source and cause it to broaden its normal spectrum at the input of your receiver. (These are the same problems that bother the more complex "DOPSCANs" that switch 4 or 8 antennas.)

Using the unit with a synthesized scanner or one of the new extended-coverage HT's will not only allow you to work in the Ham bands, but other frequencies as well. The prototypes were tried over the range of 49 MHz to 450 MHz and worked well even though the 450 MHz test was well above the suspected ½-wave limit frequency of 321 MHz calculated previously. As you get considerably above or below the 150 MHz design frequency you may find that your unit has a "null" point which is no longer perpendicular to the plane of the circuit board. However this also sometimes occurs due to multi-path in high reflection areas, especially indoors. (Don't try to do anything meaningful indoors!) In any event, don't jump to conclusions. Take several measurements at different locations a few feet apart, and consider your findings carefully before deciding whether the problem is due to the location or a characteristic of the way you have set up your particular unit.

When driving through neighborhoods it is interesting to scan the bands and see what sort of frequencies are in use. For example, one of our experimenters found several homes with 49 MHz "baby monitor" intercoms. You may also hear cordless phones near that frequency.

Another application is to drive around and look for Cable-TV leakage on 145.250 MHz. You will quite easily pinpoint hotspots on poles and at the lawn boxes used for underground installations.

Perhaps you can promote some Ham Radio good will by helping local law enforcement officials find mobiles with "stuck mikes." Such a "free" service can help educate personnel about Amateur Radio and keep you from getting "pulled over" when you are out hunting.

If you are an avid radio-controlled model airplane enthusiast, and have had a plane get away from you and get lost in the woods, this could save you time. Put a low-power transmitter and "crash switch" in your plane. Then if it gets away or crashes in the woods, you can track it down!

Some areas have rather extensive park reserves or other situations where naturalists "tag" wild animals with radio transmitters to track their migration.

They are quite interested in reports on these animals, and will give out the frequencies to individuals with a genuine interest in helping. Invite your local naturalist to speak to your club and demonstrate how you can help. But keep in mind they DO NOT put radio collars on deer and turkey just to make it easy for game hunters to track and kill them!

CHECKING DIRECTION CALIBRATION:

A round handle is best, because it allows a calibration mark at any angle. You would do well to try your unit outdoors in an open field by walking in a circle around a central source. A person keying an HT held up at arm's reach is easiest, but caution him to hold still. The null should always occur perpendicular to the plane of the antennas, but your radio or other factors may be introducing phase shift. If the error is totally consistent as you walk around the circle, then you will want to mark the true direction on the handle.

If such is the case, expect this calibration to change at different RF frequencies, or if you change the CD4047 oscillator frequency. If the error is not consistent, and changes as you walk around the source, you are experiencing (multi-path) reflections from the surroundings. Try reducing the power of the source. For example, if a 100 mW HT is too strong, remove the antenna and substitute a 51 Ohm, 2 watt carbon resistor. If you still get erratic readings you will have to go to another location.

Once you have established the calibration mark, fasten the cable along the side of the handle or mast so it runs over the mark. That way you can feel it in the dark. Now you are ready to do some serious DF-ing or Fox Hunting.

Notes:

1. The abbreviation "uF" is used throughout this text to denote "micro-Farads".

2. Bob Leskovec, K8DTS, has been licensed since 1957 and promises not to change his call letters so you can always locate his mailing address via the Ham database!

3. A less detailed description of this project appeared as "Build the HANDI-Finder!" QST Magazine, May, 1993.

4. HANDI-Finder® and RALTEC® are Registered Trademarks.

The HANDI-Finder® Experimenter's Kit

ASSEMBLING THE KIT: (Please read the whole manual before assembling)

1) Check the circuit board and make sure all the holes are drilled and it is otherwise finished and ready to accept the parts.

2) Having read the discussions about the ON/OFF switch, locate that item and make sure that the type you have does indeed fit the hole pattern on the circuit board. Do not install it yet.

3) Locate the integrated circuit socket, carefully straighten the pins, and insert it onto the component side of the board with the proper orientation. You may have to study the IC socket to determine how its design denotes the position of pin 1. Some sockets have a beveled corner at pin 1. Others have an indentation at the end between pins 1 & 14, some are not clear!

Note, for packing purposes, the IC may have been installed in the socket. It is NOT necessary to remove it, unless you can see it has been inserted in the socket incorrectly. The IC will incur much less handling and there will be less chance of damaging it if you just leave it in place when you solder the socket onto the board. Make sure the socket is properly oriented and seated flat against the board when you do the final soldering.

4) In the following order, mount the diodes, resistors, and capacitors, starting with the smallest parts first. If you have only one capacitor with long leads, SAVE that, and use the precut ones first. There is one location that needs the capacitor to be formed with longer leads.

5) Examine the ON/OFF switch and make sure that the terminals are clean and not tarnished, before soldering. If needed, carefully scrape them with a small hobby blade. Then mount the switch and solder it in position. The 6-pin switch also requires that the two diagonal frame tabs be soldered as well. NOTE: if you later use a solvent to remove flux from the board, be especially careful not to get any into the switch. Some literally melt. Some have four frame mounting pins. Carefully clip off only the two diagonal pins that prevent insertion.

6) Refer back to the discussion about the battery holder and mount that item.

7) Prepare the end of a length of RG-58/U or the miniature RG-174/U and attach it to the board. Note that the hole for the shield should be 1/8” so that the shield can fit through. The excess braid is cut off so that only about 3/16” lies flat against the circuit foil where it is soldered down. Install a nylon cable tie through the holes provided in the circuit board. Pull it tight so that it anchors the coax securely against the board to prevent flexing at the cable end. This is known as a “strain relief.” Clip off the excess. Depending on what type of handle you use, you will need to figure out how to route the coax so that it crosses to the center and comes down the handle equidistant from the two antennas for best symmetry. Later circuit board layouts have the coax routed down the centerline in the solder side of the board on the side opposite where the handles should be attached.

8) Slide on “tinnerman” nuts (if such nuts have been supplied) at the four points used to attach the open loop antennas. These are the two top-most and two bottom-most locations.

9) Fashion two open-loop antennas according to the instructions described previously and attach them to the board using the 6-32 x ½” screw hardware. That’s it! Refer to the section “TRYING IT OUT”.

The manual includes discussions of several other options and variations in the way the unit can be wired.



Print: A-Size, 1:00/Rotate

The HANDI-Finder™ is a Handheld Direction Finder which can be used to localize both AM and FM carrier-based sources using a single connection to the antenna input of an FM receiver tuned to a frequency of interest in the range of 45 to 470 MHz.

(Alternate Labels, D1=D3, D2=D4 on PC Board)

Coax connects to more complex type of antennas.

A HANDI-Finder™ Experimenter's Kit is available which includes the circuit board and components, with an extensive manual discussing antenna variations and DF-ing tips.

The quick-build kit uses open-loop wire antennas, instead of coax shown.

The CD4047 has been a standard component since the early days of CMOS and continues to be available from hobby and industrial sources.

Details at: www.handi-finder.com

Tone Freq.	R1	C1
400Hz	10K	.056uF
1000Hz	10K	.02 uF
1200Hz	47K	.01uF

3-Position Slide Switch
UP= D.F. Tone ON
Center = OFF
DOWN = ON Standby

Copyright 2005, 2006 RALTEC Consulting Services

Title	HANDI-Finder™	
Size A	Number HF2SCH01.S01	Rev
Date 2006 JAN 03		Drawn by LESKOVEC
Filename HF2SCH01.S01		Sheet 1 of 1

HANDI-Finder™ Functional Symmetrical Schematic

A
B
C
D
1
2
3
4
COAX TO ANTENNA
COAX TO FM RECEIVER (route down centerline)
COAX TO ANTENNA
C7 .001uF
C5 .001uF
C6 .001uF
D2(D4)
D1(D3)
1N4148
1N4148
R5 1K
R6 1K
R4 1K
C4 .001uF
R3 10K
C2 .001uF
R2 10K
C3 .001uF
U1
CD4047HF
VCC
OSC
RTRG
Q̄
Q
CLR
T
C
R
RC
Ā
A
GND
1
2
3
4
5
6
7
8
9
10
11
12
13
14
R1 10K
C1 .01uF
9V Battery
(Unit draws 1.7mA)
+
−

Sense The Right Way To Go With The HANDI-Finder®

by Joe Moell K0OV
ARRL Technical Advisor

The following was submitted to the Technical Correspondence column in QST Magazine for October 1993 in response to the HANDI-Finder construction project in a previous QST issue. The original HANDI-Finder was created by Bob Leskovec K8DTS. It is documented at the HANDI-Finder Web site. A kit of parts is sold by the North Olmsted Amateur Radio Depot. "Clones" of the bow-tie bidirectional HANDI-Finder are being or have been offered for sale by some other companies and individuals. The K0OV unidirectional pattern modification and antenna improvements described below are applicable to all of these bow-tie sets.

Hats off to QST for its recent promotion of foxhunting and radio direction finding (RDF) activities. Simple RDF gear in the hands of a large number of hams will provide important preparedness for emergency searches and malicious interference location.

The HANDI-Finder® by K8DTS[1] holds promise for this purpose, but its bidirectional peaks and nulls limit it to short range "sniffing" in situations where time-to-locate is of little concern. Its 180-degree ambiguity makes it unsuitable for long-range or high-speed work.

If you were shopping for a compass to use on a hike, what would you think of one with an indicator that points either north or south, with no way of determining which? You probably wouldn't buy it, even if it was priced much lower than other compasses in the store. It's the same way with foxhunt equipment.

A bidirectional RDF set such as the basic HANDI-Finder presents a 50-50 chance of leading you away from the fox instead of toward it. So it's worthwhile only for occasions when boundaries are small, such as on-foot foxhunts in a small park. Fortunately, it's a simple matter to incorporate a second mode into your HANDI-Finder to resolve the ambiguity.



In this view looking down from the sky, the bidirectional HANDI-Finder unit (a) has two nulls, each perpendicular to the plane of the antennas. The added sense mode (b) has a single null on the Antenna #1 side.

Add a Sense Mode



By adding time delay to the signal from one of the two HANDI-Finder antennas, the peak/null tone pattern of the unit is modified. If you add just the right amount of delay, the pattern changes from bidirectional (figure-8) with nulls perpendicular to the antenna plane to cardioid (heart-shaped) with a single null off one end.

This two-pattern technique forms the basis of the Handy Tracker, a RDF unit that I designed in 1989.[2] The cardioid pattern concept came from an unpublished 1980 project by Russ Andrews K6BMG. The Handy Tracker sense mode scheme can be applied to the K8DTS HANDI-Finder with the simple addition of a switch and a length of coaxial cable to provide delay.

As K8DTS points out, the bidirectional HANDI-Finder indication is independent of frequency. This is not true of the added sense mode. A delay line of a given length produces a precise cardioid pattern at only one frequency. A useful pattern is obtained over a frequency range of several per cent, however, so one delay line will provide ambiguity resolution over one full VHF amateur band.

Modification Details

The modification adds a DPDT micro-mini toggle switch without center-off (Radio Shack 275-626) and a precisely trimmed coax delay line. Mount the switch in the etch-free area of the circuit board between the two antennas.

On the rear side, cut the traces where C6 and C7 connect to the antenna terminals per the drawing. On the Antenna #2 side, wire the antenna connection through the switch per the schematic. On the Antenna #1 side, install an unshielded wire jumper 1-3/4 inches long, to compensate for the added switch wiring on the Antenna #2 side. This jumper is important, since one inch of difference in feed length to one antenna will cause 6.5 degrees bearing error in the figure-8 mode.



Rear view of modified board showing trace cuts and added switch wiring. Note loop of wire on left; this compensates for switch-lead lengths that would otherwise unbalance the system.

Cut the delay line according to the following formula:

$$l = (11808-df)v/f$$

where l = length of coax in inches, v = velocity factor of coax as a fraction, f = frequency in MHz, and d = spacing between the vertical antennas in inches. For example, assume we are adding the sense mode to a HANDI-Finder with "bow tie" open loop antennas for two meters. The vertical sections of the two loops are 15 inches apart. We are using RG-174 coax, which has velocity factor of 65.9 per cent. Computed for the center of the band (146 MHz), delay line length is

$$(11808-(15)(146))(0.659)/146 = 43.4 \text{ inches.}$$



Partial HANDI-Finder schematic showing added jumper, toggle switch S2 and delay line to provide cardioid sense mode.

Coil up the coax and lace it to the board. Miniature coax such as RG-174 is best for the delay line because it makes a compact coil. Whatever coax you use, make sure to determine its characteristic velocity factor. It is different for foam and non-foam type cables.

Because of environmental multipath and stray coupling, a perfect cardioid tone pattern may not be achieved. The end null may not be complete or there may be a double null on one end. This doesn't matter, because the purpose of the sense mode is merely to determine which of the two figure-8 nulls to follow. There is plenty of peak/null amplitude difference for that.

Getting RDF bearings with the modified HANDI-Finder is a simple two-step process. In a clear location, with S2 set for normal (bidirectional) mode, listen for the tone nulls in the receiver to obtain a line of bearing as described by K8DTS. Next, switch S2 to the cardioid pattern mode and turn the unit 90 degrees so that one end points along your line of bearing. Note the tone level. Rotate the unit 180 degrees and note the tone level again. It should be distinctly different. The lower amplitude tone will occur when Antenna #1 is closest to the signal source. To help you remember, mark the peak/null directions on the board.

Other Observations

In the K8DTS QST article photo, the receiver feedline passes over the open end of one antenna loop. This unbalances the antenna pair and can cause major bearing errors on two meters and above. The coax should be routed away from the loop.

The horizontal sections of the bow tie antennas severely degrade RDF performance. Properly spaced coax-fed vertical dipoles are far better for serious use with this type of RDF set. Such an antenna set is easy to make with inexpensive whip antennas and PVC plumbing parts.


Two dipoles spaced λ/2 max
Electronics connected to dipoles with equal length coaxes

Dual vertical antennas fed with equal-length coax lines provide the best performance with switched-antenna RDF sets.

The two antennas should be spaced as widely as possible for maximum audible df tone, but spacing must not exceed one half free-space wavelength at the receiving frequency. Approximately 24 inch spacing is practical for both two meters and 125 cm. Coax cables from the HANDI-Finder board to each of the two vertical dipoles must be exactly equal in length.

Wide antenna spacing gives better performance, but it may increase the received tone deviation to the point that the receiver "squelches out." If this occurs, reduce the tone oscillator frequency to 400 Hz or lower by increasing the value of R1 and/or C1.

Footnotes:

[1] Leskovec, "Build the HANDI-Finder!" QST, May 1993, pp 35-38.

[2] Moell, "Homing In," 73 Amateur Radio, September 1989, pp 58-59 and November 1989, pp 52-53.

The spelling and form of HANDI-Finder constitutes a trademark registered to K8DTS.



The added coax delay line is tied to the rear of the circuit board.



Close-up of top area of board, showing added DPST switch and wire jumper to provide equal signal paths in bidirectional mode.

Frequently Asked Questions and Answers About T-hunting and RDF

by Joe Moell KØOV

Over 98% of reader response to my articles is via e-mail. The 80-20 rule (or is it 90-10?) definitely applies, because the vast majority of questions are the same. Here they are, along with the answers. Now maybe I can spend more time building and T-hunting!

- Part 1 - Questions about Dopplers (scroll down)
- Part 2 - Questions about Other RDF Equipment
- Part 3 - Questions About Transmitters and and Covert Tracking
- Part 4 - Miscellaneous Questions

Part 1 - Questions About Dopplers

Q: What is a Doppler? What is a Roanoke Doppler?

A: Nineteenth Century physicist Christian Doppler is credited with creating equations that describe the apparent frequency shifts that result from the relative motion of the sender and receiver of a wave. The Doppler principle is now used for many applications, including dating the universe and catching highway speeders. In radio direction finding, a simulated rotating antenna can be used to determine the direction of an incoming signal using this principle.

When transmitter hunters speak of Dopplers, they usually mean a device with an electronically rotating array of 3 to 8 vertically oriented whips or dipoles and a circular display of 8 to 50 light-emitting diodes. These Doppler add-ons work with VHF and UHF narrowband FM receivers. There are other RDF devices with similar antenna sets and displays that are used with AM receivers (e.g Watson-Watt), but these are not Doppler sets.

The Roanoke Doppler was first published in my book "TRANSMITTER HUNTING---Radio Direction Finding Simplified" (THRDFS), along with an extensive writeup of the theory of operation. The Roanoke Doppler has become the most popular Doppler RDF home construction project. Originated by Chuck Tavaris N4FQ, then improved and documented by Joe Moell KØOV and Thomas Curlee WB6UZZ, the design was named by KØOV to honor the transmitter hunters of Roanoke, Virginia, where N4FQ tested his prototype. This Homing In site is the official support site of the Roanoke Doppler project:

- Three suppliers of circuit boards and parts for the Roanoke Doppler are listed on the Hardware Sources page.
- Updates to the THRDFS documentation of the Roanoke Doppler are in the THRDFS Update page.
- An improved multiband antenna switcher is fully described in the Wide-Range Antenna Array page.

There are other home-construction Doppler projects, but only the ones built from the design in THRDFS and this Web site are Roanoke Dopplers.

Q: I can't locate any 75492 ICs for the Roanoke Doppler display. What shall I do?

A: An improved 16-LED display circuit is in the THRDFS Update page at this site. The 75492 ICs have been eliminated. If you already have a circuit board for this project, you can still use it.

Q: The WA2EBY Doppler circuit in a recent ham magazine looks very much like the Roanoke Doppler. Is it an improvement?

A: That author has utilized many of the design attributes of the Roanoke Doppler, but his unit has no new functions or operating features.

Q: The WA2EBY article states that ECG-555 PIN diodes give poor UHF performance and that ordinary 1N4148 diodes are just as good for a Doppler antenna. Is that true?

A: First, The ECG-555 is an older PIN diode, with unspecified RF series resistance. Newer PIN diode types listed on the Hardware Sources page of this site should perform better. Second, the switcher circuit of the WA2EBY Doppler is not optimized for PIN diodes. For best isolation, RF diodes should be reverse-biased when OFF, not just at zero DC current. That's because the series capacitance of PIN diodes drops dramatically as OFF (reverse) bias goes from 0 to 4 volts. (Examples: HP 5082-3080 goes from 1.1 to 0.4 pF. MPN3404 goes from 2.5 to 1.4 pF.) The lower the capacitance, the less RF gets through (better isolation). The Wide-Range Roanoke Antenna at this Homing In site reverse-biases the OFF diodes, which is an important reason why it performs better than the original Roanoke antenna. The WA2EBY Doppler circuit does not reverse-bias the OFF diodes. I believe that the results of the WA2EBY's loss/isolation tests would have been quite different if it did.

I discuss PIN versus switching/rectifier diodes for Dopplers on page 128 of THRDFS. PIN diodes provide significantly less insertion loss when ON, if biased properly, meaning that a PIN switcher will generally have less loss. More importantly, stray RF rectification is much less likely with PINs. I encountered significant cross-modulation problems using a Doppler with non-PINs, especially when driving near strong RF sources. WA2EBY did not test for cross-modulation when he evaluated diodes. I would welcome input from anyone who has done such tests.

Q: Will the Roanoke Doppler find aircraft Emergency Locator Transmitters (ELTs)?

A: The Roanoke and other ring-antenna Doppler RDF sets can readily track signals in the 120 and 240 MHz aircraft bands, provided that a suitable receiver is used. The Doppler modulation produced by switched whips in a Doppler array is FM, not AM. Therefore, the receiver must have an FM detector to properly process it. I use a venerable Regency MX-7000 scanner for this purpose. Just tune it to the proper frequency (121.5 or 243.0 MHz for ELTs, 121.6 MHz for tests) and set the receiver to the Narrowband FM mode.

The new Wide-Range Antenna Array should be used with the Roanoke Doppler processor for greatest sensitivity and best rejection of multipath distortion. Whips for 121.5 MHz should be 22 inches long, spaced in a square pattern 21 inches on each side. Whip lengths and spacings should be halved for 243.0 MHz operation. The Doppler is intended for vehicle or fixed station use only, not for on-foot operation.

Some high-end scanning receivers (including Icom R1, R10, R100, R7100-2, AOR AR-3000A, AR-8000, Radio Shack Pro-60 and others) can be operated in the Narrowband FM mode on 121.5 MHz. Specification changes may occur, so check to be sure before purchasing. Another idea for experimenters is to install crystals for 121.5 and 121.6 into an old crystal-controlled FM scanner. Everybody wants synthesized scanners nowadays, so "rockbound" sets are cheap and plentiful at swap meets and yard sales. Retune the RF stages as necessary for best sensitivity, because these sets were usually designed for receiving 146 MHz and up.



While a Doppler may be useful in some ELT tracking situations (such as a false alarms from aircraft on an airport runway), it is not a universal tool. ELT signals from actual crashes are usually very weak and of mixed wave polarization. Experienced Civil Air Patrol (CAP) volunteers in my area prefer cubical quads and phased arrays (such as the L-Per) instead of a Doppler when in such weak-signal situations. The photo shows a dual frequency (121.5 and 243.0 MHz) stiff-wire quad built by Bob Miller N6ZHZ, Commander of Brackett Composite Squadron 64 in La Verne, California. He says, "With the quad, I am able to pick up a 243 MHz ELT two to five miles miles before the L-Per's antenna will hear it. When there are two or three ELTs chirping simultaneously in hangers at an airport, I use a high-gain quad to track one at a time, listening to the differences in tone sweep rate of each one."

An RF attenuator should be used with an RDF quad to allow S-meter bearing readout and to help determine how close you are to the ELT. Plans for suitable quads are in THRDFS. For more on CAP and tales of searches for ELTs, see Homing In for April 1994.

Q: Can I use the Roanoke (or other) Doppler on the 10-meter ham band and/or the 11-meter Citizens Band?

A: It could be done if:

- The receiver is in FM detection mode (not SSB or AM)
- Switcher inductors and capacitors are optimized for this frequency range
- Antennas are 8-foot whips in a square pattern 8 feet by 8 feet

Of course this is not practical on a car, but could be considered for a fixed installation. Remember, Dopplers need carrier-type signals, so you can track amplitude-modulated signals (in FM mode) but not SSB signals. I have experimented with the Roanoke Doppler on 6 meter (50 MHz) FM signals, using resonant whips spaced in a four-foot square. They fit on the roof of the van, but there wasn't enough ground plane area around the whips, and the whips were so tall that they waved around too much while driving. Compared to baseline two-meter performance, this didn't work very well, especially in motion.

Q: I'm thinking of mounting a Doppler RDF antenna on top of my home ham station tower. Any suggestions?

A: One problem with remote operation of the array will be rf losses in the coax. You will probably not have problems with long control lines, although some added protection from lightning-induced transients is in order. For tower mounting, I recommend using four vertical dipoles (which would look like the marine DF antenna photo in THRDFS) instead of whips on a ground plane. This will give better performance by minimizing mutual coupling between the whips.

Q: OK, how about putting the Doppler at our mountaintop repeater site to find jammers on the input?

A: There are many pitfalls in the way of remote mountaintop RDF systems. I get letters regularly from hams who tell me about the wonderful linked RDF systems at repeater sites that they'll be putting on line "real soon now." I encourage them to send me all the details of their results, with photos, so I can tell the world via Homing In. Then I never hear from them again.

You'll probably discover, as they do, that you won't be able to successfully operate a Doppler DF at your repeater site. Here's why:

1. The commutating antenna system, "moving" at an audio rate, will induce the annoying Doppler tone into your repeater receiver and probably into most other receivers at the site, even those on widely different frequencies. This will occur even if you use a separate receiver for the Doppler antenna. Note that this phenomenon is not caused by digital switching noise in the commutating antenna. It is a parasitic RF effect and can occur even if no digital switching noise exists.
2. The cross-modulation products caused by stong signals from your repeater transmitter and other VHF/UHF transmitters at the site into the switched antenna system will make the Doppler insensitive and prone to unreliable indications.

Fast-switched dual-antenna RDF sets such as TDOA's will probably have similar problems. You might consider a slowly rotating beam with some sort of direction indication through the repeater---this was done by the Happy Flyers organization many years ago.

I know of only one successful remote repeater-connected RDF system now in operation, and it is not a Doppler. (If you know of others, please enlighten me.) This system uses a phased array which is switched very slowly (every second or so) to avoid the problems mentioned above. That slow switching is OK in the user's application, because it is intended to track continuously-transmitting ELTs, not ham-band kerchunkers.

So if you want to use Dopplers for remote RDF, put them at sites that are not associated with repeaters or other VHF/UHF radio systems.

Q: I have read several articles on 2-meter Dopplers and they all specify different antenna element spacings. What is the best?

A: No matter how many whips or vertical dipole elements in a Doppler array, the adjacent elements must not be more than 1/2 free-space wavelength apart, to avoid ambiguous bearings due to phase steps of greater than 180 degrees. Furthermore, adjacent element spacings of greater than 1/4 wavelength will produce phase steps of more than 90 degrees, lowering the level of the recovered audio tone and worsening the signal-to-noise ratio. With that in mind, an optimum adjacent-whip spacing for a 4-whip mobile array for VHF or UHF is slightly less than 1/4 wavelength at the highest frequency to be used. Plans for the 4-whip Roanoke Doppler in THRDFS call for 18-inch whip-to-whip spacing, which is 0.22 wavelength.

The array doesn't have to be this big, but don't make it too small, either. Deviation of the recovered Doppler tone is a function of antenna size and speed of rotation, as given by the formula on page 121 of THRDFS. This works out to about 0.5 KHz deviation for the Roanoke Doppler 2-meter antenna, which is a good value. A super-small array such as the 0.07 wavelength-on-a-side mentioned in the Dick Smith literature won't work well, because the recovered Doppler tone out of the receiver would be only 0.1 KHz. It could be readily overpowered by modulation audio and noise.

If you use a mag-mount implementation, remember to place the whips in a perfect square pattern. Measure spacing carefully or make a template. A slightly rectangular or trapezoidal pattern will introduce significant bearing errors at some angles.

Q: What about the spacing if I use more than four whips?

A: Going to 6, 8, 12 or more whips, as provided for in some Doppler sets, provides little improvement if the array size (radius of rotation) is the same as for 4 whips. The Doppler tone deviation is unchanged, though there are fewer high-order harmonics in the recovered audio. (That's unimportant if a very narrow passband filter is used, as in the Roanoke Doppler). Furthermore, the closer element spacing of a same-size-more-whips array increases inter-whip RF coupling, which degrades performance in multipath.

To fully realize the advantages of more whips, the array size must be increased. Consider a two-meter 8-whip array in an octagon pattern of 18 inches per side (i.e. the same adjacent whip spacing as the Roanoke Doppler). Radius of rotation is more than double that of the 4-whip Roanoke, giving over 1 KHz Doppler tone deviation at the same rotation rate. The array aperture is more than doubled, which improves performance in multipath.

However, an array with a diameter of almost 4-1/2 feet won't fit on most vehicles, especially when you remember that you would need 7-1/2 feet total diameter to provide ground plane under the whips. A similar size (in wavelengths) array for the 70 cm band (450 MHz) would be only 2-1/2 feet diameter, which is practical.

Q: Why doesn't the Roanoke Doppler use RF preamps and/or "soft switching" in the antenna system to give more sensitivity and less noise?

A: Questions like this indicate three assumptions:

- Assumption #1: Soft switching eliminates noise
- Assumption #2: Monolithic amps provide increased system sensitivity
- Assumption #3: A Doppler with switched preamps provides the same directional performance as one using PIN diodes.

I disagree with all three assumptions. Here's why:

1. Any Doppler antenna commutation, whether "hard" or "soft," produces additional spectral components in the RF signal to the receiver. It is true that rectangular-wave switching can create some broadband noise, but if the noise is really bad in your system, it's probably because the diodes are biased or driven improperly. Wide-bandwidth receivers such as scanners and handi-talkies are much more susceptible to this problem than mobile radios with good input RF filtering (such as helical resonators). You may find that changing your receiver or adding a helical filter between antenna and receiver improves the performance of your Doppler markedly.

2. Monolithic preamps have gain, which can overcome the small amount of loss in the coax from antenna to receiver. But they usually have a poor noise figure, much worse than most receivers. RF gain ahead of the receiver will worsen any receiver overload and cross-modulation problems. Strong signals can also overload the preamps, distorting the incoming signal phase and degrading the bearing accuracy. (Long-time T-hunter Mike Musick NØQBF has observed this even on signals from one or two miles away!) So unless you are using a very insensitive receiver, antenna preamps will probably do more harm than good. In addition, some Doppler sets hard-switch the preamp supply voltages. This causes the same broadband noise problems in a wideband receiver that improperly biasing the PIN diodes does.
3. As I explained in detail in my Homing In of April 1995 and August 2003, the impedance match (or mismatch) presented to switched-off whips in a Doppler array determines the multipath performance of the system. Preamps usually "look like" 50 ohms, which is undesirable in this application.

In summary, I believe that a properly designed PIN-diode switcher (with correct ON and OFF biasing), when used with a sensitive narrow-range receiver, gives as good or better overall Doppler performance (in both sensitivity and multipath accuracy) than any preamp-based design does, whether hard or soft-switched.

Q: Our club wants to set up some RDF sites to automatically find jammers and display their locations on the Internet. How do we do it?

A: First, understand that you won't be able to use such a system to positively identify RF coming from a specific house or apartment at a distance. Let's say you set up a RDF system with three sites to cover a typical urban area of 20 X 20 miles. For good coverage of the area, the sites will have to be on the perimeter. Assume that you can find enough quiet sites and link them. Now assume that the jammer is right in the middle of the triangle of sites (best case). The intersection of your bearings and their uncertainties will create a polygon with an area of about 4 square miles! That certainly won't be good enough evidence for the FCC. There are about 10 hams per square mile in my city, probably the same as where you live. So you'll still have to do plenty of close-in DFing to verify the actual perpetrator's site and get eyewitness evidence.

Why the large polygon? Because the inherent uncertainty of a bearing from a typical VHF 4-whip Doppler in an urban environment is about +/- 5 degrees, even if you have 10-bit readout precision. Sometimes, the bearing error is even greater, especially at fixed sites. (See Chapter 18 of THRDFS.)

This is not intended to discourage you, just to add a healthy dose of reality. If you want to link up RDF stations, consider using APRS, which allows packet interconnection of a limitless number, both fixed and mobile, close-in or far away, each one displaying their own and everyone else's bearings. Bearings and station locations can be input to APRS either manually or automatically, so even base stations with beams can help out. For more info, see my Homing In columns in 73 Magazine for October 1994, January 1995, and February 1995.

Q: How can I interface my Doppler to APRS?

A: Any of the popular homebrew or kit-built Doppler RDF sets with 8, 16, or 32 LED indicators can be connected to computers using a circuit developed by Robert Swain N7LUE. This includes the popular Roanoke Doppler and the DoppleScAnt from QST in the 70's. Robert's circuit takes the binary information from the LED drivers and outputs a serial RS232 data stream of ASCII characters representing directions. For details, see Doppler-to-APRS interface at this Web site and Homing In for August 1995. A microcontroller-based serial interface that outputs in "Agrelo" format is described on the Web pages of Bob Simmons WB6EYV. He also sells the PicoDopp, a Doppler add-on that includes serial interface, in semi-kit form.

Some sets made by Doppler Systems Incorporated feature RS232 serial output consisting of 3-digit numerical readout of bearing in degrees. Doppler Systems sets in the 3000, 4000, and 5000 series can also be used with N7LUE's interface.

The MicroFinder Doppler set by AHHA! Solutions has serial output of bearing information in "Agrelo" format.

Q: Why are there only 16 LEDs on the Roanoke Doppler?

A: The Roanoke Doppler was designed for the best combination of simplicity and performance. A 16 LED display is usually quite adequate for tracking signals when mobile in urban areas. It gives a rapid indication of which way to drive when time is of essence. I still use my 16-LED unit on the local hunts with good results. When I need higher accuracy for triangulation, I switch to a beam.

Finer resolution is possible with some circuit changes. Tom Curlee WB6UZZ has designed a version with digital readout to the nearest degree. But the basic bearing accuracy of VHF Dopplers on vehicles is typically +/- 5 degrees, so such a display gives a false sense of accuracy. And all these improvements require more complexity. That means more parts to find and greater cost. We have found that most hams want maximum simplicity in projects they have to build themselves. (On the other hand, when they buy a ready-to-use piece of gear, they want maximum bells and whistles.)

Part 2 - Questions About Other RDF Equipment

Q: Can you help me get my (choose one) Agrelo, Ramsey, Dick Smith, or "bow-tie" RDF equipment (not in THRDFS) to work?

A: Mail about these units is so frequent that I have posted details at this site.

- Agrelo DFjr Doppler
- Ramsey SlyFox and Foxhound
- Dick Smith Doppler
- "Bow-tie" sets by K8DTS and others

Q: I can't get my Shrunken Quad to work. What's wrong?

A: Most likely you are using the wrong piston trimmers, but it could also be an improperly built balun. Go to More on the Shrunken Quad to find out.

Q: Are there any updates/corrections to ______ (fill in your favorite project in TRANSMITTER HUNTING---Radio Direction Finding Simplified)?

A: Click here to get the latest updates to THRDFS.

Q: Where can I find boards/kits/parts for your projects?

A: I try to locate inexpensive sources for uncommon parts and include them in all my project articles. For updates and additional parts/boards info, jump to the Hardware Resources page at this site.

Part 3 - Questions About Transmitters and Covert Tracking

Q: My club wants to start transmitter hunting but first we need a hidden transmitter. What is available?

A: No problem! The transmitting part of T-hunting is easy if you give it a little thought. Keep in mind that no transmitting setup is perfect for all hiding situations. Hiders use a wide variety of equipment, with power output and antenna type depending on the distance to the start point and the level of intended difficulty. You need to determine, for instance, whether you want to do short range on-foot hunting, longer range hunting on bicycles, or still longer range mobile hunts.

For your first mobile hunts, just have someone stay with the transmitter and and key it up at appropriate intervals. The hider can read into the mike from a book, or from the club newsletter, or just make comments and urge the hunters on, as NØQEC and KBØIEK of the Lincoln (Nebraska) Amateur Radio Club are doing in the photo at left.

After a few hunts, you may want to put together an unattended transmitting setup, so the hider doesn't have to stay with the rig. For starters, connect your two-meter hand-held or mobile transceiver to a tape recorder playing an endless loop answering machine cassette with an appropriate message and ID. Some hiders like to use a dual-band hand-held and activate it on the subband from another transmitter. Later on, after you gain some experience and have a better idea what suits your needs, consider a dedicated home-built or commercial "foxbox" with tones and a cycling timer for hiding. See the Hardware Resources page at this site for transmitter controller ideas.

For short-range on-foot hunts in parks, consider complete mini-transmitters like the SquawkBox by Bob Simmons WB6EYV (photo at right). It records and sends short voice messages at adjustable periodic intervals.

More about transmitting gear for on-foot hunts can be found in the Equipment Ideas for Radio-Orienteering page of this site. And of course there is a complete chapter of clever transmitter hiding ideas in THRDFS.

Q: I need a miniature transmitter to put on my prized possession (sports car, TV set, motorcycle, coonhound) to find it after it wanders away or is stolen/abducted. What is available?

A: Yes, I have actually had inquiries about tracking devices for each of the above examples, and many more! Unfortunately, it is still true that you get what you pay for, and no matter what you pay, there's no assurance of success.

In the under-$40 category are "experimenter" micro-transmitters such as the TT7-K "Tracking Transmitter Homing Beacon" sold by Amazing Devices. Several miniature transmitter models are available from ElectroKits. These "bugs" typically use the 88-108 MHz FM broadcast band, where low-power unlicensed transmitters are permitted by FCC Part 15. Manufacturers sometimes claim range of three miles or more for these FM micro-transmitters. But that range assumes high-gain antennas on both transmitter and receiver. A practical antenna on a stealth radio tag will seldom be large and efficient enough for that. Furthermore, if one were to actually achieve three-mile range with such a transmitter, that fact would demonstrate that the field strength is in excess of that allowed by FCC Part 15 rules for unlicensed devices in the USA. In other words, it would be illegal operation of a radio transmitter in the eyes of the law.

Some of these experimenter FM-band transmitters use simple L-C tuning, so the transmitter tends shift frequency due to temperature changes, battery voltage droop or proximity to other objects. Futhermore, the FM broadcast band is not suitable for covert operations, as the tag can be tuned in on every home and car radio within range. Usable tracking range is severely limited by interference from powerful broadcast stations. The high level of audio FM deviation (+/-75 KHz) used by transmitters and receivers in the FM broadcast band is not compatible with narrowband Doppler RDF techniques. Have I convinced you that this is not a good option for most applications?

Also available for about $40 are micro VHF transmitters for the two-meter ham radio band, such as the MR6 Model Rocket Tracking Transmitter Kit by Ramsey Electronics. A similar postage-stamp sized transmitter project was detailed in Homing In for May and September 1993 (photo at left). At about 10 milliwatts, such transmitters are perfect for short-range ham radio transmitter hunts (see previous question). But two-meter frequencies may be used only by licensed ham radio operators, with proper transmitter identification, in accordance with FCC regulations. Plenty of ham radio T-hunters are ready and eager to track down intruders on these frequencies, and they won't be amused if they discover that a non-ham is using their spectrum space to keep track of his cat. There are restrictions and license requirements for the use of other VHF and UHF frequencies at these power levels as well.

A much better choice would be the tiny transmitters and tracking receivers made specifically for tracking mammals, reptiles, birds, fish and even insects. See my RDF links page for commercial suppliers of transmitters and receivers that are popular with two market groups: wildlife researchers and the owners of prize hounds. A good example is Communications Specialists of Orange, California, which sells waterproof tracking transmitters that are about the size of a stack of six quarters (photo at right). They may operate unlicensed under FCC Part 15 rules and are powered by a lithium-ion "coin-cell" battery that lasts about a month. Com-Spec is expanding the market for these radio tags by selling them as the LoCATor Pet Tracking System, the Radio Controlled Airplane ELT System, and the Law Enforcement Tracking System. Range of Part 15 compliant transmitters is a few blocks in the city and up to a mile in open terrain with transmitter and receiver elevated. For official law enforcement use, more powerful transmitters certified to FCC Part 95 are available for greater range.

To save battery life, these critter-tracking transmitters are pulsed for a few tens of milliseconds, every second or so. Their low-power signals are so weak at long range that dual-antenna sets and Dopplers are at a disadvantage. Sensitive narrowband receivers and beam or phased-array antennas work best. Professional grade tracking receivers are quite expensive, but the 30-channel Com-Spec Model PR-30 215 MHz range set with Moxon type directional antenna (photo at right) is a bargain at about $200. Another option is a consumer-type scanner. It must be multi-mode model such as the Icom IC-R10, Trident TR2400 or Sony ICF-PRO80, which include CW/SSB (BFO) modes. For a tracking antenna, you could build a small cubical quad from plans in THRDFS.

If money is no object, consider the complete RDF tracking systems manufactured by law-enforcement suppliers such as Tracking Products, Inc. Also at the high end of the cost range are "hostage tracking" systems sold by "spy market" distributors such as Surveillance Equipment Group and Airtight Investigations. Note that even with their high prices, there are practical limits on range and battery life. All advertising claims must be taken with more than a grain of salt. None of these providers offer any guarantees that you will locate whatever you're tracking or even that you will hear a trackable signal.

For vehicles, don't overlook LoJack and other commercial tracking systems. LoJack transmitters are installed in an undisclosed place in your vehicle or other important asset and activated automatically when it's reported stolen to the police. Then the signal is received and RDF-tracked by police and sheriff cruisers and aircraft (over 400 in the Los Angeles area alone). Ask the LoJack salesman if the guarantee of your car's return is still offered.

There are also non-RDF vehicle tracking systems such as the new GPS-based CyntrX by Enhanced Vehicle Applications of Wisconsin. It is sold by TechWholesale in Ohio. (Reports from users wanted, please let me know your experiences by e-mail.)

Q: What about a pager-sized tracking device to put on toddlers? Parents would carry a pocket-sized receiver so that they could locate the child in case he/she became lost.

A: As you can imagine, the tracking of children is a much more serious and difficult matter than the tracking of cats and sports cars. Here are just some of the many factors that must be considered if direction-finding technology is to be used:

- Size - For sufficient transmitter power and antenna size for tracking over a wide area, the child's device must be bigger and heavier than most people desire.
- Tracker - An effective tracker needs a "wide aperture" antenna for sensitivity and accuracy, so it cannot be pocket-sized. But parents won't want to haul around a big tracker on every trip to the amusement park.
- Battery Life - The longer the battery must last, the bigger and heavier the transmitter on the child must be.
- Antenna - How do you put an effective antenna next to a child's body without detuning it?
- RF Radiation - Is it safe to have a transmitting antenna next to a child's body?
- Liability - Will the maker be sued if parents cannot quickly find their child with the device?
- Security - How do you keep criminals from tracking lost children, too? What happens if a potential kidnapper finds the lost child before the parents do?

Companies such as Xmark Systems make "perimeter protection" systems that sound an alarm if a tag-wearing individual wanders or is taken out of a protected area. These systems are marketed to health care facilities as alarms to provide early notification of wandering Alzheimers or mental patients, or of infant abductions. They are based on RFID technologies (see next question), so they don't have any direction-finding capabilities. The protected perimeter is non-portable, and the tags can't be used to help find the person once he or she is outside the protected area. Care Trak, Incorporated sells a system of wrist/ankle transmitters that combines perimeter alarm and short-range (up to one mile) RDF tracking. In some localities, RDF-proficient volunteers assist authorities in tracking wandering patients under Project Lifesaver.

Some startup "personal tracking" companies, such as Protect Me Toys (now defunct?), eWorldTrack, Wherify Wireless, and Digital Angel (also defunct?) have received considerable press (and resulting investor attention) for their claims of long-range positioning and tracking. None of their systems use traditional direction finding (i.e. beacon transmitter and human-carried RDF gear). Instead, they are based on wearable Global Positioning Receivers with radio transmitters that beacon the GPS data to trackers directly or via cell/PCS phone systems. Currently available models are relatively large, have short battery life, and require a clear view of the sky for accurate positioning. A savvy child abductor would quickly remove such a device from the child or shield it to render it inoperative.

Other RDF-based systems now on the market for tracking children and adults include the medium- and high-end solutions described in my answer to the previous question, with the usual power, range, and battery limitation. If you have personal experience with any of these products, good or bad, or if you discover any other suitable (or unsuitable) systems, please let me know the details by e-mail.

Q: Our construction company is losing small tools, either by accident (falling into holes) or theft. Can a transmitter be inserted into items like wrenches, drills or grinders, with a RDF unit capable of detecting them inside a car trunk?

A: Radio Direction Finding (RDF) technology is typically done at considerable distance (from yards to miles and beyond). To do that, transmitters require long-term power sources (such as batteries) and antennas. They're usually too large to be placed on or in a hand tool. In addition, the transmitted signal can be detected by anyone with a receiver tuned to the proper frequency, so these systems are not covert.

RFID technology at the jobsite exit is probably more appropriate for this tool-detection application. RFID systems track property and objects at relatively close range with unique codes. For instance, chips (also called tags or transponders) can be implanted in pets to provide positive proof of ownership if the pet strays into the pound or is stolen. A reader device, passed over the chip, detects it and reads out the chip's unique ID code. Similar RFID systems sound an alarm when non-paid-for merchandise passes through the doors of a store. RFID done at greater distance in automatic toll collection systems on and elsewhere. At one time, the FasTrack transponders for southern California toll roads could even be used to quickly pay for a McDonald's burger at the offramp. (This feature was discontinued because so many transponders were being stolen out of cars and then used for this purpose!)

In an ideal situation, the chips are "passive," meaning that they don't require battery power. They usually cannot be detected with conventional receivers, but only by a reader or polling device designed to be used with them.

Part 4 - Miscellaneous Questions

Q: I'm ready to go on a mobile T-hunt. How do I find one?

A: If you live in southern California, see the Southern California T-Hunts for Beginners page at this site for monthly mobile T-hunts in the Los Angeles and Orange County area where first-timers are especially welcomed and encouraged. Web sites about other Los Angeles area Saturday night hunts and the southern California All-Day hunts are on the Links page of this site. That page also has links to Web sites and Homing In Correspondents who can tell you about hunts all over the USA, and in some other countries, too. If there are no hunts in your area now, get together with your local ham club members and start them!

Q: My friends and I chat on the local two-meter repeater. Somebody on there transmits beeps and mocks us. We can all hear him on the input of the repeater. Please listen with your direction finding equipment. We need to stop him.

(Believe it or not, requests for me to listen on VHF/UHF have come from hams that are hundreds of miles away from me!) You and your friends need to put some RDF gear on your vehicles and track down the offender yourselves. That's why I have this site and my book --- to help hams like you become proficient at RDF. It's not hard. Once you find him or her, a little friendly persuasion may be all that it takes to eliminate the problem. If not, the chapter on solving malicious interference problems in THRDFS may be helpful in developing a strategy.

You should also find out if the Amateur Auxiliary and Official Observer programs of the American Radio Relay League are active in your area. If so, join them now. Your ARRL Section Manager has more information.

Q: Is it true that transmitters can be "fingerprinted" for positive identification without the user being aware?



A: The concept of transmitter fingerprinting was invented and patented decades ago by Phil Farrell K7PF of Seattle. He licensed his patent/technique to The Boeing Company and to Motron Electronics, which sells equipment for it. The Motron implementation (called TxID) consists of a card that plugs into the expansion slot of a PC, plus software running under DOS. The asking price is higher than most individuals are willing to pay, but it is affordable for repeater clubs. I tested and reviewed the system in Homing In for November 1994. The review explains the principles of fingerprinting and shows good and bad points, including comparison of some same-model transmitters. Since then, Motron has added features such as receiver frequency control and readout for remote operation. TxID will control a tape recorder for evidentiary purposes.

A few hams have developed similar fingerprinting systems. The first was "XMIT_ID" by Richard Rager KB8RLN. It used PC software and an 8-bit Soundblaster card. I have lost contact with Richard and don't know the current status of this project.

"Sherlock" by Malcolm Mallette WA9BVS also runs on a PC and uses its sound card with commercial oscilloscope software. The newest version of Sherlock, which works with Windows XP and Vista, was detailed in a feature article by WA9BVS in the Winter 2006 issue of CQ VHF magazine. Click to download this article in PDF format (7 MB), courtesy of WA9BVS.

XMIT_ID and Sherlock are intended for home experimentation only. Commercial production of any fingerprinting system based on the turn-on frequency changes of a transmitter may infringe on US patent 5,005,210.

Q: What is a Crenshaw Factor and why do I need one?

A: The Crenshaw Factor has been used for many years in southern California T-hunts to normalize mileages and account for odometer differences between various vehicles. Your vehicle's Crenshaw Factor is the odometer mileage you get when you drive a standardized course that runs along Crenshaw Boulevard for about 9 miles. The course was chosen because it is relatively straight and goes up to the start point of the All-day hunts. This makes it easy for hunters to check their factors regularly on the way to a hunt.

A big problem right now is that the landmarks at the start of the Crenshaw have changed. The official start point is in front of a now-gone telephone booth in front of a now-gone Winchell's Doughnut shop on the southwest corner of Artesia Boulevard and Crenshaw. If you can find this point, then all you do is record your odo reading and drive in the left-hand lane along Crenshaw to the stop sign at Crest Road in Rancho Palos Verdes. Your elapsed mileage to that point is your Crenshaw Factor.

Nobody knows exactly what this distance is, but it doesn't matter. To normalize mileages on a T-hunt, each vehicle's elapsed odometer mileage is divided by its Crenshaw factor. The result is in "Crenshaw Units." The team with minimum Crenshaw Units wins.

Example: Say your odometer mileage on the hunt is 35.7 and your Crenshaw factor is 8.8. Your Crenshaw Units are 4.057. You think you won, but another hunter has odo mileage of 36.8 and Crenshaw factor of 9.3. That means his odo reads higher than yours for the same distance traveled. His Crenshaw Units are 3.957, so he beat you.

It is commonplace for two or more hunters to have low mileages within a few tenths of one another. Crenshaw Factors are needed to determine winners on many of our milege hunts, so it is important for every hunter to have one.

Q: Why has your book's price increased to $24.95?

A: I don't know. It was done by the new publisher in recent printing runs, without notice to the authors. There are no changes in these print runs, so look for previous-printing books at lower prices, if you can find them.

Q: I have a ham store and would like to carry your book. Do I have to get it from ARRL?

A: Retailers and dealers should get books directly from the publisher. Call McGraw-Hill Trade Order Desk at (800) 722-4726 to place quantity (5 or more) orders.

Q: Is there any difference between ISBN number 007-1560068 and ISBN number 0-8306-2701-4 for your book?

A: The book has two ISBN numbers because one was assigned to it by TAB Books originally, and the second was assigned by McGraw-Hill when McGraw-Hill acquired TAB Books. Booksellers might show stock in either ISBN number, depending on when they ordered the book and put it into their computer system. Sorry for the confusion, but I have had no control over this process.

Q: Why don't you sell copies of old Homing In columns or post them here on the Web?

A: For logistic and contractual reasons, I don't mail out or sell copies of magazine articles I have written. Furthermore, they cannot be posted here or on any other Web site, with only a few exceptions. Your fastest source for back issues of ham magazines is probably a visit to your local library. A nearby ham radio store may also have recent issues in stock. Many ham clubs maintain ham magazine libraries for their members.

Q: Can I make and sell kits and boards for projects in your books and articles?

A: Since Tom Curlee and I don't have the time to get into the board/kit business, we welcome other enterprising hams supplying these products. However, our publishers insist that we protect the copyrighted material appearing in the book and my magazine columns. Kit/board suppliers must not duplicate, sell, or give away any of the TAB/McGraw-Hill or 73 documentation of the projects. Kit/board buyers should be urged to purchase THRDFS for the tune-up, calibration, installation, and operating details. This works out well, because some of our kit suppliers are making extra money by retailing the book! To purchase books wholesale (5 or more copies), call the "trade order" desk at TAB/Mc-Graw-Hill. Please note that Tom and I support the circuits in our book, but we accept no responsibility for performance of third-party boards and products.

Hardware Resources for RDF Home Builders

Sources for the Roanoke Doppler project

Complete construction plans for the Roanoke Doppler are in Transmitter Hunting---Radio Direction Finding Simplified (THRDFS). The following are sources of printed circuit boards for the display unit. Some may also offer critical parts, complete kits, and/or wired/tested units.

- Directional Systems: Jim Sorenson KA4IIA, PO Box 81881, Conyers, GA 30094, ka4iia@radio.org
- FAR Circuits: Fred Reimers KF9GX, 18N640 Field Court, Dundee, IL 60118, farcir@ais.net or http://www.farcircuits.net (847) 836-9148. Users have reported errors on older versions of the display boards. They have been corrected in display boards now being shipped. FAR Circuits also has a circuit board for the Wide-Range Antenna Array. There is a minor correction to the marking on this board. Click here for more information.
- Stephen Douglas K6HZT of Sacramento, CA, k6hzt@arrl.net or http://www.marshwildman.com/doppler.htm. Please note the board errata information on his site.

Disclaimer: The information above, and elsewhere on this page, is provided for the convenience of readers only. These suppliers are independent entities. They have no business association with Joe Moell or Tab/McGraw-Hill. A listing on this page does not constitute endorsement of products. Contact these suppliers directly for offers and prices.

Boards are no longer available from Ed Greany KB6DOL or Tom Lewis AB5CK.

Sources for RF attenuator projects

Resistive RF attenuators are best suited for mobile HF and VHF T-hunting with directional antennas such as loops, yagis and quads. Pete Ostapchuk N9SFX sells parts for resistive attenuators, including a 6-section enclosure machined from 6061-T6 aluminum bar stock and engraved with attenuation values. Also available from him are switches, resistors and connectors. Plans for his project are in QST Magazine for May 1998. Send e-mail to n9sfx@aol.com for details and prices. The above disclaimer applies.

Another source of resistive RF attenuators is National RF, Incorporated (formerly Radio Engineers) of San Diego, CA.

For on-foot VHF/UHF "sniffing" and international-style foxhunting with a beam and handi-talkie or scanner, an "offset" or "active" attenuator is better because it eliminates the problem of signal leakage directly into the receiver's case. Plans for an active attenuator are at this Homing In site, click here.

Sources for fox-boxes

Hidden transmitter controllers, sometimes called "fox-boxes" are units that provide audio and timed key-up/key-down (push-to-talk) outputs. A fox-box turns an ordinary handi-talkie or mobile transceiver into a cycling hidden T. Here are four fox-box projects for home construction:

1. The Un-Music Box by KØOV is an easy-to-build project using common easy-to-obtain CMOS ICs. No microprocessor programming is required. Provides on-off cycling or continuous transmissions. Callsign is hand-programmed using two switches; shift register memory has battery backup. Complete plans in the book TRANSMITTER HUNTING---Radio Direction Finding Simplified. You can remote control the Un-Music Box with a surplus pager receiver using plans in Homing In for December 1990.
2. PicCon by Byon Garrabrant N6BG uses a Microchip PIC microcontroller and has a variety of programmed on/off modes and tone sequences for mobile T-hunts as well as IARU-standard MOE/MOI/MOS audio, timing and synchronization for international-style radio-orienteering. DTMF remote control and programming with your HT or external receiver. Delayed turn-on and turn-off timers. Callsign and programming info are held in EEPROM when power is removed. Reviewed in Homing In for March 1997. Complete kit is available from N6BG.
3. TBOX by Ron Seese N6MBR uses an 80C51 microprocessor to provide three programmed tone sequences and/or a CW message. User-programmable on and off times in intervals from seconds to hours. Programmed via RS-232 serial port using commands similar to packet TNCs. Non-volatile memory (EEPROM) holds programming and message when powered down. Optional SmartWatch clock turns fox on automatically at programmed time. Plans for basic unit are in Homing In for October 1991. Assembly, object and binary files for the microcontroller program (10K total) are available at this Homing In site. Contact N6MBR regarding availability of kits and critical parts.
4. Francois Tremblay VE2JX and Jacques Brodeur VE2EMM of Montreal have designed a new PIC-based foxbox for international-style hunts with MOE/MOI/MOS audio, synchronization of 2 to 7 foxes, delayed start of up to 3-1/2 hours in 1/2-hour increments, and automatic shutoff after four hours of operation. Callsign is held in non-volatile flash memory. Callsign changes and mode setup are easily done with dipswitches. This project is fully described in Homing In for April 1998.

Sources of PIN type RF diodes

For maximum receiving sensitivity and minimum problems with cross-modulation, good RF PIN diodes must be used in hard-switched dopplers such as the Roanoke Doppler. Breakdown voltage and power rating of the PIN diodes are not important in low-level receiving circuits. (You aren't going to transmit through the switcher, are you?) For low loss and good sensitivity, the diodes should have low RF resistance (Rs) at the expected forward DC bias current (7.5 mA for the wideband switcher). They should have low capacitance (Ct) at the reverse bias off-state voltage. Effective carrier lifetime and reverse recovery time (Trr) should be short. (PIN diodes with long carrier lifetime are ideal for current-controlled RF attenuators, but that's not what we want in this application.) Keep the diode leads very short to minimize inductance and make sure signal path lengths, including diodes, are equal for all elements in the array.

Suitable PIN diodes include:

- Narda KS3542 -- DO-34 package, click for data sheet. A ham with a supply of these diodes has offered to make them available in small quantities to home builders of RDF equipment. Send e-mail to me for more information.

  Philips NTE555 or ECG555 -- "Replacement" type semiconductor available at local electronics parts houses all over the country. Even some giant computer stores such as Fry's Electronics carry NTE parts. Priced $1.50 to $2.00 each. This is an older part with tab leads and unspecified series RF resistance.
- Agilent Technologies (formerly Hewlett-Packard) surface-mount PIN diodes -- Surface-mount parts are best if you're building a doppler for UHF (400 MHz and up). Three types used to be easy to get from RadioShack.com but are apparently no longer available there. Try Arrow Electronics, a major parts distributor in in Melville, New York. The Agilent HSMP-3892 or HSMP-3893 are good choices for a series doppler switcher such as the wideband array on this Web site. On the other hand, the HSMP-3820 is optimized for a shunt switcher such as the one in THRDFS.
- Motorola MPN3404 -- In TO92-style plastic package. 50 cents each or ten for $4.50 at Circuit Specialists, 220 S. Country Club Dr. #2, Mesa, AZ 85210 (800) 528-1417. $1.00 each from Debco Electronics, 4025 Edwards Road, Cincinnati, OH 45209 (513) 531-4499. Advertised price is 60 cents each at Dan's Small Parts and Kits, Box 3634, Missoula, MT 59806-3634 (406) 258-2782.
- TRW A5S303 -- Axial lead device formerly available from Tanner Electronics in Carrollton, TX (214) 242-8702. Does anyone have a new source?
- Agilent Technologies 5082-3077 -- Axial-lead low-Rs device available from Newark Electronics. Newark also carries Agilent 5082-3081 and 5082-3080, which are long-carrier-lifetime parts intended for variable RF attenuators and thus not suitable for doppler switches.
- Motorola MMBV3401LT1 -- Surface-mount replacement for the now-discontinued MPN3401. Available from Motorola industrial distributors. Not suitable for perf-board construction.

After I bought some Motorola PIN diodes from Debco Electronics, I mentioned their availability in Homing In for April 1995. A reader wrote to me after publication to say that Debco was astonished at the response. The order-taker said that they hadn't sold a PIN diode for over a year and then after the article came out they began selling like hotcakes. Who says hams don't build nowadays?

Other Sources of RF Parts

Hard-to-find RF parts such as air variable capacitors for tuning HF loop antennas can sometimes be found at dealers of "overstocked" or "industrial surplus" components. Here are three to try:

- Bogdan Electronic Research & Development (Jim & Carolyn), PO Box 62, Lakewood, CA 90712, (562) 634-0911. They sell RF parts by mail and are often at southern California swap meets, too. Note: Jim says that the margin on small quantities of RF parts is so low that it's not cost-effective for him to return calls. (I know the problem!) Therefore, please use e-mail or call back to catch him or Carolyn "live" on the phone if you get a recording when you call.
- All Electronics, PO Box 567, Van Nuys, CA 91408.
- Alltronics, 2300 Zanker Road, San Jose, CA 95131, (408) 943-9773.

For more information about sealed RF "piston" trimmer capacitors and sources, see the Shrunken Quad page at this site.

Ferrite beads and cores for the dual-polarization quad (see Homing In for February 1997) and other RF projects are available by mail order from Amidon Associates. Locals can save shipping charges by picking up orders at 240 Briggs Avenue, Costa Mesa, California, during normal business hours. Call in advance to 800-898-1883 or 714-850-4660.

ByteMark Corporation, 7714 Trent Street Orlando, FL 32807 (407) 679-3184 also carries Amidon ferrite components and has technical information about Amidon ferrite and iron powder products on its Web site. In addition, ByteMark sells a Windows-based program for calculating the turns for coils on various Amidon cores.

The Philmore line of packaged electronic parts includes unusual items such as Amidon T50-6 cores (used in the ATX80 80-meter fox transmitter), International Rectifier HEXFETs, MPF-102 JFETs, etc. Unfortunately the Philmore Web site does not have a complete product list, but it does include a list of local distributors of these parts.

Crystals for 80-meter foxboxes are available from Brian Carling AF4K in Sanford, FL. He also sells some crystal-can oscillators that may be suitable for building offset attenuators.

Jerry Boyd WB8WFK provides this feedback on ON7YD's Fox Transmitter for 80 meters (ATX80), which was featured in 73 Magazine for November 2000: "Motorola MC14001B Quad-NOR ICs from Radio Shack (part number 276-2401) didn't work. The oscillator would not start properly. I tried 6 different ones and they all acted the same. I put in an old Fairchild CD4001B Quad-NOR and now it works with no problem. I downloaded data sheets from the manufacturers' Web sites and the internal schematics are indeed different." Fairchild ICs are available from many suppliers, including Digi-Key. KØOV's six transmitters use Signetics (Philips) CD4001B's packaged by Jim-Pak and sold by local parts suppliers nationwide -- they all work fine.

Sources for building polar-plot bearing readouts

I have many requests for sources of unusual electromechanical parts used in two-dimensional bearing indicators such as the KK6CU motorized quad, the WB8WFK and KD6IFZ computer displays, and the NØMKJ Foxcopter. (See the Homing In Index page at this site for articles describing these RDF systems.)

For (relatively) inexpensive surplus sine-cosine potentiometers as used in the KK6CU motorized quad, try Servo Systems Company, 115 Main Road, PO Box 97, Montville, NJ 07045, (201) 335-1007, in USA (800) 922-1103. The last catalog I received from this company included sin-cos pots by Litton, Duncan, N.E.I., Samarius, and Gamewell. There were continuous turning and single-turn models with prices from US$18.50 to $69.50.

For a "Cadillac" system, check out these contactless sin-cos resolvers using internal magnets and Hall effect sensors, designed to be rotated at up to 10,000 RPM: Elweco Incorporated, PO Box 909, Painesville, OH 44077-0909, (440) 254-1716.

Small industrial rotary joints (slip rings) in the $30 price class are suitable for low-voltage uses. NØMKJ used one of these for the two-meter coax feed in his Foxcopter. They are available from McMaster-Carr Supply Company, PO Box 54960, Los Angeles, CA 90054-0960, (310) 692-5911.

Another promising source of rotary joints is Mercotac, Incorporated, 6195 Corte del Cedro #100, Carlsbad, CA 92009, (619) 431-7723. Unfortunately the Web site does not list prices. If you use one of these products in your RDF system, please let me know how it works and what it costs.

Inexpensive electronic compasses with digital output (Vector 2X series) are manufactured by Precision Navigation Incorporated, 1235 Pear Avenue, Suite 111, Mountain View, CA 94043 (415) 962-8777. They are sold by Jameco Electronic Components, 1355 Shoreway Road, Belmont, CA 94002, (415) 592-8097, in USA (800) 831-4242. They are also sold by JDR Microdevices, 1850 South 10th Street, San Jose, CA 95112, (408) 494-1400, in USA (800) 538-5000.

From Peter PB2RDF comes this suggestion for a source of obsolete and out-of-stock electronic components for replacement or for older designs: 1-Source Electronic Components, 591-B Bicycle Path, Port Jefferson Station, NY 11776 (800) 966-8826 or (631) 642-2479.

RF Sniffer with Tone Output

Here is a neat Sniffer designed by Don, KF6GQ. It produces an audible tone which rises in frequency as the signal gets stronger. It uses 5 transistors and a 555 timer IC.

For a 1 Watt transmitter, sniffing range is about 225 feet using a 3 element Quad beam, or about 100 feet with a 1/4 wave spike antenna.

The Zero Adjust pot is used to set the tone frequency when there is no RF. With knob, field adjustable.


RF Sniffer with Tone Output
Pin Jack
5-45 pFd
L1
Ct
10K
BNC
Sensitivity Adjust
Q1
100K
100K
0.001
Q2
100K
Q3
10K
Q4
100K
10K
100K
Zero Adjust
9V
+
1K
Q5
4
8
7
3.3K
2
6
555 Timer
0.15 uFd
1
3
10uF
+
1K
Design by KF6GQ

The Sensitivity Adjustment pot is used to control how much signal is required to produce the maximum tone frequency. With knob, field adjustable.

Parts Not Given on Schematic

L1 = 5 turns, 1/4 inch form tapped at 1.5 turns. (For 2 meters)
Ct = Small RF trimmer capacitor, adjustable over about 5 to 45 pFd. Not critical. Screwdriver adjustment is fine.
Q1 & Q4 = 2N5457 (silicon J-FET)
Q2 & Q3 = 2N3904 (silicon NPN)
Q5 = 2N3906 (silicon PNP)
NOTE: Just about any small-signal silicon transistor of the same general type as specified should work.

Contact Information

George (Russ) Andrews, K6BMG
BMG Engineering, Inc.
9935 Garibaldi Avenue
Temple City, CA 91780 USA
Phone: 1(626)285-6963
FAX: 1(626)285-1684 (dedicated line, automatic)
Web: http://members.aol.com/bmgenginc

Audible S-Meter


AUDIBLE S-METER
1N761*
Radio S-meter
Vcc
Radio Ground
500 K-ohm pot
12 K-ohm
9V
Vcc
8 Vcc
7 Timing Cap
6 Timing Res
5 Mod Input
LM 566
Gnd 1
2
3
4
0.01 mf
1mf
100 ohm
8 ohm Speaker
5K
freq Hz.
0
0
Vcc
V pin 5

The Montreal Audio FS-Meter

PARTS LIST, 27 JULY 99

R1 = 2M7 1/4 W (2.7 mohms)
R2 = 47R 1/4 W (47 ohms)
R3 = 100K 1/4 W
R4 = 10K 1/4 W
R5 = 10K 1/4 W
R6 = 1K0 1/4 W or 1K0 trimm pot DK# D4AA12-ND for volume adjustment
if needed (1 kohm)

RV1 = 1M0 to 5M0 POTENTIOMETER (GAIN) (1 to 5 mohms)
RV2 = 10K 1T TRIMM POT, DK# D4AA14-ND

C1 = 2-20 pF RED TRIMMING CAP DK# SG20015-ND
C2 = .001 uF CER
C3, C4 = .1uF CER
C5 = 1 uF ELECTROLITIC 16V
C6 = 100 uF ELECTROLITIC 16V, Mount laying down on the board
C7 = .01 uF CER

D1 = 1N34, 1N60 ETC GERMANIUM DIODE
IC1 = MAXIM MAX495CPA RAIL TO RAIL SINGLE SUPPLY OP-AMP, DK# MAX495CPA-ND
IC2 = MICROCHIP PIC12C671/JW, UPGRADABLE, DK# PIC12C671/JW-ND
OR FOR LOWER COST, PIC12C671-04/P, NOT UPGRADABLE, DK# PIC12C671-04/P

L1 = 2T, 1/4" ID ON COLD END OF L1 #20
L2 = 5T, 1/4" ID AIR WOUND #20

SW1 = SPST MINIATURE SWITCH

MISC:

3 = AAA BATTERY HOLDER
1 = 18 pins IC socket or 2 = 8 pins IC sockets
1/8" EARPHONE JACK MONO
SINGLE EARPHONE
BNC CHASSIS JACK
PUNCH BOARD OR PCB
METAL BOX for shielding


10K
4.7uf
8 7 6 5
+V O C
MAX
495
C - + -V
1 2 3 4
1<5M0
10K
.1 uF
-V
PIC
12C671
+V
3 AAA
BATT.
+
4.5V
-
100uf
1/4" ID
AIR WOUND
10K
5T
1N34
100K
2-20pF
.001uF
2M7
47R
NUMB
2T
1K0
1uf
EARPHONE

THE MONTREAL AUDIO FS-METER

JACQUES BRODEUR VE2EMM

V 1.0 JUNE 99

Crystal Detectors to Point Contact and Layered Signal Diodes in Electronics

OddMix.com - Technical Note - Crystal Radio - TN080417 - Karl Nagy



Picture 1. "Ernest Roger" Crystal detector from 1920

Many of the **younger generation** never had the pleasure to have, or to even see a real beautiful crystal detector as shown on **Picture 1**. A detector like that was the product of the early 1920's, and it was an expensive, quality, well made product. They were usually hands assembled with machine made components.

This particular "**Ernest Roger**" detector device is built on an insulated base, either wood or most likely of Bakelite, the most widely used and only available plastic material at the times.

Many of the younger generation never had the pleasure to have, or to even see a real beautiful crystal detector as shown on **Picture 1**. The new generations are much too involved with technology and playing on their computers or going to an **online University**. This excellent detector holder used copper, brass and bronze generously for the crystal holder and for all of the **electrodes**.

The most often used crystal in this and similar detectors - then and now - was **pyrite** or galena as shown in the 1925 listing in a table in the **"American Mineralogist"** publication, that has a listing of thirty three minerals catalogued with rectifying detector properties.

1N21B
OddMix.com

Picture 2. Early point contact diode with adjustable srew

Among the very first commercially produced diodes is the 1N21B shown on **Picture 2**. It is more than curious, that this "diode" is enclosed in a case on which there is a slotted screw-head is just visible on the wide side (lower right). That screw is connected to a fine "cats whisker" steel wire, a few turns of a spring-like device, terminating in a point that is in touch of the germanium semiconductor material connected to the top left diode terminal.

The arrangement is much smaller, and more diode like, then the detector on **Picture 1**., but it made in a very similar arrangement, which has became known as the point contact diode. From these and similar germanium diodes, evolutionary progress leads us to current PN junction Silicon, Gallium Arsenide or other more exotic semiconductor materials which are the achievement of the latest scientific age and many years of steady experimentation, research and development.



Picture 3. Point contact diode

Picture 3 shows the cross section of a hermetically glass enclosed, point contact diode. If the left side, point contact terminal would be attached to a screw and a short spring, and the glass envelope would have a threaded metal part in it, the **Picture 2** and **Picture 3** devices would be nearly identical.

These point contact "cat's whisker" devices, are still made occasionally because of their very small capacitance. As it was discovered early on, they are highly useful in high frequency electronics. All the way up to microwave frequencies they useable. The simplest radar detectors usually made with a simple horn **antenna**, a diode similar to **Picture 2** and **Picture 3** and a transistor amplifier. If the designer keeps it simple, and don't use a local oscillator, such radar detectors are not even detectable by the police.

Previous Page | **All Circuit List**

Google Search

● Web ○ www.oddmix.com

056522

Copyright © 2015 K Nagy - http://www.OddMix.com - All Rights Reserved
Page Revised: 2015-01-01 - - Privacy Policy - Site Map - Support

Hosted by 1&1



Fig. 3.1 Aerial tuning coil wound from 38-s.w.g. wire on a $\frac{5}{16}$-in. diameter ferrite rod.

Fig. 3.1 details the construction of a suitable coil for a tuned circuit, matched to a ferrite rod of $\frac{5}{16}$ in. diameter and about 4 in. long (see Chapter 4 for alternative coil windings on different rod sizes). If a rod is purchased longer than 4 in., it can be used as it is, or cut down by marking around with a file and then breaking off the surplus length.

Cut seven 1-in. lengths of gumstrip. Moisten one and wrap around the rod gummed side up. Now add about another half a dozen wrappings of similar length over the first, this time with gummed side *down* to form a reasonably rigid tube. Make sure that the paper tube is a *sliding* fit on the ferrite rod and leave to dry thoroughly (preferably removed from the rod so that it cannot become stuck to it).

When the paper tube is quite dry it should be rigid, when the coil windings can be applied. The wire to be used is 38-s.w.g. enamelled copper wire, the number 38 referring to the actual diameter of the wire according to the standard wire gauge (s.w.g.).*

Starting about $\frac{1}{4}$ in. in from one end of the paper tube, wind the wire carefully round the tube, with each turn tight against the one before it, until sixteen full turns have been completed. Then make a loop in the wire, as shown, and carry on winding, with succeeding turns touching, until fifty turns in all have been completed. The two loose ends of the coil (the start and finish) can be secured with a dab of sealing wax whilst the projecting loop can be twisted together (e.g. by putting a pencil through the loop and twisting up). Cut off the loop, leaving about $\frac{1}{2}$ in. protruding from the main coil, bare the wire ends and solder together. This forms point 2 on the coil; the start is point 1, and the end point 3–see Fig. 3.1. It will be easy to remember these without marking since the loop or tapping point (2) comes much closer one end (1) than the other (3).

---

* American wire gauge (AWG) is about two sizes smaller than the British standard wire gauge (s.w.g.). For example, 38 s.w.g. is approximately the same as 36 AWG.

Cut a panel of *Paxolin sheet* to about the size shown in Fig. 3.2, using a hacksaw.* On this secure a *tag strip*, as shown, and drill a hole to mount a miniature or small-size 500 pF *variable capacitor*.



Fig. 3.2 Paxolin panel and tag strip for crystal set circuits.



Fig. 3.3 Layout of components on Paxolin panel.

The aerial coil is then mounted on the panel as shown in Fig. 3.3, gluing the coil on to the Paxolin with two or three dabs of sealing wax, or some other suitable adhesive. *Note:* the ferrite rod must be free to slide in the paper tube for 'tuning' adjustments.

Virtually any miniature germanium or silicon diode will be suitable for the detector. Recommended types, which are readily available, are 1N34 and 1N914.

Earphones must be of *high-impedance* type, which need not be expensive to buy, and the higher the impedance the better the reception.

---

* A phenolic or fiberglass sheet may also be used.


EXTERNAL AERIAL
3
2
1
DIODE
HIGH-IMPEDANCE EARPIECE OR PHONES
CONNECTION TO EXTERNAL EARTH

Fig. 3.4 Wiring connections to complete the crystal set.

Alternatively a deaf-aid type earpiece can be used; this will not give the same volume or quality of reproduction as headphones, but is a less expensive component. This should preferably be of the *high-impedance magnetic* type, with high sensitivity. Any high-impedance earpiece will suffice, but if of crystal type will require a resistor, connected across it, to complete the circuit. This will reduce the amount of current flowing through the earpiece and lower the strength of signal.

Wiring connections are shown in Fig. 3.4. End 3 of the aerial coil (the end of the 50-turn coil) connects to one terminal of the tuning capacitor, the aerial or 'hot' end of the tuned circuit, and the point to which an external aerial is connected. The other end of the coil (end 1) connects to the other terminal of the tuning capacitor, from which an additional wire is taken to the first tag on the tag strip. This is the 'earthy' end of the tuned circuit, and the point to which an external earth is connected. Leave plenty of slack wire between the coil and tuning capacitor.

The other connections are then as follows:

(i) Tapping point of the coil wire bared and connected to the second tag.
(ii) The diode also soldered to this same tag, and to any other free tag.
(iii) Headphone (or earpiece) leads to the 'earthing' tag, and to the 'free' tag to which the above diode has been connected. All connections should be made with *soldered* joints.

The wiring-up can be checked against the *circuit diagram* shown in Fig. 3.5 (ignoring the components shown with broken lines). The set should now be 'working'.

In areas of strong signal strength, no external aerial or earth connections should be necessary. Performance will, however, be improved in any area by attaching an aerial wire (which can be any thin wire, e.g. using the same wire as for the coil winding), of up to 160 feet. The longer the aerial the better the reception, provided it is led away from the receiver to as *high* a point as possible.

An earth connection may further improve aerial performance; by this we mean a connection to some conductor positively in contact with the ground (preferably buried), an excellent example being a metal water-pipe. Thus, if an earth connection is found to be necessary (or you want to try one to see how performance is affected), connect a wire from the 'earthing' tag on the receiver to a convenient water-pipe.

This question of obtaining a *good* aerial and earth is a most important one in areas of poor signal strength. Linking up to a television aerial is often a good plan, since TV aerials are also usually mounted as high as possible. If bare wire is used, it is also important that the upper (free) end of the aerial is not made fast to something which could produce an earth connection (e.g. a damp tree), or at least is suitably insulated from such a support. String is not an efficient insulator; that, too, can conduct when wet.

Quite good results are often obtained by using the springs of a bed as an aerial, in which case an earth connection is usually not necessary. Sometimes, too, when other attempts to yield a good signal strength in



Fig. 3.5 *Circuit I.* Circuit diagram of basic crystal set.

the aerial have failed, connecting the *aerial* side of the tuning coil to a *good earth* (a water-pipe) can produce better results, the normal earth connection being left off.

Tuning

The receiver is adjusted as follows. Turn the tuning capacitor to fully close the vanes, then open about half a turn on the spindle or knob. (If you are using a trimmer as a tuning capacitor, screw right down and then open half a turn.)

The tuning coil should now be slid up and down the ferrite rod (the coil leads were left a fairly long time to give the necessary freedom of movement) until BBC Radio 3 is heard.*

It may be necessary to slightly alter the adjustment of the variable condenser to tune in to this programme. Also, because of the ferrite-rod aerial the set will be directional, that is, the signal strength received will depend to some extent on the direction in which the aerial rod is pointing, so position the set to pick up the maximum volume.

Having established the best position of the tuning coil on the rod to receive BBC Radio 3, fix permanently with a dab of sealing wax. You should then find it possible to tune in to further stations by altering the setting of the variable capacitor—e.g. typically Radio 4 in about the middle of the capacitor travel and Radio 1 towards the other end.

Any reception you get will almost certainly be very weak and (unless you live close to a broadcast station) you can really feel satisfied if you get any station at all at audible strength. But it is surprising how, sometimes, even quite distant stations can be heard. Also you can often improve the reception and listening strength by quite simple modifications. Try these in order:

(i) Connect a 1,000-pF capacitor across the headphone (earpiece) connections (C2 in Fig. 3.5).

(ii) Instead of connecting the external aerial directly to the tuned circuit, connect one lead to a 220-pF capacitor, and the other end of the capacitor circuit to the 'hot' end of the tuned circuit (C1 in Fig. 3.5).

(iii) Instead of connecting the external aerial to the tuned circuit, connect to the tapping point of the coil (tag to which the diode is also connected). Try a direct connection, and also connecting in a 220-pF capacitor.

---

* Tune to an AM broadcast station near the lower end of the dial—close to 550 kHz.

(iv) Try connecting a 1.2-k resistor (or higher value) across the phone connection (R in Fig. 3.5). You may be using the wrong type of phones or earpiece, which do not provide a proper load or complete the circuit.

If there is a complete lack of response, check for faulty wiring-up. A more likely cause, however, is lack of an external aerial or earth connection in an area where these are strictly necessary for adequate reception; or an inefficient aerial (too short) or poor earth connection (bad electrical contact to a good earth point, or connection to a bad earth point).

Another possible cause of apparent failure may be too much outside noise entering the ear so that it is impossible to detect the very weak radio signal as it is being tuned in. Headphones are better than a single deaf-aid type of earpiece in this respect but, in any case, a really quiet room is virtually essential for initial setting up and tuning adjustments. Also, if your adjustment of the tuning control is too coarse, you may completely miss the setting for the station you are looking for, without realizing it.

Reception will also tend to vary with weather conditions. Some days it may be so poor that what was normally a strong station is hardly heard at all. The simple basic receiver has many limitations but, since it costs very little to construct and nothing at all to operate, this must be regarded as inevitable.

Providing you can hear something–even if too weak a signal to distinguish properly–you can certainly improve the performance of your basic set by further experimentation with tuned circuits (see Chapter 4) and/or the addition of amplification to the circuit. You can also try other types of basic crystal set, as described in the following projects.

Circuit 2 (Fig. 3.6) is identical to *Circuit 1* except that, instead of a diode, a transistor is used as a detector. Only two of the transistor leads are connected–the emitter (*e*) connection to the tapping part of the coil, and the base (*b*) to the 'earthy' end of the circuit. The collector lead of the transistor is ignored (bend it out of the way so that it cannot accidentally short out the other leads).

You can try almost any type of low-cost AF transistor; recommended types are OC42 2N370, 2N2925, 2N5088.

With the addition of two more components, Circuit 2 can be modified to work the transistor both as a detector and an amplifier, to give stronger signals through the headphones. Using the same transistor type



Fig. 3.6 *Circuit 2.* Crystal set using transistor instead of a diode.

as above (or near-equivalent) resistor R should be 15 k and capacitor C3 1 μF or higher.

This time a battery is also required to supply power for the transistor to work as an amplifier. This can be from 1.5 V up to 9 V. Remember the rules for polarity of connection: those shown in Fig. 3.7 are for a p-n-p transistor; an n-p-n transistor would need the battery connected the opposite way round. Battery polarity also affects the connections of capacitor C3 (if an electrolytic or polarized type).

Experiment further by trying the effect of using additional capacitors in the circuit, e.g. C1, 220 pF; C2, 0.001 μF (try other values as well); C4, 0.001 μF (try other values as well).


C1
R
C2
+
C3
C4
1·5 TO 9 VOLT
BATTERY
+

Fig. 3.7 *Circuit 3.* Crystal set with amplification.


D2
+
C2
L
C1
+
D1
C4
C3
CRYSTAL
EARPIECE

Fig. 3.8 *Circuit 4.* Double diode crystal set.

This circuit incorporates 'voltage doubling' to improve the signal volume and should give better performance than a single diode circuit. L and C1 are the usual tuned circuit, but an unusual feature is that the *aerial* is connected to the coil tapping point. Any type of germanium diodes can be used (they should preferably be the same), making sure to connect them the right way round. A high-impedance *crystal* earpiece must be used in this circuit.

Capacitor values are: C2, 220 pF (this capacitor can be omitted--try with and without in the circuit); C3 and C4, 1,000 pF.

The optimum tapping point for the aerial connection to the coil L is best found by trial and error (see Chapter 4 on 'Tuned Circuits'), but the set should work at a nominal one-third tapping point from the 'earthy' end.

This set can also be tried with conventional tuned-circuit coupling--*i.e.* aerial to the top of the coil L, and diode D2 connection to the tapping point on the coil.

The Fredbox

2007-05-26

I first heard about The G3XBM Fredbox transceiver via Solder Smoke. As soon as I saw it I just had to give it a go. It is a very simple and elegant design. Of course it offers no bells or whistles, just a fixed TX and RX frequency, and a flea-power output on TX, but it has a special charm in its simplicity and the retro usage of AM on VHF.

Transmitter

I built the transmitter side first. BF199s were selected as a good candidate for the RF devices, but I lacked a crystal in the range specified in the original article. Instead, I used a common 16.384 MHz crystal and redesigned the circuit to be two triplers rather than two doublers. This crystal is a common "computer" crystal, but places the TX frequency in the high-end simplex segment. This is a bit too close to the pager-splattered end of the band for my liking, and doesn't match the band-plans. For now this is OK, I'll get a custom crystal cut eventually.

I didn't use shielded cans or variable inductors for the transmit coils (as specified by the article), rather I used fixed inductances wound on T37-6 toroid cores with bare 0.71 mm tinned copper wire. My LC resonance calculator and nH inductance meter were enormously helpful in making the selection and testing of the tripler and output stage resonators. Each stage was tuned with trimmer capacitors.

It was amazingly easy to get the TX-side working, I just built each stage from the crystal to the final amp in turn, testing as I went. Each stage is well behaved and peaks nicely.

Peter VK2TPM could hear the signal at his QTH several kilometres away when I connected the half-finished TX board into my flower-pot antenna. The DC input power was about 23 mW, and no special attempt was made to match the output into the load, in fact the series trimmer in the matching network was absent at this point, just a fixed 12 pF capacitor was used for DC blocking.



Upon finishing the TX circuit I did experience a bit of RF pick-up in the microphone amplifier 2nd stage. A 1 nF capacitor to ground discouraged its RF gain and eliminated the problem. The 2nd AF amp stage is located immediately adjacent the crystal oscillator stage and was picking up RF directly. The effect was not audible, but was visible on the spectrum analyser as weak 16.384 MHz sidebands either side of the carrier. This wasn't causing feedback, just high-frequency modulation of the signal. If nothing else it proved the bandwidth of the modulator, which is perhaps a surprise considering the 100 nF decoupling on the modulated rail, however the output impedance of the series modulator emitter is so low it could deliver a few tens of mVs of HF ripple into that kind of load.

Receiver

© 2000 - 2009 Alan Yates - All Rights Reserved.

As easy as the Transmitter was, the Receiver was hard. It fought me every inch of the way. I spent an entire day trying to work out why it was simply not super regenerating from about 130-160 MHz. It turned out to be a 10 nF decoupling capacitor on the cold-end of the detector resonator. The article specified 1 nF, and I originally intended to use this value, but I had a strip of 10 nF mono's on the bench, so I used them. At build time I did consider why 1 nF was specified in the first place, I figured it was avoid the exact problem that would befall my unit, decoupling resonance. (Lesson #1: Trust the original builder and your initial instinct.) When the unit wouldn't oscillate properly I assumed that I had damaged the capacitor on install - this is a pretty common fault, so I tested it in-place by ensuring it would shunt a HF signal (my standard decoupling cap test), it passed this test just fine. (Lesson #2: Test at the frequency of operation.)

My hubris about "modern components" being superior and likely "purely capacitive" at VHF turned out to be completely wrong. It took *hours* to work it out, but eventually I determined the entire decoupling network was resonant near the operating frequency. Much foul language later and I replaced the cap with a ceramic 1 nF, with its "flashing" broken off and scraped right back to the disc to minimise the lead length. This cured the problem.

For the longest time I had assumed it was the source coil - and in fact the first source RFC I used (a molded choke) was being operated above its self-resonant frequency and prevented any oscillation at all. I replaced it with a few turns on a ferrite bead which seems just fine now.

A couple of other minor annoyances/mistakes were worked through (like picking larger inductances and making the entire circuit so sensitive to stray capacitance it was a nightmare to tune - DUH!).



Eventually the unit super-regenerated right through the region of interest and the LNA stage was constructed. Initially I put the LNA drain coil too close to the detector coil and they over-coupled. This meant as I tuned through resonance on the LNA drain it would pull the detector so much it would shut down. Bugger! Moving the coils apart a little reduced this effect to acceptable levels, but the core of one still effects the other a little. I'm happy with the current coupling, and it is actually useful to help tuning the LNA resonator. As you rock it through resonance it will pull the detector, and by observing the wiggle on the spectrum analyser you can tell you've got it tuned up. The AGC action of the detector makes it hard to tune for maximum smoke otherwise, as the AF output doesn't change much at all even when the front-end isn't tuned up properly. Once you've got it nearly right you can use a weak signal to tune for best signal to noise.

© 2000 - 2009 Alan Yates - All Rights Reserved.



Note the pagers above the 2 metre band in this spectrogram. The hump in the noise floor is the receiver super-regeneration side bands. The smaller peak in between is the output of the Fredbox transmitter, the leakage from the unshielded prototype on my desk operating into a 47 Ohm load. It is rather disturbing that the pager signals are *larger* than this local signal just a foot or two from the spectrum analyser antenna.



I used J310s for the receiver FETs, and a 2N3904 for the audio amp. Although the main design requirement for Roger appears to have been flea-power, I think a better AF amplifier that can drive modern low-impedance headphones would be preferable. Only Jaycar now carries crystal earphones with a nice soft silicone ear piece. The one I used comes from DSE and it is hard-plastic - not very nice on the ear. I really hate these kind of earphones anyway, I'll probably be rebuilding it for a low-Z output at some point, but it does work pretty well as-is.

BTW: While I was in the "Special Hell" of decoupling resonance I took the RX down to the FM broadcast band, and up to the VHF-hi TV band. It works wonderfully in both, which isn't a surprise. However, by adjusting the drain-source feedback (then a trimmer, now fixed) I

Hall's regen on the FM band. The topology is more forgiving however, allowing grounding of the tuning cap. I also built several different oscillator topologies in desperation before I identified the decoupling fault, in one I got a Colpitts-like oscillator working with emitter coupled feedback to a tapped capacitor across the tank. This is something I should have thought about a *long* time ago, I'll probably build yet another FM broadcast regen using this topology for the detector, it seemed quite easy to control just by manipulation of the base voltage.

Boxing It Up

I am still tossing up between a cast Aluminium box, a custom box folded out of Aluminium sheet, or an Altoids tin. The circuit is small enough to just fit inside an Altoids tin but it probably won't fit with a battery. I'll pick up a centre-off momentary-one-side switch over the next week and finish off the radio one way or the other.



Note the use of an old telephone receiver as the microphone. It is nearly as large as the entire TX board. I'll have to find my electret mics, I know I have a bag of them somewhere that I got from a Rockby sale.

I'm strongly considering rebuilding the radio, perhaps through-the-hole to minimise its size. Although my prototype isn't too large as-is, it would be nice to neaten it up. Maybe I'll build it with fixed caps and variable inductors to save space too, although shielded cans are about the same size. It *might* be possible to tune the multiplier stages with stretched coils and fixed caps, this would make it much more compact and save money too if it ends up being kitted...

More TX Power

I am considering running the unit on 12 Volts to get a bit more RF out, and perhaps building in a small amplifier to get it up to 1 Watt region. This would probably involve a rebuild of the TX side to use a 2N4427 or similar final device, and a more robust series modulator transistor. This won't be efficient, but is probably easier to get going than a linear amp which would need careful drive adjustment.

I'll probably conduct some experiments around using a 2N7000 or VN10KM as the output device. The math suggests they may operate on 2 metres. I've already got them working on 6 metres in a brief experiment last month (must document that).

Comments

Working with VHF is fun! I find it a great learning experience, especially when you get problems like the resonant decoupling cap. That kind of thing really pushes your understanding of the physics and teaches you a lot.

I know a lot of HAMs won't touch anything above the bandwidth of their oscilloscopes. I can understand the frustration when something doesn't work, especially when you can't see why, but it really isn't that much worse at VHF. With just a diode probe you can achieve a lot. It does help enormously if you have VHF test equipment, for example I likely would have never noticed the HF modulation problem had I not had a spectrum analyser (although the HF was visible on the collector of the modulator drive amp, and most of us have a CRO that can see fine near 16 MHz).

A wavemeter can be helpful, if a bit retro, especially for making sure your multipliers are tuned up right and for looking for spurs. You can build one quite easily, it only needs to be a resonator with a detector and a LED or meter as a read-out. I'm a big fan of the biased 1N5711 through the decoupled bottom of the tank coil topology. For super-sensitivity you can use a MPSA18 as a DC amplifier. With a signal generator or dipper and a counter or scanner/receiver you can easily calibrate it. It can be used like a poor-man's spectrum

© 2000 - 2009 Alan Yates - All Rights Reserved.

My only advice when you get stuck is to trust the physics, do the math and follow your instinct when nothing is making sense. Rebuild parts of the circuit and test them independently. Measure what is actually happening and try to figure out what kind of misbehaviour in the circuit would cause the observed of behaviour. That will often solve an otherwise intractable problem.

Update 2007-06-05

I took the Fredbox boards to the local Homebrew Group meeting. I had both halves hooked up and talking across the room. Peter VK2TPM had brought along a digital audio recorder and did an interview with many of us in attendance. You can hear what I said about The Fredbox on Soldersmoke 62, and even a brief snippet of audio going through The Fredbox.

Also on the recording are Peter VK2EMU talking about the 80 meter challenge, John VK2ASU talking about his transmitter modules for the challenge (and an interesting diversion into IRF510 gate-modulation with some input from Brian VK2TOX - something I was thinking about back here, apparently Drew Diamond VK3XU has already produced a design doing just this). Mike VK2BMR also talks about his great VSWR/power meter project. His unit was absolutely beautiful, I was very much taken by the excellent job he did of cutting the PCB stock that made up the external directional coupler box, essentially flawless, perfectly square workmanship.

Update 2007-06-09

I've built a weak-signal source for aligning the receiver. One of the biggest weaknesses of the Fredbox receiver is that it drifts in frequency quite significantly with Vcc variations. Powered by a 9 Volt battery near the end of its life, it may drift enough to make the receiver completely off-frequency despite its poor selectivity. If I build this circuit again I'll probably put in a stabilized supply for the detector stage to avoid this problem.

© 2000 - 2009 Alan Yates - All Rights Reserved.



The signal source is a Pierce oscillator driving a tuned circuit which selects the VHF harmonic of interest. Because of the oscillator topology the crystal isn't pulled down as much as in the Fredbox circuit. The difference is fairly minor for my purposes, the poor selectivity of the receiver makes the difference in frequency of no real consequence. There is no active (or passive) multiplier, so the tuned circuit is merely extracting the harmonic energy from the oscillator. The harmonic energy available is very small, which is perfect for the application, giving an almost undetectable signal 1 metre away.

Update 2007-06-10

I've boxed up the Fredbox. As discussed earlier I went with the Altoids tin, despite this not allowing the battery to also fit inside the enclosure. I tossed up soldering an additional tin to the back to hold the batteries, but for now I've gone with the 9-volt battery snap just hanging out. It will work well with 6xAA battery holders which can just be held to the box with a rubber band.

© 2000 - 2009 Alan Yates - All Rights Reserved. XHTML | CSS | CSS toggle



For the RF connector I chose an RCA. I can hear all the VHF engineers cringing, but for the purposes of this prototype it works just fine. The Antenna is a half-wave of wire helical which is quarter-wave resonant (with some pruning). The former is a piece of centre conductor and insulator from RG-213 coax. The centre conductor was left in place and is soldered into the RCA plug centre conductor, adding some capacitive loading and shortening the length of wire needed for resonance. I have no idea if this is good or bad, but it works.



© 2000 - 2009 Alan Yates - All Rights Reserved.

I didn't find my stash of electret microphones, so I ended up just soldering the telephone receiver into the top of the Altoids tin. Ugly as hell, but also kinda unique. It looks somewhat like those Vietnam-war era VHF-low walkie-talkies.

I couldn't find a momentary-one-side toggle switch, so a centre-off on-both-sides switch was used instead. A special dummy load/diode peak-voltage probe was assembled for the final alignment. The carrier power ended up being near 25 mW on 12 Volts, on 9 Volts 10 mW just like Roger says in the article.

Update 2007-06-11

The 2N7000 on 2 metres experiment was a failure, it simply doesn't produce useful power beyond 90 MHz or so. However, it is very usable below 70 MHz. My input network was far from optimal, so perhaps with some more work it would be possible to get it working higher up, and I haven't tried an VN10KM in the same circuit.



I've also been fiddling around with grounded-base class-C multipliers. (Not just decoupled, biased base, the base actually soldered directly to the ground plane.) At first this seems a little weird, but if you pull the emitter low with a link-coupling to the previous stage collector current will flow. The advantage is excellent reverse isolation, which might help with stability with less than ideal layouts and devices. Such a topology was apparently quite common years ago with the 2N918.

1 comment.

© 2000 - 2009 Alan Yates - All Rights Reserved.



The GS3 antenna installation from the side of the van.

The lower base tube of the GS-series of antennas is made of a heavy gauge 2" diameter aluminum tube for strength and low RF resistance. (All the specifications for the antennas are on Gary's web site.) The loading coil is permanently and securely attached to a metal strengthening ring that is located at the bottom of the loading coil. The top whip that I chose to use with the GS3 is only 55 inches long. I needed to use a relatively short top whip to be able to have enough vertical clearance for obstructions. Ideally, the top whip should be at least a foot longer for better radiation efficiency and lower loading coil losses.

With a top whip this short, the lowest frequency the antenna will tune to is about 3700 kHz, but that is low enough for my use. (I do have a longer top whip that I can install that will allow the antenna to tune down below the bottom of the 80 Meter band.) With the 55 inch whip, the antenna requires about 1 to 2 turns of the loading coil to resonate on 10 meters. But at that frequency, the overall loss is quite low, and the antenna efficiency is fairly high. All things considered, the short top whip is a reasonable compromise for my use. Since the loss resistance of the loading coil is so much lower than the Bandspanner antenna, the overall results are better, plus I have the advantage of an antenna that I can retune on the fly from the drivers seat of the van.



The loading coil of the GS3 antenna.

The GS3 loading coil is a real work of art. The antenna is strong enough to withstand almost any impact. The coil windings are inside the sturdy fiberglass tube, which Gary molds around the loading coil. Plastic end supports are used to eliminate the excessive RF losses that are common to many other screwdriver antennas that use metal end caps on their loading coils. Most of the RF loss in the loading coil will be at the top end of the loading coil, and Gary uses only plastic end caps at that point to minimize the losses. Gary builds his antennas as I build mine - engineering considerations first, for a better signal.



The top of the GS3 loading coil.

The topmost few turns of the 14 gauge wire loading coil can be seen in this picture. The wire is firmly and permanently embedded into the inside of the fiberglass tube. This construction protects the coil and the sliding contacts from deterioration due to the weather. A sturdy 3/8-24 thread brass fitting to accept the top whip is mounted in the center of the upper plastic coil cover. The whip seen here is one is one that I have used with various mobile installations since I had my first 1961 VW bug. It is cut for the 6-meter band, and it has survived at least five different vehicles. The base stud was originally chrome plated brass, while the whip itself is made from what is apparently indestructible 1/4" diameter stainless steel.



The rooftop magnet mount system as seen from the rear of the van.

In this picture, you are standing on the roof of the van looking down at the wide spaced magnet mount I constructed for this antenna. Engineering-wise, a magnet mount is not what you want to use with a mobile HF antenna. But since I have had very good results using magnet mounts on this van (probably because of the large mass of metal under the antenna) I decided to try it with the GS3 and see how it worked. I figured that if it failed to perform well enough for me, I would just drill a few more holes through the roof and install a permanent mount.

This magnet mount system was modeled after a magnet mount that I originally purchased from the Lakeview antenna company some years ago. The original design used four magnets arranged in a square pattern similar to this one but with a considerably smaller footprint. It always worked very well, and never once in over 50,000 miles of driving did it come loose from the roof. That includes the time when I had a HamStick antenna ripped from the mount when it became snagged in an overhead obstruction.

This magnet mount system uses four magnets, each one measuring 5 inches in diameter. Because the steel sheet roof of the van is fairly thick, the magnets stick extremely well. The metal bars connecting the magnets are each made of two lengths of hard aluminum stock. Each section measures 1 inch wide by 1/4 inch thick by 36 inches long. Because there are two of these strips in each bar, this gives a total thickness of 1/2 inch per bar. Making each bar from two sections of metal instead of one solid bar allows for slightly more flexibility so that as the antenna moves on the mount there is less tendency to detach the magnets from the roof of the vehicle. The horizontal plate that holds the antenna is made from 1/4 inch thick by 2 inch wide by 23 inch long hard aluminum stock. All the bolts and other hardware are stainless steel.



The rooftop magnet mount as seen from the front of the van.

In this view you are standing on the roof of the vehicle looking towards the back. The common mode RF choke for the coaxial feedline cable to the antenna may be seen near the lower right magnet. This is closest to the driver side door.

Slightly above and to the right of the antenna base spring mounted on the two parallel fiberglass support rods are the two common mode RF chokes for the motor power leads and the reed switch wires. Common mode RF is the biggest cause of troubles and tuning problems in HF mobile installations. (See K0BG's article.) You can also see the shunt coil that is mounted at the base of the antenna next to the base spring. This is required to compensate for the capacitive reactance of the short antenna at HF.



RF coax cable and control wires to inside of van and 6-meter antenna.

Near the front of the van is a quarter wave 6-meter antenna. Unfortunately the 6-meter antenna interacts somewhat with the GS3 antenna on 20 meters. The unwanted interaction occurs because the 6-meter antenna and it's coaxial cable are resonant slightly below the 20 meter band. This interaction affects the reactance of the GS3 antenna causing the SWR across of the

20 meter band to be about 3 to 1. However this isn't a real problem since the auto tuner in the TS-480SAT easily handles that much mismatch.

Below the 6-meter antenna (seen here positioned towards the rear of the vehicle) is another magnet mount. I can install a scanner antenna or a UHF antenna on this mount if needed.

The RF coax and control wires from the GS3 are fastened together with plastic ties. These lines come together with the coax feedlines from the other two antennas where they go over the edge of the roof and down into the passenger compartment of the vehicle. A small but powerful magnet is used to hold the wires for the GS3 antenna in place on the roof of the vehicle.



RF feed to base of antenna.

A small metal bracket holds an SO-239 connector for the RF feed going to the antenna. Installing a connector here makes it much easier to remove the antenna and the magnet mount from the roof of the vehicle should it be necessary. There is a small piece of 1/4 inch thick clear plastic placed between the metal bracket and the roof of the vehicle. This prevents the edge of the metal bracket from scraping the paint on the roof of the vehicle as the magnet mount flexes when the vehicle is bouncing up and down on our very bumpy country road.

When the GS3 antenna is used with a pickup truck or a sedan, it is usually attached to a fixed mount. However, I didn't think that was a good idea when the antenna was mounted on the roof of the van. I thought that mounting the antenna on a stiff spring would be a better and safer option. I had unpleasant visions of a firmly mounted antenna encountering a low hanging Oak tree branch! A base spring it would be.

The spring that I chose for mounting the GS3 is Cal-Av model MARK-5. This is a heavy spring, (Cal-Av makes much larger springs) and weighs slightly over 2 pounds. That's much heavier than your Radio Shack antenna spring. It takes a lot of force to bend it, and it works quite well with the rather heavy GS3 antenna. When I am driving, the antenna does not start to tilt back from the wind pressure until I reach a speed of between 45 and 50 m.p.h.. But the MARK-5 is flexible enough to still allow movement when the antenna encounters tree branches and other obstructions.



The shunt inductor at the RF feedpoint.

Gary supplies a shunt inductor to use with the GS3 antenna when you purchase his antenna, but Gary's inductor did not have quite enough inductance to properly tune the antenna on 75 meters when it was mounted on the roof of the van. I suspect that is because of the large amount of metal of the van under the antenna makes a better than usual (for a mobile system) ground plane. I made a new shunt inductor a little larger in diameter following the excellent suggestions on K0BG's web page about antenna matching. It worked perfectly, and the antenna tuned up nicely on all bands, 75 through 10 meters. I used my AIM-4170 to sweep the antenna when adjusting the shunt coil.



Common mode RF choke for RF coax.

To prevent RF feedback into the gear in the vehicle, it is necessary to use some common mode RF chokes on all the lines from the antenna. For the choke for the RF coax cable, I used two Mix 31 ferrite split beads and ran a total of 6 turns of RG-8X coax through the beads. That provided sufficient impedance to eliminate and problems. The ferrite beads are attached to the magnet mount support bars with plastic ties.



Common Mode RF chokes for motor power wires and reed switch.

I did the same thing with the motor power wires and the wires to the reed switch on the antenna. A single Mix 31 ferrite split bead was enough for each set of wires. There is one choke on the motor wires, and one choke on the reed switch wires. There are 16 bifilar turns of wire on each toroid. They were wound according to the directions on K0BG's web page. Because the wire in these choke coils covers the outside surface of the ferrite beads I did not want to mount these chokes against a metal surface. Instead, I mounted them on two fiberglass rods, one of which passes through the center of each choke. The fiberglass rods are fastened to the aluminum bars with stainless steel hardware. The rods themselves were cut from inexpensive electric fence support posts.



Common Mode RF chokes for motor power wires and reed switch.

The wires from the common mode RF chokes connect to the wires coming from the GS3 antenna through a Molex connector. The connector is sloped slightly downwards. The end of the Molex connector closest to the antenna is the highest end of the connector. That end of the connector is filled with silicone RTV sealer to prevent rain water and moisture from getting into the top of the connector. The bottom end of the Molex connector closest to the chokes is left open. That allows any moisture that does get into the connector to drain out. Although you can't easily see it in this picture, the end of the brown cable from the MFJ antenna controller inside the vehicle connecting to the RF chokes has the top open end of the insulation where the wires exit the cable bent over and pointed down. This is visible as a slight downward bend just past the plastic tie wrap to the left of the wire crimp splices by the RF chokes. This prevents any rainwater from getting into the cable and working its way downward and into the vehicle.



Magnetic reed switch mounting.

The reed switch that connects to the antenna controller is mounted under that mass of tape you see just below the plastic tuning position indicator cover below the loading coil.



Magnetic reed switch mounting.

It's rather a sloppy looking job, but it does work. Gary does not supply the GS3 antenna with an internal reed switch. However he did mount a magnet on the motor shaft for me, so I was able to attach a reed switch to the outside of the antenna. If nothing else, having the switch on the outside of the antenna makes it easier to change the switch when it eventually fails. There's a lot of extra tape visible on the antenna where the switch is mounted. That's because there are several wire splices and some extra wire under the tape. I tried three different reed switches before I finally found one that worked satisfactorily. The reed switch that I ended up using is a Hamlin reed switch. The manufacturers part number is 5930011766643. Eventually I'll get around to removing the extra tape and straighten out the wiring to improve the appearance.



MARK-5 base spring.

This is one tough spring! But it's what this antenna needs because the weight of GS3 without a top whip is about 9 pounds. That's a lot of antenna to have mounted on top of a spring, but the MARK-5 handles it just fine.

I left enough slack in the motor and control wires from the antenna so that no matter what the position or tilt of the antenna is as it moves around on the base spring, the wire will not be flexed excessively. I also covered the wire with some convoluted tubing for additional protection from sun, wind, and weather.



Yeah; I know - it sure needs a good wash job! Well, the van always gets parked in the same direction, and as you know, moss grows on the North side of the tree...

The coax cables from the antennas on the roof of the vehicle and the brown control wire from the GS3 antenna come down from the top of the roof over the rain gutter and into the vehicle through the door seal. What looks like a cut out in the rain gutter is actually placed there by the factory to allow rain water to drain at that spot instead of running down over the door entrance. It made a convenient place to bring the cables over the edge of the roof.



I decided the simplest way to keep the cables in place for the door seal as it closed against the frame was to use some cable ties and self tapping sheet-metal screws. This method keeps a cables firmly in place so that once the door seal has taken a set around the cables I don't get any water leakage into the vehicle.

I use another cable clamp to keep the wires tightly against the door frame.



I use more cable clamps to bring all the wires straight down by the edge of the door frame.



The electronics package is a Kenwood TS-480SAT. It is anchored to the floor behind the driver seat. I used two wooden blocks to elevate the radio slightly from the carpet to allow for plenty of ventilation space. The extra cable length is coiled up and stuffed under the bottom of the radio. A terminal strip is mounted on the wall of the vehicle to provide connections for primary DC power, MFJ controller power, GS3 antenna motor leads, and the antenna reed switch.



I made a slip over wooden cover and painted it flat black for low visibility. When the cover is placed over the radio, someone looking into the vehicle from outside can't see the radio. The case has plenty of clearance space around the radio for ventilating air to get in and out. The back of the wooden enclosure is open so the cooling fans and the TS-480SAT can exhaust the hot air with no restrictions.



This is the view of the radio installation as seen from the rear passenger seat. (Note that the dog is an optional but self-installing feature of this vehicle.) The enclosure is sturdy enough that passengers can put their feet on the box with no damage.



Terminal block connections (by pairs) from left to right: GS3 antenna reed switch, GS3 antenna motor, DC power to the MFJ-1924 antenna controller, DC power to TS-480SAT, fused DC power from vehicle battery. The fuse protects the +12 V DC power line to the antenna controller.



Modified MFJ-1924 Antenna Controller

One of the advantages of a screwdriver antenna is that you can control it from the operators position. The simplest control is simply a double pole double throw switch. Flip the switch one way, the antenna tunes up in frequency, flip the switch the other way, and the antenna tunes down in frequency. This is a simple and reliable method of controlling the antenna, but it has the disadvantage that you don't have any way to tell where the antenna is tuned at any given time. You need some sort of antenna controller for that.

The MFJ-1924 antenna controller is designed to remember 10 specific tuning settings. It does this by counting the number of revolutions that the shaft of the tuning motor makes. In order to do this, the MFJ assumes that there are two things available from the antenna.

The first thing the controller needs is a contact closure of some sort, usually from a reed switch mounted inside the antenna. This tells the controller how many turns the tuning system has made. Note that this does not directly correspond to the number of turns in the coil, but rather how many rotations the tuning shaft has made. It doesn't matter though because the tuning system will make only X number of turns from one end of the tuning range to the other.

The second thing the controller needs is some way to tell when the tuning system has reached the end of its travel range. Most screwdriver antennas simply run the tuning mechanism into mechanical end stops and jams the motor when the end of the tuning range is reached. This stalls the motor and causes the motor drive current to increase dramatically. The MFJ-1924 controller is designed to sense this increase in current. At that point, the controller shuts off power to the antenna tuning motor.

Sometimes, for reasons known only to Murphy, the controller will lose track of how many counts have gone by. For this reason, the MFJ controller has a function which enables you to "bottom" the antenna. This function tunes the antenna to the lowest frequency, stops the drive motor, and then zeroes the turns counter. So far, so good. It looks like the MFJ-1924 antenna controller is just what I need to control the GS3 antenna. Well, it was, almost.

First problem - no reed switch in the GS3 antenna. That one was fairly easily taken care of. Gary had already installed the magnet inside the antenna, so all I had to do was to mount a reed switch on the outside of the antenna, run the wires down the lower mast of the antenna, and then run them through a common mode RF choke.

Second problem - no stalled motor current for the controller to detect. In order to protect the tuning motor in the GS3 antenna Gary builds in a slip clutch arrangement. That means that when the antenna tuning mechanism reaches the end of its travel, the motor will continue to revolve but the tuning mechanism stops moving. Unfortunately for the MFJ antenna controller, this has the disadvantage of not allowing the tuning motor drive current to increase very much above the normal running current. The advantage is that it is impossible to damage the tuning mechanism or burn out the drive motor by running it into the end stops. I found that I was unable to get the MFJ controller to sense the end of travel of the tuning mechanism. I even went as far as to dig into the MFJ's internal circuitry and increase the sensitivity of the drive current detection circuit, but in the end, I found that there just wasn't enough difference in normal tuning and end of travel motor current to make the controller work reliably.

The solution ended up being a combination of electronics and brain power. I made a slight modification to the controller. Now, when I need to reset the controller and "bottom" the antenna and zero the counter, I place the MFJ controller in its counter reset mode. This starts tuning the antenna to the lowest frequency position. Meanwhile, I sit quietly and listen until I hear the "thunk-thunk-thunk" of the drive mechanism slipping when it reaches the lower end of the tuning range. Since the antenna is mounted on the metal roof, the sound is quite audible. At that point I press the little Magic Button on the bottom of the controller.

I drilled a small hole in the bottom of the controller case and installed a normally open push-button switch. I have the switch button protruding just slightly out of the hole so it can't be pressed accidentally. The switch is connected in series with a 50 ohm resistor. The resistor and switch were then wired directly across the tuning motor wires coming from the antenna controller. When the button is pushed, current flows through the resistor from the output of the MFJ controller. This extra current is added to the current being drawn by the tuning motor. This makes the MFJ controller "think" the motor has reached the end stop and has stalled. This tells the MFJ controller to turn off the power to the tuning motor and reset the counter to zero.



I knew I would have to take the MFJ antenna controller out of the vehicle from time to time, so I installed a Molex connector on the wires coming from the controller.



This is the mobile installation as seen the driver seat. Everything can be easily reached with one hand without stretching.

I used several cable clamps to secure the wires from the MFJ antenna controller. The controller itself is mounted to the vehicle with some adhesive backed high-strength hook and loop fastener material. The open spot in the dashboard is for the vehicle entertainment radio. I pulled the old radio out while I was doing the installation of the ham rig. I have a new entertainment radio ready to install. It will replace the old one which was killed by a nearby lightning strike. <!>



Here is a bottom view of the modified MFJ-1924 antenna controller. The Magic Button is at the far right of the controller. The switch was salvaged from a computer, and it's held inside the case with a blob of hot melt glue. Not fancy, but it works.

The silver switch is a single pole double throw switch. It inserts a 50 ohm 1 Watt resistor in series with the antenna tuning motor power wires. This cuts the speed of the drive motor by approximately half. If I need to tune the antenna manually, I can slow it down by using this switch. That makes it much easier to "tune by ear" if I need to tune to an odd frequency that is not programmed into the controller. It's also very useful if I am driving and want to manually change frequencies. I don't have to take my eyes off the road to adjust the antenna.



Here is the MFJ-1924 antenna controller after my modifications to it. After installing the Molex connector on the end of the wires, I use some convoluted tubing for protection. Hmm... I see a Blue Box inside the controller. That's not standard; I wonder what it's for?



At the top left of the picture is the Magic Switch. It is pretty well buried under the blob of hot melt glue I used to hold it in place. Above the two black motor control relays you can see the extra toggle switch I installed to change the motor speed.

Oh, the blue box? That's a relay that I had to install to make the controller happy. It turned out that the MFJ controller occasionally missed counts from the reed switch. This caused the tuning to be off by a turn or two very often, resulting in a higher than desired VSWR reading. I spent some time looking at the reed switch pulses with an oscilloscope, and although I did not see anything wrong with them, the MFJ consistently miscounted. Installation of various types of RFI filters and RC networks failed to resolve the problem, which happened whether or not I was transmitting..Finally I decided that the CPU in the controller must be very sensitive to the rising and falling edges of the switch pulses. Perhaps adding a relay would fix the problem. Taking another page from K0BG (scroll down to the "Debouncer") I tried a small 12 volt relay and found that it did help resolve the problem. It was almost - but not quite - perfect.

Digging into my NOS parts junkbox, I found a Mercury wetted reed relay. (Sorry OSHA & RHOS) I managed to stuff it inside the MFJ controller. I took the relay coil DC power from the switched +12 volts DC, so as not to have a constant drain on the vehicle battery should the reed switch stay in the closed position at the end of the tune cycle. After installing the relay, the problem of miscounts went away. Perfect! I just have to remember that the controller - and the relay - must be operated in an upright position or the Mercury will roll around inside the relay and short out the relay contacts, resulting in no count pulses. I figure the reason this relay works so well is that unlike a normal relay, a Mercury wetted relay has virtually no contact bounce. Once the contacts close, they stay closed, and when they open, they open cleanly.



Because I didn't have a 50 ohm 1 Watt resistor on hand, I made one by connecting a total of 4 - 50 ohm 1/4 Watt resistors in a series parallel combination.

A Tree Antenna for the 600 Meter Band

Sept 8, 2007 - By W5JGV (updated January 01, 2008)

"Why put up an antenna when they're growing all around you?"



There are two antennas in this picture and one of them is not made of metal. Can you find them both?

If you look carefully, you can just see the horizontal single wire antenna in the background in the far right side of the picture. That is my 160 meter dipole antenna, which is about 20 feet above the ground. The other antenna is the large Oak tree in the center of the picture. Near the base of the tree trunk is the coupling coil which surrounds the trunk.

Yes, the tree IS the antenna!

My interest in tree antennas goes back many years, when I first read about some experiments using coils to couple RF energy to trees. Unfortunately, I neglected to save the article, and it was only much later that I was able to locate the source for the article.

Here are four articles that explain tree antennas - George O Squire Tree Antenna Patent.pdf - 1975 January Ikrath IEEE tree antennas.pdf - Robert Hand article.pdf and Signal Propagation at 400 kHz Using an Oak Tree with a HEMAC as an Antenna AD735330.pdf

It appears that there are two methods generally used to connect to a tree for using it as an antenna. The first is to drive a nail into the tree some distance up from the ground, and the second is to use a coupling coil around the trunk close to the ground. Since I prefer not to climb trees unless I really have to, I decided that the coupling coil would be the better approach.

Since little, if any, design data has been published on tree antenna coupling coils, I took a guess at what might work for the coil dimensions. I guesstimated that using a coil with about half the diameter of the tree trunk would be about right for the coil diameter. The length of the coil would be the diameter of the tree trunk. The number of turns was an unknown, but I figured that if the inductance was too small the tuning would be very sharp, and changing environmental conditions, rain, temperature, etc., might cause tuning problems. A larger inductance would be less sensitive to such things.

I decided on an inductance of about 175 uH as a starting point. That would require a coil of about 75 turns of about 10 inch diameter, or a total of about 195 feet of wire. Since I had a lot of #10 AWG bare copper wire available, that was used for the construction of the coupling coil.

Tuning the coil to resonance at 505 KHz would require approximately 575 pF of capacitance. At resonance, the coil losses would be about 10 Ohms, which would not be too good for transmitting, but for receiving, it should not pose a problem. At resonance, the impedance of the circuit would be about 30 Kohms so it would be a fairly good match for FET RF preamplifier.

Designing the coil was one thing, but how was I going to hold it in place against the tree? It had to be held away from the bark, or losses would increase when the tree got wet in the rain. After wearing out several pencils and using up the back of a lot of old envelopes, I finally hit on the idea of dropping each turn of the coil into a series of parallel slots cut into a length of plastic pipe. Then, when I bent the pipe around the tree, the flexing of the pipe would cause the slots to close up slightly and squeeze the wire tightly between the sides of each slot. At that point, all I'd have to do was to manhandle seven feet of flexible pipe and a hundred loose turns of copper wire into place while screwing the whole thing firmly to the tree trunk. I figured I'd work on that little problem after the coil was built.

Time to start construction!



Construction of the coupling coil was started by running a broomstick through a roll of Bonnie, KB5YSE's art studio wrapping paper and supporting the roll between two wooden chairs. The roll measures about 9 inches in diameter, and made a solid form on which to wind the #10 AWG bare copper wire for the coil. The free end of the wire was simply taped to the roll of paper and winding was begun. After about 90 turns were wound on the form, the coil was carefully removed from the form and set aside for later installation.



The wire I used was left over from a commercial AM broadcast antenna installation I did many years ago. It is bare, soft drawn, #10 AWG pure copper wire. It was just right for a coil of this size, since it is strong enough to hold its shape without any extra support.



Here is the finished winding while it is still on the winding form. It looks neat at this point, but as soon as I loosened the wire to remove it from the form, it promptly sprang into action and unwound into a larger diameter shape, and instantly piled up into what appeared to be a massively tangled heap! Fortunately, it was very easy to unravel, and placement of the wire coil onto the supporting tube went along without any unexpected difficulty.



All that wire has to be supported somehow, and I figured the easiest and cheapest way would be to take a length of 1" diameter plastic pipe and cut an evenly spaced series of slots into the pipe. As the pipe was bent around the tree and fastened in place against the tree, the slots would close up slightly as the pipe was bent. This would "put the squeeze" on the wire and hold the coil firmly in place. I drew a series of pencil marks spaced one inch apart on the pipe. The slots were then cut a little more than halfway through the pipe using a carbide tipped saw blade on a table saw. I made a "sled" for the saw to hold the pipe tightly in position as I cut the slots. The use of the sled also kept my fingers well away from the saw blade during the cutting process.



Well, here's the coil in place around the trunk of the tree. I'd like to say that the uneven placement of the ends of the tube were to ensure proper drainage of water from the tube when it rains, but in reality, I just screwed up a bit and didn't line things up quite right. (Hmm... I think I like the rain drain idea better!)



Seen from the other side of the tree, the coupling coil looks a bit better. The black screws that hold the pipe against the tree are not tightened up snugly. You must allow some slack here, or as the tree grows it will crush the pipe and eventually pull the screws right through the pipe, ruining the coil.



In this top view of the support pipe, you can see how the slots close up as the pipe is bent around the tree. As the slots close up, they pinch the turns of the coupling coil tightly. After the pipe is fastened in place, you cannot pull any of the turns through the slots. It's tight! The difficult part is that each turn of wire must be hand adjusted as the turns are placed into the slots. Of course, while I was doing this, about six other turns were trying to jump out of their slots. It turned out to be a real "juggling act" to get the turns to stay in place as I assembled the coil, but I finally beat the recalcitrant coils into their proper positions; order prevailed, and I got the coil finished at last.



Tune up time! Does it actually work?

A quick test setup was made using a portable radio and an old 435 pF dual section variable capacitor salvaged from a defunct broadcast receiver. The coil resonated with the calculated amount of capacity connected across it. As it eventually turned out, this was about the easiest way to tune the antenna. All I have to do is to position the portable radio antenna close but not touching the coupling coil. The radio is then tuned to the frequency at which I want to tune the antenna. When the coupling coil is tuned to resonance, the signal (or background noise) in the radio increases, indicating that the system is tuned to resonance at that frequency.



After the first tune up was so successful, I quickly constructed the elaborate weather cover you see here. Slits were cut into the bottom of an empty plastic water bottle and the tuning capacitor and feedline connections were stuffed into the bottle. This setup, complete with the Radio Shack clip leads, was used for several days before a more permanent enclosure was installed.



Now, this looks more like it! The enclosure is one that I salvaged from my Katrina-ravaged tower at my old QTH in New Orleans. The cabinet is at least 30 years old (Hoffman makes good stuff, you bet'cha!) and has been out in the sun and rain all those years. It is still weather tight using the original gaskets. It is Fiberglass and was starting to shed glass strands, so I refinished the outside of the enclosure.

There are two connections visible on the left side of the enclosure. The connection closest to the tree goes to the left ("cold") end of the coupling coil. This end of the coil is also connected to ground. The front-most connection goes to a tap on the coil that is 10 turns from the ground end of the coil. This is the feed point for the 75 Ohm coaxial cable that goes to the receiver in the shack.



A close-up view of the tap and cold end of the coil connections.





Stainless steel through bolts carry the signals through the Fiberglass walls of the enclosure. Sealer is applied to the bolts so that rain will not enter the enclosure. The bolts that hold the enclosure against the tree are not snugged up tight, there is room for the tree to grow. Both the bolts holding the enclosure to the tree and the screws holding the coupling coil in place will have to be backed out slightly every year or so.



The ground system for the coupler uses three steel screws that are driven into the roots of the tree. I figured that the tree probably has a better connection to the ground than I could manage to get by driving a ground rod. After running the screws into the roots, the screws are removed and the end of an aluminum wire are pushed down into the holes. The screws are then replaced. This gives a good connection to the damp wood. Do NOT drive copper or brass wire or screws into a live tree, as the copper may kill the tree. Iron, steel or aluminum is OK.



At the center ground-root, the wires from the other two ground-roots and the twisted pair of ground wires from the coupler circuit all come together. All the wires go about two and a half inches into the tree root. I used aluminum electric fence wire for the ground wires.



The ground wire goes from the tree roots to the coaxial connector on the bottom of the tuner enclosure.



A split-bolt wire connector connects the ground wire to the pigtail coming from the connector.





As you can see, the enclosure is mostly empty space. A much smaller cabinet could be used, but this one was available and didn't cost me anything



The frame of the tuning capacitor is simply bolted to an aluminum angle bracket and fastened directly to the grounded through bolt. Since the capacitor frame is grounded, I cam simply grab the dial cord drum on the end of the capacitor shaft and turn it as needed to adjust the capacitor.



Both sections of the capacitor are in parallel, and connected to the wire leading off to the right of the picture. That wire goes through a ceramic feedthrough insulator on the right side of the enclosure and then connects to the hot side of the coupling coil.





The wire closest to the back of the cabinet is the ground wire between the cold end of the coupling coil and earth ground. The wire nearest the front of the cabinet connects the coil tap to the center wire of the coaxial cable going back to the shack. Two spacers made from vinyl plastic tube that were used to hold the parallel wires in place.



I had previously installed this 100 uH coil in the enclosure to be used as part of a shunt feed tuned for my old tower on 75 Meters.

However, even after much tinkering, it never worked properly, so I abandoned that project. It was only after removing the coil to refinish the enclosure for this tree antenna project that I realized that the cause of the problem was. It seems that when I wound the coil, I covered the winding with what apparently was a VERY good clear varnish, because it prevented the E. F. Johnson squeeze clips that I used from making contact with the wire! No wonder it would not work!! All I can figure out is that I must have had total brain fade when I built the tuner. I left the coil in the enclosure, since it just looks so nice. <G>



Except for the RF preamplifier, this is the finished system. I simply ran the coax cable over the ground and back to the shack. It's easy to change if I need to, and the lawn mower misses it. In a year or so, the grass will have grown over it and it won't be noticeable.

While working on the tuner, I noticed this little guy walking across the turns of the coupler coil. If he had been parallel to the turns, I probably would never have noticed him.

CLOSING THOUGHTS -

- The tree I chose for this project is about 90 feet tall. There are others available that are taller, or more in the clear, or both, but this one was in a good spot for testing. It is far enough from the house so as not to pick up much "house noise" but close enough so that I can get a long extension cord out to it to run test gear. I may try a different tree at some point.

- I suggest using aluminum electric fence wire or aluminum clothes-line wire for making the coil. That would make the coil lighter and easier to handle during construction, and the losses in the coil will not be enough greater to worry about. One advantage of the #10 bare copper wire is that it fits perfectly in the slot cut by the circular saw blade. Other types of wire may require a different width slot and considerably more construction effort.

- I strongly suggest that you drill the holes for the mounting screws through the plastic support pipe BEFORE you try to attach the coil to the tree, unless you have at least six hands to hold everything.

- Having an extra person available when you attach the coil to the tree is a great help. I did it all by myself, but I waited until the dark of the moon, on a Tuesday, and I held my tongue >just< so. ;)

- I did not use any isolation transformers between the coupling unit and the coax feedline going back to the ham shack. I did not see any extra noise pickup from the coax cable either with or without the cable grounded at the tree end of the cable. Your installation may be different, of course. I happen to have (finally!) a very low RF noise QTH.

- This coupling coil was designed for MF operation. The tuning range of the coil with the capacitor I used is from roughly 428 KHz to 1150 KHz. No detuning of the system is noticed unless you bring your hand within a few inches of the hot end of the coil. A coil with fewer turns would probably work better for HF work.

- The signal pickup of the tree antenna seems about equal to or a little less than using one side of my 160 meter dipole antenna, which is about 20 feet high. It does seem to pick up a little less noise than the dipole, so the S/N ratio appears better overall. I have not had the tree-tenna in use long enough to make any accurate conclusions.

- I have not noticed any difference in signal pickup from day to night, nor does rain seem to change the antenna characteristics.

- Tuning of the antenna may be done by using the variable capacitor or by shorting out one or more turns of the coil on the "cold" end. This raises the operating frequency but does not seem to change the sensitivity of the antenna appreciably. Since the "cold" end of the coil is grounded, a simple relay arrangement may be used to short out some of the coil turns to ground to make frequency shifts remotely.

- The antenna works even better since I installed my RF preamplifier.

73,

Ralph - W5JGV - WD2XSH/7

[BACK]

10 element UHF antenna

de ON6MU


D8
D7
D6
D5
D4
D3
D2
D1
Drv
R
L9
L8
L7
L6
L5
L4
L3
L2
L1

Technical specs

Forward gain = 11,82 dBd
Front/Back ratio = 22 dB
SWR at 435 MHz = 1:1
Frequency range = 430...440MHz
Horizontal angle = 33°
Vertical angle = 38°

Length of the elements

R = 348 mm
Drv= 328 mm
D1 = 302 mm
D2 = 298 mm
D3 = 292 mm
D4 = 287 mm
D5 = 285 mm
D6 = 282 mm
D7 = 280 mm
D8 = 276 mm

Spacing

L1 = 145 mm
L2 = 50 mm
L3 = 124 mm
L4 = 149 mm
L5 = 173 mm
L6 = 194 mm
L7 = 208 mm
L8 = 217 mm
L9 = 225 mm

1.5 meter boom needed


159 mm
10
159 mm
box
Boom
Alu tube 10 mm, 15cm length
(Bazooka shoke)
connect tube to boom
50 ohm coax

Note: adjust length of the dipole if needed
Important: the dipole is not connected to the boom. It must be mounted isolated from the boom.

You can also use a folded dipole with a 1:4 balun (see my site for more info about building a balun)instead of a open dipole. To fine tune the SWR (in both cases) by in- or decreasing the dipole length or by moving the dipole between the first director and the reflector a bit. Sometimes it can help by changing the connection points on the dipole (connecting the coax a bit of the center).


connect tube to boom
dipole
bazooka tube
coax
boom



Horizontal stacking distance: 1075 mm
Vertical stacking distance: 933 mm

The elements diameter of the antenna may vary between 5...10mm and the dipole diameter may vary between 8...12mm (12mm recommended) without the need of changing anything to the length or spacing.
All elements except the dipole are electrically connected to the boom and may be mounted on top or through it.
The thickness/diameter of the boom may vary between 10...17mm.
Bazooka tube (RF choke to prevent rf wave currents): not critical, as long as it fits the coax snugly; examples: 15cm long 10mm diameter (for Aircel etc.), 15cm long 15mm diameter (for H100, Aircom+ etc.). Or you can use a few ferrite beads placed over the coax directly behind the driver instead.
Use a piece of isolator type boom (plastic tube, wood, fiberglass) of +/- 40cm if you mount the antenna vertical to prevent distorion of the radiation pattern.
The ideal SWR can vary a bit if the elements are isolated, raised from the boom or do to construction. A bit of experimentation with the driver length can solve this easily.
Note: the antenna can also be tuned between approx. 428...446MHz by adjusting the driver

START DOWNLOAD - VIEW PDF
Convert From Doc to PDF, PDF to Doc Simply With The Free Online App!
FromDocToPDF

Images of the 70cm Yagi antenna,
How Greg **SP5LGN** made it

Click to enlarge

Thanks Greg for the photo's!

Optimized 6-element UHF Yagi Antenna RE-A430Y6

70cm UHF 6ELEMENT YAGI ANTENNA

de ON6MU


D4
D3
D2
D1
Drv
R
L5
L4
L3
L2
L1

Technical specs

Forward Gain = 9dBd
Front-Back ratio = 13dB
SWR at 435MHz = 1:1
Bandwidth = 10MHz
Frequency range = 430...440MHz

Length of the elements

R = 346 mm
Dr = 326 mm
D1 = 302 mm
D2 = 298 mm
D3 = 292 mm
D4 = 288 mm

Spacing of the elements

L1 = 128 mm
L2 = 55 mm
L3 = 124 mm
L4 = 149 mm
L5 = 174 mm

Used material

Aluminum tubes of 8 mm Ø
Boom = 15 x 10 mm
15 cm alu tube Ø 10 mm for aircel or RG-58 coax. Use O 15 mm for RG213, H-100, Aircom.


158mm
10
158mm
box
Boom
Dr
Alu tube 10 mm, 15cm length (Bazooka shoke)
connect tube to boom
50 ohm coax

Note: adjust length of the dipole if needed Important: the dipole is not connected to the boom. It must be mounted isolated from the boom.

You can also use a folded dipole with a 1:4 balun (see my site for more info about building a balun)instead of a open dipole. To fine tune the SWR (in both cases) by in- or decreasing the dipole length or by moving the dipole between the first director and the reflector a bit. Sometimes it can help by changing the connection points on the dipole (connecting the coax a bit of the center).


connect tube to boom
dipole
bazooka tube
coax
boom



The elements diameter of the antenna may vary between 5...10mm and the dipole diameter may
vary between 8...12mm (12mm recommended) without the need of changing anything to the length or spacing.
All elements except the dipole are electrically connected to the boom and may be mounted on top or through it.
The thickness/diameter of the boom may vary between 10...17mm.
Use an isolator type boom (plastic tube, wood, fiberglass) if you mount the antenna vertical to prevent distorion of the radiation pattern.

Pictures and details of the optimized UHF Yagi antenna
430 Mc to 440 Mhz (420 Mc to 450 Mc @ 1:2 SWR)

- Michel F1SRC and how he made it:
  http://f1src.free.fr/antenne/yagi/yagi_6el_70cm.htm
-
- How Greg SP5LGN made it

Click to enlarge

Thanks Greg.

- How Geert ON3GVG made the antenna:



Note from Geert: he made the driver a few mm smaller to obtain an obtimum SWR in the band segment.
Thanks Geert!

Optimized 4-Element UHF Yagi antenna RE-A430Y4



The original antenna was designed as a moderately short antenna for the 10 meter band.

I originally wanted an antenna that would not hit everything overhead while driving, since it was to be installed on a van. I came up with an antenna that extended only 1.65 meters or about 5 feet 4 inches above the top of the vehicle. It had a calculated efficiency of 42% when compared to a half-wave dipole. It was my hope to be able to install a series of different loading coils to be able to operate on the other HF bands. However, calculations indicated that the antennas was simply too short to work well as the frequency was lowered. Something better was needed.

The Evolution of the Antenna Design

My first thought was to increase the length of the antenna below the loading coil. My reasoning was that since that portion of the antenna carries the highest RF current, then adding more length there would increase the radiation efficiency of the antenna more than would adding the same length to the antenna above the coil. Unfortunately, since the antenna is mounted on top of a van which is a rather high vehicle, that would place the coil at a dangerous height with regard to tree branches and the like. Since the loading coils were going to be rather heavy due to their sturdy construction, placing a heavy coil high up on a flexible support did not seem like a good idea. I decided to investigate what increasing the length of the upper portion of the antenna would do to the radiation efficiency.

It quickly became apparent that very good results could be obtained by increasing the top whip length. As it turned out, this was due to two factors. First, the antenna was center loaded, and second, increasing the top whip length greatly reduced the coil losses due to the smaller number of turns required. This also meant that I could use larger wire for the coils, which further reduced the losses. It was almost like getting something for nothing!

Since I had once a standard CB-length whip plus the magnetic mount and base spring installed on the van, I knew that a total height of 3 meters was workable, even though it did hit quite a number of overhead obstructions. I ran calculations to determine how it would work. The results were very encouraging, and I promptly set out to build the antenna. I still had the CB whip, and figured that I could simply cut the top end off of it to get the total length of 3 meters for the completed antenna.

While laying out all the parts on the ground to see how they would fit together, I looked at the CB whip and realized that I would only have to cut off about 17 inches. That seemed like a waste, and I really hated to cut that small amount off of a perfectly good antenna.

Just for fun, I decided to repeat the calculations to see what would happen to the gain if I left the extra 17 inches on the antenna. I was surprised to find that the antenna efficiency increased between 19 and 31 percent, depending on frequency. The trade off, of course, was that I knew the antenna was going to hit a lot more objects overhead than if I trimmed the 17 inches off of it. As a test, I assembled the antenna full length and drove around with it for a few weeks to determined how much of a problem it would be. I decided that I could live with it, as a necessary price for the increased signal strength.

This table shows the results of the calculations. Notice the large jump in gain between the original short antenna and the 3 meter antenna. Longer IS better! <G>

Computed Radiation Efficiency of Center Loaded Mobile Antenna vs. 1/2 wave Dipole Antenna

TEST FREQUENCY, MHz	**Original 1.65 Meter Antenna**	**Proposed 3.0 Meter Antenna**	**Actual 3.42 Meter Antenna**	**% GAIN INCREASE 1.65 > 3.0 Meters**	**% GAIN INCREASE 3.0 > 3.42 Meters**
1.95	0.09	0.3	0.4	333	31
3.9	0.5	1.5	1.9	300	26
7.3	2.0	5.5	6.9	275	22
10	3.9	10	12.4	256	23

14.2	7.6	18.8	22.8	247	22
18.15	12	27.7	33	231	19
21.2	15.7	34.6	40.6	220	19
24.9	20.3	40.6	40.6	200	0
28.4	24.7	40.6	40.6	164	0

Construction Details

I was able to make use of the basic antenna design and most of the parts when constructed the final antenna. I'll show you in the following pictures how I did it. This is a very easy antenna to build, and you can do it with some simple tools and parts from the local home improvement or hardware store.



When I made the 10 meter coil for the first 1.65 meter long antenna, I used 1/4" OD copper tube for the coil. I inserted the ends of the coil into a short length of 3/8" OD copper tube and then flattened the ends of the tube. I then drilled a 1/4" diameter hole through the flattened ends so they could be attached to the antenna posts. This coil should have had one more turn on it. That way, the turns would have been spaced a bit further apart. This would have lessened the coil losses somewhat. However, the calculated loss in power was not enough to worry about, so I never bothered to make a new coil for the antenna.

See that length of clear plastic between the ends of the coil? When using a self-supporting coil like this one, you MUST use an insulating brace like the plastic strip shown here or the white insulator between the two antenna sections will fracture when you hit a big tree branch with the antenna!



This is a close-up picture of one of the ends of the loading coil.

You can see the coil tube inside the larger flattened copper tube. The larger tube added structural strength to the ends of the coil and provided a larger area for drilling the mounting bolt holes through the coil ends.



A big antenna needs a serious mag-mount!

I purchased this magnetic mount for my mobile antenna years ago over the Internet - I don't remember where I got it - but it holds to the roof like a barnacle on a ships' hull. You can fold the antenna over until it touches the roof of the van and the mag-mount stays put. It requires two hands and a short pry-bar to get it loose.

See all that rust on the horizontal bar? That's from a cheap steel quick disconnect I used for several years. It finally rusted to then point that it made intermittent contact and I decided to get rid of it. So far, I have not found anything strong enough to replace it. I have broken two fairly heavy brass quick disconnects so far. So, for now, I just either tie the antenna down to the roof of the van or unscrew it when I have to go into a low garage. Needless to say, I strongly favor outside parking spaces!



This picture was taken before I installed the quick disconnect. It shows the lower end of the bottom section of the antenna. The antenna mast sections are constructed from hard wall copper pipe, 1/2" in diameter. A brass plug with a 3/8" x 24 threaded hole was pressed into the end of the copper pipe and hard-soldered into place. To hold the plug in place during the soldering process, I rolled several grooves around the outside of the copper pipe as seen here. I was careful not to roll them too deeply and weaken the pipe.



A small "weep hole" is drilled through the pipe wall just above the upper end of the brass plug that was soldered into the pipe. The hole allows water to drain out of the antenna and not sit inside and corrode the mounting bolt. Water WILL get into the antenna - you can't prevent it - so you might as well make provisions to allow the water to drain out.

To hold the antenna to the base spring, I used a length of threaded steel rod cut from a stainless steel bolt. After making sure that the threaded rod was the the correct length and that everything fit properly, I removed the mounting bolt from the base of the antenna and the base spring and used thread locking compound (OK, I used Super Glue, if you must know) to retain the bolt in the base of the antenna. That way I would not misplace the bolt when I had to remove the antenna from the base spring.



The Center Insulator and Coil Mounts.

The lower section of the antenna is a 1/2" diameter copper pipe about 60 cm (24 inches) long that extends upward to the lower coil support.

The support itself is made from a 1/2" sweat "T" fitting, a 2" length of 1/2" copper pipe and a 1/2" sweat cap.

The bolts holding the coil in place are 1/4" diameter x 1-1/2" long stainless steel bolts. A 1/4" hole is drilled through the center of each pipe cap before soldering it in place, and the bolts are temporarily held in place by gently tightening the nut visible in this picture.

The plastic center insulator is a 1/2" female-female threaded PVC coupler.

Each end of the antenna sections that thread into this coupler has copper adapters that go from 1/2" OD copper pipe to 1/2" iron pipe. These fittings have a male thread on them so they will screw into the plastic coupler which then becomes the antenna center insulator.

Using plumbers hard solder (not rosin core radio solder) and the proper cleaning flux, the copper components are soldered together.

Next, the interior of the copper sections is thoroughly washed with clean water to remove any soldering flux residue and then placed in the sun or some other warm place to dry.

When everything is dry, the nuts on the coil mounting bolts are firmly tightened, and the sections may be screwed into the center insulator.





The coil support posts shown with the 10 - 12 - 15 meter shunt strap in place.

Note that with this shunt strap in place, the plastic strengthening strip is not needed. This is because the shunt strap is made from a length of heavy silver-plated copper stock.

The top support for the loading coil is fabricated in the same manner as the bottom support.

To hold the top whip, a 2" long length of 1/2" OD copper pipe is soldered into the "T" fitting. Another female threaded brass plug is inserted into the top end of the 2" long pipe section and soldered in place.

Hey! What's that extra set of pipe fittings doing, and why are they there? (Keep reading for the answer!)





A (very) close up photo of those extra pipe fittings.

I always had a problem getting the antenna loading coil lined up "just so" on the mount. When you screw the antenna into the mount, you never know where the loading coil will be pointing when the mounting screw is tight. With coaxial mounted loading coils, this is not a problem, but this antenna has the loading coil mounted off-center from the mast. Provision needs to be made to adjust the coil position. How come?

Well, the loading coil must always "trail" the antenna mast; that is, the coil must be directly behind the antenna mast when the vehicle is moving. The reason is rather obvious - after you hit the first big low-hanging tree branch! If the coil happens to be in front of the antenna mast, the coil may become snagged on the tree branch and instantly becomes part of the local roadside litter. When the coil is mounted behind the mast, the mast simply slides harmlessly beneath the tree branch, the coil does not get hit, and all is well.

In order to accomplish this alignment without resorting to the use of shim stock, various thicknesses of washers, and all sorts of other chicanery, I decided I had to have a way to be able to rotate the coil around the mast in some way. Since everything was soldered together, I came up with the idea of using a pair of threaded mating fittings that I could simply twist to get the alignment exactly correct. I drilled and threaded a pair of holes through the outside (female) fitting so I could use a pair of stainless steel screws to lock the fittings in place after after the adjustment was complete.



The 40 Meter loading coil in place on the antenna.

Notice the stainless steel nut at the bottom of the coil. This nit, and another one at the top of the coil holds the coil on the antenna. Changing coils is easy. Simply remove the nuts at the top and bottom of the coil, swap coils, and replace the nuts. Tighten firmly - but not excessively - and the PVC plastic acts as a lock nut to keep the coil in place. Still, it's a good idea to carry a few spare nuts in the vehicle in case you drop one while changing coils.



The complete Coil Set for the antenna.

From left to right -

Top Row: coil form made from 2" OD schedule 40 PVC pipe; old self-supporting 10-meter coil made from 1/4" copper tubing; plastic support spacer, used with self-supporting coils; copper shunt ring, used to tune loading coils.

Bottom Row: loading coils for 160-meters, 75-meters, 40-meters, 20-meters, and 17-meters.

The 160 and 75-meter coils are wound using #14 AWG Nylon insulated wire; all the rest of the coils are wound with #10 AWG THHN insulated wire. Note that no terminals are used on the coils - the wire ends are simply wrapped around the mounting bolts. When the coil is attached to the antenna, the wire loops are pressed against the copper coil mounts to make the electrical connection by the coil form when you tighten the 1/4" nuts from the inside of the coil form.



General Coil Construction

The coil form is made from a length of 2" OD PVC pipe. I cut each coil form about 3/4" longer on each end than the spacing between the mounting bolts. NOTE: Make sure that each coil form fits easily over the mounting bolts before winding on the wire or you'll have problems changing coils.

After winding the wire on each coil, an application of epoxy adhesive (J-B Kwik) was used to keep the coil turns in place. A coat of black spray paint was applied for appearance and to make the white plastic coil form less noticeable. NOTE: Apply the epoxy AFTER you have adjusted the coil to resonance.

If you just wind the wire on the coil forms directly, this will result in the coil "springing back" and becoming loose on the form when you release the wire after winding it. I wound several extra turns on each coil as I wound it on the form, then removed the coil from the coil form and then squeezed it down around a slightly smaller form (actually a spray can of insect repellent.) I then removed the now slightly smaller diameter coil and gently screwed it onto the coil form, where it remained tight enough to stay in place properly.



The 75-Meter coil

The calculations indicated that I would need to use #22 AWG wire to get enough turns on the coil in the space I had available. The losses would have been quite high, if I used that small size wire. So, this coil is wound with #14 AWG wire. Since using larger wire would not allow as many turns in the same length, I could either use a larger diameter form (too much wind resistance and negative "eye appeal",) or a longer form, continuing the extra turns below the lower mounting bolt (wind resistance, and higher RF losses.) Something better was needed.

Remembering my switching power supply transformer winding experience, I decided to try winding the loading coil for the antenna in the same manner, that is, complete the first layer of the winding in the usual manner, then "jump" the winding end back up towards the start of the first layer and then continue the second layer of the winding towards the end of the first layer of the winding. This is sometimes referred to as a "Z" winding.

You can see the black painted bolt in the right of the photo that holds the end of the first layer of the winding. From that bolt, the wire that begins the second layer "jumps" back to the left of the second layer of the winding. The end of the second layer is brought out to one of the mounting bolt holes. You can see the epoxy that holds the windings in place.



The 160-Meter Coil

Wound in the same manner as the 75-meter coil, the 160-meter coil required only 60% of the number of turns as would be needed if the windings were in a single layer. The trade off is that there are several stray resonances of the antenna system using this coil, but none of them cause any problems with normal operation. Since less wire is used in this coil than would be used in a single layer coil, the copper losses are less, but the dielectric losses are slightly higher due to the overlapped windings. However, the use of the "Z" winding method minimizes the dielectric losses as much as possible. The measured Rac loss of this coil is less than the originally calculated coil using #22 AWG wire.



Tuning Ring in place inside the 40-Meter Coil

As it turned out, I didn't need to use it, but I found that I could insert a shorted copper ring inside the coil and adjust the antenna tuning plus or minus a turn or so on each coil. I also tried using various types of ferrite and iron tuning slugs, but found that the copper ring produced less extra loss in the coil than did the ferrite core. When the ring is placed parallel to the turns on the coil, it acts like a shorted turn and reduces the inductance of the coil. The ring fits in place by friction, and after adjusting it, it may be permanently attached with some epoxy. Further minor adjustments may then be made by bending the ring slightly.

ADDITIONAL LOADING COIL DATA

(This loading coil data was added on 24 July 2010)

Since this article went on-line, I have received quite a few questions about the exact construction of the loading coils. Although it is possible for a careful observer to look at the photos posted on this page and deduce the construction of the coils, it is probably a good idea for me to post a more complete description of the construction of the coils so the reader can more easily build them.

In the chart below, all the coils are wound on lengths of Schedule 40 white PVC pipe. The actual end-to-end length of the coil windings is shown in the chart. Due to the thickness of the insulation on the THHN wire, the actual diameter of the finished coil will be close to 2.5 inches. The inductance values are what I measured on my completed loading coils.

FREQUENCY BAND	INDUCTANCE	WIRE GAUGE	NUMBER OF TURNS	COIL LENGTH	COIL DIAMETER	COIL FORM
18 MHz	1.5 uHy	# 10 THHN	5	3.5 Inches	2.5 Inches	2" PVC sch 40 Pipe
14 MHz	3.8 uHy	# 10 THHN	9	3.5 Inches	2.5 Inches	2" PVC sch 40 Pipe
7 MHz	16.5 uHy	# 10 THHN	22	3.5 Inches	2.5 Inches	2" PVC sch 40 Pipe
4 MHz	55 uHy	# 14 THHN	Layer 1 = 34, Layer 2 = 6, overlaps layer 1	3.75 Inches	2.5 Inches	2" PVC sch 40 Pipe
2 MHz	100 uHy	# 14 THHN	Layer 1 = 34, Layer 2 = 20, overlaps layer 1	3.75 Inches	2.5 Inches	2" PVC sch 40 Pipe

Note that the coils for 160 and 75 meters have overlapping coil windings. This can be avoided by using smaller diameter wire or using a longer length coil form. Depending on where you place the top layer of wire on the first layer (near one end or near the center of the first layer of wire) the inductance of the coil will vary somewhat, and you may need to adjust the number of turns on the coil. Tuning on the lower frequency bands will be more critical, so you should expect to do some tuning as needed.

Please note that these exact coils may NOT work for you in your particular situation. Factors such as whip length, height above ground, size of the vehicle, etc., will require tuning the antenna, either by tweaking the number of turns on the coils or adjusting the length of the antenna's top whip slightly. In my case, "close enough" was good enough, because I planned to use an antenna tuner in my mobile station. In any case, the dimensions given in the chart above should get you "in the ball park", as it were.

Tuning the Antenna

A center loaded vertical antenna will not present a pure resistive load at the base of the antenna. Usually, a matching network is added at the bottom of the antenna to cancel the reactance and transform the lower than 50 Ohm feedpoint resistance to something close to 50 Ohms. Since this antenna was designed to operate over several HF bands, a single matching network is impractical. Instead, I chose to connect the antenna through a length of low-loss coaxial cable to an automatic antenna tuner (ATU) inside the vehicle within reach of the operator and out of the weather.

To make the best use of the antenna with this set-up, the loading coils for the antenna should be tuned to resonance at the high end of each band. The antenna will then look electrically "short" to the tuner, which will then be able to tune the antenna to the desired operating frequency. If the loading coil in the antenna is tuned to a frequency below the top of the band, then operation above that critical frequency will cause the antenna to look

ON6MU's "Vipormutant" Antenna
RE-AHFV14P

Versatile Inexpensive Portable Multi-band Tunable Antenna

de ON6MU
revision 2

AdChoices RF Antenna Design Antenna 2M 70CM Antenna

Features

- Only 3 meters high fully extended (effective radiating element height)
- Less then one meter inserted (no element is larger then one meter including the tunable section)
- Tunable without the use of an extra tuner (just switch till you get the best SWR)
- Covers all frequencies from UHF to 7 MHz without a tuner
- UHF (tuned by de- or increasing the length of the antenna) 3/4 2*5/8 4*5/8
- VHF (tuned by de- or increasing the length of the antenna) 1/4 5/8 2*5/8
- HF (tuned by switching)
  6 meters (1/4 1/2)
  10 meters (1/4)
  12 meters
  15 meters

17 meters
20 meters
30 meters
40 meters: with large counterpoise and/or with longer radiating element, or extra tuner
80 meters: if radiating element is > 5 meters, or with large counterpoise and/or with extra tuner

- Works with or without cointerpoise
- Ideal as portable or balcony antenna
- Compact and extremly portable
- Not too critical on the material or sizes of the elements
- +- 50 watt input
- SWL's Note: tunable on all frequencies between the bands mentioned above

What you need to build the "Vipormutant"

- 5 (or more depending on how high you want your boom) alu tubes
- piece of hard insulating tube (+- 7 cm), examples: plastic, nylon, bamboo...

- some low loss RG174 50 Ohm coax

- carbon/ferrite bead or toroid (to act as a choke)

- a few meters of 0,75mm enamelled copper wire to make the coil

- SO239 (PL259 female)
- Paint, silicon, glue etc. to seal things up
- Plastic box to mount over the coil and where we'll put the switch and SO239 connector
- 12 position rotary switch
- a few innox hose clamps

About the "Vipormutant" antenna:

Well yes, one must have a name HI...It is nothing more then a base coil loaded antenna, but with a selector direct on the base to tune the antenna.
Most of us don't have the luxury of building a 1/4, 1/2 or even a 5/8 wavelength vertical antenna for HF. We have to settle for something a little shorter. (A lot shorter, in the case of people following the FCC's Part 15 rules, which limit them to 3 meters in size.) Shorter vertical antennas can give acceptable (but not spectacular) performance.
I needed a highly (HF) portable antenna to use with my FT-817 which should have the highest possible frequency range (also VHF) and still compact enough to take along almost anywhere! The antenna should be versatile enough to allow further experimenting, to allow being mounted on a balcony, caravan, outdoors etc... So I came up with a compact vertical (dismounted no higher then 1 meter) with a "tuner" directly connected to the antenna radiating element (the best possible place a tuner can be).
The "Vipormutant" tuning principle gets energy into the antenna on a wide range of frequencies, but the design of an antenna is what controls what happens to the RF energy from there. For some antennas, the antenna is simply not complete without a radial system, or at least a counterpoise. Other types of antennas need no RF ground system at all. Most reference books on antennas provide solid guidance on radials and counterpoises, but only for antennas cut to a specific frequency. When using the "Vipormutant" it will also act like tuner and at the best place a tuner should be: directly beneeth the antenna! So the rules have to change somewhat because the "Vipormutant" almost operates across the full range of HF frequencies unto UHF. It doesn't need a counterpoise to work, but the efficiency will increase when you do use it.

Considerations:

- If the length of the conductor is very short compared to a wavelength (< wave/4), the electric and magnetic fields will decrease dramatically within a distance of one or two wavelengths.
- It is impossible to make a small antenna to radiate as efficient like a big antenna.
- Ground losses affect radiation patterns and cause high signal losses for some frequencies. Such losses can be greatly reduced if a good conducting ground is provided in the vicinity of the antenna.

The coil/tuner

Wind 0,8mm enamelled copper wire around the isolator (+- 16mm diamter) and make a tap every xx turns (see fig. 2 and 3)

Fig.1



Fig.2



The coil dimensions isn't too critical.

Relatively short antennas behave like lossy capacitors and present a high impedance load to the transmitter due to the large amount of capacitive reactance that is present. The loading coil helps to tune out that reactance. Tuning out the reactance is important because a tuned antenna will accept and radiate much more power than a mismatched antenna.

When the loading coil is installed at the bottom of the vertical radiator, we call it a "base loaded" antenna. Base loading requires the smallest amount of inductance to achieve resonance.

The shoke

Is made out of miniature 50 Ohm coax (rg174) that goes a few turns through the carbon/ferrite bead or toroid. You can also use a Snap-Together Ferrite Choke Core.
If a ferrite is put over a cable which includes both signal and return lines, it will have no effect on the signal (differential-mode) current but it will increase the impedance to common-mode currents. This is because the differential currents, by definition, sum to zero in each wire pair and therefore there is no net magnetic field. If there is no field, the ferrite is invisible. But the common mode currents do produce a net magnetic flux and this flux is concentrated in the bulk of the ferrite, leading to an increased impedance for these currents only. The choke should prevent any mantle currents flowing and should decrease RFI.

The effectiveness can be increased by looping the cable several times through the core, but the benefit is limited at higher frequencies by the stray capacitance between the turns of the cable.

Fig 3.



4 turns

Highlighted

Start Download - View PDF

Convert From Doc to PDF, PDF to Doc Simply With The Free Online App! download.fromdoctopdf.com

The base insulator





The vertical radiator "driver" element and tuning box

I used a plastic box of 130x70x40mm. On top and bottom I drilled a hole to fit the driver element (radiator of +/- 40cm length)and boom (also +/- 40cm length).

On the side I drilled a hole for the rotary switch and the SO239 connector, whilest on the opposite side I drilled a hole to fit a "ground" bolt where I can easily connect the counterpoise and/or ground to if needed.

Fig 4



Fig 5


-antenna
strong water-proof PVC box-
-band switch
shoke
ground bolt -
-SO239 UHF connector
-alu boom
ON6MU

This is how things are connected inside the box:

Fig. 6


antenna base element
box
isolator
rotary switch
RG-174
ferrite core (shoke)
SO239
Ground rod, Boom

Example

The rotary switch is used for tuning the antenna on each band. The first position allows UHF/VHF ranges.
Tuning is done by sliding in/out of the elements.
The "lower" the switch (higher inductance) the lower the resonance frequency of the antenna.

Remember, and this is important too, to seal everything up so no moisture can penetrate the antenna!
Because the radiating vertical antenna elements are made out of separate pieces that fits inside each other and are tightened by hose clamps, the construction isn't waterproof.
If you use a hollow isolating piece you need to to prevent moisture from getting inside the box (via the places where the elements are hold together). I've used a rubber "stopper" that fits snugly on the bottom of the driver element and glued tight.

Black paint finishes the job:

fig. 7



using a round box
In my first design I used a plastic box of 50mm diameter and 9 cm heigh. On top I drilled two holes: one for the driver element (radiator of 40cm) and a hole for the rotary switch (as was used in the first prototype).

fig.8: The main driver element and tuning unit finished



This allows it to be used on almost any boom or can be extended to use with or without vertical elements!
Ideal for experimenting!

Featuring Today

The antenna construction specs

All elements are made out of aluminum.
Fig. 9


Ø2,5 mm
1m
Ø6 mm
1m
Ø10 mm
1m
Ø13 mm
40 cm
16 mm
7 cm
10cm
Ø19 mm
40 cm
Ø22 mm
1m

This makes the antenna effective radiating elements a total length of 3 meters. The boom elements can be chosen freely and on your needs. A short one (one element of a meter), a medium sized one of several 1 meter tubes or none at all! The bottom piece where the boom is "connected" too is 40 cm and can/could be put directly in the ground (if made pointed for sure). Or you could fix it in a umbrella stand. Use your imagination HI.

Examples of "Vipormutant's" utilization

Used it on a balcony:




random length
wire
Balcony

This could cover even the lowest HF-bands!

Use it outdoors without grounding:


Brick or wooden pole



Use it outdoors as a shortened "dipole" balanced antenna (rotary switch set approx. in the middle):



Frequencies below 7 MHz could easily be match 1:1 SWR if total length of the "dipole" > 4 meters
Further tuning can be done with selecting a different impedance using the rotary switch.
Different lengths of wire can be used (an example: one part 3 meter, the other 5 meter or more)

Use it outdoors with ground or counterpoise:





Radials and Counterpoises basic purposes:

1. To improve the RF ground conductivity for the ground current return path. Unless you live in a salt-water swamp, your ground conductivity makes a very poor path for the return of ground currents. This increases the ground losses and reduces the efficiency of an antenna that needs a good RF ground.

2. To provide a counterbalance for the feed point of the antenna to reduce RF radiation back to the radio room. The "Vipormutant" changes the rules because there is no single frequency that you will be operating on, so all of the thumb rules for 1/4 and 1/2 wavelength radials don’t apply. It is possible to be either a purist or a pragmatist in deciding what radials to put in place.

3. Number of radials: More is better, up to a point. In carefully controlled experiments, it has been proved that increasing the number of radials from 2 to 15, or from 4 to 16, produces significant increases in signal strength. Further increasing the number of radials to 60 only produces 1 to 2 dB of increase in field strength. Follow this link to see some of the empirical data.

4. Where to put the radials: For a semi-permanent installation, it is customary to bury the radials a few inches down in the soil. This makes it much easier to mow and walk in the area around the antenna. However, some experimenters have gotten an improvement in performance by raising the radials and the antenna base a few inches above the soil. Raising the antenna and ground system several meters above the earth, for example by installing the base of the antenna on a roof-top, can improve the antenna's performance by reducing capacitive earth losses.

While the "Vipormutant" will provide a good match with a poor RF ground system which will will able you to transmit, your antenna efficiency will be low. Nevertheless, by using a tuning circuit directly at the antenna radiating element losses are kept to a miminum. Getting the greatest efficiency out of your antenna system needs a proper RF ground unless you’re using a balanced antenna system

The efficiency of the antenna increases by using a counterpoise. However, the antenna can be tuned perfectly without!

Don't forget to check these out:

ON6MU Homebrew projects
Radioamateur related projects

ON6MU Ham mods
Modifications of transceivers

ALLIED ELECTRONICS & AUTOMATION Allied Doesn't Take Lighting Lightly MW MEAN WELL SHOP NOW

73"

Have fun and my best 73"

Guy, ON6MU
http://www.qsl.net/on6mu

Comments, pictures or experiences with my antenna are always welcome!

ON6MU



MARTIN - G8JNJ

ECLECTIC AETHER - Adventures with Amateur Radio

Index E-Mail & Comments

Revolutionary New Design

Please note that this webpage was originally intended to give guidance about how to improve the performance of an antenna that is similar in design to that of the Comet CHA-250.

In the time since I originally wrote this webpage, I have developed a completely new type of broadband vertical antenna, the Terminated Coaxial Cage Monopole (TC2M), which does not require a tuner, is simple and cost effective to construct, and offers performance that is comparable to, or better than, other similar sized multi-band antennas.

Many prototypes of the antenna have been built and tested for long periods of time, and the final optimised design has been granted a UK Patent.

Information about this new antenna, including construction information, was featured in the May & June 2014 issues of Radio Communications Magazine, published in the UK by the Radio Society of Great Britain (RSGB). Following its publication, I was awarded the RSGB 2015 Bennett Prize in recognition of a 'significant contribution or innovation which furthers the art of radio communication'

Full details are now available for non-commercial use.

Click here for a PDF copy of the original article

Or alternatively visit the TC2M Antenna Website for more details www.tc2m.info

I strongly encourage you to try the new design as it provides much better performance than the antenna featured on this web page.

G8JNJ Broadband HF Vertical Antenna - Requires no tuner - copied by many companies

The following notes show the design and construction of a Broadband HF Vertical antenna which does not require a tuner, and which is capable of providing moderate performance on all bands from 7MHz to 28MHz (reduced performance from 3.5MHz to 51MHz).

It follows an extensive period of investigation with a Comet CHA-250 'style' antenna using a specially constructed 5:1 transformer. I tried and rejected many other designs before finally arriving at this version.

The basic design and principles originally outlined on this page in 2008 have been copied by many companies (mainly in North America) without any acknowledgement of the source of the copyrighted design. They sell their products for many $100's of US dollars and continue to make outlandish claims about their performance.

So if you wish to experiment and construct a fairly compact multiband antenna, that works moderately well, doesn't require a tuner and can be built for less than £20 if you shop around for parts, this may be for you.

Please note that this antenna will NOT out-perform a beam antenna at 100ft on the HF bands or a 260 ft long wire on the LF bands - It works about as well as a 7m long vertical antenna can do !

I find this antenna particularly useful for HF beacon monitoring using Faros software, WSPR personal beaconing or HF ALE operation using PC ALE (most of which are free).

You can compare the performance of this antenna against others, by taking a look at my transmit and receive signal reports for various bands, which have been automatically logged on the WSPR database.

Folks considering making a G5IJ antenna (which is not what it seems as the concept is flawed, it's actually equivalent to a thick wire radiator fed via an impedance transformer, with the coax acting as a counterpoise) or those using fishing poles, 4:1 baluns and remote auto-tuners may also be interested in this design, which has minimal loss.

The principle of operation is that a specific length of radiating element is chosen so that it presents an average value of impedance on most amateur bands. A special matching transformer is attached at the feed point to convert the antenna feed impedance to something close to 50 ohms.

Note that all of these 'easy to match' antennas work in more or less the same way by incorporating resistive loss into the matching transformer, or by adding external resistors such as the Diamond BB7V and BB6W.

Most have a low value of Shunt resistance which makes the SWR look good when a length of wire with a high feedpoint impedance (Voltage fed) is attached (1/2 wave and even multiples). This can be observed as providing a low SWR when no antenna wire is attached to the transformer.

Some others also include a high value of series resistance which makes the SWR look good when a length of wire with a low feedpoint impedance (Current fed) is attached (1/4 wave and odd multiples) or an electrically short wire is used. This can be observed as providing a low SWR when the output of the transformer is shorted to the ground connection of the screen of the coax.

When a good low loss transformer is used, both of the above tests should produce a very high SWR reading, as there are no transformer losses to mask the bad match (open circuit and short circuit).

When a resistor is connected across the transformer in order to improve the match, it will absorb a lot of the applied power that would ideally be radiated. The value of the resistor will determine how much power is wasted and what the worst case SWR will be. If the transformer has a resistor that is equal in value to it's secondary impedance then it will dissipate a large amount of the applied power, but with no antenna connected the SWR will be close to 1:1. The exact amount of power that will be radiated will depend upon the antenna wire feed impedance at a particular frequency, but it is likely to radiate more power when the antenna feed impedance is lower than the the value of load resistance.

If you use a resistor that is twice the value of the transformer secondary impedance then the maximum SWR with no antenna connected will be 2:1. This is usually the maximum SWR most radios can withstand without the SWR protection operating to reduce the output power to a safe level. As the value of resistance is higher than in the previous example, less power will be wasted heating up the resistor and more power will be radiated.

The antenna can be ground mounted or attached to an insulated pole, which will further improve the HF performance (as shown later).

The graph below shows the measured VSWR of a 6.5m vertical wire antenna (supported on a 10m fishing pole) fed against 10 buried radials, and terminated with differing values of resistive loads.



The Red trace is with a 50 ohm termination, Yellow with 100 ohm, Orange with 200 ohm, Green 300 ohm and Blue with 450 ohm. So the lowest overall VSWR is with a resistive termination impedance of around 200 to 300 ohms. The two markers show the 1/4 resonant frequency (M1 at 10.5MHz) and the 1/2 wave resonant frequency (M2 at 21MHz).

If some additional loss through the transformer and approx 2dB loss through coax cable is factored in, and the radiating element and radial system are fine tuned, it is possible to achieve a VSWR of less than 2:1 on most amateur bands.

My improved transformer design still has some through loss, but it is much less than the original Comet clone. This results in several dB improvement in antenna gain compared to the Comet version (A/B measurements made with remote receiver).



Graph showing loss through transformers. The Blue trace is the Comet clone and the Red trace is my improved transformer.

The performance of the new transformer is much better than previous versions I have tested. I am no longer able to measure any improvement in radiated signal strength by connecting a remote tuner at the end of the low loss coax feeding the antenna (apart from 1.9MHz & 3.6 MHz where an improvement of approximately 2dB was observed).

The through loss is much lower than the original version and the antenna design trades improved radiation efficiency for slightly a higher VSWR figure.

However because of the reduction in through loss (and its masking effect on VSWR), the VSWR is slightly higher than that of the Comet clone.



The graph above shows the VSWR measured at the base of a 6.5m high vertical supported by a 10m fishing pole. The Red trace shows the 6.5m wire fed directly. The Green trace shows a 300 ohm resistive termination, the Orange trace shows the vertical fed via a Comet style transformer, and the Blue trace shows the vertical fed via my modified version of the transformer. The two markers show the 1/4 resonant frequency (M1 at 10.5MHz) and the 1/2 wave resonant frequency (M2 at 21MHz).

Note that the transformer adds a progressively greater shunt resistance at low frequencies which improves the VSWR. Further improvements in matching can be obtained by using short radials, or counterpoise wires instead of a large earth system. This increases the resistive component of the antenna impedance at the lowest frequencies. Although this reduces the antenna gain, it makes very little difference to the overall performance on the low frequency bands, as the antenna is far too short to be efficient on these frequencies anyway. These facts may horrify you, but a lot of commercial antenna manufacturers use similar techniques, they just don't tell you !

Many people would also argue that 2 or 3dB loss through a matching network is too high. But my tests suggest that even a good ATU can add between 0.5 to 1.5dB dB loss, and that many 4:1 baluns, especially those wound on iron powder cores can also add a further 1 to 3dB of loss, especially when feeding low impedance or highly reactive loads. So 2 to 3dB loss may be fairly average, and I would argue that many amateurs already have this amount of loss in their transmission path without realising it, as they have never taken the time to measure it.

The chart below shows the VSWR measured via a 10m long cable at the base of the antenna. Note that any additional feeder losses will further improve the figures. For example when a typical length of coax cable (with 1 to 2 dB loss) is connected the VSWR will improve further. e.g. A 3:1 VSWR load will measure as 2.3:1 with a 1 dB cable loss and 1.9:1 with 2dB cable loss.

Frequency	**Gain**	**VSWR**
1.9 MHz	-26dBi	8.5:1
3.6 MHz	-6dBi	4.2:1
7.1 MHz	+1dBi	2.1:1
10.1 MHz	+1dBi	1.75:1
14.1 MHz	+1dBi	1.46:1
18.1 MHz	+3dBi	1.94:1
21.1 MHz	+4dBi	2.25:1
24.9 MHz	+4dBi	2.73:1
29 MHz	+2dBi	2.38
51MHz	+1dBi	1.5:1

A better indication of the performance can be obtained from the plot shown below. Note that the angle of radiation tends to become more elevated on 29MHz & 51MHz slightly reducing the useful gain.



The basic components of the antenna are a 9m fishing pole, 6m support pole, home built 5:1 transformer and some wire. These are configured as shown in the diagram below.


G8JNJ - Broadband Vertical Antenna - V1.2
Optional – 10m long horizontal wire for improved NVIS performance on 80m
6.5m of 5mm dia coax tie wrapped to pole. Only outer braid connected
9m long fishing pole, top section removed, bottom section attached to support pole
Optional – 4 x 1m long radials for improved performance on 6m
5:1 RF transformer
Connected to radiating element 2m from bottom
6m long conductive support pole, insulated from ground
10m long radial wires connected to outer of coax connector & support pole
Plastic bottle base insulator
Coax to radio
Ground
Guy wires insulated from ground
1:1 ferrite balun
Coax outer braid connected to earth on 'radio' side of balun
© G8JNJ 2008
www.g8jnj.webs.com



A diagram showing construction of the 5:1 transformer is shown below. Note that this is not the same as the Comet balun details of which can be found here. The ferrite rings seem to be similar to type 33material and can be obtained from CPC part number CBBR6924 or CBBR6945 Both of these are supplied in packs of five and should just slide over standard 15mm dia copper water pipe. Unfortunately some of the ferrite rings I have bought recently are slightly smaller, and so will not fit over standard size copper water pipe. If you encounter this problem you may have to buy brass tubing from a model shop instead.


5:1 Broadband RF Transformer Construction
To Antenna
2.5mm copper wire
Foam insulated inner core from 75ohm satellite TV coax
50mm x 15mm Brass tube or Copper water pipe
25mm ferrite ring CPC CBBR 6924 or CBBR 6945 3 glued together
Loop
To Radio
© G8JNJ 2008
www.g8jnj.webs.com

Here's one I made earlier !



Note - Since I originally built this antenna. Several people have tried to use it with an auto-tuner in order to improve the performance. This is not likely to make much difference, because of the losses in the transformer. If you do wish to achieve better efficiency with an auto-tuner. Then I suggest you use the 4:1 Unun wound on type 52 Iron powder material shown at the bottom of the BBV7 section of this page.

The 1:1 balun which is used to isolate the coax feed at the base of the antenna uses five of the same ferrite rings glued together with five turns of coax passed through the centre. Ideally you need at least four of these in order to achieve the best results.



FAQ's - Answers to questions I have been asked about the antenna

How well does it work ?

It depends upon what you choose to compare it against, and on which bands. For example I would expect it to perform fairly well against something like an 18AVT on the HF bands, however it will not work anything like as well as a 132ft wire on the LF bands. I estimate 8 to 10dB worse on 80m and 20 to 30 dB worse on 1.9MHz. The only fair comparison would be against the same radiator and counterpoise, but fed with an auto-tuner in place of the matching transformer, as this would represent the best performance you could achieve in this configuration. This is how I measured the antenna performance and the standard I judge it against. By its very nature the transformer version will be worse than this ideal, but I think it's worth trading a few dB of additional loss in order to obtain broadband operation. Note that since I originally built this antenna. Several people have tried to use it with an auto-tuner in order to improve the performance. This is not likely to make much difference, because of the losses in the transformer. If you do wish to achieve better efficiency with an auto-tuner such as an LDG Z11Pro. Then I suggest you use the 4:1 Unun wound on type 52 Iron powder material shown at the bottom of the BBV7 section of this page

In summary it compares favourably with other multiband vertical antennas of similar height on the HF bands but not quite as well on the LF bands.

Why can I hear stations, but they can�t hear me ?

You would expect that if you can hear stations you should be able to work them, however the lower noise floor on receive means that you can sometimes hear stations on the LF bands which would otherwise be masked by QRM on larger antennas. In summary the signal level is lower but the signal to noise ratio is much better.

You can hear DX with it, and it seems to work very well on RX, but perhaps not quite as well on TX, which seems strange as you should expect reciprocal performance. I can measure my transmitted field strength remotely and compare the antenna against other designs and it seems to match dB for dB on TX and RX (apart from obvious absolute gain differences). Yet sometimes I call stations on the vertical and they don't come back, switch over to the other antenna and they do, even though on receive they are the same strength, it's a very odd phenomenon but I suspect it's simply down to a better receive S/N ratio on the vertical (as opposed to the absolute signal strength). I find it works well as a receive antenna on 160m and one constructor John, G4IJD, has heard a ZL station on 80m at reasonable strength. In comparisons I have found it outperforms a Datong active antenna mounted at the same height.

What is the resonant frequency of the antenna ?

The basis of the antenna is that it is NOT resonant on any of the desired frequencies. It is designed so that the impedance presented by the radiating element on wanted frequencies is close to the secondary impedance of the transformer for maximum energy transfer. The use of a 7.1m radiating element is not accidental (the radiating element is actually a ¼ wavelength long at 10.4MHz). It□s intended to present a manageable impedance on the desired amateur bands, whilst not being too long (under 5/8 wave) for effective operation on 10m and 6m. Making the vertical element longer would cause the angle of radiation to increase in elevation, reducing the useful gain.

How can I further improve its performance ?

The main problem is balancing the parameters of maximum vertical length (which needs to be kept below 5/8 wave at the highest frequency), sufficient length to be efficient at the lowest frequency, a moderate feed impedance (to suit the transformer ratio) for the radiating element at all frequencies required for TX, and ideally some horizontal component to keep the folks who require NVIS performance on 80m happy.

You could replace the transformer with an auto-tuner, increase the number and length of radials, increase the height of the support pole, use lower loss coax, increase the transmit power, add an 80m long offset top loading wire. The permutations are endless - but it□s not the antenna you started with !

How can I make it work better on the LF bands ?

Performance on 80m is a bit of a compromise. I think it□s about 6dB down on an equivalent length radiating element and counterpoise, but with an auto-atu in place of the transformer. Feeding the transformer with a remote atu made about 2dB improvement on 80m over the transformer alone. On the HF bands adding a remote atu made very little difference.

However the perceived lack of performance may be due to several factors. One is that it□s a lot shorter than a ¼ wavelength on the LF bands, another is that being a vertical it has very little upward radiation, so it is a poor performer for NVIS coverage on 1.9 and 3.6MHz. Hence once you get outside the ground wave coverage there is nothing until past about 500 Miles so it□s very poor for semi-local contacts.

The main difficulty is managing the impedance presented by the radiating element on the LF bands. For example a 7m long wire over an average ground plane on 1.9MHz is typically 10 □ J1310 and on 3.6MHz 10.5 □J640. As you can see the resistive element is very small in relation to the transformer secondary impedance and the reactive component is very much greater and capacitive. With my transformer design I have tried to roll off the impedance ratio at the LF end to get a closer match to the radiating element but it□s still a long way out. From this I hope you can get a good feel for what design parameters can be traded, and those which will remain a compromise. The ideal efficient broadband antenna is a □holy grail□ for antenna designers, and I□m sure there are a lot more qualified persons than myself who haven□t found it yet.

John, G4IJD suggested using the antenna in a horizontal configuration. I have been playing with this idea, and the best configuration so far seems to be something like an 11.2m horizontal wire at 10m above ground, with the transformer also at 10m, fed with coax and with the 1:1 choke balun fitted to the coax at 2m above ground.

However I suspect that the mechanical difficulties of supporting the transformer at 10m may make an inverted L easier to implement.
To achieve this all that's required is the addition of a horizontal wire at the top of the existing vertical section.This would add an NVIS component, increase the radiation resistance and improve the efficiency on 80m. The question is, how long should the horizontal wire section be. I suggest keeping the vertical section the same length as the original design, but add a horizontal wire of length 12.2m or 27.2m long, to make the total length of radiating element either 19.2m or 34.2m.

These lengths should not present an impedance of much greater than 1K on any of the desired transmit frequencies.You can use the LVD programme on this website to give an estimation of feed impedance if you wish to experiment with other lengths (also see my notes relating to auto-tuners). Using a 12.2m horizontal top wire will add a useful NVIS component on 3.6MHz, but you really need to get upto 27.2m long before it becomes effective. However at this point the antenna is starting to become fairly large. Another option would be to use two top (or more) wires of differing lengths say a ratio of 1/3 & 2/3 in order to provide mismatched currents which would result in better NVIS coverage.

One other idea I have tried, is to add a helical winding at the top of the vertical element in order to improve performance on the LF bands without adversely affecting the HF bands. 400 turns of close spaced wire 2m down from the top of the radiating elment with about another 0.5m of wire above it works well for 160m and also provides some improvement on 80m.

Another alternative would be to try using the transformer to feed something like a 60m dia horizontal loop, which would also improve NVIS coverage on the LF bands.

How can I make it work better on 6m ?

Performance on 6m is reduced beacuse of the length of radiating element. Ideally a vertical antenna should not be longer than 5/8 wavelength, or most of the radiated energy tends to fire up towards the sky. I have tried modeling the antenna with a four element capacity hat at various heights, and have found that four 1m long radials attached to the main vertical radiating element 2m above the feed point, results in approximately 6dB more gain towards the horizon. There is still some energy radiated up towards the sky, but this is more than offset by the improvement in gain at low angles. This modification does result in a slight reduction in gain on 10m, but this may be a worthwhile trade. So far I have not had the opportunity to try this, but hope to do so in the near future.

Could I use some other form of loading ?

There is a problem in adding any form of loading as it introduces varying impedances at other frequencies. A loading coil or trap which is introduced to improve performance on the LF bands will have an impact at the HF end. The least problematic method would be to add a loading coil towards the top of the radiating element and / or capacitive loading. A technique such as Petlowany loading is also a possibility, see my washing line antenna.

John, G4IJD, has been experimenting with capacity hat loading, using four sloping wires from the top of the radiating element. I have included some of John's comments below

>>>Having first established that my effort came close to your results (base of antenna still at about 3m agl) my "gut" feeling was that T (or maybe capacity since T is really out of the question) loading would improve the match on top band and 80m without significantly altering the loading on the HF bands.

For test purposes I have attached 4 wires, all equal in length to the main element, to the top of the antenna.By bringing these wires out from the base I can see any effect on the matching quite easily.

Using all four wires extended out to about 5m from the base at 90 degrees to each other, the VSWR on top band drops to about 1.4:1 when measured at the transmitter and so an ATU is not required. Matching on all other bands can then be taken care of by an ATU. To return everything to normal I simply connect all wires together at the base of the main element.Haven't tried all combinations yet but will keep you posted.

I have no idea what effect this has on the radiation pattern but in my situation the extra wires double up as guy wires and stabilise the antenna in high winds thus boosting neighbour confidence. Of course all this is possible because the base is easily accessible from a ladder.

I think this antenna will appeal to a lot of people as long as they read all your notes and don't expect too much from it. As an all band convenience antenna it's ideal for me. I can think several uses for a second one. <<<

More analysis of this is required, but it struck me that the wires could be brought bact to the base of the radiating element to form a cage folded monopole, perhaps something like this. Some broadband military HF antennas use this technique, often in conjunction with a high power terminating resistor.

Why did you use coax cable as the radiating element ?

When I modelled the antenna I found I got better results using a larger diameter conductor. I reduced the diameter until the results started worsen. The best compromise was to use a diameter of around 10mm, and coax cable was the cheapest option. If you have aluminium tube or an old CB antenna this would be better still. Just cut the length so that it is a ¼ wave at 10.4MHz as this will give the correct matching impedance at other frequencies. If you need to use a shorter support pole it is possible to use a □lazy□ helical winding for the radiating element, say up to 4 turns per metre length it should be OK, however this technique tends to introduce unpredictable secondary resonances which could put □lumps and bumps□ into the frequency response.

How critical is the height of the mounting pole and the length and number of radials ?

They are not too critical, for example, three 5m long radials would be fine, however I would suggest that all the radials or counterpoise wires and the mounting pole are not connected to ground and the length does not exceed 10m. You may wish to experiment with the lengths and □angle of dangle□ to achieve the best impedance match on the required frequencies. On the LF bands longer radials would be better but you could try adding say two inductively loaded radials tuned on the LF bands of interest. As I previously stated you can mount it higher or lower within certain limits. But if this is not easy you could consider ground mounting with at least four radials. In this case adding more radials will further improve the performance.

I have obtained very good results by mounting this antenna on top of a building with a metal clad roof. I did not use any radials, but mounted the transfomer close to the edge of the roof and connected it to the cladding with a short metal strap.

If either of these two methods are not possible, you can ground mount the antenna and connect it to as many radials as possible. However the gain will be significantly lower than using an elevated feed and counterpoise / radials.

Why is there a 1:1 choke balun at the base of the mast ?

The purpose of this is twofold. It is designed to provide a high impedance □break□ in the feed cable at a specific point so that the vertical section of the coax (and the support pole it runs along) is □lifted□ above ground to form a counterpoise, the whole antenna then becomes similar to an off-centre fed vertical dipole. If the balun was fitted at the top of the pole, there would still be coupling between the outer of the coax below the balun and the support pole. The second purpose is to prevent electrical noise and other unwanted interfering signals which may be carried on the outer of the coax from being conducted into the receive path. It also eliminates RF on the coax when used for transmit purposes.

Please note that simply using coiled coax as a balun does not provide a high enough choking impedance for this purpose.

Can I use chokes from CRT monitor cables or some others I have in my junk box ?

I have tried a large selection of ferrite materials, including some which I have recovered from scrap CRT PC monitors. There is a very large variation between types (even those from the same make and model) I think they just use whatever they can get hold of. If you have a large number (at least 10 and ideally 30 - 40 or more for 1.9 & 3.6MHz) and thread them over coax they can be used for the 1:1 balun to suppress noise which would otherwise be induced on to the received signal. However the variation in characteristics makes them difficult to use for the transformer, if you wish to obtain repeatable results. Also be very careful about ring cores you buy at radio rallies or on e-bay. Many of these are actually made from iron powder, and are designed for low frequency (əMHz) use in switched mode power supplies. They are not suitable in this application. If you have an impedance measuring bridge you can test them to see if they are made of ferrite. As a rule of thumb with one turn you should obtain about 2.5uH at 2MHz, 1uH at 10MHz and 0.4uH at 30MHz for a 20 x 30mm core with 7mm dia hole if it is similar to type 43 material. However if you do this I cannot guarantee it will work as well as a transformer made with the specified parts.

Do I have to use copper or brass tube ?

No, Wolfgang, OE1MWW has successfully used braid from RG213 coax. He also tried using just a single wire loop, but found that the closer coupling provided by the coaxial tube winding produced much better results. See further down the page.

How can I increase the power handling ?

The main problem with power handling seems to be at frequencies around 18 to 22MHz where the length of radiating element is around ½ wavelength which presents a high load impedance. This results in power being dissipated in the ferrite material used in the transformer core. Using a metal box and heatsink and bonding the ferrite material to the box with thermally conductive epoxy resin may help. More cores can be added, but this will lower the frequency at which the maximum impedance transformation occurs, which may increase loss on the LF bands. Another suggestion is that the ferrite cores are replaced with powdered iron and the quantity increased. You may need to use 20 or more powdered iron cores to achieve the required inductance. The input impedance with no radiating element connected should measure at least 200 ohms at the lowest operating frequency.

Why did you use the inner from coax cable for the transformer secondary winding ?

I picked this for its high voltage insulation properties. Most foam insulated satellite TV coax has a breakdown voltage of around 1.8KV. This should be adequate for power levels up to about 200watts on frequencies where the radiating element presents the highest impedance (and requires maximum feed voltage) to the transformer.

G8JNJ - 01/06/2014 v4.3

Who else has made one ?

despite the fact that my original design artwork was clearly marked © G8JNJ 2008, several companies have copied and sold key parts of this design without crediting the source.

I'll let you guess who they are, as the manufacturer of one of the four shown below threatened to sue me for putting a photo showing the inside of **"their"** matching unit on my website !









Update

At least these guy's are a bit more open, but still no credit to the source.

In early 2016 a video entitled "Inside of an Alpha Match" was posted on YouTube by user "steinhest" showing the inside of a matching unit as sold by Alpha Antenna.

Follow this link to the video:-

www.youtube.com/watch?v=IbLAeqqRdNc

Here's a still frame captured from the video



In the comments section of the You tube video

"Chameleon Antenna" posted:-

"Wow!! They're now using what we've been using in our HYBRID, HYBRID-MINI and EMCOMM II for years!!!! It's a 5:1 UNUN!! LOL"

"ChameleonWalker" later posted:-

"This is the pictures of our 5:1 transformers.

https://www.dropbox.com/sc/3dfx1137sbu3jmc/AACt-xhgYo-DF9BgOhDV67wla



The larger one is used in the HYBRID, HYBRID-MINI, EMCOMM II, TD, TD Lite and the WINDOM 40 and the small one is used in the HYBRID-MICRO.

It took few days to get the pictures done because we were entirely sold out on just about everything! We're currently manufacturing 200 HYBRID, HYBRID-MINI and HYBRID-MICRO and tonnes of others products...

With any of the above mentioned antennas and with a proper installation this is the type of performances that can be possible to achieve with them. Our transformers are made in a way to reduce the losses to a minimum."

Here's a more detailed view of the larger transformer.



Here's another video that has been posted on Youtube. This one shows the inside of both an Alpha and Cameleon matching unit.

https://youtu.be/4n30XykCChY

They look very familiar don't they ?

Note that both Chameleon and Alpha Antenna get consistently good reviews on Eham http://www.eham.net/reviews/ so why not try building one yourself.

Other amateurs who have experimented with this concept are:-

Marty KN0CK

Giovanni IW2EN

John. G4IJD

Jerry. G4GGZ

Peter, PE1DCD

Gernot, OE1IFM http://www.oe1ifm.at/index.php?option=com_content&view=article&id=54&Itemid=59 Built for the V53ARC WSPR beacon



Wolfgang, OE1MWW



Dirk, PE1CZW



Sven, OZ6SI



RAFAEL DE SOUZA



Miguel, PU3XPG



G8JNJ - Last updated 22/07/2016 v4.6

All content is made freely available for personal use only. Please acknowledge the author if content is used elsewhere or contact me if you wish to make commercial use of any material. © Martin Ehrenfried G8JNJ 2007 to 2018.

9:1 Magnetic Longwire Balun / Unun



Completed 9:1 UnUn

These are sometimes known as a *Magnetic Longwire Balun*. Its really an impedance transformer (9:1) to feed a high impedance, end fed (unbalanced) random wire which is likely to be a few hundred ohms, and transform it into something closer to a 50Ω (unbalanced) coaxial input, hence UnUn. It can however also be used as a balun by not grounding the other half of the balanced output. The toroid is a T130-2 Iron Powder core, with 3 x 9 turns of 18SWG enammeled copper wire, and the connections can be seen below.

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More


450Ω
To Wire Antenna
A1
B1
C1
A2
B2
C2
50Ω
To Radio
or Tuner
Ground Rod or
Counterpoise
9:1 UnUn - John M0UKD

The triple winding connections. 8 turns is shown here, but more turns is preferred. 10 would be ideal.


End Fed
Antenna
A1
A2
B1
B2
C1
C2
Pri: 1 turn
Sec: 3 turn
1:3 turns ratio
1:9 impedance ratio
50Ω to 450Ω
50Ω
Ground
9:1 UnUn - M0UKD.com
M0UKD

9:1 UnUn Schematic

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More


GND
Long Wire
NC
50 ohm
Input

Completed windings


Long
Wire
50 Ohm
Input
Ground

The completed unit.

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More

Antenna Here is a Dipole

You've probably heard this phrase in many QSOs. Just what *is* a dipole antenna, and why are they so popular?

By James W. ("Rus") Healy, NJ2L
Assistant Technical Editor

Dipole antennas have been widely used since the early days of radio. Simplicity and effectiveness for a wide range of communications needs are the reasons for this—and they're also the properties that make dipoles worthy of your consideration. There's more to building and installing an effective dipole antenna system than choosing the wire and insulators, as you'll see. Next month, I'll discuss choosing the right feed line for your dipole, and related subjects.

What is a Dipole?

The dipole gets its name from its two halves—one on each side of its center (see Fig 1). (In contrast, a *monopole* has a single element, usually fed against ground as a vertical.) A dipole is a *balanced* antenna, meaning that the "poles" are symmetrical: They're equal lengths and extend in opposite directions from the feed point. In its simplest form, a dipole is an antenna made of wire and fed at its center as shown in Fig 1. (This may look familiar: You may have received a QSL card with a sketched dipole, resembling Fig 1, to denote the antenna the other station used during your contact.)

To be *resonant*, a dipole must be electrically a half wavelength long at the operating frequency. A dipole's resonance occurs at the length at which its impedance has no reactance—only resistance—at a given frequency. As it turns out, that resonant impedance range is compatible with many common coaxial feed lines. Within limits, however, resonance isn't necessary for a dipole to be effective, as I'll explain a bit later. Resonant half-wave dipoles range in size from about 16 feet for the 10-meter band (28-29.7 MHz) to 260 feet for the 160-meter band (1.8-2 MHz). See Table 1.

The lowest frequency at which a dipole is resonant is known as its *fundamental resonance*. A dipole works best at and above its fundamental-resonant frequency. But if a total-length limitation imposed by property boundaries or the spacing of available supports keeps you from doing this, make the antenna as long as you can, even if it's not a half wavelength. Resonances repeat, for half-wavelength-long dipoles, at *odd multiples* of the fundamental-resonant frequencies. For instance, a dipole resonant at 2.5 MHz is also resonant at 7.5 MHz, 12.5 MHz, and so on. These higher-frequency resonances are known as *harmonic resonances*.

As I mentioned earlier, a dipole doesn't have to be resonant to work well. More important than resonance are good construction and efficient power transfer from the transmitter to the antenna. Using an antenna tuner, you can match dipoles that are far longer or shorter than resonant length, but the feed line plays an important role in efficient power transfer, as I'll discuss next month. If you're primarily interested in operating on only one band, a resonant dipole is a good choice. If you're interested in multiband operation with a single antenna, the picture is a bit different. In this situation, it's a good idea to make the antenna resonant at the lowest frequency you plan to use it on (that's where the antenna is longest, because antenna length is proportional to wavelength).



Fig 1—One of the simplest antennas used by hams, the dipole is also one of the most effective, considering the relatively small space it requires. In its simplest form, a dipole is a wire fed at its center.

Table 1

Approximate Lengths of Half-Wave Dipoles for the MF/HF Ham Bands*

Frequency	*Length*
28.4 MHz	16 ft, 6 in.
24.9 MHz	18 ft, 10 in.
21.1 MHz	22 ft, 2 in.
18.1 MHz	25 ft, 10 in.
14.1 MHz	33 ft, 2 in.
10.1 MHz	46 ft, 4 in.
7.1 MHz	65 ft, 11 in.
3.6 MHz	130 ft
1.8 MHz	260 ft

*General equation for half-wave dipole length: $\ell = 468 \div f$, where ℓ is length in feet and f is frequency in megahertz. This equation yields good starting points; you may have to lengthen or trim your antenna to achieve resonance. See the sidebar entitled "Dipole Construction and Adjustment."

Why are Dipole Antennas so Popular?

For almost any kind of MF/HF operation, dipoles are easy to build and install, and they give good results when put up at any reasonable height. "Reasonable heights" are anywhere from a few feet and up, depending on the band. A good general height guideline is half a wavelength or more, but that's impractical for many of us, especially on 40, 80 and 160 meters. At the least, a dipole should clear any surrounding buildings, and other large obstacles, for good performance.

Many hams do quite well with dipole antennas that are electrically low; for instance, an 80-meter dipole strung between two trees at 50 feet (less than a quarter wavelength) allows me to work Europeans regularly on 80-meter CW with a 100-watt transceiver. As a bonus, this antenna works even better at higher frequencies, where it's electrically much farther above ground, as I'll also discuss later.

Variations on the Theme

Part of the beauty of dipole antennas, like many other simple things, is their flexibility. Dipoles can be installed in an infinite number of configurations other than the classical flat-top arrangement (Fig 1). Some of the more common variations include the inverted **V** (sometimes called the drooping dipole—Fig 2A [page 26]); parallel-multiband dipole (Fig 2B); sloping dipole (*sloper*—Fig 2C); vertical dipole (Fig 1, rotated 90°); folded dipole (Fig 2D); and trap dipole (Fig 2E).

Inverted-**V** dipoles are probably more common than flat-top versions. As you might expect, the inverted **V** gets its name from its shape. The main advantages of inverted **V**s are that they need only one high support, and that you can get more total wire into the same horizontal space using

Dipole Construction and Adjustment

Dipoles can be made of almost any kind of wire or tubing, but how well they work and how long they last is determined by the quality of the parts and care you use in building them. With that in mind, here's what it takes to make a dipole antenna.

- *Wire.* Stranded and solid copper, and copper-plated steel (Copperweld), are the most popular types used for antenna construction. Don't use soft, solid copper (such as house wire) for long unsupported runs in resonant antennas; solid wire can stretch enough after installation to detune the antenna. Use reasonably large wire (no. 16 or larger) for permanent antennas. No. 18 or smaller wire is generally okay for low-profile or temporary antennas, or those cut for 14 MHz or higher frequencies. There's little difference between antennas made from insulated and uninsulated wire, although the presence of insulation generally lowers the resonant frequency of a given length of wire by a bit. Insulated wire is heavier and thicker, which, depending on its color, can make it more or less visible than its uninsulated equivalent. Davis RF (see "Where to Get the Pieces") carries uninsulated, stranded no. 14 copper that's made of 168 strands of wire. This is good stuff for dipoles (or home-brew balanced feed lines) because it's very flexible and easy to work with, doesn't stretch, and resists breakage well.
- *Insulators.* A dipole should have insulators (Fig A) at its center (feed point) and at each end, where ropes (or other restraints) support the antenna. The center insulator serves two primary purposes: (1) it separates and supports the feed-line conductors, making for strong mechanical wire joints that minimize stress on solder joints; and (2) it gives you a convenient place from which to support the dipole with a rope, if your dipole is center-supported. End insulators serve another purpose: They provide an isolated support point at the high-voltage ends of the antenna wire. (Potentials at the ends of a resonant dipole can be in the kilovolts—even with just a 100-watt transmitter!)



Fig A—Several varieties of insulators are commonly available to hams. The lower-center ceramic unit and the plastic insulator on the left are current Radio Shack products. The others, and close variants, are available from many mail-order sources (see "Where to Get the Pieces").

Plastic, ceramic or porcelain insulators are fine for most applications. Home-made varnished hardwood is also acceptable. There's no need to use a special center insulator at a dipole's feed point—the impedance, and therefore the RF voltage, there is low—although doing so can make construction easier.

- *Rope.* Nylon, Dacron and similar materials are best. Avoid polypropylene; it rapidly deteriorates in sunlight. Also avoid hemp and other natural materials. They tend to stay damp and rot in the center after getting rained on, with no outwardly visible signs of damage. If you select nylon rope, use the braided variety and carefully seal its cut ends by melting them with a match or cigarette lighter. This rope is very strong, but unlike Dacron, it also initially stretches as much as a few percent.

To make a dipole that'll stay up and that's easy to work on, using the right knots is important. Learn (or relearn) to tie a *bowline* (an unsliding loop); a *clove hitch* (for attaching rope to poles, tower legs, and such); a *taut-line hitch* (a sliding knot for adjusting the tension in a rope); and a *sheet bend* (for joining the ends of two ropes). These knots are simple to tie, and are described in every edition of the Boy Scout *Handbook* and *Fieldbook*, as well as some merit badge booklets (look under Boy Scouts of America in the Yellow Pages for local suppliers of BSA materials). Another good reason to be acquainted with these knots: When (if) you start working on towers (or other supports) and bigger antennas, these knots can save your *life*, not to mention your hardware.

- *Soldering.* To make permanent

this configuration. This is often an important advantage on the lower-frequency bands, where real estate and support height suitable for putting up a full-size dipole are at a premium. Inverted **V**s usually work almost as well as horizontal flat-top dipoles when the dipole's height is the same as the feed-point height of an inverted **V**. It's important to keep the antenna ends high enough above the ground so that people, vehicles and such can't come into accidental contact with them.

Another common dipole configuration is the multiband parallel version. In such an antenna (Fig 2B), multiple dipole elements are fed at the same point, with a single feed line, and supported by spacers attached to the longest dipole element. The main advantage of parallel dipoles is multiband coverage with resonant elements on each band, allowing the use of a single coaxial feed line for several bands without

Where to Get the Pieces

Here's a brief list of suppliers of wire, insulators, feed line, connectors, and other items you'll need for making and installing dipole antennas. For a more complete list, see the advertisements in this and other issues of *QST*.

- Radio Shack stores (antenna wire, coaxial cable, ceramic and plastic insulators, connector-sealant tape and other supplies). See 1991 catalog, page 137.
- Davis RF, PO Box 230, Carlisle, MA 01740, tel 508-369-1738 or 800-484-4002, extension 1356 (high-flexibility antenna wire, coaxial cable, several varieties of prefabricated balanced line [and parts to make your own], ceramic insulators, aluminum tubing and other supplies). Catalog available.
- Ocean State Electronics, PO Box 1458, Westerly, RI 02891, tel 401-596-3080, fax 401-596-3590 (antenna wire, coaxial cable and connectors, 300-Ω twinlead, insulators). Catalog available.
- Certified Communications, Rte 2, Pittman Rd, Landrum, SC 29356, tel 803-895-4195 (coaxial cable, balanced feed line).
- The Radio Works, PO Box 6159, Portsmouth, VA 23703, tel 804-484-0140, fax 804-483-1873 (antenna wire, coaxial cable and connectors, balanced feed line, baluns, insulators, rope, sealant and other supplies). Catalog available.
- Most major Amateur Radio equipment dealers (Amateur Electronic Supply, Ham Radio Outlet, and other *QST* advertisers) carry parts for dipole construction.—*NJ2L*



Fig B—Secure end-insulator connections are important to long antenna life. Top to bottom: Leave part of the insulation from the wire end to protect the wire where it goes through the insulator eye; wind several turns of wire back on itself to make a strong mechanical connection; solder the joint; and spray it with clear lacquer to prevent corrosion.



Fig C—Coaxial cable feeding a dipole antenna. The center insulator is omitted for clarity. When measuring and adjusting a dipole fed with coax, keep in mind that the stripped coax center-conductor and shield lengths *add to the antenna length*.

connections that will stand up to wind and weather, you'll need a soldering device that can quickly heat the wires to be joined. A 30-W iron probably won't do an acceptable job with wires larger than no. 16; a 100-W or larger soldering gun is best. If you're using relatively heavy wire and ceramic or porcelain insulators, you can use a propane torch (preferably with a soldering tip) for soldering. (If you do this, heat the joint first, then remove the flame and let the heat of the wires melt the solder into the hot junction.) Use 60/40 (or similar) rosin-core solder (available from Radio Shack and most hardware stores). Use caution when soldering close to plastic insulators; too much heat will damage them. Don't breathe solder or insulation fumes!

- *Tape, sealant and similar protective coverings.* Protect your solder joints and feed-line connections from the weather after soldering by tightly wrapping them with high-quality electrical tape (such as Scotch 33 or 88) or silicone adhesive tape, or covering them with Coax-Seal (or equivalent). Solder joints at end insulators can be sufficiently protected by spraying them with clear lacquer, available from most hardware and home-supply stores. Weatherproofing properly soldered end-insulator joints is optional, but *seal the center insulator* as if you were planning to use it underwater. The last thing you want is rainwater in your coax!

In dipole construction, it's important to make strong mechanical junctions in the wires. An antenna that depends solely on solder joints to handle wind stresses will surely fall down sooner than one that's made with good mechanical connections. RF interference can also result from deteriorated solder joints. Fig B shows how to make a solid mechanical connection at an insulator.

Bringing a Dipole "On Frequency"

To resonate a dipole that's fed with coaxial cable, select a band and cut the wire a couple of feet longer than the appropriate length shown in Table 1. Then, install center and end insulators and attach the coaxial feed line (Fig C shows how to attach coaxial feed line to a dipole). Support the antenna a few feet above ground, measure the SWR and trim the antenna (equally from each end) to raise the resonance to the desired frequency. If the antenna is too short, splice in some additional wire, or attach equal amounts at the end insulators and let it hang from them. Copper-and-brass split-bolt clamps, made for attaching copper ground wires together and available from most home-improvement stores, are great for making these additions.

Selecting supports and installing antennas is the subject of many other articles. See the references listed under "Further Reading" for a few of these.—*NJ2L*

Further Reading

For more information on antenna construction and installation, see the references listed below. The issues of *QST* cited here may be available at your local library; if not, contact the Technical Department Secretary at ARRL Headquarters (see p 3 of this issue) for any photocopies you need. (There is a nominal charge for this service.)

- G. Hall, Ed., *The ARRL Antenna Book*, 15th ed (Newington: ARRL, 1987). If you're aware of this book, you may think that it's a highly technical reference intended for those with lots of antenna knowledge and experience. In truth, it's intended for hams at all experience and license levels, and even those who aren't yet licensed. All of the subjects I've covered in this article are treated from basic to detailed levels in *The ARRL Antenna Book*, and it should be the key reference in your quest for antenna wisdom.
- C. Hutchinson and L. Wolfgang, Eds, *The ARRL Handbook for Radio Amateurs*, 1991 ed (Newington: ARRL, 1990). Chapter 17, "Antenna Fundamentals," provides a good technical introduction to dipole theory and feeding.
- D. Brede, "The Care and Feeding of an Amateur's Favorite Antenna Support—The Tree," *QST*, Sep 1989, pp 26-28, 40.
- W. Calvert, "The EZY Launcher," elsewhere in this issue.—*NJ2L*

the need for an antenna tuner. An inherent disadvantage of parallel dipoles, however, is narrower bandwidth than single dipoles provide.

Two other fairly popular dipole variations are the trap dipole and the folded dipole. Traps are tuned circuits (consisting of inductance and capacitance) that electrically isolate the inner and outer sections of the antenna at certain frequencies, providing multiband resonant coverage from a single antenna. At a trap's resonant frequency, it presents a high impedance and therefore isolates the outer segments of the dipole, making the antenna electrically shorter than it is physically. At frequencies below the trap's resonance, it has a low impedance, which makes it transparent to RF (ie, it doesn't isolate any part of the antenna).. Traps aren't used only in dipoles:



Fig 2—Variations on the dipole are numerous: at A, an inverted V; at B, a multiband parallel dipole; at C, a sloping dipole (sloper); at D, a folded dipole; and at E, at trap dipole. Dipoles of the multiband parallel, trap and folded varieties can be installed in sloping or inverted-V configurations.

Trap Yagi beams and verticals are also popular. Folded dipoles are a bit less common in Amateur Radio use; they use full-length parallel wires shorted at the ends, and have feed-point impedances that provide good matches to balanced feed lines. FM-broadcast receivers usually use folded dipoles made from TV twinlead. *The ARRL Antenna Book* and *The ARRL Handbook* cover trap and parallel dipoles in more detail (see "Further Reading").

The Dual-Band Dipole

Two popular ham bands, especially for Novice and Technician Class operators, are those at 7 and 21 MHz. As mentioned earlier, dipoles have harmonic resonances at odd multiples of their fundamental resonances. Because 21 MHz is the third harmonic of 7 MHz, 7-MHz dipoles are harmonically resonant in the popular ham band at 21 MHz. This is attractive because it allows you to install a 40-meter dipole, feed it with coax, and use it without an antenna tuner on both 40 and 15 meters.

But there's a catch: The third harmonic of the Novice 40-meter allocation (7100-7150 kHz) begins at 21,300 kHz; yet the Novice segment of 15 meters is 21,100-21,200 kHz. As a result of this and other effects, a 40-meter dipole does not provide a low SWR in the 40- *and* 15-meter Novice segments without a tuner.



Fig 3—Figure-8-shaped capacitance hats, made and placed as described in the text, can make your 40-meter dipole resonate anywhere you like in the 15-meter band.

An easy fix for this, as shown in Fig 3, is to *capacitively load* the antenna about a quarter wavelength (at 21.1 MHz) away from the feed point in both wires. Known as *capacitance hats*, the simple loading wires shown lower the antenna's resonant frequency on 15 meters without substantially affecting resonance on 40 meters.

To put this scheme to use, first measure, cut and adjust the dipole to resonance at the desired 40-meter frequency, as described in the sidebar called "Dipole Construction and Adjustment." Then, cut two 2-foot-long pieces of stiff wire (such as no. 12 or no. 14 house wire) and solder the ends of each one together to form two loops. Twist the loops in the middle to form figure-8s, and strip and solder the wires where they cross. Install these capacitance hats on the dipole by stripping the antenna wire (if necessary) and soldering the hats to the dipole about a third of the way out from the feed point (placement isn't critical) on each wire. To resonate the antenna on 15 meters, adjust the loop shapes *(not while you're transmitting!)* until the SWR is acceptable in the desired segment of the 15-meter band. You can make all these adjustments with the dipole just a few feet off the ground; raising the antenna to its permanent height shouldn't shift the SWR much. Recheck the antenna's 40-meter resonance before raising it, though.

Feed-Line Considerations

The antenna wire and insulators, how you put them together and where you string them up is only part of a dipole-based antenna *system*. Next month, I'll cover selecting and using a feed line for your dipole(s). In the meantime, I suggest that you have a look at the two parts of Dave (WJ1Z) Newkirk's article, "Connectors for (Almost) All Occasions," in the April and May issues.

1:1 Voltage Balun for HF wire dipoles

Heres a neat 1:1 50 ohm balun for use on HF horizontal wire dipoles. It uses an AM radio ferrite rod, with 3×14 turns of wire. 10-14 turns should be good for 2-30MHz. I used 18SWG enammeled copper wire. It all fits in a small project box. Great for setting up portable. For 20 metres, I started with 6 metres of wire per element, and trimmed each down until it has minimum S.W.R. I managed to get a 1:1.1 S.W.R. on my desired frequency. Bandwidth from the resonant frequency is about 200KHz either way, any more needs an ATU. The wire and ferrite core I had already, the box, terminal plugs and SO-239 came to about £6. The balun can also be built on a ferrite toroid such as an FT140-43 or FT240-43.



1:1 ferrite rod voltage balun

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Accept Read More


50Ω
Unbalanced
50Ω
Balanced
1:1 Voltage Balun on Ferrite Rod - M0UKD

Bandwidth may be increased by more spacing between each trifilar turn. I didn't have room on this tiny ferrite rod, but it performs OK.

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More

1:1 Voltage balun ("Ruthroff")


50Ω
Unbalanced
M0UKD
50Ω
Balanced
1
2
3
1
2
3

10-15 trifilar turns on ferrite rod.

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More


50Ω
Unbalanced
50Ω
Balanced
1:1 voltage balun ("Ruthroff")
MØUKD

Schematic Diagram



This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More

End Fed Half Wave Antenna Coupler (EFHW)



The finished End Fed Half Wave antenna coupler.

Centre fed half wave dipoles make great, simple and effective antennas for the HF bands. Sometimes however, the centre feed is not ideal, for example when you want to use it as a vertical. Being able to feed the dipole from one end gives you more options on how to erect an antenna and makes portable operation easier. A vertical, a sloper, a piece of wire hung in a hedge are all good examples. A ground mounted half wave vertical has a peak radiation angle of 20°, so it makes a good choice for DX.

I have been experimenting with feeding end fed half wave antennas matched by a parallel tuned circuit coupler. This article will explain my findings and reasons for constructing it the way I did.

A dipole can be fed anywhere along its length. A centre feed gives around 70Ω. A 'Windom' type off centre fed dipole (fed 38% along its length) provides around a 200Ω feed. The feed impedance at the very end of a half wave is thousands of ohms, usually somewhere between 2000Ω to 5000Ω, which we need to match to our 50Ω transceiver. The problem with end feeding a half wave is also its advantage. The high impedance means that the feedpoint has a very high voltage but low current, therefore very little ground is required. A very small counterpoise should be adequate from 7 to 30MHz, or you can even use the coax and transceiver

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Accept Read More

Below is the schematic of the final build.


End Fed
Half Wave
T1
Pri: 2t
Sec: 16t (1.5µH)
1:8 turns ratio
1:64 impedance ratio
50Ω to 3200Ω
15-350pf
T1
50Ω
Counterpoise / Coax Ground Switch
Counterpoise
MØUKD
7-30MHz End Fed Half Wave Coupler - M0UKD.com

End Fed Half Wave Antenna Coupler Schematic – 7-30MHz

For calculating the length of a half wave in metres, I use 141÷*f* (MHz) for wire elements. These dimensions were derived from modelling the antenna in EZNEC. I have found this calculation to work well, however it depends on many factors such as wire used, location etc. I have made a javascript calculator below for simplicity with a 15m half wave ready to go!

Enter the frequency: 21.25 MHz

Calculate

Half Wave antenna is: Metres

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More



```
Freq       21.2 MHz
SWR        1.062
Z          3015 at 0.11 deg.
           = 3015 + j 5.808 ohms
Refl Coeff 0.02984 at 178.15 deg.
           = -0.02983 + j 0.0009624
Ret Loss   30.5 dB
```

End Fed Half Wave (6.65m @ 21.2MHz, ground mounted) SWR – Actual bandwidth on the 50Ω side of the coupler will be much narrower, due to the tuned circuit we are using. This is showing the feed point SWR at 3200Ω

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More



Current along the half wave. Notice how the feedpoint is not quite as high impedance as the top of the antenna.

First off, construction will be a juggle between available components and the desired band coverage. I had a capacitor that I wanted to use, which is a Johnson 154-2 air variable capacitor, with a range of 15-353pf. I would like to cover 7 to 30MHz with my coupler if possibe, so the next thing I needed to design was an inductor that would resonate in a parallel LC circuit at just above 30MHz when the capacitor is at minimum. Using this **Resonant LC Calculator**, I worked out that an inductance of 1.5μH will resonate at about 33MHz when the capacitor is at 15pf and 6.9MHz when the capacitor is at its maximum of 353pf. Sounds perfect to me! If you have a smaller value capacitor, for example 200pf maximum, it should still cover 10MHZ to 30MHz. A switch could be added to add a further capacitance of 150-200pf to include 7MHz operation.

So, lets build the secondary transformer inductor first. I wanted to transform 50Ω to around 3000Ω. This would require a 1:8 turns ratio. Impedance transformation is calculated by squaring the secondary turns ratio (note ratio, not actual turns) 8^2 is 64. 50×64=3200Ω (our input impedance x 8^2). I looked at using a **T200-6** iron powder toroid, but the problem was 1.5μH required *only* 12 turns. As I wanted a 1:8 turns ratio (for a 1:64 impedance ratio), I needed a primary of 1.33 turns, which was going to be impossible. I could have made it 16 turns and a 2 turn primary, but then the inductance would be too large for 30MHz.

So, I decided to use an air wound transformer. This way, I can build it with a 16 turn secondary, *and* at the inductance I wanted by altering the diameter and/or length of the coil. Using this **Air Inductance Calculator**, I worked out that a 19mm diameter, 52mm long, 16 turn inductor should give an inductance of 1.5uH, so this is what I built

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More

Winding the secondary inductor

Once it was wound, I tested it on an LC meter, which confirmed it was around 1.5µH. You can expand or contract the inductor to fine tune the impedance to suit. The importance is that it remains 16 turns to match with the 2 turn primary. I then wound the primary coil, which had to be a slightly larger diameter so that it could fit over the secondary coil and provide inductive coupling. You can see the finished 2 turn primary and 16 turn secondary below.



The completed inductors. They have their differences, but I will make them a happy 'couple'!

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More

secondary and a terminal block glued to a small block of MDF for the primary. The coax is soldered to the primary, the terminal block is just to hold it in place. There is a counterpoise connection on the side, the antenna connection on the front and the capacitor, SO239 and counterpoise/coax ground switch on the rear. Some photos of the completed unit are below.



The completed End Fed Half Wave Coupler

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More



The tuning control, SO239, ground switch and on the right, the counterpoise connection.

DANGER!
High Voltage RF!
MØUKD

The antenna connection. The second hand box had a few holes in it, so I made this sticker to cover them up!

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More

this is due to extra stray capacitance. I tuned the coupler to resonance into a resistor (in my case 3.2kΩ) so a 1:1 SWR was obtained on my chosen frequency of 21.25MHz, then I removed the resistor and attached the half wave antenna (6.65m) and counterpoise (66cm) from the above calculator. Without adjusting the variable capacitor, I had a 1:1 SWR. This confirmed that I had a resonant half wave and that I was feeding it at or very close to the peak voltage point and the feed impedance was around 3200Ω. I found that a small counterpoise was required. Sometimes, the stray capacitance to ground was good enough on its own, especially on the higher bands and if the coupler was laying on the ground. If its all away from ground, I get consistent results using the above setup. I have had good success also by using the coax as the return, by connecting the 'bottom' of the primary and secondary together via a switch to use the coax shield and transceiver as a counterpoise.

You may be able to adjust the capacitor to match the antenna if its not a perfect half wave, but then it will be a higher current feed and the simple ground system will be inadequate. The coupler will also not be working as it was designed and will be inefficient, generating heat. The coupler is a tuned impedance transformer, not an antenna 'tuning' unit. Stick to the above, and it should be a sure thing!

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More



A half wave vertical for 21MHz. 6.65 metres of wire on a 9 metre fibreglass pole. The coupler is mounted 2 metres up and attached to the top of the fence. The 67cm counterpoise just hangs down in free air.

Below is a short video from my second test with the coupler, here on 17m.

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More

END FED 6–40 Meter Multiband HF Antenna

Introduction

This EARC project produces an inexpensive, multiband, end fed HF antenna matchbox that is quick and easy to setup and use. The end fed feature adds portable convenience, but does present another issue. The problem with an end fed half wave antenna is that the antenna presents high impedance, creating a significant miss match with the usual transceiver impedance of 50 ohms. This miss match is significantly greater than typical tuners can accommodate without a matching transformer.

This project creates a trifilar wound, 9:1 UNUN (unbalance to unbalance) toroid matching transformer that will match the high input impedance of an end fed antenna into the range where most antenna tuners can produce good performance. The matchbox handles 100 watts of power. ***This project requires an antenna tuner to achieve satisfactory SWR***. If you need an auto tuner, we recommend the LDG line of auto tuners, shown to work well with these matchbox antennas, and highly rated by users. They are reasonably priced and available at most ham stores.

The matchbox project uses readily available common hardware and materials listed below.

Matchbox Parts List

End Fed HF
Matchbox Antenna

1	small plastic enclosure (shown right)
1	powdered iron toroid T130-2
3	20” pieces of 18 AWG solid insulated copper wire in red, green, and black
2	# 8-32 x 3/4” hex head machine screws
2	# 8 lock washers
2	# 8 ring wire lugs
2	# 8 flat washers
2	# 8 lock washer/nut combination
2	# 8 wing nut
1	SO-239 panel mount connector to fit keyed enclosure opening

30’ # 18 AWG insulated stranded wire antenna with ring lug attached Small amount of clear silicone caulk to secure toroid in place

Preparing the MATCHBOX Plastic Enclosure



The enclosure needs one 5/8” hole for the SO-239 connector, and one 11/64” hole for the counterpoise wing nut on the lower side of the enclosure. An 11/64” hole on the upper right side of the box facilitates antenna connector mounting.

TOROID WINDING

First, wind the three 20” pieces of insulated solid wire onto the toroid. Place the wires as shown green-black-red, and wrap the toroid 9 turns so that it looks like the photo on the right. Notice there are three wires extending from the left winding and three wires extending from the right winding. As the connections are completed, the steps refer to the specific wires by left or right and color.

NOTE: Count turns by counting the number of times the wire goes thru the toroid center.



Crimp together and solder ***__the left black wire__*** with the ***__right red wire__*** When the step is completed, it will look like the right photo.

The next three steps should appear as shown in the first photo on page 3. Crimp and solder a # 8 lug to the ***__left red__*** wire about 2” from the toroid. The completed lug will later connect to the antenna connection bolt on the upper inside of the enclosure.

Twist the **__left green__** wire with the ***__right black__*** wire. Strip the ends of the two wires and twist together at about 2”. This twisted pair will solder to the center connection of the SO-239 connector in a later step.

Trim and strip the remaining ***__right green__*** wire at about 2”. Cut an additional 2” piece of green wire, and crimp and solder both wires to a # 8 lug. The 2” green wire will connect to the ground connector on the SO-239 already installed in the enclosure. Strip remaining green wire end 3/8" and bend into a hook for connection to the SO-239 ground connector.



The SO-239 connector and ground lug should be installed through the keyed hole in the lower right with the mounting nut securely tightened.

Solder the green and black twisted pair to the SO-239 center connector.   Solder the green wire hook to the ground lug on the SO-239 connector.



From inside the box, place an 8-32 machine screw through a lock washer, the # 8 lug on the green wire, then through the lower 11/64'" mounting hole. Place a flat washer on the outside protruding machine screw followed by # 8 lock washer/nut and tighten securely. Place a # 8 wing nut on the machine screw to finish the **counterpoise connector**.

Position the toroid inside the box to allow connection of the red antenna wire lug to an 832 machine screw and lock- washer on the upper box side. Place a flat washer on the outside of the box followed with a # 8 lock washer/nut. Tighten the nut securely. Next, place the wing nut on the **antenna connector** and your project appears as shown above.

A small spot of clear silicone compound is used to secure the toroid from movement in the enclosure.   The final assembly step is to secure the box cover in place with four screws.

Preparing the Antenna Wire

Matchbox performance will be determined by two factors: The length of the antenna wire, and the capability of the tuner. The length of the antenna wire should be between 24 and 60 feet for best performance. Additional counterpoise is not normally required, as the coax shield provides the counterpoise function. Wires longer than 60 feet may have excessive impedance for some tuners to properly match. Wires shorter than 24 feet may not radiate as effectively. A 30 foot insulated 18 gauge stranded wire antenna and connecting lug is included with the project and should meet most requirements without need for any counterpoise.

Experience has shown that most external tuners and some internal tuners will tune 80–6 meters with an antenna length of 24’ to 30’. If a longer antenna is desired, the provided antenna can be lengthened.

Some tuners, in particular internal tuners, may not tune the full 80-6 meter range. You may need to try different wire lengths to optimize your antenna configuration. If you are having difficulty getting your rig to tune, start with a 26’ wire. This should produce good results on at least 40-6 meters using the narrowest performance range of internal tuners.

Best performance is achieved with a coax of 16’ or longer, with the coax shield providing the counterpoise function. Additional counterpoise is usually not required in this design, although the lower wing nut provides a convenient counterpoise connector if needed. The end fed antenna system works well in horizontal, sloper, and vertical configurations.

Observe established safety practices when working with antennas, and avoid proximity to power or utility wires. Permanent installations should be equipped with appropriate static and lighting protection.

Keep amateur radio safe and fun!

End Fed HF
Matchbox Antenna

Toroid Wiring Schematic


ANTENNA CONNECTION
Red wire
Black wire
Coax center
INPUT
Green wire
Coax Shield

Feedback on 6-40 End Fed Matchbox Antennas

The antenna is amazing. I receive fantastic signal report from DX stations as well as hams around the country. I previously used a short version GR5V that was in an inverted V configuration on the roof of our house. This antenna was noisy but worked. Your antenna out performs the prior antenna and is much quieter. Thanks again for the fine product that your club offers. ***May 2012***

It took me 10 minutes to install and WOW - within 10 minutes I made my first HF contact (from CT to GA). And in the span of 4 hours made 3 more !! I was transmitting just 5 Watts from Yaesu 857ND using this antenna. This antenna rocks ! Thanks a ton ! 73 ***May 2012***

The 6 - 40 Matchbox antenna works great! Easily tunes with the Z100 tuner - very low SWR's on 20m thru 10m. Antenna was up about 45 feet on tree branch - wire length was about 52.5 feet, slight slope, 55 feet of coax, line isolator at radio. ***Work Hawaii for the very first time. Guess the antenna wanted to call home :-) 57 report, 100 watts, 15 Meter band, Icom 718.*** A great portable antenna that I will use often at Montrose Harbor along the lakefront in Chicago. Thank you for a fine, well made product. ***April 2012***

It arrived today in fine shape. I got is up in the air this afternoon using a 31 foot radiator. Top is at 45 feet. Loads on all bands 80-10M with my LDG auto-tuner absolutely no problem, My first QSO was KH7X in the ARRL SS contest with 100W. Amazing. This thing rocks! It's a great antenna! Nice job and a great buy. ***November 2011***

I set-up my jackite pole today and tried a 68' wire with the 9:1 unun matchbox. I set it up as an inverted L with about 26 feet vertical and 42 feet horizontal. With my IC-703 it tuned 80 through 6 all well below 1.5:1. I am going to leave the antenna up a few days and make a few contacts. I think the matchbox is terrific. ***October 2011***

My 6 – 40 meter end fed arrived through the UK holiday mail and I departed from my norm of a sloper and mounted it vertically on a 10m fishing pole. It is surprisingly effective and rewarded me with a surprise contact on 17m into the Falkland Islands at 20:30UT last night. ***January 2012***
When I attached it to a 10m fiberglass fishing pole and went vertical - wow! Easy 5/9 contacts out to 6,000+ miles when propagation was anything better than the worst. My simple ATU easily matches the antenna with SWR never greater than about 1.4 on any band it is built for. ***December 2012***

You can dither and procrastinate, but with this antenna, you'll be talking to the world in no time on any band that happens to be hot - and with your hard-earned cash hardly touched! ***January 2012***

Just wanted to report back that I have tossed the antenna into a tree about 20' up in an inverted vee shape and I am pleased to report that I can tune anywhere I need on 40-10M using the TS-590 internal tuner!! My first contact was on 40M within 10 minutes of erecting the antenna and was all the way to TX from my condo here in MI using just 10 watts. This is by far the best HAM related investment I have made in a long time. Living in a condo with strict association rules, I am able to conceal this wire in a tree out my bedroom window and talk all over. I'm very happy and would recommend this antenna to anyone in a similar situation. ***March 2013***

I have had your multiband end fed antenna installed here in Singapore for a few weeks now and am very pleased. I used the wire from my previous antenna which is 66 feet long. It works beautifully! I have it hanging vertically outside my 15th story apartment window on a 5 foot horizontal pole (to get it away from the reinforced concrete building). A couple of fish weights on the end keep it from blowing around too much. I would recommend this antenna to anyone who is facing a challenging QTH. ***April 2013*** I received my antenna yesterday, a quick 4 days since I ordered it. I attached it to a 31 foot pole and my IC-706MK2. Within minutes, I made my first contact with 9A4KW in Zagreb, Croatia on 20 meters. Being able to reach out over 4,000 miles gives me real confidence that I have found my portable antenna. Thanks for your rapid response and fine product. ***May 2013***

In only 2 weeks of casual on-air time. If you could see how I had to zig-zag it through a big tree above the roof of my RV, you'd be saying like I am, "how the heck can that work? I worked 90% of the stations I called, and just added Mexico City on 15m that gave me a 5x9. ***September 2013***

Just wanted to let you know how pleased I am with my ERAC matchbox antenna. I put the EARC antenna in the backyard with the feed point at 4 feet and the wire sloping up to 35 feet. I have 125 feet of coax feed line. My transceiver's built-in antenna tuner will adjust the SWR to below 1.2 to 1 on all bands 80-6 meters. Last weekend I worked 65 countries on 5 continents. I live in an antenna restricted community and this antenna has allowed me to enjoy ham radio again. ***February 2014***

I used the EARC Matchbox today. It works GREAT on 20m with a 30 ft radiator in vertical positioning, fed with 25ft of RG175/u coax. I've been talking up and down the east coast with 3W on SSB all afternoon! People ask me to repeat my power output again and again. I can't wait until I get the chance to use it at night, where I think it'll really shine! This has a permanent place in my portable kit. Thanks for the great product! ***April 2014***

I performed a simple install in Virginia making it vertical by using a 28 foot fiber glass kite pole. Within 30 minutes (NO KIDDING) I was receiving Lebanon on 17 meters! I also worked Russia and Eastern Europe that night on 20 meters. I love this antenna and I give it a 100% (5 STAR) rating. ***May 2014***

This little box is magic. NY, IA and NM from GA with ease on 100w ***June 2014***

Just wanted to let you guys know, this matchbox is wonderful. I built the matchbox, connected it to 55 feet of solid #14 about 20 feet in the air. My rig is a Yaesu FT-817ND connected to a MFJ-971 tuner with coax running between the tuner and the matchbox. So far I have worked Slovenia twice, Morocco, St. Helena Island, Cuba, Cost Rica, Vermont, Wyoming, Florida, North Dakota, Brazil, and Colombia. This setup works really well on the higher bands. Thank you for putting this design on the internet. I like it so much its become permanent here. ***September 2014***

This antenna continues to amaze me. It worked well U-shaped "indoors" with 50 watts, and now outdoors as a sloper. It easily loads 10-40m with my TS-570s internal tuner. I'm sold on it and own two of them now. I'm working at least 90% of the DX I chase. I have no RFI in the shack either. ***November 2014***

EARC Antennas are operating in virtually every state, these countries and more!

Argentina Australia Belgium Brazil Canada Chile Denmark Greece

Hong Kong India Ireland Israel Italy Mexico Mozambique New Zealand Russia Singapore Sweden Tasmania United Kingdom

ORDERING A MATCHBOX ANTENNA FROM EARC

Volunteers of the Honolulu Emergency Amateur Radio Club (EARC) carefully assemble the 6-40 End Fed matchbox antennas for those who prefer not to build one. For a donation of **$56** (Including USPS priority mail shipping) club volunteers will build and deliver a 6-40 matchbox with a 30 foot antenna wire anywhere in the U.S., we do not ship internationally. Note that coax cable is not included.

Payment by PayPal

To pay via **PayPal**, make your payment to paypal@earchi.org using any major credit card. Include your name, mailing address, and email address with the order.

We will ship promptly and you will likely receive the order in the US in 7 days or less. If you have any questions about your order, please email webmaster@earchi.org

Thank you for your interest in the activities of Honolulu Emergency Amateur Radio Club and amateur radio.

2N6084 144MHz FM Power Amplifier

Power
TX
Off
144-146MHz 50w Amplifier
On

Simple 2m amplifier.

I built the PA board for this when I was a foundation licencee, but under the foundation licence, you must only use comercially made transmitters. Since getting my intermediate licence, I have put it in a box, and added an RF sensing switch so I can use it. It uses a 2N6084 RF transistor, and will produce 50w output max. It is a class C amplifier design, and therefore good for FM mode only. I have tried using the 2N6084 in class A, but amplifier gain was down to about 4dB and it seemed a but pointless!

2.5w	10w
4w	20w
7w	30w
10w	40w
13w	50w

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More



Inside the box

Accept


SHINMEI
RSB-12-S
2A 30VDC RES.
1A120VAC RES.
700170 T2207

RF Sensing circuit & DPDT relay switch

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More



PA Stage

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More

Back


L1
RFC1
Gnd
C7
C8
C9
+13.8v
RFC2
RFC3
C10
C11
L2
L3
C4
RF Out
RF In
C1
L1
C5
C6
Q1
C2
C3
RFC1

Component List

C1, C2, C3, C4 = 5-65pf Trimmer
C5, C6 = 47pf ceramic
C7, C8 = 0.1uf
C9 = 10nf
C10 = 1000pf
C11 = 10uf 16v
L1 = Half turn 6mm Diameter 18SWG (see above)
L2 = 5 turns, 6mm diameter 18SWG
L3 = 1 turn, 6mm diameter 18SWG
RFC1 = 6 hole ferrite bead (see above)
RFC2, RFC3 = Small ferrite bead
Q1 = 2N6084

John M0UKD
144-146 MHz 50w FM Amplifier
John Parfrey
Rev 1.0
10/11/2008
Page 1 of 1

Schematic of the PA board. CLICK IT FOR LARGE VERSION!

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More


RF Sensing switch
2N3904
2N 3904
E B C
Radio
10pf
R1*
10k
1N4148
10k
10nf
B
E
C
B
E
C
ANT
1N4148
10nf
100μf
+ve 12v
PA OUT
PA IN
* R1 = <10w - 100Ω
10-30w - 1kΩ
30-100w - 10kΩ
2E0UKD

Schematic of RF sensing switch circuit.

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More

G3XBM 472kHz Transverter

Here is my 472kHz 630m transverter. A design by Roger G3XBM. The schematic I built is here.



432kHz Transverter, front.

I added TX/RX switching, a switchable 12dB attenuator for 0.5w or 8w drive and an output via a 100pF capacitor for attaching a frequency counter.

The local oscillator uses a 3.2768MHz crystal, and is set to 3.2765MHz by a 5-65pF trimmer. The input frequency minus the local oscillator frequency determines the output frequency. An input of 3748.5kHz gives an output on 472kHz.

Output power is about 12w at 13.8v.

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More


472kHz OUT
3748.5kHz IN
PTT
13.8v

Rear connections

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More



Inside the transverter. Thanks to George M1GEO for the SBL-1 mixer!

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More


Topward
FREQUENCY COUNTER 1208
G3XBM 472kHz Transverter - M0UKD
ON
TX
500mW
Input
8W
Freq Counter
ICOM IC-7400
3.749.50

On air!

And the first QSO, George M1GEO on CW!

Accept

This website uses cookies to improve your experience. We'll assume you're ok with this, but you can opt-out if you wish.

Read More

The “Tree Antenna”

RCC Aug & Oct 2006 – Dave/WB7ESV

Aug 2006 Article

What is unique about this antenna is that it is only a tree. The tree is used as a Gamma or Shunt fed vertical. To make this work, we drove a 3 ½” deck screw into the tree (you need to make contact with the sap vein), at about 15’ above the ground (15’ to 20’ will work). We attached a wire to the screw, extended the wire 2’ perpendicular to the tree, tied a rope to the wire at the 2’ point, tied the other end of the rope to a tree limb and dropped the wire to the ground.

At the ground we drove a 3’ ground rod 2 feet out from the base of the tree and attached a rope to the ground rod and to the wire to keep the wire tight.

At the feed-point end of the wire we connected an MFJ-901B tuner strapped for “WIRE” operation and connected the tuner ground to the ground rod.

Coax was connected and run to the operating position in a tent. To tune the antenna, an MFJ-269 SWR Analyzer was connected to the tuner input and the tuner adjusted for minimum SWR at the center of the operating band. The antenna is capable of operation on 10 - 80 meters. Many contacts were made including: Hawaii, Texas, Oklahoma, Montana, Wyoming, Utah, Idaho, California, VE6 and VE7.

The tree height should be no shorter than 30 feet and any wire antenna tuner will work.

Oct 2006 Article

Those who are building or have built it are: Jeff, KB6IBB, in The Dalles, OR; Tom, KD7ZOS, in Portland, OR; Dave, W0OXB, in Stillwater,MN; and Larry, KE7HGC, in Vancouver, WA.

Those who have it up and running have made contacts all over the U.S. and have stated that: .If I can hear them, I can talk to them.

If you are in an area that frowns on antennas and you have a tree that is at least 30. tall, give it a try. What you will need to build the Tree Antenna is: A tree that is at least 30’ tall, a 3# nail or wood screw, (not galvanized), 20’- # 12 - # 16 AWG copper wire (can be solid or stranded, un-insulated or insulated), a 4’ ground rod, wire clamp for the ground rod, 2-egg insulators and an antenna tuner that can be remotely adjusted, (ICOM AH-4, SGC SmartTuner, Home Brew with small motors to operate the variable capacitor(s) and inductor, etc). If you decide to ‘Home Brew’ a tuner, there are several in the ARRL Amateur Radio Handbook that will work very well.

Solder one end of the copper wire to the nail/screw. At about 15’- 18’ up the side of the tree drive the nail/ screw into the tree so as to penetrate the sap vein of the tree. (This is important for RF conduction.) Draw the wire out 2’ perpendicular from where you drove the nail/screw and support the wire with an egg insulator tied to a rope which is tied off to a limb of the tree and let the rest of the wire drop down to the ground.

Drive the ground rod into the ground 2' out from the base of the tree leaving about 3' of the rod above ground level. Attach a short piece of rope to a egg insulator and attach the other end of the insulator to the copper wire so that the insulator/wire is about 6' above the top of the ground rod. Leave enough wire to connect to the tuner.

Attach a short piece of rope to a egg insulator and attach the other end of the insulator to the copper wire so that the insulator/wire is about 6' above the top of the ground rod. Leave enough wire to connect to the tuner.

Attach the rope to the ground rod and install the antenna tuner to the end of the wire and place the tuner in a plastic container to protect it from the weather.

Connect a short ground wire from the ground side of the tuner to the ground rod with a clamp and make sure all connections are tight and sealed from weather.

If you are wondering where the “Tree Antenna” Comes from, it’s from a WWI/WWII Army Signal Corps Emergency Communications Manual.

Amateur Radio MØMTJ

MDS975.co.uk HOME PAGE

My Home Page

Amateur Radio Operating Conditions
Antennas
Accessories
Projects & Kits
Data Modes
Information
Portable
QSL
RSGB Ltd
Links
QRM
Bits 'n' Bobs
Contact

WSPR
Weak Signal Propagation Reporter

Site Map

MDS975 Home

Feedback

Site Search

Find

powered by FreeFind

G Whip Antenna Products
Get on the air with TOP QUALITY BRITISH

M0MTJ | Operating Conditions | Antennas / Aerials | /P Portable Operating | Accessories | Projects & Kits | Useful Information
Contact MØMTJ | Contact M6ORS | Links to Amateur Radio Sites | RSGB | QSL | The Amateur Radio Mini Site Map
News, Developments, Events, Photographs and other 'Bits 'n' Bobs' | WSPR Weak Signal Propagation Reporter

AERIALS (ANTENNAS) 2

Antennas 1 | **Antennas 3** | **Antennas 4** | **Antennas 5** | **Antennas 6** | **Antennas 7**

Index To Other Antenna Pages:
Antennas 1 : Aerials used at M0MTJ
Antennas 2 : Including ideas for compact aerkals for Top Band /160 metres
Antennas 3 : Felix Scerri VK4FUQ discusses Loop Antennas, baluns, masts & other antenna related topics
Antennas 4 : Many antenna ideas from various sources particularly for multi-band operation & also gives information about antenna trimming, knots for wire antennas and useful antenna rigging accessory ideas.
Antennas 5 : Half Wave End Fed aerials for 144 MHz VHF / 430 MHz UHF and 50 MHz 6 Metre band & J-Pole Aerials
Antennas 6 : Simple and effective H.F. Antenna ideas - Ground Plane and All Band Doublet
Antennas 7 : Omni-Directional - Circularly (Mixed) Polarized Aerial for VHF / 2 Meters.

Compact Top Band Antenna - An Inverted L for stealth with low(ish) visual impact

With a small back garden there is no way that I could accommodate an aerial for the 160m band that would be anything approaching full size. A full size dipole would be about 65 metres long and would need to be mounted at a very good height to be at its most effective. A full size vertical 1/4 wave would be about 37.5 meters tall. Impossible! Bending a 1/4 wave wire into an inverted L would still result in a very long wire - say 10 metres vertically and 27.5 metres horizontally. Still too large.

Full size top band antennas are big, far too big for my small plot, so I have tried a few different shortened 160m aerials. I really would prefer to use a balanced dipole not only for the radiation efficiency, but just as importantly for the lower noise on receive - like a ground mounted vertical aerial an inverted L can be rather noisy on RX. However I have to settle for a compromise, so shown in the drawings and photographs below is my current top band aerial, along with some previous experiments and ideas further down the page.

This incarnation of my Top Band aerial takes two forms. A compact Inverted L and, in its lower position, a less conspicuous sloping wire, shown below:



General layout of Top Band Aerial with fibreglass pole retracted to a height of 2 metres
Wire lengths are approximate: Inductor 5cm dia with approx 40 turns of 0.9mm e.c.w.

G-WHIP ANTENNAS

My first experiments were with a base loaded sloper which worked ok-ish for local ground wave, but could have been better. The first weak link that I wanted to change was moving the base loading coil further up the aerial wire so that it would be positioned on the more horizontal section.

It was also very low, so could surely benefit from some additional vertical height. However I could not realistically erect another permanent pole in the garden for fear of upsetting the XYL!

Therefore I decided that I needed a design that could be semi-permanent and offer two slightly different configurations: The idea is that, as a sloping wire, the aerial can be left in place at all times for RX and still be operable on TX. Since it is essentially just a wire sloping from fence height (2m) up to the roof apex it has fairly minimal visual impact. Alternatively, when required - at night - the telescopic pole can be extended to transform the aerial into the larger Inverted L.

The Earth and Radials: The aerial is fed against ground, so the ground needs to be as good as possible. At the base of the aerial a copper earth rod is driven into the ground. Additional ground radial wires are also added to provide a counterpoise and help reduce earth loss. The more the merrier.

The Support: A 10 metre long telescopic fibreglass fishing pole is used as part of the support. A wooden post was driven into the ground, adjacent to the earth rod. The connector box is screwed on to the post and the fishing pole was fixed to the post using nylon straps.

Since the top sections of a fishing pole are too thin to support the aerial wire, the last four sections were removed, leaving the pole 6 metres in length, which is a respectable height in a small back garden, though being even taller would be better.

A small lightweight pulley is fixed to the top of the fibreglass pole using two nylon ties - as seen in the photograph. As a sloping wire, the fishing pole is collapsed to 2m in height while being extended to 6 metres when being used as the 'full' Inverted L. The pole is quite flexible and so will tend to bend quite noticeably when 6 metres long with the wire attached to the top. This could be remedied by adding a back guy rope of required.

The far end of the aerial wire is tied to a egg type insulator and nylon halyard which is suspended through a pulley on a pole attached near the apex of the roof. The nylon halyard is tied off on a cleat hook near ground level to enable easy raising and lowering of the aerial wire.

The Wire: Aerial wire is PVC covered stranded wire of about 16/18 swg http://www.whwestlake.co.uk. The wires were cut for the maximum length that could be fitted into the available space - so as much wire was in the air as possible. This was about 3.5 metres from the feed point to inductor and around 12 to 13 metres from the inductor to the far end.

(If you make one of these get the vertical portion as high as possible and the horizontal section as long as possible and reduce the coil's inductance accordingly)**.**

The Inductor and Resonance:

The resonance of the aerial system was adjusted not by altering the length of the wires, but by changing the inductance of the loading coil.

I had some 0.9mm (20 s.w.g.) enamelled copper wire on a reel, so I used that to wind the coil. The coil former is 5cm in diameter and about 15 cm long, cut from an empty tube of silicone bath sealant (the 'gun' type). Two holes are drilled in the former for the fixing bolts and wing nuts that secure the aerial and coil wires.

I used an MFJ antenna analyzer to check resonance and adjust the number of turns. Initially the coil was wound with 60 turns, but the resonance was well below 1800 kHz. Turns were gradually removed until resonance was around 1940 kHz, leaving 39 turns on the coil. (Thicker e.c.wire might have been better, I would have preferred to use something like 18.swg 1.2mm diameter and this may possibly get changed in the future)

Enamelled copper wire:
http://www.esr.co.uk/electronics/cable-copper.htm

When the adjustments were finished the aerial wires and coil wires are terminated with lugs and fixed in place with the bolts and wing nuts. The winding was also covered in duck tape. All exposed connections should be suitably protected against the weather for a permanent installation.

When setting up any aerial an antenna analyzer is extremely useful - allowing all the measurements to be done in the garden or back yard thereby simplifying and speeding up the process considerably. These simple measurements can be made using the transceiver and VSWR meter, though that is obviously less convenient and will involve transmitting regular short burst of carrier, so it's very important to ensure that the power used is the absolute minimum and that the frequency being used is clear.



General layout of Top Band Aerial with a fibreglass pole extended to a height of 6 metres
Wire lengths are approximate: Inductor 5cm dia with approx 39 turns of 0.9mm e.c.w.

To transform the aerial to the Inverted L format (shown in the above diagram) I envisaged that changing the first length of wire, from a 3.5 metre length to 6.5 metre length, and the inductor would be necessary. I had assumed that a coil with less inductance (fewer turns) would be required due to the longer length of aerial wire used in the Inverted L arrangement.

I was, however, proved wrong. On first attempt I left the original coil in place, just adding the longer wire section (from connection box to coil) and raising the pole to its full 6 metres. The point of resonance was only about 20 kHz away from where it was as a sloper.

This, I think, can be explained by the fact that in the sloper configuration, the wire is close to the ground, other objects and vegetation which will in effect add loading to the aerial, Consequently a loading coil with less inductance than might otherwise be expected is required. So, by happy coincidence, the same coil is also suitable for the longer wire that is at a greater height (and therefore is influenced less by ground loading).

This, quite by chance, made the swap from Sloper to Inverted L a little easier since there was no need to wind a second coil - the change being made by merely adding the longer first wire section and pushing up the pole to its full 6 metre height.

If there are no concerns or objections to installing a tall pole at the bottom of the garden, then the Inverted L arrangement could be left as a permanent installation. In that case the pole need not be a fibreglass fishing pole, although it is still an attractive lightweight method, instead a couple of 3 metre long sections of treated timber could be joined together to form a 6 metre high post - the higher and longer the better though!

These links may be useful in helping to calculate loading coils:

Antenna Loading Coil Calculator : http://eweb.chemeng.ed.ac.uk/jack/radio/software/loading.html

Coil winding design program : http://ecosse.org/jack/radio/software/newcoil3.html

Loaded dipole calculator by K7MEM : http://www.k7mem.com/Electronic_Notebook/antennas/shortant.html

Ring Core Calculato r: http://www.dl5swb.de/html/mini_ring_core_calculator.htm



Top Band Inverted L - photograph showing the wooden support post with telescopic pole attached with connection box, cables and earth rod. The cable entering from the left is the earthing strap which is connected to ground rods and radial wires. The coaxial feeder cable exits from the bottom right of the box and is wound around a length of white plastic pipe to form a simple RF Choke.


Antenna Wire
Box
'Choc Block' connectors
RG213 coax
Earth Cable
To TXVR
To Earth Spike

My original implementation which used 'choc block' connectors. The final design has all soldered joints with a stainless steel bolt and wing not at the top of the connecting box.

Top Band Inverted L - pulley on top of the 6m telescopic pole



Top Band Inverted L - loading inductor.

This is the unfinished coil, the connections on the left are properly finished off using lugs, but the connections on the right are unfinished to allow adjustment of the number of turns. When that is settled the final lug is soldered to the end of the enamelled copper wire and held in place with the bolt and wing nut. The coil is 39 turns of 0.9mm e.c.w., wound on a 5cm diameter former made out of an empty silicone bathroom sealant tube. (I would have preferred to use slightly thicker e.c.w. of about 18 swg 1.2mm diameter, so that may get changed in the future)

Enamelled copper wire:
http://www.sycomcomp.co.uk
http://www.esr.co.uk/electronics/cable-copper.htm



Top Band Inverted L - pulley, rope and insulator supporting the wire at the far end

Top Band Inverted L - supported by a 6m long fibrelass (roach) pole



Top Band Inverted L - looking up!

The photo exaggerates the bend a little, but it's not enough to worry about. The bend could easily be corrected by adding a back guy to pull the pole back towards the vertical position, but for this job it's fine as it is.

DOES IT WORK?

Yes! This aerial does work, I am glad to say!

It works better than my initial short sloping wire shown further down this page, which is what one would expect!

Rather than merely settling for a local ground wave signal I was very pleased to contact Top Band enthusiast Steve G7KLJ on my first attempt. Steve is 170 miles distant from me and the night time sky wave provided a pretty good result. G7KLJ gave me a 5 / 8 with my 100 watts on 1843kcs using my small aerial. I gave G7KLJ 5 / 9+10 with Steve's large doublet and 400 watts (lovely audio too Steve!).

Admittedly that's potentially a 16dB difference, which is pretty huge, but G7KLJ had the benefit of 300 more watts - that's a 6dB advantage. It also depends on how the individual S meters compare. Steve seemed to indicate that his S meter was a bit on the lazy side - 1 S Point pessimistic? But maybe my S meter similarly pessimistic?

Compared to a full size inverted L my loaded aerial is less than half the size and is obviously going to lose out, but by how much? Half the size, half the effective power - 3dB down? Probably a lot more - 6dB? There's one S point lost already (Who wants to bet that it's a lot more than that?). Since I have a ground system that is far from ideal there's another few dB's lost - another 6dB? That would be 2 S Points lost before taking into account anything else. This is all pure guesswork and speculation admittedly and probably quite groundless (almost literally in my case), and might best be described as pointless ramblings! (Where did the delete key go?) The pessimist? The realist?

The only thing proved by this single event is that my aerial radiates at least something useful - and that G7KLJ has a great station! www.g7klj.com

Droitwich

OK so it's not Droitwich, but it does work and gets me on Top Band when otherwise there would be no chance.

I am happy - but as with anything improvements can always be made. The aerial could be taller perhaps, though I cannot make it any longer. The earth system could be far far better, though I would struggle to accommodate any improvements at the present QTH. I could use better coaxial cable and also (importantly) attempt to lower the received noise by experimenting with chokes or burying the feeder to reduce common mode currents.

Plenty to think about and plenty to play with!

Important notes on effective Grounding by Jim K8OZ

Mike - I was reading about your work on the 160 meter Inverted L, and it makes me want to go out and build some more antennas! Congratulations. Your story is fascinating, and very well documented.

The only thing I can offer as a suggestion is to get as much radial wire along the edge of your property as possible (assuming your XYL will not allow you to bury radial wire all over your yard). Even if you can only run multiple wires 1/8th of a meter apart from each other, and parallel to each other, your losses will be reduced. The ground losses have quite an impact on your transmitted signal, so any wire you can "hide" along the edge of your property will help improve your signal strength - little, by little...! { It may also affect your resonant frequency slightly, but that's easy to deal with by adjusting with an antenna tuner or slightly changing the loading coil. }

Good luck OM, and keep up the refinements on your antenna system. You're doing great! 73,

Jim, K8OZ
Albuquerque, NM

Top Band Antenna by Mark, G0MGX and Vince G0ORC

Mike, I've been reading with interest your musings on top band antennas and have tried to build a replica of yours today with a fellow ham G0ORC. Thanks very much for the information and the link. You can see the results of my attempts here:

Construction: http://g0mgx.blogspot.co.uk/2012/08/top-band-what-happens-there-then.html

It Works!: http://g0mgx.blogspot.co.uk/2012/08/well-this-top-band-twig-does-it-work.html

Mark. G0MGX

Mike,

I know you have been in contact with my good friend Mark G0MGX but I felt I needed to say thanks and acknowledge your work on a 160m sloper.

It works very well here and, thanks to Mark who built several inductors until one gave us an SWR of 1.1 on the CW end of the band and also braised several copper rods together for form a reasonable earth under a large pine tree. He has passed on to me details of the website of K7MEM which may well inspire me to try a sloper for 80m as well.

I've always wanted a top band antenna but felt that I didn't have the room - but thanks to your idea and Mark's enthusiasm for the project I now have what I wanted - I'm being heard (and can hear) into European Russia with it so it certainly works!

Thanks again - I enjoyed your website very much. (Just heard A65BP as well!)

73, Vince G0ORC http://www.qrz.com/db/G0ORC

Further Developments of this antenna...

Another Top Band Aerial by MØMTJ

After reading the article "Top Band in a Small Garden" in the August 2012 edition of Practical Wireless Magazine ('PW'), I investigated further development of my Top Band Sloper / Inverted L Antenna (shown above).

The article by Stuart Craigen G4GTX described a compact wire antenna for top band that could be accommodated in small gardens. The antenna is shunt fed at the base, the coax being connected across a 7 turn coil (wound on an off-cut of an empty silicone sealant cartridge), with the braid connected to the earth stake and radial ground wires. The centre conductor is connected to the aerial wire.

I could not quite accommodate the shape that Stuart suggested for the aerial wire, but it is very similar: For my version the feed point is at the bottom of the garden near the fence immediately adjacent the earth stake. The first section of aerial is about 9.14 metres long - the wire rises 3.5 metres vertically up the 6.5 metre tall telescopic pole, at the 3.5 metre point the wire is held in place on the mast by a small bungee and then folds over almost horizontally and runs for a further 5.64 metres where it connects to the loading inductor.

The inductor consists of 36 turns of 18 swg (1.2mm diameter) enamelled copper wire on a 50mm diameter, lightweight plastic former (again made from an off-cut of an empty silicone sealant cartridge). After the inductor there is a further 6 metres (approx) of wire rising to a dog-bone insulator, fixed to the end of a length of para cord that runs up to the pulley shown in a previous photograph. From the dog-bone insulator the aerial wire runs back, in the opposite direction, for about 12 metres, returning to the top of the 6.5 metre tall mast at the bottom of the garden, tied off to an egg insulator which is itself fixed to the top of the mast by a very short length of para-cord fixed to the mast by a thick nylon cable tie.

If the wire dimensions are changed, the number of turns on the inductor will have to be changed accordingly. Similarly my antenna is located quite near the 80m/40m Inverted L and the interaction of the antenna affects the tuning and hence the number of turns required on the loading coil.


Pulley
Aluminium pole
Dogbone insulator
Aerial wire
Telescopic fibreglass fishing pole fixed to a wooden post
12 metres
6.5 mtrs
6.3 metres
Egg insulator
Inductor
5.64 metres
< 3.5 mtrs
Counterpoise ground radials
Shunt coil and Connection box
Fence
Halyard
Coax to shack
Dimensions shown are approximate
Wooden post
Another compact Top Band Aerial by M0MTJ
Earth rod

Another Top Band Aerial (drawing not to scale)
The inductor is 36 turns of 1.2mm diameter (18 swg) enamelled copper wire on a 2 inch former

With that arrangement there is about 27 metres of wire in the air. The point of resonance is 1900 kHz, but this can be adjusted by altering the number of turns on the inductor. As expected bandwidth is quite narrow. As with any antenna fed against ground the earthing needs to as extensive as possible - as noted previously, above. I suspect that it may be better that the top wire should be horizontal, or sloping slightly upwards, however with the available space and materials available the best that I could achieve had the top wire sloping slightly downwards to the post. Lowering the position of the dog-bone insulator or using a taller post could overcome this.



Photograph of the feed-point of the compact, folded, Top Band antenna showing the 7 turn shunt fed coil in the weatherproof housing. Nuts and bolts are stainless steel.

First Test: A brief on air test on 8th September 2012 between 2100 and 2130 UTC on 1.933 MHz brought in two prizes: Peter EI7JM near Malin Head and Tony M3LTD in Naseby, Leicestershire. EI7JM was a true 5/9 to me and he gave me a report of a true 5/9. M3LTD was 5/7. Many thanks to both stations for the useful contacts.

For different sized gardens the best idea might be to get as much aerial wire into the air and then make adjustments to the point of resonance by simply adjusting the number of turns on the inductor.

Practical Wireless Magazine
Obtain the article "Top Band in a Small Garden" by Stuart Craigen G4GTX from Practical Wireless Back Issues department

Stuart Craigen G4GTX comments:

Hi Mike, I have just been looking at your fascinating antenna page on top band antennas! Glad to see that you had a go at building my shunt fed wire vertical that I did for Practical Wireless! I found it tremendous. A few weeks ago I was talking to G3YFN in Newcastle at about 4pm when I was called by G4BIM in the Isle of Wight! I also got a QSL 5/9 from Luxembourg!. Have fun.with it!

Thanks for the nice comments about my shunt fed 160m aerial. I enclose some QSL cards which you might find interesting to look at! Note the times of the QSO's and the reports! At night I have been told that I sound like the BBC from some European stations!!

Note G4BIM Isle of Wight 5/7 from Sunderland at 4.30 pm and Aberdeen at night. It certainly works for me. I think that the shunt feeding is the answer as it taps into the aerial at the 50 ohm point. Putting the loading coil away from the base should increase efficiency hence approx midway. A chap near Newcastle built one of these a few years ago and his groundwave signal was 5/9+20 here in Sunderland 12 miles away!!!
73
Stuart G4GTX

More ideas....

Adding Top Band to the 40m / 80m Inverted L antenna using a switchable loading coil:

Due to an aborted house move in 2010 I had removed all the antennas. While re-establishing the aerials in 2011, and considering space limitations, I decided to experiment with adding a loading coil to the 40m / 80m Inverted L aerial. The loading coil has a link wire to short it out of circuit when using the aerial for 80 metres and 40 metres. The link wire is removed when Top Band is required. The coil consists of approximately 37 turns wound on a piece of 68mm (2.8 inch approx) diameter PVC pipe:



Work In Progress! - Adding 160 metre loading coil to the 80m / 40m Inverted L Aerial.
The loading coil has a link wire to short it out of circuit when using the aerial for 80 metres and 40 metres.
The link wire is removed when Top Band is required.
The coil consists of approximately 37 turns wound on a piece of 68mm (2.7 inch approx) diameter PVC pipe.

More about the 80 / 40 metre Inverted L Aerial on Antennas Page 1 >

Simple Vertical Top Band Aerial Using A Fibreglass Telescopic Fishing Pole (Roach Pole)?

If there really is no space to accommodate a top band dipole, inverted V or even the inverted L above, then another option could be a simple vertical. Again based on a 10 metre long fibreglass roach pole, this could be installed as a permanent aerial, or only deployed as and when required on a temporary and stealthy basis.

The 10 metre long fishing pole would be erected by standing it on the ground, using three or four nylon guy ropes as support, or tying it to a wooden ground stake driven into the ground. The vertical radiator would consist of about 9.5 metres of PVC covered wire fixed at the top of the pole and with a loading coil at the centre. As with the design above, the loading coil could be wound on a 5 cm diameter using 1.2 mm diameter enamelled copper wire. To make the former as light weight as possible, once again, the tube from an empty bathroom sealant (or silicone sealer etc) gun could be used. They are, conveniently, 50mm in diameter.

I have not experimented with the number of turns required for the centre loading coil, but from experience with the above aerial, the figure may lie somewhere between 50 and 100 turns.

The aerial would be fed with coaxial cable and would need a good earth rod at its base and a good number of ground radials, as along as possible.

Previous Top Band Aerial Experiments:

Top Band Inverted V

This is a considerably shortened dipole for 160 metres, using loading coils to reduce the length of each leg to about 7.5 metres length. Each coil is wound on a 5 cm diameter former and consists of approximately 120 turns of 1.2mm diameter enamelled copper wire. The dipole was arranged in an inverted V configuration.

Being as a dipole is a balanced aerial, it was fed at its centre using balanced twin feeder for lowest loss and, being balanced, lowest noise.

In this configuration it was very quiet, but did also appear to receive very well. At my QTH the noise on top band generally ranges from S7 to S9, on this inverted V the noise was S4 to S6. However it did not transmit well at all - I believe this to be not only because the dipole is very short (only 15m) but because the angle at which the wires at the top of the V was far too acute - only about 45 degrees. The angle at the top of the V really should be over well 90 degrees - maybe something like 110 degrees would be best. Clearly this seems to be a problem.

I had not got the space to separate the wires any further, but it was an interesting experiment that appeared to demonstrate that a balanced dipole fed with balanced twin feeder could help reduce noise. If more space was available this is an antenna that I would wish to pursue further.


MØMTJ
20m/10m Dipole
80m/40m Inverted L
160m Inverted V
2m/70cm Yagi

Top Band Shortened (loaded) Inverted V

Short Base Loaded Sloper - a first attempt at a top band antenna

160m metres is probably the noisiest band, but I wanted to give it a go anyway even though space at my QTH is at a premium and fitting in a suitable antenna is quite challenging. The most promising candidate that I initially found, apart from small commercially available antennas, was the "Practical Antenna For 160 metres" described by Frank G3YCC and featured on the website of IW5EDI and linked to on the pages of www.dxzone.com


70 ft
70 ft of pvc covered stranded wire space wound on 1 1/4 in fibre glass tubing
mount on mast
50 Ohm Coax
Antenna for 160 meters band

G3YCC Top Band Antenna

This Top Band antenna consists of 140 feet of wire, 70 feet space wound around a non-conductive (fibreglass) pole or tube about 6 feet long, with remainder forming a sloping wire falling back to near ground level. The antenna is UN-Balanced and is therefore fed with unbalanced coaxial cable, with the braid connected to a ground stake at the base of the aerial.

The above design is intended to have the coil section mounted on top of a mast or pole with the wire running downwards. I could not accommodate that arrangement, so I adapted the design to produce the antenna shown below:


Nylon halyard & pulley
Egg insulator
Fence or wall
10m
Antenna wire
Pulley
Loading Coil
Nylon halyard
Connection box
1m
Radial Wires
Coaxial cable
Earth Rod

The drawing above shows the loaded Top-Band Antenna - a first attempt at an aerial for 160m - consisting of the radiating top wire, a base loading coil, earth stake and additional earth radials that act as a counterpoise: The top wire is about 10 metres long and slopes down to the loading coil which consists of 64 turns of the aerial cable wound around a 4" diameter PVC pipe and then falls vertically for about 1 metre where it enters the connection box. The halyard arrangement allows the antenna wire to be quickly dropped for adjustment and then raised back into position. There is an earth rod at the base of the antenna connected to several ground radials and a second earth rod a few metres away.After performing some tests I find that it does work reasonably well for local contacts ground wave contacts around the town, but it could be better and is certainly very disappointing for longer distance work.


Antenna Wire
Box
'Choc Block' connectors
RG213 coax
Earth Cable
To TXVR
To Earth Spike

Above: The Connection Box

Read more developments here>

Efficiency

The aerial shown above is obviously very much shortened and therefore is very inefficient when compared to a full size resonant quater wave aerial. A shortened aerial still needs to make best use of the space - so the antenna wire needs to be as long as possible. Resonance is adjusted by varying the inductance of the loading coil. Also it is necessary to use the largest earth system as is practicable to obtain the best possible efficiency.

Performance

In my configuration described above it is admittedly a very low efficiency antenna - but at least it gets one on Top Band! It's ok for local working around a town or a city, but it's certainly not a DX aerial by any stretch of the imagination. I could hear many stations 100 to 200 miles away, but they could not read my signals. For local ground wave work it was adequate.

I suspect that if the original design by G3YCC was employed, i.e. the coil mounted at the top of a pole and the loading wire running down, that it may work rather better than my implementation. The problem that my implementation has is that the loading coil is at the bottom of the aerial, near the ground. Better efficiency may be acheived with centre loading. The longer the radiating wire the better too.

More Details

The antenna was fed by coaxial cable from the shack in the bedroom at the front of the house to the feed point at the base of the fence at the bottom of the back garden. The coaxial cable enters a small plastic box, screwed to the fence post, where it is terminated: The outer conductor of the coax is connected to the earth cable with a 'chock block' connecter, the earth cable going to a four foot long earth rod hammered into the ground near by. The centre conductor of the coax is connected to the antenna cable also using a 'choc block' connector.

The antenna wire runs vertically up the fence for about 1 metre to the loading coil which consists of 64 turns of the antenna wire wound around a piece of 4 inch diameter PVC pipe. About 32 turns a close wound and the other 32 turns space wound; The inductance, and therefore the point of resonance could be easily adjusted by altering the spacing of the windings. Once set at the required point of resonance the windings can be held in place with duck tape.

The antenna wire exits the coil at the top and passes through a pully secured to the top of the fence and then slopes upwards for about 10 metres to the fixing point at a convenient point on the house, in this case the eaves. The end of the wire is tied off to a plastic 'egg insulator'. The egg insulator is tied to a nylon halyard wich passes through a second pully at the fixing point. This allows the antenna wire to be quickly dropped for adjustment and then raised back into position.

The earth system should be as extensive as possible for better efficiency; e.g. earth stake and a number earth radials, as long as possible around the garden to provide a counterpoise.

Link:

Visit www.g7klj.com - the website of 160 metre entusiast Steve G7KLJ

OTHER THINGS

Antennas for HF

There are dozens, if not hundreds, of antenna designs from which to choose. All have their own proponents. Some are genuinely good while others might be considered as nothing more than glorified dummy loads! The key thing for me was to choose the most effective an antenna that could fit within the constrains of my small back garden and also one that would not be too ugly.

I decided that wire antennas, made from PVC covered stranded wire, would be least objectionable on visual grounds. After all they look like glorified washing lines and almost everyone has a washing line**!**

Knots to use when fixing Wire Antennas

It's important to use the correct knot for the job. I find that the Bowline is very useful for fixing end, egg and dog-bone insulators to the ends of the wire and/or ropes. The Round Turn & Two Hitches, Anchor Bend and Buntline Hitch knots are very good for tying a rope to a pole or a mast. A Double Sheet Bend can join two pieces of rope together - even if they are of unequal size. 'Animated Knots' will show you how to do them: http://www.animatedknots.com

The antenna or antennas really are the key to an effective amateur radio station. The most expensive radio will be of little value unless it is used with the best possible and most effective antenna; so I had to set about finding the best antennas that I could accommodate for HF and VHF work.

The dilemma facing most radio amateurs is that antennas for HF are often large and difficult to accommodate in modern small back gardens. Additionally there may be objections on the grounds of visual impact. Some people do not regard antennas as the beautiful creations that radio enthusiasts do!

Cables and Feeders

As I have learned by experience and from the tutorials I have studied as part of the licensing exam process, a very important consideration concerning the antenna system is the loss incurred in the cable that connects the radio to the antenna. A loss of 3dB sounds like a small amount when you say it quickly, but that equates to only HALF of your transmitter power reaching the aerial! We'd soon complain if our new 100 watt transceiver only produced 50 watts - so why stand the chance of losing this much power in the feed line?

Starting off as an M3 licensee I could only use 10dBw (10 watts) power at the antenna termination, so if I had a feeder with a loss of 3dB I would have to run the transmitter at 20 Watts to get 10 watts to the aerial!

Coaxial Cables

For HF using a single band resonant antenna, a dipole for example, Mini 8 or even RG58 is probably fine since the SWR should be between 1:1 and 2:1. However if one was to consider using the antenna on non resonant frequencies the VSWR will be higher, maybe very much higher, and the consequential losses in coaxial cable will be greatly magnified and power losses very significant. I did not want to run such an inefficient station.

For this reason I chose to use low loss RG213 coaxial cable for my Inverted L since I may need to use it on bands other than the 40 metre and 80 metres that it is intended for and where the SWR may be 4:1 or 5:1. RG213 will help keep feedline losses to a minimum. No lossy RG58 on Mini8 for me! Westflex 103 would be even better, of course.

For VHF and UHF I now consider Westflex103 as the minimum standard of cable to use, it's half the loss of even RG213. Losses at VHF are much higher than HF and at UHF they are even higher, so Westflex 103 helps preserve as much of that precious transmitter power as possible.

See more about Coaxial Cable Losses here >

Balanced Feeders = Low Noise

It's difficult to feed a centre fed wire dipole with RG213 or Westflex 103, both cables are really too thick and heavy. RG58 or Mini 8 are lighter and therefore more suitable for suspended wire dipoles, but to match the unbalanced coaxial cable to the balanced dipole would need a 1:1 'choke balun' at its centre, as I have learned. However, as mentioned above, when attempting to use the dipole at non-resonant frequencies the VSWR will be higher and the losses in the coaxial cable will be very much larger too, and hence much less of the precious transmitter power will be actually radiated by the antenna. Not an ideal situation

I have learned that the only really sensible way to feed dipole type antennas, which are 'balanced', is to use a balanced feeder such as 300 ohm ribbon cable, 450 ohm ladder line or the best option, it seems, might be 75 ohm Twin Feeder. All such twin feeders are extremely low loss, much much lower than any coaxial cable, so low that it could almost be considered lossless by comparison. Of course nothing is lossless, but twin feeder is as near as you'll get, so that's how I will feed my dipoles from now on! See the note on Doublet antennas below.

Tony Nailer of Spectrum Communications notes that: "75 ohm twin feeder is lower loss than coax. It allows the aerial to be properly balanced and the very close spacing of the wires prevents pickup or radiation from the feeder. It does not need to be spaced off, unlike ribbon feeder. Use of twin feeder makes this aerial much lower noise than one fed with coax. Also importantly it generates less TVI !! Note that the [trapped dipole] aerial is generally 72 ohms, and will need to be used with an ATU with transistorised rigs which are unforgiving about SWR mismatches."

Spectrum Communications are now supplying a new design of top quality, very low loss, twin feeder. It is rated at 2kW at 100 ohms. It can be supplied by 100 metre reel or by the meter, or in various lengths with the ends expertly terminated and made off. I can confirm the superior quality of this product and its low noise properties.

Spectrum Communications also supply a very high quality, well made 1:1 Balun that is perfect for connecting the twin feeder to the unbalanced input of an A.T.U. of transceiver.

Doublet or Dipole (Horizontal or Sloper)

I have also experimented with a second HF antenna - the 'doublet' style antenna. I fed this with low loss twin feeder and cut it for the lowest frequency of operation, in my case 20 metres (14 MHz).

Some initial experiments have shown that it is very effective on 20 metres, better than my Inverted L - which is designed essentially for 80m and 40m.

In theory a doublet antenna, when fed by twin feeder (NOT coaxial cable) and matched at the transmitter end via a

1:1 balun and an ATU (or to use a more correct term, Antenna Matching Unit) at the transceiver should be able to work on all bands with a higher frequency than the band that it is cut for.

On other bands such as 17m (18 MHz), 15m (21 MHz), 12m (24 MHz) and 10m 28 MHz) the doublet showed generally lower VSWR than the Inverted L .... however (and here is a nice lesson) it is actually not quite as effective as the Inverted L! I think that size may matter here - the overall length of the Inverted L is much longer.

This short 14 MHz doublet is only about 10 metres in total length and was suspended at about 25 feet high at one end from the same fibreglass pole fixed at the apex of the roof and taken down to another 16 foot high wooden pole installed on the other side of the back garden in somewhat of a 'sloper' style.

Trapped Horizontal Dipole or Vertical Antenna for 20m / 10m

I also experimented with a trapped wire dipole cut to be resonant for 20 metres and 10 metres, again fed with twin feeder and matched at the radio end via a 1:1 balun and the ATU (AMU !).

I may also try an antenna for 20m / 15m and 10m in a Vertical 'ground plane' arrangement which should give a lower angle of radiation than a horizontal dipole - therefore better for longer distance DX.

At the moment I am using the 20m / 10m trapped dipole in a rather unorthodox arrangement. I have installed a fibreglass fishing pole, mounted vertically on a stake on one side of the garden. Most of the wire dipole is fixed to the vertical pole, but being as the dipole is somewhat longer than 7 metres, a portion of the wire runs away from the pole horizontally along a fence panel about 1.5 meters above ground level. It's vaguely L shaped, but mostly vertical which should help with the angle of radiation. It seems to work very well indeed - I like the mostly vertical idea.
The antenna can be seen on this page >

Other Dipoles:

Spectrum Communications can supply a full size W3DZZ style antenna with a 7MHz trap for use on 40m and 80m and usable on 20m, 15m and 10m. A half size version with a 14 MHz trap for use on 40m and 20 metres, plus 15m and 10m is also available. As a special order an even shorter version using a 28 MHz trap is available for 20 metres and 10 metres. http://www.spectrumcomms.co.uk/G2DYM.htm Al versions designed to be used with balanced line feeder - lince they are balanced aerials - for low noise and lowest loss.

PDF Document - The W3DZZ Antenna -
http://www.users.icscotland.net/~len.paget/GM0ONX%20trap%20dipole.pdf (But rather than using coaxial cable with a 'choke balun' at the centre of the dipole, try using twin feeder with the Choke Balun at the radio end for less power loss!)

Links

Enamelled copper wire supply: http://www.esr.co.uk/electronics/cable-copper.htm

Loading coil calculators: http://www.k7mem.com/Electronic_Notebook/antennas/shortant.html

Ring Core Calculator: http://www.dl5swb.de/html/mini_ring_core_calculator.htm

Vertical Antenna For 50 MHz, 144 MHz and 430 MHz



Watson W-2000 on Telescopic Mast at the lowest position
more on this page

OTHER ANTENNAS

Our good friend in Australia Felix Scerri, VK4FUQ, uses Inverted V antennas but also highly recommends the Quad Loop style antenna for HF work. These are well worth investigating, and you can read more here: Antennas 3 see the antennas at the MØMTJ QTH here with many more antenna ideas on Antennas 4 and the Links Page here and here

Antennas 1 | Antennas 3 | Antennas 4 | Antennas 5 | Antennas 6 | Antennas 7

G Whip Antenna Products
G-Whip Antenna Products
Geoff G4ICD offers a multitude of high quality solutions for portable, mobile and permenant base installations

M0MTJ | Operating Conditions | Antennas / Aerials | /P Portable Operating | Accessories | Projects & Kits | Useful Information

Contact MØMTJ | Contact M6ORS | Links to Amateur Radio Sites | RSGB | QSL | The Amateur Radio Mini Site Map

WSPR Weak Signal Propagation Reporter

News, Developments, Events, Photographs and other 'Bits 'n' Bobs'

MDS975 Home

Feedback

MAIL

Mike Smith - MDS975.co.uk © 2003 - 2016

M0MTJ

Amateur Radio; Ham Radio; Radio; Transceivers; HF; VHF; UHF; Data Modes; Morse Code; RTTY; PSK31; SSTV; FSTV; Amtor; Sitor Antennas; Aerials; Cable; Coaxial Cable; Twin Lead; Masts; Poles; Propagation; Computer; PC; USB Computer Interface; Microphone Loudspeaker; Filters; Noise Reduction; DSP; Digital Signal Processing; Morse Key; SWR ; Inverted L; Inverted V; Dipole; Doublet.

My Home Page

Amateur Radio Operating Conditions
Antennas
Accessories
Projects & Kits
Data Modes
Information
Portable
QSL
RSGB Ltd
Links
QRM
Bits 'n' Bobs
Contact

WSPR
Weak Signal Propagation Reporting

PORTABLE

Site Map

MDS975 Home

Feedback

Site Search
Find
powered by FreeFind

QRM from PLT

G Whip Antenna Products

M0MTJ | Operating Conditions | Antennas / Aerials | /P Portable Operating | Accessories | Projects & Kits | Useful Information
Contact MØMTJ | Contact M6ORS | Links to Amateur Radio Sites | RSGB | QSL | The Amateur Radio Mini Site Map
News, Developments, Events, Photographs and other 'Bits 'n' Bobs' | WSPR Weak Signal Propagation Reporter

AERIALS (ANTENNAS) 1

Antennas 2 | Antennas 3 | Antennas 4 | Antennas 5 | Antennas 6 | Antennas 7

"Success is 90% antenna and 10% rig. Hobby is 90% listening 10% transmitting" - *MM0HDW.*

AERIALS used by MØMTJ

This page shows some the antennas that I have used over the course of time.

Index To Other Antenna Pages:
Antennas 1 : Aerials used by M0MTJ
Antennas 2 : Including ideas for compact aerials for Top Band /160 metres
Antennas 3 : Felix Scerri VK4FUQ discusses Loop Aerials, baluns, masts & other antenna related topics
Antennas 4 : Many antenna ideas from various sources particularly for multi-band operation & also gives information about
antenna trimming, knots for wire antennas and useful aerial rigging accessory ideas.
Antennas 5 : Half Wave (physically end fed) aerials for 144 MHz VHF / 430 MHz UHF and 50 MHz 6 Metre band & J-Pole Aerials
Antennas 6 : Simple and effective H.F. Aerial ideas: The All Band Doublet, an All Band Sloper & a Ground Plane Aerial
Antennas 7 : Omni-Directional - Circularly (Mixed) Polarized Aerial for VHF / 2 Meters.

2014 : Current Set Up - as at September 2014:



The Summer of 2014 has seen a few changes of aerials. The 80m/40m Inverted L was removed and replaced with a newly constructed Doublet Antenna fed with ladder line via a 4:1 G-Whip current balun and an LDG "ATU". The Tecadi support pole originally used for the Inverted L is now used to support one end of the Doublet. You have probably read this elsewhere, but I can confirm that the All Band Doublet (fed with ladder line *not coax*) is a superb all round HF aerial. Highly recommended.

The SGC-230 Automatic Antenna Coupler was moved from the original feedpoint of the Inverted L antenna to the second feed-point on the other side of the garden. This now feeds a sloping wire of approximately 20 meters length to ensure that the 80 Meter Band and Top Band (160 meters) remain available. This antenna will also 'tune' on most other bands, so remains a very useful second antenna, though the All Band Doublet is often considerably better, particularly on the higher frequencies. The old SGC-230 was also faulty and I replaced it with a new CG-3000 auto coupler from Martin Lynch and Sons.

The J-Pole for 4 Meters (70 MHz) was removed since it wasn't used much, being only connected to a 4m hand-held radio - it seemed to be a waste of precious antenna space. This was replaced with a newly constructed Half Wave "CFR" Antenna (Coaxial Dipole) for 6 Meters (50 MHz) connected to the main HF radio via Westflex 103 coax. The DK7ZB dual band Yagi antenna remains, as does the 10m / 6m Fan Dipole in the loft space. Also remaining in place at the apex of the house is the home-brew 2m / 70cm "CFR" Antenna (Coaxial Dipole) for VHF/UHF FM operation - this has been a particularly effective antenna.

To sumarise:

1) A 20 meter long doublet antenna fed with balanced ladder line for 40 meters to 6 meters. The 'old timers' really knew their stuff, this an excellent all round antenna that is easy and cheap to make and should be quite easy to accommodate and install. See photograph below and read more here

2) A Sloper Antenna consisting of two parallel wires - one wire being 20 meters long with a second parallel wire

Get on the air with TOP QUALITY BRITISH G-WHIP ANTENNAS



SOTA Beams Lightweight 2 metre & 70cms Yagis, Dipole, Accessories & Poles www.sotabeams.co.uk


MØMTJ
Sloper Antenna
Pulley
Egg Insulator
Aluminium Pole
80mm spacers
3.5 metre tall fibreglass pole
20 meter long antenna wire
10 meter long antenna wire
Halyard
Counterpoise Wires
CG-3000 Auto Coupler
Earth Stake
(Not to scale)
160m to 10m using two parallel sloping wires & remote auto antenna coupler

that is 10 meters in length. The first 2.5 meters (approx) of wire runs vertically up a non metallic post, then the remainder slopes back towards the house being finished off with an insulator which is attached to a Para-Cord lanyard that runs through a pulley on a pole at the apex of the roof. The antenna wire can therefore easily be let down for maintenance or adjustment whenever required. For lowest possible loss, the antenna is fed via a GC3000 automatic antenna coupler located at the bottom of the garden. The antenna is primarily for lower HF bands including 160 meters, 80 meters and and 40 meters, but it also works very well on some higher bands. The GC3000 itself is mounted in a waterproof IP56 rated enclosure near ground level at the bottom of the garden. Grounding is achieved from two 4 foot long copper ground stakes and several radial grounding wires.

Read more about the Sloper Antenna and the CG3000 here.

3) A 'home-brew' omnidirectional, vertical dual band, end fed antenna for 2 metres and 70cm. This is of the Controlled Feeder Radiation design (CFR) by VK2ZOI; effectively an end fed half wave dipole on 2m with an aluminium sleeve dipole section to achieve 70cms with a few extra dB's of gain. It is mounted on an aluminium mast. It's feed-point is about 11 metres a.g.l. read more here

4) A DK7ZB design dual band Yagi antenna, with 5 elements for 2 metres and 8 elements for 70cms, mounted horizontally for SSB. A lightweight antenna rotator is employed and uses a push-up telescopic mast. Height above ground level is again approximately 7 metres. The DK7ZB is an excellent twin band Yagi antenna. read more here

5) A Half Wave End Fed / Controlled Feeder Radiation (CFR) antenna for 6 meters / 50 MHz. Supported by a 3 meter long telescopic fibreglass fishing pole attached to the top of the aluminium push up mast that supports the DK7ZB dual band yagi and rotator.

6) Dual Band Fan Dipole, made from thick loudspeaker wire, mounted horizontally in the loft space for 10 meters an 6 metres. Cheap & quite effective.

Other Options that can be deployed on an 'as required basis' :

7) A half wave Wire J-Pole fixed to a telescopic fibreglass fishing pole for 10m. Cheap and effective. more about J-Poles here and also here on Antenna page 5

8) Compact Loaded Top Band Antenna, based on a design idea by Stuart Craigen G4GTX more

9 & 10) G Whip End Fed Zepps (EFZ's) for either 20m, 15m or 17m or the G-Whip "WideBander" which is an 'UnTenna' style antenna that can be used for 20m through to 10m using good quality G Whip 9:1 UnUn; useful additions for antenna flexibility. more

11) N9TAX Dual Band Slim Jim (J-Pole) antenna mounted in the loft as a back-up antenna for 2m and 70cms. Very good. more

12) Delta Loop Antenna - 16 metre loop of wire in triangular Delta shape, hung from the top of the pole supporting the inverted L antenna and fed via RG213 coaxial cable via a 4:1 balun. The loop is really a single band antenna cut for one wavelength on the band of interest, however it also can be pressed into service for some higher bands - a good, cheap and easy to install aerial; Often works better than the inverted L on the higher bands, but on 10 metres the tuned 10 metre dipole in the loft is sometimes better. more

Knots: Knots for securing wire aerials and other things more here

H.F. ANTENNAS used by M0MTJ

All Band Doublet Antenna

The Doublet Antenna consists of two 10 meter long top wires to form the 20 meter long 'dipole' section. The centre is fed with Ladder Line rather than coaxial cable. A dipole fed with coaxial cable is essentially a single band (mono band) antenna. Feeding such an aerial with ladder line, or open wire twin feeder makes a much more effective multi-band antenna.

The ladder line runs down to a high efficiency 4:1 Current Balun (G-Whip) which is connected to an LDG AT-200 automatic antenna matching unit via a very short RG213 patch lead to ensure lowest losses. The Antenna tuner and balun are housed in a box which is itself contained in a small garden shed to protect it from the weather. The LDG antenna matching unit is then connected back to the 'shack' via a run of RG-213 coaxial cable. Read more about the All Band Doublet Antenna here.

A view of part of the MØMTJ All Band Doublet Antenna
Read more here

ANTENNAS FOR VHF and UHF - 2 m & 70 cms

The main antennas are as follows:

Home-Brew dual band end (physically end fed) half wave "Coaxial Dipole" for 2m & 70cm

For 2m and 70cm FM I use a mounted on a lightweight aluminium telescopic pole on the apex of the hose. The base of the antenna (the bottom of the radiating element) is approximately 11 metres above ground level. This antenna is based on the Controlled Feeder Radiation principle (CFR) and is described by VK2ZOI. Read more about its construction here. Also seen in the photograph below are the ropes that support the H.F. wire aerials.

Home brew dual band vertical antenna for 2 metres and 70 cms
Read more about its construction here

Dual Band Yagi for 2m & 70cm

For 2 metres and 70cms SSB there is a horizontal DK7ZB design dual band Yagi antenna. This has 5 elements for 2 metres and 8 elements for 70 cms. A lightweight antenna rotator is employed and uses the same push-up telescopic mast that the Home-Brew 70MHz J-Pole is mounted on. Height above ground level is again approximately 7 metres. The DK7ZB is an excellent twin band Yagi antenna**.**



Push up aluminium mast with rotator, 2m / 70cm DK7ZB Yagi and a 4m J-Pole at the top



The DK7ZB 5 + 8 element dual band yagi for 2m and 70 cm - designed by Martin Steyer DK7ZB
Available from Arthur M0PLK (SQ2PLK) at Ham Radio Shop:
http://stores.ebay.co.uk/urbasket-eu
http://ham-radio.urbasket.eu
Also available from VPA SYSTEMS by SQ9VPA http://www.vpa-systems.pl
Kits available from NUXCOM.de : http://shop.nuxcom.de

2 Meter J-Pole Antenna for the garden shed - and other J-Pole antennas for 6 metres and 10 metres :

While experimenting with antennas in the garden in the summer of 2012 I thought that it would be good to have a hand-held radio in the shed to do some monitoring and make a few contacts. To improve upon the performance of the 'rubber duck' antenna I quickly made a J-Pole antenna for the 2 metre band.

It is made from a 47cm length of 450 ohm Wireman ladder line as the 1/4 wave matching section, plus a 97cm length of stranded wire as the 1/2 wave radiator. It is fed with 3 metres of Mil spec RG58 c/u coaxial cable that is soldered to the 1/4 wave matching section's impedance matching point at 3.5 cm from the bottom. The coax feeder is wound around some PVC tube to form a choke. The completed antenna is taped to a 2.2 metre long fibreglass fishing pole that I purchased from Poundland (for £1.00). It took about 20 minutes to make followed by some testing and adjustment with the antenna analyser. The fishing pole is lashed to the shed with some cable ties.

This simple antenna works pretty well, but being so low down signal strengths are not huge, but it's pleasing to get on the air with something so simple and cheap!

Find out how easy it is to construct J-Pole Antennas here

Now, if it was at the top of my 10 metre long fishing pole. . . . . (!)



The Shed Antenna - a 2m J-Pole by M0MTJ
Note the simple choke balun at its base made by winding 8 turns
of the coaxial cable around a small off cut of white PVC water pipe.
Find out how easy it is to construct J-Pole Antennas here



The feed point of a J-Pole antenna made from Wireman 450 ohm ladder line.
More here

More Antennas . . .

Inverted L Antenna for 80m and 40m (and some other HF Bands from 80m to 10m)



The basic layout of the Inverted L Antenna (Practical Wireless)

The first antenna that I installed was for HF. I decided on an Inverted L that incorporates a 7MHz trap so that it can be used on both 7MHz (40 metres) and 3.5 MHz (80 metres).

The design of this Inverted L is well known and a good design has been published previously in Practical Wireless by Len Paget GM0ONX. It is based on one half of the famous W3DZZ trapped dipole antenna.

It can be made entirely from scratch as a DIY project, or the 7MHz trap could be purchased commercially as a ready made item, or whole antenna can bought as a complete kit from Tony Nailer, G4CFY, at Spectrum Communications. I opted to buy the 7MHz trap from Spectrum Communications, as I already had most of the other materials required - rope, egg insulator, plastic box, and some good aerial wire. The Spectrum Communications trap is solid and well made and 'potted' to protect against the elements.

This antenna is tuned for 40 metres and 80 metres, but the VSWR is acceptable on several other bands being in the region of 2:1 to 5:1. The designer anticipated that this antenna would be usable on five of the H.F. bands between 80m and 10m.

I have found that with the use of the Antenna Tuning Unit it can be used on all of the H.F. bands. However the polar radiation pattern may very well be less predictable on bands other than the intended 40 and 80 metres, and it may well be less effective than might be desirable - but it does work!

The antenna is in the back garden, while the shack (radio room) is in a bedroom at the front of the house. It is fed by a 30 metre length of RG213 coaxial cable (it is not possible to use twin feeder for this type of antenna as the Inverted L is an UN-Balanced aerial, whereas twin feeder is balanced). With this length of cable I estimate the loss in the feeder alone to be about 1dB at 7MHz. The feed point of the aerial is located at the base of a 16 foot high wooden pole near the bottom of the garden. The horizontal top wire returns to a fibreglass pole installed at the apex of the roof.

+ 17 + 160: I have since added a separate sloping wire element for the 17 Metre Band and a switchable loading coil for Top Band - see notes below...



Photograph showing the wooden support post and termination point of the Inverted L antenna The post is coloured green with green fence treatment to mast it somewhat. I have also placed it near the bush to provide further camouflage.



The low loss RG213 coaxial cable runs from the shack at the front of the house up into the loft and exits into the back garden down the rear wall, through some garden hose to offer some protection along the flower bed to the bottom of the garden where it is connected to the base of the Inverted L antenna.

The suspended Inverted L aerial with 7 MHz trap.

The Inverted L antenna - lower section now nicely camouflaged. The wooden support post is some 6 metres long.



The photograph above shows the Dacron ropes supporting the ends of the Inverted L and Dipole antennas are held in place at the top of the fibreglass support mast by a pulley - one pulley for each support rope. This facilitates rapid lowering of either antenna for adjustment or replacement. This photograph also shows a second rope and pulley system that was originally used to support the 20m dipole and is now used for the top band inverted L wire aerial.

I needed a good reliable knot for securing ropes when installing wire antennas and have found the Bowline to be one of the most useful, it is strong and easy to tie. A Bowline will not slip in any circumstances and, usefully, the more load that is put on it, the tighter it gets.



The Bowline Knot

A Bowline can be used to tie two ropes together and should be used to tie a support rope to a pulley, dipole centre and other antenna items.

It's important to use the correct knot for the job when fixing up wire antennas. I find the Bowline is a very useful for fixing end, egg and dog-bone insulators to the ends of the wire and/or ropes. The Round Turn & Two Hitches, Anchor Bend (Anchor Hitch) and Buntline Hitch knots are very good for tying a rope to a pole or a mast. A Double Sheet Bend can join two pieces of rope together - even if they are of unequal size. 'Animated Knots' will show you how to do them: http://www.animatedknots.com

Photo showing pulley fixed to the top of the wooden support post and the aerial support rope that it holds in place.

The Spectrum Communications Trap



View of trap showing that the joints have been thoroughly sealed against the weather with self amalgamating tape and silicone sealant.



Just for good measure I sealed the internal side of the machine screw that forms the connection terminal against the weather with Watson sealant putty.

Adding Top Band to the 80 / 40 metre Inverted L Antenna:

Due to an aborted house move in 2010 I had removed all the antennas. While re-establishing the aerials in 2011, and considering space limitations, I decided to experiment with adding a loading coil to the 40m / 80m Inverted L aerial. The loading coil has a link wire to short it out of circuit when using the aerial for 80 metres and 40 metres. The link wire is removed when Top Band is required.

I also took the opportunity to replace the original wooden post with a strong 6 metre tall fibreglass pole.

The coil consists of approximately 37 turns of PVC covered antenna wire wound on a short piece of PVC pipe. Once the required points of resonance were set for 40 metres and 80 metres, the link wire was removed and number of turns on the coil were adjusted until the required point of resonance was found on the 160 metre band. I set it to around 1900 kHz - the bandwidth is quite narrow.

Once the work was done, the joints and connections were sealed with either Liquid Electrical Tape or self amalgamating tape, then the connecting box, V bolts and white PVC pipe were sprayed with green paint to help it all blend in with the surroundings a little better.

Adding the 17 Metre (18 MHz) Band to the 80 / 40 metre Inverted L Antenna:

The Inverted L is not too good for the 'WARC' bands so to obtain better performance on the 17 Metre band I added a single slightly sloping wire element cut for that band. The lower end of the wire is permanently connected to the feed terminal on the junction box, the other end is tied to a small dog bone insulator. This dog bone is then supported by a length of thin para-cord which is tied to the horizontal wire of the main Inverted L element. (N.B. The 17 metre modification is not currently shown in the photographs below.)



Work In Progress! - September 2011
Reconfiguring Inverted L with additional Top Band Loading Coil for 160 metres.
A strong 6 metre tall fibreglass pole replaces the original heavy wooden post.



Adding 160 metre loading coil to the 80m / 40m Inverted L Aerial.
The loading coil has a link wire to short it out of circuit when using the aerial for 80 metres and 40 metres.
The link wire is removed when Top Band is required.
The coil consists of approximately 37 turns wound on a piece of PVC pipe.



Adding 160 metre loading coil to the 80m / 40m Inverted L Aerial.
The loading coil has a link wire to short it out of circuit when using the aerial for 80 metres and 40 metres.
The link wire is removed when Top Band is required.
The coil consists of approximately 37 turns wound on a piece of PVC pipe.


Inverted L wire
Pulleys
Small dog bone
Delta Loop wire
Para Cord to hoist second wire element
Para Cord to hoist Delta Loop
Second wire element
Fibreglass pole
MØMTJ

Photograph showing the Inverted L antenna with additional vertical wire element and position of Delta Loop


TRAPPED INVERTED L ANTENNA
19'7"
7·1 MHz
TRAP
INSULATED POLE
33'
COUPLING BOX
COAX
SUPPORT & EARTH STAKE
80 - 10 metres, with a small garden.

The commercial version of the basic 80m - 10m Inverted L is available from Tony Nailer at Spectrum Communications

Important notes on effective Grounding by Jim K8OZ

Mike - I was reading about your work on the 160 meter Inverted L, and it makes me want to go out and build some more antennas! Congratulations. Your story is fascinating, and very well documented.

The only thing I can offer as a suggestion is to get as much radial wire along the edge of your property as possible (assuming your XYL will not allow you to bury radial wire all over your yard). Even if you can only run multiple wires 1/8th of a meter apart from each other, and parallel to each other, your losses will be reduced. The ground lossses have quite an impact on your transmitted signal, so any wire you can "hide" along the edge of your property will help improve your signal strentgh - little, by little...!   { It may also affect your resonant frequency slightly, but that's easy to deal with by adjusting with an antenna tuner or slightly changing the loading coil. }

Good luck OM, and keep up the refinements on your antenna system. You're doing great! 73,

Jim, K8OZ
Albuquerque, NM

Delta Loop Antenna - Tuned for the 17 metre band but also usable as a multi-band operation



A typical Delta Loop antenna - diagram by W5SDC - gives multi-band operation with minimal cost.
My Delta Loop is fed near the bottom corner - it cannot be fed at the top, as in the diagram above, due to unwanted interaction with the antenna wire of the Inverted L antenna which is supported on the same pole.

My Delta Loop is fed near the bottom at one corner - it cannot be fed at the top, as in the diagram above, due to unwanted interaction with the antenna wire of the Inverted L antenna which is supported on the same pole.

It consists of a 16 metre long loop of wire in triangular Delta shape, hung from the top of the pole supporting the inverted L antenna and fed via RG213 coaxial cable via a home-brew 4:1 balun. A loop is really a single band antenna cut for one wavelength on the band of interest, however it can also work on higher bands with an ATU - as a good, cheap and easy to install multi-band H.F. aerial. Performance is a little better than the inverted L on the higher bands, but on 10 metres the tuned 10 / 6 metre wire 'fan' dipole in the loft can still be better.


Inverted L wire
Delta Loop wire
MØMTJ

Apex of Delta Loop by M0MTJ


Small dog bone insulator
Delta Loop wire
M0MTJ

Bottom left corner of Delta Loop antenna by M0MTJ


Ladder line of a different antenna
Delta Loop wires
4:1 Balun
Short timber support post
MØMTJ

Feed point of the Delta Loop at the bottom right hand corner



The Feed Point of the Delta Loop Antenna is at the bottom right hand corner
The Antenna is fed via a 'home brew' 4:1 balun by M0MTJ

Below are the VSWR measurements for the 16 metre long loop which has been measured an cut for resonance in the 17 metre band. For comparison are the measurements for the 12 metre long loop (which has not been optimised) and an 18 metre long loop which is of arbitrary length:

16 metre long loop of wire for the 17 Metre Band (optimised for 17m band)		
BAND	VSWR	VSWR
20m	14.0 MHz = 6.5	14.35 MHz = 4.9
17m	18.07 MHz = 1.2	18.16 MHz = 1.2
15m	21.0 MHz = 3.1	21.45 MHz = 3.7
12m	24.8 MHz = 5.9	25.9 MHz = 6.1
10m	28.0 MHz = 4.1	29.5 MHz = 4.4

12 metre long loop of wire for the 12 Metre Band (NOT optimised)		
BAND	VSWR	VSWR
20m	14.0 MHz = 22.1	14.35 MHz = 21.1
17m	18.07 MHz = 8.4	18.16 MHz = 8.1
15m	21.0 MHz = 5.0	21.45 MHz = 4.6
12m	24.8 MHz = 1.9	25.9 MHz = 2.0
10m	28.0 MHz = 5.0	29.5 MHz = 6.1

18 metre long loop of wire (An arbitary length between 20m & 17m)		
BAND	VSWR	VSWR
20m	14.0 MHz = 2.1	14.35 MHz = 1.4

17m	18.07 MHz = 2.6	18.16 MHz = 2.5
15m	21.0 MHz = 6.8	21.45 MHz = 8.4
12m	24.8 MHz = 6.3	25.9 MHz = 6.5
10m	28.0 MHz = 2.9	29.5 MHz = 2.5

Many users claim that loop aerials are quieter than typical vertical antennas. There are many plans available in the internet and given a suitable support or pole and a 4:1 balun it can take only a few minutes to install a loop antenna.

Arthur M0PLK (SQ2PLK) at Ham Radio Shop supplies an interesting lightweight self supporting Delta Loop antenna: http://ham-radio.urbasket.eu - see the review on the Polonia DX Award here: http://pdxa.one.pl/articles.php?article_id=17

LOOP ANTENNA LINKS: See lots more links to Loop Antennas on my links page here

Dipole or Doublet Antenna for 20m and 10m

This is an antenna trapped dipole for 20m and 10m. Currently it is fed by 75 ohm twin feeder to a 1:1 balun in the loft, then on to the ATU (AMU) via a short RG213 coaxial cable. Although it was initially installed horizontally, it is now installed with one leg supported vertically on a 7 metre fibreglass 'Sota' pole with the other leg supported horizontally about 2 metres above the ground. This is a rather unorthodox arrangement for a balanced dipole, but it seems to work ok and was inspired by another radio amateur's idea - although I don't recommend balanced feeder for this arrangement!

It looks much neater than the horizontally strung dipole and offers a more omnidirectional radiation pattern too.



Dipole Centre with PVC covered wire and 75 ohm twin feeder attached.



Removable end support method for wire dipole using a plastic antenna insulator, snap-hook and Dacron rope.



Photo showing how the wooden support posts are held in the ground by the steel Met Post.
This Met Post and wooden pole now supports the 7 metre high fibreglass Sota Pole (fishing pole).

The 'deformed dipole'.

A Dipole for 20m and 10m.

One leg is vertical, giving a more omnidirectional pattern and supported by the 7 metre long fibreglass fishing pole, while the other leg runs off horizontally at about 2 metres above the ground.

This antenna is fed by 75 ohm twin feeder.

The Deformed Dipole

Compact Antenna for Top Band

A Shortened Inverted L for 160 Metres

Despite the dreadful noise on top band caused by modern electronic gadgets and the difficulty in accommodating a necessarily large aerial in a small garden, I was keen to try to get on to top band. I experimented with some different ideas during 2009, some of which are shown on this page.

Eventually I settled on the design shown below. It is an Inverted L type aerial, shortened by the use of a loading coil. It uses a fibreglass telescopic fishing pole to allow it to be easily lowered out of sight when not in use. Read more on Antennas page 2 here>


Pulley
Egg insulator
Aluminium pole
Aerial wire
12m
Telescopic fibreglass fishing pole - 6m high fixed to wooden post
Inductor
Pulley
1m
5.5m
Counterpoise ground radials
Connection box
Fence
Halyard
Coax to shack
Wooden post
Earth rod
Top Band Aerial by MØMTJ

Shortened Base Loaded Top Band Antenna For Small Gardens
uses a fibreglass telescopic fishing pole to allow it to be easily lowered out of sight when not in use.

Read more about Top Band Antennas on Antennas page 2 >

Other Antennas:

End Fed Zepp Antennas for 20m / 17m and 15m :

High quality commercially built Zepp antenna from G Whip Antenna Products.
http://www.gwhip.co.uk/

Above is a high efficiency, high quality commercially built Zepp style antenna using a half wave radiator. However there is a difference - unlike the traditional Zepp antennas, G4ICD's design dispenses with the long trailing 1/4 wave twin feeder matching section and counterpoise and, instead, uses a G-Whip's helical tuned unit.

The end fed Zepp is extremely versatile - it can simply be hung from the fascia board or guttering just outside one's window: The 1/2 wave wire radiator made of high strength Kevlar is easily sloped down the garden and is a camouflage green in colour so as to be almost invisible. The G-Whip Zepp is supplied with a fascia board insulator, a throwing line with plus cable strain relief and fittings, the IP65 waterproof resin potted box fitted with UHF connectors (SO239) for coax feeder. The Zepp can be mounted vertically (e.g. using a telescopic fibreglass pole), horizontally or sloping and can be ready in a matter of minutes.

I then decided to try an excellent new design developed by Geoff G4ICD - an End Fed Zepp antenna with a difference. The G-Whip End Fed Zepps are high efficiency, resonant mono band antennas utilising a half wave radiator, however this new G-Whip design by G4ICD dispenses with the long trailing 1/4 wave twin feeder matching section and counterpoise and, instead, uses a helical tuned unit. Using versions for 20m, 17m and 15m will enable me to get on the air with the minimum of fuss since the G-Whip end fed Zepp can simply be hung from the facia board or guttering just outside one's window. The high-strength Kevlar, camouflage green 1/2 wave wire radiator is easily sloped down the garden to be almost invisible.

G-Whip Widebander :



GWhip Widebander antenna.

Using the popular idea of feeding a large but non resonant antenna with an impedance converting 9:1 unun.

The G Whip wideband antenna consists of a 9:1 unun of GWhip's customary high quality for best efficiency, two 20metre lengths of kevlar wire for the radiator and counterpoise which provide operation from 3.6MHz to 50MHz. Feed with good quality low loss coax and use an ATU to match. The 20 metre radiator wire can be used as a sloper, or supported by convenient supports such as poles or trees in a straight line or 'dog legged'. I use a shorter radiator wire run up a telescopic fibreglass pole for operation on 20 metres an above.

Dual Band J-Pole :

There is a dual band vertical J-Pole antenna in the loft as a back up for the 2m and 70cm bands.

DUAL BAND SLIM JIM
BY N9TAX 2M-70CM

The excellent Dual Band N9TAX Slim Jim antenna that I use in the loft as a reserve antenna.
More information from Joe N9TAX at: www.n9tax.com
www.ebay.co.uk/itm/VHF-UHF-Slim-Jim-J-Pole-Dual-Band-2m-70cm-Antenna-jpole

Previous Antenna installations:

(2011 - 2013)

1) A trapped Inverted L for 80m and 40m with an SGC-230 auto antenna coupler at its feed-point at the bottom of the garden. RG213 coaxial cable is used to feed the output of the auto-coupler back to the shack. This can be used on all bands from 160 through to 10 metres. The support post is installed at the bottom of the garden with the end of the antenna wire being supported by Dacron rope that is attached to a pulley on a pole at the apex of the roof. A simple, single sloping wire element provides use on the 17 metre band. Although too short to be really effective on 160 metres, Top Band can be tuned by the SGC coupler. A pretty good all-round antenna. more

2) A half wave Wire J-Pole fixed to a telescopic fibreglass fishing pole for 10m. Cheap and effective. more about J-Poles

3) A 'home-brew' omnidirectional, vertical dual band, end fed antenna for 2 metres and 70cm. This is of the Controlled Feeder Radiation design (CFR) by VK2ZOI; effectively an end fed half wave dipole on 2m with an aluminium sleeve to achieve 70cms with a few extra dB's of gain. It is mounted on an aluminium mast 10 metres a.g.l. more

4) A DK7ZB design dual band Yagi antenna, with 5 elements for 2 metres and 8 elements for 70cms, mounted horizontally for SSB. A lightweight antenna rotator is employed and uses a push-up telescopic mast. Height above ground level is again approximately 7 metres. The DK7ZB is an excellent twin band Yagi antenna. more

5) Dual Band Fan Dipole, made from thick loudspeaker wire, mounted horizontally in the loft space for 10 meters an 6 metres. Cheap & effective.

6) (Installed late September 2013) Wire J-Pole antenna for 4 Metres (70 MHz) supported on a 3 metre long telescopic fibreglass pole to be attached to the top of the aluminium push up mast that supports the DK7ZB dual band yagi and rotator,

Other Options that can be deployed on an 'as required basis':

7) Compact Loaded Top Band Antenna, based on a design idea by Stuart Craigen G4GTX more

8 & 9) G Whip End Fed Zepps (EFZ's) for either 20m, 15m or 17m or the G-Whip "WideBander" which is an 'UnTenna' style antenna that can be used for 20m through to 10m using good quality G Whip 9:1 UnUn; useful additions for antenna flexibility. more

10) N9TAX Dual Band Slim Jim (J-Pole) antenna mounted in the loft as a back-up antenna for 2m and 70cms. Very good. more

11) Delta Loop Antenna - 16 metre loop of wire in triangular Delta shape, hung from the top of the pole supporting the inverted L antenna and fed via RG213 coaxial cable via a 4:1 balun. The loop is really a single band antenna cut for one wavelength on the band of interest, however it also can be pressed into service for some higher bands - a good, cheap and easy to install aerial; Often works better than the inverted L on the higher bands, but on 10 metres the tuned 10 metre dipole in the loft is sometimes better. more

(2011)

In mid 2011 I experimented with an excellent N9TAX designed dual band Slim-Jim (J-Pole) antenna for 2m and 70cms. This is made from lightweight 450 Ohm ladder line which can be fixed to the top of a 10m tall fibreglass, telescopic, fishing pole. The N9TAX works extremely well indeed. More information from Joe N9TAX at: www.n9tax.com and buy at: www.ebay.co.uk/itm/VHF-UHF-Slim-Jim-J-Pole-Dual-Band-2m-70cm-Antenna-jpole

N.B. I tried to home-brew the DJB-1 dual band J-Pole antenna using plans published by the ARRL in QST magazine. I wanted a neat antenna that could be enclosed in a protective tube to minimise weathering effects. However trying to tune this antenna at UHF frequencies proved to be frustratingly difficult to do and after two full days work I could not get the thing resonate accurately at the correct frequency. Sadly, for this reason, I cannot recommend the Dual Band J-Pole as a home-brew project.

The N9TAX antenna on the other hand works very well. However it cannot be enclosed in a tube due to the velocity factor effect de-tuning the antenna's resonant frequencies.

(Late 2011)

Due to difficulties with the stability of a lightweight fishing pole as a support I moved back to using the lightweight aluminium telescopic mast, with stays, to support a Watson W-50 vertical dual band collinear for 2 metres and 70 cms FM.

The excellent N9TAX dual band Slim Jim is now installed in the loft.

(Antennas used up until 2010)

1) A trapped Inverted L for 80m and 40m fed by RG213 coaxial cable to the LDG Z-11 Pro antenna matching unit in the shack. This can be used on all bands from 80 through to 10 metres. The support post is installed at the bottom of the garden with the end of the antenna wire being supported by Dacron rope that is attached to a pulley on a pole at the apex of the roof. This excellent antenna is still use. *more*

2) A trapped dipole for 20m and 10m. This was fed by 75 ohm twin feeder to a 1:1 balun then on to the AMU via RG213 coaxial cable. It was initially installed horizontally, but more latterly installed with one leg supported vertically on a 7 metre fibreglass 'Sota' pole with the other leg supported horizontally about 2 metres above the ground. A rather unorthodox arrangement for a balanced dipole, but it seemed to work ok, it looked much neater than a horizontally slung dipole and also offered a more omnidirectional radiation pattern. *more*

4) A compact Inverted L for the 160 metre band - Top Band - shortened with a loading coil. *more*

5) As N9TAX Dual Band Slim Jim (J-Pole) antenna for 2m and 70cms. This was fixed near the top of a 10m telescopic fibreglass fishing pole that I pushed up whenever it was required. *more*

(2008)

W-2000 - Vertical Collinear mounted on a temporary 10m telescopic pole:

I no longer have the Watson W-2000 but this is how it was used previously:

The Watson W-2000 covered VHF (2 metres / 144 MHz) and UHF (70 cms / 430 MHz) and also, rather usefully, 6 metres (50 MHz) too. The W-2000 is 2.5 metres long and enclosed in white fibreglass with three radial elements at the base.

Unfortunately I had nowhere practical to install a separate mast for the VHF / UHF antenna, so this was mounted on top of a 30 foot (10 metre) high telescopic aluminium mast in the back garden. The base of the mast was placed in a handy metal sleeved hole that was already present in a small wall in the garden. Very fortunate indeed!

The antenna is connected to the radio via the very low loss Westflex 103 coaxial cable. The cable was left in place permanently, running from the shack in the front bedroom, up into the loft and out of a small hole in the back of the house, down a drain pipe into the back garden. From there the aerial can be connected as an when required:

When VHF or UHF operation is required I have to connect the coaxial cable to the Watson W-2000, fix it to the top of the telescopic mast, which is very quick using two V bolts and 4 wing nuts, put the mast in the hole and raise it to a good height. I tend to extend it so that the bottom of the antenna is at about 24 feet in the air, the height of the apex of the house, so it is in fairly clear space.

A VHF and UHF aerial needs to be as high as possible since at these frequencies communication is essentially local and 'line of sight' - unless heightened propagation conditions, such as Sporadic E or a Temperature Inversion is prevailing at the time.

Even at 24 feet the mast is rather wobbly, so it was tied down using three nylon guy ropes.



The Watson W-2000 on to of the extended telescopic pole - about 8 or 9 metres high.

Photograph of a Watson W-2000 on Telescopic Mast at the lowest position.

MORE ANTENNAS

Our good friend in Australia Felix Scerri, VK4FUQ, uses Inverted V antennas but also highly recommends the Quad Loop style antenna for HF work. These are well worth investigating, and you can read more here: Antennas 3 with more antenna ideas on Antennas 2 and Antennas 4 and the Links Page here and here

KNOTS FOR SECURING WIRE ANTENNAS

I have found the Bowline to be one of the most useful, it is strong and easy to tie. A Bowline will not slip in any circumstances and, usefully, the more load that is put on it, the tighter it gets. Read more about good knots for amateur radio aerials here...



The Bowline Knot - Read more about knots here ...

Antenna Trimming Chart and useful Antenna Rigging Accessory ideas

On Antennas 4 I have included a helpful Antenna Trimming Chart and some useful ideas for Antenna Rigging Accessories

More project ideas here>

73

Mike, M0MTJ 2011 / 2012

Antennas 2 | Antennas 3 | Antennas 4 | Antennas 5 | Antennas 6

Links to further reading:

Introducing The All Band Doublet: http://www.cebik.com/content/edu/edu6.html ***N.B. Create a free account at*** http://www.cebik.com

The All Band Doublet - http://www.cebik.com/wire/abd.html

The ALL Band HF Doublet on Ham Universe - http://www.hamuniverse.com/hfdoublet.html

Multi Band Dipoles Compared - by ARRL on QST and DX Zone:
http://www.arrl.org/tis/info/pdf/9611073.pdf http://www.dxzone.com/cgi-bin/dir/jump2.cgi?ID=7499

PDF Document - The W3DZZ Antenna -
http://www.users.icscotland.net/~len.paget/GM0ONX%20trap%20dipole.pdf (**!!! But don't use coaxial cable with a 'choke balun' at the centre of the dipole! Use twin feeder with the Choke Balun at the other end. Less power loss.!!!***)

See Practical Dipole Antennas Compared: http://www.qsl.net/ta1dx/amator/practical_dipole_antenna.htm

Practical Antenna For 160 Metres - http://www.iw5edi.com/ham-radio/?a-practical-antenna-for-160-metres,32
http://www.ik1mnj.net/id202.htm

More:

The website of GM0ONX http://www.gm0onx.co.uk/

The Inverted L - PDF document: http://www.users.icscotland.net/~len.paget/5%20band%20Inverted%20L.pdf

Adding Top Band To The Inverted L - PDF Document:
http://www.users.icscotland.net/~len.paget/Inverted%20L%20adding%20top%20band.pdf

The All Band Inverted L - http://www.antennex.com/preview/archive3/ltv.htm

Q.T.H. Move in 2010 !%*?"*!?!

We decided that we'd like to move house in 2009, we found a new property in early 2010. My amateur radio aerials were duly taken down and the ham shack packed away. However after months of delays we still had not moved by August 2010, but we were still hoping to move. However after months of messing about and stringing us along our buyer pulled out the very day before we were to exchange contracts later in August 2010.

This cost us a lot of time and a great deal of wasted money. Thank you Mrs xxxxxx :-(

After a wasted year we decided to stay where we were and take the house of the market. Instead we spent the next eight months remodelling and redecorating. No time for playing radio of course and besides everything was still all packed away in boxes!

In mid 2011 I was getting frustrated that I had no radio. So I suppose it's time to think about re-establishing the station and to start planning the installation of some antennas. Of course Jules, my XYL, understandably questions my antennas and experiments!

Due to time constraints I will probably start again with a somewhat temporary antenna. I was thinking along the lines of an "Untenna" - so I installed a 7.2 ish long wire supported on a vertical fibreglass pole with a horizontal 'counterpoise' connected via a 9:1 balun to the coax back to the shack. Of course it is a fairly low efficiency multi-band (wideband) antenna, but easy to get going quickly. The GWhip Widebander antenna by Geoff Brown G4ICD is possibly the highest quality antenna of this type available, using a very high efficiency, top quality 9:1 UnUn with a 17 meter wire radiator and 10 metre long counterpoise - a very useful, versatile 'all situations' antenna.

As time progressed I re-established my full size trapped Inverted L antenna for 80metres and 40 metres and added a switchable loading coil at its base for use on 160 meters, as described above.

Then I gradually re-established the 2 metres and 70 cms antennas with the vertical W-50 and horizontal dual band DK7ZB Yagi - as detailed above.

Antennas 2 | Antennas 3 | Antennas 4 | Antennas 5 | Antennas 6

Index To Other Antenna Pages:
Antennas 1 : Aerials used at M0MTJ
Antennas 2 : Including ..... Ideas for compact aerials for Top Band /160 metres
Antennas 3 : Felix Scerri VK4FUQ discusses Loop Antennas, baluns, masts & other antenna related topics
Antennas 4 : Including ...... Many antenna ideas from various sources particularly for multi-band operation & also gives information about
antenna trimming, knots for wire antennas and useful antenna rigging accessory ideas.
Antennas 5 : Including ..... Half Wave End Fed aerials for 144 MHz VHF / 430 MHz UHF and 50 MHz 6 Metre band & J-Pole Aerials
Antennas 6 : Including .... Simple and effective H.F. Antenna ideas - Ground Plane and All Band Doublet

G Whip Antenna Products
G-Whip Antenna Products
Geoff Brown G4ICD offers a multitude of high quality solutions for portable, mobile and permanent base installations

G-WHIP
ANTENNA
PRODUCTS
PRO

G-WHIP G Pro Whip antennas
http://www.gwhip.co.uk/

G Whip
Antenna
News
New Products.
WWW.GWHIP.CO.UK
G Whip Antenna Products

http://www.gwhip.co.uk/

Just For Fun:

A tower that we may like to have to attach our antennas to - but I don't think that Health And Safety was taken into account here:

M0MTJ | Operating Conditions | Antennas / Aerials | /P Portable Operating | Accessories | Projects & Kits

Useful Information | Contact MØMTJ | Contact M6ORS | Links to Amateur Radio Sites

RSGB | QSL | The Amateur Radio Mini Site Map

WSPR Weak Signal Propagation Reporter

News, Developments, Events, Photographs and other 'Bits 'n' Bobs'

MDS975 Home

Feedback

MAIL

Mike Smith - MDS975.co.uk © 2003 - 2016

M0MTJ

Amateur Radio; Ham Radio; Radio; Transceivers; HF; VHF; UHF; Data Modes; Morse Code; RTTY; PSK31; SSTV; FSTV; Amtor; Sitor Antennas; Aerials; Cable; Coaxial Cable; Twin Lead; Masts; Poles; Propagation; Computer; PC; USB Computer Interface; Microphone Loudspeaker; Filters; Noise Reduction; DSP; Digital Signal Processing; Morse Key; SWR ; Inverted L; Inverted V; Dipole; Doublet.

http://www.freeradio.co.uk/

MDS975 www.mds975.co.uk

ANTENNA
TUNING UNITS
(ATUs)

MDS975 www.mds975.co.uk

Home | Contact | Site Map | Links

Radio Stations & Memorabilia | Loop & Frame Aerials | Copper Tube Antenna
DXing & Short Wave | Make A Signal Meter | Riding On A Radio Wave

ATUs - ANTENNA TUNING UNITS

THE ATU

AE PEAK
LF MF HF
BAND
ATTEN.
RX PEAK
TRANSMATCH ATU MK II

An Antenna Tuning Unit

For good Short Wave reception long aerial really is required to dig those distant stations out of the ether. To effectively couple such an aerial to a radio a matching unit called an ATU (Antenna Tuning Unit) can often be extremely helpful. An ATU is relatively straightforward to construct and uses simple parts that are quite easy to obtain. The ATU shown above is of my own construction and is used with a Lowe HF-150 receiver.


EGG INSULATORS
LENGTH = 10 to 30m
TO RECEIVER
AERIAL
GROUND

Typical Aerial Installation

AERIALS [or ANTENNAS]

AERIAL n. & adj. > n. a metal rod, wire or other structure by which signals are transmitted or received as part of a radio or television transmission or receiving system. > adj. 1. by or from or involving aircraft (aerial navigation; aerial photography). > 2 a existing, moving or happening in the air. b of or in the atmosphere, atmospheric. 3 a thin as air, ethereal. b immaterial, imaginary. c of air, gaseous

For the purpose of this page we'll choose the noun, I think. So the aerial can be:

A Random Length Of Wire Strung As High As Possible
OR -
A Carefully Designed Structure Whereby The Element (Or Elements) Is (Are) Tuned To Resonate At The Required Operating Wavelength (Frequency) Of The Station Or Waveband Being Received

(What??)

The advantage of a long random wire aerial to a listener is that it is easy to install in a loft or around a garden. Many Short Wave Listeners' (SWL's) aerials consist of such a long end fed wire of a random length perhaps between 10 and 50 meters, i.e. not cut to resonate at a specific wavelength. The disadvantage is that it is not tuned to a specific wavelength and therfore may not be particularly efficient at gathering the signals from a desired station. This is because a random wire aerial system will not present an even impedance* to the input of the radio receiver. This should generally be around 50 Ohms.

[* Impedance is the resistance to the flow of an alternating current (AC) - in this case a radio wave]

The impedance of a random wire aerial could swing from a few Ohms up to several thousand Ohms depending on what frequency is being used. This will present a serious mis-match to the receiver, which would prefer to 'see' a nice constant 50 Ohm load. This mismatch of impedance between aerial and radio can detrimentally effect the amount of signal transferred from the aerial to the radio, and therfore weaken reception of stations at some wavelengths.

An Antenna Tuning Unit (ATU) can help match the impedance of the aerial to the 50 Ohm impedance required by the radio. Once the impedance of the aerial matches the impedance at the input of the radio (after being tuned by the ATU) the greater the chance of the RF energy being effectively transferred.

Using an ATU will not always improve reception. If, by pure chance, the random wire aerial presents a 50 Ohm impedance to the radio on, say, the 41 meter band then no further improvement in signal strength will be obtained. But then if the radio is tuned to the 25 meter band, for instance, the aerial may have a 500 Ohm impedance and on this band the ATU will help to transfer more signal and improve reception.

WAVELENGTHS AND FREQUENCIES

This is the mathematical formula to calculate the wavelength of a particular frequency:

$$V/F = \text{wavelength}$$

$$\text{E.G: } V/F = 300{,}000{,}000/1{,}875{,}000\text{Hz} = 300/1.875\text{MHz} = 160\text{m}$$

The velocity of a radio wave when travelling through space is the same as the spped of light

i.e. 300,000,000 meters per second (186,000 miles per second). V = Velocity, F = Frequency in Hz. The result of the calculation is the wavelength in meters.

Once the wavelength of the radio wave is known, the relationship with the length of the aerial can be determined. An aerial that is 1/4 wavelength or an odd multiple of 1/4 wavelengths e.g. 5/8th or 7/8th wavelength, the impedance presented to the receiver will be quite low. If the aerial is a full or half wavelength long then the impedance will be much higher.

LOWE, JOHN WILSON AND THE SIX BAND SAGGER

Have a little look at the bottom of the LOWE HF-150 page since it includes an interesting article by John Wilson, formerly of Lowe Electronics, about aerials, specifically the "Six Band Sagger".

ATUs AND FILTERING

The ATU acts as an Impedance Matching Transformer with the ability to accept a wide range of input impedances and match them to the 50ohms that is required by the receiver. It also has the bonus of providing an certain amount of filtering, which can help overcome receiver overloading, by letting through the required frequency while attenuating the higher and lower frequencies. There are two types of ATU circuits described further down this page, the Pi type and the T type. The T type is particularly effective as a 'high pass' filter, and is very useful for filtering out interference on Short Wave caused by high power Medium Wave transmitters that can overload a short wave radio.

The graph below shows the effect that can be acheived:



The solid line shows the filtering effect of an ATU at shortwave frequencies, while the broken line shows the filtering performance at medium wave frequencies

MAKE YOUR OWN ATU

The circuit diagram below shows the circuit for a typical Pi type ATU which seems to be a popular arrange ment for many ATUs. I have built ATUs using this Pi arrangement and although they work quite well and are certainly a useful improvement over no ATU at all, I have found in my own experience that the 'T' arrangement in the next circuit works even better, matching more easily over a wide range of frequencies and also seemingly offering improved filtering in my own circumstances.

Each aerial arrangement is different and you may find that this circuit performs best of all in your circumstances:



Pi type circuit - Very popular for many ATUs

Below is the circuit diagram for my preferred choice of a T type circuit which includes a variable attenuator and which could not be simpler to construct. This circuit, with the coil described, covers from 500kHz medium wave to 30MHz short wave. Tuning capacitor VC1 is adjusted to match the aerial side while tuning capacitor VC2 is adjusted to match the receiver side. This circuit is often referred to as a TRANSMATCH, particularly in the USA.



T type circuit, which I have found to be more effective than the Pi type at my listening post, possibly because this design acts as a 'high pass' filter, and is therefore very useful for filtering out interference to short wave reception caused by high power medium wave transmitters that can overload the short wave radio

All that is needed is:

1	**Self wound coil with 12 tapping points. See below**
1	**Reel of 22 s.w.g enamelled copper wire for coil**
1	**Coil former, eg the inside of a fax roll (30 mm diam approx)**
1	**12 way switch to select tapping pints on coil**
2	**500pF tuning capacitors (200pF or 365pF can also be used)**
1	**1 k ohm linear potentiometer for attenuator**
2	**Red terminal posts**
2	**Green terminal posts**
1	**Coaxial socket, e.g. 3.5mm jack (as used here) or SO239**
1	**Case 150 x 100 x 60 mm + with rubber feet**

See additional notes below >

SOURCES FOR TUNING CAPACITORS

Old broken radio sets - but don't smash a nice one up for the sake of a capacitor! Old radio sets, especially the old 'valved' wirelesses are very interesting and often sound superb and could be quite rare.

J BIRKETT RADIO COMPONENTS,. 25 THE STRAIT, LINCOLN, LN2 1JD. telephone (uk) 01522 520767 http://www.zyra.org.uk/birkett.htm

MAINLINE GROUP http://www.mainlinegroup.co.uk/jacksonbrothers/index.htm

COIL WINDING DETAILS

The coils that I have made for my ATUs have been wound around formers made from the plasic tube found inside a typical fax roll. This can be cut to a suitable length to fit inside the enclosure, in this case 150mm long with a 30mm diameter. If a plastic fax roll is not available then a strong cardboard tube could be used instead.

Two small holes can be drilled at each end of the tube to feed the start and finish portions of the 22 swg wire through in order to secure it. Then wind the required number of turns, putting a tight twist in the wire at each tapping point, taking care to scrape off the enamel so that the connecting wire can be soldered into place.

Alternatively, as I did in my first coil, I inserted printed circuit board (PCB) terminal pins into the tube to secure the wire to at the start and finish points of the coil and at each tapping point, as you can see in the photograph below. This involved drilling a hole in the soft plasic of the tube slightly smaller than the PCB pin and forcing the first pin in for a tight fit. The enamel must be scraped of the wire, wrapped arount the pin with a single turn and then soldered in place - quickly to avoid melting the plastc! Then the first turn of the coil is made, another hole drilled and pin inserted and wire scraped clean of enamel and soldered to the pin. Proceed until all the turns and tapping points have been made according to the diagram.

The diagram below shows the number of turns between each tapping point:



Once the coil is complete the tapping points can be wired to the 12 way switch by using short lengths of hook-up wire (e.g. 7/0.2mm pvc covered), being careful to wire the into the circuit exactly as in the diagram.

The Mk1 ATU using the T type circuit


To RADIO
AERIAL
CENTRE CONDUCTOR
3.5mm
OUT
SCREEN
GROUND
EARTH

The rear panel of the Mk1 ATU showing the aerial input and output terminal posts.
A 3.5mm jack socket is also included as an alternative output socket for convenient connection to a portable radio via a length of flexible 50 ohm coaxial cable



Internal view of the Mk 1 Antenna Tuning Unit showing the coil and its 12 tapping points, the range switch and two space-saving Jackson type solid dielectric tuning capacitors. The potentiometer that forms the variable attenuator is hidden from view by the range switch.

The Mark 2 Aerial Tuning Unit


AE PEAK
LF MF HF
BAND
ATTEN.
RX PEAK
TRANSMATCH ATU MK II

The Mark 2 Antenna Tuning Unit

The Mark 1 ATU described above was initially made using the Pi match circuit and when I made this, the Mark2, I used the T match circuit design and when I found that it worked even better I modified the Mark 1 to also use the T match circuit layout.

The Mark 1 is used for a portable radio and therefore is more compact, the Mark 2 is used for the HF-150 so can be a bit larger. It is housed in an aluminium case and uses the larger air-spaced tuning capacitors and also has SO239 sockets are fitted for the input and output.

The coil is larger too, using the same former made from the centre of a fax roll but longer at 220mm to accommodate additional windings to enable coverage of long wave frequencies. An additional switch is also included to give plenty of adjustment while including the long wave range.



The circuit diagram showing the coil and the 12 way switch to adjust the Short Wave ranges and the additional 3 way switch to change to Medium Wave and Long Wave coverage*. The attenuator is simply a 1k ohm potentiometer.
* Position 1 is Long Wave; 2 Medium Wave; 3 Short Wave ranges - adjusted with 12 way switch

Tuning Capacitors: In these circuits, as is the general rule of thumb with radio projects, the moving vanes of tuning capacitors - and therefore the spindles/shafts - are connected to the earthy side of the circuit. Ensuring that the moving vanes are connected to the earthy side minimises 'hand capacitance' effects when touching the adjustment knobs. The fixed vanes are therefore connected to the 'hot' (top) side of the circuit.

You will have to determine which terminals on your particular capacitor are connected to the fixed vanes and which are connected to the moving vanes. It should be able to determine this visually from the physical construction of your particular component, but if you are unsure always use the continuity tester function of your multimeter.

With dual gang variable capacitors with smaller values per gang, it may be desirable to connect the two fixed sets of vanes together in parallel to increase maximum capacitance. For many metal framed air-spaced variable capacitors the moving vanes will effectively be connected together via the brass spindle to the main frame of the capacitor body. The fixed vanes and their associated terminals will be isolated from the metal frame by ceramic,

paxolin, or similar, insulators.

PARTS REQUIRED

1	Self wound coil with 13 tapping points
1	Reel of 22 swg enamelled copper wire
1	Reel of 30 swg enamelled copper wire (for longwave part)
1	Coil Former **220mm** long & approx **30mm** diameter
1	12 way switch
1	3 way switch
2	500pF tuning capacitors (200pF or 365pF can also be used)
1	1 k ohm linear potentiometer
2	Red Terminal posts
2	Green terminal posts
2	SO239 sockets
1	Aluminium case 220 x 130 x 65 mm + rubber feet

See additional notes below >

SOURCES FOR TUNING CAPACITORS

Old broken radio sets - but don't smash a nice one up for the sake of a capacitor! Old radio sets, especially the old 'valved' wirelesses are very interesting and often sound superb and could be quite rare.

J BIRKETT RADIO COMPONENTS,. 25 THE STRAIT, LINCOLN, LN2 1JD. telephone (uk) 01522 520767 http://www.zyra.org.uk/birkett.htm

MAINLINE GROUP http://www.mainlinegroup.co.uk/jacksonbrothers/index.htm]

COIL WINDING DETAILS

The coil is essentially the same as the coil described above being wound on the centre of a fax roll or any similar former approximately 30mm in diameter, but slightly longer at 220 mm long. In this case I secured the start and the finish of the windings by simply looping the 22 swg enamelled copper wire through two small holes at each ends of the former to secure it in place. The taps are formed by simply twisting the wire into a loop at each specified interval, to form the connection points to the range switch, making sure that all the enamel is scaped off so that the connecting wires to the switches can be properly soldered in place.

One difference with this coil is that it is designed to cover the Long Wave band too, and the final 110 turns are wound from slightly thinner 30 swg enamelled copper wire, this was done simply to save space. Inside the tube at this end are placed a couple of short lengths of ferrite rod, no longer than 50mm. These are then adjusted, once the ATU is functioning, to give the required tuning range. Alternatively more windings could be added to the final winding to increase its inductance until the desired range is achieved.


110
65
30
20
10
5
5
4
4
3
2
2
1
1
GROUND
TUNING CAPACITORS

Diagram showing the number of turns between each tapping point


1
1
2
2
3
4
4
5
5
10
20
30
65
110

Detail of tapping point intervals and how the coil is wired into the circuit

ANTENNA
EARTH
RX

Detail of tapping point intervals and how the coil is wired into the circuit

The rear panel. On the left the input terminal posts for the aerial and earth wires, with the addition of a SO239 socket for the connection of coaxial cable. On the right the SO239 coaxial output socket for connection to a radio with a coaxial input socket also provided are the alternative terminal posts for single wire output and ground connections to the radio.



Photo showing the relatively straightforward internal construction of an ATU.
2 large air-spaced tuning capacitors, range switches, potentiometer, and coil with 14 tapping points.



Photo showing how two 2 inch lengths of ferrite rod are put inside the coil at the longwave end of the coil to provide coverage of these low frequencies

ADDITIONAL NOTES:

Thank you to Dr Paul S Crawford who e-mailed us with this additional useful advice:

"You have basically have a capacitor input system connected to the antenna, my own preferance is always to put a 100K Ohm 'bleeder' resistor to GND on such an input just to stop any static build up on hot dry days, etc. Of course, you might also want to include a neon lamp across the input as a crude (but cheap) induced lightening surge arrestor as well.

Regards,
Paul "

Thanks Paul for taking the trouble to get in touch. The lightning arrestor is certainly an excellent safety feature, and if you are troubled with noise caused by a build up of static on the aerial wire, then the 100k resistor is a good tip.

A Question About The Daiwa CL-22 antenna coupler

Dear Sir, I hope you can answer a few questions for me, if you can help me, it will be gratefully appreciated, firstly i am 11 years old, and have just started SWL listening with a DX 394 radio, been using a end fed long wire about 25m long into back of radio.

Recently bought a Daiwa cl-22 coupler(atu) at a car boot sale for £3, it looks in mint condition, but didn't come with any operating instructions, and scoured the internet for some with no effect.
the ATU, has 3 controls on the front..... one marked Receiver, one marked Antenna, both theses are variable controls, and one marked band (A to G), i understand the Band control, also the Antenna control, what is mystifying me, is the variable control marked Receiver ?.

Also on the rear of ATU is 4 screw terminals, grouped in pairs, one marked Receiver, and the other marked Antenna, the Antenna screw terminals are coloured ,one black and one red, and the same for the Receiver terminals, they are very small screw terminals, looks like they only for very thin wire, my question is how do i connect my long wire to the ATU, and to which terminal?

I really hope you can help me with this, as your web site seems to be the only one, on the internet, which seems to want to help anyone like myself, looking forward to hearing your reply.

Thanking you, Ashley Griffiths. May 2012

Hi Ashley, I am not familiar with this particular unit, but most antenna matching units are similar in operation. One pair of terminals on the rear will be used to connect to the antenna and the other pair to the receiver.

Use RG58 coaxial cable to connect between the a.m.u. and receiver. The red to the centre conductor of the RG58 coaxial cable and the other terminal to the outer shield. Some antennas use coaxial cable to feed to the receiver or a.m.u., but in your case you are using a single random wire as an aerial, so simply connect this to the red terminal.

Often connecting the other (ground / GND) terminal to an earth / grounding stake driven in to soft damp soil outside can help reception. Possibly reducing interference or increasing signal strength. It's worth trying, but it does not always help in every case. I don't know without seeing the physical circuit what the actual circuit topography will be. It could be what is known as a "T" match or perhaps a
"Pi" match. Nevertheless the controls on your a.m.u. will perform the same functions and will likely be as described below.

All three controls will tend to interact with each other. The band control is most likely to be a multi-way switch that selects tapping points on an inductor (coil). This sets the general band of operation - usually from around 3MHz at the longer wavelength end of the short wave (H.F.) bands up to around 30MHz at the shortest wavelengths of the short wave (H.F.) band.

'A' will correspond to one end of the HF band (maybe the shortest wave / highest frequency end) and 'G' the other end (maybe the longest wave / lowest frequency end) - or the other way around. You will determine this by experimentation. The other two controls will normally be variable capacitors. One of these will be on the antenna side of the circuit, while the other will be in the output (receiver) side of the matching circuit.

All the controls have to be adjusted to provide the best impedance match between the receiver which always requires a 50 Ohm antenna impedance and the antenna which will present a complex and varying impedance of just several ohms to (perhaps) many hundreds of Ohms dependent on frequency being used.

For example if you want to listen to a radio station in the 31 metre band and your particular random wire antenna presents 50 Ohms to the receiver's antenna input socket then conditions are well matched and you will not need to use the matching unit, indeed it may have little or no effect and may even induces losses that actually weaken reception!

However if on the 31 metre band your random wire antenna presents an impedance (resistance to an alternating current) of several hundred Ohms or more, or a lot less than 50 Ohms then matching will be poor and some of the signal will be lost. This is when the matching unit can help. By adjusting the controls correctly better impedance matching can be achieved so that more of the signal is ransferred from the random antenna to the radio receiver.

Each band will be different and will need different amounts of matching. You will need to experiment with the controls and determine the best position of all three that produces the highest signal strength. Make a note of their positions for each HF band on a paper chart so that you can easily and quickly set the correct positions in the future as you hop from band to band on the receiver.

I think that's as much as I can tell you without knowing or seeing the actual a.m.u., but these basic principles are the same for any a.m.u. - I hope that helps!

73
Mike
M0MTJ

Hi Mike, Thanks for sharing your expertise and experience!

I am an American living in Mexico and want to use a longwire antenna of about 130 feet for shortwave listening. Am thinking to bring the signal into the house with a 9:1 unun and RG8x coax, then fine tune with your ATU MK II into my Yaesu FT-847.

I don't understand the use of the two ferrite rods.... do they simply enhance the effect of the wiring in the fax tube or do the rods have wires wound around them as well? For the alternative of more windings around the fax tube (I assume that eliminates the need for the rods), about how many more windings?

If I cant find a fax paper tube (30 mm = 1.1811 inches) can I use pvc plumbing pipe that is either 3/4 nominal =1.050 inch outer diameter or 1 inch nominal = 1.315 inch outer diameter?

I cant find 500 pf tuning capacitors so will use 365pf instead...do you know which frequencies I will not be able to tune as a result?

I understand the longwire is directional, pointing toward the far end. Will it likely cover at least 22.5 degrees to each side of its direction?

Is a plastic enclosure just as good as metal, or is shielding an issue? Your photo seems to be of a plastic box, and I can source a plastic enclosure locally.

I wish I could find people like you here where I live in Mexico to share ideas, and passion for whatever hobby it might be, SWL, amateur radio, and so forth.

My great grandparents are British but I haven't visited your country, but will someday. I am envious because you have so many enthusiasts for many interesting activities in your country. I even have the idea that all your countrymen have amazing gardens in their backyards...

When I know what to order so can start to collect the parts...

Thank you Mike, Ransom Peek in Patzcuaro, Michoacan Mexico. (November 2014)

Hi Ransom,

Thanks for your email, it's nice to hear from you.

Using a 'long wire' (I prefer to use the term 'random wire') antenna fed via a 9:1 UnUn is a popular antenna to use at present. It's certainly not the ideal antenna for all circumstances, but as a compromise 'all around' antenna it is probably a pretty good choice.

The two ferrite rods are plain - no additional windings. I simply used them to increase the inductance of that section of the coil windings, therefore allowing use on the lower frequency bands. Their size and position within the tube will dictate the actual frequency range of that section. So - nothing critical, but you may need to experiment a little.

The same applies to the tube. The size is not critical, but it will effect the inductance and hence the frequencies that are covered. Anything (card / paper / PVC) of about 25 to 30 mm (i.e. about 1 inch) will be fine - but again you may need to experiment with the final tapping positions to ensure that your obtain the frequency coverage that you require. I cannot give you absolutes - but the rule is; the larger the diameter of the coil the higher the inductance and hence the lower the frequency - similarly the greater the number of turns on the coil the higher the inductance and hence the lower the frequency - and obviously the converse is true.

365pF cap's are fine and are, in fact, commonly used in ATU's. Naturally the frequency coverage will be a bit different using smaller value cap's, but this can likely be compensated for by adjusting the tapping points if necessary. Lower value cap's may need a few more turns on the coil to compensate.

A straight wire will have some directionality, but depending on the frequency of operation, the pattern will tend to break up into lobes causing some nulls in certain directions. As a rule of thumb, however, the deepest nulls will tend to be off the ends of the wire, while the greatest signal pick up will broadside to the wire.

Please also note that this is a receiving ATU, it has not been rated for transmitting, although it might be ok QRP operation (i.e. < 5watts).

If you have not already done so - just try the 9:1 fed antenna straight into the radio. It may be fine for your swl needs as it is. Then, if you feel that you need a bit of impedance matching, you could try making the ATU. Of course - there can be endless experiments with antennas!

A plastic case should be fine for a receiving ATU.

It is interesting to learn that your great grandparents were from the UK!

As for back gardens here - well they can be of all shapes and sizes, or, indeed, non existent!

Our garden is quite small - but the gardens of many older (1930's) suburban houses could be 100 feet long, or much more. The back gardens of newer houses tend to be very compact - even for larger houses - due to the VERY high cost of land nowadays. Small gardens are called "Postage Stamp" gardens. Of course, many people live in flats and apartments, some of which have shared/communal gardens, and some have no gardens at all. The radio enthusiast therefore has to devise all sorts of compact or 'stealthy' methods of installing an antenna! Maybe a wire aerial supported on a fibreglass fishing pole fixed to the balcony, perhaps.

I hope that helps! Good luck with your projects.

73
Mike
M0MTJ

More about Components / Aerials / UnUns and Baluns

Simplification: If do not need cover the long wave or medium wave bands then you can omit those windings. This will make construction and wiring simpler.

Variable Capacitors: The variable capacitors can be anything over 200pF in value - just bear in mind that smaller values will not give as much adjustment range as larger values. Using a smaller value capacitor, such as 200pF, should not be a problem but it may require some experimentation with different tapping spacings, or perhaps using a greater number of tapping points, to obtain the required band coverage.

The use the miniature polyvaricon cap's which have a value of around 200pF will help keep costs low and will work perfectly well in receiving ATU's. You might also find these in old junk pocket transistor radios that can be salvaged for these sorts of projects.

Aerials and Feeder arrangements:

This will be a case of experimentation to find what provides the best reception - whether that be best signal strengths from stations of most interest, or lowest noise - i.e. best Signal to Noise ratio (S/N).

Try a 'long wire' aerial to begin with. Actually the expression 'Random Wire' is a more accurate and better terminology. Connect the aerial wire directly to the ATU. This may give good signal strengths but may also be noisy.

If you are troubled with noise:

Try connecting coaxial antenna cable to the ATU with shield to the ground terminal and centre conductor to input terminal. Take the coax to the outside the house and connect the the inner conductor to the random ('long') wire aerial. This may lower noise - or may just lower signal strength! It is important to attempt to judge whether the Signal to Noise ratio has improved. It might be found that actual strengths have been lowered, but that the noise level may have reduced by a greater extent, so as long as the signals are still resovable the overall noise should be lower.

Further experiments: Experiment with connecting the far end of the coax inner conductor to the random aerial wire but also connect the shield of the coax to an earth stake in the back yard or garden. This will change the aerial system - possibly reducing local noise pick up - possibly not!

Also experiment with a matching transformer at the far end of the coax. The use of an UNbalanced to UNbalanced transformer would be the most appropriate for this purpose - so try winding a simple 4:1 ratio UNUN or perhaps try a 9:1 UNUN which may work even better.

There are numerous UNUN designs on the web often using a toroid core, while some designs also use a 10mm ferrite rod. The wire used to make the windings might be enamelled copper wire or even p.v.c. covered wire. Either method would be good for these experiments. Here are some links for constructing UnUns and BalUns:

UnUn designs

M0UKD - 9:1 Unun (so-called magnetic longwire balun):
http://www.m0ukd.com/Magnetic_Long_Wire_UnUn/index.php

How To Build an UNUN by G7LRR:
http://www.pcsystems-ss.co.uk/g7lrrweb/index.php?module=pagemaster&PAGE_user_op=view_page&PAGE_id=52&MMN_position=77:37

IW7EHC - Unun Design for Longwire antennas:
http://iw7ehc.altervista.org/ununEN.htm

Balun designs

Build An Air Wound 1:1 Choke Balun For HF: http://www.hamuniverse.com/balun.html

1:1 Balun for balanced dipole aerials : http://www.m0ukd.com/1to1_HF_Balun_for_dipole/index.php
http://warga11mc.blogspot.com/2010/07/balun-11-14.html

Cost Effective 1:1 Current Mode Balun:
http://www.arising.com.au/people/Holland/Ralph/cmbalun.htm

Inexpensive 1:1 Balun: http://oz1jux.dk/balun.htm

Build a 1:1 Coaxial Balun: http://www.iw5edi.com/ham-radio/?a-1-1-coaxial-balun,41

Broadband Balun Design: http://www.qsl.net/ta1dx/amator/broadband_baluns.htm

Step-By-Step Construction of a 4:1 Current-Type (Guanella) Balun:
www.n0ss.net/qrp_4-1_guanella-type_balun.pdf

Making Baluns 1:1 and 4:1 Baluns - Swindon and District Amateur Radio Club:
http://www.sdarc.net/wp-content/uploads/pdfs/Making_Baluns.pdf

Air Wound 4:1 balun: http://www.combotec.com/projects/balun14/balun14.html

Home brew a 4:1 balun: http://www.rason.org/Projects/balun/balun.htm

4:1 balun for 160 to 10 meters by Clay Wynn: http://www.hard-core-dx.com/nordicdx/antenna/feed/4_1balun.html

4:1 and 1:1 Balun ideas by PD7BZ
http://www.pd7bz.com/radioprogs/manuals/balun_transformer.htm

Balun Winding: http://users.catchnet.com.au/~rjandusimports/balun_winding.html

4:1 and 1:1 Balun construction by M0SCG: http://www.m0scg.org.uk/Projects/?p=207

QRP 4:1 Balun for 160 to 10m : http://www.dxzone.com/cgi-bin/dir/jump2.cgi?ID=16753

UK Source for Silver Plated PTFE (Teflon) covered wire for winding higher power baluns:
http://wires.co.uk/acatalog/ptfe_covered.html
14awg / 16 swg or 0.16 mm dia wire. 12awg / 14swg 0.2mm dia wire and larger toroid for higher

powers.

Balun using T200-2 toroid (17 turns of e.c.w.) or T200A-2 toroid (13 turns of e.c.w.) for 400 watt H.F. Balun.
T400-2 Toroid (14 turns of e.c.w.) for 1000 watt H.F. Balun.
Amidon ferrite & powdered iron cores & ferrites: https://www.amidoncorp.com
Bytemark ferrite & powedered iron cores & ferrites: http://www.cwsbytemark.com
http://www.bytemark.com

I hope you enjoy building one of these useful devices, and enjoy even more the benefits that an ATU can bring to your listening post with minimal expense.

73
Mike
MØMTJ

Radio Stations & Memorabilia | **Loop & Frame Aerials** | **Copper Tube Antenna**

DXing & Short Wave | **Make A Signal Meter** | **Riding On A Radio Wave**

^Top Of Page

Home | Contact | Site Map | Reciprocal Links & Credits | Thank You

MDS975.co.uk © 2005 - 2015

AD8307 RF Power Meter

2010-02-01

At the latest ARNSW Homebrew Group meeting I had the opportunity to finally calibrate my AD8307-based RF power measurement head.



Mark VK2XOF brought along his power and frequency reference equipment and gave me a bunch of calibration points.

© 2000 - 2009 Alan Yates - All Rights Reserved.



Data points above 13 dBm were given using the generator out of levelling-loop calibration so the slight compression approaching 20 dBm is to be expected. The levelling off below -40 dBm however is not. I know the noise floor of the meter (dummy-load terminated) is about 500 mV DC output, -40 dBm is about 2.65 V out, suggesting wideband noise from the generator was swamping the lower level spot calibration signals.

Regardless in between the data is very consistent and lets me compute a "slope + intercept" calibration relying on the excellent linearity of the AD8307. The 0 dBm intercept is 5.09 Volts and the slope is 16.469 dB per Volt (60.7 mV per dB). Based on the 500 mV noise floor this equates to about -75.6 dBm, or about 80 dB dynamic range - as expected for an AD8307-based unit.

Frequency response wise, my use of leaded resistors means it maintains its accuracy to about 250 MHz, which is sufficient for my immediate purposes. The circuit design itself is the W7ZOI design from EMRFD, page 7.7, figure 7.13.

3 comments.

© 2000 - 2009 Alan Yates - All Rights Reserved.

Alan's Lab

me and my geeky hobbies

search

Home Twitter YouTube Calculators

Antenna Experiments are Great Teaching Aids

2008-08-20

With the QRSS beacon now working pretty well it is down to getting the antenna system in better order. My limited space gives me little chance of a full-size dipole or vertical, so loaded compact antennas have been the mainstay of my station.

© 2000 - 2009 Alan Yates - All Rights Reserved.



The Loaded Dipole

The 30 meter compact dipole is only about 5 metres long. It is currently erected sloping from the guttering to the balcony railing. Each arm has a 2 metre radiator then a ~27 uH loading coil wound on a piece of PVC pipe using 1.8 mm magnet wire, followed by a roughly 1/2 metre capacitive loading element which is rolled up at the ends to roughly tune the antenna. Fine tuning is achieved using the matching unit at the feed point.

© 2000 - 2009 Alan Yates - All Rights Reserved.

The Matching Unit

The matching unit is a conventional Z-match topology.


30 Metre Z-match AMU
6-210 pF
Coax In
6-210 pF
Binding Posts Out
16 Turns
Tap 11 Turns
6 Turns
T120-6 Core

The coil is 16 turns on a T120-6 core. The load winding is 6 turns over the main resonated winding. The coax centre feeds into the resonated winding via a 6-210 pF polyvaricon (both gangs together in parallel) at a tap 5 turns down from the "hot" side. The cold side is returned to the coax braid. Another polyvaricon is used to resonate the main winding, also using both gangs paralleled.

© 2000 - 2009 Alan Yates - All Rights Reserved.



Achieving a match is an iterative process, but quickly finds very good return losses. I typically just hang the impedance bridge off the feed point while tuning up. No explicit balun is implemented, but current balance in the dipole appears pretty good (based on fluorescent tube experiments - see below) - that said no attempt to measure braid current has been made but it doesn't seem significant.

The Vertical

As detailed previously the 3 metre aluminium radiator used for the 80 metre beacon is matched simply with a polyvaricon (120 pF gang only) varying its effective capacitance as seen by the 7.8 uH loading inductor. The inductor is wound on a piece of ~1" OD PVC conduit.

© 2000 - 2009 Alan Yates - All Rights Reserved.



Once the capacitance of the whip was tuned out it appeared as almost exactly 50 ohms resistive. This took me by surprise, I expected a much lower value. At the time I blamed excessive ground losses, but even then that didn't completely make sense as on 80 metres the loss wasn't anywhere near that bad and the increase in radiation resistance with the higher frequency couldn't explain the high feed point impedance either. It worked, so I choose to ignore the odd result... Big mistake, science 101; when your results and model disagree check both!

Antenna Interaction

While initial QRSS transmitting experiments were carried out on the dipole (the vertical matching not yet attempted), all the recent transmissions have used the vertical. The signal seems better in practice, but I was curious how much the two antennas interacted, especially after the odd feed point impedance measurements of the vertical. When I switched over to using the vertical I simply disconnected the feed line to the dipole and plugged it into the vertical in close proximity. With the Z-match still tuned-up at the feed point all seemed fine, but I got a very good lesson in electromagnetics when I checked the current distribution using a fluorescent lighting tube!

© 2000 - 2009 Alan Yates - All Rights Reserved.

Field Around Dipole Loading Coil
(5.918 Mbytes)

With the vertical energised with only 1.5 Watts from the beacon TX I could easily light the tube in proximity to both dipole antenna loading coils. Clearly the antenna was parasitically absorbing a lot of the near-field of the vertical, no doubt re-radiating it and distorting the pattern of the vertical.

Field Around the Other Loading Coil
(3.862 Mbytes)

Experiments have just begun into the nature of the interaction, but detuning the Z-match or disconnecting it reduced the antenna current to negligible levels. Unfortunately this causes the feed point resistance of the vertical at resonance to drop enormously and offer a very poor match to the feed line. Remote signal levels seen in Grabbers are inconclusive, signals seemed to improve immediately after the change, but have since dropped off and now appear much worse! Only careful experiments with switching the resonance on and off could really tell for sure if the pattern produced by the interacting antennas is "better" for some destinations or not. Experiments such as this are complicated to implement because of the interaction itself and how much it changes the feed point impedance of both antennas. For an "apples to apples" comparison the antenna configuration in use must match the TX properly, accept all its power and not change the power the TX can generate (i.e. offer the same load).

Another complication was noted, the change in return loss of the vertical caused the beacon TX internal temperature to change, resulting in a visible drift of the beacon frequency by several Hz. A similar effect was noted when a freak sleet storm detuned the antenna enormously by covering it in icy slush. This is a form of drift I didn't predict after having gone to quite a length to minimise direct load pulling. I did have second thoughts during assembly about putting the amplifier inside the same box because of its heat generation, I had hoped it would just help keep the beacon above room temperature - which in fact it does quite well - but variations in dissipation with load condition is now something else to consider. Nature is often a very inconsiderate teacher, but a completely consistent one at least. No doubt people in the space program and other mission critical engineering applications have similar battles with what is totally obvious *after* it happens.

Fixing the Vertical

With the dipole no longer significantly interacting with the vertical I measured the input resistance of the vertical + loading coil at resonance as almost exactly 16 Ohms. An L-network was designed to match this to the 50 Ohm transmission line. The series inductance of the L network is small enough (370 nH) to absorb into the existing 7.8 uH loading inductance, leaving just the 458 pF shunt capacitance to be added. A 470 pF silver mica transmitting cap was soldered across the feed point allowing an excellent return loss from 50 Ohms to be achieved.

The feed point resistance once resonated on 80 metres was 22 ohms (must recheck this value my technique and instrumentation has improved since then). With a 500 milliohm radiation resistance on 80 metres this puts the antenna efficiency at about 2.3 % or about 16 dB down on a lossless 1/4 wave vertical. A similar calculation for 30 metres where the radiation resistance is about 4 ohms gives 25% efficiency or 6 dB down. 6 dB is one S-point - the loss is fairly trivial on 30 and not a massive deal on 80 either despite what might be called woeful efficiency.

How valid is this loss figure? If we take the 16 - 4 = 12 Ohm loss resistance for 30 metres and assume half of it is from the inductor finite Q then the Q figure that would give 6 Ohms loss is only 83 (XL ~= +j500). One hopes the inductor Q is better than this... Lets assume the inductor Q is at least 150 which seems reasonable, this is a

© 2000 - 2009 Alan Yates - All Rights Reserved.

ground loss seem reasonable? The balcony railing is Stainless Steel which means it has a higher resistivity than Copper, but also a deeper skin depth as a result. Physically it isn't large enough to be a "good" ground-plane, so 10 Ohms does sound fairly reasonable IMO.

For 80 metres where the XL is 1.4 kilo-ohms we have about 10 ohms more apparent loss. An inductor Q of about 117 gives 12 ohms of loss to add to the 10 ohms of estimated ground loss (likely not the same on 80). The geometry and construction of the 80 metre loading inductor could easily see its Q in this region. Measurement of the actual inductor Qs at the frequency of operation would be instructive to get a better estimate of ground loss, but it is obvious that the antenna efficiency is likely dominated by the ground losses on 30 metres and even the best efforts to improve loading coil Q on 80 won't improve the overall system efficiency all that much.

Other Notes

Because these are narrow-band devices and matching techniques, the return-loss seen on your instruments will rapidly tell you if you have a harmonic energy problem. A good return loss peak (or null if you prefer) will be almost impossible to achieve unless the transmitter is fairly spectrally pure.

My fluorescent tube ionises more easily than an NE-2 bulb - this was surprising. However its ionisation hysteresis seems larger. This is probably predictable as it is filled with an Argon/Mercury mixture rather than Neon and the pressure is likely quite different, but an interesting observation none the less.



Ionisation Threshold Effect
(5.958 Mbytes)

The impedance of the 3 metre vertical is much lower on 30 metres than on 80, hence the Q is smaller and tuning up is easier and less touchy. Also the RF voltage produced at the same power level is smaller so Polyvaricons are quite suitable in the matching network. This also means my usual method of using an NE-2 bulb hanging off the mast clamp to tune for maximum output doesn't work. :(One of the big advantages of QRP is that you don't need insanely good components to withstand the voltages and currents associated with QRO operation, and you can't really burn yourself even from high-Z points.

Antennas aren't magic. I know that is stating the obvious, but like most Hams I think I am a little in awe of how a piece of metal the right size and shape can transduce electromagnetic energy with space. The laws of physics still apply and even your basic AC circuit theory is usable in the antenna domain. Radiation can make it seem like it is different, but if you model radiation much the same as loss (an extra resistance) it all works and makes sense. Antennas can be extremely confusing at times, and it is all too easy to omit the major radiator from your model! If experience has taught me anything about antennas (or RF in general) it is that you have to measure everything you can, confirm your assumptions and test your model. The more I work with antennas the more I am driven to build test equipment, especially impedance bridges, RF ammeters and (calibrated) field strength meters. To me this is what Ham Radio is all about, a technical hobby of life-long learning about the electromagnetic force of nature.

Leave a comment on this article.

Attachments

title	type	size
Z-Match Circuit Source	application/postscript	10.743 kbytes

© 2000 - 2009 Alan Yates - All Rights Reserved.

End-Fed Half-Wave Antenna & Tuner

2007-03-11

For the on-going 2007 ARNSW Homebrew Group Challenge work I needed a simple 80 metre antenna. As a home-unit resident the size of a full half-wave is pretty impractical, but I decided to try it so I had a base-line to compare future shortened verticals to.

While centre-fed would be the simplest to get going and probably the easiest to install in a semi-permanent manner, I went with end-feeding. I would like to have the option of using the antenna portable, where a transmission line is just something else to carry and end-feeding is probably the easiest to set-up.

I read everything I could on the subject, the ARRL antenna book is good, but I found Steve Yates AA5TB's website especially useful. Steve explains the physics of the counterpoise well, and gave me confidence that it would indeed work as I had planned without stray-RF problems.

The Tuner

A matching box was constructed, containing both a matching circuit and a resistive 50 Ohm VSWR bridge that borrows heavily from Dan Tayloe N7VE (et al). The matching inductor value was picked to resonate the available variable capacitor gang just below 80 metres at maximum capacitance. The Hi-Z side floats to make it more versatile, a simple clip lead can be used to return the counterpoise side to the coax braid, if so desired.

The final device tunes a resistive load of 3-7 kilo-Ohms from 3.2 MHz to 12.6 MHz. 40 metres is covered (and 30 metres too, but I lack a transceiver for it currently), it is unfortunate that 20 metres could not be covered as well, without switching out some of the windings. W0CH switches his inductor taps, but this also changes the impedance match too much for my taste (Note that you can compensate somewhat for a few kOhms of resistive mismatch and an undetermined amount of reactive mismatch with the tuning). His circuit is otherwise very similar to mine (and just about everyone else's who has an internal bridge).



The unit was built in a small plastic box, and it was quite a squeeze to fit the tuner and the bridge inside. The resulting unit is very small and should work fine in portable operations. The tuner can be seen running about 1 Watt CW from the challenge transmitter into a 4k7 dummy load and a neon bulb which is getting stinking hot!

© 2000 - 2009 Alan Yates - All Rights Reserved.



This gross abuse of a Neon bulb shows the voltage step-up of the tuner and proves it can feed a high impedance load fairly efficiently.

The Antenna

The radiator itself is simply a half-wave long piece of wire. I used an unzipped length of "zip cord", a full free-space half wave length (about 41.6 metres) which makes the antenna a bit reactive, but this is easily tuned out. Managing the wire while it was measured and unzipped was actually one of the more challenging parts of the project, but with the help of the XYL and the parents it took only 20 minutes or so. Black plastic egg insulators from the WICEN stand at Wyong were strung on the wire, two fixed at each end and two floating to allow various geometries for deployment. Banana plugs were added to each free end of the wire, so either might be used as a feed point.

© 2000 - 2009 Alan Yates - All Rights Reserved.

Testing

After some trial and error it was found possible to just fit the antenna's enormous length on my property. The centre was strung up at my 3rd story bedroom window and the ends sloped down to the extreme boundaries, one being the car park railing at the edge of a cliff, the other being the adjoining property's fence. The car park end was the most practical to feed from, so I took some gel-cells, a few radios and a fold-up chair down to the cliff edge and set-up there.

The antenna works much better than any I've used before. The inverted-V configuration may have something to do with this. I used the railing around the car park as a counterpoise, but it was possible to run using just the radio and its coax as a counterpoise too, by clipping the counterpoise connector to the coax socket outer with an alligator clip lead. It was very easy to tune in either way, on both 80 and 40 metres. The ARNSW morse practice beacon was full-scale on my VR-500, were normally is is barely S1 on my north-south horizontal 40 metre dipole. With a homebrew 80 metre transceiver I could hear lots of DX and local QSOs, and I listened to the WIA broadcast using my 80 metre VXO receiver for the first time at a good signal level. As the sun went down the mosquitoes got too bad to stand any longer, so packed up and went back indoors.

I had to take down the antenna, it is simply too big to leave up all the time, if I want to keep the neighbours on side anyway. The car park end is also a bit of pedestrian hazard, so this antenna will only be going up for special occasions. The experiment was otherwise a complete success, and I am very impressed with the antennas performance. I also now have good figures to shoot for with a shortened vertical.

5 comments.

© 2000 - 2009 Alan Yates - All Rights Reserved.

XHTML | CSS | CSS toggle

Alan's Lab

me and my geeky hobbies

Phantom-Powered Active Loop Receive Antenna for 30 Metres

2010-03-27

This loop antenna was built for 30 metre QRSS reception, but tunes beyond 30 metres and might be useful for general narrow-band (fix-tuned) HF work.



The Antenna

The loop is two turns of ~3 mm multi-strand hook-up wire, wound on a large (465 mm diameter) embroidery frame. The coil is centre-tapped, and referenced to "ground" at that point. A polyvaricon tunes the coil to resonance at the frequency of interest, and a push-pull JFET buffer amplifier transforms the very high impedance of the parallel resonant circuit down to something suitable for what is seen through the coax from the receiver (and also offers some power gain at the same time to offset feed-line loss). The buffer can deliver a relatively large amount of power, in excess of 0 dBm. This should offer good strong-signal handling, but I have not measured its IP3.

© 2000 - 2009 Alan Yates - All Rights Reserved.



Each J310 stands about 2.5 mA. I hand-picked a pair of well matched J310s (by Vpp and Idss), this is likely unnecessary but it can't hurt to ensure each arm has similar biasing and gain to optimise the distortion cancelling effects. The 33 Ohm resistors in the drains help eliminate any tendency for spurious oscillation. The supply current feeds into the bifilar drain loads from the decoupled "cold"-end of the output winding, using it as a choke. This seems to work well in practice, with no visible distortion asymmetry (when over-driven) from the DC bias on the magnetics. (The standing currents in the bifilar winding cancel, but those in the output secondary do not, fortunately the supply current is only about 5 mA so this should be of no consequence. As long as the transistors saturate well before our ferrite core - an FT50-43 - we are in good shape.)

© 2000 - 2009 Alan Yates - All Rights Reserved.


Active HF Receive Loop Antenna
VK2ZAY
12V
Bias-Tee
~90u
16 turns
FT37-43
100n
470n
FT50-43
12 turns bifilar
5 turns output
100n
33
J310
100
5-120p
Loop Antenna
~4u1 2 turns 465mm dia

More gain is available by bypassing the 100 Ohm source resistors. Oscillation can occur with excessive gain. You can set the gain at a higher, but stable level by adding resistance in series with the bypass capacitors.

The Bias-Tee

To feed the DC supply to the antenna at the shack-end of the coax a simple bias-tee was constructed. As the frequency of operation is only mid-HF a simplistic ferrite toroidal choke and two capacitor affair was constructed in a small die-cast box. I was confident this construction was sufficient at the frequency of operation, but curious about its performance elsewhere, as such it became one of the first test subjects for my experimental scalar network analyser.

© 2000 - 2009 Alan Yates - All Rights Reserved.



Despite having very poor "design hygiene" for high frequency response, sweeps of the bias-tee with the analyser suggest it offers acceptable performance across HF. There are some oddities in these measurements however. Fortunately they appear to be measurement equipment problems rather than excessively nasty behaviour of the device under test:

© 2000 - 2009 Alan Yates - All Rights Reserved.



Note how the measured "return-loss" exceeds the bridge directivity below 20 MHz. This is of course an illusion, caused by the small stray reactances of the bias-T conjugate matching the bridge for better than calibration reference balance. Ideally I should change the graphing software to compute error bars based on the reflection signal magnitude compared to the directivity established by Open-Short-Load calibration at the same frequency. As the directivity of the bridge exceeds 30 dB above a few MHz all the way to 60 MHz we can safely say the bias-Tee is an reasonable match over the same range displaying a return loss exceeding 20 dB the entire way.

© 2000 - 2009 Alan Yates - All Rights Reserved.



Transmission measurements similarly have some weirdness. Despite the test setup having 20 dB of attenuation in the signal path the bias-T performs the miracle of over-unity performance. Of course this is not real! Again it is just conjugate matching something in the system to make the reference calibration invalid. The variation is only a fraction of a dB so for all intents the bias-T is near-perfect across HF and into low VHF.

Lab Testing

It is rather difficult to lab test a loop antenna in a reasonable way. In particular it is extremely difficult to immerse it in a RF field of sufficiently controlled spatial uniformity and consistent amplitude with frequency to make absolute and repeatable measurements. For my initial testing a 100 mm diameter coupling loop was connected to the signal generator and loosely coupled to the antenna loop. Sufficient drive was applied to achieve a few dBm out of the loop buffer and into the power meter at peak of resonance. This allowed crude measurements of bandwidth and amplifier compression.

More detailed investigations were made by sweeping the unit with the same experimental scalar analyser used to test the bias-tee. Exact amplitude measurements made in this way are fairly meaningless, as the coupling loop is not well matched to the generator. 10 dB of padding was placed between the coupling loop and the generator but as the loop was placed almost orthogonally to the antenna loop to provide weak coupling (for Q estimation) the coupling loop does not see much of the antenna loop loss resistance.

© 2000 - 2009 Alan Yates - All Rights Reserved.



The loop tunes 7.23 MHz to 12.32 MHz with the polyvaricon used. The apparent loop Q drops with frequency, being 55.6 at 7.23 MHz, then 33.3 at 10.33 MHz and 28 at 12.32 MHz. The loop inductance is about 4.1 uH so the input impedances which match these Qs are 10 kΩ, 8.8 kΩ and 8.9 kΩ respectively. Wider sweeps show problems with the test set-up, in particular generator harmonic energy when tuned below the loop resonances. Neither sweeps have me feeling very comfortable about the quality of test set-up (or the loop construction for that matter). The HF feed-through is probably due to the unshielded housing of the buffer amplifier and stray circuit capacitances. Maybe a LPF should be added to the output to suppress these responses? A HF receiver should reject them with no dramas, but the number of hints of internal resonances and general "complexity" of the baseline above and around resonance doesn't make me too comfortable.

© 2000 - 2009 Alan Yates - All Rights Reserved.



When the amplifier is left unpowered the loop leaks through RF at a lower amplitude, and the resonance is shifted down in frequency somewhat. This is immediately apparent when you connect a receiver to the loop, even without powering it on you can peak-up the background noise level by tuning the polyvaricon. However once power is applied the loop must be retuned (up somewhat) for maximum background noise. Loop Q is degraded quite significantly in the leak-through mode, with Qs of 39.3, 17.1 and 9.1 for the test frequencies discussed above. Loop Q in general could be improved by weaker coupling to the JFET gates, some simulation could optimise the values required if the resonator usable Q was measured and the FETs well characterised. Noise figure would be compromised by resistive DC gate biasing, maybe use chokes?

© 2000 - 2009 Alan Yates - All Rights Reserved. XHTML | CSS | CSS toggle



On thing I initially found rather disturbing about this particular sweep is the 2nd harmonic peak is absent from the "off" run. The 3rd harmonic peak is 15 dB different just as the fundamental is - but the 2nd harmonic "on" signal is smaller and 15 dB down from its level is into the -41 dB "leakage floor" we appear to be observing... All was revealed when I considered that the reference level here is about -12 dBm meaning the leakage is around -53 dBm, quite likely considering the unshielded nature of the amplifier in close proximity to the coupling loop.

Field Testing

For real RX testing I lashed-up the antenna on the balcony, mounted a little above railing height, and A/B compared it against the base-loaded vertical I use for QRSS transmission. This is *not* a very fair test, as the vertical is 3 metres tall, while the loop is less than half a metre in diameter and was mounted at the base of the vertical. Also, interaction between the antennas was *not* controlled during the experiment, and experience has taught me this is critical for meaningful results.

The loop is largely limited by its aperture (cross-section). Compared to my loaded vertical it is about 6 dB down, making it ineffective for its original design purpose (improving my QRSS RX noise floor). However, unlike the omnidirectional vertical it has well defined nulls which are useful for avoiding local interference. The nulls do help dodge some noise, but unless I make it larger or mount it higher the loop is simply not as good for QRSS RX.

For comparison purposes I have built a much larger passive tuned loop antenna. The square loop is root-2 metres on a side in a diamond configuration (for mechanical simplicity) and is matched to the coax using a ferrite transformer placed near the polyvaricon that tunes the loop winding to resonance. It was not possible to fit the loop in the shack for Q-determination and hence the matching is at best an educated guess. Its Q is likely dominated by whatever the receiver input impedance reflects into the loop tank through the matching transformer. Experiments continue, comparing the three antennas for relative performance. More experience and additional test instrumentation is required before fair comparisons can be made.

2 comments.

Attachments

title	type	size

© 2000 - 2009 Alan Yates - All Rights Reserved.

Active Loop Circuit Diagram Source	application/postscript	13.671 kbytes

© 2000 - 2009 Alan Yates - All Rights Reserved.

THE ARRL

$4.00

ANTENNA ANTHOLOGY

The best
of recent QST
hf antenna articles
and theory presentations



PUBLISHED BY THE AMERICAN RADIO RELAY LEAGUE

The ARRL
Antenna Anthology

Edited by
Marian S. Anderson, WB1FSB

American Radio Relay League, Inc.
Newington, CT 06111

Copyright © 1978 by

The American Radio Relay League, Inc.

Copyright secured under the Pan-American Convention

International Copyright secured

This work is Publication No. 36 of the Radio Amateur's Library, published by the League. All rights reserved. No part of this work may be reproduced in any form except by written permission of the publisher. All rights of translation are reserved.

Printed In USA

Quedan reservados todos los derechos

Library of Congress Catalog Card Number: 78-71955

$4.00 in USA
$4.50 elsewhere

Foreword

What type of amateur antenna best suits your needs? Does the available space on your property permit the installation of an effective DX antenna? Is there a compromise antenna system that will provide acceptable results over short and long distances while being reasonable in price and modest in complexity? No doubt you have come to grips with these matters repeatedly since obtaining your amateur license. So, where does one turn to find the answers to these sometimes perplexing questions? What one pre-eminent source might one consult among all of the antenna booklets published for amateurs? Why, *QST*, naturally!

This anthology contains what the ARRL hq. staff considers the best of the *QST* antenna articles and theory presentations in recent years. The contributions of numerous amateur authors and designers are contained in this volume for your convenience. This publication was developed not only to serve as a compilation of good articles, but to reach those amateurs who do not have access to past issues of the League's official monthly journal, *QST*.

The editors of this booklet have attempted to select the types of antennas that have greatest appeal to those who like to construct their own radiators, and for the many amateurs who can't justify the expense of purchasing commercial counterparts. A book of this type contains something for everyone who enjoys building and experimenting with antennas. But, if you aren't a builder you will still enjoy the hours of interesting reading provided by these works.

We wish to extend our gratitude to those *QST* authors whose articles have been selected for publication in this volume. Their enthusiasm, ability and generosity typifies clearly what Amateur Radio is all about. Should you have some original antenna ideas of proven performance, send an article to the ARRL, describing your work. Not only may your story be published in *QST* — it might appear in a future edition of this book.

Richard L. Baldwin, W1RU
General Manager

Contents

1 Vertical Antennas
Page 7

2 Yagi Antennas
Page 41

3 Quad Antennas
Page 53

4 Miscellaneous Antenna Types
Page 76

5 Antenna Theory and Test Methods
Page 100

Index
Page 150

Chapter 1

Vertical Antennas

One of the most practical antennas for use where limited space exists is the vertical. This type of antenna is particularly useful to amateurs who live in dense urban areas where city lots are traditionally small. The same general restriction prevails for those who dwell in apartment buildings. In such locations it is often easier to go "up" with an antenna than to erect one horizontally. But the virtues of vertical antennas extend beyond the foregoing considerations: "Verticals," as they often are called, are relatively inexpensive, easy to erect and are capable of performing well for local (stateside) and DX work. A vertical antenna exhibits a low angle of radiation when worked against a good ground system. This makes it an effective DX type of antenna.

This chapter contains reprints of some popular vertical-antenna systems that have appeared in *QST* during recent years. For the most part, the presentations contained herein have been "lifted" in their entirety, thus making it unnecessary for the reader to research the original articles for additional information.

A Two-Band Vertical for the Novice

Build this inexpensive Novice antenna. It is easy to construct and is made from readily available materials.

Knowing of a Novice who had space problems, the author set out to design an antenna for him that could be used on 40 and 15 meters. His previous antenna was a horizontal "V" whose performance wasn't worth the time it took to put it up. Because of his narrow property, the angle between the two wires was only around 40 degrees, no doubt causing considerable signal cancelation. Horizontal antennas were ruled out, so the best antenna for him was a vertical.

Knowing (or caring) little about multiband trap-loaded antennas, it was decided the simplest antenna would be a quarter-wavelength vertical on 40 meters. After a little paper work, and using formulas given in *The ARRL Antenna Book*, the correct length would be 31 feet 10 inches (9.70 m) for 7.175 MHz. This length would also work as a 3/4-wavelength antenna on 15 meters, providing two-band coverage. However, a 32-foot (9.75-m) vertical antenna made roof-mounting too difficult! Mounting the vertical to the side of the house alleviated many guying and support problems.

Materials

The first concern was what to use for antenna materials. Being almost 32 feet high, the vertical would need strength, so the writer thought of steel tubing, but that was much too expensive. With conduit there aren't enough sizes offered, and that left only one more material — aluminum tubing. The latter comes in just about any size desired, and the author had no trouble in finding just what he wanted. Going to the nearest aluminum dealer, the author found his stock to be more than ample.[1]

In order to keep the cost minimal, the author decided to make the base piece from 1-inch (25-mm) diameter thin-wall tubing. Into 12 feet (3.66 m) of this was inserted a 12-foot piece of 7/8-inch (22-mm) diameter thin-wall tubing. This piece was telescoped 2 feet (0.610 m), then bolted and clamped (after the end had been slit twice by a pair of tin snips). It was necessary to use hose clamps on the tubing because the galvanized bolts didn't provide a good bond between the pieces. The top section was 13-1/2-foot (4.11-m) piece of 3/4-inch (19-mm) diameter thin-wall tubing inserted far enough into the lower piece to make the overall antenna length about 31 feet, 10 inches (9.70 m). Because of its large size, all the work must be done while the antenna is

Here is the base mount, installed on the side of the house. The two white wires coming out from the base are the radials.

---

[1] [Editor's Note: TV mast material is also well suited for verticals and comes in 10-foot (3.05-m) lengths, either steel or, preferably, aluminum.]


HOLE FOR GROMMET
HOLES FOR WOOD SCREWS, COUNTERSUNK
HOLES FOR WOOD SCREWS, COUNTERSUNK
HOLE FOR SO-239 FITTING
HOLE FOR BOLT
3" (76mm)
HOLES FOR BOLTS USED TO SECURE RADIALS
4"(102mm)
1/8"(3mm) SHEET ALUM.
4"(102mm)
3"(76mm)
9" (229mm)
LARGE RUBBER GROMMET
3/4"(19mm) PINE
ANTENNA
U BOLT
SELF-TAPPING SHEET-METAL SCREW
1" (25.4mm)
CERAMIC "BEEHIVE" INSULATOR OR SIMILAR
REMAINING PORTION OF BOLT CAN BE USED TO ATTACH RADIAL WIRES

Fig. 1 — Details for making the base-mounting section of the vertical.


*
LARGE GROMMET
3" (76mm)
* THIS BRACKET SHOULD BE MADE SO THAT IT WILL HOLD THE ANTENNA AWAY FROM THE HOUSE THE SAME DISTANCE THAT IT IS AT THE BASE BRACKET.
SUPPORT BRACKET

Fig. 2 — Details for the support bracket.

lying on the ground. Then, the antenna must be disassembled and put up piece by piece. (Do not attempt to put the antenna up in one piece! While the weight isn't excessive, the tubing cannot stand the strain.)

Putting It Up

The original base bracket was made from 3/4-inch (19-mm) pine, but during the first rain the wood got wet and the bracket turned out to be a very poor insulator. So the unit was redesigned to use two pieces of 1/8-inch (3-mm) thick sheet aluminum, a large grommet, and a ceramic standoff insulator (see Fig. 1).

Assembling the two-band vertical was quite simple. First, a 4-foot (1.22-m) stake was driven into the ground about 2-1/2 feet (0.76 m), and about four or five inches (102 or 127 mm) away from the side of the house. Next, the bottom section (with the bracket attached) was slipped over the stake and tightened in place with the U bolts. Then the second section was inserted into the first, clamped and bolted in place. A support bracket was made from scrap aluminum, and a large grommet was installed on it to insulate the antenna from the brace (see Fig. 2). This assembly was then attached to the side of the house (near the gable) with wood screws. Last, the third section was forced through the grommet in the second bracket, and was then inserted into the second piece and clamped. (If adjustment of resonance is desired, it is better not to bolt the final section). A suitable cap was mounted on top of the antenna to keep out moisture.

Tune Up

RG-58/U coax was then connected between the transmitter and antenna with an SWR bridge in the line, and power was applied at 7175 kHz. The SWR was found to be 3:1. This was without any ground system on the antenna. In order to obtain a better match and reduce the SWR, it was apparent that a ground system was required.

According to *The ARRL Antenna Book*, two methods of making a suitable ground system can be used. One way is to connect the coax outer shield directly to ground at the base of the antenna, via a ground rod. However, this doesn't work too well unless the soil is extremely conductive (his wasn't). The other method is to make up some sort of artificial ground in the form of radials.

The author cut a radial from some surplus wire to the same length as the vertical section, attached the radial to the base plate and the SWR dropped to 2:1. Unknown to the author at the time, *The Antenna Book* says that the radials should be 2.5 percent longer than the vertical itself, so actually, they should have been made 32-feet 7-3/4-inches (9.95-m) long. A second radial, similar to the first, was attached and the SWR dropped further (to about 1.4:1). When the soil was wet, such as after a rain or after watering, the SWR takes a nose dive to less than 1.2:1. Since the property space was limited, two radials were all that could be used. Ideally, the most perfect system would consist of a metal disk, one quarter wavelength in radius, buried a few inches below the earth's surface, but this approach is rather impractical! But if the antenna was to be erected in an area *away* from buildings, and guyed, a ground system could be made of chicken wire or other similar material. However, the more radials, the better the artificial ground. Also, they should be laid out in as nearly a spoke-like pattern as possible. Hy-Gain recommended for their AVQ series antennas that a radial system be used consisting of at least two radials for *each* band used. However, for this installation the 40-meter radials operate on their third harmonic at 15 meters, requiring but one set of wires.[2]

The length specified makes the antenna resonant at about 7175 kHz on 40 meters. On 15 meters, at the third harmonic, the antenna is resonant at about 21,425 kHz, but power was applied as low as 21,105 kHz,



The support bracket, as described in Fig. 2.

[2] [Editor's note: Actually, *any* radials, regardless of length, will help the performance of the system. Also when used on 15 meters, the antenna would be three quarter wavelengths long with low-impedance feed, approximately 50 ohms. However, the angle of radiation from the antenna will be higher than that of a quarter-wavelength vertical.]

and the SWR appeared to be only 1.4:1, well within tolerable limits. Bandwidth on both Novice bands was essentially flat.

Additional Information

Total cost will depend greatly on the individual's ability to scrounge parts. If the builder prefers to purchase the principal materials, this list will be useful.

3 — pieces thin-wall aluminum tubing, 1- (25-mm), 7/8- (22-mm), and 3/4-inch (19-mm) diameters. 12 (3.66 m), 12 (3.66 m) and 13-1/2 feet (4.11 m) long, respectively.

2 — U bolts.

1—SO-239 connector.

The other material, including three bolts and nuts, six wood screws, two grommets, two hose clamps, wood and aluminum for brackets, ground stake, and cap will vary from no cost to a few dollars, dependent on available materials. If used or surplus tubing is available one could save a substantial amount of money.

In this instance, the top of the antenna extends about 16 feet (4.88 m) above the peak of the roof, but because of the bracing no guy wires were necessary. If the antenna is to be erected in a high-wind area, guys made from nonconducting monofilament fishing line (or other nonconducting line) could be used.

The owner has received nothing but glowing reports so far. Running about 70 watts input, the first CQ on 40 meters raised W9SVJ in northern Indiana from Glendale, CA. His report, RST 589. On 15 meters the owner has worked ZL3JC, AX7SM and JH1EZZ, and received very good reports.

This vertical has no gain, and probably couldn't come near a Yagi or a quad in performance, but for an antenna costing less than $10 it does one heck of an FB job. This material was originally presented in *QST* by Jerry Arnold, WA6MBP.

Build This Novice Four-Band Vertical

Putting your first amateur station together can be an expensive proposition. One way to cut costs is to keep the antenna simple. Here's how to shave the price and provide four-band operation.

Is operation with one antenna acceptable if it covers the 80-, 40-, 15- and 10-meter bands? For a new Novice that's a reasonable approach. The author's backyard is smaller than that of most urban homes, so full-size dipole or inverted-V antennas were out of the question. Not owning a tower (yet!), it seemed that a ground-mounted vertical antenna would be worth trying.

After reading *The ARRL Antenna Book*, it was decided that a ground-mounted vertical antenna would be easiest to build. Some radial wires could be buried, and the metal fence which encloses the backyard could also be hooked up to enlarge the ground system. The author preferred this type of antenna to one installed above ground, because radials of specific lengths for each of the four bands would have been needed for a roof-mounted, groundplane type of vertical. The buried wires for the ground-mounted antenna could be any convenient length, as long as the available space would permit. From what was read about these antennas, the author believed that reasonable performance could be had even if the ground radials weren't numerous and long, although generally the more, the better.

With the help of W1FB some used aluminum tubing was purchased that would telescope together and give the author a 25-foot (7.62-meter) antenna. The wall thickness of the tubing is 0.058 inch (1.5 mm). Three 10-foot (3.05 m) sections are used. The largest diameter is 1 inch (25 mm). The center telescoping section has a diameter of 7/8 inch (22 mm) and the top piece of tubing has a 3/4-inch (19-mm) diameter. This material, plus hose clamps for holding the sections together, came to $8. An old ceramic rotary switch, a coaxial connector, a feed-through bushing, and a piece of Air Dux coil stock were acquired at a flea market for an additional $3. Two medium-size, ceramic standoff insulators were donated by W1FB. He said they cost him 50 cents each at a swap session. All that remained to collect was a weatherproof box for the loading coil, some 50-ohm coaxial cable and six U bolts. The author's OM, Bob, found some used 1-1/2-inch (38-mm) steel pipe which is 7 feet (2.13 m) long. It is used as a support for the vertical.


The completed 4-band vertical antenna used at WB1FSB. The box at the base of the antenna contains a loading coil.

Constructing the Antenna

A lawn-edger tool was used to make slits in the lawn, out from the base of the antenna toward the edges of the backyard. The slits were cut to a depth of 2 inches (51 mm). A total of 10 radials were buried in the slits. Some are only 15 feet (4.57 m) in length, while others are 25 feet (7.62 m) long. The metal yard fence was bonded together as needed, using wire jumpers between the fence sections. A single buried wire joined the fence to the common ground point at the base of the antenna.

The OM drove the steel pipe into the ground to a depth of 4 feet (1.22 m), leaving 3 feet (0.91 m) above ground for attaching the vertical antenna and weatherproof box. Construction details are shown in Fig. 3.

Although a wooden box could have been used to house the loading coil, switch and other hardware, an old electrical housing that the author's OM had in his junk box was used (Fig. 4.). It was drilled and


TO BASE OF VERTICAL
VIA FEEDTHROUGH BUSHING
40/15
10
S1
J1
L1
COAX TO RIG
80
TO BURIED RADIALS
25'
(7.62m)
HOSE CLAMP
SLIT END OF TUBING WITH HACK SAW (4 CUTS)
PLATES, 1/4 X 12 X 6-INCH (6X304X154mm)
SMALL METAL PLATE AND ONE U BOLT FOR EACH INSULATOR
STEEL PIPE
U BOLT
STANDOFF INSULATOR
METAL OR WOODEN BOX (ATTACHED TO PIPE WITH U BOLTS)
JUMPER WIRE TO VERTICAL
UNDERGROUND COAX CABLE TO RIG
FEEDTHROUGH BUSHING
BAND SWITCH
WIRE TO BURIED RADIALS

Fig. 3 — Dimensional drawing of the four-band Novice antenna. The top ends of the two lower tubing sections are slit four times each by means of a hack saw. This permits a tight joint when the hose clamp is compressed. The vertical is attached to one metal plate with U bolts. The large standoff insulators with metal feet connect this plate to a,pair of small ones. The latter are attached to the steel support pipe by means of two U bolts. The metal box is also affixed to the steel pipe with two U bolts. The band switch is a single-pole three-position ceramic wafer type. L1 can be a 5-inch (127-mm) length of B & W 3029 Miniductor, 2-1/2 inches (64 mm) in diameter, 6 turns per inch of no. 12 wire. See text for alternative mounting methods.



Fig. 4 — Closeup view of the base of the vertical. The aluminum tubing is affixed to a metal plate. The latter is attached to the iron support pipe by means of two surplus standoff insulators. Small aluminum plates are attached to the ends of the insulators to permit them to be fastened to the iron pipe by means of U bolts. The radial wires are connected to the bottom of the coil-housing box.

Fig. 5 — The author checks the SWR of the antenna during final adjustment of the system.

punched on the bottom surface to hold the feedthrough bushing, coaxial connector, switch and ground terminal for the radials.

W1FB designed the antenna, but he wasn't sure that an acceptable impedance match could be had on all four bands without a complex matching network. It was decided to try his idea, so the installation was completed.

Adjusting the Vertical

The author helped her OM install the antenna, then called W1FB for some assistance in tuning the system. He thought we could tune the vertical for 40 meters and make it work okay as a 3/4-wavelength vertical on 15 meters. For use on 80 meters it would be fairly short (63 feet or 19.20 m is the correct length for 3.7 MHz). With base loading it should offer adequate service out to a few hundred miles on 80 meters. Finally, it would operate as a 3/4-wavelength vertical on 10 meters.

A homemade SWR indicator was hooked in the coaxial line at the base of the vertical.[1] A small amount of transmitter power (5 W) was applied at 3725 kHz and the 80-meter switch lead was touched on the turns of the coil until minimum reflected power was indicated (Fig. 5). An SWR of 1:1 was obtained. The wire was then soldered in place on the coil. Next power was fed to the antenna on 7125 kHz, and the 40-meter switch lead was touched to the coil turns until an SWR of 1:1 was read. While using the same coil tap power was supplied to the antenna on 21.1 MHz and the SWR checked. It was approximately 3:1. By moving the coil tap just one turn we were able to get an SWR of 1.5:1 on 15 meters. A recheck on 40 meters followed. The SWR for that band was less than 2:1 — not a bad compromise! The coil was bypassed entirely for operation on 10 meters: an SWR of 2:1

---

[1] DeMaw, "A QRP Man's RF Power Meter," *QST*, June 1973.



Fig. 6 — Interior view of the coil housing showing the switch, feedthrough bushing, coaxial connector, and ground post for the radials. The coil shown is a piece of Air Dux stock with a tapered pitch. It was obtained at a flea market.

was indicated at 28,000 kHz. The length of the overall antenna for operation on 28,100 kHz should be 25 feet or 7.62 m (3/4-wavelength radiator). However, the switch leads inside the coil housing add to the antenna length. If an SWR of less than 2:1 is desired, break the 10-meter switch lead and insert a 100-pF air variable capacitor. The unwanted reactance can be tuned out by this means and a low SWR will result.

Opening and closing the cover of the metal box had only a minor effect on the SWR. At last an on-the-air test of the system was possible. Fig. 6 shows the interior of the coil and switch housing.

Results

Good signal reports have been received on all bands. The first QSO on 40 meters netted an RST 599 report from North Carolina and many similar reports followed on 80, 15 and 10 meters. The author feels that a WAS award is not too far away now that this antenna is in operation.

An Alternative

There are many ways you can duplicate this design using substitute materials. For example, electrical conduit with couplers between the sections should be satisfactory in place of the aluminum tubing. The entire structure could be made from 2 x 4 inch (51 x 102-mm) lumber. If that is done, the radiator could even be a 25-foot (7.62 m) piece of no. 10 wire, supported on the side of the wood with standoff insulators.

Instead of the mounting method shown in Fig. 3, the vertical pipe could probably be inserted into a 2-foot (.61-m) length of PVC tubing, then clamped to the mounting plate. This would eliminate the need for the two standoff insulators. Better still, four or five wraps of Teflon sheeting (10 mil or 0.25 mm thickness) could be placed over the bottom end of the vertical before clamping it in place on the mounting plate. Teflon can be purchased at most plastic-supply houses.

The author hopes this idea is useful to other Novices who are trying to keep the budget within reasonable limits. This writer likes the way the antenna is working. Others should have good luck with this antenna also. Oh, by the way, the ground radials are made from various scraps of wire. The size isn't important, and they can be insulated or bare. There is quite an assortment of wire types buried in the lawn! This material was originally presented in *QST* by Marian Anderson, WB1FSB.

The Cheapie GP

Keeping an ear on 10 and 15 meters? With the trend of rising solar flux, 15 meters "opens" nearly every day — 10 meters occasionally. Don't miss these openings. Build a Cheapie GP!

Looking for an antenna to cover the 10- and 15-meter bands that won't pinch your pocketbook? Should it contain easy to obtain items and be relatively simple to construct while using ordinary hand tools? Must it be physically small and not a neighborhood eyesore? If your answer to these questions is "yup," you've turned to the right page! Detailed here is a duo-band coaxial-cable-fed, trap groundplane antenna system.

A groundplane antenna consists of a vertical quarter-wavelength radiator and an artificial metallic ground system extending radially from its base. For good results the antenna should be mounted at least one-quarter wavelength above ground. This is approximately 12 feet (3.66 m) on 15 meters. At this height and higher, only four radials for each band are necessary to provide a good ground system. If this antenna was ground mounted, many more radials would be needed to reduce earth losses to an acceptable low level. The antenna has an omnidirectional horizontal or *H*-plane pattern which means radiation from the antenna is essentially the same in all horizontal directions as shown in Fig. 7A. In Fig. 7B the approximate vertical or *E*-plane pattern of the antenna is shown for the antenna mounted one-quarter wavelength above ground. As can be seen, maximum radiation occurs at the low angles above the horizontal plane of the antenna. The antenna has an overhead null so little energy is radiated at high angles. This does not detract from the usefulness of the antenna, since DX signals seldom arrive at high angles on these bands. Instead, maximum radiation is concentrated at the *lower angles* where it will be more effective. Conversely, a horizontal dipole mounted one-quarter wavelength or less above ground will have maximum radiation straight up or nearly so. Lower-angle radiation will not occur unless the dipole is raised to a height of one-half wavelength or more above ground. If it is not possible to mount your horizontal antenna a half wavelength above ground, the vertically polarized groundplane is perhaps the logical choice over a dipole. As a general rule, the higher the groundplane can be located above power lines, gutters, house wiring and the like, the better it will perform.

A Duo-Band System

For the antenna to perform properly on two bands, it must function as a *separate* groundplane vertical on each band. This requirement is met quite simply in the case of the radials since four radials are used for each band. The 10-meter radials are 8 feet, 5 inches (2.56 m) long and the 15-meter radials are 11 feet, 7 inches (3.53 m). When the antenna is operated in the 10-meter mode, the 15-meter radials have little effect on the system. Similarly, when the antenna is used on 15 meters, the 10-meter radials do not appreciably alter the operation of the antenna. The effect of the additional radials is to change slightly the feed point resistance and the resonant frequencies of the antenna.

The vertical member of the antenna must act as a quarter-wavelength radiator on both 10 and 15 meters. To accomplish this a trap is inserted in the 15-meter vertical section. Its approximate location is a



Fig. 7 — (A) Horizontal or H-plane pattern of the groundplane. (B) Approximate vertical or E-plane pattern of the antenna.



Fig. 8 — Constructional details of the duo-band antenna system.



A photograph of the base assembly. The SO-239 coaxial connector and hood can be seen in the center of the aluminum L bracket. The U bolts are TV-type antenna hardware. The plywood should be coated with varnish or similar material.



A close-up view of the trap. The leads from the coaxial-cable capacitor should be soldered directly to the pigtails of the coil. These connections should be coated with varnish after they have been secured under the hose clamps.

10-meter quarter wavelength above the base. The trap has a high impedance on 10 meters, thereby electrically divorcing the top section of the antenna when it is operated on that band. The length of the 10-meter section (section below the trap) is somewhat shorter than that of a simple 10-meter-only quarter-wavelength vertical. This is because the trap and top section of the duo-band system add top loading to the 10-meter portion of the antenna, reducing the length required for quarter-wavelength resonance. A coaxial-cable capacitor and a coil made from copper tubing form the trap which is resonant at approximately 28.150 MHz. On 15 meters the trap has a low impedance, effectively connecting together those portions of the antenna above and below the trap. The overall length of the 15-meter radiator is a bit shorter than a simple quarter-wavelength radiator would normally be for that band. This is because at 21 MHz the trap introduces inductance into the radiator — similar to the effects of a loading coil.

Construction

The vertical section of the antenna is mounted to a 3/4-inch (19-mm) thick piece of plywood board that measures 7 X 10 inches (178 mm X 254 mm). Several coats of exterior varnish or similar material will help protect the wood from inclement weather. Both the mast and the radiator are mounted to the piece of wood by means of TV U-bolt hardware. The vertical is electrically isolated from the wood with a piece of 1-inch (24-mm) diameter PVC tubing. A piece approximately 8 inches (203 mm) long is required, and it is of the schedule-80 variety. To prepare the tubing it must be slit along the entire length on one side. A hacksaw will work quite well. The PVC fits rather snugly on the aluminum tubing and will have to be "persuaded" on with the aid of a hammer. The mast is mounted directly to the wood with no insulation. An SO-239 coaxial connector and four solder lugs are mounted to an L-shaped bracket made from a piece of aluminum sheet. A short length of test probe wire, or inner conductor of RG-58/U cable, is soldered to the inner terminal of the connector. A UG-106/U connector hood is then slid over the wire and onto the coaxial connector. The hood and connector are bolted to the aluminum bracket. Two wood screws are used to secure the aluminum bracket to the plywood as shown in the drawing and photograph. The free end of the wire coming from the connector is soldered to a lug which is mounted to the bottom of the vertical radiator. Any space between the wire and where it passes through the hood is filled with GE silicone glue and seal or similar material to keep moisture out. The eight radials are soldered to the four lugs on the aluminum bracket. The two sections of the vertical member are separated by a piece of clear acrylic rod. Approximately 8 inches (203 mm) of 7/8-inch (22-mm) OD material is required. The aluminum tubing must be slit lengthwise for several inches so that the acrylic rod may be inserted. The two pieces of aluminum tubing are separated by 2-1/4 inches (57 mm).

The trap capacitor is made from RG-8/U coaxial cable and is 30.5 inches (775 mm) long. RG-8/U cable has 29.5 pF of capacitance per foot and RG-58/U has 28.5 pF per foot. RG-8/U cable is recommended over RG-58/U because of its higher breakdown-voltage characteristic. The braid should be pulled back 2-inches (51 mm) on one end of the cable, and the center conductor soldered to one end of the coil. Solder the braid to the other end of the coil. Compression-type hose clamps are placed over the capacitor/coil leads and put in position at the edges of the aluminum tubing. When tightened securely, the clamps serve a two-fold purpose — they keep the trap in contact with the vertical members and prevent the aluminum tubing from slipping off the acrylic rod. The coaxial-cable capacitor runs upward along the top section of the antenna. This is the side of the antenna to which the braid of the capacitor is connected. A cork or plastic cap should be placed in the very top of the antenna to keep moisture out.

Installation and Operation

The antenna may be mounted in position using a TV-type tripod, chimney, wall or vent mount. Alternatively, a telescoping mast or ordinary steel TV masting may be used, in which case the radials may be used as guys for the structure.

Any length of 50-ohm cable may be used to feed the antenna. The SWR at resonance should be on the order of 1.2 to 1.5:1 on both bands. The SWR is not 1 because the feedpoint resistance is something other than 50 ohms — closer to 35 or 40 ohms. Nearby metallic objects may also have an effect on the impedance of the antenna. The antenna is resonant at approximately 21.150 MHz and 28.150 MHz.

Some amateurs place too much importance on obtaining a "no reflected power" reading on their SWR indicators. Most ham transmitters will load into lines which exhibit an SWR of up to 2:1, the exception being some of the new broadband, no-tuning transmitters. To demonstrate how little effect an SWR of 1.5 or 2:1 will have on the system, consider the following: If the antenna is fed with 100 feet (30.48 m) of RG-8/U cable and if the antenna is perfectly matched to the line (an SWR of 1), the power loss along the cable will be approximately 0.98 dB on 10 meters. If the SWR on the line is increased to 1.5:1, the additional loss on the line due to the higher SWR is less than 0.1 dB. If the SWR is increased to 2:1, the additional loss over that of the matched condition will be on the order of 0.2 dB. This amount of loss is insignificant, and for this reason a complicated matching network is not necessary. This material was originally presented in *QST* by Jay Rusgrove, W1VD.

A High-Performance, 20-, 40- and 80-Meter Vertical System

Urban dwellers with small lots take heart! Here are the details for building your own DX-effective three-band mini-vertical antenna. Cost-conscious amateurs will be happy with the low cost of this system.

In another article on vertical antennas,[1] we tried to point out some fundamental characteristics of ground-mounted verticals, namely: (1) a good image plane is necessary for efficient operation, (2) a vertical over a good image plane compares favorably with a dipole at an elevation of one-half to one wavelength, (3) a short vertical compromises little in the way of performance.

This paper describes a highly efficient, three-band vertical system for 20, 40 and 80 meters, using elements of the order of an eighth wavelength. The system consists of an 80-meter vertical in parallel with a 20/40-meter trap vertical. Actually, either the 80-meter or the 20/40-meter vertical can be constructed and used alone if one is not interested in triband operation. The input impedances of both antennas are 12-1/2 ohms and they use the same 4:1 matching transformer.[2] The antennas also use the same radial system consisting of 100 radials of no. 15 aluminum wire 50 feet (15.24 m) in length (a lesser number of radials can be used as is discussed later in the article). Because of expected lower sunspot activity and, hence. poorer propagation conditions on the higher bands, the 40- and 80-meter portions of this antenna system, in particular, should prove very effective in DX communication over the next few years.

The first part of this paper deals with the design and tune-up considerations of the 80-meter element; the second part with the 20/40-meter element and the way it is used with the 80-meter vertical forming an efficient triband system. This is followed by reports on performance. Reference is also made to other alternatives for a multiband vertical system.

80-Meter Vertical

The two considerations in designing the 80-meter element of this vertical system were: (1) a good bandwidth for a reasonable height (a height one person can handle); and (2) proper spacing between the 80 and 20/40 portions such that coupling is negligible and both can be used over the same radial system.

Prior to building the shortened vertical described in this article, two others were constructed and tested on the air. One was a 22-foot (6.71 m) vertical[3] which had a 65-kHz bandwidth. The other was a trap vertical[4] with only a 20-kHz bandwidth. Both of these antennas were used separately over the same image plane of 100 radials and were efficient radiators. Therefore, the main reason in going to a slightly longer antenna was simply *to obtain a broader bandwidth.* The eighth-wavelength vertical on 40 meters from the previous work[5] promised considerable improvement by adding only a few feet. The results are shown in Figs. 9 and 10. The total height turned out to be 29 feet (8.83 m). This resulted in a bandwidth of about 140 kHz, a little more than twice the bandwidth of the 22-footer (6.71 m).

The vertical, in Fig. 9, uses a 20-foot (6.10-m) section of thick-wall aluminum tubing. (It was used some years ago as a gin pole for erecting a beam on a 40-foot (12.2 m) tower.) An 8-foot (2.44 m) extension was constructed with 1-inch (25-mm) tubing bolted in place using spacers for centering. The insulator at the bottom is phenolic tubing with a canvas base.[6] It has a 1/2-inch (13-mm) thick wall, is 9 inches



The triband vertical showing the polypropylene guys which provide an extra margin of support.



Fig. 9 — The 20-, 40- and 80-meter vertical antenna system. Tuning and construction details are given in the text.

Close-up of the base of the triband vertical antenna.

(229 mm) long and has an ID of 1 inch (25-mm). The bottom aluminum tubing supporting the antenna is 3-1/2 feet (1.06 m) long with 2-1/2 feet (0.76 m) of it placed in cement. The diameter of the hole in the ground is about 1 foot (0.31 m). Even though this construction could probably be self-supporting, three simple polypropylene guys at about the 7-foot (2.13-m) level are used for extra margin of support. The radials at the top use 1/2-inch (13-mm) aluminum tubing.[7] The base loading consists of 12-1/2 turns of a B&W 3029 coil.[8] Actually, 14 turns are on the coil. A shorting stub, as shown in the close-up picture of the base of the two antennas, is used for adjustment. To place the minimum SWR near the low end of the phone band, where much of the DX is worked, 1-1/2 turns were shorted out. The final number of turns employed depends, to some extent, on the number of radials used in the image plane. A simple check is to set the shorting tap at some convenient point, like 12 or 13 turns, and plot the SWR. If the minimum value appears too high in frequency, then add about a half a turn of coil. This half turn chould change the position of the minimum SWR value by about 50 kHz. As can be seen in Fig. 10, the minimum value of SWR is practically 1:1 and occurs at 3.840 MHz. This also verifies the input impedance value of 12-1/2 ohms, as expected from the previous work on short verticals.

20/40-Meter Vertical

In extending the operation of a vertical system over other bands, many alternatives are available. A trap vertical with a 12-1/2-ohm input impedance can be connected in parallel with the 80-meter vertical. Alternatively, the trap vertical can be designed to present an impedance of 50 ohms and thus be connected to the input side of the 4:1 transformer.[9] If broadband operation is desired on only 80 and 40 meters, then one-eighth wavelength verticals on both bands can be used.[10]

For this work, a 20/40-meter trapped vertical having an input impedance of 12-1/2 ohms was used. It offered a rather simple mechanical form of parallel operation as is shown in Fig. 9 and the close-up picture. The bandwidth on 40 meters of 155 kHz appeared acceptable. This bandwidth can be extended by about 50 percent by using the 50-ohm design of a trap vertical.

In the first attempt of parallel operation, the 20/40-meter vertical was placed only 14 inches (355 mm) away from the 80-meter vertical. The coupling appeared excessive. The 80-meter vertical was detuned by approximately 50 kHz. The 20/40-meter vertical also required excessive base loading in order to present an acceptable input impedance. By doubling the spacing between the verticals to 28 inches (711 mm), the interaction between them became negligible. The final values of heights and loadings were practically the same as if the elements were operating alone.

The adjustment of the 20/40-meter vertical is somewhat more complicated than the 80-meter vertical. An impedance bridge, as described in the *ARRL Handbook*, is of considerable help. In this case, there are two degrees of freedom: (1) varying the number of turns at the base, and (2) adjusting the lengths of the vertical sections.

Basically, the tuning is as follows: The tap is set at about 5-1/2 turns and the 20-meter section adjusted to give an acceptable value of SWR, both in position in the band and in magnitude. If the impedance is too high, it can be lowered by increasing the number of turns and lowering the height of the 20-meter section for resonance. After this, the 40-meter portion is then tuned. A plot of the SWR vs. frequency can immediately give an indication of the necessary adjustment of the section above the 20-meter trap. If the minimum value appears too low in frequency, a shortening of the top section is required. In no case should large adjustments be made. A change of a few

Table 1

Some Results With Triband Vertical

Date	*Station Contacted*	*W2FMI Signal Report*	*Freq.(MHz)*	*Input Power SSB (Peak)*	*Comments*
3/13	K5LWL/YV6	59 + 10 dB	7	2 kW	very, very strong signal, only one signal stronger — he used a Yagi at 120 feet (36.58 m)
4/3	WB5HJY	59 + 40 dB	7	2 kW	superior to anything on band
4/4	ZF1SP	59 +	14	2 kW	very, very nice signal
4/4	WA4MUR/4	59 + 40 dB	14	2 kW	best signal on whole band
4/18	KV4HW	59 + 10 dB	7	2 kW	loudest on band
5/9	K6YIY	59	4	2 kW	K1GZL and I are only ones they hear
5/9	W9LZX	59 + 30 dB	4	2 kW	strongest (very consistent signal)
5/12	W2DU	59 +	4	2 kW	tremendous signal
5/17	VK5PB	56-7	4	2 kW	remarkably strong
5/17	W4JNY	59 + 20 dB	4	2 kW	outstanding, certainly one of best
5/22	VK5PB	59 + 10 dB	7	2 kW	really amazing
5/23	ZL3RJ	57-8	4	2 kW	one of the strongest he's heard for some time — pinned the S meter
5/27	WA2BQL	59 + 30 dB	4	200 W	very potent — Stronger than most locals — couldn't believe you were using 200 W

inches has considerable effect. If the input impedance on 40 meters appears too low, then the 20-meter section has to be lengthened. This requires that the whole procedure be repeated. In any case, the initial adjustment should be started on the highest band of the trap vertical.

Results

Short verticals have been used by the author during the past year with considerable success. Many DX contacts were made on 40 meters with antennas varying in length from 6 to 33 feet (1.83 to 10.05 m). Since an extensive ground system was used, very little difference in effectiveness was noticed between the antennas.[11] This even includes redesigned trap verticals. As was stated before, the objective of the present investigation was to design a three-band vertical system which not only yielded competitive antennas on the lower bands, but one that was capable of covering a considerable portion of 80 meters. As was seen, a separate one-eighth wavelength antenna connected in parallel with a trap vertical not only gave a bandwidth on 80 meters of 140 kHz where the SWR was less than 2:1, but was short enough to not require considerable help in erection.

During all this time of operation of short verticals on 40 meters, and as of this writing, including several months on 80 meters, very few signal reports were received which did not indicate one of the best signals on the band. Table 1 gives some of the reports and comments received. In only three specific cases on 40 meters have the short verticals been bested by other antenna systems. One is shown in Table 1 where K5LWL/YV6 reported a stronger stateside signal by an amateur using a Yagi at 120 feet (36.58 m). The other cases include a comparison with W2GO of Linden, NJ. On 40 meters, VK5PB reported 6 dB and VK2WC 10 dB in favor of W2GO's signals. He was using a two-element Yagi at 60 feet (18.28 m). The elements were 44-1/2 feet (13.56 m) in length and the boom, 20 feet (6.10 m). On 80 meters, only one other station received a stronger report on direct comparison. This was by W2HCW, when comparing my signals with VK5PB. The difference was 2 to 3 S units. His antenna was an 80-meter Yagi at 120 feet (36.58 m).

Invariably, most amateurs were surprised by the performance of these verticals. In many instances, questions were asked regarding the minimum number and length of radials required for efficient operation of ground-mounted verticals. As was noted in previous articles,[12] the answer depends to some extent on the conductivity of the soil at the respective locations. Poorer soils not only require more radials, but ones that are also considerably longer. Although more experimental work is required in this area, it appears that about 50 radials, 0.2 wavelength long, should generally give good operation. The loss in this case will be approximately 1 to 2 ohms. Doubling the number to 100 radials should reduce the loss to less than 1 ohm. It should be noted that even 1 to 2 ohms of loss are appreciable with these short antennas since their radiation resistances are only 12-1/2 ohms.



Fig. 10 — Standing wave ratio vs. frequency for the 20-, 40-, and 80-meter vertical antenna system.

Again, the author would like to acknowledge the help, encouragement, and interest shown by the many amateurs during our experimental studies on verticals. Very few antenna laboratories can boast of a greater number of willing and competent field stations. In particular, we would like to thank Al Jones, W2GO, for his considerable help in obtaining comparative reports in Australia and New Zealand. This material was originally presented in *QST* by J. Sevick, W2FMI.

References

[1] Sevick, "The W2FMI Ground-Mounted Short Vertical," *QST*, March 1973. Also appears elsewhere in this chapter.

[2] Sevick, "The W2FMI 20-Meter Vertical Beam," *QST*, June 1972.

[3] See footnote 1.

[4] Commercial unit.

[5] See footnote 1.

[6] Cadillac Plastic and Chemical Co., P. O. Box 810, Detroit, MI 48232

[7] Construction details on the top hat are also given in the reference in footnote 1.

[8] 2-1/2-inch (64-mm) diameter, 6 tpi, no. 12 wire.

[9] The characterization and design of these trap verticals will be published later.

[10] See footnote 1 for details on the 40-meter vertical.

[11] See footnote 1.

[12] See footnote 1.

A Multiband Vertical Radiator

An efficient multiband radiator with no traps and no loading coils? Impossible; you can't build one without them and have it work! "Oh, yes, sure you can." I doubt it. "You wanna bet? Come on, I'll show you."

What would you say if the author told you this vertical antenna system was 89-percent efficient but had only six radials? (Efficiency is defined as the ratio of radiated power to total power delivered to the antenna.) No, it's no joke. The vertical antenna that is described here is designed to work against ground systems that are less than optimum.

By increasing the radiation resistance by about 200 ohms, we have been able to improve the effectiveness substantially of a vertical radiator with a poor ground system. The value of 200 ohms was selected as the feed-point radiation resistance because a toroid autotransformer with a 1:4 ratio will match 50-ohm coax line very nicely. An added bonus when using such an arrangement is the Faraday screen effect that reduces noise pickup from being transferred to the feed line. The noise reduction over a conventional network was determined to be about 6 dB. See Figs. 11 and 12.

The system is based on a 135-degree antenna height. The radiation resistance at the base of the structure is about 200 ohms,[1] ideal for our matching system. And at the same time the radiation pattern retains a reasonable form. The 10-meter groundplane on top of the structure acts as a top hat. On 7 MHz the phase loops cause the antenna to look like a fat radiator and between the two, top hat and phase loops, the electrical height of the antenna is raised to within the tuning range of the toriodal loading network. On 14 and 21 MHz the phase loops keep the instantaneous current on the structure in phase and eliminate high-angle lobes. When the system is switched to operate on 28 MHz, the groundplane at the top of the structure is fed through the coax line running up the lower portion of the structure.

Construction and Tuning

The photographs and the drawings show how the antenna is constructed. The system was designed so that "storebought" items could be used for the assembly, rather than fabrication of the antenna components. A list of required parts is given in Table 2.

The tuning adjustments of the system are very noncritical. Tuning can be done with an SWR indicator. The best sequence is to start with the highest frequency and work down. The 28-MHz groundplane used as a top hat can be adjusted before it is attached to the rest of the antenna. The Radio Shack 11-meter groundplane that we used comes with a hairpin or "beta" match. With a short length of 50-ohm coax for the feed line, the groundplane should be adjusted for the lowest SWR in the 10-meter band. After the groundplane has been adjusted and attached to the top of the antenna, the entire system can be raised into position for final tune-up on the lower frequencies.

At this point the SWR indicator should be inserted in the 50-ohm feed line from the transmitter, as close to the antenna matching network at the base of the structure as possible. All that remains is the adjustment of the 200-pF capacitor. The

This multiband radiator, just over 36 feet (10.97 m) tall, operates on five amateur bands, 80 through 10 meters.

Table 2

Parts Required for the Multiband Vertical Radiator

- 3 —10-ft (3.05 m) lengths TV mast; Radio Shack 15-5066.
- 1 —27-MHz ground plane; Radio Shack 21-901.
- 3 —100-ft (30.48 m) rolls of 22-gauge hook-up wire; Radio Shack 278-1295.
- 1 —Amidon Balun kit (see Fig. 12).
- 1 —Aluminum box for tuner.
- 1 —28-ft (8.53 m) length of RG-8/U coax line.
- 4 —8-ft (2.44 m) sections of aluminum tubing (see Fig. 11).
- 1 —Base insulator; soft drink or (?) bottle.
- 1 —200-pF capacitor, air variable, surplus.
- Misc. — See text and figures.



Notes

1) Radio Shack 27-MHz groundplane cut to dimensions shown. Radials are at right angle and connected to mast.
2) Three heavy-duty 10-ft (3.05-m) sections TV mast.
3) Phase loops, sections of telescoping 5/8-(16-mm) and 1/2-inch (13-mm) aluminum tubing spaced 4-1/2 inches (114 mm) from mast. See text.
4) 50-ohm coax such as RG-8/U. At upper end connect center conductor to top element, braid to ground-plane elements. Connect lower end to base loader network (Fig 12).

Fig. 11 — Details of the multiband radiating structure. See Table 2 for parts list. It is very important that a uniform spacing be maintained for the phasing loops, which may be supported at the bottom by shelf brackets. To support the upper portions of these loops, the author used homemade wooden spacers, 1/2 X 1 inch (13 X 25 mm), which were soaked in paraffin and held in place by screws passing through the loop tubing and the main radiator tubing. Homemade Plexiglas spacers may also be used.

---

[1] *The ARRL Antenna Book*, 13th Ed. See Fig. 2-74 and the accompanying text on page 60.



The base of the multiband antenna system. The 200-pF capacitor of the matching network is mounted inside a weatherproofed box, and the 80-meter loading coil is mounted outside. The porcelain knife switches for bandswitching are mounted outside the aluminum box under a homemade hinged cover. The structure itself is supported by a 10-foot (3.05-m) wooden post set 2 feet (0.61 m) in the ground (concrete optional).

Although heavy-duty insulators were used to support the radiating mast from the post as shown here, experience has indicated that insulators are not required. The author suggests that a modified pair of chimney-mount brackets be fastened to the post with lag screws. A short length of PVC pipe or Mylar film may be placed around the mast where it is supported, if you feel it necessary to have the mast insulated from the post.



Fig. 12 — Schematic diagram of the base loading network. The connection to the mast base should be made with a short wire, no longer than one foot (0.31-m). The 200-pF capacitor should have a minimum of 1/16-inch (1.6-mm) plate spacing.

L1 — 80-meter loading coil, 0.67 µH; 4 turns of aluminum grounding wire, 3-inch (76-mm) diameter, 1 turn per inch, air core.
S1 — Dpdt, heavy-duty type. Two porcelain knife switches from the local hardware store will suffice, one for each pole.
T1 — Bifilar-wound toroidal autotransformer, 1:4 ratio; 11 turns spaced around 2-inch (51-mm) ID toroidal core: Amidon Balun Kit or equiv. (Amidon Associated, 12033 Otsego St., North Hollywood, CA 91607).

tuning will be different for each band. On 21 MHz the capacitor will be only about five percent meshed, on 14 MHz about half, and on 7 MHz nearly fully meshed. The capacitor on 3.5 MHz, along with the 3.5-MHz coil, can be adjusted to whatever section of the band you wish to work. The bandwidth will be about 400 kHz with less than 2:1 VSWR. To switch bands, all that is required is to set the double-pole, double-throw switch for the proper band and adjust the 200-pF variable capacitor.

All of the antennas constructed so far were cut to the dimensions shown in Fig. 11 and have not required any change. They have been installed in a wide variety of locations and the system design has been broad enough in tolerance to handle all of them. The writer's antenna has been in operation since 1972 and has performed exceptionally well. In the first year on the air, I managed to work 100 countries with less than 250 watts. In several experiments with just the six radials, we made comparative tests between this design and a properly matched quarter-wave vertical over the same radial system. The radiation efficiency was about 60 percent for the quarter wave vs. 89 percent for the "little monster." In the far field the signal improvement was better than 6 dB.

Now there are eight of these antennas on the air, and several more are under construction. All of the hams who have built the antenna have had comparable results to mine.

There are three hams to whom this author would like to give credit. They helped in testing and measuring the system and encouraged me to get it down on paper. They are Bob Crawford, WA6RYZ; Frank Scott, W6WOP and John Campbell, W6NVV. This material was presented originally in *QST* by A. E. Collins, K6VV.

References

The ARRL Antenna Book, ARRL, Newington, CT.

King, *The Theory of Linear Antennas*, Harvard University Press, Cambridge, MA.

Terman, *Radio Engineering*, McGraw-Hill Book Co., New York, NY.

A Triband Vertical Antenna

Keep your vertical antenna simple. Operate three bands without using traps!

The most common vertical is the quarter-wave type, which radiates well and is easily matched to a coax feed line, but has the weakness that it is a single-band antenna. Methods of adapting a vertical for multiband operation include the use of traps, loading coils and elements of different length fed in parallel. The antenna system to be described here was arrived at by treating separately the problems of designing the antenna and of designing the matching system.

The antenna design was easy. A height of 22 feet (6.71 m) is optimum for a vertical antenna for 10, 15 and 20, and several commercial verticals are of this height. It corresponds to about five-eighths wavelength on 10 meters. Greater height results in reduced low-angle radiation on 10, besides being more difficult to erect. A 22-foot (6.71-m) vertical gives better low-angle radiation than a quarter-wave vertical on all three bands and is especially good on 10 meters.

The antenna consists of 22 feet (6.71 m) of 300-ohm twin-lead, with both conductors tied together, held about an inch from a bamboo pole by means of small blocks of insulating material spaced every two feet or so along the pole and held in place with plastic electrical tape. The pole is guyed with nylon fishing line, and the antenna is operated against a groundplane of four quarter-wave radials for each band. The use of twin-lead rather than a single wire simulates a thicker conductor and reduces the impedance, making the antenna easier to match. Even so, the antenna impedances are vastly different on the three bands. The presumed values of impedance are listed in Table 3. These values are taken from published data[1] and assume a cylindrical antenna of specific radius operated against a perfect ground. The antenna is not cylindrical, and it operates against a wire groundplane, so that the impedances listed must be considered approximate only. The results obtained indicate that they are at least fairly close.

Table 3

Approximate impedances at base of 22-foot (6.71-m) ground-plane vertical antenna

Frequency	*Resistance*	*Reactance*
14.250 MHz	100 ohms	+200 ohms
21.375 MHz	1200 ohms	—500 ohms
28.500 MHz	60 ohms	—220 ohms

Table 4

Impedances at input end of 27.8-foot (8.47-m) matching section of 300-ohm twin-lead terminated by the impedances listed in Table 3.

Frequency	*Resistance*	*Reactance*
14.250 MHz	93 ohms	+177 ohms
21.375 MHz	63 ohms	0 ohms
28.500 MHz	75 ohms	—282 ohms



Fig. 13 — The triband vertical antenna system.

A — Vertical radiator, 22 ft (6.71 m) of 300-ohm twin-lead with conductors in parallel.
B — Four radials, each consisting of 1/4λ of wire, for each band (12 wires in all).
C — Matching section, 27.8 ft (8.47 m) of 300-ohm twin-lead.
D — Reactance unit; see Fig. 14.
E — 75-ohm coax to transmitter, any length.



Fig. 14 — Reactance-unit circuit.

L1 — 0.86 μH; 7 turns no. 16 (or heavier). 1-inch (25-mm) dia, 1-inch (25-mm) winding length.
C1 — 30-pF air trimmer set to 23.1 pF.
C2 — 100-pF air trimmer set to 41.7 pF.

If the three antenna matching impedances are normalized to 300 ohms and plotted on a Smith chart, it can be seen that it is possible to obtain a reasonably good match to a coax line on any of the three bands by using an appropriate length of 300-ohm line as a matching section connected between the antenna and the coax line. What is not possible is to find a single length of line that will provide suitable matching on all three bands.

It turns out, however, that a 27.8-foot (8.47 m) section of 300-ohm line having the 0.82 velocity factor which is usual for twin-lead has interesting characteristics. Such a section of line, connected to an antenna having the impedances listed in Table 3, has the input impedances listed in Table 4. This combination of antenna and matching section is shown in Fig. 13.

It will be noted, first of all, that this combination may be used as it stands on 15 meters and fed with any usual coax. What is even more interesting, however, is that the input resistance is near 75 ohms on all three bands, though on 10 and 20 there is also considerable reactance. If a reactance unit could be made which had just the correct value of reactance to cancel out the input reactance of the matching section on all three bands, the unit could be connected in series with the matching-section input and the system fed with 75-ohm coax on all three bands.

Reactance Units

Can such a unit be made? Certainly! It's not hard at all. It consists of a simple seven-turn coil and two trimmer capacitors and is shown in Fig. 14. The trimmers are most easily adjusted with the aid of a grid-dip meter before the reactance unit is installed. C1 should be set so that L1C1 resonates at 35.85 MHz, and C2 can be subsequently adjusted by temporarily connecting it in parallel with L1C1 and varying it until the combination resonates at 21.37 MHz.

With the reactance unit adjusted as described, the antenna when first assembled showed SWRs of 2.1, 1.4, and 1.5 on 10, 15, and 20 meters respectively. Connecting the unit into the feed system apparently increased its shunt capacitance somewhat, for a small reduction in the value of C1 changed the SWR readings to 1.3, 1.5, and 1.4. These values could probably have been improved still more by further adjustment of C1 and C2, but it was not considered worth the trouble. If it is undertaken it should be borne in mind that the adjustments interact, but that C1 has its greatest effect on 10 meters and C2 on 20 meters. In any case it is not possible to obtain a perfect 1:1 match with this antenna system.

An SWR of 2, however, which can easily be bettered on all three bands, is within the loading capability of almost any transmitter and causes an *additional* loss over a perfectly matched line of less than half a dB even when the transmission line is very long. Since such a change in signal strength is undetectable, an SWR of 2 is in practice as good as an SWR of 1, as far as losses are concerned.

---

[1] Jordan, E. C., *Electromagnetic Waves, and Radiating Systems*, Figs. 13-12 and -13, New York: Prentice-Hall, Inc., 1950, pp. 482-3.

A Few Notes

A few observations are in order. The matching section has a fairly high SWR (between 4:1 and 8:1), and it should be spaced well clear of metal objects and should not have sharp bends. TV standoffs are useful here. It is important that the same side of the matching section be connected to the coax shield and to the groundplane. If such a thing were available, 300-ohm coax would probably be preferred for the matching section, but for medium power (180 watts PEP) TV-type twin-lead for the matching section and receiving-type trimmers in the reactance unit have proved satisfactory. The parallel circuit L1C1 does not operate at its resonant frequency, and thus high circulating currents are not encountered. High power might necessitate heavier components. The reactance unit needs protection from the weather and can be built into a small plastic box and sealed with plastic electrical tape.

Although the antenna is matched at three widely separated frequencies, it is not matched at intermediate frequencies and is thus not a broad-band antenna in the usual sense. Nevertheless, it is broad enough for normal ham use. The SWR remains below 2:1 over the entire 15- and 20-meter bands, and also between 28.3 and 29.4 MHz on 10.

All SWRs mentioned in this article have been measured at the transmitter and are thus probably a little optimistic. Transmission-line losses are not known, but the line is not long (about 40 ft. [12.19 m]), and it is doubtful that the SWRs at the reactance unit are much higher than those measured at the transmitter.

This antenna is no match for a quad or a Yagi, but it has provided numerous transatlantic QSOs on all three bands. Because of its effectiveness, convenience, and the cheapness and availability of everything used in its construction, it should appeal to many hams. This material was originally presented in *QST* by Frank A. Regier, OD5CG.

A Multiband Groundplane Vertical Antenna with Tuned Feeders

Who says tuned feeders are used only with horizontal wire antennas? Go multiband with a simple vertical radiator by using a tuned-feeder system — and do it with ease!

For several years, the author has experimented with several versions of this antenna and has found them to be most satisfactory. The antenna shown in Fig. 15 provides not only outstanding performance on 10, 15 and 20 meters, but performance on 40 and 80 meters equivalent to most mobile-antenna installations. Full efficiency on these latter bands can be realized by making the vertical and radial portions proportionately longer.

The antenna system consists of the radiating element, groundplane radials, an open-wire feeder of any convenient length, a Transmatch capable of either series or parallel tuning, and an antenna SWR bridge. This combination is shown in Fig. 16.



Fig. 15 — Sketch of W4VON's simple multiband antenna.

Antenna and Radial Lengths

The author preferred to cut the antenna for resonance on one particular ham band (20 meters), but it is not necessary that the antenna be resonant on any band. Efficiency will suffer, of course, on bands where the length is significantly shorter than one-quarter wavelength. Whatever the length chosen for the antenna, the radials should be of about the same length.

Construction

Constructional details are shown in the sketch of Fig. 15. In the event the specified aluminum tubing is not available, thin-walled galvanized electrical conduit, aluminum conduit, or copper pipe may be used.

It is recommended that the vertical element not be supported by drilling holes through the tubing, as this will substantially weaken the structure. An alternative mounting arrangement is shown in Fig. 17. The insulators are porcelain standoff types with a lag-screw insert. They will be found at electrical supply houses (also at Sears), and are sometimes referred to as "saddle" type insulators. The hose clamps are stainless-steel gear type.

Adjustment

Operation of the antenna is simple. The Transmatch (a suitable one, including SWR bridge, is described in the ARRL *Handbooks)* and SWR bridge are connected, and the tuning network adjusted for



Fig. 16 — Recommended setup for coupling antenna line to low-impedance transmitter output.



Fig. 17 — Suggested method of mounting radiator element without drilling holes in aluminum tubing.

maximum forward and minimum reflected power. Initially, it will be necessary to determine experimentally whether series or parallel tuning is required for the particular combination of band, feeder length, and antenna length selected.

The tuned-line-fed groundplane vertical antenna gives excellent performance, can be easily constructed in just a few hours even by a beginner, requires a minimum of installation space and costs less than $5, excluding the Transmatch and SWR bridge. The tuned circuit of the Transmatch provides excellent discrimination against harmonic output from the transmitter. Ease of construction and portability make this antenna an ideal one for Field Day use.

In case one wonders about the mismatch between the line and the antenna, the secret is in the use of open-wire line. The loss in such a line with an SWR of 25:1, at 10 meters, is less than the loss in RG-58/U when the latter is matched. This material was originally presented in *QST* by Arthur S. Gillespie, Jr., K4TP.

A Helically Wound Vertical Antenna for the 75-Meter Band

"Around and around she goes, and where she comes out — nobody knows." True, perhaps, with a wheel of fortune, but with a helically wound vertical the rf comes out effectively for DX and local work!

In order to have a full-size vertical antenna for the 75-meter band, the antenna would have to be around 65 feet (19.81 m) tall. That, alone, would require guying, or some other means of support which would result in a structure with no aesthetic appeal to any nonhams (who comprise almost 100 percent of the author's neighborhood). By using a helical configuration, the overall antenna height is reduced, thus eliminating the need for guying. With the helically wound antenna, more equal current and voltage distribution is accomplished (as compared with a lumped impedance from a loading coil). As a result, a better radiation pattern is produced. With this system very little reactance has to be cancelled out, eliminating the need for an overly large "top hat."[1] This antenna will easily take the full legal power limit.

The dark pole to the immediate left of the tower is the WA0WHE helically wound vertical antenna.

Construction details for the antenna are shown in Fig. 19. The following is a list of parts used in constructing the antenna system.

1 — 20-ft (6.10-m) section of 4-inch (102-mm) OD plastic pipe (obtained at a local plumber)
130 ft. (39.62 m) no. 12 plastic-insulated



Fig. 18 — Measured SWR of the vertical antenna.

---

[1] [Editor's Note: Some form of metal top hat should be connected to the last turn of the driven element at the high-impedance end of the radiator. Extremely high levels of rf voltage can develop at the end of the helix, sometimes causing the tip of the antenna to burn. The top hat tends to lower the Q of the antenna, thus reducing the voltage level at the far end. An aluminum pie tin mounted on a ceramic cone insulator works well in this application.]


BLOCK OF WOOD USED TO FASTEN TOP HAT TO POLE
10"(254mm) TOP HAT SOLDERED TO END OF ANTENNA WIRE
10' X 2" X 2" (3.05m X 51mm X 51mm) WITH SHIMS USED FOR INTERNAL BRACING
FEEDTHROUGH INSULATOR
BASE LOADING ASSEMBLY COVER
STAKE (4)
THUMB NUT (4)
(A)
ANT. LENGTH = 492/F(MHz) = 492/3.995 = 123' (37.49m)
WIND FULL HALF WAVE OF NO. 12 PLASTIC INS. COPPER (SOLID) WIRE EQUALLY SPACED AROUND THE SUPPORT
LEAVE BOTTOM OPEN TO RELEASE WATER
FEEDTHROUGH INSULATOR
150pF
RG-8/U IN THROUGH SIDE
8' (2.44m) TO 10' (3.05m) GND ROD WITH RADIALS SOLDERED
(B)

Fig. 19 — Construction details of the helically wound antenna.

solid copper wire (allow a little extra, about 2 ft. [0.61 m])

1 — 10-in. (254-mm) disk of sheet metal (top hat; stop at a sheet metal or furnace repairman — I got this free)

260 ft. (79.25 m) no. 14 solid bare copper wire (I used only four radials in this system; use as many as you have room or money for)

20 sq. ft. (1.86 sq. m) of marine plywood for base

2 — 2 × 2 10-ft. (3.05 m) sections, for internal bracing

1 — 8-ft (2.44-m) copper ground rod (for radial junction)

The cost can be reduced considerably if all materials are readily located or already owned.

Fig. 18 shows the results of SWR measurements. The SWR indicator used to make the measurements was a Midland model. The antenna was adjusted for minimum SWR at resonant frequency with the tuning capacitor at the base. The frequency for this antenna is 3995 kHz with 123 feet (37.49 m) of wire wound on the support and one 8-ft. (2.44-m) ground rod and four 65-ft. (19.81-m) radials. There are numerous configurations possible with this system including a broadcasting favorite such as phasing two or more structures. I forgot to mention . . . give the entire structure one or two coats of marine varnish to seal the turns. This material was originally presented in *QST* by Gary L. Ellingson, WA0WHE.

The Ground-Image Vertical Antenna

The name of the game with vertical antennas is the "ground system." Not just any hastily contrived radial ground will do the job right. Read these details for building an effective ground that provides positive results.

Even though a beam antenna supported at the modest height of 40 feet (12.19 m) is a compromise (a 20-meter beam should be higher to be really effective), it still can be an obstacle to good neighborly relations, at least if your neighbors don't appreciate the ecological beauty of such an installation. Moreover, even that modest sort of an installation presents quite a number of engineering problems.

This report presents the results of the first phase of an investigation to find a less conspicuous but equally effective antenna for use at a new location. The author hopes it will provide suggestions for those faced with a similar problem. At the least, it may be of some value to those with a general interest in the subject of antennas.

This first part of this section deals briefly with theoretical considerations, the second with experimental results on quarter-wavelength and five-eighths-wavelength verticals, and the third on the test equipment. It should be pointed out at the outset that the information presented here is the work of a hobby and as such cannot be exhaustive. It is hoped that others will repeat some of the experiments, extend the work, and report the effect in practice of a groundplane system above 3 MHz. To my knowledge such practical data have not been reported.

Theoretical Considerations

A beam antenna possesses the advantage of gain and directivity. Nevertheless, its DX capability is determined primarily by its vertical radiation pattern. A large portion of the radiated energy should be directed between 5 and 25 degrees from the horizon.[1,2] Horizontally polarized antennas yield lower angles of radiation with increase in height above the ground. This is a result of the interference pattern created by reradiation from the earth's surface. Since the earth is a somewhat conducting medium, the electric field tangential to the surface must be approximately zero. This "boundary" condition is brought about by the induced surface currents which create an electric field of opposite phase. This field then combines constructively and destructively with the initial radiation from the antenna. A model for this condition is an image antenna of opposite phase below the earth's surface as a depth equivalent to the height above the surface.[3] In order to get a lobe below 15 degrees, the antenna height must exceed a wavelength. This is greater than 60 feet (18.29 m) on 20 meters.


The 20-meter vertical antenna in the foreground, and the 26-foot (7.93-m) test tower.


The base of the vertical element of the antenna and the impedance bridge. Forty radials, in bundles of five are fastened to the aluminum base plate and are tied down with a ring made from copper tubing.

On the other hand, a vertical antenna, in the ideal case, possesses an image which is in phase to produce a lobe tangential to the earth's surface. Only when the antenna length is increased to a wavelength, or multiple thereof, does the tangential lobe disappear. This is true whether the antenna is on the ground or suspended in space. Therefore, a vertical beam, i.e., an array of vertical antennas coupled together with an appropriate feed system, on the surface of the earth, seemed to be the logical choice for the new installation since it would appear to meet the following objectives: The system should

1) Exhibit a minimum profile.
2) Be easy to install and tune.
3) Offer a low angle of radiation.
4) Not require a large outlay of money.

The author proceeded, therefore, to construct an array with four vertical elements. When the tests were begun, it immediately became apparent that the simple procedures the writer was using were inadequate to cope with such a complex system. The author had to start anew to develop a test procedure and to build some suitable test equipment. The logical step was to backtrack to a single vertical antenna and use it as a standard on which to develop some basic test standards. As discussed subsequently, the writer found that relatively simple equipment, e.g., a simple impedance bridge, a field-strength meter, and a test oscillator, gave this author all of the data about the system that he needed.

It is important to note that a true ground-image antenna differs substantially from a ground-plane antenna system which relies merely on a few $\lambda/4$ radials above the ground. A true ground-image system results when a sufficient number of radials are used and an image of only the vertical section is sufficient to describe it. Considerable information[4,5] is available on ground-image systems for verticals operating below 3 MHz. The results have shown that some


Base hardware for the antennas being tested. The insulator was made from 1-inch (25-mm) maple dowel, turned down to accept the 7/8-inch (22-mm) inside diameter of the ground and antenna tubing.

Table 5

Comparison of responses of 1/4-wavelength and 5/8-wavelength vertical antennas at low radiation angles. Data were taken by field-strength meter mounted on a wooden tower at a distance of 7.5 wavelengths at 14.25 MHz. Field strength (E) is normalized to maximum value obtained with 5/8-wavelength case.

θ	*E(λ/4)*	*E(5/8λ)*	*GAIN OF 5/8-λ ANTENNA*
0.1°	0	0.58	∞
0.4°	0	0.62	∞
0.75°	0.62	0.80	3.4 dB
1.1°	0.69	1.0	3.2 dB
1.5°	0.62	0.92	3.4 dB
2.25°	0.48	0.80	4.3 dB
3°	0.41	0.69	4.5 dB

The triband trap vertical antenna, which has an overall height of only 12.5 feet (3.81 m). With the system of 40 radials, performance of this antenna on 20 meters was about the same as that of the 1/4 and 5/8-wavelength vertical elements.



Fig. 20 — The input impedance of a 20-meter quarter-wave vertical antenna as a function of the number of radials 0.4-wavelength long. The four and eight radials consisted of bundles of five wires of no. 18 guage. The 40-radial point was obtained by fanning out the eight bundles.



Fig. 21 — The improvement of low-angle radiation of a quarter-wavelength vertical antenna on 20 meters as a function of the number of added radials. A test oscillator was mounted on a wooden tower four wavelengths away at an elevation angle of six degrees from the base of the vertical.



Fig. 22 — The result of interlacing 3/2-wavelength radials in a particular direction. Data were obtained by using a test oscillator on a wooden tower eight wavelengths away, at an elevation angle of 3 degrees from the base of the vertical. The results indicate the advantage of longer wires and the possibility of directional properties of a nonsymmetrical radial system.

100 radials of λ/2 in length, buried just below the surface, provide an adequate ground system. At higher frequencies, the dielectric effect of the earth becomes important, resulting in severe discrimination of radiation or reception at very low angles.[6,7] At low angles, the waves not only suffer by absorption, but also by a change in phase which results in destructive interference. Since little specific information was available at higher frequencies, the objective of the present work was to measure the input impedance and vertical radiation pattern at low angles of a vertical antenna as a function of the number of radials, in order to determine the feasibility of a vertical-array system as a competitor to beams at high elevation. The results of the tests were most gratifying. The author found that many of the "rules of thumb" which have developed and have been perpetuated to the point where they are practically taken for granted were more myth than truth.

Experimental Results

The classical paper on radial systems, which reports experimental results at 1 and 3 MHz, indicates that a large number of radials 0.4λ long should be used.[8] This appeared to be a good starting point for a 20-meter vertical. Accordingly, to check the number of radials needed, this author used eight bundles of wires, each 25 feet (7.62 m) long, and each made up of five no. 18 copper wires. Each bundle was bolted to a 5 × 1/4-inch (127 × 6-mm) aluminum plate as shown in the photograph. The writer was then able to use each bundle as a radial, measure the input impedance of the system, and then separate the bundles, wire by wire, to increase the number of radials in the system.

Fig. 20 shows the input impedance as a function of the number of radials used. Measurements were made with a simple impedance bridge. (Its construction is discussed later.) The antenna was resonated before each measurement was made, and the difference between the 40-radial system and the 8-radial system resulted only by fanning out the bundles of wires. This technique points out another important feature of ground systems and refutes one of the old myths: since the current carried by the radial system is equally divided among n radial elements, each radial is required to carry only 1/n of the total current. This means that relatively small diameter wire is perfectly adequate.

Moreover, it was found that at the higher frequencies it is best to keep the radials near the surface of the ground. Radials buried more than a few feet become less effective! Thus, you should not rely on the old admonition that radials should be 6 feet (1.83 m) down to be effective. This writer found that burying the wires slightly below the surface is the best way of installing the system. Mechanically the radials can be nailed down, electrically they are most effective, and esthetically they provide little interference to a healthy stand of grass.

It will be seen from Fig. 20 that the input impedance for a vertical antenna is drastically affected by the number of radials. Many radial wires are necessary to prevent an excessive loss of power and to provide a convenient input impedance. Fig. 20 also shows the theoretical impedance limit for an antenna having an effective height-to-radius ratio of 300:1.[9]

Fig. 21 shows the effect on low-angle radiation as a function of the number of radials. These data were obtained by placing a test oscillator on a wooden tower, four wavelengths away. A photograph shows the 20-meter vertical and the 26-foot wooden test tower.

The effect of using longer radials in a particular direction is shown in Fig. 22. Radials of no. 18 wire, 3/2 wavelengths long, were put down between the existing 40 radials. The spacing between the longer wires was five degrees. The considerable improvement indicates the need for longer wires and the directional properties a groundplane could give.

A 5/8-wavelength vertical was also constructed and tested. It consisted of a 40-ft. (12.19-m) telescoping aluminum pole and a loading coil of eight turns of no. 12 wire with a diameter of 2.5 inches (64 mm). The comparison in low-angle radiation at a distance of 7.5 wavelengths is presented in Table 5. A field-strength meter was mounted at different heights on the 26-foot (7.93-m) tower. The groundplane for these data consisted of the 40 0.4-λ radials plus the 11 3/2-λ ones. Measurements were taken in the direction of the added longer radials. The results show the improvement in low angle radiation offered by the 5/8-λ vertical. The input impedance of this longer antenna was found to be 76 ohms.

On-the-Air Checks

From these experiments and measurements the author decided to settle on a 1/4-λ antenna with approximately 40 radials. The installation is shown in the photograph. This writer then proceeded to make on-the-air tests to compare its effectiveness with an inverted-V antenna having its apex at 0.4 wavelength, and with a 5/8-λ vertical using the same ground system. Surprisingly, the 1/4-λ vertical seemed to perform just as well as the much taller 5/8-λ vertical. This could result from the fact that most signals arrive after several hops and the optimum lobe angle is probably as high as 15 to 20 degrees.[10] At that angle, the λ/4 antenna actually enjoys an advantage. With practically all DX contacts, the verticals had a 6- to 8-dB improvement over the inverted V! The only exceptions were at intermediate distances and for local contacts. At about 500 or 600 miles, the inverted V with its higher angle of radiation gave better results. Locally, the verticals gave far superior performance. Improvements of 10 to 15 dB were recorded. A triband trap vertical antenna was also tested on 20 meters and found to be practically the same in impedance and performance. This antenna had an overall height of only 12.5 feet (3.81 m)!

Test Equipment

A most interesting aspect of antenna measurements is that the equipment can be rather simple and in many cases constructed from items most amateurs have in their junk boxes. All that is really needed is some standard to compare with, such as a wattmeter or an S meter that is known to have reasonable accuracy. This writer has used both — the wattmeter in a Drake L-4B linear amplifier and the S meter in a R-4B receiver.

The impedance bridge shown in the photograph was patterned after the one shown in the *ARRL Handbook*. Care was taken in shielding the input and output circuits. The meter was mounted externally in order to minimize stray pickup. A calibration curve was obtained at 14.25 MHz by using many carbon resistors of known values as the load.

The field-strength meter is a simple diode detector and dc amplifier. The instrument was constructed to cover the 10-, 15- and 20-meter bands. Its meter was also mounted externally, The antenna length for the field-strength meter was determined by the strength of the available field. In addition to these pieces of test equipment, a 20-meter transistorized crystal oscillator was used for many of the tests.

Conclusion

The performance of a vertical antenna on the ground is highly dependent upon a good ground system, and, properly installed, the antenna can be a very good performer indeed for DX and local contacts. This is particularly true at the higher frequencies where the dielectric property of the earth plays a major role. Forty radials of no. 18 wire, 0.4λ long, will increase the total radiated power by about 3 dB. Radials can be thin if a sufficient number are used. The thought of using thick wires buried deeply, probably a carryover from lightning grounds, is not valid at higher frequencies. The idea of using only four buried radials, as commonly recommended, is a serious error, and if this article does nothing more than eliminate that misconception, this author will be satisfied. Since the electric field only penetrates the ground for a foot or two at the higher frequencies, the radial wires need be buried only as deep as necessary to escape children's feet and the lawn mower. Finally, these results from the single vertical antenna indicate that a vertical array could be a competitor to the more elaborate horizontal beams and warrants further investigation. This material was originally presented in *QST* by Jerry Sevick, W2FMI.

References

[1] Terman, *Radio Engineering*, McGraw-Hill, New York, 1947, p. 651.

[2] Friis, Feldman, and Sharpless, "The Determination of the Direction of Arrival of Short Radio Waves," *Proceedings of the IRE*, Vol. 22, No. 1, January 1934.

[3] Williams, "Antenna Theory and Design," *The Electrical Design of Antennae*, Vol. 2, Second Edition, Sir Isaac Pitman and Sons Ltd., London, p. 126.

[4] Brown, Lewis, and Epstein, "Ground Systems as a Factor in Antenna Efficiency," *Proceedings of the IRE*, Vol. 25, No. 6, June 1937.

[5] Wait, "Input Resistance of L. F. Unipole Aerials," *Wireless Engineer*, May 1955.

[6] Feldman, "The Optical Behavior of the Ground for Short Radio Waves," *Proceedings of the IRE*, Vol. 21, No. 6, June 1933.

[7] Jager, "Effect of the Earth's Surface on Antenna Patterns in the Short Wave Range," *Internat Elekitron Rundschau 1970*, Nr. 4.

[8] See footnote 4.

[9] King and Harrison, "The Impedance of Short, Long, and Capacitively Loaded Antennas with a Critical Discussion of the Antenna Problem," *Journal of Applied Physics*, Vol. 15, February 1944.

[10] See footnote 2.

The W2FMI Ground-Mounted Short Vertical

Just because the vertical is physically short doesn't mean it won't provide excellent results in DX work. Theory says it can be done. Here's how!

A short vertical antenna, properly designed and installed, approaches the efficiency of a full-size resonant quarter-wave antenna. Even a six-foot (1.83 m) vertical on 40 meters can produce an exceptional signal. Theory tells us that this should be possible, but the practical achievement of such a result requires an understanding of the problems of ground losses, loading, and impedance matching. This paper covers design principles which are applicable to all of our amateur bands.

Background

Earlier work by the author[1] on the radiation efficiency of a ground-mounted vertical resulted from the desire to design a simple, inexpensive, low-profile DX beam for 20 meters. This first work reviewed the theoretical considerations involved and pointed out that a good ground system is essential to achieve efficient operation of a resonant quarter-wave antenna. The second work applied these results to a 20-meter beam.[2] In the process of trying to extend the results of these investigations to the 40-, 80- and 160-meter bands, and to possible multiband operation, the need arose to understand the operation of a shortened vertical and the effects of different loading schemes on the input impedance.

The first part of this paper deals with the theoretical considerations of a short vertical antenna and the experimental procedures involved in measuring the various parameters. This is followed by experimental results which show the trade-offs involved in shortening antennas by various loading schemes. Finally, specific designs are given for the 40- and 80-meter bands.

Theoretical and Experimental Considerations

There are several old familiar axioms in Amateur Radio that are not completely understood by the amateur. The author refers specifically to the two sayings: *Make the antenna as long as possible and erect it as high as possible,* and, *A full-size beam is better than a smaller beam, and a tall vertical is always better than a short one.* The first axiom is particularly relevant to horizontal antennas, where height is most important for reliable DX operation.[3] Increasing the length tends to increase the gain in certain directions. But with the vertical antenna, taking it off the ground and feeding it at a voltage point (like the J antenna) in order to eliminate radials can result in poorer performance because of increased earth loss.[4,5] More experimental work remains to be done on this phase of vertical antennas. The second axiom noted above is generally true, but misinterpreted by many. The author refers to those important properties: power gain — important in transmitting and capture cross-section — important in receiving. (Power gain is the gain, in magnitude, compared to an isotropic radiator; cross-section is a fictitious area related to the ability of the antenna to intercept the radiated power and make it available to the receiver for detection.) As will be seen below, very little is compromised in these properties by shortening the antenna.



The matching network and base hardware showing 115 radials with the 6-foot (1.83-m) vertical. The pi network is covered with a plastic bag.



The 10-foot (3.05-m), 40-meter vertical designed for an input impedance of 12.5 ohms in order to use a 4:1 step-up bifilar transformer. The top hat has a diameter of 4 feet (1.22 m) and the coil, placed one foot (0.31 m) below, has 14 turns. Shown at the base is the transformer and impedance bridge.



The author with the 6-foot (1.83-m), 40-meter vertical.

The short antenna has been defined as one that is small compared to a wavelength. In a more exact form, it is defined in such a manner as to simplify the mathematics in the theoretical calculations. King[6] has used the following inequality as the definition where

$$\beta_0 h = \leq 0.5$$

$$\beta_0 = \frac{2\pi}{\lambda}$$

h = half-length of a center-fed antenna or the height of a ground-mounted vertical.

λ = the wavelength

$\beta_0 h$ is actually a quantity which is used to express the height of an antenna in terms of an angle in radians. Thus, this quantity is independent of the frequency. Since 40

Table 6

Inductive Loading

	No. of Turns*	h	$R_{rad.}$
1)	*Base Loading*		
a)	7	24 ft 3 in.	14.5 ohms
b)	10	18 ft 9 in.	7.5 ohms
c)	12	15 ft 7 in.	5.5 ohms
d)	14	13 ft	4 ohms
e)	18	8 ft 10 in.	2 ohms
2)	*Midpoint Loading*		
	*No. of Turns**	*h*	$R_{rad.}$
a)	6	28 ft 5 in.	28.5 ohms
b)	11	24 ft 3 in.	25.2 ohms
c)	15	19 ft 8 in.	16.5 ohms
d)	18	15 ft 8 in.	12.3 ohms
e)	24	14 ft 6 in.	10.5 ohms
3)	*Three-Quarter Point Loading*		
	*No. of Turns**	*h*	$R_{rad.}$
a)	10	29 ft 4 in.	32.5 ohms
b)	18	23 ft	26 ohms
c)	23	21 ft 2 in.	23.5 ohms
d)	24	19 ft 2 in.	22 ohms

*B & W 3029, 2-1/2 in. dia, 6 TPI, no. 12 wire.

1 ft = 0.3048 m

Table 7

Top Hat and Distributed Loading

1) *Top Hat Loading* (4-spoked wheel with 1/8-inch Al wire rim)

	Diameter	*h*	*$R_{rad.}$*
a)	1 ft	30 ft 10 in.	34 ohms
b)	2 ft	28 ft 7 in.	32.5 ohms
c)	4 ft	24 ft	30 ohms
d)	7 ft	19 ft 2 in.	23.5 ohms
e)	4 ft*	23 ft 4 in.	29.4 ohms

2) *Distributed Loading* (Helical Antenna)

	No. of Turns	*h*	*$R_{rad.}$*	*Top Hat at 1.5 ft Above Coil*
a)	111	12 ft	8 ohms	1 ft dia.
b)	105	12 ft	10 ohms	2 ft dia.
c)	113	7 ft	6 ohms	2 ft dia.
d)	75	7 ft	7.5 ohms	4 ft dia.

*8-spoked wheel
1 ft = 0.3048 m

Table 8

Parameters of the 40-Meter Short Vertical Designs

Total Height	*$R_{rad.}$ (ohms)*	*No. Turns**	*Dia. Top (ft)*	*Bandwidth*
6 ft	3.5	14	7	100 kHz
8-1/2 ft	7.5	at 6 in. below top hat		
8-1/2 ft	7.5	75 on 7 ft dowel 1-5/8 in. in dia.	4	100 kHz
10 ft	12.5	14 1 ft below top hat	4	125 kHz
15 ft 10 in.	12.5	7 at base	4	540 kHz

*Except for helical antenna, coil wire is same as shown in Table 6.
1 ft = 0.3048 m



Base of the vertical antenna with 60 radials. The aluminum disk is 15 inches (0.38 m) in diameter and 1/4 inch (6 mm) thick. Sixty tapped holes for 1/4-20 aluminum hex-head bolts form the outer ring and 20 form the inner ring. The insulator is polystyrene material with a 1-inch (25-mm) diameter. Also shown is the impedance bridge for measuring input resistance.
Originally, circular wires were used to connect all radials together. These were positioned every 2 feet (0.61 m), starting from the antenna base. Then, one at a time, they were removed, meanwhile keeping a check on the antenna radiation resistance. There was no apparent change in the radiation resistance, so it was concluded that the interconnecting rings of wire were not needed in the ground system.



Eight-and-one-half-foot (2.59-m) helical antenna using a 2-foot (0.61-m) top hat 1-1/2 feet (0.46 m) above the 7-foot (2.13-m) helix. The 75 turns have approximately a 3-inch (76-mm) pitch below the midpoint and 1.5-inch (38-mm) pitch above. Very little difference was noted in reversing the pitches. The input impedance was 7.5 ohms.

meters was used mostly for experimental results presented in this article, the inequality above assures accurate theoretical calculations for verticals of 11 feet (3.35 m) or less.

The theoretical results show that the power gain for a *very* short antenna, even less than 1-foot (0.31-m) high on 40 meters, is 1.5.[7] This increases slowly to 1.513 for an 11-foot (3.35-m) antenna. These gains are to be compared to about 1.62 for a resonant quarter-wave vertical. It can be seen that this difference amounts to less than 0.4 dB or 0.07 S unit, based on 6 dB per S unit.

In a similar fashion, the capture cross-sections differ by relatively small amounts. For the *very* short antenna, a cross-section value is $0.119\ \lambda^2$, while for the quarter-wave vertical it is $0.13\ \lambda^2$. This is surprising to many since it is difficult to visualize a vertical of a foot or two (0.31 or 0.61 m) in height on 40 meters, having practically the same receiving ability as a 33-foot (10.06-m) quarter-wave antenna!

But the important property of a short vertical that makes its capture cross-section nearly the equivalent of a full $1/4$-λ antenna is its *very small value of input resistance.* Fig 23 shows the theoretical curve and the 40-meter experimental results for the input resistance of a ground-mounted vertical as a function of height.[8] The experimental data were obtained by essentially canceling out the capacitive reactance of the vertical by an inductance at the base of the antenna and



Construction details for the top hats. For diameters of 4 and 7 feet (1.22 and 2.13 m), 1/2-inch (13-mm) aluminum tubing was used. The hose clamp is of stainless steel. The rest of the hardware is all aluminum.

measuring the resistive value with an impedance bridge. Since an extensive, low-loss radial system was used, the resistance measured was actually that of the antenna itself, which is called the *radiation resistance.*

Fig. 24 shows the input resistance of a quarter-wave resonant vertical as a function of the number of radials. At the 115-radial point, the input resistance approaches the theoretical value of 35 ohms, which strongly indicates low earth loss and, hence, reliable data in short antenna measurements. The picture also shows the base hardware for 60 radials. The wire is 15-gauge aluminum. There is nothing sacred about 15 gauge. No. 22 wire, or even no. 28, would be just as good.



Fig. 23 — Theoretical curve and experimental results for the radiation resistance as function of height.



Fig. 24 — Input resistance of a quarter-wave ground-mounted resonant vertical as a function of the number of radials.

It should also be noted that very little difference was noted whether 0.2-λ or 0.4-λ radials were used. At 16 radials, the results are practically identical. In fact, this curve is also similar to the one obtained on 20 meters which was reported earlier.[9] More work remains to be done on the trade-offs in performance versus length of radials for ground-mounted verticals.[10]

Experimental Results

In designing a shortened vertical beam for 40, 80 or 160 meters, a most important consideration is the value of the input impedance of the driven element. As seen in Fig. 23, a shortened vertical using base loading has an extremely low value, particularly at one-eighth wavelength and less. This input impedance is then usually lowered in the presence of other elements in a beam array. The resulting very low value of input impedance makes it difficult to design matching networks. Therefore, an experimental investigation was undertaken to see what increases in radiation resistance could be obtained by other methods of loading, i.e., top hat, three-quarter point, midpoint, and distributed (helical antenna). The results of these experiments are shown in Fig. 25. Table 6 shows the individual points for inductive loading and Table 7 for top hat and distributive loading. Several interesting points were brought out by these experimental results. Fig. 25 shows that top-hat loading yielded the largest value of radiation resistance for a particular height. Surprisingly, the helical antenna[11] yielded a value less than midpoint loading. The three-quarter point and midpoint loading curves were not extended to lower values of height because data were very difficult to obtain below the points shown on the respective curves. The combinations of inductances and lengths below the heights shown on these two curves were probably beyond resonant conditions at the frequency used in the measurements. The other curves were extended by dashed lines indicating no difficulties were encountered in the measurements and other lengths were very possible.

Another interesting aspect of the top-hat loading curve is that a four-spoked wheel approaches to a good degree a solid disk. Doubling to eight spokes only improves the loading by about nine percent as noted in Table 7. Thus, *a few radials on the top of a vertical are very effective.*

Four radials at the base, approximating a ground system, are practically *useless* as noted in Fig. 24. Also, it can be seen from Table 7 that the reduction in length because of top-hat loading is approximately equal to twice the diameter of the disk.

On 160 meters, top hats have been made with sloping wires or struts with success.[12] Because of the sloping nature of this top hat, some cancellation of the antenna current takes place, thus reducing the radiation resistance further.

Although the curves in Fig. 25 were obtained from experiments at 7.21 MHz, these data can be applied to the other bands by proper scaling. For example, by doubling all dimensions, including the number of turns of the loading coils, the radiation resistance values would apply at a frequency of 3.6 MHz. By increasing the dimensions by only 1.85 instead of 2, the results would then apply to a frequency of 3.9 MHz. In like manner, a proper scaling factor could be used to apply these results to a portion of any of the amateur bands.

40- and 80-Meter Short-Vertical Designs

As was stated before, a most important consideration in designing short verticals is a knowledge of the input resistance and how it varies with different types of loading. The objective is to obtain a resistance value large compared to earth losses, so that efficient operation is obtained. In the author's specific case, using 115 radials, practically no earth loss was measured, and, hence, any radiation resistance above a few ohms assured good operation and an opportunity to verify the theoretical predictions for very short vertical antennas.

Since a broad-band, bifilar, 4:1 step-up transformer was available from previous work,[13] the first design was for the shortest vertical having an input resistance of 12.5 ohms. From the curves of Fig. 25, it appeared that a 16- or 17-foot (4.88- or 5.18-m) antenna with a coil of some 13 turns (extrapolated from Table 6) at 8 or 9 feet (2.44 or 2.74 m) from the base would provide the proper impedance at 40 meters. Further, it was decided that some 7 or 8 feet (2.13 or 2.44 m) of length above the coil could be replaced by an eight-spoked top hat having a diameter of 4 feet (1.22 m). The actual design that resulted, after proper tuning, is shown in the picture. The antenna had a total height of only 10 feet (3.05 m) and a 14-turn coil placed 1 foot (0.31 m) below the top hat. This height was about one foot (0.31 m) higher than first expected, but upon careful examination it was noted that the top hat also reduced the radiation resistance, while replacing a section of the vertical portion. Therefore, the height had to be increased somewhat when considering top-loading effects. Also shown in a picture are the construction details for the top hat.

Two other shortened verticals for 40 meters were investigated. One was an 8-1/2-foot (2.59-m) helical using a 4-foot (1.22-m) top hat and 75 turns on a 1-5/8-inch (41-mm), 7-foot (2.13-m) long, wooden dowel. The input impedance was 7.5 ohms and it was matched with a standard pi network. Pictures are shown with the network. Several tests were made by doubling the winding pitch below and above the midpoint, keeping the number of turns constant, with very little difference in results.



Fig. 25 — Experimental results of radiation resistance as a function of height of antenna for various types of loading (40-meter data).



Fig. 26 — Standing wave ratio of various short verticals compared to a resonant quarter-wave antenna . The sixteenth-wavelength antenna is the 8-1/2-foot (2.59-m) helical design, the twelfth-wavelength is the 10-foot (3.05-m) antenna, and the eighth-wavelength is the 15-foot 10-inch (4.83-m) antenna. (All three are described in the text.)

The second antenna, also for 40 meters, using a 7-foot (2.13-m) top-hat, resulted in a matched vertical only 6 feet (1.83 m) high. It had a 14-turn coil, 6 inches (152 mm) below the top hat and an input impedance of only 3.5 ohms. Matching was accomplished with the 4:1 transformer and the pi network. A picture of the antenna and matching network is shown.

A larger 40-meter vertical antenna was also investigated. It had a 4-foot (1.22-m) top hat and 7 turns of base loading which resulted in a height of 15 feet 10 inches (4.83 m) (approximately 1/8 wavelength) and an input impedance of 12.5 ohms. The purpose of this design was to compare its low-angle radiation and bandwidth[14] with the other antennas. Table 8 shows the parameters of these various short vertical designs. Fig. 26 shows the SWR curves of three of the short antennas compared to a quarter-wave resonant vertical and Fig. 27 shows the SWR of the 6-foot (1.83 m) antenna.



Fig. 27 — Standing wave ratio of the 6-foot (1.83-m) vertical using a 7-foot (2.13-m) top hat and 14 turns of loading 6 inches (152 mm) below the top hat.



Fig. 28 — The standing wave ratio for the 22-foot (6.71-m), 80-meter vertical.

As can be seen by the SWR curves, shortening an antenna generally decreases its bandwidth. Also by comparing the 8-1/2- and 6-foot (2.59 and 1.83-m) antennas top-hat loading appears to affect the SWR the least. It should also be noted that an eighth-wavelength antenna appears to have a reasonable bandwidth and would probably result in a practical beam design.[15]

And finally, the four short-vertical designs described above were compared with a resonant quarter-wavelength antenna for low-angle radiation and on the air with other amateurs signals. The low-angle radiation measurements were made at three wavelengths in distance and at heights of 1, 3, 6 and 8 feet (0.31, 0.91, 1.83, 2.44 meters). This relates to vertical angles of 0.15, 0.45, 0.90 and 1.2 degrees, respectively. All measurements were made under matched conditions and with a constant 100 watts fed into the antennas under test. In no case were there any appreciable differences noted in the field strength measurements. In fact, the 6-foot (1.83-m) antenna seemed to give slightly higher readings! These measurements certainly tend to verify the theory on the power gain predicted for short verticals. On-the-air checks were again very gratifying and exciting. Over 200 contacts with the 6-foot (1.83-m) antenna strongly indicated the efficiency and capability of a short vertical. Invariably at distances greater than 500 or 600 miles, the short verticals yielded excellent signals.

As was stated previously, all of the results obtained by measurements on 40 meters can be scaled, by the appropriate ratios of frequencies, to other bands. This was tried out on 80 meters. Since a 7-foot (2.13-m) top hat was available (instead of an 8-foot [2.44-m] one), the height turned out to be 22 feet (6.71 m) instead of 20 (6.10 m). The loading coil had 24 turns and was placed 2 feet (0.61 m) below the top hat. On-the-air results duplicated those on 40 meters. The bandwidth was 65 kHz (half of the 40-meter value) as shown in Fig. 28.

Conclusions

Several interesting results came out of this investigation which, even to one schooled in antenna theory, are difficult to believe. The author refers specifically to the ability of very short verticals to radiate and receive as well as a full-size quarter-wave antenna. The differences are practically negligible. But, as was seen, the trade-offs are in lowered input impedances and bandwidths. However, with a good image plane and a proper design, these trade-offs can be entirely acceptable.

As a result of this investigation, other problems were noted which indicate the need for further experimentation. The writer refers specifically to the trade-offs encountered when shortening the radials (to 0.1 wavelength, for example), the efficiency of ground-mounted versus elevated verticals as a function of height above ground, the characteristics of a multiband vertical over a low-loss image plane, and a shortened vertical beam using elements of the order of an eighth wavelength.

Another point should be mentioned in relation to the results reported here. Even though they were obtained on short, ground-mounted verticals, they are valid for center-fed verticals or horizontal antennas as well. The only differences are that the impedance values should be doubled and the effect of the image antenna accounted for.

The author would like to acknowledge the support of many amateurs for their fine words of encouragement and excellent reporting during on-the-air contacts. In this study, some 350 amateurs reported on comparisons between signals from these short verticals and those of other stations. This material was originally presented in *QST* by Jerry Sevick, W2FMI.

References

[1] Sevick "The Ground-Image Vertical Antenna," *QST*, July 1971. Also appears elsewhere in this chapter.

[2] Sevick, "The W2FMI 20-Meter Vertical Beam," *QST*, June 1972.

[3] See footnote 1.

[4] Miller, Poggio, Burke, Seldon, "Analysis of Wire Antennas in the Presence of a Conducting Half-Space. Part II. The Vertical Antenna in Free Space," *Canadian Journal of Physics*, Vol. 50, 1972.

[5] Feldman, "The Optical Behavior of the Ground for Short Radio Waves," *Proc. of the Inst. of Radio Engineers*, Vol. 21, no. 6, June 1933.

[6] King, *The Theory of Linear Antennas*, Harvard Univ. Press, Cambridge, MA, 1956.

[7] See reference in footnote 6, p. 497.

[8] See reference in footnote 6, p. 190.

[9] See footnote 1.

[10] Weeks, *Antenna Engineering*, McGraw-Hill Book Company, 1968, p. 48.

[11] The diameter of the helical antenna was 1-5/8 inches (41 mm). Each helical antenna had a top hat 18 inches (457 mm) above the helix in order to terminate the upper turns with sufficient capacitive reactance.

[12] See reference in footnote 10, p. 44.

[13] See footnote 2.

[14] Bandwidth is defined as the range in frequency where SWR is less than 2:1.

[15] See footnote 2.

Optimizing Vertical Antenna Performance

Do you have tower restrictions, a small yard or patio, almost no room for antennas? If so, here are some suggestions for making your signal bigger in spite of the handicaps.

Antennas never cease to be a hot topic of conversation among amateurs; the interesting articles by John Stanley, K4ERO/HC1[1] and Roger Hostenback, W5EGS,[2] on the optimum grounding of vertical antennas have led the author to communicate these thoughts on the subject. Obstacles at the author's present location (typical of many suburban dwellings) place severe limitations upon where ground wires can be placed. These obstacles are large boulders, areas of concrete, the house, vegetable and flower beds, and the neighbors' property lines. It has not been possible to lay out radials of uniform length or of uniform angular distribution. Nevertheless, the author has had successful results with vertical antennas. Although the writer must make a number of statements which are based upon fragmentary evidence and are lacking in scientific rigor, they should be useful for suggesting how others might proceed to optimize their particular situations.

The writer has three very dissimilar vertical antennas. Much of the discussion will pertain to their individual ground systems, although strictly speaking they cannot be independent; a change of the grounding conductors of one vertical is bound to affect the others. For brevity the writer shall not discuss the methods of impedance matching of the antennas as this is a topic thoroughly covered elsewhere. The author *shall* mention some problems of using dissimilar antennas in a phased array, although the results are preliminary.

The three antennas are (1) a shunt-fed crank-up tower having a three-element triband Yagi on top, the height being variable from 27 to 41 feet (8.23 to 12.50 m); (2) a 40-foot (12.19-m) insulated base-loaded antenna consisting of a 30-foot (9.14-m) pipe mast topped by a whip, located approximately 70 feet (21.34 m) south of the tower and hereafter referred to as the "south antenna"; (3) about 20 feet (6.10 m) east of the tower, a vertical antenna termed the "north antenna," which was described in an earlier *QST* article.[3] Fig. 29 shows the layout. The north antenna has been used with various heights up to 40 feet (12.19 m) but in the present experiments it is used in its "summer" configuration with a height of 25 feet (7.62 m) and with a 7/14-MHz trap located 10 feet (3.05 m) from the base. For 3.5-MHz operation additional loading is supplied at the base.

The Grounding Systems

None of the three verticals have anything approaching an optimum ground system; while the south antenna has the best on paper, it is not necessarily the best in performance. When the south antenna was first placed into operation the grounding system consisted of about 200 feet (60.96 m)

How do you ground a vertical antenna when there is no ground?

Optimizing ground-wire currents is well worth the time and effort required.



Fig. 29 — The WØJF backyard, with antenna farm.



Fig. 30 — Suggested substitute for a thermocouple ammeter.

of wire distributed among a few conductors which went out more or less radially. One was about 60 feet (18.29 m) long, the others 30 feet (9.14 m) or less. On 7 MHz the performance was generally inferior to that of a horizontal half-wave dipole 30 feet (9.14 m) above ground. Later, the ground system was augmented to utilize about 1000 feet (304.80 m) of wire, and the vertical then began outperforming the dipole.

While the author foresaw Stanley's statement that possibly not all of this additional wire would be effective, it was assumed that any wires added at least would do no harm, and the writer tried to put wires in the entire immediate area of the antenna, subject to the constraints mentioned above. Several of the radials have bends to avoid obstacles. In a few cases a single wire goes out from the antenna to a junction some distance away, and then several wires fan outward from the junction. Three wires are connected at the far ends to a few square feet of chicken wire. Where the wires are in shrubbery they are above ground; otherwise they are an inch or two (25 or 51 mm) below. None of the additional wires were as long as 60 feet (18.29 m), and the lengths were generally determined by the obstacles they encountered. Haphazard as this system was, the improvement was spectacular.

While making this change in the south antenna's grounding, the author carried out two simple experiments. First, when operating at 7 MHz, a 33-foot (10.06-m) piece of wire was added, which in free space would be 1/4-λ long, but which when laid on the ground would be longer (in wavelengths). The writer connected it to the rest of the ground system through a thermocouple ammeter, and read the current while applying power. With this wire then cut in half and laid out as separate radials in opposite directions, it was found that the total current increased. Cutting these 1/8-λ pieces in half and distributing the resulting fragments as four radials in directions at 90 degrees to each other caused the total current to decrease. These observations led the author to conclude that for a given total amount of wire the most efficient layout would be radials having lengths of about 1/8 a free-space wavelength. This conclusion is consistent with Stanley's Table 1.[1]

In the other experiment, the author also used a 33-foot (10.06-m) piece of wire, but half of it was no. 34 and half no. 12 wire. With the thick end adjacent to the antenna, the current was higher than with the wire turned around so that the thin end was adjacent. The experiment showed that wire diameter is of some consequence, and it is more important to have heavy conductors close to the antenna.

The Tower and the North Antenna

Grounding of the tower is very heterogeneous; first of all, of course, the bottom of the tower is buried in the ground some 8 feet (2.44 m). There are two radials about 25 feet (7.62 m) long going in a more or less southerly direction, then a short wire going to a water faucet on the wall of the house. Finally, and probably most important, there is a wire that goes northward about 20 feet (6.10 m) and makes a junction with the middle of a 120-foot (36.58-m) east/west wire. The eastern end of this wire is located at the common corner with the property of the neighbor to the northeast and at that point is bonded to his extensive chain link fence. About 25 feet (7.62 m) west of this bond to the fence, there is a junction with a southward wire which is connected to the base of the north antenna. Otherwise, the grounding system of the north antenna, consisting of a few radial wires, is as described in the earlier *QST* article.

Some observations were made by connecting a thermocouple ammeter and a selection of capacitors and inductors in series with various conductors connected to the base of the tower. On 3.5 MHz, with the wire that goes to the fence, the author found a very strong resonance using a 300-pF capacitor. No such resonance was found with this wire of 7 MHz nor on 1.8 MHz, nor did there seem to be any resonance with any of the other wires.

No attempt has been made to bond the upper and lower sections of the tower (where they telescope) together. No such bonding seems necessary, except in the rare case of an extremely strong wind, when there is some receiver noise resulting from poor conductivity between the sections. Cranking the tower up and down seems to have little effect upon the degree of impedance mismatch.

On 3.5 MHz, using a power of about 150 watts, the author had contacts all over the world using this shunt-fed tower, usually not cranked all the way up. The south antenna has also given fairly good account of itself, but with its thousand feet (304 m) of radial wires its performance is still not quite as good as that of the tower with its meager "black magic" grounding.

On 7 MHz, the behavior of the tower is the reverse even though the impedance match is somewhat superior to that on 3.5 MHz. The performance, despite the good match, is far inferior to the south antenna or even the north antenna. Offhand, one would expect the performance, such as it is, to be better with the tower cranked down to minimum height, when it would be close to 1/4λ, but the few reports received on the air indicate better performance is obtained at maximum height. The overall performance of the tower on 7 MHz is a complete mystery.

The author has used the tower on 1.8 MHz only rarely, but has worked as far as 1000 miles, even though there is a very bad impedance mismatch on the feed line. One of the author's future projects is to cure that, since the tower may be magic on the top band, too!

What if You Don't Have a Thermocouple Ammeter?

The preceding discussion has, the author hopes, suggested that individuals may be able to optimize their ground systems by measuring the currents in individual ground wires. In this regard the writer has been fortunate in having available a number of thermocouple ammeters, instruments not commonly available in ham shacks. However, it was found easy to make a substitute which can serve to measure relative current and to detect resonances. Take a short length of twin-lead, speaker cord or similar cable, about a foot (0.305 m) long. Connect one wire of the pair in series with the circuit to be studied (the ground wire). Connect the two ends of the other wire of the pair to a semiconductor diode and a sensitive dc meter in series (Fig. 30). For convenience and for reproducibility in results, coil the cable up and secure it to a terminal board.

Using Dissimilar Antennas in a Phased Array

The author can use any two of the three verticals as a phased array by connecting the feed lines in parallel at the transmitter. In the shack the author has a switchboard that can switch additional lengths of line in series with one antenna or the other. The writer does not attempt to change the impedance match at the bases of the individual antennas, but does generally retune the transmitter as the phasing is changed. Some of the effects observed must be attributed to variations in impedance mismatches rather than to basic changes in directivity. Nevertheless, some gain can usually be obtained by combining the verticals in one way or another.

In the use of two dissimilar antennas, two questions arise which may not apply when identical antennas are used. First, is there really an advantage in using the two of them in a phased array over using the better of the two alone? The relevance of this question may be seen by considering the extreme case where one is very much better than the other. In such a case the field strength of the poorer one is so much less that there is little difference whether it is in or out of phase with the field of the better one, and there can be little or no observable directional effect when the two are used together. Furthermore, the power supplied to the better antenna is cut in half while the other half of the power is largely wasted.

This simple argument suggests that in most cases the two antennas should be nearly equal in the field strengths they produce if they are to be effective in a phased array. However, the actual situation is sufficiently complex that exceptions may be found. For one thing, the better antenna may have "blind" directions in its pattern because of obstructions, and the poorer one may help to fill those in. Also, the impedance effects which have been mentioned before are hard to predict. The author can only suggest that one may find it worthwhile to try using two such antennas together, and may find unexpected advantages in some directions.

On 3.5 MHz the north antenna is generally much poorer than the tower. However, in some directions observers have consistently reported a small gain in using the two together over the tower alone. Incidentally, it should be mentioned that observations made on receiving are not reliable tests, partly because of impedance effects. Also, some of the noise received may be generated locally and its effect may mask the true pattern of the array. The only reliable evaluation is by transmitting to distant observers.

The second question concerning dissimilar antennas involves solving for an unknown quantity: the relative phase of the two antennas. The relative phase of the field of an antenna is *not* determined solely by the length of the transmission line connecting it to a transmitter. The impedance of the antenna usually contains a reactive component, and its presence gives rise to a phase shift. With two identical antennas these phase shifts are the same and do not affect the relative phase between the two antennas, which is determined only by the difference in feed-line lengths. With dissimilar antennas these phase shifts are generally not identical, and they may vary in different ways with shifts in frequency or with variations in the moisture content of the earth. Not unrelated was a discovery made when changing the grounding of the south antenna from 200 feet (60.96 m) of wire to 1000 (304.80 m). There was a substantial change in the phasing when it was used in an array with the tower.

The author has experimentally answered this phasing question by setting up a small probe antenna at a point equally distant from the two antennas and connecting it to a field-strength meter. The line lengths are varied until a minimum (usually quite sharp) is observed. Then it is known that the antennas are 180 degrees out of phase, and the array is a bidirectional end-fire one (W8JK). If the author adds or subtracts 1/2 λ of line from one antenna, the antennas should be in phase and a maximum should be observed. The experimental observations are in agreement with such predictions. If a length of line equal in electrical wavelengths to the spacing between the antennas is then added or subtracted from the feed line of one of them, the combination approximates a unidirectional end-fire array. The favored direction is away from the element which has the longer equivalent feed line (larger phase shift from the transmitter).

To reiterate, the results with phasing dissimilar verticals are very preliminary, and there is little that can be said about them except for the fact that at times very noticeable gains over using the better single antenna are observed.

Vertical Versus Horizontal Antennas

The author used some *horizontal* antennas and observed the differences in performance between them and the vertical antennas at a particular location. Horizontal antennas were not tried on 7 and 3.5 MHz any higher than 30 feet (9.14 m) above ground, however.

The first foothills of the Rocky Mountains rise up immediately to the west of the author's QTH, the nearest ones subtending a vertical angle of about 10 or 15 degrees. As expected, propagation to the west is usually difficult. To the east there are some power wires running north and south. The land slopes off to the north, and has a line-of-sight view for 12 miles from the base of the antenna tower.

The writer finds a tendency for horizontal antennas to be superior to the west, over the mountains, and for verticals to be superior to the east. Standard theory explains these findings as follows: Probably many of the signals coming over the mountains are scattered by the surface of the ground. Those familiar with advanced electromagnetic theory remember that according to the Fresnel equations, the reflection coefficient is greater when the wave is polarized with the electric vector parallel to the surface (i.e., horizontal). Therefore, this scattered radiation is probably horizontally polarized. On the other hand, the electric field from the vertical antenna is perpendicular to the direction of the power wires and is less disturbed by them than the field of a horizontal antenna.

Although very few firm results were presented, the author hopes he has suggested some procedures which will help those facing restrictions on grounding systems they can use. With a little persistence and ingenuity, they should be able to build effective antennas. It *is* possible to evaluate simple arrays yourself and to improve their performance according to your own communication requirements. This material was originally presented in *QST* by Yardley Beers, WØJF.

References

[1] Stanley, "Optimum Ground Systems for Vertical Antennas," *QST*, December 1976.

[2] Hoestenback, "Improving Earth-Ground Characteristics," *QST*, December 1976.

[3] Beers, "Short Antennas for the Lower Frequencies," *QST*, September 1970.

Some Plain Facts about Multiband Vertical Antennas

Does engineering jargon, page-long equations and references to the *IEEE Proceedings* have you gnawing your nails in frustration? Take heart, for these bits of knowledge about multiband vertical antennas are given in plain lingo.

During discussions with newcomers, and old-timers for that matter, it becomes apparent that there is considerable confusion as to what exactly a multiband vertical antenna is. The confusion concerns the method of feed, how much mismatch one can expect, how many radials are required, how the particular antenna is built for multiband use, plus some other points.

This article breaks the subject into simple language and provides the reader with sufficient expertise to assure him that he won't wind up with a system he really doesn't want. Before going into a discussion of the different types of multiband "verticals" we will offer some simple antenna facts.

Some Basic Theory

The term "multiband antenna" has come to mean many things to hams. With trap antennas, tapped coils, random wires, and so forth, there is plenty of reason for the confusion. Simply, a multiband antenna is one that can be used on more than one band. How we make it work on different bands is another story.

Basically, any piece of wire of *any* length can be classed as a multiband antenna. For example, a length of wire 4 feet (1.22 m) long *could* by used on *any* amateur band, from 160 meters on up. But how well the piece of wire would work is a completely different matter.

In the feed point of any antenna there is *radiation resistance.* The energy supplied to an antenna is dissipated in the form of radio waves and in heat losses in the wire and nearby insulating materials. The radiated energy is the useful part, but so far as the transmitter is concerned it represents a power consumption just as much as does the energy lost in heating the wire. In either case the dissipated power is equal to I^2R; in the case of heat losses, R is a real resistance (ohmic losses), but in the case of radiation, R is an *assumed* resistance. This fictitious resistance is the radiation resistance. This brings us to our first important point about multiband antennas.

Whenever one reduces the size (length) of an antenna physically, the radiation resistance is reduced also. As an example, assume we have a 20-meter quarter-wave antenna, which is approximately 16 feet (4.88 m) long. Let's imagine we made it out of no. 40 wire, which has a resistance of about 1 ohm per foot, (0.31 m). The radiation resistance of a resonant quarter-wave vertical operated against a perfect ground is on the order of 35 ohms. In this case, the feed-point impedance of our antenna would be roughly 35 ohms in radiation resistance plus 16 ohms in ohmic resistance. If we were to feed 51 watts into this antenna 16 watts would be dissipated as heat (lost power) and the remainder — 35 watts — would be radiated. Now, suppose we use this same antenna on 80 meters. As mentioned above, when we reduce the size of an antenna physically the radiation resistance is also reduced. On 80 meters our 16-foot (4.88-m) antenna would have a radiation resistance on the order of 1 ohm! However, we would still have the ohmic resistance of 16 ohms. It doesn't take much figuring to realize that just about all of our power would be lost as heat.

Of course we wouldn't use no. 40 wire for such an antenna. More likely the antenna would be made from aluminum tubing and the ohmic losses would be very low, but probably still more than the radiation resistance. There is an old axiom in Amateur Radio that offers some pretty good advice: Always make the antenna as long as possible and erect it as high as possible. Also, there is a joke that goes with that axiom — if such an antenna stays up, it is too small!

At this point we have only mentioned radiation and ohmic resistance in the antenna feed point. These are the two resistances that exist when the antenna is resonant. When the antenna is not resonant, there is reactance present in the feed point. Reactance is also expressed in ohms, but it isn't a real resistance in the sense that power can be dissipated therein. We won't go into a long discussion on reactance because it would take up too much space. An excellent explanation can be found in the League publication, *Understanding Amateur Radio.* Simply, reactance can be likened to a gate or door that stops or hinders the flow of current into a circuit. When an antenna is operated at some frequency other than the resonant frequency there will always be reactance present. Keep in mind that with *any* antenna, multiband or otherwise, we always have a condition on some band or frequency where the antenna is not resonant. Therefore, there will be reactance at the feedpoint.

Types of Vertical Antennas

The basic and most popular type of vertical is one that is a quarter wavelength long and is operated against ground or in a groundplane configuration. The antenna is usually made from tubing and the radials are wire. An ideal groundplane (simulated earth ground) would be a sheet of metal with



Fig. 31 — A typical multiband vertical antenna. A description of the system is given in the text.

a radius of one-quarter wavelength or more. However, this is only practical at vhf so the customary method is to use wires as the radials. Probably the number one question asked about groundplane antennas is, "how many radials are required?" The answer is simply, the more radials used, the better the antenna will perform, at least up to a certain point. This should not be construed to mean that an antenna with only two or three radials won't work. Such an antenna will work, but for *maximum* performance one should consider 40 or more radials. If the reader is interested in performance data for a few radials versus many, he should read the article in *QST* by Sevick.[1]

The feed-point impedance of quarter-wave groundplane is on the order of 35 ohms. The impedance can be raised by drooping the radials down until a 50-ohm match is obtained. Exactly how much droop is required depends on the number of radials.

The quarter-wave groundplane is essentially a single-band antenna. However, a 40-meter quarter-wave vertical can also be used on 15 meters, a happy circumstance for the Novice. In this case, a 40-meter quarter wave works out to be three quarter waves on 15 and any *odd* multiple of quarter waves will provide a relatively low-impedance feed.

Multiband Verticals

When we get into the field of multiband verticals we find that considerable confusion exists. As pointed out previously, *any* antenna can be *called* a multiband antenna, but how we get power into such an antenna is another matter.

Up until the '50s any amateur multiband antenna was a system that usually consisted of an antenna, tuned feeders, and an antenna coupler. In the early '50s more and more amateurs started to use coaxial cable for feeders, along with band-switching transmitters. The next logical step was the use of a multiband antenna system that required no adjustments and always presented a matched condition to the feed line — in other words, an antenna that had a 50-ohm feed-point impedance on every desired band and frequency within a given band. A logical development was the multiband trap antenna.

By inserting traps in an antenna it was possible to make an antenna "look" like a resonant half-wave dipole in whichever band was used; or, in the case of multiband verticals, making the vertical look like a resonant quarter-wave antenna for the desired band. However, and this is important as far as the newcomer is concerned, to our knowledge there is *no* multiband trap antenna that will provide a perfect match on all bands, *regardless* of what some antenna manufacturers may tell you. Many hams have spent countless hours trying to adjust trap antennas for that "perfect" match when actually, it is just about impossible to obtain such a condition.

Nontrap Multiband Verticals

Several antenna manufacturers sell multiband antennas that consist of a vertical piece of tubing, usually 16 to 20 feet (4.88 to 6.10 m) long. The tubing is used with a loading coil at the ground end. By making appropriate taps and adjustments on the coil the antenna can be matched (or closely matched) on any given band. This type antenna has *no* traps. This in turn means that the coil taps and adjustments *must* be altered when one changes bands. Some misguided amateurs buy these antennas expecting all they need do is put them up and the antenna will work on all bands, automatically. Let's make one point clear: such an antenna *is* a multiband antenna, but requires adjustment *at the antenna* when one changes bands.

Of course, the next question should be, "If the antenna is that simple can't I build my own?" Yes, it is a very simple multiband antenna to make and install. Two or three sections of inexpensive 10-foot (3.05-m) TV mast sections can serve as the vertical radiating element. The mast can be supported on an insulator, such as a beverage bottle, and the mast guyed with nylon line. Fig. 31 shows a diagram of the antenna system. L1 should be a coil made of bare wire, no. 12 or 14, so that it can be tapped at every turn. A convenient coil size is 2-1/2 inches (64 mm) in diameter, six turns per inch (25 mm), such as B & W 3905-1 stock. The number of turns required, assuming 80 meters as the lowest band to be used, should be about 30 turns with an antenna length of 25 feet (7.62 m).

Adjustment of the antenna requires the use of an SWR bridge. Connect the coax line across a few turns of L1 and make a trial position of the shorting tap. Measure the SWR, then try various positions of the shorting tap until the SWR reaches its lowest value. Then vary the line tap similarly. This should bring the SWR down to a low value. Small adjustments of both taps should provide an SWR close to 1. If not, try adding C1 and repeat the adjustment procedure, varying C1 each time until a match is achieved. Radials will enhance the performance of the antenna. The number of radials is up to the individual amateur.



Fig. 32 — Drawing of the theoretical multiband trap vertical. In commercial practice, certain traps may be grouped together, giving the impression that only a single trap is used.

Trap Verticals

As mentioned earlier, traps can be installed in a multiband vertical. These traps are usually parallel-tuned circuits and the objective is to make each section of the antenna work as a quarter-wave vertical or odd multiple thereof on the desired band. Fig. 32 shows an example of this type antenna.

The purpose in using this type antenna is to provide a system that always presents a matched condition for the feed line. Unfortunately, there is so much interaction between various sections of the antenna that it is impossible to come up with a *perfect* match on each band. What is an *acceptable* match is another story.

Amateurs as a whole are inclined to attach too much importance to an SWR of 1. They feel that if their SWR bridge isn't showing an absolute zero reflected power that something is horribly wrong and they won't work out. The plain fact is that using a feed line such as RG-8/U (assume a 100-foot [30.48 m] length) one could have an SWR of as much as 5:1 and have *no* appreciable loss in the system. However, there is one clinker in this thinking!

In many instances commercially made transmitters and transceivers are designed by the manufacturer to work into a 50-ohm load only. They don't allow much leeway from this figure. When there is a mismatch in the antenna system, it can become impossible to load and tune the final amplifier of the transmitter. There just isn't enough tuning range in the tank circuit of the amplifier to handle the reactance that may be present in the load. There is a way around this problem however, and that is using a Transmatch in the feed line to disguise the mismatch.[2] The Transmatch can be adjusted so that the transmitter "sees" a 50-ohm load regardless of the mismatch at the antenna.

The Harmonic Problems

Another consideration should be mentioned. As pointed out earlier, *any* antenna can be a multiband antenna. By the same token any harmonics generated in the transmitter that reach the antenna can be radiated. It is true that a single-band antenna will reject harmonic energy, but *not* completely. In the case of a multiband trap antenna there is no rejection of some harmonics, simply because the antenna is designed to be resonant on all hf amateur bands. The solution to this problem is the use of a selective circuit installed in the feed line. A Transmatch is such a circuit and should provide adequate harmonic rejection.

Some Other Thoughts

The question is frequently asked, "Should I mount my vertical on the ground, or get the base up in the air?" Getting the antenna up in the clear is always better than having it mounted at earth level and surrounded by rain gutters, house wiring, trees, power lines and so forth. However, getting the vertical antenna up in the air also means that radials, as many as possible, should be used. The average installation (if there is such a thing) usually consists of three or four radials (or more) cut for the lowest operating frequency. Such a system should give a good performance.

Another important matter is that of the earth ground. When verticals are mounted at ground level the ground losses can be very important. Too many amateurs buy their verticals, get a 5-foot (1.52-m) long TV-type ground rod and drive it into the earth at the base of the antenna. They think this provides a good ground connection. As a matter of fact, the TV-type ground rods are practically worthless for amateur work. A *good* ground rod is the type used by the power company for home installations. This is a rod that is heavily galvanized, 5/8 inch (16 mm) in diameter, and about 10 feet (3.05 m) long. The amateur should be able to buy these rods from any wholesale electrical supply house. If possible, tie your ground connection to the water-system piping, assuming metal piping is used.

You'll hear the statement from fellow hams that verticals are poor antennas and radiate poorly in all directions. This isn't true, because a vertical *can* by a good antenna, but you have to give it a fighting chance. This material was originally presented in *QST* by Lewis McCoy, W1ICP.

References

[1] Sevick, "The Ground-Image Vertical Antenna" *QST,* July 1971. Also appears elsewhere in this chapter.

[2] A suitable Transmatch is described in the transmission-line chapter of any edition of *The Radio Amateur's Handbook.*

Shunt-Feeding Towers for Operation on the Lower Amateur Frequencies

The 160- and 80-meter DX antenna you've dreamed about may already be standing on your property — just waiting to be used as a DX vertical. Read this presentation and learn how to shunt-feed your tower on 1.8 and 3.5 MHz!

Shunt-feeding a tower used to support beam antennas for 14 MHz or higher frequencies has obvious advantages for the amateur who wants to work all lower bands. If a good ground system is installed, the result may be a very effective antenna for DX work on 80 and 160. The shorter tower installations may work very well on 40 meters, if the effective height above ground is less that 5/8 wavelength. Beyond this height the radiation angle goes higher, and the effectiveness for DX goes down.

The shunt-fed tower is at its best on 160, where a full quarter-wavelength vertical antenna is rarely possible. Almost any tower height can be used. If the beam structure provides some top loading, so much the better — but anything can be made to radiate, if it is fed properly. A self-supporting, aluminum, crank-up, tilt-over tower is used at W5RTQ with a TH6DXX tribander mounted at 70 feet (21.34 m). Measurements showed that the entire structure has about the same properties as a 125-foot (38.10-m) vertical. It thus works quite well on 160 and 80 in DX work requiring low-angle radiation. It can also be used on 40, but results are rather poor because of high radiation angle. WB5FKX, with a 37-foot (11.28-m) tower and a 21-MHz beam, finds that shunt feed on 40 enables him to work DX that he never knew existed before.



Close-up view of the base of the shunt-fed tower, showing the two bottom arms and their insulators.

Preparing the Structure

Usually some work on the tower system must be done before shunt-feeding is tried. Metallic guys should be broken up with insulators. They can be made to simulate top loading, if needed, by judicious placement of the first insulators. Don't overdo it; there is no need to "tune the radiator to resonance" in this way. If the tower is fastened to a house at a point more than about one-fourth of the height of the tower, it may be desirable to insulate the tower from the building. Plexiglas sheet, 1/4-inch (6-mm) or more thick, can be bent to any desired shape for this purpose, if it is heated in an oven and bent while hot.

All cables should be taped tightly to the tower, preferably on the inside, and run down to the ground level. It is not necessary to bond shielded cables to the tower

Table 9

Shunt-Feed Details for Several Towers Used on 160 Meters

Station	*Height of Tower* (ft)	*"Top-Hat"* (Beams)	*Average Height of Beam* (ft)	*Height of Wire-to-Tower Connection* (ft)	*Wire-to-Tower Spacing* (in.)	*Tuned Value of Gamma Capacitor*
W5RTQ	69	TH6DXX	70	68	30	150 pF
K5PFL	86	Stacked 40, 20, 15, 10 M beams	95	75	24	125 pF
K4PUZ	64	TH6DXX	66	63	8	300 pF
K8KAS	70	TH6DXX	77	68	24	225 pF
W1CER	50	QST 20-M DX Weasel	55	47	44	400 pF

1 ft = 0.3048 m
1 in. = 25.4 mm

electrically, but there should be no exceptions to the down-to-the-ground rule.

No rf problems have developed with rotators, beam traps, or even TV sets where the TV antenna is part of the radiating structure, as is the case at WB5FKX. His only precaution was use of coax on the TV antenna. It would be well to proceed with caution, as every installation could be different in this respect.

Though the effects of ground losses are less severe with the shunt-fed vertical than with the simple quarter-wave antenna, a good system of buried radials is very desirable. The ideal would be 120 radials, each 250 feet (76.20 m) long, but fewer and/or shorter ones must often suffice. You can sneak them around corners of houses, along fences or sidewalks, wherever they can be put a few inches under the surface, or even on the earth surface. Aluminum clothesline wire is used extensively at W5RTQ, and it stands up well. Neoprene-covered aluminum wire may be safer in highly acid soils. Contact with the soil is not important. Deep-driven ground rods, and connection to underground copper water pipes, are good, if usable.


CONNECTION TO TOWER
NO. 8 COPPER SPACED 30" (0.76m) MAX. FROM TOWER
80/75-METER FEED WIRE, NO. 8 ALUMINUM SPACED 15"(0.38m) FROM TOWER
STANDOFF INSULATOR
STANDOFF INSULATOR
150-pF VARIABLES
250-pF VARIABLE
BURIED RADIALS CONNECTED TO BASE OF TOWER
COAXIAL FEED

Fig. 33 — Principal details of the shunt-fed tower at W5RTQ. The 160-meter feed, left side, connects to the top of the tower through a horizontal arm of 1-inch (25-mm) diameter aluminum tubing. The other arms have stand-off insulators at their outer ends, made of 1-foot (0.31-m) lengths of plastic water pipe. The connection for 80/75, right, is made similarly, at 28 feet (8.53 m), but two variable capacitors are used, to permit adjustment of matching with large changes in frequency.

Though variable capacitors are shown in Fig. 33, they were all replaced with fixed-value units except one, which is inside a plastic box at the tower base.

Installing the Shunt Feed

Principal details of the shunt-fed tower for 80 and 160 meters are shown in Fig. 33. Rigid rod or tubing can be used for the feed portion, but heavy gauge aluminum or copper wire is easier to work with. Flexible stranded no. 8 copper wire is used for the 160-meter feed at W5RTQ, because when the tower is cranked down, the feed wire must come down with it. Connection is made at the top, 68 feet (20.73 m), through a 4-foot (1.22-m) length of aluminum tubing clamped to the top of the tower, horizontally. The wire is clamped to the tubing at the outer end, and runs down vertically through standoff insulators. These are made by fitting 12-inch (0.31-m) lengths of PVC plastic water pipe over 3-foot (0.91-m) lengths of aluminum tubing. These are clamped to the tower at 15 to 20-foot (4.57 to 6.10-m) intervals, with the bottom one about 3 feet (0.91 m) above ground. The lengths given allow for adjustment of the tower-to-wire spacing over a range of about 12 to 36 inches (0.31 to 91 m), for impedance matching.

The gamma-match capacitor for 160 is a 250-pF variable with about 1/16-inch (1.6-mm) plate spacing, which is adequate for the power levels presently authorized. The omega match used for 80 and 75 permits retuning for large excursions in frequency encountered in using both cw and phone on this band. Two capacitors are required, each about 150 pF, with plate spacing of about 3/16 inch (4.8 mm), if full power is used. They can be mounted in plastic refrigerator containers for protection against the weather. Use well-insulated knobs to avoid rf burns during the adjustment process.

Separate 50-ohm lines run underground to the station. The shield side of their connectors should be grounded to the base of the tower and to the buried radials as directly as possible.

Tuning Procedure

It is suggested that the 160-meter wire be connected to the top of a structure 75 feet (22.86 m) tall or less. Note, from Table 9, that the monster at K5PFL was fed at 75 feet (22.86 m) above ground. Mount the standoff insulators so as to have a spacing of about 24 inches (0.61 m) between wire and tower. Pull the wire taut and clamp it in place at the bottom insulator. Leave a little slack below to permit adjustment of the wire spacing, if necessary.

Adjust the series capacitor in the 160-meter line for minimum reflected power, as indicated on an SWR meter connected between the coax and the connector on the capacitor housing. Make this adjustment at a frequency near the middle of your expected operating range. If a high SWR is indicated, try moving the wire closer to the tower. Just the lower part of the wire need be moved for an indication as to whether reduced spacing is needed. If the SWR drops, move all insulators closer to the tower, and try again. If the SWR goes up, increase the spacing. There will be a practical range of about 12 to 36 inches (0.31 to .91 m). If going down to 12 inches (0.31 m) does not give a low SWR, try connecting the top a bit farther down the tower. If wide spacing does not make it, the omega match shown for 80-meter work should be tried. No adjustment of spacing is needed with the latter arrangement which may be necessary with short towers or installations having little or no top loading.

The two-capacitor arrangement is also useful for working in more than one 25-kHz segment of the 160-meter band. Tune up on the highest frequency, say 1990 kHz, using the single capacitor, making the settings of wire spacing and connection point permanent for this frequency. To move to the lower frequency, say 1810 kHz, connect the second capacitor into the circuit and adjust it for the new frequency. Switching the second capacitor in and out then allows changing from one segment to the other, with no more than a slight retuning of the first capacitor.

The omega match is recommended for 80-meter operation, because of the wide tuning range required. It was found that the point of connection could be at 28 feet (8.53 m), using a single support at the top of the first tower section. This served as a mount for the second standoff insulator for the 160-meter feed, as well.

A 40-meter feed, not shown, was connected at about 20 feet (6.10 m) up, with about 8 inches (203 mm) spacing between wire and tower.

Substituting Fixed-Value Capacitors

Depending on the frequencies used and the matching problems in a given installation, it may be possible to put fixed-value capacitors in place of some or all of the variables shown in Fig. 33, and then switch them remotely, or by hand, when changing frequency. This was done at W5RTQ. The 160-meter gamma capacitor is now a fixed-value, 150-pF type designed for high rf current service. It does not have to be weatherproofed, and it gives a satisfactory match over the small frequency range used on this band.

Two or three similar capacitors connected in series are used in covering the cw and phone frequencies in the 80-meter band. Operation around 3800 kHz requires about 50 pF in the omega (parallel) capacitor, so the three 150-pF units are used in series. Moving to cw operation near 3500 kHz requires about 75 pF, so only two 150-pF capacitors are used in series. The only variable now in the system is the 150-pF capacitor mounted in the plastic refrigerator box at the base of the tower. It is the series or gamma capacitor in the 80-meter feed. Even this could be replaced with a fixed unit, as it has been found unnecessary to adjust it in the course of normal operation of the station, if only small changes in frequency are made in using the two modes.

Because every tower installation is likely to be different from every other one in some respects, the values and dimensions given here may be subject to change, but the general principles should hold. Proof of this was found in the May 1975 issue of *Ham Radio,*[1] wherein W4OQ describes shunt-feeding in very similar terms. He also presented estimates of the electrical height of various tower-beam combinations that prospective shunt-feed users should find of interest.

It is hoped that this information will inspire others to try shunt-feeding their towers. This method offers an effective way to fire up on the lower frequencies that is useful to many who may have wanted to work these amateur frequencies but have shied away from doing so because of limited antenna space. This material was originally presented in *QST* by Earl W. Cunningham, K6SE.

---

[1] True, "Shunt-Fed Vertical Antennas," *Ham Radio,* May 1975.

The Minooka Special

This 160-meter vertical antenna could be just the one for you, if you reside on property of city-lot size or are a mobile operator. You can make it from readily available, inexpensive material.

Inspiration for the design offered here resulted in part from the author's survey of antennas in use by 160-meter operators, worldwide. An extensive report was compiled, which filled a loose-leaf notebook! A boil-down of the most useful information resulted in an 11-page report which was made available to numerous amateurs. Subsequently, the writer was encouraged to submit some of the data for publication. Approximately 60 operators were polled. The following information from that inquiry should be of interest to those who are curious about "preferred" antennas for top-band use.

Question 1: "If you could put up any antenna for 160, what would it be?" *Result:* 60% favored verticals, 30% said horizontals, and 10% indicated mixed feelings. (The term "vertical" includes various configurations — 1/4, 1/2, and 5/8 wavelength, vertical arrays, and inverted Ls.)

Question 2: "Comparing antennas that an average ham could build, do you prefer verticals or horizontals for 160?" *Result:* 70% said vertical, 17% favored horizontal, 5% inverted L, 2% horizontal and vertical, 2% inverted V, and 3% had no opinion. Reasons given for the responses were, "Because of signal comparisons and past experience. A backyard-compatible vertical is more effective than a backyard-compatible horizontal."

Question 3: "Do you operate mobile on 160? If so, what is the antenna used?" *Result:* Three used base-loaded verticals, eight used center-loaded ones, and one employed a Heliwhip. Some of the operators used capacitance hats. Other questions in the survey dealt with receiving antennas, types of soil and terrain, besides requesting complete details of the present transmitting antenna.

Fig. 34 shows some of the vertical systems used when the poll began in 1969. Additional configurations used by successful 160-meter operators are illustrated in Fig. 35. It can be seen that a great deal of useful "backyard theory" is represented in the systems shown. The experience and trials of others can save countless years of experimenting with antennas (not that some of us can't use the exercise)! It is hoped that these data will be of value to future 160-meter operators.

The Minooka Special

The following is a description of an effective vertical antenna for 160 meters, designed with these objectives in mind:

1) Highly effective for 160-meter DX and local work.
2) Easy to build and adjust.
3) Very economical.
4) Fits neatly into back yard.
5) Reasonable bandwidth.
6) Good for portable and DXpedition work.
7) Can be scaled down for mobile operation.

The resultant antenna (Fig. 36) is top loaded inductively and can be built by anyone from readily available material. Only a dip meter and SWR indicator are needed for tune-up. Many versions were built and tested, ranging from 7-foot (2.13-m) mobile types to 60-foot (18.29-m) backyard


137' (41.75m)
FEED
WØAIH
75'(22.86m)
80'
(24.38m)
FEED
K2ANR,
W3IN
33' (10.06m)
W9YYG, W9YYF,
VK5KO, W1BB
FEED
32'
(9.75m)
7'
(2.13m)
K2GNC
W9BKA/8
80'
(24.38m)
FEED
25 WIRES
40'
(12.19m)
W2BP
0.0023µF
FEED
270'
(82.30m)
W1DEO
FEED
55' TO 74'
(16.76-22.56m)
VE3QU, K9DUA,
W1PL, W9OAR,
K8DHT, W9PFT,
W6ITY
FEED
120'
(36.58m)
K1PBW,
W9UCW
MATCHING
INDUCTOR
FEED
137'
(41.75m)
W8GDO, W2IU
0.0015µF
2.9µH
0.0012µF
FEED
110'(33.53m)
K1PBW
1' (0.31m)
25'(7.62m)
500pF
270pF
FEED
MINOOKA
HF BEAM
WA9EYY
60'
(18.29m)
6' (1.83m)
SPACING
GAMMA
MATCH
FEED
= GROUND
SYSTEM
= CAPACITANCE HAT

Fig. 34 — Illustrations of vertically polarized 160-meter antennas used by various operators for DX and local work. L and C values are not specified in some of the examples because the data were not furnished by the users.

Table 10

	No. 1	No. 2	No. 3	No. 4	No. 5	No. 6
X	5 ft (1.52 m)	8 ft (2.43 m)	4 ft (1.22 m)	4 ft (1.22 m)	19 ft (5.79 m)	3 ft 3 in. (0.99 m)
Y	2 ft (0.61 m)	15 in. (381 mm)	3 ft 6 in. (1.07 m)	4 ft (1.22 m)	11 in. (279 mm)	3 ft (0.91 m)
Z	As long as possible					
Wire Size	No. 20	No. 19	No. 18	No. 16	No. 19	No. 22

Here is a 50-foot (15.24-m) version of the Minooka Special. It is tuned remotely at K9SKX, and is used on 160 through 20 meters. Nylon or polypropylene guy lines should be used.

or DXpedition models. They have been used with good results from 20-foot (6.10-m)-wide backyards in cluttered Chicago, to vast beaches on Carribean islands, and in South America. The fixed-tuned bandwidths vary from 10 kHz for mobile versions, to 50 kHz for the larger fixed-station models (SWR 2:1 or better).

Construction

The physical layout of the antenna is centered around the use of 3/4-inch (19-mm) diameter rigid PVC water pipe. This sturdy tubing has an outside diameter of 1 inch (25 mm). The inner diameter provides an "interference fit" for 1/2-inch (13-mm) EMT conduit (thinwall). A 3/8-24 nut is driven into a 5-inch (127-mm) length of conduit, then aligned and braized into position. Next, the conduit is taper-ground and polished on the opposite end, then driven into the PVC tubing (see table of dimensions).

In the construction of mobile antennas another piece of conduit is driven into the bottom of the PVC coil form and a 3/8-24 bolt is brazed into the bottom end. The bolt will mate with standard mobile antenna mounts. For larger versions of the antenna the PVC material can be mounted in TV masting, or whatever. A standard 8-foot (2.44-m) stainless-steel whip between 3 and 8 feet (0.91 and 2.44 m) in length can be screwed into the top section. For home-installed versions of the antenna a



Close-up view of the top section of a coil assembly. This unit was used during mobile operation for over three years (40,000 miles or 64,374 km).

A mobile version of the Minooka Special is shown mounted on the author's car.


70' (21.34m)
50' TO 100' (15.24-30.48m)
70' (21.34m)
K8RRH
70' (21.34m)
FEED
70' (21.34m)
K8CRJ
70' (21.34m)
FEED
INVERTED U
1/4 λ
AS MUCH AS POSS.
W1BB, W8KFX
FEED
150' (45.72m)
50' (15.24m)
W1FB/W1CKK
250pF
200pF
28μH
FEED
200pF
130'(39.62m) RADIALS BURIED
INVERTED L
1/4 λ
W6JHO, W8GDQ, K8RRH
FEED
INVERTED L (FOLDED UNIPOLE)
67'(20.42m)
335' (102.11m)
67'(20.42m)
67'(20.42m)
W9PNE
FEED
OFF-CENTER-FED HORIZONTAL

Fig. 35 — Examples of additional antennas for 160 meters which proved effective for long-haul work.



A portable version of the 160-meter vertical antenna. It was used by W9YYG and W9UCW at HK0BKX in January 1974.

3- or 4-foot (0.91- or 22-m) piece of thin-wall tubing can be used in place of the whip. This will save on the cost of materials, and will eliminate the need to have brazing done. The coil wire should be soldered to the conduit to assure a good electrical connection.

Adjustment

Pick a set of dimensions from the table which suits your application, but add a few inches more of coil turns (all turns close wound) than are recommended. This will allow leeway for pruning the system to resonance.

To simplify adjustment it is suggested that the system be assembled first with only the coil and top section (no base section). Place the antenna where it is in the clear (on the car or fixed-station site), and where it can be tuned against the proposed ground system — car body or ground radials.

A three-turn link should be connected temporarily between the lower end of the coil and the ground system. This will permit rough tuning of the system to resonance by inserting a dipper coil into the link and adjusting the coil turns on the antenna until a dip is noted in the desired part of the band. Upon completion of the pruning the constructor can, if he wishes, cover the coil with weatherproof tape or shrink tubing. The antenna should be tuned for roughly 2000 kHz if the entire band is to be used. Adjust the resonance for 1850 kHz if only the low segment will be utilized.



Fig. 36 — Electrical details of the Minooka Special. Table 10 gives specific information concerning dimensions X, Y and Z. L2 may vary in size from 1 to 20 turns, and L3 will contain between 5 and 10 turns, typically. L2 and L3 are made from no. 18 wire, spaced 1/8 inch (3 mm) between turns. The coil diameter is 1-1/2 inches (38 mm). Refer to text for tuning instructions.

Erect the antenna with all of its parts — coil, top and bottom section — and insert inductors L2 and L3 of Fig. 36 as shown. With L3 temporarily out of the system, adjust L2 for the lowerest value of SWR obtainable at the desired operating frequency. Then, place L3 back in the circuit and adjust it for an SWR reading of 1. Addition of the base section later on will not affect the resonant frequency of the overall system materially, provided the base section does not exceed, say, 60 feet (18.29 m).

The foregoing steps are used also in adjusting the mobile version of the antenna. However, because of the small size it is possible to adjust the antenna in completely assembled form. Only L3 of Fig. 36 is needed for mobile antennas. The main coil, L1, is adjusted for resonance, then L3 is set for lowest SWR. L3 can be mounted inside the trunk or under the bumper in a weatherproof enclosure.

For fixed-station operation it is recommended that a good ground system be employed. One should use at least 10 radials of, say, no. 18 or larger wire, 10 to 50 feet (3.05 to 15.24 m) in length. If you can manage 40 radials, 60 feet (18.29 m) in length, all the better.[1]

Concluding Comments

Three fixed-station versions of the Minooka Special have been tested and used at W9UCW. Each was compared against the regular antenna, which is a one-quarter wavelength vertical (130 feet [39.62 m] high), and operates against a radial system that contains 12,000 feet (3657.6 m) of wire. The short verticals were always inferior to the big antenna by approximately 5 dB.

Using version no. 4 from the table (4-foot [1.22-m] base section), the author worked W1s through W6s from the mobile setup. The rig was an HW-18 transceiver. Contacts were also made with VP9 and KV4 stations from the car.

While DXing from San Andres (HK0) reports were received of signal strengths exceeding S9 plus 20 dB from Maine to Washington. Good reports were received from Europe also.

Because the loading coil acts as an rf choke at 3.5 MHz and above, several versions of the antenna have been used successfully from 160 through 20 meters with an appropriate L-network matching section installed at the base of the system.

Acknowledgements

The author wishes to express his gratitude to all who helped make this article possible, . . . particularly K9SKX, WA9EYY, and W9YYF, who assisted with the initial experiments on the Minooka Special. The participants in the antenna survey (a list too large to include here) deserve considerable thanks for their help as well. This material was originally presented in *QST* by Barry A. Boothe, W9UCW.

[1] [Editor's Note: The reader should be aware that 1/4-wavelength radials (or longer ones) are recommended for best efficiency in a system of this kind. Detailed information on the subject is given in *The ARRL Antenna Book*, 13th Edition. The recommendations given by the author are no doubt based on the lack of space available in the typical urban lot, around which his design was established. See Hills, "The Grounds Beneath Us." *RSGB Bulletin*, June 1966.]

Inexpensive 5/8-Wave Vertical Antenna with Coaxial Transformer

The author's hastily constructed 5/8-wave vertical antenna (inspired by W0JF's results[1]) consists of a supporting structure made from sections of 2 × 2-inch (51 × 51-mm) lumber on which four lengths of 300-ohm TV ribbon are affixed. Each section of ribbon line is 41 feet 6 inches (12.65 m) long. A length of this line is attached to each side surface of the 2 × 2 support mast, then the ends (top and bottom) of all four line sections are connected in parallel to form a single vertical conductor. The coax-line dimensions are near those of W2JTJ,[2] and are shown in Fig. 37. The SWR varies from a flicker of reflected power at 14,000 kHz to 1.5:1 at 14,350 kHz. (The next task is to get that lowest-SWR point shifted to 14,275 kHz.) The whole thing is leaning against a tree, almost vertical, and seems to work well. This material was originally presented in *QST* by Robert J. Earl, W1DRV.



Fig. 37 — Coax-line transformer for 20-meter 5/8-wave vertical antenna.

References

[1] Beers, "Short Antennas for the Lower Frequencies," *QST*, August and September 1970.
[2] Czerwinski, "Coaxial Transformer for Voltage-Fed Antennas," *QST*, June 1961.

A Backyard 160-Meter Vertical

A 160-meter band was the favorite one at the author's QTH this winter. The same could be said for many other amateurs and the simple antenna described here may be of interest.

Some of the old-timers will tell the newcomer to 160 meters that the best antenna for local and DX work is the vertical. Since a full-size vertical would be very large, the question is finding a type that will fit into a closely packed residential area.

As a starter, the writer took an old 40-foot (12.19-m) telescoping mast and insulated it from the ground. (This can be done by setting it on top of a large soft-drink bottle, or clamping it to a wooden post.) The antenna was fed at the base with RG-58A/U 52-ohm coaxial cable. The shield was wired to a radial system and a ground rod. A hint for the radials — buy some aluminum clothesline and cut a number of slits in your yard with a flat spade. Next, push the wire into the slits and tamp the grass back together. If there are any swampy parts of the yard, these seem to make the best ground areas.


50'(15.24m)WIRES
VERTICAL ELEMENT 40' (12.19m) MAST OR TOWER
INSULATORS AND ANCHOR POSTS OR TREES
RG-58A/U
RADIAL GROUND SYSTEM
SHIELD TO GROUND
GROUND ROD

Fig. 38 — A space-saving vertical for 160 meters. While not always possible, it is desirable to have the wires for the top hat run off at right angles to the mast.

Rather than using a loading network at the base of the antenna, the author constructed a capacitive hat to load it at the top instead. The top hat was made from four 50-foot (15.24-m) pieces of wire strung out from the top of the mast in guy-wire fashion. They are connected electrically to the top, and stretched until they are as close as possible to a 90-degree angle with respect to the mast.

The system described works well with a 40-foot (12.19-m) mast, but other lengths could be used instead. However, the top hat may have to be adjusted in order to bring the system to resonance. While my vertical occupies very little space, it seems to perform as well as do many "full-size" antennas on 160 meters. This material was originally presented in *QST* by Mike Mussler, WB8JJA.

Chapter 2

Yagi Antennas

The antenna systems treated in this chapter are variations of the basic directional gain antenna devised many years ago by Yagi and Uda. Over the years the fundamental design and its variations have been referred to simply as the Yagi. How Mr. Uda was excluded from the credits remains a mystery, as he was a co-developer of the antenna under discussion.

Yagi types of antennas appeal to all manner of hf- vhf- and uhf-band operators. The primary response characteristic of the Yagi is unidirectional, discounting minor response lobes off the front, sides and rear of the antenna. The major lobe concentrates the radiated energy in a desired direction to provide gain in dB and discrimination against interference from unwanted directions.

Yagis can be used singly or in array combinations. In the latter case, each time the size of an array is doubled the system gain can be made to increase by 3 dB — assuming that the phasing, impedance matching, and aperture parameters are correct. Thus, a pair of 3-element Yagis which are "stacked" in an array to meet the foregoing criteria will exhibit 3 dB more gain than a single 3-element Yagi. To effect another 3 dB increase in gain, four 3-element Yagis would need to be placed in a given array of Yagis, and so on.

This chapter deals with the cream of the Yagi crop, so to speak, as taken from past issues of *QST*. When zoning laws and available property permit, the Yagi is preferred over the single-element vertical antennas described in chapter 1.

The 20-Meter DX Weasel

Short antennas have always captured the interest of amateurs.

The antenna presented here is a monoband version of the Bite-Size Beam for 20 and 15 meters published elsewhere in this chapter. It is designed for 20-meter operation only. Most of the parts were "lifted" from the original array.

The reader is cautioned against attempting to figure why some of the dimensions were selected. As a point of interest, they just happened that way. One new twist was added to this system — capacitance hats. The hats provided one noticeable improvement in performance which became obvious during the initial tune-up phase of the project. The hats lowered the Q of the elements and hence broadened the overall response of the system. While only conjecture, one might say that it is this broad tuning which causes the parasitic elements to perform as they do. Element tuning on the Bite-Size Beam[1] was critical. If the dimensions given here are followed carefully, the antenna should provide excellent characteristics for gain and pattern. Front-to-back measurements indicate approximately 20 dB. The front-to-side ratio was measured in excess of 25 dB. There are no objectionable side lobes. The SWR is less than 2:1 at each end of the band when the gamma capacitor and rod are set for proper operation at 14.1 MHz. There is no need to select phone or cw as the primary mode of operation.



Details of the loading coil and capacitance hat on one of the elements.

Construction

The boom and all the elements are made from 1-1/4-inch (32-mm) diameter aluminum tubing available at most hardware stores. The two boom sections and the two pieces which make up the center portion of the driven element are coupled using 15-inch (0.38-m) sleeves of 1-3/8-inch (35-mm) OD aluminum tubing. Sheet-metal screws should be used to secure the sections within the coupling sleeves.

The loading coils are wound on 1-1/8-inch (29-mm) diameter Plexiglas rod. Details are shown in Fig. 1. Be sure to slit the ends of the aluminum tubing where the compression clamps are placed. The coils are made from no. 14 enameled wire. The specified number of turns are equally spaced to cover the entire 9 inches (229 mm) of Plexiglas.



Fig. 1 — Details for joining sections of aluminum tubing and Plexiglas rod.

The capacitance hats are constructed from 3/4-inch (19-mm) angle aluminum. Two pieces 2 feet (0.61 m) in length are required for each hat. The model shown in the diagrams has the angle aluminum



Fig. 2 — Constructional details for the 20-meter beam. The coils on each side of the element are identical. The gamma capacitor is a 140-pF variable unit manufactured by E. F. Johnson Co.

fastened to the element using aluminum strips and no. 8 sheet-metal screws, but sheet-metal screws alone can be used. Solder lugs are fastened to the ends of the angle aluminum and no. 12 or 14 wire connects the ends of the aluminum, resulting in a square loop. The wires should be soldered at each of the solder lugs.

All of the elements are secured to the boom with TV U-bolt hardware. Plated bolts are desirable to prevent rust from forming. An aluminum plate 9 inches (229 mm) square by 1/4-inch (6-mm) thick was used as the boom-to-mast plate.

A boom strut is recommended because the weight of the elements is sufficient to cause the boom to sag. A 1/8-inch (3-mm) diameter nylon line is plenty strong. A U-bolt clamp is placed on the mast several feet above the antenna and provides the attachment point for the center of the truss line. To reduce the possibility of water accumulating in the element tubing and subsequently freezing, crutch caps are placed over the ends. Rubber feet suitable for keeping furniture from scratching hardwood floors would serve the same purpose.

A piece of Plexiglas was mounted inside an aluminum Minibox to provide support and insulation for the gamma capacitor. A plastic refrigerator box would serve the purpose just as well. The capacitor housing is mounted to the boom by means of a U bolt. The gamma rod is made of 3/8-inch (10-mm) aluminum 40 inches (1.016 m) long and is connected to the gamma capacitor by a 6-inch (152-mm) length of strap aluminum.

Tune-Up and Operation

Table 1

Complete Parts List for the Short Beam

Qty	*Material*
2	10-foot (3.05-m) lengths of 1-1/4-inch (32-mm) dia. aluminum tubing (one for the reflector center section, one for the reflector end sections).
3	8-foot (2.44-m) lengths of 1-1/4-inch (32-mm) dia. aluminum tubing (two lengths for the boom, one length for the director element center).
4	6-foot (1.83-m) lengths of 1-1/4-inch (32-mm) dia. aluminum tubing (two lengths for the driven element center, two lengths for the director and driven element ends).
2	15-inch (0.38-m) lengths of 1-5/8-inch (41-mm) dia. aluminum tubing.
1	40-inch (12.19-m) length of 1-3/8-inch (10-mm) dia. aluminum tubing.
4	6-foot (1.83-m) lengths of 3/4-inch (19-mm) angle aluminum.
6	12-inch (0.31-m) lengths of 1-1/8-inch (29-mm) dia. Plexiglas rod.
1	9-inch (229-mm) square, 1/4-inch (6-mm) thick aluminum plate.
8	U bolts.
12	Compression hose clamps.
8	Crutch caps.
38 ft	No. 12 enameled copper wire.
60 ft	No. 14 enameled copper wire.

The builder is encouraged to follow the dimensions given in Fig. 2 as a starting point for the position of the gamma rod shorting strap. Connect the coaxial cable and install the antenna near or at the top of the tower. The gamma capacitor should be adjusted for minimum SWR at 14.1 MHz as indicated by an SWR meter (or power meter) connected in the feed line at the gamma capacitor box. If a perfect match cannot be obtained, a slight repositioning of the gamma short might be required.

Evaluation of performance is always a difficult task. The 20-Meter DX Weasel is mounted on top of a 50-foot (15.24-m) high tower at the QTH of W1FB. The transmitter input power for the testing period was 3 watts. Many European stations as well as a ZL have been contacted with ease. In fact, the Weasel has been responsible for cracking a few pileups on the first call!

Obtaining the Material

Table 1 lists all of the major parts used in the 20-meter Weasel. Most of the U-bolt hardware as well as the aluminum tubing should be available from large hardware stores. The Plexiglas rod, however, presents a bit more of a problem as indicated by mail received by the ARRL Technical Department. Many large plastic supply dealers stock the cast rod. The problem is that there are not very many large dealers! Additionally, Plexiglas is a petroleum-base product which means the cost is no doubt higher than one would expect. Those amateurs who are unable to locate aluminum hardware or Plexiglas should consult the yellow pages to see who their nearest supplier is. This material was originally presented in *QST* by Robert Myers, W1XT and Jay Rusgrove, W1VD.

[1] See page 45.

The HW-40 Micro Beam

A helically wound 2-element 40-meter Yagi.

Disconsolate pleas from apartment dwellers and other amateurs who live on property that is too small in area to permit the use of large 40-meter antennas prompted the authors to develop the antenna described here. The particular dimensions represented in this design were dictated primarily by the kind of fiberglass tubing that was immediately available. Kirk quad spreaders were obtained for use as forms on which to wind the helical elements. Longer (or shorter) elements can be used with good results. This article is intended as a guide in the design of similar antennas.

The HW-40 is scaled down to 28 percent of full size. Two elements are used, each being 18 feet (5.49 m) in length, tip-to-tip. Thus, the elements are just 2 feet (0.61 m) longer than those of a full-size 10-meter Yagi. A 16-foot (4.88-m)-long Reynolds aluminum-tubing boom (two 8-foot [2.44-m] lengths joined) provides 0.12-wavelength spacing between the driven element and reflector. The weight of the array is approximately 25 pounds, making it practical to use a TV-type antenna rotator with the system.

Design Considerations

Some may argue that helically wound antennas will tend to radiate off the ends of the elements (axial mode), and that the condition will prevent the Yagi from exhibiting normal front-to-side and front-to-back characteristics. It was established by Kraus,[1] that axial-mode radiation occurs only when a helix is one wavelength or greater in circumference. Generally, when the circumference is less than two-thirds wavelength, a nearly sinusoidal type of current distribution exists. This is effected by alternate reinforcement and cancellation of the two traveling waves which are directed oppositely. Each is of nearly identical current amplitude (I_0), hence the T_0 transmission mode results for both traveling waves on the helix. Because of the foregoing condition the helices of this antenna radiate in the *normal mode* and will exhibit linear polarization characteristics. The diameter of these helices is merely 0.0009469 wavelength, eliminating any opportunity for axial-mode radiation. Front-to-side and front-to-back checks of the beam indicate, indeed, that normal-mode radiation is occurring. A number of relative tests were performed locally at distances up to 20 miles, and the front-to-back characteristics indicate a 10-dB figure. Front-to-side checks confirm a figure of approximately 28 dB. The effect is not so pronounced when receiving high-angle incoming signals. Depending upon the time of day, distance involved, and other propagation factors, various directivity traits will be observed.

The HW-40 beam, just 28 percent of full-size, is light enough to require only a TV-rotator.

Helically wound elements were chosen in preference to lumped-inductance elements in order to obtain linear voltage and current distribution across the elements, and to make the matching technique less difficult. Even if end-loaded elements with capacitance hats were used, the 18-foot (5.49-m) dimension would make it impossible to use. a gamma match of conventional design. Because of the very low value of radiation resistance of short loaded antennas, other conventional matching schemes would not lend ease to matching a 50-ohm coaxial feeder to the system.

There are certain penalties one must accept when using physically shortened antennas of this kind, and an in-depth treatment of the subject was given by Sevick in *QST*.[2] It was a fortunate circumstance in this case that the feed-point impedance of the beam turned out to be approximately 12 ohms. Therefore, a 4:1 toroidal balun was installed at the feed point to provide a near-perfect match to the 50-ohm transmission line. In addition to encountering low values of feed impedance, the bandwidth of loaded elements is greatly less than with full-size antennas. This beam was tuned for operation at a center frequency of 7050 kHz. It works well from 7025 to 7075 kHz, with an SWR no greater than 2:1. It is flat at 7050 kHz. Those wishing to duplicate this Yagi should be willing to accept this design tradeoff in the interest of having an effective directional antenna. It is recommended, therefore, that it be tuned for one's favorite part of the 40-meter band. The use of a Transmatch will, however, permit excursions into portions of the band where the SWR becomes greater than 1:1.

Construction Details

The construction of the 40-meter beam is very simple and requires no special tools or hardware. Two fiberglass 15-meter quad arm spreaders are mounted on an aluminum plate with U bolts, as shown in the photograph. A wooden dowel is inserted approximately 6 inches (152 mm) in the end of each fiberglass arm to prevent the U bolts from crushing the poles. The aluminum mounting plate is equipped with U-bolt hardware for attachment to the 1-1/4-inch (32-mm) diameter boom.

A plastic refrigerator box is mounted on each element support plate and is used to house a Miniductor coil. No. 14 copper wire is used for the elements. The wire is wound directly on the fiberglass poles at a density of *40 turns per foot* (not turns per inch!) for a total of 360 evenly spaced turns. The wire is attached at each end with an automotive hose clamp of the proper size to fit the fiberglass rods. Since the fiberglass is tapered, care must be taken to keep the turns from sliding in the direction of the tips. Several pieces of plastic electrical tape were wrapped around the pole and wire at intervals of 1 foot (0.31 m). All of the element half sections are identical in terms of wire and pitch. Coil dimensions and type are given in Fig. 3.

The driven-element matching system consists of a 4:1 balun transformer and a link tightly coupled to the Miniductor. Complete details are given in Fig. 4.

Mounted at the end of each element (held in place by the hose clamp) is a short section of stiff copper wire used to allow for final tuning of the system as well as to broaden the frequency response of the antenna. Since the overall antenna is very small in relation to a full-sized array, the SWR points of 2:1 are rather close to each other, as mentioned earlier. The antenna shown in the photograph provides an SWR of less than 2:1 within about 25 kHz either side of resonance. Tuning the antenna for phone-band operation should not be difficult and the procedure outlined below should be suitable.

Tuning

The parasitic element is adjusted to be about four percent lower in frequency than


TOP VIEW
2-ELEMENT 40-M HELICAL BEAM
DRIVEN ELEMENT
10"
(254mm)
9'
(2.74m)
12"
(0.31m)
6"
(152mm)
1/4" ALUMINUM PLATE
(6mm)
19T
9'
(2.74m)
10"
(254mm)
1" HOSE CLAMPS
(25mm)
WOODEN DOWELS
1" HOSE CLAMPS
(25mm)
U BOLTS
L
1:4
50-239
ALUMINUM WELDING ROD
SEE FIG. 2 FOR DETAILS
ELEMENT-TO-BOOM FIXTURE
1"(25mm) HOSE CLAMP
TAPERED FIBERGLASS ELEMENT AND WINDING (40 TURNS PER FOOT)
12 T LINK
PLASTIC REFRIGERATOR BOX
BOOM 2-8'x1-1/4" (2.44 x 32mm) PIECES OF ALUMINUM TUBING
15'8" (4.78m)
MAST AND U BOLTS
BOOM-TO-MAST FIXTURE
PLASTIC REFRIGERATOR BOX
REFLECTOR
U BOLTS
9'
(2.74m)
B&W 3025
9'
(2.74m)
8"
(203mm)
1" HOSE CLAMP
(25mm)
24T
U BOLTS
8"
(203mm)
WOODEN DOWELS
1" HOSE CLAMP
(25mm)
1" HOSE CLAMP
(25mm)
1" HOSE CLAMP
(25mm)
3"
(76mm)
6"
(152mm)
3"
(76mm)

Fig. 3 — Overall dimensions for the 40-meter short beam. The boom consists of two pieces of standard 1-1/4-inch (32-mm) dia do-it-yourself aluminum tubing.


10 TURNS NO.14 BIFILAR WINDING ON TOROIDAL CORE
1:4 BALUN
50Ω
NO.14 PLASTIC COVERED 12T LINK
PLASTIC REFRIGERATOR BOX
U BOLT
19T
B&W 3025
1"(25mm) HOSE CLAMP
1" HOSE CLAMP (25mm)
1/4"(6mm) ALUMINUM PLATE
TAPERED FIBERGLASS ELEMENT AND WINDING (40 TURNS PER FOOT-NO.14)
1" (25mm) WOODEN DOWEL
1" (25mm) WOODEN DOWEL
BOOM AND U BOLT
FRONT VIEW OF DRIVEN ELEMENT
(2-ELEMENT 40-M HELICAL BEAM)

Fig. 4 — Schematic diagram of the balun assembly mounted inside the plastic utility box. The core is a single T-200-2 Amidon. The 12-turn link is wound directly over the 19-turn Miniductor.

the driven element. A grid-dip oscillator was coupled to the center loading coil and the element tips were trimmed (a quarter of an inch [6 mm] at a time!) until the GDO indicated resonance to be at 6.678 MHz. For phone-band use, the ends could be snipped for 6.840 MHz. Adjusting the driven element is simple. Place an SWR meter or power meter at the input connector and cut the end wires (or add some if necessary) to obtain a proper match between line and antenna.

Performance Characteristics

Once the initial near-ground tuning of the elements was completed, the HW-40 was carried aloft and mounted on the 40-foot (12.19-m) tower at W1FB. Final touching up of the matching and element resonances was effected after the beam was in place on the tower. It is important to realize that shortened antennas are sensitive to changes in environment because of their narrow-band characteristics. Thus, height above ground and distance from nearby objects will cause some change in resonance of the elements. The resonant frequency of the HW-40 changed some 150 kHz between tuning at several feet above ground to final tweaking atop the tower.

It should be noted that the 40-meter beam has yet to be tested at an ideal height above ground. A distance of 40 feet (12.19 m) above the earth is not much more than one-quarter wavelength at 7 MHz, though performance thus far has been better than one might expect when using a beam or dipole less than one-half wavelength above ground.

Comparisons were made between the beam and three types of wire antennas . . . an inverted V, a 3/4-wavelength end-fed wire, and a full-wave 40-meter loop (with its theoretical 2-dB gain).[3] The results have been interesting, though at times rather confusing. The confusion results from the time-of-day/propagation syndrome mentioned earlier. At no time, however, did the inverted-V or 3/4-wavelength antennas surpass the performance of the HW-40. The beam was always as good as or better than the other two radiators, regardless of band conditions or time. During contacts with European or South American DX stations, the beam was always the best antenna, usually by two S units or more. During daytime contacts out to, say, 1000 miles, the wire antennas equalled the beam at times.

When comparing the beam to the full-wave loop, results became less easy to evaluate. That is, the antennas took turns being best. Frequently, the loop outperformed the beam (in the favored direction of the loop) both on short-haul and DX contacts. At other times the beam had the edge by a couple of S units. At this time it is impossible to say which antenna would provide the best all-year, all-around service. But, it has been observed that the beam is far less subject to pickup of man-made and atmospheric noise because of its narrow-band characteristics (the loop exhibits the opposite bandwidth trait— broad). Reduction in noise during reception can be a blessing, especially when working with the weaker signals! Another beneficial effect of the narrow-band feature is that strong, near-frequency signals do not so severely affect the receiver with respect to overloading and cross modulation, as is the situation with other types of antennas. The proof of this came when trying to operate while W1AW (two blocks away from W1FB) was transmitting code practice. Until the beam was erected it was impossible to use the 40-meter band, but with the beam connected to the receiver, and with the antenna pointed away from W1AW, it became possible to operate within 10 kHz of W1AW without knowing that station was on the air! So, if some kW operator lives down the street from you, this little beam could put you back in business.

While running approximately 80 watts output, the short beam has been extremely effective in working DX. DX stations now answer our CQs, whereas with the wire antennas (loop excepted) this seldom happened. Signal reports from DX stations average 579, with many 589 and 599 reports. During QRP operation with the beam (2 watts output), a number of DX stations have been raised and worked. The signal reports are lower of course, but RST 559 and 569 indicates that something good must be happening! One unrelated event occurred while testing the beam and loop with the QRP setup: a station in the 4th call area called CQ and was answered. He came back and said, "No QRP lids, CQ kWs only." It's unlikely that the HW-40 beam can be blamed for that, especially since we went on to work five European stations later that day with the 2-watt equipment!

Acknowledgements

The authors wish to express gratitude to those who helped construct, test and erect the 40-meter beam. Special thanks to K1JX, who "clomped" up and down the ARRL test tower and the W1FB station tower numerous times with test gear (and the beam) until the final design goals were met. Thanks also to W1NPG (SK) who labored silently while winding the helices, and subsequently endured the unbearable Connecticut heat-wave temperatures of August, while putting two coats of exterior spar varnish on the completed elements. The element dimensions and turns information were developed by K1TD to test a newly developed calculator program. This material was originally presented in *QST* by Robert Myers, W1XT and Doug DeMaw, W1FB.

References

[1] Kraus, *Antennas*, First Edition, McGraw-Hill Book Co., Chapter 7.
[2] Sevick, "The Ground-Mounted Short Vertical," *QST*, March 1973, p. 13. (See Chapter 1.)
[3] DeMaw, "The Novi-Loop," *QST*, October 1973. (See Chapter 4.)

A Bite-Size Beam for 20 and 15 Meters

Do you want to work DX from your space-restricted QTH with increased effectiveness? If the answer is yes, perhaps this two-band Yagi system is just the one for you.

There is no doubt that a hundred-foot (30.48-m) tower with stacked monobanders for 20 and 15 meters is one way to generate an effective signal in the pileups. But what are the characteristics of this big system which make it perform better than a dipole strung between two trees? First, the tall tower places the antenna up in the clear, away from most of the surrounding ground clutter. Even a relatively short tower (40-foot [12.2-m] variety) provides this advantage in many instances. The ability to point the major radiation lobe of the antenna in the correct direction is another reason the high monobanders outperform the kinky wire. But if the antenna is capable of supporting its own elements, the directional characteristics can be used to good advantage whether the beam is mounted at 100 feet (30.5 m), or at 40 feet (12.2 m). And without any question, the ability to reject interference aids substantially in the reception of weak signals.

A typical one-foot (0.31-m)-per-side triangle tower is self-supporting (when properly installed) to 40 feet in height and requires less than one square foot of property. For many amateurs, the major limiting factor is the inability to turn a monoband beam (or even a large tribander) without hitting some object like a tall tree. Hesitation on behalf of the amateur to place what might be considered by his neighbors an offensive amount of hardware in the sky near his home is another reason beams are ruled out. The 2-element-per-band, 20- and 15-meter, interlaced Yagi presented here, overcomes these problems. It is lightweight and is less than 16-feet (4.88-m) square. And it's probably no more obtrusive than a large TV antenna.

So What if It's Short!

A popular misconception among amateurs is that any element short of full size is no good in an antenna system. Reducing the size of an antenna by 50 percent does lower the efficiency by a decibel or two, but the gain capability of a parasitic array outweighs this small loss in efficiency. Mounting the antenna above the interference-generating neighborhood can greatly reduce susceptibility to man-made noise and certainly aids in the reduction of rf heating to trees, telephone poles, and buildings. It has been said that a brick wall, or dense foliage, can attenuate a signal passed through it by as much as 20 dB. Placing the antenna above these energy-absorbing objects is very desirable.

The coils are wound on Plexiglas rod. Compression clamps are used to hold the Plexiglas in position Sheet-metal screws and solder lugs provide attachment points for the ends of the loading coils.

View of the short beam from the front yard at W1FB.



The gamma assembly is held in place by means of a small U bolt. The capacitors are mounted on etched circuit board.

It is a generally accepted fact that traps are difficult to build and adjust, as well as their being lossy. Loading coils, on the other hand, are easy to wind and require essentially no adjustment. If the wire size is large, losses are not a major factor. W2FMI lauded the merits of short antennas in an earlier article explaining that in reality, short (50 percent) elements do not materially depreciate the gain.[1] With these ideas in mind, the authors designed and built a shortened-element, but wide spaced, director array for 20 meters interlaced with a similar 15-meter reflector configuration also having optimum spacing for maximum gain. By placing the 15-meter driven element in front of the 20-meter array, the longer 20-meter elements tend to act as reflectors on 15 meters. There are no unwanted reflectors "in front" nor any directors "behind" the active array — elements which could cause pattern distortion and poor front-to-back ratio.

Construction

The dual-band beam has four elements, the longest of which is 16 feet (4.88 m). All of the elements and the boom are made from 1-1/4-inch (32-mm) diameter aluminum tubing available at most hardware stores. Element sections and boom pieces are joined together by slotting a 10-inch (254-mm) length of 1-1/4-inch (32-mm) tubing with a nibbling tool and compressing it for a snug fit inside the element and boom tubing. Coupling details are shown in Fig. 6.

The loading coils are wound on 1-1/8-inch (29-mm) diameter Plexiglas rod. The rod slips into the element tubing and is held in place with compression clamps. Be sure to slit the end of the aluminum where the compression clamps are placed. The model shown in the photographs has coils made of surplus Teflon-insulated miniature audio coaxial cable with the shield braid and inner conductor shorted together. A suitable substitute would be no. 14 enameled copper wire wound to the same dimensions as those given in Fig. 5.

All of the elements are secured to the boom with common TV U-bolt hardware. Plated bolts are desirable to prevent rust from forming. A 1/4-inch (6-mm) thick boom-to-mast plate is constructed from a few pieces of sheet aluminum cut into 10-inch (254-mm) square sheets and held together with no. 8 hardware. Several cookie tins could be used if sheet aluminum is not available. One local amateur used a plate from a large electrical box as a boom-to-mast bracket. Since it is galvanized, it is quite resistant to the harsh New England winters.

A boom strut (sometimes called a truss) is recommended because the weight of the elements is sufficient to cause the boom to sag a bit. A 1/8-inch (3-mm) diameter nylon line is plenty strong. A U-bolt clamp is


RES. FREQ. 14.050 MHz
RES. FREQ. 20.0 MHz
RES. FREQ. 14.7 MHz
RES. FREQ. 21.050 MHz
30.5 TURNS
16.5 TURNS
23 TURNS
19 TURNS
20-METER DRIVEN ELEMENT
15-METER REFLECTOR
4' (1.22m)
3" (0.91 mm)
15-METER DRIVEN ELEMENT
COAXIAL CABLE
20-METER GAMMA CAPACITOR BOX
20-METER DIRECTOR
MAST PLATE
15-METER GAMMA CAPACITOR BOX
6' (1.83m)
3" (0.91 mm)
5-1/2' (1.68m)
4' (1.22m)
4' (1.22m)
4' (1.22m)
3' (0.91m)
3' (0.91m)
2' (0.61m)
2' (0.61m)
6' (1.83m)
9' (2.74m)
15' (4.57m)
(A)
ADJOINING 1-1/4" (32mm) STOCK
1/4-INCH (6mm) SLOT IN 1-1/4" (32mm) SHORT SECTION OF TUBING
(B)

Fig. 5 — Constructional details for the 20- and 15-meter beam. The coils for each side of the element are identical. The gamma capacitors are each 140-pF variable units manufactured by E. F. Johnson Co. The capacitors are insulated from ground within the container. Since the design is one-half size for each band, the tuning is somewhat critical. The builder is encouraged to follow carefully the dimensions given in the text.

Table 2

Complete Parts List for the Short Beam

Qty	*Material*
9	8-foot (2.44-m) lengths of aluminum tubing, 1-1/4-in. (32 mm) dia
11	U bolts
2	Variable capacitors, 140 pF (E. F. Johnson)
4 ft	Plexiglas cast rod, 1-1/8-in. (29 mm) dia
16	Stainless steel hose clamps, 1-1/2-in. (38 mm) dia
1	Aluminum plate, 8-in. (203 mm) square
10 ft	Aluminum solid rod, 1/4-in. (6 mm) dia
2	Refrigerator boxes, 4 X 4 X 4 in. (102 X 102 X 102 mm)
25 ft	Nylon rope, 1/8-in. (3 mm) dia
16	No. 8 sheet metal screws
16	No. 8 solder lugs
8	Plastic (or rubber) end caps, 1-1/4-in. (32 mm) dia



The boom-to-mast plate.



Fig. 6 — Coupling details for joining sections of aluminum tubing.

placed on the mast several feet above the antenna and provides the attachment point for the center of the truss line. To reduce the possibility of water accumulating in the element tubing and subsequently freezing (rupture may be the end result), crutch caps are placed over the element ends. Rubber feet suitable for keeping furniture from scratching hardwood floors would serve the same purpose. In fact, the rubber tips prevent the element ends from damaging surrounding objects during installation.

A heavy-duty steel mast should be used, such as a 1-inch (25-mm)-diameter galvanized water pipe. Steel TV mast is also acceptable. Any conventional TV-type antenna rotator should hold up under load conditions presented by this antenna. Nevertheless, certain precautions should be taken to assure continued trouble-free service. For instance, whenever possible, mount the rotator inside the tower and extend the mast through the tower top sleeve. This procedure relieves the rotator from having to handle lateral pressures during windy weather conditions. A thrust bearing is desirable to reduce downward forces on the rotator bearings.

Hookup and Operation

The monoband nature of the beam requires the use of two coaxial feed lines. The coaxial cable is attached to the 15-meter element (at the front of the beam) at the gamma-capacitor box. The other end of the cable is connected to a surplus 28-V dc single-pole coaxial switch.[2] The cable for the 20-meter element is connected in a similar fashion. The switch allows the use of a single feed line from the shack to a point just below the antenna where the switch is mounted. It is a simple matter to provide voltage to the switch for operation on one of the two bands. At the price of coaxial cable today, a double run of feed line represents a substantial investment and should be avoided if possible.

An etched-circuit board was mounted inside an aluminum Minibox to provide support and insulation for each of the gamma tuning capacitors. Plastic refrigerator boxes available from most department stores would serve just as well. The capacitor housing is mounted to the boom by means of U bolts.

The builder is encouraged to follow the dimensions given in Fig. 5 as a starting point for the position of the gamma rods and shorting bar. Placing the antenna near the top of the tower and then tilting it to allow the capacitors to be reached makes it possible to adjust the capacitors for minimum SWR as indicated by an SWR meter (or power meter) connected in the feed line at the relay. If the SWR cannot be reduced below some nominal figure of approximately 1.4:1, a slight repositioning of the gamma short might be required. The dimensions given are for operation at 14.050 MHz and 21.050 MHz. The SWR climbs above 2:1 about 50 kHz in either direction from the center frequency. Although tests were not conducted at more than 150 watts input to the transmitter there is no reason why the system would not operate correctly with a kilowatt of power supplied to it.

After many months of testing at the QTH of W1FB, several characteristics were noted. First, the antenna withstood several wind and ice storms common to Connecticut. Performance turned out to be what can be expected from a 2-element Yagi. Since the 20-meter portion of the antenna is a director array, the front-to-back ratio is a bit less than 10 dB. On 15 meters, where the system operates with a reflector parasitic element, the front-to-back ratio is considerably better — on the order of 15 dB.

This antenna was mounted atop a 40-foot (12.2-m) tower where previously there was connected a 20-meter sloping dipole pointed at Europe (a multielement array for 2 meters graced the top of the tower!). The number of European stations contacted increased rather dramatically with the installation of the beam. Except in pileups on rare DX stations, DX is now worked as a routine, even though W1FB is a QRP fan and typically runs less than 2 watts of output power.

No doubt the increased effectiveness of the signal was caused by several factors. The antenna certainly has gain (although at ARRL hq. we have no way of making accurate measurements) and is well above the nearby small trees. More importantly, the antenna is now far from the aluminum house siding which once was directly in the pattern of the 20-meter "sloper." Of course, the front-to-back characteristic has the tendency of making DX signals louder in relation to stateside stations and therefore makes receiving much easier.

If previously you've felt that a beam and tower were not possible at your QTH, perhaps re-evaluation of the situation is in order. This antenna, as shown in the photograph, does not appear offensive when viewed from the front yard. Yet the overall amount of property occupied (at ground level) is less than one square foot. And the turning radius is slightly over 11 feet (3.35 m)! This material was originally presented in *QST* by Robert Myers, W1XT and Clarke Greene, K1JX.

References

[1] Sevick, "The W2FMI Ground-Mounted Short Vertical," *QST*, March 1973. (See Chapter 1.)

[2] Purchased from Fair Radio Sales, Lima, OH.

Linear Loaded 20-Meter Beam

Build this novel minibeam for 20 meters . . . it works!

Full-sized antennas are fine if you have the height and room for them. But much of the advantage is usually lost with average installations. So why bother with a sad-looking monster a few feet atop the house when a trim, smaller model will do the job. This article deals with a method that eliminates the messy and expensive loading coils as well.

Having built an HW-32A transceiver, the author's 20-meter activity was restricted to the phone band. A homemade vertical antenna did a fair job in the states, but not for DX. This writer's thoughts ran to a beam and the aluminum tubing that could be obtained for full-size construction. A 2-element beam was constructed, using a gamma match and information found in the *Handbook*. The beam worked electrically, but the mechanical construction left much to be desired. It flopped in the wind like a wounded butterfly. The author tried to correct this with a wooden framework, but it was just as bad. Something with shorter elements was desired, something that was rigid and would still perform well. But all of the author's research turned up only loading coils or other methods involving a loss compromise.

The author's aluminum supply included four 12-ft (3.66-m) lengths of 7/8-inch (22-mm) diameter tubing. This would give two elements of 24 ft (7.32-m) length and a minimum of sag. The problem was how to mount them and make up the difference in physical and electrical length for a half-wave length. Loading coils were ruled out. The possibility of folding wire under the elements seemed to have merit. (Later, this was found to be called linear loading.) This dictated a split element and standoff supports for the tubing.

Two 2-ft (0.61-m) lengths of aluminum channel were obtained for the element supports (Fig. 7). each 12-ft (3.66-m) section was attached using 1-in. (25-mm) ceramic standoff insulators. A 34-in. (19-mm) birch dowel was used to stiffen and prevent crushing of the tubing where the attachment was made. Element supports were grooved and attached to a 10-ft (3-m) TV mast section using a single 5/16-in. (8-mm) U bolt.



The folded additional loading wire was no. 12 copper house wire with the insulation stripped off, and was supported by two bakelite blocks on each element section. The blocks were anchored to the tubing by small sheet metal screws. Ends of the wire sections were formed into a loop to hold their position.

Tune-Up and Adjustments

My thinking in regard to coaxial-cable-fed dipoles is that they should use a balun or matching device of some kind. This beam, having a split driven element, seemed to call for a 1:1 balun since it was to be fed with RG-58/U (Fig. 8). Formulas found in handbooks for beam-element lengths did not seem to work for the linear-loading design, so cut-and-try was used many times. In final tests, a grid-dip meter was utilized with a calibrated receiver to determine the driven-element total length of 35 ft (10.67 m). A reflector with 10-ft (3.05-m) spacing was used.

It was found that adding a reflector of five-percent greater length lowered the frequency (with the beam near the ground) but on raising the beam to rooftop, the frequency had increased. The 10-ft spacing gave a 3:1 VSWR which was very difficult to reduce. Testing this arrangement on the air seemed to indicate more gain in the back direction than in the front. After many tests and much rebuilding of the wire lengths, the director element approach seemed to give the most encouraging results. The VSWR was down to 1.5:1 and the five-percent shorter director raised the frequency to the phone band. Spacing was reduced to 7 ft 6 in. (2.29 m).



The beam atop the author's tower.

More research brought out the possibility of inductive matching to get the VSWR


SIDE VIEW
11'6" x 7/8" DIRECTOR (3.50m x 22mm)
12' x 7/8" DRIVEN ELEMENT (3.66m x 22mm)
1-1/2" (38mm)
BAKELITE BLOCK
BRASS BOLTS
5-1/2" (140mm)
15" (381mm)
NO.12 FOLDED WIRE
1/8" (3mm) ALUMINUM CHANNEL 2' x 2" x 2" (61m x 51mm x 51mm)
1" x 1" INSULATOR (25mm x 25mm)
5/16" (7mm) U BOLT
TO RECEIVE 1-1/4" (32mm) TV MAST BOOM 10' (3.05m)
TOP VIEW
1-1/4" (32mm)
DIRECTOR CONTINUOUS AS SHOWN, NO.12 WIRE DRIVEN ELEMENT OPEN TO BALUN AND HAIRPIN
NO.12 WIRE
LOOPS FOR DRIVEN ELEMENT ARE 10" (254mm) CIR.
SOLDER LUGS FOR NO.12 WIRE UNDER BRASS BOLT HEAD
LOOPS FOR DIRECTOR ELEMENT ARE 2-1/2" (64 mm) CIR.
SET SCREW
BLOCK DETAIL
2-1/8" (54mm)
7/8" (22mm)
1-3/4" (44mm)
1-1/8" (29mm)
7/16" (11mm)
FOR NO.12 WIRE SUPPORT (1/8" DRILL)-(3mm)

Fig. 7 — Construction details of the loaded beam.


5-1/2" (140mm)
12' (3.66m)
12' (3.66 m)
DRIVEN ELEMENT
10" (254mm) CIRCULAR LOOP
BALUN 1:1
TOTAL WIRE LENGTH - 5'6" (1.68m)
7/8" (22mm) ALUMINUM TUBE
COAX RG-58/U
7'6" SPACING (2.29m)
23" (584mm) HAIRPIN 1-1/2" (38mm)
5-1/2" (140mm)
11'6" (3.50m)
11'6" (3.50m)
DIRECTOR ELEMENT
TOTAL WIRE LENGTH 10'3" (3.12m)
FOLDED WIRE WITH LOOP
2-1/2" (64mm) CIRCULAR LOOP

Fig. 8 — Critical electrical dimensions.

down to a more reasonable level. Many hairpin lengths and widths were tried with varying results. The final hairpin was 23-in. long by 1-1/2 in. (580 × 38 mm) wide with a slight fan shape to fit the balun connections. This reduced the VSWR at 14,200 kHz and 14,350 kHz with a flat response in between.

On-the-Air Tests

The help of other amateurs in tests for front-to back ratio was very helpful. Average reports have been 2.5 S units in the forward position over the back position. The author did not have a reference dipole for gain tests, but has heard and worked more DX than in the past 20 years. The beam is mounted on a rooftop 10-ft (3-m) steel tower 38 ft (11.6-m) above the ground. It weighs around 20 pounds and is rotated by an older-type TV rotator. This material was originally presented in *QST* by Cole Collinge, W0YNF.

The Log-Yag Array

The Yagi antenna array has been around for years and years. A relative newcomer to hams is the log-periodic dipole array (LPDA), which offers nearly constant gain over a greater bandwidth than the Yagi. Guess what happens when you cross a Yagi with an LPDA . . . .

With the decline in sunspot activity, a number of amateurs have considered monoband Yagi arrays. The first problem encountered seems to be array length, that is, overall size for a desired gain and bandwidth. The Log-Yag principle, as will be discussed shortly, has produced a system which will provide the amateur with another alternative to the long-boom Yagi, stacked Yagis, or loop-antenna systems. The L-P Yagi (Log-Yag) array is not a new system; many such arrays have been designed and developed by Oliver Swan[1] and others.[2] This article, however, will provide the basic theory of operation, design procedure, and the construction of a practical antenna.

Theory of Operation

The Log-Yag array utilizes an LPDA-driven[3] group of elements, designed to cover a desired bandwidth, in conjunction with parasitic elements to achieve higher gains and greater directivity than would be realized with either the LPDA or Yagi array alone. The Yagi array requires a long boom and wide element spacing for wide bandwidth and high gain. This is because the Q of the Yagi system increases as the number of elements is increased and/or as the spacing between adjacent elements is decreased.[4,5] An increase in the Q of the Yagi array means that the total bandwidth of that array is decreased; optimum gain, front-to-back ratio, and side lobe rejection are obtainable only over small portions of the band. Dr. I. L. Morris, using a high-speed digital computer, has completed extensive research on 4-, 8-, and 10-director Yagi-Uda arrays.[6] His work is comprehensive and is recommended reading for all technically minded amateurs. The parameters varied in his study were element length, spacing, radius and number. As can be seen in Fig. 9, the forward gain and front-to-back ratio



The attachment of the elements to the boom.



From the front to the back of the Log-Yag array. Note the truss provides lateral and vertical support.



The completed Log-Yag array ready for use. The array mounted above the Log-Yag is a 7-element LPDA for 21 to 30 MHz.



Fig. 9 — The effects of director spacing on various Yagi arrays. The change in gain and front-to-back ratio is plotted for the change in director spacing. The reflector spacing has been held constant.



The connections between the balun and the input terminals.

deteriorate sharply as element spacings decrease. If the elements are closely spaced, then as the frequency is shifted either side of the array design frequency the electrical spacing between adjacent elements changes rapidly. This causes a higher SWR and a deterioration of forward gain and front-to-back ratio.

The Log-Yag system overcomes this difficulty by using a multiple driven element "cell" designed in accordance with the principles of the log-periodic dipole array.[7,8] Since this log cell exhibits both gain and directivity by itself, it is a more effective radiator than a simple dipole driven element. The front-to-back ratio and gain of the log cell can be improved with the addition of a parasitic reflector and director. It is not necessary for the parasitic element spacings to be large with respect to wavelength, as in the Yagi array, since the log cell is the determining factor in the array bandwidth. In fact, the element spacings within the log cell may be small with respect to a wavelength without appreciable deterioration of the cell gain. For example, decreasing the relative spacing constant (σ) from 0.1 to 0.5 λ will decrease the gain by less than 1 dB. Hence, a further reduction in boom length. It can be seen that the Log-Yag array will exhibit high theoretical gain (11 dBd), high front-to-back ratio (30 dB), high cross polarization (front-to-side ratio — 45 dB), and a wideband response utilizing boom lengths approximately one half that of a Yagi with similar characteristics.[2]



Fig. 10 — Beam patterns of 20-meter arrays.
No. 1 — 3-el. log cell, dir. @ 0.1λ, ref. @ 0.2λ.
No. 2 — 5-el. log periodic, σ = 0.1.
No. 3 — 3-el. log cell, 1st dir. @ 0.1λ, 2nd dir. @ 0.2λ.
No. 4 — 4-el. log cell, ref. @ 0.15λ.
No. 5 — 4-el. log cell, dir. @ 0.15λ, ref. @ 0.085λ (described in this article).

The author has built many monoband 14-MHz Log-Yag arrays in an attempt to find an optimum combination of elements, while holding the boom length to that of a full-sized, three-element monobander Yagi. Relative radiation patterns for various element combinations are found in Fig. 10. The final array design takes the form of a four-element log cell, parasitic reflector spaced at 0.085 λ_{max} and parasitic director spaced at 0.15 λ_{max} where λ_{max} is the longest free-space wavelength within the array passband. It has been found that array gain is almost unaffected with reflector spacings from 0.08 λ to 0.25 λ and the increase in boom length is not justified.[9] The function of the reflector is to improve the front-to-back ratio of the log cell while the director sharpens the forward lobe and decreases the half-power beamwidth. As the spacing between the parasitic elements and the log cell decreases, the parasitic elements must increase in length.[10]

The log cell is designed to meet upper and lower band limits with σ = 0.05λ. The design parameter τ is dependent on the structure bandwidth, B_s. When the log-periodic design parameters have been found, the element length and spacings can be determined. A review of the "Log-Periodic Dipole Array" is recommended though not necessary for the design of the Log-Yag array.[3,7,8]

The method of feeding the antenna is identical to that of feeding the log-periodic dipole array without the parasitic elements. As shown in Fig. 11, a balanced feeder is required for each log-cell element, and all adjacent elements are fed with a 180° phase shift by alternating connections. Since the Log-Yag array will be covering a relatively small bandwidth, the radiation resistance of the narrow-band log cell will vary from 80 to 90 ohms (tubing elements) depending on the operating bandwidth. The addition of parasitic elements lowers the log-cell radiation resistance. Hence, it is recommended that a 1-to-1 balun be connected at the log-cell input terminals and 52-ohm coaxial cable be used for the feed line. The measured radiation resistance of the 14-MHz Log-Yag installed at the author's QTH is 37 ohms, 14.0 to 14.35 MHz. It is assumed that tubing elements will be used. However, if a wire array is used then the radiation resistance R_o and antenna-feeder input impedance Z_o must be calculated so that the proper balun and coax may be used. The procedure is outlined in detail in *The ARRL Antenna Book*.[3,7]

Design Procedure

The following step-by-step design procedure may be used to design any monoband Log-Yag for any desired bandwidth.



Fig. 11 — Layout of the Log-Yag array.

1) Determine the operating bandwidth, B, between f_1, lowest frequency (band edge), and f_n, highest frequency (band edge).

$$B = \frac{f_n}{f_1}$$

2) Determine the structure bandwidth (log-cell array) B_s.

$$B_s = 1.15B$$

3) Determine the design parameter τ (based on 4-element log cell, note 1).

$$\tau = \frac{1}{\sqrt[3]{B_s}}$$

Note 1. The design parameter τ is chosen for a four-element log cell since it provides the best bandpass for most amateur bands. For log cells with any number of elements

$$\tau = \frac{1}{\sqrt[(n-1)]{B_s}}$$

where n = number of elements within the log cell.

4) Determine the apex half-angle α: Since $\sigma = 0.05$ (relative spacing constant), then

$$\cot\alpha = \frac{0.2}{1-\tau}$$

5) Determine the longest free-space wavelength λ_{max}, log-cell boom length, L (ft) and longest element length within the log cell l_1 (ft).

$$\lambda_{max} = \frac{984}{f_1\,\mathrm{MHz}}$$

$$L = \left[\frac{1}{4}\left(1-\frac{1}{B_s}\right)\cot\alpha\right]\lambda_{max}$$

and

$$l_1 = \frac{492}{f_1\,\mathrm{MHz}}$$

$$l_2 = \tau l_1$$

$$l_3 = \tau l_2$$

$$l_4 = \tau l_3$$

6) Determine the element spacing (d_{12}), distance between elements l_1 and l_2 (ft).

$$d_{12} = \frac{1}{2}\left(l_1 - l_2\right) \quad \cot\alpha$$

and

$$d_{23} = \tau d_{12}$$

$$d_{34} = \tau d_{23}$$

7) Determine the parasitic element lengths (ft) and spacings (ft).

$$l_{REF} = \frac{509.6}{f_1\,\mathrm{MHz}}$$

$$d_{REF} = \frac{84}{f_1\,\mathrm{MHz}}$$

$$l_{DIR} = \frac{450.8}{f_1\,\mathrm{MHz}}$$

$$d_{DIR} = \frac{148}{f_1\,\mathrm{MHz}}$$

This completes the design.

The Finished Log-Yag

The proof is always to be found in the completed and operating product. The



Fig. 12 — Assembly details. The numbered components refer to Table 6.



The interconnection between the elements of the log cell changes sides between each element.

Table 3

Array Characteristics

1. Frequency range	14-14.35 MHz
2. Operating bandwidth	B = 1.025
3. Design parameter	τ = 0.946657
4. Apex half angle	a = 14.92°, cot = 3.753
5. Half-power beam width	42° (14-14.35 MHz)
6. Bandwidth of structure	B_s = 1.17875
7. Free-space wavelength	λ_{max} = 70.28 ft
8. Log cell boom length	L = 10.0 ft
9. Longest log element	l_1 = 35.14 ft (a tabulation of element lengths and spacings given in Table 2)
10. Forward gain over dipole	11.5 dB (theoretical)
11. Front-to-back ratio	32 dB (theoretical)
12. Front-to-side ratio	45 dB (theoretical)
13. Input impedance	Z_0 = 37 ohms
14. SWR	1.3 to 1 (14-14.35 MHz)
15. Total weight	96 pounds
16. Wind-load area	8.5 sq. ft
17. Feed-point impedance	Z_0 = 37 ohms
18. Reflector length	36.4 ft @ 6.0 ft spacing
19. Director length	32.2 ft @ 10.5 ft spacing
20. Total boom length	26.5 ft

The mechanical construction of the log cell is identical to that described in *The ARRL Antenna Book*, except for the lengths and spacings.[3,7] Fig. 12 shows how the log cell is constructed as well as the addition of the parasitic elements.

1 ft = 0.30478 m

Table 4

Array Dimensions

Element	*Length Ft*	*Spacing Ft*
Reflector	36.4	6.0 (Ref. to l_1)
l_1	35.14	3.51 (d_{12})
l_2	33.27	3.32 (d_{23})
l_3	31.49	3.14 (d_{34})
l_4	29.81	10.57 (l_4 to dir.)
Director	32.2	

1 ft = 0.30478 m

Table 5

Element Material Requirements

Element	*1-in. Tubing Length (Ft)*	*Qty.*	*7/8-in. Tubing Length (Ft)*	*Qty.*	*3/4-in. Tubing Length (Ft)*	*Qty.*	*1 1/4-in. Angle Length (Ft)*	*1 X 1/4-in. Bar Length (Ft)*
Reflector	12	1	6	2	8	2	None	None
l_1	6	2	6	2	8	2	3	1
l_2	6	2	6	2	8	2	3	1
l_3	6	2	6	2	6	2	3	1
l_4	6	2	6	2	6	2	3	1
Director	12	1	6	2	6	2	None	None

1 ft= 0.30478 m

Table 6

Materials List

1. Aluminum tubing — 0.047 in. wall thickness
   1 in. — 12 ft lengths, 24 lin. ft
   1 in. — 12 ft or 6 ft lengths, 48 lin. ft
   7/8 in. — 12 ft or 6 ft lengths, 72 lin. ft
   3/4 in. — 8 ft lengths, 48 lin. ft
   3/4 in. — 6 ft lengths, 36 lin. ft
2. Stainless steel hose clamps — 2 in. max., 8 ea.
3. Stainless steel hose clamps — 1-1/4 in. max., 24 ea.
4. TV-type U bolts — 1-1/2 in., 6 ea.
5. U bolts, galv. type: 5/16 in. X 1-1/2 in., 4 ea.
6. U bolts, galv. type: 1/4 in. X 1 in., 2 ea.
7. 1 in. ID water-service polyethylene pipe 160 lb/in.^{2} test, approx. 1-3/8 in. OD, 7 lin. ft
8. 1-1/4 in. X 1-1/4 in. X 1/8 in. aluminum angle — 6 ft lengths, 12 lin. ft
9. 1 in. X 1/4 in. aluminum bar — 6 ft lengths, 6 lin. ft
10. 1-1/4 in. top rail of chain-link fence, 26.5 lin. ft
11 1:1 toroid balun, 1 ea.
12. No. 6-32 X 1 in. stainless steel screws, 8 ea.
    No. 6-32 stainless steel nuts, 16 ea.
    No. 6 solder lugs, 8 ea.
13. No. 12 copper feed wire, 22 lin. ft
14 12 in. X 6 in. X 1/4 in. aluminum plate, 1 ea.
15. 6 in. X 4 in. X 1/4 in. aluminum plate, 1 ea.
16. 3/4 in. galv. pipe, 3 lin. ft
17. 1 in. galv. pipe — mast, 5 lin. ft
18. Galv. guy wire, 50 lin. ft
19. 1/4 in. X 2 in. turnbuckles, 4 ea.
20. 1/4 in. X 1-1/2 in. eye bolts, 2 ea.
21. TV guy clamps and eyebolts, 2 ea.

1 in. = 25.4 mm
1 ft = 0.30478 m

author's 14-MHZ Log-Yag on-the-air performance on cw and ssb substantiates the theory. The characteristics of the array are given in Table 3.

The materials needed are given in Table 5. In the construction diagram, Fig. 12, the materials are referenced by their respective material list number. The photographs show the overall construction picture, and the drawings show the details.

The materials should be available from most hardware and electronic stores. However, some have found difficulty in obtaining aluminum tubing. This can be solved by writing to the manufacturer and asking for the name of their distributor nearest your locality. Commercial antenna manufacturers will sell their tubing, but the cost is at a premium.

This array is in operation at K4EWG and W4BBP. The results on the air are nothing short of fantastic! It will give the stacked Yagis and long-boom Yagis a run for their money.

It is the authors' hope that this antenna design will stimulate additional work and research by other amateurs. The field seems wide open, and Yag-Log combinations are endless. The optimum design is by no means achieved in this article. It does seem, however, that a log cell of more than four elements would be necessary only where the array bandwidths, B, exceed $1.03 (B = f_n/f_1)$.

The authors wish to thank George Smith, W4AEO, for his work in substantiating a consideration for log periodic gain.[8] This material was originally presented in *QST* by P. D. Rhodes, K4EWG and J. R. Painter, W4BBP.

References

[1] "The Swan Multidrive 2-Meter Antenna," *QST*, Oct. 1969.
[2] Orr, *Radio Handbook*, 18th edition, pp. 547-548.
[3] Rhodes, "The Log-Periodic Dipole Array," *QST*, November 1973.
[4] *The ARRL Antenna Book*, 13th edition, p. 151.
[5] See ref. 2 above, p. 558.
[6] King, Mack and Sandler, "Arrays of Cylindrical Dipoles," *Yagi-Uda Programme Apdx. V*, 1968, pp. 218-232,468-470.
[7] See ref. 4 above: pp. 160-164, 208-210, and Fig. 9-18.
[8] Smith, "Yes, I've Built Sixteen Log Periodic Antennas!" *73*, March 1975. See pp. 98-99.
[9] Orr, "Antennas," *CQ*, March 1975. See section headed "The KLM Antenna."
[10] See ref. 4 above, p. 204 and Fig. 9-5.

Chapter 3

Quad Antennas

A currently popular form of directional gain antenna is called the "quad." In general performance principles, it compares favorably to the Yagi beams discussed in chapter 2. The proper name for this antenna is the "cubical quad." It was developed by Clarence Moore, W9LZX, in 1942 when he was an engineer for HCJB in Quito, Ecuador. The design came as a solution to large corona discharges at the ends of existing beam-antenna elements. The problem was caused by the highly ionized air at the transmitter location, some two miles above sea level. Operation was in the commercial 25-meter band, which for the intentions of the broadcaster, required a gain type of antenna.

Moore concluded that a gain antenna with no ends was required to handle the 10-kW power without corona or flashover. Thus, the quad was born. Not only did it handle the power without difficulty, it later became a popular amateur antenna after he developed a model for use on 20 meters.

The primary limitation of quad antennas is the unwieldy nature of the "beast," especially at 40 and 20 meters, compared to a Yagi. The supporting framework is subject to extreme stress from ice and wind loading. Nonetheless, the quad has proven to be one of the most effective DX beams that an amateur can build at modest cost. This chapter contains data on various types of quads for a number of amateur bands. It is a compendium of the best on the subject, as published in past issues of *QST*.

Quads and Yagis: Comparisons, Patterns and Working Dimensions

Want a fresh look at the Yagi vs. quad question? This is "must" reading for the antenna-minded.

The material in the following sections will present a discussion of two time-tested antenna arrays.

In this class of arrays the Yagi (more properly the Yagi-Uda) antenna is the grandfather of them all. There are very few antennas which can compete with the electrical operation and simplicity of construction of this array. However, in the early 1940s C. C. Moore, of radio station HCJB, brought into being a parasitic array of loop elements with properties very comparable to those of the Yagi-Uda array. Since its conception this array has become very popular in Amateur Radio circles. It has come to be known as the "cubical quad" or "quad" antenna because of the common use of square loops and box-like construction.[1]

The material to follow will attempt to present an unbiased comparison of these two arrays based upon the experimental and theoretical results of many workers. This material is prefaced by a short section of introductory antenna concepts and definitions so that certain terms and notation will have more meaning when the comparisons between the quad and Yagi antennas are made. Finally, in the last section, some of the experimental patterns of modeled quad and Yagi arrays are presented. A compilation of some of the working dimensions for both types of arrays are also given. This latter material should be of interest to the builder and experimenter.

Introductory Antenna Theory and Definitions: Polarization

Inspection of the radiation field of an antenna will show it to have plane-wave character and to be made up of electric and magnetic field lines which are perpendicular to each other. Polarization of an electromagnetic wave is defined as that direction in which the electric field lines are oriented. If the electric field vector is fixed (in direction) in a plane it is said to be linearly polarized. For example, the polarization of a dipole is linear. If the plane in which this dipole lies is horizontal or parallel to some reference plane (e.g., the surface of the earth), it is called a horizontally polarized antenna. Vertical polarization would result if the dipole were placed perpendicular to the reference plane. It should be noted that if the electric vector does not stay fixed in position but rotates (its tip tracing out an ellipse), then the wave is said to be elliptically polarized. Circular polarization is a special case of elliptical polarization. Elliptical polarization will have a right- or left-hand sense, depending upon the direction of rotation of the electric vector.

Directivity and Gain of an Antenna

The degree to which a particular antenna can concentrate the antenna pattern into a beam is known as *directivity*. Mathematically, it is the ratio of the power density (in watts per square unit of measure) that would be available at an observation point to the power density one would have if the total radiated power were radiated *equally* well in *all* directions.[2] Directivity is a function of the antenna pattern alone and does not take into account antenna efficiency or losses.

The gain of an antenna can be defined in terms of directivity when antenna efficiency is taken into consideration. If K is the antenna efficiency, a number between 0 and 1, then antenna gain is given by

$$G = KD$$

where

G = antenna gain
K = antenna efficiency
D = directivity

The gain in decibels is then given by

$$\text{dB gain} = 10 \log_{10} G.$$

Please note that the above definition has been such that it is a function of the observation point. In amateur circles gain is usually measured at that observation point where the maximum power density is observed. Further, when considering practical Yagi and quad arrays for the hf range, K is normally taken as 1. Gain measured in the above manner is normally called gain with respect to an isotropic antenna. It is interesting to note that since a half-wave dipole concentrates its pattern into certain directions, it will have some gain with respect to an isotropic antenna. This gain with respect to isotropic is found to be

$$G = 1.64$$

or, in dB,

$$G_{dB} = 2.15 \text{ dB}$$

If the vertical and horizontal half-power beam widths are known for a given antenna the following formula will give (somewhat on the generous side) the gain of the antenna with respect to an isotropic antenna

$$G = \frac{40{,}000}{\theta_H \theta_V}$$

where

θ_H = horizontal half-power beam width in degrees.

θ_V = vertical half-power beam width in degrees.

This formula assumes low-side and back-lobe levels for the antenna pattern. If the gain with respect to isotropic is known then the gain with respect to a half-wave dipole is obtained by subtracting 2.15 dB.

Antenna Aperture or Area

This concept is of most use when discussing a receiving antenna. It is a measure of the antenna's ability to gather in available radiated power at some receiving position. Antenna area and gain are *directly* related

$$G = 4\pi \frac{A}{\lambda^2}$$

where

G = antenna gain

λ = operating wavelength

A = area (based upon square units of length measurement, with the length measurement the same as that assumed for λ). It should be noted that one *cannot* have two antennas with the same gain and different areas. One hears this concept misused (in the sense of the above sentence) quite often on the amateur bands. That is to say, if you feel that one antenna has more capture area than another, then it must also have more gain.

Antenna Patterns

The pattern of an antenna may be plotted by recording the received electric field strength or power density as a function of viewing (observation) angle. The properties of most antennas used by radio amateurs (below 30 MHz) can be described by two basic patterns. Consider a pattern due to a radiating half-wave dipole, this pattern to be obtained by moving a sampling or test antenna about the dipole in the horizontal plane which contains the dipole. This pattern is called the horizontal-plane or E-plane pattern (the pattern was taken in a plane containing the electric E-lines, hence the name E-plane pattern). If the sampling antenna is placed directly in front of the horizontal dipole (and in the horizontal plane) and moved up over the top of the dipole (in a plane perpendicular to the horizontal plane), and on around until it returns to the starting position, the result is the vertical-plane or H-plane pattern (since the test antenna moved in a plane parallel to the magnetic H-lines it is called an H-plane pattern).

For Yagi and quad arrays these two patterns will give enough essential information to determine their expected radiating properties.

Comparison of Quad and Yagi Arrays

The cubical quad antenna was first introduced to the radio world in 1942 by Clarence C. Moore at HCJB to alleviate a serious corona problem occurring on a large commercial shortwave Yagi array. It is a parasitic array formed with loop elements which are approximately one wavelength in circumference.

Important to proper operation of a quad antenna are considerations of proper element sizes, spacing between elements, boom length, feed impedance and so forth. The following material presents a discussion of these considerations and a comparison of the quad and Yagi arrays.

Polarization of a Quad Antenna

The polarization of a quad antenna can be determined by considering the current distribution on the driven element. To stress the point that square, diamond, or circular loop all produce essentially the same polarization, consider the current distribution shown in Fig. 1. A little thought reveals that fact that the vertical components of current produce radiated fields that cancel each other, and the horizontal components of current produce a radiated field (broadside to the loop) with all components adding. The polarization of any of these loops is then linear and parallel to an imaginary horizontal line drawn through the current minima. Hence, if a quad loop is fed at the bottom it produces horizontal polarization, and if fed on the side it will have vertical polarization. The geometrical form of the loop, square, diamond or circular, does not mean that the (broadside) radiation has a possible combination of both horizontal and vertical polarization or circular polarization. This seems to be a common misconception in amateur circles. The linear polarization properties introduced above can be verified easily experimentally. It should be further noted that there are no noticeable differences in the radiating properties or impedance of a loop 1 wavelength in circumference whether it be of the circle, diamond or square configuration.

Angle of Radiation for a Horizontally Polarized Quad Antenna

Placement of an antenna above a conducting ground will alter its free-space radiation pattern, positioning the maximum of its main lobe at possibly a new angle with respect to a horizontal reference line. The angular position of this main lobe is called the *angle of radiation.* The angle of radiation of an antenna is a function of its height above the conducting ground and its polarization. Given the height and the polarization, the angle of radiation can be determined by using the concept of the antenna's virtual image or ray theory and reflection of the wave by the ground.

The following conclusions can now be drawn:

The angle of radiation of a *horizontally* polarized quad antenna, at a given boom height, is essentially the *same* as that of a *horizontally* polarized Yagi at the same boom height.

This must be so because the boundary conditions imposed upon the electromag-



Fig. 1 — Current distribution on circular, diamond and square loops 1 wavelength in circumference.



Fig. 2 — Vertical-plane radiation patterns for a horizontally polarized quad or Yagi array above perfectly conducting ground.



Fig. 3 — On-axis gain of a single loop as a function of loop circumference. (From "Studies of Large Circular Loop Antennas" by S. Adachi and Y. Mushiake *Sci. Rep. Ritu*, B-[Elect. Comm.] vol. 9, no. 2, Tohoku Univ., Sendai, Japan, 1957.)

netic wave at the surface of ground are completely insensitive to the fact that the wave is produced by a quad antenna as opposed to the wave produced by a Yagi antenna.

Typical patterns of a quad *or* Yagi antenna placed at a height of 1/2 λ or 1 λ above a perfect ground are shown in Fig. 2 at A and B.

Gain Comparisons of the Quad Antenna with the Yagi Antenna

The gain of a quad array (of given boom length) seems to be somewhat higher than that of a Yagi array of the same boom length. This gain difference can be explained by considering the theoretical work of Adachi and Mushiake of Tohoku University in Japan. In 1952 and 1957 they published two papers which discussed the current distribution, impedance, and radiating properties of loops of large circumference.[3]

Fig. 3 shows the gain of a single loop as a function of wavelength and wire diameter. Fig. 4 shows the variation of reactance and radiation resistance for a single loop. Please note the dependence upon the circumference-to-wire-diameter ratio in these two figures. They showed that the broadside gain of a single loop 1λ in circumference was approximately 2 dB above that of a half-wave dipole. This result implies that a parasitic array of loop elements should have the same gain advantage when compared to a Yagi array of comparable boom length.

This gain differential for the quad array does appear and can be verified experimentally. Fig. 5 demonstrates this comparison. The points on the figure were obtained as follows: For the antenna under consideration E and H plane patterns were made. The gain was then calculated using the E and H-plane half-power beam widths of these radiation patterns and the formula discussed above. This gain and the boom length of the antenna were then used to determine a point on the graph given in Fig. 5, where gain and boom length represent the parameters under consideration. The data points for many, many antennas, both quad and Yagi, were then placed on the graph and a smooth curve representing an average for each type of antenna was then drawn.

The expected gain difference of 2 dB does indeed appear in favor of the quad antenna. This gain differential is essentially that predicted by the results of the Japanese workers cited above.

The measurements used to obtain the above gain comparisons were performed at 440 MHz. A measuring frequency of 440



Fig. 4 — Reactance and radiation resistance of a single loop versus circumference. Note: Ω is a measure of the ratio of loop circumference to wire diameter. Ω = 2ln 8a/ρ where a = loop radius and ρ = wire radius.



Fig. 5 — Quad and Yagi array gain as a function of boom length.

Table 1

Quad Dimensions

2-element Quad (W0HTH)
Spacing (given below)
Boom length (given below)

Band	*40 M*	*20 M*	*15 M*	*10 M*
Reflector	144 ft 11-1/2 in.	72 ft 4 in.	48 ft 8 in.	35 ft 7 in.
Driven Element	140 ft 11-1/2 in.	70 ft 2 in.	47 ft 4 in.	34 ft 7 in.
Spacing	30 ft	13 ft	10 ft	6 ft 6 in.
Boom length	30 ft	13 ft	10 ft	6 ft 6 in.
Feed method	Directly with 23 ft of RG-11, then any length RG-8 coax.	Directly with 11 ft 7 in. RG-11, then any length RG-8 coax.	Directly with 7 ft 8-1/2 in. RG-11, then any length RG-8 coax.	Directly with 5 ft 8 in. RG-11, then any length RG-8 coax.

(Note that a spider or boomless quad arrangement could be used for the 10/15/20 meter parts of the above dimensions yielding a triband antenna)

4-element Quad* (W0AIW [20 M] /W0HTH** /K0KKU/K0EZH/W6FXB)
Spacing: equal; 10 ft
Boom length: 30 ft

Band	*20 M*		*15 M*	*10 M*
	Phone	CW		
Reflector	72 ft 1-1/2 in.	72 ft 5 in.	48 ft 8 in.	35 ft 8-1/2 in.
Driven Element	70 ft 1-1/2 in.	70 ft 5 in.	47 ft 4 in.	34 ft 8-1/2 in.
Director 1	69 ft 1 in.	69 ft 1 in.	46 ft 4 in.	33 ft 7-1/4 in.
Director 2	69 ft 1 in.	69 ft 1 in.	46 ft 4 in.	33 ft 7-1/4 in.
Feed Method	Directly with 50-ohm coax.		Directly with 50-ohm coax.	Directly with 5 ft 9 in. RG-11, then any length RG-8 coax.

*Common boom used to form a triband array.
**The 2-element 40-meter quad given above is added to form a four-band quad array.

4-element Quad (W0HTH/K8DYZ*/K8YIB*/W7EPA*)
Spacing: equal; 13 ft 4 in.
Boom length: 40 ft

Band	*20 M*	*15 M*	*10 M*
Reflector	72 ft 5 in.	48 ft 4 in.	35 ft 8-1/2 in.
Driven Element	70 ft 5 in.	47 ft 0 in.	34 ft 8-1/2 in.*
Director 1	69 ft 1 in.	46 ft 1 in.	(Directors 1-3 all
Director 2	69 ft 1 in.	46 ft 1 in.	33 ft 7 in.)*
Feed method	Directly with 50-ohm coax.	Directly with 7 ft 9 in. RG-11, then any length 50-ohm coax.	Directly with 50-ohm coax.

*For the 10-meter band the driven element is placed between the 20/15 reflector and 20/15 driven element. The 10-meter reflector is placed on the same frame as the 20/15-meter reflectors and the remaining 10-meter directors are placed on the remaining 20/15-meter frames. The 10-meter portion is then a 5-element quad.

6-element Quad (W0YDM, W7UMJ)
Spacing: equal; 12 ft
Boom length: 60 ft

Band: 20 M	
Reflector	72 ft 1-1/2 in.
Driven Element	70 ft 1-1/2 in.
Directors 1, 2 and 3	69 ft 1 in.
Director 4	69 ft 4 in.
Feed Method	Directly with 50-ohm coax.

1 ft = 0.3048 m



Fig. 6 A: Shape factor as a function of the loop circumference-to-wire diameter ratio. B: Loop "resonant length correction factor" versus shape factor. (Circled values obtained from S. Adachi, and Y. Mushiake, "Studies of Large Circular Loop Antennas" *Sci. Rep. Ritu*, B-[Elect. Comm.] vol. 9, no. 2, Tohoku Univ., Sept. 1957.)

MHz was chosen so that 1 cm (at this frequency) is equivalent to 1 foot of measurement at 14 MHz. Hence, to relate these results directly to the 20-meter amateur band, boom length in cm from the curve can be read as boom length in feet. For example, the gain of a quad on a 40-foot (12.19-m) boom should be slightly more than 1 dB above a quad on a 25-foot (7.62-m) boom. Comparison of the signals from these two antennas at a receiving station will not reveal much difference; however, in the DX pile-ups the longer antenna should have a slight advantage. Another interesting interpretation of these results is to note that a quad on a 30-foot (9.14-m) boom is equivalent to a Yagi on a 55-foot (16.76-m) boom. Hence the boom of a Yagi antenna must be about 1.8 times longer than the boom of a quad in order for the two gains to be comparable.

Impedance Properties and Matching

The driving-point impedance of a quad antenna depends upon the element spacing and number of elements. For 2-element quad antennas the results of Bill Orr in his *Quad Antenna* handbook can be used to determine the driving-point impedance. For multielement quads (3 or more elements)[4] the impedance will range from 40 to 60 ohms. Matching of these multielement quads is most easily done by direct feed with a 50-ohm coaxial line. A 1:1 balun can be used but experimental results show that it does not give performance any better than that obtained with direct feed. A gamma match can be used to obtain an exact match to any chosen coaxial line. For details of using a gamma match on a quad antenna see Bill Orr's *Quad Antenna* handbook.

If a single boom is used to construct a multiband quad antenna, then it is recommended that a separate feed line to each driven element be used.

Approximate Formulas for Quad Antenna Element Lengths

The multielement quad antenna gained its first real popularity following the work of Lee Bergren, W0AIW, in the early 1960s. He published the results of his work in *QST* in 1963.[5] Many experimentalists have used his dimensions for antennas in the 20-meter amateur band and have scaled them to other bands. Based upon Bergren's work and others the following empirical formulas can be used to determine the element lengths of a quad antenna

$$\text{Circumference of driven element} = \frac{1005}{f_{MHz}} \text{ feet}$$

$$\text{Circumference of reflector element} = \frac{1030}{f_{MHz}} \text{ feet}$$

$$\text{Circumference of director elements} = \frac{975}{f_{MHz}} \text{ feet}$$

These results should only be used for quad antennas operating below 30 MHz. It is interesting to note that for quad antennas the reflector and directors are only 2-1/2 to 3 percent different in length from the driven element. This is a smaller change than that normally encountered in Yagi arrays.

The above figures should not be used for vhf or uhf quad antennas. At these higher frequencies the circumference-to-wire-diameter ratio becomes small enough that its effect upon the resonant properties of the loop must be considered. Here again, the results of Adachi and Mushiake are useful and the effects of wire size on the resonant length of the loop can be taken into account. These results are given in graphical form in Fig. 6 where, based upon the circumference-to-wire-diameter ratio, a circumference correction factor can be obtained. Once the correct size of the driven element is determined (using the results of Fig. 6) a quad antenna can be designed by making the reflector approximately 3 percent longer and the directors 3 percent shorter.

The above results can be used to obtain workable dimensions but, just as with approximate formulas for Yagi antenna element lengths, the "best" dimensions would have to be determined experimentally by tuning the array.

A Collection of Quad and Yagi Patterns and Dimensions: E and H Plane Patterns for Quad and Yagi Arrays

The previous section referred to a group of experimental tests, where a series of model antennas were constructed and the E and H plane patterns obtained.

It should be noted that these patterns have direct interpretation in light of the 20-meter band. Recall that the experiments were performed at 440 MHz, where dimensions for boom length, element size, and spacing in cm are directly equivalent to dimensions in feet for the 20-meter band. For example, the patterns for a 440-MHz, 5-element Yagi on a 55-cm boom can also be taken as the pattern for a 14-MHz, 5-element Yagi on a 55-foot boom.

Perusal of these patterns will give a



2-ELEMENT CUBICAL QUAD
8-cm BOOM
440 MHz
(A)

3-ELEMENT YAGI
20-cm BOOM
435 MHz
(B)

Fig. 7 — E and H plane radiation patterns for (A) 2-element quad antenna and (B) 3-element Yagi antenna.



4-ELEMENT CUBICAL QUAD
30-cm BOOM
445 MHz
(A)

5-ELEMENT YAGI
55-cm BOOM
445 MHz
(B)

Fig. 8 — E and H plane radiation patterns for (A) 4-element quad antenna and (B) 5-element Yagi antenna.



6-ELEMENT CUBICAL QUAD
60-cm BOOM
440 MHz
(A)

7-ELEMENT YAGI
80-cm BOOM
440 MHz
(B)

Fig. 9 — E and H plane radiation patterns for (A) 6-element quad antenna and (B) 7-element Yagi antenna.

visual means of comparing the quad and Yagi arrays. It is interesting to note the dependence of gain and pattern beam width upon array boom length. Without further comment, typical patterns for both types of antennas are given in Figs. 7 through 9.

A Tabulation of Dimensions of Working Arrays

Presented in tabular form are a few representative dimensions for both quad and Yagi antennas. These are dimensions presently in use by a number of amateurs. Most of the Yagi dimensions are due to amateurs across the country who sent their dimensions to Mr. Hal Wolff or the author to be modeled on the antenna range at the University of Denver. The quad dimensions also are those now in use by a number of amateurs in this country and abroad. It should be noted that most of these dimensions, and the resulting model antennas, provided the necessary data used in the previous section to compare the quad and Yagi. Where known, either the user(s) or the originator of a set of dimensions is indicated. The first set of dimensions is for quad antennas, the second set for Yagi antennas.

Summary

A comparison between the quad and Yagi antennas, on the basis of gain, has been given, this comparison being based upon both theoretical and experimental results. The results indicate that if both antennas have the same boom length the gain of the quad array will be about 2 dB higher than that of the Yagi. For either antenna, gain is a function of boom length and will increase approximately 2.5 dB each time the boom length is doubled. Hence, a 2-dB gain advantage is equivalent to a boom-length advantage of 1.8. In other words, for the quad and Yagi arrays to have comparable gain, the boom length of the Yagi antenna must be 1.8 times longer than that of the quad.

The size of the wire used for the loop element (relative to the loop circumference) will have an influence upon the resonance and radiating properties of the loop. The influence of this shape factor — i.e., the ratio of loop circumference to wire diameter — can be accounted for by using the referenced results of Adache and Mushiake.

In conclusion, it might be stated that one type of antenna (quad or Yagi) is not necessarily better than the other. The choice between a quad or Yagi array will depend critically upon many factors. For example, if single-band operation is of main importance and the geographical area where the antenna is to be used does not have high-wind problems, the best and simplest choice would be a long-boom Yagi antenna. If multiband operation is desired, or if wind problems were to limit the length of the boom to some nominal value, then the quad antenna would be a good choice. Likewise, the choice of available materials in your locale, and the acceptance of the appearance of the antenna by your neighbors or family, constitute other determining factors. The best approach is to survey your requirements and

Table 2

Yagi Dimensions

3-element Yagi (W6SAF)
Boom length: 24 ft
Band: 20 M

	Element Length	*Spacing*
Reflector	34 ft 10-3/4 in.	R—DE: 13 ft 9-1/2 in.
Driven Element	33 ft 2-1/2 in.	DE—D: 10 ft 4-1/2 in.
Director	31 ft. 9-1/2 in.	

3-element Yagi (W0OKC)
Boom length: 26 ft
Band: 20 M

	Element Length	*Spacing*
Reflector	35 ft 6 in.	R—DE: 14 ft
Driven Element	33 ft 4 in.	DE—D: 12 ft
Director	31 ft 7 in.	

3-element Yagi (W0CM, formerly W0JYW)
Boom length: 30 ft
Band: 20 M

	Element Length	*Spacing*
Reflector	35 ft 4-1/2 in.	R—DE: 13 ft
Driven Element	32 ft 2-1/2 in.	DE—D: 17 ft
Director	31 ft 10 in.	
Feed Method	Folded dipole	

4-element Yagi (K0KKU)
Boom length: 30 ft
Band: 20 M

	Element Length	*Spacing*
Reflector	35 ft 6 in.	(all elements
Driven Element	33 ft 4 in.	equally spaced)
Director 1	31 ft 9-1/2 in.	
Director 2	31 ft 2 in.	

4-element Yagi (W4PLL)
Boom length: 30 ft
Band: 20 M

	Element Length	*Spacing*
Reflector	35 ft 4-1/2 in.	(all elements
Driven Element	33 ft 4-1/2 in.	equally spaced)
Director 1	31 ft 9-1/2 in.	
Director 2	31 ft 9-1/2 in.	

4-element Yagi (K6VIZ)
Boom length: 32 ft
Band: 20 M

	Element Length	*Spacing*
Reflector	35 ft 6 in.	R—DE: 10 ft
Driven Element	32 ft 8 in.	DE—D1: 10 ft
Director 1	31 ft 8 in.	D1—D2: 12 ft
Director 2	31 ft 1 in.	

4-element Yagi (W0OKC)
Boom length: 36 ft
Band: 20 M

	Element Length	*Spacing*
Reflector	35 ft 6 in.	R—DE: 14 ft
Driven Element	33 ft 4 in.	DE—D1: 10 ft 8 in.
Director 1	31 ft 8-1/2 in.	D1—D2: 11 ft 4 in.
Director 2	31 ft 1 in.	

4-element Yagi
Boom length: 40 ft
Band: 20 M

	Element Length	*Spacing*
Reflector	35 ft 6 in.	R—DE: 14 ft
Driven Element	33 ft 4 in.	DE—D1: 12 ft
Director 1	31 ft 7 in.	D1—D2: 14 ft
Director 2	31 ft 0 in.	

5-element Yagi (WA6ZZK)
Boom length: 40 ft
Band: 20 M

	Element Length	*Spacing*
Reflector	34 ft 10 in.	R—DE: 10 ft
Driven Element	33 ft 4 in.	DE—D1: 9 ft
Director 1	32 ft 6 in.	D1—D2: 10 ft 6 in.
Director 2	32 ft 2 in.	D2—D3: 10 ft 6 in.
Director 3	31 ft 10 in.	

5-element Yagi
Boom length: 46 ft
Band: 20 M

	Element Length	*Spacing*
Reflector	35 ft 7-3/4 in.	
Driven Element	34 ft 5-3/8 in.	(All elements
Director 1	33 ft 2 in.	equally spaced
Director 2	31 ft 9-1/2 in.	at 11 ft 6 in.)
Director 3	30 ft 4-1/2 in.	

1 ft = 0.3048 m

5-element Yagi (K6EVR)
Boom length: 46 ft
Band: 20M

	Element Length	Spacing
Reflector	35 ft 4 in.	R—DE: 12 ft
Driven Element	33 ft 5 in.	DE—D1: 10 ft
Director 1	31 ft 8 in.	D1—D1: 12 ft
Director 2	31 ft 8 in.	D2—D3: 12 ft
Director 3	31 ft 8 in.	

5-element Yagi (W8PWH)
Boom length: 52 ft
Band: 20M

	Element Length	Spacing
Reflector	35 ft 11 in.	R—DE: 13 ft 10 in.
Driven Element	33 ft 4-1/2 in.	DE—D1: 10 ft 5 in.
Director 1	32 ft 10 in.	D1—D2: 13 ft 10 in.
Director 2	31 ft 2 in.	D2—D3: 13 ft 10 in.
Director 3	30 ft 9 in.	

5-element Yagi (W4EX, formerly W4DQH)
Boom length: 54 ft
Band: 20M

	Element Length	Spacing
Reflector	35 ft 0 in.	R—DE: 13 ft 6 in.
Driven Element	33 ft 4 in.	DE—D1: 11 ft 6 in.
Director 1	32 ft 3 in.	D1—D2: 13 ft
Director 2	32 ft 1 in.	D2—D3: 16 ft
Director 3	31 ft 11 in.	

5-element Yagi (W6RR, formerly W6ITA)
Boom length: 55 ft
Band: 20M

	Element Length	Spacing
Reflector	34 ft 9 in.	R—DE: 16 ft 9 in.
Driven Element	33 ft 7 in.	
Director 1	31 ft 11 in.	(All elements equally spaced)
Director 2	31 ft 9-1/2 in.	
Director 3	31 ft 8 in.	

6-element Yagi
Boom length: 46 ft
Band: 20M

	Element Length	Spacing
Reflector	35 ft 5 in.	
Driven Element	34 ft 5-1/2 in.	(All elements equally spaced at 9 ft 2-3/8 in.)
Director 1	32 ft 7 in.	
Director 2	32 ft 3 in.	
Director 3	31 ft 4-1/2 in.	
Director 4	31 ft 1/2 in.	

6-element Yagi (W0OKC)
Boom length: 46 ft
Band: 20M

	Element Length	Spacing
Reflector	35 ft 4 in.	R—DE: 10 ft
Driven Element	33 ft 4 in.	DE—D1: 8 ft
Director 1	31 ft 11 in.	D1—D2: 9 ft
Director 2	31 ft 3-1/2 in.	D2—D3: 9 ft 6 in.
Director 3	31 ft 1/2 in.	D3—D4: 9 ft 6 in.
Director 4	30 ft 11 in.	

6-element Yagi (W0OKC)
Boom length: 74 ft
Band: 20M

	Element Length	Spacing
Reflector	35 ft 5 in.	R—DE: 16 ft 6 in.
Driven Element	33 ft 4 in.	DE—D1: 9 ft 9 in.
Director 1	31 ft 9-1/2 in.	D1—D2: 14 ft
Director 2	31 ft 2-1/2 in.	D2—D3: 17 ft 6 in.
Director 3	30 ft 11 in.	D3—D4: 21 ft
Director 4	30 ft 8 in.	

7-element Yagi (W6HAW)
Boom length: 80 ft
Band: 20M

	Element Length	Spacing
Reflector	35 ft 5 in.	R—DE: 14 ft
Driven Element	33 ft 4 in.	DE—D1: 11 ft
Director 1	31 ft 8 in.	D1—D2: 12 ft
Director 2	31 ft 4 in.	D2—D3: 13 ft
Director 3	30 ft 8 in.	D3—D4: 14 ft
Director 4	30 ft 8 in.	D4—D5: 16 ft
Director 5	30 ft 8 in.	

8-element Yagi (WA6EKD)
Boom length: 100 ft
Band: 20M

	Element Length	Spacing
Reflector	34 ft 9 in.	(All elements equally spaced at 14 ft 4 in.)
Driven Element	33 ft 5 in.	
Director 1	32 ft 2 in.	
Director 2	31 ft 11-3/4 in.	
Director 3	31 ft 9-7/8 in.	
Director 4	31 ft 8 in.	
Director 5	31 ft 2 in.	
Director 6	30 ft 11-3/4 in.	

environmental restrictions, make your choice and proceed accordingly.

Acknowledgements

It is very difficult to acknowledge systematically and completely all those who have made the quad antenna a successful communications antenna. However, surely credit must be given to C. C. Moore, the father of the quad antenna, to William Orr, who presented the first written material on the theory and construction of 2-element quads; to Lee Bergren, who showed the feasibility and advantages of using multielement quad arrays; to the Japanese workers, Adache and Mushiake, of Tohoku University, who presented a detailed analysis and experimental verification of the electromagnetic properties of loop antennas of large circumference; and finally, to all the radio amateurs, in all corners of the world, who developed constructional and design techniques and proved or disproved their validity.

The author would like also to acknowledge the help of Mr. Hal Wolff (WA0IOR) for his aid in constructing the model Yagi and quad arrays and running the patterns. These patterns were obtained by using the antenna range of the Denver Research Institute of the University of Denver.[6] Many Denver-area amateurs have entered into these quad experiments, notably Messrs. Jim Snyder (K0ZCM), Butch Ford (WA0IMX), Ed Wood (K0KKU), Keith Farris (W0YDM), Warren Wheeler (W0R-EQ) and many others. The author gratefully acknowledges their assistance, help and encouragement. This material originally presented in *QST* by J. E. Lindsay, Jr., W7ZQ.

References

[1] For a colorful description of C. C. Moore's invention of the cubical quad antenna see the introduction of W. I. Orr's *Quad Antennas*, Radio Publications, Inc.

[2] An antenna which radiates equally well in all directions is called an isotropic radiator or isotropic antenna.

[3] Adachi and Mushiake, "Theoretical formulation for large circular loop antennas by integral equation method," *Repts. of the Research Institute of Elec. Commun.*, Tohoku University, Sendai, Japan, Sci. Rept. Ritu, B(Elec. Commun.), vol. 9, no. 1, 1957.

Idem., "Studies of large circular loop antennas," *Repts. of the Research Institute of Elec. Commun.*, Tohoku University, Sci. Rept. Ritu, B(Elec. Commun.), vol. 9, September 1952.

[4] Element spacing of 0.14λ to 0.2λ being considered.

[5] Bergren, "Multielement Quads," *QST*, May 1963.

[6] At the time these tests were performed (1962-64), the author was head of the Antenna Laboratory, Denver Research Institute, University of Denver. Mr. Hal Wolff was the research technician at this facility.

Additional References

Jasik, *Antenna Engineering Handbook*. New York: McGraw-Hill, 1961, pp. 16-25.

Lindsay, "A circular loop antenna with non-uniform current distribution," *IRE Trans. Antennas and Propagation (Communications)*, vol. AP-8, pp. 439-441, July 1960.

Lindsay, "A parasitic end-fire array of circular loop elements," *IEEE Trans. Antennas and Propagation (Communications)*, vol. AP-15, No. 5, pp. 697-698, Sept. 1967.

A Triband One-Loop Cubical Quad Element

Why not trade gain for economy and structural reliability? This three-band "DX Getter" consists of a single quad loop. It will stay aloft in high winds and won't look like an ugly monster to those who dwell nearby.

The advantages of a rotatable beam antenna are well known to all DXers. A problem arises in many situations regarding just how a reasonable compromise between antenna performance and cost, size and weight can be obtained. Because this author likes to live in peace with the XYL, the neighbors and the local council, the antenna must not be considered dangerous or an eyesore as far as appearance is concerned. In addition, the antenna must not hang over the fence of the 50- × 150-foot (15- × 46-m) block, half of which is already occupied by buildings. With these limitations firmly implanted in mind, the author added such factors as cost and difficulty of erecting and supporting a full-size, 20-meter Yagi or cubical quad. After weighing all the facts, it was felt that the only way out was to construct an economy-style, reduced-size antenna.

A single-loop, cubical-quad triband element is shown in Fig. 10. Such a cubical quad has only one-fourth the weight and wind resistance of a full-sized, three-element cubical quad of the same mechanical strength. The mechanical and installation difficulties are many times smaller; the cost of mast and rotor are also considerably reduced. Yes, the antenna is a compromise and the gain is less than that of a 3-element quad, but this antenna still puts a signal in good DX company. This quad, because of its smaller physical size, will be tolerated in many more locations than its big brother. If desired, this quad could be used as an indoor antenna strung between two opposite room walls.

Rather than going to a complicated switching arrangement to change bands, it was decided to apply what the author called the "triband-antenna principle" to this antenna. The theory behind this principle evolves around the same general ideas outlined by Pichitino in *QST*[1] several years ago. Antennas constructed along these guidelines do not operate harmonically and have only the desired resonances. The quad that was built is shortened only at the lowest operating frequency. It is full size at the middle operating frequency and much longer at the highest operating frequency. In addition, no heavy blocking tuned circuits are used near the element ends.



Fig. 10 — Single-loop triband cubical-quad element. Metric dimensions are shown; approximate English-unit dimensions are given in parentheses. Frequencies shown for C1L1 and C2L2 are those to which these circuits are tuned when disconnected from the loop.

C1 — 55 pF.

C2 — 49 pF.

L1 — 7 turns, No. 12, 38-mm (1-1/2-inch) diameter, space wound to 16 mm (5/8-inch) length.

L2 — 4 turns, No. 12, 38-mm (1-1/2-inch) diameter, space wound to 18 mm (11/16-inch) length.

L3 — 4 turns, No. 12, 38-mm (1-1/2-inch) diameter, space wound to 10-mm (3/8-inch) length.

With C1 giving 20-meter resonance depends mainly on the total element length and L1. Fifteen-meter resonance is controlled principally by C1 and L2. Ten-meter resonance is determined by C2 and L2. Once the antenna is constructed, it may be fine-tuned on each band by varying the constants that control the resonant frequencies. After the quad was tuned up, the author found the SWR on each band to be very satisfactory. On 20 meters, the antenna resonated at 14.15 MHz with a resulting SWR of approximately 1:1. With a 15-meter resonance at 21.3 MHz, an SWR of 1.3:1 was measured. On 10 meters, 28.6 MHz was selected as the resonant frequency. The resulting SWR at resonance on this band was 1.5:1. The phase relationship of the fields in L1 and L2 varies from band to band so that too much direct coupling between these coils should be avoided.

Although the author used copper wire to make the loop element, you may desire to use aluminum tubing. The actual constructional details are left to the builder. The materials used and the methods of supporting the antenna are limited only by your imagination. The techniques employed may be as simple or as sophisticated as you may desire. DJ2UT used short pieces of coaxial cable as capacitors and placed them inside the tubing which he used for the element. The coils and inner capacitor ends were sealed and molded in resin. Fifteen- and 10-meter resonances are obtained by shifting copper rings over the ends of L1 and L2. This can be done without affecting the sealed coils in any way.

The author concluded this antenna to be rather efficient based on observations that the tuning network does not become warm and a low SWR has been measured across each of the three bands. This writer wishes to thank OM Sommer, DJ2UT, and his co-workers for the very considerable amount of work carried out, and the many practical ideas which have made successful antennas with the triband principle possible. This material was originally presented in *QST* by Hans F. Ruckert, VK2AOU.

---

[1] Pichitino, "A New Principle in Two-Band Rotary-Beam Design," *QST*, October 1948.

A 2-Element, 15-Meter Quad for the Novice

Why not build this 2-element quad for 15 meters? It is easy to construct, inexpensive and in many ways quite novel.

Not being blessed with a large area for antennas, the author decided on an optimum-spaced, 2-element monoband quad. The standard formulas were used for sides and spacing, and the antenna is fed with 50-ohm cable through a quarter-wave "Q" section of 75-ohm coax cut to the standard formula. The reflector has a tuning stub.

The driven element grid-dips at 21,150 kHz and the reflector was tuned by using the grid-dip oscillator as a signal generator. The grid-dip meter was placed in a neighbor's home. Then, the back of the quad was aimed at the dip meter, and the reflector was tuned for the lowest indication on the S-meter.

One of the checks made on the antenna was with VE5XH, in Swift Current, SK. Doug gave the following information: The quad has 2 S-units gain over my 1/4-wave groundplane which was at the same height. Strength off the front was S9 and to the rear was S2, indicating a good front-to-back ratio. Because the constructional details are rather novel, the author felt that other hams might be interested in how this antenna was built.


SMALL EYE BOLTS DOUBLE NUTTED
WATER HOSE SPLIT TO SHIM THEN TAPED AND LACQUERED
ONE SPREADER COTTER-KEYED TO PREVENT ROTATION
REFLECTOR 12'2" (3.71m)
DRIVEN 11'10-1/2" (3.62m)
10' (3.05m)
HOSE CLAMP
BRACE
20' (6.10m)
75Ω, RG59/U 7'8" (2.34m)
CENTER
SHIELD
FEED TO XMTR - ANY LENGTH, 52ΩCOAX

Fig. 11 — Detailed drawing of the quad. The cotter pin and cross-brace are required to prevent shifting of the spreaders. Small sections of split water hose are used for shims between the aluminum tubing and the plastic water pipe.

Construction

The author used 1-1/4-inch (32-mm) TV steel mast pipe, 10 feet (3 m) long, for the boom. Also, 10-foot lengths of TV mast sections, but aluminum, are used for the spreaders. However, 10-foot long spreaders are not long enough for a 15-meter quad; 20-foot (6.1-m) lengths are required. In order to obtain the required length, 20-foot lengths of one-inch (25 mm) diameter, ridged plastic water pipe were run completely through the 10-foot aluminum pipe sections. Pieces of rubber hose were used as shims between the aluminum pipe and the plastic pipe and these were taped where the plastic pipe emerges from the aluminum.



The completed quad on the tower. For tune-up, the quad was temporarily mounted on the garage roof.

The plastic water pipe comes in 20-foot lengths, 80 feet (24.4 m) being required. This pipe was purchased from a local plumbing and lighting outlet; the cost was $10 for the 80 feet. It is ridged plastic, but is not strong enough to support itself; so the aluminum mast pipe is used for the center portion of the spreaders.

The spreaders are clamped to the boom with standard U bolts, and one spreader in each element is pinned to the boom with a 5/16-inch (8 mm) cotter key. Additionally, a piece of one-inch (25 mm) conduit is used in each element as a cross-brace, to hold the correct angle between the spreaders.

The formulas and element lengths for 21,150 kHz are as follows

Driven element

$$\frac{1005}{f\,(\mathrm{MHz})} = 47 \text{ feet, 6 inches (14.48 m)}$$

Reflector

$$\frac{1030}{f\,(\mathrm{MHz})} = 48 \text{ feet, 8 inches (14.83 m)}$$

Boom spacing

$$0.2 \text{ wavelength} = 0.2 \times \frac{984}{f\,(\mathrm{MHz})} = 9 \text{ feet, 3 inches (2.84 m)}$$

75-ohm matching section

$$\frac{246 \times V}{f\,(\mathrm{MHz})} = \frac{162.4}{f\,(\mathrm{MHz})} = 7 \text{ feet, 8 inches (2.34 m)}$$



Fig. 12 — Side view, showing the mounting plate, Q matching section, and coax feed.



Fig. 13 — The cross-boom bracket, made from 3/8-inch (10 mm) aluminum plate. Ordinary TV U bolts are used to secure it to the boom and mast.



Fig. 14 — The reflector tuning stub is 36 inches (0.91 m) long. The shorting bar, a short piece of wire the same size as used in the stub was approximately 10 inches (254 mm) from the insulator when adjusted for maximum front-to-back ratio. Spacing between wires of the stub may be of the order of a few inches; this spacing is not critical since the stub length is adjusted by the shorting stub in the tune-up procedure.

The author used no. 14 soft-drawn enameled wire for loops and they were secured to the plastic pipe with double-nutted eye bolts. The reflector tuning stub was made from no. 12 copperweld wire. The total length of my stub is 36 inches (0.91 m), and after tuning, the shorting bar ended up approximately 10 inches (254 mm) from the loop.

The SWR showed almost a perfect match across the entire band. Since the quad was put up, the author has worked all continents and 35 countries on the Novice band. Stateside contacts always run S8 to S9. The total cost of the antenna was $28 at the time the system was built. This material was originally presented in *QST* by John Daebelliehn, WA9BJC.

A Practical 40-Meter Quad

One of the most perplexing problems continuously plaguing Field Day committees is how to install a good antenna system. For most clubs, finding a good location is generally the easiest job. The location must then be surveyed by the club antenna specialists. Deciding how many transmitters to use depends mostly on how many indivudual antennas can be set up for simultaneous operation as well as how many operators are available for the 24-hour stretch. Of course, an abundance of equipment is desirable.

Propagation conditions for Field Day and Sweepstakes generally favor the lower bands since they usually remain open all night. Success on the higher frequency bands (10 and 15 meters) depends primarily on catching the short-duration openings. The old trick of tying a rock to the end of a long piece of wire, tossing it into the tallest tree and loading it with a coupler just won't "cut the mustard" anymore. Gain and directivity into the dense population areas is the goal. However, the antenna must be simple to construct, easy to tune, and moderately stable against the wrath of Murphy and Mother Nature.

Our club decided to try a 2-element full-sized cubical quad for 40 meters. The immediate reaction within the more conservative ranks of our club was, "A 40-meter quad? It'll never work — the first breeze will knock it down!" With these objections in mind, we went ahead with our plans. Our location was approximately rectangular in shape, 60 feet wide, 500 feet long (18 × 152 m) and above the rest of the terrain. Of course, it just happened to be one of the highest locations in Winnebago County, IL!

The sketch illustrates the basic construction of the quad. Dimensions were estimated using the formula

$$L(\text{feet}) = \frac{248}{f(\text{MHz})}$$

where L is the length of one side of the diamond.

The parasitic element was constructed as a reflector using an extra long stub. A small relay shorts out the stub, thus converting the parasitic element from a reflector to a director (see Fig. 15).

The resonant frequency of the driven element is 7150 kHz, the middle of the band. The distance L for the driven element is 34 feet 8 inches (10.57 m). The parasitic element dimension is 5 percent smaller than the driven element. The stub is constructed so that the total circumference of the parasitic element with stub in the line is 5 percent greater than the driven element. L for the



Fig. 15 — A simple relay arrangement is used to short out the stub and change the pattern of the antenna from one direction to another. A small plastic bag provides weatherproofing in the event it rains. (Doesn't it always?)

director is 33 feet (10.06 m). The stub length is 6 feet 9 inches (2.06 m). Eight-inch (203-mm) plastic spacers are placed between the two wires of the stub.

Supporting the quad is very simple. The mast is 50 feet (15.24 m) high, and guyed with nylon ropes. The boom is constructed from two telescoping sections of electrical conduit and is 18 feet (5.49 m) long. The elements are made from no. 14 stranded wire. The driven element is fed directly with RG-58/U coaxial cable. Location of the stub short is determined by the point of maximum front-to-back ratio. The boom-to-mast construction utilizes the support base from a Ham-M rotator. All it takes is a couple of U bolts and the boom-to-mast assembly is complete (see Fig. 16). The wire is strung from the end of the boom and is supported by a small piece of nylon rope and an egg insulator.

Results

Orientation for the quad was east and west. Favoring the eastern direction was the driven element/reflector combination, whereas the driven element/director combination was broadside to the western direction. A local amateur, approximately 5 miles (8 km) west of the Field Day site, assisted in tuning the quad for maximum front-to-back ratio. The end result was approximately 25 dB.

Results were a tremendous surprise! The antenna worked just as planned. The class of entry for simultaneous operation of two transmitters was used. One transmitter operated on 20 and 80 meters; the second transmitter was set up for 15 and 40 meters. Our club, W9AXD/9, scored third place in the two-transmitter class. Our biggest totals came from 40 meters — 693 contacts, over one third of our total number. For the first four hours of the contest, the antenna was aimed east. A rate of 90 contacts per hour prevailed for five solid hours. From that point on it was a steady decline after a sharp drop to about 45 contacts per hour. It was later surmised that the reason for the drop in contact rate was lack of activity and difficulty in finding stations that hadn't been worked before. The East Coast QRM was drastically reduced by changing the switch from "east" to "west." By midmorning we were surprised to find only a dozen W5 stations listed in the log. The antenna may not have been too effective in the southern direction.



Fig. 16 — The bottom section of a CDE Ham-M rotor can be adapted to serve as a boom-to-mast bracket.

There is no reason why this arrangement could not be used for DX operating. The antenna could be positioned just underneath a beam for the higher frequency bands with the peak of the diamond supported from a boom placed through the top section of the tower.

This material was originally presented in *QST* by Peter H. Grillo, W6RTT.

Build This C-T Quad Beam for Reduced Size

This quad-beam antenna, while smaller in size than a conventional quad, performs like a veteran. The trade secret is to use capacitive tuning.

One of the main drawbacks of the quad beam is its large size compared to the Yagi beam. Previous efforts to reduce the size of the quad have utilized systems of inductive tuning. Loading coils have been used on one or two sides[1] or in the corners. Linear inductors on the vertical sides have also been used.[2] The purpose of this article is to explain a simple method of capacitive tuning to reduce the size of the quad. The C-T (capacitor-tuned) loop is diagrammed in Fig. 17.

It is well-known that the physical size of the dipole antenna can be reduced by replacing a portion of the antenna with a capacitive body and adding an inductor to restore the system to resonance. It seems less well-known that the full-wave loop antenna also may be reduced in physical size while holding the resonant frequency of the system constant by adding capacitance at the voltage loops. No inductors are needed. The capacitance may be added by any of the methods shown in Fig. 18.

The outside dimensions of the C-T loop may be anything chosen by the builder with the larger limit being the full-size, full-wave loop. The limit on the amount of size reduction effectively attainable depends both upon the electrical resistance in the circuit and upon the tendency in loop antennas for the current to become equal at all points in the circuit when the loop becomes very small in proportion to the free-space wavelength at the frequency under consideration. The geometrical shape of the loop is unimportant to basic operation provided that the capacitance is placed at or between the voltage loops. The bottom half of the chart in Fig. 21 shows the effective dimensional range of the C-T loop. The top half shows the tuning range that can



A winter snow sets the scene and accentuates the diamonds of the C-T quad-beam antenna at W7WKB.



Fig. 17 — The C-T quad design with arrows indicating current flow for 1/2 cycle. The center capacitor is located at the minimum-current (highest-voltage) point in the loop. Each side is less than 1/4-wavelength long. See text and Fig. 21.



Fig. 18 — Methods of adding capacitance to the C-T loop are shown here. In Fig. 18C, if the center-back wires are placed too closely to the center-in wires, they become ineffective. A 12-inch (0.3048 m) spacing from the end of the center-back wire to the center-in wire is satisfactory. Wires running back toward the loop center may be attached to the outside ends of the center-back wires if more capacitance is needed. In Fig. 18D, the capacitance added by the center cross wires varies with both the length of wire and spacing between wires.

be expected by using various methods of adding capacitance to the diamond quad. These dimensions are intended as guidelines only.

The feedpoint resistance of the full-size, 1-wavelength loop is about 100 ohms. The feedpoint resistance of the C-T loop decreases as it is made smaller but will offer a good match to a 50-ohm coaxial line over the entire usable range as shown in the chart. A gamma match may be used if an exact match is desired.

More than one C-T loop may be used to form the C-T quad beam. A parasitic reflector was used in this installation because of the higher radiation resistance attainable while maintaining good gain. Maintaining the radiation resistance as high as possible is particularly important in small beams, both to keep efficiency high and to prevent the bandwidth from becoming too narrow.

Tuning and Mounting

The use of a grid-dip meter to attain initial band resonance is very helpful. By using a grid-dip oscillator, this beam was tuned initially with the driven element to resonate at the center of the band of interest. The reflector was then tuned to resonate at a frequency three percent lower than the driven element. Final adjustments were made using a test oscillator located about 1000 feet (300 m) away as a reference signal.



Fig. 19 — Dimensions for the 40-meter C-T quad are shown above. For the 2-element beam the spacing between the driven element and the reflector is 20 feet (6.10 m). The length of the center-back wire (dimension A) is 12 feet, 9 inches (3.89 m) for the reflector, and 9 feet, 11 inches (3.02 m) for the driven element.



Fig. 20 — A variable capacitor is illustrated here. It can be used to tune the C-T quad. The eight-inch (203-mm) tubular portion is made from plastic water pipe. The cylindrical capacitor plates are formed from a copper sheet. One plate slides inside the eight-inch (203-mm) tube and the other over the outside of the tube. Maximum capacitance is approximately 25 pF.



Fig. 21 — The chart shown above, providing dimensional guidelines for a single C-T loop, is based on the equation LF = C, where L is the outside dimension in feet, F is the frequency in MHz, and C is a constant chosen for the size of the C-T loop to be constructed. Use the largest size possible for the best electrical results. This is particularly true when using C-T loop elements to form a parasitic beam.
To use the chart, pick the largest C (up to C = 1005) feasible for your application. Use bottom half of the chart to see if the C-T loop will operate at the dimensional size selected. Then refer to the top half of the chart for the recommended capacitance method.

Table 3

Data for plotting SWR curve. Information in this table is used for plotting the SWR curve for the 40-meter C-T quad beam, as described in the text.

Frequency (MHz)	*SWR*
7.500	4.87
7.450	4.00
7.400	3.08
7.350	2.33
7.300	1.82
7.275	1.78
7.250	1.94
7.200	3.44
7.150	5.25
7.100	8.08

The director was tuned for lowest SWR and the reflector for best gain. If you lack a grid-dipper, initial resonance can be established by listening to your station receiver for a strong signal while making the adjustments. A dramatic increase in signal strength will be noticed at resonance. Tuning is accomplished by shortening or lengthening the capacitance wires.

The single loop or beam may be mounted either horizontally or vertically for horizontal or vertical polarization, but in either case it should be mounted as high above the ground as possible. Loop antennas operating close to ground will show a much higher feedpoint resistance than normal and will waste considerable power in groundheating effects. A rough guideline is to mount the antenna so that the bottom point is at least half the loop diameter above the ground.

The working 40-meter version of the C-T quad beam had a diamond configuration because of the greater mechanical strength and because of the longer center wire for tuning purposes. Final dimensions are shown in Fig. 19. A good quality center insulator should be used because of the high voltages present at the center.

A tubular tuning capacitor was originally installed in the driven element and worked well until the kW power level was reached. It then promptly arced over, leaving a conductive carbon deposit. A version using 2-inch (51-mm) plates as shown in Fig. 20 adequately tuned the reflector even at the kW level for some time. The capacitors, as shown, were not tried under wet conditions, but would probably be satisfactory at power levels up to 400 watts. For long-term use, the method shown in Fig. 18D is preferred over plate-to-plate capacitors because the high voltages are handled more easily.

Because some dielectric heating was noticed in this capacitor, the wire-tuned version was adopted. The wire version is recommended over the methods shown in Fig. 18D and 18E, any time the loop is large enough to be tuned by no more than one doubled-back wire (as shown in Fig. 18C). Tuning wires eliminate the capacitor with its heat loss and allow somewhat better current distribution. Less center radiation occurs because of partial cancelingeffects in the doubled-back wires. It would be wise initially to cut each center-back wire 12 inches (0.31 m) longer than shown to allow tuning. Pruning each center-back wire by 1 foot (304.8 m) increases the resonant frequency by roughly 100 kHz in the 40-meter version. No. 14 Copperweld wire was used throughout.

Performance

The antenna described performed up to expectations and has prompted many complimentary reports. The SWR curve information shown in Table 3 was attained using a 75-ohm coaxial feed line without any matching network. The SWR would be lower if a 50-ohm line or if a matching network were used. Forward signal strength as compared to the strength to the rear showed a maximum 30-dB difference as measured by means of the receiver S meter. Typical difference, as finally adjusted, was 12 dB.

The gain of the C-T quad over a comparable double Zepp (full wave on 40) was typically at least one S unit better when both antennas were at a height of 45 feet (13.7 m). The Zepp was better on very short skip but the C-T quad consistently was favored on longer skip. When elevated to 65 feet (19.8 m), the C-T quad gave outstanding results. At this height, two S-units improvement over a vertical antenna at distant points was noted many times.

The C-T quad may be built for any band. It should be most useful in meeting requirements for an inexpensive easily tuned wire-beam antenna where the full-size quad is unsuitable for mechanical or economic reasons. This material was orginally presented in *QST* by Roger Sparks, W7WKB.

References

[1] Pinner, "The Short Quad," *QST,* February 1964.

[2] Courtier-Dulton, "Some Notes on a 7-MHz Linear-Loaded Quad." See Chapter 4.

A Nearly Full-Size, Rotatable, 2-Element Quad for 80 Meters

We don't expect readers to rush right out and duplicate this antenna system — but this doesn't mean a lot of hams wouldn't like to!

Many hams have been thinking about new 80-meter antennas to improve their DX capabilities. On the higher amateur frequencies, antenna gain is relatively easy to acquire with a compact Yagi or quad. It is much harder in this respect on 40 meters. On 80 meters, however, the problem of securing any increase in antenna gain over a conventional dipole or groundplane is very difficult indeed, particularly where space is limited. Rhombics, Vs or multi-element collinear arrays become completely impractical on the normal urban or suburban lot. Even a phased vertical array is hard to handle on a city lot, and too often, performance is marginal because it is impossible to install an optimum ground system at such a location.

The author solved this problem at his QTH by constructing an almost full size 2-element quad for 80 meters. A unique tuning arrangement permits this antenna to be operated at any frequency within the 80-meter band with an SWR of close to 1. While certainly not adaptable to every individual's situation or pocketbook, a description of this antenna should be of interest to many amateurs. As far as it is known, this is the first and only set of beams, on one rotatable tower, covering all bands from 2 to 80 meters. By connecting the 2 quad elements in series to form a rotatable, bidirectional loop, the frequency coverage has been extended to 160 meters.

At this point, a few comments might be in order on the circumstances which led to this sizeable 80-meter antenna project. In June 1965, the writer returned to ham radio activity after a QRT of almost 30 years. During the first year of operation, the antennas of K3JH were a conventional commercial tribander for 10, 15 and 20 meters mounted on a 60-foot (18.3-m) tilt-over tower, and a trapped, inverted V for 40 and 80 meters. A bit of DX chasing soon led to the conclusion that better antennas were needed. Since the QTH is on a suburban lot about 175-feet (53.3-m) square, and heavily wooded, a "Christmas tree" array seemed the best alternative. Consequently, in the summer of 1966, with a great deal of help from Bob Scully, W2FXN, a 115-foot (35-m) rotary tower was installed along with full-size monoband beams for all bands from 2 through 40 meters.



The bottom support of the quad elements is shown in this view, along with the tuning-network box, which is mounted on the mast.

This rotary steel tower is 16 inches (0.41 m) OD at the base with 1-inch (25-mm) thick walls. The tower rests in a 1/2-inch thick steel bearing-tube 15 feet (4.57 m) long and 20-inches (0.51-m) OD. The bearing tube is imbedded in a block of concrete 8 × 8 × 16 feet (2.44 × 2.44 × 4.88 m) which weighs 70 tons. The tower tapers to 5-1/2 inches (140 mm) at the top, and was designed to carry nine full-size monoband beams through 125-mph winds.

Initially, the antenna complement was as follows

2/6meters — Vert. groundplane at 115 feet (35 m)
6 " — 6 el at 113 feet (34.5 m)
2 " — 15 el at 109 feet (33.2 m)
20 " — 5 el at 104 feet (31.7 m)
15 " — 5 el at 96 feet (29.3 m)
10 " — 6 el at 86 feet (26.2 m)
40 " — 3 el at 77 feet (23.5 m)

A rotary ball-bearing ring and clamp at the 70-foot (2.13-m) level on the tower was used to support one end of an inverted L for 80 meters. This long wire, which could be used also on the higher frequencies, was fed through a Matchbox at the base.

Performance on 40 through 2 meters with this antenna system was generally excellent. The L and inverted V on 80, however, left much to be desired, especially when compared to the antenna performance on the other bands.

In attempts to improve this situation, several different 80-meter antennas were installed at various times between 1966 and the spring of 1969. Included in this effort were a top-loaded groundplane and a pair of phased verticals. None of these antennas provided sufficient improvement in DX performance on 80 to be considered satisfactory.

With the advent of the 5-Band DXCC, the question of how to do better on 80 meters again became a matter of concern. It was at this time that the concept of a quad of some sort, to be mounted on the rotary tower, began to emerge. Since 40-meter quads had been constructed previously, and were mechanically feasible, the thought at first was to build a half-size quad for 80 meters, using loading coils. Preliminary calculations indicated the possibility of achieving some gain over a dipole in addition to the obvious advantage of being able to rotate the array.

It was quickly determined that a half-size quad mounted at 57 feet (17.4 m) would fit underneath the 40-meter Yagi. Construction could be quite conventional using fiberglass X frames in each element, and a spacing of 0.15 wavelength.

Design Considerations

The proposed design was discussed with a number of amateurs including Jim Lindsay, W0HJ, Dunc Carter, W5IOU, and Claus Moeller, DL7CM, who were most helpful with advice and suggestions. A search of the literature disclosed that a number of loaded antennas of various types had been built. In most cases, however, performance had been judged empirically, and there was little in the way of specific comparative data on the performance of loaded versus unloaded configurations, or versus a reference dipole. Because of this, the decision was made to build and test a 14-MHz model of a half-size quad. This would enable a direct comparison between the performance of a miniaturized quad and other antennas. Of particular interest was a comparison with a dipole, since this was the more normal antenna used by amateurs on 80 meters.

Henry Pemberton, W3PN, who had become interested in the project, provided the X frames and supports from an old 20-meter quad, for use in the test model. Tom Consalvi, W3EOZ, provided some suitable coil stock for the test design. With this help, the 14-MHz model was quickly constructed. No trouble was experienced in pruning the coils and resonating the loops. Except for one bad piece of insulation on one coil, which promptly burst into flame when rf power was applied to the antenna, the driven element could be fed with a full kilowatt at an SWR of 1. The SWR, however, would rise sharply when the coils, which had no protection from the weather, became wet from rain. All testing, therefore, had to be done on dry days.

Since the 80-meter version was to be mounted on the tower one-quarter wavelength above ground, the 14-MHz model was mounted for the tests at the same relative height. Standard procedures for tuning up the quad were used, and will not be detailed here. Impedance of the loaded loop was measured at 60 ohms, so it could be driven nicely with a 50-ohm line. The bandwidth was 125 kHz, measured between frequencies each side of the resonant frequency where the SWR was 3:1. This was the result expected, due to the heavy loading.

Extensive on-the-air comparisons were made between the model and various other antennas. These included a dipole at the same height above ground as the model, a 3-element tribander at 60 feet (18.3 m), two different inverted Vs at 50 feet (15.2 m) and a 5-element monoband Yagi at 104 feet (31.7 m). The regular antenna switching arrangements in the station were such that almost instantaneous comparisons could be made between the different antennas, minimizing QSB differences in the receiver. In the transmit mode, many amateurs compared signal differences between the test model and the other antennas. It is impossible to list the calls of all those who helped in this way.

After considerable testing, adjustment, readjustment, and minor configuration changes in the model, the results were found to be quite discouraging. The simple conclusion was that a loaded half-size quad had insufficient gain compared to a dipole to warrant proceeding any further with an 80-meter version.

Further Exploration

Before abandoning the 80-meter project, however, we decided to explore some practical ways to increase the size of the elements, preferably without using the normal-type quad X frames, which would be difficult if not impossible to handle when the antenna grew too large. This thinking developed the concept of using the 14-MHz boom at 104 feet (31.7 m) to support diamond-shaped elements at the top, and using a boom and spreaders rather than an X frame to hold the elements at the center. The bottom of the quad elements could be supported easily with a relatively light boom and spreaders near the base of the tower.

In order to reduce the size of the center boom and spreaders, the first model was kite-shaped with an included angle at the top of about 50 degrees. Unfortunately, the results were poor, and compared to a dipole there was no gain. We concluded that this configuration was so squashed together that the antenna was acting like a dipole instead of a quad. A series of configurations was then drawn up on paper. The boom and spreader sizes were varied, but the included angle at the top of each diamond element was kept at 75 degrees or more. This helped to pin down a configuration which would be mechanically feasible, and which would be a reasonable compromise among the various considerations to be taken into account. The one selected is shown in Fig. 22.


A detailed view of one of the quad elements, showing the method of supporting the loop.

Because these elements are almost full size at 4 MHz, making a 20-meter model quite large, it was decided to build and test a model of this configuration on 15 meters. The test procedures for this model were the same as those previously described for the 20-meter model of the half-size quad. This model showed substantial gain compared to the reference dipole at the same height. Also, the model mounted only 15 feet (4.6 m) above the ground compared favorably in performance with the tribander at 60 feet (18.3 m). The 5-element monobander at 96 feet (29.3 m) consistently provided better gain, as was to be expected. The impedance of the driven element was about 80 ohms. Bandwidth between SWR points of 3:1 was 250 kHz, or about twice what was measured on the half-size model.

Mechanical Considerations

After a lengthy test period, during which many on-the-air comparisons were made, the results were good enough to make the decision to build an 80-meter version of this antenna. Because of the size of the proposed antenna, considerable thought had to be given to the mechanical design to assure longevity comparable to the other beams which are rated for 125-mph winds. The wire in the quad elements is no. 12 stranded copperweld. All other metal in the antenna is aluminum or stainless steel. The two quad elements are suspended from the 20-meter boom at 104 feet (31.7 m). The insulators are five glazed porcelain knobs. Spacing is one-eighth wavelength, 36 feet (10.97 m). The 20-meter boom is 46 feet (14.02 m) long, and is made from 4-inch (102-mm) OD, 1/4-inch (6-mm) wall T-6 aluminum tubing at the center, and similar material tapering from 3-1/2 inches (89 -mm) to 3-inch (76-mm) OD at the ends. A 1/4-inch stainless steel cable supports the boom 18 feet (5.49 m) out from each side of the tower. Originally, the plan was to slide the quad elements down this cable from the tower. Unfortunately, the steel plates holding the Yagi elements to the boom on the other beams were found to be rusting because of poor plating. Rather than dismantle the beams, a crane was brought in so that these plates could be cleaned and painted by a man carried up in a boatswain's chair. At the same time, the elements were hung from the 20-meter beam, and the center boom and spreaders for the quad were installed with relative ease.

Dimensions

The 36-foot (10.97-m) center boom at the 57-foot (17.37-m) level of the tower is made of a single 24-foot (7.32-m) section of 3-1/2-inch (13-mm), 1/4-inch (6-mm) wall, T-6 tubing with 7-foot (2.13-m) sections of 3-inch (76-mm) OD pipe telescoped and bolted at each end. The boom is supported from the tower with a 3/16-inch (4.76-mm) stainless-steel cable. The spreaders at each end of this boom are 70 feet (21.34 m) long. Each consists of a 24-foot (7.32-m) piece of 2-1/2-inch (64-mm) OD, 1/8-inch (3-mm) wall, T-6 tubing at the center, with two short pieces of 2-1/8 × 1/8-inch (54 mm × 3-mm) tubing telescoped and bolted at each end to make up a length of 30 feet (9.14 m). To complete the spreaders, 20-foot (6.10-m) sections of 1-1/2- and 1-1/4-inch (38- and 32-mm) fiberglass poles are attached to each end of the aluminum centerpiece. Use of the fiberglass reduces weight and eliminates a one-quarter wavelength piece of metal from the middle of the quad element. A 1/8-inch (3-mm) cable and strut supports each spreader to minimize sag, which is very slight as may be noted in the photograph. A welded aluminum T structure and stainless steel clamps are used to hold the spreaders on to the ends of the boom. A stainless steel clamp and Teflon grommet is attached to the ends of each spreader to hold the element wires in place. The only function of the spreaders is to hold the two opposite sides of each quad element apart without too much fore and aft flopping around when the antenna is rotated. The length of the spreaders, wind loading, and safety factor dictates the heavy mechanical design.

The lower boom, which is 23 feet (7 m) off the ground, is made of a 24-foot (7.32-m) section of 2-1/4 × 1/4-inch (57- × 6-mm) T-6 tubing with shorter 2- × 1/4-inch (51- × 6-mm) pieces telescoped and bolted at each end to make the total length of 36 feet (10.97 m). To maintain symmetry, 17-foot (5.18-m) spreaders are attached to each end of the lower boom. These spreaders are made of 1-1/2-inch (38-mm) fiberglass. They are attached to the boom with aluminum angles and stainless-steel clamps. A light stainless-steel cable and strut holds the lower spreaders firm against the pull of the quad-element wires, which are attached to each end of the lower spreaders with stainless-steel clamps. The wires are taped along the fiberglass almost to the center of the spreaders, and then go off at right angles to the tuning box, which is mounted on the tower 13 feet (4 m) above ground. The distance from the end of the lower boom to the tower is about 18 feet (5.5 m), and the 36 feet (11 m) of wire which connects the quad proper to the tuning box represents loading.

Tuning

Each element, including the 36 feet (10.97 m) of connecting wire just mentioned, resonates at 4050 kHz. Thus, a small amount of additional inductive loading is required to tune the antenna to resonance within the 80-meter band. This is accomplished by putting two relatively small motor-driven coils in series with each loop of the antenna. The reversible motor for each pair of coils in each loop is controlled by a two-way toggle switch mounted on the antenna control panel in the shack. In the case of the driven element, tuning is accomplished simply by applying power to the antenna and then adjusting the loading inductances by the motor-control switch to the point where the SWR is minimum, usually very close to 1. Tuning the reflector can be accomplished by turning the back of the quad toward a distant signal, and adjusting the reflector loading coils for minimum received signal. This seemed a bit cumbersome to do each time the operating frequency was changed from cw to ssb and vice-versa, so a microswitch was added to the reflector coils and motor assembly. Each revolution of the coils flicks the microswitch, which actuates a light on the control panel in the shack. By counting the blinks of the light, and referring to a chart which shows the resonant frequency of the reflector versus the number of turns of inductance in the loop, the reflector can be tuned to any desired frequency. With this tuning scheme, it is quite easy to tune the quad for best performance at any point in the 80-meter band. The bandwidth between the 3:1 SWR points is close to 200 kHz, so retuning is required only for large frequency changes within the band. Frequency flexibility otherwise is quite good.


QUAD LOOP DIMENSIONS
104'
(31.70m)
75°
56-1/2'
(17.22m)
57'
(17.37m)
70' ACROSS
(21.34m)
105°
44-1/2'
(13.56m)
23'
(7.01m)
7'
(2.13m)
18' (5.49m)
THESE TWO WIRES RUN OFF AT NEARLY 90° TO THE PLANE OF LOOP TO THE TUNING BOX
252' (76.81m) OF WIRE IN EACH LOOP, INCLUDING LEADS TO TUNING BOX

Fig. 22 — Dimensions of one of the quad loops.



Here is the complete antenna system, 2 through 160 meters, all rotatable, directional arrays.

The impedance of the driven element measures about 75 ohms. The antenna is coupled to the transmitter through a balun and 50-ohm line. The difference between the resonant frequency of the driven element and the reflector, when the latter is tuned for maximum front-to-back ratio, is in the order of only 1-1/2 percent. This probably results from the quad being only a one-quarter wavelength above the ground. The front-to-back ratio is about 20 dB, and the front-to-side, 50 dB. All measurements have an indicated gain over a dipole in the order of 6 to 7 dB. No degradation in performance, or SWR, has been observed during heavy rain. The small loading coils are protected from the weather, of course, in their aluminum tuner box, so the problem, which was encountered with unprotected load coils in the 20-meter test model, has been eliminated.

Tests were conducted with the second element tuned as a director instead of a reflector; there was no noticeable improvement in gain, whereas the front-to-back ratio was diminished. It is felt that the best results are obtained with the reflector.

Some thought was given to driving both elements at a 135-degree phase difference to obtain a cardioid pattern. It is felt, however, that the conventional quad pattern, with deep nulls on each side, and a reasonably good front-to-back ratio, is more desireable for DX. So, nothing further has been done with such a phasing arrangement.

Results

DX results on 80 meters have improved considerably since the new antenna was put on the air. On cw, the gain seems to drop off somewhat as compared to the phone end of the band. Probably this is due to the fact that the relative size of the antenna is smaller at the cw operating frequencies. Nevertheless, reports usually are from one to several S units higher than other U.S. stations with comparable power input, and conventional antennas. In most instances during pile-ups in a recent cw contest, it took only a call or two to get through, whereas, previously, the station was usually last. It was found also that contacts could be made earlier, as the band opened. In several instances like this, it was amazing to get a response from a DX station, and then to hear other U.S. stations calling without success.

Reports from overseas on ssb are outstanding. During a recent phone contest, several dozen DX contacts were made in just a few hours — everyone on the first call.

During the day, on 80 meters, it is quite easy to work into Canada or the Carolinas with good signals at both ends of the circuit. On a dipole, very often the other station is completely unreadable, if not inaudible. This points up the fact that one notices great improvement in reception with the quad compared to a dipole, which on 80 is just as important as being able to transmit a better signal.

Once it was determined that the quad worked well on 80 meters, the possibility of operating the antenna on 160 meters was explored. Since the loops independently resonated at 4050 kHz, and there was considerable inductive loading available in the coils, it was felt that it might be possible to resonate the antenna on 1.8 MHz by putting the two loops in series. Actually, with the load coils tuned to minimum, the series-connected loops resonated at 1775 kHz because of the mutual coupling. By shortening out the coils entirely, the pair of loops were resonated at 1805 kHz. Therefore, the SWR at the low end of the 160-meter band is very low.

Domestic reports on 160 meters have been excellent. Consistent directional effects have been noted by several observers when the two-turn loop is rotated. The pattern is the typical figure eight, with deep nulls off each side of the loop. It remains to evaluate how well the antenna works on 160-meter DX.

Following completion of the antenna in September, there have been several severe storms, with winds gusting as high as 65 mph. These velocities barely moved the wires and spreaders around. It is apparent that the heavy construction is adequate to handle the winds of much higher velocity for which the antenna was designed. Although it is probably one of the largest quads in existence, it certainly appears as though it will stay up a long time, even through rough weather.

In conclusion, this project could never have been completed successfully without the help of many domestic and overseas amateurs. Their reports, advice, and assistance will always be appreciated. Although this has been a sizeable and difficult antenna task, a great deal of satisfaction has been derived from carrying it through from concept to on-the-air operation. The simple lesson has been relearned with regard to antennas — that one cannot get something for nothing. Mini-size antennas are better than no antennas, but there is no substitute for full-size antennas if one wants full-size results. This material was originally presented in *QST* by Joe Hertzberg, N3EA.

The Folded Mini Quad

A full-wavelength loop can take a variety of forms. Despite the shape suggested here, the author claims good results.

An unusual type of full-wavelength wireloop antenna is in use here on 2 and 15 meters. The design, which the author had not seen previously, provides an antenna that occupies minimum space; the antenna is omnidirectional, vertically polarized, broadbanded and requires no groundplane.

It evolves from a full-wavelength loop.[1] The loop, if fed on the side (x-y) as in Fig. 23A, radiates a vertically polarized signal. The radiation pattern is bidirectional, with maximum radiation broadside to the plane of the loop and with the highest field strength in the plane A-A′.

The loop can be deformed into a square, such as in the elements of a quad, and without much loss of efficiency into a rectangle (Fig. 23C). Vertical polarization, bidirectional signal pattern and maximum radiation from the plane A-A′ are retained.

A 90 degree bend at A-A′ and two further right angle bends at B-B′ and C-C′ transforms the flat loop into a cube. The circumference is still a full wavelength and each side of the cube measures 1/10 wavelength. Again, vertical polarization is retained, but the appreciable bidirectional radiation from the sides of the cube adjacent to A-A′ leads to a nearly omnidirectional radiation pattern.

My 2-meter antenna was constructed from aluminum clothesline wire; the length in feet was chosen by 1005/f MHz. It is fed with 50-ohm coaxial cable through a Pomona Electronics no. 1699 adapter and no matching device is used. The SWR is less than 1.2:1 from 144 to 146.5 MHz and climbs to 1.4:1 at 148 MHz. The radiation pattern was measured with a simple field-strength meter, using a half-wave dipole as pickup element and a 20-kΩ resistance in series with the 20-μA meter to improve linearity.[2] The front-to-back ratio is 1.8 dB with no prominent sidelobes apparent, but a rather sharp 3-dB dip is caused by the "shadow" of the feed line and hardware.



Fig. 23 — Conversion of the full-wavelength loop to the space-saving cubical configuration. The length of the wire and the vertical polarization remain but the pattern changes from bidirectional to omnidirectional. The spacing between the feed point and the adjacent side is not critical. The spacing on 2 meters is about 1-1/2 inches (38 mm), and on 15 meters is about 4 inches (102 mm).

Performance

Fed with 10 watts and used as an indoor antenna, it gives consistent communication with 2-meter fm base and mobile stations within a 10- to 15-mile radius. It performs better on receive and transmit than a 1/4-wave whip at the same location.

A 15-meter version of the antenna was then constructed and suspended in the attic with string and tacks. It is operated with 100 watts and the rig loads almost as well as the 2-meter version, but with a slightly higher SWR. The first contacts were with California and it has since given excellent performance to the West, Midwest and South as well as to South America and Europe.

The close proximity of antenna sections radiating out of phase may lower the efficiency over that of a loop, yet, in terms of space requirement, construction cost and ease of installation (no radials!) and tuning, the antenna is hard to beat. As a full-wave loop it should have a slight edge over a vertical. The author recommends further experimentation and modification, e.g., into the even more space-saving configuration of a cylinder. This material was originally presented in *QST* by Max Blumer, WA1MKP, SK.

References

[1] *The ARRL Antenna Book*, 13th ed., 1974, p. 65.

[2] *The Radio Amateur's Handbook*, 46th ed., 1969, p. 553.

A Convenient Stub-Tuning System for Quad Antennas

The cubical quad has been a popular antenna with amateurs for a number of reasons — relatively light weight, small turning radius, low cost, and good DX performance at rather low heights when compared to other antennas. The authors' experience with quads has demonstrated, however, that best possible performance requires careful parasitic-element tuning. Cutting elements according to various "established" length formulas has often yielded less than satisfactory results. While adjustments for maximum forward gain are generally uncritical, a mediocre front-to-back ratio often results unless time and care are taken to tune the parasitic elements. Factors such as spacing between elements, proximity of the antenna to ground, or influence of other objects (including the other concentric loops in a multiband array) require that the electrical length of the parasitic elements be adjusted using empirical methods if optimum performance is to be realized from the system. It was felt that if one was going to the trouble of erecting a good antenna system, it was worth seeing to it that the antenna was delivering the performance of which it was capable.

These considerations led to the development of the parasitic-element tuning system described here. While the scheme is applicable to quads in general, whether rotary or fixed, the original intended application was in a fixed two-element, full-size 40-meter quad. The descriptions here apply to this 40-meter system, but the general information allows one to follow the same scheme with a quad for any band.

A 40-Meter System

This 40-meter antenna consisted of two non-rotatable full-wave wire loops suspended from a boom which was mounted near the top of a tower. Spacing between elements was 22 feet (6.71 m). The corners of the loops were tied down to convenient anchor points by means of ropes, thereby eliminating the need for spreaders. With the elements thus fixed in place, the antenna was oriented in one general direction and could not be steered elsewhere. A driven-element and reflector combination was used.



The matching network built by the authors for the modified 40-meter system. Relays, used in the switching circuitry, are not visible. The builder is left to choose a suitable network of his own to meet his operating requirements. Basic design information can be found in *The Radio Amateur's Handbook* or *The ARRL Antenna Book*.

Early experiments with the antenna demonstrated the need for careful reflector tuning. Several trips were made up the tower to alternately prune and add wire to the reflector before the antenna exhibited good performance at the frequencies of interest. But when tuned properly, the quad really performed! In many instances signals which were inaudible while using an 80-foot (24.4-m) high reference dipole were perfectly readable with the quad (at a median height of about 100 feet [30.5 m]). Reception was further enhanced by rejection of unwanted signals off the back of the quad.

Now if only the quad could be made rotatable. . . . Unfortunately, a full-size rotating system (spreaders would be needed) was out of the question. The cost, difficulties of construction and installation, and the severe effects of New England winters discouraged such ideas. The authors, being avid contesters and DXers, were willing to settle for the next best alternative — keeping the fixed quad, but electrically switching its pattern.

The solution involved a tunable stub attached to one of the elements to lengthen or shorten it electrically. With the appropriate stub switched in, the single element could be made to look like either a reflector or director and thus cause the pattern to be reversed. In order that adjustments be made quickly, easily, and from a convenient location (such as the shack or the bottom of the tower), it involved more than the conventional short stub often used with quads. Rather, the situation called for a long stub — long enough to reach the desired remote location — terminated in a variable reactance. Tuning the element, then, involved nothing more than adjustment of the value of reactance which could be provided conveniently by means of a variable capacitor.

The electrical principle is simple. One adds inductive reactance to lengthen an element electrically, or capacitive reactance to shorten it. Typically, the former arrangement is used with quads in a driven-element and reflector combination in which both elements are cut to the same physical length. A stub, shorted at the end, is attached at the center of the bottom section of the reflector. By varying the position of a shorting bar along the stub, the amount of inductive reactance presented to the element can be varied and the electrical length altered correspondingly. Because the stub is short in length, this adjustment must be made at the antenna itself, preferably near or at its final height.

Now, if the stub is cut to some different length which happens to be longer than in the above case, the parasitic element can still be made to see the proper amount of inductive reactance (if it is a reflector) provided the stub is terminated properly with some other reactance (in general, something other than a short). Varying the reactive termination is then equivalent to moving the shorting bar along the conventional stub. This is a consequence of the impedance-transforming property of transmission lines. The long stub can be treated as a transmission line. If we know its characteristic impedance, its length, and the impedance that must be seen at the parasitic-element end of the line, the Smith Chart can tell us what kind of termination is required at the opposite end.

A reflector cut to the same physical dimensions as the driven element — self-resonant at the desired operating frequency — must "see" roughly 150 ohms of inductive reactance at the terminals where the stub is attached. Although little information is available about the use of directors with quads, it is assumed initially that a director, also cut to the same length as the driven element, must see a roughly equal but opposite amount of reactance, or about 150 ohms of capacitive reactance. If one desires to make the termination at the end of the stub a variable capacitor for convenience of tuning, which was the case in the 40-meter system under consideration, the problem can be rephrased slightly: what length of line of a given characteristic impedance is required so that a variable capacitor (a 10- to 350-pF unit was used) causes the parasitic element to see the above reactances? This is easily solved with a Smith Chart. Two somewhat different systems evolved from these ideas. The second, a modification of the first, will be described last.

The design procedure for the 40-meter version went as follows: The driven and parasitic elements were cut to the same length, given by the more or less standard formula, $L = 1005/f$, where L is the length in feet, and f the frequency in MHz. This resulted in a loop circumference of 143 feet, 6 inches (43.74 m) at a frequency of 7.0 MHz. In the practical installation, the loops were triangular in shape rather than


22'
(6.70m)
ARRAY SHOWN POINTED IN THIS DIRECTION
DRIVEN ELEMENT
PARASITIC ELEMENT
72-OHM TWIN-LEAD FEED LINE
450-OHM OPEN-WIRE LINE STUB
TO SHACK
12λ + Nλ/2
N=0, 1, 2, ...
K1
C1
C2

Fig. 24 — Configuration of 2-element switchable 40-meter quad. Triangular loops are shown, although square or diamond loops can be used too. Both elements are cut to the same dimensions: 143 feet, 6 inches (43.74 m) for 7.0-MHz operation. The selection of either C1 or C2 by means of K1 determines which direction the array is pointed. Switching components K1, C1 and C2, can be installed inside the shack or on the ground. The stub line is cut long enough to reach them. Feeding the driven element with 72-ohm Twin Lead results in a low SWR.

- C1 — 10- to 350-pF air-variable capacitor, adjusted for director operation as described in text.
- C2 — Same as C1, except adjusted for reflector operation.
- K1 — Dpdt relay (Potter and Brumfield KA11DG or equivalent).



Fig. 25— Example of Smith Chart calculations required to arrive at correct stub dimensions. A 10- to 250-pF capacitor is used as the variable-reactance element which terminates the 450-ohm transmission line used for a parasitic-element stub. The chart is normalized to 450 ohms. The arc between points A and B represents the range of reactance of the capacitor as it is tuned between the extremes of its range. If the capacitor is connected to a 0.12-wavelength long stub (plus any multiple of one-half wavelength) with a 450-ohm characteristic impedance, the range of reactance represented by the arc between points C and D is presented to the parasitic element. This range is sufficient to cause a properly cut parasitic element to look like either a director or reflector. Further discussion of Smith Chart calculations can be found in the latest edition of *The ARRL Antenna Book*.

square or diamond. Shape is relatively uncritical — performance is approximately equivalent for the various geometric configurations, and ease of installation was considered more important. The triangle has the advantage of requiring only three tie-off points — one at the top where it hangs from the boom and two at the bottom — whereas the other two forms require support at four corners. Furthermore, the triangle requires less vertical height — approximately 41 feet (12.5 m) on 40 meters, assuming equal-length sides — as opposed to the diamond which needs about 50 feet (15.25 m). The square requires the least vertical height but is the most difficult to support mechanically. The resultant configuration is shown in Fig. 24.

The stub line was made from 450-ohm open-wire transmission line because of its relatively low cost in commercially made form and its low-loss characteristics. The reactance range of the 10- to 350-pF capacitor by itself at 7 MHz was then plotted on the Smith Chart as shown in Fig. 25. (Recall that $X^L = 2\pi fL$ and $X^C = 1/2\pi fC$ where X^L and X^C represent values of inductive and capacitive reactance respectively, given in ohms, L and C the corresponding values of inductance in henrys and capacitance in farads, and f, the frequency in hertz.) The low-capacitance end of the range is indicated as point B in Fig. 25 with the Smith Chart normalized to 450 ohms in this example, while the other extreme comes out at point A. If the capacitor was then connected at the end of a 0.12-wavelength section of the 450-ohm line (approximately 16 feet [4.88 m] in open-wire line), the impedance seen at the other end of the line would vary between the range of slightly greater than +j300 to -j300, represented by points C and D. This would meet the +j150 and -j150 reactive loading requirements of the parasitic element for reflector and director operation, respectively. Actually a stub length of 0.12 wavelength, plus any multiple of a half wavelength, would work too, because any half-wavelength section of transmission line merely repeats at one end the impedance that appears at the other. Thus, the distance to the desired remote location dictates the minimum required line length. Another advantage of using 450-ohm line, as opposed to a line with a lower characteristic impedance, becomes apparent when working examples on the Smith Chart — for a given capacitor tuning range, the 450-ohm line produces a greater range of reactance change at the antenna end of the line. A 300-ohm line would serve almost as well, however, providing only slightly less tuning flexibility.

The stub was terminated at a dpdt relay which was controlled from the station operating position and which was used to select one of two variable capacitors — one adjusted to provide reactance for reflector operation and the other for director operation, as shown in Fig. 24. In this manner, the pattern could be flipped around 180 degrees instantly from the shack. The driven element was fed directly with 72-ohm transmitting-type Twin-Lead. A low SWR was obtained with no special provisions made for matching.

The director and reflector tuning should be done empirically, as was stated before. Experience has shown that quads tune rather broadly for maximum forward gain. It was found that fairly large changes in the settings of the variable capacitors did not alter the gain significantly. It is best, therefore, to tune for maximum front-to-back ratio, on which the settings had considerably more effect. On-the-air signals arriving from the rear direction can be nulled by tuning the capacitors. The nulls should be fairly pronounced if the


ELEMENT NO. 2
ELEMENT NO. 1
450-OHM OPEN-WIRE LINES, BOTH CUT TO SAME LENGTH
K1
K2
C1
MATCHING NETWORK
COAXIAL FEED LINE (RG-8/U, RG-11/U, ETC.) TO STATION

Fig. 26 — Configuration of modified 2-element switchable 40-meter quad. The lines from each element are both cut to the same length, which can be the same as the parasitic element line in Fig. 24 or other suitable length. Both elements are cut to the same dimensions as in Fig. 24. The positions of K1 and K2 determine whether an element is fed as a driven element or terminated as a reflector. The array pattern can be switched by determining which element operates as a reflector or driven element. Only one tuning capacitor is required, but a matching network is needed to match a coaxial feed line.

- C1 — 10- to 250-pF air-variable capacitor, adjusted for reflector operation.
- K1, K2 — Dpdt relays operated simultaneously, or both may be replaced by a single four-pole, double-throw relay (Potter and Brumfield KA11DG or equivalent).

system is set up as described here. The exact amount of attenuation of signals off the back of the antenna varies from signal to signal. It was observed that the 40-meter antenna exhibited the greatest front-to-back ratio for signals arriving from distant locations (at low radiation angles). Alternatively, field-strength measurements can be made to determine the proper settings for minimum radiation or reception off the rear of the antenna. In this fashion, one capacitor is adjusted for director operation and the other for reflector operation.

When making large excursions in operating frequency on 40 meters, it is necessary to touch up the tuning. A director tuned for operation in the low end of the cw segment is self-resonant approximately in the middle of the phone portion and provides little usable gain at those higher frequencies. Retuning is done easily, however — something which is not possible using fixed-tuned elements.

A Modified 40-Meter System

The 40-meter system described above provided very good results over a period of months, including stateside and DX contest work and casual DXing. After some thought, however, a modified system was constructed. The new configuration provided some advantages over the orginal scheme.

The same principle of operation was retained. The new system shown in Fig. 26, used only a reflector-type parasitic element, but the switching system now allowed either element to operate as the driven element or reflector. In this manner, the antenna pattern could still be reversed by choosing the appropriate element for the desired function.

Several factors prompted the change. It was found with the original system that a considerably higher front-to-back ratio could be had using a reflector rather than a director. The latter yielded no more than about 10-dB discrimination against signals received off the back of the antenna, even with careful tuning, whereas with the former the figure was approximately as high as 25 dB. Although most available literature made little mention of quad performance using a director, this observation agreed with what little published data could be found on the subject.[1] The reflector-only model also had the advantage that just one tuning adjustment was required, since one stub reflector served both elements in an identical fashion. Furthermore, because the system behaved the same no matter which direction the array was switched, the SWR did not change when switching, and the transmitter was thus always tuned properly. With the original scheme the antenna feed-point impedance changed when switched between director and reflector operation. Although the resultant SWR was not objectionable in either case (it did change, though), it was necessary to retune the transmitter after switching, or tolerate a moderate amount of mistuning.

The design procedure for the new arrangement is basically the same as before. Both elements are cut to the same length. Only the stub requirements for a reflector need be considered now in doing the Smith Chart calculations. Once the stub line length is determined, two such identical-length lines, both made from the same type of transmission line, are cut, one for each element. A four-pole, double-throw relay, or two dpdt relays operated simultaneously, are required in the hookup shown in Fig. 26, to switch the two lines between the parasitic-element termination and the main feed-line matching network.

The new system has one disadvantage, however. A matching network is required between the transmitter and driven element because of the mismatch between the main feedline, which is presumably coax, and the driven-element open-wire feed line. The original system required no special matching. This presented no problem in the 40-meter system considered here since a suitable network was easily constructed. The builder is left to choose a suitable matching network of his own as there are numerous possibilities to take care of the varied matching requirements which may arise under different situations. Depending upon one's preferences and requirements, the modified scheme may or may not prove more attractive.

Additional Remarks

A few general comments can be made at this point. Although a variable capacitor has been designated thus far as the termination for the stub, there is no reason for not using a coil or some other combination of inductance and capacitance if it will work with a stub length which happens to be convenient. The builder can choose for himself. The 10- to 350-pF capacitor described earlier had approximately 0.05-inch (1.27 mm) spacing between plates. While it is difficult to predict the voltages present in the parasitic element (and across the capacitor), no arcing between plates was observed during transmitting periods, even while running one kilowatt transmitter dc input. This suggested the plate spacing was adequate.

The lines from each element should be brought away perpendicular to the elements as much as possible, and open-wire line should be kept reasonably clear of nearby objects, especially metal ones. Also, the velocity factor of the line being used (0.95 for "ladder" line) must be remembered when computing physical lengths.

The authors erected a single diamond-shaped 80-meter quad loop with its bottom close to the ground. The antenna was tried as both a vertically and horizontally polarized radiator. For DX work, the vertically polarized version yielded unquestionably superior results in terms of greater signal strengths at long distances and the beneficial feature of rejection of unwanted high-angle radiation from stateside stations when receiving. A parasitic element to accompany the single loop was not tried. These observations suggest interesting possibilities for vertically polarized ground-mounted quads for low frequencies.

The ideas presented here are applicable to any quad antenna, but should be especially useful in designing large arrays which cannot be turned physically. The design procedure is simple in any case. The feature of continuously variable tuning eliminates the guesswork in cutting fixed-length, fixed-tuned elements. The system will serve well in any situation where, say, climbing the tower to work on the antenna is not convenient.

A fixed, switchable array is an asset to the contestant or DXer who finds it necessary to change antenna headings in a hurry. From the northeastern U.S., a single such array provides good coverage of Europe and Africa in one direction and of the western U.S. and the Pacific in the other. If two suitable supports spaced a reasonable distance apart are available, two arrays of this type, perpendicular to each other, can provide a wide range of coverage. This material was originally presented in *QST* by John E. Kaufmann, WA1CQW and Gary E. Kopec, K8RX.

---

[1] "Technical Topics," *Radio Communication*, February 1973, p. 101.

Some Notes on a 7-MHz, Linear-Loaded Quad

If you like to experiment with antennas, here are enough new ideas about the construction of quad antennas to keep you going.

Most amateurs who have a serious interest in working DX in the 3.5- to 28-MHz bands would like to have antennas providing them with forward gain on all of these bands. Today, a triband trap Yagi or cubical quad may be employed to achieve this objective on 14, 21 and 28 MHz. Rotary beams are, for all practical purposes, out of the question for 3.5 MHz, but it is possible to achieve some gain with a 7-MHz rotary beam without having to pay a fortune for a supporting structure.

The Hy-Gain linear-loaded 2-element Yagi or the Mosley inductively loaded beam for 7 MHz can achieve this objective. The writer, however, prefers quads to Yagis, based on his own experience. Difficulties often arise when one seeks to mount beams for several different bands on the same tower without marked loss of performance on any band. The primary problem is, of course, that a full-sized cubical quad for 7 MHz is a monstrous structure. Such antennas have been erected, but they are not suited for the average amateur with a limited budget.

The first step in building a 7-MHz quad is, therefore, to design a single 7-MHz quad loop of reasonable size which is mechanically strong enough to survive most weather conditions.

Linear Loading

As a general rule, a reduction in antenna size to two-thirds of full size can be effected without a noticeable drop in performance, providing care is taken to limit the losses introduced by the loading devices. This means that one can think in terms of a loop for 7 MHz with 24 feet (7.32 m) on a side instead of 36 feet (10.97 m) on a side. An additional factor in choosing a 24-foot-per-side length was that the longest bamboo spreaders that the writer could obtain were 18 feet (5.5 m). Attempts were made to lengthen these spreaders, but results were not satisfactory mechanically.

If a 24-foot loop is to be used, the next questions are where to put the loading and what form of loading to use. A full-sized quad loop has symmetrical current distribution. The current maxima occur in the middle of the horizontal sections, and the current minima develop in the middle of the vertical sections. The current distribution in the vertical elements is such that most vertical radiation is canceled out. It is desirable to retain this current distribution in the shortened loop. It is also desirable not to put the loading in the center of the horizontal elements, since maximum radiation occurs at the current maxima, and it does not make sense to cut out the portion of an antenna that does the most effective work. The writer, therefore, chose to put the loading in the vertical sides.



Fig. 27 — A method for linear-loading of one side of a quad element.



Fig. 28 — Dimensions used for the 7-MHz quad elements when the loop has been cut for resonance at the low end of the band. Depending on the height above ground and the particular portion of the band to be operated, the amount of center loading at the vertical sides may have to be varied slightly.

There are two popular methods of loading, stubs or coils. The writer dislikes coils for loading since, if they are wound with a heavy-gauge wire (desirable in order to avoid undue losses), they are bulky and difficult to weatherproof. The choice was therefore stub loading. It would have been possible to insert a stub at each corner of the loop, tied back to the spreaders. But, the current flowing in such stubs would be unbalanced, and radiation in unwanted directions would take place from the stubs themselves. There is also the consideration that if the same spreaders are used for 14-, 21- and 28-MHz loops, stubs at the corners of the 7-MHz loop would have to be mounted well clear of the loops for the other bands.



Fig. 29 — Diagram of the matching section used on the 40-meter driven element. The gamma capacitor employs a 100-pF air variable and a 100-pF high-voltage silver mica connected in parallel.

The original linear-loaded 7-MHz quad element was tried by the writer in a four-band quad some years ago. A single stub in the center of each vertical side was used. The loading stubs were made 14 feet (4.27 m) long and were tied on to a point near the center of the boom. Performance of this quad on 7 MHz was excellent, but the 21-MHz quad mounted on the same boom was almost useless, probably due to pickup at 21 MHz by the 7-MHz loop with subsequent reradiation. An attempt was made to find an efficient method of loading which did not involve long stubs "floating around." The next step was to try folding the wires in the vertical sections back on themselves as shown in Fig. 27A. Current distribution either side of the center part of the vertical elements is symmetrical, as desired. This change resulted in a loop that was resonant near 7 MHz, although its resonant frequency was slightly high. Shortening of the stubs slightly, as shown in Fig. 27B, was tried. This had virtually no effect on resonant frequency. This is no doubt because the increased end-loading effect of the portion A almost equalled the reduction in stub length. Short stubs (abour 4 feet [1.22 m] long) were then



G3FPQ's compact 4-band quad has 2 elements for 7 MHz, 3 elements for 14 MHz, and 4 elements for 21 and 28 MHz. Pairs of Yagi-type directors are used in place of the usual loop director for the three higher frequency bands.

inserted at the center of the vertical sides, at right angles to the vertical sides as shown in Fig. 28, and resonance at 7 MHz was achieved.

A four-band quad for 7, 14, 21 and 28 MHz was then constructed. Much to the writer's delight, there appeared to be no noticeable interference with the pattern of the 21-MHz quad by the 7-MHZ elements. The loading effect of the stubs would be different at 21 MHz since they would include current maxima; the result is to give a loop which, while resonant at 7 MHz, does not appear to have a third-harmonic resonance in or near the 21-MHz band.

Yagi-Type Directors

The reader can probably see from the photograph that the directors for 14, 21 and 28 MHz consist of pairs of stacked Yagi-type elements level with the driven elements. There are two pairs of Yagi directors for the 10- and 15-meter elements at approximately 6-foot, 6-inch (2 m) spacing, and one pair of Yagi directors for 20 meters at approximately 13-foot (4 m) spacing. The overall length of the directors is 31 feet, 3 inches (9.52 m) on 20 meters; 20 feet, 10 inches (6.35 m) on 15 meters; and 15 feet, 2-1/2 inches (4.63 m) on 10 meters. Performance of the author's array on 10, 15, and 20 meters at the moment is little, if any, better than an ordinary 2-element quad. The writer has only recently had an opportunity to start checking out the directors to see what adjustment they need. Current indications are that they require lengthening, but there is a good deal more experimental work to be done. Anyone who wants to try this system must be prepared to do a good deal of cut and try to tune the directors, if any real increase in performance over a standard two-element quad is to be achieved.

One also has to bear in mind that when dealing with multiband quads the resonant frequency of Yagi-type directors is likely to be affected to a far greater extent by the proximity of other elements than would be the case for a quad-loop director. This is because a Yagi director is a comparatively high-Q element. From the theoretical point of view, the drawback to quad-loop directors is that the reactances involved are such that there is a comparatively low degree of mutual coupling between the quad-driven element and the quad-loop director. This, of course, reduces the efficiency of the loop as a director. This problem should not apply to the same extent with Yagi-type directors, and, in theory at least, they should prove to be more efficient than quad-loop directors. The question now is whether practice follows theory or not. This writer won't have an opportunity to conduct any detailed experiments until the summer. When deciding the original length for the Yagi directors, allowance was made for a rise in frequency of approximately 100 kHz. But, the only way to cope with the effects on the director resonant frequency of the proximity of other elements is by field-strength measurements, coupled with a good deal of cut and try. As in any multiband quad, separate feed lines should be used for each band to minimize interaction between bands.

The author's quad has been up for six months now, and final tuning remains to be done to the 7-MHz reflector loop to achieve maximum front-to-back ratio. But the results, even on a cut-and-try basis, are well worth the work that went into the array. This material was originally presented in *QST* by David. L. Courtier-Dutton, G3FPQ.

Spider Quad Mount: Simplified

There seems to be a growing interest in the spider quad. The photograph shows a version of a hub or "spider" mount. Using a 2-foot (0.61-m) length of 2-inch (51-mm) diameter steel pipe, a mount can be constructed easily. Two cuts, 10 inches (254 mm) long, are made through the diameter at each end of the pipe. This leaves 4 inches (102 mm) in the middle for the boom. The cut ends are then bent to an angle to suit the desired spacing. The unit shown in the photograph is bent to 108 degrees. The spreaders may be attached to the boom mount with hose clamps, bolts or wire.

The beauty of this design is that it can be made to any size desired. Also, it can be enlarged to a 4-element version, as shown in Fig. 30.

Fig. 30





One of these spider mounts is in use at KP4DJI (constructed by KP4DIO and KP4DJI) using bamboo spreaders. The results have been excellent. This material originally presented in *QST* by Lynda B. Crowley, KP4DIP.

Two-Band Quad Matching

While experimenting with a 2-element, 2-band cubical quad antenna the problem of matching the antenna to a 50-ohm transmission line arose. The antenna is a "plain vanilla" quad built around information in W6SAI's book, *Quad Antennas*. The author's method of feeding the antenna *did not* produce fantastic front-to-back ratio or forward gain. It merely made the standing-wave ratio more acceptable to the 32S-3B used at the home QTH.

After building the 2-band quad, the author checked it with a General Radio 1606 impedance bridge and found the 10-meter antenna to be about 118 ohms and the 15-meter antenna to be about 91 ohms at resonance. This is 2.36:1 and 1.82:1, or approximately 2:1 for a 50-ohm transmission line. The feed system described here made the VSWR much nearer the desired 1:1.

The heart of the system is a ferrite-core autotransformer. The measured impedance ratio is very close to 50:107 ohms. The insertion loss is less than 0.2 dB from 15 to 30 MHz when terminated in 107 ohms. When it is terminated in 50 or 200 ohms the insertion loss is less than 0.35 dB from 15 to 30 MHz. Several transformers were built before these figures were obtained, and after a suitable design was achieved it was connected to the quad as shown in Fig. 31. You do not have to sacrifice F/B ratio for a more acceptable VSWR by detuning the reflector stubs; simply adjust the tuning stubs for maximum F/B ratio and then design the transformer for the proper impedance ratio. Also, lowering the VSWR places a larger portion of the desired band within an impedance range the average pi-section tuner will accept.

In answer to on-the-air inquiries: Yes, performance of the antenna varies considerably from one end of the band to the other.


10 AND 15 METER CUBICAL QUADS
RG/58 ANY LENGTH
SOLDER OUTER SHIELDS TOGETHER AT BOTH ENDS OF THE LINE. THESE LINES ARE 9' (2.74m) LONG ON THE EXPERIMENTAL ANTENNA.
RG/213 OR EQUIV. TO TRANS.
1 TURN
3 TURNS
WIRE USED WAS 18 AWG TEFLON INSULATED MULTISTRAND
5/8" (16mm)
1/2" (13mm)
2-1/2" (64mm)
FERRITE CORE INDIANA GENERAL Q2 MATERIAL
100Ω
50Ω
EQUIVALENT CIRCUIT OF FERRITE TRANSFORMER

Fig. 31 — Two-band quad matching.



Fig. 32 — Standing-wave ratio curves taken with a laboratory-type VSWR bridge. Measurements were made at the transmitter ends of the transmission line with the antenna array mounted on a steel tower 44 feet (13.4 m) above ground.

This antenna feed system is a broadband device, so don't forget to use a low-pass filter. This material was originally presented in *QST* by Toney L. Magnino, W5MVK.

Chapter 4

Miscellaneous Antenna Types

Here is a potpourri of useful antennas for the hf-band enthusiast. This chapter contains information on how to build and operate loop antennas, limited-space antennas and variations of the quad. Once again, the work of numerous *QST* authors has been collected for a timeless volume of useful construction details that can benefit amateurs whose operating objectives are numerous and varied.

For the most part, the antennas described in this section are simple and inexpensive to build. The performance characteristics are consistent with the operating needs of ragchewers, contesters and DX-chasers alike, assuming that the builder does not strive to have the loudest signal on the amateur bands.

Beat the Noise with a "Scoop Loop"

Operators on 160 and 80 meters fight a common foe — noise. Atmospheric QRN is compounded by the presence of man-made noise. Loop antennas for receiving may offer an economical solution to your noise problems. Here are some timely details.

If you've been tempted to massage your receiver with a 10-pound hammer because you can't copy some of the weak signals being heard by your colleagues, you may need a receiving loop! A high ambient noise level on 160 meters has stifled the author's DX work for several years, and more than once was ready to capitulate in favor of the man-made and atmospheric noises that the 75-foot (22.9-m) shunt-fed vertical responded to. "Grrrr," would be the snarl as the author listened to stations with Beverage antennas: They were handing out RST 579 signal reports to DX stations, and the author couldn't find the DX signals in the noise, let alone copy them.

Something had to be done. It was a matter of giving up on 1.8-MHz efforts toward DXCC, or putting forth a zealous attempt toward an improved signal-to-noise ratio. Some effective outdoor receiving antennas were erected (half-wavelength open loop — parallel to the ground, and a 200-foot [61-m] end-fed wire a few feet off the ground), but they did not always respond well to DX signals: It depended on band conditions. Also, there was the danger of receiver front-end damage caused by unwanted excitation of the large receiving antennas (resonant) during the transmit period. They were in close proximity to the vertical antenna, which was used for transmitting purposes. Lethargy prevented the author from installing a protective circuit at the receiver front end, and as a consequence the writer "blew" a JFET preamp and two protective diodes in the front end of the FT-301D transceiver.

Revisiting the Past

While for many years experimenting with small receiving loops for 40, 80 and 160 meters, the efforts were casual. The best of the loops was an outdoor one of the shielded variety, five feet (1.52 m) on a side, and fashioned from RG-59/U coaxial cable.[1] However, it was necessary to go out-of-doors each time to rotate it, and the author wasn't enthusiastic about investing in a rotator to use with the loop.

Recently, it seemed that some work could be done with indoor types of receiving loops. After all, loops of that kind have been around since radio was invented, and plenty of amateurs are using them effectively. After scanning available literature (Terman, Kraus, Jasik and Keen),[2] the author set about the task of building a framework for the chosen design. This time a multiturn loop would be tested (Fig. 1).

Construction

The photograph shows the general structure of the loop. In Fig. 2 are the dimensions of the wooden frame used to contain the antenna wires. There is nothing magic about the size of the antenna: Two pieces of wood that were stored in the workshop were used, each being 48 inches long, 1-1/2 inches wide and 3/8 inch thick (1.22 m × 38 mm × 10 mm).

Arbitrarily, the author decided to make L1 of Fig. 1 a five-turn winding. Holes were drilled (five) in each end of the cross-frame to accommodate the loop turns and hold them in place. Actually, there should be six holes at the bottom point of the frame to permit the final end of L1 to be secured during the threading-through process.

Five additional holes were drilled (Fig. 2) 3/4 inch (19 mm) below the holes for L1. These are used to contain L2, the one-turn output link of the antenna. L2 requires two holes at the bottom member of the frame — again to provide an anchor point for the ends of L2. Alternatively, V-shaped notches can be filed on the ends of the cross-frame. The wire for L1 can be laid in the grooves rather than threaded through the holes shown in Fig. 2. L2 should, however, be wound inside L1, through the five holes shown in the drawing.

A mounting base for the assembled antenna can be made to the builder's specifications. This writer used a piece of 3/4-inch (19 mm) plywood which has dimensions of 30 × 12 inches (0.76 m × 305 mm). A 1-inch (25 mm) diameter hole was drilled in the center of the board to accept an 18-inch (457 mm) length of 1-inch diameter dowel rod. The latter is lashed to the framework of the loop to enable the



The silhouette is of an indoor version of the four-turn shielded loop described in this article. A wooden framework is used to support the main loop winding and the one-turn pickup link. The resonating capacitor is mounted on an aluminum L bracket along with a phono jack and an 860-pF disk capacitor. The latter is used between the output link and the phono jack instead of a trimmer capacitor. The framework was built by Technical Secretary Marian Anderson's OM, Bob. It has been stained and coated with clear lacquer.

operator to rotate the loop as desired. Although this is a "kluge" type of assembly, it serves its purpose adequately. A *carpenter* should be able to conceive a more practical base and support system for the antenna!

Number 22 insulated hookup wire was used for the loop turns. There is nothing critical about the wire size, but it is best to use the larger gauges. This will make the loop more rugged.

Performance

A variety of feed systems were tried before the author settled for the method illustrated in Fig. 1. Direct connection to the terminals of L1 required careful balancing to assure a uniform loop-response pattern. Unbalance causes pattern distortion, and if it's bad enough the maximum response can occur off the broad side of the loop rather than in the plane of the antenna.

Addition of a one-turn coupling loop, L2, proved to be the easiest method for assuring good balance. Bandwidth of the loop is dependent upon the Q. The latter can be controlled by the amount of capacitance used at C2: the lighter the coupling, the greater the loaded Q. Loop resonance is effected by means of C1. Since there is interaction between L1 and L2, it is necessary to readjust C1 each time C2 is tweaked. In this application it should be stressed that C2 is not used for the purpose of obtaining an SWR of 1. It is purely a *coupling* device. Hence, a 50-ohm condition does not necessarily exist at the loop output terminals.



Fig. 1 — Schematic diagram of the receiving loop. C1 and C2 are mica compression trimmers. The illustration at A shows the 1-turn link inside the 5-turn one. At B is an expanded diagram of the feed point for L2.



Fig. 2 — Dimensional drawing of the wooden frame which contains the Scoop Loop. Further information concerning the structure is given in the text.

During initial experiments the pickup loop, L2, was connected directly to the 50-ohm input port of a 40-dB broadband preamplifier which was designed by W7ZOI (Fig. 3). Without C2 in the circuit the coupling was excessive. This resulted in low Q, and the loop bandwidth was approximately 150 kHz at the 3-dB points of the response curve. After C2 was added and adjusted to provide a bandwidth of 25 kHz, the loop gain increased 10 dB. Alternatively, one might make L2 smaller and locate it closer to the center of the loop frame in order to lighten the coupling between the two windings. This could be a somewhat tedious mechanical procedure: The writer's inherent lassitude favored the addition of C2 for the purpose!

Performance Characteristics

A test range was set up for checking the null properties and relative gain of the loop. The equipment was arranged in an outdoor location, well away from power wiring and other station antennas. A crystal-controlled weak-signal source (2N2222A oscillator and 9-volt battery) was placed some 100 feet (30.48 m) from the test loop. It contained a 36-inch (0.91-m) whip antenna (vertically mounted) for radiation of the test signal. The 75-foot (22.86-m) transmitting vertical was shorted out at the feed point to prevent it from being resonant and affecting the loop antenna during the test period.

A 50-ohm Tektronix step attenuator was placed in the coaxial line between the loop and the receiver. The attenuator was used to measure accurately the changes in S-meter reading on the FT-301D transceiver which was used as a detector during the measurements.

A null depth of —21 dB was obtained with the loop. An extremely sharp null was noted. As the broad side of the loop was moved toward the signal source, the null began slowly, then fell deeply to —21 dB over the final 10 degrees of rotation. No evidence of pattern distortion was observed. The null was dead off the broad side of the antenna, and maximum response was directly off the thin side of the loop.

A comparison between the 75-foot (22.86-m) transmitting vertical (shunt-fed tower, top loaded and with buried radials) and the wire loop indicated that on groundwave signals the loop (without preamp in line) was —18 dB respective to the vertical. This suggested that in a practical installation a single JFET or dual-gate MOSFET preamp would provide unity gain with the transmitting vertical.

Using the Loop Indoors

The author's home has aluminum siding, and as is the case with all modern homes there is a network of water pipes, phone wires, TV lead-in conductors and house wiring. The author wondered how well the loop would perform within all of these unwanted signal obstacles, some of which form loops by themselves! The ham shack is at ground level inside the family room, and the loop was placed on a stand at floor level. The clutter of unwanted conductors disturbed the directivity of the loop somewhat, but the signal-pickup ability of the antenna was not impaired.


+12.5 V
70 mA
47
0.1
RFC 15μH
3300
240
1000
10
150
120
91
39
SIG. IN (50 OHMS)
OUTPUT (50 OHMS)
Q1 2N5179
Q2 2N5179
Q3 2N5179
Q4 2N5179
(A)
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF) ; OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS ; k = 1 000, M = 1000 000.
-1 dB
5.8
870
(B)
1.8 - 1.9 MHz
50 OHMS
68
220
50 S.M.
1000 S.M.
C1 200
C2 200
L1
L2
BWL = 100 kHz IL = 0.5 dB f₀ = 1.85 MHz
S.M. = SILVER MICA
(C)

Fig. 3 — The W7ZOI broadband 40-dB preamplifier is shown at A. Capacitors are disk ceramic or chip types. Resistors are 1/4-w composition. The upper 3-dB point of the amplifier is at 65 MHz. Heavy feedback is used to stabilize gain and provide a 50-ohm characteristic. At B is a 1-dB attenuator pad which can be used between an antenna of unknown impedance and the filter at C to provide a proper load for the filter. The Butterworth band-pass filter at C is suitable for use with the preamp at A. It will help reject out-of-band signals to improve the IMD characteristics of the preamp. When the preamp is used with nonresonant receiving antennas, it will be necessary to employ the filter to protect the preamp from signals across its response range (bc band through vhf). The preamp and filter would be fine for use with Beverage antennas. C1 and C2 are mica trimmers. L1 and L2 consist of 31 turns of no. 22 enameled wire on Amidon T68-6 toroid cores (5.1 μH).


1.8 - 2.0 MHz
L2
C2
1000
TO PREAMP. AND RECEIVER
L1
C1A
C1B
100
(A)
ELECTROSTATIC SHIELD
OPEN
C1
200
(B)
TO C2 OF B
0.1
(+6 dB) MPF102
S
D
G
10
56
RFC 1mH
TO W7ZOI PREAMP.
100
+12V
COMMON-GATE PREAMP.
(C)

Fig. 4 — The drawing at A shows the circuit of a 7 X 5/8-inch (178 X 16-mm) ferrite-rod loop (see text). At B is the final version which employs an electrostatic shield. C1 and C2 are mica compression trimmers (see text for other details). The circuit at C was used ahead of the W7ZOI preamplifier to improve the system noise figure.

A step attenuator was inserted between the W7ZOI preamplifier and the station receiver so that unity gain could be established between the loop and the 160-meter vertical (22 dB of gain had to be gotten rid of). An antenna switch was added to the system to permit rapid comparisons between the antennas.

Extensive tests proved that the loop outperforms the vertical by a substantial margin when it comes to digging weak signals out of the noise (man-made and atmospheric). The author has copied PA0HIP, PY0ZAE, G3MYI, W6RW, W6BLZ, W5AB and others perfectly Q5 on the loop (indoors) when they couldn't be found, or were unreadable on the vertical. It is only fair to say that on some occasions the vertical was the better antenna for receiving. Propagation conditions and ambient noise levels at a given time will determine which antenna can provide the best reception. Typically, the ambient noise level from the W1FB vertical is S3 on a receiver that is calibrated to indicate S9 on a 50-μV signal.[3] The same receiver shows no noise response when the loop is connected to it. However, static crashes (atmospheric noise peaks) are as loud with the loop as they are with the vertical when a storm is in the immediate area. Noise from distant storms can be discriminated against by turning the loop null toward the storm front. It appears that the major part of the author's ambient noise is man-made in nature. At times it peaks as high as S8.

When the loop is used indoors it responsds to unwanted 15.750-kHz TV spurs, and when appliances are actuated the transients kick the receiver S meter rather hard. This is because the loop is contained within loops formed by house wiring. This type of interference has not been observed while using the vertical antenna, even though it is affixed to the rear of my house. To prove that the house wiring was causing the problem with TV birdies and transients, the loop was located out-of-doors for two nights. The interference vanished!

Some Other Loop Experiments

Ferrite-rod loops have been used to advantage for many years (bc-band radios, direction-finder receivers for boats and aircraft, etc.), so it seemed worthwhile to investigate a model of that type of antenna before concluding the tests. Two versions were tried, each with a preamplifier.[4] The first consisted of a single 7 × 5/8-inch (178 × 16 mm) Amidon Assoc. ferrite rod on which was wound a 40-turn solenoidal coil of no. 22 insulated hookup wire. The loop was tuned to resonance by means of a 100-pF per section split-stator variable. A four-turn output link was wound over the center



View of the ferrite-rod loop and test setup accessories. In the foreground (left) is the Butterworth band-pass filter. Below it at the center is the broadband preamplifier, and the Tektronix 2701 step attenuator is at the far right.

of the primary winding. The latter occupied approximately 3 inches (76 mm) of the center portion of the rod. A small aluminum chassis served as the foundation for the antenna, and the rod was spaced some 3 inches (76 mm) above the chassis. Performance tests showed the antenna to be less efficient than the large 5-turn wire loop. As referenced to the 75-foot (22.86-m) vertical, the ferrite loop was —38 dB. Furthermore, it was prone to the same induction effects which plagued the wire loop when both were used indoors. The rod-loop null was dismal — some 10 dB!

An improved model of the loop was built by using epoxy cement to join together a pair of 7-inch (178-mm) ferrite rods, end to end. The sensitivity (μV per meter) increases with the length of the rod, but is dependent upon the length of the coil which is wound on the rod. A multilayer coil contained at the center of the rod should be considerably better than a solenoidal coil spread over the major portion of the rod: The shorter the coil, the higher the Q of the antenna.

The author did not have Litz wire available, and was unable to build a multilayer coil, so a short solenoidal winding was placed on the center 5 inches (127 mm) of the 14 × 5/8-inch (356 × 16 mm) rod. It consisted of 32 turns of no. 12 insulated wire, spaced one wire diameter between each turn. The ferrite rods are made of Q2 material (μ = 125).

Fig. 4 shows the schematic diagram of the rod loop. A four-turn output link is wound over the center of L1. C1 is a mica compression trimmer which tunes the loop to resonance. C2 is used as a coupling capacitor to control the loop loading.

It seemed worthwhile to try shielding the loop, so a pair of aluminum L brackets were bolted to the chassis as shown in the photograph. Each bracket is 16 × 3-3/4 inches (406 × 95mm). The shields are spaced 1 inch (25 mm) either side of the loop.

The top of the U-shaped channel must be left open to prevent the shield from acting as a shorted turn. Proof of the effect can be seen by shorting across the open end of the trough (over the center of the rod) with a screwdriver. The received signal will vanish! An electrostatic shield, when used with a loop antenna, should minimize induced fields from nearby conductors and precipitation static, thereby making the system better for indoor use.

Rod-Loop Tests

The same outdoor test setup was employed for checking the performance of the rod loop. The nulls occur off the ends of the rod, and maximum response is found off the broad sides of the rod. A null of —23 dB was obtained with the loop, but efficiency was less than that obtained with the 5-turn wire loop. When compared to the 75-foot (22.86-m) vertical a reading of —31 dB was obtained, 13 dB inferior to the wire loop. The noise figure of the W7ZOI broadband preamplifier was too high for use with the new antenna, so a common-gate JFET pre-preamplifier was added between the loop output and the input to the 'ZOI unit. Ideally, a 30- or 35-dB preamplifier (two JFETs) should be used with the rod loop to assure a low noise figure and ample gain.

With the coupling set for maximum loop gain, the bandwidth (measured with an HP spectrum analyzer) is 10 kHz at the 3-dB points. The loop was measured independent of the shields and preamp for unloaded


1.8-2.0 MHz
C1
200
ROD LOOP OF FIG. 4B
1.8-2.0 MHz
C2
1000
20 (508mm) SENSE ANTENNA
R1
10k
PHASING
C3
200
AMPLIFIER
MPF102
C4
200
1.8-2.0 MHz
50
10k
220
0.1
100
0.1
+12V
50-OHM OUTPUT
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF OR $\mu\mu$F); RESISTANCES ARE IN OHMS; k=1000, M=1 000 000

Fig. 5 — Suggested circuit for using a sense antenna with the rod loop. The sense antenna can be mounted 6 to 10 inches (152 to 254 mm) in front of the broadside of the rod loop (centered). C1, C2, C3 and R1 are adjusted alternately for the deepest null possible off the rejection side of the loop (side opposite the sense antenna). It may be necessary to experiment with the length of the sense antenna to obtain the best null in the cardioid response pattern. The tuned circuits for the JFET preamp can be wound on T-68-2 toroid cores.

Q by means of an HP Q meter. A reading of 430 was obtained.

The electrostatic shield cured the unwanted pickup of TV spurs and appliance transients during indoor use. The author would like to mention that the wire and rod loops are affected to some extent by the presence of the 75-foot (22.86-m) vertical. The latter is only 20 feet (6.10 m) away from the operating position. It tends to reradiate noise and signals. Some of that energy is picked up by the loop antennas. If an indoor loop is to be used regularly, or if it is outdoors, but within 100 feet (30.48 m) or so of the vertical, the latter should be shorted out or detuned during the receive period. An spst relay could be slaved to the regular antenna change-over relay to accomplish this.



The 4-turn coax loop with electrostatic shielding. The trimmers are visible on aluminum brackets below the loop.

An improvement in performance for either type of loop could be had by adding a sense antenna and appropriate phasing circuit (Fig. 5). This would provide a cardioid pattern and result in a unidirectional response. Greater reduction of QRN and QRM would be effected through that technique. A weatherproof system of that type could be placed out-of-doors for year-round use. A TV type of rotator would be useful for changing the loop position, as desired.

The W1FB 4T-ES Loop

During a final investigation of loop types and performance characteristics, an attempt was made to devise a shielded loop small enough to be practical indoors. The primary objective was to develop a loop from ordinary materials — something that was inexpensive and easy to build. It should have efficiency comparable to that of the 5-turn wire loop described earlier in this report. A reasonable null depth and an undistorted pattern were sought also. From these criteria evolved the 4T-ES (four turn, electrostatic shield) loop shown in Fig. 6.



Fig. 6 — Structural details of the W1FB 4T-ES loop antenna. At A is an illustration of the total length of RG-58/U before the loop is formed. An expanded view of the loop turns and pickup link is given at B. Drawing C shows how the loop turns are taped together side by side as the antenna takes its final form.

It consists of four turns of RG-58/U cable which are formed into a circular configuration to provide a diameter of 13-1/2 inches (343 mm). There is nothing critical about the diameter, and RG-59/U coaxial cable could be used instead of the type specified. The turns are formed side by side, then taped at several points to maintain the loop form.

It is necessary to split the shield braid at the electrical midpoint of the loop. This prevents the shield from acting as a shorted turn. The principle is the same as that described for the ferrite-rod loop with its aluminum-channel shield. The braids are joined at the loop feed point and made common to one end of L2. The three grounded elements are then attached to the coaxial connector ground terminal on the loop support frame.

Loop performance was checked by using the test procedure discussed earlier. A null depth of —26 dB resulted. There was no discernible pattern warping, and the null occurred deeply over just a few degrees of rotation. The 4T-ES was 18 dB inferior to the 75-foot (22.86-m) vertical antenna when checking distant signals. The unloaded Q was measured by means of the HP Q meter. A value of 85 was obtained. Because C2 was set for light loading of the loop, a bandwidth (3-dB points) of 20 kHz was obtained when the preamplifier and receiver were connected to the antenna.

Numerous comparisons were made on DX signals from Europe and the Caribbean area during the ARRL DX Contest in March of 1977. In all instances the 4T-ES was as good as or better than the 75-foot (22.86-m) vertical. Ambient noise was considerably lower in amplitude while using the loop, even though all tests were performed with the loop indoors at ground level. There was no reduction in atmospheric noise (which was high that weekend) because the maxima of the loop favored the N.E. and S.W. directions: The storm front was S.W. of Connecticut. However, rotation of the loop caused a drop of 26 dB in the static crashes when the loop nulls were S.W. and N.E. Because of the electrostatic shielding there was minimum noise induction from the house wiring — a contrast to the performance characteristics of the unshielded 5-turn wire loop. The W7ZOI broadband preamplifier and an attenuator were used during the tests. There were some instances when the loop provided a stronger signal response than the vertical, even though the two systems were adjusted for unity gain.



Close-up view of the 160-meter indoor receiving loop at W1FB. The antenna is resting on a piano bench, and is situated near the operating position so that it can be hand-rotated as necessary.

The 4T-ES is suitable for use indoors,

but it could be weatherproofed for outside installations. Epoxy cement could be used to seal the open ends of the coaxial cable of L1, and the trimmer capacitors would survive the natural elements if housed in a metal or plastic container.

In Summary

The loops that have been discussed here should be suitable for use on 40 or 80 meters if scaled accordingly. They may not show much directivity on sky-wave signals because of the "tumbling effect" at the higher frequencies. But QRM from nearby amateurs could be reduced greatly, and man-made noise sources could be rejected significantly by correct orientation of the loop.

The author has attempted to discuss some of the characteristics of small loops which are not treated in most of the references contained in amateur journals. There is plenty of latitude remaining for experimentation, and the reader is encouraged to apply his or her skills in developing better loops for amateur use. Meanwhile, why not build a small loop and scoop those weak signals out of the noise? It could mean some new countries for you on "top band" or 80 meters. This material was originally presented in *QST* by Doug DeMaw, W1FB.

References

[1] DeMaw, "A Receiving Loop for 160 Meters," *QST*, March 1974.

[2] Terman, *Electronic & Radio Engineering*, McGraw-Hill. Kraus, *Antennas*, McGraw-Hill. Jasik, *Antenna Engineering Handbook*, McGraw-Hill. Keen, *Wireless Direction Finding*, 3rd Edition, Iliffe & Sons, Ltd.

[3] DeMaw, "His Eminence — the Receiver," Parts 1 and 2, *QST*, June and July 1976. Receiver used in combination with an Autek Research QF-1 RC active audio filter.

[4] DeMaw, "Build This Quickie Preamp," *QST*, April 1977.

The Half Square Antenna

Do those 100 countries still elude you for 80-meter DXCC? In terms of dollars versus decibels, a half-square antenna may be your best bet for putting punch into your signal.



Fig. 7 — Bobtail array. The dotted lines show the approximate current distribution along the antenna and the arrows indicate the relative directions. With this array, the high-current points occur at the highest points on the antenna.



Fig. 8 — The "half-square" evolved when one leg broke off the bobtail. The input impedance of both the bobtail and half-square antenna is very high, which eliminates the need for an elaborate ground system at the feed point. Either a parallel-tuned circuit or a quarter-wave transformer can be used to match to a 50-ohm feed line.

With 5-band DXCC as bait, considerable interest has arisen in DX and antennas for the lower frequency ham bands. The author's attempts to get a decent 80-meter DX antenna have gone through an evolutionary cycle with a lot of iterative tries and with steadily improving results. The half-square antenna that is the latest of these has some interesting properties and gives about as many "dBs per buck" as any this author has seen.

Before describing this configuration, it might be interesting to cover briefly the different antennas tried which didn't work as well. The writer's available options were set up by (1) a yard full of tall trees and (2) very little money to spend. The first antenna was an inverted V hung on the 75-foot (22.9-m) tower. This is really a quite good antenna — primarily because it has the high current part of the antenna at the highest support point. It provided a standard against which all succeeding antennas were checked. The next step was to add a parasitic element (director) which didn't seem to help at all. This is perhaps not so surprising with the ground so close. Viewed simply, normal parasitic coupling is dependent upon a fair proportion of the current in the driven element being coupled to the parasitic element. When they are both close to the ground, the reverse polarity of the image of the driven element starts to couple heavily to both the driven element and the parasitic element, making it practically impossible to get the desired parasitic current at any useful spacings.

This effect has been shown experimentally to be less with closed-loop type antennas such as the quad. Based on this supposition, the author next constructed a 2-element quad, supported at the corners by ropes tied off to trees. With only 75-foot (22.9-m) trees and the consequent sag, the bottom was only about 6 feet (1.83 m) off the ground. However, the quad did work, had an acceptable feedpoint impedance, and gave a few dB (about 1/2 an S unit) improvement over the inverted V on European contacts. Obviously, the only useful low-angle radiation in this antenna came from the upper half of it, the lower half serving to feed or excite the upper half. A major problem with the quad was keeping it up. It had to be very tightly stretched between trees to keep it from sagging to the ground and as a result the wire often broke.



Fig. 9 — Two-element half square array gives greater gain and a very wide bandwidth.



Fig. 10 — Measured SWR of the antenna shown in Fig. 9.



Fig. 11 — Computer-pattern plot for a 2-element half square array with 0.15-wavelength spacing between elements. The angles referred to in the drawing are shown in the inset.



Fig. 12 — Computer-pattern plot for the antenna of Fig. 11 with 0.25-wavelength spacing.

To try another tack which would avoid the parasitic coupling problem an 8JK array with four half-wave elements was tried, all elements being fed. With the span of this being so long and with lots of high-voltage points which had to be kept from touching the trees, the author only managed to get it to a height of about 40 feet (12.19 m). The signal-report results with this were essentially identical to the quad on the path to Europe. The horizontal beamwidth was noticeably less than the quad. It probably would have done better if the writer could have gotten it to 75 or 80 feet (22.86 or 24.38 m) in height.

The next antenna tried was the so-called bobtail which is shown in Fig. 7. This is a broadside vertical array with approximately twice the current in the center leg as the two outer legs and with current distribution in the horizontal wires which tend to cancel horizontally polarized emission.[1] A major reason for trying this was the author's frustration with trying to use the maximum available height of the trees and still be able to feed the antenna and keep the high-voltage points clear of the tree branches. The author had avoided vertical antennas before because of the difficulty in getting a good low-loss ground. Also, the trees looked like great vertically polarized rf energy eaters. The bobtail is particularly nice for tree hanging since its highest support points (A, B, and C in Fig. 7) are all at low impedance and looked as if they could be directly slung over a tree limb with no insulators. It is fed from the bottom at a high-impedance point so the ground system doesn't need to be as good as it does with low-impedance feedpoints. Also, like the inverted V, the bobtail has its maximum current at the highest support point. It can be excited from a parallel-resonant tank circuit or a quarter-wavelength stub.

The bobtail has been an outstanding performer. It's at least an S unit better than the inverted V and works great on DX paths to the Far East (JA, KG6, and VS6). The author put up two of these at right angles and found their interaction to be practically nil even though their center legs are quite close. When switching, the author ground the feed point of the one not in use.

The Half-Square Antenna

With such fine results, it was thought the ultimate "tree-hung" antenna had been discovered. However, after a particularly bad storm, it was noticed that one leg of the bobtail had broken off and yet the antenna feed impedance hadn't changed noticeably. Furthermore, the results compared with the inverted V seemed about the same as the full bobtail. Fig. 8 shows the configuration. It is a 2-element (instead of 3) vertical broadside array with the same current in both legs. It has all the advantages of the bobtail except that the radiation from the horizontal part of the antenna doesn't cancel as well in all directions and some end-fire, horizontally polarized energy does spill off. This might be considered an advantage or a disadvantage, depending on whether you're seeking coverage or discrimination! In discussing this with Ed Watters, WA3LGX, he pointed out the kinship this antenna has with the bisquare array. It's sort of half of a bisquare laid sideways with the ground image antenna making up the other half. That, plus its obvious shape, led the author to dub it the half-square antenna.



Fig. 13 — A 3-element half-square array.

After using a single half-square for awhile, it was decided to add another element with about 0.15-wavelength spacing. With the new element in place, a check was made to see what parasitic coupling there might be between elements. With several hundred watts fed into the driven element there was no evidence of rf on the parasitic element (using a neon bulb). This was a very gross measurement which tended to confirm what was expected. The very close proximity of the antenna to ground tends to reduce greatly parasitic coupling to a nearby element. Being puzzled why it should appear so small, the only hope was to devise a means of measuring this coupling more accurately.

Having had to tear down the 8JK antenna to get enough wire for this antenna, as a first try for feeding it, the author just used the 8JK open-wire line and stub match as it existed. The one wavelength of wire for each element was taken directly from the 8JK also. Fig. 9 shows the configuration. Unlike the 8JK, which was narrowband (centered around the middle of the band), this configuration gave the very flat SWR shown in Fig. 10 — on the first try! The SWR was not very different whether the feed-line stub was connected to point A, B, or C (Fig. 9). B gives a bidirectional characteristic while connection to A or C gives some unidirectivity. The author is still suspicious of the wide bandwidth and suspects the two elements may be different effective lengths, giving a stagger-tuned effect. If the spacing between these two were increased to a quarter wave and fed at point A or point C, it should theoretically add another couple of dB gain



Fig. 14 — Any of the antennas mentioned can be bent as shown in order to keep the current loops at the upper corners.

and give a more significant front-to-back ratio than with the 0.15-wavelength spacing. WA3LGX plugged the dimensions and shape of this antenna into a generalized computer program he has developed for wire antennas and got the curves shown in Figs. 11 and 12. Fig. 11 defines the forward pattern for 0.15-wavelength spacing assuming a perfectly conducting earth. Fig. 12 is for quarter-wave spacing. The actual patterns will be modified at angles below 10° to 15° by the earth's resistivity[2] as is the case with any vertical antenna. The 0.15-wavelength-spaced antenna was used for some time and consistently gave better results than the bobtail on the path to Europe.

The writer took one other step beyond the 2-element array and added another element at 1/8-wavelength spacing (see Fig. 13). The extra element is fed, as are the other two, with an extension of the same open wire line. This antenna is considerably quieter (less QRN) than any of the other 80-meter antennas the writer had and has better than half an S unit advantage over the bobtail on European signals. It doesn't require any retuning to cover the whole band.

With these antennas not insulated at their support points, one might expect some effects when the tree sap rises or in wet conditions. The author hasn't been able to notice any differences from dry weather to monsoon-type rains or wet snow covering everything. The trees are slightly over 1/4-wavelength high on 80 meters. Considered as antennas or absorbers, they would look like grounded 1/4-wavelength vertical radiators. The vertical sections of the half-square antenna that run close to the trees are just the opposite. That is, at the bottom of the antenna the voltage is high and at the top, the voltage is low. This should minimize coupling to the trees, as opposed to, for example, using 1/4-wavelength grounded verticals for the antenna elements.

160-Meter Operation

Now if you look closely, you can see that the 80-meter half-square whether 1, 2 or 3 elements, should make a good antenna for 160 meters. Each element is 1/2-wavelength long on 160 meters, voltage fed on the end, and the high current part of the antenna is at the maximum height. True, a higher impedance part of the antenna touches the tree, but you can't have everything free! While not having managed to work any DX with the few watts available on 160 meters, the author can *hear* Central European ham stations quite well on this band for the first time ever at this location. Of course, a different stub or tuning arrangement is necessary for getting a low SWR on 160 meters. The writer just unshorted the stub and put a tapped coil (about 14 microhenries) in series with the coax feed line to tune it.

Construction Details

These antennas were all built with no. 14 soft-drawn copper wire. The elements are pulled over the top limbs of trees that have approximately the correct spacing and tied to nylon strings at about shoulder level. If your trees aren't a full quarter wave high, the extra wire can be stretched out parallel to the ground at each end as shown in Fig. 14. Note that you still get the maximum current point at the highest support point you have.

The best technique found for getting a line over the highest tree is to use a fisherman's casting reel (I use a Zebco 202) with an 8-pound nylon line and a 1- or 1-1/2-ounce sinker. The reel is put in the RELEASE position and a sling shot is used to shoot the sinker and line over the desired tree. This is a very accurate technique and you can easily put a line over 90-foot (27.43-m) trees. The light fishing line is used to pull over a heavier line. It's a good idea to paint the sinker a bright color since the line is almost invisible. You can waste a lot of time looking for the sinker at the end of the line.

Be sure to leave enough droop in the horizontal section of the antenna to allow for tree motion in high winds. The open-wire feed line used for the harness and stub sections is made with the same no. 14 wire spaced 3-1/2 inches (89 mm).

The avid Field Day or camping fan will notice the obvious advantages of the half-square antenna for that type of operation. It uses minimum materials, goes up very quickly, will really put out a booming signal on 80 meters, and can be taken down in just a few minutes. You can also make good use of the fishing rod in between your turns at the key. This material was originally presented in *QST* by Ben Vester, K3BC.

References

[1] [Editor's Note: While complete cancellation of the horizontally polarized component occurs at a point broadside to the array, some radiation from the flat-top portion will exist at other angles. This is because of incomplete cancellation of the components from the opposite ends of the flat top.]

[2] *The ARRL Antenna Book*, 12th Edition, p. 46.

The HRH Delta-Loop Beam

Here's an antenna that should excite the interest of the amateur fraternity. The Delta-Loop beam has all the features of a quad without many of the disadvantages.

The evolution and design of the antenna shown in the photographs came about primarily because of a lack of confidence in the mechanical durability of quads. Anyone who has ever built and used quads knows how difficult it is to keep them up in icing and high wind conditions.

The author being an old-time mechanic, felt there had to be a better design for an antenna that used full-wave elements in a parasitic array, so some years ago a start was made to find that better design. One thing that nearly all readers will agree is that Mother Nature is about the best designer there is. Along these lines, just observe the growth of branches on tree limbs. You'll find that many of the smaller branches will grow up in a semivertical pattern from the limb; see Fig. 15. It takes a considerable amount of icing and wind to break such branches, indicating the soundness of the design. This same idea should apply to elements mounted on a boom.

To test the idea, an element of aluminum tubing was mounted on a boom. The element was mounted as shown in Fig. 17. The boom was then secured to the family car with the element in a vertical position. The assembly was then tested at 65- to 75-mph. Even though the element was only secured to the boom as shown in Fig. 17, there was no "set" or permanent bending. This test opened the door to several possibilities in beam design.


Fig. 15 — The basic idea for the Delta-Loop beam was conceived from the growth of tree limbs and branches. Here are just a few of nature's configurations that lend themselves to antenna design!


This is a 10-meter, 2-element Delta Loop that is very similar in construction to the antenna described in the article.

A loop aerial can take many shapes. Anyone who studies the history of the quad will find that many different configurations have been used. Why not use a triangle?[1] It should be possible to achieve a very good design using a vertical triangle. See Fig. 16. This shape appears ideal for a beam with full-wave elements, and has most of the advantages of the quad without many of the disadvantages. This led to the construction of several antennas of the type shown in the photographs, and some of these advantages become quickly apparent.

First, the entire antenna is *above* the boom. Second, the antenna is constructed primarily of aluminum tubing, which provides extra strength as compared with wire elements. Third, the antenna has Plumber's Delight type construction, meaning that the antenna is at ground potential for lightning protection, plus the fact that this type construction lends itself to gamma matching of the feed point, eliminating the need for a balun. Last, but not least, we find the antenna is very attractive in its symmetry. Of course, the important point is how well does the antenna perform?

Several 10-meter models have been tested and the unit shown in the roof-mounted position is 20-meter Delta Loop. Using a gamma match with 50-ohm coaxial feed, a 10-meter model was matched at 28.8 MHz. The antenna consisted of a driven element plus reflector with the elements spaced 6-1/2 feet (2 m) apart, or approximately 0.2 wavelength. Surprisingly, the antenna was extremely flat across the entire 10-meter band, the worst mismatch being *less* than 1.2 to 1.[2]

The author has no means of measuring gain or front-to-back ratios. However, with the spacing and element sizes the same as a quad, the gain should be the same, or at least so close the difference would be insignificant. On-the-air tests have shown the antenna to be as good as or better than quads the author has had up. Front-to-back and front-to-side reports have been outstanding, both on ground wave and skip.

Element Lengths

Many tests have been made on driven elements to determine the effect of element lengths on SWR. It was found that the flattest curve was obtained with the formula

$$\frac{1005}{f_{MHz}} \text{ (feet)}$$

for the driven element. The reflector should be about three percent longer, or

$$\frac{1030}{f_{MHz}}$$

If directors are desired it would appear that a length three percent shorter than the driven element would be adequate.



Fig. 16 — This drawing shows the driven element and feed method of the Delta Loop. Tests have shown that the overall length of the antenna is slightly longer than a wavelength (1.02λ). Each side of the antenna is approximately 1/3 wavelength long. The top, or wire section, is made slightly shorter to put tension on the vertical members.

Table 1

Bill of Materials

Tubing used is 6061 T6.
4 — 12-foot lengths of 3/4-inch OD, 0.035 wall (elements).
1 — 12-foot length 1-3/4-inch OD, 0.065 wall (boom).
8 — 3/4-inch diameter stainless steel hose clamps.
1 — 9-inch length of 3/8-inch OD by 5/16-inch ID.
1 — 9-inch length of 1/2-inch OD to slide over 3/8-inch section.
25 feet of copper wire no. 12 or 14, or equivalent in stranded wire.

Feet X 0.3048 = m.
Inches X 25.4 = mm.



Fig. 18 — Here are the details on the gamma-matching section. As mentioned in the text, the coax fitting can be a female type SO-239, mounted on a small bracket which is mounted on the boom. Spacing insulators for spacing the gamma line from the element can be made up from pieces of Lucite or Plexiglas.



Fig. 17 — This drawing shows the method of mounting the element to the boom. A cotter pin is used on the under side of the boom and a hose clamp on the top to hold the element securely to the boom.



Here is our roof-mounted 20-meter Delta-Loop beam that is now undergoing a series of tests.

As to element spacing, the author has long been an advocate of wide spacing (0.17 to 0.2 wavelength) whenever possible. In the 10-meter tests 0.2 wavelength spacing was used.

For readers who are interested, complete construction information on a 10-meter model, including a list of the required tubing, follows.

Construction Notes

Fig. 17 shows the method of mounting the element tubing to the boom. The angle between the semi-vertical elements is shown as 75 degrees but this can vary a few degrees either way without any appreciable effect on the performance of the array. It is difficult to drill and line up the element support holes in the boom and come out to *exactly* 75 degrees.

There are a couple of methods of making the holes in the boom to hold the elements. One of the simplest is to use a Greenlee-type chassis punch. This makes a clean hole in the boom. Another method is to drill holes large enough to take the end of a 3/4-inch (19-mm) reamer and then ream out the holes to the necessary diameter.

One not accustomed to working with angles might find it difficult to drill holes at a 75-degree angle. A simple method is to first drill holes to take a single element. Next, make a jig from a piece of stiff cardboard or similiar material, using a protractor to get the 75-degree angle. Then insert the single element into the boom and lay the jig along the element; this will give you the correct alingment for the other element.

The elements are inserted through the boom just far enough to take a cotter pin on the underside of the boom. On the top side, a hose clamp is used to hold the element to the boom and prevent slippage. A length of copper wire can be wrapped around both elements just below the clamp to insure a good contact between the elements and the boom. Hose clamps are also used at the tops of the elements to hold the horizontal wire.

Fig. 18 shows the details of the gamma matching section. The gamma section is made up from the inner conductor of the coax, including its insulation, and two sections of telescoping aluminum tubing. The outer covering and braid is removed from a 52-inch (1.32-m) length of RG-8/U coax. In Fig. 18, a male coax fitting is shown with a short length of braid, 2 inches (51 mm) long, which is grounded to the boom via a clamp and bracket. If desired, a chassis-type coax fitting, type SO-239, could be mounted on the boom with a small metal bracket. The capacitor section is made of two lengths of tubing 3/8-inch (10 mm), and 1/2-inch (13 mm) diameter, respectively, and both 9 inches (229 mm) long. The 3/8-inch (10 mm) tubing fits over the insulation around the coax inner conductor while the 1/2-inch (13 mm) tubing slides over the 3/8-inch (10 mm) material. The larger tube is drilled and tapped to take a locking screw. Spacing of the section from the element is 3 inches (76 mm).

In adjusting the gamma, figures given in



Fig. 19 — For those interested in exact figures, this sketch provides the element and boom lengths for a Delta-Loop beam for 28.8 MHz.

Fig. 19 can be used as a guide. In order to avoid matching errors, the gamma should be adjusted with the SWR bridge right at the beam. Set the shorting bar to the dimension given in the diagram and slide the 1/2-inch (13 mm) tubing over the smaller tubing, looking for a setting that gives a match. If one cannot be obtained, move the shorting bar and sliding tubing assembly a short distance, say an inch (25 mm), and then try different settings of the 1/2-inch (13 mm) tubing until you find a match. We found that the settings were not critical in getting a match. Once the beam is matched, the regular feed line to the station can be attached to the feed point. The connection should be taped to prevent moisture from getting into the fitting and coax.

As stated earlier, the antenna is extremely flat across the entire 10-meter band. The present model was designed for 28.8 MHz and matched at this frequency. The SWR at the highest point, at 29.7 MHz, was about 1.2 to 1. This dropped to 1 to 1 at about 29 MHz and stayed at 1 to 1 all the way down to 28 MHz. This feature of the antenna certainly is a help when using a transceiver designed for 50-ohm output. The beam has proved its ruggedness through winds and icing conditions. All in all, we think the Delta-Loop beam is one of the best performers we have seen. This material was originally presented in *QST* by Harry R. Habig, K8ANV.

References

[1] [Editor's Note: A triangular loop configuration also was described in *QST* in April 1968, "Technical Correspondence" by Norman Watson, W6DL, independently of K8ANV's design. Mr. Habig has been working for some years on this design and has a patent pending.]

[2] [Editor's Note: A 10-meter model of the Delta Loop beam tested at ARRL headquarters was matched at 28.8 MHz and an SWR curve was made using a Bird Wattmeter. The largest mismatch also was less than 1.2 to 1 MHz (at 29.7 MHz).]

The Delta-Loop Beam on 15

DX capability, low SWR and readily available construction materials are highlights of this 15-meter beam antenna. Similar to a quad, but rugged as a Yagi — those are the virtues of the Delta Loop.

Some of the features of the 15-meter beam described in this article include a very low SWR across the entire band, use of readily available materials, "Plumber's Delight" type construction — which is always an appealing feature of any beam antenna — and last but not least, excellent performance. On the last point, the antenna shown in the photographs was tested during a DX contest with a transmitter input power of 100 watts. The boom of the antenna was mounted only eight feet (2.44 m) above the ground, but in about five hours of contest operation 58 different countries were worked — and, believe it or not, the majority of the reports received were 59. Possibly conditions were above par, but even so the antenna shows it can do a real job under crowded band conditions.

As stated above, the beam uses Plumber's Delight type construction. For the newcomer's information, this type of construction has the antenna elements connected directly to the boom which in turn can be connected directly to earth ground without having any effect on the performance of the antenna. This is desirable because of the lightning protection offered by the system.



Fig. 20 — Basic configuration of the Delta-Loop driven element. Each side is approximately 1/3-wavelength long.

Fig. 20 is a drawing of the Delta-Loop driven element. The overall length around the driven element is slightly over one wavelength. Each side is approximately 1/3 wavelength long. The reason we say "approximately" is that the top section of the antenna is made of wire and is slightly shorter than 1/3 wavelength in order to put tension on the wire. A gamma-match feed system is used, eliminating the need for a balun.

The formula used in figuring the driven element length is

$$\frac{1005}{f_{MHz}},$$

where f is the desired resonant frequency of the driven element. The answer will be in feet. The reflector length formula is

$$\frac{1030}{f_{MHz}}.$$

For a frequency of 21.2 MHz this figures out to a driven element 47 feet 5 inches (14.45 m) long and a reflector that is 48 feet 7 inches (14.81 m) long. Element spacing is approximately 0.2 wavelength or about 9 feet (2.74 m). Fig. 21 shows the two elements with the lengths of each segment.

Material Requirements

The beam elements were built primarily from Reynolds Do-It-Yourself aluminum tubing, which *should* be available from most hardware dealers. The reason we say "should" is because in some sections of the country hardware stores don't stock the tubing. However, most dealers will order the tubing for you. If you live in an area near or in a city of reasonable size, a look through the Yellow Pages will show any aluminum tubing dealers. The Reynolds



Fig. 21 — The element dimensions and the boom length. All measurements on the elements are made from where the element enters the boom; the portion of the element extending through the boom is not counted.



Fig. 22 — Construction details for the boom-to-mast mounting bracket. The U bolts holding the boom are 2-inch (51-mm) type. Those holding the mast will depend on the mast diameter — we used 1-1/2-inch (38-mm) U bolts for a 1-1/2-inch diameter mast.

Table 2

Shopping List

Quantity	*Length (ft)*	*Diameter (in.)*	*Reynolds no.*
4	8	1	4242
4	8	3/4	4222
2	6	7/8	4231
1	9	2	See Text.

3 feet of 3/8- or 1/2-inch diameter aluminum tubing.
12, 1-inch diameter hose clamps, stainless steel.
35 feet of no. 12 or 14 copper wire, solid or stranded.
1 variable capacitor, 100 pF maximum, 0.025 spacing or greater.
1 one-quart freezer container.
1 SO-239 Coax chassis connector.
5 1/4-inch diameter aluminum nuts and bolts, 1-1/4-inches long.

Feet X 0.3048 = m.
Inches X 25.4 = mm.

Do-It-Yourself tubing comes in 8-foot (2.44-m) lengths but most of the commercial tubing available from metal distributors comes in 12-foot (3.66-m) lengths. If you obtain the 12-foot types, be sure to specify type 6061 (61S) alloy as this material affords excellent strength for antenna elements. The boom used in this antenna was made from this alloy and is 2 inches (51 mm) in diameter with a 0.065-inch (1.65-mm) wall. Another source of aluminum or steel tubing is electrical supply houses; although this type of aluminum is a little too soft for the elements it would be suitable for a boom. Also, electrician's thin-wall steel tubing is available in various sizes, including the 2-inch diameter, for a boom. In a pinch, the boom could be made of wood, such as a length of 2 × 4. In such a case, the bottoms of the elements could be connected together with a length of wire to maintain the Plumber's Delight feature. The shopping list included here should prove of help in purchasing the parts.

Construction

The first step in building the antenna is to make up the vertical elements. The description given here is based on using the Reynolds tubing. Using a hack saw, cut the 7/8-inch (22-mm) tubing into 2-foot (0.61-m) sections. This particular type is made by Reynolds for the purpose of telescoping the 1- and 3/4-inch (25-mm and 19-mm) diameter sections together and comes in 6-foot (1.83-m) lengths. After cutting off four 2-foot (0.61 m) lengths you'll have one 4-foot (1.22-m) piece remaining. Cut this into four 1-foot (0.31-m) lengths and set these pieces aside for the time being.

Next, cut two lots, the thickness of the hacksaw blade, about 2 inches (51 mm) deep in one end of each of the 1-inch (25-mm) and 7/8-inch (22-mm) diameter lengths. Slide the 7/8-inch tubing inside the 1-inch diameter to a length of about 6 inches (152 mm) and then slip the hose clamps over the slots and tighten them. The 3/4-inch (19-mm) tubing can then be inserted into the slotted ends of the 7/8-inch (22-mm) tubing and these sections clamped with hose clamps. Two of the elements should be adjusted to the proper length for the driven element and two for the reflector, as per Fig. 21 (or whatever length you wish from the formulas). Some amateurs may prefer to cut their antennas for the cw portion of the band and others for the phone section.

The next step is to cut the 1-inch (25-mm) holes in the boom to take the ends of the 1-inch diameter elements. We used a 1-inch chassis punch to make the holes, but a 1-inch metal reamer could also be used. The aluminum is easy to cut or punch so making the holes should be no problem. What can be a problem is lining up the holes so that the 75-degree angle between the elements is obtained. We made a jig from a piece of cardboard, using a protractor. Once one set of holes for the director and reflector were made the elements were temporarily mounted in the boom. The cardboard jig was laid on the elements and the 75-degree holes were marked off and drilled.

When the holes are all drilled, the boom can be laid on the ground and the element ends inserted into the boom holes. We allowed about 1/4-inch (6-mm) extension of the base of the elements through the boom so as to allow space for cotter-pin holes. However, before drilling the cotter-pin holes, insert the four 1-foot (0.31-m) lengths of the 7/8-inch (22-mm) tubing into the elements at the boom. This will serve to give added strength to the elements at the support point. Drill each of the four ends to take the cotter pins and install the pins. Tighten down the hose clamps on the top side of the boom to secure the elements in place.

Drill the tops of the elements to take the 1/4- × 1-inch (6-mm × 25-mm) aluminum bolts. The top wires can then be installed.

The close-up view shows the gamma installation. The gamma capacitor is mounted inside a plastic freezer container which is held in place by a small metal L-shaped plate mounted on the box and the boom, using four self-tapping screws. This plate also holds an SO-239 coax chassis fitting to take the feed line. We like to install an SWR bridge directly at the beam when making SWR or matching tests to reduce matching errors, and having the fitting there simplifies the procedure. The gamma rod, made from a length of 3/8-inch (10-mm) aluminum tubing 36 inches (0.91 m) long, is flattened at one end for a length of 1-1/2 inches (38 mm).The flatted portion is bent over at right angles and drilled to take one of the 1/4- × 1-1/4-inch (6-mm × 32-mm) aluminum bolts, which is mounted through the top of the freezer box. The gamma rod is held in place by this bolt and by the shorting bar between the rod and the element. The shorting bar is made from a piece of aluminum, 1 inch (25 mm) wide and long enough to fit around the two pieces of tubing and provide a separation of 3 inches (76 mm) between the rod and the elements.

How you mount the antenna boom to the supporting mast will depend a great deal on what type of tower or supporting structure you have. The method shown in the photo is a fairly simple one, and easy to make up. Fig. 22 shows details of the construction of the mounting unit. The one shown in the photo supporting the beam was made from two pieces of 1/16-inch (2 mm) thick aluminum plate. However, we found that even with the double plate there was still too much "give" in the mounting setup, so a replacement was made from 1/4-inch (6 mm) thick aluminum. This made the mount competely steady. Either a plate of 1/4-inch aluminum or 1/8-inch (3 mm) steel should be adequate for the jobs. The 2-inch (51 mm) U bolts that hold the boom to the mounting plate were adequate, but just for added insurance, 3/8-inch (10 mm), 2-3/4-inch (70 mm) long machine bolts (two required) were installed through the boom and mounting plate for greater holding strength.



This view shows the completed antenna being matched.

During our tests, a weather front moved through the area and we had wind gusts up to 40 mph plus icing and snow loading on the antenna. The antenna and elements showed very little movement in these winds, and the entire antenna appeared very strong.

Adjustments

Adjustment of the gamma section is quite simple. Install an SWR bridge at the gamma feed point and tune up the rig on the desired frequency, Set the gamma shorting bar 24 inches (0.61 m) from the base of the gamma rod and tighten the gamma-bar nuts and bolts just enough to make electrical contact. Set the SWR bridge to read reflected power and adjust the gamma capacitor for a dip. The object is to find a setting of the capacitor and the gamma bar that gives a reading of zero in the reflected position. This may take a few tries, but you'll find the settings are not critical. If you adjust the antenna near the ground you may find it will require a new adjustment when it is up in its permanent location.

How you mount the antenna in its permanent location will depend on what you have to hold the antenna. If you use a boom mounting-plate-to-mast assembly such as already described, the U bolts holding the boom could be left slightly loose and the 3/8-inch (10-mm) bolts left out. The antenna could then be installed in an upside-down position and then rotated into place. Two men are better than one for this job, but one man *can* do the job. If a hole, say 1/2-inch (13-mm) diameter, is drilled through the boom a 1/2-inch rod could be slid through to serve as a lever to rotate the boom and antenna into an upright position and the U bolts and hardware could be then tightened down.

We think the Delta-Loop beam is an excellent antenna and offers many possibilities. Certainly the results obtained to this point prove the antenna is a real performer. Our tower is a crank-up job, making antenna testing a fairly simple project. The antenna was first matched at the 8-foot (2.44 m) level (boom height) and at the cranked-up height, about 55 feet (16.76 m) above ground. A very slight readjustment of the gamma capacitor was required at the greater height in order to get down to a 1-to-1 SWR. However, the change in SWR from the 8-foot to 55-foot (2.44- to 16.76-m) heights was very small. Also, the highest SWR was at 21,450 kHz, the top end of the band, with a mismatch no worse than 1.2 to 1. At 21,300 kHz the SWR dropped to 1 to 1 and remained at that figure all the way to the lower band edge.

The entire antenna weighs about 15 pounds (using the aluminum boom) so the antenna could be rotated with a heavy-duty TV rotator. One last note: We sprayed the cotter pins and hose clamps with a clear acrylic spray to reduce corrosion. This simple precaution should be taken in all antenna construction to prevent or reduce rusting. This material was originally presented in *QST* by Lewis G. McCoy, W1ICP.



The plastic freezer box is held in place by the small metal bracket which is attached to the boom with self-tapping screws. Also on the bracket is a coax fitting to take the RG-8/U coaxial feed line. The gamma rod is mounted on top of the box and is held to the element with the shorting clamp.



In this close-up view of the end of the boom, the mounting of the element ends are clearly shown. Cotter pins are used on the bottom end of the element and hose clamps on the top side of the boom. This secures the elements to the boom. The plastic freezer box that houses the gamma capacitor is clearly visible behind the elements.

Antennas for Travel Trailers and Campers

Pounding brass and rendering "lip service" from an RV or mobile home can be disappointing as all get-out if the antenna doesn't "play" well. Here are some tips for rig-mounted radiators that get the job done.

Who knows why so many hams like to go camping? Perhaps it's their Field Day training; perhaps it's the next logical step after mobile operation, or perhaps they just cannot leave home without their rigs. At any rate, it is nice to have your own means of communication with the outside world when you are away from home in the Maine woods, at the Grand Canyon, or even down in Mexico.

One thing all hams know is that no matter how good a transmitter you may have, you cannot get out without an antenna; and the better the antenna is, the better you get out. The antenna is usually no problem for the home station. The sky is the limit, so to speak. A 65-foot (19.81 m) crank-up tilt-over tower with a triband beam on top, and a couple of inverted Vs for 40 and 75 are not at all uncommon. But did you ever contemplate transporting such an antenna system to a state park, or some other campground, and setting it up while your XYL cooked suppper? Obviously, the mobile operator is faced with vastly different problems than those confronting the ham who stays at home, when it comes to antennas.

In 1929, the author built a 14-foot travel trailer, which was christened "Black Maria." Shortly thereafter, the writer got a ham license, and one of the first thoughts was toward a rig for the trailer. This was in the days when mobile operation was still a novelty, and the story of Black Maria was the author's first contribution to *QST*, in 1933. The rig used a pair of 33s in parallel operating from a B-battery pack.

Over the ensuing 35 years, many portable antenna designs have been tried, and much has been learned about their relative performance. The degree to which a trailer traveler is restricted in a choice of an antenna varies widely, of course, depending upon the facilities available at each stopping point. These are seldom known in advance, but to get the most out of the equipment, the trailer operator should be prepared to take maximum advantage of whatever facilities he may find on each occasion.



The author's 30-foot (9.14 m) Airstream trailer with the 75-meter Airstream Loop in place. The "tuning" mast is the one carrying the flag.

Dipole Antennas

Long ago, it was found that a simple dipole for 40 or 75 would far outperform the author's mobile whip, even with the dipole only a few feet above ground. While writing this, sitting in the latest Black Maria — a 30-foot Airstream job — up in Port Colburne, ON, the author was listening to the 75-meter phone band. The dipole is only 8 feet (2.44 m) above ground. When checking into the Airstream Travel Trailer Net, which meets every Sunday on 3963 kHz at 8 A.M. local time, the writer worked other trailer stations in Connecticut, New Jersey, Maryland, Pennsylvania, New York and Ohio. Several times the author switched to the mobile whip and could not be heard through the QRM. Such a dipole can be prefabricated and, when rolled up, occupies very little storage space.

When the length of the stay warrants it, and trees or other supports are available, the antenna will be even more effective when raised to a respectable height. A bow and arrow is kept on hand for shooting lines over taller trees. Incidentally, Hy-Gain makes a deluxe portable dipole consisting of two stainless-steel tapes in a double plastic housing. The tapes are calibrated in meters, and can be quickly reeled out to the proper length for use on any desired band. The unit is fitted with a coax connector, making installation very easy.

If only a single support is available, the dipole can be used in "inverted-V" fashion. A convenient way of putting up such an antenna is to use three or four 5-foot (1.52 m) lengths of 1-1/4-inch (32 mm) aluminum TV masting as a center pole, mounting it on the front of the trailer. The author has a mounting for such an arrangement clamped to the bumper, as shown in one of the photographs. The mast can be equipped with light nylon halyards for hoisting the center of the dipole. The ends of the dipole can be attached to whatever may be handy, but the higher, the better.



Insulated mounting at one end of the "Airstream Loop" 75-meter antenna. The "tuning" mast can be mounted directly in one of the other sockets. The tuning will vary with the spacing between masts as well as the length of the "tuning" mast. The insulated mounting can be transferred to one of the side sockets to obtain maximum spacing.

Loaded Antennas

Of course, there are many times when the surroundings, or the shortness of the stopover, make erection of a conventional dipole impractical. On these occasions, the author used one or another of several arrangements shown in the accompanying photographs and sketches. Where the



An elevated mounting for a mobile whip at a top rear corner of the trailer body. The bracket is fastened by pop rivets. This point may also be used, with the whip removed, for feeding wire dipoles.

A check with a 20-watt fluorescent lamp by W1WKZ indicates the "hot" points on the Airstream Loop 75-meter antenna system.

antenna system is one that requires a ground for operation, it was found that a quarter-wave wire counterpoise connected to the trailer, and strung out a few feet above ground, is usually a much better "ground" than the trailer alone, even if the trailer is actually grounded to a driven rod. The author carries two each of wires cut to lengths of 8, 16, 32 and 60 feet (2.44, 4.88, 9.75 and 18.29 m) for use as counterpoise on the 10-, 20-, 40- and 75-meter bands, respectively. One end of each wire is fitted with a large battery clip, while the other is terminated in an insulator. Trailer awning poles come in handy as counterpoise supports when nothing else is available.

"Airstream Loop" Antenna

Of particular interest is the 75-meter folded configuration shown in the sketch of Fig. 23, which is called the "Airstream Loop," although, strictly speaking, it does not function as a true loop. With the fittings that are provided, this antenna can be put up in a few minutes, and its performance seems to be about equal to that of a low dipole. It has the advantage that it is completely supported by the trailer, and requires no external supports. It is contained entirely within your own campsite. There are no wires strung out for you or your neighboring campers to trip over or be garroted by in the dark. A 30-foot (9.14-m) length of wire is strung between, and connected to, two poles made of aluminum TV mast sections. A third mast (A), of approximately the same length as the others, and connected to the trailer, is an essential part of the system. This arrangement appears to work as a folded half-wave antenna, the 30-foot (9.14-m) wire and the two poles connected to it forming one half of the antenna, while the other half is formed by the trailer body and mast (A). Probing with a fluorescent lamp shows that the end of the trailer opposite the feed point is "hot" while the feed-point end is "cold." The system can be tuned by adjustment of the length of pole A, and/or changing the spacing between A and the adjacent pole. The spacing can be changed by a selection of the pole mounting sockets shown in one of the photographs. In this manner, the resonant frequency can be changed by almost 150 kHz. For any adjustment, the transmitter can be tuned about 30 kHz either side of the resonant point before the SWR exceeds 3 to 1. Since the "hot" end of the trailer is the front end in my case, the tow car must be unhitched, and an insulating block used under the customary supporting jack.



A 25-foot (7.62 m) base-loaded antenna mounted on brackets attached to the side of the trailer.

In a similar arragement for 40 meters, mast A is omitted, and a wire approximately 21 feet (6.40 m) long is connected to the pole at the feed-point end. The open end of the wire is supported from the pole at the opposite end of the trailer by a length of nylon rope.

40-Meter Monopole

Another 40-meter antenna that has been used with considerable success is a 34-foot (10.36 m) length of 300-ohm ribbon line connected as a folded monopole, and strung up in the same manner as the antenna just described. One conductor of the ribbon is grounded to the trailer at the feed point, while the other conductor is connected to the center conductor of the coax line. The two ribbon conductors are connected together at the far end.

Matching

Standing-wave ratios up to 5 or 6 to 1 are hardly worth worrying about at 4 MHz so



A five-band antenna system. A New-Tronics mobile antenna base section is fitted with a Waters Add-a-Band adapter. The short resonators for 10, 15 and 20 meters are Waters. The 80-meter resonator (top) is New-Tronics. A threaded stud has been added to the vacant side of the adapter to take a New-Tronics 40-meter resonator. The system is fed at the base with a single coax line.



Fig. 23 — 75-meter "Airstream Loop"



A bumper-mounted socket for TV masting.



An 80-meter dipole made of two New-Tronics 75-meter mobile whip back to back. The 15-foot (4.57 m) mast is bumper-mounted. A 1-to-1 balun is mounted on the center insulating panel, which is secured to the mast with U bolts. This antenna is quite narrow-band when operated on 75 meters, making it necessary to retune the antenna for excursions of more than 30 or 40 kHz.



Brackets for mounting TV masting on the side of the trailer. The upper bracket is fitted with a removable U-shaped yoke bolted to the bracket. The brackets are fastened to the trailer with pop rivets.

Table 3

Hustler 75-meter mobile whip mounted vertically on top rear corner of trailer	S7
Same as above, with 60-foot counterpoise wire connected to trailer	S9
Two Hustler 75-meter mobile whips back to back as a horizontal loaded dipole	S9 + 5 dB
60-foot horizontal wire 8 feet high, using trailer as ground	S9 + 10 dB
Hustler 4BTV trap vertical with 75-meter resonator	S9 + 10 dB
120-foot dipole, 15 feet high at center	S9 + 20 dB
"Airstream Loop" antenna	S9 + 20 dB
Home-station dipole 50 feet high	S9 + 30 dB

Feet = 0.3048 = m.

far as additional power loss is concerned. However, an SWR greater than 1 to 1 causes the line input impedance to vary, depending on the length of the line. The output circuits of many transmitters and transceivers are not designed to work into loads departing significantly from 50 ohms. With these units, it may not be possible to load the final stage, or components in the output stage not designed for the voltages that develop with higher-impedance loads may be damaged. Use a Monimatch, or other reflectometer, and adjust the antenna for minimum SWR. The author carries along several mica capacitors ranging in value from 50 pF to 0.002 µF with battery clips attached, which are used to shunt the line at the feed point. Start out with the lowest value, and double the capacitance in steps until you get an SWR of 1 to 1 somewhere in the band, and then adjust the antenna length for resonance at the desired frequency.[1]

To get some idea of the relative performances, a series of checks was made at 3825 kHz on several of the antennas described. A receiver with a horizontal antenna was set up at a distance of eight miles from the trailer, and S-meter readings were taken with the results shown in the accompanying tabulation. All readings were made with identical input power to the transmitter, and with the antennas adjusted for an SWR of 1 to 1.

To sum it all up:

1) Carry a complete set of mobile whips for lunch stops, or other occasions where you just do not have the time or room for anything better.

2) If at all possible, use a 1/4-wave counterpoise clipped to the trailer when using a mobile whip.

3) If you have the time or space, clip a 1/4-wave wire, instead of a whip, to your mobile antenna mount, and run it out to a bush or tree.

4) In addition to (3), clip a 1/4-wave counterpoise to the trailer, and run it in the opposite direction.

5) If you are stopping for a short time, or for the night, rig up the 5-band mobile whip with five 1/4-wave counterpoises, one of appropriate length for each band.

6) If you want to concentrate on one band, put up the 16-foot (4.88 m) mobile-whip dipole, if your space is limited.

7) If you have plenty of room, put up a 1/2-wave dipole for your favorite band.

8) If you want to work all bands, and space for dipoles is limited, then put up your trap vertical with the 75-meter resonator tuned to your favorite frequency.

9) If you are going to spend a week in a particular campground, shoot some lines over a couple of high trees with a bow and arrow, and get your dipoles up in the air as high as possible.

10) The use of balloons and kites is good, but depends completely on the wind.

11) Next best to a high dipole, put up the "Airstream Loop" antenna for 75 meters.

12) If all else fails, bring your 2-kW PEP linear and your 2.5 kW ac gas generator along. This will at least keep the other campers awake. Don't forget a low-pass filter for TVI! This material was originally presented in *QST* by Philip S. Rand, W1DBM.

[1] [Editor's Note: This method is equivalent to the use of a stepdown L network. It can be used when the antenna feed-point impedance is lower than the line impedance. To obtain a match, the antenna length must be somewhat longer than a resonant length, so that the antenna shows inductive reactance at the feed point. (This reactance serves as a substitute for the reactance of the coil of a conventional L network.) For an accurate match, it is necessary to adust the antenna length and the value of the capacitor until the appropriate transformation ratio is obtained.]

The Apartment Dweller's Dilemma

Having trouble getting a signal out from "concrete city"? Nonresonant, random-length wires can provide surprising results if a Transmatch is used to make the rig happy with the load it sees.

It is apparent that many would-be amateurs living in apartment buildings believe it is impossible to get an effective signal on the air. They feel the need to have an outdoor antenna in order to make contacts. This isn't true. Of course, the apartment dweller can always go mobile, but there comes a time when the amateur wants a home station. This article treats the problem and, hopefully, will get a few more hams on the air.

Some General Considerations

There are exceptions to the following rules but, in general, they can be depended upon.

1) An outdoor antenna will work better than an indoor one.

2) An antenna inside a frame building with wood exteriors is better than the same antenna in a steel-and-concrete building.

3) The higher above ground, inside or out, the better the antenna will work.

4) The bigger (or longer) you can make an indoor antenna, the better — even if it means running the wire around corners.

5) Even a poor antenna *should* produce some contacts.

The completed Transmatch. The counter dial and knob are James Millen Mfg. Co., Inc. products. Check with G. R. Whitehouse, Amherst, NH 03031.

The Coupling Problem

Most transmitters are designed to work into a 50-ohm load, and contain little or no provision for adjusting the transmitter when the load is other than 50 ohms. Unfortunately, there is no random-length wire antenna that will present a 50-ohm load on all bands. What is required is a Transmatch. A Transmatch is simply an adjustable LC network that converts the unknown antenna impedance to 50 ohms. This unit, shown in Fig. 24 and the photographs, will cover the 80- through 10-meter bands and can handle 1 kW of rf power. In addition to matching the transmitter to the antenna load, the Transmatch helps reduce harmonic radiation. Many Novices get in trouble with the FCC because of 2nd-harmonic radiation from the 80-meter signal. This unit should reduce such harmonic radiation. Also, the use of a Transmatch can provide better front-end selectivity for the receiver. Some receivers are subject to severe cross modulation when operated near a broadcast station. The Transmatch should reduce this effect.



Fig. 24 — Circuit diagram of the L-network Transmatch. The eight banana jacks are E. F. Johnson type 108-900, and three dual banana plugs are required, E. F. Johnson type 108-200.

C1 — Variable capacitor, 350 pF (E. F. Johnson 154-10).

D1, D2 — 1N34A germanium diode.

J1, J2 — Chassis connector, type SO-239.

J3 — Feedthrough terminal, isolantite.

L1, L2 — See Fig. 25, part of etched circuit assembly.

L3 — Variable inductor, 28 μH (E. F. Johnson 220-203).

M1 — 100-μA meter.

R1, R2 — 68-ohm, 1/2-watt carbon or composition, *not wirewound.*

R3 — 25,000-ohm carbon control, linear taper.

S1 — Spst toggle.

Circuit Details

The unit shown in Fig. 24 is designed to be used in three configurations. They are shown at B, C and D. With one of the three hookups, it should be possible to match practically any antenna to the transmitter.

In order to get complete band coverage and avoid the complexities of bandswitching, banana and jack plugs are used to change the circuit to the configuration needed. For example, if one wanted the setup shown at B, he would jumper terminals 7 and 8, 1 and 3, and 4 and 5. Using the banana plugs makes for easy changing of the circuit.

Whenever a Transmatch is used, the operator should have a way of knowing when the unit is adjusted correctly. The answer to this need is a Monimatch or other SWR indicator. If you have an SWR meter, it can be connected in the line between the transmitter and the coupler. If



Fig. 25 — Etched circuit-board template. The foil side is shown, with etched portion shaded.

not, you can build the Monimatch[1] shown in Fig. 24, and include it in the cabinet with the Transmatch.

Construction Details

The chassis for mounting the Transmatch is made from a piece of aluminum measuring 10 × 19 inches (254 × 482 mm). The ends of the 19-inch length of aluminum are bent up to form a U-shaped chassis, the ends being 4-1/2 inches high to form a chassis 10 × 10 × 4-1/2 inches (254 × 254 × 114 mm). The back side of the U has an opening cut out, 3-1/4 inches high by 4-1/2 inches (83 × 114 mm) long. A piece of Plexiglas is mounted over this opening. The jack-plug sockets are installed directly on the plastic. Connections from the roller inductor, L3, and variable capacitor, C1, are made to the banana jacks. Be careful when drilling the holes for the jacks to insure that they will mate with the plugs. Fig. 25 shows the details for a pc-board Monimatch.

Methods for making etched circuit boards are given in detail in the construction chapter of The Radio Amateur's Handbook, so we won't treat the process here. When installing D1 and D2 on the board, be sure to use a heat sink while soldering the leads. Too much heat can ruin the diodes. Shielded leads are used from the circuit board to S1 to prevent unwanted rf pickup.

Today's equipment builder soon finds out that locating parts can be a tough problem. Fortunately, we have found a distributor who will furnish all the parts. With the exception of the chassis, the parts for the Transmatch can be purchased from Barry Electronics.[2]

Some Antenna Ideas

With this Transmatch one should be able to match any random-length antenna to his transmitter. To test the system, we strung up 25 feet (7.62 m) of wire in the ARRL lab (a steel-and-concrete building, first floor). The Transmatch provided the desired 50-ohm impedance on all bands. We didn't get any "60-over-9" reports, but we *did* make contacts.

As to your antenna installation, we suggest running the wire up to the ceiling, around the room, perhaps into the next room, making the antennas as long as possible. If the XYL objects to the wire, use an invisible antenna. Nope, we're not



The Monimatch is at the upper left, covered by a metal enclosure. Connections from the roller inductor and the variable capacitor to the terminals on the jacks are made with thin strips of copper, although no. 12 or 14 wire can be used instead. The two antenna terminals are at the rear right. The top terminal is for use with a coax-fed antenna, if desired.

joking! You can make the antenna from no. 26 or 28 wire, which will be practically invisible. Also, you can conceal the wire behind molding. Be sure to insulate the wire if it runs near any metal. In some cases, it is impossible to get the wire outside. However, if you have a screen in one of your windows, terminate the end of the antenna at the screen. The screen *is* outside and it will help the system radiate. While it may be difficult to install, the antenna length to shoot for is approximately 120 to 130 feet (36.58 to 39.62 m) because this is a good length for multiband operation.

If you cannot put an antenna on the apartment roof, there is still a trick or two for having an outside antenna. You can drop a wire out the window and let it hang down. How long the wire should be will depend on how high up you are. You can make the wire long enough to reach nearly to the earth, but high enough to be beyond the reach of passersby. *Safety first*, always! There is no electrical law that states that a vertical must be fed at the bottom. Just connect the end of the wire to your Transmatch and tune up the system. You can use small-diameter wire. Use a lead sinker on the end of the wire and possibly imbed the sinker in a small sponge-rubber ball. (That way, you won't break your neighbor's window.)

If there is a support to which you can attach the far end of the antenna you can use the invisible-wire trick. Use rubber bands for insulators. Erect no. 26 or 28 wire. Don't be too discouraged if the wire gets broken by passing birds!

We know one ham who lived in a basement flat. He ran a wire through the wall to the bottom of a rain gutter, tuned up the system, and managed to work DXCC. (Safety first, again. The downspout should be beyond the reach of human beings!) The general idea is to use ingenuity. With a Transmatch you never can tell *what* will prove to be a useful antenna.

How to Tune Up

Using the Transmatch is not complicated. Although it takes some time to find the correct combination of settings, once determined, they can be logged for later reference. Use a short length of 50-ohm coax to connect the Transmatch to the transmitter. Attach the antenna to the Transmatch. Tune up your transmitter on the desired band, making sure that the final amplifier is resonated, but with the power output reduced. With the Monimatch in the forward-reading position, set the sensitivity control for a full-scale reading. You may have to increase the output of the transmitter to get full deflection, but be sure to keep the final amplifier tank in resonance. Switch the meter to the reflected position, and then adjust L1 and C1, until you get the lowest indication of reflected power. It should be possible to get the meter to read zero. When you have a zero reading in the reflected position, versus full scale in the forward setting, the Transmatch is correctly adjusted, and the SWR is 1. You may have to change the circuit to one of the other configurations in order to get a match, but one combination should work. Once you have the Transmatch set properly, you can then adjust the transmitter to its rated power input. One other point: It isn't always possible to get a good ground connection in an apartment. Therefore, a connection to a cold-water pipe or earth ground should be used. This material was originally presented in *QST* by Lewis G. McCoy, W1ICP.

References

[1] McCoy, "An Etched-Circuit Monimatch for Checking Your Antenna System," *QST*, October 1969. (See Chapter 5.)

[2] Barry Electronics, 512 Broadway, New York, NY 10012.

A 40-Meter DDRR Antenna

This antenna consists of a 1/4-wavelength element grounded at one end and wound into a single-turn coil, a few conductor diameters above the ground (see Fig. 26).

Shortly after the author's article on a practical DDRR Antenna appeared,[1] a number of inquiries were received regarding low-frequency versions of this antenna for operation at ground level. After a little experimenting, the author came up with this version of a 40-meter DDRR which works quite well. In early tests very fine QSOs were held with stations as far away as Phoenix, while the antenna was located inside the garage and surrounded by myriad metallic objects. When the antenna was relocated to the backyard, marked improvement was noted, even though this antenna site was marred by a sharp rise of 4 feet (1.22 m) in ground elevation, plus close proximity to house wiring and power lines. In spite of these obstacles solid contact was easily achieved with stations up and down the West Coast. Encouraged by these results, we moved the antenna to a rooftop location which put it well in the clear insofar as metallic objects above the groundplane were concerned. In this location, the DDRR really proved its worth. In spite of its low profile, a little over 1 foot (0.31 m), and its very small span, a few inches over 9 feet (2.74 m), it was more than adequate when competing with any signal on the band. The obvious conclusion from my experiments is that the 40-Meter DDRR is the apartment-dweller's dream. It is principally for that group that this article is prepared. Other interested amateurs might be those who are limited, as this author is, by too much house on too little real estate; or those who for other reasons cannot cope with high towers, masts and guy wires.



Fig. 26
RD = 0.078 λ (28°)
SP = 0.11D (2.5°)
FP = 0.25 h (See Note 1)
C = (See Note 2)
D = (See Note 3)
G = (See Table 4)

Notes: (1) Actual dimension must be found experimentally. (2) Value to resonate the antenna to the operating freq. (3) d ranges upward from 1/2" (13 mm). The larger "d" is the higher efficiency is. Use largest practical size, e.g., 1/2" (13 mm) for 10 meters, 5" (127 mm) or 6" (152 mm) for 80 or 160 meters.

Before this writer's enthusiasm sends you out to rip down your inverted V or to dismantle your beam, remember this: The DDRR, for all of its capabilities, will not supplant a full-size single-frequency antenna which is properly erected over clear terrain. What it will do is provide an



The chicken-wire groundplane is evident in the background. The base plate can be seen at lower right. Note the relative positions of the 52-ohm coaxial feed at the left end of the plate, the flange on the foot of the post, and the tuning unit at the right-hand end of the plate.

The braided lead across the flared joint is to assure electrical continuity. The screws used are self-tapping sheet-metal screws. The top end of the insulator (2-inch [51 mm] diameter PVC pipe) is a standard PVC pipe cap; the bottom is closed off with a cap from an aerosol can (2-inch [51 mm] ID).


3" (76mm)
2 HOLES 1/8"(3mm) FOR FEED LINE CONNECTOR BRACKET
2 HOLES 1/4"(6mm) FOR EXHAUST PIPE FLANGE ATTACHING FOOT TO BASE PLATE
1/2" (13mm)
1-1/2" (38mm)
8" (203mm)
2 HOLES 1/8" (3mm) TO MOUNT TUNING UNIT, CAPACITOR, AND MOTOR ON SAME BRACKET
10" (254mm)
1 HOLE 1/8"(3mm) TO CONNECT BASE PLATE TO GROUND PLANE
2" (51mm)
3" (76 mm)
3" (76mm)
1" (25mm)
5" (127mm)
3" (76mm)
1" (25mm)
17" (431mm)

Fig. 27 — Drawing of the base plate which can be made from either steel or aluminum, as described in the text.

Table 4

Dimensions for 1/4 Wavelength DDRR Elements

Band (Meters)	*160*	*80*	*40*	*20*	*15*	*10*	*6*	*2*
Feed Point (FP)*	12"	6"	6"	2"	1.5"	3"	1"	1/2"
Gap (G)	16"	7"	5"	3"	2.5"	2"	1.5"	1"
Capacitor, pF (C)	150	100	70	35	15	15	10	5
Spacing (Height) (SP)	48"	24"	11"	6"	4 3/4"	3"	1 1/2"	1"
Tubing Diameter (D)	5"	4"	2"	1"	3/4"	3/4"	1/2"	1/4"
Ring Diameter (RD)	36'	18'	9'	4.5'	3'4"	2'4"	16 1/4"	6"

*See Fig. 26 for explanation of designations.

Feet X 0.3048 = m.

Inches X 25.4 = mm.

antenna which will enable communications of respectable quality, where heretofore it has been impossible because of inadequate space to erect a 40-meter antenna.

Some consideration should also be given to the fact that the high-Q nature of the DDRR and its resultant narrow-band characteristics serve to reduce the noise level. Boyer[2,3] reports that in the initial experiments it was found that DX stations which could copy signals from either a vertical or a DDRR could only be heard on the DDRR due to the reduction in background noise. So if you have a noisy location, it might be to your benefit to try the DDRR, regardless of what antenna you are presently using.

Constructing the 40-Meter DDRR

In this application, 2-inch (51 mm) diameter automobile exhaust pipe was used as the radiating element. The local muffler shop not only supplied the material, but also undertook to bend it to specifications. This was an obvious course since the material and the power bender were right at hand.

The dimensions for 40 meters are:

Ring — 9 foot (2.74 m) diameter, center to center.

Height — 12 inches (0.31 m) from ground plant to element center.

Gap — 6 inches (152 mm) from upright post center to open end of ring.

In forming the ring to these dimensions, four 10-foot (3.05 m) lengths of tubing were used. A 10-degree bend was made at 9-inch (229 mm) intervals in three of the lengths. The fourth length was similarly treated, except for the last 18 inches (0.46 m) which were bent at right angles to form the upright leg of the ring. One end of each section was flared so that the sections could be coupled together by slipping the end of one into the flare of its mate.

The required flares are easily made at the muffler shop with the aid of the forming tools. Another task which can best be completed at the shop is to weld a flange onto the end of the upright leg. This flange is to facilitate attaching the leg to the mounting plate which provides a chassis for the tuning mechanism and the coaxial-feed coupler. After bending and flaring is complete, the ring is assembled and minor adjustments made to bring it into round and to the proper dimensions. This can best be done by drawing a circle on the floor with chalk and fitting the ring inside the circle. The circle must be slightly larger than the center-to-center diameter so that the reference line can be seen easily. For example, with two-inch (51-mm) tubing the actual diameter of the reference circle must be 9 feet, 2 inches (2.79 m). When you



Fig. 28 — Circuit diagram of the power supply and control motor.

D1 through D4 — 1 A, 50 PRV, or equiv.
F1 — Fuse, 1 A.
J1, J2 — Two-terminal jack.
MT1 — Motor (see text).
P1, P2 — Two-terminal plug.
S1 — Spst.
S2 — Dpdt, center off.
T1 — Transformer (see text).



Clamps used to connect the feed line and the open end to the capacitor are standard hose clamps. The heavy black lead, center to lower right, is the 52-ohm feed line. The smaller line coming from the plastic housing is the motor control line.

have a satisfactory fit between the tubing ring and the chalk ring, drill a 1/4-inch (6-mm) hole through each of the joints to accept a 1/4-inch bolt. These bolts will clamp the sections together. Also, they can be used to attach the insulators which support the ring at a fixed height above the groundplane.

Making and Attaching the Insulators

Insulators for the antenna were made from 11-inch (279-mm) lengths of 2-inch (51-mm) PVC pipe inserted into a standard cap of the same material. The PVC caps are first drilled through the center to accept the 1/4-inch (6-mm) bolt previously installed at the joints. The caps are then slipped onto the bolts and nuts are installed and tightened to secure the caps in place. The 11-inch length of pipe, when inserted into the cap and pressed firmly until it touches bottom, results in a total insulator length of 12 inches (0.31 m). Four insulators are required: one at each of the joints and one near the open end of the ring for support. It is wise to locate this insulator as far back from the end of the ring as possible because of the increasing high rf voltage that develops as the end of the ring is approached.[4] As a final measure, the bottom ends of the insulators were sealed to prevent moisture from forming on the inside surfaces. Standard PVC caps could be used here, but we found that plastic caps from 15-ounce aerosol cans fit well.

Making the Mounting Plate

The mounting plate is required to provide good mechanical and electrical connections for the grounded leg of the radiator, the coaxial feed-line connection, and the tuning mechanism. If you are using aluminum tubing, you should use an aluminum plate, and for steel tubing, a steel plate to lessen corrosion from the contacting of dissimilar metals. Dimensions for the plate are shown in Fig. 27. The important consideration here is that good, solid mechanical and electrical connections are made between the ground side at the coaxial connector, the ring base, and the tuning capacitor.

The Tuning Unit

We found that the 9-foot (2.74 m) ring resonated easily with approximately 20 pF of capacitance between the high end of the ring and the base plate or ground. A 35-pF double-spaced variable from the junk box was pressed into service here (Cardwell NG-35-DS). Any variable which will tune the system to resonance and which will not arc under full power should be satisfactory. Remember, the rf voltage at the high impedance end of this antenna can reach 20 to 30 kV with high power, so if you are using the maximum legal limit, you would do well to consider using a vacuum variable capacitor. Since we limited our power to 500 watts PEP, the double-spaced Cardwell unit was satisfactory. To provide for full band coverage, the capacitor was coupled to a reversible, slow-speed motor which enabled the antenna to be remotely tuned from the operating position. An indicated SWR of 1.1 to 1 was easily achieved over the entire 40-meter band. The motor used was a surplus item made by Globe Industries of Dayton, OH.[5] At 20 volts dc the shaft of this motor turns at about 1 rpm which is ideal for DDRR tuning. The gears used were surplus items. If you cannot obtain gears, string and pulley drive will do almost as well, or you can mount both the motor and the capacitor in line and use direct coupling. Of course, if you operate on a fixed frequency or within a 40- to 50-kHz segment of the band, you can dispense with the motor entirely and simply tune the capacitor manually. In any case, the tuning unit must be protected from the weather. We used a plastic refigerator box to house the tuning capacitor and its drive motor.

Fig. 28 shows the electrical connection for the motor. A small train transformer or power supply for toy slot-cars will work admirably as a tuning motor power source. Standard ac zip cord was used for the connection between the control unit and the motor.

Electrical Connections and the Groundplane

The connection between the open end of the ring and the tuning capacitor is made with no. 12 wire or larger. On the end of the base plate opposite the tuning unit, and directly under the ring about 8 inches (203 mm) from the grounded post, install a bracket for a coaxial connector. The connector should be oriented so that the feed line will lead away from the ring at close to 90 degrees. Install a clamp on the ring directly above the coaxial connector. Connect a lead of no. 12 or larger wire from the coaxial connector to the clamp. This wire must have a certain amount of flexibility to accommodate the movement necessary when adjusting the match. The matching point must be found by experimentation. It will be affected by the nature and quality of the groundplane over which the antenna is operating. The antenna will function over earth ground; however, in our location we found the electrical ground to be unpredictable. A groundplane surface of chicken wire (laid under the antenna and bonded to the base plate) provided a constant ground reference and improved performance. In a rooftop location sheet metal roofing should provide an excellent groundplane. A poor ground usually results in a matching point for the feed line far out along the circumference of the circle. In our installation a near-perfect match was obtained with the feed line connected to the ring about 12 inches (0.31 m) from the grounded post. During testing, when the antenna was set up on a concrete surface without the groundplane, a match was found when the feed line was connected nearly 7 feet (2.13 m) from the post!



The tuning motor, above the capacitor, couples to the capacitor shaft through the gears at left. Both the motor and the capacitor are mounted on a common bracket which attaches to the base plate by two bolts through the weatherproof housing. The lead passing upward through the grommet connects the stator of the capacitor to the open end of the ring.

As shown in photos, the compactness of the antenna is readily apparent. The groundplane is made up of three 12-foot (3.66-m) lengths of chicken wire, each 4 feet (1.22 m) wide, which are bonded along the edges at about 6-inch (152-mm) intervals. In our installation the antenna, with the groundplane, could be dismantled in about 30 minutes. If portability is not important, it is best to bond all of the joints in the tubing so that good electrical continuity is assured.

After all construction is completed, the antenna should be given a coat of primer paint to minimize rust. If it suits you, there is no reason why a final coat of enamel could not be applied.

Tuning Procedures

Once the mechanical construction is completed, the antenna should be erected in its intended operating location. Coupling to the station may be accomplished with either 52-ohm or 72-ohm coaxial cable. Tune and load the transmitter as with any antenna. While observing an SWR meter in the line, operate the tuning motor. Indication of resonance is the noticeable decrease in indicated reflected power. At this point, note the loading of the transmitter; it will probably increase markedly as antenna resonance is approached. Retune the transmitter and move the feed-point tap on the antenna for a further reduction in indicated reflected power. There is interaction between the movement at the feed tap and the resonance point; therefore, it will be necessary to operate the tuning motor each time the tap is adjusted until the lowest SWR is achieved. Don't settle for anything less than 1.1 to 1. With a good ground and proper tuning and matching, this ratio can be achieved and maintained over the entire band. Once the proper feed point has been located, the only adjustment necessary when changing frequency is retuning the antenna to resonance by means of the motor. If the antenna is to be fixed tuned, provide an insulated shaft extension of 18 inches (457 mm) or so to the tuning-capacitor shaft for manual adjustment. This not only provides insulation from the high rf voltage but also minimizes body-capacitance effects during the tuning process.

Alternatives

A number of materials other than the steel tubing used here are well suited for the ring element. Standard E.M.T. or electrical conduit would work as well with a slight increase in weight. One advantage to be gained through the use of conduit is the elimination of the flaring operation since standard couplings would serve to connect each segment of the ring to its adjacent member. Another suitable material is copper tubing. This material is superior to either exhaust pipe or conduit in terms of its conductivity characteristics. Another advantage of copper is that it is available in continuous lengths and the joints could be omitted entirely.

The 2-inch (51 mm) dimension is by no means mandatory. Smaller diameter tubing has been used with satisfactory results.[6] In fact, DDRR antennas have been fabricated with wire elements. But, if the element diameter is reduced, the antenna tunes more *sharply*. Some experimenters may wish to go in the other direction and use a larger diameter. The author recommends the use of aluminum downspout with a diameter of about 4 inches (2 mm). This material does not lend itself to bending, however, and the ring must be configured as a regular polygon of eight or more sides. Because of the large number of joints involved, welding is about the only practical means of joining the segments. Unless you are equipped to do this work yourself, the cost of welding might be prohibitive. Anyone who undertakes to make a DDRR antenna of a large element diameter will be rewarded in terms of improved performance.

Performance

Results have been quite encouraging, and it is hoped that more and more hams will equip themselves with the DDRR in the future. The antenna has proved its worth and deserves more investigation by the amateur fraternity than it has been given in the past. No intensive efforts have been made to work DX with the antenna described here: however, a low angle of radiation is conducive to DX, and this antenna demonstrates a low radiation angle. It was found that distant areas, such as the East Coast, are more easily contacted than are stations nearby. All of the results could be attributed to peculiarities of individual stations or skip conditions, but since they are charateristics which can be anticipated with high-efficiency antennas having low radiation angle, we prefer that interpretation. Besides, where else will you find an antenna for 40 meters that is small enough to fit into a corner of the backyard and not protrude above the fence; or for that matter, which could be mounted on the roof of an apartment building or even a ranch-type house and not be visible from the street?

Nearly everyone who listened to the description of this new antenna was enthusiastic. The author hopes to hear many hams on the air working with the DDRR in the near future. This material was originally presented in *QST* by W. E. English, W6WYQ.

Parts List

4 — 10-ft (3.05 m) lengths of 2-in. (51 mm) tubing, exhaust pipe, conduit or copper tubing.
1 — base plate 7-1/2 X 19 X 1/8 inches (191 X 482 X 3 mm), steel, aluminum, or copper to match tubing.
4 — PVC pipe caps for 2-inch (51 mm) pipe.
4 feet (1.22 m) of 2-inch PVC pipe.
2 clamps for 2-inch tubing.
4 — 1/4 X 4-inch (6 X 102 mm) bolts with nuts.
1 reversible motor with 1-rpm shaft output.
1 wide spaced variable capacitor. 5 to 35 pF (Millen 16550 or equiv.).
1 coaxial connector SO-239.
2 sets 2-connector plug and socket for motor control.
36 feet (10.97 m) of 4-foot (1.22 m) chicken wire or equivalent.
1 flange to attach tube to base plate.
2 — 1/2 X 1-inch (13 X 25 mm) bolts with nuts (flange mounting).
8 — 3-inch (76 mm) bonding strips no. 8 braided wire.
4 plugs 2-inch (51 mm) ID for insulator bases.

References

Hicks, "The DDRR Antenna: A New Approach to Compact Antenna Design," *CQ*, June 1964.
Horn, "The Half Wavelength DDRR Antenna," *CQ*, September 1967.
The Radio Amateur's Handbook, 46th ed., The American Radio Relay League.

Notes

[1] English, "A Practical DDRR Antenna," *73*, June 1970.

[2] Boyer, U.S. Patent Nos. RD 26196, RE 3,151,328 (All rights assigned to the Northrop Corporation.)

[3] Boyer, "Hula-Hoop Antennas: A Coming Trend?" *Electronics*, January 11, 1963.

[4] Editor's Note: Because of the danger of rf burns, in the event of accidental contact with the antenna, precautions should be taken to prevent random access to the completed installation.

[5] Globe C-5A-1106 (available from Lectronic Research Labs Inc., 75 Arch St., Philadelphia, PA 19106).

[6] See footnote 1.

Novi-Loop

A medium-size roll of wire, some insulators and a day of good antenna "puttin' up" weather can net you a Novi Loop. What will it do for you? Well, follow these instructions and get set to work 40-meter DX. Nuff said!

One of the sad facts of life for many beginners is the matter of poor antenna performance. Many enthusiastic Novices have fallen behind in their efforts to work DX because of bitter disappointment caused by poor performance in the antenna department. All too often it is suggested that a simple end-fed hunk of wire is ample for all-around Novice band operation, or that a dipole will suffice for most Novice operation. Sure, almost any kind of radiator that can be tuned to the operating frequency and marched to the impedance of the feed line and transmitter will enable the operator of a low-power station to make some contacts from time to time. It depends on how high the system is above ground, how free and clear it is of surrounding objects that can detune the radiator and absorb the energy radiated from it, and upon the condition of the band at a given time. It should stand as a firm rule, then, that any amateur who wants good results should erect the best antenna system he can, consistent with available space, finances and structural practicality. It is possible to advance beyond the plateau of simple dipoles and random-length wires in the quest for better performance, and without going to the expense and effort of erecting large directional beams such as the cubical quad or Yagi.

What will be described here can be applied to any of the high-frequency amateur bands. However, the example given relates to only the 40-meter Novice band. The antenna is a full-wave loop of wire, mounted through necessity at W1FB in a rectangular format, and matched with a simple quarter-wavelength coaxial transformer. It has given excellent performance in DX work and for making "solid" stateside contacts. Total cost for the antenna system (wire, matching transformer and insulators) is under $12, exclusive of the feed line used to connect the antenna to the rig.

Antenna Features

Full-wave, closed-loop antennas are broadband, low-Q devices. This is a handy feature because it permits the operator to move his transmitter frequency within a particular band without need to compensate for an increase in standing-wave ratio (SWR) which might otherwise occur if other types of antennas were used. (The higher the Q of an antenna, the narrower its bandwidth, even though an SWR of 1 can be obtained at some frequency within the band for which it is built.) The foregoing rules out the need for a Transmatch with the loop antenna, provided the feed method recommended here is applied.

Another interesting feature of this kind of antenna is the theoretical gain of approximately 2 dB it exhibits over a half-wave dipole. The angle of radiation from a properly erected full-wave loop is considered to be lower than that of a dipole when both are less than one-half wavelength above ground. This feature suggests the superiority of the loop in situations where significant height above ground is not a practical goal for the chap wishing to put up a 40-meter antenna.

A full-wavelength closed loop need not be square. It can be trapezoidal, rectangular, circular, or some distorted configuration in between those shapes. For best results, however, the builder should attempt to make the loop as square as possible. The more rectangular the shape, the greater the cancellation of energy in the system, and the less effective it will be. The effect is similar to that of a dipole whose effectiveness becomes impaired as the ends of the dipole are brought closer and closer together. The practical limit can be seen in the "inverted-V" antenna, where a 90-degree apex angle between the legs is the minimum value used. Angles that are less than 90 degrees cause serious cancellation of the rf energy.

The loop can be fed in the center of one of the vertical sides if vertical polarization is desired. For horizontal polarization it is necessary to feed either of the horizontal sides at the center. At the time of this writing there have been no data compiled to provide a comparison between the performance, vertical versus horizontal. Such an experiment could be interesting (and possibly productive) for the Novice.

Erecting the Antenna

Optimum directivity occurs at right angles to the plane of the loop, or in more



Fig. 29 — Details of the full-wave loop. The dimensions given are for operation at the low end of 40 meters (7050 kHz). The height above ground was 7 feet (2.13 m) in this instance, though improved performance should result if the builder can install the loop higher above ground without sacrificing length on the vertical sides. The inset illustrates how a single supporting structure can be used to hold the loop in a diamond-shaped configuration. Feeding the diamond at the lower tip provides radiation in the horizontal plane. Feeding the system at either side will result in vertical polarization of the radiated signal.

simple terms, broadside from the loop. Therefore, one should try to hang the system from available supports which will enable the antenna to radiate the maximum amount in some favored direction. The bidirectional pattern is maximized NE and SW at the writer's QTH. This gives good results in working Europeans and the stations "down under." Excellent signal reports have been obtained off the sides of the loop when working within the USA.

Just how the wire is erected will depend on what is available in one's yard. Trees are always handy for supporting antennas, and in many instances the house is high enough to be included in the lineup of solid objects from which to hang a radiator. If only one supporting structure is available it should be a simple matter to put up an A frame or pipe mast to use as a remaining support. (Also, tower owners see Fig. 29 inset.)

The overall length of the wire used in a loop is determined from the formula

$$\frac{1005}{\text{f (MHz)}}.$$

Hence, for operation at 7125 kHz the overall wire length will be 141 feet (42.98 m). The matching transformer, an electrical quarter wavelength of 75-ohm coax cable, can be computed by dividing 234 by the operating frequency in MHz, then multiplying that number by the velocity factor of the cable being used. Thus, for operation at 7125 kHz

$$\frac{234}{7.125\ \text{(MHz)}} = 32.84 \text{ feet}$$

If coax with solid polyethylene insulation is used, a velocity factor of 0.66 must be employed. Foam-polyethylene coax has a velocity factor of 0.80. Assuming we are to use the solid dielectric coax, RG-59/U, the length of the matching transformer becomes 32.84 (feet) × 0.66 = 21.67 feet, or 21 feet 8 inches (6.605 m). The transformer will convert the 100-ohm feed-point impedance of the loop to 50 ohms, a convenient value for connecting the system to the transmitter. The loop described here was measured with the K1TD Macromatcher[1] and found to exhibit an impedance of 110 ohms. Some inductive reactance was indicated. By removing 1 foot (0.31 m) of wire from the overall loop the reactance dropped to zero, though the antenna loaded up fine prior to the final trimming. The feed impedance at 21 MHz was also 110 ohms, but considerable inductive reactance was observed. Most certainly one could use the antenna on 15 meters with reasonable success, despite the SWR which might be present.

Results

During two weeks of testing the loop gave an excellent account of itself. It was compared with the writer's two-element short beam for 40 meters, and the results indicated that the loop was better than the beam on some occasions. At other times the beam provided better performance, or was at least equal to the loop. The differences noted were the result of band conditions and the time of day. High-angle signals can cause misleading results when comparing antennas for hf-band use. More meaningful tests can be made on ground-wave contacts, however, and several checks made between the loop and the beam indicated that radiation at right angles to the plane of the loop compared closely with that from the front of the beam. The beam is rotatable and installed 40 feet (12.19 m) above ground.

With 150 watts dc input to the transmitter PA, and operating at the low end of 40 meters (loop was cut for 7050 kHz), the first night of operation resulted in the logging of three Russian stations, two Polish ones, two Yugoslavians, one Italian station and two English ones. The lowest report was RST 549. The highest report was RST 599. Generally speaking, the loop has outperformed the beam during most long-haul contacts. Though no effort has yet been made to work South American stations (off the side of the loop), they have been heard loud and clear, as have some VK stations via long path at approximately 2300 UTC.

It is quite likely that the Novice who chooses to erect his own Novi-Loop will have a commanding signal on 40 meters. If backyard space permits, it should be a worthwhile venture. Don't forget, the formulas and guidelines given here are applicable to the other hf Novice bands as well. This material was originally presented in *QST* by Doug DeMaw, W1FB.

---

[1] Hall, "The Macromatcher," *QST*, January 1972.

Chapter 5

Antenna Theory and Test Methods

In order to obtain top performance from a given style of amateur antenna, it is important to understand the basic principles of operation. Additionally, some test procedures are necessary if one is to ensure that his or her antenna is functioning at its best. This chapter contains assorted data on antenna theory, plus a number of common-sense test methods.

These reprints of popular *QST* articles were chosen for all amateurs, regardless of their technical-aptitude levels. There's something to honor in the phrase, "Learn by doing." This chapter will help to make that philosophy a reality.

Quad vs. Triband Yagi

The controversy about quads working better than Yagis, or vice versa, may never end. But, we'll bet our newest roll of RG-8/U that you'll find some interesting reading on the subject in this report.

While stationed in Japan, a sort of DX crossroads of the world, this writer had the opportunity to observe, firsthand, the excellent performance of the cubical quad in competition with the Yagi, dipoles and an assortment of other antenna systems. In pursuing this undertaking certain steps were necessary to insure than any conclusions made would be meaningful. With this in mind a play emerged.

Objectives

In the many articles written on the cubical quad, it is noteworthy that only on a few occasions have the authors been privileged to compare the quad with other types of antennas on a real-time basis, and from the same operating location. Furthermore, when such comparisons were made, the authors generally compared against some type of monoband antenna system. A casual scanning of the 10-, 15- and 20-meter phone bands would lead one to conclude that the triband Yagi enjoys a rather high position of popularity among the antennas in general use. This being the case, it appeared that a worthwhile contribution to the data already available on the Yagi and quad might be made by conducting a series of controlled comparative tests, employing the triband Yagi and the quad. The test objectives were then defined: to compare various configurations of a cubical quad antenna with a representative commercial triband Yagi; such tests to be conducted over short, medium, and long transmission paths, and to arrive at conclusions regarding the relative merits of each antenna.

Table 1

	Mod. 1	*Mod. 2*	*Mod. 3*	*Mod. 4*
Reflector Element	72'3"	70'4"	72'5"	72'5"
Driven Element	69'	70'4"	70'5"	70'5"
Director Element	—	—	—	69'1"
Spacing "A"	7'6-1/2"	8'5"	13'4"	13'
Spacing "B"	—	—	—	13'
Stub	20-30"	34-38"	—	—

Feet X 0.3048 = m.
Inches X 25.4 = mm.

Test Plan and Procedure

Every effort was made to conduct the tests in a manner which would lessen the possibility of compromising the techniques employed by either the writer or participating stations:

1) The test to be performed by establishing communications with Amateur Radio stations located throughout the world on a random and scheduled basis.

2) Amateur Radio stations volunteering to assist in this effort to be briefed on conduct of test and data desired.

3) A voice ssb transmission to be made to the participating station, identifying the first antenna used as antenna "A."

4) The voice transmission to be followed immediately by an unmodulated carrier for a period of approximately 5 seconds.

5) The antennas would be switched, and a voice transmission made identifying the antenna as "B," and the procedures above repeated.

6) Participating stations will note signal strength related to each antenna, and provide a numerical value as observed on his S meter or other indicating device. These values to be logged, and the test reinitiated with another volunteer station.

Equipment Preparation

1) Antenna heights to be as nearly identical as possible.

2) Center of antenna horizontal lobe patterns to be as nearly identical as possible when pointing the antennas toward a participating station.

3) Resonant frequency of each antenna to be matched as closely as possible.

4) Transmission lines to be matched to antennas and transmitter loading to be as nearly identical as possible with each antenna.

5) Instantaneous transfer of antennas.

6) Relative power and SWR to be monitored continuously.

7) Prior to and after each data gathering session, equipment parameters will be verified. If a significant deviation in any parameter is noted, data collected will be discarded.

Antenna performance conclusions to be based on an analysis of data derived from a minimum of 50 unmodulated-carrier observations with each antenna configuration, and supplemented with data gathered during conventional ssb QSOs.

Table 2

	Mod. 1	*Mod. 2*	*Mod. 3*	*Mod. 4*
Total Observations	50	60	60	52
Less than 2100 miles	12	2	3	3
2100 to 4800 miles	33	31	33	32
Greater than 4800 miles	5	27	24	17
Signal Difference				
More than 1 S unit better	—	—	—	—
Less than 1 S unit better	—	—	7	9
No discernible difference	1	5	51	43
Less than 1 S unit poorer	27	46	2	—
More than 1 S unit poorer	22	9	—	—

Antenna Selection

This writer had been using a four-element commercial triband Yagi (boom length 24 feet [7.32 m], and 55 feet [16.76 m] above ground) for approximately 1-1/2 years, so the properties of this antenna were fairly well established. Furthermore, in on-the-air comparisons with competitive models of triband Yagis in use by other U.S. amateurs operating from the Tokyo area, the antenna appeared representative of commercial triband antennas in general use by the amateur community. Therefore, the Yagi in use at the author's station was selected as the reference antenna.

Text material concerning quad antennas, available to the author in Japan, was reviewed. It became evident that there are almost as many variations in quad design as there are writers on the subject. After much deliberation, and many discussions with amateurs throughout the world, the decision was made to test three models of the quad (a fourth model was tested as will be noted later). Since the physical characteristics of the quad are fairly standard, only the dimensions of the elements and the spacing between them was considered. The dimensions for the three models tested were obtained from a Japanese manufacturer of cubical quads, from Orr's book, *All About Cubical Quad Antennas,*[1] and from Dr., J. E. Lindsay, Jr., W0HJ.[2]

Preliminary Testing

Several days were spent "dry running" the test plan to validate the concept, and to smooth out the operating procedures and techniques. Of particular concern was the possible time required to make a valid data-gathering observation. If data were to be reasonably accurate, the transmission path had to be stable, and the signal-strength observations must be taken on each antenna during a short period of time. The dry runs were valuable in this respect.

A problem became evident during the first day of testing. It appears that those of us who speak and understand English do not always convey the same message when using the same words. As a result it was necessary to modify the verbal format, utilizing simple sentences and placing them in a logical sequence.

It also became apparent that the test could not be conducted under all transmission-path conditions; that even under ideal conditions several observations were often necessary before a conclusive report could be compiled. It was decided to conduct the tests only on 20 meters. The operating time available to the writer favored openings on 20 meters to Europe via the long path, and to Australia, the U.S. and various islands in the Pacific. It was also decided to orient the test antennas so that the topography and obstructions seen by each antenna would be essentially the same. (Physical separation between the two antennas was in the order of one wavelength.)



Fig. 1 — Element spacing information for Table 1.



Fig. 2 — CLOSE SPACING IS FOR THE BIRDS!

Testing

Dimensions of the first quad model selected were furnished by a Japanese manufacturer of cubical-quad antennas. (see Table 1). The antenna was assembled, utilizing commercially manufactured heavy-duty hardware and fiberglass spreaders. It was tuned to a center frequency of 14,200 kHz. Testing of the first model began in November 1967 and continued for one month. The results for this period are given in Table 2.

In mid-December 1967 the first quad was replaced by a model constructed according to the formula and dimensions given in Orr's book. The results obtained with model 2 are contained in Table 2.

Construction of the third model (with wider element spacing) was carried out next. Two matching systems (Gamma and Q-section) were experimented with on this antenna. A satisfactory match could be had with either system. However, the Q-section was used for the test because it was the technique used with the previous two quad models (SWR with each antenna was never more than 1.3:1 with a difference between antennas no greater than 0.1). The results conducted with this model were most enlightening, as shown in Table 2. The model antenna was also used extensively during the first weekend of the 1968 ARRL DX Contest. Though these contacts were not used in tabulating test samplings, it is interesting to observe that openings to the U.S. (using the quad) lasted 15 to 30 minutes longer on each end of the period than with the Yagi. It is assumed that this phenomenon would also apply to each of the other quad models.

The fourth quad tested was a 3-element wide-spaced model constructed according to more dimensions furnished by W0HJ. The results of the samplings were somewhat disappointing and are given in Table 2. (Frankly, the author felt that the 3-element quad would show a substantial improvement over the Yagi in every case.) The 3-element model did appear to have a better front-to-back and front-to-side ratio than either the Yagi or the other quad models. One positive comment: The 3-element model is a monster to assemble and put up! In the author's opinion the difference in performance isn't worth the small improvement. Perhaps, on the other hand, if one accepts the 2-element model as the departure point between a simple mechanical structure and a major project, a 4-element model might be more worth the effort. However, this is purely conjecture on the part of the author.

Summary

The antenna tests indicate that:

1) One can expect to achieve the same or better results with a 2-element quad of proper dimensions than with a 3- or 4-element triband Yagi.

2) A wide-spaced quad will perform substantially better than a close-spaced quad.

3) Dollar for dollar, the quad appears to be a better investment than a Yagi.

Acknowledgements

The writer wishes to thank all of the amateurs who participated in the series of tests, particularly the VK gang, who night after night tolerated the request for observations. The support couldn't have been better, and on many occasions, upon completing a check with a particular station, several other stations would call to give their observations (which were taken during the same transmission test). This material was originally presented in *QST* by Col John H. Parrott, Jr., W4FRU.

References

[1] Orr, *All About Cubical-Quad Antennas*, Radio Publications, Wilton, CT 06897.

[2] Dimensions later published: Lindsay, "Quads and Yagis," *QST*, May 1968. (See chapter 3).

High Versus Low Antennas Performance Tests Using Identical Arrays

This section compares the performances of identical antennas mounted side-by-side at different heights, and produces some experimental evidence to support the practical importance of antenna height for most types of Amateur Radio communication.

"The higher the better" is the traditional rule of thumb for ham radio antennas. Few amateurs would disagree with this axiom, and most experienced antenna builders can recall how much better they got out after "raising the beam another 15 feet (4.57 m)." However, few empirical studies of the effect of antenna height on signal strength have been published in amateur circles.

This is unforunate, since several amateurs have studied the question methodically, including Dr. J. E. Lindsay, who has now published his definitive treatise on quads and Yagis[1] but not his excellent work in this area. And while both *The ARRL Antenna Book* and Orr's *Beam Antenna Handbook*[2] discuss the importance of antenna height in theoretical terms, neither reports the results of practical studies in the field.

With this in mind, the author set out to study the effect of height on signal strength at various distances, on several bands, and with various forms of propagation. Only amateur equipment was available for the study, but in other respects, the author strived to keep the methodology as rigorous as possible.

The Method


The two cubical quads used by the author to study the effects of antenna height on performance. The antenna at right is atop a 34-foot (10.36 m) tilt-over mast described by the author in June 1969 *QST*. The quad at left is on a 72-foot (21.95 m) tower.

The author's approach was to erect identical antennas atop two towers of different heights and obtain comparative signal reports — with some safeguards to minimize reporting errors and to assure proper statistical treatment for the resulting data. For the main tests, one tower was 72 feet (21.95 m) high (the practical maximum for the author's residential backyard at the time of the tests), while the other stood 34 feet (10.36 m) high (about the minimum usable height for DX work, according to Orr). The two towers were placed as far apart as possible without trespassing — about 50 feet (15.24 m). With this separation, no interaction was evident on any band.

A pair of 2-element cubical quads were selected for the 10-, 15- and 20-meter experiments. Each had an eight-foot (2.44 m) boom with all elements mounted concentrically on two sets of spreaders, and each antenna was fed with a single feed line (85 feet [25.9 m] of RG-8/U in both cases). This design obviously involves some compromises in element spacing and impedance matching, but both quads developed good SWR curves and front-to-back ratios when tuned. And, more important for our study, whatever compromises existed were essentially the same for both the high and low antennas.

It became apparent during the tests that many amateurs regard cubical quads as exceptional performers at low heights, but (unlike Yagis) not much better if raised higher. This popular impression is contrary to Lindsay's findings, which suggest that quads and Yagis respond quite comparably to changes in their height. Accepting Lindsay's conclusions, we assumed that our findings would be roughly the same if Yagis had been used for the primary experiments.

Table 3

Comparative Performance Data for High and Low Antennas

Band/path	No. reports	No. favoring high antenna	No. favoring low antenna	No. reporting no difference	Mean high-antenna advantage
20/DX	16	16	0	0	2.1 S units
20/U.S.	18	15	0	3	1.4 S units
15/DX	12	12	0	0	1.8 S units
15/U.S.	36	20	0	16	0.9 S units
15/ground-wave	12	12	0	0	2.2 S units
10/DX	8	7	0	1	1 S unit
6/ground-wave	5	5	0	0	2 S units
6/E-skip	10	2	7	1	−1.3 S units
2/ground-wave	16	16	0	0	3.3 S units

The author wanted to determine how well high and low antennas would perform not only on DX work, but on "Stateside" F-layer communications, ground-wave work, and E-skip as well. Thus, separate tabulations were kept for DX reports (i.e., those from stations more than 4000 miles away) and for reports from "Stateside" stations (i.e., F-layer reports over 1500—3000-mile paths) on each frequency band.[3] The author was careful to avoid seeking reports during anything that resembled an E-skip opening on 10, 15, and 20 meters, in the interest of studying E skip vs. antenna height separately on 6 meters.

To study the effect of height on vhf groundwave signals, the author replaced the cubical quads on the two towers with two pairs of seven-element 2-meter Yagis, each fed in phase with ratio-dipole driven elements. A move to a new home prevented the use of the same two towers for 6-meter experiments, but the author later set up two 3-element 6-meter Yagis — one atop a new 90-foot (27.43 m) tower, and the other on a 42-footer (12.8 m) — to continue the study.

On each band, the tests were conducted on ssb (except on 2 meters, where a-m was used), with an audio tone serving as a reference signal. The author switched between the high and low antennas repeatedly on each test, in an effort to counteract the effects of QSB.

This test procedure does introduce some sources of error, including the variability of hams' skills in observing the results, and the lack of receiver S-meter standardization. To cope with this kind of sampling fluctuation, the author obtained a number of reports on each band and then used t-distribution statistical methodology to evaluate the resulting data. Even with these efforts to make the study as rigorous as possible, however, the author makes no claim to finality for the results obtained. The findings on each band did prove to be statistically significant (at the 0.05 level of significance or better), but you don't "prove" things or arrive at exact parameters this way. The only claim the author makes for his results is that they suggest general trends that will probably be confirmed if this study is replicated elsewhere. There is no implication here that a 72-foot (21.95 m) high antenna produces "12-dB gain" over a 34-foot (10.36 m) -high antenna in 20-meter DX work just because the mean advantage in our tests was about two S units in this instance.

The Results

The results of these tests, summarized in the accompanying table, were interesting in several respects. With the exception of one case on 10 meters, every single DX station reported a substantially better signal from the high quad than the low one. This is thoroughly predicted in the literature, but we also found that the high quad produced a significantly stronger signal (taking the mean, or average, figure) on "Stateside" work. And on ground-wave work, the high antennas were absolutely consistent in outperforming lower ones. However, E-skip contacts proved to be another story, a point to be covered in detail later. The mean advantage of the high quad over the low quad in DX work was 2.1 S units on 20 meters, 1.8 S units on 15, and one S unit on the 10-meter band.

Since the author's linear amplifier (a commercial unit using two 3-400Zs) produces a signal gain of about two S units over the exciter alone on most S meters, it became apparent that many DX stations could not distinguish the kilowatt feeding the lower quad from the exciter "barefoot" with the higher array. The implications of this dramatic difference in signal strength for DX-contest operations are obvious: it's no wonder the "big guns" using antennas 130 feet (39.62 m) high get through the pileups quickly, with or without big linears.

On Stateside F-layer work, the pattern was less consistent, although the high array continued to hold a significant edge. While a majority of the reports still favored the high quad by one or two S units, more than a third of the stations dissented, reporting equal or virtually equal signals from the two quads. No one reported a stronger signal from the lower antenna, perhaps because of the author's effort to avoid E-ship contacts in this phase of the study. The mean advantage of the higher quad was 1.4 S units on 20-meter Stateside work, and 0.9 S unit on 15 — still a substantial advantage, but not enough to render a low antenna useless for portable work, as generations of Field Day operators can attest. In fact, the author previously described a portable quad[4] that stood only 19 feet (5.79 m) high, but nevertheless worked very well for "back-home" contacts during a long vacation. An antenna only 19 feet (5.97 m) high is clearly undesirable, but if higher antennas are not feasible, much successful hamming can still be done. (This is especially true on an occasion like Field Day, when almost everyone's antenna is low, and the few beams that are 40 [12.19 m] or more feet high seem to dominate the bands; if the competition is using a low antenna you can too!)

Ground-wave Tests

Although the plan was to study the effect of antenna height on ground-wave communication only on vhf bands, a number of stations within 100 miles volunteered reports on the hf bands. These reports were not tabulated except on 15 meters, but they consistently favored the higher array by at least two S units.

In the vhf experiments, height again proved decisive for gound-wave work. On both 2 and 6 meters, every station favored the high antenna. On two meters, the mean advantage was an amazing 3.3 S units. Surprisingly, the higher array appeared to be equally superior on contacts with San Bernardino-Riverside stations (some 30 miles from Beaumont, CA, where these tests were conducted) and on contacts into the Los Angeles basin (almost 100 miles away).[5]

After moving and acquiring the 90-foot (27.43 m) tower, the author put a single 7-element 2-meter Yagi up and took an S-meter reading on a nearby repeater with the new tower cranked down. As the tower ascended to its full height, the signal rose from S8 to 15 dB over S9 on a popular transceiver's S meter.

On 6 meters, only a few ground-wave tests were conducted, but the results were similar: Everyone favored the higher antenna substantially.

6-Meter E-Skip Tests

However, on 6-meter E skip an entirely different relationship developed: The *lower* antenna had the advantage in seven out of 10 tests during single-hop openings.[6] Only one station favored the high antenna, and the low array had a mean advantage of 1.3 S units over the high array!

Although this finding is surprising and contrary to every other test conducted, it is consistent with the one previous practical study of antenna height vs. signal strength the author could locate in ham radio literature. Working in the late 1940s, Leroy May[7] set up identical 6-meter Yagis at heights of 35 and 75 feet (10.67 and 22.8 m), and compared 350 received signals on the two arrays. He found that the low array was superior for distances below 1000 miles while the higher array began to pull ahead at distances exceeding 1100 miles.

The author made no attempt to fully replicate May's work, but all of our 6-meter E-skip experience supports him: For contacts into many major cities from greater Los Angeles, a high antenna is a handicap! Much to his chagrin, the author has frequently seen his 90-foot (27.43 m) - high Yagi outperformed on 6-meter E skip by a beam sitting 10 feet (3.05 m) above somebody's roof on a TV mast.

Conclusions and Recommendations

It is customary when reporting a study such as this to conclude by summarizing the findings and making some recommendations. The conclusion here must be that, for every application except E-skip work, there are worthwhile advantages of having an antenna at least 70 feet (21.34 m) high. This height advantage is most pronounced on ground-wave and long-haul DX work.

The only logical recommendation we can make, then, is that all hams should own towers 70 feet (21.34 m) high. May all of the XYLs, frightened neighbors, bill collectors, and zoning-conscious city officials of the world forgive us!

Alternately, maybe we should suggest that all hams (except the author) use 35-foot (10.67 m) towers to give the author a better chance in DX contests. Or better yet, how about an antenna-height multiplier for the DX contests? Let's see, that's 1.5 if your antenna is below 75 feet (22.86 m), 2.0 if it's below 40 feet (12.19 m), and 3.0 if you bury it in the ground . . . This material was originally presented in *QST* by Wayne E. Overbeck, N6NB.

References

[1] Lindsay, "Quads and Yagis," *QST*, May 1968 (See chapter 3).

[2] Orr, William I., *Beam Antenna Handbook*, 3rd Edition.

[3] No 10-meter "Stateside" tests are reported because the muf was too low for reliable F-layer work across the U.S. when these tests were run.

[4] Overbeck, "The 20-Minute Portable Quad," *QST*, May 1967.

[5] On the hf bands, it is normally assumed that a high antenna has a greater advantage over a low antenna on long-haul DX than it does on shorter paths, but the opposite may well be true for vhf ground-wave work. This is suggested in the *ARRL VHF Manual*, (1st Edition, pages 24,25). Thus, one would expect that an increase in height would result in greater improvement in signals over the 30-mile path than over the 100-mile path.

[6] At the time of the 6-meter tests, E skip was barely "in season." The author is continuing this study during seasons of more frequent E-skip openings.

[7] May, "Some Practical Results on the Question of Antenna Height," *CQ*, April 1953.

Limited-Space Antennas and Methods Of Coupling

When short, random-length wire antennas prove disappointing, chances are the installer didn't follow a few basic rules for good performance. These tips should lead the way to better results with "randoms."

One very popular type of antenna, probably because of its simplicity, is a wire of either a predetermined or random length, fed at one end. It is common procedure among amateurs these days to refer to such an antenna as a "long wire." Actually, this term is usually incorrect because, by definition, a long-wire antenna is a wire that is several wavelengths long at the operating frequency. But no matter what you call it, the end-fed wire can be a very simple antenna to put up and use, if certain steps are taken.

Transmitter Loads

Nearly all transmitters described these days are designed to work into 50- to 70-ohm loads, with little thought given to any load that departs very far from these figures. If the load is something different than the above figure it may be impossible to get the amplifier in a transmitter to load up. In order for the final amplifier stage to operate at its best efficiency, the load (the antenna system) must be within the design range of the amplifier.

An end-fed wire may present a load of 50 to 70 ohms, but if it does it will be a case of pure luck on the part of the user — and what's more important, that load won't stay the same across a band. In other



The completed transmatch with the 80/40-meter coil plugged in. At the rear is the 20-meter coil and the 10/15-meter unit is to the front. In regular operation, the antenna would be attached to the standoff insulator at the top rear of the chassis. The clip lead visible below the coil is the one attached to the jack bar.



The wiring below deck. At the rear of the chassis is the Varimatcher section. C2 is at the left front of the chassis.



Fig. 3 — This block diagram shows the set-up for using a Transmatch. Not shown is an antenna relay which normally would be inserted in the coaxial line. If a low-pass filter is used, it should be the last item in the line before the Transmatch.

words, the antenna will present a 50- to 70-ohm load for only a very limited frequency range. Once we QSY the load may change to where it is no longer within the tuning range of the amplifier. Our problem boils down to having the transmitter *always* see a load of 50 to 70 ohms, regardless of the band or frequency in use. This in turn means we must make the antenna system look like a 50- to 70-ohm load, no matter which band we use it on.

The Transmatch, an Adjustable RF Transformer

Let's make one point clear about end-fed wires, or any antenna, for that matter: There is no way of predicting what the feed-point impedance (load) will be before making and installing the antenna. We can come close, but there are many factors that get into the act to determine what the impedance will be. The antenna's height, its proximity to nearby objects, its length, and the antenna's relation to earth ground are just a few of the factors. If we don't know what the feed-point impedance is, how can we make the transmitter always work into a 50-ohm load? The easiest way is to insert a Transmatch between the transmitter and the feed point. A Transmatch is simply an adjustable rf transformer that takes our unknown feed-point load and converts it to a desired load, 50 ohms in the case shown in Fig. 3.

Note in Fig. 3 that we show a random-length antenna and an earth ground connection. In this case, our unknown load exists between the end of the antenna and ground. On the transmitter side of the Transmatch we have 50-ohm coaxial cable and inserted in this cable is a 50-ohm reflectometer or SWR (standing-wave-ratio) bridge. The reflectometer is simply a measuring instrument that tells us when our Transmatch is properly adjusted to convert our unknown load to a 50-ohm load. If the Transmatch has adequate matching range, we can convert any feed-point load to 50 ohms. And this means that we can take any random length wire and make a working antenna out of it for any amateur band or frequency. There are some practical limits as to how short a wire we can use, but actually the antenna can be quite short in relation to a wavelength and still work.



EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF) ; OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS ; k = 1 000, M = 1 000 000.

C2 — 150-pF variable (Millen 19140 or similar).
D1, D2 — 1N34A germanium diode.
J1 — Coax chassis fitting, type SO-239.
L1, L2 — See Fig. 7.
L3, L4 — See Fig. 6.
C1 — 150-pF variable, (air gap 0.077 inch [2 mm] or larger for high power, Millen 12515 or similar; air gap 0.040 inch [1 mm] for low power, Millen 19140W or similar).
M1 — 0-1 milliammeter (more sensitive meter can be used).
R1 — 50-ohms, 1/2-watt carbon or composition, not wire-wound.
R2 — 50 kΩ control, linear taper.
S1 — Single-pole, single-throw toggle switch.

Fig. 4 — Circuit diagram of the Transmatch and Varimatcher. All 0.001-µF capacitors are disk ceramic.

Limited-Space Antennas

Many hams live in apartments or locations where it is impossible to put up an "antenna farm" or even a half-wave dipole for 80 or 40 meters. Random-length wires are sometimes the best bet in these circumstances. For hams who live under such conditions there are some general rules that can be followed for best performance. If possible, always get the antenna up on the roof. If not, get the antenna as high as possible. Make the wire as long as possible, even if it has to go around corners. Don't overlook existing antenna possibilities, such as rain gutters or roof flashing. In a moment we are going to describe a Transmatch that can be used to couple practically any wire or metal structure to the transmitter, including rain gutters.

If it is impossible to get an outdoor antenna up (and don't overlook "invisible" antennas[1]). an indoor antenna will work, but not as well as an outdoor one. With the Transmatch to be described, you can run a wire around the ceiling molding and couple the wire to the rig, maintaining that 50-ohm load we mentioned earlier. When you hear hams talking about loading up the bed spring, don't laugh — many a ham has made contacts that way. All you need is some method of coupling the bed spring to the rig; that's what our Transmatch will do.

The Transmatch

Shown in Fig. 4 is the circuit for a Transmatch that will do the job we've been talking about. This unit will match practically any wire to our 50-ohm rigs on any band from 80 through 10 meters. Depending on which capacitor plate spacing you use for C1 the Transmatch can be used for Novice powers or up to the legal limit of 1 kW. Actually, the closer-spaced capacitor will handle 200 watts or so. The same type coil stock is used for either power level, high or low.

Also included in the Transmatch shown in Fig. 4 and the photographs is an SWR bridge. This is a necessary item in order to know when the Transmatch is correctly adjusted. If you already have a Monimatch or reflectometer, the unit described can be eliminated from the Transmatch.

With the random-wire antenna we'll be dealing with various loads, depending on the frequency and band in use. Shown in Fig. 5 are the three basic circuit configurations used with the Transmatch. The circuit can be changed to conform with type A, B, or C by reversing the plug-in coil in the jack bar or by changing the capacitor C1 from the output side of the L configuration, as in B, to the input side, as in C. The capacitor is changed by means of a clip lead connected to the stator.

Some loads may require the circuit setup of A. In this configuration, a link-coupled parallel-tuned circuit is used, the antenna being tapped onto L1.

Construction Details

The chassis used to hold the parts is 2×7 × 9 inches (51 mm × 178 mm × 229 mm) and the panel measures 7 × 9 inches (178 mm × 229 mm). Any chassis large enough to hold the parts can be used. C1 and the jack bar for the plug-in coils are mounted on top the chassis, and the Varimatcher reflectometer and C2 are mounted below the chassis top. The remaining components are mounted on the chassis front.



Fig. 5 — Three possible configurations with the Transmatch as described in the text. To set up types B or C the plug-in coil is reversed in the jack bar and terminal no. 3 of the jack is clipped to terminal no. 2.

A 4-inch (102 mm) length of RG-58/U coaxial cable is used for the pickup and conductor sections of the SWR bridge. Details for making this section are given in Fig. 6. Study these details and the photograph of the bottom view carefully before starting construction. The black outer covering of the coax is removed, leaving the braid and inner conductor with its insulation. The outer braid will be L3 and the inner conductor L4. You'll notice that there is an open area at the center of the coax braid. This is to allow room for the connection of one end of the 50-ohm resistor to the center of the inner part of the coaxial line. Use a probe or pointed instrument to open up the area in the braid and then carefully tin the edges of the opening with solder so as to prevent any of the hair-like wires from shorting to the resistor lead or inner conductor. The ends of the braid can be wrapped with a few turns of solid wire and tinned. The wire ends will provide a support for the connection to the feed-through terminal and the inner pin of J1.

The metal trough that houses the bridge section is made from a piece of copper flashing, although tin or aluminum could be used. It is a good idea to drill the holes for J1 and the feed-through bushing before bending up the trough into a U. Also, when soldering the leads for the diodes, D1 and D2, use a heat sink between the body of diode and the point being soldered, because too much heat can ruin the diode.

Using the Transmatch

In making the antenna, shoot for a length of at least 1/4 wavelength at the lowest operating frequency. In other words, if you plan on working 80 meters as the lowest band, then the antenna should be 60 feet (18.29 m) long, at least. This doesn't mean that shorter wires won't work — they will, but not nearly as well. A lot of hams will say they can't get up a length of 60 feet! The wire doesn't *have* to run straight. You can go around corners, up and down, or what have you. The important point is to get up as much wire as possible.

By the same token, many hams think (mistakenly) that they have to have a good earth ground connection in order for their station to work. It's fine if you have one but if you don't, forget it. If you have access to a water pipe or other earth ground connection make a connection to the rig and the Transmatch, but if you can't, don't worry. The antenna will still work.

With the antenna connected and the rig on the desired frequency, feed enough power through the system to get at least a half-scale reading on the Varimatcher meter, and have the Transmatch set up as in (A). Tap the antenna onto the first turn of the coil L1 at the "hot" end, or end opposite the ground. Incidentally, always turn the rig off when making any adjust-



Fig. 6 — Constructional details of the Varimatcher bridge section. The braided portion of the coax is L3 and the inner portion is L4.

---

[1] Any wire that is no. 28 or smaller is practically impossible to see when strung up as an antenna. Many hams use "invisible" antennas to prevent a touchy landlord situation.

ments on the Transmatch. There may not be any dc voltages present but some very, very high rf voltages can be developed on the Transmatch coils and can cause a nasty rf burn.

With the antenna tapped on near the hot end of L1 switch S1 to read reflected power and adjust C1 and C2 for a dip or minimum reading. If you cannot get the reflected reading down to zero, or close to it, turn off the power and move the antenna tap closer to the ground end of the coil. You'll eventually find a tap point that will give a reading of zero in the reflected position versus full scale in the forward position of S1. If you find that the tap point on L1 is very close, say within 25 percent, to the ground end, you may want to try configuration B or C.

In eight of these configurations, start at the antenna end of the coil and, using another short clip lead, short out turns or portions of turns as you move the antenna tap towards the transmitter end of the circuit. In other words, the antenna is always on the end of the coil, but you may have some of the coil shorted out in order to get a match as indicated by M1.

Once you get a match for any given band, make a chart of the taps and so forth so you can return to the setup when you change bands.



Fig. 7 — The 80/40-meter coil. To use the coil on 40 meters, short out 10 turns, counting from the "A" end of the coil. Shorting clips should be copper and the shorting leads should be insulated. Coil stock is no. 14 wire, 8 turns per inch (25 mm), 2-1/2 inches (64 mm) in diameter (Air Dux 2008T, B & W 3906-1, or Polycoils 1775).
The 20-meter coil consists of 4 turns of no. 12 solid wire, 2-1/2 inches in diameter, with the turns spaced so that L1 is 1-1/2 inches (38 mm) long. L2 is one turn of no. 12, same diameter as L1, spaced 1/2 inch (13 mm) from the end of L1. The 15/10-meter L1 coil is 2 turns of no. 12 solid wire, 2-1/2 inches (64 mm) in diameter, turns spaced to cover 1-1/2 inches (38 mm). L2 is a single turn, same diameter as L1, spaced 1/2 inch (13 mm) from L1.
All coils are mounted on Millen type 40305 plugs and the socket (jack bar) is a Millen 41305. See G. R. Whitehouse ads in *QST*.

The main reason for using configurations B and C is that if the antenna is tapped near ground on L1 in configuration A, extremely high rf voltages can develop across C1 even with Novice powers. We don't recommend playing around with "arcs" from coils but it might be wise to prove to yourself just how much voltage can be developed. With the antenna tapped near the ground end of L1, take a pencil and hold it by the wood, not at the eraser end but in the center. With the key closed and the rig loaded up to about 75 watts, touch the lead end of the pencil to the stator of C1. You'll quickly see why caution is necessary. Such an arc can make a very nasty and painful burn.

If you want to try using antennas that are *very* short for the frequency, such as 10 feet (3.05 m) long on 80 meters (similar to a mobile whip) certain additional steps may be required to obtain a match with the Transmatch. When you make the coil for 80 and 40 meters you'll have some coil stock left over. With very short antennas, this can be used as a "loading" coil. Connect the antenna to one end of the coil and connect the other end to the antenna terminal on the Transmatch. Then go through the tune-up procedure. You may have to use a clip lead to short out turns on the coil but you'll find a setup that will permit matching with the Transmatch. Again, avoid coming in contact with the series loading coil because very high rf voltages can develop in such a setup.

Some beginners may not be aware of it, but a fluorescent lamp or neon bulb will light up when in an rf field, if the rf voltage is high enough. If you have a fluorescent lamp (a burned-out one is OK), the lamp can be laid along the antenna wire where it leaves the Transmatch. This makes a good output indicator, showing when power is flowing in the antenna. This material was originally presented in *QST* by Lewis G. McCoy, W1ICP.

Off-Center-Loaded Dipole Antennas

So you can't manage a buried radial system on your city lot, eh? Then why not scrap those plans for a vertical antenna and try K1TD's version of a short dipole? Here are the design tips you need.

In these times when much of our amateur population lives in urban areas, the subject of shortened antennas for the lower frequency amateur bands is a very popular one. Physically short ground-mounted vertical antennas with lumped-constant loading to make them resonant can be quite efficient radiators, if a good radial system has been installed. This has certainly been evidenced in Sevick's series of *QST* articles.[1] To many amateurs, however, the "hitch" in constructing such a system is the installation of a good radial system. It must be admitted that for the "top" amateur bands, 160 and 80/75 meters, an efficient system of buried radials requires a sizable amount of real estate, even for a physically short radiator. On the average city-size lot, 50 or 75 by 120 to 150 feet (15.24 - 22.86 m by 36.58 - 45.72 m), it's almost impossible to install a highly efficient radial system for 80/75 meters, much less for 160 meters, when structures like a house and perhaps a separate garage exist. Or to some amateurs, just the thought of burying hundreds or maybe thousands of feet of wire is enough to turn off any enthusiasm for the project.

What's the alternative? A dipole type of antenna with lunped-constant loading. At modest heights, 30 or 40 feet (9.14 or 12.19 m), such an antenna will prove to be quite satisfactory if it is physically longer than about 0.2 wavelength. Shorter lengths may also be used, at reduced efficiency. Such an antenna can be fed directly with 50-ohm coaxial line, and it can be operated with no earth ground. (Of course the chassis of the transmitter and/or receiver should be grounded adequately for protection against shock hazard.)

Nearly all of us are familiar with the concept behind the use of inductive loading. A vertical antenna which is shorter than a quarter wave (or a dipole antenna which is



Fig. 8 — A dipole antenna lengthened electrically with off-center loading coils. For a fixed dimension A, greater efficiency will be realized with greater distance B, but as B is increased, L must be larger in value to maintain resonance.

(Eq. 1):

$$L_{\mu H} = \frac{10^6}{68\pi^2 f^2} \left\{ \frac{\left[\ln \frac{24\left(\frac{234}{f} - B\right)}{D} - 1\right] \left[\left(1 - \frac{fB}{234}\right)^2 - 1\right]}{\frac{234}{f} - B} - \frac{\left[\ln \frac{\left(24\,\frac{A}{2} - B\right)}{D} - 1\right] \left[\left(\frac{\frac{fA}{2} - fB}{234}\right)^2 - 1\right]}{\frac{A}{2} - B} \right\}$$

where

$L_{\mu H}$ = inductance required for resonance
ln = natural log
f = frequency, MHz
A = overall antenna length, feet
B = distance from center to each loading coil, feet
D = diameter of radiator, inches

shorter than a half wave) will exhibit capacitive reactance at its base (or center) feed point. To cancel such capacitive reactance, a coil having the proper inductive reactance may be connected in series with the base feed point of the vertical. The same result will be obtained through the use of two such coils for a dipole, one coil connected in series with each half. It is not necessary for the inductor to be installed at the feed point, however. In fact greater radiating efficiency results through improved current distribution if the inductor is located along the radiator some distance away from the low-impedance feed point, *viz,* in the manner of a center-loaded mobile whip antenna. Fig. 8 shows this concept extended to a dipole element, with off-center loading. The inductors resonate the antenna to the operating frequency, but do little actual radiating themselves. (This is in contrast to helically wound or continuously loaded elements, where a long thin inductor is the radiator as well as the loading element.)

In the antenna represented by Fig. 8, there are many variable factors to be considered when a practical antenna for a given frequency is being constructed. Of primary consideration from an efficiency standpoint is the overall length, shown as dimension A. Another consideration for efficiency is the distance of the coils from center, dimension B. The longer the overall length (A), up to a half wave, and the farther the loading coils are placed from the center (B), the greater is the efficiency of the antenna. However, the greater is distance B (for a fixed overall antenna size), the larger the inductors must be to maintain resonance. Theoretically, if the coils were placed at the outer ends of the dipole, they should be infinite in value to maintain resonance. Capacitive loading of the ends, either through proximity of the antenna to other objects or through the addition of capacitance hats, will reduce this requirement to a more practical value.

What Inductance Values?

As a matter of personal interest, this writer has been doing experimental work for a number of years with off-center-loaded antennas. One big drawback to such experimentation was the ever-present need for a large amount of cut-and-try work to arrive at resonance whenever a new set of dimensions was to be used. Probably the number of pruned-off turns from coil stock from such experiments, if straightened out and soldered end to end, would make up several full-sized half-wave antennas for the 160-meter band. Therefore, most of the writer's work of late in this area has been in going through paperwork exercises, looking for a way whereby at least "ball-park" values of inductance needed for a particular system could be calculated.

The equation contained in the Mobile chapter of *The ARRL Antenna Book* for determining the capacitance of a vertical antenna shorter than a quarter wavelength looked promising in early computations, and, indeed, it became the basis for the calculation procedure which finally resulted. This procedure has been found to produce results much closer than mere "ball-park" values for the necessary inductance — for wire antennas "in the clear" at moderate heights, the final inductance values found by cut-and-try pruning for lowest SWR at the desired frequency have been so close to the value from calculations that a laboratory bridge was necessary to measure the difference. The results are equally good for elements using tubing. Once the needed inductance value is determined by calculations, it is generally found sufficient to obtain coil dimensions from an ARRL L/C/F Calculator (see LaPlaca[2]) or by equation. Any significant pruning which has been found necessary could always be attributed to objects in proximity to the ends of the antenna.

The complete set of calculations is expressed in the mathematical relationship as Eq. 1, presented here primarily for mathematics buffs or those having access to electronic computers. This equation yields the inductance required, in microhenrys, for single-band resonance of a shortened antenna of a particular physical size at a given frequency, for a specific position of the loading coils from the center of the antenna. To spare the reader the task of performing some rather tedious calculations, Fig. 9 has been prepared from Eq. 1. The curves of the chart have been normalized, and may be used for any frequency of resonance. The chart is based on a half-wavelength/diameter ratio of the radiator of approximately 24,000. (This corresponds to no. 14 wire on 80 meters or no. 8 wire on 160 meters.) For "thinner" conductors, the required inductance will be somewhat greater than that determined from Fig. 9, and less inductance will be required for "thicker" conductors.

The use of the chart is as follows: At the intersection of the appropriate curve from the body for dimension A and the proper value for the coil position from the horizontal scale at the bottom of the chart, read the required inductive reactance for resonance from the scale at the left. Dimensions A and B are shown in Fig. 8, and for use with the chart are expressed as percentages. Dimension A is taken as percent length of the shortened antenna with respect to the length of a resonant half-wave dipole of the same conductor material. Dimension B is taken as the percent of coil distance from the feed point to the end of the shortened antenna. For example, resonating an antenna which is 50 percent or half the size of a half-wave dipole (one-quarter wavelength overall), with loading coils positioned midway between the feed point and each end (50 percent out), would require loading coils having an inductive reactance of approximately 950 ohms at the operating frequency. If the antenna is hung "in the clear," and if the length/diameter ratio of the conductor is near 24,000, inductance values as determined from the chart will be very close to actual values required. (Eq. 1 above takes the diameter of the radiator into account, and thus may be used for any length/diameter ratio.) For practical



Fig. 9 — A chart for determining approximate inductance values for off-center-loaded dipoles. At the intersection of the appropriate curve from the body of the chart for dimension A and the proper value for the coil position from the horizontal scale at the bottom of the chart, read the required inductive reactance for resonance from the scale at left. See Fig. 8 regarding dimensions A and B.



Fig. 10 — At A, an 80-meter dipole loaded for 160-meter operation. The inductors are 37 turns of coil stock having a 3-inch (76 mm) dia and 10 turns per inch (25 mm) (B & W 3035). At B, the impedance plot of this antenna installed at a height of 50 feet (15.24 m) (solid curve), and the plot of a 160-meter half-wave dipole (broken curve).



Fig. 11 — Copper electrical service connectors, sold under one trade name of Servit, provide a simple means of installing the loading coils. The antenna wire and the ends of the coil wires should be tinned to prevent corrosion. In addition, a protective coating of acrylic spray may be used at each connection.

purposes, dimension B may be taken as that distance from the center of the feed-point insulator to the inside eye of the loading-coil insulator, and dimension A as the eye-to-eye distance inside the end insulators (which are not drawn in Fig. 8).

Proximity of surrounding objects in individual installations may require some pruning of the coils, and the exact amount of final inductance required should be determined experimentally. If the antenna is hung in inverted-V style, with the ends brought near the earth, the required inductance will almost always be somewhat less than that determined from the chart or equation. A grid-dip meter, Macromatcher (see Hall and Kaufmann[3]), or SWR indicator may be used during the final adjustment procedure.

Practical Antennas

Although one might erect an inductively loaded antenna that is cut for a single amateur band, it is possible to use the antenna itself for two, three or more bands of operation, if provision is made to lower the antenna for band changes. A simple rope halyard and pulley arrangement at one of the supports will do the trick. Fig. 10A shows a three-band antenna of this nature, for 160, 80 and 20 meters. If the insulators shown are left open, with nothing bridging them, the antenna is a simple half-wave dipole cut for 14.18 MHz. (The 48.5-foot [14.78 m] lengths act merely as support wires, and have negligible effect on operation of the antenna.) If the insulators are bridged with short lengths of antenna wire, the antenna becomes a center-fed 80-meter dipole, resonant at about 3.6 MHz. For 160-meter operation the 20-meter insulators may be bridged with loading coils to resonate the antenna at 1.8 MHz, as shown in Fig. 10A. Burndy or other manufacturers' "Servit" type of electrical connectors may be used for ease in making band changes quickly, as shown in Fig. 11.

The calculation procedure for determining loading-coil values for the antenna of Fig. 10A, using the chart of Fig. 9, goes like this. If operation is desired on 1.8 MHz, the length of a full-sized half-wave dipole is found from the relationship 468/f to be 260 feet (79.25 m). The 130-foot (39.62 m) length of Fig. 10A represents 50 percent of this size, meaning that the dimension-A curve marked "50 percent" in Fig. 9 is to be used. The position of the coils is $16.5/(16.5 + 48.5) \times 100$, or 25 percent of the distance out from center, dimension B. From the intersection of 25 (horizontal scale at bottom) and the 50 percent curve, the required inductive reactance is read from the scale at the left of Fig. 9 to be 650 ohms. The inductance, L, is $650/2\pi f$ or 57.5 microhenrys, if no. 8 wire is to be used. For smaller diameter wire, the inductance should be somewhat larger. (Calculations from Eq. 1 for no. 12 wire indicate the required inductance is 60.99 µH.)

The radiation resistance of a shortened antenna loaded to resonance is less than that of a full-sized antenna. Further, the shortened antenna is "sharper," meaning that the change in reactance versus frequency is greater. In other words, the shortened antenna acts as a tuned circuit having a higher Q than a full-sized antenna.

To check these characteristics, the line input impedances for the antenna of Fig. 10A were measured with a laboratory bridge, and the electrical line length at the measurement frequency was then taken into account to determine the impedance at the antenna feed point. The antenna was constructed of no. 12 wire and hung at a height of 50 feet (15.24 m) as a "flat-top" radiator.

The solid curve of Fig. 10B is a plot of the feed-point impedance versus frequency for this antenna. The plot on Smith Chart coordinates is more meaningful than a simple SWR-vs.-frequency curve because the magnitudes of the resistive and reactive components are shown, as well as the sign of the reactance. (Capacitive reactance is negative, plotted to the left of the vertical center line, and inductive reactance is positive, plotted to the right.) In this presentation, a 50-ohm nonreactive impedance will appear at the exact center of the chart. The SWR in 50-ohm line for a given frequency may be determined by first noting the distance from the center of the chart to the particular impedance plot on the curve, and next measuring this same distance down the vertical center line from chart center (a drawing compass is helpful for this task), and finally dividing 50 into the value read at that point on the center line. For example, the SWR at 1.8 MHz equals 120/50 or 2.4, as indicated by the segment of the 2.4 SWR circle in Fig. 10 B. It may be seen that resonance (zero reactance) occurs at approximately 1810 kHz, where the resistance is about 22 ohms. The SWR at resonance is 2.33:1, and climbs to 3:1 at 1825 kHz. At 1850 kHz, the SWR is 10:1. Without any matching provisions the antenna is relatively sharp, as mentioned earlier. If one sets the usable bandwidth as the frequency range where the SWR is 3:1 or less, it is approximately 35 kHz, or 1.9 percent of the resonant frequency. As far as efficiency is concerned, ohmic losses are low, and the antenna is a good performer on 160 meters. Because of its horizontal polarization, it has proved to be most effective at night, and stations several hundred miles away have been worked with S 9 reports received for the 50-watt signal.

For a comparison of impedances, the broken curve of Fig. 10B is a plot of measured impedances of a full-size half-wave dipole, 260 feet (79.25 m) long overall, hung in place of the shortened antenna. From this curve it may be seen that resonance occurs at 1810 kHz, where the resistance is 59 ohms. The 3:1-SWR bandwidth for the half-wave antenna is in the order of 60 kHz, or 3.3 percent of the resonant frequency. It is interesting to note on this curve that the SWR at resonance is 1.18:1, and that it is a somewhat lower value, 1.15:1, at a frequency a few kilohertz above resonance. (Measurements were made every 5 kHz across this band, but plot points are shown only for 25-kHz increments to avoid crowding of the data.) This evidence refutes the oft-heard statement that the SWR-vs.-frequency curve is *always* lowest at antenna resonance. Points to remember are that the SWR in a transmission line is completely dependent upon the characteristic-impedance value of the line in use. Using a line of different impedance may shift the position of the SWR curve along the frequency axis in a simple SWR-vs.-frequency plot. This is definitely true in this case — if the 160-meter half-wave dipole were to be fed with 75-ohm line, the lowest SWR would occur at a frequency about 5 kHz *below* antenna resonance, whereas with 50-ohm line the lowest SWR is at a frequency slightly *above* resonance. The reason this happens is that the resistive component of the impedance, which consists of the radiation resistance plus any loss resistance, is not constant with frequency, even over a rather narrow frequency range. It must be acknowledged that the differences here are very slight, however, and for practical purposes the frequency of lowest SWR is (within a few kilohertz) the resonant frequency of the antenna.



Fig. 12 — At A, a 40-meter dipole loaded for 80-meter operation. For resonance at 3.55 MHz the coils should be approximately 40 μH (27 turns of stock); 3.75 MHz, 35 μH (24 turns); 3.9 MHz, 31 μH (22 turns); and 4.0 MHz, 29 μH (21 turns). These are calculated inductance values for no. 12 antenna wire. Coil stock referenced above is 3-inch (76 mm) diameter, 10 turns per inch (25 mm) (B & W 3035). At B, the impedance plot of the 3.55-MHz version (solid curve) and of an 80-meter half-wave dipole (broken curve).

Another point concerning the SWR values bears noting. The values as determined from the plots in the manner described above are quite accurate, having been determined by measurements with laboratory equipment. In contrast, measurements with simple SWR indicators usually cannot be relied upon for anywhere near the equivalent accuracy.

For example, the author owns a commercially manufactured SWR indicator of the Monimatch type (see McCoy[4]) which, under a particular set of conditions, indicates a 2.5:1 SWR in a line where laboratory measuring equipment shows the *true SWR to be 4:1*. A significant difference! Herein lies another reason why impedance plots on Smith Chart coordinates are more meaningful than a simple SWR-vs.-frequency curve — greater accuracy may generally be expected.

A Half-Size 80-Meter Antenna

Fig. 12A shows the 3-band concept described earlier as it can be applied to 80, 40 and 20 meters. Its overall length is 66 feet (20.12 m), not a difficult length to use on a small lot. This antenna was constructed for 80-meter operation with a design-center frequency of 3.55 MHz, using no. 12 antenna wire and 40-μH loading coils — 27 turns of stock having a diameter of 3 inches (76 mm) and a pitch of 10 turns per inch (25 mm) (tpi). Feed-point impedances versus 80-meter frequency for the antenna, hung at a height of 50 feet (15.24 m), are shown by the solid curve at B of Fig. 12. Actual resonance occurred at 3.54 MHz, where the resistance was about 26 ohms. The bandwidth within which the SWR is 3:1 is 60 kHz, or 1.69 percent of the resonant frequency.

Also shown in Fig. 12B, by the broken curve, are the feed-point impedances of a half-wave dipole, 132 feet (40.23 m) overall length, hung in place of the shortened antenna. Resonance occurs at 3.54 MHz, where the resistance is 43.5 ohms and the SWR is 1.15:1. The broader nature of the half-wave antenna is exhibited by the "tighter" curve which swings closer to the 50-ohm center point of the chart than the shorter, loaded antenna. The SWR at 3.5 MHz is 1.6:1, and remains below 3:1 to 3.67 MHz.

Capacitive and Inductive Loading

One would assume that a combination of capacitive and inductive loading might provide a different feed-point impedance than would inductive loading alone, because of different current distributions in the radiators. To check out this assumption, the antenna of Fig. 12A was used as a "test bed" for comparative measurements. Capacitance hats were attached at different points along the 17-foot (5.18 m) lengths of wire outside the coils, and the coils were pruned to reresonate the antenna at about the same frequency as before. The impedance measuremnts were then repeated.

Dangling End Sections

First, "hats" consisting of 18 inches (457 mm) of no. 12 wire were affixed to the antenna ends and permitted to dangle. This lowered the resonant frequency to 3435 kHz. By calculations, this was approximately the same effect as that of extending the 17-foot portions of the antenna by the same amount as the dangling lengths, so it

Table 4

Characteristics of Various Loading Techniques, 66-Foot, 80-Meter Dipole

Loading	*Approx. feed-point resistance, resonance*	*SWR at resonance*	*3:1-SWR bandwidth, % of resonant freq.*
40-μH coils only	26 ohms	1.92:1	1.69
36.5-μH coils, 18" dangling ends	26	1.90:1	1.79
36" hats outside 32.5-μH coils	23	2.15:1	1.68
30-μH coils, 36" hats at ends	25	1.98:1	2.05
None (λ/2 dipole)	43.5	1.15	Greater than 3.6

Coil positions for each loaded antenna were 16 feet from antenna center. All antennas were constructed of no. 12 wire and installed at a height of 50 feet.

Feet X 0.3048 = m.

Inches X 25.4 = mm.



Fig. 13 — Curve A is the impedance plot of the antenna of Fig. 12A with 18-inch (457 mm) dangling end sections added and the coil trimmed to restore resonance near the original frequency. Curve B is a plot of the same antenna with X-shaped capacitance hats added at a point just outside the loading coils (dangling sections removed and coils trimmed to reestablish resonance.).



Fig. 14 — Impedance plot of a 66-foot (20.12 m) dipole using a combination of off-center inductive loading and capacitive end loading. Of all the shortened configurations tried, this arrangement offered the greatest bandwidth.

would seem to make little difference whether short sections of extra length are added inside the supporting insulators or are at the ends, suspended at right angles to the main antenna wire.

The inductors were reduced from 40 to 36.5 μH (25-turn coils replaced the original 27-turn coils), and resonance occurred at about 3575 kHz. At this frequency the resistance was 26 ohms and the SWR 1.90:1. The 3:1-SWR bandwidth, 64 kHz, is 1.79 percent of the frequency of resonance. The impedance plot for this arrangement is shown as Curve A in Fig. 13. The resistance at resonance for this antenna is identical to that with the coils alone, and the bandwidth is only 4 kHz greater, 64 kHz vs. 60. From these results, one would conclude that the main advantage offered by the "danglers" is a small saving of space over a flat-top antenna.

Capacitance Hats near Loading Coils

Next the dangling end sections were removed and a pair of capacitance hats was formed, each from two 36-inch (0.91 m) lengths of no. 12 solid wire. The two wires for a single hat were attached at their centers to the antenna wire at a point just outside one of the loading coils. The hat wires were then bent radially to form an X at right angles to the antenna wire, like four spokes of a wheel with the main antenna wire at the hub. The diameter of the X-shaped hat was thus 36 inches. The second hat was placed in a like manner just outside the second coil. Burndy connectors were used to affix the hat wires. The resonant frequency of this configuration with the original 40-μH loading coils was found to be 3290 kHz. The effect of adding the hats was about the same as that of extending the 17-foot (5.18 m) lengths to 19 feet (5.79 m).

When the inductors were replaced with 23-turn coils (32.5 μH), the antenna resonated at about 3.575 MHz, the resistance being 23 ohms. The SWR at resonance is 2.15:1, and the 3:1-SWR bandwidth for this configuration is 60 kHz, 1.68 percent of the resonant frequency. The impedance of this arrangement versus frequency is shown by Curve B of Fig. 13.

It is surprising to note that, by the standards of most amateurs, the characteristics of this antenna are not as good as those of the same length antenna with loading coils alone. The SWR at resonance for the antenna with combination capacitive and inductive loading is higher (2.15 vs. 1.92), and the 3:1-SWR bandwidths are the same, 60 kHz. Perhaps a significant factor here, though, is that the diameter of the capacitance hats used for these measurements was small, only 0.011 wavelength. Supporting much larger hats presents mechanical problems with wire antennas, however, as even these were a bit flimsy and would require reshaping after gusty weather.

Capacitance Hats at Antenna Ends

Finally, the X-shaped capacitance hats were moved to the outside ends of the antenna, just inside the end insulators. With the original 40-μH coils, resonance appeared at 3215 kHz. From calculations, it was as if the 17-foot (5.18 m) end sections were actually 21 feet (6.40 m) long. With 30-μH coils (22 turns) in place, the resonant frequency was 3560 kHz. At this frequency the resistance was 25 ohms and the SWR 1.98:1. The 3:1-SWR bandwidth is 73 kHz, or 2.05 percent of the resonant frequency. The impedance plot of this antenna is given in Fig. 14.

It is interesting to note that the position and shape of the plot for this antenna on Smith Chart coordinates is nearly identical to that for the same length antenna with loading coils only, the solid curve of Fig. 12B. For this antenna, however, the plot points for 25-kHz frequency increments appear closer together, which accounts for the increased bandwidth.

Conclusions

The measured characteristics of these various configurations of loading for the 80-meter antennas are tabulated in Table 4. Remember that the overall "flat-top" length of each antenna arrangement is 66 feet (20.12 m), and that the loading coils are always positioned 16 feet (4.88 m) each side of the center of the antenna, being pruned for resonance at approximately 3550 kHz. For comparison, information for a half-wave dipole is also included.

Of the various arrangements, capacitive end loading decidedly provides the greatest bandwidth, excepting the full-size half-wave antenna, of course. Although there are slight differences in the resistance value at resonance, all are of the same order of magnitude. These values, as well as those for the 160-meter antenna discussed earlier, tend to confirm a *broad* rule of thumb that the writer has formulated for this type of antenna: The feed-point impedance value at resonance is roughly proportional to the length of the antenna. That is, a loaded antenna which is half the size of a half-wave dipole will have approximately half the radiation resistance of the full-sized antenna.

Eq. 1 given earlier or the chart of Fig. 9 allows one to calculate loading-coil values for antennas with loading coils only. Additional capacitive loading is not taken into account. Calculating the effects of various capacitive loading arrangements appears to be difficult, and work remains to be done in this area.

Multiband Antennas with Loading Coils

All of the foregoing material has been devoted to the loading of an antenna for resonance at a single frequency. Resonated as described, the antenna is electrically a half wave in length. It will, however, operate well on higher frequencies — frequencies at which it is an odd multiple of half waves in *electrical* length . . . three half waves, five half waves, etc. Because of the lumped loading of the shortened antenna, these higher frequencies will likely not be closely related to odd-order harmonics of the fundamental frequency, as the case would be for a nonloaded radiator. (For example, it is a well-known fact that a 7-MHz half-wave dipole operates well on its third harmonic, 21 MHz.)

A loaded dipole will become an electrical 3/2-λ antenna at some frequency below that which is three times the fundamental resonant frequency. Depending upon the overall antenna length, coil value, and coil position, it is possible for an 80-meter loaded dipole to become a 3/2-λ performer on 40 meters. With such an arrangement, one would have a dual-band antenna without requiring the use of traps. The idea can be expanded upon to arrive at a loaded antenna without traps which will operate on more than two bands. This scheme offers considerable constructional simplification as compared with trap arrangements.

The multiband loading-coil concept has been recognized for better than half a century, but little use of the technique has been made by amateurs. Some years ago a very good article on the subject was published by William Lattin, W4JRW.[5] That article is recommended reading for anyone interested in more details on the concept. Supplemental information has been published by Buchanan.[6] Attempts by this writer to calculate antenna sizes and coil values for dual-band antennas have met with some success. From calculations and experiments to date, it appears that with only two loading coils (one each side of center), the antenna must always be greater than a half wave in physical length for the higher of the two frequency bands. In other words any 80/40 meter arrangement, for example, apparently would need to be longer than 66 feet (20.12 m) from tip to tip. However, much work also remains to be done in this area. This material was originally presented in *QST* by Jerry Hall, K1TD.

References

[1] Sevick, "The Ground-Image Vertical Antenna," *QST*, July 1971. (See chapter 1.) Also, "The W2FMI Ground-Mounted Short Vertical," *QST*, March 1973. (See chapter 1.) "A High Performance 20-, 40- and 80-Meter Vertical System," *QST*, December 1973. (See chapter 1.) "The Constant-Impedance Trap Vertical," *QST*, March 1974, p. 29.

[2] LaPlaca, "Using the ARRL L/C/F Calculator," *QST*, December 1973, p. 26.

[3] Hall and Kaufmann, "The Macromatcher, An Rf Impedance Bridge for Coax Lines," *QST*, January 1972, p. 14. Information also contained in *The Radio Amateur's Handbook* and *The ARRL Antenna Book*.

[4] McCoy, "Monimatch, Mark II," *QST*, February 1957, p. 38. Also, "An Etched-Circuit Monimatch For Checking Your Antenna System," *QST*, October 1969. (See chapter 4.)

[5] Lattin, "Multiband Antennas Using Loading Coils," *QST*, April 1961, p. 43.

[6] Buchanan, "An Inexpensive 40- and 80-Meter Antenna, Hints and Kinks," *QST*, September 1962, p. 62.

Efficient Short Radiators

If you're cramped for space to put up a beam antenna, you'll want to investigate these ideas as one way to shrink 'er down to usable size.

Shortened antennas have been popular with amateurs for either esthetic, space limitation or economic reasons. And most are inefficient radiators with narrow bandwidth. This section will first define some limitations and problems of conventinal short antenna designs. A design for a half-size 2-element Yagi, the performance of which is competitive with its full-size equivalent, will follow.

It has been proved that no appreciable difference exists between the directive patterns of "short" and full half-wave horizontal dipoles. Since the gain of a half-wave dipole over an isotropic radiator is determined by the dipole directive pattern and since the length of the dipole (up to λ/2) has negligible effect on its directive pattern, the length of the dipole (up to λ/2) has a negligible effect on its gain. An assumption is made that the efficiencies of both the short and half-wave dipoles are equal. The efficiency of an antenna can be expressed as

$$\text{Eff} = \frac{R_r}{R_r + R_{loss}} \qquad \text{Eq. 1}$$

where R_r = radiation resistance

R_{loss} = loss resistance of conductors, coils, etc.

The radiation resistance (R_r) of a horizontal dipole is determined by its length and height above ground. In free space, the R_r of a half-wave dipole is 73 ohms. As the length of the dipole is reduced, the R_r decreases as the square of the length. Thus, for a half-size dipole (as compared with λ/2), the R_r decreases to a value one-fourth that of the λ/2 dipole or approximately 13 ohms.

The efficiency of a half-wave dipole is very high, being on the order of 95 percent. The R_r is large and R_{loss} small by comparison. If we reduce the overall length by a factor of two, the R_r decreases by a factor of four. Input impedance at the center of the dipole is comprised of a low resistance and large capacitive reactance, so inductive loading is required in order to resonate the dipole. The inductive reactance needed to center-load the antenna will be approximately 1 kΩ (depending on conductor size used for the antenna). Assuming a coil Q of 200 and computing efficiency using Eq 1: This means that 28 percent of the transmitting power applied to the antenna is dissipated in the loading coil. The author has neglected any additional losses in the matching network which would result if the above antenna were driven by a 50-ohm source.

Let's suppose we decide to build a 2-element Yagi using shortened center-loaded elements. The driven element by itself has an R_r of 13 ohms. Adding a close-



Fig. 15 — Electrical equivalent for the center-loaded dipole discussed in the text. Efficiency is 72 percent, as determined by Eq. 1.



The 100-MHz "model" used by the author for testing shortened elements in a Yagi antenna design.



Fig. 16 — Electrical equivalent of a loaded 2-element antenna. The efficiency is 47 percent.

spaced parasitic element reduces the radiation resistance by approximately a factor of three. Thus, the driven element has an impedance composed of approximately 4.5 ohms resistive and 1 kΩ reactive. Loading both the driven and parasitic elements with the same inductors that were used for the dipole and computing efficiency

$$\text{Eff} = \frac{4.5}{4.5 + 5} = 47 \text{ percent}$$

This efficiency equates to slightly more than a 3-dB power loss in the driven element. The writer has neglected the sizable loss in the matching network since it must transform the 50-ohm source to the 9.5-ohm impedance of the antenna at resonance. In addition, the loading coil of the parasitic element will contribute approximately 1 dB of loss.

Taking into account the losses on loading coils of both the driven and parasitic elements and the loss on the driven element to feed-line matching network, we can easily account for a 5-dB power loss. Such a power loss would nullify the gain of a properly tuned Yagi, making it little better than a full-size dipole.

It should be obvious from the previous examples that the poor performance of short dipoles, and particularly Yagis, is a direct result of losses in loading inductors. If we can reduce these losses while raising the radiation resistance, the increase in efficiency will (might?) make the short dipole or Yagi competitive with its full-size counterpart.

Test Antenna

The helically wound whip antenna has always been appealing because the R_r tends to be higher than that of the base-loaded whip. This is because it is continuously loaded. In fact, using end-loading (large capacitance hats), the current distribution will be much more constant, yielding an R_r of up to four times that of a base-loaded whip. The author decided to use the helical design for a short test dipole and investigate the properties of this antenna versus that of a full-size dipole.

Conventional design for a helically wound antenna uses a form (wood, bamboo, fiberglass) wound with approximately λ/2 of no. 14 wire per λ/4 element. The writer felt that the resistive R_{loss} of this large amount of wire would be as great as that of the loading coils in the center-loaded dipole, making the helical design ineffective. As it is desirable to reduce conductor resistance, the surface area of the conductor must be substantially increased. Tubing is not mechanically suitable, and because skin depth is only on the order of 0.001 inch (0.03 mm),[1] the use of tubing is not required. Some 1/2-inch (13 mm) wide copper tape[2] was on hand and a study of its skin resistance revealed a loss per unit length of 12 percent less than that of the no. 14 wire.

A helically wound dipole was constructed (using the 1/2-inch [13 mm] wide tape) for use at 100 MHz. This frequency was chosen so that field-strength measurements could be performed using a local fm broadcast station as the signal source. A 28-inch (711 mm) length of 3/4-inch (19 mm) CPVC tubing (plastic water pipe) was wound with 38 equally spaced turns of the 1/2-inch (13 mm) wide tape. Using a grid-dip meter, resonance was measured at 104 MHz. Next, two 5-1/2-inch (140 mm) diameter six-spoke capacitance hats were attached to the ends. Resonance was again measured and found to be 84 MHz. A C-match[3] was constructed to transform the low impedance of the short dipole to 50 ohms. The C-match requires that the element be made to look inductive by lowering its resonant frequency. A variable capacitor is then shunted across the feed point and adjusted for resonance. This L/C ratio determines the impedance transformation. A 100-pF variable capacitor was shunted across the feed point of the test dipole and a 50-ohm coaxial cable was attached. Since the dipole is a balanced antenna, feed-line decoupling was necessary. The author used a quarter-wave sleeve (bazooka).



Fig. 17 — Curves depicting gain and FBR (front-to-back ratio) vs. frequency when the Yagi antenna is tuned for operation at 100 MHz.



Fig. 18 — VSWR vs. frequency when the Yagi antenna is tuned for operation at 100 MHz.

Antenna Tuning

Rf power was applied to the test antenna through an SWR meter (measurements were taken in a screen room). Turns were removed, one at a time, and the shunt capacitor adjusted until a 1:1 match occurred. The capacitance hats were always installed at the tips of the element. When adjusted for a 1:1 match, the dipole consisted of 32 turns of copper tape, center fed, with 40 pF shunting the feed point and an overall element length of 21 inches (533 mm) which is 37 percent of the length of a full-size dipole. Tuning was very simple and took but 15 minutes to complete.

Measurements

The feed-point impedance was measured (with C-match disconnected) to be 20 ohms. The skin depth resistance was computed to be 0.24 ohm. Computing efficiency

$$\text{Eff} = \frac{20}{20 + 0.24} = 98 \text{ percent}$$

which is essentially the same as a full-size dipole. Bandwidth between 2:1 SWR points was measured to be greater than 6 percent of the operating frequency. Large capacity hats (for 100 MHz) and wide tape play an equally important role in reducing the Q of the antenna sufficiently to obtain a wide bandwidth. Next, a low-level signal generator and dipole were set up 5 wavelengths away from the test antenna. Using an Empire NF-105 noise and field-strength meter, a comparison was made on field strength between the test antenna and a full-size dipole. Results indicated no apparent measurable difference between the short helically wound dipole and a full-size dipole. Field-strength measurements were then taken on the signal from a local fm broadcast station. Again, there was no apparent difference; not bad for an antenna that is less than half size. The next question to be answered was whether gain could be secured by the addition of a parasitic element.

A boom and a parasitic element were added to the shortened test dipole. Although a director might provide better gain and front-to-back ratio (FBR), the decrease in radiation resistance, to a very low value (dipole by itself equals 20 ohms) because of the close spacing, was thought to decrease efficiency and bandwidth. A parasitic reflector was constructed, similar to that of the driven element. The element was split in the center and a 100-pF capacitor installed for tuning purposes. Element spacing was adjusted to 0.15 λ. With the capacitor fully meshed, the six-spoke capacitance hats were physically positioned on the element (both equidistant from element center) so that the reflector resonated at 93 MHz. Nominal reflector tuning calls for reflector resonance approximately 5-percent lower in frequency than the driven element, or 95 MHz. With the above configuration, the author was able to adjust reflector resonance, using the variable capacitor, anywhere in the range of 93 to 96.5 MHz or 3.5 to 7 percent lower in frequency than the driven element.

Using the same field-strength measurement set up as with the dipole, the reflector was aimed at the source signal and adjusted (using the variable capacitor at element center) for minimum pickup. The driven element was then readjusted for a 1:1 SWR and the process repeated until minimum rear pickup and a 1:1 SWR occurred simultaneously. Gain and FBR measurements were made at the design frequency and at points two percent of the design frequency on either side. The results are described in Fig. 17. The bandwidth measurements are given in Fig. 18.

As can be seen from the curves in Fig. 17, a gain of 4 dBd, and a 15-dB FBR can be secured quite easily with a physically short Yagi. As with other Yagis, the gain is relatively constant over a wide frequency range. However, the FBR drops quite fast especially when trying to use the antenna below its design frequency. From curves given in Fig. 18, the bandwidth between the 2:1 VSWR points is shown to be about 3.7 percent. Translated to 20 meters this bandwidth would be 500 kHz, equal to or greater than the average 3-band trap Yagi. If indeed the design were scaled to 14 MHz, the antenna would have element lengths of slightly over 12 feet (3.66 m) and a boom length of 10 feet, 6 inches (3.20 m).

Adapting Design to Ham Bands

Since it has been shown that a physically short Yagi can provide significant gain and FBR, a few design pointers are in order. First, make the element length no shorter than physically necessary for your particular situation. Bandwidth and efficiency will improve with greater lengths. Second, the use of large capacitance hats is recommended, as this reduces the helical conductor length and thus R_{loss}. Third, use large forms of good dielectric quality (fiberglass). The larger the form diameter, the greater the length reduction for a given number of turns. Also, with large diameter forms, 1.5 inch (38 mm), the width of the conductor can be increased, thus reducing R_{loss}. Fourth, regardless of the matching network used, construction of capacitance hats, etc., *solder all* joints and *seal* with silicone rubber. *Do not rely on pressure joints.* Fifth, to secure a reasonable FBR with any Yagi using a split driven element and fed with coaxial cable, some form of balun transformer is required to keep currents from flowing on the outside of the coax braid. Sixth, the use of a grid-dip meter is the only practical method to secure resonance with a fixed physical length. Construction will require some cut and try. Proximity to surrounding objects will affect resonance, and should be avoided when tuning the array.

No doubt the author has left out items, which may prove to be a problem for the reader. This article was intended to be more thought provoking than constructional, although there should be enough information here to build your own antenna with a reasonable amount of experimental effort. My current plans call for construction of a 2-element 10-meter Yagi (for reception of OSCAR signals) with 6-foot (1.83 m) elements and a 5-foot (1.52 m) boom. The author wishes to thank Mike Povlich, WB9HGS and Russ Mills for their assistance with measurements. This material was originally presented in *QST* by Ronald J. Gorski, N9AU.

References

[1] Kuecken, *Antennas and Transmission Lines*, Howard W. Sams and Company, Indianapolis, IN, 1st Edition (1969), p. 274.

[2] Copper tape available from Minnesota Mining and Mfg. Check Yellow Pages for the address of a local distributor.

[3] Orr, *Beam Antenna Handbook*, Radio Publications Inc., Wilton, CT, 3rd Edition, p. 63.

Simple Arrays of Vertical Antenna Elements

Work DX with a vengeance! Simple arrays of vertical elements will provide good low-angle radiation. DXCC may be closer than you think if you can manage a system like this one!

Because of the excellent low-angle radiation properties of vertical antenna elements and because of the benefits to be gained by horizontal-plane directivity, it is interesting to attempt to determine "optimum" arrangments of elements to produce "beam" antenna arrays. Because of the enormous variety of configurations possible, and the great difficulty of either experimental modeling or calculating exact theoretical performance, it has not been practical in the past to arrive at valid conclusions. However, it is now quite easy to simulate such antenna arrays by computer programs, and these can produce relatively quick and precise answers to a very large number of postulated configurations. After a number of computer trial runs, "optimum" configurations can be found quite readily. Such a computer program for quarter-wave elements has been written and supplied by H. Hurwitz, WA2VBW. Using a modification of this program, the author has investigated a

Table 5

Case	Element	Current	Phase	X	Y	Beam Direction	Beam Gain	Back Radiation	Minor Lobes
1	1	1	0	0	0	0°	3 dB	-3 dB	-α
	2	1	-90	0.25	0				
2	1	1	0	0	0	0°	4.1 dB	5.7 dB	-11.5
	2	1	-120	0.25	0				
3	1	1	0	0	0	90°	1.1 dB	0 dB	0 dB
	2	1	0	0.25	0				

Table 6

I1	I2	$\phi 1$	$\phi 2$	Beam Gain	Back Radiation	Minor Lobes
1	0.8	0	-120	4.0 dB	-5.5 dB	-10.8 dB
1	1	0	-120	4.1	-5.7	-11.5
1	1.2	0	-120	4.1	-5.6	-12.5
1	1	0	-100	3.4	-3.8	-11.1
1	1	0	-120	4.1	-5.7	-11.5
1	1	0	-140	4.6	-6.6	-6.6

Table 7

Element	Current	Phase	X	Y	Beam Direction	Beam Gain	Back Radiation	Minor Lobes
1	1	0	0	0	0°	5.6 dB	-8.7 dB	-8.7 dB
2	1	-120	0.25	0				
3	1	-240	0.5	0				

Table 8

Element	Current	Phase	X	Y	Beam Direction	Beam Gain	Back Radiation	Minor Lobes
1	1	0	0	0	90°	2.7 dB	0 dB	0 dB
2	1	0	0.25	0				
3	1	0	0.5	0				

Table 9

Element	Current	Phase	X	Y	Beam Direction	Beam Gain	Back Radiation	Minor Lobes
1	0.5	0	0	0.145	0°	4.35 dB	-6.1 dB	-15. dB
2	1	-110	0.25	0				
3	0.5	0	0	0.145				



Fig. 19

large number of simple array configurations, which are potentially quite useful at the lower amateur frequencies, with the salient results given here. It is hoped that these will prove interesting to those considering construction of such arrays.

Technique for Optimizing Arrays

We must first try to define the problem and the parameters leading to an optimum design. The horizontal-plane pattern of an array of (vertical) elements depends only on the magnitudes of the individual element currents and their phases, and not on the way the currents are produced (e.g., driven or parasitic). The computer program allows one to specify the locations (x,y coordinates) of any number, n, of quarter-wave elements; also one must specify the magnitude of current and its phase in each element (usually normalized to unity current and zero phase for a given fiducial element). With these data inputs the radiation pattern is calculated and plotted out, giving the relative power gain in each azimuth angle interval, say, 5 or 10 degrees. The power gain is normalized to that power which would have been radiated at the same azimuth by a *single* vertical element using the same input electrical drive power. By using trial values of the current in all elements, in both amplitude and phase, one soon develops a feel for the behavior of the system, and can usually arrive at a "best" value for all the currents and phases. One can then try different geometrical separations of the elements and in this way arrive at the "best" spacing. Usually this best configuration is a compromise between power gain and good pattern control, e.g., front-to-back ratio, or more generally, main lobe to minor lobe (side or back) ratio.

In addition to the optimization described above it must be noted that if the array is to be used primarily to produce a "beam" in a given general direction with little emphasis on other directions, one usually finds a linear array of elements best (equivalent to an end-fire Yagi array). However, if the array is to be used for all directions, a more (circularly) symmetrical array should be considered. These points will become clear in the discussion of results.

Two-Element Array

In the case of two elements there is only one possible configuration. Consider one element at the origin of the x,y plane (coordinates 0,0) and the other element along the x axis (coordinate x,0). The parameters available are x, which we specify in units of wavelength, λ, the rf currents I1 and I2 in each element (we shall normalize one of the currents, e.g., I1, to unity) and the phases, $\phi 1$ and $\phi 2$, of the currents (we shall generally normalize the phase of the current in element 1 as zero and specify the relative phase of the current in element 2 in electrical degrees, either positive for leading currents or negative for lagging currents). It soon becomes apparent that the region of main interest is where the spacing x is in the neighborhood of 0.25, i.e. λ/4, and there the currents are nearly equal in magnitude. The reasons are that, for spacings of 0.5 or greater, other strong lobes appear in the pattern, and for grossly unequal currents relatively poor

Table 10

Element Spacing	*Optimum* $\phi 2$	*Beam Gain*	*Back Radiation*	*Minor Lobes*
0.2	-130°	4.65 dB	-6.5 dB	-18 dB
0.25	-120°	4.6	-6.5	-16
0.3	-110°	4.4	-6.2	-14
0.35	-110°	4.2	-5.8	-12

Table 11

Element	*Current*	*Phase*	*X*	*Y*	*Beam Direction*	*Beam Gain*	*Back Radiation*	*Minor Lobes*
1	1	0	0	0	0°	7.4 dB	-9.9 dB	-9.9 dB
2	1	-120	0.25	0				
3	1	-240	0.5	0				
4	1	0	0.75	0				

Table 12

Element	*Current*	*Phase*	*X*	*Y*	*Beam Direction*	*Beam Gain*	*Back Radiation*	*Minor Lobes*
1	1	0	0	0	90°	4.2 dB	0 dB	0 dB
2	1	0	0.25	0				
3	1	0	0.5	0				
4	1	0	0.75	0				

Table 13

Element	*Current*	*Phase*	*X*	*Y*	*Beam Direction*	*Beam Gain*	*Back Radiation*	*Minor Lobes*
1	1	0	0	0	45°	6.4 dB	-18 dB	-18 dB
2	1	-110	0.25	0				
3	1	-220	0.25	0.25				
4	1	-110	0	0.25				

Table 14

Element	*Current*	*Phase*	*X*	*Y*	*Beam Direction*	*Beam Gain*	*Back Radiation*	*Minor Lobes*
1	1	0	0	0	0°	5.1 dB	-11.5 dB	-11.5 dB
2	1	-120	0.25	0				
3	1	-120	0.25	0.25				
4	1	0	0	0.25				

Table 15

Square side Length (inλ*)*	ϕA *opt.*	ϕB *opt.*	*Beam Gain*	*Back Radiation*	*Minor Lobes*
0.167	-130	-260	6.6 dB	-22 dB	-22 dB
0.25	-110	-220	6.4	-18	-18
0.333	-80	-160	5.6	-18	-18



Fig. 20

peak gain and pattern discrimination result. Although the spacing x is not especially critical in the neighborhood of 0.25 (one can essentially compensate by adjustment of phase angle) we shall now examine the case where x = 0.25, and where I1 = I2 = 1. Best overall pattern discrimination (minimum back lobe) for the endfire case occurs where $\phi 1$ = 0, and $\phi 2$ = 90 degrees, and the power-gain pattern is shown in Fig. 19A.

Peak gain is 2 (or 3 dB) and occurs along the x-axis direction. Fig. 19A shows the power pattern of the array, i.e., it shows quantitatively where the radiated power goes. However, if one is looking at what an S meter would indicate, one can present exactly the same information on a vertical *logarithmic* scale as shown in Fig. 19B.

The vertical scale is shown in dB relative to the value for a single vertical radiator. This type of display is useful in judging excellence of pattern with respect to minor lobes. For all future cases discussed here, both displays will be shown.

It is possible to increase the gain of this array at the expense of some back lobe by increasing the phase lag in element 2, e.g., if $\phi 2$ = −120 degrees the peak gain, again along the x axis, is 2.59 (or 4.1 dB) and the entire pattern is shown again in Figs. 20A and B.

Note that the back lobe now shows a gain of 0.186, which is −11.5 dB relative to the forward lobe.

These two elements can be used to form either a beam along the +x axis as shown, or reversed along the −x axis (by reversing the phase $\phi 2$, i.e., making it +120 instead of −120 degrees) or if the two elements are driven in the same phase, i.e., $\phi 1 = \phi 2 = 0$, one produces a bilateral broadside beam as shown in Fig. 21.

Here the peak gain is 1.1 dB, but there is a "back" lobe of equal magnitude to the front lobe. Note that all patterns will be symmetrical around the x axis, or more generally around the line of any set of linearly-positioned elements. This example has illustrated some of the aspects of all of the results to be presented; namely, that:

a) The best element spacing will be found to be in the neighborhood of 0.25 wavelength.
b) Current ratios and phases can be adjusted to produce either a best *pattern discrimination* (minor lobe rejection) or best *main lobe gain.* It is generally not possible to get both at the same time, and a compromise must be made.

It may be useful to tabulate the salient results of each "best" case by noting the coordinates of the elements in the x,y plane, the individual drive currents, the individual phases, main beam heading in the x,y plane, main beam gain, and the



Fig. 21



Fig. 22



Fig. 23

largest pattern gain (such as given by either the side of the main lobe or by minor lobes) observed anywhere in the entire 180-degree sector centered just opposite in direction to the main lobe. We shall designate this quantity as "back radiation" and express it in dB relative to the main lobe gain. We shall also tabulate the largest minor lobe in this sector and label it "minor lobe," again expressed in dB relative to the main lobe. Thus for the cases just described, Table 5 is presented.

The sensitivity of these results to variations of currents and phases is not high. For example, one can summarize case 2 above with somewhat altered I2, or $\phi 2$, as shown in Table 6.

The author feels that end-fire case 2, where $\phi 2 = -120$ degrees, probably represents the "best" design with a good pattern and gain. Other more complicated cases presented below are optimized in this same way and only the "best" configuration will be shown with actual results.

Three-Element Arrays

For three elements, two different geometries suggest themselves: the linear array, best for a single preferred directional line, and an equilateral triangle configuration, the closest approach to circular symmetry. The latter, as we shall see, could be switched to give "beams" in any one of six angular positions (every 60 degrees). Let us consider first the linear array.

Linear Array — As in the 2-element linear array just discussed, the optimum arrangement seems to center around an element spacing of about 0.25 wavelength with approximately equal current drives. The optimum end-fire case is shown in Table 7; the broadside case is shown in Table 8.

The patterns for these cases are shown in Figs. 22 and 23.

Remember that for the end-fire case, which one can think of as a 3-element Yagi on its side, the rather large side lobe results because the pattern lies in a plane perpendicular to the elements. Side radiation is hard to avoid, as one cannot take advantage of the nulls off of the ends of excited elements.

Equilateral Triangular Array — For this case, the optimum situation appears to be as shown in Table 9. The behavior is very similar to the case of two elements in end-fire. See Table 5 (we have just split one of the two elements and have moved the separate pieces to the triangle corners). The pattern is shown in Fig. 24.

Reversing the phases will reverse the beam direction, and by rotating the drive currents (and phases) around the triangle, one can produce six beam directions (every 60 degrees). This is an attractive feature, but it does not come free; the maximum gain of the system is somewhat less than one obtains with the three linearly-disposed elements (which are chiefly useful in a direction along the line of the array).

The exact size of the triangular array is not critical — one must simply choose the best phase angle for the particular geometry. The "best" phase angles, $\phi 2 (\phi 1 = \phi 3 = 0)$, as determined by computer runs, for different spacings (triangle side lengths expressed in terms of λ) are shown in Table 10.

Four-Element Arrays

With four elements, there are at least three configurations which are interesting to investigate. As before, the linear array with a preferred beam direction is one type, but there are two configurations which possess a measure of circular symmetry. One of these is described by three antenna elements at the corners of an equilateral triangle with the fourth element at the geometric center of the triangle. This one we shall designate as a center-filled triangle. The other type is a square array.



Fig. 24

(A)

(B)



Fig. 25

(A)

(B)



Fig. 26

(A)

(B)



Fig. 27

(A)

(B)

Let us take these three types in order.

Four-Element Linear Array — For this case the optimum end-fire solution appears to be as shown in Table 11. The gain and major lobe shape of this configuration seems to be excellent. The broadside case is shown in Table 12. Patterns for this case are shown in Figs. 25A, B, and 26A, B.

Note that for this array there is poor coverage in some azimuthal directions (e.g., ±45 degrees) if only the two tabulated phase arrangements are used.

Center-Filled Triangle — A large number of situations were examined for this configuration, but unfortunately no combinations of spacing, currents or phases were found that looked very good. The best pattern was not particularly better than that of the three-element triangle alone, and was substantially inferior to that of the 4-element square to be discussed next.

Four-Element Square Array — For this case the best situation appears to be as shown in Table 13. Note that this arrangement fires diagonally and produces a respectable gain and excellent pattern. The "broadside" arrangement for the same square is shown in Table 14. The computed patterns are shown in Figs. 27 and 28.

The diagonal-fire pattern is exceptional, providing extremely low back radiation and minor lobes. The broadside pattern is not nearly as good, somewhat superior but reminiscent of the end-fire pattern obtainable with just 2 elements (see Fig. 20). In fact, the power-gain coverage at all angles (including the broadside angle) just using the switched four diagonal beams is large enough that it probably is not worthwhile using the broadside arrangement at all even to "fill" between diagonal beams.

This square array is superior to the center-filled triangle, and to all other simpler configurations (circular) in both gain and pattern discrimination. It is sufficiently good that one might ask what particular properties of the square have led to the nearly ideal performance. The



Fig. 28

author believes that there are two parameters which are noteworthy: first, the gain is respectable in diagonal fire because one can view the square along its diagonal as a three-element linear array in which the center element is split, each half being displaced to the other corners of the square. Thus the array behaves something like a 3-element (Yagi-like) linear array which is known to have a good gain. Secondly, the lobes are much smaller than the linear array due to the tendency for the phase cancellation of waves produced by the spatially-separated corner elements.

Again, as in previous examples, the actual dimensions of the square are not very critical, as long as one adjusts the phase (delay), ϕA in elements 2 and 4 and the larger phase delay, ϕB, in element 3 to the "best" value. Examples of such "best" phase values for different size squares are shown in the Table 15.

It turns out that the calculated gain figures for the smaller arrays are actually slightly larger than the gain for the larger squares, but as a practical matter this fact is probably offset by the larger (reactive) currents required for radiation. The larger currents are necessary because of the mutual coupling and phase relations between elements and the required phase relationships; in practice with the inefficiencies usually caused by ground currents when using vertical antennas, the gain differences for the various squares are probably inconsequential. The patterns for all cases are quite good, but the best pattern is obtained for the $\lambda/4$ square. Incidentally, the 0.167λ and 0.33λ square allows the possibility that a single square can be used for two amateur bands, and this has indeed become the subject of a practical antenna system.[1]

Conclusion

Computer trial runs, through a program developed by WA2VBW, have facilitated the investigation of a large number of $\lambda/4$ vertical antenna-array configurations. "Best" configurations, drive conditions, power gains and patterns have been found for the cases of two, three and four elements. Especially interesting is the case of four elements arranged in a square whose side dimension is about one-quarter wavelength.

Cases using more than 4 elements have been investigated, but the complexity, probable cost, and difficulty of installation of such configurations, reduces their utility and so they will not be reported here.

The author wishes to acknowledge the contribution of Henry Hurwitz, WA2VBW, who supplied the original computer program for this investigation. This material was originally presented in *QST* by James L. Lawson, W2PV.

References

[1] Lawson, W2PV, "75/80 Meter Vertical Antenna Square Array," *QST*, March 1971.

360-Degree Steerable Vertical Phased Arrays

Microwave power-splitting and phasing techniques were applied to the design of this 80-meter array. It has established an outstanding record for performance on long and difficult paths.

The possibility of providing effective 360-degree horizontal coverage with an array switched electrically, rather than rotated mechanically, has long intrigued many designers. Such a solution to the directional antenna problem is of particular interest to amateurs operating on the lower frequencies, where any mechanical rotation system is difficult and expensive to build. One of the authors, now W1CF, writing under his old call, W1HKK, described an 80-meter switchable phased array of four quarter-wave in-line elements more than 10 years ago.[1] The present article describes several novel array designs, using up-to-date technology, which provide greatly improved operation. Also covered are techniques used for effective power division, the beam-forming phasing system, switching, and impedance matching. Ground radials, cable and connector selection, and dc continuity testing are discussed.

One of these arrays recently constructed for 80-meter use has a single 97-degree lobe with a gain over a single vertical of approximately 7 dB at low angles. Its front-to-back ratio is 25 dB, and its front-to-side ratio is more that 12 dB, over the whole 80-meter band. It is switchable over 360 degrees in four 90-degree steps.

Computer-Modeled Arrays and Patterns

In the spring of 1975, while sitting over a cup of coffee, the three authors discussed the possibility of rebuilding the 1965 4-



Fig. 29 — Polar plot of relative power, and planar view of the four-element diamond array showing the pattern obtained with no dc voltage on the switching relays, as in Fig. 31. Minor lobes are too far down to show on this scale.



Fig. 30 — Bandwidth and side-lobe study of the four-element diamond array.

element array, using many improvements in technology that have evolved in the last 10 years. Dr. Joseph White accelerated the effort by coming up with a computer program written in Fortran IV, called ARRAY, which allows the user to plot patterns of arrays of from 2 to 99 elements in various spacings and combinations of phase and power, without ever leaving the computer terminal. Over 30 iterations using 4 elements were explored, and the computer-printed polar plots and other gain data analyzed, before we arrived at a configuration which provided good forward gain over a broad beamwidth, with no measurable unwanted lobes.

The configuration selected has four quarter-wavelength vertical elements in a square, with quarter-wave spacing between adjacent elements, as shown, with its predicted pattern, in Fig. 29. All elements are fed with equal amplitudes, the rear element at 0°, the two side elements at -90° and the lead element at -180°. The beam is transmitted along the diagonal from the rear to lead element. Gain due to horizontal beam formation alone is about 5.3 dB over a single vertical element. Front-to-back ratio is 25 dB. Front-to-side ratio is 12 dB, at 90° either side, increasing to much higher levels at 135° either side. Since most of the vertical energy is concentrated at low angles by the array, as much as 4 dB of gain additional to the predicted 5.3 dB in the horizontal plane can be achieved in theory, with perfectly conducting ground. The authors estimate that a good radial system and less-than-perfect ground yield an additional gain of 2 dB, or a total gain just over 7 dB for the system described.

The computer predicts a half-power beamwidth of 97°, so a suitable switching matrix can be used to direct the beam to four different quadrants, with only a slight loss of forward gain at the cross-over points, and virtually no deterioration of the front-to-back and front-to-side suppression. A computer study of the effect of variations in element spacing on forward-gain to maximum side-lobe level, plotted in Fig. 30, led to selection of $\lambda/4$ spacing of the corners of the square array. The 80-meter beam erected according to the computer-synthesized array design has proven to be remarkably successful. On-the-air results clearly approximate the performance anticipated by the program.

RF Power Dividers

Good power splitters are essential to the operation of phased arrays. Two-way and three-way power dividers will be discussed. Amateurs in broadcasting are well aware that tapped coils are the mainstay for power division in their industry. This reactive technique presents many problems.[2] The authors, being more versed in microwave techniques, thought it logical to scale up in wavelength the methods of power division used most successfully in the microwave region, particularly what is now known as the Wilkinson Power Divider,[3] shown in Fig. 31. Power from the transmitter is fed through a 50-ohm line of any length to a coaxial T, feeding two quarter-wavelength 70-ohm lines, W1 and W2. The two inner conductors of the 70-ohm lines are connected through a 100-ohm noninductive resistor, R1. This type of divider gives an equal power split, matches to 50-ohm loads at the two outputs, and has the unique property that any energy returning to the two outputs out of phase, due to mismatches or mutuals, is absorbed in the 100-ohm resistor.

The 90-degree phase-delay cable (DL) used in one side of each of the three power-splitting hybrids serves to assure that equal power reflections from the antennas are absorbed. Theoretically the resistors absorb none of the forward power. This technique provides approximately 30 dB of isolation from one output terminal to the other, to unwanted energy.

Reference is made in the 1965 article to difficulty in adjusting a phased array, because of element interaction due to mutual impedances between elements. The Wilkinson Power Divider, when used to feed phased arrays, reduces these problems and those resulting from imperfect match at the antenna inputs, and contributes to the realization of the predicted patterns. The "Wilkinson," is a remarkably simple and uncritical solution to the problem of power division. The 3-element vertical array described later uses a three-way "Wilkinson," shown in Fig. 33. It is constructed by splitting the 50-ohm input three ways, into three quarter-wave lengths of 93-ohm coaxial cable. The center conductors are connected together through 150-ohm noninductive resistors. An alternative approach is to return each center conductor to an ungrounded common point, through 50-ohm noninductive resistors.

Feeding, Switching and Phasing

The 4-element diamond array erected at W1CF uses three Wilkinson two-way

Terminations and switching relays at the center of W1CF array.



Fig. 31 — Schematic diagram of the Wilkinson Power Dividers, phasing lines, and switching relays (rf connections) for the four-element array. Dc switching commands for the four pattern headings are given at the lower right.

power dividers, as shown in Fig. 31. Phasing is accomplished with three 90-degree sections of RG-8/U cable, DL1, DL2, DL3. The four outputs are at 0°, -90°, -90° and -180° respectively in phase relationship, with power from the transmitter divided into four equal parts. Every effort was made to preserve symmetry throughout the system, in the hybrids, phase shifters, rf switching, feeds, and antenna placement, in order to have the array perform uniformly as it is switched between the four headings.

The switching can be done with six spdt coaxial relays, as in Fig. 31, or with one transfer relay and four spdt relays. With no voltage on the relay coils, the arms are in the positions shown in Fig. 31, giving northeasterly directivity (57° true, on Paris) the heading used most of the time at W1CF. The array is about 500 feet (152.40 m) from the transmitter, necessitating use of remote relays. A prospective user should consider the tradeoff between cable and relay costs. If the array is close to the station, four equal lengths of 50-ohm line can be brought into the station, and the switching done with a 4-pole, 4-position switch.

The long run of line here was dictated by the desire to take advantage of ground qualities and concealment afforded by swampland 500 feet (152.4 m) from the house. Not wanting to be electrocuted, we used 28 volts dc for operation of the switching relays. By judicious use of binary arithmetic, the switching commands require only three wires. Selection of the four beam headings is done at the operating position with a 4-wafer, 4-position switch. Relays should be selected for reliability and ease of weatherproofing. The cluster of relays and teminations shown in the photograph is at the geometrical center of the W1CF array. The connectors are protected against moisture by 3/4-inch (19 mm) heat-shrink tubing, which should extend from the bottom half inch (13 mm) of the connector 2 inches (51 mm) down the cable. In addition, wide plastic wastebaskets are used to protect these components. The expensive precautions were taken as the result of hard experience with moisture in the cables and connectors in the 1965 array.



Fig. 32 — Polar plot of relative power, and planar view of the three-element triangular array.

Radiators and Radials

Relays K1 through K4 (Fig. 31) connect to their respective radiators through equal lengths of 50-ohm line, with no special attempt made for matching. The radiators are 57.5 feet (17.53 m) tall, above the base insulators. Constructional details follow the 1965 article, except as outlined below. Base insulators are 2-inch (51-mm) ID PVC pipe, 1/4 inch (6-mm) wall, 18 inches (457 mm) long, affixed to the aluminum with PVC cement and self-tapping screws. Each radiator is guyed at three levels with 3/16-inch (5-mm) galvanized cable, broken every 30 feet (9.14 m) with egg insulators.

Though 120 radials are considered to be the optimum number, only 40 per element are used here. Most are 65 feet (19.81 m) long, no. 12 galvanized wire, lying directly on the ground. This presents no hazard, as there is no foot traffic through the swamp area. The center radials are interconnected to two common busses in the central region, as recommended in reference 2. The authors feel intuitively that the square geometry of the array, in addition to providing considerable symmetry of the mutuals, allows a higher packing density for the radials, reducing ground losses.

Though the array has quarter-wavelength elements, all the feedpoints are at 50 ohms, and any type of vertical element can be used, provided an effort is made to match the inputs, and networks used for matching are *the same for all 4 elements.* Obviously, a height of 5/8 wavelength would be desirable, particularly for arrays built for higher frequencies. An indication of match would be to put rf voltmeters across the 100-ohm resistors, and tune the matching networks simultaneously for minimum voltage across the resistors. A nice thing about the λ/4 case is that the match is close enough that this step has not been necessary.

Testing

Before the array is fired up somebody should go to each element and short the input, while another person watches an ohmmeter placed across the main line at the station end. Make sure that a very low dc resistance is measured. Then, with the array in the normal position, as in Fig. 31, make sure that the resistance across the



HEADING	K1	K2	K3
0°		x	x
60°		x	
120°	x	x	
180°	x		
240°	x		x
300°			x

Fig. 33 — Schematic diagram of a three-element vertical array and its directivity switching and power dividing circuitry. Interconnecting leads should be as short and symmetrical as possible. The 50-ohm lines between the relays and antenna elements should be all the same length.

input is high. If it is low, check for moisture in the cables or connectors or for other leakage resistance. Silicone grease in the connectors is a good moisture preventive measure. It is recommended that these resistance checks be repeated periodically to be sure that all is well.

When the array is ready for use, go easy at first, as any reflected energy will be dissipated in the 100-ohm resistors. If they become hot, better matching is necessary, and if they blow up, perhaps higher-wattage resistors are needed. At W1CF, resistor banks were made up of 6, 20-watt, 150-ohm surplus resistors in series-parallel to give 100 ohms. These handle the dissipated power when the system is driven from a 4CX1000A amplifier, and after a month of operation there was no evidence of resistor damage. No attempt should be made to hot-switch the directivity. This was done inadvertently, and the result was the need for extensive emergency repairs — in midwinter.

Performance

In the short time that the array has been in use, all continents have been worked on 80-meter phone, including several stations in Japan and India, tough paths from New England. Gain and side and back rejection on all signals except those arriving from very high angles are just what the computer program predicted.

In receiving in the "search" mode, one hand tunes the receiver while the other operates the lobe selector switch, to see which position "listens" best. The big W1CF rotary array for 10, 15 and 20 takes 45 seconds to rotate 360°, which tends to discourage frequent directional checks. With the phased array a complete scan takes but a few seconds. The high front and side rejection eliminates most of the interference from signals in unwanted directions, and in transmitting the clean patterns help to prevent ruffled feathers.

A surprising by-product has been the reduced atmospheric noise pickup from unwanted directions. In particular, when listening toward Europe atmospheric noise coming from electrical storms in the southwest is greatly reduced, improving the signal-to-noise ratio on signals arriving from across the pond. The array is an order of magnitude better on both transmitting and receiving than any antenna previously used on 80 at W1CF. It has more than held its own with the competition, in all four quadrants. Of special interest to operators who like to use both phone and cw on 80 is the fact that the SWR is close to unity, from 3.5 to 4 MHz.

Triangle 3-Element Array

Anticipating that some amateurs may wish to use three rather than four elements, the ARRAY program was used to explore equilateral triangle configurations. Though it was not reduced to practice, a 3-element vertical array with 0.288λ spacing between adjacent radiators looks promising. The lead element is driven at 0° and the two side elements at -90°. The forward lobe is 135° wide, with a gain of close to 5.5 dB, including an estimated 1 dB contributed by vertical focusing. Front-to-back ratio is 12 dB. With suitable switching, the pattern can be aimed in six different directions, again providing 360-degree coverage. The three-way Wilkinson mentioned earlier must be used with three 90-degree sections of 50-ohm line, to provide the proper phase relationships. Several other configurations appear promising, but involve more complex switching and power-dividing circuitry.

Applications for Other Frequencies

The diamond and triangle antenna configurations may find uses at other frequencies, as was done with the 1965 design.[4] Formulas are given below for determining the line lengths and element spacings. A 2-meter phased array can be mounted on the roof of a car and wafer-switched to the desired directions. For people who like to experiment with logic and rf switching with semiconductors, circuits can be devised so that the receiver can scan periodically, and the antenna steered to the desired signal.

The authors wish to thank the many people who have contributed to the success of this project, including W1FRR, K1GXT, W1HMV, W1FXT, K1CCK, M. E. Hines, F. Howe, H. Wells, R. Rearwin, H. P. Scott, and many others. We also wish to thank Microwaves Associates, Inc., for the use of their superb computer facilities.

Formulas for length of quarter-wave (90°) phasing lines, and spacing of radiators, are given below:

Electrical λ/4, solid-dielectric coaxial line, 50 or 70 ohms (RG-8, -11, -58, -59):

$$L_{ft} = \frac{162.36}{f_{MHz}}$$

Electrical λ/4, solid-dielectric coaxial line, 93 ohms (RG-62, -71):

$$L_{ft} = \frac{206.64}{f_{MHz}}$$

300-ohm Twin-Lead — parallel three λ/4 sections to approximate 93-ohm cable (requires 1 input and 3 output 1:1 baluns):

$$L_{ft} = \frac{201.72}{f_{MHz}}$$

Radiator spacing, diamond array:

$$S_{ft} = \frac{246}{f_{MHz}} > 0.25\lambda$$

Radiator spacing, triangular array:

$$S_{ft} = \frac{283.4}{f_{MHz}} > 0.288\ \lambda$$

This material was originally presented in *QST* by Dana W. Atchley, Jr., W1CF, Harold E. Stinehelfer and Joseph F. White, Ph.D.

References

[1] Atchley, "Switchable 4-Element 80-Meter Phased Array," *QST,* March 1965.

[2] National Association of Broadcasters, *Engineering Handbook*, 6th Edition.

[3] Wilkinson, "An N-Way Hybrid Power Divider," *IRE Transactions on Microwave Theory and Techniques,* January 1960.

[4] Botts, "A Four-Element Vertical Beam for 40/15 Meters," *QST,* June 1975.

An Etched-Circuit Monimatch for Checking Your Antenna System

Why buy an expensive SWR indicator when you can build this slick little unit at home? Not only will you save money, but you'll learn something about how SWR meters operate. Try the W1ICP circuit — you'll like it!

A Novice who reads the instruction manual that comes with his transmitter and uses a 50-ohm dummy antenna can follow the tune-up procedures fairly accurately. With the dummy antenna he will find that the settings for the tuning controls will be fairly close to those specified by the manufacturer. However, when an antenna system is attached to the rig, in many instances the adjustments are far removed from any "book" setting. When this happens the Novice finds that he cannot get proper tuning of the rig, or worse yet, actually damages the equipment by trying to "force" it to work.



Fig. 34 — A typical setup for using a Monimatch in a multiband antenna system using a single dipole. The length of the dipole is not critical but it should be at least 1/4 wavelength overall at the lowest operating frequency for good efficiency. The feed line can be any length. The antenna relay and low-pass filter may be omitted if not needed.

Nearly every transmitter these days, whether commercial or home-built, has a final amplifier stage that is designed to work into a 50-ohm load. If the load is something other than 50 ohms it may be impossible to tune the amplifier stage correctly. Of course, an important part of the problem is finding out what the load is — or, rather, how far from 50 ohms it happens to be. The piece of measuring gear described in this article is a device for doing just this. However, before describing the Monimatch and what it can do, let's take a little closer look at antenna-system loads.

The "50-Ohm" Load

The evolution of transmitter design since WW II has been influenced by several factors that have led to design that is more or less standard these days. First off, television came along right after the war and the hams quickly discovered that extremely tight shielding of a transmitter was needed to prevent undesired radiation that could cause TVI. However, when tight shielding was installed, band changing without band-switching became a real chore because there were so doggone many screws to unscrew and rescrew.

The one type of tank circuit that lent itself very well to the problem was the pi network. It was a fairly simple job to design a tightly shielded bandswitching transmitter, using the pi network, that would work into a 50-ohm load. Why 50 ohms? Simply because at this time 50-ohm coaxial cable had become a very popular type of transmission line. During the war, techniques were developed that made the manufacture of flexible coaxial cable a



Here is the completed Monimatch with the two meters and the sensitivity control in the box at the right. The sensing unit is at the left.



This is the sensing unit of the etched circuit Monimatch. As pointed out in the text, be sure to use a heat sink when soldering the diodes and resistors to the circuit board. The two shielded pickup leads are routed out the back of the Minibox, through a rubber grommet.



Fig. 35 — Circuit details of the etched-circuit Monimatch. The 0.001 μF capacitors are disk ceramic.
D1, D2 — 1N34A germanium diodes.
J1, J2 — Coax chassis fittings, type SO-239.
L1, L2 — See text and Fig. 36.
M1, M2 — 0-50 μA meter (Lafayette 99 H 5049).
R1, R2 — 68-ohm, 1/2-watt carbon or composition.
R3 — 25 kΩ control, linear taper.
S1 — Spdt switch.

reliable and economical process. So TVI and the availability of coax feed lines were the primary contributing factors that led to our present-day transmitter design.

If the load that is attached to the transmitter is something other than 50 ohms then the transmitter may be difficult to load, depending on a couple of other factors. While it is possible to design a pi network that will handle quite a wide variety of loads, many present day manufacturers, in order to compete in given price ranges, use a minimum number of parts in the tank circuit of the amplifier. For such rigs to operate properly the load must be between 25 and 75 ohms. This of course means that the user *must* furnish a load that will fall within this range.

Transmission Lines

The output terminal on all rigs these days is a coax fitting, which of course implies that a coaxial line must be attached to the rig. This doesn't mean that the coaxial line has to go all the way to the antenna. It could be connected to a Transmatch or a balun. What is important is that the first thing in the antenna system is the coaxial line that is attached to the rig.

Many Novices mistakenly believe that if you attach a 50-ohm coaxial cable to rig you *automatically* have a 50-ohm load. This is not true. The 50-ohm designation on the cable merely means that 50 ohms is the *characteristic impedance* of the cable. The characteristic impedance of a transmission line is determined by the size of the conductors used, the spacing of the conductors, and the dielectric material used to separate and support the conductors. The only time you would have a 50-ohm load using 50-ohm cable is when the line is terminated in its characteristic impedance. In other words, if the antenna has an impedance of 50 ohms then you will have a 50-ohm load on the rig. If the antenna has an impedance of other than 50 ohms then the load at the transmitter will be something other than 50 ohms. This in turn leads us up to a short discussion of standing-wave ratio.

SWR

If a transmission line is terminated in its characteristic impedance, all the power fed into the line from the transmitter will be delivered to the load end — in this case, the antenna. Actually, not quite all the power will reach the antenna because there is always some loss in the transmission line itself. However, what is important is that when the line is terminated in its characteristic impedance none of the power that reaches the end is reflected back toward the transmitter; all of it is used up in the antenna.

When the antenna impedance is different from the line impedance some of the power will be reflected back toward the transmitter end. Standing waves of voltages and currents will then exist on the transmission line. When this happens, the transmitter will no longer "see" a 50-ohm load. Exactly what the load will be will depend on several factors,[1] but suffice to say it will be something other than 50 ohms.

The standing-wave ratio on the transmission line is the ratio of maximum to minimum voltage or maximum to minimum current that exists along the line. If the line were matched in its characteristic impedance the voltage would be the same along the line and of course the SWR would be 1 to 1. The SWR is determined by dividing the resonant antenna impedance into the line impedance, or vice versa. For example, if the antenna impedance were 25 ohms and a 50-ohm line were used, the SWR would be 2 to 1.

For a moment, let's assume that regardless of how bad a mismatch exists, we are still able to tune and load our transmitter. The question then arises, how does the mismatch affect the losses in the transmission line? The answer to the question depends on how efficient the transmission line is.

Remember earlier we said there are always some power losses in every transmission line. If we have a mismatch at the antenna end, some of the power that reaches the end will be reflected back down the line. In traveling back, some of this power will be dissipated in the line, and the higher the SWR the higher these additional losses will be, because a higher SWR means that a greater proportion of the power will be reflected. In a transmission line that is 100 percent efficient (one that has no losses) it follows that regardless of how high an SWR exists, we wouldn't have any losses due to the SWR. Unfortunately, there "ain't no such" line, although some types of lines are much less lossy than others.

Also unfortunately, coaxial lines fall into the class that can be considered to be lossy lines. Just as an example, let's assume that you are using 100 feet (30.48 m) of RG-58/U on the Novice 15-meter band, and you are getting 50 watts out of your 75-watt Novice rig. This 50 watts is what is leaving your transmitter on the way to antenna via the 100 feet (30.48 m) of line. The loss for 100 feet (30.48 m) of RG-58/U at 21 MHz is 1.9 decibels. Translating this figure to power, we would lose about 20 of our 50 watts in the losses in the feed line, leaving only 30 watts to reach the antenna and be radiated. This is assuming the antenna impedance to be 50 ohms, the same as that of the line. If there is a mismatch the losses will be higher, as pointed out earlier. Suppose the SWR is 3 to 1, using the same setup. The *additional* loss in the system because of the SWR would be 1 dB, or a total of close to 3 dB. A 3-dB loss represents almost exactly one-half the power — that is, only 25 watts reach the antenna to be radiated. RG-8/U cable has the same characteristic impedance as RG-58/U but has less loss because it has larger conductors and more spacing between the conductors (and of course is more expensive).

The closest thing to a lossless transmission line is open-wire line. An open wire line on 21 MHz has only 0.08 dB loss per 100 feet (30.48 m). Even with a very high mismatch — for example, an SWR of 20 to 1, the additional losses are still less than 1 db!

This should not be interpreted to mean that coax is an undesirable type of line to use. For beam antennas it is difficult to beat the ease and convenience of using coax. However, for a single antenna, such as a dipole that is to be used on all bands and all frequencies, the best system is one consisting of a Transmatch and a feed line of open-wire line, such as shown in Fig. 34. With this system you can forget about line losses, SWR on the line, and mismatches between the antenna and feed line. By correctly adjusting the Transmatch, you can always give your rig a 50-ohm load regardless of what the load is on the antenna side of the Transmatch. If we use an SWR bridge in the short length of 50-ohm coaxial line that connects the rig to the

Transmatch, we can adjust the Transmatch so that the 50-ohm line shows a match, or SWR of 1 to 1, and the transmitter always sees a 50-ohm load.

The SWR bridge in the photographs and drawings is simple to build, and when installed in 50-ohm cable, will show the relative mismatch in the line, and also will indicate when you get the Transmatch properly adjusted for a match. The SWR bridge can also be used as an output indicator, which is very handy when tuning up the rig.

SWR Bridge Circuit Details

The etched-circuit Monimatch shown here is a reflectometer that samples the forward and reflected voltage in a 50-ohm line. Fig. 35 shows the circuit diagram. L1 and L2 are the pickup lines. In operation, a very small amount of power is coupled into the pickup lines and the rf voltages are rectified by D1 and D2. The rectified voltages are then fed to the two meters, M1 and M2, and the SWR then determined from the readings.

While a Monimatch is not a precise piece of measuring equipment, the SWR readings will be close enough for practical purposes. In order to determine the SWR, the forward-reading meter is set to full scale by adjusting R3, the sensitivity control, and then the reading on the "reflected" meter is noted. The formula for the SWR using this system is

$$\frac{F+R}{F-R}.$$

For example, let's assume the "reflected" reading is 5, with the "forward" reading being 10. Then 15 divided by 5 (that is, 10 + 5 divided by 10 − 5) would mean the SWR is 3 to 1. The closer the "reflected" reading is to zero, versus full-scale reading on "forward," the closer you come to 1 to 1, or a matched condition.

In the unit shown, two meters are used, one for the forward and the second for the reflected reading. However, if desired a single meter can be used and switched as shown in Fig. 35 at B. We used two meters in the indicator as this permits constant monitoring of what is happening in the line. The meters are inexpensive ones made in Japan.

Construction Details

Fig. 36 is a full-sized template of the etched circuit board. A *QST* article[2] went into detail showing simple methods for making etched circuits, so we won't treat the process here. In making this board, it is suggested that the board be covered with masking tape and then the pattern of Fig. 36 transferred to the tape. Using a sharp knife edge or razor blade and a straight edge, the masking tape can be carefully and accurately cut to the pattern.

After the board is etched, it can be positioned in the Minibox over the chassis connector holes and the board can then be marked at the drilling points for the mounting holes and the center conductor pins of the coax fittings. When installing the mounting screws, be sure they don't short to the center — conductor portion of the foil on the board.

There are a couple of other construction points that should be stressed. The lead lengths on R1 and R2 should be kept as short as possible. Also, be sure to use carbon or composition resistors, *not* wire-wound. When mounting the resistor and diode ends to the pickup sections, L1 and L2, the connections should be at the very ends of the sections. Also, use a heat sink when soldering the leads on any of the components mounted on the board, as too much heat from the iron can ruin the component.

The Monimatch and meters are mounted in separate Miniboxes, 2-1/4 × 2-1/4 × 5 inches (57 mm × 57 mm × 127 mm). The two connectors on the Monimatch sensing unit, J1 and J2, are mounted with their center pins 3-3/4 inches (95 mm) apart, center-to-center. In order to avoid an impedance "bump" in the feed line when the bridge is inserted in the line, the circuit board should be mounted 1/4 inch (6 mm) above the base of the Minibox. Quarter-inch (6 mm) spacers can be used under the circuit board at the screws holding both the board and the coax fittings to position the board accurately.

Shielded conductors should be used for the connections from the diodes to the meter enclosure. The shields should be grounded to the chassis at both boxes. These lead lengths are not critical, and the Monimatch can be remote from the meter indicator.



Fig. 36 — Etched circuit board template. The foil side is shown; the etched portion is shaded.

Using the Bridge

If you are using coax feed from the rig to the antenna, the bridge can be installed at any convenient spot in the line. If you are using a Transmatch, similar to the system as shown in Fig. 34, the Monimatch should be installed on the transmitter side of the Transmatch. Any relays or filters should be installed between the bridge and the transmitter, as shown.

Set R3 so that the arm of the control is at the top of the resistance — in other words, with all the resistance in series with the meter circuit. Tune up your rig in the normal fashion, and once tuned up adjust the sensitivity of the "forward" meter by moving the arm of R3 until the meter reads full scale. You can then determine the SWR by the formula mentioned earlier.

When adjusting a Transmatch, feed just enough power through the system to obtain about half-scale reading on the "forward" meter and then adjust the Transmatch controls for a match, as indicated by zero reflected power. You may have to adjust R3 as you adjust the Transmatch to keep the "forward" meter from reading more than full scale. Once you have the Transmatch adjusted for a 1-to-1 ratio as indicated by the bridge, the transmitter can be loaded up in the normal manner. We usually reduce the forward reading to about half scale, and then tune the rig for maximum output, as indicated by the meter. When doing this, you may notice that maximum output as indicated by the bridge meter occurs at some setting other than the normal transmitter plate meter "dip" reading. (Normally, the instruction manuals tell you to tune for a plate dip if the transmitter has no output meter.) However, the amplifier stage will work better if you tune for maximum output rather than the dip — keeping the plate loading within the transmitter ratings, of course.

Once you become familiar with the use of the bridge and interpreting the readings, you'll find it a very valuable device in your station. This material originally presented in *QST* by Lewis G. McCoy, W1ICP.

References

[1][Editors Note: It is recommended that the newcomer obtain a copy of *The ARRL Antenna Book* for more detailed information on transmission line operation than can be provided in this article.]

[2]Schiebold, "Fast'n' Easy Printed Circuit Boards," *QST*, August 1969.

In-Line RF Power Metering

Problems are frequently encountered in designing and building reflected-power meters and SWR bridges. Examples of practical in-line rf wattmeters are given here, along with complete details for building a unit that will provide two power ranges, forward and reflected, for use from 3.5 to 30 MHz.

ANTENNA
RFL
FWD
μA

It is neither costly nor difficult to build an rf wattmeter. And, if the instrument is equipped with a few additional components it can be switched to read reflected power as well as forward power. With the foregoing feature the instrument can be used as an SWR meter for antenna matching and Transmatch adjustments.

Perhaps the most difficult task faced by the constructor is that of calibrating the power meter for whatever wattage range he desires to have. The least difficult method is to use a commercial wattmeter as a standard. If one is not available, the power output of the test transmitter can be computed by means of an rf ammeter in series with a 50-ohm dummy load, using the standard formula, $P = I^2R$. Or, if one is not interested in obtaining power readings the bridge can be used solely as an SWR indicator, as is done with the Monimatch-style SWR bridge.[1]

The advantage of the circuits shown here over those of Monimatch bridges is that these instruments are not frequency-sensitive. Monimatch indicators become more sensitive as the operating frequency is increased, thus making it impractical to calibrate them in watts for more than one band, or for more than one portion of a given band. The units described here are more sensitive than Monimatches are. This makes it possible to calibrate them for power levels as low as 1 watt, full scale, in any part of the hf spectrum.

All of the circuits shown in this article are similar to the basic one which was described in *QST*.[2] Some of the circuits are those of commercial power meters, and are used to illustrate variations in the basic Bruene design. The reader may wish to experiment with some of these circuits.

Design Philosophy

Referring to the circuit of Fig. 37B, the circuit used by Collins Radio Company, the transmission-line center conductor passes through the center of a toroid core and becomes the primary of T1. The multi-turn winding on the core functions as the transformer secondary. Current flowing through the line-wire primary induces a voltage in the secondary which causes a current to flow through resistors R5 and R6. The voltage drops across these resistors are equal in amplitude, but 180 degrees out of phase with respect to common or ground. They are thus, for practical purposes, respectively in and out of phase with the line current. Capacitive voltage dividers, C3C7 and C4C8, are connected across the line to obtain equal-amplitude voltages *in* phase with the line voltage, the division ratio being adjusted so that these voltages match the voltage drops across R5 and R6 in amplitude. (As the current/voltage ratio in the line depends on the load, this can be done only for a particular value of load impedance. Load



values chosen for this standardization are pure resistances that match the characteristic impedance of the transmission line with which the bridge is to be used, usually 50 or 75 ohms.) Under these conditions, the voltages rectified by D1 and D2 represent, in the one case, the vector *sum* of the voltages caused by the line current and voltage, and in the other, the vector *difference*. With respect to the resistance for which the circuit has been set up, the sum is proportional to the forward component of a traveling wave such as occurs on a transmission line, and the difference is proportional to the reflected component.

The Collins circuit uses two 8-μF capacitors, C5 and C6, to permit the meter to approach the PEP level during ssb operation. The dc voltages in the forward and reflected lines charge the capacitors to permit a near-peak reading. The discharge rate is set by the series calibrating resistors, R1 through R4, and is dependent upon which of them is switched into the metering line at a given time. The circuit of Fig. 37B uses two 43-pF capacitors, C1 and C2, to cancel the inductive reactances of R5 and R6. Such reactance may become manifest at the high end of the range for which the instrument is built. If reactance is present in that part of the circuit the meter readings may not be accurate, especially at 10 and 15 meters. The capacitors were not needed in the circuit of Fig. 38, perhaps because the resistor leads were very short when they were mounted on the etched-circuit board.

Some Design Hints

It is important that the layout of any rf bridge be as symmetrical as possible if good balance is to be had. The circuit-board layout for the instrument of Fig. 38 meets this requirement. Also, the input and output parts of the equipment should be isolated from the remainder of the circuit so that only the sampling circuits feed voltage to the bridge. A shield across the end of the box which contains the input and output jacks, and the interconnecting line between them, is necessary. If stray rf gets into the bridge circuit it will be impossible to obtain a complete zero reflected-power reading on M1 even though a 1:1 SWR exists.

Referring again to Fig. 38, resistors R1 and R2 should be selected for the best null reading when adjusting the bridge into a resistive 50- or 75-ohm load. Normally the value will be somewhere between 10 and 47 ohms. The 10-ohm value worked well with the homemade instruments shown here. It was found that half-watt resistors exhibited somewhat less inductive reactance at 30 MHz than did some 1-watt units tried. R1 and R2 should be as closely matched in resistance as possible. They need not be exactly 10 ohms, so a VTVM can be used to match them. The resistors used for the circuit of Fig. 38 were actually 10.5 ohms each, and were chosen from an assortment of "10-percenters" on hand.

Silver-mica capacitors C3 and C4 were close enough in value so that special selection was not required. There should be enough leeway in the ranges of C1 and C2 to compensate for any difference in the values of the 330-pF capacitors. Ideally, however, C3 and C4 should be matched in value.

Diodes D1 and D2 should also be matched for best results. An ohmmeter can be used to select a pair of diodes whose forward dc resistances are within a couple of ohms of being the same. Similarly, the back resistances of the diodes can be matched. The matched diodes will help to assure equal meter readings when the bridge is reversed. (The bridge should be perfectly bilateral in its performance characteristics.) Germanium diodes are used in the bridges described here, but



Fig. 37 — Schematic diagrams of typical in-line power meters. At A, the R. L. Drake W-4 instrument. It uses a center-tapped transformer at T1 and has but one capacitive voltage divider in the sensing circuit. The circuit at B is discussed in the text, and is used by Collins Radio Company. The capacitive voltage dividers in this circuit use two 500-pF feedthrough capacitors in place of the silver-mica capacitors specified in Fig. 38. Capacitors C5 and C6 permit a charge time that enables the meter to read near-peak power on ssb. Calibrating resistances R1 through R4 are factory selected. The circuit at C is similar to one used by Comdel in their power meter. In this circuit C1 is a fixed-value (small) capacitor, and the bridge is nulled by the larger capacitor in the divider, C2.



Watts	*Mi*	*Watts*
100	200	1000
90	180	900
80	170	800
70	155	700
60	145	600
50	125	500
40	105	400
30	85	300
20	65	200
10	40	100
5	20	50

Fig. 38 — Schematic diagram of a practical power wattmeter. A calibration scale for M1 is shown also. Fixed-value resistors are 1/2-watt composition. Fixed-value capacitors are disk ceramic unless otherwise noted. Decimal-value capacitances are in μF. Others are pF. Resistance is in ohms; k = 1000.

C1, C2 — 1.3- to 6.7-pF miniature trimmer (E. F. Johnson 189-502-4. Available from Newark Electronics, Chicago, IL).
C3-C11, incl. — Numbered for circuit-board identification.
D1, D2 — Small-signal germanium diode. IN34A, etc. (see text).
J1, J2 — Chassis-mount coax connector of builder's choice. Type SO-239 used here.
M1 — 0- to 200-μA meter (Triplett type 330-M used here.)
R1, R2 — Matched 10-ohm resistors (see text).
R3, R4 — 5000-ohm printed-circuit carbon control (IRC R502-B).
R5, R6 — 25,000-ohm printed-ciruit carbon control (IRC R253-B).
RFC1, RFC2 — 500-μH rf choke (Millen 34300-500 or similar).
S1 — Dpdt single-section phenolic wafer switch (Mallory 3222J).
S2 — Spdt phenolic wafer switch (Centralab 1460).
T1 — Toroidal transformer; 35 turns of no. 26 enam. wire to cover entire core of Amidon T-68-2 toroid (Amidon Assoc., 12033 Otsego St., No. Hollywood, CA 91607).

silicon diodes can also be used. Silicon diodes conduct at a higher voltage than germanium diodes do — approximately 0.7 volt — and will not work too well in low-power wattmeters. Some silicon diodes were tried, but ceased to conduct at approximately 8 watts in the circuit of Fig. 38. This effect can cause misleading results when low values of reflected power are present during antenna adjustments. The SWR can appear to be zero when actually it isn't. The germanium diodes conduct at approximately 0.3 volt, making them more suitable for low-power readings.

Any meter whose full-scale reading is between 50 microamperes and 1 milliampere can be used at M1. The more sensitive the meter, the more difficult it will be to get an absolute reflected-power reading of zero. Some residual current will flow in the bridge circuit no matter how carefully the circuit is balanced, and a sensitive instrument will detect this current flow. Also, the more sensitive the meter, the larger will have to be the calibrating resistances, R3 through R6, to provide high-power readings. A 0- to 200-microampere meter represents a good compromise for power ranges between 100 and 2000 watts.

Construction

The power meter of Fig. 38 is built in two sections. The rf circuit and the calibrating resistors are housed in a 4 × 4 × 2-inch (102 × 102 × 51 mm) aluminum utility box. All components other than J1, J2, and the feedthrough capacitors, are assembled on the etched-circuit board.[3] Switches S1 and S2, and the meter, M1, are installed in a sloping-panel utility box which measures 5 × 4 inches (127 × 102 mm). Four-conductor shielded cable — the shield serving as the common lead — is used to join the two pieces. There is no reason why the entire instrument cannot be housed in one container, but it is sometimes awkward to have coaxial cables attach to a unit that occupies a prominent place in the operating position. Built as shown, the two-piece instrument permits the rf pickup head to be concealed behind the transmitter, while the control head can be mounted where it is accessible to the operator.

Toroidal transformer T1 fits into a cutout area on the circuit board. A 1-inch (25 mm) long section of RG-8/U cable — vinyl jacket and shield braid removed — provides a snug fit in the center hole of the toroid, and is used to complete the line between J1 and J2. The inner conductor of the RG-8/U section solders to the circuit board, thus holding T1 in place.

A flashing-copper shield divides T1 and its center-conductor line from the remainder of the circuit. This partition is shown in dotted lines in Fig. 38. It is mounted on the non-foil side of the circuit board and is secured at each end to solder lugs which are mounted under the retaining screws for J1 and J2.

The circuit board is held in place, at the end near T1, by means of an aluminum L bracket. The circuit-board end nearest the feedthrough capacitors is held in place by a no. 6 spade bolt. A solder lug is mounted under the no. 6 nut (outside the case) which secures the spade bolt. The lug serves as a connection point for the common lead between the rf head and the control box. Two solder lugs are mounted under the bottom two retaining screws of each coax connector. The free ends of the lugs are soldered to the copper foil of the circuit board.

A partition is visible in the foil-side view of the rf head. It can be eliminated if desired, since it did not prove necessary when the unit was tested. Similarly, an extra shield partition is shown on the top side of the board. It too can be eliminated, for it turned out to be unnecessary. The flashing-copper shield discussed earlier is the only one required for the circuit of Fig. 38.

Checkout and Tune-up

Once the instrument is wired and ready to test it should be inspected for unwanted solder bridges between the circuit-board foils. It is usually a good idea to scrape out the rosin buildup between the foils, and this can be done with the blade of a small screwdriver. A continuity check for "opens" and "shorts" should also be made before power is applied to the unit. Make certain that the diodes are installed for the correct polarity — the banded ends (cathodes) toward C1 and C2.

Connect a noninductive 50-ohm dummy load to J2. A Heath Cantenna or similar load will serve nicely for adjustment purposes. Place S2 in the FORWARD position, and set S1 for the 100- range. An rf ammeter or calibrated power meter



Top view of the rf head for the circuit of Fig. 38. A flashing-copper shield isolates the through-line and T1 from the rest of the circuit. The second shield (thicker) is not required and can be eliminated from the circuit. If a 2000-watt scale is desired, fixed-value resistors of approximately 22 kΩ can be connected in series with high-range printed-circuit controls. Or, the 25 kΩ controls shown here can be replaced by 50 kΩ units.



Bottom view of the rf head for the circuit of Fig. 38. The fixed-value resistor at the lower left does not belong in the circuit, but was added as a shunt for one of the calibrating controls which was too high in value — a 50 kΩ unit that was on hand. The shield partition shown here proved unnecessary and can be eliminated.



Fig. 39 — Inside view of the 5- and 50-watt power meter rf head. Component values are the same as in the circuit of Fig. 38, except for the calibrating resistances (see text). An aluminum shield isolates the through-line and toroid from the remainder of the circuit. A 50-μA meter is used in this model.

should be connected between J2 and the dummy load during the tests, providing power calibration points against which to plot the scale of M1. Apply transmitter output power to J1, gradually, until M1 begins to deflect upward. Increase transmitter power and adjust R4 so that a full-scale meter reading occurs when 100 watts is indicated on the rf ammeter or other standard in use. Next, switch S2 to REFLECTED and turn the transmitter off. Temporarily short across R3, turn the transmitter on, and gradually increase power until a meter reading is noted. With an insulated screwdriver adjust C2 for a null in the meter reading.

The next step is to reverse the coax connections to J1 and J2. Place S2 in the REFLECTED position and apply transmitter power until the meter reads full scale at 100 watts output. In this mode the REFLECTED position actually reads forward power because the bridge is reversed. Calibrating resistance R3 is set to obtain 100 watts full scale during this adjustment. Now, switch S2 to FORWARD and temporarily place a short across R4. Adjust C1 for a null reading on M1. Repeat the foregoing steps until no further improvement can be obtained. It will not be necessary to repeat the nulling adjustments on the 1000-watt range, but R5 and R6 will have to be adjusted to provide a full-scale meter reading at 1000 watts. If insufficient meter deflection is available for nulling adjustments on the 100-watt range, it may be necessary to adjust C1 and C2 at some power level higher than 100 watts. If the capacitors tune through a null, but the meter will not drop all the way to zero, chances are that some rf is leaking into the bridge circuit through stray coupling. If so, it may be necessary to experiment with the shielding of the through-line section of the rf head. If only a small residual reading is noted it will be of minor importance and can be ignored. In the circuit of Fig. 38 there remained approximately one-half a meter division when the null was reached, and this occurred only on the 1000-watt range. Since this was representative of less than 2 watts of power, it was deemed inconsequential.

With the component values given in Fig. 38 the meter readings track for both power ranges. That is, the 10-watt level on the



Inside view of the modified Heath HM-15 bridge. The new components are grouped at the center of the chassis on a 5-lug terminal strip. The nulling capacitors are connected between the inner line and the terminal strip. Press-fit aluminum shield covers are slipped over the trough line to aid in rf isolation. One cover is in place; the other is at the right of the photo. Improved shielding might be effected by installing an aluminum plate between the terminal strip and the two nulling capacitors.



Inside view of a 2000-watt power meter built by N1RM. This bridge is patterned after the circuit of Fig. 37B. Point-to-point wiring is used throughout, thus avoiding the need for a circuit board. Two piston trimmers are used for the nulling capacitors and are mounted one above the other on a phenolic block. The two 500-pF feedthrough capacitors are part of the capacitive voltage dividers.



Fig. 40 — Inside view of a 3-watt power meter for QRP rigs. Its circuit is given on page 16 of June 1969 *QST*. Ceramic trimmers are used for nulling the bridge. Type SO-239 connectors are paralleled with phono jacks to add versatility. A 4 X 4 X 2 inch (102 X 102 X 51 mm) utility box houses the entire unit.



Fig. 41 — Schematic diagram of the modified Heath HM-15 SWR meter. D1, D2, M1, R1 and S1 are original components from the HM-15. T1 is the same as in Fig. 38. See text for additional details.

100-watt range, and the 100-watt point on the 1000-watt range fall at the same place on the meter scale, and so on. This no doubt results from the fact that the diodes are conducting in the most linear portion of their curve. Ordinarily, this desirable condition does not exist, making it necessary to plot separate scales for the different power ranges.

Tests indicate that the SWR caused by insertion of the power meter in the transmission line is negligible. It was checked at 28 MHz and no reflected-power could be noted on a Bird wattmeter. Similarly, the insertion loss was so low that it could not be measured with ordinary instruments.

Other Circuits

Additional circuits and photos are shown for variations in the basic design used at Fig. 38. A low-power model, having scales for 5 and 50 watts, is shown in Fig. 39. It uses fixed-value resistors for meter calibration. The required values of resistance were first determined by temporarily inserting a potentiometer in the meter line, obtaining the required full-scale reading, then substituting fixed-value resistances of the proper ohmage. The meter readings for the two power ranges do not track in this model.

A low-power meter was designed for use with the QRP transmitter described in June 1969 *QST*. It is shown in Fig. 40, and has a full-scale calibration of 3 watts. To obtain additional sensitivity, the primary of the toroidal transformer consists of a one-turn link instead of the single wire that would normally pass through the hole in the toroid core.

Some experiments were conducted to see if a Heath HM-15 SWR bridge (a Monimatch type) could be modified to work in a Bruene circuit. The results were satisfactory, and the circuit is given in Fig. 41. No attempt was made to obtain a calibration scale for the meter. The unit is being used as a simple SWR indicator, but now has better sensitivity in the lower part of the hf spectrum — 7 watts, full scale, from 3.5 to 30 MHz. Also, the instrument is no longer "frequency-conscious" as was the case before modification. The original pickup lines were discarded, the FWD-REV panel switch was rotated 180 degrees so that the labels were correct for the new circuit, and press-fit shield covers were installed on the trough line as shown in the photo. A power scale could be plotted by setting the sensitivity control in a fixed position — possibly replacing the existing control with a screwdriver-adjust type. A new 100-μA meter could be installed to provide a better scale for calibration in watts.

It was necessary to dismantle the trough line so that the toroidal transformer could be slipped over the inner line. A few wraps of mylar tape were wound over the center of the inner line to insulate the toroid winding from the line, and to provide a snug fit to keep the toroid in place. The trough was notched out with a nibbling tool to allow clearance for the toroidal transformer. Additional shielding can be added between the line and the rest of the circuit to further assure a zero meter reading in the reflected position.

It is hoped that the experimenter will find sufficient information here to enable him to build a power meter that will satisfy his specific needs. This material was originally presented in *QST* by Doug DeMaw, W1FB.

References

[1] "Monimatch Mark II," *QST*, February 1957.

[2] Bruene, "An Inside Picture of Directional Wattmeters," *QST*, April 1959.

[3] The etched-circuit board pattern and parts layout sheet for this power meter are available from ARRL hq. Send 25 cents and an s.a.s.e. Check with Circuit Board Specialists, P. O. Box 969, Pueblo, CO 81001 for negative and circuit boards.

A Resistive Antenna Bridge — Simplified

SWR indicators are neat, but when it comes to making measurements of resonant impedances, you need a true bridge type of instrument. Measure those low antenna resistances directly with this W2FMI circuit, and do it up to 30 MHz with ease!

As shown previously,[1] a bridge using a single variable capacitor can be used to measure resonant impedances of antennas and losses in coils with reasonable accuracy. With addition of an L/C network, the bridge can also be very useful in adjusting antennas for resonance conditions. Recently it was brought to the author's attention that a bridge using a variable resistance could also perform well. This is possible because the range of antenna impedances is generally low enough to allow for low values of resistance in the arms of the bridge. Under these conditions parasitic capacitances are negligible up to 30 MHz.

Resistive bridges have the advantages of small size, readily available components, and dial calibrations which can be made practically linear. Two bridges are shown with their respective calibration curves. The first is a linear device. The second expands the lower portion of the calibration curve, 0 to 30 ohms, to measure lower values of antenna impedance and coil losses more accurately.

Bridge Details

The resistive bridge with a variable resistance in one arm and equal resistances in the other two is shown in the photographs, and schematically in Fig. 42A. The nonlinear bridge is similar mechanically. The small enclosures and compact layout minimize lead lengths. With the linear version the dial practically reads directly in



Exterior and interior view of the resistive bridge. Appearance and component arrangement are essentially the same for the two types described.

---

[1] Sevick, "Simple RF Bridges," April 1975 *QST*, page 11.



Fig. 42 — Schematic diagram and parts information for the linear (A) and nonlinear (B) resistance bridges. Resistor wattages are the minimum recommended.

D1 — Germanium diode.
J1, J2 — Coaxial connector, chassis type.
J3 — Phono jack.
R1 — 100-ohm, 2-watt linear control (Allen-Bradley, Type J).



Fig. 43 — Calibration curves for the linear (A) and nonlinear (B) resistance bridges. The add-on L/C network used was described in the author's *QST* article on capacitive bridges.

ohms. In using the L/C network described in the previous article, a constant offset occurs, because of ohmic loss in the coils. This can be as high as 20 ohms, as is shown by the 160-meter curve with the L/C network, Fig. 43A.

The variable resistor used in the bridges has a parasitic (stray) capacitance of the order of 10 to 20 pF, which has little effect even at 14 MHz. Other potentiometers of similar design can probably be substituted. The calibration curves provide a good check. If the difference between the calibrations for the lowest and highest frequencies to be used is greater than an ohm or two, parasitic capacitances are probably excessive.

The nonlinear bridge uses most of the same components, but the control is connected in the differential mode, as shown in Fig. 42B. Resistance is subtracted from one arm and added to the other, tending to spread out the low end of the resistance scale for increased accuracy. In this version, the dial can be read easily to 0.5 ohm.

Results

The author has found these resistance bridges to be entirely satisfactory for measurements in the range of 1.8 to 30 MHz. Because of their greatly expanded scales, as compared with the capacitive bridges, and generally lower values of resistance in all arms of the bridge, they tend to have less marked nulls when used with very low-power signal sources. Increasing the minimum power to 20 or 30 milliwatts, when using the sensitive meter described previously, should take care of this.

In closing, the writer wishes to thank Roger A. Sykes, W1PP, for bringing the resistive bridge to the author's attention. This material was originally presented in *QST* by Jerry Sevick, W2FMI.

Why a Transmatch?

Let's cut away some of the mumbo jumbo about antennas. Here's some basic information to help the newcomer make the decision that best suits his need.

These days, nearly all transmitters have a pi-network tank circuit in the final amplifier. There are good reasons for this. With the pi tank it is possible to design a band-switching transmitter with excellent shielding (in order to prevent undesired harmonic radiation as far as TVI is concerned) and to accomplish the job with a minimum of complications. Additionally, the tank circuit easily can be set up to work into 50- or 70-ohm loads, the characteristic impedance of the popular types of coaxial feed lines. However, as we will see, this is where a "clinker" can get into the act.

When a pi network is designed to work into a 50-ohm load, the load *must* be 50 ohms in order for the transmitter to work at full efficiency. Merely connecting 50-ohm coax to the tank circuit does *not* accomplish this. For the tank to "see" a 50-ohm load, the far end of the coax — the load or antenna end — must also have the same impedance as the coax, 50 ohms. If the load is not 50 ohms the pi network will see some other value than 50 ohms. Usually, too, the tank will see reactance as well as resistance when the line is not matched. While reactance is expressed in ohms, it isn't a true resistance, and what it does is make it more difficult to put power into the line unless certain steps are taken to compensate for it.

Pi-Network Tank Circuits

In the conventional transmitter pi tank we have two controls, customarily referred to as the "tuning" and "loading" controls. The tuning control is the one that resonates the tank circuit to the desired frequency. The loading control, when adjusted properly, permits the final amplifier stage to be loaded to the desired input. To a limited extent it can also be used to compensate for the reactance in the load.



Fig. 44 — At the top is a simple half-wave dipole using coax feed. At the bottom is a drawing of a trap dipole. When a signal is fed to this antenna, for example an 80-meter one, the feed line "sees" a more-or-less resonant antenna on 80. When the transmitter is switched to 40, the traps "divorce" the 80-meter portion and the feed line sees a resonant 40-meter half-wave.



Fig. 45 — This drawing shows an ideal multiband antenna system. The units can be connected together by either 50- or 70-ohm coaxial line. The SWR bridge must match the line used. By putting the antenna relay in this section of the line, the Transmatch can be used to advantage for receiving as well as transmitting.

The clinker in this is that the reactance of many antenna-system loads may have too wide a range for the loading capacitor to handle. If you've ever been in the situation where is was impossible to load (or unload) the amplifier stage, the likely reason is that the load is too reactive to be handled by the tank circuit.

Such a condition can lead to some serious difficulties. While a correctly tuned pi network will offer good harmonic attenuation, an improperly adjusted tank may provide *no* harmonic attenuation. In fact, many Novices who receive second-harmonic violation notices for their 80-meter operation can lay the blame on poor loads and incorrectly adjusted tank circuits. This leads us to the real crux of the problem. How do we get a 50-ohm load on the various bands and frequencies desired?

Antenna Loads

As we said earlier, in order for a transmitter to see a 50-ohm load the far end of the 50-ohm coax must also see 50 ohms. The point where you feed the antenna has a certain impedance; in a half-wave dipole, for example, the impedance will be in the neighborhood of 50 ohms, depending somewhat on the dipole's height above ground. Also, at resonance there will be no reactance in the impedance. When we change frequency, the antenna is no longer resonant and reactance is introduced into the impedance. In turn, reactance is present at the transmitter end of the line. Whether or not the transmitter tank circuit can compensate for it will depend on the range of the loading capacitor.

How do we go about getting an antenna that will look like 50 ohms over a wide range of frequencies within a band — and, for that matter, on several bands? It isn't exactly easy.

For example, if we cut an 80-meter half-wave dipole for the center of the band, 3750 kHz, it is possible to obtain a fairly good match for 50-ohm coax at that frequency and approximately 50 kHz each side of 3750 kHz. However, at the band edges, 3500 and 4000 kHz, the impedance will be very reactive and the mismatch between the coax and the feed point may be as high as 10 to 1. It would be difficult, if not impossible, for our pi network to handle that type of mismatch. Actually, there is no "simple" antenna, by ham standards, that can be coax fed on 80 meters and cover the entire band with a reasonable match. The 40-, 20- and 15-meter bands are narrow enough so that the pi tank will handle a coax-fed dipole under normal circumstances. However, a coax-fed dipole is essentially a one-band system so such an antenna is not the answer if we want to work "all" bands and all frequencies with a single antenna.

Trap Antennas

One type of multiband antenna with coax feed is the trap antenna, either horizontal or vertical. The horizontal variety is essentially a dipole with traps added to divorce parts of the antenna so the coax "sees" an electrically resonant dipole on the band in use. However, the trap dipole is no "broader" than a single dipole. Fig. 44 shows such a trap dipole antenna.

There are a couple of drawbacks to trap dipoles. First, a coax-fed single-band dipole is essentially a selective circuit, in that it tends to discourage undesired harmonics from being accepted and radiated. For example, a 40-meter harmonic would have a tough time in an 80-meter coax-fed dipole because the antenna and line are badly mismatched on 40. A trap system, however, does not discriminate against such undesired signals. Also, traps introduce power loss — probably not a great deal, but nevertheless loss. But if you want to use coax line and have multiband operation, the trap dipole is an answer. On the other hand, a Novice may ask, "Is there a better multiband system, one without the trap losses and harmonic problems?" The answer is yes, but before describing it let's take a look at feed lines.

Feed Lines

Three common types of feed lines are used by amateurs: coaxial, twin-lead, and open-wire. Each has a certain amount of loss, with coax the lossiest, twin-lead next, and open-wire line the most efficient. An important point to keep in mind is that the greater the mismatch, or standing-wave ratio, on the transmission line, the greater the line loss. Also, the loss in any line increases with frequency: The loss will be least at 80 meters and will become progressively greater as we approach vhf or uhf. As an example, the loss in 100 feet (30.48 m) of RG-58/U line at 144 MHz is about 6 decibels. Translating this to power, if we had a transmitter that was putting out 100 watts only about 25 watts would reach the antenna, at the end of a 100-foot (30.48 m) line, to be radiated. The remaining 75 watts would be dissipated as heat in the line! And, most important, this figure is based on the coax being *matched* at the antenna end. The mismatch or SWR will depend entirely on the impedance of the transmission line and the impedance of the antenna. If there is a mismatch, the losses increase. On 80 meters, this same coax has a loss of less than 1 dB for 100 feet (30.48 m) of line, so we could tolerate more of a mismatch.

But don't overlook the fact that if the line and antenna are mismatched it may be impossible to make the amplifier load, even if the extra loss can be tolerated. The question that then comes to mind is if we use a low-loss line so we can tolerate a high degree of mismatch, how can we make the transmitter see a 50-ohm load? The answer to this is to use a Transmatch between the transmitter and antenna.

The Transmatch

A Transmatch is simply an adjustable rf transformer that converts an unknown load (antenna side) to a desired load (transmitter side). It consists of inductances and capacitances which can be adjusted to provide a perfect 50-ohm load for the transmitter on any band or frequency.

Let's take an example to show how a Transmatch can do the job. The impedance at the center of an 80-meter dipole is

Approximate Attenuation in Decibels/100 ft. (30.48 m)

Type	Z_0	3.5	7.0	14.0	21.0	28.0	50.	144	220	420
RG-58/U	52.5	0.68	1.0	1.5	1.9	2.2	3.1	5.7	7.2	10.4
100W. Output		8	18	28	35	38	51	72	81	92
RG-8/U	52.	0.30	0.45	0.66	0.83	0.98	1.35	2.5	3.3	4.8
RG-59/U	73	0.64	0.90	1.3	1.6	1.8	2.4	4.2	5.2	7.2
RG-11/U	75	0.38	0.55	0.80	0.98	1.15	1.55	2.8	3.8	4.9
Twin-lead	300	0.18	0.28	0.41	0.52	0.60	0.85	1.55	1.9	2.8
Open-wire	—	0.03	0.05	0.07	0.08	0.1	0.13	0.25		

This chart shows the attenuation figures in decibels for common types of feed lines. Z_0 is the nominal impedance. In the case of open-wire line, the impedance will depend on the size of the conductors and their spacing. The second line of the chart indicates the amount of power that would be lost in a 100-foot (30.48 m) run of RG-58/U when properly matched. For example, on 21 MHz, the loss per 100 feet (30.48 m) is 1.9 dB. With 100 watts output from the transmitter, 1.9 dB represents a loss of 35 watts in the line. A mismatch will increase the line loss.



At the left are two examples of coaxial feed lines. The three lines at the right are balanced-type lines, 70-ohm, 300-ohm twin-lead, and TV open-wire line.

between 50 and 70 ohms on 80 meters. On 40 meters, the impedance at the same point on this same antenna is about 4000 ohms. If we feed this antenna with 300-ohm twin-lead the mismatch on 40 would be on the order of 13 or 14 to 1. However, bear in mind that 300-ohm line has relatively low loss, so we can probably tolerate the high SWR if the line is fairly short — less than 100 feet (30.48 m). Our only problem in making this antenna work on 40 is to take care of coupling the line to the transmitter. To do this the feed line is connected to the Transmatch and the Transmatch is then adjusted so that the transmitter sees a 50-ohm load. What we have now is an 80-meter dipole being used efficiently on 40, and our transmitter is working into the load it was designed for.

Now let's suppose that we feed this same antenna with 50-ohm coax. On 40, the mismatch would be 4000/50, or about 80 to 1! Because coax is not a low-loss line, the loss in the transmission line would be prohibitive. However, with twin-lead — or, even better, open-wire line — the loss is usually insignificant.

Also, and most important, a Transmatch adds selectivity at the output of the transmitter. It will discriminate against any undesired harmonics or spurious signals. And, if the antenna switching is set up so that the Transmatch is in the circuit on receiving, it will provide more selectivity for the receiver. In fact, a common problem for hams who live near broadcast stations is cross-modulation of 80- and 40-meter ham signals by the strong bc signal. A Transmatch will provide enough selectivity in most cases to eliminate bc cross modulation when it occurs in the receiver's front end.

Many hams are reluctant to use a Transmatch because it requires additional adjustments. However, the advantages are so great in a multiband system that any additional adjustments are more than worth the effort. With a Transmatch, the antenna doesn't have to be a half wave long to work on any band. For example, we described a complete multiband system just recently[1] using an antenna only 100 feet (30.48 m) long. Most hams can manage to get up a 60-foot (18.29-m) dipole, either horizontal or in an inverted-V configuration, and such an antenna also will work on 80 through 10. One method of putting up a multiband system is to find two supports for each end of the antenna, cut a wire long enough to run between them, put an insulator in the center of the antenna and at each end, and attach open-wire or twin-lead feeders long enough to reach the station. That's all there is to it. Bear in mind that a dipole fed this way doesn't have to be a half wave long; it can be any length, and it will work. Of course it is always a good idea to make it as long as possible and get it up as high as possible. Also, if possible, make it at least 1/4-wavelength long at its lowest operating frequency — about 60 feet (18.29 m) for 80 meters, for example.

A Few Notes

Many hams are reluctant to use open-wire line because of the problems in getting it into the shack from outdoors. One simple answer to this is to bring the line to the entrance — window sill, doorway, or whatever — and at that point attach 300-ohm twin-lead (which is insulated) and run the twin-lead in to the Transmatch. The fact that the two lines are not alike is of no concern because the load at the antenna side of the Transmatch is going to be some unknown value anyhow.

You may have read or heard that you must use coaxial lines in order to avoid TVI. Don't believe it. If you have a well-shielded transmitter and use a low-pass filter with it you won't have any harmonics coming out. Ask youself this simple question: "If there are harmonics, what difference can the kind of transmission line make?" The answer is, of course, "No difference."

One of the beauties in using a Transmatch is that the coaxial line between it and the rig can always be matched, and this matched section is where you put your low-pass filter. This eliminates any danger to the filter from excessive voltage or current caused by a mismatch.

One typical Novice question is "If my transmitter loads properly and I have no TVI problem, do I need more matching between the transmitter and antenna? I am using coax feed. What good would it do me to pay for the additional complexity of changing from band to band?" The answer to such a question depends on several factors. Is the harmonic attenuation — not TVI, but low-frequency harmonics — adequate? This could be a problem the Novice isn't aware of. As to the complexities of band changing, this will depend on how much the Novice desires to work other bands.

What we have tried to do in this article is to show the reader the problems and the recommended cure. There is nothing new about the multiband system using tuned feeders; it has been used for many years, and the interesting thing about it is that it is still the best multiband system. For further information it is recommended that the newcomer study *Understanding Amateur Radio* and *The ARRL Antenna Book* to gain a better insight as to how antennas work. This material was originally presented in *QST* by Lewis G. McCoy, W1ICP.

References

[1] McCoy, "A Complete Multiband Antenna System," *QST*, November 1967.

The Ultimate Transmatch

Most hams would like to own a Transmatch that could cover 80 through 10 meters, and work during coax-to-coax or balanced-lines conditions. Here is just such a unit. It will match the proverbial bedsprings, or any other nonresonant or resonant antenna — without plug-in coils or band switching — even on 160 meters.

Some amateurs assume that because they use coaxial feed lines they don't need a Transmatch. This can be an incorrect assumption.

The Harmonic Problem

A large number of hams have found to their sorrow that the harmonic suppression in their transmitters may leave much to be desired. The FCC issues many citations to Novices each year for second-harmonic violations.

A typical Novice station might consist of a transmitter and receiver, with direct coax feed to a trap dipole or vertical antenna. In a properly adjusted transmitter of typical design, often there is insufficient attenuation of the second-harmonic energy. This can mean that the second harmonic of the signal can reach the antenna and be radiated. What is required to eliminate or reduce the second harmonic, and higher-order harmonics, is more selectivity between the transmitter and the antenna. A Transmatch is an excellent aid in taking care of the harmonic problem.

The 50-Ohm-Load Problem

Still another reason for using a Transmatch is that nearly all manufacturers of transmitters design their rigs to work into a nonreactive, 50-ohm load. Any departure from this load impedance causes difficulty in tuning and loading the final-amplifier stage. It might be pertinent to point out that simply because a ham uses 50-ohm coax, it doesn't necessarily follow that he will have a 50-ohm load. Basically, in order to have a 50-ohm load when using 50-ohm coax, the coax must be terminated in a 50-ohm resistive impedance. In other words, the antenna impedance must be 50 ohms.

When the terminating impedance of the coaxial cable is other than 50 ohms, then the transmitter will be "looking" at some value other than 50 ohms. It is practically impossible to design a single antenna that will have an impedance of 50 ohms on all of the bands a ham might want to use. One answer to the problem is to employ a device that will "match" the unknown load to the 50-ohm impedance required by the transmitter. One such circuit or device is a Transmatch, simply an adjustable rf transformer that can match the unknown load presented by the transmitter end of the feed line to the required 50-ohm transmitter impedance.

The kW version of the Ultimate Transmatch. The knobs and dial counter are standard Millen components. The front bottom of the cabinet is tilted by means of two 2-inch (51 mm) standoff insulators used as feet.

Receiver Cross-Modulation

In addition to taking care of the problems just outlined, a Transmatch can serve another very useful function at the receiver. Some receivers are susceptible to what is known as cross-modulation, or front-end overloading, by strong nearby radio stations. This is particularly true on 160 or 80 meters when a broadcast station is nearby. The bc station overloads the front end of the communications receiver, causing "birdies" and other unwanted responses across the band. A Transmatch will eliminate or greatly reduce this problem in nearly all instances.

The Ultimate Transmatch

We shall describe two Transmatches — one for the Novice power limit, and another for the legal 2-kW PEP limit. We have found that many amateurs on the verge of taking their General, or higher-class licenses, would rather invest initially in a unit that will take care of all of their future needs.

Some years ago, a Transmatch was described that was designed for use with coaxial feed lines.[1] It was called "the 50-Ohm Transmatch." This unit handles mismatches on the order of 4:1. It can transform a load of about 200 ohms, or 12 ohms, to a 50-ohm impedance. The circuit of the Transmatch described in this article, Fig. 46, is similar, but with two notable exceptions. In place of a tapped, switched inductor, a variable inductor is used. (The idea for this innovation came from Al LaPlaca, K2DDK.) The variable inductor is a coil wound on an insulated form that can be rotated so that a movable wheel shorts out and grounds the unused portion of the coil. Using the roller inductor, along with the two variable capacitors, the Transmatch provides an almost unlimited matching range, plus the feature of 80- through 10-meter coverage without band switching. With the values shown in the units, it is even possible to add one fixed capacitor to obtain 160-meter coverage.

The other exception is the use of a 1:4 (unbalanced-to-balanced) balun transformer on the output side of the Transmatch, which permits the use of balanced feed lines. This means that a Transmatch can cover 160 through 10 meters (including the MARS frequencies). It can be used to match into coaxial lines, random-length end-fed wires, or balanced feeders, and can do the job without using switches.

The two units shown in the photographs underwent extensive tests as to efficiency, power-handling capabilities, and methods of adjustment. In coax-to-coax tests, power inputs and outputs through the Transmatch were carefully measured while using Bird Thruline wattmeters and an adjustable dummy load. As carefully as could be measured, and with indicated mismatches of up to 15:1, the Transmatches showed an efficiency of over 95 percent. This small loss in efficiency more than outweighs the usefulness of the device.

Many tests were made with the high-power version to check heating of the roller inductor and the balun. Under a key-down condition, with 1200 watts indicated power through the Transmatch, the transmitter was kept on for 15-minute periods. In one test, the measured rf current through the coil was in excess of 15 amperes. The roller inductor used in the unit is rated at 5 amperes, so this was considered a fairly rugged test. The coil did get warm, but not enough to be a cause for concern. Keep in mind that in regular amateur work, 15



Fig. 46 — Circuit diagram of the Ultimate Transmatch.
C1 — Split-stator variable, 250 pF per section; see text. For low-power version, E. F. Johnson type 16250; or similar, for high-power version, Millen type 16250, or similar.
C2 — 200-pF variable, for low power, E. F. Johnson type 167-12 or similar, for high power, Millen type 16520 0.171-inch (0.43 cm) spacing, 16520A, 0.077-inch (2 mm) spacing, or similar.
J1, J2 — Coax chassis fitting, type SO-239.
J3, J4, J5 — Feed through insulators.
L1 — Roller inductor, see text. If 160-meter operation is desired, total inductance should be 28 μH, E. F. Johnson type 229-203; otherwise, 18 μH is adequate, E. F. Johnson type 229-202.
T1 — 1-to-4 balun; see text for details, cores are Amidon type T-200-2.

minutes would be a ridiculous figure for continuous operation.[2] In cw and ssb operation, the duty cycle would be in terms of seconds or even fractions of seconds.

The balun used for balanced operation in the high-power unit was made up from three Amidon 1-kW cores — more about that in a moment. N1RM has made extensive checks on a single-core balun. It was found that a single core would easily handle 500 watts of power during severe mismatch conditions. Failure of the core, most likely due to saturation and heating, took place at the 700-watt level. In the high-power Transmatch shown here, three cores are used. They are wrapped with glass insulating tape and then wound with Teflon covered wire. Wire insulation material can be important because of the extremely high rf voltages that may be developed with some load conditions. In many tests of long duration, using up to 1400 watts output into a dummy load, it was almost impossible to detect any heating of the balun.

Bear in mind that the balun would only be needed if balanced-line operation were desired. For coax-to-coax or random-wire feed, the balun can be omitted.

Construction Information

A look at Fig. 46, at A, will show that the circuit is a very simple one. The input line from the transmitter is connected to the rotor of C1, a split-stator capacitor. This means that the capacitor must be insulated from the chassis, using standoff pillars, and from the panel by means of an insulated shaft coupler. The same is true for C2. In the kW unit shown, we have installed a power bridge. Construction details are not given here for the bridge because such a unit was described in detail in *QST*[3]. Also, many amateurs already have a Monimatch[4] or some other type of SWR indicator. An SWR bridge or matching indicator is needed in the 50-ohm line between the rig and the Transmatch to show when the Transmatch is correctly adjusted.

Layout of the components should follow the same arrangement shown in the photographs — C1 at the input side, the roller inductor at the center, and then C2. If a balun is going to be installed, allow enough room behind the roller coil for mounting the balun. In the two units shown, the cabinets are made up from aluminum sheet stock. If desired, a commercial chassis and cabinet can be used. In the low-power Transmatch, leave at least 1/2-inch (13 mm) spacing between the edges of the capacitors and any part of the chassis and cabinet. Allow 1-inch (25 mm) spacing in the kW unit.



Fig. 47 — At A, details for padding a low-value variable for C1 by installing a second variable, C3, the same value as the low-power unit C2. In the case of tuning 160 meters, using an inductor of 28 μH for L1, and 250 pF per section for C1, a fixed capacitor of 100 pF can be used at C3, Centralab type 850-100N, or similar. At B, details for connecting the bifilar windings on the balun are given. The ungrounded leads a and b are connected to J3 and J4, the feedthrough insulator terminals.

Balun Details

For the low-power Transmatch, a single toroid core will more than handle the power. Incidentally, the low-power unit was tested under all conditions at about 100 watts through the Transmatch. The



At the rear of the roller inductor is the 1:4 balun. The balun is set on top of a standoff insulator and is held in place with a piece of insulated board and a screw. The fixed capacitor mounted on the rear wall is the 160-meter unit. Both the variable capacitors and inductor are mounted on 1-inch (25 mm) high standoff insulators.



This is the low-power Transmatch. The salvaged roller inductor is mounted on the front panel, making use of the original mounting brackets.



Here is an inside view of the Ultimate Transmatch as built by Al LaPlaca, K2DDK, who came up the idea of using the roller inductor. The installation on top the right-hand capacitor is the homemade 160-meter switch and fixed loading capacitor.

power-handling capabilities of the units depend primarily on the plate spacing used for C1 and C2, aside from the balun requirements mentioned earlier. At the 100-watt level, a plate spacing of 0.03 inch (0.8 mm) is adequate. A 0.045-inch (1 mm) spacing should handle 500 watts. In the kW unit shown, C1 has a 0.077-inch (2 mm) spacing. While a 0.077-inch spacing capacitor wasn't tried at C2, such plate spacing should work at the kW level.

In making the low-power balun, wind two layers of Scotch brand electrical tape around the core before putting on the wire. This will provide extra insulation, and will protect the edges of the wire to prevent the enamel from being scraped away. Fig. 47, at B, shows a sketch of the winding. The winding consists of 10 bifilar turns of no. 14 Formvar insulated wire. Connected as shown, this will provide a 1:4, unbalanced-to-balanced configuration.

Three cores are needed in the high-power balun. Each core is covered with two layers of 3-M type 27 glass-cloth insulating tape. Next, the three cores are stacked, then covered with two more layers of the tape. The winding consists of 15 bifilar turns of either no. 12 or 14 insulated wire. The insulation should have a minimum rating of 1000 volts and can be either Teflon or vinyl-nylon (or any other suitable covering with a minimum voltage rating of 1000 volts).

In making the low-power Transmatch, a roller coil from a junked 40-meter ARC-5 transmitter was salvaged and installed in the unit. Many amateurs know other hams who have old ARC-5 gear, and these units are a good source for the roller coils. However, some hams may not be able to locate used ARC-5 transmitters, so we have included some information on sources of surplus and new roller inductors. There may be surplus outlets in your area worth investigating. Look for a roller coil that has a minimum inductance of 10 μH when used with C1 having a value of 200 pF per section. Such a combination will cover a low frequency of 3500 kHz. In the unit shown, in addition to the ARC-5 roller, we used a value of 100 pF per section for C1 and padded that capacitor with another of 200 pF (single section) in order to provide the required coverage. This added capacitor is shown in Fig. 47 at A. By using this approach, it is sometimes easier to save money then when trying to locate a 200-pF-per-section variable for C1. (Incidentally, you can use a variable at C1 of more than 200 pF per section for good coverage with the roller inductance specified above.)

An even better approach to get the required capacitance for C1, because it is better to maintain the symmetry of the circuit as shown in Fig. 46 at A, would be to gang two 200-pF variables to make up your own split-stator capacitor, with the desired plate spacing. (There may be some around, but we couldn't find any manufactured split-stator with the required plate spacing and capacitance). Still another approach would be to clip fixed transmitting-type mica capacitors across each section of C1 to obtain the required capacitance for use on 160 and 80.

Finding the Parts

As most hams are finding out, it is becoming more and more difficult to buy, or find, components for construction projects. Some searching was done, and the following information is worth passing on. Barry Electronics of New York City has informed us that they will fill any order for any amateur component at the manufacturer's current amateur net price. The parts specified in Fig. 46 are currently manufactured items. Also, Fair Radio Sales in Lima, OH has some surplus roller inductors and counter dials in stock. The roller-inductor catalog number is 5950-199-6469, and the counter dial is listed as RT-45. Also, Millen components can be purchased directly from G. R. Whitehouse, Amherst, NH 03031.

Using the Transmatch

One of the first considerations in using a setup for "coax-to-coax" is exactly how much, or how high an SWR can be tolerated. As has been pointed out, this Transmatch will handle *any* mismatch on the line. Without getting into a lot of details, a few observations about coaxial lines are in order. First, the higher the SWR, the greater the losses in coaxial lines. The amount of losses depends on the line construction and the *frequency* at which the line is used — the lower the frequency, the less will be the losses. For example, RG-8/U has a loss per 100 feet (30.48 m) of line of only 0.33 -dB at 3.5 MHz with an SWR of 1 (a matched condition). At 28 MHz, this same line would have a loss of slightly less than 1 dB. However, as the SWR rises, so do the losses. With an SWR of 10:1, for example, the additional losses at 3.5 MHz would amount to about 0.6 dB, or an overall loss of about 1 dB. For the same SWR at 28 MHz, the losses would be about 2.5 dB, or a total loss of about 3.5 dB. Since a loss of 3 dB would mean half of the ouput power from the rig would be dissipated in 100 feet (30.48 m) of line, one could easily tolerate the condition at 80 meters, but the losses would be prohibitive at 28 MHz. This means that the amateur would be wise to keep the match at the antenna feed point as close to 50 ohms as possible, and thereby keep the SWR low.

With trap or multiple dipoles, the SWR should be less than 5 to 1; the Transmatch would be ideal. Keep in mind that you must provide a load for a transceiver or amplifier that is close to 50 ohms. The Transmatch will provide a means.

In a coax-to-coax system, set both C1 and C2 at maximum capacitance (plates fully meshed), then feed enough power through the Transmatch to get a full-scale forward reading on your SWR indicator. It is always important to use low power when adjusting a Transmatch. Next, switch the SWR bridge to read reflected power, then run the roller inductor slowly through its range. At some point you will notice a sharp dip in the reflected-power reading. Once this point is reached you should adjust C1 and C2, with possibly a slight adjustment of the roller coil, to get a perfect match. Power can then be increased to the desired level. You'll find that several different settings of the Transmatch may provide a perfect match. The one to shoot for is the condition that requires the most capacitance at C1 and C2 for a matched condition.

If a random-length, end-fed antenna is used, merely connect the end of the antenna to terminal J3, Fig. 46B, and go through the adjustment procedures outlined above. It is helpful to have an earth ground connection on the Transmatch. Also, if possible, use an antenna length that comes out to a quarter wavelength, or odd multiple thereof. Such an antenna will be of low impedance, and will reduce the chances of high rf voltages appearing on the Transmatch or associated equipment.

If balanced feeders are used, the feeders should be connected to terminals J4 and J5 with a short jumper connected between terminals J3 and J4. Again, the previously discussed tune-up and adjustment procedures should be followed in setting up the Transmatch.

Some Other Thoughts

Some amateurs might be concerned about the amount of voltage that can be developed in a mismatched coaxial line. In a matched condition, with 1000 watts in a 50-ohm line, the rf voltage would be about 220 volts. With a standing-wave ratio or 20:1 (!), the increase in voltage would be 4-1/2 times, or approximately 990 volts. This however, is well within the rating of the RG-8/U cable.

This Transmatch should satisfy the needs of those hams who desire a multiband unit without switches or plug-in coils. Once the settings for the controls are determined, a chart can be made up for any given istallation. Band changing is then quickly done. This material was originally presented in *QST* by Lewis G. McCoy, W1ICP.

References

[1] "The 50-Ohmer Transmatch," *QST*, July 1961.

[2] [Editor's Note: However, teletype operation would be continuous (to say nothing of those long-winded a-m operators!).]

[3] "In-Line RF Power Metering," *QST*, December 1969. (See chapter 4.)

[4] *Understanding Amateur Radio*, p. 209.

Build a Baby Ultimate

Got a match? Not a classic "match," but one between the antenna and your QRP rig may be what you need. If so, this article is for you.

Nobody needs or wants a 50-pound Transmatch during a QRP junket to a favorite lake, campsite or other distant location. The entire point of QRP operation is negated when the low-power station can be held on the palm of one's hand, but the accessory gear needs to be transported by hand truck to the car, airport or whatever! Operators who prefer to use a random-length wire antenna for field work will require a matching network between the 50-ohm transmitter output and the end of the antenna, whose characteristic impedance can be anything from a few ohms to a couple of thousand. For low-power work (25 watts or less) it doesn't take a big Transmatch to do the job, and some novel ideas can be applied to make the matcher cover 80 through 10 meters without a roller inductor or messy tapped-coil switching arrangement. This article shows some tricks that can be applied to meet that goal.

The heart of the Baby Transmatch is the half-toroid variable inductor. It is the by-product of a few "skull sessions" between Andy Pfieffer, K1KLO, and the writer. Both amateurs are QRP "freaks," and finding the proper mechanical technique for building a miniature panel-operated variable inductor of reasonable inductance range was challenging and productive. The machine-shop skill and impagination of K1KLO can be realized when viewing the accompanying close-up photograph. Early efforts along this line provided a slider type of full-toroid variable inductor (rheostat style), and dismal results were had: the inductor Q was very low, approximately 5, as a result of the shorted-turn syndrome. Finally, a powdered-iron Toroid core of Q1 material, 1-inch (25 mm) diameter, with 3/16 by 3/16-inch (5mm by 5mm) walls, was sawed in half and cemented to a plastic arm. The arm was glued to the shaft of the control so that it would enable the operator to change the coil inductance by moving the semicircular toroid section in and out of the coil.

Exterior view of the Baby Ultimate. Dymo tape labels are used to identify the controls.



Interior view of the matcher showing the K1KLO variable inductor (lower center).

The coil in this unit was air wound, then cemented to a semicircular piece of plastic which is affixed to a plastic disk of 1-1/2-inch (38 mm) diameter. The overall coil-and-plastic assembly is glued to the 3/8-inch (10 mm) bushing and 1/4-inch (6 mm) diameter control shaft. Although all of the metal work was done from scratch on a lathe, an old volume control or rheostat bushing and shaft can be modified to perform the function required. All that's needed here is some amateur ingenuity! The tuning range of the variable inductor is 3 to 9 μH, and the unloaded Q was measured as 150 at 7.9 MHz.

It is reasonable to conclude that the K1KLO "giz," as he calls it, could be made to cover a greater inductance range by making the coil bigger in ID and cementing both halves of the toroid core together — one atop the other — to provide greater permeability overall. Ferrite material is unsuitable for this component because of the hardness of ferrite. Without special cutting tools the latter will resist all efforts to saw through it. One-half of an Amidon 1-kW balun-kit, powdered-iron toroid should be excellent for larger units of this kind.

Other Circuit Features

As is shown in Fig. 48A, S1 is used to switch an additional variable inductor (L1) in parallel with the K1KLO unit, L2. This provides a lower minimum-inductance amount for operaion on 15 and 10 meters.

Fig. 48B illustrates some variations which will extend the Transmatch range down to 80 meters. The model shown photographically was designed for 40 through 10 meters. In the second example, S2 and L3 have been added to increase the total inductance to permit 80-meter matching. Also, C1 has been changed to a



Fig. 48 — The diagram at A is for the 40- through 10-meter Transmatch. At B, a suggested circuit for coverage from 80 through 10 meters.

C1 — Dual-section air variable (Miller 2109, J. W. Miller Co., 19070 Reyes Ave., Compton, CA 90224). See text.
C2 — Calectro or Archer single-section miniature 365-pF variable.
J1-J3, incl. — Phono jack.
L1 — 3.1-to 4.8-μH slug-tuned inductor (Miller 4504 with red core).
L2 — See text. Contains 32 turns of no. 22 enam. wire, air wound, 7/16-inch (11 mm) OD.
L3 — 5.5-to 8.6-μH slug-tuned inductor (Miller 4505 with red core.)
S1, S2 — Spdt slide or toggle switch.

two-section 365-pF, bc-style variable, also for the same reason. A dual 365-pF capacitor can be used for the circuit at A, but the tuning rate will be much sharper than with the unit specified.

Three phono jacks are used for external connections. The first photograph shows a pair of clip leads which have been soldered to two phono plugs. These are used for making connections to a single-wire antenna and ground.

The slug screw of L1 protrudes from the top panel of the small plastic meter case. This feature enables the operator to have additional control of the overall inductance amount during operation on 15 or 10 meters. All internal ground connections are brought to a common point — J3, which has both of its terminals joined.

The "Ultimate" design is based on one which was popularized by W1ICP when he described in *QST* a 1-kW version of the circuit.[1] The network will match a wide range of impedances, but it should be pointed out that this circuit is not capable of providing much (if any) harmonic attenuation. Examination of the circuit will show that the network is basically a high-pass type.

Building the Transmatch

A 1-1/2 × 2-3/4 × 4-inch (38 mm × 70 mm × 102 mm) plastic meter style of case is used to house the Transmatch. The box used by the writer was made by RCA as an enclosure for a 9-volt regulated power-supply kit. Similar boxes are available at Radio Shack and other parts stores, but most have a metal cover. If the latter are used, it will be necessary for the builder to isolate the rotors of C1 and C2 from the metal plate. Adhesive-backed plastic feet are affixed to the bottom of the case. They will keep it from moving about on the operating table.

Using the Transmatch

When matching the 50-ohm transmitter to a given antenna (fed with coaxial line or single wire in nature), an SWR indicator will be necessary between the transmitter and the Transmatch.[2] C1, C2 and L2 are adjusted one at a time for the lowest reflected-power reading on the meter. There will be interaction between the controls, so it will be necessary to go over them several times to effect an SWR of 1.

Some difficulty may be encountered while working with a voltage-fed (high impedance) wire antenna. The symptom is one of hand capacitance affecting the SWR reading. In such instances the tune-and-try method will be required, moving the hands away from the box after each adjustment. For this reason the builder may wish to house the circuit in a metal box and use insulating shaft couplings on C1, C2 and L2. Of course, this will make the unit somewhat larger.

The writer used this Transmatch for two weeks in October 1975 while on a QRP sortie to Barbados (8P6EU). Maximum power used was 20 watts output, and minimum power was 2 watts ouput. The 40-, 20- and 15-meter bands were used, and all manner of antennas (end fed and coaxially fed) were employed. In all cases the SWR could be set for a 1:1 condition. Insertion loss through the Transmatch was measured at 14 MHz while delivering 20 watts to a test dummy load. The loss was approximately 0.1 dB at a matched condition. No heating of the components was noted.

One final word is in order. Always use the maximum possible amount of capacitance at C2 when adjusting the Transmatch for an SWR of 1. There can be several settings of C1, C2 and L2 which will provide a match. Best efficiency will always occur with maximum usable C at C2, and this is true of all variations of the Ultimate Transmatch.

If you're a QRP enthusiast, this matcher should be part of your setup when 50-ohm antennas aren't used. It is lightweight, small of size, and can be tucked away in the XYL's handbag when enroute, if need be! This material was originally presented in *QST* by Doug DeMaw, W1FB.

References

[1] McCoy, "The Ultimate Transmatch," *QST*, July 1970. (Included in this chapter.)

[2] DeMaw, "A QRP Man's RF Power Meter," *QST*, June 1973, p. 13.

Simple Broadband Matching Networks

This article gives complete details on constructing broadband matching transformers for ratios of 4:1, 6:1, 9:1 and 16:1.

Are you looking for a physically small DX antenna? To obtain low-angle radiation on 80 and 160 meters, many amateurs use vertical antennas. Horizontal antennas would have to be at elevations of a half-wavelength or greater to be comparable. Suitable supporting structures are beyond the reach of most amateurs at these lower-frequency bands. Quarter-wavelength verticals require some 60 feet (18.29 m) on 80 meters and 120 feet (36.58 m) on 160 meters — still very tall structures! However, short verticals over a good image plane have been shown theoretically[1] and experimentally[2] to perform practically as well as their full-size quarter-wavelength counterparts. The only problems are very low input impedances and narrower bandwidths.

This paper describes broadband matching networks which can efficiently match 50-ohm coaxial cable to verticals as short as 1/25 wavelength. Also included is information on short vertical antenna designs incorporating large top hats in order to improve bandwidth, such as a very short 40-meter vertical and a dual-band 80- and 160-meter short vertical with remote switching. In addition, loading coils using powdered-iron toroidal cores are discussed.

Broadband Matching Transformers

Broadband transformers have been widely used because of their inherent bandwidth ratios (as high as 20,000:1) from a few tens of kilohertz to over a thousand megahertz. This is possible because of the transmission-line nature of the windings. The interwinding capacitance is a component of the characteristic impedance and therefore, unlike the conventional transformer, forms no resonances which seriously limit the bandwidth.[3] At low frequencies, where interwinding capacitances can be neglected, these transformers are similar in operation to the conventional transformer. The main difference (and a very important one from a power standpoint) is that the windings tend to cancel out the induced flux in the core. Thus, high-permeability ferrite cores, which are not only highly nonlinear but also suffer serious damage even at flux levels as low as 200 to 500 gauss, can be used. This greatly extends the low-frequency range of performance. Since higher permeability also permits fewer turns at the lower frequencies, high-frequency performance is also improved since the upper cutoff is determined mainly from transmission-line considerations. At the high-frequency cutoff, the effect of the core is negligible.

Connie, W2FMI's better half, is making use of the shade under Jerry's 40-meter umbrella antenna. It is hoped that Jerry warns her about touching the antenna when he is running high power!

The applications of broadband transformers to antennas and broadband circuits have been covered by a number of authors.[4,5] This paper extends the application of these transformers to include the operation of short ground-mounted vertical antennas with impedances as low as 3 to 4 ohms. Further design considerations illustrate variable matches to vertical antennas having impedances even greater than 35 ohms.

Bifilar matching transformers for ground-mounted verticals lend themselves to unbalanced operation. That is, both input and output terminals can have a common ground connection. This eliminates the third magnetizing winding required in balanced-to-unbalanced (balun) operation. By adding third and fourth windings, as well as tapping windings at appropriate points, various combinations of broadband matching can be obtained. Fig. 49 shows a 4:1 unbalanced-to-balanced configuration. This transformer can be used with verticals of 12.5 or 200 ohms when using 50-ohm cable. No. 14 wire can be used and it will easily handle 1000 watts of power. By tapping at points 1/4, 1/2 and 3/4 of the way along the top winding, ratios of approximately 1.5:1, 2:1, and 3:1 can also be obtained. It should be noted that one of the wires was covered with vinyl electrical tape in order to prevent voltage breakdown between the windings. This was necessary when a step-up ratio was used at high power to match antennas with impedances greater than 50 ohms.

Fig. 50 shows a transformer with four windings, permitting wide-band matching ratios as high as 16:1. A picture shows a four-winding transformer with taps at 4:1, 6:1, 9:1 and 16:1. In tracing the current flow in the windings when using the 16:1 tap, one sees that the top three windings carry the same current. The bottom winding, in order to maintain the proper potentials, sustains a current three times greater. The bottom current cancels out the core flux due to the other three windings. If this transformer is used to match into low impedances, like 3 to 4 ohms, the current in the bottom winding can be as high as 15 amperes if the high side of the transformer is fed with 50-ohm cable handling a kilowatt of power. If one needs a 16:1 match like this at high power, then cascading two 4:1 transformers is recommended. In this case, the transformer at the lowest impedance side only requires each winding to handle 7.5 A. Thus even no. 14 wire would suffice in this application.



A 4-winding, wideband transformer (with front cover removed) with connections made for matching ratios of 4:1, 6:1, 9:1, and 16:1. The 6:1 ratio is the top coaxial connector and, from left to right, 16:1, 9:1, and 4:1 are the others. There are 10 (quadrifilar) turns of no. 14 enameled wire on a Q1, 2.5 inch (64 mm) ferrite core.



Fig. 49 — Four-to-one broadband bifilar transformer. Upper winding can be tapped at appropriate points to obtain other ratios such as 1.5:1, 2:1 and 3:1.



Fig. 50 — Four-winding, broadband, variable impedance transformer. Connections a, b and c can be placed at appropriate points to yield various ratios from 1.5:1 to 16:1.



Fig. 51 — Final design and bandwidth characteristic of a short 40-meter vertical having an input impedance of 3.5 ohms and utilizing a commercial beach umbrella. This antenna established its worth as a prototype for the lower frequencies.

The popular cores used in these applications are 2.5 inch (64 mm) OD ferrites[6] of Q1 and Q2 material and powdered iron cores,[7] of 2-inch (51 mm) OD. The permeabilities of these cores, μ, are nominally 125, 40 and 10, respectively. Powdered iron cores of permeabilities 8 and 25 are also available.

In all cases these cores can be made to operate over the 10- to 160-meter bands with full power capability and very low loss. The main difference in their design is that lower permeability cores require more turns at the lower frequencies. For example, Q1 material required 10 turns to cover the 160-meter band, Q2 required 12 turns, and powdered iron ($\mu = 10$) required 14 turns. Since the more common powdered-iron core is generally smaller in diameter and requires more turns because of lower permeability, higher ratios are sometimes difficult to obtain because of physical limitations. Although most of the author's experimentation on these transformers was done on the 40-, 80- and 160-meter bands, the results indicated that they should operate on the higher bands equally well. When working with low impedance levels, unwanted parasitic inductances come into play, particularly on 14 MHz and above. In this case lead lengths should be kept to a minimum.

All the results obtained by the author have shown that the transformers can be used to match a variety of loads and impedance ratios, they can be used over many bands, and that they exhibit negligible loss in operation. More importantly, the core materials are readily available and low in cost.

A Short Vertical Antenna Design

These transformers permit efficient matching to impedances as low as 3 to 4 ohms. This means, with some top-hat loading, antennas could be 4 to 5 feet (1.22 to 1.52 m) tall on 40, 8 to 10 feet (2.44 to 3.05 m) on 80, and 16 to 20 feet (4.88 to 6.10 m) on 160 meters. With the capability of tapping off any portion of the transformer windings, thus providing variable matching, the heights of these antennas can be increased at will depending upon the bandwidth desired.



Fig. 52 — The 80- and 160-meter dual-band vertical system. The remotely switched matching network is described in the text. Not shown are three sets of polypropylene guy ropes at heights of about 9, 18 and 26 feet (2.74, 5.49 and 7.92 m).



Fig. 53 — The remotely switched matching network for the 80- and 160-meter dual-band vertical antenna. The indicated switch positions are for 160-meter operation.
S1 — Dpdt antenna relay.
J1 — Coaxial connector, chassis type.
L — Load coil for 160 meters, 22-1/2 turns, no. 14 wire on 4 cores of 2-inch (51 mm) OD powdered-iron, permeability of 10 (Amidon T-200-2).
T — Broadband transformer (see text).

The first short vertical designed by the author was brought about by a trip to a local shopping center. The author saw a beach unbrella that had about the right proportions one would use in designing a short 40-meter vertical. The "antenna" was purchased (at a nominal price) and a 14-turn coil, connected across an insulated section about three feet (0.91 m) from the ground, was used to tune the vertical to resonance. The measured input impedance was 3.5 ohms and was matched easily to 50-Ω line with a 16:1 transformer. Fig. 51 shows the final design and the bandwidth characteristic. Several months of operation on 40 meters verified the outstanding capability of this short vertical antenna (with an extensive radial system) and established its worth as a prototype for the lower frequencies. A further study showed that the 6-foot (1.83 m) diameter top-section was about the equivalent of a 4-1/2-foot (1.37 m) diameter solid disk.

A Dual-Band 160- and 80-Meter System

The antenna shown in Fig. 52 is a dual-band design using a remotely switched matching network (see photograph) which not only changed a tap on a broadband transformer from 4:1 to 9:1, but also introduced a powdered-iron base-loading coil for 160-meter operation.

The circuit diagram for the remote matching network is shown in Fig. 53. The loading coil was made with four powdered-iron (μ = 10, 2-inch [51 mm] OD) cores. They were first wrapped individually with several layers of vinyl electrical tape before being combined and wrapped again. The necessary inductance was obtained with 22-1/2 turns. A slight adjustment of the loading coil and the height of the antenna was found necessary in order to put the minimum SWR at 1812 kHz. In general, a 1-foot (0.31 m) change in height of the antenna changes the 80-meter resonance by 60 kHz and the 160-meter resonance by 15 kHz. A change of 1/2 turn on the



Bottom view of the matching network for the dual-band 80- and 160-meter vertical. The loading coil is on the right and the trifilar 4:1 and 9:1 matching transformer on the left. The dpdt 24-volt antenna relay switches in or out the loading coil and changes the taps on the transformer to the appropriate ratio. The enclosure is the conventional 4 X 5 X 6-inch (102 mm X 127 mm X 152 mm) aluminum Minibox.



The broadband bifilar transformer shown has 12 bifilar turns, no. 14 wire, on a ferrite (Q1 material, 2.5 inch [64 mm] OD) core. Taps are also placed at 3, 6, and 9 turns, thus yielding ratios of 1.5:1, 2:1, 3:1 and 4:1. This transformer has a connection at the 1.5:1 ratio tap. Extra insulation was provided for the enameled wire in order to prevent voltage breakdown when matching into loads greater than 50 ohms.

powdered-iron core coil changes the 160-meter resonance by about 50 kHz. It should be noted that the windings had extra insulation (about one layer of vinyl tape) added on the inside part of the windings in order to prevent breakdown between them.

Low-permeability ferrite material Q2 (μ = 40, but still four times larger than the powdered iron material) was also investigated for use as a core for a 160-meter loading inductance. It was hoped that with several stacked cores of this material, the flux density would be reduced to a level where nonlinearities and permanent damage could be avoided. Two cores and about 10 turns of wire were used. The result was negative. Large changes in inductance were noted on voice peaks by the sudden large changes in the SWR. Also, small but permanent changes in the SWR were observed, indicating permanent damage. In contrast to ferrite, powdered iron maintains its linearity at high flux densities and suffers no permanent damage. As noted above, four cores of permeability 10, and 22-1/2 turns, provided the proper inductance (approx. 30 μH). The loss in this coil was about equal to the air-wound coil (33 turns, 6 tpi, no. 12 wire, 2-1/2-inch [64 mm] OD). Two stacked powdered-iron cores of permeability 25 were also investigated. This arrangement required about 17 turns, but was rejected because the loss, which was mainly in the two cores, went up to 3 ohms. This is certainly intolerable since it is of the order of magnitude of the radiation resistance of the very short vertical.

Concluding Remarks

The predominant characteristic of the short antenna is probably its very low value of radiation resistance. One must be careful of excessive ground and ohmic losses in coils and matching networks. A good image plane can eliminate the ground-loss factor. The application of a top hat eases the problem somewhat because it increases the effective length and thus the radiation resistance. The radiation resistance can be increased five-fold[8] by resorting to complete top-hat loading of a vertical. Combinations of top-hat and inductive loading can be used depending upon the radiator height and the bandwidth desired. One can also resort to a short folded unipole. With these combinations at his disposal, the designer is left with the problem of efficiently matching his transmission line to various impedance levels. The wide-band transmission-line transformer can provide the answer. It is capable of operating very efficiently over a wide range of impedances and impedance ratios.

The author would like to acknowledge the generosity of the following companies who supplied cores and information for the experiments: Indiana General Corp., Amidon Associates, and the Arnold Engineering Co.

Finally, the author would like to thank his colleague Mort Fagen, WA2EIT, for his encouragement and discussions of the antenna papers the author has written. This material was originally presented in *QST* by Jerry Sevick, W2FMI.

References

[1] King, *The Theory of Linear Antennas*, Harvard University Press, Cambridge, MA, 1956.
[2] Sevick, "The W2FMI Ground-Mounted Short Vertical," *QST*, March 1973. (See chapter 1.)
[3] Ruthroff, "Some Broad-Band Transformers," *Proc. IRE*, Vol. 47, p. 137, August 1959.
[4] Turrin, "Application of Broadband Balun Transformers," *QST*, April 1969.
[5] Krauss and Allen, "Designing Toroidal Transformers to Optimize Wideband Performance," *Electronics*, August 16, 1973.
[6] Indiana General Corp., Electronics Div., Keasby, NJ 08832.
[7] Amidon Associates, 12033 Otsego Street, North Hollywood, CA 91607; The Arnold Engineering Co., Marengo, IL.
[8] See reference 2.

An RF-Sensed Antenna Changeover Relay

Flick of the switch, sir? Not with this system — it's automatic!

One subject that can be confusing for the newcomer to Amateur Radio is that of antenna-changeover systems. Several systems have been devised over the years and most can be classified into three or four main categories. Before delving into a discussion on these systems, a brief look at the simplest method of all might be in order, that is, no antenna changeover at all. With this setup two separate antennas are used, one for the transmitter and one for the receiver. This system is impractical for the most part since duplicate antennas would be required for each band of operation. There are instances, however, when separate antennas with different directive patterns can be used to an advantage, as in the case of specialized receiving antennas. Generally speaking, most stations use the same antenna for transmit and receiver purposes, so this is more the exception than the rule.

Several antenna-changeover systems, designed to transfer a single antenna from the receiver to the transmitter, are shown in Fig. 54. At A, a manual switch is used to transfer the antenna connection. This scheme is simple and works well, but is not without several drawbacks. Good-quality, high-power rf switches are often costly and




The inner layout of the antenna-changeover relay. Wiring or placement of circuit board and other components is not critical.



Fig. 54 — Several different antenna-changeover systems in block diagram form.

hard to locate and, of course, the operator is required to switch manually from receive to transmit.

One of these problems was eliminated with the advent of the coaxial relay. These relays were, in most cases, mounted external to the transmitter and receiver with connecting cables running to and from the unit, as shown in Fig. 54B. Many of these relays were rated for a kilowatt a-m signal, and maintained the 50-ohm line impedance. The voltage needed for the relay field was switched on or off with a low-powered toggle or foot switch. Alternatively, the transmit-receive switch might be located on the front panel of the transmitter with control voltage or a normally open or closed circuit available at a socket on the rear apron. Several extra sets of relay contacts were usually furnished with the relay to perform various functions, including that of muting the station receiver during transmit periods. Although this system of antenna transfer represented an improvement over the previous setup, it was still necessary for the operator to switch the antenna manually via the relay-control switch.

It's been said that laziness is the mother of invention and so it seemed natural that a more automatic system be developed. The relatively modern scheme at Fig. 54C has the transfer relay built into the transmitter. This system is quite popular and is used by most commercial manufacturers of amateur equipment that offer a separate transmitter and receiver. When the key is pressed the relay activates automatically and switches the antenna to the transmitter. A variable-length delay is usually included to hold the relay closed, thereby keeping the antenna connected to the transmitter during code characters. After the last group of code characters is sent, the relay will remain closed for a second or two — the amount of time controllable. When the relay deactivates, the antenna is reconnected to the receiver.

Unfortunately, some amateurs who build their own equipment or purchase transmitters and receivers of different manufacture, sometimes resort to switching methods A or B. These setups, of course, do not include the automatic features of system C. The circuit described here and shown in simplified form in Fig. 54D was designed with this in mind. Basically, this system detects the presence of rf at the output of the transmitter and immediately breaks the antenna connection to the receiver. At the same time the antenna connection to the transmitter is made. One of the features of this system is that no modifications to either the transmitter or receiver are required.

Circuit Description

R1 of Fig. 55 serves as an rf-voltage divider to permit the circuit to be used with transmitters of various power-output amounts. Rf energy is routed through C1 to the base of broadband amplifier Q1. The amplified hf-band energy is supplied to a voltage-doubler (D1 and D2) through a broadband toroidal step-down transformer, T1. The rectified rf voltage at the output of D1 and D2 is filtered by means of RFC2, C5 and C6. This prevents unwanted rf from reaching U1 and affecting its performance.

C6, R7 and R6 comprise a timing network (variable) which governs the hold-in time of the relay, K1. The smaller the resistance amount at R6, the shorter will be the time delay.

U1 functions as an inverting amplifier. When the input dc voltage at pin 2 increases, the output dc voltage at pin 6 decreases. The output voltage causes the base of relay driver Q2 to be forward biased negatively when it drops below approximately 1.4 volts. Diodes D5 and D6, by virtue of their combined barrier voltages (0.7 V each), establish the 1.4-V fixed bias level. Without the diodes, Q2 would conduct sufficiently to prevent the relay from dropping out during no-signal periods. D4 is used to suppress transients caused by the field coil of K1. When no rectified rf reaches U1, Q2 is cut off because of the high positive base voltage it receives from U1, and the relay contacts to the transmitter are open.


BROADBAND AMPLIFIER
J1
TRANS.
J2
ANT.
K1B
J3
REC.
47k
*
R1
5000
SENSI-TIVITY
C1
0.01
R2
1000
R3
5600
R4
100
C3
39
Q1
2N2222A
12.5
12.5
1.8
1.8
1.2
1.4
R5
1000
T1
C4
0.1
D2
1N914
D1
1N914
RFC1
C2
0.1
+
12.5V
-
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS; k = 1000, M = 1 000 000
▭ = DC VOLTAGE WITH NO SIGNAL INPUT
◯ = DC VOLTAGE WITH SIGNAL INPUT
* = OMIT RESISTOR FOR POWER LEVELS UNDER 100 WATTS.
0.4
1.8
C7
0.01
D3
1N914
U1
741
0
2.5
RFC2
C5
0.01
C6
2μF
50V
R6
2.5M
DELAY
R7
680k
+12.5V
Q2
2N4037
12.5
1.5
12.5
2.5
SWITCH
D5
1N914
D6
1N914
D4
1N914
K1A
12.5V

Fig. 55 — Schematic diagram of the rf-sensed antenna-changeover relay. All resistors are half-watt composition type. Capacitors are disk-ceramic unless noted otherwise. Component numbers not appearing in the parts list are for identification purposes only.

J1, J2 — Connector, SO-239.
J3 — Connector, phono-type.
K1 — Dpdt relay, 5-ampere contacts, 12-volt field.
R1 — Linear potentiometer, 5000 ohms.
R2 — Linear potentiometer, 2.5 megohms.
RFC1, RFC2 — Rf choke, 42 turns no. 28 enam. wire on an Amidon FT-50-43 core.
T1 — Broadband transformer. Primary: 25 turns no. 28 enam. wire on an Amidon FT-50-43 core; secondary: 5 turns no. 28 enam. wire wound over primary winding.
U1 — Op amp, 741.


1N914
2N4037
TO RELAY
2μF +
50V
680k
1N914
E
B
C
U1
8
1
R6
RFC 2
0.01μF
1N914
0.01μF
J
1N914
39pF
100Ω
1000Ω
R1
1N914
T1
0.1μF
E
B
C
1000Ω
5600Ω
0.01μF
2N2222A
TO RELAY AND J2
RFC 1
0.1ΩF
J = JUMPER

Fig. 56 — Circuit-board etching pattern for the changeover relay. The pattern is shown at actual size from the foil side of the board with gray areas representing copper. Decimal-value numbers alone represent capacitance in microfarads. Whole-number values with no units represent resistances in ohms; k = 1000. J = wire jumper. All components are mounted on the nonfoil side of the board. K indicates the cathode of a diode.

Construction

In Fig. 56 is a suggested printed-circuit board layout showing the foil pattern and parts placement. R1 and R6 may be circuit-board-mounted potentiometers if the builder desires, as the board layout was designed to accommodate such units. Potentiometers of this type are entirely suitable if the builder does not anticipate frequent changes in power levels and length of delay, as these controls must be readjusted for such changes. If the builder is interested in having access to these controls, panel-mounted potentiometers can be used at the front apron, in which case wires will have to be run from the circuit board to the controls.

Our finished model was housed in a 5 × 3 × 2-inch (127 mm × 76 mm × 51 mm) aluminum Minibox. R1 and R6 were mounted on the front panel and Kurz-Kasch knobs were placed on the control shafts to dress up the appearance of the finished product. D4 is attached directly to the relay terminals. The rear panel supports the terminals for the transmitter, antenna, receiver antenna and power supply. SO-239 connectors were used for the transmitter and antenna connections, and a phono connector was employed for the receiver antenna. Any type of connectors may be substituted to match those used in the builder's station. The power-supply lead is brought out through a feedthrough capacitor. This type of feedthrough is not necessary; a simple feedthrough insulator or wire could be used instead. In our case, the capacitor lead served as a convenient tie point during preliminary testing of the unit.

Operation

Connect the antenna, transmitter, receiver antenna lead and the power-supply connections to the appropriate terminals. Set R6, the time-delay control, to its minimum delay position (ccw) and the sensitivity control to its midrotation position. While keying the transmitter, decrease the setting of the sensitivity control to a point just above that where the transmitter no longer makes the relay energize. Once this has been set, it may be left in that position until a moderate change in power level has been made. The delay control should then be adjusted for the length of delay desired. The circuit shown has been tested from 1.8 to 30 MHz and at dc power input levels up to and including 1000 watts. This material was originally presented in *QST* by Doug DeMaw, W1FB, and Jay Rusgrove, W1VD.

Measuring Antenna Gain with Amateur Methods

Beat the cost of expensive test gear. Make your antenna measurements using this unique method! A VU meter, a handful of parts and this simple explanation are all you need.

Several excellent articles have been written about the techniques used at vhf conferences to measure antenna gains. Two such articles in particular, by Clark[1] and Knadle,[2] suggest very good antenna-range procedures. Both describe techniques which, if properly applied, will produce accurate relative antenna-gain data (in decibels) for vhf-uhf antennas.

However, these antenna range-measurement systems require equipment most amateurs lack — ratiometers, precisely calibrated attenuators, or at least specialized detectors and commercial grade audio or VSWR meters. Moreover, setting up a near-field antenna range is a tricky business in itself. One text[3] simply warns amateurs not to expect accurate antenna-gain measurements if they try it! The problem, of course, is that outdoor antenna ranges invite all sorts of error-causing reflections from various objects, not the least of them being the earth itself.

Ground reflections alone can completely invalidate the results on an otherwise good antenna range. At the 1973 West Coast VHF Conference, for instance, the author's 8-element quagi for 432 MHz[4] was measured at precisely the same gain as a well-built 15-element Yagi more than twice its size, despite the fact (established in other tests) that the bigger antenna had 2 to 3 dB more actual gain! The problem was that, even with the sophisticated measuring equipment in use, ground reflections were distorting the results. The best "gain" indication came with both antennas within a few inches of the earth, and the smaller quagi with its lower Q didn't mind the detuning effects of the earth's proximity as much as the bigger and higher Q array.

With results like that, wild claims are sometimes made for one vhf antenna or another. And the claims may be even wilder on the hf bands, where an amateur may well be told his signal is two of three S units louder than another ham's signal when the actual gain difference between the two antennas is insignificant. The ham who "won " the comparison by several S units, of course, is likely to go away thinking his antenna is 12 or 18 dB better than the other guy's, since S meters are supposed to show 6-dB signal difference per S point.



For the antenna gain-measurement technique described here, two identical masts in a clear area (here a southern California beach) are required. With the test and reference antennas at equal heights and fed with identical feed lines, the signal produced by the two antennas is compared by rapid and repeated switching. Here an 8-element quagi is tested against an 11-element Yagi that has been modified for quagi-type drive. The modified Yagi delivers 3 dB more gain than the conventional version, but 2 dB less than the quagi.

A Better Way

This article describes a more reliable and valid way to estimate antenna gain, and without expensive or hard-to-find test equipment. The technique requires only this equipment: a cooperative nearby ham with a transmitter capable of generating a few watts of steady carrier, a receiver whose agc can be turned off, an ordinary audio VU meter, and some antennas to measure.

The technique is nothing more than a more rigorous application of the test procedure radio amateurs have always used when they asked for "comparison" signal reports. It takes advantage of the fact that audio VU meters, unlike S meters, are calibrated directly and fairly accurately in decibels, with easy readout down to fractions of a dB. And with the agc turned off, most receivers will closely reproduce changes in the signal input at the antenna terminals with corresponding changes in audio output until they are badly overloaded.

This means that a nearby amateur's signal transmitted at a reasonably low power level can be used to compare the gain of various antennas by rapidly switching back and forth between them and averaging the results.

The only trick is to use a "test signal" that is coming from a point source — not a signal that is being reflected from surrounding objects. If your test antennas can "see" the signal source a few miles away and are well clear of nearby objects (and clear of the earth itself), valid results should be attainable if the procedures below are followed.

The author has spent many hours working with both local antenna ranges covering a few dozen wavelengths, and on-the-air signals from local stations. It is apparent that ground reflections and other



Fig. 57 — The audio VU-meter system for antenna gain measurements.



Fig. 58 — This small box houses all the test equipment required for antenna gain measurements using the technique described here. The front-panel audio VU meter is calibrated directly in decibels, with readout possible to about 0.2 dB in the most expanded part of the scale. Not visible are the meter level potentiometer (on rear), and small speaker which is mounted downward.

such error sources are less serious problems when a steady, on-the-air carrier a few miles away — and not a local signal a few dozen wavelengths away — is the signal source.

Test Procedures

Here's how the procedure works at vhf (at hf, it's a little more complicated because antennas are larger, as we'll see later):

1) Build an audio VU metering circuit like the one shown in the photo and Fig. 57. All parts should be readily available anywhere that consumer electronics parts are sold. The speaker and meter-gain control are handy to have when the receiver itself is located some distance away from the antenna test site, but they aren't absolutely essential.

2) Get a nearby amateur (perhaps one to five miles away) to generate a steady carrier into an antenna of the same polarization as your test antennas. A small beam pointed toward your test site is much better than a dipole or groundplane antenna because it is less likely to invite reflection error. A beam pointed somewhere else is worst of all!

3) Two of the antennas to be tested should be set up side by side, with identical lengths of feed line going to a coaxial relay or well-isolated switch. The two supporting poles should be high enough that the test antennas are at least two wavelengths above ground (13 feet [3.96 m] or more at 2 meters) and clear of nearby obstructions. To minimize interaction between the two antennas, the two masts should also be at least one to two wavelengths apart and standing side by side in relation to the signal source.

4) Make sure you can raise and lower your antennas and move them from side to side by at least a full wavelength or so (81 inches [2.06 m] at 2 meters) without the indicated signal varying more than about 1 dB. If you can't do that, you probably have reflection problems that will have to be solved before you can make valid readings. If this is the case, try different sites until you do achieve nonspotty reception.

5) Check the receiver agc to be sure it is off; then rapidly switch between the two antennas and record the difference in decibels. Do it several times and calculate the average figure (the mean, for statisticians).

6) Next reverse the two antennas. Put antenna no. 1 on mast no. 2 and attach it to feed line no. 2. Move antenna no. 2 over to mast no. 1 and feed line no. 1. Do not eliminate this step and expect valid results.

Now run the test again. If there are more than very slight differences from the previous test, one antenna or the other is seeing some obstruction or reflection source. Your site isn't clear enough for good results; try a different one.

Since this test procedure requires only receiving, there is no reason not to perform it somewhere other than at home — anywhere that is clear of obstructions. Use a receiver or transceiver that runs on battery power, if necessary.

7) If you have followed steps one through six, you now have an accurate indication of the relative gain of your two antennas. Now you can make one of your antennas a "reference" antenna and compare any other antennas you or



Fig. 59 — Here a 15-element long-boom quagi for 432 MHz is compared to a 16-element log-periodic Yagi, using the test procedure described in this article. The two antennas both deliver 15 dB gain over a dipole, decisively better than any other 432-MHz antenna tested here. The antennas to be tested are set up side by side and fed with identical lengths of coax. The antennas should be at least two wavelengths above ground and clear of nearby obstructions. To minimize interaction between the two antennas, the masts should also be at least one to two wavelengths apart, and standing side by side in relation to the signal source.



Fig. 60 — An earlier version of the metering system in Fig. 57, with assorted elements of various lengths and the yardstick used to make temporary placements on the boom.



Fig. 61 — The technique used to design a new vhf or uhf antenna experimentally. The boom is shown with the first few elements already in place, and each additional element is adjusted back and forth on the boom until a point of maximum indication of the VU meter is found.

neighboring hams have against this reference.

So how do you determine how much gain your antennas have over a dipole? Some people would say, "Simple, make the reference antenna a dipole." But it may not be that easy, because dipoles are notorious for finding reflections that more directional antennas can't "see." At vhf conference gain-measurement seminars, dipoles have sometimes shown as much as 3 or 4 dB gain over a dipole!

The best reference antenna is probably a small beam of known (or approximately known) gain, assuming you don't have the National Bureau of Standards type of reference antenna that professionals use for this purpose. A 3-element Yagi or a 2-element quad built to handbook dimensions will usually deliver about 6 dB gain over a dipole at 2 meters, if the SWR is okay at the design frequency.

Thus, if you find that a particular 8-element antenna consistently produces 4.5 more dB on the VU meter than your little reference beam, you'll know you have an antenna with about 10.5 dB gain. You won't be exactly correct, but you'll be close to the right figure. Conversely, if your bigger beam doesn't show much gain over the small one, and there are no measurement errors of the sort just described, you'll know for sure that something is wrong with the big antenna.

Once you have established the integrity of your test site, you can even design your own antennas very accurately, using the audio VU-meter technique. To do that, set up your reference antenna and begin designing your new antenna by putting an empty boom on the other pole. Now start with 2 or 3 elements, get a decent SWR and try adding more elements.

As you add elements, you will be able to actually see where each new element "wants to be" on the boom, and you can see your new antenna gain over the reference antenna increase as you go along. Try all sorts of element lengths and spacings as you progress.

Antenna design professionals call this process "perturbation" and they do it with sophisticated mathematics, but you can design antennas that work just as well as theirs on your own antenna range, once you master this technique. Then, if you do go to a vhf conference with your best home-designed antennas, you'll know about how much gain they have before you enter the gain contest. And you'll never come away from such an event with an antenna that has "minus 3 dB gain!" Moreover, you'll know that your measurements, made without any of the sophisticated equipment you saw at the vhf conference, are about as accurate as anybody's. In fact, you may find your own measurements are more valid than the ones at the conference, especially if the antenna-gain figure jumps all over the place when you raise and lower it at the conference antenna range.

HF Antenna Measurements

So far, all of this has been devoted to vhf antenna-gain measurements. Many readers will say, "That's fine, but I want to measure the gain of my 5-element 20-meter beam!" Of course, an audio VU meter and a receiver without agc are a much better way than the notoriously inaccurate S meter to compare two dissimilar hf antennas. The author has seen an S meter show three or four *S units* of signal difference between two antennas that are really only 3 or 4 dB apart in gain.

However, the only accurate way to calculate the gain of an antenna is to compare it to a reference antenna at the same height and then switch the two antennas to opposite masts to validate the data. That may be impractical at hf, but perhaps not as much so as it seems at first. Most amateurs motivated enough to install a 5-element beam on a crankup tower can probably find a way to temporarily set up a smaller beam (not a dipole) on a 20-foot (6.10 m) mast above a roof. Then the two antennas at identical heights can be compared on stable, line-of-sight signals.

The results of this test can be invalidated by obstructions or even by other antennas mounted on the same tower with the test antenna, but at least this will be more valid than a comparison against another ham's readings, when the two locations and rigs may be entirely different.

And if you can switch your test reference hf antennas to opposite masts, you can measure the actual gain of one over the other. One suggestion before you put that giant, long-boom array on the big tower: Put a little beam on the tower and an identical one on the rooftop mast and perform the audio VU-meter tests to see if the two antenna sites do seem to be identical. If they are comparable, then you can put the big antenna on the tower and find out how much gain it has, if any, over the small one on your roof when the two are at the same height.

This may seem cumbersome, and in fact it is! That's why most antenna designers do their research at vhf where antennas are so nice and small, and then scale their best designs up for the hf bands. But if you really want to know your big beam's actual gain, this is probably the easiest way to find out.

Conclusions

The antenna gain-measuring technique described in this article has repeatedly been proved to be reliable and valid. The author has used it to design new antennas that work well enough for all kinds of contest and DX work, including moonbounce. For a dedicated amateur, working DX on a home-designed antenna far surpasses the thrill of working the same DX with an antenna purchased at a store! But remember, whether you're working 20 meters or 23 centimeters, a signal source, a receiver with its agc disabled and an audio VU meter are the only pieces of equipment you need to measure antenna gain with this technique. This material was originally presented in *QST* by Wayne Overbeck, PhD, N6NB.

References

[1] Clark, "Direct Methods for Measuring Antenna Gain," *Ham Radio*, July 1969.

[2] Knadle, "UHF Antenna Ratiometry: An Outdoor Range Improvement Technique," a paper presented to IEEE Intercon session L, April 1975.

[3] Brier and Orr, *VHF Handbook for Radio Amateurs*, Radio Publications, Inc., Wilton, CT p. 225.

[4] Overbeck, "The VHF Quagi," *QST*, April 1977.

[5] Knadle, "UHF Antenna Ratiometry," *QST*, February 1976.

Index

"Airstream Loop," 75-meter: 90
Antenna ideas: 93, 109
Apartment dweller's dilemma: 92
Aperture: 54

Baby ultimate Transmatch: 138
Balun: 136
Base loading network, vertical: 17
Beams: 41, 53
Bobtail array: 81
Bridge, resistive antenna: 131
Bridge, SWR: 125
Broadband matching networks, simple: 140
Broadband matching transformers: 140

Capacitance hats: 111
Capacitive loading: 110
Capacitor-tuned quad: 63
Changeover relay, rf-sensed: 142
Coil housing box: 10
Comparisons:
  High vs. low antennas: 102
  Quad vs. Yagi: 53, 100
Computer-modeled arrays and patterns: 119
Coupling methods: 104
Cross-modulation, receiver: 135

DDRR, 40-meter: 95
Delta-Loop beam, HRH: 84
Delta Loop, 10-meter: 84
Delta Loop, 15-meter: 86
Delta Loop, 20-meter: 85
Dipoles: 89
Dipole, off-center-loaded: 107
Directive arrays: 41, 53
Directivity: 53
Director spacing, effects of: 50
Distributed loading: 26
Dual-band 160- and 80-meter vertical: 141
DX antenna, 160- and 80-meter: 34
DX weasel, 20-meter: 41

Efficient short radiators: 13, 25, 27, 112, 141
E-skip tests, 6-meter: 103
Etched-circuit Monimatch: 123

Ferrite-rod loop: 78
Folded mini quad: 69

Gain, measuring with amateur methods: 145
Gain, quad vs. Yagi: 55
Ground-image vertical: 22
Grounding systems, verticals: 29
Ground-mounted short verticals: 25
Groundplane, H-plane pattern: 11
Groundplane with tuned feeders, multiband: 19
Ground-wave tests: 103

Half-size 80-meter: 110
Half square array, three-element: 82
Half square array, two-element: 82
Half square, 80-meter: 81
Harmonic problems: 33, 135
Helical, 8-1/2 ft: 26
Helically wound vertical, 75-meter: 20
Hf measurements: 147
High vs. low antennas: 102
Horizontal vs. vertical: 32
H-plane pattern, groundplane: 11
HW-40 micro beam: 43

Impedance properties and matching, quad: 56
Inductive loading: 110
In-line rf power metering: 126
Input resistance vs. number of radials: 27

L-network Transmatch: 92
Loaded antennas for travel: 89
Limited-space antennas: 7, 104
Linear array, vertical four-element: 118
Loading coils with multiband antennas: 112
Loading, capacitive and inductive: 110
Loading, distributed: 26
Loading, top-hat: 26
Loads, antenna: 133
Loads, transmitter: 104
Load, 50-ohm: 123, 135
Log-Yag array: 49
Loop:
  Antenna, W1FB 4T-ES: 80
  Antennas for receiving: 76
  Experiments: 78
  Ferrite-rod: 78
  Four-turn coax: 80
  Four-turn shielded: 77
  Indoor: 77
  40-meter full wave: 98
  160-meter indoor receiving: 80

Matching networks, simple broadband: 140
Matching, two-band quad: 75
Measuring gain with amateur methods: 145
Metering, in-line rf power: 126
Micro beam, HW-40: 43
Minooka special: 36
Minooka special, mobile: 38
Miscellaneous antenna types: 76
Monimatch, etched-circuit: 123
Monopole, 40-meter: 90
Multiband antennas: 7, 9, 11, 13, 16, 18, 19, 32, 45, 60, 92, 133
Multiband antennas with loading coils: 112
Multiband ground plane with tuned feeders: 19
Multiband verticals: 16, 32
Multiband verticals, nontrap: 33

Noise, beating: 76
Novice four-band vertical: 9
Novice two-band vertical: 7
Novi-Loop: 98

Off-center-loaded dipole: 107
Optimizing verticals: 29, 115

Phased array, dissimilar antennas: 30
Pi-network tank circuits: 132
Polarization, quads: 54
Portable 160-meter vertical: 38
Power dividers, rf: 120
Preamplifier, broadband 40-dB: 78

Quads: 53
  C-T, reduced size: 63
  Folded mini: 69
  Impedance properties and matching: 56
  Matching, two-band: 75
  Polarization: 54
  Radiation angle: 54
  Spider mount: 74
  Stub tuning: 70
  Triband one-loop cubical: 60
  Yagi-type directors: 74
  7-MHz, linear-loaded: 73
  15-meter, two-element: 61
  40-meter: 62
  80-meter two-element: 66
Quad vs Yagi: 53, 100

Radials, input resistance vs. number of: 27
Radiation angle, quad: 54
Radiation resistance/height curve: 27
Random-length wires: 92, 104
Reactance compensation: 18
Receiver cross-modulation: 135
Resistive antenna bridge: 131
Rf power dividers: 120
Rf power metering, in-line: 126
Rf-sensed changeover relay: 142
Rod-loop tests: 79
Rod loop, sense antenna with: 79

Scoop loop beats noise: 76
Sense antenna: 79
Short radiators, efficient: 27, 112
Short vertical design: 13, 25, 27, 141
Short verticals, SWR: 28
Shunt-feeding towers: 34,
Simple arrays of vertical elements: 114
Spider quad mount: 74
Square array, vertical four-element: 118
Stub tuning, quads: 70
SWR: 124
SWR bridge: 125

Tank circuits, pi-network: 132
Theory and test methods: 100
Top hat loading: 26
Towers, shunt-feeding: 34
Transformers, broadband matching: 140
Transmatch: 92, 105, 132, 135, 138
Transmatch, baby: 138

Transmatch, L-network: 92
Transmatch, Ultimate: 135
Transmission lines: 124
Transmitter loads: 104
Trap antennas: 33, 133
Trap verticals: 33
Travel trailers and campers: 89
Triangle three-element vertical array: 122
Tribanders: 13, 18, 60, 100
Triband one-loop cubical quad: 60

Ultimate Transmatch: 135
Ultimate transmatch, baby: 138

Varimatcher: 105
Verticals: 7
  Four-element arrays: 117
  Ground-image: 22
  Ground-mounted short: 25
  High-performance 20-, 40- and 80-meter: 13
  Linear array, four-element: 118
  Multiband: 32
  Multiband groundplane with tuned feeders: 19
  Nontrap multiband: 33
  Novice four-band: 9
  Novice two-band: 7
  Optimizing: 29, 115
  Radiator, multiband: 16
  Short design: 13, 25, 27, 141
  Simple arrays: 114
  Square array, four-element: 118
  Three-element arrays: 117
  Trap: 33
  Triangle three-element array: 122
  Types of: 32
  Two-element array: 115
  5/8-wave, 20-meter: 39
  10- and 15-meter groundplane: 11
  10-, 15- and 20-meter: 18
  75-meter, helically wound: 20
  160-meter: 36
  160- and 80-meter system: 141
  360-degree steerable phased arrays: 119
Vertical vs. horizontal: 31

Why a Transmatch?: 132
Wilkinson power dividers: 121
Wire, nonresonant, random-length: 92

Yagis: 41
  Director spacing, effects of: 50
  Helically wound, two-element, 40-meter: 43
  Log-Yag array: 49
  20- and 15-meter bite-size beam: 45
  20-meter DX Weasel: 41
  20-meter minibeam: 48
Yagi-type directors for quads: 74
Yagi vs. quad: 53, 100

6-meter E-skip tests: 103
7-MHz, linear-loaded quad: 73
10- and 15-meter groundplane: 11
10-meter Delta Loop: 84
10-, 15- and 20-meter one-loop quad: 60
10-, 15- and 20-meter vertical: 18
15-meter Delta Loop: 86
15-meter quad, two-element: 61
20- and 15-meter bite-size beam: 45
20-meter arrays, beam patterns: 50
20-meter beam, linear loaded: 48
20-meter Delta Loop: 85
20-meter DX Weasel: 41
20-meter minibeam: 48
20-meter, 5/8-wave vertical: 39
20-, 40- and 80-meter vertical system: 13
40- and 15-meter vertical: 7
40-meter DDRR: 94
40-meter full-wave loop: 98
40-meter monopole: 90
40-meter quad: 62
40-meter vertical, short: 25
40-meter Yagi, helically wound two-element: 43
50-ohm load: 123, 135
75-meter "Airstream Loop'" 91
75-meter, helically wound vertical: 20
80-meter DX antenna: 34
80-meter, half-size: 110
80-meter half-square: 81
80-meter quad, two-element: 66
80-meter receiving loop: 76
80-meter vertical, short: 27
160-meter DX antenna: 34
160-meter indoor receiving loop: 80
160-meter, space-saving vertical: 40
160-meter vertical: 36
160-meter vertical, portable: 38
160-meters, receiving loop: 76
160- and 80-meter vertical: 141
160 on 80-meter half-square: 83
360-degree steerable vertical phased arrays: 119



ARRL publications . . .

the foundation of a dynamic hobby

Open the doors to amateur radio.

Whether novice or old-time amateur, student or engineer, League publications will help you to keep abreast of the times in the ever-expanding field of electronics.

THE RADIO AMATEUR'S HANDBOOK
Internationally recognized, universally consulted. The all-purpose volume of radio. Packed with information useful to the amateur and professional alike. Written in a clear, concise manner. Contains hundreds of photos, diagrams, charts and tables. **$9.75**

ARRL HAM RADIO OPERATING GUIDE
Written for the amateur who prides himself on good operating procedures. A ready reference source and guide to good operating practices. Ideal for the amateur who wishes to brush up on operating procedures and who wishes information on all facets of amateur operating. **$4.00**

TUNE IN THE WORLD WITH HAM RADIO
The complete beginner's package. Everything needed to obtain a Novice license: Theory, rules, how to assemble a station, and operating practices. With one-hour code cassette. **$7.00**

SOLID STATE BASICS
Enter the fascinating world of solid state with this exciting book. Perfect as a study guide for the beginner or as a refresher for the more experienced builder. Complete with a ten watt transmitter as a workshop exercise. **$5.00**

THE RADIO AMATEUR'S VHF MANUAL
A thorough treatment of vhf. Covers receiving and transmitting principles, techniques and construction, antenna and feed system design, uhf and and microwaves, test equipment, interference causes and cures. **$4.00**

GETTING TO KNOW OSCAR — FROM THE GROUND UP
This booklet is a reprint of an extremely popular series appearing in *QST*. **$3.00**

UNDERSTANDING AMATEUR RADIO
For the beginner. Explains in simple language the elementary principles of electronic and radio circuits. Includes how-to-build-it information on low cost receivers, transmitters and antennas. A "must" guide for the newcomer. **$5.00**

ARRL CODE KIT
Two top-quality cassettes provide practice at 5, 7-1/2, 10 and 13 wpm. Step-by-step progression and use of random code characters plus proven suggestions and hints in the accompanying instruction book make increasing your code proficiency easy! **$8.00**

FM AND REPEATERS FOR THE RADIO AMATEUR
Complete treatment of fm and repeaters. Chapters on receivers, transmitters, antennas and repeater operation. Of great value to the fm buff as well as to those just becoming interested in the subject. **$5.00**

THE ARRL ANTENNA BOOK
Theoretical explanation and complete instructions for building different types of antennas for amateur work. Simple doublets, multielement arrays, mobile types, rotaries, long wires, rhombics and others. **$5.00**

SOLID STATE DESIGN FOR THE RADIO AMATEUR
Thorough treatment of the use of solid state devices. Provides a wealth of tried and proven circuitry plus practical application data. **$7.00**

ARRL ELECTRONICS DATA BOOK
Includes data on radio frequency circuits, filter design, *L*, *C*, and *R* networks, antennas and feed systems. A catalog of solid-state circuits and much more. This 128-page reference is a useful addition to the amateur's technical library. **$4.00**

THE RADIO AMATEUR'S LICENSE MANUAL
Study guide and reference book. Points the way to the coveted amateur license. Complete with typical questions and answers to the FCC amateur exams for Technician, General, Advanced and Extra Class. **$4.00**

SPECIALIZED COMMUNICATIONS TECHNIQUES
Seven chapters cover the more esoteric forms of amateur radio: ATV, SSTV, FAX, RTTY, Satellite Communications, and advanced communication techniques. **$4.00**

OPERATING KIT
The active ham's favorites — The Ham Radio Operating Guide, Log Book, Message Pad and U.S.A. Call Area Map. **$6.50**

A COURSE IN RADIO FUNDAMENTALS
Twenty-six chapters present the electrical and electronic principles that are basic to understanding radio circuit operation. **$4.00**

RADIO FREQUENCY INTERFERENCE
A must publication for all hams! Full treatment is given to the causes and solutions for those pesky interference problems. Complete with illustrations and photos of the more common kinds of interference. **$3.00**

HINTS AND KINKS
If you build and operate an amateur radio station, you'll find this a mighty valuable book in your shack and workshop. **$4.00**

SINGLE SIDEBAND FOR THE RADIO AMATEUR
A digest of the best articles from *QST*. Includes discussions of theory and practical how-to-build-it descriptions of equipment. **$4.00**

Available from **THE AMERICAN RADIO RELAY LEAGUE, NEWINGTON, CT. 06111**

PRICES ARE VALID IN U.S.A. ONLY AND ARE SUBJECT TO CHANGE WITHOUT NOTICE.

QRP SWL HOMEBUILDER

RF — Test and Measurement Homepage

FAQ | Site Update Log | About... | Design Apps

Topics 1998 - 2005

- SWL Page
- RF Preamps
- QRPHB Software
- Popcorn DC Receiver Mainframe
- 40 M Popcorn Superhet Receiver
- Broadband Transformer Topics
- Diplexer Topics
- Ugly Construction
- Wee Willy 75 M DSB Transceiver
- W7ZOI JFET Biasing Tutorial
- EMRFD Review
- Tapped Cap Impedance Transformation
- More Active Antenna Experiments
- Fun with LEDs
- SWL Receiving Antenna Experiments

Topics 2006 - 2009

- Experiments with JFET Biasing
- TRF Receiver for WWV
- MF and HF SWL Receiving Antenna
- MF and HF Receive Antenna Splitter
- MF TRF Receiver
- Junk Box Low Pass NDB Filter
- More NDB Ideas and Circuits
- Low Pass Audio Filter Experiments
- TRF WWV Receiver for 5 MHz
- Complementary-Symmetry Amplifier Biasing Basics
- Low Power Audio Amp Experiments
- Two Bravo Receiver Experiments
- ICOM IC-7200 Review
- Electronic Hobbyist Circuits
- Output of a Diode Ring Mixer in an Oscilloscope

Topics 2010 - 2011

- Low Noise Crystal Oscillators
- Crystal Parameter Checker Supplement
- Hobbyist Circuits 2010
- RF Workbench Page 1
- RF Workbench Page 2
- AF Transistor Input Z Experiments
- RF Workbench Page 3
- Misc RF Experiments 2011
- Hobby and Fun 2011
- QRP Modules 2011
- Receiver Band-pass Filters
- RF Workbench Page 4
- VFO-2011
- VHF Butler Oscillator

Topics 2012 - 2014

- VHF to the Max !
- HF Ragbag
- RF Workbench Page 5
- VHF-FM
- Sundry Experiments 2012-13
- VHF - Veronica
- RF Workbench Page 6
- HF Embarcadero
- Caitlyn 310 : UHF Beginnings



Make it — then measure it!

QRP SWL HOMEBUILDER

RF — Test and Measurement

Frequently Asked Questions

1. How to you make your schematics?

I hand draw my schematics using the Paint Program that ships with all Microsoft Windows(tm) operating systems.

I strive to make schematics as clear and as small in file size as possible.The Windows Clipboard is used extensively to copy and paste the desired components from previous schematics to new schematics — very few new components are ever drawn; rather they are recycled from schematic to schematic. My system allows me to paste color 3-D labels and small photographic bitmaps into schematics.

The raw 24-bit bitmap drawings are compressed to 16-bit png files. Prior to May 17, 2010, bitmaps were compressed as 8-bit gif files. An example drafted circuit using the Windows 7 Paint program follows.


tda-1.bmp - Paint
Home
View
Paste
Clipboard
Select
Image
Tools
Brushes
Shapes
Outline
Fill
Size
Color 1
Color 2
Colors
Edit colors
12v
TDA7052 Power Measurement
10
100 uF
+
1
2
3
5
6
8
U1
TDA7052
8 Ω
402 × 312px
Size: 368.1KB
100%

At least 25 people have sent or recommended software for making schematics. Thank you for this kind gesture, but I prefer my current method and after 15 years — make schematics quickly.

2. How come you don't supply parts lists? Other people do.

The answer is simple; lack of time. It takes considerable time and effort to put up a new web page and also to maintain a large web site. I save time by leaving the parts list up to the builder. In addition, this site is about experimentation and using what parts you have on hand.

3. Why didn't you answer my email?

I answer all legitimate emails as soon as possible. Our POP3 server gets an average of 2016 spam emails per month (December 2013 data), however, our software removes 99.27% of these and I never see them. Occasionally, legitimate emails are filtered in error and I apologize. I've received as many as 83 legitimate emails in a single day so can get behind. Please keep emailing — when readers stop emailing, I'll know the site has fallen totally obsolete [it may already be obsolete] and delete it.

Our mail server software logs and analyzes the network information of all spammers and may automatically filter and/or block their addresses or even their entire ISPs at the router level. Analysis indicates that 90% of our SPAM comes from just 3 countries and if you happen to live in one of these countries, the filtering will be especially sensitive.

This sounds dogmatic and unfriendly, however, until you've set up a domain and must handle ++ spam emails, endure and then develop router control software and other strategies to handle DDoS attacks and so forth, your completely naive about the 'dark side' of running a homebrew web server. Massive amounts of bandwidth might be otherwise wasted by allowing unwanted server use unless we actively counter these activities to keep the site running well for legitimate hobbyists. Not to mention all the wasted time. Further:

The 3 host web servers, the power, the server software, the security apps, the internet bandwidth etc.are owned or purchased by my family, and as you know, nothing is free. Despite many offers by companies to place ads on my pages, I've kept the site advertisment free and running pops.net costs us a few thousand dollars each year. We ask you to please respect our site for the sake of the experimenters who visit.

Pops.net server rack in our warehouse.

While I appreciate that some people might want to email invite me onto their social networks, I do not have time to participate. All email traffic from or involving social networks see this page for a list is deleted automatically by our POP3 server control software.

I **never** buy or sell parts via email, nor exchange hyperlinks. Never. I do give free parts to those in need though.

All email with the .info domain is blocked.

The number of people selling kits has jumped up by ~4 dB in the past 5 years. Increasingly, builders who need help with kits were emailing me for support. I rarely build kits and my knowledge regarding kit building is nearly 0. Please contact your kit seller for help.

You may wish to enquire with the kit seller about their online support polices and promptness prior to purchase. Additionally you might try the "support" email address provided and see if and how promptly they reply. Most of the popular kit sellers (AADE, Kits and Parts, etc.) provide excellent support to their customers. Like anything else online; buyer beware.

4. How come you didn't link to my web site - I linked to yours?

A big thanks to the folks who link to this web site! The QRP/SWL HomeBuilder site focus is content, not web links. Making a lot of links means spending time testing for and tracking down dead links - the so called "link rot". Time spent on the web site is time away from the electronics work bench. In addition, it is not logistically possible to reciprocate in kind, as hundreds of web sites and blogs have linked this site.

5. I see the word "popcorn" used a lot on this site- what's this all about?

Popcorn connotes the essential theme of the web site; simple, frugal, without fuss and over use of technical jargon, or complex math and engineering techniques. The QRP/SWL HomeBuilder web site is referred to as the popcorn site by many. The site targets hobbyists. The emphasis is fun. The hope is that it will attract new people to electronic design, measurement and experimentation. Hopefully, this site stimulates interest in QRP homebrew electronics.

Soon after I began building electronic circuits, my teachers and the popular electronic-related media of the day pushed me towards etched, printed circuit boards. I complied and this killed my passion for electronics. For me, habitually stuffing circuit boards lacks creativity and freedom.

Later, I discovered people were building guitar and bass amps using point to point wiring techniques with terminal strips and partial circuit boards. I became interested in building and repairing guitar amps and this passion continues today. In 1992, the discovery of 2 QST articles changed everything *for me (complete reference provided):* The Ugly Weekender: parts 1 and 2 by Roger Hayward, KA7EXM and Wes Hayward, W7ZOI; published in QST for August 1981 and June 1992. This was my first exposure to Ugly Construction and it was immediately adopted as the defacto standard bread boarding method in my electronics work shop. In fairness, etched circuit boards are a great tool, but not essential for the experimenter.
After working with Ugly Construction over time, considerable progress was made in understanding RF circuits and one output was the launch of this web site in 1998.

Currently, little has changed, I continue to prefer scratch-homebrew rather than kit-homebrew electronics. My interest in Short Wave radio and analog electronics has grown considerably. For me, electronic circuits hold a certain mystique which arouses my curiosity to learn, enjoy and share. As a lay person, this web site has facilitated meeting some awesome people through email from all continents and it has been a privilege to learn from them, my mentors, book and web authors and often enough; from my mistakes.

5. What do you mean by a 5K1 or 3K3 resistor value?

For E24 or 5% tolerance resistors 5K1 = 5.1K, 3K3 = 3.3K and so on. For E96 or 1% resistors 31.6K is written as 31.6K. All resistors are 1/4 watt unless otherwise specified.

6. How do you measure audio amp output power?

Please see Figure 4 on this web page. Any amp when cranked, outputs much greater power than when it is providing a clean sine wave. The quoted power for any audio power amp on this web site is the maximum average power it will give before the pure sine wave becomes distorted.

7. I noticed a new web page appears and then it is edited for 1-2 weeks. When is the web page completed?

When a new web page is added, it takes a week or so to find and change some of the grammar and spelling errors. Sometimes new ideas or feedback will cause me to further edit a web page at any point in time. This whole web site is a work in progress. The last date any given web page was edited is posted on the bottom of the web page.

8. Do you buy or sell stuff?

No and no. I receive numerous emails from people asking me to sell them stuff. I do not sell anything - no parts, books, coffee cups, ball caps, tee-shirts, ad space — nothing. I do not buy parts in commercial-quantity volumes and have no need to make contracts for obtaining any electronic components. Every week, Asian companies email to ask about buying their parts — please note, my answer is *always* the same: no thank you.

9. Questions and concerns about printing and printability

Each year, a few readers email to complain how poorly the web pages print. This is true and I apologize.

Some people prefer pdf files for easy printing. I have resisted going to pdf format for 3 main reasons:

1. The web site audience is international and many are using web translators. PDF files are 8-bit graphic image files and do not translate.
2. More and more readers are using mobile computer devices and pdf files are a pain for them.
3. We should all print less often to save resources

As an experimenter, I dislike crammed, small-size schematics and feel they should be drawn for *maximum* clarity. Therefore, my schematics tend to have a lot of white space and color contrast. I try to make them no wider than 700 pixels, although sometimes it's impossible to do this. Big schematics are *not* printer friendly. The only practical solution is to click on and open them in a separate browser window for easier sizing and printing.

I also feature big photos which burn up a lot of printer paper. Project photos are important to me; they provide a more intimate glimpse into the bench work and promote the real purpose of the site — building stuff.

A potential printing solution for Microsoft Explorer 8 users; Click

10. I have noticed in your CMOS logic photographs, you don't always ground unused input gates. Isn't this bad?

Proper CMOS logic practice mandates the grounding of all unused input gates. In prototypes and experiments, I don't always do this as I generally want to re-use the IC in other experiments. This is a cost saving measure. When you build a lot of stuff, it can get expensive and recycling parts makes sense. In keeper circuits or critical prototypes, unused input gates are directly soldered to the copper clad board. This also anchors the IC very well.

11. What is the proper URL of the home page?

http://www.qrp.pops.net

The following pre-2006 URL was decommissioned August 6, 2010: http://www.qrp.pops.net/default.htm

12. What are the QRPHB Design Centers and Professor Ivanenko character about?



This web site is about design and not just providing circuits to copy; I'm hopeful that the QRPHB Design Center concept initiated in 2011 will invigorate the site. Design Centers are the presentation of simple, but useful algorithms for amateur builders to advance their skills on the bench.

Professor Vasily Ivanenko ( ), a *fictitious* retired Russian physics professor wants to share his knowledge and give back to society. He signifies each Design Center. Professor Ivanenko was drawn for me by Rod Adams in 1996 using the Paint program that ships with Windows (the same app I make my schematics with). Rod did all of the other original bitmap art for this website including the coil guy and junk box pictures. This character was inspired by one of my favorite photographers: Irving Penn — this photograph, which is all over the web.

A new character; Dr. Natasha Petrovna appeared in late Summer 2012.

The professors are just a good bit of fun — add intrigue, characters on whom to focus and a means of identifying Design Centers. Electronics with just math and physics bores us all. Adding splash, color, clear photographs and characters such as the coil guy or the Professors boosts the site's appeal and provides a creative outlet for me.

13. Why did you kill your blog?

Time mostly. *My* blog wasted *yours* and my time. I carefully analyzed my personal yield from blogs in 2012 to 2013 — for the most part, blogs just entertain + share trivia, or rehash someone elses idea(s), or 'innocently' attract you in hope to sell stuff — and sometimes, just fulfill the author's need for attention. I don't seek, nor have time for entertainment or spectacle within my RF hobby and I certainly don't wish to waste *your* time. Each to his own, I suppose.

My analysis showed that unfortunately, blogs rarely boosted my understanding of electronic design or measurement practices. My ardent focus is to learn + improve and then pay some of this knowledge forward on a web site. Of course, everything in context — many exceptional people blog. For example, Dave AA7EE, or Jason, NT7S.

Most of the RF design and measurement people I follow keep old fashion web sites and provide generous email support. Design and measurement web sites, plus reputable and/or peer-reviewed industry and hobbist books, journals and multimedia work best for me.

Further, great elmers don't just publicly hang-out on blogs, or web server groups, or publish Utube videos — some just check their emails and when asked — give wonderful support without fanfare. Hats off to these humble folks. Thank you!

14. What oscilloscope should I buy?

Yikes — a tough question I get nearly every month. Please do your research. My best answer is buy the best 'scope you can afford. Are you a casual experimenter, or sit in your lab a lot? I prefer DSO's , however, made due with a old boat- anchor CRT for my first 10 years. The Rigol 1052/1152 seem popular entry-level choices due to their cost versus performance ratio. On the other hand, view this video to see how much Rigol DSO technology has changed.

I owned and sold my 1052 to a builder in Michigan — a worthy choice like many other 'scopes. IMHO, the FFT and math functions on the 1052 and 1152 suffer due to low memory depth and clock jitter.

Even if you only work at HF, a bandwidth 5X higher than your main frequencies of interest works better for showing harmonics. Again, I advise people to simply buy the best 'scope they can afford since it will form the heart of your test bench.

15. I'm a beginner — what toroids should I buy?

Opinions will vary, but here's what I recommend. Buy any quantity you wish, but sometimes minimum quantities apply and shipping to some countries costs dearly, so I tend to order enough parts to last me for awhile.



```
A basic HF toroid starter kit might look like:

Quantity  Part#    Type

10-25     FT37-43  ferrite
10-25     T50-6    powdered iron

Above that, perhaps add these toroids.......

10-25     T68-6    powdered iron
10-25     T37-2    powdered iron
10-25     T50-2    powdered iron
10-25     FT50-61  ferrite


That's about it -- These will build most things RF on a HF beginner bench
```

RF — Test and Measurement

QRP — Log: Updates To Permanent Content



Oct 5, 2014 --- The end of QRPHB? Expect the Qrp site to go down each day for 1-4 hours. As I wrote before, we're losing an average of 10% of the outgoing packets and this peaks as high as 40% when many people are accessing the site. See an example graph below.



On Oct 2, 1 of our ISP's techs came and tested our WAN -- "it's better than most" he said. Hopefully they can do something to boost the performance on their side. Wave bought out all the local competition and we're stuck with them [this is happening everywhere]. Click for 1 of the many links writing about the emerging internet cable company monopoly.

You'd think that in 2014 we could properly host a web site like we've done since 1998? To boot, Stuart is paying for a high bandwidth business account and getting less than 1% of the promised bandwidth. We chatted today and will wait patiently for Wave to improve our outflow - but only for so long.

If Wave can't or won't boost performance, I am leaning towards taking this web site down as opposed to moving it -- it's been a good run. QRPHB creates a lot of work and I could get way more done without the web site hassles. So, 2014 might be it for me. If so, thanks for coming here all these years and best of luck with your experiments!

--- Sep. 19 --- Wave Broadband, our Internet provider suffered major problems recently and I shut the site down for 4 days rather than have it limp along pathetically. Well the Wave saga *continues*: the site loads slowly and pictures are missing etc.

Our email server remains working even when the main site is down. You can always email me if the site is not working for you -- or if you have a comment or question.

Vistor volume rose this Summer so we added a better router that provides bit by bit data performance collection and new features to help throughput. At minimum user bandwidth, a unique visitor hits the site every ~0.7 minutes. I'll start formal bench experiments on October 3 --- to kick off the sites' 16th season.



August 31, 2014 — Kit to upgrade my HP frequency counter to 3 GHz added as Section 5 on Caitlyn 310 — UHF Beginnings.

August 18, 2014 — QRP-POS Data on the Sundry Web Page. Look at the end of Section 8: Popcorn AF Amps For Receivers — Reprise. This new, all-discrete AF stage will go into the Funster Line receiver and ranks as 1 of my best in terms of power and headroom.

August 12, 2014 — Funster Line: a QRP 40M band CW trans-receiver added to HF Embarcadero web page as Menu item 4. Click here for Funster. Only the transmitter is presented for now.

June 18, 2014 — I tweaked the page now called About... on the top level menu. Also, on this web page, I added a new essay for 2014 just under the essay for 2010. I'm off the bench until Fall, but hope to add a little content on rainy days or such. I'm about 2 years behind in presenting some of my experiments.

May 22 and 26, 2014 — New Supplemental Web Page for VHF-FM launched. This page and another supplement will house some new receivers over time. The new supplement is linked on the original VHF-FM web page in section number 4.

May 5, 2014 — Section 7: NE612 Mixer Diddy added to VHF Veronica

April 14, 2014 — Completion of Return Loss Bridge Experiments [added Bridge #4] on Caitlyn 310.

April 7, 2014 — Return loss and VCO experiments added to Caitlyn 310.

March 7, 2014 — Section 3 added to VHF-FM. A DC Converter for VCOs. **March 25** QRP-POSDATA for March 2014 Poor Hams Scalar Network Analyzer (PHSNA) added to Section 1 of Sundry.

February 14, 2014 — Caitlyn 310 — New repository web page for my venture into UHF. Click. Surprisingly, the site averages ~ 3000 unique visitors every 24 hours. Click for the Feb 25 tally

January 15, 2014 — The FAQ was often missed and therefore moved to the top level menu + editted/augmented.

January 4, 2014 — A follow-on version of the K3NHI QEX power meter added to RF Workbench 5 as section 6.

December 15, 2013 — I added Section 3 to HF Embarcadero. VXO and VCXO Notes. I significantly updated the VFO-2011 web page on Dec 17, 2013.

November 7, 2013 — Section 6 added to VHF — Véronique. 1 photo added to the end of the Ugly Construction page. Severe Fall weather conditions took down the server for ~1 hour today.

November 1, 2013 — I added Section 2 to HF Embarcadero. A vestigal set of notes regarding my attempts to update the Popcorn Superhet receiver.

October 31, 2013 — Section 5 added to VHF — Véronique.

October 27, 2013 — VHF-FM re-formatted and Section 2 added. I imagine this page will disinterest many.

October 18, 2013 — 3 rarely accessed web pages removed from drop down menu, but not deleted from the server. New QRP-Posdata added to HF-Ragbag (near the end). Section 3 edited and Section 4 added to VHF — Véronique.

October 11, 2013 — Build Season 15 begins [I bench experiment Oct to May]. I added HF Embarcadero to hold all my HF and perhaps AF experiments this season. I'll also add content to VHF FM, VHF — Véronique and RF Workbench 6 over the next 12 months. Thanks.

September 9, 2013 — Blog deleted.

August 8, 2013 — Section 2 of RF Workbench 6 added. Measuring PA collector V and I to calculate efficiency. On August 16 — I added a new essay on the Ugly Construction page called Is Ugly Construction Less Reproducible than Manhattan?

June 25, 2013 — I started RF Workbench 6. It will take 1 year to complete

April 14, 2013 — I added Section 3: 50 Ω MMIC Bench Amplifer to the VHF 2013 Veronica web page.

March 31, 2013 — I started a new content page called Pin Outs

March 25, 2013 — Section 9: an essay about the 1981 Progressive Receiver, plus the final section — 10: Miscellaneous Pictures and Figures added to Sundry 2012-13

March 18, 2013 — Section 8. Popcorn AF Amplifier for Receivers — Reprise added to Sundry 2012-13

March 10, 2013 — I added a new VHF content page for 2013: VHF-2013 - Veronica

February 16, 2012 — I added Section **7** -- A Journey Above HF -- to the Sundry Experiments 2012-13 web page.

February 14, 2012 — I added Section **6** -- Non-Mechanical Iambic Paddle -- to the Sundry 2012-13 web page.

February 1, 2013 — A seperate QRP—POSDATA added to RF Workbench 4. Now QRP— POSDATA 1, 2 and 3.

December 15, 2012 — I added Section 4 to Sundry Experiments 2012 - 2013 . A PLL circuit from EMRFD.

January 5, 2013 — I added Section 5 to Sundry Experiments 2012 - 2013 . A simple AF feedback amp. An essay concerning L-C meters was also added on RF Workbench 5. Section **5.**

December 22, 2012 — I deleted the web page ***Tuning VFOs with a PN Junction*** since some of the experiments were poor quality and performed back in 1998 when I was more ignorant than now. I've learned much since then and my new VCOs from the past 1-2 years reflect this knowledge. The ***Selected QRP Reading list*** and ***Cascode 7 Receiver*** web pages were also wiped.

December 15, 2012 — I added Section 4 to Sundry Experiments 2012 - 2013 . A PLL circuit from EMRFD.

December 3, 2012 — I added Section 3 to Sundry Experiments 2012 - 2013 . Interview with Jason from Etherkit

November 13, 2012 — QRP — Posdata added to the VHF to the Max web page. Section 5: Z-Comm VCO.

November 1, 2012 — Sundry Experiments 2012 - 2013 web page added.
QRP — PosData added to Section 2 of **Power Meter Calibrators** on RF Workbench 5 and updated again on Nov 22, 2012.

October 16, 2012 — VHF FM web page added. Already, it has spawned a first supplemental web page

Sept 24, 2012 — QRP — Posdata added to the end of the HF Ragbag web page. I added a bypass and decouple network for HF to lower VHF.

August 17, 2012 — QRP — Posdata #2 added to bottom of the Receiver Band-pass Filters web page.

August 6, 2012 — Section 5: **Some Experiments with RF Bypass Capacitors** added to the HF Ragbag web page. Also a new QRP — Posdata added to the bottom of the Crystal Parameter Checker web page.

August 1, 2012 — QRP — Posdata added to the Receiver Band-pass Filters web page.

July 12, 2012 — I added a corrected schematic on the Wee Willy page: Wayne. M0WAY — 14 MHz PA under August 25, 2011. Also, added a new essay on **Microphonics in DC Receivers**. See Section 4 on the HF Ragbag Page

June 23, 2012 — RF Workbench 5 added. Click here.

May 31, 2012 — Galina discovered that I neglected to publish the proper version of the Hobby and Fun 2011 page and corrected my error. A fine-tuneable Wien Bridge Oscillator idea from Ken Kuhn now appears at the page bottom.

April 21, 2012 — I heavily edited RF Workbench 1 and 2.

April 13, 2012 — Web site purge. I removed RF Filters, VFO 1998, QRP Workshop Ideas, Miscellaneous Schematics and Photos, Base-biased VFO, Funster Transceiver, Miscellaneous Circuits and Ideas 2005 and Crystal Oscillator Offsets. **Reason:** substandard.

April 6, 2012 — 50 MHz Receiver Pre-amp and Filter added to VHF to the Max web page .Section 4.

March 26, 2012 — HF Ragbag web page added to top-level menu. Non-VHF experiment repository for 2012.

March 19, 2012 — VHF to the Max web page added to top-level menu. 50 MHz VCO experiments added to this page in Section 3.

March 14, 2012 — EMRFD review edited.

February 29, 2012 — Minor edits to the Audio Transistor Input Impedance Experiments web page. Also, I updated the calculation of the common emiiter amplifier base input resistance using the better formula: **Rin = (B+1)*(re + RE')** [while ignoring REB]. This is my favorite web page on the site.

February 26, 2012 — QRP— Posdata added to the bottom of the 2nd NDB web page

February 17, 2012 — I introduced a new miscellaneous VHF page: VHF to the Max — I'll slowly add stuff over 2012. Major editing done to the Broadband Transformer web page.

February 4, 2012 — RF Workbench 1 and 2 significantly edited. 2 new photos added.

January 28, 2012 — QRP — Posdata added to Crystal Parameter Checker web page and to QRP Modules 2011 under 7 MHz VCO Experiments on this web page. I re-wrote the temperature compensation section of the VFO-2011 web page and added 3 photographs.

January 3, 2012 — Web site change: I update web essays with an "epilogue section". In 2012 and on, they will be called QRP — Posdata (Spanish for post-script or epilogue). Posdata #2 added to the RF Workbench 4 web page.

December 17, 2011 — The Butler Did It ! - First VHF Experiments 2011 web page added. A 50 MHz frequency doubler added Dec 26, 2011.

Nov 12, 2011 — Our server went down for 16 hours. Both AC power and cable Internet to the warehouse failed after a rain storm and wind gusts knocked down some trees that severed the hydro and cable wires. Expect more weather-related down time as Winter approaches.

Oct 15, 2011 — VFO-2011 added.

Oct 2, 2011 — RF Workbench Page 4 added. On **Oct 17, 2011** I added an epilogue.

Sept 20, 2011 — Double Stacked Toroid VFO 2008 web page pulled off. It was substandard and some of the material will re-emerge on a VFO 2011 page this Winter.

Sept 19, 2011 — I updated the SWL essay since it was 6 years old and much has changed with respect to Internet radio. Over time I have received ++ emails expressing different views. I am more a SWL than a Ham and offer just 1 opinion and live by a "each to his own" mantra. Context is everything - this is a radio electronic experimenters site that recognizes SWL'ers are important members of the radio community. Click. Wee Willy web page updated again!

Sept 12, 2011 — Design Center concerning popcorn receiver band-pass filters added. Click.

Aug 26, 2011 — Minor update at the end of Wee Willy DSB transceiver. ***New Junk Box Blog format***. Change is good.

July 30, 2011 — New web page QRP Modules listed on the main menu. Currently under construction.

March 31, 2011 — 2 photos added to the Ugly Construction web page

March 19, 2011 — New content; Hobby and Fun 2011 . I'll slowly add more stuff over the year.

Feb 12, 2011 — New content. Miscellaneous RF Experiments 2011

Dec 29, 2010 — New content. RF Workbench Page 3

Dec 12, 2010 — Final additions to the the 2010 Hobbyist Page added — these concern matching FETs, BJTS and diodes.

Nov 10, 2010 — Some editing and 2 photos added to RF Workbench page 2.

Oct 9, 2010 — This October marks the 12th season of experiments for the site. I have 4 partially completed web pages on the go — pure craziness. I decided to finish them 1 at a time and then add them sequentially. Today, a new web page was added and is 1 of 2 supplements to a future main QRP audio page: Audio Transistor Input Impedance Experiments. The first new "permanent" content since March 2010.

Oct 7, 2010 —The Junk box page lay out was simplified: Accommodating the various modern Web devices plus screen resolutions proved difficult with the old html code. Although less impressive, the new format updates quickly and looks the same on every computer.

Aug 15, 2010 — The cable supplying the Internet connection failed. The site went down for 25 hours. Expect more shut downs over the next couple of days as we resolve any remaining problems.

August 6, 2010 — I decommissioned the historic home page URL http://www.qrp.pops.net/default.htm. This page was a html hard-coded parallel version of the the *correct* home page URL http://www.qrp.pops.net. It was just too much work to continue to update the old (pre-2006) home page in addition to the proper home page.

June 28, 2010 — Web subtitle change : **Amateur Radio Electronic Design** to shorten the name and reflect the site's main purpose.

Effective May 17, 2010 — Schematics now use the 16-bit png format. I have abandoned the 8-bit gif format

May and June 2010: The pops.net net control crew rest up for the next big wind storm. The servers lost power for many hours on May 4 and June 12 due to bad weather. Severe storms arising from the Pacific Ocean threaten our AC power lines each Spring.

March 2010

Wide Range L-C Oscillator added to Hobbyist 2010 page. Link **March 7**

JavaScript Applet **K** added to the QRP Tools page **March 11**

RF Workbench Page 2 added. Link **March 15**

February 2010

JavaScript Applet **J** added to the QRP Tools page **Feb 6**

Editing of the Low Noise Crystal Oscillator web page **Feb 22**

RF Workbench Page 1 added. Link **Feb 18**

January 2010

Experiment #6 added to the Hobbyist page **Jan 2**

New content Low Noise Crystal Oscillator **Jan 10**

2 photos added to the bottom of the Ugly Construction web page. **Jan 12**

1 photo added to the Broadband Transformers page **Jan 12**

New content Hobbyist Page 2010 **Jan 13**

New content: Supplement to JavaScript Applet G which is located on the QRP Tools page **Jan 11**

Additions to the Low Noise Crystal Osc page: the DSO versus CRO essay, plus 5 MHz crystal oscillator added **Jan 31**

JavaScript Applets H and I added to the QRP Tools web page **Jan 31**

December 2009

It has been brought to my attention that the email replies I am sending are not compatible with some of the latest email software such as Thunderbird etc. The reason was that I was using a homebrew email program written over 10 years ago. It is now obsolete. A new email platform is now in place along with a completely **new email address**. Consult the email web page for more information. **Dec 30**

Experiment #5 added to the Hobbyist page FAQ updated and edited. **Dec 30**

Experiment #4 added to the Hobbyist page **Dec 26**

Experiment #3 added to the Hobbyist page **Dec 23**

What does the output of a diode ring mixer look like in your oscilloscope? This has become a FAQ. The question is answered in a contribution by Wes, W7ZOI. Big thanks to Wes for this content. **Dec 22**

I am very pleased to present the **Mike, KL7R Memorial Receiver Experiments**. Click here **Dec 19**

New bulleted list format added to this page to improve readability **Dec 19**

A minor addition was added to the bottom of the Ugly Construction web page. Flux pen photo and text. **Dec 19**

Minor updates to the VFO 2008 "Stacked Toroids" web page under **Epilogue - December 19, 2009**

Update to JavaScript applet **Item E: Calculate Cut off Frequency for an RC Low Pass Filter**. Now has a capacitor range from 0.1 nF to 1500 nF. QRP tools page. **Dec 19**

Editing plus a photo added to the broadband transformer page. This page was improved to support an upcoming project. **Dec 17**

Drafting errors on this schematic corrected (fuse position+ negative rail LED polarity). From this web page. Thanks to Paul, K0EET and Tom for the good eyes and their emails. **Dec 16**

VFO Experiments 2009 updated again; 3 images added. Supplemental web page added and updated **Dec 13**

New JavaScript applet added to QRP Tools page; **Item F: dBm calculator. Dec 12**

Nov 22-27, 2009

1 Hertz Precision Time Base added to the Hobbyist Page.
VFO Experiments 2009 added
The top level menu item "Java Tools" was renamed **QRP Tools.** This menu provides a link to my Webmaster's page and some basic JavaScript applets. Some new material will appear on the Junk Box page during this time.

Nov 20, 2009

Finally; Fall-Winter experiments begin. A small update on the VFO 2008 web page under A 3.5 MHz VFO for Diode Ring Mixers was added.
The RF Preamp page was updated with some content that was first presented on the Junk Box web page. I have received a lot of email about these amps and decided to permanently add them to the site.
The W7ZOI file linked on this page is now in pdf format.

Nov 1, 2009

The Ugly Construction web page was augmented and re-written. 2 new photos were added. This term actually came from Wes and Roger Hayward.
A new Electronic Hobbyist page was added to the drop down 2009 menu.

Oct 25, 2009

Some small updates to the Junk Box page were made. I don't ever think I have been so excited about upcoming Fall and Winter experiments as there are a number of cool, new ideas in my notebook. Extra work and travelling have kept me off the bench, but this will cease in mid November. After that, it's back to the work bench. The Fall-Winter experiments will include some HAM, SWL, general electronics and tube guitar amp experiments. Thanks for your feedback and ideas!

Oct 19, 2009

RSS feed. Click on the **orange RSS icon** above to establish a feed. I will only show 1 item; the latest addition of major new content to the site. Additions to the Junk Box page will occasionally be counted as "new content" and will be included on the feed.

Can anyone guess what brand of beer is in the tool box ? Yes.... its

Oct 12, 2009

Fall weather has come to Western North America! Thanks to Cor, PA3COR for debugging the JavaScript code on this page. Apps number D and E now work in Firefox. Rediscover the fun and learning of scratch homebrew electronics!

RF — Test and Measurement

About My Web Site

Welcome Friends!

Introduction

Welcome to the QRP and SWL Homebuilder web site. I write about my experiments with relatively simple and primitive electronic circuits.

Avoiding excessive algebra and obscure parts, I emphasize and show fundamental bench practices.

Through real experiments I examine topics to challenge and intrigue amateur designers — providing examples and describing ways to plan, problem solve, breadboard and measure your circuits.

As amateur experimenters we ought to advance in our hobby; not just perform cookbook electronics. Designing and improving your circuits requires considerable knowledge and effort. Fortunately, others selflessly share their ideas to teach us.

OUT
GEN2
GEN1

In time, you may recognize your electronics workbench as your greatest teacher. Bench experiments involve us thinking about and measuring our circuits so we know what's happening instead of relying too much on folklore, guessing and copying others. Designing and/or simulating circuits with software can enhance your learning but does not obviate the need to spend time in the trenches with meters, wires and solder.

People often learn skills by modeling others. We need sound examples of how other builders work and think to inform our own designs — inspired, creative and active learning driven by experience and reflection.

At some level, our bench experiences are stories of growth and realization sparked by going and doing. For example, why did the designer choose a particular resistor value? You try different resistor values while measuring the results and increase your knowledge. Collecting schematics, kit building or just thinking do not provide as intimate a learning experience as soldering your ideas on a bare copper board. Talking, tweeting or day dreaming about design is not the same as *doing it*.

Russian novelist Fyodor Dostoyevsky describes the contrast between real life and passivism; "love in action is a harsh and dreadful thing compared to love in dreams", The Brothers Karamazov, Братья Карамазовы. Dare to dream, but better yet, dare to innovate — to design and build *your own* circuits. You may start by just modifying a favorite circuit or scaling a stage to another frequency. We need more innovators and less imitators to grow and sustain our great hobby.

Electronic design produces more than a completed circuit. On the bench, even joy is experiential – a moment of discovery (or several discrete moments) yields more pleasure than stuffing a circuit board or operating a piece of gear. Creativity trumps process every time!

I hope this site demonstrates my passion for building basic, "popcorn" circuits and sharing ideas. Please remember I am just a lay person experimenter and not an electrical engineer.

Regards, Todd, VE7BPO

Essay for 2010

Building or buying test equipment and acquiring a good reference library are important to your experiments. Spurred by the realization that sound bench measurement practices are at the heart of good design, test equipment receives greater focus in 2010 and on.

A reference library is vital to our electronic experiments; good examples lead to better experiments. Poor circuits are everywhere and some builders can't tell a good design from a bad one. Minimalism and simplicity aren't excuses for sloppy design when your goal is to learn. Collecting and sharing well designed circuits helps us avoid wasting time and experiencing frustration. Circuits with attributes like well defined input or output impedances, low noise or harmonic distortion are desirable to fuel experimentation. Look for better quality circuit examples in 2010 and on.

The Internet is changing how we read and write. The prevalence of small portable web devices such as iPhones, ever increasing numbers of web sites and blogs, and the use of search engines create fierce competition among sites. Modern sites attract your attention with varied visual, aural and textural media and unfortunately, hype and pseudo-journalism. Narrative writing is more skimmed than read. Brief is in — bullets, subtitles, lists and graphics replace long lines of narrative prose which no one seems to have time for anymore.

Have you noticed the changes on this website? New content still contains lots of narrative writing, but assumes an active voice, with emphasis on brevity, clarity and speaking directly to you, the reader. Sharing mostly obsolete, analog 1970's-style circuits, QRP/SWL HomeBuilder attracts a tiny, niche audience. I believe the success of this website depends on providing good and diverse content — not Tags, RS feeds, adopting net-speak, or self promotion. You be the judge.

Essay for 2014

The Internet of Everything?

Bucking the trend, my contribution to amateur RF homebrew remains informational and not social. Why?

Social media information represents a Pandora’s Box of good science and opinion, mediocre thought, or trash potentially created and/or disseminated by anyone who’s connected. We accept that much of our social media content doesn’t come from the best or brightest — some people are just plain interesting, or express themselves vigorously, seem like-minded, or touch our hearts.

Some builders, like me, seek objectivity and not just “likes” and “follows” based on sentiment and spectacle. While a few radio builders may prefer to join hands and sing Kumbaya, or pat themselves and others on the back simply because their breadboard actually works, a trifling of us care more about how and why our circuits work. We *like* measures and measurement tools and *follow* science, experiments and the works of those who shine brightly.

What’s wrong with plain information, unfettered discovery, experimental rigor, objectivity and rational, kind thought?

It’s not that these characteristics don’t attribute social web clients — they do, but the negative impacts of social media worry me a little. A brief list of concerns: loss of privacy, the threat of wasting time while really just isolating ourselves from our real friends + family. The numbing exposure to the Internet of Ads and Spam. Still too, bubbling up like purulent sores come the charlatans, the misinformation peddlers, the opinion spammers, and those who anonymously leave stinging sarcasm, or outright hatred [hostile online comments that attack people, or divert a healthy flow of ideas].

Running a low-tech web site with nearly 0 commercials suits me better.

SEO — Search Engine Optimization

I’ve read that Google analyses your web site content, the number and quality of the sites that link to your pages, their search engine clicks and so forth. In part, Google seems to rank a site based on how relevant and authoritative they believe it is. Some people specifically employ SEO techniques to gather in more traffic.
To my surprise, each year, tens of thousands come to this site via search engines like Google. I don’t think my material seems too relevant or authoritative. I’ve made no effort at SEO, so I conclude that you, my readers have more to do with the site’s success than anything I’ve ever done.

Thank you.

Hope Invigorates

Invigorated by the excellent work either emailed to me by experimenters such as Michel F6FEO, or Dick, N4HAY; or posted on blogs or Community sites like Yahoo, I feel hopeful about the future of our hobby in 2014. The PHSNA Yahoo group leaders, the recent work of Jason, NT7S, Steve VE7SL and many others show that *amateur design* experiments still have a pulse + respirations.
The aforementioned get my vote for their MOF like behavior: a strong blend of creativity, tradition and quality.

Looking Ahead — Future Site Content

Most of my new receiver work involves quadrature and in-phase mixers fed with (2) local oscillators; 1 output shifted 90 degrees from the other — essentially, EMRFD Chapter 9. Even my Funster [a personal, lowbrow trans-receiver I drag onto hill and dale] now contains phasing receiver circuitry to reduce the opposite sideband by 20 dB along with further low-pass filtering. I hope to add some Funster content to HF Embarcadero in Winter 2014. Like many of you, the 1 resource I lack the most is time.
While I'm thrilled with the notion of a receiver appliance that contains just an antenna, LNA, ADC and some sort of "wonderfall" display or speaker, I'm still smitten by analog design with hardware. Still, the I-Q mixer will offer a nice transition into SDR should I ever wish to spend my free time writing C# and not melting solder.


Kumbaya Factor
Unit = dBk
Asks how, why & what next?
Review article
Rehash old topics without re-engineering or analysis
Advance knowledge base
Kumbaya factor
Folklore, feel good, fall back
0 dBk
10 dBk
Test and Measurement
Matrix to evaluate Amateur Radio technical material
Trivia and Entertainment
New ideas and circuits
Hold hands and sing Kumbaya

Best to you!

Miscellaneous

My special thanks to Wes Hayward, W7ZOI for his generous support and elmering over many years.

EMRFD is the main reference of my site

All permanant content circuits were built and tested. Schematics are drafted as carefully as possible. Please accept that bench and/or drafting errors may occur. No liability arising from the application, use, or misuse of these projects that results in direct or indirect damage or loss is assumed.

Full price is paid for all parts used and no monies are or were received for promoting any products or companies on this web site. Any ads, hyperlinks or mention of commercial products or companies is out of courtesy only.

"Until you build and measure it, you don't know what you don't know";
Rick Campbell, KK7B; VHF Open Sources — Design of Low Power High-Stability Low Phase Noise Single Frequency VHF Sources with High Spectral Purity; 2008

Information Regarding the Compression of Schematics

I see many electronics web authors compressing black and white schematics as jpg files. This results in distortion of the schematic. Schematics are best compressed using the 8-bit, lossless LZW algorithm which means converting the file to a png, gif, or even pdf format. The files sizes will typically be smaller than .jpg compression, have no distortion and can be edited easily.

- RAC is the National Amateur Radio Society of Canada
- For my web page concerning support of the **Radio Amateurs of Canada**, please click here

---



The hand drawn image bitmaps on this web site (logo etc.) are by Rod Adams. All website photographs were taken by VE7BPO except as indicated.


QRPHB Design Center
Java Script Applets

1. Click for the old QRP HomeBuilder Graphics page. Click for my Pin Outs page. Click for my Homepage

---

2. Some simple tools written in JavaScript for the QRP/SWL HomeBuilder:

`Minimal input error checking`

A. Calculate DC Voltage Divider Bias


Voltage
R1
Bias voltage
R2

Enter Voltage: Enter R1: Enter R2: Bias voltage =

B. Calculate Inductive Reactance

Enter Inductance in uH: Enter Freq in MHz: XL (ohms) =

C. Calculate DC Current for a Current Mirror



Enter VCC: Enter RC in ohms Current (mA) =

D. Calculate # of Turns To Obtain a Desired Inductance on a Ferrite Torroid

Enter Inductance in millihenries: Select Core: FT37-43 Turns =

The *AL for this ferrite core is* =

E. Calculate Cut off Frequency for an RC Low Pass Filter



Enter resistor value in ohms: Select capacitor values in uF: 0.01 3 dB down frequency (Hertz) =

F. Calculate Power in dBm and mW from Peak to Peak Voltage



Enter measured peak-to-peak voltage into a 50 ohm load: dBm, mW

Application Note: This web site follows the EMRFD standard for dBm power measurement. dBm = the power delivered into a 50 Ohm resistive load which is temporarily substituted at that point in the signal chain.

G. Calculate Lm and Cm For a Crystal using the G3UUR Method

ABRACON
5.0000
AB 0436

Enter frequency in **MHz** written on crystal (series resonant frequency):

Enter measured frequency in **MHz** with switch open: Enter measured frequency in **MHz** with switch thrown:

Enter crystal capacitance in **pF**: Enter open switch circuit capacitance in **pF**:

Cm = femto Farads , **Lm** = Henries

Supplemental web page for this applet: Crystal filter measurement and adjustment Link

H. Calculate Decibel Power Gain or Loss from 2 Peak-peak Voltages



Enter voltage 1: Enter voltage 2 dB gain or loss =

I. Calculate Decibel Power Gain or Loss from Input and Output power

Enter input power in watts: Enter output power in watts dB gain or loss =

J. Calculate dBm and mW from RMS Voltage (50 ohms)

Enter RMS voltage dBm mW

K. Calculate Return Loss and VSWR (50 Ohms Detector)



Enter the detector signal in pk-pk volts when the unknown port is terminated in an open circuit:

Enter the detector signal in pk-pk volts when the unknown port is terminated in the unknown impedance:

Return loss = dB, VSWR=1:

Measurements per Figure 7.41 EMRFD. Schematic here

L. Calculate Power from the DC Output of an AD8307 Meter

1. Linear calibration steps:

Enter measured DVM voltage at -10 dBm:

Enter measured DVM voltage at -20 dBm:

2. Calculate power in dBm from DVM voltage:

Enter measured DVM voltage:

Power =

M. L-C-C Tee Network



Enter **frequency** in MHz:

Enter **R1** in Ω:

Enter **R2** in Ω:

R1 must be < R2, but the network is bi-directional

Enter Q: *Perhaps start with 2-5*

C1 = pF, C2 = pF, L = uH

N. Parallel Resistor Values (2-4 resistors)



Enter R1: Enter R2 Enter R3: Enter R4:

R = ohms

O. LCR -- a Reactance Calculator In beta -- do not use !

Mode: L C to Reactance Inductance: uH Enter frequency in MHz



This page last updated: September 21, 2013

RF — Test and Measurement

Short Wave Listening коротковолновое радио

Introduction to Short and Medium Wave Radio Listening

Short wave radio listening was a childhood passion and I enjoy being an SWL just as much today and log at least 800 hours of SWL per year. There seems to be many web pages devoted to construction of radio equipment for the amateur radio experimenter but relatively few for the shortwave radio devotee. I decided to expand this web site to include projects for the SWL Homebuilder in 2005.

My favorite bands are 49 meters (5.9 - 6.2 MHz) at night-time and 19 meters (15.1-15.8 MHz) during the daylight hours. I also listen to medium wave DX around 1400 - 1600 KHz.

Why Listen to Analog Short Wave Radio?

Is analog short wave radio dead? I think not.

No doubt, short wave radio has passed its prime and is slowly dying, however, it's still fun and/or relevant to some.

World band radio: Almost 1/2 of the world's population lives on $2.00 *USD* or less per day. The Internet (the main alternative to shortwave radio) poses a luxury to many poor people living in lower-income countries — experienced travelers or those who support people in developing countries will understand this statement. In some countries now, ranking in the middle class just means you have a full-time job. In addition, oppressive governmental regimes may limit foreign media and Internet access: LW, MW and SW radio can break through obstacles such as natural or man-made disasters, borders, poverty and censorship.

For SWL hobbyists, analog shortwave radio entertains, informs and best of all, provides opportunities to analyze propagation and experiment with real radio topics including static, solar flares, QRN, antennas, grounding, baluns, coax, and wire. SWLing poses an adventure — it's unpredictable, challenging and increasingly difficult as stations decrease and QRN increases. I've built many antennas and even some noise cancelling circuits just to pull in a few Dx stations. The sport of SWL lies in making DX contacts: a theme shared with Ham radio.

What About Internet Radio?

Radio by definition is the transmission and reception of electromagnetic waves of **radio frequency**; but perhaps blue-tooth or Wi-Fi reception from a hot spot qualifies as *radio* in the modern era? Just as peanuts aren't nuts, Internet server or webcasted radio is not RF broadcasted radio. I think Internet radio is great, but fundamentally a very different medium from that enjoyed by SWL fans

Internet radio involves a radio player decoding a stream of compressed bits fed from a Internet radio station or virtual receiver. In some cases, the material originates from a real radio station that also broadcasts an AM or FM signal. For example, you can tune FM station Rooskie Radio "Русское Радио" in much of Slavik Europe or play them on a computer device anywhere you can get an Internet connection.

For lovers of foreign content, listening to Internet radio makes sense; providing convenience, a good signal when bandwidth is high and 24 hour per day listening on 1 IP address. Internet radio offers a much cheaper way for content providers to beam their news and music services around the globe — we've seen numerous large broadcast radio services such as the BBC World Service reduce or drop analog SW and add Internet radio, satellite and digital SW transmissions for their customers.

The exciting growth of independent and niche Internet radio stations increases personal freedom of choice and provides opportunities for unique interest providers and consumers to find each. Media streaming companies and manufacturers of Internet radio *players* and their worldwide distributors benefit too.

This technology is a far cry from tuning the SW bands with a homebrew or commercial radio frequency *receiver* and a length of wire slung in a tree. Perhaps, the greatest advantages of Internet radio are that you don't have to get up early, or stay up late to pull in some rare Dx, nor do you need any radio skills or special equipment — perfect for the majority of listeners. But we're SWL radio hobbyists: people who listen for both content and because we love radio propagation and gear.

There is nothing wrong with Internet radio, or any of the modern data streaming techniques however, SWL aficionados driven by skill, the thrill of Dx and love of their experimental hobby share a special bond that Internet radio doesn't give them.

ICOM
IC-R75
COMMUNICATIONS RECEIVER
10.000.00
PHONES
POWER
AF-⊙-RF/SQL
TWIN PBT
SSB
CW/RTTY
FIL
AM
FM
TS
CLOCK
V/M
MW
CLR
SEL
SCAN
▼DN
UP▲
ENT
P.AMP
ATT
NR
ANF
NB
AGC

Assembling a station The most important component in your radio shack is your antenna. Don't hesitate to safely experiment with the many antenna designs available on the world wide web. Your sure to find a commercial unit or home brew antenna design that suits your real estate and budget.

Your next task is to find a receiver. It is difficult to recommend any one receiver because there are so many excellent commercial receivers to choose from. If you are thinking about purchasing a used receiver, you might consider checking eBay to find a receiver or to learn the going price for used gear. The ultimate SWL experience in my opinion is to build and operate a receiver on at least 1 band.

Favorite SWL and SWL-related Web Sites

Wikipedia-Shortwave Bands A good description of the bands and their general propagation.

Canada's SWL-DXer website 🍁 Hard core Canadian web site dedicated to SWL. Thanks gentlemen!



http://www.bobsamerica.com/swl

http://www.dxing.info/

Doug's Shortwave Radio Page

AA6V's SWL Links

Method for soldering a PL-259 to RG-213 or RG-8

Digital Modes For SWL Fans

PSK31


VE7BPO - DigiPan
File Edit Clear Mode Options View Lock Configure Help
Lookup CQ Call 3 Call BTU Signoff File Brag T/R Squelch Clear Multi
Call: Name: QTH: Rec'd: Sent: Band: Notes:
1000
2000
3000
TX RX IMD: Sq AFC Snap

Band: 20m

ng theory and slowing down for everyone else on the air.. hihi but now days i would be doing real well to get 5 wpm.. hihi love psk ..started working it last sep and its a great mode to rag chew with... i also work sstv and ssb.. so i have a lot of modes to pick from.. and dont need cw any more.. good luck with the tripple play.. i dont try for those things.. i am just a rag chewer at heart and thats abt all i do ron.. and send pics on sstv.. hihi so you have a nice day and bye for now.. enjoy that warm wx..

BPSK31 04/12/2009 19:05:42 z

There are a number of good sites about this relatively new HAM mode. All that you minimally need is a receiver dialed in at 14.070 USB (or another

PSK31 frequency), a microphone hooked to your computer sound card and some free software. The software (DigiPan 2.0) is available at http://www.digipan.net/ .

I use a USB interfaced microphone and place it about 2 cm from my receiver speaker. If HAMs are operating; you should hear some warbles and see some waterfalls on your screen. Click on one of the waterfalls to begin receiving the text. I knew nothing about this mode, but was up and running in 15 minutes.

Additional Short Wave and Medium Wave Receiver Photos

OPTIMUS
FM
MW
LW
SW
MHz
kHz
kHz
88 92 98 104 108
530 600 800 1100 1700
150 175 200 240 280
5.81 5.90 6.10 6.20
7.10 7.30 7.45 7.60
9.45 9.55 9.70 9.90
11.55 11.70 11.90 12.15
15.10 15.30 15.50 15.70
17.45 17.75 18.00 18.15


BC 54 6 7 8 10 16 KC
6 TRANSISTORS
RCA VICTOR


RCA VICTOR
RCA VICTOR
SISTOR
DIO
MODEL GP-626
RCA VICTOR


BC 54 6 7 8 10 16 KC
6 TRANSISTORS
RCA VICTOR

Amateur and Short Wave Radio Electronics Experimenter's Web Site

RF Preamps

W1FB 6M RF Preamp

Discussion:



Q1 MPF102 , J310 , U310

T1 Main = 11 turns # 24AWG on a T37-6 or T37-10
Ant winding 1 turn , Q1 source winding 3 turns

T2 Main = 11 turns #24AWG on a T37-6 or T37-10
Drain tap is 3 turns from variable cap end of main winding
Output winding is one turn

Here is a schematic sent to me by W1FB many years ago. It is very similar to a 6M two-stage preamp that he published in QST in the mid eighties. Doug really favored the grounded gate FET for narrow band preamps. His published work is replete with examples of them on just about every band. I built that amp and remember getting about 10 dB gain, which is all that I wanted for the 6M direct conversion receiver using a diode ring detector that I was building. The great feature of the amp is that it combines a band pass filter and preamp in one. I lost the original schematic that Doug sent me but was delighted to see that I made a bitmapped drawing of it on a floppy disk that was recently re-discovered when we were moving an old desk. The shield shown in the schematic was a small piece of grounded ,double sided PC board in which, I made a small chamfered hole in to pass the lead going to the T2 tap. The shield, along with very short component leads will help minimize parasitic oscillations. The T2 tap is 3 turns down from the end of the T2 main winding that connects to the variable capacitor. Doug specified T37-10 cores for the inductors, but I substituted T37-6 cores and used the same number of windings as specified for the T37-10 core inductors. It worked fine.

VE7GC Popcorn RF Preamp

Discussion:

Here is an easy RF preamp by Dick Pattinson, VE7GC. It uses a single tuned circuit at the front end and can connect directly to a mixer or product detector in a simple receiver project. Note how Dick provided adjustable RF gain control for this circuit in his Wee Willy project on this website. If you can not find Tak Lee green 10.7 MHz IF coils, probably any other brand of 10.7 MHz slug tuned IF transformer would work. The Mouser catalog number is 421F123 . If your 10.7 MHz IF coil has a built in capacitor at the base , remove it. A fixed inductor may also be wound using a powdered iron torroid core and then all or a portion of the C1 capacity would be made variable. The input impedance is 50 ohms and the output impedance is low due to the Q2 emitter follower stage.


VE7GC RF PREAMP
VCC 12 volts
100
0.1 uF
4K7
Q2
47 pF
Q1
Input
T1
1M
C1
4K7
4K7
0.1 uF
0.1 uF
To RCVR
T1 10.7 MHz IF coil (TAK LEE or equivalent)
C1 100 pF for 7 MHz , 300-400 pF for 3.7 MHz
Q1 MPF102
Q2 2N3904 or 2N2222A

A Low Noise, High Dynamic Range Broadband RF Amp

Discussion:

This schematic is a version of a circuit developed and patented by David Norton and Allen Podell in June 1974. This variation was described by Joe Reisert, W1JR in the now defunct Ham Radio Magazine. The Norton design uses transformer coupling to achieve "noiseless negative feedback" and is really outstanding.
A great article utilizing and augmenting on this technique receivers is by Jacob Makhinson, N6NWP in QST magazine for Feb 1993 with "A High Dynamic Range MF/HF Receiver Front End". Makhinson arranged 2 in push-pull to obtain excellent results. Obtain a back-issue of QST for closer study. **Note** that the fore mentioned Feb QST article has the coil phasing wrong and the correct phasing can be seen at this web site from QST for July 1996. There is also information about Norton feedback RF amplifiers in EMFRD.


High Dynamic Range RF Amp
VCC
.01 uF
100
.01 uF
8K2
Ferrite Beads
Nb
Q1
Na
.01 uF
Output
2K
1b
Mb
.01 uF
Ma
1a
.01 uF
Input
RFC 22uH
51
Q1 2N5109 or MRF581
Balun Core BN43-2402
Ferrite Bead FB43-101
50 ohms Z In and Out
Four Practical Transformer Ratios
1
N
M
R Load
N = 1 , M = 2 , GAIN = 6 dB
N = 5 , M = 3 , GAIN = 9.5 dB
N = 11 , M = 4 , GAIN = 12 dB
N = 19 , M = 5 , GAIN = 14 dB
Balun Core Winding Info
1a
1b
Ma
Na
Nb
Mb

If you are building a contest-grade receiver and need a good RF preamp and/or post mixer amplifier, the Norton type is quite suitable. An amp built using a 2N5109 can have a noise figure in the 2.5 - 3dB range. I have also built them with 2N3866, MRF517, MRF581 and a 2N5179 although the last transistor would be a somewhat poorer choice. This schematic with a 2N5109 is good from 1.8 to 150 MHz with a 1.2:1 VSWR or less according to Joe Reisert. I have even put one in a friends CB radio and he was delighted.

Winding and Construction Hints

Making the Norton amps requires some planning to keep all component leads as short as possible. The transistor leads and any connecting components should be trimmed as short as practical to promote stability. Sketch the component layout on a piece of paper and modify it until you are satisfied you have designed a good layout. The ferrite beads on the transistor collector aid in stability and should be used to preserve the noise figure by squashing any oscillations should they develop. The 22 uH choke can be the little epoxy coated units that are color coded and look somewhat like resistors. Do not use a choke less than 22 uH.

Before winding, the builder must first decide how much gain is needed from the amp. For an RF preamp, the stage should have gain equal to or greater than the passive stages after it. Also there will be losses in the transformer, so the theoretical gain of the Norton amp maybe 1 dB off and will need to be factored in. For the purposes of discussion, a 9.5 dB amp is desired , so N = 5 and M = 3. The first step is to mark one side of the core with a dab of liquid paper, paint or a small piece of tape. This will allow you to keep track of the transformer later. To mark, hold the core so that both channels are parallel to the floor, one on top of the other. Apply your dab of paint to the top of the core and use the marked top to denote the A windings. 1a, Ma and Na will all start from the top channel in the balun core. Using 32 AWG wire for all three windings, start with winding 1 and wind the single turn from point 1a to 1b. Cut off the leads so they are shorter than 5 centimeters (2 inches). Next, wind Ma to Mb three complete turns through the binocular core and trim the leads if needed. Tie a small knot in the wire at both ends. This will clearly mark this M winding. Both windings should look like the diagram under the schematic. 1a to 1b are on the left of the balun core and winding Ma to Mb are on the right side of the core. Mb has a distinguishing knot at the tip of both wire ends. Ma starts from the top of the core which you have marked with a dab of paint or something. Finally, wind Na to Nb five complete turns through the core in the same direction as the previous winding M. Strip wires Na and Mb (Mb has the knot), twist together and solder. Scrape the enamel off the leads **very** gently with a sharp hobbyist knife.

Insert the transformer in your circuit and cut the leads to their proper length and then solder away. It maybe preferable to pre-strip the leads on winding 1 as it is hard to strip the enamel off a fine wire that has only one turn and it may accidentally pull out of the core. If it does, just re-insert it into the balun core on the correct side. Once you have soldered Na and Mb you can always identify the windings later because you have marked the top of the balun core which denotes the A windings. Try and make your windings gently tight as if there is too much slack you may have difficulty getting the last few windings thru the core channels. A 14 dB gain amp maybe **impossible** to wind with 32 AWG wire, it may best to use 34 AWG for that amplifier. I have never built one for greater than 12 dB. The transformers are a bit tedious to wind, however persevere and the results will be well worth it. For HF, you can substitute 0.1 uF caps for the 0.01 caps shown if you like.

Toroidal Inductor Norton Amp Experiments

Discussion:

The amp shown in the schematic to the right uses a ferrite torroid for the transformer and has ~10 dB gain. Winding 1 turn of wire over the cold end as shown in the schematic is tricky. Try to keep this link as short as possible. A ferrite bead or a 22-51 ohm resistor on the transistor collector is desirable. You can try increasing the turns (1:21:5 etc) to experimentally obtain more gain from this amp. The torroid version is a valid option for builders who do not have balun (binocular) core ferrites in their junk box. Toroidal inductors are certainly easier to wind then binocular core versions.

In 2007, I built several Norton "noiseless feedback" RF amps using FT50-43 and FT37-43 ferrite torroids. These are outstanding and I recommend using them in projects. The input and output Z is 50 ohms. The overall BJT topology is reminiscent of a common base amp. I have some basic information concerning this amp on this web page . They are straight forward to build. The biggest problem is the phasing of the single turn link. Get it wrong and your amp can turn into an oscillator.

Figure 1



Q1 = 2N5109 or NTE 123 etc
T1 = Secondary: 15 turns with a tap a 4 turns from the cold end.
Primary: 1 link over cold end
T1: use FT50-43 or FT37-43 ferrite



Shown above. The breadboard of Figure 1.


Figure 2
Input
6 MHz RF
75
.1
T1
100
100
1
4
11
4K7
470 uH
.1
.1
75
- 10 dB
Q1
100
100
- 10 dB
~ 4 dB gain
1K
.001
68
T1 = 15t FT50-43 Ferrite, tap @ 4t
Output

Shown above is the Figure 1 amp above (labeled Figure 2) with a 50 ohm -10 dB pad on the input and output, so gain is low. I used these pads to evaluate the amp in a number of experiments. I never got around to writing up these experiments on the web site and likely never will. I wish I had more time as my notebooks are full of unpublished experiments that would be great content for this web site.



Figure 3

Input
6 MHz RF
75
.1
T1
470 uH
100
100
1
5
21
.1
- 10 dB
4K7
.1
75
100
100
Q1
- 10 dB
1K
.001
68
Output

10.7 dB gain

T1 = 26t FT50-61 Ferrite, tap @ 5t

The amp above (labeled Figure 3) is a hot one; 10.7 dB gain even with 10 dB of attenuation. You can leave off the input pad and decrease the output pad to -6dB if you want or require a wide band, low noise RF amp with lots of guts. Most builders use binocular ferrite cores for the inductor, but torroids work fine for many applications.


correctly
phased link
incorrectly
phased link
VE7BPO
14863370

Shown above is a photograph of 1 of the experiments from 2007. The one turn link from the Norton amplifiers just above is shown phased correctly and then phased incorrectly. Note the oscillation in the "badly wired" amp at 14.86 MHz. I routinely check all of my noiseless RF amps using the oscilloscope. Occasionally, I will put a shunt coil and cap (from input to ground) on the input to "exaggerate" any oscillations. This has proven to be a useful technique for testing if the phasing of the one turn link was done correctly.

RF preamp for the 40 Meter band with 3 tuned filters


7 Mhz Front end
50 ohms
RF in
47 pF
220 pF
CV
68 pF
5 pF
L1
CV
100 pF
T1
23
5
180
.1
51
s
d
g
J310
1K8
CV
100 pF
T2
24
4
50 ohms
100
.1
12.24v
L1 = 2.1uH = 23t T50-6
T1 = 23t T50-6; tap 5 from gnd
T2 = 24: 4 turns on a T50-6
CV = 8 - 70 pF trimmer cap
~ around 7 dB gain
VE7BPO
0.
B
t
div.
m
6.03
Frequency
MHz
0.20
Freq./div stop
8.03
C:\Do

An experimenter's 40 Meter band front end for CW. This has a double-tuned filter and a low gain, lower noise RF amp. Great circuit for isolation of a product detector or mixer in a popcorn receiver.



A photograph of the above 40 meter band front end, double-tuned filter plus tuned common gate RF amplifier. Input and output Z is 50 ohms.

Amateur and Short Wave Radio Electronics Experimenter's Web Site

QRP HomeBuilder Software

Disclaimer:

THE QRP HOMEBUILDER SOFTWARE OFFERED HEREIN ("THE SOFTWARE") DOES NOT COME WITH ANY WARRANTY, EXPRESS OR IMPLIED. IF YOU MAKE USE OF THE SOFTWARE, PLEASE BE AWARE THAT YOU DO SO AT YOUR OWN RISK. NEITHER THE AUTHORS OF THE SOFTWARE AT JENNA DESIGN NOR ANY OTHER PARTY WILL ACCEPT RESPONSIBILITY FOR ANY OCURRING OR UNFORESEEN CONSEQUENCES OR DAMAGES THAT ARISE AS A RESULT OF THE USE OR MISUSE OF THE SOFTWARE.

Technical Info and Distribution

The QRP HomeBuilder applications are written in C++ for speed and compactness. Apps will specified as GUI (graphical user interface) or 32-bit console based (DOS look). Anyone may display or distribute these applications via website or diskette providing that they do not charge for the program(s). I know longer have a C++ compiler and no future work on these applications is anticipated.

QRP - RELATED APPLICATIONS FOR DOWNLOADING

CoilBuilder_99

CoilBuilder_99 is a powdered iron inductor winding application. Enter desired inductance, select core size and mix and press the Calculate button to determine the correct number of windings for your inductor. Data is also given showing, core color, permeability, frequency range, AL value and maximum number of turns versus wire guage for the chosen core size. Encompasses 12 different core sizes and 8 different mixes of powdered iron. Calculated results can be stored on a disk file or printed out.

Style: GUI, File size: 90K, zipped, 44K.

Bug Fixes: Some missing AL values for # 7 material added April 24/99. K6WHP's superior version is linked below.

Current Version is: 4 / 24 / 1999

Download the CB99.zip file

PI Filter Designer

PI Filter Designer is a simple 3 element 50 ohm input and output impedance pi filter designing application. This program allows the user to design simple lowpass filters by selecting from a variety of standard capacitor values either empirically or to suit what you have on hand. The filter 3 dB cutoff frequency and required L1 inductance are automatically calculated and displayed. In addition, the user may select an additional capacitor value to put in parallel with both caps C1 and C2. In this app XL = XC = 50 ohms impedance. No other impedances can be calculated with this program.

Style: GUI, File size: 47K, zipped, 22K.

Current Version is: 1 / 14 / 1999

Download the pifilter.zip file



CapCoder

CapCoder gives the capacitance in microfarads, nanofarads and picofarads and tolerance of any capacitor code entered into its input section. Example : 104J. This app uses numeric spin-buttons and a combo box so that no typing is required for data entry.

Style: GUI, File size: 48K, zipped, 22K.

Bug Fixes : A nanofarad conversion error was corrected July 2, 1999.

Current Version is: 07 / 02 / 1999
Download the capcoder.zip file

Resistor Coder

Resistor Coder gives the resistance in ohms of any resistor color code entered into its input section. Four or five band resistors can be accommodated by this program. This app uses drop-down combo boxes so that no typing is required for data entry. Results may be saved to a disk file or directly printed.

Style: GUI, File size: 58K, zipped, 27K.

Current Version is: 1 / 16 / 1999
Download the resistor coder.zip file

Ferrite

Ferrite is used to calculate the number of turns required on toroidal ferrite cores to achieve the desired millihenry-value inductance. 15 different ferrite toroids are included in this application. This program will calculate the winding data for an inductance range of 0.001 to 27 millihenries.

Style: Console, File size: 64K, zipped, 31K.

Bug Fixes: Thanks to PA3CKR for the bug report; fixed Jan 19/99.

Current Version is: 1 / 19 / 1999
Download the ferrite.zip file

Universal Diplexer

Universal Diplexer calculates the inductance and capacitance values for a Bridge-Tee diplexer based upon a chosen superhet receiver intermediate frequency. The diplexer is the Joe Reisert, W1JR popularized design discussed under Diplexer Topics on this web site. The user inputs an IF and presses the Calculate button to have the capacitor and inductor values given in pF and uH respectively. The diplexer schematic is included in the application. Note that the this is for the Q = 1 version of the Bridge-Tee Diplexer.



Style: GUI, File size: 49K, zipped, 22K.

Current Version is: 1 / 19 / 1999
Download the diplexer.zip file

HF Dipole

A very basic program for calculating the length of each leg of a 1/2 wave wire dipole antenna. Program good for 1 - 500 MHz, although intended for MF - HF useage. This app does nothing more than the standard 468/freq (MHz) type calculations. It was written for DOS many years ago and ported to Windows. The output shows the 1/2 wavelength and 1/4 wavelength design wire length in feet and meters. This app is probably of no help to experienced antenna designers.

Style: GUI, File size: 46K, zipped, 22K.

Update : Minor improvements made Feb 9, 1999

Current Version is: 2 / 9 / 1999
Download the hf_dipole.zip file

Resonator



This application calculates the inductor and capacitor values for the tank circuit of a simple bipolar transistor RF amp. The basic schematic is shown above. Enter the center frequency plus the inductive/capacitive reactance you desire and press the Calculate button to calculate the necessary inductance and capacitance for L and C respectively.

Style: GUI, File size: 50K, zipped, 21K.

Current Version is: 1 / 23 / 1999

[Download the resonator.zip file]

NPN DC-BIAS

This application calculates the various voltages and currents of a simple voltage divider bias NPN bipolar transistor amp. The following is calculated: IB, IC, IE, VE, VB, VC, VCE and detection of Saturation or Cutoff. The user can alter the VCC, VBE, transistor beta and any of four resistor values R1, R2, RC and RE by picking the transistor value from a standard-value resistor table or manually entering the value. The schematic illustrates some of the voltage measuring points on the transistor schematic. *This app is in final BETA.*



Style: GUI, File size: 73K, zipped, 32K.

Current Version is: 16 / 04 / 1999

[Download the nbias.zip file]

Amateur and Short Wave Radio Electronics Experimenter's Web Site

Popcorn Direct Conversion Main Frame

Discussion:

Note: if you click on a schematic, a larger version will appear in a new web browser window.

Shown to the right is the schematic to a low cost popcorn direct conversion receiver main frame. To complete the receiver, a front end band pass filter and a VFO with an output power of 7 dBm is required. This is indeed a frugal project using 4 cheap transistors, an RC low pass filter and an LM386N for output power to a pair of low-impedance headphones. The builder also has a choice of 5 diplexers and an optional mute circuit. This receiver is easily built using Ugly Construction and can be built in 3-4 hours with a bit of luck.


Popcorn DC Receiver Main Frame
+ 13.8 VDC
100K
1K
22uF
Q1
22uF
10K
100K
4K7
4K7
4K7
VFO
LO
RF
AF
?
BP Filter
Product Detector
Choose an AF Diplexer
Q2
Q3
C1
C2
C3
.022
2K2
22K
22uF
10K
10uF
Low Pass AF Filter
AF Preamp
+ 13.8 VDC
1K
22uF
10
91K
4K7
47uF
.22 uF
Q4
1uF
LM386N
100uF
3
6
5
2
4
100
10K
10
10K Pot
390
10uF
.1
AF Amp
PA
Phones

Q1 - Q4 2N3904 , 2N2222a etc
Detector 50 ohm Diode Ring Mixer
C1 - C3 CW .047 uF
SSB .015 uF

drawn July 10, 1999

Product Detector and Diplexers

The 50 ohm diode ring product detector can be commercial units such as the Mini-Circuits SBL1 or TUF-1 or homebrewed 50 ohm impedance units. Five simple "diplexers" are shown in the lower "Adjuncts" schematic for you to choose from. The one you choose will depend on available parts, cost and your requirements in a popcorn receiver such as this. These diplexers are mostly of the low pass filter variety and provide a ~50 ohm termination to the diode ring mixer and some matching to preserve the product detector dynamic range. I realize that except for (A) and (D) these audio frequency filters are not truly diplexers and will not provide DC to daylight matching. The intent of this web site is not high performance-high cost


A
10 mH
2.2uF
2.2uF
51
10 mH
B
2.7 mH
22uF
1 uF
51
20 turns
#28 AWG
FT37-43
C
.1
22uF
51
D
2.7 mH
1uF
1uF
10uF
51
2.7 mH
E
47 mH
.1
1uF
33uF
51
POPCORN DC
RECEIVER
ADJUNCTS
To VCC
From Q4
SideTone
Input
10
1uF
47uF
F
1N4148
2K2
Q5
Apply VCC to
Mute Receiver
.1
6K8
10K
Pot
3
2
6
4
5
100uF
10
.1
drawn July 11, 1999

design and please do not confuse it as such. Note that electrolytic capacitors that bypass to ground such as the 1 uF caps must be non-polarized or bipolar for best results.

The (A) diplexer is by W7ZOI and is described on the Diplexer Web Page on this site.

The (B) and (D) diplexers are my designs and the (D) diplexer is the (B) diplexer with out the high pass component.

The (B) diplexer shown has a 3000 hertz 2 pole high pass/2 pole low pass design. This 2nd order filter provides reasonable overall matching Capacitors are standard-value, non-polar electrolytic types.

The (C) diplexer is a very basic, but very practical choice for this receiver.

The (E) diplexer is one that I used in one of my first DC receivers and the 47 millihenry inductor is a standard value unit sold by Mouser Electronics and others.

Another diplexer choice for this receiver might be the unit described by Rick Campbell, KK7B in his Binaural I-Q receiver project published in the March 1999 issue of QST.

Update May 15, 2009

There was confusion regarding the 2.7 to 47 mH inductors mentioned on this web page. I originally wound just the 2.7 mH inductor on a ferrite, but not the others. This is not a great idea as losses are high. For millihenries-value inductors, commercial parts should be purchased. A good brand to consider might be Epcos. Sorry for causing confusion.

10 milliHenry inductor
* Not wound at home

AF Preamps

The AF preamp section follows that of the Ugly Weekender Receiver designed by Wes Hayward, W7ZOI. I tried many other configurations and came to the conclusion that these two simple but elegant stages give a winning combination of low noise, good gain, low parts count, low hum and good AM broadcast band rejection. The Q1 transistor decouples the receiver preamp very well and no hum was detected in the headphones providing a well filtered DC power supply was used. The Q2 grounded base amp provides a low impedance termination of the product detector and diplexer stages. Q2 and Q3 are direct coupled and provide lots of gain to drive the succeeding low pass filter without it adding a huge abundance of noise to the signal. The bypass capacitor (0.022 uF) is essential to bypass any broadcast AM detected in the Q1 stage to ground. Other values of capacitors maybe tried, but do not omit this critical part.

Low Pass Filter

I cannot handle listening to a DC receiver on a crowded band without some low pass filtering. The high pitch heterodynes effect my concentration and give me a headache. Nevertheless, it is neat to temporarily listen to an unfiltered DC receiver; to hear the pure and wonderful signals possible by beating RF directly into audio. I prefer low pass to band pass filters at audio and have used many combinations of active filters using discrete components and op-amps, as well as passive designs using AF inductors to build wave filters. This receiver uses none of these devices, however they could be easily substituted for the filter shown. Connected to Q3 is a simple, cheap RC low pass filter based upon the design criteria given on the Discrete Component RC Audio Filters web page on this web site. The cutoff values you calculate will be ballpark and values of 0.047 uF for CW and 0.015 uF for SSB were chosen, but other values could just as easily been used and please do not hesitate to experiment with the caps and/or the resistors to suit the parts you have on hand. For the capacitors in the low pass filters, avoid using ceramic disk type caps if you want the best possible performance. Polyester, polypropylene, polystyrene or polyester film type are all suitable, however, ceramic caps will work if you are really going junk box/low cost.

I attempted to make a wave file to demonstrate the low pass filter. I came right off the headphone jack into the input of the of my 16-bit PC sound card via a step up audio transformer and the results were a little disappointing. Sixty-cycle hum and distortion of loud stations were added by the sound card. The sound file is big (636 KB) and is a digital recording of me tuning through a 30 meter pile-up using the lowest sample rate and frequency possible on my computer. The low sample rate/frequency also degraded the sound somewhat as well, but I decided to put it on the page, warts and all. The DX station was a VK2 and sure did cause a lot of excitement on 30 meters that night around sunset on the left coast. Actually the wave file demonstrates how good the receiver sensitivity and AM radio immunity is. In addition, the low receiver background noise is also very apparent underneath the constant 60 cycle hum. The 60 cycle hum and clipping of loud CW signals is not heard in the headphones and is a soundcard manifestation. Perhaps the best method would be to come of Q4 and go right into the sound card with a smaller line-in signal voltage. Download the popdc wave file

---

AF Driver and Final Amp

Connected to the input and output of the Q4 stage are small value capacitors to provide some high pass filtering for the receiver amplifier chain. Some emitter degeneration is used on Q4 to provide a better termination of the preceding RC low pass filter. The receiver amplifier chain has a lot of gain and when the 10K pot is turned to minimal resistance (cranked) , the LM386N can be driven into distortion. You may want to limit the maximum gain with a series resistor connected to the 10K pot after building and testing this receiver.

The final AF amp is the perennial LM386N, a low cost, easy to use AF amp. Turn it upside down and solder pins 2 and 4 right to your copper ground plane to anchor this part. It can easily be configured to drive a small speaker.

An optional mute circuit is shown in the "Adjuncts" schematic and is labeled (F). This circuit is a simple transistor switch which grounds the output from Q4 and mutes the receiver audio. This circuit switches rapidly and there are no annoying pops or clicks to be heard in the headphones when it is switched. Apply the VCC to the diode as shown to mute the receiver during transmit if the receiver is used in conjunction with a transmitter. Q5 in the mute circuit can be a 2N3904 or 2N2222a or substitute.

In addition, a suggested side tone input to the LM386N is shown. I have started to use simple one section RC filters on the output of my side tone oscillators to smooth the waveform into a more pleasing audio tone.

Conclusion:

This popcorn receiver can be made very inexpensively and has good sensitivity and a reasonable noise level and selectivity. I tested this main frame on 30 and 40 meters and really enjoyed it. This receiver main frame could be combined with an inexpensive VFO using tuning diodes to keep cost down and the popcorn factor up. Although it does not use tuning diodes, a 40 Meter band VFO schematic has been placed on the VFO page.

Here is a YouTube Link using the receiver with a different front end filter and VFO. This is not my radio or video.

A blog post from Peter AK6L --- it's good to see builders moving beyond kits.

RF — Test and Measurement

40 Meter Popcorn Superhet Receiver

Discussion:

Note: if you click on a schematic, a larger version will appear in a new web browser window.

To the right is the schematic for a no-frills, relatively low-cost CW superhet receiver with a 4.00 MHz Intermediate frequency. There is no AGC or RF gain control, however this receiver has good large signal handling capability. This receiver uses just 6 bipolar transistors and an op amp for reasonable volume into headphones. Much of the ideas/design of the various stages must be credited to Wes Hayward as I borrowed heavily from his previous work and through ideas obtained by discussion. If one were to homebrew the diode ring mixers, indeed this would be a very low cost receiver giving reasonable performance which outperforms any NE602 based superhet receivers that I have built or listened to. Below the main schematic is a diplexer diagram that allows the builder to choose from one of two RF and AF diplexers used to terminate the diode ring mixers.


40 METER POPCORN SUPERHET
ANT
L1
L2
10 pF
100pF
20pF
20pF
Bandpass Filter
.1
1K5
1K5
1K
150
.1
4.7
Q1
RF Amp
+ 13.8 VDC
100
T1
.1
.1
.1
36
150
150
-6dB Pad
(50 ohms)
VFO
?
Choose mixer with Diplexer
A or B
+ 13.8 VDC
100
2K7
.1
L3
.1
390
.1
Q2
Heat Sink
560
47
5.6
.1
IF Preamp
.1
150
680
-6dB Pad
(200 ohm)
1N4148
Diode Limiter
+13 dBm
300 pF
300 pF
300 pF
4.00 MHz IF Crystal Filter
T2
.1
2K7
.1
390
Q3
Heat Sink
560
75
5.6
.1
IF Amp
+ 13.8 VDC
100
T2
.1
.1
18
295
-3dB Pad
(50 ohm)

L1 , L2 32 turns of #26 AWG on a T50-6 toroid core. Tap 5 turns up from grounded end.
T1 , T2 10 bifilar turns #28 AWG on an FT37-43 toroid core.
L3 18 turns #26 AWG on an FT37-43 toroid core.
Q1 2N3904 , 2N2222a , 2N5179 etc .
Q2 2N3866 , 2N5109 etc.

Band pass Filter and RF Preamp

From the 50 ohm receiver antenna jack, first off is a double-tuned band pass filter which was designed by Rick Campbell, KK7B and works very well. The trimmer caps can be the 5 - 20 pF units sold by Digi-key and Mouser. The fixed-value caps in my prototype were inexpensive monolithic ceramic capacitors purchased from Digi-key. Rick used an NP0 ceramic for the 10 pF coupling cap plus silver-mica type for the 100 pF caps in his original design. For possible lower insertion loss, the probable best/cheapest way would be to use all NPO ceramics for the fixed value caps in this filter.


VCC 13.8 volts
22uF
1K
BFO
?
Choose mixer with
Diplexer C or D
10K
100K
22uF
10uF
Q4
2K2
22K
10uF
AF Preamp
1K
22uF
22uF
10K
470
Q5
100K
4K7
.1
.22
10K
100K
1K
390
10uF
100
Q6
2K2
10uF
AF Amps / Filters
10K
Pot
.01
10
LM386N
47uF
3
2
6
4
5
PA
100uF
10
.1
Phones
Q4 2N3904 , 2N2222a etc
Q5 , Q6 2N3906

The RF amp is my favorite popcorn RF amp ; a 50 ohm feedback amp. A grounded-gate JFET amp was tried in its place and was also found to be quite suitable and does not require the -6dB pi attenuator that follows the feedback amp as shown in the schematic. The feedback amp's 50 ohm input impedance properly terminates the band pass filter. The -6 dB attenuator pad following the amp to helps provide a 50 ohm input impedance for the mixer and to reduce stage gain which aids in preserving the signal to noise ratio of the receiver. If a builder wants a little more sensitivity, the pi attenuation pad could be reduced to -3 dB however this may effect the receiver dynamic range. The transformer T1 is one of 2 broadband transmission line transformers in this receiver. It transforms the 200 ohm collector impedance to 50 ohms for the succeeding stage.



Mixer and Diplexer

A 50 ohm diode ring mixer (7dBm) such as the Mini Circuits SBL-1 or TUF-1 or homebrew are all suitable. Following the mixer is an RF diplexer of your choice. The more complex Brifge-Tee (Q = 1)diplexer (A) is an excellent design, however maybe overkill in a popcorn superhet such as this. For the (A) diplexer, to get the necessary 800 pF for the capacitors, simply parallel a 470 with a 330 pF or a 120 pF with a 680 pf capacitor. The inductors at 2.0 uH are wound on powdered-iron torroids. You can use # 26 AWG wire and it requires 22 turns on a T37-2 core or 20 turns on a T50-2 core. In addition, you can use a #6 material torroid to wind the inductors. This diplexer is described elsewhere on this web site.

The simpler (B) diplexer uses a ~3 times the IF frequency that I have seen this basic design in many textbooks and articles and provides reasonable matching with a 50 ohm inductive and capacitive reactance. The cutoff frequency chosen was 11.78 MHz as this allows the use of a standard value capacitor (270pF). To wind the 0.68 uH inductor use 13 turns on a T37-2 torroid or 12 turns on a T50-2 powdered iron torroid core. You can easily use 24 - 26 AWG wire for the inductor.

IF Preamp , Crystal Filter and IF Amplifier

Except for the inductors, the IF preamp and IF amp are identical and both warrant a small clip-on heat sink as they draw reasonable current. The standing current maybe increased or reduced by changing the 47 and 75 ohm resistors connected to the Q2 and Q3 emitter respectively. Factors such as available power supply current versus dynamic range requirements may come into play. One may want to stand more current in the IF preamp and less current in the IF amp. For example, the 75 ohm resistor on the Q3 emitter could be increased considerably and/or the 5.6 ohm degeneration resistor could be increased as well if less stage current draw is wanted. The 2N3866 transistor is usually a cheaper way to go for these amps than the 2N5109, but the choice is up to you as you may have something available in your junk box. The 200 ohm -6dB pad following the IF preamp should not be omitted as it helps prevents the stage from seeing reactance's created ahead by the crystal filter. The four diodes form a 13dB limiter to protect the crystal filter should a catastrophically large signal be present in the receiver's front end. They maybe omitted. A -3dB 50 ohm resistive pad terminates the IF amp and helps establish a 50 ohm input impedance for the product detector ahead. **Click here** for more on the IF preamp.

This receiver has a narrow IF Cohn Crystal filter. Bandwidth is ~ 405 hertz, which unfortunately makes tuning quite sharp however this filter is very nice for crowded band conditions. The IF filter crystals should be closely matched in frequency to prevent unwanted ripple in the pass band. Generally, you have to buy 10 and then if you have a frequency counter, use the receiver BFO stage to test your crystals for matching. Pick the closest 4 crystals and use them in your filter. It does not matter if the crystals have series or 20 pF load capacitance, but it does matter that they are matched in frequency within 40 hertz of one another or better for this receiver. For my prototype receiver, I purchased ten 20 pF load capacitance 4 MHz crystals and luckily found 4 that matched each other within 9 hertz! For those builders who do not have a frequency counter, some QRP parts retailers sell matched sets of crystals. It is important to note that the BFO should be set on the high side of the IF frequency as simple crystal ladder filters have a steeper upper passband than lower pass band.

The crystal filter is terminated by the 4:1 transmission line transformer and then 50 ohm impedance of the IF amplifier. The -3dB pad following the IF feedback amplifier helps to terminate the crystal filter by helping ensure a 50 ohm IF amp input impedance and should not be omitted. Place a 75 and a 220 ohm resistor in series to get the required 295 ohm resistance on each leg of the pi attenuator.

Many may balk at just one stage of IF amplification, but since there is no AGC and this is a CW receiver, it works well. A feedback amp is once again used to provide correct input and output impedances for stages connected to the IF amp. Following the IF amp is another attenuator set for -3dB and then a 50 ohm diode ring mixer.

Product Detector, AF Diplexer and Audio Amplifiers

The mixer/detector can be SBL-1 or TUF-1 types or homebrew if you want to reduce costs further as the mixers are the single most expensive components in this receiver.

Again a choice of diplexers is required. The (C) AF diplexer is very simplistic but very practical if you are trying to keep costs low. The (D) diplexer is designed by W7ZOI and is from the Diplexer Web Page on this site.

Following the diplexer, a grounded base audio amp provides a 50 ohm termination to the product detector. AF gain and some AF filtering are provided by Q5 and Q6 which together attenuate frequencies less than 72 hertz and greater than 638 hertz. This amplifier pair are described on the discrete AF filters web page on this web site. Keep your leads short on all the AF transistors.

The final AF amp is the perennial LM386N, a low cost, easy to use AF amp. Turn it upside down and solder pins 2 and 4 right to your copper ground plane to anchor this part. There are a number of low-noise alternatives to the LM386 available which are generally more expensive but would be quite suitable. Discrete component AF amps can also be used, but a popcorn part such as the LM386N maybe cheaper and easier.

VFO and BFO

VFO schematic

BFO schematic

Alternate version of this receiver

Construction Ideas

When constructing any project, build in small modules and test each one separately. For instance, the AF amp should be built first and then tested by injecting a very low-level audio frequency tone into that stage and listening for output in your headphones. Every QRP workbench should have a simple AF tone oscillator from a schematic similar to the ones used for keying side tones in CW transmitters. The encased oscillator should have to a 100K or so potentiometer connected to the output to vary the output signal amplitude. Generally use maximum resistance on the 100K pot to start with and reduce this resistance slowly as the in-test amplified oscillator output could be very loud!. After testing the AF amp, build the 3rd AF preamp stage including the 10K panel mounted pot so you can vary the gain going into the AF amp. Now inject the AF oscillator output into the input on the pot and vary the 10K pot to ensure that the stage you built is working. It should be a lot louder now and should go up and down in volume with the 10K pot. Finally build the remaining preamp stage and once again test the circuit with your AF oscillator. The output into the phones should be painfully loud now when cranked up! The next stage to build would be the BFO. If you do not have a scope, peak the tuned circuit by watching the S meter on a radio receiver located nearby. Ensure that you put a load on the output winding of the BFO such as 47 ohm resistor to ground. A small piece of wire can be used as an antenna if the BFO signal is too weak to activate the S meter on your receiver. Once peaked, you can now use the BFO to match your IF crystals. To use the BFO to match your crystals, use a small wire to bypass or disconnect the 60 pF variable capacitor that is used to connect the crystal to ground. In other words, the bottom lead of the crystal is connected to ground with a short piece of wire. This makes testing your crystals a little more scientific as the variable capacitor cannot influence the crystal frequency during testing. You can also use the BFO in conjunction with a scope or voltage probe to test the various RF amps in the receiver. I do this all the time with my scope. Proceed with this build a stage, test a stage method and you should be rewarded with a functional end product.

KK4RF's version of the 40 Meter Band Popcorn Superhet

Marty, KK4RF emailed me and described his version of the popcorn superhet from this web page and contributed some great info and photos of his receiver. Of note is Marty's use of Radio Shack IC boards for mounting the components for each stage other than the VFO circuit. This is yet another variation from ugly construction that I have also used which works extremely well. Marty built the VFO using pure ugly construction and I was glad to hear that he is enjoying good frequency stability even with the lid off the VFO enclosure.

He built the receiver into an old Heathkit HW-12 single-bander case from the 1960's and it is a very attractive receiver to say the least. He found an old National Velvet Vernier Drive at the Virginia Beach Hamfest this year and used it to tune the VFO. Don't you love Hamfests! For the BFO he used an BFO circuit with a 4 mHz crystal from a different receiver project (a project that never quite worked.) He built a small power supply and located it along with the BFO under the chassis.

I like Marty's generous use of ground plane and neat stage layout. He reports good selectivity with his IF filter and apparently built four superhets that did not work before building this popcorn version. This is more a testimony to Marty's perservance to home building than to this receiver design in my opinion. I won't tell you how many rig failures I have personally incurred, as it would take a long time! Many thanks to Marty, KK4RF for the feedback and great pictures.



Amateur and Short Wave Radio Electronics Experimenter's Web Site

Broadband Transformers plus Diode Ring Mixers

Discussion



There are 2 basic types of broadband transformers used in most QRP work — conventional and transmission line style. Both types may be wound on ferrite toroids, pot cores or rods, however, I only discuss the toroidal transformers we employ to give a 4:1 impedance transformation.

I use these transmission line transformers on many projects on the QRP / SWL HomeBuilder web site. For MF and HF uses, a ferrite core permeability of 850-900 is generally required and the FT37-43 ferrite core proves suitable. Shown above are 3 equivalent schematics of the 4:1 transmission line transformer. You'll probably find that the center drawing easiest to conceptualize, however, with closer examination, all 3 schematics are the same and transform signals from unbalanced 50 Ω impedance up to 200 Ω unbalanced impedance or visa-versa.

The high impedance is 200 Ω and the low impedance is 50 Ω in all cases. It is important to know that these transformers are symmetrical and the points labeled Ground or VCC can be switched with the point labeled High Impedance. *Click on the schematic to enlarge it.*

Winding the 4:1 Transformers

Wire Twisting

Transmission line transformers are wound with bifilar (2 wires — generally twisted together). Winding these transformers is very easy. All you need are two ~18 cm (7 inch) pieces of #28 AWG enamel coated wire and an FT37-43 ferrite toroidal core.

A shop vise, a ruler, plus a brace and bit hand drill may aid your construction — I bought my brace and bit drill at a garage sale for 2 dollars. You need to twist the 2 pieces of wire together to get ~3-4 twists per cm (8-10 twists per inch) in the wire. To do this, loosely twist the wires at one end and place these twisted ends in a bench vise. Next, place the free wire ends together in your brace and bit drill chuck (no drill bit) and tighten up the chuck so that the wires are held securely.

Try to keep wire length and tension equal. Start turning your drill to twist the wires together and every once and a while measure how many twists per cm with a ruler. When you get to 3-4 twists per cm (8-10 twists per inch) you're done and then may trim the excess leads with a wire cutter in preparation for final winding and soldering.

At VHF, I often use just 3 or 4 total turns on an FT23-43 toroid with a piece of wire just a few cm long. I place the 2 wires in the vise and twist them using a pair of pliers held parallel to the wire.

Transmission line transformers will also work if the wires are untwisted. 3-4 twists per cm only serves as a non-criticial guide. Never wind your simple 4:1 transformers with bare wire.

A brace and bit hand drill plus a vise provides a good way to twist your wires.

Final Wiring and Soldering

Leaving a 2.5 cm (1 inch) lead, wind ten complete loops through the toroidal core leaving a small gap between the start and finish leads.

Untwist the leads a little so that you have 4 separate wires. One set of these wires wires will be called winding #1 and the other winding #2. You need to identify them and further break them into 1a, 1b and 2a and 2b. Generally I regard the the top two windings as (A) and the the bottom two wires (B), however, use whatever system works best for you. Strip off the enamel at the tips of all four leads and then get your ohmmeter or better yet, a beeping continuity tester.

Start on one of the top (A) wires by connecting the ohmmeter or continuity beeper to it and then touch one of the bottom wires and then the other bottom wire. Whatever bottom wire (B) shows continuity with your top wire should be marked along with the source top (A) wire with paint, liquid paper, tape, or whatever you like.

I prefer to wind 2 different colored wires if possible.

Designate the marked wire pair winding number 1. You may also want to test for a short circuit — there should be no connection between wire set 1 and wire set 2 at all. So now you have 2 wires sets, winding set 1 is marked and winding set 2 is unmarked. The top two wires are arbitrarily labeled A and the bottom two wires are labeled B . Refer to the schematic above for clarification. Connect 1b to 2a and twist them together and then solder. Your done!

It's really easy to make these things don't you think?.



A trio of bifilar transformers wound on FT37-43 ferrite toroids. 2 colors of wire reduces errors and speeds up construction. Consider making up 5 at a time, so you have them on hand and do not have to interrupt your experiments.

Homebuilding Diode Ring Mixers



Discussion:

Easy to make, homebuilt diode ring mixers give a low-cost alternative to commercial diode ring mixers. A double-balanced diode ring mixer has 2 unbalanced to balanced transformers and a diode ring. The impedances at the three ports is 50 Ω. The transformers are wound with #28 AWG enamel coated wire on a FT37-43 ferrite toroidal core using a trifilar (3 wire) technique.

The wire twisting and winding technique is done as described above for the bifilar transformers. The connections 2b and 3a are twisted together and soldered. Again you will have to develop a technique to help you distinguish the wires from 1 another. *Click on the schematic to enlarge*



A trifilar transformer wound using 3 colors of wire on an FT37-43 toroid

#32 BELD. 1/4 LB.
20
30
28

A sample of the enamel coated copper wire collection I wind inductors and transformers with. In stock are wire gauges from 18 to 34. Like everything else, this collection started small and grew over time. Be vigilant for bargains and when you find a good price, purchase a whole bunch as it does not go bad. The Belden wire (orange spool ends) is over 40 years old and the enamel insulation remains perfect.

Diode Matching for Mixers



Discussion

For optimal results Schottky or Hot-Carrier diodes should be used. However, common diodes such as the 1N914, 1N4148 or 1N4454 are all quite suitable and are much cheaper. The four ring diodes should be matched to help mixer balance and thus carrier suppression. At MF and HF the most critical matching required is the forward voltage drop across the diode and this is easily performed with a sensitive voltmeter.

Set your voltmeter on the 2 volt scale to give you 3 decimal places for matching the voltage drops. Try and find 4 diodes close to one another. In addition, best results maybe obtained if all the diodes are the same type (i.e. all 1N4148) and if they are all from the same manufacturer. Look above for easy schematic to match your diodes with a voltmeter. Give the diode under test at least 20 seconds to warm up and stabilize before taking your voltage measurement.

RF — Test and Measurement

Diplexers Topics

Introduction

My original web page on diplexers was rather incomplete and received some criticism from electronic engineers albeit the focus of this web site is "popcorn" designs. Wes Hayward, W7ZOI provided me some excellent schematics, analysis and simulations for diplexers which terminate doubly balanced mixers and these are presented below. After this section, the W1JR Bridge-Tee RF Diplexer from the original QRP HomeBuilder diplexer web page is presented along with new commentary and simulations by W7ZOI.

The final section presents a practical diplexer for terminating a product detector. All graphical images labeled as Figures 1-24 are copyright and property of W7ZOI and may not be presented elsewhere. Updated September 23, 2000.

W7ZOI Diplexer Notes

The usual amplifier is a two-port circuit. That is, it has an input port consisting of two terminals and an output consisting of two more. One terminal (ground) can be shared between the ports. Many filters are also two-port networks, including most of the ladders networks we use so often. Many other networks have three or even more ports. A common example is a mixer, which has three ports. Another example of a three port network is a diplexer. This linear network is usually designed around two port filters where one end of two different filters are paralleled to form an input port. This is illustrated as Figure 1. The purpose of a diplexer is usually to force a frequency constant impedance to occur at the input port, even though we usually only use one of the two output ports for signals. The simplest form of diplexer uses a pair of 1 element filters, a low pass and a high pass. This is shown in Figure 2.



Figure 1



Figure 2

Where the equations give the L and C that provide a perfect match. The angular frequency is called the cross-over. A familiar example is the cross over used in audio systems. The network that splits signals is a diplexer. Here is an example where both outputs are used. Another form of diplexer is the band pass/band-stop combination. This is shown in Figure 3:

Let's now consider further some examples, some that work and some that don't work as well. First, let's look at an audio diplexer that follows a product detector in a DC receiver. The load of interest is the first audio stage, which has a 50 Ohm input resistance. The diplexer offered is Figure 4. Note that this is not the combination of filters. It just looks like a low pass with an extra resistor. The response of this circuit is shown in Figure 5. The transmitted signal never gets up to the desired 1 volt in the low pass passband while the impedance match, represented by reflection coefficient, never gets down to the desired zero. The response is just that of a lossy low pass filter.



Figure 3

In 2012; Click on many of the diplexer images to see the original sized version


R1
50
R2
50
L1
1.4m
out1
0.56u
C2
R4
50
V1
2v
V2
1v
gam1
R3
1g
0
This isn't even a diplexer. It's just
a low pass with an extra resistor.

Figure 4



Figure 5

The normal filter circuit without the extra resistor is Figure 6. The corresponding output response is shown in Figure 7. Note that the transmitted signal is now up at 1 while the reflection is down to zero, both within the passband. Transmission goes to zero while reflection is 1 in the stopband.


R5
50
L2
1.4m
out2
0.56u
C3
R7
50
V3
2v
V4
1v
gam2
R8
1g
0
Here's a normal 2nd order LPF

Figure 6



Figure 7

Now let's use the low pass and put a high pass with it to try to form a diplexer. This is shown in Figure 8 where we now have just guessed at component values. The response, shown in Figure 9, has high pass and low pass outputs that we might expect. The match is good at the frequency extremes, but is only so-so in the transition band.


R1
50
V1
2v
0
V2
1v
gam
R3
1g
L1
1.4m
outLow
0.56u
C2
R4
50
C4
1u
outHi
L3
1m
R9
50
Now we convert it to a diplexer.
We will just guess at the High Pass values.

Figure 8



Figure 9

Let's now look at a carefully designed pair of two element filters. The circuit is Figure 10 an is a final example. The corresponding response is Figure 11. It is hard to see, for the response merges in with the baseline. However, the reflection is zero and it is zero everywhere. This filter was designed for a 1 kHz crossover, so it can be scaled to other frequencies with ease.


R1
50
V1
2v
0
V2
1v
gam
R3
1g
L1
11.25m
outLow
2.25u
C2
R4
50
C4
2.25u
outHi
L3
11.25m
R9
50
Let's fix it:
Here's an exact solution at 1 kHz crossover.

Figure 10



Figure 11

Figure 12 is another final audio example. This circuit is very similar to the one used in the past by Roy Lewallen, W7EL, although the inductor was smaller at 100 uH in his Optimized rig. The response of this diplexer is shown in Figure 13. This is not perfect, but it is probably quite a good performer in typical receiver situations.


R1
50
V1
2v
0
V2
1v
gam
R3
1g
L1
1.4m
outLow
0.56u
C2
R4
50
C4
100n
outHi
R9
50
This is an approximate diplexer format. This is like what Roy did.

Figure 12



Figure 13

Finally, here's a higher frequency example. 5th order low pass and high pass filters are combined. The filters have a cross over at about 150 MHz. Note that there is a slight reflection in the transition band. This is probably just the result of our having rounded some values in the design process. Figures 14 and 15. An outstanding reference on this is Nic Hamilton, G4TXG, "Improving Direct Conversion Receiver Design," Radio

Communications, April 1991.



Figure 14



Figure 15



Bridge-Tee RF Diplexer

This is an excellent bandstop/bandpass diplexer popularized by Joe Reisert W1JR. This easy to build diplexer has a low parts count and is easily built using Ugly Construction. Resistors R1 and R2 present a 50 ohm impedance to the mixer output and a 50 ohm impedance to the input of the post mixer amplifier. The IF frequency is passed through the diplexer while out of passband RF is given a low impedance path to ground. The capacitance for C1 is generally built up by substituting the nearest standard value capacitor or by placing 2 or more capacitors in parallel with each other to achieve the desired value. The same procedure is then repeated for the C2 capacitance. For more strenuous purposes, a portion of C1 and C2 or the inductors L1 and L2 can be variable and adjusted on the bench. The inductors can easily wound on powdered-iron toroid cores. I have used T50-2 or T50-6 type toroids with good results. The Q of the inductors is 1.

It is possible to design a more generalized form of this diplexer with a higher loaded Q in the resonators. The diplexer shown and used in the program has a Q of 1. This was used by W1JR in his VHF/UHF World Column in the now defunct HAM Radio Magazine for March and November 1984. It was also more recently used by Jacob Makhinson, N6NWP in his A High-Dynamic Range MF/HF Receiver Front End in QST for February 1993. The actual formulae for this diplexer is far more complex than the simplified formula shown below or used in the program, but both provide a very good approximation for the Q = 1 version as used by W1JR and N6NWP. If you wanted Q=10, the series tuned circuit would use L that is 10 times as high with C to resonate. The parallel tuned circuit would then use C that was 10 times higher with L to resonate.

A supplemental web page with some hard-core mathematics for this diplexer can be found on the Diplexer Supplemental Page.

Simplified Formulae (Q = 1):
R1 and R2 are always 51 ohm resistors.
Inductors L1 and L2 -> 50 / (6.283 * frequency in Megahertz)
Capacitors C1 and C2 -> 1 / (6.283 * 50 * frequency in Hertz)

Example 1: For a 9 Mhz IF , L1 and L2 = 0.88 microhenrys and C1 and C2 = 350 picofarads
Example 2: For a 4.92 MHz IF , L1 and L2 = 1.62 microhenries and C1 and C2 = 647 picofarads

I wrote a simple program to do the math for the Q = 1 version. Download the Bridge-Tee RF Diplexer Diplexer Program

---

Comments and analysis by W7ZOI

This is a double ended version of the first order bandpass/bandstop design presented earlier. But it's a good one, within the constraints of what it can do. The first is the simulation schematic for the diplexer, which is better termed a Bridge-Tee Diplexer. (There are bridge Tee filters and attenuators too.) That figure is entitled Figure 16.


Bridge-Tee Diplexer
R1
50
L1
880n
C1
354p
V1
2v
V2
1v
R3
50
R4
50
out
gamma
880n
L2
C2
354p
R5
50
R2
1g
0

Figure 16



Figure 17

The response for this circuit is shown in Figure 17. This is extremely good. The through response is very flat owing to the low Q of the series tuned circuit. But even better is the match. It is very good. Indeed, it would have been perfect except for slight roundoff errors that occurred as we designed the networks.



```
8.9          8.96         9.04         9.1
-24.4397     -9.73945     -7.74807     -23.7041
-.015936     -0.489551    -0.801446    -.018872
```

Figure 18


Bridge-Tee Diplexer
R1
50
L1
880n
C1
354p
L3
100u
3.15151p
C6
L4
100u
3.15151p
C7
396p
C3
796p
C4
396p
C5
2v
V1
1v
V2
R3
50
R4
50
R6
1g
out
gamma
C2
354p
L2
880n
R5
50
R2
1g
0
Ideal "Crystal-like"
50 kHz
R6 just there to keep SPICE happy.

Figure 19

This kind of thing works fine if you really have a perfect match following the diplexer. But what if you don't. There are some places where they do not do the job that some folks think they will do. For example, a diplexer WILL NOT cause the impedance to be flat if it is followed by a filter. The diplexer must still be properly terminated at both output ports. In Todd's usual applications, he is worried about providing a good mixer termination for a product detector. The audio amp that he uses will usually have a common base first stage and that will present a good wideband load to the diplexer, so he is okay. But other folks have placed a diplexer after a switching mode mixer that then drives a narrow filter. The diplexer then does little good. To illustrate this situation, I designed a "crystal like" two pole LC bandpass filter with a 50 kHz bandwidth. This represents the general case where we try to put a diplexer between a mixer and a filter. The filter response by itself is shown in Figure 18. The schematic for the diplexer and following filter is in Figure 19.

The response for the combination is in Figure 20. Here we see a passband response that is fine; it's just the repeat of the filter response we already saw. However, the input impedance looking into the diplexer, the impedance that would be seen by a mixer, is terrible. The return loss is 0 dB at all frequencies except where we get within the passband of the filter.


MicroSim Probe - [Bridge-Tee Diplexer 1.dat]
File Edit Trace Plot View Tools Window Help
0
-20
-40
-60
Terrible Impedance match
except within BPF passband
Bandpass output response
Figure 20
8.4MHz
8.6MHz
8.8MHz
9.0MHz
9.2MHz
9.4MHz
9.6MHz
DB(V(out)) DB(V(gamma))
Frequency
Start
Mouse
Explor...
Micro...
Micro...
PSpic...
Micro...
2:35 PM

Practical Diplexer for Popcorn Receivers


Practical Diplexer
10 mH
2.2uF
2.2 uF
51
10 mH

Building a diplexer to follow a product detector is not a cheap endeavor. Audio inductors and capacitors such as metalized polyester film types are not common in many builder's junk boxes. I really like the design shown in Figure 10 and wished to use it because it uses just 2 inductors and capacitors which is in keeping with the popcorn nature of this website. The main difficulty is that the inductors and capacitors are not standard value types and series connecting components to achieve the desired values would add to both the cost and size of the finished product.

Obviously, it will not likely match from DC to daylight. That is not the intention of this simple design or this web site in general. I asked Wes to place just 2 standard value capacitors and inductors in the Figure 10 diplexer design and see what happens.

Here was his response to my request:
OK, here are some "practical values." Note that things don't really change that much. We start with 11.x mH and 2.25 uF. Change the inductor to 10 mH and get Figure 21. Then change the cap to 2.2 uF and see almost no change in Figure 22.





But now move into the world of even greater reality and acknowledge that many of the inductors we use at audio are very low Q. Change Qu of L to 10 at 1 kHz, so I put 6.3 Ohms in series with each L to get Figure 23. And do the same thing, but with a dB scale, for Figure 24. Note that we can see the difficulties, but things are still pretty good. We see some loss (about 1 dB) in the low pass path and less than perfect match. But the match is still very good. 20 dB is about 1.1:1 vswr, much better than 99.9% of the hams can really measure. (A 10 dB match is about 2:1.) Hope this is what you were after....Wes

It was and I will use this "practical" diplexer in my next popcorn DC receiver project. Note that the practical diplexer input and output impedance is 50 ohms and the 2.2 uF caps should not be polarized capacitors such as regular electrolytic types which have a positive and negative polarity.





Many thanks to Wes Hayward, W7ZOI for his work on this page.
A version of this web page in Russian Cyrillic

RF — Test and Measurement

Ugly Construction

Discussion


MG Chemicals
COPPER CLAD BOARD
Complies with Mil-S-13949H-GFK. Stress Relieved UV Blocked
Flame Retardant - UL Rated 94-VO. UL-FR-4, 1 oz Copper

We enjoy many ways to build electronic circuits. For example, you might breadboard on a perforated circuit board, an etched PC board, a sheet of copper clad board, or even a piece of copper wire. In the hay day of tube electronics, builders used terminal strips and point-to-point wiring within the project chassis. I mostly breadboard using Ugly Construction.

Ugly Construction, "dead bug", or "ground-plane construction" involves building circuits on top of a double or single-sided copper clad board (copper side up for single-sided board). The copper ground-plane provides a low impedance ground and mechanically supports the parts soldered to it. Component leads requiring grounding are soldered *directly* to the copper surface, while the ungrounded leads of these parts anchor any ungrounded parts connected to them. Isolated sections called stand-offs hold other ungrounded or remotely located parts.

Example stand-offs include high value resistors (10 Megohm or greater), terminal strips, or small copper islands glued onto or cut into the copper ground-plane. Parts such as transistors, IC's or commercial diode ring mixers are generally flipped upside down and anchored by their grounded lead(s). Metal encased parts such as crystals can be grounded by a short wire or directly soldered upside down to the copper board.

DC voltage wires, or decoupling resistors may be supported by soldering 1 lead of a bypass capacitor to the ground plane while the other lead holds the DC voltage carrying part up off the copper board a short distance. I mostly use grounded caps for stand-offs and not 10M resistors.



Shown above — a 10 Megohm, half-watt, stand-off resistor anchors the "hot" inductor terminal plus supports the ungrounded trimmer capacitor terminal. The coil's 24 gauge wire provides additional mechanical stability. The signal loss from adding the 10M resistor was about 0.1 volts peak to peak in 1 experiment.

Ugly Construction allows the experimenter total control over the design of a project and in my opinion, its greatest strength is *speed*. Ugly Construction yields rapid and flexible bread boarding — very appealing for prodigious home builders.

The Origin of the Term "Ugly Construction"

Roger Hayward, KA7EXM and Wes Hayward, W7ZOI coined the term "Ugly Construction" while writing the "Ugly Weekender" published in the August 1981 issue of QST. I asked Wes about this in 2009. The term was a takeoff from the 1958 book entitled The Ugly American by William Lederer and Eugene Burdick.

A big part of the learning of the QST article was Ugly Construction! The term and the bread boarding technique emphasized the fact that there is no correlation between the "prettiness" of a construction project and the way it works. According to Wes, the goal had a couple of corollaries. "First, people like myself who do NOT have the knack for doing pretty projects can still build successful radios. Second, is that we all need to look at our projects after the fact to discover what it is that really makes them work well. In the case of the Ugly Weekender, the thing that makes it fly is that there is a wonderful ground plane with that PC board material".

Indeed, this transceiver functions very well; especially after you temperature compensate the VFO. Wes also built versions for the 30 and 80 meter bands. I have versions on 15, 40 and 80 meters. The transmitter portion is a true QRP classic; both as a Ham radio transmitter and because it promoted "ugly" ground-plane or dead bug bread boarding techniques to the scratch homebrew community.

Classic Ugly Construction

This term emerged in Spring 2010 and describes the archetype popularized by Roger and Wes Hayward. All ungrounded leads not anchored to other parts are attached to the copper ground-plane via high ohm resistors — *no* glued pads or islands cut in the copper board.

In-situ comparisons of a 10 megohm resistor versus islands cut into the ground plane and glued-on Manhattan-style pads demonstrated that the resistor had the lowest capacitance; around 1 pF versus 4 pF or greater for the pads or islands. Click for a high resolution transmitter chain built with 100% Classic Ugly Construction. Click for a crystal oscillator.



Above — *Classic* Ugly Construction using a high ohm stand-off resistor. The top of the 10 megohm resistor is the VCC connection point. It feeds a 150 ohm / 47 uF decoupling network connected to a transistor collector resistor. Bypass capacitors also serve as stand-offs and I prefer thick lead (100 volt or greater) caps for stand-off duty.


VOL
EAR
JUNKBOX RECEIVER
UGLY QRP TRANSMITTER
KA7EXM
VFO
TUNE
KEY
SPOT

Above — The original Ugly Weekender. Photograph used by permission of Roger, KA7EXM.



Above — The original Ugly Weekender. Now this is *Classic* Ugly Construction. Please refrain from building this transceiver and adding modern notions such as a PIC microcontroller keyer — that's just wrong!

Photograph used by permission of Roger, KA7EXM.

Ugly Construction Variants

The most popular Ugly Construction variant is called Manhattan style. Manhattan or "paddy board" construction uses small square or round pads cut or stamped from PC board that are glued copper side up onto a large copper clad board also placed copper side up. The small pads or "islands" serve to anchor ungrounded components. Components soldered to the pads such as transistors or ICs are generally not positioned upside down like in Classic Ugly Construction. Many Manhattan style builders use IC sockets as well. These hobbyists sometimes build beautiful looking layouts — Manhattan is a wonderful bread boarding technique. Google for more information. The best Manhattan construction and copper board chassis bashing I've seen comes from Dave, AA7EE. Click for a blog describing his version of the WBR regenerative receiver. *Linked with the permission of Dave, AA7EE.*

Another interesting variant is used by Dick Pattinson, VE7GC. The circuit board is placed copper side up and holes are drilled and countersunk so that the holes are isolated from the ground plane. Ungrounded components are connected underneath the main board through the countersunk holes. There are many such variations. Each Ugly Construction variant has advantages and disadvantages.

On this website, stand-offs are created by cutting a few lines into the copper board with a small, motorized hobbyist cutting tool; with high megohm value resistors, and occasionally by a small Manhattan style pad or 2. Manhattan pads are great for supporting components needing solid anchoring such as a trimmer capacitor or potentiometer.

Classic Ugly Construction dominates circuits breadboarded after May 2010.

The motor tool may also be used to grind off the copper underneath where VFO toroidal inductors will lie, so that the inductor Q is not effected by the being glued onto a copper surface. In audio projects, I may also grind off the copper around the copper board mounting bolts so that they are isolated from the chassis and do not provide multiple grounds and create the potential for ground loops.

Is Ugly Construction Less Reproducible than Manhattan?

I've received well over 1000 emails about Ugly Construction since launching the site in 1998. Some feel that circuits made with Manhattan pads are more reproducible than Classic Ugly Construction builds. This might be true, but to my knowledge nobody has performed a comparison trial.

The important question is why would this happen? I've read/heard opinions that the stray L and C from the long component leads associated with Ugly Construction might wreck circuit reproducibility, but respectfully disagree from DC to HF. In microwave breadboards, we fabricate lumped element inductors and capacitors (*i.e. precisely dimensioned Manhattan pads*) right into the PC board — Manhattan pads glued all around a breadboard may potentially exhibit much more stray L and C than a few component leads in an Ugly build. Also, wise Ugly builders keep their lead lengths short where it counts: for example, RF bypass + ground and at the input/output of a BJT or FET that offers gain into UHF.

I conjecture human error probably inflicts more problems for Ugly Construction builders — Manhattan building, with its slower pace might trigger less mistakes by newbies. Still, too, Manhattan builders tend to make prettier, squared and aligned circuits and it's easier to spot trouble — plus they look nicer in photographs and some builders carefully document and photograph their builds for others to admire and strictly copy. I've see Manhattan build photos where every resistor tolerance band pointed in the same direction — wow! I think it might be difficult to put such a 'work of art' into an RF-tight metal box for much-sought isolation.

Further, in Ugly Construction — upside down parts might wreak havoc on the "spatially challenged" builder. Who knows? I'm comforted knowing that kit sellers who provide a screened printed circuit board with explicit instructions, still must provide major email support to mitigate build errors. To err in an ugly fashion is human?

Whatever variant of construction you choose, it's sure to be a winner!

Further Discussion

Wire

Non-stranded (solid core) copper wire such as the 22 AWG 3-color package sold by Radio Shack seems a good choice for hook up wire. With non-stranded wire, you do not have to worry about little stay wire hairs causing shorts and it's easier to wrap around components leads. I use red for wires that carry positive voltage, green for grounding and black for wires that carry AC signals short distances. In addition, RG-174 or shielded wire is used to carry AC signals for distances greater than 10 cm, and for connecting stages requiring 50 ohm input or output impedances such as diode ring mixers or low-pass filters.

2781306
NEXXTECH
Hook Up Wire
22 Gauge Solid

Your Health

Please consider the following safety comments:

For regular soldering, ensure ventilation of your room — flux fumes can be harmful. Open your shop window and/or use a small fan to improve fresh air intake;

Whenever possible, perform high wattage soldering outdoors;

When grinding paths on copper clad boards, wear a small particulate respirator, gloves, plus ear and eye protection and most importantly; **do it outside** for yours and your family's health;

Wash your hands after soldering and handling freshly cut, fiberglass dust laden copper clad boards.

Soldering Irons

For soldering copper clad boards together, AC grounds on tube guitar amp chassis and performing antenna work, I currently use a Weller SP 80L (80 watt) soldering iron. It is heavy and unwieldy, so you have to be very careful when its plugged in. These high wattage soldering irons produce lots of smoke.

Weller
SP 80L

Shown above is an 80 watt "heat torch". My main soldering irons are typically in the 30-35 watt range. Consider keeping at least 1 back up soldering iron, as you never know when a soldering iron is going to burn up. My current 35 watt iron is shown below. These Weller irons have a built in lamp which lights when they are plugged in; a very nice feature. I also keep a small stock of new soldering iron tips.

Weller
SP23L

Copper Clad Board

Some builders ask about sources for copper clad board. I personally use boards made by MG Chemicals as they have dealers in my city and are reasonably priced and good quality. Try the search words **copper clad board** plus **your country name** in your favorite web search engine. A few links follow, but as I have only used boards sold locally, I can't comment about the online companies.

MG Chemicals Worldwide distributer index

Electronic Goldmine Online store

Circuit Specialists Online store

Miscellaneous

Shown below is a schematic and the Ugly Constructed version of it.


12 VDC
10K
100
22 uF
22 uF
1K
10K
,027
22 uF
22K
,027
22K
3
1458a
1
2
22K
4
56K
5
1458b
7
6
1 uF
10K
10K
1N4148
100K
1N4148

The second half of 1458 is set up as a voltage follower
Fabulous tone and sine wave

270 Hertz

Above. The schematic of an adapted sine wave audio frequency oscillator taken with permission from EMRFD , Figure 12.4. EMRFD is the main reference for this web site. The original schematic author was Wes, W7ZOI



Above. I built this circuit from start to scope in about 25 minutes. This was a scrap, pre-used board with a positive voltage path and a potentiometer holder already on it When miniaturization is not your goal, construction is much easier and faster. I re-use parts and boards to save money. You may remove entire stages from 1 board and solder them onto another.



Above. Note how the 10K output potentiometer holder is soldered to the main copper clad board. The grounded 10K resistor is used to anchor the 22K resistors connected to IC pins 2 and 3 and can be seen in the foreground.



Shown above is another project. Entire control panels can be built from copper clad board for prototype circuits. In this board are numerous cut paths, 7 potentiometers, 3 jacks and a switch. Do not build an LC VFO over double sided copper clad board; lest it become "a capacitor" and affect your frequency stability.



Shown above is a CD4013B D Flip-Flop soldered "dead bug" style. Pins 4, 6,7, 8 and 10 are grounded to the copper surface; well anchoring this part. Using proper static precautions, I have never had a CMOS device failure using Ugly Construction and also save the price of an IC socket.



Above — a method to anchor op-amps using a split (negative and positive) power supply. Pins 4 and 8 are soldered to the copper board via a 10 megohm resistor. A 0.1 uF ceramic bypass capacitor is also connected to these pins. The resistor leads were left a little long to allow easy connection of the power supply wires. I write each pin's polarity on the board to avoid wiring mistakes.



Shown above is another use for copper clad board; heat sinks. In this case, 2 scraps are epoxy glued to 2N3904 and 2N3906 transistors.

MG Chemicals
ROSIN FLUX PEN
Cat. No. 835-P Net. Fill 10 ml
Non-Corrosive RA Type Flux. FLAMMABLE / INFLAMMABLE

A flux pen like this one from MG chemicals is a handy item for the QRP workshop. They are great for applying liquid flux to allow easy and precise soldering of SMT components. Also sometimes when adding components to ground in already built up circuit boards, it can be difficult to get your soldering iron down at a low angle for proper heat transfer. Some flux can help solder a part to the copper ground plane in these situations.

Shown above are the basic tools used to cut copper clad board. A felt pen marker, small square and a set of straight aviation shears. If you press one end of the copper board into the side of your bench and keep pressure on the handle of the aviation shears with your thigh, it is possible to make long, straight cuts. The board will flex and move out of the way as you cut. Your leg provides the force to advance the aviation shears.

The motorized grinding/cutting tool used to carve out small pathways in copper clad board.

NET CONTENTS
6 ROLLS
BULL DOG
CAUTION:
GLOVES RECOMMENDED
WHEN USING THIS PRODUCT
SUPERFINE
STEEL WOOL
MANUFACTURED BY
THAMESVILLE METAL PRODUCTS LIMITED
THAMESVILLE - ONTARIO

Steel wool used to clean up copper clad board before construction. A box like this will last for years.

OLFA SILVER

For 15 years, I've used this 9 mm cutter to scrape the enamel insulation off the magnet wire wound on toroidal inductors.

QRP SWL HOMEBUILDER

Amateur and Short Wave Radio Electronics Experimenter's Web Site

VE7GC Wee Willy 75 Meter DSB Transceiver Project

Introduction

I meet a lot of interesting amateur radio enthusiasts online and on the air. Among them is Dick Pattinson, VE7GC who was first licensed in 1934. When Dick isn't sailing he builds and operates his homebrew QRP gear to hams around the west coast of Canada and the U.S.

Presented is a double sideband transceiver that Dick calls "Wee Willy". This rig has a low parts count and is easily built using non-etched PC board techniques. Dick even makes his own radio case using copper clad PC board for the front and back panels and cardboard for the rest of the case. The set itself is in a case 1 1/4 by 2 1/4 by 5 1/2 inches. There is a separate container which holds a 6 volt rechargeable battery and speaker. The speaker/battery case is about 2 1/2 inches cubed and is not shown.

The circuits are built in three sections on the circuit board, namely TX, RX, and VFO. An electret condenser microphone is on front panel along with T/R switch, volume and frequency adjust. The back panel has the antenna jack, power input cord and the speaker jack. The battery pack has a 100 uF capacitor to across the power leads for additional filtering and is shown in the VFO schematic.

The text that follows is clipboard pastings from email that Dick sent me with some additional comments and expansions by me. Dick's project exemplifies practicality and innovation and with that is a major contribution for the QRPHB site.

Construction Methods

Dick's electronic construction method is quite fascinating and represents yet another derivation of ugly construction. The electronic wiring is done on single sided PC board, copper side up. Small holes are drilled through the PC board material to allow component leads to pass through them. Then the holes carrying active leads are chamfered (countersunk) with a larger drill bit which is not run all the way through the PC board. This leaves an ground-insulated side to the hole and prevents a component lead short circuit. The copper being topside allows both convenient and short component grounding. The Wee Willy parts layout is extremely neat and compact. Dick, presumably through practice has great skill with this technique and I plan to try it in the future.

The project case is constructed from 1/16th inch cardboard which is cut and bent to fit the electronic PC board. Once cut, the outer surface and edges at the front are covered with tissue paper or Kleenex (tm) type tissues soaked in white glue. The applied tissue paper and glue is allowed to dry and then additional coats are added to build up a body. Alternately, the cardboard case can be coated with lots of glue and the covering material imbedded in the glue. The air bubbles are pressed out and extra glue is added where necessary. When enough material has been added to cover up and strengthen the case joints and the glue is perfectly dry, the case is painted with Rust Coat Enamel available at hardware stores. The end result is a glossy, durable finish which looks very sharp.

Transmitter

This transmitter uses an electret condenser microphone (Dick used an Archer 270-90). The mic is built right into the front panel of the chassis and this of course guarantees short mic leads. A 741 op amp is used as a speech amplifier which in turn drives the balanced modulator a Signetics NE602 doubly balanced mixer. The input and output impedance of the NE602 mixer is around 1500 ohms.

To adjust the transmitter, set the bias control on the VN10 stage to ground and tweak L1 to resonance using an RF probe or scope on the VN10 input. The input signal must be audio, spoken into the front panel microphone to get the DSB. Once L1 is tuned, connect a 50 ohm load to the antenna with some sort of RF indicator (such as a RF power meter) and advance the bias control to give a watt or so output. Then speaking into the microphone should result in a DSB signal suitable for communicating on QRP! No audio input should result in no RF output. The supplied voltage should be kept at 6 volts, remembering that NE602's cannot stand voltage greater than 9 volts. With suitable voltage control such as a 6.8 volt zener diode on these chips, one could use higher input voltage with a corresponding RF output.

There is another way of setting the bias on the VN10. After aligning L1, with a ammeter in the six volt supply line, advance the bias control until the input current increases about 10 mA (with no modulation). If you do not have an FT37-77 ferrite core, substitute 10 bifilar turns on a FT37-43 ferrite core for the T1 transformer

.


Wee Willy Transmitter
a
+ 6 v
b
To Rx
b
Ant
a
Mic
3K3
100K
.1
1K
.001
741
8 7 6 5
1 2 3 4
10K
4.7uF
10K
1K
.1
100
To VFO
NE602
8 7 6 5
1 2 3 4
.1
330pF
.1
L1
50 pF
10K
10K
L2
Q1
d
g
s
.1
100
.1
.1
1K
Q2
d
g
s
Q3
d
g
s
T1
.1
L3
680 pF
470 pF
L1 10.7 MHz tunable Tak Lee IF coil
L2 47 uH RF choke
L3 22 turns # 24 AWG on a T50-2 Powdered Iron Core
T1 T1 is 6 turns Bifilar wound #24 wire on FT37-77 core
Q1 - Q3 VN10 nJFETs

Receiver

The receiver is a direct conversion type with a manual RF gain control in the form of a 5K potentiometer. Listening to a weak signal on the desired frequency the RF stage and the mixer core (T1 and T2) adjustments are made until you hear the loudest possible signal, keeping the input test signal as low as possible. When the receiver is connected to a doublet antenna there is no lack of incoming signal, which can be controlled by the front panel RF gain control.

The antenna and 6 volt supply is switched manually from TX to RX mode and back by a front panel mounted switch. If you can not find Tak Lee green 10.7 MHz IF coils, probably any other brand of 10.7 MHz slug tuned IF transformer would work. The Mouser catalog number 421F123 would work well and in another 80 meter project I used it with a 470 pF capacitor instead of the 330 pF cap shown. I would start with Dick's 330 pf cap and if it will not tune to resonance sharply, slightly increase the cap value up to see if a bit more capacity is required to resonate it on the desired 75 Meter frequency. Note that the secondary coil on the L1 transformer in the transmitter schematic is unused. If your 10.7 MHz IF coil has a built in capacitor at the base, remove it.

During receive, the standby drain current at 6.0 volts was 24 mA and on loud signals it rose to 100 mA. If this is too much, probably the easiest thing to do would be to put in a series resistor from positive to the LM386 to limit the drain current. To get output on the speaker it is a matter of how loud you want it for the drain you draw. If earphone only reception is okay, then the drain could be reduced considerably.


Wee Willy Receiver
a
+ 6 v
100
+
100uF
.1
100
VFO
22uF
10 (1/2 watt)
.1
10uF
+
+
100uF
Speaker
.1
8 7 6 5
NE602
1 2 3 4
.022
8 7 6 5
LM386
1 2 3 4
10
+
.1
4K7
Q2
b Ant
Q1
.001
.001
T1
T2
5K
330 pF
1M
4K7
.1
4K7
330 pF
Tak Lee
Green Core
Tak Lee
Green Core
T1, T2 Tak Lee 10.7 MHz tunable IF coils
Q1 J310 and MPF102
Q2 2N3904 or 2N2222

VFO

Dick's diagram indicate that this VFO was based upon a design presented in SPRAT for summer 1995. The main inductor L1 is wound with #32 AWG wire on a 1/4 inch slug-tuned coil former. This coil would have an XL somewhere between 250 - 310 ohms, so if you cannot find a coil former as described , you could easily wind one on a powdered iron toroid and make a portion of the C1 capacity variable for adjustment. A suggested alternate inductor is 53 turns of #26 AWG on a T68-6 core powdered iron core.

Dick suggests checking an old television to find suitable coil formers such as the one he used. It would probably be best to distribute the 120 pF C1 capacity among 3-4 capacitors to enhance stability. These caps should be NP0 ceramic for best results with frequency stability.

Dick's oscillator uses the slug tuned core to put VFO frequency close in frequency to where you want to operate and the variable resistor tuner on the front panel allows adjustment around the incoming signal to get the correct pitch. The desired band-edge is easily set by adjusting the slug while listening to the VFO frequency as audio on another receiver that has a frequency readout or directly with a frequency counter.

The L2 150 uH RF choke can be a simple epoxy unit which resembles a resistor. The D1 variable capacitance diode is a BB104 which has ~ 35 pF capacitance on each side. These are available at Dan's Small Parts and Kits whose URL is in the Links section of the site info web page. Experimentation with other tuning diodes could produce a practical alternative to the specified D1 part.


Wee Willy VFO
100K
20K
Tune
C1
120 pF
C2
22 pF
C3
22 pF
Q1
470
100
+ 6 v
+
33uF
.1
2.2 v Zener
.1
+
100 uF
D1
100K
L1
Tap 12 t
C4
22 pF
Q2
RX
.01
TX
.01
270K
2K7
150 uH
L2
L1 52 turns # 30 AWG on a 1/4 inch former , tap at
12 turns from the grounded end.
L2 150uH RFC
Q1 Q2 nJFET MPF102 , J310 etc
D1 BB104 tuning diode
C1 - C4 NP0 ceramic caps

Operating Wee Willy

Dick sent me Willy in the mail and the first available moment I fired the little rig up and spanned the VFO which tuned from ~ 3721 to 3738 KHz. I then proceeded to tune 3729, the frequency of BCEN, our SSB provincial public service net and on my first break was able to check in with one call sign repeat to the net control station. The band conditions were noisy and most signals were S8 or lower, however Wee Willy's 1.5 watts P.E.P. were able to check me in with my folded Marconi antenna. I later changed the L1 slug and worked some stations higher up the band. My audio reports were favorible and no one knew I was running DSB. This is a fun radio and it looks cute to boot!

When transmitting, I had to be careful to keep my hand away from the VFO compartment to prevent pulling the VFO frequency with the capacitance change from my hand. The VFO has reasonable long term frequency stability and copying CW stations with the receiver was possible without frequent tuning readjustments.

The following are some digital photos of Wee Willy taken by VE7ZAC.

Move your mouse over the images for a larger version.



From left to right the electret mic, TX/RX switch, RF gain control and VFO tuning control. The number 375 is Dick's project identification number. He has given me many schematics of his projects and each has a unique number and case color. For the non-Canadians, the large coin on top of Willy is our "Loonie" a 1 dollar coin. The large 2 color coin in front of the rig is our "Toonie" a 2 dollar coin.



The hole on the left of this rear panel shot is for adjusting the L1 slug for the VFO. From wherever on the band the VFO is set a front panel tuning range of about 17 KHz was possible. Also shown are the speaker jack , BNC antenna connection and DC power leads.



Wee Willy with the cover off.



These top view shots clearly shows the 3 distinct compartments. From left to right the TX , RX and VFO sections. The VFO has a PC board seperator for shielding. Dick's construction method is well illustrated with this photo. The IC's are in sockets. The 3 VN10s have a small tab on the top. There are no heat sinks on the VN10 finals and they do require any for a 6 volt supply voltage. The rear panel jacks and VFO inductor are all mounted in PC board material.





Here is a bottom shot showing the connecting wiring through the chamfered PC board holes. Many thanks to Dick Pattinson, VE7GC for allowing me to present one of his projects.

Wee Wee Willy by NM8T

NM8T Builds Wee Wee Willy

Steve White, NM8T emailed me a few weeks ago that he was building Wee Willy and was not getting the expected output power. I forwarded his email to Dick and they problem solved the issue. It turns out that the V10KM's were the culprit.

Here are their final two emails:

Steve: I think you have found a solution to your problem. I did not know that VN10's are different. I bought mine in 1994 from a radio parts supplier and they are marked VN10KM F324A1. Have fun with your new rig and let us know how you are doing with it. 73, Dick

Dick, I have completed my little rig and have had a blast with it so far. My first CQ yielded me 3 contacts in Pittsburg, Pa. My friend across town gave me a 20 over S9 report. The three hams in Pa. were astounded that I had only 1.5 watt PEP. I had to use 12 volts and used small 5 volt regulators to feed the NE602's. This works very well. I even used a little homebrew tuner with it and got my swr flat. I am going to take the little rig to Dayton Hamvention next year. I go every year and take a little project each year to show everyone. I hope it is ok to call my little rig Wee Wee Willy, since it is a little smaller than your version. I want to thank you for your help in getting this rig completed and also thank Todd for his help in getting me in contact with you. Your little rig is very neat and right up my alley for a QRP rig. I look forward to working you someday on QRP. I'm 47yrs. old on the 24th of this month. I have a whole room full of QRP rigs such as HW-7, HW-8, HW-9, Argonaut 509, 515, Powermite PM-3a. Have built a Cascade, LCK, Spider, MXM, Keyers, Tuners, and all kind of other projects. I love QRP and hope to build many more soon. The Wee Willy is one of my favorite rigs. Here are some pictures for you and Todd. Thanks and Hpe CU Agn. 73's NM8T (No more 8 Tracks) Steve White - Fayetteville, WV

75m DSB
Tune – Wee Wee WILLY – Gain
MIC



My special thanks to Steve White and Dick Pattinson.

Countless builders have constructed the Wee Willy on several bands. Here are 2 more examples. Paul, KE7HR Link1 and Link 2. The finals even made it into the the BITX17 transceiver. Allan Yates published some good work on the final amp.

I've also tweaked Dick's design, but decided to leave his little rig and this web page alone out of respect to him. It's always easier to improve rather than actually *design* something. I'll never better the experiences I had operating and documenting his transceiver.

Update February 15, 2011

I lost touch with Dick and decided to call him on Feb 10, 2011. He's 95 years old and no longer building. Sadly, his wife Christina died 2 years ago. She was a beautiful person and a gifted painter. Dick remains astonished that Wee Willy - Project 375 QRP Radiophone has been built by at least 50 people (that I know about) world wide, the subject of blogs and the basis/inspiration for numerous radio projects. I met Dick on 80 meters and my wife and I once visited his residence and spent 2 glorious, days on Saltspring Island with he and his wife.

Dick sent me the radio and documentation on Aug 13, 1998. He was a hardcore builder and a professional electronics technician who, for a time, flew his float plane to service equipment in the Gulf Islands of British Columbia. Dick keeps many binders full of his carefully numbered and well documented projects. He gave me a few sheets for my reference library as a gift. Dick's work inspired me early on and I cherish the time I had Wee Willy in my radio shack - blown away by DSB, QRP and such a novel little radio.

Dick asked me to send his greetings to all QRP Homebuilders everywhere.

More Updates

Aug 25, 2011

Hi. Been viewing your web site for a while, lot of great information for builders. I thought i would let you know that I built the "Wee Willy", it works great, so good that I decided to try building one for 20m. I built the 20m version with a 14.318 crystal instead of a VFO ideal for my local net, also changed the PA circuit using IRF510 giving me 2.5W output, the transistor can run 5W, but it does get rather hot, I must say that the quality of the transmitted audio is amazing, everyone comments how good it is and some do not believe it is home-brew!!! I have put a few CQ calls out with a simple dipole and made contacts into Belgium, Netherlands, Finland and Saudi Arabia. Many thanks again for putting the Wee Willy on your website, it has opened my eyes to how well you get get out with QRP power.

Regards Wayne. M0WAY. Click for Wayne's fabulous Wee Willy bread board.

Sept 19, 2011

Wayne, M0WAY wrote again,

I built another Wee Willy and put it into a box, but with a few extra bits:

A new VFO was added that runs 14.190 – 14.350 MHz (an 11 MHz crystal oscillator + a 3.2 MHz VFO + a band-pass filter) I got the power up to 4W, however the audio was a little over powered from the extra RF, so I had to reduce the audio gain and added an antenna switching circuit, after I burnt out my receive circuit with the 4W output.

Here's Wayne's PA (from the NE602 on ** updated July 12, 2012 **) Click for a photo of his latest incarnation. Thanks again!

Oct 19, 2011

Mark, WA4JAT built a "0 cost" Wee Willy from 100% junk box parts including a CB radio transistor for the final. Click and click. Mark tunes the VFO using an air variable capacitor mounted in the former Heath Kit signal tracer project chassis. The cable running out of the front is the microphone coax with an electret mic at the end. Employing large size VFO, Rx and Tx boards facilitate easy future modifications. Awesome work Mark!

JFET BIASING TUTORIAL BY W7ZOI

This tutorial is copyright © 2000-2001 by Wes Hayward, W7ZOI.

JFET Biasing and an Amplifier Design W7ZOI, 30Dec00.

Junction Field Effect Transistors (JFETs) are generally no more difficult to bias than a bipolar transistor. In many ways they behave essentially like a classic triode vacuum tube. The current flowing between FET drain and source is controlled by the gate-to-source voltage, V_{GS}. (This is the voltage you would measure with a voltmeter connected between the gate and the source.)

The Fig. 1 schematic defines the parameters we use to describe the DC behavior of a JFET. The 100 Ohm resistor is added to preserve UHF stability during measurements. The gate voltage, V, is then varied while measuring drain current. The results are then plotted, as shown in Fig. 1. The FET is characterized by the simple quadratic equation below the schematic with the two FET related parameters of I_{DSS} and V_P. I_{DSS} is the drain current when the gate is short circuited to the source. The pinchoff voltage, V_P, is V_{GS} when the drain current is essentially zero. The example in Fig. 1 has I_{DSS}=20 mA and V_P=-4 volts. Source and drain current are identical in the JFET.



$$I(V) := I_{dss} \cdot \left(1 - \frac{V}{V_p}\right)^2$$

$I_{dss} := 20$ mA $\quad V_p := -4$ volts

Figure 1

Basic behavior of an N-Channel depletion mode JFET.
The numbers shown basically illustrate the ideas.

The experimenter wishing to use a JFET in a circuit will most often use the method called "self biasing" where a resistor is placed in the source lead. The gate is grounded. The FET current also flows in the resistor. The current generates a voltage drop that elevates the source voltage above that of the gate, which is the same as biasing the gate negative with respect to the source. This establishes a drain current less than I_{DSS}.

Drain voltage is not critical so long as it is a few volts greater than the source.

The resistor value for a desired bias is calculated with Equation 1 if I_{DSS} and V_P are known. But these parameters are rarely well specified. For example, the popular J310 is characterized only by ranges: I_{DSS} is 24 to 60 mA and V_P is -2 to -6.5 volts.

$$R_s := \frac{V_p}{I_D} \cdot \left(\sqrt{\frac{I_D}{I_{dss}}} - 1\right) \qquad \text{Eq.1}$$

I_{DSS} and V_P are easily measured for a specific FET with the circuit shown in Fig. 2. The circuit is built with a variety of source resistor values and the source voltage is then measured for each with a high impedance voltmeter. The pinchoff voltage will then be the negative of the source voltage when R_S is a large value such as 100K. Grounding the source through a current meter generates a direct reading of I_{DSS}. This brief measurement will provide enough data to allow biasing.



Figure 2

Circuit used to determine FET DC parameters.

This experiment was performed with a junk box 2N5454, producing the parameters I_{DSS}=11 mA and V_P=-2.8 volts. The current equation from Fig. 1 is plotted in Fig. 3 with these parameters. Additional points were measured producing points close to the curve.



Figure 3

Data and smooth curve for a 2N5454 we measured.
This FET has a pinch off of -2.8 volts and a IDSS of 11 mA.

This exercise SHOULD be done with virtually every FET that the experimenter uses. It is not enough to obtain data for a given FET type, although if a group of parts are available from one manufacturing batch, moderate uniformity might be expected.

We mentioned the J310 earlier with an I_{DSS} spread from 24 to 60 mA. That 2.5:1 span range is one of the better of commonly available parts. The historically popular MPF-102 has a 10:1 spread in I_{DSS} (2 to 20 mA) with V_P extending from -0.5 to -7.5 volts! Clearly, this part should be used only with extreme care. It's a good RF part, but one MPF-102 may not resemble the next.

Assume the FET we summarized in Fig. 3 was to be used in an amplifier and that we wished to bias the FET for 5 mA. The 5 mA point can be picked on the graph and matches V_{GS} of approximately -0.9 volt. 0.9 volt drop from 5 mA matches a resistor of 180 Ohms. Application of Eq. 1 produces 182 Ohms. Crosshairs indicating the 5 mA point are included in Fig. 3.

Once a FET has been biased, it can be used in a small-signal amplifier. The significant gain parameter is the transconductance, given by Eq. 2. Transconductance is the drain signal current flowing for each volt of signal applied to the gate. Note that g_M depends upon the bias current. The g_M value given in data sheets corresponds to operation at I_{dss}.

$$g_m = 2\cdot\frac{I_{dss}}{V_p}\cdot\left(1-\frac{V_{GS}}{V_p}\right) \qquad \text{Eq.2}$$



$$I_{dss} := .011 \quad V_p := -2.8 \quad V_{GS} := -0.9$$

$$g_m := 2\cdot\frac{I_{dss}}{V_p}\cdot\left(1-\frac{V_{GS}}{V_p}\right) \qquad g_m = -5.33163\cdot 10^{-3}$$

Figure 4

Data used to produce transconductance for the FET used in our sample amplifier.

Evaluation of g_M from Eq. 2 for our 5 mA bias produces the data in Fig. 4.

Consider the amplifier shown in Fig. 5. We will use this as an output buffer for an oscillator. Assume that we have tapped a signal from the oscillator tank where a voltage of 1 volt peak-to-peak is available. When this is applied to the FET gate, a current of 5.33 mA pk-pk will flow. The transformer uses a 15 turn drain winding and a 3 turn output link on a FT37-43 ferrite toroid. This turns ratio transforms the 50 Ohm load to appear as 1250 Ohms in the drain line. A current of 5.3 mA pk-pk flowing here produces a voltage of 6.25 V pk-pk. The no-signal drain voltage will be about 11 volts, so positive and negative 3 volt excursions will not cause voltage limiting. The current will vary from the 5 mA DC value down to nearly 3 mA (still well above zero) and up to nearly 8 mA, still below I_{dss}. The signal at the 50 Ohm load is reduced by the transformer to 1.33 V pk-pk. This is about +6 dBm, enough power to drive a diode ring mixer. This simple circuit is a low noise, efficient, and very useful amplifier.



Figure 5

Common source amplifier biased for 5 mA drain current.

Figure 6 shows a FET amplifier that uses "long tail" biasing. A negative power supply is now used, forcing the biasing resistor to behave like a constant current source. This method can accommodate a wide range of FETs of a given type if the bias is set up for $I_d < I_{dss}$-min.


+12v
51
.1
100
.01
1 Meg
2.48K
.1
.1
100
-12 V

Figure 6

Amplifier with "long tail" biasing. This amplifier is biased for 5 mA and is identical in performance to that of Figure 5, but does not require the careful device characterization.

RF — Test and Measurement

EMRFD Review

Experimental Methods in RF Design

$49.95
EXPERIMENTAL METHODS
in RF DESIGN
Wes Hayward, W7ZOI
Rick Campbell, KK7B
Bob Larkin, W7PUA
ARRL
CD-ROM INCLUDED

First published by the ARRL in 2003, EMRFD serves as the main QRP/SWL Homebuilder site reference.

Written by Wes Hayward, W7ZOI, Rick Campbell, KK7B and Bob Larkin, W7PUA, EMRFD is the follow-on to the 1977 ARRL publication, Solid State Design For The Radio Amateur (SSD).

A treasure trove of narrative and tabled information, schematics, references and photographs adorn this lengthy (512 page) book that comes with a data CD filled with software and key reference papers. With the included CD, EMRFD is about twice the size of the original SSD.

Wes and crew emphasize fundamental radio equipment design and bench testing rather than providing the usual catalog of circuits to just casually copy and not carefully examine.

Since we amateur builders own varied skills, abilities and test equipment, some sections may intimidate readers, while others may inspire and drive your bench practices to a higher level of competence and joy. The heart of RF design lies in measurement and reason: EMRFD emphasizes this and in doing so alienates some readers.

For some, homebrew radio electronics and kit building are synonymous — plenty of kits are sold to builders who chose to build someone else's design, rather than capture their own ideas on a scrap of copper board, or at least, to modify their equipment to suit their needs. EMRFD may appeal to builders who enjoy learning about RF *design*, or want more innovative and creative bench experiences — 1 stage at a time.

Although stressing that *build and measure* = a proven way to improve in this hobby, Wes and team share other pearls including bread boarding techniques, parts lay out, hot parts and pitfalls to avoid.

The first chapter is simply called Getting Started. On page 8, Wes shares his first simple receiver design — this page starts your breadboarding in haste! EMRFD features information and designs for all levels of experimenters, although basic electronics knowledge and some experience are needed to get the most out of its content.

Replete with sidebar examples about measuring or calculating data for common circuits, EMRFD also offers general purpose stages including a universal monoband superhet receiver front end or AF chain instead of less versatile, single- application circuits. The design information feels vibrant and flexible and some of the material is original, or presented in a way that adds to the existing amateur radio knowledge base. For example, new front-end mute circuits, or the cascode JFET mixer and RF amplifier.

Wes also shares some new ideas for RF and IF amplifiers ranging from simple to state-of-the-art. This book has something for everyone — I prefer to describe EMRFD's influence on our hobby in simple action verbs such as: improve, innovate, inspire, explore and transform.

Software:

The Microsoft Windows programs run on everything up to and including Windows 7. While a few programs are new, others represent updates of the historic W7ZOI Ladpac applications. Upon mastery of the Ladpac program suite, you'll generate the needed stages to boost *your* designs.

For example you can design complex double or triple tuned band-pass filters for your projects without any math — the software gives you the series capacitor values so you need not worry about putting links on your inductors to match input or output impedances.

EMRFD = the **must have** reference book for your homebrew workshop.

See CD-ROM contents which
immediately follows Chapter 12.
ARRL
Acrobat® Reader
copyright © 1987-2003
Adobe Systems
Incorporated.
All rights reserved.
Adobe and Acrobat
are trademarks
of Adobe Systems
Incorporated.
Supplemental CD for
Experimental Methods
in RF Design
First Edition
disc

[ARRL EMRFD web link]

[Link to the W7ZOI errata page for EMRFD]

RF — Test and Measurement

Tapped Capacitor Impedance Transformation in LC Bandpass Filters

copyright © Wes Hayward, W7ZOI, April 30, 2003.



We often use a pair of capacitors to match impedances at the termination ends of LC bandpass filters. The circuit consists of a shunt capacitor at the termination followed by a series capacitor connecting to the high Z end of a parallel tuned circuit. Some readers have asked about how the capacitors are picked. Although there is considerable flexibility in some of the choices, it is not empirical as some have guessed. A simplified double tuned circuit design sequence is presented in the sidebar on page 3.14 of EMRFD and this is the beginning of the analysis used in the programs DTC.exe and TTC.exe contained on the EMRFD CD. I'll not go into too much detail here, for it's in EMRFD, beginning on page 3.8, and in chapter 3 of IRFD. Here is what happens in the programs:

Bandpass filter design begins with an almost arbitrary choice of inductor. We pick 3 uH for a 7 MHz double tuned bandpass filter that we will use to illustrate the ideas. This L resonates at 7 MHz with 172.3 pF.



A bandwidth and center frequency are picked for the filter. This establishes a filter Q. The Q of an end section is then determined by the desired filter shape (Butterworth, etc)Let's say we want to do a 7 MHz center frequency Butterworth filter with BW=0.2 MHz. Filter Q is then 35=7/0.2. QE will then be 35x(root(2))= 49.5. The QE value in the sidebar (p3.14) includes the effect of finite inductor Q. Assume a lossless inductor for this example.

So what does this mean? It means that the end tuned circuit, when not coupled to the rest of the filter, needs to be set up to have a Q of 49.5. This is experimentally significant. (ref: QST, Dec, 1991). The reactance at 7 MHz of our 3 uH inductor is X=131.9 Ohms, so we need to load each end with a resistance R=QX=6.53K-Ohm.

What this means is that we would realize our double tuned bandpass filter with center frequency of 7 MHz and bandwidth of 200 kHz if we terminated a simple double tuned circuit in 6.5K at each end. The filter is shown below where we have used additional equations (EMRFD p 3.14) to calculate the coupling and tuning capacitors.



This is a useable filter design, for it will generate the desired shape and bandwidth. But, it is not very practical; it does not fit in our low impedance world.

The filter can be redesigned. One classic, but usually impractical solution is to scale the filter to lower impedance levels. For example, if we dropped L from 3 uH to 23 nH, we could directly load our filter with 50 Ohms and get the required end section Q. But this is not at all practical. First, it's difficult to build inductors with L this small and still have reasonable Q at 7 MHz. Second, the parasitic inductance of the rather large (high C) capacitors that we would attach to this inductor would begin to compare to 23 nH. A better re-design would use transformation circuits, schemes that will let us use a 50 Ohm termination (or whatever we need) and make it function as a 6.5K resistance when seen by the inductor.

One such scheme is a transformer. This could be realized with ferrite cores or with links inductors wound on the existing 3 microHenry parts. But link coupling with design precision is a challenge of it's own. Conventional two and three element transforming networks (L, pi, Tee) are also suitable.

The simplest transforming circuit uses a series capacitor. Let's do some analysis to see how this works:

We have arbitrarily picked a 10 pF capacitor to illustrate the idea. At 7 MHz, the reactance of a 10 pF capacitor is 2274 Ohms. Hence, the complex impedance of the 50 Ohm resistance and the series capacitor is Z=50-j2274. The impedance transformation behavior of this circuit is studied by transforming the series impedance to a parallel admittance. Recall that Y=1/Z. So Y=1/(50-j2274). The result is Y=(G+jB)=9.67E-6 + j4.4E-4. Of special importance is the resistive real part of the admittance.



The 10 pF series capacitor in our example makes the 50 Ohm resistor look like a 103 K-Ohm resistor in parallel with a capacitor that is nearly 10 pF. The general case causes a R0 value resistor to look like a value of Rp with a series capacitor with reactance given by



$$X_C = \sqrt{R_p \cdot R_0 - R_0^2} \qquad \text{Eq. AA}$$

This equation is #3.1-5 from IRFD where it is derived.

Our original example filter needed a parallel resistance, Rp, of 6.5K-Ohms, which is produced by a series capacitor with a reactance of 568 Ohms. This is a capacitor of 40 pF. Another version of our double tuned bandpass filter is then

Notice that the tuning capacitors, the elements across the inductor, have dropped as C is added at the ends.



A capacitor in series with a resistance produces higher equivalent resistance. Consider a parallel combination. Here we pick a value of 200 pF as the parallel C and calculate the admittance. This is then converted to an impedance with Z=1/Y and the individual components are evaluated. This result is shown to the right.



$$Y = G + j \cdot B$$

where

$$G = \frac{1}{R} \quad \text{and} \quad B = \omega \cdot C$$

The parallel capacitor transforms the 50 Ohms to behave like a lower value.
In this case, we obtain about 42 Ohms in series with a 1236 pF capacitor.





$$C_p = \sqrt{\frac{R_p \cdot C_s^2}{R_0} - \frac{1}{R_0^2 \cdot \omega^2}} - C_s$$

Eq. BB

A series capacitor transforms a termination to “look like” a higher resistance while a parallel capacitor “transforms to” a lower R. Clearly, the combination of the two can generate about any result we need, realizing that they will also produce reactance that must be absorbed into the existing tuned circuits. The mathematics (now symbolic and not just number manipulation) is messy, but not difficult. A resistive termination R0 (50 Ohms or whatever) is paralleled by a capacitor Cp. The admittance is calculated and is converted to an impedance. The impedance of a series capacitor, Cs, is then added. The result is converted back to an admittance. The resistive real part is extracted and inverted to yield Rp. This expression is then solved to yield a design equation:

This is the equation used in the programs. A related expression provides the equivalent capacitance, needed to calculate the tuning capacitor for each resonator.

If we use the program with the center frequency and bandwidth presented earlier, we find that the minimum allowed series capacitance is 40 pF. If we then insert a value of 47 pF, we see that parallel 240 pF capacitors are needed to properly load the resonators. This variation is shown to the right. Circuits using the capacitor tap are practical, for they allow existing junk box parts to be used. The topology has little other utility, offering virtually the same response as a filter using only series capacitors for loading.



Useful link shared by Tim, KE7VYD on Feb 4, 2014. Click

Amateur and Short Wave Radio Electronics Experimenter's Web Site

More Active Antenna Experiments

Introduction

Many builders emailed me requesting a simple, broadband VPA (voltage probe antenna) design with more power gain than the common gate versions I have presented elsewhere on this web site. Connecting a whip antenna to a cascode JFET stage described by W7ZOI in Experimental Methods in RF Design is 1 method I considered.

I built the version shown in Figure 1 almost 2 years ago. This VPA. although more powerful, overloaded the front end of my test receiver with multiple RF signals. Clearly some tuning on the input was needed.


Experimental Broadband Cascode JFET VPA
9 VDC
100
.1
T1
30
3
50 ohms output
100K
Whip
Ant
Hi Z output
d
g
s
Q2
.001
100K
.1
.01
d
g
s
Q1
1M
100
.1
1N4148 x 2
Q1 , Q2 MPF102
T1 30t primary, 3t secondary on a FT50-43 core

Figure 1

Feb 2005 by VE7BPO

The Tuned Whip

Previous experimentation confirmed that it is easy to tune a short whip antenna by connecting it to the hot end of an L C (inductor and capacitor) tank circuit. The high impedance whip antenna was "matched" to a JFET RF amplifier by placing a high value (1 megohm or greater) on the JFET gate to ground. Although this method is practical, I desired a network to transform the output impedance of the tuned whip tank tank circuit to a known impedance. I do not possess the knowledge or mathematical skill to design such a network and asked Wes Hayward if he might consider doing this for me. My desired parameters for the network were 10.0 MHz, a 50 ohm output impedance and a 4 foot (122 cm) whip. Please refer to Wes' calculations and schematic in Figure 2 below. This math is difficult, however, a practical design for experimentation is provided.



Antenna Network. The antenna is a short whip at 10 MHz. We assume a length of 4 ft with a diameter of 0.25 inch. EZnec modeled this as 7.58 pF in parallel with 3.3 MegOhm. We assumed a perfect, ideal ground for a vertical with 48 antenna segments.

$R := 3.3 \cdot 10^{6}$ $A := 7.58 \cdot 10^{-12}$ $C_1 := 47 \cdot 10^{-12}$

$C_2 := 470 \cdot 10^{-12}$ $Z := 50$

$L := 3 \cdot 10^{-6}$ $Q_u := 200$

$f := 10$ F is in MHz.

For given values of C1, C2, Z, A, R, L, Qu, we wish to calculate the value for V needed for tuning to the desired frequency (10 MHz) and the overall network Q.

$\omega := 2 \cdot 10^{6} \cdot \pi \cdot f$

"whiptune.gif"

$$R_Z := \frac{Z^2 \cdot \omega^2 \cdot C_1{}^2 + 2 \cdot Z^2 \cdot \omega^2 \cdot C_1 \cdot C_2 + \omega^2 \cdot C_2{}^2 \cdot Z^2 + 1}{\omega^2 \cdot C_1{}^2 \cdot Z} \qquad R_Z = 8.343 \times 10^{3}$$

$$C_Z := C_1 \cdot \frac{\left(1 + Z^2 \cdot \omega^2 \cdot C_1 \cdot C_2 + \omega^2 \cdot C_2{}^2 \cdot Z^2\right)}{\left(Z^2 \cdot \omega^2 \cdot C_1{}^2 + 2 \cdot Z^2 \cdot \omega^2 \cdot C_1 \cdot C_2 + \omega^2 \cdot C_2{}^2 \cdot Z^2 + 1\right)} \qquad C_Z = 4.39 \times 10^{-11}$$

The inductor resonates at f with Cnet, obtained with the usual resonance condition.

$C_{net} := \frac{1}{\omega^2 \cdot L}$ We must now subtract the C of the whip plus that from the load to get the variable needed to tune.

$C_V := C_{net} - C_Z - A$ Note: If CV is negative, we must reduce L or C1 to get a postive value.

$C_V = 3.295 \times 10^{-11}$

The net resistance across the inductor is the parallel combination of RZ, R(antenna), and the R related to Qu, Rp=QuωL.

$G_{net} := \frac{1}{R_Z} + \frac{1}{R} + \frac{1}{Q_u \cdot \omega \cdot L}$ $R_{net} := \frac{1}{G_{net}}$ $R_{net} = 6.817 \times 10^{3}$

The net Q is given as $Q_{net} := \frac{R_{net}}{\omega \cdot L}$ $Q_{net} = 36.167$

Figure 2

By W7ZOI Feb 27, 2005

Common Gate Amplifier Version

I built the circuit shown in Figure 3 and Figure 4 and tested it on a medium grade SWL receiver (Realistic DX 300), rather than an expensive Amateur Radio receiver. I required this active antenna for experimenting with a 10 MHz WWV superheterodyne receiver I am designing. For practical analysis, VE7TW and I did listening tests with a commercially made 4 foot telescopic whip antenna that is fitted to a standard PL-259 connector (Figure 5) and his deluxe multi-band commercial SWL antenna up a 25 foot tower.

The Figure 3 VPA was very quiet
and pulled in WWV much better



L1 = 3 uH = 23t T68-2 or 35t T50-2 powdered iron torroid
L2 = 3 uH = 25t T50-2 with tap 6 turns from cold end
CV = 10-40 pF trimmer capacitor
RFC = 4.7 - 22 uH
Q1 = Q2 = 2 similar JFET types such as MPF102 or J310

Figure 3

than the plain 4 foot whip of Figure 5, however, received station signal strength was quite weak when compared to the outside antenna. Our conclusion was that considering the significant losses of the 4 foot whip antenna it was connected to, the common gate RF amp does not likely have enough voltage gain to please most builders. This amp did present a low impedance to the whip network and no spurious oscillation were measured on the bench. Do not omit the 22 ohm or similar value resistor in the drain of the FET. It is used to to push the UHF parasitic oscillation tendency into the ground. Such oscillations will trash your receiver mixer intermodulation performance.

The 150 ohm source resistor can be increased in value and/or 1 of the JFETs removed if you wish to reduce the current draw on a 9 volt battery. It might be better to substitute 1 better JFET such as the J310 rather than use the "popcorn" MPF102 as shown. This VPA may be practical for a receiver that has an existing broadband RF preamplifier. The tap on L2 was found experimentally and the output impedance is probably higher than 50 ohms, but is likely a reasonable low impedance match to most receiver front ends. A broadband transformer for L2 might also be a good choice.


Figure 4


Figure 5

Figure 4 above: For the whip network, it is critical that you use a inductor that has an unloaded Q of 200 or above. Practically speaking, this means you cannot use a fixed value inductor such as an epoxy coated or molded RF choke. Use a powdered iron torroid instead. In my test VPA designs, for L1, I used a T68-2 core wound with (the green) 22 gauge enamel coated wire to get as high an unloaded Q as possible. If you use the T50-2 core, use 24 gauge wire if possible. Higher Q = lower losses.

Figure 5 above: This is a 4 foot whip antenna factory connected to a PL-259 that came with the Realistic DX300. It presents a very high impedance to the test receiver front end and probably wasn't a good choice to compare the VPA designs to.

Cascode JFET Amplifier Version

It was decided to use a cascode JFET amplifier to obtain more power gain. The whip network was changed to try to match the 10K input of the JFET amplifier shown in Figure 6. The whip network capacitor values (150 and 33 pF) were calculated to the best of my ability. This amplifier was tested in the same manner as the Figure 3 design. It worked very well. The WWV signal that morning was not very strong and could not even be heard with the plain 4 foot whip. The signal strength of the tuned whip was just below that of the outside antenna. The outside antenna was much quieter however and had less fading. The tuned whip antenna was quite noisy in comparison. The high gain RF amp brought up the strength of the environmental noise sources in the house. The RF gain of the receiver was reduced to compensate for the added noise.

Another problem was noted with this and other tuned drain versions of the cascode JFET amplifier; instability.

Recently, I connected a tuned drain version of the Figure 1 VPA to a receiver that contained a tuned input stage and was able to measure oscillations in the VPA with my scope. The FET drain tank and the tuned input amp seemed to be interacting.



10 MHz Tuned Whip Active Antenna

L1 = 3 uH = 23t T68-2 or 25t T50-2 powdered iron torroid
L2 = 3 uH = 23t T50-2 with a tap 6 turns from the cold end
CV = 10 - 40 pF trimmer capacitor
Q1 = Q2 = MPF102 nJFET

Figure 6

March 6, 2005 by VE7BPO

A "swamping" resistor was placed across the VPA drain tank circuit. I had to use a resistor value of less than 1200 ohms to eliminate this instability. This greatly reduced the gain and selectivity advantage of a tuned output and I realized that output tuning may be impractical for many reasons. Some SWL builders use regenerative receivers and such a problem would be disastrous. I sent the Figure 6 schematic to Wes Hayward and he suggested using a broad or wide band amplifier as shown in Figure 8.

Instability can also occur in broadband output versions and a swamping resistor is still necessary but is used mostly to force an output impedance so that a transformer can be designed.

All of the cascode JFET amplifiers shown have fixed bias on Q2. Variable gain is possible by changing the bias voltage on Q2 with a voltage divider and/or modifying the amplifier circuit to give a greater range of bias controlled voltage gain. Please refer to EMRFD page 6.17 for information regarding this. A switchable resistor attenuator might also be practical for some builders.

Figure 6 above: The tuned whip network is connected to a cascode JFET amplifier. A dual gate MOSFET would also be a great choice. I have many on hand, but chose the cascode JFET topology because many builders no longer have access to these devices or prefer not to use the more available surface mount types. They are also more expensive.

Figure 7 to the right: Detail of the tapped L2 inductor should you decide to experiment with a tuned drain version or need one for another project. Wind your coil and leave an extra long loop for your wire tap. Cut the tapped loop at the midpoint and use a small piece of folded ~150 grit sandpaper to remove the enamel from each of the 2 wires. Twist the now bare wires together and lightly solder them. Cut the end wires to the required length and use the sandpaper to remove the enamel. A method to strip enamel off wire is a frequently asked question for me and sandpaper works well.


Figure 7

Broadband Output Version

Figure 8: The broadband version W7ZOI suggested to try building. I modified the output transformer in the Figure 6 project and tested it with Tom, VE7TW. We really liked it. By adjusting the network trimmer capacitor, I was also able to tune the 30 meter Amateur radio band as well. For 30 meter band use, I peaked the tank circuit at 10.125 MHz by listening to receiver noise with a home brew direct conversion receiver and was suitably impressed.

This is the active antenna design I wll use for my future projects where strong voltage gain is required. If your receiver has a higher impedance such as 500 ohms, you might try using a couple more links on the output transformer secondary winding.



Figure 8

W7ZOI March 6, 2005

Tuning a Whip To Other Frequencies



Figure 9

The ability to calculate the network values for different frequencies may prove difficult for those who lack software and/or math skills. To that end, a table follows which has some radio frequency bands and some suggested starting values for the Figure 9 parameters. Please note these are calculated and are suggested starting points based upon my limited understanding of radio electronics. Experimentation is the best method to find what component values will work for you.

Emails regarding the component values used in actual experiments is greatly welcomed.

The **R** value is the input impedance of your RF amplifier. In the case of the cascode JFET amp, it is the Q1 gate resistor.

Note that the actual circuit CV value is typically much lower than the suggested (calculated) CV value from the chart. CV is used to **resonate** the tank. CV is dependent on several factors including the capacitance of the whip antenna, your RF amplifier input capacitance , your circuit layout, component lead lengths and variations in the powdered iron core and C1 and C2 capacitors values. Expect that your whip antenna will exhibit between 8 and 15 pF of capacitance. You need to subtract this from the suggested (calculated) CV value from the Figure 10 table.

Wes, W7ZOI told me that the whip antenna capacitance will remain constant as you change frequency providing you are below 1/4 wavelength for a given frequency. Here is a good web site applet to calculate wire or whip 1/4 or 1/2 wave lengths per frequency: http://www.csgnetwork.com/antennagenericfreqlencalc.html.

The actual circuit CV might include a trimmer capacitor plus a parallel fixed value capacitor.

How to find the correct trimmer capacitor for any tuned circuit you wish to resonate

I suggest you chose a circuit CV value by placing a variable trimmer capacitor in your circuit that when set to minimum will be below half or more than the calculated CV value. Then peak the whip tank circuit using a test oscillator and scope or RF probe or by just using receiver noise. Now temporarily add a 5-10 pF capacitor in parallel with trimmer capacitor. Just barely solder it in place or even just hold it in place without touching the leads. If the output increases, you were under the correct circuit CV value. Add more capacitance and check again. Repeat until you are satisfied with your chosen circuit CV value.



Tuned Whip Suggested Starting Values						
Band	**Freq** (MHz)	**CV** (pF)	**C1** (pF)	**C2** (pF)	**L** (uH)	**R** (ohms)
120M	2.3-2.5	270	150	22	15	2K2
90M	3.2-3.4	165	150	10	12.6	4K7
75M	3.9-4.0	115	150	33	11	4K7
49M	4.75-5.060	83	47	22	11	4K7
41M	7.10-7.60	75	150	18	5.1	10K
31M	9.2-9.9	73	150	22	3	10K
25M	11.6-12.2	58	47	18	2.5	10K
22M	13.57-13.87	34	100	47	2	10K
19M	15.1-15.8	32	47	33	2	10K
16M	17.48-17.9	38	33	27	1.5	10K
13M	21.45-21.85	19	27	39	1.5	10K
11M	25.6-26.1	26	18	36	1	10K
10M	26.965-27.41	22	18	39	1	10K
Some Amateur QRP Frequencies						
80M	3.56	185	150	5	10	4K7
40M	7.04	85	220	10	5.1	10K
20M	14.06	56	22	10	2	10K
17M	18.069	36	33	27	1.5	10K
15M	21.06	22	27	39	1.5	10K
15M	21.06	27	18	39	.8	10K
15M	21.06	48	33	10	1.0	22K
10M	28.06	19	18	47	1	10K
10M	28.06	29	15	33	0.8	10K

Figure 10

If after adding the initial 5-10 pF capacitor, the output decreases, try peaking the tank again to see if you can restore the signal strength you had before you added the temporary capacitor. If after peaking, the signal strength is down, you now have too much capacitance and can remove the temporary capacitor.

You just might also have too much capacitance. You might try a smaller variable cap or reduce the value of any fixed capacitors in parallel with your trimmer to make sure your minimum capacitance is not too high to properly resonate the input tank circuit.

The point is you need to be able to tell if you have too little or too much capacitance for CV and by going under and over you can tell if you are truly resonating the tank when you adjust the trimmer capacitor. Experimentation will tell you.

Another option is to put in a front panel adjusted variable capacitor. Front panel switchable inductors might also allow other bands to be tuned with 1 tuned whip network.

Moving your body as you adjust the trimmer capacitor can change the tuning, so please keep this in mind.

Figure 10 above. Picking an inductor value for the whip network can be tricky and sometimes trial and error is required. This table may be used to find starting values for the Figure 9 network. Below 41 meters, I suggest trying a lowered RF amp input impedance as shown to allow practical component values. Most of these calculations have not been tested.

I think an indoor active antenna for 74 meters or below might just be a noise generator.

I chose a frequency mid band for any given SWL band on the chart. The bandwidth of the input network is wide enough so this should be suitable to cover a good portion of the band.

Building An Active Antenna

To build this active antenna, chose the input tank network values from the Figure 10 chart or from your own calculations and then use them in the Figure 6 circuit. The Q1 source resistor can practically be from 100 to 390 ohms depending on how long you need your 9 volt battery to last. Increasing this resistor value will reduce the amplifier power gain. Try different values and see for yourself!

Some Practical Examples: 40 and 41 Meter Band

An active antenna that would provide coverage of the entire 40 meter Amateur Radio and 41 meter Shortwave band was designed. A varactor diode was used as the tuning element. The tuning voltage to the varactor was controlled by a 10K potentiometer which also had an integral switch. The finished VPA is shown in Figures 11 and 12.



Figure 11



Figure 12

Figure 13 below: A hotter JFET, the J310 was used in this VPA. In the test receiver, I was able to peak a signal from ~ 6.90 to 7.60 MHz. Tuning is very sharp but peaking is easily performed by turning the potentiometer gently back and forth while listening to receiver noise or a station. It might have been better to use a smaller value zener diode as when the 9 volt battery fades below 7.5 VDC, the zener diode will not conduct and the voltage regulation will fail. Having said that, this "hotter" VPA is intended for use with an external power supply as current draw at 9 and 12 volts is 19 mA and 28.9 mA respectively.

I tried using this VPA as the antenna for the Cascode 7 receiver shown elsewhere on this web site. When the VPA was peaked at the receiver tuning frequency, loud oscillations occurred. The receiver and the VPA were about 1 meter apart. I had to turn on the -10 dB attenuator and detune the VPA for the oscillations to stop. Moving my hand near the whip antenna varied the oscillations. The high gain, tuned circuits of the Cascode 7 receiver are not a good choice for an active antenna.

Future receivers projects will have a integral VPA and clearly the front end of these receivers will have to be designed carefully. A low cost Grundig receiver was also overloaded with this VPA.

This VPA worked well with other receivers which did not have a tuned, high gain preamp.

Figure 14: From the chart, the MV209 exhibits about 44 pF (guessing) when 0 volts are


40 - 41 Meter Band Active Antenna
L1 = 5.1 uH = 30t #22 on a T68-2 or 32t #24 on a T50-2
T1 = 12t primary : 2t secondary on FT37-43
D1 = 7.5 volt zener diode
D2 = MV209 varactor diode
Q1 = Q2 = J310 nJFET
1K
9 VDC
S1
.001
470
D1
Tune
10K
100
.1
T1
.1
1K8
50 ohms output
100K
39
d
g
s
Q2
.001
100K
.01
4 foot whip
.1
220 pF
d
Q1
L1
g
s
10 pF
10K
180
.1
D2
220K

Figure 13

Mar 12, 2005 VE7BPO

applied to it.

The VPA was built and tested before the tuning diode components were added. A 7.039 MHz crystal oscillator with a piece of wire for an antenna was used as an RF source. The T2 secondary was connected to ground via a 47 ohm load resistor.

A 47 pF fixed capacitor was lightly soldered in parallel with L1 and the voltage was measured with an oscilloscope. A 10 pF capacitor was then carefully held across L1 and the voltage increased by 0.25 volts. A 22 pF capacitor was then tried and the voltage decreased much below that of just the 47 pF capacitor. The nearest standard value I had on hand above 47 pF was 56 pF. The 47 pF capacitor was removed and replaced with the 56 pF one. I tried holding a 5 pF capacitor in parallel with the 56 pF and the measured voltage decreased. I had experimentally determined that to resonate L1 at 7.039 MHz I needed between 47 and 56 pF for the CV value. This range should be close enough to resonate the tank at 7.0 MHz as well.



Figure 14

I then chose a varactor diode. The MV209 would be perfect for my project based upon the Figure 14 chart. I anticipated that I might have to place a small trimmer capacitor in parallel with the varactor to resonate the tank at the my lowest design frequency which was 7.0 MHz. As it turned out, in addition to the varactor capacitance, the voltage control circuit added additional capacitance and I actually needed 0.30 volts (measured between the 10K pot and the 220K resistor) to resonate the whip at 7.039 MHz. This was perfect; I did not need a trimmer capacitor! At 0 volts to the varactor diode, my whip resonated ~ 6.90 MHz.

---

5 MHz WWV Cascode Bipolar Amplifier



Figure 15

I wanted to build a non-FET version as shown in Figure 15. The tuned whip tank was originally resonated with a 5 - 40 pF trimmer capacitor. I unsoldered this trimmer capacitor and measured it with a meter; it was 27 pF. A 27 pF fixed value capacitor was soldered in and tested. The circuit was resonant at 4.98 MHz. This was close enough for me and also the 3 high Q fixed value capacitors provided a very narrow 6 dB bandwidth along with the inductor. The output impedance value of the tuned whip is around 200 ohms to match the Q1 bipolar amp input impedance.

Listening tests indicated that this circuit probably had too much gain at 5 MHz. It might be favorable to lower the Q1 emitter current to 7 mA or so by raising the Q1 emitter resistor or decreasing the Q1 bias voltage. Also, a series feedback, degenerative resistor on the Q1 emitter might be considered. This active antenna was comparable to the outdoor reference aerial for signal strength, however, predictably was much noisier.

Final Comments

I found that using lower Q trimmer and fixed value capacitors undesirably increased the tuned whip bandwidth presumably by lowering the resonant circuit Q. The inductor unloaded Q was the dominant factor however. The worst case scenario was a tuned whip built with junk-quality parts which had a -6 dB bandwidth of ~390 KHz.

I also learned that you should expect high gain amplifiers to oscillate and specifically design to reduce or suppress this tendency.

The 2005 Active Antenna experiments were fun and provided many learning opportunities. An active antenna is a perfect weekend project. There is no substitute to learning by building and testing electronic circuits with your own hands.

My sincere thanks to all of the friends who helped me with these experiments.

Experiments by Other Builders

What follows are some VPA experiments by others that were sent to me by email. I seek your feedback and photographs to help improve this web site and also to gain motivation to add more new content.

Joe, K9LY
Hi, Todd :

Attached are some photos of a voltage probe amplifier that I built using ideas from your excellent website. I use a TenTec 1254 receiver in the car and listen to some shortwave broadcasts during the daily commute to and from work. The antenna is a 4-foot whip that screws into the trunk-lip mount shown. The amplifier is held to the bottom of the trunk lid by a magnet and has survived for several weeks without falling off.

The amplifier is tuned by a varicap diode and covers approx. 9-14 MHz. The tuning voltage comes from a potentiometer that I added to the front panel of the receiver.

I decided to use the 2N3904 cascode amplifier because I liked the idea of using the most common transistor possible. The LC-tuned input is nice because the antenna whip is held at chassis ground potential, which should help prevent damage to the amp caused by static buildup.

The TenTec 1254 Receiver. http://radio.tentec.com/kits/Receiver





Above left: Inside Joe's trunk lid SWL Active antenna. Great ugly construction in a sturdy Hammond chassis.
Above right: Joe's remotely tuned SWL active (or voltage probe) antenna amp and whip holder. Thanks Joe!

Amateur and Short Wave Radio Electronics Experimenter's Web Site

Fun with LEDs

Introduction

This summer I built several LED projects including sequential LED chasers (sequentially left to right) and also "Nite-Rider" style which go (sequentially left-right-left-right-etc). Many more LED schematics can be found on the World Wide Web via a Google search. LED projects are great fun for both HAM's and SWL's alike. They are also a lot of fun for children to experiment with. Currently, I am experimenting with PIC microcontrollers to perform LED "tricks".

I also built several very bright LED flashlights which run on a single 1.5 volt battery. For ultra-bright LED flashlight schematics, check out Dick Cappel's excellent and very informative web site. He has a number of LED driver circuits and other great schematics and theory. To wind the inductor for these LED flashlights, I had good success using an FT-37-43 ferrite torroid core. I used at least 40 turns of wire which is generally center tapped.

LED Chasers



Above. This is the schematic for a ***very*** basic 10 LED chaser I built. I prefer my "chasers" to run slower than most and chose a 10 uF capacitor for C1. The 10K pot can reduce the flash speed from not moving to whatever minimum time constant is possible with the C1 value you choose. Don't bother with ultra-bright LEDs for these "chaser" projects as cheaper, lower millicandela (mcd) LEDS work fine. I favor blue and green LEDS. The 4017 decade counter is a fabulous part and can be driven to flash a row of LEDs with a 555 timer chip or a discrete BJT multivibrator.

Update Feb 25, 2011: Many "experts" have emailed, or flamed me on web forums to say this circuit can't possibly work. I really hope these unhappy men cultivate enough humility to study and understand the 555 and more importantly; to reap some of the happiness and joy that comes from being positive and helpful to others. Since 2005, greater than 300 builders have emailed to say this simple circuit works and they want to learn more about electronics.

My intent was to have the least number of parts to flash some LEDs. Some new builders become overwhelmed when the parts count is high — I once shared this fear and relate. You'll see a number of different bias circuits for the 555. Many builders run the reset pin; **Pin 4** high (connected to the 9 volt battery) and as a rule, this is a good thing to do, but it's not necessary for the circuit to work. Pin 7 is an open collector output to ground — its primary purpose is to discharge the capacitor.

It's important for the DC voltage in the pot wiper to not become too close to the + 9 volt rail or VCC (This happens when when the pot is rotated so that maximal DC voltage appears on pin 7), as pin 7 would draw excessive current. In my original schematic I left out a series resistor from VCC to the pot to eliminate this problem. After some thought, I added a 1K resistor on Feb 25, 2011, although this limits the rate somewhat. I run the pot on my circuit about mid-range and it hasn't been re-adjusted (or turned off) since 2005.

Also, the rotated pot wiper shouldn't get within a couple of hundred ohms of the capacitor as that too would cause excessive current spikes into pin 7. Generally, I prefer not to have much current on the wiper of a pot or, at least, try to keep the current small. Often, you can use a pot to set the desired timer speed and then remove, measure and substitute 2 standard value fixed resistors. A better way is to use math and calculate the resistor values, but this involves math and some people want nothing to do with equations.

This circuit is meant to provide a minimalist working circuit, but doesn't provide a great example of 555 design. Happily, for those wanting to learn more, countless great 555 tutorials may be found on the web. One of my 555 favorite sites is that managed by fellow Canadian Rob Paisley. Increasingly, I am exchanging electronics-related emails with model railroad enthusiasts across the globe and many of them know of Rob's wonderful web site.

Matthew Ritchie built and posted a nice version of the LED Chaser on YouTube. A reader sent in this breadboard photo.

By far, the coolest device incorporating the LED chaser lies within a sculpture called Cyanic by Seattle-area artist Allet. Click for his web site. Cyanic may be found on the New Sculpture Build section on his web site. You have to start the Quick Time video manually with a mouse click. I love Allett's work and his lastest light sculpture exemplifies how the Internet can unite creative people with a positive attitude.

A 10 LED sequential flasher in a blue Hammond chassis. The schematic is shown above.



An RC oscillator designed for a 3 volt LED chaser. It oscillates quite slowly so the LED chaser it triggers will not be overly distracting. Some RC oscillator design details are discussed later. This oscillator triggered a 4017 decade counter instead of the 555 timer chip shown in the "Simple 10 LED Chaser" schematic. There are many links describing the theory of the 2 transistor astable multivibrator on the World Wide Web. I also have some information on this web page.



Above . This is a tiny 3 volt chaser which uses an LED bar instead of discrete LEDs. It draws 3.8 mA peak current on pulses. It uses the optimized BJT astable multivibrator shown directly above which fires at ~120 cycles per minute (slowly). The 3 volt battery pack is hidden behind it and should last several months. Soldering the LED bar was not an easy task. The plastic Hammond case measures 2.46 by 1.38 inches (6.25 by 3.5 cm).

A schematic to allow the 4017 decade counter to sequentially flash 6 LEDS left-right-left-right-etc. Connect your favorite square wave oscillator to pin 14. I built 4 of these using various oscillators and LED colors. You might consider using lower DC voltages and if so, may adjust the 1K current limiting resistor by using ohm's law. The 10 small signal diodes may be any appropriate type including the 1N914 or 1N4148. None of my 4 projects exceeded 6 mA peak current draw, so battery life is excellent. I increased the 1K resistor to 1K5 in my 4th project as I found the LED's that I used too bright.


"Nite-Rider" 6 LED FLASHER USING 4017 IC
1K
3
2
11
4
9
7
6
10
5
1
CD4017B
13
15
8
14
16
To Oscillator
9 VDC
drawn on 11.09.05 VE7BPO

The prototype "nite-rider" project with messy wiring. The holes for the LEDs were bored with a hand drill and it shows! The discrete transistor multivibrator can be seen behind the 4017 IC.

One of the four "nite-rider"

project chassis I built. After completion, this one was given to the son of VE7KPB. When drilling in a plastic chassis, I learned it is best to use a drill press set to a lower speed.

Sequentially Off LED Pulser

This circuit uses a series of transistors with an RC pair to pulse a string of LEDs.

This the favorite LED experiment I performed this summer. This flasher circuit is different in that it turns **off** alternate LEDs for about 1 second in sequence. When you connect this circuit to the 9 volt battery, all of the transistors are usually placed in saturation and therefore all the LEDs are **on**. Closing the switch on the base terminal of Q1 for a moment initiates the correct pulse sequence. The pulse initiates in Q1 which turns off the LED connected to the Q1 collector for about 1


Sequentially Off LED Flasher
9 VDC
100K
1K5
100K
1K5
100K
1K5
+
22 uF
+
22 uF
+
22 uF
Q1
Q2
Q3
Close to start
Q1 = Q2 = Q3 = 2N3904 etc.
24.09.05 VE7BPO

second. When Q1 turns back on (goes into saturation), Q2 turns off. When Q2 turns back on then Q3 turns off and so on. The circuit is a closed loop and many more stages may be added.

You can experiment with different base resistor and coupling capacitor values to vary the speed of the LED string or to create a sense of randomness by varying each transistor's RC stage separately. This is a fun circuit!

Youtube link (not mine).

The prototype 3 transistor version. I just used a piece of wire to ground the Q1 base terminal and establish the correct pulse sequence after powering it up. For the LEDs, transistors, resistors and capacitors you can use whatever appropriate parts that you happen to have on hand. Current draw is less than 10 mA with a fresh 9 volt battery. Decrease the 1K5 current limiting resistor to 1K or so if you want brighter LEDs at the expense of more current draw. Do not operate this circuit above 9 volts unless you connect diodes from the transistor emitters to ground to prevent emitter-base breakdown.





LED 1 and 2 are on and LED 3 is off at this moment in time.

Above and below photographs. This low current version has 9 LEDs connected in a chain and is powered by 3 volts. The 10th LED (extreme right hand side) is a flashing LED which is directly connected to the 3 volt supply and also uses a 1K current limiting resistor. Total peak current draw is only ~ 7 mA, yet it is still bright enough to see at night-time. The power supply is 2 D-cell batteries connected in series and then to the circuit by soldering wires directly onto the batteries with a 100 watt soldering iron.



NoNot counting the 10th flashing LED, 5 of the 9 LEDs are on at any given moment. A sequential flash effect is noted (the state of each LED flip-flops and shifts over 1 position each flash). If you build this project with an even number of LEDs, the sequential effect is not seen. Half of the LEDS (spaced every other LED) are on and the other half are off at any moment. The same LEDs are lit or unlit each pulse. Thus the effect is more like a typical multivibrator LED flasher. This variable, even versus odd number of stages property makes the circuit quite versatile.



Conclusion

I hope that you have some fun experimenting with these and other circuits.

Amateur Radio Electronics Designer's Web Site

SWL Receiving Antenna Experiments

Introduction



I have a lot to learn about SWL antennas. What follows are some brief experiments I performed in late October 2005. I have been experimenting with a half wavelength end-fed wire for use as a portable 40M band HAM transceiver (receive and transmit) antenna. This wire antenna is 67 feet long. End fed wires are very popular with those who pack a small portable transceiver when backpacking and camping. No feed line is required and the far end of the wire can be strung up using objects such as nearby trees or collapsible, portable poles. An elaborate ground system is not required. The return for the RF energy to ground might be grounding rod(s), short or long radial(s), or even just capacitively coupling to the local environment (including the operator!). Simple tuners are easily built to transform the high (thousands of ohms) wire impedance to the 50 ohms or so required by the transmitter.

I wanted to know if I could use this antenna as a tunable receive antenna for the the 30 and 31 Meter bands in addition to a tunable transmit/receiver antenna for my HAM radio work on 40 Meters. **What I verified is that tuning a multiband receive only antenna is not very practical.** When you tune a receive antenna you increase received noise and desired signals proportionally and therefore do not improve the signal to noise ratio in a meaningful way. Sometimes until you perform some experimentation, you don't really believe even good advice.

To the right: A computer simulation of a 40 Meter band end-fed Wire performed by W7ZOI on W7EL's EZnec program. The simulation was for 10.1 and 7.0 MHz with a 22 and 12 gauge wire. One 33 ft radial was used from the base of the 23.7 ft piece up 0.3 feet from the ground in this simulation. Z is impedance. Z and j are complex numbers used to represent the multi-dimensional quantities of the AC analysis of this antenna. In actual fact, j is an imaginary number. I suggest you might just ignore j unless your are well informed about impedance arithmetic.

Antenna Matching

A tuner can help match the impedance of the wire antenna and feed line (if used) to the input impedance of the receiver at a given frequency. This will result in more received signal and noise voltage to the receiver's input. HAM radio enthusiasts use antenna tuners to transform the impedance between the radio and the antenna tuner to 50 ohms to allow maximal output power from their transmitter. Non- amateur radio operators, can not use transmitters to


Simulated with EZnec 4.0 from W7EL
44 ft
23.7 ft
#12 or #22 Wire Used
33 ft
0.3 ft
1 ft
Ground
End Fed Half Wave Antenna for Portable Use w7zoi, 24 Oct 05
Z(7)=5204 + j 35 with #12 wire
Z(7)=6374 + j 1239 with #22 wire
Z(10.1)=148.3 + j 168 with #12 wire
Z(10.1)=146 + j 186.6 with #22 wire

match their antennas. This leaves either using receiver noise, S-Meter or an antenna analyzer such as the MFJ259. I just used my ears and S-meter. All of the tuners presented work as transmitter tuners as well. Any network used for transmitter work must be able to handle the output power of the transmitter final amplifier.

The Wire Antenna Experiments

I tried 3 different antenna tuners to see if I could tune an 18 gauge wire on 40-41 and 30-31 meters. My wire went from my computer room in the basement out a hole in the wall and sloped at ~ 50 degrees up to a rope tied to a tree in my backyard. The tip of the antenna is about 50 feet (15 meters) high. A 10 gauge insulated ground wire also passes from the computer room outside under the back lawn. It is "earthed" to two, 2 meter copper grounding rods hammered into the ground. No direct connection to the house ground system and the outside antenna grounding system should be made as this may result in increased receiver noise.

Antenna Tuner 1

The schematic on the left below, is very popular with HAMS who use it to to tune monoband end-fed wires. It is very simple and works reasonably well. Although the capacitor was able to resonate the 35 turns inductor, the T1 turns ratio was wrong and reducing it to 28:3 was required to get the maximum receiver signal in my experiments on the 40 and 41 meter bands. The alternative was to shorten or lengthen the wire antenna which is not very practical as it meant repeatedly climbing a tree.


Antenna Tuner 1
21.10.05 VE7BPO
T1
67 foot wire
50 ohms
10-150 pF
T1 = 4 uH = 28t primary on a T68-7 torroid with a 3 turn link


Improved Antenna Tuner 1
100
High Z Load
365
This is much better, for it will allow a perfect match.
22.10.05 W7ZOI

Above right: An improved version of the Antenna Tuner 1 schematic from W7ZOI. This tuner has 2 user "tweaking" adjustments much like most modern commercial antenna tuners (which typically also have a band changing adjustment).
I did not build this version.

In addition, this tuner would not tune the 67 foot wire on the 30 or 31 meters band. This was no surprise. When I turned the variable capacitor, I noticed some change in received signal, but not much. The signal strength was very poor and I could not hear much of anything.

Below. Two built up views of the Antenna Tuner 1 schematic. I soldered the antenna wire to the circuit in the isolated area connecting the inductor and capacitor. The outside antenna ground wire was soldered to the large copper ground plane.





Antenna Tuner 2

This was the next tuner I built. Antenna tuner 2 tuned very sharply on the 40 and 41 Meter bands. It is designed to match a high impedance antenna, so it could not match the medium impedance (~150 ohms) wire to the 30 and 31 meter bands very well at all. Since ~ 150 ohms is fairly close to my receivers 50 ohm input impedance, I just connected the wire antenna directly to my receiver. The received noise and signals were then much stronger than those with the Antenna Tuner 2 network in the circuit on 30-31 meters.







Above: Two constructed views of the Antenna Tuner 2 schematic. The variable capacitors were bought at a HAM festival in 1992 for 2 dollars each.

Antenna Tuner 3

The next antenna tuner topology I tried was the familiar L network. Circuit **A** is configured in a shunt L (inductor to ground) and series C (capacitor) and is a high pass L network. Circuit **B** is configured in a series L and shunt C and is a low pass L network.


Antenna Tuner 3
A
67 foot wire
C1
L1
50 ohms
B
67 foot wire
L1
C1
50 ohms
23.10.05 VE7BPO


DS5CKP photo

L networks (especially the low pass form) are very popular as random wire tuners. MFJ sells an excellent version as the model MFJ-16010. A photograph of this tuner is shown below right. The above left photograph was taken by **DS5CKP** who also sells a random wire antenna tuner at: http://user.chollian.net/~cyberline/ckptuner.htm


Transmitter
Toroid Coil
Antenna
L
Max. L
10-324 pf
C
MFJ-16010 Circuit Diagram

INDUCTANCE
CAPACITANCE
MFJ ANTENNA TUNER
Model MFJ-16010

Above. MFJ web publishes their manual including the schematic for the MFJ-16010 random wire antenna tuner. The inductor is actually wound on 3 stacked (probably ferrite) cores which are tapped. The taps are connected to a front panel mounted 12 position switch. This allows coverage from 2-30 MHz. As a simple experiment, I tried stacking 2 and then 3 FT-50-61 ferrite cores and was able to get a wind range of inductances from the 6 taps I made on my test inductor.

Numerous examples of the L network antenna tuner can be found on the web and in print including the 2006 A.R.R.L. handbook. I decided to try the high pass L network topology to experiment with.

I built part **A** of the Antenna Tuner 3 schematic with shunt L and series C. On the 40-41 meter bands I tried 3 different inductors; 4 uH, 2.1 uH and 1.3 uH. I tuned the network to get the greatest receive noise and S meter reading and measured the variable capacitor value. At 7.30 MHz, the capacitance values were 86 pF, 141 pF and 182 pF respectively. Although non-critical, I settled on a 2.6 uH inductor (23 turns on a T50-2 powdered iron torroid) so I could use a junk-box 10-150 pF variable capacitor to resonate it. Later I decided just a trimmer capacitor might do. You need around 125 pF at 7.30 MHz to tune the network with a 2.6 uH inductor (to give you a ballpark C value to start with).




30-31 and 40-41 Meter Receive Antenna Tuner
C1
100 pF
L1
67 foot wire
40-41 M
Bypass
50 ohms
Bottom DPDT
C1 = 10-70 pF trimmer
L1 = 2.6 uH = 23 t T50-2
05.11.05 VE7BPO

Schematic to the right: A very small receiver tuner that allowed the L network to be switched in and out of the antenna path was constructed. The L network is tuned on 40-41 meters via a small trimmer cap on top of the double pole, double throw switch. A small plastic alignment screw driver is used for signal peaking. An air variable capacitor would be much easier to tune as you move up and down these bands.

Below left: Front view. Technically, the switch label should indicate **40M** and **bypass** as the bypassed antenna could be used on any band.

Below right: Rear view The trimmer cap can be seen on top of the switch.





Below left: Side view, the antenna wire is held via an alligator clip. This allows me to unclip and ground the antenna when it is not in use. The antenna ground wire is soldered to the copper ground plane.

Below right: A T6-8 core wound with with 24 gauge wire. I used larger powered iron torroids to wind my inductors, however, they can also be wound on ferrite cores or be air-wound. The core size, wire gauge and type of inductor used can affect the selectivity and insertion loss of the tuner network, however for practical receiving purposes it is not a major concern.



Conclusion

The final experiment allow me to easily switch between a matched and direct 67 foot wire antenna on 40 and 41 meters. I performed several listening tests and generally agree with those who say receive antenna tuners offer little to no improvement in signal readability. The only advantages I can think of for matching a receive antenna to a reasonably quiet and sensitive receiver are:

1. There may be some improvement in the receiver front end filter function as these filters are designed to have a specific input impedance.
2. Certain balanced mixers may function better with the correct impedance on their RF port.
3. The tuner itself (depending on design) may marginally improve the front end selectivity of the receiver it is connected to.

I do like the noise roar and louder signals with the matched antenna on 40 and 41 meters, although this is totally subjective. I think the reason for this is that as a HAM radio operator who always matches the antenna for any band I am on, I am used to louder signals and noise levels. I also spent most of my first 10 years of HAM radio operation on 80 and 160 meters which are relatively noisy bands and have been conditioned so that noise is "normal".

On 30-31 meters the bypassed antenna worked quite well and the L network can be switched in as an attenuator. Perhaps you might build up a tuner and try for yourself!

Although they are simple, low cost and easy to put up, it is likely unwise to use an end-fed wire without coaxial feed line as a receiving antenna. The ground wire is part of the antenna system and easily picks up household generated noise which will present to your receivers input. The time honored and easiest methods to reduce receiver noise are to get your antenna away from the house and other noise sources, use buried coaxial cable feed line to the house and directly earth ground the shield of the feed line with stakes. Antenna/ feed line "link coupling" by a transformer may also reduce noise (especially if the antenna system is balanced) and this topic begs further study.

Suggested Links

There are some fabulous web sites on the topic of SWL antennas and reducing receiver noise. I suggest these 5. Try a Google search for more.

http://www.dxing.info/equipment/

http://www.hard-core-dx.com/nordicdx/antenna/feed/feed1.html

http://www.aa5tb.com/efha.html

http://www.nyx.net/~dgrunber/

As usual, I learned a great deal from the process of experimenting. I look forward to spring when some more antenna experiments can be performed.

QRP SWL HOMEBUILDER

Amateur and Short Wave Radio Electronics Experimenter's Web Site

Experiments with JFET Biasing

The most common way of biasing a Junction Field Effect Transistor (JFET) is with a source resistor. This method, shown in Fig 1 below, has the advantage of offering negative feedback to stabilize the bias conditions. This is the same thing that happens when a bipolar transistor uses an emitter resistor. Self bias can be used as a method to evaluate a JFET to determine the critical parameters that describe it: Idss and Vp. These are discussed in Chapter 2 of **Experimental Methods in RF Design** and many other places.



Figure 1

The method used in our experiment is to set up the FET of interest in a test fixture with a power supply, bypass capacitor, resistors in the drain and gate to suppress parasitic oscillations, and a handful of extra resistors, R-test, that can be paralleled with an existing 100K source resistor. A digital volt meter (DVM) is the basis for the measurements. We begin by using the DVM to measure the resistance of our test resistors, for the values will be used in calculations. The DVM is then attached to the FET source to measure the DC voltage. The first value we measure is with no attached R-test. The measured value will be very close to the FET pinchoff voltage.

The measurements we will perform infer drain current as a function of gate to source voltage. The physics of the FET support the model that there is no gate current so long as the gate is not forward biased with regard to the source. Hence, the drain current equals that in the source. We will measure the source current by measuring the voltage drop across the source resistor. The gate is at ground potential, for there is no gate current, so the gate to source voltage is just the negative of the source to ground voltage.

The resistors that I pulled from my stock for some measurements were marked as 22, 39, 68, 100, 150, 300, 510, 680, 1K, 2K, 3.3K, 6.8K, and 10K Ohm. The measured values are shown in attached figures. A systematic pattern was noticed with all of the measured resistances under the marked value, suggesting an error in the calibration of my DVM, a Fluke Model 73. All resistors were 2% carbon film 0.25 Watt. However, when I measured a 499 Ohm, 1% metal film resistor, it came up exactly at 500 Ohms. The differences between the measured values and those marked on the part were small enough that I neglected the details and used measured values for calculations.

The first FET I examined was a 2N5454, a common JFET that I had in my junk box. The source voltage was 3.26 with nothing but the 100K for source bias. I started my measurements with the largest resistor, 10K. The voltage dropped to 2.90 and was stable. I merely held the resistor in place rather than soldering it. The resistor was kept in place long enough to get a stable reading that I could record in my lab notebook. All results were of the same character until I got to the 300 Ohm resistor. At that point I started to notice a slight heating effect. The source voltage was 1.523, but slowly dropped to 1.518 volts. This behavior continued through the lower value resistors. The 22 Ohms produced 264 mV on the source that then dropped to 256 mV.

Later I examined a J310 JFET. This is a much larger area part than the 2N5454 with an Idss that is about three times larger. With the 22 Ohms in the test fixture, V-source went to 701 mV, but settled at 652 mV. The drain current was then 32 mA. With a 10 volt power supply, there was nearly 200 mW dissipated in the FET. This is within ratings, but high enough to produce heating. Operation at higher voltages and at Idss would further tax the part. One must take care when doing these measurements to be sure that the source voltage is observed quickly.

Attached are the MathCad documents that I used to examine the data. A spread sheet such as Excel could be used, but I prefer the graphics of MathCad. The second page for the 2N5454 shows a graph for the observed data as well as a calculated one. The two FET parameters for the 2N5454 were varied to obtain a good correspondence between the two. The part had Idss=15 mA with Vp=-3.5 volts. This is similar to the popular MPF-102, but close to the high Idss extreme for that part.

The data presented for the J310 is more abbreviated with only two points shown. I picked the 22 Ohm and 1K source resistors. This still produced data that is very close to that obtained with many more data points.

My initial analysis suggested that we could characterize the FET by measuring the source voltage with 100K in place to approximately determine Vp, and to then short circuit the source through the mA scale on the DVM to obtain Idss. This is a reasonable start. However, the pinchoff will usually be a few percent more negative (for an N-channel depletion mode part). The long leads in the source also make me feel uncomfortable with regard to parasitic oscillations.

After the DC measurements were done, I thought it wise to look at the potential for oscillation. The J310 was in the test circuit at this time. The TO-92 J310s are parts that are well known for their propensity for oscillation, so I guessed that it would not be difficult to coax this one into such a mode. But this was not what I found. I eliminated the 100 Ohm drain resistor, but moved the FET close to the 0.1 uF bypass. This bypass is not a very good one for VHF and upward. No oscillation was seen. I then eliminated the gate resistor, replacing it with the normal gate lead. Still no oscillation. I eventually added a gate inductor and a parallel tuned circuit in the source. The source bias resistor had a RF choke in series with it. I finally saw a robust VHF oscillation, but nothing else up through 1.5 GHz.

Experiments with JFET Biasing, after correspondence with VE7BPO on 14Feb06. (See earlier Mathcad file "Jfet_bias1_ve7bpo.mcd) Measurements on 2N5454.

$n := 0..12$ **index for measurements and calculations. Vsn=measured source voltages.**

$$Rx_n := \begin{pmatrix} 21.6 \\ 38.6 \\ 66.9 \\ 98.3 \\ 149.4 \\ 298.3 \\ 508 \\ 671 \\ 998 \\ 1997 \\ 3270 \\ 6720 \\ 9810 \end{pmatrix}$$

<== Measured Rx value

R values paralleled with 100K ======>

$$Rp_n := \frac{1}{\left(\frac{1}{Rx_n} + \frac{1}{100400}\right)}$$

$Rp_n =$

	0
0	21.595
1	38.585
2	66.855
3	98.204
4	149.178
5	297.416
6	505.443
7	666.545
8	988.177
9	$1.958 \cdot 10^3$
10	$3.167 \cdot 10^3$
11	$6.298 \cdot 10^3$
12	$8.937 \cdot 10^3$

$$Vs_n := \begin{pmatrix} 0.264 \\ 0.429 \\ 0.654 \\ 0.85 \\ 1.09 \\ 1.523 \\ 1.845 \\ 2.001 \\ 2.203 \\ 2.492 \\ 2.652 \\ 2.82 \\ 2.90 \end{pmatrix}$$

$Vg_n := 0 - Vs_n$

$Vg_n =$

	0
0	-0.264
1	-0.429
2	-0.654
3	-0.85
4	-1.09
5	-1.523
6	-1.845
7	-2.001
8	-2.203
9	-2.492
10	-2.652
11	-2.82
12	-2.9

Use Mathcad "vectorize" operator.

$$Id_n := \overrightarrow{\frac{Vs_n}{Rp_n}} 1000$$

$Id_n =$

	0
0	12.225
1	11.118
2	9.782
3	8.655
4	7.307
5	5.121
6	3.65
7	3.002
8	2.229
9	1.273
10	0.837
11	0.448
12	0.325

Let pinchoff be $u_p := -3.5$ **and** $I_{dss} := 15$

$$u := -3, -2.9 .. 0$$

$$I(u) := I_{dss} \cdot \left(1 - \frac{u}{u_p}\right)^2$$

Try various values for pinchoff and Idss to get a reasonable match.

Blue is measured data while red shows calculated behavior.



Experimental Note: During the measurements, I noticed a definite thermal change in Idss when dissipation was high. This occurred at higher currents, with low source bias resistors. The Vg values I used in my data were the first ones recorded with the DVM. The most extreme case was with the 22 Ohm source R. The source V started at 264 mV and went down to 256 mV. The effect was more dramatic with a larger part, a J310. That part, when operated with a 22 Ohm R, started with 701 mV and dropped to 652 mV.



Experiments with JFET Biasing, after correspondence with VE7BPO on 14Feb06. (See earlier Mathcad file "Jfet bias 18feb06.mcd) Measurements on J310.

Here we examine a minimal data set of just two points.

$n := 0..1$ **index for measurements and calculations.**

$Rx_n := \begin{pmatrix} 21.6 \\ 998 \end{pmatrix}$ **<== Measured Rx values.**

$$Rp_n := \frac{1}{\left(\frac{1}{Rx_n} + \frac{1}{100400}\right)}$$

Vsn=measured source voltages.

R values paralleled with 100K ======> $Rp_n = \begin{pmatrix} 21.595 \\ 988.177 \end{pmatrix}$

$Vs_n := \begin{pmatrix} 0.701 \\ 2.97 \end{pmatrix}$ $Vg_n := 0 - Vs_n$

$Vg_n = \begin{pmatrix} -0.701 \\ -2.97 \end{pmatrix}$

Use Mathcad "vectorize" operator.

$$Id_n := \overrightarrow{\frac{Vs_n}{Rp_n}\,1000}$$

$Id_n = \begin{pmatrix} 32.461 \\ 3.006 \end{pmatrix}$

Let pinchoff be $u_p := -4$ and $I_{dss} := 48$

$u := -4, -3.9..0$

$$I(u) := I_{dss} \cdot \left(1 - \frac{u}{u_p}\right)^2$$

Try various values for pinchoff and Idss to get a reasonable match.

Blue is data while red shows calculated behavior.

18 Feb, 2006 by W7ZOI

Many thanks to Wes, W7ZOI for this contribution.

10 MHz WWV Receiver Experiments

New feature: Click on a schematic to load it into a separate browser page for printing

Introduction

For nearly a year, I have been trying to develop a tuned radio frequency (TRF) 10 MHz, WWV, AM receiver. My initial RF stages were common emitter or common source stages with tuned input and output. Despite careful layout, parasitic oscillations plagued these designs and they were discarded. Later, I discovered that only tuning the input of RF stages reduced this tendency towards instability and still provided reasonable selectivity. Different detectors were also tried and evaluated.

A simple receiver that sounds great and is fun to build and experiment with follows. My special thanks to Wes, W7ZOI for performing many of the simulations and providing suggestions which kept me going.

WWV Audio Files from Sept 26, 2006

WWV File 1

WWV File 2

WWV File 3

The audio was digitally recorded using an electret condenser microphone held 3 cm away from the receiver speaker. The files were compressed using the WMA format.

Supplemental Web Page added June 29, 2007

Receiver Front End


WWV Receiver Front End

Q1 = Q2 = dual gate MOSFET 40673 or ECG 222
L1 = 4.1 uH = 27 turns T-68-2 using 22 AWG wire.
Tap 2 turns from ground
CV1 = 10 - 40 pF trimmer cap
L2 = L4 = 12 turns on a FT37-43 Ferrite core
L3 = 3.0 uH = 25 turns # 26 AWG on a T50-2 core
CV2 = 10 - 70 pF trimmer capacitor

Oct 1, 2006 VE7BPO

Above schematic. The receiver front end has just 1 single-pole filter. For even greater selectivity (but greater insertion loss), consider moving the L1 tap to 1 turn from ground. My receiver was connected to a 80 meter dipole via an antenna tuner. The antenna tuner provided additional selectivity. No local broadcast band (BCB) signals were heard when the chassis lid was tightened on. You may require additional RF high pass or band pass filtering in your location.

The RF gain control is very basic and only the first 1/3 of the 10K pot is used to go from minimal to maximal gain. Modifications to allow more precise variation in RF gain for dual gate MOSFETs or cascode JFETS are shown in EMRFD. The method shown works fine. For the most part, I keep it set to minimal gain. Using higher gain than necessary, increases receiver noise and may overdrive the detector.

TRF receivers require careful layout. A piece of wire greater than 2-3 cm between the stages may be enough to plague your receiver with local BCB interference depending on your layout and chassis integrity. For interstage connections that had greater than a 2 cm gap, shielded 50 ohm cable was used to prevent BCB interference.

Dual gate MOSFETs provide adequate gain and low noise. you might consider cascoding 2 JFETS for each RF stage if you cannot obtain them. titleernatively, bipolar feedback amplifiers may be used and examples are provided later on this web page.

XTal Filter and RF Amplifier


XTAL FILTER AND RF AMPLIFIER
12 volts
100
.1
100K
47K
4K7
L1
To Detector
- 3 dB Bandwidth 6 KHz
Y1 Y2 Y3
C1
C4
.001
G2
D
G1
Q1
S
2000 ohms
2K
100
.1
C2 C3
VE7BPO
Sept 2006

C1 = C2 = C3 = C4 = 20 pF
Y1 = Y2 = Y3 = 10.0 MHz
Q1 = dual gate MOSFET 40673 etc.
L1 = 12 t FT 37-43 Ferrite toroid

Schematic: The Q2 output impedance is 2000 ohms to match the input impedance of the Cohn crystal filter. This filter was designed by Wes, W7ZOI. Matched, computer grade, 10 MHz crystals were used. Choose 10 MHz crystals that are marked for a 20 pF or 32 pF load capacitance if possible. Using a 10 MHz crystal oscillator, find 3 that are closest to one another in frequency.

You may substitute 2K2 resistors instead of the specified 2K with a slight penalty in pass band shape.


GPLA
File
About GPLA
GPLA - 2002
S21 =
S11 =
S21 Ref.
Click to Review Circuit
dB
Plot
Enter new value and Click
Frequency
Place Cursor
Drag a box on graph to Zoom
Zoom to Original Sweep
Save S21 as Ref.
Value Tune Mode
Up
Down
Reset Cursor

```
0  Load R = 2000.0
1  xtl  ser  0.00
2  cap  ser  19.60
3  cap  par  19.62
4  xtl  ser  0.00
5  cap  par  19.62
6  xtl  ser  0.00
7  cap  ser  19.60
8  rlb  ser  0.00
98  Source R = 2000.0
99  Inductor Q = 100.0

Crystal Parameters:
100.  Freq.= 10.0000
101.  Lm = 0.0200
```

top: 0.

10.00 dB/div.

bottom: -60.0

N (index): 1

NewValue: 0

start: -10000 Hz

Freq./div: 5000

stop: 15000

C:\Documents and Settings\Owner\My Doc

Cursor Data =====>: 100 Hz

S21= -10.56 dB

S11= -0.52 dB

☑ Plot S11

☐ Plot Referenc

NR= 4

%= 5

Value=

Above graphic. A simulation of the receiver crystal filter using GPLA, a program written by Wes, W7ZOI that comes with EMRFD. EMRFD is the major reference for this web site and I recommend that you add this book and companion software to your home library. The pass band is not symmetrical. It is mistuned for the lower pass band frequencies and would serve better as an upper sideband filter. Nevertheless, it works reasonably well and is simple to build and tolerant to component variation and match. At certain times, a very strong shortwave station at 9.985 MHz can be heard along with WWV. This usually occurs in the early evening when the WWV signal is not that strong at my location. For most of the day and night, whether WWV is present or not, very little interference has been detected.

Bypassing the crystal filter is an interesting experiment. As many as 5 stations were heard simultaneously and these varied as time passed. I heard Radio Vatican, Radio Habana and many other broadcasts during 1 evening. At one point I heard a station at 9.75 MHZ, WWV and a strong CW carrier at 10 .110 MHz!


GPLA
File
About GPLA
GPLA - 2002
S21 =
S11 =
S21 Ref.
Click to Review Circuit
top
dB
Plot
dB/div.
bottom
Frequency
Freq./div
Place Cursor
Cursor Data =====>:
Drag a box on graph to Zoom
Zoom to Original Sweep
Save S21 as Ref.
Plot S11
Plot Referenc
Value Tune Mode
Up
Down
Reset Cursor
N (index)
NewValue
Enter new value and Click

0 Load R = 2000.0
1 xtl ser 0.00
2 cap ser 19.60
3 cap par 19.62
4 xtl ser 0.00
5 cap par 19.62
6 xtl ser 0.00
7 cap ser 19.60
8 rlb ser 0.00
98 Source R = 2000.0
99 Inductor Q = 100.0

Crystal Parameters:
100. Freq.= 10.0000
101. Lm = 0.0200

N (index): 1
NewValue: 0

top: 0.
10.00 dB/div.
bottom: -60.0

start: -200000 Hz
Freq./div: 20000
stop: 200000
C:\Documents and Settings\Owner\My Doc

Cursor Data =====>: 0.0 Hz
S21= -- dB
S11= -- dB

☐ Plot S11
☐ Plot Referenc

NR= 4
%= 5
Value=

Above graphic. This is a sweep that goes from 200 kHz below to 200 kHz above 10 MHz to show the stop band response of this filter. This filter has a pretty decent response considering the low cost and effort involved.



VK4FUQ AM Detector

D1 = Silicon Small Signal Schottky Diode; NTE 112, 1N5711, SK3089 etc.
Q1 = Q2 = MPF102 nJFET

Oct 1, 2006 by VE7BPO

Above schematic. This detector is fabulous. It was designed by Felix Scerri, VK4FUQ. He has a web page explaining his high fidelity detectors at the Elliot Sound Products (ESP) site: http://sound.westhost.com/articles/am-radio.htm

The ESP web site is a personal favorite. Rod Elliot has one of the best do-it-yourself electronic web sites available. The main URL for his site is http://sound.westhost.com/index2.html

My sincere thanks to Rod and Felix for permission to present Felix's detector on this web page.

His improved AM detector has 3 positive advantages; it has high bandwidth, low distortion and incredible (and variable) sensitivity. I cannot get over how nice this detector sounds compared to others I have built and analyzed during weak and strong signal testing. The variable bias control allows the listener to adjust the bias to maintain detected audio fidelity even when the RF signal is weak.

This detector uses a UHF mixer diode often found in older television sets. Increasing the diode bias from O volts towards maximum causes three things to happen:

1. Increased sensitivity.
2. Increased audio high frequency response.
3. Slight increase in receiver noise.

When the WWV RF signal is weak, turning the bias off may result in the detected WWV signal disappearing. Increasing the bias will bring WWV back in. I generally run the bias control pot about 1/2 way and of course, higher as WWV fades out. I like the fidelity that the bias adds even when the WWV signal is strong. Note how the WWV audio quality continues to be high in fidelity as WWV fades out in this sound file.

Felix called for a 1 mH radio frequency choke. The largest I had in stock was a 1000 uH choke. I had to decouple it as shown to prevent oscillations from occurring in my receiver. For the 1 uF and 2.2 uF capacitors, I used polyester film types which sounded better than electrolytic capacitors.

Oct 13, 2006: Note. The 1000 pf input cap to the detector was omitted in error in the original schematic which is now correct.

To the right: The detector board. On the left is an op amp preamp stage that was later disconnected as it was not needed. Note the copper is removed where the chassis mounting nut contacts the copper board. Both audio boards were isolated from chassis ground and star grounded to a single point. The speaker negative terminal was also directly connected to this point. There is no hum.


1.00uF±5%
250V 0030

Audio Amplifier


Audio Amplifier
12 VDC
.01
10K
10K
10K
22 uF
+
100
2200 uF
+
100 uF
+
4K7
Volume
10K
1 uF
+
3
2
1
4
5532a
.1
4K7
5
6
8
7
5532b
4K7
.1
100K
390 pF
390 pF
100K
12K
4K7
4K7
Q1
Q2
Q3
10 uF
+
22
22
1000 uF
+
1000 uF
+
330 uF
+
+
2K7
−
Q1 = Q2 = 2N3904
Q3 = 2N3906
NE5532 low noise, dual op amp
from EMRFD
by KK7B
Sept 23, 2006 VE7BPO

Above schematic. Rick, KK7B designed this low noise audio amplifier. It is from EMRFD. This superb AF amp greatly compliments the VK4FUQ detector. This is the best speaker audio amp under 1 watt I have ever used. Distortion is very low as long as it is not over-driven. I increased some capacitor values compared to the original schematic. Please refer to EMRFD for details on this stage. The chassis of this receiver greatly increases the low frequency response. On the 1 second pulses of WWV, the receiver "knocks" like a metronome. This does not occur when the chassis lid is off.

WWV web site: http://tf.nist.gov/stations/wwv.html All the often subtle pulses and tones transmitted at various times during the hour can be heard with this receiver.

To the right: A bread board of the AF amp. This is the audio amp I shall use in future projects which contain a speaker. Kudos to KK7B.

Below 3 images: Different views of the TRF receiver. On the front from left to right are the bias "sensitivity" control, volume control with integral power switch and blue LED "power on" indicator.

On the rear from left to right are the 12 VDC input jack, an unused switch (was an -10 dB attenuator at 1 point), the RF gain control and a coaxial SO239 connection.

Further Experiments

What follows are some of the ideas and circuits tried over the past year.

Schematic to the right: A 10 MHz, double tuned RF band pass filter that may be used ahead of the receiver. Insertion loss is ~ 3 dB and this filter uses a 5 pF coupling capacitor which are not too difficult to find. Filters with bandwidths of 150 - 180 KHz were also tested.


Double Tuned Filter
.34 MHz 3 dB bandwidth
50 ohms
47 pF
5 pF
47 pF
50 ohms
220 pf
100 pF
C1
L1
L2
C2
100 pF
220 pf

L1 = L2 = 1.2 uH = 17 turns T37-2 powdered Fe core
C1 = C2 = 15 - 50 pf trimmer capacitor

23 Sept 2006

To the right: A GPLA simulation of the popcorn DTC shown above. titlehough a little mistuned, it is reasonable for a filter that uses common junk box values and has low insertion loss.



L-Match AM Detector


L-Match and AM Detector
12 VDC
1M
.01
.01
100
1M
50 ohms
impedance
.01
1000 uH
.1
22 uF
+
.1
L1
D1
5K6
1.0 uF
Q1
d
g
s
CV
220 pF
27K
220 pF
1M
+
2.2 uF
To AF
stage
Q2
d
g
s
5K6
L1 = 5 uH = 32 turns T50-2 Powder Fe torroid
CV = 15 - 55 pF trimmer cap
D1 = Silicon Small Signal Schottky Diode; NTE 112, 1N5711, SK3089 etc.
Q1 = Q2 = MPF102 nJFET
Sept 2006 by VE7BPO

Above schematic. The VK4FUQ detector can also be used to follow a 50 ohm output impedance stage by using an L-match as shown. The L match tunes very sharply. I peaked the L-match with the bias at 0 volts.

The input impedance of the detector is related to the DC current flowing in the diode. This is established by the adjustable bias current or "sensitivity control". The input resistance will be 26/I, where I is the current in mA.

For example, if the current in the diode is 10 microamps (0.01 mA) the input Z is 2600 Ohms. I have found that any input Z value from 2000 to 5100 ohms worked well with this detector.

Image to the right: A photograph of the L-match connected to a - 6dB 50 ohm pad which terminated the 50 ohm feedback amplifier that drove the L-match.



Feedback amplifiers


50 ohms input/output Z Feedback Amplifiers
12 VDC
220
.1
T1
.1
.1
3K3
3K3
Q1
.1
680
220
3.9
220
.1
T2
.1
3K3
3K3
Q2
.1
680
220
3.9
- 6 dB
.1
36
150
150
Q1 = Q2 = 2N3904
T1 = T2 = 12 bifilar turns FT37-43
Sept 2006 by VE7BPO

Above schematic. Feedback amplifiers may be used as RF amplifiers for a TRF receiver. This stage followed the crystal filter in one version of my TRF receiver. Stability was excellent. This feedback amplifier was designed by Wes, W7ZOI. It has ~ 20 dB gain and draws a little over 5 mA current.



Above graphic. 2 feedback amplifiers are shown on this breadboard. The double tuned filter (DTC) shown earlier is also built on this board. In this version, the crystal filter was omitted and replaced with the DTC.


FBA
File
About FBA
Feedback Amplifier Analysis
Edit Circuit and Transistor; click "Calculate" or "Change"
Change R-feedback
+
-
Input
Source R
Z_{OUT}
Z_{IN}
R_L *
R_L
N:1 Ideal
Change R-E
+
-
Calculate

Transistor Parameters : DC Beta 100 F-t, MHz 300 Rb' 10 C col-base, pF 5

F. MHz 5

10000 pF

10 nH

1600

50

N = 2

R_L = 50

I_E = 5 mA

4

10 nH

Gain (dB)= 20.836

Z-in = 68.491 +j -16.045 Input Return Loss = 13.776 dB

Z-out = 260.120 +j -41.626 Output Return Loss = 16.012 dB

Above graphic. Using software that ships with EMRFD, W7ZOI designed the feedback amplifier used in this version of the receiver.


NPN Bias
File
About Bias
Bipolar Transistor Biasing
V_C
V_B
β =
ΔV=
+5%
-5%
Calculate

Edit Resistors, Beta, Veb, and Vcc. Then Click "Calculate."

I(base) = 0.049

12

220.00

10.3469 Volts

3300

0.01

V(col) = 10.3470V

V(base) = 1.7401 Volts

680

100

220.00

0.65

I(emitter) = 4.9552 mA

Col. Dis. = 45.4150 mW

I(supply) = 7.5142 mA

Above graphic. The feedback amplifier bias resistor values were also calculated using software written by W7ZOI and included with EMRFD.


10 MHz Crystal Bandpass RF Filter

12 volts
220
.01
220
.1
T2
.1
- 3dB BW 6 KHz
2K
47
CV
T1
26
C1
C4
3
7
220
d
Q2
.1
50 ohms
s
d
g
s
50 ohms
g
2K
100 uH RFC
.1
Q1
C2
C3
220

T1 = 3.4 uH ; secondary 26 turns T50-2, tap 7 turns from grounded end,
primary 3 turns over secondary at grounded end
T2 = 12 turns FT37 - 43
CV = 10-70 pF variable trimmer capacitor (need ~ 50 pf)
Q1 = Q2 = MPF102 nJFET or equivalent
C1 = C2 = C3 = C4 = 20 pF

Sept 30, 2006 by VE7BPO

Above schematic. This circuit has the crystal filter matched to 50 ohms input and output stages using JFETs. The JFETs also serve to provide a little more gain. Careful layout is required to reduce BCB interference for all stages in a TRF receiver.


Popcorn Crystal Filter

12 volts
100
.1
10 Mhz
6 KHz BW
477 Z in and Z out
22K
2.3 uH
.1
50 ohms
2N3904
470
22K
50 ohms
CV
3K3
33 pF
98 pF

Sept 2006 VE7BPO

Above schematic. This is the original crystal filter that I designed. The input and output impedance is 477 ohms. The input was matched to the preceding 50 ohm stage using an L-network. A emitter follower is used to match the output to the 50 ohm stage which followed. Later, the emitter follower was replaced with the source follower (with a 470 ohm gate resistor) that is shown in the schematic directly above. The source follower had greater immunity to BCB interference and provided a better termination for this filter. This popcorn filter worked well, titlehough occasionally there was another station in addition to WWV, in the pass band. This also happened with the filter used in the final version of this receiver.


GPLA
File
About GPLA
GPLA - 2002
S21 =
S11 =
S21 Ref.
Click to Review Circuit
dB
Plot
Enter new value and Click
Place Cursor
Drag a box on graph to Zoom
Zoom to Original Sweep
Save S21 as Ref.
Value Tune Mode
Up
Down
Reset Cursor

brown = with 33 pF end caps
red = with no end caps

3 cap par 33.00
4 xtl ser 0.00
5 cap par 33.00
6 xtl ser 0.00
7 cap ser 99999.00
8 rlb ser 0.00
98 Source R = 477.0
99 Inductor Q = 100.0

Crystal Parameters:
100. Freq.= 10.0000
101. Lm = 0.0200
102. Cp. 2.00
103. Qx. 100000.0

top 0.
10.00 dB/div.
bottom -60.0
N (index) 7
NewValue 99999
start -5000.00 Frequency Hz 5000.00 Freq./div stop 10000.00 C:\Documents and Settings\Owner\My Doc
Cursor Data =====>: 100 Hz S21= -3.00 dB S11= -4.01 dB
☐ Plot S11 ☑ Plot Referenc
NR= 4 %= 5 Value=

Above graphic. Here are GPLA simulations of the popcorn filter with and with out 33 pF series end capacitors which serve to tune the filter. The brown tracing illustrates that it is better to include a series 33 pF cap at each end of the "popcorn" crystal filter. I did not use this filter because the dual gate MOSFET RF amps used in the final version, have better gain driving or following the 2000 ohm filter designed by W7ZOI.

GPLA is a "must-have" program. You can "tune" filters with different or asymmetric input/output impedances.


10.0 MHz Test Oscillator
VCC
100
2N3904 x2
.1
10K
Oct 7, 2006
VE7BPO
10K
100 pF
100 pF
1K2
.1
75
2K2
100
100
50 ohms

Above schematic. This 10.0 MHz crystal oscillator has a - 10 dB, 50 ohm pad on the output and was used to match the crystals, test the RF amps and align the filters used in these experiments.



Above graphic. A breadboard of the test oscillator shown above.



Above graphic. Some of the bread boards developed during experimentation. My final receiver layout (and potentiometer positioning) is not optimal, however this is a prototype and I had no idea what the finished version would look like.


Common Base RF Amplifier Experiment
12.10
51
.1
11.87
T1
27
8K2
.1
.56
Q1
150
1.26
.1
1K
47pF
CV
L1
25
3
150
3.58 mA IE
.58
Q2
1.28
.1
27
8K2
1K
3.68 mA IE
51
.1
L2
22
2
11.87
100
DC voltages in brown

Q1 = Q2 = 2N3904
T1 = 22 turns FT-37-43 ferrite core
L1 = 25 turns # 24 AWG on T-50-2 powdered Fe core; 3 turn secondary
L2 = 22 turns FT-37-43 ferrite core; 2 turns secondary
CV = 10 - 40 pF trimmer capacitor

Dec 30, 2005 VE7BPO

Above schematic. This is one RF amp that was built for this receiver. The turns ratios on L1 is too drastic to afford much gain.



Above graphic. I have been told many times that my breadboards are very ugly looking. This breadboard of the schematic directly above, shows that occasionally, I can build a nice looking circuit!

Conclusion

The highlights of these experiments were VK4FUQ's detector and KK7B's AF amplifier.

When constructing such a receiver, *build backwards*. Install the speaker and then build and test the AF amp. Test it by touching your finger to the input and listening for noise or BCB radio. Turn the 10K pot and verify that the noise increases or decreases appropriately. Perhaps test it using an AF oscillator.

If it works, you get immediate positive feedback and motivation to continue. If it does not work, you only have 1 stage to trouble shoot.

Next, build the detector. To test it, connect a piece of wire about 25 cm long between the RFC and the anode of the diode. You should then hear local BCB radio. Slowly turn the bias potentiometer from 0 to fully on. Notice how increasing the bias may bring in 2 or more stations compared to when it was at 0. Also notice how it changes the tone and sensitivity of the detector. Try shortening the "test antenna" and observing how sensitive this detector is with the bias increased.

If all went well, you now have an AM radio!

Next add in the Q3 RF amp and again test it using a short piece of wire. Then continue on until you arrive at the antenna connection for your receiver.

Best regards, VE7BPO

Amateur and Short Wave Radio Electronics Experimenter's Web Site

MF and HF Receiving Antenna

Introduction

GRUNDIG
1600
S350

My first shortwave antenna was a simple end-fed wire which started at my bedroom window and extended out horizontally to a tree which was 25 feet away from our house. The antenna feed line was a short piece of wire that connected to the near end of the antenna and entered the house through a small hole I made in my wooden window sill. This feed line was directly connected to my receiver's high impedance antenna input. My station ground was long piece of wire that was connected to a copper pipe located in the bathroom next door. While this antenna brought in "the world" to my bedroom, it was extremely noisy. Directly connecting your antenna feed line and house ground system to your receiver are not good RFI reduction practices. This web page will explore some experiments in trying to minimize the Radio Frequency Interference (RFI) arising from my local environment.

Indoor RFI sources are usually plentiful. Electrical appliances such as washing machines, televisions, DVD players, computers and electrical wiring may all emit RFI which your antenna, or directly connected house ground system may pick up and feed to your receiver. Certain indoor devices may be really strong RFI sources and will have to be eliminated or decoupled. Outside of your house are also potential sources of RFI. These may include such things as power transformers, electric fence and garage door openers. RFI location and reduction is out of scope for this web page, however a good place to learn more is the ARRL RFI book (out-of-print: search on Amazon). To find RFI sources in your home and neighborhood, try using a battery powered AM radio. At my QTH, I located a noisy VCR inside the house my Grundig S350. We rarely use this VCR and now just leave it unplugged until we actually need to operate it. I tuned the receiver to an empty frequency and found this VCR by trial and error. **Please note this web page is concerned with feeding a shortwave listening antenna and does not describe providing protection against lightning.** For web sites which covers lightening plus RF ground please refer to this offering from W8JI or eHam.net.
Protect your home and family from lightening !!

Outdoor MF and HF Antenna

The schematic to the left summarizes the outdoor VE7BPO MF and HF receiving antenna system for summer 2007. Although modest for a big city lot, this antenna seems to pull in the DX and is relatively free of RFI. This antenna was just a case of "putting as much wire in the sky as possible" and the dimensions are indicated for interest sake only. The 27 meter long horizontal section is supported between 2 trees at a height of about 14 meters high. The weight of the



vertical element wire plus slack in the horizontal wire droop it to about 13 meters high in the center. The vertical section is soldered to the horizontal wire 6 meters from the nearest anchoring tree and runs straight down to the antenna feed point which is about 1 meter off the ground. The feed point is a piece of copper-clad PC board (with isolated sections created with a hobbyist motor tool) and is bolted to a long copper pipe which serves as the first station earth-grounding stake. A transformer (T1) configured as a UNUN **(unbalanced-to-unbalanced)** is used to interface the antenna with 50 ohm coax that runs through the house and into the radio shack. Some rudimentary experiments with the UNUN and the earth-grounding system were undertaken.

The methods I used to potentially lower unwanted RFI to my antenna system are as follows:

1. The receiver and power supply are independently connected to a single, central ground point (ground buss) in the radio shack.
2. 6-10 gauge wire is used for my ground system (not including the radials which are bare 12 gauge wire).
3. The ground wire connecting to my first earth stake to the station ground buss is just outside the shack window and is short as possible to provide a low impedance and low inductance path for MF and HF frequencies.
4. There is a second ground stake located 1 meter from the primary ground stake (I will add 2-4 more in time).
5. I have a large piece of steel buried underneath the soil tied in to my system as well as 3 bare copper radials. The radials are 3 - 7 meters in length.
6. New RG58/U coax was used as the feed line.
7. All wire splices in the grounding system are soldered and taped up. I used conductive grease (to prevent oxidation at the wire-stake interface) on any clamps connected to ground stakes. My ground stakes are ~ 2 meters long.
8. The earth grounding area soil is moist and peat-laden and is watered regularly.
9. I plan to maintain this ground system every 2 years.

4:1 UNUN

My antenna is almost an end-fed wire with both a vertical and horizontal section. I do not have the gear to measure the impedance versus frequency in the MF and HF bands. I do know that on some bands it may present an impedance of several thousand ohms and a transformer can smooth out the variation in impedance versus frequency so my receiver sees a relatively low impedance on most bands. The transformer also serves to help reduce RFI from my antenna system by eliminating unwanted common mode currents flowing on the outside of the coax braid. Grounding the antenna via the UNUN will also prevent static electricity from building up on the antenna. My first UNUN had a 4:1 impedance ratio. It is shown to the right. The antenna connects to point **A**. The ground stake connects to point **B.** Point **C** connects to the inner wire of the coax and point **D** is connected to the braid and also the grounding stake. I used 24 AWG wire and A FT114-43 ferrite core. You can clearly see there are 20 primary windings and 10 secondary windings loosely coupled. I chose the FT114-43 core because I had it on hand and the 24 gauge wire provides good mechanical support for the coil. I could have used an FT50-43 ferrite torroid as well with a smaller wire gauge. You can also use a bifilar transmission line type transformer. I was very happy with this UNUN and however it did not have as much signal strength as I expected on the 160 meter amateur band and below.



9:1 UNUN



Next I tried a 9:1 impedance ratio UNUN. This an extremely popular impedance transformation ratio for end-fed or random wire SWL antennas. I wound 30 primary and 10 secondary turns on a FT114-43 ferrite torroid. The connection points are identical to those described in the above 4:1 UNUN. Remember that the impedance transformation ratio is the square of the actual turns ratio on your transformer; thus my 3:1 turns ratio is a 9:1 impedance ratio. Electrical engineers commonly use a rule when winding broadband transformers such as these. The inductive reactance (XL) of the smaller winding must be at least 4 times the load impedance at the lowest frequency that the transformer "looks" into. So for 50 ohm coax, the XL should be at least 200 ohms at 500 KHz which is the lowest frequency I intend to receive. The formula for XL is **XL = 6.28 X F X L**. Frequency (F) is in Hertz and L is the inductance in Henries.

At 500 KHz my inductor has an XL of 189 ohms which is almost perfect. I should have used 11 turns which is an XL of 229 ohms and strictly observes the 4X rule. Therefore my UNUN ideally should have used 33:11 turns on the FT114-43 torroid. If you use a FT50-43 torroid, use the same 33:11 turns ratio; this will provide 198 ohms XL at 500 KHz. For practical purposes, my 30:10 UNUN should work fine as I rarely tune frequencies less than 1000 KHz. I found this UNUN to have strong signals all the way down to MF and decided to use a 9:1 impedance ratio for my antenna system. Many experimenters and a few commercial UNUNs recommend the 9:1 impedance ratio for multiband end-fed or random wire antennas. Eventually I will encase it in a water and UV proof enclosure.

Conclusion



My experiments while constructing a reasonable quality MF and HF receiving antenna confirmed that using a UNUN, coax and a good RF ground system can reduce common mode RFI in my receivers.
I also tried temporarily connecting my ground system to a copper water pipe located in my shack while listening to WWV at 5 MHz and immediately the noise level rose 2 S-units on my receiver.
This pipe was clearly not grounded in my house where there is a mixture of plastic and copper water pipes. Additionally, my antenna wire and feed point is away from the house in a quiet area according to listening tests using a Grundig S350.

It is relatively easy to construct a UNUN on your bench using a ferrite torroid. Many builders have emailed me to say they do not feel comfortable winding torroids. Torroids are easy to use and by winding a couple and experiencing some success, your confidence working with them will surely improve. If you live in a part of the world where you can not easily obtain a suitable ferrite core, just email me and I may send you an FT50-43. You can also choose a ferrite with a different core permeability. Some builders use number 75 material. I used the FT114-43 because I get all my torroids from W8DIZ and just use what he has in stock for my projects. If you really do not want to construct a UNUN, commercial products are available on the web on sites such as http://www.arraysolutions.com/Products/baluns.htm.

I wish you good luck with your own antenna experiments and please be safe!

Some SWL Antenna Related Links

L.B. Cebik, W4RNL was a respected antenna expert. There is great information on his web pages

Build a Shortwave Antenna. A good overview of home brew multi-band antennas by N4UJW

Amateur and Short Wave Radio Electronics Experimenter's Web Site

MF and HF Receive Antenna Splitter

Introduction

As a radio experimenter, I have numerous MF and HF receivers to listen to but usually only 1 main outdoor antenna. Typically, this means that only my main radio receiver is connected to the outdoor antenna and my other receivers must use small indoor antennas with or without RF preamplifiers. I wanted to to permanently connect my main radio shack receiver and the receiver in the room directly above the shack to my main MF and HF antenna at the same time. The solution was to build a simple antenna splitter which allows the 2 radio receivers to connect to the single coaxial antenna feed line while preserving the correct impedance at all connection points. This project is based upon the splitter presented in EMRFD labeled Figure 3.81.

Each receiver and the antenna feed line have a 50 ohm characteristic impedance. This in-phase splitter is passive and has a loss of just over 3 dB. It is designed to operate from 500 KHz up to 30 MHz.

Please do not transmit through this device.



Project Schematic

The schematic to the left illustrates the entire splitter network from the antenna input to the input of the 2 receivers. T1 and T2 are broadband ferrite transformers with enough inductive reactance to tune down to the bottom of the broadcast band. If you only require a splitter for HF, then wind T1 with 10 total turns and a tap at 7 turns from the grounded end and T2 with just 10 bifilar windings. I used FT50-43 cores to allow the use of thicker gauge wire which provides reasonable securement of the coils without external anchors, and because bigger inductors are easier to photograph. The FT37-43 ferrite core would also be a good choice, especially if miniaturization is a design goal.


MF- HF Receive Antenna Splitter

T1 = 14 turns FT50-43 ferrite torroid. Tap at 10 turns from grounded end for 25 ohm point
T2 = 11 bifilar turns FT50-43 ferrite torroid

Circuit Building Details



The antenna splitter breadboard is shown to the right. I used 3 colors of 22 gauge enamel covered wire to make my inductors. T2 is the actual splitter network coil and is the lower transformer in the photograph. The 100 ohm resistor serves to isolate the 2 ports connected to the receivers and absorbs impedance mismatches which may present when one terminal is not properly terminated. Note that the characteristic impedance at the input of this 3 port network is only 25 ohms. You can choose to ignore this or use an additional network such as a broadband transformer or an L- match between your antenna coax and the splitter to match this 25 ohm impedance.

I chose to use T1 which is an autotransformer with a tap at approximately the 25 ohm point. The splitter network worked well during my tests. Having only 1 receiver versus 2 receivers connected made no difference to the signal strength due to the excellent output port isolation.

Note that Wes, W7ZOI uses this 3 port network network several times in EMRFD. One example is the Lichen transceiver while another is the 6M superhet receiver presented in Chapter 6. Consult EMRFD for further discussion of this and other multiple port networks.

T2 is a bifilar transformer. The 2 wires were twisted together by securing one end of the 2 wires in a vise and the other end of these 2 wires in the chuck of a brace and bit (manual) hand drill. I twisted the hand drill until I had 8 twists per inch on the 2 wires . I used 2 color wire for ease of construction, however, it is almost as easy to tell the windings from one another by using an ohm meter or audible continuity tester.

Chassis

To the right is the completed project showing the SO-239 connectors which are wired to the antenna splitter output ports. A chassis from an old project was recycled for this new project. The large bolts seen in some of the of the photos were used to fill in holes which had been drilled for the old project. This was done to provide improved RF shielding. The bolts also increased the weight of the chassis and help keep it from tipping over. Although it does not look as attractive as if I had used a brand new project chassis, considerable cost savings were realized. These little Hammond project boxes are getting very expensive. Also the splitter is kept an the back of my main radio desk where it is out of sight anyway.

Update August 10, 2008 - Contribution by Dave, G4AON

This original network was designed for use in the MF to HF spectrum. Limiting this network is the input matching transformer T1 which negatively effects the T2 output port isolation; especially at 41 meters and higher. Testing by Dave, G4AON confirmed this. Dave designed, built and tested a trifilar wound, UNUN input matching transformer which provides a much flatter response for T2 port isolation from 0.1 to 52 MHz.



To the left you can see the G4AON input circuit for T1. In keeping with a design optimized for higher frequencies, less total turns are used on the transformers. His trifilar wound input transformer version is going to generate an impedance of (16/24)^2 x 50 = 22 Ohms at mid-band. My variation will generate (10/14)^2 * 50 = 25.5 ohms at mid-band. Using his version of T1 as opposed to my simple auto-transformer, Dave was able to provide better isolation of the output ports than the original design across a wider range of frequencies.

In the two popular, commercially sold RF splitters we have examined, the company did not even bother to match the input to the T2 transformer and some builders have written me to say they just omitted T1 and for their typical SWL listening this worked out fine for them. Increasing isolation across a wider frequency band and also matching the T2 input are issues that you the builder will have to consider.   Certainly the lossy and often non-predictable #43 ferrite material is a factor which might affect your transformer performance. While a trifilar transformer is a little more difficult build for a novice as compared to an auto-transformer, this improved design might work very well at your QTH. Testing like Dave did is certainly the way to go and I greatly appreciate his contribution.

To the right are Dave's excellent bench measurements. He used a Marconi 2018 signal generator, a Racal 9301 RF millivoltmeter and a Bird load on the other port. Kudos to Dave for performing this experiment and contributing to the receive antenna splitter knowledge base.

Dave's web site.



Antenna splitter measurements		
Freq (MHz)	Port 1 & 2 loss(dB)	Port 1 – 2 isolation (dB)
0.1	-3	16
1	-3	31
2	-3	33
3.6	-3	32
4	-3	32
5	-3	30
6	-3	28
7	-3	28
10	-3	25
14	-3	23
18	-3	22
21	-3.5	21
24	-3.5	20
28	-3.5	19
52	-4	16

Conclusion

It is really awesome to be able to connect 2 receivers to the same outdoor antenna. The 3 port network and cabling to the additional receiver does not seem to increase receive noise levels from RFI in the house. Most likely this is due to the fact I am using shielded coax, a shielded project box and have a good RF ground system.

This is a simple project you can build in one evening.
I hope you receive some good DX! 73 es CUL, VE7BPO

Here is a link from F6AOJ

Additional Photos



SWL HOMEBUILDER

Amateur and Short Wave Radio Electronics Experimenter's Web Site

Medium Frequency TRF Receiver

Introduction

This series of experiments was initiated in 2006, stalled, and was finally completed 16 months later with the inspiration provided by work regarding zero power receivers web-published by Wes, W7ZOI in late summer 2007.

Described is a complete receiver, built and presented backwards from the audio stage to the antenna. The design goals were to build a Tuned Radio Frequency broadcast band receiver with one RF amplifier, a high performance detector and a simple, headphone-level audio stage.



Receiver Block Diagram



The receiver block diagram is shown to the left. The antenna is a ~ 1 meter long whip purchased from Radio Shack in the USA. A single cascode bipolar junction transistor amplifier boosts the RF voltage and drives an envelope detector which is terminated by a JFET source follower. The source follower connects to a 10K volume potentiometer which controls the AF signal voltage into a headphone-level audio amplifier. Like most of the projects on this site, the intention is to present some circuits and ideas for experimentation. This receiver is designed for local broadcast band AM radio reception, however, the various circuits could be used in or titleered for DX receivers as well.

[A Supplemental Page can be found here](#)

Audio Stage

The AF amplifier is a superb design by Rick, KK7B and is featured in many projects in EMRFD. This audio amplifier uses one 5532 op amp and has low noise and high gain. The 220 pF feedback capacitors can be increased to boost the low frequency response. I have built 6 or 7 versions of this stage and have used feedback capacitors up to 560 pF for this purpose. In the audio path, polyester film capacitors were used to try to improve the audio quality. Additionally, the value of the 15 uF capacitor connected to pin 2 is flexible. The quiescent current draw of this stage at 12.2 VDC is 12.3 mA. Some builders may have to increase the 100 uF filter capacitor on the main 12.2 volt line to overcome motorboat oscillation. None occurred in my breadboard version. I suggest using this audio stage instead of the LM386 or discrete component final audio amplifiers in all projects which call for a headphone-level audio power amplifier on this web site.


AF Stage
12.2 VDC
10K
10K
100 uF
.01
100
22 uF
10K
100 uF
AF in
10K
1 uF
3
2
5532a
1
4
.1
5
6
8
7
5532b
220 uF
150
10K
4K7
15 uF
100K
220 pF
4K7
100K
220 pF
Nov 3, 2007 by VE7BPO

Close up of the KK7B audio amplifier breadboard from the 10K potentiometer to headphone jack

---

Cascode BJT RF Amplifier and High Performance Detector


RF Amp and Detector
100
12.2 VDC
.1
.01
T1
D1
D2
10K
470 pF
470K
30
12
2.2 uF
Q3
27K
V Bias
d
g
s
2.2 uF
12K
R1
1M
2K7
Q1
.001
3K3
220 -
270 pF
470 pF
Q2
33
270 pF
4K7
220
.1
Nov 2, 2007 by VE7BPO

Q1 = Q2 = 2N3904
Q3 = J310
D1 = D2 = Germanium diode
T1 = 30 primary and 12 CT secondary on FT50-43

R1	V Bias
12K	0.3 v
22K	0.54 v
47K	1.1 v
100K	2.1 v

Chosen R1 = 100K

Above is the combined RF amplifier, detector and JFET source follower schematic.

Cascode BJT RF Amplifier

To the left is a simplified RF amp diagram taken from the schematic above indicating the measured DC voltages for reference purposes.

T1, the output transformer was wound on an FT-50-43 ferrite toroid. An FT37-43 would also be suitable. Number 28 gauge enamel coated magnet wire was used for the 30 turn primary and 26 gauge wire was wound over top to make the secondary 12 turn, center-tapped winding. The 26 gauge wire was used for the secondary winding because it provided good anchoring of the transformer by the center tapped ground connection.

You may consider substituting a 22 to 100 ohm resistor for the ferrite bead on Q1. It suppresses VHF oscillations.

Detector

To the right is a photograph of the detector from the Q1 transformer through to the JFET source follower. Schottky/hot carrier diodes or germanium diodes such as the 1N34A with a low forward voltage drop are strongly recommended. I have found there to be significant variation in



sensitivity between different types of these diodes. The 2 germanium diodes I used were matched as described on this web page. A number of detectors were built and tested for this receiver, however, the design shown had the best audio quality when compared to the others. The virtues of this detector include low noise, high bandwidth, high sensitivity and low distortion. although a little complex, this is a detector worthy of consideration in your AM receiver projects. The center-tapped Q2 transformer secondary and the 2 diodes provide full wave detection. This serves to reduce distortion somewhat and cancel even-order harmonics in the carrier signal. You may eliminate one of the diodes and convert the Q2 transformer secondary to a conventional, single link.

A 470K ohm resistor and R1 form a voltage divider that sets the detector bias voltage (V Bias). Some measured R1 values and corresponding bias voltages are shown in the schematic. I chose an R1 value of 100K for my final version. You may have to increase or decrease the R1 value to suit your local detector sensitivity requirements. You could also substitute a bias potentiometer for front panel adjustment of the receiver sensitivity. In this detector, changing the R1 value also changed the detector frequency response. I built a separate voltage divider with roughly the same V bias consisting of a 68K and a 15K resistor and swapped it for the 470K and 100K pair. Interestingly, the 470 K and 100K pair had better low frequency response and slightly higher sensitivity than the 68K and 15K voltage divider.
Diode detectors are best driven with a high impedance source and followed by a high impedance load. Q3, a simple JFET source follower provides a high impedance load. You might want to substitute a "popcorn" MPF102 for the high Idss J310 indicated in the schematic as a J310 is not really required here. If you substitute a MPF102, please increase the source resistor from 2K7 to 4K7 ohms.

Front-end Band Pass Filter and Antenna

In late summer 2007, Wes, W7ZOI conducted experiments with zero power receivers (crystal sets and such). He wound some inductors using ferrites with an unloaded Q of over 270 at MF! Please check out Wes' web site. His work with high Q ferrite inductors illustrates the importance of quantitative measurement and also provided the following revelation; we really do not have to resort to large, air core, Litz wire coils to build high-performance inductors at MF! The early prototype front end for this project was built using FT50-61 ferrite cores, however after Wes emailed me his work on zero power

receivers, I had to get some FT-114-61 ferrites for the front end of this receiver. The next day, I emailed Mark Laurain from Amidon Associates Inc and ordered some FT-114-61 ferrite toroids. The arrival of these ferrites prompted me to finish this project and put it up on the web.

The schematic on the right is the final band pass filter used for the front end. I initially tried using just L3 for the front end, but I was unable to just tune a single station. In my city, there are 2 powerful AM radio stations at 630 and 1150 KHz. With a single inductor, I could peak one of the stations, but the other could be heard in the background. Thus, the double-tuned band pass filter presented was designed and built. Now only one station can be detected with this circuit and tuning is sharp. Most builders would use a dual-ganged variable tuning capacitor, however, I elected to use 2 separate variable capacitors. Considerable flexibility with this circuit is possible. You will have to experiment to best determine your local sensitivity versus selectivity needs and to suit the variable capacitors you have available. Large AM receiver capacitors are getting hard to find. I obtained the 2 variable capacitors shown in the photographs below from 2 old receivers found in a second hand store. One of the receivers was a Marconi tube radio that was in poor condition. I paid $5.00 for both radios and harvested the 2 beautiful variable capacitors as well as some other parts such as knobs, switches and terminal strips. Never pass up on an old, derelict radio as a potential variable capacitor source!



Front-end Bandpass Filter

L1 = 54t # 24 AWG on a FT-114-61 ferrite core,
tap 26t (A) from grounded end
L2 = 5 uH = 9t # 22 AWG on a FT-50-61 core
L3 = 54t # 24 AWG on a FT-114-61 ferrite core,
tap 30 (B), 20 (C) and 10 (D) from ground
C1 and C2 = large AM radio variable caps





Shown above are 2 photographs of the band pass filter breadboards. The 2 variable capacitors had a variation of ~ 24 to 500 pF. There is considerable interplay between the 2 capacitors. For my QTH, it was better to peak C2 first and afterward to peak C1. Consider that L1 and L2 have a hot end and a grounded end. The antenna is connected to the the hot end of L1. Predictably, when substituting the L1 center tap as the antenna connection, the selectivity of the L1-C1 tank is increased and the sensitivity or received signal strength is reduced. This also occurs when testing the various tap points on L3 to feed the RF amplifier-detector stages. In the final circuit, I settled on Point C, 20 turns from ground. Using Point D, reduces sensitivity and increased selectivity. The opposite is true when using Point B. You the builder, have to determine which L1 and L3 connection points to use based on your own experiments and local factors. You may also change the receiver sensitivity by making changes such as increasing or decreasing the 270 pF coupling capacitor value, the emitter degeneration on Q2, or the detector bias.

Band pass Filter Analysis

It is impractical to sweep a BCB band filter using variable capacitors, so some analysis using GPLA, a program that ships with EMRFD was used to plot and better understand the double-tuned band pass filter response. A worst case inductor unloaded Q of 200 was used, but I imagine that the actual Q of L1 and L3 is much higher. For the source impedance, 100K ohm was used conjecturing that a short whip antenna at 1150 KHz would have a very high input impedance and not load down the L1 inductor. In reality, it is likely the antenna input impedance might be closer to 1 Megohm, however, I am using the worst case scenario. If the filter performs better than simulated - all is great! Higher source and load impedances and higher unloaded Q inductors would decrease the bandwidth of this filter which is desirable.
Note that I am concerned that L2 at 5 uH may may overcouple the 2 tank circuits. I did not see a double humped response on GPLA analysis, however, experimentation with L2 may be in order for the more astute homebuilder. You might consider lowering the L2 value to 3 or 4 uH and performing some testing. The load impedance for L3 was rather arbitrarily chosen. Considering that various taps on L3 may be used, the XC of the 270 pF coupling capacitor and the input impedance of the RF amplifier, I just chose 47K as the L3 load impedance. Below are 2 screen captures of GPLA plots. The top graph is the double tuned band pass filter and below it is the single tuned band pass filter consisting just of L3 and C3.
These graphs lead to 2 main conclusions:

1. The final band pass filter design appears to be reasonably sound.
2. We can understand why I could not tune in a single radio station with just L3 and C3 as the band pass filter; the filter skirts are not very steep and the second unwanted station was also amplified and detected.


GPLA
File
About GPLA
GPLA - 2002
S21 =
S11 =
S21 Ref.
Click to Review Circuit
dB
Plot
dB/div.
Place Cursor
Cursor Data =====>
Drag a box on graph to Zoom
Zoom to Original Sweep
Save S21 as Ref.
Plot S11
Plot Referenc
Value Tune Mode
Up
Down
Enter new value and Click
Reset Cursor

```
0  Load R = 47000.0
1  cap  par  82.00
2  ind  ser  228000.00
3  ind  par  5000.00
4  ind  ser  228000.00
5  cap  par  82.00
98  Source R = 100000.0
99  Inductor Q = 200.0
```

Double tuned band pass filter

top 0.
10.00 dB/div.
bottom -60.0
start 0.5 Frequency MHz 0.1 Freq./div stop 1.8 C:\Todds\QRPHB\A-DESIGN\2007\am-det
Cursor Data =====>: 1.150 MHz S21= -2.18 dB S11= 0.00 dB
N (index) 5
NewValue 82
☐ Plot S11 ☐ Plot Referenc
NR= 4 %= 5 Value=


GPLA
File
About GPLA
GPLA - 2002
S21 =
S11 =
S21 Ref.
Click to Review Circuit
dB
Plot
Enter new value and Click
Frequency
Place Cursor
Drag a box on graph to Zoom
Zoom to Original Sweep
Save S21 as Ref.
Plot Referenc
Reset Cursor
Value Tune Mode
Up
Down

0 Load R = 47000.0
1 ind par 228000.00
2 cap par 84.00
98 Source R = 100000.0
99 Inductor Q = 210.0

Single tuned band pass filter

top 0.
10.00 dB/div.
bottom -60.0
start 0.5 MHz 0.1 Freq./div stop 1.8 C:\Todds\QRPHB\A-DESIGN\2007\am-det
N (index) 99
NewValue 210
Cursor Data =====> 1.150 MHz S21= -1.37 dB S11= 0.00 dB
☑ Plot S11 ☐ Plot Referenc
NR= 4 %= 5 Value=

Varactor Tuned Front-end Filter

On November 11, 2007, I decided to investigate whether or not variable capacitance or varactor diodes could effectively replace the air variable capacitors in the band pass filter. In my parts cabinet were several MVAM -109 which is an obsolete but still readily available part. Another varactor, especially designed for tuning AM receivers is the 1SV149. This varactor is manufactured from Toshiba and is also appropriate.

While not comparable to the Q of 300 or greater of a good quality air variable capacitor, varactors are smaller, cheaper and can be easily ganged together so that only 1 potentiometer is required to tune the front-end filter. To the right is a photo of the varactor tuned front-end filter breadboard.



To the left is the schematic of the varactor tuned front-end band pass filter. The air variable capacitors were unsoldered from the original filter breadboard and a small board drilled and fitted with two 250K potentiometers was soldered to it.



Varactor Controlled Bandpass Filter

Tuning voltages	630 KHz	A = 0.76v	D = 1.0v
	1150 KHz	A = 4.42v	D = 4.77v

L1 = 228 uH = 54t FT-114-61 ferrite torroid
L2 = 5 uH = 9t FT-50-61 ferrite torroid
L3 = same as L1 with tap 15t (B) and 10t (C) from ground
R1 = R2 = 250K potentiometer
D1 = D2 = D3 = D4 = MVAM-109 varactor diode

L3 was also modified to have taps at 10 and 15 turns from ground. I conjectured that since the varactor diodes have less Q than their air variable cousins, it would be wise to tap down on L3 to try and increase the selectivity of the L3 tank circuit. In the end, I used the tap at 10 turns from ground for my receiver as signal strength was still acceptably strong. You may choose to use the tap at 15 or some other point to suit your local selectivity/sensitivity requirements.

I was able to tune in single stations as I previously did with the air variable capacitors. Tuning is "touchy". Ten-turn pots would be a better choice, however, are not very frugal for such a project. You get used to tuning with conventional potentiometers after a few minutes or so. I measured the reverse voltages required to tune the 2 main local AM radio stations and they are tabled in the schematic. The L1 tank requires slightly more capacitance to resonate than the L3 tank. Thus it takes a little less applied reverse voltage to the varactor pair resonating the L1 tank compared to the varactor pair resonating the L3 tank .A side view photograph of the varactor breadboard is shown directly below. The component leads have been kept long so that I can recycle parts from experimental project to project as possible. This helps contain costs. Shorter lead lengths and proper lay out should be pursued in any final projects you build.



Single Varactor Tuned Front-end Filter

Tuning with a single potentiometer ganged to both varactors is easy to do after learning from the experiment above. All that is required is a method to compensate for the differences in capacitance between the the 2 LC tanks. I placed a high-Q (Q=300) variable trimmer capacitor in parallel with L1. By listening to the receive signal strength and tuning in one radio station using the potentiometer, I was able to peak CV for the strongest signal. I did this for both 650 and 1150 KHz and actually unsoldered CV and measured its value with a capacitance meter. The CV value was ~ 6 pF for both frequencies. I decided to replace CV with a fixed 5 pF silver mica capacitor and left it there in my final filter version. Your results will probably be different. I suggest just leaving CV


Single Pot Varactor-Tuned BP Filter
12.23 VDC
220
.001
250K
Tune
VE7BPO 11/11/07
0.1
1 meter whip
100K
100K
D1
D2
CV
L1
L2
L3
B
C
D3
D4
to 270 pF cap
L1 = 228 uH = 54t FT-114-61 ferrite torroid
L2 = 5 uH = 9t FT-50-61 ferrite torroid
L3 = same as L1 with tap 15t (B) and 10t (C) from ground
CV = 2.7 - 10 pF trimmer cap
D1 = D2 = D3 = D4 = MVAM-109 varactor diode

and using this trimmer cap to peak the signal once you have tuned a desired radio station with the main tuning potentiometer. An alternative to using CV is to vary L1. You could try compressing the number of L1 windings to allow tracking of the 2 LC tank circuits.

For the varactors, I used back-to-back VVC diodes as opposed to just a single varactor to resonate each tank. This was done in an effort preserve the highest varactor Q possible. The RF voltage of the AM RF signal may be high enough to forward bias a single varactor during a portion of the AC signal and degrade Q. This does not happen when back-to-back diodes are used. Almost all high-grade FM tuner schematics I have seen use back-to-back varactor diodes in their various ganged, tunable band pass filters. The major drawback of back-to-back diodes is your tuning range is reduced because you now have 2 capacitors in series. Experimentation may be required to achieve the BCB band-spread that you desire. You can add another pair of varactors in parallel or add some parallel fixed capacitance or even change the L1 and L3 inductance values for example.

This receiver tunes nicely and sounds fabulous. Last evening I was able to tune in 5 different AM stations, however, other than the local 2 radio stations, the others were quite faint. This is not bad considering this receiver has only 1 RF amp and a 1 meter long antenna. This band pass filter could be adapted as a pre-selector for AM radio reception. To match 50 ohms, lower L1 and L3 tap points could be chosen or a few links of wire may be wound around the inductors.

In the photograph below, you can see the 5 pF capacitor soldered in parallel with the MVAM-109 pair associated with L1. The antenna also connects to the ungrounded end of the 5 pF capacitor. Below in the last photograph; since only one potentiometer is used for tuning, a large knob was screwed on to the pot control shaft to make tuning a little easier. The solder-laden 220 ohm resistor is the connection point for the regulated 12.2 VDC. The 220 ohm resistor on the left has been cut from the 12.2 VDC connection point so 0 voltage goes to the left potentiometer.

Final Thoughts

I emailed Wes, W7ZOI and asked him why it is better to inductively couple a tuned circuit which use air variable tuning capacitors. Wes wrote his answer in the form of a complete web article entitled Coupling Methods in the Double Tuned Circuit. Big thanks Wes! From his summary, when the inductors used to resonate each tuned circuit are constant, and inductive coupling is used, the coupling of the resonators will remain constant as the variable capacitors are tuned across the band. Please download and study his web article for it not only discusses coupling in the double tuned circuit, but provides some insight into using his LadBuild and GPLA software from EMRFD.

Amateur and Short Wave Radio Electronics Experimenter's Web Site

Junk Box NDB Low Pass Filter

Introduction

With winter approaching, many HAM and SWL hobbyists find intrigue in tuning in NDB or **N**on-**D**irectional **B**eacons. Although the tunable NDB band depends on your location, in Canada it may be found in a band ranging from about 190 to 535 KHz. Canadian beacons either have just a carrier (no offset)or are tuned using the USB with about a 400 Hertz offset, however, different offset frequencies and certainly LSB are used when receiving DX from other countries.

Less than 10 Km away from my QTH is a 10 KW AM radio station at 1150 KHz. On my test receiver, the S-meter reads off the scale (> 60 dB over S-9) when tuned to this frequency. This local radio station causes spurious, second-order intermodulation products (direct mixing) that all but wipes out some weaker NDB stations that I am trying to tune in. Certainly, having a 500 Hertz crystal IF filter is useful, but attenuating this local QRM is also desirable and is the topic of this web page. Many general coverage receivers offer limited or in some cases no filtering of the NDB band, however an outboard filter is an easy project to build in one afternoon.

Update Oct 11, 2010: Here is a link to a version of this project built by Robert, K5TD

Project Schematic

To the left is the project schematic. It seems odd to build a low pass filter to reduce BCB interference (as usually a high pass filter is required for this purpose at HF) however for NDB, an aggressive low pass filter is required. For simplicity sake, a 7 element Chebychev low pass filter was chosen. Since it is easy to wind reasonably high-Q inductors for 10 uH and greater inductance using number 61 material on a ferrite torroid, the FT50-61 core was chosen for all of the inductors. Number 22 gauge wire was used for the coils to keep the unloaded Q as high as possible. The FT37-61 ferrite is also suitable, but will have less Q and require smaller gauge wire. Use 19 turns instead of 17 for the 20.2 uH and 21 turns instead of 19 for the 24.1 uH coil. Do not use number 43 material ferrite cores.


533 KHz Low Pass Filter
20.2 uH
17 turns
24.1 uH
19 turns
20.2 uH
17 turns
50 ohms
50 ohms
4700 pF
472
10 000 pF
103
4700 pF
472
All inductors wound on FT50-61 ferrite torroids

Components

I do not stock RF capacitors greater than 2200 pF, so junk box ceramic capacitors were used to build this filter. In fact, this design specifically uses more common, standard value capacitors to reduce cost and to not have to order in parts. Certainly, the astute builder could use higher quality capacitors or even large powdered iron torroids instead of the ferrite cores for inductors if higher performance is desired. Try to use high Q capacitors if you can find or are purchasing them. Poly or silver mica caps would be great choices. You can substitute a 5000 pF capacitor for the 4700 pF called for in the schematic.
To the right is a photograph of the components I used in the project breadboard.


472K
200 M*
472K
200 M*
E
103M
500V
E
103M
500V

Breadboard

To the left is the completed project. Ugly construction as always, was used. The inductors were spaced at least 2.5 cm (1 inch) apart at right angles to try to minimize unwanted coupling.



GPLA Simulation


GPLA
File
About GPLA
GPLA - 2002
S21 =
S11 =
S21 Ref.
Click to Review Circuit
dB
Plot
dB/div.
Place Cursor
Drag a box on graph to Zoom
Zoom to Original Sweep
Save S21 as Ref.
Reset Cursor
Up
Down
Enter new value and Click

0 Load R = 50.0
1 cap par 4700.00
2 ind ser 20000.00
3 cap par 10000.00
4 ind ser 24100.00
5 cap par 10000.00
6 ind ser 20000.00
7 cap par 470.00
98 Source R = 50.0
99 Inductor Q = 200.0

top 0.
10.00 dB/div.
bottom -60.0
start 0.00 Frequency MHz 10.00 Freq./div stop 2.00
C:\Todds\QRPHB\A-DESIGN\2007\NDB fil
Cursor Data =====>: 0.535 MHz S21= -0.70 dB S11= 0.00 dB
☑ Plot S11 ☐ Plot Referenc
N (index) 99
NewValue 200
Value Tune Mode
NR= 4 %= 5 Value=

Above is the plot of the filter during simulation with GPLA. The simulation calculated an attenuation of ~46dB at 1150 KHz. At 1000 KHz the signal was 40 dB down, at 800 KHz it was ~24 dB down and at 630 KHz, the attenuation was only ~5.7 dB! Clearly this filter is not suitable if the offending BCB interference is from a station significantly less than 0.8 MHz. For my situation, this filter is acceptable. A 5 element Chebychev filter was also designed and plotted but was discarded as there was only 32 dB attenuation at 1150 KHz.
Since I wanted to tune as high as 535 KHz, the 533 KHz cutoff frequency was chosen. Additional work to help those with strong BCB interference at the lower BCB will be attempted in the future and presented on another web page.

Receiver Testing and Comments

USB
RX
DSP
0.389.00
ANT 1 F.AGC
S1 3 5 7 9 20 40 60dB
MEMO 22

Click on the picture to the left to hear the beacon YWB at 389 KHz with a 500 crystal hertz IF filter engaged on a borrowed Icom R-75 receiver. W7ZOI did some measurements on his R75 receiver S-meter using a signal generator and step attenuator. From S9 on up to 60 over, the steps were very accurate. However, below S9, correlation was poor. The built in attenuator is -20 dB when engaged. On my test receiver, I did some A/B testing with the filter in or out. For 1150 KHz (without the low pass filter) I had to engage the receiver's attenuator as without it, the S-meter reads off scale. With the attenuator engaged, the S-meter reads 50 dB over S-9 when tuned to 1150 KHz.

With the filter connected between the receiver and the feed line, (and the attenuator engaged) the S-meter read S-9.This is a drop of about 50 dB at 1150 KHz which means that this filter pretty much works as designed. I love the Icom R75 receiver; it is good value with it's many features in a compact package. Further testing was undertaken on other frequencies.

When listening to **WWV**; At 2.5 MHz, without the filter, the S-meter read S-9. With the filter inline, I could not hear WWV or see any S-meter reading. At 5 MHz without the filter, the S-meter read was at 20 dB over S-9. With the filter inline, I could still hear WWV very faintly, but the S-meter did not register. There was little noticeable attenuation at less than 700 KHz when using this filter.

Additional Photos and information



Shown above is the completed project in a Hammond die-cast case with SO-239 connectors at each end.

Shown above a photo of the Skookum beacon SX. It is on 389 KHz. This NDB is located in Skookumchuck BC, Canada

Links

My friend and fellow NDB enthusiast, Ken, VE7KPB has a posting on his web site showing some of the beacons he has logged from his QTH. Consider trying some of these frequencies from your own QTH to get used to finding beacons. Note you must temporarily allow pop ups to see his excellent log.

We recommend this non-directional beacon search and log utility program called WWSU from VE3GOP It must be registered and is a wonderful low cost tool.
I was near beacon L in Balti, Moldova (Балти, Молдова) in 2006. Below is a snippet from the VE3GOP program showing beacon L and also some nearby beacons. (Я изучаю русский язык). Приветствую Вас дорогие друзья!



Coverage radius from B-389 kHz (km) 160

```
L       389 kHz  BALTI, Moldova ( 7690 km)
IAS     391 kHz  IASI, Romania ( 7725 km)
SCV     396 kHz  SUCEAVA, Romania ( 7621 km)
MO      406 kHz  MOHYLIV PODILSKYI, Ukraine ( 7650 km)
LD      473 kHz  CHISINAU, Moldova ( 7828 km)
RG      473 kHz  CHISINAU, Moldova ( 7820 km)
N       509 kHz  CHERNIVTSI, Ukraine ( 7558 km)
R       509 kHz  CHERNIVTSI, Ukraine ( 7563 km)
```

Martin Francis has an excellent NDB web site including the free program called NDB WEBLOG for a number of platforms

Some beacons may be located using this NavAid web site

Clint, KA7OEI has an informative web site regarding NDB listening including using digital computer processing to dig out weak signals. This is also a great overview site for newcomers to NDB.

Conclusion

To the right is the outcome when I connect my frequency counter directly to my antenna coax cable feed line. 1150 KHz is my nemesis frequency! Happily it can be tamed with a little filtering to allow NDB listening and logging.


5246L ELECTRONIC COUNTER
HEWLETT · PACKARD
KHZ
01146613
FUNCTION
RESET
AR 5395-TEST

To the right is the outcome with my SWL antenna coaxial feed line connected directly to the scope. The scope was on the 0.5 volts per cm scale, so the peak to peak voltage is 0.2 volts. In just about any high-gain audio amplifier I build, if I touch my finger to the input, I can hear AM 1150 loud and clear - no wonder!

Good luck with your own NDB adventures!



SWL HOMEBUILDER

Amateur and Short Wave Radio Electronics Experimenter's Web Site

More NDB Information and Circuits

Introduction

Latest Update: December 3, 2012

This web page holds a collection of NDB-related ideas, experiences and hopefully will include some feedback from fellow NDB enthusiasts.

I devoted a new notebook to this topic and hopefully with inspiration from band listening and communicating/learning from others, I will fill it over time. New content will be added to the bottom of the existing material as QRP-Postadata



Improved NDB Chebyshev Low Pass Filter

A popcorn or "junk box" low pass filter was designed and presented [on this web page](). After discussion with VE7TW and testing a Realistic DX-300 and other receivers, it became apparent that even more attenuation of a strong local BCB station at 1150 KHz was desirable. In addition, there are other moderately strong AM radio stations from 630 to 800 KHz (especially at night time) which maybe causing mixer intermodulation distortion products. A fault of the junk box low pass filter is poor attenuation below 800 KHz and a better design was a prudent goal. Building on the learning obtained from the junk box filter experiments, an improved 7 element Chebyshev low pass filter was designed and is presented directly below. The 3 dB cut off of this filter is calculated to be 526 KHz. This is the filter that I now use for my home radio station. At my

nemesis frequency of 1150 KHz (where a powerful local radio station broadcasts), the attenuation is calculated to be 68 dB. It takes careful layout and a conductive chassis to realize this level of attenuation, but the effort is worth it. In very strong AM BCB locations, you might consider placing 2 such filters in series between your antenna and receiver if required.

NDB Low Pass Filter. - 3 dB Attenuation @ 526 KHz


20 uH
17 turns
36 uH
23 turns
36 uH
23 turns
20 uH
17 turns
50 ohms
50 ohms
8300 pF
10000 pF
8300 pF
8300 pF = 6800 + 1500
top
0.
dB
Plot
10.00
dB/div.
bottom
60.0
start
0.00
Frequency
MHz
10.00
Freq./div
stop
1.50

-3 dB	~526 KHz
-6 dB	~545 KHz
-10 dB	~ 565 KHz
-20 dB	~ 625 KHz
-40 dB	~780 KHz
-60 dB	~ 1027 KHz

All inductors wound on FT50-61 torroids

The schematic and simulation of the improved NDB low pass filter is shown above.

Non-directional Beacon Identification

It is interesting to visit nearby beacons. In the photograph to the right is XC which broadcasts at 242 KHz.

I have learned that it is very important to confirm the NDB stations your hear via a database or list. What you hear on the air should match the database/list for **both** call sign and frequency, else suspect that you may have copied it incorrectly. **RNA**, the definitive signal list for North and Central America plus Hawaii may be found here.

Three Questions

Steve Ratzlaff, AA7U is an experienced NDB DXer and has been listening to beacons since the mid-1980's.
I asked him the following 3 questions:

1. LF beacons do little more than send their station identification in Morse code, are mostly low power and generally might be perceived by some people as boring and low tech. Yet, on the World Wide Web, one finds numerous web sites, software, projects and commercial equipment all passionately dedicated to NDB listening. What's all this fuss about listening to beacons?

Steve: It's a hobby that requires quite a bit of skill and technical accomplishment to get the most from the equipment. Most folks have AC noise to deal with, which can be particularly bad at LF. Finding an antenna that works at LF and that can be used at your own location can be a major task; finding a radio that has decent LF sensitivity, or an LF converter to use with an existing radio--all these must be detitle with just to begin hearing anything at LF. I find it to be quite a challenge. If it were easy to receive LF beacons then I probably would have lost interest years ago! It's true that in recent years several software programs have become available that allow finding beacons somewhat easier--one simply looks for them on the computer screen and decodes the dots and dashes of the beacon being received. This is quite popular among beginners and veterans alike. But the traditional method of aurally listening for the morse code idents of beacons is probably used more often, though many are combining both aural and software techniques now.

2. Let's say I live in a small city lot or even an apartment. I have modest equipment and/or not a huge amount of cash to spend on gear for NDB listening. From the antenna through to the headphones, what are some basic recommendations you might give to a newcomer wanting to get started in NDB listening?

Steve: The radio must have decent sensitivity at LF, or else an LF converter must be used. Due to high local AC noise, any type of LF antenna used indoors will be a poor substitute to one that can be placed outdoors. A few portable radios cover the LF NDB frequency range that will work for hearing local beacons, though the radio may need to be used outside to get away from AC noise. The discontinued Sony 2010 was the standard for portable radios for reasonable LF performance. Newer radios like the Degen DE1103 have been found to work reasonably well at LF and can be bought for well under $100 by mail order from eBay sellers; or the more expensive Kaito 1103 version, which has a warranty, can be obtained from several distributors like Universal Shortwave. The much more expensive semi-portable Eton E1 works well at LF, but is more in the price range of a tabletop radio. The Icom R75 is currently the best bargain in a tabletop radio that has very good LF sensitivity as well as 1 Hz tuning, which is an asset if a narrow external audio filter is used. I'm not too optimistic about what someone living in an apartment or high rise building might do to successfully receive LF beacons indoors. Often the AC noise level is too high to be able to use an indoor antenna. But some have been able to use loop antennas indoors for the stronger signals. An example of a top of the line commercial loop would be the Wellbrook ALA1530 or LFL1010. Unlike at shortwave frequencies, where simply tossing a wire out the window to a nearby tree or other support, or even running the wire around the room inside, will usually work fairly well, at LF a wire less than several hundred feet generally doesn't perform very well. It can be argued that an active whip antenna makes a very good LF antenna, and doesn't take up much room, but it must be used outdoors. And if there are strong AMBCB signals, then the active antenna, either loop or whip, must have very good overload resistance otherwise it can generate distortion of its own from the strong BCB signals.

3. What kind of distances are considered DX for NDB?

Steve: NDB DX is pretty much a relative thing. One just starting out might be thrilled to hear a beacon from the next town, or from the other side of his own state or province. As one improves his listening setup and gains experience, then usually DX goals also expand to try to hear beacons farther and farther away. NDB DXing generally is not a competitive hobby, unlike amateur radio with its various competitive "contests". Each person's listening setup, local noise level, etc. is usually very different from someone else's, even someone in the same town or general area. One person might live in the suburbs and have a lower noise level than his friend who lives right in town and has a much higher noise level. One might have room to put an antenna in a quiet spot; the other might be limited to much less. People who live near an ocean generally have a much better chance at hearing something exotic offshore than folks living far inland. Folks living in the central or eastern part of North America have many more beacons available to be heard than folks in western North America. But there are always a few beacons that are much stronger than most, and can be heard from long distances of 1000 miles or more, pretty much anywhere in North America at night. One example would be 206 GLS in Galveston, Texas, which runs around 2000 watts, has a large antenna, and is generally readily heard anywhere in North America at night--that beacon might be 1500 miles or more away, and might be considered real DX. However another 25 watt beacon from the same general area in Texas might be hard to hear only several hundred miles from that beacon. So "DX" is pretty much a relative term. Ndblist, an international email list devoted to beacons, is open to anyone with an interest in beacons--members post their loggings there. What might be a local beacon to someone might be DX to someone in a different part of the country. All levels of experience are welcome.

Thanks Steve.

NDB High Pass Filter

A high pass filter using standard value capacitors was designed using GPLA. although, such a filter would not help AC line noise and RFI generated in the house, I suspected my antenna was picking up local noise from below the NDB band. This filter was mounted inside a die-cast Hammond box with a SO-239 at each end. I used 22 gauge enamel covered wire for the inductors. A photo of the filter is shown to the right.
For the 0.01 uF caps, I used junk box ceramic capacitors with a 20% tolerance, however, I did measure a bunch and found 2 within 5% tolerance for my filter bread board.



To the left is the filter schematic. This is an N = 7 Chebyshev high pass filter with a 3 dB cut off of 157 KHz. This cutoff frequency allowed the use of common, standard value capacitors and also even turns numbers to reach the desired inductance for the inductors when wound with FT50-61 ferrite cores.


157 KHz High Pass Filter for NDB
.022 uF
.01 uF
.01 uF
.022 uF
50 ohms
50 ohms
33 uH
22 turns
27 uH
20 turns
33 uH
22 turns
VE7BPO
All inductors wound on FT50-61 ferrite torroids

Use 5% tolerance, high Q caps such as polystyrene or NP0 ceramic and **not** junk box bypass-grade ceramic capacitors as possible. I used trashy ceramic caps for the 0.01 uF parts due to lack of better parts at the time of building and testing.


GPLA
File
About GPLA
GPLA - 2002
S21 =
S11 =
S21 Ref.
Click to Review Circuit
top
dB
Plot
dB/div.
bottom
157 KHz High Pass
N (index)
NewValue
Enter new value and Click
start
Frequency
Freq./div stop
Place Cursor
Cursor Data =====>:
Drag a box on graph to Zoom
Zoom to Original Sweep
Save S21 as Ref.
Plot S11
Plot Referenc
Value Tune Mode
Up
Down
Reset Cursor

-3 dB ~ 157 KHz
-6 dB ~ 150 KHz
-20 dB ~ 128 KHz
-40 dB ~ 99 KHz

0 Load R = 50.0
1 cap ser 22000.00
2 ind par 33000.00
3 cap ser 10000.00
4 ind par 27000.00
5 cap ser 10000.00
6 ind par 33000.00
7 cap ser 22000.00
98 Source R = 50.0
99 Inductor Q = 200.0

top: 0.
dB/div.: 10.00
bottom: -60.0
N (index): 4
NewValue: 27000
start: 0.00 MHz
Frequency: 10.00
Freq./div stop: .3
C:\Todds\QRPHB\A-DESIGN\2007\NDB fil
Cursor Data =====>: 0.178 MHz
S21 = -0.28 dB
S11 = 0.00 dB
☑ Plot S11
☐ Plot Referenc
NR= 4
%= 5
Value=

Above is the filter GPLA simulation. In particular, I have harsh noise from about 110 KHz on down. At 78 KHz, where this filter has a calculated attenuation of ~ 56 dB, I made an audio file of the band noise. This is in AM mode with the filter out for a few seconds and then in line. With the high pass filter in line, there is pronounced attenuation of the noise and my local 10 KW BCB station at 1150 KHz suddenly appears. Prior to this it was hidden by the harsh noise. At frequencies less than ~200 KHz (without my low pass filter) I can hear this BCB station intermittently as I tune around. I suspect that the R75 filtering down at 200 KHz and down is insufficient to stop this monster station.

At my QTH, using a high pass filter reduces some of the noise on the NDB band. At my location, a high pass plus a low pass filter in cascade between my antenna and my receiver results in less QRN and easier weak signal copying.

Long Wave Broadcast Radio Filter

I learned about LW Broadcast radio from Steve Ratzlaff. In particular, радио россий "Rah-deo RaSEE" (make sure you roll the R!) can occasionally be heard on the west coast and broadcasts at night-time using 500-1000 KW power. The frequencies he recommended to try were 153, 180, 189, and perhaps 171, 234 and 279 KHz. I have terrible problems with a local BCB radio station at 1150 KHZ that causes intermodulation distortion and/or blow-by detection at and below 200 KHz in addition to a terrible noise source at 78-120 KHz. Therefore, I built another cascade low pass/high pass filter and placed it in the same chassis as my regular NDB low pass/high pass combination filter for use when tuning LWBC and perhaps for when listening to frequencies less than 200 KHz.

1800±5%
CDE
153J


322 KHz Low Pass Filter
VE7BPO
30 uH
21 turns
53 uH
28 turns
53 uH
28 turns
30 uH
21 turns
50 ohms
50 ohms
15000 pf
17700 pF
15000 pf
All inductors wound on a FT-50-61 ferrite torroid

Above is. the schematic of the 322 KHz low pass filter. In the photograph above, you can see a 50 ohm pad at the input that was used only during testing. This filter offers a calculated attenuation of ~ 98 dB to my 1150 KHz interfering station. In reality it is not possible to achieve this level of attenuation, however, there is no detectable 1150 KHz signal interference with the filter in line which makes me happy. Click here to listen to the dramatic difference with regard to interference this filter makes at my QTH with my receiver tuned to 199 KHz. The receiver is set for wide band AM detection; first without the LWBC filter and then with the filter switched in. When the filter is switched in, the BCB interference disappears and a Canadian NDB (UAB @ 200 KHz can faintly be heard along with our cat meowing in the background. It is not possible to listen to LF without aggressive low pass/high pass filtering at my QTH.


GPLA
File
About GPLA
GPLA - 2002
Click to Review Circuit
S21 =
S11 =
S21 Ref.
top
dB
Plot
dB/div.
bottom
start
Frequency
Freq./div
stop
Place Cursor
Cursor Data =====>:
Drag a box on graph to Zoom
Zoom to Original Sweep
Save S21 as Ref.
Reset Cursor
Value Tune Mode
Up
Down
Enter new value and Click

322 KHz Low Pass

ATT	KHz
-3 dB	~322
-6 dB	~333
-10 dB	~345
-20 dB	~381
-40 dB	~487
-60 dB	~635
-76 dB	~800
-99 dB	~1150

0 Load R = 50.0
1 ind ser 30000.00
2 cap par 15000.00
3 ind ser 53000.00
4 cap par 17700.00
5 ind ser 53000.00
6 cap par 15000.00
7 ind ser 30000.00
98 Source R = 50.0
99 Inductor Q = 200.0

N (index): 3
NewValue: 53000

top: 0.
10.00 dB/div.
bottom: -60.0
start: 0.00 MHz
Freq./div: 10.00
stop: 1.5
C:\Todds\QRPHB\A-DESIGN\2007\lw-bcb
Cursor Data =====>: 0.294 MHz S21= -0.26 dB S11= 0.00 dB
☑ Plot S11
☐ Plot Referenc
NR= 4
%= 5
Value=

Above is the GPLA simulation of the LWBC low pass filter.


33000 pF
12700 pF
12700 pF
33000 pF
50 ohms
50 ohms
39 uH
24 turns
33 uH
22 turns
39 uH
24 turns
VE7BPO

129 KHz High Pass Filter

All inductors wound on FT50-61 ferrite torroids

12700 pF = 10000 + 2700

Above is the schematic of the 129 KHz LWBC high pass filter. In either of the 2 filters, capacitor values can be obtained using 1 or 2 standard value capacitors in parallel. The cutoff frequencies of both filters were chosen to allow using practical component values.


GPLA
File
About GPLA
GPLA - 2002
S21 =
S11 =
S21 Ref.
Click to Review Circuit
dB
Plot
Frequency
Place Cursor
Cursor Data =====>
Drag a box on graph to Zoom
Zoom to Original Sweep
Save S21 as Ref.
Enter new value and Click
Up
Down
Reset Cursor

129 KHz High Pass

ATT	KHz
- 3 dB	~129
- 6 dB	~123
-10 dB	~117
-20 dB	~103
-40 dB	~78

0 Load R = 50.0
1 cap ser 33000.00
2 ind par 39000.00
3 cap ser 12700.00
4 ind par 33000.00
5 cap ser 12700.00
6 ind par 39000.00
7 cap ser 33000.00
98 Source R = 50.0
99 Inductor Q = 200.0

top 0.
10.00 dB/div.
bottom -60.0
start 0.00 MHz
10.00 Freq./div
stop 0.30
C:\Todds\QRPHB\A-DESIGN\2007\lw-bcb
N (index) 3
NewValue 12700
Cursor Data =====>: 0.145 MHz S21= -0.28 dB S11= 0.00 dB
☑ Plot S11 ☐ Plot Referenc
Value Tune Mode
NR= 4 %= 5 Value=

Above is the GPLA simulation of the LWBC high pass filter. The high pass filter might not be needed at your QTH. My LWBC filter has the low pass filter before the high pass filter. I.e. they are in series or cascaded.

Dual NDB and LWBC Filters



For use in my radio shack, I built LWBC and NDB filters inside 1 chassis with separate inputs and outputs. Some photos of this project are shown directly above and below. The NDB filter is the 526 KHz low pass filter in series with the 157 KHz high pass filter. The LWBC filter is the 322 KHz low pass filter in series with the 129 KHz high pass filter. High Q caps were used and the inductors were wound with either 22 or 24 gauge wire to obtain a relatively high unloaded Q. The large Hammond project case allowed reasonable spacing of the inductors and a nice long input to output layout.

Beacon XJ @326 KHz

Above is NDB XJ in Fort St. John, BC. Photo by VE7KPB in August 2008.

QRP — Posdata: NDB Low-pass Filter with Trap

An email from Rick, NU7Z spawned this 2012 addition.

Depending on their design, typical NDB low-pass filters provide less than 20 dB attenuation at 620 - 630 KHz, and if you hear a strong station on this frequency — good luck!

Rick sought a filter with a trap at ~ 620 KHz — after mulling around, we encountered design problems with a trap frequency so close to the low-pass cut-off frequency and later asked Wes, W7ZOI if he might help design our filter.


NDB Low-pass Filter with 620 KHz Trap
8t FT50-61
4.69 uH
19t FT50-61
24.30 uH
8t FT50-61
4.69 uH
50 Ω
50 Ω
.015 uF
.015 uF
6800 pF
560 pF
.012 uF
.001 uF
.012 uF
.001 uF
560 pF
6800 pF

Above — My version of the Wes, W7ZOI designed NDB low-pass filter with a trap. **Red** filter below


R1
50
L1
22µ
L2
24.3µ
L3
22µ
out1
V1
AC 2
C1
7.3n
C3
12.96n
C4
12.96n
C2
7.3n
R2
50
.ac dec 500 0.2meg 2meg
R3
50
L4
4.687µ
C9
14.06n
L5
24.3µ
L6
22µ
out2
V2
AC 2
C5
7.3n
C7
12.96n
C8
12.96n
C6
7.3n
R4
50
R5
50
L7
4.687µ
C14
14.06n
L8
24.3µ
L9
4.687µ
C15
14.06n
out3
V3
AC 2
C10
7.3n
C12
12.96n
C13
12.96n
C11
7.3n
R6
50

Above — A 7th order, 0.1 dB ripple **Chebyshev low-pass filter** with a 550 KHz cut-off filter evolved to include **1 trap**, and then **2 traps** at 620 KHz.

We learned that in simple situations, you may modify the elements of a low-pass filter so that the usual inductor is replaced by a parallel trap. See Wes' work in EMRFD Chapter 3; in particular, Figure 3.10.

Wes wrote he's employed this technique successfully before — for example, to add harmonic suppression to a simple output network for a QRP transmitter, although he hadn't added traps to higher order filters like the 1 we wanted. Click for a file containing the math contributed by Wes, W7ZOI.



Above — The SPICE analysis of the 3 color-coded filters above. This design excludes the impact of finite L and C and the unloaded Q that could significantly affect function since the trap frequency is close to the low-pass cutoff frequency. These factors usually worsen the insertion loss near cutoff, but since we're using this filter in a noisy RF environment, filter misperformance should be tolerable.

In the future, Wes recommended designing an elliptical low-pass filter with software such as that distributed by AADE.



Above — A version of the filter built by Rick, NU7Z using epoxy-coated inductors for the L's. The insertion loss with these inductors = ~ 5 dB, although he runs a 40 dB receive preamp and can accommodate such losses.

Despite employing a loop receiving antenna, he could not listen around 500 KHz due to a loud, local broadcast station at 630 KHz. Inserting this filter reduced this 630 KHz signal from 40 dB over S-9 down to S-1 on his receiver S-meter.

Fantastic! Big thanks (большое спасибо) to Wes, W7ZOI.

Amateur and Short Wave Radio Electronics Experimenter's Web Site

440 Hertz Peaked Low Pass Audio Filter Experiments

Introduction

At audio frequencies, low pass filtering can go a long way to improving CW and beacon reception. It has a been a long time since I built one and therefore decided to experiment with some designs using the 5532 op amp. EMRFD has a great section on RC active audio filters starting at Chapter 3.5 and this is where I began. After some experimentation, I remembered a peaked low pass filter designed and published by Wes, W7ZOI in the 1970's. This filter became very popular in Russia after publication in a 1971 Russian Amateur Radio Journal. I asked Wes if he might design another low pass filter peaked for 440 Hertz, which is my favorite CW beat note frequency. This filter is intended for use as an out board headphone jack device for the Icom R75 or other receiver.

AF LOW PASS
PHONES
INPUT

Base Project Schematic


+12
+12
100
10K
0.1
100
IN
0.1
F
1K
2.7K
3.3K
0.1
100
22
10K
0.1
10K
5532
Q
4.7K
1K
Tunable RC Active Peaked Low Pass Filter
w7zoi 14Dec07

Above is the filter designed by Wes, W7ZOI. It has two 1K pots you can tweak; a subtle frequency control and a Q adjustment. It is theoretically possible to adjust the Q too strongly as to cause oscillation, although this did not happen with my bread board.

Schematic and Circuit Building Details


440 Hz Peaked Low Pass Headphone Amplifier
12.2 VDC
To pin 3 of unused 5532(2) section
10K
10K
22 uF
.01
12.2 VDC
22 uF
10K
100
100 uF
10K
100 uF
receiver headphone jack
.1
5
8
.1
+
3K3
3
5
8
220 uF
5532(1)
7
+
5532(2)
7
10
6
4
3K3
.1
5532(1)
1
.1
6
4
10K
150
(2)
2
47K *
4K7
Other 1/2 of 5532(2) unused
10K
5K1
220 pF
* 33 - 100 K may be used to suit needs
.68 uF
All 0.1 uF caps are poly" something"

Above is the final filter design. My prototype filter had 2 variable pots and I disconnected and measured them after discovering my favorite setting and then constructed the version shown above using fixed-value resistors instead of the potentiometers. If you like to tweak knobs, you might leave 1 or both of the pots in. The 0.68 uF cap can be raised as high as 4.7 uF if you have poly caps this large in capacitance value. although, it seems wasteful, I did not use one half of the second 5532 op amp. Feel free to add another pole of low pass filtering or something else to utilize this stage if you like. Pin 3 of the unused, second op amp 1/2 is connected to the 10K/10K voltage divider bias with a wire as indicated in the text.

This filter sounds the best when the R75 volume control is minimally turned on as I suspect some of the wide band noise heard is from the ICOM AF chain. More importantly, If the R75 audio gain control is turned too high, the filter will be overdriven and sound distorted This is especially true when using the 2.4 KHz wide SSB filter on the R75. The 10 ohm filter input resistor attenuates the receiver output and makes it more difficult to overdrive the audio filter. The 500 Hz filter at the 9 MHz Receiver IF has quite a bit of of loss and with this filter switched in, it is difficult to overdrive the audio filter. For best results, an audio filter should be placed just after the first AF preamp stage, however, using the headphone jack is the only option available for adding AF filtering in most commercial receivers I have used.
The second op amp stage is used to increase the headphone volume and the 47K feedback resistor can be adjusted to suit your needs. It is really important to experiment with the component values which will match your receiver and the IF filters and antenna you have. For example the input shunt resistor may be increased from 10 to 18-22 ohms if you always use a narrow IF filter during CW and beacon listening or received signals are low in volume. This is an experimenter's circuit, not a finished project. Overall, this circuit has low output volume and is really gentle on the ears in terms of noise and amplitude.

Project Breadboard and Samples

Shown to the right is a side photo of the experimental project. The big yellow Mallory polyester caps were used as I did not have any other desirable AF filtering caps in my parts stock. The day after, I built this filter, my parts order (including a big selection of polyester film audio caps) from Digi-Key arrived, however this is Murphy's law. These Mallorys are good quality capacitors- just a little large!



Low pass filters can really help reduce noise during reception. Two example audio files follow. These were heard in the NDB band using a 2.4 KHz SSB IF filter.
290 YYF
312 UNT
The occasional scratchy noises are me moving as I held the headphones around the microphone.



Above is the filter photographed from above. The 3 blue LEDs are used to light the lower row of buttons on the R75 as it is difficult to see them with a low level of light in the radio shack. No hum is heard with this filter. When you build AF amps or filters with the 5532, after soldering pin 4 to the copper ground plane, start out by connecting the components associated with pins 6 and 7 and then 1 and 2. I suggest this as placing components between adjacent pins is often the most difficult part of building when using ugly construction with op amps.

If by accident you make an unintentional solder bridge between 2 adjacent pins on an op amp, simply heat the 2 bridged pins up and gently drive a small screw driver between the pins. This should remove your unwanted solder bridge. The 5532 op amp is quiet and relatively inexpensive. In EMRFD, there are countless examples of how one can use them in a variety of applications.

Additional Information and Photographs

Above is a photo of the audio filter in action on the NDB band. The blue LED reflection can be seen on the receiver. For serious NDB and CW pile up work, narrow band pass audio filters are generally required. This simple audio filter experiment might be useful as a spring board for your own AF filter experiments and to learn the filter requirements of your own particular receiver.

Above is the filter photographed from the rear. The DC power cord has a built in RFI filter. For homebuilt projects, DC power cords can be obtain by cutting the power cord off old unwanted or broken "wall wart" power supplies. This provides you with a nice cord with a built-in plug. I collect old AC "wall wart" transformers for this purpose. This filter is powered by the main 12 volt DC supply on my radio bench.

Amateur and Short Wave Radio Electronics Experimenter's Web Site

Cascode Hybrid-Based WWV Receiver for 5 MHz

Introduction

This was my favorite project of 2007. When I web published the original TRF WWV receiver for 10 MHz in 2006, there were many complaints that I used hard-to-find dual-gate MOSFETs and also that the AF stage lacked the popcorn factor that this web site has become strongly associated with. In this experimental project, these 2 concerns are addressed.

RF GAIN
Volume

The cascode JFET and BJT amplifier stage used in this receiver is based upon the amplifer described in the Hybrid Cascode IF Amplifier article which was published in QST for December 2007 and designed by W7ZOI and WA7MLH. This amplifier topology has many advantages including high gain + low noise, that it can function well at DC voltages less than 12 VDC and that the noise figure does not degrade when the BJT bias (and stage gain) is lowered during AGC action. Please read the QST article and also refer to the W7ZOI web site for more details on the IF amplifier and the cascode hybrid topology.

Receiver Block Diagram


Outdoor MF/HF
Antenna
Loudspeaker
Front end
Filter
RF Amplifier
Crystal Filter
RF Amplifier
(2 stages)
Detector
Audio
Amplifier

The receiver block diagram is shown above. To hear digitally recorded examples of this receiver, click here , here or here. No attempt was made to make these files sound better than they really are- there is signal fading, room noise etc. A electret microphone was placed near the loud speaker to record these audio samples. *Note I am now compressing audio files in the mp3 format to allow listening by those who use Linux as their operating system.* **A supplemental web page** to this main web page is linked here

---

Receiver Front End: Band Pass Filter and First RF Amplifier



L1 = L2 = 32 turns # 26 AWG on a T50-2 torroid
CV = 10 - 70 pF trimmer capacitor
T1 = 14 turns on a FT37-43 ferrite
Q1 = 2N3904
Q2 = J310

This receiver is meant to interface with a standard 50 ohm feed line. Testing was performed using my MF/HF antenna.
I built 3 separate bread boards of this receiver and tried varying the number of RF amps, using different detectors (as well as different detector followers) and eventually built and tested this basic receiver design for 5, 6 and 10 MHz. With respect to using the cascode hybrid amp (and probably any other amplifier type) **in a TRF receiver**, I learned 3 things:

1. Do not operate the RF amps at maximum gain. I built some very powerful amps with a Q2 source resistor of 47 ohms and over 6 volts bias on Q1. While powerful, this amp broke into oscillation and also consumed much current (nearly 20 ma).

2. Keep the RF stages at least 2-3 cm apart to reduce the chance of parasitic oscillations.

3. Keep the input band pass filter at least 2 cm from the Q1/Q2 amp or you might encounter some unwanted oscillations.

For the front end band pass filter, a reasonably narrow bandwidth was desired. When sweeping early filter designs using a signal generator and oscilloscope, a double humped response was noted. These filter designs used a 10 pF coupling capacitor. The coupling capacitor was then decreased to 5 pF. To obtain the required 5 pF, two 10 pF capacitors were placed in series as shown in the photograph directly to the right.

I struggled with this filter design because one end is terminated in the gate resistance of Q2 of the hybrid cascode amplifier and was not the standard 50 ohm impedance termination. My early filter designs suffered severe insertion loss or poor selectivity. I asked Wes, W7ZOI, for some instruction on solving my filter problems. I learned that this filter topology is referred to as a singly terminated, double tuned band pass filter. Wes designed the front end band pass filter for the 5 MHz receiver for us all to learn from and for this I am very grateful to him.




GPLA
File About GPLA
GPLA - 2002
S21 =
S11 =
S21 Ref.
Click to Review Circuit
dB
Plot
dB/div.
Frequency
Freq./div stop
Place Cursor
Cursor Data =====>
Drag a box on graph to Zoom
Zoom to Original Sweep
Save S21 as Ref.
☑ Plot S11
☐ Plot Referenc
Value Tune Mode
Up
Down
Reset Cursor
Enter new value and Click

0 Load R = 20000.0
1 cap par 194.28
2 ind par 5120.00
3 cap ser 5.00
4 dupe ind par 2.00
5 cap par 104.84
6 cap ser 100.00
7 cap par 430.00
8 rlb ser 0.00
98 Source R = 50.0
99 Inductor Q = 230.0

top 0.
10.000 dB/div.
bottom -60.0
start 4.000 MHz
Freq./div 0.500
stop 6.000
C:\Documents and Settings\Owner\My Doc

Cursor Data =====> 5 MHz S21= -2.34 dB S11= -28.08 dB

N (index) 3
NewValue 5

NR= 5 %= 0.25 Value=

Above. A GPLA simulation of the singly terminated, double tuned filter designed by W7ZOI. A double tuned circuit is mandatory ahead of the WWV receiver as local BCB and other RF energy will be amplified by the first RF amp and may distort the WWV signal in the crystal filter or even might blow-by the crystal filter and be detected and heard in the speaker.



Directly above is a close up photograph of the input filter bread board. Filter tuning was done by ear (and screwdriver!) Simply tune the trimmer capacitors for the loudest audible WWV pulses in the speaker and you are set. If you can't locate a 20K gate resistor for Q2, a 22K resistor will work okay.

Crystal Filter and Second RF Amplifier Stage

In the schematic to the right is the crystal filter and second RF amplifier. The input impedance of the crystal filter is established by the 1K shunt resistor across the output transformer on Q1. The output impedance of the crystal filter is set by the 1K gate resistor of Q4. A filter input/output Z of 1000 ohms gave the best overall shape and bandwidth during my testing.

Developing this filter was difficult. My first batch of junk box crystals had a low motional inductance and with the filter I built I could hear stations ~400 KHz below and/or above the filter center frequency in addition to WWV. After giving up in frustration for nearly 2 months, a batch of 10 crystals were ordered from Digi-Key. These were microprocessor crystals; ones with 18 pF load capacitance in a HC49/U holder. The new filter was tweaked and tested and now provides single signal reception of WWV. Your own results may vary according to your crystal parameters. The Digi-Key part number is provided for reference purposes only.


Xtal Filter and Second RF Amp
12.2 VDC
51
.1
12K
.001
.001
T2
Q3
10K
All crystal filter caps are pF
Y1
Y2
Y3
Y4
Y5
47
47
1K
g
d
s
Q4
.1
150
33
47
47
33
Y1- Y5 = 5 MHz Xtals (Digi-Key 535-9025-ND)
T2 = 14 turns on an FT- 37- 43 ferrite torroid
Q3 = 2N3904
Q4 = J310
VE7BPO

drafting error corrected Dec 30, 2007 - the Q3 output cap



To the left is a close up photograph of the 5 MHz crystal filter. The crystals were turned upside down and the outer cases were directly soldered to the copper ground plane as you can easily see in the crystal to the left of the others. The rest of the crystals as well as one of the 47 pF tuning capacitors were soldered on the other side and solder points are hidden from view. The crystals were positioned to keep the output of Q1 away from the input of Q4. ***Stage lay out is very important in TRF receivers.*** I found stage layout to be far more important than keeping lead lengths short from my experimentation.



0 Load R = 1000.0
1 cap ser 33.00
2 xtl ser 0.00
3 cap par 33.00
4 xtl ser 0.00
5 cap par 47.00
6 xtl ser 0.00
7 cap par 47.00
8 xtl ser 0.00
9 cap par 33.00
10 xtl ser 0.00
11 cap ser 47.00
98 Source R = 1000.0
99 Inductor Q = 100.0

top: 0.
dB/div: 10.00
bottom: -60.0
start: -6000.00
Frequency: Hz
Freq./div: 6000.00
stop: 12000.00
N (index): 98
NewValue: 1000
C:\Todds\QRPHB\A-DESIGN\2007\49 met

Directly above is the GPLA simulation of my crystal filter. The 5 MHz point is not centered exactly in the middle of the pass band, but a reasonable AM filter was built nonetheless. Crystal parameters, especially motional inductance and capacitance can make or break your filter. Motional inductance and capacitance describe the L and C values that make up the crystal's electrical LC model. Very large inductive and capacitive reactance values at the specified operating frequency give the crystal its extraordinarily high "quality factor" or "Q". For example, If the motional L is too low, your filter may not work as expected; providing single signal reception of WWV. The Lm was 0.02 and the Cp was 5 in the crystals which I used for my filter. In general, low Q crystals will give poor results. Oppositely, crystals with very high Q may give a lower then expected bandwidth and this may reduce AM receive fidelity. Experimentation is necessary.

Third RF Amplifier Stage and Detector

To the left is schematic of the final RF stage and the envelope detector. This RF stage has variable gain by means of a front-panel mounted 10K potentiometer which is used to vary the bias on Q5. The input Z of this stage is 100 K and is set by the Q6 gate resistor. The output of Q5 is AC coupled to a detector designed by Wes, W7ZOI. I performed considerable experimentation with basic diode detectors as well as detector source followers; some of which I sent to Wes for his consideration. He designed and emailed me back this simple, good sounding detector design which uses the gate voltage of Q7 to bias the germanium diode. Other types of diodes such as as hot carrier diodes will likely not have the output voltage of the Germanium type. Germanium diodes, when biased, had more noise and high frequency response in addition to higher output when compared to others I tried during my experiments. Diode detector guru, Felix, VK4FUQ advised me of an excellent diode he is now using called the BAT46. The audio samples of a local AM radio station using this diode and his other hi-fi lab equipment that he sent me are beyond fantastic.


3rd RF Amp + Detector
12.2 VDC
Main power buss
12.2 VDC
51
.1
.001
10K
10K
Front panel
RF gain
control
2K2
T3
0.1 poly
D1
.1
d
Q7
g
220K
s
10K
1M
To AF
amp
.001
Q5
4K7
270 -
1000 pF
(I used a
560 pF)
d
From Q3
Q6
g
s
100K
150
.1
T3 = 14 t #24 AWG on FT - 37- 43 ferrite
D1 = Germanium diode
Q5 = 2N3904
Q6 = J310 Q7 = MPF102
VE7BPO

The photograph on the right is a close up of the enveloped detector designed by W7ZOI. The germanium diode was purchased from The Source in Canada (Radio Shack in the USA). The blue, partially hidden shunt capacitor is a multi-layer ceramic 560 pF cap. The other capacitors are metalized, polyester film types. Ensure correct diode polarity.

Audio Stage

To the left is the schematic of the audio stage. The very "popcorn" LM386 AF chip is used to please the audience who complained about my AF stages not having enough popcorn factor. A 4K7 resistor was inserted between pins 1 and 8 to reduce the gain somewhat. Thus, the LM386 is still being operated in the high gain mode but won't hurt your ears with loud noise and distortion. The 470 pF cap on pin 3 may be changed or eliminated. It is a simple low pass filter.



A secondary, audio output connects to a front panel mounted RCA phono jack. This allows me to use my lab grade (KK7B AF amp) and turn the audio off on the normal receiver AF amp.

The photograph to the right is a close up of the LM386-based audio stage. This is where I started. After drilling the chassis, wiring the speaker, installing the chassis potentiometers, making the main power buss and LED indicator, the AF stage was built on the main board. The main board was then temporarily soldered in and tested. (Some connections were made via alligator clips such as the speaker wires). When the AF amp worked as expected, the main board was removed from the receiver chassis and the net stage was built. Up next were the detector and source follower. After bread boarding these, again the main board was laid in the chassis, wired, tested and then removed when all was functioning well. To test the detector I touched my finger to the input and heard local BCB radio. Following this, RF Amp #3 was added to the main board and again the main board was temporarily wired up and tested by touching the input of Q6 with my finger and observing that a local broadcast radio station increased/decreased in amplitude when the RF gain control was turned up and down. DC voltages were also measured and considered from project start to finish.



Actually, all you need to do is connect a band pass filter such as this to Q6 and the components after and you will have a nice TRF BCB AM radio. Each successive stage was built and tested, so when the receiver was finished, I already knew that it worked. I cannot emphasize enough how important it is to build your receiver backwards and test each stage as you go. There is strong temptation to start at the antenna connection and work until you get to the speaker, but please consider doing the opposite.

The bare copper wire in the photograph is the positive connection point for the speaker wire. It was trimmed somewhat during final assembly to reduce the possibility of it shorting.

Miscellaneous Photographs



The photograph above shows some of the detail of the receiver main board from the right hand side which contains the detector, source follower and audio amp stages from right to left.



The photograph above shows a top view of the main chassis and also the chassis cover with the speaker bolted on and wired up.



This wider angle photograph shows the main board from the left side. From left to right in the nearground are the SO-239 antenna connector, LC band pass filter and first RF amplifier.



The photograph above shows the speaker attached to the Hammond chassis top. Holes were drilled in the chassis lid with a drill press to allow the sound to pass through.


5 MHZ WWV
12 VDC

The photograph above shows the reverse view of the receiver chassis.

RF — Test and Measurement

Complementary-Symmetry Amplifier Biasing Basics

Introduction



This page provides information concerning the biasing of Class-AB, complementary-symmetry audio amplifiers. These schematics should be considered theoretical, as design considerations such as thermal stability, negative feedback and component power ratings are minimized or excluded for sake of clarity.

The basic 2 transistor complementary-symmetry amplifier may be used as a simple low power AF amp or as a building block for a high powered stage such as a 50 watt guitar amplifier. It is important to understand how to properly bias your AF power amps to reduce distortion and to promote easy troubleshooting when problems arise. This web page describes the hows and whys of biasing in a progressive manner with minimal math.

Discussion

Figure 1



A review of the common collector amplifier (which is more commonly called the emitter follower) is a good place to start. We may refer to the complementary-symmetry transistor pair as complementary emitter followers since they are an NPN and PNP emitter follower connected in series. An emitter follower amp is shown in Figure 1. Its properties include:

✓ input on the base - output on the emitter
✓ high input impedance and low output impedance
✓ a voltage gain of 1
✓ good current and power gain

In an appropriate configuration, these qualities are perfect for driving a low impedance load such as an 8 ohm speaker with large output currents that are not provided by our typical transistor or op amp voltage amplifier stages. In many cases, we bias the emitter follower with a voltage divider network comprised of 2 identical value resistors. In Figure 1, the voltage divider consists of a series pair of 10K resistors and thus VBias = 6 volts. These 10K bias resistors will be used throughout this web page as the circuits evolve.

In Figure 2 is a pair of complementary emitter followers which have their bases biased with our now familiar series connected 10K bias network for a VBias of 6 volts. When the power is turned on, output capacitor C2 charges through the NPN transistor until it reaches about 6 volts *(theoretical value used to keep things simple)*. When the voltage at point V Emitter reaches 6 volts, the NPN transistor goes into cutoff because VBias voltage now equals the V emitter voltage. Recall that the NPN transistor base must be positive with respect to the emitter for current to flow. Both the NPN and the PNP transistor are in cutoff. This is the amplifier's quiescent state *(assuming no signal is applied to the input via C1)* and is called Class B bias.





In Figure 3, a positive going signal is applied to the input capacitor. The NPN transistor becomes forward biased and turns ON. Current flows **through the NPN transistor** and charges capacitor C2 to a higher potential. The PNP transistor stays in cut off. The NPN transistor is an emitter follower connected to the speaker.

In Figure 4 a negative going signal the (negative half-cycle) is applied to the input. Q3 turns ON and discharges the output capacitor through the speaker as shown in **red.** The PNP transistor is an emitter follower connected to the speaker.

Thus the NPN and the PNP transistor conduct on alternate half cycles which causes AC current to flow through the speaker. The complementary emitter followers are said to be in push-pull operation.





The circuit of Figure 2 has a significant problem; output signal distortion. Silicon transistors such as the 2N3904 and 2N3906 will not conduct until their bases are forward biased by somewhere around 0.7 volts. For the NPN transistor, this means that it will not conduct until the input signal has gone positive by about 0.7 volts. Oppositely, the PNP transistor will remain in cut off until the input signal goes negative by approximately 0.7 volts. As a result, there is a dead zone during the point in time when one transistor cuts OFF and the other turns ON. Shown above is a normal sinusoidal AC waveform in red and another with the distorted waveform of Figure 2 in red and blue. This distortion is called crossover distortion because it occurs at the zero crossing point of the AC waveform. This introduces odd-order harmonics into the output signal. Such is the drawback of the Class B amplifier.



The above photograph shows crossover distortion in an under-biased power amp.



Figure 5 shows the principle technique used to reduce crossover distortion; both transistors are (slightly) forward biased almost to conduction in their quiescent state. As a result, any amplitude of positive or negative going signal will bias the appropriate transistor into conduction. An easy way to achieve this biasing is by adding 1 resistor to our 10K voltage divider network. In Figure 5 is a circuit I built, measured and listened to. R3, a 2K2 ohm resistor was placed in between R1 and R2, our usual 10K bias resistors. As a result , both transistors are forward biased.

That is: the base of the PNP transistor is negative with respect to its emitter and the the base of the NPN transistor is positive with respect to its emitter. As a rule of thumb, you need to drop at least 1 volt across R3. I chose a 2K2 resistor and it worked fine in my particular amp. The Figure 5 biasing topology is rarely used as it puts a series resistance on the PNP input among other problems; however, it exemplifies the basic principles of biasing our complimentary pair. With the forward bias on the transistor pair we now are in Class AB. The output capacitor serves to block the quiescent DC current from flowing through the speaker.



Figure 6 illustrates an improved biasing method over that of Figure 5 by using a pair of silicon diodes. You see this circuit used a lot by hobbyists. The voltage divider consists of 2 resistors and the 2 diodes. The 2 series connected diodes are connected in parallel to the NPN and PNP transistor base-emitter junctions which serves to keep the transistors turned on slightly. The net effect of the diode pair is the same as R3 in Figure 5. The voltage drop per diode was measured at 0.57 volts. The AC resistance of these 2 forward biased diodes is non-significant. There is major problem with the diode/resistor voltage divider; no way to adjust the diodes forward voltage drop. If each diode's forward threshold voltage is unequal to the base-emitter junction voltage of each transistor, either not enough forward bias is applied, or the 2 transistors may be turned on too much reducing efficiency and possibly cause excessive heating. Additionally, the pair of diodes lack the ability to provide temperature compensation when the transistors get hot.



Figure 7 shows the best way to bias our complimentary pair. Our familiar 10K-10K voltage divider is kept, but a transistor Q3 with its own biasing resistors R3 and R4 are added. You might think of R3 and R4 as a voltage divider within a voltage divider. Q3 is referred to as an amplified diode or DC level shifter. It often receives local thermal feedback from the power follower output transistors. This usually involves mounting Q3 on the same heat sink as the finals. If the output transistors heat up, so does Q3 and this results in a a smaller voltage drop across Q3 which translates into less forward bias to Q1 and Q2. Within limits, Q3 with its own base-emitter junction provides variable forward bias for the output transistors.



Shown above is the breadboard of the Figure 6 circuit built on scrap of copper clad board. Transistors were 2N3904 and 2N3906 types, diodes were 1N4148. The capacitor and resistor to the right were a low pass filter (10 ohm and 0.1 uF) to stabilize the output. The unseen speaker was connected to the red and green wires.

Figure 8



In practice, either R3 or R4 is often replaced with a trimmer potentiometer or a trimmer potentiometer is used instead of R3 and R4 and sometimes R3 and R4 are not of equal value. Shown above in Figure 8 are 3 variable bias topologies for Q3 that I have used. In some cases you will notice that the builder places a fixed value resistor or even a diode in series with the potentiometer in circuits like A or B. Using a potentiometer allows precise adjustment of the quiescent bias current and the ability to dial in the lowest crossover distortion possible. You can set the bias current using any combination of an oscilloscope and signal generator, a voltmeter, an ammeter or possibly try do it by ear when listening for and removing crossover distortion at low volume levels. The procedure I have read to adjust the bias by listening is as follows: Allow some low level signal through the amp so you can just hear it in the speaker. Turn the potentiometer from 1 extreme to another until crossover distortion is heard. Move the pot in the opposite direction until the crossover distortion disappears.
From my limited experience; in some amplifiers under 2 watts or so, you may not hear much of an audible change in crossover distortion when adjusting the bias control potentiometer, so the listening method is not useful in certain cases. It is worth mentioning, that crossover distortion sounds awful and you can usually hear it in amplifiers that are under biased.

Many builders just have a multimeter. In this case, measure the voltage drop across Q3 (the amplified diode) and ensure that is a least 1.1 volts and then slowly adjust the bias up or down from that point. Ultimately, you may have to just make the final bias setting by deciding what voltage drop across Q3 and/or what complementary pair quiescent current you want to establish. It is really not that difficult. *Whatever method you use,*

always re-check the Q3 voltage drop and amplifier bias current with no input signal to inform yourself of what is happening.
I am uncertain of the best method to measure the amplifier quiescent current, however I normally measure it using an ammeter connected in series with the emitter of the NPN transistor of the complementary pair.



Shown to the right and below are more images of what crossover distortion can look like in an under-biased power follower stage. The *right* output waveform also contains a little harmonic distortion, however that's a separate issue. I listened to this amp when connected to a speaker and music audio source; the audio had a noticeable "grungy" distorted sound. As mentioned, crossover distortion sounds terrible. The bias to the power followers (a complimentary pair of two 2N3906 and two 2N3904 transistors set up as Darlington emitter followers) was increased and the crossover distortion disappeared. A post bias adjustment audio listening test confirmed that the crossover distortion was gone.



Click for a Russian language mp3 audio file. Vladimir (Volodya), a fellow builder in Ukraine, wanted an A - B comparison of Class AB versus Class B (cross-over distortion). In this audio file, I tweak a potentiometer biasing a pair of power followers to give contrast between the 2 amplifier classes. Under biased AF amps sound terrible in any language! The audio source was a cassette player. The speaker output was recorded, digitized and stuffed into the mp3 file.



Shown above is a bread board of a complete amplifier utilizing a 10K pot to vary the bias on the amplified diode *(see Figure 8 c)*. With a 12.22 volt power supply, turning the potentiometer from one extreme to the other varied the current draw of the amplifier from about 0 to 95 mA. The average quiescent current draw of a properly biased **single complimentary pair** was somewhere between 5 and 10 mA in my bread boards.

Figure 9



You may see a capacitor inserted between the output transistor bases as shown in Figure 9A and 9B. I have seen capacitor values from 4.7 uF to 100 uF used and the value is not critical, however, from my experiments, I have learned it is mandatory. This capacitor serves to keep the bias voltage constant as the AC signal swings up and down. Some engineers refer to the amplified diode an **NPN shifter bias amplifier** or a **level shifter**. Its function is to charge up the capacitor between the bases of the power follower NPN and PNP pair to a voltage difference that establishes the quiescent current.

In 9C, R1 has been replaced with a PNP transistor which is usually forward biased by another transistor. You may observe any number of variations of the basic biasing circuit presented in Figures 6 and 7, including 3 or more small signal diodes, 2 amplified diodes, current sources, feedback loops and more. although the techniques vary, the authors are still just biasing the complementary emitter followers to achieve low crossover distortion, stability and/or thermal tracking.


Figure 10
2.81 mA quiescent
+ 14.94v
10K
0.62v
TIP 31C
1N4148
51
0v
1.22v
51
1N4148
TIP 32C
-0.59v
10K
- 14.83v
A
5.31 mA quiescent
+ 14.94v
10K
0.70v
TIP 31C
2N3904
1K
R3
51
0.026v
0.15v
1.53v
51
1K
R4
-0.78v
10K
TIP 32C
B
- 14.84v
All measured voltages are referenced to ground

Shown above in Figure 10 are 2 amplifiers using a split power supply. The split power supply offers increased headroom due to a greater AC voltage swing as well as increases the available RMS output power without using super high AC power transformer secondary voltages. In addition, the split supply works well with op amps and if desired, enables you to reduce the number of coupling capacitors by allowing direct coupling of the preamp and speaker to the power amplifier. Coupling capacitors alter frequency response and perhaps may present phase shift issues. In some cases, we as builders use coupling capacitors to provide effects such as high pass filtering, however in Hi-Fi amps, enhanced low frequency response is usually desired; which necessitates the use of high value coupling caps in single power supply amplifiers. In split supply amps, the choice of using a coupling capacitor or not is available to you. In the Figure 10 a and b circuits above, the speaker is directly coupled to the complementary emitter followers output. Note that the voltage at this point is 0 or nearly 0 volts. For any given power supply voltage you chose (split or not), please ensure the amplifier components can handle the current and subsequent heat when a signal voltage is applied. This topic is out of scope. Build and measure...build and measure...



Shown above is a breadboard of the Figure 10b circuit. Additional experiments using even higher voltages were also performed, hence the moderate power TIP transistors were utilized. I burnt up four 2N3904/6 transistors performing many experiments with biasing over 3 nights. Some of the outputs of these experiments will be presented in future projects.



Shown above in Figure 11 is a complimentary emitter follower pair directly coupled to an op amp. The amplified diode and its biasing network is inside the op amp feedback loop. There are examples of this circuit in EMRFD and also on this web site. In single supply powered op amps, it is possible to omit R1. An example of this may be found in Figure 12.30 in EMRFD. Using a low noise op amp such as the NE5532 to drive your power followers can give outstanding results.



Shown above in Figure 12 is another theoretical power amp which illustrates the building block aspects of the simple stage we have been discussing. Q4 and Q5 are cascaded with Q1 and Q2 to build up the current (Darlington emitter followers). Such an amp could have several watts of output power depending on the supply voltage. The emitter resistors on Q4 and Q5 are often 0.47 to 1 ohm power resistors.

References

EMRFD Although Rick Campbell and Bob Larsen contributed chapters and circuits, the principal author is Wes Hayward. It amazes me that any human being could know so much about electronics and is so willing to share his knowledge. Respect.

Henderson, John. Electronic Devices Published in 1991 by Prentice Hall

Oleksy, Jerome E. Practical Solid-state Circuit Design Published 1974 by Howard W. Sams and Co.,Inc

Slone, Randy G. Understanding Electricity and Electronics Published 1996 by TAB Books-McGraw Hill

Amateur and Short Wave Radio Electronics Experimenter's Web Site

Low Power Audio Amp Experiments

Introduction

This web page contains some experiments on simple, low power, speaker output audio amplifiers. Presented are ideas, some measurements and examples of audio amplifiers which will likely sound better than the IC audio chips commonly seen in many receiver projects. This web page is a follow-on to this one and is a completely new area of experimentation for me. Audio amps were built using both split and positive power supplies. In all cases the complimentary power followers were driven by an op-amp. I tried building some power amps using discrete transistor differential amplifier stages with current sources as the driver, but the noise performance and simplicity of the NE5532 or NE5534 op-amp was superior.



Split or Bi-polar Power Supply Audio Amplifiers

Figure 1

Split Power Supply



corrected Dec 16, 2009

In order to build up some split power supply amplifiers, a basic power supply was constructed and the schematic is shown in Figure 1 above. I found it was essential to regulate the voltage or hum would appear on the output. Choose a standard value fuse that is rated somewhere just above the maximum current you measure. I used 2 different AC output power transformers which were in the 18-24 volt, 375 mA to 1 amp range. The LEDS are strongly suggested. They inform you when there is power applied and their relative brightness will also often fall when higher current is being drawn on one side or the other. This alerted me to an accidental solder bridge to ground on more than 1 occasion.


G-LUXON
SM 105°C
G-LUXON

The split power supply is shown in the photograph to the left. The retro Bakelite fuse holder is from an old tube audio amplifier. If you are wondering why the copper clad board is so large, the power supply is part of a future project. Some builders would use even greater value filter capacitors than those shown. Heat sinks on the voltage regulators are required for supplying DC to higher power amplifiers.

Rod Elliot Headphone Amp


Figure 2
+15
470 uF
6K8
BD139
+0.63v
10K
1N4148
+
2.2 uF
5
+
8
4.7
1K
5532
7
0v
100 uF
0v
+
22K
6
–
4
1.26v
+
100 uF
Volume
.1
4.7
1N4148
8 ohm
speaker
1K
+
-0.62v
6K8
4.7 uF
-15
470 uF
BD140
22K
Headphone Amplifier
by Rod Elliott (ESP)
120 pF
Quiescent measurements in
red color. Stage quiescent
current was 9.5mA
http://sound.westhost.com/project113.htm

The first amp I built is shown in the Figure 2 schematic above. This amplifier was designed by Rod Elliot and is used with his permission. Rod's ESP web site is a virtual treasury of audio design information. If you are into understanding audio design, visiting his web site is strongly recommended. Rod sells printed circuit boards for all of his circuits if you prefer this building method . Note I have made some minor modifications to some part values. although primarily designed as a low distortion, high power, headphone amplifier, it drives an 8 ohm speaker very well. I was able to drive this amplifier as high as 0.68 watts average power with a pure sine wave output during analysis. Power measurement is discussed in the next section. Note that on this web page, I quote the entire stage quiescent current. Since the op-amp and the

2 (or more) power followers are a "package", it is a lot easier to just measure the current at the power supply lead(s) of the stage than unsolder and lift up a transistor lead. In this case, with no input single, the stage current was about 9.5 mA. I did check and about half the current is going to the op-amp with the other half to the transistor pair. This is a wonderful sounding amplifier and Rod has an entire web page devoted to it, so I will not comment further.

There are a variety of suitable transistor pairs for audio power amplifiers depending on the power output you are choosing. I stock just a few; BD139-140, TIP 41C-42C, NTE 128-129. The higher beta 2N3904-3906 or 2N4401-4403 pairs worked well in the low power, single power supply amplifiers shown on this web page. I also performed some higher output power experiments which required the TIP and BD transistors and these are not shown.



Above photograph. A breadboard of the Rod Elliot headphone amplifier. This early version had a temporary output capacitor. When first testing a new circuit that has a direct speaker output, it might be a good idea to temporarily use an output capacitor until you measure your voltages and current and feel your transistor temperatures. This will save your speaker if you made a big mistake and/or blow up the transistors when you first power it up.

Amplified Diode Biased Audio Amp

Figure 3


+15
470 uF
10K
NTE 128
10K
2.2 uF
+0.57v
5
8
4.7
1K
5532
7
0v
1.14v
100 uF
0v
8 ohm speaker
22K
6
4
.1
10K
4.7
-0.56v
1K
4.7 uF
-15
470 uF
10K
NTE 129
22K
150 pF
Stage quiescent current 7.8 mA
Quiescent measurements in red

Above in Figure 3 is a split power supply audio amp using an "amplified diode" to control the bias. The bias transistor was wedged between one of the output transistors and a piece of copper clad board to allow thermal tracking. The 10K bias control resistor was a trimmer type suspended over the copper clad board in most of my bread boards. Usually, you just need to set and forget about this resistor after initial set up. I adjusted the bias by watching in my oscilloscope with a low level, 1 KHz sine wave connected to the input. I measured the various voltages and stage current at quiescent and have indicated these values in red for learning purposes. The bias current range was 7.2 to 154 mA when turning the 10K trimmer pot from 1 extreme to the other. The maximal clean output average power of this amp was 0.78 watts. I used press on heat sinks for the NTE128-129 pair and they ran quite warm to touch. These TO39 type packaged transistors are somewhat difficult to heat sink compared to the TIP/BD transistor packages where you can just bolt on a heat sink of any size that is required. Please remember that the metal tab on the TIP and BD transistors is connected to the collector terminal.

In the above photograph is my first bread board of the Figure 3 amplifier. This particular version had TIP transistors, a 4 ohm speaker and an 470 uF output capacitor. Note the full size 10K bias control potentiometer on the left hand side. This was purely a experimenter's bread board, but it sounded amazing when listening to music through it.

Harmonic Distortion and Measuring Output Power



Average Power Formula

Applies to a continuous sinusoidal tone into a purely resistive load

$$P = \frac{\text{Peak Voltage}^2}{2 \times \text{Load Resistance}}$$

Figure 4

In Figure 4 is the formula used to calculate the average power of the circuits on this web page. For example if you measure 6 volts peak to peak on the oscilloscope, (3 volts peak voltage) and your resistive load is 8 ohms, the average power is 560 milliwatts. At any point in an AC waveform there is power and it may be reported using a variety of ways. Was it clean? distorted? a peak value? an RMS value? - often it is unclear.

To be clear, I measured the peak voltage on a pure, undistorted sine wave into an 8 ohm resistor. Stated power values are the mean sine wave power calculated with the formula shown. See this somewhat controversial link for details. You may not agree with my methodology, however, it allows you to compare the circuits on this web page. If you really must know the peak power, multiply the stated average sine wave power by 2. I will leave the power measurement and calculation debate up to scholars; as a lay-person, I need something simple.

The bench voltage measurement was as follows: The amplifier was connected to a 1 KHz pure sine wave generator and the 10K volume control pot was advanced just until any sign of distortion of the amplifier output sine wave appeared. Voltage measurement was taken at the point just before distortion occurred.

Heathkit
AUDIO GENERATOR
POWER
FREQUENCY
OUTPUT

It is difficult to photograph a sine wave without a tripod. Motion, the angle, light reflection and jpeg graphic compression all wreck the perfect sine wave. In the Figure 4 graphic above is a typical 1 KHz output waveform from my power amplifiers (squeaky clean) at the amplifiers maximum average power level.

To the right is a photograph of my AF signal generator. This is an old, tube device but the output sine wave is beautiful. I did not perform spectrum analysis with a computer audio sound card program and will leave this up to audiophiles. These audio amps sound great; especially when compared to the IC audio power amps that many of us tend to use in our receivers.



In the above photograph is **A**, an 8 x 1 ohm resistor load and **B**, an 8 ohm load made from parallel 1/2 watt 10 and 39 ohm resistors. In dummy load **A**, I used 5 two watt metal film resistors plus 3 half watt resistors. In the future, I will obtain 3 more 2 watt resistors and replace the 1/2 watt resistors for a 16 watt rating. For a quick resistive load, **B** is the way to go for most of the circuits on this web page.. You can make a 4 ohm load from parallel 4.7 and 27 ohm resistors. In truth, a single resistor or any combination of resistors adding up to the desired load R value will work.

Figure 5



In Figure 5 above are some scope waveforms ranging from mildly distorted to full-on dirty.

Power Amplifier Concerns

Although the amplifiers on this page are 0.15-0.8 watts or so, they can consume relatively large current compared to the usual voltage amplifier circuits we build. Some potentially helpful tips to help keep away ground loops, oscillations and thermal run away are suggested as follows:

✓ Connect your negative speaker terminal directly to the AF power amp (do not use a common ground for the negative speaker terminal).
✓ Use big power supply line bypass capacitors (no 10 uF caps here)
✓ Keep your audio amplifier copper clad board separate from the rest of your circuit boards and star ground it to your main power supply ground point.
✓ Use heat sinks on your final transistors and voltage regulator(s) when you go for bigger power
✓ Watch your layout - keep the output away from the input etc.
✓ Watch your emitter resistor power ratings in "higher wattage" amplifiers. Burning resistors stink.

Single Power Supply Audio Power Amps

Since most 12 volt power supplies are actually closer to 14 volts; these experiments were performed with a typical radio bench DC power supply at 13.69 volts.. Figure 6, 7a and 7b represent evolving experiments aimed at obtaining greater output power.

Figure 6


13.69v
Average sinewave power = 141 mW
10K (1%)
10K (1%)
470 uF
+
33 uF
1 KHz
Sine wave
10K
2N3904
10K
2.2 uF
10K
5
+
8
5532
7
6
−
4
7.59v
1 Ω
6.89v
+
470 uF
1.39v
+
100 uF
1 Ω
10K
6.20v
10
39
4K7
4.7 uF
10K
2N3906
8 Ω
load
100K
330 pF
Stage quiescent current 8.9 mA
Quiescent measurements in red

Shown above in Figure 6 is the fundamental design using one op-amp and 2 power followers. It is shown in an AC output power measurement configuration. The bias current range was about 5 to 100 mA when turning the 10K trimmer bias control pot from one extreme to the other. Maximal sine wave average output power was only 141 mW. Nevertheless, it might be loud enough for some receiver applications.
I connected this amplifier to a VCC of 15 volts. The maximal sine wave average output power was then 220 mW. In all of the single supply audio amps presented , increasing the VCC increased the maximal power output. Driving these amplifiers beyond a pure sine wave output power resulted in predictable harmonic distortion plus the re-emergence of crossover distortion in the output. This was an incredible learning; how could there be crossover distortion re-emerging in a amp that was properly biased to begin with? Increasing the bias current to the maximum level did not remove this crossover distortion. After emailing this question to Rick, KK7B and Wes, W7ZOI, and reading their replies, my best guess was that at some power level, the 5532 op-amp can not provide enough current to properly drive the complementary symmetry pair. The AC current in the output transistors may be limited by the base drive of the op-amp and they were no longer forward biased at the crossover point.



Above photograph. This is the Figure 6 amp driven past the point where the sine wave is pure. Note the crossover distortion blips on the sine wave. The base drive current for the power follower pair all comes from the op-amp. At this point there is likely not enough base drive to keep the base emitter junctions forward biased.



In the above photograph I blacked out the room and photographed the same scope waveform as above while shaking the camera from side to side. This adds some horizontal spreading of the signal and provided more information about what was happening as compared to a single,

clear oscilloscope trace.
I should mention that this crossover distortion blip occurred in all of the Figure 2 to 6 amps when they were driven past the point where a pure sine wave was seen. It is clear that maximal available power from a simple audio amplifier like this **(one NE5532 op-amp plus 2 power followers)** is constrained and thus its application is limited. Greater output power is possible using a split supply per Figures 2 and 3, however, a typical radio project has a 12 volt, single power supply. These basic amplifiers with a single power supply, may be very appropriate for projects such as a compact radio receivers or a code practice oscillator project, but not for applications where you require louder audio.



Shown above in Figure 7a is an easy method to get more output power from the Figure 6 amplifier; add another set of complimentary pair current amplifiers. I found 33-39 ohms to be a good emitter resistor value during my experiments. Many hi-fi amp builders will use greater emitter resistor values, however, a design goal was to get more output power from our 12 volt supply. Series emitter resistors are used to improve linearity and operating-point stability. I kept the final power follower pair emitter resistor values at 1 ohm to get maximal output power. An output 10 ohm + 0.1 uF low pass filter was used to help prevent oscillations in view of the low emitter resistor values on the finals.

Biasing

The top 10K bias resistor was lowered to 6K8 to facilitate "more linear" setting of the output transistor bias with the 10K trimmer potentiometer. It did not help much. Setting the bias is very delicate procedure and you must turn the screw driver very slowly. In my bread board, the optimal stage bias current was 22.3 mA but anything around 20 mA should be fine. If you do not have an oscilloscope, after ensuring that there is no input signal, connect an ammeter in series with the positive power supply lead. Turn the bias potentiometer with with the screwdriver until you get close to 22 mA. If you only have a voltmeter, the rule of thumb of 1.1 seems to work... Measure the voltage across the final 2N3904-2N3906 bases and ensure the difference is at least 1.1 volts while adjusting the 10K trimmer pot. Personally I do my biasing with an oscilloscope at at least 2 different frequencies on the signal generator, however the for mentioned methods will work okay. This is a popcorn stage and a popcorn web site after all!

For the lowest potential noise, consider using metal film type resistors in your audio amps and "polysomething" capacitors wherever AC signal is coupled to another component or ground, excluding the output capacitor.

Figure 7b


13.69v
10K (1%)
10k (1%)
33 uF
470 uF
6K8
.001
2N3904
470
**
7.43v
10K
10K
2.2 uF
5
8
5532
7
6
4
100 uF
33
1.11v
1 Ω
6.SSv
Volume
10K
2N3904
33
1 Ω
470 uF
4K7
10
8 Ω
4.7 uF
10K
2N3906
6.33v
470
.1
100K
330 pF

Quiescent measurements in red

Stage quiescent current = 22.5 mA

Average sinewave power = 406 mW

Compound pair final transistors : 2N3904/ 2N3906

** = consider heat sink

Drafting error -fixed Feb 18, 2011

Further experiments to increase output power were frustrating. Finally a compound or Sziklai pair was trialed and increased the average power to over 400 mW as shown in Figure 7b . I used a small piece of copper clad board on the finals for a heat sink, although they really didn't get that warm. Ideally, the amplified diode should also be glued onto one of the heat sink boards for thermal tracking. This amplifier is now in a chassis as a bench reference audio amp for receiver testing.



In the above photograph is the Figure 7b prototype. I am using a new miniature potentiometer for my experiments that I bought from Digi-Key. The base has 2 leads which can be soldered right on the copper clad board for easy anchoring and removal after testing.



Another view of the bread board on which the Figure 6, 7a and 7b experiments were conducted.

KK7B Headroom Boosting Emitter Capacitors

We first learned about using large value emitter caps in audio amp complimentary pairs from EMRFD. Experimentation revealed that these capacitors do 2 things: **1.** Can increase the amplifier sine wave headroom and **2.**



Add some low pass filtering. I learned from Rick, KK7B, that he designed his EMRFD amp to achieve low output power, low distortion and lower DC current drain. He desired a clean output audio amplifier for his R2 series of receivers without needing a lot of quiescent current or heat sinks on the 2N3904-2N3906 pair. The caps were added to make the amplifier think it had much lower emitter resistors at AC than the 22 ohm resistors he used in the EMRFD projects. When Rick made measurements and simulations of the amplifier, it was very stable, had low distortion and provided a very nice clean sound at all signal levels, from very weak signals in a few milliwatts of noise, to music driving the speaker. The result is outstanding and Rick's design was the catalyst for my own interest in audio amplifier experimentation.

I performed experiments with these capacitors and found that they increased my amplifier power and head room in some cases, and that the boost is indirectly proportional to the emitter resistor value. With 1 ohm output transistor emitter resistors the boost is generally not that significant. With 4.7 ohm or greater emitter resistors, they can make a big difference and you might consider trialing them for more power and headroom as appropriate. They can also add a nice, warm sound to your audio amp. Refer to EMRFD for numerous examples of this technique.

Popcorn Audio Amplifier



What follows is a popcorn or "poor man's" audio power amp using the 2N3904-2N3906 pair. To meet true popcorn criteria, all of the capacitors used in my breadboard were electrolytic and you can substitute different values from your own junk box. It would be better to use "polysomething" capacitors for the NE5532 pin 5 and 6 signal capacitors if you have them. I normally use a 1 uF to 4.7 uF poly-type capacitor in series with the 4K7 resistor on pin 6. The 270 pF feedback capacitor could be omitted or substituted with a higher or lower value to suit whatever high frequency roll off you desire.

The transistor glue-on heat sinks seen in the 1 bread board photograph are completely unnecessary. This BJT pair were used in other higher power experiments as well. The 22 uF capacitor between the transistor bases is essential from my experimentation. Without this capacitor, the amplifier headroom decreases and crossover distortion occurs. You can use the other half of the 5532 for a preamplifier or use a NE5534 instead. A 741 op-amp would be a horrible substitution. The NE5532 performance is breathtaking considering its low cost. 181 mW is surprisingly loud. All resistors are quarter watt rated. What a fun little amplifier! The schematic is Figure 8.

Figure 8


12.22v
10K
10K
10uF
100 uF
2N3904
6.11v
6.79v
10K
2.2 uF
1 Ω
10K
5
8
6.15v
5532
7
1.28v
22 uF
Volume
6
4
+ 330 uF
1N4148
x2
1 Ω
4K7
5.52v
10uF
2K2
2N3906
8 Ω
100K
270 pF
Average power = 197 mW with
a 13.8v power supply
181 mW average Power
Stage quiescent current 7.23 mA
Quiescent measurements in red


missing
10K pot

The bread board of the Figure 8 popcorn amplifier using transistors without heat sinks.

Additional Outputs


TIP 31C-32C
BD139/140
B C E
E C B


12.22v
2N3906
2N3906
100 uF
10
10
1K2
2N3904
8
7
4
1 Ω
22 uF
1 Ω
1N4148
x2
8.9mA
Current
source
2K2
2N3906

I tried putting a current source on the Figure 8 bias and it made no difference to the amplifier characteristics according to my simple oscilloscope, listening and DC analysis.

One of the full wave rectifier, voltage regulator and filter bread boards used in these experiments. I went as high as 24 VCC on some single supply amps I tested and was getting over 5 watts average output power

NPN

QRP SWL HOMEBUILDER

Amateur and Short Wave Radio Electronics Experimenter's Web Site

Two Bravo Receiver Experiments

Introduction

An experimental direct conversion receiver is presented. This 1990's style receiver was built to re-familiarize with DC receivers and try out a few new ideas. Design-on-the-bench bread boarding was used exclusively and was a pleasant way to both learn and pass time. Feedback has been received stating that that certain stages of previous receiver experiments were either too basic or too complex and thus a particular receiver was not built. This web site is as much a cookbook as anything. Kludge together whatever receiver stages you want; no project is meant to be set in stone. This receiver has a high popcorn factor with MPF102 and 2N3904s as the main semiconductors.



Variable Frequency Oscillator

Figure 1



7.000 - 7.115
MHz VFO
.001
C0G
VR1
Bottom
+
22 uF
12.24v
100
.1
L2
.001
C0G
68 pF
3K3
5 pF
C0G
10 pF
C0G
18
d
g
s
d
g
s
6-50 pF
trimmer
39 pF
C0G
15 pF
C0G
47 pF
C0G
L1
330K
36
390
100K
560
.1
25
5
8 - 107 pF
air variable
Tuning
4 - 12 pF
air variable
Band
edge
.001
C0G
100 uH
RFC

L1 = 6.1 uH = 36t on a T68-6 torroid; tap at 5 and 25 turns (used 26 AWG)
L2 = 3.6 uH = 30t on a T50-6 torroid or 35t on a T37-6
N-channel JFETs : MPF102
100 uH RFC used was wound; 38t on a FT50-61 ferrite torroid

The first stage built was the VFO shown above in Figure 1. The oscillator portion is based upon Figure 4.15 from EMRFD. The VFO resonator tank is isolated from the JFET by tapping down as shown. This is an outstanding VFO topology. See this web page for a few more details and a coil tap calculator. I favor high L to C ratios in my RF tanks, although this does not affect the VFO function. The tapped inductor in this oscillator allows you to use a high RF voltage (low C + high L) while still keeping the FET gate AC voltage at a reasonable level. The buffer amp was designed for high output power and supplies nearly 5 volts peak to peak to the product detector local oscillator port. You can vary the output voltage by increasing or decreasing the 15 pF coupling capacitor for use in other projects.
To peak the L2 tank trimmer capacitor, use a scope, RF voltmeter, or temporarily connect a 10K (or greater value) resistor load to ground via a 10 - 47 pF output capacitor and adjust this capacitor while listening with a nearby CW receiver. (Use a short piece of wire as an antenna.) Additionally, you could also peak this trimmer cap while listening to a CW signal with the completed 2 Bravo receiver. It takes around 100 pF to resonate the L2 tank at 7.040 MHz in case you are wondering.

Since air variable capacitors were used for tuning and to set the band edge, Q is high and frequency stability is excellent. My 1 hour frequency drift was 50 Hertz uncovered. The high RF energy in the tank circuit results in low noise. The L1 taps also allow the use of a 5 pF gate coupling capacitor rather than the hard to locate 3.3 pF cap used in many example VFO schematics. With different buffer/amps as required, this is now my number 1 VFO topology and it is nothing short of stellar. Note that the 100 uH RFC can be wound with 15 turns on an FT37-43 ferrite torroid, or replaced with a fixed value choke.



In the above photograph is the VFO bread board. I used 26 gauge wire for the inductor and took my time to make sure the wire was laying flat on the T68-6 torroidal core. You can pull the wire tighter if you wash your hands before winding.

Band pass Filter and Product Detector

Figure 2


7 MHz
Front end
VFO
in
15 pF
50 ohms
RF
in
47 pF
5 pF
100 pF
C1
L1
C2
T1
32
34
17
4K7
.1
d
g
s
51
.001
T2
AF
out
Low impedance
470
s
g
d
51
4.3 mA
.001
100
12.24v
+
100 uF

C1 = C2 = 8 - 70 pF trimmer cap
L1 = 4.1 uH = 32t #26 AWG on a T50-6 (T1 also)
T1 = 32t primary : 34t secondary; center tap = 17t
Q1=Q2 = J310
T2 = Audio transformer 1K : 8 ohm

Please refer to Figure 2. The second stage constructed was the double tuned band pass filter. You will need about 50-54 pF to resonate L1 and T1 at 7.040 MHz. The C1 and C2 values chosen are thus perfect for tuning the 40 Meter CW band. I peaked my particular front end filter at a center frequency of 7.025 MHz using a 50 ohm output impedance RF generator and then did some fine tuning with an antenna connected after the receiver was constructed. You may also just tune C1 and C2 for maximum signal strength when listening to band noise and QSOs. Filter bandwidth is sufficient to cover the whole CW sub-band. No AM broadcast band radio was heard during several nights of testing.

The product detector is single balanced for improved port isolation and BCB rejection. Lay out your circuit to try to achieve symmetry. The schematic calls for J310s. I built the first prototype with MPF102 that were matched for Idss. To find two with the same Idss, I had to measure 16 transistors! This is too painful, and I recommend just using a pair of J310s. The words "matched" and "MPF102" should not be used in the same sentence! Ideally, your J310s should be matched, however, the process should not take as long as for MPF102 JFETS. The choice is yours to make. T1 is a little tricky to wind, however, your best effort should be good enough.
Some builders will be unhappy with using a audio transformer (T2), however, they are still in catalogs and online stores, or can be harvested from an old transistor radio. CB radio modulation transformers are also a possible source. A higher impedance audio transformer, will likely give even more conversion gain. Without the 51 ohm drain resistors, oscillations occurred in my bread board.



Above. A temporary 5K1 (5.1K) resistor was soldered across the second tank for testing when the front end filter was designed on my work bench.

Audio Pre-amplifier


12.24v
Figure 3
47K
22 uF
All BJTs 2N3904
11.66v
11.00v
9.87v
1K
10K
100K
4K7
7.68v
22uF
5.22v
7.01v
4.56v
.068
1.94v
.082
1 uF
1.28v
10 uF
10K
22 uf
22K
10K
2K2
22 uf
Ugly Weekender AF Chain by W7ZOI; published in QST for June 1992

To match the low impedance winding of the audio transformer, a common base amp topology was chosen. I decided to use a favorite circuit; the

audio chain from the first amateur band receiver that I ever built -The Ugly Weekender. The final common emitter feedback amplifier from the original schematic was omitted as the 3 stages above provided enough voltage gain. The Figure 3 amplifier is worth studying. It is difficult to DC couple audio amplifier stages and not end up with your second and/or third stage in saturation. This example of good design by W7ZOI illustrates how to do it. The third stage, a common emitter amp is a level shifter and drops the DC voltage back down, although this stage is AC coupled to the volume potentiometer. For lower noise, you could AC couple the first common base amp to a 5532 op-amp, although, this would reduce the popcorn factor a bit. Do not expect ear blasting voltage gain from this humble circuit. It provides reasonable drive to the power amp stage.
The 0.82 and 0.68 uF capacitors shunt any detected RF energy to ground and also provide some low pass filtering. The original schematic called for 0.1 uF capacitors and which values work the best is yours to decide. Polyester film type capacitors were used in the bread board.

Photographed above is the Figure 3 bread board. You can also see the VFO buffer/amp and the audio transformer. I tried several AF preamplifiers, but preferred Figure 3 to all others.

Audio Power Amplifier


12.24v
10
12.23v
.01
100
470 uF
Figure 4
11.90v
33 uF
1K
2N3904
Feb 12, 2009
Adapted from EMRFD Figure 1.17
8.64v
2N3904
3.9 Ω
7.24v
2.72v
22 uF
12K
6.62v
3.9 Ω
470 uF
4K7
10K
1 uF
Rg
2.28v
2N3904
5.92v
2N3906
8 Ω
1K
1.35v
Volume
68
390 pF
10K
4K7
680
33 uF
16.4 ma
quiescent

Figure 4 provided 3 nights of experimentation. The base circuit for this amplifier was Figure 1.17 from EMRFD. To increase power gain and reduce harmonic distortion, Darlington configured emitter follower pairs were employed. This worked, except the power followers were under biased and had serious crossover distortion. To remedy this, the amplified diode (level shifter) bias was increased until a sine wave was seen on the oscilloscope. This was achieved by replacing the 10K resistor (R6 in the original schematic) with a 4K7 ohm resistor. The next task was to try to increase the voltage gain. Rg in EMRFD Figure 1.17 called for a 3K3 resistor. Rg was dropped to 1K; this worked. The degenerative feedback on the common emitter amplifier of EMRFD Fig 1.17 was also dropped somewhat. Next some bootstrapping feedback was AC coupled to the collector of the main common emitter amplifier. Each of the 2 collector resistor values was changed around and the outcome was recorded. Ultimately the 100 ohm plus 1K ohm resistor series pair was chosen and provided a boost of 0.85 volts peak-to-peak clean voltage gain to the output waveform. The power follower emitter degeneration resistors were also decreased from 22 to 3.9 ohms. The result is a low distortion power amp with about 150 mW of clean average power output. This receiver is not super loud, but it is reasonably loud and the audio is bell clear. If you use this amplifier stage in other projects that have a higher gain pre-amplifier, I recommend keeping Rg at 3K3 ohms as this amplifier will likely exhibit lower distortion characteristics.



Shown above is the Figure 4 bread board. A 10 ohm resistor was used to decouple this stage. Without the resistor, audio oscillations at around 850 Hz manifested when the volume was greater than about half way up. The voltage drop across the 10 ohm resistor is trivial. You may have to increase this resistor value if you experience instability. Expect all amplifiers to oscillate and decouple them accordingly. The 390 pF feedback capacitor is required. The Figure 4 amplifier exhibits greater gain as frequency increases and in a direct conversion filter with no low pass filtering, this would be very harsh indeed. Feel free to experiment with the value of this feedback capacitor. Kudos to W7ZOI for the EMRFD Figure 1.17 schematic which serves as a great specimen to inform and challenge us experimenters. The original common emitter amplifier (Q1 in EMRFD Figure 1 .17) bias current is perfect and although I tried increasing and decreasing it, I returned to the originally specified bias resistor values.

Additional Outputs


Alternate 7 MHz
Front end
VFO
in
Figure 5
100 uH
15t F37-43
AF
out
15 pF
d
51
.001
High Z
.15
50 ohms
RF
47 pF
5 pF
g
s
32
34
17
4K7
.1
470
n.c.
T2
100
12.24v
+
100 uF
100 pF
C1
L1
C2
T1
s
g
4.3 mA
d
51
.001
C1 = C2 = 8 - 70 pF trimmer cap
L1 = 4.1 uH = 32t #26 AWG on a T50-6 (T1 also)
T1 = 32t primary : 34t secondary; center tap = 17t
Q1=Q2 = J310
T2 = Audio transformer 1K : 8 ohm

Figure 5 depicts the product detector with a high impedance output. From my experiments at least, it was better to use the low Z coil for improved product detector balance and audio voltage gain.


Figure 6
12.24v
9.21v
1K
100
11.95v
22 uF
100 uF
2K2
2K7
5.19v
15K
2K2
1 uF
22 uF
5.77v
2N3904
22 uF
5.73v
6.18v
2N3904
4K7
5.07v
4K7
5.01v
1 uF
3.84v
g
d
MPF102
3.14v
s
100K
1.04v
10K
560
22 uF
1K2
22 uF
1.7 mA
2.65 mA

Figure 6: A high impedance input audio stage. The first stage is a hybrid cascode. The second stage is common emitter, common base cascode. Care was taken with transistor biasing to try to optimize distortion characteristics. Certainly, I am a total novice with such amplifiers and more time on the bench and also with computer simulation is required to better understand these amplifiers. At any rate, the schematics with DC voltages are posted for others to study and hopefully improve.


12.24v
.01
100 uF
2K2
2N3904
8.09v
7.15 mA quiescent current
3.9 Ω
6.79v
2.57v
22 uF
470 uF
12K
3.9 Ω
2N3904
6.22v
4K7
10K
5.52v
1 uF
3K3
2.15v
2N3904
2N3906
8 Ω
1.48v
Volume
100
4K7
680
33 uF
10K
150 pF
225 mW average sine wave power
Adapted from EMRFD Figure 1.17

I have 3 adapted versions of the EMRFD Figure 1.17 amplifier in my note book. This is my favorite and has the greatest clean maximum average power output of all of the 3 versions. This power amplifier somewhat lacks sufficient voltage gain for the 2 Bravo receiver (with its relatively low gain audio pre-amplifier) and thus Figure 4 was chosen as the more suitable power amplifier. You could lower the 3K3 resistor to increase the voltage gain. This circuit begs experimentation.



A couple of low pass RC audio filters were tried but later abandoned. One filter with its 1 uF AC coupling capacitors is shown in the photo above. It is quite an experience to hear an unfiltered direct conversion receiver. I love the purity. This is okay for an experimental or casual receiver, but not for a contest rig. Low pass filtering is definitely required in that context.



A different angle photo of the VFO bread board. My "build most of the project on 1 copper clad board" construction technique is not really suitable for "a keeper" receiver. VFOs should ideally be in a shielded box. Proper construction techniques and grounding ideas for DC receivers can be found in EMRFD, so they are not covered on this web page.


top
0.
dB
lot
.00
B/div.
ttom
).0
Double tuned band pass filter
Place Cursor

rt 4 Frequency MHz .5 Freq./div stop 12 C:\Doc

Cursor Data =====>: 7.025 MHz S21= -1.23

A GPLA simulation of the front end band pass filter centered at 7.025 MHz.

Amateur and Short Wave Radio Electronics Experimenter's Web Site

ICOM IC-7200 Listening Tests and Observations

Introduction

In Spring 2009, I evaluated and photographed the ICOM IC-7200 transceiver. For this web page, only its receiver was evaluated for HAM and SWL purposes by using my eyes and ears. For technical evaluation, please click on these assessments written by Adam, VA7OJ/AB4OJ or Peter, G3SJX . Additionally, eHam.net has a review web page to consult and the ARRL publication, QST for June 2009 has a review. With my modest camera and lighting equipment, it was difficult to well photograph this very dark colored transceiver indoors.

I like ICOM radio equipment and am therefore biased in my review. Please consider trying this and any other radio out before you purchase it. Our needs, expectations and budgets tend to be uniquely different. Like others, I would rather own the new ICOM IC-7600, Yaesu FT2000D or Elecraft K3, however, my budget does not allow this.

It appears that the target audience for this transceiver is as follows: portable or field/emergency communication usage and/or it is oriented towards entry level HAMs or perhaps those wishing a modern DSP-filtered back up rig. My review is from a SWL/HAM perspective.


NB
NR
ANF METER
V/M 1 1.8
A/B 2 3.5
SPLIT 3 7
MW 4 10
M-CL 5 14
AGC 6 18
COMP 7 21
SCAN 8 24
VOX 9 28
RIT · GENE
MNF 0 50
F-INP ENT BAND
P.AMP ATT
M-CH/RIT SET
M-CH MNF
RIT



General Thoughts

Although modern and stylish, this radio is very easy to use. The owners manual is well written with clear examples of how to perform the various setting changes. After reading the manual and and trying the radio buttons and knobs out, I pretty much mastered receive operation on my first night. The LCD display is small, however is reasonably adequate considering that this whole radio is compact. I believe some operators will have difficulty with this diminutive display. The S-meter is a little difficult to see. You can push a front panel button which announces the S-Meter reading, set frequency and mode in English or Japanese language if you can't quite see the display at an odd viewing angle.

The VFO knob has adjustable resolution and works well, however, it lacks that silky smooth/weighted feeling of many other radios including the R75 receiver. The ICOM engineers had there work cut out for them; include all the modern interference fighting features; place them in a small chassis; make it easy to use and come in on budget. They did it! This radio is full of useful interference management tools. One example is the (DSP) manual notch filter; it works superbly. There is no FM mode. I imagine by dropping FM mode capability , the designers were able to use the specified 6 KHz roofing filter at the second IF which has the potential to improve dynamic range at close-in signal spacing for some modes. When I started in Amateur Radio many years ago, roofing filters were never mentioned, but have become a huge marketing lever and seemingly a topic of much confusion.

DSP IF Filtering

The DSP IF filtering works very well. Does it function better than more traditional crystal IF filtering? Yes and no. It is a question of compromise for me. The greatest DSP attribute is that there are no expensive crystal filters to purchase. Additionally, you can customize the desired IF filter bandwidth (wide, medium and narrow) for each mode and also set a "hard" versus "soft" filter shape. The soft shape equates less ringing and potentially less listener fatigue than the hard setting. I have never liked listening to CW signals through stiff, 6-8 pole 250-500 Hz crystal filters on any receiver, so for me, adjustable DSP IF filtering is preferable. DSP IF filtering is not perfect as authors like Rob Sherwood, NC0B have presented, however, ICOM have a pretty good DSP platform out now and I am pretty sure their latest technology from the IC-7600/PRO 3 on down have also been used in this receiver. After all, you can always try to find an old Drake and order some crystal filters for it, or spend significantly more cash on a high-end transceiver if you need better performance.

Shown to the the left is a few front panel controls and the front firing speaker. This speaker is reasonably nice sounding. There seems to be less harmonic distortion and audio gain than the R75 receiver. The radio front panel controls are well thought out and seemed intuitive to use after reading the manual and/or just trying them out. The various hardware components such as potentiometers, rotary switches, microphone jack, PL-259 jack etc seem not to be of the highest quality. When you compare such components to that used in their older designs, there is

ICOM IC-7200
TWIN PBT
AF-RF/SQL
MIC
PHONES
MODE
TS
TUNER
FILTER
SPCH
HF/50MHz

evidence of modern cost containment. I have seen many reviews describing this transceiver as rugged. Certainly the diecast frame is solid, and I hope the forementioned hardware is as well. There is only one antenna connection. I believe that any radio offering the 6 meter band should offer two SO239 antenna connections, however, this likely would have crowded the back panel layout and increased cost for the RF in/out switching.

The VFO knob (shown to the right) looks and feels a little cheap. Functionally, however, the knob spins very well and precise tuning is easy to perform. One of my first tasks was to input various the frequencies I use for both amateur and short wave listening into the (201 maximum) memory slots. This was very easy to do and each memory channel also stores the mode and filter setting.

HF/50MHz TRANSCEIVER
MODE
TS
TUNER
FILTER
SPCH
V/M
MW
COMP
RIT
P.A
M-CH

AM Reception (R75 versus IC-7200)

The IC-7200 is a good short wave receiver. With a high quality external speaker connected, pleasant and warm sounding AM audio may be heard; however it is not Hi-Fi. That is; the IC-7200 is not an audiophile AM receiver. There is no synchronous AM detection and no 15 KHz wide IF filter for example. For AM reception, the user may choose from an 8000 to 800 Hz IF bandwidth in the 3 switchable filter settings. During testing, I set my wide filter setting to 8000 Hz, my medium setting to 6000 Hz and my narrow setting to 3000 Hz for AM reception. Of course these bandwidths can be further adjusted at any time. Local MW broadcast radio sounded great with an 8000 Hz IF bandwidth during testing. The various AM reception appropriate interference controls such as pass band tuning (PBT), automatic notch filter (ANF) and digital noise reduction are all configurable or adjustable and I found the ANF and digital noise reduction helpful when listening on the crowded 49 meter band during a rain storm.
I performed A/B comparisons with the IC-7200 and the R75 simultaneously hooked to the same antenna. For AM reception, they are comparable with the R75 having marginally better sounding (more Hi-Fi) audio. I had the R75 IF filter bandwidth set at 15 KHz and the IC-7200 IF bandwidth set at 8 KHz (both at their maximum IF bandwidth).

CW/SSB Reception (R75 versus IC-7200)

In CW mode, both were set to have a 500 Hertz IF bandwidth.(The R75 had the FL-100 model 500 Hertz crystal filter in its 9 MHz IF slot). The IC-7200 was quieter, clearer and less overloaded by adjacent stations during pile ups. There were occasionally weak signals I was able to copy on the IC-7200 that I could not even hear on the R75 due to noise. The IC-7200 is a joy to use on CW; really fantastic.
On SSB, I found both receivers fairly comparable, but the IC-7200 was better for pulling weak signals out of the noise as the noise floor was a little quieter and the audio a little more crisp. My wife also agreed with me in her "independent tests" of the CW and SSB reception. I am certain to catch flak because my subjective comments are based upon listening tests and not measurements. It is interesting to note that in almost every aspect of our lives, preferences are made using 1 or more of our 5 senses. From listening, observing and also reading the reviews of others, it seems ICOM has a hit with the IC-7200.

Mouse over the images below left to view a full size photograph

The IC-7200 in the sun.



Rear view of the transceiver.

Top angle view. There are ventilation holes at the top right hand side. You can just see the ventilation screen just next to the right top panel screw.

Reverse angle top view. The military look is attractive.

The IC-7200 and R75 side by side.

Another photograph of the 2 radios from the front angle for comparison. The LCD display size difference is quite obvious in this shot.

The receivers at a right angle. The IC-7200 is a glad update, although, I would likely not upgrade from the R75 to the IC-7200 just for receiving purposes. If I was considering choosing the IC-718 (transceiver version of the R75), the IC-7200 is worth the extra money. It is also an excellent transceiver consideration for an entry-level rig, for back up purposes. or for the budget-minded operator.

Conclusion

The IC-7200 is a serious choice for amateurs seeking a good, modern HF plus 6 Meter transceiver. It is more than adequate as an SWL receiver if you are an amateur radio operator plus SW listener like myself. Please try one out for yourself if you are considering this transceiver.

Amateur Radio Electronic Design

Electronic Hobbyist Circuits



This page will house a collection of brief hobbyist experiments.

1. Pseudo-Random Number Generator

This circuit describes a simple, 6-bit random number pseudo-generator used to study binary counters and in particular, shift registers. Some very basic background information about binary counters and shift registers is provided. In reality there are dozens of different shift register topologies available and it can get quite complex. If you wish to find a good logic tutorial website, I strongly recommend Ken Bigelow's site as it has interactive diagrams. Flip-flops are also covered well on wikipedia and many other web sites.

Binary Counter: The circuit most often used as a counter is called a binary flip-flop. The basic flip-flop can be viewed as a toggle switch having either an ON or OFF position. This is the binary state 1 (HIGH) or 0 (LOW). Like the toggle switch, the binary flip-flop has 2 binary states 1 or 0. A binary flip flop counter counts in a sequence such as 0, 1, 0 ,1 etc. A straight binary counter can be built by using 1 or more flip-flops connected in a manner that the binary number stored in these flip-flops will represent the total number of trigger pulses received at the counter input.

Ring Counter: A ring counter has 2 or more flip-flops cascaded so that the output from one flip-flop becomes the input of the next flip-flop. The flip-flops are connected so that all of their outputs are at the binary state 0 except for one flip-flop. By pulsing the input of the ring counter, it will sequentially change the binary state of the succeeding flip-flop from binary 0 to binary 1. The flip-flop that contains the binary 1 indicates the count of this binary counter. The maximum number of pulses that can be counted by N flip-flops is N pulses.

Shift Register: A serial entry shift register is similar to a ring counter, except that the output flip-flop is not connected to the input flip-flop. Like the ring counter, the flip-flops are cascaded so that the output from one flip-flop becomes the input of the next flip-flop. All the set trigger and reset trigger inputs are tied together to form what is called a shift bus. Clock pulses are applied to the shift bus to cause the stored binary information to shift from left to right; one bit position per each received clock pulse. In Figure 2, this serial input/output + parallel output register has its 5th and 6th bits exclusive ORed to the serial input to form a pseudo-random sequencer, which is called a pseudo-random number generator by some.

The CMOS logic ICs used were one 4070 XOR (Exclusive OR) and three CD4013B D flip-flops. Junk box LEDs were used to observe the binary state of the clock and each of the 6 bits of the shift register.


Figure 1

12 VDC
4070 XOR
.1
2
3
1
7
13
12
11
6
14
5
4
+
10 uF
Clock
output
1M
100K
1K
14
13
12
1
2
3
"dead bug"

Since only one XOR gate is needed for the shift register, the remaining gates were configured to make the clock. These gates are essentially wired up as inverters to form an astable multivibrator with a frequency of about 0.45 Hertz or 27 pulses per minute. Shown above in Figure 1 is the clock schematic and the pin 1 marking for all of the digital ICs on this web page. The output LED is not mandatory, but will instantly tell you whether or not your clock is working. I built this whole circuit using Ugly Construction with the ICs flipped upside down in a "dead bug" fashion. You can increase the clock speed by decreasing the 100K resistor or the capacitor values. F Hertz = 1/ (2.2 * R * C) with R in ohms and C in farads. The slow clock speed was chosen to better observe the digital output of the shift register.


Figure 2

12 VDC
1K
1K
1K
1K
1K
.1
14
14
14
5
D
Q
R
S
1
9
4
10
6
8
3
7
11
13
Clock
1K
10
9
8

D Flip Flops = CD4013B
XOR gate = 4070

serial in/out, parallel out 6 stage shift register with XORed 5th & 6th bits

In Figure 2 is the shift register. Each 4013 was wired up as 2 cascaded flip-flops and connected to the clock. Power was applied and then a test lead was used to bring pin 5 of the first flip-flop HIGH (connected to 12 volts for 1-2 seconds) . Both flip-flop state monitor LEDS turned ON in sequence with subsequent clock pulses. Afterwards, pin 5 was set LOW (shorted to ground with a test lead for a couple of seconds) and each LED turned OFF in sequence with subsequent clock pulses. The remaining two 4013s were wired up and tested the the same way and then finally the last XOR gate was wired up.

To avoid error, frequent pin counting and a systematic approach is recommended. For example, for each 4013, I soldered the ground pins, wired the pin 14 VDD, connected the clock to pins 3 and 11, then wired up the pin 1 and pin 13 LEDs. Systematic construction techniques are something that you the experimenter can develop and perfect over time. This approach saves time and grief. On some projects, when you have a lot of pins wired up, tracing and repairing an early mistake can be difficult.



Shown above is a bread board of the entire pseudo-random number generator. I just built in on a scrap of board and did not lay it out so the LEDs were in a row, as I am not going to keep this project. The clock state monitor is the green colored LED. There are 63 possible states or combinations of the 6 bits (111000, 100110, 100101, 000101, 000001 etc.) State 000000 is disallowed and will hang up the shift register. If your clock LED is flashing and no shift register LEDs are lit, then "reset" by momentarily setting pin 5 of the first flip-flop HIGH (momentarily apply 12 volts). Long live the reset switch!

Pseudo-random numbers are now mostly generated by computer microprocessors controlled by software and have applications in cryptography, electronic music, security and many other applications. This "hardware" pseudo-random number generator experiment was really cool and if you want to randomly flash some LEDs, this could be the project to use!

If you are new to digital electronics; (like me) Welcome! Starting small with projects like this one will hopefully lead to increased confidence and problem solving skills for even bigger projects. You can also build the shift registers with J-K flip-flops, but it is more difficult and 4013s or other series D flip-flops are cheap as Борщ (borscht).

Figure 3


1
2
3
4
4 stage
1
2
3
4
5
6
6 stage
1
2
3
4
5
6
7
8
8 stage

Shown above in Figure 3 is how to hook up the XOR gate(s) for 4, 6 and 8 stage pseudo-random number generators. The 6 stage shift-register is of course, Figure 2 above and is presented for reference purposes. The 8 stage version = 1 byte.

2. One Hertz Precision Time Base

Digital clocks are very interesting. In the past 6 months, 10 -15 RC clocks have been constructed and tested. RC oscillators in the KHz to Hertz range are surprisingly frequency stable. For many projects, a plain RC clock is adequate, however, like in radio design, a crystal controlled time reference is sometimes required. Two examples of projects requiring precision clocks are time of day clocks and frequency counters. Presented is a 1 Hertz clock built from two 4000 series CMOS Logic ICs. Here is a great 4000 series tutorial with pin outs and more.

Figure 4

One Hertz Clock


L78L05
Bottom
12v
5 v
.001
22 uF
+
330
16
14
6.5- 50 pF
10M
32768 Hz
330K
15 pF
C0G
11
10
12
8
4060
3
9
2 Hz
3
5
CLK
D
4013
R
S
Q
Q̄
1
2
4
6
7
1 Hz
output
220

12. 5 pF load capacitance crystal

Shown above in Figure 4 is the complete schematic with an output LED for testing. In the past, the MM5369 17 Stage Oscillator/Divider was popular for hobbyist precision time bases, however, it has gone obsolete. The 4060 ripple counter is a good "modern" replacement, although a different crystal is required. A 32768 Hertz crystal was used and is divided 16384 times to provide a 2 Hz output. The 4060 then drives a 4013 D Flip-flop configured as a divide by 2 to provide a 1 Hz output frequency. Key parts references may be found on the Webmaster's page.



Shown above is the frequency and output waveform when a frequency counter and oscilloscope are (respectively) connected to pin 9 of the 4060 in Figure 4. The 6.5-50 pF trimmer pot is used for calibration. Originally, I used a trimmer cap instead of the fixed 15 pF capacitor shown between the 330K resistor and the crystal. After adjusting this trimmer capacitor for the best looking waveform, I removed the trimmer cap and measured it at 13 pF. I substituted the nearest standard value I had in my parts collection; 15 pF. It was interesting to measure the 4013 output frequency at 1 Hz.



A close up photo of the 4060 oscillator/divider breadboard. The 10M resistor used was a 1/2 watt rated R as I have dozens of these in my parts collection. You can see the tiny cylindrical crystal just above and left of the orange Murata trimmer capacitor. It is oriented horizontally. This is a useful time base for the QRP workshop.

3. 10000 and 5000 Hz Multivibrator Clock

It is fun to occasionally build circuits using discrete semiconductors rather than with ICs. A 5000 Hz digital clock was needed for an experiment. It was decided to use multivibrators for the basic oscillator and a divide by 2.



Figure 5

Figure 5 is the entire circuit. The tuning range of the astable multivibrator was about 7060-10650 Hz. The 5K pot was slowly adjusted until 10000 Hz was measured in a frequency counter. Following testing of the astable multivibrator, the flip flop was built and examined. Astable multivibrator function has been discussed previously on this web site.

Please refer to the bistable multivibrator. It is a one input circuit set up for toggle or flip-flop operation. Negative edge pulses applied between the two 0.001 capacitors will cause the binary state of Q1 and Q2 to change to the opposite state. The multivibrator circuit is made up of Q1, Q2 and the 47K and 1K base and collector resistors respectively. The other components D1, D2, the RS resistors and CS capacitors comprise a steering circuit to generate the proper response to the negative edge pulses. When a negative input pulse arrives, it is guided to the base terminal of the ON transistor, but prevented from reaching the base terminal of the OFF transistor.

In order to study this circuit at DC, I temporarily exchanged the 0.001 timing capacitors in the astable multivibrator with some 22 uF electrolytic caps to slow it down. Referring back to the bistable multivibrator, let us assume that Q1 is OFF and Q2 is ON. The collector voltage of Q1 is high (cut off). The collector voltage of Q2 is low (saturation). The Q1 collector is connected to the cathode of D1 by the 100K RS resistor. The cathode of D1 is reverse biased by the high Q1 collector voltage and also because its anode is held close to 0 volts by the 47K resistor connected to the collector terminal of Q2. It would take a very strong negative input pulse to forward bias D1 enough to reach the Q1 base terminal. The Q2 collector voltage is nearly 0 volts and therefore the D2 cathode has little to no reverse bias voltage via its RS. Thus, any small amplitude negative input pulse will cause D2 to become forward biased, reach the base of Q2 and drive Q2 OFF. Once Q2 switches off, in turn Q1 is toggled ON and its collector voltage goes low. The large reverse bias on D1 disappears. However, Q2 is now OFF and D2 will now be strongly reverse biased which will steer the next negative input pulse to the base of Q1. This is the basis of the circuit's negative edge flip-flop operation.

In another experiment, I changed the .001 C0G capacitors of the astable multivibrator to 470 pF. This gave a usable range of 22968 to 14832 Hertz (11484-7416 Hz at the Q1 and Q2 output) . Looking at the output of the flip-flop in the oscilloscope; at the higher frequency range, the flip-flop could not keep up and failed to divide by 2. I found experimentally that the time constant of each of the CS and RS components seemed to be the problem. When the CS capacitors were also decreased to 470 pF, the flip-flop worked properly.
As you increase the flip-flop operation frequency, speed up bypass capacitors might also be required across the 47K base resistors of Q1 and Q2 . A suggested starting value to try is 220 pF. Some builders also bypass the resistors in the RS steering circuit at higher frequencies, however, this is getting a little crazy. It is really important to look at the output waveform in the oscilloscope to ensure reasonable performance.



Shown above is the Figure 5 breadboard prototype.

Figure 6



5 KHz output waveform of Q2

4. One KHz Digital and Analog Oscillator

A 1 KHz oscillator with 5 volt digital outputs 180 degrees apart and an analog output was sought. The frequency had to be near to, but not exactly 1000 Hertz. A major question to answer was how much low pass filtering is needed to remove the odd harmonics from digital circuits?


Figure 7
12v
L78L05
Bottom
5v
.01
22 uF
TC74AC00
1
2
3
7
4
5
14
6
9
10
8
12
13
1K5
12K
2.002 KHz
.022
1,4,10,12,14
3
74HC74
Q
Q̄
D
2
5
6
7,11,13
A
Digital
B
1.001 KHz
10K
10K
22 uF
100
22 uF
10K
1 KHz Oscillator
.1
A or B
1 uF
2K2
2K2
.047
5
8
7
6
4
5532a
2K2
2K2
.1
3
2
1
5532b
.047
Analog
1 uF
1 KHz low-pass filter

Figure 7 shows the complete schematic. NAND gates from a 74AC00 were wired as inverters and with the 13.5 K resistance and a 0.022 uF polyester capacitor, the frequency was 2002 Hertz. To improve the digital waveform and get the desired 2 outputs, a D flip-flop was used. The output frequency was 1001 Hertz. The digital part was completed!

For the analog filtering, active low-pass filters were tried, and in total 4 poles with a 1 KHz cuff off worked reasonably well. The filter uses the 5532 op-amp with common vales capacitors and resistors. Poly"something" caps were utilized.

Figure 8



In Figure 8 is the output waveform of the low pass filter stages. A pretty nice sine wave was achieved and this oscillator could see duty for testing audio amplifiers. The scope was photographed at an angle to avoid the camera reflection and this distorts the sine waves a little.


12v
L78L05
Bottom
5v
experimental circuit
.01
+
22 uF
TC74AC00
1,4,10,12,14
1
2
3
7
4
5
14
6
9
10
8
3
74HC74
Q
5
D
Q̄
2
6
7,11,13
12
13
1K5
12K
2.002 KHz
.022
22 uF
+
100
.1
.1
2K2
2K2
2K2
2K2
.047
.047
5
8
7
6
4
5532a
3
2
1
5532b
Analog
1 uF
1 KHz low-pass filter

Figure 9

Figure 9 depicts an experiment with the op-amp biasing. If the op-amp is run at 5 volts VCC, the bias requirement is 1/2 VCC or 2.5 volts. The DC voltage at the output of the D flip-flop was 2.55 volts. The 2K2 resistor was connected directly to this output and this eliminated the VCC/2 resistor bias network and a coupling capacitor.

Figure 10



Figure 10 shows the output waveform of Figure 9. The AC waveform has harmonic distortion and thus the Figure 9 circuit will not be kept nor utilized.



The Figure 7 breadboard. A 0.39 coupling capacitor (not 1 uF) was used between the D flip-flop and 5532a in this particular version. Unfortunately, no 0.047 uF caps were available for the low-pass filters and therefore a 0.039 plus a 0.0082 were placed in parallel for each of the .047 uF caps.

5. One KHz Low Distortion Signal Generator

Although I own a variable frequency wein bridge oscillator, it has been been set to 1 KHz for 2-3 years and is large and temperamental. It was decided to make a low distortion sine wave oscillator for just this one frequency. The circuit will be placed in a box along with another signal generator.

There are a number of ways to build signal generators using op amps. Countless example circuits may be found on the World Wide Web and some of them are really fantastic. Chose whichever method works best for you. Some might find my circuit to be overkill, but to each his own.


Low Distortion 1018 Hz Signal
12V
10K
33 uF
100 uF
100
100
22 uF
33 uF
10K
Tuning Rs
6K8
820
6K8
820
Tuning Rs
.1
.1
.022
.022
5532a
2K2
2K2
5532b
2K2
2K2
.047
.047
5532a
3
8
1
2
4
5
7
6
3
8
1
2
4
6K8
820
150K
1N4148
forward matched
diodes @ DC
1 KHz low-pass filter
R1
R2
R3
2K2
15K
2.2 uF
10K
2.2 uF
5
7
6
5532b
R4
2.2 uF
100
gain
Figure 11
27K

Figure 11 shows the entire circuit. The Wein bridge oscillator is from EMRFD and was designed by Wes, W7ZOI.

A 0.22 uF capacitor was chosen for the tuned circuits. Using resistors from my parts collection, 1018 Hz was the closest I could get to 1 KHz. This is the 6K8 + 820 ohms resistors labeled "tuning Rs". Other values were tried. For example, a single 6K8 gave 1142 Hz and a single 8K2 gave 939 Hz.

When the circuit was first built, I used a 10K on the VCC/2 bias point to pin 2 and a 22K feedback R from pin 1 back to pin 2. The sine wave had mild distortion. By experimentation, it was learned that the resistance from the VCC/2 bias point to pin 2 significantly affected the waveform purity. The 2K2+15K plus the R1 + R2 resistance values shown were determined by using a potentiometers rather than fixed resistors. Care was taken to adjust the feedback resistance from pin 1 back to pin 2 to keep away any overdrive distortion. I do not understand this, but even changing the 820 ohm R2 to 570 ohms, altered the sine wave purity.

The best looking sine wave came when the resistance from the VCC/2 bias point to pin 2 was the same as the tuning resistance; 6K8 plus 820 ohms. Later, the pin 1 to pin 2 feedback resistance was chosen for an unclipped; waveform with a reasonable output voltage using a potentiometer. The potentiometer was removed and measured at 17.1K, thus the 15K + 2K2 were soldered in. It was also discovered that by increasing R3 from 56K or 100K to 150K slightly improved the waveform.

The Figure 7 low-pass filter was connected to the main oscillator as shown. The final op-amp stage was used as a buffer between the low-pass filter and the gain control. R4 is used to set whatever output impedance you choose. Practically speaking, it could be any value between 47 and 620 ohms. Many AF oscillators have an output impedance of 600 ohms and 620 is the nearest E24 standard value. For my project, a 100 ohm

R4 was chosen. Output peak to peak voltage is 0.0 to 4.84v continuously.

Figure 12



Here is the raw output of the basic Wien bridge oscillator. It is hard to photograph well, but it is stellar to say the least.



The Figure 11 breadboard mounted in a plastic Hammond chassis. The voltage regulator seen to the left of the bottom polyester cap is a 7812. This project has its own regulated power supply. Other view of Fig 11. Two 10 Megohm standoff resistors were used to help support all the resistors soldered to pins 1, 2 and 3 of the main oscillator.

1018 HERTZ
OFF
GAIN

A front view photo of the AF oscillator. A separate 7 plus 14 MHz oscillator circuit and controls will be placed on the right hand side of this box. The orange power ON indicator LED was epoxy glued into the chassis hole. Putting circuits in cabinets is one of the most expensive aspects of homebrew construction. One must be ever vigilant for bargain chassis boxes and hardware to keep costs down. Techniques such as gluing in the LED rather than purchasing a separate holder and recycling knobs and switches are also practiced for cost containment.

Figure 13



The output of Figure 11 is shown in Figure 13. This is the best sine wave seen ever on my scope. I looked at it closely and there is no change in line thickness or symmetry anywhere. It inverts with no change on the scope. Testing audio amplifiers will now be much more fun.

6. LM386 Power Experiments

The LM386 is an IC audio amp that has been used in thousands of hobbyist projects over the past 2 decades. By adding a capacitor +/- a resistor between pins 1 and 8, this device's internal gain can be changed from x20 to up to x200.


12.24v
Figure 14
10
100 uF
+
4
3
in
LM386
6
5
2
8
1
470 uF
+
10
8 Ω
.1
+
10 uF

Test circuit schematic in Figure 14.


low
TEKTRONIX
010-161

The experiment breadboard is shown above. A very standard configuration. The amplifier drove an 8 ohm, 1 watt resistive load.



Figure 15

Over the years, I have noticed some kit sellers and project authors claiming that their LM386 based AF stages gave 1 or occasionally even 2 watts of output power into an 8 ohm speaker. This was confirmed on the bench. This device will output 1 watt into 8 ohms at 1018 Hertz with little problem. However, this is clearly 1 watt of square wave distortion.

The quiescent current of the LM386 was around 7 mA. The signal generator gain was increased until the first signs of distortion appeared. The gain was then backed off a little so a pure sine wave was observed in the oscilloscope. The current was ~ 155 mA and the measured power was 289 mW. Please refer to Figure 15 for the 289 mW sine wave. This was the clean signal power of the LM386 on my bench. The output waveforms at 563 mW and 1 watt are also shown. Extreme harmonic distortion occurred above 300 mW. This device will draw 240 mA or more when driven and clipping hard. It is not my intention to malign the LM386. It is a useful part, albeit a little dated. Its AF gain capability versus size is something to behold. Many builders have moved to the TDA7052 audio amplifier IC, or like myself, build their own low noise audio power amps.

1018 HERTZ
OFF
GAIN
ON
12.2 VDC

The 12.24 volt DC supply and the 1018 Hz AF audio oscillator used in these experiments.

SWL HOMEBUILDER

RF — Test and Measurement

Time Domain Output from a Diode Ring Mixer

22 Dec 2009, w7zoi


BPF 7-7.3 MHz
N=3
IL < 2 dB
1.5 MHz
LPF
N=5
.05 dB Cheb.
500 KHz
LPF
for
NDB
7.5 MHz LPF
0.07 dB Cheby
IL = .11 dB @ 7
11 Nov 98
N=7 14 MHz
LPF
MED. PWR
SBL-1 WH
L
I
R
RECYCLED

Figure 1. Some available experimental modules.

Some folks wonder about the output that they should see on their oscilloscope when looking at the output from a diode ring mixer. There is no set, pat answer. The output can change dramatically as levels, frequencies, and even terminations are changed. This complication is illustrated here with a few screen shots, taken with a Rigol DS1052E 50 MHz bandwidth digital storage oscilloscope. The experiments started with the following pile of modules. Your collection will probably differ.



Figure 2. The inside of the module containing a Mini-Circuits SBL-1 diode ring mixer. This is a standard part that is essentially generic.

The first experiment was to set up a pair of 10 MHz signal sources. One was from a homebrew generator, shown below.

Figure 3


RIGOL
STOP
T
1 -40.0mV
T 10.0551MHz
1
Vpp(1) = 1.54V
CH1 500mV
Time 20.00ns
T→0.0000s

Figure 3. The 10 MHz signal from a homebrew signal source. The 1.54 volt peak to peak signal is applied to a 50 Ohm terminator at the oscilloscope. The delivered power is then +7.7 dBm.

This signal was filtered with a 14 MHz low pass circuit. This caused the amplitude to drop by 0.2 dB. The source was then attached to the LO (local oscillator) port of the SBL-1 mixer.

Figure 4


RIGOL
STOP
1 -12.2mV
T <5Hz
1
Vpp(1)=2.24mV
CH1 2.00mV
Time 20.00ns
T→0.0000s

Figure 4. The IF output from the mixer when there is nothing attached to the RF port. Note the scope sensitivity of 2 mV/div.

Next, we attached a 50 Ohm terminator to the R mixer port.

Figure 5


RIGOL
STOP
1 -12.2mV
T <5Hz
1
Vpp(1)=4.08mV
CH1 2.00mV
Time 20.00ns
T→0.0000s

Figure 5. The IF output with LO drive, but without an R signal. But the R port is now terminated. This waveform, when compared with Fig 4, shows just how sensitive the mixer can be to termination.

In the next experiment, a -20 dBm signal was applied to the R port. The frequency was very close to the 10 MHz LO that is still present.

Figure 6


RIGOL
STOP
1 -40.0mV
<5Hz
Vpp(1)=27.6mV
CH1 10.0mV
Time 2.000us
0.0000s

Fig 6. There are two dominant signals from the mixer. One is a low frequency at 100 kHz. But this is accompanied by a high frequency of about 20 MHz. These two outputs, a sum and difference frequency, are expected from any mixer.

A filter can isolate the two dominant outputs. This is shown below where a 500 kHz low pass filter is inserted in the line between the mixer and the oscilloscope. A 6 dB pad is between the mixer and the filter, for direct insertion would upset the termination of the mixer.

Figure 7


RIGOL
STOP
1 0.00uV
98.8504kHz
Vpp(1)=15.2mV
CH1 10.0mV
Time 2.000us
0.0000s

Figure 7. The output of about 100 kHz after a low pass filter is inserted in the mixer output.

The next experiments emulate a SSB transmitter. We start with a signal at 11.06 MHz with strength -20 dBm. (This is a common IF used in homebrew SSB transceivers such as the BITX-20.) This is applied to the mixer R port. The L port is driven with a +7 dBm signal at 3.19 MHz. The LO signal is low pass filtered to attenuate harmonics, a measure that is probably not necessary, but the filters were there. The IF output is shown below.

Figure 8



Figure 8. Time domain output of a SBL-1 set up as the “transmit” mixer in a SSB rig. This is far from the “perfect sine wave” that some folks tell us we should observe. This waveform contains many different frequency components. The counter output should not be interpreted to have any meaning. (I should have turned it off.)

The signal of Fig 8 can also be viewed with a spectrum analyzer. This is shown below. This measurement was taken with the August 1998 QST Spectrum Analyzer and not the FFT routine in the DSO. The Rigol scope has a nice display for an analyzer.

Figure 9



Figure 9. Spectrum of the signal shown in Fig 8. The largest signal on screen is that at the left, which is the spectrum analyzer zero spur. This is a spurious output that is typical of most SA systems. The desired signal at 11.06+3.19=14.25 MHz is just to the right of center. But the image is also present at the different frequency of 7.87 MHz at about 3 major divisions from the left edge.

Alas, I didn’t find a 14 MHz bandpass filter in the junk box. Such a filter would have allowed selection of the dominant 14 MHz component while attenuating all the rest of the junk shown. The many other signals are the result of harmonic mixing. That is, we observe IF outputs at N x FLO +/- M x FRF where N and M are integers. Some of these spurious outputs can be quite strong with diode ring mixers. They are best avoided with high frequency LO signals. In this case, a LO at 14.25+11.06=25.31 MHz would produce a much cleaner output spectrum. It is much easier to obtain LO stability with an oscillator built at 3.19 MHz.

Bottom Line

It is not reasonable to have a well defined, predictable time domain (i.e., normal oscilloscope) output from a mixer. The exact results depend upon too many variables. A spectrum analyzer can be used to garner much more information.

RF — Test and Measurement

Low Noise Crystal Oscillators

Introduction



Some experiments were conducted to build a low noise crystal oscillator with 50 ohm output at 7 and 14 MHz for the test bench.

Some readers might wonder why build such an oscillator? Although a variable RF signal generator is an important bench tool, it is also nice to have a fixed frequency signal source on your favorite HAM band. This RF source can be connected to other 50 ohm modules such as band-pass filters, diode ring mixers or feedback amplifiers to conduct experiments at a whim. The project goal was a low noise oscillator with 2 outputs so it could drive a divide by 2 flip-flop for 40 meter band digital mixer work, or fundamental frequency use on the 20 and 40 meter bands.

Presented are some experiments carried out to realize this goal. Only some of the better experiments and circuits are shown. An additional circuit was added Jan 31, 2010.

First Steps


Figure 1
9v
To transistor base
.1
7.040 MHz
51
-1.7 dBm
330 pF
12
A
12v
100
.1
T50-2
40
10 pF
2K2
6
50 Ω
6.5-50 pF
33
B
560
RX
.1
1K5
6K8
.1
2K2
100
12v
.1
82K
7.040 MHz
.1
C
51
390 pF
22K
6.8 dBm
4.3 uH
29t T50-2
10-265 pF
C tune
12
220 pF
1K
.1

The 7.040 MHz crystal used is an AT cut, HC6-U holder part made locally by West Crystal. I reviewed the information concerning crystal oscillators in Chapter 4.5 of EMRFD and then started melting solder. The oscillator output was extracted as described in EMRFD Figure 4.24. The output is low distortion, low impedance and low gain. Like in most experiments, I built it, measured the DC voltages and then looked at the AC voltages in the oscilloscope.

In order to measure the output, a 51 ohm load was transformer coupled as shown in Figure 1a. I am uncertain if this was a good method for power measurement, however, it allowed comparison of the experimental circuits. As shown, the output with a 9 volt regulated power supply is low; -1.7 dBm. Still, a circuit like EMRFD Figure 4.24 can be used with a variety of crystal frequencies and has great utility.

Figure 2



Signal from BJT emitter

Signal from between cap and crystal

Figure 2 shows two output waveforms taken from my crystal oscillator. When a signal is taken from the emitter of the main oscillator transistor (what we typically do) harmonic distortion occurs as shown in the above left. Actually, the distorted waveform photo above left looks better than most do. Typically, they look like this. Many builders will just place a low pass filter on such an oscillator's output and be very satisfied with the harmonic content in their signal. Certainly this is a good, common and practical way to go. However, for some builders, the experimenter's journey is what counts. That is, the fun and learning occurs during designing/building/testing and not just operating home built gear.

When the output is taken from between the shunt capacitor and the crystal per Figure 1A, a much cleaner sine wave is available. The photo above right tells this story. The focus of all of the experiments on this web page is boosting this lower distortion, lower phase noise signal into something useful. To increase the base oscillator output voltage, the VCC was raised to 12 VDC and the BJT emitter circuit was tuned per Figure 1C. Resident on my work bench are a few potentiometers and a 10-254 pF air variable capacitor with short attached leads. These parts are inserted into test circuits to allow tweaking of R or C as desired. Once the desired tweaking is performed, the potentiometer or variable capacitor is removed and measured. The closest fixed value R or C is then substituted as appropriate. In this experiment, the highest output voltage occurred when the variable capacitor measured 181.7 pF. Thus in my version, 33 pF and 150 pF capacitors were placed in parallel and are shown later in Figure 3.

The Figure 1A output transformer circuit was again used and the power output was 6.8 dBm. Being tuned to 1 crystal frequency is the biggest drawback of the 1C circuit. Tuning a crystal oscillator as described earlier is easy to do however.

The next task was to design and build a buffer/amplifier. To match the low impedance of the Figure 1C crystal oscillator, a common base amp was built. The circuit was morphed over time, however, the initial design is shown as Figure 1B. It was interesting to note that a series resistor (RX) is required to keep the waveform pure. Any RX value less than 470 ohms compromised the sine wave purity. The 560 ohm R shown was perfect, however, as expected, attenuated the oscillator signal. In order to get a decent output voltage, the common base amp had to be run at 5 mA or greater current and ultimately collector tuning was added to try and realize an output voltage greater than 4 dBm.

Through experimentation I learned that adjusting Fig 1B's tuning, emitter current and RX value all could distort the output of the main oscillator at certain values or settings. Running high current also invites parasitic oscillations and soon it was realized that common base was perhaps not the best choice (at least for me) as another separate amplifier stage would be required to get a decent output voltage with or without an attenuator pad.. After trying a number of different buffer-amplifiers including a 50 ohm feedback amp, I chose a favorite circuit which I know has excellent gain plus back to front isolation and would not distort the oscillator waveform; a lightly coupled JFET amp.

---

7 MHz Circuit


12 VDC regulated
.01
100
100
.1
Figure 3
.1
100 pF
to 14 MHz circuit
T1
L2
18
3
1K8
39
Q1
82K
Y1
33
←150→
- 6 dB
50 Ω
390 pF
390 pF
5 pF
390 pF
22K
d
g
s
Q2
L1
100K
220
33 pF
C tune
150 pF
C tune
220 pF
1K
.1
Is = 7 mA
L1 = 4.3 uH = 29t T50-2
L2 = 1.1 uH = 15t T44-6
T1 = 18t : 3t FT37-43
Y1 = 7.040 MHz
Q1 = 2N3904
Q2 = J310

In Figure 3 is the complete schematic of the 7 MHz portion of the low distortion crystal oscillator. The output was 0.52 dBm. A 6 dB 50 ohm pad ensures a well-buffered 50 ohm termination. This aids in calculating gain or loss in circuits it drives. You could easily decrease this to a -3 or -4 dB pad. This reflects the wisdom handed down by our mentors who encourage building RF stages in 50 ohm impedance blocks. A Q2 source bypass capacitor was not placed as it increased harmonic distortion in the output signal. The output is filtered with a simple pi filter. The 100 pF coupling capacitor connect this circuit to Figure 6; the 14 MHz circuit.


L/C Meter IIB
Lx= 1.150 µHy
ZERO
INDUCTANCE
Short circuit test leads

L2 was wound and measured. It is desirable (but not absolutely necessary) to perform measurement on powdered iron toroids to compensate for variations in wire spacing and toroid permeability. I used a T44-6 core; use whatever appropriate powdered iron toroid you want.


GPLA
File
About GPLA
GPLA - 2002
Click to Review Circuit
S21 =
S11 =
S21 Ref.
dB
Plot
Figure 4
Enter new value and Click
Frequency
Place Cursor
Drag a box on graph to Zoom
Zoom to Original Sweep
Save S21 as Ref.
Plot Referenc
Value Tune Mode
Up
Down
Value=
Reset Cursor

0 Load R = 50.0
1 cap par 390.00
2 ind ser 1100.00
3 cap par 390.00
98 Source R = 50.0
99 Inductor Q = 225.0

top 0.

10.000 dB/div.

bottom -60.0

start 6 MHz

Freq./div 10

stop 100

C:\Todds\QRPHB\QRPHB\aa-fall 2009-20

N (index) 99

NewValue 225

Cursor Data =====>: 11.640 MHz

S21= -3.12 dB

S11= 0.00 dB

☑ Plot S11

☐ Plot Referenc

NR= 2

%= 5

A GPLA analysis of the Pi low-pass filter is shown in Figure 4. The basic circuit was designed with PI Filter Designer on this page and tweaked in GPLA. You may wish to omit this filter or perhaps design a better one yourself.

Figure 5



-0.52 dBm, 0.88804 mW

The 7 MHz output waveform on the Tektronix (left) and the Rigol oscilloscopes. On the Tek scope, the output power was 0.50 dBm and on the Rigol scope it was 0.52 dBm. The Rigol is an amazing oscilloscope, but only has 256 horizontal lines of resolution, therefore cannot replicate the stellar and beautiful waveform tracings of the ancient Tek scope. In reality, probably, no other modern scope can. I have received many positive comments about the old Tektronix oscilloscope waveforms. It is important to mention, that Rigol waveform viewing is not bad, just very different. The visual display is incredibly accurate and its triggering options, bandwidth, sampling rate and waveform display tools are fantastic. фантастический !

During these experiments, the 40 year old (plus) Tektronix scope was distorting frequencies greater than 10 MHz and breaking into oscillations. After 3 major repairs in 2009, the scope replaced with a Rigol DS1052E. Signal viewing will certainly different; that is for sure. The decision to move from a cathode ray oscilloscope (CRO) to a digital storage scope (DSO) was not taken lightly.

DSO versus CRO - some comments from the workbench

Choosing a CRO versus a DSO is an individualized process. It is your decision alone. Questions to ask yourself may include: What are my needs? What is my budget? Do I have weight and/or space constraints? Carefully weigh the advantages and disadvantages of each.

Proponents of CROs state that these scopes cannot generate artifacts, nor distort the signal. This of course is true as long as the scope bandwidth is adequate. Further, some people feel that aliasing or artifact generated in DSOs due to undersampling (taking too few samples of a waveform) is unacceptable. They may even feel that DSOs are not precision measurement instruments as a result. Limited horizontal screen resolution in DSOs is also a bugaboo for some experimenters and provides further evidence of DSO inferiority in the minds of these folks. These concerns are indeed valid; however, black and white thinking is a little out of fashion in a world more containing shades-of-gray.

The DSO takes a series of samples and stores them in memory. When sufficient samples are present, they are assembled and displayed. The sampling rate of a DSO is variable and depends on the time base setting used. Modern DSOs, like the Rigol, Tektronix Oscilloscopes and Agilent Oscilloscopes have better sampling rates and larger memories than their predecessors and hence aliasing is less of a problem than before; although in some measurement situations, undersampling can occur. One must always well consider and interpret whatever you are measuring and if you use a DSO, always keep undersampling in mind. When first using a DSO, you are on the bottom of a learning curve, however, with attentiveness and practice, one can learn to look for and possibly mitigate undersampling should it occur. In certain cases, a CRO will be superior to a DSO. In my discussions with others about Rigol signal viewing , only 1 significant "aliasing" problem has been noted by a builder when he tested a balanced modulator. The display did not give the expected result (was not filled in as expected) and a CRO was pulled out and the problem was verified. The builder knew there was a problem and could understand why it occurred. This builder also wrote that this was not so much a problem, as a reality of using a DSO.

Some techniques I have gleaned from the Internet about detecting aliasing may include the following:

Vary the time base over several ranges. Events occurring near the time base should be reproducible and if they are not, undersampling might be occurring.

As possible, use a single sweep and dot display. The 'dots' will indicate just where the scope took each sample. If the dots are far apart relative to the waveform timing, aliasing is a possibility.

Some techniques to minimize aliasing:

Choose linear interpolation when using math functions.

Use bandwidth limiting in low level measurements (The Rigol seems to automatically use B/W limiting in these situations).

Use trace averaging for low level measurements as possible.

The Rigol weighs 50 times less than my old scope and fits on a small shelf in my small workspace. As a hobbyist, it meets my needs and budget plus has some very cool features. Undersampling is considered and in some cases, such as low level measurement, an analog scope might be a better choice. Happily, a CRO is available to me if I really stress out over it. Signal viewing was taken for granted with my old scope. In some ways, this DSO has prompted me to dig deeper; to become more vigilant and thoughtful about signal measurement and display. If you have a spectrum analyzer, and use a DSO for signal viewing, the ability to perform slow sweeps while maintaining a perfect display is quite enjoyable. Again, please decide the CRO versus DSO issue for yourself (or maybe get a hybrid). The DSO is not a perfect solution to every signal viewing situation, but their constraints are quite livable considering their numerous modern features.

DSO's: “They are not your father’s oscilloscope”; that is certain!



The Figure 3 breadboard. AWG 24 to 26 gauge wire was used in the various inductors and transformers to better secure or anchor these parts.

---

14 MHz Circuit


12.24v
14 MHz
Figure 6
100
100
100
.1
.1
.1
T3
T5
2K2
T2
18
3
22
22
LP
DX
51
39
39
.001
←220→
←220→
50 Ω
50 Ω
- 4 dB
- 4 dB
d
Q4
T4
10 pF
d
Q5
g
d
g
22
g
s
Q3
g
s
s
2K2
5
100K
1M
220
470
470
.1
.1
CV

Q3 = Q4 = Q5 = J310
T2 = 10 turns FT37-43
T3 = 10 trifilar turns FT37-43
T4 = 2 uH = 22t on a T50-6; tap @5t
T5 = 18 : 3 turns FT37-43
L3 = .55 uH = 11 turns T30-6
CV = 6.5 - 50 pF

Figure 6 is the final schematic for the 14 MHz circuit as developed on the workbench. Your design might look very different than mine. In the first version of this circuit, there were only 2 JFET amplifiers and the resultant output voltage was too low (even without a 50 ohm attenuation pad). To compensate, I ran the source current of the JFETs above 15 mA, placed a source bypass capacitor on Q4 and also used a 1000 pF capacitor to couple the input to Figure 2. Some fairly bad harmonic distortion was measured at the output and it seemed crazy to run so much current. Therefore it was decided to run a third JFET amplifier and use only modest current in the trio of JFET amplifiers.

CV tunes very sharply and required some care when peaking the output voltage.

Figure 7


RIGOL
T'D
2 40.0mV
14.0785MHz
Vpp(2)= 2.02V
CH2 500mV
Time 10.00ns
17.60ns

Figure 7 is a screen capture of the 14 MHz circuit output measured using a sensitive 50 ohm terminated oscilloscope. This was with no low-pass filtering. The output is distorted. Presumably this happened in the diode frequency doubler. This is not a low-distortion oscillator.

15.3 MHz Low-pass Filter


50 Ω
.34 uH
.83 uH
.83 uH
.34 uH
50 Ω
270 pF
330 pF
270 pF

A N = 7 Chebyshev low-pass filter was inserted in Figure 6 at point LP. I checked with a spectrum analyzer and the 2nd harmonic was down 38 dB. There were no other measurable harmonics after that.

Figure 7b


RIGOL
STOP
2 4.00mV
14.0785MHz
Vpp(2)= 1.13V
CH2 200mV
Time 10.00ns
17.60ns

Figure 7b is a screen capture of the 14 MHz circuit output after the low-pass filter and final attenuator pad. Vpp on this graphic = peak to peak voltage = 1.13 volts. The output power is 5.04 dBm, or 3.19 mW . The Q4 and Q5 source resistors and the output attenuator pads are 2 areas of the circuit where you might easily change the output power. In the end, the circuit labeled Figure 6 was chosen. Your output voltage will probably vary, but can be easily adjusted as described.

Figure 8


A
B
RIGOL
STOP
1 0.00uV
7.03925MHz
Vpp(1)= 2.80V
CH1 500mV
Time 20.00ns
0.0000s
RIGOL
T'D
1 0.00uV
14.0785MHz
Vpp(1)= 1.34V
CH1 500mV
Time 20.00ns
0.0000s

Figure 8 are Rigol digital screen captures. Figure 8A is a measurement taken from the anode at point DX from Figure 6. Figure 8B is a measurement taken at the cathode of DX and shows distortion caused by the diodes, reduced AC voltage and of course, frequency doubling.



The 7 and 14 MHz circuits bread boarded and mounted in a chassis. The 7.039 MHz and 14.079 MHz outputs are connected to BNC jacks via RG-174 cable. The 15.3 MHz Chebyshev low-pass filter and -4 dB attenuator pads are on a raised Ugly Construction board. Some VCC decoupling parts are also on the bottom RF board.



The 7 and14 MHz crystal oscillator board mounted in a project chassis along with a 1 KHz low noise oscillator This photo was a prototype version that did not have a Chebyshev low-pass filter after the 14 MHz stage.



Front view of the .001, 7 & 14 MHz oscillator. It is really fun to build your own test equipment.

Transformer Notes and Conclusion



A photo of T5 from Figure 6. Some builders have emailed and stated they do not like to wind inductors/ transformers. I always ask them why? Often these builders were concerned with little details such as wire gauge and spacing, choosing the core size and which magnetic material to use. The Radio Amateur literature is replete with great tutorials on winding coils using toroids. Truly; the more toroids you wind, the easier it gets. Here are some simple points for beginners:

Powdered iron toroids are generally for tuned circuits. I.e. A capacitor and the inductor are tuned to a center frequency. Powdered irons containing the #2 and #6 material tend to tune sharply and have fairly high Q

Ferrites toroids are generally for use in broadband or wideband (untuned) applications. #43 material is relatively low Q and lossy as compared to the number #2 and #6 powdered iron toroids

Wind your inductors with enamel coated magnet wire. Popular gauges include 28, 26 and 24, but this is quite variable.

Minimally, you could get by with just #43 ferrite and #6 powdered iron toroids. For example, FT37-43 ferrites and T50-6 plus T68-6 powdered iron toroids could build a lot of inductors/transformers. In the photo above, I used #24 AWG wire for the 18 turns and #22 AWG wire for the 3-turn link. The 3 turn link is grounded on one end and well anchors the transformer. Thicker wire was chosen because Ugly Construction was used and the part is really anchored with the #22 AWG wire.

Conclusion

It took quite a lot of experimentation to reach the project goal. The experience was pleasant and comparing the old and new oscilloscopes was an added bonus. Perhaps, the circuits are overly complicated, however, they are critical signal generators for my workbench. Well designed signal generators have extensive RF-proof shielding to allow serious attenuation. These will have to do.

Addition - Jan 31, 2010 5 MHz JFET Low Noise Oscillator



Figure 9
14t FT37-43
87 uH
L7809
Bottom
12v
.1
51
.1
68 pF
Q1
J310s
330k
5 MHz
150 pF
270
150 pF
20 log(.356) = -8.97100004
20 log(.724) = -2.80522868
difference 6.17 dB
1.17 dBm
-4.99 dBm
724 mV
356 mV
Q2
.1
39
5 pF
1M
150
- 6 dB
Output: -4.99 dBm
10 bifilar
turns FT37-43
270
50 Ω
termination
d
g
s

Another experimental low noise oscillator was built for 5 MHz. The desired output power was -5 dBm. The schematic and peak-peak output voltages and powers are shown in Figure 9. The 68 pF capacitor in series with the crystal was found experimentally by using a variable capacitor and measuring the output voltage and observing the scope waveform. When these appeared to be optimal, the trimmer capacitor was removed and measured at 67.17 pF. This circuit can easily be adjusted to give higher output power such as 7 dBm. To increase power, you may consider increasing the VCC to 12 volts, add a 0.1 uF source bypass capacitor in parallel with the 270 Ohm resistor of Q2 and/or adjust the pad attenuation. There are other circuit alterations to increase power, but the aforementioned are a good start.

It is important to measure your output voltages with a 50 ohm load connected to the device. Standard value resistors were used which throw off the value somewhat, but the actual attenuation of the pad is very close to the 6 dB attenuation expected. The math can be done with software such as Applets H and I on the QRP tools web page.



The breadboard of Figure 9 is shown above. The - 5 dBm output was required for some upcoming experiments and to study log and power measurements. The black BNC appliance is a 50 ohm load. These are very handy, but not a necessity. In most cases, a simple 51 ohm resistor to ground is the load.

Figure 10


RIGOL T'D
4.00mV
5.00026MHz
20.00ns
Freq(1)=*****
Prd(1)=*****
Vpp(1)= 356mV
CH1 50.0mV
Time 100.0ns
0.0000s

A screen capture from Figure 9 signal viewing maneuvers.

Figure 11


RIGOL T'D
0.00uV
5.00026MHz
Freq(1)=5.000MHz
Prd(1)=200.0ns
Vpp(1)= 356mV
CH1=50.0mV
Time 50.00ns
0.0000s

The output waveform looks good - even on a DSO!

Spectrum Analysis

Figure 12



The output of the Figure 9 oscillator was further attenuated -19 dB for analysis in a spectrum analyzer. The -19 dB was chosen as this 50 ohm pad uses near standard resistor values and would well ensure a very safe signal level for the spectrum analyzer. The pad is shown in the Figure 14 schematic. The second harmonic (2F) is down about 20 dB from the fundamental. Each horizontal division is 5 MHz and each vertical division is 10 dB. Compared to other more conventional oscillators that were checked in the spectrum analyzer, this oscillator has low harmonic content.

Figure 13



A N=5 or 5 element Chebyshev low-pass filter was placed after the Figure 9 oscillator and connected to the spectrum analyzer to see what happens. The 3 dB down frequency of this low-pass filter was 6.53 MHz. The second harmonic is now ~42 dB down. There are no measureable harmonics after 2F. It is really cool to "see" what a filter does to a signal.

Figure 14


-24.64 dBm
50 Ω
-19 dB
220
1.2 uH
2.5 uH
1.2 uH
13.1 mV RMS
← 62 →
820 pF
820 pF
Inductors: 28 AWG wire on T37-2
1.2 uH = 17t 2.5 uH = 25t
50Ω terminated scope
RIGOL
T'D
0.00uV
5.00026MHz
Vrms(2)=13.1mV
Vpp(2)=37.6mV
Freq(2)=5.000MHz
CH2 5.00mV
Time 50.00ns
T→40.00ns

The schematic of the -19 dB attenuator pad and the low-pass filter is shown. To measure the output, the 10X probe was disconnected. The circuit was connected to the oscilloscope via 50 ohm coaxial cable and the scope input was terminated with 2 paralleled 100 ohm resistors. The 50 ohm scope termination technique will be discussed in a future web page addition. The RMS voltage values were inputted into Applet J on the QRP Tools page to calculate the output power. The RMS output was 0.131 volts which calculated to an output power of -24.6 dBm.

RF — Test and Measurement

Crystal Parameter Checker

Introduction

This web page is a supplement to JavaScript Applet **G** on this web page. This software does the math using a simpified version of the method to determine motional inductance and capacitance developed by David, G3UUR. This is a very basic tutorial meant as an introductory guide for novice builders.

GND
ABRACON
5.0000
AB 0436
CRYSTAL CHECKER

Shown in the photo above is 1 of my crystal parameter checkers. The schematic may be found in many places including EMRFD Figure 3.35 (See Errata) and on this pdf by Nick, WA5BDU. A power indicator LED has been added, but the circuit is the standard design. In this breadboard, the crystal being measured is tack soldered in.

Many builders just copy other builder's I.F. filter schematics, however, your crystal filters will perform better if your design is based upon the exact parameters of the crystals you have. For the simple design or optimization of a crystal filter, it is necessary to measure crystal parallel capacitance plus take other measurements to calculate motional inductance and capacitance. Determining your crystal parameters is not difficult if you have a capacitance meter, a frequency counter and some math skills. It is easiest to use a program to crunch the math; hence I wrote a stupid-simple JavaScript applet.

Designing filters is another story; it takes knowledge, practice and good software for this. Filter design theory has been extensively covered by Anatoly Zverev, Wes Hayward and others. The work of Nick, WA5BDU is also greatly appreciated. His presentations and references are excellent for those keen on learning more about filter design.

A four crystal 5.00 MHz SSB I.F. filter was desired. 20 crystals were on hand — they were from the same batch. The crystals were all placed in the above oscillator and their frequency was measured. The 4 crystals closest matching in frequency were set aside. The crystal parameters of these 4 were then determined. Typically these values are averaged and this average is used to design or tweak the filter using software.

---

1. Measure Capacitance

The procedure for determining the parameters of 1 crystal is described.

The first step is to measure the crystal capacitance (called parallel capacitance) using a capacitance meter.



Measuring the crystal parallel capacitance



Parallel capacitance of the above 5.0 MHz crystal in an AADE LC meter



Next, measure the capacitance of the open switch plus the 33 pF fixed value cap wired in-situ. This will give you the total circuit capacitance of the open switch, the 33 pF fixed value capacitor, and any stray capacitance from your crystal holder, wires, etc. The switch itself plus stray wiring will be a few pF so the total should be around 36 to 40 pF or so. In my test oscillator, the result = 41.19 pF as shown. On my other crystal checker with a better switch, it's 36.9 pF.

In the calculation of crystal Lm and Cm, the parallel capacitance and the switch circuit capacitance will be summed.

---

2. Measure Frequencies

A crystal is put in the oscillator with the switch open. Record the frequency. Your counter must have resolution down to 1 Hertz. After recording this value, throw the switch and measure and record this frequency. You now have all the measured values required to calculate motional parameters and adjust or design a filter. Motional parameters are calculated in Applet G.


TRONIC COUNTER
PACKARD
MHZ
04999274
kHz
HEWLETT PACKARD
TIME BASE
ANACONDA ELECTRONICS COMPANY TEC No
48-5395-TEST
FUNCTION
GATE

Frequency measured with the switch open = 4.999274 MHz


RONIC COUNTER
PACKARD
MHZ
04998317
kHz
HEWLETT PACKARD
TIME BASE
ANACONDA ELECTRONICS COMPANY TEC No
48-5395-TEST
FUNCTION

Frequency measured with the switch thrown = 4.998317 MHz

---

3. Do Math by Hand or with Software



G. Calculate Lm and Cm For a Crystal using the G3UUR Method

ABRACON
5.0000
AB 0436
image

Enter frequency in MHz written on crystal (nominal frequency): 5.0

Enter measured frequency in MHz with switch open: 4.999274 Enter measured frequency in MHz with switch thrown: 4.998317

Enter crystal capacitance in pF: 4.65 Enter open switch circuit capacitance in pF: 41.19

Calculate Xtal Parameters

Cm = 17.55 femto Farads , Lm = 0.0578 Henries

The applet **G** calculation of the crystal parameters using the above measured values

---

4. Example Filter Adjustment

It is assumed that most builders will use software to design or tweak their crystal filters. The only 2 programs tried *(to date)* include AADE Filter Design and the Ladpac software collection that supplements EMRFD. I am more familiar with the Ladpac programs written by Wes, W7ZOI. Only these programs are demonstrated. Please read the instructional file Ladpac2008 Manual.pdf to understand these programs. *The Ladpac software bundle includes GPLA.*

The purpose of this tutorial is not to teach crystal filter design, but to describe a relatively simple method to tweak an existing design using your measured crystal parallel capacitance and its calculated motional inductance.

The first step is to digitally format your filter into a file that can be analyzed in GPLA. In my opinion, the easiest way to do this is to use the ladder circuit editor ladbuild02.exe or better yet, its update - ladbuild08.exe. The model filter follows:



5.0 MHz Lower Sideband Filter

-3 dB Bandwidth = 2.185 KHz
C-par = 4.65 F
Lm = 0.0578 H

68 pF
68 pF
820
10 pF
39 pF
47 pF
39 pF
10 pF
820

The model 5 MHz SSB filter



Ladder Builder Circuit Editor 2008

Marker N = 1

Click anywhere to begin. Select part # with Mouse.

R Load = 820.00

Nominal Crystal Values (equal for all crystals)
Fx, MHz = 5.000
Lm, H = 0.057800
Qx = 100000.0
C-par, pF = 4.650

Global Parameters

Inductor Q 250.00
f begin 0.000
f end 30.000
f step (not used in GPLA-08) 0.1
f / div 10.000
dB Bottom 60.000
dB/div 10.000

Place Cursor in drawing, click, then select part from those below.

R Source = 820.00
Value = 0.000
Part = wir
Connection = ser

LadBuild08 2nov08 w7zoi

File
About Ladbuild
RL
RS
Default File
Load
Save
Exit
C
L
R
RLB
Xtal
Exchange Ser/Par
Convert Part to Duplicate
Add "Wire" at Load End
Add "Wire" after N
Remove Part N

Clear any existing components and enter the termination R, C-par and Lm values. Qx is set at 100000


RL
RS
68.00
39.00
47.00
39.00
68.00
10.00
0.00
0.00
0.00
0.00
10.00

Build your filter within the editor. Save your work. Start up GPLA and load your newly saved filter.


File
About GPLA
Click to Review Circuit
S21 =
S11 =
S21 Ref.
#, part, connection, value:
top
dB
Plot
dB/div.
bottom
Enter #
Enter New Value
Click to load new value
start
Frequency
Freq./div
stop

```
7  xtl  ser  0.0000
8  cap  par  39.0000
9  xtl  ser  0.0000
10  cap  ser  68.0000
11  cap  par  10.0000
98  Source R = 820.0
99  Inductor Q = 250.0

Crystal Parameters:
100.  Freq.= 5.0000
101.  Lm = 0.0578
102.  Cp. 4.65
103.  Qx. 100000.0
```

top: 0.
dB/div.: 10.00
bottom: -60.0
Enter #: 1
Enter New Value: 0
start: -7000
Frequency: Hz
Freq./div: 1000
stop: 7000
C:\Todds\QRPHB\QRPHB\aa-fall 2009-20

Set a sweep and **x** axis increment (-7000, 1000 and 7000 in this example). Push the Plot button

Let's say you wanted to use this filter design and have determined the average parameters of the 5.00 MHz crystals in your parts collection. Let's assume that for your crystals, C-par = 3.1 pF, and Lm = 0.098H. Input these values in GPLA.


File
About GPLA
Click to Review Circuit
S21 =
S11 =
S21 Ref.
#, part, connection, value:
top
dB
Plot
dB/div.
bottom
Enter #
Enter New Value
Click to load new value
start
Frequency
Freq./div
stop

```
7  xtl  ser  0.0000
8  cap  par  39.0000
9  xtl  ser  0.0000
10  cap  ser  68.0000
11  cap  par  10.0000
98  Source R = 820.0
99  Inductor Q = 250.0

Crystal Parameters:
100.  Freq.= 5.0000
101.  Lm = 0.0980
102.  Cp. 3.10
103.  Qx. 100000.0
```

top: 0.
dB/div.: 10.00
bottom: -60.0
Enter #: 101
Enter New Value: .098
start: -7000
Frequency: Hz
Freq./div: 1000
stop: 7000
C:\Todds\QRPHB\QRPHB\aa-fall 2009-20

Look what happened to the crystal filter's bandwidth. Our - 3dB bandwidth is now somewhere around 1464 Hertz. This simple experiment illustrates how important it is to use the parameters of <u>your</u> crystals to obtain a desired filter response.

Experiment with the various functions in GPLA to learn how to use it. Set whatever reasonable sweep you want. This program is best learned by using it repeatedly.



#, part, connection, value:

7 xtl ser 0.0000
8 cap par 22.0000
9 xtl ser 0.0000
10 cap ser 39.0000
11 cap par 5.0000
98 Source R = 1500.0
99 Inductor Q = 250.0

Crystal Parameters:
100. Freq.= 5.0000
101. Lm = 0.0980
102. Cp. 3.10
103. Qx. 100000.0

top 0.

10.00 dB/div.

bottom -60.0

Enter # 10

Enter New Value 39

start -7000 Hz

1000 Freq./div

stop 7000

C:\Todds\QRPHB\QRPHB\aa-fall 2009-20

In the above screen capture, the above filter was tweaked to "re-establish" a -3dB bandwidth of ~2.172 KHz. All adjustment was performed entirely in GPLA by swapping capacitor values and observing the resultant waveform. When you get an overall pleasing bandwidth plus shape, but there is too much ripple at the top, generally you must increase the terminating R values. This is the brute-force, manual way to tune filters. For this method, you need not understand terminology such as as series resistance, MESH, K or Q values, Butterworth response, or Chebyshev with 0.1 dB of ripple.

Admittedly, at first, this method can be quite time consuming and tedious, however, with practice, you may be able to tweak a filter in only a few minutes. Clearly, the more you dig into understanding crystal filter design, the better your filters can be, however, getting overly complex can scare off builders who are new to this hobby. Note these filters use standard value capacitors and resistors; perfect for popcorn I.F. filters.



The original 5 MHz Model filter with updated C and R values using Lm = 0.098 and C-par = 3.1


S21 =
S11 =
S21 Ref.
Click to Review Circuit
dB
Plot
Click to load new value
Frequency

top: 0.

dB/div.: 1

bottom: -20.0

start: -4000

Hz: 1000 Freq./div

stop: 4000

C:\Todds\QRPHB\QRPHB\aa-fall 2009-20

#, part, connection, value:

```
0  Load R = 1500.0
1  cap  par  5.0000
2  cap  ser  39.0000
3  xtl  ser  0.0000
4  cap  par  22.0000
5  xtl  ser  0.0000
6  cap  par  27.0000
7  xtl  ser  0.0000
8  cap  par  22.0000
9  xtl  ser  0.0000
10  cap  ser  39.0000
11  cap  par  5.0000
98  Source R = 1500.0
99  Inductor Q = 250.0
```

Enter #: 10

Enter New Valu: 39

GPLA zoom of the **Y** axis showing the first 20 dB of attenuation.

---

5. The Model 5 MHz SSB filter Design

Although this page is not about crystal filter design, an example follows for reference purposes.

For designing filters, the application xlad08.exe is a good choice. The following 3 screen captures show the raw design process and GPLA analysis of the model 5 MHz Lower Sideband filter shown earlier with C-par = 4.65 pF and Lm = .0578. There are some great articles in print and on the Web to study if you want to learn about filter design. The Ladpac software from EMRFD is excellent. My special thanks to Wes, W7ZOI for answering my questions about his software. From this information, I was able to make this web page.


XLAD08: Crystal Ladder Filter Design
File
About XLAD
1. Characterize Crystal
2. Set B and N
2A. Generate Butterworth, Chebyshev, or Cohn k and q.
3. Set q1 and qn
4. Match Ends
5. Calculate Coupling Caps
6. Tune each Filter Mesh
Save design to default file.
Exit

Follow instructions in numeric order:

F , MHz: 5.0 Motional L, Henry: .0578 Q-u: 100000 C0, pF.: 4.65

1. Enter or edit crystal parameters and click:

Filter Bandwidth, Hz, = 2000 Number of Crystals in Filter (20 max) = 4

2. Enter/Edit B and N and click:

2A.(Optional) To generate k and q values, click:

q1 = 1.5065 qn = 1.5065

3. Enter or Edit End Normalized Q values and click:

Min End Resistance = 747.7

End R = 800

4. Enter or Edit End R and click:

Shunt End Capacitors: C-1, pF 10.52 C-N, pF 10.52

k1-2 0.6685 k2-3 0.5428 k3-4 0.6685 k4-5 0.0000 k5-6 0.0000

k6-7 0.0000 k7-8 0.0000 k8-9 0.0000 k9-10 0.0000

5. Enter or Edit the Normalized coupling coefficients and click:

6. Edit Coupling and End Caps, if desired, and Tune Filter:

Shunt Coupling Capacitors, pF

C12= 40.69 C67= 0.00

C23= 50.12 C78= 0.00

C34= 40.69 C89= 0.00

C45= 0.00 C9-10= 0.00

C56= 0.00

SeriesTuning Capacitors, pF,

CT1= 72.80 CT6= 0.00

CT2= 99999.00 CT7= 0.00

CT3= 99999.00 CT8= 0.00

CT4= 72.80 CT9= 0.00

CT5= 0.00 CT10= 0.00

xlad08, 5 Nov 08d, w7zoi

A Tuning Cap. of 99999 indicates a wire when building the filter.



Note: The default k and q data built into the program describe a N=5 Gaussian-to-6 dB shape.
Ref: Zverev, "Handbook of Filter Synthesis," Wiley, 1967.

1. Pick Filter Type

● Chebyshev ○ Butterworth ○ Min-Loss (Cohn)

2. Enter Number of crystals (10 max): 4

3. If Chebyshev, enter Passband Ripple in dB (max of 3 dB.): .2

4. Click Here to calculate k and q.

q1 = 1.50654 qn = 1.50654

jk	k[jk]
12	0.66851
23	0.54281
34	0.66851



top: 0.

10.00 dB/div.

bottom: -60.0

start: -4000.00 Hz 2000.00 Freq./div stop: 8000.00

C:\Todds\QRPHB\QRPHB\aa-fall 2009-20

Cursor Data =====> 0.0 Hz S21= -- dB S11= -- dB

#, part, connection, value:

0 Load R = 800.0
1 cap par 10.5200
2 xtl ser 0.0000
3 cap ser 72.8000
4 cap par 40.6900
5 xtl ser 0.0000
6 cap ser 99999.0000
7 cap par 50.1200
8 xtl ser 0.0000
9 cap ser 99999.0000
10 cap par 40.6900
11 xtl ser 0.0000
12 cap ser 72.8000
13 cap par 10.5200

Enter #: 1 Enter New Value: 0

- 3dB BW = 2181 Hz

---

6. Conclusion

This web page presents a brief method to calculate crystal motional parameters and as required, to adjust crystal filter circuits to function optimally. This approach like my Java-script applet are simplistic to avoid the fear factor associated with crystal ladder design.

Listening tests are also valuable for assessing crystal filter function. Is the bandwidth as you expected? Does the filter ring excessively? Does it sound tinny? In the recent past, the crystal filters in 2 kit receivers/transceivers were tweaked as a favor to friends. *Please note, I have total respect for people who sell kits and appreciate the contribution they make to our hobby.*

The crystals of these Cohn type filters were removed and analyzed and the bandwidth was not as specified. In 1 case, the filter shape looked terrible in GPLA. Clearly, the kit sellers provided crystals which had markedly different parameters from those used by the original circuit designer. The I.F. filter capacitors were replaced with appropriate values and the R values were adjusted via either resistors and/or transformer ratios and the improved filters sounded pleasant.

It is a real treat to listen to a receiver with a well designed crystal filter — sadly, I don't enjoy this experience that often.



In my opinion, the best sounding CW crystal filter design is the Gaussian to 6 dB. Some operators would never use such a filter in a contest-grade receiver as the filter skirts are not steep enough for them. There are tricks to make the stop band better (more like a Chebyshev response, but without the ringing), however, this topic is out of scope.

I sincerely ask for your feedback on the G. JavaScript Applet. Does it work correctly? How could it be improved? Can you contribute better code? Thanks and 73.

QRP — Posdata for January 2012 — More on Crystal Ladder Design

Important to both superheterodyne receivers and single sideband transmitters, crystal ladder filter design lies juxtaposed as both a favorite and feared RF design topic. Newer builders may lack math skills, and/or become paralyzed by the terminology — or lack the ambition to learn or apply good bench practices. Even a cursory Internet search returns many fabulous files to read — witnessing a crystal ladder filter design article explosion.

The difficulty characterizing and building filters has progressively declined since the advent of the first handheld computers — improvements in personal computers and filter design software allows astute builders to pursue even complex xtal filter response shapes in 2012.

In QST for July 1987. Wes, W7ZOI wrote **Designing and Building Simple Crystal Filters**. This article promoted Cohn or Min-loss filters and its intent was to transcend the math and measurement associated with xtal ladder filters of the day and allow builders to just frequency match some crystals, and then go experiment.

In my estimation, this article proved revolutionary — soon after, builders around the globe, Elecraft, and other kit companies embraced this technique/topology and the rest is history. *(I call it the paper that launched a thousand kits).* If you're a new builder and feel overwhelmed by the material on or referenced by this web page, please consider first obtaining this article.

Learning about crystal ladder filter design is time well spent.

In 2011/2012 I explored the works of 3 builders who share their work via the web and/or journals.

Horst Steder, DJ6EV and Jack Hardcastle, G3JIR

The Steder and Hardcastle works emphasize that we need to measure/calculate crystal L and C parameters, plus the coupling and tuning capacitances (not just frequency). Through emails with Horst, DJ6EV, I learned many things, but 3 stand out:

1. It's better to design a good filter than fix a bad one.
2. Careful measurement of your crystal parameters plus software design and simulation = the best chance for getting your desired performance.
3. Deriving motional parameters from a 3 dB bandwidth measurement remains a great way to characterize multiple xtals. *In my opinion, the G3UUR method is the easiest way to characterize a small batch of xtals.*

Some of the earliest references to modern crystal ladder design I've found were written by Jack Hardcastle and published in RadCom and QST — I later confirmed this by reading work by Wes, W7ZOI and others. Hardcastle's and Haywards' work proved foundational for the experimenters that followed including David Gordon-Smith, Chris Trask, Jim Kortge and many others.

Steder and Hardcastle's combined experience assessing and/or documenting crystal ladder design spans decades.

Their QEX article **Crystal Ladder Filters for All** may be legally downloaded from the ARRL website here.

Program download URL: http://www.arrl.org/qexfiles (select 2010, "11x09_Steder_Hardcastle.zip")

The QEX article describes Steder's Microsoft Windows™ program, methods to derive motional parameters, plus cites many important references. The main program calculates practical lower-sideband crystal ladder filters based on the exact equations published by M. Dishal in 1965. Hardcastle transformed these equations into a computer useable form in 1983 and Steder incorporated these equations into a modern, easy-to-use and interactive application with nice graphing and table displays.

For simplicity, the program assumes lossless crystals, however, the calculated values can easily be transferred into another simulation program such as GPLA to add or refine parameters such as loss resistance.

The main "Dishal" application calculates filters with Butterworth, Chebychev and constant-k (Cohn) properties and the so-called "QER" filter type by G3UUR (a low ripple version of the Cohn filter). Further; sub-programs in the top-level menu calculate xtal parameters (by both the G3UUR and 3 dB method), plus L-C impedance matching and ladder termination networks. An extensive help file well explains the program.

Iacopo Giangrandi — Introduction to Crystal Ladder Filters

Link: http://www.giangrandi.ch/electronics/crystalfilters/xtalintro.html

Iacopo (Jack) uses a transmission measurement to infer the motional parameters — inserting a series capacitance and measuring the series resonant frequency shift was also described in 1998 by Rolf-Dieter Mergner, DJ9FG.

His web article/applications provides what is likely needed by most builders — simple filter synthesis while avoiding expensive test gear. His filters plots/figures are spectrum analyzer measurements that I really like. Although his program can generate aymmetrical filters that some builders might not be used to, the frequency domain plots indicate proper function.
Giangrandi's filter design programs appear to be based on Jack Hardcastle's work and possibly content published in a paper by Patrick Magnin, F6HYE and Bernard Borcard, F3BB in Radio REF for April 1990.

I encourage you to try all the methods and applications mentioned to discover what works best for you. Don't lose heart, for characterizing crystals with a vector network analyzer is also a time-consuming endeavor and simple often = best on the QRP Workbench.

QRP — Posdata for August 2012 — Measuring Crystal Q

Prior to July 26, 2012, I could not measure Xtal Q. Why? I tried to measure crystal Q with the shunt-series tuned method (essentially the crystal acts as a trap and a step attenuator is used to calculate the insertion loss the xtal exhibits when centered in the notch) but failed because I could not precisely set the frequency with my homebrew L-C oscillator.

You really need a DDS or a Si570 based signal generator and preferably a spectrum analyzer to exact the measurement with the "trap method". The DDS is critical, while the SA only preferable — a power meter, or a 50 ohm terminated 'scope can work as the detector if a low-pass filter is placed just after the xtal.

On July 26, 2012 Wes, W7ZOI developed a simplified method and wrote a pdf file called **Simplified Measurement of Crystal Q** after feedback from myself and John Larkin about Q measurement difficulties without a digital-based signal generator. Unfortunately, this pdf file is no longer offered for download by W7ZOI. His method works well and I'm glad that as of now, I can *completely* characterize any crystal I own.

I present an experiment showing how I measured the Q of a 10 MHz crystal applying the new method developed by Wes, W7ZOI.

The crystal is evaluated as a N=1 low-pass filter resonated by a shunt capacitor at each end. I stuck with Wes' suggestion to try 1000 pF at 9 to 10 MHz. For lower frequency xtals he recommended trying larger value shunt capacitors. Just experiment with the shunt capacitance — if you use too high a C for a given crystal, your xtal low-pass filter bandwidth might get too narrow to measure with an L-C based signal generator.

The following diagrams employ 2 programs from the Ladpac software that ship with EMRFD


Measure the Insertion Loss of a Crystal Filter
50 Ω detector
Xtal filter
50 Ω coax with BNC connectors
10 dB pad
Signal Generator
50 Ω
1000 pF
A
50 Ω
Tune SG to get the highest pk-pk voltage in the 'scope
50 Ω detector
Through Connector
10 dB pad
50 Ω coax with BNC connectors
Signal Generator
50 Ω
B
50 Ω
Remove xtal and insert through connector at the same Freq as above

Above — Measurement of crystal filter insertion loss. In Part A, I carefully tuned my signal generator to get the highest peak-peak voltage in my 50 Ω terminated oscilloscope. I recorded this AC voltage as V Fil. In Part B, I removed the crystal filter board and replaced it with a BNC clad RF through-connector. I recorded this AC voltage as V Cal.

I discuss this standard method to measure the insertion loss or gain of a *device under test* in RF Workbench 2.

Even with the simplified method, you'll need a signal generator with good tuning resolution. My generator is shown on VFO 2011 as the 2.8-10.5 MHz Signal Generator. This is my version of the EMRFD Figure 7.27 generator.



Insertion Loss

IL = 20 LOG (V CAL / V FIL)

Vcal = 464 mV pk-pk; Vfil = 267 mV pk-pk

IL = 20 log (1.7378) = 4. 8 dB

Above — The formula for insertion loss using peak-peak voltages. With my 10.0 MHz crystal, V Cal = 464 mV pk-pk and V Fil = 267 mV pk-pk. The insertion loss of my crystal = 4.8 dB.


+12V
10K
2N3904
0.1
C_S
10K
C_P
C_P
1K
(C_S includes switch "open" capacitance)
G3UUR method

$$C_M = 2 \cdot C_S \cdot \frac{\Delta F}{F}$$ Old Equation, p 3.19.

$$C_M = 2 \cdot (C_S + C_0) \cdot \frac{\Delta F}{F}$$ Updated Equation

10 MHz Xtal

C0 = 4.87 pF
CS = open switch + cap = 37.4 pF
Open switch F = 9.998710 MHz
Thrown switch F = 9.996104 MHz
Lm = 0.0115 H

Measure C0
Calculate Lm


About Ladbuild
Marker N
ck anywhere to begin. Select part # with Mouse.
Global
Parameters
RL
RS
fault
File
Ladbuild08

Marker N 4
R Load = 50.00
Nominal Crystal Values (equal for all crystals)
Fx, MHz = 10.000
Lm, H = 0.011500
Qx = 100000.0
C-par, pF = 4.870
0.00
1000.00
1000.00

Above — First I measured C0 (C-par) and then with the G3UUR method, calculated the motional inductance of my xtal. Finally, I entered all the needed variables into Ladbuild08 to make a filter to analyze in GPLA.


General Purpose Ladder Analysis, 2012, Beta 0.4
File
About GPLA
S21 =
S11 =
S21 Ref.
gpla-12.4 28july12 w7zoi
Click to List Circuit
Drag a box on graph to Zoom
Zoom to Original Sweep
Save S21 as Ref.
Place Cursor
Reset Cursor
Tune Part Value, Inductor Q, or Qx.
Up
Down
Click to load new value
Save as Default, Exit.
EXIT

top 0 dB

2 dB/div.

bottom -10.0 dB

Start Freq. 0.000

Frequency Units Hz

100 Freq./div

stop Freq 400

☑ Plot S11

☐ Plot Referenc

Frequency 199.333 Hz

S21= -4.80 dB

S11= -7.44 dB

#= 103

%= 1

Value=

#, part, connection, value:

0 Load R = 50.0
1 cap par 1000.0000
2 xtl ser 0.0000
3 cap par 1000.0000
4 rlb ser 0.0000
98 Source R = 50.0
99 Inductor Q = 250.0

Crystal Parameters:
100. Freq.= 10.0000
101. Lm = 0.0115
102. Cp. 4.87
103. Qx. 108286.0

Part # 1

New Value 0

E:\Hobbyist\QRPHB notes\2012\wes contributions 2012\Q of xtal\my-10.cir

Mouse Frequency 382.0000

S21 at F-mouse = -10.73 dB

S11 at F-mouse = -1.03 dB

Above — With GPLA, I adjusted the value for *Qx* up or down until my *centered* S21 value indicated -4.8 dB (the insertion loss of my crystal determined earlier). My crystal Q = Qx = 108286.


FOX100-20
10.000

Above — 10 MHz Crystal filter breadboard.



Above — A sweep of the 10 MHz Crystal filter used to determine the Crystal Q



QRP SWL HOMEBUILDER

Amateur Radio Electronic Design

Electronic Hobbyist Circuits 2010



This page houses a collection of brief hobbyist experiments.

1. LM380 Power Examination

BR
M9324
LM380N


12.24v
100 uF
10
470 uF
470 uF
input
LM380
4.7
8 Ω
.1
3,4,5,7
10,11,12
10 uF
5.7 volts peak-peak
2.03 watts peak power
Average sine wave power
= 508 mW
Figure 1

Figure 1 shows the test set up. This is a good part with an input impedance of 150kΩ. The gain is internally fixed at 34 dB. The average clean power was 508 mW. The test input frequency was 1018 Hertz.



The breadboard of Figure 1 is shown above.

2. Wide Range L- C Oscillator



9 MHz L-C Oscillator

CV = 2-10 pF air variable trimmer cap
L1 = 6.1 uH = 36 turns on a T68-6

Shown above is a single frequency version of a VFO topology which allows a wide frequency range when additional switched inductors and/or capacitors plus a tuning variable capacitor are used. One good usage example would be a to use such a VFO to drive a bridge to make a wide range antenna analyzer. Q1 is essentially a common gate amplifier. The source is driven and the output is taken off the drain. This FET exhibits no signal phase shift. Q2 is a source follower that is AC coupled through that 22 pF capacitor The 18 ohm resistor is used to kill UHF parasitic oscillations. The Q2 follower also has no phase shift. Connecting the output of Q2 back to stage Q1 gives zero phase shift. The L-C tank will select the frequency where 0 phase shift is obtained. The tank will show phases other than 0 away from its resonance.

Q3 is an AC-coupled source follower to further buffer the VFO from its load. The RFC can be anything from your junk box, although it should likely be low Q. The low-pass decoupling filter on the the 12 volt supply path can also be anything reasonable. I wound mine using 17 turns on an FT37- 43 ferrite toroid. Its purpose is to keep RF from traveling down the 12 volts DC voltage wire to other parts of your circuit.

Any component connected to the L-C tank (at the Q1 drain, or the cold end of L1) can affect VFO tuning and drift. Temperature compensation will be necessary to achieve perfect stability. I use NP0 and C0G caps interchangeably. In the design shown, stability was good and the output had low measured distortion. This VFO will pretty much oscillate with any reasonable L and C values in the tank circuit. I found frequency stability was a little better with a higher L to C ratio. This is a great experimenter's circuit. One version built oscillated at 150 MHz.



The breadboard of the above schematic. Pull the wire on your #6 powdered iron toroids tight to prevent air gaps between the toroid and the wire. Number 26 gauge wire was used on L1 as shown. High Q tank parts will garner the best results.


12 V
Bottom
L7805
LC Switching Ideas
.001 C0G
100
Switch 1
100
L5
L4
L3
L2
.001 C0G
L1
22 pF NP0
C1
C2
18
33 pF
68 pF
d
g
s
d
s
g
Switch 2
1M
10 - 180 pF
Tune
150

Some potential switching ideas are presented above. The builder is in total control of the tuning range and must calibrate the L and C values according to needs and the parts on hand. Output power will vary according to the L-C ratios and some designs include automatic signal amplitude leveling and/or RF gain controls.

3. FET Matching



I find matching high IDSS FETs like the J310 to be a pain. I generally matched them for IDSS and occasionally for IDSS and VP. Observations that when the IDSS of 2 or more FETs match, their pinch-off voltage (VP) also matches, led me to not measure VP. In addition, the variability of VP measurements causes me distress. Click here for a tutorial if you don't understand the terms IDSS and VP.



Above — The device I use to measure IDSS and VP. From Ken Kuhn's web site.

Conceptually IDSS and VP aren't difficult to understand — measuring them is another story. With the above device, first IDSS is measured; the final drain voltage potentiometer setting is left and then I measure VP. While measuring IDSS in high IDSS FETs, heating can occur and you may actually see current start to drop as you increase the drain voltage (negative temperature coefficient). On J310 specification sheets, the manufacturers state they pulse the current during measurement to prevent heating. While performing IDSS measurements, I am fearful of destroying the FET I am trying to characterize! Measuring VP is also problematic.

I have tried 3 methods to quantify VP:

Adjust the 0 - 6 volt supply until I think the current goes to 0. Serial measurements 1 day apart can vary by a variation of as much as 0.5 volts; it's quite subjective.

Adjust the 0 - 6 volt supply and measure the gate voltage that produces a drain current somewhere between 0.1 and 1 percent of IDSS and declare that to be VP.

Adjust the 0 - 6 volt supply so the ammeter reads ¼ IDSS and multiply this voltage by - 2.0. Refer to Ken Kuhn's site for details. Although reasonably accurate, the second order math is only a rough approximation — the real math is impossible to do by hand as it involves fractional exponents and these exponents and other factors vary as a function of the physical JFET geometry.



Above — The breadboard of the device I use to measure IDSS and VP. There is no actual switch, I either ground the green wire to the copper board, or tack solder it to the 0 - 6 volt potentiometer wiper. 10 megohm resistors plus the pot ground wire anchor each pot to the copper clad board.

All 3 methods to quantify VP frustrate me. There must be a way to match J310s or other FETs without characterizing them. I frequently collaborate with readers to problem solve and learn. A potential solution contributed by a supportive reader follows:



Q1	Q2	Volts
J310	J310	0.058
J310	J310	0.003
J310	J310	0.614
J310	J310	0.215
J310	MPF102	7.23

Above — A bridge is used to match a pair of JFETS. It's often best to match devices in a circuit that closely resembles the one that you intend to use them in. The differential output of each drain is measured by placing a DVM lead on each drain and recording the voltage. Generally, I stick a FET in the Q2 slot and put FETs from my parts bin in the Q1 slot to match it. The results of 5 different FET pairs are tabled above. A match <= 50 mV is probably acceptable and in 1 case, I found a match of 3 mV! You can match 1 FET with many using this device.

Note the poor match when an MPF102 and a J310 were tested. 1% tolerance resistors are recommended for the bridge.



Above — A set and forget precision bridge using trimmers to establish a perfect DC match on both halves. If you don't have 1% parts, the trimmer resistors offer a solution. You can place a trimmer at either the drain or source end as shown and just use 5% resistors. Calibrate each half of the bridge with your ohm meter. I cover bridges on this web page if you need more information on them.

Above — A differential FET matcher breadboard. This version had a 9.1M gate resistor on Q1 by accident, although it made no difference to the experiment, as no DC gate current flows.

4. BJT and Diode Matching



Q1	Q2	Volts
2N3904	2N3904	0.533
2N3904	2N3904	0.261
2N3904	2N3904	0.017
2N3904	2N3904	0.135
2N3904	2N3904	0.340
2N3904	2N3904	0.262

Above — Differential BFT matcher. Differential voltage matching works for bipolar junction transistors and diodes also. PN junctions are thermally sensitive — let them stabilize before testing. I measured 6 2N3904 transistors and the tabled results remind us why this transistor isn't the best choice for matched BJT circuits.



Above — The breadboard of the differential transistor matcher. Any reasonable resistor values will work fine, but don't run the current too high — my circuit has a nominal emitter current of 2.25 mA.

Differential Diode Matcher



D1	D2	Millivolts
1N4148	1N4148	2.4
1N4148	1N4148	4.1
1N4148	1N4148	6.6
1N4148	1N4007	18.1
1N4148	Schottky	315
1N4148	Ge	169
1N4148	1N4148	6.8
1N4148	1N4148	4.9

Measurements with each diode current @ 77.3 μA

Above — The differential diode matcher. The 10K pot allows you to vary the current to suit your needs. The ammeter reads double the diode current. Considering only 1 diode; the current ranges from 0.01 to 5.82 mA. You can drop the 1% metal film 2K0 resistors down as low as 470 ohms or so if you need serious current. Tabled are some measurements performed with the 10K pot dialed to give 0.636v (77.3 uA per diode). This provided excellent sensitivity. Measurement was performed on my DVMs 200 mV scale. Builders might experiment with diode current to assess measurement sensitivity and linearity or even to match the diodes across a range of current values.

Clear glass passivated diodes can be affected by light — photons will pass through the glass and knock electrons through the barrier. Ensure each D.U.T is exposed to the same amount of ambient light. Some microwave detector diodes can be damaged with as little as 1 mA of current. Replace the 2K0 resistors with 10-15K resistors, or lower VCC to prevent damage .



Above — Breadboard of the differential diode matcher. The 2K0 resistors are suspended by a vertically mounted 10M stand-off resistor.

5. Bipolar Junction Transistor Beta Tester

Bipolar Transistor Beta Tester





BJT	Beta
2N3904	193
2N2222a	354
2N3904	172
2N3904	173
2N3904	167
2N3904	151
2N3866	349
2N5109	348
2N4401	236
2N4401	221
2N3906	234
2N3906	139
2N3906	230
2N3906	209
2N3906	227

Above — Disappointed with the transistor beta testers in our common, low-cost digital multimeters, we did the logical thing; designed and built our own. This collaborative project was more an experiment with BJTs than anything else. It's about as simple a beta measurement device as you can make and still get good results. Preventing damage to our parts inventory underpins this design — the 100 Ω emitter resistor plus ~ 10 microamps of base bias keeps the IC low to help avoid smoke since most new small signal transistors have a beta of 100-400.

Ensure the correct polarity for PNP versus NPN transistors. The voltage divider targets 5 volts using a standard ~12 volt supply; I just used whatever resistors were handy and ended up with the 6K8 — 3K3 pair. VCC should be regulated. Perform the measurements with a single multimeter allowing time for stabilization.

To use: Set the potentiometer so that the voltage drop across the 10K resistor is 100 mV. Then move your DMM leads to the 100 Ω resistor and measure the beta. This device measures beta, the static gain at DC.

Measuring beta is a bit inexact since beta is affected by so many variables as follows:

Beta tends to be low at low operating currents and rises and plateaus for medium currents and then falls at higher currents.

Beta tends to increase with temperature.

Beta is affected by the voltage between the collector and emitter -- this is a weak effect except when the voltage is very small.

The beta can vary as the battery depletes in DMM beta testers.



Above — Breadboard of the QRP beta tester. We hope you have as much fun with this circuit as we did.



Above — Testing a 2N2222a. We found measuring transistors to be very instructive; comparing our results to specification sheets, handling the different BJTs, gaining experience — all part of the exciting world of bench electronics. Such circuits, although simple, are great for both learning and design.

6. FET Tester - VGS Measurement Tool



Above — A FET VGS Tester. The final collaborative output from late December 2010: a device to examine VGS. A zener diode value from 6 -7.5 volts or so should work okay. VDS should be greater than the nominal VP for greatest accuracy. The VDS using 7.5 volt zener diode was 4.85 volts. The range of VGS on my breadboard was roughly 6 to -6 VDC without the 470K range limiting resistor; it's up to you if you want to limit the VGS range.

Using the mV scale on your DVM, potentiometer adjust the current until the meter just reads 0. Then move your leads to the VGS test points to read the pinch-off voltage.

The 0 current point will only ever be close. The interesting issue with the 0 point as defined is it never goes to true zero — just zero enough — that point may be hidden if your meter scale truncates lower current measurements to zero. If you're able to repeatedly get consistent VP measurements with whatever method your using, then it's likely accurate.

We thought about measuring gate leakage current across the 10K gate resistor, but accurate measurement is impossible with this device. The gate leakage current is going to be in the low nanoampere region at the very highest unless the JFET is bad. The expected voltage across the 10K resistor would be a few 10s of microvolts. A better way to measure gate leakage is to use the 10M resistance of a DVM instead of this resistor. The DVM then acts as a current meter by measuring the voltage across the 10M resistance. A reading of 200 mV would mean a current of 20 nA.



Above — Front view of the FET tester with a "chicken head" knob on the potentiometer.



Above — Measuring a J310 with the FET tester prototype breadboard.


FET Tester
12.22v
1K
mV = mA
100
1%
V
10K
1%
d
1M
g
s
Current adjust
V
Vgs
6.11v
VDS
.1
Version 2
A
12.22v
100K
10
22 uF
7
+
3
+
741
–
100K
6
10
6.11v
2
4
+
22 uF
B
12.22v
10K
1N4148
+
10
6.11v
1N4148
100 uF
10
10K

Above — Instead of a zener diode, low impedance VCC/2 splitters are shown as A and B; the zener diode is easier.



Above — Reverse view. I didn't bother with the 470K VGS range limiting resistor in my breadboard.



RF — Test and Measurement

RF Workbench Page 1

The first installment of a multi-part series exploring basic 50 Ω RF circuit measurement. This web series borrows heavily from the work of Wes, W7ZOI.

RF Workbench 1 shows a way to measure AC signals and quantify power. As circuit builders, knowing the power gain *or loss* in dB of stages like filters or amplifiers; or the absolute power in dBm of our RF signal sources dominates our bench work.

Ignite your bench measurement — Better measurement fidelity inspires confidence, creativity and fun!

Calculate Power Gain from your Oscilloscope Peak-Peak Voltage

An oscilloscope peak-to-peak voltage provides a popular way to determine power gain or absolute power.



To calculate the power of a sinusoidal waveform, you measure its AC voltage. Assuming your 'scope is calibrated, the first step is to measure the amount of vertical deflection on the screen.

In the figure shown left, the vertical deflection = 4.1 cm. Multiply this measurement by the volts/cm setting of your scope. Lets assume your scope was set to 0.1 volts/cm. Thus the result = 0.41 volts. One final multiplication is required; you must multiply the resultant voltage by the attenuation ratio of the probe. In most cases, a 10X probe is used. Therefore, the measured peak-to-peak voltage is 0.41 x 10 = 4.1 volts. DSOs output numeric voltage readings in addition to that shown — a nice feature.

This signal exhibits a major problem; it's distorted. To calculate the power from peak-to-peak voltage, you require a sine wave. To obtain a sine wave, this distorted signal must be low-pass filtered. Let's examine this topic with some real experiments.

Signal Viewing versus Power Experiments

Measuring 'scope signals takes some skill to get accurate, reproducible results. Consider the following signals taken from an 8 MHz VFO.


Distorted Signal
Low-pass Filtered Signal
RIGOL T'D
8.00457MHz
Vavg(1)=-22.1mV Vpp(1)= 832mV Vrms(1)= 301mV
CH1 200mV Time 20.00ns 31.20ns
8.00576MHz
Vavg(1)=-13.8mV Vpp(1)= 824mV Vrms(1)= 280mV
CH1 200mV Time 20.00ns 30.40ns
Power = 2.38 dBm
10X Probe
Power = 2.30 dBm

Examine the distorted signal on the left and compare it to same signal after low-pass filtering. I calculated the power in dBm from the peak-peak voltages (Vpp) shown as 832 mV and 824 mV: left to right respectively.

Only the sinusoidal power proves accurate. I'll discuss the formula to assess power soon.


Distorted Signal
Low-pass Filtered Signal
RIGOL T'D
8.00623MHz
Vavg(2)=-13.6mV Vpp(2)= 776mV Vrms(2)= 280mV
CH2 200mV Time 20.00ns 30.40ns
8.00391MHz
Vavg(2)=-15.4mV Vpp(2)= 784mV Vrms(2)= 266mV
CH2 200mV Time 20.00ns 30.40ns
Power = 1.78 dBm
50 ohm Terminated Scope
Power = 1.86 dBm

The same 8 MHz VFO examined with a 50 Ω terminated oscilloscope; a superb measurement technique that offers greater sensitivity. In all 4 cases shown, the vertical scale = 0.2 volts/cm.

To better compare the distorted and filtered signals, I attenuated the output of the VFO to allow safe examination with a spectrum analyzer. A spectrum analyzer graphs the power (in dBm) of all measured frequencies on its Y axis against a user defined frequency range on the X axis.



Spectral analysis of the distorted 8 MHz signal. The second harmonic (16 MHz) is about 22 dB down from the fundamental. The signal is rich in harmonics that causes error in the calculation of the output power. Each vertical square is 10 dB. Each horizontal square = 20 MHz. The harmonics go 2x fundamental, 3x fundamental, 4x fundamental and so on.



Spectral analysis of the 8 MHz VFO after passing through an N = 5 Chebyshev low-pass filter. The second harmonic now lies about 40 dB down from the 8 MHz carrier (-40 dBc) and the 3rd harmonic is almost down in the noise. Each horizontal square = 10 MHz.



The breadboard of the 8 MHz oscillator oscillator from the above experiments. The output drove a BJT amp biased to give distortion and a 50 Ω output. I adjusted the frequency with the high Q air-variable trimmer capacitor seen to the left.

Low-pass Filter

Some builders wonder why I only employ sine wave signal generators on this web site. To calculate power, they require no low-pass filtering — now you know why. If you're calculating power from a distorted signal, a stiff low pass filter helps ensure measurement fidelity. All of my signal sources feature a 2nd harmonic response of at least -30 dBc, but -50 dBc is typical. To filter receiver front ends, signal generators, or mixer outputs, I keep several 7 element low-pass filter bench modules on hand that cover several 3 dB cut-off frequencies between 3 and 60 MHz.

Although, any old low-pass filters might work fine, Wes, W7ZOI suggests an N = 5 Chebyshev with 0.2 dB of ripple at about 1.2x the signal frequency as a starting point for designing a test-bench low-pass filter. If you don't know how to design low-pass filters choose a pre-designed filter from a filter table. For the experiments above, I selected a filter from an ARRL Handbook. See the schematic below:



Calculating Power (dBm and mW) from Peak-to-Peak Voltage

To calculate the power from peak-peak voltage, the load impedance (Z) must be known. In RF design, the standardized impedance value = 50 Ω. For CATV and video, 75 Ω is common, and in audio and telecommunication design, a 600 Ω impedance dominates. Although we can technically employ any Z, this web site conforms to the 50 Ω RF impedance standard.

The SI unit of power is the watt. In radio, we might see the term dB used, however, dB is a decibel comparison between 2 signals and not an absolute value like the watt. On the bench, dBm serves as the most common and useful term — dBm is the measured power ratio in decibels referenced to 1 milliwatt.

dBm represents an absolute power — so useful because both large and small signals are quantified with 1 number. Some important bullets follow:

- 0 dBm = 1 mW
- 3 dBm = ~2mW; so doubling the power from 0 dBm equals a 3 dB increase in power
- Increasing the power from 0 dBm to 10 dBm boosts power by 10 dB. The power is now 10X baseline or 10 mW
- 20 dBm = 100 mW
- -27 dBm means that the output has ~500 times less power than 1 milliwatt. -27 dBm = 0.002 mW or 2 microwatts

Hopefully over time, you' ll ingrain the concept of logarithmic power gain or loss (in dB) and power referenced to 1 mW (in dBm). This is bread and butter radio design information you must know.

50 Ω Measurement Virtues

You build a VFO, measure it with your 'scope; calculate the output power into a 49.9 Ω resistor and then record this power in dBm. Let's say it's 6 dBm. VFO output power = 6 dBm.

Next, you place a 6 dB attenuator pad on the VFO output. VFO output power now = 0 dBm.

Finally you connect a 10 dB gain RF amplifer to your VFO. Your VFO output now = 10 dBm. What a beautiful system ! ..... it really gets fun when we measure down at - 30 dBm and so forth.



The chart above really helps you visualize the relationships of mW, AC voltages and dBm



Calculate Power (mW & dBm) from Pk-pk Voltage

Power in mW = 2.5 (peak to peak voltage)^2
Power in dBm = 10 log (mW)

2.0 Volts pk-pk = 10 mW
10 mW = 10 dBm

1.416 Volts pk-pk = 5.01 mW
5.01 mW = 7 dBm

In order to get from peak-to-peak voltage to power, math is required. I show the formula above. You may elect to skip the math and calculate dBm or mW from peak-to-peak voltage with software. A number of programs are available; I wrote 1 here as Applet **F**.



10 log (42)

10 log(42) = 16.2324929

If you lack a scientific calculator, Google has math functions. Shown above = a logarithm calculation

In Search of 50 Ohms

How do I establish a 50 Ω output impedance in my RF amplifier? I get this question often.

From my experience, in **simple** amplifiers lacking negative feedback, a 50 Ω output impedance must be created by inserting a resistor somewhere in the circuit that forces a 50 Ω output impedance.

For example, we might use a 50 Ω collector resistor in a BJT amplifier (or a 50 Ω drain resistor in a JFET amplifier), or place a fixed resistor in parallel with the collector/drain transformer and use a secondary winding to establish the 50 Ω output impedance. Sometimes we'll place a series resistor (say from 22 to 51 ohms) on the output of an emitter or source follower to bring the low output impedance up to 50 Ω. These form basic explanations and usage examples may be found on many schematics on the QRP / SWL website.

We experimenters also employ negative **feedback** with or without output transformers to establish a 50 Ω input and/or output Z and I show many examples on this site.

The following diagram explores 1 method to get a 50 Ω output impedance in a simple amplifier. It doesn't matter if the transistor is a JFET or a BJT, the principle is the same. This diagram and tutorial are simplistic and meant to help novice builders learn to design their own amplifier stages. You may connect any resistor value across the output of a transformer to calculate power, however, this web site only considers 50 ohms.



Broadband Amplifer with 50 Ohms Output

How to determine # turns for smallest link:

The smallest winding should have 4X the XL
XL = 50 ohms
4 x 50 ohms = 200 ohms

For FT37-43 ferrite toroid:

3.5 MHz	minimum 5 turns
5.0 MHz	minimum 4 turns
7- 10 MHz	minimum 3 turns
14 MHz	minimum 2 turns

1800 / 50 = 36 or 36:1 Z ratio
Square root of 36 = 6
Therefore the turns ratio is 6 : 1

The above diagram describes a broadband (untuned) amplifier. I employed a FT37-43 ferrite toroid: a common part. Other ferrite toroids may be substituted, however the table depicting the minimum number of turns won't apply.

Consider the BJT amp shown. The transformer primary winding is shunted with a parallel 1800 Ω resistor. The 1K8 resistor "forces" a 1K8 ohm collector output resistance in the primary winding.

To transform the 1800 Ω primary impedance to 50 ohms; use a 3 turn secondary link. Calculate the primary to secondary turns ratio as follows:

1800 ohms divided by 50 ohms = 36. The impedance ratio = 36:1.
The turns ratio is the square root of the impedance ratio; thus the turns ratio is 6:1. The primary winding must have 6X the number of turns of the secondary winding. In the 3rd RF Workbench web page, you'll see that the above explanation pertains to the "ideal transformer", however, the concept is useful — especially to the target audience of this website.

New builders might ask — why not wind 6 turns for the primary winding and 1 turn for the secondary winding? We avoid this because the smaller or secondary winding should have have a minimum inductive reactance (XL) of 4X the impedance it is connected to. Thus for a 50 ohm circuit, the minimum XL = 200 Ω at the design frequency.

This design rule serves only as a rough guide. We employ the minimum 4X rule because employing an XL less than 4X may create unwanted signal losses and affect the smaller winding's impedance. The table to the right of the amplifier shows the minimum numbers of secondary turns for a few common frequencies with the FT37-43 ferrite toroid.

Thus for our 7 MHz amplifier, we need at least 3 secondary turns and multiply this number by the turns ratio to give a 18:3 turns ratio. You might also choose 24:4.

For ferrites other than the FT37-43, calculate the minimum number of turns with the XL= 2 pi * F*L formula and detemine L from the turns versus AL toroid data, or measure L with an inductance meter.

For AC measurement a 50 Ω purely resistive load should be temporarily connected between the output link and ground. This might be a 51 ohm resistor, a 49.9 ohm 1% metal film resistor, 2 parallel 100 ohm resistors, or some other "50 Ω" load. We measure peak-to-peak voltage across the load and then calculate the power in dBm or mW. After measurement, the temporary 50 Ω load is removed and the circuit connected to the succeeding stage.



51 and 49.9 Ω resistors

We measure the peak-peak voltage across this 50 ohm resistor with a 10X 'scope probe; or alternately may connect the device output to a 50 Ω terminated scope to measure peak-peak voltage to calculate power.

I normally measure in a 50 Ω measurement environment and temporarily solder a BNC connector onto my breadboard and connect this port to a 50 Ω terminated scope with coax. After testing and voltage measurement, I remove the RF connector and then build and test the next stage.

Case Study


Case Study
12.24v
100
.01
100
.001
.001
B
VPP(1)= 3.08V
C
VPP(1)= 2.00V
13
3
attenuation
pad
L1
T1
A
VPP(1)= 12.1V
CV
CV
50 Ω
51
6K8
20 pF
Q2
d
g
s
Q1
100K
3K3
270
.001
470
15 pF
50.0 MHz
3rd overtone
Q1 = 2N3904 Q2 = J310
L1 = 13t T25-6
T1 = 13t primary : 3t secondary T25-6
CV = 2.5 -10 pF trimmer cap

Pretend that you breadboarded the above circuit entitled "Case Study". This is a 50 MHz crystal oscillator and buffer. The crystal fundamental frequency = 16.7 MHz, but the L1 tank is tuned to its 3rd overtone; 50.0 MHz. You measure and record the peak-to-peak voltages at the points labeled A, B and C.



The peak-to-peak voltages are shown as Vpp. The vertical scale (volts/cm) is shown on the bottom of each figure.

Examine Point A. The AC voltage = 12.1 volts peak-peak. Compare this to the peak-peak voltage at Point B. Note the difference. Some builders emailed me after they measured similar differences on the primary and secondary transformer windings of their circuits with a 10X probe. These builders felt something must be wrong. All normal; you can expect the peak to peak voltage to roughly decrease (or increase) by the transformer turns ratio.

The 12.1 volts peak-peak decreased by a factor of 4.3 (13 / 3 turns ratio) which is 2.8 volts peak-peak. In our case, the measured secondary peak-peak voltage was 3.08 volts — in the ballpark. Please remember this serves as a **coarse** guide only. It helps you to know what to reasonably expect during signal viewing.

Peak-to-peak voltage changing in accordance with the transformer turns ratio represents a simplistic explanation describing the "ideal transformer". To understand real world transformer function, you must contemplate factors such as Ohm's law for AC, conservation of energy (this is what causes the voltage to drop while preserving power) and basic transformer behavior. These principles are explained in publications such as The ARRL Handbook for Radio Communications, or the RSGB Radio Communication Handbook. An old high school physics text book might prove a better reference.

Here are the case questions:

1. Calculate the power in dBm at point B
2. Calculate the power in dBm at point C
3. What is the attenuation in dB of the 50 ohms attenuation pad?
4. What is the output power in mW of this stage?

Click on this link for the answers and to see the actual resistor values of the attenuator pad.

Finally, placing a 10X probe at Point **A** will de-tune the L-C tank circuit somewhat and thus alter the AC voltage. In real-world building; to tune Q2, tweak the variable capacitor (CV) with your 10X probe connected to Point C.



The breadboard of the 50 MHz oscillator prototype.

Oscilloscope Probing

10X Oscilloscope Probe

Please refer to EMRFD Chapter 7 for great information about measuring power in RF circuits. The 10X oscilloscope probe is one of the most important measurement tools to have on your bench. There are countless web articles concerning the 10X probe, so I don't have much to add.

Take care of your 10X probe: don't solder components you've clipped your probe to; avoid setting heavy objects on the cable; store it carefully and inspect it frequently.

When do you use a 10X probe ? Measure with a 10X probe for in-situ ("in place", or "in circuit") voltage measurement and in situations where you can afford a 10X reduction in sensitivity. In low level measurements such as millivolt level measurements, the reduced sensitivity of a 10X probe may reduce or disallow accurate measurement. Additionally, the 20 pF or so capacitance of a 10X probe can detune resonant circuits; especially at VHF on up.

Close up of the Rigol oscilloscope probe 10X and 1X switch.

50 ohm Terminated Oscilloscope

At RF, we generally work with (or try to work with) circuits with 50 Ω impedances. If possible consider performing your measurements in a purely 50 ohm environment.

That is — instead of using a 10X probe, shunt the oscilloscope input port to ground through a 50 Ω resistor and connect your test circuit to the 'scope with 50 ohm impedance coaxial cable. On my 'scopes, I have Channel 1 set up for the 10X probe work and Channel 2 set up for a 50 ohm environment.

I asked Wes about the benefits of performing measurement in a 50 Ω environment. I learned the main advantage of a 50 ohm approach is a well defined port impedance. The second virtue; a 10X greater voltage sensitivity — the increased sensitivity for low level measurement amazes me. In some cases, small signals that I couldn't accurately measure with a 10X probe, gave an excellent scope tracing with more consistent voltage readings in a 50 Ω environment.

You also may enjoy improved signal viewing. For example, in a few cases I have observed harmonic distortion with a 50 ohm terminated scope unseen with a 10X probe I confirmed this distortion with a spectrum analyzer.

If you have never performed measurement in a 50 Ω environment, consider trying it out — you'll enjoy it. You may buy commercial 50 Ω feed-through devices that connect to your oscilloscope input, or homebrew your own, but try to keep the 50 ohm termination as close to the oscilloscope input as possible.



Establishing a 50 Ω impedance measuring environment. The oscilloscope input is terminated with a 50 Ω resistance and connected to a device with a 50 Ω output impedance via 50 Ω coaxial cable.

Try not to routinely connect a feed-through attenuator pad to your feedthrough 50 Ω 'scope terminator — error may arise.



My very first homebrew 50 Ω scope terminator module with 2 female connectors. I connected this module to my oscilloscope input via a commerical 9 cm long 50 Ω coaxial cable with a male connector on each end.

Two parallel 100 ohm resistors formed the 50 Ω load. Ideally, the 50 Ω shunt resistor should be right at the 'scope's female BNC jack — so this homebrew module shown fell short as a stalwart 50 Ω terminator. Inspired to move to a 50 Ω environment and lacking a male BNC connector, it did the job until my commercial version came by mail. You might find oscilloscope feedthrough terminators for sale at Ham festivals.

An ideal homebrew solution — place a male and female BNC connector in a small metal box very close together to allow a very short interconnecting wire. The box would hang off of the oscilloscope. Better still are commercial, shielded 50 Ω feed through terminators which thread right onto the oscilloscope's female BNC input jack.



Above — a commercial 50 Ω feed-through BNC terminator on my oscilloscope input.



Above — Measuring in a 50 Ω environment. Bliss!   Я люблю это.

RF Current Sampler

Figure 1



All ports are terminated in 50 Ohms

RF sample port will present as 0.5 Ohms in series with the RF signal path

Figure 1 shows a basic circuit to sample RF current from a power stage such as a QRP transmitter. Many experimenters lack 50 Ω step attenuators rated to handle transmitter-level power. One basic solution is to sample the RF current of the power amplifier using a wideband step-

down transformer. Terminate the RF current sample port with a 50 Ω impedance device. This may include a spectrum analyzer, power meter, receiver with an attenuator, or a 50 Ω terminated oscilloscope.
A usage example = examining a transmitter's spectral purity with a spectrum analyzer. The output power at the sample port will drop by 20-22 dB. A 50 Ω impedance step attenuator can be used to further reduce this power level to whatever you want. For this chore, a typical experimenter's 1-2 watt step attenuator works, since it never "sees" the higher wattage transmitter power.

For example, a 5 watt amplifier 20 dB down is 0.05 watts or 50 mW at the RF current sampler port. 50 mW = 17 dBm. To examine this signal with a spectrum analyzer you may wish to decrease the power down to -27 dBm. The following chart shows the basic process.



50Ω

RF power = 5 watts = 44.72 V pk-pk = 37 dBm

RF power at sample port assuming 20 dB attenuation:
RF power = 50 mW = 4.48 V pk-pk = 17 dBm

Say we want -27 dBm power for examination in a Spectrum Analyzer

Desired RF power = .002 mW = 28 mV pk-pk = -27 dB
Therefore we must further attenuate the signal 44 dB

With the RF sampler, you can do all of the attenuation (64 dB) with a common, low-power step attenuator.



A Hammond chassis shields the RF current sampler used on my bench.


Transmitter Spectrum Analysis
Transmitter
Attenuator
rated for the applied power
Low-level power meter
Spectrum Analyzer
A
All modules 50 Ω
Transmitter
RF Sampler
Dummy Load
rated for the applied power
B
Attenuator
Spectrum Analyzer

The above graphic illustrates 2 methods to examine the output of a transmitter in a spectrum analyzer. Method B is described above. The dummy load must handle the transmitter output power, however a 5 or 10 watt dummy load is easy to make. Method A requires a step-attenuator which can handle the transmitter output power. The low-level power meter promotes the need to quantify the output power before you connect anything to the output of the attenuator. This is also true for Method B.

Always measure the output power at the RF sample port with your oscilloscope or low-level power meter before hooking up any expensive low-level measurement device such as a spectrum analyzer! осторожно!

Miscellaneous Photos

Feed-through
terminator
DC to 1GHz
50Ω/1W
Made in China

TA051
CE
Sales order 62403
BNC feedthrough 50R 1W 1GHz
Pico Technology Limited
www.picotech.com

MALE TERMINATOR 50Ω +1%

Above — a 50 Ω BNC terminator. These are essential QRP work bench items and may be found on eBay for cheap.

Click for a photograph of 4 of my BNC RF port terminators: 27, 50, 75 and 100 ohms from left to right — useful to calibrate and test RF circuitry.

QRP SWL HOMEBUILDER

RF — Test and Measurement

RF Workbench Page 2

Welcome to part 2 of a web series exploring basic RF measurement and bench practices. This installment builds on the information from the RF Workbench Page 1

I share introductory and practical content on attenuation, the return loss bridge, insertion loss or gain and spectrum analyzers. Consult EMRFD and use your favorite web search engine for more information.

The Attenuator Network

Like onions in your kitchen, the importance of attenuators can't be overstated. On the bench, attenuator pads go in nearly every test circuit to deliver correct power and/or help match port impedances.

Think of attenuators as passive networks that intentionally insert power loss between 2 components independent of frequency. For example: you might follow a 50 Ω signal source with an attenuator to decrease its power, increase its return loss, and/or buffer it from downstream impedance changes.

Most attenuator networks have fixed input and output impedances.

The input and output impedances may be the same, or different.

Attenuation may be fixed or variable. Most often, we use simple, fixed resistive pads that function as voltage dividers.

Express attenuation in dB.

Attenuators increase return loss and reduce VSWR.

Attenuators may function as buffers to isolate stages.

All attenuators on this web site feature 50 Ω input and output ports.



The desired response of an attenuator network. Practically speaking, device construction techniques including shielding will limit how high in frequency your attenuator will properly operate.

GENERAL ELECTRIC
AEROSPACE
ELECTRONICS DEPT.
INSERTION LOSS 0DB
Attenuator
MODEL 30-0
Zo= 50 OHMS
IN
20DB
20DB
20DB
20DB
10DB
5DB
3DB
2DB
1DB
KAY ELECTRIC CO.
PINE BROOK, N.J.

A pair of commercial 50 Ω input/output impedance step attenuators from the past. Occasionally, you'll find them for sale at Ham festivals or estate sales. Most work well for HF and perhaps even VHF work depending on their design and condition. Visually examine and test the attenuator before use.

How to Design and Build Attenuator Networks

To design attenuators with a 50 Ω input and output impedance, I recommend viewing a table. Click for a table.

After choosing the degree of precision; solder up 2 or 3 resistors and you're done. Nearest value 5% tolerance resistors offer reasonable precision for our popcorn circuits, but combining 1% and 5% tolerance resistors works too.

Choose low inductance resistor such as carbon film types and strive for short lead lengths. Well consider resistor power dissipation — for example, an 8 dB attenuator pad will dissipate 84% of the RF passed through it. I have seen attenuator pads that were exposed to high power and some or all of the resistors were burnt and turned to charcoal. Clearly the operator did not regard the power rating of the attenuator resistors. Refer to EMRFD Section 7.4 for practical information concerning attenuator design and power dissipation.

Three of the attenuator pads from my bench attenuator drawer. When using Ugly Construction or its variants, you can solder in, change, or remove attenuator pads at a whim. A small stock of these pads speeds up your work flow.



A 10 dB attenuator pad from my collection. This box uses two 100 Ω (5%) resistors and a 68 ohm (1%) resistor for the 96.2 and 71.2 ohm resistances called for. I used the 1% tolerance part because all my 68 Ω resistors are metal film 1% tolerance 1/4 watt types. Perhaps, I'll pursue a closer match to the calculated resistor values 1 day, but this module works okay. You may also stick 2 seperate attenuators in the little Hammond box shown.

6dB ATTEN
FREQUENCY:D
10dB ATTEN
FREQUENCY:D

Two commercial BNC feed-through (in-line) attenuators. I use these *every* day and prefer them over homebrew R networks since they don't require a coaxial cable. I own many: two 6 dB, two 10 dB, one 3 dB and a 20 dB: all were purchased on eBay.

VAT-15
15 dB ATTENUATOR
50 OHM
VAT-6
6 dB ATTENUATOR
50 OHM

Two commercial SMA in-line attenuators for my VHF and UHF experiments: 6 and 15 dB. Click for a marker table with 4 data points derived from sweeping these 2 filters.

Step Attenuators

A step attenuator belongs on every serious RF workbench. They allow in-situ attenuation adjustment with a degree of precision as low as 1 dB. Step attenuators are nothing more than switched calibrated resistances and the switches can be SPDT, relays, rotary or digitally-controlled types. The quality and price of commercial attenuators varies widely. Experimenter concerns include the minimum attenuator insertion loss, power rating, return loss, noise from switch contacts and noise from the resistors themselves.

A homebrew step attenuator makes a great weekend project and almost every radio handbook contains 1. Web linked projects plus commercial kits may be found online — use your favorite search engine to find them.

Some homebuilders prefer 1% metal film resistors to keep resistor noise down. Stick your step attenuators in a metal, RF-proof box and insert quality interfaces such as BNC, N or SMA connectors. Your needs, budget and parts collection determine the outcome when you home build one.

Serebriakova Attenuator - Серебрякова аттенюатор (50 Ом)



The Serebriakova; a simple, variable attenuator well suited for QRP homebuilding. Filled with gratitude to its Russian designer's family, I share this contribution with my readers. This attenuator network makes signals smaller or larger in a 50 ohm environment via a potentiometer. My analysis indicates acceptable performance considering its simplicity. The input match is close to 50 Ω across the range of the potentiometer. The output match across the potentiometer range is mediocre. Click here for a DC match analysis from Wes, W7ZOI. As shown, you wouldn't place this device on your main bench signal generator output as the output impedance diverges widely during amplitude adjustment.

Add fixed attenuator pads on the input and/or output to improve matching into 50 ohms. This circuit could serve in multiple applications including an RF gain control on a receiver front end, for bench measurement (when adapted) and for a low-level transmitter gain control. The Serebriakova attenuator may function up to 500 MHz in a carefully constructed, shielded box. The input and output capacitors may be omitted below 30 MHz. The attenuation varies a minimum of 20 dB when turning the potentiometer from CCW to CW. Click for a build by he yl.


Adapted Serebriakova Attenuator
50 Ω input
220
100
22
DPDT bottom
68
220
100
- 4 dB
- 10 dB
Use a small pot if possible
Pot should be new and clean
22
50 Ω output
500
220
-4 dB
220
47
can increase to 6 or 10 dB

A variant of the Serebriakova attenuator is shown above. Input and output matching are enhanced by fixed attenuator pads. The input match into 50 ohms is fine. After testing, I learned that the fixed 4 dB output attenuator pad is likely too low to ensure a wide range output match into 50 ohms. A 6 or 10 dB output pad is preferable, however, if this is your only variable attenuator, the device would then only be usable for very low-level work. You can decide what value of input or output pads to use.

A new, clean and small size 500 ohm pot works best. Store your potentiometer collection in sealed plastic bags to keep out workshop and house dust.



Serebriakova Attenuator RL and VSWR @ 14 MHz			
Setting	Input -4 dB	Input -10 dB	Output
CCW	27.9 dB; 1: 1.08	30.6 dB; 1: 1.06	9.6 dB; 1: 2.00
Midrange	17.08 dB; 1 :1.30	25.2 dB; 1: 1.12	10.5 dB; 1: 1.85
CW	25.4 dB; 1: 1.11	30.8 dB; 1 :1.06	21.2 dB; 1: 1.19

Shown above are return loss (RL) and VSWR measurements performed on the adapted Serebriakova attenuator shown above. Clearly the input match is better than the output match. The output match did not significantly change when the attenuation switch was moved from 4 to 10 dB attenuation or back.

Based upon these values, it might be a better compromise to put a 3 to 4 dB pad on the input and a 10 dB attenuator pad on the output to ensure an output RL of at least 20 dB. Some might argue that the output RL should be higher. Perhaps, but the match is pretty good for such a simple circuit. Let's put it in perspective; a commercial signal generator that sells on the Internet for $450.00 U.S dollars was measured by a builder I know in the UK and he found a best case RL of 10 dB ! Jim later sold it and built a homebrew signal generator with a 35 dB return loss at all frequencies.

Fixed attenuator pads provide a good remedy for mismatched ports and I discuss why and how in the next section.



The shielded, adapted, Serebriakova attenuator. When home building your personal version, strive to make the AC connections as short as possible. The above device has nearly 23 dB of variable attenuation at 14 MHz. If you can't build, find, nor afford a precision step attenuator for your QRP workbench, this device may work okay for you.

Impedance Matching, Return Loss and VSWR

We radio folks build, buy and apply lots of gear with a stated *nominal 50 Ω input or output impedance*. In truth, a *pure* 50 Ω impedance occurs rarely and components in an RF system are frequently mismatched. Almost every Ham radio operator matches their antenna impedance to their feed line + radio to maximize transmitter output power — but radio and antenna system matching is often the only case where these Hams match their gear.

In contrast, we experimenters, tirelessly match our 50 ohm RF system components — this work flow avails our **modus operandi** on the bench**.** And so, we builders match the input and/or output ports of *all* our RF stages: signal generators, filters, splitters, antennas and so on. You can easily measure the impedance match of your RF components with a basic device based upon a Wheatstone bridge; the return loss bridge. First, let's discuss matching a little more:

On the RF Workbench, we talk about return loss, reflection coefficient and VSWR to quantify impedance matching. I only consider return loss and VSWR on this web site.

When 2 system components are impedance matched, maximal power transfers from 1 device to the other. If the impedances are different, RF power is reflected back to the signal source. This reduces the amount of power delivered to the load. Transmitted and reflected waves moving along a transmission line superimpose and cause standing or stationary waves. The greater the impedance mismatch between the 2 components, the larger the amplitude of the standing waves. Mathematical formulas compute how much power is lost due to mismatch. Consider reading a great tutorial on SWR, Return Loss, and Reflection Coefficient linked here by Wenzel Associates.

Return Loss

Return Loss = the difference between the outgoing incident power and the reflected power as a result of the mismatch between the the signal source and its load. Return loss is expressed in dB as a positive number on this web page. The higher the return loss, the better the impedance match. An ideal prefect match would have a RL of infinity; that is, no power is reflected back to the signal source and all of the incident power is delivered to the load. If a circuit has no load (open circuit), the RL is 0 dB — all of the power is reflected back to the signal source.

Other terms quantifying return loss are S11 and S22, however S11/S22 are the negative of return loss: RL = 20 dB or S11/S22 = -20 dB. We say S11 as S — one — one and S22 as S — two — two. I discuss these S-numbers, or Scattering Parameters elsewhere.

VSWR

Voltage standing wave ratio is another measure of how well the components in an RF network are impedance matched. Increasing the return loss lowers the VSWR and vice-versa. Most amateur radio enthusiasts are familiar with VSWR and often refer to it as "match" or "SWR". RL and VSWR can be derived mathematically from one other. VSWR = [10^(RL/20) + 1] / [10^(RL/20) - 1]. **Note X ^ Y means X raised to the power of Y therefore 2^3 = 2x2X2 = 8.**

Thus a RL of **10 dB** = 1: 1.92 VSWR and **20 dB** = 1:1.2 VSWR and **30 dB** = 1:1.07 VSWR

In EMRFD, Wes presents a return loss bridge as Figure 7.41. This circuit, shown below is easy to build and use.



The 50 Ω impedance detector may include a spectrum analyzer, power meter, receiver with an attenuator, or a 50 Ω terminated oscilloscope. On my bench, a 50 ohm terminated scope is favored.

Let's measure the return loss of a 27 Ω resistor to learn how. The procedure with a 50 Ω terminated 'scope follows:

Connect a 50 Ω output impedance signal generator to the bridge RF input port with 50 ohm coax;

Connect a 50 ohm terminated oscilloscope to the detector port via 50 ohm coaxial cable;

Record the peak-to-peak (open circuit) voltage with no load on the end of a short coax cable connected to the unknown Impedance port;

Record the peak-to-peak voltage with "unknown" coaxial cable terminated with the 27 Ω resistor

Calculate the power difference in dBm between these 2 peak-to-peak voltages.

Return loss = the difference in dB between these 2 values calculated by hand or with software. Please refer to the RF Workbench Page 1 for information how to calculate power. I wrote a JavaScript Applet that take these 2 peak-to-peak voltages and calculates RL and VSWR; its labeled **K** on this web page.

Before measuring the unknown RL of a circuit, we usually connect a 50 Ω terminator to the unknown impedance port and calculate the best possible return loss: we refer to this value as bridge directivity — the best possible match for that return loss bridge at that test frequency. I keep a permanent 50 Ω terminator + a barrel connector on my bench for this purpose.

Click for a photo of the gear I use for all RL measurement. *Best viewed at full resolution*

Lets run through the procedure to measure the return loss of a 27 Ω resistor again, but with added photographs and 'scope captures. I tested at 14.070 MHz.

Above — We'll measure the return loss of this device; a 27 Ω resistor soldered on a BNC connector. We call this a resistive terminator and I keep a small collection of 27 - 100 Ω terminators on-hand for calibration purposes.



Acquisition
Normal
2.00GSa/s

Channels
DC 10.0:1
DC 1.00:1

Measurements
Freq(1): No signal
Pk-Pk(1): No signal
Pk-Pk(2): 135mV
Freq(2): 14.07MHz

Shown above — The peak-peak voltage with a 14.07 MHz oscillator connected to the RF port; a 50 Ω terminated scope connected to the detector port; and a 20 cm — unterminated — 50 Ω cable connected to the unknown impedance port. **The open circuit measurement.**

Above — Next, I connected the 27 Ω terminator to the unknown impedance coaxial cable with a through-connector interface.



Normal
2.00GSa/s

DC 10.0:1
DC 1.00:1

Freq(1): No signal
Pk-Pk(1): No signal
Pk-Pk(2): 35.8mV
Freq(2): 14.07MHz

Shown above — The peak-peak voltage with a 14.07 MHz oscillator connected to the RF port; a 50 Ω terminated scope connected to the detector port; and a 27 Ω resistive terminator across the end of the unknown impedance cable**. The reflected signal from a 27 Ω resistor.**



K. Calculate Return Loss and VSWR (50 Ohms Detector)

http://www.qrp.pops.net/qrp-java-calculator.htm

Enter the detector signal in pk-pk volts when the unknown port is terminated in an open circuit: 135

Enter the detector signal in pk-pk volts when the unknown port is terminated in the unknown impedance: 35.8

Return loss = 11.53 dB, VSWR=1:1.72

Shown above — Calculating the return loss and VSWR of the 27 Ω resistor with my JavaScript Applet **K**. mV versus volts peak-peak does not matter since we calculate a ratio of power.

Use the return loss measurement procedure depicted above to measure the return loss of any device you choose. If your D.U.T. has 2 ports, terminate the unmeasured port in 50 Ω. I show further RL measurment examples on RF Workbench 3.

I measured the return loss of some commercial gear in my shack and yard and will share 2 examples: 1) An expensive commercial transceiver I borrowed had an input port return loss of 15 dB (a 1.4:1 VSWR) The return loss of 15 dB indicates that the reflected wave power is 15 dB lower in power than the incident wave. 2) With a borrowed commercial bridge, my tuner-matched antenna revealed a return loss of ~60 dB.



A RL bridge from my bench built with 51 Ω 5% tolerance resistors. I show a better RL bridge and some other experiments on RF Workbench 3.

Return Loss and the Attenuator Network (How Do Attenuator Pads Improve Component Matching?)

We routinely employ attenuator pads to increase return loss in a 50 Ω RF environment. For example, let's say you're testing a signal generator and measure a return loss of 6 dB. If you place a 10 dB attenuator pad after the signal generator, the return loss increases to 26 dB. If we used a 6 dB pad instead, the return loss would now = 18 dB. In both cases the return loss is increased by 2x the attenuator pad value. The doubling of return loss occurs because both the incident wave and reflected signals pass through the attenuator pad — that's how attenuator pads improve matching.

Attenuator pads reduce power, but that is why somebody invented the RF amplifier.

What is the minimally acceptable return loss for a device such as a signal generator? No single answer exists. The minimum return loss depends on the context: are you making precision circuits or just tuning an antenna?

Precision Circuits:

For amateur experimenter bench circuits, aim for a return loss of at least 20 dB. This often means adding an attenuator pad to the ports of your signal generator, amplifier, or other device to get a minimum 20 dB return loss. For an electronic engineer, the minimal return loss is probably higher; maybe 30 dB or so. I have read conflicting opinions about this and for some people — me included — design overkill is normal.

Antenna tuning:

When tuning an antenna for full transmitter output power, the minimal return loss is around 14 dB (a VSWR of 1:1.5). If you measure an antenna system return loss of 14 dB or better, the match is fine. Many Hams will protest a 1:1.5 VSWR and ardently chase a 1:1 VSWR on every frequency with their antenna tuner.

A Method to Measure Insertion Loss or Gain

Often, we want to measure the gain of an amplifier, or the insertion loss of a filter, or attenuator pad. I show how to do this with a 50 Ω terminated scope:



1. Peak signal generator or tweak filter tuning capacitors for maximum signal in oscilloscope

2. Record AC voltage in scope

3. Remove Device Under Test and replace with BNC barrel connector

4. Record AC voltage in scope

The circuit starts with a signal generator set to the frequency of interest. I show an attenuator pad in this diagram to stress that the signal generator output port must have a return loss >= 20 dB.

Connect the input of the 50 Ω **D**evice **U**nder **T**est to the generator output via 50 Ω coax

Connect the 50 Ω output of the D.U.T. to your 50 Ω terminated oscilloscope

Turn on the signal generator and if needed, peak the signal; In the case of a low-pass filter, the signal generator frequency control is tweaked to give a maximum pk-pk voltage in your 'scope. When evaluating a band-pass filter, tweak the filter trimmer capacitors for the maximum signal at the desired center frequency. Signal peaking ensures that losses caused by the filters are not caused by the filter mistuning, or in the case of the low-pass filter, to allow for cutoff frequency deviation caused by component value variations. It may be necessary to increase the signal generator amplitude to view a good quality signal in your 'scope.

Record the peak-to-peak voltage.

Remove the DUT and replace it with a BNC through-connector and record this peak-to-peak voltage.

Calculate the power in dBm of the 2 recorded voltages — their difference equals the insertion loss or gain in dB. I wrote a JavaScript Applet to do this. Click and scroll to **H**

This awesome measurement technique controls the input and output impedance and uses the same coaxial cables with and without the D.U.T. for accuracy. Some builders might choose to terminate the D.U.T. with a 50 Ω resistor and measure with a 10X scope. The capacitance of the probe may alter measurement in some cases. As always, choose your measurement technique based upon whatever gear you own and how exacting your standards are.



Spectrum Analyzers - Comments from the Workbench

Electronics professionals ruminate that spectrum analyzers are uncommon because experimenters perceive them as esoteric and difficult. My own opinion differs. Spectrum analyzers are relatively uncommon because of one reason - cost. I have watched prices on sites like eBay with amazement. The ads go something like this: 1.5 GHz spectrum analyzer for sale. Built in 1982. Ships in 2 pieces weighing over 22 kilograms. Minimum bid $1850.00. *And...sorry, I live in Florida, U.S.A. and in all likelihood, shipping these 2 heavy pieces is going to cost you a fortune. In the attached ad photos you can see lots of wear and tear, plus some screen burn-in on the display....* Guaranteed to turn on however!

Perhaps I exaggerate or even lampoon the perceived value of old boat anchor spectrum analyzers, but I have bought and sold cars for less money. Be prepared - spectrum analyzers are not cheap. They are however, very cool and open the door into a truly fascinating world. Frequency domain circuit measurement (spectrum analysis) addicts and intrigues. Homebuilding a spectrum analyzer is a serious option, but requires advanced building skills. Click and click for the W7ZOI/K7TAU project.

In recent times, the Rigol DSA-815 spectrum analyzer with tracking generator proved a game-changer to the bloated price of heavy, old and tired gear. Click for a Rigol datasheet. Signalhound also sells spectrum analyzers and tracking generators . A tracking generators *plus* spectrum analyzer allows you to sweep your device under test over a range of frequencies.

Prior to using a spectrum analyzer, I casually considered shielding stages or placing critical pieces in RF-proof boxes. Quickly I learned that RF in our home and community can and does get into your projects. p>



The center frequency of the display = ~150 MHz. The signal spikes appeared and disappeared after 4-9 seconds or so — after a little detective work with my scanner, I learned they were local police and ambulance FM radio conversations. I noticed this interference when I took the lid off a RF-tight band-pass filter — these signals arose in a 28 MHz superhet receiver !! While low in amplitude, experiences like this inform us to watch for lurking RFI.

I found numerous sources of RF in our home with a spectrum analyzer — the clothes washing machine during its spin cycle proved to be the worse RFI generator. RF-tight shielding with SMA, or BNC connectors and DC feed-through capacitors and aggressively decoupling and bypassing DC lines eliminated many of RFI problems during my experiments. I now better appreciate these anti-RFI techniques.

Spectrum Analyzer Calibrator



Spectrum Analyzer Calibration Oscillator

L7809
Bottom
12v
.1
1K
.1
51
47K
.1
470 pF
47K
470 pF
5 MHz
10K
10K
2N3904

A harmonic rich, spectrum analyzer calibrator designed by Wes, W7ZOI and displayed with his permission. Adjust the 10K potentiometer to provide the output power needed to calibrate your spectrum analyzer. I set mine to -27 dBm. Be careful when connecting signal generators to your spectrum analyzer, since a higher than rated input power may destroy the mixer/front-end of your spectrum analyzer and cost you dearly.



5 MHz Low-pass Filter

RMS voltage
50 Ω
1.2 uH
2.5 uH
1.2 uH
820 pF
820 pF
50Ω terminated scope

Inductors: 28 AWG wire on T37-2
1.2 uH = 17t 2.5 uH = 25t

I used this filter to set the -27 dBm power needed to calibrate my spectrum analyzer.



Spectrum analysis of the 5 MHz spectrum analyzer calibrator.



Breadboard of the 5 MHz spectrum analyzer calibrator.


NO
Spectrum Analyzer
51

Don't use a "50 ohm" termination when measuring with a 50 Ω impedance spectrum analyzer.


Spectrum Analyzer
51
NO

No resistor is required, as the the input impedance of the SA is 50 Ω.

Miscellaneous Photos and Notes

-10 DB PAD
50 OHMS
RETURN-LOSS BRIDGE
RF
?
DETECTOR
MENT
MPLER
S

Some of the 50 Ω modules built during the RF Workbench page 1 and 2 experiments

1 3 6 9 30 dB
10 WATT LOAD

15542
HAT-6+
6 dB ATTENUATOR
50 OHM
15542
VAT – 6
6 dB ATTENUATOR

Amateur Radio Electronic Design

Audio Transistor Input Impedance Experiments

Introduction



I examined audio transistor amplifier input impedance during Spring — Summer 2010 and generated enough content for a web page.

On this web page, I explore determining AF amplifier input impedance by using network theory and calculation, plus direct measurement with instruments containing a Wheatstone bridge. This content emphasizes learning through performing bench experiments and I hope it sparks your own experiments and research into impedance measurement test equipment and theory.

Many RF circuits require termination with stages containing a well defined input impedance. Consider, for example, amplifiers that follow L-C low-pass filters, diode ring mixers or crystal filters — a known impedance (usually 50 ohms) must terminate these stages to optimize return loss. A special case is the diode ring product detector; which must be followed by a 50 ohm input impedance audio amplifier. How do we design or assess a small-signal audio amplifier that has a 50 ohm input impedance? This question spawned every experiment on this web page — the content grew and evolved along with my understanding of this topic.

Audio transistor input impedance may be calculated with equations or software, however, doing the math or using or affording these programs might be problematic for some amateur builders. Additionally, component variances such as transistor Beta and different power supply voltages can causes significant differences between the theoretical and the actual input impedance realized. Further, amplifiers, such as a feedback pair that involve combinations of series or shunt feedback can be difficult to analyze accurately using equations during small or large signal analysis. It may be easier for experimenters to just measure and tweak amplifier components on the bench — the focus of this web page!

As an rank amateur, I have much to learn, and by no means am an expert in electronic design. If you see an error on this web site, disagree with my analysis, or have suggestions for improvement, please email them — I am an amateur hobbyist, who earns no money from this site, and who relies on the assistance of others to keep the content as accurate and vibrant as possible.

The topics:

Part 1: Some basic transistor network theory and how to calculate input Z

- Part 2: 50 ohm input impedance Wheatstone bridge measurement
- Part 3: Measuring unknown impedances
- Part 4: Miscellaneous circuits, scans and photographs.

Notes:

Small signal analysis refers to modeling or examining an amplifier at a single operating point (its bias point) and applying linear equations which assess the amplifier with no signal applied. In small signal analysis, we assume that the signal is so small that transistor gain, capacitance and other factors are static.

Part 1: Some Basic Transistor Network Theory and How to Calculate Input Z

Some basic network theory plus methods to calculate the input impedance of common emitter and common base audio amplifiers.

Three basic small-signal transistor parameters include *beta,* emitter resistance *Re*, and bulk resistance *REB*.

Beta is the term used to designate the current gain of a common emitter circuit — it's the ratio of collector (output) current to base (input) current.

Small-signal emitter resistance; Re = 26 / IE ,or, 26 divided by the emitter current in millamperes. For example, an emitter bias current of 0.52 mA gives a small-signal emitter resistance of 50 ohms, or visa versa . Re is the resistance seen looking into the emitter whether the stage input is the transistor base or emitter terminal. Re is the dynamic resistance of the input junction due to carrier action.

REB represents the bulk resistance of the semiconductor not arising from contact resistance; in other words, it's the DC resistance of the base and emitter leads plus the pn junction. Typically REB = 2 to 6 ohms and is often ignored (your choice) when the current is low — say, for example, < 9 mA for a typical common-emitter voltage amplifier. In large power transistors or for switching operations, the typical REB value may vary. REB, in part, limits the maximal gain of a transistor.

The constant 26 used when calculating the dynamic resistance of a forward-biased PN junction is derived via calculus. Professor Kuhn's website link containing the math.

There is also a base spreading resistance generally known as 'rbb' that, in effect exists laterally across the transistor. A simple model puts rbb at about 100 ohms in series with the base and it's one of the causes of finite transistor frequency response. While interesting, rbb isn't discussed further.


Collector Terminal
R_C
high resistance
Base Terminal
Small-signal equivalent network of a BJT
r_e
$\frac{26}{I_E}$
R_{EB}
Emitter Terminal
Any unbypassed emitter resistance
Transresistance

Above — the small-signal equivalent network of any transistor. re = 26/IE. Also, re + REB + any unbypassed external resistor may be termed the *Transresistance*, a DC ohmic value representing the total resistance of the emitter. The collector resistance RC is high because of its reverse bias. Collector resistance is not considered when calculating input impedance of simple AF transistor stages.

Calculating the input resistance of a common base stage

Calculating the input impedance of a common base amplifier is easy. Input impedance = 26/ emitter current (IE). You can either bench measure or calculate the emitter current using DC analysis. Click for the formula to calculate emitter current . A complete example follows:



Common Base Amp - Calculate Z in

$$VB = \frac{22K}{100K + 22K} * 12 \text{ volts} = 2.16 \text{ volts}$$

$$VE = 2.16 - 0.7 \text{ volts} = 1.46 \text{ volts}$$

$$IE = \frac{1.46 \text{ volts}}{1K} = 1.46 \text{ mA}$$

$$Z_{in} = \frac{26}{IE} \quad \text{(ignoring REB)}$$

$$Z_{in} = \frac{26}{1.46 \text{ mA}} = 17.81 \text{ ohms}$$

If you breadboard the circuit, directly measure IE

12v
R1
100K
1K5
out
22 uF
VB
VE
in
R2
22K
1K
IE

Above — An example common base amplifier and its input impedance calculation. In this example, emitter current is calculated using DC analysis. On the bench, it's better to un-ground the 1K emitter resistor and connect your ammeter between this resistor and ground to directly measure IE. REB was ignored and = 0.

Consider the 50 ohm input Z common base amplifier we often use after a diode ring product detector plus diplexer:



Common Base Amplifier

Return loss = 32.1 dB

150
12.24
47 uF
10K
8K2
22 uF
4K7
22 uF
2N3904
3K3
50 ohms in
(1 KHz)
4K7
IE = 0.51 mA

Above — A common base amplifier built for a direct conversion receiver in Spring 2010. This amplifier is shown in test setup for bench analysis

— with a DC decoupling network and an AC coupled 4K7 resistive load. The emitter current established using 5% tolerance resistors was 0.51 mA. Therefore, the calculated input Z is 26/0.51 = 51 ohms. The return loss of this amplifier as measured with the *active* 50 ohm Wheatstone bridge device described later on this web page was a spectacular 32.1 dB! If a different power supply voltage or biasing/emitter resistors were used, the IE would change and along with IE, the input impedance and return loss.

This amp illustrates that testing and tweaking AF amplifiers on the bench will garner the best results. If I just copy someone else's design; perhaps with a different DC voltage, or decoupling network and don't adjust the emitter current by tweaking the base biasing or emitter resistor resistors, the input impedance could differ significantly. Whenever you build a common base amplifier, measure its DC current and as necessary, tweak resistors to get the current needed for a perfect impedance match. It is good practice to measure all the DC voltages and emitter current on any amplifier you build — you will learn what is normal, what to expect and perhaps detect errors or parts failure(s).

Performing return loss measurement is also a fantastic way to ensure good matching to the 50 ohm impedance diode ring product detector that feeds this amplifier.

Calculating the input resistance of a common emitter stage

Calculating the input impedance of a common emitter amplifier is also straight forward, but not as easy as the common base amplifier.

In the **common base amplifier**, the emitter is the input element, therefore the input signal resistance is 26 / IE + REB. Often we ignore REB. If current of the common base amplifier is for example, 2 mA or so, then the 2-6 ohms of REB may be significant as 26 / 2 mA = 13 ohms. REB may be a factor because 2-6 ohms is a significant percentage of the total input resistance.

For a **common emitter amplifier**, the input resistance looking into the base is Beta (26/IE + REB + RE). Again REB is often ignored. We need to include any transistor DC biasing resistors which are also seen by the input signal as it moves through the transistor base. An example follows:



Above — An example common emitter amplifier re-drawn to illustrate how the input resistances combine to provide the AC input impedance. In this case, the 270 ohm emitter resistor RE is un-bypassed. R1, R2 and the components RE, re and REB are in parallel as the DC supply acts as a short to ground for the AC input signal. The components RE, re and REB (if used) must be multiplied by the transistor Beta value (+ 1) since the resistance looking into the base is Beta times that looking into the emitter.

Therefore: Rin = (B+1)*(re + REB + RE'). Normally we ignore REB so practically speaking Rin = (B+1)*(re + RE')



Common Emitter Amp – Calculate Z in

Beta = 100

$$V_{R2} = \frac{4K7}{4K7 + 10K} * 12 \text{ volts} = 3.84 \text{ volts}$$

$$V_{RE} = 3.84 - 0.7 \text{ volts} = 3.14 \text{ volts}$$

$$I_E = \frac{3.14 \text{ volts}}{270 \text{ ohms}} = 11.6 \text{ mA}$$

Calculate the base resistance R_b [ignore R_{EB}]

$$R_b = (\text{Beta} + 1) * \left(\frac{26}{IE} + R_{EB} + R_E\right)$$

$$R_b = 101 \ (2.24 + 270) = 27496.24 \text{ ohms}$$

$$\text{Zin} = \frac{1}{\frac{1}{R1} + \frac{1}{R2} + \frac{1}{Rb}}$$

$$\text{Zin} = \frac{1}{\frac{1}{10K} + \frac{1}{4K7} + \frac{1}{27496}} = 2.86 \text{ K}$$

Above — The math for the common emitter circuit shown directly above using DC analysis to calculate the current. On the bench, we just measure the emitter current (no need to calculate it). We assume IE = IC for a common emitter amplifier. REB = 0 (when ignored). If the 270 ohm resistor RE was bypassed with an electrolytic capacitor, the 270 ohm resistance would also = 0; and then Rb = Beta + 1 * (26/IE).

Conclusion

This theory explains how to calculate input impedance in 2 basic transistor AF amplifiers. Consult an electronics text for further explanation. Although the arithmetic is simple, quite frankly, it's a little boring. Let's go to the bench and have some fun. I was quite naive about measuring AF amplifier input impedance; however, my experiments yielded some knowledge and a strong appreciation for the Wheatstone bridge network. Onward...

Part 2: 50 ohm Input Impedance Wheatstone Bridge Measurement

Testing for a NULL or measuring the return loss of AF amplifiers with a 50 ohm input impedance.

Refer to the diagram on the right. Redrawn in a way more familiar to builders, the Wheatstone bridge network is just a pair of voltage dividers in parallel. We measure the difference in AC voltage between the ports labeled Out 1 and Out 2. The bridge is said to be balanced and produce NULL or 0 output when Out 1 and Out 2 are equal in voltage. Another description — when in perfect balance, the signal loss due to mismatch between the output ports is infinite. However, if this balance is disturbed by a mismatch between ports Out 1 and Out 2, an AC voltage appears and the return loss decreases in proportion to the mismatch (within limits and providing your instrument can measure accurately).

Let's focus on some practical bench applications in the new millennia: On your bench, you might employ a Wheatstone bridge network to measure return loss (or VSWR) or to simply to detect a NULL indicating a close impedance match between 2 stages. Specific examples include tuning your feed line and antenna, checking the match between a signal generator and a filter, or measuring an audio amplifier input impedance. In my estimation, the Wheatstone bridge lies among the most important test circuits in the amateur designer's arsenal; worthy of study and experimentation.


Wheatstone Bridge Balanced Network
In
Out 1
Out 2
R1
R2
R3
R4
When Out 1 = Out 2, the loss is infinite

Notes:

- The input signal can be AC or DC, but all discussion is confined to an AC signal source
- E96 (1%) metal film resistors were used in all Wheatstone bridges
- All bridges were tested at 1 KHz
- Ensure you do not overdrive your bridge; lest distortion occur! When a bridge is overdriven, you might cancel the fundamental frequency when balancing the bridge, but not the harmonics! Therefore, parasitic harmonics appear in the output that skew the the NULL or return loss values. I learned low pass filtering the amplified bridge output is really important.
- Any distortion in the bridge output means you must reduce your input signal drive level; however, this may reduce the accuracy of the RL measurements. There is no free lunch! You generally want just enough input signal to accurately measure the signal with the bridge at NULL.



Comments from the Workbench

Above — an evolution of the 4 resistor bridge into a device to measure impedance and capacitance. In its classic form, each bridge leg is a resistor voltage divider with a detector connected across ports A and B. If ports A and B have equal voltages and R1 = R2, then R3 and R4 must also be equal; the bridge lies balanced or in a NULL state. If you remove R4 and measure an unknown resistance, the bridge will return to balance after adjusting pot R2 to equal the unknown resistance. In most cases, R2 is calibrated and the impedance is read directly off the potentiometer dial. Bridges can be arranged to measure unknown capacitance, inductance , frequency and other parameters by using precision 1% fixed components, calibrating the 10 turn pot to indicate the desired parameter, or for deriving the unknown value via equations.

Builders of lore used bridges to quantify many values on the bench. Although we have better ways to measure inductance and capacitance today, the Wheatstone bridge is still the *king* when it comes to simple measurement of network impedances; for example, QRP antenna tuners. Some builders use an LED to indicate bridge imbalance.

Building a passive instrument to measure the return loss of a 50 ohm input Z audio preamplifier.

Non-radio folks don't generally understand this — to properly terminate a diode ring mixer, 50 Ω impedance stages are needed. The inspiration driving *all* the experiments on this web page was to design a 50 ohm input impedance common emitter audio preamplifier to follow a diode ring mixer. I could have just used the familiar common-base amplifier popularized by Roy, W7EL, but of course, wouldn't learn anything. Somehow, I became drawn in by curiosity and generated enough content to fill a whole web page.

I decided to try and build some return loss bridges and test them by using known, fixed-value resistors as the unknown impedance. My first bridge, was an AF version of this RF return loss bridge using a junk box 600 ohm, 1:1 audio isolation transformer. It didn't work until I rearranged it as shown in the schematic below.


Audio Frequency Return Loss Bridge
Unknown Impedance
50 Ω Audio Source
T1
50 Ω Detector
49.9
49.9
49.9
T1 = 1:1 Audio Transformer
100 Ω: 100 Ω 42TM030-RC (Mouser)
150 Ω: 150Ω 107D-ND (Digi-Key)

Above — A simple return loss bridge using an AF transformer and 50 ohm detector. Suitable detectors are described here in the section covering return loss bridges — I used a 50 ohm terminated scope. Using 20 log (peak-peak voltage) to crunch the 50 Ω AC voltage into dB, the bridge was measured at open circuit, plus with various fixed 5% tolerance resistors terminating the Unknown Z port. Using a junk box 600 ohm 1:1 AF transformer, my results initially seemed good, but upon analysis were fraught with error. Note the suggested transformers in the schematic.



Above — The very first AF return loss bridge built. Anchored to the ground plane with resistors, the transformer was a 600 ohm *junk box* special. Although I was able to achieve a deep NULL using a 49.9 ohm resistor, the return loss was 86 dB; not possible. Additionally, other fixed resistors gave return loss values more than 4-5 dB away from the proper value. Likely, my junk box transformer lacked sufficient inductance for 1 KHz. For testing your bridge, use a formula to inform you of what RL value to expect for a given fixed resistor.



Calculate the RL of a resistor in a 50 Ω bridge

$$V = \frac{(\text{Resistor value} - 50)}{(50 + \text{Resistor value})}$$

RL = -20 log (absolute value of V)

510 ohm resistor:

```
V = (510 - 50) / (50 + 510)
RL = -20 log | 0.82 |
RL =  1.72 dB
```

Above — The formula to calculate the expected return loss for a fixed resistor placed in the Unknown Impedance port on a Wheatstone bridge. Click for a table of Return Loss values for some non 50 ohm resistors. Your RL values, will rarely be exact, but should be close to the predicted value. A well functioning bridge should yield a return loss of > 40 dB using a 51 to 47 ohm resistor as the Unknown Impedance.



Above — A second bridge was built after obtaining a 100 Ω : 100 Ω AF transformer from Mouser Electronics. This transformer was ideal (each coil has ~ 1H in inductance!). Bench testing indicated good function. My results are tabled below:



Measurement of R L B

Resistor Ω	Return Loss (dB)
10	3.35
22	7.47
27	9.74
33	12.39
39	16.23
49.9	56.73
62	16.54
75	12.82
100	9.15
220	3.95
510	1.63

Above — A table of the above 50 ohm Wheatstone bridge return loss measurements. These results are acceptable. The NULL with a 49.9 ohm resistor was incredibly sharp and garnered a RL of 56.73 dB. My AF source was a low noise 1 KHz, 50 ohm output impedance signal generator.

If you do not need return loss, and only require a NULL to indicate a match, a common 600 ohm transformer may work okay for you.

Building an active instrument to measure the return loss of a 50 ohm input Z audio preamplifier.

The results of my early experiments with a passive bridge were encouraging. Noting that most builders would have difficulty obtaining a 100 Ω : 100 Ω AF transformer, a version using op-amps was sought. My first 3 designs did not work properly and I became discouraged. Some guidance from Wes, W7ZOI allowed me to problem solve and experience success.


100 uF
to VCC/2
VCC = 12.2 v
47K
150
47K
100 uF
150
100 uF
150
unknown impedance
100K
100 uF
100 uF
.047
5
8
R2
22.6K
U1a
R1
2K0
7
6
.47
AF in 50Ω
49.9 Ω
49.9 Ω
2
U2a
1
2K0
17.8K
5
8
high Z buffer
R3
2K0
.0015
U2b
2
4
49.9 Ω
3
7
6
1
U1b
R4
22.6K
low pass filter
fCO =1005 Hz
Q = 5.3
.047
3
4
100 uF
49.9 Ω
100K
VCC/2
2K2
Volts AC
differential amp
VCC/2
R1 = R3 (matched)
R2 = R4 (matched)
Gain = R2/R1
Audio Frequency
Return Loss Bridge
U1 = U2 = LM358

Above — Schematic of my active Wheatstone bridge, amplifier and low-pass filter for measuring the Return Loss of 50 ohm input impedance AF amplifiers. I built 3 copies of the above device; best results occurred when careful layout and planning were employed. Optimal performance occurred when encased in a metal box.

The bridge was built from 1% metal film resistors. 0.047 polyester film capacitors lightly couple the bridge to high impedance op-amp buffers labeled U1a + U1b. My experiments informed me that to minimize loading on the bridge is important. The LM358 is an excellent op-amp choice, but almost any other op-amp could be employed successfully. U2a is the differential amplifier and matching R1 + R3 and R2 + R4 with 1% tolerance resistors is critical; 5% resistors did not work well. The gain is non-critical — feel free to choose reasonable resistor ratios based upon the resistors you have in stock. The differential amp promotes the unfortunate side effect of amplifying both the desired AF source plus any common mode signals. Although common mode suppression is an important consideration when designing instrumentation amps, fortunately, performance is fine. A amplifier topology using a differential amp across the bridge was trialed, but functioned identically to the simpler differential amp shown. Consult a textbook for more information on Instrumentation amps. Much information was gleaned from Professor Ken Kuhn's web site.

The output is low-pass filtered by a single stage Sallen-Key low-pass filter with a peak frequency of 1 kHz and a Q of 5. This filter gain at 5 at 1 kHz is 0.328 at 2 kHz and 0.123 at 3 kHz. Thus, the second harmonic is reduced by a factor of (5/0.328) = 15.2 and the third harmonic is reduced by a factor of 40.6. **Do not omit a low pass filter**. I chose a 1 KHz cutoff, but experimentation indicated a low-pass cut-off frequency as high as 10 KHz may work okay if you plan to use the bridge at frequencies other than 1 KHz.

Power supply decoupling proved important. When less DC low-pass filtering (less than the 150 Ω plus the 100 uF capacitors shown) was employed, some low frequency audio noise appeared in the output.

I measured using a X1 oscilloscope probe on the output of U2b.



Above — A breadboard of the active Wheatstone bridge schematic located above. When tested with fixed value resistors, the RL @ 49.9 ohms was 55.4 dB and close to predicted value with other test resistors. This instrument will be put in a metal case and become a permanent part of my test equipment arsenal.

Part 3: Measuring Unknown Impedances

Building an instrument to measure the input impedance of an audio preamplifier using a NULL.

330
500
680
220
150
75
50
820

Above — One of several Wheatstone bridge circuits built in the Spring-Summer of 2010. In these bridges, the potentiometer was calibrated and the panel labeled using fixed resistances for calibration. One big challenge is range or resolution; dependent on the bridge resistor values and what impedance you are trying to measure. Greatest accuracy is associated with 5 or 10 turn potentiometers, but these are expensive. Often, I used standard, linear taper pots to save money during my experiments. Over 7 different bridges were built and tested. To save time, I didn't photograph many of my projects from the summer.


100 uF
12.2v
47K
100 uF
NE5532N
L78L05
Bottom
47K
100
.15
.33
100 uF
47K
100
100 uF
13
1
14
5
4
5K6
15K
3
8
12
2
7
3
6
2.2 uF
- 3.6 dB
1.8K Z
2K7
.022
U1a
1
1K8
18K
5
U1b
7
9
8
19.4K Ω
total R
18K
1K8
2
4
.0022
6
HEF4093
1 dB ripple Chebychev low-pass filter
fCO 1000 Hz
100 uF
1.0 KHz oscillator
.1 uF
10K
AF Input Impedance
Measurement Tool
Rp
Rs
A
B
Rv
Rx
?
Wheatstone bridge

Above — A complete 1 KHz signal generator, low-pass filter and bridge circuit which became the prototype for most of my experiments in this section. Click for a high resolution photo of 1 of the breadboards during construction.

The 1 KHz signal generator is a digital oscillator built with 2 gates from a 4093. This excellent oscillator uses a single R + C network for tuning and requires a voltage regulator for frequency stability. The output signal is attenuated 3.6 dB and low-pass filtered by 4 poles of active filtering. A 10K pot controls the drive into the bridge circuit. The bridge outputs are labeled **A** and **B** and require buffering, amplification and low-pass filtering similar to the active bridge shown earlier. These functions and some comments on the bridge resistors come later.


RIGOL
T'D
0.00uV
1.00433kHz
Freq(1)=1.000kHz
Vpp(1)= 4.60V
Vrms(1)= 2.18V
CH1 1.00V
Time 200.0us
0.0000s

Above — The oscilloscope waveform from the digital 1 KHz oscillator. Digital clocks fascinate me and this was an untried design. Initially a CMOS 555 timer was considered, however, I own many 4000 series NAND Schmitt triggers and pressed 1 into service. Another good choice might be the 74HC132. The first NAND gate (inverter) contributes 180 degrees of phase shift, while the RC low-pass filter tank circuit digitally shifts the AC the other 180 degrees. Output noise is filtered by both the low-pass filter and the input Schmitt trigger dead band or hysteresis. The result is a fairly crisp square wave that may rival the 555.


RIGOL
T'D
56.0mV
1.01028kHz
Freq(1)=1.008kHz
Vpp(1)= 1.00V
Vrms(1)= 362mV
CH1 200mV
Time 200.0us
0.0000s

Above — The output of the 1 KHz low-pass filter. A sine wave is desirable, but not critical; suppression of energy in the range of 5-10 KHz, informed the filter design goal. At 8000 Hz, the attenuation is > 80 dB. All good.


100 uF
to VCC/2
VCC = 12.2 v
47K
150
47K
100 uF
150
100 uF
150
100K
100 uF
U1 = U2 = LM358
100 uF
.047
A
5
8
U1a
7
6
R1
2K0
R2
24.3K
0.1
2
1
U2a
2K2
22K
5
8
U2b
7
6
.0068
high Z buffer
R3
2K0
3
4
2
U1b
1
3
4
.047
B
R4
24.3K
100K
VCC/2
differential amp
100 uF
2K2
Volts AC
VCC/2
R1 = R3 (matched)
R2 = R4 (matched)
Gain = R2/R1
Wheatstone bridge Buffer, amplifier and filter
2 dB ripple Chebychev low-pass filter
1 KHz FCo

Above — The buffer, differential amplifier and low-pass filter employed during this series of experiments. Function is identical to the similar stage described earlier.



Above — The output of amplified and filtered Wheatstone bridge at open circuit (no resistance at the Unknown Impedance port).



Above — the output of the amplified and filtered Wheatstone bridge at NULL (potentiometer setting balanced to match the resistance at the Unknown Impedance port. Below 2 mV, accuracy is lost.

$$Rx = Rv * (Rs / Rp)$$



Rs = R Scale *(100, 1K, 10K, 100K, 1M etc.)*
Rx = unknown impedance
Rp = R parallel *(nominally = Rv)*
Rv = variable resistor to balance circuit

Above — The math behind the bridge. I found when R Variable (Rv) was the same resistance as the fixed resistor R parallel (Rp), reasonable resolution was possible. "Reasonable resolution" means your pot has a good range of rotation as you go from the lowest to highest measureable impedance. Generally, Rv has to be less than the maximal impedance you are trying to measure.

R Scale (Rs) can be switched in decades via a panel mount switch to cover a wide range of resistance with good resolution, or just be 1 or 2 values. It's your design call.


Poor Man's Wheatstone Bridge
Low = 27 – 500 Ω
High = 500 – 1K Ω
oscillator
1K0
1K0
A
B
500
Rx
?
*
High
Low
1K0
1K0
Uses normal 500 Ω
linear taper pot
optional cap
for tuning out
reactance
220
270
150
330
100
Low
75
390
50
27
470
510
680
820
560
High
510
1K
Potentiometer settings in my experiment calibrated with resistors

Above — My poor man's impedance measurement device that uses a common 500 ohm linear taper pot as the balancing resistor. In order to get good pot resolution, the desired range is switched. This bridge measures impedances at the Unknown Port from about 27 ohms up to 1K with decent resolution. The blue circles depict how I calibrated the front panel of my device using 2 colors. This device had an average return loss of 32.5 dB when a NULL was obtained.

Measuring resistors to calibrate a bridge is quite different from real-world measurement of reactive AF amplifier loads — if the unknown resistance has a large inductive or capacitive reactance, obtaining good bridge balance might prove difficult. Your bridge can *only* null the in-phase signal. An extension to the standard bridge involves adding a series or shunt capacitance (depending on the phase of the reactance) to the A or B port. This may allow you to null the reactive part and also provide the reactive impedance value as well. An outstanding reference may be located with your favorite search engine: Look for the manual for the **General Radio GR1650 Impedance Bridge.** I found a copy and the download was very slow, but worth it. This manual may be the greatest reference every published on the Wheatstone bridge and comprehensively covers tuning out the reactance of complex impedances amid a myriad of other topics.



`Calculate Input Z`

$$\text{Input Z} = \frac{1}{1/10K + 1/4K7 + ((\text{Beta}+1) * (26 / 5.8))}$$

Assuming a Beta of 100 : Z_{in} = 397 Ω

Assuming a Beta of 200 : Z_{in} = 703 Ω

Z_{in} measured with above bridge = 595 Ω

Above — The poor man's bridge measurement of a test AF amplifier on my bench. The reactive component of the amplifier input impedance was minimized using a 0.039 uF capacitor found experimentally. Of particular interest, is the difference between the *calculated* input Z and the *actual* input Z measured with the bridge.

The Beta of the 2N3904's in my collection ranges from about 100 to 225. Calculations with 2 different Beta values are shown (RE is *well* bypassed with a 470 uF capacitor, so, re = (Beta * 26/5.8 mA) . The measured input Z was 595 ohms. I confirmed this by removing the 0.039uF tuning capacitor, plus connecting a fixed 595 ohm resistance to the Unknown Impedance port. I then turned the potentiometer fully clockwise and adjusted it for a NULL. When the bridge was nulled, the potentiometer knob pointed at the same mark as when the amplifier was connected to this Unknown Impedance port.


Vpp(1)= 1.34V
Vrms
Time 500.0
Vpp(1)=60.0mV
Vrm
Time 500.
GOL
AUTO
Vpp(1)=13.6mV
20.0mV
200 mV scale
Open Circuit
50 mV scale
NULL of
Complex Z
20 mV scale
balanced with
.039 uF cap

Above — The oscilloscope output waveform of the amplifier circuit shown above: open circuit, with the potentiometer balanced as well as possible and finally, the potentiometer balanced with the addition of a 0.039 uF capacitor attached to Port B. Although, I was able to get a NULL without the capactitor by just tweaking the potentiometer, slightly better precision was obtained after adding the 0.039 uF balancing capacitor.

Part 4: Miscellaneous Circuits, Scans and Photographs

1
2
3
CW
VISHAY
SPECTROL
PRECISION
POTENTIOMETER
1009 MEX
MOD 534

Above — More accurate results will be obtained with a calibrated 10 turn potentiometer to balance your bridge. A local store sold me this precision 10-turn, 10K pot for about 11 dollars (still expensive for me). They normally sell for twice this price in Canada.



Measure Input Impedance of AF Voltage Amp

Above — My first input impedance measurement device that didn't work. It turns out my experiments were performed *incorrectly*, however, I'm glad because this failure spurred me to investigate bridge networks. The series resistance method *is* worth understanding and happily, Jeff, AD6MX described the correct procedure in a private email received December 2010. I quote him below:

"The series resistance method for input impedance should start with the variable resistor disconnected from the node to be measured. The open circuit voltage at the end of that resistor is measured (the resistor value doesn't affect the open circuit voltage since there's no current into an open circuit.)

Next the free end of the variable resistor is then connected to the input node and the resistor is finally adjusted for half the open circuit voltage at the same end of the resistor, at the input node being measured. What happens is the variable resistor and the node input impedance form a voltage divider, with equal arms or branches.

The value of the resistor when measured out of the circuit is the same as the input impedance at the measured input node. This scheme has some assumptions: the driving amplifier has negligible output impedance compared to the measured impedance, and the input impedance is purely resistive, with no reactance or V-I phase shift.

The phase shift condition may be checked by taking these 3 voltage measurements: across each branch of the divider separately, and also the driving source voltage (across both branches in series.) The sum of the separate branch voltages should match the source voltage when there is little phase shift.

This 3 voltage scheme is used in some antenna analyzers in order to measure phase shift. For checking for the resistive condition, it's not important the 3 voltage method has a sign ambiguity which needs an additional step to resolve. Your description seemed to suggest starting with zero series resistance, but you see that is not the same as the procedure above. The applied voltage needs to be small enough that the amplifier remains operating in its linear range during the measurement".

Thanks for this info Jeff!



TYPE 1650-A

IMPEDANCE BRIDGE

Form 1650-0100-E
July, 1962

Copyright 1962 by General Radio Company
West Concord, Massachusetts, USA

3.48 MB

GENERAL RADIO COMPANY
WEST CONCORD, MASSACHUSETTS, USA

Above — A modified scan of General Radio's *über awesome* manual for the Type 1650-A Impedance Bridge.

QRP SWL HOMEBUILDER

RF — Test and Measurement

RF Workbench Page 3

This web page is the third installment of a 6 part series that explores basic measurement of RF circuits.

Part 3, further examines Return Loss Bridges from a bench-practice viewpoint.

I borrow heavily from the work of Wes, W7ZOI per correspondence, direct contributions and from EMRFD.

I focus on measuring low-level, HF circuits with a return loss bridge — topics such as using the bridge for antenna matching are omitted and readily found on the web. This web page contains minimal text and just relies on simple diagrams and photographs to transfer ideas and knowledge. Information regarding wideband bridge network function may be found elsewhere on this and other web sites and in EMRFD.

More on Return Loss

Gear

Equipping for a 50 Ω measurement environment in 2010 greatly improved my design capacity. The 50 Ω terminated oscilloscope makes a sensitive and accurate detector for return loss measurement. Discussion about using a 50 Ω oscilloscope termination is on the RF Workbench 1 web page.


RF
50 Ω
50 Ω
50 Ω
?
50 Ω detector
50 Ω
50 Ω
RF
50 Ω
50 Ω
50 Ω
?
to detector

Above left — The RLB and measurement set up from EMRFD. Occasionally, you may see bridges using a different balun transformer wiring as shown to the right of this figure.



Above — All the needed parts to home build a return loss bridge. For some, the parts investment might seem substantial, but what hobby isn't expensive? If you consider the cost of commercially manufactured bridges, a homebrew solution seems a bargain. Recycled parts and a home-built chassis are inviting cost-containment techniques. See the web site of Jim, K8IQY for an example of a homebrew RLB chassis. Jim, a Manhattan style construction wizard, builds the nicest looking gear — he puts me to shame.



Above — A completed bridge. I used 1% tolerance 49.1 ohm resistors and an FT50-43 ferrite toroid for the bifilar wound transformer. Inductance = 38.4 uH. Many builders use the FT37-43 ferrite core. I prefer using 2 colors of enamel coated wire to avoid confusion when building stuff with transmission line style transformers and all I had in 2 colors was 24 gauge wire The bigger size ferrite toroid better accommodates the 24 gauge wire, plus photographs better.

Bridge directivity of the above RLB was 30 dB at 7 MHz, 34 dB at 14 MHz, 35.6 dB at 21 MHz, 42.1 dB at 50 MHz and 43.4 dB at 100 MHz.

If you build a circuit with a return loss close to 30 dB, it's a good day.

RETURN~LOSS BRIDGE
RF
?
DETECTOR
D

Above — The completed RF-tight bridge. Don't forget to label your network ports.

Measurement Technique


Amplifier
INPUT Port
50 Ohm
Termination
Signal
Generator
50
"RF"
Return Loss
Bridge
"X"
"Det"
Pad and LPF
if needed
Oscilloscope
50 Ohm
Termination
"RF"
R1
R3
T
R2
"X"
Unknown Z
"Det"
To
"Detector"
24Dec10
w7zoi

Measurement of an Amplifier Input Return Loss

Measurement Procedure:

1. Terminate X port in an open circuit and note level. e.g.,250 mV pp at scope.

2. Attached a 50 Ohm load at X just to check the bridge. e.g., now see 5 mV pp.

3. Bridge directivity is 20Log(250/5)=34 dB. This is the best you can measure. Better numbers are meaningless.

4. Remove the 50 Ohm load. Attached the amplifier input and note level. e.g. 18 mV pp.

5. Amp Input RL is 20Log(250/18) =23 dB.

Above — Measure the return loss input of an amplifier. You'll need at least one 50 ohm BNC feed-through terminator on your bench to test amplifiers with wired-in BNC connectors (such as on this amp); else just solder a 47, 49.9 or 51 ohm resistor from the amplifier output to ground. The BNC connectors allow you to quickly and solderlessly interface components such as filters, attenuators, oscilloscopes or **50 Ω** signal generators.

A typical amp measurement work flow may go something like this: Measure gain using a signal generator and the 50 ohm terminated scope; add the bridge and measure input return loss; finally, flip the amplifier around and measure output return loss. All 3 functions can be performed in 2

— 5 minutes including time to drink coffee + perform calculations by computer or with a HP scientific calculator.



Measurement of an Amplifier Output Return Loss

Amplifier
Outpit Port
50 Ohm
Termination
Signal
Generator
50
"RF"
Return Loss
Bridge
"X"
"Det"
Pad and LPF
if needed
Oscilloscope
50 Ohm
Termination
"RF"
R1
R3
T
R2
"X"
Unknown Z
"Det"
To
"Detector"
24Dec10
w7zoi

Measurement Procedure:

1. Terminate X port in an open circuit and note level. e.g.,250 mV pp at scope.

2. Attached a 50 Ohm load at X just to check the bridge. e.g., now see 5 mV pp.

3. Bridge *directivity* is 20Log(250/5)=34 dB. This is the best you can measure. Better numbers are meaningless.

4. Remove the 50 Ohm load. Attached the amplifier output and note level. e.g. 32 mV pp.

5. Amp Output RL is 20Log(250/32) =18 dB.

Above — Measure the return loss output of an amplifier. The above 2 procedural diagrams provided by Wes, W7ZOI. Many thanks to Wes. These figures are copyrighted © by Wes Hayward, 2010.

Your signal generator should have a return loss of at least 20 dB for greatest accuracy — all of my bench test generators have at least 30 dB of return loss. If you have a signal generator with a low impedance output and place a 10 dB attenuation pad on the output, you'll have at least 20 dB of return loss.

In the above figures, Wes gives an open circuit return loss of 250 mV; I set my signal generator output so the open return loss is somewhere between 170 and 250 mV; this allows you to accurately measure a really good 50 ohm return loss at >= 5 mV or so. Some people may have trouble going any lower than 5 mV due to scope accuracy. This is just something to consider.

Bench Exploration

For me at least, a special case of return loss measurement exists; measuring the return loss of a local oscillator. Since the oscillator under test must be *on* during measurement, it's emitting a signal at the same frequency as the bridge signal generator and interferes with measurement. If some 50 ohm attenuation is added to reduce the local oscillator under test output signal amplitude, this increases the return loss of the local oscillator under test. This is normally a good thing, however, we seek the **raw** output return loss or output impedance of the local oscillator under test.


Measuring the Output Z of an Oscillator

T1 = trifilar winding on a powdered iron toroid:
XL = 50 Ω @ the test frequency
For example, 1.14 uH at 7.0 MHz *(wind on a T50-2)*

Above — An initial experiment that a builder from Michigan, USA and I first used to measure the output impedance of a local oscillator consistent with the breadth and scope of this web site. We wanted something simple and wished to avoid building a vector network analyzer or performing ugly algebra. I built a simple crystal oscillator for 7.0 MHz using an output transformer wound to give a low impedance output. The circuit was measured and calculated using the instrument above and the formula and procedure below.

The calculated output Z was 33.2 ohms. I build a standard value resistor 6 dB attenuator pad from this table. After fitting the pad, I re-measured and re-calculated the output impedance at 46.8 ohms. This seemed okay. I built a couple of oscillators for other frequencies and the output impedances were hundreds of ohms! — disappointing. Still, we were on the bench in a solution-focused mode and needed to try something else.



Formula

$$\text{LO output Z} = \left(\frac{\text{Out1} + \text{Out2}}{\text{Out1} - \text{Out2}} \right) \times 50$$

Make Out1 the larger pk-pk voltage

Out1 and Out2 are connected to 50 ohm terminated scope inputs, or 1 of them is connected to a 50 ohm terminated scope output, while the other is terminated with a 50 ohm resistor.

Above — The formula for calculating the output impedance with the *experimental* local oscillator output Z device.



Above — Breadboard of the experimental L.O. output impedance bridge with a 50 ohm feed-through terminator on the Output 1 port. It failed to work as expected. Skillful adult problem solving goes something like this:

1. Identify the problem.
2. Brainstorm to generate some potential solutions.
3. Try out one of your ideas.
4. If that doesn't work, try another idea.
5. If none of your ideas work, wait a while, or ask an expert.

Well, we ran out of ideas and decided to ask experts for some more ideas; Professor Kuhn and Wes, W7ZOI.

I'll share their key messages. First, accurately measuring the output impedance of an RF oscillator can be difficult — measuring the return loss of a buffer amplifier is much easier. For this, some builders run the bridge signal generator on a slightly different frequency than the oscillator under test while using a spectrum analyzer as the 50 ohm RLB detector.

Another way is to short circuit the tank on the oscillator and measure the buffer output in the normal way — a popcorn solution indeed!

We tried calculating oscillator output impedance using different equations and 1 example is shown below. Failing to account for inductive and/or capacitive reactance plus resistance in the output circuit (including the transformer), plus upsetting the circuit during AC voltage measurement adds uncertainty to calculations — measurement seems more reliable.



R	Pk-Pk Voltage
open ckt	3.31v
1M	2.28v
330	2.12v
100	1.80v
49.9	1.49v
22	1.05v

$$Zout = \frac{R * \text{open circuit } V}{V \text{ load}} - R$$

$$Zo = \left(\frac{50 * 3.31}{1.49}\right) - 50 \Rightarrow Zo = 61.1\ \Omega$$

RL = 20.1 dB

Above — One method of calculating output impedance. Running the output at open-circuit likely effects the oscillator by changing its load despite having the JFET buffer. Some builders use this equation for calculating the output impedance in their audio amplifiers. This amplifier **should** have a 50 ohm output impedance based upon the transformer turns ratio and the 1K8 resistor across transformer: 1800:50 ohms = a 36:1 impedance ratio and a 6:1 turns ratio.



see graph
14.0 MHz
5v Reg
.1
12.22v
100
.1
1K8
X
RETURN LOSS BRIDGE
F
D
100
FT37-43
39
T50-6
2.65 uH
68 pF
C0G
SHORT
J310
.001
C0G
.001
C0G
22
47 pF
C0G
1M
330
J310
d
g
s
330
330 pF
C0G
IS = 6.15 mA

Measure Return Loss of Oscillator Buffer

- 13.324 MHz oscillator with shorted tank
- Adding a 10 dB pad to the 12:3t version gave a return loss of 27.5 dB

Turns Ratio	Return Loss
12:6	3.6 dB
12:5	5.1 dB
12:4	9.0 dB
12:3	17.9 dB
12:2	9.8 dB
12:1	2.9 dB
10:5	4.9 dB
10:4	7.8 dB
10:3	15.2 dB
10:2	11.1 dB

Above — A simple 13.3 MHz L-C oscillator was built and evaluated. After shorting the tank coil, return loss versus turns ratio was measured and tabled as shown. To my surprise, I observed the best match with a 4:1 turns ratio. This suggested that the transformer, wound on a ferrite FT37-43 toroid was exhibiting high resistance and far from the "ideal transformer". The inductance of my 12 turn transformer was 38.3 uH.

The initial secondary winding had 6 turns and then was reduced sequentially by 1 turn. After removing each turn, the 1/2 cm of increased wire length was cut off and the enamel scraped off of the new wire ending to ensure a short connection to the output jack. During measurement, unless the secondary transformer wires were kept tidy, a ~40 MHz oscillation occurred when the 1K8 resistor was disconnected. The 1K8 resistor prevented such oscillations and improved the return loss by 1-4 dB at the various turns ratios. Testing frequency was 14 MHz.



Measure Return Loss of Oscillator Buffer

see graph
14.0 MHZ
5v Reg
.1
12.22v
100
.1
1K8
X
RETURN LOSS BRIDGE
F
D
100
39
FT50-61
SHORT
T50-6
2.65 uH
68 pF
C0G
J310
g
d
s
.001
C0G
.001
C0G
22
1M
330
J310
47 pF
C0G
330
330 pF
C0G

Turns Ratio	Return Loss
24:7	7.1 dB
24:6	10.0 dB
24:5	18.8 dB
24:4	20.3 dB
24:3	9.3 dB
24:2	4.2 dB

Above — The same circuit with a lower-loss, FT50-61 ferrite transformer. I could have used a FT37-61, but prefer the 50-61 as the bigger core allows the use of heavier wire which provides some robustness when performing intensive experiments. The inductance of 24 turns on a FT50-61 measured 36.2 uH. Although lower permeability ferrite toroids require more windings, this transformer is closer to the "ideal transformer" than that wound on a FT37-43 ferrite core — a 6:1 turns ratio gave the best return loss; the output Z is pretty close to 50 ohms.

The information garnered during these tests proved enlightening and reinforces why bench measurement provides the greatest way to learn about and optimize your circuits. I hope this simple web page on return loss measurement fuels your own experiments — the most important experiments will be those *you* do on *your* bench.

Miscellaneous Figures and Photos



Calculate Output Z of an Oscillator – Experiment 1

Measure the open circuit output amplitude of the oscillator and then add a load so that the loaded voltage dropped to something in the range of 50 to 75 percent of the open circuit voltage. Then use voltage divider theory to calculate the source resistance of the oscillator.

$$V_{loaded} = \frac{V_{unloaded} * R_{load}}{(R_{oscillator} + R_{load}}$$



Rtest	Vout	Icalc	Pcalc	Zout calc
1000000	0.9999	9.999E-07	9.998E-07	
220	0.8148	0.0037	0.0030	49.9779
50	0.5003	0.0100	0.0050	49.9300
22	0.3056	0.0139	0.0042	49.9823

Miscellaneous RF Topics 2011

Introduction



My basic goal for Fall and Winter 2010 was to fearlessly advance my RF design ability — pushing just beyond my comfort zone to impose the psychological stress that promotes focused learning. You may have experienced this in University or when working against a deadline. Cramming, "burning the midnight oil", or locked room brainstorming exemplify this approach.

These circuits feature carefully measured input and output impedances (nominal impedance = 50 Ω), plus voltage gain and DC current.

This web site spawns email with builders worldwide. Our interactions are varied; getting help, giving help — or just chat. On occasion, I design, build and/or test circuits to help struggling builders. After spending considerable time, I email them my work hoping it will help. Often enough, I never receive any acknowledgement from these readers — did the circuit work or did they appreciate I spent 1-2 hours researching their concern?. This is actually normal — we must constantly strive to overcome our innate, self-centered nature; lest it dominate our behavior. все нормальные.

To that point, I wish to gratefully acknowledge the people who support me in this hobby: Wes, Ken, Scott, Peter, Tom and the many others whose email advice and published and private work informs and inspires me.

Topics:

1. Transmit Mixer Experiments
2. Bipolar Transistor Feedback Amplifier Experiments
3. JFET Common Gate Transistor Amplifier Experiments

Navigation and Preamble:

This web page grew into a large monster — and includes a supplemental web page with numbered topics referenced in the text. I apologize for the navigation difficulties this web page poses. Equal time was spent experimenting with the circuit designs and circuit photography. I strive to provide a variety of bitmap and photographic image styles on this web site.

---

1. Transmit Mixer Experiments

Since I've never experimented with transmit mixers, I didn't appreciate how much time goes into their design. Consider, for example, the LO system from the project entitled A Monoband SSB/CW Transceiver in Chapter 6 of EMRFD. The mega low (about -20 dBm) output from a diode ring mixing a VFO and crystal oscillator is triple tuned band-pass filtered and then amplified to +8 dBm. Continuing on, the transmitter chain features more mixing, band-pass filtering and voltage amplification by a feedback amplifier chain boosting the signal to around 300 mW. The circuits needed to mix, filter and amplify this RF chain would challenge most amateur designers — me included.

Contrast this with a typical first transmitter built by a new builder. Likely your first scratch homebrew transmitter consisted of a crystal oscillator, a keyed Class A buffer/amplifier and perhaps a Class C final amplifier. No mixer was needed for we obtained a crystal cut on the frequency of choice. Our focus was **power**— getting 0.25 to 1 watt into our antenna system! A good example was the Tuna Tin 2 transmitter by the late Doug DeMaw, W1FB that only used 2 stages. Although Doug wrote his 1976 article for Hams to build a transmitter from parts found at home, kitted versions are sold today.

Returning to transmit mixers — as amateur designers, we likely need to start on a small portion of the transmit chain and then after developing some competency, slowly extend our experiments all the way to the antenna port. In Fall 2010, I just examined some basic transmit mixing to get a feel for what's involved and what to expect. Mixing signals is a complex affair encompassing topics such as intercept point, conversion gain or loss, image noise suppression, noise figure, spurious/intermodulation products and port isolation. To keep things simple, only mixer port isolation and reducing spurious mixer products were examined.

Before beginning, I express the following concern: We experimenters, as stewards of the airwaves, must build exemplary transmitters with very low spurious outputs. I follow the example of Wes, W7ZOI and others — my transmit chains have spurious frequencies at least 50-60 dB down from the carrier (dBc). As a web author and radio amateur, I never want to directly or indirectly contribute to RFI and hope you agree.

Why Use a Transmit Mixer?

If you plan to design a superheterodyne based transceiver, you'll probably need to use a transmit mixer. Also mixing 2 frequencies permits using cheap microprocessors crystals to target a desired transmit frequency; separate crystal oscillators drive the RF and LO ports of the mixer. For added flexibility, the LO can be converted to a VFO once you have the basic design working well.

I purchased a bag of low cost crystals. By mixing 2 appropriate crystals, output on a Ham band is possible. For example, crystals at 2.048 + 5.0688 MHz = 7.117 MHz; 4.194 + 11.228 MHz = 7.034 MHz; and 3.932 + 11.046 MHz = 7.114 MHz. I frequently operate QRP on 40 Meters in the USA Novice band, so 7.114, or 7.117 MHz is okay. This helps CW operators avoid all the RTTY and QRM down in the traditional 40M band QRP frequency window.

Some Mixer Bullets

- Mixers have 3 conventionally named ports; RF, LO (local oscillator) and IF (output).
- The diode ring mixers presented are Level 7 mixers. Maximal LO power is 7 dBm.
- Many builders limit the maximum RF power into a Level 7 diode ring transmit mixer RF port to between 0 to -3 dBm.
- The term *isolation* refers to the amount of LO power that leaks into the RF or the IF ports.
- Low-pass filtering the LO *can* significantly reduce harmonic products in a mixer
- The top of the spectrum analyzer screen (always the top, and never the bottom) is called the reference level. That is the power at the top. If you have a signal generator with the output adjusted to be -27 dBm and pass this signal into the spectrum analyzer and adjust the attenuation in the analyzer to put that signal at the top of the screen, you then the reference level is -27 dBm. *(Pertains to examining a mixer output in a SA)*

Choosing a Mixer

A number of mixers were considered; passive, active, unbalanced, single-balanced and finally, double-balanced. The diode ring mixer is an obvious good choice commensurate with my goals of reducing spurs, LO feed through and achieving high port-to-port isolation. In future web pages, other mixers may be presented, however this page is focused on the diode ring mixer. Click for a file with a few scanned pages concerning mixers from my "ideas only" notebook from ~2002. I own over 30 notebooks now.


MCL C 008
ADE-1

Above — ADE-1 diode ring mixers. We're using these now as they're cheaper than the SBL-1, TUFF-1 etc. hole-though versions. Although SMT parts, they can be flipped over and wired "normally" with a little effort, steady hands and good vision. Mini-Circuits will sell them in small quantities to Hams; email them and enquire. I feel the diode ring mixer has been misunderstood by some amateur builders — lore and misperceptions that the 7 dBm LO port drive, the need for 50 ohm port terminations, a ~ 5 dB insertion loss and cost make them undesirable. Their excellent performance and design challenges are reasons why we use them; "the journey — not the destination" stuff.

In receiver applications, some builders and kit sellers seem more focused on features such low-battery indicators, digital displays, miniaturization and cost containment than basic receiver performance. Certainly keeping cost down down deserves consideration, however, good mixer performance is king. You'll have to decide what's affordable and important and build accordingly.


Mixing of Low Level Crystal Oscillators – DRM
12.2 VDC
.1
470
Q1 = Q2 = 2N3904
470
.1
3.932 MHz
Crystal
diode ring mixer
11.046 MHz
Crystal
.1
10K
-8.27 dBm
-8.56 dBm
10K
Q1
150 pF
47 pF
Q2
RF
LO
IF
220 pF
10K
10K
180 pF
470 pF
470 pF
2K7
220 pF
.1
100 pF
2K7
50 Ω
7.116 MHz

Above — My very first transmit mixer experiment. My hope was to build a transmit mixer possessing low spurious output to alleviate the need for stiff, post mixer band-pass filtering such as a triple tuned band-pass filter. Thus, low-level, low distortion output was taken from between each crystal oscillators' shunt capacitor and crystal. The desired output frequency is ~7.114 MHz to build a transmitter for the 40 Meter Ham band.

The mixer output to 50 MHz looked like this in a Spectrum Analyzer. The dominant frequencies are the **sum** and the **difference**: 11.046 **+** 3.932 MHz = **14.98 MHz**; 11.046 **-** 3.932 MHz = **7.114 MHz**. The frequencies realized are *slightly* different since the oscillator output is shifted by crystal variances and from circuit capacitance.

In the experiments that follow, I built some circuits to filter and/or amplify the output of the *above* mixer circuit.



Above — The first post mixer amp; a common base input amplifier that's AC coupled to a common drain FET amp. I hoped that 2 tuned L-C tank circuits could substitute for a passive double or triple-tuned band-pass filter, plus provide some gain.

A broad-band, common base input amp was chosen to properly terminate the diode ring mixer and alleviate the need for a diplexer. A ~50 Ω input impedance is established by a 47 Ω series resistor since the 2N3904s input impedance is quite low due to the moderately high emitter current employed to boost gain and IMD performance.

This amplifier failed to reduce spurious output 50 dB down or greater — my design goal. Here are its scope and spectrum analyzer outputs; please observe that the unwanted 14.98 MHz signal is only 32 dB down from the desire IF of 7.114 MHz. An RC network consisting of a shunt 10 ohm resistor + an 18 pF cap provides additional low-pass filtering above 20 MHz. I attribute this simple filter to Dr. Ulrich Rohde as I have seen it in some of his post mixer, common base RF amplifier designs. Click for a brief supplement regarding his low-pass network ***(#2 RC Low-pass Network on the Supplemental Page)***

The amp design shown above was actually an improved version of this prototype. In the prototype amp, the mixer power at 14.98 MHz was only 23 dB down from the desired intermediate frequency of 7.114 MHz. You can't expect a single L-C tank to well filter a mixer output. Unfortunately, the 1K2 -12K resistor providing DC bias for the emitter follower lowers the Q of the common-base collector tank circuit. 12K is better than 1K2 in this regard. Poor performance sparked the design of the second common base amp shown above.

I use ferrite beads and 51 Ω resistors interchangeably on the collector/drains of amplifiers to snuff out UHF oscillations. According to my experiments, the resistors may work better. I purchased the ferrite beads from Diz. After the common base amplifiers shown above, I decided to try a tuned input + output common gate JFET amp:


JFET Post Mixer Amp
12.22V
.1
100
10-70 pF
32
T2
3
51
Q1
T1
32
12
8
s
d
g
10-70 pF
.1
220
.1
IS 8.83 mA
Q1 = J310
T1 = 32t T50-2; tap at 8t & 12t
T2 = T1 with a 3t link

Above — A JFET common gate amp with tuned input and output built about 3 years ago. For spectrum analysis. I padded the amplifier output to provide a -28 dBm 7.116 MHz signal. The vertical resolution on the SA is the standard 10 dB/division. As shown, the 14.98 MHz signal is ~ 39 dB down; an improvement over the amplifiers shown previously. This narrow-band amplifier requires a diplexer. I wanted *better* filtering than that offered by amplified circuits with 2 tuned L-C circuits, so I halted this experiment and decided to try a triple tuned band-pass filter.

This JFET circuit experimentation spawned over 8 weeks of experiments concerning common-gate RF amps — some of them appear later.


Triple Tuned Band-pass Filter
diode ring mixer
3.93 MHz
RF
IF
LO
11.05 MHz
39
150
-6 dB
68 pF
300 pF
33 pF
CV
L1
5 pF
82 pF
CV
L2
5 pF
33 pF
CV
L3
68 pF
300 pF
50 Ω
L = 3 uH
CV = 5 – 70 pF trimmer cap
Center Frequency 7.112 MHz
3 dB Bandwidth 300 KHz

Above — A triple tuned band-pass filter designed with software from EMRFD called TTC-08. Click for the breadboard photo. The diode ring was connected to the filter input via a 6 dB attenuator pad using short leads. Click for analysis in GPLA. All inductors are 3.0 uH — 23 or 24 turns on a T50-2 powdered iron toroid. I measured all the inductors and obtain the exact desired inductance by expanding or squishing the wire turns, or if necessary, adding (this means rewinding the entire coil) or removing a turn. If you lack an inductance meter, just winding the formula calculated number of turns will be close enough for most applications — I only got a good L- C meter in 2009 and somehow managed.

I learned that the ultimate way to peak a triple tuned filter is by tweaking the tuning capacitors while it's connected to a spectrum analyzer — what a thrill!



Above — While a little tedious to build and align, the triple tuned filter worked magnificently; the strongest spur is 54-55 dB down and the 14.98 MHz signal is gone. Insertion loss = 2.5 dB. This experiment provided a benchmark of what great post mixer filtering looks like. Post mixer filtering is an important topic worth studying further:

Why do we need filtering on a mixer output?

Let's examine mixer ports more closely. A port is just a pair of wires where signals are applied or removed. There are 2 kinds of mixer *outputs*: 1) the sum plus difference frequencies; 2) spurs.

Further, 2 kinds of spurs occur: One type is straight feed through where 1 signal from the 2 input ports makes it out to a 3rd port. Examples include LO feed through to the RF port, or LO feed through to the IF port.

The other type of spur is a mixing product such as a harmonic.

In general, the mixer output frequencies are numerically described by an equation:
IF (output) = N x L +/- M x R
N and M are both integers, 1, 2, 3, ... L = local oscillator frequency, R = radio frequency

A mixer is said to be balanced when you duplicate some of its functions and then combine them — usually with transformers. Consider, for example, the single diode mixer — they work, but the output contains ++ feed through and spurs. A mixer with 2 diodes or 2 FETs etc. can be much easier to use because the transformer combines the signals in a way that cancels some of the spurs and feed through. The double-balanced diode ring mixer uses four diodes and 2 transformers — producing even less feed through and harmonic output.

In a double-balanced diode ring mixer, the LO and RF ports are balanced and all ports of the mixer are isolated from each other. The double-balanced mixer greatly reduces, but does not stop all LO feed through at the RF and IF ports. A wideband match at 50 ohms is required to maintain mixer balance; hence you will often see attenuator pads on the LO, RF and *especially* the IF ports.

Let's focus on the IF port. Attenuator pads absorb any reflected mixer products and signals coming back into the IF port, thus increasing the match to the IF port. You may have noticed some builders use a diplexer on the IF port. The diplexer presents a wideband match to all IF port frequencies — passing the desired sum or difference frequency and absorbing the unwanted mixer products reflected back into the IF port by subsequent stages.

Since the IF output contains the sum and difference of the LO + RF, LO feed though, and other spurious energy, band-pass filtering is required to launder the IF signal into something useful. Following a transmit mixer, we filter with an L-C band-pass filter — after a receive mixer, crystal band-pass filters dominate. If you choose an unbalanced mixer or single-balanced mixer, filtering becomes more difficult than with a double balanced mixer. Unbalanced mixers are usually reserved for situations where high performance is being sacrificed for cost containment and/or want of a low parts count. There is no free lunch — you either alleviate as many mixer products as you can at a low-level with good practices, or have to deal with them down your signal chain while sacrificing optimal mixer performance.

Double balanced mixers are sensitive to non-resistive IF port terminations. When improperly terminated, the 2 transmission-line transformers work poorly — any reflected power generates high voltage across the diodes and degrades mixer performance. According to Dr. Ulrich Rohde, some proper ways to terminate the mixer include using a diplexer followed by a wideband 50 Ω feedback amp, or a common-gate JFET amplifier. *(Reference 1)*

Improved Local and RF Oscillators

In the earlier experiment, I really should have the run the LO port at 7 dBm. In order to improve my experiments, new crystal oscillators were designed with emphasis on correct LO output power and low harmonic energy.



Above — The new LO; a 3.93 MHz crystal oscillator with stiff low-pass filtering. Admittedly, this 7 element Chebychev low-pass filter is overkill, however, I wanted to examine filtering and learn how much is required. On the bench — do whatever you like; even chasing crazy personal goals can be instructive and help you relate to information from texts and articles, or satisfy a whim. I can read something 100 times, but may not understand it well until I actually do it.



Above —The LO breadboard in close-up using a long focal length lens. Click for a wide angle photograph. The unsoldered end of the 100 Ω resistor in the close up photograph is where I connected the VCC.


0
3.93 MHz @ - 25 dBm
H = 5 MHz/div
V = 10 dB/div
POWER
INTENS
PROBE POWER
VOL.
PHONE
ATTEN INSTRUMENTS AT6011

Above — Spectrum analysis of the well-filtered 3.93 MHz LO. Not surprising, no harmonic energy is seen.


T50-6
4.5 uH
FCo = 11.32 MHz
100
12.22 V
.1
30
5
39
.83 uH
.83 uH
50 Ω
←150→
- 6 dB
50 Ω
J310
d
g
s
10-70 pF
270 pF
470 pF
270 pF
47K
430
11.046 MHz
IS = 4.36 mA
Data
Power = 6.96 dBm
All harmonics > 55 dBc

Above — The redesigned RF port oscillator. Clearly, the 7 element Chebychev low-pass filter isn't needed, so an N = 5 version was tried. Click for the spectrum analysis — again no harmonic energy was seen. In both the RF and LO signal generators, I tried to get as close to 7 dBm output power as possible.

To operate this oscillator at the desired RF port signal level; for example, between 0 and -10 dBm, you might just attenuate the output with a fixed pad or step attenuator. My conclusions echo the work of others experimenters; lowering the RF port down from 7 dBm to as low as - 10 dBm, lowered the amplitude of the spurious mixer products seen in the spectrum analyzer. Click for a sample. Refer to the QST Technical Correspondence citation in the references section for more information.



Above — The 2 re-designed oscillators wired up and connected to an SBL-1 mixer. I actually connected the attenuator pads after the low-pass filters as explained later.

Two different crystal oscillators were then built:


LO and RF Crystal Oscillators
100
T50-6
12.22 V
30t
5t
.1
68
50 Ω
J310
←100→
-10 dB
50 Ω
11.228 MHz
d
10-70 pF
11.23 MHz
-3.39 dBm
2nd harmonic -36 dBc
g
s
47K
1K5
RF
100
T50-2
Low-pass filter FCo = 5.07 MHz
2.16 uH
2.16 uH
12.22 V
36t
6t
39
50 Ω
.1
J310
150 pF
←150→
- 6 dB
50 Ω
4.194 MHz
d
10-70 pF
680 pF
1200 pF
680 pF
g
s
47K
470
LO
4.19 MHz
6.84 dBm
2nd harmonic -54 dBc

Above — Two different crystal oscillators targeting ~ 7.034 MHz were built. Click for the breadboard photo. You can see the crystal frequencies in this photograph. The RF port oscillator power was set to -3.39 dBm by choosing a low value JFET source resistor and attaching a 10 dB attenuator pad. Relatively low harmonic distortion prompted the exclusion of a low-pass filter on the RF oscillator. The LO output power was ~ 7 dBm.



Above — The final experiment; placing a double tuned band-pass filter after the TUFF-1 diode ring mixer with the 2 latest crystal oscillators attached . This filter was in my junk box and I peaked it for the 7.034 MHz IF with a spectrum analyzer. The strongest spur was 42 dB down from the carrier — falling well short of the triple tuned band-pass filter presented before.

Clearly from all these experiments, a strong case for placing a triple tuned band-pass filter after a transmit mixer exists. If you use an unbalanced or single-balance mixer, a double balanced mixer might sufficiently not block feed through and spurious RF to keep your signal chain tidy. I enjoy studying the transmit chains of others to see how they filtered spurious and feed through RF. At the end of the day, as long as the output carrier spurs are low enough to meet your country's regulatory requirements, you're okay. Designing for low spurious emissions is an exciting challenge — one you'll miss if you don't try your hand with RF design.

A realization emerged following these experiments — I couldn't measure the return loss of the local oscillators! It technically could be done, but not by me. After 2 weeks of struggling, I engaged an American colleague with whom I occasionally build experimental circuits. After making some progress, we became stalled again. This time I asked Professor Ken Kuhn and Wes, W7ZOI for some ideas. Eventually a method to measure the RL of local oscillators came together along with enough material for another web page — RF Workbench 3.

When you do experiments, knowledge evolves as you go — for me, I learn mostly from making mistakes. I often think I should repeat most of my experiments over before presenting them, but this would consume too much time. However, footnotes can serve to steer readers for minor issues. If I had to re-build the crystal oscillators from Part 1, I'd build each crystal oscillator with a separate JFET buffer — then the return loss of the oscillator buffers could be measured as shown on RF Workbench 3 (with a shorted oscillator tank). Also, the pi attenuator pads on the crystal oscillators should follow the low-pass filters to garner the best output return loss. The good news is past experiments inform future experiments.

---

2. Bipolar Transistor Feedback Amplifier Experiments

I love making signals bigger — especially while preserving fidelity. It would be nice to become a reasonably competent amplifier designer — hopefully by studying sound schematics, applying software, building circuits and measuring evermore parameters this might occur. The mathematical equations of RF amplifier design seem quite daunting; they're the fodder of electrical engineers with their Hewlett Packard scientific calculators, SPICE software and GHz F-t transistors. With most things technical, as you try to advance, more questions than answers cross your mind; however, somehow this is normal and may actually signal progress.

Abundant amplifier references exist; for example, EMRDF Chapter 2: Feedback Amplifiers. This is essential reading and I won't repeat this information. Rather, I'll just share some ideas developed or reinforced on my bench. In the past, I've preferred amplifiers with narrow-band (tuned circuits) in an attempt to reduce distortion and maximize gain. Now after critically examining these tuned amps with scope and spectrum analyzer, I better appreciate the significant intrinsic feedback of RF transistors ***(the tendency to oscillate)*** and broadband designs are sought. Often you'll spend more time taming a tuned amplifier than building one.

This section focuses on return loss, bias techniques and achieving linear amplification — for example; finding ways to apply negative feedback, match the input, or how to set the collector voltage. All my experiments and thoughts about RF amplifiers are from an amateur designers' perspective and I welcome your feedback. The first amplifier shown is a classic W7ZOI topology that I call the "Beaverton Special".



Above — A classic feedback amplifier popularized by Wes, W7ZOI in books like Solid State Design for the Radio Amateur and EMRFD. My respect for this humble design increased after building and testing 4 different versions to get a feel for amps with both shunt and series feedback. Of the 4 built, this particular version became my favorite — providing excellent input and output matching without crazy high emitter current. Employing a low noise / high F-t 2N3866 transistor is icing on the cake — an attempt to maximize impedance matching and performance using this standard, fits most transistors bias/feedback circuit. The humble 2N3904 also worked well in this slot. You don't need the ferrite collector bead with a 2N3904.

Other good experiments include trying different transistors and/or increasing the emitter current while being careful not to exceed the BJT's current rating (plus add heat sinking as required). You might also try the stage at different frequencies or perhaps sweep it to see at what frequency the gain starts to fall off.

Of the 4 BJT feedback amps shown in part 2, only this amp has a true broad-band input and output. What bothers me about broad-band linear amplifiers is that when you chain up 2 or more of them, signal fidelity generally degrades as it passes through each successive amp stage. Solutions include mopping things up with some low-pass filtering after the last stage, leaving it alone, or tuning the amplifiers (i.e. not using broadband stages).

The biggest caveat for feedback amps are variations in input and output impedance caused by source and load mismatches. For example, a 75 Ω resistor was connected to the output of the FBA above. The input return loss degraded to 16.8 dB. Further, the same 75 Ω load was removed and then connected to the input during output return loss measurement— this degraded the output RL to 23.4 dB. Clearly *load* mismatches upset return loss more than *source* mismatching. A 50 Ω attenuation pad should likely follow a feedback amp in situations where high input return loss are desired; for example, after a diode ring mixer.

Noticing a variation of the classis feedback topology in EMRFD Figure 6.140, I asked Wes, W7ZOI about it. It turns out there's another way to "skin the shunt feedback cat". The above RF amp uses a series connection of 2 feedback resistors (1K5 and 1K5 with a bypass cap across one 1K5). The result is a resistance at DC of 3K, but a resistance at RF of just 1K5. You could also use a 3K resistor directly from collector to base that is paralleled by a series connection of a 1K5 resistor plus a 0.1 uF capacitor. That network has the same impedance as my amp shown above. That is; the resistance would be 3K at DC, but 1K5 at RF.

This explanation fueled the next experiment — transistor amplifiers have 2 operating conditions; 1 at DC, the other at AC. Like a carpenter framing a house, you begin design by setting the DC bias — no small design task since bias concerns more than just establishing the base voltage and emitter current. For example, biasing may effect voltage gain, maximum signal handling capability, noise figure, impedance matching, class of operation, the operating point (sometimes called quiescent point or q-point), feedback and temperature stability. Biasing provides much to think about, however, a practical way to explore any topic is to chunk it into small, understandable pieces that become a stepping stone to advancement. Let's focus on biasing for temperature stability. The next amp uses the wrap-around PNP bias — an awesome technique.



Above — A 7 MHz FBA using PNP wrap-around biasing. I learned about wrap-around biasing from Wes, W7ZOI and share a simple way for new builders to also learn this technique as the **#1 Design Center** on the supplemental web page. Click for a prototype breadboard photograph. This amplifier employs heavy shunt feedback from collector to base. Degenerative (series) feedback from the 2 parallel 10 ohm resistors also enhances temperature stability.
Expanded bias circuit temperature stability discussion follows amplifier number 4.

The wrap-around or feedback bias scheme is good because it's self stabilizing. The diode in the PNP bias network further ensures that the PNP bias remains constant with temperature changes. It really should be to glued to the NPN transistor (or its heat sink) to allow tracking of the NPN's temperature variations. This bias circuit doesn't load the NPN base input impedance. Another great virtue is that the emitter of the amplifying transistor can be directly connected to ground allowing better performance at VHF and UHF.

Noise from the PNP will be amplified by the NPN, so the low-pass network formed by the 0.1 uF capacitor and 4K7 resistor is essential. In some related circuits, you may see an RF choke used instead of a resistor.

The actual 2N5109 input impedance is probably around 40 ohms — easy matching with an L-match network.

Amplifiers with an L-match tuned input shouldn't follow a diode ring mixer unless preceded with a diplexer since the narrow-band L-match tunes only 1 frequency. L-match networks can make an impedance bigger or smaller depending how they're oriented and also provide some low or high-pass filtering depending on the configuration. I design my L-networks on the bench using experience plus trial and error — a better way is to use software. I recommend the program called Zmat08.exe that is included on the CD that accompanies EMRFD. The software will get you close, however, bench tweaking is required since you're often matching a complex impedance, comprised in part, of stray reactance.

Setting up an L-Network for an Input Match

A suggested bench method for optimizing input Return Loss (RL) using an L-Match network.

Your task is find the "perfect" L and C values to get a RL of 20 dB or higher. Start by soldering in an inductor calculated from Zmat08.exe or according to your wisdom. Set up the amplifier for input return loss measurement. The first chore is to find the nominal target capacitance that provides the best match at the design frequency. I use a big range, air variable capacitor for this — with the input circuit connected to a return loss bridge, connect up and tune the big variable capacitor to give the greatest RL. Remove the variable capacitor, measure it, and then solder in an equivalent trimmer capacitor, and as required, fixed capacitor(s) so you can tune at least 25 pF above and below the target capacitance. Often, the target C will be close to whatever the software recommends. In amplifier 2, my C values are the 180 pF + a 10-70 pF trimmer.

Next, determine the optimal inductor. On my bench, I keep a variety of pre-wound #6; and #2 material powdered-iron toroid inductors and choose one close to the calculated or a self-chosen L value. I start with an inductor wound with 4-5 more turns than needed. After soldering it in, the RL is checked. Remove 1 or 2 turns, tweak the trimmer capacitor and again check the RL. If after removing 1 or 2 turns, the RL is going up, you've determined there was enough inductance to get the best RL. *(If the RL goes down, you probably didn't start with enough L to get the best possible RL).*

You can also also squeeze together or spread apart the toroid windings to vary inductance — the maximal inductance variation varies due to factors including wire gauge and total turns. Compressing the windings with thumb and forefinger *increases* the inductance and widening the gaps between windings *reduces* inductance on a toroid.

Assuming the RL increased after removing 1 or 2 turns, remove another turn, tweak the trimmer capacitor and check the return loss, and so on. Repeat until your return loss starts to decrease. Then add back a turn or 2 to find the absolute best match. *This procedure allows you to find the optimum inductance in-situ.* Once, you've figured out the best inductance, cut the inductor leads short, solder it in, tweak the trimmer capacitor, and then consider further tweaking the coil by expanding or squishing the windings on the toroid while looking at the RL in a bridge detector.

In summary, to get the best possible RL — design a prospective L-match with software, and then bench test to determine the optimal in-situ L and C by using values above and below the calculated L and C values while observing the results in a return loss bridge. This method seems tedious, but emphasizes that repeated bench practice and patience pays off. You can always just use the calculated L-network values and/or develop your own method to set them up.

Consider mitigating the stray inductance caused by the long lead that occurs after removing wire turns by cutting the lead and scraping off the enamel insulation every couple of turns or so. This is a gamble — If you cut the lead and need to add back a turn, you'll have to rewind the coil from scratch, or add in and solder another turn (messy). I'm often able to get a L-network RL of 22-26 dB using my method and feel it's worth the the time and effort.

When bench tweaking the L and C values, your actually looking at the peak-to-peak AC voltage with the amp input connected to the unknown port of the RL bridge. Tune for the lowest, stable peak-to-peak voltage. Test it against the open circuit peak-to-peak voltage to calculate the RL. Since the open circuit doesn't change, you know the return loss is improving when the peak-to-peak voltage of the amplifier under test is going *down*. I store the open circuit voltage in my scientific calculator and calculate the RL from time to time as I'm tweaking the L and C values. After awhile, the whole procedure becomes automatic and quick. Once you 're done and everything's tidy, measure the open circuit and connected amp peak-to-peak voltages and calculate RL a final time. This is your reportable return loss.

You can scale matching networks from other builder's schematics by calculating the XL and XL and then applying these reactances to your desired frequency. Bench tweaking is still required. I also hope the person whom I'm copying didn't make a bench or drafting error. Be discerning about whatever your find on the Internet "Misinformation Highway" — this site included. Although I'm no philosopher, I know at least 3 things about people. They: 1. are often biased; 2. can lie; and 3. can make errors.

Above —Some toroids and the *air variable capacitor* I sometimes use to **coarsely** bench tune L-C circuits to determine the "ballpark" tuning capacitance. This capacitor features built-in reduction drive and varies from 15pF to 428 pF. When using an external capacitor connected to your circuit with short copper wires, expect some signal distortion and watch out for hand and body caused capacitance variations. The connecting wires also have reactance which won't be there when you swap in a small trimmer cap plus any fixed value capacitors.

Next up is a common emitter amp using "noiseless" feedback - this means the AC feedback is achieved with transformers instead of "noisy" resistors.

3


Noiseless Collector-Emitter FBA
10
12.22 VDC
1N4148
180
330
.1
.1
1K
16t
8.59v
12t
7.95v
Q1
.1
50 Ω
Q1 = 2N3906
Q2= 2N5109
2K2
FT37-43
4K7
.1
22
Gain = 21.6 dB
Input RL = 22 – 29 dB
Output RL = 14.5 dB
IE = 34.3 mA
50 Ω
6.0 uH
Q2
.1
4t
L-match
22 pF
10 - 70 pF
10
Tested at 7.040 MHz

Above — Schematic of a 7 MHz collector-emitter "Griffiths" feedback amp. I ran substantial emitter current through this NPN. RC = 116.5 ohms — I paralleled 2 resistors for RC because I lack resistors between 100 and 150 ohms. The basic design is by Bruce Griffiths, who has a great web site. I thought I put up *big* schematics!

The input L-network was designed on the bench and provides a good input match peaked at 7.040 MHz — this pumped up the gain 3-4 dB. In my amp, a T50-2 powdered iron toroid inductor forms the L-match coil. Matching for the best possible input return loss is touchy and best done on the bench. For example, if the 6 uH inductor is decreased to 5.8 uH, the match could fall by 2-4 dB. With patience and careful tweaking return losses approaching 29 dB are possible, but likely too time consuming for most builders. The procedure as described earlier is pragmatic: connect a RL bridge to the input and adjust the L and C values until the lowest return loss is discovered. Even squishing or expanding the toroidal inductor windings can squeeze out a final dB or so of input matching.

Output matching proved interesting. Although I tried, the best output RL I could muster was 14.5 dB. Lowering the 10 Ω degeneration resistor or increasing the current could increase the output return loss. An output attenuator pad might be considered — a 3 - 6 dB pad would increase the output RL to over 20 dB.

All 3 output transformer windings were wound on a FT37-43 with care to keep the phasing correct. Amplifier gain is not dependent on collector current. For example, substituting an Ra of 180 ohms (clipping out the 330 Ω resistor) yielded a gain of 19.5 dB, an emitter current of ~ 20 mA and an output return loss of 12.6 dB, while the input match changed very little.

The oscillation snuffer 22 Ω collector resistor was 15 ohms in another version, however, parasitic oscillations were discovered at ~175 MHz and snuffed out by raising this resistor from 15 to 22 ohms. I sometimes go as high as 51 Ω; especially in JFET circuits.



Above — The breadboard of the noiseless collector-emitter 7 MHz feedback amp. Click for a photo of another version. The hot "modern" replacement for the 2N5109 is this SMT part. I also like the BFG135 T/R BJT.

The final FBA experiments *below* use a standard voltage divider bias, tweaked for temperature compensation. The AC feedback is base to emitter — a rarely used topology in North America; although I'm not sure why.

4

Base-Emitter FBA -- DC Bias Using a 2N2222a


12.22v
12.01v
180
8.45v
10
.1
.1
14t FT37-43
8K2
2N2222a
39
7.67
1.76v
1.14v
1K5
47
10
IE = 20.1 mA
Transistor temp 24.6 C
hFE = 150

Above — The DC bias resistor values for a 2N2222a with a DC Beta or hFE of 150 and a emitter current of 20.1 mA. Almost every text author writes about voltage divider bias temperature stability, but some builders get bogged down in the details. Since the bipolar junction transistor is a voltage controlled device *(see section 4: QRP-POSDATA for an explanation)*, you must set up some DC voltages — I created a design center presenting an easy approach to design reasonably temperature stable BJT amps. See **#5 Design Center** on the supplemental web page. After getting the bias, the AC parts were added, and the completed schematic is shown below.



Above — A base-emitter feedback amp built Dec 21, 2010. I read about base-emitter feedback in Dr. Rohde's book *(Reference 1)*. He had some discussion, a small signal model and lots of difficult math, but no circuit examples. After searching on the web I found 1 example in the HBR-2000 transceiver; a project designed and built my respected Canadian colleague Marcus, VE7CA. Click for his web site. I decided to build my own design using a L-match to tune the input to 50 Ω.

The above amp was built around around a 2N2222a. The 39 ohm resistor is not really required with the 2N2222a. For high F-t transistors like the 2N3866, 2N5109 or microwave transistors, ferrite bead(s) or the resistor are *not* an option. Low F-t transistors like the 2N2222a or 2N3904 don't need the UHF oscillation snuffer resistor since they lack real gain at these frequencies. With the design center, you should be able to bias your own amp according to the emitter current you want — choose a BJT, measure or choose its hFE and then choose IE.

Missing from this web page is how to choose an operating point + discussion about DC load lines and related topics. I may tackle these topics on a future web page. I'm not sure anyone cares about this anymore.

The most difficult part was the output transformer. Lacking a base to collector connection, the collector impedance runs quite high and finding a good match into 50 Ω proved impossible — even with a shunt resistor across the primary coil. I saw a strategy in Marcus' amp; AC couple the collector to ground via a 510 Ω resistor. I did this. From then on, it was just trial and error to identify the optimum turns ratio for the collector transformer. An interesting experiment might be to figure out the turns ratio using a lower loss output transformer such as a FT-37-61.

The turns ratio of the various collector and drain transformers on most of these amplifier designs were determined by placing the amp in an output RL measurement setup and adding or removing secondary turns to get the highest possible RL. See the procedures for RL measurement on the RF Workbench pages.



Above — The breadboard of the first version of the base-emitter FBA.

---

3. JFET Common Gate (CG)Transistor Amplifier Experiments

These experiments focus on setting up a desired input return loss and getting a reasonable output return loss in the CG amplifier. My expectation of an easy set of experiments proved wrong — assumptions never substitute for actually building and measuring.

I like motorcycles. The difference between riding a motorbike versus *driving* a car parallels learning on the bench versus learning by just simulating or calculating component "ideal" values on paper or computer. In the car you're isolated from wind, smells, temperature changes and subtle road traction and camber differences that you fully sense on the motorcycle. Bench experiments prove equally visceral and experiential — the sensory input from learning as you build and test circuits imprints deeply in your mind.

1


7 MHz JFET Linear Amplifier
12.22v
RFC
51
.1
.1
51
.1
T2
32
50 Ω
10
32
L1
1K5
Input RL = 20.8 dB
47 pF
1000 pF
22
s
d
20
s
d
50 Ω
T1
g
Cx
L2
g
.1
15
Q1
CV
Q2
510
CV
100
100
1000 pF
1000 pF
IS = 17.1 mA
IS = 17.9 mA
Output RL = 12.4 dB
Cx is tuned
Gain = 13.6 dB

T1 = 22t FT37-61; tap 15t from grounded end
Q1 = Q2 = J310 or U310
CV = 10 – 70 pF trimmer capacitor
L1 = 5.8 uH = 32t T50-2 toroid
L2 = 20t FT37-61 RFC = 15t FT37-43
T2 = L1 with 10 turn link

Above — A 7 MHz JFET "linear" amplifier built only for testing ideas — *do not build*. It went through several incarnations and prompted many experiments. The input return loss was deliberately set to 20.8 dB, although I set a RL from 10.0 - 28.6 dB during my experiments. Bypassing the JFET source resistor increases gain, but of course changes input RL.

The output transformer represents a terrible design, but shows the length I went to to try an obtain a decent output return loss. Working with this circuit, led me to abandon tuning the output transformer in situations where a high return loss was desired since the low value resistors required kill the tank Q significantly.



Above — Breadboard of 1 version of the prototype low-level JFET "linear" amplifiers for 7 MHz. Click Click . Cx is tuned with a variable cap and a nearest standard value substituted; in my case 46 pF was the measured value of the variable cap at point Cx.

Setting Input Impedance



Above — The procedure used to set a desired CG amplifier input Return Loss. Numerous factors influence the input impedance and I discuss them in **#4 Some Factors Affecting Common-Gate Amplifier Input Impedance** on the supplemental web page. I keep some tapped inductors on my workbench such as this FT50-43 or these FT50-61 core inductors. To find the best return loss using such a coil, you can change tap points, remove windings and even wind more turns and solder the 1 end of your new windings to 1 end of the existing wire. Some builders omit inductor taps and manipulate the input return loss other ways as described in the supplemental article.

Normally we set the input match after establishing the output match since the output impedance dramatically affects the input impedance.

Further, you might notice that the tap point may vary between different JFETs. Most of my "real world" coils have at least 2 tap points and I choose the tap that gives the best return loss. More often than not, I bias for 14 - 18 mA and leave off the source bypass capacitor; it's your call.

The input return loss that gives the lowest noise figure is often chosen by engineers.



Rx	IS (mA)	Gain (dB)	Input RL (dB)	Output RL (dB)
100	19.25	8.6	26.6	14.7
150	14.65	7.9	20.3	14.3
180	12.84	7.1	17.9	14.4

Above — An experimental 7 MHz common gate amp designed to terminate a diode ring mixer. The best thing about using 2 JFETs is that you don't have to determine the tap point in the decoupling inductor (12 turns on a FT37-43 in this amplifier). I put up to 4 in parallel during my various experiments. It's faster to match just 2 JFETs, so 2 were favored.

The output RL wasn't great at ~ 14 dB, however is probably normal or better than most published amateur projects. I set the output match by adding a shunt 1K8 resistor across the primary winding and then finding the turns ratio to give the best output return loss. Without the resistor, the best output RL will be ~5 dB or worse. The resistor reduces power.

I learned that putting JFETs in parallel in a common gate amplifier reduced the output return loss in circuits using an output transformer like in the schematic above; this is unfortunate.

I wanted an output RL of 20 dB or greater — this is no small request; over a week was spent investigating transformer behavior and finding ways to improve output return loss when you really *want* to.



Above — The breadboard of the above 7 MHz CG amplifier.

Output Impedance Experiments

For some reason, I assumed that when using an arithmetically correct turns ratio, the output transformer will end up at 50 Ωs. For example, if I wish to transform 450 ohms to 50 ohms, I'd use a 9:1 impedance ratio (3:1 turns ratio) and get 50 ohms. Sadly, it isn't this simple — impedance transformation is complicated and whole books have been written about it. I'll share some of my experiments that might inform yours.

The first task was to built a simple jig to evaluate primary and secondary coupling, turns ratios and return loss.


24t
5t
1K8
X
RETURN LOSS BRIDGE
F
D

Return Loss of FT37-43 transformer			Return Loss of FT37-61 transformer		
Frequency	7 MHz	14 MHz	Frequency	7 MHz	14 MHz
Open circuit	2.3 dB	2.4 dB	Open circuit	0.5 dB	0.9 dB
Shunt 1K8	16.7 dB	17.5 dB	Shunt 1K8	6.4 dB	11.8 dB

Transformer Return Loss Tool

Above — The simple tool built to evaluate the return loss of a transformer out-of-circuit. In this case, I examined the 24t : 5t transformer of the 7 MHz CG amplifier shown earlier. The table shows the best possible return loss when the 1K8 resistor is across the primary coil. Additional experiments were completed and follow below.


Determining optimal R
24t
5t
4K7
X
RETURN LOSS BRIDGE
F
D
FT37-61
A
24t
5t
1K2
X
RETURN LOSS BRIDGE
F
D
FT37-61
B

Return Loss = 16.7 dB @ 14 MHz

1200 : 50 ohms = 24Z ratio = 4.9 turns ratio

24 turns / 4.9 = 5 turns

Above — An experiment to see if changing the shunt resistor can improve return loss; yes it can. The shunt resistor was a 4K7 potentiometer — Using the potentiometer, I was able to determine the optimal resistance needed to increase the return loss @ 14 MHz of the **FT37-61** ferrite-base 24t : 5t transformer. The pot was removed, measured and replaced with the nearest standard value; a 1K2 resistor. The best possible RL was 16.7 dB using a 1K2 shunt resistor. At 7 MHz, the FT37-61 didn't work well. Five turns on a FT37-61 based transformer doesn't have enough inductive reactance to get a good return loss.



Above — The transformer testing jig. I omitted the switch shown in the schematic above and just soldered the shunt resistor across the primary winding.


200
50 Ω
10 BFT
7 MHz : 29.8 dB
14 MHz : 29.5 dB
4:1 Z
10t
5t
50 Ω
200
7 MHz : 19.7 dB
14 MHz : 18.7 dB
20t
10t
50 Ω
200
7 MHz : 22.2 dB
14 MHz 16.9 dB
450
50 Ω
10 TFT
7 MHz : 26.7 dB
14 MHz : 22.6 dB
Return Loss with some FT37-43 transformers
24t
8t
50 Ω
450
9:1 Z
7 MHz : 14.6 dB
14 MHz : 14.8 dB

Above — Some of the outcomes using the transformer jig pictured above. While I basically understood that transformer efficiency tends to fall as the turns ratio increases, I never thought this would also happen with return loss. By *no* means do these crude experiments constitute science, but the following themes emerged:

1. The better coupling of transmission line transformers (bifilar, trifilar etc.) translates into improved RL over conventionally wound transformers
2. Limiting the turns ratio to 3:1 or less generally improved the return loss. As the turns ratio moves above 3:1, the best possible return loss tends to decrease.
3. The smaller or secondary winding should have 4-10 times the inductive reactance of the impedance it's connected to. For a 50 ohms impedance this means a minimal XL of 200 - 500 ohms. I noticed a weak trend towards better return loss with higher XLs. This means that to use a FT37-61 at 7 MHz, the secondary winding should be 9 -14 turns or so.


Transformer Experiments
200
50 Ω
10 BFT FT37-61
4:1 Z ratio
7 MHz : 8.9 dB RL
14 MHz : 14.3 dB RL
820
50 Ω
10 BFT FT37-43
16:1 Z ratio
7 MHz : 27.7 dB RL
14 MHz : 20.6 dB RL
=
820
16:1 Z ratio
50 Ω
10 QFT FT37-43

Above — Further transformer experiments. For a 4:1 impedance transformation at 7 and 14 MHz, a FT37-43 ferrite toroid gave a better out-of-circuit RL than the FT37-61 *The comparison transformer with a FT37-43 ferrite core was shown earlier*. It's possible to transform a big impedance such as 16:1 by cascading 2 bifilar transformers, or by using a quadrifilar transformer. I didn't build the quadrifilar transmission line transformer, but show it for completeness sake.

Of course, once you connect the transformers to a real circuit, things will change — still it's great to be able to examine transformer return loss in a controlled environment.



Data with Resistor	
Input RL	22.4 dB
Output RL	20.6 dB
Gain	3.1 dB
Data No Resistor	
Input RL	21.8 dB
Output RL	3.4 dB
Gain	8.5 dB

7 MHz CG Amp
.1
12.22v
51
10 BFT FT37-43
820
.1
50 Ω
.1
J310
s
d
g
33
50 Ω
2t
12t
FT37-43
100
.1
18 mA

Above — a common gate amplifier experiment using 2 cascaded 4:1 Z transmission line transformers. Data with and without the 820 Ω resistor shows that while the resistor gives a great output RL; it eats a lot of power. In cases where I've seen cascaded transmission line transformers used, the resistor was omitted. The Ugly Weekender transmitter by Wes, W7ZOI provides a good example.

In many cases, it's prudent to sacrifice gain for return loss, however, when you see a builder (like the former me), put a 32:3 turns ratio on a 5 MHz amplifier output transformer and label the secondary windings **"50 Ω",** we'll know better.



Above — An evolution of the amplifier above to get the best possible output RL. I omitted the 820 ohm resistor and matched the output with an L-network. The return loss on the output of the second transmission line transformer (measured before the L-match was added) was 3.4 dB.

The L-match values were *roughly* determined by using this chart (you can also do the math). According to the chart an *(output)* RL of 3.4 dB, is either 10 ohms or ~250 ohms or so. Ten ohms is unlikely, so I designed my L-match to match 250 to 50 ohms. This provided some starting values for the L and C parts and the rest was done on the bench using trial and error with an RL bridge. At the time, this was the highest output RL I'd ever achieved.

RF engineers use math to calculate impedance (they always do). I sent the schematic to Wes, W7ZOI for his analysis and summarize his return email comments as follows: At 7 MHz, the XL of the 2.22uH inductor is 97.6 Ω, therefore the impedance looking into that with 50 Ohms as the load is 50+j97.6. A complex inversion of this value gives a complex admittance that has a real part: 0.0041. Flipping that gives 240 Ω. The equivalent reactance is inductive with a value that would be tuned by a 184 pF capacitor; a bit more than you have there — so there is some reactance presented by the center tap of the second transformer. Neglecting these details, the L net generates about 240 Ohms. The two transformers then kick the Z up by 16 to 3856 Ohms.

I was pleased that my simple chart gave a value close to his calculation. Test it out — the chart may work okay for you.

The input match is over 20 dB and reasonable. More time could have been spent on the input autotransformer by tapping and such to increase the input RL, however, time is the 1 resource we all seem to lack.

4

The final amplifier experiments employ an L-match to set output return loss. When reading electrical engineering books you'll often see all sorts of matching networks on both the input and output of FETs and BJT amplifiers. The networks look simple, but in practice, aren't. They tune sharply, have a low bandwidth and in the case of the CG amp, harbor a big problem — tuning the output for the best output return loss, **dramatically** affects the *input* return loss and potentially, your return loss measurement by the reactance affecting the RF signal in your bridge.

When tuning the output, you're actually changing 2 complex impedances — this is not trivial.

Also if you're off by a few pF or tens of uH in your network C and L values respectively, you can wreak havoc with the measurements. At this point, I don't possess all the skills needed to tune both the output and the input network to a RL of 20 dB or greater; especially with a broadband input.



Above — A common gate amp employing a high-pass L-network to match the output. Miraculously after 2 hours of tweaking, I obtained a good input and output match; however this amp isn't reproducible. The inductor was wound on a T68-2 using 28 gauge wire — always a pain. Through trial and error, I learned that the output impedance of the drain was around 11800 ohms. Starting with 18.4 uH on theT68-2, I removed 2-3 turns at a time until a reasonably low return loss was obtained; then I removed 1 turn at a time. I went too far and had to add back a turn. I clipped the excess lead every second turn which made it tedious, but exacting. It seems that the L value is very critical – it would be nice to use a variable inductor to figure these things out. Compressing and expanding the windings also provided a simple way to vary inductance.

In several other circuits, the best possible input return loss was only 14 dB. Mistuning also caused oscillations to occur in one 14 MHz amp with an output network inductor of 7.4 uH. I also tried a 14 MHz amp with an L-match on both the input and output, however, was unable to match both the input and output due to the interplay between them.


High-pass
L
50 Ω
s
d
g
C
High-pass with parallel C
L
50 Ω
s
d
g
C
C
Low-pass
RFC
50 Ω
s
d
g
C
L
.1
L-Match Networks

Above — Here are 3 possible L-network configurations for tuning a CG amplifier output. They can be used in other circuits and are worth studying. The L-match with 2 variable capacitors generally requires lower inductance than the others.



Above — A breadboard of 1 of the high-pass tuned CG amps. The gate lead on this transistor is too long — the inductance will likely cause UHF oscillations. 2 ferrite beads were placed on the drain to mitigate these, but a better construction technique is recommended and shown below.



Above — the preferred way to ground the gate with the JFET on its side. The hole-through version of the U310 JFET has a metal case that is connected to the gate that makes it ideal for grounded gate amplifiers. Some suppliers only sell SMT versions of the U310 now.

4. QRP — Posdata for January 2013: Transistor Bias Model

This discussion concerns setting up the DC bias point for linear BJT operation.

Earlier I stated that a bipolar transistor is a voltage controlled device. A few readers thought I made a typo: something I frequently do, but not in this case, since I purposely made that statement. In reality, the argument could go either way since collector–emitter current is controlled by the base-emitter current (~a current controlled device) and by the base–emitter voltage (~a voltage controlled device).

Stated using the correct physical model, a transistor is a **current controlled current source**. With external circuitry we can manipulate this physical model into a voltage controlled current source, or a voltage controlled voltage source, or even a current controlled voltage source. Whether you model the transistor with current or voltage, the math tells the truth when properly examined.

Please view the following two 2N3904 SPICE models generated by Wes, W7ZOI for me many years ago when I began to learn small signal analysis using impedance and hybrid parameters, plus set out to learn ways to establish DC bias and temperature stability in BJTs.



Above — the Y axis shows how changing base-emitter voltage or current changes the VBE. We tend to assume a VBE of 0.7, however, the math shows the truth. Whether we plot voltage or current for the Y axis data, the graph slope remains similar. The greater the applied DC voltage placed on the base-emitter port, the more current will flow.



Above — Logarithimic base current plotted against VBE. If we want this current to increase, we need to put more DC voltage on the BE junction. On the bench, we may easily measure base voltage to confirm our calculations — measuring base current proves more difficult. Whether I'm setting up amplifer bias with voltage dividers, a current source, or even biasing it with a downstream AGC voltage, I prefer to think in terms of voltage control — although I get that V and I truly just coexist.

Current or voltage modelling — it's your choice and the math will guide you. Look for these equations on the Web, or in second hand bookstores. I've got 8 or 9 transistor theory books now and they're really timeless.

---

5. Miscellaneous Figures and Photographs

ECS D
11.04-
KOREA

RF

Shunt Feedback
Decreases input Z
Affects current gain



FBA

RE

Series Feedback
Increases input Z
Affects voltage gain
emitter degeneration



6. References

1. Communications Receivers - Principles & Design. Rohde, L.R and Bucher, T.T.N. 1988. McGraw-Hill.
2. Technical Correspondence QST Magazine (ARRL) Aug 1990. Hayward W.
3. Experimental Methods in RF Design (ARRL) 2003. Hayward W. Campbell R. Larkin B.
4. Microwave Handbook Vol 1. Components and Operating Techniques. 1989 RSGB.
5. Emails with Wes, W7ZOI and Professor Ken Kuhn, Winter 2010-2011 — Thanks! Никогда не забуд.

QRP SWL HOMEBUILDER

RF — Test and Measurement

Hobby and Fun 2011



Introduction

Hobbies are supposed to be for recreation. Electronics should be fun, not stressful — heavy math, big parts counts and complexity are more likely to scare away experimenters than recruit them. This page avoids the measurement focus of my latest stuff and simply promotes fun and discovery.

You might be interested to know that my simple experiments/projects garner the most emails. Many wrote "I'm rediscovering electronics", or, "I want a simple and fun hobby". Hobby and fun are my goals too.

Simple Regenerative Receiver Experiments



Above — 2 air variable capacitors and a copper clad board screwed onto a piece of wood for my bench musing. Regenerative receivers delight and amaze — some builders take them very seriously. I respect this, but to me; they should be as simple as possible. I wanted a 2 stage "genny" receiver for this page and present 2 different receivers; 1 is my design, the others is a JFET variant of a favorite W7ZOI circuit. Quoting Wes, W7ZOI "feedback your imagination".

Some builders place a simple common gate or a common base RF preamp on the input to boost gain and reduce antenna radiation of the RF oscillator, while others place an RF gain control on the input — usually a potentiometer; to prevent overloading the RF stage. I won't prescribe what to do — that's up to you. There are countless example of regenerative receivers on the web and you can many spend hours viewing them. Some of the most intriguing are those built by Russian speaking experimenters. Example link.

My circuit ideas are meant as fodder for your own experiments.


Frequency : 5339 kHz
Station : 52EX, Chinese military
FT50-61 ferrite core
8t
2t
150 pF
3t
10K
1 uF
To
AF amp
*
2N3904
.1
470 pF
.001
C0G
2K2
270
10K
40M band
1/4 wave
vertical
39K
150
12.22V
.1
* Tuning cap 10 - 200 pF
79 pF @ 5339 KHz

Above — An experimental, ultra-simple "CW" receiver. At 5339 KHz I hear strong Morse code each night. It's suggested to be from China, but I'm unsure. Connected to my 1/4 wave 40M band vertical - a simple matching network and trimmer tuning capacitor were fitted to the input. Here's some audio. I like the beat note of this receiver - it has no regeneration control and is fixed for CW. Minimalist circuits are fun — some hardcore regen builders might freak out; no voltage regulator (here's a version with that + a T68-6 inductor), no regeneration control (here's a version with that), a relatively low Q coil etc. I wanted to try my hand at design and not just copy someone else's receiver.

I call it the Stupid— Simple receiver and although it emits crisp, warm audio, some bench work is required to get the correct bias and appropriate amount of positive RF feedback — an experimenter's circuit that explores DC bias and AC feedback. The sort of thing a father can build with his son. We need more circuits fitting this profile.


6 MHz Short wave
T68-6 3.1 uH
22t
7t
6t
68 pF
470 pF
*
10K
1 uF
To AF amp
2N3904
2.28v
.1
0.69v
0.05v
.001
C0G
1K2
150
7K5
10K
40M band
1/4 wave
vertical
Tuning cap = 10 - 200 pF
93 pF @ 6010 KHz *
5v Reg
.1
12.22v
The Stupid — Simple

Above — The Stupid—Simple experimental receiver set up for ~6 - 7 MHz. 2011 marks the 50th anniversary of Radio Habana Cuba. We tune RHC at 6010 KHz, and as long as I've been listening to SW radio, I've tuned this station. Here are 3 sound bytes from around 6 MHz recorded from 2:30-2:40 GMT on Feb 28, 2011, including an old repeated episode of DX'ers Unlimited by Arnie Coro which had faded out by the time I located and turned on my audio recorder. Audio1 Audio2 Audio 3. The audio stage in these recording was a discrete transistor AF amp I designed, however, an LM386 was chosen for the final amp to keep the parts count and difficulty down. I got a little too close to the receiver a couple of times during the recording and made the open circuit breadboard squeal.

Arnie Coro talked about a "regenerodyne" receiver in Sound Byte *Audio3*. Very cool. Here's a link. Now this is radio!



Above — The Stupid-Simple regenerative receiver breadboard for 6 MHz. You can see the T68-6 — the red secondary windings are wound in the same direction as the 22 turns of primary. I started with 9 turns and unwound a link and tested sequentially until I had the right amount of feedback for AM. I just used normal hook up wire for the secondary winding. The white colored cable goes to the audio amp. This is a prototype experimental layout — a regenerative receiver should have short connections around the tank circuit and be in metal box for best results.

On some stations, my little 1 RF + 1 AF stage receiver sounded better than my superheterodyne receivers. The 2N3904 is just barely turned on — I determined that a base bias of 0.66-0.69v provided maximal sensitivity. The 150 ohm emitter resistor can be a 500 ohm pot and used to fine tune the regeneration. 150 ohms gave the best compromise gain and feedback + current for the 2N3904.

Audio Amplifier



Above — I chose an LM386-N for my AF power amplifier. The LM386 exhibits less peak signal distortion when run in the low-power (X20) gain mode and a higher VCC such as 12 volts. My receiver used the schematic denoted B — a 10K and 0.033 to 0.047 uF RC network is used to reduce the amplifier high frequency response. Click for a sound byte of me tuning around 6 MHz with a 10K + 0.047 uF RC network between pins 1 and 5. Figure B is my favorite way to use the LM386 and comes right off the National Semiconductor LM386 data sheet. Look for this data sheet with your favorite search engine.

Because I have a big antenna, Figure B provides adequate volume to a speaker. Connecting pins 1 and 8 via a 10 uF capacitor bypasses some emitter resistance and gives X200 gain. A resistor in series with the capacitor pin 1 and 8 will reduce the gain. Figure A shows a gain = 50 configuration. You'll have to choose the LM386 set gain to suit your particular regenerative receiver, however, the greater the gain setting, the greater the chance of distortion, unwanted noise and audio feedback.

I generally build my audio power amps around op amps or discrete transistors, but the LM386 exalts this web page's theme. Distortion in all these small power amplifiers is dependent on input signal amplitude as much as anything else.

LM386 Motorboaters

Expect AF feedback motorboating via your DC power lines as you increase the AF gain pot in *many* LM386 circuits. If this happens, try better bypass and decoupling on the LM386 power line: 100 to 470 μF shunt bypass on the DC line + a 10-22 series decoupling resistor, plus 100 - 470 μF shunt bypass on pin 6. Click for 1 example. ypically 470 μF bypass is required if you suffer 60 hertz hum. You may model your simple RC filter with application E on the javascript applet page to see the 3 dB cut off frequency of your particular DC line low-pass filter.

Stupid—Simple Notes

The Stupid—Simple circuit really needs the adjustable 10K regeneration control if you wish to tune both AM and CW. The number of turns on the feedback winding varies with factors including transistor beta, how you wind the primary and secondary windings (greatly affects the coupling between the primary and secondary windings) and whether you want AM, or CW reception — or both. Experiment with the number of turns to figure it out.

You can try "matching" the tank circuit to your antenna by decreasing the 470 pF cap to as low as 68 pF. This will affect the tuning capacitor range. For an air variable tuning capacitor, use anything you can find. Consider connecting fixed parallel and/or series capacitors to reach or limit the desired capacitance. Many good examples are published on the web.

Some builders float the tuning capacitor across the inductor so the cap is ungrounded. The stator (body) of the capacitor should be connected to the circuit ground to help minimize the effects of hand capacitance. A grounded metal case further helps.



Above — My popcorn regenerative design "The Stupid-Simple" set up for broadcast band radio at 1150 KHz.

A reader from Brazil enquired about putting the Simple Stupid on MW. I had some time for a couple of experiments but only wanted 1 frequency — 1150 KHz, the local 10 KW sports radio station. Using 28 gauge wire, I wound 54 turns (about 230 uH) on a A FT-114-61. Most builders won't have this toroid, however ferrite rods from AM radios are plentiful and a great substitute.

This design relaxed the regeneration to improve audio quality (no whining or hissing). The bias and feedback loop were wound for the best sounding audio. For example, at the bias shown, if you increased the 19 turn link to 21 turns, the bass response increases; decreasing to 17 turns reduces the bass response.

As a result of lowered positive feedback, the selectivity is down, however, a variable capacitor is needed to peak the station. After peak tuning, I removed and measured the air variable cap at ~ 200 pF and then substituted a 220 pF fixed capacitor to simplify things.

For audio, I used a bench AF power amp into a speaker. It sounds nice for 1 transistor. Audio sample



Above — The breadboard of the 1 channel receiver for my workshop - I'll use it to keep track of the Canadian Football League statistics. My test antenna was a long piece of outside wire. Red hook-up wire forms the 19 turn feedback winding.

For cities with multiple AM stations (AM stations are dying out in Canada), you'll have to add more regeneration and probably move to a better design. This radio is simple, but not extraordinary.



Above — Another regenerative design that tuned AM, SSB and CW from 5-11 MHz with different toroid coils wound on a T50-6. It's based on a favorite design by Wes, W7ZOI. I suggest tapping L1 at 10 - 25% of the total number of turns. The secondary link for the antenna connection depends on the impedance of the antenna, but 5 - 10% of the total number of L1 primary turns worked well at my QTH. Please experiment with the secondary link to determine the optimal coupling to your antenna. My L1 inductance ranged from 1.5 to 5.6 uH. You may have to add a fixed capacitor in parallel with your air variable capacitor when using low inductance coils such as 1.5 uH.

The 51 ohm resistor suppresses UHF parasitic oscillations. The AF transformer is a transistor radio output (1000 : 8 ohm) junk box special and serves as an RF choke. I tried various AF transformers harvested from old transistor radios in this slot and they all worked fine. Nothing's really critical on this receiver — that's why I like it. Truly junk box radio.

Simple Active Antenna Experiments



Above — A voltage probe or active antenna using a telescopic whip. It's been awhile since I built one in keeping with a minimalistic circuit theme. I tested this VPA from 5 to 14 MHz. The center tap on the coil allows the peaking at ~10 MHz and higher. The L value is non-critical; choose a value that will work with your tuning variable capacitor or varactor. The L - C values can be *roughly* determined from a chart like this, or just do the math (XL = XC at the desired frequency). Account for stray inductance. If you wish to perform return loss measurements on this circuit, you'll have to short the 6.7 uH inductor as the whip antenna can tune in RF from the RF signal generator used for the return loss bridge.

Without the 1K load, the circuit will oscillate. I thought about some ways to match the output transformer to a regenerative receiver tank circuit. The 100 uH drain choke could be replaced by a (bifilar) 2:1 transmission line transformer or two. Transformer experiments this Winter clearly illustrated the superior coupling of transmission line transformers and mandates using them over conventional transformers whenever possible.

Using a conventional transformer with a shunt resistor across the transformer would also work, but the resistor reduces gain. I built and tested this output circuit with an 8:1 transformation using two 2:1 transmission line transformers. The output impedance at the JFET drain is somewhere around 4300-4500 ohms at 7-14 MHz. The transformed output impedance is somewhere around 250-330 ohms at 7- 14 MHz. Connecting the VPA output to a tap in the regenerative main tuning inductor might work — being careful not to load down the regenerative tank coil.



Above — The VPA breadboard on my latest notebook. The 100K pot sets the stage gain. While simple, it works okay.



Above — the VPA built March 12, 2011 (the 14-200 pF air variable cap is not shown). It took about 45 minutes to design, build and test it. The 1K load used for testing is the blue resistor to the extreme right.

Low-pass Filter for 21 MHz


15M Band Low-pass Filter
477 nH
559 nH
477 nH
50 Ω
50 Ω
120 pF
270 pF
270 pF
120 pF
Insertion loss at 21.060 MHz = 0.31 dB

Above — A 7 element Chebyshev low-pass filter for the 15 Meters Ham band (fCo = 25.03 MHz to allow the use of standard value capacitors). A builder requested a band-pass filter design for his 15M band receiver. In order to accurately test my design, I decided to make a permanent, low-pass filter module to follow my signal generator. 15 Meters is a favorite Ham band, so I'm certain to use it in the future.


File
About GPLA
S21 =
S11 =
S21 Ref.
Click to Review Circuit
top
dB
Plot
dB/div.
bottom
start
Frequency
Freq./div stop
Place Cursor
Cursor Data =====>:
Enter #
Enter New Value
Click to load new value

3 dB = 25.03 MHz
20 dB = 34.63 MHz
40 dB = 39.48 MHz

15M Band Low-pass

#, part, connection, value:
0 Load R = 50.0
1 cap par 120.0000
2 ind ser 477.0000
3 cap par 270.0000
4 ind ser 559.0000
5 cap par 270.0000
6 ind ser 477.0000
7 cap par 120.0000
98 Source R = 50.0
99 Inductor Q = 220.0

top: 0.0
dB/div.: 10.00
bottom: -60.0
start: 18 MHz
Freq./div: 5
stop: 60
C:\Users\Tyko\Todds\QRPHB\QRPHB\20
Enter #: 99
Enter New Value: 220
Cursor Data: 21.060 MHz
S21= -0.16 dB
S11= 0.00 dB

Above — A GPLA plot of the filter. The frequency cut-off at -3, -20 and -40 dB are shown. Perhaps this filter is overkill, but I had all the parts on hand and love a serious low-pass filter. Click for the bread board photo.

Fine-Tuneable 1 KHz Wein Bridge Oscillator

FINE TUNING
AF GAIN

In 2010, I wanted a fine-tuneable Wien bridge oscillator to drive a notch filter in an AF distortion analyzer. Ken Kuhn drew me up a schematic on his coffee break and emailed it the same morning.


.022
7.50K
V+
2K
10 turn
2K0
3
8
.1
+
−
1
2K0
.1
2
4
7.50K
.022
V-
0.15
-12 dB
@ 7K5 Ω
998 Hz Q = 5.3
30.1K
22.6K
5
+
7
10.0K
.001
6
−
Prototype
July 6, 2010
low pass filter
4.7 uF
wien bridge oscillator
10.0K
24.3K
1N4148 x2
1K
10.0K
969-1025 Hertz
@ present
OPA2134
12.4K
Fine Tunable 1 KHz Wien Bridge Oscillator

I applied anti-parallel diodes instead of the classic incandescent bulb for amplitude stabalization in the feedback loop; probably a mistake leading to higher distortion. Ken's fine-tuning circuit works perfectly. I matched the 7K5 + 2K0 + 0.22 uF components on each filter half. 1% parts go in this circuit.


.022
8.2K
V+
2K
10 turn
2K0
3
8
.1
2K0
+
-
1
2
.1
4
8.2K
.022
V-
Wien bridge oscillator
10.0K
24.3K
10.0K
1N4148 x2
12.4K
OPA2134
-20.8 dB
1.96K
Z
.22
V+
.1
21.5K
16.2K
3
8
2.15K
.018
Q = 1.08
2
4
.1
1
V-
.47
OPA2604
2.21K
17.8K
5
+
.0015
6
-
7
Q = 5.58
low pass filters
fC0 = 1010 Hz
4.7 uF
1K
Fine Tunable 905 Hz
Wien Bridge Oscillator

A version for 905 Hertz built with crazy expensive op-amps. I chose 905 Hz to match my notch filter frequency.



My breadboard.

QRP Modules 2011

Introduction



As experimenters, we rebuild core circuits over time. I decided to increase my collection of stock modular circuits to avoid re-inventing the wheel. This web page serves as a module repository for the website.

Since our needs differ, I've shared these circuits more for interest sake and really not as schematics to copy. All modules were carefully built and tested.

1 great virtue of the metal encased module is strong shielding. RF modules use a 50 ohm port impedance and BNC connectors. RCA jacks interface the AF modules.

---

40 Meter Band-pass Filter


7 MHz Band-pass Filter
5 pF
47 pF
47 pF
50 Ω
50 Ω
2.4 uH
120 pF
33 pF
CV
CV
120 pF
33 pF
Qu = 220
FC = 7.040 MHz
BW = 237 KHz
IL = 2.1 dB
S11 = - 27 dB
CV = 2 - 20 pF

Above — A 40 Meter Ham band double-tuned band-pass filter. I designed this circuit using 2 programs that came with EMRFD and describe the process on this web page. The 2.4 uH measured coils were wound using #22 AWG wire on T68-6 powdered iron toroids and all fixed caps were ceramic C0G type. I centered my filter at 7.040 MHz. You should be able to peak it anywhere on the 40 Meter CW sub-band by tweaking the variable capacitors.

I peaked the trimmer capacitor while looking at the peak-to-peak voltage on a 50 ohm terminated oscilloscope. The filter input was connected to a 7.040 MHz signal generator with a 30 dB return loss, low harmonics (-55 dBc) and 50 ohm cables.



#, part, connection, value:

0 Load R = 50.0
1 cap ser 48.0000
2 ind par 2400.0000
3 cap par 160.1000
4 cap ser 5.0000
5 cap par 160.1000
6 ind par 2400.0000
7 cap ser 48.0000
8 rlb ser 0.0000
98 Source R = 50.0
99 Inductor Q = 220.0

-3 dB BW = 237 KHz

Enter # 3

Enter New Value 160.1

10.00 dB/div.

bottom -60.0

start 5 Frequency MHz 0.5 Freq./div stop 9

C:\Users\Tyko\Todds\QRPHB\QRPHB\20

Cursor Data =====> 7.04 MHz S21= -1.68 dB S11= -37.15 dB

☑ Plot S11 ☐ Plot Referenc

Above — A simulation of my filter design in in GPLA08. The calculated IL was 1.68 dB, I measured the IL at 2.1 dB The calculated return loss or S11 was 37.2 dB; I measured 27 dB. A good filter.



Above — the 40 meter double tuned band-pass filter breadboard with temporary BNC connectors and series caps. Since this filter will serve as my main front-end filter for all future 40M band receiver bench design, I blinged out and put in big toroids and high Q, air-variable trimmer capacitors. While I could have just use a single 150 pF tank capacitor and a wide range trimmer cap such as common, ceramic 10-70 pF, the small range, high Q trimmer capacitors offer better performance and fine tuning.

Click for a spectrum analyzer +tracking generator sweep where the center frequency = 7.040 MHz. Graticules: Horizontal = 1 MHz per division, Vertical = 10 dB per division. You can see why it tunes so sharply.

After testing the bread-board, I removed the temporary BNC connectors and series caps, I stuck it in a Hammond box and wired in permanent, short leaded 47 pF capacitors. Final testing in the sealed box varied minimally from the open bread board. This board looks especially ugly because it held a previous filter and contained lots of remnant solder.

Broadband Feedback Amp


Beaverton Special
Feedback Amp
2N2222a
12.21v
51
10 bifilar turns
FT37-43
11.02v
.1
.1
1K5
1K5
heat sink
50 Ω
50 Ω
.1
.1
1K
2.67v
2.07v
100
.1
4.7
24.2 mA

Frequency	Gain
5 MHz	21.4 dB
7 MHz	21.1 dB
14 MHz	19.3 dB
21 MHz	17.8 dB

Return Loss in dB

Freq	Input	Output
5 MHz	19.3	30
7 MHz	21.9	30
14 MHz	20.4	26.3
21 MHz	24.4	26.4

Above — A "Beaverton Special" feedback amp with analysis. As experimenters, we often need a go-to, broadband 50 ohms input and output RF amplifier. This is it!

Popularized by Wes, W7ZOI and Doug DeMaw, W1FB, this amp has stood the test of time and fits perfectly into the 50 ohm module concept. A bevy of transistors were tried — a 2N4401, 2N5179, 2N3904, 2N3866 or 2N5109 all worked fine. For the greatest return loss and signal handling possible, current over 21 mA is required and thus a 2N3904 isn't the best choice. Collector current = heat, so heat sink the BJT as appropriate.

I found that a 2N2222a biased with over 22 mA emitter current gave a stellar output return loss and low distortion. Within reason, for different transistors, keep the bias and feedback resistors constant and change the emitter resistor (100 ohms in my amp) to set the current you want or need.

Many builders follow this amp with an attenuator pad to preserve the input return loss.

Diode Ring Mixer


Diode Ring Mixer
LO
Diode Ring
RF
RF IF G LO
TUF-1
bottom up
IF

Above — A Minicircuits TUF-1 diode ring mixer was used in standard configuration. 7 dBm LO drive.



Above — The DRM module. It's hard to photograph inside a solder laden chassis. Connections are short.

Popcorn Audio Frequency Power Amplifiers


Popcorn Receiver Audio Amp
12.22v
.01
150
1K
33 uF
1K5
100 uF
10
470 uF
4.7 uF
6K8
10K
10K
4
3
6
5
LM386
470 uF
2
1
7
10
10K
4K7
22 uF
10K
.1
1 uF
4K7
2N3906
.039
15K
22 uF
2N3904
405 mW average power

Above — Popcorn receiver audio power amp. I wanted a simple audio stage for testing popcorn receivers (to follow a high output impedance preamp device). Completing this module means never having to build such an amp again. The voltage gain is provided by BJTs to keep the noise down, but the popcorn factor up. The preamp impressed me with its strong signal handling capacity via feedback and careful biasing. The NPN is center biased so that when its intentionally distorted during testing, the positive and negative halves of the AC waveform distort equally — it provides a nice, big, AC voltage swing. An LM386 in X20 gain mode with some bass boosting comprises a reasonable power amp section. The 10K resistor on the output discharges the 470 uF cap when no speaker is connected to avoid a loud pop. The 4K7 series input R can be lowered, or omitted for more sensitivity.

Some builders might employ the LM386 in a higher gain mode at the expense of fidelity, or just wire up a TDA7052. I think in popcorn circuits, what really matters is that you understand what you're doing and try to *design* rather than just copy the "usual circuits".

POS
POPCORN RECEIVER AF AMP
OUT
GAIN

Above — The popcorn AF amp in a clear blue chassis. Phono jacks provided a connection for the input and output — they 're inexpensive and readily available. The DC supply is connected to uninsulated banana jacks on the rear; it's well decoupled (resistor) + bypassed (capacitor) to help stop parasitic AF feedback. This amp is pretty quiet, considering its junk box legacy.



Above — The project with the top cover removed. The board is secured by the ground wires connecting it to the pot, jacks and DC voltage posts. The input is on the right.

I like a relatively simple, lower gain AF amp on the bench for receiver development. You can use such an amp to decide on how much overall AF gain is needed, how you'll distribute it, and not have to deal with unwanted AF feedback.


12.22v
470 -
1000 uF
100
100 uF
1K2
set TP1
@ 1/2 VCC
BD139
6.78v
1N4148
1 Ω
BIAS
10K
22 uF
1.33v
TP1
6.11v
1000 uF
9.7K
nominal
1 Ω
1N4148
BD140
5.45v
4K7
8 Ω
1.75v
10K
2N3906
1 uF
100
470 pF
1.17v
100 uF
2N3904
1K
Volume
1W AF-PA
0.89v
1K
47
Clean power = 1.1 W
Quiescent draw = 28 mA
Gain = 15.3 dB

Above — 1 watt popcorn audio power amplifier. Built around the BD139/140 complimentary pair - I achieved a clean I KHz sine wave at 1.1 Watts power after testing + tweaking my prototype design. I chose the familiar series diode pair to bias the power followers into Class A/B; an amplified diode (transistor level shifter) might be a better choice.

Bootstrapping the 2N3904 voltage amp pumps up the clean signal power capacity. The 2N3906 establishes the bias for the 2N3904 and the BD139-140 pair. Set the 10K bias pot so that the DC voltage at TP1 is 1/2 of the VCC. During testing, the AC voltage was centered perfectly between the DC rails and when pushed into clipping, the positive and negative AC waveform distorted nearly equally. Quiescent current = 28 mA ; not meant for a field-portable receiver.

Click for a photo of my breadboard. Copper clad board serves as heat sinks for the power followers. The BD139 and BD140 make great complimentary transistors for audio frequency power amplifiers. With an Ft of 190 MHz, the BD139 can work okay as a driver or even the final in modest power QRP transmitters.



Above — 1 watt Audio PA (reverse view).

Pop DC2 — Popcorn Direct Conversion Receiver Main Frame

These circuits update the Popcorn DC receiver from 1998 and includes all components from the product detector through to the speaker, minus the VFO and band-pass filter.


Pop DC2
To DC Supply
75
75
470 uF
11.73v
100 uF
11.92v
FCo = 882 Hertz
820
1K2
820
820
LO 7 dBm
Q1
Q2
.22
- .47
.22
.22
16t FT37-43
0.77v
3.88v
LO
RF
AF
3.21v
.1
100 uF
.096v
ADE-1
1K
15
1K
51
Q1 = Q2= 2N5089
Band-pass FL
6.54 mA
3.28 mA
2K7
390
Popcorn Direct Conversion Receiver Main Frame

Above — The mixer and first audio preamplifier The 0.22 uF to 0.47uF cap connecting Q2's collector to the low-pass filter network exerts a high-pass response to remove low frequency noise and potentially any hum. I heard no hum, although a 470 uF filter capacitor on Q1 helps ensure that. Increase the 100 uF filter capacitor filtering Q2 if you hear hum or motor boating. The diode ring mixer exhibits AF that's hard to beat — very dynamic, vibrant and lively. I enjoyed the low microphonics with the double balance + a return loss of over 25 dB on all of 3 of its ports. Alternate photo.

I've read negative comments about my use of "those big filter capacitors" — 1 thing radiophiles can learn from audiophiles is that to adequately decouple and bypass means we need to stop fooling around with the usual 22 - 47 uF capacitors and *really* bypass. Viewing well designed AF amplifiers informs us so; these designers *really* filter their amplifiers from the DC supply. You can always increase the decoupling resistor value to allow use of a smaller capacitor value, however, we only have a single power supply at around 12 VDC, and I dislike giving up too much of it for DC filtering purposes. Do what ever amuses you.

Click for some analysis of the preamp. The MPSA18 went obsolete in 2011, so I chose the low-noise 2N5089 for Q1 and Q2.

The Popcorn DC2 receiver keeps the format of the earlier version; discrete transistors for all but the power amp and R-C low-pass filtering. The filter still allows you to listen to SSB, as there aren't many poles and the cutoff is nearly 900 Hertz —it just removes the ice-pick in the ear often heard in unfiltered DC receivers. You can change the capacitor values for a different cutoff frequency. Applet E performs this function.

Second Preamplifier Stage with TDA7052 final



Above — The 2nd pre-amp and AF power amp. Experimenting with a number of audio stages, I decided on this cascode common emitter / common base amp biased to provide temperature stability, high gain, low distortion + proper termination of the low-pass filter. (The input Return Loss = 19 dB in my 820 ohm bridge set up). Increase the 100 uF filter capacitor on Q3 up to as high as 470 uF if you hear motor boating (low frequency thumping). This stage is prone to feedback since it's directly connected to the power amp. Photograph.

The simple and effective TDA bridged amp has a fixed gain of 40, so this receiver isn't crazy loud, however, it sounds okay. The bypass capacitor on Pin 2 filters hash noise and *can* remove some of the high frequency din from off frequency stations. Experiment to find the best value for your ears; even 0.015 uF might be your preference. I chose a 0.047 uF for my final version.

The 2 uF coupling caps between the power amp and Q3 can be lowered or raised to suit your parts collection. All the audio path coupling or bypass capacitors were "polysomething" types in my bread boards.

This is a base station receiver since the quiescent current draw listening to noise = 37 mA.

For low parts count or beginner's receivers, IC audio power amps make sense; 1 chip and you're done. Consider, for example, the TDA7052 — 2 bridged amplifiers supply reasonable power and headroom in an 8 pin DIP package. A good, but imperfect part. Depending on your goals and abilities, the limitations of the 7052's fixed 40 dB gain and/or the inability to drive grounded loads or insert additional feedback networks may constrain your designs.

Sound Bytes on 40 Meters:

I recorded these sound bytes prior to adding a 0.047 uF bypass capacitor to pin 2 of the 7052 chip and increasing the coupling cap on Q2 from 0.22 to 0.47 uF.

For a control — An ICOM superheterodyne receiver with digital IF filtering set to wide (2.2 KHz) was recorded immediately after recording the Pop DC2 receiver (although I pressed the middle (900 Hz) and narrow (600 Hz) filter selection briefly, but they made the noise worse), The antenna is a 1/4 wave vertical in a city lot with noisy conditions. I don't believe in artificially making my stuff sound better than real, and present warts-and-all audio files. I compressed these files heavily so you'll hear the noise phase shifting a little. Normally with this antenna, a "quiet" QRN level is S9; it doesn't bother me. Icom

Pop DC2 — I was tuning through a pile up to hear how the receiver copes with all the signals (twice as many with a DC receiver!)

Pop DC2 — More QRN, QSB and pile ups.

SSB - After this, I changed the .22 coupling cap between Q2 and the R-C filter .47 uF to add a little more bottom end.



Above — Speaker terminal (an RCA jack isolated from ground on the TDA7052 version). Volume pot at right.

Second Preamplifier Stage with LM386 final


12.22v
To pre-amp DC supply
1K
22 uF
150
.1
10
470 uF
11.47v
100 uF
-470 uF
Pop DC2
6K8
1K2
6.0v
2.2 uF
22 uF
4.31v
Q3
10K
3
4
6
1000 uF
5
LM386
.015
10
8
2K0
2.24v
Q4
Volume
2
1
1K
.1
10 uF
To low-pass filter
2.2 uF
2K2
1.53v
22 uF
390
Q3 = Q4 = 2N3904
22
LM386 Version
3.91 mA

Above — The 2nd preamp and final with an LM386 set for just under a gain of 50. Click for a Canadian SSB sound byte.

Alternate Final Amp Stage that connects to the Q3 volume potentiometer


To DC Supply for Q3-Q4
100 uF
180
470 uF
220
100 uF
.1
12.22v
7K5
1K2
33K
820
470 pF
BD139
8.12v
1N4148
22 uF
1.32v
1 Ω
1 Ω
2.2 uF
1N4148
1000 uF
10K
2.2 uF
4.24v
5.22v
Q5
BD140
6.80v
8 Ω
Volume
4K7
680
22 uF
3.57v
12K
7.40v
47
0.74v
Q6
Pop DC2
5.28 mA
2K2
.001
22
Maxim Ozerov Version
Максим Озеров
~30 mA Quiescent Current
Q5 = Q6 = 2N4401
3.78 mA

Above — A reader called Maxim Ozerov requested a discrete semiconductor version of the power amp after I posted the 7052 version on my blog. Placing 2 voltage amps inside the negative feedback loop proved challenging, since I'm no expert and learn on the bench. The gain = ~42 and the maximum pure sine wave power before clipping begins to occur = ~625 mW. This amp is louder and sounds warmer than the 7052 version.

2N3904s work fine for Q5 and Q6, but I found that the 2N4401 had a consistently higher DC beta and this helps ensure the bias and collector resistors shown will provide the widest possible, pure AC signal swing.

This amp replaces the earlier IC power amps (connects to 10K volume pot after Q2, however a 2.2 uF coupling cap is required after the volume potentiometer). If you need more **voltage** gain, increase the value of the 12K negative feedback resistor. Above 75K, the gain will approach 50 and *greatly* increase the possibility of distortion.

My dummy load for development and testing = three 1/2 watt resistors in parallel: 75, 82 and 10 ohms.

Certainly you can craft better - louder - quieter audio stages with low noise op-amps, however, my readers write that they enjoy building up discrete transistor designs, and for popcorn receivers; I do too.

Sound bytes from November 1, 2011

40 Meters - QRN is lower tonight. Some audio from a lineout tape deck (no tone controls nor equalization). I have only 2 cassette tapes, This one is Russian language from 1983 - the 1 strong accented syllable generates good peaks for AF listening tests. Audio recorded from an 8 ohm, 18 cm (7 inch) speaker mounted in a wooden frame with no back. Speaker choice and cabinets are critical and often overlooked; again we may look to audiophiles for guidance

Click for some 50 ohm AF preamplifier experiments cut from this page.

7 MHz VCO Experiments



As RF designers and builders, we rely on signal generators for nearly every experiment. I sought a reliable 7 MHz voltage controlled oscillator and built 1 after some effort. I'll describe and critique a VCO I rapidly designed for a reader and then present a better VCO with some design ideas.

7 MHz VCO Experiments: A rapidly developed Popcorn 7 MHz VCO

A reader needed a 7 MHz VCO in a hurry (3 hours); he only had 1 MVAM109 varactor and wanted to cover the bottom 60 KHz of the 40 Meter Ham band using a linear taper 10K potentiometer for tuning. He planned to use a dual-gate MOSFET cascode buffer (good choice), so I didn't have to bother with a buffer.



Freq (MHz)	7.000	7.066
DC volts	0.45	0
AC volts	3.44 pk-pk	4.0 pk-pk

Above — The VCO with a 100K resistor as the temporary buffer. He'll use a 100K resistor on G1 of the 2-gate MOSFET buffer. With a Q of 150 at 1 MHz; high noise level and a hyper-abrupt capacitance-versus-voltage curve designed for tuning AM radios, the MVAM109 varactor ranks poorly. The C of my MVAM109 with no reverse DC voltage was 725 pF.

Still, this VCO tuned in a linear fashion, showed a nice sinusoidal output and proved frequency stable. I wanted the AC voltage at the varactor anode at under 1 volt pk-pk (it was 752 mV) to help reduce forward conduction during the positive AC voltage swing. I was bad and ran the tuning DC voltage from 0 to 0.45 volts which greatly increases the potential for forward conduction in a varactor. To mitigate this somewhat, an 82 pF couples the varactor to the tank and drops the AC voltage and reactance seen by the varactor.

In VCOs on the web and print, you'll often see builders connect their varactor to a high Z, and high AC voltage point in the VFO tank; whoa!

At HF, if a varactor is forward biased by the positive half of the AC signal, varactor leakage current and voltage-source loading increases momentarily and lowers Q + broadens tuning. Further, serious harmonic energy and phase noise might be generated as the varactor is biased positive and negative alternately. You can sometimes see distortion in your scope during experiments with extreme AC voltage swings across the varactor. The varactor coupling capacitor should be as low as possible.

Balanced varactor tuning (anode to anode) provides another way to reduce AC signal effects at the cost of reduced maximum capacitance since the 2 varactors are in series. With back-to-back varactors, as the AC signal swings, the varactors are driven into high and low capacitance alternately, but the net capacitance remains constant. Thus applied reverse DC voltage sets the varactor capacitance rather than AC signal amplitude.

The reader for whom I made this impromptu circuit can lower the AC tank voltage by decreasing the VCC or increasing the 680 ohm source resistor after installing the buffer and tweaking things for a 7 dBm output voltage. This topology suffers from an amplitude versus frequency issue — at 7.0 MHz, the output = 3.44 volts pk-pk and at 7.066 MHz the output rises to 4.0 volts pk-pk.

Stuck with an MVAM109 constraint and 3 hours to design/build a VCO, I share this circuit as a raw experiment; not an example of good design because it is not. I took the signal off the gate to derive the best sine wave; this requires a lightly coupled, high impedance buffer with strong reverse isolation to prevent the pulling of the VCO frequency by downstream changes.

A lower L + higher C in the tank, and/or a higher Q varactor could turn this VCO into something reasonable. Popcorn versus high performance? You choose!

7 MHz VCO Experiments: A Suitable 7 MHz VCO

PART 1: Introduction

During my Fall 2011 VCO experiments I studied books including EMRFD and built versions of EMRFD Figures 4.33 and 4.34. Figure 4.33 is a common-base Colpitt's Oscillator using a hyperabrupt varactor. On Q1, the 33 ohm resistor in series with the 0.1 uF cap "de-Q" the 2N3904 to reduce UHF oscillations. Wes also employs current limiting with a 1K5 emitter resistor.

The temperature drift compensation circuit involving a temperature sensitive reference diode + op-amp fascinated me — astute temperature compensation design. I built and tested the whole circuit; the VCO has some amplitude versus frequency and phase noise issues, but it's okay for general use and *great* for varied environments. After tackling Figure 4.33, I built and tested the JFET Colpitts oscillator in Figure 4.34 and share my experiences developing this VCO with an alternate buffer.

These circuits are not cookie-cutter / carbon-copy: they show raw design ideas from the bench.

PART 2: The Voltage Controlled Oscillator


7 MHz VCO
November 16, 2011: Version B
12.22v
regulated
5v Reg
+
470 uF
.1
.1
100
temperature
compensation
1N5818
33 pF
C0G
100 pF
C0G
J310
100K
d
g
s
.001
C0G
10
turn
Tune
A
10K
100
100K
390 pF
C0G
To
buffer
.1
.001
C0G
2-10 pF
air
100K
470 pF
C0G
2K2
3K3
MV2105
6.1 - 6.4 uH
T50-6

Above — A JFET Colpitts VCO picked after after trying 5 different topologies. This VCO is my version of EMRFD Figure 4.34; originally designed by Wes, W7ZOI.

This JFET Colpitts oscillator exhibits a flat output versus frequency, low noise, scales easily to other frequencies and accomodates a wide variety of varactors. For example, you may scale it to other frequencies by changing the L and tweaking the "Colpitt's capacitors" up or down as needed.

I employed a small air variable trimmer capacitor to set the lower band edge and this meant experimenting with the inductor to find 1 that allowed me to set the band edge with such a small trimmer capacitor. I built 2 versions; in 1 the required L= 6.09 uH and in the other, L= 6.4 uH. It would be much easier to use a trimmer cap with a larger capacitance range as it makes chosing the inductor less exacting.

With the trimmer shown set to half its range, I started with a 6.6 uH coil and remove 1 turn at a time until the output in a counter was close to 7.00 MHz. After permanently fixing the inductor, I tweaked the trimmer cap so the lower band edge was 7.000 MHz with the chassis lid on.

To further drop phase noise, you could reduce the 33 pF coupling cap, add another pair of anti-parallel varactors, run a higher C to L ratio, or perhaps decrease the source resistor to increase the current limiting. Also low resistance, high Q, SMT varactors would help lower phase noise — SOD parts are tiny, but test your hand steadiness and vision.


Tuning Range
RIGOL T'D 1.20mV
7.00007MHz
Vpp(2)= 1.43V Freq(2)=6.993MHz Vpp(1)=*****
CH2 200mV Time 50.00ns 0.0000s
RIGOL T'D 1.20mV
7.10295MHz
Vpp(2)= 1.39V Freq(2)=7.092MHz Vpp(1)=*****
CH2 200mV Time 50.00ns 0.0000s
DC @ Point A = 3.0 volts
DC @ Point A = 12.21 volts

Above — When tuning from the minimum frequency and tuning voltage (7.0 MHz / 3.0 VDC) to the maximum tuning voltage and frequency (7.103 MHz / 12.21 VDC) the signal amplitude only changes 0.04 volts peak-peak.

I kept a minimum of 3.0 VDC on the varactors at the minumum frequency to provide reasonably linear tuning, keep the applied reverse voltage away from 0, and improve temperature stability. All were bench determined and are not factors you can generalize to all VCO circuits. Change the minimum DC voltage on your VCO control by adjusting the resistor on the grounded end of the pot; 3K3 in my case.

Click for a moderate resolution photograph of the VCO and buffer prior to adding the temperature compensation parts.

PART 3: The Buffer/Amplifer


12.22v
Version A
.1
22K
100
100
.1
.1
T1
10K
gain
L1
1K8
10K
2K2
.1
3K3
10.79v
50 Ω
Q2
2.45v
Q3
.1
S22 = -29 dB
.001
.1
1K
1.81v
150
.1
Q1
d
g
s
Sine wave from
-15 to 10 dBm
10 pF
C0G
1M
47
150
.1
12.1 mA
1N4148
0 to ~12 mA
L1 = 14t FT37-43
T1 = 10 BFT FT37-43
Q1 = J310
Q2 = 2N3904
Q3 = 2N4401
7 MHz VCO Buffer

Above — The Q1-Q2 hybrid-cascode amp gives strong reverse isolation (nearly 70 dB) and front panel gain control. You could also employ a dual gate MOSFET or JFET cascode with either fixed bias, front panel control, or a trimmer resistor to adjust the bias on Q2

I enjoyed designing the Q3 final amp amp and matching its input impedance to the output Z of Q2. One way to establish a fixed + known output impedance in order to to get a strong return loss without tuned circuits/networks is to feedback some signal from the collector to the base. The difficulty lies in finding how much negative feedback to apply, while still DC biasing the amplifier for good temperature stability. I set up a crude experiment to determine the Scattering Parameter S22. The goal is to set up a good Q3 output return loss using feedback + matching the Q3 input impedance by tweaking the inductor resistor across L1 and adjusting Q3's emitter degeneration.

The return loss in my first prototype without any attenuator pad = 29 dB; some of this was pure luck.


Tweaking Potentiometers
100
100
.1
.1
T1
L1
5K
10K
50 Ω
.1
3K3
.1
RETURN LOSS BRIDGE
F
7.050 MHz
Q2
Q3
.1
1K
D
150
.1
50 ohm terminated scope
d
g
s
Q1
1M
500
15
prevents 0 ohms

Above — Q2 and Q3 with 3 variable **orange colored** resistors in-situ and a Return-Loss bridge connected to the output. The potentiometers are tweaked while watching the detected output in an oscillocope. Adjust all the pots for the lowest peak-peak voltage and then carefully remove each pot and measure its resistance with an ohm meter. Replace all 3 pots with the nearest equivalent standard value resistor. Then measure and calculate the return loss (negative of S22). Watch the Q3 emitter resistance — too little R might bring distortion.


12.22v
.1
R
82K
100
100
.1
.1
T1
Version B
100K
gain
L1
1K5
5K6
2K2
100K
3K3
.1
50 Ω
.1
Q2
.1
Q3
S22 = -22 dB
.001
1K
150
.1
Sine wave from -15 to 10 dBm
d
Q1
g
s
10 pF
C0G
1M
47
150
.1
1N4148
L1 = 14t FT37-43
T1 = 10 BFT FT37-43
Q1 = J310
Q2 = 2N3904
Q3 = 2N4401
7 MHz VCO Buffer

Above — A seperate buffer built with 100% different parts that required different AC feedback plus shunt resistor across L1. The parts in this circuit weren't as hot as Version A, and the maximum output voltage was only 1.8 volts pk-pk. In order to get the AC output voltage to just above 2 volts, I had to tweak the resistor labelled **R**.

To keep the heat and current down in the final amp, I decided to keep the maximum clean output to 2 volts peak-peak (= 10 mW = 10 dBm) with an emitter current of ~ 12 mA. If you want higher clean output than 10 dBm, you'll have to run more Q3 emitter current and maybe choose a different BJT, plus apply a heat sink.

When cranked to maximum DC voltage, the Q2 gain pot allows a peak output AC voltage of ~2.2 volts pk-pk into 50 ohms and distortion is evident. At or below 2 volts pk-pk all is well — I'll use this VCO mostly from 0 to 7 dBm.

Since the circuits uses 2 BJTs and a JFET and many 5% tolerance resistors , the Q3 output will vary according to your parts. Tweak the resistor labelled **R** to provide a maximum AC signal just over 2 volts peak-peak into 50 ohms. This translates to around 3.8-5.5 volts DC bias for Q2 with your gain pot cranked fully clockwise.

Return loss variations. You probably noticed the return loss in Version B = 23 dB, while Version A = 29 dB.

Version B originally had the 1K8 shunt resistor across L1 and the 10K + 0.1 uF AC feedback arm just like version A and I measured a return loss of 22 dB. I stuck in 2 tweaking potentiometers (did not bother tweaking the the emitter series feedback element). After pot tweaking, the best return loss I could obtain with 5% tolerance resistors was 23 dB and this probably represents what the average builder will obtain. An S22 of - 22 to -23 dB works fine for the QRP work bench.

If you don't plan to do any potentiometer tweaking, I recommend building circuit A since it has a little more gain due to the slightly higher shunt resistor, and also I built 3 versions of Version A with an S22 of -22 dB or higher.

PART 4: Temperature Compensation

Before temperature compensation, my VCO slowly drifted down in frequency and was unusable.

If you look through the Ham Radio VFO/VCO literature, you will see that many builders use polystyrene caps as the Colpitt's capacitors, and/or in parallel with other NP0/C0G tuning capacitors. Negative temperature compensation caps like an N750, or the polystyrene types temperature compensated the oscillator. Negative temperature co-efficient caps are hard to obtain for many builders; especially in small quantities, however, they are worth their weight in gold.

Diode Compensation

Stabilize your VCO as much as possible with compensating capacitors and by following prudent temperature stability techniques before adding diode compensation. *See the VFO 2011 web page and EMRFD.* Temperature compensation is best performed in a homebrew oven (see EMRFD) and normally takes an incredible amount of time and patience.

Temperature compensating diodes are far from static — a diodes temperature co-efficient is dynamic and may vary with current and also unfortunately, with temperature and even while tuning your VCO !



Above — Simplistic diode temperature compensensation schemes.

The late, great, Doug DeMaw advocated sticking a 2N3904 or 2N2222a (wired as a diode) between the control potentiometer and the varactor decoupling network since the forward biased P-N junction exhibits a negative temperature co-efficient and should stop the decrease in frequency. It can help, however, as you tune and swing the control DC voltage from minimum to maximum the forward bias on the diode increases and the diode temperature coefficient decreases.

I've never had success using a transistor in this way; the BJT caused the VCO frequency to increase in an erratic manner that varied along with the DC control voltage. When watching drift in a frequency counter set to sample every second or so, a stable design will slowly change frequency in 1 or occasionallly 2 Hertz increments — some people call this "linear drift". if you see your VCO dropping down frequency in 10 - 20 Hertz jumps per second, you'll have a bad time temperature compensating.

I experimented with the above 3 designs that keep a constant current on the diode. Figures A and B work. I tried both and confirmed that a given diode compensated slightly differently when in circuit A or B. This gives you a bit of a tweaking room for your chosen compensation diode. I tried Figure C, but it had too much negative temperature coefficient and sent the VCO drifting upward about 1-2 Hertz each second.

I settled on circuit A and then tried some diodes: the initial best was a grubby old Germanium from my junk box. The best choice turned out to be a Schottky barrier rectifier (1N5818). I connected the VCO to a receiver and could listen to CW QSOs without groaning. My VCO now drifted up in linear, 1 Hertz hops at about 105 Hz per hour. It took a long time to tack solder in and wait 10 or 15 minutes for each diode to stablize before I finally settled on the 1N5818.

The better solution is to choose a suitable diode and vary its current to tweak the temperature compensation. Wes did this in EMRFD Figure 4.33.

Advanced designs may use a reference voltage + a temperature dependent voltage that is applied to op-amps in a proportional way to temperature compensate the DC control voltage. Then, too, some builders ovenize their VCO container to maintain a very stable environmental temperature.


7 MHz VCO
November 19, 2011
Version C
12.22v
regulated
5v Reg
470 uF
.1
.1
100
1K2
1N5818
x2
1K
temperature
compensation
33 pF
C0G
100 pF
C0G
J310
d
g
s
.001
C0G
100K
10
turn
Tune
A
100
100K
10K
.1
.001
C0G
3K3
MV2105
2-10 pF
air
6.1 - 6.4 uH
T50-6
100K
390 pF
C0G
470 pF
C0G
2K2
To
buffer

Above — A simple and elegant diode compensation scheme proposed by Ken Kuhn. Basically, it lets you tweak the degree of compensation to what is really needed rather than accept what you get from a diode. Adding more diodes will increase the effect — but the 1.2 K resistor should be increased accordingly to roughly match the overall voltage drop of the diodes. Hopefully there is a point on the 1K potentiometer where temperature compensation can be very good at a tuning point of interest. The diodes should be located to thermally match the rest of the oscillator circuitry.

Set the band edge *after* finding the sweet spot on the 1K potentiometer since it will affect the tuning frequency. This experimental circuit cannot be casually copied and it took a while to converge to the desired operating point on the 1K potentiometer. Generally you start with the 1K pot towards the 1.2 K resistor and then adjust for the best stability after warm-up. Then repeat and adjust as necessary over time.

Temperature compensatiing an oscillator like this is a challenge as all parts have some temperature drift and it takes a lot of measurements (and often, some dumb luck) to determine the overall compensation curve that is needed.

My 1 hour drift up in frequency is now ~ 60 Hertz per hour at various tuning frequencies across the tuning range. I stuck with the 1N5818 diode, and probably should have tried other diodes and also changed the 1K2 resistor to observe any effects, however, I have spent an inordinate amount of time on this circuit and leave it to others, or future bench work to improve. *See QRP — Posdata below.*

7 MHZ VCO
GAIN
TUNE
G

Above — Version C of the VCO. When I built the first versions, I drilled a hole to accomodate a third potentiometer, but filled it with a LED holder that was temperature sealed with epoxy glue. The 1K pot *jus*t fit into my chassis.

QRP— Posdata for January 2012

In late 2011, I shopped on eBay to build up a small quantity of 10 - 270 pF polystyrene, plus some 56 pF N750 ceramic temperature compensation capacitors. After 2 simple, but time-consuming experiments, I temperature stablized my 7 MHz VCO frequency drift to under 10 Hz per hour in the relatively constant temperature of our basement.

I didn't feel like re-doing the whole resonator circuit and thus focused on the tank to FET coupling capacitor. Placing a N750 capacitor in parallel with a fixed NP0/C0G cap to make 100 pF resulted in over-compensation and no amount of tweaking on the "adjustable diode" circuit worked. A few hours late, I swapped in a 100 pF polystyrene capacitor and after further hours of waiting and tweaking, I nailed the frequency stability sought.

An oven provides the best way to temperature compensate, however, whether you choose the oven method, or the bench method like I did, great patience is required to see if a change to your TC circuitry works or not.


7 MHz VCO
12.22v
regulated
5v Reg
470 uF
.1
.1
1K2
1N5818 x2
1K
Temperature Compensation
Temperature Compensation
100
J310
33 pF
C0G
100 pF
polystyrene
.001
C0G
100K
10 turn
Tune
A
10K
100
100K
.1
.001
C0G
3K3
MV2105
2-10 pF
air
100K
390 pF
C0G
470 pF
C0G
2K2
To buffer
6.1 - 6.4 uH
T50-6
Tunes 6.99 – 7.104 MHz

Above — Final version of the 7 MHz VCO. I changed the 100 pF capacitor coupling the JFET to the resonator circuitry from C0G to polystyrene and slowly tweaked the 1K temperature compensation pot to find the point of convergence.


0 min
Freq
7,000,072.853
Hz
Gate
Ch 1
MEASURE
LIMITS
MATH
DISPLAY
Remote
Freq Ch 1
Freq Ch 2
Uppr &
Scale &
More Digits
HEWLETT PACKARD
53181A 225 MHz FREQUENCY COUNTER
32 min
7,000,069.295
63 min
7,000,071.148

Above — The ~1 hour drift after a 30 minute warmup period for the 7 MHz VCO. Love this.

TEMPCO
CAPS

Above — My new temperature compensation capacitor parts drawer. I'll keep an eye out for further bargain temperature compensation parts on eBay and at Ham Radio festivals.

Fearless Leader and Hero   Храбрый вождь и герой

Above — Professor Vasily Ivanenko ( ), fearless leader (ТЫ МОЙ ГЕРОЙ)

He's my hero because he's humble, fallible, well-intentioned and moral. Professor Ivanenko lives for learning — fame is filler — hollow and distracting. His current *ego* lags his voltage by 90 degrees. Is he part inductor / part human?



Miscellaneous Photos and circuits

Above — 3 types of adapters. A BNC male to SMA female, a BNC male to PL-259, and a BNC female to S0-239 allow the RF modules to be connected to a variety of equipment.

SPECTRUM ANALYZER CALIBRATOR
RF
RF
RF
GAIN
D
4
-10

Click


RF
50Ω
LO
7dBm

Double Tuned Receiver Band-pass Filter Design Center

This web page is for builders who own EMRFD. Assisted by 4 of the Ladpac programs from the EMRFD compact disk, and the information presented in EMRFD Chapter 3, I share some experiments building popcorn receiver band-pass filters. Prior to diving into this material, please read the help file ***Ladpac2008 Manual.pdf*** and a file on the EMRFD compact disk called The Double Tuned Circuit: An Experimenter's tutorial by Wes, W7ZOI.

Preface

Derived from experiments, my web content reflects the efforts of a lay-person, hobby-level designer — I make mistakes. I say this not to make excuses or avoid accountability, but to share the truth. My hope is that my experiments inform yours and we all improve over time. I correct reported mistakes and rely on your eyes to see them.

Arduous and requiring good math skills, filter design is out of reach for many builders. Software changes this and learning to apply computer programs in real-world situations is part of our hobby. This web page shares some bench experiences, plus my thoughts about using some programs written by Wes, W7ZOI. I present suggestions and examples based more on empiricism and from reading about band-pass filter design than scientific methodology.

From email regarding my VFO and RF Workbench pages, I have become aware that I've lead many builders to think that a perfect sine wave and a high return loss are "must have" bench outcomes. This is false. A clean sine wave proves useful for accurate measurement, but is not a *de rigueur* bench outcome. A desire for high return loss reflects my own personal *obsession*; in simple QRP rigs, this may represent folly. Please don't overestimate the importance of return loss from my bias; decide for yourself.

Part 1: Experiments with 2 coupled L-C tanks.

Goal: A 15 Meter band band-pass filter with an insertion loss < 4 dB and a return loss of >= 20 dB.

Software: Ladbuild08 and GPLA08.

The simplest band-pass filter is an L-C tank. To get a decent stop band we generally couple 2 or 3 tanks together with series capacitor(s). Other filter topologies were ignored. In Part 1, I just connected up a couple of tanks on the bench without the use of software. Some attempts at impedance matching via transformer links were also trialed.


15M Band-pass Filter

insertion loss less than 3 dB with steep skirts, but these filters only had a return loss of 10 - 12 dB!

Figure 1

Above — I built a 5 component filter for the base experiment. Inductors = 7 turns of #22 AWG on a T68-6; tapped at 2 turns from ground. The inductors turns were expanded or compressed until L= 300 nH. Tuning capacitors = large 15 to 300 pF air variable capacitors. Coupling capacitors trialed = 2 pF, 3.3 pF, 5 pF, and 7.5 pF.

After soldering in a coupling capacitor, each tank (also called resonator) was tuned to resonance by looking at the peak-peak output voltage in a 50 ohm terminated oscilloscope. After tuning, I measured insertion and return loss and then swept each filter with a tracking generator + spectrum analyzer. On the bench I determined that the greatest return loss occurred with 2 transformer taps from ground; the result — a dismal 10-12 dB.

What effect does changing the coupling capacitor have?


2 pF coupling capacitor

Above — A spectrum analyzer + tracking generator sweep of the filter response with a 2 pF coupling capacitor between the inductors. Graticules = 2 MHz per horizontal division and 10 dB per vertical division. Click on this zoom to better see the - 3 dB bandwidth. The sweep revealed a sharp peak response with steep skirts and a 3 dB down BW of ~220 KHz or so. Some of the noise arose from the big air variable caps connected to each tank with short hook up wires, plus no shielding.



Above — The SA + TG sweep with a 3.3 pF coupling capacitor. The peak isn't as sharp, but still looks good. As shown, increasing the coupling capacitor value increases the 3 dB filter bandwidth with all other components equal.



Above — With a 5 pF coupling capacitor, a double humped response appeared. The bandwidth further increases.



Above — A zoom of the double humped filter response employing a 7.5 pF coupling capacitor. Imagine the difficulty tuning this band-pass filter in a receiver by listening to band noise. Tuning in either peak skews the filter bandwidth. Additionally, the 3dB bandwidth now = ~ 1.6 MHz — Not a good filter!

Optimizing Return Loss

Despite trying, I could not obtain a better return loss than 10 -12 dB by changing the tap point on the 7 turn inductors. In part this was due to limited potential autotransformer ratios on a 7 turn coil. I emailed Wes, W7ZOI and he sent this file. I learned that adding a series capacitor to each end will tune the filter to 50 ohms impedance. What capacitor value should we use?

The answer can be found purely experimentally, or with Ladbuild08 to make a digital file of your filter and GPLA08 to analyze it.


Click anywhere to begin. Select part # with Mouse.

Marker N 8

R Load = 50.00

Nominal Crystal Values (equal for all crystals)

Fx, MHz = 10.000

Lm, H = 0.020000

Qx = 100000.0

C-par, pF = 3.000

Inductor Q 250.00

f begin 0.000

f end 30.000

f step (not used in GPLA-08) 0.1

Place Cursor in drawing, click, then select part from those below.

R Source = 50.00

Value = 0.000

Part = rlb

Connection = ser

About Ladbuild
Global Parameters
Default File
Load
RL
RS
RLB
300.00
3.30
165.00
22.00
165.00
300.00
22.00
(cropped)
C
L
R
RLB
Xtal
Exchange Ser/Par
Convert Part to Duplicate
Add "Wire" at Load End
Add "Wire" after N
Remove Part N
LadBuild08 2nov08 w7zoi

Above — I "built up" my Figure 1 filter in Ladbuild08 with a 3.3 pF coupling capacitor. Initially I guessed at the values for the series end capacitors and knew my tuning capacitor were ~ 165 pF because I removed and measured them from the peaked filter from Figure 1 and added a few pF for stray capacitance. Any of these values can be changed in GPLA, so educated guessing is okay.

For size 50 to 68 toroidal inductors, many builders choose a Qu value from 200 - 250 with # 6 material. Qu affects insertion loss and to some extent, return loss. Click for a tutorial from Wes', W7ZOI site and consult EMRFD for more information.
In order for GPLA08 to display an S11 plot (return loss), a return loss bridge (RLB) must be added as shown. Also check the **Plot S11** check box in GPLA08.


Click to Review Circuit
S21 =
S11 =
S21 Ref.
top
0.
dB
lot
.00
B/div.
tom
.0
Enter #
Enter New Valu
Click to load new value
rt
Frequency
MHz
Freq./div stop
lace Cursor
Cursor Data =====>
MHz
dB
dB

#, part, connection, value:
0 Load R = 50.0
1 cap ser 22.0000
2 ind par 300.0000
3 cap par 165.0000
4 cap ser 3.3000
5 cap par 165.0000
6 ind par 300.0000
7 cap ser 22.0000
8 rlb ser 0.0000
98 Source R = 50.0
99 Inductor Q = 250.0

Enter # 1
Enter New Valu 22

start 18 MHz, Freq./div 10, stop 25, startfile.cir

Cursor Data: 21.060 MHz, S21= -2.02 dB, S11= -24.38 dB

Above — The GPLA 08 filter simulation of the filter "built" with Ladbuild08 above.


File
About GPLA
Click to Review Circuit
S21 =
S11 =
S21 Ref.
top
0.
dB
Plot
dB/div.
bottom
Enter #
Enter New Valu
Click to load new value
start
Frequency
MHz
Freq./div stop
Place Cursor
Cursor Data =====>
MHz
dB
dB

#, part, connection, value:
0 Load R = 50.0
1 cap ser 23.0000
2 ind par 300.0000
3 cap par 165.0000
4 cap ser 3.3000
5 ind par 300.0000
6 cap par 165.0000
7 cap ser 23.0000
8 rlb ser 0.0000
98 Source R = 50.0
99 Inductor Q = 250.0

dB/div. 10.00, bottom -60.0

Enter # 1
Enter New Valu 23

start 18 MHz, Freq./div 10.00, stop 25, C:\Users\Tyko\Todds\QRPHB\QRPHB\20

Cursor Data: 21.06 MHz, S21= -2.00 dB, S11= -31.72 dB

Above — In this filter simulation, I tweaked the end capacitors (parts #1 and #7) from 22 to 23 pF and watched the return loss (S11) improve by 7.34 dB — if wanted, you can optimize the end capacitor values to improve the match into 50 ohms. To re-establish the center frequency, slight retuning of parallel capacitors #3 and 6 is required when changing the series end capacitors; although I specifically didn't change them for this example.

Increasing the 2 end capacitors to increase S11 renders an option only; you don't have to go for the best S11 in your filters. Increasing the series end capacitors to bump up return loss tends to increase the 3 dB bandwidth and reduce insertion loss.



Above — I built and measured the filter with 22 pF end capacitors since these are common, standard values. In another experiment, a 1 pF cap was soldered in parallel with each series capacitor and the return loss increased by about 4 dB. Click for a bench photo of an alternate version of the above filter. Clearly, GPLA08 simulation furnishes us popcorn builders with a starting point to make top-notch band-pass filters.

Click for another simulation of a filter employing a 2 pF coupling capacitor, with the end capacitors tweaked for the best S11. *S-11 is just the negative of the return loss.* I would certainly use this filter in the front end of a popcorn direct conversion receiver.

An easier way to design your band-pass filters involves using DTC08 to design a raw filter and GPLA08 to substitute in standard value capacitors and tweak your filter. That's part 2. The material presented in this section supports the discussion in Part 2 and 3.

Part 2: Band-pass Filter Design using DTC08

Prior to using these Ladpac programs, some numbered design points and a preamble follow.

More than anything else, our parts collection dictates what filter parameters we choose and end up with. For example, if you want filters with a low bandwidth such as 150 KHz and under, you'll require inductors and capacitors that provide really high Q, or you might suffer from punishing insertion loss.

The following are general starting points only — *your* needs, parts and abilities drive *your* filter design. Example variances include: if a low noise amplifier follows a filter, a higher insertion loss might be okay; a high return loss is not always required for a low noise figure; especially in popcorn receivers. Also, it's a viable choice to trade off insertion loss for steep skirts in some filters.

1. A reasonable 3 dB bandwidth = 100 to 500 KHz, but this depends on the purpose of the filter.
Numerous considerations challenge us. Will this be a whole band (CW + SSB) filter, or a CW only filter? As a CW op who uses simple equipment, I tend to design moderate bandwidth (200-300 KHz) CW-only filters. If you need CW + SSB, then a bandwidth of 350 KHz or greater might suit you. It's really up to you.

Other factors affecting bandwidth choice include whether the filter drives a superheterodyne or a direct conversion receiver. In superheterodyne receivers, your intermediate frequency informs your filter bandwidth choice. Consider the following 2 diagrams:


Click to Review Circuit
S21 =
S11 =
S21 Ref.
top
0.0
dB
Plot
dB/div.
bottom
CF
Frequency
Freq./div
Place Cursor

#, part, connection, value:

0 Load R = 50.0
1 cap ser 19.0000
2 ind par 1000.0000
3 cap par 107.7000
4 cap ser 1.5015
5 cap par 107.7000
6 ind par 1000.0000
7 cap ser 19.0000
8 rlb ser 0.0000
98 Source R = 50.0
99 Inductor Q = 250.0

- 3dB BW = 242 KHz

Enter # 5
Enter New Value 107.7
Click to load new value

10.00 dB/div.
bottom -60.0
start 12.89 MHz 0.23 Freq./div stop 15.22
C:\Users\Tyko\Todds\QRPHB\QRPHB\20

Cursor Data =====> 14.060 MHz S21= -2.91 dB S11= -39.70 dB

Above — Using DTC08 and GPLA08, I designed an example filter for the front end of a 14 MHz superheterodyne receiver with an 11 MHz IF. BW = 242 KHz. CF = 14.060 MHz; a frequency some QRP operators favor.


Click to Review Circuit
S21 =
S11 =
S21 Ref.
top
0.0
Image
dB
Plot
dB/div.
bottom
CF
Frequency
Freq./div
Place Cursor

#, part, connection, value:

0 Load R = 50.0
1 cap ser 19.0000
2 ind par 1000.0000
3 cap par 107.7000
4 cap ser 1.5015
5 cap par 107.7000
6 ind par 1000.0000
7 cap ser 19.0000
8 rlb ser 0.0000
98 Source R = 50.0
99 Inductor Q = 250.0

Enter # 5
Enter New Value 107.7
Click to load new value

10.00 dB/div.
bottom -60.0
start 7 MHz 1 Freq./div stop 18
C:\Users\Tyko\Todds\QRPHB\QRPHB\20

Cursor Data =====> 8 MHz S21= -88.42 dB S11= 0.00 dB

CF = 14.060 MHz
IF = 11 MHz, LO = 3 MHz
Image = 11 - 3 = 8 MHz

Assessing Image Frequency Attenuation

Above — Assessing filter attenuation at the image frequency using GPLA08. *To keep the arithmetic simple, I employed a frequency of 14 MHz for the image frequency calculation.* As shown, the simulated attenuation of my 8 MHz image frequency is 88.42 dB. Since I personally target an image frequency suppression of 60-70 dB; at 88 dB, if I wanted, I could increase the bandwidth of this filter for broader coverage and reduced insertion loss.

How much image frequency rejection is needed for superheterodyne receivers? I'm uncertain, for I have seen competent authors choose between 50 and 100 dB. I feel a good target = 60 - 70 dB, and 50 dB is the bare minimum. To realize image attenuation above 50 dB, shielding is usually required.

Three or more L-C tank band-pass filters may be required when your image frequency is close to the IF frequency. Choose both your intermediate frequency and your bandwidth wisely.

2. After selecting your bandwidth, *tweak the inductance* and only if necessary, make minor adjustments to your set 3 dB bandwidth to give standard, or near-standard value coupling capacitors that you *own.* Obviously, you can place fixed capacitors in series or parallel, or even couple your resonators with a variable capacitor.

3. I favor size 50 to 80 powdered iron toroids with number 2, 6, or 10 material for a reasonably high Qu.

4. I aim for an insertion loss of of 3-4 dB; especially above the 40 Meter band; *consider the variances discussed earlier*

5. I aim for a return loss of at least 20 dB; *consider the variances discussed earlier*

6. If you can, measure your bread boarded filter bandwidth to confirm or improve the GLPA simulation. Insertion and return loss are easily measured — see EMRFD and the RF Workbench web pages on this site for methods.

I provide no graphic tutorial of DTC08; however, some work flow suggestions follow:

Open up DTC08, choose your center frequency, Qu, inductance and bandwidth and then press the **Calculate** button. Adjust the L until you get close to a standard value coupling capacitor from your parts bin. If required, you may also tweak the bandwidth value to get the needed coupling capacitor. It's wise to change the L before BW since changes in inductance don't cause too many complications within limits.

Name and save your filter to a specific file system directory or folder; or simply save it as the default file.

Open GPLA08 and load your recently saved filter file. Press the **Plot** button and then the **Click to Review Circuit** button. In some cases, you will have to type the CF in the *Cursor Data* text box and press **Plot** to set the cursor at your center frequency.

Change the coupling capacitor(s) to a standard value using the **Enter New Value** data entry controls.

Adjust the series end coupling capacitors to standard values. and if S11 is an issue for you, tweak them up and down while observing S11. Re-establish your center frequency by tweaking the parallel tank tuning capacitors and then re-plot to ensure the CF is lined up with the center of the plot.

In Part 3, I provide 3 filter design examples. Your own filter designs will be the most important examples to study.

Part 3: Band-pass Filter Examples

Example 1: An 80 Meter Band Filter



Above — Breadboard photograph of the 80M filter. This example filter may hit home for you — I like listening to CW at and below the 3560 KHz QRP calling frequency, however, another local Ham likes to talk on 75 meters SSB at or above 3790 KHz. This situation calls for a narrow band-pass filter. With my filter, the attenuation at 3790 KHz = ~ 24 dB; had I built a wide bandwidth filter, for example, 350 KHz BW; the attenuation at 3790 KHz, would only be ~4 dB. Perhaps a 3 resonator filter with even steeper skirts would be better?

I'll show the design process from start to test.


Design of Double Tuned Circuits -- 2008
File
About DTC--08
Exit
Calculate
Classic Form DTC
Ce
Cm
Ce
R0
Ln
Ct
Ct
Ln
R0
Save as Default File
+
-

Enter or Edit the following data. Then click on "Calculate"

Frequency, MHz 3.56

Bandwidth, MHz 0.1

Filter Termination R0 Both Ends Equal 50

Inductance, nH 3970

Inductor Q 225

Ce = 83.68

Cm = 9.9996

Ct = 409.76

Bandwidth % 5

mdtc08d 21Oct08 w7zoi

(altered screen capture)

Above — The basic DTC08 data entry fields were populated. I chose a 100 KHz bandwidth and tried different L values until Cm = 10 pF, since I have a whole drawer of 10 pF capacitors. I believed my Inductor Q would be at least 225 and wound 25 turns of #22 AWG on a T68-2 toroid and expanded or contracted the windings until I measured 3970 nanohenries. In reality, we should measure the inductor Q and in future I will, however, my sense is that few builders do.


S21 =
S11 =
S21 Ref.
top
dB
Plot
dB/div.
bottom
Click to Review Circuit
Click to load new value
Place Cursor
Frequency
Freq./div
stop
start

top 0.0

10.00 dB/div.

bottom -60.0

#, part, connection, value:

0 Load R = 50.0
1 cap ser 97.0000
2 ind par 3970.0000
3 cap par 397.2500
4 cap ser 10.0000
5 cap par 397.2500
6 ind par 3970.0000
7 cap ser 97.0000
8 rlb ser 0.0000
98 Source R = 50.0
99 Inductor Q = 225.0

3 dB BW = 124 KHz

Enter # 3

Enter New Value 397.25

start 2.9 Frequency MHz .1 Freq./div stop 4.3 C:\Users\Tyko\Todds\QRPHB\QRPHB\20

Cursor Data =====>: 3.560 MHz S21= -1.93 dB S11= -37.23 dB

Above — After saving my filter, I opened it up in GPLA08 as above. I replaced #4 with a standard 10.0 pF value, and started tweaking the end caps; parts #1 and #7 to gain a better S11 per my obsession with return loss. Retuning #3 and #7 re-establishes the center frequency and allows the S21 and S11 values to be interpreted. I settled on this filter and headed for the bench.



Above — Schematic and analysis of the breadboard. Click for another photograph. In reality, I bench determined the exact capacitance needed to tune each tank at 3.56 MHz with 2 large air variable capacitors that I removed and measured after peaking the filter. For each tank, I try to get just below this value with fixed value capacitors and add a small (2.5 - 22 pF, or so) air variable trimmer capacitor for peaking.

You need to test with capacitance under and over that required to ensure you properly tuned each L-C tank to resonance. Your parts collection, stray capacitance, mistakes or inductance variations in the toroids necessitate custom tuning of your tanks on the bench. I give capacitance values that should work, but it's up to you to ensure resonance of each tank. I find narrow BW filters require a steady hand to tune.

After peaking the tank in your oscilloscope, record the peak-to-peak voltage. Remove the filter and connect your signal generator to your scope with an RF barrel connector and again record the peak to peak voltage. The difference between the 2 is your insertion loss. You can calculate IL with Applet H on this page . Next, perform return loss measurements. If you can, determine the true 3 dB bandwidth of your filter by sweeping it with SA plus a generator. My filter 3 dB BW = 124 KHz.

Example 2: 20 Meter Band Superheterodyne Receiver Filter

A fictitious builder wants a superheterodyne receiver that covers 14.0 - 14.350. His IF = 2 MHz. The local oscillator = 12 MHz. The image frequency = (12 - 2) = 10 MHz. He centers his filter at 14.020 MHz. In this simulation-only example, we'll go from 1 resonator to 3.



Above — A single resonator with series matching capacitors "built up" in Ladbuild08.


S21 =
S11 =
S21 Ref.
top
0.0
dB
Plot
dB/div.
bottom
start
Frequency
Freq./div stop
Place Cursor
Cursor Data =====>
Click to load new value

#, part, connection, value:

0 Load R = 50.0
1 cap ser 18.0000
2 ind par 1000.0000
3 cap par 86.2000
4 cap ser 18.0000
5 rlb ser 0.0000
98 Source R = 50.0
99 Inductor Q = 200.0

3 dB BW = 417 KHz

Enter #: 3
Enter New Value: 86.2

dB/div.: 10.00
bottom: -60.0
start: 10 MHz
Freq./div: 1
stop: 19
C:\Users\Tyko\Todds\QRPHB\QRPHB\20

Cursor Data =====> 14.420 MHz
S21= -1.65 dB
S11= -15.02 dB

Above — The GPLA08 plot of the single tank filter. The bandwidth = 417 KHz. Increasing the end capacitors to 22 pF to try to increase return loss increases the 3 dB bandwidth [as shown here](), so we better stick with the original design.
In GPLA simulations with a perfectly centered filter, S21 = the insertion loss and S11 is negative of the return loss.


Click to Review Circuit
S21 =
S11 =
S21 Ref.
top
0.0
Image
dB
Plot
dB/div.
bottom
start
Frequency
Freq./div stop
Place Cursor
Cursor Data =====>
Click to load new value

#, part, connection, value:

0 Load R = 50.0
1 cap ser 18.0000
2 ind par 1000.0000
3 cap par 86.2000
4 cap ser 18.0000
5 rlb ser 0.0000
98 Source R = 50.0
99 Inductor Q = 200.0

Enter #: 3
Enter New Value: 86.2

dB/div.: 10.00
bottom: -60.0
start: 9 MHz
Freq./div: 1
stop: 19
C:\Users\Tyko\Todds\QRPHB\QRPHB\20

Cursor Data =====> 10 MHz
S21= -36.22 dB
S11= -0.00 dB

Above — Assessing image frequency attenuation in GPLA08; this sucks — only 36.2 dB down. We need to add a tank.


File
About DTC--08
Classic Form DTC
Calculate
Save as Default File
Ce
Cm
Ce
R0
Ln
Ct
Ct
Ln
R0

Enter or Edit the following data. Then click on "Calculate"

Frequency, MHz 14

Bandwidth, MHz 0.35

Filter Termination R0 Both Ends Equal 50

Inductance, nH 1150

Inductor Q 200

Ce = 18.06

Cm = 1.9866

Ct = 92.34

Above — Building up a filter in DTC08, I increased the L from 1000 to 1150 nH to give a Cm near to a standard value.


S21 =
S11 =
S21 Ref.
dB
Plot
dB/div.
Click to Review Circuit
Click to load new value
Place Cursor
Frequency
Freq./div stop
dB
dB

top 0.

10.00 dB/div.

bottom -60.0

#, part, connection, value:

```
0  Load R = 50.0
1  cap  ser  18.0000
2  ind  par  1150.0000
3  cap  par  92.4000
4  cap  ser  2.0000
5  cap  par  92.4000
6  ind  par  1150.0000
7  cap  ser  18.0000
8  rlb  ser  0.0000
98  Source R = 50.0
99  Inductor Q = 200.0
```

Enter # 3

Enter New Value 92.4

start 10 MHz 1 Freq./div stop 19

C:\Users\Tyko\Todds\QRPHB\QRPHB\20

Cursor Data =====> 14.020 MHz S21= -2.89 dB S11= -10.87 dB

Above — The GPLA08 plot of the double tuned filter. I set #4 to 2 pF and #1 and #7 to 18 pF (nearest standard values). #3 and #5 were slightly tweaked to center the filter. The simulated IL is only up 1.24 dB from the single resonator version. You are probably wondering why I didn't design the filter for a CF = 14.020 MHz in DTC08 above to keep consistency. I probably should have, but wanted to illustrate the versatility of GPLA08 to center filters "on the fly".


Click to Review Circuit
S21 =
S11 =
S21 Ref.
dB
Plot
Place Cursor
Click to load new value

top 0.0

10.00 dB/div.

bottom -60.0

start 9 Frequency MHz 1 Freq./div stop 19

C:\Users\Tyko\Todds\QRPHB\QRPHB\20

Cursor Data =====> 10 MHz S21= -69.16 dB S11= -0.00 dB

#, part, connection, value:

```
0  Load R = 50.0
1  cap  ser  18.0000
2  ind  par  1150.0000
3  cap  par  92.4000
4  cap  ser  2.0000
5  cap  par  92.4000
6  ind  par  1150.0000
7  cap  ser  18.0000
8  rlb  ser  0.0000
98  Source R = 50.0
99  Inductor Q = 200.0
```

Enter # 3

Enter New Value 92.4

Above — Assessment of the 10 MHz image — now it's 69.2 dB down. Although this filter will work well for his particular receiver specifications, this fastidious builder wants even greater image attenuation and decides to add a third resonator!


Classic Form TTC
Calculate
Save As Default File
C_e
C_m
C_m
C_e
R_0
L_n
C_te
L_n
C_tm
C_te
L_n
R_0

Edit or Enter the Following Data. Then click on "Calculate."

Frequency, MHz = 14.020

Bandwidth, MHz = .35

Filter Termination R0 = 50

Both Ends Equal

Inductance, nH, = 1100

Inductor Qu = 200

Ce = 23.16

Cte = 92.16

Cm = 2.0680

Ctm = 113.02

Above — Building up a filter in TTC08, I chose an L of 1100 nH to give a Cm close to a standard value.


S21 =
S11 =
S21 Ref.
Click to Review Circuit
dB
Plot
Enter #
Enter New Value
Click to load new value
Place Cursor
rag a box on graph to Zoom
Zoom to Original Sweep
Save S21 as Ref.

#, part, connection, value:
0 Load R = 50.0
1 cap ser 23.1600
2 ind par 1100.0000
3 cap par 92.1600
4 cap ser 2.0680
5 ind par 1100.0000
6 cap par 113.0200
7 cap ser 2.0680
8 ind par 1100.0000
9 cap par 92.1600
10 cap ser 23.1600
11 rlb ser 0.0000
98 Source R = 50.0
99 Inductor Q = 200.0

top 0.
0.00 dB/div.
ottom 60.0
Enter # 1
Enter New Value 0
tart 12.27 Frequency MHz 0.35 Freq./div stop 15.77 C:\Users\Tyko\Todds\QRPHB\QRPHB\20
Cursor Data =====>: 14.020 MHz S21= -3.53 dB S11= -23.49 dB
☑ Plot S11 ☐ Plot Referenc

Above — The GPLA plot of the 3 tank filter. I performed no parts tweaking — it's up to you from here on in. The simulated IL remains quite reasonable.


S21 =
S11 =
S21 Ref.
Click to Review Circuit
dB
Plot
Enter #
Enter New Value
Click to load new value
Place Cursor

#, part, connection, value:
0 Load R = 50.0
1 cap ser 23.1600
2 ind par 1100.0000
3 cap par 92.1600
4 cap ser 2.0680
5 ind par 1100.0000
6 cap par 113.0200
7 cap ser 2.0680
8 ind par 1100.0000
9 cap par 92.1600
10 cap ser 23.1600
11 rlb ser 0.0000
98 Source R = 50.0
99 Inductor Q = 200.0

top 0.
10.00 dB/div.
bottom -60.0
Enter # 1
Enter New Value 0
start 9 Frequency MHz 1 Freq./div stop 18 C:\Users\Tyko\Todds\QRPHB\QRPHB\20
Cursor Data =====>: 10 MHz S21= -100.07 dB S11= -0.00 dB

Above — The GPLA08 assessment of the 10 MHz image frequency. Now 100 dB down!



Above — The 1 tank and 3 tank filters superimposed to show the skirt action. The 3 dB bandwidth is the same!

Example 3: A 20 Meter Band-pass Filter for a Builder from Argentina



Above — An Argentinean builder emailed that he wanted a band-pass filter optimized for 14.070-14.095 MHz RTTY but also usable for the CW sub-band and lower SSB frequencies. He wanted a center frequency in the RRTY sub-band and I chose 14.079 MHz. Tuning this filter to a center frequency as low as 7.030 MHz for CW should be possible with the variable capacitor value shown, but as mentioned, you really need to do this carefully on your bench. I employed T80-10 toroids and scrunched or expanded the 16 turns of # 22 AWG wire until they measured exactly 1000 nH.

The best return loss will only occur when your filter is perfectly tuned to the test frequency, so tune carefully.



Above — The schematic + bench analysis for the 20 Meter band double tuned band-pass filter. My original design called for 22 pF series end capacitors to get a decent return loss. After building and measuring the circuit, the results were disappointing: insertion loss = 3.7 dB and a return loss = 17 dB. I wanted a better S11 and IL, so I decreased the end capacitors to 20 pF and savored the measured data shown in the schematic.

Simulating this tweaked design in GPLA08 unveiled a lower return loss than the original design simulation with 22 pF end capacitors; exactly opposite to my bench observations.

Bench work reveals the truth — The filter *you* get is dependent on factors such as parts types + tolerances, stray reactance, layout, test gear and any bench errors. For example, I don't know the Qu of my 1 uH inductors, but suspect that the Qu is greater than the 250 specified. Also my intended - 3 dB bandwidth was 350 KHz, yet my filter = 315 KHz; in part, because I lowered the series end capacitors, but also due to other fore mentioned factors.

Many popcorn builders can't easily measure their filter bandwidth. Does it really matter? Probably not, however, the big realization for me is that unless you measure, you won't actually know your data like insertion loss, return loss, or bandwidth — simulations are great, but don't obliterate the need for bench testing as possible.

Consider this; with the SPICE program you can design a circuit with a 2N3904 and run 400 mA of current through it — the transistor won't smoke 1 bit ! Project outcomes depend on understanding and employing best practices, experience and measurement on the bench. Finding best practices proves difficult in a day and time when general scientific literacy, the number of expert mentors and interest in analog electronics are all waning.

Click for another photo of the filter. On my actual filter, I used high Q, air variable trimmer caps that only had a capacitance variation of 15 pF or so. I soldered in fixed capacitors to get close to the capacitance needed to tune each tank. If possible, I think its better use smaller value trimmer caps because they permit finer tuning. The air variable trimmer offers high Q plus you can see when the capacitor is fully meshed (maximum C). This signals that you need to add more fixed capacitance to that tank for peaking.

Conclusion

To repeat; our parts collection dictates our band-pass filter outcomes. Size 50 to 68 #6 material toroids will work fine for most HF frequencies above 3 MHz. Don't stress out too much if your insertion or return loss is a little higher than you wanted; in all likelihood your filter will work fine and you'll be glad you didn't just copy some else's design and rob yourself of the design experience.

I am hopeful, this web page will inspire a few builders to experiment with band-pass filters for their receivers and other applications. My sincere thanks to Wes, W7ZOI for his guidance with filter design.

QRP — Posdata for August 2012 — NE612 Mixer Band-pass Filters

I designed some band-pass filters for NE612 based front-ends with LadBuild and GPLA and show my 75 Meter band filter design figures below. I'm not a fan of employing an NE612 as a receiver mixer since it easily overloads and spews harmonics when mixing strong input signals. The 1K

'RF gain' pot found in many receivers, or the more conventional switchable attenuator pad prove essential when receiving 'booming' signals with a NE602/NE612 mixer in your front-end.

Still, for field-portable tranceivers/receivers, the NE612 mixer keeps the current and radio size down nicely.


File
About GPLA
S21 =
S11 =
S21 Ref.
Click to List Circuit
Drag a box on graph to Zoom
Zoom to Original Sweep
Save S21 as Ref.
Place Cursor
Reset Cursor
Click to load new value
Save as Default, Exit.
Up
Down
EXIT

General Purpose Ladder Analysis, 2012, Beta 0.4

gpla-12.4 28july12 w7zoi

#, part, connection, value:

0 Load R = 47.6
1 cap ser 180.0000
2 ind par 4700.0000
3 cap par 196.3721
4 cap ser 27.0000
5 cap par 360.2896
6 ind par 4700.0000
7 cap ser 82.0000
8 rlb ser 0.0000
98 Source R = 1500.0
99 Inductor Q = 150.0

3 dB BW:
364 KHz

top 0 dB
10.00 dB/div.
bottom -60.0 dB

Start Freq. 1.70
Frequency Units MHz
0.40 Freq./div
stop Freq 7

Part # 0
New Value 47.6

☑ Plot S11
☐ Plot Referenc

Frequency 3.688 MHz
S21= -0.89 dB
S11= -23.28 dB

Tune Part Value, Inductor Q, or Qx.
#= 5
%= 1
Value=

E:\Hobbyist\QRPHB notes\2012\HF\wee willy stuff\july30_classic.cir_classic.ci

Mouse Frequency 8.6077
S21 at F-mouse = -35.86 dB
S11 at F-mouse = -0.00 dB

Center Frequency 3.69 MHz in this simulation

75 Meter Band Filter

Above — My filter centered at 3.69 MHz. I set the 3 dB bandwidth higher than my usual 200-300 KHz so I could tune a good chunk of the 80-75M band without losing too much signal.

To establish some starting L and C values, I built a classic form filter in DTC08 with a 50 Ω input and output impedance centered at 3.69 MHz. After some tweaking, I settled on L = 4700 nH, Ce = 148 pF, coupling capacitor Cm = 27 pF and about 220 pF (Ct) to resonate each tank.

Next I changed the termination R's to 1500 Ω in DTC08 to simulate the right half of the filter matched into the 1K5 input impedance of an NE612. This gave me some Ct and Ce values to start with. I started Ladbuild 08 and built up a schematic.

In a seperate experiment, I determined that the resonator Qu of a 3.7 MHz L-C tank with an L of 4700 nH wound on a T50-2 core, was ~150.



Above — The completed schematic. My filter exhibits an attenuation of ~70 dB at the top of the AM radio broadcast band (1500 KHz) providing I shield it in an RF-tight box. I took the 47.6 Ω input Z from the 1K pot and my 50 Ω antenna in parallel. An input Z of 50 Ω would work just as well in simulation and on-bench.

In Part A, I show a possible way to resonate each tank with 1 fixed C and a trimmer capacitor. In Part B, I omitted this detail and just show the calculated C needed for resonance as a variable capacitance.

To make this filter with GPLA, I tweaked the capacitor values to nearest standard value parts and tuned the filter with the GPLA Tune Part Value controls while looking at the waveform and my 3 dB bandwidth. I love tweaking values in GPLA and over the years have designed several hundred RF filters for readers.
The rubber hits the road on the bench however! You can get an E.E. degree without melting solder in this day and time — but only bench measurements tell the truth.

Please tune each tank carefully like I mentioned earlier... For example, say a tank needs 180 pF for resonance, *but you don't know this*. You solder in a 100 pF cap and a 5-50 pF *enclosed* ceramic trimmer capacitor into the L-C tank. While watching the 'scope this tank will "peak" since the tank will exhibit its highest peak-peak voltage when the trimmer cap is set to 50 pF and fall off as you decrease the C of the trimmer. You might think you peaked the tank, however you' re actually under by 30 pF!

While leaving the trimmer set to maximum C (peak-peak voltage) in this theoretical example, if you tack solder in another 10 pF cap your 'scope will show an even greater pk-pk voltage. , If you remove this 10 pF cap and then place in a 27 pF cap, the pk-pk voltage will go even higher since you're almost at the target 180 pF. If you removed the 27 pF cap and tack soldered in a 47 pF cap, the pk-pk voltage in the 'scope will go down since your now at 197 pF. Thus you know that resonance is somewhere between 177 and 197 pF.

Of course you could decrease the trimmer cap C and stil use the 47 pF cap, however, my description isn't a prescription to follow, just some things to think about. Sometimes I remove a trimmer cap and measure it to ensure the cap is not set to maximum C; that would tell me I need to add more fixed capacitor(s) to the tank. Air variable trimmer caps give visual indication since maximum C occurs with maximum mesh. Unfortunately they are rare and expensive.

On my bench I keep a pair of small 12 to 400 pF air variable caps and temporarily solder them into my tanks. After peaking, I remove and measure them — then I have a good idea of what capacitance is needed to resonate the tank at my test frequency.

It's all an experiment.

Click for another low loss, well matched example: CF = 5.17 MHz, 3 dB BW = 196 KHz. 50 ohm version. NE612 final version.


612A
612A
1
2
1
2
INPUT
Figure 1
a. Single-Ended Tuned Input
b. Balanced Input (For Attenuation of Second-Order Products)

Above — NE612 input circuits. The NE612 datasheet specifies a 3 pF input capacitance + a 1K5 input resistance.

If you look around the Web, many builders just run a single tank for band-pass filtering. While okay for novelty-grade rigs, the poor filter stopband may unleash some ugly problems in the mixer and on down the receiver chain.


TANK 1
TANK 2
50 Ω
NE612
1
2
3
.1 µF

Above — A double tuned circuit with the L-C tanks named 1 and 2 and a series capacitor to match Tank 2 to the NE612.

Most builders match Tank 1 into its 50 Ω source with a capacitor divider, or a matching transformer. For Tank 2, some enthusiasts just connect the Tank 2 coil directly to pin 1 as shown in Figure 1a. Without the matching series capacitor, unfortunate side effects may arise...



Above — The low-pass skirt of a double-tuned filter may attenuate higher frequencies poorly when no series capacitor (or other network) matches Tank 2 to the NE612 input. I perfectly matched Tank 1 to its 50 Ω source just connected Tank 2 to a 1500 Ω resistive load in this simulation. I wonder how bad things get in the real world when a complex impedance is involved?



File
About GPLA
S21 =
S11 =
S21 Ref.
gpla-12.4 28july12 w7zoi
Click to List Circuit
#, part, connection, value:
20 M Band Filter
top
dB
dB/div.
bottom
dB
Frequency Units
Freq./div
Drag a box on graph to Zoom
Zoom to Original Sweep
Save S21 as Ref.
Plot Referenc
Place Cursor
Reset Cursor
Click to load new value

```
0  Load R = 50.0
1  cap  ser  15.0000
2  ind  par  1500.0000
3  cap  par  69.8000
4  cap  ser  1.0000
5  cap  par  82.0000
6  ind  par  1500.0000
7  cap  ser  3.3000
8  rlb  ser  0.0000
98  Source R = 1500.0
99  Inductor Q = 200.0
```

CF = 14.030 MHz

B/W = 245 KHz

top 0 dB

10.00 dB/div.

bottom -60.0 dB

Start Freq. 11

Frequency Units MHz

.5 Freq./div

stop Freq 18

Part # 5

New Value 82

☑ Plot S11

☐ Plot Referenc

Frequency 14.030 MHz

S21= -3.64 dB

S11= -29.74 dB

Above — I designed a filter for a 20 Meter band CW receiver centered at 14.030 MHz with DTC and GPLA. The design 3 dB bandwidth = 245 KHz. NE612 filter design was discussed in QRP — Posdata 1.

I then breadboarded the filter with T68-6 inductors, but common lower Qu ceramic trimmer capacitors.


20M Band Band-pass Filter
15 pF
1 pF
3.3 pF
A
50 Ω
1.5 uH
1K5
CV
CV
15 pF
CV = 6 - 70 pF
1 pF
15 pF
3.3 pF
50 Ω
1
NE612
1.5 uH
82 pF
B
69.8 pF
2
3
.1 μF

Above — The DTC/GPLA filter design with Tank 2 evolved to provide single-ended input for the NE612.

I wanted to test 2 questions:

1. Does the 0.1 μF coupling cap connected to the cold end of Tank 2 and Pin 2 change the bandwidth or filter skirt shape?
2. Will the 3.3 pF cap really match the NE612?

I expect that worldwide, the NE612 input impedance may vary slightly from part to part; different breadboards will exhibit different reactances and that although the datasheet specifies 1500 Ω , we may be dealing with a complex impedance that varies with the aforementioned factors plus perhaps, input frequency. I simply want a good filter with clean skirts.


A
Tracking
Generator
50 Ω
10 dB
15 pF
69.8 pF
1 pF
1.5 uH
3.3 pF
82 pF
1K5
FT37-43
16t : 3t
20 dB
Spectrum
Analyzer
B
Tracking
Generator
50 Ω
10 dB
15 pF
69.8 pF
1 pF
1.5 uH
3.3 pF
82 pF
1K5
.1 µF
FT37-43
16t : 3t
20 dB
Spectrum
Analyzer

Figure 2

Above — Experiment #1. I compared spectrum analysis of circuit A with B. I built and measured A and then cut away some copper to isolate the copper board grounding the Tank B parts. This "island" was AC coupled to the rest of the ground plane with a short leaded 0.1 µF ceramic capacitor.

I saw no significant difference between Circuit A and B — it appears the 0.1 µF capacitor does not affect the filter parameters to any extent.

To simulate a NE612, I soldered a 1K5 Ω 5% resistor across Tank 2. Tank 2 was transformer coupled to the 50 Ω Z required for spectrum analysis. A 20 dB pad ensured a strong return loss and a safe input amplitude for the SA.



Above — Spectrum analysis of Figure 2A or B. I saw flat topping of the waveform – almost double humping with a higher than wanted 3 dB bandwidth; this bothered me. Fixing this problem was Experiment #2.



Above — A zoom of the poor coupling of Figure 2A or B. From my experience building filters, I suspected a termination resistance mismatch in Tank 2 ; exactly what I was trying to avoid!


20M Band Band-pass Filter
50 Ω
15 pF
69.8 pF
1 pF
1.5 uH
2.5 - 10 pF
82 pF
0.1 µF
NE612
1
2
3

Above — I swapped a trimmer capacitor for the series 3.3 pF fixed cap in Tank 2. Then I reconnected the circuit into my test set up.



Above — A photo of my TG + SA measurement after tweaking the newly added trimmer capacitor and peaking each tank. I shifted the SA screen center over so the tracing could be seen without all the hash marks in the center. Wonderful.



Above — A zoom of the now matched Tank 2. Due to the bench-altered Tank 2 match, my low-Q variable capacitors and other factors, the 3 dB bandwidth now is just over 300 KHz.

I'm not sure if these experiments reflect what actually happens with a NE612 input band-pass filter, however, I plan to match my second tank with a series trimmer capacitor in future NE602/NE612 work. I also want to explore balanced input.

RF — Test and Measurement

RF Workbench Page 4

The 4th installment of a QRP/SWL HomeBuilder series exploring *basic* RF measurement

Part 4 describes a method to calculate reverse isolation in the **50 Ω environment** after converting measured peak-to-peak AC voltages to dBm. I tested 2 common amps at ~7 MHz to show the concepts and calculations.

In this series, I gratefully borrow from the work of Wes, W7ZOI per correspondence, direct contributions and from EMRFD.

Tools Needed

1. 50 Ω terminated scope (or a spectrum analyzer) and a 50 Ω signal generator
2. 50 Ω RF cables with RF connectors (such as short cables with female BNC connectors)
3. 6 dB 50 Ω attenuator pad; plus an adjustable attenuator if you use a fixed output signal generator.
4. BNC through-response connector(s)

Procedure

1. Measure the amplifier forward power gain. This is S21.
2. Measure amplifier reverse power gain. This is S12. Like S11, express S12 as a negative value.
3. Reverse isolation using dB values = S21 - S12.

Step 1 : Measure the forward power gain



Figure 1 shows how to measure forward gain in a 50 Ω environment — **1**. Convert the measured AC voltage to dBm, **2**. Disconnect the amplifier, insert a through-response connector and convert this measured AC voltage to dBm. The difference between the 2 values = S21. Applet H will do these calculations from the peak-peak voltages. *The attenuation pad following the signal generator in Figures 1 and 2 signify that the signal generators have a 50 ohm output impedance and is optional.*

Choose a signal generator level that ensures the output of your amplifier is linear while providing a good signal to noise ratio for measurement. With an oscilloscope, I generally test amplifiers with an input power of between 0 and -11 dBm; although choose whatever level that works for you consistent with linear amplification.

After measuring the forward gain of your amp, a good way to test for linearity is to add a fixed 6 dB pad between your signal generator and your amplifier to drop the applied signal by half. *[A 6dB pad drops the peak-peak voltage by 1/2 . A 3 dB pad drops the power in dBm by 1/2]*. The power gain should be equal or nearly equal to the measured dB value obtained before you added the 6 dB pad. If they vary significantly, you are likely driving the amp too hard and causing some non-linear output products. S21 = complex *linear* gain.

Step 2 : Measure the reverse power gain



Figure 2 shows how to measure reverse gain in a 50 Ω environment — **1**. Convert the measured AC voltage to dBm, **2**. Disconnect the amplifier, insert a through-response connector and convert this measured AC voltage to dBm. The difference = S12. Ensure that you employ the same drive level used to measure the forward gain.

Measuring reverse gain may be tough. When the amplifier under test requires a low drive level and/or has strong reverse isolation, you may not have enough signal to accurately measure with your oscilloscope. The tool of choice for low reverse voltage measurment is a spectrum analyzer (SA) — a narrow band SA may be required to distinguish the weak signal from random noise with low signal voltages.

Summary

A **practical** bench work flow goes something like:

1. Measure the through-response peak-peak voltage.
2. Measure and record the peak-peak AC voltage while driving the amplifier input port (forward gain set-up).
3. Reverse the amp so you're driving the output port and then measure the peak-peak AC voltage (reverse gain set-up).
4. Calculate S21 and S12.
5. Calculate reverse isolation.

Example 1: Feedback amplifier

In the first example, I measure the reverse isolation of a Beaverton Special feedback amp. The schematic is shown below. Tested with a 7.039 MHz signal generator possessing a return loss of 30 dB.


Example 1
12.22v
10 bifilar turns
FT37-43
51
.1
.1
1K5
50 Ω
1K5
.1
39
50 Ω
.1
1K
2N3866
150
- 6 dB
.1
75
4.7

50 ohm Voltage Measurements:


RIGOL
T'D
2 -4.00mV
T 7.03926MHz
2
Vpp(1)=*****
Freq(1)=*****
Vpp(2)= 188mV
CH2 40.5mV
Time 50.00ns
T→0.0000s

Above — AC voltage with a through-response connector in-situ: 188 mV pk-pk


RIGOL
T'D
2 -8.00mV
T 7.03926MHz
2
Vpp(1)=*****
Freq(1)=*****
Vpp(2)= 1.07V
CH2 200mV
Time 50.00ns
T→0.0000s

Above — AC voltage with forward gain set-up: 1.07 V pk-pk


RIGOL
T'D
2 0.00uV
T 7.04693MHz
2
Vpp(1)=*****
Freq(1)=*****
Vpp(2)=5.28mV
CH2 2.00mV
Time 50.00ns
T→0.0000s

Above — AC voltage with reverse gain set-up: 5.28 mV pk-pk.

S21 = 15.1 dB. S12 = -31 dB. I tested my driven amp's linearity by adding a scrap, standard value 6 dB pad in between the signal generator and the amplifier — the S21 was 15.2 dB with the pad and 15.1 dB without the added 6 dB pad. It's linear.



Reverse Isolation Calculation

R.I. = S21 - S12
R.I. = 15.1 dB - -31.03 dB
R.I. = 46.13 dB

Example 2: Common Base Amplifier


Example 2
12.22v
75
.1
10 BFT FT37-43
15K
.1
2.24 uH
50 Ω
S11= -26.5 dB
50 Ω
372 nH
FT37-43
(940 pF)
.1
(173 pF)
S22 = -24.8 dB
.1
1K5
12t
.1
100
2N3904
Stage current = 4.28 mA

Above — A common base amp employing L- networks for a strong return loss in and out at 7.039 MHz. S11 and S22 = the negative of return loss.

Through connector voltage = 192 mV peak-peak.

S21 = (1.88 volts peak-peak AC voltage) = 19.82 dB.

S12 = (1.68 mV peak-peak AC voltage) = -41.16 dB.

Reverse isolation at 7.039 MHz = (S21 - S12) = 61.42 dB

I confirmed the linearity of my S21 using the aforementioned 6 dB attenuator pad — I couldn't increase my signal generator output level above the indicated -10.35 dBm, since gain compression emerged in the common base amplifier (reduced AC voltage was measured).

My reverse AC voltage was under 2 mV; about the threshold where my oscilloscope waveform becomes rather ugly and sits in the noise. Clearly, the limitations of measuring reverse isolation with an oscilloscope must be factored. Still, you got to love 60 dB + of reverse isolation in a popcorn circuit.

1 local professional EE told me if you can measure it with a 'scope, you don't have spectacular reverse isolation - no doubt, a spectrum analyzer

pumps up the measurement quality in circuits with high reverse isolation, but more amateur designers have 'scopes than spectrum analyzers, so just do your best.

Involving Scattering Parameters as possible on your workbench can only lead to circuit improvement. You can't better your outcomes if you can't or don't measure them — applying and more importantly, understanding test equipment is just 1 component of our hobby. A hobby unto itself; test equipment activity complements amateur radio design. I have met test equipment focused builders who make radio gear just as an excuse to apply their test gear!

Improved bench practices are the corollary of striving to learn more about measurement techniques and increasing our collection of measurement devices.

QRP — Posdata 1: Hycas Amplifier

I love the hybrid cascode (hycas) as a general purpose RF amplifier. What's not to love about a using a common source FET followed by a common base bipolar amp? I attempted to measure the reverse isolation of a version just using an oscilloscope.



Above — A hycas amp set up for high return loss on both ends at 14.078 MHz. Too much current may cause gain compression and harmonic distortion, so please test your hycas amps for both. I tested using a signal generator with a 30 dB return loss driving a 50 Ω terminated oscilloscope. Since the hycas amp contain a high impedance input JFET and a common base amp, the reverse isolation should be reasonably high, or at least as good as a common base amplifier.

My testing failed — The reverse isolation was too high to measure with an oscilloscope. Using proper bench techniques (linear amplification + honest scope reporting), I determined the highest reverse isolation I could measure = 64 dB. In fact, injecting a whopping signal of 1.08 volts peak-peak into the hycas output port only gave an S12 of 1.84 mV — whoa!

The problem is such a strong signal (1.08 volts peak-peak) at the input port results in severe limiting and distortion; so valid reverse isolation measurement isn't possible. Even a 350 mV peak-peak signal may give some gain compression during S21 measurement depending on your matching. Thus, I can only accurately say that the reverse isolation of my hycas amp is greater than 64 dB.

Strong reverse isolation is 1 reason I favor hycas amps as VFO buffers. They make pretty good I.F. amps also.

The hycas IF amp system by Wes, W7ZOI and Jeff, WA7MLH offers amazing performance and features an excellent JFET bias scheme. I built 1 in 2008 — amazing design.

QRP — Posdata 2: Doesn't S12 = Reverse Isolation?

Many web sites, books and people report that reverse isolation = S12, yet above, I depart from this argument. In truth, I think reverse isolation equals S12, but reverse isolation may also equal S21 - S12.

I'll let you decide what to do, but explain why I enjoy the latter.

S12 is a negative value.

I prefer to turn that negative value into a positive 1 — RF Workbench 4 concerns measuring and applying amplifiers with the goal of high reverse isolation and not just measuring S12.

The main purpose to quantify amplifer reverse isolation is to strive to *improve reverse isolation* and an amplifier is but 1 component in our 50 Ω block. I believe in a creative, systems approach; open minded and positive (pun intended).

The whole RF Workbench series attempts to present 50 Ω bench measurements in a vibrant way devoid of excessive + boring engineer-style content that could blank the eyes of the budding Hams/SWLs designers that visit my site. I imagine this web site bores more advanced RF designers *to tears*.

Our goal is to obtain high reverse isolation while applying a 50 Ω systems approach.

Break away from strict + "stodgy" math-driven methods to fuel creative thought and experimentation.

I posit that an appropriate figure of merit in a well designed isolation amplifier is the difference between S21 and S12; and therefore, the term reverse isolation can be more than just S12.

Ham/SWL component-level experimentation by commoners like me is ~~slowly~~ dying and being replaced by a new generation of skilled, code writing experimenters. Although, some builders just copy other people's code and then apply it to kitted hardware. Reverse isolation impacts both our analog and digital designs.

Please consider this example:

I'm switching a level 7 diode ring mixer with 12 MHz and per normal, create lots of internal harmonic energy. With my spectrum analyzer connected to the mixer RF port I measure my 12 MHz LO signal at 50 dB below a +7 dBm signal, or -43 dBm. That's a 50 over S9 signal — very high amplitude in context!

I require strong LO isolation in my circuit and thus stick in a 50 Ω input/output amplifier. I measure this amp: S21 = 15 dB and S12 = -31 dB.

So, the signal at the amplifier input is -43 dBm plus -31 dB = -74 dBm. But, alas, -74 dBm isn't good enough me — I want to use that amplifier to elicit greater isolation. However, I don't want any gain in my system, so I insert a 15 dB attenuator pad after the amplifier. For this pad, both S12 and S21 = -15 dB. For my amp, the net cascade is S21 = 0 and S12 = -46 dB.
Since S21 = 0, the block has 0 impact on the signal amplitude applied to the mixer, but the signal at the input of my isolation amplifier is -43 dBm plus - 46 dB, or -89 dBm. This isolation I like — it also illustrates a systems approach that gets you thinking about measurement in your own 50 Ω blocks.

The figure of merit for making a good isolation amplifier is now the difference between S21 and S12. If you want, go ahead and just use S12 for reverse isolation, but you'll probably measure S21 plus S12 anyway and that's what this web page is about! Onward.

QRP — Posdata 3

Comments From the Workbench

I'm no amateur electonics expert — I'd like to be one, but this is a tough field; RF and AF *design* is quite scientific, under-resourced and a bit overwhelming. How do we experimenters advance and stay motivated? Reading works by professionals like Chris Trask, N7ZWY, Bob Larkin, W7PUA, Doug Self, Rod Elliott and others may highlight our lack of knowledge and scientific methodology — a realization which can distress and demotivate us lay-designers. To a degree, this is irrational thinking; personal growth is always about hard work, problem solving and overcoming barriers.

Unlike the white belted Karate student, who studies and practices under the guidance of a master to attain black belt skill level, most amateur designers, excluding electrical engineering students, can't access good teachers. As a lay-person, with few face-to-face mentors (nobody in

Canada), I try to learn by experimenting and incorporating whatever knowledge, advice or schematics I can find. Fortunately, some Electrical Engineers give me advice by email and in turn I'm able to share this information via experiments on QRP / SWL HomeBuilder.

Our dusty, analog hobby fades palpably — the number of analog electronics gurus dwindles each decade and modern electronics embraces miniature circuitry often involving digital ICs controlled by lines of code.

Current electronics hobbyist magazines rightfully focus on topics that are contemporary or important to their advertisers; for example, promoting mixed-signal ICs, DSP, microcontrollers and the kits they describe and then sell for income. Nuts and Volts is 1 example. Both analog RF and AF design increasingly lies in the hands of a small group of specialists, enthusiasts and students.

Yet, we *persevere*. Sharing our knowledge, circuits, experiences and references on the Internet helps sustain our small global community. That's the site purpose— sharing the (warts and all) experiments + basic information of a lay-person.

The Emitter Choke in Common Base RF Amps

This web page covers reverse isolation — a really important topic. 2 principle amplifiers we employ for strong reverse isolation are the common base BJT and common gate JFET alone or in cascode with other amplifier topologies.

Some comments regarding using a radio frequency choke in the common base amplifier follow.



Above — Case 1: Emitter resistor only.

Apart from providing DC bias along with R1 and R2, emitter resistor RE plays another important role. Despending on its value, a portion of the input AC signal may pass through RE to ground instead of going through the transistor — degrading signal amplitude and noise figure. To minimize this, the resistor value should be many times (~10X or more) than the input impedance of the amplifier.

Although we might bias a common base amp to give an input Z of 50 Ω, often we'll choose a much lower input Z to get higher voltage gain. Input Z = 26 / Ie where Ie = mA; so if you bias for 5 mA, you are looking at an input Z of ~5 Ohms. In that case, a low value bias resistor such as 100 Ω won't shunt much of the input signal to ground, nor will it likely contribute much noise.

For most common base RF amps, a correctly chosen emitter resistor is all that's needed to decouple the AC signal and using an emitter choke proves hard to justify. However, it's important to understand how to apply an emitter choke since the basic principle also extends to the common gate JFET amplifer and other circuits.



Above — Case 2: Emitter resistor plus a choke.

The choke’s main purpose is to block or choke RF from passing to ground. The ideal choke would present infinite impedance to AC signals, plus 0 resistance to DC voltage. In reality, "ideal" = fantasy electronics and you can simply estimate a choke's inductive reactance using the classic formula (XL =2*PI * Freq * L).

Using a coil (and not just a resistor) is generally better for decoupling — although how much better might be debatable. If the inductive reactance (XL) of the coil is significantly higher than the input impedance of the transistor, then all of the input signal power goes to the transistor.

By convention, a minimum choke XL should be at least 3 times the input resistance, however, the self-resonant frequency of the coil must be significantly higher than the applied frequency. Thus, an ideal range of inductive reactance exists, and too little or too much can degrade performance. Many builders target an XL around 10 times higher than the transistor input impedance at the lowest operating frequency.

Example: For a common base amp biased for an input Z of 50 ohms, the minimum inductive reactance (XL) for the choke = 500 ohms. To calculate the inductance of an emitter choke for this amp at 50 MHz, we re-arrange the formula to solve for L.

L = XL / 2* Pi * F
L minimum = 1.59 uH.
Winding the choke on a ferrite core, or possibly a bead for VHF often means less turns, less winding capacitance and a higher self-resonant frequency.



Above — Case 3: Bypassed emitter resistor plus choke.

The primary purpose of the capacitor across RE is to filter resistor noise — but that is only an issue well below the frequency of interest and it should not be relevant at high frequencies where the choke reactance is significant. There may be some useful effect if the self-resonant frequency of the capacitor Cx is above the frequency of interest.

You can only use bypass capacitor **Cx** when a choke is implemented.

A 0.1 uF may be useless at high frequency. In error, I've used this value previously on the site; after 14 years of experimenting, I've learned a lot from my design mistakes.

The case of the common gate JFET amplifier

This discussion also informs common gate JFET amplifer design. The JFET source requires signal decoupling similar to the emitter of the bipolar transistor discussed above.



Above — Case 4: A choke plus source resistor will commonly be the "go to" design. Things get a bit more complicated with some, but not all JFET circuits — engineers often match the JFET input for a low noise figure rather than just the "correct" input impedance.

A good example follows: We might place a common gate JFET amp after a diode ring mixer because of the wideband load it presents to the mixer's RF port. The best noise match may occur with a hypothetical input Z of ~70 Ω (this argument represents an advanced topic).

After measuring the JFET pinchoff voltage and Idss, you would likely find that a source bias resistor of ~100 Ohms would be needed. This R value is so close to the JFET input Z that signal losses to ground would occur — demanding a choke for signal amplitude preservation, plus impedance and noise figure control.

QRP SWL HOMEBUILDER

RF — Test and Measurement

VFO - 2011



Building VFOs in 2011 might seem an irrelevant exercise given the move to and evolution of digital signal generators laden with bells and whistles like memories and audio or video frequency displays.

A successful L-C VFO requires skill, patience and some good parts to pull off — else, a "drift monster" may result. Despite their limitations, it's possible to build L-C VFOs with low frequency drift, distortion and phase noise; our typical VFO performance markers. L-C VFOs don't require programming skills or equipment to encode a microprocessor — making them a good choice for people who don't build or can't afford kit oscillators. Most of all, they kindle creativity, problem solving and pride when your oscillator actually works as planned. Junk box radio; my passion.

This material reflects lots of empiricism; not pure science. It's really *your* VFO design odyssey; a chance to think creatively and critically to sort out what works and what's folly.
Countless web pages discuss VFO design and I encourage you to search for and read them. Wes' EMRFD oscillator and temperature compensation notes = essential reading. Only your first 25 VFOs will prove difficult — it gets easier after that.

VFO 2011 Topics:

1. Frequency Stability Notes
2. Vackar VFO Experiments
3. HF Signal Generator
4. Miscellaneous Bits

---

1. Frequency Stability Notes

Building an oscillator that stays on frequency purports our greatest challenge and goal in L-C VFO design. Since drifting VFOs pose a source of frustration, I cover some topics that may help your VFO stay on frequency — do they help?

What is good drift parameter?

I'm uncertain, for after warm-up, I've measured kits that drifted 50-150 Hertz per hour, built L-C VFOs that drifted under 20 Hz per hour and every once and a while, build a drift monster VFO that sweeps upward at 2 - 8 hertz per minute! Likely under 20 Hertz per hour after warm up = a gold standard to compare against. You should be able to listen to a 10-20 minute QSO with no re-tuning, however, this assumes the transmitting stations are locked on frequency.

1. Unloaded Q and Frequency Stability

The number 1 reason to employ high resonator Q in oscillators is to obtain low phase noise. Secondly, the very steep phase slope through high Q resonance minimizes the effect of amplifier phase shifts caused by temperature changes and this in turn, minimizes any amplifier-induced frequency instability.

Long term frequency stability is chiefly dependent on the temperature, environmental and age stability of the resonator components regardless of Q.

I often see designs featuring high Q inductors wound on powdered iron toroids complimented with trashy, low Q variable and/or fixed capacitors, If you design for a high Q tank to minimize phase noise, consider using a high Q coil plus appropriately temperature stable, high Q capacitors.

2. Temperature Stable Inductors

Knowing that I'm venturing into a topic of great debate and lore, the inductor is 1/2 of the VFO resonator and thus a major source of temperature drift in L-C VFOs. Since MF and some HF VFO designs *may* preclude using the *inherently more temperature stable air wound inductor*, powdered iron toroids dominate our evermore compact designs. Many builders choose #6 material, although the lower temperature coefficient of #7 material theoretically should be better — however, my experiments have failed to measure a significant difference between these 2.

Some builders prefer size 68 inductors, for the bigger core is less affected by heating than smaller size toroids. My experience suggests that providing the VFO amplifier current is kept low, both size 50 and 68 are both suitable and the inductance needed should inform the core size.

I used to think that heavier gauge wire created greater frequency stability than smaller gauge wire until Wes, W7ZOI, woke me up. As it turns out, smaller gauge wire is often better for thermal stability because smaller gauge wire lies closer against the toroid core. Winding stiffer, heavier gauge wire creates more air gaps than smaller gauge wire and air gaps expand and contract during temperature changes. Smaller gauge wire will have a reduced Q, but it won't be as significantly lower as you might guess. As possible, I prefer tightly wound number 28 wire. 26 gauge wire tends to be my maximum size wire for VFO coils, however I suggest you make your own conclusions.

Wash your hands before winding and use both hands to actively move both the toroid and wire for tight turns. Take your time, ensure steady wire pressure and avoid kinking your wire. Taps increase the likelihood for air gaps — mitigate this by stripping the 2 tap forming wires as close to the toroid as possible and twist them into 1 wire right down tightly to the toroid edge to reduce any air gap.

The thermal stability characteristics of wire can be mitigated somewhat by annealing the wire with temperature cycling or by dunking it in boiling water. Roy, W7EL first reported annealing coils in 1980 and this has been confirmed during experiments by builders using temperature controlled ovens. I don't boil my coils any more.

3. Double Stacked Toroids

I noticed a new trend in VFO design is to stack 2 powdered iron toroid inductors. This allows the builder to double the inductance per number of windings over a single toroidal inductor. In an L-C VFO, the goal of these builders possibly is to reduce heating effects, increase unloaded Q, or perhaps to reduce core magnet flux density. For me the goal is far simpler, I just want to make compact, large L value inductors for 3 MHz and less.

Above — A T68-6 hamburger. The two T68-6 cores were epoxy glued together and compressed lightly in a vice for several hours. One of the initial tests I performed was to see if boiling the stacked coil affected the epoxy glue. The glue was not effected by annealing wire on a stacked coil with 5 or even 10 minutes of boiling in water. As mentioned, I stopped boiling my VFO inductors as tightly winding them with 26 gauge wire seems to work well.

I hold concern that stacked toroids may create more wire-air gaps when compared to a single toroid and stay with 1 toroid as possible. In compact antenna tuners and other non VFO projects, this isn't an issue.

4. VFO Tank Capacitors

We choose VFO tank capacitors to avoid temperature change caused frequency drift, or to counter drift during our temperature compensation process.

Many authors have published guidelines for long term temperature stability. It's important to consider these guidelines, but also try whatever works. I believe the following arguments are accurate based upon my experiments:

1. Multiple NP0 or C0G (0 temperature-compensation) tank caps: Most builders minimally use 4 or more C0G or NPO capacitors to reduce heating effects and to average out temperature coefficient variations.

2. No VFO tank capacitors from online surplus parts stores; buy new stock from known and reputable manufacturers. Grab bags and musty, old, surplus parts can obviate good design.

3. Trimmer and tuning caps need to be temperature stable. Air variable capacitors = my favorite, as possible.

4. Varactor, or diode tuning generally = more drift and a greater need for temperature compensation.

5. Employ short, stiff capacitor leads. I use 100 volt or higher voltage C0G tank caps as they tend to have thicker leads that stay put — perfect for Ugly, Manhattan, or Chuck Adam's MUPPET construction.

5. Temperature Compensation

The goal of temperature compensation is to cancel the tendency of the VFO to drift in 1 direction — easier said than done + very time consuming. A web search for VFO temperature compensation will yield many good write-ups. I feel it's partly art, partly luck and partly science. Your net VFO temperature coefficient can be affected by so many variables, so no 1 recipe will ensure a low drift VFO. Experiment, allow a lot of time to assess your changes and be patient — you'll figure it out.

The simplest way to test for drift involves watching a frequency counter, but if you don't have one, you might use a commercial, frequency stable (synthesized) receiver set in the SSB/CW mode. I use both. Experienced builders often employ an oven to test their temperature compensation at different, controlled temperatures. Wes, W7ZOI employs a styrofoam cooler housing a light bulb heat source controlled by a Variac. See EMRFD for more details and a photograph.

In 2011, I decided to build up a supply of temperature compensation capacitors and keep them in their own parts bin.

TEMPCO
CAPS

Above — "Tempco caps". A parts drawer containing polystyrene capacitors from 10 to 270 pF plus some 56 pF ceramic N750 capacitors for negative temperature compensation. I purchased these capacitors on eBay.

For capacitors other than NP0 (which use 0 instead of a ppm value), the temperature coefficient = **P** for positive and **N** for negative, followed by a 3-digit value specifying ppm/°C. For example, N220 is - 200 ppm/°C. and P100 is +100 ppm/°C.

I use NP0 and C0G ceramic capacitors interchangeably for both tuning and RF bypassing the VFO tank resonator. For C0G/NP0 *temperature compensation bypass*, I normally apply 0.01 or 0.001 μF caps, however, the more expensive 0.1 μF COG ceramic capacitors are still sold if you need C0G/NP0 bypass <= 7 MHz.

If your VFO is drifting upward you might insert 1 or more positive coefficient capacitor(s). If your VFO drifts downward, then try using negative coefficient value(s). Sometimes just 1 capacitor will do the job.

Since I don't stock any positive coefficient capacitors for positive coefficient compensation, I might try a adding a silver mica capacitor. ***Caution*** silver mica capacitors are extremely non-predictable and can't be universally recommended in temperature compensation schemes. You might also try swapping out 1 or more of your main tank NP0 or C0G capacitors in case they are bad; sometimes it gets frustrating. I provide some temperature compensation examples on the QRP Modules 2011 web page in the 7 MHz VCO section.



Above — 56 pF N750 ceramic capacitors rated at 1KV

6. Mechanical Rigidity

Movement of your VFO tank parts may lead to frequency instability. For example,

1. Well secure your single-sided only copper board. I use at least 4 number 8 bolts — 4-40 hardware is too light. Boards can warp over time if not lashed down properly. Aggressively bolt down any variable capacitors. No tank parts should move.

2. Anchor your inductor so it cannot budge: nylon bolts, zap-straps, glue - whatever.

3. Consider placing the VFO in a strong chassis with rubber feet.

4. Buss wires should be made from thicker gauge, well anchored wire.

7. Miscellaneous Points

1. Regulate the VFO amplifier DC voltage and wideband filter it. Voltage regulators require RF and often AF bypass to attenuate any noise or ripple riding on the DC.

> A decoupling resistor with a bypass cap on either side will widen your DC supply filtering bandwidth and deserves strong consideration. A poorly filtered DC supply can easily transmit the VFO tank energy to other stages along your DC lines and also may allow noise on the DC supply to modulate your VFO and increase phase noise.

2. You should have the buffer + a load resistor connected to your VFO when testing. **Do your temperature stability work after the buffer is built and the VFO is in its case.**

3.Stick your VFOs in an air tight, RF tight case to minimize air temperature changes and RF leakage respectively. Sometimes a VFO will drift once in a case because any radiated buffer amplifier heat will warm up the inside of the chassis. This usually levels off after warm up.

4. Modern voltage regulators may significantly reduce noise compared to a zener diode regulator. Specific low noise and low temperature coefficient voltage regulators are available, but maybe overkill for you. Whatever you use — filter it well —
The Micrel MIC5209-5.0BS in SOT223 sits in a couple of my reference oscillators.

5. JFET Gate clamping diodes may increase phase noise, but not prohibitively so in most popcorn designs.

6. When winding toroid inductors, wind 2 extra turns. When finished, unwind the first 2 turns since they are usually loosely wound and prime culprits for air gaps.

7. Since magnet wire comes off small spools, wire has a natural curve or radius — ensure you wind your coils according to the natural curve of the wire.

8. The need to secure powdered iron windings with dope, wax, goop, etc. is over-emphasized and usually unnecessary.

---

2. Vackar VFO Experiments

Some builders proclaim the Vackar as the "King of VFOs". I built a couple and became impressed by the low distortion and less than 5 Hertz per hour long-term drift achieved in my 2 designs. Inspired by work from Iulian, YO3DAC entitled Very Low Phase Noise Vackar VFO for HF Transceivers *(link and reference used by permission of Iulian)*, I crafted my version from his notes and schematic.


7 MHz Vackar VFO
Tunes 7.00 - 7.034 MHz
12.22v
100
FT37-43
14t:4t
.1
1 mH
.1
5v Reg
470
8K2
.001
C0G
Q3
2N3904
2K2
.001
3.3 pF
C0G
d
g
s
Q2
J310
4.87 uH
T50-6
26 AWG
270 pF
C0G
100 pF
C0G
27K
47K
Q1
BD139
180
.1
5 pF
SM
20 pF
C0G
4K7
47 pF
C0G
510
.001
C0G
5-120 pF
air
tune
82 pF
C0G
12 pF
C0G
4.5-24 pF
air
band-edge
0.4 mA IE
A

Above — Schematic of the Vackar VFO employing a BD139 — a large area transistor, to reduce 1/f noise. Iulian shared many design pearls in his paper and I won't repeat them. I ran Q1 with 0.4 mA emitter current to reduce heating and flicker noise. It's difficult to measure flicker noise, so no objective comments can be made.

I limited the tuning range to 34 KHz since the tuning capacitor lacked reduction gear and I was born with fumble fingers. As a CW operator - you'll find me down at the bottom of the band away from the RRTY anyhow. Increasing the 5 pF cap coupling the tuning capacitor to the tank increases the tuning range as expected.

Temperature compensating my VFO with the 5 pF silver mica capacitor proved a gamble since SM caps are unpredictable and often best avoided. In *my* VFO, it worked perfectly, however. This circuit is difficult to replicate and *not recommended* for new builders. Temperature compensation provided the sublime frequency stability.


7 MHz Vackar VFO
12.22v
51
10 bifilar turns
FT37-43
.1
.1
1K5
1K5
heat
sink
.1
39
50 Ω
.1
1K
2N2222a
150
100
.1
- 6 dB
4.7
B
Total current = 33.9 mA
Return loss = 24.3 dB
Output power = 6.84 dBm
2nd harmonic = -36 dBc

Above — The final amp and measured output data. Measuring the 2nd harmonic 36 dB down without any tuned circuit or low-pass filter rocked. I ran nearly 22 mA of emitter current to bump up the return loss and spectral purity. A 2N5109 or 2N3866 would likely do a better job with less current. Total current = the entire VFO current. I glued a drilled copper penny on the 2N2222 to dissipate heat.

A photo of my version of a Vackar VFO. My design goals included low phase noise, low distortion, a return loss over 20 dB, good reverse isolation and ~7 dBm output power. I believe all VFOs are experimental; you build to suit whatever tuning capacitor or varactors you have, plus design around constraints such as total current, tuning range and other personal criteria.

Unlike harmonic distortion, oscillator phase noise, being close to the oscillation frequency, cannot be removed by filtering nor limiting — you must design for low phase noise. Modern digital VFOs are well harmonically filtered, and any phase noise depends on the DDS clock employed, so check the DDS specifications carefully if you go the DDS VFO route.

I'll be the first to state I'm no expert with VFOs, however, likely the only way to become expert is to build many and learn from your mistakes.

Above — A 7 MHz Vackar VFO with the lid off

Sound Test?

Although this technique raises the ire of some builders, I test my VFOs in a nearby receiver. The VFO output was terminated with a 51 ohm resistor that was also attached to my frequency counter via alligator clips and wire. I tuned a nearby CW superheterodyne receiver to 7.00 MHz with the audio beat note centered in its 600 hertz wide I.F. filter and watched the counter plus listened to the receiver.

Click for a 1 minute 32 second audio file of the result (it stayed perfectly on frequency for ~5 hours of testing before I got a bad headache from listening to it and shut it off). *You can initially hear a station in the back ground despite only having a 45 cm piece of wire as the receiver antenna.* The VFO slowly drifts down to 6999996 Hz and then slowly back up to 7000000 Hz. You can hear the signal amplitude decrease as the VFO drifts down. So it doesn't stay perfectly on frequency, but slowly cycles up and down a few hertz. This VFO is my lab temperature stability benchmark for an L-C VFO.

A badly drifting VFO will move out of the test receiver I.F. pass band and sound like a Theremin as it does. Testing in a receiver; places the VFO in the exact circumstance it will be used — beating RF to mix to another frequency; in this case, base band audio.

The temperature stability and compensation of any VFO schematic are rarely reproducible since there are just too many variables. Try your best to get the drift out of your VFO using low temperature coefficient capacitors (NP0/C0G) and then after that, temperature compensate. Even today, I occasionally build a drift monster VFO and become frustrated. VFO design is not for the faint of heart and it's no wonder that many builders make a VXO, or cave in and build or buy a DDS signal generator.

---

3. HF Signal Generator



Above — I built a general purpose ~2.8 to 10.8 MHz signal generator (SG) for my lab in 2011. The first VFO topology tested was the Vackar. In my version, while employing a 100K ohm resistor as the buffer, the VFO only tuned from about 4 to 8 MHz and suffered from *extreme* amplitude variation as I changed the frequency across its range. For sweeping filters or measuring Q, a signal leveling circuit would be needed as normally we like our SG output to be flat across its frequency range. I later changed to a Hartley VFO because of its flatter output and the wider available frequency range with any given resonator.

This initial Vackar VFO experiment wasn't a total waste as I learned a way to accurately sweep a **D**evice **U**nder **T**est with an unlevel amplitude SG. Measure the peak-peak voltages of the DUT with a signal generator and an oscilloscope in the same manner we measure insertion loss or gain in a 50 ohm system: Measure the peak-to-peak voltage with the DUT in line; disconnect the DUT, insert a barrel connector and then re-measure.

The dBm difference between the 2 becomes the dB value to plot for *that* frequency. To a sweep a filter, say for example, a band-pass filter, find the center frequency and then sweep below and above that CF while plotting the dB versus frequency.
This "in and thorough" measurement described takes time, but resolves any frequency versus amplitude issues and can be used to test signal generators. We tend to ignore things like cable loss versus frequency and scope or spectrum analyzer ripple.

Still, it will be easier to just use a Hartley VFO where our sweeps are assumed to be level due to the flatness of the amplitude versus frequency for **small excursions** such as 3 dB band-pass filter sweeps. Do not expect amplitude flatness over wide excursions however — this requires additional circuitry.

To reduce noise and boost fidelity, this SG runs modest current and was not designed for battery use.


Low Freq: C = 370 pF
High Freq: C = 20 pF
12.22v
100
C
220 pF
C0G
150 pF
C0G
5 pF
C0G
d
g
s
.1
1M
J310
1N4148
44t
3t
51
8t
IS = 1.66 mA
T50-6
S
G1
Q1
D
G2
Bottom up
40673
12.22v
10K
10K
.001
100
C
220 pF
C0G
150 pF
C0G
5 pF
C0G
G2
D
G1
S
.1
BF998
1M
1N4148
44t
3t
8t
51
Signal Generator 2.7 – 10.7 MHz

Above — My Hartley VFO is morphed into a double-gate MOSFET VFO; this was a mistake and I make lots of them.

When venturing out, it's often best to confirm a proven design is working before morphing it to something untried. Shown above left is the Hartley oscillator from EMRFD Chapter 7 sans buffer. Fixed "tuning" capacitors; either 20 pF (not shown) or 370 pF (150 pF + 220 pF) represent the intended high and low frequency swing of my air variable tuning capacitors.

I wanted a variable amplitude VFO and thus replaced the JFET with a double-gate MOSFET using a simple variable voltage divider to control gate 2. I showed this to Wes, W7ZOI and he informed me that the flicker noise of MOSFETs precludes their use in oscillators. I have always wondered why I've never seen MOSFET VFOs in any radio literature.



Above — My project chassis fitted with hardware. I employed 2 air variable tuning capacitors — the fine tuning capacitor ranges 13.6 to 27.5 pF, features built in 6:1 reduction gear and was purchased from Doug DeMaw many years ago. I secured the main copper board with 6 number 8 bolts. Rubber feet provide a stable, shock resistant base for the sheet metal box.

Final Build


2.8 – 10.8 MHz Signal Generator
A
180 pF
C0G
S1
3.3 pF
C0G
12.22v
+
22 -
470 uF
150
.1
10K - 15K
100
100
.1
.1
12t
FT37-43
10.6 -
148 pF
coarse
13.6 -
27.5 pF
fine
5 pF
C0G
Q1
d
g
s
.1
10K
gain
19t
6t
FBA
FT37-43
.1
High Z
Q4
d
10K
1N4148
1M
4K7
Q2
.1
510
g
s
1K
44t
3t
8t
.1
T50-6
Q3
d
g
s
4K7
150
.1
Q1=Q3=Q4= J310 ; Q2 = 2N3904
S1 thrown = low range ; S1 open = high range
1N4148

Above — Oscillator + buffer schematics of the latest version of my signal generator. I spent 1 evening playing with VFO designs and settled on the simple Hartley from EMRFD, Figure 7 .27. The 3 turn link provided lower distortion than coupling the oscillator to its buffer by the JFET source or gate.

Regulated 12.2 VDC powers the oscillator; avoiding the typical 5-9 VDC voltage regulator we normally use. A 22 to 470 μF cap should be employed to filter any voltage regulator noise from our DC supply. Mine has a 470 μF capacitor.

1 hour drift lies under 40 Hertz when averaged from 15 different frequency points between minimum and maximum. The Q2/Q3, Q4 and Q5 transformer inductances were optimized to allow good signal and/or matching performance in the ~ 2.5 to 10.8 MHz frequency range.

A hybrid cascode (hycas) buffer with variable base bias on Q2 forms the amplitude control for both the high impedance and low impedance outputs. The 510 ohm gate resistance on Q4 terminates the hycas amplifier and sets up a known output impedance to drive the 50 ohm feedback amp. I measured a greater than 22 dB return loss on the output of the 19:6 turn transformer from 4 to 14 MHz — indicating it drives the feedback amp reasonably well.


2.8 – 10.8 MHz Signal Generator
B
12.22v
51
12 BFT FT37-43
.1
.1
1K5
1K5
50 Ω
FBA
.1
1K
2N5109
68
.1
4.7
.1
37
50 Ω
— 150 —
6 dB
25.1 mA
Output = -15.4 to 10.5 dBm @ 5 MHz

Frequency	RL out
4.92 MHz	31.1 dB
7.00 MHz	32.1 dB
14.00 MHz	27.9 dB

Above — The 50 ohm impedance feedback amp. Running 25.1 mA current allowed a clean sine wave output up to 2.12 volts-peak to peak into a 50 Ω terminated oscilloscope, plus an output return loss of over 30 dB across the SG tuning range. 3 tabled output return loss measurements are shown; including an out-of-range 14 MHz measurement.

Two series resistors made up the 37 ohm "resistor" depicted in the 6 dB pad, although a 39 Ω resistor would work fine.

At low output amplitudes, I typically stick an external 6, 10 or 20 dB attenuator on the output since the hycas amp can distort the signal a little when the gain control is set to a really low bias voltage on Q2. Then I fine tune the output power with the gain control.


ON
HI–Z
50 OHM
GAIN
HI
LOW
FINE
COARSE

Above — A "lid off" front panel photograph. Click or click for other photos. I'm now using miniature pots with a shaft diameter of 3.18mm. The potentiometer shaft lacks a knob and I'll purchase some on my next parts order.



Above — The completed signal generator.


RIGOL
T'D
2 0.00uV
T 3.50000MHz
2
Vpp(1)=*****
Freq(1)=*****
Vpp(2)= 1.68V
CH2 260mV
Time 50.00ns
T→0.0000s

Above — Signal generator output at 3.5 MHz.

I appreciate that the VFO tank would be difficult to replicate since the 2 air variable capacitors are unique, however this is true of most VFOs. Wes wrote some great notes in EMRFD Chapter 7 regarding copying signal generators and the versatility of the Hartley VFO. I hope this project furnishes some ideas that spawn you to build something better than I did. *(I've received over 350 related emails since posting this page in 2011* *and many readers have built really great VFOs — Way To Go !)*

QRP — PosData for December 17, 2013

I slightly boosted the tuning range from 2.8 to 10.8 MHz by dropping the 5 pF resonator capacitor to 3.3 pF in October 2013. The schematics now reflect this changes plus clarify 1-2 stumbling blocks readers had. For example: my use of a 100K gain pot plus a 150K maximum voltage limiting for the Q2 bias. My build still has these, however, I altered the schematic to show a common 10K gain pot, plus a fixed 10 to 15K resistor used to limit the Q2 bias to between 5 and 6 VDC maximum.

In reality, any reasonable pot and resistor will do since they function as simple voltage dividers. With a 12 volt supply, we don't want to drive the Q2 bias with more than ~ 5 to 6 VDC since this will just distort the AC signal as the hycas stage saturates. Measuring with a voltmeter, solder either a 10K, 12K, or 15K resistor to limit the maximum Q2 bias with the 10K potentiometer turned fully clockwise.



Above — Alternate way to couple the Hartley oscillator to the hycas buffer. Ground the JFET gate with a shunt resistor and lightly AC couple the JFET gate to the Hartley secondary coil with a series capacitor. You choose the capacitor value to limit the signal amplitude as needed. Our main goals are to lightly couple the Hartley tank to its buffer and avoid overdriving the hycas stage. Numerous examples of this "Alternate Take" circuit may be found on the QRP / SWL HomeBuilder web site.

---

4. Miscellaneous Bits



Above — Scope traces of an unbuffered Hartley oscillator with a X10 scope probe across a 51 ohm resistor across the 3 turn link. The unbuffered Hartley sine wave isn't harmonic free, but cleans up when properly buffered with a higher impedance amplifier. Figure A = the lowest frequency (2.7 MHz) — the distortion increased with frequency (Figure B was measured at 10.5 MHz). Figure C illustrates how slightly stronger output coupling with a 6 turn link trashes the output waveform — the strategy of using 2-3 links over the center of the main inductor works well.

Figure D is the 6 link coupled Figure C oscillator with the gate clamping diode removed; yikes! I spent 4 hours studying what different current, voltages, coupling and so forth do to the Harley oscillator. I recommend the Hartley topology because it's simple, always starts and versatile.


100
8K2
1 mH
.1
.001
2K2
3.3 pF
C0G
Q1
27K
100 pF
C0G
4K7
47 pF
C0G
0 pF

Above — In my various signal generator experiments, I zap strapped the toroid to a small piece of thick copper board that was later soldered to the main board. The L seems robustly secured.



Above — A stacked toroid from the deleted VFO-2008 web page. I incorporated some of the information from the VFO-2008 page into this web page


12.24v
.001
C0G
Bottom
100 uF
5V regulator
.001
C0G
Band
edge
5 pF
C0G
d
g
s
10 pF
C0G
optional outputs
330K
Buffer
Buffer
390
10 pF
C0G
Main
tuning
C0G
C0G
C0G
Fixed tank caps
.001
C0G
100 uH

Above — In order of preference, 3 ways to couple a Hartley oscillator to its buffer. From now on, I'll couple with a 1-3 turn link since it gave a lower distortion signal than with source or gate coupling. This figure omits the gate clamping diode seen earlier— tapping the inductor as shown keepings the FET gate AC voltage at a reasonable level when not using a gate clamping diode. Some builders leave off the gate clamp diode that clips positive signal peaks for lower phase noise. The diode acts as an AGC and offers benefit. Reverse biasing this diode was suggested by Dr. Ulrich Rohde: see — Key Components of Modern Receiver Design - Part 2: Dr. Ulrich Rohde, KA2WEU , QST for June 1994.

A formula to use for the inductor taps: Divide the total turns by 1.45 to get the first tap and by 7.25 to get the second tap (near ground link).



Enjoy your VFO experiments.



50 OHM
GAIN
HI
ON
HI-Z

The Butler Did It ! - First VHF Experiments 2011



Venturing into VHF, I felt like a beginner with no experience or confidence — however, the excitement and allure of new parts and circuits kept me going.

After performing a literature review, talking to some colleagues and renovating my QRP work bench, my first tasks involved buying some VHF parts + exploring the Butler crystal oscillator. Specifically, I'll cover my experiences with the common base version of the Butler oscillator.

Like HF, the VHF knowledge base contains ever-present lore. Consider the Butler oscillator — I have read arguments stating that the emitter follower version of the Butler oscillattor is vastly superior to the common base version because the latter is prone to UHF and other spurs. These comments seem to have originated from a good book entitled Crystal Oscillator Circuits. *Revised Edition* by Robert J. Matthys published in 1992 by the Krieger Publishing Company.

While examining the schematics of professional/world class gear using a Butler, the common base version clearly dominates. Spectrum analysis and other measurements indicate that when common UHF oscillation management techniques are applied, common base Butler crystal oscillators work well.

Suppressing UHF oscillations with ferrite beads (and small value resistors), feedback, neutralization, limiting gain, etcetera are routine practices for us experimenters applying active devices that have strong gain into UHF on up. This is vanilla, or matter-of-fact construction for us; no worries. While fun and often convenient, lore ultimately stifles our progress.

Increasingly, I'm adopting the philosophy of Bob, K3NHI; "TMITK" — to measure is to know. Consider, too, you have to know what to measure and possess the required gear.

For BJTS, I purchased PN5179, MPSH10, 2SC3355, BF199, 2SC3357-RE, 2N5109/2N3866 and NE46134. The PNP part = MPSH81.



For JFETs, the J310 in TO-92 and SMT will remain my workhorse FET part along with a couple of other *low noise* JFETs and 2-gate MOSFETs. At VHF, the noise figure in a receiver chain is established by the first amplifier so a low noise preamp ranks important.

A collection of 100 volt NP0 capacitors ranging from 1 pF to 22 pF were added along with some chip and SMT caps as low as 0.5 pF. You might need a few air trimmer capacitors with a minimum capacitance ~ 2 pf — I applied 2 - 20 pF trimmer capacitors in most of the circuits that follow.

---

1. Experiments with a Butler Oscillator with a 23.3 MHz Fundamental Crystal

Fundamental Frequency

Long ago, I pulled a crystal marked 70.00000 MHz from a Drake Transmitter. I keep a fundamental oscillator based upon EMRFD Figure 4.23 on hand and verifed the fundamental frrequency at 23.3 MHz.


Butler Oscillator set for Fundamental Oscillation
8v reg
12.22v
.001
.01
454 nH
T30-6
4K7
22 pF
- 5 dB
15
15
50 Ω
10-60 pF
68 pF
82
.001
1K
100
23.3 MHz
150 pF
PN5179

Above — A Butler oscillator arranged for output at the fundamental crystal frequency. While commonly arranged as an overtone oscillator, the Butler is a good oscillator for any application. Consider, for example, EMRFD Figure 7.32. Wes applied the Butler at a 14 MHz fundamental because he wanted the lowest phase noise and IMD prone signal source possible. Tellingly, his buffer circuitry also conforms to this high standard.

My initial waveform looked distorted and prompted a solution. My experience yields that the L value needs to be adjusted for the best looking waveform in the Butler circuit. The inductor wire, wrapped around a T30-6 toroid was either scrunched to increase the inductance, or expanded to decrease the L while re-peaking the trimmer cap. Eventually, with patience, a beautiful sine wave emerged on my 'scope. I removed and measured the L with an ADE inductance meter. Consider all of my reported inductance values as nominal — gentle expansion or contraction of the inductor coils might be required to get an agreeable sine wave.

Click for the oscillocope tracing at 23.3 MHz.

The Butler at Overtone Frequencies


Butler Template
8v reg
.001
.001
XL = 55-110 Ω
4K7
XC= 318 Ω
15
15
XC = 159 Ω
82
,001
1K
100
XC = 40 Ω
L in Henrys
F in Hertz
C in Farads
XC / XL in ohms
XL = 2 * pi * F * L
so L = XL / (2 * pi * F)
XC = 1 / (2 * pi * F * C)
so C = 1 / (2 * pi * F * XC)

Above — A template (of sorts) for calculating Butler capacitor and coil values. The concept, rather than the absolute value matters most. I examined some well-designed Butler oscillators from professional equipment and determined their average XL and XC values. From the reactances shown, calculate the L and C values for the overtone frequency of interest with the 2 formulas in orange boxes. *Remember these XL or XC values just serve as starting values for experiments.*

For example : At 50 MHz with an XL of 108 Ω : L = 108 Ω / (6.28 * 50000000 Hz) = 0.000000344 H or 344 nH.

Fine tuning of the capacitor and inductor values might be required since factors including buffer input resistance +/- reactances, the overtone frequency and/or your breadboard layout may affect your Butler oscilator function.

In the experiments from the 3rd to 9th overtone frequency, the L = an air inductor wound with 21 to 22 AWG wire on a bolt.

Third Overtone Frequency


Butler Common Base Oscillator @ 3rd OT
8v reg
12.22v
.001
.001
234 nH
4K7
7.98v
2 - 20 pF
10 pF
- 5 dB
50 Ω
15
15
82
1.28v
15 pF
0.26v
.001
1K
100
70 MHz
68 pF
F = 23.3 MHz
PN5179
6.83 mA

Above — The Butler oscillator now arranged for output at the third overtone. Click and click for the 'scope outputs at the third crystal overtone. The first scope tracing was slightly mistuned. Once again, the inductor had to be gently squished or contracted to obtain a pristine sine wave.

Fifth Overtone Frequency


Butler Oscillator at 5th Overtone
8v reg
12.22v
.001
.001
4 turns
4K7
7.98v
5 pF
- 5 dB
50 Ω
15
15
82
2 - 20 pF
1.28v
3.3pF
5 pF
0.68v
.001
1K
100
116.8 MHz
47 pF
PN5179
F = 23.3 MHz
6.83 mA
4 turn L wound on a bolt
5.9 millimeters diameter (1/4 inch)
Pitch = 1.41 mm pitch (18 TPI)

Above — The Butler oscillator at the 23.3 Mhz crystal's 5th overtone. Here's the 'scope tracing and an Ugly Construction photograph. The output = 7 dBm — very cool.

Some authors directly connect the attenuated output to the Local Oscillator port of a diode ring mixer. The signal is adjusted to the desired 7 dBm power by tweaking the 50 Ω pad attenuation, and/or the NPN's current. A good example = Single-Conversion Microwave SSB/CW Transceivers by Rick Campbell in QST for May, 1993.

The circuit above was measured with a 50 Ω terminated oscilloscope however, I also tested it with a 10X probe attached to termination resistors from 51 to 1 Meg ohms. When changing the 51 ohm termination resistor to a higher value such as as 47K, a previously working Butler may stop oscillating. The buffer input impedance and capacitance greatly affected the oscillator in my experiments.

When I wired up a Butler, 1 of 3 things happened: it did not oscillate, it gave a distorted output waveform, or it wowed me with a nice sine wave. Tuning the L-C tank is critical + finicky and may test your patience.

Adding an Inductor Across the Crystal


Butler Oscillator at 5th Overtone
8v reg
12.22v
.001
.001
4 turns
4K7
5 pF
- 5 dB
15
15
50 Ω
82
2 - 20 pF
3.3pF
5 pF
.001
1K
100
409 nH
47 pF
PN5179
116.8 MHz

Above — The 5th overtone Butler with an inductor in parallel with the crystal



Above — My 116.8 MHz oscillator breadboard with an inductor wound on a T50-6 with wide spacing to allow scrunching and expanding of the windings across the crystal. I roughly determined my L should be ~ 400 nH and wound this on a # 6 toroid. While observing the output in my scope, I scrunched and then expanded its windings and adjusted the trimmer capacitor. The goal was to find a clean signal that snuffed out immediately when the trimmer cap was tuned off resonance. After finding the optimal L, I later removed and measured the coil. There is very little "wiggle room" — the oscillator tunes up and then dies very sharply as you tweak the trimmer cap. No sidebands were observed.

The inductor across the crystal is optional — some suggest it might only be needed above ~ 70 MHz.

At frequencies above ~70 MHz, the parallel capacitance of the xtal (C par) approaches the internal series resistance of the xtal and this provides an alternate path around the crystal for the signal and may short-circuit the crystal. The parallel inductor resonates with the crystal's parallel capacitance and tunes it out, so the crystal remains unbypassed.

Our teacher, Wes, W7ZOI published a document covering the Butler parallel crystal inductor here.

Simply put — the inductor allows clean tuning and output. That is, when you tune the trimmer to one side or another, the oscillator just dies and doesn't produce the sidebands that are shown in Wes' web article.

Since many of us choose computer, or other surplus crystals, a high C par + low Q crystal might give you tuning woes depending on your overtone frequency. In this case, adding the L to your circuit may improve tuning and ward off any unwanted sidebands.

With my particular crystal the parallel inductor is not needed, however, I can report that even slight mistuning just snuffed out my oscillator with the added inductor.

Seventh and Ninth Overtone Frequency



Above — I decided to take the Butler up to the 7th and 9th overtones. The 1 pF coupling capacitor proved the most critical part; for example, if I raised it to 5 pF, the oscillator would not tune above the 5th overtone. I wound the inductors on bolts and then compressed or stretched the links to get the perfect inductance. At these frequencies, stray inductance becomes quite significant and my coils were 1 to 1.5 turns less than indicated on a spreadsheet coil inductance calculator. Click for the seventh overtone 'scope shot. Click for the ninth OT 'scope tracing.

I'm confident that if my 'scope bandwidth was higher, I could have resonated the 11th overtone.

---

2. Butler Oscillator-based 50 MHz Signal Generator

Lacking a 6 Meter band signal generator, I decided to build a 1 frequency device employing a Butler oscillator. Some may laugh at a 1 frequency signal generator — I won't since I'll use it to design and align amplifers, filters, a new 6 Meter band VCO and measure scattering parameters. Besides, you can double, triple, VXO or mix single frequency generators with another variable oscillator — this web site has roots in humble, simple test equipment.

In my bag, I found a crystal labelled 50.0000 MHz and measured its fundamental at 16.67 MHz in a simple Colpitt's oscillator — perfect . Design goals included variable amplitude, strong reverse isolation + reasonable shielding and return loss. Since, I lack another 6 Meter band signal generator I could not measure return loss, however, choosing proven circuits + a terminal attenuator pad will help.

50 MHz Crystal Signal Generator

PART 1


12.22v
8v reg
.01
.01
100
.01
FT23-43
6t 2t
to amp
343 nH
nominal
510
10K
4K7
2.2 pF
Gain
10K
3K3
Q1
2 - 20 pF
Q3
.001
22 pF
.001
1K
330
50 MHz
3rd OT
82 pF
d
g
s
Q2
47K
180
.1
Q1 = Q3 = PN5179
Q2 = J310

Above — Butler oscillator + hycas buffer. The 22 pF cap in the Butler was originally 15 pF, but when tested with various coils, oscillations proved a litle sluggish, so the 22 pF was substituted. I experimented with the coil, but ran out of time, so I wound a few turns of wire on a T50-10 toroid and soldered it in. After some careful manipulation of the windings, a glorious sine wave arose. I removed the L, measured it at 343 nH and then re-soldered it in place. An air coil or other size 6 or 10 powdered iron inductor should work fine.

Click for a moderate resolution photograph of the entire project.

50 MHz Crystal Signal Generator

PART 2


From 12.22v supply
.01
+
22 uF
56
4 BFT FT23-43
.1
.01
1K5
1K5
.1
216 nH
216 nH
37.8
50 Ω
22
2N5109
220
.1
1K
150
6 dB
4 dB
75
.1
68 pF
120 pF
68 pF
4.7
low-pass FL

Above — The final amplifier and low-pass filter. The maximum output of the Q2/Q3 amp is hot and can overdrive the 2N5109, therefore a 4 dB pad was added. This pad also improves the input return loss of the 2N5109. An alternate technique might be to further reduce the maximal DC bias voltage into the Q3 base and remove the 4 dB pad.

Click for the minimum and maximum output voltage waveforms from my 'scope


RIGOL
13:06:08 2013-10-06
Local
Status
Peak
TRIG Free
SWP Cont
Corr
S.T.
PA
C.W.
Blank
Blank
Math
-4
-14
-24
-34
-44
-54
-64
-74
-84
-94
-104
1
2
Peak
Next Peak
Peak Right
Peak Left
Min Search
Peak Peak
Cont Peak
On
Off
Search Para
1/2

Ref -4.00 dBm

Att 10 dB

Marker2 100.00 MHz -66.51 dBm

Marker
100.000000 MHz
-66.51 dBm

Center Freq 75.000 MHz

RBW 1.0000 MHz

VBW 1.000 kHz

Span 150.00 MHz

SWT 150.00 ms

Above — Spectrum analysis with the generator output at -10 dBm. I placed Marker # 2 on the 2nd harmonic peak (100 MHz) and measured the power. The low-pass filter only attenuates the 2nd harmonic by ~ 25 dB, however, with the nice sine wave from the Butler, the 2nd harmonic measured -66.51 dBm = -56.51 dBc.

The 37.8 resistance indicated in the pad = 2 resistors in series. Many just use a 37 or 39 Ω R.

I look forward to advancing my VHF skills with this little signal generator.

50 MHZ XTAL OSCILLATOR
PART 1
12.22v
100
.1
510
FT23-43
6t
2t
Q3
3K3
.001
Q2
47K
180
.001

3. Doubler for the 50 MHz Signal Generator




50 MHz Doubler Experiment
12.22v
+
22 uF
100
.01
100
.01
T50-10
6t 2t
C
50 Ω
510
.01
T1
1N4148
4t
A
10K
L1
BF199
T37-6
1050 nH
nominal
1/2t
10-60 pF
10K
.001
3 - 20 pF
CV
d
g
s
J310
1N4148
B
d
J310
g
s
3.3 pF
100 K
50 Ω
2K7
180
.1
180
.1
CV
L-C-C
Network
CV = 2.8 -10 pF trimmer cap
T1 = 5 trifilar turns FT37-43
L1 = 4 turns on a # 8 bolt; tap @ 1/2 t

Above — An experimental frequency doubler for the Butler Oscillator-based 50 MHz Signal Generator shown above.

After trying a few circuits, I settled on a simple full-wave doubler featuring matched 1N4148 diodes driven by a JFET amplifier. Chapter 3 of Solid State Design for the Radio Amateur by Hayward and DeMaw for the ARRL = my key reference. Matched diodes (and a little luck), may suppress the 50 MHz signal up to 60 dB so only a single-tuned circuit follows the diodes.

The first JFET amp drives the diodes to improve harmonics + output voltage — an L-C-C Tee network matches the 2K7 Ω input to the 50 MHz signal generator output. I designed this matching network on the bench with the 2 diodes disconnected to avoid distortion during signal measurements. Using a 10X probe, I peaked the capactors for the greatest signal amplitude after finding the optimal L by educated trial and error. The inductor wound on a T37-6 was scrunched a little to further peak the L-C-C network.

I wound L1 with bare copper 26 AWG wire on a #8 bolt with coarse threads. To make enough space to solder on the 1/2 turn tap, I stretched the last turn with the other 3 turns still on the bolt to prevent stretching these coils. Click for a 'scope tracing at Point A. My 10X scope probe has ~ 15 pF capacitance and this affected the tuning — you can see some harmonics in the signal. With the 10X probe at Point B, I was nearly able to turn the circuit to 100.0 mHz, but still the 10:1 probe upsets the circuit somewhat.

This L - C tank tunes sharply and best with a non-conductive screw driver. I final tuned the L1 tank when the hycas amp was completed and connected to a 50 Ω terminated 'scope — eliminating the earlier tuning problems caused by the 10X probe. It seems that VHF requires more thought and care than HF when tuning resonators (tanks).

Point C is the maximum output (10.34 dBm) into a 50 ohm terminated 'scope. The 100.0 MHz signal is okay, but some builders might want to add low-pass filtering +/- an attenuator pad; or perhaps drive another feedback amp?


TO-92
MPS5179
C
B
E
MPSH81
MPSH10
PN5179
2SC3355
C
E
B
TO-92
2SC3357
E
C
B
SOT-89
top
B
C
E
NE46134
SOT-89
BF199
C
E
B
TO-92
Pin-outs

VHF to the Max — Miscellaneous 2012 Experiments

As a VHF newcomer, I need to make lots of circuits, measurements, mistakes and maybe — I might advance. My literature review revealed a big gap between popular, "for-fun", novelty-grade projects and the blinged-out circuits such as ultra low-noise LNA's featuring GaAs, MESFET, and pHEMT devices. Where do we find the middle ground projects? Likely on our own RF work benches.

Numerous questions arose — Will Ugly Constuction work? Do I have the right test gear? Am I measuring the proper things? What about noise figure? All a bit overwhelming — but even improbable discoveries began as simple questions and observations. We solve far more difficult problems each day.

I'm learning that whether your a beginner, or a master, bench fundamentals rank supreme. Want to avoid oscillations in your high fT BJT VHF amplifier? Work towards high reverse isolation, strong S11 and S22, careful layout and employ techniques that suppress instability — nothing earth shattering huh? I'm told that acquiring the needed skills takes time and practice.

In early Winter 2011-2012, I built some VHF signal generators, amplifiers and a lots of junk. This web page documents a few of these experiments.

Section 1. Early MAX2606 VCO experiments
Section 2: A 2-band signal generator based upon the MAX2606 VCO
Section 3: 50 MHz VCO
Section 4: 50 MHz Receiver Pre-amp and Filter
Section 5: QRP — POSDATA: Z-Communications VCO Experiments

Section 1. Early MAX2606 Experiments



Above — My first of many MAX2606 VCO Experimental breadboards.

Maxim makes a series of cool SOT23-6 VCOs ranging from 45 to 650 MHz. Wanting a VCO to cover from ~100 to 106 MHz, I just had to try this chip. The datasheet provided all the online information I could find; save for a few homebrew, flea-powered FM transmitter projects that proved unhelpful.

After soldering the IC on a breakout (prototype) board using about 20X magnification, the proto-board was dropped onto a copper clad board with some of the copper ground away.

Max2606 VCO Experiments



L1 = 5 turns on a 5/8 inch bolt (15.9 mm)
L2 = L3 = 411 nH

Above — My first MAX2606 VCO experiment. A coil lying on the workbench was soldered in as L1. I stretched it a little to set the lower band edge. Going from CCW to CW on the 100K tuning pot, I measured from 86.3 — 106.3 MHz. I'll write about L1 a little later, for making a good output network consumed my initial experiments.

The Maxim datasheet shows a simple output network consisting of 2 pull-up resistors with a maximum R of 1K. All the online FM transmitter designs I saw used 1K pull-up resistors and made no attempt at matching or even employing inductors in place of the resistors. I applied two 560 ohm pull-up resistors in place of L2 and L3 and the output looked distorted and low in amplitude. Click for a 50 Ω terminated 'scope tracing and click for a tracing with a 10X probe connected to a 10K load resistor. Unacceptable for even us scratch-builder RF experimenters.

Wanting to match the output into a 50 Ω load with high-pass L-network instead of just resistors, I calculated that an L of 250 to 800 nH, plus a capacitor from 2 to 10 pF might work, however, as a VHF newbie, my hopes weren't high. I went for a single-ended output and not knowing what to do, terminated the unused port with an AC-coupled 49.9 Ω resistor.

Choosing a 100 MHz test frequency (where I own a doubled 50 MHz xtal oscillator), I removed L1 to snuff the oscillator and measured an output return loss of ~ 17 dB with L2 = L3 = 298 nH and the variable cap set to 7.3 pF (I removed it and measured it). It took about 1 hour of trying different L values to get this return loss. I also learned that the L value and L to C ratio of L2 and its series capacitor greatly affects the purity of the output waveform.

Like all L-networks, the L and C *must* be correct to obtain a strong, clean output. Since C is variable, I tried various inductor values and further fine-tuned them by scrunching or expanding the L2 windings. *Compress or expand the L2 windings + trim the variable capacitor to peak the L-network at your desired frequency.*

From my experiments, the L3 inductance should be close to L2 for the best output voltage and symmetry, however, don't bother scrunching or expanding L3 because this won't greatly affect the output signal as long as the L3 inductance is close to L2.

Click or click for some 'scope captures of poorly matched output L-networks — low gain and/or distortion appeared with mistuning.

Click for the output where L2 = L3 = 298 nH. I had the tuning set to 100.6 MHz for this screen capture, however, you can see the nice waveform and strong peak-peak voltage when compared to the pull-up resistor only versions.

The problem with a high Q L- network = low bandwidth. I wound L2 and L3 on T37-10 powdered iron toroids and later tried T37-6 toroids. The higher Q of the number 10 material seemed to translate into higher output voltage, but narrower bandwidth over the number 6 material toroidal inductors. Alternate breadboard. When tuning the MAX2606, signal amplitude changes with tuning frequency and a single L-network peaked somewhere near the middle of the tuning range further worsens this amplitude issue.

The *unbuffered* VCO waveform distorts somewhat as you move farther away from the peak L-network frequency. After trial and error, I settled in a compromise of L2 = L3 = 411 nH. This gave the best overall signal purity + amplitude from about 98 to 106 MHz with a set peak at ~ 102 MHz. Tuning below 98 MHz tended to really distort the waveform. Click for the *unbuffered* minimum and maximum frequency 'scope tracings.

Placing an attenuator pad plus a buffer amp after the VCO dramatically reduced this distortion in my experiments, assuming the L-network components are correct and tuned.



Above — A trial buffer first connected to output of the VCO schematic above. Two series-connected 2 transmission line transformers dropped the output impedance down for examination in my 50 Ω terminated scope — unfortunately the output return loss was poor (less than 10 Ω). Unlike the common base stage in a hybrid cascode amp, varying the bias to adjust gain worked poorly and lower applied bias caused distortion. I found it preferable to just fix the bias to get the greatest voltage gain + lowest harmonic distortion.

This buffer was discarded since the return loss was too low for my needs.

Testing a Hybrid-Cascode Buffer


MAX2606 with Hycas Buffer
~100 MHZ
L1
337 nH
nominal
1
2
3
6
5
4
Maxim
Max2606
150 pF
to hycas buffer
L2
C out
10
12.22v
5 VDC
L3
←.001→
.1
150 pF
100K
.001
C0G/NP0
2K7
Tune
.001
C0G/
NP0
100K
100K
L2 = L3 = 265 nH nominal


MAX2606 HYCAS BUFFER
12.22v
100
FT23-43
6t 2t
50 Ω
.001
.001
10K
510
,01
3K3
10K
PN5179
.001
Gain
d
from Max2606
g
s
J310
2K7
180
.1

Above — MAX2606 VCO into a hybrid cascode buffer at ~ 100 MHz. I also tried a buffer with a cascode of PN5179 transistors, however, the input Z of the buffer changed when adjusting the gain potentiometer and wrecked the input matching, so I stuck with the hycas buffer shown above.

L1 and L2 = ~ 265 nH wound on T37-10 toroids. To peak the L-match at ~102 MHz, I originally placed a 100 pF in parallel with a 10 - 70 pF trimmer cap for *C out*. After tuning, I removed, then measured these 2 caps to discover that *C out* = ~150 pF; so I just substituted a 150 pF capacitor. The L1 windings were expanded a little to re-peak the output network — expanding the coils raises fCo, while compressing the windings lowers the cut-off frequency. I don't recommend omitting a trimmer capacitor unless your confident with your measurements.

Click for the maximum power 'scope tracing of the hycas amp with the L-match peaked at 102.2 MHz (3.44 dbM)

Once again, I terminated the secondary output of the MAX2606 with an load resistance equal to the main output with an approximately equivalent fixed-value capactor — I'm not sure if it's needed, but it works okay and I stuck with it.

Up at ~ 144 MHz

Click for another experiment with the fore mentioned MAX2606 into the hycas buffer shown above at ~ 144 MHz. I peaked the L-match for 142.2 MHz and the output power = a surprising 7 dBm. The output is a clean sine wave from 135 to 169 MHz, although the signal amplitude varies widely. I also peaked it at ~144 MHz. I wound L1 - L3 with #21 AWG on a #10 bolt. Photo 1 Photo 2.

Let's build something useful with the MAX2606 based upon the experiments thus far...

Section 2.   A 2-band Signal Generator Based Upon the MAX2606 VCO

Above — My dual VCO based on the MAX2606. This general-purpose signal generator will start my VHF circuit development in these 2 frequency bands. The importance of owning good signal generators can't be overstated — while not engineer grade, this box features a clean sine wave, strong output return loss and 1 KHz or better tuning resolution.

The center ON-OFF-ON toggle switch only turns on 1 oscillator at a time. The top 2 (ten-turn) tuning potentiometers lack knobs *(I'll get some later)* and the black knobs below them are attached to *unused* potentiometers. Initially, I planned to employ front panel gain control and drilled holes and fitted 10K pots in the chassis — I later decided to control the output power with outboard variable attenuators and skipped front panel power control for simplicity sake. Click for a side view of the unfinished project. Click for an early photo of the VCO **A** breadboard — I attached a shield to the copper clad board to help isolate the 2 VCOs.

I chose the frequency band **A** (138.5 - 172 MHz) to include the Ham 2 meter band + local commercial/service VHF segment and band **B** (98.919 - 109.06 MHz) to capture the FM broadcast band above 98 MHz.

Band A: 138.5 - 172 MHz


VHF Signal Generator A
L1
149 nH
Maxim
Max2606
1
2
3
4
5
6
2 - 10 pF
To amp
L2
L3
10
←.001→
5 VDC
12.22v
.1
3.3 pF
51
100K
.001
NP0
.001
NP0
Tune
100K
100K
138.5 – 172.1 MHZ
Peaked at 144 MHz
L2 = L3 = 303 nH *nominal*
VCO

Above — The VCO schematic **A**. An L-match peaks the output at 144 MHz into 50 Ω. The beauty of this circuit = simplicity; just 2 active devices give low distortion and a strong output return loss (S22) on the 2 Meter Ham band.


VHF Signal Generator A
12.22v
10
220
.001
.001
1K
2K
2N3906
.1
1K5
4 BFT
FT23-43
From
L-Match
22
←220→
4 dB
.01
PN5179
.01
22
←220→
4 dB
50 Ω
Amp

Above — The output amplifier for VCO "A". Click for a schematic with some analysis at 144 MHz (the frequency I'll use the most). I spent a lot of time trying to develop a 50 Ω output Z voltage amp up at ~ 144 MHz. My attempts to employ shunt and series feedback gave generally poor results — stray reactances plague the standard FBA designs that work great under ~70 MHz.

Since the MAX2606 has an output L-Match, getting a high output return was my only goal — grounding the PN5179 emitter, employing a 4:1 transmission line transformer and biasing for ~15 mA emitter current did the trick. A 4 dB pad on the NPN input further establishes a strong S22 (output return loss).

As possible, I attach additional 50 Ω outboard attenuators on my signal generators, however, the S22 on the stock generator should be okay across the VCO range due to the two 4 dB pads.

I measured the S11 on a prototype NPN amplifier by using the MAX2606 VCO shown to drive a MMIC with a 16 dB 50 Ω attenuator pad on the output and connecting it to the RF port of my return loss bridge. Thus, the actual VCO helped me design the final amplifier which buffers it in my final build. I kept the PN5179 and all other leads short as possible.

The output power looks like a sine wave when tuned from CCW to CW: With the 10-turn tuning potentiometer set to CCW [138.5 MHz], the output power ranges from -1.9 dBm; hits a peak of 0 dBm at 144 MHz and then gradually drops to -11.2 dBm at CW [172.1 MHz].

I moved away from the hycas buffer amp to simply my design and increase reproducibility. A MMIC might also work well, however the high current drain, potential for instability and biasing considerations introduce new problems — a simple wrap around PNP-biased NPN amplifier works okay. Sometimes the best solution = the simplest.

Band B: 98.919 - 109.06 MHz



Above — The VCO schematic **B**. An L-match peaks the output at 103 Mhz, although compressing or expanding L2 and tweaking the 2 -10 pF capacitor can peak the L-network anywhere in the tuning range. I limited the tuning range by adding a 4K7 R to the tuning pot to enable better matching and fine tuning.

In all cases L1 = an air inductor wound on a coarsely threaded bolt using 20 or 21 guage enamel-coated magnet wire for mechanical stability. I set the lower band edge of the VCO by setting the tuning pot to CCW and compressing or expanding the L1 inductor to get the frequency shown.

For L1, I found that excessively long leads can create unwanted oscillations and my coils are just a few mm above the copper board. Some builders properly mount their coils in a upright "smokestack" fashion and/or well away from the nearby metallic chassis or copper PCB to minimize Q losses + inductance changes. My coils lie well away from the metal chassis walls.


VHF Signal Generator B
12.22v
10
220
.001
.001
1K
2N3906
4 BFT
FT23-43
2K
1K5
.1
22
From
L-Match
←220→
4 dB
.01
PN5179
.01
18
50 Ω
←300→
3 dB
4.07 dBm @
103 MHz
Amp

Above — The VCO **B** buffer/amplifier schematic. A clean sine wave appears across the entire tuning range — output return loss tuning from minimum to maximum was > 21 dB before I added the 3 dB pad.

Click for a photo of the completed, partially labelled project during the final tune up with all the boards bolted in.

Section 3. 50 MHz VCO


VCO Block Diagram
7
MHz
VCO
0 dBm
RF
Diode
Ring
Mixer
IF
Feedback
Amp
Band-pass
Filter
Feedback
Amp
Low-pass
Filter
50 Ω
LO
43
MHz
7 dBm
Xtal Oscillator
Pad
50 MHz

Above — Block diagram of the 50 MHz VCO I designed and built in February-March 2012. Click for a photo.



Design Sources

7 MHz VCO : EMRFD
43 MHz Xtal Oscilator : Various circuits, W7ZOI web site, Rick, KK7B projects
Feedback Amps : EMRFD book and software (fba08.exe)
Triple-tuned Band-pass FL : EMRFD software (TTC08.exe)
60 MHz Low-pass FL : 1991 ARRL Handbook (from table)

Above — Like most of you, I'm just an amateur designer who relies on others for example circuits, design procedures and inspiration. These cited references plus hard work drove my experiments. This project succeeds the Miscellaneous RF Experiments web page from 2011 — QRP SWL HomeBuilder evolves as I do.

7 MHz VCO + Buffer Amplifier [0 dBM output power]


7 MHz VCO
12.22v
regulated
temp
compensator
1N5818 x2
1K
trimmer
.001
C0G
1K2
Metal Film
+
100 uF
.1
5v Reg
.001
C0G
100
J310
.001
C0G
22 pF
C0G
100 pF
poly
100K
10 turn
5K
Tune
100
100K
470
.001
C0G
.001
C0G
BB535 x6
2.3-
16.5 pF
air
5.29 uH
T50-6
100K
390 pF
C0G
140 pF
poly
390 pF
C0G
140 pF
poly
2K2
TUNES 7.0 – 7.250 MHZ

Above — 7 MHz Colpitts VCO schematic.

This VCO tunes ~7.00 to 7.250 MHz, although a wider tuning range occurs if you allow the tuning diodes to drop to 0 VDC with the 5K tuning pot cranked CCW. A 470 ohm resistor keeps about 1 VDC on the varactors at the lowest tuning frequency/applied reverse DC voltage.



Above — A macro photograph of the six BB535 varactors soldered on the VCO breadboard. With 0 applied reverse DC voltage, their total C = 43.5 pF. I left room for up to 4 more diodes, but didn't need them.

Macro photography provides an excellent way to inspect SMT parts — apart from all the fiberglass dust on the board, no shorts or other problems arose when soldering. Next to pF-value chip capacitors, these SMD varactors proved the most difficult surface-mount parts I've breadboarded to-date. Using clear tape, I tape my SMT parts to the PC board when soldering. With tape, you can still make tiny device placement adjustments with a pick or tweezers and yet the device holds steady enough to solder. I recently obtained a microscope for SMT work, although didn't need it for these diodes.

Striving for lower phase noise meant properly applying high Q tank parts — I soldered in 3 pairs of high-grade BB535 varactors and arranged them anti-parallel to avoid forward conduction + even harmonics. I also limited the AC voltage swing they "see" by connecting them to the L with a 22 pF capacitor. Tight windings of #28 gauge magnet wire on a T50-6 toroid formed the inductor. 4 number 8 bolts anchor the 7 MHz VCO board to the chassis and prevent board warp + movement.



Above — a view of the square blue 1K temperature compensation (tempco) trimmer potentiometer.

To aid temperature compensation, I included 3 polystyrene capacitors in the base VCO — the tempco circuitry represents about 16 hours of work from December 2011. Click or click for photos of the bread board before the tempco parts were soldered on — the temporatry BNC connector lies in the background was removed after testing.

With care and patience my lid-on 1 hour temperature drift = ~10 Hz. My temperature compensation strategy worked because I took the time to measure and then determine how to cancel temperature drift in this 1 circuit — your results will vary and *experimentation* remains the key to temperature compensating VCOs and VFOs.

See EMRFD, and the VFO-2011 + QRP Modules 2011 web pages for more tempco information.


7 MHz VCO Buffer
12.22v
7K5
100
.1
68
.1
.1
10K
.1
10BFT
FT37-43
1K8
trimmer
470
12t
4t
FT37-43
2K2
3K3
50 Ω
39
.1
.1
←150→
6 dB
0 dBm
.001
2N3904
.1
2N2222a
1K
d
J310
g
s
From
VCO
10 pF
100K
100
.1
4.7
120
.1
18.2 mA

Above — 7 MHz VCO buffer/amplifier. I adjusted the 10K trimmer pot on the hycas buffer for exactly 0 dBm drive. Even before adding the 6 dB attenuator pad, the output return loss = 23.8 dB @ 7.0 MHz.

Originally, I wanted a VCO output of 7 dBm and applied ~18 mA emitter current in the final amp to preserve signal fidelity and eliminate the need for a low-pass filter. This buffer works great up to an output power of ~10 dBm: above 10 dBm or so, distortion occurs and you'll need to add a low-pass filter.

Adjust the hycas trimmer pot for whatever output power you seek, but If you're ever using this buffer for 7 -10 dBm output power, drop the 6 dB attenuator pad to 3 dB. This drops the drive level to maintain low harmonic distortion (2nd harmonic down > 35 dBc).

43 MHz Butler Xtal Oscillator [6.4 dBm output power]



Above — Some Butler crystal oscillator parts prior to the build. Since this Butler will go inside a box containing a VCO and some high gain amplifiers, it would be foolish to not stick it in an RF-tight box. On the Hammond chassis above, you'll notice a feedthrough capacitor for the 12 VDC and an gold colored SMA connector for the output.

Since the required L = over 400 nH, I opted for a toroidal inductor wound on a T30-10 instead of the air coil shown in the photo.


43 MHz Butler Oscillator
.01
8v reg
12.22v
.01
.01
.01
449 nH nominal
T30-10
2K7
BF199
15 pF
170 nH
18
50 Ω
2-10 pF
68 pF
300
22 pF
3 dB
1K
.001
120
82 pF
Fund. = 14.33 MHz
3rd OT = 43.0 MHz

Above — 43 MHz Butler overtone oscillator schematic. The highest power I could muster = 6.4 dBm (close enough to 7 dBM).

This Butler looks good on FFT. Click, Click or click for 3 'scope captures. Despite trying to milk maximal power, the 2nd harmonic is over 40 dBc down. Click for a snap shot of the completed oscillator.



Above — The original Butler oscillator before adding the pi low-pass filter. The bolt (seen at top right) will also pass through the outer VCO chassis to hold this sub-chassis in place. Click for a bigger photograph.

Post-Mixer Amplifer and Triple-Tuned Filter

Post–mixer Amp and Band-pass Filter



Above — Schematic of the diode ring mixer, Q1 feedback amp and the triple-tuned filter. *I used a MCL SBL-1 mixer*. L1 - L3 were wound on T30-10 toroids. I bought my #10 and some #12 toroids from the great folks at Debco Electronics.

The post-mixer feedback amp data at 50.0 MHz (isolated from the mixer and pad + filter) : Emitter current = 18.5 mA, S21 =18 dB, S11 = -24.4 dB, S22 = - 21.5 dB. *(S21 = power gain; S11 = negative of the input return loss; S22 = negative of the output return loss).*

The 6 dB pad helps absorb signal reflections from the filter caused from stray reactance plus capacitance variations caused by coupling the 2 tanks with only 0.5 pF (2 series 1 pF capacitors with a +/- 0.25 pF tolerance!)

Preliminary filter alignment: Peak your filter however you want — but here's how I peaked my filter with a crystal controlled 50.0 MHz signal generator connected via a temporary BNC connector tack soldered onto the copper board and wired to the Q1 input. Terminate the filter with a ~50 Ω resistor, or a temporary BNC connector plugged with a 50 Ω resistive terminator.

Connect the signal generator to Q1 and peak C1, C2 and C3 (in that order) using a 10X 'scope probe. It's better measure with your probe at point C2 when tuning C1 since this reduces mistuning caused by probe capacitance — measure at point C3 when tuning C2 etc.

Then peak C3, Cx and Cy with the probe touching the terminating 50 Ω resistor. *It easier to perform the first tune-up with a 10X probe going sequentially from C1 to C3 since these peaking capacitors tune pin sharp.*

After the preliminary tune-up, if possible, connect a temporary BNC connector to the output and re-peak all the caps with a 50 Ω terminated scope; this boosts sensitivity and eliminates 'scope probe capacitance.

Perform pentultimate 50.0 Mhz alignment after you add the post-filter amp, low-pass filter and the 3 dB pad. Capacitor Cy critically sets the output return loss of Q2 and when properly matched, establishes a 50 Ω termination for the triple-tuned band-pass filter.

You can also match Cx by connecting a return loss bridge to the input of Q1 and terminating the RF chain with a 50 Ω resistor, although tuning Cx only changes the input S11 a little. In 1 experiment, I replaced Cx with 6 pF and it worked okay.

I wonder how I ever managed before making a return loss bridge: the workhorse of the QRP workbench.


Alignment Method
Cy
.01
1K5
BP Filter
FBA
LP Filter
50 Ω
1K5
.1
FBA
Q1
.01
1K
.1
100
4.7
Pad
?
RETURN LOSS BRIDGE
D
50.0 MHz

Peak Cy in the band-pass filter for the best match with your return loss bridge

Above — Schematic depicting how to tune up Cy.

Tuning Cy matches the band-pass filter output to the Q2 input impedance — it's fascinating to examine the interdependence of these 50 Ω stages. After setting Cy, I connected the 50 MHz signal generator to the Q1 input and a 50 Ω terminated 'scope to the output and re-peaked Cx, C1, C2 and C3 — finally I tweaked Cy 1 last time with the whole stage in a return loss measurement set-up.


File
About GPLA
S21 =
S11 =
S21 Ref.
top
dB
Plot
dB/div.
bottom
start
Frequency
Freq./div
stop
Click to Review Circuit
Enter #
Enter New Value
Click to load new value
Place Cursor
Cursor Data =====>
Drag a box on graph to Zoom
Zoom to Original Sweep
Save S21 as Ref.
Plot S11
Plot Referenc

top 0.

10.00 dB/div.

bottom -60.0

start 44.3 MHz 1.40 Freq./div stop 59.3 C:\Users\Tyko\Todds\QRPHB\QRPHB\20

#, part, connection, value:

```
0  Load R = 50.0
1  cap  ser  6.0000
2  ind  par  400.0000
3  cap  par  18.7300
4  cap  ser  0.5015
5  ind  par  400.0000
6  cap  par  24.1700
7  cap  ser  0.5015
8  ind  par  400.0000
9  cap  par  18.7300
10 cap  ser  6.0000
11 rlb  ser  0.0000
98 Source R = 50.0
99 Inductor Q = 150.0
```

Enter # 3 Enter New Value 18.73

Cursor Data =====> 50.125 MHz S21= -4.17 dB S11= -22.01 dB

☑ Plot S11 ☐ Plot Referenc

Above — A GPLA simulation of the triple-tuned band-pass filter. CF = 50.125 MHz. I substituted 6 pF (the nominal value) for the 2 series end capacitors in my simulation. отлично!

Post-filter Feedback Amplifer, Low-pass Filter and Pad



Above — Q2, the post filter feedback amp (FBA), an N=5 Chebyshev low-pass filter plus a 3 dB pad.

For Q2, I copied Q1 to deliver a strong input and output return loss. In many circuits employing cascaded FBAs, you increase emitter current in each successive FBA to reduce distortion, however, increasing emitter current affects both the input and output impedance and may trash your amplifier's S11 and S22.

I spent days studying, simulating + bench testing different amplifier designs in the Q2 slot — I generated enough material for another web page and plan to show this work in an update to my Popcorn superhet receiver some day.

It's possible to overdrive Q2 depending on your amplifer power and stage matching. If so, you might consider placing a 3-4 dB pad after the band-pass filter. Some might opt for a 7 element low-pass filter; experiment — as always.

Low-pass filter inductors = turns on T30-10 toroids, although #6 material toroids, or air coils will work fine.

Outputs

After bolting down the boards, wiring the DC and RF and confirming it worked, I finalized alignment. Using a frequency counter, I tuned the VCO to 50.125 MHz (the half-way point) and peaked C1, C2, C3 for the maximum peak-peak voltage into my 50 Ω terminated 'scope.

Click for the output at 50.125 MHz — 10.09 dBm. I normally hang an outboard 50 Ω attenuator on the output of my signal generators and keep 3 dB, 6 dB, 10 dB and 20 dB BNC-connected pads handy. With a 3 dB pad, the output power = 6.84 dBm — perfect for switching Level 7 diode ring mixers. Click for the 'scope shot with a 3 dB pad applied.

Click or click for an FFT of the output signal. The second harmonic is > 50 dB down. What fun!

The "vestigial" RF gain control shown on the chassis remains unused; wastage.

Miscellaneous Photos and Figures


Post-mixer Amp and Band-pass Filter
Feb 27, 2012
diode
ring mixer
RF
IF
LO
S11 = 13 dB
.01
RFC
120
16.2 mA
s
d
g
J310
.01
L1
4K7
51
12.22v
.01
C1
1 pF
C2
L2
1 pF
1 pF
C3
L3
1 pF
to
hycas
RFC = 5 turns FT23-43 (~4.2 uH)
C1 = C2 = C3 = 12- 60 pF trimmer cap
L1 = L2 = L3 = 280 nH (T30-10 toroid)

Above — A **failed** experimental JFET post-mixer amp with tuned output driving a double-tuned filter.

Click for a GPLA simulation of the double-tuned filter. The common gate JFET amp provides a great way to terminate a diode ring and obviates the need for a diplexer network. Click for a breadboard photo of the above stage.

The amplifier input match @ 50 MHz is only ~ 13 dB, however, we're not interested in a narrow band match — the tuned output network makes strong input matching at 50 MHz impossible *(for me at least)* without additional L and C (narrow band components that we don't want!). I tried a few tapped inductor schemes, however, at VHF, adding turns added significant capacitance and things got ugly fast.

The common gate JFET amp/filter goof-up shattered my expectations. The 4K7 input/output impedance drove instability through unwanted coupling between the inductors. I learned my lesson: at or above 50 MHz, *stick to 50 Ω stages* for stability.

OFF
50
Ω
ON
GAIN
TUNE


.01
12.22v
.01
.1
2K7
BF199
170 nH
18
68 pF
300
3 dB
2-10 pF
1K
120
Fund. = 14.33 MHz
3rd OT = 43.0 MHz

Section 4. 50 MHz Receiver Pre-amp and Filter


50 MHz Band-pass Stage
12.22v
51
.01
.01
18 pF
570 nH
J310
L1
17.8 pF
C4
50 Ω
50 Ω
C1
100 pF
100 pF
5t FT23-43
1 pF
1 pF
C2
L2
C3
7.3 pF
180
S11 = 16.8 dB
S22 = 30 dB
S21 = 10.1 dB
12.3 mA
C1= C2 = C3 = 5-25 pF
C4 = 3 -12 pF
L1 = L2 = 400 nH

Above — A 50 MHz receiver front end filter with embedded common gate amplifer.

Inspired by the General Purpose Monoband Receiver Front End from Figure 6.69 in EMRFD, I applied inductive and capacitive reactance modeling, DTC08, Ladbuild08 and GPLA08 from the EMRFD ladpac series and built a 50 MHz equivalent.

Connect an antenna to the input and a 50 Ω impedance mixer to the output.

I tested the stage at 50.0 MHz and wound my inductors on T30-10 toroids, although #6 material cores would work okay. You'll find all the measurement techniques in my RF Workbench series 1-4 available though the top-level menu.



top: 0.
10.00 dB/div.
bottom: -60.0

#, part, connection, value:
0 Load R = 50.0
1 cap par 100.0000
2 ind ser 570.0000
3 cap ser 23.3000
4 cap par 100.0000
5 rlb ser 0.0000
98 Source R = 50.0
99 Inductor Q = 150.0

Enter #: 3
Enter New Value: 23.3

start 0.00 Frequency MHz 20 Freq./div stop 200 C:\Users\Tyko\Todds\QRPHB\QRPHB\20

Cursor Data =====> 50.000 MHz S21= -0.39 dB S11= -19.81 dB

Above — GPLA simulation of the peaked low-pass filter "built" in Ladbuild08.

Wes often employs a peaked low-pass filter and after studying his work, I can see why — way better attenuation than a simple 3 element low-pass filter. The FM broadcast band runs from about 87.5 to 108 MHz and in Russia, they call it "YKB" (Ультракороткие волны) or ultra-shortwave. At 87.5 MHz, attenuation = 25 dB; pretty good for such a simple filter. At 144 MHz, filter attenuation rises to ~ 40 dB.

This peaked low-pass filter acts as a preselector for the JFET amp that follows it. *Please read the text describing Figure 6.69 in EMRFD for some great notes by Wes.*

In the simulation above, a 50.0 MHz peak response occurred with C1 at 23.3 pF, while in my real circuit, the capacitor was set to ~ 18 pF. Stray L and C + the input Z of the JFET amp caused this variance, but assuredly; GPLA gets you close.

To peak the low-pass filter, I connected a return loss bridge to the input port and tweaked C1 for the lowest possible peak-peak voltage (tuned for the the best return loss which = 16.8 dB in my circuit). *You may also compress or expand the 540 nH inductor to aid tweaking.*

Since common gate amplifiers often exhibit a lower noise figure with a slight mismatch, an S11 of -16.8 dB works fine .I wish I had the gear to set the input match for the lowest possible noise figure — perhaps 1 day I will.


General Purpose Ladder Analysis, 2008
File
About GPLA
S21 =
S11 =
S21 Ref.
top
dB
Plot
dB/div.
bottom
Click to Review Circuit
Enter #
Enter New Value
Click to load new value
Frequency
Freq./div
Place Cursor
Cursor Data =====>

#, part, connection, value:

0 Load R = 50.0
1 cap ser 6.0000
2 ind par 400.0000
3 cap par 18.9000
4 cap ser 0.5000
5 cap par 18.9000
6 ind par 400.0000
7 cap ser 6.0000
8 rlb ser 0.0000
98 Source R = 50.0
99 Inductor Q = 150.0

march 5/12

top: 0.0
dB/div: 10.00
bottom: -60.0
Enter #: 3
Enter New Value: 18.9
start: 40.00 MHz
Freq./div: 2.0
stop: 60
C:\Users\Tyko\Todds\QRPHB\QRPHB\20
Cursor Data: 49.987 MHz
S21= -2.89 dB
S11= -26.86 dB

Above — A GPLA simulation of the 50 MHz double tuned band-pass filter "built" in DTC08. The bandwidth = ~1.8 MHz and varies slightly with the tuning of C4.

I peaked both C2 and C3 with a 50 Ω signal generator and a 50 Ω terminated scope connected to the input and output ports respectively.

Next, I connected my return loss bridge to the output and tweaked C3 and C4 for the lowest peak-peak voltage — the best return loss — and since you tweak 2 capacitors, a strong output return loss delights you.

Finally, I measured the peak-peak voltage with the amp in-line, and after removed the amp and reconnected the 50 Ω cables with a through-connector. Inputting the 2 pk-pk voltages into Applet H on the Design Center web page gave a gain *or S21* of 10.1 dB. I repeated all of the steps above a couple more times to ensure I had set C2, C3 and C4 perfectly.

I found tuning the resonators difficult due to the sharp tuning and wide capacitance range of C1-C3. Assuming your tanks are peaked, the best amplifier gain correlated to the highest input and output port return loss. Have I stressed the importance of a return loss bridge enough?

10.1 dB gain should be enough gain for listening to terrestrial 6 Meter band signals with my 5 element Yagi antenna.



Above — A photo of my protoype 50 MHz pre-amp breadboard. In my "keeper" version, I'll swap in a U310 JFET and bias it for ~15 mA.

Section 5. QRP — POSDATA: Z-Communications VCO Experiment

Looking on eBay, sellers list numerous VCOs, although most are surface mount and go well above VHF. My favorite VCO comes from Mini-Circuits Labs: the POS series. Click for an example: the POS-75. These "plug- in" VCOs come in same package as the SBL-1 mixer and are likely obsolete, but still for sale. If you're building a frequency synthesizer with low phase noise requirements, MCL VCOs seem hard to beat. You can still order them from MCL, but the high product and shipping costs might alarm you.

I've looked for cheaper alternatives and the Z-Comm VCO raises 1 possibility. Last year, I purchased a V149MEM1 device for 5 dollars including shipping. Some experiments follow:



Above — My first breadboard. Lacking the MINI-16 receptable, like with MCL POS VCOs: I turned it upside down and soldered the metal case to my ground plane. If I were to keep this circuit. I wound solder all 4 sides to the copper clad board, plus run some copper de-soldering brade from the bottom to the ground plane, or even cut a square hole and flush mounted the VCO on is back.

While mounting it upside down deviates from the recommendations found on the Z-Comm mounting datasheet, I fiigured that for VHF at least, it might work okay. We desire low inductance grounding, but creativity might allow dead bug construction techniques to work.


12.22v
22
1nF
1nF
LM78L05
1 nF
+
10 µF
220 nH
220
1 nF
VCC
330
3K3
Total stage I = 23.5 mA
MPSH10
RF
47
BOTTOM VIEW
1 nF
MPSH10
10
27
120
10
10
0.5 - 4.5 tuning V
Tune
10K
V max
1K
1nF
C0G
14.4 dB loss L-pad
1 nF
1K2
270
1nF
47
3.8 mA
100K
Manual tune
100K
Ramp in
50 Ω
1nF
13K
V min
Z-Comm VCO: V149MEM1

Above — My complete VCO. The Z-comm VCOs require at least a 10 dB pad on the output to keep port return loss high. Without a pad, you might see something like this plus boost the phase noise. In my circuit, I applied a resistor L-network with ~ 14.3 dB loss to pad the output and provide a match into a common base amp with an input impedance of ~ 6.8 Ω.

The 2-stage buffer is the brainchild of Bob, K3NHI and I love it. This buffer features a common base stage driving a emitter follower yielding high bandwidth and great reverse isolation. Normally, at VHF, the buffer is followed by more such stage(s), or a MMIC. The 220 nH inductor wound on a T30-12 toroid improves the high frequency response of the common base amplifer — experiment with this L to suit whatever VCO you wish to buffer. The gain of the 2 amp buffer is typically around 9 dB and the return loss at the input and output ports lies under 11 dB, so apply attenuator pads to boost S11/S22 as required.

Click for the scope tracing at 0.5 VDC tuning voltage. Click for the 4.5 VDC tuning voltage 'scope tracing. The harmonic distortion at the lowest tuning voltage = ~ -19 dBc and decreases to -28 dBc at the highest tuning voltage; better than specified. Notice that power decreases as frequency increases. All the commercial VCOs I tested do this. A higher fT amp like the PN5179 or other BJT might be a better choice to offset the power change versus frequency *contribution* of the buffer/amp.

For a sweep circuit, I would mix this VCO with another low level, single frequency VCO with its current controlled by a downstream leveling circut to derive a flat amplitude over the range of the VCO. I plan to try the Z- Comm V150S015 in such an arrangement to make a 70 - 150 MHz VCO for sweeping.

Please refer to the datasheet for the pin out on the Z-Comm VCO: I chose the pinout shown in the schematic to make an efficient drawing. The two 10 Ω resistors in the buffer/amp snub UHF oscillations first measured by Bob and confirmed by me. Ferrite beads might work as alternates.

Section 6. Miscellaneous Photos


VHF SIGNAL GENERATOR
138-172 MHz
50Ω
T
ON | ON
OFF
T
98-109 MHZ
50Ω


OFF
ON

MALE TERMINATOR 50Ω

RF — Test and Measurement

HF Ragbag



It's easier to present short topics on catch-all web pages — HF Ragbag shows some 2012 non-VHF experiments in no particular order. I also share thoughts on circuit building and writing: we can think and work better.

1. Comments from the Workbench - The Need for Clarity

On Building

In 2012, I boosted my circuit and writing quality to improve your experience: a genuine, return-to-basics approach in amateur, component-level electronic design. As possible, RF circuits will feature 50 Ω input and output ports — totally adopting a 50 Ω environment — for I'm convinced this is the best way to go. The 50 Ω building and measuring standard offers much: an easy-to-interface modular approach; 10 dB improved sensitivity over a 10X 'scope probe and if wanted, measurement with commercial or homebrew test equipment such as a spectrum analyzer, network analyzer or RF power meter.

Like many, I started out by collecting and copying circuits with little emphasis on true understanding. I wanted a completed circuit — quickly as possible — failing to develop my design skills. Without design skills honed by studying and properly measuring our circuits, we bide in hit-and-miss electronics — a frustrating repetition of trial and error, over and over again. We ought to adopt the attitude and thinking of engineers while keeping our design work —including the math — fun. However, embracing scratch-homebrew electronics with the overall goal of trying to understand each stage takes effort. "There is no substitute for hard work" wrote Thomas A. Edison. Scratch homebrew involves reading, simulating, collecting parts, mastering new techniques and building or buying test equipment.

This is more than knack, an abused noun that often means "hack". Our key tasks: to measure, analyze and understand the circuits we copy or create takes patience and practice. Dissecting circuits to understand their function means to hypothesize and reflect — to apply science on paper, with software, and finally, through careful bench experiments. Often we lack the math skills or test equipment to fully investigate some aspects of our circuits, but try our best: measure what we can measure, seek help and grow. I hope this site shows our hobby can be less about making stuff and more about the rewards of actual design: an authentic, personal journey to get better at something you love.

I've never been much of a kit builder; it's too much like Max Klein's Paint by Number for my tastes. But kits dominate HF QRP homebrew and may offer a cost effective way to make gear; especially test gear. Stuffing parts in a printed circuit board won't teach you much about design, but might get your feet wet. Some people remain perfectly happy building kits or madly copying circuits — all the power to you! Do whatever you want. One day you might awaken, but don't worry; I won't try to goad, or convince you.

My favorite builders include people over 50 who suffer the often crippling symptoms of 'appliance apathy' — an epiphany reminds them why they first got into radio: homebrew experiences. Maybe a crystal radio set, or a simple superhet receiver they breadboarded long ago. *Then they come back full circle*; like a loop antenna. Oh-boy — "Bob" rediscovered his radio roots and needs to unleash his creativity and passion to learn and improve. I write for people like Bob. Heck; I am Bob.

On Writing

You'll notice improved narrative writing too: I prefer to read and write crisp statements in short sentences and paragraphs. Brief, yet descriptive text accompanied by ample white space, clear headings and bulleted lists invites you to read on. Plain language writing — simple, clear, writing that is easy to read and understand — signals a refreshing move away from the turgid, word-filled claptrap I learned in grade school. Making your prose easier to read requires greater effort writing and re-writing. My first..to...fourth drafts always suck.

Passive verbs, or nouns and adjectives that function as verbs with no clear subject confuses readers and boosts wordiness: I employ active verbs to invigorate my writing — active verbs connote me or some else performing an activity you can visualize or feel. Actions that may inspire, persuade, or even vex you! Ours' is an emotional hobby.

RF electronics contains rich amounts of jargon. Of course, we must learn some jargon to communicate our ideas as hobbyists, but writing jargon to impress, or to place yourself above others lacks humility and alienates people. Do you know anyone who likes being talked down to? The first step towards becoming humble is to admit you're not humble and then work on it — and I'm working on it.

Although I enjoy writing about electronic experiments, I'm not sure it's worthwhile — Does anyone actually design circuits anymore? Well, back to my 1970's-style analog experiments...

---

2. Magnitude Only Scattering-Parameters



2 Port Scattering Matrix —
Magnitude only S-parameters

S11 - Excite Port 1 and assess the reflection at Port 1 (Negative of return loss)
S12 - Excite Port 2 and assess the response at Port 1 (Reverse gain)
S21 - Excite Port 1 and assess the response at Port 2 (Forward gain)
S22 - Excite Port 2 and assess the reflection at Port 2 (Negative of return loss)

Above — A simple model describing the S-parameters displayed on QRP / SWL HomeBuilder in a Class A amplifer with 50 Ω ports.

S-Parameters

Any device with 2 connectors may be modelled at AC for a specified frequency with just 4 scattering parameters: forward gain, reverse gain + input and output impedance (match or VSWR).

S-parameters address voltage ratios: comparing the amplitude of different signals at the 2 ports. For example, S21 is the magnitude of forward gain and equals the ratio of output voltage to input voltage.

S-parameters are vectors; a mathematical quantity that may be visualized as an arrow anchored at 1 end that pivots around its base. The length of the arrow represents magnitude while the angle it makes with another vector or its base line decribes its phase in degrees. In addition to phase and magnitude, S-parameters allow analysis of gain, stability, complex impedance (resistance + reactance), admittance and other vector quantities.

Measure S-parameters with all ports terminated in a 50 Ω impedance.

Some of us worry only about the gain, losses or "match" in our 50 Ω circuits and could care less how the signal phase changes as it passes through our amplifiers or attenuators. I express only S-parameter magnitude in logarithmic form (dB) and take this *Über simplified* approach because builders can easily measure S11, S12, S21 and S22 on a 50 Ω test bench with a small staple of bench accessories + a 50 Ω 'scope or detector.

Topics like matrix theory, vector math, the "jay" operator, converting S-parameters into other matrices, Smith charts etc. may turn *off* the average amateur designer. You advanced readers, may raise your 2 port network skills by visiting better web sites + reading books, simulating with SPICE, or better yet, measuring your port parameters with a vector network analyzer.

---

3. More on Feedback Amplifiers (FBA)

Many builders (myself included) copy feedback amps rather than design their own. By tweaking the emitter current, shunt and series feedback while measuring S11 and S22, plus simulating with a program called FBA08.exe, I've learned it's possible to design good feedback amps FBA08 is 1 of the Ladpac programs that ships with EMRFD.

I wanted a FBA with ~35 mA emitter current for improved IMD and low distortion on strong signals. Such an amp might follow a diode ring mixer in a receiver I.F. chain.


FBA
File
About FBA
Feedback Amplifier Analysis
Change R-feedback
+
-
Input
Source R
N:1 Ideal
Z_{OUT}
Z_{IN}
R_L
R_L *
nH
pF
mA
Edit Circuit and Transistor; click "Calculate" or "Change"
Change R-E
+
-
Calculate

Transistor Parameters : DC Beta 100 F-t, MHz 1000 Rb' 10 C col-base, pF 5

F, MHz 7

10000 pF

10 nH

1500

50

N = 2

R_L = 50

I_E = 35 mA

6.2

5 nH

Gain (dB)= 21.911

Z-in = 50.090 +j -10.586 Input Return Loss = 19.562 dB

Z-out = 183.490 +j -53.365 Output Return Loss = 16.816 dB

Above — My 7 MHz FBA set up. Wes, W7ZOI suggested using 5 nH as the default emitter inductance and 10 nH for the default collector to base inductance in FBA08. These represent stray inductances in your circuit breadboard. Emitter inductance affects the input impedance more.

Zin = input impedance. Zout = output impedance.

Explore this program to learn how changing the emitter resistor, feedback resistor and emitter current affect the input and output return loss.

Adjusting the transformer N and load values only affect the calculations for Zin because this app wasn't really designed to crunch output transformer Z ratios for Zout manipulation. The default output Z = 200 Ω and thus for the N parameter with a 50 Ω RL, RL is multiplied by N^2 to set the amplifer load impedance.

From FBA08 simulations: with an emitter current of 35 mA, my series feedback = 6.2 Ω and shunt feedback = 1500 Ω.

I chose a simple voltage divider bias network to set up the ~35 ma and ensure reasonable temperature stability.



VCC = 11.4
R1 = 1500.0
RC = 0.0
R2 = 1000.0
RE = 100.0
beta = 150
VBE = 0.70

○ R1 ● RC
○ R2 ○ RE

11.4

```
-------------------------------
DC Bias Calculations
-------------------------------
Transistor beta = 150
R1 = 1500 ohms
R2 = 1000 ohms
RC = 0 ohms
RE = 100 ohms

Bias Currents:

IB = 245.859876 uA
IC = 36.878981 mA
IE = 37.124842 mA

Bias Voltages:

VE = 3.712484 volts
VB = 4.412484 volts
VC = 11.400000 volts
VCE = 7.687515 volts
VCC = 11.40 volts
VBE = 0.70 volts
```

Above — Choosing the emitter and nearest standard value bias network resistors to set up ~ 35 mA emitter current with a program. Actual biasing requires you to set up the correct emitter current + establish reasonable temperature stability.

Click and scroll to #5 for some basic transistor biasing notes. While this supplement shows a simple method for stable bias networks, it probably understates that **Beta** bias stabiility is a function of the ratio of RB to RE, where RB = the 2 base resistors in parallel. The lower the ratio the better, but then more input power is lost in those resistors. A higher ratio reduces stability but wastes less input power — another trade off we must negotiate! See Ken Kuhn's web site for thorough, expert-level information on voltage divider biasing your BJT amplifiers.

I use NPN DC BIAS, a program I wrote, however, Wes included 1 in the Ladpac software called Biasnpn08.exe that's also good. Determine the VC for the program by first multiplying the value of your decoupling resistor by the emitter current in Amperes to learn the voltage drop across the R. Then, subtract that voltage drop from your power supply voltage: 12.22V - (.0371 A X 22 ohms) = 11.4 VDC.

Our software allows you to pick approximate base and emitter resistor values to set up a desired current in your amplifier breadboard, but you must still choose reasonable values for temperature stability. Tweak them as needed, or choose some other bias method such as a current source. Let's move to the bench...


FBA #1
12.21v
22
.1
.1
11.34v
10 BFT
FT37-43
.1
50 Ω
1K5
1K5
.1
2N3866
50 Ω
.1
4.17v
3.44v
1K
100
.1
4.7
35.2 mA
Tested at 7 MHz
S21= 21.8 dB
S11 = - 35.6 dB
S22 = - 19.2

Above — My 7 MHz FBA with some measured S-parameters. On the bench, I lowered the 6.2 Ω series resistor to 4.7 Ω because the voltage divider bias network also affected Z in. I tried 3.3, 4.7 and 5.7 Ω resistors for series feedback and settled on 4.7 Ω since an S11 of -35.6 dB wins the prize!

The S22 of -19.2 dB bettered the value predicted by FBA and seems quite acceptable considering we normally follow a FBA with a 6 dB pad that raises the output return loss another 12 dB. FBA08 gets you close, however, only bench experiments will realize the amplifer you want, and sometimes, a decent S11 and/or S22 may elude you.



Above — A photo of the 35 mA feedback amp built on scrap of copper clad board.

Parallel Transistor Feedback Amp


12.21v
15
.1
11.50v
.1
8t FT37-43
.1
50 Ω
FBA #2
1K
560
.1
.1
50 Ω
4.93v
2N5109
820
5.6
5.6
1
1
Tested at
10.0 MHz
S21 = 18.4 dB
S11 = 21.4 dB
S22 = 20.9 dB
100
4.07v
.1
41.6 mA

Above — A feedback amp with two 2N5109 transistors wired in parallel. Click for a photograph of this prototype. I lacked 6.8 Ω resistors and placed 1 Ω + 5.6 Ω to make the needed R for a strong S11.

Originally, I built FBA #2 with a 4:1 Z transmission line transformer, but measurements of S22 disppointed me. Later, a L wound with 8 turns around an FT37-43 ferrite toroid drove an S22 of 24 dB, but S11 was only 18.5 dB.

With the amp set up to measure return loss on the input port, I placed a 500 Ω potentiometer in series with a 100 Ω resistor between the collector and base terminals and tweaked the pot to obtain the lowest peak-peak voltage in my 'scope (lowest return loss). After, I removed the pot and measured its resistance at 572 Ω. Finally, I soldered in a 560 Ω resistor and re-checked S11. Perfect. With my goal of at least 20 dB for S11 and S22 obtained, I powered down my bench and took some photos.

Wes, W7ZOI displayed parallel transistor FBAs in EMRFD and other works and recently I noticed Lyle, KK7P employed a parallel NE46134 FBA as a post-mixer amplifer in the Elecraft K3.

Wes wired 2 parallel 2N3904s to avoid using an expensive medium power BJT like the 2N5109. Doing so splits the heat between 2 devices, but does not deliver better IMD performance beyond what is offered by increasing the emitter current. In a typical FBA bias setup, you may measure as much as 10 volts between the collector and emitter terminals and with a supply of 12 VDC + a standing current of 20 mA, the collector dissipation = ~200 mW. This is about maximum for a TO-92 device likes a 2N3904, but only half of maximal dissipation for 2 in parallel.

Then, too, the K3 applies 2 parallel medium power BJTs get power dissipation with an SMT transistor. For strong IMD performance, Lyle and crew are throwing 80 mA or so into the pair — hard to do with SMT parts, so they overcome heat and power dissipation issues with 2 devices. Cool (literally).

Heat sink BJTs when you crank up the emitter current.



Above — An attempted 2N3904-based parallel feedback amp. Each BJT draws ~21 mA emitter current. Without the 6 dB output pad, the output return loss = 14 dB — I *failed* to realize both a strong (raw) S11 and S22.

The power gain including the 6 dB pad = 10.5 dB. I'll discard this design since it's substandard — without failures, victory may taste bland.

For bench designers, making a parallel FBA where both the raw S11 and S21 are > 20 dB is difficult and bench failures may either frusturate you, or enhance your resolve to succeed. With success, great satisfaction arises and I'm addicted to that feeling.

An FBA bench triumph means you managed to establish the perfect combination of series + shunt feedback, emitter current and the correct output transformer ratio for *that* transistor plus its biasing circuitry — no small task.

A well matched amplifier = a thing of beauty! The fetching trio of high S11, S22 and S21 rewards your efforts and boosts your confidence to experiment further. And so it goes...

Sadly, only a fraction of hobbyists create and evaluate their own circuits.

---

4. Microphonics in Direct Conversion Receivers

LO = local oscillator or VFO. DC Receiver = direct conversion receiver.

Microphonics are induced electrical responses that arise from a mechanical vibration on the DC receiver chassis or circuitry. The audio amp, acting like a transducer, makes a clicking, or popping noise when you do things like tap the chassis, or unplug components — the disturbance throws out a burst of DC voltage that's amplifed by the AF chain and pops the speaker.

We may read or hear inexperienced builders tell us to expect microphonics in our DC receivers — *de trop* folklore strikes again! As a student of EMRFD and those wise designers who live in and around Beaverton, Oregon, I share some of their best tips to decrease microphonics in your DC receiver projects. " Keep Your LO From Radiating to the Outside World and Keep Unwanted RF from the Outside World Getting Into Your Receiver” seems the appropos title for the bulleted notes that follow:

Read EMRFD pages 8.7 to 8.11 and then build or apply the presented examples. Wisdom is experiential; it comes by doing, not just reading. It's no accident that Chapter 8 author Rick, KK7B mentions microphonics and hum in the same section. I've never read more thorough notes regarding DC receiver nuances anywhere; for example, did you consider that an ungrounded air variable capacitor shaft poking outside the LO box will radiate LO signal per Figure 8.18 ? I didn't in my early days.

Stick your LO in a RF-tight enclosure with RF-grade connectors and coax to patch the AC signal to the product detector. Bypass RF with feedthrough capacitors on any DC voltage lines that pass through the LO chassis wall. Many enthusiasts have only operated kitted or homebrew DC receivers where the LO and receiver guts lie on the same circuit board — this *ensures* microphonics. Wes and Roger built the historic Ugly Weekender VFO, transmitter and receiver in seperate boxes — resulting in low microphonics and no pulling of the VFO when keying the transmitter. Nothing in that 2 part QST series was done by accident. Read these articles to "go to school".

Reciprocally important; keep unwanted outside world RF from getting inside your DC receiver! Apply resistors plus capacitors, or inductors plus capacitors to decouple and bypass RF from moving along on your DC voltage lines, key line, microphone cables etc.

Keep product detector port-to-port isolation high. Typically, we employ double balanced mixers to obtain high port-to-port isolation. I cover mixer balance on this page . For diode ring mixers, measure the return loss of the circuits that you connect to the product detector LO, RF and AF ports — I aim for 20 dB or greater return loss on my LO output, RF output and AF amp input circuits to help preserve the product detector balance and keep port isolation as high as possible. Along with 50 Ω amplifers, attach attenuator pads, AF diplexers, or whatever to help increase port return loss as required.

LO-RF port isolation: Consider a common gate amp with an output matching network to get a high output return loss (S22). The common gate amp provides strong reverse isolation without adding much noise.

Avoid end-fed wire antennas where there is a strong antenna field right next to your radio.

I favor sturdy chassis/cabinets with rubber feet. Homebrew copper clad board or die-cast aluminum cabinets may work best as joints and screwed connections won’t corrode. *This is a weak recommendation.*

Double the LO frequency or apply a heterodyne VFO. Often microphonics arise in the VFO tank. EMRFD cover this well. If the VFO operates at a significantly different frequency than any of the signals reaching the balanced mixer, leaked LO won't cause as much havoc as when a LO tank is tuned to the mixer RF port frequency.

Despite proper techniques, RF can exit via the antenna port and make its back into our rig through power supply cables (often modulated by our house AC electricity). In some cases, we require special power supply decoupling to decrease hum and microphonics. We might need to add a common mode choke (+/- capacitors) for common mode noise suppression in addition to the usual differential mode choke(s) and capacitors. In my main shack power supply, I run a common-mode choke plus I soldered a 0.01 uF capacitor across each bridge rectifier diode to bypass RF.

Some radio operators just run battery power supplies.

Above — Feedthrough capacitors. I prefer hole mount over solder mount parts, however, quality feedthrough capacitors of any kind tend to be expensive. As a hobbyist, I'm constantly searching for bargains and when I find 1, I'll purchase a bunch to meet my current and future needs.



Above — Some double balanced mixers from my collection: ADE-1, NE602, TUF-1, TUF-2, SBL-1 and a SRA-173H; a MiniCircuit Lab's Level 17 diode ring mixer.

You owe it to yourself to listen to a DC receiver designed and built to reduce microphonics — music to our ears.

---

5. Some Experiments with RF Bypass Capacitors

Introduction

Bypass implies a low impedance path to ground for RF at 1 or more frequencies. After reading EMRFD pages 2.28 - 2.31, I decided to explore this subject for the first time. My bench measurements from Spring 2012 punctuated how little I knew about RF bypass and I share these notes as something for me and others to build on.

In these experiments, I

1. observed the self resonant frequency of MuRata RPE Series, 50v, 5% capacitors with X7R temp compensation at 0.1, 0.01 and 0.001 µF.
2. examined a wire short, plus 1 and then 2 Johanson Dielectric 0.01µF, 50v, X7R, size 1206 chip capacitors.
3. tested a 0.1 µF RF cap plus a parallel 2.2 µF electrolytic capacitor to look at parallel resonance side effects.
4. attempted to reduce the Q of some parallel capacitors to reduce unwanted high impedance peaks.



Above — The frequency dependent components of a capacitor are shown in this capacitor equivalent circuit schematic; essentially an RLC network. Engineers use mathematical formulae to describe the components of a capacitor along with reactance and with this math, you might derive an unknown variable from available data so it's worth diving into on your own.

ESR or equivalent series resistance = the sum of all of a capacitors' resistive components. Expressed in ohms, ESR acts like a resistor in series with the capacitor. Normally we desire capacitors with an ESR as low as possible. Consider reading the capacitor datasheets for those your stock and/or searching for information regarding low ESR capacitors on the Internet.

ESL refers to the equivalent series inductance; the sum of all the capacitor's inductive components. This includes lead length in hole-through parts.

In a given capacitor, the series resonant frequency is the frequency where the inductive reactance from the ESL = the capacitive reactance, but since the 2 reactances are 180 degrees opposite in phase, they cancel to drop the impedance to 0 and the capacitor acts like a resistor at its ESR.

The series inductance of a capacitor may be determined using a network analyzer and unfortunately this in unattainable by most average builders. When designing RF bypass with network analysis, we strive for a low impedance over a wide frequency range, although small ripples typically occur.



Above — A plot of equivalent series inductance. ESR tends to increase with frequency.

Methods



Above — My test set up. I performed all analysis with a tracking generator plus spectrum analyzer. The 50 Ω system used short coax patch cables fitted with BNC connectors with 20 dB attenuator pads before and after the capacitors under test. The capacitors shown as C0 and C1 were soldered on a copper board with short leads and BNC connectors. C1 is omitted when evaluating only 1 capacitor.

You may also perform capacitor self resonant frequency testing with a vector network analyzer, a signal generator plus a 50 Ω terminated scope, or with a sweep generator ramp-driving the oscilloscope X input while simultaneously driving a VCO with logarithmic output to the Y oscilloscope input. SPICE simulations may also yield insight.



Above — The -27 dBm reference with a through-connector between my 2 coax patch cables (C0 + C1 board removed).
To save time I shot these SA photos handheld and prefer a slower shutter to capture a nice CRT tracing, so some of the photos show a little hand jitter.

Single Shunt Capacitors



Above — C0 = 0.1 µF. I view the capacitor like a trap. At almost 5.8 MHz lies the peak attenuation, or lowest impedance — this is C0's self resonant frequency. The peak bypass frequency lies ~ 60 dB down. At 20 MHz, the attenuation is only ~ 30 dB.



Above — Another shot of the 0.1 µF bypass cap with a 200 MHz span. At 50 MHz, the reference signal lies only ~ 17 dB down. At 100 MHz, the attenuation is only ~ 11 dB — this hardly qualifies as “bypass” much above the self resonant frequency. Above the self resonant frequency, a capacitor's XL affects impedance more than the ESR and XC of the capacitor.



Above — C0 = 0.01 µF. The peak bypass frequency (capacitor self resonant frequency) is centered at 17.5 MHz and is ~ 50 dB down; not as deep as with the 0.1 µf cap. At 50 MHz, the attenuation is ~ 21 dB.



Above — C0 = 0.001. The response is peaked at 62 MHz with an attenuation of ~42 dB. At 100 MHz, the signal is 17 dB down. Again, the peak attenuation looks diminished compared to that of the 0.1 µF and the 0.01µF caps.

Capacitors in Parallel

Now I placed 2 caps in parallel (C0 + C1) as some builders do to try and garner a wider attenuation bandwidth.



Above — C0 = 0.1 µF + C1 = 0.1 µF. The peak attenuation = 60 dB at 8 MHz; up 2 MHz from that of the single 0.1 µf capacitor. At 100 MHz, attenuation = ~ 19 dB — better than a single 0.1 µF but still low.



Above — C0 = 0.1 µF + C1 = 0.01 µF. Yikes! With the 2 different cap values, we get an unfortunate high impedance blip peaking at 13 MHz. Each capacitor exerts its self resonant frequency, but in between these self resonant frequencies, lies a disaster.
When placed in parallel, the inductance of 1 capacitor resonates with the capacitance of the other to form a parallel resonance — leading to a high impedance — that blocks RF bypass and peaks at a specific frequency.

But wait. Things can get worse:



Above — C0 = 0.1 µF + C1 = 0.001 µF. The wide value variance between these 2 capacitors creates a huge, high impedance spike where the attenuation is only about 6 dB at 40 MHz. Catastrophic bypass indeed. катастрофа.

A 7 mm Length of Copper Wire



Above — A 7 mm piece of 26 gauge copper wire was shorted to ground instead of C0. This wire measured at ~7 nH of inductance and I saw that attenuation decreases with frequency from 62 dB at 8 MHz to ~33 dB at 20 MHz. Even a short piece of wire doesn't exhibit a flat, wideband bypass.



Above — This spectrum analysis shows three 7 mm wires shunted to ground – not much different than 1 wire.

0.01 µF Chip Capacitor(s)



Above — The magnified copper board that I tested one or two 0.01 µF chip capacitors. You can see 1 capacitor soldered in.



Above — C0 = 0.01 µF SMT cap. The SMT parts exhibited a peak attenuation of 45 dB at ~37 MHz. The attenuation dip lacks the sharp peak of the hole-through 0.01 µF cap shown eariler and exhibits a somewhat wider bandwidth. The self resonant frequency of the chip capacitor is 5 MHz higher than the particular hole-through capacitor I measured. Click for a side by side photo.



Above — C0 = 0.01 µF + C1 = 0.01 µF. The SMT parts exhibited a peak attenuation of 45 dB at ~37 MHz; similar to the single 0.01 µ F chip cap, but with a few more dB attenuation between 10 and 20 MHz.

0.1 µF Ceramic + a 2.2 µF Electrolytic Capacitor



Above — C0 = 0.1 µF and C1 = 2.2 µF. The low Q 2.2 µF C1 electrolytic cap did not create the a parallel resonance with C0. Shaky photo — sorry. I also tested a 10 and 22 µF cap in parallel with C0 and saw no disturbance caused by a parallel resonance between a big AF capacitor and C0 (an RF value cap) with my RF spectrum analyzer.

Some additional experiments applying a low Q *A*F capacitor plus a ceramic *RF* capacitor for wideband bypass yielded some interesting results and I'll present these in a future project.

Capacitors in Parallel with a Series Resistor to Lower Q

In previous experiments, placing 2 RF capacitors in parallel led to the formation of a peaked high impedance blip between the low impedance peaks set by the self-resonant frequency of the 2 capacitors. If multiple capacitors are soldered in parallel, the series inductance of each capacitor will resonate with the capacitance of the next smaller C value.

One solution is to put a resistance in series with all but 1 of the parallel capacitors so that the Q of resonance formed by this capacitor's series inductance and the capacitance of the next smaller capacitor is low. If capacitors exhibited 0 inductance then putting capacitors in parallel would be fine, however, since capacitors exhibit inductance, a parallel resonant frequency may occur with capacitors in parallel.

I found applying a series resistance to lower Q may flatten the impedance versus frequency response of the bypass network, but didn't decrease the impedance at any 1 frequency. Optimal bypassing or achieving the lowest impedance over a wide frequency range presents a complex topic that might even challenge some engineers.



Decreased Q Bypass

Above — A method to exact wideband bypass.



Above — My first try with C0 = 0.1 µF, R0 = 39 Ω and C1 = 0.01 µF. I arbitrarily placed the 39 Ω resistor in the R0 slot and saw that the high impedance peak seen earlier disappeared. This gave me the confidence to try 3 capacitors. I had no idea what R value to use and really just wanted to see what happens.



Above — The spectrograph with C0 = 0.1 µF, R0 = 10K, C1 = 0.01 µF, R1 = 47K and C3 = 0.001 µF.



Above — C0 = 0.1 µF, R0 = 10K, C1 = 0.01 µF, R1 = 47K and C3 = 0.001 µF. Again, no high impedance peak response; the self resonant frequency is close to that measured with a single 0.001 uF earlier, however, the peak bypass frequency moved from to 57 MHz from 62 MHz. Changing the resistor values moved the self-resonant frequency and the peak attenuation value a little, but I fell kilometers short of setting a wide band bypass. My approach lacks any real science and I need to step it up.

I hope to learn what capacitor values and types, plus R values to apply. This sounds like a job for simulation as well as further on-bench experiments? After writing this material, I learned that Ken Kuhn wrote an Excel spreadsheet to examine the net impedance of up to 3 capacitors in parallel Click to download.



Above — Just as a gag, I removed R0 from capacitor C0 in 1 circuit and then hooked up the board. The high impedance peak re-emerged.

A Commerical Example

I found a wideband MMIC employing (R1 + C1 and C2) as part of a bypass strategy. Cick for the datasheet excerpt. Note the size of the SMD capacitors; 0603 — tiny caps! My experiments showed some high gain MMICs require careful low inductance grounding and correct part choices or crippling oscillations and other bypass issues might arise.

My Learnings

When we think bypass, we really should think frequency dependent attenuation. The bypass cap is actually a network where impedance versus frequency varies significantly. At its self resonant frequency, a capacitor will exhibit the lowest possible impedance making a single capacitor a relatively narrow-band bypass device. Intuitively, we might want to choose a capacitor with a series resonant frequency at the frequency we wish to bypass, however, if we require a wideband bypass, the need to evaluate our bypass capacitor(s) increases.

In short, above the series resonant frequency of a capacitor, its bypass is basically useless and we should likely ensure that the self-resonant frequency of the particular capacitor we're using is above the highest frequency to be bypassed.

Bypassing with 2 or more unmatched RF caps will lead to an attenuation gap with peak(s) determined by the parallel resonance of these capacitors. Going above a 10:1 capacitor ratio, for example, greater than a 0.1 and a 0.01 µf, may cause a **severe** gap in attenuation at the parallel resonant frequency generated by the 2 capacitors.

Mine and work from more reputable authors clearly shows we should avoid applying parallel **RF** bypass capacitors of *different* values unless we apply a Q-reducing resistor to the capacitor(s) in parallel with a given RF bypass capacitor. Please read EMRFD page 2.3 for more information and watch out for abundant folklore concerning RF bypass.

The need for measurement and analysis challenges us; in some cases, you may realize good attenuation in the radio band of interest, while poorly bypassing the frequencies above it and compromise an otherwise good design.

Capacitor lead length may affect self-resonance at RF.

Future Work

It would be awesome to learn more about getting a wide-band bypass. I want to order some low or ultra-low ESR caps and measure them. My MuRata RPE Series caps specify low inductance; low is relative — how low is low? Should we apply chip capacitors for bypass in our critical circuits such as low noise VHF amps or MMICs?. Am I fussing about nothing? Lots of questions that folklore just won't answer.

Per EMRFD page 2.3, bypass is only half the equation — we need to *decouple* + bypass to filter RF from moving along our DC lines and so forth.

6. Some Experiments with Chokes plus Decouple and Bypass Filters

Introduction

SRF = self resonant frequency; XL = inductive reactance; XC = capacitive reactance. L = inductor; C = capacitor; R = resistor.

Like the capacitor, inductors are networks with R, L and C and possess a SRF. R, L and C may vary with factors including the number of windings, frequency, or whether the L is wound on a ferromagnetic material, or air wound.

Considering R, L and C:

at frequencies below the SRF, XL dominates;
at frequencies above the SRF XC dominates;
at the SRF, the magnitude of XL and XC are equal but 180 degrees out of phase leaving resistance to dominate.

I encourage you to learn more by visiting the fabulous web site of David, G3YNH.



Above — Reference signal at -27 dBm. I used the exact test method shown in Section 5.

For those unaware, the spectrum analyzer screen is divided into 10 by 10 graticules. Each vertical division represent a 10 dB change; read down from the reference -27 dBm to measure the attenuation of the reference signal in dB. Horizontal divisions represent frequency; start at 0 on the left hand side and increment as specified on each figure.

A Few Inductors



Above — A 19.9 uH epoxy coated choke that exhibits a primary SRF at 18 MHz and a second, smaller SRF at ~128 MHz. This wretched L gave me grief at 63 MHz. After measurement, I tossed it in the garbage can.



Above — A large, junk box choke with an SRF at about 10 MHz.



Above — I rarely use these big chokes: 870 µH with a SRF at about 2 MHz.



Above — A common L on our benches — 10 turns of #26 AWG on a FT37-43 ferrite toroid.

I couldn't measure the SRF with any span on my spectrum analyzer. I expect that a parasitic capacitance lies in parallel with the inductance, but the #43 material, with its low Q and high losses blankets the usual deep notch we see when the L exhibits a higher Qu.

10 Turns on a FT37- 43 with a Bypass Capacitor Shunting Each End



Above — Look at the big difference after adding shunt capacitors to a 10 turn FT37-43! Even at 100 MHz the attenuation lies nearly 50 dB down. Now I understand why Wes says **decouple plus bypass** when filtering our DC lines and so forth.



Above — The 10 turn FT37-43 coil with 0.1 μF shunt caps measured out to 500 MHz. Pardon the camera shake; I took all the photos hand held to save time.

A Resistor with a Bypass Capacitor Shunting Each End



Above — A 51 Ω resistor bypassed with 0.1 µF capacitors at each end spanned out to 100 MHz. Even at 30 MHz, the attenuation looks stellar.



Above — The 0.1 µF bypassed 51 Ω resistor out to 200 MHz. I often use a 51 Ω decoupling resistor with appropriate capacitor values in active circuits that draw from 10 - 18 mA.



Above — The "bench standard"; a 100 Ω R with a shunt 0.1 µF at each end. We use this all the time. Even at 25 MHz, the attenuation looks around 55 dB down.



Above — The 100 Ω R with the shunt capacitors decreased to 0.01µF. At 6 MHz, we're about 50 dB down. From 10 to 20 MHz, the attenuation is about as high as I can measure.



Above — 100 Ω R plus 0.01 μF caps out to 50 MHz. I've used this combination of R and C for filtering at 50 MHz a lot.



Above — 100 Ω R plus 0.001 μF capacitors out to 100 MHz. In my particular circuit, the attenuation at 50 MHz equals that of the 100 R + 0.01 μF C low-pass filter shown directly above.



Above — A 100 Ω R plus a single 0.001 μF capacitor. If you leave off 1 capacitor, a serious notch appears at ~ 68 MHz. If you flip the filter around so the bypass cap is on the right hand side, the tracing appears the same. This problem occurred with all the filters tested in all experiments. As possible, solder a suitable bypass capacitor on *both* sides of the R or L.

I encourage you to experiment with the SRF of coils and wideband decouple + bypass filters on your own.

QRP Posdata for Oct 2013 — SRF of some common bypass capacitors



Capacitor	Notch Freq
0.1 µF	6.56 MHz
0.01µF	22.68 MHz
0.001 µF	69.62 MHz
0.0022 µF	53.2 MHz
680 pF	87.34 MHz
470 pF	88.17 MHz
220 pF	154.58 MHz
100 pF	222.91 MHz

- Self resonant frequencies of some common bypass capacitors covering ~ 6.6 to 220 MHz
- Use table to inform bypass cap versus frequency choices

Tested as shown to left in calibrated TG + SA using instrument grade 9 cm SMA cables and connectors.

- The deepest notch [-64.32 dBm] occurred with the 0.1 µF cap and decreased progressively with capacitance
- Caps tested = muRata RPE series monolithic ceramic with C0G temp compensation. Different brands, types, etc. of caps may change results significantly
- Leads short as possible with the SMA connectors soldered right on the ground plane

Above — A reference table showing the self resonant frequency of several comon value bypass capacitors in my parts collection. For example, if

I'm making a 21 MHz circuit, the best bypass capacitor choice from the table above = 0.01 μF. If possible, sweep the capacitors in your own collection to determine their SRF; or whether they're even suitable.



03:04:36 2013-10-16

Ref 0.00 dBm Att 10 dB Marker1 69.624 MHz -59.51 dBm

Marker
69.624912 MHz
-59.51 dBm

Center Freq 68.500 MHz Span 39.702 MHz
*RBW 3.000 kHz *VBW 300 Hz SWT 44.114 s

RIGOL
Local
Status
Peak
TRIG Free
SWP Cont
Corr
S.T.
PA
C.W.
Blank
Blank
Math
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
1
Marker
Select Mkr
1
2
3
4
Normal
Delta
Delta Pair
Ref
Delta
Span Pair
Span
Center
Off
Mkr Trace
Auto
1/2

Above — The close-in sweep of the 0.001 μF capacitor tabled above.



50 Ω
L
50 Ω
C
50 Ω
R
50 Ω
C

Above — As possible, stick 2 of your bypass cap values in a pi filter network with a series decoupling L or R to derive wideband filtration. For example, to filter your DC power lines.



RIGOL
Local
Status
Peak
TRIG Free
SWP Cont
Corr
S.T.
PA
C.W.
Blank
Blank
Math
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
1
Marker
Select Mkr
1
2
3
4
Normal
Delta
Delta Pair
Ref
Delta
Span Pair
Span
Center
Off
Mkr Trace
Auto
1/2

14:03:19 2013-10-15

Ref 0.00 dBm

Att 10 dB

Marker1 144.00 MHz -48.56 dBm

Marker
144.000000 MHz
-48.56 dBm

Center Freq 150.00 MHz

Span 300.00 MHz

* RBW 30.000 kHz

* VBW 3.000 kHz

SWT 3.3333 s

Above — A 300 MHz sweep of a pi filter [220 pF + 1.2 µH + 220 pF] for the DC supply line of a 150 MHz oscillator. The SRF peak lies at 76.69 MHz, but this filter works okay out to about 200 MHz. I placed a marker at 144 MHz and could use this filter for the 2M band as well.



02:44:02 2013-10-16

Ref 0.00 dBm Att 10 dB Marker1 150.00 MHz -47.49 dBm

Marker
150.000000 MHz
-47.49 dBm

Center Freq 250.00 MHz Span 500.00 MHz

RBW 10.000 kHz VBW 10.000 kHz SWT 5.0000 s

RIGOL
Local
Status
Peak
TRIG Free
SWP Cont
Corr
S.T.
PA
C.W.
Blank
Blank
Math
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
1
Marker
Select Mkr
1
2
3
4
Normal
Delta
Delta Pair
Ref
Delta
Span Pair
Span
Center
Off
Mkr Trace
Auto
1/2

Above — The network described above, except I replaced the 1.2 µH L with a size 0805 10 Ω resistor [220 pF + 10R + 220 pF] and swept to 500 MHz. I set Marker 1 on 150 MHz; the frequency of the oscillator I wanted to DC powerline filter. The resistor gives a bit more filter bandwidth around 150 MHz. A 51 or 100 Ω resistor will further increase the bandwidth while decreasing the attenuation depth somewhat. Although resistors incur a DC voltage drop, they avoid the potential of an unwanted SRF in your filter arising from a renegade inductor— and so, a resistor may pose a better choice for pi filtering DC lines and so forth. It's your call.

At HF and lower VHF, I've found a hole-through capacitor may sometimes filter better than a "garden variety" SMT counterpart. Click for a graphic that shows this. Presumably, the SMT cap exhibited a lower Q than the equivalent hole-though part. At some frequency above 200 MHz, the lead inductance of the hole-through capacitor may cause the opposite effect.

Further, on the VHF — Véronique web page, Section 6: I swept 3 capacitors including an ultra-high Q SMT part.

RF — Test and Measurement

RF Workbench Page 5

Welcome to part 5 of a web series exploring basic RF measurement and bench practices. This installment builds on the information from RF Workbench Parts 1 - 4.

In RFWB #5 I share a hodge-podge of thoughts and circuits concerning power measurement on the beginner-level RF workbench. Consult EMRFD for more support. Big thanks to my mentors: Wes, W7ZOI. Bob, K3NHI and John, K5IRK for their support as I advance to the basics.

Power Measurement Empowers You

Before embracing the 50 Ω RF environment, I misjudged the need to quantify small signal power — now I get that we measure lots of low-level signals on the 50 Ω RF workbench. Whether you're driving a mixer RF port with -30 dBm to reduce spurs, or tweaking an amplifer-under-test to exact the best S21, low-level RF power measurement is fundamental to fruitful RF design.

1 way to measure low-level RF power includes building a log linear RF power meter (PM) based on the Analog Devices AD8307. The basic circuit I show posits that most of you measure from MF to HF and don't need a PM that reads flat into UHF and further; a simple, 2 chip circuit might even prompt you to actually build a barebones PM for your QRP workbench.

Search for and download the Analog Devices AD8307 Revision D datasheet — it's definitely worth a read. Kudos to the design team that brought us a truly milestone device for low-cost power measurement.

Analog Devices offers a whole family of log-amps at different frequency ranges — for example, the AD8311 Log Amp/Detector covers from ~100 MHz to 2500 MHz. A sister product, the AD8302 2.7 GHz RF / IF Gain Phase Detector looks amazing.

AD8307
AR 0512
45536

---

1. A Barebones RF Power Meter

Lacks the usual input frequency compensation network needed to keep power measurement flat over several hundred MHz — since most input compensate by attenuating HF, this simple version offers stronger sensitivity at HF than usual.

Good from MF up to about 100 MHz.

4.5v B+ to eliminate power supply decoupling issues and to give greater battery life than a 9v battery.

Minimum input power about -70 dBm. Maximum input power +15 dBm. Requires a metal box.

Big thanks to Wes, W7ZOI for letting me present his simple RF power meter. I found *numerous* AD8307-based RF power meter designs in periodicals and on the web and the writers devised simple to elaborate input compensation networks to establish a flat response out to 500 MHz — involving parts such as nH-level inductors, chip resistors and capacitors. This PM goes the opposite direction; a plain circuit for you builders who measure under 100 MHz; particularly at HF.


4.5V
3x AA
.1
50 Ω
.01
NC
8
7
6
5
51
10
BARENONES
POWER METER
.1
R1
R2
A
6K8
6K8
4.7 uF
AD8307
25 mV/dB
1
2
3
4
.01
NC
.001
3
2
U1a
8
1
4
U1 = LM358
5K
10K
.01
5
U1b
7
6
A = Meter (0 – 200 uA)
B = Output to DVM or 'scope
20 mV/dB
1K
B
designed by W7ZOI

Above — the complete Barebones PM schematic. Presented with the permission of Wes, W7ZOI.

AD8307 Input Pin 8: Some Graphs and Notes:



06/07/2012 file: 060712_8307 Overlays of PM and crude PM performance over ~ 1 to 100 MHz at -20 nominal. Display is 2 dB/Grid, 10 MHz / Grid
Magenta = crude PM board, blue = BK PM. Crude assy has no input compensation net. Evident is the ~ 1dB roll off as in AD data sheet at 100 MHz. Source is BK 100 MHz sweeper - believed to be "flat" as when compared with Wavetek gen.

Above — The lack of input compensation might raise a few eyebrows! A sweep of the Barebones PM by Bob, K3NHI shows a reasonably flat response out to 100 MHz that's comparible to some of the 0-100 MHz range of wider sweeps in the published compensated circuits I've read.



Above — A different Barebones PM plot from Wes, W7ZOI that goes out 500 MHz. For HF work, this power meter proves adequate for QRP HomeBuilders. By all means, add some input compensation if you want to — good circuit examples abound. For example, EMRFD Figure 7.13, or Bob Kopski's — An Advanced VHF Wattmeter referenced in Section 5.

AD8307 specifications allow a typical +/- 0.3 dBm "ripple" in the input to output transfer characteristic. Bob, K3NHI verified this ripple in his lab.

Therefore; depending on the position of a signal in the transfer curve, a move between 2 different power levels may yield as much as 0.6 db peak difference error. Figure 8 of the Rev D datasheet shows this. Figure 24 plus associated text tells why this occurs: the transfer characteristic is a chunk or segmented realization of a log transfer characteristic. It's really good — just not perfect.

If you consider the cost of thermal sensor power meters from Agilent, Techtronix, or even the Mini-Circuits PWR-6GHS, the AD8307 seems a bargain.

Measuring U1a Pin 1 With a Panel Meter

The first output at Pin 1 drives nearly any junkbox DC panel meter you might own The schematic specifies a 0-200 uA movement, however a 1 mA meter movement also works by tweaking R1 and R2 to establish the correct current. In the circuit shown the R = 13.6K. This R establishes the current required to drive the 200 uA meter Wes used in his design — nothing more. A wide variety of panel meters work because the drive current comes from an op-amp. Don't order an expensive panel meter just because you want to employ a 100 or 200 uA model — choose your meter because it affords good needle movement and resolution to allow accurate power measurement.

Although elementary for some, the following diagram shows you how to measure the maximum current for your meter: 100 uA, 200 uA, etc.



Example calculation with V Battery = 4.53v
V Meter = 0.24v and R Pot = 22.5K Ω

Calculate the maximum current and internal resistance of a panel meter.

Current at Maximum Deflection

Formula: (V Battery – V Meter) / R Pot

4.53v – 0.24v / 22500 Ω = 0.0001906 A

or 191 μA

1. Adjust 25K pot to get a full needle deflection.
2. Measure the pot resistance with your DVM *R Pot*
3. Measure the voltage across the meter *V Meter*

Ohm's Law

Above — In my shoebox sat 4 different panel meters. I measured 1 meter and show the math above — a 191 μA meter.

DIRECT CURRENT
0
.2
.4
.6
.8
1
Simpson

Above — An antique 1 mA panel meter driven with 1 mA to achieve full deflection.

Meter resolution presents the biggest problem for junkbox panel meters and if you look around the web, you'll see some great examples how builders calibrated and/or marked the scale on their AD8307 circuit panel meters.



Above — Panel meter markings on my friend Peter's power meter.

I personally like my panel meters to read about 75% of full deflection at 7 dBm, but it's really your choice. Adjust R1 and/or R2 up or down to give the desired amount of meter deflection for whatever panel meter you own.

You may apply Ohm's law to figure out the maximum in-situ current for any panel meter. In the schematic the total R is 13.6K, so when you apply +10 dBm applied to the power meter input, the current in the panel meter will be 2.0v /13.6K = 147 uA. The maximum 200 uA will occur with a Pin 1 voltage of 2.72v. The op-amp won't go all the way to the positive rail, but If it did go all the way to 4.5v, you would hurl 331 uA into the panel meter. This exceeds the meter's uppermost scale, but likely won't destroy it.

The 4.7 uF cap can be any small uF capacitor value and low-pass filters the DC to smooth out the meter movement. I used a 10 uF in my breadboard.

I normally view the panel meter to tune resonant circuits and observe trends; but not to precisely measure power — it's often more accurate to quantify power readings at Port B since this eliminates panel meter resolution issues.

How to Measure Power at Port B

We measure the DC voltage at port B and use equations or graphs to translate this voltage into an actual power reading after reference calibration. U1a and U1b are unity-gain voltage followers to buffer the AD8307 output. U1B features a 5K potentiometer in series with a 10K shunt resistor to form a voltage divider that changes the 25 mV/dB AD8307 output to 20 dB/mV. Tweak the 5K pot to calibrate to get as close to 20 dB/mV as possible, although since the LM358 buffers just pass on the DC voltage changes of the AD8307, the pot does not technically alter log linearity.

Wes published some essential notes on his web site. On page 8, you find his formula to convert a measured DC voltage into dBm. I wrote a program that incorporates his formula: Applet L on my Design Center web page; except that it takes calibration power at -10 dBm and -20 dBm.

Let's run through 1 example:



L. Calculate Power from the DC Output of an AD8307 Meter

http://www.qrp.pops.net/qrp-java-calculator.htm

1. Linear calibration steps:

Enter measured DVM voltage at -10 dBm: 1.60 Enter measured DVM voltage at -20 dBm: 1.40

2. Calculate power in dBm from DVM voltage:

Enter measured DVM voltage: 1.94 Power = 7

Above — A screen capture of JavaScript Applet L. I calibrated my instrument by connecting a 10.0 MHz sine wave calibrator to the 50 Ω input port of my PM. At -10 dBm input power, my Port B reading was 1.6 VDC; at -20 dBm, I measured 1.4v at Port B. These 2 points establish the log linearity per Wes' notes. After this calibration, I measured the output power of a 4 MHz sine wave VFO that I designed to run at 7 dBm output power to drive the LO port of a diode ring mixer. Port B read 1.94 volts and when I entered this into Applet L and pushed <<Calculate>>, the VFO output power was indeed 7 dBm. More on this later...



Above — My prototype RF-tight breadboard of the Barebones PM. I ran my 'trademark' die case box, BNC RF input and Port B connectors, a common ground lug and feedthrough capacitors for the B+ and panel meter connections. I placed a BNC to RCA adaptor on Port B to allow the insertion of a standard-type positive DVM probe. A black alligator clip terminates the distal end of the negative probe on all my DVMs. I just clip it onto the ground lug.

20 10 7 5 3 0 3
20 50 100%
VU

Above — A view of my breadboard showing my 100 uA panel meter and the 4.5v battery pack. I raised R2 in the original schematic up to 8K2 to set my preferred needle movement in this 100 uA panel meter. A meter with linear markings might be better?

Some Further AD8307 Notes

After power up, you'll notice a DC output voltage around 0.22v or so with no input signal; this arises from wideband noise caused by resistors and amplifiers in the AD8307— all normal.

If possible, verify a 25 mV per dB power change with a manual sweep using a sine wave signal generator on the input and a DVM to AD8307 Pin 4. If you don't have the test gear to perform this function check, no problem.

The AD8307 input resistance = 1100 Ω , so we must place a resistor in parallel with the input to establish 50 Ω. Many builders just shunt a short-leaded 51 Ω resistor from input to ground like Wes did, however, you might also see builders place a 1% tolerance 53.2 Ω R in that slot to derive an input Z of 49.9 Ω. I did this in another "blinged-out", frequency compensated AD8307 meter I built for future UHF circuit experiments.

With 20 and/or 40 dB taps, attenuator pads and some 50 Ω cables, a Barebones AD8307 PM can measure everything HF you might build or buy for your *QRP* workbench. I posit that a simple AD8307 power meter may form the heart of a basic, first QRP workbench. Lacking a oscilloscope when I started in radio electronics, I measured RF with a germanium diode RF probe and a DVM — I would have enjoyed a simple log power meter plus a basic calibrator, however, the AD8307 did not exist back then.



Above — Some builders lament because an AD8307 (in DIP) costs around $10.00. I bid for and bought the AR version chip shown above for $4.42 USD. The above green Proto Advantage breakout board cost $1.00. To compare; some people spend $5.00 for a boutique coffee in Canada — it's all good.

The SMD packaged AD8307AR may offer better performance above 100 MHz with its lower lead inductance.

QRP — PosData for Dec 3, 2013

Realize your bench acumen — adapt and build some test equipment to suit *your* needs. Steve, VK2SJA crafted a version of the AD8307 PM. Click for his beautiful box featuring a 1mA meter movement. Aided by the Tonne software "Meter" program and the AD8307 datasheet, his ranks among the best I've seen. Kudos Steve.

---

2. Power Meter Calibrators

1. CMOS Clock Oscillator RF Calibrator @ -10 dBm

Bob, K3NHI designed a 10.0 MHz reference oscillator for -10 dBm that might help equip the beginner bench. This CMOS signal source does not need an AC power reference to calibrate it — just a DVM to make a DC measurement and your good to go!

In addition to calibrating an AD8307-based PM, you might use this -10 dBm reference to calibrate other gear including homebrew sine wave signal generators; that's what I'll do later.

MX045
10M0000
CTS 3C
1030 12A
MX045
10M0000
CTS 3C
1030 12A

Above — The recommended CMOS clock oscillator for the CMOS RF calibrator. Digi-Key part # CTX772-ND. Data sheet.
If you substitute another CMOS clock, it must swing nearly rail-to-rail for accuracy. Bob intended this calibrator for those who lack the bench instruments needed to precisely calibrate RF devices since only a DVM is needed for calibration. This generator also offers a range of calibrated harmonics as Bob described in his January-February QEX article A Simple RF Power Calibrator — great when you want to examine a spectrum analyzer over a limited span.


CMOS RF Calibrator
NC
1
7
MX045
bottom
14
8
9v Battery
5v Reg
4.7 uF
4.7 uF
200
R
1K
10K
.1
52.3
DC Cal
RF Out

Adjust trimmer R for 50.0 mV @ the DC Cal port with a 50 Ω terminator on the RF port.

Above — My version of the K3NHI CMOS signal source (presented with the permission of Bob, K3NHI). The 52.3 Ω resistor is a standard 1% part and I bought 5 for all my AD8307 projects and this little signal generator. In my first version, the trimmer resistor was 500 Ω and worked okay, but the 200 Ω trimmer improved calibration. I ordered 10 Bourns 200 Ω and 10 Bourns 500 Ω trimmers on eBay for a few dollars and after studying Bob's published work and applying his influences to my own, I now love to precisely calibrate or bias circuits with a 200 or 500 Ω trimmer R as appropriate.

QRP — PosData for November 22, 2012

If required, you may substitute a 49.9 to 51 Ω resistor for the 52.3 Ω specified.

Per Bob's QEX 2010 Tech Notes and his emails specifically about calibrating the AD8307 with a CMOS *square wave***:** Modern AD8307 chips are better calibrated with a -10 dBM square wave. To test log linearity after CMOS signal generator calibration, apply a sine wave signal generator to your power meter and adjust its output to get the same power meter DC output voltage as with the CMOS generator. Then insert attenuator pads on the now calibrated sine wave generator to assess the mV/dB change with different power levels.

Bob's original CMOS calibrator outputted - 20 dBm, however, he updated it to output -10 dBm in 2010 as reported in his QEX 2010 Tech Notes.

Some readers have asked why calibrate the AD8307 at 10 MHz? Calibrate at whatever frequency you want, or more than one. However, at 10 MHz, the AD8307 exhibits its best log performance compared to other frequencies. Click or click for datasheet graphs.

EQUUS
#4320
.050
www.iequus.com
AUTOPOWER OFF
10 MegOhm Input Impedance
DCV
500
20
2
200m
OFF
500
200
ACV
BAT.
12V
6V
1.5V
2m
DCA
mA
20m
200m
10A
20M
200K
2K
OHM
Ω
200
©IEC 2002

Above — The DVM calibration port reading (2 volt scale) from my CMOS clock calibrator after calibration. That was easy!



DSO-X 2022A, MY51360373: Wed Jun 20 11:08:58 2012

1 2 20mV/ 16.80ns 19.00ns/ Auto 2 59.3mV

Acquisition
Normal
2.00GSa/s

Channels
DC 10.0:1
DC 1.00:1

Measurements
Pk-Pk(1): No signal
Pk-Pk(2): 117mV
Freq(2): 10.00MHz
AC RMS - FS(2): 50.00mV

T
2
Agilent
Autoscale Menu
Undo Autoscale
Fast Debug ☐
Channels All
Acq Mode Normal

Above — The calibrated CMOS clock RF calibrator in my 50 Ω terminated scope.



Above — The breadboard of my version of the K3HNI CMOS -10 dBm RF calibrator. For best results, stick it in a shielded box. When correctly calibrated, it outputs -10 dBm on an AD8307 PM, -14 dBm on a spectrum analyzer and -13 dBm on a conventional, thermal-sensor power meter.



AD8307 Calibration 1
DVM
V
-
+
50 Ω coax
with RF
connectors
AD8307
Power Meter
CMOS
Calibrator
-10 dBm

Above — The procedure for calibrating an AD8307 PM with the -10 dBm square wave CMOS signal source.



Above — When I connected the calibrated CMOS clock RF calibrator to my build of the Barebones PM, I measured 1.60v with my DVM; ***the -10 dBm reference voltage.*** Since the log-linear power changes 20 mV/dB; for my calibration reference voltage: 1.40v = -20 dBm, 1.20v = -30 dBm, 2.0v = 10 dBm etc.

Remember that the Barebones PM runs on a battery pack and over time the B+ will change. *Each tim*e I measure power with the meter I first calibrate it to establish the -10 dBm reference voltage.

Here's a simple formula that only works for 20 mV/dB @ my particular 1.60v calibration voltage, but gives you the general idea:

Power in dBm = 50 x (V - 1.8)

So if I measure 1.94v: 50 x (1.94 - 1.8) = 7 dBm.

2. Sine Wave Oscillator for Calibration @ -10 dBm and -20 dBm.

You may also calibrate your AD8307 PM with a calibrated sine wave signal generator. Advanced builders who own the gear needed to measure RF power tend to use a sine wave for calibration.

It's easy to calibrate the AD8307 with a sine wave signal source. Normally we calibrate our sine wave signal generators with instruments such as a 50 Ω terminated 'scope, a spectrum analyzer, a calibrated power meter, or a 49.9 to 51 Ω terminating resistor plus a 10X probe etc., but if you lack these instruments, your stuck.

No problem. You may calibrate any appropriate sine wave oscillator at -10 dBm with your Barebones PM and the CMOS RF Calibrator shown earlier. Let's examine the procedure:



AD8307 Calibration 2

DVM
V
Square wave
CMOS Calibrator
AD8307
Power Meter
-10 dBm

Determine the AD8307 output DC voltage @-10 dBm and calibrate the sine wave device to get the same AD8307 DC output voltage

DVM
V
Adjust sine wave
Calibrator for -10 dBm
AD8307
Power Meter
cal
to
-10 dBm

Calibrate the AD8307 PM with the CMOS square wave reference and record the DC voltage at the output of Port B. Connect up your sine wave generator and adjust its output until you get the same Port B DC voltage as the reference CMOS RF signal generator — your sine wave oscillator should now be calibrated to -10 dBm.


12.22 V
100
T50-6
33t
5t
19 dB
220
A
50 Ω
2nd harmonic
-39 dBc
.1
.1
←62→
J310
d
g
s
39 pF
2.7-10 pF
10.0 MHz
47K
1K2
1K
10 MHZ
Sine Wave Calibrator
-10dBm
Optional switch
10 dB pad
DPDT
bottom
A

Above — I designed this simple 10.0 MHz sine wave calibrator to evaluate Bob's CMOS square wave RF calibrator and serve as an example sine wave reference oscillator. When running a regulated VCC of at least 12v and the *tank is perfectly* tuned, low distortion arises. I measured the second harmonic @ 39 dBc down. The L with 33 turns = 4.43 uH.

The initial tuning procedure goes like this:

1. Terminate the output with a 50 Ω resistor terminator, or a 50 Ω terminated 'scope, or your AD8307 PM.
2. Connect an ammeter between the VCC node and the regulated power supply.
3. Adjust the emitter trimmer R so that the circuit draws around 2.7 mA — then disconnect the ammeter leads.
4. Adjust the trimmer cap for the highest pk-pk voltage (and/or or best looking waveform) in the 'scope, or highest power in the AD8307 PM. *Nominal total C to resonate my particular circuit was ~ 45 pF.*

If not already done, connect the tuned-up sine wave signal source to a AD8307 PM. Adjust the trimmer potentiometer so the Port B DC voltage = the reference voltage measured during your CMOS RF generator power meter calibration. Your sine wave signal source is now calibrated to -10 dBm.



Above — The breadboard of my 10 MHz sine wave signal source. I included the optional switched 10 dB attenuator shown on the schematic inset. In the end I decided to just stick a removable **10 dB** pad like this 6 dB pad in-line for my -20 dBm measurement.


10 dB Pad Ideas
50 Ω
71.2
50 Ω
96.2
50 Ω
27
220
100
50 Ω
100
100
2K7
100
100
2K7

Above — Craft accurate attenuator pads with parallel + series resistors and some creative energy. Lacking the proper 1% parts, I hand selected some 5% resistors among the values shown to the right and built a pad that *precisely* gave a 10 dB power drop at 50 Ω.

Now let's check the calibration of this little sinusoidal RF generator...


EQUUS
#4320
1.60
www.iequus.com
10 MegOhm Input Impedance
DCV
500
20
200m
OFF
ACV
500
200
BAT.
LOAD TEST
12V
6V
1.5V
2m
20M
200K
2K

Above — When connected to the Barebones PM, I calibrated the output power of the sine wave generator by tweaking the trimmer pot to give an output of 1.60v; the same Port B voltage yielded by the CMOS RF calibrator.


DSO-X 2022A, MY51360373: Mon Jun 18 06:42:56 2012

1 2 34mV/ 22.60ns 19.50ns/ Auto 2 4.00mV

Acquisition
Normal
2.00GSa/s

Channels
DC 10.0:1
DC 1.00:1

Measurements
Pk-Pk(1): No signal
Pk-Pk(2): 200mV
Freq(2): 10.01MHz
AC RMS - FS(2): 69.07mV

f(t) = FFT(Ch2)

Function f(t)
Operator FFT
Source 1 2
Span 200MHz
Center 10.0MHz
More FFT

Above — The 50 Ω terminated 'scope verification of my calibrated 10 MHz sine wave signal source: 200 mV pk-pk = -10 dBm. Wow, thanks for this Bob!


EQUUS
#4320
www.iequus.com
10 MegOhm Input Impedance
DCV
ACV
OFF
BAT
2K
200K
20M
200m
20
500
200
12V
6V
1.5V
2m
1.40

Above — The Port B voltage when a 10 dB attenuator pad was connected to the calibrated -10 dBm sine wave signal source: Measured power = -20 dBm. Notice the 20 mV/dB power drop — right on specification.

Refer to the section titled **<How to Measure Power at Port B>** Recall Wes' calculation needed 2 points to set the log linearity. I chose -10 dBm and -20 dBm instead of 0 dBm and -10 dBm so the CMOS RF calibrator could be used to calibrate any sine wave signal generators on hand.

The -10 dBm calibration reference power serves as 1 of the calibration points in Applet L while we derive the other by adding a 10 dB attenuator pad to a *sine wave* signal source output port. ***Don't connect an attenuator pad to the CMOS square wave calibrator —*** error in the AD8307 arises. Why? Analog Devices mysteriously changed the AD8307 at some point after 2004 and altered its crest factor — this disallows us performing log linearity calibration with a square wave.



Above — A 20 dB pad connected to the -10 dBm sine wave signal source yielded 1.22v at Port B in the Barebones PM. See the power calculation with Applet L below:



L. Calculate Power from the DC Output of an AD8307 Meter

http://www.qrp.pops.net/qrp-java-calculator.htm

1. Linear calibration steps:

Enter measured DVM voltage at -10 dBm: 1.60 Enter measured DVM voltage at -20 dBm: 1.40

2. Calculate power in dBm from DVM voltage:

Enter measured DVM voltage: 1.22 Calculate Power = -29

Above — The calculation of the output power with a 20 dB attenuator pad on the sine wave signal source output. We're off by 1 dB since it should have calculated a power of -30 dBm. Could this be error caused by my attenuator circuit, or non-linearity by the AD8307 PM, or a bit of both? We have to live with such problems. Still, the Barebones power meter seems quite impressive for a simple circuit that I scratch built and calibrated in about 25 minutes.



Above — The Barebones PM DC output voltage with a 30 dB attenuator pad on the output of my -10 dBm, 10 MHz sine wave signal generator: Measured power = -39.5 dBm. Again; a very good — but not perfect power meter.

A Barebones power meter allows builders with modest equipment to measure power, gain/loss, and with a return loss bridge, return loss at HF. I wish I owned this little gem back when I started out.

Richard, "Dick", N4HAY, posted some great notes on his blog. I recommend following his blog since he really digs deep and likes math — thanks Dick!

Best!

---

3. A Basic RF Workbench

Since January 2012, a handful of readers asked what I consider a good basic *RF* work bench. Again, I'm just an amateur hobbyist, so my opinion might show my ignorance.

A stand-alone 50 MHz oscilloscope with at least one 10X probe. *More bandwidth if you plan to work above 50 MHz*

If no oscillocope, an AD8307-based power meter *The modern version of the diode RF probe*.

3-4 50 Ω coaxial cables with BNC connectors; a 50 Ω scope feed-through terminator, *1-2* 50 Ω BNC port terminators, a though-connector and some BNC connectors to solder onto temporary circuit boards or mount in a chassis.

A homebrew return loss bridge.

3, 6, 10 and 20 dB BNC connector equipped attenuator pads, or a step attenuator.

Signal generator(s) that cover most of HF; +/- VHF signal generators described in the next section.

AADE L/C Meter IIB. Click

12 volt regulated power supply good for at least 1 amp.

Digital multimeter. *I use 2 and keep 1 set up for current measurement only.*

Frequency counter: homebrew or commercial. *I ran a 40 year old, ovenized, accurate HP counter until 2012.*

With these devices, as possible, you can work in a modular, 50 Ω environment and measure gain or loss in dB, return loss in dB and absolute power in dBm. Starting small and expanding your bench around 50 Ω input and output impedance devices will provide a lifetime of challenge and excitement in RF design.

Later, the big toys can follow: spectrum analyzers, VNAs, commercial signal generators and other lab quality stuff.

Equipping an RF bench presents quite a financial burden. I started small and slowly added pieces over time. Many pieces such as my L/C Meter IIB were gifts for holidays or my birthday. Other pieces were old, inexpensive equipment that I restored and calibrated.

3dB ATTE
FREQUENC
Mini-Circuits
15542
HAT-

Above — RF tools of the trade. We're RF experimenters! As scratch homebrew builders, gear like BNC, SMA and through-connectors, 50 Ω terminators and inline attenuators lie scattered on our benches; our fodder. Alternate photo.

---

4. VHF Signal Generators

Having only started at VHF in November 2011, my knowledge suffers, however, a search for accessible, affordable, good quality VHF signal generators disheartened me. Ten year old or newer signal generators covering the VHF band work up to several GHz and cost a small fortune.

Lamenting old timers often recommend the vaccum tube HP-608 series that covered ~10-480 MHz. These heavy, glowing beasts sometimes come up in estate sales or on eBay for $200-400.

Then, too, the HP8640 series seems attractive, however, they are full of decaying parts. Ken Kuhn and others restore old HP gear as a hobby and this direction certainly gives us a valid option.

I've investigated 1 or 2 new, low-cost, commercial signal generators that work into VHF, but they failed to excite me; especially after I downloaded the schematics and sat in disbelief over their poor design.

Some minimum commercial signal requirements might include stable, linear tuning, a metal chassis, 50 Ω output with a return loss greater than 20 dB and low harmonic distortion at all frequencies. Like the rest of our lives, our budget usually determines what we buy.

I decided to build my own VHF signal generators and document them on this web site. I've learned that home building signal generators between 50 and 200 MHz requires skill and care, but can be done.

What about digital clocks?

At VHF, DDS spurs get extreme as you get closer to the maximum clock frequency .

The Si570 looks intriguing, however, still requires an MCU + components, I haven't read any lab quality evaluations of the Si570 as part of a engineer-grade VHF-UHF signal generator and if you know better, please email me.

---

5. L - C Meters

If you search for opinions about which L/C meter to get, you'll find an abundance of super write-ups including those that cover measuring with Kelvin probes, SMD tweezers; or statements suggesting that if you really need maximum accuracy, purchase a VNA. I encourage you to research this yourself and find the best L/C meter for *your* bench. Here are my 2 cents worth of opinion and please remember — I'm often wrong.

I use an AADE L/C IIB meter to test inductors and capacitors for HF and even some VHF work. Yes, the AADE L/C IIB doesn't measure large-value electrolytic caps and so forth, however, considering the cost versus performance — it's accurate enough for the popcorn RF workbench.

The AADE L/C meter uses the method described by William Carver, W7AAZ in an article called The LC Tester published in Communications Quarterly, Winter 2003 . EMRFD page 7.12 briefly examines Bill's circuit and shows his original oscillator along with an extended range Colpitts oscillator designed by Wes. For brevity sake, I'll just discuss inductance measurement with Carver-style meters. With care, an inductance resolution of 5 - 20 nH might be realized with such a device.

We normally don't consider that our inductor is actually a network with L, a parallel C and losses that might be modelled as R in series with the L, or a R in parallel with the C depending on our model. The inductor also exhibits a self-resonant frequency and for our design purposes, we usually *ignore* all these details and just consider it a "pure L". My L/C meter's oscillator runs from a few tens to a few hundred KHz and generally lies below the self-resonant frequency of the inductors I measure with it. I've learned by sweeping/analyzing my completed filters, that as long as you avoid the coil's SRF, *the low frequency* Carver-style meter proves a stalwart inductance meter for most HF and some VHF applications.

Often, we popcorn builders want to make a filter, an oscillator, or a pi, or L match and we apply software or tables to calculate the L and C values needed to resonate our filter tank(s) or matching networks, or to synthesize a low-pass filter. These math-driven programs/tables assume the *pure* "pixie dust" L described eariler — disregarding the stray C and R. So getting all worked up about whether our coil is 4.50 or 4.59 microHenries seems moot.

Further, we man-handle our inductors [changing the inductance somewhat] into a breadboard laden with 5% (or greater tolerance) capacitors, copper board pads/paths that exhibit C, active devices and so forth. Then, too, we connect these resonators, or filters to other blocks with sometimes reactive ports, plus or minus shielding. Despite all these variables, miraculously, we make the filter with our "measured" L work!

As we move up in frequency, the effects of stray L effect magnify and at some point our filter networks may behave poorly.

For band-pass filters with Carver-style device measured inductors, we need only adjust each trimmer capacitor to get the highest possible peak-peak voltage, or RF power with our filter between a signal generator and a 50 Ω terminated scope, power meter *respectively*, or whatever. After sweeping these peaked filters, rarely do I need to compress/expand, or add or remove windings to tweak the L get the desired filter response when the filter input and output ports are well matched.

In the case of single frequency matching networks like the L-match, we might need to tweak up or down the L to derive strong port matching. In all cases, our software and the L/C meter can get us into the ballpark, but in-situ bench measurement with other instruments will garner the home run.


L/C Meter IIB
Lx= 1.501 µHy
ZERO
INDUCTANCE
Short circuit test leads
CAPACITANCE
Open circuit test leads
PUSH & HOLD ZERO
Until display = 0.00
MODE SELECT
With Lx and Cx out
Push ZERO/MODE
PWR
Lx
Cx

---

6. Bob, K3NHI — RF Power Meter Follow-on


BATTERY TEST
DVM
MAIN
-6
-4
-2
0
dB X 1
dBm X 10
- 75.4
dBm
RF POWER METER & DETECTOR
dBm
dB
ANALOG OFFSET
ON
PWR
.01
1
10
Pk
DET kHz / Pk
DET OUT OFFSET
DET
OUT
10 mV/dB
RF IN 50 Ohms
0 dB
ATTN
20 dB
+23 dBm Max

Bob built a follow-on detector and power meter to his 2002 QEX power meter *[Reference 3 in Section 7].* Bob gave me the green light to share his creation on my site. Thanks awfully Bob!

Click for the schematic in pdf format. Per typical K3NHI fashion, it's laden with trimmer pots allowing precise calibration — Bob's stuff contains loads of tweaks and wiggles! The new PM offers more flexibility + features including bigger battery supplies that won't quickly die when you fail to turn it off. He also included a means to measure battery voltage on the analog meter. Click for a photo showing the batteries. Low noise, high-speed, rail to rail, CMOS op-amps for IC1 and IC3, allow you to capture PEP during sideband transmitter measurement with appropriate attenuation.

The TS922 op-amp might be hard to find in DIP since that package went obsolete, however, it's available in SMD. If you can't get any TS922, likely other modern, high speed, rail to rail, CMOS op-amps will work fine — consult datasheets to ensure you meet or beat the TS922's performance for IC1 and IC3. Some of the latest design op-amps offer truly sublime specifications and evoke joy in our breadboards.

Bob critically *isolated* the entire RF sub assembly **outlined in green on the schematic** with metal shielding and feed through capacitors for the B+ and DC output. This helps ensure stable and accurate AC voltage measurement. Click or click or click for more of Bob's photographs.

7. References

[1] Roger Hayward, KA7EXM — A PIC-based HF/VHF Power Meter, QEX May/June 2005

[2] Wes Hayward, W7ZOI, Bob Larkin, W7PUA, Simple RF-Power Measurement, QST, June 2001

[3] Bob Kopski, K3NHI — An Advanced VHF Wattmeter, QEX, May/June 2002.

[4] Bob Kopski, K3NHI — A Simple Enhancement for the Advanced VHF Wattmeter, QEX, Sept/Oct 2003.

[5] Bob Kopski, K3NHI — A Simple RF Power Calibrator, QEX, Jan/Feb 2004 **+** Tech Notes article, QEX, May/June 2010.

RF — Test and Measurement

VHF FM

Yes - I could purchase a FM radio-in-an IC for $2.00 and be done in 35 minutes, but what would I learn?

Repository for FM superhet receiver experiments conducted from 2012 to 2014.

1. 10.7 MHz IF Filter Experiments
2. A Basic Colpitts VCO
3. DC-DC Converter for VCOs
4. Supplemental Page #1 - it's time to make some receivers
5. Miscellaneous Photos or Figures

---

1. 10.7 MHz IF Filter Experiments



As a FM receiver design newbie, I read about and experimented with some 10.7 MHz IF filters to learn common practices, what's available and which measurements might help me to reach my goals. Over time, I've collected a variety of crystal and ceramic filters for hopeful future work. Click for 2 exotic examples. IF filters might be purchased at Ham festivals, surplus electronic parts stored and/or online. Prior to paying for a filter, I've found it useful to politely request a sweep of the filter, or, better yet, perform this task myself. To sweep a filter in your lab, you'll need a tool such as a spectrum analyzer with tracking generator, a VNA, or some other analog/digital sweep system.

I'll homebrew some crystal filters for narrow band FM in future installments — I ordered some 20 MHz xtals.

Sometimes a filter in your junkbox will state the IF and perhaps the 3 or 6 dB bandwidth, but not the input/output port termination impedance. How do we determine this impedance? I've learned we can figure this out by testing differerent termination resistors with this simple test jig:



R = Termination impedance - 50 Ω

* Apply nearest standard value resistor

* Example - 500 Ω termination R : use 470 Ω resistors

Above — A simple crystal or ceramic IF filter sweeping jig. Since the series resistors attenuate the signal, losses occur; but the shape should look clean with minimal ripple. Normally, we builders will also place (or switch in) 50 Ω attenuator pads on both the signal source and detector within our sweep system to buffer impedance mismatch. Comparisons of this simple jig with more precise and complicated matching methods suggest that for many filter sweeps, it might work fine.



Above — My test jig with a Murata ceramic filter soldered in-situ. Keep the resistors *close* to the board. I've pretty much moved to SMA connectors in my lab: they're cheaper than BNC, plus we can buy a wide variety of quality 50 Ω patch cables donning various connectors for low cost. For example, a 30 cm cable with a male BNC and SMA connector on either end.



Above — A poor termination may result in improper bandwidth and ripple — easy to spot in this trace. Click for a trace from a 'gone bad' instrumentation crystal filter: 10.7 MHz @ 30 KHz with 2200 Ω Z in/out. Not really usable with ~ 10 dB ripple.



Above — Older 280 KHz Murata 10.7 MHz IF filters purchased long ago. Low cost = their main attraction, although they too will suffer total obsolescence and a price increase.

I bought some newer, lower insertion loss ceramic filters in the following bandwidths: 280 KHz, 230 KHz, 150 KHz, 25 KHz and 20 KHz. Check their datasheet — most Murata ceramic filters require a 330 Ω termination (preferably resistive) and I keep a filter sweeper jig with 270 Ω resistors as a regular bench tool. 280 KHz was a popular WBFM filter bandwidth in many older high-end FM receivers including my 1980's T-85 Yamaha receiver; my benchmark FM receiver.

Many of us hopeful FM builders, smitten by modern digital gear, fail to recognize the fantastic design achievements made by FM receiver engineers back in the day. All those air-variable, ganged band-pass preamp stages, low noise amplifers and often incredibly complicated and great sounding FM multiplex circuits just blow me away. Perhaps I'm a hopeless analog nostalgic? My T-85 sports 5 ceramic filters [280 KHz and 230 KHz B/W Muratas] and the narrow filters are listener switchable for narrow band Dx.

Ways to Match These Filters with Amplifers



12.2v
39
.01
.01
50 Ω
10 BFT
FT37-43
3K3
2K2
270
J310
50 Ω
.01
3t
s
d
g
1320 Ω
10t FT37-43
100
10.7 MHz

Above — A common gate JFET amplifer drives a 330 Ω ceramic filter. I placed 2 resistors in parallel to get the needed shunt R of 1320; my 2 resistors measured 1316 Ω. The bifilar transmission line transformer provides the 330 Ω Z to drive the filter. Details of the JFET amp come in a later schematic, but the input return loss at 10.7 MHz = 23 dB. I swept this circuit and it looked similar to the tracing with the same ceramic filter in my 270 Ω filter sweeping jig. This particular filter exhibited 6.4 dB of insertion loss.



A
B
68
.01
1K
330
12.2v
5.64v
9.4v
4.93v
1K
820
.01
4.7
2N3904
6.13 mA
68
.01
820
330
12.2v
2N3904
820
820
.01
10
6.13 mA
10.7 MHz

Above — 2 versions of a BJT amp with a 330 Ω input and output impedance. If you read schematics of good FM receivers, often the designers drive the filter with a 330 Ω collector resistor. Click for an example. By keeping the bias and degeneration resistors low and the current moderate, an amplifer with 330 Ω input Z is easy to design [although the input Z will vary with Beta].

I felt surprised that version **A** exhibited a voltage gain of 11.7 despite those low bias and collector resistors. You can stick a filter on either side as shown. Murata recommends a buffer amp between cascaded ceramic filters and you'll see this often in FM receiver schematics from the 1980s or so. Resistors provide wideband termination. Version B is the same amp with a little more degeneration to lower the gain and serves as a design example. I've got the procedure documented here under '*Calculating the input resistance of a common emitter stage'.*


12.2v
39
.01
.01
68
10 BFT
FT37-43
3K3
2K2
.01
330
1K
10t FT37-43
tap @ 3t from
source end
Diode ring
mixer
743.7 nH
3t
s
d
g
1320 Ω
297.5 pF
.01
J310
300 pF
100
49.9
1st order diplexer
1K
330 ohms
input & output Z
820
.01
4.7
2N3904
17.4 mA
S11 for JFET
amp = -23 dB
10.7 MHz

Above — An IF block using the designs shown earlier. I terminated this stage with a 270 Ω resistor and of course removed the mixer and diplexer. 2 sweeps lie below. I'm tempted to tune the JFET drain and couple the transformer with a few links as needed to get a 4:1 impedance ratio. Anyhow — food for thought.



Above — A sweep of the IF block shown above left sans the mixer + diplexer (*two* 280 KHz ceramic filters). On the right lies the trace of the common gate amp driving a *single* 280 KHz filter with its output terminated with a 270 resistor. The advantages of 2 cascaded filters seems apparent, although the slight downward dimple at the center frequency might represent some capacitive loading at the output of the common gate amplifier.

I built a number of other amplifers and swept all of them Click or click for 2 early examples that use active devices instead of series matching resistors on the output. In these circuits, R Term was changed and then the circuit was swept. The tracings looked good.



Above — I built Brian, K6STI's nJFET IF amp. He used it to offset the losses associated with 2 ceramic filters. Click for Brian's fabulous website. I placed 150 KHz 3dB BW filters before and after a J310 and swept — my circuit exhibited a 2 dB net loss which seems quite reasonable.

The 330 input resistor is a load/termination on the input filter and will dissipate some energy and lower the AC input voltage to the gate compared to the usual high Z input resistors we apply in our JFET common source amps — from open circuit to full termination would incur a 6 dB voltage drop. Still, for simplicity versus performance, Brian's circuit looks hard to beat.



Above — 2 ceramic filters in series. I added a small trimmer between the pair in hopes to mitigate any filter skirt distress or ripple. Click for a tracing with and without the trimmer capacitor. You might experiment with the filter coupling and the filter block termination impedances to better their skirts and passband The losses of the above filter block may reach 12-14 dB.

If you don't have a sweep system, I was able to crudely test the amplifers + filters with my 10.7 MHz signal generator and a DSO.

Resistance Bridge

If you go with a BJT IF amplifer, it's possible to measure the input impedance with a bridge and tweak the emitter current and/or degeneration resistor to get very close to a 330 Ω Zin. I keep a drawer with through-hole resistors rated between 1 and 10 Ω for tweaking my emitter resistor values to change series feedback in my common emitter amps.

I first designed a simple 330 Ω bridge for measurement with my DVM. It worked, but the null lacked the depth and resolution we need. Later I improved the sensitivity by adding another coil and changing to a 'scope or SA detector, but after building EMRFD Figure 7.36, I abandoned my bridge. Figure 7.36 just blew me away. The null of a 330 resistor was only a few 10s of microvolts during calibration.

I placed a small 500 Ω pot in parallel with a 120 Ω resistor for the variable resistance. After some basic testing, I calibrated it with a 330 Ω resistor; adjusting the pot for the deepest null and just left it there for testing my 330 Ω IF amps @ 10.7 MHz.

I plan to make Figure 7.36 for VHF and maybe UHF with chip caps plus a small screwdriver adjustable trimmer pot [to get the lowest possible L] calibrate it and make it a part of my test bench arsenal. After getting a null, we measure the pot's resistance with an ohm meter to learn the impedance at the ? port

Considering that our predecessors measured just about everything RF with a bridge, this little circuit suddenly become relevant. A series L and C "add-on" circuit shown as Figure 7.39 may be placed in series with the ? port and device under test to deepen the null in the face of reactance. Bridge circuits form the very essence of RF measurement. Yes Bobby, we can measure impedance without a VNA.

2. A Basic Colpitts VCO

FM TUNER VCO
TUNE

Above — My completed Colpitts VCO. *I installed the unlabelled, left-sided pot in case a potentiometer is required for future AFC circuitry changes. It's not hooked up.*

I reviewed some 1970's FM receiver schematics to learn that before PLL-locked VCOs dominated, often Colpitts VCOs were locked onto a strong frequency with Automatic Frequency Control (AFC). Local oscillators tanks often employed a inductor plus an air variable capacitor that tuned from ~77 to 119 MHz with a varactor for AFC. All the tuning and front-end filter air variable capacitors were ganged together and I'm sure alignment took some skill.

Some VCOs tuned with varactor(s) instead of an air variable cap — this is what I wish to do. Varactor tuned VCOs usually suffer more thermal drift than air variable capacitor versions.

AFC compensates for VCO thermal drift by a seperate varactor with its control voltage line DC coupled to the FM detector through an R-C low-pass filter. Any difference between the VCO frequency and the desired FM frequency produces a proportional DC voltage. The DC control voltage changes the oscillator to the desired frequency by re-tuning the AFC varactor within this feedback loop, albeit over a limited range. AFC is unsuitable for weak signal DXing, since it may pull the receiver onto a strong adjacent signal. Many 1970's FM receivers supplied an AFC defeat switch.

I remember 1 old FM receiver in my parent's home that stayed locked on 1 frequency for years thanks to AFC.


6t FT37-43
FT23-43
6t 2t
in
LM78L08
out
10
.001
.001
510
50 Ω
15K
.0047
.001 C0G
100
12.22v
98.5 MHz – 119.4 MHz
VCO for 10.7 MHz IF
PN5179
10K
.001
J310
5 pF
C0G
2.2 pF
C0G
.001 C0G
d
J310
g
s
100K
BB639
Cx
x2
100 K
150
.001
8.2 pF C0G
2K2
100K
BB639 x2
~ 125 nH
air core
150K
5K
Tune
100
150K
10
.001
.001
2.2 µF
.001
3K9
AFC Circuit
.0047
AFC in

Above — The schematic of my version of a JFET Colpitts VCO (with AFC) that lacks the standard gate to source feedback capacitor; the intrinsic capacitance from the J310 gate to source provides the feedback needed for oscillation.The 8.2 pF bypass cap was determined on the bench — too little, or too much C decreases output voltage, or snuffs out the oscillator.

I just couldn't bring myself to make a VCO with a BJT, since on my bench at least, they suffer more thermal drift than JFET-based oscillators. I built with a mixture of SMT and hole-through capacitors and resistors. The anti-parallel arranged hyperabrupt varactors were found on eBay. Click for a rear photo of the project chassis. The gold colored jack is an SMA connector.

I bench designed this VCO and it took many hours to find the correct amount of L and C for the resonator to give a low distortion, sine wave output across the ~21 MHz tuning range. This meant soldering in and removing these tank components frequently. Click for the lowest frequency output. Click for the highest.

In the example local oscillators I reviewed, the engineers made no attempt to level off the signal that normally increases in AC voltage as you increase frequency. I also ignored levelling. Presumably the designers didn't worry with leveling the oscillator output in their superhet receiver as long as the output voltage sufficiently drove the mixer into complete switching. Levelling would add cost and complexity. This isn't a lab grade RF signal generator — that's for sure.

At present, the AFC varactor pair is disconnected since I won't know how strongly to couple it with Cx until I have a working detector. Also I will need to experiment to determine the best R-C time constant for the low-pass filter; likely the 2.2 uF capacitor will need an increase in value.

With the 3K9 Ω resistor under the 5K tuning pot, I keep at least 5 VDC on the tuning varactors or the VCO would stop running as I tuned the pot towards CCW. The coil = about 3 turns of 16 gauge wire on a 5/8 inch bolt. (Despite Canada going metric in ~1975, they still sell nuts and bolts in inches at our hardware stores). The stiff wire prevents the inductor from turning into a "microphonic" spring when the VCO is bumped. Click for a photo. The nominal L = ~ 125 nH, although I bent and manipulated the coil so it sat attached to the copper clad board with no tension and then squished or expanded the turns to establish my lower band edge.

In many FM receivers, either a single or balanced dual-gate MOSFET mixer was driven by a high impedance buffer/amplifer. If I mix with a 2-gate MOSFET, I'll insert a common gate JFET amplifier on the IF strip to boost the LO output impedance and AC voltage.

The feedthrough capacitors are 0.0047 µF - they were on sale so I bought them. To prevent a parasitic high impedance when placed in parallel with my standard 0.001 µF bypass caps, I placed a series 10 Ω resistor.

I enjoyed this crazy design; trying to replicate a relic, but popular local oscillator idea from decades ago. Let's hope I did it justice. Perhaps future VHF stuff on the FM and even 2 meter band will involve an Si570 and PIC, Arduino or other microcontroller? This simple VCO will do for now. My greatest passion lies in designing and building the front end.


98.2 – 119.4 MHz VFO
Tune
air
air
104 nH
1.9 - 9.7 pF
2 pF
NPO
1 pF
COG
100 pF
COG
10K
15K
1nF
100
47
12.22v
1nF
150K
1nF
11.53v
1 nF
50 Ω
200
J310
1 pF
COG
4.56v
6.76v
100K
220K
15 pF
COG
3K3
10 pF
COG
470
4.46v
1nF
5 BFT
FT23-43
J310
2.55 mA
PN5179
15 mA

Above — A well-buffered, bench-module, high-side VFO I sometimes use for broadcast FM band mixing into a 10.7 MHz IF. The output at 98.5 MHz = -5.35 dBm, perfect for switching Gilbert cell mixers with a little padding or amplitude tweaking. Click for the output of the Colpitts only with a 10X probe @ 120 MHz. With care, you can see the second harmonic in the 'scope tracing — click for the SA tracing that shows the 2nd harmonic 27.5 dB down from the carrier. Click for a 'scope tracing with my MMIC bench module amplifier from VHF Veronica connected; the amp exerts some low-pass filtering that cleans up the signal somewhat.

---

3. DC-DC Converter for VCOs

Until now, I ran a maximum reverse DC voltage of ~12 volts in my varactors. For wider VCO or L-C filter tuning, builders may chose 28 volt varactors such as the BB535 or BB149A and boost the 12v supply up to 28v with a DC-DC converter. Some build inductorless converters pulsed from 555 timers, or use CMOS voltage converters like the CL7662, or Si7661 to make a doubler. As an RF constructor, I like working with coils and built the following circuit:

DC–DC CONVERTER
SET DC
28V
OUT

Above — Bench module: 28v DC to DC converter. While containing no tuning control pot, my build places the zener diode regulator control potentiometer on the front panel to allow fast-tweaking of the output voltage from ~21-30 VDC depending on the load. Click for the breadboard photo.


Regulated DC Converter for VCOs
28v
Output
molded choke
12.21v
470 µH
molded choke
470 µH
560
470 µF
50v
+
+
+
+
22 µF
22 µF
1N4148
1N4148
100 µf
50v
10K
2N3904
2N3906
10K
10K
150 pF
set
VDC
100K
8.2-10v Zener
Tune
E X A M P L E
4K7
10K
500
Fine tune
22 µF
4K7
R
4K7
2N3904

From circuit design of Matjaž, S53MV
Presented by permission of Andy from UKW-Berichte/VHF-Communications

Above — My regulated 28v converter for varactor tuning adapted from a design by Matjaž, S53MV. I pulled this circuit from his *amazing* 2-part article with circuits that span from 11 GHz RF to DC. *See the reference articles below*. I filtered heavily and at switch-on, my circuit draws ~ 50 mA, but then drops to ~ 11 mA after the capacitors charge. The 10K *[set VDC]* trimmer pot allows you to dial in your desired output voltage and thus this converter may work over a wide range of DC power supply voltages.

The tuning control(s) might be a single potentiometer, or even seperate pots for tuning 2 different VCOs. In the above schematic, I show 1 possible tuning scheme: a 10K coarse tuning in series with a 500 Ω fine tuning potentiometer. R keeps some minimal reverse DC on the varactor(s) and is optional. Again, my bench module DC converter omits any tuning controls — these are built into the circuit containing the varactor diode(s).

The oscillator frequency varies slightly with the set output voltage. Click for a screen capture at ~32 VAC with a 10X probe placed on the PNP emitter. In another test, with no load, I watched the coil's magnetic field collapse and ring in this cool 'scope capture. This is why I love deep memory DSOs so much.

VHF
COMMUNICATIONS

TV Satellite Receive System Part 1 : Low Noise 11 Ghz Down Converter ---- issue 4/86

TV Satellite Receive System, Part 2 : Indoor Unit ------- issue 1/87

http://www.vhfcomm.co.uk/

Above — Andy, G8ATD who owns VHF Communications magazine granted me permission to show the DC converter circuit. His magazine archives provide a treasure trove of useful circuits from VHF to Microwave and it's clear Andy passionately spent lots of time publishing the magazine until 2013, plus scanning and organizing the archived material.
Although VHF, UHF and microwave focused, much of the concepts and learning can also enrich your HF exploits.


VHF VCO
45.4 - 57.7 MHz
2.02v min tuning voltage
12.22v
.001
C0G
3K3
10K
.001
C0G
J310
5.92v
470 pF
C0G
220 pF
C0G
28.0v
150K
air
100K
47 pF
C0G
10K
220K
.001
C0G
47 pF
C0G
2K2
680
22 µF
2 - 4.7 pF
196 nH
BB639

Above — A "quicky" VCO thrown together to test the DC-converter. Click and click for the output with the tuning pot set to fully CCW and then

CW. The 680 R keeps about 2 volts on the varactors with the tuning pot set to CCW.

In the reference articles cited above, you'll find 2 HF-VHF Hartley VFO designs that tune over a 20 MHz span thanks to 28 volt varactors and careful design. In yet another UHF circuit, a 1 octave tuning span is realized with the author's specially designed VCO. Truly hardcore design from a great teacher — I crave exposure to the work of such authors.



Above — A photo of my "quicky" VHF VCO. 73!

---

4. Supplemental Web Page #1

Click for the first supplemental web page.

---

5. Miscellaneous Photos or Figures



Regency
TRANS
OFF | VOL
SQUELCH
MIC
F1
F2
F3
F4
BTL-304
VHF-FM
IVER


743.7 nH
297.5 pF
calculated
300 pF
used
49.9
1034.6nH
243.6 pF
240 pF
213.9 pF
220 pF
Chebyshev
908.1 nH
49.9



1st order

10.7 MHz IF Diplexer

2nd order

Oct 19, 2013

VE7BPO



RF — Test and Measurement

Sundry Experiments 2012 - 2013

This page shows some of my better non-VHF experiments for 2012-2013.

Although VHF and UHF excite me greatly, It's always fun to build at HF, or even AF.

Section 1: I explain why you might see sweeps that look like oscilloscope tracings on QRPHB: they're devices swept with equipment designed by Bob, K3NHI. Bob's work simply amazes me — full-on, creative precocity.

Section 2: An LM1875 AF power amplifer test.

Section 3: Three Questions with Jason, NT7S.

Section 4: EMRFD Experiments — A 1-on-1 Tracking or Offset Phase-locked Loop.

Section 5: Boot-strapped Popcorn AF Feedback Pair.

Section 6: Non-Mechanical Iambic Paddle.

Section 7: A Journey Above HF.

Section 8: Popcorn AF Amplifier — Reprise

Section 9: The Progressive Receiver by John, K5IRK and Wes, W7ZOI

Section 10: Miscellaneous Pictures and Figures

---

1. Analog Sweep System

Today, advanced experimenters might build a network analyzer/sweeper incorporating a microcontroller, a DDS, or Si570 based frequency synthesizer, plus the needed analog RF circuitry. I went another direction: the Bob Kopski, K3NHI sweep system — all analog, no lines of code and probably 4X the bench work. I show some photos, traces and text in hope it might inspire you to pursue your own sweep system — digital-based or otherwise.


K3NHI Sweeper System
Timing module
Trigger or Ramp to X input of DSO.
Ramp voltage to RF VCO
'scope (DSO ideal)
RF module
DUT
AD8307 Power Meter
Y
X
This module is specific to the task at hand. One box is 0 to 100 MHz for LC filters. Another is narrow in the few MHz area for crystal filters.

Above — The K3NHI Sweep System macro diagram drawn by Wes. The resultant trace looks like the output of a tracking generator plus spectrum analyzer. What I like most is that I'm measuring with my "tough" 'scope and need not worry about input power and so forth like we do with expensive RF test gear. I simply love measuring signals with my oscilloscope. Testing circuits with Bob's sweep system compels me to treasure component-level analog design and renews my passion afresh.


MANUAL
RAMP
MON
OUT
TUNE
IN
RF
50Ω
RF IN
50Ω
OFF
MAX SECONDS
MODE
MANUAL SWEEP
HI
LO
AVG
RATE
.2
.5
1
.1
2
.05
5
10
CENTER
WIDTH
SWEEP
DC
S/S
RUN
AUTO
MAN
CAL
X-AXIS
Y-AXIS
15V
RDY
5.3V
1-SHOT
RAPID RESET
16V
TRIG OUT
OUT
OUT
OUT
15V
MAIN

Above — 3 components of my K3NHI sweep system. Click for a higher resolution photo. To date, I've made the Utility Sweep Generator (time base) *on the bottom*, a 1-118 MHz VCO with clean and level output *top left*, an AD8307 power meter optimized for sweeps *top right* and a crystal filter VCO *shown later*.

Building Bob's Utility Sweep Generator proved difficult. Although technically just a ramp generator, this 1 is calibrated, provides high isolation between the X and Y channels and will sweep *anything*. The power supply has 8 different regulated DC voltages including ~ - 3V. I may use it as the time base for a spectrum analyzer project 1 day.
Bob gave me permission to post the schematics: One Two Three IC1-5 is an LM324 op-amp. Doc 1 Doc 2

Email me for some build notes.

Click, click, or click for photos of the 1- 118 MHz VCO. Click for the schematics. One Two

I show a bare-bones AD8307-based Power Meter (PM) on the **RF Workbench 5** web page, however, to augment the PM for sweeping, I added input compensation, plus some tweaks from Bob's QEX articles: Bob Kopski, K3NHI — An Advanced VHF Wattmeter, QEX, May/June 2002 *and* Bob Kopski, K3NHI — A Simple Enhancement for the Advanced VHF Wattmeter, QEX, Sept/Oct 2003.

I strongly recommend you build Bob's power meter (referenced above) if you're contemplating a power meter build.


9v
5v
78L05
10
pos
+
.1
10
10 µF
22 µF
3K3
22 µF
15 pF
.1
neg
RF
470
10 nH
.01
NC
51
8
7
6
5
1N4148
+ 8.3v
AD8307
25 mV/dB
10
U1a
4
8
5K6
9
11
calibration
1K
5
U1b
7
10 mV/dB
1
2
3
4
.1
NC
.001
-0.7v
2K
6
5v
3K9
1K
DC offset
5K
3
U1c
1
2K7
1K
DC
2
1 µF
LM324
AD8307 PM
for Sweeps

Above — My AD8307-based power meter. Click for a photo of an early version lacking the level shifter. The level shifter, or DC offset control allows precise Y axis control to enable a resolution up to 1mV/dB when set up properly in the DSO. With this resolution, it's possible to see filter ripple.


MANUAL
TUNE
RAMP
IN
MON
OUT
RF
RF IN
OFF
MAX SECONDS
MODE
DC
S/S
MANUAL SWEEP
HI
LO
AVG
RATE
SWEEP
CAL
.2
.5
1
.1
.05
2
5
10
CENTER
WIDTH
RUN
AUTO
MAN
RDY
5.3V
X-AXIS
Y-AXIS
15V
1-SHOT
RAPID RESET
16V
TRIG OUT
OUT
15V

Above — The K3NHI sweep system in action. This photo shows the power meter with the (later) added DC offset control. Using the offset control potentiometer, I'm able to examine the top of a signal peak at 1 dB per division with various spans.

7 MHZ BANDPASS
BW-237 KHZ IL-2.1 DB

Above — I swept a 7 MHz band-pass filter bench module.



Above — A sweep of the above 7 MHz band-pass filter. At the time I was still learning system calibration and remember feeling blissful that I made such a cool sweep system.



Above — A sweep of the 7 MHz band-pass filter with a tracking generator plus spectrum analyzer for comparison. The span differed from that used with the K3NHI sweep system, however, I'm sure I'll get better with the K3NHI system over time.



Above — My build of the K3NHI *Hartley* VCO for sweeping crystal filters. I ordered a 4 mm tuning knob for the 10-turn "Manual Tune" potentiometer used to help center the sweep in my 'scope. This 10-turn pot, a DIP switch with C's and a secondary L, plus two MV209 varactors allow narrow resolution sweeps (< 5 Hz nominal) within a ~2.5 - 18 MHz range.

I monitor the sweep frequency on a counter via the VCO monitor port and all the tweaks on this VCO and the Utility Sweep Generator allow easy filter centering. Click for a breadboard of the VCO with the first buffer and a temporary BNC connector for testing. Click for the whole project. The secondary wideband buffer provides strong signal fidelity, reverse isolation and output return loss (22.3 dB) — it draws 61 mA. Click for the VCO schematic courtesy of Bob, K3NHI. Click for a side-by-side of a xtal filter as measured with Bob's sweep system plus an N2PK VNA.



Above — I made and then swept a simple ~500 Hertz wide 4.9152 MHz Cohn or Min-Loss filter using 4 crystals.

So now, if you see sweeps on the site that look like oscilloscope tracings, you'll understand how they were created. I've learned so much from Bob's work and his mentorship last Spring. John, K5IRK coached me also.

QRP-POSDATA for October 2013

3 builders incorporated Bob's sweep system circuitry into projects including a receiver, a spectrum analyzer and the following build of the Utility Sweep Generator (USG) by Jay: Jay built some PC boards to simplify the wiring challenge this USG presents. Click 1 Click 2 Click 3. Great stuff — thanks for sharing.

QRP-POSDATA for March 2014 — Poor Hams Scalar Network Analyzer (PHSNA) —



Above — The PHSNA built by Mikey, WB8ICN.

Jerry W5JH, along with Jim, N5IB and Nick, WA5BDU developed this low-cost sweeper/ lab toolkit.

The Poor Hams Scalar Network Analyzer consists of an Arduino UNO R3, plus an AD9850, or AD9851 DDS, a W7ZOI/W7PUA Power Meter and a MS Windows OS based computer. Builders can scan and plot L-C filters, crystal filters, RF amplifiers and such — much like Bob's sweep system — or an HF tracking generator + spectrum analyzer. The PHSNA also measures crystal parameters with little fuss. Connect a return loss bridge to easily sweep return loss measures of the input or output ports of filters, amplifiers, antennas and more. The total cost to build the PHSNA is approximately $50-60 USD.

Mikey graciously sent me some photographs of his PHSNA build. Complete system in his lab with the chassis lids removed for these photos. Monitor photo showing menu choices. Power meter. Mikey's jig to examine crystals with a 12.5 Ω termination. Once you own a calibrated sweep system, you'll wonder how you ever managed without 1.

Thanks again to Mikey for the photos. I built and tested the return loss bridge using the PCB from the PHSNA Yahoo group. Click for a 613 KB pdf file of my build. Nick, WA5BDU web site.

Hats off to Jerry and crew for this open-system project! A Yahoo group called PHSNA serves as the communications hub and houses superb, detailed documentation. You need to join Yahoo to access this group. Then search for PHNSA and while your at it, also sign onto the EMRFD group.

---

2. LM1875 Audio Power Amplifier

I tested the LM1875 AF power amplifer because its specifications look great: 20 watts into a 4Ω or 8Ω load on ±25V supplies and a TO-220 package for easy heat sinking. Of course, for this web site, I tested it with a typical radio experimenter bench power supply; a single-supply at ~ 12 VDC.

This is probably not a great part for Ugly Construction and I *attempted* to return the load ground, the output Zobel RC filter network, feedback loop and input grounds to a central grounding point through separate paths cut paths into my copper board. A better breadboard method might include the so called "star grounding".

I saw RF oscillations on the 'scope and removed them by soldering a 0.001μF bypass capacitor across the input. A 470 pF bypass capacitor did not work well enough. The datasheet describes specific causes and cures for RF oscillations and I've learned they must be heeded. I once found similar problems with an LM380.


10 μF
47K
47K
100 uF
10
100 uF
12.2v
1 KHz
47K
.1
.1
1 μF
1
5
4
1000 μF
10K
.001
2
3
1
8 Ω
LM1875
0.22
200K
10K
10 μF
With a 12.2v Single Supply
Average Clean Power = 856 mW
Quiescent current = 14.5 mA

Above — The LM1875 in the ~suggested datasheet, single-supply set up. This amplifer reminds me of setting up an op-amp. Unlike the LM380, within limits, you may choose the gain to suit your needs. As shown the gain = 25.6 dB. Dropping the feedback R to 100K dropped the gain down to 20.5 dB. For clean output power capacity; it blows away the LM380.



Above — My first LM1875 test breadboard. After the photo, I moved the 0.1 μF RF bypass cap right onto lead 5 — we should carefully RF bypass device power supply leads, but I got sloppy.



DSO-X 2022A, MY51360373: Thu Nov 01 03:44:50 2012

1 1.00V/ 2 4.000µs 200.0µs/ Auto 1 110mV

Acquisition
Normal
25.0MSa/s

Channels
DC 10.0:1
DC 1.00:1

Measurements
Freq(1):
1.0147kHz
Pk-Pk(1):
7.40V
AC RMS - Cyc(1):
2.5646V

Display Menu

Agilent
Persistence Off
Capture Waveforms
Clear Persistence
Clear Display
Grid Full
Intensity 20%

Above — At the maximum power before visible sine wave distortion appears; 856 mW. I listened to this amp while connected to a line-level tape player and an 8 Ω speaker load: very nice. I want to try it with a split +/-15 VDC supply and a star grounded breadboard since a 12v single-supply limits the output power so much. Still, at 12 volts single-supply, this IC yielded the highest clean, average output power of any AF Power chip I've tested: a worthy consideration for a high-grade receiver.



DSO-X 2022A, MY51360373: Thu Nov 01 03:45:01 2012

1 2.00V/ 2 4.000µs 200.0µs/ Auto 1 110mV

Acquisition: Normal 25.0MSa/s

Channels: DC 10.0:1; DC 1.00:1

Measurements:
Freq(1): 1.0141kHz
Pk-Pk(1): 8.1V
AC RMS - Cyc(1): 2.9854V

Above — 'Scope tracing; I advanced the 10K volume pot to drive the amp into clipping.

---

3. Interview — Three Questions with Jason, NT7S from Etherkit

I follow 2 English language amateur radio blogs — 1 is Ripples in the Ether by Jason, NT7S

Possessing a modern flare, Jason, the blogger, gently but resolutely challenges some of the cliquish, dogmatic thought and behavior that tarnishes amateur radio, or just blogs about fun stuff. He writes well — creating an emotional dialog that stimulates thought and reflection. We get a sense that he cares about our radio hobby and wants it to grow and improve.

Jason, the man behind Etherkit, champions a modern, open-source vision that I find both positive and refreshing.

1. Tell me about your decision to embrace the open source software philosophy for your hardware in a time where proprietary code, copyrights and patents still hold strong. How do Ham Radio equipment sellers benefit from code sharing?

I believe that the open sharing of knowledge has always been one of the cornerstones of our amateur radio community, going back to its earliest days. So the open source/open hardware ethos has always resonated with me in regard to our hobby. I started Etherkit with the intention of providing a small bit of income to my family and as a way to promote the idea of open hardware within the ham radio community at large. I have no illusions of becoming the next Elecraft, but I hope that I can build up a stable of affordable and fully-open ham radio kits that will be "hackable" and extensible for the motivated experimenter. I do this by providing the full source code for my microcontroller firmware, all of the PCB design files, Creative Commons licensed documentation, and programming ports for my products. I've already seen some neat examples of customers extending my first product (the OpenBeacon MEPT kit) by doing things such as adding in WWVB time discipline and pairing it up with a Raspberry Pi for cheap automation. I hope that others will take my code or my circuits and re-purpose them in their own work, even if they don't buy my products.

I am not an open source zealot and do not begrudge the large majority of vendors who choose to keep their intellectual property closed. However, most of what us smaller companies do is not on the cutting edge of radio. We leverage the knowledge and works of those who came before us. Perhaps if I created something wholly-new that would be patent worthy, I would consider keeping it closed, but that's not the kind of products that I'm able to develop as a one-man operation. We do not copy the designs of others, but we do take concepts that are for the most part well-tested and come with new ways to implement them. Because of that, it's my personal opinion that I have a duty to keep my designs open.

In the open hardware world at-large, there is a discussion about whether open source hurts your own business prospects. There are still some debatable points in that discussion, but I think it has been shown that if you look at the entire balance, open hardware is a good thing for smaller companies. One of the largest concerns is that under most open source licenses, a competitor can just clone your hardware and undercut your sales. That is a genuine concern, but I think that products such as Arduino have shown that if you make a quality product, most folks will recognize that quality and stick with the original.

Even if others buy a clone of your hardware, in all likelihood, that may be strengthening your brand identity (as long as that vendor isn't stealing your name). Another concern is that a customer can just copy your product for themselves. To that, I say good!. Because of the work and costs involved (economy of scale), it's going to be time and/or money consuming to make that copy. It's probably cheaper and faster to just buy the kit. The reason you copy it for personal use is because you love working with the technology. Which is exactly what I want to encourage. You may lose a small bit of sales, but I think it gives you more name recognition in the end.

2. What’s it like being a vendor at Dayton?

To be clear, I wasn't a vendor at Hamvention in 2012 (hopefully I will be there by 2014), but I was a vendor at Four Days In May at the Fairborn Holiday Inn. It was a wonderful experience to get to sit with the big names in the QRP world, selling my wares. I got the opportunity to meet tons of QRPers and build up some good relationships. Online sales are wonderful for the ultra-small operations such as myself, but nothing beats actually meeting your customers face-to-face, especially when you are at the world's most well-known QRP convention.

3. In industry, SMT parts are normal and hole-thru might better be called “hold-over”; what’s your view on kitting products with SMT parts?

We've seen some SMT kits within the QRP world, but they still are more of an oddity than anything else. I understand the concerns that people have with SMT assembly, but I think that there is still a lot of trepidation that builders needn't have. It's my opinion that SMT construction with "larger" components such 1206 or 0805 is well within the capabilities of the average kit builder. I also believe that once you are comfortable with SMT construction, it is probably faster and more efficient than through-hole construction.

OpenBeacon is a through-hole product, but I have had a QRP CW rig in development for the last two years that is a SMT design. In beta testing, I've found that one of the biggest challenges in kitting is that I have to clearly identify each and every component. With a through-hole kit, you can just throw all of the resistors or all of the capacitors together because they are clearly marked. Not so with SMT. You have to have a system to keep each value separated from the others and marked with a value. SMT resistors and semiconductors have a laser-etched value, but it's nearly impossible to see by naked-eye, and SMT capacitors generally have no markings at all.

So I have had to compartmentalize each strip of components of the same value cut from a reel, and mark them with a sticker. That is pretty costly and time-consuming. I'm hoping to find ways to streamline this process so that I can release SMT kits without the large time investment that it currently takes.

---

4. EMRFD Experiments — A 1-on-1 Tracking Phase-locked Loop

I built the 1-on-1, or offset phase-locked loop circuitry described on EMRFD page 4.22 and share these schematics in faith you'll create your own. Rich with wisdom and reason, this section lies among the best topics from EMRFD. Please read Wes' notes since I won't repeat his narrative — only supply a few ideas and measurements. In the article closer, Wes suggests some modern parts to raise performance and I applied all of them with the exception of the 14 MHz VCO.

Rather than building the main VCO with divide by N circuitry to allow multiband use, I copied the original 14 MHz oscillator verbatim. Why? Well, I wanted to test this VCO: a design that wisely doesn't expose the varactor to high impedance or signal amplitude and thus avoids forward-biasing the single tuning diode. I've discussed this before on the QRP Modules 2011 web page under **7 MHz VCO Experiments**. Also, I really just wanted to learn about PLL circuitry. The Figure 1 macro schematic below illustrates this project.

In my circuit, a frequency stable 14 MHz VCO = **the goal**; the rest of the circuitry supports this.


Loop Filter
14 MHz
VCO
VCO
out
-
+
Low-pass
1.5 MHz
Phase-
Frequency
Detector
12.5 MHz
Clock
Oscillator
1.5 MHz
MTO (VFO)

Figure 1


1.5 MHz VFO
Manually Tuned Oscillator
12.2V
.047
to
buffer
VCC
+
10 µF
in
LM7805
out
.22 µF
100
J310
1000 pF
C0G
Trim
Tune
.22 µF
470 pF
x3
poly
1200 pF
C0G
to
buffer
470 pF
x3
poly
1200 pF
C0G
1K5
100K
150 pF
C0G
4 - 10 pF
6-30 pF
14.7 µH
T50-6
Tunes 1.50 - 1.52 MHz

Above — The 1.5 MHz VFO. In his modern writing, Wes calls this the MTO, or Manually Tuned Oscillator *in the context of a tracking PLL.* I wound the L with # 30 AWG wire on a T50-6 toroid.

My MTO exhibits a low tuning range (only 1.50 to 1.52 MHz) since I built in a box with a small air-variable capacitor that swung only 24 pF and I ran the "Colpitts capacitors" at 2610 pF to keep phase noise low. This box normally holds a VHF oscillator and I just removed the main board and swapped in a 1.5 MHz equipped copper board. I won't keep this PLL and thus sticking the 1.5 MHz MTO in an existing oscillator chassis with a grounded tuning shaft and feedthrough capacitor helped save money and time.



Above — The built 1.5 MHz MTO. With temperature compensation from 6 stiff-leaded, 600 VDC, 470 pF polystyrene capacitors, my frequency drift measured between 3 and 4 hertz per hour upward at room temperature. Properly designed + built + temperature compensated L-C oscillators at 1.5 to 3.5 MHz may exhibit stellar temperature stability. See the VFO - 2011 web page for some tips.

Since this VFO was sublimely frequency stable, I didn't possess the guts to change up the L-C ratio to garner a wider tuning range from the small air-variable tuning capacitor. A 100 pF, or greater delta-F air-variable tuning capacitor would stretch the VFO (MTO) tuning range nicely.


1.5 MHz VFO Buffer
12 VDC line
47
10
.1
.1
10K
10 pF
Q1
10K
150
22
.1
50 Ω
A
.1
.1
10K
Q2
470
T1
Q1 = 2N3904   Q2 = 2N3906   T1 = 12 trifilar turns FT37-43

Above — I designed this buffer last year and it's my new favorite. Click for the original. A 10 pF C0G/NP0 capacitor lightly couples the MTO output to the high impedance of Q1, an emitter follower. Further, a common base amp provides gain and *essential* reverse isolation. You may adjust Q2 gain by changing the degenerative feedback offered by the 22 Ω resistor and 0.1 μF capacitor. For example, decreasing the R to 18 Ω may provide 7 dBm output for a diode ring mixer.

MTO output power = 6.71 dBm.

I transformed the 470 Ω collector resistor impedance to 50 Ω with a transmission line transformer. Even though part of the PLL circuitry involves logic gates, or is at DC; as possible, my circuits employ a 50 Ω input or output impedance to allow measurement with my 50 Ω modules and/or instruments, plus transmission via 50 Ω cables.


13.98 - 14.3 MHz VCO by W7ZOI
12.2v
330
.01
220
.01
12 BFT
FT37-43
2K2
.01
C0G
10K
.001
C0G
100
47 pF
C0G
3- 20 pF
22 pF
C0G
10K
220
4K7
.01
C0G
.01
50 Ω
.01
MV209
2N3906
.01
270
2K2
640 nH
T37-6
1K
.01
C0G
100 pF
C0G
220 pF
C0G
100
22
2N3904

Above — The 13.98 to 14.3 MHz VCO by Wes, W7ZOI (Figure 4.43 in EMRFD). The connector in series with the 1K varactor resistor was an RCA type. Output power = 1.62 dBm. I employed a 3 - 20 pF air variable for the trimmer.


12.5 MHz Clock Oscillator
NC
1
7
12.5 MHz
bottom
12.2v
14
8
fCo = 12.3 MHz
-9.6 dBm
820 nH
820 nH
in
LM7805
out
600
+
.1
1 µF
51
50 Ω
180 pF
390 pF
180 pF

Above — In the original circuit, Wes built his 12.5 MHz crystal oscillator with a single 2N3904. Lacking a 12.5 MHz crystal, I built my xtal oscillator from an old, junkbox 12.5 MHz clock oscillator. A resistor L- matching network drove a low-pass filter to scrub off harmonics, Click for the clean output 'scope tracing at 211 mV pk-pk in my first version. Later, some tweaks gave a final power of -9.6 dBm (208 mV pk-pk). Many authors switch their NE612 mixers with a peak-peak voltage of ~200-300 mV. An AC-coupled 51 Ω resistor on the NE612 pin 6 properly terminates the oscillator to establish the desired drive power and filtering.



Above — Oscillator breadboards: 14 MHz VCO (left) and the 12.5 MHz clock oscillator (right).


-16.38 dBm
96 mV pk-pk
Power Splitter
Measured loss
-5.98 dB
14 MHz in
18
18
18
27
27
27
Adjust as needed
12 dB pad
VCO out
-9.66 dBm
208 mV pk-pk
12.5 MHz
4t
22t
.1
.01
.01
.01
51
22
NC
NE612
1K2
20t
4t
LM7805
out
in
12.2 VDC
.1
.1
51
12 BFT
1.7 MHz low-pass
5 uH
5 uH
2300 pF
5000 pF
T50-2
2300 pF
.1
1K5
1K5
.1
1K
heat sink
100
.1
4.7
24.2 mA
2N2222a
.1
.1
B
50 Ω
2.36 dBm
FT37-43
FT37-43
FT37-43

Above — Click to view the power splitter, mixer, low-pass filter and amplifier schematic. Click for an FFT of the clean 1.5 MHz output sine wave. At this point, the 14 MHz VCO has no DC voltage connected to its frequency compensation varactor. As shown, the mixer products are seriously attenuated by the simple, low-pass filter + keeping the mixer RF port signal amplitude low. The power splitter provides the input for the mixer and also the main output for the 14 MHz VCO. The main VCO output requires 50 Ω buffer/amplifer(s) to drive a receiver mixer, transmitter chain, or whatever.

I inserted the 12 dB attenuator pad to keep my mixer RF port signal low to drop the mixer products amplitude down; further losses occur in the transformer. You can change this pad to whatever is required. I belong to the camp of builders who drive their transmit mixers with low-level RF signals to avoid messy outputs at the IF port.

Click for a breadboard photo of my initial bench tests with the mixer board. A 50 Ω resistive terminator shunts the main VCO output port during this testing. I temporarily insert BNC connectors along my development breadboards to measure output signals with my 50 Ω terminated 'scope, spectrum analyzer, or power meters and *rarely* measure RF circuits with a 10X probe.


12.2v
out
LM7805
in
+
1 µF
.47
10
.01
51
.1
47K
47K
+
22 µF
3
+
7
OPA-27
2
−
6
4
14
2K
2K
74HC74
A
NC
5
6
3
2
4
1
10K
10K
4K7
.01
470 pF
820
A
.1
15K
51
6K8
50 Ω
.1
14
2
3
A
1
7
DC
to
VCO
control
2N3904
2K
13
74HC74
B
9
11
12
10
8
7
B
.1
15K
51
6K8
50 Ω
10K
10K
470 pF
2K
74HC00
4
B
6
NC
5
9
C
8
NC
10
12
D
11
NC
13
Phase-Frequency
Detector and
Loop Filter

Above — Phase-frequency detector and loop filter schematic. 51 Ω resistors terminate each 1.5 MHz input and drive two 2N3904 switches per EMRFD Figure 4.41. The loop filter design from EMRFD works as described, however, if you make a loop filter for a different circuit, casual copying goes out the window. Engineers design their loop filters according to factors including the crossover frequency, VCO gain, the N-division for the loop, etcetera *with software.* Some people and companies offer such software on the Web.

My loop filter 0.01 µF cap was a 1% polyester capacitor, although Wes specs a 10% tolerance in EMRFD. No cheapo ceramic bypass caps here please.



Above — Phase-frequency detector and loop filter breadboard. Click for a photo of the scattered, ugly, working boards on my workbench. Many prototypes look like this on our benches, however, sometimes, they work perfectly until we stick them in a box! Do you relate? Each oscillator belongs in its own metal box with strong bypass and decoupling networks (feedthrough caps reign supreme here) since the 3 oscillators might decide to party together and create havoc.


HEWLETT PACKARD
53181A 225 MHz
FREQUENCY COUNTER
14.000,061,50 MHz
Freq
Ch 1
Gate
MEASURE
LIMITS
MATH
DISPLAY
CHANNEL 1
POWER

Above — My VCO frequency with the 1.5 MHz MTO set at full mesh. Since my MTO only tuned from 1.50 to 1.52 MHz, my VCO only tuned from

14.00 to 14.020 MHz, but that's easily fixed as I've stated. I'm very happy — it locked perfectly and my 14 MHz VCO stayed on frequency at the exact previously measured frequency drift of the 1.5 MHz MTO. When I connected the 14 MHz VCO to my counter without the PLL circuitry, it drifted willy-nilly.

Conclusion

The sense of awe and joy arising from locking a VCO on frequency won't be understood by many. The concepts and circuitry offers many possibilities. If the MTO and VCO exhibit low phase noise, short-term oscillator stability may be fantastic.

The 14 MHz VCO could be a 56 MHz VCO with sequential division by flip-flops to provide output at 28, 14 and 7 MHz with the 14 MHz portion going to the offset mixer. In EMRFD, Figure 4.44, Wes offers 14 and 7 MHz output by dividing the 14 MHz signal from the main power divider output port. The 7 MHz band is low-pass filtered to remove harmonic energy.

Wes extended this circuit by dividing the MTO by a hardware programmable frequency divider so that the difference from the mixer and low-pass filter is 170 kHz nominal. He uses this 'Almost Synthesizer' on the air for his QRP adventures.

While most builders will sensibly jump from an L-C VFO to a kit containing a programmed microcontroller plus a DDS or Si579, it's also fun to play with hardware to learn and ingrain synthesizer concepts + gain bench wisdom.

QRP — PosData for April 17, 2013

For a good read on the offset PLL, consider studying Wes' book **Introduction to Radio Frequency Design**, ARRL, 1994, page 320 and on. *This book is now out of print*. Wes ported the PLL active loop filter design program he wrote for IRFD from DOS to Windows in April 2013. Click and scroll for it. Thanks for this Wes!

---

5. Boot-strapped Popcorn AF Feedback Pair



Above — I designed this AF stage for a builder from Indonesia; a popcorn AF shunt feedback amp based on the work of Douglass Self. Despite only drawing ~ 5 mA, this amp stayed clean until the output voltage exceeded 7.04 volts peak-peak on my test bench. Boot-strapping increases gain and lowers distortion in Q1.

Q2 buffers the Q1 voltage amp from external loading and increases gain.The Q3 current source boosts the load-handling capacity of the Q2 emitter follower. The input R can be raised to reduce sensitivity. The 1K output R could be a 5-10 K volume pot.

---

6. Non-Mechanical Iambic Paddle

Above — The very ugly development proto-board of my half-done non-mechanical Iambic paddle. At some point I'll build the other half (the dah paddle switch) and press it into service. You might also use this circuit as a non-mechanical straight key.


Non Mechanical Iambic Paddle
12.2V
in
LM7809
out
.1
+
10 µF
.1
1N4148
CKT to ground
CD4093BE
14
1
3
5
.22
8
10
2K2
.01
12
11
13
2
7
470K
6
4
9
10K
2N7000
1N4148
.001
1M
On R = 1.7 Ω
680 pF
47K
1N4148
Touch paddle
9v
10K
CKT to ground
2K2
ground to switch ON
9v to CKT
2K2
.01
10K
.01
2N3904
On R = 71.3 Ω
2N3906
1K
7.2 mA test circuit

Above — The schematic for 1 of the paddle circuits. I compared the ON resistance of the BJT switch with the enhancement mode FET and the 2N7000 won: only the FET could key the continuity tester on my DVM.

You may extend this circuit with a 2N3906 switch for paddle-switched 9 volts (or whatever VCC you want). In the bottom right, I connected the PNP collector to an LED and flashed it for fun. The 0.01 µF capacitor on the switch drain or collector bypasses any RF to ground. With higher power RF, you may have to place a similar bypass cap in parallel with the shunt 10K resistor on the 2N3904/2N7000 base and gate respectively.


Agilent
Autoscale Menu
Undo Autoscale
Fast Debug ☐
Channels All
Acq Mode Normal

DSO-X 2022A, MY51360373: Thu Feb 14 13:50:45 2013

1 2.00V/ 2 0.0s 5.000µs/ Auto 1 4.74V

Acquisition
Normal
1.00GSa/s

Channels
DC 10.0:1
DC 1.00:1

Measurements
Freq(2): No signal
Pk-Pk(2): No signal
Pk-Pk(1): 9.2V
Freq(1): 42.733kHz

Above — A 'scope shot of the ~ 43 KHz oscillator generated in the first 4093 Schmitt trigger NAND gate.



DSO-X 2022A, MY51360373: Thu Feb 14 13:51:35 2013

1 2.00V/ 2 0.0s 5.000µs/ Auto 1 4.74V

Acquisition
Normal
1.00GSa/s

Channels
DC 10.0:1
DC 1.00:1

Measurements
Freq(2): No signal
Pk-Pk(2): No signal
Pk-Pk(1): 7.1V
Freq(1): 46.714kHz

Above — Here's the disturbed oscillator output *just* after the paddle is touched: this stops the signal at pin 5 and 6 of gate 2 and kills the AC output at pin 4. The DC voltage across the 0.001 μF cap discharges through the 1 megohm resistor pushing pin 10 HIGH to turn on the 2N7000 (or the 2N3904). Normally, pin 10 is LOW since the rectified output of the undisturbed ~43 KHz oscillator goes to both pin 8 and 9.

A fun circuit for a Saturday afternoon...

---

7. A Journey Above HF

This project began as a 14 MHz low-noise amplifier build, but ended up with me learning more about SMT breadboard techniques and suppressing spurs. A short exploratory/descriptive account of my bench journey plus some photos follow.

VAT-6
6 dB ATTENUATOR
50 OHM

Above — I'm slowly adding SMA connectors and pieces. Since modern consumer digital network engineers use them, they're abundant and often rated from DC to 18 GHz; more bandwidth than I'll ever need.

I'm also building with evermore SMT components and just love it. Through-hole (I prefer to say hole-through) stuff continues to disappear like lemonade on a hot August afternoon.

Above — The schematic of my version of Victor 4Z4ME's feedback amp (FBA) as tested at 14 MHz: he emailed me a paper and provided some online support. Click for another version from December 2012. Typical noiseless FBAs suffer from poor reverse isolation, however, Victor runs the collector to base feedback through an asymmetrical 3 dB power combiner/splitter that boosts port isolation, defines the gain, plus sets the input and output impedance.

Strong virtues of the asymmetrical power splitter — fully utilized in this design include a very low loss on the input side (the 1 turn side) and a much higher loss ont the feedback side that allows the feedback to defines the input impedance on one side while exerting a negligible impact on noise figure and dynamic range on the other side. Victor measured a noise figure of 1.5 dB using a MRF586 BJT. Thanks to Victor for the information and design.

For strong IMD properties, I ran 50.6 mA total stage current into a gorgeous, low-noise, NE46134 NPN transistor with a fT of 5.5 GHz. Using VHF-UHF techniques, I built with mostly SMT parts on 2–sided board using copper wire vias to connect the 2 copper surfaces. I discussed the wrap-around bias technique in 2011 as number 1.



Above — My prototype breadboard with dremel cut islands for soldering the size 1206 or 0805 SMT parts, plus a few hole-through items. Carving an island for the SOT89 transistor package proved difficult, but even I (a challenged dremelist) did it.

Woe to Oscillations: Like misplaced car keys, oscillations may remain hidden unless you search for them. Often, the only difference between a proper oscillator and a regular amplifier is we *want* the former to oscillate. To check for instability, we might use our high bandwidth scope, or a spectrum analyzer, but many will have to find spurious RF with basic, DC - HF bandwidth test equipment. In any case, just do your best. To some extent, unwanted oscillations are the *elephant in the room* that few talk about. Well, it's okay to think, talk and feel some emotions about them.

Sure enough, when I connected a 14 MHz signal to the amp's input and a 50 Ω terminated 'scope to the output to measure gain, my sine wave had 2 or 3 others on top of it. In the 4Z4ME amp, the PNP bias transistor can be a source of AF to HF oscillations.

Victor wrote: "The circuit has a low frequency amplifying loop that goes through both transistors. The PNP transistor does not invert the signal (it is a common base amplifier) and the RF transistor inverts so it is a loop with 180 degrees phase shift (negative feedback). The various decoupling and RF coupling capacitors in this loop add phase shift on this low frequency loop. If the accumulated phase shift adds to an additional 180 degrees and gain is larger than 1 you have oscillations. The simplest way to solve it is to make one of the capacitors very large so it will add only 90 degrees phase shift but it will drop the gain at the higher frequencies where the other capacitors start to add phase shift to be less than 1 so there are no conditions for low frequency oscillations. This technique is called "Dominant Pole". That's the reason that I suggested to connect a very large capacitor to the PNP transistor".

I found my oscillations disappeared with a 0.1 μF collector bypass cap on the PNP (Cx on my schematic). The 0.1 μF cap on the PNP collector was critical – a 0.22 μF failed to work, as did a .001 μF --- but a 0.1 μF held it stable. In another 2N2222a-based 4Z4ME amp with 0.01 μF input and output caps, it took a 10 μF capacitor on the PNP collector to snuff out some ~766 Hz oscillations.

We don't use a wrap-around PNP bias with our RF oscillators — that's asking for trouble.

I aso measured oscillations at ~ 372 MHz with my spectrum analyzer. A collector 10 Ω R killed these UHF oscillations and after that I saw no spurs from .001 to 1 GHz. (I should have made the dremel cut right close to the NPN collector for the 10 Ω resistor. I hoped there were no oscillations above 1 GHz because I can't measure them.

Finding oscillations:

Many builders lack a spectrum analyzer, let alone 1 that goes up into UHF bandwidth. I'll share a few tips I've learned on the bench that don't require expensive test gear:

A 10X scope probe on the drain or collector of an amp may sometimes reveal oscillations up to the maximum 'scope bandwidth — set your 'scope vertical scale for high sensitivity. This provides direct measurment of oscillations.

Indirect methods to infer unwanted oscillations also lie in our armatorium. I learned this trick from Wes: Place the circuit under test in your normal gain measurement set up with an oscilloscope. Then vary the DC power supply voltage slowly and smoothly — your measured 'scope voltage changes should also track slowly and smoothly. You may see an AC voltage jump as the amplifier goes into and out of oscillation with the DC power supply tweaking. After finding this oscillation caused AC voltage spike, you work to remedy it with a variety of means such as better bypassing, changing bias voltages, shielding and locating breadboard errors.

Sometimes if you put your finger near the active part while watching the bias voltage or current you may see the bias jump around *if* oscillations are present.

My final indirect oscillation busting technique: If you measure the specified/expected gain and return loss on the input/output port, this *may* signal your device is stable — I've noticed this with MMICs where I saw oscillations on my SA, stabilized them and *only then*, measured the expected S21, S11 and S22.

Sometimes, eliminating a hot part proves the best fix! In 2012, a new builder wrote to say that he soldered in a Mini-Circuits DC - 6GHz MMIC; the ERA-2SM in SOT-86 as a buffer for his 3.5 MHz VFO. Anyhow, in the photo were long leads plus no decoupling resistors etc. It sounds like the circuit behaved hyperreactively and *vibrat*ed in spasm. The cure was to eliminate the microwave part and put in a hycas amp built with a J310 + a 2N3904 — we encounter risk when plying the latest, hottest, super-high fT amplifiers sold on eBay with casual abandon.

Practice makes perfect. if you believe learning is experiential and build to learn, you'll learn to build.

Finally, as an amateur, I struggled to choose a SMT ferrite bead and after reviewing many datasheets and application notes I ordered a size 0805, 800 mA part with 120 ohms Z at 100 MHz and its peak impedance at 340 MHz. I'll let you know how that works out.

RF Bypass on our DC lines: As possible, we ought to provide a broadband RF bypass to provide a low impedance to RF from low frequency up to the maximum frequency wherever our FET, BJT, MMIC, etc. operates. For example, you can't just swap a higher gain BF998 (1 GHz) for a 40673 (VHF) dual-gate MOSFET and expect the same stability and bypass requirements can you? At the very least, I bypass G2 of the BF998 with a size 0805 0.01 or .001 µF SMT capacitor and the drain with RF bypass good for 1 GHz.

Wideband RF bypass may solve oscillation issues too.

I tried to apply a broadband bypass in my breadboard, although it gets extremely difficult to think about bypassing RF at > 1 GHz for the QRP homebuilder. Our hobby should include reflection and proper intention at the very least.



Above — A photo of the bottom of my breadboard showing the vias. I made mistakes: we should try to keep the via holes as close as possible to all bypass caps, my 10 Ω collector snubber resistor, collector port, or whatever we need to put at RF ground. The vias connect circuit areas to the large area, low impedance ground plane to minimize inductance. We should also try to place bypass capacitors as physically close to the pins of whatever we're bypassing.



Above — A TG + SA sweep of the gain of my 4Z4ME NE46134 FBA from ~1 to 20.6 MHz. Each vertical quare denotes 10 dB. Each horizontal square = the value specified in the photo. In this case; 2 MHz per division. Maximum gain was ~16 dB.



Above — A sweep from ~ 1 to 200 MHz. This would also make a good 6 meter band amplifer or ????.



Above — A sweep from ~ 1 to 500 MHz.



Above — Bob K3NHI made and swept a 2N5109 version of the 4Z4ME amp biased for ~47 mA emitter current. Here he swept return loss at the amp's input and output from about 1 to 100 MHz. The output return loss of my build was down, however, I didn't own many SMT resistors between 33 and 68 Ω. For example, if the output impedance at the collector is 10 Ω, then the series resistor should be 40 (39) Ω.

I've found that in my FBAs, changing the current and also the transistor type (2N5109 , 2N2222a etc.) also affects the input and output return loss. At HF, it's possible to measure RL with a simple bridge, so optimization is possible.

I learned a lot by building just 1 amplifer and discussing my findings by email with friends. Hopefully the next version I make will show improved understanding and skill.

---

8. Popcorn AF Amplifier for Receivers — Reprise

I've worked on a popcorn audio power amplifier (PA) since 2008 and offer my latest experiments. There's only so much you can do with a single-supply 12 volt AF power amp, but I enjoy improving my circuit.

My power measurement technique is shown as Figure 4 here. To enhance versatility, the following PA's may be coupled to whatever preamplifer you choose. In all cases, I drove the power amp stage with a 5532 op-amp voltage amplifer. The power followers were biased with a 2N3904 amplified diode (also called NPN shifter bias amplifier, or DC level shifter) rather than just a pair of series diodes, since this allows you to dial in just the right amount of bias as you watch the AC signal in your 'scope. I wrote a tutorial that explains how to bias complimentary-symmetry power followers in 2008: Click for the link.


884 mW clean power
Quiescent I = 55 mA
12.19v
47K
47K
22 µF
22
470 µF
22 µF
4K7
BD139
1 KHz
5
8
5532
7
6
4
1µF
1µF
1K
A
6.56v
1 Ω
F
10K
5.82v
2N3904
1.37v
22 µF
5.87v
1000 µF
12K
1 Ω
5.33v
8 Ω
4K7
Gain
1N5 (.0015 µF)
BD140
Figure 1

Above — Figure 1: A popcorn AF power amplifer in full bench *test* mode. Measure the AC with a 10X 'scope probe across the 8 Ω resistor and the DC voltage and current with a multimeter. A distortion analyzer proves useful, but not essential for popcorn circuitry. I also listened to each amplifer connected to a line-level cassette player and an 8 Ω, 15 cm speaker. A 4 Ω speaker doubles the maximal clean power, but I don't own any and stuck to 8 Ω.

Containing no negative feedback, the power amplifer stage runs from the red-colored designator points **A** to **F**. You can AC or DC couple point F to your preamplifer stage as required to apply negative feedback.
As mentioned, you can use the 5532 preamp shown with any reasonable gain (i.e. change the 12K resistor), or opt to replace it with your own design. A low output impedance amplifer best drives the power stage.


1 1.00V/ 2
234.0µs
200.0µs/
Auto
1
129mV
Agilent
Save
Recall
Default/Erase
Press to Save

DSO-X 2022A, MY51360373: Sun Mar 17 05:02:02 2013

Acquisition
High Res
12.5MSa/s

Channels
DC 10.0:1
DC 1.00:1

Measurements
Freq(2): No signal
Pk-Pk(2): No signal
Pk-Pk(1): 7.52V
Freq(1): 1.0183kHz

Save to file = scope_4

Above — The output of Figure 1 in my 'scope driven to the maximal pk-pk voltage just before distortion begins to appear. Obviously this task is somewhat subjective, however, allows comparison of the amps you build on your bench.



DSO-X 2022A, MY51360373: Sun Mar 17 05:00:58 2013

1 320mV/ 2 234.0us 200.0us/ Auto 1 129mV

Acquisition
High Res
12.5MSa/s

Channels
DC 10.0:1
DC 1.00:1

Measurements
Freq(2): No signal
Pk-Pk(2): No signal
Pk-Pk(1): 2.22V
Freq(1): 1.0183kHz

Save to file = scope_3

Above — A 'scope screen capture with the 22 µF level-shifter filter capacitor from Figure 1 removed. Look what happened; the maximum clean signal fell from 7.52v pk-pk to 2.22v pk-pk. That capacitor is essential to get the maximal possible headroom.


865 mW clean power *
Quiescent I = 160 mA
12.19v
47K
47K
22 µF
22
470 µF
22 µF
BD139
1 KHz
5
8
5532
7
6
4
1µF
1K
10K
2N3904
22 µF
1 Ω
1 Ω
1000 µF
8 Ω
12K
1N5
4K7
Gain
BD140
Figure 2

Above — Figure 2 is Figure 1 with the op-amp DC coupled to the level-shifter. I tested the circuit with and without the 4K7 resistor connecting the base of the 2N3904 to the DC supply: it didn't boost the amplifer headroom, nor reduced crossover distortion, so I removed that R.



DSO-X 2022A, MY51360373: Sun Mar 17 05:29:04 2013

1 1.00V/ 2 234.0us 200.0us/ Auto 1 129mV

Acquisition: High Res 12.5MSa/s

Channels: DC 10.0:1; DC 1.00:1

Measurements:

Freq(2): No signal

Pk-Pk(2): No signal

Pk-Pk(1): 7.44V

Freq(1): 1.0183kHz

Save to file = scope_6

Cross over Distortion
DC Coupled
Agilent
Save
Recall
Default/Erase
Press to Save

Above — The Figure 2 amplifer 'scope tracing. At *maximum power*, crossover distortion appeared and I've seen this before. Likely, there is not enough base drive to keep the power followers forward biased. By adjusting the level shifter, I almost removed the crossover distortion, but never eliminated it. This drove the quiescent current up to 160 mA. Yikes!


.766 W Popcorn AF Power Amp
12.18v
47K
47K
470 µF
22 µF
10
12.05v
100 µF
6.79v
BD139
poly
1µF
6.08v
47K
10K
Gain
5
8
5532
7
6
4
1.42v
10 µF
1 Ω
1 Ω
470 µF
8 Ω
1N4148
x2
6.07v
4K7
4.7 µF
poly
470
5.37v
BD140
11.6 mA
6.08v
47K
390 pF
Power Gain 19 dB
Quiescent current
71.5 mA

Figure 3

Above — A variation of Figure 2 employing diodes instead of an NPN level-shifter. To kill the cross-over distortion, I lowered the 4K7 resistor by a magnitude of 10. This gave a maximum clean power of 766 mW with a quiescent current of nearly 72 mA. Head room and quiescent current are inferior to the Figure 1 circuit.


DSO-X 2022A, MY51360373: Sat Jan 19 08:53:59 2013

1 1.00V/ 2 0.0s 200.0µs/ Auto 1 22.0mV

Acquisition: Normal 25.0MSa/s

Channels: DC 10.0:1; DC 1.00:1

Measurements:

Pk-Pk(2): No signal

Freq(2): No signal

Freq(1): 1.0162kHz

Pk-Pk(1): 7.00V

Agilent
Help Menu
Getting Started
Using Quick Help
About Oscilloscope
Language English

Above — The Figure 3 'scope tracing. Click for a 'scope tracing with the signal generator amplitude increased *slightly* to push this amp into clipping.


970 mW clean power
Quiescent I = 48.6 mA
12.19v
47K
47K
22
22 µF
470 µF
22 µF
4K7
BD139
2N4401
5
8
5532
7
6
4
1µF
1µF
1K
A
7.50v
6.83v
10K
2N3904
2.71v
22 µF
68
10 µF
1.37v
1 Ω
1 Ω
1000 µF
12K
4.79v
5.46v
4K7
1N5
2N4403
BD140
8 Ω

Figure 4

Above — Back to an AC coupled power amplifer like Figure 1. I added a set of intermediate followers built with a 2N4401/2N4403 pair. The clean output power now lies at 970 mW with a quiescent current under 50 mA. Adjusting the trimmer potentiometer on the level-shifter even a tiny amount may change the quiescent current dramatically.

I found a bias of 1.37v across the BD139/140 pair removed all trace of cross-over distortion at maximum clean signal power. Just tweak the 10K trimmer potentiometer while looking at your 'scope and decide what bias you prefer. I lower the bias until crossover distortion appears and slowly tweak it to find the sweet spot. Then measure the DC voltage across the power follower base terminals, plus the total stage quiescent current with the signal generator switched off. You might have to repeat this procedure a few times, since trimmer pot adjustment is quite sensitive.

Jerry, W5JH made a PC board. Click for front photo. Click for rear photo.



DSO-X 2022A, MY51360373: Sun Mar 17 06:00:41 2013

1 1.08V/ 2 234.0us 200.0us/ Auto 1 129mV

Agilent

Acquisition
High Res
12.5MSa/s

Channels
DC 10.0:1
DC 1.00:1

Measurements
Freq(2):
No signal
Pk-Pk(2):
No signal
Pk-Pk(1):
7.88V
Freq(1):
1.0183kHz

Save to file = scope_8

Save
Recall
Default/Erase
Press to Save

Above — The Figure 4 'scope tracing.



1.13W clean power
Quiescent I = 91 mA
12.19v
47K
47K
22 µF
22
470 µF
22 µF
4K7
2N4401
BD139
1µF
5
8
7
5532
6
4
1µF
1K
A
7.48v
6.81v
1 Ω
1 Ω
10K
2N3904
2.67v
22 µF
68
10 µF
1.33v
6.14v
1000 µF
12K
1 Ω
1 Ω
4.81v
5.48v
4K7
1N5
2N4403
8 Ω
BD140

Figure 5

Above — I added another BD139/140 power follower pair in parallel. The boost in headroom over Figure 4 was small, but it was nice to break the 1 Watt barrier. This amp sounded great and blew away an LM386 set up for a gain of 20 — more headroom, less noise and boosted warmth.


DSO-X 2022A, MY51360373: Sun Mar 17 06:12:24 2013

1 1.16V/ 2 234.0us 200.0us/ Auto 1 129mV

Acquisition
High Res
12.5MSa/s

Channels
DC 10.0:1
DC 1.00:1

Measurements
Freq(2): No signal
Pk-Pk(2): No signal
Pk-Pk(1): 8.52V
Freq(1): 1.0183kHz

Save to file = scope_9

Above — The Figure 5 'scope tracing.



Above — The Figure 5 breadboard. I built all the AF power amps on this board. Signal caps <= to 1 µF were polyester film, while I employed 10 or 22 µF tantalum caps for the level shifters. Electrolytic caps work fine; especially for the level shifter capacitors. The green power indicator LED drew 10 mA and I subtracted this from the quiescent current measurements.

Depending on the AF gain of your receiver, you might wish to add the familiar Zobel filter; a 10 Ω R in series with 0.1 µF C from the positive end of the output capacitor to ground, or more AF bypassing/ decoupling to the circuitry.

No component values were critical — imbuing the spirit of homebrew radio, substitute parts and measure outcomes.

QRP — PosData for August 18, 2014



1.5W clean output with 12.22 VDC and 122 mA current
Quiescent current = 34 mA [5 mA from FBA]
Drive PA stages with a low impedance.
R = 1K to 4K7 to limit distortion as needed

Above — I built a 100% discrete version of Figure 4 power amplifer with a 2N4401/2N4403 feedback voltage amp that drives the PA stage with a low impedance. Without a low impedance drive, the PA [all the components right of the 1 µF capacitor where you see **PA**] the headroom of the PA section falls down. Thus an op-amp or emitter follower drive works great.

I moved to SMD power transistors: the NXP BCX56 + BCX53. These give a little more output than the BD139/140, and take much less board room. I ran no heat sink other than 8 mm by 4 mm PC board traces for the collectors. A better choice might be the related BCP56 + BCP53 pair in SOT223 since the bigger package of this version better sinks heat.

I determined the optimum emitter resistor for the 2N4401/2N4403 followers = 120 Ω [not 68 Ω as shown in Figure 4]. This drops the the PA quiescent current in half and yields the same performance. If you build Figure 4, change to 120 Ω.

I meant Figure 4 and the QRP POS-Data amp as easy-to-make power amplifiers with a *little* gain. You will have to add voltage gain in some AF projects. For Figure 4, it's easy to change up the 12K resistor, or apply the other half of the 5532. Decouple and bypass better if you get motor boating or hum. 73 de VE7BPO

9. The Progressive Receiver by Wes, W7ZOI and John, K5IRK

When introduced in QST for November 1981, the Progressive Communications Receiver (PR) by Wes, W7ZOI and John, K5IRK set a dynamic range benchmark for dual-conversion homebrew receivers: 94 dB in CW mode. 31 years later, few other home-built radios have ever reached this benchmark.

The PR is a single conversion superheterodyne 80m receiver; or perhaps it's a direct conversion receiver with an extra mixer ahead of the product detector? It's both and that's the point. Further, Wes and John added other bands with another mixer, plus a crystal oscillator, RF filter +/- an RF amp for each band.

You'll see the PR listed as A High-Performance Communication Receiver in ARRL Handbooks from the early 90s or so. ARRL staffers built and enjoyed the PR in their test lab for many years.

After purchasing the 1991 ARRL Handbook and reading about this project, I slowly adopted and entrenched the PR's progressive (modular) approach. When I built and web published my 2 TRF WWV receivers with crystal IF filters, a couple of people wrote that I "grossly over-designed" them, however, other, more astute builders placed a mixer on the front end and turned their TRF into a multi-band superhet like I later did. These builders understood how progressive circuit building works — all PR inspired.

I hope my introduction renews your interest in the PR. Wes and John's article is thorough and complete — I can't add to it, however, I'll share my thoughts along with those from Wes and John all these decades later.

The IF Stage gain comes from 2 dual gate MOSFET amplifiers. The final MOSFET amp drives a BJT differential pair providing 9 MHz RF to the product detector at 50 Ω and signal for the AGC circuit. Wes recalls using a 3N211 in the original MOSFET slots since Doug DeMaw owned a pile of them and contributed some. In some areas, the 40673 was the dominant 2-gate MOSFET soldered by radio home builders back in the day.

An evolved version of the PR Intermediate Frequency stage appeared in EMRFD as Figure 6.50. Wes replaced the now hard-to-find and *expensive* leaded dual-gate dual gate MOSFET with a cascode of J310s. I built this stage and it performed well with my 12.2 VDC power supply.

Jeff, WA7MLH built the general purpose IF system and noticed if the power supply dropped below 12 VDC, the gain control and maximum gain fell off and he wrote to Wes about his findings. Wes later confirmed dysfunction with a lower DC supply. I asked him to recollect this time:

"…. Frankly I don't remember if I went immediately to computer simulations or if I built a single stage. I think I built. Anyway, Jeff was correct, depending upon the FETs that were used. Then I got to plowing into the details of the cascode, this time with SPICE. I was using PSPICE for some simulations, but was in the process of switching over to LT-SPICE. That makes no difference, for I used the same models in both.

Anyway, playing with a single stage showed that the mechanism for gain reduction was that when the voltage on the upper gate was reduced, it did nothing to the upper stage, but it compressed the supply on the lower FET. So far as signal goes, the upper part was nothing more than a common gate stage that passed whatever signal current was there in the drain of the lower part on into the source of the upper part.

But these were depletion mode FETs, the normal thing for most of the JFETs we use. As such, you have to get the gate down pretty low to get the source voltage low enough to be effective in reducing the gain of that lower FET. That's when it became clear that one could use other parts in the upper slot. An enhancement mode FET such as a MOSFET would work well. And just a common bipolar would do the job nicely too..."
Wes, W7ZOI per an email - January 2013.

In QST for 2007, a refined version of the EMRFD Figure 6.50 IF stage appeared with a hybrid cascode amplifier instead of the cascode JFETs (and the 2 original dual gate MOSFETs of the PR). Further, Wes added a third amplifier to widen gain control. The hybrid cascade stage has since gone in 100s of receivers across the globe; ensuring the PR legacy lives on as the modernized hycas version.

Roger, KA7EXM sold kits of the hycas amp for years, however, these kits sold out. PC boards may still be available via his web site. Roger received permission to publish the QST hycas article online:

Above — The now *sold out* hycas IF System kit once offered by Roger, KA7EXM.

To underscore my love of the original PR IF amp, I built a version using SMT dual gate MOSFETs in 2013 and feel the SMT version might be perfect for builders who prefer to manually control IF gain in most situations, but want AGC control now and then. Versions built with the BF998 MOSFET may suffer parasitic ocillations at UHF and so meticulous attention to decoupling and bypassing out to UHF and in some cases double-sided copper board may be required to prevent unwanted ringing at UHF.

If you build the entire PR with the BF998, the VFO output runs about 10 dBm and requires attenuation. Again, please consider UHF oscillation precautions.

Wes and others have built both leaded and all-SMT versions of the hycas amplifer.

John, K5IRK Recalls

I wanted John's recollection of the PR design and build and received the following narrative in late March 2013:

"…One night in late 1979 I had telephoned Wes to chat about QRP and building rigs. During the conversation he told me he had a project and related QST article in mind and asked me if I wanted to participate. He was in the process of writing a book (IRFD) and didn't have much free time, so he needed some help. I told him yes. A few weeks later I received the first schematics and began to gather parts.

Recall that the project started as direct conversion receiver. But it then progressed (hence the title of the article) to a superhet. I choose to build my superhet with a SSB filter as I had already built Wes' CW Competition Grade RX from SSD. During the next year he sent me schematics and a few critical parts thru snail mail. (The Internet and e-mail would come later.) I would build the circuits and report the results back to him. As I recall, we only had about three phone conversations throughout the whole project.

The design was an iterative process. For example, the IF circuitry began with a single 40673, but grew to include two stages. Wes bread boarded this in a mono band version of the receiver at his end. An early audio derived AGC system was replaced by the IF derived circuit that appears in the article. The VFO was also designed twice, as were the Front end Filters and the BFO. More is said below about the design procedure.

I designed the circuit board layouts. The traces on my boards were drawn by hand and etched at home. I sent hand drawn sketches of each of the boards to Doug DeMaw; Circuit Boards Specialists (CBS) then created the commercial boards for those folks who wanted boards. I recall that we sent out layouts to any readers for a SASE. All of my boards were designed and built on double sided PC material with the exception of the VFO board and the Audio Filter boards. This can be seen in the photos. The boards eventually sold by CBS were single sided. All layouts and functionality were confirmed prior to publication.

The traditional design process for a homebrew ham receiver in 1980 started with schematic sketches based upon the intuition and experience of the designer. The total circuit would then be built. Measurements were merely things that were done afterward, something to characterize the result. The PR was different. Individual stages were designed, built, and measured. Negative feedback was used in the critical amplifiers to guarantee that the gains were high enough for reasonable noise figure, but low enough to preserve input intercept.

Only after the individual stages were operational, were they assembled to form a working receiver. Some stages were further modified during system assembly and evaluation. We had no computers available for circuit simulation, although the gain distribution was optimized with a hand calculator. The goal was not just a receiver that sounded good, but a box with good two tone dynamic range.

Once my receiver was completed, I sent it to Wes for MDS and DR measurements. A goal was to compare these measurements with those already done in Oregon. Roger (KA7EXM) took many (if not all) of the photos. Wes then forwarded the receiver to ARRL. They returned it to me when they were finished. Wes refined the article during the final months of the project before it was finally published. I received copies of his drafts, and then offered my feedback.

We had hoped that a "few" experimenters would enjoy building the receiver, but had no idea that it would be as successful as it was. We eventually learned why this occurred: First, the receiver held up well when it was measured at ARRL Headquarters, exceeding the performance of most of the appliances being evaluated at the time. This prompted some League staff members to build the receiver for their own use. This, in turn, prompted them to include it in the Handbook for several years.

My original receiver plays as well today as it did in the beginning. The electrolytic caps on the audio board have been replaced, for they were beginning to go south on me, but that's the only change. I do have a second version that is used for experiments..."

Some PR photos taken by John in March 2013




TYPE XF-92A
C.F.: 9000KHz
NO:
YAESU MUSEN CO.LTD.

"...You will notice a couple of things different in these photos than in the photos in the article. First, tacked on to the Front Panel 365 pF variable cap is a mica trimmer cap.....this is of no significance as I was just messing with lowering the BW upper and lower frequencies to see what difference it would make....None is the answer..." *John, K5IRK.*





"...In the above photo you will see the addition of the 30 meter band to the RX with the diagonal front end filter board and the Xtal Oscillator attached to the BFO Box's wall that was added some years after the article was published…." *John, K5IRK.*

High-pass plus Peaked Low-pass Filter

If you know me, you know I love the peaked low-pass filter both at RF and AF. This adoration came from studying the PR and other work published and shared privately to me by Wes. *A good reference = The Peaked Lowpass: A Look at the ultraspherical filter by Wes for Ham Radio, June 1984.*

While the high-pass + peaked low-pass filter placed ahead of the second mixer in the PR wouldn't likely go in a modern W7ZOI design, its narrow-band LC filtration generates a roofing action when the receiver uses converters for bands other than 80 meters. The result is that much of the DR obtained in the single conversion version is retained in the dual conversion receivers.


File
About GPLA
S21 =
S11 =
S21 Ref.
gpla-12.4 28july12 w7zoi
Click to List Circuit
#, part, connection, value:
Frequency Units
Drag a box on graph to Zoom
Zoom to Original Sweep
Save S21 as Ref.
Place Cursor
Reset Cursor
Click to load new value

3.5 -4 MHz High-Pass +
Peaked Low-pass Filter

```
0 Load R = 50.0
1 cap ser 650.0000
2 ind par 2000.0000
3 cap ser 420.0000
4 ind par 1800.0000
5 cap ser 420.0000
6 ind par 2000.0000
7 cap ser 650.0000
8 cap par 5000.0000
9 ind ser 4200.0000
10 cap par 905.5246
11 ind ser 4200.0000
12 cap par 5000.0000
13 rlb ser 0.0000
98 Source R = 50.0
99 Inductor Q = 200.0
```

top 0 dB
10.00 dB/div.
ottom 60.0 dB
tart Freq. 2.2
Frequency Units MHz
10.00 Freq./div
stop Freq 7
Part # 2
New Value 2000
☑ Plot S11
☐ Plot Referenc
Frequenc 3.800 MHz
S21= -2.93 dB
S11= -10.03 dB

Above — A GPLA simulation of the front end high-pass/peaked low-pass filter centered for 3.8 MHz by tweaking capacitor #10 in the software. Click for another simulated filter that covers 3-4 MHz. Look at the sublime low and high-pass skirt action with a 3 dB bandwidth of 73 KHz. Love this!

Click for a screen shot of an entire 40 Meter band version shown with the low-pass filter section centered at 7.003 MHz. I also made 1 for WWV 10 MHz — by scaling the original version's XL and XC and tweaking with GPLA, you may build 1 for any HF band.

AF Amplifier

The post product detector AF chain sounds great. Many of us later replaced the Q5 mute switch with something quieter, however, even today — this AF block holds its own against most discrete component headphone-level circuits. I particularly love the crisp fidelity of the Class A feedback pair Q3 and Q4. Today, I would substitute a BD139 for Q4.

Wrap up

I could go on, but this web page is already too long. Studying + building stages from the PR; a receiver designed more than 3 decades ago, might raise your game today. Go team!

---

10. Miscellaneous Pictures and Figures



Above — I built a prototype 200 MHz oscillator with trailing low-pass filter before making the 210 MHz version placed in the 1-118 MHz VFO for the K3NHI sweep system. (Section 1). The secondary coil floats and may be positioned between any of the 4 primary links to change coupling and thus output power.


200 MHz Oscillator by K3NHI
100
12.22v
.001
4.41 mA
3K3
.001
3K9
5.01v
MPSH81
10
1 pF
C0G
4.29v
2K2
.001
C0G
220 MHz low-pass FL
4t
1t
39
50 nH
50 nH
18
2 - 6 pF
150
300
6 dB
3 dB
15 pF
27 pF
15 pF
50 Ω
105 nH

Above — The schematic of my 200 MHz local oscillator. Click for another version I designed that tuned from ~135-208 MHz.


K3NHI
Level Control Loop
BJT
VCC1
12.22v
10K
VCC2
10K
11.99v
11.25v
A
3K3
IE = 3.51 mA
VCC1
R1
R2
VCC2
Vo
R3
B

Solving bias for a voltage divider with 3 resistors

$$Vo = VCC1*R2\|R3/(R1+R2\|R3) + VCC2*R1\|R3/(R2+R1\|R3)$$

...where VCC1 is associated with R1 and VCC2 is associated with R2. VCC1 may = VCC2

Above — In the K3NHI 1-118 MHZ VCO lies a fabulous leveling circuit that involves a CMOS rail-to-rail op-amp controlling a BJT level shifter. To understand the bias of this BJT, I made a breadboard (A) and then a simple model (B) and developed the equation shown that involves 3 bias resistors. Bias or Vo is determined by superposition. VCC1 and VCC2 may be equal or not. VCC2 comes from the op-amp. I also learned it's a good thing to surround myself with smart people.


OWON Wave analyzing software
File View Format Communications Language Help
K5IRK XTAL FILTER
Scale Position
50 mS
C Voltage
Scale Position
10.0mV
C

7/9/2012 6 MHz 10 xtal filter redesigned.

Magenta=Reference 0 dBm for both Blue and Green traces

Blue=10dB/Vertical Grid, 1kHz/Horizontal Grid

Green=1 dB/Vertical Grid, 1kHz/Horizontal Grid

IL=1.2 dBm, 3dB BW=2.8 kHz rather than 2.7 kHz...close enough.

☐ ch1	5 nS	5.00mV	/ 1
☐ ch2	5 nS	5.00mV	/ 1
☑ A	50 mS	100 mV	/ 1
☑ B	50 mS	100 mV	/ 1
☑ C	50 mS	10.0mV	/ 1

Period: 0.49 S
Freq: 2.046 Hz
PK-PK: 79.200 mV

C:\Program Files\DS_WAVE\dat\D1207091727.bin
PDS 5022S

Above — John, K5IRQ designed and swept a 10 crystal SSB filter with an insertion loss of 1.2 dB in the K3NHI sweeper that I just had to show you. Click for his build up in Ladbuild08 and then GPLA08 from the EMRFD CD. Bob's xtal sweeper from Section 1 and Wes' software arm us experimenters with solid tools. Nothing can replace measurement and reason.

QRP SWL HOMEBUILDER

RF — Test and Measurement

VHF — Véronique



Repository for VHF experiments conducted in 2013 and 2014.

1. Ferrite beads
2. BFS17A transistor
3. 50 Ω MMIC Bench Amplifer
4. Breadboarding Double-Sided Copper Boards
5. Simple Preamp Filter
6. VHF Band-pass Filter Experiments
7. NE612 Mixer Diddy
8. Miscellaneous Photographs

---

1. Ferrite Beads

I toiled to choose an SMT ferrite bead for my junk box. Selecting suitable chip beads not only troubles us, but even some engineers I've read — which to choose? Chip beads act as high frequency resistors that present a low impedance to DC plus our desired RF signal while impeding and dissipating UHF through resistive losses caused by minute heating of the ferrite material from eddy currents. SMT beads are typically rated by their maximum current, resistance at DC, and the impedance they present at 100 MHz.

Since a ferrite bead's impedance is essentially resistive to parasitic UHF oscillations, I remembered that the model for a bead is actually an inductor paralleled by a resistor. It's the "resistor" we're after, for that's the extra load that tends to stabilize the amplifier. From past success in UHF supression with low-value (10-51 Ω) resistors, I chose my SMT bead to have a relatively low Z at 100 MHz. Consider, too, that many chip beads sold today serve as RFI suppressors for high speed digital lines where the Z at 100 MHz and maximum current lie well above my requirements.

I found a chip bead that appealed to me on eBay and bought 50: size 0805; 800 mA; with a Z at 100 MHz of 120 Ω.



Laird Technology size 0805 ferrite EMI bead
Max current 800 mA; 25 Ω @ 25 MHz; 120 Ω @ 100 MHz;
170 Ω @ 500 MHz; 114 Ω @ 1 GHz; peak impedance 170 Ω at 340 MHz

Above — A sweep of my bead from 1- 500 MHz. Sadly, I did not perfectly center the sweep at 250 MHz, but the peak impedance occurred close to the specified 340 MHz.



Above — I swept my Laird techlogies chip bead out to 1 GHz. Ultimately, I'll have to verify its function with in-situ experiments. For example, before and after chip bead analysis of a low noise amplifier that's oscillating at UHF.

FB43-101

If you sweep the floor under my QRP work bench, you'll find 2N3904s, J310s and a few FB-43-101s in the dust pan. In our hobby, FB-43-101s are common as fleas on a dog; many builders like to stick them on the drain, collector, or base/gate lead(s) of an active part to squash UHF oscillations. I've never seen a datasheet for this part and decided to sweep 1 for reference purposes.

2 sweeps of the FB-43-101 follow:



Above — A 1 - 500 MHz sweep of the FB-43-101 slide-on bead. This tracing shows very subtle attenuation that peaks between 400 and 450 MHz. Probably this minimal attenuation at UHF provides the reason we often need to put 2 on the drain or collector of our amplifiers?



Above — A 1 - 1000 MHz sweep of the FB-43-101.

---

2. BFS17A Transistor

I sought a surface mount NPN transistor to supplant my leaded transistors such as the PN5179, BF199 or MPSH10. Serving as a general purpose transistors biased for ~5 to 20 mA collector current — they'll work as buffers + oscillators + as the BJT for hybrid-cascode amplifiers built with a SMT J310 on the bottom.

My requirements were SOT-23 (3 well *seperated* leads allow easily carved islands in a copper board with a dremel tool); an fT that's not too high to help reduce higher UHF oscillations; and a noise figure < 3. Other factors included price and availability. We enjoy many choices with such criteria, but I settled on the BFS17A. Click for the data sheet . In summary, it's a 2.8 GHz part with a NF of 2.5 dB at 800 MHz.



AAbove — My test schematic; a simple feedback amp with capacitors oriented to 50 MHz and above. A limited selection of SMT resistors constrained my experients, but the results seem okay. I strove for the best possible input and output return loss at 50 MHz. I wanted a emitter current of ~ 12 mA and got 13 mA with the bias resistors on-hand.



Above — A 200 MHz wide sweep of my breadboard with tracking generator + spectrum analyzer. Please view the various 2-port measurements at 50 MHz in the lower half. Despite some input and output port mismatching, a gain of 19.2 dB was measured at 50 MHz.

I wound my output transformer within a BN43-2402 binocular ferrite, but ordered some #61 material equivalents for assessment at VHF.



Above — My magnified breadboard looking messy after many parts substitutions from experiments to find the best possible S11 and S22. I removed the shiny RF connectors prior to photography since they often create blown highlights. Alternate image. Despite a limited RF bypass before and after the 100 Ω decoupling resistor + crude bread boarding, I measured no parasitic oscillations from 0.001 to 1 GHz — likely due to the heavy shunt feedback. I liked this transistor, found it easy to breadboard and ordered 100. You'll see the BFS17A in my experiments hereafter.

By all means, order whatever transistor *you* want. Past emailers wrote to say they enjoy reading how other experimenters think about and assess their parts such as RF beads or transistors.

Surface Mount Part Soldering



Above — Solder wick. On my SMT workbench, wick proves the most important tool period. A piece of desoldering wick can transform a monster mistake into a perfect circuit in under 2 seconds.

I've read many accounts of how builders anchor the parts they're soldering. We need to keep the SMT part flat on the board to avoid mechanical tension and poor solder joints — a system is required. For size 0805 and 1206 parts, I often just use my index finger fingernail to hold the part in place while I solder 1 lead with my other hand. After a few seconds of cooling, I solder the other lead and then usually touch up the first joint. For tricky formats like SOT-23, or SOT-143, I usually tape down the part while ensuring even pressure on all leads and just solder 1 lead. After cooling, I remove the tape and easily solder the other leads. Again, the intial lead may require some retouching.

SMT Size

Above — A 5X magnified roll of 50 BFS17A in SOT-23. Compact or what?

Above — BFS17A in SOT-23

---

3. 50 Ω MMIC Bench Amplifer

To boost low-level signals during experiments, every 50 Ω workbench needs a utility RF amp module. With strong wideband gain + RF port return loss (S11 and S22), MMICs make a good choice. Since I own 15 pieces, I built an amp around the MCL MAR-3, a modest gain + noise figure, 2 GHz plastic part in the Micro-X package. We enjoy a bevy of MMICS to choose from and as they increase in fT and gain, so does the need for solid, low inductance grounding techniques.



Above — The completed amplifer module in a Hammond box with an RCA jack for the DC voltage.



Frequency	S21
7 MHz	11 dB
14 MHz	11.2 dB
50 MHz	11.7 dB
100 MHz	12.1 dB
144 MHz	11.4 dB

Above — Schematic with a table showing gain versus frequency. I built all SMT (size 0805 mostly) except for *short* leaded 1 nF input and output coupling capacitors. I applied sturdy wideband DC filtering since I can't risk RF flowing on my DC lines during bench experiments. I measured no oscillations from 100 KHz to 1.5 GHz.

I chose a 1.2 µH SMT choke in an attempt to boost gain from ~66 to 150 MHz. Many builders leave off the choke, but some RF will flow through the 220 Ω bias resistor to ground and thus, to get maximum gain, a high impedance RFC might help. Recall this RFC should exert an inductive reactance of at least 500 Ω (>= 10 X the load impedance) at the lowest amplifer operating frequency; in my case this occurs at ~66 MHz. A better choice for the RFC might be 1.6 µH which exerts ~ 500 Ω at 50 MHz, but I just own size 0805 1.0 and 1.2 µH chip inductors.

My particular amp delivers ~10 to 12 dB gain from about 5 to 180 MHz. Since the coupling capacitor value determines the low frequency response, if you want a MMIC amp for mostly HF, try reducing your input coupling caps from 0.001 to 0.01 µF or so. You mighty increase the RFC to say 10 µH as well — that's why we don't just build kits; design to suit *your* needs.

The 220 Ω bias resistor should really be 200 Ω for a VCC of 12.2v, however, I had to substitute the 220 Ω R due to a low selection of SMT parts. This dropped the current and also my gain at 100 MHz = 0.4 dB less than that specified in the MAR-3 datasheet — no big deal.

I built the bread board on 2-sided FR4 copper clad board. I soldered thin copper foil around all 4 edges to adjoin the top and bottom copper surfaces. Around each MMIC ground lead, I drilled 4 via holes and soldered copper wire from top to bottom. 2 vias were positioned near every bypass capacitor and all along the input and output paths. 23 total via wires.



Above — Tracking generator plus spectrum analyzer sweep out to 200 MHz. Click for a sweep from 1 to 10 MHz showing a rapid fall off below 5 MHz. This little amp will serve me well for most HF and especially my VHF experiments. A UHF amplifier module is planned and all knowledge gained from VHF circuit building will flow forward.


Mini Circuits
DO NOT OPEN EXCEPT AT APPROVED FIELD FORCE PROTECTIVE WORK STATIONS
P/N MAR-3
WFR MA03-4340C
W/O MA03-4/4340C@L
D/C 9448
C/O MALAYSIA
QTY 1

Above — Part of a strip of MCL MAR-3 amplifiers.

Feedback Amps (FBAs)

MMICs like the MAR-3 use a Darlington feedback pair. Still, too, we shouldn't write-off discrete component FBAs wielding transformers + shunt and series feedback at VHF. These amps; staples of countless W7ZOI and W1FB projects since the 1970s; evolved commercially into GaAs FBAs built on a tiny wafer by companies like TriQuint Semiconductor.

In broadband amplifiers, negative feedback permits a wideband (flat) gain response, reduces input and output VSWR (S21 and S22) and controls performance changes from S-parameter and other variations from transistor to transistor. In 2013, I needed an amp chain with >=25 dB gain at 144-165 MHz [~150 MHz mostly] for low level stuff : -25 to -10 dBm input power. Inspired by Wes' 144 MHz CW/DSB transmitter FBA chain *(**SSD** -- Chapter 8 -- Figure 30 in Solid Stage Design for the Radio Amateur; ARRL published in 1986 and out of print)*; I cascaded 3 PN5179 BJTs as FBAs:


Total I = 54.1 mA
All AC measurements made at 150.0 MHz
12.2v
220 pF
51
220 pF
33
220 pF
27
220 pF
5 BFT
FT23-43
5 BFT
FT23-43
5 BFT
FT23-43
50 Ω
22
220
4 dB
S22 = -16.3 dB
1K
1K
1K
220 pF
220 pF
220 pF
220 pF
3K3
3K3
3K0
50 Ω
220 pF
220 pF
220 pF
Q1
Q2
Q3
220 pF
1K
1K
1K
220
120
82
10
12
12
220 pF
220 pF
220 pF
S11 = -21.7 dB
11.2 mA
17.5 mA
25.4 mA
S21 = 26.6 dB @ 150.0 MHz
Upper 3 dB B/W limit = 175.9 MHz
Q1 = Q2 = Q3 = PN5179

Above — My 150 MHz (design frequency) FBA module. Since the fT of the PN5179 = 900 to 2000 MHz @ a 100 MHz test frequency, gain drops steadily as we move up above 100 MHz. Centered at 150 MHz, my upper 3 dB drop off point was 175.9 MHz — thus this amp works okay from 144-165 MHz where I need it.

I built and tweaked each stage to derive the best S11 and S22 . *Click for a snapshot taken of my test of Q1 with a BNC connector attached to both ports — I did this for each stage.* It's a trade off since if you boost the emitter degeneration R, the S11 will improve but the gain decreases. Typical stage S11 = -18.5 dB and S22 = -17 dB. I progressively bumped up the current in each stage to reduce gain compression. I get ~12-13 dBm power out of the whole amplifer before compression/distortion occurs.

Securing the best S11 and S22 for each stages might seem silly, but invoked learning. The S11 and S22 of the *total amplifer* counts the most. An interesting thing happened to S22 – with a RF connector soldered right on the board without the pad, S22 = -23.8 dB. When I added the 4 dB pad and stuck it in the box and then ran a ~ 5mm copper wire to connect an SMA output jack, the S22 decreased to -16.3 dB! At 150 MHz — life differs from 7 MHz.

Placing the 4 dB pad between stage 2 and 3 will stabilize + enhance S22, gives a 4 dB higher 1 dB compression point and output intercept, which may make a FBA chain more useful for experiments like transmit driver applications. I can report I measured no oscillations out to 1.5 GHz and this amp works okay for my intended purpose with gain of 26.6 dB at 150 MHz.

I employed 220 pF caps because the plus the self resonant frequency of my 220 pF Murata caps = 154.6 MHz. Therefore, gain at lower HF is low.



Above — FBA breadboard photograph.

QRP — Posdata for October 27, 2013

I first learned radio electronics from SSD, EMRFD and the ARRL Handbook and still remember the joy when my copy of SSD arrived in 1990. Feedback amplifiers litter this book — and for good reason — they offer stable 50 Ω blocks for building up our RF signal. Wes' 144 MHz CW/DSB transmitter still intrigues me and inspired the circuit shown above.

I asked Wes if he kept that 2M transmitter, and if so, could he snap a couple of photos for me? Wes opened it up to see that the VXO and the frequency multiplier chain were missing. Click Click Click . Thanks to Wes, W7ZOI for the photos.

4. Breadboarding Double-Sided Copper Boards

Seeking a low inductance AC ground for some of my VHF and UHF FR-4 prototype breadboards, I join the top and bottom copper surfaces with solder wick along its 4 edges and copper wire vias in the main board area.



Above — A bench staple, solder wick, joins the 4 edges in true Ugy fashion. Many prefer copper foil for this task, but it's not cheap, nor readily available prompting a pragmatic approach. I take a hammer and pound the solder wick [0.125 inch minimum] so it becomes wider and thinner.



Above — Take a piece of wick and tack it in 2-4 places along the top surface of the copper board. The center solder shown above looks perfect — too much solder will flow into the wick and make a difficult bend job around the board edge. Tack just enough wick so you have enough left to go over the edge and to solder on other side of the copper board.



Above — With hand and/or pliers manipulate the wick around the other side to completely bridge the top to bottom. Finally, liberally solder the wick on both surfaces, move to the next board edge and repeat. Click for a rather messy UHF board with copper wick on 2 edges and numerous vias around a prescaler chip, some input + DC lines and a switch.

Above HF, most don't make pretty prototype boards to admire — rather, builders strive for good AC grounding and generally stick their board in a metal box for shielding and this hides the breadboard. No one's ever told me I make pretty circuits for any frequency and I'm okay with it.

Onto wire vias:

DRILLCO
Cutting Tools
Baton Rouge, LA
200A103
13 ~~12~~ Each
SIZE 3/64
JOBBER DRILL
GENERAL PURPOSE
DRILLCO
CUTTING TOOLS

Above — Your drill chuck will need to accommodate small bits such as those shown above (3/64 inches = 1.2 mm) . I keep these and others that vary from 0.5 mm to 1.2 mm for making via holes.



Above — Magnified via wire soldered at the top side. I found making a hole close to the same size of the via wire will hold the wire in place for rapid soldering. This wire is normally clipped flush at this point. Click for a photo of my flush cutters.



Above — The board shown above was flipped over to solder the bottom copper surface. I try to drill and solder in all vias prior to soldering active devices, since the board heat may damage some parts.

---

5. Simple Preamp Filter

Some RF filtering should proceed our receiver low noise amplifer (LNA) input — but what? Low-pass, high-pass, band-pass, 2 poles, many poles? Factors informing this decision might include our receive frequencies, QRM, selection of IF and thus our image stripping requirements, plus maximum tolerable signal loss before the LNA. We might not want image rejection from this filter since the post LNA filter can tackle this function.

I examined an input filter presented by Joe Reisert, W1JR in the November 1986 Ham Radio. Joe wrote a fantastic column called VHF/UHF World and his context was a high dynamic range 2M receive converter to a 28 MHz IF.



I'm uncertain how to classify this filter: it looks like a standard pi low-pass filter except the input and output series capacitors exert a high-pass skirt. Joe built his filter for 144 MHz. After "building" Joe's filter in Ladbuild08 I tweaked the filter in GPLA *[software from EMRFD]* to center it at our local NOAA weather channel: 162.55 MHz. Click for the GPLA plot.


Simple Preamp Filter
5 pF
139.3 nH
5 pF
50 Ω
50 Ω
8.96 pF
8.96 pF
3.3 - 10 pF
3.3 - 10 pF
Insertion loss 0.25 dB
Centered @ 162.55 MHz

Above — Input filter schematic with values shown to center this rather symmetrical filter at 162.55 MHz. The half power (3 dB down) bandwidth = 18 MHz. You can easily scale it to other other frequencies — by tweaking the trimmer caps and perhaps squishing or expanding the inductor links some, this filter will tune widely including the 2 Meter Ham band. The IL blew me away (better than calculated) — the resonator Q was high due to the air wound L and Q >= 700 trimmer caps along with good port matching.

Click to view a larger photo of the breadboard. I wound the coil on a 3/8 inch diameter bolt but then spread the turns to get the L and length I wanted. Built on double-sided copper clad board, a few copper wire vias connect top to bottom. I joined the LC circuit to its ports with leaded 5 pF ceramic caps.


07:32:30 2013-10-31

Ref 0.00 dBm Att 10 dB Marker1 162.55 MHz -0.59 dB

RBW 1.000000 MHz

Center Freq 162.55 MHz Span 325.10 MHz

RBW 1.0000 MHz VBW 1.0000 MHz SWT 10.836 ms

BW

RBW 1.000000 MHz Auto Manual

VBW 1.000000 MHz Auto Manual

V/R Ratio 1.0000000

Filter Type Gauss EMI
RIGOL
Local
Status
Peak
TRIG Free
SWP Cont
Corr
S.T.
PA
C.W.
Blank
Blank
Math
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
(dB)
1
1/1

Above — Tracking generator plus spectrum analyzer sweep. Under sweep set up, I minutely squished or expanded the L and tweaked the caps to peak the filter at 162.55 MHz while obtaining the lowest insertion loss. Further, I had to tweak the trimmer capacitors to center the filter with the Hammond lid on since putting the lid on changed the center frequency slightly. A *TG equipped* spectrum analyzer proves the ultimate bench tool for VHF and UHF in my humble opinion.

Above — Zero calibration of my AADE L/C IIB meter. By sweeping numerous LC circuits after measuring the L with this tool, I've learned it's reasonably accurate with low inductance coils. I zero the meter prior to *each* measurement and zero calibrate it with the alligator clips butted end-to-end while gripping a small piece of copper wire. Try to keep the same relative alligator clip position during coil measurement. I'm uncertain if this is protocol, but it seems to work for me.

Thanks to Joe, W1JR for this circuit and the opportunity to learn more about component-level VHF design and construction.

---

6. VHF Band-pass Filter Experiments

Build Notes

1. All filters designed with the EMRFD ladpac programs DTC08, or TTC08 and then tweaked in GPLA.

2. Seeking a band-pass filter for my experiments with the local NOAA weather channel at 162.55 MHz, I designed, built and tested 3 filters. With a 10.7 MHz IF superhet receiver, the image frequency = 141.15 MHz.

3. My VHF sweep system = a tracking generator plus a spectrum analyzer.

Filter 1

To avoid the need for proper electromagnetic/electrostatic shielding, I kept my HF experimenter hat on and built my first filter with powdered iron toroids (T30-12) knowing I would pay a Qu penalty that may wreck filter insertion loss, bandwidth and port matching. I hoped that the passive electromagnetic shielding offered by toroidal inductors would reduce resonator coupling.

162.55 MHz Triple Tuned Band-pass Filter



Insertion loss = 5.22 dB
3 dB bandwidth = 5.89 MHz



Above — Mixed-mode triple-tuned filter schematic. Click for the GPLA simulation. When we want to go up in frequency plus desire a narrow bandwidth, we face 2 options: reduce our inductance and/or coupling capacitor(s). This taxes our parts collection and breadboard skills since capacitors less than 1 pF are relatively uncommon and require SMD breadboard techniques. I adjusted my design bandwidth and inductance in TTC08.exe to allow the 0.5 pF capacitors plopped in my parts bin to work. For a change of pace, I chose a mixed-mode filter topology.

I strive to place a single high Q variable capacitor in my band-pass filter tanks, however, my Q = 700 SMD trimmers only ranged 3.3 to 10 pF so I stuck a leaded ceramic capactor in parallel with each trimmer.

Common SMD capacitors exhibit low to medium Q and I try to avoid them in my at HF band-pass filters: often I'll just solder a short leaded though-hole caps instead. I also applied this logic to my VHF filter, however, this might prove foolish at VHF since the self-resonant frequency of a given leaded cap is lower than that of an equivalent SMD cap and capacitor XL becomes more significant as we move up in frequency.

Click for a pdf file showing a simple experiment with 3 capacitors . I'll occasionally use ultra-high Q SMD caps in my future experiments based upon these results.



Above — My TTC breadboard. Click for a larger photo. Click for a bench sweep to view a feculent skirt peak in the filter spectogram. Some resonator coupling occurred despite spacing and placing the inductors at right angles. This circuit possessed 6 tweaks: the 3 trimmers and the 3 Ls — I just kept tweaking them until I got the best shape and lowest IL. That's 21 gauge wire on the toroids. My image frequency = 47.28 dB down. Since the sweep yielded such a wide discrepancy from my GPLA simulation, I discarded this filter and moved on to design #2.

Filter 2

Attempting to obtain a resonator Qu of at least 300-400, I moved to air core inductors wound with bare 22 gauge copper wire *plus* air-variable capacitors. Double-tuned classic topology. Without stout shielding, air wound inductors will couple and trash the stopband.

Create With Metal
Quality Metal Sheets
K·S
Metal edges may be sharp. Use gloves and safety glasses when handling. Children should have adult supervision.

Above — Copper and brass sheets I bought for making filter boxes after Wes recommended using metal sheets or strips for shielding filters. In North America, builders can purchase a sheet metal hand brake plus a rotary cutter/shear for under $100 and make all sorts of boxes for radio gear. I'll equip my QRP workshop with such equipment over the next year. This was my first experience man-handling sheet metal or strips.


162.55 MHz Band-pass Filter
50 Ω
1.35 - 4.5 pF
1.75 pF
0.2 pF
1.35 - 4.5 pF
1.75 pF
50 Ω
3 - 15 pF
12.14 pF
68 nH
3 - 15 pF
12.14 pF
68 nH
3 dB bandwidth = 5.4 MHz
Insertion loss = 2.17 dB
Air caps and coil

Above — Schematic diagram of Filter #2 with tabled IL and half-power bandwidth. Click to view a macro photograph of the filter. I soldered the brass box onto a double sided copper-clad FR4 bread board laden with some copper wire vias to enhance the ground plane. The 0.2 μF coupling cap = an ATC microwave cap.

Click and click for the sweeps. Notice the splendid skirt symmetry at the filter top and also the fantastic peak attenuation in the low-pass skirt

(~81 dB from the filter peak to the lowest point in the low-pass filter skirt). I'd never seen deeper attenuation on my bench before: quite gratifying. My double-tuned filter had essentially matched the 3 dB BW of triple-tuned filter #1 with less insertion loss.

Not all appeared perfect however; attenuation of frequencies above the passband looked so-so and I was unable to get a lower 3 dB bandwidth by manipulating L and C in each tank.



Above — My first ever brass box soldered on a 2-sided copper clad board: Filter #2. Lacking proper tools and also the knack for making beautiful chassis like Dave, AA7EE does, I just did my best. My only concern was getting tank isolation. I chiseled out a small cut in the center brass divider just high enough to clear the SMD 0.2 pF chip capacitor and center copper strip. Overlaps allowed soldering of brass walls After tweaking the L and C parts, I placed a brass lid on top during sweeps. Okay, onto filter # 3:

Filter 3

When coupling caps fall below 1 pF, some builders place their resonators in close proximity to couple the tanks, however, these usually involves slug-tuned powdered iron or ferrite inductors with a generally low Q. The coil consists of cup core and a threaded center core which combine to give a magnetic shield. A tin plated copper can surrounds the core for electrostatic shielding. I think after these experiments — placing each resonator in its own sealed box seems a better option.

I noticed another approach in The Double Tuned Circuit: An Experimenter’s Tutorial in QST for December 1991 by Wes, W7ZOI. Wes drilled a hole in the tank compartment divider and passed a wire soldered to 1 tank through the hole and positioned it near the variable capacitor of the other resonator. We change coupling by adjusting this wire.

The wire may be thought of a "tweakable" capacitor, however, the key point is we need to couple energy from 1 resonator to the next; whether by wire, capacitor or inductor, proper resonator coupling will give the required skirt shape within the the limits imposed by Q and the matching to the 50 Ω ports. When establishing a filter passband, the end Q and resonator coupling pretty much dictate the outcome.

Filter #3 involved more mechanics than electronics. I made a U shaped box from a small sheet of copper.



Above — My copper box drilled for the 2 air-variable tuning capacitors. I built the walls, top and divider from thinner gauge brass strips. Rosin flux aids soldering your metal sheets together — I soldered mine with a Weller 80 Watt iron and began with the center divider. Click for a side shot after completion.



Double-Tuned Filter

* CF = 162.55 MHz
* Great ability to vary BW by adjusting probe
* 1 filter gave a 3.57 MHz 1/2 power BW with an IL of 1.87 dB
* Another gave a 3 dB BW of 2.37 MHz with an IL of 5.79 dB
* Breath taking filter symmetry when tuned and matched

Above — My filter schematic with some tabled data. Click for a top off photograph where you can easily see the black wire probe. To change coupling, you change the wire length and/or its distance from the second tank capacitor. I really enjoyed moving the wire and watching the outcome on the screen. Per usual, I tweaked the coupling, Ls and end caps to derive many 3 dB bandwidths. In 1 arrangement with a 3 dB bandwidth of 3.57 MHz, the insertion loss was only 1.87 dB — I had evidently found a perfect ratio + combination of L and C yielding a low IL.

I'll increase the coil wire gauge in future experiments to lower solenoid resistance and try to garner even more Qu.

This is the *best* filter I've ever built. After peaking the tanks to 162.55 MHz, resonator adjustments weren't really needed. By moving the wire probe I saw that BW and IL change inversely. While tweaking the series caps and moving the probe, it felt like déjà vu from my experiences simulating these exact changes in GPLA over many years — except now they were alive and kicking. With some inductor manipulation (or as needed, changing the inductors) this filter can be centered from ~140 to well over 200 MHz. A high-octane, dramatic and versatile filter indeed.

Click for a sweep where I moved the wire very close to the neighboring tank capactor and over coupled the filter.

Click for a screen shot of another sweep.

Conclusion

With new awareness that resonator coupling and other issues may *also* occur in HF band-pass filters, making these 3 filters surely boosted my future band-pass filter construction standards at any frequency. Over the years, builders have emailed me sweeps of HF band-pass filters (usually VNA sweeps) with also sorts of extra resonances +/- poor insertion loss. Since I'm just an amateur, often nimrod RF enthusiast, I won't pretend I possess all the knowledge to critique their filter woes.

However, photos of their HF filters usually look messy and rushed: opposite to our needs — eschewing important factors like symmetrical layouts, inductor spacing, a first-rate ground plane, larger gauge + well spaced wire wound on big as possible toroid cores Yikes, I better stop now lest I venture into filter folklore.

Today, designing a filter with software is merely half the battle — construction poses the harder task. Unsurprisingly, measurement and experimental methods will elevate your outcomes.

Filter analysis with a sweep system is the ultimate, however I built and then tested many band-pass filters with a frequency counter, a signal generator, a 'scope and a return loss bridge during the first 12 years of my RF life.

Assuming you have a filter that peaks and isn't overcoupled: to measure the 3 dB bandwidth, first peak the filter to resonance for the highest peak-peak voltage in your 'scope. Here's the rest of the procedure:



1. Multiply the peak-peak voltage of your centered filter by 0.707 and record this value.
2. Decrease the frequency of your RF generator until the scope shows the .707 value and record it as Frequency Low
3. Increase the RF generator frequency above the peak until you once again get 0.707 of your peak-peak measured voltage. Record this as Frequency High.
4. 3 dB bandwidth = Frequency High - Frequency Low.

You may also wish to measure the insertion and return loss as described in EMRFD, Radio Society Handbooks, or the RF Workbench series on this web site.

Whether you run superhet, low IF, SDR, or Zero IF (DC) receivers, or need to filter a transmit chain, well made band-pass filters just might boost your project performance. VHF poses additional challenges but offers great learning opportunities.

QRP — Posdata for Nov 12, 2013

A. Notes for Filter #2

Victor, 4Z4ME wrote to explain why the attenuation above the passband in Filter #2 looked mediocre. Filter topology and component values yielded the poor high-pass attenuation and not unwanted coupling as I originally shared.

Victor wrote: "The problem is that all the couplings are of one nature, in this case capacitive.
At very low frequencies the inductors short the signal to ground while the capacitors impedance gets higher so it is clear that the output signal goes to zero.

At high frequencies the inductors may be regarded as disconnected because their impedance get very high, however although the capacitors impedance get lower , you have them both at the series arms and at the parallel arms, so the signal gets to be attenuated by their impedance ratio and not get shorted to ground.

This can be shown in analytic calculation, or easier by simulation. See the attached file (LTSpice simulation). You can see that the filter (similar to your filter) gets closer to a finite attenuation at high frequencies, getting closer to the attenuation of a similar circuit with the inductors *removed*.

You can get better high frequency results by trading the center 0.2pF capacitor coupling to an inductive coupling. Remove the coupling capacitor and insert a wire through the center shield, ground its ends close to the main inductor. Shape the wire to a small loop near the grounded end of each of the resonator inductors to get small inductive coupling, and you get again a good BPF but with better high frequency attenuation. Instead of loops you can connect the coupling wire at a tap at the bottom of the main resonator inductors, close to the ground".





Filter 2 Pos-data Experiment

Above — Following Victor's suggestion, I inductively coupled the Filter #2 resonators with a wire looped near the grounded end of each tank inductor. Please view the schematic above. High-pass attenuation above the passband improved significantly. Click for a sweep out to ~ 511 MHz that shows the peak high-pass attenuation much closer to the low-pass skirt peak reponse.

At 2X center frequency (325.1 MHz) the high-pass skirt peak attenuation closed within 14 dB of the low-pass peak attenuation compared to the original Filter #2 response where the delta was around 30 dB. Further improvement occurs as we move above ~400 MHz. Big thanks to Victor for his support.

B. Sheet Metal Safety

A cut finger while working sheet metal prompted the following remarks: Jagged edges from cut sheet metal (especially brass stock it seems) may lead to deep cuts. Filing a burred edge with the metal clamped in a vice between some thicker metal stock with its raspy edge barely showing will reduce the "knife edge effect". When drilling, clamp the metal piece to your bench on a wooden backing board . If you jam your hand drill in an unclamped piece of metal it could spin and really gore you. Safety first.

---

7. NE612 Mixer Diddy

The Signetics NE612 and ilk enjoys wide use by the amateur radio community in novelty-grade Ham band receivers, or in somewhat better receivers laden with abounding front end filters + *stout,* switchable RF attenuators. Do you think of the NE612 as an ersatz receiver mixer? Some only consider them for the transmit mixer slot. Read this link why.


NE612 Evaluation
1nF
5v
12.2v
+
22
100 µF
1nF
393 nH
T37-6
1nF
2.08 µH
T50-6
8
7
11t
1
5
22t
50 Ω
2t
RF
NE612
4t
50 Ω
IF
50 MHz
2
4
10.7 MHz
3
6
1nF
5 - 30 pF
75 pF
5 - 30 pF
LO
200 mV
pk-pk
60.7 MHz
Output: 1K5:50 ohms

Above — My base schematic. I applied differential input to cancel 2nd order mixer products and balanced output to obtain maximum conversion gain. Click for the breadboard. Powdered iron toroids, Q = 1500 trimmers and a fixed C on the output formed the resonators. I chose a 10.7 MHz IF to drive low-cost ceramic filters in further (unshown) experiments. Normally, we don't bother tuning the input since our bandpass filter should launder the input signal sufficiently.


60.7 MHz Oscillator
12.2v
100
1nF
C0G
3K3
1nF
3K9
100
1nF
MPSH81
2N3904
2K2
1nF
C0G
2.7 pF
C0G
T37-6
470
3K9
probe
2 - 6 pF
air
NPO
air
330
1nF
1K
2-10 pF
output
5.05 mA

Above — My 'thrown together' 60.7 MHz local oscillator. A wire on the common base buffer amp input avoids the series R and C usually required and I moved the wire probe to set the output power between 180 and 250 mV peak-peak into a 1K resistor load.



Input power	IF	RF	LO	2RF	Gain
-35 dBm	-24.3 dBm	-68.71 dBm	-47.09 dBm	-68.14 dBm	10.7 dB
-30 dBm	-19.89 dBm	-63.68 dBm	-47.01 dBm	-58.29 dBm	10.11 dB
-25 dBm	-17.41 dBm	-60.07 dBm	-46.96 dBm	-50.06 dBm	7.59 dB
-20 dBm	-16.21 dBm	-55.62 dBm	-46.65 dBm	-45.06 dBm	3.79 dB
0 dBm	-13.27 dBm	-55.64 dBm	-45.99 dBm	-53.28 dBm	-13.27 dB

Above — A table showing the mixer input, IF, RF, LO, 2xRF [the worst spur] power readings, plus calculated conversion gain. This table echos the datasheet + work by others — input power >= -25 dBm drives this mixer into compression. The NE612 runs low current plus low voltage across the output transistors — thus the maximum output power is limited to somewhere between +2 dBm to +5 dBm from my experiments.

Even with -35 dBm input power, I measured a conversion gain much lower than the typical 14-18 dB enjoyed by others who applied differential output at ~ 50 MHz. Turns out, I goofed — each output transistor contains a 1K5 Ω resistor, so when wired differentially, the output Z = 3K. Back to the bench!


RIGOL
03:12:30 2014-05-04
Local
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
1
2
3
VBW
1.000 kHz

Ref 0.00 dBm
Att 10 dB
Marker1 10.661 MHz -13.27 dBm
Center Freq 50.661 MHz
Span 100.00 MHz
*RBW 3.000 kHz
*VBW 1.000 kHz
SWT 33.333 s

Marker Table

Marker	Trace	Type	X Axis	Amp
1D	1	Frequency	10.661901 MHz	-13.27 dBm
2D	1	Frequency	49.995234 MHz	-55.64 dBm
3D	1	Frequency	60.661901 MHz	-45.99 dBm

Bad Dog !

Mixer Input @ 0 dBm

Above — SA of the mixer output with 0 dBm RF input. Something we would never do in real-life, but I wanted to see the spurs with such a drive: the spurious output actually looks great! The NE602, NE612, MC1496 and SO42P [all Gilbert cell mixers] output cleanly; especially when compared to diode-based mixers.


NE612 Conversion Gain Experiment
1nF
5v
12.2v
+
100 µF
1nF
22
1nF
393 nH
T37-6
4.53 µH
T50-6
8
7
1
5
11t
31t
50 Ω
50 Ω
2t
4t
RF
NE612
IF
50 MHz
2
4
3
6
-14.06 dBm
5 - 30 pF
5 - 30 pF
22 pF
1nF
10.8 MHz
-30 dBm
LO
224 mV
pk-pk
60.8 MHz
Output 3K:50 ohms
Conversion Gain = 15.94 dB

Above — My mixer with output Z corrected at 3K Ω. Wow, a conversion gain of 15.94 dB with -30 dBm drive. All good now. Click for the IF measurement on my SA. The LO had drifted up to 60.8 in this experiment, however, I left it and peaked the output resonator for maximum smoke. I also extracted another 0.5 to 0.8 dB gain by tweaking the LO drive. In my breadboard, a drive of 224 mV pk-pk gave the highest conversion gain.

Hereafter, I'll drive my NE612 transmit mixers with between -26 to -30 dBm on the RF port with differential input and output.

---

8. Miscellaneous Photographs



Above — Hair or lint in my SMT macro photo

Rosenberger
Rosenberger

Above — Instrument grade N-male to SMA female

Above — Instrument grade N-male to SMA female; gorgeous machine work.

RF — Test and Measurement

RF Workbench Page 6 — QRP Transmitters

RF Workbench 6 explores some questions regarding basic transmitter power amplifer (PA) design. Since I write for both Ham and non-Ham readers, I feel badly that RF Workbench 6 excludes pure radio listeners; please consider getting your amateur radio licence to join the fun.

For Class A, AB and C transmitters in current source operation, radio builders knew most everything presented on this web page back in the 1980's — humbled and guileless, I've but a skosh of new ideas to further elevate this topic. Sometimes I feel bound in a creative straightjacket because puzzling design questions paralyze my understanding and progress. This web page explores a few transmitter questions born on my QRP work bench and I hope you'll relate and go design your own high-octane transmitters. As always, I hope to share insightful + actionable info for the DIY scratch builder; albeit from a lay-person perspective.

I borrow heavily from the work of Wes, W7ZOI per correspondence, direct contributions, from EMRFD and the references listed in Section 5. My sincere thanks to Wes for his support and inspiration.

Preface

You require an amateur radio operator licence to operate a radio transmitter and it's up to you to know and ensure your transmitter spurious emissions meet or beat the regulations in your country.

Although I measure my circuits with calibrated equipment, expect your measured voltage and current to differ from mine. **Why?** Variables may include your DC power supply voltage and current rating, dummy load resistance, stray L and C, cables and wire effects, bench errors, parasitic oscillations, temperature effects and parts tolerances.

I unabashedly declare my love for experiential learning: to build and measure, discover and develop — and best of all, to tune, tweak, and transform my RF power amps to unleash the "smoke" and power we all crave.

Contents

Section 1: 21.06 MHz Bipolar Transistor Transmitter in Class C: Dig out your old transistors and explore some Class C topics.

Section 2: PA Measurement with Examples: Measure collector V and I

Sections 3, 4: Incomplete and coming in 2013-14. I'll post any additions on the QRP Log -- Thanks

Section 5: I'll list all the references for this web page

Section 6: Photographs and Miscellany. I'm told at least ~~3~~ (now 4) people enjoy my photos.

Section 1: 21.06 MHz Bipolar Transistor Transmitter in Class C

Despite all the buzz about PA efficiency and the trend towards more efficient switched-mode power amplifiers, my email inbox fills with content regarding those Class A to C power amps. Consider too, most Hams, including QRP buffs, power their rigs with an AC connected DC supply that makes battery life moot. Perhaps our love of PAs in current source operation harkens from our historic tube days: do we simply enjoy making heat and wasting power? Like me, you might just love making and measuring bipolar transistor circuits.

A Class C power amplifer excited by a crystal oscillator offers both new and reawakening homebrewers the chance to make a simple but relatively powerful, 1 frequency transmitter with only 2 - 4 RF stages. Keying a Class-C PA embodies the Ham glory days: put some RF into the sky with basic, analog circuitry.


Block Diagram
21.06 MHz
Broadband
or
L-C-C
Buffer
Driver
PA input
match
Power
Amp
PA output
match
Xtal
Osc.
Drive
Hycas
BD139
Broadband
or
L-C-C
2SC1969
Low-
pass FL
21.16 MHz
10X
Short
ground
Dummy
Load
50 Ω

Above — The block diagram for all the experiments in Section 1. Each stage involving transistors was built and tested from left to right before making the next stage.

Crystal Oscillator, Keying Switch and Hycas Buffer Amplifer

As more a listener than a talker, I wanted a low-level crystal oscillator to keep my *key up* current draw low. In the class C power amplifers based on the above block diagram, I measured only 7.5 mA. *key up* and several hundred mA *key down*. I also wanted my back wave to be > 40 dB when I eventually converted the PA to Class AB during another set of experiments.

Design Question 1: What backwave should I strive for?

Backwave = the dB difference in output power between key up and down. Opinions differ and context may partly explain why. If you're working DX, backwave is less important than when your working nearby ops on 80 meters. From asking respected authors, experiments and operating, I feel 40 dB should be the minimal backwave to strive for. Operating Class C, your final(s) are turned off during key up and a >= 40 dB backwave proves an easy goal.


12.2V
.01
LM7805
in
out
.01
51
.01
390 pF
21.06 MHz
d
g
s
J310
330 K
82 pF
560
33 pF
5 pF
output
10X
10K
5.04 mA

Figure 1

Above left — The 21.06 MHz crystal oscillator. Click for the output voltage into 10K Ω. Click for the FFT. Seeking low distortion and output power, I placed variable capacitors in the feedback and source slots and also played with the 560 Ω source resistor. While watching in my 'scope and tweaking , I chose the the lowest distortion signal under 1 Vpp. The variable capacitors were removed, measured and replaced with nearest standard 5% parts. The 10K load of Figure 1 corresponds to the gate resistor of the hycas amplifer input.

21.0588241
MHz
Gate
Freq
Ch 1

Above — Without the 390 pF capacitor, the crystal oscillator vibrated at 21.058 MHz.

21.0603168
MHz
Freq
Ch 1

Above — The crystal oscillator measured frequency after experimentally adding a 390 pF cap. Should I have tried a 470 pF capacitor and attemped to get 21.0600 MHz?
My oscillator looks unconventional and in some cases you might want 1 with higher output voltage. Check EMRFD and the other W7ZOI references in Section 5 for xtal oscillator design ideas.


use appropriate PNP
TIP42A
To driver
12.1 VDC
510
51
.01
.22
4K7
1K2
T50-6
4.06 µH
29t
6t
50 Ω
jack only used
for testing
3K3
.01
5K
Gain
2K2
2N3904
Max bias
5.54 VDC
.01
2.5-10 pF
7.05 pF
d
g
s
J310
from 5 pF
cap of LO
10K
150
.01
Figure 2
IS = 14.6 mA @
maximum gain

Above — Figure 2, the hybrid cascode buffer. I've never tuned, nor keyed a hybrid cascode amp before and it works well. Click for the oscilloscope output. Click for the FFT measured with a long wire grounded 10X probe. I applied a junkbox TIP42A switch lying on my bench since I keyed a number of *unshown* high current stages during my experiments. Only about 10% of my experiments ever make it onto the QRP/SWL HB web site. For the PNP switch, just use whatever can handle the *measured* current with key down: 2N3904, 2N4403, 2N2907, BD140, etc.,etc..

Yes dear reader, measure everything.

The Driver Amplifer



Above — A BD139 feedback amp breadboard. Click for the schematic. Wanting an output power of at least 22 dBm to drive my final, I built 3 varieties with both the BD139 and a 2N3866. Normally, for receiver amplifers, I focus on a strong input and output return loss and work hard to maintain linearity — but mostly keep the emitter current under 50 mA. At 21.06 MHz, the biggest *clean* signal I could muster with such a broadband feedback amp was +16 to +18 dBm — well short of my goal. Click for a DSO screen shot of the 41.3 mA amp at 6.42 Vpp or ~20.13 dBm power; quite distorted.

I needed to try something else and saw the Figure 3 amplifier in some of Wes' work; wielding bold emitter current to boost signal handling and power.

Figure 3



Notes:
Beta varied from 83-160 on random samples from at least 3 different companies. Emitter current can vary from device to device and with different heat sinks

Above — The W7ZOI designed feedback amp used for a driver in all Section 1 power amp experiments. Love it! Many builders feel tempted to abandon series and/or shunt feedback and just "go for gain". My experiments suggest this approach often leads to instability within the driver circuit and possibly on down the RF chain. We should strive for linearity and stability; 2 big reasons we apply feedback. Flirt with a driver *lacking* feedback if you dare.

Click for the maximum output power attained by turning my hycas bias pot fully clockwise: 7.77 Vpp, or 21.79 dBm. You can see distortion, but since this stage will drive a Class-C transistor PA (i.e. it will switch "a diode" on and off and generate clipping), I decided it will work fine. A VHF-UHF transistor such as the 2N3866 or 2N5109 may yield as much as 3-4 dBm more power, however, you'll see more clipping at higher driver levels. I stuck with the BD139 and tried several pieces from at least 3 different manufacturers (The BD139 was made by at least 10 companies at 1 point). A Philips version purchased in 2008 yielded the 21.8 dBm, so I bolted it to a home built copper clad heat sink and soldered it in place.

Calculating Transistor Output Power Off the Bench

Design Question 2: How do I mathematically estimate my Class A amplifier output power?



```
IE = 88.612400 mA
Bias Voltages:
VE = 1.595023 volts
VB = 2.295023 volts
VC = 10.100000 volts
VCE = 8.504977 volts
VCC = 10.10 volts
VBE = 0.70 volts
```

P (t) = V (t) x I (t)

Where
P (t) = instantaneous power in Watts
V (t) = the voltage drop across the BJT
I (t) = the current through the BJT

8.5 volts x 0.0886 Amps = 753 mW
Assume we'll get 25% or 188 mW output
10 log (188) = 22. 74 dBm

Figure 4

Calculate Output Power from VCE and IE

Above — Estimating output power from my Figure 3 amplifier. I measured a static DC Beta of 125 as shown in Section 5 on this page. Then I calculated VCE (the voltage across the transistor) and emitter current with my program NPN-DC Bias. Wes wrote a similar and likely better program called Biasnpn08.exe that's included on the EMRFD compact disk.
You may also measure your VCE and IE directly and improve the above calculation with measurements. I do this frequently.

Class A amps exhibit about 25% efficiency and also imagine that Figure 3 will bear some gain compression.

My measured power = 21.8 dBm — it amazes me how close a non-bench calculation using DC analysis can get to a AC bench measurement. The Figure 4 procedure is apparently a bread and butter RF design tool.

The Power Amplifier Input

Design Question 3: How do I match my driver output to the Class-C power amp input to maximize power?

This question provided a few nights of reading and experiments; time well spent. We have 2 main ways to match our driver output to the PA input: broadband or tuned. First, lets explore the problem theoretically:



Figure 5

Above — A simple model sent by Wes: driving an amplifier with a power source. As amateur designers, simple models help us understand complex concepts.

A pure voltage source doesn't really exist. We don't apply a voltage to the base of the PA; rather, we apply a power source (our signal generator) — a signal voltage followed by a series impedance that's usually just a source resistance for a load. The power source + source impedance together *source* the load that includes the load capacitance represented as an input cap in Figure 5. You may wish to read about Thévenin's theorem and its dual, Norton's theorem to learn more about linear network analysis.

The load presents an impedance where the power is delivered and either dissipated in its resistance, or reflected back to the source when the load contains a reactance . At our PA input, this capacitive load reflects some of the signal back and induces a pole that corresponds to a "capacitor" time constant.

If you consider our power source, its source resistance, the PA input capacitance and just omit the effects of Q you'll see that the the voltage across the capacitor decreases as frequency increases. If you insert a 2:1 turns ratio transformer after the driver, you'll drop the AC voltage by 2 and its resistance by 4. For the same capacitance, the 3 dB cutoff frequency of this single pole filter increases. Also, the lower output impedance drops the driver amplifier voltage gain and may boost stability.

In short, we need a low driver source impedance since the Class C bipolar amplifier base-emitter junction has lots of capacitance To get current flowing into the PA base, we drop our driver output source impedance down *low*.

I thought — couldn't we just neutralize this capactance with an inductive output impedance? Thus our PA driver stage would drive a resistive load and everything would be "ducky". I consulted Wes, plus viewed some math and circuitry.

You can't effectively neutralize a bipolar transistor amplifier, since the capacitance isn't constant and behaves more like like a varactor diode rather than the C shown in Figure 5.. Even when forward biased, diode capacitance depends on the instantaneous voltage that appears across the diode. In contrast, 'FETs prove less troublesome and thus it's possible to achieve some neutralization with a 'FET amplifier. Please view the power stage from EMRFD Figure 11.14. Check out the push-pull pair of IRF511s. C5 and C6, at 22 pF each, are neutralizing capacitors.

In some cases, the capacitive reactance may be absorbed as part of a resonant circuit on the PA input. For example, a low-pass filter might soak up some of the C.

In all cases, our goal is drive in some power and switch the PA transistor solidly on and off (i.e. technically approaching class B but definitely class C because conduction will be less than 180 degrees) — a low output impedance can drive that input capacitance.

Driving final(s) with a very low output Z rings true even if your driving the latest (super-costly) ultra-low loss, high breakdown voltage, silicon GaN FETs to output >100 Watts at 1296 MHz in Class D, E, F, or Inverse Class F. Just get it done!



Above — Figure 6 shows 2 basic methods to drive the PA with a low impedance: single frequency network or broadband step-down transformer. I'll discuss both methods in detail later. Let's move away from theory and lighten things up for a couple of minutes.



Above — A short 10X probe ground lead boosts Tx measurement accuracy; in particular, for FFT analysis with your DSO. You can read or see **why** by searching the web for text and/or videos concerning oscilloscope probes.



Above — The long gone 2SC1969 works great. Beware of counterfeits however.

Bipolar transistor selection troubles us since most of the 'old standbys' went obsolete way back when. I've been collecting dusty, old *QRP* driver and PA transistors for decades and my bag includes BD139, MJE181, 2SC2509, 2SC1969, 2SC2166, NTE123, 2N3053, 2N4037 and 2N2219A. For VHF, apart from the 2N5109/2N3866 standards, I've kept a few MRF607, 2SC1971 and 2N3553.

VHF/UHF transistors exhibit tremendous gain at lower HF, but they might oscillate without due care.

Some rules I've gleaned: The fT of a BJT should be at least 3-5 times the operating frequency; the VCEO should be at least double the VCC (more is better) ; don't exceed the maximum heat dissipation, nor maximum current. In short, read the datasheet. I won't cover heat sinking, nor gain compensation for multi-band amplifers on this web page; for it's been done by far better authors.

Lets make a basic Class C power amplifier based upon the RF blocks presented thus far.

Class C PA with Broadband Input and L-C-C Tuned Output


R Load = VCC2 / 2Po = 12.1 * 12.1 / 2 (4) = 18.3 Ω
Output Po = 36.53 dBm = 4494.4 mW
21.060 MHz
12.1v
Collector current 565 mA
13.3 µH
16t FT50-61
Measured values in red
+
10 uF
.01
.01
5.5 µH
10t FT37-61
optimal
282 pF
270 pF
488 nH
488 nH
50 Ω
from
driver
.1
247 nF
T30-6
33
120 pF
optimal
132.5 pF
150 pF
270 pF
150 pF
8t BFT
FT37-43
2SC1969
18 to 50 Ω
L-C-C Network
Q = 1.62
Low-pass Filter
Figure 7

Above — Input matched PA via a broadband transformer (a bifilar wound transmission line transformer with a 4:1 Z ratio). A great example of this design includes the Figure 2 of Ugly Weekender transmitter by Wes. The 50 Ω output Z of the driver is transformed to 12.5 Ω. to drive the PA input. While a conventional link-coupled transformer works okay, the closer coupling of a twisted wire transmission line transformer often affords a better impedance transform and lower losses. You might experiment with a 9:1 Z transformer instead of the 4:1 shown. Click for a highly compressed photo of 1 of the full breadboards.

The 33 Ω resistor helps lower gain and stabilize the amp. I ran 33 to 100 Ω applying experimental methods. Read more about the PA base resistor and coil XL requirements in the text following Design Question 6.


DSO-X 2022A, MY51360373: Mon Jun 17 07:53:10 2013

Acquisition: Normal 2.00GSa/s

Channels: DC 10.0:1; DC 1.00:1

Measurements:
Freq(2): No signal
Freq(1): 21.05MHz
Pk-Pk(1): 42.4V
Pk-Pk(2): No signal

Above — The 'scope output from Figure 7. 42.4 Vpp = 36.53 dBm = 4.49 Watts.

L-C-C Output Matching Network

3 discussion points arise from Figure 7: [1] the output matching network. [2] the collector choke + decoupling circuitry, and [3] the low-pass filter. I'll discuss choosing a collector choke and decoupling in Section 2. We design our low-pass filters with tables or software; I used an old ARRL Radio Amateurs Handbook and then tweaked it in GPLA to get standard value capacitors. Click for a GPLA simulation of my filter. The L-C-C network also provides some low-pass filtering.

To calculate the collector output resistance, we use the formula R(load) = Vcc^2/ (2*Pout) as shown in Figure 7 for 4 Watts. For 1.5 Watts at 12 VDC --- R(load) = 12 * 12 / 2(1.5) = 48 Ω --- no output matching network is required; making 1.5 watts a popular transmitter power for new builders eager to learn about Class C.

Design Question 4: How do I make an L-C-C matching network?

Let's stick with 4W power and make an L-C-C Tee network for a 18 to 50 Ω transform. I prefer the L-C-C network over the L-network because you get 2 capacitors to tweak and I find it much easier to match a wide range of impedances compared to the L-network. Since we may pinch, or expand the inductor windings, in reality, the L-C-C gives you 2.5 possible tweaks.

Normally I wind the L on a number 6 powdered iron toroid with 26-28 gauge magnet wire in size T25, T30, T37, or T50. 26 gauge wire allows for good coil squishing and expansion with thumb and forefinger. For design cycle capacitors, I mostly solder in those horrible, low Q, orange, green, or red muRata trimmer caps such as the TZ03Z500F169B00. Although rare, ceramic-mica trimmers work well.



M. L-C-C Tee Network

http://www.qrp.pops.net/qrp-java-calculator.htm

Enter **frequency** in MHz: 21.06

Enter **R1** in Ω: 18 Enter **R2** in Ω: 50 *R1 must be < R2, but the network is bi-directional*

Enter Q: 1.62 If C1 or C2 = NaN or Infinity, try increasing Q

Calculate L-C-C Values **C1** = 123.71 pF , **C2** = 273.78 pF , **L** = 0.22 uH

Above — To calculate L, C1 and C2 we may employ software to obtain starting L and C values. I recommend Wes' ZMAT08.exe, a Ladpac program that ships on the EMRFD CD. I wrote my own java-script applet with less prompting and error checking and put in on the Design Center web page as **M**. Note I used 18 Ω as the load resistance in my calculations.

During actual bench assessment of your network, output your PA to a 50 Ω dummy load rated for that power and preferably measure the peak to peak voltage with a short-grounded 10X probe.

For Figure 7, I wound and tack soldered in a measured L of about 230 nH and placed a 100 pF cap plus 6-50 pF trimmer for C1 and a 220 pF + 22 pF cap + 6-50 pF trimmer cap for C2. The tuning procedure goes like this:

Tune the capacitors for maxmum power. Try squishing the L, then re-tweak C1 and C2 and see what happens. Did the Vpp go up or down? We want it to go up, so if the Vpp went up you needed more L, and perhaps still need more. If you squish the coil again (or remove it, add 1-2 turns and then replace it) and the Vpp goes down, you increased the L too much and need to go back down. If the original Vpp goes up when you expand the coils, you had too much L and need to do the opposite procedure just described. Re-tweak C1 and C2 after every inductance change and calculate the power in dBm and/or watts on your bench.

Through trial and error you'll find the optimal L. If nothing works, suspect a bench error, or device failure. Occasionally, I add too much, or too little fixed C in parallel with the trimmer cap. Another time, my transistor was fried.

Once you've extracted the maximum power, remove the cap(s) that make up C1 and measure them. Do the same for C2. I replace C1 and C2 with the nearest equivalent standard value capacitor or (parallel capacitors) and then repeat the tuning procedure to find the optimal L for these 2 new capacitors. Normally, after optimizing the Vpp, I'll remove and measure L to confirm my L-C-C network design. You can use the L just removed or make a tidier version to permanently solder in.

Once you solder in the "keeper" L, you'll need to expand or compress the links a tad to peak your Vpp once again. Although it sounds like a chore, I love measuring a higher Vpp with each successful manipulation of the L-C-C network; it's quite a rush actually.

In the end, my optimal measured values were: L = 247 nH, C1 = 132.5 pF and C2 = 282 pF. In my final, I substituted C1 = 120 pF and C2 = 270 pF as shown in Figure 7. Although I designed for 4W, I squeezed out 4.49W with my L-C-C network.

Design Question 4: How do I choose my L-C-C matching network Q?

The easy answer is the degree of impedance transformation sets the minimum Q and thus choosing the best Q becomes the central question.

The theory regarding loaded versus unloaded Q + network losses and such may bog down many, but in context, a lower Q leads to a more efficient network with less loss. Low Q values also means we tweak larger value capacitors that minimize the effects of stray capacitance. In the collector output network of Figure 7, the Q of 1.62 gave more power than an earlier Q = 5 network. Further, during design, I sometimes slightly adjust the Q in software so I get closer to standard value caps for C1 and C2.

Don't be afraid to remove C2 and just make an L-network. Again, just experiment on your bench to gain confidence.

I tried making this circuit with a BD139 in the PA slot and managed to squeeze a mere 3.1 Watts power at 12.1 VDC. Others, such as Wes and Jason, NT7S delivered more power into 50 Ω at and even above 21 MHz with a BD139 PA.

Factors such as transistor specifications, frequency, VCC, and driver power may affect the output power. In the end, the 2SC1969, a final I harvested from an old Cobra CB more than 20 years ago delighted me. I constantly scrounge for old driver and PA transistors in my travels. Sadly, many old CB radios given to me over time suffered from fried finals.
You might try checking eBay, but watch out for fakes.

The BD139 grew to notoriety because it's widely available, cheap and generally does the job at or below ~28 MHz, depending on what output power your seek. I found wide variation in Beta (or hFE) and fT in the random batch I tested. Also remember we're hitting them with lots of current and they heat up and specs change. At 7 MHz, the BD139 works great. The BD139 reminds me of the MPF102 JFET; you never know what your going to get. The best I've tested were Fairchild BD139s and woefully, they're all gone.

Class C Power Amp with Broadband Input and L-C-C Tuned Output

Let's make a PA with an L-C-C Tee network tuned input: Figure 8.


Figure 8
Keyed
12.1v
22
.01
.01
50 to 3 Ω
L-C-C Network
Q = 5
10 BFT
FT37-43
220 pF
22 pF
390 pF
113 nH
T25-6
345 nH
1t BN61-2402
R
12.1v
13.3 µH
16t FT50-61
+
10 uF
.01
.01
5.5 µH
10t FT37-61
270 pF
488 nH
488 nH
50 Ω
247 nH
T30-6
120 pF
150 pF
270 pF
150 pF
1K5
.01
510
18
.01
12
(22 + 27)
BD139
2SC1969
18 to 50 Ω
L-C-C Network
Q = 1.62
Low-pass Filter
21.16 MHz
21.060 MHz
R = 51: 49.8 Volts pk-pk = 37.92 dBm = 6200.1 mW
R = 33: 45.7 Volts pk-pk = 37.18 dBm = 5221.3 mW

Above — Figure 8. The Figure 7 PA with a tuned input network smashed my world with 6.2W power. Click for the FFT showing the second harmonic down at least 55 dB. I later confirmed this with spectrum analysis.

Design Question 5: How do I choose my PA input impedance?

PA Input Impedance

Calculating the input Z of a transistor with 100's of mA emitter challenges us.The familiar calculations like Zin = (Beta +1) x 26 /I e (mA) don't work out perfectly since our transistor is hot and Beta changes, and in my case I'm way up in fT. I asked Wes and he suggested I assume an input Z of 3 Ω (with about 200 pF of parallel C). Thus , I chose a 50:3 Ω transform to design my L-C-C network.

From my experiments, bench tweaking an L-network, or L-C-C network will accommodate anything even close to 3 Ω input impedance — 3 Ω seems quite actionable. Tune your L-C-C network in the manner described for the PA output match. Since your transforming 50 Ω to 3 Ω, the minimum Q will rise.

Design Question 6: How do I choose my PA input choke and resistor when fed with an L-C-C network?

The RFC serves as a DC return path for the PA base just like in the transformer in the wideband version. We normally apply a rule that the minimum inductive reactance of a choke should be 10x the impedance it's connected to, so that's 30 Ω XL.
Since F = 21.06 MHz, the minimum choke value will be 30 Ω / 21.06 MHz x 6.28) = 227 nH. In order to keep the SRF up and for ease, I ran a single turn of 26 gauge wire through a BN61-2402 binocular core and measured 345 nH. Good enough. The # 61 mix will exhibit some Q. Likely # 43 material will work fine too.

The resistor labelled R serves to reduce the Q of *my* particular RFC, lowers gain and boosts stability. With R = 33 - 51 Ω, the amp held stable, but if I tried to increase R above 51 Ω spasm erupted. The resistor affected output power as shown in Figure 8. Again the resistor should minimally be about 10X the input Z or so. I tried an R of 10 Ω and the output power dropped down to a little under 3W as more of my driver output just flowed through the resistor to ground.

To conclude, I executed the time honored tradition of choosing parts and circuits to extract power from a crystal oscillator-driven analog RF amplifer chain. Much of this information extends to linear operation (Class A, AB) and general RF design. Have fun designing your own transmitters and as always, apply experimental methods!

Section 2: PA Measurement with Examples

In this section, I posted some PA measurement ideas + experiments and comments about PA collector chokes.


13.5v
22
11.2v
.1
.1
10 BFT
FT37-43
1.38 uH
1.7 uH
1.38 uH
50 Ω
.1
270 pF
680 pF
680 pF
270 pF
1K5
2N5109
7.36 MHz low-pass filter
50 Ω
signal
generator
in
.1
2.44v
1.77v
510
18
.1
15
101 mA
7 MHz
Lab Driver
20.1 dB gain
My maximum power = 26.84 dBm = 483.025 mW
2nd harmonic = -48 dBc at 26.84 dBm

Above — To boost my signal generator output for driving *any* experimental PA up to about ~20W output, I built a high-current, sine wave driver. I excite this amplifer with my variable gain homebrew HF signal generator — in the version shown above, a 7 MHz low-pass filter is soldered on the amplifier breadboard. I'll stick this amp in a metal box sans filter and then apply the correct bench module low-pass filter via a BNC connector. Click for a photo of 3 of my HF low-pass filter bench modules.

Normally the low-pass filter output is pad attenuated to buffer and reduce the output voltage since it's rare I need up to 483 mW drive on the QRP workbench.



Above — A photo of the PA driver amplifer breadboard.


DVM
I
VCC
DVM
V
DC Supply
22
.1
.1
Bypass caps
RFC2
RFC1
Low-pass Fl
50 Ω
RF Power
10 BFT
FT37-43
R
BJT
1K5
.1
Driver
510
18
.1
15
Signal Generator
Drive

Measuring Collector Efficiency

The ratio of RF output power to DC collector power.

$P_{Collector}$ = VCC * I (amperes)

Above — A method to simultaneously measure collector **V** and **I** to calculate DC collector power. Two DVMs boost measurement fidelity since the current measuring ammeter's internal resistance will drop the DC supply ~ 0.2 to 0.5 volts depending on the device and current. Collector efficiency = RF output power / (V * I) .

This method provides a great excuse to purchase another multimeter.

Measure VCC where shown since the decoupling and bypass filters help prevent the AC signal from affecting the DC measurement. We only touch our 10X 'scope probe on the collector. Exert due care and wear eye protection in case you blow up the transistor and create shrapnel.


VCC
22
.1
.1
10 BFT
FT37-43
10X
.1
R
PA Input
Matching
Network
.1
PA
Disconnect driver from
PA input match, add R
and measure power
1K5
.1
Driver
510
18
.1
15
Signal
Generator
Drive
R = a temporary 49.9 to
51 Ω resistor with the PA
input matching network
disconnected
Measurement for 'Power Added' Efficiency

Above — Power Added Efficiency considers the base drive power in addition to the DC collector power. The formula = RF output power / (DC Power + RF drive power). Although uncommon, measuring drive power helps you to assess and compare both input matching and PA efficiency metrics.

At the very least — I like knowing my PA drive power and so employ driver amplifiers with 50 Ω output impedance to allow this power measurement. I often permanently solder a 49.9 or 51 Ω resistor to the breadboard ground plane and temporarily connect this R ; plus disconnect the input matching circuit to measure driver power when I've finished tweaking my collector to antenna port circuitry.


VCC
+
+
DSO or Analog Scope
Base and Collector
Voltage Measurement
10X
C
B
10X
C
B
FFT (DSO)
C
Voltage Measurement
and FFT

Above — Oscillocope measurements of the base and collector voltages. Most of us enjoy simultaneously running 2 channels on our 'scopes. With a good quality DSO, FFT analysis of the collector waveform may yield insight, however, this knowledge might also confound us since interpreting our measures is fully half of the task.

I often struggle to properly interpret measures. Some builders blog about or email me that they enjoy an innate gift at understanding electronic circuitry — I don't. I guess I lack the knack? For some of us, problems and complications block progress, but more often than not, we eventually cross the finish line.

Above — 1.5 Watt, Class C breadboard used for the experiments that follow. I changed the collector choke (RFC1) and applied various filters to examine some of the measurement techniques aforementioned. Click for a bigger photo.

The Collector Choke


VCC
FT37-43
15.2 µH
7.04 MHz
+
10 µF
.1
+
10 µF
.1
.1
FT37-43
12.7 µH
B
50 Ω
22
220
4 dB
8t
2t
FT37-43
A
39
BD139
.1
50 Ω
Dummy load
B
A
2.1 Watts Collector Power

Above — A Class C amplifer with it's collector AC coupled to a 50 Ω resistor load. *No filter.*



Above — Base and collector waveforms. The unfiltered collector waveform (top) rich in even and odd harmonics ~resembles a square wave. The maximum collector voltage occurs when the current is 0 and in concert, the maximum collector current flows where collector voltage falls to near 0. As the BJT shuts off, the collector circuit kicks and rings so that the DC collector voltage may rise as high as twice VCC.



Above — An FFT of the unfiltered collector showing F1, F2, F3, F4, F5, etc. Distortion city!

The Collector Choke

I've read web pages suggesting we might boost PA efficiency by decreasing the collector choke inductance. While that's possible, in reality, it's not that simple. Experiments involving factors like collector load resistance, angle of conduction, RFC inductance/Q, matching networks, base drive configuration and output filtration are ripe with complicated math and theory that I struggle to understand — entire books and research papers explore these topics as author(s) configure their PA into Class D, E, etc. to boost efficiency. The published design work and PA devices out today are truly breath taking.

We should likely think of the BJT, collector current + voltage, the RFC, base drive and output networks as a system of parts that interact — changing 1 part might change collector current, impedance, efficiency, harmonics, etcetera. As such, the experiments that follow do not construe science; only some experiments by a neophyte to ponder and build on.

The ideal RFC passes only DC — i.e. exhibits infinite impedance to AC, but a short circuit to DC. The primary purpose of the choke is to block our high-power, distorted AC signal from flowing on our DC power lines. Some authors suggest that the minimum inductance for the inductor should be 5-10X the collector resistance and I'll leave that up to you. At HF, I wind my RFCs on #43 or #61 material ferrites while keeping the turns number low as I remember that the coil will exhibit a self resonant frequency that might cause problems if it lies near a frequency I need to filter.

1.5 Watt Amp with Three Different Collector Chokes

The 1.5 Watt obviates the need for a matching network since the collector load resistance = 48 Ω with a VCC of 12v. I rebelled and ran 13.5 V supply for a calculated 60.8 Ω collector load R. I probably should have this matched this collector load to 50 Ω at 13.5v, but wanted a "real world" amp without a matching network. At the very least, these amplifiers illustrate the PA measurement techniques shown above. I wound the RFC on a common FT37-43.

In all cases, I adjusted the base drive so that the sine wave PA output read ~24.5 Vpp while measuring collector V and I. I made DSO measures of the the base and collector voltage and collector FFTs, although forgot to save some of them as screen captures.


VCC
FT37-43
15.2 µH
+
10 µF
.1
+
10 µF
.1
.1
FT37-43
4.52 µH
7.04 MHz
FCo = 7.36 MHz
1038 nH
1700 nH
1038 nH
50 Ω
22
220
4 dB
8t
2t
39
.1
270 pF
680 pF
680 pF
270 pF
50 Ω
FT37-43
BD139

needed more base drive

13.5v * 0.219A = 2956.5 mW
Vpp = 24.5 = 31.76 dBm = 1500.625 mW
1500.63 / 2956.5 = 50.8 % efficiency

Above — The collector choke = 4.52 µH or an XL of ~ 200 Ω @ 7.040 MHz. My measurements indicate an efficiency of 50.8%. With a choke XL of only ~ 200 Ω, some of my collector AC might be flowing to ground through the bypass caps and that'll kill efficiency. Click for an FFT of the collector. This circuit required more base drive than the other 2.


VCC
FT37-43
15.2 µH
+
10 µF
.1
+
10 µF
.1
.1
FT37-43
9.8 µH
7.04 MHz
FCo 7.36 MHz
1038 nH
1700 nH
1038 nH
50 Ω
22
220
4 dB
8t
2t
39
.1
270 pF
680 pF
680 pF
270 pF
50 Ω
FT37-43
BD139

13.47V * 0.1819A = 2450 mW
24.6 Vpp = 31.8 dBm = 1512.9 mW
1512.9 / 2450 = 61.8% efficiency

Above — The collector choke = 9.8 µH = an XL of ~ 434 Ω. Efficiency now 61.8%. Base and collector tracing. Collector FFT.


VCC
FT37-43
15.2 µH
7.04 MHz
+
10 µF
.1
+
10 µF
.1
.1
FT37-43
21.5 µH
FCo = 7.36 MHz
1038 nH
1700 nH
1038 nH
50 Ω
50 Ω
22
220
4 dB
8t
2t
39
.1
270 pF
680 pF
680 pF
270 pF
FT37-43
BD139
13.45v * 0.156A = 2.098W
24.5Vpp = 31.76 dBm=1500.625 mW
1.5W /2.098W = 71.5% efficiency

Above — The collector choke = 20.5 µH = an XL of ~ 951 Ω. 71.5% efficiency. Base + collector. Collector FFT. Sine wave FFT. To date, 71.5% is the best Class C efficiency I've measured.


Diplexer Version
VCC
FT37-43
15.2 µH
+
10 µF
.1
+
10 µF
.1
.1
FT37-43
21.5 µH
All inductors measured and wound on #6 material.
Top caps were hand picked and measured.
Smaller font bottom cap = the calculated value
1774.9n
2007.5n
739.7n
Low-pass
50 Ω
822 pF
821.7p
653 pF
644.4p
.1
50 Ω
22
220
4 dB
8t
2t
39
FT37-43
BD139
300 pF
260 pF
688 pF
291.3p
257.5p
699p
High-pass
100
x2
1 watt Rs
629.1n
802.3n
Efficiency 44%
N = 5 Diplexer for FCO of 7 MHz
Caps 5 and 10% standard value

Above — A PA terminated in a N= 5 diplexer for 7 MHz. Click for the FFT of the collector. The collector waveform looks telling — resembling the 50 Ω resistor terminated version shown earlier. Unshown; I lowered the signal generator to 6.99 MHz and drove it to a sinusoidal 1825 mW to obtain a true 50 Ω collector load resistance plus get the greatest low-pass output signal and efficiency (44%) . Although diplexers will 50 Ω terminate the collector at all frequencies, they don't afford high collector efficiency.

Rogues Gallery



Above — Some 5W CW amplifier collector waveforms as I tried to boost efficiency by manipulating a matching network to drive up the ringing; all failures. These seemingly simple Class C PA's aren't so simple after all. Although failures — I felt thrilled by these experiments and vow to get better at it.



Above — A sine wave output of a very unstable PA.



Above — To observe a renegade series resonant frequency, I wound a choke for a 21 MHz amplifer on a T68-2 powdered iron toroid: a casual 24 turns of wire. Sweeping it shows 2 SRFs at roughly 115 and 350 MHz. 2 SRFs jarred me.



Above — I placed a couple of caps on the cold side like we normally do for our PA chokes. Likely I should have used a 0.01 µF cap instead of the 0.1 µF shown for 21 MHz, but the result would be the same: 2 SRFs remain and poor wideband bypass arises. We clearly need to consider SRF in our chokes and how it might affect our PA function and DC line filtering.

Conclusion to PA Measurement

With an oscilloscope and 2 DVMs you can easily explore boosting your Class C PA efficiency. I've seen precious little info on this topic in the amateur RF experimenter literature. 1 reputable reference = a section in EMRFD called **A Look at Some High Efficiency Amplifers**. For now, I'll temporize. Likely you'll advance faster than me, since I'm more a receiver guy and don't devote enough time to study transmitter design.

The math and concepts of efficient PA design within Class C - E flummox me. Most have just switched to driving FETs with a square wave built up from parallel inverters (high-speed logic gates in the now obsolete 74AC series) — but hopefully our experiments tweaking BJTs in Class C will carry us forward into other Tx modes.

Measuriing collector power with 2 DVMS while watching the sine wave output in your 'scope gives you incredible feedback: you can even observe thermal runaway. After purposely advancing the base drive to "heat up" a BJT, I saw the Vpp progressively drop in the 'scope, the DC voltmeter drop somewhat and then the DC current meter 'take off' : 400, 500, 890, 1200 mA and suddenly, poof, the BJT was on fire, exploded and flung 2 leads into the air. Normally, they just smoke and stink up your lab. I put a picture of a couple of blown BD139s in the photo section below. Expect to burn up some BJTs during experiments and please work safely.

Section 4: Class E Amplifier

This section unposted.

Section 5: References

1. Solid State Design for the Radio Amateur by Wes Hayward, W7ZOI and Doug DeMaw W1FB. American Radio Relay League 1986.

2. An Updated Universal QRP Transmitter by Wes Hayward, W7ZOI. American Radio Relay League: QST for April 2006.

3. Class E Amplifiers Part 1: Class E Basics. Dan Tayloe, N7VE / Ozarkcon Class E Presentation, 1994. *Search for it online*

4. The Handiman's Guide to MOSFET "Switched Mode" Amplifiers by Paul Harden, NA5N Part 1 Introduction to Class C,D,E and F. First Published in the journal "QRPp". Paul's Site

---

Section 6: Miscellaneous Figures and Photos

JE181
8047
C3039
M0H4

2N3553
K0350
2N3553
K0350

2I D600D
WC9838


THM
6071
BD139
SM 105°C

HF - Embarcadero

Respository web page for HF experiments performed in Fall 2013 and Winter 2014.

1. IMD Oscillator Quest
2. Almost Popcorn Superhet — an older, variant and incomplete HF project added for sake of interest
3. VXO — VCXO Notes
4. Funster Line — A Simple 40M Band QRP Trans-receiver.
5. Miscellaneous Photos and Figures

1. IMD Oscillator Quest

To measure IMD and calculate IP3 in receivers and components, we need 2 oscillators that typically lie 20 KHz apart, although some apply other frequency spacings. We join these oscillators with a 6 dB (or 3 dB) hybrid combiner and often follow the combiner with an RF attenuator and/or low-pass filter before connecting to a DUT and detector. I sought an oscillator possessing low phase noise, low distortion, strong return loss + high reverse isolation and documented my experiments to fuel your own. Nestled half-way within the HF band, 14 MHz is a popular IMD oscillator frequency choice. I chose 14.0 MHz and 14.020 MHz for classic 20 KHz spacing.

Wes, W7ZOI well covers intercept measurements in EMRFD and in part, popularized receiver DR measurements with his QST article entitled Defining and Measuring Receiver Dynamic Range in QST for July 1975. Click for the article header only. After publishing his article, receiver DR testing by the major Ham transceiver manufacturers became standard.

If you own 2 crystals spaced 20 KHz apart, you're set. A Butler oscillator set up for vibration at the xtal fundamental frequency works well. See EMRFD Figure 7.32 for a great example — A Butler carefully biased to stand reasonable current for low phase noise with a low impedance in the Colpitt's tank. Wes placed a 100 Ω resistor on the link between base terminals of the differential pair. The low impedance and the bias levelling provides current limiting and prevents the oscillator BJT from going into saturation.


14.0 MHz Butler with Hycas Buffer
9v reg
100
T50-6
20t
4t
22
50 Ω
.01
4K7
1K2
.01
+
10 µF
.01
13t T37-6
Tweak L
to tune
5K
gain
+220+
4 dB
6-60 pF
2N3904
4K7
33 pF
4K7
Q1
100 pF
2N3904
.01
100 pF
d
J310
g
s
.01
1K
5K6
14 MHz
220 pF
10K
220
.01
-19.76 dBm to 0.77 dBm
Current 16.51 mA @ full throttle
0.2 mA through the Q1 emitter

Above — A fundamental frequency Butler with hybrid-cascode (hycas) buffer I built for 14.0 MHz some years ago. Rather than tuning the oscillator tank with the usual low-Q trimmer capacitor, I designed for a fixed C of ~100 pF and thumb and finger tuned the tank to preserve the Q.

Alternately, a standard Colpitt's crystal oscillator with the crystal connected to ground via a shunt capacitor of >= 200 pF provides a great way to get a low phase noise, low distortion oscillator. Take the oscillator output from the junction of the xtal and shunt capacitor and ensure you lightly load this node. See EMRFD Figure 4.24 or my Low Noise Crystal Oscillator web page for examples.

A problem arose. I couldn't find 2 crystals 20 KHz apart, so running 2 fundamental Butler or Colpitts oscillators for IMD measurement seemed out of reach. A web search yielded 1 solution; pull the xtal oscillators to a desired spacing around 14 MHz and crystal filter the output to drop phase noise.

My next experiments mirrored the work of Christian, DL9NL on this web site. It appears he based his design on that of Stuart, KI6QP who authored A Precision Two-Tone RF Generator for IMD Measurements for QEX for April 1995. Stuart used crystals cut 20 KHz apart to make 2 Colpitt's oscillators running moderate current with output filtering by 1 xtal filter tuned to the oscillator frequency to reduce phase noise.

In his project, Christian, DL9NL wired up two 14.318 MHz microprocessor filters in a super VXO topology to cleverly move the xtals 5 or 20 KHz apart. He also output filtered his 2 oscillators with a xtal filter.


12.2v
8v
+
10 µF
.01
.01
47
500 nH
T37-6
10K
.01
10K
18 pF
2N3904
2N3904
220 pF
6-60 pF
10K
150
120
10K
220 pF
68
.01
2N3906
T37-6
20t
4t
0 dBm
2-12 pF
50 Ω
22
5 pF
100pF
1K
.01
10K
1K2
6-60 pF
220
14 MHz
14 MHz
4 dB

As shown this oscillator = 14.009 MHz

General Idea:

1. Use a super VXO with added L and/or C on 2 different oscillators to pull them 20 KHz apart
2. Apply an external xtal filter to lower phase noise

Above — 1 of my rudimentary experiments involving a super VXO plus output xtal filter. Not a great design. In this experiment, the 2 crystals were connected to ground via a 5 pF capacitor to yield 14.009 MHz. I learned that xtal frequency and xtal parameters determined the available frequency spread and output filter function.

After thought and the above bench work, and also because I need to make oscillators for IMD measurements at 50-100 MHz, I decided to go with an LC oscillator. They work fine for IMD measures with proper design and construction. For example, the signal generator shown in EMRFD Fig 7.27 sports a phase noise approaching -140 dBc/Hz @ a 10 kHz spacing; getting awfully close to the cherished vintage HP-8640B signal generator.

With LC oscillators, I learned that a metal enclosure with a feedthrough capacitor for the DC line proved important.Strong reverse isolation also ranks 'very important'. A case in point follows:


RIGOL
14:00:24 2013-10-10
Local
Status
Peak
TRIG Free
SWP Cont
Corr
S.T.
PA
C.W.
Blank
Blank
Math
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
1
Peak
Next Peak
Peak Right
Peak Left
Min Search
Peak Peak
Cont Peak
On
Off
Search Para
1/2

Ref 0.00 dBm
Att 10 dB
Marker1 14.023 MHz -11.73 dBm

Marker
14.023708 MHz
-11.73 dBm

Center Freq 14.023 MHz
Span 250.00 kHz
RBW 300 Hz
VBW 30 Hz
SWT 27.777 s

Above — A close-in spectrum analysis of 1 of my 14.02 MHz LC oscillators. Span = 250 KHz; RBW = 300 Hz and my video bandwidth = 30 Hz to "cut the grass". You can see a spur about 92 KHz right of center; a signal from my SA or environment is getting back into my VCO and low-level modulating it. Yikes! Another RF-tight LC oscillator with a common-base isolation amp showed no such spur.

Close in spectrum analysis may allow you to measure phase noise with your spectrum analyzer, however the wide-range, first oscillator of a Rigol spectrum analyzer operates in the range of 2- 4 GHz and is varactor tuned; as such, the best phase noise we can measure with it = -88 dBc/Hz @ 10 KHz spacing.


1 pF
C0G
12.22v
22 uF
51
.01
C0G
10t bifilar FT37-43
220
22
.01
220
untuned buffer
47 pF
C0G
5 pF
C0G
J310
82
d
g
s
air
1M
.01
C0G
47 pF
C0G
12 pF
C0G
1.25
-4.55 pF
1N4148
.01
15t
20t
4t
50 Ω
1t
4t
22
2K2
1K2
220
T50-6
T50-6
4 dB
220
.01
C0G
270
.01
1K
6-60 pF
14.02 MHz
Hartley
15.2 mA total current
2N3904

Above — 1 of my experiments: a Hartley with common-base buffer amp right out of EMRFD Figure 7.27 sans the final amp. I made 2 versions: 1 with a tuned buffer amp and another with a wideband output (see orange inset). The output power of the tuned amp and wideband amp = -6.7 dBm and -11.7 dBm respectively.

You may want to add a final amplifer — I've got a couple of amplifer modules if I need to get to 0 dBm or above. Prior to tweaking the lid-on frequency to 14.02 MHz, I measured the 2nd harmonic at 55 -dBC in the tuned output version— yay! Building with solid temperature drift techniques, the frequency drift in my counter went just a few hertz *up* over time. The Figure 7.27 oscillator remains a go-to circuit for us builders.


14.02 MHz LO with Hycas Buffer
12.2v
.01µF
C0G
220
100
.01µF
C0G
J310
10 pF
C0G
39 pF
C0G
100 pF
C0G
100 pF
poly
1K
88 µH
RFC
air
875 nH
100K
1.25-4.55 pF
air
100 pF
C0G
4K7
.01µF
1K2
20t
4t
39
50 Ω
150
5K
gain
4K7
6-60 pF
2N3904
.01µF
5 pF
C0G
10K
d
g
s
J310
220
.01µF

Above — A Colpitts with hycas buffer allowing variable power output. During measurement of IMD, the 2 oscillators need to exert the same amplitude, so only 1 needs to have variable output power. A wideband bench generator plus a 1 frequency oscillator like this might be all you need.



Above — A photo of the completed Colpitts LC oscillator. Running a phono jack for the DC input was a mistake. A feedthrough capacitor = the best choice. The epoxy glued air wound coil and air trimmer cap plus the regular temperature stability techniques and a 100 pF polystyrene capacitor yielded a temperature drift under 40 Hertz per hour. 5 bolts anchor the copper clad board.

I connected the 5 pF coupling cap to the lowest turn on the air coil. Mounting an air coil (solenoid) in smokestack fashion over a copper board probably upsets its Qu, but it worked okay.



Above — Our old friend the Return Loss Bridge is also known as a 6 dB hybrid combiner and 1 serves double-duty on your QRP workbench as an isolator and a return loss bridge.

Phase Noise and Commercial Signal Generators

The worst of today's ham transceivers transmit a CW carrier with noise that is down by 117 dBc/Hz @ 10 kHz spacing. This is bad enough that if you had a Ham operating this rig 0.8 km away you would hear this noise, even with a perfect receiver. In a typical oscillator, the phase noise @ 100 kHz spacing lies ~20 dB lower than @ 10 kHz out to a noise floor that is around -140 dBm/Hz or better. The Elecraft K3 impresses us with phase noise at -138 dBc/Hz @ 10 KHz [Sherwood].

We either build, borrow or buy our signal generators. Second hand commercial products range from good old HP/Agilent gear or LC boxes once used by TV/FM receiver repairmen. The TV service equipment covers ~300 kHz to 150 MHz and tends to be inaccurate with a limited output amplitude range, while the vintage HP stuff often is heavy, decaying and crowds your bench.

Most of hobbyists can't afford nor justify spending $8-18k on boxes that go down to -127 dBm amplitude and -146 dBc phase noise at 1 GHz @ 20 kHz offset [Agilent N5181B MXG X-Series RF Analog Signal Generator]. These generators feature components like a YIG oscillator phase locked to an ovenized crystal reference. Professional, high-end gear.

Another choice = the Arbitrary/Function Generator or ARB that sell for a fraction of the cost of the aforementioned boxes. A few friends own them, in particular, products made by Rigol and GW Instek. These DDS generators range in frequency and price: higher price generally = better phase noise.
For example, the popular Rigol DG1022A phase noise = -108 dBc/Hz @ 10 KHz offset and the DG4162 = ≤-115 dBc/Hz @ 10 KHz offset; not good. Often ARBs will feature a host of modulation functions, sweeps, frequency counters and the 2 output channel models may offer I/Q outputs and the ability to perform 2-tone IMD tests. Search around the T Equipment website to read some equipment datasheets

My question to 2 informed EEs — Is the phase noise of a -115 dBc/Hz ARB *good enough* to reliably measure IMD? Their answer: yes, if you have a high end, modern spectrum analyzer with a minimum RBW of 100 Hz, deft analyzer skill and understand the measurement. Often us hobbyists have to make due with whatever test equipment we can build or buy.

You might just build a low noise oscillator with a crystal at 14.0 MHz and provide the other tone with your bench signal generator or some other combination of 2 devices. This is test equipment junkie fodder — band-of-brother's stuff. Thanks for reading.

---

2. Almost Popcorn Superhet

I published this rogue web page with hope you might find it interesting. It houses notes and photos for an incomplete update to my 1998 Popcorn 7 MHz, CW, superhet receiver.

Click for the Almost Superhet web page.

Click for the Almost Superhet Supplement page

---

3. VXO — VCXO Notes

VXOs and VCXOs provide a useful main or reference oscillator for HF and when multiplied, in VHF-UHF designs. Ignorant of such circuits, I executed some crude experiments to discover how they work and find ways to improve my designs. Increasingly clinical on my bench, I'm losing patience with the radio mystique — although the limits of my lab equipment, brain power and bench skills humble and tumble me into deeper understanding why educated people might submit to electronics folklore and go in blind faith.

I'm not sure my bench work accomplished much, but if I can add 1 factoid to the RF enthusiast VXO knowledge base, then, I'll feel happy. I'm officially adopting **System D**; the slang term that originated in the French-speaking African continent and Caribbean Plate. In Down and Out in Paris and London, George Orwell called these System D practitioners "débrouillards" — low-level kitchen help, who achieve culinary success in the worst of circumstances. Television hero MacGyver practiced System D.

System D in the context of the QRP Homebuilder describes an effective, practical and resourceful builder who skillfully adapts to any situation and *gets it done*. System D builders don't just kludge together crap — these science-informed débrouillards innovate and shine. Sounds hopeful doesn't it?

Nearly all my bench adventures begin with a web search and the key word *VCXO* yielded many espléndido files + presentations by people and companies who passionately share their knowlege and experiences. Thanks to all!

Experiments

It started with an email from Paol — what's the S12 of the source follower in his 14 MHz VXO buffer amplifier? I built 1 for 10 MHz and tested it since I didn't know.



Above — Device Under Test. Paol copied a source follower he found on a web site (complete with an über kitsch 1 mH choke on the source). I tweaked the current and replaced that big, old MF choke with a tapped FT37-43 giving an output return loss of ~ 13.5 dB. Although mediocre, it's probably better than the match provided by the series resistor we typically stick between the JFET source and its 50 Ω load. Further, for my S12 measurement, I matched the input with a L-C-C network to get a strong return loss @ 27 dB. Measured with a spectrum analyzer, S12 = -32 dB; paltry reverse isolation. The matching networks incurred some losses but raised measurement fidelity.

-32 dB — not great, but okay if followed by another amp. For a diode ring mixer, I might couple it to a common base amp, or eliminate the source follower altogether and replace it with a hycas buffer amp. Paol drove a NE612 transmit mixer with his VXO + a source follower and it worked okay in his bare-bones TX. He AC-coupled a 51 Ω resistor to ground on pin 6 of the NE612 that well terminated the LP filter. Intrigued, I then helped him with his VXO.


14 MHz
6.57v
220
7.11v
51
7.86v
8v
12.21v
100K
.1
.1
10 µF
.1
+
+
.1
470 µF
5.11v
2N4401
330 pF
100 pF
J310
14.34 MHz LP Filter
50 Ω
L1
4.55v
10K
10
T1
696 nH
696 nH
.1
470K
100 pF
2K2
4
T50-6
T50-6
100K
100
2.18 mA
150 pF
330 pF
150 pF
12.5 mA
DKV6516
12.18v
22
+
10K
Tune
470 µF
10 µF
.1
VXO
L1 = 7.9 µH
T1 = 10t FT37-43 with a tap
4t from ground
RL = ~ 15 dB
Total current = 18.96 mA

Tune	Min	Max
Frequency	13.953 MHz	14.005 MHz
Amplitude	245 mV	233 mV

Above — My first VXO experiment with varactors instead of an air variable cap that technically creates a voltage-controlled crystal oscillator (VCXO). The tabled values were measured with L1 wound on a FT50-61 ferrite toroid.

Paol had varactors but no air-variable capacitors. Both of us owned some Q = 200, DKV6516 silicon varactor diodes that with a reverse DC voltage of 2 to 10 volts give a nice tuning range of 18 to 140 pF for a single diode. We cheated and ran the reverse DC voltage from 0 to 12.2 volts, although later increased the 22 Ω R to limit the peak tuning voltage to 10v. Paol also put a fixed resistor on the cold end of his 10K tuning pot to keep a minimum 2 VDC on the varactors: I didn't bother, since my "this is only a test" breadboard will be dismantled and junked.

Above — DKV6516



Above — VCXO breadboard. Paol and I each made a VCXO and he with 14.060 MHz crystals. Lacking these, I just used 2 junk box 14 MHz crystals with a measured Qu of ~80K. The tapped FT37-43 gave an output return loss of ~ 15 dB thus providing a reasonable match into a simple 50 Ω low-pass filter. Click for a sweep showing the 2nd harmonic suppression.

My initial build didn't contain the two noise filtering 470 µF caps on the 12 volt supply: I originally soldered a solitary 22 µF cap cap close to the 8 volt voltage regulator input. My 12.2 volts comes from a regulated DC supply. More on filtering noise later.



RIGOL 06:58:28 2013-12-02

Ref 0.00 dBm * Att 15 dB Marker1 14.007 MHz -46.06 dBm

RBW 100 Hz

Center Freq 14.006 MHz Span 1.0000 MHz

* RBW 100 Hz VBW 100 Hz SWT 100.00 s

RBW 100 Hz Manual

VBW 100 Hz Auto

V/R Ratio 1.0000000

Filter Type Gauss

Local
Status
Peak
TRIG
Free
SWP
Cont
Corr
S.T.
PA
C.W.
Blank
Blank
Math
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
BW
RBW
Auto
Manual
VBW
Auto
Manual
EMI
1/1

Above — My VCXO spectrogram showed 2 big spurs: 300 KHz down and 100 KHz up from center frequency (CF). I exchanged the varactors with an elegant, Q >= 1000 air variable, plus changed to a higher Q inductor, but could not get rid of these spikes. I assumed these spurs came from the crystals, or the BJT. Then, too, might they arise from my spectrum analyzer?


RIGOL
12:37:55 2013-12-02
Local
Status
Peak
TRIG Free
SWP Cont
Corr
S.T.
PA
C.W.
Blank
Blank
Math
-31
-37
-43
-49
-55
-61
-67
-73
-79
-85
-91
2
3
Marker
Select Mkr
1 2 3 4
Normal
Delta
Delta Pair
Ref Delta
Span Pair
Span Center
Off
Mkr Trace
Auto
1/2

Ref -30.80 dBm
Att 10 dB
Marker1 13.992 MHz -31.52 dBm

Marker
13.992500 MHz
-31.52 dBm

Center Freq 14.000 MHz
Span 500.00 kHz
*RBW 100 Hz
VBW 100 Hz
SWT 50.000 s

Marker Table

Marker	Trace	Type	X Axis	Amp
1D	1	Frequency	13.992500 MHz	-31.52 dBm
2D	1	Frequency	14.100000 MHz	-43.83 dBm
3D	1	Frequency	14.151666 MHz	-43.09 dBm

Above — 14 MHz crystal sweep spectogram. To find out why these spurs occurred, I swept 1 crystal at a time from my batch and saw spurs on all of them. However, after some reading, I discovered that the mere presence of a crystal spurious response doesn't signal causality since this is almost a normal happening. Wes, W7ZOI explains this on this web page. Crystals usually have a spurious response and from Wes, the spur is more often than not about 80 or 100 kHz above the main signal. This happens with fairly good crystals, less so with crappy, cheap crystals and even less often with good quality crystals. Since many of us buy computer-grade crystals from Mouser-Key, or online auction sites, who really knows what we're getting? 1 day I hope to test a Q = 1 million crystal — that will be fun.

However, renograde crystals could still be the cause. Sometimes when pulling a crystal(s), we're living on the edge — the main resonance is pulled so far that the circuit balks at the resonant frequency, or lies near the edge of such behavior and spurs start to show up. *Back to System D*. Simple substitution with 2 other crystals from another batch could tell me if these particular crystals were behaving poorly. It turns out, they were.


RIGOL
12:54:17 2013-12-12
Local
Status
Peak
TRIG Free
SWP Cont
Corr
S.T.
PA
C.W.
Blank
Blank
Math
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
-110
BW
RBW
100 Hz
Auto Manual
VBW
100 Hz
Auto Manual
V/R Ratio
1.0000000
Filter Type
Gauss EMI
1/1

Ref -10.00 dBm
*Att 10 dB
Marker1 12.011 MHz -72.37 dBm

RBW
100 Hz

Center Freq 12.000 MHz
Span 1.0000 MHz
*RBW 100 Hz
VBW 100 Hz
SWT 100.00 s

Above — Spectogram of the VCXO with 12 MHz crystals. I wanted to try other 14 MHz crystals, but didn't own any. My nearest value crystals were 12 MHz jobs with a Qu of 120K. Eh voila! No spurs — yay! Let's talk about noise:



Above — Schematic for sideband noise discussion

System D design poses a real challenge with repect to noise. Measuring noise proves an advanced technique beyond the scope of this popcorn RF web site. We can't measure noise with our spectrum analyzer since the oscillator in the analyzer usually exhibits more noise than the VXO we want to test.

On page 4.12 of EMRFD version 1 is a small photo of 2 spectograms that show a clean crystal trace contrasted with a really bad oscillator trace. Baffled, because I could not replicate this experiment, I emailed Wes and asked him how he did it. Wes wrote we're able to see the noise in those traces because his SA featured a multiple pole, wideband filter with steep skirts that allows us to see the baseline noise close-in to the carrier. In contrast, most modern SAs feature synchronously tuned resonator type, or digital filters that produce a narrow peak with skirts that spread way out. The noise gets swept under the skirts.

By all means, advanced builders may apply notch filter techniques to measure oscillator sideband noise down low, however, a consideration for others might be to apply techniques proven to reduce noise and spurs — and just build the best oscillator possible plus measure what you can.

Some basic techniques to make a low-noise VCXO are well described elsewhere and may include: a high Q resonator, high Q varactors [with low series resistance], low power supply noise [including varactor tuning voltage], a low flicker noise amplifer, avoid overdriving the crystal and try to swing the highest AC voltage in the tank without reaching saturation and/or causing reverse breakdown in the varactor(s). Even the ratio of the Colpitts capacitors can affect phase noise, but without a method to measure phase noise, this gets esoteric. Some of these techniques also apply to VXOs.

Power Supply Noise

Bob, K3NHI and others have measured significant noise from the LM317 or related voltage regulators that we amateurs typically use. Power supply noise can FM our resonator and boost oscillator sideband noise. We may filter power supply noise with *large* value capacitors plus/minus series decoupling. See the work of Leif, SM5BSZ on this web page under the heading "The +12V supply is carefully decoupled like this". In addition, Charles Wenzel, published this web page.

I employed both techniques in my discussion schematic above. I went with the pi filter shown above 1000 µF - 39R - 1000 µF at the voltage input. A inductor might be used instead of the R if the voltage drop is too high for you. The Wenzel circuit fascinates me. The series resistor (18 Ω in my version) samples the current that flows into the oscillator. A voltage is then developed that is applied to the amplifier to generate a voltage that is out of phase with the noise current.

With good DC noise filtering I could measure small improvements in sideband noise in my SA despite only able to measure down to -88 dBc/Hertz at 10 KHz offset. In contrast, you rarely ever see even 1 electrolytic capacitor in the VXO schematics featured on many Ham radio builder sites.

Another trick is to avoid a regulator altogether. Since my DC supply already has a voltage regulator set to 12.2v, placing a second 5 to 8 volt regulator after it might just add another noise source.

Overdriving the Crystal

I heed the advice of Konstantinos, SV3ORA. He found that gently driving his crystal generated less noise and spurs compared to overdriving the crystal. Thus I adjusted my emitter resistor to about 1 mA current. For the schematic above, a typical emitter resistor starting value = 1K8. Just measure your emitter current.

I employed a large area, slower BJT, the BD139 to hopefully drop flicker noise. Expensive, super high Q crystals (Q = 500K to 1 million) may be driven with up to several mA of current, however, it's likely not so for the computer-grade xtals we typically use. I can't measure the outcome of these interventions, but System D thinking might just prevail.

Varactors

Varactors tend to be low Q and their Q deteriorates as we go up in frequency. I've seen very low phase noise VCXOs employing varactors, however, these were engineering marvels. Still, as a VHFer and hopeful UHF enthusiast, this is the direction I wish to go. We ideally need to keep some reverse DC voltage on the varactors at all times and not go to 0 — this also limits tuning range in our simple 12v supply radios. Read your datasheet. Air variable capacitors (a VXO) might be a better solution for your application.

How Does a VXO work?


Cm
C1
Rm
R1
C0
Lm
L1
=

Above — The crystal equivalent electrical circuit has 2 arms: The impedance of the motional arm Zm lies in parallel with Zo, the impedance resulting from the parallel capacitance C0 (formed by the 2 crystal leads.) We measure and/or calculate these parameters when designing our crystal filters. In the above schematic I added the external L and C used to move the crystal's series resonant frequency around in our VXO, VCXO, or Super VXO circuits.


20 MHz
.01
10K
12.2v
10K
2N3904
10K
2K2
.01
Low Z
to counter
10K
100 pF
.01
100 pF
2K2
19.998615 MHz
2N3906
L = 2.42 µH
C min = 6.27 pF
C Max = 110.4 pF
C min = 20.003 MHz
C max = 19.999 MHz
19.996 MHz
C min = 20.002 MHz
C max = 19.997 MHz

Above — I made some simple experiments to explain why we place both a L and C in series with the crystal and how it changes the crystal frequency in our oscillator. From these experiments, some theory from EMRFD and wisdom from Ken Kuhn, I made the following simple conclusions:

Electrically a crystal looks like a large inductance in series with a small capacitance and in parallel with C0. An external inductor adds to the crystal’s series inductance and *lowers* the resonant frequency.

The external variable capacitor adds in series with the crystal internal capacitance to lower the net capacitance and *raise* the resonant frequency.

The purpose of adding an external inductor is so that we can tune both lower and higher than the natural crystal frequency. In contrast, if we only apply an inductor, the oscillator frequency would always be lower and if we just apply a capacitor, the oscillator frequency would always be higher.

Since the external inductance has much lower Q than the effective internal inductance, it adds to noise and signal losses. The same goes for the external C.

As we raise the inductance ever higher to boost the delta F, at some point, the parallel C of the crystal resonates with this "too high" L and the series resonant frequency has nothing to do with the series resonance of the crystal. This kills the normally sublime frequency stability of a crystal-based oscillator.

Q of the VXO/VCXO Inductor

I experimented to learn that the Q of that L doesn't need to be that high to allow the frequency to be moved up or down by an air variable cap or varactor.

For example, if I wound a coil on a T68-2 and shunted it with a resistor no less than 1K8 — it worked fine (sometimes the frequency shift would even improve 2-3 KHz for a given L). A #61 ferrite toroid wound inductor also worked well and requires much less turns allowing thicker wire for mechanical stability. Also, the lower number of turns helps avoid significant SRFs. Temperature stability remains a question with the this and all ferrites.

An FT37-43 or FT50-43 ferrite inductor worked poorly – I measured high signal losses plus the maximum frequency swing dropped when compared to the same inductance value wound on a T-68-2, or FT-50-61. Avoid #43 ferrites in any resonator circuit unless you're purposely building a noisy oscillator for learning purposes.

Some guys use those little molded chokes with a Q of ~ 50 for the L and they also work well. Predictably, as I lowered the Q of the external L, or went from an air variable C to a varactor, signal losses increased resulting in lower signal output amplitude.

Decreasing resonator Q increases phase noise. For a popcorn radio, I’m not sure the change in phase noise would be a deal breaker in some homebrew projects, but as possible, I think it's wise to employ high Q resonator components: crystal, inductor and the variable capacitance. Thus I'll wind my VXO/VCXO inductors on powdered iron toroids hereafter.

Since a quartz crystal resonator is driven by the piezoelectric effect, fundamental plus overtone frequency modes (3/5/ 7/11) may be derived. I unbypassed the collector and placed a collector choke on it to examine the output with my 'scope. The waveform rung with many harmonics. Lots to learn.

Go débrouillards!

---

4. Funster Line — A Simple 40M Band QRP Trans-receiver

Click for the Funster transmittter notes.

---

5. Miscellaneous Photographs and Figures


THE
"STUDENTS"
POCKET SET OF
MATHEMATICAL
INSTRUMENTS
CRITERION
TRADE MARK
REGISTERED
S&D.B.
MADE IN ENGLAND
REGISTERED DESIGN
Nº 579534
PATENT
Nº 5217

Above — My handed-down geometry set — purchased in 1938. Click for larger picture.



Above — My prototype Colpitts LC oscillator with only a 10K resistor as the load.


169
10.000
10.000
MHZ
MHZ
CDGU
10.000
10.000
MHZ
MHZ
CDGU
CDGU

Above — Hi Q glass encased crystals. Click for another photo.


RCA TUBE
REFERENCE BOOK
19
RCA
48
RCA, ENGINEERING
PRODUCTS DIVISION
MONTREAL, CANADA

April 2014: New player on the scene — Bar Bar Kitty — chief science officer and QC consultant.

April 2014: Other new pet: Munchkin. Clear-spoken and direct — pet me, or feed me... and oh yah, Q2 is oscillating.

MP143
14M31818
CTS5C0315

RF — Test and Measurement

Caitlyn 310 — UHF Beginnings

Respository web page for beginner UHF experiments in 2014-2015.

1. References
2. Transistors, RFCs, Capacitors and a 50 Ω Detector
3. Return Loss Bridge Experiments
4. VCO Experiments
5. Frequency Counter Kit

---

1. References

After a modest quest, I found an excellent microwave primer called Microwaves Made Simple. Principles and Applications by W. Stephen Cheung and Fred H. Levien. Published in 1985, the authors brilliantly teach the basics in plain language (no small task). My copy was printed in December 2013 by Artech House who print single copies of many classic texts on demand. Click for a photo of my book.

The ARRL published 2 UHF compendium books entitled: The ARRL UHF / Microwave Experimenters Manual [1990] and The ARRL UHF / Microwave Projects Manual [1994]. While out of print, used copies seem prevalent and might serve as good resources for builders who hunger for circuits and Ham-related UHF circuit building information. Click and click for photos.

Instrument companies provide continuing education and materials to educate & support their customers. With luck you'll find helpful free application notes and other tools. Two recent RF library additions include an Agilent CD containing all their current application notes and webcasts [my image is truncated and the CD includes applying SA's, 'scopes and signal generators], and this old Spectrum Analyzer Fundamentals booklet by Tek.

---

2. Transistors, RFCs, Capacitors and a 50 Ω Detector

I want to grasp circuits from 300 to 1296 MHz. This meant acquiring some UHF parts, making some bench tools and buying a 50 Ω detector to sweep and/or measure power in my UHF stages. Click for a snapshot of some of my parts cabinets.

BJTs

I'll employ the BFR93A, 2SC3356, and 2SC3583 as my mainstay NPN bipolars; at least to start with. Numerous transistors will work — price, availability, NF and shipping costs informed my choice. I'd also feel happy with MRF901, BFR92 and BFR96 NPNs and it's always fun reading datasheets. My PNP choice = BFT93 by NXP. Later on, I'll add in discrete GaASFET and other non-BJT species. Only 2 MMICs lie in the parts cabinet: MAR-3 and MGA-61563.

Radio Frequency Chokes (RFC)

Although, I'll also wind, or perhaps ply carefully dimensioned copper board traces to make RF chokes, I built up a stock of lower Q chip inductors in size 0805 and 0603. These include 8.2 nH, 33 nH, 68 nH, 220 nH, 330 nH, 470 nH and a few other values. For RFCs we need to consider L, tolerance, SRF, Q , maximum current and temperature stability — it's probably better to only buy clearly specified parts so you can study their datasheet to glean this information. I've swept nearly all my RFCs and recorded their SRF.

Choosing RFCs — SRF (series resonant frequency)

An RF choke exerts its greatest impedance at its SRF and in the case of a first-order RFC such as a single inductor, we should aim the SRF at or near the frequency we wish to attenuate the most. Consider a choke in the emitter lead of a BJT Colpitts oscillator with a frequency range from 375 to 400 MHz: The choke's ideal SRF should lie somewhere above 400 MHz. As possible, the SRF of a first-order RFC should exceed the operating frequency of the device it's choking.

In higher-order filter applications such as a C-L or C-L-C (pi filter) applications, engineers tend to target the choke's SRF to >= 10 times the operating frequency. Challenges such as limited inductor choices, needing to match stages, or coping with stray reactances will arise, however, as amateur UHFers, we just try our best to fit an RFC.

UHF Capacitors

I swept numerous size 0805 + some 0603 and 1206 capacitors in a microstrip line jig to determine their SRF. Math formulas enable us to calculate and plot attentuation, Q and ESR at self-resonance if we wish. Click for 1 example. Although we rarely apply capacitors at their SRF in practical circuits, considering Q, ESR and attenuation gets us thinking that capacitor SRF is a dynamic value that may vary widely with part size, capacitance and datasheet specified Q.

For instance, if you take a size 1206 capacitor, measure its SRF and then replace it with a same-value size 0805 capacitor, the SRF of these two caps might vary by as much as 200 MHz or more. Size does matter! Even the same value capactor by a different manufacturer may be a SRF game changer. Bob, K3NHI tells it correctly: to measure *is* to know.

Datasheet specified capacitor Q is usually measured at a low frequency like 1 MHz. Since Q decreases as frequency increases, a capacitor that specs a Q of 2500 at 1 MHz may only sport a Q of 87 at its SRF way up at 512 MHz. During sweeps, I measured a deeper attenuation notch and often a higher SRF for "very high Q" caps when compared to the common, low-medium Q, popcorn caps sold as mystery parts by online stores or auctions. I'm now hypervigilent about finding very high Q SMD capacitors for sale at a low price.

I wrote the SRF of all my SMD caps in my notebook and use this data to inform my capacitor choice for RF bypass and tuning. Click for a photo of 3 UHF parts drawers. I've pretty much gone to size 0805 caps to try and garner a higher SRF at VHF and UHF. Still, too, we might have to solder down 0603 parts up above 1 GHz. Yikes!

Did you notice that when you drop a 0805 part on the floor, you never ever find it again? Even a little cough can expunge a size 0603 part from your QRP workbench.

50 Ω Detector

From 0.5 - 200 MHz, my 50 Ω terminated input DSO forms the heart of my test bench. An analog, or digital storage oscillocope with a bandwidth >= 1 GHz, plus a suitable wideband probe costs dearly and for many, won't be an option. UHF bandwidth, thermistor-based 50 Ω power meters are also expensive and lack signal viewing.

Thus, a spectrum analyzer seems the best choice for the amateur UHF enthusiast. A spectrum analyzer with a built-in tracking generator adds serious value — giving us a MF-UHF sweep system with profound utility. One popular, modern TG + SA choice is the Rigol DSA-815. I'm fortunate to have access to gear that measures up to 3 GHz.

3. Return Loss Bridge Experiments (RLB)

I'd be lost without a return loss bridge at UHF. Directivity marks the touchstone of a return loss bridge — and up at UHF grabbing a minimum 20 dB directivity may pose quite a challenge. Experiments to find a bridge with good directivity from 250 to 1750 MHz follow:



Above — A macro photo of RLB#1: 1 of the 3 "string of pearls" type return loss bridge built this Winter. I tried different numbers, sizes and mixes of ferrites. This particular bridge had 3 and then 2 FT37-61 toroids as shown, although I did not shorten the RG-174 coax when reducing to 2 toroids. The 61 mix gave poor directivity and was abandoned.



Notes

Cable -- RG-174

Ferrites -- #43 toroids [FT23-43, or FB43-2401, or FT37-43]

Resistors -- 1% size 0805
100 Ω in parallel

Above — Return loss bridge #1: the "string of pearls" variant. Several web sites feature great "string of pearls" RLB experiments for you to review and many place enough ferrite to extend from HF to UHF. I swept each of my builds in a Rigol tracking generator + spectrum analyzer with 4 frequency markers set. I made an open-circuit sweep [nothing on the unknown impedance port] followed by a sweep with a Mini-Circuits Labs DC - 18 GHz, 50 Ω load threaded on the unknown Z port. The difference between the open-circuit and 50 Ω measurement = the directivity at that frequency.


RIGOL
08:09:47 2014-02-09
Local
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
(dB)
Marker
1.750000000 GHz
-35.10 dB
1
2
3
4

Ref 0.00 dBm Att 10 dB Marker4 1.7500 GHz -35.10 dB

Center Freq 1.0000 GHz Span 1.5000 GHz

*RBW 100.00 kHz VBW 100.00 kHz SWT 150.00 ms

Marker Table

Marker	Trace	Type	X Axis	Amp	Directivity
1D	1	Frequency	250.000000 MHz	-42.26 dB	25.1 dB
2D	1	Frequency	752.500000 MHz	-38.28 dB	22.55 dB
3D	1	Frequency	1.207500000 GHz	-39.27 dB	23.68 dB
4D	1	Frequency	1.750000000 GHz	-35.10 dB	18.64 dB

Above — The sweep of my best "string of pearls" bridge from 250 MHz to 1.75 GHz showing the directivity at 4 frequency points. Click for the open circuit sweep. I felt encouraged by this sweep with five FB43-2401 beads over each piece of coax cut just long enough to fit the beads. I built on 2-sided FR4 copper clad board with at least 6 via wires connecting the 2 copper surfaces.


Return Loss Bridge 2
RF in
51
51
51
T1 = ferrite toroid
2.5 mm OD AL= 537
Unknown
Load
50 Ω
Detector
T1

Above — Schematic of RLB #2: the bridge topology featured in EMRFD. T1 = 5 bifilar windings of 32 gauge wire wound on a *tiny* ferrite toroid boasting a strong AL. I pulled this ferrite from a blown up mixer removed from an old 1.5 GHz spectrum analyzer. I started with 5 toroids, but during winding, got spastic and dropped 2 of them on the floor and concluded that the SMD part gnome who lurks beneath my bench swallowed them up, since I couldn't find them after an intensive search.



Above — Magnified return loss bridge #2 breadboard. Serious UHF enthusiast Paul Wade, W1GHz found that the smaller your breadboard, the better the UHF directivity in his bridge experiments: My findings support his. In RLB #2, I went with plain, size 1206, 5% resistors. I just ordered some size 0603 49.9 Ω 1% resistors for future experiments in my quest to make my ultimate UHF RLB.


RIGOL
12:27:43 2014-02-13
Local
Ref 0.00 dBm
Att 10 dB
Marker1 250.00 MHz -38.75 dB
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
(dB)
RBW
10.000 kHz
50 ohm load "Directivity Test"
1
2
3
4
Center Freq 1.0000 GHz
Span 1.5000 GHz
RBW 10.000 kHz
VBW 10.000 kHz
SWT 15.000 s
Marker Table

Marker	Trace	Type	X Axis	Amp	Directivity
1D	1	Frequency	250.000000 MHz	-38.75 dB	26.79 dB
2D	1	Frequency	850.000000 MHz	-36.12 dB	22.4 dB
3D	1	Frequency	1.300000000 GHz	-29.66 dB	14.82 dB
4D	1	Frequency	1.750000000 GHz	-26.06 dB	10.78 dB

Above — The sweep of RLB #2 from 250 MHz to 1.75 GHz showing the directivity at 4 frequency points. Above ~900 MHz, directivity falls right off, so this bridge won't cut it for a serious UHF bench. I tried reducing T1 to 3 bifilar windings but this worsened the directivity. Click for a different sweep of RLB # 2 from 50 MHz to 1.5 GHz. Directivity = 27.5 dB at 50 MHz, so this bridge would work great for VHF. I imagine that SMD 49.9 Ω 1% resistors might boost directivity a little.

Of course, we're always impressed by the work of Kostas , SV3ORA.

Return Loss Bridge 3

Some experiments with the 3-bead RLB from Sam Wetterlin follow:


#1
MuRata
2K2
Ref
Det
W7ZOI
W7PUA
G4TXG
WA7TZY
SMT
RLB
RF-IN
Load

Above — My build of the Wetterlin 3-bead return loss bridge. This PC board was the only 1 left over from a 2006 joint project between the 4 Hams whose calls are etched on the PCB. Wes sent me this board and some of the parts and I'm grateful. My 3 dB pads = 294 Ω 1% resistors plus an 18 Ω 5% in size 0805. My 49.9 Ω 1% resistors = size 0603. The transformer = a Minicircuits Labs TC1-1-1-13M+. Click for the ferrite description. I used 24 gauge copper via wires to connect grounded nodes to the ground plane on the back of the PC board. I chose to permanently solder a 49.9 Ω resistor on the reference port.


RIGOL
Local
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
(dB)
1
2
3
4
VBW
3.000 kHz

13:16:20 2014-03-28

Ref 0.00 dBm **Att** 10 dB **Marker4** 1.5000 GHz -21.61 dB

Center Freq 750.00 MHz **Span** 1.5000 GHz

RBW 3.000 kHz **VBW** 3.000 kHz **SWT** 166.66 s

Marker Table

Marker	Trace	Type	X Axis	Amp
1D	1	Frequency	100.000000 MHz	-19.75 dB
2D	1	Frequency	600.000000 MHz	-19.47 dB
3D	1	Frequency	1.000000000 GHz	-20.52 dB
4D	1	Frequency	1.500000000 GHz	-21.61 dB

Open circuit sweep

Above — Open circuit sweep with 4 markers set. Span = 1.5 GHz.


RIGOL
Local
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
(dB)
VBW
3.000 kHz
1
2
3
4

13:11:19 2014-03-28

Ref 0.00 dBm **Att** 10 dB **Marker4** 1.5000 GHz -35.25 dB

Center Freq 750.00 MHz **Span** 1.5000 GHz

RBW 3.000 kHz **VBW** 3.000 kHz **SWT** 166.66 s

Marker Table

Marker	**Trace**	**Type**	**X Axis**	**Amp**	**Directivity**
1D	1	Frequency	100.000000 MHz	-45.72 dB	25.97 dB
2D	1	Frequency	600.000000 MHz	-38.49 dB	19.02 dB
3D	1	Frequency	1.000000000 GHz	-36.92 dB	16.4 dB
4D	1	Frequency	1.500000000 GHz	-35.25 dB	13.64 dB

Above — 50 ohm load termination sweep with calculated directivity. Click for the 50 Ω sweep where the span = 200 MHz. I was disappointed with the UHF directivity in *my* build.


#1
Ref
MuRata
2K2
Det
W7ZOI
W7PUA
G4TXG
WA7TZY
SMT
RLB
RF-IN
Load

Above — The 3-bead RLB with added series trimmer capacitors on the load and reference ports. SMT trimmer caps = Voltronics JR300 5.5-30 pF with a Q of 1500. I tried both shunt and series caps to try and boost UHF directivity.



RIGOL
Local
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
(dB)
RBW
3.000 kHz
1
2
3
4

06:55:28 2014-03-29

Ref 0.00 dBm **Att** 10 dB **Marker3** 1.1000 GHz -21.50 dB

Center Freq 750.00 MHz **Span** 1.5000 GHz

*RBW 3.000 kHz **VBW** 3.000 kHz **SWT** 166.66 s

Marker Table

Marker	Trace	Type	X Axis	Amp
1D	1	Frequency	330.000000 MHz	-24.10 dB
2D	1	Frequency	850.000000 MHz	-21.83 dB
3D	1	Frequency	1.100000000 GHz	-21.50 dB
4D	1	Frequency	1.500000000 GHz	-22.44 dB

Open circuit sweep

Above — Open circuit sweep of the 3-bead bridge with series capacitors on the load and reference ports.



Ref 0.00 dBm
Att 10 dB
Marker3 1.1000 GHz -40.18 dB

Center Freq 750.00 MHz
Span 1.5000 GHz
RBW 3.000 kHz
VBW 3.000 kHz
SWT 166.66 s

Marker Table

Marker	Trace	Type	X Axis	Amp	Directivity
1D	1	Frequency	330.000000 MHz	-30.80 dB	6.7 dB
2D	1	Frequency	850.000000 MHz	-42.74 dB	20.91 dB
3D	1	Frequency	1.100000000 GHz	-40.18 dB	18.68 dB
4D	1	Frequency	1.500000000 GHz	-36.36 dB	13.92 dB

Above — 50 Ω load sweep. By carefully tweaking the 2 trimmer caps, I set the deepest NULL at ~ 850 MHz; although it's not as deep as I want. Low end directivity was compromised.

Return Loss Bridge 4

Since my bench experiments with the "string of pearls" (SOP) return loss bridge showed promise, I kept going and eventually built a version closer to my goal: A bridge for 300 MHz to 2 GHz with decent directivity.


SMA
Unknown Z
wire vias
wire vias
RF Port
SMA
50
50
RG-178
50 Ω Detector
SMA
24 gauge copper wire
wire vias
50
wire vias
(6) FB-43-2402
binocular core
FR-4 double sided Cu board
50 Ω Reference
FR-4 double sided Cu board
Bridge 4

Above — My SOP build diagram of Bridge #4. I cut traces in 2-sided FR-4 Cu board to make the needed microstripline paths.The two 49.9 Ω 1% bridge resistors = size 0603, however, my reference port 49.9 Ω, 1% resistor was size 1206. The braid of the coax goes to the unknown impedance port and the center core to the reference port. Six FB-43-2402 binocular cores just passed the diameter of the RG-178 coax and binocular ferrites boosted balance compared to seperate beads in my experiments.

Rather than run coax through the remaining hole in the ferrite string, I just used a 24 gauge piece of Cu wire for balun symmetry. I left the green insulation on the wire to help keep it in place during soldering — I used the same wire spool to make the via wires.



Above — Breadboard photograph. Click for a larger photo. I soldered some thin brass sheet metal to electrically join the ground planes of the 2 carved boards [represents the normal RF-tight metal chassis we apply].The brass sheet boosted directivity 8 dB by improving balun function.

Comments by a prominent figure in our hobby ....."and the thing is 'ugly to the core'. Way to go."


RIGOL
03:59:08 2014-04-14
Local
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
(dB)
1
2
3
4
VBW
3.000 kHz
Open circuit sweep
Marker Table
Bridge # 4

Ref 0.00 dBm

Att 10 dB

Marker4 2.0000 GHz -16.67 dB

Center Freq 1.0000 GHz

Span 2.0000 GHz

* RBW 10.000 kHz

* VBW 3.000 kHz

SWT 66.666 s

Marker	Trace	Type	X Axis	Amp
1D	1	Frequency	300.000000 MHz	-14.47 dB
2D	1	Frequency	800.000000 MHz	-15.28 dB
3D	1	Frequency	1.400000000 GHz	-15.89 dB
4D	1	Frequency	2.000000000 GHz	-16.67 dB

Above — Open circuit sweep with a 2 GHz span and center frequency of 1 GHz.


RIGOL
Local
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
(dB)
VBW
3.000 kHz
Bridge #4
50 ohm load
1
2
3
4

03:56:56 2014-04-14

Ref 0.00 dBm **Att** 10 dB **Marker4** 2.0000 GHz -38.66 dB

Center Freq 1.0000 GHz **Span** 2.0000 GHz

RBW 10.000 kHz **VBW** 3.000 kHz **SWT** 66.666 s

Marker Table

Marker	Trace	Type	X Axis	Amp	Directivity
1D	1	Frequency	300.000000 MHz	-56.82 dB	44.35 dB
2D	1	Frequency	800.000000 MHz	-58.49 dB	43.21 dB
3D	1	Frequency	1.400000000 GHz	-46.70 dB	30.81 dB
4D	1	Frequency	2.000000000 GHz	-38.66 dB	21.99 dB

Above — Sweep with a 50 Ω load threaded on the unknown impedance port and 4 markers showing directivity at those 4 frequencies. Yay — this is much better! I wanted at least 30 dB directivity at 1296 MHz and got it.


RIGOL
04:13:09 2014-04-14
Local
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
(dB)
1
2
3
4
Marker
50.000000 MHz
-13.77 dB
open circuit
Bridge # 4

Ref 0.00 dBm
Att 10 dB
Marker3 50.000 MHz -13.77 dB
Center Freq 250.00 MHz
Span 500.00 MHz
*RBW 10.000 kHz
*VBW 3.000 kHz
SWT 16.666 s

Marker Table

Marker	Trace	Type	X Axis	Amp
1D	1	Frequency	5.000000 MHz	-15.49 dB
2D	1	Frequency	20.000000 MHz	-13.90 dB
3D	1	Frequency	50.000000 MHz	-13.77 dB
4D	1	Frequency	499.166666 MHz	-13.87 dB

Above — Open circuit sweep with a 500 MHz span and center frequency of 250 MHz. I set 2 of the markers to evaluate the directivity at HF.


RIGOL
04:11:53 2014-04-14
Local
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
-100
(dB)
1
2
3
4
Marker
50.000000 MHz
-53.73 dB
Bridge # 4
50 ohm load
Marker Table

Ref 0.00 dBm Att 10 dB Marker3 50.000 MHz -53.73 dB

Center Freq 250.00 MHz Span 500.00 MHz

RBW 10.000 kHz VBW 3.000 kHz SWT 16.666 s

Marker	Trace	Type	X Axis	Amp	Directivity
1D	1	Frequency	5.000000 MHz	-53.73 dB	38.24 dB
2D	1	Frequency	20.000000 MHz	-54.77 dB	40.87 dB
3D	1	Frequency	50.000000 MHz	-53.73 dB	39.96 dB
4D	1	Frequency	499.166666 MHz	-57.58 dB	43.71 dB

Above — 500 MHz sweep of Bridge #4 with a 50 load on the unknown impedance port. The directivity at HF surprised me. Although better suited for VHF-UHF, this bridge will work okay from 5 MHz to ~1.5 GHz.

---

4. VCO Experiments

Ask experimenters about homebrew RF oscillators and you might hear about a pleasing paradox — vexing and satisfying in the same breath! At UHF we usually make a VCO and keep it on frequency by phase/frequency locking to a xtal oscillator reference. I sought some wideband, free running VCOs in hopes I'd inch up the learning curve.



Q1 = 2N4403 , Q2 = MPSH18

Based on a design of Matjaz, S53MV presented in TV Satellite Receive System Part 2: Indoor Unit --- Issue 1/87 VHF Communications

Above — My first attempt at a VCO circuit described by Matjaž, S53MV in a 2-part article published in VHF Communications magazine. The original circuit contained a tunable RF filter, mixer, buffer amplifer + more and I recommend you purchase the 2 articles for your own analysis. Shown with permission from Andy Barter of VHF Communications magazine, I ordered all issues from the 1980s which came on this DVD.

With 28v varactors, this VCO will tune 1 octave minimum.

To bench investigate this stunning common emitter Colpitts variant, I first built it at VHF using through-hole parts with a standard 12 volt tuning voltage that tuned from 49 to 91.4 MHz. The output came from 1 link around the 463 nH inductor terminated in a 1K resistor at the hot end + ground at the cold end to allow 10X probe measurement with my DSO.

Matjaž, S53MV describes his circuit function here. A variable C on the base in combination with the input capacitance of Q2 operates as a tuned impedance matching network and preserves a steep phase slope (which means you have higher Q) — a requirement for low phase noise. In essence, the inductor with a varactor at each end forms an adjustable pi-network to provide correct phase shift tracking.



The LED serves as a shunt voltage regulator -- thus the current through R and Q2 is constant. Noise is low. About 2.15 mA current flows through the diode.

12.22v
1 nF
1 nF
R
1 nF
10.32v
Q1
10.84v
4K7
1 nF
330
4K7
7.69v
0.78v
2K2
0.66v
Q2

DC voltages for
R = 150 ohms

R = 72 : Q2 emitter current = 20 mA
R = 100 : Q2 emitter current = 16 mA
R = 143 : Q2 emitter current = 10 mA
R = 150 : Q2 emitter current = 9.85 mA
R = 270 : Q2 emitter current = 5 mA
R = 470 : Q2 emitter current = 2.74 mA

Q1 = 2N4403 Q2 = 2N3904 in this test

Above — I built the low-noise, temperature-stable, PNP current source using though-hole parts. R provides a convenient way to vary collector current, although changing the PNP base bias also works.



Q1 = 2N4403, Q2 = BFR93A, D1 = D2 = D3 = BB149A , L1 = ~10 nH
Based on a design of Matjaz, S53MV presented in TV Satellite Receive System Part 2:
Indoor Unit --- Issue 1/87 VHF Communications

Above — My UHF VCO schematic. Click for the breadboard photo. A wire positioned near L1 provided the output into my spectrum analyzer. Click for a sweep with the reverse DC voltage set at 0v. Click for the a sweep with the tuning at 28v to establish the lowest possible varactor capacitance. Markers indicate the carrier frequency. As shown, a common emitter VCO exhibits rich harmonic energy and viewing the second harmonic at 2 GHz felt really cool in the 28v sweep. Not to worry — the tracking generator in the Rigol TG + SA units also exhibit strong harmonics and work fine for sweeping.

Click for a pdf file showing how I laid out my board. I cut traces on the top of 2-sided FR4 board and connected any grounded points on top to the bottom ground plane with a 24 gauge copper via wire. A 28v DC-DC Converter to supply the varactors lies on VHF-FM.

I varied L and even tried a 3 mm by 8 mm copper sheet metal inductor but this failed to oscillate. In the end, a single wire with ~10 nH inductance worked to give me the tuning span shown. L1's distance above the ground plane was determined by tuning the VCO for the smoothest transistion across its range. This circuit begs further experiments including Q2 current, L1 and the 470 pF fixed feedback capacitor.

5. Frequency Counter Kit

A sensitive UHF bandwidth frequency counter makes an important tool for the UHF homebrew experimenter. With a search engine, you'll find commercial and kit counters for sale along with DIY projects for builders handy with microcontrollers.

If you already own a decent counter, then a crude prescaler tool employing an IC like the MC12079 might work okay if you can tolerate or manage modulus division by 64, 128, or 256. The MC12079 requires an RF signal between -17 dBm to +3 dBm to count properly, so many builders place amplifier(s) along with anti-parallel clamping diodes before the digital IC. The Motorola datasheet shows a basic circuit to build off.



Above — My first UHF counter experiment involved the Motorola MC12079 and 12080 prescalers. Eventually I made a proper double-sided copper board device with anti-parallel diodes, a MMIC, the MC12079 and some 74AC series logic — it worked okay for casual use. The 2 big drawbacks were MC12079 self-oscillation with 0 applied input signal and having to remember to multiply measures by my set prescaler division integer. I sought a long-term solution.

A Solution Appears

In 2012 I bought a second-hand, calibrated HP 53131A with the optional A6 High Stability Timebase from an EE for ½ the going price at the time. 225 MHz bandwidth poses its only limitation; it even came with the original spiral bound manual.

This summer, Shahriar from TheSignalPath.com reviewed a Chinese kit to take the HP 53131A to 3 GHz with a clone of the original HP OPT30 Channel 2 kit. Based on his quantitative review and warm thoughts of using my sturdy HP counter at UHF, I got 1. Mine sold on eBay for $87 Canadian including shipping. Click for TheSignalPath.com video. Click for a larger photo of the kit I bought.

53181 A 225 MHz
FREQUENCY COUNTER
CHANNEL 2
MEASURE
LIMITS
MATH
DISPLAY
CHANNEL 1
Freq Ch 2
Uppr & Lower
Scale & Offset
More Digits
Fewer Digits
Trigger Sensitivity
Gate & ExtArm
Limit Modes
Stats
50 Ω 1M Ω
DC AC
Local
Save & Print
Run
Stop/ Single
X10 Attenuate
100kHz Filter
Enter

Above — My HP counter with the kit installed as Channel 2.


AGILENT/HP 53131/53132 OPT 030
BG7TBL 2013-10-18

Above — Top of the circuit board. Anti-parallel diodes, 4 MMICS, passives and then even more anti-parallel diodes go before the prescaler chip.


AGILENT/HP 53131/53132 OPT 030
BG7TBL 2013-10-18
C21
R8
CR4
C18
C19
C17
U4
C16
U3
C15
U2
C14
CR5
CR3
C10
R5
C9
C8
R4
C7
C6
R3
C5
R2

Above — Close up of SMD circuitry.



Above — Rear view of the circuit board showing stiching vias that join the top ground plane to the bottom ground plane along the signal path. My tests showed that it works okay to 3.1 GHz. Click for a picture of the installed board. I'm very happy with my HP counter's boosted bandwidth.


MICROWAVES
MADE
SIMPLE
Principles and
Applications

RF — Test and Measurement

Funster Line — Transmitter

Funster Line
VFO IN
FO
RF GAIN
KEY
XTAL
POWER

Menu Item 4 on the HF Embarcadero web page. Click here to go back.

The receiver will go on its own page and hopefully I'll complete and write it up this Fall.

1. Transmitter
2. References

Introduction

I began the Funster transceiver line in 1995 and show the 2014 version [now back to a CW trans-receiver on the 40M band]. Judging by reader feedback, plus analog scratch-homebrew threads in social networks, email lists and print, many of us feel a nostalgic pull towards old-school radio. Me too.

Now at version 8 — Funster shares my joy in making a simple, old-style radio with all discrete parts. In some ways, this radio set is a twisted version of Wes and Roger's Ugly Weekender from QST for August 1981.

1. Transmitter

Summary

Variable power: 128 to 3312 mW @ 13.6 VDC. Switchable 7.04 MHz xtal oscillator or external VFO input port. Solid state transmit/receive [T/R] circuit with PIN diode. External continuous and switched 12 VDC power jacks. Single-ended BJT Class C power amplifier with 67% efficiency.

Note: I state 12 VDC in my DC circuits, however, this nominal value might better be termed 12 -13.6 VDC.

Key up power current draw @ 13.6 VDC = 17 mA. Key down current @ 3W RF power with 13.6 VDC = 420 mA.

DC Circuitry

It's fun to march off the signal path and focus on DC circuitry — switching, regulating and filtering the DC voltage feeding our RF or AF stages with finesse. Trans-receivers contain DC, RF, AF and external patch cords that benefit from mindful DC line filtering + selective high-isolation amps in the signal path to prevent RF flowing where it's unwanted. You'll see heaps of decoupling with RF + AF bypass and a few strong reverse-isolation amplifers in this radio set.


Polarity Protector
IRF9630
12v in
S1
s
d
g
2.52v
10K
10v
100 µF
.1
140 µH
FT50-43
100 µF
.1
A
12v Out
To receiver
or VFO etc.
B
12V to PA
and PIN diode
switch collector
C
Keyed 12v Out
.1
22
D
Keyed 12v to
keyed voltage
amplifers
510
.22
.1
KEY
3K3
.01
Switch
TIP42A
1K5
22
1N4148
E
~9v (with load)
To xtal oscillator
and buffer
.1
1K5
9.67v
100 µF
.1
47 µF
.1
10v
Voltage Regulator
2N4401
Funster
Transmitter DC Circuitry

Above — The DC circuit board. Click for the breadboard photo. A reader sent me 2 IRF9630 power MOSFETS: avoiding the voltage drop of the usual single rectifier diode, I employed 1 as a reverse polarity protector. Another reader sent me a long strip of 2N4401 BJTs, so I ran them instead of the equally good 2N3904. Thanks for the parts guys!

A simple series voltage regulator with a zener diode reference supplies DC to the crystal oscillator and its buffer. The base-emitter voltage drop of the 2N4401 emitter follower lays in series with the load, so load current changes alter the regulator output voltage. Vout = Vzener - VBE : so the regulated voltage is roughly 9 VDC.

Oscillator Circuitry


Oscillator Circuitry
From
~9v regulated
100
2N4401
NC
68
.1
DPDT
.1
15K
7.040
MHz
35.4 µH
10t FT37-43
10K
10K
2N4401
390 pF
1K5
390 pF
330 pF
.1
47
560
.1
4K7
.1
low noise oscillator
front panel
50 ohms
external VFO
-5.65 dBm to equal xtal oscillator
buffer
Funster

Above — Oscillator circuitry. I soldered my oscillator circuitry on the DC control board. Click for the breadboard. Click for a close-up of the old NorCal crystal supplied by NT7S — thanks Jason! To equilibrate to the xtal oscillator AC output voltage, the VFO input port should run about -5.65 dBm. I might stick a 6 dB attenuator pad on the front panel switch and use a 7 MHz VFO with 0 dBm output power.

Keyed Voltage Amps


Keyed Voltage Amps
Funster
D
22
2N4401
.1
47
T1
T3
.1
to PA
*
100K
.1
.1
1K5
10K
RF Gain
T2
1K5
.1
2N5109
18K
.1
3K3
.1
1K
.1
75
4.7
d
from oscillator
g
s
J310
3K3
150
.1
52 mA @ 13.6v
46 mA @ 12.2v
Will deliver a sine wave until 6.79 Vpp [20.6 dBm] -- then gain compression begins *
T1 = T2 = T3 = 10 BFT FT37-43

Above — The 2 keyed voltage amplifers. Click for a breadboard photograph. I set the value of the RF gain pot series resistors by placing a 100K pot before and after the 10K gain pot and tweaked them back and forth to find close to 3W maximum and 125 mW minimum RF power with the gain pot set @ CW and CCW respectively. The 100K pots were removed, measured and nearest standard value resistors substituted: 100K and 18K.

By carefully choosing the 75 Ω emitter resistor, the 2N5109 feedback amp output remains a sine wave at the drive levels needed for a PA output at 3 Watts. At 3 Watts PA output, the feedback amp output voltage = 5.91 volts pk-pk [19.4 dBm]. The emitter current shown will cleanly drive a PA for more power if desired. Boost it as needed.

Power Transistor and T/R Switching



Above — Final testing the PA and T/R circuitry before installing it into the Hammond chassis. Click for a bigger photo of my test setup.

Three temporary RF connectors were soldered on this board for bench measurement. I connected the (SMA) receiver port to Channel 1 of my 50 Ω terminated 'scope to measure the RF not getting shunted to ground by the PIN diode. The SMA cable/connector to the far left is a temporary cable connected to the keyed voltage amp board output in the Tx chassis — thus I tested the PA stage with its own xtal oscillator and RF amplifers. The right-sided BNC RF port connects the PA low-pass filter to a 10W, 50 Ω dummy load via a 22 cm 50 Ω patch cable.

Further, I measured collector voltage + collector current with 2 DVMs and also PA output power in my oscillocope (DSO) Channel 2 with a 10X probe employing a tiny ground lead.


PA and T/R Circuitry
XL = ~400 Ω
9.1 µH
.1
50 Ω
FT50-61
Receiver Port
8.8 dB loss
PIN diode
B
18.6 µH
FB43-2401
.1
RFC
+
+
10 µF
.1
10 µF
.1
B
2N4401
BAR64-05
1N4148
D
125 µH
FT50-77
1K
RFC
10K
100K
.1
.33
10 BFT
FT37-43
RFC
24.6 µH
FB43-2401
XC = ~400 Ω
56 pF
FCo = 7.36 MHz
1.38 µH
1.7 µH
1.38 µH
50 Ω
ANT
from
voltage
amps
.1
T50-6
47
43v
220 pF
680 pF
680 pF
270 pF
2SC1969
Funster
PIN Diode SOT-23

Above — PA and T/R circuitry schematic. Click for another breadboard photograph taken before the 2N4401 switch was added. Although we might run a BD139 or other cheap BJT for the final, I chose my favorite HF classic, the 2SC1969. This transistor will survive a high VSWR, however a 43 volt - 500 mW zener diode further protects it from such.

In 1 version with a 1:4 Z collector matching network and no zener diode, I measured 6.25W RF power after tweaking the 100K and 18K RF gain limiting resistors in the preceeding hycas voltage amp to drive the PA harder. At ~3W maximum power in my final experiment, the 2SC1969 barely warms up.

Collector Matching

After a number of experiments, I learned that from tens of mW up to ~ 3.3 Watts RF power, we may omit collector matching and still get reasonable efficiency if you run a collector choke >= 15 µH. Thus, I made the maximum power ~ close to 3W — easy peasy.

Ask QRP enthusiasts what QRP is all about and they might extol the thrill of exacting the most kilometers per Watt — in keeping with that spirit, I love turning down my Tx power and the Funster front panel RF gain control makes it a breeze.

The PA circuit is standard fodder. I wound the 24.6 µH and 18.6 µH RFCs on FB43-2401 ferrites [a single hole bead that looks like a fat FT37-43]. An FT37-43 or FT50-43 makes a great substitute.

PA Measures


Ref 10.00 dBm
Att 20 dB
Marker1 7.0466 MHz -53.85 dB
Delta Marker
7.046667 MHz
-53.85 dB
10
0
-10
-20
-30
-40
-50
-60
-70
-80
-90
2nd Harmonic
10 MHz clock
in SA
1

Above — Spectrum analysis of the Tx output. The 10 MHz clock signal from my spectrum analyzer lays between the fundamental and 2nd harmonic. The 2nd harmonic = -53.85 dBc @ 3W power output.


10X Probe on 2SC1969 Collector
Agilent
Acquisition
Averaging: 16
2.00GSa/s
Channels
DC 10.0:1
DC 1.00:1
Measurements
Freq(2): No signal
Pk-Pk(1): 34.66V
Freq(1): 7.04MHz
Pk-Pk(2): No signal
T
1

Above — PA collector waveform at 3W output measured with my DSO's 10X probe.

EQUUS
#4320
13.58
DCV
OFF
ACV
VICHY
VC99
APO
DC
0.331
AUTO
A
MAX/MIN
Hz/DUTY
REL
HOLD
RANGE
DC/AC
Hz
°C
hFE

Above — Set your meters on stun! DC measures to calculate PA efficiency [See RF Workbench 6]: DC power = 13.58V x 0.331A = 4.49W. RF power = 3W. Efficiency = RF power / DC power = 3W / 4.49W = 66.8%.

T/R Discussion for Single Band Transceivers

Previous Funsters ran a simple QSK T/R circuit developed by Wes, W7ZOI in the early 1980s: a series X = 500 Ω resonator with anti-parallel diodes between the L and C. The series capacitor presents 500 Ω reactance to the 50 Ω transmit line so that only a small portion of the transmitter power flows to ground via the diodes and even less reaches the receiver input. In short, the 500 Ω capacitive reactance + clamping action of the anti-parallel diodes protect the receiver front end.

For 1 band, this simple circuit sizzles. Two potential concerns:

~6-9 dB loss of the receive signal making it better for lower HF, although I've seen builders add a receive preamp and use this T/R system on 12 and 10 meters. Since both band noise and signals get attenuated simultaneously, I've rarely had readability issues on 160-30 meters in my popcorn transceivers.

The anti-parallel diodes may cause IMD. The intercept for the 500 Ohm series reactances with shunt diodes is around +6 or +7 dBm. This might exert problems in a high performance receiver front end, but poses a non-issue with typical NE612 front ends. Many builders, including Wes, reduce IMD potential with 2 or 3 series diodes on each leg. Another solution includes running a PIN diode as the shunt element. That's what I did.



Acquisition
Normal
2.00GSa/s
Channels
DC 10.0:1
DC 1.00:1
Measurements
Pk-Pk(1): No signal
Freq(1): No signal
Pk-Pk(2): 1.93V
AC RMS - FS(2): 673.9mV

Acquisition
Normal
2.00GSa/s
Channels
DC 10.0:1
DC 1.00:1
Measurements
Pk-Pk(1): No signal
Freq(1): No signal
Pk-Pk(2): 1.46V
AC RMS - FS(2): 575.8mV

7.04 MHz into detector

Same signal into anti-parallel diodes

Above — The DSO tracing of an experiment showing the before and after effect of 2 anti-parallel diodes. The voltage across a silicon diode varies with the current going through it. Silicon diodes don't conduct much current until the voltage across them reaches a threshold [typically ~0.6 to 0.7 volts].

In situ, the forward threshold voltage of each diode limits the circuit voltage by clipping off AC voltage above its threshold. Clamping refers to the limiting of voltage in *2* directions using anti-parallel pair(s) of clipping diodes. For example, if a negative-going AC dips more than 1 diode drop below ground, the left hand diode will begin to conduct and clip off any voltage above its threshold. This, of course, describes the "ideal diode" — in real life, factors like switching speed, current-handling and temperature are all in play.



Above — 2 possible T/R schemes. Figure A shows the classic W7ZOI T/R system with 2 diodes per leg. See EMRFD Fig 2.112, for an example with 3 diodes per leg. For 1 band, it's often our go-to circuit.

Figure B shows a scheme well suited for VHF on up: Both PIN diodes get forward biased during transmit mode, however, a 1/4 wave transmission line lays between the series and shunt PIN diode. 1/4 wave transmission lines exert magic [actually it's pure physics that may be verified with a Smith chart]. When the shunt PIN diode gets biased *on* and grounds the receiver port end of the transmission line, the other end looks like an open circuit and thus power flows to the antenna port and not into the forward biased shunt PIN diode to ground. I hope to apply this system in future VHF and UHF projects and sadly, it's impracticable at HF.

Funster Version 8 T/R

As it happens, I seek experience with PIN diodes and therefore shunted a PIN diode instead of running anti-parallel diodes in the classic W7ZOI T/R scheme. This meant adding a transistor switch to quickly bias on the PIN diode @ *key down* and run a little hang time @ *key up*.

Please refer to the PA-T/R schematic. During key down, keyed 12 volts saturates the 2N4401 switch and 11 ma current biases *on* the PIN diode. At key up, the BJT switch's base voltage is held on by the 10K plus series 0.33 μF capacitor just long enough to allow the stored energy in the large PA collector choke to collapse — protecting the receiver.

Feel free to experiment with the timing capacitor value. Previously, Wes, W7ZOI suggested connecting the T/R receiver port to a 50 Ω teminated 'scope for general measurement and also for clocking up RC time constants in DC switching circuits. With a 2 channel 'scope you can monitor the receiver port switch function in 1 channel while watching the PA collector AC voltage in the other. Now that's experimenting! Click for a sample from my QRP workbench.

I chose an XC / XL of 400 Ω for the series L-C network. The 9.1 μH coil shouldn't be wound on a 43 material ferrite [the Qu is just too low]: a bigger powdered iron toroid like size 68, or even a 61 ferrite material toroid works okay from my experiments [Q's as high as 162 were measured on a FT50-61 @ 1 MHz in 2013]. Although this coil tunes coarsely, try tweaking the 9.1 μH inductor with thumb and forefinger during actual signal testing in a receiver.

I wound the 125 µH choke connected to the pin diode cathode on a 77 material ferrite toroid to get it done with just a few turns and avoid a self resonant frequency close to 7 MHz.



Output at Receiver port measured with 50 ohm 'scope. Tx power = 3W

Acquisition
Averaging: 16
2.00GSa/s

Channels
DC 10.0:1
DC 1.00:1

Measurements
Freq(2): 7.04MHz
Pk-Pk(1): No signal
Freq(1): No signal
Pk-Pk(2): 145.9mV

Above — 50 Ω terminated DSO measurement of the receiver port @ 3W transmitter power. Theoretically all power should shunt to ground through the PIN diode, however, the diode exhibits a little resistance and the series L-C circuit contains reactance, so isolation is never perfect.



Receiver port output low-pass filtered into 50 ohm 'scope. Tx power = 3W

Acquisition
Averaging: 16
2.00GSa/s

Channels
DC 10.0:1
DC 1.00:1

Measurements
Freq(2): 7.04MHz
Pk-Pk(1): No signal
Freq(1): No signal
Pk-Pk(2): 123.8mV

Above — A low-pass filtered measure of the receiver port while in transmit mode. The beauty of a 50 Ω measurement environment shines: I placed a 7.36 MHz-bench module low-pass filter between the receive port and my DSO to quantify the leaked power to the receiver port as -14.17 dBm when the transmitter delivers 3W. Safe for my receiver.

My sincere thanks to those who offered advice and feedback during the build of this transmitter.


VFO IN
7.04 MHZ
RF GAIN
KEY
-5.7 DBM
VFO
POWER

Above — Funster in the field.


RF OUT
RECEIVER
SWITCHED
12V
12V OUT
12V IN

Above — Rear view of the Funster Tx.

VFO IN
VFO
XTAL
RF GAIN
POWER
KEY

---

2. References

T/R References

Perfecting a QSK System. QEX for Mar/Apr 2006. Markus, VE7CA. Click for pdf.

Electronic Switching and How it Works, QST for September 1984. Doug, W1FB

7 MHz receiver -- discussion begins on page 215 -- On page 214 in Fig 1 see the 33 pF input cap plus receiver protecting anti-parallel diodes. Also view the 555 timer and other T/R control circuitry in Figure 2 on page 215. *This receiver realizes the first-ever printed version of the W7ZOI T/R system described earlier.* Solid State Design for the Radio Amateur. ARRL,1986 [out of print] by Wes, W7ZOI and Doug W1FB.

Transmit - Receive Antenna Switching. EMRFD. First published by the ARRL in 2003. Page 6.68.

Schematic for the 30-W, 7 MHz power amplifier. Figure 2.112 [page 2-42] EMRFD. Design by Wes, W7ZOI

VHF FM — Supplement 1

This page supplements VHF FM

1. 10.7 MHz IF Strip - with example broadcast band FM receiver
2. NOAA Receiver Experiments @ 162.55 MHz

---

1. 10.7 MHz IF Strip

I'm inexperienced with making FM receivers and lack confidence. I began with a utility module to allow basic assessment of the circuit gain required for different detectors, ceramic filter bandwidths, and more so — to get something working to boost my confidence.

The FM receiver 10.7 MHz IF standard began soon after World War 2 and 10.7 MHz still makes sense for the primitive radio builder — surplus IF filters still seem available in a variety of bandwidths. Although vexxing, if we suffer from receiver images at 10.7 MHz, we can always filter the input better, or jump up the IF and make a crystal filter for say 20 MHz. Above 20 MHz good, inexpensive, fundamental-mode crystals get hard to find.

Mixer

I chose a diode ring mixer; again. After trying other mixers such as balanced FETs, or an NE612 , I kept coming back to the diode ring. Partly I'm biased and partly it's from from measures like this one. Although the oscillators weren't perfectly set for a 10.7 MHz IF, the LO and RF signals are both > 40 dB down from the desired IF — love this.

Since I designed a 50 Ω bench module, the IF output contains a source follower to drive the IF port. In an actual "keeper" receiver, you probably wouldn't bother since you might just directly drive the detector, or perhaps another 330 Ω input/output IF amp before the detector.

Although I humbly build simple/primitive circuits, my design goal is never for a *low parts count* — each part serves its purpose. A low parts count ideology plus minimalism exploits the frugal and primitive homebrew nature of our brother hobbyists, however, often gets out of hand. Some builders just cite a low parts count *design goal* to rationalize a poor design. Worse yet, inexperienced minimalists often exclude vital parts such as DC supply decoupling and bypassing, temperature stablizing bias networks, or adequate band-pass filtering. To each his own. Please discern all you see or read in homebrew radio; we're builders, not lemmings.


12.2v
33
51
.1
.1
.1
68
T50-6
24t
8t
10 BFT
FT37-43
8K2
4K7
.1
330
1320 Ω
10t FT37-43
tap @ 3t from
source end
2987 Ω
1K
LO
1035 nH
RF
3t
47 pF
.1
J310
5 - 30 pF
1K
820
.1
3K3
2K2
J310
39
.1
50 Ω
RFC
~12 µH
180
220 pF
120 pF
120 pF
100
330 Ω input/output Z
ceramic filters
2N3904
4.7
11.1 ma
908 nH
49.9 Ω
Gain of amplifers including filter losses = 18.1 dB
Diode ring mixer
2nd order diplexer
Chebyshev response
Losses of mixer plus diplexer = 8 dB
10.7 MHz IF Strip

Above — Click on the IF strip schematic to view it. Most all the stages were discussed on VHF-FM. My net module gain = 10.1 dB. The 2 ceramic IF filters = 230 KHz Muratas with a measured average loss of 6.15 dB each.

LO
RF
10.7 MHZ IF
STRIP

Above — The boxed up circuit contains 3 SMA jacks. Click for a photo of the completed breadboard.



Above — A close up of the mixer, diplexer and JFET amp, although the SBL-1 mixer is disconnected. This board contains a temporary BNC jack to allow testing of the non-mixer parts such as JFET gain, diplexer loss, return loss, to confirm the tuning cap choice and also to look for any UHF oscillations eminating from the FET, a UHF part. Click to zoom in on the common gate amplifer with its gate lead soldered as close to the plastic case as possible.

Detector

I tried to homebrew my first IF amp +/- limiter and detectors , but felt unhappy with their performance, failures, circuit complexity and/or noise issues. Click click or click for 3 raw, miserable design examples from Winter 2014. Discouraged; after 2 months of lamenting, I opted for an IC detector subsystem. 3 relic part choices might include the CA3089, SA604A or LA1150.

In my case, the CA3089 suited me best and offers a lot: a double-balanced quadrature FM detector with limiter + IF ampifiers; squelch, AFC, AGC, AF preamp and the potential for high-fidelity FM reception. All that's required is an outboard detector resonator — easy to build with a powered iron toroid plus a fixed + trimmer cap.
Price + shipping varies widely, but last year, I got 5 shipped to me from Europe for $7.25 USD and these will make 5 receivers — not bad at all. What hobby isn't expensive?

I've even read that some builders used the CA3089 for an S-meter amplifer, although its logarithmic compliance is far from stellar. You'll need to download the CA3089 datasheet.

Let's build a receiver:


ANT
Block Diagram
98.2 – 119.4 MHz
RF
IF
AF
VFO
10.7 MHz IF STRIP
CA3089
LM386

Above — The block diagram. The antenna = 1 meter piece of wire soldered to a SMA jack that was threaded into a brass sheet to fashion a crude ground plane. No LNA or input band-pass filtering was employed.


12.22v
1nF
100
1nF
15K
10pF
COG
98.2 – 119.4 MHz VFO
Tune
air
air
100 pF
COG
10K
15 pF
COG
3K3
10 pF
COG
104 nH
1.9 - 9.7 pF
2 pF
NPO
1 pF
COG
2.55 mA
PN5179
51
1nF
L1
~12 µH
100 pF
100K
180
1nF
10.84 mA
J310
51
1nF
11t
2t
50 Ω
1K5
FT23-43
~6.5 dBm
10K
180
1nF
10.68 mA
J310
L1 = 3t BN43-2402

Above — The temperature compensated, free running VFO. Normally we should run a VCO-PLL, digital contraption, or a VFO/VCO with ALC feedback, but this thing worked fine to learn on.



FL1 = 330 Ω input/ouput Z ceramic 10.7 MHz IF filter
RFC = 22 - 35 µH choke wound on a #43 ferrite

Above — The detector assembly. To match to the 50 Ω IF strip port, I employed a common base amp with a 330 Ω collector resistor driving a final 230 KHz wide "tail end or mop up" filter. In many designs you could simply drop this amp as the gain isn't really needed. On the other hand, the CA3089 contains a limiter and it won't hurt at all.

To make the detector coil, a small square island was carved on the copper clad board. The island was bisected so that pin 9 soldered to 1/2 the island and pin 10 to the other half. The 3K9 R, 56 pF C and a small, high Q SMT trimmer capacitor bridged the 2 islands. Finally, a 2.23 μH, T50-6 toroidal inductor was soldered across the 2 islands.

Tune a station and peak the trimmer cap for the most crisp sounding audio — it's set and forget. When driven with enough signal for full quieting, the CA3089 delivers very low distortion — the FM receiver in my truck sounds worse.

An RFC provides a DC short across pin 8 to 9 and keep ~5.5 VDC bias on the pin 9 transistor base. The minimum inductance should be 10X the detector coil. I wound my RFC with 6 turns on a BN43-2402 [35 μH] , but any old #43 ferrite wound choke >= 22 μH should work. For my chokes, I prefer a low # of turns on a binocular core to avoid any SRF issues.

Since the CA3089 contains a powerful audo preamplifer, only an AF power amplifer with low gain is required. I opted with the old LM386, but in future, better, "keeper rigs" I'll add an op-amp tone control stack driving a pair of power followers for good measure.





Above — Final audio power amp: an LM386 set for a voltage gain of 20 with some low-pass filtering and stout DC line filtering.

Click for a photo of the detector and LM386 assembly. Click for a better view of the outboard resonator and nearby RFC.

Outcomes

After connecting the VFO, antenna, IF strip, detector assemby, speaker and powering them up, loud FM radio blared through the loudspeaker. I tuned every local FM station with full quieting and felt surprised that despite no band-pass filtering, plus no RF preamp, it worked and sounded so well.

Further experiments showed that inserting as much as 15 dB attenuation between the IF stip and the detector assembly still kept full quieting on all the stronger stations. In some cities with multiple, strong FM stations, input band-pass filters will be needed. I'll cover that in a later installment.

I connected this VFO to the IF strip and tuned in my local NOAA weather station at 162.55 MHz. Click for a photo of the VFO built on a piece of bent copper sheet metal.

Future experiments may include changing ceramic filter bandwidth, trying different mixers, applying varactor-tuned input band-pass filters for strong FM environments and for FM Dxing. Finally, I'll design a low-noise preamp with a common gate JFET and/or a dual-gate MOSFET. Utimately, I hope to make a dedicated NOAA weather receiver, a broadcast FM Dx receiver and then some narrow band FM jobs for 2M or 6M. The future looks good.

Audio sample one : a few local stations [mostly recorded before I added the negative feedback on the LM386]
Audio sample two: a weak signal [our provincial Highway Report] that doesn't reach full quieting.

Thanks.

---

2. NOAA Receiver Experiments @ 162.55 MHz

I document some *raw* experiments and hopefully 1 day will make a good receiver for my local NOAA FM broadcast.


12.22v
220 pF
COG
100
220 pF
COG
15K
Tune
47 pF
COG
BFS17A
0.5 pF
COG
5 pF
COG
10K
15 pF
COG
~ 49 nH
air
2.7 pF
COG
2K7
10 pF
COG
2 -
6 pF
air
1.4 -
4.6 pf
air
TUNES 168.6 – 175.1 MHZ

Above — I built a VFO for 173.25 MHz with fine tuning for my local, NOAA weather report receiver @ 162.55 MHz. The fine tuning 2- 6 pF variable capacitor in series with an ATX 0.5 pF chip cap resolves 10's of kilohertz to permit tuning narrow band signals. You'll especially need fine resolution tuning when applying ceramic IF filters <= 150 KHz.

Above — The 2 VFO air variable tuning capacitors. Click for the circuit breadboard with a tuned, common emitter buffer, that I'd rather not show [because it sucks]. I ran the VFO into a bench module to boost the power up between 5 and 10 dBm in my experiments.

Since @ VHF, my VFO went on 2-sided FR4 board with several wire vias joining the 2 surfaces. We normally avoid double sided boards for VFOs since doing so makes a low Q, potentially moisture absorbant, undefined temperature coefficient "capacitor" that may worsen temperature drift. For bench learning and in particular, FM reception, temperature stability tested adequate and I can listen for hours without retuning.


2.23 µH
T50-6
12.2v
10-30 pF
target 74 pF
4.7
15
56 pF
.1
100
.1
.01
.01
T50-6
24t
8t
.1
68
RFC
3K9
1K
330
11
8
9
10
1
CA3089
6
2K2
AF out
330
2987 Ω
4K7
8K2
3
.01
2
4
14
16
1K
10.7 MHz IF
820
.1
47 pF
10
4.7
.01
5-30 pF
J310
d
s
g
.01
NC
2N3904
Ant
10K
220 pF
d
g
s
220 pF
47K
390
100
4.7
12.2v
10K
220 pF
2-6 pF
~149 nH
1 nF
50 Ω
39
173.25 MHz LO
Peak
6 turns
FT23-43
220 pF
4K7
220 pF
560
MPSH10 or PN5179

Above — The entire receiver with a cascode mixer from EMRFD. In experimenter's mode; I tried out many ideas. For example: different bandwidth IF filters [settled on 230 KHz] , 1 versus 2 ceramic filters, or eliminating the 2N3904 amp [2 better drove the CA3089]. One salient learning — IF filters may possess a wide variation in center frequency and thus if you have a sweeper, matching them might be useful. In this receiver topology, you don't need to match 230 KHz or 280 KHz ceramic filters; the mismatch became noticeable with a <= 150 KHz 3 dB filter bandwidth.

I boosted the VFO signal with a common base amp — I varied the power into this LO amplifier by applying different strength attenuator pads. Between 1.5 to 2 Vpp on the mixer gate gave a reasonable compromise of conversion gain, noise and easy-to-get VFO power. From EMRFD, maximum conversion gain occurs when driven with 5 Vpp.

This unbalanced mixer worked fine, however, without a metal case, I heard a little hum from my DC supply and noises from household appliances such as the clothes washer and fridge. This receiver suffered from microphonics as well. The AF amp was a LM386 set for gain = 50.

A simple LC resonator tuned the mixer RF input and proved essential. I tried different ways to couple a 25 cm long wire antenna such as tapping the coil and an L- network, however, my main antenna peeve was severe hand capacitance effects. Although this receiver does not require a preamp for RF gain, the isolation seems needed. If you put your hand near the telescopic whip antenna of my Realistic Pro 2020 scanner, no noise or RF disturbance arises.

From studying scanner and FM receiver schematics, most rigs contain a dual-gate MOSFET preamp for a low noise figure and high input isolation. These MOSFET amplifiers feature input and output tuning, although with slug-tuned inductor cans and the oh-so-typical varactors, the resonator Q runs low.


Basic Pre amp
12.2v
100
220 pF
10K
~149 nH
50 Ω
27
PN5179
To
Mixer
Ant
220 pF
560
220 pF
4K7
220 pF
2-6 pF
S21 = 11.87 dB

Above — I quickly built a tuned-output common base amp to study front end isolation. I removed the existing resonator and connected this to the JFET mixer gate. It eliminated antenna hand capacitance effects. Click for a sound byte of the receiver with this preamplifier and a 20 cm wire antenna attached to its input. [206 KB download]. I reckon some of my receiver problems arose from the mess of unshielded boards, modules and wire on my bench.

Tuned Input with a 2-Gate MOSFET   [162.55 MHz]

A dual gate MOSFET preamp concluded this day's experiments. Tests of a simple input network follow:


Input Assessment 1
12.2v
51
220 pF
220 pF
10K
4K7
220 pF
51
G2
G1
D
S
220 pF
50 Ω
SMD bead
D
G2
G1
S
BF998
2.2 - 6 pF
50 Ω
96 nH
1.33 - 4.6 pF

Above — Input Assessment 1. To examine the input without any output network effects, I loaded the BF998 drain with a 51 Ω resistor and matched the input parallel resonator for the greatest input return loss [-S21] by tweaking the series SMD trimmer capacitor. After setting the best input return loss [21 dB], I swept this amp.

The XL of the 96 nH air wound coil = 98 Ω and the XL and XC of this tank may be scaled to other frequencies by keeping the reactance values shown or choosing your own. For example; a coil for 50 MHz where XL = 98 Ω = ~312 nH. I discussed and swept the ferrite bead soldered on the FET drain in Section 1 of the VHF Veronica web page.



06:33:43 2014-06-22

Ref -5.00 dBm

Att 15 dB

Marker1 162.55 MHz -5.87 dB

Marker
162.550000 MHz
-5.87 dB

Center Freq 162.55 MHz

Span 325.10 MHz

RBW 3.000 kHz

VBW 3.000 kHz

SWT 36.122 s

Cont Peak On Off

Above — A sweep of the Input Assessment 1 amplifer. Although easy peasy to adjust, series matching the resonator to its input load results in a slipshod right-hand [low-pass] skirt. Click for a screen shot showing the amp's 3 dB bandwidth.


Input Assessment 2
12.2v
51
220 pF
10K
220 pF
G2
G1
4K7
220 pF
D
S
51
220 pF
50 Ω
SMD bead
D
G2
G1
S
BF998
220 pF
50 Ω
96 nH
5.6-11 pF

Above — Input Assessment 2. After measuring a poor low-pass skirt in Input Assessment # 1, I opted for the conventional tapped transformer to steepen the low-pass skirt response versus frequency. My sweeps *did* show a better low-pass skirt shape . Finally, I built a "real" amp and soldered in a broadband output network, tweaked the bias scheme + limited the VDD with a series 150 Ω resistor. A higher value input resonator trimmer cap is required for this amplifier versus that in Input Assessment # 1.



Above — The final 162.55 MHz preamp schematic + some measures. Click for a breadboard photo. Click for the gain measurement with a TG & SA. I measured the same S21 [within 0.3 dB] using my VHF signal generator plus my 50 Ω input DSO. I didn't push too hard with the gate bias or VDD, since neither maximal gain nor parasitic oscillations were sought. Click for a zoom of the filter peak response. Click for a wider sweep to see the right-hand skirt response.

Built on 2-sided FR4 with short cut paths to fit mostly size 0805 SMD parts, I placed via wires on every ground point and detected 0 unwanted oscillations from HF to 3 GHz.

A bare copper wire coil allows us to set the input impedance tap point anywhere along the wire — unlike the *integer only* tap points provided by magnetic toroid-based transformers. In LNA design, many builders set the input tap point for the lowest NF with the amp in noise figure test mode. Another vanilla flavored option is to set the tap with the amplifier input connected to a return loss bridge while adjusting the tap point for the best input return loss — that's what I did. My S11 = - 16.9 dB with my final tap around 1.2 turns of the total 7 links on my 96 nH coil.

The output transformer presents a poor match to 50 Ω with a S22 of just -12 dB. I plan to put a 4 dB pad after it for my NOAA receiver, so it's okay. Some might chase a better output return loss and also perhaps tune the output for better band-pass filtration.

Your FM receiver preamp might need better input filtration, however, if a simple design works, then simple rules! Have fun with *your own* experiments.

473
270
472

QRP SWL HOMEBUILDER

RF — Test and Measurement

Pin Outs

Mini-Circuits Labs SBL-1 and TUF-1 diode ring mixers

...more later


8
6
4
2
MCL
7
5
3
1
MCL SBL-1

Above — Normal set-up: **Ground** -- Pins 2, 5, 6 and 7. **LO** -- Pin 8, **IF** -- Pins 3 and 4, **RF** -- Pin 1


1
2
3
4
M
MCL TUF-1

Above — **RF** -- Pin 1, I**F** -- Pin 2, **Ground** -- Pin 3, **LO** -- Pin 4.

RF — Test and Measurement

VHF-FM Supplement — Amplifiers

Deleted October 26, 2013

Amateur Radio Electronic Design

KL7R Memorial Receiver Experiments

Introduction



This web page is a memorial to Mike Caughran, KL7R, who died suddenly in January 2007. Mike was a passionate experimenter who was embraced by the homebrew radio electronics community. He was best known as the co-creator of and sidekick to Bill Meara, M0HBR on the podcast Solder Smoke. Mike was a hardcore science and technology buff. His knowledge of general science and curiosity about minimalist RF designs was amazing. I worked Mike on 40 and 80 meter CW and later by voice on eQSO. Mike was the first person to refer to this web site as the "popcorn site". He held an interest in digital circuits. In tribute to Mike, a series of receiver experiments which includes some digital circuits are presented. Mike Caughran will be remembered as a remarkable, kind and passionate homebuilder.

Navigation

There are 3 linked web pages associated with this KL7R tribute web page.

1. Mike's personal web page His own web page memorializes him best
2. Supplemental web page Additional schematics and photos which supplement this main web page
3. VFO web page Describes the VFOs used for these experiments

My special thanks to Wes, W7ZOI for his coaching and suggestions to improve many of the circuits on this web page. This web page borrows heavily from his designs as presented in EMRFD.

Receiver Description


Receiver Block Diagram
180 degree splitter
Band-pass
filter
Q
D
Q̄
7 MHz
VFO
Frequency
doubler
BJT driver
D flip-flop
FET bus
switch
Audio
chain

Shown above is the receiver block diagram. The KL7R memorial receiver depicted on this web page is the final output of many hours of experimentation. Most of the circuits or circuit ideas originated in EMRFD.

From our conversations, Mike was always challenging himself; experimenting, testing and pushing his knowledge threshold. The joy of discovery motivated him. Fired by his spirit of inquiry, I explored methods to build a receiver containing at least 1 digital circuit. On many days, I accomplished nothing. The circuits did not work and little to no progress was made. These were the difficult dry spells all experimenters must endure. Design and circuit failures can be very disheartening. I also wasted a lot of parts. However, I kept going and slowly successes occurred and my confidence rose. The end result was a little more knowledge and a cool, popcorn, direct conversion receiver which I hope will provide ideas and inspiration for your own experiments.

Double Tuned Band-pass Filter

Figure 1

40 Meter Band-pass Filter



CV = 6.0 - 50 pF trimmer cap

L1 = L2 = 3.4 uH = 29 t #24 AWG on a T50-6 toroid

Input and output impedance = 50 ohms

-3 dB bandwidth = .220 MHz

Insertion loss = 2.3 dB

Figure 1 shows the front end band-pass filter. If you can't obtain a 3.3 pF coupling capacitor, try this other 7 MHz band-pass filter circuit or perhaps just design your own. See the Webmaster's page for information concerning many of the parts used on this web page.



Shown above is a photograph of the Figure 1 breadboard. The inductors were spaced apart at right angles to reduce unwanted coupling. The copper clad board L-C tank divider is not necessary. The 51 ohm load resistor seen to the right was removed after testing.


GPLA - 2002
S21 =
S11 =
S21 Ref.
Click to Review Circuit
dB
Plot
Enter new value and Click
Place Cursor
Cursor Data =====>
Frequency

0 Load R = 50.0
1 cap par 390.00
2 cap ser 47.00
3 cap par 103.05
4 ind par 3400.00
5 cap ser 3.34
6 ind par 3400.00
7 cap par 103.05
8 cap ser 47.00
9 cap par 390.00
10 rlb ser 0.00
98 Source R = 50.0
99 Inductor Q = 200.0

top 0.
10.00 dB/div.
bottom -60.0
start 5.2 MHz
0.22 Freq./div
stop 9.00
C:\Todds\QRPHB\QRPHB\fall 2009-2010\
N (index) 9
NewValue 390
0 MHz
S21= -- dB
S11= -- dB

Shown above is a GLPA simulation of the Figure 1 band-pass filter. Хорошо.

Product Detector Experiments


updated March 28, 2012
Figure 2
L78L05
Bottom
12.21
16t FT37-43
110 uH
22 uF
.1
.1
22 uF
1K
1,4,10,12,14
T1
2.16
7
8
2.46
20t FT37-43
170 uH
10K
3
Q
5
RF in
50 ohms
2K2
2.46
2
Dual FET Bus Switch
3
.1
47 uF
4K7
2
D
U1
Q̄
6
2K2
22uF
.1
5
U2
6
51
Q1
7,11,13
1
4
2.17
1OE
1A
1B
GND
1
2
3
4
U2
8
7
6
5
VCC
2OE
2B
2A
DC voltages in red
Q1 = 2N3904
U1 = 74HC74
U2 = SN74CBT3306CDR
T1 = 10 trifilar turns FT37-43

Shown above in Figure 2 is the BJT driver, D flip-flop and the CMOS switch product detector. The 14 MHz VFO connects to Q1 via a 0.1 uF coupling capacitor that is shown on the VFO schematic. A dual FET bus switch (CBT3306) serves as the product detector. The on-resistance of this switch is only around 3 ohms! If you are ambitious, you might try using a 14 pin SOIC switch such as the QUAD FET SN74CBT3125DR with 2 pairs of the 4 switches wired in parallel. I tried 3 different CMOS switches in the U2 slot. The other switches were the MAX4066CPD and a 74HC4053 (wired up appropriately using their datasheets). The insertion loss and performance of these 2 switches was disappointing. My bench standard for comparison was a 7 dBm diode ring mixer. Numerous experiments were performed. For example, I tried running the 4066 at 12 volts VCC to minimize its on-resistance and had to modify most of Figure 2 as well. Being new to digital, blending 5 volt and 12 volt logic IC required great effort to get it working properly. These experiments consumed the better part of 2 days. My conclusion was that if you are going to go to the trouble of make a CMOS switch work, you might as well use a part that has a low on-resistance. Hence, I have since abandoned using DIP IC CMOS switches (4053, 4052, 4066 etc.) as mixers and product detectors. They may still be a good choice in your own context.

The CBT3306 is outstanding and very similar to the diode ring mixer with respect to insertion loss and audio quality as a product detector. There are some other good CMOS switches you might try. I chose the CBT3306 because it was SOIC (the largest of the common SMT topologies), costs only 77 cents (Canadian dollars) and only has 8 pins to deal with. Pragmatism on the workbench is always good!

SMT versus VE7BPO

The difficulty with using the CBT3306 was that I had to learn about and equip for SMT. I ordered the switches and after their arrival, hesitated to do anything with them for 5 days. I managed to borrow a magnifier and bought a SOIC prototype board and some flux. Still, I seemed to be paralyzed with fear about soldering U2. I was stuck. For inspiration, I went back to Mike's web site and found this web page. Here Mike was working with a 18 pin SOIC chip and I was worried about a mere 8 pin IC! Part of the problem was my relatively poor eyesight. I learned this can be managed with a magnifying visor. I bought mine here , but only after U2 was soldered in. The borrowed table magnifier was okay, but constrained arm movement and reduced lighting. The visor seems to be a better choice.



Shown above is the CBT3306 soldered on my prototype board. I put flux on the board traces and then tinned them. Following that, I lined up U2s leads on the traces and began soldering. The bottom pins (pins 1-4) did not go well, but they were soldered all the same. Following that, the soldering of pins 5-8 went very well. I was very happy; the SMT monster had been tamed! It was learned from Wes, W7ZOI that many builders use Surfboards for SOIC applications. I will get some for future SMT IC work. Using SMT parts in your Ugly Construction allows you to use parts which are unavailable otherwise. Increasingly, good old DIP ICs are disappearing from catalogs and some new parts are appearing as SMT only. It makes sense to jump in and use SMT parts when it is advantageous for spec reasons, or if miniaturization is required.

With some effort, the Figure 2 circuit could be morphed into Colin, G3SBI's H-mode mixer format. Not on this web site though! If you Google "H-mode mixer" , many good websites will be returned.

The product detector's baseband audio output is at the 47 uF capacitor which connects to Q1 of Figure 3. A simple 51 ohm, low pass network is used to terminate U2. This is from W7EL's An Optimized QRP Transceiver from QST for Aug 1980. I have some more information regarding AF termination circuits on this web page. You may wish to increase the 170 uH inductor value somewhat to get more low pass filtering. The product detector circuit is the number one potential source of hum and noise in this receiver. Take the time to plan your layout to minimize wire length and crossing and provide some physical symmetry. Decouple well.



Shown above is the product detector. At this point, I had not decide how to terminate U2 and had soldered a shunt 0.1 uF cap and 51 ohm resistor to the switch output. U2 is dwarfed by the FT37-43 toroid; a part we normally think of as small in size.


Figure 3
CU306C
77M
ALND G4
Pin 1
8BH9F0K G4
CBT3125
Pin 1
1OE 1 14 VCC
1A 2 13 4OE
1B 3 12 4A
2OE 4 11 4B
2A 5 10 3OE
2B 6 9 3A
GND 7 8 3B

Figure 3. Photographs of the FET bus switches I have in my collection and the pin-out for the 14 pin CBT3125

A diode ring mixer was used as a reference mixer in the product detector experiments.

Audio Amplifier Chain


12.21v
100
12.07
Q2
100K
1N4148
1N4148
11.58
22 uF
+
22 uF
100
10.94
2K2
6K8
22 uF
Figure 4
.30
Q1
2.10
2.76
10K
3K9
+
10 uF
3K3
6.11
3
+
5532a
1
2
−
4
1K
1K
5
+
8
5532b
7
.15
6
−
U1a
U1b
Volume
1 uF
1 uF
500
Ie = .54 mA
1K
22K
Rg1
.1
.0022
Q1 = Q2 = 2N3904
DC voltages in red
750 Hz low-pass filter

Shown in Figure 4 is the audio preamp and first low pass filter. Direct conversion receivers are all about audio. High performance DC receivers have become more common since Rick, KK7B unleashed his R1 on the world in 1992. High performance receivers are out of scope for this popcorn website, however, this design is welcome. The entire audio chain uses low-cost 5532 op amps, cheap BJTs, plus fairly common resistor and capacitor values. Poly"something" capacitors were used for all audio AC coupling and shunting capacitors of 4.7 uF or less.

For hum immunity, the familiar BJT capacitive multiplier popularized by Roy, W7EL was used at Q2. Using a high-end spectrum analyzer, Wes, W7ZOI demonstrated that this circuit can oscillate. He detected oscillations at UHF. Thus, Wes recommended using a 100 ohm snubber resistor on the Q2 collector to alleviate these parasitic oscillations. Additionally, 2 diodes were added in parallel to the 100K base resistor. This provides an instant-on feature for the audio preamp, as normally there is a time-constant delay when you switch on the receiver. I like this feature, but it is purely optional.

Q1 is a common base amp biased for 0.54 mA. Therefore, the input impedance is 26/0.54 or about 48 ohms. The 6K8 + 2K2 collector resistors were paralleled so that the quiescent collector voltage was close to 6.1 volts. You could also substitute a single 9K1 resistor, although this is an uncommon value. This voltage provides the approximate VCC/2 bias needed for U1a and U1b. Connecting the Q1 collector directly to the pin 3 op-amp input allows the exclusion of a coupling capacitor and the usual VCC/2 resistor network used to bias the 5532 op-amp from a single power supply. I borrowed this from EMRFD.

The gain of U1 is set by the resistor labeled Rg1. If after testing, the AF gain is too high (for example if this AF stage was used in a superheterodyne receiver), simply lower this resistor value. I chose a 22K ohm resistor to allow enough gain for weak signal listening. On louder stations, you will need to lower the volume control to prevent distortion in the stages that follow as overall, there is a lot of gain in this AF chain. Adjust the Rg1 value to suit your needs. If you use a switch such as a 4052 for U2, or your receive antenna is small, you may want to increase this resistor a little for more gain. This is an experimenter's receiver after all. The 0.0022 uF capacitor in the op-amp feedback loop provides a single pole of low pass filtering. I ran this capacitor as high as 0.0082 uF. This gave a theoretical 3 dB cutoff frequency of ~ 880 Hz, but the receiver lost its sizzle. Experimentally, I learned that using a 0.0022 uF feedback capacitor on both U1A and U2A dropped some of the high frequency noise while preserving some sparkle in the received audio.

The audio preamp chain is concluded with a 750 Hz low-pass filter. Resistor values were kept low to minimize noise. All the active low pass filters are low Q, Sallen-Key designs with a Butterworth response. They are stable, easily scalable and brain-dead simple. These filters are fatigueless due to their gentle cut off slope. I actually had a 0.30 uF capacitor in my parts collection, although it was a 600 volt rated part from my tube amp parts bag. You could use two 0.15 uF capacitor in parallel or just substitute a 0.33 uF capacitor. If you can't find a 500 ohm volume control potentiometer, swap in whatever you have, but try to keep the resistance low.



In Figure 5, the remaining preamplifier stage and low-pass filters are shown. Rg2 was chosen for the same reason as Rg1 in Figure 4. Please experiment with these values. The low pass filter stages are scaled up by a factor of 10 as resistance values are less critical at this point in the audio chain. You could use the same resistor and capacitor values used in the first low-pass filter or use the Figure 5 values for all of the low-pass filters. Very often, our parts collections dictate how we experimenters design and build circuits.

Figure 6


12.21
100
10
470 uF
DC voltages in red
.001
33 uF
100 uF
2N3904
from low-pass filters
5
8
7
7.33v
5532b
6
4
2K7
5.03v
1K
22 uF
U3b
4K7
4.7 uF
2.30v
1.28v
1
1
470 uF
5.65v
6K8
1
1
100K
8 Ω
390 pF
2N3906
10
.1
Max sine wave power 305 mW

Figure 6 is the power amplifier schematic. Apart from field portable transceivers where headphones are used to save battery power, I exclusively listen to my receivers via a loudspeaker. This safely allows the exclusion of AGC circuits. You may have noticed that AGC circuits have not been presented on this web site. I rarely use them. The extensive VCC decoupling in Figure 6 is needed in this high gain AF chain. The 1 ohm emitter resistors in the finals invite instability, but were tamed with the 10 ohm / 0.1 uF low pass filter. My original design called for 2.2 ohm emitter resistors, but none were available. This final amplifier is moderately loud and very quiet. When it was first built (the AF chain was built backwards), you could not tell it was on when no signal was applied. With no antenna connected to this receiver and the volume on full, there is only a little noise. This is a good way to test a receiver AF chain for noise. Speaker choice is also important. Speakers of a greater power rating and size sound better; especially when mounted in a wooden cabinet.

Biasing power amps has been discussed extensively on this web site. Ensure you measure and record your quiescent DC voltages as shown in Figure 6. If you hear cross over distortion or the quiescent voltage between the bases of the paralleled final transistors is less than 1.25 volts, try decreasing the 6K8 resistor to 5K6 ohms.



The final preamp breadboard is shown above. You can tell by all the grunge and the solder marks, that many different configurations were trialed. Despite looking haggard, the AF chain is quiet and does not hum nor detect broadcast radio.

Shown above is an early breadboard of Figure 6. In this version, the volume control was at the input and a voltage divider network was wired to pin 5 to provide VCC/2 bias. Testing with an audio signal generator, a tape player and other sources were performed. Later, the biasing resistors and the potentiometer were removed and the Figure 5 stage was added to the copper clad board and tested.

Final Thoughts

We are remembered best by those whom we affect. Certainly Mike's unique perspective and enthusiasm inspired me to dig deeper into this hobby. I asked Bill, M0HBR, for a quote to conclude this web page. Bill wrote this: "Just last week somebody was asking me for background info on Mike's DSB modification of the Heath HW-8... I think it is a real tribute to Mike that years after his passing, hams around the world are still talking about him fondly, still visiting his web site, still following his lead on homebrew radio projects. Certainly among the 3,000 + listeners of the SolderSmoke podcast, Mike is present in spirit every time a soldering iron is heated up." Thank you Bill.

My heartfelt regards to Mike's family.

QRP SWL HOMEBUILDER

Amateur and Short Wave Radio Electronics Experimenter's Web Site

VFO Experiments 2009

Amateur and Short Wave Radio Electronics Experimenter's Web Site

Supplement to the VFO 2009 Web Page

This web page is a supplement to the VFO 2009 Web Page

Figure 10 Bipolar Transistor Notes



This circuit is from EMRFD and is an analog to digital interface for the VFO. I did not understand the circuit, so I asked Wes, W7ZOI to explain his design criteria and the basic circuit function. This transistor circuit is a driver. The purpose of this transistor driver is to positive edge trigger a D flip-flop. The paramount criterion was that the transistor collector has a quiescent bias voltage that fell between the minimal acceptable logic high and logic low DC voltages on the 74HC74 clock input. See this chart for details about this topic. The correct DC collector voltage is set via feedback from a voltage divider (in this case, a 10K and 4K7 resistor). The collector DC voltage (shown above in Figure 1A) was 2.36 and lies perfectly between the logic low and high state of the 74HC device that it drives.

This transistor circuit is also a high gain amplifier, however, its primary function is a driver. Refer to figure 1B. When connected to the VFO output, the base voltage drops to 0.30 volts. This is an average DC voltage because it fluctuates as the AC waveform swings up and down. More or less AC drive on the input will change this DC voltage.
When connected to the VFO output, the collector voltage dropped to 0.71 VDC. Again, this is just an average, as when the AC swings positive, the the collector voltage will drop down to saturation (where collector voltage is less than base voltage) and then increase towards the positive supply. It does not have to go into cutoff; just to 3.2 volts or so. It also does not have to go into saturation; just to below the 1.3 volts or so. Thus, the transistor remains between cutoff and saturation when appropriately driven with a sine wave.

Our VFO serves as the clock and data on the D flip-flop inputs are only transferred to the flip-flop's outputs on the positive edge of a clock pulse. Positive edge triggering means that the output only responds to the input changes when the clock signal transitions from logic low to logic high. What a fantastic little circuit! You can find additional information and some practical examples in EMRFD. My special thanks to Wes, W7ZOI for helping me to better understand his design.

Positive Edge Triggering


Leading or
positive edge
Trailing or
negative edge

The triggering of a positive edge triggered flip flop is better understood viewing a graphic like above. The instant the waveform goes positive, the flip flop is triggered. It is easy to understand why a square wave is desirable for clean triggering.



QRP SWL HOMEBUILDER

Amateur and Short Wave Radio Electronics Experimenter's Web Site

RF — Test and Measurement

Radio Amateurs of Canada Support Page

Commentary for Canadian Radio Amateurs

A significant number of licensed Canadian amateur radio operators do not support their national amateur radio society: Radio Amateurs of Canada Typically support is by membership, but may also include volunteering time to perform the various functions required to run a large, non-profit organization. It has been demonstrated repeatedly, that a small percentage of people are doing most of the work in modern volunteer organizations.

Some thoughts concerning volunteerism

- Volunteerism is down in many sectors including service clubs, meal delivery programs, church groups, volunteer firefighters radio clubs, etc. etc.
- The population is aging and our current volunteers are retiring; Younger folks have so many distractions and things they can do today. We now live in a world with 200 plus TV channels! The spirit of volunteerism seems to be decreasing in the western world.
- There is some evidence that people who donate their cash to charities also tend to participate in groups, associations and organizations. Is this a characteristic or trait?
- People volunteer for causes they believe in. What do people believe in now? Is our culture too self-absorbed, individualistic and focused on our own personal agendas and pleasure?
- Economics. Are young to middle aged people less able to volunteer and contribute because they are spending more of their time working?

RAC Membership

If you haven't, please consider joining the RAC. I joined out of respect to the many RAC volunteers who have devoted their personal time and continue to toil to keep amateur radio viable in Canada. We cannot take our currently allocated radio frequency bands for granted. There are groups who for profit, want to apply technologies which will consume or interfere with the radio frequency bands we enjoy. Canadian amateur radio needs a strong, united voice to survive into the future.
Apathy and lack of awareness may significantly decrease the rights and privileges we enjoy as radio amateurs today. The least we can do is support our national amateur radio society. It would be even better if more of us contributed by volunteering our personal time towards our wonderful radio hobby and serving the RAC.



The RAC Journal The Canadian Amateur is an excellent resource. Sept-Oct 2009 marked the first ever antenna issue.

Old QRPHB Web site graphics...


Junk Box Blog



QRP
HOME BUILDER


QRP
SWL
HOME BUILDER

QRP
Home Builder




L1
C1
QRP
Homebuilder Homepage
C2
L2


VE7BPO's
junk box



This page last updated: September 21, 2013

RF — Test and Measurement

Info on the Popcorn Superhet RF Amp

Discussion



I have received a lot of emails regarding this RF amp from the popcorn superhet receiver. This amp was designed using a calculator and as it turns out, my input and output impedance was off by several ohms from the target 50 ohms input Z and 200 ohms output Z. Today we have computer programs to calculate the resistor values, so crunching the math is not a factor any more. This RF amp is preceded by a 50 ohm diplexer and followed by a 200 ohm pad, so it actually matches the preceding and following stages very well considering that it is clearly depicted to be a popcorn receiver. If I had to redesign this amp in 2008, I would use software to design a CE amp using "noiseless" Norton feedback, Still, this was a good sounding receiver at the time.
Probably the weakest section of this receiver is the audio preamp from Q5 on through to the LM386. I would likely never use these noisy stages in 2008-9. Instead I would use low noise op amps. This web site like my own abilities has grown over time. In the following section, I have paraphrased some writing from Wes, W7ZOI concerning the Q2 RF amp.

An Analysis by W7ZOI

The input impedance of a common emitter bipolar transistor amplifier is related to the standing current, the emitter degeneration resistance, the transistor beta, the F-t, and the operating frequency. Most of those details can be well modeled with the hybrid pi model. If you put quite a bit of emitter degeneration in such an amplifier, the gain drops while the input impedance increases. However, it is much less dependent upon beta and frequency. The emitter degeneration is one form of negative feedback. But now we introduce a second form of negative feedback by applying some of the collector voltage to a resistor that generates a current that is fed back to the base. This feedback tends to reduce gain just as does emitter degeneration. But it also tends to reduce input impedance. By playing a careful balancing act, you can design an amplifier that has a 50 Ohm input and output impedance with a reasonable amount of gain. This particular circuit has a gain of 21.7 dB at 10 MHz and an input return loss of 14 dB. The output return loss is even better at 18.6 dB. Z-in is 39-j14 while Z-out is 172-j34.

These are calculated values using that hybrid pi model. I have devoted a few pages to a discussion of this feedback amplifier topology in the ARRL 2003 book, Experimental Methods in RF Design. This was co-authored by KK7B and W7PUA. You can get the book on line from the ARRL. The book includes computer programs that will handle the design chores. One deals with bias issues while another does the RF design and analysis.

The RF amplifier under discussion may be found on this web page



Amateur and Short Wave Radio Electronics Experimenter's Web Site

3 MHz VFO for 40M Popcorn Superhet Receivers



Discussion

This VFO was first popularized by Roy Lewallen, W7EL and has been used in countless homebrew and commercially sold QRP rigs. For the 40 meter ugly super hets, you have a choice of a VFO frequency of 3 MHz or 11 MHz and I chose the former for this website. For L1, you can use the T68-6 as shown or redesign your own inductor using a T50-6 core. The T68-6 core allows the builder to wind the coil using # 24 AWG wire for enhanced Q and stability. The main tuning capacitor, C1 that was used had a built in reduction drive and went from 4 - 19 pF. If you use a tuning capacitor with a greater capacitance swing, you may have to connect it to the top of L1 via a small-value NP0 capacitor to reduce the tuning frequency range. This can be done using math or by just plain experimentation. C2 is a small ceramic air-variable trimmer from my junk box used to set the lower band edge of the VFO. It can be omitted if the user wants to go frugal and experimentally set the lowest frequency of the VFO using small-value ceramic NP0 caps. Air variable caps for C1 and C2 are mandatory for minimal drift VFO operation. C3 actually refers to 4 NP0 ceramic caps which were used to place the VFO on the correct frequency. Four caps were used to minimize heating and thus drift in the VFO. For the prototype VFO which tunes something ~ 3.00 to 3.67 MHz , I used the mentioned air-variable, four NP0 ceramic caps (20pF,100pF,5pF,100pF) and C2 the trimmer cap that went from 2 - 50 pF. These values should be used only as a guide for prospective builders as there are many variables at play. Following a 10 minute warm up period, the VF0 frequency stability is excellent. Again, keeps all component leads as short as possible. T1 is a broadband transformer wound by using 20 turns of # 26 AWG over a FT37-43 toroid core and then distributing 5 secondary turns spaced evenly over the primary windings. Do not omit the 33 ohm load resistor. The 2.7 to 3.0 pF coupling cap should also be of the NP0 ceramic type. Q1 can be the J310 (my favorite) , 2N4416 , MPF102 or other correct substitutes.

This VFO should be in a separate sealed, shielded box from the rest of the receiver

.

VFO Stability Hints

Numerous tips for enhancing VFO stability have been generated from Wes Hayward, W7ZOI, Roy Lewallen, W7EL, Doug DeMaw, W1FB and others. Here are a few summarized:

1. Use air wound or powdered-iron toroidal inductors made from number 6 material.
2. Use the heaviest gauge of wire possible to wind your inductor.
3. Anneal the inductor by boiling it in water for around 5 minutes after winding.
4. Use ugly construction above a SINGLE-SIDED copper side up ground plane.

5. Capacitors in the L-C circuit should be NP0 ceramic type.
6. Use air variable capacitors for tuning that have double bearings and no backlash.
7. The VFO should be operated at a lower regulated voltage.
8. Do not use cheap low-Q trimmer caps.
9. Completely encase the VFO to prevent RF leakage and to minimize environmental temperature changes.

Amateur and Short Wave Radio Electronics Experimenter's Web Site

4 MHz BFO for 40M Popcorn Superhet Receivers


4 MHz BFO

Q1, Q2 2N3904

D1 9.1 volt 400 mW Zener Diode

L1 19.8uH, XL = 498 ohms T68-2 Toroid 59t Primary 12t secondary

Discussion

Shown is a 2 stage BFO for use with the Ugly 40 meter superhets with a 4.00 MHz IF. This is a design by W7ZOI which I have used from 3.5 to 9 MHz by only changing the crystal and the Q2 output coil and capacitor values to suit the frequency of choice. The output coil is 59 primary and 12 secondary windings on a T68-2 toroid core. You will need in the order of 79 pF to resonate this coil, thus a 68 pF plus a 5-20 pF variable works well. If you do not have a T68-2 core, a T50-2 could be used with 30 AWG wire which is a bit difficult so you could opt for an XL of 200 ohms which would be 40 primary and 8 secondary turns on a T50-2 core. You would need ~200 pF to resonate such a coil and the BFO would have reduced output power, but would still work okay. If you design your own tank, you probably should not use an XL/XC less than 190 ohms for the output stage at 4 MHz. Use a 5:1 turns ratio for primary to secondary windings.


3 Element Low Pass Filter

It wouldn't hurt to follow the Popcorn Superhet BFO with a low pass filter. A simple pi-type 3 element filter is suitable. Since I had a couple of 470 pF caps left over, I made a low pass filter using a 6.8 MHz cutoff frequency with a 1.17 uH inductor. A 1.17 uH inductor using a T37-2 core requires 17 turns while on a T50-2 core requires 15 turns. Caps were inexpensive monolithic ceramics from Digi-Key. The filter is shown below, L1 = 1.17uH , C1 and C2 = 470 pF. If you want, you may use other cutoff frequencies to suit any junk box caps you have on hand and use an XL/XC of 50 ohms.

Construction

Keep component leads as short as possible to promote stability. Do not omit the zener diode D1. I thought of using a small ferrite bead on the base of Q2 and will try it on the next version of this BFO that I make. The BFO, if unstable can break into all sorts of weird AF sound effects that are very annoying. The BFO should ideally be in a shielded box, but many amateurs have good results by just placing the BFO strategically in the receiver chassis. When winding L1, make sure you wind the secondary coil so that the secondary's grounded end is on the cold side of the primary coil that connects to the 100 ohm resistor and positive voltage. I just pick one end of the primary coil and close wind the secondary coil from this point in the same direction for the correct number of windings. Then the starting point of the secondary can be grounded and the other end connected to the detector or a low pass filter. After building the coil, temporarily place a 51 ohm resistor from the secondary output lead to ground. Then you can test and peak the tuning of the output tank into a load. Leave the resistor in place for all your testing work such as crystal matching or RF stage testing until you are ready to connect it to the product detector. The 60 pF variable cap connected between the crystal and ground is used to set the beat frequency of the BFO. Adjust it to get a good sounding beat note when listening to a station. You will notice that the beat frequency can be tuned roughly by just listening to 40 meter band noise in the headphones and then tweaked on an active QSO.

QRPHB Archive Schematics


UGLIER SISTER 40M SUPERHET
+ 13.8 VDC
100
Ferrite Beads
8K2
.1
L1
10pF
L2
100pF
20pF
20pF
2K2
.1
.1
Bandpass Filter
RFC 22 uH
51
RF Amp
LO input
DBM1
Mixer
.1
800 pF
1.99 uH
51
51
800 pF
1.99 uH
Diplexer
+ 13.8 VDC
100
2K7
.1
L3
.1
390
.1
Q2
.1
Heat Sink
560
39
5.6
.1
IF Preamp
150
600
-6dB Pad
(200 ohm)
1N4148
Diode Limiter
+13 dBm
300 pF
300 pF
300 pF
4.00 MHz IF Crystal Filter
Q1, Q2, Q3 2N3866 , 2N5109 etc
T1 See text
T2, T3 10 bifilar turns #28 AWG FT37-43 toroid
L3 18 turns #26 AWG on a FT37-43 toroid
T2
.1
+ 13.8 VDC
100
T3
.1
.1
2K7
.1
390
Q3
Heat Sink
560
39
5.6
.1
IF Amp

<\p>


UGLIER SISTER 40M SUPERHET
22uF
220
+ 13.8 VDC
.1
100K
Q4
22 uF
.01
3K3
1K
22uF
22
22uF
BFO input
-3 dB Pad
50 ohms
18
300
DBM2
Detector
Diplexer
2.7 mH
1 uF
51
10K
100K
10uF
Q5
2K2
22K
.1
10uF
Q6
Q7
10K
+ 13.8 VDC
to mute
AF Preamp
Chain
100K
4K7
10uF
3K3
10K
470
Q8
1uF
.047
10uF
10K
Pot
AF Amp
LM380N
68K
1K2
.22
10K
.01
2
6
14
8
1
3,4,5,7,
10,11,12
10uF
470uF/35v
4.7
1K
.1
Headphones
Speaker
100 uF
.1
10
1/2 watt resistor
+ 13.8 VDC

drawn Dec 3, 1998

Caps in diplexer non-polar

<\p>

Uglier Sister Superhet Receiver

This is a 40 M superhet that I built a few years ago. While I was happy with this receiver, it has been discontinued from the main listings on the QRPHB website. I have had a couple requests for this schematic, so I have created this archival web page.
I stood a lot of current in the IF preamp and main IF amplifiers, which is not really necessary, particularly in the case of the post-filter amp. Of course raising the emitter resistor values is easy to do in these amps if you do wish to lower the current. There also is no audio filtering in the AF preamp stages, which is something that I often use in better quality receivers that I build now.

VFO and BFO

VFO schematic
BFO schematic

Construction Information

Refer to this web page for details on the xtal filter, diplexer and construction information.

The Norton RF preamp is discussed on the RF Preamp web page.

Return to the QRP HomeBuilder Homepage

Amateur and Short Wave Radio Electronics Experimenter's Web Site

Diplexer Supplemental Page

More Information on the Bridge-Tee Diplexer

Introduction

No web page on the QRPHB web site has furnished more email and controversy than the Diplexer Web page. This page has received much work to improve its content and accuracy and the email received has been greatly appreciated. Presented is the detailed math and some information regarding the Bridge-Tee Diplexer by Helmut Strickner, VK4STR and Wes Hayward, W7ZOI.

VK4STR

The T-bridge diplexer math calculation (also known as the W1JR diplexer)

The formulae presented and used in the program for the Bridge-T Diplexer uses a Q of 1. Using a Q = 1 resonator is not optimal because we don't want a "broad peaking response" of the series LC resonator in the T-bridge diplexer. Our goal should be to only let the desired IF frequency pass and attenuate all other frequencies as much as possible by properly terminating them into 50 Ohms in the diplexer.

The optimal Q for HF frequencies is around 10, less for higher frequencies. The higher Q of the series resonator effectively increases the attenuation of undesired harmonic frequency components from the mixer IF-port, and the reflected products from the crystal back to the IF-port. The IM performance (IP3) of the receiver is improved.

The possible improvement in IP3 depends mainly on the following stages. The post-mixer amplifier following the diplexer has to handle huge impedance variations at the input of the crystal filter. Crystals do not absorb but reflect any products they cannot handle. These products are then reflected back to the IF-port of the mixer deteriorating the IM performance.

A low Q diplexer lets these reflections from the crystal pass unhindered and most mixers will react with degraded intermodulation performance. It is also important to note that a good termination insensitive post-mixer amplifier should follow the diplexer.

The best results for a high intercept (IP3) receiver can be obtained by choosing:

1. High level mixer
2. T-bridge diplexer with optimised Q (Q=10 for HF)
3. Termination insensitive post-mixer amplifier (see N6NWP - QEX July 1995)

I believe that the intermodulation performance of many receivers can be improved by some simple measures like a properly designed diplexer. The T-bridge diplexer from W1JR is the best one around, go for it.

A brief example of the calculation for a 10.7MHz diplexer follows in Figure 1. The value of K should be 10 for short wave and 2 to 4 for VHF (2 meter band). K is the ratio of L to C.

I hope that you can use this example to calculate the values for other diplexer frequencies.

To fully understand the basis of this calculation please refer to Meinke/Grundlach: "Taschenbuch der Hochfrequenztechnik", Springer-

Verlag Berlin/Heidelberg. Page 127.



$$K = \frac{1}{Z} \cdot \sqrt{\frac{L}{c}} \quad (K = 10) \qquad \omega_r = 67\,196\,000$$

$$L_1 = \frac{K \cdot Z}{\omega_r} = \frac{10 \cdot 50}{2 \cdot 3{,}14 \cdot 10{,}7 \cdot 10^6} = $$
$$= 7{,}44 \cdot 10^{-6} \approx 7{,}5\ \mu H$$

$$C_1 = \frac{1}{\omega^2 \cdot L_1} = \frac{1}{(2 \cdot 3{,}14 \cdot 10{,}7 \cdot 10^6)^2 \cdot 7{,}44 \cdot 10^{-6}} = $$
$$= 29{,}7 \cdot 10^{-12} \approx 30\ pf$$

$$L_2 = C_1 \cdot Z^2 = 29{,}7 \cdot 10^{-12} \cdot 50^2 = $$
$$= 7{,}42 \cdot 10^{-8} \approx 74\ nH$$

$$C_2 = \frac{L_1}{Z^2} = \frac{7{,}44 \cdot 10^{-6}}{50^2} = $$
$$= 2{,}97 \cdot 10^{-9} \approx 3\ nF$$

Figure 1

73!
Helmut VK4STR

W7ZOI

Attached are some outputs from Mathcad, Version 7.0. The "proper" equations are derived, along with some other results. Feel free to put these on the web, although this is mathematics rather than the usual "formulas" and there might not be any interest in such stuff.

As it turns out, the formula that Todd presented in completely accurate for the case of Q=1. That is, both the series and parallel tuned circuits have inductors and capacitors with reactance of 50 Ohms. Evaluation then shows that S11=0 for all frequency, while S21 peaks broadly at the resonant frequency. If you pick a higher Q, the inductor in the series tuned circuit increases by Q and the capacitor in the parallel one increases by Q. Resonance is maintained in both. Again, you then get a perfect match at all frequencies and a S21 peak at resonance. But I don't know if this is what Joe had in his original work.



Shown is a general bridge T type network with series impedance S and parallel impedance P. We wish to find the input impedance seen by the generator. But to do this, we need to know the input current. The input voltage is set at 1, so Zin=1/Iin. To calculate this, we must know E and V. These are obtained with a nodal analysis.

We write the nodal equation at E :

$$\frac{(1-E)}{R}=\frac{E}{P}+\frac{(E-V)}{R}$$

We solve this for E:

$$\frac{(1-E)}{R}=\frac{E}{P}+\frac{(E-V)}{R} \text{ solve}, E \rightarrow \frac{-\left(\frac{1}{R}+\frac{1}{R}\cdot V\right)}{\left(\frac{-2}{R}-\frac{1}{P}\right)}$$

We now write the equation at V and solve it for E:

$$\frac{(1-V)}{S}+\frac{(E-V)}{R}=\frac{V}{R} \text{ solve}, E \rightarrow -\left(\frac{1}{S}-\frac{1}{S}\cdot V-\frac{2}{R}\cdot V\right)\cdot R$$

We now equate the two expressions for E to each other and solve that for V.

$$-\left(\frac{1}{S}-\frac{1}{S}\cdot V-\frac{2}{R}\cdot V\right)\cdot R=\frac{-\left(\frac{1}{R}+\frac{1}{R}\cdot V\right)}{\left(\frac{-2}{R}-\frac{1}{P}\right)} \text{ solve}, V \rightarrow \frac{-\left[\frac{-R}{S}+\frac{1}{\left[\left(\frac{-2}{R}-\frac{1}{P}\right)\cdot R\right]}\right]}{\left[\frac{R}{S}+2+\frac{1}{\left[\left(\frac{-2}{R}-\frac{1}{P}\right)\cdot R\right]}\right]}$$

which simplifies to $V = \dfrac{\left(2\cdot R\cdot P+R^2+P\cdot S\right)}{\left(2\cdot R\cdot P+R^2+3\cdot P\cdot S+2\cdot S\cdot R\right)}$

We now take one of the expressions for E and put V in it to obtain a complete solution.

$$E = 2\cdot P\cdot\frac{(R+S)}{\left(2\cdot R\cdot P+R^2+3\cdot P\cdot S+2\cdot S\cdot R\right)}$$

The next chore is to evaluate the input impedance, Zin. We get this by calculating the input current. The input voltage is set at 1, so Zin=1/ i-in.

$i \text{ in} = \dfrac{(1-V)}{S}+\dfrac{(1-E)}{R}$ So $Z = \dfrac{1}{\left[\frac{(1-V)}{S}+\frac{(1-E)}{R}\right]}$

which simplifies to $Z \text{ in} = \dfrac{-1}{(-R+R\cdot V-S+S\cdot E)}\cdot S\cdot R$

But to get a meaningful expression, we must sub V and E into this. When we do so, we get

Figure 2

$$Z\text{ in} = \frac{\left(2\cdot R\cdot P + R^2 + 3\cdot P\cdot S + 2\cdot S\cdot R\right)}{\left(2\cdot R\cdot P + 3\cdot R^2 + P\cdot S + 2\cdot S\cdot R\right)}\cdot R$$

This is now a useful result. We can, for example, let S, P, and R be resistor values. We can then design bridge T attenuators. But let's continue with the analysis. Let's ask the question "What are the conditions that will provide an input impedance of R?" We merely set the Zin expression equal to R, and then solve that equation for S or P. We will solve for P.

$$\frac{\left(2\cdot R\cdot P + R^2 + 3\cdot P\cdot S + 2\cdot S\cdot R\right)}{\left(2\cdot R\cdot P + 3\cdot R^2 + P\cdot S + 2\cdot S\cdot R\right)}\cdot R = R \text{ solve}, P \rightarrow \frac{R^2}{S}$$

Hey, that's a cool result, and it's even rather simple. This is an expression for P in terms of S. If we use it for attenuators, it says that our pad is matched with these conditions. We can combine these results with the equation for V to get the attenuation. A couple of interesting matched pads are shown:



Figure 3

The expression for V was $\frac{\left(2\cdot R\cdot P + R^2 + P\cdot S\right)}{\left(2\cdot R\cdot P + R^2 + 3\cdot P\cdot S + 2\cdot S\cdot R\right)}$ But the conditions for a match were

$P = \frac{R^2}{S}$ So, we put this in for P.

$$\frac{\left(2\cdot R\cdot P + R^2 + P\cdot S\right)}{\left(2\cdot R\cdot P + R^2 + 3\cdot P\cdot S + 2\cdot S\cdot R\right)} \text{ substitute}, P = \frac{R^2}{S} \rightarrow \frac{\left(2\cdot\frac{R^3}{S} + 2\cdot R^2\right)}{\left(2\cdot\frac{R^3}{S} + 4\cdot R^2 + 2\cdot S\cdot R\right)}$$

which simplifies to $V = \frac{R}{(R + S)}$ So the two pads have voltage outputs of 0.5 and 0.333 and the resulting attenuations are 6 and 9.54 dB.

But enough about the attenuators. Let's get back to the original question, that of the diplexer. The circuit of interest is one where the series network is a series tuned circuit while the parallel one is a parallel tuned circuit. But we want to know the conditions that will generate a perfect match. With such a circuit, it is clear that a match will exist at resonance so long as both circuits are resonant at the same frequency. The impedance of the series tuned circuit goes to zero while that of the parallel TC becomes infinite (neglecting loss.)



We write the susceptance (imaginary part of admittance) directly for the parallel tuned circuit as

$$B_p = \omega \cdot C_p - \frac{1}{\omega \cdot L_p}$$

But the reactance is the recipricol of this, $\frac{1}{\left(\omega \cdot C_p - \frac{1}{\omega \cdot L_p}\right)}$

which simplifies to become $\frac{1}{\left(\omega^2 \cdot L_p \cdot C_p - 1\right)} \cdot \omega \cdot L_p$

We know that this is resonant at the same frequency as the series tuned circuit with L and C. So, $L \cdot C = L_p \cdot C_p$ and $L_p = \frac{L \cdot C}{C_p}$ We substitute these in the above expression:

$$X_p = \frac{1}{\left[\omega^2 \cdot (L \cdot C) - 1\right]} \cdot \omega \cdot \frac{L \cdot C}{C_p}$$

But earlier analysis showed us that this reactance was related to the series reactance:

$P = \frac{R^2}{S}$ with S = $\omega \cdot L - \frac{1}{\omega \cdot C}$ This lets us set up an equation that is then solved for Cp.

$$\frac{1}{\left[\omega^2 \cdot (L \cdot C) - 1\right]} \cdot \omega \cdot \frac{L \cdot C}{C_p} = \frac{R^2}{\left(\omega \cdot L - \frac{1}{\omega \cdot C}\right)} \text{ solve}, C_p \rightarrow \frac{L}{R^2}$$

This is a particularly simple, yet useful result

1) Pick a crossover frequency f, Hz. Then, $\omega = 2 \cdot \pi \cdot f$

2) Pick a series inductor L. Use one with a reactance of around 50 Ohms if you want a very broad response. Make it larger for narrower bandwidth.

3) Resonate the series L with a cap, $C = \frac{1}{\omega^2 \cdot L}$

4) Pick a parallel cap $C_p = \frac{L}{R^2}$

5) Resonate that cap with a parallel inductor $L_p = \frac{1}{\omega^2 \cdot C_p}$

Figure 4

This web page is copyrighted 1998-2005

Amateur and Short Wave Radio Electronics Experimenter's Web Site

Astable Multivibrator Projects

Discussion:

Astable or free-running multivibrators have been used in home-built amateur radio equipment for many years. The basic circuit is a two stage amplifier with AC-coupled feedback from output to input. One transistor stage is on (conducting current) while the other is off (not conducting current) until the stages switch conducting states repeatedly at a specific frequency. The oscillation frequency is set by the resistor and capacitor values connected to the base terminal of each stage. This RC network determines how long the transistor stays in the off position.

Presented are two projects which utilize astable multivibrators built using the ubiquitous 2N3904 BJT. The first project is a code practice audio-frequency oscillator while the second is a simple , no-frills electronic keyer for keying a transmitter. Either circuit would be a great first project to learn how to build circuits using Ugly Construction.

Code Practice Oscillator


Astable Multivibrator Code Practice Oscillator
VCC
10
22uF
0.1
10K
100K
10K
.01
.01
Q1
Q2
Q3
1N4148
1N4148
KEY
2K7
10uF
100K
4K7
1K
22uF
Q4
10K
470
10uF
22uF
10K Pot
10uF
22K
27K
Q5
47 uF
180
Phones
drawn Jan 24/99
All transistors 2N3904
All caps in microfarads

Above is the schematic for a simple Morse code practice oscillator. This circuit was originally built with 2N3904 transistors, however many different NPN transistors could be substituted as required.

Tracing the circuit from left to right first brings us to the multivibrator circuit which is composed of Q1 and Q2. The oscillation frequency of the multivibrator is ~ 700 hertz and is set by the RC network formed by the 100K resistor and the 0.01 uF capacitor connected to each transistor base terminal. The approximate time off for each transistor is given by the following formula:

[Time 0ff = 0.7 * R * C] with R in ohms and C in farads.

It maybe more practical to leave the resistance value fixed and vary the capacitor value to obtain a desired oscillation frequency. Rearranging the above formula allows this :

[Total Time Off = 1 / Frequency] with Total Time Off being the total number of seconds that both transistors are off and Frequency is in hertz.

Once the total time off is known, you must divide that answer by 2 as each transistor is off half of the total time off in this symmetrical circuit. Then you simply solve for the capacitor value:

[Time Half = Total Time Off / 2]
[Capacitor = Time Half / (0.7 * R)] with Capacitor answer in farads.

Lets run the numbers to solve for the capacitor values in the schematic;
R = 100K, desired frequency = 700 hertz.
Total Time Off = 1 / F ----> 1 / 700 = 0.00143 seconds.
Time Half = Total Time Off / 2 ----> 0.00143 / 2 = 0.00071 seconds.
Capacitor = Time Half / (0.7 * R) ----> 0.00071 / (0.7 * 100000) = 0.0000001 farads = 0.01 microfarads.

For 600 hertz, the capacitors would be 0.012 uF and for 400 hertz, 0.018 uF.

As you can see it is maybe necessary to adjust the base resistor value to achieve a specific oscillation frequency. The rule of thumb is that the base resistor should be ~ten times the value of the collector resistor assuming the base-bias resistor is connected to VCC as shown.

The output of the multivibrator is buffered by the high input impedance of an emitter follower Q3. This serves to prevent the oscillation frequency from changing when the output load is changed. The AF stage connected to the emitter-follower is a standard high gain common-emitter amp that has been used in many of the projects on this web site. As the multivibrator is buffered by 2 amplifier stages, good frequency stability is realized and frequency changes are negligible when turning the volume control pot. The final stage is a common-collector amplifier which can drive low impedance headphones with reasonable volume.

Code Practice Oscillator Project Notes

The voltage / time output waveform of the astable multivibrator is largely a square wave which some people find harsh. Many users prefer listening to a sine wave although that is beyond the scope of this web page. The multivibrator shown has real advantages in that, it is both dependable and tolerant with respect to parts substitutions. Keying the oscillator as shown practically guarantees that the multivibrator will start running each time you hit the key.

VCC can be 9 to 13.8 volts DC and the larger the voltage the greater the volume in the headphones. The B+ decoupling circuit at the top left can be omitted for battery operation or if you prefer not to bother with it. The basic multivibrator and emitter-follower circuit can be used in a transceiver as a sidetone for monitoring keying. A series resistor from the emitter-follower maybe necessary to attenuate/match the sidetone to the transceiver's AF amp.

If you desire speaker level output, the Q5 common-collector final can be omitted and the circuit shown below used. This circuit uses the LM386N and provides up to ~ 0.5 watts into an 8 ohm speaker. Connect the Figure 1 circuit as shown to the 10 uF coupling capacitor connected to the collector of Q4. Do not connect the 10 ohm half-watt resistor to the decoupled VCC shown in the schematic. The power supply to the LM386N AF amp should be directly connected to the VCC, not like the common-collector AF stage shown in the schematic to the right.


Figure 1

Simple Electronic Keyer

A simple keyer suitable for a popcorn QRP transmitter can be built around an astable multivibrator and an example of such is shown above. The basic design of this keyer is from notes, however the original author of the circuit is unknown. The notes were written in 1973 . I modernized the circuit, added a variable speed control and designed an additional output driver stage.

Keyer Operation

Keying this circuit generates either dits and spaces or dahs and spaces. When the keyer is idle, Q1 is on and Q2 and Q3 are switched off. When the user sends code, Q1 turns off and Q2 and Q3 switch on and in



turn key any device appropriately connected to the collector of Q3. The off-time of Q1 sets the on-time of Q2 and Q3. The off-time of Q2 and Q3 is set by the 22K Q2 base resistor. This off-time is the set time of the spaces and is constant.

The 68K resistor on the base of Q1 is about three times the resistance of the 22K base resistor on Q2 and consequently dahs are ~ three times the length in duration than dits. Spaces and dits are of the same length of time because when sending dits, the 68K base resistor is paralleled with the 33K resistor and effectively the resistance is ~22K ohms. If the optional relay driver transistor Q4 is used instead of Q3, the theory is the same, just substitute Q4 wherever you see Q3.

Keyer Speed

The keyer speed is very sensitive to the power supply voltage and any keyer speeds mentioned are ball-park values. Your results may vary depending on your VCC and component tolerances. If the 25K speed control pot is turned to minimum resistance, the actual power supply voltage will be present on both the paddle common and the top end of the 68K base resistor. This will be the maximum speed for the keyer. In fact, the speed control pot could be omitted if you want to economize and the keyer will run at the maximum speed as determined by C1 and C2. If you do not want the speed control feature, connect the paddle common and the 68K resistor to the VCC supply. Another alternative is to build a two speed keyer by using a switch to switch in or out a fixed resistor to vary the voltage instead of using a potentiometer. A trimmer resistor may also be used for "lid-off" speed adjustments.

Varying the base-bias voltage with a pot changes the charging rate on capacitors C1 and C2. Although, I experienced no problems be careful with some resistances/VCCs as the circuit may be unable to provide enough current to saturate the transistors when the base-bias voltage is at its minimum setting (pot set to maximum resistance). Smaller pots such as 10K can also be used with a more limited ability to reduce the keyer speed below the maximum rate.

To set the maximum rate for the keyer, it is necessary to vary the value of C1 and C2. For this circuit to function correctly, C1 must equal C2. An experiment was conducted with the 25K pot removed and the paddle common and the supply end of the 68K resistor connected to the main B+ terminal. VCC was measured at 13.8 volts. C1 = C2. The words per minute were counted for four different standard capacitance values and the results were as follows:

2.2 uF = 27 WPM
3.3 uF = 23 WPM
4.7 uF = 17 WPM
10 uF = 9 WPM

For this project, I settled with the 3.3 uF value, although personally, I use a 2.2 uF capacitor for C1 and C2. Sending speed can be reduced with the speed control pot or by increasing the time interval between characters and words. With 3.3 uf caps for C1 and C2, turning the 25K speed control pot to maximum resistance dropped the sending rate down to 12 words per minute. If you needed to slow down below 12 WPM, an amateur could send code using the Farnsworth method as mentioned above. At any rate this circuit allows you to determine the maximum speed rate by choosing the C1 and C2 capacitance value to suit your needs.

Q3, Q4 Output Stages

Two different output stages maybe used with this keyer and they will be referred to as the Q3 or Q4 stage.The Q3 stage is a simple transistor switch which will ground any component(s) connected to its collector when turned on during code sending. A variety of transistors maybe used here and care must be taken to ensure that you do not exceed the maximum dissipation of a given BJT.

The Q4 stage is a relay driver. The 12 volt relay used during bench testing was a Radio Shack reed relay that I had in my parts collection. Specifications were SPST 1A @ 125 VAC , 1050 ohms DC coil resistance, part number 275-233. My VCC was 13.8 volts so a 1K2 current limiting resistor was placed between the relay and supply voltage. The relay has suffered no harm despite significant torture but be careful when you are using a VCC greater than 12 volts. This resistance may be dropped down to 470 ohms or omitted if you are using lower voltages. Any relay with a DC coil resistance of 500 to 3000 ohms should work in this circuit.

I have never used this keyer with the Q4 relay driver for QRP operation as I prefer solid-state switching. The Q3 stage in turn can be connected to trigger a PNP transistor switch to supply DC voltage to a keyed transmitter driver and/or to pull a VFO to its offset frequency. A great example of PNP transistor switches can be found in The Ugly Weekender article by KA7EXM and W7ZOI. This article is referenced in the recommended reading list on this web site. Another bonus of the Q3 stage is that it draws less current than the Q4 stage.

Sending Code

If you are used to a deluxe iambic keyer, this keyer will take some getting used to. The dahs in particular can be problematic as they do not self-complete like they do on my station homebrew TTL iambic keyer. After some practice, however most people should be able to send some good morse code with it despite the lack of iambic luxury.

Miscellaneous

When you power up this keyer, it sends a dit. In one version of this keyer, used in a 40M transceiver, I had a 10K pot for the speed control with a built-in switch on the 10K pot to turn the keyer on or off during station setup.

The diodes D1 - D4 can be any common switching diode such as the 1N914. Q1 to Q4 can be any NPN transistor with a Beta greater than 50 such as the 2N3904 or 2N2222. In the test keyer, all BJT's were 2N3904.

For fun, I connected the multivibrator code practice oscillator to the keyer and gave the keyer a workout. They both work great together and are very complimentary. Have fun with astable multivibrators !

Update Oct 2007:

Giovanni, IW7EHC has posted a great web page on this schematic including PCB layout files in FidoCAD format

Check out his excellent Italian and English language web site

---

Supplemental Page for the 10 MHz WWV TRF receiver

I have received a tremendous amount of feedback regarding the 10 MHz WWV TRF receiver. Many builders have constructed their own versions and have improved it. This captures the spirit of the QRP/SWL Homebuilder web site; take an idea and evolve it into something better on the bench.

I will post some of the feedback as well as provide additional comments and images regarding the 10 MHz WWV project on this supplemental web page. Please continue to provide project feedback and help me to improve the QRP/SWL HomeBuilder web site.



Above. Etched Audio amplifier PC board from K5HP.

Terry, K5HP
Hi Todd,

I have just finished (few days ago) your design for the 10 MHz WWV Receiver. I reduced you schematic diagrams to CirCad schematics, drug out the rat-net, positioned and connected everything, and etched the boards. I'll include a photo of the 4 finished boards. They are very roomy for extra tinkering. Except for two solder bridges on two very big pads on the tweeker capacitors in the front end, it all worked perfectly first try. Hmmm, I cannot say that for all my projects in the past. After repairing the two shorts to ground of the RF path, the front end then tuned and worked perfectly also.

I have not taken the project out to the Lab (barn) and put it on my Motorola Service monitor, but the input to the filter board is roughly 500 uV. It can easily hear WWV at this level with a decent antenna connected to the filter input when WWV is fairly strong at my location. Not bad, considering the mismatch at that location.

Have you or someone else tinkered with an AGC/AVC circuit? At one time I had a nice circuit using an National chip (don't remember the number) which is no longer available that was easy to build and easy to retro-fit into something. It was an AVC which they called an audio AGC.

When I built out the boards I placed proper credit to you and the other developers mentioned on the boards. Should you want my work product it's free for the asking. I'll be glad to send it to you. CirCad in ver 4 is a fairly



Above. Audio amplifier PC board overlay for parts placement from K5HP.

complete PCB cad program and it's free too. There is a version 5, but I have not tried it out yet.

My sincere congratulation for producing and error free web article. That is a heck of a more than you can say about many other projects in the past. Most of those in the past had errors a plenty, and some just did not flat work as described. Someone just thought they would as it turned out. Thanks for the fine article and I'll check your site over for more interesting thing to build or learn from. Best wishes and good luck.

Above. A layout of the 4 completed boards by K5HP.

"I use the CirCAD to produce the artwork, then take the laser printer output and bond the plastic toner onto the PCB. Works good most of the time. Sure easier than trying to do photo etch, and silk screening is pretty expensive. The bottom copper is viewed as you would look down onto the top of a circuit board, through to the copper side. The side you are seeing is bonded to the copper surface. Print one out, hold it up to a light source looking through non printed side and it becomes apparent."

Terry designed and built printed circuit boards. His photographs, etching and overlay files are all bundled together in convenient zipped files which can be downloaded below.

Download the front end zip file

Download the Crystal filter zip file

Download the Detector zip file

Download the AF amp zip file


Butterworth
2K
7
19.6
88
19.6
7
2K
19.6
2K
Cohn
19.6
19.6
19.6
2K

Above. Schematics diagrams of 10 MHz crystal filters by Wes, W7ZOI. I did not experiment with the Butterworth type filter.


All Crystals: 10MHz series freq,
20 mH motional L, 2 pF parallel C,
Qu=100K.
=
2 pF
12.6
.02 H
.0126651 pF
477
33
33
477
VE7BPO
xtal_fil

Above. Schematics diagrams by Wes, W7ZOI.
A schematic representation of the 10 MHz xtal is shown along with the "popcorn" 10 MHz xtal filter I designed.


L-net eval
V(out)
17dB
16dB
15dB
14dB
13dB
12dB
11dB
10dB
9dB
8dB
7dB
6dB
5dB
-20°
-30°
-40°
-50°
-60°
-70°
-80°
-90°
-100°
-110°
-120°
-130°
-140°
-150°
-160°
7.0MHz
8.4MHz
9.8MHz
11.2MHz
12.6MHz
14.0MHz
R1
50
L1
5μ
out
V1
AC 2
C1
50p
R2
2K

.ac lin 1000 7meg 14meg

Above. A simulation of an L network depicted in the L-Match and AM Detector schematic for those interested in driving this detector with a 50 ohm output impedance.

Amateur and Short Wave Radio Electronics Experimenter's Web Site

MF TRF Receiver Supplemental Page

Click here to go to the main project web page This supplemental page is under construction

---

5532 Op amp Pin Out



A Version of the Receiver Using Just L1 and C1 as the band pass filter

You can see a red LED and current limiting resistor in the photos. This is a power on indicator. The telescopic whip antenna can be seen in the lower photo.





Early Versions of the Project Front End

In section A of the schematic below, a dual-ganged 365 pF air variable capacitor was used for tuning. CV, a small compensating capacitor may be required to adjust for the capacitive differences of the 2 L-C tanks in the front end filter. It may have to be placed on the L1 side of the filter (opposite to what is shown). A JFET source follower was used for Q1 but discarded because stage gain was insufficient with a short whip antenna.

In the version depicted as section B, two 12-110 pF air variable capacitors were used along with switchable 270 pF capacitors to provide 2 ranges of tuning. Although this worked, the switching mechanism was found to degrade selectivity somewhat. The JFET was reconfigured as a common source RF amp. This amp caused some distortion of the RF signal on stronger stations unless the gate resistor was lowered to 47K or less. Ultimately a cascode BJT RF amp was chosen for the project. A photograph of the section A breadboard is shown below the schematic.

Broadcast Radio Band Front End


A
12 V
100
.1
47
4 foot whip
365 pF dual ganged
27 pF
d
Q1
.1
g
s
1M
1 mH
L1
L3
CV
220
L2
B
12 V
100
.1
4K7
.1
4 foot whip
L1
27 pF
d
Q1
270 pF
g
s
1M
220
.1
L1
CV1
SPDT
high-low range
CV2
L3
L2

Oct 16, 2006 by VE7BPO

L1 = L3 = 200 uH or 55 turns #28 AWG on a FT50-61 ferrite core
L2 = ~ 5 uH = 9 turns #22 AWG on a FT50-61 ferrite core
CV = small value trimmer capacitor for tracking - 4.5 - 20 pF
CV1 = CV2 = 12 - 110 pF air variable capacitor
Q1 = nJFET; MPF102 or J310



The inspirational detector schematic used for motivation to develop the full wave detector


Q1 2N404
COLLECTOR
BASE
C2
50mfd
D1
D2
R1 220K
EMITTER
T1
L1
C3 365 pf
D4
D3
R2 220K
EMITTER
C1
BASE
50mfd
COLLECTOR
Q2 2N404
B1
SW1
4, 5 VOLTS

Varactor Tuned Front-end Band pass Filter


E
103M
500V
TUNE

Above photo. The 2 potentiometer varactor controlled band pass filter.

Amateur and Short Wave Radio Electronics Experimenter's Web Site

Supplemental to the Cascode Hybrid 5 MHz WWV Receiver

DC Voltages of the Cascode Hybrid Amp



On the right is the basic hybrid cascode amplifier schematic. Note that the Q1 voltage divider bias has two 10K resistors as compared to the 12K and 10K combination used in the final project. A slightly lower Q1 bias voltage was ultimately chosen along with a 150 ohm Q2 source resistor to enhance stability. Early bread boards of this amplifier used a 47 - 100 ohms Q2 source resistor along with the slightly higher Q1 bias, but suffered from parasitic oscillations.

The DC voltages are rounded to 1 decimal point. These are ball park values for reference purposes. The typical stage current draw was around 11 mA. R1 sets the output impedance and is optional. R2 sets the input impedance. This amp is very versatile in that it can be used to match a wide variety of input and output impedances.

The **main 5 MHz WWV receiver web page** which this web page supplements is here.
Click here for a recording of 5 MHz WWV made with the Icom R-75 receiver using the 6 KHz AM filter and the stock speaker. You may wish to compare it to the recorded 5 MHz WWV receiver project audio files linked here , here and here.

---

10 MHz Components

For those who wish to experimentally develop a 10 MHz version, I have included some potential band pass and crystal filter schematics you may wish to consider. In addition, my preliminary experiments indicated that another RF amplifier stage might be necessary for 10 MHz WWV. During development of these band pass and crystal filters, 10 MHz WWV reception was very poor and due to lack of time and the poor conditions, further experimentation was abandoned.
To the left is a 10 MHz band pass filter schematic with a -3dB bandwidth of around 100 KHz.


10 MHz Front end Band Pass Filter
50 ohms
47
5
All caps in pF
g
d
s
4K7
220
CV
56
L1
L2
CV
100
L1 = L2 = 1.1 uH = 15t #24 AWG on a T50-2
CV = 6.5 - 50 pF trimmer capacitor


GPLA - 2002
S21 =
S11 =
S21 Ref.
Click to Review Circuit
10 MHz BP Filter
dB
Plot
dB/div.
Frequency
Freq./div
Enter new value and Click
Place Cursor
Cursor Data =====>

0 Load R = 50.0
1 cap par 220.00
2 cap ser 47.00
3 cap par 183.00
4 ind par 1100.00
5 cap ser 5.00
6 ind par 1100.00
7 cap par 224.00
98 Source R = 4700.0
99 Inductor Q = 240.0

top 0.
10.00 dB/div.
bottom -60.0
start 7.40 MHz
10.00 Freq./div
stop 13.00
C:\Todds\QRPHB\A-DESIGN\2007\5-MHZ
N (index) 7
NewValue 224
Cursor Data =====>: 10.004 MHz S21= -2.32 dB S11= 0.00 dB

The GPLA simulation of the 10 MHz front end band pass filter. Tuning is very sharp with this filter.

To the left is a crystal filter design for 10 MHz. The realized bandwidth of these simple min-loss crystal filters is dependent on your crystal parameters.


10 MHz Crystal Filter
3 dB BW ~ 6 KHz
VE7BPO
All crystal filter caps are pF
22
Y1
Y2
Y3
Y4
Y5
22
1200
1200
15
22
22
15
Y1 - 5 = 10 MHz

A photograph of the experimental 10 MHz crystal filter is shown to the right. Leads were kept long so that parts could be reused in future experiments.


GPLA - 2002
S21 =
S11 =
S21 Ref.
Click to Review Circuit
top
dB
Plot
dB/div.
bottom
10 MHz
~ 6 KHz @ -3 dB
N (index)
NewValue
Enter new value and Click
Place Cursor
Cursor Data =====>

top: 0.

dB/div.: 10.00

bottom: -60.0

0 Load R = 1200.0
1 cap ser 22.00
2 xtl ser 0.00
3 cap par 15.00
4 xtl ser 0.00
5 cap par 22.00
6 xtl ser 0.00
7 cap par 22.00
8 xtl ser 0.00
9 cap par 22.00
10 xtl ser 0.00
11 cap par 15.00
12 cap ser 22.00
98 Source R = 1200.0
99 Inductor Q = 250.0

N (index): 98

NewValue: 1200

start: -8000 Frequency Hz 6000 Freq./div stop: 12000 C:\Todds\QRPHB\A-DESIGN\2007\5-MHZ

Cursor Data =====>: 840.000 Hz S21= -2.91 dB S11= 0.00 dB

Above. The GPLA simulation of the 10 MHz crystal filter.

6 MHz Components


6 MHz Front end Band Pass Filter
All caps are in pF
50 ohms
100
5
470
CV
56
L1
L2
CV
100
22K
g
d
s
L1 = L2 = 3.3 uH = 26 turns T50-2
CV = 6.5 - 50 pF trimmer capacitor

Since it is easy to find 6 MHz crystals and Radio Habana Cuba is on 6.0 MHz, band pass and crystal filters were designed for reference purposes. To the right is the front end, band pass filter schematic.

To the left is a potential crystal filter for 6 MHz AM reception. The bandwidth is ~ 5 KHz which is starting to get too narrow for some listeners, however, your crystal parameters will determine your filter's actual bandwidth.


6 MHz Crystal Filter
3 dB BW ~ 5 KHz
All crystal filter caps are pF
VE7BPO
47
Y1
Y2
Y3
Y4
Y5
47
1200
1200
33
47
47
33
Y1 - 5 = 6.0 MHz


GPLA - 2002
S21 =
S11 =
S21 Ref.
Click to Review Circuit
dB
Plot
6 MHz
~5 KHz @ - 3dB
Enter new value and Click
Frequency
Place Cursor

top 0.

10.00 dB/div.

bottom -60.0

0 Load R = 1200.0
1 cap ser 47.00
2 xtl ser 0.00
3 cap par 33.00
4 xtl ser 0.00
5 cap par 47.00
6 xtl ser 0.00
7 cap par 47.00
8 xtl ser 0.00
9 cap par 47.00
10 xtl ser 0.00
11 cap par 33.00
12 cap ser 47.00
98 Source R = 1200.0
99 Inductor Q = 100.0

N (index) 99
NewValue 100

start -6000 Hz 6000 Freq./div stop 11000 C:\Todds\QRPHB\A-DESIGN\2007\5-MHZ

Cursor Data =====>: 715.000 Hz S21= -2.79 dB S11= 0.00 dB

The GPLA simulation of the crystal filter using the parameters from the 6.0 MHz crystals I had in my parts collection.

VE7BPO Envelope Detector


AM Detector
VE7BPO
12.2 VDC
.01 uF
220 K
1 uF
poly
.1 uF
Ge
10K
V Bias
d
g
s
1 uF
poly
100K
47K
1M
4K7
220 pF
470 pF
Diode : Germanium Diode
JFET : MPF102

To the left is the schematic of another detector experimentally developed for the 5 MHz WWV receiver. The germanium diode has incredible sensitivity when biased, although noise tends to increase with applied DC voltage. This basic design also worked well with a hot carrier diodes, although had less sensitivity. V bias can be changed by adjusting the 220K, 47K and 100 K resistor values. Note diode polarity.

Miscellaneous Photos and Circuits



Above. A work bench version of the basic receiver bread board built in distinct stages from the antenna input to the speaker.

Above, A breadboard of the KK7B audio stage which is preferred to the LM386 stage used in the 5 MHz WWV receiver. The LM386 does take up less room and certainly increases the popcorn factor.

JVC
VGS1001-002
NOM. 2.5W
MAX. 4W
3.2 Ω
±20%
SB
105°C
07/85

Above. The AF stage shown above in a chassis containing a speaker. This is my lab AF amp for testing receivers on my work bench.


12V
10
LM386
1000uF
22
SPKR
10K
10
.1
10uF
10K
1M
.1
10K
.01uF
Ge
33K
100pF
1M
VCC
4K7
(MPF102)
AF AMP
1uF
phone
100K
100
.1
RF amp + detector

A work bench photo of the first version of the W7ZOI detector built in October 2007 is shown above.

RF — Test and Measurement

My Links

Greetings! I enter the QRPHB / SWL HomeBuilder site here and linked a few of my favorite tools, part suppliers and URLs I like and wish to remember. This page might feel intransigent.

In the following section called **Graphics**, I show the odd newer schematic or photo unpublished as permanent site content. A schematic might just represent my mistaken notion or whimsy: a sense of what's caught my fancy — not that my opinion is better than anyone elses.

Quick Navigator

Graphics

Russian giant sunflower — grew to over 3 meters tall


PCE
PCE-DM12
0024
°C
Mode
Range
Data Hold
Relative
CAT III - 600V
CAP Hz% °C °F
Ω
V
OFF
10A
mA
µA
Auto Power Off
10A
V Ω
CAP TEMP

My gorgeous new PCE multimeter just in time for Season 16 experiments starting October 3. Click for another photo. Click for the PCE website — test equipment galore.

RF Transistor Data Spreadsheets

FET

BJT

Test Equipment

Test equipment

USA Rigol Dealer T Equipment

Online Tools and Publications

Standard resistor and cap values

Smith Chart information

Good inductive/capacitive reactance calculator other tools available

Resistive pad attenuator calculator

Ohm's Law 1 pager

VHF Communications website UKW-Berichte/VHF-Communications

The Signal Path EE video blog They review and show the DSA1030A SA + TG

DUBUS Technical magazine for 50 MHz and above

Favorite Experimenters

Esteemed QRP homebrew mentor - Wes Hayward's, W7ZOI web site

🍁 Iulian, YOUDAC-VA3IUL Comprehensive design information and amazing circuits web site

🍁 Markus Hansen, VE7CA A venerable Room 19 Radio School graduate. He has authored for QST. See his receiver featured in QST for March 2006

🍁 Blog of fellow VE7-land experimenter Steve, VE7SL. Look for a link to Steve's web site on his blog

Professor Ken Kuhn's web site. Perhaps start on his site map. A treasure trove of useful information

Ripples in the Ether An always interesting blog from our friend Jason who runs Etherkit

SV3ORA's Site Friend Konstantinos from Greece. Design info galore. Check out his microwave links.

FM Tuner Site Vintage FM Tuner Information

Paul, KE7HR Caver website

Matjaž, S53MV Microwave and RF. My favorite microwave designer. See this page for some inspiration

Paul Wade, W1GHZ authors my favorite QST column *Microwavelengths* His site

Jacques, VE2AZX web site Retired EE with great ideas

Michigan QRP Club Publish *The 5 Watter* Quarterly

Website of Michel, **F6FEO** from France. F6FEO project pages: click and click

Roland, a retired EE who lives in France keeps this wonderful test equipment page

JF1OZL Mega site that first inspired me years ago. He once wrote me a letter - great guy

Brian, K6STI 88-108 MHz web site.

Leif, SM5BSZ Amazing work

KA7OEI Microwave Page web site


RE
RE
RE
RE
RE
RE

ТЕЛЕГРАФНЫЙ КЛЮЧ
СОЛДАТЫ РОА!
ПОЧЕТНАЯ ГРАМОТА
ЦК ВЛКСМ

Memorial Museum of the Leningrad Siege, St. Petersburg, Russia VE7BP0 photos 2006

Государственный музей обороны и блокады Ленинграда


MP042
4M9152
CTS5C0248

RF — Test and Measurement

RF Workbench Page 1 - Case Study Answers

This web page supplements RF Workbench Page 1

Answers:

1. Calculate the power in dBm at point B **= 13.75 dBm**
2. Calculate the power in dBm at point C **= 10 dBm**
3. What is the attenuation in dB of the 50 ohms attenuator pad? **= -3.75 dB**
4. What is the output power in mW of this stage? **= 10 mW**


Case Study
B
Vpp(1)= 3.08V
C
Vpp(1)= 2.00V
13
3
T1
22
CV
← 220 →
51
- 4 dB
50 Ω
d
g
s

The design contained a "theoretical" - 4 dB, 50 Ω attenuator pad using standard value resistor substitutions

QRP SWL HOMEBUILDER

RF — Test and Measurement

50 Ohms Attenuator Pads

This web page supplements RF Workbench Page 2

Table For Pi and T- type pads



Attenuation	Pi-type		T-Type	
dB	R parallel	R series	R series	R parallel
1	869.5	5.8	2.9	433.3
2	436.2	11.6	5.7	215.2
3	292.4	17.6	8.6	141.9
4	220.9	23.8	11.3	104.8
5	178.4	30.4	14	82.2
6	150.5	37.4	16.6	66.9
7	130.7	44.8	19.1	55.8
8	116.1	52.8	21.5	47.3
9	105	61.6	23.8	40.6
10	96.2	71.2	26	35.1
12	83.5	93.2	29.9	26.8
14	74.9	120.3	33.4	20.8
15	71.6	136.1	34.9	18.4
16	68.8	153.8	36.3	16.3
18	64.4	195.4	38.8	12.8
19	62.6	220	39.9	11.4
20	61.1	247.5	40.9	10.1
24	56.7	394.6	44	6.3
25	56	443.2	44.7	5.6


Pi-Type
50 Ω
R series
50 Ω
R parallel
T-Type
R series
R series
50 Ω
50 Ω
R parallel
Attenuators

To build attenuator networks, we normally choose use nearest standard resistor values, or parallel/series 2 or more resistors from our resistor collection to approximate the tabled R. If you're building with 5% parts, consider measuring a few resistors with an ohmmeter to find the best match to the tabeled R.

Resistors in the 8 dB T-type or the 4, 14 and 19 dB Pi-type networks are close to 5% standard resistor values.

QRP SWL HOMEBUILDER

RF — Test and Measurement

Expected Return Loss Table (50 ohm bridge)

This web page is a supplement to Transistor Input Impedance Experiments



Expected Return Loss in a 50 ohm Bridge

Resistor (Ω)	Return Loss (dB)
10.00	3.52
15.00	5.38
22.00	8.20
27.00	10.50
33.00	13.77
39.00	18.16
47.00	30.19
62.00	19.40
68.00	16.33
75.00	13.98
82.00	12.31
100.00	9.54
120.00	7.71
150.00	6.02
170.00	5.26
200.00	4.43
220.00	4.02
270.00	3.25
330.00	2.65
390.00	2.20
470.00	1.86
510.00	1.71

QRP SWL HOMEBUILDER

RF — Test and Measurement

Miscellaneous RF Topics 2011 Supplement

Introduction

This web page supplements the Miscellaneous RF Topics 2011 web page.

1. Design Center - Wrap Around Bias



PNP Wrap-around Bias for an NPN RF Amp

There are entire books written on RF power amps. I don’t pretend to be an expert and offer a simple approach to help move novice builders up the learning curve. Big thanks to Wes, W7ZOI for the theory and explanation for EMRFD Figure 2.16; the wrap-around PNP bias of an NPN transistor with grounded emitter. This bias circuit is fantastic and helps prevent you from burning up too many expensive medium power transistors such as the 2N3866 or 2N5109 during experiments and operation. From our emails, the following experiments were performed and information gleaned.

Since the NPN emitter terminal is grounded or near to ground on my web page examples, the current can really run high — Don't forget to use heat sinks and appropriately rated resistors on the NPN circuit when you really go for power.





Desired IE	IE (mA)	VC (volts)	V ref (volts)	Ra (Ω)
19.0	19.83	8.62	8.15	180
42.0	43.51	8.31	8.15	82
105.0	108.50	8.22	8.15	33.3

Above — The schematic and data table from some biasing experiments. The normal decoupling parts were removed to isolate the biasing circuitry. All voltage and current values were measured. Another photo. A folded piece of paper is under the wire connecting the NPN emitter to the copper clad board. This is how I measure emitter current. The paper acts as an insulator and allows you to press hard with the ammeter probe to ensure good contact. After current measurement, the paper was discarded and the emitter soldered to the copper ground plane.

Biasing Procedure

Step 1: Choose a Target VC

Using collector resistor Ra, we want to drop about 2/3 of the power supply voltage across the NPN transistor. For a 12 volt supply or VCC, this is 8 volts VC. The formula is Target voltage = VCC x 0.66. Why choose 2/3 VCC instead of ½ VCC like we do for Class A audio amplifiers? In audio amps we just use a resistor as the load and the collector voltage can't go above the power supply unless we insert some reactances in the circuit. In simple AF voltage amps, the half VCC supply allows the greatest undistorted, peak-to-peak AC signal swing.

In RF power amps, a transformer or RFC lies on the collector terminal, so the instantaneous collector voltage (sum of the supply voltage plus the peak AC voltage) can go well above the supply voltage. If you have 8 volts on the collector, VC can easily rise to 16 volts or so on signal peaks. It's often prudent to choose a VC closer to VCC than the classic ½ VCC of audio amplifiers.

Hereafter, Target VC is referred to as **VRef**

Step 2: Choose R1 and R2 to bias the PNP @ VRef

Choose the PNP biasing transistors R1 and R2 so that the PNP bias = VRef. The formula follows:

$$\mathrm{VRef} = \frac{\mathrm{VCC} \times \mathrm{R2}}{\mathrm{R1} + \mathrm{R2}}$$

I wrote a Java Applet that does the math Applet A ; just plug in a VCC and play with the resistor values until you get your target VRef with the resistors from your parts collection. Try to get a bias as close as possible to the targeted VRef, but don’t stress out over it.

Step 3: Choose Ra to give (VRef + 0.6)

Ra = VCC – (VRef + 0.6) / desired current in amperes. Use or make up Ra with nearest standard resistor value(s) with an appropriate power rating. In a PNP, the emitter terminal is 0.6 VDC higher than the base, so need to we add that to VRef. The desired current is any reasonable current that you want to set up; for example 25 mA or 75 ma.

Example Calculation

I wanted a emitter current of 105 mA from the Figure 1 circuit. VCC = 12.24. Let's run through the steps.

Step 1: Choose a Target VC

Target voltage = 12.24v x 0.66 = 8.1 VDC -> Now called VRef

Step 2: Choose R1 and R2 to bias the PNP at VRef

I just plugged some resistor values into Java Applet A. R1 is normally lower than R2.



A. Calculate DC Voltage Divider Bias

Enter Voltage: 12.24 Enter R1: 1000 Enter R2: 2000 Bias voltage = 8.16

Above — A practical bias network. I have lots of 1 and 2K resistors. 8.16 v is close to my target VRef.

Step 3: Choose Ra to give (VRef + 0.6)

12.24v – (8.16v + 0.6v) / 0.105 A desired = 33.1 ohms. I put three 100 ohm ½ watt resistors in parallel for Ra. Click for lateral view photo showing the 3 resistors.

The exact measurements of this example and 2 other (19 and 42 mA) are tabled in Figure 1. I used an 82 ohm 1/2 watt resistor for Ra in the 42 mA version. The bench values closely approximate the calculated values. This circuit is quite instructive. In a real circuit (Figure 2) we add in the decoupling parts. Ra performs double duty as the decoupling resistor as well as the current regulator resistor.

Figure 2



Above — A working version of the desired 42 mA medium power amp from Figure 1. Refer to EMRFD Chapter 2 for further information.

How does the PNP wrap-around bias loop work?

Using the sample conditions from Figure 2: VC = 8.16v calculated, Desired IE = 42 mA and VCC = 12.24v
The main decoupling/current limiting resistor Ra is established at 12.24v – (8.16v + 0.6v) / 0.042 mA = 82.9 Ohms.

No matter what, the PNP VRef = 8.16 volts. All of the desired conditions are established and the current is flowing in the NPN. Let's change these conditions and see what happens.

First, instead of 42 mA, assume that the NPN current drops to something less. Hence, there will not be as much of a drop across Ra. This will cause VC to increase. This is the voltage on the PNP emitter. When this voltage increases, there is more voltage between the base and the emitter of the PNP, which will make it draw **more** current. That current comes out of the PNP collector runs to the base of the NPN. This causes the NPN to draw more current (beta times) which increases its collector current and causes the collector voltage to drop because of the I x R drop in Ra. It drops until it reaches the 8.16 volt level.

Let's now assume the opposite. The NPN draw too much current, more than the desired 42 mA. This means that there is too much I x R drop in Ra and VC goes **below** 8.16 volts. This tends to turn the PNP off. The PNP collector current drops, so the NPN base current also drops, causing the NPN collector current to drop. This causes VC to again increase to reach 8.16 volts. Is this cool or what?

---

2. RC Low-pass Network



Above — Spectrum analysis without the RC low-pass filter.



Above — Spectrum analysis with the RC filter in-situ. Above 20 MHz, the spurs are ~5-6 dB down.

3. Transistor Power Dissipation in the 2N3904



Above — Power Dissipation versus Temperature for the 2N3904 in 3 packages.

Power dissipation in the collector resistor

For example, VC (the voltage across the transistor) = 10 volts and the emitter current = 20 mA

P = I x E = .020 amps x 10 volts = 200 mW

Power dissipation in the emitter resistor

P = I x E = .020 amps x the measured emitter voltage

or P = I x I x R

For example, emitter current = 20 mA with a 5 ohm emitter resistor; P = .020 amps x .020 amps x 5 ohms = 2 mW

We assume IE = IC in the above examples. At 200 mW collector dissipation, the 2N3904 temperature temperature climbs to about 65 C. A metal can transistor such as 2N2222 has more surface area and better heat dissipation. A heat sink also improves heat dissipation. Temperature dissipation charts are referenced to ambient temperature which may be dependent on the air circulation around the transistor. If you plan on running 200 mW or so collector dissipation with a 2N3904, glue on a heat sink. A pinch of the finger and thumb, or a infrared thermometer are the most common popcorn ways to test for the need for more heat sinking, or a part with better power dissipation.



Above — I learned this from a Russian builder. 100 heat sinks for a dollar. Typically, a small blob of epoxy with the transistor positioned to the lower edge of the penny works best. I used too much epoxy and didn't wait for it to completely dry before taking this photograph — the penny slid down.

---

4. Some Factors Affecting Common-Gate Amplifier Input Impedance

A question arises: with all the devices and topologies available, why build a common-gate JFET RF amp in 2011 and on? For the J310 JFET at least: they're cheap, the input impedance is close to 50 ohms and wideband, the amp demonstrates good stability, signal handling capability and linear performance — all without running mega-current. Мне нравится. Many authors state the common-gate noise figure is inferior to that obtainable with the common-source topology, but for the popcorn builder, the common-gate noise figure is probably reasonable.


Figure 1
.1
12.22v
100
37t
8t
50 Ω
T50-2
FT37-43
12t
50 Ω
.1
3t
s
d
g
J310
47 pF
.1
330K
150
.1
RFC
1000 uH
47K
12.22v
100K
IS changes with
DC gate voltage
Gate DC bias voltage
.1

Above — A JFET gate biasing experiment. Here I applied 0-7 volts DC to the gate of a common-gate FET amp. The results proved interesting; see the graph below. The drain was tuned with a fixed 47 pF cap and manually "scrunch tuned" by pinching the T50-2 toroid with fingers and thumb. The input RFC serves to decouple the DC from the AC signal and the tap is used to improve the input impedance match.



Above in Figure 2 — A graph of the DC gate voltage versus gain, input return loss and source current from Figure 1.

Increasing the DC gate voltage increases the source current as shown in the graph — ranging from 9.8 to 38.6 mA. From a DC gate voltage of 0 to about 4 volts, amplifier gain changes very little. Technically, the gain of this amplifier should increase along with drain current, however, the input resistance simultaneously goes down, creating greater voltage division loss at the input plus reduced return loss from impedance mismatch. This tends to cancel the increased gain as the plot shows.

The AC signal current injected into the FET comes out of the drain with power gain because that same current is now flowing into a higher impedance. The gain is dependent on the ratio of the impedance at the drain to that at the source. Click for a SPICE plot of DC gate voltage versus source current for 0 - 5 volts from Wes, W7ZOI.

From experiments, I learned that at least 6 things effect input return loss: the source resistor value, stacking or paralleling JFETS, the gate DC voltage(all which change current and/or transconductance), whether or not you bypass the source resistor, negative feedback and also the tap on the input RFC. Like other amps, the impedance of the device before and after the JFET amp can also change the input match, but those are external and normal considerations.



Above — Breadboard of the DC gate bias experiments of Figure1. Properly biased JFETs act like a current source where drain current is controlled by the gate-to-source DC voltage. The input impedance of the common gate amp is the reciprocal of the transconductance. Ken Kuhn posted some great JFET design notes in the yellow JFET section on his web site. EMRFD provides another essential reference for RF JFET design.

Noise Figure and the Common Gate Amplifier

Noise figure is important in low-level RF amplifiers such as a preamp or post-mixer amp because noise generated by these amplifiers contributes to the overall noise figure of a receiver. The input impedance an amp like the common-gate is considered an *active* impedance. Often, with active impedances, obtaining the maximum power transfer and lowest noise figure don't occur simultaneously. That is, the optimum input impedance match for gain is not the optimum input match for low noise performance. With pure resistances, the best noise figure possible is 3 dB; however, when using an active impedance, it's possible to achieve a noise figure less than 3 dB by applying negative feedback or other techniques to manipulate the JFET active input impedance and lower its voltage noise.

A stellar example by Bill, W7AAZI employs DC gate bias, noiseless negative feedback and paralleled JFETs to achieve a noise figure in the 1.2-1.5 dB range. This mind-boggling circuit is described in EMRFD as Figure 6.94. I wanted to explore this topic: can amateur builders design *common-gate* amplifiers for a lower noise figure? The answer is perhaps, however, unfortunately, there is no cookie-cutter approach.

Low noise amplifier design imposes an advanced topic and many builders lack the math skills and/or test equipment to design and generate results. Each design must be approached on a case-by-case basis, although similar fundamentals apply to all cases — using active impedance manipulation techniques and paralleling up JFETs while paying attention to all the resistances in a circuit — even loss resistance in the inductors. I learned from Professor Ken Kuhn that when amplifiers are paralleled the output signal power adds linearly, whereas the internal noise adds statistically (square root of the sum of the squares) and thus noise figure improves. In short, paralleling JFETs reduces voltage noise, but only to a point, as input capacitance also increases which can degrade high frequency performance and noise figure. Ideally, the JFETs paralleled should be matched for IDSS and VP.

Further, all devices have a voltage noise specifications (in volts per root Hz) and a current noise specifications (in amperes per root Hz). The source impedance that produces the lowest noise is the ratio of the two — derived from Ohm's law. The input impedance of the device may be higher or lower; thus the optimum source impedance for low noise is not necessarily the optimum source impedance for maximum power transfer. It's unlikely that these two impedances differ widely, however, only careful bench measurements or closely copying proven designs will ensure the desired results.

---

5. Design Center - Temperature Stable Voltage Divider Bias





Simple steps for a temperature stable amplifier

1. IB = IE / hFE
2. VE = 1.5 * VBE
3. VB = VE + VBE
4. RE = VE/IE
5. ID = IB * 10 (ID is divider current)
6. R2 = VB/ID
7. R1 = (VCC – VB) / ID

Above — A simple way to design a temperature stable BJT voltage divider bias. Assumes that IC = IE. You specify IE.

I sought to develop a simple way for builders to design a temperature stable BJT amp using voltage divider bias. It wasn't so easy. Here is the full math from Ken Kuhn. As shown, it gets complicated and over-the-head of the target readers of this web site.

My simple approach makes assumptions, and certainly an astute builder could improve my algorithm - I developed other formulae, however settled on this one because it well fits the scope of the QRP/SWL HB web site. Most engineers design their bias networks in SPICE and I recommend this.

To choose a Beta or hFE, you can measure the Beta or use the transistor datasheet Beta near to the emiiter current you intend to apply. Many builders debate this and even go as far to state that spec sheet Beta values are useless. This may be true, but you *have* to decide on some approach. Ultimately, you will build the amplifier and can tweak 1 or more of the bias resistor values to set your bias voltage (emitter current). Click for a snippet from a 2N3904 datasheet showing hFE at a range of currents.

Biasing BJTs is a great example of building to suit your design requirements. The average reader likely operates their radios at room temperature where a minimum temperature stability factor is needed. On the other hand, you may operate field portable, or use a crammed chassis where transistors heat threatens stability. As always, your design choices must fit your needs, parts and abilities.
The above 7-step method forms a simple **QRPHB Design Center** method to achieve a reasonable temperature stability factor at normal

operating temperatures. I considered 2 factors: VBE and Beta (hFE) changes.

VBE

We normally attribute the voltage difference from base to emitter (VBE) as 0.7 volts for silicon transistors. VBE changes inversely with temperature and at AF to HF, we mitigate VBE creep by applying an emitter resistor to increase the emitter voltage VE. The emitter resistor provides a feedback loop so as collector current starts to increase due to a rise in temperature, the voltage drop across RE also starts to increase. This voltage tends to reverse bias the base-emitter junction. The net effect is decreased collector current.

How do I choose an emitter resistor value for VBE bias stability asked the little grasshopper (novice)?

The VE value should typically be about 10 to 25% of VCC. VE recommendations really vary from author to author — some say VE should be at least 5X VBE while other authors suggest 2-4 volts as the minimum acceptable VE value for bias stability in typical AF-HF amplifiers. I use 1.5 * VBE (0.7) = a VE of 1.05 volts, but it's up to you. Since you know IE for your transistor, calculate the resistor RE to provide the target VE using ohm’s law: RE = VE/IE.

At VHF on up, emitters are typically directly connected to ground since that path must have as near zero inductance as possible. In these amps, the bias is derived by a feedback circuit that controls the base current to stabilize the collector current at a specific level. Inductance in the emitter lead causes significant loss of gain at higher frequencies and also upsets the input impedance to the base. Similar effects occur in JFETs and even vacuum tubes. 10s of nH of inductance at 144 MHz represents a reactance of 10s of ohms. At UHF on up this becomes very serious — that's why construction methods are so critical for these builders.

In conclusion; to influence VBE stability against temperature changes and to some extent leakage current, at AF- HF, apply series feedback to a raise emitter voltage (VE). Accounting for variations arising from 5% tolerance parts, I chose a minimal VE of 1.05 volts (equation 2 of 7 in my "Simple Steps..." algorithm).

A tradeoff challenges us — increasing the emitter resistance, increases AC degeneration, lowers AC signal gain and raises the transistor input impedance. Bypassing all or part of the emitter resistance offsets these problems.

Beta

Beta variation arising from temperature changes must be mitigated. I briefly discuss the factors that change Beta in the bullets under the #5 Bipolar Junction Transistor Beta Tester on this page.

To design "beta independent amplifiers", the builder alters the resistance ratio RB/RE. Decreasing this ratio improves the Beta stability while decreasing the amplifier current gain. The ratio can be confusing, so the Design Center equations 5, 6 and 7 just make the current in the divider 10X the base current. It's simple — you're done. Feel free to choose whatever ratio you think is best. Good values for the RB/RE ratio lie in the 12 - 20 range.



Design Example

[hFE = 100, IC = 10 mA (0.01A), VCC = 11.22v, VBE = 0.7]

*I used a 100 ohm low-pass resistor; so VCC = 12.22v - (0.01 A * 100 ohms) = 11.22v*

1. IB = IE / hFE = .0001 A
2. VE = 1.5 * VBE = 1.05v
3. VB = VE + VBE = 1.75v
4. RE = VE/IE = 105 ohms **(Use 82 – 100)**
5. ID = IB * 10 = 0.001 A
6. R2 = VB/ID = 1750 ohms **(use 1K8)**
7. R1 = (VCC – VB) / ID = 9470 ohms **(Use 10K)**

Above — A design example employing my "Simple steps for a temp stable amp" bias algorithm. My VCC = 12.22 volts, but, as always I decoupled and bypassed the VCC — in this case, I applied a 100 ohm /0.1 uF network. At 10 mA emitter current, the voltage drop across the 100 Ω resistor results in a VCC of 11.22 volts.

Big thanks to Wes, W7ZOI and Professor Ken Kuhn for helping me with my math problems and to better understand biasing concepts.

A friend made a Design Center spread sheet for MS Excel. In this application you enter the desired IC rather than IE.

Amateur Radio Electronic Design

50 Ohm Common Emitter Audio Preamp Experiments

Introduction

This page supplements the Pop DC2 Receiver Experiments from this web page.


50 Ω Input Feedback Pair
12.22v
11.69v
75
2K7
.001
220 uF
100 uF
or greater
4.46v
Q2
0.76v
50 Ω
Q1
1K
27
1K
3K9
3.75v
AF
Feb 12, 2011

Gain = 18.0 dB
Stage current = 7.22 mA
Input Return Loss = 28.7 dB
Q1= Q2 = 2N3904

Above — A 50 ohm audio preamp to follow a diode ring product detector.

Many seek an alternative to the common base AF preamp that typically follows a diode ring product detector. Winter experiments yielded some possible ideas. The simplest is shown above.

Using all different parts, I built and measured another version to ensure reproducibility of the input return loss while just using standard 5% resistor values. The second amp proved similar: 18.4 dB gain, 7.27 mA stage current (3 .8 mA is consumed by the emitter follower), a return loss of 27.6 dB and a nice sine wave output. A 2K2 resistor AC coupled to the emitter follower provided a load. Note in the photo, I used 1% resistors in some slots, but the values were standard 5% and not unusual values like 15.4 K etc.. The 3K9 feedback R is the most critical value — it's a 5% part.

About 1/4 of my resistor collection are 1% metal film, as I don't like stocking both 5% and 1% tolerances of the same R value. I envision this amp driving a 5532 amplifier/low-pass filter built with 5% resistors with the op-amp output connected to a 1-10K volume control potentiometer.

The amp above is pure popcorn fluff, yet represents over 8 hours of reading, calculations and bench discovery. In another version, I soldered in low noise transistors (MPSA18 for example) and 1% metal film resistors to try and drop the noise figure. Yet another stage had Q1 collector bootstrapping (3 layers of feedback). I'm not sure what I'll do with these experiments, however, at least 1 of these will end up on the module page as the update to the popcorn DC receiver mainframe.

Glenn, VE7DNL built a landmark common emitter preamp with parallel 2N4401s, shunt feedback and some 1% bias resistors. I built a version of his pre-amp without the diplexer. The input return loss in my version was only 5 dB — likely the diplexer network helps establish the input match. It appears Glenn's goal was low NF and the best match and noise figure don't always correlate. I matched Q2 and Q3 as well as I could since only 6 were available. An Hfe of 220- 240 is not uncommon for the 2N4401 — a good part.

Here's a SPICE plot of the amp performed by Wes, W7ZOI. The two plots are S21 and S11. S21 is the forward gain in dB. S11 is the input reflection coefficient, which is just the negative of the return loss. At 1 kHz, the calculated gain = just under 42 dB and the input match = ~17 dB return loss.

To improve return loss in my breadboard, I need to tweek Q2 and Q3 bias (lower the 6.04K resistor), plus add some emitter degeneration. Emitter degeneration (series feedback) would worsen the noise figure. The 100 uF emitter caps offer some series feedback and capacitor values like 1000 uF are needed if "true" AF bypass is wanted.



Above — Alternate experimental 50 ohm audio preamp to follow a diode ring product detector. The high impedance output enables small value output coupling capacitors for pseudo high-pass filtering. I simply added a collector resistor plus a decoupling network to Q2. The low noise MPSA18 BJT is a favorite and predictable part. The 2N3904, 2N4401 and others should work fine.

Don't even think about using an input capacitor less than 100 uF at 50 ohms — you'll trash the input Return Loss. I measured the highest Return

Loss with a 470 uF coupling capacitor, but the 100 uF cap shown worked almost as well.

I'm currently decreasing the (Q2) 1K emitter resistor with hopes of squeezing out a little more gain while trying to preserve strong signal handling capacity. I've found that heavy feedback is your friend.


50Ω Input Feedback Pair
May 19, 2011
12.22v
Gain = 17.8 dB
Return Loss = 25 dB
75
75
100 uF
100 uF
390
2K7
8.87v
4.01v
100 uF
or greater
0.73v
MPSA18
MPSA18
Q2
50 Ω
Q1
3.35v
1K
27
470
1K5
2K0
10.9 mA stage current

Above — Another version; trying to increase stage gain. The Q2 collector resistor dramatically affects clean signal handling — lowest distortion occurred with a 367 ohm collector resistance. I substituted a 390 ohm collector R. This dropped the gain a little, but increasing distortion over gain is never my goal.

During experiments, dropping the the Q2 emitter resistor below 470 ohms made the other biasing resistors more critical, decreased return loss and invited distortion. The best return loss occurred when critically biasing with 1% resistors — I'm avoiding that!


50 Ω AF Preamp
Part A
Return loss = 26.3 dB
Gain = 18.9 dB
Stage current = 15.9 mA
Q1 =Q2 = 2N3904
12.22v
22 uF
75
75
100 uF
100 uF
12.0v
11.69v
820
2K7
6.05v
50 Ω LO
20t FT37-43
170 uH
4.18v
Q2
LO
RF
AF
0.76v
Q1
3.46v
50 Ω
input
.1
220 uF
1K
27
560
51
1K5
2K0
(3.48K 1% R)
Feb 26, 2011

Above — Another popcorn part experiment from February. A low-pass network terminates a diode ring mixer and drives a 50 ohm input feedback pair arranged so the Q2 collector DC voltage is approximately 1/2 VCC — this provides the DC bias for a 5532 op-amp low-pass filter arranged in the Sallen-Key topology.

The Q2 collector voltage removes the need for a separate single supply op-amp bias network and an AC coupling cap. I didn't try this circuit in a receiver; arranging the feedback network and testing the possibility of such a design drove this experiment. A perfect 1/2 VCC Q2 collector voltage might be obtained with a standard 1% value 806 ohm R. I lack this part.

RF — Test and Measurement

Almost Popcorn Superhet



1. Receiver Concept and Macro Diagram

Not done.

Maybe a flight-of-fancy that never crosses the finish line? This page seems to repeatedly find the back burner; a good intention that never sees completion. Sadly this is normal for some of us builders — how many incomplete projects adorn your home and workshop? Still, this web page might fuel your *own* experiments.

For years, I've attempted to update my Popcorn Superhet from 1998 but always seem to lose interest from numerous distractions such as VHF and UHF experiments and other non-radio stuff. So here it is so far — raw and unrefined: more experiments from my analog-centric workbench. To clarify — I love the new digital radio stuff, but that's well covered on the net by numerous code writers and those bleeding edge, frontier-pioneer types. I prefer a 50 Ω lab with all the visceral enjoyment and learning it has to offer. To each his own.

This web page remains unlisted on the main top level menu — and for good reason.

Click for some supplemental lab notes.

---

2. N = 4, Gaussian-to-6 dB Crystal Ladder Filter

I frequency matched four 11.0592 crystals, characterized them and took an average of those crystal parameters plus some data from Zverev and inputted this into xlad08.exe, a program that ships with EMRFD.


XLAD08: Crystal Ladder Filter Design
File
About XLAD
1. Characterize Crystal
2. Set B and N
2A. Generate Butterworth, Chebyshev, or Cohn k and
3. Set q1 and qn
4. Match Ends
5. Calculate Coupling Caps
6. Tune each Filter Mesh
Save design to default file.
Exit

Follow instructions in numeric order:

F , MHz 11.0592 Motional L, Henry .01 Q-u 70000 C0, pF. 4.86

1. Enter or edit crystal parameters and click:

Filter Bandwidth, Hz, = 1000 Number of Crystals in Filter (20 max) = 4

2. Enter/Edit B and N and click:

2A.(Optional) To generate k and q values, click:

q1 = 0.6 qn = 1.2348

3. Enter or Edit End Normalized Q values and click:

Min End Resistance = 103.4

End R = 200

4. Enter or Edit End R and click:

Shunt End Capacitors C-1, pF 69.55 C-N, pF 134.17

k1-2 1.4512 k2-3 0.9245 k3-4 0.6213 k4-5 00000 k5-6 0.0010

k6-7 0.0010 k7-8 0.0010 k8-9 0.0010 k9-10 0.0010

5. Enter or Edit the Normalized coupling coefficients and click:

6. Edit Coupling and End Caps, if desired, and Tune Filter:

Shunt Coupling Capacitors, pF

C12= 144.72
C23= 227.17
C34= 338.03
C45= 0.00
C56= 0.00
C67= 0.00
C78= 0.00
C89= 0.00
C9-10= 0.00

SeriesTuning Capacitors, pF.

CT1= 99999.00
CT2= 393.19
CT3= 153.97
CT4= 195.76
CT5= 0.00
CT6= 0.00
CT7= 0.00
CT8= 0.00
CT9= 0.00
CT10= 0.00

A Tuning Cap. of 99999 indicates a wire when building the filter.

xlad08, 5 Nov 08d, w7zoi

Above — Xlad08.exe screen shot.


393.2 pF
154 pF
195.8 pF
50 Ω
50 Ω
69.6 pF
144.7 pF
227.2 pF
338.3 pF
134.2 pF
11 BFT
FT37-43
11 BFT
FT37-43
XLAD Calculated Capacitor Values

Above — The xlad filter expressed as a schematic. Click for a GPLA plot of the filter.

I built and hand tuned this crystal filter with my analog sweep system. Click for a photo of the optimized filter breadboard — I used 1 or 2 parallel capacitors to tune each capacitance to derive the best possible skirt shape. Click for a sweep of this optimized filter in my 'scope. 2 bifilar transmission line transformers provided the required 200 Ω port termination in my 50 Ω sweep system.

I sought a crystal filter based on the xlad08 calculated values using only 1 nearest standard value in each capacitor slot.

Transitional filters like the G-to-6 dB, are generally tolerant of part substitutions and thus I sought a filter with only 1 nearest 5% standard-value capacitor in *every* slot instead of 2 sticking 2 close in value parallel caps to make up the needed capacitance as needed.



IF = 11.0592 MHz, Lm = 0.01, Qu = 70K, C0 = 4.86 pF, BW = 1KHz Q1= 0.6, QN = 1.2348, R = 200 ohms, K1-2 = 1.4513, K2-3 = 0.9245, K3-4 = 0.6213

N=4 Gaussian-to-6 dB

Above —The 2-step transition to a 1 capacitor, nearest standard value in each capacitor slot. In the top diagram, I placed a trimmer cap on each end to allow filter tweaking while looking at the swept filter in my 'scope. I've learned that adjusting the parallel cap nearest to each port a simple way to tweak a G-to-6 dB filter. After setting the best looking skirt, I removed and measured the end parallel capacitance and substituted the nearest standard fixed capacitor. Manipulating the capacitors values will change filter bandwidth and return loss.

You might compare the lower filter to the xlad calculated values to see how tolerant the circuit is.



Above — A sweep of the single value capacitor version that's used in the Almost Popcorn receiver. While the 1 KHz filter skirt isn't perfect, it's reasonable. Click for the test bench breadboard. This particular filter measured 1/2 power bandwidth = 1227 KHz and the insertion loss was ~3.6 dB.

3. IF Amplifier


12.21v
BF998
.022
5K6
100
5.6pF
10
100
G2
G1
D
S
5.6pF
.022
IF gain
10
5.6pF
10
10K
FT37-43
.022
FT37-43
11t
.01
12t
3t
50 Ω
3K3
2K2
2K2
2K2
1K8
Output RL
= 21.8 dB
xtal
FL
200 Ω
17.42 uH
19t FT37-61
.01
27
390 pF
.01
27
Input RL
= 28.5 dB
G2
D
G1
S
G2
D
G1
S
1.8 - 12 pF
1.8 - 12 pF
3K3
100
.01
10K
100
.01
Maximum gain = 43.3 dB
Gain variation = 30.6 dB
Max current = 9.7 mA
1N4148
Almost Popcorn IF Amp

Above — Version 2 of a popcorn IF amplifer idea with BF998s. IF = 11.0572 MHz.

I have no use for AGC in my personal receivers since I listen through a speaker and *always* ride the RF gain control with my finger. Since the BF998 has gain into UHF, wideband decoupling + bypass SMT R-C networks filter each MOSFET in case of oscillations. Click and click for photos. This circuit will operate fine with just 0.022 µF bypass caps.

A network matches the 200 Ω xtal filter output impedance to the 3K3 input Z of the IF amp cascade. The L-C-C network has become a favorite matching weapon — 2 tweaks is often better than the 1 offered by a garden variety L-network. The product detector that follows this stage is a Level 7 diode ring mixer soldered onto the audio preamp board. This receiver will feature some modish circuits aimed at low noise + high fidelity but still stay "almost popcorn". Anyhow, that's my hope.



Above — A breadboard of the Popcorn IF amp sans the input network. I tested this stage using an oscillator with a 3K3 output impedance and liked what I saw. Click for a reverse angle view. After this build, I ordered some SMT versions of the 1N4148 diode. The BNC connector was only soldered on the board for testing purposes.



Above — Setting up to measure the return loss of the 200 Ω input Z of my popcorn IF amp. 1 difference between scratch homebrew and kit building is all the measurements you need to make to optimize your scratch receiver. A joie de vivre stems from our descriptive/exploratory analysis before and after making our breadboard. We just learn from mistakes and move forward to improve both our knowledge and gear.

I chose a 200 Ω input impedance for a reason — it's easy to apply a standard 50 Ω return loss bridge via a 4:1 transmission line transformer to establish the correct input impedance for the single frequency matching network.

From the set-up shown above, I found that with a 200 Ω resistor, my return loss at 11.057 MHz = 33.4 dB. This signals the very best we can achieve with our network: directivity. Click for a photo of the above experiment breadboarded on a scap of copper clad board.


Q = 5.7
T37-61
Qu = ~100
16.4 uH
4.3 pF
1.5-7.4 pF
3K3
3 - 22 pF
10.1 pF
Tweak L and C's for best return loss
11.0572 MHz
RETURN LOSS BRIDGE
?
RF
D
Figure 2
11 BFT
FT37-43
50 Ω terminated scope (Detector)

Above — The schematic of my 200 to 3K3 Ω matching network. I designed it with zmat08.exe, a program by Wes that I first used as a console app since the days of DOS. *Zmat08 program comes with EMRFD.* Click for a screen shot of from Zmat08.

The calculated values from Zmat08 only consider a pure resistance and not a complex impedance, so on-bench adjustments of the design L and C values are normally required and fun to do. Variable trimmer caps make tweaking the C easy.


Q = 5.7
T37-61
Qu = ~100
17.42 uH
3.07 pF
1.5-7.4 pF
3K3
3 - 22 pF
9.15 pF
RETURN LOSS BRIDGE
?
RF
11.0572 MHz
D
Figure 3
11 BFT
FT37-43
50 Ω terminated scope (Detector)

Above — The final— *measured* schematic — While watching the peak to peak voltage on my 50 Ω terminated scope, L and both capacitors were tweaked until I found the highest return loss. L is tweaked by scrunching or expanding turns, or adding/removing turns as needed: in this case, I added a turn and expanded the windings slightly. With the L-C-C match, a return loss greater than 25 dB may arise plying good bench practices — mine measured a lovely 29.2 dB. I removed and measured the inductor plus 2 capacitors to get the values shown **black** in Figure 3.



Above — A breadboard of the Figure 3 network before I experimented to find the best L (and shortened its leads).

After I making and tweaking the Figure 3 network, I took the coil along with 2 cheaper trimmer caps and added them to my IF amplifer breadboard. While measuring the return loss of the IF strip input, I had to expand a couple of links on the inductor, but after tweaking the L and the 2 trimmer caps, I measured a 28.5 dB return loss. This ensures my crystal filter will see close to a 200 Ω termination at the IF input. I love well matched stages!

Further, I made a L network and then a L-C-C network to match the output port, however, UHF oscillations erupted. I then went back to a simple broadband transformer and measured a RL of 21.8 dB with a 12:3 turns ratio. Done.

---

4. Mixer and Post-Mixer Amplifer


Universal Diplexer QRPHB Series

C1 and C2: 286.8 pF

L1 and L2: 0.72 uH

Enter Frequency in MHz: 11.1

Above — I tested the W1JR (Joe Reisert) bridged-tee diplexer against another design used by Ten-Tek. I'll show the outcomes on the Almost Popcorn receiver page some day, but the W1JR better fullfills its purpose; termination from DC to daylight at the mixer IF port. I calculated the L and C values for a 11.0592 MHz IF with my Universal Diplexer application from many moons ago.


.ac dec 500 .1meg 100meg
R1
50
L1
720n
287p
C2
s21
V1
V2
R3
50
R4
50
R5
50
C1
287p
L2
720n
AC 2
AC 1
R2
100meg
s11

Above — SPICE provides a great way to assess a diplexer since you can plot both S21 and S11 against frequency.



Above — A fantastic match! Thanks Joe for the design and to **Wes, W7ZOI** for his help with diplexers and the SPICE plots through many years of related experiments. Since web publishing the diplexer page, at least 500 diplexer-related emails have come in. Human translated versions of the web page exist in at least 3 languages.



Above — The evaluation breadboard of my W1JR diplexer. Those are T30-6 toroids but they look huge in this photo.



Above — Tracking generator plus spectrum analysis sweep. SPICE does a better of examining the high-pass side.


12.20v
22
11.34v
.01
.01
11t
FT37-43
270 pF
1K5
.01
150
200 Ω
To
xtal FL
10 dBm
18 pF
720 nH
1K5
300
300
.01
2N5109
A
LO
RF
IF
49.9
49.9
.01
300
300
4.19v
3.46v
MCL
RMS-5LH
1K
720 nH
100
.1
From point A
4.7
18 pF
270 pF
IF = 11.0592 MHz
40.4 mA
S11 = -20.9 dB
S12 = 31.2 dB
S21 = 15.5 dB
S22 = -30.6 dB
Mixer-Diplexer-Amp

Above — A look at the diode ring mixer, diplexer and post-mixer amp from the latest version of my Almost Popcorn Receiver. I tested the diplexer and RF amp with pad as one unit (see the S-values).

It did not make sense to use a transmission line transformer to get 50 Ω on the amp collector and then use another transformer to build it back up to the needed 200 Ω impedance for the crystal filter, so I just employed a single choke driving a 200 Ω Z attenuator pad.
S parameters are 50 Ω values, thus S22 = the 200 Ω transformed into 50 Ω. After terminating the stages 200 Ω output with a 4:1 Z transmission line transformer, I tested it like any other 50 Ω circuit andmeasured S22 as -30.6 dB — my xtal filter input Z is well established.

Even with the 6 dB *(200 Ω)* attenuator pad and losses from the diplexer, the stage gain from point A = 15.5 dB. Click for to view a bigger picture of the breadboard. Losses from a diode ring mixer are typically 5 - 7 dB.


MCL 1 942
RMS-5LH
J3
U1
J1
J2
IF
RF
RF Bay, Inc.
MIXADE REV. A 09/2004

Above — Mixer and diplexer assembly. The RMS-5LH takes 10 dBm LO drive.

5. Product Detector and Post Product Detector AF Amplifer

I kept the diode ring for a product detector: an SBL-1 driven with a xtal oscillator (BFO).


12.21v
470 µF
75
100
100 µF
100 µF
2K7
68K
11.78v
50 Ω
4.21v
Q2
0.72v
Q1
1 µF
100 µF
1K
0.08v
27
Q3
0.35v
100
4K7
1N4148
3K9
3.56v
3.54 mA
S11 = -24.1 dB
Gain = 17.3 dB
Total I = 7.41 mA
Q1 = Q2 = Q3 = 2N5089

Above — My post-product detector amplifier: a common emitter/ emitter follower pair arranged for a 50 Ω input impedance with shunt and series feedback. Getting the biggest, clean sine wave in and out posed my only goal — the 3.54 mA current source on the follower helps that cause. The input Z tested quite insensitive to output load variations and the (S11) return loss = 24.1 dB.



Figure 2

12.21v
470 µF
75
100
100 µF
.01µF
100 µF
47K
22
100 µF
LO 7dBm
2K7
68K
100 µF
Q2
12t FT37-43
LO
RF
AF
Q1
47K
3
8
7
5532
RF
.1µF
100 µF
1K
1 µF
SBL-1
27
Q3
1K
2
4
49.9
1N4148
100
25K
3K9
Q1=Q2=Q3 = 2N5089
.0015 µF

Above — The "Full Monty product detector to AF preamp". A MCL SBL-1 diode ring mixer drives the 50 Ω input Z feedback pair and finally a 5532 op-amp with adjustable gain. The 25K gain trimmer pot allows the builder to accommodate factors such as whether the stage is a DC receiver, or an RF-AF block for a superheterodyne receiver like in this radio. I'll set the gain as low as possible and hope to build up my AC voltage with active, gain producing low-pass filter op-amp stages.

The output t pin 7 is directly coupled to an op-amp AF filter. With software we can easily design a myriad of audio filters: band-pass, low-pass, high-pass, all-pass etc. I only run low-pass filters in this slot and even here we must decide whether to make our reponse Gaussian to 6 dB (or 12 dB), Bessel, Butterworth, or a Chebyshev with some degree of ripple. I'm testing out a few designs with an eye towards simplicity and 10% parts.

Spurred on by curiosity, with my ears as the main evaluation tool; I currently have a 5532 paper design to deliver 20 dB gain with a 500 Hz pass-band, Gaussian to 12 dB low-pass response. Click for schematic, I chose a 500 Hz cut off frequency since the skirt shape by definition is subtle and the Q low. This trick should better roll off the AF above 1 KHz a little faster without the ugly group delay associated with steeper filters employing more poles. We shall see!



Above — The compact breadboard of Figure 2.

Audio filters and AF power amp are incomplete.....

RF — Test and Measurement

Almost Popcorn Superhet — Supplemental Lab Notes



These lab notes supplement the Almost Popcorn Superhet Receiver Web page which has remained incomplete for greater than 10 years. I'm sorry for the rough writing and procrastination.

N = 3 Gaussian-to-6 dB Crystal Ladder Filter

I spent a pleasant Saturday afternoon designing, building and testing Gaussian-to-6 dB crystal filters. I inputted some xtal parameters + constants from Zverev into Xlad08.exe from EMRFD. Here's the N = 3 version


XLAD08: Crystal Ladder Filter Design
File
About XLAD
1. Characterize Crystal
2. Set B and N
2A. Generate Butterworth, Chebyshev, or Cohn k and q.
3. Set q1 and qn
4. Match Ends
5. Calculate Coupling Caps
6. Tune each Filter Mesh
Save design to default file.
Exit

Follow instructions in numeric order:

F , MHz 11.0592
Motional L, Henry .01
Q-u 70000
C0, pF. 4.86

1. Enter or edit crystal parameters and click:

Filter Bandwidth, Hz, = 1000
Number of Crystals in Filter (20 max) = 3

2. Enter/Edit B and N and click:

2A.(Optional) To generate k and q values, click:

q1 = .4691
qn = 1.731

3. Enter or Edit End Normalized Q values and click:

Min End Resistance = 135.3

End R = 200

4. Enter or Edit End R and click:

Shunt End Capacitors

C-1, pF 49.78
C-N, pF 175.56

k1-2 1.4574
k2-3 .6496
k3-4 0.0000
k4-5 0.0000
k5-6 0.0000
k6-7 0.0000
k7-8 0.0000
k8-9 0.0000
k9-10 0.0000

5. Enter or Edit the Normalized coupling coefficients and click:

6. Edit Coupling and End Caps, if desired, and Tune Filter:

Shunt Coupling Capacitors, pF

C12= 144.10
C23= 323.30
C34= 0.00
C45= 0.00
C56= 0.00
C67= 0.00
C78= 0.00
C89= 0.00
C9-10= 0.00

SeriesTuning Capacitors, pF,

CT1= 99999.00
CT2= 293.25
CT3= 182.72
CT4= 0.00
CT5= 0.00
CT6= 0.00
CT7= 0.00
CT8= 0.00
CT9= 0.00
CT10= 0.00

xlad08, 5 Nov 08d, w7zoi

A Tuning Cap. of 99999 indicates a wire when building the filter.

Above — A screen capture from Xlad. This app allows skilled builders to depart from the typical Cohn (Min-Loss) filter and tune filter poles to derive beautiful skirt shapes and low insertion loss if wanted. I'm not a great crystal filter designer, but I've seen work from friends who have a knack for it: imagine making a N= 8 to 10 crystal CW filter with just ~1 dB insertion loss like these builders! Click for the GPLA simulation.


N = 3 Gaussian to 6 dB
293.3 pF
182.7 pF
200 Ω
200 Ω
49.8 pF
144.1 pF
323.3 pF
175.6 pF
F = 11.0592 MHz, C-par = 4.86 pF, Lm = 0.01
Qu = 70K, Q1 = 0.4691, QN = 1.731, R = 200 Ω
K1-2= 1.4574, K2-3 = 0.6496, BW = 1 KHz

Above — Gaussian-to-6 dB xtal filer schematic where N = 3.


CV
300 pF
150 pF
176.2 pF
50 Ω
50 Ω
CV
56.7 pF
CV
156.7 pF
100 pF
CV
302.3 pF
270 pF
180 pF
11 BFT
FT37-43
11 BFT
FT37-43
Filter
Exploration
N=3 Gaussian-to-6dB
CV = 5 - 79 pF variable
Measured C

Above — Circuit to allow evaluation of the filter in my 50 Ω sweep system. Transmission transformers provide the needed 200 Ω filter termination. I inserted 4 trimmer caps to permit tweaking of the filter under test to establish the very best filter shape. With trimmer capacitor adjustment, I was able to trash the filter or peak it well. Click for 3 different swept bandwidths: Sweep-1 Sweep-2 Sweep-3.

After peaking, I removed *all* the caps and measured them as shown in **red font**. I'll replicate these values with nearest standard-value fixed capacitors. The trimmer caps nearest to the ports proved more sensistive compared to the 2 middle trimmers capacitors during tuning.

This might be the coolest thing I've ever done on my test bench.



Above — My N = 3 filter breadboard. I left the capacitor leads long for re-use. I consume huge numbers of parts and recycle as possible to keep costs down.

Mixer and Post Mixer Amplifer Development



Above — Ugly breadboard shot with my ancient 105 mm lens for a change. It's a Beaverton Special feedback amp (FBA) biased for ~40 mA. For my post-mixer amp. If you need a stout RF amp, this one will do in a storm.


12.20v
22
11.34v
.01
.01
6 BFT
BN43-2402
220
220
.01
5 dB
50 Ω
15
15
To
xtal FL
82
1K5
1K5
2N5109
11.0592 MHz
S11 = -19 dB
S12 = -29.7 dB
S21 = 16.7 dB
S22 = -35.2 dB
.01
.01
50 Ω
4.19v
3.46v
From
diplexer
1K
100
.1
4.7
Post Mixer Amplifer
40.4 mA

Above — The Beaverton Special feedback amp biased for ~40 mA with a 50 Ω output Z. The FBA with no 5 dB pad: S11 -18.5 dB; S12 -34.6 dB; S21 22.1 dB and S22 -31.8 dB. I love this FBA for its simplicity and well defined port impedance. My IF = 11.0592 MHz. Click for a discarded (but cool) photo.

To drive the 200 Ω input Z of my xtal filter I later converted the output to 200 Ω by changing the collector transformer and pad.

Frequency Synthesizers and Logic

I've spent a great deal of time reading about & playing with some HC series logic I bought in 2011-2012. I even purchased a few 74AC74, a D flip-flop you can clock up to 160 MHz or so. Most of my reading concerned frequency synthesizers: PLLs, dividers, prescalers, etc. Since most modern devices run a clock at GHz frequencies, the evolution of frequency synthesis technology from around the mid 1970's to now makes for a fascinating read.


5v Reg
12v
+
10 µF
.1
14
7
10 MHz Clock Osc
1
NC
8
5
16
14
4
74HC193
13
11
8
9
10
1
15
22K
x4
2
74HC74
5
3
7
1, 4, 10, 11,
12, 13, 14
F
Programmable
Divider
Experiment

Above — Using a CMOS 10 MHz clock oscillator, I tested out a positive edge-triggered programmable frequency divider designed by Wes, W7ZOI in 2011. It works perfectly.



Switches	Frequency (KHz)	N
0000	0	0
0001	3333	3
0010	2500	4
0011	2000	5
0100	1666	6
0101	1429	7
0110	1250	8
0111	1111	9
1000	1000	10
1001	909	11
1010	833	12
1011	769	13
1100	714	14
1101	666	15
1110	625	16
1111	588.2	17

Programming Pin Sequence on 74HC193: 9, 10, 1, 15

Above — A test of all 16 combinations of the 4 programming switches with the 10,000 KHz input. I show the measured output frequency in KHz and the integer generated by dividing the output F into 10,000 KHz. You may leave pin 9 HIGH and just run it as a divide by 10 to 17 counter with 3 panel mounted programming switches — that's what I hope to do.

While working at Tektronixs, Wes designed the frequency synthesizer for the 492 Spectrum Analyzer; a portable SA that went to 21 GHz or so. His experiences informed the design of this simple, low-cost, edge-triggered divider.

Here, Wes applies the 74HC193 as a down counter where a number is loaded and then it count downs until zero is reached. The number gets boosted by 2 — 1 comes from the 74HC74 D flip-flop, while the other arises from the phasing of the signals. The 74HC74 makes the overall output coherent with its clock and avoids the flicker noise that otherwise might be generated in the long divider chain of the ripple counter.

The standard binary to decimal conversion is altered in this circuit.



Above — My ugly breadboard. Instead of switches, I relied on bench jumpers to set a pin LOW.

Check out the standard binary switch combinations on this cool website: Math Is Fun. I also enjoyed their hexidecimal drum machine tool - Click. Actually, the whole web site looks great and I will recommend it to our friends with children and maybe even a few radio enthusiasts.

The Local Oscillator


Loop Filter
18.059 -18.177 MHz
VCO out
-
+
Low-pass
Phase-Frequency Detector
Butler with low phase noise and FL
program WORD
74HC193
74HC74
Divide by 10-16
3.5795 MHz color burst crystal @ 5th OT = 17.8975 MHz
MTO 2576- 2796 KHz

7 MHz receiver where
IF = 11.0592 MHz

Design Cycle
December 15, 2012

Above — An Almost Synthesizer based upon the design currently in use at W7ZOI.

I picked the MTO, xtal oscillator and VCO frequencies and will design the loop filter once I get the parts and a few small die-cast boxes on hand. The MTO division integer is low and quiet — plus this scheme enhances MTO frequency stability and spectral purity. A 4-bit ripple counter + flip flop perform the division where N = 10 - 16. I might go higher with N , but don't want to get too greedy. For CW, I'm generally in the bottom 20 KHz of the band anyway.

The MTO tunes about a 13-14 KHz range and the N gives 6 different tuning ranges (with some overlap) to span a total range of ~118 KHz. The 4-bit WORD is changed by 3 chassis-mount toggle switches and give a PLL reference of ~~175 to 280 KHz.

This almost synthesis seems a little crude in a time when people use microcontrollers to input a WORD into a chip with with the simple turn of a rotary controller, however this set-up fosters learning, huge fun, and when the oscillators plus loop filter are well designed; low phase noise and reciprocal mixing.

The Crystal Filter



Above — A GPLA sweep of my 4 crystal filter where C parallel = 4.86 pF, Lm = .01 H, IF = 11.0572 MHz, BW = 1 KHz and R term = 200 ohms. This Gaussian to 6 dB filter design was chosen for speaker audio that sounds full + dynamic without the hollow ringing so often heard in homebrew receivers. I filter in my brain and first learned to copy CW across a room while listening to a speaker.

My code mentor Doug, could make coffee, walk around the room, talk to us and still 100% copy CW at 40 WPM. He taught us the ear to brain bandwidth is ~ 100 Hz when copying weak signal CW through a sideband crystal filter. To this day, I prefer listening through wider CW filters with brain band-pass filtering.

Amateur and Short Wave Radio Electronics Experimenter's Web Site

KL7R Memorial Supplemental Page

This web page is a supplement to the K7LR Memorial Receiver Experiments Web Page

Audio Preamplifier Focus


V2
12
R3
100
Q1
2N3904
R2
100k
1N4148
D1
1N4148
D2
C2
22µ
R10
10k
R13
10k
C6
22µ
R4
6.8k
R7
10k
col
U1
R8
100k
C5
390p
R9
1k
C4
100n
u1out
Q2
2N3904
C1
50µ
R1
50
R5
3.3k
R6
3.3k
C3
10µ
V1
AC 2
R11
1k
R12
1k
C8
0.3µ
C7
0.15µ
U2
NewVal
u2out
C9
1µ
R14
1K
R15
75k
C10
470p
U3
u3out
R17
10k
R16
10k
C12
33n
C11
15n
U4
u4out
R19
10k
R18
10k
C14
33n
C13
15n
U5
u5out
;op
.ac dec 500 100 5000

Shown above is a SPICE build of an earlier prototype of the audio preamp chain which was ultimately used in this receiver. This SPICE work was performed by Wes, W7ZOI. Note that at this point, I had 100K plus 390 pF feedback in U1 and a 75K plus 470 pF feedback resistors in the op-amp amplifiers (really massive gain). I spent 4-5 days trying different audio stages before settling on the circuits shown.



Shown above is the voltage versus frequency plot from a SPICE run of the schematic shown above. The gentle slope (decibels per octave) of the low pass filters can be seen. Certainly Chebychev filters with 1-2 dB of ripple would have provided steeper filtering, but the filters would have odd resistor values and be less easily modified or reproduced by popcorn builders. The V(u5out) shows a reasonable low pass response for the AF preamp.

Audio Power Amp


AF Power Amp
22K
22K
100
12.24v
10
470 uF
22 uF
33 uF
100 uF
.001
10K
22K
Volume
1 uF
5
6
8
7
4
5532b
7.33v
5.03v
5.65v
2K7
1K
6K8
22 uF
2.30v
1.28v
2N3904
2N3906
1
1
1
1
470 uF
8 Ω
4K7
4.7 uF
100K
390 pF
10
.1
Max sine wave power 305 mW

This schematic shows a stand-alone version of the audio power amp. If only 1/2 of the 5532 is used, connect pins 3 and 2 of the unused op-amp to the point where all the 22K resistors connect (VCC/2 bias point).

Product Detector Notes


Product Detector
RF
ON resistance
~2.5-5 ohms
LO
AF
Output
A
SPDT CMOS
analog switch
4053
RF
ON resistance
~ 120 ohms
AF
Output
square wave
LO
B

Shown above is the analogy between an SPDT CMOS switch and a single-ended, diode product detector. In both cases (A and B), the LO causes 1 diode (switch) to conduct, while the other is OFF. Then, on the other half cycle, the other diode (switch) conducts. If you wish to actually using the product detector/mixer depicted as "A" go with Figure 5.19B in EMRFD which has the LO applied to the transformer primary. As shown, "A" has poor LO to RF isolation, but it helps model the CMOS SPDT analog switch function. Function and performance are completely different topics... The on-resistance of the 4053 is much higher and thus performance is not identical.


CMOS Analog Switch Model
Logic High
On
Resistance
A
B
closed
Logic Low
A
B
open

CMOS analog switch model. A or B are bidirectional and can be used interchangeably for the input or output. Ideally the on-resistance should be low to reduce propagation delay of digital signals plus resistance and perhaps distortion of analog signals. They can be used to switch digital bus data or analog signals. CMOS switches can replace mechanical reed switches in some low power circuits.


4053 Pin out
12, 2, 5
14, 15, 4
13, 1, 3
9, 10, 11
X0, Y0, Z0
X, Y, Z
X1, Y1, Z1
A, B, C
74HC4053N
Y1 1
Y0 2
Z1 3
Z 4
Z0 5
INH 6
VEE 7
VSS 8
16 VDD
15 Y
14 X
13 X1
12 X0
11 A
10 B
9 C
4053
CONTROLS
6 INHIBIT
11 A
10 B
9 C
SWITCHES IN/OUT
12 X0
13 X1
2 Y0
1 Y1
5 Z0
3 Z1
X 14
Y 15
Z 4
COMMONS OUT/IN
VDD = PIN 16
VSS = PIN 8
VEE = PIN 7

The CD4053BC is a triple 2-channel multiplexer having three separate digital control inputs; A, B, and C, and an inhibit input. Each control input selects one of a pair of channels which are connected in a single-pole double-throw configuration. A high on resistance makes the 4053 a compromise part for RF mixing. It might be perfectly okay for your design.


Quad Bilateral Switch
1 in 1
1 out 2
2 in 3
2 out 4
2 control 5
3 control 6
7
14 VDD
13 1 control
12 4 control
11 4 in
10 4 out
9 3 in
8 3 out
4066
MAXIM
MAX4066CPD
+0822

All inputs can serve as outputs and visa versa
A switch is closed only when the control pin is HIGH
Series ON resistance varies with VDD, device, etc.
Max switching freq is ~ 10 MHz. Check datasheet

The 4066 is more easily understood when drawn in a semi-schematic. The on-resistance of this MAXIM version is better than the usual HC4066. About 45 ohms with a VCC of 12 or so.


4066 Concept
12.24v
100
22 uF
.1
22 uF
.1
10K
10K
330K
RF input
.1
T1
.1
330K
14
1
3
9
11
2
4
8
10
13
5
7
6
12
4066
.001
T2
22 uF
.1
.001
F1
F2
T1 = 10 bifilar turns FT37-43
T2 = 1K : 8 ohm AF transformer
Failed Experiment - DO NOT BUILD
4066 = MAX4066CPD+

A 4066 experiment that was a total failure. It is both humbling and useful to show your failures and not just the good fruit. This circuit had hum, noise and low output. The input transformer was a bifilar type, which was really cool.



The breadboard of the 4066 Concept schematic shown above.

74HC4053N
L8D0D5 13
UnG0838D
MAXIM
MAX4066CPD
+0822

The DIP IC switches used as product detectors in the K7LR memorial receiver experiments.

My work bench during some final experiments for this project.

QRP SWL HOMEBUILDER

Amateur and Short Wave Radio Electronics Experimenter's Web Site

---

K7LR MEMORIAL RECEIVER VFOs

This web page is a supplement to the K7LR Memorial Receiver Experiments Web Page

14 MHz VFO Circuit

Figure 1


12.22 V
.001
C0G
L78L05
Bottom
1K
5.00 V
.001
C0G
.1
100
T1
+
22 uF
100
.1
1N4148
1N4148
L2
22
5
10 pF
C0G
100K
CV
Q3
d
g
s
.1
270
7 MHz
Tune
10-108 pF
air variable
Band-edge
4-12 pF
air variable
15 pF
COG
5 pF
C0G
470K
Q1
d
g
s
10 pF
C0G
1M
Q2
d
g
s
51
RX
L1
25
5
.001
C0G
390
100 uH
68 pF
COG
12 pF
NPO
18 pF
NPO
12 pF
NPO
CX
Tunes 7.000 - 7.068 MHz
doubler
14 MHz

L1 = 6.1 uH = 36t on a T68-6 toroid. Tap at 25 and 5 turns. (used 26 AWG)
Q1 = Q2 = Q3 = J310
100 uH RFC that I used was wound as follows: 38t on a FT50-61 ferrite toroid
T1 = 10 trifilar turns on a FT37-43 L2 = 2 uH = 22t on a T50-6; tap @5t
CV = 6.0-50 pF trimmer capacitor
RX = 470 ohms

Figure 1 is the 14 MHz VFO used to switch (clock) the CMOS switch product detector. The tuning range can be easily changed by adjusting capacitor CX. As shown, the the tuning capacitor has a frequency range of about 68 Hz. If you decrease CX to 47 pF, the tuning range increases to around 99 Hz. Increasing CX to 100 pF gave about a 40 Hz tuning range. When you use a larger tuning range, fine tuning can become difficult. A geared reduction dial is one possible solution. For simplicity, I prefer to just keep the tuning range low as reasonably possible and use a big knob on the main tuning variable capacitor. Even the 68 Hertz tuning range shown can prove difficult for fine tuning. As experimenters, we are continually problem solving. Choose the tuning range and/or methods which suit your personal needs.

The base 7 MHz oscillator is doubled since a D flip flop is used to clock the CMOS switch product detector. This oscillator has low harmonic content and this is important for suppressing the 7 MHz fundamental frequency and its harmonics in the frequency doubler. Some astute builders may even match the two diodes used in the doubler. Diode matching is discussed on this page. CV tunes very sharply and the output at Q3 is a clean sine wave. This in turn provides a well balanced square wave at each output of the D flip-flop. The Q3 output voltage was measured at -0.46 dBm (0.6 volts peak to peak into 50 ohms).

Choosing Capacitor Values

There are a number of ways to determine the capacitor values required to tune your VFO L-C tank circuit. It is pretty much essential to have a frequency counter and nice perhaps, to own a capacitance meter. Main tuning capacitors are typically harvested from an old radio or from the junk box. Its tuning range could be anywhere from 30 to 300 pF, or more. To limit the tuning range of this variable capacitor, normally you parallel a fixed-value capacitor and then series connect it to the top of L1 with a small, fixed-value capacitor. I performed this task entirely by trial an error using a frequency counter connected to the collector of Q2. Some fixed value NP0 or C0G capacitors plus a small trimmer capacitor are also required for tuning and to set the lower band edge respectively. Finding the right combination of capacitor values is painstaking, but with practice, gets easier. Once you have the basic capacitor values sorted out and your tuning range set, frequency stability experiments are then performed. This is known as VFO temperature compensation. Some times temperature compensation can be achieved by finding the right combination of NP0 and C0G capacitors. Additionally some negative or positive temperature coefficient capacitors may have to be soldered in and tested. Your final capacitor leads should be short as practically possible to reduce stray lead capacitance and for mechanical rigidity. Temperature compensation is discussed on this web page.

A 7 MHz VFO Circuit for Diode Ring Product Detectors


Figure 2
+
22 uF
100
.1
T1
18
3
1KS
50
Ω
33
10 pF
C0G
d
g
s
Q2
1M
470
RX
connect to Q1 of Figure 1
Q2 = J310
T1 = 18t primary 3t secondary FT 37-43

If you want to build a simpler version of the K7LR memorial receiver, a diode ring mixer may be substituted for the digital switch. The VFO requires modification as it will be run at 7 MHz. A different buffer is used and the Q2 to Q3 frequency doubler circuit is excluded. The diode ring product detector version is very nice. You could use a Mini-circuits TUF-1 , SBL-1 or alternate, or perhaps homebrew your own.

In Figure 2 is a VFO buffer configured to drive a 50 ohms input impedance, 7 dBm level, diode ring mixer. Change Rx to change the output voltage. With RX at 470 ohms, the output was somewhere around 5 dBm. This is useable for many situations. If you want exactly 7 dBm, the AC peak to peak voltage with a **51** ohm load resistor connected to the 3 turn link should be 1.43 volts. Adjust RX to achieve this voltage in your oscilloscope.


Diode Ring Product Detector
7 MHz
VFO
20t FT37-43
170 uH
LO
RF
AF
+
BP
Filter
.1
47 uF
51
note capacitor
polarity

Note that if you build a diode ring product detector receiver version using the simple W7EL low pass termination network, the polarity of the 47 uF electrolytic capacitor will need to be changed as shown.

Key goals of this website include providing ideas, basic support and encouragement. I am delighted when builders make their own stuff and not copy my circuits. This is why we homebrew; to create, explore and share. Mike, K7LR did all of these very well.

QRP SWL HOMEBUILDER

Amateur and Short Wave Radio Electronics Experimenter's Web Site

---

Photography Links

Nikkor 50mm lenses

HENRI CARTIER-BRESSON - shot a lot with 50mm - video to watch over and over

The genius of photography -- BBC4 series about the history of photography

http://www.freestylephoto.biz

BASIC ANTENNAS

Understanding
Practical Antennas and Design

Includes Details of Easy-to-Build Antennas!

Joel R. Hallas, W1ZR


NEC-4 filename: 1r0at120
Japan
Asia
Europe
Africa
South America

Published by: ARRL The national association for AMATEUR RADIO

Table of Contents

Chapter 1 Introduction to Antennas
Chapter 2 The Half-Wave Dipole Antenna in Free Space
Chapter 3 The Field From a Dipole Near the Earth
Chapter 4 The Impedance of an Antenna
Chapter 5 Transmission Lines
Chapter 6 Making Real Dipole Antennas
Chapter 7 The Field From Two Horizontal Dipoles
Chapter 8 The Field From Two Vertical Dipoles
Chapter 9 Transmission Lines as Transformers
Chapter 10 Practical Two Element Antenna Arrays
Chapter 11 Wideband Dipole Antennas
Chapter 12 Multiband Dipole Antennas
Chapter 13 Vertical Monopole Antennas
Chapter 14 Arrays of Vertical Monopole Antennas
Chapter 15 Practical Multielement Driven Arrays
Chapter 16 Surface Reflector Antennas
Chapter 17 Surface Reflector Antennas You Can Build
Chapter 18 Antenna Arrays With Parasitically Coupled Elements
Chapter 19 The Yagi-Uda or Yagi, Parasitically Coupled Antenna
Chapter 20 Practical Yagis for HF and VHF
Chapter 21 Log Periodic Dipole Arrays
Chapter 22 Loop Antennas
Chapter 23 Loop Antennas You Can Build
Chapter 24 Antennas for Microwave Applications
Chapter 25 Vehicle Antennas
Chapter 26 Antenna Measurements
Appendix A Getting Started in Antenna Modeling with *EZNEC*
Appendix B Using Decibels in Antenna Calculations
Index

About the ARRL

The national association for Amateur Radio

The seed for Amateur Radio was planted in the 1890s, when Guglielmo Marconi began his experiments in wireless telegraphy. Soon he was joined by dozens, then hundreds, of others who were enthusiastic about sending and receiving messages through the air—some with a commercial interest, but others solely out of a love for this new communications medium. The United States government began licensing Amateur Radio operators in 1912.

By 1914, there were thousands of Amateur Radio operators—hams—in the United States. Hiram Percy Maxim, a leading Hartford, Connecticut inventor and industrialist, saw the need for an organization to band together this fledgling group of radio experimenters. In May 1914 he founded the American Radio Relay League (ARRL) to meet that need.

Today ARRL, with approximately 150,000 members, is the largest organization of radio amateurs in the United States. The ARRL is a not-for-profit organization that:

- promotes interest in Amateur Radio communications and experimentation
- represents US radio amateurs in legislative matters, and
- maintains fraternalism and a high standard of conduct among Amateur Radio operators.

At ARRL headquarters in the Hartford suburb of Newington, the staff helps serve the needs of members. ARRL is also International Secretariat for the International Amateur Radio Union, which is made up of similar societies in 150 countries around the world.

ARRL publishes the monthly journal *QST*, as well as newsletters and many publications covering all aspects of Amateur Radio. Its headquarters station, W1AW, transmits bulletins of interest to radio amateurs and Morse code practice sessions. The ARRL also coordinates an extensive field organization, which includes volunteers who provide technical information and other support services for radio amateurs as well as communications for public-service activities. In addition, ARRL represents US amateurs with the Federal Communications Commission and other government agencies in the US and abroad.

Membership in ARRL means much more than receiving *QST* each month. In addition to the services already described, ARRL offers membership services on a personal level, such as the ARRL Volunteer Examiner Coordinator Program and a QSL bureau.

Full ARRL membership (available only to licensed radio amateurs) gives you a voice in how the affairs of the organization are governed. ARRL policy is set by a Board of Directors (one from each of 15 Divisions) elected by the membership. The day-to-day operation of ARRL HQ is managed by a Chief Executive Officer.

No matter what aspect of Amateur Radio attracts you, ARRL membership is relevant and important. There would be no Amateur Radio as we know it today were it not for the ARRL. We would be happy to welcome you as a member! (An Amateur Radio license is not required for Associate Membership.) For more information about ARRL and answers to any questions you may have about Amateur Radio, write or call:

ARRL—The national association for Amateur Radio
225 Main Street
Newington CT 06111-1494
Voice: 860-594-0200
Fax: 860-594-0259
E-mail: **hq@arrl.org**
Internet: **www.arrl.org/**

Prospective new amateurs call (toll-free):
800-32-NEW HAM (800-326-3942)
You can also contact us via e-mail at **newham@arrl.org**
or check out *ARRLWeb* at **http://www.arrl.org/**

Chapter 1

Introduction to Antennas



This impressive collection of antennas is part of the ARRL station, W1AW

Contents

So What is an Antenna? 1-2

Concepts You'll Need to be Familiar With 1-5

So What is an Antenna?

For something so simple to check out, and often so simple to make, an antenna is remarkably difficult for many people to understand. That's unfortunate, because for many radio systems the antenna is one of the most important elements, one that can make the difference between a successful and an unsuccessful system.


UBA0001
Larger Electrical Signal
Strong Acoustic Wave
Small Electrical Signal
Weak Acoustic Wave
Audio Amplifier
Input Transducer (Microphone)
Output Transducer (Loudspeaker)

Fig 1-1 — Illustration of transducers changing one form of energy into another.


AF Transducer
TR Switch
Transmit Amplifier
Receive Amplifier
Modulator
Demodulator
AF Oscillator
Pulse Generator
Receive Processor
Display
UBA0002
Antenna
TR Switch
Transmit Amplifier
Receive Amplifier
Modulator
Demodulator
RF Oscillator
Pulse Generator
Receive Processor
Display

Fig 1-2 — At (A), simplified system diagram of a sonar system. At (B), simplified system diagram of a radar.

How Can You Picture Antennas?

Perhaps an analogy from *The ARRL Antenna Book* will help. You are familiar with sound systems. Whether represented by your home stereo or by an airport public address, sound systems have one thing in common. The system's last stop on its way to your ears is a *transducer*, a device that transforms energy from one form to another, in this case — a loudspeaker. The loudspeaker *transforms* an electrical signal that the amplifier delivers into energy in an acoustic wave that can propagate through the air to your ears.

A radio transmitter acts the same way, except that its amplifier produces energy at a higher frequency than the sound you can hear, and the transducer is an *antenna* that transforms the high-frequency electrical energy into an electromagnetic wave. This wave can propagate through air (or space) for long distances.

For some reason, perhaps because of our familiarity with audio systems or because you can actually hear the results in your ears, it seems easier to grasp the concept of the generation and propagation of acoustic waves than it is to understand the generation and transmission of radio waves.

The audio transmitter analogy can be continued in the receiving direction. A *microphone* is just another transducer that transforms acoustic waves containing speech or music into weak electrical signals that can be amplified and processed. Similarly, a receiving antenna captures weak electromagnetic waves and transforms them into electrical signals that can be processed in a receiver. **Fig 1-1** shows a system or block diagram of a sound system with transducers (loudspeaker and microphone) at each end.

Many of the phenomena that act upon acoustic waves also occur with electromagnetic waves. It is not an accident that a parabolic reflector radar antenna looks very much like a parabolic eavesdropping microphone, or that sonar and radar operate in the same fashion. *Sonar* relies on acoustic waves propagating through water to find and reflect back from underwater objects, such as submarines or schools of fish. Similarly, *radar* sends out electromagnetic waves through space, listening for signals reflected back from objects such as aircraft, space vehicles or weather fronts. **Fig 1-2** shows simplified system



Fig 1-3 — A wire immersed in the magnetic field of a permanent magnet. At A, if everything is static there is no current flow in the wire. At B, if you move the wire up and down within the field, the wire experiences a changing magnetic field and current is induced to flow.



(A) Wire with Current Coming Out of Page Magnetic Field Wraps Counter-Clockwise

(B) "Right-Hand Rule" Direction of Magnetic Field Along Curved Fingers

Fig 1-4 — Direction of magnetic field around a wire.

diagrams of radar and sonar systems.

While we're mentally picturing antennas, perhaps an even better analogy than acoustic waves is to compare electromagnetic waves of light to those of radio signals. Light waves propagate through space using the same mechanisms and at the same speed as radio waves. Similar parabolic shapes can reflect and focus both light and radio waves. Light needs a polished mirror as a reflector, such as the mirrored reflector in your flashlight or car headlight. I will sometimes draw on your appreciation of light reflection as I discuss some types of antennas.

What's an Electromagnetic Wave?

An *electromagnetic wave*, as the name implies, consists of a combination of the properties of both electric and magnetic fields.

Static Electric and Magnetic Fields

You are no doubt familiar with magnetism and electricity from everyday experience. One kind of magnetism and electricity is the *static* form. Static electricity is a collection of positive or negative charges that are at rest on a body until discharged by a current flow. This happens to your body when you walk across a rug on a dry day. In climates where the humidity is very low, particularly during the winter, your body can accumulate a charge, perhaps making your hair stand up. That lasts until you discharge the accumulation by touching a grounded object, such as a screw on a light switch plate, or even the long-suffering dog's nose. Then the charge is dissipated sometimes quite dramatically— with a big spark.

Similarly, a static magnetic field exists around a permanent magnet. You can observe the effect of magnetism on a compass needle or even on a screwdriver.

Static electric and magnetic fields do not result in electromagnetic waves. It is only when a magnetic or electric field is *changing* that you can have electromagnetic radiation. You can visualize the effect by considering some other things that make use of electric and magnetic fields. **Fig 1-3** shows a wire immersed in the magnetic field of a permanent magnet. If everything is static (Fig 1-3A) there is no current flow in the wire. If you change the magnetic field at the wire by moving the wire up and down within the field (Fig 1-3B), the changing magnetic field causes a current to flow. This is how an electric power generator transforms mechanical energy into electrical energy.

You could cause the same effect by keeping the wire in one position and changing the magnetic field around it. You could do this by moving the magnet, but more interestingly you could replace the permanent magnet with an electromagnet and change the current in it. This is just a *transformer*, something with which you are familiar. When you change the current in the transformer winding, you can move between electric and magnetic fields.

Direction of Fields

Both magnetic and electric fields act in particular directions. A magnetic field acts around the conductor carrying the current. The convention for its direction is that if positive current is flowing in a particular direction, the magnetic field will go around the wire, as shown in **Fig 1-4A**. This can be remembered by calling on the *right-hand rule*. This rule says that if you hold a current carrying wire in your right hand, with the current going in the direction of your thumb, the magnetic field will be in the direction of your curled fingers, as shown in Fig 1-4B.

Electric fields act between areas

with charges of different sense. That is, an area with excess electrons is said to have a negative charge, while an area having a deficiency of electrons has a net positive charge. The electric field goes from the positively charged area to the negatively charged area, as shown in **Fig 1-5**.

Changing Fields in Space

The key to electromagnetic waves is to understand that a changing current in space will cause a changing electric field. The changing electric field will in turn induce a changing magnetic field in space and the two will propagate outward from the source, continuing to the end of the universe.

This surprising fact was predicted by a number of forward-looking scientists, notably James Clerke Maxwell in his *Treatise on Electricity and Magnetism*, published in 1873, written without the benefit of Maxwell actually being able to experience the phenomenon. Maxwell's famous equations defined the relationships between currents and fields in a concise way that remains the basis for all work in the field.

In the following decade, Heinrich Hertz, a professor of physics at Germany's Karlsruhe Polytechnic University, used an electric spark to generate electromagnetic waves. He was able to measure their wavelength and velocity, reinforcing Maxwell's theoretical work.

How Do You Make an Electromagnetic Wave?

As the previous discussion describes, it is conceptually easy to generate an electromagnetic wave. All you need to do is to cause a changing current in a conductor and a wave will propagate outward to the end of the universe. Thus if you were to listen carefully to a radio when you discharge your finger against the wall switch plate, you would have a sudden increase in current and a relatively short-duration electromagnetic wave propagating from your finger.

The resulting wave would not be very strong, nor would it be very useful. It carries little information, although arguably it could be used to measure the dryness of the carpet, or perhaps the location of your finger, but both are a bit of a stretch. The US Federal Communications Commission (FCC) classifies this kind of radiation as an *unintended emitter*. The generator of an unintended emitter is required not to interfere with licensed users of the radio spectrum.

Electromagnetic waves of this sort are generated every time you turn on a light switch or when the spark plugs in your car fire as the engine turns. In these cases, rather than trying to make antennas, the responsible user attempts to *avoid* the propagation of electromagnetic waves — by shielding the engine compartment or by keeping his hands in his pocket as he walks on dry rugs.

So What if You Do Want to Send Out a Wave?

If you really want to transmit a radio signal, you likely would like to send it on a particular frequency. Note that this is different than the wave resulting from a spark, as used in very early transmitters. Sparks, or other fast changing pulses, contain frequency components across a wide radio spectrum.

A modern transmitter starts with an electrical current that is changing at a particular frequency. Causing that current to flow through a conductor will result in an electromagnetic wave that varies at that frequency. The frequency will be maintained as the wave propagates from the conductor. If the signal is strong enough as it reaches a receiving antenna, a receiver tuned to that frequency will be able to receive the signal and decode any information that was embedded in the signal — You have radio!

This Sounds Simple — What's the Big Deal?

As with many things, a conceptually simple concept only gets complicated when you try to make it happen in a really useful way. There are really only two basic practical issues that arise when dealing with antennas:

- How do you get the antenna to accept the power from the transmitter, or give it up to a receiver?
- How do you cause the radiation from a transmit antenna to go in the direction you want, or equivalently, how do you get a receive antenna to accept radiation (only) from a particular direction?


UBA0005
Region Deficient in Electrons is Positively Charged
Direction of Electric Field
Region with Excess Electrons is Negatively Charged

Fig 1-5 — Direction of electric field between two charged areas.

There are many peripheral but perhaps equally important issues, such as, "How do you keep the antenna structure from falling down?" In this book, I will focus on the electrical issues and leave the structural issues to mechanical and civil engineers, who have the tools to deal with such matters.

So Why Don't All Wires With Changing Current Radiate?

Well, in fact, they all do. In most cases, however, circuits have a return wire to complete the circuit close to the first wire. Since both these wires carry equal current, they will both radiate equally, but in opposite phase. The net radiation is thus the sum of the radiation from the two wires. But since they are equal and opposite, the net fields are almost zero — except in the region between them. Thus a key requirement for a conductor to be an efficient radiator is that it should not have a return path in close proximity. In this context, *close* means a small fraction of a wavelength at the frequency of the current. A wavelength is the distance a wave travels during the time of one cycle.

Some Concepts You'll Need to be Familiar With

This book is intended to provide a basic understanding of antennas. It would be nice if you could just start here, but you do need to have just a bit of background in some concepts from electronics and radio to make it all come together. These will be introduced from time to time, with the hope that if they are not familiar, you will go back to some of your earlier reference books to review the topic. To start with, you should clearly understand the following terms.

Frequency

This is the rate at which an alternating current waveform or signal goes through a full cycle, from zero voltage to maximum, back to zero, to voltage minimum and then back to zero. The basic unit is hertz (Hz). A signal with a frequency of 1 Hz completes one cycle every second. You will generally be dealing with signals at higher frequencies and the number of Hz will generally be preceded with a modifier indicating that the value is some multiple of Hz. The usual ones you will see are:

- kilohertz (kHz), thousands of Hz
- Megahertz (MHz), millions of Hz, or thousands of kHz
- Gigahertz (GHz), billions of Hz, or thousands of MHz.

Thus a signal with a frequency of 3,600,000 Hz is the same as one of 3600 kHz or 3.6 MHz.

Period

Period is defined as the time it takes for a waveform to make a complete cycle. The basic units are seconds. If a waveform makes F cycles in one second, the time it takes for a single cycle is just 1/F. Thus, in the example above, a 3.6 MHz signal would have a period of 1/3,600,000, which is 0.000000278 seconds. I will use the multiplier of *microseconds* to describe events in millionths of seconds, so the period would be described as 0.278 microseconds, often written as 0.278 μsec, where the Greek letter μ is short for "micro."

Wavelength

Radio signals travel at a finite speed. In free space, or in the Earth's atmosphere, they travel at the same speed as light. Light travels at about 186,000 miles per second, or 300,000,000 meters per second in space. I will generally work in units of meters per second to conform to the practice of most people working in the radio field.

Wavelength is defined as the distance a wave travels during one cycle. In the above example, during the 0.278 μsec that the signal takes to complete a cycle, it will travel 0.000000278 seconds × 300,000,000 meters per second or 83.3 meters. That is the wavelength of a signal at 3.6 MHz. I will generally follow industry practice and use the Greek letter lambda (λ) to indicate a wavelength. Thus, if something were two wavelengths long, you would say 2 λ. For half a wavelength, you would say λ/2.

A signal can be described equally well by either its frequency or its wavelength. It may be of interest to note that before the then-new FCC started assigning the spectrum by frequency around 1930, the use of wavelength was more common. Many radios of the period had their dials labeled in both frequency and wavelength, since it wasn't clear which term would become the more common system of signal definition. Common usage now is to define particular signals by frequency, while using the approximate wavelength to indicate a band of frequencies assigned to a particular service. Thus an 83.3-meter signal is one of a number of frequencies in the "80 meter" amateur band.

Chapter 2

The Half-Wave Dipole Antenna in Free Space



Radiation pattern of a dipole in free space.

Contents

The Half-Wave Dipole....2-2
So How Does a Dipole Work?....2-3
Where Does the Power Go?....2-4
Antenna Analysis Tools....2-5
Polar Plots....2-5
Which Way is Up?....2-6
Review Questions....2-6

The Half-Wave Dipole

It's tempting to start out looking at a tiny radiating element consisting of a short conductor with an alternating current flowing in it. Then you could consider all other antenna structures as collections of such *mini-antennas*, each piece with a slightly different location, current magnitude and current phase. The radiating electromagnetic field results from the summation of all the fields radiated by all the mini-antennas. In fact, that's the way many antenna-analysis software programs analyze the performance of complicated antennas.

However, I won't start there because it's hard to imagine just how you can make those mini-antennas work without considering all the interconnecting wires, and these interconnecting wires may well be more significant than the antennas themselves. I will thus start with an examination of an antenna that will actually work and is frequently encountered — the half wave ($\lambda/2$) dipole.[1]



Fig 2-1– Half-wave ($\lambda/2$) dipole.

A $\lambda/2$ dipole antenna is formed by having a conductor that is electrically half a wavelength long at the frequency that will be transmitted or received. Here, λ represents the distance the electrical signal would travel down the wire during the time of one cycle of the sine wave alternating current (ac) signal from a generator at the operating frequency f_0. I will discuss the antenna first as a transmitting antenna and later discuss receiving applications. This antenna is a good place to start because:

- The $\lambda/2$ dipole is frequently used as an antenna in many real applications.
- Many other antennas are made up of combinations of $\lambda/2$ dipoles in various configurations.
- The $\lambda/2$ dipole is a reference standard for comparison of the performance of other antennas.

The layout of a $\lambda/2$ dipole is shown in **Fig 2-1**. The circle in the center represents a generator that generates a signal at the operating frequency f_0. The total length of the conductor from end-to-end is approximately $\lambda/2$.

The distance of one wavelength in free space is just the speed of light multiplied by the time it takes to make a complete *cycle*. The time for one cycle is the waveform's *period* or $1/f_0$. Thus a wavelength in free space is given by the following formula:

$\lambda = c/f_0$

Here c is the speed of light and f_0 is the frequency of the signal that generated the wave. There are many units that can be used; however, it is important that they be consistent. For example, if c is in meters per second, f_0 is in Hertz (cycles per second), then λ will be in meters. For example, for a frequency of 10 MHz, you have

λ = 300,000,000 meters per second ÷ 10,000,000 Hertz = 30 meters.

Note, for radio work, it is convenient to use a value for c of 300 million meters per second, and f_0 in MHz, which neatly cancels out the six zeros in numerator and denominator.

λ = 300 million meters per second ÷ 10 MHz = 30 meters.

So How Does a Dipole Work?

The key to understanding how a dipole works is to look at the boundaries or endpoints, where some conditions exert themselves. Physicists would call these *boundary conditions* because they occur at the boundary between regions. In this case you have a boundary between a conducting wire and free space at each end of the dipole. The condition is that there can be no current flow at the open end of a conductor — there's no place for current to go! If the generator is delivering any power to this antenna, and it is, then λ/4 back from the place where the current is zero, the current must be at its maximum, as shown in **Fig 2-2**.



Fig 2-2 – Current along a λ/2 dipole.



Fig 2-3 – Voltage along a λ/2 dipole.

Similarly, with no current flowing at the end of the antenna, the voltage must be at its maximum. Again, the minimum voltage is found λ/4 back from the place where it is maximum, as shown in **Fig 2-3**. That would be at the center of the dipole, λ/4 from each end, just where I've hooked up the generator.

The power the generator puts into the antenna will (you hope) be transformed from an electrical signal into a radiated electromagnetic wave. The antenna power will just be the current at the center multiplied by the voltage at the center, which is, of course, the current and voltage supplied by the generator. Ohm's Law, just as in any other circuit, defines the relationship between the voltage and current. Note that the feed point of the dipole is just an electrical circuit, with connections going to the antenna from the generator. In *free space*, away from ground (more about free space later) you find that the voltage at that point is just 73 times the current. Thus the generator sees a load that looks like a resistor of 73 Ω = E/I. This value can be rather strenuously derived, but it is much easier to imagine measuring it![2]

Where Does the Power Go?

The amount of power that the generator delivers is the same that it would deliver into a resistor with a resistance of 73 Ω. This forms a convenient boundary between the circuit portion of a system and the radiating-field portion of the system. The generator can be designed to deliver power to a 73 Ω resistor and that power (less any losses) will be transformed into a radiated field by the changing currents flowing on the dipole. This resistance is called the *radiation resistance*.

The radiating field leaves the dipole in a three-dimensional fashion that is a little difficult to describe fully in words. Outgoing electrical and magnetic fields created by the antenna are perpendicular to each other, and each field is also perpendicular to the direction in which a wave travels away from the antenna. The overall field strength in any direction is proportional to the magnitudes of the two field components. This results in a radiating field that leaves with maximum strength in a direction perpendicular to the wire making up the dipole. The field strength is reduced as you move around the dipole towards the direction of the ends, at which point there are neither magnetic nor electric field lines. This is roughly shown in **Fig 2-5**.

A more precise representation of the field strength in each direction as you move from one end half way around the antenna is shown in **Fig 2-6**. Here I have plotted both the relative strength either of the electric or of the magnetic field (since they are proportional), as well as the power, which is proportional to the square of the field strength.



Fig 2-4 Electric and magnetic fields surrounding a λ/2 dipole.



Fig 2-5 – Direction of radiation from a λ/2 dipole.



Fig 2-6 – Calculated relative field strength and power.

Antenna Analysis Tools

It is quite possible to manually calculate the field strength from antennas, particularly simple ones such as a dipole. Such calculations require math skills beyond the scope of this book. Fortunately, through the use of computer modeling, you can avoid such efforts. Computer modeling is also of great benefit for the analysis of more complex structures, providing convenient, easy-to-use output formats.

There are a number of such programs available. I will use *EZNEC*, a program written by Roy Lewallen, W7EL, that is easy to use, and which, at this writing, is available in a limited size free demonstration version on his Web site, **www.eznec.com**. A description of the basics of how to use *EZNEC* is provided in Appendix A.

Polar Plots

While a representation as shown in Fig 2-6 can be used to describe the strength of the fields or the power in a particular direction, it is more common to show the information in something called a *polar plot*. This kind of plot represents the intensity in a particular direction by the length of a line, at any angle from the center of the plot to the pattern. **Fig 2-7** is a polar plot of the radiation from a dipole in free space as a function of the azimuth angle with 0° being perpendicular to the antenna. This is one of the outputs from *EZNEC* and you will be using this view extensively throughout the book. The relative power is generally shown in *decibels* (dB), a convenient logarithmic representation that makes it easy to add up system gains and losses. If you are not familiar with decibels, see Appendix B.

Fig 2-8 is a representation of the field strength as a function of elevation angle, taken at the azimuth angle of maximum output. Note that because you are in free space and thus have not considered any ground effects, the elevation pattern is constant. You will see quite a difference when you get "down to Earth" in the next chapter!



Fig 2-7– Modeled relative power in decibels (dB) as a function of azimuth angle on a polar plot.



Fig 2-8 – Modeled relative power vs elevation angle.

Which Way is Up?

An antenna in *free space*, such as we have been discussing, is interesting because you don't need to consider the interactions between the antenna and anything else around it. In the extreme case, your antenna is considered to be the only object in the universe. While this might be simple to discuss, it is very hard to actually measure — Where would you stand to make a measurement?

Polarization

In real life many antennas are near, and occasionally even under, the Earth. I will discuss how this affects antenna operation in later chapters. However, it is important at this point to define *antenna orientation*. A dipole antenna constructed near the Earth could be oriented in a number of ways. The extreme cases, and those most often encountered, are with the dipole conductors in a straight line, either parallel to, or perpendicular to, the Earth's surface.

If the dipole is oriented parallel to the Earth, the electric field would also be parallel to the Earth. As seen by an observer on the ground, both the antenna and the electric field would appear to be horizontal. Such an antenna is said to be *horizontally polarized*. Not too surprisingly, a dipole perpendicular to the Earth's surface is said to be *vertically polarized*.

The polarization direction of an antenna is important for a number of reasons:

- Antennas that are horizontally polarized will not receive any signal from a vertically polarized wavefront, and vice-versa.
- Antennas that are horizontally polarized have performance characteristics very different from those vertically polarized when both are near the ground.

Either polarization can be effectively used; however, it is important to understand the differences so that you can make good use of their distinct properties. Note also that there is nothing that says an antenna can't be oriented in-between horizontal and vertical. Such an antenna is said to have *skew polarization*. It can be considered a combination of horizontal and vertical polarization, with part of its power associated with each, depending on how far it is tilted.

It is also possible to have an antenna that generates a wavefront that shifts in polarization as it leaves the antenna, continually changing in space. This is called *circular polarization*, and I will discuss it, as well as skew polarization, in applications later in this book.

Notes

[1] See Chapter 1.

[2] J. Kraus, W8JK, *Antennas*, McGraw Hill Book Company, New York, 1950, pp 143-146.

Review Questions

2.1. Describe circumstances for which a "free space" dipole model can represent a real antenna.

2.2. Calculate the approximate length of $\lambda/2$ dipoles for 0.1, 1, 10, 100 and 1000 MHz.

2.3. Discuss applications for which a horizontally polarized dipole might be most appropriate. Repeat for a dipole with vertical polarization.

2.4. Consider an amplifier with 20 dB of gain, matching networks at input and output each with a loss of 1 dB and an antenna with a gain of 5 dB. What is the total system gain? (See Appendix B, if needed.)

2.5. If an input signal of 0 dBm is applied to that system, what is the output radiated power in dBm, mW?

Chapter 3

The Field From a Dipole Near the Earth


Wire length in feet = 468/f(MHz)
Cut long. Trim for best
SWR at transceiver
50 Ω
Coax
HF Transceiver
Lightning
Arrestor
Station Earth Ground

Inverted V dipole over ground connected to radio station.

Contents

Phase of an Electromagnetic Wave 3-2
What is the Effect of Ground Reflections? 3-3
Chapter Summary 3-7
Review Questions 3-7

I have discussed the way a dipole works if far removed from the Earth. While this is a useful place to begin, and may be directly applicable for space communications, I now want to discuss the very real case of antennas near the Earth. The Earth has two major effects on antenna performance and behavior:

- Reflections from the Earth's surface interact with radiation leaving directly from the antenna, resulting in a change to the direction at which that radiation seems to leave the antenna.
- Proximity to the Earth may change the electrical parameters of the antenna, such as its feed-point *impedance*, as I'll get into later.

You must first grasp the fundamental concept of the phase of a wavefront.

Phase of an Electromagnetic Wave

In the last chapter, when I spoke of the strength of an electromagnetic wave, or its parts — the electric and magnetic fields — I was talking about the magnitude of an ac sine wave at the frequency of the generator driving the antenna. Just as when you talk about a 120 V ac household circuit, you recognize that 120 V is the root-mean-square (RMS) or effective value of the sine wave. The actual voltage varies with time at a frequency of 60 Hz, as shown in **Fig 3-1**.



Fig 3-1 – Voltage of a 120 V ac sine-wave signal as a function of time.

If you sample the voltage at various times, you will measure an instantaneous voltage anywhere from –170 to +170 V. If you were to combine two such signals in a circuit that added the voltages, the result could range anywhere between –340 to +340 V, depending on the relative *phase* of the two signals. If you were to add two signals of the same phase, you would end up with twice the voltage, as shown in **Fig 3-2**.



Fig 3-2 – Resultant voltage of two signals of Fig 3-1 adding together versus time.

On the other extreme, if one signal were at its maximum positive level at exactly the same time as the other is at its maximum negative level, the resulting net voltage would add up to 0 V. In other words, the signals would *cancel* each other. **Fig 3-3** shows a signal whose phase is exactly out-of-phase with the signal in Fig 3-1.



Fig 3-3 – Voltage of a second 120 V 60-Hz ac signal opposite in phase to Fig 3-1.

Electromagnetic waves travel from an origin to a destination via multiple paths, especially through the ionosphere, and as a consequence they exhibit all sorts of variations. Depending on the relative phase of the signals at the reception point, they could add, or they could subtract from each other. Consider the case of only two signals arriving at a receiver with exactly the same strength. They can combine to produce a signal that is somewhere between twice the level of each signal by itself, down to a level of zero, where they completely cancel each other. *Fading* and signal enhancement can occur for many different reasons.

What is the Effect of Ground Reflections?

A signal transmitted in any direction from an antenna near the Earth will have a direct path, and it will also have a path that results from a reflection from the surface of the Earth. Consider a simple case to start. Assume that you are an observer located some distance from the antenna such that the Earth between you and the antenna looks like it is flat. Assume that the antenna is mounted over perfectly conducting ground. This is depicted in **Fig 3-4**.

For any elevation or *takeoff* angle there is a direct path from the antenna to the observer, and there is also a reflected path. These two paths have different lengths, with the reflected path always longer than the direct path. The difference in length will depend on how high the antenna is above the ground and the elevation angle. Note that this *flat Earth* model falls apart for the case of zero elevation because there can be no reflection, but ignore that extreme case for the time being.

As the downward wave strikes the Earth, the combination of the incident wave and reflected wave cannot create an electric field at the surface of the ground since the fields can't exist in a perfectly conducting ground medium — they are, in essence, shorted out by the ground. For a horizontally polarized antenna in Fig 3-4 the reflected wave therefore must be out-of-phase with the incident wave. I have indicated the polarization of a horizontally polarized antenna with a "+" sign. This represents the tail of an arrow (or vector) heading into the paper.

Interestingly, and importantly, a vertically polarized wave must have the reflected and incident waves in-phase with each other because opposite ends of the field are at the Earth's surface when they are in-phase.

Note that for any takeoff angle and height, you could calculate the difference in path length using plane geometry and trigonometry. By knowing the difference in path length, the signal frequency and the speed of propagation (which is the same as the speed of light in air), you could easily compute the phase difference due to the different path and thus the resultant amplitude. Fortunately, you can also use antenna-modeling tools to determine the same thing.

You also can imagine that the reflected wave comes from another antenna that is located under the earth the same distance that the real antenna is above the earth. This is called an *image antenna* and isn't real, but the path length difference is a bit easier to visualize and calculate. Again, the two antennas are in-phase for the case of vertically polarized antennas and out-of-phase for horizontal ones. The configuration is shown in **Fig 3-5** for horizontal antennas.

Note the point of the arrowhead on the image antenna, indicting opposite polarity from the real antenna. The vertical antenna configuration is shown in **Fig 3-6**. The height is at the center of the antenna. Note that the antenna and its image have the same polarity for the vertical case.



Fig 3-4 – Illustration of additional path length (and thus phase delay) of reflected wave compared to direct space wave



Fig 3-5 — Image antenna concept for visualizing ground reflection. Note opposite polarity (180° phase shift) of image for horizontal polarization.

How Do The Numbers Add Up?

Knowing the phase of the reflected wave and the height of the antenna, you can thus determine the resultant phase of the direct and reflected signals as a function of height. This just means that you need to know the difference in path length in terms of wavelengths. For example, if the polarization is vertical, and the difference in path length is an odd multiple of a half wavelength, the signals will be out-of-phase and cancel at that angle. At other elevation angles, the difference may be an even number of half wavelengths and the signals will be the same phase and will add together. For horizontally polarized waves, it is just the reverse. Intermediate angles will have values in between these extremes.

You can determine the intensity of the combination of the two antennas by merely adding up the signals for each elevation and azimuth angle. Alternately, you could take advantage of the capabilities of an antenna-analysis program to do so, such as *EZNEC*, which I've mentioned previously in Chapter 2.

Dipole Over Typical Ground

As you would expect based on the earlier discussion, the elevation pattern of an antenna near the Earth will be quite different from one far removed from the Earth. This is all due to reflections from the Earth. If you move the antenna with the modeled uniform elevation shown earlier in Fig 2-8 from outer space down to ½ wavelength above ground (about 50 feet at this frequency), you will get the pattern shown in **Fig 3-7**, which compares the elevation pattern for a dipole ½ wave above both *perfect ground* and typical soil. First, consider the reflected wave. Remember for a horizontal antenna at this height the reflection is out-of-phase to start with. So ½ wavelength (180°) off ground gives a phase reversal at the reflection (another 180°) and one more ½ wavelength (180°) up towards the antenna result in an out-of-phase signal that cancels the upward going wave. Note also that the wave along the horizon cancels with the out-of-phase reflected wave, resulting in no radiation at 0° elevation.



Fig 3-6 — **Image antenna concept for visualizing ground reflection. Note same polarity (0° phase shift) of image for vertical polarization.**

Where Does the Power Go?

Nothing in the process I just described heats up or otherwise absorbs power, so the total power is redistributed to the areas that aren't reduced by the reflected signal. The areas with the most signal have a significantly stronger signal than they had in the free-space case, because the other areas have a significantly weaker signal. This effect is referred to as *ground reflection gain*. It isn't a real gain, such as you might get from an amplifier, but is more of a redistribution. On the other hand, if you want the signal to go where the signal combined with its ground reflection goes, it seems just like an amplifier to a distant receiver.

This redistribution happened to a certain extent with the dipole in free space described in Chapter 2. Note that because the radiation does not occur from the ends of the dipole, the main beam is about 2 decibels (dB) stronger than if it were a completely uniform *isotropic radiator* (a theoretical antenna that radiates equally in all directions). By tending to cancel the upward and horizontal signals, the maximum signal in the main beam is about 5.5 dB stronger than for the free-space case. This can be a real advantage if that's where you want the energy to go!

What About a Better Ground?

The model used for Fig 3-7 was an attempt to model typical dirt. For those who like the details, it assumed ground with a conductivity of 0.005 siemens/meter and a dielectric constant of 13. *EZNEC* allows you to enter the exact ground parameters for your location, or you can choose a perfect ground model. For perfect ground, imagine a few acres of gold foil under the antenna, heading off in all directions. The results are also shown in Fig 3-7. Note that the general shapes are similar. However, the upward cancellation is complete over perfect ground since the wave is completely reflected from a perfect conductor. The resulting ground reflection gain is a bit higher as a



Fig 3-7 — ***EZNEC* overlay of the broadside elevation pattern of a horizontal dipole antenna mounted a half wavelength over real ground (dashed line) compared to that same antenna over perfect ground (solid).**

Table 1

Lowest Elevation Peak and Ground Reflection Gain at Various Elevation Angles for Dipole Over Real Ground

Height Above Ground	*Center of Peak*	*Gain at 10°(dBi)*	*Gain at 20°(dBi)*	*Gain at 30°(dBi)*	*Gain at 90°(dBi)*
1/4 Wavelength	90°	–3.7	1.5	3.9	5.7
1/2 Wavelength	28°	2.55	6.71	7.38	–5.5
1 Wavelength	14°	6.86	5.8	–10.6	–5.6
2 Wavelengths	7°	5.9	6.9	–9.1	–4.2

consequence.

While perfect ground may be hard to come by, *saltwater* provides a close approximation. It is also possible to simulate almost-perfect ground over a region with a large expanse of bonded wire mesh, or similar structures.

What Happens at Different Heights?

If you examine again the geometry in Fig 3-4 or Fig 3-5, it's clear that the elevation pattern of a horizontal antenna is very dependent upon the height above ground. If the antenna is much lower than the ½ wavelength you have been looking at, a horizontal antenna will not have the upward direction energy cancelled, with the result that most of the energy heads upward. This is shown for the case of a λ/4 high dipole in **Fig 3-8**, which overlays the responses for three horizontal dipoles — ¼, 1 and 2 wavelengths high. Later in this book when I discuss how signals get from place to place, you'll discover that a low antenna can work well for medium distance communications.

As the height over ground increases, the patterns for a horizontally polarized antenna tend to get more complex, and you get an increased number of elevation angles with *nulls*. This is shown clearly in the case of a horizontal antenna a full wave above ground and for one that is two wavelengths above ground in Fig 3-8. Note that as the antenna height increases, the first radiation peak moves down to lower angles and each peak covers a narrow range of elevation before the next null. This results in gaps in elevation-angle coverage. A summary of the signal intensity for each case is shown in **Table 1**.

I haven't mentioned the azimuth pattern in a while, largely because not much happens as the antenna height is changed. Above the very lowest heights, it stays about the same. Compare **Fig 3-9**, a plot of the azimuth pattern of a horizontal dipole mounted 2 wavelengths above ground with that of the horizontal dipole in free space (Fig 2-7) and note the similarity.

How About Vertically Polarized Antennas?

So far I have been discussing horizontally polarized dipoles. I could have just as well started with antennas with vertical polarization near the ground. As noted in Fig 3-6, the geometry is the same, but the big difference is that the signal from the image is in the same phase as that from the antenna. This means that the signals add towards the horizon for perfect ground rather than having a null at 0° elevation. The elevation



Fig 3-8 — *EZNEC* overlay of broadside elevation patterns of a horizontal dipole mounted at three heights over real ground: 2 λ = solid line, 1 λ = dashed line, λ/4 = dotted line.



Fig 3-9 — *EZNEC* azimuth plot for a horizontal dipole mounted 2 λ above typical ground at the peak of the first elevation lobe (7°).

pattern of a ½ wave dipole whose bottom is 1 foot over perfect ground is shown in **Fig 3-10**, along with a plot of the same antenna mounted 1 foot over typical soil. Note that unlike the horizontal dipole, either vertical dipole radiates equally well at all azimuth angles, often an advantage for some types of systems such as broadcast or mobile radio. You can see very clearly in Fig 3-10 that even typical soil has a big effect on the level of signal launched by a vertical antenna. This is due to the losses incurred when the signal is reflected from lossy soil.

The effects of ground reflections are also apparent for vertical antennas as they are elevated. **Fig 3-11** shows a comparison when the bottom of a vertical dipole is elevated one and two wavelengths above typical soil. You can see that elevating a vertical dipole well above lossy soil has a strong effect on the strength of signals launched from that antenna.

Fig 3-12 compares the elevation response for a vertical dipole whose bottom is 2 wavelengths high and a horizontal dipole that is 2 wavelengths high. This is again over typical soil.



Fig 3-10 — *EZNEC* overlay of elevation plots for a vertical dipole antenna whose bottom is mounted 1 foot above typical ground, compared to the same dipole mounted over perfect ground. You can see that reflection losses in typical soil can be high.



Fig 3-11 — *EZNEC* overlay of elevation plots for a vertical dipole antenna whose bottom is mounted 1 foot above typical ground (dotted line), compared to the same dipole mounted 1 λ above typical ground (dashed line) and the same dipole mounted 2 λ over typical ground (solid line). The loss in the ground directly under the antenna (sometimes called "heating up the worms") can be substantial when the bottom of the antenna is close to the soil.



Fig 3-12 — *EZNEC* overlays of elevation plot for a vertical dipole antenna whose bottom end is mounted 2 λ above real ground (dashed line), compared with a horizontal dipole mounted 2 λ high (solid line).

Chapter Summary

In this chapter I have examined the effects of moving a simple antenna from outer space to a practical location near the ground. You saw that reflections from the ground result in signals that can add or subtract from the antenna's main wave, depending on the relative phase of the two signals. This effect can prove to be beneficial or detrimental, depending on how the system will be used. In any event, it is easily predictable through modeling and you can decide, as a system designer, how you want everything to come together.

The Earth is but one reflection mechanism with which you will have to deal. Almost any object that a signal encounters will change that signal to a certain extent. Sometimes, as in radar, a reflected signal is the reason for the system. In other circumstances, it can be either helpful or cause problems. I will explore circumstances of each type in later chapters.

Review Questions

3.1. Calculate the actual height of an antenna $\lambda/2$ above the ground for frequencies of 1, 10 and 100 MHz.

3.2. Compare Figs 3-7 and 3-8 and consider why less-than-perfect ground may still be fine for horizontally polarized antennas. Under what conditions would perfect ground help you?

3.3. Repeat question 3.2. for vertically polarized antennas. Compare Figs 3-10 and 3-12 to get the idea. Why might you want to take extra care to simulate a perfect ground for a low vertical dipole?

3.4. Based on their azimuth and elevation patterns, can you think of applications that would be best suited for vertical antennas? How about horizontal antennas?

Chapter 4

The Impedance of an Antenna



A collection of antenna impedance measurement instruments.

Contents

Antenna Impedance 4-2
Review Questions...4-5

So far I have discussed the half-wave dipole in some of its different forms. I have always assumed that there was a transmitter (or receiver) at the center of it. I haven't yet discussed how you connect the transmitter to the antenna, or whether it's convenient to physically locate the transmitter at the center of the antenna. There are really two issues here:

- How does the feed-point input impedance of the antenna compare to the load impedance needed by the transmitter? This chapter will discuss the nature of antenna feed-point impedances.
- The second issue is whether or not you can (or would want to) physically locate the transmitter at the center of the antenna. This is sometimes the case, and I could describe some examples, but it is generally reserved for situations in which the antennas are relatively large and the transmitters are relatively small, such as phased-array radars. In other cases, you generally interconnect the transmitter and antenna with a *transmission line*.

A transmission line is a type of cable designed for the purpose. They are available in a number of configurations, all with the property that if they are connected to an antenna (or any load for that matter) that has an impedance equal to the *characteristic impedance* of the transmission line, a value determined by the physical properties of the line, the other end of the line will see the same impedance. Thus if we *match* the impedance of the antenna to the transmission line, we can locate the transmitter any distance from the antenna and have it act almost as if the transmitter were at the center of the antenna.

We will discuss transmission lines, as well as matching, in the next chapter. The place to start is with the impedance of the antenna and the knowledge that you don't really have to locate the transmitter at the middle of it. Anyone who has seen a photo of the transmitter room at a TV or radio station or especially the Voice of America will immediately appreciate the desirability of being able to separate the transmitter from the antenna!

Antenna Impedance

As with any circuit element, the impedance an antenna presents to its source can be defined by the current that flows when a voltage is applied to it. There are, after all, no footnotes to Ohm's law that repeal it for the case of an antenna. Thus for any possible connection point to an antenna, if we know the levels of current and voltage, Ohm's law will reveal the impedance at that point.

Note that I could talk about a receiver connected to the antenna rather than a transmitter. Here, I will discuss transmitting antennas, with the understanding that receiving antennas have the same impedance characteristics.



Fig 4-1 — Voltage and current distribution along the length of a resonant half-wave dipole.

The Impedance of a Center-Fed Dipole

In Chapter 2, I discussed the current and voltage distribution along the length of a λ/2 dipole. I elected to feed it in the center since that's where the voltage was at a minimum and the current at a maximum. The drawings of current and voltage are reproduced as **Fig 4-1**. The ratio of voltage to current, the impedance, will vary as you change any of the key dipole parameters. If you change the length through values around λ/2, the ratio will go through a point at which the ratio is resistive. This is also described as the *resonant* point— that is, there is no reactive component and thus the impedance is entirely resistive. This special length is referred to as the resonant half-wave dipole length. Even though it is special, it is very useful and frequently encountered.

Impedance of a Dipole in Free Space

I will discuss some of the factors that cause the impedance of a λ/2 dipole to differ; however, as a starting point, I'll consider the case of a thin dipole in free space. At resonance it will have an impedance of around 72 Ω. If you make the antenna just a bit shorter (or change to a slightly lower frequency), it will look like a resistance in series with a small amount of capacitance. If you make it just a bit longer, it will look like a resistance in series with a small inductance.

A key parameter in determining both the impedance of a resonant dipole and how the impedance changes with frequency is the ratio of length-to-diameter. Using a 10-MHz

Table 4-1

Impedance of Nominal λ/2 Dipole in Free Space (Ω, – indicates capacitive reactance)

	L/D = 10,000 (47.81 foot length)		*L/D = 1000 (47.31 foot length)*		*L/D = 100 (45.98 foot length)*	
Frequency	*Impedance*		*Impedance*		*Impedance*	
MHz	R	X	R	X	R	X
9.9	70.0	–16.0	69.7	–11.7	69.6	–7.3
9.95	71.0	–8.1	70.8	–5.9	70.1	–3.7
10.00	72.1	0	72.1	0	72.0	0
10.05	72.2	+8.0	73.0	+5.8	73.2	+3.5
10.1	74.3	+16.1	74.1	+11.8	74.4	+7.2

dipole as an example, **Table 4-1** provides the results from an *EZNEC* simulation of an ideal loss-free dipole at three different length-to-diameter ratios. The first, 10,000:1, is fairly typical of a dipole made from wire. The second would correspond to an antenna constructed from fairly thick wire, while the third would represent an antenna made from 5-inch tubing (or more likely at this frequency, a cage of wires). As frequencies go up and down, the typical length-to-diameter ratios change due to material availability, but all can be encountered in the real world.

There are a few points that should be observed as you look at Table 4-1:

1. As the conductor diameter increases, the length of the resonant dipole decreases. Note that in free space, λ/2 at 10 MHz is 49.2 feet, compared to 47.81 feet for the wire case (about 97%) down to 45.98 feet for the very thick dipole (about 93.5%).
2. As the conductor diameter increases, the change in impedance with frequency decreases. This will be an important consideration when we talk about wideband antennas later in the book.
3. If the source is designed to feed a resistive load, it is relatively simple to provide a match to it even if the antenna has a reactive component. The circuit is shown in **Fig 4-2**. For example, if we want to operate a 10-MHz, L/D = 1,000:1 antenna on 10.1 MHz, the inductive reactance component is +11.8 Ω. By inserting a capacitor with a capacitive reactance of –11.8 Ω at the antenna



Fig 4-2 — Simplified diagram of an antenna as a load, with a resonating network to provide a resistive load to the source.



Fig 4-3 — Impedance of 10 MHz, λ/2 dipole with length-to-diameter ratio (L/D) of 10,000:1 from 1 to 50 MHz. The X axis is real (resistive) component, while the Y axis is reactive. Positive values indicate inductive reactance; negative values indicate capacitive reactance. Key frequencies are shown.



Fig 4-4 —Same as Fig 4-3 except L/D is 1,000:1.



Fig 4-5 —Same as Fig 4-3 except L/D is 100:1.



Fig 4-6 — Impedance of a resonant thin dipole as a function of height above ground, or other reflecting surface. The solid line represents a perfectly conducting surface, while the dashed line represents "real" ground.

(see Fig 4-2), you will present the source with a resistive load of 74.4 Ω, almost the same as if we shortened the antenna to make it resonant.

Figs 4-3 through **4-5** show the change in impedance over a wide frequency range for the length-to-diameter ranges of Table 4-1. The differences are striking.

Impedance of a Dipole near Earth

Reflections from the ground couple to a dipole, much in the way a load on one winding of a transformer couples to another. Thus the impedance of a dipole will be different at different heights above ground, depending on the magnitude and phase of the reflection — functions of ground characteristics and the height above ground. **Fig 4-6** shows the impedance of resonant horizontal and vertical dipoles at different heights above ground. Note that other conductive surfaces will have a similar effect on impedance. Coupled antenna elements will also, but I'll reserve that discussion for later.

Review Questions

4.1 Why might we care what the impedance of an antenna is?

4.2 What principle accounts for the difference in the effect of ground between horizontal and vertical antennas?

4.3 What might be the effect of connecting an antenna and a transmitter with different impedances?

4.4 Describe advantages and disadvantages of thin and thick antennas as shown in Figs 4-3 through 4-5.

Chapter 5

Transmission Lines



Transmission lines come in many forms serving many applications.

Contents

Characteristic Impedance 5-2
Attenuation 5-3
Propagation Velocity 5-4
Lines With Unmatched Terminations 5-4
Review Questions 5-6

As I have mentioned previously, frequently the antenna and radio are not located in the same place. There are some notable exceptions, particularly in portable handheld systems and various microwave communications and radar systems. But in most other cases, optimum performance requires the transmitter and receiver to be at some distance from the antenna. (There may also be a matter of combat survival, especially if your enemy is equipped with anti-radiation weaponry designed to home in on a signal.)

The component that makes the interconnection is called a *transmission line*. Transmission lines are used in places besides radio systems — for example, power-distribution lines are a kind of transmission line, as are telephone wires and cable TV connections.

In addition to just transporting signals, transmission lines have some important properties that you will need to understand to allow you to make proper use of them. This section briefly discusses these key parameters.

Characteristic Impedance

A transmission line generally is composed of two conductors, either parallel wires, such as we see on power transmission poles, or one wire surrounding the other, as in coaxial cable TV wire. The two configurations are shown in **Fig 5-1**. Either type has a certain inductance and capacitance per unit length and can be modeled as shown in **Fig 5-2**, with the values determined by the physical dimensions of the conductors and the properties of the insulating material between the conductors.

If a voltage or signal is applied to such a network, there will be an initial current flow independent of whatever is on the far end of the line, but based only on the L and C values. The initial current will be the result of the source charging the shunt capacitors through the series inductors and will be the same as if the source were connected to a resistor whose value is equal to the square root of L/C. If the far end of the line is terminated in a resistive load of the same value, all the power sent down the line will be delivered to the load. This is called a *matched* condition. The impedance determined in this way is called the *characteristic impedance* of the transmission line and is perhaps the most important parameter associated with a transmission line.

Common coaxial transmission lines have characteristic impedances (referred to as Z_0) between 35 and 100 Ω, while balanced lines are found in the range of 70 to 600 Ω. What this means to us as radio people is that if we have an antenna that has an impedance of 50 Ω and a radio transmitter designed to drive a 50 Ω load, we can connect the two with any length of the appropriate 50 Ω coaxial cable and the transmitter will think it is right next to the antenna. The antenna will receive most (see next section) of the transmitted power and all is well with the world!



Fig 5-1 – Parallel wire (A) and coaxial (B) transmission lines.



Fig 5-2 – Lumped constant equivalent of an ideal transmission line.

Attenuation

The ideal transmission line model shown in Fig 5-2 passes all input power to a matched load at the output. A real transmission line, however, has loss resistance associated with the wire conductors and loses some signal due to the lossy nature of the insulating material. As transmission lines are made of larger conductors, the resistance is reduced and as the dielectric material gets closer to low-loss air, the losses are reduced. The *skin effect* causes currents to travel nearer to the surface of the conductors at higher frequencies, and the effective loss thus increases as the frequency is increased.

Fig 5-3 provides some real-world examples of the losses as a function of frequency for the most common types of transmission line. Note that the loss increases linearly with length and the values are for a length of 100 feet. Note also that the losses shown are for transmission lines feeding loads matched to their Z_0. As will be discussed shortly, losses can increase significantly if the line is not matched.

The "open-wire" line shown consists of two parallel wires with air dielectric and spacers, typically resulting in a Z_0 of 600 Ω. While the losses of such a line are low, they only work well if spaced from metal objects and not coiled up. While coaxial cables have higher loss, almost the entire signal is kept within the outer conductor. Coaxial cable can be run inside conduit, coiled up, placed next to other wires and is therefore much more convenient to work with. Sometimes a long straight run of open-wire line will be transformed to 50 Ω at the ends with coaxial cable used at the antenna and radio ends to take advantage of the benefits of both.



Fig 5-3 — Loss of some typical transmission lines in dB per 100 feet as a function of frequency. The RG-58 transmission lines are 50 Ω polyethylene insulated coaxial cable slightly less than ¼ inch in diameter. The RG-8 through RG-216 are 50 and 70 Ω polyethylene insulated transmission lines with a diameter somewhat less than ½ inch. The "hardline" types have a foam dielectric very near to air.

Propagation Velocity

Signals in air dielectric transmission lines propagate at almost the speed of light. Other dielectric materials cause the signals in transmission lines to slow down, just as you can observe with light rays traveling through water. In many cases, this is not a matter of concern, since you usually only care that the signals get out the other end; however, there are some exceptions.

The velocity is reduced by a factor of one over the square root of the relative dielectric constant. Some cable specifications provide the relative velocity as a fraction of the speed of light. If not, and you know the material, most engineering handbooks include tables of properties of materials. For example, polyethylene is a common cable insulating material and has a relative dielectric constant of 2.26. The square root of 2.25 is 1.5, so the propagation velocity in polyethylene insulated coaxial cable is $3/1.5 \times 10^8$ or 2×10^8 m/sec. The velocity of light in air is 3×10^8 m/sec.

Some applications actually use coaxial cables to provide delayed signals in pulse applications. Having a way to accurately predict the delay just by knowing the cable characteristics and measuring the length of the cable can save a lot of lab time. In the radio world, we will talk about driving antenna elements in a particular phase relationship to obtain a desired antenna pattern. If a transmission line is used to provide the two signals of different phase, we need to know how fast the signal propagates in order to determine the required line length. As we will discuss in the next section, transmission lines of particular electrical lengths can be used as impedance transformers. Unless we know the propagation velocity we can't determine the proper length.

Lines With Unmatched Terminations

In our discussions so far, we have been talking about transmission lines feeding terminations matched to their characteristic impedance. Other than that case, the voltage-current relationship at the load will reflect the impedance of the load — not the characteristic impedance. Along the line the voltage and current will vary with distance, providing a load to the transmitter end that is generally neither that of the far end Z_L, nor the Z_0 of the transmission line. The transmitter load can be calculated knowing the Z_L, the Z_0 and the electrical length of the line as discussed in the following sidebar.

The ratio of maximum voltage on the line to minimum voltage on the line is called the *standing wave ratio* or SWR. A matched line has an SWR of 1:1. A 50 Ω line terminated with a 25 or 100 Ω load will have an SWR of 2:1. There is a whole family of complex impedances that will also have a 2:1 SWR. By the way, the computation of SWR is easier with resistive loads.

There are some interesting special cases with a mismatched line. The load impedance, resistive or complex repeats every λ/2, for example. The impedance goes to the opposite extreme in odd multiples of a λ/4. For example, our 25 Ω load would get transformed to 100 Ω in λ/4 or 3/4λ transmission line sections and vice versa. This effect can be used to our advantage if we wish to transform impedances at a specific frequency.

A generally less desirable effect of mismatched lines is that the losses increase. This is easy to see, if voltages and currents are higher, we might expect losses to increase as well. **Fig 5-4** provides the additional loss for a mismatched line that needs to be added to the matched loss in Fig 5-3. As is evident, the combination of matched loss and high SWR results in dramatic increases in loss. This is why antenna designs that don't use matched transmission lines often use air-dielectric lines, which have inherently less loss under matched conditions to start off with.



Fig 5-4 – Additional loss of a transmission line when mismatched. This loss needs to be added to the loss in Fig 5-3 for mismatched lines.

Notes

[1] *TLW* is supplied with *The ARRL Antenna Book*, 21st Edition, Available from your ARRL dealer or the ARRL Bookstore, ARRL order no. 9876. Telephone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.org/shop/; pubsales@arrl.org.**

Determining the Input Impedance of an Unmatched Transmission Line

The input impedance of a transmission line of any length with any terminating impedance can be determined in a number of different ways. The most straightforward way is through direct calculation. Unfortunately, this is also perhaps the most time consuming and perhaps most error prone method, at least until you have it set up on a spreadsheet or other program. The input impedance can be found as follows:

$$Z_{in} = Z_0 \frac{Z_L \cosh(\gamma \ell) + Z_0 \sinh(\gamma \ell)}{Z_L \sinh(\gamma \ell) + Z_0 \cosh(\gamma \ell)}$$

where

Z_{in} = complex impedance at input to line in Ω

Z_L = complex load impedance at end of line = $R_a \pm j X_a$

Z_0 = complex characteristic impedance of the line

ℓ = physical length of the line

γ = complex loss coefficient = $\alpha + j\beta$

α = matched-line loss attenuation constant in nepers/meter. (Note one neper = 8.688 dB. Cables in US are generally specified in dB/100 feet.)

β = phase constant of line in radians/unit length. Note that 2 π radians = one wavelength.

Alternately,

$\beta = 2\pi/(VF \times 983.6/f\ (MHz))$ for ℓ in feet

If the line is lossless (or is short enough that losses are not significant), the expression reduces to the somewhat simpler:

$$Z_{in} = Z_0 \frac{Z_L + jZ_0 \tan(\beta \ell)}{Z_0 + jZ_L \tan(\beta \ell)}$$

Note that most scientific calculators, including the *Windows* scientific calculator and Microsoft *Excel*, can be used to evaluate the hyperbolic trig functions, even if you're not comfortable with them. If you set up (and save) an *Excel* worksheet with the formula above, you will be ready to quickly determine the input impedance any time you have all the input parameters. As noted, be careful with the units.

My favorite way to determine the input impedance, as well as the line loss, standing wave ratio (SWR) is using *TLW* (*Transmission Line for Windows*) software that comes with *The ARRL Antenna Book*.[1] The main screen is shown in **Fig 5-A** performing an analysis of the condition of the L/D of 10,000:1 case from Table 4-1 at 10.1 MHz. Note the antenna input impedance (74.3 + *j* 16.1) is inserted in the LOAD box. The output impedance through 100 feet of RG-58A 50 Ω coax is provided at the bottom in both rectangular (69.02 – *j* 6.23) and polar coordinates (69.53 at an angle of –5.15°), along with the SWR at line input (1.40) and output (1.62) as well as line loss (1.661 dB) — both for the matched case (1.555 dB) and the additional loss due to mismatch (0.106 dB). That's about everything I could think to ask, except which pile in the basement actually holds my RG-58A!

A third way to evaluate the input impedance is through a graphical method. A *Smith chart*, see **Fig 5-B**, can be used to determine the input impedance of a transmission line. This was very commonly used before the personal computer became ubiquitous. In addition to the accuracy limitations due to the input and output resolution inherent in a chart, the *Smith chart* assumes that the line is lossless. This may result in significant error depending on the amount of line loss.



TLW, Transmission Line Program for Windows

Version 3.00, Copyright 2000-2006, ARRL, by N6BV, Mar 14, 2006

Cable Type: RG-58A (Belden 8259)

● Feet ○ Meters Length: 100 Feet Lambda Frequency: 10.1 MHz

Use "w" suffix for wavelength (for example, 0.25w)

Characteristic Z0: 50.0 - j 0.92 Ohms Matched-Line Loss: 1.555 dB/100 Feet

Velocity Factor: 0.66 Max Voltage: 1400 V Total Matched-Line Loss: 1.555 dB

Source: ● Normal ○ Autek ○ Noise Bridge

● Load ○ Input Resistance: 74.3 Reactance: 16.1 Ohms

● Volt./Current ○ Resist./React.

SWR at Line Input: 1.40 SWR at Load: 1.62 Rho at Load: 0.23679

Additional Loss Due to SWR: 0.106 dB Total Line Loss: 1.661 dB

Impedance at Input: 69.02 - j 6.23 Ohms = 69.30 Ohms at -5.15 Degrees



Fig 5-A — The main screen of *TLW* (*Transmission Line for Windows*) software is shown performing an analysis of the L/D of 10,000:1 case from Chapter 4's Table 4-1 at 10.1 MHz.

Fig 5-B — A *Smith chart* used for the graphical determination of the input impedance of a lossless transmission line.

Review Questions

5-1. Describe three reasons it might be desirable to have a transmitter and an antenna in different locations.

5-2. If you want to make a $\lambda/4$ section of RG213 for a 10 MHz system, how long would you make it?

5-3. A 1000 W transmitter at 15 MHz is feeding a matched load through 200 feet of RG-8 transmission line. How much power reaches the antenna? Repeat if the frequency is 150 MHz. Repeat both cases if the antenna has an SWR of 3:1.

Chapter 6

Making Real Dipole Antennas


Coax Wrapped Around Insulator
Insulator
Braid
Inner Conductor
This point should be sealed to keep moisture out of coax.
Coax
Coax
Insulator
Clamp
Rope to Support
QS0712-Work01

A dipole is easy to make and works well for many applications.

Contents

Making Real Dipole Antennas 6-2
Review Questions...6-7

Table 1

Maximum Tension for Stressed, Unloaded, Antenna Wire.

American	*Recommended Tension*[1] *(pounds)*		*Weight (pounds per 1000 feet)*	
Wire Gauge	*Copper-Clad Steel*[2]	*Hard-Drawn Copper*	*Copper-Clad Steel*[2]	*Hard-Drawn Copper*
4	*495*	*214*	*115.8*	*126.0*
6	*310*	*130*	*72.9*	*79.5*
8	*195*	*84*	*45.5*	*50.0*
10	*120*	*52*	*28.8*	*31.4*
12	*75*	*32*	*18.1*	*19.8*
14	*50*	*20*	*11.4*	*12.4*
16	*31*	*13*	*7.1*	*7.8*
18	*19*	*8*	*4.5*	*4.9*
20	*12*	*5*	*2.8*	*3.1*

[1] Approximately one-tenth the breaking load. Might be increased by 50% if the end supports are firm and there is no danger of icing.

[2] Copperweld,™ 40% copper.

ing sag in the center of the half span (see **Fig 6-5**) for a given amount of tension can be estimated using the nomograph shown in **Fig 6-6**.

Many other mechanical configurations have been used, with the most common perhaps being the dipole slung between two trees. This is often constructed by using some kind of line launcher, such as a sling shot, fly-casting rod, bow and arrow or even a radio-controlled helicopter to get the line over a desired tree limb. While this method has been used successfully many times, almost all such installations eventually fail due to a combination of factors. The major problem is that the trees move in the wind. If the trees at both ends moved the same distance, in the same direction and at the same time, the tension would remain constant. Unfortunately, trees can't be counted on to do any of those things.

Keeping it Up in that Tree

To maximize the success of a tree-mounted dipole, you must take tree sway into account. One way is to note the maximum sway of the trees at each end and add that length to each halyard once set for the appropriate sag to give the maximum tension specified in Table 6-1. Note that if there is no center support, and the weight of the transmission line is thus also supported by the antenna, additional tension will be applied to the wire and you must allow for additional sag.

An additional failure mode is halyard *chafing*. As the tree moves back and forth, the bark cuts into the halyard rope, eventually causing it to break. Chafing can be minimized if the halyard is run directly down and secured to the trunk of the same tree that it's over. In that way the halyard tends to move with the tree rather than having the tree move along the halyard.

Some rope is better than others at resisting chafing. Twisted nylon rope has excellent stretch characteristics; however, it seems to chafe very quickly. I have found "yacht braid," a generic name for rope used for sailboat halyards, a rope that lasts quite long in antenna-mounting service. Although it is designed for low stretch, it makes up for that deficiency by resisting chafing.

I suppose the strongest halyard material is stranded aircraft-grade stainless-steel rope, although it may saw through the supporting tree limb in place of chafing. One trick to reduce chafe breakage is to start with an extra long halyard. Every year or so, lower the antenna end and inspect for chafing. If it has started, cut off a few feet of rope at the antenna end and re-hoist. You will move the chafed area away from the limb.



Fig 6-5 — The half span and associated sag of an unloaded wire suspended from both ends.

Some have used stretching elements at the antenna insulators. Some insulators are made with internal springs; however, their travel range is usually insufficient to solve a serious tree-sway problem. Some have employed screen door closing springs for the purpose. Another approach is to have a sacrificial halyard section of lighter line holding the ends of a loop of the main halyard. If tree sway strain happens, the light line will break and the loop inserts enough extra halyard to avoid excessive tension. A combination of these methods can also be used.

A better way is to use the pulley arrangement shown in **Fig 6-7**. This solves all the problems at once. There is no chafing because the rope holding up the pulley is fixed (as long as it is secured to the same trunk, as noted previously). A constant tension is applied by the weight, independent of tree sway. You can adjust the tension easily by adjusting the weight used.



Fig 6-6 — Nomograph for determining wire sag. (John Elengo, Jr, K1AFR)

For all halyard arrangements, you should provide an extra *downhaul* line from the halyard side of the end insulator. This line is used to get the end of the halyard down in the event the antenna breaks. There's nothing more frustrating than completing a five-minute antenna repair and then spending the whole day getting the halyard back up in the tree!

A Special Case — the Inverted V Dipole

Finding two or, even better yet, three solid supports for a dipole is often difficult. Fortunately, an antenna with similar, but not quite equal performance, can be constructed with a single support by putting the apex of the antenna on top of the support and extending the dipole arms at an angle downward to be secured near the ground. **Fig 6-8** shows the configuration. In addition to needing only a single support, this arrangement has the advantage that the support can also support the weight of the center structure and transmission line.

The downside to the *inverted V dipole* is that the maximum radiation occurs at a somewhat higher angle than for a horizontal dipole at the same height. See **Fig 6-9**. It shows the elevation pattern of a 10 MHz λ/2 flattop dipole at 50 feet over typical ground, compared to the pattern for an inverted V with an included angle between the two legs of 90°, with its apex at 50 feet, the same height as the flattop dipole. The V has its maximum radiation at 31° rather than 27° for the dipole. The 50 foot dipole could be lowered about 12% to 44 feet and have the same elevation response. The inverted V also has about 1 dB less gain at its maximum elevation. In many applications, these are reasonable trade-offs.

For the same wire length, a 90° inverted V will have a resonant frequency about 6% higher than determined by the 468/F formula, depending on the droop angle from the horizontal. Shallower angles, say 120°, will be closer to the performance of a horizontal dipole, and steeper drooping angles could also be used, with correspondingly reduced performance. One advantage of the Inverted V configuration is that the real part of the feed-point impedance drops somewhat as the dipole arms are lowered and as a result the match to commonly used 50 Ω coaxial cable is improved.

Vertical Dipoles for HF

We have been concentrating on horizontal HF dipoles so far because they are the most frequently encountered HF dipoles. Vertical HF antennas are more often of the *monopole* variety (think half a dipole), because they can be easily fed at the base. We will discuss monopoles in another chapter later in the book.

Vertical half-wave HF dipoles are, however, sometimes encountered. The primary advantages of a vertical dipole over a horizontal one are that they provide omnidirectional azimuth coverage and, like an inverted V, they require a single support — *almost*. In order to work most effectively, the feed line should be perpendicular to the antenna for at least λ/4. This generally requires a second support at least half as high as the primary one as shown in **Fig 6-10**. An additional advantage is that they provide low angle coverage, even at low heights. The major support must be at least λ/2 high for a full-sized λ/2 vertical dipole, and the actual low angle response of an inverted V on the same support may have a similar pattern.

A potential disadvantage of a typical vertically polarized antenna compared to a horizontal one is that the reflected signal from a horizontal antenna above real ground tends to add significantly to the signal at medium elevation angles. Over perfect ground, the reflected in-phase signal from a vertical theoretically should add significant power at very low takeoff angles; however, this reflected power is lost for waves traveling over typical lossy soil. Now, if you have



Fig 6-7 — Pulley arrangement for securing an antenna halyard to a tree while avoiding chaffing and high tension during tree movement.



Fig 6-8 — Inverted V wire dipole.



Fig 6-9 — Elevation pattern of inverted V wire dipole (dashed) compared to that of horizontal dipole (solid)



Fig 6-10 — Vertical HF wire dipole showing need for second support to maintain perpendicular transmission line.

seawater in the desired directions, a vertical would have much more reflected signal at low elevations than even a higher horizontal dipole. But for most types of lossy soil, the situation is as shown in **Fig 6-11**.



Fig 6-11 — Elevation pattern of vertical 10 MHz dipole suspended from 50 foot support (dashed) compared to that from an inverted V from the same support in its preferred direction (solid).

What About Other Lengths?

A dipole with a length of approximately λ/2 is often used because it provides a convenient impedance match to popular transmission line types. As noted in Table 4-1 and Figs 4-3 to 4-5, dipoles of other lengths can also be used, but the feed-point impedance will be quite different. These lengths can also be used effectively, as long as an appropriate matching network is provided to match the impedance to that required by the radio equipment or the transmission line. I will discuss some particular applications of different length dipoles in Chapter 12.

VHF and UHF Dipoles

I have been focusing on HF dipoles so far. However, a dipole also works well at higher frequencies. As a matter of construction convenience, dipoles above the HF range tend to be made from solid tubing rather than flexible wire. Rigid tubing has the advantage that it can be supported from the center insulator and thus doesn't require support or insulators at the ends. In many cases, since their size makes it so easy, at VHF and UHF dipoles are parts of directional arrays, a topic for later discussion.

Review Questions

6-1 What are two reasons why it is desirable to have a support at the center of a wire dipole?

6-2 What are the results of changing from a thin coaxial cable to a thicker one with lower loss? Case 1 with no support at the center of the dipole; case 2 with a support?

6-3 Why is it better to secure an antenna halyard at the base of the same tree that the halyard is over?

Chapter 7

The Field From Two Horizontal Dipoles



Chuck Hutchinson, K8CH, adjusts his two element array.

Contents

THe Field From Two Horizontal Dipoles 7-2

Horizontal Dipoles in a "Stack" 7-2

Chapter Summary 7-7

Review Questions..7-7

The Field From Two Horizontal Dipoles

In Chapter 3 I described the action of a dipole in the presence of its below-ground "image antenna." It is also common to find antenna arrays of multiple real dipoles. As you might expect from the discussion of the dipole above its image antenna in Chapter 3, horizontally polarized antennas combined above one another will result in a change of the elevation pattern, while side-by-side antennas will change the azimuth pattern. This chapter will begin to examine how two dipoles can be combined to achieve some desired outcomes.

Horizontal Dipoles in a "Stack"

Perhaps the easiest configuration to start with is to add an additional dipole above the one you used in the last few chapters and find how it performs. A broadside view of the configuration is shown in **Fig 7-1**, with an end view shown in **Fig 7-2**. It looks very much as you would expect, but note that unlike the image configuration in Chapter 3, I chose here to feed both antennas in the same phase. Unlike the image situation, this is a choice depending on how you connect the sources. I could have connected each antenna to sources that are out-of-phase.

Another difference of note is that the height of this two-element array (and other large antenna structures) is taken as the height of the center of the array. That was true of the single dipole as well, but for the single dipole the height also was as high as the antenna got. This may have ramifications on the size of support structures and clearances, so keep it in mind.

If you divide the available transmitter power in half and apply each half to the two dipoles in free space, each will separately attempt to radiate the same kind of signal I described in Chapter 2.[1] However, since the signals are on the same frequency, when you look at the response you see the combination of the output from both antennas, not just one.



Fig 7-1 — Front view of configuration of two in-phase stacked horizontal dipoles.



Fig 7-2 — End view of the two horizontal dipoles with polarity as indicated.

So What Happens?

The first antenna configuration that I will examine is one in which the dipoles are spaced λ/2 apart. Because the dipoles are driven in the same phase, every point in space that is the same distance from each antenna will receive the benefit of each antenna's pattern adding together. This clearly happens going horizontally away from the plane of the antennas (for any spacing), as shown in **Fig 7-3**. This is the direction broadside to the plane of the array (imagine the antennas stapled to a billboard) and thus this configuration of dipoles is often called a *broadside array*. Note that if you feed them in the opposite phase the signals in the broadside direction would cancel, just as in the case of a horizontal antenna and its image — more about this later.

A single dipole in free space will radiate the same level signal at all elevation angles. As seen in Fig 7-3, this is not happening with two dipoles. Let's consider the radiation from one, say the lower, dipole that would head upwards if left to itself. The radiation going upwards, towards the second dipole, starts out in the same phase as is fed to the second dipole, but by the time the signal has traveled the λ/2 towards the upper dipole, the signal in the upper dipole is exactly 180° out-of-phase. Since the signals in that direction are the same strength, they combine by cancelling out going upwards! You have made an antenna with a *null* in the pattern at a 90° elevation angle. Note that for the free-space case, the exact same thing happens going downward.



Fig 7-3 — *EZNEC* elevation plot for two element horizontal array in free space.



Fig 7-4 — *EZNEC* plot of azimuth pattern of two element array in free space.

What Happens to All the Energy?

Note that nowhere did I talk about anything getting warm or otherwise dissipating energy. All the energy fed to the antenna system will be radiated. If it doesn't go one place, it will go another. Just as the light from a flashlight bulb with a reflector is brighter going out the front, and weaker elsewhere, the energy from this broadside antenna is greatest perpendicular to the "billboard" (unlike the flashlight, on both sides of the billboard) and less elsewhere. If you compare the field strengths at the maximum of the elevation patterns of the two-dipole array (Fig 7-3) with that of the single dipole in free space (Fig 2-8) you will find that the difference in maximum signal is 5.88 – 2.06 = 3.82 dB.[2] This represents an increase in power by a factor of 2.41, a bit more than double that from the single dipole in the maximum direction.

Someone listening from the direction of maximum radiation (the main *lobe*), if they didn't know about the exact configuration of the antenna, could think you more than doubled the transmitter power. This effect illustrates the concept of *antenna gain*, although there really isn't any *more* power, you have just moved it around, concentrating the power more in certain directions.

Note that someone from right above the antenna might think you turned off your transmitter! Note also that the azimuth pattern (see **Fig 7-4**) remains largely unchanged.

What If We Get Back Down to Earth?

While the free-space pattern is a good way to isolate the effect of adding the second antenna, the real-world situation is near the ground. As you might expect, you still have the effect



Fig 7-5 — *EZNEC* plot of elevation pattern of two element horizontal array over perfect ground.



Fig 7-6 — *EZNEC* plot of elevation pattern of two element horizontal array over typical ground.

of the reflections from the ground to deal with, even though you don't have any signal heading straight downward from the two stacked dipoles in Fig 7-2.

No matter how complex the array, the effect of the ground is still that of an image antenna, 180° out-of-phase with the real horizontally polarized antenna, and the same distance below the ground. The result for a horizontally polarized antenna is still a cancellation of energy at 0° elevation and a reduction of radiation at very low angles, as shown in **Fig 7-5** for perfect ground and over typical ground in **Fig 7-6**.

Let's Feed the Two Antennas Out-of-Phase

So far you've been looking at the case where the generators attached to the antennas are of the same phase. This is a useful and frequently encountered case, but clearly only one of many ways you could drive the antennas. The other extreme case is to turn one of the generators around so that the two antennas are fed out-of-phase. If you think about it, this is similar to the horizontal antenna and its image, but in this case both elements are above ground.

For the case of λ/2 spacing, the wave from the lower antenna starts out at the opposite phase from the signal in the upper antenna. By the time it propagates to the upper antenna, the phase of the signal in that antenna has shifted exactly 180° and now the two signals propagate upward in the same phase and thus they add, as seen by any receiver directly above. The signal heading downward has the same result and another lobe, at least in free space, heads downward. The signals perpendicular to the array, the broadside direction that had the maximum response previously, now has a null. The name often given to this configuration is somewhat confusing, since it is called an *end-fire array*. A more descriptive name might be *edge-fire*, or something else that doesn't make it sound like the signal is leaving the ends of the elements. After all, the azimuth pattern still has a null off the ends of the dipoles. **Fig 7-7** is the elevation pattern in free space for the 180° out-of-phase case.



Fig 7-7 — *EZNEC* elevation plot of two element end-fire array of vertically stacked elements in free space.



Fig 7-8 — End view of the two horizontal end-fire dipoles, with phases as indicated.

The End-Fire Array on Its Side

An interesting case to consider is the end-fire array with both antennas at the same height, and still fed 180° out-of-phase as shown in **Fig 7-8**. An *EZNEC* elevation plot over typical real ground is shown in **Fig 7-9**, and it is interesting to compare this with the similar looking plot of the broadside array response in Fig 7-5. This is an indication of an important general principle — there are often multiple configurations that will provide the response you want. You can pick the one that best suits the physical limitations of a particular installation.

What if We Use a Different Dipole Spacing?

The $\lambda/2$ spacing cases just examined represent a very special distance in which the radiation in the plane containing the elements cancels or adds because the time it takes a wave to move between the two elements results in exactly a 180° phase difference. There is nothing to prevent you from picking any other spacing, and there may be reasons why other spacings are beneficial. One extreme would be a spacing of zero, or one dipole resting on the other. If the two are fed in the same phase, they just act like a single, but slightly thicker antenna. If you attempt to feed the two dipoles out-of-phase, it will act as if you short-circuited the transmitter and you will not be able to put any energy into the system.

At other spacings you will find that the shape of the response gradually changes. At smaller spacings the cancellation in the previous null directions is less than 100%; while at larger spacings there can be additional peaks and nulls because there are path differences greater than $\lambda/2$. I will examine the effect of spacing in more detail in the chapter on Arrays of Multiple Elements.

A Unidirectional End-Fire Array

A very interesting special case of the end-fire configuration exists if you change the spacing to $\lambda/4$ and the phase between the elements from 180° to 90°. With this arrangement, as shown in **Fig 7-10**, with a 90° delay (we'll show how to do that soon) to the signal connected to Dipole 1, its signal has advanced to 0° by the time the signal from Dipole 2 gets there and they add in-phase in the direction from Dipole 1 towards Dipole 2. On the other hand, the signal from Dipole 2 at –90° reaches Dipole 1 when it is at +90°, cancelling in that direction. See **Fig 7-11** for the elevation-plane plot of this array and **Fig 7-12** for the azimuthal pattern.

It should be clear that there are many applications in which a unidirectional antenna would be useful — for example a radar operator could tell if an aircraft is in front of or behind the radar. As I



Fig 7-9 — *EZNEC* elevation plot of end-fire array 0.75λ above real ground.



Fig 7-10 — Physical configuration of two element unidirectional array.



Fig 7-11 — *EZNEC* plot of elevation pattern of two element unidirectional array over typical ground.



Fig 7-12 — *EZNEC* plot of azimuth pattern of two element unidirectional array at peak of elevation pattern.

will discuss later, this is just one of many ways in which you can generate a unidirectional pattern.

Two Dipoles in Line — Collinear arrays

Another configuration of two dipoles is to have them along the same line, end-to-end. The configuration is shown in **Fig 7-13**, with the path difference in the signals shown in **Fig 7-14**. Note that the spacing can be any length larger than λ/2, since they would overlap if less, and then they would not act as two separate dipoles. For the case of the minimal λ/2 spacing at a height of λ/2 over real ground, the azimuth pattern is shown in **Fig 7-15**. In the direction broadside to the two dipoles, the patterns add, as you would expect, but at any other azimuth the propagation distance is different, as shown in Fig 7-14.

The further you move away from broadside, the greater the difference in the path length, with the result that the patterns from the two antennas no longer reinforce each other as you shift off axis. Unlike the stacked case, you have thus modified the azimuth pattern, but not the elevation pattern (compare **Fig 7 -16**, the elevation pattern, with Fig 3-7).


UBA0052
Spacing
+
-
Dipole 1
+
-
Dipole2
Height
Ground

Fig 7-13 — Front view of two element collinear array.


Wavefront
Dipole 1
Dipole 2
Azimuth Angle
Difference in Path Length
+
-
Dipole 1
+
-
Dipole2
UBA0053
Spacing

Fig 7-14 — Physical configuration of two element collinear array.



Fig 7-15 — *EZNEC* plot of azimuth response of two element collinear array.



Fig 7-16 — *EZNEC* plot of elevation pattern of the collinear array over real ground.

Chapter Summary

In this chapter I have introduced and discussed the topic of how two horizontally polarized dipoles can be used to deliver more RF energy to smaller volumes of space than a single dipole would. If you stack the dipoles one above the other, you limit the elevation coverage. In a special case you can limit the coverage to a single direction.

If you put the dipoles side-by-side, you do not change the elevation coverage, but limit the azimuth coverage. Either arrangement can be used to advantage, since it makes sense to send the energy to places where it can be used.

Review Questions

7.1 Under what circumstances might a 2-element broadside array be beneficial?

7.2 Given that broadside and end-fire arrays can have similar responses, why might one be preferable to the other?

7.3 What are some of the benefits of a collinear array, and some of the disadvantages in comparison to the other two antennas?

7.4 Describe two potentially beneficial uses for a unidirectional array.

Notes

[1] To implement "half-power" in the *EZNEC* model description, each source voltage or current should be set at 0.707 times the full value (usually 1.0) because the power is proportional to the square of the voltage or current.

[2] If you are not comfortable working with decibels, spend some time with Appendix A.

Chapter 8

The Field From Two Vertical Dipoles



The combined field from multiple antennas can be oriented in many helpful ways.

Contents

The Field From Two Vertical Dipoles....8-2

Side By Side Vertical Dipoles....8-2

Vertical Dipoles in a Line....8-4

Phase Steered Arrays....8-5

Review Questions....8-7

The Field From Two Vertical Dipoles

In Chapter 7 I described the way the fields from two horizontal dipoles combine at a distant point. I pointed out that if the two dipoles were fed equal amounts of energy in the same phase that the energy would add everywhere the distance to each of the dipoles was the same. I also noted that the presence of the ground reflection could modify the result, depending on how high above the ground the antenna elements were located. If the elements were fed in opposite phase (180°) the energy would cancel in directions that were equal distances from the elements and thus the directional characteristics would be changed.

As you might expect, similar things happen to dipoles that are oriented vertically. In fact, you may wonder why vertical dipoles rate a whole chapter, since they are essentially the same as horizontal antennas placed on their side. The big difference is in the way that ground reflections act on vertically polarized signals. I will start with essentially the same configurations as in the horizontal case in Chapter 7.

Side-by-Side Vertical Dipoles

The side-by-side case is in many respects similar to the "stack" of horizontal dipoles I started with in the last chapter. A broadside view of the configuration is shown in **Fig 8-1** with a bird's-eye view in **Fig 8-2**. Here both dipoles are fed in the same phase. This means that their fields will add in the direction perpendicular to the plane of the antennas.

By convention, the height of this array is taken as the height of the center of the array. With a vertical $\lambda/2$ dipole, this distance cannot be less than $\lambda/4$ because otherwise the bottom would be on the ground. I have chosen a height of 36 feet for a 30 meter dipole. This places the bottom 12 feet above the ground. This is a special height, as I will discuss later, but I could have selected any height greater than about 24 feet to keep the bottom of the dipole off the ground.

In-Phase Performance

With equal power to the two elements, the free-space azimuth pattern shown in **Fig 8-3** will result. As expected, the maximum field strength occurs in the direction broadside to the plane of the elements (0° per the indicated azimuth angle in Fig 8-2). You won't be too surprised at the free-space elevation pattern, taken at the maximum of the azimuth pattern — in the broadside direction and shown in **Fig 8-4**.

If you modify the *EZNEC* model by putting the antenna above perfect ground, you will see in **Fig 8-5** the first major change from the horizontal case. Unlike the horizontal array, the vertical array provides the strongest signal at the horizon (0° elevation). Again, this is a result



Fig 8-1 — Front view of configuration of two in-phase stacked vertical dipoles.



Fig 8-2 — End view of the two vertical dipoles, with polarity as indicated.

of the antenna image (the apparent starting point of the ground reflection) being in-phase with the antenna itself for vertical polarization. Arrays of this sort can approximate the perfect-ground case if there is highly conductive ground in the desired broadside direction. If the antenna array is located adjacent to a body of saltwater, or if many wavelengths of wire mesh are used to simulate a highly conductive ground, very low takeoff angles can be achieved.

Over typical ground, the picture is not quite so rosy. The electromagnetic waves traveling adjacent to the ground heat up the lossy ground resulting in less energy traveling along the surface. A number of other effects combine to eliminate the very low-angle propagation, as shown in **Fig 8-6**, where the patterns for perfect and typical grounds are compared. Compare these results to those of the horizontal array in Chapter 4 at a comparable height and note that the peak of the vertical beam is still at a slightly lower angle.

Different applications often find one orientation superior to another. For example, early naval shipboard radar systems tried vertical polarization, with the hope that the low-angle coverage would be excellent for observing distant surface vessels. What they found instead was that reflections from seawater wave fronts (called *sea clutter* in the radar business) overloaded the receivers and masked real targets. A change to horizontal polarization with its null at the horizon largely eliminated the problem. The height of the usual naval shipboard radar was sufficient that distant targets could still be seen above the horizon.



Fig 8-3 — *EZNEC* plot of azimuth pattern of two element array in free space.



Fig 8-4 — *EZNEC* elevation plot two element vertical array in free space.



Fig 8-5 — *EZNEC* plot of elevation pattern of two element vertical array over perfect ground.



Fig 8-6 — *EZNEC* plot of elevation pattern of two element vertical array over typical ground.

Vertical Dipoles in a Line

Vertical dipoles in a collinear configuration make a particularly useful antenna system. By placing one dipole above the other, as shown in **Fig 8-7**, and feeding them in phase we reinforce the radiation near the horizon. The resulting elevation pattern is shown in **Fig 8-8** for two collinear dipoles (dashed line) compared to just the lower dipole (solid line). When the second dipole is added, the peak field intensity becomes somewhat stronger and is focused closer to the horizon. This configuration, as well as designs with additional in-phase dipoles, are commonly used by VHF and UHF base stations who need to communicate with vehicle-mounted radios in all directions. At VHF/UHF a number of dipoles can be combined in such a vertical collinear configuration and still be of reasonable size. The additional gain improves the signal-to-noise ratio at the edges of the coverage area.

It is interesting to look at the effect of element spacing on the resultant pattern. The maximum gain of two collinear dipoles occurs at a spacing of 1 λ (λ/2 between element ends). The resulting pattern is shown in **Fig 8-9**. While the peak gain is about 1.7 dB higher than the close-spaced collinear, the energy going upward is starting to become predominant. This is because at wider spacings the path length from the two elements can be in-phase at angles other than the broadside direction.

The peak at about 43° elevation results because there is still enough energy in each element's pattern and they are close enough to being in-phase that they add to a large measure. At 43° elevation, the difference in path length is 0.68 λ (244° compared to 1 λ or 360° for in-phase). At a spacing of 1 λ, the next elevation at which the two waves will be in phase is 90°, or straight-up. But the individual elements don't radiate at 90°. Hence there is nothing to combine and there is thus still a null at the vertical.



Fig 8-7 — Elevation view of two vertical dipoles in collinear configuration.



Fig 8-8 — *EZNEC* elevation pattern of two closely spaced collinear vertical dipoles (dashed line) compared to the pattern of just the lower dipole (solid line) above typical ground.



Fig 8-9 — *EZNEC* plot of elevation pattern of two element vertical collinear array with center-to-center spacing of 1 λ.

For any spacings greater than 90° (λ/4) there will be elevation angles at which the path difference is 360° within the pattern of each antenna, so the combined pattern gets more complex and often less useful. For example, **Fig 8-10** shows the pattern at a spacing of 2 λ. At this spacing, the waves from the two dipoles are still in-phase at the horizon, but are in-phase again at an elevation angle of 30°. (See the sidebar for a description of the calculation.) Since the individual dipole patterns are only down a small amount there, a significant additional lobe results.



Fig 8-10 — *EZNEC* plot of elevation pattern of two element vertical collinear array with center-to-center spacing of 2 λ.

Phase Steered Arrays

The two element vertical array can be used as an antenna system that can be *steered* to point in different directions by changing phase. While the λ/4 spaced horizontal array can have its direction switched by changing the sequence of feeding the two dipoles, a vertical array offers more possibilities. It should be easy to imagine a pair of λ/2 spaced vertical dipoles providing either east-west or north-south coverage, depending on whether they are fed in-phase or out-of-phase. A possibly even more useful case is the λ/4 spaced case, where either of two unidirectional patterns can be had along the plane of the wires. This is similar to the horizontal unidirectional arrangement of Chapter 4. In addition, the two elements can be fed in-phase to provide broadside bidirectional coverage, at somewhat less gain than the more wide-spaced case.

Perhaps the most extreme example of an application of phase-steering technology is that of the USAF AN/FPS-115 Pave Paws phased array radar shown in **Fig 8-11**. This system provides a "no moving parts" radar system in which each of the two face-plates (one shown, the other oriented to provide nearly 270° total coverage) are composed of 896 distinct antenna elements, each with its own transmitter and receiver front-end. The array is about 72 feet wide with an operating frequency in the 435 MHz range. By combining the signals from each of the elements with carefully controlled phase, a phase-steered beam with an azimuth and elevation width of 2.2° is achieved, capable of detecting targets up to 3000 nautical miles away. There are many advantages of such a system compared to the usual rotating radar antenna — faster tracking, possibility of multiple simultaneous beams and less wear and tear — to name a few.



Fig 8-11 — View of one panel of Pave Paws phased array system.

Calculating Path-Length Difference

It is relatively simple to calculate the difference in path length between the waves from two antenna elements. I will describe the collinear case, as was just discussed in this chapter. However, the same technique can be used for any configuration of elements.

Since you are looking at the combination of signals at a large distance, you can take advantage of the fact that two parallel lines meet at a point an infinite distance away. You can consider the signals leaving each antenna element on parallel paths as shown in **Fig A**. You also consider that the signals start from the center of each element and that the distance between the two individual wavefronts' starting point is the spacing L.

For an elevation angle of 0°, the two paths are the same length and the difference is zero. As the elevation angle, θ, increases, the difference in path length, D, increases up to the maximum, which occurs in the end-fire case for θ = 90°.

To determine the length, as shown in Fig A, the upper interior angle of the right triangle formed between L and D is the same as the elevation angle (because the sum of the angles in a triangle is 180°). Using plane trigonometry, we can see that the difference in path length is just D = L × sin θ.

For examples, look at Fig 8-10 for three elevation angles and see what the path length differences are, as well as the resulting differences in phase between the two signals. (Remembering that a full wavelength results in a shift of 360°) L = 2 λ. As shown in **Table A**, the signals are exactly in-phase at 0°, and thus would add at 0° elevation were it not for ground losses. At 14.5° elevation, the signals are 180° out-of-phase and thus cancel, leaving the null shown. At an elevation of 30° the signals are 360° out-of-phase, the same as being in-phase, so they add again. At 30° off axis, each dipole response is starting to fall off, so the maximum signal occurs at a slightly lower angle.

Table A

Phase angle at key elevation angles as a function of elevation angle for 2 λ element spacing.

θ	sin θ	D = L × sin θ	Phase
0°	0	0 λ	0°
14.5°	0.25	0.50 λ	180°
30°	0.5	1.0 λ	360°



Fig 8-A — Difference in path length of signals from two elements of collinear array.

Review Questions

8.1 Why are arrays of vertical dipoles usually used as base stations for mobile networks?

8.2 Discuss some of the benefits of vertically polarized antenna systems compared to horizontal ones. Consider physical characteristics as well as electrical ones.

8.3 Why might you not want to use vertically polarized antenna systems to communicate with nearby aircraft?

8.4 What do you think would happen as you added more and more vertical collinear elements above the first two?

8.5 Under what circumstances might a conventional mechanically rotating array have advantages over a phase steered system, such as Pave Paws?

Chapter 9

Transmission Lines as Transformers



Transmission lines can serve in many roles. Here one is used as a resonant circuit.

Contents

Lines With Unmatched Terminations 9-2
Review Questions...9-4

In discussions so far, I have mostly been talking about transmission lines feeding terminations matched to their characteristic impedance (Z_0). It is often the case, either by design or accident, that the load impedance does not match the line Z_0. As I mentioned in Chapter 5, the impedance seen at the input of a transmission line is a function of the load impedance, the line characteristic impedance, the loss in the line and the number (or fraction) of wavelengths of line.

Lines With Unmatched Terminations

It is often beneficial to operate transmission lines into matched loads. The line loss will be lowest for that case, voltages and currents are easily predictable, avoiding stress on components connected to the line. There are cases in which operating lines in an unmatched condition can provide just what we need — easily predictable impedance transformation.



Fig 9-1 — Quarter-wave transmission-line transformer.

The Quarter-Wave (λ/4) Transmission-Line Transformer

Along a transmission line that is not matched to its load, the voltage and current will vary with distance, providing a load to the transmitter end that is generally neither that of the far end Z_L, nor the Z_0 of the transmission line. The ratio of maximum voltage on the line to minimum voltage on the line is called the *standing wave ratio* or SWR. A matched line has an SWR of 1:1, a 50 Ω line terminated with a 25 or 100 Ω load will have an SWR of 2:1. There are a whole family of complex impedances that will also have a 2:1 SWR, by the way. However, the computation is much easier with resistive loads.

For a lossless line (and approximately for a short section of real transmission line) the SWR will remain the same along the length of the line. The load impedance, resistive or complex, repeats every λ/2. The impedance goes to the opposite extreme at odd multiples of λ /4. For example, a 25 Ω load would get transformed to 100 Ω with λ/4 or 3λ/4 transmission line sections and vice versa. This effect can be used to your advantage if you wish to transform impedances at a specific frequency. For example, if you have an antenna with an impedance of 100 Ω and you connect it to a λ/4 section of 75 Ω coax, the SWR will be 100/75 or 1.33:1. At the other end of the λ/4 section, the impedance will be 75/1.33 or 56 Ω, a close match (SWR of 1.12:1) to 50 Ω transmission line. You could then use standard 50 Ω coax cable for a long run to your 50 Ω transmitter with lower losses than if you had used the original 100 Ω load directly, with its 2:1 SWR.

The general expression for the input impedance (Z_i) of a λ/4 section of transmission line with characteristic impedance Z_0, terminated in a load of Z_L is:

$$Z_i = \frac{Z_0^2}{Z_L}$$

To solve for the needed transmission line Z_0, we rearrange as:

$$Z_0 = \sqrt{Z_i Z_L}$$

A few observations are in order. While the quantities are shown as complex numbers, transmission lines are available (for practical purposes) only with real, non-reactive Z_0. This implies that the formulation works best for real values of Z_L, as in the above example. This is not a limitation if you work with resonant antennas, which by definition offer a resistive load. Note, as I will


Total Length 2 × 0.65 λ Each Side = 1.3 λ
Transmission Line Length and Zo to be Determined to Match Antenna Z to 50 Ω
UBA0067

Fig 9-2 — Extended double Zepp with matching section of line.



Fig 9-3 — Extended double Zepp azimuth pattern.

discuss, complex impedances can be transformed to match real transmission lines by using transmission line lengths other than λ/4.

The utility of the λ/4 transmission-line transformer method can be limited by the range of available transmission line impedances. Coaxial cable is generally available with Z_0 from about 30 to 90 Ω, while balanced line is available from about 70 to 600 Ω. It is practical to connect transmission lines in parallel (particularly coax) to obtain lower values of Z_0. For VHF and UHF work, it is also feasible to fabricate transmission-line sections with a wider range of values, or non-standard values, through the use of available copper or aluminum tubing.

Since the transformation will repeat with any odd number of λ/4 sections, it is tempting to consider using 3λ/4 or higher odd multiples of a λ/4. This has two potentially significant pitfalls that should be evaluated first. The use of longer mismatched sections will result in higher losses. Often more serious, for sections Nλ/4, the change in Z_i with frequency will happen N times more rapidly with the longer section, effectively reducing the operating bandwidth of the system.

It is also possible to use successive λ/4 sections of line with different Z_0 to work from one impedance to another in steps. This method shares the pitfall described above.

Transformation With Other Lengths of Transmission Line

While a λ/4 transmission line transformer is very useful, especially for resistive loads, sometimes other situations require transformation. A good example is to consider a popular antenna with a reactive input impedance, the extended double Zepp. This antenna is just a center-fed dipole with each side of length 0.625 λ. It is the longest type of simple antenna that can still focus its energy into a single lobe on each side. The extra length and spacing, similar to the two-element collinear, but with a simpler feed system, result in a bi-directional pencil-sharp pattern with higher gain than a dipole. This can be useful to work stations in a particular direction.

While you could perform a lot of math and determine the impedance at the center of this antenna, you can more simply model it using *EZNEC*. The resulting azimuth pattern is shown in **Fig 9-3**, while the impedance plot is shown in **Fig 9-4**. Note that the impedance at the center at 10.0 MHz is 237.7 – *j* 1187 Ω, not suggestive of a standard transmission line! Again, avoiding tedious math, you could turn to the *TLW* program and insert the antenna impedance in the LOAD window, using the minus sign to indicate – *j*. Next, adjust the two available parameters, the line length and Z_0, until you find something that looks like the desired input impedance in the IMPEDANCE AT INPUT indication at the bottom. It takes a few trials to see a direction, but you can find a reasonable length of easily available open-wire 600 Ω line that transforms the impedance to 50 Ω for a coax run to the transmitter.

I was lucky to find an easy solution to this matching problem, perhaps a reason that this is a popular antenna. This will not always be the case. If this technique doesn't result in a result that is easy to deal with, sometimes an intermediate value can be found so it can be transformed to your desired impedance through a λ/4 transmission-line transformer. Even better for this antenna might be to use a λ/2 long 4:1 balanced-to-unbalanced transformer as shown in the next section. It is also possible to try various nonstandard, but buildable line sections using the USER DEFINED TRANSMISSION LINE option in *TLW*.

The Half-Wave Loop 4:1 Balanced-to-Unbalanced Transformer

As discussed in Chapter 6, many antennas are naturally balanced with respect to ground, while coaxial



Fig 9-4 — *TLW* impedance and SWR of extended double Zepp.



TLW

TLW. Transmission Line Program for Windows

Version 2.0, Copyright 2000-2003, ARRL, by N6BV, July 22, 2003

Cable Type: 600-Ohm Open-Wire Ladder Line

● Feet ○ Meters Length: 16.065 Feet 0.178 Lambda Frequency: 10.0 MHz

Use "w" suffix for wavelength (for example, 0.25w)

Characteristic Z0: 599.9 - j 0.57 Ohms Matched-Line Loss: 0.057 dB/100 Feet

Velocity Factor: 0.92 Max Voltage: 12000 V Total Matched-Line Loss: 0.009 dB

Source: ● Normal ○ Autek ○ Noise Bridge

● Load ○ Input Resistance: 237.7 Reactance: -1187 Ohms

● Volt./Current ○ Resist./React.

SWR at Line Input: 12.50 SWR at Load: 12.66 Rho at Load: 0.85360

Additional Loss Due to SWR: 0.068 dB Total Line Loss: 0.077 dB

Impedance at Input: 48.00 - j 0.00 Ohms = 48.00 Ohms at 0.00 Degrees

UBA0070

Fig 9-5 — Impedance of extended double Zepp transformed through empirically determined line section.



Fig 9-6 — Coaxial loop 4:1 transformer-balun.

transmission lines are naturally unbalanced. Sometimes the resulting discontinuity obtained by hooking an unbalanced line to a balanced antenna can cause problems of various types.

In Chapter 6, I mentioned the choke balun as a way to avoid the effects of the unbalance. Another way is through the use of a coaxial cable loop balun, as shown in **Fig 9-5**. The secret to how this works is that a λ/2 of transmission line repeats at its input whatever the load impedance is at the output. It is often possible to arrange an antenna impedance to be a 200 Ω balanced load. As shown in Fig 9-5, half of the load, one side at ground or common potential, appears on one end of the loop. At the other end of the loop it is 100 Ω again and in parallel with the 100 Ω of the other side. Because of the phase difference of 180°, due to the λ/2 length of line, the two sides are out-of-phase and can drive the antenna properly. The two combine to form a 50 Ω load with one side at ground potential — a perfect spot for connection to 50 Ω coaxial cable.

Note that the transformation ratio of 4:1 will happen for any load and any cable Z_0. The closer the cable Z_0 is to the half load, the less rapidly Z_i will change with changes in frequency, or equivalently, the less fussy the balun will be about cutting accuracy.

Review Questions

9-1 You wish to feed two 50-Ω impedance antennas in phase by joining their transmission lines together. How might you transform the resulting 25-Ω to provide a close match to 50-Ω transmission line?

9-2. Repeat question 9-1 in a different way so that the impedance of the connections of the two antenna feeds is 50 Ω. (Hint — this will require two transformers.)

9-3 Consider a λ/2 transmission-line loop balun constructed from RG-58 coax cable and designed to feed a 10-MHz antenna with an impedance of 200 Ω. What will be the loss in the length of cable considering the resulting SWR?

9-4 Repeat 9-3 for RG-213 cable?

Chapter 10

Practical Two Element Antenna Arrays



This two element array uses loop elements.

Contents

The Two Element Broadside Array 10-2
Changing The Spacing 10-4
Feeding Collinear Dipoles 10-5
The Double Zepp...10-6
Review Questions...10-6

It's not much more difficult to construct two element (or even more) antenna arrays than to construct the dipoles described in Chapter 6. In this chapter, I will discuss a few classic two element antennas, and even toss in a simple four-element array to set the stage for more complex antennas.

The Two element Broadside Array

If you suspend two dipoles, as in Fig 6-1, one above the other, you will make a simple broadside array. As I discussed in Chapter 7, by feeding the two in-phase, you focus the radiation towards the horizon (for free space) or for real ground move it more in that direction.

Fig 10-1 shows the configuration. Note that I have defined the height (h) as that to the array center, and the spacing (s) as the separation between the two elements. You can see the benefits of the configuration with λ/2 spacing by looking at the solid trace in **Fig 10-2** that shows the elevation pattern of the array over typical ground. A dipole also at a height of 50 feet is shown in the dashed trace. Since you need a support of about 75 feet to have the center at 50 feet, it seemed fair to also show a single dipole at that height. Its elevation pattern is shown in the dotted trace. Note that even though the peak of the dotted trace is at a lower elevation angle than the peak of the broadside array, the actual radiation at every low elevation angle is stronger with the broadside array. The array has nulled out the vertical radiation, a benefit in some cases, especially if noise tends to appear from high elevation angles, as it often does.

If it were free space, without ground reflections that cancel at the horizon, the main lobe of the array would be more than 3 dB stronger than either dipole. In this real-world case the improvement is a bit less than 2 dB, still worth doing.



Fig 10-1 — Details of a simple two element HF broadside array.



Fig 10-2 — Elevation pattern of the 10 MHz broadside array (solid) compared with dipoles at 50 feet (dashed) and 74.6 feet (dotted).

Putting the Broadside Array Together

Putting together a broadside array is something like putting up two dipoles. The main trick is to make sure that you are actually feeding the pair in-phase. This can be accomplished if:

- The transmission lines from the junction in Fig 10-1 to each dipole are the same type and the same length
- The connections are made in the same direction. That is, both right-hand dipole arms must be connected through the lines to the same point at the junction. If they are reversed the dipoles will be 180° out-of-phase — a possible configu-

ration, but not what you want here.

Hooking Them Up

An interesting property of two parallel antennas is that their coupling due to proximity results in a mutual impedance that combines with each antenna's self-impedance to result in a new impedance at each feed point. This effect will be found to some extent for all multielement arrays. For a broadside array, the effect is that each dipole's impedance (that by itself would be about 65 Ω at this height above ground) will be raised to around 80 Ω by the effect of mutual coupling. If you were to feed each antenna with λ/4 of 50 Ω coax, the impedance transformation due to the λ/4 line discussed in Chapter 9 would result in an impedance at the bottom of each line of 31.25 Ω. This results in 15.6 Ω when they are connected in parallel. The result is a fairly high (3.2:1) standing wave ratio for the run to the transmitter if 50 Ω coax is used.

In Search of a Better Match

There are a number of ways to connect the antennas and achieve a reasonable match to 50 Ω coaxial cable. Two that are almost painless are as follows:

- Use readily available 75 Ω coax for the λ/4 sections going to each antenna. The λ/4 transformation with 80 Ω at the input will result in 70 Ω for each feed. This will combine to make 35 Ω, resulting in an SWR of 1.4:1. This is usually a workable match. Note that with standard coax, the antennas could be only 0.33 λ apart (perhaps 0.4 λ with foam dielectric coax). This spacing will work almost as well as λ/2, but will not quite cancel the upward lobe and will have a bit less gain.
- Use 50 Ω coax for the lines going to each antenna, but make them an electrical λ/2 long. The λ/2 sections will both repeat the 80 Ω at the input for each feed. These will combine in parallel for 40 Ω, resulting in an SWR of 1.25:1. With standard coax this means that the antennas could be up to 0.66 λ apart, a spacing that provides even higher gain.



Fig 10-3 — Details of a simple HF end-fire array. Note 180° phase reversal is required at the junction point.

Another way is sometimes encountered. This one requires some care to result in equal signals going to the two antennas, but does offer a simplicity that is hard to beat. If the two antennas are connected together via an exact λ/2 length of transmission line that is reversed (upper shield to the right element arm, lower shield to the left) the resulting signals to the two antennas will be in-phase. In addition, because the λ/2 transmission line repeats the impedance of the upper antenna the impedance of the upper antenna will be repeated at the junction and the parallel connection should result in an impedance of about 40 Ω.

In a similar way, a 1 λ section of transmission line will also repeat the impedance of the upper antenna at the lower. This time the two antennas will be in-phase if connected to the same side of each antenna. This allows a spacing of up to 0.66 λ, which should result in higher gain and an impedance that is even higher due to mutual impedance and thus a closer match to 50 Ω coax at the junction point.

The 8JK, an Effective and Easy End-Fire Array

The classic HF end-fire array was described by the late John Kraus, W8JK, Professor Emeritus at Ohio State University and the force behind one of the earliest radio telescope development efforts. The antenna still bears his call sign and is called the "8JK Flat-top Array."

The HF end-fire array is just two dipoles at the same height fed 180° out-of-phase. Skyward energy is cancelled and all available power is radiated towards the horizon. The original 8JK was designed using longer elements, and I'll talk about that configuration again in the multiband antenna chapter. But for now, let's look at the single-band λ/2 resonant case.

The basic configuration is shown in **Fig 10-3**. There is nothing surprising here, but as often the case, the devil is in the details.

Hooking Them Up

A key issue is the mutual coupling of the two closely spaced dipoles. Because the two elements are closely spaced, the mutual inductance between them has a significant effect and reduces the feed-point impedance of each dipole to a very low value. For example, at 0.1 λ, in theory a spacing with high gain, the predicted impedance of each dipole is only around 6 Ω. At 0.15 λ it rises to about 12.5 Ω, perhaps a value that can be matched more efficiently.

If you feed each dipole with a λ/4

length of 50 Ω coax, the impedance at the end of each should be 200 λ. If we combine them in parallel (remembering to reverse the connections at one dipole to make them out-of-phase) the result should be 100 λ. Now you either can use 50 Ω coax with an SWR of 2:1, or you can insert a λ/4 section of 75 Ω coax and have an almost perfect match to 50 Ω.

An Easy Collinear Array

The arrays I have described so far in this chapter have been designed to focus their energy at low radiation angles while still maintaining the wide azimuth pattern of a dipole. It is easy to make a horizontal array that doesn't restrict the elevation pattern, but instead has a sharper azimuth pattern to generate gain in the main lobe. This is accomplished by putting two (or more elements along the same axis, or in-line as shown in **Fig 10-5**. This configuration is called a *collinear array*.



Fig 10-4 — Elevation response of the 10-MHz half-wave end-fire array of Fig 10-3 with 0.15 λ spacing, 50 feet above ground.



Fig 10-5 — Configuration of two element collinear array.

Changing the Spacing

The minimum center-to-center spacing of λ/2 dipoles is 0.5 λ and the resulting azimuth pattern of a pair of common 30-MHz dipoles, 50 feet high is shown in **Fig 10-6**. The sharpness and gain of the two-lobed pattern increases as the elements are separated, up to a spacing of 0.625 λ, at which point the beamwidth is reduced to 40° and the gain in the main lobes increases to a bit more than 3 dB compared to a dipole (dBd). Above that spacing, the sharpness of the main lobe increases; however, power also appears in additional lobes, reducing the increase in main-lobe gain. This is illustrated in the azimuth plot shown in **Fig 10-8** for a spacing of 1 λ. The multi-lobed pattern can sometimes prove useful if you are trying to communicate with regions at different azimuths at the same time.



Fig 10-6 — Azimuth pattern of two element collinear array with center-to-center spacing of 0.5 λ.



Fig 10-7 — Azimuth pattern of two element collinear array with center-to-center spacing of 0.625 λ.

Feeding Collinear Dipoles

As with other multi-element systems, you must be concerned with the effects of mutual impedance as you try to feed collinear elements. As you might expect, the coupling between wires on the same axis is not very strong and the effects are small except at close spacings. The real part of the impedance of each dipole goes up smartly at λ/2 spacing, but is negligible for spacings at 0.625 λ and greater. The reactive part of the mutual impedance results in a need to shorten each dipole by about 1% at close spacings in order to achieve resonance. The results are summarized in **Table 10-1**. Each dipole can be fed with equal length sections of 50 Ω line with reasonable (less than 3:1) SWR at 50 Ω expected at the junction. If 93 Ω cable is available, a λ/4 transformer can be used to transform the impedance above 100 Ω, followed by λ/2 sections of 50 Ω cable so a pair of paralleled feed lines will be just above 50 Ω. A 75 Ω cable can do almost as well.

Table 10-1

Summary of Collinear Parameters Compared to Single Dipole

C-C Spacing	*Gain (dBi)*	*Gain (dBd)*	*Beamwidth*	*Z(Ω)*	*Length Correction*
Single Dipole	7.6	0	85.8°	67	100%
0.5 λ	9.5	1.9	53.4°	88	99%
0.625 λ	10.8	3.2	40°	65	99%
1.0 λ	10.5	2.9	29.8°*	66	100%

*Broadside lobes only.



Fig 10-8 — Azimuth pattern of two element collinear array with center-to-center spacing of 1 λ.

The Double Zepp

The extended double Zepp (EDZ), discussed in Chapter 9 to illustrate transmission-line transformation of nonresistive loads, and its companion, the (non-extended) double Zepp, are two easy-to-implement collinear arrays. The double Zepp looks like a center-fed full-wave dipole, but is really two λ/2 dipoles, each end-fed in-phase with a single transmission line. The impedance at that point at resonance is quite high, around 5800 Ω for a 10 MHz system of #12 wire 50 feet high.

Using our expression from Chapter 9 for finding the impedance of a λ/4 matching section to match to 50 Ω, reveals that a 538 Ω line is needed. While you could construct that line, a common 600 Ω line will transform the impedance to 62 Ω, yielding a usually acceptable SWR of 1.2:1 for 50 Ω line. The configuration was shown in **Fig 10-9**.

The azimuth pattern of the double Zepp is the same as a dual-fed collinear with 0.5 λ spacing. The extended-double Zepp with its matching section is described in Chapter 9. The extended double Zepp azimuth pattern is shown in Fig 9-3. Note that the out-of-phase radiation from the center section of the extended double Zepp results in a slightly ragged pattern compared to the 0.625 λ dual-fed collinear; however, it is close enough to work well in most applications and is often easier to construct.

Notes

[1] J. Kraus, W8JK (SK), "Directional Antennas with Closely-Spaced Elements," *QST*, Jan 1938, pp 21-25.


Total Length 2 x 0.5 λ Each Side = 1.0 λ total
Quarter-Wave Transformer with Z0 of 600 Ω to Match Antenna Z to approximately 50 Ω
UBA0080

Fig 10-9 — Configuration of center fed Zepp version of two element collinear array.

Review Questions

10-1. Discuss the benefits and limitations of 2-element broadside arrays as a means of focusing radiation at low elevation angles.

10-2. Discuss the benefits and limitations of 2-element end-fire arrays.

10-3. Consider the collinear array of Fig 10-5. Why can't it be fed via a pair of λ/4 matching sections?

10-4. What factors might you consider to decide between using an extended-double-Zepp and a dual 0.625-λ spaced dual-fed collinear pair?

Chapter 11

Wideband Dipole Antennas



The X-shaped spreaders on either side of the center of the wideband cage dipole at W1AW

Contents

What's the Story About Bandwidth? 11-2

The Two Dimensional Cage — the "Fat" Dipole Antenna 11-4

The Conical Dipole and Fan Dipole 11-5

The Folded Dipole Antenna 11-6

The Terminated Wideband Folded Dipole Antenna 11-6

Review Questions 11-7

What's the Story About Bandwidth?

To date I have been discussing antennas designed for a single frequency, usually a convenient 10 MHz. It is important to recognize that any signal, except for a steady carrier, includes sidebands around the operating frequency. To avoid distortion of the transmitted signal, the antenna needs, at a minimum, to be able to radiate all the frequencies that are part of the transmitted signal — without distortion.

The Effects of Bandwidth Restriction

All of the antenna parameters we have discussed — SWR, elevation pattern and azimuth pattern — will change when the transmit frequency is changed. Each can also have the effect of making a change in the received signal level, even if the receiving antenna has no restrictions itself.

For narrowband signals, usually the first transmit parameter to exhibit a noticeable difference is the SWR. While the SWR itself won't result in a change in antenna response, the resulting change in impedance as seen at the transmitter will often result in a change in the power delivered to the load. Depending on the loss of the transmission line to start with, an increase in SWR can also result in an increase in line loss, also reducing the power delivered to the antenna.

How Much Bandwidth do You Need?

Different transmission modes require different bandwidths to carry the associated sidebands. **Table 11-1** is a summary of common signal types encountered in radio systems, along with their requisite bandwidths. These bandwidths apply to a transmission system operating on a single carrier frequency. While there are many such single-frequency broadcasters and communications systems, there are also many that require operation on multiple frequencies. These fall in a few categories that I'll discuss below.

Table 11-1

Bandwidths of Common Transmission Modes

Mode	*Use*	*Typical Bandwidth*
Radiotelegraph	Manual Keying	<100 Hz
Radioteletype	Manual Keyboard	<300 Hz
SSB Voice	Communication	3 kHz
AM Voice	Communication	6.6 kHz
AM Voice/Music	Broadcast	10 kHz
FM Voice	Communication	15 kHz
FM Stereo Music	Broadcast	150 kHz
Analog Television	Broadcast	6 MHz
Pulse	Data/Radiolocation	2/Pulse Width[1]

[1]Typical, varies significantly with risetime and pulse shape.

Operation Across a Band of Frequencies

Instead of a single frequency of operation, some services require users to be able to operate on different channels within a band of frequencies. Examples of this kind of operation include the Amateur Radio service that allows operation on multiple, fairly wide bands across the radio spectrum. Another example is the maritime radio service.

Maritime HF operation occurs in multiple bands across HF and into VHF to allow for different ranges and propagation conditions. Within each band the operator initiates communication on a *calling channel* and then switches to one of a number of *working channels* to pass traffic. The selected working channel will depend on the type of service, category of distant station (shipboard, shore station, drawbridge or USCG, as examples — each with different assigned groups of channels) and whether or not a particular channel is in use, so most stations must be prepared to operate on virtually any channel.

In either of the above examples, operational simplicity results if the design of the antenna is such that an operator can select any channel within a band without having to make a change in the antenna system or the transmitter output circuit. The ability to accomplish this is usually a function of the width of the band as a fraction of the band's center frequency.

Do We Have a Problem?

A good example of such a band is the US 80 meter amateur band. It extends from 3.5 to 4.0 MHz, a width of 0.5 MHz, or 13.3% of the band center. Other amateur HF bands have a narrower percentage bandwidth, so this is a good limiting case to look at. If you can make 80 meters happen, you can succeed on any other HF amateur band.

I'll start examining the issue by looking at a good baseline configuration — a $\lambda/2$ long thin wire dipole. I will assume that you have a radio system that can work into a 2:1 SWR at 50 Ω. I will use a standard dipole height of 50 feet, and find a length that makes the SWR approximately equal at the band edges. The result is shown in **Fig 11-1**. The 2:1 SWR bandwidth is around 150 kHz, with an SWR that rises above 5:1 at the band edges. It looks like something will have to happen to obtain an antenna that meets the requirements — it would take more than three separate dipoles of this simple design to cover the entire band! At around 130 feet in length, this is not a solution for everyone — besides, I don't want to require the operator to have to remember to switch antennas in mid-operation as channels are changed.

So What Should You Do?

The first step is to observe that I have posed a bit of a hurdle by not having an antenna that has an impedance of 50 Ω at any frequency in the band. Assume that I can design a wideband 69:50 Ω transformer that will transform the antenna mid-band load of 69 Ω to the 50 Ω that the transmission line and radio want to see. There are a number of ways to do that, so please assume I have one at hand. The result is shown in the plot of **Fig 11-2**. Note that I now can cover 200 kHz with an SWR of 2:1 — I'm headed in the right direction but I'm not there yet.

In Chapter 4, I discussed the relationship of antenna length-to-thickness ratio as it affects impedance change with frequency. Another term for that is *bandwidth*, so let's explore that as a possibility. Using *EZNEC*, it is easy to adjust the wire diameter to get the SWR bandwidth I want. I find that by increasing the wire from #12 to 24 inches in diameter I can achieve the desired SWR bandwidth, as shown in **Fig 11-3**.

Using tubing for elements is quite common at higher frequencies, and thick-diameter tubing is found as a material in a number of broadband VHF antenna designs. Unfortunately, even with the shortened length of the thicker antenna (from 127 to 118 feet), hoisting that much thick tubing up 50 feet may not be a feasible solution, in spite of how easy it is to model.



Fig 11-1 — SWR plot of 80 meter dipole of #12 wire at 50 feet.



Fig 11-2 — SWR plot of 80 meter dipole of #12 wire at 50 feet referenced to 69 Ω.



Fig 11-3 — SWR plot of 24 inch diameter 80 meter dipole at 50 feet referenced to 69 Ω.

Enter the Cage Antenna

Instead of using tubing, you can simulate the current flow on a tube by providing multiple wires along its length at some radius from the center. The more wires you have, the closer it will act like a piece of tubing. Consider an antenna made of four wires, equally spaced on the corners of a square with an 8 foot diagonal shown in **Fig 11-4**, you achieve virtually the same SWR performance as the 2 foot diameter tube, with much less weight. Additional wires will result in a smaller cross section required, but a heavier structure. A cage antenna of six wires about 1 foot across was used at the US end of the first amateur transatlantic communication back in 1923.



Fig 11-4 — Details of a four wire cage antenna.

A Two-Dimensional Cage — the "Fat" Dipole Antenna

Instead of making a three dimensional skeleton of tubing, you can simplify things even further, by adding a parallel wire some distance from the first. The configuration is shown in **Fig 11-5**. The outside ends are both at the same potential, so they can be connected, or not as you wish. Wider spacing will determine the bandwidth for this band, but a spacing larger than about 1 foot doesn't change things much. I have made an *EZNEC* SWR plot of such a dipole with a 1 foot spacing, as shown in **Fig 11-6**. Compare this with the SWR plot of a single wire "thin" dipole in Fig 11-1.

While this configuration almost meets a 3:1 SWR goal, rather than my 2:1 SWR goal for 80 meters, when scaled it will cover any higher HF amateur band. Some radios, more tolerant of SWR, will work across all of 80 meters as well.


Increasing Spacing Results in Wider Bandwidth
UBA0085
50 Ω Transmission Line To Radio

Fig 11-5 — Details of an HF two dimensional "fat dipole" configuration.



Fig 11-6 — SWR plot of an 80 meter fat dipole with 1 foot spacing between wires.

The Conical Dipole and Fan Dipole

An alternative to a large-diameter cylinder antenna, or its wire equivalent, is a dipole made from conical sections with their apexes at the center of the antenna. Again, metal cones are feasible at VHF and above, but mechanically difficult at HF. An approximation to a cone can be constructed using multiple wires on each side of the antenna center. A five wire configuration is shown in **Figs 11-7** and **11-8**. The SWR plot in Fig 11-8 assumes the use of a transformer to match from 40 to 50 Ω. Again, this doesn't quite meet my 2:1 criterion across the band, but it is pretty close and will work for bands with a band-to-center frequency ratio of about 9%.

By using a two dimensional equivalent of a cone, you have the *fan dipole* shown in **Fig 11-9**. This provides considerable mechanical simplicity, since a single halyard can easily hoist each end, perhaps guided by a spacer or two. I have selected a spacing of 4 feet at the ends for the SWR curve shown in **Fig 11-10**. As you would expect, it is not quite as effective as the three-dimensional version, but it may be sufficient for many applications.


Increasing Angle Results in Wider Bandwidth
UBA0087
50 Ω Transmission Line To Radio

Fig 11-7 — Details of an HF "skeleton cone" dipole configuration.



Fig 11-8 — SWR plot of an 80 meter skeleton cone dipole with 4 foot radius cone.


Increasing Angle Results in Wider Bandwidth
UBA0089
50 Ω Transmission Line To Radio

Fig 11-9 — Details of an HF two dimensional cone or "fan dipole" configuration.



Fig 11-10— SWR of an 80 meter fan dipole configuration with end spacing of 4 feet.

The Folded Dipole Antenna

An interesting dipole variant is one called a *folded dipole*. This is actually two dipoles — one fed in the center — and one fed at the ends, in close proximity to each other, as shown in **Fig 11-11**. The combination of the two antennas results in two differences from the usual dipole:

The impedance is four times the impedance of a single dipole — nominally 280 Ω rather than 70 Ω — a close match to common 300 Ω transmission line. The bandwidth is similar to a dipole with wires of the same spacing; however, the folded dipole offers an opportunity to have such a dipole with a higher impedance — especially beneficial in some kinds of arrays.


Each Wire Length, Approximately λ/2
300 Ω Transmission Line or
6 : 1 Transformer to 50 Ω
to Transmitter
UBA0091

Fig 11-11 — Details of an HF folded dipole configuration.

The Terminated Wideband Folded Dipole Antenna

It will likely not come as a surprise to anyone who has read this far that one way to have a wideband load on a transmitter is to connect it to a resistor. Unfortunately, while providing a good match, resistors don't generally radiate energy, except perhaps as heat, very effectively!

An interesting combination of a resistive load and long connecting wires that does divide power between resistive heating and radiation from the antenna is called the *terminated wideband folded dipole* (TWFD). The configuration is shown in **Fig 11-12**. They can be made in different lengths; however, I have selected a 95-foot version for modeling. This antenna is available as a commercial product, advertised to cover the range of 3 to 30 MHz with a reasonable SWR. One look at the plot in **Fig 11-13** indicates that it appears to deliver on the bandwidth promise.


R=850 Ω
17 : 1 Transformer to 50 Ω
to Transmitter
50 Ω Transmission Line
to Transmitter
UBA0092

Fig 11-12 — Details of a terminated wideband folded dipole (TWFD) configuration.



Fig 11-13 — SWR of 95 foot terminated wideband folded dipole (TWFD).



Fig 11-14 — Broadside gain of 95 foot terminated wideband folded dipole (TWFD).

Not surprisingly, there is a penalty associated with this type of antenna and that is in radiating efficiency. Any power that is dissipated in the resistor is not radiated and thus there is less available than would be the case of an antenna made of conducting material. **Fig 11-14** shows the broadside gain as a function of frequency. Compare these values to a λ/2 dipole over typical ground with a broadside gain of at least 7 dBi (increasing somewhat with frequency), and you will see that there is a penalty of at least 4 dB starting above its λ/2 frequency of around 5 MHz. Below that its penalty is significantly higher, reaching about 16 dB at 3 MHz.

The dip in broadside output at 20 MHz is due to pattern splitting. The antenna actually has a gain of around 4 dBi at 50° off broadside. This may or may not be an issue depending on how it is used. If the far end destination is the same at all frequencies, then this broadside null would make the antenna a poor choice if it always has to radiate towards the broadside direction — such as in a point-to-point automatic link enablement (ALE) system, which will be searching for frequencies that have good propagation and automatically switch equipment to an optimum frequency.

In spite of the fact that many dedicated antenna fans don't like to see resistors in antennas, the TWFD may be a good choice in some applications. At the lower portion of the HF spectrum, received signal-to-noise ratio (SNR) is often limited by external noise, so a loss in the antenna system won't reduce received SNR. On the transmit side, a government-funded station may be able to just throw a switch to add 10 dB of power and more than make up for the antenna loss at many frequencies! Being able to change frequencies without worrying about antenna operation is a great convenience, especially for untrained or stressed operators.

Notes

[1] *TLW* is supplied with *The ARRL Antenna Book*, 21st Edition, available from the ARRL Bookstore at **www.arrl.org/catalog/** order number 9876 — $44.95.

Review Questions

11-1. Describe some applications for which a thin-wire dipole would have sufficient bandwidth.

11-2. What would be the likely effects of operating a 3.5 MHz transmitter into an antenna with an SWR as shown in Fig 11-1?

11-3. Under what conditions might the TWFD antenna be a good choice? What are the penalties of using one compared to separate dipoles for a number of channels?

Chapter 12

Multiband Dipole Antennas

Resonant circuits allow both these antennas to operate on multiple bands.

Contents

What Do We Mean by Bands? 12-2
What Does Multiband Mean? 12-3
Taking Advantage of Multiple Resonances....................12-3
Multiple Resonator Antennas 12-5
Antennas With Resonant Traps 12-6
The Center Fed Zepp 12-7
The G5RV Dipole...12-9
Wrap Up 12-9
Review Questions...12-10

What Do We Mean by Bands?

In this context, a band is a range of frequencies assigned to a particular function. You are familiar with the MF AM broadcast band, covering 550 to 1700 kHz, a range that is a challenge for wideband antennas. In addition, there is broadcasting throughout the HF region in multiple bands as shown in **Table 12-1**. Other services with multiple HF bands include the Amateur Radio, maritime and aeronautical services.

In the case of services using HF allocations, it is common to have multiple bands assigned to the same function, in some cases carrying the same information, so that as the ionospheric conditions change a listener can shift from a channel in one band to a channel in another and still maintain communication. In some cases, as with a diversity receiving system using frequency diversity, this happens automatically. In other cases a manual frequency change is required. It is convenient to be able to use the same antenna to cover multiple bands. While having a separate antenna for each band is a possibility, it often is not practical from a real-estate resource standpoint.

Table 12-1

Selected US HF Frequency Allocations by Service* (MHz)

Amateur	*Aeronautical*	*Maritime*	*Broadcast*
		3.0 – 3.155	
			3.2 – 3.4**
	3.4 – 3.5		
3.5 – 4.0			
			3.9 – 4.05**
		4.0 – 4.438	
	4.65 – 4.75		
			4.75 – 4.995**
			5.005 – 5.1**
5.33 – 5.41***			
	5.45 – 5.73		
			5.9 – 6.2
		6.2 — 6.525	
	6.525 – 6.765		
7.0 – 7.3			
			7.2 – 7.35**
		8.195– 8.815	
	8.815 – 9.040		
			9.5 – 9.9
	10.005 – 10.1		
10.1 – 10.15			
	11.175 – 11.4		
			11.6 – 12.1**
		12.23 – 13.2	
	13.2 – 13.36		
			13.57 – 13.87
14.0 – 14.35			
			15.1 – 15.6
		16.36 –17.41	
			17.9 – 18.03
18.068 – 18.168			
		19.68 – 19.8	
21.0 – 21.45			
			21.45 – 21.85
	21.924 – 22.0		
24.89 – 24.99			
		25.07 – 25.21	
			25.67 – 26.1
		26.1 — 26.175	
28.0 – 29.7			

*This should be considered representative and not official.
There are some variations between allocations in different regions of the world.
Allocations do not necessarily imply usage.
**Outside US only.
***Five specific channels allocated in this range.

What Does Multiband Mean?

In our last chapter, we discussed *wideband* dipole antennas. It should be clear that if multiple bands are within the bandwidth of a wideband antenna, it could also serve as a *multiband* antenna. What I will be talking about in this chapter is a group of dipole antennas types that can operate on multiple distinct bands — but not necessarily all the frequencies in between, as would be the case with a wideband antenna.

Taking Advantage of Multiple Resonances

As noted in Chapter 4, particularly in Figs 4-3 through 4-5, at frequencies that are approximately odd multiples of a dipole's λ/2 frequency a dipole will show an impedance very similar to that at its λ/2 frequency. If you have allocations that include bands that are odd multiples of the frequency of other bands, you can take advantage of this to get an additional band for "free." As noted in Table 12-1, most services have band with, or close to, such a frequency relationship.

As an example, consider the US amateur bands at 7 and 21 MHz (40 and 15 meters). If you construct a λ/2 dipole for 7.15 MHz, at the usual height of 50 feet above ground, you will find that it has a 50 Ω SWR curve such as that shown in **Fig 12-1**. While the SWR is very close to the usual design goal of 2:1 across the band, by inserting a 1.5:1 transformer at the feed it is even better, as shown in **Fig 12-2**.



Fig 12-1 — SWR plot of λ/2 dipole for 7.15 MHz, at a height of 50 feet above ground.



Fig 12-2 — SWR plot of antenna in Fig 12-1 with 1.5:1 transformer at feed point.

Matching a Dipole on Two Bands

Now try feeding the antenna across the 15-meter band. You would think this should work just fine. Oops — as shown in **Fig 12-3**, things don't quite work that way. On 15 meters the same physical height above ground is three times as high in terms of wavelength than on 40 meters. And other factors have similar effects. The result is that the antenna is mistuned on the higher band. By retuning the antenna for 15 meters in the *EZNEC* model, shortening it by 1.4 feet, you end up with the result shown in **Fig 12-4**. Note that this assumes that the 1.5:1 transformer is designed to work over the 7 to 21.45-MHz range — not usually a problem.



Fig 12-3 — SWR plot of antenna in Fig 12-2 over the 15 meter band.

Now what is happening on our original band — 40 meters? As shown in **Fig 12-5**, not surprisingly, it is not quite as good as it was before, but it comes very close to meeting the design criterion. It is generally true that the tuning will be much more critical on the higher band, so tuning there — perhaps with a bit of "Kentucky windage" back and forth — it is often possible to come up with an antenna with a satisfactory match on both bands.

Is That All There is to it?

It's fine to be able to properly feed energy into — and receive energy from — an antenna on two bands, but you also need to consider where the energy goes to or comes from. Your antenna at a height of 50 feet will be about 0.36 λ high on 40 meters and 1.08 λ high on 15 meters. This difference in electrical height means that the peak of the elevation lobe will move from 40° on 40 meters to 13° on 15 meters. This will have implications for your transmission range, because the 40° elevation is optimum for medium ranges (say, out to 2000 miles) while a 13° takeoff angle will be best at longer ranges — it all depends on the effective height of the ionosphere.

In addition, the azimuth pattern will change from the familiar bidirectional "figure-eight" pattern of a dipole to a much more complex pattern, as shown in **Fig 12-6**. This is a characteristic of center-fed antennas that are used on frequencies above 1 λ long. Note that, just as in the case of elevation angles, this may be either a benefit or liability depending on where the other end of the communication link is located. In this case, the gain at the peak of the broadside beam is almost identical for the two cases, although more precise aiming accuracy is required on the higher band.



Fig 12-4 — SWR plot of antenna in Fig 12-2 shortened by 1.4 feet over the 15 meter band.



Fig 12-5 — SWR plot of antenna of shortened antenna over the 40 meter band.



Fig 12-6 — Azimuth plot of antenna on 40 meters (solid line) compared to 15 meters (dashed line).

Multiple Resonator Antennas

The use of antennas on odd harmonic resonances is convenient, but will likely never cover all your multiband antenna requirements. There are a number of approaches that can provide similar performance, usually at some cost in terms of additional complexity.

Parallel Dipoles for Multiple Bands

One approach is to join multiple antennas together in the same space and using the same transmission line. This is generally referred to as *parallel dipoles*, and is shown in **Fig 12-7**.

The concept on which this is based is that with antennas at widely different frequencies, each will be resonant within its band and will have a sufficiently high impedance on other bands so it doesn't readily accept power from the transmission line. While this makes a fine story, and the arrangement is often successfully employed, there are two pitfalls that can limit the usefulness of this approach:

- In addition to the connected parallel impedance of the additional dipole, there is a significant mutually coupled impedance that may be hard to predict. It will range from negligible to significant as the direction of the second dipole is changed from being perpendicular to, towards being parallel to the first.
- While the impedance may be high, except for harmonic frequencies, it will generally be reactive resulting in a need to retune the antenna lengths compared to a single-band dipole.

You must do some trimming to make everything work. The good news is that any energy that goes into the off-band dipole will be radiated, although not necessarily in the desired direction.



Fig 12-7 — Configuration of parallel dipoles for two bands.

Parasitically Coupled Multiband Antennas

A solution that is somewhat similar to the previous parallel dipoles is actually another form of parallel dipole — in a different sense of the word. While parallel in the previous section referred to a parallel electrical connection, it is also possible to couple from one parallel dipole to another tuned to a different frequency without direct connections. This is based on mutual impedances and is called *parasitic coupling*. See **Fig 12-8**.



Fig 12-8 — Configuration of parasitically coupled dipoles for two bands.

Several commercial manufacturers of Amateur Radio directive antennas for the higher HF regions have used this concept successfully. While the concept is simple, successful implementation may be a bit tricky. Modeling efforts indicate that spacing between driven and parasitic element is critical for successful operation. The spacing between driven (lower frequency) dipole and parasitically coupled element needs to be about 0.003 to 0.004 λ to achieve appropriate coupling.

The good news is that the coupled element doesn't have much impact on the tuning or pattern performance of the driven (lower frequency) dipole. The bad news is that the SWR bandwidth of the higher frequency element(s) is narrower than would be the case for a connected dipole on the same band. Adding additional bands in this way makes for additional interaction and complexity, although the promise of a compact and inexpensive multiband structure certainly seems attractive.

Antennas with Resonant Traps

A parallel-resonant circuit has the property that it has a high impedance at its resonant frequency. A high impedance acts very much like an insulator. By placing such a circuit on each side of a dipole antenna at the λ/2 end points corresponding to the resonant frequency, the antenna effectively ends there for that frequency. At a lower frequency, the parallel-resonant circuit is no longer resonant and looks like an inductance. The configuration is shown in **Fig 12-9**.

Fig 12-10 shows the SWR plot of such an antenna made for the 80 and 40 meter amateur bands. The traps are made from 10 µH inductors in parallel with 50 pF capacitors, along with the additional capacitance of the leads. This results in resonance around 7 MHz. On the lower frequency, the trap looks like an inductance, and it serves to act as if part of the antenna became rolled up, resulting in a shortened overall electrical length.

There is nothing to prevent the addition of other traps on each side to provide operation on additional bands, and you will frequently encounter this. An advantage of this arrangement over others to be discussed is that this method maintains the broadside response pattern of a dipole on each band — not the case with some other multiband designs.

On any higher-frequency bands without traps, the trap acts like a capacitor and thus tends to make the antenna look electrically shorter than its physical length. Since there are an infinite number of combinations of L and C that can be resonant at any frequency, it is possible to select a pair that are resonant at 7.15 MHz and take advantage of this property. Chester Buchanan, W3DZZ, developed such a trap dipole in the 1950s with resonances in the 80, 40, 20, 15 and 10 meter bands — all the HF amateur bands at that time.[2] **Fig 12-11** shows the *EZNEC* SWR plot of such an antenna.



Fig 12-9 — Configuration of two-band trap dipole for 80 and 40 meters.



Fig 12-10 — SWR of two-band trap dipole in Fig 12-9 showing resonances on 80 and 40 meters.



Fig 12-11 — SWR of two-band trap dipole in Fig 12-9 from 10 to 32 MHz showing additional resonances on 20, 15 and 10 meters.

The Center Fed Zepp

As noted in **Table 4-1** and Figs 4-3 to 4-5 and earlier sections of this chapter, you can use dipoles of electrical lengths other than λ/2 effectively. The consequence of using an antenna that isn't resonant (or which is resonant but doesn't match the transmission feed line) is that you will need a matching network to couple power from the transmitter to the antenna system. If the matching system, generally called an *antenna tuner*, is located at the antenna itself, 50 Ω coaxial cable can be used for the run to the radio room. If the matching network is located near the radio equipment, particular attention must be paid to losses in the transmission line, since the SWR will be quite high on many bands.

A popular antenna system for wide frequency coverage is one called a *center fed Zepp*. This antenna is a variation of the antenna that used to trail behind Zeppelin airships in the 1930s. The antenna is not "wideband" in the same sense as previous examples. Instead, it has a feed impedance that varies widely with frequency, but which is compensated for at the radio end of the transmission line by a tunable matching network. The center fed Zepp can operate on all frequencies above (and even somewhat below) its λ/2 resonant frequency.

The concept of this antenna is to start with a λ/2 dipole at the lowest frequency of operation, as shown in **Fig 12-12.** Feed the dipole with a low-loss transmission line and use a matching device at the radio end to adjust for whatever impedance is found on the frequency you wish to operate.

The design parameters for such an antenna are based on λ/2 at 3.6 MHz and fed with 100 feet of nominal 450 Ω (actual Z_0 around 400 Ω) "window" transmission line. The resulting SWR curve is shown in **Fig 12-13**. The resulting line losses are shown in **Table 12-2**. The dipole length in feet is found by dividing 468 by 3.6, resulting in 130 feet. I will assume a height of 50 feet, reasonable for many locations with mature trees.

Note that in spite of an SWR as high as 12:1, the worst-case loss in this low-loss transmission line is only around 0.5 dB — hardly noticeable. By contrast, consider feeding the antenna with typical 50 Ω coax, which would be fine at the antenna's λ/2


Wire Length, 468 / F at Lowest Frequency
Low-Loss Transmission Line
Adjustable Matching Network
50 Ω to Transmitter
UBA0106

Fig 12-12 — Configuration of center fed Zepp.

Table 12-2

Design Parameters for Center-Fed Zepp

Frequency	*Antenna Z, Ω*	*SWR at 400 Ω*	*Line Loss (dB)*
3.6	63 – *j* 39	6.4	0.128
5.3	351 + *j* 868	7.25	0.176
7.2	4253 – *j* 1232	11.5	0.399
10.1	105 – *j* 595	12.4	0.501
14.2	1472 + *j* 1816	9.45	0.428
21.2	648 + *j* 1042	6.27	0.385
28.3	348.4 + *j* 606	4.43	0.318



Fig 12-13 — SWR plot (400 Ω reference) of center-fed Zepp.

resonance. If you used lightweight RG-58A cable, for example, the SWR at 28.3 MHz would be 28.2:1. And the total loss in the cable would be a staggering 10.5 dB — burning up more than 90% of the power in the transmission line, with less than 10% of the power actually delivered to the antenna.

Note the azimuth radiation patterns for selected bands shown in **Fig 12-14** through **Fig 12-17**. At 7.2 MHz, where the antenna is about 1 λ long, the pattern looks very much like what you would expect to see from a λ/2 dipole. The sharp-eyed observer will note that compared to that of a λ/2 dipole, the lobes are sharper and the gain is a bit higher. As the electrical length moves above 1 λ, the pattern gets significantly more complex. This can be a mixed blessing. On the plus side, you get more gain and coverage into different regions on the higher bands. On the other side, if you wish to communicate (or listen) to specific locations, you may wish you had the dipole's simple pattern on every band.

Another band-to-band difference is that at the single height of 50 feet, the elevation angle response is lower as the operating frequency is increased. This allows for longer-range communication at higher frequencies, again a possible benefit, depending on requirements.



Fig 12-14 — Azimuth radiation pattern of 3.6 MHz center fed Zepp at 7.2 MHz.



Fig 12-15 — Azimuth radiation pattern of 3.6 MHz center fed Zepp at 10.1 MHz.



Fig 12-16 — Azimuth radiation pattern of 3.6 MHz center fed Zepp at 14.2 MHz.



Fig 12-17 — Azimuth radiation pattern of 3.6 MHz center fed Zepp at 28.3 MHz.

The G5RV Dipole

The G5RV, named for its late developer Louis Varney, G5RV, is a variation of the center fed Zepp. Varney originally designed the dipole to be 1.5 λ long on the 20 meter band, where it could achieve a modest amount of gain over a half wave dipole, and yet could also operate on other amateur bands with an antenna tuner. This approach is in contrast to most multiband single-wire dipoles described earlier, which start off with a half-wave-long wire at the *lowest* frequency of operation. The G5RV employs a simple feed system using a transition between open-wire and coaxial transmission lines and has moderate SWR on bands other than 20 meters.

The G5RV antenna has a "flat top" length of 102 feet and Varney fed his with what he called a "20 meter matching section" of 34 feet of low-loss 300 Ω TV-ribbon line, followed by enough 75 Ω coax to get down to the transmitter. Most designs nowadays use more commonly available 450 Ω window line for the 34 foot matching section.

A plot of the SWR of an *EZNEC* model is shown in **Fig 12-18** for 50 Ω coax. On 15 meters the SWR is rather high, in excess of 25:1, for example. In the 20-meter band, the SWR rises as high as about 4:1.

I have used a few G5RVs over the years and believe that their simplicity, more than their performance, accounts for their popularity. In my experience it is very difficult to adjust the two available parameters — flat-top length and matching line length — and end up with good SWR performance on many amateur bands. That being said, I have achieved a 5:1 SWR on most bands and find that is low enough to use low loss 50 Ω coax if the runs are short enough. As Varney recommended, a tuner makes life easier at the radio end of the feed line.



Fig 12-18 — SWR plot (50 Ω reference) of G5RV dipole.

Wrap-Up

It is clearly possible to use a dipole antenna or its variants to achieve satisfactory operation on multiple bands. This can be very helpful to those trying to install an HF station on a property of limited size. In addition, the ability to not have to switch antennas when changing frequencies is a major benefit.

The downside is that while a single-band dipole is very easy to tune and place into operation, most multiband antennas (the center-fed Zepp is a notable exception) require considerable interrelated tuning steps to get everything working as anticipated.

There are other types of multiband antennas besides those based on the λ/2 horizontal dipole. I will discuss them in subsequent chapters.

Notes

[1] *TLW* is supplied with *The ARRL Antenna Book*, 21st Edition, available from the ARRL Bookstore at **www.arrl.org/catalog/** order number 9876 — $39.95.

[2] C. Buchanan, W3DZZ, "The Multimatch Antenna System," *QST*, Mar 1955, pp 22-24.

Review Questions

12-1. Why is a multiband antenna a benefit?
12-2. Of the antennas described, which provides maximum signal strength in the broadside direction on all bands?
12-3. What are the benefits of a multiband antenna with different azimuth patterns on different bands?

Chapter 13

Vertical Monopole Antennas



The field from a monopole extends uniformly in all directions.

Contents

How Can Half a Dipole Work? 13-2
Wrap Up 13-5
Review Questions 13-5

How Can Half a Dipole Work?

If, by just looking at the name, you conclude that a ***monopole*** ought to be half a **dipole** — you'd be right! The hard part comes in understanding what happens to the *other half* of the antenna. The key is that a monopole is located adjacent to some kind of ground. How well it works is closely related to the nature of the nearby — as well as more distant — ground.

The key to the operation of a λ/4 vertical is that the electric field generated by a source driving the antenna terminates on the ground instead of on the other half of a dipole. **Fig 13-1** compares the electric field of a vertically oriented λ/2 dipole in free space with the field of a λ/4 monopole above a perfectly conducting ground. Note that the fields are identical in the region above ground. Not surprisingly, they don't exist below ground.

Radiation from a Monopole

The radiation elevation pattern of a λ/4 monopole over perfect ground is shown in **Fig 13-2**. With a "perfect ground" both under the antenna and at some distance, the reflected and direct signals combine to result in maximum radiation at the horizon, just as you would have from a vertical dipole in free space. This condition is similar to what occurs with a vertical monopole erected in an ocean communicating to another vertical antenna in the same ocean at distances at which the Earth is approximately flat. For longer distances, the broadside signal will maintain its direction tangent to the Earth's surface, resulting in long distance propagation if the ionosphere supports that frequency.

The Effects of Imperfect Ground



Fig 13-1 — At A, electric field lines of a vertical dipole. At B, monopole over perfect ground.



Fig 13-2 — Elevation pattern of antenna in Fig 13-1B.

In many cases, an ocean is not at hand and the reality of imperfect ground must be taken into account. The properties of real ground that change the way an antenna performs can be characterized by its conductivity and dielectric constant. These vary widely by region, as well as by localized conditions within a region. The ground has two distinct effects on the performance of a monopole. Many people confuse these, so it is important that they be clearly understood.

The Ground as a Part of the Antenna Load

To connect a transmission line (usually a coaxial cable) to a monopole, you have two connections to make. The center conductor is usually connected to the insulated monopole. The shield must be connected to something else — *ground*. This ground connection must carry every bit of current that the monopole does, in order for the antenna to accept the transmitter power. A major hitch is that imperfect ground doesn't have a good GROUND terminal to connect to.

To properly connect to the ground, we need to connect to the region on which the electric lines of force terminate. This generally requires bare radial wires at or beneath the surface of the ground. Note that the "ground rods" often used for lightning protection and power neutral grounding connect largely below the surface. Because of the skin effect, higher frequency currents tend to flow near the surface of real soil. The resulting connection will have some effective resistance, lots in the typical ground rod, less as more and longer ground radials are used near the surface. For the purpose of determining the power that actually reaches the antenna, the situation can be analyzed as an equivalent circuit. See **Fig 13-3**.

At resonance, $L_A = C_A$ and thus the resistance shown as R_R represents the load of the antenna itself, as if it were over perfect ground. This is called the *radiation resistance* of the antenna. Power dissipated in the radiation resistance becomes the actual power radiated by the antenna. The resonant radiation resistance of this ideal monopole is just half of that of a resonant dipole in free space, or 36 Ω.

R_G represents the equivalent RF resistance of the ground connection.



Fig 13-3 — Equivalent electrical circuit of monopole antenna over real ground.



Fig 13-4 — Configuration of ground-mounted monopole with radial ground system.

Power dissipated in this resistance ends up warming up the ground — not usually a goal of the antenna designer. The total power delivered by the source is thus split up into a portion that is radiated and a portion that is dissipated in the ground. The efficiency of a monopole can be defined as the fraction of the power delivered by the source that ends up being radiated by the antenna. For a current *i* that flows in the circuit, the power delivered is:

$$P = i^2 \times (R_R + R_G) \qquad \text{Eq 13-1}$$

While the radiated power is just:

$$P_R = i^2 \times R_R \qquad \text{Eq 13-2}$$

Thus the resulting efficiency is:

$$P_R / P_R = R_R / (R_R + R_G) \qquad \text{Eq 13-3}$$

Achieving High Efficiency with a Ground Mounted Monopole

The usual ground system for feeding power to a vertical monopole consists of buried radial wires extending out in all directions from a point just beneath the base of the antenna. See **Fig 13-4**. The radials wires ideally would be uninsulated to make maximum contact with the Earth's surface. Each radial is typically λ/4 to λ/2 in length. Over typically lossy ground, the antenna's effectiveness is a direct function of radial quantity. The resistance of R_G as measured by Jerry Sevick, W2FMI, in typical New Jersey soil is shown in **Fig 13-5**.

Note that the ground resistance approaches 0 Ω and thus the total load resistance approaches the value of R_R as the quantity reaches 100 radials. This requires a large quantity of wire, not to mention a significant amount of effort with a digging tool; however, that is exactly what is done by most commercial AM broadcast stations, which are typical monopole users. In addition, broadcasters tend to search out areas with high conductivity, so when you see such an antenna in a swamp, it isn't just because the real estate cost was low!

While it might be convenient to use a small number of radials, let's say three, a look at Fig 13-5 indicates that the antenna impedance in his soil would be about 72 Ω. If it were, in fact, 72 Ω, R_G would be: $R - R_R = (72 - 36)$ or 36 Ω. The resulting efficiency, per Eq 13-3, is thus 36/72 = 50%, corresponding to a signal loss of 3 dB, or half your power. Note that a nice match to 50 Ω cable occurs with 10 radials in this soil. While that is convenient, it also implies that R_G = 14 Ω. The resulting efficiency is thus 36/50 = 72%, or a signal loss of 1.4 dB.

For any desired efficiency, it is conceptually a simple matter to add ground radials until R_G is reduced to a value that results in an acceptable efficiency. There is often an easy trade-off between the cost of increasing transmitter power and the cost of additional radials. While the efficiency impacts both transmit and receive performance, in the lower HF region, the receiver performance is generally limited by received noise, which is reduced along with the desired signal, making the improvement moot.

There are some services, for example Amateur Radio, in which government regulations limit transmitter output power. In that case, once the limit is reached, improving antenna efficiency may be the only



Fig 13-5 — Measured resistance of resonant monopole of Fig 13-4 as a function of the number of buried radials over typical soil.



Fig 13-6 — Configuration of a monopole with an elevated ground system.

choice in order to achieve optimized transmit effectiveness from a monopole. There may be other issues to deal with. I once worked on an offshore system with vertical monopoles in which some local nationals would steal the radials at night to sell for scrap. There, we had a distinct incentive to find a way to optimize using fewer radials!

Achieving High Efficiency with an Elevated Monopole

A typical ground system for feeding power to a vertical monopole suffers from the losses due to the conductivity of imperfect soil. One way to improve on this is to elevate the monopole above ground and create an artificial ground structure with minimal losses. This can be accomplished by having multiple resonant insulated radials, each tuned to be λ/4 long, at some height above real ground.

Usual practice is to have the radials at least 8 feet above ground to avoid human strangulation or deer-antler interference (some areas may require greater heights or perhaps fencing). The configuration is shown in **Fig 13-6**. If raised well above the Earth, this antenna is called a *ground plane* and is quite popular as a VHF omnidirectional fixed-station antenna.

A monopole with an elevated ground system approaches the efficiency of a ground-mounted monopole with a large number of buried radials. Unfortunately, some of the benefits of the monopole are lost in the process, including its low visibility and lack of required dedicated real estate. Considered from another point of view, a monopole with four elevated radials requires exactly the same hardware and number of supports as two dipoles, not counting the monopole itself. If the supports can be made somewhat higher, in most cases (except perhaps on the oceanfront) the resulting dipole system will be more effective.

The Ground as a Reflector and Attenuator for the Far Field

A somewhat more subtle, but often much more significant, ground effect occurs particularly with respect to the low-angle reflection leaving the monopole. We often select a monopole because we would like long-distance propagation by low angle radiation; however, ground conductivity impacts us in two ways.

Lossy ground actually slows down the radiation in contact with the Earth's surface, resulting in a tilt to the wavefront that makes it stay in closer contact with the ground for greater distances before it is launched into space. This effect can be of benefit to medium-wave AM broadcasters, who obtain extended ground wave coverage as a result.

For those interested in the wavefront leaving the surface and launching skyward, the extended proximity to the lossy ground results in signals being attenuated by heating of the ground. This is compounded by the fact that lossy ground is a less effective reflector than a perfect ground or an ocean, so that the reinforcement at the horizon that we would like from the reflected wave is less effective than it might be.

Unfortunately, once we pick an antenna location, the ground at some distance from our antenna is even less under our control than that underneath the antenna. The result of lossy ground in the vicinity of the antenna can be seen in **Fig 13-7**, an *EZNEC* prediction of a monopole with eight radials over typical ground. Note that, unlike the perfect-ground case, shown in Fig 13-3, there is no resultant radiation at the horizon and all the low-angle radiation is reduced.



Fig 13-7 — Elevation pattern of λ/4 monopole over typical ground.

You can construct an extended ground system extending many wavelengths from the antenna base to support the very low angle radiation; however, the amount of real estate required is quite large. I have seen this done on one occasion and it worked well; however, it made use of an abandoned Air Force base, and had (surprise) a large budget.

It is interesting to compare this typical monopole with a dipole at the same height as the top of the monopole (λ/4). The two patterns are shown together in **Fig 13-8**, considering the broadside response of the dipole — it isn't quite omnidirectional, even at this height. The dipole has about the same signal at the low angles, in its best direction, as well as considerably more at the high angles. The reason for this comparison is that you clearly can get at least one support that high! Of course, a higher dipole would have significantly more low angle response.



Fig 13-8 — Elevation pattern of λ/4 monopole over typical ground compared to horizontal dipole λ/4 above typical ground.

The monopole has a null directly overhead — which is the dipole's maximum elevation angle — sometimes an advantage for either antenna, depending on your objective. In some cases, received noise comes from medium range sources that propagate at high angles. This often provides a significant advantage in received signal-to-noise ratio if the desired signal arrives at a low angle. In this application, the monopole shines, although there are even more capable antennas that will be covered later in the book.

Wrap Up

A ground-mounted vertical monopole may be a logical choice for an HF antenna, especially if omnidirectional coverage is desired. It often can be less obvious aesthetically than a horizontal antenna, and perhaps even be disguised as a flagpole or a rain gutter. A vertical also takes up very little real estate — once the ground system is installed, of course. It also can really shine in performance — especially if its base is right at the water's edge.

Monopoles are quite useful as elements in multielement HF arrays, as will be discussed in the next chapter. They offer the possibility of effective electronic beam steering in azimuth — often difficult to do with other types of elements.

Review Questions

13-1. Under what conditions can a ground mounted monopole be more effective than a horizontal antenna?

13-2. What are the major disadvantages of a monopole?

13-3. What problem does a monopole with an elevated ground solve? Why might it not be a good trade-off?

Chapter 14

Arrays of Vertical Monopole Antennas



The fields from multiple monopoles can be combined to add in desired directions. This array uses four vertical elements on corners of a square.

Contents

Arrays of Vertical Monopole Antennas 14-2
Lining Up Elements of a Vertical Array 14-2
Feeding Driven Arrays 14-4
Chapter Summary 14-6
Review Questions 14-6

Arrays of Vertical Monopole Antennas

One of the benefits of a vertical monopole discussed in the previous chapter is its omnidirectional azimuth radiation pattern. This is ideal in some applications, such as broadcasting or for a base station that needs to communicate with mobile stations in many directions. The other side of that coin is that the radiation intensity in any particular direction is less than would result from most horizontal antennas with their limited azimuth coverage. However, by using multiple monopoles arranged in arrays virtually any desired azimuth coverage can be obtained with resulting gain in desired directions. In some cases the same physical antenna array can be aimed in different directions in response to changes in requirements.

Lining Up Elements of a Vertical Array



Fig 14-1 — Configuration of a broadside array of two monopole antennas.



Fig 14-2 — Azimuth pattern of a broadside array of two monopole antennas with λ/2 spacing (dashed line) compared to that of a single monopole (solid line).

The directivity of an array of monopoles will be determined by the quantity, spacings and phase differences of the applied signals. I will discuss a number of different cases, starting with perhaps the most straightforward.

Two Element Broadside Array

This two-element broadside array consists of two monopoles, fed by equal in-phase signals. **Fig 14-1** shows the configuration. The signals combine at maximum strength along a line equidistant from both monopoles, which is perpendicular to the center of a line drawn between the elements.

The azimuth radiation pattern of such an array with a spacing of λ/2 is shown in **Fig 14-2**, compared to that of a single monopole. These patterns are for the ideal case, over perfectly conducting ground. All the effects of ground conditions relating to efficiency and far-field ground losses discussed in the previous chapter also affect the radiation from the array, to the same extent as the single monopole. The elevation pattern is essentially unchanged from the single monopole.

Note that the spacing of λ/2 is a special case in that the radiation from each element, while starting in-phase with that of its neighbor, is 180° out-of-phase by the time it reaches the other element. This results in a deep null along the line between the elements.

At spacings below λ/2, the null fills in and the reduction in sideways rejection is much less, as shown in the λ/4 case in **Fig 14-3**. For spacings greater than λ/2, the side radiation actually increases — to a



Fig 14-3 — Azimuth pattern of a broadside array of two monopole antennas with λ/2 spacing (dotted line) compared to λ/4 (solid line) and λ (dashed line).

maximum at a full λ, since the energy arriving at the other elements is now 360° out-of-phase, which is the same as being in-phase. Above λ/2 spacing, arrays have significant lobes at other azimuths, and thus most systems use spacings less than λ/2. One exception is a spacing of 5λ/8, which offers the maximum broadside gain at a cost of some spurious lobes. Its azimuth pattern is shown in **Fig 14-4**.



Fig 14-4 — Azimuth pattern of a broadside array of two monopole antennas with 5λ/8 spacing.

Two Element End-Fire Array

Just as in the case of horizontal dipoles, two monopoles fed equal currents 180° out of phase as shown in **Fig 14-5**, will have no radiation in the broadside direction. For spacing less than λ, maximum gain is in the plane of the elements. The gain increases for close spacings. The coupled mutual impedance subtracts and thus reduces the impedance at each element. **Fig 14-6** shows the pattern for spacings of λ/2 and λ/8. Any additional gain is small.

In most cases, spacings of less than about λ/8 start to show losses due to the low impedances that may offset the additional gain due to directivity. **Fig 14-7** shows the impedance of both broadside and end-fire arrays as a function of element spacing.

Two Element Cardioid Array

An interesting and useful array is one in which the elements are spaced λ/4 apart and fed 90° out-of-phase. By the time the signal from the delayed element reaches the element with the leading phase, its phase is now 90° later and the two signals are in-phase and add. The signal from the leading element, on the other hand, reaches the lagging element with a delay such that the lagging element is now 180° behind its phase and thus they cancel in that direction. The result is a very useful unidirectional pattern with a deep null to the rear, as shown in **Fig 14-8**. A transmission line section with an electrical length of λ/4 can be used to yield the desired 90° delay. In some configurations the feed line can be remotely switched between the elements to provide reversible directionality.



Fig 14-6 — Azimuth pattern of an end-fire array of two monopole antennas with λ/2 spacing (solid) compared to λ/8 (dotted).



Fig 14-5 — Configuration of an end-fire array of two monopole antennas.



Fig 14-7 — Impedance of each monopole in broadside and end-fire configurations as a function of element spacing.



Fig 14-8 — Azimuth pattern of a cardioid array of two monopole antennas with λ/4 spacing and 90° phase shift.

Feeding Driven Arrays

There is an issue that should be raised at this point about feeding complex driven arrays. Any that are not fed either in-phase or 180° out-of-phase require special attention. The patterns shown assume equal currents in each element at the desired phase.

We have mentioned that elements have mutual coupling between them that change the driving-point impedance to that of the antenna element itself plus or minus the coupled impedance. This means that unless the resulting impedance of each of the elements is the same, there will not be the same match to the transmission line and thus unequal currents as well as the possibility of unanticipated phase shifts, if the element impedances have reactive components.

There are a number of ways to deal with this issue, many beyond the scope of this book, but a few should provide examples of some current practice.

- Many AM MF broadcast stations use multielement phased antenna arrays to reach selected regions of customers or to avoid interference to other users of the same channel. They generally have adjustable matching networks at the base of each element to allow precise adjustment of current amplitude and phase. They often have remote measurement systems to determine the field strength in different directions to ensure that the adjustments are correctly made.
- A property of odd multiples of λ/4 lengths of transmission lines is that, if fed in parallel, they will deliver the identical currents to their loads — even if the load impedances for each line are different. This property can be used in some arrays to *force* identical currents to multiple elements. (See Chapter 8 in late editions of *The ARRL Antenna Book* for details.)

Steering the Beam From an Array of Monopoles

So far I have discussed all the extreme cases of feeding two driven antenna elements. In addition, intermediate phasing of elements can be used to steer a beam in virtually any direction. By delaying the phase of the signal to one element, it is (almost) equivalent to physically moving that element back (or the other one forward) by a distance corresponding to the signal delay.

Consider a signal delayed some fraction of a wavelength, in this ex-



Fig 14-9 — Configuration of a broadside array with delayed phase in one element to steer beam by about 10°.



Fig 14-10 — Azimuth pattern of the steered array of Fig 14-9.

ample $\lambda/12$ or 30°. At a wavelength of 30 meters, that corresponds to a distance of 30/12 or 2.5 meters. Our elements are spaced $\lambda/2$ or 15 meters apart. This is equivalent to shifting the axis of the antenna by an angle of $\sin^{-1}$ (2.5/15) or 9.6°. See **Fig 14-9**. The resulting pattern is shown in **Fig 14-10**.

In many applications, it is desired to have a steered unidirectional pattern. The steered array of Fig 14-9 can have additional elements $\lambda/4$ behind them, phased by 90° from each of the originals, to result in a pair of cardioid arrays with a beam steered as shown in **Fig 14-11**.

Arrays With Unequal Currents

So far, all of the arrays examined have been fed with equal currents. This is generally the case with pairs of elements, or pairs of pairs, as in the steered-cardioid array in Fig 14-11. In the case of larger arrays, the width of the array often exceeds $\lambda/2$, resulting in undesired directions at which signals from the further-apart elements add in-phase. Consider an array consisting of eight vertical monopoles each separated by $\lambda/4$ with the intent of feeding them in-phase to obtain a narrow high-gain beam broadside to the array. The azimuth pattern of such a system is shown in **Fig 14-12**.

Note that the design objectives have been met. The main beam is less than 26° wide on each side and the gain is 12.5 dBi, a very respectable signal. Notice something else, the spurious *sidelobes*. These have cropped up because of the in-phase combinations of the outer elements at 45° off axis on each side. For many applications these extra lobes are a small price to pay for the additional gain of the larger array. There are some applications, however, in which such types of sidelobes are completely unacceptable. For example, in a radar system with a rotating antenna, a single aircraft would seem to appear at different azimuths (with different strengths), resulting in false alarms and mistargeting of weapons. A modern digital system with processing can be used to eliminate the false targets; however, it is also possible to eliminate them through a change to the antenna design based on adjusting the currents in each element.

The resulting system is called a *tapered* current distribution. The idea is that the currents delivered to the outside elements are reduced in a systematic manner to deemphasize their contributions to the sidelobes, while still providing some contribution to the desired main beam. There are a number of systems in use; I will briefly describe two:

Linear taper — the currents in each element are reduced linearly starting in the center and tapering down towards each end. The slope of the taper can be adjusted with a steep slope having the most benefit, but also reducing the gain of the main beam the most. **Fig 14-13** shows the effect of applying a taper of 1, 2, 3, 4, 4, 3, 2, 1 across the array. Note that the sidelobes are almost, but not quite, gone. The beamwidth has increased by about 7° and the gain is down about 1 dB.

Binomial taper — The use of binomial coefficients as a tapering function can be shown to virtually eliminate sidelobes, albeit at a greater cost in desired characteristics. The binomial coefficients for an 8-element array are 1, 7, 21, 35, 35, 21, 7, 1. The azimuth pattern of



Fig 14-11 — Azimuth pattern of the steered array of Fig 14-9 with added cardioid shaping elements.



Fig 14-12 — Azimuth pattern of eight element broadside array with uniform current distribution.



Fig 14-13 — Azimuth pattern of eight element broadside array with linear tapered current distribution.

such an array with that current distribution is shown in **Fig 14-14**. Note that there are very low sidelobes; however, the deep side nulls are gone and the beamwidth is significantly wider, reducing the gain.



Fig 14-14 — Azimuth pattern of eight element broadside array with binomial tapered current distribution.

Binomial Coefficients

Binomial coefficients are frequently encountered in antenna (as well as filtering) systems. They are the constants preceding each variable term found by performing the algebraic raising of a binomial to a power as in $(a + b)^n$. For example, if n = 2, $(a + b)^2 = 1 \times a^2 + 2 \times a \times b + 1 \times b^2$, and the coefficients are 1, 2, 1. If n = 3, $(a + b)^2 = 1 \times a^3 + 3 \times a^2 \times b + 3 \times a \times b^2 + 1 \times b^3$, and the coefficients are 1, 3, 3, 1.

While the coefficients can be determined by algebraic multiplication, a shortcut is to observe that if they are put above each other starting with n=1, any coefficient can be found by adding the term above to the one to the left of the term above as in the following:

1, 1
1, 2, 1
1, 3, 3, 1
1, 4, 6, 4, 1
1, 5, 10, 10, 5, 1
1, 6, 15, 20, 15, 6, 1
1, 7, 21, 35, 35, 21, 7, 1
and so on.

Chapter Summary

This chapter has introduced some interesting and significant concepts in the capabilities of antennas. We have seen that multiple vertical monopoles can have their patterns shifted in various ways — broadside, end-fire, cardioid and even towards almost any azimuth by shifting the relative phase of the currents in each element. This allows the possibility of electronically steered antenna arrays, a very powerful tool in the toolbox of the antenna designer.

Review Questions

14-1. If you feed two monopoles with equal lengths of coax cable, which way will the pattern point?

14-2. If you add a $\lambda/2$ section of transmission line to one of the monopoles in question 14-1, what change will occur to the pattern?

14-3. If you feed two monopoles spaced $\lambda/4$ with equal currents 90 out-of-phase, what happens to the resulting pattern?

14-4. Why might you want to feed a large array with non-uniform element currents? What are the trade-offs involved?

Chapter 15

Practical Multielement Driven Arrays



These multiple elements are combined to achieve an omnidirectional pattern.

Contents

Practical Multielement Driven Arrays 15-2

The Bobtail Curtain Array 15-2

The X-Array Antenna 15-4

The Four-Square Array 15-5

A Real-World Steerable Undirectional Array 15-7

Long-Wire Antennas 15-8

But Wait There's More! 15-10

The Beverage Long-Wire Receiving Antenna 15-11

Chapter Summary 15-12

Review Questions 15-12

Practical Multielement Driven Arrays

In earlier chapters I have discussed a number of arrangements of horizontal and vertical elements used as single and multi-element antenna arrays. Almost any combination of them, in almost any quantity, can be (and probably has been) used to construct antennas that meet specific requirements. In this chapter I will discuss how principles described in preceding chapters have been effectively used to construct some classic antenna arrays.

The Bobtail Curtain Array



Fig 15-1 — Configuration of a Bobtail Curtain three element monopole broadside antenna system.

One of the simplest, and perhaps oldest, three element vertical monopole arrays is called a *Bobtail Curtain*. It consists of three vertical monopoles fed in-phase to form a broadside array with a tapered current distribution. The construction shown in **Fig 15-1** is deceptively simple, but it has some unusual features in spite of its simplicity.

The three monopoles are fed via a single connection to the bottom of the center element. Note that the outer two verticals are not connected to ground. This makes the bottoms the high voltage end of each outer monopole. The center vertical also exhibits a high impedance at the bottom, by virtue of its being connected to the other two through the lengths specified. It thus requires a transformation to match to low-impedance transmission line. In its earliest days, this transformation was generally accomplished with a link-coupled tuned circuit. The link would form the low-impedance driving point, while the resonant circuit would be resonated at the desired frequency. The antenna was connected to one end of the parallel-tuned resonant circuit, and there was a connection to a ground system on the other end. These days, a weatherproof remote automatic antenna-tuning unit is commonly used for matching.

The high-impedance feed results in the maximum current being at the top of each monopole. This raises the area of maximum radiation away from ground and makes the efficiency somewhat less dependent on the conditions of the ground beneath the array. The effect of ground conditions beyond the near field is still the limiting factor for far-field radiation in the far field, as with any vertical HF array. Note that having the high-voltage end near the ground suggests that proper protection should be employed to avoid accidental contact by humans or animals during operation.

The low impedance point at the top of each outer vertical is connected in parallel to the center one through a λ/2 section of wire, so the impedance is low again at the connection point. Because all the current flows up the center element and then splits to head towards the outer elements, each outer element has half the current of the center. Thus we have the kind of taper described in the last chapter. Note that with three elements, the taper will be 1 – 2 – 1, which can be considered either a linear or a binomial taper, if you worry about naming such things!

The horizontal wires would also radiate, but because they are carrying identical currents in opposite directions, their radiation broadside to the elements cancels, while the nulls from the ends largely takes care of the rest.

Because there is a low impedance at the top, it is also possible to feed the junction at the top of the center element directly with a low-impedance transmission line. This is not usually done, however, because it is often difficult to install a transmission line without coupling it to the other portions of the antenna. The modeled impedance at that point is a close match to the usual 50 Ω coaxial cable, although there really isn't quite a ground at that point, so an isolating choke or balun would have to be employed to keep common-mode current off the coax shield.

How Does it Work?

The Bobtail Curtain is quite directive, as shown in **Fig 15-2**, with significant gain compared to a single monopole. The sharpness of its azimuth pattern makes it well suited for point-to-point links. Or you could use a number of Bobtail Curtains for wider coverage — especially if multiple supports are available.

The large horizontal section might make a reader wonder about the relative benefits of this antenna compared to a full-wave center-fed horizontal antenna hanging from the same supports. The horizontal antenna has almost the same azimuth pattern, as shown in **Fig 15-3**. However the choice between the two is clearly highlighted in **Fig 15-4**, which compares their elevation patterns over typical ground. Note that the horizontal antenna actually has a higher peak gain; however, it is generally directed at higher elevation angles. Note that the gain of the vertical curtain is significantly higher at lower elevation angles. The choices are thus:

- If you are designing an HF system for medium-range communication (typically 1000 miles or less) by means of *Near Vertical Incidence Skywave* (NVIS) propagation, the horizontal system would be more effective.
- On the other hand, if you want longer-haul communication at low takeoff angles, the vertical array will both provide stronger signals near the horizon and reduced interference and noise from closer-in stations and noise sources, often a limiting factor in reception.

For many installations seeking long-haul propagation, the issue often becomes height of available, or feasible, supports. At the lower frequencies in the HF or MF region, even λ/4 heights can be challenging, and a horizontal antenna capable of producing low-angle radiation requires heights well above λ/2. For example, at 1.8 MHz a λ/2 high antenna would be 273 feet high!



Fig 15-2 — Azimuth pattern of a Bobtail Curtain array at 10° elevation angle over typical flat ground.



Fig 15-3 — Azimuth pattern of a Bobtail Curtain (solid line), compared to a full-wave center-fed horizontal antenna (dashed line) over typical flat ground at 30° elevation.



Fig 15-4 — Elevation pattern of a Bobtail Curtain (solid line), compared to a full-wave center-fed horizontal antenna (dashed line).

The X-Array Antenna

Another simple array to construct is the combination collinear-broadside system known as the *X-Array*. This antenna, shown in **Fig 15-5** is made from four folded dipoles fed in-phase. The dimensions between the elements are not terribly critical; however, those shown result in a good balance between gain and a clean pattern. They also result in a combined drive-point impedance of close to 50 Ω, a good match to coax, if each element feed line is an electrical full-wave and the parallel combination is fed through a balun to transition from balanced-to-unbalanced feed lines.



Fig 15-5 — Configuration of an X-Array of four folded-dipole elements.

Building an X-Array Antenna

The only critical part of construction of this antenna is to make sure that all elements are tied together in-phase. This means the all right-hand-side element connections need to be on one side of the combined feed, while all left-side connections be on the other. Note that because the two wires in each folded dipole are at the same phase, it doesn't matter if the connections are to the top or bottom wire of the folded dipole elements.

By having the individual element feed lines (typically 300 Ω line is used) be exactly one electrical wavelength long, the folded-dipole feed impedance is repeated at the junction point. The effects of mutual coupling reduce the folded-dipole impedances so that the combination is very near 50 Ω.

You can make construction and materials provisioning easier if both antenna elements and dipole feed lines are all made from 300 Ω TV type twinlead or amateur type window line. You should limit the use of TV twinlead to low-power transmitters.

X-Array Performance

Azimuth and elevation patterns for an X-Array with elements at λ/2 and a full wavelength above ground are shown in **Figs 15-6** and **15-7** respectively. Note that the benefit of the ground reflection adds significantly to overall gain, as compared to vertical arrays, such as the Bobtail Curtain.

While the Bobtail Curtain is often employed at the lower end of the HF spectrum, the X-Array is an antenna best suited for the upper portion of the HF region into VHF because it requires significant vertical spacing. The antenna modeled for the following plots had the lower element at a height of λ/2 and the upper element another λ/2 high. At a 10 MHz modeling frequency, this represents a height of about 100 feet. While that height can be accommodated, the expense of two towers of that height argues for antennas that can be supported by a single support, such as I will cover in later chapters.

At 30 MHz, the top of the HF range, a height of 30 feet will do the trick and is not nearly as daunting. Existing trees or buildings can often be used to good advantage. As with the Bobtail Curtain, the X-Array has a narrow azimuthal pattern, best used for point-to point or in combination with other antennas. Many amateur stations using long, single-wire antennas have deep nulls in their coverage at some azimuth angles, particularly at the higher frequencies. If the nulls are in an unfortunate direction, an antenna such as the X-Array can be an effective and simple way to fill in the gap.



Fig 15-6 — Azimuth pattern of an X-Array at 17° elevation angle.



Fig 15-7 — Elevation pattern of an X-Array.

The Four-Square Array

An antenna that is very popular with amateur operators looking for long-haul performance on the 160 through 40 meter amateur bands is called the *Four-Square* array. This is a unidirectional array consisting of four, usually λ/4 long, monopoles at the corners of a square with sides λ/4 long. With the phasing of the sources shown in **Fig 15-8**, the antenna will fire on the diagonal between the elements with 0° and –180° phase delay.

The resulting azimuth and elevation patterns over typical earth are shown in **Figs 15-9** and **15-10**. Note that the half-power beamwidth of the azimuth pattern is 100°, so that four directions can cover all azimuths with some overlap. The real benefit of the Four-Square comes from its symmetry. Because the element spacings are the same, the feed system can be moved instead of the antenna elements and thus, via a relay network, all four directions can be achieved with a single antenna. The gain over an isotropic radiator is about 5.2 dBi over typical ground, although the gain would increase to 10.8 dBi if the ground were perfect. As with all vertical systems, ground conductivity some wavelengths from the system plays a large part in determining effectiveness at low takeoff angles.

It is interesting to compare the Four Square to the two element cardioid discussed in the last chapter. That is sort of half a Four-Square, with a half-power beamwidth of 170° and a peak gain 2.6 dB less than the Four-Square. It can cover almost all azimuths from one direction or the other, and adds the prospect of a less-than-optimum broadside array to fill in the gap. The switching is much easier to implement, however, without implementing the broadside direction.

Feeding the Four-Square

As noted in the last chapter, the effects of mutual coupling on elements fed at different phase angles generally results in different feed impedances at each element. In order to force equal currents into each element at the desired phase, a combination of selected transmission-line lengths and an LC impedance-matching network can be employed. **Fig 15-11** shows the arrangement used to obtain the desired results from a Four-Square.

The exact values for the inductive and capacitive reactances shown in Fig 15-11 will depend on the ground conditions, the number of radials used at the base of each monopole and the Z_0 of the cable used for the phasing lines. Note that the electrical, not physical length of the cables is specified. These should be trimmed for the center of the desired band using an antenna analyzer or impedance bridge for optimum performance. The values for various arrangements are given in **Table 15-1**. These should be considered starting points, since the exact ground conditions will have a major impact on the impedance.



Fig 15-8 — Configuration of a Four-Square array of four λ/4 monopole elements, spaced λ/4 on each side.



Fig 15-9 — Azimuth pattern of a Four-Square array at 25° elevation angle.



Fig 15-10 — Elevation pattern of a Four-Square array.


Max.
EL. 4
λ/4 , Z_0
L Network
X_{sh}
X_{ser}
EL. 2
λ/4 , Z_0
λ/4 , Z_0
EL. 3
λ/2 , Any Z
λ/4 , Z_0
Feed
ANT0324
EL. 1

Fig 15-11 — Optimum feed arrangement for Four-Square array.

Table 15-1

L Network Values for the Four-Square Array Feed Arrangement of Fig 15-11.

Radials per Element	*Cable Z_0*	*X_{SER} (Ω)*	*X_{SH} (Ω)*
4	50	17.1	–13.7
4	75	38.5	–30.9
8	50	20.2	–15.6
8	75	45.4	–35.2
16	50	23.6	–17.6
16	75	53.1	–39.6

A Real-World Steerable Unidirectional Array



Fig 15-13 — Configuration of an eight element broadside array that provides four simultaneous beams.

The eight element broadside array discussed briefly in the last chapter was part of a larger system I worked on early in my engineering career. By pairing each element with a rearward element phased to generate a cardioid response the system becomes a 16 element unidirectional broadside array with the azimuth pattern shown in **Fig 15-12.**

While not likely a system for the home constructer, this antenna was something that was successfully deployed in the field and can serve as an interesting example of what can be accomplished. This antenna was part of a world-wide system with separate receiving and transmitting systems located continents apart. There were four transmitting stations and five receiving locations. Each receiving station had to monitor all four transmitters, each at different azimuths.

The four transmitters were in the same quadrant, so rather than erect four separate antennas at each receiver location, a single array was used to synthesize four pencil-shaped beams — one towards each transmitter. This was accomplished by making the array unidirectional (using a reflecting screen to be discussed in a later chapter) to eliminate the unneeded response from the rear. The cardioid arrangement used here will provide the same result for a single frequency.



Fig 15-12 — Azimuth pattern of a 16 element unidirectional broadside array showing three separate beams at 10° increments.

Each receiving element was fed through an equal-length transmission line to a preamplifier. Each preamplifier had a splitter with four outputs. Each output had a delay line corresponding to the shift for a single beam, as discussed for a two element array in the last chapter. The eight signals for each of the beams were combined in an eight-port summing network. Thus each beam was available for the appropriate receivers. The configuration is shown in **Fig 15-13**. **Fig 15-14** shows the azimuth response for three such beams, each 10° apart.

I was not only involved in the development of procedures to make sure that all phases were correct, but had an opportunity to participate in an evaluation of the results at one location to validate the concept. A helicopter was fitted with a suspended vertical dipole with a battery-powered transmitter at its center. An observer with a transit was stationed at the



Fig 15-14 — Azimuth pattern of the steered array in Fig 15-12, showing three separate beams at 10° increments.

array center to call off azimuth positions while the helicopter's navigator used a hyperbolic navigation system to verify the radial distance. The signal from each receiver was measured and the antenna worked as specified (much to my relief).

Long-Wire Antennas

One of the simplest antennas to build is called a *long wire*. As its name implies, it is just a long, in terms of wavelengths, piece of wire. It can be resonant or not, although is often easier to feed and predict the performance if it is resonant. While some call any piece of wire a long wire, most would say it would have to be at least 2 λ long to qualify for the term.

The Basic Long Wire

A piece of wire 2 λ long is a kind of collinear array consisting of four λ/2 elements one after the other. Unlike the previously discussed multielement collinear antennas in which elements were fed in-phase, the end-to-end connection results in alternate sections being of opposite phase. Thus unlike the in-phase collinear with its main lobe broadside to the wire, an end-fed long wire with an even number of elements will have a broadside null and a pattern that has offset major lobes, as shown in **Fig 15-15**.

This wire can be fed at one end using high-impedance transmission line, or the first λ/2 element can be fed in the center with lower-impedance line. Its resonant impedance at that point is about 120 Ω, so a good match to 50-Ω coax can be obtained through a λ/4 section of 75-Ω coax.



Fig 15-15 — Azimuth pattern of the 2 λ end-fed long wire.



Fig 15-16 — Pair of 2 λ end-fed long wires combined into a V-beam.

If the long wire is end fed (often connected directly to a tuning unit at the transmitter), it can provide good performance from a frequency as low as λ/4 (if fed against a good ground) and as high as desired. As the frequency is raised, the pattern becomes more complex and tends to focus closer to the line along the wire axis. For any given direction, there is likely a frequency that will provide good coverage.

It's hard to imagine an antenna with this amount of flexibility that is as easy to construct!

The V-Beam Array

If more directivity is desired than that afforded by a single long wire, you can configure two of them in the configuration shown in **Fig 15-16**. This is known as a *V-beam*. You take advantage of the fact that for a 2-λ wire, the center of the main lobe is 63° away from the broadside direction, or 27° from the wire axis. If you combine the effects of two such wires fed in-phase with a separation of 54°, the main lobes will reinforce along the direction of the bisector of the angles, as shown in **Fig 15-17**.

The V-beam does provide usable bidirectional gain and directivity, combined with a nice balanced feed suitable for high-impedance low-loss balanced transmission lines. It can be operated on other frequencies, although the angle between the wires will only be optimum at its design point. For longer-length wires, the main lobes move closer to the wire axis and thus a smaller angle is beneficial.

The Rhombic

If you place two V-beams end-to-end, you would end up with the *rhombic* shown in **Fig 15-18**. This configuration further reinforces the on-axis directivity and further reduces the broad sidelobes of the V-beam, as shown in the azimuth pattern in **Fig 15-19**. The rhombic, however, really moves into prime time and



Fig 15-17 — Azimuth pattern of the 2 λ per leg V-beam.

changes character with the simple addition of a terminating resistor across the gap at the far end, as shown in **Fig 15-20**.

The *terminated rhombic* is a bit different in operation than other antennas you've looked at. You might consider it as a special sort of transmission line. As previously mentioned, an open-wire transmission line doesn't radiate if the two wires are very close together. A terminated rhombic, however, you have essentially a terminated transmission line that has its wires spaced very far apart. The currents moving down the line to result in radiation, and the angles and spacings add in the desired direction along the bisector of the angle between the fed ends.

Note that, unlike other antennas you have studied, there is no reflection from the far end of the terminated rhombic. The result is that there is no radiation back towards the source end. You thus have a unidirectional antenna with significant gain and directivity, as shown in **Fig 15-21**. Terminated rhombics have long been used for fixed (for HF they are hard to rotate!) point-to-point transoceanic links and have provided good stable results. The terminating resistor absorbs about half the incident power and thus must be a substantial resistor for high-power transmitting applications.



Fig 15-18 — A pair of two 2 λ V-beams combined into a rhombic.



Fig 15-19 — Azimuth pattern of the 2 λ per leg rhombic.



Fig 15-20 — A pair of 2 λ V-beams combined into a terminated rhombic.



Fig 15-21 — Azimuth pattern of the 2 λ per leg terminated rhombic.

Because of the lack of reflections from the termination point, the rhombic acts like a reasonably frequency independent load to the source and thus has a wide impedance bandwidth. The 600 Ω SWR over a 2:1 frequency range is shown in **Fig 15-22**. While the wire angles will not be optimum for multiple frequencies, the antenna can still be used over this frequency range with excellent results. At the high end, the pattern tends to break up; however, compromise angles can be found that can control this over a wide range. Just using the 10 MHz design angle used for the V beam, I achieved the results in **Fig 15-23** for 8 and 14 MHz operation.



Fig 15-22 — 600-Ω SWR of 2 λ per leg rhombic over 2:1 frequency range.



Fig 15-23 — 10 MHz 2 λ per leg rhombic's azimuth pattern at 8 MHz (dashed line) and 14 MHz (solid line).

The Beverage Long-Wire Receiving Antenna

An antenna that looks like a long wire and is made from a long piece of wire, but is quite different in operation from those we've discussed, is called a *Beverage* antenna. This is named for Harold Beverage, who developed and patented this antenna just after WW I. The Beverage antenna is designed to be a highly directive receiving antenna that responds to vertically polarized low-angle waves approaching along the ground. It accomplishes this by itself being installed quite close to the ground, cancelling most its response to sky waves as well as horizontally polarized signals. Vertically polarized waves coming along the lossy ground tend to slow along the bottom near the ground, resulting in a tilt to the wavefront. This tilt couples a signal along the length of the wire that adds in-phase with the signal as it continues to propagate along the wire towards the matching transformer.

Waves coming from the other direction accumulate as well, but are dissipated in a terminating resistor, just like they do in the rhombic. The termination is usually between 400 and 600 Ω, adjusted for best front- to-back ratio. The configuration is shown in **Fig 15-24**.

The consequence of this is that desired signal is received without the noise from nearby lightning or other noise sources that tend to arrive from high elevation angles. Other interfering noise or signals that arrive from unwanted directions are also attenuated by the directional characteristics of the Beverage.

The absolute gain of a Beverage system is quite low; however, this receiving antenna is typically used for low frequencies (MF and just into HF) where atmospheric noise is the key limitation to signal-to-noise ratio and thus the weak desired signal is at much higher SNR than with other antennas because the noise is reduced more than the signal.



Fig 15-24 — Configuration of a Beverage low-noise receiving antenna.

Chapter Summary

This chapter has provided some easy — and some not-so-easy — examples of practical arrays that can be constructed to meet particular operating objectives. An interesting aspect of this is that most can be constructed from available materials at relatively low cost, compared to commercially available antennas, yet they all offer significant performance advantages over simpler systems.

Review Questions

15-1. Why might it be desirable to have the bottom of the Bobtail Curtain elements 8 feet above ground?

15-2. How many X-Array antennas would be needed to have coverage of all 360° at the –3 dB level?

15-3. How might you make a unidirectional version of an X-Array?

15-4. Why are extra components required to properly drive the elements of a Four-Square array at the proper phase and amplitude?

Chapter 16

Surface Reflector Antennas



This reflector antenna is used for point-to-point communication at 10 GHz.

Contents

Surface Reflector Antennas 16-2
The Plane Reflector Antenna 16-2
The Corner Reflector Antenna 16-4
The Parabolic Reflector Antenna 16-5
The Parabolic Dish Reflector - In Three Dimensions 16-6
Feeding Antennas for Space Communication 16-7
Chapter Summary 16-8
Review Questions 16-8

Surface Reflector Antennas

As noted in previous chapters, it is frequently desirable to restrict the coverage of antennas to a single direction. I have previously introduced the λ/4 spaced, 90° phased array that produces a cardioid unidirectional pattern. There are other arrangements that have a similar effect.

Just as radio waves reflect from a large conductive surface, such as seawater, they will also reflect from a surface such as a metal plane. If the plane is large enough to reflect most of the radiation from the antenna, it will redirect the radiation away from the plane. If the spacing is such that the radiation ends up largely in-phase with the radiation from the antenna itself, this will reinforce the radiation from the antenna, resulting in a stronger signal in the desired direction and no signal to the rear.

The Plane Reflector Antenna

The simplest case to imagine is an infinite, flat and perfectly conducting plane. Fortunately it neither has to be infinite nor perfect to function quite nicely, thank you, but let's start here. **Fig 16-1** shows the configuration of a dipole placed in front of such a plane. You can imagine that this is a horizontal dipole above a perfectly conducting ground and it acts just the same way. Because the dipole is parallel to the surface, the phase of the reflected wave is out-of-phase with the incident wave, resulting in a phase shift of 180° at the boundary.

What Spacing Gives Us the Correct Phase?

You would generally like the signal coming directly from the antenna to reflect in-phase with the reflection so they add up going away from the reflector. If you space the dipole λ/4 in front of the reflector, the wave going rearward will have a propagation delay corresponding to a 90° phase shift as it travels to the reflector. The reflector will impart a 180° delay to the signal, as explained above, and there will be another 90° delay for the signal to return to the dipole, so that the total delay is 360°. This means that signals going directly rearward will add in-phase with signals leaving the dipole traveling towards the front.

Note that waves leaving the dipole at any other angles take a longer path and don't add fully in-phase. Nonetheless, the combined effect is beneficial. This is shown in **Fig 16-2**.



Fig 16-1 — Dipole in front of a plane reflector.

How Do You Make a Giant Plane at HF?

While a large solid metal plane is sometimes used at the higher VHF frequencies and above, at HF and for many applications above HF, a plate that extends outward on each side of the dipole by around λ/8 and above and below by λ/4 will have a similar effect. In addition, by replacing the plane with a *skeleton* of wires spaced much closer than a wavelength, the weight, cost and wind resistance can be reduced considerably.

In developing the models for these patterns, I wanted to get a feel for the effect of skeleton-wire spacing. Using my usual 10 MHz (30 meter) frequency, I started with a wire spacing of 1 foot, about 0.01 λ. I then reduced every other wire and continued until I reached a spacing of 4 feet, or about 0.04 λ, before I noted any degradation in forward gain or front-to-



Fig 16-2 — Side view of dipole in front of a plane reflector. The direct radiation from the dipole is shown as a solid line, while reflected waves are shown dashed.



Fig 16-3 — Elevation pattern of the dipole in front of a skeleton plane reflector.

back ratio. This is probably a reasonable guideline for construction of reflector arrays, and is what I used for these models. Extending the width or height of the reflecting screen for the flat plane beyond these guidelines has very little impact on the predicted results.

How Does the Skeleton Play?

Fig 16-3 shows the elevation pattern of the skeleton-plane reflector over typical, real ground, with the center of the antenna at a height of λ/2. **Fig 16-4** shows the azimuth pattern compared to a dipole at the same height. Note that the radiation intensity off the front of the antenna is more than twice (about 3.6 dB) that of a dipole at the same height. Thus the rearward energy has been successfully redirected to refocus in the desired direction.

Had I used an infinite reflecting plane in free space (instead of a skeleton above earth), the forward gain compared to a dipole would have been an impressive 5.5 dB. The infinite plane would also have an infinite front-to-back ratio, compared to a respectable 20 dB for the skeleton. Unfortunately, infinite planes and free space are difficult to find, especially in the same place!



Fig 16-4 — Combined effect of all reflected waves from the plane reflector and the resulting pattern (solid), compared to a dipole in free space (dashed).

The Corner Reflector Antenna

A common alternative structure is the *corner reflector*. This can be created by folding the plane along the center behind the dipole so that the two sides are at an angle, as shown in **Fig 16-5**. The reflected waves tend to be focused somewhat more along the front axis, and with the reflected waves having a shorter distance to travel, they are closer to being in-phase with the front facing waves. The elevation pattern for a corner reflector with a 90° angle is shown in **Fig 16-6**, while the azimuth pattern, again compared to a dipole, is shown in **Fig 16-7**. For about the same size of plane (bent at the center), the corner reflector has a slight advantage over the plane reflector. However, the difference is small enough that mechanical considerations may be more of a consideration than performance when deciding between them.

Since the reflected waves travel different lengths, there is nothing magic about the $\lambda/4$ spacing, so you can use other spacings too. With narrower angles and longer plane sheets, you can achieve additional gain. A 45° corner with side lengths (L in Fig 16-3) of around 2 λ should provide about 3 dB more forward gain, for example.



Fig 16-5 — Side view of dipole in front of a corner reflector. The direct radiation from the dipole is shown in solid, while the reflected waves are shown dashed.



Fig 16-6 — Elevation pattern of the dipole in front of a skeleton corner reflector.



Fig 16-7 — Combined effect of all reflected waves from the corner reflector and the resulting pattern (solid), compared to a dipole in free space (dashed).

The Parabolic Reflector Antenna

Another structure you will sometimes encounter is the *parabolic reflector*. This is a special shape that has the property that all waves striking the reflector emanating from the *focus*, where you mount a dipole, leave the reflector in-phase and head out in parallel with the wave leaving the dipole in the desired forward direction. This is shown in **Fig 16-8**.

The power of this structure will be more evident later in this chapter when I discuss the three-dimensional paraboloid; however, in two dimensions, it is an alternate to the corner reflector. The elevation pattern for a parabolic reflector about the same size as a corner reflector is shown in **Fig 16-9**, while the azimuth pattern, compared to a dipole by itself, is shown in **Fig 16-10**.



Fig 16-8 — Side view of dipole in front of a parabolic reflector. The direct radiation from the dipole is shown in solid, while the reflected waves are shown dashed.

Some Comments about Surface Reflectors

A reasonable question to ask about any of the above antennas is why bother? After all, a cardioid array can provide similar results with fewer wires. That is a good question and there are a number of answers to this, the relevance of which will depend on your design goals and constraints.

- The surface reflector is straightforward, predictable and easy to make work. Using this kind of structure avoids the problem of mutual impedance between multiple elements and possible complications obtaining equal currents in multiple elements.
- The same structure can be used at higher frequencies by just moving the dipole closer to the screen.
- It is easily adaptable to being driven in more complex structures, such as broadside arrays.
- The reflector, using the same screen (if a plane array), can operate in two directions simultaneously by having dipoles or driven arrays on each side.



Fig 16-9 — Elevation pattern of the dipole in front of a skeleton parabolic reflector.



Fig 16-10 — Azimuth pattern of the parabolic reflector and the resulting pattern (solid), compared to a dipole in free space (dashed).

The Parabolic Dish Reflector — In Three Dimensions

So far, I have been talking about antenna structures in which the driving element is comparable in size to the reflector. As frequencies move into the upper UHF and especially microwave regions (above 1000 MHz), the wavelengths get small and antennas that would be out of the question at HF become feasible. Nowhere is this more evident than in the case of the *parabolic dish reflector.*

This is the same structure used as an optical reflector in most flashlights and vehicle headlights. Take a moment and observe a flashlight and note the difference in intensity in the *main lobe* of the flashlight compared to looking at the bulb from the side. This kind of dish shape can be just as effective for radio signals.

Because my usual 10 MHz dipole is relatively large, and because it is inherently omnidirectional around its axis, I've restricted the discussion so far to the two dimensional structure explored in the last section. While as effective as other two dimensional reflectors, the parabola really pays off when its driving antenna becomes small enough compared to the reflector size that it can be considered a point rather than a line. If that's the case, the parabola can be shaped like a dish and all radiation from the focus towards the dish will be sent from the reflector in-phase. This is perhaps more apparent in the case of a receiving antenna, in which virtually all the radiation received in the aperture of the disk is focused on the single focus point.

With a very small driving antenna, it becomes feasible to have a sub-reflector in front of the driving antenna to eliminate the direct radiation from the dipole or other driver. By eliminating the direct rays from the front of the driver, all the radiation can be via the parabola. Note that since you no longer have a direct ray to be in-phase with, there is no longer a need for a particular distance from the driver to the dish. You can use any dish size, with any focal distance, at any frequency with the appropriate driving antenna and sub-reflector located at the optical focus. You decide how much gain you need, or alternately how much receive aperture is needed for the desired signal strength, and then you select the appropriate-sized dish.

The down side of the sub-reflector is that it effectively provides a shadow to the signal to and from the main reflector. With higher frequencies, smaller drivers and larger dishes, the loss is generally a small fraction of the dish area. Typical gains for parabolic dishes are shown in **Table 16-1** for various frequencies and commonly available dish sizes.



Fig 16-11 — Slice through a three-dimensional parabolic reflector antenna showing sub-reflector.

Complex Feeds are Common at Microwave Frequencies

While these discussions on reflector arrays have focused (no pun intended) on dipole feeds, at higher frequencies where we find most parabolic dish antennas, other types of drivers are more common. In the microwave region, perhaps the most common type is the *horn* antenna. This antenna, which will be covered

Table 16-1

Expected Gain of Parabolic Dish Antennas Compared to Isotropic Radiator (dBi).

	Dish Diameter (Feet)						
Frequency (MHz)	*2*	*4*	*6*	*10*	*15*	*20*	*30*
420	6.0	12.0	15.5	20.0	23.5	26.0	29.5
1215	15.0	21.0	24.5	29.0	32.5	35.0	38.0
2300	20.5	26.5	30.0	34.5	38.0	40.5	44.0
5600	28.5	34.5	38.0	42.5	46.0	48.5	52.0
10,000	33.5	39.5	43.0	47.5	51.0	53.5	57.0

later, is unidirectional by nature and can be designed to just radiate into the area of the dish without the need for a sub-reflector.

Dishes Get Quite Large

I have encountered rotating dish antennas with diameters larger than 100 feet. I have also seen sections of parabolic dish antennas as wide as 540 feet. These were used for a very-long-range space radar system, in which the drivers rotated to use different segments to cover different azimuths. There were two drivers at different elevation angles to simultaneously track targets crossing two elevation angles. This allowed computation of ballistic trajectories.

This system was reputed to be powerful enough (a combination of a massive transmitter and very high gain antenna) to detect a basketball-sized object thousands of miles away or to *shoot down* birds that got too close. The radar was located north of the artic circle where there weren't many birds, but there were lots of warning signs posted for the occasional human that got near.

Perhaps the largest parabolic dish around is the one in use at the radio telescope of the Arecibo National Observatory in a remote corner of Puerto Rico. It has a fixed dish 305 meters (1000 feet) across that's built into a sinkhole in the rugged terrain. This is shown in **Fig 16-12**. This antenna is aimed by knowing what part of space this location is pointing toward as the earth turns and the cosmos moves around it. The large surface of this dish covers an area of more than 20 acres. It offers some 18 acres, about 26 football fields, of available receiving aperture! The dish reflects and concentrates weak celestial signals on the receiving antennas suspended 450 feet above its surface.



Fig 16-12 Parabolic dish of the Arecibo radio telescope Arecibo National Laboratory in Puerto Rico. The dish diameter is 305 meters or 1000 feet.

This leads to one of the limiting parameters of parabolic dish arrays. Surface irregularities, either from manufacturing tolerances, or in this case, possible "frost heaves," result in less than perfect phase relationships among the reflected waves. Perhaps this is why Arecibo was built in Puerto Rico rather than frigid New England!

Feeding Antennas for Space Communication

Feeding Antennas for Space Communication

Space communication is generally limited by the receive signal-to-noise ratio, since transmitter power in satellites, or distant terrestrial bodies, is usually in short supply. With an antenna pointed toward space, unless the sun crosses the path, the antenna is seeing its signal sources against a cold distant sky. Unfortunately, with the feed systems we have discussed, any sidelobes or spillover from the feed that misses the reflector heads towards earth. This is not a significant problem for the transmitted, or uplink, system — just turn up the transmit power a notch.

On the receive side, it is a whole different story. Random noise signals received from the warm earth are



Fig 16-13 — Illustration of the Cassegrain feed system — adapted from optical telescope technology.

much more powerful than those from space and can be the limiting factor in signal-to-noise ratio. If the pattern from the feed is tightened to stay entirely within the reflector, it will undoubtedly not fill it completely, thus giving up some of the possible forward gain.

One alternative is to feed the antenna from the rear using a system adapted from optical telescopes called a *Cassegrain* feed. This is illustrated in **Fig 16-13**. Note that with this feed system that if any radiation misses the sub-reflector at the main dish focus point, it heads for space rather than towards the warm earth.

The Cassegrain feed is a particularly good choice for large reflectors, since a long transmission line to the feed horn is eliminated. A low-noise receiver amplifier at the feed horn can be any size without blocking the pattern and is also in a location where it is easy to service, rather than being perhaps 100 feet over the top of the dish.

Chapter Summary

This chapter has discussed the use of surface-type reflectors used to provide gain and directivity to antenna systems. This is one alternative to the multielement arrays of driven elements I discussed in previous chapters. I will discuss other possibilities later in this book. Of the types discussed, the parabolic dish is almost universally encountered at microwave frequencies, whether used for TV satellite receive dishes, search radar antennas or point-to-point communications links.

Review Questions

16-1. Discuss the relative benefits of unidirectional phased arrays compared to surface-reflector antennas. Under what conditions might each have the edge?

16-2. Can you think of two "structures of opportunity" that could be pressed into service as plane reflectors?

16-3. Examine the two-element horizontal broadside array of Fig 7-1 and its gain shown in Fig 7-5. If you were to put a properly sized plane reflector $\lambda/4$ behind it, what would you expect the forward gain to be?

16-4. Calculate the receive aperture in wavelengths of a 15 foot parabolic dish at 2300 MHz and compare it to that of a 6 foot dish at 5600 MHz. Compare the gains of each in Table 16-1. What do you conclude?

Chapter 17

Surface Reflector Antennas You Can Build



This reflector antenna for 70 cm satellite work can be built from parts available at any hardware store.

Contents

Surface Antennas You Can Build....17-2
A Simple UHF Plane Reflector Array....17-2
High Performance VHF or UHF Array....17-4
Parabolic Dish Reflector Systems....17-6
Chapter Summary....17-7
Review Questions....17-7

Surface Antennas You Can Build

There are a number of easy to build surface reflector arrays that can be constructed in the home shop and provide excellent performance at low cost. This chapter will provide some representative examples; however, availability of materials can make some other configurations equally attractive.

A Simple UHF Plane Reflector Array

This antenna may become a classic! It provides exactly the performance needed for successful low earth orbit (LEO) satellite operation, costs relatively little and is easy to duplicate. The antenna was first presented in *QST* Magazine, but is worth repeating here.[1]

The antenna in **Fig 17-1**, consists of two broadside dipole pairs, one horizontal and one vertical, in front of a 2 foot square reflector (a 2½ foot square would work a bit better, but would be a bit more cumbersome). For terrestrial use, either polarization may be used. By feeding both polarizations with a 90° phase delay, circular polarization can be provided, which provides better communication to either a tumbling satellite using linear polarization or to a satellite that uses circular polarization in the same sense.

Fig 17-2 shows the configuration layout, while **Fig 17-3** shows the hardware store perforated aluminum sheet reflector with the dipoles in place. The reflector is made rigid by pieces of 1×1×⅛ inch aluminum angle around the edges and 1×⅛ inch bar stock across the dipole mounting locations. Each dipole is made from two 5½ inch long pieces of ¾ inch OD aluminum tubing insulated at the center with ½ inch black PVC lawn sprinkler couplings. The dipoles are insulated from, and mounted on, aluminum angle brackets that provide a separation of 5⁵⁄₁₆ inches from the reflector and 19½ inches from its opposite number.



Fig 17-1 — View of a 70 cm panel reflector antenna. Its compact size is evident.



Fig 17-2 — Layout of panel reflector.

The feed arrangement for right-hand circular polarization is shown in **Fig 17-4**. The cables to each pair of dipoles are each λ/2 (electrical length) longer on one side of a pair than another, so the connections to the dipoles are reversed to make the signals of each pair be the same phase. In addition, the cables to the horizontal pair are 90° longer, resulting in generation of right-hand circular polarization.

The "four-way power splitter" in the center consists of a pair of T adapters to join the two 50 Ω loads from each of the pair of dipoles. The resultant impedance of the two in parallel is 25 Ω. Each of the 25 Ω loads is transformed through a λ/4 length of 50 Ω coax to 100 Ω and then each is combined in parallel in another coaxial T to form a 50 Ω load for the transmission line to the radio equipment. The author used 50 Ω Type N connectors and Ts for all connections. While these are somewhat more expensive than the UHF type, they are recommended for use at VHF and above because they offer a constant impedance. In addition they are waterproof if properly assembled.

Additional details for construction can be found in the *QST* article or on the ARRL Web page.[2]



Fig 17-3 — View of panel reflector with dipoles in place.



Fig 17-4 — Detail of feed cables and four-way power divider.

High Performance VHF or UHF Array

Many serious VHF and UHF operators interested in long-haul communications have selected arrays of Yagi arrays (Yagis are described in a subsequent chapter) for their stations. Still, for those without a suitable method of confirming the Yagi's correct tuning and spacing, the plane reflector can provide a predictable alternative that is easy to duplicate in the home workshop.

The antenna shown in **Fig 17-5** brings together material from a number of chapters resulting in a combination broadside-collinear array in front of a reflecting backscreen. The dimensions given are for a design frequency of 144.5 MHz, but nothing is critical about the dimensions, nor the design frequency. This makes duplication straightforward. The *EZNEC* predicted gain of more than 18 dBi (see **Fig 17-6**) is quite impressive and hard to beat with homemade Yagis.

Element Construction

The antenna is composed of three pairs of center-fed full waves (or perhaps better yet, collinear end-fed half waves) stacked vertically to give good gain along the horizon. Each full wave



Fig 17-5 — Configuration of combination six element collinear-broadside array in front of screen reflector.

element should be about 71 inches tip to tip, with a gap between the inside ends for transmission-line connection. The upper and lower collinear elements are connected to the center pair through readily available 450 Ω ladder line from the center pair to those above and below.

Elements are made from ⅜ inch OD aluminum tubing with each λ/2 piece about 35 inches long (a bit shorter than the usual λ/2 because of the increased diameter) and spaced 20 inches from the backscreen. The elements should be supported at their center, a zero-voltage point, but it is best to use nonconducting material, such as PVC tubing, to be safe. Connections to the rods at their common ends can be made by flattening the end of each tube and drilling each for bolts, lockwashers and nuts to secure ring terminals soldered to the end of the transmission line sections.

The diameter and spacing of the driven elements results in an appropriate impedance that divides the power almost equally in thirds between the elements when the array is driven from the center pair. This results in maximum forward gain. It is important that the lines between the elements be close to an electrical λ/2 and twisted one turn, as shown in Fig 17-5, or alternately 1 λ long and not twisted, to obtain the correct phase in all three elements.

Feed Arrangement

The resultant impedance results in equal power in each pair and a good match for low-loss 300 Ω feed line going back to the station. As shown in **Fig 17-7**, the relatively flat curve of SWR vs frequency confirms that this antenna is not fussy about precise dimensions.

If coax cable is desired instead of 300 Ω line, a simple λ/2, 4:1 loop balun can be used to make the transition to readily available 75 Ω cable TV (CATV) type coax for the run to the station. This coax is available in different thicknesses, with the larger sizes offering very low loss compared to most types of coax used by amateurs. Cable is often available from CATV installers at no cost, as they often have end pieces on their reels that they can't use. The resulting 1.5:1 SWR at the radio is not generally a problem for the equipment. If a perfect match is desired, a 61 Ω, λ/4 matching section can be fabricated from copper pipe and tubing.

Backscreen

The backscreen is composed of 1.5 λ long wires that are parallel to the elements. These wires extend λ/4 above and below the driven elements. The wire lengths are not critical and any convenient construction techniques can be used. Aluminum ground wire or bare (or insulated) house wire are suitable material. Each backscreen wire is spaced 0.05 λ, about 4 inches for 2 meters, from the next. Alternately, agricultural mesh (chicken wire) can be used if its wire spacing is similar or smaller and its crossings are welded or soldered. Chicken wire should be suspended on an appropriate wood or aluminum support frame that can have attachments for the element supports.

Other Bands

The antenna can easily be scaled to operate on other bands. A second band's driven elements can be mounted on the rear of the backscreen, if the backscreen wire spacing is close enough for the higher band. If chicken wire or other two-dimensional grid wire is used, you could have a vertically polarized antenna on one side and a horizontal polarized one on the other of the reflector.



Fig 17-6 — Azimuth pattern of array in Fig 17-5 over typical ground. Note high forward gain.



Fig 17-7 — 300-Ω SWR plot of array in Fig 17-5. Note wide bandwidth for low SWR.

Parabolic Dish Reflector Systems

While it is difficult, though by no means impossible, for the home constructor to build a parabolic dish — particularly from wire mesh material — it may be far easier to obtain a surplus dish from military, commercial or personal receive-only TV use that you can adapt to your needs. Such a dish, a surplus C band (2 to 4 GHz) receive-only TV antenna, is shown in **Fig 17-8**. Most dishes can operate efficiently at any frequency where they are at least a few wavelengths across, with larger sizes providing more gain, generally proportional to the area intercepted. The upper frequency limit of dishes is the frequency where surface irregularities or dimensional tolerances become a measurable fraction of a wavelength.

Finding the Focus

The first question upon obtaining a dish is to determine the key dimensional parameters, particularly the focus distance. Refer to **Fig 17-9**. The parameters shown can be easily measured and the following formula can determine the spacing from the center of a symmetrical dish (not those that have a distorted shape, designed for off-center feed), to the focus point.

$$f = D^2/(16\ S)$$

Once the focus point is located, you must design a feed system to illuminate the reflector from that focus point.

Designing a Feed System

The feed system is a critical element of any such reflector array. To obtain the full benefit of the dish, the beamwidth of the feed antenna must be such that most of its radiation is kept within the dish, and it must fill the dish out to its edges. If the feed only illuminates part of the reflector, the remainder might just as well not be there. On the other hand, if the feed beamwidth extends beyond the width of the reflector, the power that misses the reflector is equivalent to attenuating that amount of power. Once you've found the focus location, as described above, finding the target beamwidth of the feed is easy. Look at Fig 17-9 again and note that the required horizontal and vertical beamwidth (BW) can be found as follows:

$$BW = 2 \tan^{-1}((D/2)/f)$$

In addition, the feed itself must be sufficiently small that it does not block a significant portion of the reflector surface. The fraction of the surface in the shadow of the feed, as well as its support structure, reduces the effective area of the dish and thus acts as an additional attenuator.

With all of those constraints in mind, virtually any relatively small unidirectional array can be used as a dish feed.



Fig 17-8 — A C band television receive-only dish modified for amateur space communication with motor-driven azimuth and elevation controls.



Fig 17-9 — Technique for determining focal point of symmetrical parabolic dish.

The only ones I've discussed to this point are cardioid arrays, which have a very wide beamwidth compared to most parabolas, and also plane or corner reflectors, which leave a relatively large shadow because of their size. Subsequent chapters will discuss various other options better suited for this service. These include horn, patch and Yagi antennas.

Summary

This chapter has discussed the construction of various types of unidirectional arrays you can construct using non-resonant surface reflectors. They generally operate with the simplicity of an optical mirror and, as a consequence, avoid many of the problems associated with the driving of phased arrays. Plane reflectors have been successfully employed from HF through UHF, while parabolic dishes are often the best choice in the microwave region and above.

Notes

[1] A. Monteiro, AA2TX, "A Panel-Reflector Antenna for 70 cm," *QST*, Feb 2005, pp 36-39.

[2] **www.arrl.org/files/qst-binaries/panel-antenna.zip**.

Review Questions

17-1. Discuss the relative merits of unidirectional phased arrays compared to surface-reflector antennas. Under what conditions might each have an edge in performance?

17-2. What are some of the limitations of parabolic-dish arrays? How can such limitations be overcome?

17-3. What would be the effect of using a backscreen of vertical wires behind a horizontally polarized antenna?

Chapter 18

Antenna Arrays With Parasitically Coupled Elements



An extreme example of parasitically coupled antennas. This is an array of 64 15 element Yagis.

Contents

Antenna Arrays With Parasitically Coupled Elements ...18-2
An Array With One Driven and One Parasitic Element..18-2
An Array With One Driven and Two Parasitic Elements.18-5
Chapter Summary 18-5
Review Questions..18-5

Antenna Arrays With Parasitically Coupled Elements

All the multi-element antenna arrays I have discussed so far have had some portion of the transmitter power feeding each of the elements directly through transmission lines. I have also discussed the fact that nearby elements couple to other elements via electromagnetic fields. In addition to having an impact on the element impedances, such mutual coupling results in changes in the directional patterns in the reception and transmission of signals. Now, I turn to arrays that purposely use mutual coupling.

An Array With One Driven and One Parasitic Element



Fig 18-1 Configuration of dipole with driven element and one parasitic element behind it.

A *parasitic* antenna system is one in which one or more elements are coupled to the driven element by mutual coupling only. The first example of this is shown in **Fig 18-1**. Here I take my typical resonant λ/2 dipole at 10 MHz, λ/2 above typical ground, and place another dipole of the same length — but with no transmission line attached to it — λ/4 behind it at the same height. This second dipole is just a λ/2 length of wire, with no connection to anything else.

This type of parasitic array using a driven element and other parasitic elements is named the *Yagi-Uda* array, in honor of the two Japanese scientists who developed it (although the array's name is often abbreviated to just *Yagi*). More complex Yagi arrays than the simple two element one in Fig 18-1 will be discussed in more detail in the next chapter.

Parasitic Element Impact on Pattern

A dipole by itself has a bidirectional pattern, as shown in **Fig 18-2**. Note that the peak gain after ground reflection is 7.4 dBi. By adding a single parasitic element, the pattern shifts to a *unidirectional* one. See the elevation plot in **Fig 18-3** and the azimuth plot in **Fig 8-4**. The gain in the direction opposite the side with the parasitic element is more than 3 dB higher than the dipole, while the front-to-back ratio is almost 10 dB.

It is interesting to compare this two element parasitic array to the cardioid unidirectional array presented earlier. Both arrays could be made from dipoles or vertical monopoles. While the pattern of a cardioid array is more dramatic than the pattern for the two element parasitic array in Fig 8-4, the deep null at the back exhibited by the cardioid only comes about from careful design and construction of a feed system that ensures proper phase shift and equal currents in each element. By contrast, the simplicity of the simple 2-element parasitic array is hard to beat.

Parasitic Element Impact on Dipole Impedance

In addition to the impact on the radiation pattern, a parasitically



Fig 18-2 — Azimuth pattern of reference dipole.



Fig 18-3 — Elevation pattern of antenna in Fig 18-1.

coupled element will also have an impact on the feed-point impedance of the driven element. **Fig 18-5** shows the modeled SWR curve of a reference dipole at a height of λ/2. By adding a λ/2 long parasitic element λ/4 away, the resonant frequency shifts downward more than 2%, as shown in **Fig 18-6**. Fortunately, you can compensate for this frequency shift by shortening the driven dipole to make it resonant again in the presence of mutual coupling to the second element. It becomes easier to feed the driven element using a typical coax line, while the unidirectional radiation pattern remains essentially unchanged. In other words, tuning the driven element alone has no effect on the radiation pattern.

What About Other Spacings?

I started with a spacing of λ/4, mainly because of the physical similarity to the driven cardioid configuration I described earlier in Chapter 7. There is nothing magic about this spacing distance, and you can obtain interesting results using other spacings. As you move the λ/2 long parasitic element closer than λ/4 to the driven element, the general trend is a lowering of the feed-point impedance of the driven element, plus a reduction in gain and front-to back ratio.



Fig 18-4 — Azimuth pattern of antenna in Fig 18-1.

An interesting phenomenon occurs as you reach very close spacings with a λ/2 long parasitic element. At a spacing of 0.085 λ, for example, the front-to-back ratio approaches unity and you'll see the azimuth pattern shown in **Fig 18-7**. While this shares the generally bidirectional pattern of a single dipole, the beamwidth is significantly narrower and the maximum is almost 3 dB higher than the dipole by itself. A look at the predicted SWR curve indicates that the driven element impedance drops to about 9 Ω. This is undesirable, since losses in the system begin to become an appreciable fraction of this small resistance.

Since you've passed the bidirectional point at a 0.085 λ spacing, as you move even closer you probably won't be surprised to find that the pattern now reverses itself. At a spacing of 0.05 λ, for example, you get the pattern shown in **Fig 18-8** with a λ/2 long parasitic element. At this close spacing the driven-element impedance has dropped to around 4 Ω, which makes for an even more difficult, and lossy, match.

Here's some terminology you will often encounter in discussions about parasitic arrays. If a parasitic element results in radiation away from it towards the driven element, it is called a *reflector*. On the other hand, if the radiation becomes focused in the direction moving towards the parasitic element from the driven element, the parasitic element is called a *director*.

Going to wider spacings affects things less dramatically than narrower spacings. The mutual coupling is reduced and the parasitic element has less effect on pattern and feed-point impedance. Both the gain and front-to-back ratio are generally reduced, but the driven element impedance rises. At a spacing of λ/2, the pattern actually has started to broaden, so there may be some applications for which a wide pattern



Fig 18-5 — SWR of single λ/2 dipole λ/2 above typical ground.



Fig 18-6 — SWR of driven λ/2 long dipole element with same-length parasitic element spaced λ/4 to the rear of driven element, both λ/2 above typical ground.



Fig 18-7 — Azimuth pattern of array with same-length parasitic element spaced 0.085 λ to the rear of driven element, both λ/2 above typical ground.

like that in **Fig 18-9** would be useful. The resonant impedance is back to about 80 Ω; however, the resonant frequency has shifted upwards some. At even wider spacings, there is little of interest to discuss.

What About Other Lengths for the Parasitic Element?

The other key parameter you can adjust is the length of the parasitic element — in other words, you can tune it. In an attempt to optimize forward gain and front-to-back ratio, I adjusted spacing and length of the reflector until I obtained the result shown in **Fig 18-10**. This is at a spacing of 0.2 λ with the reflector about 4% longer than the driven element. As a side note, it is an awful lot easier to go through these studies with an antenna modeling program such as *EZNEC* than to go out in the back yard, lower the antenna, change a parameter, hoist up the antenna and take readings — again and again and again!

It is also possible to head in the other direction, with closer spacing and a shorter parasitic element. By moving to a spacing of 0.085 λ and reducing the length of the parasitic element by 2.5% compared to the driven element (turning it into a director), the pattern of **Fig 18-11** was obtained. At this spacing and length, the driven element has an impedance of about 23 Ω.



Fig 18-8 — Azimuth pattern of array with same-length parasitic element spaced 0.05 λ to the rear of driven element, both λ/2 above typical ground.



Fig 18-9 — Azimuth pattern of array with same-length parasitic element spaced 0.5 λ to the driven element, both λ/2 above typical ground.



Fig 18-10 — Azimuth pattern of array with tuned parasitic reflector spaced 0.2 λ to the rear of driven element, both λ/2 above typical ground.



Fig 18-11 — Azimuth pattern of array with tuned parasitic director spaced 0.085 λ from the driven element, both λ/2 above typical ground.

An Array with One Driven and Two Parasitic Elements

Since a single parasitic element in a two element Yagi parasitic array can provide such benefit with relatively little effort, you may wonder whether adding more parasitic elements might do even more. The answer is yes.

The next chapter will go into more detail about such arrays, but the addition of a reflector and a director to the driven element (making a three element Yagi) can provide a good introduction to that discussion. The resultant pattern of a reflector at 0.2 λ spacing behind the driven element and a director at 0.085 λ ahead of the driven element is shown in **Fig 18-12**. The front-to-back ratio is now almost 25 dB, impressive indeed.



Fig 18-12 — Azimuth pattern of 3-element Yagi array with parasitic reflector and director.

Summary

I have introduced the concept of the use of parasitic (not-connected) elements in antenna arrays. These elements allow beam shaping without the problems involved obtaining correct phase relationships in previously described driven arrays. Neither does the parasitic array have the penalty of the large wind loads common to surface-reflector arrays.

Review Questions

18-1. Under what conditions might an array with one or more parasitic elements have advantages over directly driven phased arrays or surface reflector arrays previously described?

18-2. What is a negative consequence of closely coupled parasitic elements?

18-3. What can be the effect of cutting parasitic elements with a few percent error? How does this compare with driven arrays?

Chapter 19

The Yagi-Uda or Yagi, Parasitically Coupled Antenna



Yagis for multiple bands surround a higher frequency parabolic reflector array.

Contents

The Yagi-Uda, or Yagi, Parasitically Coupled Antenna...19-2
What's a Yagi All About? 19-2
Enough Talk; Let's See Some Examples! 19-3
Yagis With More Elements....19-6
Chapter Summary 19-7
Review Questions....19-7

The Yagi-Uda, or Yagi, Parasitically Coupled Antenna

The last chapter discussed the concept of parasitically coupled antennas. This antenna configuration was extensively evaluated and developed by two Japanese academics in the early part of the last century.

The concepts of the antenna later known as the *Yagi-Uda* were published in 1926 by Shintaro Uda, with the collaboration of Hidetsugu Yagi, both of Tohoku Imperial University, Sendai, Japan. Yagi published the first English-language reference on the antenna in a 1928 article and it came to be associated with his name.[1] However, Yagi always acknowledged Uda's principal contribution to the design, and the proper name for the antenna is the Yagi-Uda antenna (or array).

The Yagi was first widely used by Allied Forces as the antenna for VHF and UHF airborne radar sets during WW II, because of its simplicity and directionality. The Japanese military authorities first became aware of this technology after the Battle of Singapore, when they captured the notes of a British radar technician that mentioned "Yagi antenna." Japanese intelligence officers did not even recognize that Yagi was a Japanese name in this context. When questioned the technician said it was an antenna named after a Japanese professor. (This story is analogous to the story of American intelligence officers interrogating German rocket scientists and finding out that Robert Goddard was the real pioneer of rocket technology even though he was not well known in the US at that time.)[2]

Current usage in the US is to refer to this antennas configuration as a *Yagi*, and we will use that term in this book, with the understanding that Yagi is really short for "Yagi-Uda."

What's a Yagi All About?

The antenna developed by Uda and Yagi took the basic three element parasitic array described in the last chapter and extended it, through the addition of multiple directors, to provide a highly focused beamwidth signal for VHF and UHF (the "ultra short waves" in Yagi's article title). They empirically developed the early designs of such arrays, including the optimum lengths and spacings. The results have been relied on for many years, until the availability of modern computer modeling and simulation.

Why More Directors and not More Reflectors?

An effective reflector results in minimal signals behind the array. Thus additional reflector elements placed *behind* the first reflector receive only a very small residual signal going past the reflector element and therefore contribute little to the signal leaving at the front of the array. Occasionally, a multielement reflector structure can be found, but this is really just a different geometry at the approximate distance of the primary reflector. Sometimes a plane reflector is used behind the driven element for better front-to-back performance.

Additional directors, on the other hand, *are* in the path of the main beam formed from the driven element, reflector and any previous directors. Thus they continue to focus the beam further as it progresses forward along the antenna axis.

What Frequencies are Appropriate for Yagi Antennas?

While the original paper about Yagi-Uda antennas was focused (no pun intended) on VHF and UHF applications, there is nothing about that range that is specific to the Yagi design. On the low frequency side, the limits are the physical size of the structure. On the high frequency side, manufacturing tolerances, plus the effectiveness of other available alternatives, form the limits for the deployment of Yagis.

At upper HF and into the UHF range, Yagis tend to be made from rigid, self-supporting materials, such as aluminum tubing. At the low end, they are more often found as fixed antennas constructed of wire elements. At the upper end of the frequency range, they are sometimes even seen etched onto printed circuit material.

Enough Talk; Let's See Some Examples!

A discussion of Yagi antennas would probably start with the three element parasitic array I introduced at the end of the last chapter. However, Yagi development really gets into full swing with antennas having multiple directors. In keeping with the spirit of the original Yagi paper, I will shift the design frequency into the VHF range, but keep in mind that the results can be scaled to any frequency.

At VHF, ground reflections at any reasonable height rapidly shift through peaks and nulls. Thus I will change the usual environment to that of *free space* when generating patterns at these frequencies. **Fig 19-1** illustrates the point. Here you have the elevation patterns of identical 145 MHz reference dipoles, constructed of the same 0.25 inch aluminum tubing that I will use for the Yagis to come. One antenna is mounted 40 feet above real ground; the other is mounted in free space. The rapid fluctuations of field strength over ground tend to distract from the comparison between antenna designs. You will need to keep in mind if comparing antenna results that the main lobe gain of a free-space dipole is 2.13 dBi, while the gain of a dipole at the peak of the first elevation lobe over typical ground is 7.67 dBi. The difference of 5.54 dB is due to ground reflection gain and is close to the theoretical limit of 6 dBi. The ground reflection gain should be carried over when evaluating other free space designs.



Fig 19-1 — Comparison between elevation patterns of 145 MHz reference dipole in free space (dashed line) and the same dipole mounted 40 feet above typical ground (solid line).

The Medium Sized Three Element VHF Yagi

As noted, the three element Yagi is just an optimized and further developed version of the array with reflector and director described in Chapter 18. The configuration is shown in **Fig 19-2**. The spacing between the elements of a Yagi is a key design parameter. In general, wider spacings provide higher performance; while closer spacings result in a more compact physical configuration, but with less gain. You usually select a boom (the structural element supporting the elements) and then optimize the number of elements and their spacing on the available boom length to maximize performance. For my first example, I will start with a boom length of 0.3 λ and use 0.15 λ spacing between the driven element and both the reflector and director.

Azimuth Pattern

Careful adjustment of element lengths to obtain a resonant driven element, maximum front-to-back ratio and clean forward pattern with acceptable forward gain resulted in the element lengths shown in **Table 19-1**. The resulting free-space azimuth pattern is shown in **Fig 19-3**. The forward free-space gain of 7.84 dBi corresponds to a gain (compared to the gain of 2.13 dBi of a dipole in free



Fig 19-2 — Configuration of three element Yagi.

Table 19-1

Dimensions of the 3-Element Yagi with 0.15 λ Reflector and Director Spacing. All Elements 0.25 inches in Diameter.

Element	Length (λ)	Spacing from DE (λ)	Length (inches)	Spacing from DE (inches)	Difference (%)
Relector	0.490	0.15	40.53	12.2	3.8
Driven Element	0.472		38.42		
Director	0.440	0.15	35.82	12.2	–6.8



Fig 19-3 — Free-space azimuth pattern of three element Yagi tuned for front-to-back ratio (F/B).



Fig 19-4 — SWR (50 Ω) of three element Yagi in Fig 19-2.

space) of 5.7 dB. This is almost four times the power in the peak of the main lobe of a dipole in free space.

A key issue in the design of Yagi arrays is that the element spacings and lengths can be adjusted to obtain maximum front-to-back ratio, maximum forward gain or match to a particular impedance — but not all, or even two, parameters can be optimized using the same dimensions. It is thus important to decide what your design goals and acceptable parameter limits are before you start.

Matching to a Transmission Line

The 50 Ω SWR for the example three element Yagi is shown in **Fig 19-4**. Note that while the frequency of lowest SWR is somewhat below the design frequency of 145 MHz, the actual resonant frequency, the frequency with 0 Ω reactance, is at 145 MHz. The impedance at resonance is about 26 Ω, which is not a very convenient impedance for use with common transmission lines. This is fairly typical of Yagi antennas and I will discuss some of the techniques used to match transmission line to the generally low impedance of Yagi driven elements a bit later.

In general, this is a solved problem and I will not dwell on it as I talk about the Yagi properties in this section. For example, in this case, a $\lambda/4$ section of 36 Ω transmission line (which is available, but two common 75 Ω lines in parallel could also be used) will transform the 26 Ω to 50 Ω. The SWR plot transformed to 26 Ω, under the assumption that some sort of matching arrangement is provided is shown in **Fig 19-5**.

Yagi Operating Bandwidth

For many antenna types, the key parameter determining operating bandwidth is the frequency range over which a usable SWR is provided. Depending on requirements, that definition may or may not be appropriate for a Yagi. For example, the 26 Ω 2:1 bandwidth of the three element Yagi in Fig 19-2 is from around 141 to 147.5 MHz, as shown in **Fig 19-5**. This is about a 4.5% range around the center frequency, compared with around 8% for a similar diameter dipole.

As the frequency is changed within the operating bandwidth of a dipole, however, the pattern remains virtually constant. This is not the case with a Yagi. **Fig 19-6** shows the azimuth pattern of the Yagi in Fig 19-2 at both ends of the SWR bandwidth. Note that the forward gain is actually a bit higher, but the front-to-back ratio is significantly reduced at each end of this frequency range. Had I optimized for forward gain, rather than front-to-back ratio, you would have seen a different form of change. Whether the difference from design center performance is significant depends on your application.

It is often possible to adjust the element lengths to result in slightly less than optimum performance at a spot frequency, but for more satisfactory performance over a wider bandwidth. This is often done by making the reflector a bit longer and the director a bit shorter than optimum.

Changing the Element Spacing

Within the constraint of a boom length of 0.3 λ, you can distribute the element spacings differently and come up with a different antenna. One choice would be to have the reflector 0.2 λ behind the driven element and the director 0.1 λ in front. This is the kind of change Uda and Yagi made empirically in the laboratory, but it is even easier to do with a modeling program like *EZNEC*!

The result, perhaps with a bit of optimization left for the student, is shown in **Fig 19-7**. And **Fig 19-8** shows the azimuth with the spac-



Fig 19-5 — SWR (26 Ω) of three element Yagi in Fig 19-2.



Fig 19-6 — Azimuth pattern of three element Yagi in Fig 19-2 at 2:1 SWR limits.

ings reversed — the reflector at 0.1 λ behind the driven element and the director 0.2 λ in front. The forward gain is about 1 dB higher in this arrangement and the front-to-back ratio has improved slightly. The feed-point impedance is, however, reduced to about 10 Ω following the tweaking of lengths to regain a reasonable front-to-back ratio. There is no free lunch!

The Short and Long of Three Element VHF Yagis

If space constraints are paramount you can employ shorter boom lengths, at some cost of performance. **Fig 19-9** shows an example of a three element Yagi on a 0.1 λ boom, with equally spaced director and reflector. As is evident, this design gives up from 1 to 2 dB of forward gain compared to previous antennas with three times the boom length. The front-to-back ratio is also reduced compared to the larger antennas. This antenna has a resonant feed-point impedance of about 11 Ω.

You can also go in the other direction, using a longer boom and wider element spacing. If you make the array roughly square at 0.5 λ per side with a boom of that length, you can have a bit more of everything. I will later discuss that such a boom may be better served by adding a director or two, but the three element design can be close in performance and is lighter to raise and turn. It also has less wind loading. With careful optimization, this antenna can have additional gain, but probably not as good a front-to-back ratio as the 0.3 λ design presented earlier. It also can provide a direct 1:1 match to 50 Ω coax cable.



Fig 19-7 — Azimuth pattern of 0.3 λ boom three element Yagi with 0.2 λ reflector and 0.1 λ director spacing.



Fig 19-8 — Azimuth pattern of 0.3 λ boom three element Yagi with 0.1 λ reflector and 0.2 λ director spacing.



Fig 19-9 — Azimuth pattern of 0.1 λ boom three element Yagi with 0.05 λ reflector and director spacings.

Yagis with More Elements

What I've discussed so far has set the stage for more interesting designs of long-boom Yagis with more elements — the focus of the original Yagi-Uda work. The design variables and adjustable parameters are the same — boom length, the number of elements, element spacings and element lengths. The outcomes are the same as well — forward gain, front-to-back ratio, driving impedance and operating bandwidth. As for the earlier designs, the optimum for all parameters never occurs with any one design.

With each element you add to the mix, you get two independent variables — the element's length and its spacing from neighboring elements. Since the number of combinations of adjustments goes up with the square of the variables, it can become quite a challenge to be sure you have found the optimum. Let's see — if I make this element a bit longer — and then adjust all the other spacings and lengths to compensate — am I getting better or worse performance? You get the idea!

Fortunately, there has been a lot of work done on this subject since Yagi's 1928 paper and you don't have to reinvent every wheel. *The ARRL Antenna Book*, for example, lists lengths and spacings for many proven, optimized Yagi designs for the HF and VHF/UHF amateur bands. These designs can be scaled to provide a starting point for other applications or frequency bands too.



Fig 19-10 — Gain of optimized Yagi as a function of boom length (Courtesy of *The ARRL Antenna Book*).



Fig 19-11 — Azimuth pattern of seven element Yagi on 1 λ boom.

The Boom Length — Element Count Issue

When you start looking at antennas with boom lengths longer than about λ/3, you sometimes run into an interesting marketing gambit. Antenna manufacturers tend to market their long Yagis based on element count, with the boom length buried in the specifications sheet. In fact, boom length is arguably the most critical parameter in long boom Yagi design. For any given boom length, there is an optimum design (including an optimum number of elements) that will provide the gain shown in **Fig 19-10**.

You can also obtain the same gain with an antenna on a given boom length with more elements; however, that doesn't mean that this design has more value than one with less elements — in fact, since most antenna installations are designed to withstand a certain level of wind force, having more directors (and hence more wind-surface area) may well be a disadvantage. Watch this if you are considering buying an antenna array.

A Short "Long Yagi"

The azimuth plot of an example of an array with a boom length of 1 λ is shown in **Fig 19-11**. Note that the forward gain is close to that predicted in Fig 19-10. Its dimensions are provided in **Table 19-2** for the case with a nonmetallic boom. Metal booms may also be used; however, an adjustment in element length is usually required for them.

A Longer "Long Yagi"

Extending the Yagi to a boom length of a bit less than 2 λ results in the azimuth pattern of **Fig 19-12**. Again the forward gain is close to that predicted in Fig 19-10. This analysis could be extended as far as desired; however, a few observations are in order.

If you were to place a six element combination broadside-collinear



Fig 19-12 — Azimuth pattern of 10 element Yagi array on 2 λ boom.

Chapter Summary

Table 19-2

Dimensions of the seven element Yagi on 1 λ Insulated Boom. All Elements 0.25 inches in Diameter.

Element	*Length (λ)*	*Spacing from R (λ)*	*Length (inches)*	*Spacing from R (inches)*	*Difference (%)*
Relector	0.503	0	40.94	0	6.1
Driven Element	0.474	0.15	38.58	12.28	
Director 1	0.458	0.216	37.32	17.59	−3.3
Director 2	0.450	0.338	36.61	27.52	−5.1
Director 3	0.438	0.508	35.67	41.34	−7.5
Director 4	0.432	0.717	35.20	58.35	−8.8
Director 5	0.431	0.961	35.12	78.19	−9.0

array in front of a backscreen reflector (such as was shown earlier in Fig 17-5 in Chapter 17), the resulting reflector array provides a forward gain within about 0.5 dB of the longer 2 λ Yagi array. The antenna with the backscreen reflector, however, is about 1.5 λ high, 1.5 λ wide and 0.25 λ deep, while the Yagi is 2 λ long, about 0.5 λ wide, and not very high. You're trading, in effect, volume for area for two different arrays with comparable gains.

Whatever you decide to call "optimum" for any particular installation depends on your specific requirements. I should also point out that the reflector array from Chapter 17 has much less sensitivity to dimensional tolerances or changes in frequency, while the long-boom Yagi is more sensitive to these effects.

You could keep extending the boom and gaining additional forward gain. Another alternative is to *stack* another copy of the array on top of the first. At the optimum stacking distance, you can increase the gain by almost 3 dB. Stacking compresses the elevation pattern, rather than further squeezing more gain out of the azimuth pattern, as happens when you lengthen the boom of a Yagi. Stacking is often a good method to get more gain, since doubling the boom length results in an increase of about 2 dB.

A Yagi antenna array can have significant gain and front-to-back ratio compared to other types of structures. It offers more gain per unit of wind-surface area than many other types of high-gain systems, at the cost of having tighter dimensional tolerances and correspondingly narrow operating bandwidth. Multiple Yagi arrays can often be combined into stacks of very effective antenna systems.

Notes

[1] H. Yagi, "Beam Transmission of Ultra Short Waves," Proceedings of the IRE, 16, pp 715-740, Jun 1928.

[2] **en.wikipedia.org/wiki/Yagi_ntenna.**

Review Questions

19-1. What are some of the major advantages of Yagi antennas compared to other types of systems previously covered?

19-2. What are some of the major disadvantages of Yagi antennas compared to other types of systems previously covered?

19-3. Under what conditions might a stacked arrangement of Yagis be more useful than a single Yagi with the same total boom length. What are the disadvantages of such a system?

Chapter 20

Practical Yagis for HF and VHF

Yagis for two frequency ranges share a tower.

Contents

Practical Yagis for HF & VHF 20-2

Matching a Yagi to a Transmission Line 20-2

Let's Build Some Yagis..20-5

Chapter Summary 20-8

Review Questions..20-8

Practical Yagis for HF and VHF

The last chapter discussed the structure and results obtained with Yagi antennas. Yagis are found in antennas designed for MF through the middle of the UHF region. As has been mentioned, one downside of Yagi antennas is that satisfactory operation requires close attention to tight dimensional tolerances. I will describe here some representative, reproducible Yagi designs. You can scale them to other frequencies, but at your own risk!

Matching A Yagi to a Transmission Line

As discussed earlier, one potentially unpleasant characteristic of Yagi antennas, particularly those with close-spaced elements, is that the driven element impedance is often quite low. This is a function of parasitic element length and spacing. While it is generally possible to find parasitic element spacings and lengths that will result in a 50 Ω driven element impedance, those dimensions are not generally compact. They are also often not the ones that give best front-to-back ratio, nor the highest forward gain.

Yagi designs are compromises. Even ignoring driven element impedance, the dimensions that give best front-to-back ratio generally do not provide best forward gain. Still, once your objectives and priorities are defined, there is likely to be some Yagi configuration that meets them. By having a feed connection arrangement that works with a wide range of impedance values, you are free to optimize your trade-off between front-to-back ratio and forward gain without being constrained unduly by impedance concerns.

Before I describe particular Yagi designs, I will discuss some of the methods used to match Yagi driven elements to transmission lines.

Q Bar Matching

One of the earliest methods used to match low impedance Yagi driven elements to 50 Ω coaxial cable was called a "Q Bar." This arrangement, shown in **Fig 20-1**, is nothing more than a λ/4 transmission-line matching section. In order to match a given resistive antenna impedance (Z_A) to any transmission-line characteristic impedance (Z_0), a λ/4 transmission-line matching section of characteristic impedance Z_L can be inserted between them. The characteristic impedance of Z_L is equal to:

$$Z_L = \sqrt{Z_0 Z_A}$$

(Eq 1)

For example, if you had an antenna with a feed-point impedance of 20 Ω and wanted to match it to 450Ω ladder line, you would need a transmission line that had a characteristic impedance of 95 Ω.

The characteristic impedance of parallel-wire transmission line in free space is found as follows:

$$Z_L = 276 \ \log_{10}\left(\frac{2D}{d}\right)$$

(Eq 2)

where D is the center-to-center spacing and d is the conductor diameter.

If you had a line made from 0.25 inch diameter rods, spaced 0.275 inches center-to-center, you could achieve a Z_0 of 95 Ω, but it would make for a tight fit. You also wouldn't want to do this for a very long distance. Note that this only works if D > d, otherwise the two conductors would be touching. This sets the lower spacing limit at 83 Ω, not far from where you are now.

A more modern adaptation of this technique would be to match to a 50 Ω line. This could not work with the Q bars, but could be done with a transmission line with a characteristic impedance of 31.6 Ω. This could be approximated by paralleling two 75 Ω lines, with a resultant impedance of 37.5 Ω.

The Folded-Dipole Match

The two wire folded dipole was shown in Fig 11-11 in Chapter 11. This antenna takes up essentially the same space as a conventional single-wire dipole, but the feed-point impedance is four times the imped-



Fig 20-1 — Q-bar matching system. Note that only a limited range of values can be accommodated.

ance of a regular dipole. If a Yagi's driven element exhibits an impedance of 12.5 Ω, a folded-dipole driven element would have an impedance of 50 Ω. Note that only the driven element, not the parasitic elements, needs to be changed to a folded-dipole configuration to obtain this transformation.

The Delta Match

An *autotransformer* is a transformer with a single winding in which taps on parts of the winding provide the desired voltage-to-current ratio, or impedance ratio. The same concept applies to antennas. A half wave antenna element has a high impedance at its ends and a low impedance at the center. If you connect a transmission line between intermediate points, you can match virtually any impedance, from that of the center to that of the end-to-end impedance.

The *delta match* is perhaps the simplest implementation of this principle. It is shown in **Fig 20-2**. There is nothing magic about the dimensions, although the two connections should be equally spaced from the center to maintain balance. In use, the connection points are adjusted until a reasonable match is obtained. This will change the element tuning somewhat, so the driven element length must then be adjusted for minimum SWR and the connection points moved again, back and forth until you obtain the desired match.

This match can be used directly with a balanced transmission line, or through a balun to coax. You could use a 4:1 loop balun to match 200 Ω connection points to 50 Ω coax. See Fig 9-6 in Chapter 9. For this match, and for the next several connection methods, the center of the unbroken driven element is at zero potential, so you can connect it directly to a metallic boom if you like. If the boom and mast are well-grounded, this may have benefits in terms of lightning protection.

Typical starting points for an HF dipole connected to 600 Ω line are at a spacing between connection points of 0.12 λ for HF (0.115 λ for VHF) and a match length of 0.15 λ. The spacing should be moved inward for lower impedances until the best match is found. The driven element will generally need to be shortened a few percent to obtain an exact match.

Fig 20-2 — Delta matching system.



The T Match

Another adaptation of the autotransformer principle is called the *T match*. It differs from the delta match mainly in the connection method. The T match uses bars parallel to the antenna element to make connections to the dipole. Matching adjustment is generally provided through the adjustable position of sliding shorting bars, as shown in **Fig 20-3**. As with the delta match, the adjustments should be carried out by moving the bars the same amount on each side to maintain balance.

The T match was introduced in a *QST* article in 1940.[1] The authors (including the soon-to-be-legendary Dr John Kraus, W8JK), described a method to connect 600 Ω transmission line to a wire dipole and determined that the spacing of the shorting bars should be 24% of the dipole length for that case, with a spacing in inches of the T bars of 114/f, in MHz.



Fig 20-3 — T matching system, one of the most popular systems. It is often used with a 4:1 balun and coax feed.

For a typical Yagi made of tubing, the T-rods are usually ⅓ to ½ the diameter of the driven element. The distance between shorting bars is usually a bit less than half the driven element length.

As with the delta match, the T match is often adjusted to 200 Ω and used with a λ/2, 4:1 loop balun to match to 50 Ω coaxial cable. The T match will act to lengthen the effective dipole length. This can be accommodated by either shortening



Fig 20-4 — Detail of trombone capacitor for T or gamma match.



Fig 20-5 — Gamma matching system. Essentially half a T match. No balun required.



Fig 20-6 — Hairpin matching system. Can be visualized as a "folded T-match."

the dipole, or by inserting capacitance in the T bar connections. The capacitance is often made by using a "trombone" coaxial tuning section on each side of the T, as shown in **Fig 20-4**.

The Gamma Match

The *gamma match* is just half of a T match. It extends out from the boom towards one side of the driven element, as shown in **Fig 20-5**. Because it only extends to one side, just one side of the driven element needs shortening, or a trombone or other capacitance can be used to compensate for the added inductance. The gamma match, inherently unbalanced, provides for direct connection to coaxial cable without needing a balun.

For a typical Yagi made of tubing, the gamma rod is usually ⅓ to ½ the diameter of the driven element spaced about 0.007 λ center-to-center from the driven element and about 0.04 to 0.05 λ long to match 50 Ω. A capacitance value of about 7 pF per meter of wavelength will avoid the need to shorten the driven element beyond about 3%.

The Hairpin Match

An alternative to tapping out along the driven element is to load the center of the dipole with a shunt inductance connected to each side. This brings the electrical center effectively further out along each side of the dipole. A low-loss inductor can be formed by a short ($<< \lambda/4$) section of balanced transmission line. This arrangement, shown in **Fig 20-6**, has the appearance of a hairpin and thus it is called a *hairpin match*.

Some early work, reported in *QST* in 1962, defined the hairpin parameters for a Yagi antenna operating at 14.28 MHz.[2] These are shown in **Fig 20-7** and **Fig 20-8**. The required inductance and line length (the same line width should be used) both go down directly with frequency, so results can be scaled to provide a starting point for other frequency antennas.

This kind of match is simple to construct and works well. Note that unlike most of the other techniques mentioned, it requires a split driven element. While it will work as shown in Fig 20-6, a balun should be inserted between the driving point and the coax to avoid feed-line radiation, which can distort the antenna pattern. The balun can be as simple as a coil of the coax feed line.



Fig 20-7 — Inductance required for hairpin matching to various driving point resistances at 14.28 MHz.



Fig 20-8 — Length of 2 inch wide hairpin inductor as a function of required inductance at 14.28 MHz.

Let's Build Some Yagis


Light Nylon Cord
Insulator
2" × 2" Pine or Cedar
20 m Reflector 1065 cm (34.94')
15 m Reflector 708 cm (23.23')
3/16" Nylon Rope
10 m Reflector 531 cm (17.42')
20m Driven Element Total Length/Side 488 cm (16.01')
15m Driven Element Total Length/Side 335 cm (10.99')
10m Driven Element Total Length/Side 254 cm (8.33')
Tie Knot Here
213 cm (6.99')
175 cm (5.74')
125 cm (4.10')
Drill Hole and Thread Rope Through to Adjust so when the Antenna is Raised it is in a Horizontal Plane.
Insulator
Insulators
Light Nylon Cord
1/2" PVC Pipe Spreaders
Hairpin Match
UBA0201

Fig 20-9 — Dimensions of the VE7CA triband 2 element Yagi.

A Portable Two Element Triband Yagi

Perhaps the simplest of Yagis is the wire triband HF Yagi designed by Marcus Hansen, VE7CA.[3] Hansen is also the designer of a wonderful homemade HF transceiver that outperforms all but the highest performance commercial HF transceivers.[4]

This antenna is made of wire elements supported between 2 × 2-inch wooden spreaders. The three bands are covered by parallel driven elements, fed with a single hairpin match. The antenna uses separate reflectors, optimally spaced for each band. While shown as a triband, two element-array, it could be easily simplified into a two element monobander, or even a three element monobander for one of the higher bands by putting the driven element near the center and adding a director element. In my experience, a three element Yagi for 20 meters would be at the outer edge of what could be asked of 2 × 2-inch spreaders, although it might work for a weekend operation, when there's no wind.

A High-Performance 144 MHz 10 Element Yagi

This antenna illustrates the use of a T match and aluminum tubing to construct an easy to duplicate, but no-compromise, VHF Yagi, first described by K1FO. This antenna is one of many cases of a basic design that can be used from 10 through 19 elements described in recent editions of *The ARRL Antenna Book*.[5]

This antenna is shown in **Fig 20-13**. If you build it closely following the design specifications (given in mm to increase precision), it will yield a gain of 11.4 dBd (13.5 dBi) and a front-to-back ratio of better than 17 dB across the whole 144 to 148 MHz band. It has a 39° azimuth beamwidth when mounted as a horizontally polarized antenna.


Coax Feedline Coil About 6 to 8 Turns 10 cm (4") Diameter
Wrap Wire Around Spreader and Antenna Wire on Both Sides
1/2" PVC Pipe Spreader
9 cm (3.5")
9 cm (3.5")
43 cm (16.9")
Hard Drawn Stranded #14 Copper Wire
10 cm (4")
#14 Solid Copper House Wire
Shorting Bar
UBA0202

Fig 20-10 — Close-up of the VE7CA tribander's feed point.



Fig 20-11 — Predicted elevation pattern of the VE7CA tribander on 20 meters. Other bands will be similar, but for the same height (26 feet in this example) will have a peak lobe at a lower elevation angle.

The antenna is constructed on a 1¼ inch outside diameter boom with the elements spaced from the reflector as shown in **Table 20-1**. Details of the driven element construction are shown in **Fig 20-13**. The design is intended for the low end of the band, generally used for long-haul SSB and CW weak-signal work. It can be easily adapted to the FM portion centered at 147 MHz by shortening all elements by 17 mm.

The antenna is matched by a 200 Ω T-match and λ/2 long 4:1 loop balun designed to feed coaxial cable to the radio. When complete, adjust the T-match shorting bars for the best match. This should be done in its final position, if possible. If not, temporarily mount it as high as practical and point it upward to minimize near-ground reflection effects while adjusting the match.

Table 20-1

Dimensions of the 10 Element 144 MHz K1FO Yagi. All elements are ¼ inch diameter rod or tubing.

Element	*Position (mm from Reflector)*	*Length (mm)*
Reflector	0	1038
Driven Element	312	955
Director 1	447	956
Director 2	699	932
Director 3	1050	916
Director 4	1482	906
Director 5	1986	897
Director 6	2553	891
Director 7	3168	887
Director 8	3831	883

Diameter Matters

I have previously discussed the impact of antenna element diameter on both the resonant frequency and bandwidth of antennas. The topic is worth repeating in this discussion about Yagi antennas, since they use different kinds of construction techniques.

Wire Yagis are often used at the lower frequency ranges, where solid rotatable antennas may not be practical. In the upper HF and higher regions up to UHF, Yagis are almost always constructed of tubing supported by a single central boom. The examples I have provided in this chapter include antennas in both camps, wire and tubing.

Table A

14.15 MHz Dipole Lengths for Different Element Diameters

Diameter (in)	*Length (in)*	*Length (ft)*	*L/D*	*#/F*
0.081	402.5	33.5	4968.9	474.6
1	394.8	32.9	394.8	465.5
1-2 Stepped	405.6	33.8	n/a	478.3
2	390.8	32.6	195.4	460.9
3.75	386.4	32.2	103.0	455.6

Yagis at Upper HF

At the low end of the frequency range for rotatable antennas, structures tend to be large and mechanical issues are often paramount. While lower-frequency rotatable Yagis down to 7 MHz are sometimes encountered, the 14-MHz amateur band marks the low end for most Yagi builders. Elements can be 35 feet long and booms even longer on 20 meters. Even with "lightweight" aluminum materials, a 3 or 4 element 20 meter Yagi can be quite a mechanical challenge.

The problem is to have elements that can support themselves, both with static and wind loads, while being secured at a single point in the center. Larger sizes of thick-wall tubing are strong, but they are heavy. Smaller sizes are light, but they bend under the strain of their own weight if they are long. The answer is to use telescoping sections of progressively smaller and lighter tubing as you progress from the center to each end of an element (and boom too). The center section can be heavy to provide strength, without much bending moment, while the sections further from the center can be smaller, with thinner walls since they don't support as much weight. This technique is often referred to as stepped diameter approach. An additional advantage of this technique is that the element lengths can be easily adjusted by loosening the joints and sliding the outer ends in and out.

Modeling Stepped-Diameter Antennas — the Results

One possible difficulty is how to effectively model tapered elements by computer. The abrupt change in diameter as sections are transitioned is difficult for the NEC engine to handle. Fortunately EZNEC, and other modeling implementations, implement a correction process for these tapering effects.

To give an idea of the differences with and without tapering, Table A shows the modeled resonant lengths of dipole elements resonant at 14.15 MHz for different diameter elements, all mounted 50 feet above typical ground. The 0.81 inch entry represents #12 wire used in my HF example. The 1 to 2 inch tapered entry changes from 2 inches down to a 1 inch diameter, in steps of 0.25 inches. Of particular note is that EZNEC predicts such a tapered element must be longer than either a continuous 1 or 2 inch diameter element.

The entry #/F corresponds to the oft-quoted resonant length of a wire dipole of 468/F, where F is in MHz. That is a reasonable approximation for a wire antenna at lower frequencies but can be misleading when tapered elements of tubing are used.



Fig 20-12 — Predicted main-lobe azimuth pattern of the VE7CA tribander on 20 meters. Other bands will be similar.


Rear Boom Section
1-1/4" OD x 0.049" wall
6061-T6 round tubing
1219 mm (48") long
Center Boom Section
1-3/8" OD x 0.058" wall
6061-T6 round tubing
1829 mm (72") long
Rear Boom Section
1-1/4" OD x 0.049" wall
6061-T6 round tubing
1219 mm (48") long
No. 8-32 Screw
(2 places)
Slot and use
hose clamp (2 places)
20 mm
Mast Clamp
1016 mm
(40")
1829 mm
(72")
1016 mm
(40")
3871 mm
(152.4")
UBA0205
BOOM LAYOUT

Fig 20-13 — Layout of 10-element 144 MHz high-performance K1FO Yagi.


955 mm
83 mm
9.5 mm
No. 6 Screw
Nut and
Lockwasher
Driven Element: 0.5" Dia (12.5mm) x0.035"
Wall Aluminum Tube
Shorting Strap
Make from
0.032" Aluminum
Attach Balun Ends
to T Bars
T Bars Supported on
3/4" High Delryn Insulators
40 mm
12.5mm
Flatten Ends of
"T" Tubes
50mm
381 mm
386 mm
T Bars
3/8" x 0.035"
Aluminum
Tubing
Inches = mm x 0.0394
Driven Element Detail 12-Element 144 MHz Yagi
(A)
Driven Element Side View
Front of
Yagi
22 m
Balun
Balun Shield is Grounded
Material 0.062" Aluminum
Connector Bracket
Balun Center Conductors
Attach to T Bars
3/4" Long x 3/8" Dia
Delryn Insulator
Hole Pattern
for UG-58A/U
No. 19 Hole
(2 places)
32mm
20mm
42mm
64mm
22mm
44mm
7mm
50mm
64mm
7mm
No. 21 Hole for T Bar
Insulators (2 places)
(B)
Solder Lugs
Balun
Shield
Shield 684mm
750 mm
Material: RG-142/U or RG-303/U Teflon-insulated Coaxial Cable
ANT0704
(C)

Fig 20-14 — Construction details of 10 element 144 MHz high-performance K1FO Yagi.

Chapter Summary

This chapter discusses building and using Yagi antennas. I presented some of the most commonly encountered methods of matching Yagi driven elements, which tend to exhibit lower impedance than dipoles because of mutual coupling to the other elements. Examples of designs with very different construction methods were presented, including examples of hairpin and T-match arrangements.

Review Questions

20-1. Consider a center-fed dipole with added reflector and director elements to become a unidirectional 3 element Yagi. Why will there likely be a need to change the method that the coax is connected to the dipole?

20-2. Why can't Q-bars be used to match a 25 Ω impedance Yagi driven element to 50 Ω coax?

20-3. Compare a T-match to a gamma match. What are some of the benefits and disadvantages of each?

Notes

[1] J. Kraus, W8JK, and S. Sturgeon, W8MPH, "The T-Matched Antenna," *QST*, Sep 1940, pp 24-25.

[2] J. Gooch, W9YRV, O. Gardener, W9RWZ, and G. Roberts, "The Hairpin Match," *QST*, Apr 1962, pp 11-14.

[3] M. Hansen, VE7CA, "A Portable 2-Element Triband Yagi" *QST*, Nov 2001, pp 35-37.

[4] M. Hansen, VE7CA, "A Homebrew High Performance HF Transceiver--the HBR-2000" *QST*, Mar 2006, pp 5-9.

[5] R. D. Straw, Editor, *The ARRL Antenna Book*, 21st Edition. Available from your ARRL dealer or the ARRL Bookstore, ARRL order no. 9876. Telephone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.orgshop/**; **pubsales@arrl.org**.

Chapter 21

Log Periodic Dipole Arrays



The log periodic dipole array is an effective wideband unidirectional antenna.

Contents

Log Periodic Dipole Arrays 21-2
What's an LPDA All About? 21-2
Chapter Summary 21-5
Review Questions 21-5

Log Periodic Dipole Arrays

A wideband unidirectional antenna design that is frequently encountered from HF through UHF is called the *log periodic dipole array*, or LPDA for short. This antenna is unique in a few respects:

- An LPDA can provide wideband coverage without adjustment over as much as a 10:1 frequency range, although usually designed to cover a narrower range, typically 2:1 or 3:1 (for example, 10 to 30 MHz, or 150 to 450 MHz).
- An LPDA has a relatively constant gain, pattern and match across the entire range.

The antenna was developed as an outgrowth of studies of other periodic structures by Raymond DuHamel and Dwight Isbell of the University of Illinois in 1957 and has been in wide use since.[1]

What's an LPDA All About?

As its name implies, an LPDA is an array of dipoles. These dipoles are arranged in a special way, with an element-to-element spacing that is logarithmic. The configuration is shown in **Fig 21-1**. Note that the dipoles are fed from the front by a transmission line that is reversed between each successive pair of elements. The combination of out-of-phase feed and Yagi like element length tapering result in radiation focused towards the feed point from those dipoles in the *active region*, as shown in Fig 21-1. The active region contains the dipoles resonant or near resonant at the applied frequency. The LPDA can be fed directly with a 300 Ω balanced transmission line, or fed with coax through a wideband 4:1 or 6:1 balun transformer.

Performance Across a Frequency Range

The dipoles in the active region are responsible for the radiation on a given frequency. The dipoles on the left in Fig 21-1 are resonant at higher frequencies and exhibit a progressively higher capacitive reactance as you move from the active region towards the left side of the array. They thus accept little current and do not contribute to the radiation at the chosen frequency. Similarly, elements to the right of the active region are longer than resonant and appear inductive at the operating frequency.

As the frequency increases, the active region moves to the left and operates in a similar manner and with similar performance until the frequency is higher than just below the resonant frequency of the far-left dipole. As the frequency is reduced the active region moves to the right until it reaches a frequency somewhat below the resonant frequency of the far-right hand element. The far-right and far-left dipole resonant frequencies define the range of operating frequencies for the array.



Fig 21-1 — The basic layout of a log-periodic dipole array (LPDA) wideband unidirectional antenna.

How Big or Small Is an LPDA?

From the discussion above, it should be evident that if the array is lopped off at one or both ends, it should still work, but over a narrower frequency range. That is definitely the case. Small segments of a larger LPDA design are sometime used as driven elements for relatively narrowband Yagi arrays. In this hybrid Yagi/LPDA array, the Yagi directors help the LPDA driver cell provide a better front-to-back pattern, while the LPDA driver cell expands the SWR bandwidth beyond the usual narrowband coverage of a Yagi with a single driven element.

In general, the longer the array for a given frequency range, the longer the LPDA active region is and the more elements it must contain. LPDA arrays with relatively large active regions provide more gain and lower SWR ripple across the region. For those who would like to see the design equations, they are straightforward, if somewhat tedious, and are presented in the sidebar. Computer software is available for those who need to perform the calculations often.



Fig 21-2 — Example of an HF LPDA designed for operation over the 18.1 to 28-MHz amateur bands.

So What's Not to Like in an LPDA?

An LPDA can be an excellent choice for some applications, especially those employing wide band signals, such as very wide spread spectrum and especially those employing HF automatic frequency selection (*automatic link establishment* or ALE) based on changes in propagation. In the latter, the radio frequency can shift by a large amount in the midst of communication in response to changes in propagation conditions. This is determined by automatic testing and handshaking between the two ends of the radio link. An LPDA, unlike many HF systems, has no problem following the changes with essentially the same gain and directivity as the frequency shifts — perhaps across the entire HF region.

Perhaps the only downside of an LPDA is that for any given subset of its frequency range, other structures, even narrow-range LPDAs, can be significantly smaller. This is not a bad trade for operations in which the lower frequency end of the range is generally used, with only occasional excursions to the high end, since the majority of the size and mass is being used much of the time. On the other hand, if most of the operations are at the higher end of the range, only a relatively small portion of the mass of the LPDA is used much of the time and other options may be more cost and size effective.

The LPDA is especially well suited for cases where operation can occur on any part of the spectrum it covers. Some services, such as the Amateur Radio service and the maritime HF service, to name a few, require operation across the HF range, but operate within a finite number of relatively narrow bands within the range. These services can often be supported by multiband Yagi designs that operate on just the multiple narrow bands, but not the whole range. Such systems tend to be smaller and give higher gain than LPDAs covering the entire range.

Other LPDA Configurations

LPDAs are seen in a number of other configurations besides the basic one shown in Fig 21-1. The next most common is one in which the transmission line is not crossed between elements, but the elements are switched from side to side instead. The two sides of the transmission line are generally placed one above the other and the transmission line itself serve as booms for the two sets of elements. Two thick booms provide for a lower-impedance feed than the thin wires of Fig 21-1 and this can provide a good match for 50 or 75 Ω coax — often fed down the inside of one of the booms.

LPDAs are often used as receive antennas for the US television bands. A single LPDA can provide good reception for the VHF channels (including the 88 — 108 MHz FM broadcast band) from 54 to 216 MHz. A single LPDA can cover both the VHF and UHF TV channels (from 470 to 806 MHz). Because of the resulting unneeded coverage over the gap between 216 and 470 MHz, it is more efficient (as discussed in the last section) to have a separate array for the UHF channels. These are generally combined on the same boom to provide a single feed. The UHF antenna portion could be another LPDA, but often consists of a corner reflector array in front of the VHF LPDA.



Fig 21-3 — Typical free space azimuth plot of short LPDA.

Examples of Real LPDA Systems

A version of an LPDA, adapted from an early edition of *The ARRL Antenna Book* is shown in **Fig 21-2**. This was used as the basis for an *EZNEC* model to determine the typical performance of such a system. I designed it to be shorter than optimum (see sidebar), but physically manageable.

A representative free-space azimuth plot is shown in **Fig 21-3** and a 200 Ω SWR plot is shown in **Fig 21-4**. This LPDA is intended to be used with a wideband 4:1 transformer-type balun and then fed by



Fig 21-4 — 200 Ω SWR of HF LPDA in Fig 21-2.

coaxial cable going to the station. The performance is less than what can be obtained from a single-band Yagi array on any of its bands, but this LPDA covers all of the 17, 15, 12 and 10-meter amateur bands, as well as everything in-between.

Photos of commercially available LPDA systems for HF and VHF to UHF are shown in **Figs 21-5** and **21-6**.



Fig 21-5 — Example of an HF LPDA. This antenna covers 13 to 30 MHz..



Fig 21-6 — Another example of a commercial LPDA. This VHF-to-UHF antenna, a Comet/NCG CLP-5130, covers 50 to 1300 MHz, with an advertised forward gain of 10 to 12 dBi. It occupies a 6.7 foot boom. (*Courtesy Creative Design Corp.*)

Designing an LPDA

A full chapter of *The ARRL Antenna Book* is devoted to the design of an LPDA. However, I will here cover the very basics, drawing from that excellent reference.[2]

An LPDA is designed to fit into a truncated triangular shape, as shown in Fig 21-A. Each of the elements just touches the boundary of the triangle, giving the array its characteristic arrow shape. All the element dimensions and spacings are based on the parameters in Fig 21-A. The general design considerations are as follows:

The smaller the angle is, the higher the gain and larger the array for any frequency within the range.

The ratio of highest-to-lowest frequency is roughly proportional to the ratio of longest-to-shortest element, if constructed per the following rules.

The relationship between successive element lengths and spacings can be set to a constant (tau) as follows:

$$\tau = \frac{R_{n+1}}{R_n} = \frac{D_{n+1}}{D_n} = \frac{L_{n+1}}{L_n} \qquad \text{(Eq 1)}$$

where R_n and R_{n+1} are the distances from the triangle apex of element n and its nearest inboard neighbor.



Fig 21-A — Key parameters for the LPDA design equations.

While I have defined the relationship between adjacent elements and their spacings, I haven't defined the initial spacing. I will thus define another constant as follows:

$$\sigma = \frac{1-\tau}{4\tan\alpha} = \frac{D_n}{2L_n} \qquad \text{(Eq 2)}$$

where D_n is the distance between any two elements of the array and L_n is the length of the longer of the two. For any value of , you may determine the optimal value of $_{opt}$, as follows:

$$\sigma_{opt} = 0.243\tau - 0.05 \qquad \text{(Eq 3}$$

The value for and its corresponding value of yields the highest performance that the LPDA is capable of. The optimum value generally results in a longer boom than is practical, especially in the HF range. Smaller values of provide a smaller footprint with corresponding reduction in gain and additional SWR ripple.

Chapter Summary

This chapter discussed log-periodic dipole arrays (LPDAs). These unidirectional antennas are unique in their ability to cover an almost arbitrary range of frequencies with relatively constant gain, directivity and feed-point impedance. They are straightforward to design and construct, although they do tend to be large compared to antennas with similar performance for any single part of their frequency coverage. They are used throughout the HF to mid-UHF range, often as rotatable arrays from the middle of the HF range through the UHF range.

Notes

[1] R. DuHamel and D. Isbell, "Broadband Logarithmically Periodic Antenna Structures," IRE National Convention Record, part 1, pp 119-128, 1957.

[2] R. D. Straw, Editor, The ARRL Antenna Book, 21st Edition. Available from your ARRL dealer or the ARRL Bookstore, ARRL order no. 9876. Telephone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.org/shop/; pubsales@arrl.org.**

Review Questions

21-1. Consider an LPDA array in comparison to a Yagi. What are the advantages and disadvantages of each?

21-2. Why can't a 4:1 $\lambda/4$ coaxial cable loop balun be effectively used with a wide-range LPDA?

21-3. Describe any other antennas that could fill the place of an LPDA. How do they compare?

Chapter 22

Loop Antennas



This loop antenna, made from plumbing supplies, makes an effective MF receiving antenna.

Contents

The Large Loop in a Vertical Plane 22-2

The Large Loop in a Horizontal Plane 22-4

The Small Loop Antenna 22-6

Chapter Summary 22-7

Review Questions...22-7

This chapter really describes two completely different antennas. The two major divisions are based on the size of the antenna in terms of wavelength. A *small loop* is one whose diameter (or diagonal for a rectangular shaped loop) is much less than a wavelength, while a *large loop* has a diameter approaching or larger than a wavelength.

The Large Loop in a Vertical Plane

I'll start the discussion with the special case of a square loop in a vertical plane, with each side having a length of λ/4.

The Square Quad Loop

Look at **Fig 22-1**, a repeat of Fig 7-1, but with arrows added to indicate the current direction when each source is fed in-phase. This is a broadside array, which has bidirectional gain perpendicular to the page. At a λ/4 spacing, neither the gain nor the end-fire cancellation are optimum, but it would still be a useful performer.

If you bend each dipole towards the other to maintain a λ/4 horizontal section on each dipole, you end up with the configuration shown in **Fig 22-2**. Note that the horizontal sections are still in-phase, while the vertical sections each include the same amplitude of current in opposite phase and thus their vertically polarized radiation is canceled. Note also that the voltages on each side of both gaps are the same, since the two antennas are in phase at corresponding points along their lengths.

Thus, as shown in **Fig 22-3**, with the voltages on each side of the gap the same, you can connect the ends together without changing anything. Having done that, you can remove the upper (or lower, your choice) source and both sides will be fed across the former gap.

It's interesting to compare the performance of such a quad loop with a dipole. If you use my usual HF frequency of 10 MHz and model both at 1 λ above typical ground (to the center of the loop) you get the results shown in **Fig 22-4**, **Fig 22-5** and **Fig 22-6**. Note that the SWR shown in Fig 22-4 has about the same shape and bandwidth as a dipole, but has an impedance at resonance of 123 Ω, rather than the dipole's 70 Ω. This is not much of an issue since you can match it quite nicely to 50 Ω with a λ/4 section of 75-Ω line.



Fig 22-2 – Array of Fig 22-1, with ends bent at 90° to form a square. Note that the currents on the vertical portions are out-of-phase, while the horizontal portions remain in-phase. The two sides of each gap are at the same potential.

The shapes of the elevation and azimuth patterns are very similar to those of a dipole at the same average height, except the loop has about a 1 dB advantage in gain at this height. Note the clear tradeoffs between a dipole and a quad loop. A quad loop needs half the spacing between supports. But for comparable low-angle performance, the quad loop needs supports that must be λ/8 higher.



Fig 22-1 – Two horizontal dipoles fed in-phase to form a broadside array. The arrows indicate the direction of current flow.



Fig 22-3 – Array of Fig 22-2 with gap closed to close the square. The single source now feeds both "bent dipoles" across the gap.



Fig 22-4 — SWR of quad loop referenced to 123 Ω.



Fig 22-5 — Broadside elevation pattern of quad loop (solid line) compared to dipole (dashed line).



Fig 22-6 — Azimuth pattern of quad loop (solid line) compared to dipole (dashed line) at same average height.

(When both are mounted at the same height, the quad loop's gain at 14° elevation matches the dipole's gain.)

But wait there's more! The loop needs an additional λ/2 of antenna wire, but it needs λ/4 less transmission line. Since transmission line generally costs more than twice as much as wire, that is generally to the plus side for a loop. In addition, there is less sag and tension at the top of the loop, if the wire is supported from the sides.

So the full-wave quad loop provides just a bit of additional gain, and fits into a smaller horizontal space than a dipole. But it needs a minimum of at least λ/3 to λ/2 vertical space to make sense. Otherwise, it acts a lot like a dipole. As I will discuss in the next chapter, a quad loop is frequently used as the basis of multielement arrays.

Quad Loops in Other Shapes

Not surprisingly, most other 1 λ loop configurations have been used, generally with similar results. The two most popular besides the square are shown in **Fig 22-7**. The first, the so-called *diamond* shape, is considered by some to be less resistant to ice build up — more important in some geographical areas than in others. Note that the diamond can be suspended from a single support, but requires 1.4 times the horizontal clearance of its square brethren. The single support must be about 0.05 λ higher to have the same effective height, but that doesn't generally matter in practice. If the corners are secured by ropes to the ground, this antenna configuration allows manual azimuth pointing adjustment from the ground.

The triangular, or *delta*, configuration is particularly attractive as a dipole substitute for cases in which the dipole's required λ/2 spacing between supports is not available, although it doesn't have quite the same effective height.

Operating on Other Frequencies

A dipole provides useful radiation on frequencies higher than its resonant frequency, if you can get power to it without loss — such as by feeding it with low-loss open-wire line. The radiation pattern changes dramatically above a full wave in length, moving from being primarily broadside pattern to a multi-lobed one. Such a pattern can sometimes be beneficial, sometimes not. A quad loop is not quite as frequency friendly, as shown in **Fig 22-8**. Note that the result is an elevation pattern pointing mainly upwards. Fig 22-8 shows the endfire view, rather than the broadside direction. Loops are best used on or near their fundamental design frequency, at least until you lay them on their sides, as will be discussed in the next section.

Multiband operation is often accomplished by switching between different loops, one for each desired band. Higher frequency loops are often nested within lower frequency loops. The non-resonant loops usually have sufficiently high impedance that they can be driven together, with the energy going where it is supposed to go. But you must make sure no odd harmonics are involved since those will take power and radiate in strange directions.



Fig 22-7 — Loops in the diamond and delta configurations. Each is generally 1 λ in circumference.



Fig 22-8 — Elevation plot of 10 MHz quad loop operated on 20 MHz.

The Large Loop in a Horizontal Plane

A full wave, or larger loop laid on its side, parallel to the ground, is a useful antenna. This is frequently encountered in amateur circles, and is often referred to as a *Loop Skywire*, a name popularized by a Nov 1985 article in *QST*. The usual configuration is a square or diamond shaped loop about 277 feet in circumference, fed at one corner. This provides a full wave circumference in the 80 meter band and at multiples of 1 λ on many of the higher amateur HF bands. The layout is shown in **Fig 22-9**.

At typical heights of around 50 feet, which is less than λ/4 on 80 meters, the radiation is largely upwards, as shown in **Fig 22-10**. This is well suited for reliable *near vertical incidence skywave* (NVIS) operation out to around 1000 miles or so. The Loop Skywire has useful radiation at lower angles as well. **Fig 22-11** shows the azimuth pattern at an elevation angle of 25°, an angle useful for long-haul operation, with a gain of around that of an isotropic radiator along the diagonal from the corner to the feed point. There is also a notable lack of deep nulls, compared to say a dipole, providing reasonable coverage around the compass.

The feed impedance is similar to the loop in the vertical plane, and for a single band it can be fed through a matching section with coax, as described earlier. The usefulness of this orientation becomes more evident as you move to higher bands, as I shall discuss further below. So it is often fed with low-loss line such as 400 Ω window line. The SWR plot across 80 meters at 400 Ω is shown in **Fig 22-12**.

Operating on Other Frequencies

The Skywire Loop works well at harmonics. The radiation that would otherwise go skyward when a loop is mounted vertically will now leave towards the horizon, providing long haul coverage on the traditional long distance bands. The elevation pattern on 14 MHz is shown in **Fig 22-13**. The azimuth pattern at this frequency is interesting. The pattern at 20° elevation is shown in **Fig 22-14**, which shows four pronounced lobes, each rivaling a small Yagi in forward gain.

The SWR at its second harmonic, 7 MHz, to the top of the HF region is shown in **Fig 22-15**. Note that it is reasonable throughout the range for use with low-loss window line. There are dips of SWR at the harmonics, becoming progressively lower on 20, 15 and 10 meters. This illustrates the flexibility of this antenna in that, much like the dipole operated on higher frequencies with low-loss line, this loop is also useful, with more gain and interesting patterns that are different on each band.



Fig 22-9 — Loop Skywire antenna configuration.



Fig 22-10 — Elevation pattern of Loop Skywire on 80 meters.



Fig 22-11 — Azimuth pattern of Loop Skywire at 25° elevation on 80 meters.

A Loop Variation — the Terminated Rhombic

The square loop has lobes from each of the wires, and these combine in different directions to form complex lobe structures. These lobes vary as a function of azimuth angle on the higher frequencies. It is possible to adjust the angles of the loop to concentrate the lobes along the major axis of the loop. Tables are available in handbooks to provide the optimum angles as a function of leg length and desired elevation angle. The results are shown in **Fig 22-16** for the loop operated on 28.3 MHz, at which each of the four sides (or *legs*, in rhombic talk) is now 2 λ long. Here, I closed down the angle at the feed from 45° on each side of axis (90° total for a square), to 35° for a 2 λ leg length.

The desired lobe to the right in Fig 22-16 is the result of current running from the source towards the far end. The lobe to the rear results from current reflected from the far end returning towards the source. You can reduce the rearward lobe by terminating the end of the antenna with a resistance that equals the characteristic impedance of the antenna system. In effect, this antenna looks like a long transmission line. Around 600 Ω is usually optimal, and with such a termination you get the pattern shown in **Fig 22-17**.

The terminated rhombic makes an excellent HF, or even VHF, directional antenna that can be built at low cost. It does take up a lot of space compared to a Yagi, however, and does have a narrow beamwidth, so is best for fixed point-to-point links. If you adjust the dimensions to compromise lengths and angles, it can be effectively used for up to a four-to-one frequency range.



Fig 22-12 — SWR of Loop Skywire on 80 meters for 400 Ω transmission line.



Fig 22-13 — Elevation pattern of Loop Skywire on 20 meters.



Fig 22-14 — Azimuth pattern of Loop Skywire on 20 meters.



Fig 22-15 — SWR of Loop Skywire from 7 to 30 MHz for 400 Ω line.



Fig 22-16 — Azimuth pattern of horizontal loop adjusted for optimum 10 meter on-axis pattern.



Fig 22-17 — Azimuth pattern of loop modified to be 10 meter terminated rhombic.

The Small Loop Antenna

Loops that are quite small compared to a wavelength (typically less than 0.1 λ in circumference) operate in a very different manner from large loops. Small transmitting loops are sometimes encountered; however, they suffer from having a very low radiation resistance, requiring extraordinary measures to avoid excessive losses. They also have very narrow operating bandwidths — typically in the tens of kHz in the upper HF range. Still, some are commercially available and some have been home constructed with satisfactory results, considering their size.

The most frequent application of small loops is for reception, particularly in the LF to low HF region. A small receiving loop also suffers from the possibility of low-efficiency due to losses, but this is not generally much of a problem for receive loops in this frequency range. The reason is simple: at LF through MF and into the lower HF region (80 meters, for example), received signal-to-noise ratio is limited by external noise picked up on the antenna along with the signal so any loss reduces both noise and signal.

If you're lucky enough to have a 1940s or somewhat earlier AM broadcast radio in your basement, attic or perhaps still in operation in your living room, a look at its back will likely reveal an MF receiving loop. The typical radio of the period had enough sensitivity that it could receive local stations with a multiturn loop, serving as the radio's input tuned circuit as well as a receiving antenna.

A view of this type of antenna is shown in **Fig 22-18.** Note that the multiple turns, as with an electromagnet, couple to a propagating magnetic field coming from the edge of the loop, the opposite of the orientation of a large, full-wave loop. Note also that the horizontal orientation of the magnetic field implies that a vertically polarized waveform will provide maximum response.

Well, this is just what you want from a receiving loop at the lower frequencies. The vertical polarization is compatible with the ground wave signals arriving from broadcast stations, with their vertical transmitting arrays. The directivity does have deep nulls at right angles to the plane of the loop. Some early broadcast sets had the capability to move the antenna angle so that the whole radio wouldn't need to be reoriented to pick up stations.

After WW II, ferrites became popular as a magnetic core usable well into the radio spectrum. The earlier air-core loops were replaced by compact ferrite core antennas called *loopsticks*. These could use less wire for the same inductance and fit better in the more compact radios of the period. Such antennas were also used in marine-radio direction finders, used to determine the bearings to MF beacons that were located throughout bays and harbors. These were used until the advent of more recent LORAN C and then GPS navigation systems.

As I will discuss in the next chapter, receiving loops can be used to advantage as directional antennas for reception in the MF and low HF bands, discriminating against noise and interference by taking advantage of their directional properties.



Fig 22-18 — Illustration of a small receiving loop antenna, with its response to an incoming magnetic field.

Chapter Summary

Loop antennas can take a number of forms and each has a special place in radio. Large loops are efficient HF radiators that can be used by themselves or as part of arrays. Vertically oriented loops give dipoles a run for their money, and horizontal ones can provide considerable flexibility from a single antenna.

While a small loop can be force fit into transmitting applications, it shines the most if used for MF receiving. In this application, its advantages can be taken advantage of without excessive concerns about its loss limitations.

Review Questions

22-1. Consider a vertically oriented loop compared to a horizontal dipole. What are the relative advantages and disadvantages of each in the same space?

22-2. What are the benefits of large horizontal-plane loops compared to vertical-plane loops on harmonics of their primary resonant frequencies?

22-3. Compare the benefits of small loops for receiving with the use of such loops as transmitting antennas.

Chapter 23

Loop Antennas You Can Build



This loop antenna transmits and receives on 40 meters or can tilt down for transport.

Contents

Loop Antennas You Can Build 23-2
A Quad Loop for HF 23-2
Two Element Cubical Quad for 20 Meters 23-4
The Loop Skywire 23-6
Low Noise Receiving Loop 23-7
Chapter Summary 23-9
Review Questions 23-9

Loop Antennas You Can Build

The loop antennas described in the last chapter are not only good performers, especially considering their low cost, but they are generally easy to build and get operating. They tend to be dimensionally forgiving and generally non-critical as to construction method compared to some other antenna types. The designs presented here can be scaled in frequency to work other bands without undue difficulty.

A Quad Loop for HF

The quad loop is an effective antenna, especially for HF operation. The antenna is inexpensive to make, has less *wingspan* than a λ/2 dipole and avoids the center droop and mechanical loading of an end-supported dipole with heavy coax feed at its center. Depending on the spacing between supports and their height above ground, it can be square, rectangular or delta shaped.

The key dimension is the total length of the loop wire, although, as noted previously, the length depends to a certain extent on whether the loop is square or triangular in shape. For a square loop with top 88 feet above typical ground, the length in feet is around 1030/F (MHz) at 3.8 MHz.

A triangular loop will require about 1016/F (MHz) at 3.8 MHz. These guidelines were established at 3.8 MHz using *EZNEC* models. The modeled lengths at some other frequencies are shown in **Table 23-1**. Height above ground, nearby objects and ground conditions will also make a difference in resonant frequency, so always start a bit long and trim a little at a time to move the resonant frequency to the part of the band you want. Construction suggestions are provided in **Fig 23-1**.

There is a slight performance difference between the square quad loop and the delta loop configurations, mainly due to the effective height above ground. The square loop will have an effective height equal to that of its center, half way between the two horizontal sections, as you might expect. The delta configuration, with the apex at the bottom will have an effective height somewhat higher. By comparison, a horizontal dipole will have its effective height at or slightly above the height of its center, depending on the amount of sag.



Fig 23-1 – Loops in the "quad" and "delta" configurations. Each is generally 1 λ in circumference.

While the full-wave loop has a gain of almost 1 dB over a dipole in free space, closer to the earth and constrained by the same support height, the dipole actually has a bit of an edge at low angles. This is shown in **Fig 23-2** and in

Table 23-1

Comparison of Dipole and Loop Dimensions (feet) on Some Amateur Bands. Top Height for all is 88 Feet.

Band (Meters/MHz)	*80/3.75*		*40/7.15*		*20/14.15*		*10/28.3*	
Antenna	*Width*	*Height*	*Width*	*Height*	*Width*	*Height*	*Width*	*Height*
Dipole	128	Nil	66.6	Nil	33.6	Nil	16.8	Nil
Delta Loop	91.4	79.2	48.7	42.2	24.6	21.3	12.4	10.7
Square Loop	67.6	67.6	36.2	36.2	18.3	18.3	9.2	9.2

Table 23-2

Comparison of Dipole and Loop Parameters and Performance.

3.8 MHz Antenna	*Width (feet)*	*Elevation Angle*	*Peak Gain (dBi)*	*Gain at 42° Elevation (dBi)*	*Impedance (Ω)*
Dipole	126.4	42°	6.29	6.29	90
Delta Loop	90.4	47°	5.72	5.64	130
Square Loop	66.8	50°	5.31	5.16	120

Table 23-2. The difference shows up mainly in the elevation angle of the main beam, with lower angles needed for longer distances. As shown, the differences are about 1 dB at most, and thus the physical and mechanical considerations are often the decision makers.

Besides height, the other aspect of any trade-off is the space required between horizontal supports.

Table 23-2 provides the dimensions and performance figures for a square quad loop, an equilateral delta quad loop and a horizontal dipole at 3.8 MHz, all at a top height of 88 feet, corresponding to the height of the delta apex being 10 feet above the ground.

Dimensions for some amateur bands are provided in Table 23-1 for the bare #12 wire used in the modeling. In all cases, the antennas are suspended from 88 foot high supports. If insulated "house wire" is used, reduce the dimensions by about 2%.



Fig 23-2 — Elevation plot of 3.8 MHz dipole (solid line), delta (dashed line) and quad loop (dotted line) at same top height.

Two Element Cubical Quad for 20 Meters

One of the most popular HF loop antenna systems is the two element *cubical quad.* This is essentially a two element Yagi using loop elements. While more than two elements are sometimes found, the two element version is the most popular. It is often said that a two element quad is similar in performance to a three element conventional Yagi, due to the free space gain of a full-wave loop over a dipole. This difference is maintained with more elements but a point of diminishing returns can be reached in terms of array size.

Still, at the two element point, the quad is quite attractive. It has a width about half that of a conventional Yagi, and its boom length is about half of a three element Yagi with comparable gain. Its elements can be constructed of wire supported by an inexpensive structure and its higher feed impedance is much easier to directly feed than that of a Yagi. There's a lot to like in this picture!


Reflector
Driven Element
Bamboo or Fiberglass "Spreaders" Eight Places
Wooden or Metal Plate with U-bolts for Spreaders and Flange for Boom Two Places
Antenne Wire Tied to Spreader Ends
Feed Piont Connect λ/4 75 Ω to Transform to 50 Ω
UBA0230

Fig 23-3 — Cubical quad construction.

Building a Quad

The only tricky aspect of a quad array is that the structural elements holding the corners of the loops can't be solid metal. A typical square cubical quad is shown in **Fig 23-3**, along with construction suggestions. Key dimensions are shown in **Table 23-3** for a quad made of #12 wire with the antenna's center 50 feet above the ground.

Table 23-3

Key Dimensions of 20-Meter, two element Cubical Quad for 14.15 MHz.

Parameter	*Length*
Total Driven Element	70 feet, 2 inches
Length × Frequency	993
Driven Element Spreader	12 feet, 5 inches
Total Reflector	73 feet, 7 inches
Length × Frequency	1041
Reflector Spreader	14 feet, 7 inches
Boom	10 feet
Matching Section (75 Ω Poly, 0.66)	11 feet, 6 inches
Matching Section (75 Ω Foam, 0.8)	13 feet, 11 inches

Note that I have selected a 10 foot boom for this example. A 13 foot boom would provide a bit more gain on 20 meters; however, 10 feet is an easier length to obtain and works better for higher bands if you wish to add them later. The LENGTH × FREQUENCY entry in Table 23-3 is there in case you wish to move the center frequency. Just divide the value by the desired frequency (in the same band) and you will have the new length in feet. These numbers are somewhat different than the oft-published ones, and reflect this band at this height and element spacing.

The spreaders can be made from bamboo poles, which are sometimes available free from carpet dealers. Alternately, there are fiberglass poles made for fishing that may be suitable. If bamboo is used, it should be given a few coats of exterior varnish to increase its weather resistance.

The boom should be made from 1.5 or 2 inch thick walled aluminum tubing, depending on expected wind load and weight of the completed element assembly. Modeling showed no discernible difference with or without an aluminum boom and a 10 foot aluminum mast at its center, so materials for these functions do not impact electrical performance in the same way that they do for the element spreaders.

So How's it Play?

The modeled performance is shown in **Fig 23-4** and **Fig 23-5** for a height of 50 feet above typical ground. Note the nice azimuth pattern and the sharp front-to-back ratio. The forward gain of more than 12 dBi is more than 4 dB higher than a simple quad loop without a reflector at the same height. The three element Yagi discussed in Chapter 20, adjusted at 14.15 MHz at a height of 50 feet has a forward gain



Fig 23-4 — Elevation pattern of two element 20-meter cubical quad.



Fig 23-5— Main-lobe azimuth pattern of two element 20 meter cubical quad.

of 12.3 dBi, so the quad is definitely a contender in a smaller, perhaps less expensive and more compact package.

The 100 Ω SWR curve is shown in **Fig 23-6**. Note how flat it is across the band. It could be fed directly with 75 Ω coaxial cable, or better, with 93 Ω coax, if available. The usual arrangement, however, is to transform the impedance through a λ/4 section of 75 Ω cable. The result is an almost perfect match to 50 Ω coax at mid band. Table 23-3 shows the required lengths of solid and foamed polyethylene dielectric coax using the typical values shown. If you have manufacturer's data available, adjust for published relative dielectric constant.

Adding Additional Bands to the Two Element Quad

It is possible to use the same spreaders and quad infrastructure to support another quad for additional bands. For the case of a 20 meter quad, you could choose any of the four higher frequency HF amateur bands and install the quad wires symmetrically inside the two 20 meter loops. Note that a 10 foot boom length is 0.22 λ at 21.2 MHz, a good spacing for a two element beam.

The resulting dimensions are shown in **Table 23-4**. Note that while the unmodified 20 meter quad still operates on 20 meters following the addition of the second quad, although its optimum gain and front-to-back ratio has moved down about 150 kHz. For this reason, I have shown a new total length for the 20 meter reflector. The resonant frequency was not significantly changed so I did not change the driven element's dimensions.

The 15 meter quad's performance is shown in **Fig 23-7**, **Fig 23-8** and **Fig 23-9**. The gain is a bit higher due to the wider spacing. The 20 meter performance is unchanged, following the adjustment of reflector length.

Feeding the Two Band Quad

The best way to feed the two-band quad is by having a λ/4 transformer of 75 Ω coax from each feed point and then either separate 50 Ω transmission lines back to the station, or a single 50 Ω line with a remotely controlled relay. Some have simply connected the feed points together and used a single line; however, my modeling indicates that while the performance does not seriously suffer, there will be high SWR on at least one band. This will result in increased feed-line loss, with a net decrease in system gain, as well as a more complicated tuning network at the transmitter end.



Fig 23-6 — 100-Ω SWR of two element 20 meter cubical quad.



Fig 23-7 — Elevation pattern of two element 15 meter cubical quad using the same boom length as the 20 meter quad.

Table 23-4

Key Dimensions of Interlaced 20 and 15 meter, two element Cubical Quad for 21.2 and 14.15 MHz.

Parameter	*Length*
New 20 Meter Reflector	72 feet 10 inches
Total 15 Meter Driven Element	46 feet, 7 inches
Length × Frequency	987
Driven Element Spreader	12 feet, 5 inches
Total 15 Meter Reflector	50 feet, 5 inches
Length × Frequency	1068
Reflector Spreader	14 feet, 7 inches
Boom	10 feet
Matching Section (75 Ω Poly, 0.66)	11 feet, 6 inches
Matching Section (75 Ω Foam, 0.8)	13 feet, 11 inches

Adding Even More Bands

Quad builders have been known to build quads with wires for as many as five bands on a single set of spreaders. There is no reason that this could not be done; however, I have a few caveats:

- Expect to have to deal with a fair amount of interaction and subsequent retuning. You may want to provide a mechanism for easy adjustment of element length.
- The element spacing at one or the other ends of the range is likely to suffer, resulting in performance far from optimum on at least one band. A way to avoid this issue is to mount the spreaders in such a way that the spacing between elements increases as you get closer to the outer end of the spreader.



Fig 23-8— Main lobe azimuth pattern of two element 15 meter cubical quad.



Fig 23-9 — 100-Ω SWR of two element 15 meter cubical quad.

The Loop Skywire

The Loop Skywire introduced in the last chapter is another popular antenna among Amateur Radio operators. The basic configuration is shown again in **Fig 23-10**. You use a 1 λ loop on the lowest frequency of operation. Many people use it on other bands as well. The impedance varies by band as shown in **Table 23-5** for a 272 foot overall length, square loop at a height of 50 feet. Note that unless the 80 meter resonance is at the very bottom of the band, the harmonic resonances are not in quite the right place. While some people feed the Loop Skywire directly with 75 Ω coax, the SWR is quite high on the higher bands, partly masked at the bottom end of the coax due to the loss caused by the high SWR. A better solution is to use low loss open wire feed line and then to use an adjustable matching device (antenna tuner) at the bottom to transition to 50 Ω coax.



Fig 23-10 — Loop Skywire antenna configuration, 272 feet overall length.

Table 23-5

Impedance of 277-Foot Long Loop Skywire on Different Bands.

Frequency (MHz)	*Resonant Impedance (Ω)*
3.65	137
7.35	100
10.9	240
14.45	235
21.5	240
28.6	234

Performance charts for the antenna are shown in Chapter 22. I have heard from readers who had limited space but who were successful with all sorts of loop shapes, some at much lower heights. Perhaps this is based on comparisons with other, even more unsatisfactory antennas, but the Loop Skywire seems to be flexible even in such problematic applications!

Low Noise Receiving Loop

From the middle HF frequencies (from 14 MHz upwards), the usual challenge for a receiver is to capture the maximum signal it can, since the received signal-to-noise ratio (SNR) is generally limited by noise within the receiver at those frequencies. Every additional 0.1 µV helps!

Below about 14 MHz, depending largely on the time of year, the location and receiver specifications, much more noise is received by the antenna than is generated within the receiver itself. Much of this noise comes from thunderstorm static crashes, plus electrical noise from arcing powerlines and other such manmade sources. Under such circumstances, increasing the amount of signal captured generally increases the received noise, also, with no improvement in the signal-to-noise ratio (SNR).

This situation allows us to design antennas specifically for improved SNR, rather than for maximum signal. A small receiving loop is one antenna that can be used to improve SNR. The improvement is a result of a number of factors. First, a small loop is quite directional along the plane of the wires in the loop, so it can be rotated to find the azimuth with maximum SNR, often by placing specific noise source arrival directions in its deep nulls. In addition, it is responsive to vertically polarized signals arriving from low angles, rejecting horizontally polarized signals that may come from nearby (or even distant) noise sources.



Fig 23-12 — Pull L2 (2 mm OD stranded PVC insulated wire) through the tubing first and secure its end with tape while L1 (0.6 mm solid wire with PVC insulation) is being wound. If you have trouble pulling the length of all six turns through, it may be cut and spliced at the gap after pulling it all through.



Fig 23-11 — Schematic of the HH160RL. Both L1 and L2 are within the tubing. C2 is a receiving-type variable capacitor. If a capacitor of at least 280 pF, or a common 365-pF receiving type is used, C1 is not needed. L1 is a six-turn loop; L2 a single turn.

There are a number of published designs; however, the one that follows is from an article by Richard Marris, G2BZQ, in *QST*, Oct 1985, pp 45-46. It is straightforward and easy to reproduce. Richard called his the *HH160RL*, for Hula Hoop 160 meter receiving loop. He built his from a discarded Hula Hoop, but you can use any 24 inch length of semi-flexible plastic tubing with an inside diameter of at least ⅝ inches.

The circuit of the receiving loop is shown in **Fig 23-11**. Note that the very narrow bandwidth and low radiation resistance of such a small antenna make direct connection inefficient. It is common, as in this design, to transformer couple to a pick-up loop mounted within the main loop to avoid interfering with loop tuning and efficiency.

Construct the loop as described in **Fig 23-12, Fig 23-13** and **Fig 23-14**. A split bamboo or PVC plug that fits into and joins the tubing ends around the wires can be used to hold the ends together. Slide the plug into each end with the loop wires in the middle until there is a gap of about ¼ inch. Use epoxy (or for a PVC joint, PVC cement) to hold it together. Mount the loop in the chassis box, wire per the schematic and try it out. Note the directional pattern in **Fig 23-15**, the oppostie of that of a large loop.



Fig 23-13 — The loop is installed in a wooden or metal chassis box containing the variable capacitor with wood braces as shown.


UBA0240
1/8" Thick Top and Sides
Hole for C2
3"
5/8"
12"
Front View
2-7/8"
5-3/4"
Side View
Slots for Hoop
Top View
Exit Hole for Feed Line
Rear View
Hoop
Chassis
Complete Chassis and Hoop

Fig 23-14 — Detailed views of the chassis construction.


Null
Maximum
Maximum
UBA0241
Null

Fig 23-15 — Reception (azimuth) pattern of the receiving loop. It is turned to make best use of its sharp null to minimize noise.

Chapter Summary

Large loop antennas can be effectively used for both transmitting and receiving and offer some physical advantages over other types of structures. There are a number of configurations and each has a special place in antenna technology.

Small loops can be made into very narrow-band transmitting antennas, but really shine as directional MF receiving antennas. They can improve received SNR while taking little space and costing little.

Review Questions

23-1. Which antenna, strung from the same halyards, has the most of its radiation at lower angles — a dipole, square loop or delta loop with apex at the bottom? Which is next? What accounts for the difference?

22-2. Why is low-loss line recommended for a Loop Skywire on the harmonics of its 1 λ resonant frequency?

22-3. Why would an indoor low-noise receiving loop not likely to be of significant benefit at VHF?

Chapter 24

Antennas for Microwave Applications



Daryl, KG4PRR, installs a microwave reflector array.

Contents

Antennas for Microwave Applications 24-2

Waveguide 24-2

Horn Antennas 24-3

Slot Antennas 24-4

Patch Antennas 24-5

Chapter Summary 24-5

Review Questions 24-5

Antennas for Microwave Applications

The antennas I've discussed so far have been what I would call traditional, in that they are connected to transmitters via transmission lines. At the higher UHF into microwave frequencies, the losses associated with transmission lines can be avoided by using other technology for RF power delivery.

Waveguide

One such system is called *waveguide*, a replacement for coaxial cable in the upper UHF to SHF range for many applications. A waveguide is a completely different kind of transmission medium from traditional coaxial or other transmission lines. Transmission lines have loss that goes up logarithmically with frequency. For example, a very satisfactory 50 Ω coax cable for HF, such as RG-213, will have a matched loss for 100 feet at 1 MHz of about 0.2 dB, about 0.6 dB at 10 MHz, 2 dB at 100 MHz, 8 dB at 1 GHz and about 30 dB at 10 GHz.

The reason for the increase of loss with frequency is simple: there are two primary loss mechanisms. The first is the resistance of the conductors, primarily the inner conductor because of its smaller size. The resistance goes up with frequency due to *skin effect*.

Losses within the dielectric between the conductors in a coax cable generally also increase with frequency, for any kind of solid material. Since power at microwave frequencies is usually expensive to generate, coaxial cable is generally found only in very short interassembly cables or for noncritical functions.

A waveguide is a metallic duct structure that accepts a propagating wave and supports transmission through the length of the duct with minimal attenuation. In order to do this, waveguide must be of a size comparable to a wavelength. The inside surface of the duct is a good conductor — often silver plated — that establishes boundary conditions allowing fields that support propagation down the guide. The fields are excited inside one end of the waveguide by small antennas that form a transition between circuit elements, including transmission lines, on the outside and propagating fields on the inside of the waveguide.

One way to think about waveguide is as an extension of open-wire transmission line. **Fig 24-1** shows an open-wire transmission line with a single λ /4 shorted stub in parallel with the line. The shorted stub has an infinite impedance at its open end and thus can be bridged across the line without changing the flow of energy down the line. You could continue adding such stubs on both sides of the line until they become a continuous tube with a rectangular cross section. The result is a waveguide that will transport RF at a frequency corresponding to its width of 2 × λ /4, or λ /2. Signals with a frequency much below this *cutoff* frequency will not be propagated, supporting the size-to-frequency relationship of the waveguide.

Although I've seen waveguide used in high budget military radars at frequencies around 450 MHz, most are used at frequencies above 2 GHz, allowing reasonably sized structures. By 10 GHz, the size of waveguide approaches that of a large coaxial cable. Waveguide is most often found in rigid sections, straight or angled, and interconnected by flanges. Some semi flexible waveguide is available, making it almost as easy-to-handle as semirigid coax.



Fig 24-1 — Open-wire transmission line with λ/4 shorted stub.

Horn Antennas

A number of popular microwave antennas follow directly from the use of waveguide, although they are not restricted to waveguide use. The first I shall discuss is the *horn* antenna. The horn antenna, in its simplest form, is just a waveguide opened up on the end to let a wave propagating in the waveguide escape and become a wave propagating in space.

The horn antenna is essentially a flared out section of waveguide, in one or both dimensions. By gradually expanding the dimensions, the field can be smoothly transitioned into a plane wave with a larger aperture, providing defined directivity in either or both axis. For usual waveguide modes, the electric-field vector is across the narrow direction, roughly correlating to the voltage across a transmission line model, as seen in Fig 24-1 and **Fig 24-2**, with the magnetic-field vector in the direction aligned to the larger dimension of the waveguide, and the electric field vector perpendicular and across the narrow dimension, as shown in **Fig 24-3**. Thus, either vertical or horizontal polarization can be selected, merely by orienting the waveguide section before the transition to the horn.



Fig 24-2 — Open-wire transmission line with multiple λ/4 shorted stubs.

Rectangula cross-section waveguides transition naturally to rectangular or pyramidal horns, while circular or elliptical waveguides more naturally feed into cylindrical or oval-shaped horns. While waveguide feed of horns is a natural fit, horns can be transitioned from coaxial cable through a very short section of closed waveguide with a coax-to-waveguide coupling section.

Horn Dimensions

The key dimensions of a rectangular horn are the length (L) and aperture size (A_E and A_H). These are shown in **Fig 24-3**. For a circular horn, the corresponding aperture dimension is the common diameter (D). The dimensions are related in that for a given aperture (and hence beamwidth and gain), there is an optimum horn length that provides uniform illumination to allow the effective use of that aperture. The relationships are defined in **Table 24-1.**[1]

The resulting gain of the horn follows from the directivity and is approximately given by:

$$\text{Gain (dBi)} = 10\log_{10}(7.5 \times A_E A_H) \qquad \text{(Eq 1)}$$



Fig 24-3 — View of rectangular horn antenna terminating a waveguide.

Horn Applications

The horn can be, and often is, used directly as an antenna. Perhaps more commonly, however, it can be placed at the focus of a parabolic-dish reflector and used to drive a higher-gain system. Through the adjustment of the above parameters, the horn can provide uniform illumination of the dish with minimal waste of dish aperture, or of power being wasted by illuminating area outside the dish. In addition, the dish offers almost infinite front-to-back ratio, reducing extraneous responses in undesired directions.

Table 24-1

Beamwidth of Horn Antenna as a Function of Key Dimensions (λ)

Aperture	*Beam Width (degrees)*	
	Between First Nulls	*Between 3-dB Points*
Length for uniform illumination	115/L	51/L
Rectangular horn E-plane	115/L	$56/A_E$
Rectangular horn H-plane	172/L	$67/A_H$
Circular horn	140/L	58/D

Slot Antennas

The *slot antenna* is an interesting configuration that truly requires "thinking outside the box"! **Fig 24-4** shows a pair of λ/4 shorted stubs, used previously to describe a waveguide. In this example, however, they are fed at the center. This won't make a very good antenna because the currents on opposite sides are out-of-phase, equal and so close that radiation is essentially cancelled. If you take this case and turn it inside out by cutting a λ/4 slot in a sheet of metal, the currents will flow as shown in **Fig 24-5**, migrating from the immediate area of the slot. The result is an efficient radiating structure that can be used as an antenna. The radiation will be bidirectional towards both sides of the sheet and will be vertically polarized if oriented as shown. The impedance at the center is about 500 Ω. By feeding it about λ/20 from one end of the slot, a good match to 50 Ω coaxial cable can be obtained.

A slot can also be fed directly by a waveguide. By merely attaching a flat plate, typically a minimum of 3λ/4 wide and λ/2 high with a slot matching the waveguide opening, you have a form of unidirectional slot. It will radiate fairly uniformly across the hemisphere on the open side. Unfortunately, my antenna modeling tools only work with wire antennas, so I don't have the capability to provide the usual modeled results for these antennas.

A unidirectional slot antenna can also be made by putting an empty box behind the opening with a depth of about λ/4. This could also be considered a λ/4 shorted-waveguide stub and can serve as a very nice reflector. The applications for metal vehicle bodies should be apparent, especially since the slot need not be air, but could be some kind of dielectric structure to avoid turbulence.

To obtain additional directivity, multiple slots can be spaced and oriented just as the linear phased arrays discussed for HF. A multiple-aperture slot array can also be constructed by putting multiple slots in the appropriate places on the surface of a waveguide.



Fig 24-4—Two λ/4 shorted stubs in parallel, fed as an antenna.



Fig 24-5— Slot-antenna configuration.

The Patch Antenna

An interesting structure is called the *patch antenna*. It is constructed from a simple rectangle of metal, λ/2 on a side, suspended over a metal ground plane. This is shown in **Fig 24-6**. The coaxial feed is connected inward from the center of an edge at a point that matches the coaxial-cable impedance, with the shield just below on the ground plate. Current flows across the patch radiating in a direction perpendicular to the plate. The pattern and gain are similar to a pair of in-phase dipoles, spaced λ/2, positioned in front of a reflector. The resulting gain is about 8 dBi with a 3 dB beamwidth of about 60°. If the ground plane were infinite in extent, the front-to-back ratio would also be infinite. With a small ground plane, somewhat larger than the patch, the F/B will be about as with a Yagi.



Fig 24-6 — Construction of a patch antenna over a finite ground plate. The radiation is perpendicular to patch.

The patch is a versatile antenna that can be found in a number of applications. Its ease of construction and predictable response make it popular as a feed antenna for home-made dish antenna systems. It can also be easily fabricated on double-sided printed circuit board, although the dielectric material will result in some changes in performance and resonance. If fed directly on the edge, strip-line transmission-line sections can be easily etched at the same time to result in a match to whatever the system designer needs as a load.

Chapter Summary

At frequency ranges with small wavelengths, different antenna structures are possible than at the lower frequencies where I've spent most time in this book. Keep in mind, though, there is nothing directly related to frequency associated with these structures and they could be built for lower frequencies as well if there were particular requirements for them.

Notes

1,2 J. Kraus, *Antennas*, second edition, McGraw-Hill Book Company, New York, 1988, pp 651-653.

Review Questions

24-1. What is it about microwave antennas that make them different than antennas for lower frequencies?

24-2. Why are long coaxial cable runs not often encountered at microwave frequencies?

24-3. What are the relative advantages of patch and horn antennas as feed systems for dish antennas?

Chapter 25

Vehicle Antennas



There's almost no limit to the antennas you can support from some vehicles.

Contents

Vehicle Antennas 25-2

Land Operating Motor Vehicles 25-2

Water Borne Vehicles 25-5

Aircraft Antennas 25-6

Chapter Summary 25-7

Review Questions 25-7

Vehicle Antennas

Most of the antennas I have covered so far have been developed assuming that they were mounted some distance from the ground and thus were pretty much alone in their environment. This works well for antennas suspended a distance above ground from halyards or on a structural support such as a tower. There is another category that shares some of the previous characteristics, but that brings special challenges — antennas mounted on vehicles.

In this context, by vehicles I mean land-operating motor vehicles, aircraft and water-borne vessels. Each may need to be equipped with radio communication or radionavigation systems, and each brings its own set of challenges.

Land-Operating Motor Vehicles

We often take for granted the telecommunications capabilities of modern motor vehicles. Many have receive capability at MF (AM broadcast), VHF (FM broadcast) and UHF (satellite-based GPS navigation) as well as UHF two-way communication for cellular telephone, or specialized service programs (On-Star). In addition, most public service and utility vehicles provide dedicated two-way VHF or UHF radiotelephone and often data systems. There are also some two-way mobile HF systems in common use, principally by Amateur Radio operators and military vehicles. It's amazing that among these, only the occasional Amateur Radio operator's vehicle looks a bit like a porcupine or a fishing trawler!

Receive-Only Antennas

MF receive antennas go back in time to just after it became possible to make compact AM broadcast receivers that could fit into car dashboards. The typical antenna is a short vertical monopole, much shorter than λ/4. While a full-size λ/4 monopole would be quite a good performer at 550 kHz, the bottom of the AM broadcast band, it would be about 425 feet tall. This would be a mechanical challenge, not to mention the problems associated with going through the drive-through lane of your bank!

The typical antenna is a rod 3 or 4 feet high. It receives a much smaller amount of the usual broadcast ground-wave signal than a full-sized antenna, but because the SNR is limited by external noise, the signal is strong enough to provide usable reception. An MF automotive receiver generally has additional RF amplification compared to a home radio, to bring the received signal above that generated within the receiver.

VHF-FM broadcast reception is much more straightforward. The FM broadcast band extends from 88 to 108 MHz in the US. At 100 MHz, λ/4 is just 1.5 meters or about 59 inches long, not much longer than the length of the shortened MF monopole. With the ground side connected to the vehicle body at the base of the antenna, it can be easily matched to the input of the receiver. The reception will be fine for line-of-sight (LOS) paths to transmitters, and broadcast transmitters are generally well elevated to account for low receive antennas.

Reception of GPS satellite signals adds a new dimension to the vehicle problem. In the previous cases, I have discussed reception from transmitters sending signals at low angles of arrival — from LOS or ground-wave paths. Whatever we expect from satellites, it won't likely be restricted to low-angle reception.



Fig 25-1 — Elevation pattern of 1-GHz λ/4 monopole on vehicle.



Fig 25-2 — Elevation pattern of 1-GHz λ/4 bent monopole or inverted L on vehicle.

The elevation pattern of a λ/4 monopole over a near perfect ground, such as a metal vehicle roof at UHF, is shown in **Fig 25-1**. It clearly will be much better at reaching low-angle cellular towers than high-angle satellites for GPS or satellite-radio use. By bending about ⅔ of the vertical portion over to become horizontal, you form an antenna that would be called an *inverted L* in the MF and HF region.

The resulting elevation plot is shown in **Fig 25-2**. Note that while the low-angle response is only down



Fig 25-3 — Azimuth pattern of 1-GHz λ/4 inverted L at 15° elevation angle.



Fig 25-4 — Azimuth pattern of 1-GHz λ/4 inverted L at 60° elevation angle.

about 1 dB, the high-angle response is significantly increased. Lest you wonder about the azimuth coverage, low- and high-angle plots are shown in **Fig 25-3** and **Fig 25-4**. These show that the uniform response is maintained. The SWR of the antenna at 1000 MHz is shown in **Fig 25-5**. It is moderately sharp, but could easily be adjusted for either GPS operation at 1575 MHz or cellular coverage at either 860 or 1900 MHz.

An improvement of this approach is the popular wideband *blade* antenna. This is an adaptation of the slot antenna described in Chapter 24, and will be discussed further in the aircraft section that follows. The blade antenna can cover the entire range and looks a bit like a small dorsal fin on the back of many recent sedans.

Two-Way Radio Antennas for Motor Vehicles

Antennas for effective transmission and reception from motor vehicles divide nicely by the portion of the radio spectrum into which they fall. In the VHF and UHF ranges, the most common antenna is a vertical monopole. It provides the omnidirectional coverage sought by most vehicle systems. Such an antenna is quite efficient, since the size of the typical vehicle body makes for a good ground system under the antenna. Typical lengths range from λ/4 to 5λ/8, with the longer sizes used mainly at higher frequencies where the physical length is still reasonable.

The major limitation of such systems is that they are essentially limited to line-of-sight paths, and those generally provide limited range between land vehicles. Most VHF/UHF systems operate between a base station with an elevated antenna and multiple mobile units, or via remote repeater stations in high terrain that can "see" all mobile units over a wide geographical extent and relay transmissions between them.

HF and even MF two-way mobile systems have been in use for a long time, in spite of the fact that efficient, reasonably sized antennas for that frequency range are hard to come by. Before municipal police departments moved into the VHF range somewhat after WW II, they used MF frequencies just above the broadcast band for communications between headquarters and mobile units.



Fig 25-5 — SWR plot of 1-GHz λ/4 inverted L.

The challenge with HF mobile operation is that the same λ/4 monopoles that work well at VHF are much bigger at HF. At the top of the HF range, 30 MHz, a λ/4 monopole is about 8 feet long, and it appears often as a stainless steel flexible *whip* antenna operated against the vehicle body as a ground. The US citizen's band (CB) at 27 MHz is just at the edge of practicality with full-size antennas 9 feet long, frequently seen mounted on trucks.



Fig 25-6 — HF whip antenna, with loading coil mounted on auto fender.

For lower-frequency HF operation, electrically short antennas are usually used. It's necessary to compensate for the shorter length in some manner. The choices are to have a whip antenna with a matching network beneath the vehicle body, or to electrically lengthen the monopole by *loading* it. This term, borrowed from telephone company line-compensating parlance, means substituting an inductor for part of the antenna length to provide a resonant antenna that is physically shorter than λ/4. The *loading* inductance can be mounted at the base or somewhere in the whip itself and is sometimes used in combination with a capacitance at the top. A loaded mobile antenna is shown in **Fig 25-6**, with its *EZNEC*



Fig 25-7 — *EZNEC* model of motor vehicle with antenna on front fender.

model, borrowed from a *QST* article. This model includes the car body itself acting as a grounding system, as shown in **Fig 25-7**.[1]

If a matching network is used, the requirements on the matching network are rather extreme. For example, an 8 foot whip antenna has an impedance at its base at 3.85 MHz of about 3.25 – *j* 2395 Ω. If you use a matching network with an inductor whose Q is 100, you would have losses in excess of 15 dB within the matching network itself. The loaded antenna, including such a matching network, will have similar losses.

It's interesting to look at the modeled results of various configuration of HF mobile antennas. **Fig 25-8** shows the elevation pattern for three cases. The first case (solid line) is a full-size monopole adjusted to be resonant at 3.85 MHz. While this is not too useful in a practical sense, it does indicate an upper efficiency limit. Next, insert an ideal, no-loss, loading inductor at the center of the 8 foot whip (dashed line), and finally use one with a realizable Q of 100 (dotted line). The maximum signal intensity is summarized in **Table 25-1**.

Another result of the losses in the real inductor is shown in the SWR plots of the two loaded cases in **Fig 25-9** and **Fig 25-10**. Note that the ideal inductor results in a low resistive feed-point impedance at resonance and a very narrow bandwidth, narrower even than some modulation schemes. The low resistance requires additional matching elements, usually a shunt inductor at the base, in order to provide a matched feed to coax. By using a lossy real inductor, both problems disappear — along with about an additional 90% of the radiated power!

The 3.85 MHz example here is about the worst case for HF mobile antennas. At the other end of the HF range, 30 MHz, the 8 foot whip is a full-sized λ/4 monopole with performance comparable to a ground mounted antenna. Frequencies in-between perform in-between the two extreme cases, as you would expect, with antennas around half of full size (around 15 MHz for an 8 foot whip) not giving up much performance compared to full-sized antennas, as shown in **Table 25-2**.

Table 25-1

Transmitted Signal Intensity of Three 3.85-MHz Mobile Antenna Configurations.

Configuration	*Signal Intensity (dBi)*
Full size monopole	–1.24
Loaded 8 foot, ideal inductor	–5.85
Loaded 8 foot, real inductor	–15.36



Fig 25-8 — Response of a full-sized λ/4 monopole (solid line) on vehicle, compared with an 8-foot whip using lossless center-loaded inductor (dashed line) and an 8-foot whip with a real inductor with a Q of 100 (dotted line).



Fig 25-9 — 6.5 Ω SWR plot of 3.85 MHz center loaded antenna with lossless loading inductor.



Fig 25-10 — 58 Ω SWR plot of 3.85 MHz center loaded antenna with real world loading inductor.

Table 25-2

Transmitted Signal Intensity of 8 Foot Center Loaded Mobile Antenna Compared to Full Size at Selected Frequencies.

Frequency	*Full Size Height (feet)*	*Full Size Intensity (dBi)*	*8-Foot Signal Intensity (dBi)*	*Penalty (dB)*
3.8 MHz	68.6	−1.24	−15.36	14.1
7.15 MHz	35.6	−1.21	−8.22	7.0
14.15 MHz	17.1	−0.2	−2.09	1.9
21.2 MHz	11.3	0	−.71	0.7
28.3 MHz	8.4	0.56	0.45	0.1

Water Borne Vehicles

Water borne vehicles often use technology for their antenna systems similar to that of land vehicles; however, they have a few significant advantages:

- Salt-water vessels have an almost ideal ground structure beneath them, and often a metal hull that is tightly coupled to it.
- Many watercraft are much larger than land vehicles in all dimensions. They also often include masts and other structures that can support taller HF antennas as well as providing a higher view for VHF/UHF systems.
- While on open water, they have much longer LOS distances than land vehicles do in all but the most flat of terrains.

Aircraft Antennas

Aircraft clearly are on top of the heap when it comes to LOS distances. On the other hand, they offer some of the most severe constraints for the antenna designer due to requirements that they not have protrusions that increase air resistance.

Traditional Aircraft Antennas

Early and slower aircraft used many systems in common with other vehicles — wire antennas for HF and whips for VHF/UHF. Many still employ such systems — a short mast forward on the fuselage secures one end of a wire that terminates on an insulator at the top of the tail's vertical stabilizer. This provides reasonable MF and HF coverage, if combined with a matching network inside the fuselage. Some slow-moving strategic communications platforms have even used vertically trailing wire antennas thousands of feet long to provide long range LF or MF communications.

Short VHF and UHF monopoles, constructed of thin wire have often been used on low to medium performance aircraft. If mounted below the fuselage, they provide coverage to a wide area.

Antennas for High-Performance Aircraft

High-performance aircraft provide a completely different perspective compared to their lumbering counterparts. In an aircraft world in which a rivet head is a no-no, any kind of protrusion is generally rejected. Fortunately, there are configurations that make use of slots, patches or other technology to allow a fully streamlined configuration. Such antennas are not generally added to the airframe, but are designed into the skin of the fuselage as a part of the system-design process. I will discuss a few of the many solutions in current use.

Slot antennas are an ideal example of such a configuration. A slot in the skin of the fuselage can be driven by a waveguide from inside, or be backed by a box and coax fed, with the slot covered in insulating material with absolutely no indication from the outside that it is there — other than perhaps a "no step" admonition.

A variation of the slot is the *blade* antenna. In this case, rather than attempting to approximate an infinite ground sheet, specific tapered dimensions and offsets are used to provide coverage over a wide band of frequencies. This configuration is shown in **Fig 25-11**.



Fig 25-11 — Slot driven aircraft blade antenna.

A vertical monopole with no height, at least from the perspective of drag, can be constructed using a flush disk as a capacitive loading element as shown in **Fig 25-12**. Again, with nonconductive material between the outside of the disk and the circular hole in the fuselage, the aircraft surface streamlining can be maintained. This antenna provides omnidirectional coverage with vertical polarization.



Fig 25-12 — Side view of flush disk antenna.

Some antennas, such as rotating radar dish antennas, are more difficult to streamline. While many aircraft that have extra space, place traditional dishes behind radomes that correspond to the shape of the aircraft, the more modern approach is to synthesize the beam shapes by using multiple slot or other streamlined antennas in phased arrays with the phase controlled by computer systems to determine the desired beam positioning.

Chapter Summary

Antennas for use on vehicles are just adaptations of the same principles as antennas I have discussed previously. What makes vehicle antennas special is that they add additional constraints in terms of size — particularly height for land vehicles or air resistance for aircraft. The result is often a compromise between practicality and performance. Often the performance can be compensated for at the other end of the link, through higher antennas, additional power or sensitivity or special signal processing. Fortunately, there is usually a configuration that can be made to fit almost any application.

Notes

[1] S. Cerwin, "The Arch," *QST*, Jan 2008, pp 39-41.

Review Questions

25-1. What performance limitation makes MF vehicle receiving antennas easier to design than many others?

25-2. If heights as high as 12 feet can be accommodated by highway underpasses, what is the approximate lowest frequency that can use a full sized $\lambda/4$ monopole on a vehicle if the base of the monopole is mounted 2 feet above the roadway?

25-3. Why are slot, blade and disc antennas particularly suited for high-performance aircraft?

Chapter 26

Antenna Measurements



This homemade field strength meter can be used to map the response of transmitting antennas in different locations or directions.

Contents

Antenna Measurements 26-2

Measurement System Limitations 26-2

RF Voltage and Current 26-2

Standing Wave Ratio 26-3

Measuring SWR 26-3

Field Strength 26-6

Chapter Summary 26-8

Review Questions 26-8

Antenna Measurements

Measuring antenna characteristics and performance are important considerations in any antenna application or development project. Modeling is often much easier, quicker and better defined; however, there are always assumptions and limitations within the modeling process that can be best validated through actual physical measurements.

Measurement System Limitations

Unfortunately, it is not just modeling that has assumptions and limitations; measurements do as well. It is important to understand what some of these limitations are to be able to make valid judgments and draw appropriate conclusions from measured data. I will try to discuss these as I describe some of the various measurements that can be taken.

RF Voltage and Current

It is relatively straightforward to measure RF voltage, at least at relatively low frequencies. A series resistor, at least 100 times the value of the line Z_0 is connected to the line under load to minimize change to the conditions we are trying to measure. The resultant signal is rectified by a semiconductor diode, filtered and presented to a meter. A circuit of such a meter that can be built in a small metal box and placed in the line is shown in **Fig 26-1.**[1] It is also possible to build the components into a cigar tube with the resistor lead protruding and use it as an RF probe using a usual test meter as an indicator. Note that R1 and R2 must be *composition* resistors, not the more commonly used film type, which act more like inductors than resistors at radio frequencies.



Fig 26-1 — Schematic diagram and parts list for an RF voltmeter for coaxial line. (Courtesy *The ARRL Antenna Book.*)

C1, C2 — 0.005 or 0.01 µF ceramic capacitor.
D1 — Germanium diode, type 1N34A or equivalent.
J1, J2 — Chassis mount coaxial sockets to match connectors in use.
M1 — Milliammeter, 0-1 mA or more sensitive.
R1 — 6.8 k Ω composition resistor. 1 W for each 100 W of RF through device.
R2 — 680 Ω, 1 W composition resistor.
R3 — 10 k Ω, ½ W composition or film resistor.

The values of the components are shown in Fig 26-1 and are designed to make the meter read fairly linearly with RF voltage. You should establish reference points using a power or voltage meter of known accuracy for initial calibration of the voltmeter.

RF current can also be measured, by simply measuring the voltage across a small resistor in series with the line. To avoid changing the system SWR, the resistor should be both noninductive and it should have a value much less than that of the Z_0 of the line being measured. Note that in this case, both sides of the measurement system are at high RF potential with respect to the chassis of the metering circuit.

A type of RF ammeter called a *thermocouple* meter was in common use during WW II and samples are still frequently found. This meter, useful only through the HF region, uses a thermocouple, a device that converts temperature rise to voltage, to measure the RF current going through a resistance that is part of the thermocouple assembly. These types of RF ammeters are not commonly available as new products.

Standing Wave Ratio

Standing wave ratio (SWR) is one of the more straightforward measurements to make on an antenna system. SWR is a measure of how well the antenna, as a system load, matches the nominal system impedance. The usual way of measuring SWR is to separate the two waves that appear on a mismatched transmission line — the *incident* wave and the *reflected* wave. The incident wave represents the wave travelling from the signal source, which is usually a transmitter, towards the load, which is often an antenna. If the load impedance does not match the transmission-line characteristic impedance (Z_0), some fraction of the incident wave will be reflected back towards the transmitter. The power actually delivered to the load equals the difference so that $P_D = P_F - P_R$.

A common misconception is that the P_R term implies "lost power" in the system. Power can be lowered if the system cannot accommodate the actual load impedance seen at the transmitter. If the transmitter can perform properly, however, and if there are no other losses in the system, the reflected power is re-reflected at the source and heads back up the transmission line toward the load again. Of course, a real system cannot be totally lossless, and the losses do increase with SWR. Still if the transmitter can drive the resulting impedance seen at its output when there is an SWR, most of the power will reach the load.

Measuring SWR

The Direct Method

Incident and reflected waves will both exist along the length of the transmission line if there is SWR on that line. At any given point, a measurement of the voltage across the line will show the algebraic sum of the voltage from each wave. If there is no reflected wave (indicating a perfect match), the voltage for a lossless line will be constant along its length. On the other hand, if there is a reflected wave, it will add and subtract from the voltage of the incident wave as they propagate along the line. A direct measurement of voltage can be taken using a meter of the type shown in Fig 26-1. The SWR is defined as being equal to the ratio of the maximum voltage over the minimum voltage. Again, if there is no reflected wave, the voltage will be the same everywhere and the SWR will be 1:1.

To be sure that you have captured the extreme maximum and minimum values, you must take samples along a length equal to at least $\lambda/2$. This direct measurement requires that a non-loading voltage measurement, such as that just described, be made along the whole length. The object is to find the peak and minimum voltages, since their location will be a function of the phase angle of the load impedance. This method can be employed only if voltage sample points are available all along the line. This is not possible with regular coaxial cable, but is feasible with bare open wire line — if you can measure it without disturbing the values you are trying to measure.

At the high VHF to microwave range, it is possible to insert a section of *slotted line* into the system. A slotted line is just a precision rigid section of air-dielectric coaxial cable that has a slot through the shield, through which a voltage-measuring probe can be inserted. If the probe has a high impedance compared to the line Z_0, an accurate measure of the line voltage can be made at each point along the length of slot. If the slot is at least $\lambda/2$ long, the SWR can be determined directly from the ratio of maximum and minimum voltage readings.

While a slotted line (or even neon bulbs along HF open-wire line) can be used to measure SWR (or in the case of the neon bulbs to get a sense of the magnitude of SWR), the technique is no longer commonly used — except perhaps to demonstrate the concept in school laboratories. The most common method is to measure the forward and reflected power and compute SWR from those values.

SWR by Measuring Forward and Reflected Power

If a relatively short, in terms of wavelength, section of sampling transmission line is coupled to the main transmission line, inside the shield in the case of coax, a sample of the power going in either direction can be obtained. In **Fig 26-2**, a small sample (typically down 20 dB) of the signal in the main transmission line is obtained on the sampling line, which is terminated in a resistance at the far end. Reflected signals, returning from the output side of the main transmission line, are also coupled to the sampling line and go to the diode rectifier, which sends dc to a meter. With proper calibration, the reflected power can be read from the meter. Some systems have two sensors, one in each direction, so that forward and reflected power can be read simultaneously — others have a single sensor with metering circuit and the coupling loop is reversed to measure the power in the other direction. The



Fig 26-2 — Example of directional coupler used for measuring relative forward or reflected power.

coupling is a function of the fractional wavelength of the coupling line, so calibration is a function of frequency.

The forward and reflected powers do not show SWR directly, although some metering systems have scales calibrated to read directly in SWR. In most cases, the two power readings are noted and a calculation is made to determine SWR. This is easiest if done in two steps. The first step is to determine the magnitude of the reflection coefficient ρ. While the reflection coefficient is a complex quantity, the phase information is not needed here so you will just consider the magnitude of the quantity. This value is found as follows:

$$|\rho| = \sqrt{P_R / P_F} \qquad \text{(Eq 1)}$$

The SWR is then found as follows:

$$\text{SWR} = \frac{1+|\rho|}{1-|\rho|} = \frac{1+\sqrt{P_R / P_F}}{1-\sqrt{P_R / P_F}} \qquad \text{(Eq 2)}$$

This allows us to easily convert from forward and reflected power in watts or other units to SWR.

SWR Measurement Pitfalls and How to Avoid Them

SWR seems like a very straightforward item to measure; however, you are faced with a bit of a quandary. To perform the most accurate measurement, you need to measure at the load itself, which is usually an antenna. Placing measuring equipment, and even worse measuring people, at the antenna's feed point will probably result in a change in the impedance and thus the SWR. In addition, in many antenna installations, the antenna's feed point is at the top of a tall support structure — often not the best spot from which to be taking measurements.

The usual remedy for both problems is to measure the SWR at the bottom of the feed line. That's usually where the transmitter is and that's the part of the system that usually cares most about the SWR, so it seems like a best place to take the data. It can be, but it can also lead to errors in conclusions. If the line is lossless, the SWR at the bottom will equal that at the top. Unfortunately, real-world transmission line has losses, and the losses increase with SWR. Thus an SWR measurement at the bottom compares the full forward power with the attenuated reflection of the attenuated forward power that reaches the antenna.

Here's an example. Let's say you have a 100 W transmitter driving 100 feet of coax that has a loss of 3 dB (50% power loss) at some particular frequency. The antenna will see 50 W of power. But let's say 20% of the power is reflected due to the antenna being mismatched to the Z_0 of the transmission line. That will result in 10 W being reflected back toward the source. The 3 dB loss in the line results in 5 W showing up as reflected power at the transmitter at the bottom of the line.

Table 26-1 summarizes the power at the two locations. Note the rather distressing result. A very acceptable measurement of an SWR of 1.6:1 at the bottom of the coax is the result of an unpleasant SWR of 4:1 at the antenna. In this example, our 100 W of power results in only 40 W radiated from the antenna — yet all of our measurements make us think we're doing well. Unfortunately, this example is not unusual, especially at the upper end of HF into the VHF range. If it happens at higher frequencies, it is usually more evident since nothing much ends up going in or out of the system! The sidebar discusses ways that this can be calculated, and perhaps avoided, through the use of software.[2]

Another problem that can confuse SWR measurements is if there are any stray common-mode currents present, such as those on the outside of the coax shield. This makes the transmission system a complex one, while the SWR instrumentation is happily measuring what is happening inside the coax, it only has a view into part of the total system. Thus, results are not accurate.

You can sometimes determine whether you have common-mode problems by observing the SWR as you move your hands along the outside of the coax. If everything is working as designed, there should be no change. However, if readings do change, stop taking the measurements — they will not be particularly meaningful. You will have to use appropriate measures, such as adding common-mode chokes or current baluns, to force currents to flow only on the inside of the coax, not on the outside of the coax's shield.

Table 26-1

Forward and Reflected Power as Seen at Each End of the Transmission Line

Measurement	*Bottom of Cable*	*Top of Cable*
Forward Power (W)	100	50
Reflected Power (W)	5	10
Indicated Reflection Coefficient	0.224	0.447
Indicated SWR	1.6	4.0

I Know What's Happening at the Shack — What's Happening at the Other End of my Feed Line?

If you want to find out — here's the easy way using TLW.

Joel R. Hallas, W1ZR
Technical Editor, QST

I'm told that one of the more frequent questions received by *QST*'s "Doctor" has to do with folks wanting to determine the impact of transmission line losses on the effectiveness of their antenna system. These questions are often along the lines of "I measure an SWR of 2.5:1 at the transmitter end of 135 feet of RG-8X coaxial cable. My transceiver's auto-tuner can tune it to 1:1, but how can I tell what my losses are?" or "How much difference will I have if I have a tuner at the antenna instead of using the built-in tuner?"

These are important questions that almost every amateur operator is faced with from time to time. An approximate answer can be obtained by using the graphs found in any recent edition of The ARRL Antenna Book showing the loss characteristics of many transmission line types, plus adding in the effect of an SWR greater than 1:1. The SWR at the antenna end can be determined from the bottom end SWR and the cable loss. Using these graphs requires a bit of interpolation or Kentucky windage, but can result in useful data.

But There's an Even Better Way!

Packaged with each of the last few editions of *The ARRL Antenna Book* is a CD containing the pages of the whole Antenna Book as well as some very useful software. The program that I use almost daily is one written by Antenna Book Editor R. Dean Straw, N6BV, called *TLW* for Transmission Line for Windows.

TLW provides a very easy to operate mechanism to determine everything I usually need to know about what's happening on a transmission line. When you open the program, you are presented with a screen as shown in Figure 1. This has the values plugged in from the last time you used it, often saving a step. Let's take a quick tour of the inputs:

Cable Type — This allows you to select the cable you would like to analyze. A drop-down box provides for the selection of one of 32 of the most common types of coax and balanced lines. An additional entry is provided for User Defined Transmission Lines that can be specified by propagation velocity and attenuation.

Length — In feet or meters, your choice.



Figure 1 — The opening screen of *TLW*, illustrating the process described in the article.

Frequency — This is an important parameter when dealing with transmission line effects.

Source — This defines the form of the input impedance data. Generally, you can use NORMAL.

Impedance — The impedance can be specified as what you measure, resistive (real) and reactive (imaginary, minus means capacitive). This could come from your antenna analyzer at either end of the transmission line. Note, if you only know the SWR, not the actual impedance, all is not lost — see below.

Now for the Outputs

SWR — The SWR is provided at each end of the cable. This is an important difference that many people miss, important even with a moderate SWR at the transmitter end, as we'll see — the SWR at the antenna will be much higher due to the cable loss. With TLW, you instantly know the SWR at both ends, and the loss in the cable itself.

Rho at Load — This is the reflection coefficient, the fraction of the power reflected back from the load.

Additional Loss Due to SWR — This is one of the answers we were after.

Total Loss — And this is the other, the total loss in the line, including that caused by the mismatch.

But Doctor, What if I can OnlyMeasure the SWR —

Not the Actual Impedance?

Often the only measurement data available is the SWR at the transmitter end of the cable. Because the losses are a function of the SWR, not the particular impedance, you can just put in an arbitrary impedance with that same SWR and click the INPUT button. An easy arbitrary impedance to use is just the SWR times the Z_0 of the cable, usually 50 Ω. For example, you could use a resistance of 125 Ω to represent an SWR of 2.5:1. This is what we've done in Figure 1, using 135 feet of popular Belden RG-8X.

The results are interesting. Note that the 2.5:1 SWR as seen at the radio on 28.5 MHz results from a 7.45:1 SWR at the antenna — perhaps this is an eye-opener! Note that of the 5.6 dB loss, more than half, or 3.1 dB, is due to the mismatch. Note that if we used something other the actual measured impedance, we can't make use of the impedance data that TLW provides. We can use the SWR and loss data, however, but that's probably what we wanted to find out.

We can now do some "what ifs." We can see how much loss we have on other bands by just changing the frequency. For example, on 80 meters, with the same 2.5:1 at the transmitter end, the SWR at the antenna is about 3:1 and the loss is slightly more than 1 dB. We could also plug in an impedance calculated at the antenna end and see what difference other cable types would make. For example, with the same 28.5 MHz SWR of 7.45 at the antenna and 135 feet of 1/2 inch Andrew Heliax, we will have a total loss of 1.5 dB at 28.5 MHz. Note that the SWR seen at the bottom will now be 5.5:1 and our radio's auto-tuner might not be able to match the new load.

But Wait There's More!

You can also click the GRAPH button and get a plot of either voltage and current or resistance and reactance along the cable. Note that these will only be useful if we have started with actual impedance, rather than SWR.

Pushing the TUNER button results in a page asking you to select some specifications for your tuner parts. TLW effectively designs a tuner of the type you asked for at the shack end of the cable. It also calculates the power lost in the tuner and gives a summary of the transmitted and lost power in watts, so you don't need to calculate it!

When you've finished, be sure to hit the EXIT button, don't just close the window. Otherwise TLW may not start properly the next time you want to use it.

Field strength is a quantity that is easy to measure, but that can be difficult to interpret. A basic field-strength meter (FSM) can be as simple as an untuned crystal radio receiver with a short antenna connected to a meter movement, as shown in **Fig 26-3**.

For most antennas, the long-range performance is what you'd like to measure. For a multielement array that exhibits a good deal of gain, such as a long-boom Yagi, the field-strength meter must be physically far away from the array, well into the *far field*. The far field boundary is a function of the size and complexity of the array, as well as the wavelength. The distance to the boundary, R, can be approximated by the following:

$$R = \frac{2L^2}{\lambda} \qquad \text{(Eq 3)}$$

where L is the largest antenna dimension, and λ is the operating wavelength, all in the same units. This expression is valid for $L > \lambda$. Note that for the case of a 1λ boom Yagi, $L = \lambda$, and Eq 2 reduces to:
$R = 2\lambda$.

Making Field-Strength Measurements

A meter such as the one in Fig 26-3 can be used to provide a relative indication of field strength. There are difficulties associated with attempting absolute measurements. For example, a field-strength meter can be a good tuning aid to determine antenna, transmission line or transmitter settings that provide maximum signal strength to a particular location, or to adjust phasing lines for a null in a specific direction. Since the scale is not necessarily linear, comparison between signals is best done with the meter at the same point and a variable attenuator or calibrated transmitter power setting used to achieve the same response.



Fig 26-4 — Elevation pattern of three element Yagi in Chapter 19, in free space.

In spite of a number of limitations and caveats with such devices, as well as the general field-strength issues to be discussed, there are useful measurements that can be obtained with such a simple device. For example, to measure an antenna's front-to-back ratio at the location of the FSM, first point the back of the antenna towards the FSM and adjust the power output for a solid reading. Turn off the transmitter and make sure the meter reads zero. Other transmitters in the area can make the use of an untuned FSM unusable!

Turn the transmitter back on and make note of the transmitter power. Turn the antenna so the front of the antenna is facing the FSM, with everything else the same. Reduce the transmitter power until the same reading is obtained and measure the power. The ratio of the recorded powers is the F/B.

Another approach to obtaining relative measurements is to use the antenna under test as a receiving antenna. In this case you use a nearby steady signal source, along with a stable receiver. Many receivers incorporate a signal-strength indicator. While some have calibrations indicating signal strength, few are accurate, as I've indicated before. If a calibrated signal generator is at hand, the meter indications, or possibly the automatic gain control (AGC) voltage can be used to directly compare signals for F/B or to make direct A-to-B comparison measurements.



Fig 26-3 — Schematic diagram and parts list for a simple RF field strength meter.
C1 — 0.005 or 0.01 µF ceramic capacitor.
D1 — Germanium diode, type 1N34A or equivalent.
M1 — Milliammeter, 0-1 mA or more sensitive.
R1 — Rheostat for setting meter sensitivity. Value should be about 100 times the meter resistance.
RFC — RF choke with at least 10 kΩ impedance at operating frequency. Alternately, a 10 kΩ or higher value composition resistor can be used.

If a calibrated step attenuator is available, an even better way is to take a reference reading on the weaker signal with the attenuator at 0 dB, and then click in attenuation until the stronger signal is reduced to the same reading. The value of the attenuator then is the same as the difference between readings.

Field-Strength Measurement Pitfalls and How to Avoid Them

The biggest challenge facing those

trying to evaluate antenna performance is generally separating the antenna from its environment. In this case, what this means is anything around the antenna that will modify its performance. The ground is often the biggest hurdle, however, nearby antennas, aerial cables and even metal rain gutters can all modify the way an antenna performs.

As an example, look at the 145 MHz Yagi examined in Chapter 19. There I examined the antenna in free space to avoid just the kind of problem being addressed here. The free-space elevation pattern is shown in **Fig 26-4**. This is the pattern associated with the antenna devoid of any external influences. Compare that to the pattern at a typical height of 40 feet above real ground shown in **Fig 26-5**. Note that the maximum gain has increased by a bit less than 6 dB due to ground reflections; however, the gain varies by as much as 20 dB as you make slight changes in elevation. Compounding this height effect is that the FSM antenna will also exhibit the same performance, just as any antenna will if it is mounted more than about λ/2 over ground.

In an antenna range, the usual practice is to adjust both the antenna under test and the sense antenna up and down to make sure each is at the peak of response. A reference antenna, such as a dipole, with a known gain, then replaces the antenna under test. The process is repeated for the dipole and then the gain difference between the two can be stated.

For this kind of measurement, it is also very useful to model the antenna beforehand to gain insight into how quickly performance changes with azimuth angle. This will demonstrate the resolution required in adjustments.

Some parameters are more sensitive to ground reflections than others. For example, **Fig 26-6** is the azimuth plot of the antenna over ground at the elevation angle of its first peak at 2°. **Fig 26-7** is the azimuth plot with the elevation set near the first null at 5°. Note that while the forward gain difference is more than 20 dB, both plots have a F/B of 31 dB, within a few tenths of a dB, suggesting that front-to-back measurements can be made with little concern about where the antenna is in the elevation pattern, a fact I implicitly took advantage of earlier.



Fig 26-5 — Elevation pattern of three element Yagi 40 feet above typical ground.



Fig 26-6 — Azimuth pattern of three element Yagi 40 feet above typical ground at 2° elevation.



Fig 26-7 — Azimuth pattern of three element Yagi 40 feet above typical ground at 5° elevation.

Chapter Summary

Many systems are available to measure antenna operation and performance; however, their effective use requires an understanding of how to separate the antenna from its environment. This is particularly critical for gain measurements, but can impact all types of measurements. It is also critical to understand what it is that is being measured and how measurements in one location can be properly or improperly used to determine what is happening.

Review Questions

26-1. How can current and voltage measurements be used to determine power on a transmission line? What precaution must be taken, particularly if the SWR is greater than 1:1 to make the calculation valid?

26-2. Under what conditions can't the SWR at the bottom of a transmission line be directly used to determine antenna SWR?

26-3. What are the limitations that affect the ability to use field-strength measurements for absolute gain determination?

Notes

[1] R. D. Straw, Editor, *The ARRL Antenna Book*, 21st Edition. Available from your ARRL dealer or the ARRL Bookstore, ARRL order no. 9876. Telephone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.org/shop/; pubsales@arrl.org.**

[2] J. Hallas, W1ZR, "I Know What's Happening at the Shack -- What's Happening at the Other End of my Feed Line?" *QST*, Feb 2007, p 63.

Appendix A

Getting Started in Antenna Modeling with EZNEC

Contents

Introduction A-2
Getting Your Feet Wet With *EZNEC* A-2
Using *EZNEC* to Model Some Sample Antennas A-3

Introduction

You may well wonder how someone can determine just how well and in which directions an antenna will radiate. This is an old problem traditionally settled using an *antenna range*, which consisted of a large open space with big towers and expensive measuring equipment so that the actual directivity and gain of an antenna could be determined.

Of course, there have always been theoretical methods to determine antenna performance, but these often couldn't take into account some important factors. Key elements often missing in theoretical analyses have been the effects of ground reflections and antenna interactions with other nearby objects, such as support structures, or vehicle structure for mobile, airborne or shipboard antennas. Fortunately, in our twenty-first century computer-oriented society, we have software tools that help us avoid the need to climb towers.

The radiation from an antenna can be modeled by dividing up the antenna into a number of segments, and then adding up the radiation from each of these individual segments as seen at a distnat point. The computer must take into account both magnitude and phase from each segment, and can determine the resultant as the energy combines at some distant location, at any desired angle with respect to the antenna.

Antenna-simulation programs make the assumption that individual segments are small enough so that the current leaving a segment is the same as the current entering it. Other structures, such as other antennas, guy wires or towers, not connected to the antenna itself can also be modeled, and the currents induced in them will be part of the overall calculation.

The resulting model can be an effective tool to predict how a particular antenna will function, without having to actually construct and then measure the way it works. As with any simulation, your mileage may vary, but under most circumstances modeling provides at least a good starting point.

EZNEC

One popular antenna-modeling program is named *EZNEC* (pronounced *easy-nec)*. The "NEC" part of the name comes from the core calculation engine, the *Numerical Electromagnetics Code*, a powerful antenna-analysis tool that forms the basis of a number of antenna analysis programs. The "EZ" part of the name comes from the fact that this *Windows* implementation is indeed easy to use. *EZNEC* is available from its developer, Roy Lewallen, W7EL at **www.eznec.com**. The program is available in a number of versions, including a free demo version with no time limit. The demo is restricted in size to 20 segments, enough to get a feel for simple

Getting Your Feet Wet With EZNEC

If you follow along in this Appendix, you will get an understanding of how to use *EZNEC* to model antennas and obtain results very quickly. It is important to note that as antennas get more complicated, or get close to the ground, a number of complications make accurate results more difficult to obtain. Look at the information on the *EZNEC* Web site, or at other sources such as **www.cebik.com**, to get a sense of the limits in modeling.

To use *EZNEC*, you might start out with a sample antenna definition (some are supplied with the program). Or you might decide to enter the physical dimensions of your antenna in X, Y and Z coordinates. You also must specify wire gauge or diameter and pick a segment quantity. As mentioned above, the free demo version has a limit of 20 segments, while the basic version has a limit of 500 segments. These values are all entered on the WIRES tab.

On the SOURCES tab you specify which wires will be connected to source(s), and the location where a source connection will go in terms of percentage distance from one end of a wire. Pick the type of ground you want from the GROUND tab choices. That's all it takes to model an antenna.

To calculate some results, you might select the SWR tab and give the program a range of frequencies over which to determine the antenna's impedance and SWR (the default is 50 Ω, but you may specify other impedances). Most folks will want to see a plot of their antenna's pattern. You may select azimuth or elevation plots on the PLOT TYPE tab, and then you would click on FF PLOT to see the results. It takes less time to do it than talk about it.

Of course, there are some refinements and details that make such modeling even more useful, but I expect you will find out about them as you need them. If you want to determine the effect of changing the length of a wire, you can adjust the dimensions in the WIRES tab and run the calculations again. If you want to find how your antenna works at another frequency, just type in another frequency in the FREQUENCY tab and click FF PLOT again.

Using EZNEC to Model Some Sample Antennas

I have put together some *EZNEC* models of a simple antenna to serve two purposes — first, to show how easy it is to use, and second to illustrate some antenna principles that we have discussed in an abstract way earlier.

A Dipole in Free Space

The first antenna I will model is a horizontal half-wave dipole in free space. I have picked a frequency of 10 MHz (a 30 meter wavelength). I will use the antenna configuration shown in **Fig A-1**. The WIRES entry table that I created is shown in **Fig A-2**.

Note that I have picked a particular length so that the antenna will be resonant at almost exactly 10.0 MHz. Exact resonance is not really necessary, but this does represent a half-wave resonant dipole. I selected a height (the Z coordinate) to be half a wavelength above ground. Note that for "free space" the ground height doesn't matter, but you must specify some height.

I selected AWG #14 wire copper wire for the material. I could have specified it as a wire size (with the # symbol) or put in a number indicating diameter in inches. It is possible to set the table up in metric or English units, by the way. I selected a number of segments (19) to fit within the free demo. The program will give a warning message if you select a number of segments that result in too small or large a segment length. Keeping in mind the 500 segment limit (20 for the free demo), one way to gauge the size is to temporarily double the number and see if the results change very much. If not, your original selection is likely to provide valid results.


End 1 Coordinates:
X, Y, Z = -23.9, 0, 49.2 Feet
X, Y, Z = 0, 0, 49.2 Feet
End 1 Coordinates:
X, Y, Z = -23.9, 0, 49.2 Feet
Wire 1, Source at 50% From End 1
Height, Z = 49.2 Feet
Ground
UBA0269

Fig A-1 — Physical configuration of modeled antenna.



Wires

No.	End 1				End 2				Diameter	Segs	Insulation		
	X (ft)	Y (ft)	Z (ft)	Conn	X (ft)	Y (ft)	Z (ft)	Conn	(in)		Diel C	Thk (in)	Loss Tan
1	-23.9	0	49.2		23.9	0	49.2		#14	19	1	0	0

Fig A-2 — *EZNEC* WIRES data entry screen.



Sources

No.	Specified Pos.		Actual Pos.		Rel Amplitude	Phase	Type
	Wire #	% From E1	% From E1	Seg	(V, A)	(deg)	
1	1	50	50	10	1	0	I

Fig A-3 — *EZNEC* SOURCES data entry screen.

Now you've got a model and the *EZNEC* main window should look like **Fig A-4**. By clicking the SWR button, you would bring up the screen in **Fig A-5** on which you can specify the range and resolution you would like for an SWR plot. **Fig A-6** shows the resulting plot of SWR around the resonant frequency. Note that by putting the cursor on the 10 MHz axis, the data shown is for 10 MHz. I could select any other frequency in the range. The readout starts out with the data at the low frequency limit.

Note also that I could use this window to "trim" the antenna to be resonant, with a reactance close to zero Ω. I would make the dimensions longer if the reactance were negative, and shorter if the reactance is positive. I can continue in this fashion until I got quite close to zero. Note also that my final length, 29.9 feet is close to resonance and that I could have gotten even closer by using more decimal places. Going beyond about 1/10 of a foot for an HF wire antenna is a level of precision that works in the model, but is not realistic for my real-world ruler and wire cutters. The message is that the model is fine as



30 Meter Dipole - Free Space

File 30M FS Dipole EZ
Frequency 10 MHz
Wavelength 98.3571 ft
Wires 1 Wire, 19 segments
Sources 1 Source
Loads 0 Loads
Trans Lines 0 Transmission Lines
Transformers 0 Transformers
L Networks 0 L Networks
Y Param Networks 0 Y Param Networks
Ground Type Free Space
Wire Loss Copper
Units Feet
Plot Type Elevation
Azimuth Bearing 0 Deg
Step Size 1 Deg
Ref Level 0 dBi
Alt SWR Z0 73 ohms
Desc Options
Gnd Wave Dist OFF

UBA0272

Fig A-4 — *EZNEC* main screen showing a summary of our model parameters.



Start Frequency (MHz) [illegible]
Stop Frequency (MHz) 10.2
Frequency Step (MHz) 0.05
☐ Read Frequencies From File

UBA0273

Fig A-5 — *EZNEC* SWR parameter entry screen.

far as it goes, but don't let it result in unattainable values!

If I were actually making an antenna like this (and I have many times), I would use the model as a guide and start with perhaps an extra 6 inches of antenna length on each side. I'd raise the antenna to its operating height temporarily, measure the SWR over the frequency range I wanted, lower the antenna and shorten the ends a little at a time until I achieved the results I wanted.

If you want to adjust your model to indicate the SWR at a different Z_0, you merely change the Alternate Z_0 on the main *EZNEC* window. For example, you might change to 73 Ω, the value that the antenna shows at resonance. The results would be shown in **Fig A-7**.

You could also use the model to predict the SWR over a wider frequency range. You just need to make another pass and change the SWR entry frequency limits. An example is shown in **Fig A-8**.

Note that this highlights the fact that most antenna types have multiple resonances, as seen at slightly above the third harmonic of the 10 MHz half-wave resonance at 30.5 MHz. Some antenna designs take advantage of this effect.

The antenna patterns of your dipole are shown below for azimuth (**Fig A-9**) and elevation (**Fig A-10**). Note that the length of the line from the center of the plot to the pattern at a particular angle shows the signal strength at that angle. In this case of a dipole in free space, the elevation pattern is uniform all the way around the antenna, meaning that the elevation pattern is "omnidirectional."

The azimuth pattern shown is typical of what we would expect of a dipole — maximum radiation broadside to the antenna and no radiation from the ends. As expected, the maximum broadside radiation is about 2 dBi, 2 dB above an isotropic antenna.

Down to Earth — the Dipole Model over Real Ground

The last section dealt with an ideal dipole in free space. While space is still pretty free, it's hard to get to and most dipoles are fabricated closer to the earth! A feature of *EZNEC* is the ability to easily move between free space, perfect ground (as in an infinite gold sheet) and real ground. By just clicking on the GROUND tab of the main *EZNEC* window you are offered a choice. I have done that with this model, as shown **Fig A-11**.



Freq 10 MHz
SWR 1.46
Z 73.24 at -0.02 deg
= 73.24 - j 0.03148 ohms
Refl Coeff 0.1886 at -0.08 deg
= 0.1886 - j 0.0002073
Ret Loss 14.5 dB

Source # 1
Z0 50 ohms

UBA0274

Fig A-6 — *EZNEC* SWR plot for modeled antenna in free space with 50-Ω reference.

You can accept the *EZNEC* default ground parameters or insert actual ones depending on your knowledge of local soil conditions.

Fig A-12 shows the resulting SWR plot. While it has a similar shape to that of the free-space plot, you can see that the resonant frequency has shifted. This is a typical, in that changing almost anything about an antenna causes change in the performance. This is one reason why many antennas have adjustable element lengths to compensate for changes in local conditions.

The elevation plot in **Fig A-13** is very different from Fig A-10, the plot for the free-space antenna. Fig A-13 is for a dipole placed a half wave above flat ground. It dramatically shows the result of a reflected signal from the flat ground below. For a horizontally polarized antenna, the reflection is out of phase with the incident wave. At a height of a half wavelength above ground, the radiation cancels in the upward direction at very low takeoff angles, for example, at the horizon. At very high elevation angles, radiation cancels, for example, straight up.

As the plot data indicates, the maximum signal appears at an elevation angle of 28° with the dipole mount a half wavelength high.


SWR Plot: 30 Meter Dipole - Free Space
File Edit View Options
EZNEC Pro/4
Z0
50 ohms
Alt (73 ohms)
1
Source #
INF
10
5
SWR
3
2
1.5
1.1
1
9.8
Freq MHz
10.2

```
Freq       9.8 MHz                               Source #  1
SWR        1.55                                  Z0        73 ohms
Z          76.03 at -24.73 deg.
           = 69.06 - j 31.81 ohms
Refl Coeff 0.2202 at -84.45 deg
           = 0.02131 - j 0.2192
Ret Loss   13.1 dB
```

UBA0275

Fig A-7 — Data of Fig A-6 with reference impedance (Z_0) changed to 73 Ω.


SWR Plot: 30 Meter Dipole - Free Space
File Edit View Options
EZNEC Pro/4
Z0
50 ohms
Alt (73 ohms)
1
Source #
INF
10
5
SWR
3
2
1.5
1.1
1
9.4
Freq MHz
35

```
Freq       10 MHz                                Source #  1
SWR        1.46                                  Z0        50 ohms
Z          73.24 at -0.02 deg.
           = 73.24 - j 0.03148 ohms
Refl Coeff 0.1686 at -0.08 deg
           = 0.1686 - j 0.0002073
Ret Loss   14.5 dB
```

UBA0276

Fig A-8 — Data of Fig A-6 with expanded frequency range.


2D Plot: 30 Meter Dipole - Free Space
File Edit View Options Reset
Total Field
EZNEC Pro/4
0 dB
-5
-10
-15
-30
10 MHz

```
Elevation Plot                                    Cursor Elev  0.0 deg.
Bearing          0.0 deg.                         Gain         2.06 dBi
Outer Ring       2.06 dBi                                      0.0 dBmax

Slice Max Gain   2.06 dBi @ Elev Angle = 0.0 deg.
Front/Side       0.0 dB
Beamwidth        ?
Sidelobe Gain    < -100 dBi
Front/Sidelobe   > 100 dB
```

UBA0277

Fig A-9 — *EZNEC* graphical output (FFPLOT) **with** PLOT TYPE **set to** ELEVATION.


2D Plot: 30 Meter Dipole - Free Space
File Edit View Options Reset
Total Field
EZNEC Pro/4
0 dB
-5
-10
-15
-30
10 MHz

```
Azimuth Plot                                      Cursor Bear  2.0 deg.
Elevation Angle  0.0 deg                          Gain         2.06 dBi
Outer Ring       2.06 dBi                                      0.0 dBmax

Slice Max Gain   2.06 dBi @ Bearing = 2.0 deg.
Front/Side       31.16 dB
Beamwidth        78.2 deg.; -3dB @ 320.9, 39.1 deg.
Sidelobe Gain    2.06 dBi @ Bearing = 179.0 deg.
Front/Sidelobe   0.0 dB
```

UBA0278

Fig A-10 — *EZNEC* graphical output (FFPLOT) **with** PLOT TYPE **set to** AZIMUTH, **elevation angle set to** 0° **(horizon).**

In general, as the antenna is raised higher above the ground, the major radiation lobe is lowered, but it never quite reaches the horizon, no matter how high it is placed.

The plot in **Fig A-14** provides the azimuth pattern at a 28° elevation angle. Note that *EZNEC* allows you to specify any elevation angle for the azimuth plot. I selected the elevation that yielded the maximum signal, but you may be interested in the signal at other takeoff angles. In Fig A-14 *EZNEC* has selected the azimuth with the strongest signal for the detailed readouts at the bottom of the plot. As with all *EZNEC* plots, by merely clicking on another point on the plot, you can select the readout for that point. In **Fig A-15**, I have selected the data at 45° off axis, just by clicking on that point of the curve. This is a very powerful tool!

Going Further with *EZNEC*

The various forms of dipoles we've looked at here just scratch the surface of *EZNEC*'s capabilities. Additional elements can be added just by defining additional "wires" separate from the first. For parasitic elements, that's all there is to it. For additional driven elements, multiple sources can be defined or the elements can be connected using transmission lines, defined in their own parameter screen.

Most outputs are available in tabular form so they could be input into other programs for further analysis. As with all such analysis tools, more complicated antenna models can have pitfalls, and it is best to read the *EZNEC* documentation to understand how far limitations can be pushed before the results suffer.

In any event, try different models of the antennas shown in the book or that you think might provide interesting results. It is much easier, faster and cheaper than building them in the back yard!


EZNEC Pro/4 v. 5.0
File
Edit
Options
Outputs
Setups
View
Utilities
Help
Open
Ant Notes
Currents
Src Dat
Load Dat
FF Tab
NF Tab
SWR
View Ant
NEC-4D
FF Plot

```
30 M Dipole - 0.5 WL Abv Gnd
File                30M Dipole Over Gnd.EZ
Frequency           10 MHz
Wavelength          98.3571 ft
Wires               1 Wire, 19 segments
Sources             1 Source
Loads               0 Loads
Trans Lines         0 Transmission Lines
Transformers        0 Transformers
L Networks          0 L Networks
Y Param Networks    0 Y Param Networks
Ground Type         Real/High Accuracy
Ground Descrip      1 Medium (0.005, 13)
Wire Loss           Copper
Units               Feet
Plot Type           Azimuth
Elevation Angle     28 Deg.
Step Size           1 Deg.
Ref Level           0 dBi
Alt SWR Z0          73 ohms
Desc Options
Gnd Wave Dist       OFF
```

UBA0279

Fig A-11 — *EZNEC* main screen after selecting REAL/HIGH ACCURACY **ground in place of** FREE SPACE.


SWR Plot: 30 Meter Dipole - Free Space
File
Edit
View
Options
Z0
50 ohms
Alt (73 ohms)
1
Source #
EZNEC Pro/4
INF
10
5
SWR
3
2
1.5
1.1
9.8
Freq MHz
10.2

```
Freq       9.8 MHz                  Source #  1
SWR        1.86                     Z0        50 ohms
Z          76.03 at -24.73 deg.
           = 69.06 - j 31.81 ohms
Refl Coeff 0.3009 at -44.12 deg.
           = 0.216 - j 0.2095
Ret Loss   10.4 dB
```

UBA0280

Fig A-12 — *EZNEC* SWR plot for modeled antenna over real ground with 50-Ω reference.


2D Plot: 30 M Dipole - 0.5 WL Abv Gnd
File
Edit
View
Options
Bands
Total Field
EZNEC Pro/4
0 dB
-5
-10
-15
-20
-30
10 MHz

```
Elevation Plot                           Cursor Elev   28.0 deg.
Bearing          0.0 deg.                Gain          7.38 dBi
Outer Ring       7.38 dBi                              0.0 dBmax

Slice Max Gain   7.38 dBi @ Elev Angle = 28.0 deg.
Beamwidth        32.8 deg.; -3dB @ 13.1, 45.9 deg
Sidelobe Gain    7.38 dBi @ Elev Angle = 152.0 deg.
Front/Sidelobe   0.0 dB
```

UBA0281

Fig A-13 — *EZNEC* graphical output (FFPLOT) **with** PLOT TYPE **set to** ELEVATION **for model over real ground.**


2D Plot: 30 M Dipole 0.5 WL Abv Gnd
File Edit View Options Reset
Total Field
EZNEC Pro/4
0 dB
-5
-10
-15
-30
10 MHz

Azimuth Plot
Elevation Angle 28.0 deg.
Outer Ring 7.38 dBi

Cursor Bear 0.0 deg.
Gain 7.38 dBi
0.0 dBmax

Slice Max Gain 7.38 dBi @ Bearing = 0.0 deg.
Front/Side 10.58 dB
Beamwidth 88.0 deg.; -3dB @ 317.0, 43.0 deg.
Sidelobe Gain 7.38 dBi @ Bearing = 180.0 deg.
Front/Sidelobe 0.0 dB

UBA0282

Fig A-14 — *EZNEC* graphical output (FFPLOT) **with** PLOT TYPE **set to** AZIMUTH**, elevation angle set to** 28° **for model over real ground.**


2D Plot: 30 M Dipole 0.5 WL Abv Gnd
File Edit View Options Reset
Total Field
EZNEC Pro/4
0 dB
-5
-10
-15
-30
10 MHz

Azimuth Plot
Elevation Angle 28.0 deg.
Outer Ring 7.38 dBi

Cursor Bear 45.0 deg.
Gain 4.09 dBi
-3.29 dBmax

Slice Max Gain 7.38 dBi @ Bearing = 0.0 deg.
Front/Side 10.68 dB
Beamwidth 88.0 deg.; -3dB @ 317.0, 43.0 deg.
Sidelobe Gain 7.38 dBi @ Bearing = 180.0 deg.
Front/Sidelobe 0.0 dB

UBA0283

Fig A-15 — Same plot as Fig A-14, except cursor is set to a 45° azimuth angle to determine value is at that bearing.



BASIC ANTENNAS...

...understanding antennas from the ground up!

For something that is often so simple to make, an antenna is remarkably difficult for many people to understand. That's unfortunate, because for many radio systems the antenna is one of the most important elements, one that can make the difference between a successful and an unsuccessful system.

Basic Antennas is a comprehensive introduction to antennas—basic concepts, practical designs, and details of easy-to-build antennas. You'll learn how to make antennas that really work! This book will provide a foundation in antenna theory and design necessary for anyone undertaking more advanced topics such as those presented in ***The ARRL Antenna Book***.

Contents

- Introduction to Antennas
- Dipole Antennas
- Antenna Impedance
- Transmission Lines
- Practical Two Element Arrays
- Wideband and Multiband Antennas
- Monopole Antennas
- Reflector Antennas
- Yagis for HF and VHF
- Loop Antennas
- Antennas for Microwave Applications
- Vehicle Antennas
- Antenna Measurements

Plus, an Introduction to Antenna Modeling...and much more!

ARRL—devoted entirely to Amateur Radio

ARRL has books, software, online courses and other resources for continued education, experimentation, and growth. Look for these other popular ARRL titles:

- ***Understanding Basic Electronics***
- ***Basic Radio—Understanding the Key Building Blocks***
- ***The ARRL Antenna Book***
- ***The ARRL Handbook for Radio Communications***

Joel Hallas has been a radar and telecommunications systems engineer, engineering manager, telecommunications executive, college teacher and is now Technical Editor of *QST*, the monthly journal of ARRL, the national association for Amateur Radio. He has earned BS and MS degrees in electrical engineering. Joel is a radio amateur, and holds the license call sign W1ZR. He is also the author of ***Basic Radio—Understanding the Key Building Blocks***, published by ARRL.

Published by:
ARRL The national association for AMATEUR RADIO
www.arrl.org

ISBN 978-0-87259-999-4
52995
9 780872 599994
USA $29.95 ARRL Order No. 9994

$4.95



INSTRUCTIONS FOR USE OF
TYPE 558-P AMATEUR BAND FREQUENCY METER

AL RADIO COMPANY
GE, MASSACHUSETTS, U.S.A.

RADIO FREQUENCY TESTERS

77 Pieces of Test Equipment You Can Build!

The 73
Test Equipment Library
volume III

the 73 TEST EQUIPMENT LIBRARY

Volume III: Radio Testers

Edited by Sandy Cole W1PUF
and
Rich Force WB2QYV/1

A product of 73 Inc.

EDITOR'S COMMENTARY

This is Volume III in the *73 Magazine* series of Test Equipment books. The first two volumes covered component testers and audio frequency testers. This book, which deals with radio frequency testers, is by far one of the most important of the series.

The generation of radio frequency waves is the one common denominator through all of ham radio. No matter what your specific interest in this fascinating hobby, without the correct generation and radiation of radio waves, your enjoyment will be frustrated. In this book we have attempted to put together some of the best articles which have appeared in *73 Magazine* all aimed at assisting you in achieving the best possible on-the-air signal. Many hours have gone into its preparation by scanning past issues for projects which would be of the most use, be up-to-date and be easily constructed with available parts. We think we have achieved this end.

It must be noted that some of the equipment described in this book appeared in vintage issues of *73 Magazine*, yet the design and value of the equipment has not aged and it is as up-to-date today as it was when it was first published.

We at *73 Magazine* hope this book will help to make your effort to put out a "respectable" signal easier and more enjoyable.

73, Rich Force WB2QYV/1

Copyright 1976
73 Inc., Peterborough NH 03458

All Rights Reserved
Printed in U.S.A.

Table of Contents

The 73 Test Equipment Library

Volume III: Radio Frequency Testers

Chapter I: What is Your SWR, OM?

SWR Power Meter for 80 Thru 10m Bands	W6VAT	5
An Etched Circuit SWR Bridge	WA5SWD	6
Checking Your SWR Indicator	W5EHC	8
Home Brew Bridge Calibration	W4OAB	8
Mini SWR Bridge	W2EEY	8
VSWR Supreme	W4BRS	9
A Simple VHF SWR Meter	W2EEY/K3EZ	10
Directional Coupler and VSWR Bridge for VHF and UHF	WA6SXC	13
A Slotted Line for 1250 MHz	WA8CHD	14
Some Directional Wattmeters and a Novel VSWR Meter	G3PDM	16
SWR Bridges Using Zero-Center Meters	W2EEY/K3EZ	18

Chapter II: How to Measure RF Impedance

The Antennascope – An Effective Tool	VE3CEA	21
How to Build an Antennascope	WA1CCH	22
The Mark III RF Impedance Bridge	W6CRT	22
Measure RF Impedance with Your SWR Bridge	W2AOO	26
Use Your GDO and Z Meter	W0BMW	27

Chapter III: Measuring RF Power Output

Measuring RF Output	WA6CPP	30
Light Bulbs as RF Indicators	WB2GQY	30
Build Yourself a Light Wattmeter	Henry	32
Low Power Light Wattmeter	K1CLL	33
Yet Another Light Wattmeter	K5CXN	34
A Low Cost RF Wattmeter	WA3AJR	35
RF Power Measurement Using Hot Carrier Diodes	W6AJF	36
VHF Dummy Load Wattmeter	K9STH	38

Chapter IV: Measure Your Field Strength and Frequency

The RF Sniffer	K5JKX	39
A Useful Accessory for the Ham Shack	W2WHX	40
Two Thru Twenty FSM	W7OE	40
An Amplified, Calibrated Signal Strength Meter	VE3CES	41
Frequency Measuring Equipment at Microwave Frequencies	WA9VFG	42
Frequency Meter-1 to 10 GHz Amateur Microwave	K1CLL	43
Lambda Lines	W2DXH	46

Chapter V: RF Signal Generators

Zero-Beating with a Frequency Meter	WB4TBX	48
Hand Calibrate the BC-221 Frequency Meter	Henry	48
High Accuracy VHF Frequency Measurements	W5WGF	49
Transistorized LM Meter	W5SOT	50
An I-F Spotter	W5WGF	52
430-470 kHz Sweep Frequency Generator	WA5SWD	53

An Armstrong Sweeper W2EMF 54
A New Broom K6JHJ 54
Low Cost Signal Source VE3GFW 55
Receiver Tweaker K6UAW 56
Citizen Band Alignment Aid WA5SWD 56
FET Chirper K6QKL 57
UHF Signal Source K1CLL 58
Crystal Controlled Signal Source with Infinite Attenuator for 144, 432 and 1296 MHz K1CLL 59
Low Cost 220 MHz Signal Generator K1CLL 60
UHF Signal Generator K6MIO 62
Lab Type IF/RF Sweep Generator Using ICs K4DHC 63
100 kHz Thin-Line Pulse Generator W2DXH 70

Chapter VI: Crystal Calibrators

All Band Band-Edge Marker WA2HRZ 74
The Multical K9VXL 74
100 kHz Marker Generator W7CJB 75
All Band Frequency Marker W1KNI 75
Poor Man's Universal Frequency Generator W2EEY 76
Calibrate that Calibrator W2KPE 78
A Simple Frequency Deviation Meter K6BJ 78

Chapter VII: GDOs

The Indicating Oscillator KH6AF 80
The Little Gate Dipper W5ETT 81
The Great Dipper WA0AYP 83
The Great Dipper-Modification WA0AYP 85
Etched Circuit UHF Dipmeter W1JJL 86
UHF Grid Dipper WA6BSO 87
Wide Range VHF-UHF Dipper K1CLL 91
Extra Services from Your Grid Dip Oscillator WA4UZM 94
GDO to Find C G3OGR 94
GDO Coil Extension WA0ABI 94

Chapter VIII: Noise Generators

Simple Noise Generator K9ONT 96
A Crystal Diode Noise Generator W5TEV 96
Temperature Limited Diode Noise Generator Thomas 97
Calibrated Noise Generator for 432 W6GXN 98
Another Way to Measure Noise Figure K5JKX 99

Chapter IX: Attenuators and Dummy Loads

Low Power Attenuators for the Amateur Bands WB6AIG/WA6RDZ 102
S-Unit Attenuator WA5SWD 103
The Ever-Useful T-Pad K5JKX 103
Combination Dummy Load/Attenuator Network W2EEY 104
The Minican W6JTT 106
The Tiny Terminator K5JKX 106

Chapter I

What is Your SWR, OM?

SWR POWER METER FOR 80 THRU 10m BANDS

James Lee W6VAT

WITH the declining sunspots, usage of the lower frequency bands is definitely increasing. The resulting increased QRM is helpful to no one and only efficient equipment and operating procedures will result in a maximum number of QSO's. The SWR/PWR meter described here won't make you a better operator, but it can help you be sure that you are delivering the most rf to your antenna from your rig. Fig. 1 shows a front view of the meter.

The basic circuit is a directional coupler switched to sample either forward or reverse voltage and a voltmeter to read this voltage.

This type of coupler has an output proportional to length, power, and frequency. The longer it is, the more output it gives. Since it puts a small impedance "bump" in the line, the length of the coupler should be limited to not over 1/20 wavelength at the highest frequency, or it may begin to contribute noticeably to the SWR itself. For a given power, if the frequency of the rf flowing through the coupler is reduced, the maximum coupler output is reduced. This means that you can get full scale readings on 10 M with a lot less power than on 80 M. The meter described here gives half scale deflection on 40 M, at maximum sensitivity, with about 350 watts of forward power. If your rig is a KW this meter will fill the requirements for SWR/PWR measurements nicely. It can be left in the line at all times to monitor SWR or Power delivered to the antenna or other load. If desired, a Barker and Williamson type 551A coaxial switch can be used to insert the meter in the line for test purposes and then switch it out during operating periods.



Construction

The unit is built in a gray hammertone LMB type 141 box. The dimensions of this box are 3" x 4" x 6". Fig. 2 shows the parts placement and should answer any questions concerning layout.

The coax directional coupler is made from a 14" length of RG-8/U. The outer covering is slit lengthwise with a knife and peeled off. Take care here not to cut into the woven braid. The woven braid is then bunched toward the center to loosen it. Next, a length of #22 enameled wire is passed through the braid at about 2¼" from one end and run under the braid next to the inner insulation. It is brought out at the other end, again 2¼" from the end of the shield braid. When this is done, smooth the braid back to its original position carefully to avoid scratching the enamel on the #22 wire. The #22 enameled wire should lay as straight as possible under the braid. It should have no slack nor should it twist around the inner insulation to any great degree. The ends of the shield braid are trimmed back far enough to be soldered to Amphenol 83-1H hoods. The inner insulation is trimmed off so as to expose about 3/16" of the inner conductor. The inner conductors are then soldered to Amphenol 83-1R female type chassis mount coax connectors. The coupler may now be set aside and the rest of the meter constructed.

Potentiometer R_1 is mounted on 1/16" x 1" x 4" piece of bakelite and positioned approximately in the center of the box to minimize capacity to ground. The metal rear cover is removed from the pot for the same reason. The pot ground lead is to the center of the coax and is wire in last. The diode D_1 should be protected from damage by heat when soldering it in the circuit. Long nose pliers gripping the leads near the body of the diode are satisfactory. The directional coupler is the last item soldered in place. As can be seen in the photos—the coax connectors are mounted from the inside of the box. When the #22 enameled leads are soldered to S_1 they should be the same length, and again, take care not to scratch the enamel or a short circuit may occur and you'll have to do it all over again.

Calibration

There are any number of ways to calibrate the SWR/PWR meter, but the way most hams will use is their own rig and a suitable dummy load. Though very limited in power, a 2 watt 50 ohm resistor such as made by Ohmite, IRC and others, mounted inside an Amphenol 83-1SP male coax plug makes a very good dummy load. Although not completely noninductive, this dummy load is far superior to such real unknowns as light bulbs, electric iron heating elements, etc. This particular load is 50 ohms shunted by 6 mmfd over the range of 3-30 mc. It is a good dummy load—though a low power one.

With the back cover off, attach the dummy load to J_2, the load jack. Set R_1, the Sensitivity Control, to maximum and S_1 to FORWARD. Next apply power by hooking your rig (or



other rf source) to J_1, the transmitter jack. Make sure that the rf applied is 28-30 mc, or, the highest frequency you operate in the 3-30 mc region. This meter is sensitive to frequency. Stray capacities and other unbalances will have their greatest effect at the highest frequencies. In any event, calibrate the unit on the highest frequency your rig will tune in the 3-30 mc region. With power applied, set R_2 so the meter reading is at least half scale and switch S_1 to REVERSE. This will result in a lower meter reading. R_1 should then be adjusted for a minimum reading on the meter. Using the suggested load, you will not get a complete null, but the null should not be much more than 50 ua for half scale deflection in the FORWARD position on S_1. Don't put too much power into the dummy load since excessive dissipation can ruin it and change its characteristics greatly. If you have a higher power dummy load whose characteristics you know accurately, by all means use it, but remember a light bulb is not a good load. Once nulled, lock the nut on R_1 taking care not to disturb the setting. Replace the back cover and using the dummy load, recheck the null to make certain that it has not shifted.

Using The Meter

To make SWR measurements you need only insert it in the line and set S_1 to FORWARD and S_2 to SWR. Adjust the sensitivity control for at least a half scale reading. Then switch S_1 to REVERSE and read the value. SWR is then calculated by the following:

$$\text{SWR} = \frac{I_{fwd} + I_{rev}}{I_{fwd} - I_{rev}}$$

For example:

let $I_{fwd} = 500$ ua and $I_{rev} = 50$ ua, then

$$\text{SWR} = \frac{500 + 50}{500 - 50} = \frac{550}{450} = 1.22{:}1$$

The meter is useful for tune-up purposes where exact SWR is not needed. Just keep the FORWARD reading at a constant value and tune for minimum REVERSE readings. The exact SWR can be calculated when you have found the lowest REVERSE position.



The POWER position may appear to be essentially the same as the SWR position and it is. When measuring power into a load of known fixed value you only need to know the voltage across (or the current through) the load. The POWER position on S_2 is used with S_1 set to FORWARD. R_3 is merely set to a scale reading that is convenient for all bands if only a relative reading is used. If a good 50 ohm high power dummy load is available, you may make accurate calibrations by using a VTVM plus high frequency detector probe and measuring the actual voltage across the load. Just put a T-connector on the load jack J_2. Put the dummy load on one arm of the "T" and read the voltage at the other arm. 200 volts across a pure resistive load of 50 ohms is equal to 800 watts of power. If your rig delivers a key down 800 watts to a load then you could set R_3 at 0.8 ma on the scale, etc. The scale will not be precisely linear, particularly at low powers, but if enough resistance is used at R_3 the effects should be minimum. Since the coupler voltage is frequency sensitive one setting of R_3 will not hold for all bands. If desired, R_3 could be replaced with a switch and a number of selected resistors (one for each band). This would keep the scale factor constant between bands. This could be done for R_2 as well, but complicates an otherwise simple device

Operation

Once calibrated, the meter is very simple to use. Just hook it in the line at some convenient point and apply power. With S_1 set to FORWARD and S_2 set to SWR, adjust R_2 for at least a half scale reading. Switch S_1 to REVERSE and you will then be able to continuously monitor your reverse power. For power measurements, set S_1 to FORWARD and S_2 to PWR. Apply power and the meter will be monitoring your forward power continuously. R_3 is a screw driver adjusted pot. It can be set, and locked at a point which allows operation on all the bands you operate. The scale reading on each band will be different, but once set, these readings can be jotted down in your log book and any change quickly noted. This meter is also an excellent device for the antenna "tinkerer," or if you have coax coupling between stages in your rig it can be used to provide proper power transfer. Best of all, it is not expensive nor difficult to construct. Try one and you won't be without one again.

AN ETCHED CIRCUIT SWR BRIDGE

Ed Lawrence WA5SWD

Several of these boards have been etched and units assembled, and all have been satisfactory. I have used mine, with a 200 microamp meter, from a kw on the low bands up to a "Twoer," with no problems with sensitivity.

Since Bud Miniboxes are commonly available, I scaled this board to fit into the Bud



Schematic diagram of SWR bridge.





Fig. 1. Metering circuit for the etched circuit SWR bridge.





Fig. 2. Layout for the printed circuit board.

Minibox CU 2102A or CU 3002A. If you want to include the metering in the same package, the CU 2103A or CU 3003A should be used to give more room.

If you use the CU 2102A, center the coax connectors on the ends. If the CU 2103A, mount the connectors .8 inches from the open end. I used solder lugs bent at right angles to mount the P. C. Board to the chassis. The photograph shows the mounting much better than 10,000 words.

The meter sensitivity control circuit shown has a wider control range than the one shown in the *ARRL Handbook*, since the pot shunts the meter at low settings. This action could be accentuated by putting a fixed resistance in series with the meter movement, at the expense of sensitivity.

Although the virtues of operating transmission lines with low standing wave ratios (SWR) have been discussed many times in the past, evidently the economics of maintaining low SWR's are not readily apparent, particularly if the frequency of operation is low and the transmission line short. This has been reflected in various pseudo-technical QSO's where many have been led to the utter disregard for standing wave ratios. Most members of the amateur fraternity exist on limited budgets at best and when a significant portion of that precious transmitted power is eaten up by transmission line losses and misinterpreted standing wave ratios for naught, something should be done.



SWR vs % Power Transmitted and Power Reflected

Figure 1

A look at the graph in Fig. 1 will show you the percentage of power reflected for various standing wave ratios. For instance, if you are presently tolerating an SWR of about 5.8:1 (not uncommon in many ham shacks), 50% of the power which reaches the antenna is actually reflected back down the transmission line, heating up the final tank and causing TVI. Nor is only the transmitted signal effected, a high SWR will similarly degrade the received signal. This is particularly important in the reception of the extremely low level signals often encountered in DX and VHF operating. Stereophonic buffs should take heed too. A recent report by the IEEE (Institute of Electronic and Electrical Engineers) Professional Group on Broadcasting noted that a high SWR on receiver antenna inputs causes a reduction of stereo quality.



Figure 2

Attenuation vs frequency.

Many of the amateur stations on the air today make use of RG8A/U coaxial cable. Its excellence is proven out by its extensive use by the military, but a look at the loss graph (Fig. 2) for this cable indicates that it is not completely lossless! Even at 4 mc it has approximately 0.3 db loss per 100 feet, and on six meters there is a loss of 1.4 db for the same length. A look at Fig. 3 indicates that on 75



Figure 3

Attenuation vs Power transmitted.

meters only 94% of the transmitted power is delivered to the antenna if 100 feet of RG8A/U is in use. At 50 mc the loss has sky rocketed to 26% for the same length of line. However, there is one big hooker for these conditions to exist: the SWR must be 1:1. For any other value of SWR there will be further line losses as shown in Fig. 4 because standing waves have the property of multiplying attenuation. This graph indicates that if a transmission line is operating at an SWR of 3.7:1, the line loss will be multiplied by a factor of two. For the previously mentioned situation on 50 mc, an additional 24% loss could be expected with an RG8A/U line operating at an SWR of 3.7:1.

It should be obvious by now that the use of an SWR bridge in the line at all times is very advantageous in the maintenance of a low SWR at the operating frequency. However, contrary to popular belief, the SWR bridge does not tell all. Since there is loss or attenuation in any length of transmission line, the reflected wave will be attenuated in the same matter as the transmitted or incident signal. Because the standing wave ratio is the ratio of the incident wave to the reflected wave, attenuation of the reflected wave will give erroneous SWR measurements when the SWR bridge is conveniently located at the transmitter. In this location the bridge will see the full power of the transmitter, but only a portion of the reflected signal. In some cases where the length of the transmission line is excessively long, the reflected wave will be attenuated to such a degree that the SWR will appear to be very close to 1:1, while in reality it will be a good deal higher. This fact is graphically represented in Fig. 5.



Figure 4

Line loss multiplier vs SWR.



Figure 5

SWR vs attenuation.

For example, 143 feet of RG8A/U at 50 mc would result in approximately 2 db attenuation. If an SWR bridge inserted in the line at the transmitter indicated an SWR of 2:1, this graph shows that an SWR of 3:1 exists at the antenna. A look at Figs. 3 and 4 will indicate that a 3.3 db loss (2 db times 1.65 multiplier) occurs, amounting to 47% loss of transmitted power in transmission line losses. Of the remaining 53% power arriving at the antenna, 24% will be reflected back down the line. A little simple arithmetic will show that of the total power transmitted, only 30% will be radiated! This simple mathematical fact should make the merits of low standing wave ratios immediately obvious if we wish to get the most out of our equipment. By keeping transmission lines short and by insuring that the SWR is as close to 1:1 as practicable, line losses will be minimized, maximum power will be delivered to the antenna and more successful and reliable radio communications will result.

CHECKING YOUR SWR INDICATOR

Carl Drumeller W5EHC

Many articles have been published on how to build and even some on how to calibrate a VSWR indicator. The calibration instructions usually tell you to terminate the indicator's output with a purely-resistive 52-ohm load and then to adjust the device so that a maximum forward and minimum reflected meter deflections are obtained. Sometimes they'll go further and tell you to reverse the device and recheck for opposite indications.

This is all very well. It assures you that the VSWR indicator will be telling you the truth when it says "All's well!" while looking into an utterly-flat transmission line. It doesn't tell you a thing about what the indicator will have to say when it gets tangled up with a line that has a wildly-mismatched termination.

As most transmission lines, in actual practice, are terminated in loads which are not only mismatched in the matter of resistance but also in the inclusion of a considerable magnitude of reactance, it would be well to explore the indications you'll get under realistic circumstances. After all, these are the situations under which you'd want to take corrective steps. Accurate indications of undesired conditions, therefore, are imperative if intelligent remedial actions are to be taken.

Fortunately, some quite enlightening tests are made easily. All you'll need are some lengths of coax transmission line (the same as you're using in your antenna feedline) equipped with male fittings at each end and a few female-to-female junctions. Select the frequency at which you want to make the test. Usually it's wise to make the test on the highest frequency band you plan to use. With this in mind, make up three one-eighth wavelength sections of transmission line and mount the male fittings on the ends of each section.

If your antenna presents an unmatched load to your transmission line, you may elect to skip over this paragraph and go directly to the next one. If it does not (Ah, you dreamer!), you'll need another piece of transmission line. It should be fairly long, perhaps a half wavelength. Put a male fitting at one end and attach a termination, which is deliberately made to be a sad mismatch, at the other end. Don't just mismatch it by using too high or too low a value of resistance. Throw in some reactance, too! You might use a resistor with an inductor in series. Or, you might try a capacitor in series with the resistor. Or, you could use either an inductor or a capacitor in parallel with a resistor. In fact, it would be best to experiment with all four!

Now that you have a transmission line available that you know is mismatched, you're ready to start the test. The first check (the "control", you might call it) is made with everything normal. That is, you'll have the transmitter feeding directly into the VSWR indicator's transfer box and the transmission line (either the one to your antenna or the substitute line to the mismatched load) attached to the output of the transfer box. Note the VSWR indicated. Also note your transmitter; insure that it's tuned to resonance and is adjusted to a power you can maintain throughout the first portion of the tests. Jot down these indications. Now, insert an eighth-wave section between the transfer box and the transmission line and without making *any* other changes or adjustments, note the VSWR. Repeat these steps, adding an additional eighth-wave section each time until you've used all three. Did you detect any change in VSWR? If there was even the slightest change, your VSWR indicator is not trustworthy!

Now for two more checks. Try varying the transmitter power output. Does this have any effect upon the indicated VSWR? If it does, your VSWR indicator is not trustworthy! Then try varying the transmitter output tuning, deliberately throwing the stage out of resonance. Does this have any effect upon the indicated VSWR? If it does, your VSWR indicator is not trustworthy!

Few VSWR indicators under the $150 class will pass these basic tests. If yours doesn't, don't be perturbed. You have an instrument that still has a useful field of application. You can use it as a comparative indicator. For instance, if you're adjusting the gamma match at an antenna, it'll serve quite well; in this application, you're holding all of the significant variables constant, with the exception of one (the gamma match), the effect of which you want to observe. Your tests will have shown you the parameters you'll have to hold constant for any other than simple comparisons. In all probability, you will have found that measurements taken with different (electrical) lengths of transmission line are invalid. Also, it's probable that, owing to the non-congruity of diode curves, measurements will have to be taken at precisely the same level of rf power if accurate comparisons are to be made.

If you'll keep its very real limitations in mind, you'll find that even an inexpensive VSWR indicator has excellent potentials for useful measurements. But don't ask it to perform at levels that even its expensive siblings can't attain!

HOME BREW BRIDGE CALIBRATION

Clifford Honess W4OAB

This table is useful for all homebrew SWR bridges and gives the % reflected power and the % full scale reading in the reflected mode, when the meter is set at full scale in the forward mode.

SWR	% Pwr. Refl.	Refl. Rdg. in % of Full Scale
1.1	.2%	4.8%
1.2	.8	9.1
1.3	1.7	13.1
1.4	2.8	16.7
1.5	4.0	20.0
1.6	5.3	23.1
1.7	6.7	25.9
1.8	8.2	28.6
1.9	9.7	31.1
2.0	11.0	33.3
2.1	12.6	35.5
2.2	14.0	37.5
2.3	15.5	39.4
2.4	17.0	41.2
2.5	18.4	42.9
2.6	19.7	44.4
2.7	21.1	45.9
2.8	22.5	47.4
2.9	23.8	48.7
3.0	25.0	50.0
4.0	36.0	60.0
5.7	49.0	70.0
9.0	64.0	80.0
19.0	81.0	90.0

MINI SWR BRIDGE

John Schultz W2EEY

Most SWR meters today are of the coupled variety which can be left in a transmission line while a transmitter is operated at full power. However, for a number of prolonged tune-up operations, involving antenna matching systems, for instance, such couplers have several disadvantages.

On 160 and 80 meters, especially, a reasonable amount of power is necessary to produce full deflection—up to 100 watts with some configurations. With a very low-powered transmitter, making adjustments at this power level certainly may damage the output tube or tank-circuit components with a high SWR. This will not be the case with higher-powered circuits but, in any case, a signal strong enough to cause needless QRM will be radiated.

Another disadvantage of the coupled SWR meter, if it is home constructed, is that it must be carefully calibrated since its response is very dependent upon the mechanical configuration of the coupling circuit. This is unlike the bridge-type SWR meter (described in this article) where a standard SWR curve may be used with a good degree of accuracy.

The above factors, plus the fact that I didn't need an SWR meter continuously in the transmission line, led me to construct the little resistance type SWR bridge shown in the photograph. It is just about as simple and inexpensive a unit as can possible be built.



Fig. 1. SWR Bridge Circuit. See text for values of R_1, R_2 and R_3. R_4 and R_5 may be any matched value from 10 k to 47 k. D_1 and D_2 are IN34, IN54, or similar types. All capacitors are disc ceramic, .005 MF, 100V.

Construction

Two SO-239 coax chassis connectors are joined back to back by two 1¼ inch threaded hex spacers. The two four-lug terminal strips are mounted at the ends of one of the spacers. The wiring of diodes D_1 and D_2 as shown in **Fig. 1**, should be such that the incidental voltage-measuring point appears on the terminal strip mounted on the "input" SO-239 connector, in order to avoid confusion in measurement. Short leads, of course, should be used but hardly anything else is possible with only 1¼ inches between connectors.

Some attention must be paid to the components used if accurate readings are to be obtained. Resistor R_3 must closely match the impedance of the coaxial line used (52 or 75 ohms). For 52-ohm lines, a suitable resistor (within ½ to 1 ohm) can usually be found from a group of standard 10% tolerance, 47-ohm resistors; and for 75-ohm lines, from a group of 68-ohm resistors. Resistors R_1 and R_2 can have any value from about 30 to 100 ohms, but it is important that they are as closely matched as possible. One trick which may be used to affect very small resistance changes is to file "V" notches in a composition resistor to raise its resistance. Two-watt units are suggested for these resistors because of their longer-term stability and endurance in case too much input power is applied.



Fig. 2. Simplified diagram of SWR Bridge. V_1 represents incident voltage and V_2 the reflected voltage.

Resistors R_4 and R_5 serve as linearizing resistors so that almost any meter with a basic movement of 1 mA or less can be used as an indicator. The lower dc voltage ranges on almost any VOM will work fine. These resistors as well as diodes D_1 and D_2 should be checked to see that they match reasonably well (the resistors within a few precent and the diodes within a few percent for their forward and reverse resistance readings).

Calibration

There are really no adjustments that can be made to the bridge, and calibration really consists of checking the balance. **Fig. 2** is the dc circuit of the bridge (a simple Wheatstone bridge with resistance arms). If the balance of the bridge is good, V_2 should be the same when points R_X are opened or shorted so long as V_1 is held constant. This can be checked on the actual bridge by applying an input at the highest frequency of interest (6 or 10 meters), shorting J_2, and checking that incident and reflecting voltages are the same. The same is done with J_2 open. If the voltages are not equal, the difference can be taken as an indication of how accurate the SWR readings will be. If the difference is too great, R_1 or R_2 will have to be changed for a better match or the mounting of the components changed to reduce stray couplings.

A further check is to connect a known 52 or 75 ohm resistor across J_2. The reflected voltage should, of course, read zero.

Operation

As noted in **Fig. 2** the actual SWR is a simple function of the incident and reflected voltage readings. **Fig. 3** presents this function in graphical form. The incident voltage is simply adjusted for some convenient value, say 10 volts reading on the dc scale of a VOM (possible with most SSB transmitters by adjusting the carrier balance control with no audio input). The reflected voltage is then read as a percentage of the incident voltage and the SWR found from **Fig. 3.** The input power required to operate the bridge is essentially independent of frequency, being about 1-2 watts maximum.



Fig. 3. SWR values for selected reflected voltage readings taken as % of incident voltage reading.

It should be remembered that such a bridge can measure only the resistive portion of an impedance. When using it to adjust a circuit, if a SWR minimum null but not a zero reading for reflected voltage can be obtained, it indicates some reactive component must still be present.

VSWR SUPREME

E. L. Klein W4BRS

One of the most valuable tools used by the amateur is the Voltage Standing Wave Ratio Meter. It ranks with the grid-dipper and the plate current meter as an indispensable instrument around the ham shack. We know that the VSWR meter is very handy in indicating relative power output when tuning a transmitter, particularly when the plate dip is not too discernable. It is most useful, however, in proving that the last available watt has reached the antenna where it can do some good.

Why a good match?

Although a good copper connection is made all the way to the antenna, an efficient transfer of power may not be achieved because of a mismatch between the characteristic impedances of the various portions of the transmission system. The interesting thing is that the "match" is different for each frequency because the antenna is essentially a single frequency device.

We can appreciate the importance of a proper match between the transmitter and the antenna when we are told, for example, that a VSWR of 3 to 1 causes a power loss of nearly 3 dB for 200 feet of RG-8/U coaxial line at 30 MHz. The table below provides



Fig. 1 Schematic of basic VSWR Meter and associated switching circuits.

Table I

VSWR	Power Loss (dB)	Transmitter Power Needed to Provide 1 kW at the Antenna
1.5:1	2.1	1600 watts
2:1	2.3	1700
3:1	2.8	1900
4:1	3.3	2000
5:1	3.7	2300
7:1	4.5	2800
10:1	5.3	3400

Additional power needed to compensate for a poor impedance match between transmitter and antenna. Figures are based upon 200 feet of RG-8/U cable at 30 MHz.

the real reason why we should be concerned with the impedance match. Notice how much the transmitter power would have to be increased to make up for a poor match between the transmitter and the antenna. Incidently, this match involves each and every part of the total transmission system including connectors, antenna relay, low-pass filter, balun, etc., as well as the transmission line itself and that particularly critical point at which it is connected to the antenna.

A new approach

Most VSWR meters today are an external accessory to the transmitter. But this practice is not good. Coaxial connectors are expensive and cause unwarranted mismatch and power loss. Meter faces usually end up behind the transmitter or in some other inaccessible location. When switching from forward to reverse, the little accessory box scoots across the table leaving scratches and a distraught operator.

The transmitter plate current meter is no longer a plug-in accessory. Why should the VSWR meter be? (Believe it or not, plate meters used to be plugged in with phone jacks.) Using the simple design described here, the home constructor as well as the commercial manufacturer can now build the VSWR meter into the transmitter in the smallest possible space and at only pennies of cost.

The circuit

Nothing is new about the circuit. It has been adequately described in the past in magazine articles and handbooks. However, for the convenience of the reader, the VSWR meter circuit is reproduced in **Fig. 1** for handy reference. Terminating resistors R1 and R2 should be 33 ohms for a 50-ohm transmission line when the physical configuration, as shown here, is used. One-half watt or smaller size resistors may be used. Diodes CR1 and CR2 are any matched pair of silicon diodes or germanium. The types which are enclosed in glass cases are the easiest to use because of their small size. The ohmmeter can be used to select and match the diodes of the ten-cent surplus variety found in advertisements in ham magazines such as *73*. Bypass capacitors C1 and C2 are 1500 pF Centralab type FT-1500.

Physical components

Parts used in this VSWR meter are illustrated in **Fig. 2.** The brass tubing is about 5 to 7 inches long and of 5/16 inch outside diameter. This size tubing fits snugly around the inner polyethelyne insulation from RG-8/U coaxial cable. About 10 inches of coax is stripped of its outer jacket and braid. The inner insulation is trimmed to extend ⅛ inch past each end of the brass tubing. Two large solder lugs are selected to fit over the ¼ inch threaded shank of the bypass capacitors. These lugs should be of the long variety so they may be shaped and soldered to the brass tubing as shown in **Fig. 3.** Two 8-inch pieces of #22 enameled copper wire are also required.

Assembly

After soldering the lugs to the brass tubing about ⅝ inch in from each end, the bypass capacitors are assembled to the lugs. Place several fiber washers under the ring nuts prior to tightening them down on the threaded shank of the capacitors. This permits careful soldering of the capacitors to the lugs without danger of also soldering the nuts in place.



Fig. 3 Solder lug is shaped to fit one-quarter way around the brass tubing.

Two small grooves are now cut 180 degrees apart for the total length of the polyethelyne insulation. A small wood carving gouge or carefully manipulated razor blade can be used for this purpose. These grooves provide a space for the enameled copper wire which is held in place when assembling as shown in **Fig. 4.** Prior to this operation, the wire should be stretched and work-hardened by jerking it between two pairs of pliers. Be sure that the plane described by the two wires lies at right angles to the chassis on which the unit is mounted. This permits all resistors and diodes to have equal lead lengths.

When the inner assembly has been tugged and shoved into place within the brass tubing, the #22 wire ends are trimmed, stripped and soldered to their respective resistors and diodes. Much care should be exercised at this point to prevent melting the insulation or damaging the near zero-length component leads.



Fig. 4 Assembling the inner components into the brass tubing.

Application

A completed sensing unit for the VSWR meter is shown mounted on a typical chassis in **Fig. 5.** It will be noted that no conventional box or housing is used because the total outside of the unit is at ground rf and dc potential, save for the component connections at each end. By mounting the bypass capacitor in the chassis, the low-voltage rectified current fed to the meter switch is



Fig. 2 Component parts used in making the VSWR sensing unit.



Fig. 5 Finished VSWR sensing unit mounted on a typical chassis.

isolated from high-power rf on the other side of the chassis. It can readily be seen that the finished sensing unit occupies no more space than would be used by a coaxial lead running from an antenna relay to the antenna connector on the chassis.

A further refinement is shown in **Fig. 6.** Complete isolation of the high-power rf is provided by the coaxial hood. Impedance discontinuity is also minimized by use of the hood, which was designed for this purpose and is readily available.

Length of sensor

The dimensions given for the length of the sensor element, including its outer tubing and inner conductor, are not critical. They are, however, directly related to the power of the transmitter with which the VSWR meter is used. For example, with a one kilowatt high-frequency CW transmitter and a 0-1 milliammeter as the indicating meter, the length of the sensor can be as short as 2-3 inches. A sensor which is constructed approximately 7 inches long, as illustrated in this article, will work fine with the same meter on a 25-200 watt high frequency transmitter. If meters with higher current ratings are used, a longer sensor is required, and, conversely, a more sensitive meter would provide adequate full-scale deflection with a shorter sensor element. Obviously, it is impracticable to vary the length of the sensor element in order to vary the sensitivity of the VSWR meter as a whole. It is for this reason that the adjusting resistor is provided in series with the meter. For VHF use, the sensor can be shorter.

All that has been said above can be depicted graphically. **Fig. 7** shows the generalized relationship between the sensor length and transmitter power with which it is used. The two curves represent different meter sensitivities. A 0-1 milliammeter offers a good compromise. With a 5-7 inch long sensor and the proper series resistor, all powers normally encountered in amateur work can be handled. However, if space requirements so dictate, a shorter sensor unit can be employed with some small sacrifice in accuracy.

Terminating resistor

Small variations in mechanical construction and lead dress will have an effect on the value of the terminating resistors, R_1 and R_2. Also, a carbon resistor does not display the same reactance at high frequencies as its measured resistance at dc. The value of the 33-ohm resistor was therefore determined empirically.

To verify the proper value of the terminating resistors, the test set-up shown in **Fig. 8** is used. A radio-frequency source of approximately 10 to 20 watts is required. A transmitter exciter stage operating on the 10-meter band is preferred for this purpose. Ten meters, or even fifteen meters, will provide better accuracy than one of the lower frequency bands. A dummy load is also required. This load must be capable of dissipating the power of the radio-frequency source used in making the test. Three or four 2-watt carbon resistors of the proper value in parallel to provide 52 ohms will suffice if the power is not left on continuously.

In making the test, the selector switch is first placed in the "forward" position. With power applied, immediately adjust the sensitivity control so that the meter reads full scale. Upon switching to the "reverse" position, the meter should read near zero and be at or below the 1:1 calibration point on the meter scale. Several resistors may be substituted until the proper value is found. The important thing to remember is that both of the resistors should be simultaneously substituted and that they must be as near identical as possible as measured on a reasonably good ohmeter. Lead lengths should also be as short as possible and of identical length.



Fig. 6 Recommended chassis connection for output of VSWR meter sensing unit.



Fig. 8 Test set-up for verifying the proper value of the terminating resistors which are a part of the sensor unit. The value of the dummy load should match the characteristic impedance of the sensor unit and have a total wattage rating nearly equal to the source power.



Fig. 7 The approximate relationship between sensor length and transmitter power is shown for two commonly used meter movements. Other meter values may be used as discussed in the text.



Fig. 9 Full-size photomaster of the VSWR meter dial. A multi-purpose meter was used in the author's transmitter so that the grid and plate currents could also be read on the upper scale.

The dial scale

Using the standard formula for calculating VSWR, it is possible to calibrate the meter face as follows:

$$\text{VSWR} = \frac{\text{forward} + \text{reverse}}{\text{forward} - \text{reverse}}$$

Fig. 9 is a full-scale illustration of a meter face used with the *VSWR Supreme*. This scale fits the Triplett Model 327, as well as a number of other meters of the same size category. A word of caution—don't assume that the scale calibration, or linearity will be the same for all makes of meters. The individual meter movement selected should be checked by using the above formula and marking off radials representing 4-5 different VSWR values. With the scale from your meter at the center of an oversized radial(s) drawing, it is possible to verify the angular placement of each VSWR calibration point.

The *VSWR Supreme* is truly a novel approach to an old standby. Using the construction methods outlined in this article, it is possible to fabricate the sensor unit so that it occupies the smallest possible space. This sensor can now be built into a transmitter and take up no more room than the coaxial lead which it replaces.

A SIMPLE VHF SWR METER

John Schultz W2EEY/K3EZ

I recently wanted to do some work on a 2 meter antenna and since no other instrument was handy, started to use an SWR meter manufactured for use on the high frequency bands. After some erratic results, it was decided to check the SWR meter accuracy on 2 meters with some carbon resistors to simulate different SWR's. The results readily confirmed that the SWR meter was useless at VHF unless one didn't care whether a SWR was really 1:2 or 1:5. Rather than purchase another SWR meter, it was decided to construct one that would render reasonable results, within 10% accuracy or so, on the VHF bands, particularly 144 and 220 MHz.

There is nothing basically new in the circuitry of the SWR meter to be described. What is different about it is that it utilizes a particularly simple and inexpensive method of construction that yields reasonable results. It can be constructed as a completely self-contained SWR meter or only the pickup element can be constructed and used with an external meter. The circuitry as shown here for the meter utilizes two meter movements so one can read forward and reflected power simultaneously and avoid the annoyance of having a forward-reflected switch arrangement for a single meter.



The heart of the SWR meter is a carefully constructed pickup element. Details of construction are discussed in the text but the photo shows how closely the diodes and terminating resistors must be soldered to the pickup element.

Pickup Element

The "heart" of any SWR meter of the reflectometer type is the pickup element. Many elaborate forms for such elements have been devised which involve complicated mechanical construction. Such complicated construction does become necessary if very accurate results are desired and if the meter is to maintain linearity over a very wide frequency range. However, over a smaller frequency range and with some minor sacrifice in accuracy, the construction of a pickup element can be greatly simplified. Basically, the pickup element should not cause any discontinuity in the transmission line section in which it is inserted but yet be long enough so enough voltage can be picked up in both the forward and reflected directions to make the meter usable with even low power transmitters.



Fig. 1. SWR meter circuit. Two identical meters should be used (current range and internal resistance).

The pickup element I devised is shown in the photo. It is a 2-7/8" long piece of alternate grid pre-punched perf-board stock. The board is about 7/16" wide and within this width contained 4 separate copper strips spaced about 1/16" or less apart. The center two strips are soldered together to act as the inner conductor continuation of a coaxial line section. To solder the two inner strips together tack solder a bare piece of hookup wire between the two strips and then cover the entire two strips with solder.

Without the use of pickup wire, it will be nearly impossible to develop a smooth solder flow between the strip. Each outer strip acts as a pickup element for the SWR meter circuit shown in Fig. 1. The terminating resistor and diode are soldered to each end of the outer strip as shown in the photo and with minimum excess lead length to the strip. The use of a heat sink on the diode is necessary to prevent damage during soldering.

Mounting The Pickup Element

The pickup element made from the board stock is mounted between two approximately spaced SO-239 chassis connectors. The center strip of the board is soldered at each end to the center post of the SO-239 connector. The terminating resistor at each end is grounded as directly as possible to a ground lug held in place by one screw of the SO-239 mounting hardware. These details are shown in Fig. 2. It is important that the terminating resistor be grounded in this manner with minimum lead length. The enclosure in which the pickup element is contained should just be wide enough to accommodate the SO 239 connectors so that when the enclosure is secured together, the pickup element is boxed in by a metal surface on each side except directly above it. Many chassis or enclosure types are suitable for this purpose and the overall size of the enclosure will depend, of course, on the meter used and sensitivity control placement. These details are not covered here because they can be made as desired. They will not affect the basic accuracy of the meter as long as the pickup element is properly mounted and enclosed. The bypassing of the pickup rectifier diodes must also be done with as short leads as possible on the bypass capacitor. As shown in Fig. 2, a two lug terminal strip (one lug grounded) mounted on the side wall of the enclosure immediately at the cathode end of the diode will perform this task very well. The length of the IN34A diodes is such that the bypass capacitor cannot be connected to the same ground lug used for the terminating resistor. The leads on the capacitor would be too long and it will be ineffective.



Fig. 2. Center strip of vector board is soldered to center post of SO-239. Other components are mounted at each end of board as shown (only one end shown here).

Operation and Results

The dual meter circuit of Fig. 1 reads forward and reflected power simultaneously. The sensitivity potentiometer is set to read full scale on the forward meter and the SWR read directly from the reflected meter. The latter meter can be calibrated for various SWR's by the use of small carbon resistors (100Ω to simulate a 1:2 SWR in a 50Ω line, etc.). Usually, it is only necessary to calibrate the reflected meter for SWR's of 1.5, 2 and 3 at the frequency of interest. Calibrated in this manner, the accuracy of measurement will be roughly 10% and is certainly good enough for most general antenna work. A particularly nice meter display can be made if one can find a two meter movement in one enclosure. I purchased a surplus stereo VU meter which had dual 200 μA movements and used it in the SWR meter.

The sensitivity of the SWR meter is such that transceivers of the 1-2 watt output class can easily be used with it on the VHF bands. The basic meter, of course, can also be used on the lower frequency bands as well and it will retain good accuracy. The only problem on the lower frequency bands is that the pickup strips are so short that more transmitter power has to be used to activate the meter than is usually convenient to use during antenna experiments. No exact tests were made but probably 70–100 watts would be needed to use the meter on as low a band as 80 meters. The meter was used and checked, however, on 40 meters. The accuracy of the meter remained very good and full scale deflection of the forward level meter required a power level of 60 watts. Being an in-line type meter, it can be left permanently in line when used on any band with a minimum of loss.

DIRECTIONAL COUPLER AND VSWR BRIDGE FOR VHF AND UHF

Bob Kolb WA6SXC

The aerospace industry has fostered the development of many new components and materials. Hams, being the kind of people they are, are quick to see practical applications for these materials that never occur to design engineers. I have often heard the criticism that it is impractical to publish articles or design ham gear with these new or expensive materials, because most OM's don't have access to them. Yet I've often been dismayed when I learn of an application for a piece of surplus equipment after it is no longer available. For this reason I feel that we should publish any application that is practical regardless of how immediately it can be used. Sooner or later, the material will show up on the surplus market and then we'll know what use can be made of it.

Reliable test equipment for the VHF-UHF bands is difficult to come by on a low budget. The literature is full of "relative" measuring devices but few pieces of homebrew gear are engineered for repeatable performance. Several directional couplers have been built according to the description in this article and each has measured to within ±.5 dB of the designed value. This is due in part to the mechanical rigidity and close tolerance of RG-141 "coaxitube." No special tools are required outside of a cheap pair of vernier calipers. The tools used to make the original coupler were an Xacto knife, file, soldering gun, vernier calipers and a vise. Don't let the calipers scare you. If you're not after a closely calibrated device they may be omitted.



Fig. 1. A typical directional coupler. This device is the heart of a VSWR bridge, and can also be used for many other applications.

The design goal was a directional coupler with about 30 dB directivity in the passband with a low insertion loss. Each milliwatt measured at the coupling arm equals one watt through the main line. Such a device is the heart of a good quality VSWR Bridge. The measured values were 30.3 dB coupling and 38 dB directivity at 432 MHz. Data presented in the graph was taken using HP608C and 614A signal generators and a General Microwave R. F. Power Meter. The measured insertion loss was 0.2 dB.

Resolution of the smallest possible VSWR is limited by directivity. Few of the handbook VSWR bridges or the low cost type attractive to the CB trade achieve as much as 20 dB directivity. Thus the minimum discernable VSWR is approximately 1.7:1. With 38 dB directivity, 1.02:1 VSWR's can be accurately measured.

Directivity may be defined as the isolation of arm D from arm A, over and above the coupling as shown in the **Fig. 1.** Coupling is achieved by removing part of the jacket between adjacent coax conductors. If the input is at arm A, incident power can be sampled 30 dB down at arm C but appears −68 dB at arm D. Reflected power entering arm B is sampled −30 dB at arm D while at arm C it is −68 dB. It stands to reason if the directivity is low, one cannot tell with certainty if he is measuring incident or reflected power. Port D may be used as the dc return for a detector at port C and vice versa.

This device will have its fundamental passband where the length exposed between the two lines is $\lambda/4\sqrt{\epsilon_r}$. It will also have a passboard at $(2n - 1)\ \lambda/4\sqrt{\epsilon_r}$ or at three, five, seven, etc., times the frequency for which it is a quarter wave. Hence a coupler designed at 432 MHz is usable at 1296 MHz.

This coupler has also been used to measure relative power and modulation at 2 meters where its coupling factor for incident power is approximately −40 dB but the directivity is poor, hence arm D must be terminated in 50 ohms. It's a real aid for tune up and will give a good indication of increased power with AM modulation right in the r.f. line. RG141 will handle 500 watts of rf up to 2000 MHz.



This UHF directional coupler is very simple to make, yet offers excellent performance on the 70 and 23 cm bands.



Fig. 2. Details of the construction of the UHF directional coupler.

The formula for determining coupling length is

$$\frac{c}{4 f_0 \sqrt{\epsilon_r}} = \frac{\lambda c}{4\sqrt{\epsilon_r}} \text{ or } \frac{300 \times 10^8 \text{ cm}}{4 \times f_0 \times \sqrt{2.1} \times 2.54 \text{ cm/in}}$$

$$= \frac{\lambda c \text{ inches}}{4\sqrt{\epsilon_r}}$$

$$\sqrt{\epsilon_r} \text{ for Teflon} = \sqrt{2.1} = 1.449$$

From these calculations $\frac{\lambda \text{coupling}}{4}$ at 432 MHz is 4.73 inches. With an Xacto knife cut two pieces of line 8.73 inches long and carefully bend them so that they form the shape shown in **Fig. 2A.**

Clamp the bent coax into the vise and file away the copper jacket taking care that the filed surface is smooth and flat. A belt or stationery disc sander works well too. A cross section of the filed piece should look like **Fig. 2B.** Next fit the two pieces together so that a cross section would look like a figure 8 and secure in a vise. Heat with a soldering gun only. Do not use a torch. Avoid excessive heating. Flow solder between the two lines as shown in **Fig. 2C.** The "arms" can now be bent into any convenient configuration provided enough allowance is made at the ends for connector assembly. A good rule to follow is a minimum bend radius of half an inch although a quarter inch radius is permissible. The arms should be approximately two inches long.



Fig. 3. Use of Kings A-51-05-11 adapter for using GR-141 with standard BNC connectors.

RG 141 has the same cross section as RG 58/U *without* the vinyl jacket therefore any connector that will accept RG 58/U can be used on RG 141 provided a sleeve is made up to make a snug fit in the clamping nut. A special adaptor is made by Kings for this purpose and sells for 45 cents. The connector assembly is shown in **Fig. 3.** Three RG 88E/U and one RG 89C/U connectors were used on the coupler shown in the photo.

Fig. 4 gives the measured directivity and coupling for this type of directional coupler at both 70 and 23 cm. You can see that performance is quite satisfactory.

Fig. 5 lists a number of applications for a directional coupler. The detectors in the measuring instruments should be suitable for use at 500 or 1300 MHz.



Fig. 4. Coupling and directivity for a directional coupler similar to the one discussed in the text. This device used a coupling wavelength of 4.635 inches rather than the 4.73 inches specified in the text. The only effect of the longer wavelength is to center the curves on 432MHz instead of about 500 MHz.



Fig. 5. Applications of the directional coupler described in the text. Unlike most pieces of ham-made test equipment, this one is good at 450 and even 1300 MHz.

A SLOTTED LINE FOR 1250 MHz

Silas Smith WA8CHD

The SWR bridge is a very useful—and sometimes badly neglected—tool. Especially on 1250 mc with only two or three watts of power, you should measure your SWR and do something about it if necessary. I recently joined the 23 cm boys, though I have only worked 1234 mc so far. My first attempt to communicate with W8VKQ on the other end failed but after two evenings of diligent work with a meagre amount of test equipment we made contact. It would have been a lot easier with test equipment good in the 1250 mc range since most hams are not equipped to measure frequency and adjust their rigs at these frequencies.

After that experience, I made the slotted line indicator described in this article. The cost is next to nothing and it's easy to build, but it does a good job. The unit is built around a one inch thin wall copper tube 10¼" long (Fig. 1). This tube has a ⅛" slot cut lengthwise for 7½", about ¾ wavelength at 1250 mc. This is long enough to get a fair sampling of the standing wave or null points.

Three other pieces of 1" copper pipe are needed. Two are 5/16" long and one is 1⅜" long. The two 5/16" pieces each have ¼" cut out and are reshaped to fit inside the 1" tube. These two pieces were each soldered to 1/16" plates as in the detail in **Fig. 1.** This process makes two cup-like structures which should


SEE DETAIL "A"
R
μA
DIODE
SHORTED STUB
PROBE
3/8" COPPER TUBING
$\frac{\lambda}{4}$
1/16" COPPER TUBING
INSULATOR
1" TUBE
BNC
LINE
SEE DETAIL "B"
BNC
PROBE CARRIAGE
1/8" HOLE
1" TUBE
1⅜"
PROBE CARRIAGE
10¼"
7½" × ⅛" SLOT
1" TUBE
TO FIT DIODE
1/4" TUBE
WRAP MICA AROUND HOLDER TO FORM BY-PASS CAPACITOR
PRONG SOCKET FROM OCTAL TUBE
1/16" TUBE
DETAIL "A"
LINE
LINE
SNIP WITH TIN-SNIPS
FOLD INTO CONE SHAPE - SOLDER - DRESS WITH FILE
DETAIL "B"
BNC CONNECTOR
1" TUBE
5/16"
COMPLETE END SECTION
1/16" PLATE
REMOVE 1/4" TO FIT INSIDE TUBE OF FIG. 1
HOLES TO FIT CONNECTOR

Fig. 1. The slotted coaxial line and probe for 1215 to 1300 mc described in this article.

fit within the end of the 1" pipe. Drill nine holes in each cup: four holes for attaching the cup to the slotted line, four to fit the BNC connector mounting plate and one ⅜" hole to pass the main body of the connector. File two notches for the connector ears. You can fasten the cups to the slotted tube with small sheet metal screws, threaded holes or nuts soldered to the back of the holes.

The 1" x 1⅜" piece of pipe is for the probe carriage. It is cut lengthwise on one side, slipped over the 1" tube, centered, and a ⅛" hole drilled through it over the slot in the 1" tube.

The probe is built from ⅜" and ⅛" brass tubing from your hobby shop. At the probe end is an insulator from a coax fitting and on the other end is a jack made from an octal tube socket. A small piece of ¼" brass tubing is used to make the diode socket (see detail A). A piece of 22 gauge wire is inserted in the probe end of the 1/16" tubing and soldered. A 1N21 diode works very well.

Use **Fig. 2** to choose the proper size for the line in the center. Each end of this line should be tapered and soldered to the coax fitting as in detail B. The center conductor should be 7/16" for 50 ohms or 5/16" for 73 ohms.

The meter used should have a range that permits a full scale reading and should be calibrated with some scale.

Uses: Measuring frequency

Frequency can be measured with the slotted line in two ways: the distance between null points at one half wavelength ($\lambda/2$) or the distance between peaks. See **Fig. 3**. Measuring between the nulls is preferable since the peaks are very broad. If your line is flat, the peaks and nulls may be very small, so you may have to induce a mismatch in the line. Likewise, you may have to induce a mismatch to get the two nulls to fall within the 7½" of the line. The easiest way to induce a mismatch is a short in the line.

Measure the distance between the nulls carefully with a centimeter rule. Twice this distance divided into 30,000 will give you your frequency in megacycles. It would be a good idea to check this against a standard or at least avoid operating too close to the edge of the band.



Fig. 2. Ratio of outer tube to inner line for various impedances.

Measuring VSWR

Measuring voltage standing wave ratio (VSWR) with the slotted line is easy, too. We are looking for a ratio of E_{min}, the minimum voltage on the line, and E_{max}. The ratio:

$$\frac{E_{max}}{E_{min}} = \text{VSWR}$$

However, there is a slight complication of vectors in E_{max} and E_{min}, so that to find them, you must first determine the highest voltage read on the meter, E_1 and the lowest voltage read on the meter, E_2 with the same setting of the shunt resistor, as the probe carriage is slid along the line. Now, $E_{max} = E_1 + E_2$ and $E_{min} = E_1 - E_2$ so that

$$\text{VSWR} = \frac{E_1 + E_2}{E_1 - E_2}$$

An even simpler method is to set the meter to full scale (100) at the highest reading, and reading the VSWR directly from **Fig. 5**.


GENERATOR
SLOTTED LINE
LOAD
$\frac{\lambda}{2}$
STANDING WAVE
$\frac{\lambda}{2}$
GENERATOR
SLOTTED LINE
LOAD
FORWARD WAVE
REFLECTED WAVE

Fig. 3, Left. Measuring frequency. Fig. 4, Right. Measuring VSWR.


VSWR
1.1
1.22
1.35
1.5
1.85
2.33
3.0
0
10
20
30
40
50
60
70
80
90
100
100 POINT SCALE
REFERENCE POINT WITHIN SLOTTED LINE
REFLECTED
SHORT
OPEN
LOAD POINT

Fig. 5, Left. VSWR scale. Fig. 6, Right. Impedance measurements.

Impedance measurements

It's a little harder to measure impedance, but even it's not bad if you do it step by step. First, consider the high impedance on your line when your antenna is open or shorted. Perhaps you don't think of it as a change in impedance. This is what we are looking for. Remember that there is a definite relationship between impedance and frequency. **Fig. 6** shows the voltage relationship between a short and open. On a short set the probe for a null point, usually the first null from load end of the slotted line. This will be our reference point. You will note that when the load point is open there is a shift of 90° or a quarter wavelength either side of the reference point. This adds up to one half wavelength. Any impedance between infinity and zero ohms will lie somewhere along the half wavelength of the line. It will be noted that an open is equidistant from the reference point toward the generator and toward the load, however the line has moved toward the load (capacitive reactance). To measure this reactance, we replace the load that we measure with a short. We set our probe to the first minimum reading from the load end of the slotted line. Mark this spot with a scribe. This is our reference point. Now we remove the short and add our load under measurement. It will be noted that the voltage has moved upward. Move the probe toward the load. If the voltage goes down, you are heading in the right direction. If the voltage starts to go up change direction toward the generator. Move the probe as above to the new null point and note the direction that the probe has been moved.

Here's a step-by-step example. First, you'll need the frequency and wavelength, VSWR, direction of probe, distance between reference point and new null, and impedance of the slotted line.

Let's say as we measured the frequency, the distance between the null points was 12 cm. This is half the wavelength, so the wavelength is 24 cm. The frequency is 30000/24 or 1250 mc.

Let's say we read 80 as a maximum and 20 as a minimum on a point scale in measuring the VSWR:

$E_{max} = E_1 + E_2 = 80 + 20 = 100$
$E_{min} = E_1 - E_2 = 60$

$$\text{VSWR} = \frac{100}{60} = 1.66$$

Or set E_1 to 100 by adjustment of R, then E_2 would read 25 on the meter, a VSWR of 1.66 by **Fig. 5**.

As in **Fig. 6**, the probe was moved toward the load.

Let's assume the distance from the reference point to the new null was 2 cm. What part of a wavelength is 2 cm? Wavelength is 24 cm, so 2/24 = .083 wavelengths.

This is a movement of .083 wavelengths toward the load.



Fig. 7. Smith chart for determining impedance.

The slotted line used has an impedance of 50 ohms.

We are now ready to plot this information on the Smith chart (**Fig. 7**, better get out your magnifying glass).

Draw the VSWR circle at the prime center with a radius of 1.6.

Draw a line from .083 wavelength toward the load from the prime center.

At the intersection of the circle and line, follow the constant resistance circle to .74 and the capacitive reactance circle to .31. Our load impedance is then:

$Z_L = Z_o\ (.74 - .31j)$
$Z_L = 50\ (.74 - .31j)$
$Z_L = 37 - 15.5j$

Well, there are some of the things your slotted coax line can do besides telling you that you're on the air. A commercial version would cost $750. I guarantee that you'll get your dollar's worth out of this one as it costs less than $1 to build. I hope that it helps you get on 1250 mc.

SOME DIRECTIONAL WATTMETERS AND A NOVEL VSWR METER

P. G. Martin G3PDM

Most conventional reflectometers cannot be used for accurate power measurement because their sensitivities are frequency dependent. This is due to the use of combinations of reactance and resistance in the sampling circuits which detect the transmission line current and voltage.

This basic problem can be solved by the use of conventional lumped components instead of the distributed parameters of a transmission line. The line voltage can be sampled by two resistors or two capacitors used as a voltage divider, rather than one resistor and some distributed capacitance. The line current can be monitored by a properly designed current transformer instead of an inductance and resistance. High frequency current transformers consist of primary and secondary windings on a ferrite or iron dust toroidal core, with a low value of load resistance across the secondary winding.

All SWR bridges and directional wattmeters need to generate two dc voltages proportional to the forward and reflected voltages or currents of the transmission line. To achieve this one has either the current detector or the voltage detector providing two antiphase signals so that addition and subtraction can be performed.

A Frequency-Independent Directional Wattmeter

M. B. Allenson G3TGD, has designed a wattmeter using the above principles, where the low resistance in the current transformer secondary circuit is split into two equal parts. The center connection is taken to the voltage sampling point so that sum and difference voltages are available at the ends of the transformer secondary winding, see Fig. 1.

With two meters, this circuit can be used as a versatile calibrated directional wattmeter over the freqnecy range 100 kHz to 70 MHz, with an accuracy of about 10 per cent. Precise calculations of SWR and transmitter efficiency can be made.



Fig. 1. Circuit of the basic frequency-dependent directional wattmeter due to G3TGD. The two meters indicate forward and reflected powers.

Maximum sensitivity with a 50 μA meter is less than five milliwatts, but with the multiplier resistors specified in Fig. 1, full scale deflection corresponds to power of 1, 10, 100 and 1000 watts. Calibration is non-linear, because the instrument samples voltage, and power is proportional to voltage squared.



Fig. 2. Calibration curves for the instrument described in Fig. 1.



Fig. 3. Linear and logarithmic scales. The inherent advantages of the logarithmic form are immediately obvious.

Unfortunately, two transmission line impedances are in common use in coaxial systems: 50Ω and 75Ω. As it is not possible to design instruments whose sensitivities are independent of line impedance, some component values must depend on the impedance in use. For simplicity, only one of the voltage driver resistors need be changed, but instrument calibration will be different. By changing the current transformer resistors as well as one of the voltage divider resistors, the calibration is the same for both line impedances. This technique has been adopted here, and the calibration curves in Fig. 2, are correct for 50 or 75Ω lines provided the resistor values in Table I are used.

The Logarithmic Wattmeter

The basic instrument can be simplified by including a logarithmic network so that the power range switch is redundant and a single meter scale can be used for powers from, say, one watt to 1000 watts. A logarithmic scale has the 1, 10, 100 and 1000 watt points equally spaced (see Fig. 3).

The advantage of a logarithmic instrument is that one can measure very low reflected powers and very high forward powers simultaneously with the same percentage accuracy, without having to switch meter ranges.

It is simple to add a reasonably accurate *wide-range* logarithmic network to the meter in Fig. 1 (see Fig. 5). The basis of its



Fig. 4. Smoothed experimental plot of the current /voltage characteristic of a 1N4002 silicon junction diode, showing its logarithmic properties.

operation is that the voltage dropped across a forward-biased p-n junction diode is proportional to the logarithm of the current passing through it (see Fig. 4). To reduce the potential dynamic range of the circuit, a relatively insensitive meter is used, and a small resistance is added in series with the logarithmic diode to restore a logarithmic form to the scale (see Fig. 6).



Fig. 5. Basic wide-range logarithmic converter.

An experimental logarithmic wattmeter is shown in Fig. 7. Figure 8 gives the calibration scale for 50 or 75Ω lines, provided the correct resistors are used (Table I).

A Direct-Reading SWR Meter

A particularly useful device would be an instrument giving a direct measurement of the standing wave ratio on a transmission line, independent of the absolute power levels or the frequency in use. Such an instrument, with its single meter, would be ideal for incorporation into transmitters and transceivers (especially with the physically small sampling circuits associated with it).

The swr can be expressed in terms of the forward and reflected voltages according to:

$$\mathrm{swr} = \frac{E_f + E_r}{E_f - E_r} \qquad (1)$$

We wish to generate this function electronically, so that outputs of the two detectors can be used to generate a meter current proportional to SWR. This would be rather tedious, though not impossible.

Conveniently, manipulation of equation (1) shows that:

$$\frac{E_f}{E_r} = \frac{\mathrm{SWR} + 1}{\mathrm{SWR} - 1} \qquad (2)$$

which although not proportional to SWR, is a mathematical function of it only. Electronic division of E_f by E_r is easily done by taking logarithms and subtracting. That is:

$$\log \frac{E_f}{E_r} = \log E_f - \log E_r$$

Table I

	Ω	Ω
Line impedance	50	75
R3 and R4	27	33
R2	220	180

Values for R2, R3 and R4 to be used in 50 and 75Ω transmission lines.

In Fig. 9, the two silicon diode voltages are proportional to the logarithms of their currents, which in turn are proportional to the forward and reflected voltages. The two diode voltages can be subtracted directly by connecting a meter between them, rather than from each one to chassis.



Fig. 6. Circuit of the logarithmic directional wattmeter. D3 and D4 are matched (see text).

The meter cannot be calibrated linearly in SWR, because of equation (2), and because the circuit does not take anti-logarithms after subtracting the logarithms. The outcome of this is beneficial: the SWR meter is increasingly sensitive as the standing wave ratio approaches 1:1. This is where one wants most sensitivity: to make the final adjustments to aerial arrays, to measure the variations in SWR over a band, and so on. Fig. 10, shows a calibration curve for SWR meters. Naturally the meter sensitivity cannot be completely independent of the power level in use. Accuracy falls when the reflected power is less than about half a watt (this corresponds to an SWR of 1.05:1 when the forward power is 1 kW).



Fig. 7. An experimental logarithmic wattmeter.

A differential amplifier could be added to the circuit of Fig. 9, to enable a less sensitive meter to be used.



Fig. 8. Calibration curve for logarithmic wattmeters.

Construction of the Instruments

Layout of the sampling circuits is fairly critical, see Fig. 11. The input and output sockets should be set a few inches apart, and connected together with a short length of coaxial cable. The coax braid must be grounded at one end only, so that it acts as an electrostatic screen between the primary and secondary windings of the toroidal transformer. Twelve turns of 24 AWG enamelled wire, equally spaced around the circumference of the ring, form the secondary winding. The primary is formed by simply threading the ring onto the coax.

A suitable ferrite ring is the Mullard FX1596, made in England, although other types are suitable. The FX1596 has an outside diameter of half an inch, and is designed for wideband rf applications between 5 and 20 MHz. The main requirement is that the ferrite material should maintain a high permeability over the frequency range in use.

Other components in the sampling circuits should have the shortest possible leads. R1, R2 and R must be non-inductive solid carbon types: for high power levels (about 100 watts) R1 should consist of two or three 2 watt carbon resistors in parallel. VR1 should be a miniature skeleton potentiometer to keep stray reactance to a minimum, although it may be dispensed with by trying various fixed resistors for R2 until the reflected indication under matched conditions is zero.



Fig. 9. Complete circuit for a power-independent, frequency-independent direct-reading SWR meter.

The detector diodes need to be matched for similar voltage drop, using the circuit in Fig. 12. Point contact germanium types with a PIV rating of 80 volts or so are recommended.

Logarithmic diodes should be modern medium-current silicon junction types, such as conventional rectifier diodes. The 1N4002 is specially recommended for its good logarithmic properties. Log diodes should also be matched with the circuit in Fig. 12.

The 0.01 μF decoupling capacitors should be a disc ceramic type.

In designing a toroidal transformer different to that specified, several factors should be borne in mind. As the number of secondary turns increases, the self-capacitance rises and causes the response to fall at high



Fig. 10. Calibration curve for SWR meters of the type described in Fig. 9.

frequencies. Failure of this nature causes the reflected power indication to rise; in other words the directivity of the instrument falls. If the 27Ω resistors are raised appreciably in value, the instruments will eventually become frequency sensitive.

The ratio of the voltage sampling resistors (R1 and R2) in the HF designs is determined by the sensitivity of the current sensing circuit, and the two sampling voltages must be equal in magnitude under matched conditions. VR1 provides fine adjustment of the ratio. Absolute values of the resistors can be varied considerably, bearing in mind that as their values increase the stray capacitance across them may need to be compensated for.

Useful Equations

Let the line current be I amps, the line voltage be V volts, and the characteristic impedance of the transmission line be Z_o. Then $V = IZ_o$.

If the current transformer has a ratio of 1:n, and each of the resistors in its secondary circuit has a value of RΩ, then the rf voltage across each of them is given by:

$$V_{(i)} = \frac{IR}{n} \qquad (3)$$

The voltage detector output is obviously

$$V_{(v)} = \frac{VR_2}{R_1 + R_2} = \frac{R_2}{R_1 + R_2}\, IZ_o$$

Which is, to a good approximation,

$$V_{(v)} = \frac{R_2}{R_1}\, IZ_o \qquad (4)$$



Fig. 11. Photograph showing layout of sampling circuits used in an experimental swr meter.

The main design equation for all the HF instruments is therefore:

$$R_2 = \frac{R.R_1}{n.Z_o}$$

where the value for R2 includes the effect of VR1, if fitted.

The dissipation of some of the components specified is quite high. For those planning different circuits, the following equations express the dissipation of R1 and the current transformer resistors R:

$$W_{(R1)} = \frac{Z_o.W}{R_1} \quad \text{watts,}$$

where W is the transmitter output power.

$$W_{(R)} = \frac{W.r}{n2.Z_o} \quad \text{watts.}$$

In the instruments described, $W_{(R1)}$ is about 5 watts, and $W_{(R)}$ 2 watts for a transmitter power of 500 watts.

Calibration

If any of the instruments are built exactly as described, and used in systems of the correct impedance, the calibration given in Figs. 2, 8 and 10 will be sufficiently accurate for most purposes. For those designing their own circuits, the following procedure is recommended.

Test equipment needed includes a high power rf source (a transmitter) and an rf voltmeter. The instruments can be calibrated with less accuracy without the rf voltmeter. The wattmeters are calibrated by feeding power through the meter into an appropriate dummy load (50 or 75Ω). VR1 is set for minimum reflected power indication, and the power scale is marked according to the rf voltage appearing across the load. If an rf voltmeter is not available, a peak-reading type can be made with a diode, capacitor and dc voltmeter. As the detector output is equal to the peak rf voltage applied to it, equation (4) leads to:

$$V_{(det)} = 2.8\ V\ \frac{R_2}{R_1} = 2.8\sqrt{WZ_o\ \frac{R_2}{R_1}}$$

It would be difficult for most amateurs to obtain sufficient high power carbon resistors to calibrate an SWR meter by means of deliberate mismatching. An indirect method is therefore recommended.



Fig. 12. Hookup circuit for matching detector diodes for equal forward voltage drop, and silicon junction diodes for similar logarithmic properties. The meter should be as sensitive as possible (say 50 μA fsd), and should not deflect appreciably as the voltage is varied between zero and nine volts.



Fig. 13. Circuit used to calibrate SWR meters(see text).

Disconnect R5 and R6, Fig. 9, from the detectors, and connect them instead as shown in Fig. 13. One voltage is fixed at about 20 volts, and the other is varied between zero and 20 volts. The ratio of these voltages corresponds to a definite SWR which can be determined from equation (1). Before carrying out this procedure, however, VR2 should be set for full scale deflection of the meter under matched conditions at the highest power level to be used.

Conclusions

All of the instruments described in this article have been tested under actual operating conditions, on all amateur bands between 1.8 MHz and 30 MHz. Power levels used varied from 100 to 1200 watts. With the components specified, the instruments will sustain power levels well above the kilowatt level for periods of tens of seconds.

It is hoped that by introducing frequency independent directional wattmeters, one will be able to make useful comparisons of absolute power levels and accurate assessments of standing wave situations. The logarithmic scales are an added convenience, and the direct-reading SWR meter offers a saving in meters.

SWR BRIDGES USING ZERO-CENTER METERS

John Schultz W2EEY/K3EZ

The basic coaxial cable swr meter, which samples both the forward and reflected voltages on a transmission line, is an essential instrument in setting up an amateur station. Although a low transmission line swr in itself doesn't guarantee that an antenna system will work, knowing what the swr is remains an essential bit of information in evaluating the status of the transmitter/antenna interface.

The virtues of the usual coaxial line swr meter – economy and simple circuitry – are offset by the awkwardness involved in using the instrument: that is, switching back and forth between "forward" and "reflected" switch positions and adjusting a sensitivity control for sull-scale deflection in the forward position. This awkwardness of operation is partly relieved by dual-instrument swr meters so the forward/reflected switch is no longer necessary – but the cost of the instrument increases. The awkwardness of operation can be completely relieved by special dual movement meters with crossing pointers and/or special circuitry, but then the cost really soars.

Another approach is the usage of some different circuitry to detect the swr which can then activate a zero-center meter so one can peak up the antenna coupler, etc., for minimum swr on a transmission line with the same ease as one tunes an FM entertainment receiver for a zero-center reading on the discriminator meter. In the end analysis, practically no line is set up for any specific swr, but simply for the lowest swr that can be achieved. So, why not make the process as simple as possible? Circuitry to do this has actually been available for many years and was especially developed for use with the automatic servo-tuning of military transmitters. The zero output when tuning conditions were correct, and the plus or minus output when they were not, allowed, after sufficient power amplification, the activation of motors to tune transmitter PA task circuits, coupling circuits, etc. Now, with the economical availability of toroids and imported zero-center meters, zero-center swr type circuits can be applied to amateur usage and meet the criteria of being easy to construct and economical. They offer a real challenge to the conventional type of swr meter, especially when one is using a multiband antenna and tuner arrangement, or just leaves an swr meter in a transmission line to verify that the line swr is holding constant. In the former case, one usually knows the approximate transmitter/tuner settings on each band, and the swr meter is used to peak up the adjustments. Such peaking-up, as mentioned before in the case of an FM receiver, is certainly facilitated by just having to look at a zero-center meter. In the latter case, a zero-center meter will more readily reveal slight changes in transmission line swr from an established norm. Perhaps the only place where a conventional swr meter is still to be preferred is when one is dealing with experimental antennas where extreme swrs exist and a conventional swr meter can help to more quickly obtain "ballpark" antenna coupler or loading coil settings. The zero-center type circuits operate on a slightly different basis than the conventional swr meter circuits, and just a brief review of transmission line operation will be helpful to understand the different basis for the functioning of the two types.



Figure 1.



Figure 2.

If a transmission line is attempting to deliver power to a load, both voltage and current values exist along the line. If the antenna load impedance is resistive and equals that of the line impedance, all the power feed into the line reaches the antenna less any power loss in the line itself because of the line's inherent loss. If the load is not equal to the line impedance or reactive, part of the power the line tries to deliver is rejected by the load and reflected back along the line. This sets up standing waves of voltage and current which are not in phase with the original voltage and current waves the transmitter is trying to "pump" into the line.

Conventional swr meters sample a portion of the voltage or current wave traveling towards the load and a sample of that traveling back from the load. The relative amplitude of the two samples is the swr and, of course, the desired condition is that there be no reflected wave from the load. If there is no reflected power from the load, the line is often referred to as being "flat." This term is a bit misleading. Although the reflected power may be zero under matched conditions, the power flowing to the load via the line will still set up normal sine wave distributions of voltage and current along the line.

Another way to sense that the load is matched to the line is to determine first of all that the phase difference between the voltage and current on the line is zero and that the ratio of the in-phase voltage and current is correct for the impedance of the line being used. If there is no reactance present in the load, there will be no phase difference between voltage and current, as in any ac circuit feeding a resistive load. If the load is not only non-reactive but also of the correct resistance, the ratio of voltage and current on the line will have a definite relationship correct for a given line impedance. The zero-center meter circuits are designed to monitor both of these line conditions.

Practical Circuits

Two separate circuits are used to monitor the line conditions just described. One could switch a separate zero-center meter between the two line monitor circuits but with imported zero-center meters available for as low as $1.50, it is hardly worthwhile to do so. (A good source of the 100-0-100uA meters needed is Edlie Electronics, 2700 Hempstead Turnpike, Levittown NY 11756. Their meters with order number DA798 or DA792 cost only $1.50 but they have a $7.50 mail order minimum.) Also, for many installations, it is not necessary to use both circuits. For instance, in a home installation feeding a set of various fixed antennas, it would probably be of primary interest to have the impedance monitor circuit (voltage/current ratio). Once the antennas have been set up and operate satisfactorily, one would primarily just be interested to know that some impedance condition on the line has not changed. In a mobile installation, where some reactance cancelling L or C needs to be adjusted with frequency changes, it would be of prime interest to have the phase monitor circuit once the installation has been initially set up for a correct impedance match, and the reactance cancelling component only needs adjustment during actual operation.

Phase Monitor

Fig. 1 shows the circuit of the phase monitor. It is a basic discriminator circuit. The voltage on the transmission line to ground is sampled via R1. The current on the line induces a voltage in the windings on the toroid placed in the line which, of course, is 90° out of phase with the voltage sample. The voltage proportional to the line voltage is divided across R1 and R4 (C1 and C2 are rf bypass capacitors). The voltage proportional to line current (across the toroid winding) is divided between R2 and R3. Referenced to the center point of R2 and R3, these voltages are 180° out of phase with respect to each other and either one is 90° out of phase with respect to the voltage across R4. The voltages across R2 and R4 are rectified by D1 and, because of the diode polarity, produce a voltage with the polarity indicated across R5. Similarly, R3 and R4 and D2 produce a voltage of opposite polarity across R6. When the transmission line current and voltage are in phase, the voltages across R5 and R6 are equal and opposite, and the resultant voltage output which drives the meter is zero. For an out-of-phase condition, some output voltage exists whose magnitude indicates the amount of the phase difference and whose polarity would indicate whether the line voltage leads or lags the line current.

One could actually calibrate the output meter for different magnitudes and directions of phase difference, but this would be very tedious and not of real use for just checking the adjustment of a line for reactance cancellation. The only calibration that has to be checked is to excite the circuit into a resistive dummy load and to be sure that the zero-center feature works. If it does not, it indicates that some unbalance has been introduced during construction or some of the components (R2/R3 and R4/R5) are not closely enough matched. If the meter excursions off zero center become too violent with a high power transmitter, some additional resistance can be introduced in series with the meter to limit the maximum current flow.

Impedance Monitor

Fig. 2 shows the circuit of the impedance monitor, which is also a form of discriminator circuit. Samples of the transmission line voltage and current when they achieve the desired ratio produce an output voltage from the circuit which is zero. As in the previous circuit, a toroid placed around the center conductor of the transmission line develops by transformer action a voltage proportional to the line current. A sample of the line voltage to ground is taken via the variable capacitor C5. Unlike the previous circuit, both the sampled voltages are rectified, producing voltages across load resistors R3 and R4, without paying any attention to the phase differences between the sample voltages. It is only the amplitude of the sample voltages which determines the amplitude of the voltage across R4 (for the line voltage) or across R3 (for the line current). Because of the diode polarities, the voltages across R3 and R4 are of opposite polarity. They will cancel when equal, producing zero output voltage, and since C5 is variable, this condition can be set to occur at any desired line voltage to current ratio.

The difficulty with this circuit is that the sample voltages generated by the toroid transformers and the C5 coupling are frequency dependent. The rest of the components in the circuit (R1/C1 and R2/C2) are there to help eliminate the frequency sensitive output of the coupling elements over a reasonable range.

C5 is set with C1 and C2 at mid-range to provide a zero voltage output from the circuit on 20m when the line is terminated in a resistive load equal to the line impedance. Going to 10m, C2 is adjusted to restore balance and on 80m, C1 is used to restore balance. The adjustment has to be gone through several times before a good balance is achieved over the entire HF range. It would be possible to calibrate the meter with different value load resistors for different swrs. For high value loads, the meter would move off center in the opposite direction for low value. loads. But, such calibration would only hold true for non-reactive loads.

Construction

Many conventional swr bridge circuits have been described over the last year or two in amateur literature where a toroid transformer, rather than a parallel wire to the center conductor of a coaxial line, has been used as a pickup element. The construction of such units applies equally well to the circuits shown here. It is only the circuitry following the pickup element that is really different, plus the added R1 pickup in Fig. 1, or the C5 pickup in Fig. 2. Note that it doesn't matter on which side of the toroid these pickups are placed. However, as in any rf circuit, all leads must be kept as direct and as short as possible. The circuits shown are for the HF range, but by changing the toroid and values of the bypass capacitors, they can be extended, by experienced experimenters, into the VHF range.

Chapter II

How to Measure RF Impedance

THE ANTENNASCOPE – AN EFFECTIVE TOOL

W. R. Carruthers VE3CEA

There are two types of antennas, commercial and amateur. A commercial antenna is generally designed for one frequency, has many acres of ground around it, no obstructions and miles of heavy copper cable buried underground to provide an "effective" ground. These antennas work as designed – very well. The amateur antenna, on the other hand, is just that – an amateur design and construction.

This antenna is subject to all ills, roof tops, buildings, trees, TV masts, house electric wiring, telephone wires and what not. It's a wonder they work at all! But they can be made to work and thousands of amateurs make them work. They make them work by pruning or lengthening the feeder cable and by using an antenna coupler. These are always empirical steps, the "let's cut and try and see what happens" method. How much better it would be, and a time saver too, if we tested our antenna systems electrically and *knew* what was happening and then could take intelligent action to put the whole antenna system into resonance.

This fact is well known – an antenna can only accept power and radiate properly when it is operating at its resonant frequency. This is no problem for the commercial people who operate at one frequency. The amateur, however, wants to "roam the band" and may wish to operate over frequencies hundreds of thousands of cycles wide, even megacycles wide. How can he do this with a fixed antenna system? The answer is, he can't! But he can construct an antenna system for a certain frequency and take the penalty of reduced radiation when he moves far away from it. However this actually works very well, because each amateur has his own particular part of a band in which he likes to operate – and his friends tend to stay there too. On this particular spot, the amateur works diligently to "put out a good signal."

The question arises – how can we make sure our antenna system is radiating well at the particulaf frequency we wish to use? One answer is to use electrical test equipment to show us what is happening on the whole antenna system, which includes the antenna and the feed line.

One of the most useful devices for this purpose is the rf bridge, generally called the Antennascope. It is a simple device, inexpensive to construct and very effective in results. It is usually powered by a grid dip oscillator. Such bridges should be used at the junction of the feed line and the antenna and will show the resonant frequency of the antenna itself and the radiation resistance at the feed point.

Making such measurement up in the air is a difficult thing for the average amateur and impossible for those whose antennas are supported at the ends. If we are willing, however, to accept a small degradation in results, we can use the *rf* bridge at the station end if we have a half wave, or multiple of a half wave, feed cable. At every half wave point on a feeder cable the voltage and current vectors are in phase, which simply means that the electrical condition seen at the end of the cable is repeated every half wavelength in the cable. We can use the *rf* bridge then, at the station end of the feed line, if we are willing to agree that the results will not be 100% but reasonably close to it. The results will be affected by all the various factors that affect amateur antenna resonance and these effects may give us some peculiar results, but they can be overcome and the final results may be quite valuable to us.

Let me give you an example to illustrate what I'm talking about and to show you how effective the use of the *rf* bridge can be: –

A friend of mine constructed a 40 meter inverted V antenna, held at the feed point 40' up on his beam tower, 66' legs down to supports which held the ends about 8' off the ground. Feed line was 100' of Twin Amphenol cable, velocity factor .68. The antenna was difficult to feed, swr was high, radiation was poor. He asked me to have a look (electrical) at it. I took my grid dip meter, *rf* bridge and vtvm.

The first thing done was to check the feed line length. 1/2 wave length at 7.1 MHz was 492 x .68/7.1 or 47.1 feet. Two 1/2 wave lengths (to get into the station) would be 94.2 feet.

The first conclusion was that the feed line was 5.8 feet too long.

Next Test No. 1 was made using the *rf* bridge with results as shown in **Fig. 1**, the results being shown in table form and also plotted in graphical form.

It was obvious from this graph that the antenna system was resonating outside the



F MC	R OHMS
7.0	55
7.1	80
7.2	110
7.3	115

Fig. 1. 100' Feedline Test No. 1.



F MC	R OHMS
7.0	48
7.05	51
7.1	69
7.2	80
7.3	115

Fig. 2. 94.2' Feedline Test No. 2.

band as shown by the dotted lines. This test was repeated and the results were taken down to 6.4 MHz. They showed the system to be resonant at 6.6 MHz.

Test No. 2 was made next using the feed line cut to 94.2 feet. **Fig. 2** shows the results.

It was obvious the resonant point of the system was rising.

Test No. 3 was made next, cutting the feed line to 91.2 feet long. **Fig.** 3 shows the results.

F MC	R OHMS
7.0	43
7.1	46
7.2	76
7.3	81



Fig. 3. 91.2′ Feedline Test No. 3.

The resonant point was rising, but not far enough yet.

Test No. 4 was made using the feed line cut to 88.2 feet long. **Fig. 4** shows the results. It was obvious that we were very close to the resonant frequency of 7.1 MHz which my friend wished to use.

F MC	R OHMS
7.0	45
7.05	47
7.1	51
7.2	60
7.3	75



Fig. 4. 88.2′ Feedline Test No. 4.

Test No. 5 was with 85.2 feet in the feed line. **Fig.** 5 shows the results.

F MC	R OHMS
7.0	78
7.1	61
7.2	60
7.3	66



Fig. 5. 85.2′ Feedline Test No. 5.

Test No. 6 was with the transmitter (300 watts CW) and antenna coupler connected. There was no trouble in loading and no trouble in balancing the coupler to obtain an swr of 1 to 1 ratio.

The results on the air were interesting, 5/9+ reports to the Eastern half of the U. S. A., 5/8 reports to Germany etc. *Conclusion:* The results shown above are not precise, nor can they be expected to be precise. There are too many unknown factors entering the electrical picture, such as those which required a shortening of the feed line, in this example, to somewhat less than a half wave length. But the bridge showed us the overall picture and suggested what was required to be done. The on-the-air results show that it was giving us a good picture and a result that was very satisfactory for my friend's needs.

Why not construct an *rf* bridge and check you own antenna system? I suggest it will pay off and be very informative to you, showing you what your antenna system looks like electrically and what to do to bring your whole system to the resonant frequency you wish to obtain. . . . VE3CEA

HOW TO BUILD AN ANTENNASCOPE

Paul Franson WA1CCH

A type of simple bridge used for measuring antenna impedance is called the Antennascope, shown in Fig. 1. This bridge is designed for low power operation – a grid dip meter usually gives plenty of power. It should be built very compactly with short leads. The potentiometer should be of high quality; an Allen-Bradley Type J is fine. The bridge can be calibrated with regular composition resistors. Simply connect the resistors in turn to the antenna terminal and adjust the pot until the meter reading dips to zero. Then mark the value of the resistor by the pot pointer. In use, the meter reading will not null completely except for resistive loads, so it will not read zero for reactive antennas. Nevertheless, the minimum reading will occur at the approximate impedance reading. Remember that all antenna bridges should be used between the antenna and the transmission line.



Fig. 1. The Antennascope is a simple antenna impedance bridge. It should be constructed compactly for best high frequency use.

THE MARK III RF IMPEDANCE BRIDGE

Mark Cholewski W6CRT

NEED to measure the input impedance of that new beam? Or maybe to find out just what is the Q of the coils in your final? Or even to determine how much signal is being soaked up by your coax? If you ever want to do these, or any similar jobs, then the Mark III RF Impedance Bridge is the thing for you.

You can build it for a total cost of about $30 (exclusive of sheet metal) and, if you follow instructions closely, it will be accurate to closer than 10 percent throughout its operating range. Unlike the more common resistive-bridge and reflectometer methods of measuring impedance, the Mark III operates equally well at resonance or far away. It will measure both resistance and reactance present in resistors, capacitors, inductors, antennas, and transmission lines at any frequency between 2 and 30 mc.

Before we start into the actual construction of the Mark III, one thing must be emphasized. Accuracy can be assured only if the components, circuit, and parts layout are absolutely duplicated. The original instrument's calibration was obtained through tedious laboratory techniques. If you make any changes, the calibration curves will no longer apply. However, if instructions are followed to the letter you need have no worries about accuracy. A test model, built by W6BJU following these instructions, checked out to 2 percent accuracy at 2 mc and 10 percent at 30 mc.

Construction of the Mark III divides into three major sections: Preliminary metalwork, actual wiring, and calibration. Each will be described separately. Ready? Let's go!

Preliminary Metalwork

1. Cut, drill, and bend to shape from soft aluminum shields S1, S2, and S3 as shown in Figs. C1, C2, and C3.
2. Cut, drill, and tap plexiglas insulators I1, I2, and I3 from bulk rod stock as shown in Figs. C4 and C5. When tapping plexiglas, use water as lubricant.
3. Cut, drill, bend, and solder tubular shields S1A, S2A, and S3A as shown in Fig. C6. Copper or brass may be used; aluminum should be avoided because of solding difficulties.
4. Assemble shielded resistor assembly R2/S4 as shown in Fig. C7. The copper tubing must be drilled out to clear the body of R2. When soldering, hold the assembly in a vise to protect R2 from excessive heat.
5. Cut, drill, bend to shape, and solder box shields S1B, S2B, and S3B as shown in Fig. C8.
6. Drill S5 (a 3x4x6 LMB unpainted chassis box) as shown in Fig. C9.
7. Cut, drill, and bend to shape shield partition S5A as shown in Fig. C10.

Shielded Transformer

While classified under the "preliminary metalwork" section for reasons which will become obvious, construction of the shielded transformer is the most critical part of the entire project. Before proceeding, read and re-read steps 8 through 24 and be sure that you understand them fully. Take special care when soldering—three transformers were built for the original instrument before a non-shorted one was achieved.

8. Cut to length, drill, and tap transformer mounting insulator I4 from 5/16-inch plexiglas rod.

9. Cut and drill two bobbin-end washers as shown in Fig. C12 and solder them to a length of copper tube as also shown. Then cut halfway through the bobbin with a hacksaw.

10. Pull the shielding from an 18-inch length of RG58/U. Save 8 inches for step 19 and use the rest in step 11.

11. Solder one end of the 10-inch shielding into the U-shaped slot on the bobbin end, using an aluminum rod or small drill to keep the inside of the shielding open. It must pass



C1—Shield S1 (1 REQ), Mat'l Aluminum



C2—Shield S2 (1 REQ), Mat'l Aluminum



C4 — Insulators, Mat'l Plexglas rod
C5 — Insulator I3 (8 REQ), Mat'l Plexiglas rod



C3—Shield S3 (1 REQ), Mat'l Aluminum

No. 26 plastic-covered wire. Clean off all metal burrs and solder splatters.

12. Wind 48 turns of No. 26 plastic-covered hookup wire on the bobbin in three lays of 16 turns each. Solder the start of the winding at point A (see Fig. C12) and wind in the direction shown by the arrow.

13. The last turn will end at the shielding attached in step 11. Feed the free end of the wire into the shielding, draw the turns tight, and secure the winding with plastic tape.

14. Cut a piece of brass or copper shim stock as shown in Fig. C13 to a length which will wrap around the bobbin but will not allow the ends of the shim stock to touch each other.

15. Tin the shim stock along the edges.

16. Place the wound bobbin in a vise, wrap the shim stock around it, lining up the free ends of the shim with the slot cut in step 9, and solder the shim to the bobbin ends. Caution. *Do not overheat the winding; the plastic covering melts easily and a short is almost impossible to detect.*

17. Connect an SO-239 coax connector and UG-177/U hood to the shielded primary lead as shown in Fig. C15.

18. Wind one turn of ¼-inch diameter half-hard copper tubing around a 1-inch diameter form. Saw the tubing as shown by "phantom lines" in Fig. C14. Drill as shown in Fig. C14 and clean off all burrs.

19. Locate the 8-inch piece of shielding left over from step 10.

20. Using same technique as in step 11, solder one end of the shielding into the ⅛-inch hole. Clean off all solder splatter and burrs.

21. Solder one end of another length of No. 26 plastic-covered hookup wire to point A (see Fig. C14) and wind three turns inside the tubing in the direction shown.

22. Feed the free end of the hookup wire through the shielding. Bend the tubing into final shape as shown in Fig. C14. Pull up the three turns snugly, making sure that the plastic coating is undamaged.



C6—Tube shield, Mat'l .010 Brass



C7 — Shield Assembly S4



C8—Shield can, Mat'l Aluminum



C9—3X4X6 LMB Shield can S5

23. Connect a male phono plug to the free end of the shielded wire as shown in Fig. C15. Length of the wire is critical.



C11 — Insulator I4, Mat'l Plexglas



C10—Shield Partition S5A, Mat'l Aluminum



C13—Shield PS1A, Mat'l .005 Brass or Copper
C12 — Primary bobbin PS1, Mat'l Brass or Copper



C14—Shield PS2, Mat'l copper



C15—Transformer assembly



C16—Inside view of panel



Fig. I—HF. RF. Bridge Mark III Schematic



Fig. 2—Inside view



24. Using four pieces of ⅛-inch diameter plexiglas rod as spacers, assemble the primary and secondary shielded windings as shown in Fig. C15. Attach insulator I4 to the transformer by cementing it into the bobbin hole with Duco. Cement both windings to spacers with Duco and allow to dry overnight. This completes the transformer.

25. Remove top and bottom from the 8x10x10 utility box. Remove all paint from flanges; clean to bare metal to provide adequate rf shielding on reassembly.

26. Remove paint from inside of bottom plate for ½ inch in from each edge.

27. Remove paint from inside of top plate as shown in Fig. C16 by "phantom lines."

28. Drill the top plate as shown in Fig. C16.

Note that drawing shows INSIDE surface of plate.

29. Cut shafts of all four variable capacitors to ⅜-inch length. Remove all trimmer capacitors.

30. Tap the threeholes on the face of each capacitor, using a 6-32 tap. Take care not to damage the first stator plate; a bottom tap may be necessary. Attach three type I2 insulators to C1 and C2, using ¼-inch-long 6-32 set screws as shown in Fig. 3. This completes preliminary metalwork.

Actual Wiring

31. Attach C1 and C2 to shield box S5 using six ¼-inch-long 6-32 machine screws. Connect stator lugs of C1 to those of C2 with No. 18 tinned wire, as shown in Fig. 3.

32. Mount two soldering lugs as shown in Fig. 3 and connect remaining stator lugs to them, using No. 18 tinned wire.

33. Press the Erie CF-408 feed-thru into the 0.136-inch diameter hole in S5. Solder a short No. 18 tinned lead from the inside terminal of this insulator to the wire installed in step 31, as shown in Fig. 3.

34. Attach shield partition S5A, using three ¼-inch-long 6-32 machine screws. One of the screws installed in step 32 must be temporarily loosened and removed.

35. Attach four type I3 insulators to shield box S5 as shown in Figs. 3 and C9.

36. Attach three more soldering lugs to S5 as shown in Fig. 3, using ¼-inch-long 6-32 machine screws.

37. Attach four type I3 insulators to shield platform S1, using the 4¼-inch-spaced holes in S1 and 6-32 screws. Attach S1A to S1, using 6-32 screws from the inside of S1. Attach the female phono socket to S1 in the 7/16-inch diameter hole. Attach four type I1 insulators, using ¼-inch-long 6-32 screws. Do not tighten the screw in the hole marked "Hole A" in Fig. C1; this screw will hold a cable clamp later. See Fig. 4 for details of insulator placement.

38. Attach four type I1 insulators to shield platform S2, using the 2⅜-inch-spaced holes in S2 and ¼-inch-long 6-32 screws. Attach S2A to S2. Attach capacitor C3 with 1-¼-inch-long 6-32 screws, using two nuts on each screw as shown in Fig. 4. Mount a soldering lug under one nut as shown. Align the capacitor by adjustment of the mounting screws and nuts.

39. Solder a No. 18 tinned wire to the female phono socket and pass the wire through the corresponding hole in S2. Attach S2 to S1 with ¼-inch-long 6-32 screws going into the type I1 insulators attached to S1 in step 37.

40. Attach C4 to shield platform S3 using ⅝-inch-long 6-32 screws with dual nuts (same as in step 38). Attach S3A to S3.

41. Connect two of the stator lugs of C4 with No. 18 tinned wire as shown in Fig. 4. Slide shield assembly S4 into S3A. Center assembly S4 in S3A, using a piece of ¼-inch-long insulating tubing. Make certain that opposite ends of S4 and S3A are even as shown in Fig. 4, and cement tubing in place with Duco. Solder the shorted end of resistor R2 (which is in S4) to the wire connecting stator lugs of C4.

42. Attach shield platform S3 to S2, using ¼-inch-long 6-32 screws going into the type I1 insulators installed on S2 in step 38.

43. Place a ¼-inch-long 6-32 screw in the flange of S3 as shown in Fig. 4, with a soldering lug. Connect this lug to the stator lug of C3 with No. 18 tinned wire. Using ¼-inch-long 6-32 screws, mount a soldering lug in Hole B (see Fig. C1) of S1 and another in S2 as shown in Fig. C2. These lugs are mounted in a direction opposite to that of the platform flanges.

44. Attach the "unknown" ground lug to the panel next to the "unknown" coax connector hole, as shown in Fig. C16. Attach the "receiver" coax connector to the panel, from the inside. Attach the "IND-CAP" switch to the center of the panel, using an extra nut to position the switch as far as possible from the panel. Orient the switch as shown in Fig. 5. Place a soldering lug under each nut. Mount C5 and C6, using ⅜-inch spacers between the capacitor frames and the panel. Connect the



Fig. 3—Resistance box—Inboard view

rotors of C5 and C6 to the lugs of the switch with No. 18 tinned wire as shown in Fig. 5.

45. Solder a 2½-inch length of No. 18 tinned wire to the "COMMON" terminal of the switch. Connect the stators of C5 and C6 to the remaining switch terminals, as well as resistors R3 and R4. Complete connections are shown in Fig. 5.

46. Attach the "unknown" coax connector to the panel, placing a soldering lug under one mounting screw. Connect the "unknown" ground lug to this soldering lug to provide a good bond.



Fig. 4—Reactance Assembly—Inboard view

47. Mount panel bearings for capacitors C2 and C4. Mount the special panel bearings furnished with the Johnson Vernier Dial assemblies in place. Attach the two large dials to dummy shafts and mount the dial indicator in the position you prefer. Remove the large dials and dummy shafts after placing the dial indicators.



Fig. 5—Switch Assembly

48. Mount S5 at the left side of the panel (as shown in Fig. C16) and mount the assembly of S1, S2, and S3 at the right side. See Fig. 2.

49. Attach shaft couplers to the four capacitors. Cut the plexiglas shafts to length and mount them in place. Attach the large vernier dials. Set the dial of C2 so that it reads "0" at minimum capacity. Set the dial at C4 so that it reads "100" at maximum capacity. Mount the two Calrad dials on the panel, setting them so that they both read "0" at maximum capacity. Attach the knob to the "IND-CAP" switch.

50. Connect resistor R1 (270-ohm deposited-carbon) from the soldering lug on S2 to the lug in line on S5. Connect R3 (220 ohms) and R4 (100 ohms) to the soldering lugs on S5 which were installed in step 36. R3 will be the resistor nearest the bottom of the panel.

51. Connect a No. 18 tinned-wire lead from the "detector" coax connector to the lug on S5. Connect a No. 12 (note different wire size) lead from the "unknown" connector to the free end of R2. *Make sure that R2 is not shorted to any shield.*

52. Attach the transformer, completed in step 24, to the bottom of the panel as shown in Fig. 2. Attach the coax connector connected to the transformer to the panel in the "signal generator" hole. In the hole between the transformer and the connector, mount a cable clamp to hold the shielded primary lead. Secure the shielded secondary lead with another clamp held by the loose screw installed in step 37.



Fig. 6



Fig. 7

53. Mount a soldering lug to S1B with a ¼-inch-long 6-32 screw, placing the lug in the direction of the box opening.

54. Place ¼-inch-long 6-32 screws in all remaining tapped holes in S1, S2, and S3. Starting with S3, place all shield boxes in place and secure screws. Connect a No. 18 tinned lead from the soldering lug installed in step 53 to the Erie feed-thru on S5. Set C5 and C6 to mid-capacity.

55. Attach four rubber feet to the bottom plate of the case and four more to the bottom side of the utility cabinet. Restore the front plate in place and secure with the sheet-metal screws provided. This completes construction of the bridge. After calibration, it will be ready for use.

Calibration and Use

Since the Mark III is a null-type instrument (adapted from the Schering bridge circuit) it can only be used with a signal generator and a detector. Both must be shielded; however, a Heath SG-8 will do nicely as the signal generator and any decent communications receiver will serve as the detector. For best results, it



should be calibrated with the signal generator and receiver with which it will be used.

56. Connect the bridge to the signal generator and the receiver, using coax cable from the panel connectors to each.

57. Set both the signal generator and the receiver to 2 mc.

58. Short the "unknown" terminal and ground terminal using a banana plug in the connector or a coaxial short made by soldering the pin of a PL-259 connector to the shell through a copper disc.

59. Set the "IND-CAP" switch to "CAP."

60. Set the "Reactance" dial to 15.

61. Set the "Resistance" dial to 5.

62. Tune the signal generator, only, for maximum signal in the receiver.

63. Using the two small "balance" dials, reduce the signal in the receiver to the lowest level possible. This is the "null" or "balance" condition. The dials will interact, and multiple adjustment will be necessary. However, all receiver and signal generator adjustments must be left alone during this step.

64. Replace the short across the "unknown" connector with the 620-ohm deposited-carbon "test" resistor.

65. Using only the large "resistance" and "reactance" dials, null out the signal once more. Record the final reading of the "resistance" dial. If this reading is 95, you are extremely lucky and the first half of the calibration is complete. If not, proceed with step 66.

66. If the "resistance" dial reading is less than 95, increase the capacity of C6 slightly and repeat steps 60 through 65. If the reading is larger than 95, decrease the setting of C6 and repeat steps 60 through 65. Continue this process until the reading comes out at 95.

67. When capacitive calibration is complete, set the "IND-CAP" switch to "IND," and the "reactance" dial to 30.

68. Repeat steps 60 through 65; if the final reading of the "resistance" dial is other than 95, proceed with step 69.

69. If the reading is less than 95, increase the capacity of C5 slightly and repeat steps 60 through 65. If the reading is larger than 95, decrease the setting of C5 and repeat. Continue until the reading is 95. This completes calibration, and the curves shown here can be used for readings.

Using the Mark III

To use the Mark III, set the instrument up as described in step 56 of the calibration procedure. Set the signal generator to the desired frequency and short out the "unknown" terminal of the bridge as described in step 58.

If you're measuring an inductive impedance, set the "IND-CAP" switch to "IND," the reactance dial to 95, and the resistance dial to 5. Null the signal with the small balance dials.

Now remove the short and connect the unknown. Rebalance the bridge using the large dials, note the readings, and convert the readings to ohms by use of the calibration curves.

These initial values must be corrected. The reactance value is corrected by dividing the value read from the curve by the frequency (in mc) at which the reading was taken. The resistance value is corrected by obtaining the correction factor due to frequency from Fig. 8 and multiplying the reading by this factor.

If you're measuring a capacitive impedance, set the switch to "CAP." Then estimate the reactance of the unknown and set the large reactance dial to a value just larger. Set the resistance dial to 5 and short out the "unknown" connector. Null the signal with the short and again with the unknown, the same as for an inductive impedance.

Correct the resistance reading in the same manner as for an inductive impedance. However, the reactance reading is corrected differently: Subtract the value taken from the calibration curve from the value originally set on the reactance dial. Now divide this remainder by the frequency (in mc) at which the reading was taken. The result is the true value of capacitive reactance.

A few minutes' practice will make operation of the Mark III far more simple than the detailed directions would indicate; in practice, you can make a reading in less time than it takes to read these paragraphs.



Fig. 8

Parts Substitutions and Design Changes

Since few hams are content to build a "Chinese copy" of someone else's design, a few words on the effect of changes are necessary.

Naturally, the Mark III doesn't represent the only possible—or even necessarily the best—way in which such a bridge can be built. Any part, or all, may be changed. However, any such change will invalidate the calibration curves, and is not recommended unless the builder has access to laboratory equipment.

Even then, before making any substitutions, these three design articles should be read and fully understood:

"A Radio-Frequency Bridge for Impedance Measurements From 4000 KC/S to 60 MC/S," D. B. Sinclair, Proceedings of the I.R.E., November, 1940, pages 497-502.

"A High Frequency Model of The Precision Condenser," D. B. Sinclair, General Radio Experimenter, October-November, 1938, pages 1-7.

"The Effect of Stray Capacitances to Ground in Substitution Measurements," M. Reed, Wireless Engineering, May, 1936, page 284 ff.



Fig. 9

Parts List

Quan.	Item	Description	Cat. No.
1 ea.	C1, C2	Miller, 10-365 mmf/sect.	2112
1 ea.	C3, C4	Miller, 10-365 mmf	2111
1 ea.	C5, C6	50 mmf air padder (good quality)	APC-50
1 ea.	J1, J2, J3	SO-239 Panel coax connector	
1	J4	Phono plug	
1	J5	Phono socket	
1	R1	Aerovox 1% 1/2W 270 ohm "Carbofilm"	Type-CP
1	R2	330 ohm 5% 1/2W Carbon Resistor	
1	R3	220 ohm 5% 1W Carbon Resistor	
1	R4	100 ohm 5% 1W Carbon Resistor	
1	Test	Aerovox 1% 1/2W 620 ohm "Carbofilm"	Type-CP
1	SW	Centralab 3p; 1 Sect; 2-3 Position (reset stop to two positions only)	2506
*2	Dials	E. F. Johnson Vernier (0-100 CW)	116-285-1
2	Brgs	E. F. Johnson Panel Bearings	115-255
4	Cplrs	Metal ¼ shaft couplers	
3	Rod	¼ inch diameter plastic rod x 12"	
1	Rod	⅛ inch diameter plastic rod x 6"	
2	Rod	⅜ inch diameter plastic rod x 12"	
2	Dials	"Calrad" 1-13/32 inch Vernier Dial	VD-36
1	BP	Binding Post (ground lug)	
1	Case	Bud carrying case 10"x10"x8"	CC-1100
1	Box	LMB box (plain) 3" x 4" x 6"	
1	Hood	UG 177/U coaxial cable hood	
1	Insul.	Erie feed-thru insulator	CF-408
1	Short	PL-259 coaxial male connector	
2	Clamps	Walsco clamp for ⅛ to 3/16 cable	7502-N

Of the above list the critical parts are:
C1, C2, C3, C4, J2, R1, Test resistor, Case, LMB box, UG 177/U, Erie feed-thru.

---

* This author hand engraved these dials per Figs. 6 and 7.

MEASURE RF IMPEDANCE WITH YOUR SWR BRIDGE

Warren McDowell W2AOO

So far, the great majority of antenna impedance bridges that we have found in construction articles are devices that function only with a low power rf source. The run-of-the-mill impedance bridge is designed to operate with a grid dipper as the source of rf excitation. Operation with tube type dippers is generally intended as the transistor dippers produce an rf level that is too low for excitation of this bridge type.

The conventional antenna bridge cannot be left in the transmission line continually as excessive rf energy would soon destroy the device. This means that each time measurement of antenna impedance is desired, the transmission line must be opened and the bridge inserted and grid dip excitation applied. Grid dippers are not necessarily the most accurate rf source for a specific frequency in an amateur band . . . therefore the station receiver must monitor the dipper output for any bridge accuracy. A low power bridge will not often present the true operating impedance of the antenna . . . especially antennas with parasitic elements. A bridge that operates under full transmitter power will present a much more accurate picture of your antenna system at a specific frequency.



Fig. 1. Conventional swr bridge.

Inspiration for the "In Line" full power bridge came from information concerning the standard swr bridge. Just about every amateur has in his possession some sort of swr bridge and the great majority are of the type illustrated in Fig. 1. This bridge consists of a section of transmission line near which are placed two inductors. These inductors are actually two bridges along with their associated diodes and resistors. One of the bridges reads forward power and the other reflected power. The resistors (Rx) at the end of the inductors L1 and L2 are critical for accurate bridge null (balance) and therefore must be the proper value for the specific transmission line used. For the average swr bridge the value for Rx is 100Ω for 75Ω line and 150Ω for 50Ω transmission line. Considering that resistor Rx is critical for the impedance of the line in use, varying the value of Rx and devising a system of calibration for Rx would enable us to determine the impedance of a line when a null is achieved on the bridge meter.

The "reflected" inductor which is L1 in Fig. 1 is the portion of the bridge circuit we are interested in for impedance measurements. The value of Rx and the transmission line must balance the bridge for a null to be realized. Any variation from the above parameters will mean changing the value of Rx so that the bridge again balances at a new impedance value.

By experimenting with various values of resistance at Rx, it was determined that a 1000Ω potentiometer represents a fair value. The 1000Ω potentiometer is inserted in place of Rx on inductor L1 (see Fig. 2). This is the inductor with the diode pickup located toward the load or antenna end of the swr bridge.

Make sure that all leads to the 1000Ω potentiometer are short and that the metal case (shell) of the potentiometer is well grounded. Excessive lead length or inductance will create inaccuracy of the device. The position of the potentiometer will be determined by the physical layout of your particular swr bridge. It must be set at a point where the shaft can be extended through the front panel of your swr bridge. Allowance must also be made for a dial or other indicating device which can be calibrated in ohms (impedance) on the front panel. It might even be desirable to mount your entire present bridge in another larger case so that all functions can be accommodated.

Calibration of this in-line bridge was the major problem. An ordinary grid dip meter will not provide sufficient excitation for readings. With full power applied, especially a kilowatt, it becomes difficult to find resistive dummy loads of various values to calibrate the bridge. Even with 100W of rf, proper resistive load values are not common.

The solution to the calibration problem came to us in the form of an (ouch!) CB transmitter. A CB transmitter is fortunate if it is able to put out 3W of rf and at the same time is well within the frequency range of an swr bridge. The most important fact is that a CB transmitter will provide adequate excitation for calibration of the bridge with ordinary 5W 5% carbon (garden variety) resistors. For calibration, a good assortment of these resistors is necessary. Use values such as 5, 27, 47, 75, 100, 150, 220 and 470Ω. Intermediate values can be then interpolated on your scale. The calibration procedure is simple . . . first borrow your neighbor's CB, then attach the 5W resistors across the antenna coax connector of the bridge and excitation of the CB transmitter is applied to the remaining connector on the bridge. The bridge sensitivity should be set for a middle scale reading of the meter and the 1000Ω potentiometer is varied until you reach a null on the meter. Mark the value of the calibration resistors on the potentiometer scale (dial). Do this for all of the available resistors and your bridge will be in fair calibration.

At this point we should mention that this system does not measure reactive components in the antenna system. If your antenna is reactive, either inductive or capacitive, the meter will present a shallow, poorly defined null at the operating frequency. A sharp, well defined null will indicate a purely resistive impedance.



Fig. 2. The modified bridge leads to 1K pot should be as short as possible and shell (case) of pot grounded.

When using the bridge in its former function as an swr bridge, set the resistance dial to the value of your transmission line. When measuring impedance, vary the dial for maximum dip on the meter and read the resistance (impedance) directly.

As a final point, it is wise to insert the swr/impedance bridge at a half-wave or an even multiple of a half-wavelength from your antenna. At half-wave points from the antenna, the antenna impedance is repeated. This will enable your measurements to be much more accurate. When determing half-wavelength points, take into consideration the velocity factor of your particular coax.

USE YOUR GDO AND Z METER

Denys Fredrickson W0BMW

The GDO is one of the most versatile pieces of test equipment available. Yet there are many hams who don't know how or when to use one. The writer will try to describe and explain some of its various functions.

The GDO is basically a variable high frequency oscillator with a frequency range of approximately 550 kc to 250 Mc. It may also be used as a diode detector or wave meter. The GDO gets its name from the fact that a meter measures the grid current and when the oscillator circuit is coupled to a resonant circuit a reduction in grid current is obtained. This is called the grid dip. However, when it is used as a wavemeter and coupled to an rf source, an increase in current is obtained at resonance.

The GDO and impedance meter can be used to accomplish the following:

1. Determine the resonant frequency of tuned circuits, including antennas.
2. Determine the impedance of circuits, receiver inputs and antennas.
3. Determine the length of half-wavelength or quarter-wavelength transmission or tuning stub lines.
4. Determine the "Q" of a circuit or component with the aid of a VTVM.
5. Determine the resonant frequency of individual coils, capacitors or crystals that are within the range of the GDO.
6. Determine the rf frequency of energized circuits.
7. Monitor a radiated rf signal with the aid of headphones.
8. Neutralize rf stages.
9. Locate parasitic oscillations.
10. To align receivers and television sets.
11. Determine where BCI and TVI is entering the radio or television receivers.
12. Determine unknown inductance.
13. Determine unknown capacitance.

Now if you will step into the lab we will try to demonstrate how these instruments can be put through their paces. Let's begin with the simple functions and then gradually creep up to those which are more complex so they don't scare us before we get started.

An oscillator-detector

Simply plug in a pair of headphones (if GDO has facilities for them) and "zero-beat" with the radiating signal. This then will be the frequency of the radiating signal.

Crystal frequencies

Connect a one turn loop of wire across the crystal and couple the GDO close enough to get a dip of the meter when resonance is obtained. It is always wise to check lower frequencies to be sure it is the fundamental frequency that is being indicated.

Frequency determination

Generally the GDO has a switch which is used to remove the plate voltage from the tube. The tube will then serve the function of a diode and the meter as a diode load. When a peak deflection of the meter is obtained this will indicate the frequency of the radiating signal.

Resonance of an RF choke

When an rf choke is used as a parallel or shunt fed circuit, it must be free of self resonance over the operating frequency range of that circuit or it may burn up. The popular pi tank circuit is an example. Place a short circuit across the choke and then determine its self resonant frequency by coupling the GDO close enough to indicate a dip on the meter when the resonant frequency is obtained.

Neutralization

Apply plate power to the exciter stages and filament power only to the stage being neutralized. Use GDO as a wavemeter and couple close to the tank coil in the stage being neutralized. Vary the frequency of the GDO until maximum reading is obtained and then adjust the neutralization for minimum GDO meter reading. The circuit being neutralized may have to be retuned and the above procedure repeated with a closer coupling of the GDO to the Tank coil.

IF alignment

Tune the GDO to the desired frequency and couple it close to the if coil to be aligned. Adjust the if coil until a dip is observed on the meter. The if coil will then be tuned to the desired frequency.

Inductance and capacitance checking

To determine the value of an unknown capacitor, connect it across a known inductance and use the GDO to find the resonant frequency of the circuit. With these known values a reactance chart will give the value of the capacitor. Some GDO's supply a chart which corresponds to the coils supplied with the GDO as the known inductances. To determine the value of an unknown inductance, connect a known capacitance across the coil and use the GDO to find the resonant frequency. Again, the reactance chart may be used or the following formula (which may be used for either inductance or capacitance) for resonant circuits:

$$L = \frac{1}{39.48\ (f^2)\ C} \quad \text{or} \quad C = \frac{1}{39.48\ (f^2)\ L}$$

Where f = cycles per second
L = inductance in henries
C = capacitance in farads

The inductance of an air core coil can be estimated by the following formula:

$$L = \frac{(rN)^2}{9r \neq 10w}$$

Where L = inductance in microhenries
N = number of turns
r = radius of coil in inches
w = length of coil in inches

Q measurements

Connect a condenser across the coil so the tank circuit resonates at the desired frequency. Connect a VTVM across the tuned circuit and tune the GDO until maximum reading is obtained on the VTVM. The GDO coupling may be changed until a convenient value is obtained on the VTVM and then it must not be moved during the remainder of the test. Note the resonant frequency f_c then detune the GDO to a lower frequency until the VTVM reads 70.7 percent of its original or peak value and call this frequency f_1. Now detune the GDO to a higher frequency until the VTVM again reads 70.7 percent of its original or peak value and call this frequency f_2. The Q is then calculated by using the following formula:

$$Q = \frac{f_c}{f_3}$$

Where f_c = is the center of resonant frequency
f_3 = the difference between f_1 and f_2

Parasitic oscillations

By using a pair of headphones with the GDO, the parasitic oscillation frequency may be determined. Turn the power off of the stage being checked and then use GDO to find the circuit which resonates at the parasitic frequency by moving the GDO slowly around the wiring. When a "dip" is observed, moisten the finger and touch an ungrounded point of the circuit. If a change in the dip is observed, it indicates that it is the portion of the circuit that would be a likely suspect.

BCI and TVI locator

Most of the BCI and TVI problems can only be resolved at the receiver, either by installation of filters, resistors or condensers or a combination of all three. The problem is—where is the rf entering the receiver? Use the GDO tuned to the frequency which produces the greatest amount of interference. Probe around with the GDO until the most sensitive spot is located, which is indicated by watching or listening to the receiver interference. After the point of entry is determined then the appropriate corrective action can be accomplished.

Antenna measurements

Space does not permit to discuss all types of antennas and adjustments so only a few will be mentioned to give some idea on the use of the instruments. At this point it should be mentioned that inductive type coupling should be used between the GDO and antenna when checking near the current maximum point and capacitive coupling when checking near the voltage-maximum point.

The beam antenna has gained tremendous popularity in recent years plus many headaches for those striving to obtain the maximum effectiveness. Most of the headaches can virtually be eliminated by using the GDO and Impedance meter (Z-meter). Let's take a look at a 3 element yagi and see what has to be done to obtain a good adjustment. The element lengths must be physically adjusted or electrically loaded to obtain resonance at the desired frequencies and the feed point impedance must match the impedance of the transmission line. These two points are not the only considerations for beam adjustment but they are the most important factors. The GDO can be inductively coupled to each element and the elements adjusted until each one is resonant at the desired frequencies. It is best to make the measurements while the antenna is in operating position. This is very difficult to do in many cases but let's assume you can. After the elements have been adjusted, the feed point must be adjusted to match the line. The Z-meter and GDO will be used to accomplish this adjustment. The Z-meter is basically a resistance type bridge with a calibrated potentiometer as one of the bridge arms. Connect the Z-meter directly to the antenna feed point. Couple the GDO to the Z-meter inductively thru a couple loops of wire connected to the other terminals of the Z-meter. Tune the GDO to the resonant frequency of the beam and adjust the Z-meter to the dip or null. If the impedance indicated by the Z-meter is not the same as the transmission line then readjust the matching network and redip the Z-meter until the impedances are equal.

Now—if you can't adjust the antenna in the operational position you still can determine the resonant frequency and the impedance by standing on the good old Terra-Firma. The procedure is a little more involved but effective. First—we must have a means of electrically connecting the instruments to the antenna. This is best accomplished by a transmission line a half-wave or a multiple of a half-wave in length. Determine the height of the antenna above ground and calculate how many half-wave lengths of line will be required by using the following formula for a half-wave length of line:

$$L = \frac{(492)\ (K)}{f}$$

Where L = feet
f = megacycles
K = propagation constant
(RG/8 is .66)

This is an approximate length so be sure and cut it extra long because now we will find the exact physical length. Why an exact physical length? A halfwave length of transmission line will reflect the resistance placed across the output at the input end of the line, i.e. if a 50 ohm non-reactive resistor is placed across one end of a half wave or multiple length thereof, the GDO and Z-meter will indicate 50 ohms at the other end of the line. Cut the line somewhat longer than calculated above, short one end and connect the Z-meter to the other end of the line. NOTE: Keep twin lead off the ground and away from metal objects. Set the Z-meter to zero impedance and couple the GDO inductively to the Z-meter. Adjust GDO frequency until the fundamental frequency causes the Z-meter to dip or indicate a null. The frequency indicated should be lower than the desired frequency. Simply cut a few inches of cable off, short the end again and readjust the GDO. Repeat this procedure until the desired frequency (which should be the same as the resonant frequency of the antenna) is obtained. You will then have an electrically halfwave length of line or a multiple thereof.

Coax or twin-lead may be used for the halfwave length line when checking the impedance of the antenna. Connect the line to the antenna, hoist the antenna up to its operating position and adjust both the Z-meter and GDO for the null indication. If the antenna is not resonant at the desired frequency, the driven element should be readjusted a measured amount and then note the frequency change. This will give you an idea how much the resonant frequency changes with a corresponding element change. Now adjust the matching network to the desired impedance. This will be accomplished when the Z-meter dips at the desired impedance with the GDO set at the resonant frequency of the Antenna.

What would you do if your 100 foot coax cable developed a short someplace along the line? Replacing the whole line would be too expensive. Simply connect the Z-meter to one end of the line, adjust the Z-meter for zero impedance and then adjust the GDO for lowest frequency which will produce a null on the Z-meter. Use this frequency in the formula given for a halfwave length line and carefully calculate the length which will be the distance from the input end to the short.

A quarter wave length tuning stub can also be determined by using the procedures just outlined for the halfwave length line except a quarter wave line reflects a short at the input when the output end is electrically open. Now that we have mentioned the quarter wave length line, some may be wondering just what useful purpose does it serve. The quarter wave tuning stub (as it is sometimes called) may be used for antenna matching, TVI elimination or matching two units which have different impedances. The quarter wave matching stub can be used as a matching device on antennas which is explained in most antenna handbooks. It may also be used to eliminate an interfering frequency from entering the TV. This is accomplished by connecting a quarter wave stub to the TV antenna terminals which is a quarter wave in length at the interfering frequency.

Another use for the quarter wavelength matching stub is to permit maximum signal transfer between the source and a load which have different impedances. If the signal source impedance was 100 ohms and the load impedance was 52 ohms, a 72 ohm quarter wavelength of line would give a good impedance match. Hold it just a minute, how in the world did we come up with that 72 ohm business? Simple—another formula will give us this information.

$$Z_o = \sqrt{Z_s Z_a}$$

where Z_o = Impedance of quarterwave matching stub
Z_s = Impedance of the source
Z_a = Impedance of the load

Very little has been said concerning the various methods of GDO coupling. Actually—only two types of coupling are used; inductive and capacitive. Capacitive type coupling may be used on shielded coax cable, the ends of antenna elements and generally where the voltage maximum exists. To obtain the greatest accuracy, the GDO should be loosely coupled. Parallel coupling to inductors can be used to obtain maximum coupling.

Chapter III

Measuring RF Power Output

MEASURING RF OUTPUT

Paul Schuett WA6CPP

So your new Bandjammer 5000-Q is rated at 752W peak power. Big deal. How much of this is getting out where it counts?

It's easy to find out by inserting an rf ammeter in series with the line. A more exact reading would be to have the rf ammeter at the antenna input terminals, but that might be impractical when it comes to reading the meter (although you could put a diode there and a remote-reading meter in the shack).

Recently I found an rf ammeter at one of the mail-order surplus houses for $2.95. I installed this in a little cabinet, put two coax connectors on the back (in and out) and now can read rf current in the line, into the dummy antenna, or wherever it is going.

Remember the formula $P=I^2R$? Square the reading on the meter, multiply by the impedance of the line you're using, and you have the power past that point. At the antenna, you could determine the antenna resistance and take the current reading at that point.

For those who have difficulty with mental computations and can't find a pencil, the following chart fives the computed power levels present in matched 50 and 70 Ohm coaxial lines for various levels of rf current:

RF Current Amperes	Power Output in Watts	
	50 Ohm Line	70 Ohm Line
0.5	12.5	17.5
1.0	50	70
2.0	200	280
3.0	450	630
4.0	800	1120
5.0	1250	1750

When tuning up the rig, place the ammeter on the antenna side of any tuning or matching devices and tune for maximum current.

Inside wiring is extremely simple. Note ground wire installed to insure continuity of the shield circuit.

The completed instrument showing the coax connectors on the rear.

It's amazing to learn how much (or how little) current these rigs produce. For instance, my Swan 250-C puts 1.35A into a 50Ω line. My friend's SB101 from Heathkit put out 0.7A until we worked on the antenna – then it put out about 1.25A. My Heathkit SB401 puts anywhere from 2 to 0.6A into a 50Ω Cantenna, depending on what band it's on.

Commercial stations determine their power by the antenna current. Knowing the antenna resistance at the operating frequency, they multiply that by the current squared. If the antenna resistance is 62½Ω, 4A rf would be 1 kW into the antenna. 126.48A would be 1 MW.

Remember the ammeter does insert a little reactance in the line (I never leave it in all the time), and the calibration changes with frequency, although you can tell what side of the ballpark you are on. An rf ammeter in the shack makes a nice piece of test equipment.

LIGHT BULBS AS RF INDICATORS

John Houser WB2GQY

The major appeal to the amateur – as well as some commercial applications – of light bulbs as rf power indicators is low cost. To this must be added the universal availability of bulbs and screwbase sockets for pennies.

As low cost is of primary interest to well over 50% of those interested in any project, and as I have always had an insatiable desire to find out the why's and wherefore's of standard light bulbs as rf power indicators, I decided it might be the opportune time to do a resarch project and determine once and for all just which bulbs might be suitable and which might not be, and also to determine whether light bulbs would make *good* rf power indicators, or poor, and to find out what precautions might have to be taken if one decided he was going to take this low-cost path of determining his transmitter output power rather than go for a more expensive power output meter.

Also, power output meters in the higher wattage ranges become quite expensive compared to the $2 to $5 which might be expended in a light bulb indicator. In general, porcelain screw bases are available for from 12¢ to 25¢ each, and bulbs from 15¢ to 65¢ each, and not more than four of each are necessary for up to 3 KW power indication.

Table 1 lists most of the common types of electric light bulbs readily available. One look at this table immediately reveals why such light bulbs might not be such good rf power indicators as some folks may have thought they were in the past. It also reveals that some very special precautions have to be taken in using them, or the user may find he has overloaded his transmitter and burned up a few components which might be expensive to replace.

Table 1

Variation in Resistance, Cold to Hot State, Common Variety of Electric Light Bulbs.

Bulb Rating Watts At 115V	Cold Filament Resistance	Hot Filament Resistance	Ratio Cold to Hot Filament Res. (Approx.)
7.5	166	1750	1 to 10
25	40	529	1 to 13
40	27	331	1 to 12
60	20	219	1 to 11
100	9	132	1 to 15
150	6	83	1 to 14
200	4.5	65	1 to 14
250	3.5	53	1 to 15
500	2	26	1 to 13
750	1+	17.7	1 to 15

Table 2

Possible Configurations for Various Power Outputs at Various Impedance Terminations

A. – Nominal 70 to 73Ω Impedance Loads:		
175W Load:	3–60W bulbs in parallel	(73Ω)
	OR	
	7–25W bulbs in parallel	(70Ω)
3,000W Load:		
	4–750W bulbs in series	(71Ω)
B.) Nominal 50 to 55Ω Impedance Loads:		
250W Load:	4–60W bulbs in parallel	(54.9Ω)
500W Load:	2–150W bulbs in series, both paralleled by 1–150W bulb	(55Ω)
1,000W Load:	2–500W bulbs in series	(53.6Ω)
2,250W load:	3–750W bulbs in series	(53.1Ω)

The extremely high ratio of cold to hot filament resistance in all types of these bulbs immediately struck me as being the most undesirable factor in using them.

It is very easy to see, for instance, that if one wished to use a 250W bulb for indication on a 250W transmitter, and he computed the resistance at 250W to be 53Ω, (which it is, but only when *hot*), he would assume he had just about a perfectly matched indicator to plug in in place of his 52.5Ω feed line.

However, from this table, it is apparent that this 53Ω resistance is attained *only* at full brilliance and wattage, and the actual cold resistance is only 3.5Ω. In other words, if the bulb were connected to the antenna terminals of the transmitter, and the transmitter keyed full power, the transmitter would be looking into *not* 53Ω, but 3.5Ω, which is a lot of difference, and an extremely low value for any pi network to match.

For a few seconds, until the filament attained full brilliance, the transmitter would be subjected to a terrific overload, due to this impedance mismatch.

Therefore the first precaution which might be emphasized in using light bulbs would be *not* to key the transmitter at full power with a cold bulb, but to gradually bring the power from some lower value to full power as the bulb attains full brightness (and hot, matching resistance).

Not until I got into this project did I realize the very high ratio of resistance of these filaments from the cold to hot state; I don't suppose very many people do. It also brings to mind how the house electric meter must jump every time a bulb is snapped on in the house. This is not an ad for those light dimmers being sold at all the electrical stores, but it sure brings to mind that power bills could be cut appreciably through their use, i.e., bringing the bulb gradually to full brilliance instead of just snapping on a switch.

Getting back to the bulbs, Table 2 gives in various configurations series, and/or parallel combinations which would be most likely to give the amateur a load for a particular transmitter power output, in nominal impedances near 52 and 72Ω. If the configuration mentions 200W, this does not mean that it would be suitable for indicating the output of a 100W output transmitter, because at half brightness, the resistance offered by the bulb is not identical to that at full brightness.

While a differance of an ohm or two would not be serious, nor would a difference of as much as five, or even ten watts, at high power levels, at low power levels less than 100W, for instance, such differences would be seen to become increasingly serious from the matched impedance standpoint. The configurations given match quite a variety of standard line impedances and a wide range of power outputs. Matches can be obtained for RG-8, 11, 17, 13, 58 and 59 type cable.[1]

One may not realize without measurement that the lead length of the filament support wires alone inside the 25–150W bulbs is very close to 18 cm. Even though they are coiled on a 2 to 1 ratio, the filament is inductive in every sense of the word. At higher frequencies, the filament support wires would appear inductive, and to these factors must be added the parallel capacity of the screwbase shell and the central base contact wafer. Even though such capacity is small, it would become significant at most amateur frequencies above the 30 MHz range. Though the 22 cm total wire path would perhaps indicate a bulb could be used up to 300 MHz, such is not at all the case.

It is easy to see that the sometimes suggested trick of using a capacitor in series with a light bulb as a load should be approached with caution, for it would be very easy indeed to run into a series resonant circuit which might result in damage to the transmitter to which such circuit were connected.

In the course of my preparation of this article, I discussed the ramifications with a number of interested hams. Some of them suggested I extend the research to include the use of the smaller types of indicator (pilot) bulbs as loads for testing out transmitters with power outputs in the 1W to 20W range, not only just for amateur applications, but also with a view to using them as loads in testing FM transmitters.

When one considers that there are well over 100 types of these small bulbs, rated from .001W to 2W, and if all of these were to be considered individually, it could take a vast amount of time – and eventually one would end up with perhaps only five or so of these bulbs that would be at all suitable, so such research was not included in this article. However it did open up a field in which there may be a demand for information and may be the subject of a subsequent article.

Frequency Ranges

The use of standard screw-base ceramic or steatite porcelain light bulb sockets is entirely feasible for all of the configurations shown and will handle all amateur bands, 160 through 10. Naturally the leads from socket to socket should be as short as possible in either the series and/or parallel configurations. I found these leads can be kept to approximately 2 cm for such interconnections. Likewise, the coax termination lead should be kept to 2 cm or less.

If extra precautions as to lead lengths are observed, and the bases of the bulbs removed to enable connections directly to the stem wires, it would appear reasonable to suspect that these bulbs might be used for 6, 5, and perhaps 2 meter bands, but it is also quite evident the 2 meter band would be the practical limit.

One should be able to conjecture that light bulbs as power rf indicators are not quite the equal of well-designed power output meters which maintain their rated impedances over a very wide power output range – bulbs do not – but then, they *are* cheap in comparison.

Visual comparison of brightness is completely satisfactory for comparison purposes.

For instance, a 500W bulb connected to the 115V mains should show the same brilliance as one of the 500W bulbs as used in the 1 KW load.

Actually a transmitter supposedly putting out 2,000W PEP is putting out something less than 1,000W with average voice modulation; it would be more of the order of 500–750W average power. Remember that the light bulb is only going to show average power output, not peak, and as ham transmitters are limited to 1,000W dc input to the final amplifier, one cannot expect much more than 500–750W output (average) unless the efficiency of the final amplifier stage approaches 85% which is very unusual, although I am hearing lately that certain high-power transistors are in development which will deliver such high efficiency figures; a bit above that which heretofore has been obtainable with tubes. You should be hearing a lot more about these super-efficiency transistors in the near future; and I expect them to be appearing in certain ham transmitters within a year or so.

Naturally a CW transmitter with the final operated Class C may deliver as much as 850W with 1,000W dc input, while a DSB transmitter on phone could not be expected to deliver more than 650W with Class A or B modulation.

The research and conclusions I reached on this project brought to mind the old subject of using light bulbs in series with primaries of transformers to reduce the secondary output voltages, which is a trick which has been used for years by hams and others. The information contained herein indicates they are not only quite suitable for such usage, but in fact make quite ideal voltage regulators of a sort.

In fact, the question immediately arises as to why bulbs would not make rather ideal voltage regulators for high voltage supplies if used as a variable-resistance dc regulator in the dc leg. This again opens up a field which might bear intense investigation.

---

[1] Solid Dielectric RF Transmission Lines, W8LUQ, *Radio News* Oct. 1946.
Line Matching: Table of Power and Voltage Loss in DB, *Radio News* Feb. 1947.

BUILD YOURSELF A LIGHT WATTMETER

Carl Henry

Every week brings something new in the hectic field (or pasture) of electronics. Attempting to solve old problems with new components is an interesting pastime for electronics enthusiasts, but they must be careful not to put their foot in the wrong thing. One of the new components is the cadmium sulphide/selenide photocell. A semiconductor sensitive to light is not an entirely new concept, since selenium cells have been around for some time, but the degree of sensitivity makes the cadmium cell stand out.



Fig. 1. Circuit of Light Wattmeter.

In measurements especially, there are many possible applications for cadmium photocells. One measurement in particular is usually difficult for the amateur, and this is power measurement. There is a way of using cadmium photocells to measure power, and I call this circuit a "light wattmeter". Operation is just as the name implies, that is, the power is used to generate light which is measured by the photocell.

You have probably realized by now that we are going to use a light bulb as a load. Now this is frequently done in amateur circles, but no one will go out on a limb as to its accuracy. Except me. We know that the ordinary lamp filament has a positive temperature coefficient. Fig. 5 illustrates the variation of a typical lamp filament resistance with input power. By keeping this in mind, fairly good accuracy can be had. Of course, if you use a different lamp, the curve will still apply, but the resistance will be different.

You can run your own graph, however, by using the setup shown in Fig. 2. Either dc or ac can be used, and since the lamp has little inductive or capacitive effect, the readings taken will be good to better than 100 mc. After you have a graph on the lamp you are using, you can effect any kind of impedance match you wish.

Using a lamp as a load simplifies the problem of power measurements because loads for this service are hard to come by. Power resistors are too inductive, and when they approach 1000 watts, they become downright expensive. However, even a 1000 watt lamp is not too expensive.

Fig. 1 shows the circuit that I used as the basis of this article. A standard 150 watt lamp was used here as a load. The photocell is mounted about five inches from the bulb. A wooden box houses the wattmeter, completely sealed internally against extraneous light. Figs. 3 and 4 illustrate the variation of resistance of the photocell with variation of power applied to the lamp. Even very small amounts of power are measureable, if the cell



Fig. 2. Method of calibrating lamp and determining resistance.



Fig. 3. Response of CdS cell to 150 watt lamp.



Fig. 4. Response of cell to 7 watt lamp.



Fig. 5. Resistance versus power input, 150 watt lamp.

is shielded from external light.

The wires from the input connector to the lamp are kept as short as possible by removing the lamp base and soldering the lamp wires directly to the coaxial connector. Switch S1 selects three ranges, which can be set by the builder to anything he desires. In my case I used three ranges which cover from 0.5 watt full scale to 250 watts full scale. With some photocells a 1.35 volt mercury battery can be used instead of the 4 volt battery shown. Also, I used a 50 microamp meter, because of convenience (mine), but even a 10 ma meter will work. Don't exceed the rated power dissipation of the photocell, and remember this may derate with increasing ambient temperature. One thousand watts in a box can be a lot of ambient temperature.



Fig. 6. Calibration curve for Light Wattmeter.

Getting back to the accuracy, if I were to tell you what the meter would read with such and such a lamp, and a given power input, your calibration would be off ten to twenty per cent when the construction was finished. The best way of getting a good calibration is something you've heard before; "if you want a job done right around here you've got to do it yourself".

Now obviously you can't calibrate the wattmeter at 14 mc, because this is what you are trying to measure to start with. Luckily the light from the lamp filament is primarily a power function, and it doesn't matter whether this is dc power, or 100 mc power.

So, to calibrate the wattmeter, apply ac or dc as you wish. Measure the input voltage and current, and read the meter. Make a graph of input power vs. meter reading, and there you have it. Fig. 6 is the graph that I use with the circuit in Fig. 1. Keep the impedance variation in mind, and select a lamp with the power impedance so that standing waves won't eat up lots of your power. As a dummy load and approximate power indictor this is not too critical, of course. But if you wish accurate power measurements, your impedance should be approximately matched.

LOW POWER LIGHT WATTMETER

Bill Hoisington K1CLL

This article describes a very useful gadget for determining the rf power output of solid-state VHF–UHF transmitters in the difficult range to measure, from about 10 mW up to 5 watts. It does not read watts directly; but by a simple comparison of calibrated pilot light brilliance, it will tell you how many watts you are putting out, to within less than 5%. It allows you to check power increases and estimate your efficiency quite close.

Principle Involved

We'll start right in with this part because, while this unit is not by any means a "trick," it does not read rf directly. You first light a pilot light as a good dummy load, matching it into the rf tank circuit of your transmitter by the normal means, also noted here.

You then switch on a second bulb of the same type by means of a battery, controlling the light output with a $1.30 wirewound potentiometer in series, as shown in Fig. 1. This pot must be previously calibrated in milliwatts, as by the method of "volts times milliamperes equals milliwatts." You then match the brilliance of the bulb lit up with rf or its dull glow at some 18 to 25 milliwatts if you're just getting your transmitter going, and read the watts on the wattmeter dial. It's astonishing how well it works, how repeatable it is, and how you wouldn't be without it once you build and calibrate it.



Fig. 1. The circuit supplies the brilliance "standard" for comparison. When the "standard" lamp is mounted adjacent to the dummy load, the pot permits variation of the standard to match the load. If the resistance is panel-marked in watts, a good power indication is achieved.

Brilliance Standard

Figure 2 tells almost the whole story at a glance. You can, of course, put as much calibration on the dial as you have time for. It is quite important to orient the bulb filaments in the same relation to your eyes for best matching. There isn't much in back of the panel except one 6V battery which can be obtained in any hardware store.


RF IN
E
B
C
450 MHz AMPLIFIER
TAB CAPACITOR, SPACED 1/32 in. TO 1/8 in. FROM GROUND PLANE. ABOUT 3/8 in. SQUARE
WIRE LEAD NO LONGER THAN 1/8 in.
3-10 pF

Fig. 3. Matched pilot light load for the UHF version.

RF Matching

Not that it is particularly critical, but be sure and note the need for a large range of series capacitors for the rf pilot lights as you go up in frequency. This can be seen clearly in Figs. 2 and 3. The block diagram, Fig. 2, shows a 6 meter setup. As you go up in frequency the series capacitance drops. A good matched load on 432 MHz can be obtained as shown in Fig. 3. I sometimes remove the tin base from the bulbs, but this is not an absolute neces-



Fig. 2. A series capacitance loads the rf indicator for comparison. The capacitance value will decrease inversely with frequency increases.

sity. It is important to vary the amount of coupling, and thus the series capacity, by spacing the tab capacitor closer or further away from the ground plane, as detailed in Fig. 3. You also can use as many bulbs as you can solder onto a tuned rf inductor, even though they don't all light up with the same brilliance. You can match them all up, but you don't have to. Just check the wattage, or milliwattage, of each one and add them up for the total.

The number 48 or 49 bulb, listed at 2V and 60 mA, is rated at 120 mW, and glows dim at about 12 to 15 mW; so it can be used for low-power receiver oscillators, etc. With two other bulbs found in hardware stores, connected and matched to the rf inductor, such as the PR13 (5V at 500 mA), you can read correctly up to 5W. From there on up you're on your own, although a good variable 115V dc supply can be made up to work around 50 to 100W. I generally use a variety of 115V bulbs of different wattage, light them up with rf, and use their rated wattage.

YET ANOTHER LIGHT WATTMETER

John Meisner K5CXN

Many VHF operators would like a cheap, accurate instrument to measure rf power. The same desire is frequently expressed by operators of the HF bands. Here is a very simple wattmeter which when used with a 50Ω transmission line or load has all of the following desirable characteristics:

1. Easily calibrated to good accuracy (±5%) with your multimeter and a variable dc source;
2. Perfectly flat from dc to 450 MHz;
3. Insertion VSWR less than 1.05
4. Power readings in the 2 to 50 watt range (higher power can be measured with slight design changes);

The operating principle of this wattmeter is stark simplicity. A pilot lamp across the rf line senses a small portion of power in the line and glows brighter with increasing power. An appropriately located photovoltaic cell connected to a microammeter measures the light output which is proportional to the power flowing in the line. Of course a good deal of nonlinearity is involved in the various elements – both the lamp's resistance and its spectrum output change with heating; output of the photovoltaic cell varies considerably with both the amount and frequency of the light shining upon it. Some of these factors tend to cancel out however, because the photovoltaic cell produces some current with only infra-red lamp output at low power levels before the lamp even produces a visible glow, and the cell tends to saturate, increasing its output quite slowly at more intense illumination levels.

Probably the biggest single requirement of any wattmeter is that it must be capable of being inserted into a transmission line without disturbing the operating conditions in the line (low insertion VSWR). It might be argued that hanging a lightbulb across a transmission line will seriously affect the line impedance. Ordinarily, this is true, but the undesirable changes can be minimized and indeed approach an insignificant level if the resistance of the lamp filament is very large when compared to the line impedance. In general, a factor of 15 or more times the line impedance is sufficiently large to produce negligible effects. In the case of the suggested 10V, .014 Ampere pilot lamp, the mismatch produced in the line gives a VSWR of 1.05:1 at the power level of 1 watt. This mismatch decreases rapidly with increasing power. It falls to well below 1.01:1 at 50 watts. Another point of interest with regard to this particular choice of lamp is that it is a long-life type with a life expectancy of 10,000 hours. This implies two advantages: (a) The lamp will operate at well over its rated voltage without burnout (50.0V at 50 watts), and (b) the interior of the lamp envelope will resist darkening which would negate the wattmeter calibration. In addition, the filament structure of this type of lamp is a single-strand straight tungsten wire. The coiled type of filament structure introduces undesirable inductance into the circuit which can distort wattmeter readings in the UHF range.

The wattmeter shown is constructed in two boxes for the sake of convenience. The sensor can be located in the transmission line at any point and the meter can be placed beside the transmitter. For test work, the whole unit could easily be put into a single box. Coaxial fittings and cable were used for interconnection, but since dc only flows in this circuit, any type of wiring would be satisfactory.

The photovoltaic cell used in this wattmeter is a unit obtained from the local Allied/Radio Shack store. (Catalog No. 276-115.) Output of the cell is rated .5V at .6 mA in sunlight.



Fig. 1. Schematic diagram.

Since the cell generates considerably more than 20 mA under moderate illumination, a switching arrangement is incorporated into the wattmeter to shunt it into progressively higher current ranges with increasing power. Alternatively, a 50 or 100 milliammeter could be used with less switching at a sacrifice of sensitivity in the 1–3 watt range.

Calibration of the wattmeter is a simple process. By solution of the formula $P = V^2/R$ for voltage, the following tabulation is made for a 50Ω line impedance:

VOLTAGE (rms or dc)	POWER (Watts into 50Ω)
7.07	1
10.00	2
12.24	3
14.14	4
15.71	5
17.32	6
18.71	7
20.00	8
21.21	9
22.36	10
31.62	20
38.71	30
44.71	40
50.00	50

Using the tabulation, fasten a metered variable dc supply into the wattmeter according to the following diagram. Now simply note the reading on your wattmeter for each of the selected voltages in the table and tabulate this reading with the corresponding power in watts in a table of your own. It may even be possible to remove the front of the meter case and mark new calibrations directly on the dial. This was not possible with some hermetically sealed meters. It is best to disconnect the wattmeter from the antenna feedline for this calibration. If the meter is left with a transmission line attached and the antenna happens to be fed through a balun device with near zero resistance, the power supply, and perhaps the balun, will suffer.

It must be pointed out again that this power meter is intended for use either with 50Ω coaxial line systems with low VSWR or with 50Ω dummy loads. A coaxial line that is not "flat" (unity VSWR) or a dummy antenna that does not look like" 50Ω, which is the case with



Fig. 2. Calibration diagram.

most HF loads used at VHF or UHF, may cause distorted power readings. If you have doubt about your transmitter's power output when using this meter, you should check it while using a known 50Ω load rated at the transmitter's output frequency.

I mentioned before that this power meter was easily adaptable to higher power readings. To upgrade the meter, the only change required is to insert the correct higher voltage pilot lamp having low current, long-life specifications. Suggestions for some of these are the following Dialco Lamps:

Part No.	Max Power Level (Watts)
24CS	100
48CS	200
60PSB	340
120PSB	800

A LOW COST RF WATTMETER

Mark Leavey WA3AJR

You say you just finished building that 2 meter rig and want to find out how much power you're running but can't afford to buy a wattmeter? You've been calling "CQ 80 QRP" all day with your quarter-watt wonder and nobody is answering? Then get yourself up, go down into the workshop, and build yourself a neato-keeno handy-dandy wattmeter.

If we are going to build a wattmeter, let's consider what we want. Accuracy and ease of calibration, as well as simplicity in construction are prime requisites. The meter described here is as accurate as components allow, and it's easy to build. The calibration is logarithmic, which means that a simple graph is possible, and easier than changing the meter scale.

For the mathematicians, I will present the formulas upon which this device is based, and ways of modifying it; for those of you who avoid math whenever you can, look at the graphs and skip these few paragraphs.

To spare undue complexity, assume 51Ω line – other values can be dealt with later. Perhaps the easiest parameter to measure, and one that is proportional to power, is rf voltage. A voltmeter can be made most easily with a series resistor and a 0–1 mA meter. Now let's plunge into the actual calculations.

Assume W is the full-scale meter reading in watts, Z is the line impedance, E is the voltage measured, I is the full-scale meter reading in amps of the basic meter, and R is the value of the series resistor in ohms. We know that the voltage (IR) is equal to the square root of "impedance times power," or 14.270V. Now, since the voltage and the current (.001A because the full-scale movement is 1 mA) are known, simple division yields 14,270. The resistor value, then, is 14.270 kΩ. The upper portion of Fig. 1 is a graph that will enable the nonmathematician to choose the value of the resistor for full-scale readings up to 4 kW, with 51Ω line and a 0–1 mA meter.



Fig. 1. Logarithmic plots for determining power. The upper curve gives resistance values for determining what the full-scale meter deflection will be (remember to multiply the series resistance value shown on the chart by 12 kΩ). The lower curve will allow you to determine your precise power out if you use a 0–1 mA meter.

Why 4 kW with an amateur power limit of 1 kW? A look at the bottom half of Fig. 1 will explain. Although this is the calibration of the prototype, for 4W full scale, it will double for 40, 400, or 4000W. A half-scale reading, 0.5 mA, corresponds to 1W (1 kW, etc.). This spreads out the range below 1 kW for ease of reading and measuring.

Now get out that soldering copper and gas pliers, and build it. As the schematic (Fig. 2) shows, the circuit is a basic rectifying type rf voltmeter. The prototype was built in a small can of the plug-in-module variety that was scrounged from the junkbox. About the only critical part is the series resistor. The capacitors in the prototype were mica, but ceramic disks would work as well. The diode can be a 1N34A, 1N270, 1N52, 1N38A, or just about anything else. Use the old ham's rule of thumb: "When in doubt, try it out!"



Front view of unit.

Two sockets might prove more convenient rather than one with a coaxial tee as shown. Conventional minibox construction or building into a new or existing rig will be more than adequate. Point-to-point wiring is used to permit compactness and reduce lead length.

"Fine," you say, "but I don't have a huge mound of test equipment. How do I calibrate it?" That is the beauty of it – you don't! If the series resistor is accurate, the meter will be self-calibrating to a log scale. Remember, you know R and Z, and the full-scale W. Now assume a half-scale



Fig. 2. Schematic diagram of the simple, accurate, and easy-to-build rf wattmeter.



Connection to transmitter with dummy load (see text).

reading, I = 0.0005, and calculate W for half-scale. Plot these two points at 1.0 and 0.5 mA on Fig. 1, and connect by a straight line, which you may extend the length of the graph.



Connection to transmitter with antenna connected.

Install the meter through a coaxial tee at your antenna connector, or through some other predetermined means, and terminate with a dummy load. The one seen in the picture is three 150Ω resistors in parallel, dipped in epoxy, shielded with a copper braid, and installed on a BNC plug. Apply power and read the meter. That's it! The meter can be used with an antenna if your swr is below about 1.2:1.

So what did I promise? A low-cost, rf wattmeter that is inexpensive enough for the Novice, practical and useful enough for the General, and "Extra" accurate. Go raid the junkbox, and add a worthwhile piece of gear to your shack.

RF POWER MEASUREMENT USING HOT CARRIER DIODES

Frank Jones W6AJF

Two rf wattmeters are shown here, one with a range of 25 mW to 10W and the other covering the range of 5 to 300W. Both are useful from low radio frequencies on up through 450 MHz.

The low-power version (Fig. 1) makes use of a 20W Sierra dummy antenna built into the meter case, though the metering circuit only goes up to 10W. If the maximum is to be 20W, the reference meter reading could be about 45 μA instead of 30. The minimum power reading would be doubled. In this wattmeter, the power range potentiometer is calibrated and only a reference line on the meter is used when making rf measurements. The dummy 50Ω antenna resistor is rated up to 1000 MHz so is excellent from 450 MHz down.

The range potentiometer had an audio (nonlinear) taper. By connecting the "high" resistance end to the diode, the watt range scale is spread out quite well in the 0.1–10W range. The hot carrier diode, an HP 2900, has a 10 PIV rating, which means that the rms rf voltage across it should be less than 3V for safe operation. At 10W of rf power, the rms voltage would be a little over 22V, which means a voltage divider is needed to keep the applied diode voltage down to about 2V. An HP 2800 diode with a 75 PIV rating would be more desirable, especially if the meter was to be calibrated for 20W maximum. This diode is about $1 and has a little higher capacitance, which would require a different shunt capacitance across parts of the resistor divider to make the device work with the same power range calibration.



Bottom view of 10W unit with the rf dummy antenna clamped in one corner.

WATTS
.025
WATTS
Adj. to line
ON
OFF
R.F. WATTMETER

Top view of low powered rf wattmeter covering .025 to 10W. Built into a 8x4x2 chassis with wire screen bottom plate for ventilation.

The divider should use ½W resistors of the carbon or metal film type, since these units are part of the rf circuit. It is better to use three ½W 300Ω resistors in the string rather than a single 900Ω 2W resistor; this is because the rf resistance characteristic is usually better in ¼ or ½W types in certain ranges of resistance. Every resis-



Fig. 1. .025 to 10W RF wattmeter.

tor has some inductance and shunt capacitance which becomes part of the voltage divider. The diode shunt capacitance is in parallel with that of the 110Ω ¼W resistor in Fig. 1. However, nearly any combination of resistor sizes can be equalized within 10 to 20% over the desired frequency range. This divider is across the 50Ω dummy antenna, so should not shunt the value down to less than 49 or 48Ω. This divider has to dissipate a little rf power also. Its total resistance should be at least 20 times as high as the dummy antenna load resistor.

The values shown in Fig. 1 are just about the minimum that should be used. Too high values makes it more difficult to extend the frequency range to the upper end, though it can be done, as was discovered in the higher-powered wattmeter of Fig. 2.

All diodes are poor rectifiers at applied rf voltages below their forward bias values of 300–700 mV (peak). By using a forward dc bias voltage to make the diode conduct at least 5 or 10 mA, the detection sensitivity is increased as much as 5 or 10 times. This requires a small battery, a couple of fixed-value resistors, and an adjustable pot to balance this current out of the meter when measuring rf powers below 100 mV. If the power range is limited to a minimum of ¼ or ½W, no bias circuit is needed in this 10W instrument. The range scale in either case has to be hand calibrated.

A low-powered radio transmitter or exciter can be used as a 10W power source when calibrating the power range pot scale. The transmitter can use stage detuning to reduce power outputs down to the lower values needed. Many swr meters have watts of power calibration and one of these can be put in the coax line to the rf wattmeter for calibration service. A more accurate calibration can be made by comparing the power readings against some reliable commercial rf wattmeter within its frequency range and calibration charts. This scheme is usually necessary for checking the calibration at VHF or UHF. Another method is to use an accurate rf voltmeter across the dummy antenna connection to ground and read the power values in watts = E^2/R. For example, 5V (rms) squared is 25; and divided by 50Ω is equal to 500 mW.

The Sierra 50Ω dummy antenna has no connection available at the high end of the resistor, which terminates in a type N fitting. The metering circuit has to connect to this point as close as possible by getting into the inner conductor of a coax fitting, or by drilling a 3/8 or ½ in. hole through the shell of the dummy antenna close to the rf fitting end. This can be done and the first 300Ω resistor in the voltage divider soldered to the inner connection to the large 50Ω resistor. A long 1/8 in. diameter soldering iron tip is needed. The divider resistors, diode, and four .001 μF stud-mounted bypass capacitors were all mounted around this large hole in tapped 6-32 holes for the four capacitors. Larger values of bypass capacitors can be shunted across these 0.001 μF values to ground to extend the frequency range down to low rf or even af values. For example, a .02 μF capacitor shunt would allow operation to 2 MHz. A miniature 50 or 100 μF electrolytic shunt would function at audio frequencies down to 300 Hz. The diode must have a low-impedance path to ground over the desired frequency range to function as a peak rectifier and get as much dc output voltage as possible for the meter circuit. The microammeter in series with a variable range resistor is simply a dc voltmeter. The diode rectifier converts rf voltage to dc, so the diode should be equally efficient over the whole rf range.

The 5–300W unit was built to use with a large dummy antenna rated up to 500 MHz, which is a massive unit external to the box shown in the photographs. Quite a bit of rebuilding went into this device to make one calibration of the range potentiometer fit all frequencies from 450 to 2 MHz. The input and output coax fittings had to be finally mounted so the inner conductor tips could be soldered together and the resistor divider connected to this point. The latter consisted of two 4300Ω 2W carbon resistors and a 68Ω 1W resistor in series to a copper sheet inside of the aluminum box.

The watt range variable resistor was a 500 kΩ linear potentiometer which was limited to a lower value by shunting it from the moving arm to the diode connection end with a 220 kΩ resistor. This gave a maximum power reading of 300W when the reference line was drawn on the meter face at 12 μA. The import, low priced, 0–30 μA meter had a large meter scale. A smaller 0–50 μA meter would have been usable, since the meter is used only as a reference. The range pot knob is adjusted when rf power is applied to run the meter reading up to the line drawn on the meter scale face.



Top view of 5 to 300W metering circuit for use with external high powered dummy antenna.



Fig. 2. 5 to 300W RF wattmeter metering circuit. External 300 or 400W during antenna load.

The circuit shown in Fig. 2 was equalized to within about 15% error over the range of 2 to 450 MHz by shunting a 5 pF capacitor across the 68Ω resistor in the rf divider.

Calibration of this device was made at 144 MHz using a transmitter having up to 400W available carrier output. The meterizing unit was connected to a large Bird rf wattmeter at the external fittings of the latter. Several thermocouples had to be used to cover the wide range of power for the calibration. This required reading a chart curve for each Bird wattmeter reading and using correction factors for frequency in order to obtain the actual watts of rf power. Now, the large unit is used without the thermocouples, charts, rf choke, etc. simply as a dummy antenna. The new metering circuit connects directly into the antenna fitting, with a few feet of 50Ω coax over to the transmitters being tested.

This power measuring device can be used in any 50Ω coaxial line to monitor the actual power going toward the antenna. The swr in the line should be low, or near unity, in order for the calibration to be reasonably accurate.

VHF DUMMY LOAD WATTMETER

Glen Zook K9STH

The unit

The unit described herein is similar to some 60 watt units which may be found around many commercial two-way radio shops. This dummy load has provision for connection to an external relative output meter. This external output meter may become an accurate wattmeter if the following criteria are met:

1. Frequency bandwidth of ±10% of calibration frequency.
2. RF output kept within power dissipation of dummy load.
3. Accurate initial calibration.

These criteria may be easily met in amateur vhf operation if only one band is considered for each set of calibration data. Since most vhf amateurs operate on 50 mhz, 144 mhz or 432 mhz, the ± 10% frequency limitations may be easily met. This limitation gives a 10 mhz bandwidth at 50 mhz, 29 mhz bandwidth at 144 mhz, and 86 mhz at 432 mhz. The limitation to the power ratings of the dummy load is only common sense, for if a resistive network is overloaded, the impedance may be drastically increased, caused by damage to the load resistors. The calibration limitation may be overcome if a standard, previously calibrated unit, or commercial unit is used.

The unit consists basically of 16 220 Ohm resistors in a series parallel arrangement. The metering circuit consists of a germanium diode pickup with necessary rf filtering. The meter movement is generally a vom, but any 50 ua meter movement should suffice. Exact physical layout is not extremely critical, but it is suggested that the layout be made similar to the unit shown in the accompanying photographs. This unit is acceptable for 60 Watt output transmitters without modification. The power capability may be increased to about 200 Watts if the resistive network is suspended in 1 quart of oil. If this is done, care must be taken to keep the metering circuit out of the oil. The lead from the diode to the resistive network must, of course, be partly submerged, but keep the diode itself out of the oil. I do not personally use this arrangement, but I know of two units which have been in use at a large Southeastern two-way radio shop for several years. The same shop has incorporated a range switch with several meter shunts for various maximum scale power readings. This feature is especially useful to the amateur vhf FM operator who may be working with equipment of from ½ to 250 Watt outputs. The schematic appears as Fig. 1, and the basic circuit for various meter shunts as Fig. 2.



Fig. 1. Schematic. R1 and R2 consist of eight resistors each, in parallel.



Parts layout and interior view of Dummy Load – Wattmeter



External view.

Calibration

Calibration is best accomplished by using a Bird "Thruline" or similar commercial vhf inline wattmeter. Second choice is a Bird "Termaline" or similar dummy load-wattmeter. In both cases, a graph should be created by plotting meter divisions on the horizontal axis, and power on the vertical axis. The meter shunt should be placed at minimum resistance and increased to give maximum reading at the desired power level (this holds primarily true for units using the metering circuit of Fig. 2) or, if a vom or vtvm is being used the range switch should be placed on a high voltage setting and reduced a setting at a time until the desired reading is obtained. The transmitter should be adjusted for various power levels on the standard wattmeter and the voltage or current reading on the new meter recorded on the graph. In the case where the standard meter is of the dummy load-wattmeter type, it will be necessary to switch the coax from one unit to the other. Do not retune the transmitter, for each unit will present almost the same load to the transmitter (50 ohms). Take the reading and record as with an inline type of meter. The points on the graph should now be connected with a smooth curve (use of a draftsman's



Fig. 2. Metering shunts.



Using the Dummy Load – Wattmeter to check output of FM unit.

range switch is used, it will be necessary to calibrate for each switch position. Also, if multi-band use is expected, the graphs must be made for each band. Use of the wattmeter now requires only the connection to the transmitter, setting of range switch to the proper level, and reading the graph.

Uses

The uses of this dummy load-wattmeter are as varied as the amateur mind can devise. One very important use is determining the losses of 50 ohm coax. Measure the output of the transmitter at the transmitter. Then measure the output at the end of the length of coax. The losses in the line become apparent. The loss in db may be calculated by the standard power ratio formula, 10 $\log_{10}$ Power out of coax/Power into coax.

Another use is the determination of efficiency of final amplifier stages. This efficiency may be calculated by Power out (measured by dummy load-wattmeter)/Power in (measured by plate current/plate voltage meter) x 100%. A third use is determining once and for all which amateur really has the most output. This list may be expanded by the builder to suit his own tastes.

Conclusion

This dummy load-wattmeter is not a Bird "Termaline" nor should it be regarded as a substitute for any other laboratory equipment. However, with a little care in calibration, (assuming a 5% accuracy standard is used for initial calibration) the accuracy should be within 10%, and this, my friend, is not bad for a wattmeter costing less than $10.

Chapter IV

Measure Your Field Strength and Frequency

THE RF SNIFFER

Jim Kyle K5JKX

Every now and then there's a need to know if any rf is present in a circuit. Frequency isn't so important—the question is simply. "Is there rf here?"

Your grid-dipper can frequently answer this, if used in the wavemeter mode, but occasionally it's not sensitive enough—particularly if you're working with a receiver oscillator where power is measured in microwatts.

Here's an rf Sniffer which will indicate the slightest trace of rf in a circuit. In addition to checking receiver oscillators, it's a perfect gadget to ensure perfect neutralization of a transmitter final.

Connect the components as shown in the schematic. Use long-nosed pliers as a heat sink between the diode and the solder joint when wiring, to prevent diode damage. Note that the pickup loop of 14 gauge wire is insulated with a strip of spaghetti.

Mount capacitor and diode on back of meter with shortest possible leads. Attach pickup loop directly to negative meter terminal; it's stiff enough to do without other mechanical support.



Amplifier Neutralization—Couple the Sniffer to the antenna terminal with a temporary two-turn link around the pickup loop. Remove plate and screen voltage from the final amplifier. Apply drive. Adjust neutralization for minimum indication on the Sniffer—but don't expect to be able to get it down to zero.

Oscillator Checking—Place the pickup loop near the oscillator coil. If the oscillator's working, the Sniffer will indicate rf. Touching either the grid or plate lead (use an *insulated* tool for this test, not your fingers) should reduce the Sniffer's indication.

Receiver Troubleshooting—Check the oscillator as described above. If it's okay, next check the mixer plate coil by placing the Sniffer pickup loop near it. If you get an indication here, move to the first if stage and place the pickup loop near the plate pin of the tube socket. Proceed through the receiver until you lose the indication. The trouble is somewhere between the last indication and the point at which it disappeared.

Field Strength Meter—Couple a short antenna to the pickup loop by two turns of wire around the loop. Field strength will be indicated in a comparative manner by the meter. It cannot be calibrated, but proves useful in tuning mobile or beam antennas, etc.

SWR Measurement—(Parallel lines only). Move the Sniffer long the line. Mark maximum reading and minimum reading over a half-wavelength. Divide minimum into maximum. The quotient is, roughly, your VSWR. This method is by no means exact, but will indicate whether the line is under or over a 2:1 SWR.

UHF Frequency Measurement—Set up Lecher wires. Couple the rf Sniffer lightly to the tank circuit instead of using a flashlight bulb. Use Lecher wires in normal fashion, reading Sniffer indications for maximum and minimum. This is much more exact than the normal methods.

Improvised Grid-Dipper—If you have a signal generator available, it can be used with the rf Sniffer to serve as a "grid-dip" meter to locate resonance for any tank circuit. Couple both the generator and the Sniffer lightly to the unknown tank. Vary generator frequency. A sharp rise in Sniffer indication indicates the resonance point.

THE PINK TICKET REJECTOR

A. D. Taylor GW8PG

Hams sometimes get into trouble with the FCC because they have made a mistake in tuning a frequency multiplier or PA stage. For example, if the multiplier stage following a 3.5 MHz oscillator is accidentally tuned to 10.5 MHz instead of 7 MHz, the PA can be loaded on 10.5 MHz; and if this is done even a short transmission is likely to produce an unwanted "QSL" from the FCC! Mistakes like this can be prevented by using the simple, easily built absorption wavemeter shown in Fig. 1. Only one coil is required in this meter, the low frequency range being obtained by switching a padding capacitor in parallel with the variable tuning capacitor. With switch S1 open the tuning range is approximately 6.8 to 30 MHz, and with S1 closed it is approximately 3.5 to 6.8 MHz.

Construction of the wavemeter is simple. It can be put together in a metal utility box, on a wooden panel and baseboard, or even in a cracker can of the right size. The coil can be wound on any type of ¾ in. diameter form. If nothing else is handy, a short length of dowel could be used. The coil winding consists of 7 turns of 20-gage wire, close wound. Both the tuning capacitor (C1) and the padding capacitor (C2) should be 500 pF components, but the values of the other components are not critical.

Any meter having a full-scale deflection between 100 µA and 1 mA can be used. If the wavemeter is built in a metal box, L1 must be mounted outside the box. A slow-motion drive is not needed. If C1 is fitted with a pointer type knob and a cardboard scale is cemented onto the front panel, the calibration points can be written on the scale in ink.



Fig. 1. L1 – 7 turns 20 gage enameled copper wire, close-wound on a ¾ in. form; C1 – 500 pF variable capacitor; C2 – 500 pF fixed capacitor; C3 – Fixed capacitor, any value between 1000 pF and 0.01 µF; D1 – Silicon or germanium; M1 – Moving coil-meter (100 mA–1 mA).

When it came to calibrating the wavemeter I thought of a simple method that I have not seen described before. I soldered about 2 in. of wire onto one end of L1, and about 10 ft of wire onto the other end. I then connected the short lead to the antenna terminal of my receiver and strung the 10 ft of wire up as a temporary antenna. I then tuned the receiver to a steady signal at each frequency at which I wanted a calibration point, and adjusted C1 until the strength of the received signal suddenly dropped sharply, indicating that the wavemeter was tuned to the frequency of the signal. I was then able to mark this frequency on the cardboard tuning scale. The drop in signal strengh was very sharp so calibration was easy. Once enough calibration points had been obtained the temporary wires were unsoldered and the wavemeter was ready for use.

The only frequency which may require a little adjustment is 30 MHz. If the wavemeter will not tune as high as this, push the top turn of coil L1 about 1/8 in. away from the other turns. This should reduce the inductance sufficiently; a spot of cement will hold the turn in its new position.

To use the wavemeter for checking a transmitter, bring coil L1 close to the tank coil of the stage being checked, apply power to the stage and rotate C1 until a maximum reading is obtained on the meter. The output frequency of the stage can then be read off from the wavemeter tuning scale.

The wavemeter can also be used as a radiation meter for tuning up single-wire antennas. If it is tuned to the transmitter output frequency and placed near to the antenna wire, maximum reading on meter M1 will indicate maximum output power from the transmitter.

Many readers will have realized that the calibration method I suggest uses the principle of the rejector circuit. That is why I have called the little gadget "the pink ticket rejector"!

A USEFUL ACCESSORY FOR THE HAM SHACK

Rex Morris W2WHX

BECAUSE we are dealing with something we cannot see, namely electrons and electromagnetic radiation (we only see their effects), we must acquire the ability to use test equipment, in order to understand and find our way in this invisible realm.

The piece of test equipment about to be described is one of the more useful instruments that the amateur should have in the shack. While this instrument serves primarily as a field strength meter, it will also serve as a phone monitor, neutralization indicator and a sensitive wavemeter.



Referring to the circuit diagram, meter M1 is a sensitive instrument which indicates the pressure of rf when the device is used as a field strength meter, wavemeter or neutralization indicator.

To use this instrument as a wavemeter, a pickup loop is substituted for the short whip antenna at the top. Switch S1, the band switch on the right of the panel, is placed on the proper position. Coil L1 tunes the vhf range of approximately 90 mc to 170 mc (2 meters). L2 tunes 28 mc to 100 mc (10 meter and six meter bands). L3 tunes to 7 mc to 30 mc (40, 20, 15 and 10 meter bands). L4 tunes from 2 mc to 7 mc (80 and 40 meter bands). With switch S1 on the proper tap, condenser C2, on left of panel, is used to peak the reading on meter M1. Using a calibrated dial, frequency may be read directly. Toggle switch S2 is a high-low range switch for meter M1, providing a means of keeping the meter on scale and protecting it against burn-out. Potentiometer R1 (center of panel) is a vernier shunt control, also for keeping the meter on scale.

For use as a phone monitor, rf should be fed into the input jack with a link or pick-up wire. Once again the LC circuit is resonated to the frequency we desire. Earphones inserted in jack J2 will open the meter circuit and allow you to monitor the signal. Switch S2 is placed in the Hi position.

Field strength readings can be taken by using a short pickup antenna. Again the LC circuit should be tuned to resonance. Meter M1 will give an indication of field strength.



With switch S2 in the Hi position the meter is very sensitive and potentiometer R1 is a variable shunt providing much range of scale adjustment. For use as a remote reading field strength meter an external microammeter (with up to 200 feet of wire) may be plugged into J2. For making transmitter adjustments this is a very desirable feature.

Now notice that one position on the bandswitch S1 is vacant, this vacant position provides a very broad band—low sensitivity position for those extremely high rf fields where even R1 and S2 cannot provide enough attenuation.

Neutralization measurements are made by coupling the instrument through a pick-up link to the tank coil involved, with S2 in the Lo position. When the instrument is tuned to resonance it becomes a very sensitive rf indicator. It is so sensitive that it will readily be seen that complete neutralization exists in theory only.

As in all simple gadgets there are a few simple construction techniques which make the difference between gadget and instrument. In this case the important thing to keep in mind is that from the antenna to the crystal is the rf portion, and from the crystal to the jack J2 is the dc portion (with audio superimposed). With this in mind, construction is such that the two parts are separated, thereby giving some measure of protection from rf energy to the very sensitive microammeter M1. Also note the extensive use of sheet metal screws on the aluminum case. The only rf we want to enter the case is the rf we are attempting to measure via the antenna jack. Note again, we have here an instrument for detecting electromagnetic radiation, from approximately 170 mc to 2 mc. We now have an instrument for visualizing what cannot be seen.

The usefulness of this instrument is limited only to one's ability to apply it and interpret the results it gives. These only come with experience, trial and error and determined application.

Coil Data

L1—One turn hairpin loop.
L2—5 turns of #18 enamel wire space wound 1" dia.
L3—24 turns #22 cloth covered wire, close wound, ⅝" dia.



TWO THRU TWENTY FSM

Howard Pyle W7OE

I used a small LMB aluminum meter cabinet with a hole for a 2" meter; any equivalent cabinet can of course be used. With a small enclosure such as this (4"x4") the meter occupies the face of the cabinet and all controls are on the rear. Using a somewhat larger housing both the meter and the control knobs can be placed on a front panel if you prefer.

Rather than wind up the three coils I found that the J. W. Miller Company RF chokes with minor modifications were admirably suited for a compact job. One each of their catalog numbers 4606, 4588 and 4580 were required to cover the three frequency spreads from 2 through 20 meters. The #4606 coil should have five turns carefully removed, to cover the 10-20 meter bands; remove three turns from #4588 for six meters and two turns from the #4580 coil to handle 2 meters. These can all be resonated with a 50 pf midget variable tuning capacitor; a Hammarlund HF-50 or the equivalent is excellent. Any of the small multi-point selector switches can be used for band switching. A JBT lever switch type SS-14-ILS will handle the job or, if you prefer a rotary switch you can use a Mallory type 3215J as I did, leaving two positions unused. (I might want to add a couple of coils and try 40 and 80 later!).

MIN
6
10
15
MA
20
BAND
ON
OFF
PHONES

Resistors R-1 and R-2 shown in the schematic, need be only ½ watt. A single flashlight cell will serve for the battery although I chose a 1.4 volt mercury transistor battery to conserve space. Other items shown on the schematic are obvious and all parts are readily available from most electronic parts distributors as well as from the electronic mail order houses.

Build this little F/S meter and know what your VHF outputs are doing. If you want to check your modulation quality, a phone jack may be added as shown, making this little gadget really versatile.



Side view of the FSM.



Fig. 1. The bandswitching, transistorized field strength meter for two through twenty meters.

AN AMPLIFIED, CALIBRATED SIGNAL STRENGTH METER

J. L. Iliffe VE3CES

Recently, I had the problem of tuning a four element quad. As you may or may not be aware, these beasties are supposed to be tuned from the rear for minimum signal. A quick check showed none of my friends had a signal strength meter, so I prepared to degrade myself and buy one. A look at a few prices convinced me to build.

Since I wanted some other information on the quad, like front to back ratio and the effect of more or fewer elements, I decided to add a calibrated attenuator and enough gain to make a fairly wide input range. It also had to be cheap!

The result is shown in Fig. 1.



Fig. 1. Diagram of the field strength meter.

To use the normal rf attenuator method of switched T-pads requires complicated shields and quite a few resistors. Also the attenuator has to be terminated in its characteristic impedance to read correctly. To bypass this problem I first detect the rf, then attenuate the dc. This has the added advantage that the circuit is no longer frequency sensitive.

The incoming rf is tuned by C1-L2. C1 can be any small variable. I used both sections of a dual 15 pF because my local surplus store has them for 60¢. For VHF use only 1 section.

L2 is wound on a plastic pill bottle about 1" in diameter and tapering to 7/8". To cover 13–24 MHz, I used 11 turns spaced over about an inch. L1 is 2 turns over top of L2. I tried bandswitching with another pill bottle fastened on the other side of the shield from L2. The idea was to bandswitch another frequency range but I find it more convenient to wind on coils as needed. Use the grid dipper to get you in the ballpark. I have used this meter as high as 72 MHz without trouble. D1 can be any diode. I used a 1N34 because I could then specify it and know it would work, but I tried a computer type which also worked. If you prefer the meter to peak rather than dip, reverse D1.

Rectified rf from D1 is put on the top of R1, the calibrated attenuator. R2 in series with R1 gives the 0 dB point at its junction. For a 30 dB range, R2 is 47K if R1 is 1 MΩ This doesn't quite fill the range but is close. Changing the value of R2 will change the range but 30 dB is considerably more than the F/B ratio of most beams.

Q1 is a 2N5033 FET. The high input impedance of Q1 allows us to set the calibration of R1 directly by dc voltage measurements on the VTVM since it does not draw any base (gate) current. It is a p-channel device. If you use an n-channel type you will have to change the entire biasing of the circuit and also reverse D1.

Q2 and Q3 form a differential amplifier to drive the meter. Q2 is necessary to avoid loading Q1 and I had quite a bit of trouble balancing the meter against battery voltage changes until I added Q3. It will now operate from 8.5–9.2 volts with no trouble. The 10K pot in Q3's base centers the meter. The meter I used is a 250 μA tuning meter with no markings on it except a red/white/blue bar. This is all you need since we calibrate on R1, not the meter.

Operation

The meter is quite sensitive and with a two foot antenna I could get a reading several hundred feet behind my quad at 60 watts input. First tune the input (which is quite sharp) with the attenuator set at zero. This is the least sensitive position. Now set the meter for a convenient reading near the center scale with the incoming signal still on using R3. Adjust your antenna. When you feed it power again the reading will not be quite on scale on the meter but turning up R1 will allow you to put the meter back to the original position. Do not touch R3. The reading on R1 is now the increased gain in dB needed to bring the signal back to its original strength. In other words, the decrease in signal strength.

Note that during measurements you need a received signal to use R1. With no signal the meter will be off scale.

I have also used the meter to align oscillators and doublers in my two meter receiver. A probe can be made for this from two turns of wire on the end of a piece of coax. The high gain available allows the pickup loop to be quite far away which reduces detuning. Adjustments show up well on the meter.

FREQUENCY MEASURING EQUIPMENT AT MICROWAVE FREQUENCIES

Silas Smith WA9VFG

This article is not intended to give the theory, but rather a practical solution to the building and use of wavemeters at microwave frequencies.

In microwave work, frequency is one of the most important measurements. It must be understood the wave length in the devices described here is not the exact frequency wave length. A well-constructed wavemeter that has been calibrated can be very precise. They can be within 1.5 MHz at 10 GHz or less than half of a MHz at 1250 MHz. Temperature has some effect on the frequency. Most commercial wavemeters are constructed of Invar, a metal that changes very little with temperature. Some parts are of bi-metal construction to compensate for temperature. For the average experimenter, brass and copper will have to suffice. Although silver plating is desirable, it isn't an absolute necessity. Frequency at microwave frequencies can be measured by three methods: wavemeters, slotted lines, and frequency comparisons. All of these methods are used commercially. The frequency comparison is usually used in the laboratory to calibrate the wavemeter and the slotted line. As a general rule, any method of frequency measurement used at lower frequencies can also be used at the microwave frequencies, but are not always practical. The resonate cavity as a wavemeter is used in microwave measurements.

There are three types of cavity wavemeters: the transmission type, Fig. 1A and 1B, the reaction type, Fig. 1C, and the assorption or absorption type, Fig. 1D. All are resonate cavities. The way in which the wavemeter is used determines the type.

All wavemeters are adjusted for maximum readings except the assorption type. The assorption is adjusted for a dip in power output. The most popular wavemeter used by the beginner is the open circuited transmission line type, Fig. 2. This type of wavemeter is the equivalent of lecher wires. (Open circuit refers to the standing wave within the cavity, not the physical construction except as it pertains to the frequency wave length.) The practical physical dimensions are not many. The inner circumference of the main tube should be less than one wave length at the highest frequency to be measured. The rod should be small compared to the tube. If inductive coupling is used, the inductive coupling should be close to the shorted end. For probe coupling, the probe should be close to the middle. The open circuited transmission line is generally used in two ways. This type can be used "in line' (Fig. 1B) as it has very little loss when it is resonated. However, it should be removed from the line before transmitting, as it will act as a narrow band filter. The half wave length is the measurement between the two successive points at which the generator will load to maximum, as the rod is inserted or withdrawn.



Fig. 1.



Fig. 2.

Another method in the use of the open circuited transmission line calls for the use of an additional circuit, as in Fig. 3. The circuit is a simple crystal diode detector connected to a microampmeter. The diode and condenser are usually built into the connector, as the leads should be kept as short as possible. The half wave length measurement is made on the rod between two successive maximum readings on the meter, as the rod is inserted or withdrawn. See Fig. 1A and 1B for the setup.



Fig. 3.

The quarter wave coaxial cavity is actually a shorted coaxial line one quarter wave length long (Fig. 4, 5, 6). As illustrated in these figures this type makes a very good cavity to use as a standard. To calibrate, a chart is made of the micrometer settings at different frequency wave lengths from a calibrated source generator. Don't tell them so, but the Public Relations Department of the Telephone Company may help you here, if they have any microwave technicians close by. The quarter wave coaxial cavity can be either physically open or closed. If closed, the closed end should extend at least a quarter of an inch beyond the center conductor at its lowest frequency. The closing of the end will lower the resonate frequency. Probe (capacitance) coupling as used for coupling in Fig. 5 will shorten the center conductor, and loop (inductive) as used in Fig. 4 will lengthen the conductor. In Fig. 4 we change the length of the center conductor to change its one quarter wave length. In Figs. 5 and 6 the center conductor remains the same, and we change the resonate frequency by capacitance. This method makes it necessary to construct the center conductor very short as compared to the full quarter wave length as in Fig. 4. These devices are not longer, so caution must be used when calibrating. The closed wavemeter as indicated in Fig. 7 is a shorted coax line at each end. The wavemeter uses a shorting plunger which is movable along part of its length. If used as the quarter wave coaxial cavity, the center conductor must be longer than a quarter wave length.



Fig. 4.



Fig. 5.

Up to this point we have covered most of the wavemeters that could be used from around 144 MHz up to approximately 3000 MHz. 1000 MHz to 3000 MHz are usually called the lower microwave frequencies. If the inner circumference of the outer tube is kept less than one wavelength, these wavemeters will operate in the desired TM mode.

There are four ways to couple energy into a wavemeter, loop (Fig. 4), probe (Fig. 5), direct (Fig. 6) and slit (Fig. 8). The most commonly used is the loop, as it has very little effect upon the electric field. The usual methods for changing loop coupling is to change the size and orientation of the loop. Loop coupling is usually placed in the high current area of the wavemeter. Capacitative coupling is changed by the size of probe and the distance from the center conductor. Capacitative coupling is usually placed at the high voltage portion of the wavemeter. As in Fig. 5, a small probe – say ½ in. piece of No. 22 wire, for example – may require an external voltage amplifier. The smaller the probe, the less effect on the resonate fre-



Fig. 6.



Fig. 7.

quency of the wavemeter. In direct coupling as in Fig. 6 the primary concern is impedance. To increase the impedance, move the coupling up the line away from the shorted end. To decrease the impedance, move the coupling down the line toward the shorted end. Slit coupling (Fig. 8) can be a small hole or a series of small holes or a slit. Its purpose is to allow a certain amount of leakage. In all forms of coupling, it is desirable to use loose coupling, as the wavemeter will have less effect on the system, and the Q of the circuit will be higher.

Above 3000 MHz, usually only the tunable wavemeter is used. The cavity is one quarter wave length long. The cavity can be coupled in three ways: loop, probe and slit. Because of the high frequencies, the slit is usually used, and the meter is most often kept as an assorption meter. In the assorption method, the wavemeter should be detuned when not in use. Some of the cavity wavemeters have a little lossy material added to absorb some of the energy, as in Fig. 7. Lossy material can be made from graphite impregnated cloth in epoxy.



Fig. 8.

There is one other type of wavemeter that can be briefly mentioned; it is the reference wavemeter. The reference wavemeter is of any design as described, but would be constructed more like Fig. 6. It can be locked when adjusted to a selected frequency and used as a reference standard. The micrometer assemblies can be made from any micrometer with additional parts welded on. I constructed one using an oversized tube over the main cavity, and dimpled it at various places around its circumference until it fit smoothly over the cavity, and I used a piece of 3/8 threaded brass pipe as the main adjusting screw. I am sure you can come up with a good one without any backlash. This wavemeter spread the 1250 MHz band out to over 100 inches by rough measurements. I haven't calibrated it, so I can't say for sure just how far. There are three nice veeder root counters in the APX 6 which would make excellent wavemeters plus sliding contact material. One could even use the entire cavity.

The last method of microwave measurement that we will look at is the slotted line (Fig. 9). The slotted line is a section of coax line along which is cut a slot. A probe, which is a simple crystal detector with a one quarter wave length shorted stub for a dc return path, is moved along near the center conductor of the slotted section. In this case we are looking for two successive minimum readings along the line. The distance between these readings is one half wave length. A slotted line should also be calibrated. If calibrated at one spot near the intended frequency to be measured, a chart will not have to be made – just a K factor obtained. The distance between two successive readings times the K factor should equal the frequency half wave length. There are a few accessories that can be either built in or used externally. One is a coax attenuator shown in Fig. 4. It will slide in and out of the other half. It too can be calibrated if one wishes. A 50Ω resistor can be used for an impedance match for 50Ω lines if inductive coupling is used such as in Fig. 10 and when the loop is small. The line stretcher (Fig. 11) is useful with the slotted line. It merely consists of two coax sections, one sliding into the other.



Fig. 9



Fig. 10



Fig. 11.

FREQUENCY METER – 1 to 10 GHz AMATEUR MICROWAVE

Bill Hoisington K1CLL

A quarter wave coaxial cavity is used up to about 5 ghz, and from there to over 10 ghz the three quarter mode is used. A complete explanation of these types of operation is given.

The same type of unit can be used as a very good tuned mixer from 1 to 10 ghz.

The Coaxial Cavity

The basic circuit of the coaxial cavity is shown in Fig. 1. A cylindrical outer cavity wall encloses a round rod some 4 inches long which is the center conductor–this center conductor is grounded at one end.

The Shape of the Cavity

The exterior shape of the cavity is shown in Fig.2. and is seen to be rectangular in cross section, with two thin walls and two thick side walls. Believe me, this configuration was not arrived at in one day! De-



Fig. 1. Basic coaxial cavity.





Fig. 2. Shape of the cavity.

signing tuners for X Band, I gaily started in with sections of thin-wall round pipe, the way I'd always done on uhf. The first thing you run up against is, how do you make the diode bypass capacitor? Machine out a curved saddle piece to fit exactly over the outer wall? Possible, but too expensive. And then how do you introduce the rf probe coupling into the cavity? Add on a "saddle" with a hole in it? These considerations and others, such as mounting (more saddles?) led to the abandonment of the pipe as a shape for microwave cavities; but not until a lot of time had been spent on the above mentioned items.

Diode holder and capacity

Looking at **Fig. 3.** you will see the first answer arrived at; but only after weeks and weeks of making different types and shapes. The center conductor is slightly flattened and drilled out to fit the diode prong. An 8/32 copper machine screw is drilled out to fit the other prong, then slotted with a fine jeweller's saw, and then compressed slightly to an inside diameter a shade less than the OD of the diode prong. In this way the copper screw will hold the diode as you insert it into the cavity. Believe me, that helps!



Fig. 3. Diode holder and capacitor.

The second answer is also evident from **Fig. 3.** as the diode bypass capacity can now be made efficient at X-Band. As mentioned before, you cannot "buy" a capacitor "good for X-Band. You can make it though, as shown in **Fig. 3.**, if the cavity body has been designed correctly for it. One of the thin wall sides of the cavity is drilled out (or machined out) just wide enough to clear the diode and it's holder, which is the 8/32 copper screw. The copper capacitor plate, which is thick enough to take at least a half dozen 2/56 threads, is drilled and tapped for the 8/32 screw, and clearance drilled in the corners for the 2/56 mounting screws. A soldering lug for the dc connection is used under one of these, and a three mil (three thousandth of an inch) thick sheet of fiberglass cut out to fit, larger than the plate. This helps to keep metal particles from lodging inside the tiny crack that might be there if the fiberglass sheet did not extend out beyond the plate all the way around. You can begin to see some of the detail needed at X-Band.

Further reasons for the rectangular cross-section now show up in **Fig. 4.**, which details the rf probe connections. This item was also very troublesome in first models using pipe walls, where "more saddles" was the only solution. All "saddles" are eliminated by the rectangular shape. Small semi-rigid cable is used for the connector. I have some short lengths with X-Band antennas connected to them for use as "In-Space" pick-ups, feeding directly into the wavemeter cavity. There is at times an advantage in this type of "energy collection" (antennas) which will be taken up later.



Fig. 4. RF probe connector detail.

Fig. 5. shows detail of the treatment of the cavity end of the rf cable, or probe. The outer conductor is cut away for about one quarter inch in length and removed. About a sixteenth or so of the Teflon is left, which is then removed from the center conductor. A thin copper washer (which I generally cut out of sheet copper since the hole to solder the center conductor is quite small) is then soldered to the center conductor, making the "capacity probe", as shown in **Fig. 5.**



Fig. 5. RF probe detail.

Mylar tape or other good insulation is fastened to the side of this washer facing the center conductor. With this insulation in place you can push the probe all the way in, while testing, and still not have a dead short. Different thicknesses of fiberglass sheet can also be cemented on, to make up more permanent types of fixed capacitors, of different values.

For some uses, particularly in this one as a wavemeter, loose coupling is desired, but it must be securely locked with the set screw, otherwise your dial calibration and frequency reading will suffer.

Plunger fingers

Here is the most difficult item. It is hoped to have stock pieces made up for this work that you can purchase at reasonable cost. The fingers should be made of tempered beryllium-copper, which is not easy to work with.

Fig. 6. shows some details of the plunger and fingers. I assume, having been told so by "well-informed sources" (mechanical engineers) that these units should be made in a machine shop by competent machinists. Maybe so, as the ones I have made here in the shack by hand tend to lose their tension if not handled carefully.



Fig. 6. Plunger details: A)End view, B)Outer fingers, C)Center fingers.

Fig. 7. shows the desired fit for these fingers. The plunger body should be an easily slide-fit *inside* the ¼ inch cavity, and the center hole in the plunger after the fingers should also be an easy fit *over* the center conductor.



Fig. 7. Desired shape and curvature of the plunger fingers.

Two steel push rods lead back from the plunger through small holes in the back end of the cavity (see **Fig. 1.**); these terminate in the brass block which is furnished with a pointer for the frequency scale. Maximum extension of the plunger should be up against the end piece, as a positive reference point for the dial, in case of trouble after calibration. This point should be indicated on the scale as "minimum frequency" in order to reset the pointer if it should ever become displaced after calibration.

The diode

At present, the diode used is an X-Band "pill package," with a prong at each end as shown in **Fig. 3.** These are point-contact diodes, like the famous 1N23 ceramic cartridge types of World War II fame, only a lot smaller. Referring again to **Fig. 3.** always make sure that the ceramic part of the diode is, as nearly as possible, in the open space between the inner and outer conductors. This space is where the rf is! It is also important to make sure that there is as much metal surface continuity as possible along the cavity wall, across the fiberglass sheet X-Band capacitor insulation onto the diode capacitor plate, and from there over to the diode holder and onto the metal end of the diode.

The rf is at a maximum between the inner and, outer conductors, which is an air space of a sixteenth of an inch. and that is where the diode should be.

The diode rf bypass capacitor, formed by the diode plate and the flat top of the cavity body, need only have a capacity which is relatively small; anything over about 20 pF is sufficient. What it *must* have is the proper *lack* of inductance! The details of how this act has been covered in previous paragraphs, and if you follow those details you will find little or no rf on the *outside* of the diode capacity plate or the dc lead from it.

X-Band is not just short waves. It is really short; like a quarter wave at X-Band equals 9/32 of an inch as you can plainly see, if you get one (or more) of those little plastic millimeter rulers in a stationery store for 5 or 10¢. Be sure and get some, by the way, if you're going to do anything above two meters.



Fig. 8. Full waves for S, C and X-Bands on millimeter scale.

Fig. 8. shows the millimeter scale, with s, C, and X-Band plainly showing.

A handy wavelength-frequency chart is included here for your convenience, which is useful from the khz range way up *above* X-Band. See **Fig. 9.** Get to know the easy reciprocals, like 1 centimeter equals 30,000 mhz, 3 centimeters equals X-Band, 10 centimeters equals S-Band (3,000 mhz), 1,000 mhz equals 30 centimeters, etc. Very useful!



Fig. 9. Wave-length/frequency converter. Use of multiplying factors such as those at the bottom of the graph will cover any portion of the electromagnetic-wave spectrum.

The 3/4 mode and harmonics

Don't worry about that word "mode." Generally when something odd takes place in a cavity or waveguide, certain types of engineers tend to fall back on obscurantism (I seem to have fallen for that $64 word. It just means covering up). They say, "It jumped mode", or, "Spurious showed up."

Here's the straight dope. **Fig. 10** shows the quarter wave "mode" of operation. Starting at 1 ghz you will find *one* point of maximum dc output. If the oscillator under measurement is "running hard" with lots of 2nd and 3rd harmonic energy content, these will be found at 2 and 3 thousand megahertz, and possibly higher ones, which should drop steadily in power as you go up. The diode itself may cause some of these if hit too hard with the rf input.



Fig. 10. Quarter wave in cavity.

Fig.11. shows the 3/4 wave mode, which is a very "natural" type of operation. Don't forget that in an instrument of this,kind you are looking for standing waves and you want them to be of the greatest amplitude possible (within reason). So, if you tune the cavity by the plunger so that it measures some three quarter waves on it (allowing for length-loading of the diode on the first quarter), you will find two peaks on the meter due to the situation shown in **Fig.11.** The higher the Q, and the lower the losses along the line, the more quarter waves can be found. For the 4 inch cavity shown, three quarter waves at S-Band are the longest that will fit.



Fig. 11. Three quarter waves in cavity.

A check on this operation is easy. Using the millimeter scale on the "dial', take several readings between maximums, for example, 22, 37, 51, and 67, add the spacings together, which comes to 45 millimeters, divide by three (the number of samples), and you will find an average of 15 millimeters for the waves which are standing on the center conductor (or "along the cavity", if you prefer) and there you are, 15 millimeters for the half wave, 3 centimeters for the full wave. Which is X-Band at 10,000 mhz or 10 ghz.



Fig. 12. Double input detail.


2"
REFLECTOR
3/4"
½ WAVE ANTENNA, OFF-CENTER FED.
14 MILLIMETERS LONG,
2 MILLIMETERS WIDE,
SPACED 3 MILLIMETERS FROM REFLECTOR.

Fig. 13. Test antenna—X-Band "two-element".

If you find numbers which are not well known, you can find the frequency on the chart, at least close enough to put you in one of the microwave amateur bands, such as 5,650 or 10,500 mhz.

Use as a Microwave Mixer

This same type of cavity can be used from 1 to 10 ghz as a mixer for the front end of a superhet receiver covering those frequencies.

This application will only be touched on briefly here as the whole receiver is detailed in another article in *73 Magazine*.

Fig. 12. shows how to do it, so you can plan on this use, and make more than one, if you wish to.

Looking at Fig. 12., you can see how useful it is to have *two* thick sides on the cavity, one for rf input and one for the local oscillator input.


1 3/8
1 3/8
CENTER CONDUCTOR INSIDE INSULATION.
SLEEVE CONNECTED ONLY TO OUTER CONDUCTOR.
SEMI-RIGID COAX.

Fig. 14. Test antenna—S-Band. Dimensions suitable for amateur S-Band 2,400 mhz (omni-directional).

Conclusion

That about covers the details and some uses. The whole unit can be mounted on a piece of copper-clad, along with a 50 ma meter, the dial scale, and the centimeter-frequency chart. I broke down on this one and used a "regular" small microwave input connector for the rf. (Instead of an "RCA Phono Jack".) For connections to other units, such as oscillators and multipliers, small flexible cable may be used.

Fig. 13 shows a test antenna for X band, not the best in the world but good enough for a starter. With a lens in front it really picks up signals. Fig. 14 shows an S band antenna for the 2,400 MHz amateur frequencies.

LAMBDA LINES

James Ashe W2DXH

Over the past few years, new kinds of commercial gear and military surplus have made it quite easy to generate VHF frequencies. But the problem of measuring the frequencies has not become any easier for amateurs short on calibrated instruments. Of course this means the newcomer to VHF! What can he do to find what ballpark a circuit is radiating in, if there are no accurate devices available? When this problem came up recently, a simple solution appeared quite by accident. It was so simple, in fact, that its simplicity must be the feature that has kept it out of the ham publications. Another first for 73!

The traditional solution to the rough frequency measurement problem is to make up a Lecher Wire system. There is some question about the value of one of these in the modern ham shack. Narrow-band crystal-controlled techniques guarantee frequency and stability once the multipliers are tuned properly. In the old modulated oscillator days things were not that stable . . . so why go to all that carpentry and construction work for what fairly well promises to be a use-it-once gadget? Particularly when a little reflection (pun intended!) may bring out a cheaper, faster and better arrangement?

Ham and commercial builders of VHF gear have been using tuned stubs for years to match impedances, tune out frequencies, tune in others, etc. Yet it seems to have occurred to very few workers indeed that it might be possible to cut stubs to length accurately enough to serve as frequency standards. Apparently this can be done, with an accuracy of about 5%! This compares very favorably indeed with the performance of lower-frequency grid dip meters and some signal generators. It's pretty good for a pencil and yardstick operation: the only other items required are some understanding of how it works and a piece of 300 ohm twin lead. Belden #8235 recommended. You can calibrate that new GDO for 432 at a cost of just a few cents!

Theory

Many kinds of things show a property of tuning sharply to a certain frequency. This property is called resonance. We hear it when a struck piece of metal rings, and see it in the pendulum of an old grandfather clock. The grid dip meter shows a drop in grid current of an oscillator when a nearby resonant circuit steals energy from the oscillator. And it is the nearby resonant circuit that is the subject of this article.



Fig. 1. Four kinds of tuned stubs, taking their fundamental resonances as the frequency producing the illustrated voltage distribution. This shows that none of them has a unique resonant frequency.

The basic circuit is the quarter-wave stub. A little browsing around in the handbooks and earlier issues of 73 and other ham magazines will tell you lots about quarter wave stubs. The important practical points are that the stub resonates at certain frequencies, and that at these frequencies it can be dipped at its shorted end in the same way as any other resonant circuit.

But the term 'quarter-wave' has to be taken with a grain of salt. The tuned stub will be shorter than a free-space quarter wave, because the dielectric has a slowing-down effect on the rate at which the RF bounces end-to-end along it. Suppose you laid out a mile or so of twin-lead and transmitted a signal, at the same time sending off a reference signal by space wave. The reference signal would arrive at the other end first, in about 5.35 microseconds. The twin-lead signal would arrive a full microsecond later, about a 20% delay. Since this applies even to short lengths of twin-lead, the delay must be taken into account for accurate measurements. Also, there is a considerable difference in velocity factors between different brands and qualities of twin-lead.

Crystals are often used in overtone oscillators for generating stable VHF frequencies. The various modes of oscillation are pictured in the handbooks. Tuned lines will also show overtone resonances, and in the case of large uncertainty, it might just happen that reasonable errors could lead to a consistent but very wrong result. A halfwave line will resonate at a frequency f, and also at 2f, 3f, and so on. Note both odd and even multiples! All other resonant lines have a similar overtone resonance property. The problem is slightly aggravated by the convenience of using relatively long lines at the higher frequencies because they are easier to handle. The solution is to cut a pair of lines whose collections of resonant frequencies have only one resonance in common. The recommended lengths are a half-wave and a three-quarter wave line.

Fig. 1 shows four basic tuned lines. Just which resonance is an overtone and which is not depends somewhat on the application. The simplest way out of this problem in semantics is to say that the three-quarter wave line really doesn't have that resonance at f/3, ignore the quarter and fullwave lines, and stick to the remaining two for test work.

At 432 MHz a wave in free space is about 27.3 inches long. Suppose we are using Belden #8235 twin lead, which Belden says has a velocity factor or propagation constant of 0.77. The twinlead wavelength than is 27.3 times 0.77 or 21 inches. The halfwave stub must be 10.5 inches long, shorted on both ends; and the three-quarter wave stub 15.75 inches long, shorted at one end. These are convenient lengths, not too long to use on the workbench, nor so short that percentage accuracy in cutting becomes a big question.

Using the stubs

The commercially available grid dip meters are not noted for accuracy. It's commonly estimated that the scale calibration can be



trusted to within about 20%. With some care, calibration points taken from twin-lead resonators appear to be good to about 5%. The first precaution is accurate construction. Cut the strips slightly long, short one end of each, and cut the three-quarter wave line to length. Then go more carefully at the other end of the halfwave line, which must be shorted at both ends. It should not be too hard to get the correct lengths within one sixteenth inch.

When making frequency checks, the lines must be held off the workbench an inch or two. Use small boxes or pieces of cardboard. Probably the better part of a foot distance is in order if the workbench is of metal or has a copper surface. At two meters, a perceptible change in calibration can be detected if the line is laid out on a wood surface! It's very good practice to make up lines for two meters or lower, and practice dipping them. Some refinement of technique will certainly be required before a halfwave and a three-quarter wave line can be made to dip at the same point on a standard dip meter. Once the trick is mastered, it can be carried up to the higher frequencies.



Fig. 2. Some overtone resonances of a halfwave stub (shorted at both ends). F1, F2, F3 and F4 should be 1F, 2F, 3F, 4F.

The lines are dipped in the same way as any coil. Because they have a very high Q, there will be a tendency for the dip oscillator to pull, or to seem to give different readings when tuning down to frequency and tuning up to frequency. The remedy is less coupling: move the dip meter a little further away from the line and try again. Dip the stub at its shorted end!

But what was that trick for calibrating a dip oscillator, mentioned earlier? Can't make up a pair of lines for each frequency. No need to! That's simply the reliable way for finding the right ballpark. When you're there, you can set the lines aside, make up another three-quarter wave resonator cut for the lowest frequency, and after marking that point on the scale, trim the stub up to the next calibration frequency. Throw the remainder away when done calibrating.

The half-wave stub is also useful as a tuned coupler. Suppose you want to tune an oscillator to a particular frequency but have nothing to indicate at that frequency. Loosely couple the RF into one end of the half-wave stub, and take it out the other end with a hairpin loop, through a diode to a 50 μA meter. You will only get a reading at the resonant frequency of the half-wave stub. Simple!

Chapter V

RF Signal Generators

ZERO-BEATING WITH A FREQUENCY METER

Jim Harrison WB4TBX

After putting an LM-18 in service, I found it a nuisance to plug in headphones every time it was necessary to adjust the corrector control to produce Zero Beat at one of the crystal check points. I hooked up a phone plug to the plate winding of an audio output transformer, and then connected a small loudspeaker to the secondary winding. I leave the phone plug inserted in the LM phone jack at all times. After using this setup for a while, it occurred to me that the last few cycles either side of zero beat might not be audible, so I tried a parallel hook-up off the primary side of the transformer. The other end of the cable was connected to the Vertical input of an oscilloscope. Now, when adjusting the corrector control for zero beat, you will see low amplitude sine waves even after you can no longer hear the beat note. You tune out the sine waves until you have a perfectly straight reference line on the scope. The Heterodyne oscillator is then corrected to calibration much more accurately than trusting to the ear alone. The principle is not new, yet the idea may not have occurred to some people. Any old scope will do, as the frequencies are in the audio range.

Another bit of frustration occurred when trying to adjust the corrector knob. I would pass the zero beat point time and time again, due to the stiffness of the control. Remember, these units are built for ship-board use, and loose controls cannot be tolerated. I dug up a small vernier tuning drive, similar to the Jackson Planetary-Vernier drive, (about 5 to 1 ratio). I mounted this drive on a right-angle aluminum bracket and attached it to the LM using the two screws on the upper right side of the unit. Bore holes slightly oversize to allow for accurate alignment of the control shaft so that it will not bind. Cut out a portion of the bracket so the "High-Low" knob can be moved. The precise Zero beat adjustment can now be made very easily with the reduction drive.

HAND CALIBRATE THE BC-221 FREQUENCY METER

Carl Henry

At present many amateurs have an opportunity that may not repeat itself. I refer to the many army and navy surplus frequency meters now available, through MARS and surplus sales. Many of these meters have the original calibration chart missing, and are considered virtually useless. This is demonstrated graphically by prices, the frequency meters with charts costing $100, the meters without charts selling for one-third this amount. Meters without charts are worth more than this would seem to indicate. It is no great job to calibrate one of these meters, but it is time consuming. A little care is required, but you do not need to be a super technician or electronic engineer to do the job. Neither is elaborate equipment required.

Essential to the calibration are several items not commonly available around the shack, but easy to build. Figure 1 illustrates the first requirement. This is a 10 kc multivibrator, which will operate from a 100 kc xtal calibrator, and give 10 kc markers up to 20 mc. I am assuming here that you have or can beg, borrow, or steal a 100 kc calibrator, this being a common item. In fact, some receivers have them built in. Using this 10 kc marker source, the high band of the frequency meter can be calibrated. Interpolation to 1 kc points is then possible, and if care is used an accuracy of better than 0.005% will result.



Figure 1. 10 kc multivibrator for use with 100 kc crystal oscillator, providing 10 kc beats with frequency meter.

Fig. 2 shows a simple beat detector that can be used with earphones to get an exact zero beat. It took about ten minutes to wire up a 1629 (army surplus magic eye tube) temporarily for this purpose, and it is certainly worth while in the interest of increased accuracy.

With your equipment assembled, connect the frequency meter to its power supply. Allow at least one hour for proper warm-up so that all equipment will stabilize, including the 100 kc calibrator and 10 kc multivibrator. Set the CALIBRATE control on the frequency meter to center, and be especially careful not to move it until the calibration is complete. After the warm-up period the 100 kc calibrator should be zeroed against WWV, at as high a frequency as possible. The 10 kc multivibrator must be checked to see that it gives nine beats between each 100 kc beat. This can be done with your communications receiver, and it will be easiest to do it on as low a frequency as possible, say 600 to 700 kc. Now type several sheets of paper, listing the high range of your frequency meter by 10 kc points. If you are in doubt as to the range, check it with your receiver. To do this set the dial to the low end of its range, turn on the internal xtal, and zero in on the strongest beat at or near the low end. Turn off the internal xtal oscillator and find the signal from the frequency meter with your receiver. Note the frequency. Tune your receiver until you reach another harmonic from the frequency meter. The difference between the first and second readings is the frequency of the meter at the low end



Figure 2. A simple zero-beat indicator for use in conjunction with headphones.

of its dial. Now do the same thing at the high end, and you have the primary coverage of your frequency meter. Most have a range of 125 to 250 kc on the low band and 2 to 4 mc on the high band.

When you write up the frequency range by 10 kc points, leave a space between notations, since you will be adding information here later. Now, using the 100 kc xtal, check the high band of the frequency meter at 100 kc points, listing the dial readings. Now go back and check the dial at 10 kc points, listing all the dial readings. The checks should agree with the 100 kc checks at every tenth point. This is a handy method of cross checking yourself. You might note that on equipment of this type, always approach the final reading from below. If you pass the zero beat point, don't jockey the dial back and forth for zero beat. Go back below the beat by 5 kc or so and approach again from below. This procedure will help to eliminate error from dial backlash.

After your 10 kc points are all listed, interpolate to 1 kc points. This is the hardest part of the job, and is very time consuming. A big pot of coffee and a patient and loving XYL will be a big help here. The patient XYL can be replaced with an adding machine if you have one available, but you'll still need the coffee.

The difference between each 10 kc point must be listed. Note this in the space you left on your sheets. Each 1 kc will be 10% of this, so add 10% to the 10 kc listing for 11 kc, 10% more for 12 kc, 10% more for 13 kc, and so on. When you reach the next listed 10 kc point, the calculated listing and the measured listing must agree, another cross-check. This will take 2000 individual additions.

After the high band is finished, you may wish to calibrate the low band in the same fashion. Referring to Figure 1, change the grid-plate capacitors to 0.01 mfd. This will put the multivibrator at approximately 1 kc intervals. If you have trouble syncing the multivibrator, you may have to build another to operate at 10 kc, and sync the 1 kc from this. No trouble should be had with a strong output xtal calibrator, however. Calibrate the multivibrator as before, except with 1 kc intervals instead of 10 kc.

A calibration book can be prepared when you finish. It is a good idea to file all your original calculations and papers, should the book ever be destroyed. The frequency meter is now as good as any with original calibration book, at a good saving of money.

HIGH ACCURACY VHF FREQUENCY MEASUREMENTS

Howard Burgess W5WGF

Accurate frequency measurements can be a problem for the amateur with a limited budget. However with some home construction and careful operation the average ham can make VHF frequency measurements to an accuracy better than .00015% at two meters. This is the equivalent of measuring the distance from New York to Los Angeles with an error of only 25 feet. Many commercial units cannot equal this figure. The same method can also be used for HF and UHF measurements.

There are many ways to measure frequency but few of them are satisfactory for use at the very high frequencies. The well known hetrodyne frequency meter becomes unstable when its oscillator is operated at VHF. It can no longer be held or read to any degree of accuracy. The oscillator can be operated at a low frequency and one of the harmonics used at VHF, but any error in the oscillator will be multiplied by the number of the harmonic used. A frequency meter that can be held to within 200 hertz at 4 MHz will be off by 7.4 kHz at the 148 MHz harmonic.

A second method of much greater accuracy uses low frequency crystals which are referenced to a known standard such as WWV. The harmonics of these oscillators will be quite accurate and useful far into the UHF region. However this system has its limitations. Even when used with multivibrators and harmonic amplifiers it produces only spot frequencies.

Although neither of these two methods is satisfactory when used alone, they can be combined to make an accurate and versatile system. If you haven't guessed it by now, the system works like this. A crystal oscillator operates on 5 MHz. This oscillator can be kept to zero beat with WWV with very little effort. With a simple harmonic amplifier following it, strong markers are available every 5 MHz far into the UHF region. To fill in between the 5 MHz points, and get full tuneable coverage, all that is required is to add the output of a stable low frequency VFO to the proper marker. Example: To measure 146.25 MHz just add 1.25 MHz from a calibrated tuneable oscillator to the 145 MHz harmonic of the crystal. The same results can be had by using the 150 MHz marker and substracting 3.75 MHz.

The tuneable low frequency oscillator of this hetrodyne system can be any stable, calibrated, oscillator that will give the desired frequencies. A good signal generator can be used but better yet is the old faithful BC-221 frequency meter. The crystal oscillator that supplies the 5 MHz markers should be designed for high stability. However, even simple crystal-controlled units can be kept zero beat with WWV for periods long enough to make most measurements.


SIGNAL OUT
6AU6
XTAL OSC
5 MHz OUTPUT
UNTUNED
6AG5
AMPLIFIER
OUTPUT
TUNED TO
5 MHz
6AK5
HARMONIC GEN
AND AMP
OUTPUT
TUNED TO
HARMONIC
USED
6AS6
MIXER
OUTPUT
TUNED TO
FREQUENCY
TO BE
MEASURED
BC-221
FREQUENCY
METER

Fig. 1. Block diagram of the VHF frequency meter.

Earlier we quoted a figure of .00015% or better for the accuracy of this system. Perhaps we should show how this is possible. The crystal oscillator can be held to near zero beat with WWV but due to propagation errors in the signal of WWV, we can never be sure that our crystal is closer than 2 parts in 10 million. This would be 2 hertz of error at 10 MHz or an uncertainty of 29 Hz in the 145 MHz marker. The BC-221 is normally considered to be a .05% instrument. This would be an error of about 1.75 kHz at 3.5 MHz. However with care in calibration, and reading it is not difficult to reduce this value to 200 hertz or less. In a hetrodyne system the error of the VFO is not multiplied at VHF but is just added to the error of the crystal marker used.

The total error at 2 meters is 29 Hz contributed by the crystal and 200 Hz by the VFO for a total of 229 Hz. This is a little more than 1.5 hertz per million hertz for a tuneable system. Of course these values are approximate and with careful operation they can be reduced by 50% or more.

In the 146.25 MHz example used earlier, the VFO was required to furnish less than 1% of the total output. To put it another way, the only wobble is in the smallest cog and its contribution is so small it can't shake up the machinery too much.

The circuit shown in **Figs. 1 and 2** has been used for monitoring MARS, CAP, and several other services. The crystal oscillator is quite stable but can be tuned enough to zero with WWV. Tuning is done with C1. One stage of harmonic amplification is sufficient to give strong signals well above 150 MHz. The plate circuit of this amplifier stage is tuned to the harmonic to be used. This feeds one input


OSC.
6AU6
5 MHz
XTAL
C1
10pF
C2
25pF
R1
1M
L1
C3
200pF
MICA
C4
.002μF
R2
10k
1W
RFC-1
2.5mH
C5
C6
.002μF
R3
330k
R8
2.2k
2W
.002μF
C8
AMP.
6AG5
R4
200
1W
C7
C9
.002μF
R5
2k
1W
C11
200pF
MICA
C10
.002μF
R7 62k 2W
R6 10k WW
C12
200pF
MICA
L2
CR1
1N34
ETC.
R9
470k
R10
470k
MULT.
6AK5
C13
.001μF
R11
15k
1W
2 TURNS
NO.16
1/2" DIA.
C15
25pF
C14
.001μF
L3
RFC-2
(ABOUT
2μH)
C16
20pF
MICA
MIXER
6AS6
R12
100k
R13
220
1W
C18
.001μF
C17
.001μF
R14
20k
1W
C20 25pF
BUTTERFLY
3 TURNS NO.16
3/8" DIA.
L4
SIG.
OUT
L5
1 TURN
NO. 16
3/8" DIA.
RFC-3
(ABOUT
2μH)
+150
SLUG-TUNED
BROADCAST RF COIL
T1
C21
250pF
MICA
VFO
INPUT
C19
SELECT TO RESONATE
T1 IN RANGE FROM
1.0 TO 4.0 MHz
* 24 TURNS NO. 22 ENAM.
ON XR-50 FORM

Fig. 2. Schematic of the oscillator, multipliers and mixer for using a BC-221 on the VHF ham bands.

grid of the mixer. The other grid of the mixer is driven by the output of the BC-221 frequency meter. The tuned circuit shown in this grid resonates broadly in the 2-4 MHz range of the BC-221. This helps to keep the higher harmonics of the BC-221 out of the mixer.

The output of the mixer is resonated to the desired operating frequency. This will be either the sum or difference of the two input signals. The level of the output signal can be controlled by R6.

Operation of this system is simple. The "cook book" would read as follows:

1. Couple the output to the antenna of the VHF receiver.
2. Determine the crystal harmonic and VFO frequency that will give the frequency of the signal to be checked.
3. Tune the VHF receiver to the signal to be checked.
4. Tune the BC-221 until the output of the frequency monitor zero beats the received signal.
5. If required, peak the tuned circuits in the monitor for maximum output and adjust R6 as needed.
6. The frequency of the received signal will be the crystal harmonic plus (or minus) the reading of the BC-221.

Many details cannot be covered in one story due to lack of space. The operator will have to determine the most effeceive method of coupling to this particular receiver. He will also have to explore the many combinations of frequencies which can be used. These and many other questions cannot be included at this time. However those who require such a system as this will probably be capable of filling these details.

One word of caution is in order. With two oscillators that are rich in harmonics, there can be many unwanted "birdies." These present no problem after the operator has gained experience but the new user should be very cautious. Many times an unwanted beat can be eliminated at a critical spot by changing the two frequencies that are being mixed (shift from sum to difference).

Perhaps we should emphasize that this system is a "trade off" where the amateur can trade his skill and patience for highly accurate measurements with simple equipment.

A TRANSISTORIZED LM METER

Charles Landahl W5SOT

The last word may never be written about the BC-221 and LM frequency meters. The LM is particularly attractive because it is in the smaller package. With transistors replacing tubes, it has features most everyone wants – it is rugged, portable, and accurate, to name a few. I will describe a conversion of an LM-15 frequency meter in which field-effect transistors replace tubes; the power supply becomes a standard 9V transistor radio battery and the current drain is less than 3 mA when all functions are energized. In addition, I offer calibration information which will be of interest to anyone having a BC-221 or LM without the official calibration book. I bought an LM-15 for a temptingly low price (Fair Radio Sales Co., Lima, Ohio, $14.95). The set is sold in the "as is" condition with tubes and crystal but without calibration book. It is a good idea, but not necessary, to start with a set which is working before making the change to FETs. Resistance measurements will show if the circuits are complete. Important values are marked on the schematic of Fig. 1.


THIS RESISTOR NEEDED FOR SOME FET'S
VFO
3N128
47K
G
D
S
CAN
E109
TERMINAL E109
C117
CAP
77
R104 50K
6K
LOW
HIGH
A
B
C
D
R101 1000Ω
R102 100Ω
L101
L102
R117 130K
C102
C110
C101
C103
C104
SCREWDRIVER ADJUST
RF COUPLING
R106 25K
C105
C104
S104
R107 1 MEG
R109 1 MEG
XTAL
CHASSIS GROUND
R114 80K
C107
6K
R108
5K
C109
C109B
C-610
MIXER
270 PF
MPF-107
XTAL OSC
2.2K
6A7
L103 35Ω DC
L104 7000Ω DC
C111A
C111B
C111C
R110 60K
R115 15K
SHORT
AUDIO
C-610
76
R112 1 MEG
R111-3K
C110A
C112
T101
1200Ω DC
58Ω DC
PHONES
C113
R108 20K
SHORT
R113
C110 C
C110 B
CHASSIS GROUND
260-475V
SHORT JUMPER
R103
200-260V
R116
VOLTS
NEONS (REMOVE)
GROUND TO CHASSIS
J102
9V
41
26
36
18
56
FIL.
S102
PLATE
VOLTS
24
12

Fig. 1. Modified schematic of frequency meter.

Smash Tubes

The most difficult part of my conversion was getting up the courage to smash the tubes! I wanted the bases for mounting transistors. Place the tubes one at a time in a paper sack, hold the top closed and with a metal object, strike the glass through the paper. The flying glass is caught and collected for disposal. Scrape and clean the mastic from the inside of the tube bases. Should you choose to mount a transistor socket in the wall of each tube socket, you can use the original wires; otherwise, unsolder the old wires and replace the needed ones with about 2 in. of sturdy new tinned wires. The appropriate tube base pin connections are shown in Fig. 2. Actually there is no preferred mounting scheme. Use whatever appeals to you.

Check for clearance between socket and walls. My conversion used transistor sockets mounted on metal plates which were bolted to the wall of the salvaged tube bases. This allowed FET substitution to determine which ones would work best in the several circuits of the LM. All FETs used are N-channel.

Modification

With cover removed and the LM in the upright position, front panel toward you, on the left side wall, look through two oblong machined slots and see mounted on a phenolic board a 50 kΩ plate resistor. Parallel it with about 6 kΩ. Turn the LM upside down, panel toward you. On the underside, two resistors must be shorted and a jumper wire made up and connected. Short R115, which is a 15 kΩ wirewound resistor, quite visible on a phenolic board at the left of the 1000 kHz crystal can. Run an insulated wire from a terminal of this shorted resistor to the 260–470V tap contact of the link switch. This wire can be about 6 in. long and conveniently passes through a wall slot behind the crystal socket. The link switch and its terminals are on a phenolic board in the compartment aft of the crystal socket. The jumper wire will cross near the grid resistor, R109, of the crystal oscillator. While there, change the 100 kΩ (R109) to 1 MΩ. Next, unfasten the screws holding the phenolic board located to the left of the power plug. Tip up the board and short across R108. This is a 20 kΩ composition resistor which is in the plate voltage line to the audio amplifier. Also, at the power plug, locate pin 36. Short it to chassis ground. On most sets pin 36 is the ground return for the vfo cathode. The circuit was closed through external connections in a power supply. You have completed the surprisingly few changes needed to make the LM work on FETs and a 9V battery.

The VFO

With FET source connected to pin 5, drain to pin 2, can to pin 1 (if needed), plug the FET into the vfo socket. Connect a solid wire between terminal E109 and the gate of the FET. (Terminal E109 held the grid cap wire for the vfo tube.) Connect a 9V battery to the power plug pins. PLUS to 26 and MINUS to terminal 41. If you have a milliammeter in the battery lead, it should read about 1.5 mA when you turn on the FIL and PLATE switches. Provided you were fortunate in the choice of FET, you should hear a clear CW signal in your receiver. Set your receiver to 2 MHz or 4 MHz. You may need to connect a wire from the rf coupling post on the front of the LM to your receiver antenna. Rotate the LM dial between 0300 and 0600 on the readout. Your vfo will be on the low end of 125–250 kHz or 2–4 MHz depending on the position of the low or high band switch. The XTAL and MOD switches should be off. The FET selected for the vfo may require a 47 kΩ resistor between gate and chassis ground. I found this to be true for the RCA 3N128, 3N142,and *one* of the two 40559A FETs. On the other hand, one RCA 40559A and one of several 2N3085 silicon N-channel FET from Poly-Paks worked beautifully without adding 47 kΩ to the gate.

Apparently junction and insulated-gate field-effect transistors have slightly different characteristics which show up in this peculiar vfo circuit. My own choice is the 3N128 with the additional resistor on the gate. You may find it necessary to "tune" the source, drain, and gate resistances in order to have your vfo working well with a particular FET. I used potentiometers across the various elements to arrive at the recommended values. My vfo works reliably from 10V down to 6V and the maximum drain current is 1.5 mA.



Fig. 2. Suggested semiconductor hookups for tube sockets.

Caution

Other oscillator hook-ups may occur to you, and they will work – but the tuning range and linearity of the vfo will suffer! Linear tuning is most important, so stick with that shown.

The AFO and AF Amplifier

The audio oscillator and amplifier wasn't as fussy as the vfo. I used a Radio Shack 276-664 FET – it is said to replace a C-610 or 2N3088. I found that the Poly-Paks "hobby" FET 92CU588 will work equally well. In making up the socket, gate goes to tube pin 3, source to cathode pin 4, and drain to plate pin 2. That is all there is to this one. Plug in the FET. When you next turn on the 9V power, the milliammeter will barely increase a few hundred microamps as you switch on the modulation control. At this moment a rather pleasant 500 Hz tone will appear on the vfo frequency no matter which harmonic you have tuned in on receiver. Your modulator is finished. The audio amplifier is too, for that matter. You just won't hear anything in the headphones until you complete the crystal oscillator and the mixer circuits.

Crystal Oscillator

The reference oscillator is not much trouble. You have already changed the gate resistor from 100 kΩ to 1 MΩ. Actually this change may not be necessary because some crystals are more active and will oscillate well with the original resistor. Mine went into oscillation better with the higher value. The FET you select for this circuit can be one of several. Mine is a Motorola MPF-107. I found the Radio Shack 276-112 and the Poly-Paks 2N3085 also work, but draw more current. Whichever you choose, the gate connects to base grid pin 5, source to cathode pin 6 *through* a 2.2 kΩ resistor. Drain hooks to plate pin 4.

Now, when 9V is turned on, MOD off, XTAL on, you should hear the crystal oscillator signal every 1000 kHz on your receiver. The milliammeter should increase about 1.5 mA or less when XTAL is turned on. If you don't hear the crystal frequency, bring the receiver antenna wire close to the crystal FET. We still haven't made the connection which adds the crystal-oscillator signal to the rf coupling post on the front of the LM. Assuming you have all circuits in working order up to this point, we move to the mixer.

Mixer

There is no single FET substitute for a pentagrid converter tube. The dual-gate MOSFET comes closest; however, use of one would have defeated my goal of simplest conversion. Therefore, four N-channel FETs are needed to do the work of three tubes, but what a saving in power supply! The mixer concerns itself only with beat frequencies occurring between the reference oscillator, vfo, or an external signal – all audio work. Thus, a hobby FET was selected. I used the Poly-Paks N-channel FET. A Radio Shack C-610 replacement will also work. Connect source to chassis ground through pin 6 of the tube socket; the drain connects to plate pin 2, gate to mixer grid cap wire through the lug in tube socket wall.

Finally, connect a capacitor (200–300 pF) from the top of the 2.2 kΩ crystal oscillator source resistor to the gate of the mixer FET (grid cap wire). You are in business.

With 600Ω phones plugged into the LM, you should hear all the necessary beat frequencies occurring between the vfo and the crystal oscillator as you tune the vfo through its range. XTAL must be on and the MOD switch off. Otherwise, the audio amplifier becomes the modulator and you hear nothing in the LM phones.

What Next?

With the beat notes loud and clear you are ready to calibrate. This is quite the most fun part of the work because the linear tuning rate of the LM is almost unbelievable. The slow rate is due to the series combination of the A section of C109, C101, tuning L101 or L102. The amount of the matter is that one revolution of the 100-division circular dial produces about 3 kHz change on 125–250 kHz range, and about 50 kHz per revolution on the 2–4 MHz range. The actual calibration of my unit was 2.89 kHz and 45.17 kHz per revolution.

The linearity can be checked by how little you need to vary the "corrector" for each zero-beat checkpoint. Each LM or BC-221 will be slightly different. Now, when you consider that the vernier allows you to split one division into tenths, then it is clear that you can set a frequency to better than 0.5 kHz over the range of the frequency meter. May I repeat:

1 dial revolution of
100 div = 45.17 kHz
1 division = 0.4517 kHz
1/10 div = 45 Hz

Therefore, all you need is a checkpoint at which to zero the vfo and start counting revolutions, divisions and tenths of divisions to accurately set any frequency within the two ranges of the vfo. I found it useful to construct graphs on K&E 358 11L graph paper. The grid is 10 X 10 (per 0.5 in.). The paper has 20 units vertical and 30 horizontal. This allows graphing 100 division and leaves room for 10 vernier divisions on the right hand end of the paper. Use the crystal checkpoints listed in Table I to locate *your* dial settings. Once graphed, a frequency can be selected directly from the chart, or, depending on the accuracy desired, interpolated between checkpoints.

Table I. Crystal Checkpoints

KHz	VFO	XTAL	Approximate Dial Settings
Low Band			
125	8	1	0320
150	20	3	1192
166.667	6	1	1750
200	5	1	2935
222.222	9	2	3700
250	4	1	4647
High Band			
2000	1	2	0396
2250	4	9	0945
2500	2	5	1493
2750	4	11	1050
3000	1	3	2606
3250	4	13	3150
3500	2	7	3711
3750	4	15	4262
4000	1	4	4812

It is obvious from this discussion that the low band of the LM is fabulous. You can squeeze down to about 3 Hz by use of the vernier scale. By the way, hidden behind two cover plates just beneath the corrector knob, are "high" and "low" padder capacitors. These were used when vfo tubes were replaced to bring calibration book values into usefulness. The padders should be set near the middle of their range.

Make it Handy!

Fasten a handle to the case, strap on a 9V battery, go forth and have fun with your rejuvenated frequency meter. I use mine for its intended purposes as well as a band-edge marker and keying monitor.

AN I-F SPOTTER

Howard Burgess W5WGF

If you have ever tried to find the *if* frequencies of unfamiliar and inoperative pieces of surplus gear with no schematic, it is a waste of time to tell you how rough it can be. Even a single *if* transformer from the junk box can be a problem if it has no part number or identification.

Of course in some cases a grid dip meter can be used to find the operating frequency. However, few grid dippers cover the important *if* frequencies below 2 mc. To complicate things, if a dipper is used on a shielded transformer above 2 mc, the resonant frequency of the transformer may be shifted if the shield is removed.



The if spotter. The switch for changing the coupling capacitor is at the upper left marked "HI" and "LO." The posts on the end are X1 and X2.

If these problems sound familiar to you, we would like to suggest a little gadget that can help solve them. With just two resistors, two capacitors, and a tube, don't expect it to give a digital read-out to all your questions, but it can put you in the ball park.

The principle of operation is as simple as the construction. The tuned circuit in question is merely made to oscillate at its resonate frequency. The frequency can then be determined by tuning in its radiated signal on the ham receiver. To set the unknown coil into oscillation requires the use of a simple "two terminal" oscillator. Such an oscillator is shown in the schematic of Fig. 1. When any tuned circuit is connected to the two points marked X, the circuit will oscillate at its resonant frequency.

In this oscillator the twin triode is a tube such as the 12AT7. The section V2 furnishes the necessary feedback and eliminates the need for extra coils or feedback connections.

The construction is simple. The unit could have been built in a larger case with its own power supply and would have become a nice piece of bench equipment. However, due to the few parts required and the small amount of plate power used (3 mils at 90 volts) it was built as an overgrown probe. The power is robbed from another piece of test equipment or the receiver.

As a probe it can be used on the work bench to test individual coils and transformers or it can be held in contact with the various transformers in a receiver.

There is only one point of caution that should be observed in construction. The lead from the grid contact of VI to the XI post should be kept as short and direct as possible with the least capacity to ground. This lead becames part of the oscillating tuned circuit and limits the upper frequency to which the unit will operate.

The coupling capacitor from the grid of V1 to the plate of V2 furnishes the feedback required to maintain oscillation. To reduce the loading on the tuned circuit, this capacitor should be held to the smallest value that will sustain oscillation. Because of the wide range over which this instrument operates, a switch is provided to change values. With the capacitors shown, operation is possible from about 60 mc down to well below 50 kc. The larger value is used at the lower frequencies and is switched in only when required. With coils of medium Q the switching point is around 3 to 5 mc.

The connectors X1 and X2 can be almost any kind of posts. The ones shown on the unit here are banana plugs. These can be used as test points, or alligator clips can be slid over them for use in clipping to coil leads.

The meter shown is a three mil meter and is used to read the total plate current of both halves of the tube. This will indicate when the circuit is oscillating. When the tester is not oscillating the meter will indicate a current of about 1 mil (with 90 plate volts). Under oscillating conditions the meter will rise to as much as 3 mils with a high Q coil. The actual amount of current is not so important as the fact that the upward shift indicates that the coil is not open and is oscillating. A 5 or 10 mil meter will serve the purpose just as well.

As the pictures show, this unit was built in a small 5" x 3" x 2" box. The unit will work just as well if it is built on a small piece of peg board with a couple of leads run out to the multimeter. This is for the man in a hurry.



FIGURE 1

Circuit diagram of the if spotter

.01 Ceramic capacitor
50 pf Mica capacitor
10 pf Ceramic
68 K ½ watt carbon resistor
22 K ½ watt carbon resistor
Milliammeter in range of 3 to 10 ma
Slide action Double Pole-Single Throw switch (S1)
2 Banana plugs (x1 and x2)
12AT7 tube
Minibox (size depends on type of meter used)
9 pin miniature tube socket

When the unit is finished, apply power with the "X" points open (no coil across them). Because of the open grid of V1, the meter will drift about. After the tube has had time to warm up, short the X posts with a heavy piece of bus or copper. The meter will now come to rest somewhere around 1 mil. This is the "no oscillation" current and should be kept in mind as a reference point for future use. Now remove the short and connect almost any kind of an LC circuit across the posts. The meter reading will now rise from the "no oscillation" value indicating that the coil is oscillating. Do not use the large coupling capacitor unless the circuit refuses to oscillate with the smaller value.

To check a single *if* transformer, all that is necessary is to hook one of the *tuned* coils



Checking a ten meter tank circuit



Checking an if transformer



Inside view showing extreme simplicity of the "Spotter." The tube is mounted at an angle to keep the grid lead to the "unknown" as short as possible.



Close up of tube socket showing parts placement.

to the input terminals of the tester. Some transformers have a number of terminals which may not go directly to the tuned circuit inside. To obtain oscillation there must be both a dc and an rf path between the two pots.

If the transformer is one whose frequency falls in the range below the broadcast band it is quite convenient to have one of the surplus receivers that covers the range down to 200 kc. However the check can still be made with a regular broadcast receiver. All that is necessary is to find the harmonics of the tester as they fall in the broadcast band. They will be separated by a value equal to the frequency of the coil being tested. As an example, if a signal is spotted at 900 kc and the next one higher is found at 135 kc, it is a pretty good bet that the transformer is operating on 450 kc (1350 − 900 = 450).

To find the operating frequency of an *if* stage it is not necessary to have the amplifier in operating condition or the tubes hot. Just connect the two contacts across the primary or secondary of the transformer in question and watch for signs of oscillation on the meter. Some transformers have a portion of the bias system inside of the can. This can usually be overcome by connecting the tester from grid to ground of the tube in the stage being tested.

In addition to checking transformers it can also be useful in testing the range over which a transmitter tank will tune. Just make sure that the high voltage is turned off and connect the probe across the tank to be tested. Now you can tune the tank and follow its entire usable range with the receiver. If the tank being checked happens to be the final, the meter on the probe will indicate when the antenna is brought into resonance.

This little tester was built to do just one thing—sort out some old *ifs* in the junk box. After we tried it we found that it would do a lot of useful chores around the ham shack. With proper care and feeding, it can probably learn to do tricks that we haven't even thought of.

430-470 kHz SWEEP FREQUENCY GENERATOR

Edward Lawrence WA5SWD

Here is a simple sweep frequency generator for aligning the most common *if* strips. The unit has only one transistor because the sweep voltage is taken from the oscilloscope it is used with. Most general purpose oscilloscopes have a sawtooth output jack. By using this sawtooth, the frequency is locked to the position of the trace.

The oscillator is made to deviate in frequency in step with the voltage applied to the base bias circuit, either the sweep voltage or the dc voltage applied at the control point. If no sweep or control voltage is applied, the oscillator runs at the center frequency, and may be used as a conventional signal generator.

The 2.5 mh choke and the two 150 pf capacitors form a very broad tank circuit, so it is easy to FM the oscillator without a great change in amplitude. As to how the change in base voltage causes the frequency shift, I am not quite sure. All I know is that it is quite linear and is a positive shift (**Fig. 3**). That is, an increase in base voltage causes an increase in frequency. Also, a change in collector supply voltage will shift the frequency, so be sure to use a stable supply.

Since an rfc is used as part of the tank, you may have to compensate for a variation in center frequency by changing the 150 pf capacitors to some other value to get 455 khz as your center value.



Fig. 1. Sweep generator circuit diagram.

If you do, then run a plot of dc control voltage vs frequency and adjust the voltage divider R2 and R3 so that 1 volt P-P at the sweep pot wiper gives plus and minus 5 khz (10 khz total). This is not as hard as it sounds. Just listen for the harmonics on a broadcast band radio. For instance, the second harmonic of 430 khz is 860 khz, and the second harmonic of 470 khz is 940 khz, both handy on the BC radio. Note the dc voltages at the control point required to obtain these frequencies. Take the difference and divide by four. The answer is the P-P voltage required to shift the oscillator plus and minus 5 khz. Then apply a low, known ac voltage to the wiper of the sweep pot with the switch in the *sweep applied* position. Adjust the value of the divider resistors to get the proper fraction. In my case it was 0.43.

It is advisable to run the sweep rate as slowly as possible, in order to display the response curve as accurately as possible. The sharper the skirts, the more slowly the generator must pass through the bandpass. With this generator, the amount of frequency deviation is controlled by the P-P amplitude at the sweep pot arm. If you are looking at the response of a regular *if,* you would set the sweep amplitude high to see the entire response curve. As far as an accurate display is concerned, this is fine, since the slope of the skirts is shallow. But if you were looking at the response of a sharp filter, you could not tolerate such a wide sweep, because the fast rate-of-change would tend to skew the display. To correct this, reduce the sweep amplitude to reduce the frequency deviation down to the edges of the skirts of the response curve. This reduces the rate of change and minimizes the skewing of the display. Also, it is better to display the *if* before detection, if possible, to prevent the detector time constant from possibly distorting the display.

If you have the sweep generator set up as described, then it is easy to set the sweep for a known deviation, and then procede to read the 3 or 6 db points from the face of the scope. Be sure to disable the AGC for this test.

For those who aren't familiar with the setup for obtaining the response curve display, refer to **Fig. 2.** and the following outline.



Fig.2. Interconnections of sweep generator.

First, hook up the equipment as in Fig. 1 Set *horz gain* for desired sweep width. Adjust *sweep amplitude* pot on generator for desired frequency range. Set *output level* to mid-range. Adjust the *vert gain* for the desired pattern height.

If we wish to change the total frequency deviation and the horizontal display width at the same time, use the scope's *horz gain* control. This presumes that the amplitude of the sawtooth output is also varied by the *horz gain* control.

If we wish to change the frequency spread and not change the width of the scope display, adjust the *sweep amplitude* control. This allows you to take a better look at the sidelobes or any ripples in the passband, depending on how the controls are adjusted.

You don't have to use a sawtooth to sweep with if it isn't handy.

Sixty hz can also be used, but it will probably skew the passband you are trying to display, so I don't recommend it. One note here: when the sweep generator is first turned on, or the setting of the sweep amplitude is changed, the frequency will drift for a few seconds. This is due to the charge on C1 changing to a new level. C1 is large to couple the low frequency sweep with as little distortion as possible.



Fig.3. Sweep frequency vs dc voltage.

DC CONTROL VOLTS	FREQUENCY
5.86	430
6.27	440
6.69	450
6.90	455
7.12	460
7.33	465
7.55	470

AN ARMSTRONG SWEEPER

Al Donkin W2EMF

Sometime ago while experimenting with SSB crystal filters at 480 kc, it occurred to me that a manually swept Armstrong oscillator with a pot coupled to the tuning capacitor for 'scope sweep voltage would save point by point frequency measurements with a BC221 while adjusting the filter for minimum in-band ripple. A circuit was hurriedly developed, and the results were even better than expected. Simple though it may be, I'm sure anyone who is working with crystal filters will appreciate its usefulness. The effects of tuning and "diddling" were immediately visible in the in-band ripple and the skirts down to about 20 db could be observed with a few twists of the knob.

With this encouraging experience, a sturdier model was constructed. The circuit was assembled on a small piece of Vector-board, with the tuning capacitor and batteries mounted in a 5 × 7 × 3" aluminum chassis. An aluminum bracket was bent to hold the "sweep" pot and mounted behind the tuning capacitor, spaced to accomodate the mechanical shaft coupling. The Vectorboard was also mounted on the bracket.



The oscillator circuit is simple, using a 1 mh rfc for the tank inductor. The range of the circuit as shown is about 400 kc to 500 kc, at center frequency. The tuning capacitor is a Hammerlund MC-50-M with two of the rotor plates removed, resulting in a range of approximately 7-25 mmfd. An untuned amplifier provides isolation of the oscillator from the reactance of the load. I used 2N404 transistors but most PNP *if* transistors will work.

In addition to sweeping crystal filters, I have found this little box handy as a general purpose low frequency oscillator and sweeper for receiver *if's*. The persistency of most oscilloscopes produces a much better display than might be expected, and it certainly beats the point by point method of plotting filter responses.



A NEW BROOM

Dick Gridley K6JHJ

This unit is a sweep generator of simple design, with many uses. Besides being useful for filter alignment, as shown in the diagram, it is useful for optimizing receiver and transmitter performance.



The heart of the rig is an inexpensive item called the Vari-Cap by International Rectifier Corp. Two are discussed here, the 6.8SC20 and the 100SC2. The 6.8SC20, according to the manufacturer, will vary its capacitance from 50 mmfd at .lv to 2.5 mmfd at -200v. The 100SC2 will vary from 600 mmfd at .lv to 100 mmfd at -10v. These units each cost less than $3.00. The construction is not critical in any way, nor is layout a problem—just use good ham practices. Any power supply delivering 150 v dc at 60 ma regulated will do. The oscillator tank must be grounded and I did have some trouble until I removed the unused winding from the 455 *if* transformer used for the oscillator tank.



Sawtooth energy is applied to R1 which regulates the amount to be amplified by V1. R2 linear control merely puts a portion of regulated voltage on the Vari-Cap and thus sets the capacity of Vari-Cap close to its center, so the sawtooth pulse creates a linear frequency swing. This circuit gives about 6 kc sweep. I have used TV horizontal coils for L1 and increased C1 and C2 to .003 for 85 kc and 50 kc operation. However, to get enough swing at low frequency, the Vari-Cap was changed to a 100 SC2. For 200 kc to 10 mc the 6.8SC20 gives plenty of sweep.

A note here about scopes. Most of the average do not go below 15 cycles and the sweep rate should be about 10 cycles. Some do not have a sawtooth output jack. The sawtooth output can be picked off the sync circuit. I found the best point is on the feed side of the sync pot through a .25 mfd capacitor. Some scopes have a couple of jack pins to add capacity externally, some don't. You will find little trouble adding about .25 mfd across the slowest speed.



L1 STANDARD I F TRANSFORMER WITH ONE WINDING REMOVED.
SM- INDICATES SILVER MICA.

The use of the rig is simple. Plug the lead from R1 into the scope's sawtooth output. Couple the output from the cathode follower section of V2 to the filter input through a .001 mfd capacitor. The vertical input of the scope is connected to the filter output through an rf probe. Adjust R1 and R2 about ½ open. With C3 about ½ meshed, adjust the trimmer in the *if* can to put you in the ball park, and then use C3 for fine adjustments of frequency. Additional minor adjustments of R1 and R2 may be necessary. Of course, when used to align a receiver, the diode probe is unnecessary if the input to the scope is picked off of the diode detector. It goes without saying that it is necessary to plot an index for the scope bezel so that a ready reference is available for band pass width and depth of skirt.

Some one now says "This is just like setting ye old TV—*if* band pass." That it is. The only difference here is the frequency and the sweep generator cost was junk and $5.00.

The unused switch, shown in the photo, was installed to select one of three frequencies. However, this rig has been used on about six. I don't think I ever will decide which three to use. The unidentified tube is a 6U8 used as a 1 kc audio oscillator with cathode follower output.







LOW COST SIGNAL SOURCE

Howard White VE3GFW

For many years the Measurements Corporation Model 80 signalgenerator has been the industry standard for tuning rigs. Many hams have wanted to have a laboratory-grade signal source of this type but the $800 price tag is prohibitive. This article describes a signal source that has many of the same features as the 80 except that it only costs 1% as much. That's why I call this the Model 0.8.

You wonder at some of the features of the marvelous little device? To briefly list them, it has:

- Variable output from about 80 nV to 50 mV of rf power.
- Frequency range from 1.8 to 450 MHz so you can cover 160 through ¾ meters.
- Crystal-control frequency stability.
- Fairly clean output signal.
- A 51Ω antenna load.
- Safety feature to prevent the destruction of the device in case a transmitter is accidentally loaded into it.

The Circuit

The circuit is the combined brainchild of many ham engineers and technicians in our local 2m FM club – the Toronto FM Communications Association. More than 300 of these units have been built in the past two years, so the circuit has been exceptionally well tested in the field.

The unit consists of a single 2N5130 NPN transistor oscillator configuration. Other transistors, such as the 2N706, can be used in this circuit with slightly different biasing arrangements; however, the 2N5130 appeared to give the cleanest output signal.

Output level can be varied from less than 80 nV (the best we could measure) to 50 mV. It is controlled by a 1 kΩ pot in the transistor collector circuit. Power is obtained from a 1.5V penlight cell bypassed for rf by a 0.1 μF capacitor.

My present "0.8" signal source has been used intermittently for more than a year without any degradation of output. However, remember to shut the unit off when you're finished with it; the battery doesn't last forever.



Fig. 1. Schematic diagram of the "Point Eight" Signal Source, the "poor man's Model 80."

The unit is built on a PC board. The parts layout is almost exactly the same as that of the schematic shown in Fig. 1. The electronic components are placed on the copper side of the board. The on-off switch-level control, frequency adjustment, output jack, and crystal socket are on the other side (Fig. 2). The unit can be packaged in a minibox.

Almost any crystal in the 1.8–12 MHz will oscillate in this unit. The output is rich in harmonics to 450 MHz, so you can tune up any receiver from 160 to ¾ meters.

The output impedance of the signal source is 51Ω, a value which simulates a perfect antenna load to the receiver. This is the manner in which this is accomplished: A 51Ω, ½W resistor is connected across the terminals of an RCA phono jack. No physical connection is made to the circuit except through the common



Fig. 2. Minibox layout of the signal source panel.

ground of the PC board. The maximum output level depends on the lead lengths of the resistor. (The unit has plenty of output when the lengths are about ½ in. long.) This design has an added safety feature, too; if by accident you load a transmitter into the unit, all that is destroyed is the ½W resistor.

Operation and Uses

These units were originally designed to tune up 2m FM receivers. The procedure is quite simple. You connect the signal source to the antenna input on your receiver. Plug in a transmit crystal, and adjust the frequency control for a zero reading on the discriminator. Adjust the output level to the desired signal strength (below first limiter saturation) and tune up the receiver.

There are a myriad of other uses for the signal source. Using a 3.5 MHz crystal, you have a band edge marker. With the transmit crystals on a Twoer or any other transmitter you have instant frequency spotting without modifying the circuit of the transmitter. Of course, the signal source can be used to tune up any receiver, peak tuned circuits, be an rf source for an antenna noise bridge, and so on.

RECEIVER TWEAKER

Malcolm Oakes K6UAW

I've found that the singlemost piece of needed test equipment by the amateur on FM is a receiver alignment generator. Most of us, however, do not have access to a signal generator. (Come on now, you wouldn't really call that *TV thing* a signal generator would you?)

The unit to be described is a very functional device that will allow you to scrape every ounce of sensitivity from your receiver. The generator can be built so small you can carry it around in your shirt pocket. Compactness, combined with its battery-powered portability make it ideal for servicing mobile receivers. Stability? It's crystal controlled and is as good as the rock you plug in (you obtain the rock from your transmitter). Output reactance? Nearly zero degrees, allows proper tuning of rf stage. The attenuator shown does not have a great deal of dynamic range due to distributed capacity of the potentiometer. However, I said before, the unit was "functional" and it is just that. The signal can be attenuated into the noise and brought up to approximately a 30 uv level; overly sufficient for a normal alignment.

Construction

The circuit layout is not particularly critical, and if laid out in a manner similar to the schematic, no problems should be encountered. The attenuator section should be completely shielded away from the oscillator and multiplier stages, so rf leakage will not be a problem. A crystal socket should be provided so the unit is versatile for any frequency. However, if you plan on using it on only one channel and can spare a crystal, build it with the crystal inside. Two glass piston screwdriver adjusted trimmers must be provided (to "rubber the crystal" and tune the output to resonance) as front panel controls.



ALL RESISTORS ¼ OR ½ WATT
ALL CAPACITORS ARE IN UUF

Fig. 1. Schematic diagram of Tweeker. The registor marked * may have to be changed to one of lower value if the recommended transistor is not used.

Circuit

Transistor Q1 in the first stage is a crystal oscillator which is very loosely coupled to Q2 the multiplier. This stage is biased into "class C" so as to multiply the 6 mhz crystal 24 times, up to the two-meter band. (3 mhz crystals will also work at a multiplication of 48.) Another important function of this stage is to attenuate the oscillator output (about 6-7 volts peak-to-peak) to a level usable at the two-meter frequency for alignment – 30 to 40 uv. The potentiometer adjusted attenuator takes the signal down to a level as desired by the operator.

I developed this unit for use on two meters. Several have been built and all work fine. But, for those of you who need a six-meter generator, this same circuit should work fine with the only modification needed being the final tank frequency. (A few more turns on the coil and a slightly larger trimmer capacitor.)

Adjustment and operation

Connect the output of the generator to your rig. Plug in a crystal and tune for zero (with frequency adjustment) on the discriminator (center frequency). Now, looking at the first limiter voltage, peak the final tank. Attenuate the generator as necessary to avoid saturation of the limiter. Repeat as necessary until a definite peak is reached.

If the generator will not go down into the noise with the attenuator control, the final tank may be detuned as necessary to provide the desired range on the attenuator.

CITIZENS BAND ALIGNMENT AID

Edward Lawrence WA5SWD

It is obvious that the front end of a receiver should be tuned to respond equally well across the band, and thus have consistent sensitivity at any frequency in the band, if maximum usefulness is to be obtained. The usual method of insuring reasonable results is to tune at the middle, and check the ends. This is rather spotty, at best, as it would be better to check all channels. This is involved since you must set both frequency and amplitude 23 times in a single pass.

Naturally, a good sweep generator could be used, and the rf-mixer tracking set with it instead, but this was not available to me at the time. The circuit in Fig. 1 was originally a super-regenerative receiver taken from the GE Transistor Manual. These, as is well known, tend to spray a lot of rf back out the antenna. With this in mind, I listened with a communications receiver and noted strong modulation products about 100 kHz above and below the "carrier." Deducing this to be caused by the quench frequency, I brilliantly decided to drop the quench frequency into the audio range, by increasing the capacitance across the base bias resistor. Lo and behold! Suddenly the entire Citizens Band was alive and jumping with a mass of "line noise," which at first appeared to be like



Fig. 1. Schematic of the alignment aid. L1 is 15 turns No. 22 tapped at 9 turns from the collector end. No switch is shown, so remove battery when not in use.

73 LIBRARY

1976
REPEATER ATLAS OF THE WORLD

NEW REPEATER ATLAS

Hundreds of new listings . . . listed by both location and frequency . . . dual listing, invaluable for your car . . . find those repeaters as you travel. This is the ONLY complete list of repeaters being published. Almost 3000 repeaters listed in this issue . . . repeaters from all over the entire world. only $1.95



VHF ANTENNA HANDBOOK

The NEW VHF Antenna Handbook details the theory, design and construction of hundreds of different VHF and UHF antennas . . .

A practical book written for the average amateur who takes joy in building, not full of complex formulas for the design engineer. Packed with fabulous antenna projects you can build. $4.95

73 Vertical, Beam, and Triangle Antennas

73 VERTICAL, BEAM AND TRIANGLE ANTENNAS by Edward M. Noll W3FQJ

Describes 73 different antennas for amateurs. Each design is the result of the author's own experiments: each has actually been built and air-tested. Includes appendices covering the construction of noise bridges and antenna line tuners, as well as methods for measuring resonant frequency, velocity factor, and standing-wave ratios. 160 pages. $5.50

73 Dipole and Long-Wire Antennas

73 DIPOLE AND LONG-WIRE ANTENNAS by Edward M. Noll W3FQJ

This is the first collection of virtually every type of wire antenna used by amateurs. Includes dimensions, configurations, and detailed construction data for 73 different antenna types. Appendices describe the construction of noise bridges, line tuners, and data on measuring resonant frequency, velocity factor, and swr. 160 pages. $5.50

The 2-Meter FM Handbook

2M FM HANDBOOK

Contains almost every conceivable circuit that might be needed for use with a repeater. All circuits explained in detail. All aspects covered, from the operator to the antenna. $5.95

Practical Test Instruments You Can Build

Practical Test Instruments You Can Build

37 simple test instruments you can make – covers VOMs, VTVMs, semiconductor testing units, dip meters, wattmeters, and just about anything else you might need around the test lab and ham shack. $4.95

IC op-amp COOKBOOK

IC OP-AMP COOKBOOK

by Walter G. Jung. Covers not only the basic theory of the IC op amp is great detail, but also includes over 250 practical circuit applications, liberally illustrated. 592 pages, 5½ x 8½, soft bound. $12.95

RF AND DIGITAL TEST EQUIPMENT YOU CAN BUILD

RF burst, function, square wave generators, variable length pulse generators – 100 kHz marker, i-f and rf sweep generators, audio osc, af/rf signal injector, 146 MHz synthesizer, digital readouts for counters, several counters, prescaler, microwavemeter, etc. 252 pages. $5.95.



WEATHER SATELLITE HANDBOOK

Simple equipment and methods for getting good pictures from the weather satellite. Antennas, receivers, monitors, facsimile you can build, tracking, automatic control (you don't even have to be home). Dr. Taggart WB8DQT $4.95.

73
HANDBOOK
SLOW SCAN TELEVISION HANDBOOK

SSTV HANDBOOK

This excellent book tells all about it, from its history and basics to the present state of the art techniques. Contains chapters on circuits, monitors, cameras, color SSTV, test equipment and much more.
Hardbound $7 Softbound $5

The Fascinating World of RADIO COMMUNICATIONS

FASCINATING WORLD OF RADIO COMMUNICATION

Interesting stories of the history of radio pioneering and discovery. Also includes the fundamentals of broadcast band DXing. A must for every radio amateur. $3.95.

73
TEST EQUIPMENT LIBRARY

TEST EQUIPMENT LIBRARY

A multi-volume anthology that you won't find anywhere for three times the price! The editors of *73* present a complete guide to testing that is both basic and complete and aimed at everyone from beginners to amateur Extras. Everything from how to test diodes to frequency counters. Plus a cumulative index . . . all in *73*'s all new TEST EQUIPMENT LIBRARY Vol. I – Vol. III.

Vol. I – Component Testers – $4.95
Vol. II – Audio Frequency Testers – $4.95
Vol. III – Radio Frequency Testers – $4.95

Master Handbook of 1001 Practical Electronic Circuits

1001 PRACTICAL ELECTRONIC CIRCUITS

Tab's new 1001 circuits is available for only $9.95 ppd. The next time you want a circuit for just about anything, eat your heart out that you didn't send for this book the first time you read about it. You'd better order the book right away, before they run out. $9.95

VHF PROJECTS FOR AMATEUR AND EXPERIMENTER

A must for the VHF op. Opening chapters on operating practices and getting started in VHF, both AM and FM, followed by 58 chapters on building useful test equipment, modifying existing and surplus gear. $4.95

73 MAGAZINE • PETERBOROUGH NH 03458

Hewlett Packard 6384A power supply

SPECIFICATIONS:

DC Output: 4 to 5.5 Vdc @ 8 Amps

Load Regulation: 2 mV no load to full load

Line Regulation: 2 mV for line changes between 104 and 127 Vac at any output voltage and current within specifications

Ripple & Noise: Less than 5 mV peak to peak

Crowbar, Factory Set at 6.25 V, Automatic cutback limit circuit and overvoltage crowbar protection.

HEWLETT PACKARD 6384A Power Supply $99.95

Power design 1210 regulated power supply

Output: 0 to 12 V @ 0 to 10 Amps

Regulation: 0.01% or better.

Ripple and Noise: Less than 500 uV rms. Voltage Controlled, Metered.

POWER SUPPLY 1210 - Regulated Power Supply - $149.00

a full range, 5-function 3½ digit multimeter

RANGES

DC VOLTS: 0 to ±1.999/19.99/199.9/1500 Volts

AC VOLTS: 0 to 1.999/19.99/199.9/1000 Volts

DC CURRENT: 0 to ±1.999/19.99/199.9/1999 mA

AC CURRENT: 0 to 1.999/19.99/199.9/1999 mA

RESISTANCE: 0 to 199.9 Ω through 19.99 Megohms (6 ranges!)

ACCURACIES

DC VOLTS: ±0.2% F.S. ±0.2% of reading
(1000V range: ±0.5% F.S. ±0.5% of reading).
AC VOLTS: ±0.7% F.S. ±1% of reading
(1000V range: ±0.7% F.S. ±2% of reading).
DC CURRENT: ±0.5% F.S. ±0.8% of reading
(1000 mA range: ±0.5% F.S. ±1.8% of reading).
AC CURRENT: ±0.5% F.S. ±1.3% of reading
(1000 mA range: ±0.5% F.S. ±2.3% of reading).
RESISTANCE: ±0.5% F.S. ±0.8% of reading
(10 megohm range: ±0.5% F.S. ±1.8% of reading).

DATA PRECISION MODEL 134 – $169.00

INSTRUMENTS & COMPONENTS

AST/SERVO SYSTEMS, INC.
20 Republic Road, North Billerica MA 01862
(617) 667-8541

NEW 73 BOOKS

TEST EQUIPMENT LIBRARY
Vol. III, Radio Frequency Testers

Radio frequency waves are the common denominator of Amateur Radio so here is a book for all hams. No matter what your specific interest, such items as SWR, antenna impedance, line impedance, RF output and field strength should interest you. This book not only gives detailed instructions on testing these items but includes sections on signal generators, crystal calibrators, grid dip oscillators, noise generators, dummy loads and much more. It's a must for all up-to-date shacks.

Test Equipment Library
Vol. III, Radio Frequency Testers $4.95

TEST EQUIPMENT LIBRARY
VOL. II, Audio Frequency Testers

HOW'S YOUR SPEECH POWER? YOUR SHIFT? YOUR SYNC?

You can find out easily with a little time and a junk box full of parts. It's all right there in the new Volume II of the 73 Test Equipment Library . . . Audio Frequency Testers . . . jam packed full of all kinds of audio frequency test equipment. So if you're into SSB, RTTY, SSTV, etc., this book is a must for you . . . good book for hi-fi addicts and experimenters too!

Test Equipment Library
Vol. II, Audio Frequency Testers $4.95

BUILD YOUR OWN TEST EQUIPMENT!

SAVE A BUNDLE!



TEST EQUIPMENT LIBRARY
VOL. I, Component Testers

Just out is Volume I of the 73 Test Equipment Library . . . how to build transistor testers (eight of 'em), diode testers (3), IC testers (3), voltmeters and VTVMs (9), ohmmeters (8 different kinds), inductance (3), capacity (9), Q measurement, crystal checking (6), temperature (2), aural meters for the blind (3) and all sorts of miscellaneous data on meters . . . using them, making them more versatile, making standards, things like that. Invaluable book, ridiculously low priced.

Test Equipment Library, Vol. I, Component Testers $4.95

Send me:
☐ Vol. I . . . . Component Testers @ $4.95
☐ Vol. II . . . . . Audio Frequency Testers @ $4.95
☐ Vol. III . . . . . Radio Frequency Testers @ $4.95

☐ Cash enclosed ☐ Check enclosed

☐ BankAmericard ☐ Master Charge ☐ American Express

Card # ________________ Interbank # ________ Expiration date ________
Name ________________ Signature ________________
Address ________________________________
City ________________ State ________ Zip ________

73 magazine • Peterborough NH 03458

Meshna

New England's #1
Surplus Dealer For Over 20 Years.

Send for our latest catalog.

Meshna PO Box 62 E. Lynn, Mass. 01904



Fig. 2. Full size PC board layout (foil side).



Fig. 3. Component side parts placement.

natural noise. Then I turned on the BFO, which showed it to be many, many, many closely spaced "carriers." I presume the lower quench frequency develops a much larger bias swing on the base of the transistor, FM'ing it across the entire band. This stuff is concentrated in the region of 27 MHz, with very little spill-over into 10 or 15 meters, although the level across the design range is rather constant. The nearly constant rf level is what I needed to simplify tuneup of the front ends of the units I was working on.

Figure 2 is the layout of the P.C. board I made to facilitate reproduction of this useful circuit for a few interested friends and Fig. 3 is the component layout.

I used 6 ft of wire as an antenna connected to the emitter side of the rfc, with 9 ft of wire on the battery side of the rfc as a counterpoise. Since this made it a bit large, I carefully hung it vertically in a handy tree nearby. Of course, since this put a strong signal on every channel into every CB receiver within 300 yards, I limited the use of this device to avoid unnecessary interference to the deserving users of the band. However, one fellow accidentally launched his into a tree too high to recover with an over-ambitious heave, and it ran for about a month in the dead of winter in a nameless northern city, helping every CBer for miles around align their sets! It only draws about half a milliamp from a 9 volt battery.

Since I am sure many others would like to align their 11 meter receivers for optimum results, I am presenting this circuit as a very low cost and worthwhile aid.

FET CHIRPER

Chuck Hines K6QKL

The Chirper is an automatically keyed, crystal controlled, signal source which may be used to optimize the signal-to-noise ratio of a receiving converter. Homebrew or commercial, converters are a common thing around an amateur station. And, most of the VHF Tribe have read thru a jungle of esoterica dealing with low noise front ends, the velvet beauty of FET's on Two, noise generators and eternal truth, and how to copy 20 db below the noise by the selective use of liquid helium. With a kind of relentless evolution converters have been getting better and better, noise figures become lower, and the prices of suitable front end devices are dropping by the hour. But when it comes to aligning these converters the scene is one of wretchedness. A black art at best, the job is taken up with an enduring combination of blunt instrument and myth. The latter have a certain charm. Are you convinced your converter is in top notch condition because you can "hear noise" when you attach the antenna – or better yet, when you place a 50 ohm resistor across the input? Try putting a complete short across that same input. Shorts aren't much good as noise sources. You'll find the short gives about the same change in noise level as the 50 ohm termination. What has changed is the impedance the front end "sees". The same is partially true of the noise from the antenna. Neither is indicative of the performance of the converter. Peaking the system up for maximum on either a weak signal or on noise gets you nowhere. The diode noise generator which every VHF book of substance describes is a good and useful tool when used properly. The assumption is that everyone already knows full well how to use it and does so. Few in fact do.



I'm sure you've read of it before in many places, but a little redundancy is in order. The noise with which you are concerned is the noise generated *internally* by the first tube, transistor, or other active device the signal encounters upon its arrival at your converter. By fiddling with the external reactances, adjusting the voltage and current and otherwise manipulating the things soldered to the device, one may minimize the internally generated noise. At the same time the reason the front end exists is to amplify the signal. One usually desires as much amplification possible, short of smoke and oscillation. Minimum noise and maximum amplification is the game. Though the two are not quite mutually exclusive a certain amount of compromise takes place. Thus, the signal to noise ratio. When aligning a converter's first stage every adjustment effects *both* signal and noise. Given a constant signal source coupled into the converter thru an appropriate impedance, the job is finished when the front end has been adjusted for the greatest *difference* between signal and noise of which it is capable.

The Chirper is designed to help you do all this by letting you see what effect each adjustment has on both signal and noise. The TIS34 oscillates at a frequency controlled by the crystal. With the constants shown, that can be anywhere between 8.2 and 36 MHz. The variable capacitor must be adjusted for resonance. It isn't particularily critical but its setting peaks the *rf* output at either the fundamental or some harmonic. For 6 meters an 8.35 MHz crystal is used. A 9.0 MHz rock will pin the meter when the



Fig. 1. Schematic of the FET chirper.

Chirper is connected into a 2 meter converter. The Amidon toroid is wound with No. 30 enameled, 40 turns for the primary and 5 turns for the secondary. After it is wound, spread the turns to fill the toroid and paint it with Q dope. The diode and 5 pF coupling capacitor are connected with the shortest possible leads, the diode being grounded at the *rf* connector. The harmonic output is excellent and quite useable at 1200 Mhz.

The oscillator is turned on and off by a multivibrator combination of unijunction and NPN transistor adapted from the *G. E. Transistor Manual.* The rate at which the multivibrator cycles is determined by the large value capacitor, in this case 33 mF. The polarity of the capacitor is critical. Observe it. To increase the cycling rate, decrease the capacitance; and, to decrease the rate, put in a larger value. Mine cycles a little under once per second. A value somewhere between 30 and 40 mF should suit your needs. You are better off scrounging some odd value from a defunct computer board because of the tolerance problem. If it says 33.2 mF, its probably pretty close to that value. Otherwise you're dealing with tolerances of plus 100% and minus 50% or something equally grotesque. The 50K pot determines the portion of the cycle during which the oscillator is On and is mislabeled rate on the Chirper shown. The HEP-310 is generally available and inexpensive. Other unijunctions were not tried. On the other hand almost any NPN of reasonable quality will work in place of the 2N718. A number of 2N388 and 2N3478's were tried and behaved well. It's a good place to use those transistors you've replaced with FET's. Use something with a Beta of 50 or better for best results. The 5100 ohm resistor in series with the pot is for current limiting. It's deletion will increase battery drain with no increase in Chirper performance. Normal current from the 9 volt battery is around 5 mA.



Fig. 2. Test set-up for converter alignment.

Construction is non-critical and pretty much a matter of taste. Mine is built on a piece of vector-board and mounted in a Suzurando box, model M-1N. It measures 3¼ X 2 X 4" and there is still room inside for additions. It sells for 330 yen, about 92c. A slide switch is used to turn the power on and off. Paint one well of the slide switch with red paint – Testor's Pla, a model plastic paint, is good – and the switch will indicate its position. Red for On and black for Off. It saves batteries. Check your work and the polarity of the large capacitor. Re-check the connections to all the semi-conductors. With four different kinds of devices things can become confused. Set the pot to the middle of its range. Insert a crystal in the socket. Connect the Chirper to your converter, turn the switch on and adjust the variable capacitor for the highest reading on your S-meter. The oscillator will turn on and off. Varying the pot will extend or diminish the amount of time the oscillator is on. Whatever you do, *don't connect the chirper to an external antenna.* The harmonic content is high and even at this power level is sufficient to cause severe interference to television receivers within a two block radius.



For converter alignment, the test set-up is illustrated in Fig. 2. The Chirper is fed to the converter thru an attenuator for two reasons. First, the power output of the Chirper is too high on six and two. You don't want to align with a forty over nine signal. Something around S-5 to S-7 is desired. Second, the attenuator maintains a 50 ohm termination for the converter. A converter cannot be aligned with a floating input impedance. Fixed and variable attenuators of excellent quality are available thru surplus and homebrew data is available. See *73,* January 67, p. 40 for one that will do the job. Turn the receiver avc off. The read-out options are diverse. The best is probably a scope connected to the *if.* A vtvm can be used, connected to the audio output. And, the S-meter can be used with the avc on *fast.* This will vary with the receiver and it's particular time constants. What needs to be avoided is avc pumping that interferes with your readings.

Turn the Chirper on, adjust the attenuator for a convenient signal level. When the oscillator is on, you're reading signal. When the oscillator is off, you're reading noise (on the scope, vtvm, S-meter, etc.). As you make adjustments on your converter, observe the effect on both signal and noise. Adjust for the greatest difference between the two. Turn the Chirper off and re-check the converter neutralization. If necessary, reneutralize the converter and go thru the whole thing again. Talking about it makes it seem somewhat complex. It really isn't and the whole business won't take long once you've done it. It will become quickly apparent that highest signal level and lowest noise level do not coincide. You can vary the bias, voltage, etc., and observe the effects of each on the signal-to-noise relationship. You can, in short, optimize your converter's performance.

A number of things can be done with the Chirper. There is room in the box to build another oscillator section connected to the transistor collector, operating in parallel and simultaneous with the first oscillator. By appropriate choice of crystal and attenuation, both signals can be introduced into the converter in order to adjust the mixer for minimum cross modulation.

Or, instead of using an oscillator at all, you can use the switching section of the Chirper to key a noise generator on and off. This has a certain attraction where an integrating network is used prior to a vtvm. In this case noise is used as a signal.

In spite of it's name, the Chirper is remarkably stable. Chirp becomes apparent from two meters or so, but is no problem. Build one and take the myths out of your converter.

UHF SIGNAL SOURCE

Bill Hoisington K1CLL

The UHF experimenter learns early that the UHF ham bands don't always furnish a signal when you need them. When I build receivers and converters for 432 and 1296, I find that I need a small signal generator for alignment and band spotting. Not much power is needed for this work, so transistors are the ideal choice for generating the signal. This signal source is in three parts, a 432 source, a tripler to 1296 and a modulator.

The 432 Driver

I started with a low-cost 27 mc crystal that I found in my junk box. (Never mind how it got there!) I used my usual phase-reversing crystal circuit followed by a bunch of doublers. Lower-priced transistors were used in the early stages and the UHF ones saved for later. You really need good ones on 1296! Each doubler is biased from rectification of rf from



Fig. 1. Schematic diagram of the 432 mc signal source. The transistors aren't critical in most cases and other UHF and VHF ones will work fine.


RF OUT
1-7 TRIMMER
TEFLON TAPE
SOLDER (TYPICAL)
3/8"
-12
1/2"
2N1141
C
MAC-5
BRASS COLLECTOR RETURN PLATE
TOP VIEW
GROUND BASE
2 1/8"
COLLECTOR STRAP
1/4"
SIDE VIEW

Fig. 2. Details of the 432 mc collector circuit.

the previous stage. If you need more output than this circuit gives you, use less than a 1 k resistor in the emitter, but watch out for high collector current. **Fig. 1** shows the schematic of the 432 mc generator and **Fig. 2** gives details of the 432 mc collector circuit.


-12
RED
GREEN
T1
AR-115
R1
.02
BLK
T2
TO EMITTER OF 432 MC FINAL DOUBLER
BLUE
.1
10 μfd
500Ω
500Ω
2N247
1K
.1

Fig. 3. The tone oscillator for the 432 mc signal source.

The tone modulator

This is a crude modulator (**Fig. 3**), but it works. The modulation transformer is not absolutely necessary, but seems to improve results. You can apply the modulation almost anywhere for this application, but modulating across the 1 k emitter resistor gave the cleanest sound with the doubler used.

Now to 1296

I built this tripler to 1296 just for the fun of it. But it worked quite well. I normally don't hold with triplers at this frequency, but it's an easy way to get 1296 mc energy from the 432 mc driver. The transistor I used was a Motorola 2N1141. It's several years old and there are better ones that are far cheaper now. But it does work on 1296. I couldn't get it to work with grounded emitter, but grounded base is fine. **Fig. 4** gives the schematic but **Fig. 5** gives the details, which are vital. The input on 432 tunes very nicely. But I had to reduce the emitter resistor in the doubler to 432 to get enough drive. It ended up at 200 ohms. The collector circuit is short, but tunes smoothly. The 1296 mc output registers 100 a in the 1296 cavity in the May 73.


2N1141
MAC-5
432 MC
1296 MC
1-7
1K
*SEE TEXT
-12

Fig. 4. Schematic of the 1296 mc tripler.


EMITTER POT (SEE TEXT)
1K
MAC-5
1296 MC OUTPUT
BASE RETURN LEAD
SOLDER (TYPICAL)
BRASS EMITTER RETURN PLATE
-12
B
E
C
1/4"
TEFLON TAPE
BRASS COLLECTOR RETURN PLATE
BASE "GROUND" PLATE
INPUT 432 MC
1-7 TRIM.
TUNING CAPACITOR (SEE TEXT)
STRAP LTHS.
TRANSISTOR TYPE 2N1141
1 1/2"
7/16"

Fig. 5. Pictorial layout of the 1296 mc tripler.

You might try a small amount of modulation on the 1296 mc tripler. Also a waveguide attenuator. Be seeing you on 23 cm.

CRYSTAL CONTROLLED SIGNAL SOURCE WITH INFINITE ATTENUATOR FOR 144, 432 AND 1296 MHz

Bill Hoisington K1CLL

One of the most useful test-equipment gadgets the homebrewer can build is a signal generator. The one described here is of commercial quality and it can be completely contained inside a waveguide. Positioning, by sliding along the waveguide, provides a variable-strength stable signal of one millivolt, one microvolt, one nanovolt, or less, dropping down gradually to a true zero. It does this in a perfectly smooth fashion without steps or jumps so that every fraction of a decibel in lower noise figure shows immediately on the slide dial. What's more, the slide can be calibrated so that FM'ers can use the device for directly measuring receiver sensitivity in tenths of a microvolt.

In building a 6 meter receiver recently for maximum absolute sensitivity I naturally had to check especially on the first-stage rf transistor and circuit for minimum noise figure. (For this type of work you *must* have a signal generator capable of being attenuated out of sight with any receiver you can buy for any money.) The usual generators on the market under $100 do not do this. And many of the very expensive generators get so leaky that they have to be used 200 ft from the receiver. At any rate, the generator described here can be made up quickly and at low cost, and it *is* stable, reliable, and infinitely variable.

Waveguide

The only possible difficulty might be in obtaining the piece of waveguide needed. The piece I used is 4¼ in. wide by 2 1/8 in. high, and is 24 in. long. If you have a choice, get a piece a little longer. You could make up this item out of brass or copper if you had to, because in this case it is not used to *carry* energy but to *attenuate* it, so the worse you make it the better!

The waveguide *must not* have any holes in it and should be reasonably smooth inside; otherwise your dial would not read smoothly in attenuation. You *could* use copper or aluminum drain pipe, although I have not tried them yet. Working directly on the rf, this attenuator is good for any kind of modulation, including SSB, FM, pulse, or what have you.

Construction

Figure 1 shows the basic idea. When the signal generator plate is close to the


GENERATOR
WAVEGUIDE
CLOSED AT REC. END,
OPEN AT THE OTHER END
COPPER
END CAP
MUST BE TIGHT!
DOWEL
RCA
JACK
J1
B
A
T
A
F
M
O
D
O
S
C
SIGNAL
GENERATOR
PLATE
RECEIVER
PICKUP
PLATE
CARDBOARD OR PLYWOOD
BASEBOARD, SLIDES IN & OUT

Fig. 1. Sketch shows plan-view layout of unit inside waveguide attenuator. The oscillator unit is mounted on a flat wood or cardboard strip that can be calibrated to give accurate indications of output signal.



Fig. 2. Schematic of generator. This entire assembly about 3 x 4 in. including small 9V battery and switch must be entirely inside the waveguide. No wire or metal of any kind can be brought outside.

receiver pickup plate, you can get about 100 mV of signal into the receiver, and it is handy for checking diode receivers. When the two plates are about 8 in. apart, the signal is just detectable on a good receiver. Additional spacing between plates amounts to "waveguide beyond cutoff." I do not believe that there is any receiver in the world that can pick up the signal much beyond the 8¾ in. point.

Pretty soon in your receiver "peaking" work you get to that signal that may be but a tenth of a microvolt or so, and you begin dreaming about cryogenic front ends, masers, and such. As mentioned, every fraction of a decibel lower in noise figure, every improvement in sensitivity comes out rigorously and relentlessly on that slide dial. You can easily check which of your low-noise transistors is really low, whether that MOSFET will do a better or worse job for you, and in which circuit.

As you go up in frequency you may have to make smaller and smaller oscillators in order to fit in smaller waveguides to get the cutoff effect. (That will not be a problem if you read 73; the May issue described a "postage-stamp-sized" rf generator that is an ideal candidate for the signal source.)

Circuit

A crystal oscillator, an af oscillator, and a simple class A modulator do an excellent job to start with. Figure 2 shows the present unit as used on 6 meters. It must be stressed again that no wire or other piece of metal may be allowed to reach the outside from this assembly. I'm making up another for 2 meters soon (still my favorite band) and will try one on 450 a little later.

Audio

A controlled-feedback transformer-coupled af oscillator does a good job in furnishing a sine wave. A Motorola HEP55 is used for the oscillator, with feedback to the base from the collector through transformer T1, controlled by resistor R2. Audio output is taken off the 5 kΩ winding of T1, is fed through R4 the modulation control, and then to the base of af modulator Q2. Transistor Q2 is set up for low-power class A operation because not much modulation is needed for the signal generator. Transformer T2 is an old 5W unit from "tube-type portable" days. The secondary of T2 feeds a modulated +9V signal to Q3, the crystal-controlled 50 MHz oscillator.

This rf oscillator is one of my negative-feedback jobs with phase reversal in the crystal. A 1½ in. square plate is tied onto the collector, radiating energy to the receiver pickup plate facing it inside the waveguide. This energy is rapidly attenuated as you move the plates apart, and should be impossible to detect after some 9 or 10 in. of separation.

Once again, do *not* bring any wires or any other metal or conductor out from the oscillator assembly. If you want an outside controlled switch or other control, bring it out as a wooden dowel handle.

That's about it. Tune everything up outside the waveguide on the bench; when you're satisfied, plug your best 6 meter receiver into J1, push the oscillator plank along the waveguide (or rather I should say pull it along) away from J1. You'll get a surprise! Hope this helps you with your low-noise receiver work. It did a lot for me.

LOW COST 220 MHz SIGNAL GENERATOR

Bill Hoisington K1CLL

This article describes the design and construction of an easy to build, inexpensive, crystal controlled signal generator for the 220 MHz band, including a very low cost attenuator that goes from a quarter volt down through 1/20th of a microvolt and on to a real zero (of rf power). It is very useful for receiver front-end tuneup, low noise tests, and as a portable field generator for overall antenna tests through the receiver. For signal identification purposes, af and FM modulation are included.

If you really want to fight for a low-noise front end, this piece of equipment will be of great assistance to you, because the attenuation really is infinite and without any difficult bypassing or shielding.

Design of the attenuator.

Infinite attenuation is achieved here by the use of a 50¢ piece of aluminum tubing, as shown in Fig. 1. You cannot drive 220 MHz signals more than a few inches down inside of a piece of aluminum tubing. By putting *everything* – battery, on-off switch, circuit and all – on the movable generator strip and sliding it in and out of the tubing, you avoid all touchy, difficult and expensive bypassing, costly attentuator pots, shielding, etc., and provide a simplified means of varying the attenuation with stable, smooth, easy repeatability. Calibration is of the slide rule variety and also simple as far as writing down the microvolts on the scale is concerned.

This principle is older than radio tubes; in fact Sir Oliver Lodge used it in his 1890 microwave work.

Attenuator Construction Details

Figure 1 tells most of the story, with details in Figs. 2 through 9. An adequate rf seal can be made at the pickup end of the aluminum tubing, standard TV masting, 1¼ O.D., by 2 or 4 tabs in one end as in Fig. 3 and bending them back as shown, then cutting off the excess tubing. Install the pickup, plate, output jack, and end plate as shown in Fig. 1. I used time-saving external mounts for fastening it down to the wood baseboard as shown in Figs. 2 through 5. Drill a ¼ in. hole for a screwdriver as in Fig. 2, and use angles for the pickup end. Figure 2 also shows the scale in use for attenuation settings, and Fig. 3 shows pointer details.


STANDARD ALUMINUM MAST, 1 1/4 INCH O.D., 46 cm LONG
COPPER
END PLATE
COPPER
PHONO JACK
SWITCH
BAT.
AF
OSC.
QUINT
OUTPUT
WOOD DOWEL
COPPER CLAD, 2.3 cm WIDE, 21.5 cm LONG
2 cm
ROUND
INSULATE

Fig. 1. Sideview, 220 signal generator and infinite attentuator.


BLACK FIBER OR SIMILAR
FASTEN UNDER PUSH ROD
WOOD DOWEL PUSH ROD
69 cm
6 cm
WOOD 2 cm THICK
ALUMINUM MAST

Fig. 2. Top view of the 220 signal generator and details of the calibration pointer.

Figures 6 and 7 show pictorials of the layout, top view and side view.

The Generator

Nothing too fussy here, but attention to details will assure reliable af and rf oscillation at low power and low battery drain and good frequency multiplication. Figure 8 shows the schematic with the details of the two oscillators, the crystal in the 44 MHz range, and the quintupler. The af uses a standard circuit which, however, has one item to watch. Contrary to a transformer coupled circuit, which is seldom mentioned, this twin-T job has a nasty trick of not starting every time. However a small cap from collector to ground cures this and makes it 100% reliable in that respect. The emitter being grounded, I suppose this establishes the correct in-phase relation with the collector, in which both of these elements should be in phase. You can put a small trim pot af gain control between the modulator and the oscillator if you wish, watching out for dc voltages of course. As shown here, there is plenty of modulation for signal identification, both AM and FM.

Referring to Fig. 8, at the left is the af oscillator. It is not down symmetrically, but you can note the two 22K resistors and the two .02 frequency settling caps, along with the .05 and the 2.2K terminating the lines. All of these set the frequency, and to change the frequency you should vary all of them in at least their approximate present ratios. It is around 500 cycles as shown. Do not forget the "starting cap" from collector to ground.



Fig. 3. Cable end view tubing.



Fig. 4. Open end view.


TUBING
WOOD

Fig. 5. Side view.

This audio is fed to the base of the multiplier where it provides some AM and some FM modulation for signal identification purposes. When working with receiver oscillators, and in particular with high-ratio multipliers, this is very important. It may also be locked into any old scope sync for noise figure and sensitivity comparisons. The scope sync gives a reference point where the signal to noise ratio will always be the same, without resorting to guess work. The crystal oscillator is my old tried and true crystal phase-reversing job, which uses negative feedback from the collector coil, which, after going through the crystal, reverses phase and becomes positive, thus assuring oscillation but *only* on the crystal frequency. A HEP 75 (similar to the famous 3866) is used for the quintupler. A lot more output is noted with this powerful but smooth operating old faithful, still good to 450 MHz.

The output goes to the antenna plate on the forward end of the baseboard plank. When this plate is moved all the way in so that it is only ¼ in. from the cable pickup plate in the end of the aluminum tube, a full scale reading may be obtained on a 50 microamp meter on the output of a tuned diode detector (see Fig. 9). My first model here has marks on the scale (see Fig. 2) for 1 rf stage; 2 rf stages; mixer (feeding into a good i-f strip); mixer plus 1 rf, etc. At the 1 rf plus mixer, you begin to hear all the repeaters within 100 miles or so. With 2 rf plus mixer (followed by a sensitive i-f of course) you are really getting sensitivity. This is where you put a scope in line in order to have an electronic comparison point for signal coming out of the noise purposes, and then can really get into the low-noise bit, if you have a hermit location. Just happens I have one here. When I hear the noise of a car, it's a visitor!


TIE POINTS
HEP 55
HEP 75
9 V BATTERY
E
B
C
E B C
+9V
E
C
SWITCH
SOLDER
XTAL
L1
404 ARCO
SOLDER
403 ARCO
L2
400 ARCO
SOLDER

Fig. 6A. Layout, top view.


COMMON PIN
DRILL HOLE AND HAMMER IN
FIBER
COPPER CLAD BASEBOARD

Fig. 6B. Tie-point construction.

Output

You will see for yourself as soon as you start testing that the attenuator is smooth-working and stepless, and that true infinite attenuation is at hand. An rf input state (pre-amp) with a noise figure a fraction better than another shows right away on the scale. For example, adjustment of the fixed bias voltages on the two gates of a 3N200 or 3N201 shows right away on the scale as the


COPPER SIDE
SUBMINIATURE SWITCH
2 TIE POINTS FOR AF CIRCUIT
4 TIE POINTS
COPPER
9 V BATTERY
L1
HEP 75
B
E
C
L2
HEP 55 AF OSC.
HEP 55 WITH 3 TIE POINTS RF OSC.
ARCO 404 8-60 TRIMMER
SOLDER

Fig. 7. Side view of the signal generator, 220 MHz.


+9
4.7 K
.01
.001
AF OSC.
HEP 55
.02
4.7 K
+
22K
22K
.02
IK
.05
44 MHz
CRYSTAL
2.2 K
RF OSC.
HEP 55
4-40
pF
L1
12T
2T
2T
.01
200
.01
+
1.5 K
RFC
.01
IK
QUINTUPLER
HEP 75
3-30
150
1-7
L2
.01
.01
+
ANTENNA
PLATE

Fig. 8. Schematic. L1 = 16 turns No. 26 output tap at 2 turns, crystal feedback tap at 4 turns, from cold end. Wound on phenloic form .6 cm O.D. L2 = 6 turns No. 18 bare, air wound, .6 cm O.D., 2.5 cm long between tie points. RFC = about 40 turns No. 40, on phenolic form .3 cm O.D., 1 cm long (not critical).

push-rod is moved in and out and the signal is locked onto the scope. This work you can do right on the bench and at low cost.

There is quite a bit of mechanical work in the unit, depending on just how much "finish" you want it to have. You can also bring a dowel rod for "on and off" use. Do not, under any circumstances, bring out a *conductor*. You *can* do this, but only with an extreme amount of filtering, which is not part of this article. Be sure to set up the baseboard, antenna plate and battery first, and get them working mechanically. With a drawn-out shape like this I generally start with a longer piece of copper-clad than needed, build from one end, and then cut off what is left over. Understandably, once you have made the first one you can always see, after it is done, many ways of improving it. However, someone has to make the first one, and that's generally my job.

Antenna and Field Tests

Out of the tubing, and with a small antenna connected via a one turn link around the quadrupler coil and then to ground, returning L2 for maximum output, this little rig puts out a lot of signal on 220. Especially if you reduce the oscillator emitter resistor! Up to several volts of rf can be obtained in a tuned diode receiver if you push things along, which is around 5 to 10 mW. If you place this generator out in a field several hundred yards or more away, you can then line up your antenna on the car or house, check antenna cables, antenna input alignment, and match or mismatch for lowest noise figure, etc.

Front end alignment should first be done with a relatively broadband i-f strip on 10.7 MHz. Be sure nothing metallic on the generator strip protrudes enough to touch the inner wall of the tubing, or "scratch" will occur in the high gain receiver. A piece of thin fiberglass or other insulating sheet wrapped around the whole generator movable plank is a good precaution.

Once again I include a 220 MHz tuned diode detector, which is an absolute must for frequency multiplication, especially quintupling and such, where the other unwanted harmonics are as little as 20% away from the desired frequency. Figure 9 shows this piece of test equipment in pictorial schematic form. Remember, shape is of considerable importance as you go from VHF into UHF. It is quite easy to make the square trough line out of an old piece of copper clad. Or even a new piece! And this particular one described and shown in Fig. 9 goes very well to over 450 MHz and thus is very nice for the next band also. If you make it just as I've shown it, it will do a good job for you.

Calibration will present some difficulties, so line up some other lads around who are already on these bands and get your calibration that way.

So good luck, friends, more coming – lot's more! Keep reading.


AF
DC
OUTPUT
"PHONO" JACK
ADAPTER
(EXTERNAL)
1.4 cm SPACERS
COPPER-CLAD
COPPER INSIDE
TWO SMALL
LAFAYETTE
.001 CAPS
IN295
DIODE
10 X 10 cm
PANEL
POINTER
KNOB
10.2 cm
5 cm
7.6 cm
INSIDE TEFLON
OF RG-58/U
2.2 pF
POT LOCKING
ASSEMBLY
3 cm
ROTATES
KNURLED NUT
COPPER TUBE
PHONO
JACK
RG-58/U
SOLDER
BRAID
SOLDER SMALL
END PLATE TO
VARIABLE
CAPACITOR
VARIABLE
CAPACITOR,
10 PLATE TOTAL
"PROBABLY" 25 pF
TOTAL
COPPER OR BRASS CENTER STRAP
2.5 cm WIDE, SET VERTICALLY

Fig. 9. Tuned diode detector, 160–460 MHz.

UHF SIGNAL GENERATOR

Jim Kennedy K6MIO

Several requirements were the basis for the design of this signal generator: operation on both 432 mc and 1296 mc, high stability e.g., crystal control, variable rf amplitude, provision for insertion of various types of modulation, and lowest possible cost consistent with satisfactory operation.

I had a 27.005 mc overtone crystal left over from a brief period of disillusionment about CB and, since 27 times 6 is 432 which times 3 is 1296, this seemed a likely place to start.

Fig. 1 shows the final result. The overtone oscillator is voltage regulated and is left operating at all times when the generator is on. The crystal is mounted underneath the chassis to protect it from rapid temperature changes from drafts, etc., further enhancing the stability.

The use of diode multipliers at 432 mc and 1296 mc greatly simplifies developing UHF rf.

Direct coupling the modulation into the cathode of the last vacuum tube multiplier provides a modulation input that will accomodate almost any signal from audio to video, or even pulse.

A four position mode switch on the front panel allows the choice of carrier, no carrier, carrier with 60 cycle modulation and finally carrier with external modulation.

Construction

Building the unit presents no special problems except getting it all under the chassis. The 5 x 9½ x 2¼ chassis doesn't leave much useful



Front view of signal generator.



FIGURE 1

L1—10 turns # 28, 3/8" slug form.
L2—3 turns #28, 3/8" slug form.
L3—10 turns #18, 1/2" dia.
L4—3 turns #18, 1/4" dia.

room to spare, but it does make for a very compact device.

The lengths of the diode multiplier tuned lines were determined primarily by the space available and bear only the slightest relation to the wave lengths involved; hence, it was necessary to pad both lines with additional capacitances in order to resonate them properly.

Both lines were folded from 1/32 inch brass sheet stock. The inner conductors are made from ¼ inch brass tubing. The 432 line is 1" x 1" x 7". The input diode is tapped onto the inner conductor 1¼ inches from the other end. The signal output loop is about 1¼ inches long. The output diode is tapped 2 inches from the loop end of the line.

The tuning capacitor is made by soldering a 10-32 nut over a hole in the middle of the line shell. This provides the threads for the 10-32 screw which actually serves as the capacitor.

Round ½ inch disks are soldered to the bottom of the center of the inner conductor and to the end of the turning screw to provide additional range.

The 1296 line is similar except it is only 3⅜ inches long. The multiplier diode is tapped on the inner conductor ⅝ inches from one end. The signal output loop is about ¾ inches long and is located at the other end of the line. The tuning capacitor is identical to the one used in the 432 line.



Closeup showing the oscillator and vacuum tube multipliers.

The 15K 10 watt resistor in the carrier OFF position limits the no load voltage from exceeding the ratings on the filter capacitors.

Operation

The tune up of the tube stages can be easily accomplished with a grid dipper. The UHF stages should only need to be peaked with a converter and receiver.

Shields on all tubes and a bottom cover on the chassis are important requirements if stray leakage at the signal frequency or lower harmonics is to be eliminated as a possible source of measurement error. These were removed for the photographs but are always used in practice.

For best results it is a good idea to employ a 50 ohm (or 75 ohm as the case may be) pad between the signal generator and the equipment under test. This will insure that the generator will appear as a resistive load as much as possible. This is necessary if the generator is to duplicate the conditions presented to the receiver by a good antenna.

This pad can take many forms. The two easiest ways to make one would be to use sufficient lengths of some lossy coax. At 432 mc higher, 20 or 30 feet of RG-58 (or RG-59) seems to be quite adequate for most applications. The other approach would involve building a conventional resistor pad into a male and female BNC connector soldered back to back. Fig. 2 shows such a pad.

Aside from receiver testing, this device has several other uses to which it can be put. It is also useful as a signal source for antenna tests and it may be used as frequency standard.



FIGURE 2

Fig. 2. 20 db 52 ohm pad. Resistors mounted in BNC connector.



Closeup view showing details of diode multipliers lines.

This last use can be of great value at UHF because of the persistent problem of crystal tolerance versus frequency multiplication. A converter can easily be 40 or 50 kc or more off of the indicated frequency at 1296 mc. This can be quite a problem if you are hunting for a moonbounce signal through a 5 cps filter.

Though not shown on the diagram or in the pictures, it was found that a 50 mmfd variable capacitor connected across the crystal was sufficient to reduce 27.005 mc to the 27.000 . . . mc required to put the generator on 432.00 . . . and 1296.00 . . . mc. It will probably be necessary to retune the oscillator plate circuit for best operation; some loss in output will be encountered but this should not be a serious problem. However, if such operation is contemplated, it might be of some advantage to obtain a 27.002 mc crystal and employ a smaller variable capacitor.

In order to make the frequency standard really something of a standard, a 1 mc calibration oscillator should be employed. Some harmonic of the oscillator (5 mc, 10 mc, etc.) should be zero beated against WWV. The signal generator should then be zero beated against the 27 mc harmonic of the 1 mc calibrator—presto!—a 432-1296 mc frequency standard.

Though there are many refinements which can be made, the unit described has done a yeoman service in all the varied tasks asked of it.

LAB TYPE IF/RF SWEEP GENERATOR USING ICS

Ray Megirian K4DHC

Just about every kit-type sweep generator on the market starts life out at around 3 or 4 MHz and ends up at 200 MHz or so. This always made analysis or display of 456 kHz i-f amplifier response characteristics a tedious step-by-step plotting procedure or required time out to rig up a temporary gimmick to do the job. No more. The sweep generator to be described here will do the job with ease and precision. Even if you do not intend to duplicate the instrument, you may find parts of it useful for other applications.



Fig. 1. Schematic of the MC1648 IC.

The generator covers a frequency range of from 400 kHz to 30 MHz in five bands. It can be operated in the CW mode as well as swept, thus allowing it to be used as an ordinary signal generator. Maximum output is 350 mV p-p across 50Ω. When sweeping, the return trace may be blanked or not, as desired. Two calibrated dials are provided for setting the start and stop frequencies and the maximum sweep width would be the entire band in use. The frequencies covered by the five bands are: 400 to 900 kHz, 850 kHz to 2.3 MHz, 2 to 6 MHz, 5 to 15 MHz and 10 to 30 MHz. Sweep time is variable between 20 ms and 6 seconds per sweep. A step attenuator in conjection with a vernier control provide a maximum attenuation of the output of 120 dB. An input is provided for a post-injection marker system built into the unit. A synchronous ramp with gain control is provided for driving the oscilloscope horizontal sweep. Blanking pulses are also brought out to a connector in case they are needed for synchronizing external equipment.



Fig. 2. Tuning the MC1648 with a single diode (A) and using back-to-back diodes (B).

A New IC

The heart of the generator is a new Motorola IC, the MC1648 emitter-coupled oscillator. It was intended for use in phase-locked loop systems operating in excess of 150 MHz, but may be used in many other applications such as this one. The device provides output of high spectral purity and incorporates an internal agc system which simplifies design of the sweep generator by eliminating the need for external leveling. A buffer amplifier and emitter-follower output are also incorporated on the chip, eliminating the need for external amplifiers. Figure 1 is a schematic of the MC1648 IC. Figure 2 illustrates two methods for tuning the oscillator. The device is packaged in a 14-pin DIP and requires a 5V dc supply. Since it was intended to be used with Motorola MECL III logic, either polarity is permissible. A positive supply is used here, connected to pins 1 and 14 with 7 and 8 grounded.

All the information covered by the data sheet for the MC1648 dealt with operation from 10 MHz up to about 180 MHz. Since I was interested in going as low as 400 kHz, I had to do some experimenting with tank circuits. My best results were obtained with the use of cup cores for the two lowest bands. I also found that ordinary molded iron core rf chokes of the miniature variety did an excellent job the rest of the way. Use of these tiny components made possible a very compact 5-band assembly.

The VCO

In order to facilitate shielding and simplify construction, electronic band switching is employed. Figure 3 is the schematic for the rf portion of the generator. The 2N4391 J-FET has a low 'on' resistance and works very well as a switch. One of these transistors is placed in series with each tank circuit



ALL RESISTORS-1/4W, 5%
L1-28 TURNS NO. 30 AWG ENAMEL.
L2-12 TURNS NO. 28 AWG ENAMEL.
(L1 & L2 MOUNTED IN CUP CORE-See Text)
L3-18 μH MINIATURE MOLDED RFC.
L4-4.7 μH MINIATURE MOLDED RFC.
L5-1.1 μH MINIATURE MOLDED RFC
C1, C2-TYPE 150D TANTALUM-2.2 μF/20V.
R1-BECKMAN 89PR10K 15-T TRIMMER.

*-SELECTED PART-See Text.

Fig. 3. Schematic of the rf assembly using dc band switching.



Completed rf assembly ready for mounting in the cabinet. A plastic version of the 2N4391 was used with a considerable savings in parts cost.



Fig. 5. Pictorial demonstration of ramp generation.

and can be turned on by application of a positive voltage at the gate. This allows the use of a strictly dc-operated remote switching arrangement. The entire assembly is built on a 2 x 3 in. pc board and mounted in a Pomona Model 3306 enclosure with a Model 3328 bottom mounting plate.

A BA163 tuning diode by ITT is used to sweep the oscillator. Although it is intended for bc band use, it performs admirably at these higher frequencies and its high capacitance ratio allows wide sweep excursions. If you are planning to use this oscillator for VHF applications, a more suitable diode would be in order. According to the data sheet on the MC1648, typical maximum output frequency is 225 MHz.

The vernier attenautor is a 100Ω RV6 style potentiometer mounted inside the enclosure. A coupling and extension shaft are used to bring the control out to the front panel. The value of the resistor at the bottom end of the pot will have to be selected so that a range of 20 dB is provided with full swing of the control. Since end resistance varies from one control to another, an exact value will have to be arrived at experimentally.

The output from the VCO is a square wave. If sine wave output is desired, the agc characteristic may be modified by introducing resistance between pin 5 and ground. The small trimmer incorporated on the board is used for this purpose. It was my experience, however, that this may introduce instability with some MC1648s. Although the trimmer was left in, the one in my unit is turned to maximum resistance where it has no effect and left there. It would do no harm to leave it out altogether since no other changes would be needed.

If any readers are contemplating exact duplication of this generator, you will find the cup cores I used are no longer available. These were Ferrox-cube part number 332P133B4-3C and are obsolete. I had a large number of these on hand left over from another project and saw no sense in buying more. I am sure some of the presently available cup cores will make excellent substitutes. Those used here are about 3/8 in. in diameter and are ungapped. You may have to experiment with the number of turns in the coil to obtain the coverage you require. One handy trick you can pull with a cup core is to rotate the slots in each half so that fractional turns are produced when the coil wires are brought out separately through the



Fig. 4. (A) Foil side of rf pc board. (B) Location of parts on component side.



Fig. 6. Schematic of the ramp generator circuit.

two spaced holes. Exerting pressure on the core by means of the mounting screw will also shift the frequency and is almost like having a slug to tune. Increasing pressure seems to raise the frequency. The rf chokes used for the higher bands may also vary slightly from piece to piece and several may have to be tried to get the desired coverage. There isn't much we can do to alter the frequency where the chokes are used. Of course, slug-tuned coils may be used if the pc layout is modified. I do not recommend their use on the two lowest bands, however, since my results were rather unsatisfactory with this sort of tank circuit.

One final point would be in order before leaving the VCO. Note that the 10 KΩ resistor going to the tuning diode, the 2.2 μF rf output capacitor and each of the 12 KΩ resistors going to the transistor gates are not mounted on the board. One end of each has a hole provided on the board and then the component itself is used to make the connection to its final destination. This saves board space and eliminates separate wires. The small resistor at the bottom of the vernier attenuator is similarly mounted between the board and the bottom lug on the control. These points are more clearly seen in the photo. Also note that the cup cores are fastened directly to the board by means of 1-72 screws into threaded holes.

The Ramp Generator

In contrast with kit-type sweep generators that use the 60 Hz line for sweeping the oscillator, laboratory instruments have internal circuitry designed for this purpose. In our case, as with most sweep generators, a voltage ramp is used to control the oscillator during the sweep period. The circuitry has been arranged so that we can adjust the starting point (dc level) of the ramp independently of the stopping point. This simply means that we can set the frequency at which the sweep starts as well as the frequency at which it stops. We can also control, over a fairly wide range, the time it takes for a complete sweep. In this case, the sweep time is continuously adjustable between 20 ms and 6 seconds per sweep.

To get a better idea of how the ramp generator produces the results we've described above, let's look at Fig. 4. Note that a negative-going linear ramp (start) is combined with a positive-going linear ramp (stop) to produce the resultant ramp being applied to the varactor diode. If either input ramp is zero, the resultant will be the same as the single ramp since adding zero to anything will not change its value. Naturally, if both are zero, the output will be zero and the oscillator output frequency will be constant during the sweep period. The same is true whenever both ramps are of equal amplitude, except that the output will be a steady voltage other than zero. Also note that the resultant ramp could have a negative slope if the 'stop' input is lower than the 'start' input, and the oscillator would obviously sweep down in frequency rather than up.



The ramp and blanking generator pc assembly. The leads going to external points will go in the holes visible on the board.

The schematic for the ramp generator is shown in Fig. 6. Operational amplifiers A1 and A2 form a triangle wave generator with A1 acting as a threshold detector and A2 as an integrator. One half of the triangle (negative-going) represents the sweep period while the other half represents the retrace time. Since a square wave is generated at the output of A1, we have a convenient source of blanking voltage built right in. This signal is positive during the sweep period and is connected to the band switch when Swept 1 (blanked retrace) operation is selected. During retrace the square wave drops to zero and actually disconnects the tank circuit until the next sweep starts. An emitter-follower, Q3, buffers the square wave output for external use.

The output of inverting amplifier A3 is a positive-going ramp during the sweep period and is used for both the 'stop' signal and horizontal sweep for the oscilloscope. Since an additional inversion takes place in the output of A4, the negative-going ramp at this point is used as the 'start' signal. These two ramps are applied across front panel controls which have 6:1 reduction drives and are fitted with dials calibrated in frequency for the five operating bands. The outputs from these two pots are fed to summing amplifier Q1, where the output will be the resultant ramp we discussed above. Because the output Q1 is in the negative region (PNP transistor), a second common-base (NPN) amplifier is used to shift the output back to where it will always be positive.

The ramp and blanking generator is constructed on a pc board 2.6 x 4.1 in. in size. For convenience, all the trimmer resistors were mounted along one edge. As seen in the photo, this board was mounted by means of two small brackets in a vertical position with the trimmers facing up. To simplify pattern layout, unused pins 1, 5 and 8 on each of the four 741 opamps were clipped off right at the case. Color-coded wires were connected to all necessary points on the board before it was mounted, with the leads made long enough to reach their destinations. For those interested in building this unit, a detailed procedure for setting up the ramp generator will be given later.


TO SWEEP TIME POT
'STOP' RAMP OUT
'START' RAMP OUT
TO GAIN CONTROL (HORIZ SWEEP)
SUMMING JUNCTION FROM 'STOP' & 'START' POTS
-15V
INTERNAL BLANKING
+15V
EXTERNAL BLANKING
R1 1M
R2 10K
R3 10K
R4 10K
R5 10K
R6 10K
R7 10K
IN914
(NPN)C
(PNP)
TP1
TP2
TP3
TP4
A1
A2
A3
A4

Fig. 7 (A) Foil side of ramp generator board. (B) location of parts on component side.

The Mixer/Amplifier

In order to provide a means for displaying frequency markers, a mixer and amplifier circuit was built into the sweep generator. The schematic for this circuit is shown in Fig. 6. A marker generator was not included inside the sweeper because other rf generators were available for use as markers and the added expense seemed unnecessary. Because the mixer board was to be installed inside a shielded box, dc gain control was resorted to as with the band switching discussed earlier. A 2N4391 is used as a variable resistor to control the signal input to the amplifier stage. This in turn controls the size of the marker being displayed on the curve. A 2N3819 FET is used in a simple mixer circuit which worked the best of several tried. Incidentally, the PNP and NPN transistors used here and on the ramp generator board are unknown surplus silicon units.

The pc board for the mixer is 1.5 x 2.9 in. and is mounted in a Bud CU-124 die-cast aluminum box. Note that here again some of the components are mounted between the board and their external connectors. These include both the 10 pF and 100 pF input capacitors to the 2N3819 and the 10 KΩ resistor going to the gate of the 2N4391.

The Power Supply

Figure 7 is a schematic for the power supply. Voltage requirements for the sweep generator are +15V, −15V and +5V dc. The current drawn by any of the above circuits runs no more than 30 or 40 mA maximum,


+15
RF IN
MARKER IN
10 pF DISK
100K
1000 pF DISK
470Ω
Q1 2N3819
4.7K
.005 DISK
10K
.005 DISK
.01 DISK
100K
Q2 2N4391
10K
10K
TO GAIN CONTROL
Q3
6.8K
1K
2.2 µF-20V TANT. TYPE 150D
.005 DISK
.001 DISK
100K
100 pF DISK
DEMOD. IN
VERT.
ALL RESISTORS-1/4W, 5%.
Q3-SILICON NPN
2N3819 BOTTOM
2N4391 BOTTOM

Fig. 8. Post-injection marker circuit with dc gain control of marker size.



Completed mixer/amplifier board mounted in the die-cast housing.


TO
GAIN
CONTROL
10K
2.2 µF/20V TANT.
MARKER
IN
1000 pF
10 pF
RF IN
DEMOD. IN
10K
470Ω
10K
G
S
10K
E
1K
.001
D
B
C
100K
100 pF
100K
.006
4.7K
6.8K
.005
+15
VERTICAL

Fig. .9. (A) Foil side of mixer/amplifier pc board. (B) Location of parts on component side.



The power supply pc assembly.


T1
15V
RMS
VE18
C1
1000
µF
25V
2
A1
3
4
5
6
1
10Ω
+15
4.3K
R1
1K
TRIM
.05
DISK
1.5K
NEON
PILOT
10Ω
2
A2
3
5
6
1
+5
R2
1K
TRIM
.05
DISK
1.5K
PART OF
SWEEP TIME
CONTROL
1/4A
115 VAC
60 Hz
15V
RMS
VE18
C2
1000 µF
25V
.05
DISK
-15
1.5K
R3
1K
TRIM
4.3K
2
5
A3
6
4
1
3
10Ω
R1, R2, R3-WESCOM RV-1K
C1, C2-WESCOM U25-1000
A1, A2, A3-MOTOROLA MFC 6030
ALL RESISTORS-1/4W, 5%
T1-See Text
8
6
4
1
2
3
MFC 6030
TOP VIEW

Fig. 10. (A) Foil side of power supply pc board. (B) location of parts on component side.

making the use of small IC voltage regulators ideal. Motorola MFC6030 (plastic) regulators are used in each supply and are overload protected against accidental short circuit. Varo type VE18 molded bridge rectifiers, together with 1000 µF filter capacitors, supply the dc input to the regulators. The +15V and +5V regulators are both fed from the same source. The power transformer was a surplus unit with a 30V CT secondary. The center tap was uncovered and the two leads separated so as to provide two independent 15V windings. A small trimmer is provided in each supply for voltage adjustment.

The pc board for the power supply is 2.6 x 4.1 in. All components but the transformer are mounted on the board. The transformer is mounted directly on the chassis. Relative placement of the various components making up the complete generator can be seen quite clearly in the photo.

Control Circuits

Figure 8 is the wiring diagram for the control circuitry. Note that for CW operation of the generator, a dc voltage is applied to the varactor by way of the Start pot. In order for the dial calibration to be valid in either mode, the dc level applied to the control must be exactly the same as the peak amplitude of the ramp during swept operation. As will be explained in the set-up procedure, the ramp will vary from a starting point of approximately +1.4V and peak at +12V. Resistor R1 in series with the +15V line is selected for a +12V level at the high end of the pot. R2 is selected for a level of +1.4V at the low end. The reason for the offset of 1.4V at the low end is because the pin to which the tuning diode is connected at the MC1648, sits at this level. The source of this bias is the drop developed across two forward-biased junctions within the IC and not from any external source. Once these dc levels have been set for CW with the fixed resistors, the ramp can be made to match by means of the trimmers in the ramp generator circuit.

The rest of the control circuitry is quite straightforward. In position 2 (Swept 1) of the mode switch, positive pulses from the ramp generator are fed to the band switch during the sweep period. When retrace occurs, the pulse drops to zero and the oscillator shuts off until the next sweep starts. In the CW and Swept 2 positions of the mode switch, a steady +15V is applied to the band switch and the oscillator runs continuously.

The final function performed by the mode switch is to route the dc for CW or the ramp for swept operation to the tuning diode. The two fixed resistors are mounted point-to-point behind the panel since all points are readily accessible within every short distances. The fixed resistors associated with the marker gain control are also mounted the same way behind the panel. The switches are ordinary rotary types and the potentiometers are all ordinary carbon controls. The Start and Stop controls as well as all gain controls have linear tapers. The Sweep Time pot is an audio taper type with built-in switch for ac power.

Setting Up the Ramp Generator

For best results, a calibrated dc scope is required to properly adjust the ramp generator. Test points have been provided on the pc board and short pieces of bare wire connected to each of these points make excellent tie points for the scope probe. The


A
15V RMS IN
15V RMS IN
VE18
1000 µF 25V
+
MFC 6030
.05
10Ω
1K
4.3K
1.5K
B
+15V OUT
−15V OUT

Fig. 11. (A) Foil side of power supply PC board. (B) Location of parts on component side.


+15
+15
R1 2.4K
S1A
S1B
S1D
S1E
TO OUTPUT OF RAMP GEN. (TP4)
TO INTERNAL BLANKING
TO "A" FIG. 5
TO "B" FIG. 5
TO VARACTER
10K CW/START
+15
12K
BAND SWITCH
S1C
R2 1.2K
MARKER GAIN
50K
TO MIXER ASSEMBLY
51K
TO RF ASSEMBLY
S1-MODE SWITCH
POS.
FUNCTION
1 CW
2 SWEPT 1 (BLANKING)
3 SWEPT 2 (NO BLANKING)
* SELECTED-See Text

Fig.12 Control circuit wiring schematic.

circuit may be aligned either before or after installation. The Start, Stop and Sweep Time pots can be connected at the ends of their respective leads if the unit is checked outside the cabinet.

Set all seven trimmers to mid-range. Connect the scope to TP1 and adjust the horizontal for a full sweep of 20 ms. Set the Sweep Time control to minimum resistance and apply power. Some sort of triangular wave should be displayed. Adjust R1 for a 3V p-p amplitude of the waveform. Turn R2 cw until the negative-going portion of the triangle is 20 ms long. Since R1 and R2 interact, you will have to stop occasionally and reset R1 for proper amplitude. Once the ramp is set at 20 ms with the Sweep Time pot at minimum, the slow speed end will automatically be about 5 or 6 seconds with a 1 MΩ pot.

Transfer the scope probe to TP2 where a positive-going ramp should be seen. Set the starting point of the ramp to zero volts by means of R3. Amplitude of this ramp must be 10V. If it is not, go back and adjust R1 slightly until it is. If necessary, reset R2 for 20 ms trace length. As soon as a 10V, 20 ms, zero-based, positive-going ramp has been achieved at TP2, go on to TP3.

At TP3 there should be a negative-going ramp. Once again we require a zero base line or starting point. Adjust R5 to accomplish this. Amplitude should once again be 10V and is controlled by R4. Once you have a 10V, zero-based, negative-going ramp, move on to TP4.

Connect the probe to TP4 and set the Stop control to full cw. The Start pot should be at minimum setting. A positive-going ramp should be present at TP4. By means of trimmer R7, move the ramp up or down until the starting point is approximately +1.4V. Ordinarily the ramp will not go below zero but will flatten out as the positioning control is adjusted. This is due to clipping in the output amplifier. If the ramp generator is going to be used with another type of VCO, the ramp can be set to exactly zero if desired. In our case we can't as explained previously.

Because a substantial amount of capacitance change occurs in the tuning diode up to 12V, the final ramp amplitude is set to 12V by means of R6. Because R6 stretches the signal in a negative direction, R7 will have to be used to reset the base line at 1.4V. Other than for checking tracking between the CW and swept modes, this completes the alignment procedure for the ramp generator.

When the generator is finished, you can check the tracking by observing actual signals at the input to the VCO. Connect the scope probe to the feedthrough capacitor on the VCO assembly that goes to the tuning diode and set the Start control to maximum. Switch rapidly between the CW and Swept 1 positions of the mode switch. The CW input will be a straight line sitting at +12V while the swept input will be a ramp peaking at +12V. Next, turn the Start control to minimum and again compare levels. If the Stop control is also at minimum, both signals will be straight lines at +1.4V. If there is any substantial difference between the two modes, use R6 and R7 on the generator board to make the ramp agree with the dc levels. That completes all phases of the ramp set-up procedure.



This bird's eye view of the interior shows the location of all major assemblies.

Construction

The cabinet used here is one manufactured by Sorensen Electronics in their Mod-U-Line series. These are the most reasonably priced instrument enclosures I've come across so far and I've used them for several projects. This one is a Model MCH-5129 with a CP-129 chassis plate. Dimensions are: 5¼ in. high by 12 in. wide by 9 in. deep.

The 5-step attenuator was picked up surplus from Fertik's Electronics for about $10. It is well made and designed for 50Ω systems operating up to 1 GHz. It has an integral female BNC output connector on the front face along with four threaded mounting holes for ease of installation. The input connector is a BNC male at the end of a short piece of coax.

All rf assemblies are interconnected inside the cabinet by means of coax cables. This is clearly evident in the photo.

The Start and Stop pots were mounted on brackets behind the front panel so that Jackson Brothers type 4511/DAF reduction drives could be installed for easier tuning. The two circular dials are slightly under 2 in. in diameter and were cut from sheet plastic. While operating in the CW mode, one of these was calibrated in pencil to provide a pattern for the finished product. A master was laid out using Rubylith® film and rub-on numbers. A negative of this was then made using 3M reversing film. From the negative a finished set of dials was printed on aluminum material of the presensitized variety. These were cut out and stuck to the plastic by means of their own pressure-sensitive adhesive backing. The nameplate was made from the same material. The two index pointers are clear plastic with hairlines scored on the inside surface. They are mounted on spacers directly over each dial. All remaining labeling was done with tub-on lettering.

Vendor Addresses:

Fertik's Electronics, 9th & Tioga Sts., Philadelphia PA 19140.

Sorensen Electronics Co., Inc., 418 Queens Lane, San Jose CA 95112.

Wescom, P.O. Box 2436, El Cajon CA 92021.

The finished sweep generator makes a professional appearance.

100 KHZ THIN-LINE PULSE GENERATOR

James Ashe W2DXH

Ordinary 100-kHz frequency standards are usually audible up to a few tens of megahertz. A good one might be usable at 50 MHz. The circuit described here uses a dual NAND gate to generate a 100 kHz signal whose harmonics are usable to 432 MHz or higher. And it can be built without benefit of special instruments and knowledge.

The thin line pulse

One rather surprising result of higher mathematics is that all repetitive signals are composed of harmonically related sine and cosine waves. For example, the familiar square wave is composed of a fundamental frequency, which sets its basic repetition rate, and of odd harmonics only of its fundamental, which contribute to its square corners. If the harmonics' amplitude or phase relationship is upset, the square wave is distorted. This feature makes the square wave very useful for amplifier testing, but its harmonic content is not very good for frequency standard applications.

Now suppose that we start adding up signals of F, 2F, 3F, and so on, phased in so that they all reinforce each other once per cycle. Let's say thay are all the same amplitude. What would we get? See **Fig. 1A.**

The five equal amplitude sine waves peak simultaneously at the beginning of the fundamental's cycle. Everywhere else, until near the end of the cycle, they are more or less out of phase. Trying to see what will happen, we try adding the first two frequencies. **Fig. 1B,** the result, might suggest something to a mathematician.



(A)

(B)

Fig. 1. Five sine waves (A) and the waveform as a result of point-by-point addition (B).

As the number of frequencies is increased, their amplitudes tend to average to zero everywhere except at the beginning of the cycle. Here, they all add up to a short, sharp pulse. It follows that a short, repetitive, one-sided pulse should contain odd and even multiples of the fundamental frequency.

An ideal thin line pulse has infinite frequency content.* No real signal could meet



External view of the 100 Hz thin-line generator.



Fig. 2. Real circuit output as seen by a Tektronix 545A oscilloscope. A faster scope shows shorter rise-time and sharper corners.

this spec, but a fast digital IC can produce a very workable approximation. Fig. 2 shows a Tektronix 545A view of the generator output and tests with other scopes indicate the real pulse has better rise time and sharper corners than shown here.

If this pulse is viewed on a low-performance service variety scope, its appearance will be greatly changed. There will be an apparent loss in amplitude, since the pulse occurs and terminates before the slow circuitry can properly respond. The apparent duration is increased, also because of the slower viewing circuitry. And the fast pulse may excite circuit resonances, so that the thin line pulse appears as a damped oscillation. But these problems do not interfere with constructing the generator, because the very simple NAND gate circuitry contains no critical elements or adjustments.

How it works

There are four circuit sections, shown in Fig. 3. A 100-kHz crystal-stabilized oscillator sets the basic frequency, and a dual NAND gate circuit converts the oscillator output to a thin line pulse. A 1-Hz astable generates the output marking signal. A 6 volt dc power source is provided by a voltage doubler zener-regulated supply.

Multivibrator oscillators are not ordinarily very stable frequency sources. But if the oscillator is designed to run slightly below required frequency, and an appropriate crystal is connected between transistor base terminals, oscillations are stabilized at the crystal frequency.

The crystal does not change the multivibrator's style of operation. It synchronizes the astable to its own frequency, by triggering the OFF transistor into conduction shortly before normal RC turn-on. The output is a squarish wave with good fall time, but a long rise time as shown in **Fig. 4A.**

In passing through the first NAND gate the pulse is squared up and becomes slightly unsymmetrical. See **Fig. 4B.** A differentiating network, C7 and R11, converts the square wave into the pulses shown in **Fig. 4C.** These pulses, applied to the second NAND gate, reappear as the thin line pulses shown in **Fig. 4D.**

Since one CW signal sounds just like another and there may be several in the vicinity of a check point, a marker feature is required. This is provided by the 1-Hz astable, which paralyzes the second NAND gate part of the time. Its base bias resistors are unequal, giving a distinctive duty cycle to the output signal. A switch disables the astable if a continuous signal is required. **Fig. 5** shows the output when the second astable is operating: the output is locked in the up condition during half of each 1-Hz astable cycle.



Fig. 4. Signals at four critical points in the generator, as displayed on a Tektronix 545A oscilloscope. They are shown in time coincidence.

Sometimes an astable oscillator will refuse to start oscillating when it is turned on. It does not start because both transistors are in saturation. This reduces loop gain so that available noise cannot be amplified around the loop. It would never start without some strong, outside interference.

A pair of diodes, D1 and D2, provide a reliable remedy. The diodes are arranged so that base bias must come from whichever collector is at the higher voltage. If both transistors are in saturation, their collectors are at perhaps 1 volt, which cannot provide enough base current to keep the transistors in saturation. This contradictory situation does not arise in the real circuit, which starts reliably.

Additional diodes, D5 through D8, appear in the base circuit of the 1-Hz astable. These are protective diodes. The collector swing at turnoff of about 5 volts is conveyed powerfully to the opposite base through the large coupling capacitors C5 and C6. The reverse B-E breakdown voltage of these transistors is not known, so the diodes are provided to prevent the turnoff voltage exceeding 2 volts or so.

DC power for the Generator circuitry comes from a voltage doubler supply based on a low-current filament transformer. Its design is conventional, but a large capacitor, C12, is provided across its output to mini-



NOTES
R3, R5 • COARSE TUNING RESISTORS (TO BE SELECTED DURING TUNE-UP)
D9, D10 • SILICON, 25 PIV MIN.
C1, C2 & R4, R6 • MATCHING COMPONENTS

Fig. 3. Schematic of the 100 Hz thin-line generator.



Fig. 5. The second NAND gate locks in its up position part of the time to produce an intermittent output.

mize noise on the supply line. The supply could be replaced with some batteries, shunted by a 50 μF or larger capacitor to absorb transients. The original breadboard ran very well, powered by four flashlight batteries.

Construction

The generator is built in a Premier #PMC 1008 3x5x7 inch heavy aluminum box. Its top cover was refinished in light green enamel, and four ⅜ inch grommets in the bottom piece serve as protective feet.

Inside the box, the 6.3-volt transformer and cheater cord connector are mounted on the left-hand wall. A pilot lamp, fuse, and two switches are mounted on the horizontal panel, at the extreme left. This leaves just enough open space for the two circuit boards which occupy most of the box. Two banana jack output connectors are placed on the right-hand side, just below the panel.

The circuit boards are cut to 4½ x 5 inches, from Vector 3⁄32 inch pattern A stock and mounted parallel to the panel. The upper board is spaced an inch from the panel, and carries both astable oscillator circuits. The other board is mounted one half inch below, and carries the digital IC and the power supply circuitry. Assembled, the two boards make a sandwich with wiring sides together.

Both boards are mounted on the same four centers. These are through the second hole diagonally inward from each corner. The 1 inch 6-32 internally threaded spacers are modified by adding a short length of 6-32 threaded shaft to one end of each, simplifying assembly.

Component assembly on the boards is largely a matter of plugging in Vector T9.4 lugs. The finished product looks much better if some thought is given to facing the lugs in one of two directions. Mounting and transistor holes should be drilled and reamed to size before installing lugs.

The general arrangement puts all wiring on one side of the board and practically all components on the other side. This approach seems a little inflexible but is straightforward and looks good.

Possible board orientation problems may be overcome by working out a handling and wiring procedure that doesn't require constant reference to actual components. A good approach assumes that the board is only turned over an imaginary hinge at its bottom edge, so that top down when one side is up becomes bottom up when the other side is down. This preserves left-right relationships. Another useful convention is that all supply wiring goes to left-hand end of components.

Wiring is carried out one network (plus supply lines; ground lines; interstage lines, etc.) at a time, with prearranged color coding. Bare wire goes for short runs and where there is no chance of a short. Solder each lug when convenient. #22 solid wire fits the T9.4 lugs well, but flexible stranded wire is used for the four lines from one board to the other.

Transistors precede other components into the board, because they are convenient position markers. They are placed in their mounting holes in the board from the component side, and their leads brought to the T9.4 lugs. Then the other components are mounted on the boards. Diode and electrolytic capacitor mounting polarity should be double checked. The T9.4 lugs may need a little bending before they will take a good grip on the components, but no component soldering is done until everything is installed.



Inside the assembled thin-line generator showing the component side of the power supply and IC board.

Trimmer capacitor C3 is mounted on its tabs just under the top panel. Then a small screwdriver access hole is drilled over it in the panel, before painting, for vernier frequency adjustment after final assembly.

Certain components are matched before installation. An ohmmeter and a capacitor checker will do a satisfactory job of selecting C1 and C2, and R4 and R6, for equal values. These components are chosen alike for best symmetry of the 100-kHz oscillator operation. It might be good planning to leave these components unsoldered until tuning is completed, but everything else can be soldered to the board at this point. Note that the R3 and R5 sites do not get resistors until later.

Two optional capacitor sites are included. These are for C4, an additional and probably unnecessary padder across the crystal; and C7A, which can be added to increase the width of the thin line pulse.

Apparently, the digital IC comes in a specially designed package for testing before use. To mount the IC, solder a ⅜ inch piece of #22 wire in each of the T9.4 lugs carrying supply and signal voltages to the IC. Place the IC between the two rows of lugs, bend the wires against the proper terminals, and solder. No other mounting is required.

The original breadboard showed a lot of transient noise in its supply circuit. This originated from the IC, which was trying to get big chunks of current to manufacture pulses. Since the IC cannot deliver frequencies not available from the supply lines, very careful bypassing is indicated.

High-frequency bypassing consists of C9, a .01μF disc ceramic capacitor across the IC supply terminals on the wiring side of the board, and C10, a 100 picofarad capacitor soldered directly between supply terminals on the IC. The capacitor leads are provided with spaghetti insulation and placed for minimum open space between the capacitor leads and the IC's supply leads.

Testing before final assembly is very easy, because the odd appearing board layouts go together giving a structure that opens out like a book. The hinge is the four leads between boards. Leave transformer leads long, so that the circuit may be tested well free of its cabinet.

The upper half of the Premier box is prepared by a powerful cleaner which removes its original paint. After thorough removal of the cleaner, the metal is roughened with wet sandpaper, rinsed in vinegar solution and then clear water, leaving a very good surface that does not require priming for excellent paint adhesion. Watch out for greasy fingerprints.

Rustoleum #868 Green applied from a convenient spray can gives a fine finish. Follow instructions on the can. After drying, the fresh, clean enamel will take waterproof India ink, applied with a Leroy drafting pen. When the ink is thoroughly dry, a final coat of Rustoleum #717 Clear finishes the job. The enamel is soft at first, but hardens into a coat durable in normal lab use.



View of the component side of the astable oscillators board.


TOP PANEL
COMPONENT SIDE OF ASTABLE BOARD
1"
3/32"
1/2"
3/32"
THREADED STUD INSIDE
COMPONENT SIDE OF SUPPLY & IC BOARD

Fig. 6. Mounting dimensions and spacer assembly diagram.

Table of special parts

Crystal: 100 kHz parallel resonant 32 pF. shunt capacitance normally designed quartz crystal.

The following parts were obtained from Solid State Sales, P. O. Box 74, Somerville, Mass. 02143.

- T1 & T2: 2N2060 type dual NPN transistor
- D1, D2, D3, D4: fast point-contact Germanium diodes coded 1N59
- D5, D6, D7, D8: fast point-contact Silicon diodes marked S284GM
- G1: surplus digital integrated circuit Solid State Sales type G1. (comes with data sheet)

Tuning up

The generator should be zeroed to frequency before installation in its case. This is a two-step process. First, the 100-kHz astable base resistances are adjusted by choosing resistors for R3 and R5 to bring the oscillator frequency within trimmer range of 100 kHz, perhaps a few hundred cycles high at 15 MHz. Then the trimming capacitor brings the frequency to accurate coincidence with WWV.

To roughly zero the generator, set the trimmer capacitor, C3, at minimum capacitance. Identify WWV on a short-wave receiver, and tune around a bit to familiarize yourself with what's happening in the vicinity. It would be nice if things are fairly quiet.

Then put 4.7k resistors into the astable board at the R3 and R5 sites, turn on the generator, and look around for the signal. Depending upon actual values of C1 and C2, the signal may be on either side of WWV but is likely to be on the high side. If so, try again with resistors one size larger, which will lower the frequency. You should shortly find resistors that bring the frequency near enough to WWV for final zeroing with the capacitor. Verify tuning range on both sides of WWV.

Correct values for R3 and R5 may be approximated very quickly if a good triggered scope is available. Try selecting resistors for a period of 11.4 microseconds with the crystal removed.

Using the thin line generator

A breadboard test showed that (as might have been expected) there should be some way to distinguish generator signals from other CW signals. The continuous/intermittent feature provides the marking, and once the correct signal is located the generator can be switched to "continuous" for accurate work.

At low frequencies, the generator output and behavior resembles a conventional 100-kHz standard. The signal simply is not as strong. A greater difference appears at higher frequencies: the original model yields an audible beat note at 80-MHz from a diode mixer through an inexpensive audio amplifier. And another test shows a usable signal at 432 MHz: the 4,320th harmonic.

Some connection to the receiver or other detector is required. This is a natural consequence of a circuit design that puts the signal where it belongs, rather than spraying it all over the lab. A few picofarads coupling capacitance is sufficient at all frequencies.

Perhaps this circuit can be used for purposes other than a frequency standard. Its moderate amplitude but wideband output should be ideal for detecting changes in receiver sensitivity over a broad tuning range. In fact, with a little decoupling of the input leads and provision of a coax output connector the generator should do well as a stable, reliable small-signal source. A piece of adjustable waveguide-below-cutoff would make an excellent attenuator for work not requiring exact measurements. Another thought that occurs is possible further development by provision of some arrangement for detecting which harmonic is actually being heard.

Chapter VI

Crystal Calibrators

ALL BAND BAND-EDGE MARKER

Charles Berner WA2HRZ

This calibrator is complete with its own ac supply, eliminating the need for taking power from the receiver. If ac outlets are at a premium at your shack, the on-off switch and the line plug can be eliminated and the ac line connected across the receivers ac input so that the calibrator comes on whenever the receiver is turned on. A high density selenium rectifier was used and this contributes greatly to the compactness of the unit. The whole thing runs very cool and even after 24 hours operation, still isn't hot.

Wiring isn't too critical, but keep all leads short and direct. Using an octal socket for a xtal holder lets you use the unused pins as tiepoints and is recommended.

A Petersen type Z-2 xtal was used because it has a tolerance of .002%. This is one reason why no provision is made for "zeroing" the calibrator against a standard. The other is that there isn't any such standard as WWV for use. However, if this provision is desired, C1, the 56 mmfd capacitor, connected to pin 1 of the 6BH6 thru the 18K resistor, can be made variable. Also, if band edge markers are wanted for 50 mc and up, a 5 mc xtal may be substituted when this function is wanted and C1 made variable for "zeroing" against WWV.



T1–PWR.XFMR. PR: 115 VAC, 60 cps; SEC: 125V. 15 MA.; 6.3v, 0.6A (STANCOR-PS-8415)



This gadget can also be used as a xtal activity checker by simply replacing the marker xtal with the xtal to be tested. Tuning your receiver should get you a strong signal at the xtal's fundamental if it is OK.

Table 1:

Band	Harmonic 3.5 mc	100 kc	Marker Frequency
80 meters	1	35	3.5 mc
40 "	2	70	7.0 mc
20 "	4	140	14.0 mc
15 "	6	210	21.0 mc
10 "	8	280	28.0 mc
6 "	15	525	52.5 mc
2 "	42	1470	147.0 mc
1¼ "	63	2205	220.5 mc
1¼ "	64	2240	224.0 mc

THE MULTICAL

E. R. Davisson K9VXL

What is the "Multical"? As the name implies, "multi" would suggest several uses, and "cal" might infer a calibrator of some sort.

Well, that's right, but there is slightly more significance to the name. "Multi" is also a short form term used to describe flip-flop circuits known as multivibrators.

By combining the basic characteristics of a free-running multivibrator (astable) with crystal control, you have a simple, stable, virtually-insensitive-to-temperature-changes, crystal calibrator for that receiver you have been wondering about.

The circuit uses no inductors and depends upon the crystal for the proper feedback for oscillations. Temperature stability is partially due to the absence of capacitors.

Transistor stage Q_2 operates with unity gain, whereas transistor Q_1 operates at considerably more gain. Both stages are operating as feedback amplifiers. The harmonic generator diode D_1 is a 1N128. Any general purpose diode may be used.

By using the multivibrator circuit, the waveform obtained is comparatively rich in harmonics and could be used without any further refinements. However, to insure useful harmonics through 30 MHz starting from a 100 kHz crystal, a harmonic generator consisting of R_6 and D_1 shown in **Fig. 1** was added. The capacitors C_1 and C_2 are used strictly for coupling and have no effect on frequency stability.

Crystals from 100 kHz up to 1 MHz may be used in the Multical with no changes. The circuit will oscillate from voltages as low as 2 volts and can be operated safely from voltages as high as 20 volts. This wide range of voltage operation allows the source to be obtained from virtually any place.

Output from the calibrator may be fed directly into the receiver's input, or may be coupled to a short whip antenna. With a whip antenna, close coupling to the receiver's input



Fig. 1. Schematic of the Multical.



Fig. 2. Suggested printed circuit board layout for the Multical. A gives the copper side, B the component side. A board for the Multical is available for $1 from the Harris Company, 56 E. Main Street, Torrington, Conn.

may be required at higher frequencies. (Especially at the lower voltage levels.)

For the more ambitious builders, **Fig. 2** shows the printed circuit board layout for the Multical. Due to its small physical size (1" x 2"), room can probably be found even in the most compact of receivers. **Fig. 2A** shows the foil side, and **2B** shows the parts placement.

So the next time you wonder about the accuracy of your receiver calibration, give this simple circuit a try and you'll know for sure.

100 KHZ MARKER GENERATOR

W. W. Davey W7CJB

This useful piece of equipment generates usable harmonics from 100 kHz to 225 MHz. It is completely self contained and portable which makes it convenient not only to use in the ham shack, but also in the mobile unit or at a field day location. Its use lies mainly in accurately spotting band edges and 100 kHz calibration points throughout the ham bands.

Most modern day home receivers are equipped with calibrators, but these calibrators are of little use when needed to spot frequencies on VHF and UHF converters or portable equipment.

The generator is constructed in a 2¼ x 4¾ x 1½ inch handi-box. The parts are mounted on a vector board, and the entire unit is powered by one #216 nine volt battery or its equivalent.

Hints on construction First obtain some vector board. The piece I used was cut from the board supplied in a "GE experimenters aid hobbyist kit." The board must be cut to size before construction and will measure 3½ x 2 inches. This will allow room for the 9 volt battery in the end of the handi-box. Make sure the newly cut vector board will fit inside the handi-box before you start mounting parts. It might save a lot of trimming at a later date.

The parts layout is not critical. Components may be arranged as shown in the photo or in any other arrangement suitable to the components you may be using. I used sockets for the transistors, as I wanted to be able to experiment to see which transistors from my junk box would give the most output in the VHF and UHF bands. I ended up using the 2N404 for the oscillator and a 2N384 in the multiplier stage. I also found that Japanese 2SA83 transistors which had been removed from the *if* stages of a junked transistor radio, would work equally well in both sockets.



All components are mounted on the top of the Vector board with the exception of C4 and C5. For the most part, wiring can be completed with existing leads on components. The push-in terminals furnished with the GE experimenters kit were used for the battery connections, antenna connection and for mounting the crystal socket. The circuit board can be mounted to the handi-box with three 11/16 inch bushings. This leaves room for a slide switch to be mounted on the cover of the handi-box. Two of these bushings were purposely placed at the end of the board to form a sort of socket to hold the 9 Volt battery. The antenna output connector which is mounted on the handi-box is a switchcraft #3501FP phono jack. A small hole may be drilled in the bottom of the handi-box through which a screwdriver may be inserted for adjusting C1. For extreme accuracy C1 is adjusted to zero beat with WWV.



A 36 inch piece of insulated wire soldered into a phono plug may be inserted into the phono jack and used as a test antenna. The intensity of the markers may be varied by moving this test antenna near your receiver antenna lead-in. If you are using a coax lead-in you can couple by drilling a small hole in your coax relay so that the test antenna can be inserted near the relay armature. You will find that most SWR meters provide an easy method of coupling to the center conductor of the coax. As a last resort you can always couple to the receiver or converter antenna coil.



I have made very good use of this gadget to spot frequencies in the 144 and 220 MHz bands. It was well worth the time and effort it took to build it.

ALL BAND FREQUENCY MARKER

Kenneth W. Robbins W1KNI

Crystal controlled marker generators are useful adjuncts in any frequency determining situation requiring high accuracy, such as locating band edges, sub-bands and calibrating receivers. If you've been entertaining thoughts about construction of one, a version is described here which uses the new C/MOS integrated circuits powered by a 9 volt transistor radio battery. And instead of the usual rotary harmonic selector switch, a multi-pin IC connector strip and three test plugs serve as a miniature patch panel to enable various divisions of the reference crystal, with a maximum countdown of 256. "Rocks" from 100 kHz to 4 MHz oscillate readily in this circuit. In this model an FT241 xtal set to 400,000 Hz has been chosen for control and has usable receiver calibration divisions down to 2.5 kHz. The harmonic spectrum extends to at least 160 MHz, the tuning limit of a transistor superregen used in testing. When used in densely occupied HF bands, an AM beeper can be switched on as an identification aid.

Divide by	Output, kHz
1	400
2	200
4	100
8	50
10	40
16	25
20	20
40	10
80	5
100	4
160	2.5

Table 1.

Referring to Fig. 1, one third of a hex inverter makes up a crystal controlled oscillator and buffer, another third is a slow rate pulser and the two remaining units function in the dividing section. These are all standard circuits described in RCA's COS/MOS Data Book #SSD-203. An emitter follower minimizes loading on the IC outputs, speeds up rise time to increase harmonic content, and provides a low impedance output. The AM



Fig. 1. Schematic.



Photo 2.

beeper is a simple clamp that gates rf on or off to following stages.

Photo 1 shows all components mounted on Vector P pattern perf-board that fits inside a Bud minibox. Sleeving 3/8" (10mm) long is slipped over the wire trap terminals of the contact strip to space it up from the board. A DPDT center-off miniature toggle switch acts as one board to panel spacer. Diagonally across from it, a 4-40 threaded rod conducts emitter follower output up through the front panel via a 1/2" (13mm) insulating spacer and plastic shoulder washers. Two regular 4-40 screws and spacers complete the four corner mounting. This spacing allows the contact strip to project partly through a panel cutout so that it is mechanically secure without fastening.



Photo 1.

Photo 2 (completed assembly) shows a stick-on label with patching connection call-outs for various division ratios. If only one crystal is employed, labeling could indicate most used frequencies instead. A typical frequency vs division listing for this model is shown in Table 1. You can easily make up a complete table of all possible ratios, remembering that each CD4015 shift register divides by even numbers ONLY, starting at 2 and ending at 16.

Uses to which a marker generator may be put have been described before: i-f alignment, BFO, scope linearity, etc. A type that divides down to the audio range like this one is especially useful in checking superhets. A very broad and flat spectrum of overlapping signals is generated and an audio tone will be heard no matter where the set is tuned. If its tracking and sensitivity are top-notch, the S meter will hold steady over the tuning range. Tracking adjustment amounts to tweaking for maximum meter reading or loudest audio tone. Then patch for 100 KHz markers and check calibration. It's a lot faster and easier than using a conventional signal generator.

1	CD4009	1	15/60pF trimmer
2	CD4015	1	.01 uF
1	1N34	1	xtal; see text
1	1N995	1	xtal socket
1	2N5130 or equiv.	1	Alco #MST205P switch
1	2.7k	1	Bud #CU-2115HG minibox
1	4.7k	1	Vector #44P29-062 perfboard
1	47k	1	#216 battery
2	22M	1	Battery connector
1	22pF	3	16 pin IC sockets
1	47pF	3	Augat patch pins or equiv.
1	100pF	1	20 pin contact strip
1	470pF		SAE #Series 7000

Table 2. Parts List.

POOR MAN'S UNIVERSAL FREQUENCY GENERATOR

John Schultz W2EEY

As precise frequency control and measurement becomes more and more a part of the amateur radio game, the need develops for test instruments that deliver a wide range of both rf and af signals of high accuracy. It would be ideal if everyone could have a frequency counter and a synthesizer type rf and af generator but that is hardly the case. Most amateurs must utilize their basic station gear along with selected accessory items to test out and adjust equipment. This article describes a very useful accessory item that for a modest cost goes a long way toward having some of the expensive test equipment just mentioned. The item to be described is somewhat like a grid-dip meter in that it is basically a simple type of oscillator but as one gets to know and use it, new uses for it are found and its versatility constantly expands.

Circuit Description

Figure 1 shows the circuit diagram of the test generator. Basically, it consists of a string of SN7490 decade counters which are used to divide down a selected input signal by a factor of 10 or 2. The input signal can come from a 1 MHz master oscillator, a special crystal oscillator for externally used crystals or from any external sine-wave source. The special crystal oscillator which uses a SN7400 will operate with almost any basic or overtone crystal in the hf range. It can be used for crystals in the low frequency and lower VHF range also by a simple



Fig. 1. Diagram of universal frequency generator. Output frequencies shown are for using 1 MHz oscillator.

modification. One gate of the SN7400 crystal oscillator is used to drive a LED which will indicate that the crystal is oscillating so it serves as a crystal activity indicator as well. When an external sine-wave source is used, it is first coupled through a SN74121 multivibrator. This stage squares off the sine wave so it can better drive the subsequent frequency divider chain.

The frequency divider chain is fixed, although one could easily switch the individual SN7490 units to divide by different ratios when desired. This should be obvious by noting the wiring of the divide by 2 SN7490 with that of the divide by 10 units. However, the variety of frequencies which can be generated then with different input sources becomes confusing and more than would normally be needed.

The fixed divider chain follows the sequence: divide by 10, divide by 2, divide by 10, divide by 10. A separate branch after the first divide by 10 unit goes through two other divide by 10 stages. In the case of the divider chain being driven by the 1 MHz master oscillator, this results in the following output frequencies being simultaneously present: 1 MHz (basic oscillator output), 100 kHz, 50 kHz, 10 kHz, 5000 Hz, 1000 Hz and 500 Hz. With any other frequency input source you can easily calculate what frequency outputs the divider chain will bring in both the rf and af regions. Many surplus crystals will produce interesting frequencies of high stability in the af region that can be used for test purposes.

When using the special crystal oscillator, the LED will glow to indicate that oscillation is taking place. As shown with a 150 pF capacitor from one side of the crystal oscillator circuit to ground, the oscillator will work satisfactorily with hf crystals. Its range of oscillation can be extended to lf as well as high frequency overtone crystals by changing this capacitor. The value of capacitor required in picofarads is 500 divided by the frequency of the crystal in MHz. This value need, however, to be only approximate unless you require an absolutely square wave output from the unit.

When using the multivibrator input about a 1½ to 2V peak input, either sine-wave or approximate square wave is required.

Construction

The whole unit can be constructed on a piece of perforated board about 3 x 2 in. and made completely portable if powered by a 4½V battery (Burgess No.532) or just three D cells in series. This arrangement does not provide the absolutely best stability for the 1 MHz master oscillator but unless you intend to use the unit for marker frequency generation in the VHF range, it is a perfectly satisfactory arrangement. Alternatively, one could power the ICs from any standard 5.5V regulated supply used for IC digital circuitry.

I constructed my unit for battery powered operation and enclosed the unit in a small aluminum mini-box. The output of each divider was brought to a pin jack on the front panel of the unit.

One simple way to wire the relatively small number of ICs involved is to purchase perforated board which has hole spacing to fit standard DIP and preferably with a copper pad still left around each hole. The ICs are then placed on the board and the appropriate pins which either go to ground or to the 4.5V line bent in different directions. The ground line is run along one side of the IC and the 4.5V line along the other side and bare wire used to connect the appropriate pins to either line. Figure 2 illustrates the wiring for one of the divide by 10 ICs. When one starts this process on the board, it will be surprising how fast the wiring is completed. Individual insulated wire jumpers are used to make the input/output connections between ICs. The wiring is not critical and using a receiver to hear the markers, or an audio amplifier for the lower frequency outputs, one should be able to determine quickly if the circuit is working. The frequency of the 1 MHz master oscillator may be brought exactly on frequency using the 25 pF trimmer in the circuit and checking against WWV with a harmonic of the oscillator or by using a counter.

Applications

As I mentioned before, the applications that you can find for the generator really begin to unfold only after you have had it around the shack for awhile. Some of the applications would be:

1. A frequency marker generator for receiver calibration. The markers are usable up into the VHF range.

2. To extend the range of present rf or af signal generators into lower frequency ranges than they presently cover.



Fig. 2. Perforated board wiring of ICs. One SN 7490 divide by 10 unit is shown wired.

3. To perform stability checks on high frequency variable oscillators. The divider chain will always perform precisely and you can monitor the change in frequency of a higher frequency oscillator with a stable low frequency receiver.

4. A frequency generator to generate precise rf or af square wave signals at any frequency desired by choosing the proper crystal.

5. A crystal activity checker.

6. By taking two or more of the simultaneous outputs together via mixing diodes and a series tuned circuit resonant at the desired frequency, you can also mix the divider outputs to generate a variety of intermediate frequency outputs.

CALIBRATE THAT CALIBRATOR

Mitchel Katz W2KPE

Most modern receivers and transceivers in use today rely upon a 100 kHz crystal oscillator to calibrate the tuning dial. While some of the calibrators are built in, others come as outboard accessories. In any event the operation of each is the same.

By this time we all probably know what "zero beating" is. The 100 kHz oscillator in order to serve as a calibrator must be "zeroed" to some standard frequency such as the WWV carrier frequency on 5, 10, 15, 20, etc. MHz. With a CW or AM receiver, we can very easily tune through the zero beat point. On SSB receivers because one of the sidebands is missing we can only hear the one side as we approach zero. The other side of zero is greatly attenuated and may possibly not be heard at all. To further complicate matters for us in trying to calibrate the 100 kHz oscillator, as we can only hear down to about 20 Hz, we can't zero in any closer than this. Leaving the receiver at this point, we next turn on the 100 kHz calibrate oscillator. After a suitable warm up period, we turn the tune control of the oscillator and again adjust for a zero beat condition against the WWV frequency. With this method of calibration we have several possible sources of error. First in zeroing WWV with the receiver beat frequency oscillator and then zero beating the 100 kHz calibrator against the bfo. Each of these adjustments is limited to the lower limit of our hearing range, as well as the fact that we are obtaining the zero beat at a relatively low i-f frequency.

A more accurate method of calibrating the 100 kHz oscillator will now be discussed. After the receiver and calibrator oscillator have been warmed up for about 30 minutes, tune in WWV on a frequency that produces a fairly good, steady signal. Adjust the tuning for maximum reading on the S-meter. Having tuned in WWV, turn *off* the beat frequency oscillator. Now turn on the 100 kHz oscillator that is to be calibrated. If a harmonic of this oscillator is fairly close to the WWV frequency, a beat note will be heard. At this time adjust the calibrator "crystal tune" control and the S-meter will start pulsing from a maximum to a minimum value. The closer you get to dead center the slower the pulsing action will become. It is fairly easy to come down to 1 pulse per second with this method. If your receiver doesn't have a meter, you can also hear this pulsation very clearly. In any event you would always tune for the slowest pulse rate.

Note that with this method we have adjusted the calibrator frequency harmonic directly to the WWV carrier rather than to a low i-f. We have eliminated one zero beating step, and this, together with the fact that we are obtaining the zero beat at a much higher frequency, will provide greater accuracy.

Having described the method, here are a few points of general interest:

1. Before attempting any calibration let the equipment heat up for at least a half hour to stabilize.

2. After tuning in WWV, wait until the 400 Hz modulating tone goes off before adjusting the calibrator. If not, you may find later that you zero beat the 400 Hz instead of the carrier frequency!

3. The levels produced in the receiver by WWV and the calibrator oscillator should be about equal to produce a good beat between the two frequencies.

4. Use the highest WWV frequency that will produce a good, stable signal in the receiver. Certainly a 1 pulse per second beat at 20 MHz will provide greater calibration accuracy than 1 pps beat at 5 MHz or better yet than 455 kHz! The accuracy will be considerably greater and it is no more difficult to come by.

A SIMPLE FREQUENCY DEVIATION METER

John Reinartz K6BJ

A frequency-deviation meter allows one to read the deviation plus or minus that a received signal is off frequency. Depending on the meter range desired and used, a deviation of ten or less cycles can be read either high or low. Such a device is especially useful when used on MARS nets or when frequency checks are desired of any incoming signal and the answer must be in cycles low or high of a desired frequency. Those grinding their own crystals or desiring to compare crystals will find this device especially useful.


.1
.1
.1
100K
SILICON DIODES
10K
INPUT
+
3v
−
FLASH
LIGHT
CELL
−
3v
+
0-50 µA
THERE IS NO MEASURABLE DRAIN ON THE BATT
WHEN METER IS NOT IN USE.

Fig. 1

Two fundamental circuits were investigated, one using diodes only and the other using transistors only. These are shown in Fig. 1 and 2 respectively. A 0-50 microampere meter should be used for the diode type and a 0-1 milliampere meter will serve nicely for the transistor type, although a 0-50 or 0-100 microampere meter will also serve nicely in the transistor type frequency-deviation meter system. Silicon diodes were used for the diode type and 2N123 for the transistor type. An input voltage of 25 is needed for the diode type and 7 volts or less for the transistor type depending on the meter sensitivity, being 2 volts when a 50 microampere meter is used.

Whatever scale reading is desired, be it 250 cycles low or high or 500 cycles low or high, the meter cover is removed and new figures are added below the meter scale with a zero in the center of the scale and maximum readings at each end of the scale as appropriate. Pencil markings will do. The 250 cycle can be read to 10 cycles per division and the 500 cycle scale can be read to 20 cycles per scale division. Each can be read to half these values or 5 and 10 cycles respectively.

In use, you set your frequency meter, LM or 221 either 250 cycles or 500 cycles lower than the frequency to be checked. If the frequency to be checked is right on, the frequency-deviation meter will read zero at the center of the scale on the meter; if the frequency is low, the meter will read low and if higher, the meter will read higher. The answer in cycles will be the value indicated by your new markings. In use the frequency-deviation meter is connected across the high impedance output of your receiver in the case of the diode type and across the low impedance output in the case of the transistor type.



Fig. 2

In those cases where a definite frequency will be under observation, it will be found advantageous to grind or obtain a crystal that is adjustable to 250 cycles low or 500 cycles low, as appropriate, and to use it in the transistorized oscillator shown in Fig. 3. Any crystal holder that has an adjustable air gap will do. Some of the TCS surplus crystal holders have a three point adjustable top plate and are about the best obtainable. Since your best and probably only method of adjusting the crystal is by the use of your LM or BC221, be sure that your frequency standard is accurate. It is best to use the low frequency position and with the 1 mc crystal switch on, tune the meter to that portion of the desired frequency less the mc part. For instance, to set the LM for a reading of 2,732,000 cycles, set the LM on the low frequency for 732,000 cycles or 732 kc. The 1 mc crystal will furnish the mc part of the reading. In my case I set the LM to 731.5 kc and adjust the crystal to that frequency in the adjustable TCS holder. The transistorized oscillator holds the frequency to such a close tolerance it has not been necessary to make adjustments in weeks. A hand held push switch connected into the positive battery lead allows the oscillator to be turned on as needed to check the frequency of a MARS station on 2732 kc to an accuracy of plus or minus 10 cycles of that frequency. The frequency-deviation meter is of course checked against the 440 or 600 cycle tone of WWV, no other check is necessary since the scale is linear.



Fig. 3

Chapter VII

GDOs

THE INDICATING OSCILLATOR

Ken Brown KH6AF

Relatives of this little gadget have been around a long time! Even the transistorized versions, which usually leave something to be desired. With an FET, however, we are back in business as with tubes, but with many advantages.

The range of this oscillator is fantastic. That is, without any circuit tricks or special handling. The low frequency end was carried down to the 1 MHz in order to cover the lowest ham band. The high end takes care of 250 MHz easily. This can be extended with a little more effort.

Use of a field-effect transistor (FET) allows operation more nearly like the tubes with which we are, perhaps, more familiar. However, we are not tied to the power lines, which alone makes it worthwhile.

A 2N4221 FET was used in this indicating oscillator. Very likely other FETs will work also. The MOSFETs also should be as good, if not better. The new ones with built-in diode protection would be much easier to handle.



Standard banana plugs spaced ¾ in. make ideal bases for the coils. The lower frequency coils are wound on polystyrene forms.



Fig. 1. Indicating oscillator circuit diagram.

The circuit (Fig.1) is not critical. However, the sensitivity control should not be bypassed. Layout could possibly be improved with a slightly larger box, allowing the dial to be placed on the face with the meter. It is a good idea to keep the layout symmetrical as far as possible, particularly the tuned circuit. This can be seen in the photo of the inside view. The box used was an LMB 532 EL with the cover reversed to allow for coil mounting insulator (polystryrene or other good rf insulating material). The meter should be a 50 μA movement; otherwise, a meter amplifier such as the one shown schematically in Fig. 2 will be necessary. This is no problem, as there is room for this amplifier on the circuit board.

A thumbwheel from a BC-375 tuning unit could be used very nicely as a dial. Three sides have been left clear for ease in placement of unit when in use. Plug-in coils makes for easy bank change and application to the job at hand. Standard-spaced banana pins allow for use with other accessories. Use 5/8 in. polystryrene tubing and stud-type banana pins.

A dual banana plug can be used during construction for setting the spacing accurately. The coils shown have the pins wired in place for stronger mechanical assembly. Drill a hole for about 24 AWG copper wire on each side of the pin studs which will lie along each side of the poly tubing. Use a number 59 or 60 drill. One wire is enough on each pin. Form a hairpin with about an inch of wire, push it through the drilled holes from the outside. Now twist tightly with longnose pliers, cut it off short, but not so short as to allow the wire to untwist! Then apply several coats of liquid "poly" cement. Be sure to move the coils frequently during the hardening period to make sure the liquid "poly" flows evenly over the stud and forms a slight fillet with the tube. Epoxy doesn't seem to work well with polystyrene. Neither Allied nor Newark list liquid polystyrene any longer, but your neighborhood hobby shop should be well stocked.

The lowest frequency coil (number 1, 0.95–2.2 MHz) was made from a Miller



Fig. 2. This meter amplifier will increase the level of the signal so that a less-sensitive meter than 50 μA may be used.



Interior view of oscillator with coil attached shows construction of the author's version.



Fig. 1. Schematic diagram of the little gate dipper.

951 ferrite 0.5 mH choke with 6 or 8 turns removed – just enough to slip inside the poly tubing. Some reaming may be necessary. The number 2 coil (2.2–5.4 MHz) was made from a Miller ferrite antenna unit with the slug permanently installed in the top end and all lugs and mounting hardware removed. This coil was also mounted inside the poly tubing. The number 3 coil (5.4–13.5 MHz) consists of 32 turns of 28 AWG enameled wire, close-wound on the outside of the poly tubing. All coils are 2½ in. long with windings as near the end as practical. The number 4 coil (27–50 MHz) consists of 10 turns of 24 AWG enameled wire, close-wound. The number 5 coil (45–100 MHz) consists of 2 turns of 14 AWG enameled wire, self-supporting. The number 6 coil (60–270 MHz) is one hairpin loop 3/8 x 1 in.

A jack is provided for headphone use. The screwdriver-adjusted miniature pot is for zero adjustment of the meter amplifier. It can be seen in the photograph.

THE LITTLE GATE DIPPER

John Aggers W5ETT

Possibly you now own a grid dipper, but is it small, easy to handle, and cordless, making it completely portable? If not, you will want to build this gate dip meter. The cost is extremely low – only about $7. All parts are readily obtainable and construction is simple. The plug-in coil forms, using battery plugs and polystyrene tubing, are easy to make.

The Circuit

An MPF 102 FET is used in a modified Colpitts circuit. Except for the #1 coil, where a choke is used, the B+ is fed to the centertap of the coil. This is necessary to obtain a fairly constant gate current as the oscillator is tuned to its end frequencies. Drain current varies from 4 to 1 mA proceeding from 225 to 1.7 MHz. At the same time the gate current varies from 20 to well over 50 µA.

From this, it is apparent that the stronger the oscillations the smaller the drain current and the larger the gate current. In gate dip operation, as power is drawn from the oscillator the drain current will increase and the gate current will decrease or dip.

Limited wavemeter operation, obtained by switching off the B+, is accompanied by a slight shift in calibration. When the circuit picks up rf, the FET suddenly goes into oscillation using the rf as its battery. Thus, the amount of rf picked up must be large enough or there will be no oscillation and no meter indication. However, despite these deficiencies, it is still considered a useful mode of operation and for that reason has been included. It is only necessary to wire the sensitivity control so that the resistance is maximum when the switch is in the off position.

Construction

A natural finish aluminum minibox (4 x 2-1/8 x 1-5/8 in.) is used for the meter case. The variable capacitor came from an old transistor radio and measured 1 3/8 x 1/2 x 1 in. The shaft was already squared and tapped for a small screw. Since those listed in the catalogs have a plain or flat shaft, you will have to use a collar with setscrew, or drill and tap the shaft. The trimmer capacitors are not used and should be removed.



The little gate dipper with spare coils.



Meter is held against the front panel by a small bracket. The FET is the small black object in the center.

To make the coil socket you will need three pin receptacles from an octal socket, two pieces of 1/8 in. Plexiglas approximately 7/8 x 3/4 in., and one battery plug for a pattern. The pins of the battery plug form a triangle. I shall refer to the holes at the base as the outside holes. Drill holes in one piece of plastic to match the pins of the battery plug. Match the two pieces of plastic, clamp in a vise, and drill the two outside holes in the second piece. Bend the lug part of each socket pin to a right angle. Slip one over each outside pin of the battery plug. Using this as a jig, solder the lug portions to the stators of the variable capacitor. Remove the plug, and the pieces of plastic should fit down over the variable capacitor. The lug part of the center socket pin is brought out between the two layers of plastic.

File a small notch in the bottom piece to accommodate the lug. Before cementing the two pieces together and to the frame, make each hole slightly larger than the diameter of the socket pins. This will allow for expansion when the plug is inserted.

The dial is made of 2-1/4 in. diameter 1/8 in. Plexiglas. To give the dial a rough edge, for good thumb traction, I heated an old gear wheel and rigged up an arrangement to rotate the dial against it. The gear should have rather coarse teeth and rotate with the dial, or you will create flat spots.

The variable capacitor can now be mounted in the case. Position it so that the top and sides of the dial will be just about even with the edges of the case.

The dial marker is mounted on square aluminum posts. The top post (2 in. long) has 1½ in. of its length filed down to a 1/8 in. thickness to reduce its bulky appearance. To make the hairline, scribe a line in a ½ in. wide piece of plastic and fill in with a ballpoint pen.

The sensitivity control I used was already prepared for the knob shown. If you don't have one like it, use a dime-size pot and a setscrew knob. Any resistance from 5 to 10 kΩ will be fine.

Keystone light meters are available from Olson Electronics in a package of five ($3.99) or Transistors Unlimited Co. (75¢ each). Some modification of the meter is necessary. Remove the light cell and series resistor. Drill two holes, spaced ½ in. apart in the back of the case to pass 4–40 machine screws for easy soldering, make sure the heads and nuts are clean and free of any nickel plating. The screws should be filed even with nuts in order to make room for the battery. Solder the leads from the meter movement to the terminals, but be quick because the plastic case tends to melt in a hurry.

Wiring is just a here-to-there proposition, requiring no terminal boards or terminal lugs. The FET is soldered in place supported by its own leads. With reasonable care you should not damage it. A battery holder was found unnecessary; however, it is a good idea to wrap a layer of tape or stiff fiber paper around the battery to prevent the metal case from shorting out the meter terminals.

Coil Construction

Figure 2 and the photo give the necessary dimensions and show the parts needed to make the coil forms. The battery plugs are listed in the catalogs to fit #482 and


1-3/8 in. LG COPPER STRIP x 1/16 in. WIDE
CLEAR PLASTIC 5/8 DIA
RFC
RFC: 10T 20 AWG CLOSEWOUND ON 1/8 in. I.D.
M3 BATT PLUG
G
CT
D
1
85-225 MHz
50T CT CLOSEWOUND 28 AWG
1K
1K
G CT D
4
6-15 MHz
CT
G
D
CT
2
32-85 MHz
1-1/2 T
2-1/2 T
GATE DRAIN CT
18T CT CLOSEWOUND 28AWG (SPACED 1/4 in. BETWEEN TWO WINDINGS)
POWDERED-IRON SLUG (1/4 x 1/2 in.) (3/8 x 1/2 in. FOR 1.7-3 MHz)
60T (110T FOR 1.7-3 MHz)
CLOSEWOUND 30 AWG SILK
60T (110T FOR 1.7-3 MHz)
G D CT
3
13-32 MHz
G CT D
5
2.9-6 MHz (1.7-3 MHz)

Fig. 2. Coil configurations for various frequencies of resonance.

M3 batteries. The center pin should be filed slightly shorter to make the plug seat evenly in the socket. While you are at it, file the nickel plating from the ends of all plug prongs. This will make for easier soldering.

Complete coil information is given in Fig. 2. However a little explanation may be in order. The irregular method of winding the #2 coil is necessary to reach 85 MHz and still maintain oscillation. With 4 turns close-wound the highest was too low. With the 4 turns spaced, oscillation ceased at the highest frequency. The 30 AWG silk wire was taken from a TV flyback transformer. The resistors in the centertap of the last three coils improve the meter's sensitivity slightly. They are mounted right next to the coil winding. With a slight groove filed inside the insulating sleeve, it should slip over the resistor.

The #6 coil is layer-wound as space permits and scrambled wound the rest of the necessary turns. The top winding of all coils should end near the very edge of the coil form. This will make for easier coupling to a tuned circuit. After the coils are checked out the insulating sleeves may be glued to the plug base.

Allow the glue to dry for several days before plugging the open ends of each coil with a small cardboard disk. The coils are painted with colored lacquers. Colored paper between the coil and the insulating sleeve will probably work just as well.

Calibration

For calibration purposes, you will need another indicating oscillator or dip meter. Operate it in the diode or wavemeter mode and loosely coupled to the gate dipper. I calibrated only 5 points on each scale plus any ham bands which appeared. Remember the dipper is not a frequency meter but something to get you in the ballpark.

Conclusion

The little gate dipper was checked against a well known commercial tube equivalent and, as near as I could tell, they were just about even. The battery should last for a long time because the current drain is extremely low.

THE GREAT DIPPER

John E. Boyd WA0AYP

Test equipment is essential in the hamshack, as those of us have found when we attempted to get that new piece of homebrew perking for the first time. One of the most useful pieces of test equipment is the grid dip oscillator or simply, the GDO; besides being relatively inexpensive, it is particularly versatile. Need an indicating absorption wave meter? The GDO will do that. How about a modulated signal source? It handles that too. If you are interested in discovering its whole variety of uses, why not purchase one of several books on the subject.

Every item used in this GDO was selected with an eye toward the average home builder. There are no parts which must be specially purchased from the West Indies Export Company or similar outfit. Nearly all the parts, except for the meter, miniature pot, and mode switch, were obtained from the junkbox, or rather, from several junkboxes. If you insist on buying all new parts, total cost of the project will be about $20.



Circuit description

The grid-dip oscillator, in this case more properly termed an emitter-dip oscillator, gets its name from the fact that emitter current in transistor Q_1 decreases when the tuned circuit C_1-L_1 is in resonance with a nearby circuit. This decrease is easily seen by the dip of the meter indicating pointer.

When switched to the diode position, B+ is removed from the oscillator and the incoming rf is rectified by diode D_x; the voltage developed across the 2k resistor is amplified by the meter amplifier and monitored by the 0-1 mA meter. In switching to the signal position, B+ is removed from the meter amplifier but applied to the modulator, and a 1 kHz tone is available from one of the output jacks. In the modulated oscillator position, B+ is reapplied to the oscillator, and the oscillator is modulated by the 1 kHz tone.

Like a patch-work quilt, this GDO was built using circuits from already published articles or books and modified where necessary. The whole circuit is composed of three separate entities–oscillator, meter amplifier, and audio tone generator. The circuit is not particularly critical, but lead lengths and dress in the oscillator must follow good VHF practice, if stable VHF oscillation is to be maintained.

My operating time is spent on the various bands from 28 mHz to 432 mHz. Quite naturally, when I discovered that the GDO would not oscillate satisfactorily over the entire range from 2 mHz to 200 mHz, I juggled values so that it would oscillate well at 216 mHz (for tuning frequency doublers to 432 mHz); then I tried to get as low in frequency as possible. Oscillation was vigorous to about 20 mHz. Coils and scales were then made to cover the respective ranges. It you don't do any homebrewing on the VHF bands perhaps you will find it necessary to



Fig. 1. Circuit diagram of the great dipper. Note that although the 2N2398 is a PNP transistor, the 2N918 is NPN, and if used as the oscillator transistor, problems would arise with voltage polarity. The diode D_x may be almost anything that you have available. The 1 pF gimmick capacitor consists of 1½" of twisted wire.

Internal construction of the great dipper. The modulator and oscillator boards are to the right—the oscillator transistor is mounted right next to the coil jacks.



change the value of the emitter-collector feedback capacitor, and to juggle the emitter and base resistor values in order to sustain oscillation at your desired frequencies.

Construction

Vector board was used, mainly because I wanted to experiment with component values; however, a printed circuit would be just as good, especially for something such as a club project. It can be seen from the photograph that the meter amplifier and audio oscillator are built on separate boards. This is due to the fact that I built several different amplifiers; the layout would look neater if they were on the same board. Positioning of the rf oscillator and capacitor C_1 as shown in the photograph is recommended, but the placement of other parts is not critical.

Fiberglass board is used as an insulator for mounting the banana jacks and plugs. It cuts and drills easily and appears to work fine. Three banana jacks were used, the third jack being used merely to provide mechanical rigidity. It could also be used, if necessary, to shunt additional capacitance across the emitter and collector on the lower frequencies.

Because a shear and a brake were available, I constructed my own chassis, consisting of two U-shaped pieces of 1/16" aluminum. Using the GDO is a breeze, for it fits the hand very comfortably; if placed on the workbench, it doesn't roll off each time it is bumped. The completed case (1¾" H x 2½" W x 6¾" L) is exceptionally rigid and imparts a reassuringly solid feel when handled. Commercially available miniboxes could be used if you don't have facilities available for rolling your own.

In building the rf oscillator, keep all the rf leads as short as possible; especially the short lead from C_1 to Q_1 and from circuit ground to chassis ground. It was found that false dips could be completely eliminated if a copper strap ¼" wide was added from the capacitor ground lug directly to chassis ground. Apparently the ground on the variable capacitor C_1 is not quite good enough at frequencies above 100 mHz. Various transistors were tried in the oscillator; the PNP type 2N2398 was found to be a good performer, as was the NPN type 2N918. However, the use of the NPN type could lead to problems with battery polarity. Capacitor C_2 is a 1½" length of twisted wire positioned near the collector lead of Q_1. This slightly modified oscillator circuit is from a book describing, among other things, a transistorized GDO which you may wish to use as a reference.

To keep cost low, a 0-1 mA meter was used in conjunction with a simple meter amplifier. If you happen to have a 0-50 μA meter lying in the junkbox, that would work equally well, and the circuit could be simplified accordingly. Several circuits were built for the meter amplifier; the one chosen was a compromise between cost and performance. A germanium transistor was used because it requires less voltage to turn it on. Leakage is low, the pointer of the meter resting just off zero when no coil is in place. Further information can be obtained from January 1966 *73 Magazine*, which was the source for this circuit.

A transistorized audio tone generator is coupled by a 2 μF capacitor to the base of the oscillator transistor for modulation. This modulated oscillator allows the GDO to be used as a versatile signal source. An output jack is included on the panel to allow the 1 kHz tone to be used without turning on the oscillator.



Fig. 3. Construction of the plug-in coil assemblies. The coil forms were made from the plastic containers which hold Polaroid print coater.



Fig. 2. Layout of the two circuit boards used in the great dipper. Although two boards were used in this case, the circuit could be easily adapted to one board, and even to printed circuitry.


4-POSITION SWITCH (29 CENT VARIETY FROM RADIO SHACK OR LAFAYETTE)
SIGNAL
DIODE
OSC.
MOD. OSC.
METER AMP.
AUDIO OSC.
RF OSC.
+9

Fig. 4. Wiring the four-position slide switch for the great dipper.



The three plug-in coils for the Great Dipper. Three ranges cover from 28 to 216 MHz. The second harmonic of 216 MHz may be used for tuning up 432 MHz converters and such.



Fig. 5. Full-scale dials for the great dipper. If the construction shown in the photographs is followed closely, the calibration of these dials should be within several percent.

There are a couple of components which not everyone will want to duplicate. One, the sub-miniature 10k pot with SPST switch, was chosen because a very limited amount of space was available; if the unit is built on a larger chassis, the more commonly available *Midgetrol* could be used. The other, a four position switch used to select the desired mode, is a 29c variety available from Lafayette or Radio Shack. It has a peculiar switching arrangement and if you duplicate this project, several hours of experimenting could be eliminated by following the pictorial diagram included in this article. A disadvantage of this particular switch is that the meter does not indicate in the modulated oscillator position.

Using individual scales on each plug-in coil assembly greatly enhances scale legibility, reducing the chance of reading error and speeding frequency identification. This scheme; however, is not original. It was described in a 1957 issue of *Short-wave Magazine*, and is currently being used on a commercial GDO. It requires little additional effort to build the coil assembly in this manner and is, to me, well worth that extra effort. For want of anything else, the coil forms were made from the plastic tubes which contain the film coater supplied with each roll of Polaroid film.

Lastly, ease of tuning is accomplished largely through the use of a 1" skirted knob. Small knobs are simply too difficult to use comfortably.

Calibration and operation

It is best to calibrate this GDO by listening for the oscillator, modulated by the 1 kHz tone, on a general coverage receiver. An alternate method is to use another GDO, placing one in oscillate and the other in diode, tuning for either peak or dip. The scales which were used on this GDO will serve if parts and layout are followed closely.

To use this unit as a dipper, place the mode switch in oscillate, and place the dipper coil next to the coil under test. The turns of both coils should be parallel, and not at right angles to each other. To keep from pulling the oscillator frequency, keep the two coils separated as much as possible, while still maintaining a meter dip. This assures that dial accuracy will be kept high. If a coil is inaccessable, twist a pair of wires together, forming a two turn coil on each end; slip this coupling link over the two coils. Keep in mind that a coil, when it is in a circuit, may not dip at the same frequency as when it is out of this same circuit.

GREATER DIPPER – MODIFICATION

John E. Boyd WA0AYP

Introduction

To the uninitiated, a grid dip oscillator is neither glamorous nor exotic, even if it does happen to be transistorized. But to those who have ever tried to put a coil on frequency, one is worth its weight in microcircuits.

The original model of the *Great Dipper* proved to be a versatile, if unexciting, grid dip oscillator. Intended to be used mostly at VHF, the dipper was limited to frequencies above 28 MHz. To those who seldom operate above 10 meters, the lack of frequency coverage below 28 MHz was a definite handicap. Expanding the frequency coverage downward extends the dipper's usefulness considerably.

Component changes made were not extensive, nor were the physical dimensions of the unit changed. The schematic diagram of the modified circuit is shown in **Fig. 1**, and the pictorial diagram of **Fig. 2** is included to supplement the photographs printed in the original article.

Modification

First, the oscillator circuit board should be rotated 90 degrees from its original position so that transistor substitution or replacement can be made easily. A microwave diode might be substituted for the original glass computer-type diode; this results in better performance at VHF, but its effect cannot be accurately predicted. A 1N21 or 1N23 diode could be used in place of the D4900 called for in the schematic. Best oscillator performance over a wide frequency range results from using a 5 pF capacitor as the collector feedback coupler, but this was a compromise value. If operation is likely to be confined to either the HF or VHF segments of the radio spectrum, some experimentation with this capacitor should result in improved performance over that particular range. For experimentation, use a 3-12 pF or 4-30 pF trimmer.



*Fig. 1. Schematic of modified circuit, with component changes indicated by *. L1: 13-23 MHz, 14½ turns No. 20; 22-44 MHz, 5¼ turns No. 24, 45-90 MHz, 1½ turns No. 24; 90-195 MHz, 2½ x 3/8 in.*



Fig. 2. Pictorial view of the dipper and its circuit board.

To perk up meter amplifier performance, the 2N388 meter amplifier is replaced by a 2N918, a relatively high gain, low leakage transistor.

Although the change was not made in this unit, a 6-100 pF (MAPC-100) variable capacitor could be substituted for the existing 5-50 pF unit. As can be seen from the full-size scales, frequency coverage is narrow on the 13-23 MHz plug-in coil. Those who frequently construct HF gear might benefit from the substitution.

Operation

Operation of the dipper is the same as before, except the frequency range is greater. Another coil must be wound for the 10-25 MHz range, but existing coils were not modified. Calibration is now different from before; full-size scales are included with this article for those who do not have a general-coverage receiver or another grid dip oscillator on hand for calibration.

Oscillation is still vigorous at 13 MHz, which indicates lower frequencies may be reached with a suitable coil plugged in. Similarly, oscillation is still noticeable at 195 MHz, so operation at higher frequencies may be possible.

Finishing Touches

Appearance of the dipper was improved after enlisting the help of a draftsman. The dial and meter scales were professionally inked. **Figure 3** provides full-size copies of these scales.

To improve the legibility of the labels and scales, they were inked on yellow cards rather than on conventional white paper. It's a small point, but for those who use test equipment frequently, the black-on-yellow technique results in less eye strain.

ETCHED CIRCUIT UHF DIPMETER

Bob Corbett W1JJL

I made three models of the dipper. They cover 130-175 MHz, 175-250 MHz, and 250-480 MHz. The first two models use the same size inductor, with the 130-175 MHz model using a larger capacitor for tuning with a ceramic trimmer across it. This trimmer is not shown in the schematic; its value is 7-45 pF and it should be adjusted to cover the proper range.

The 250-480 MHz dipper uses a smaller inductor than the others. It also has a copper jumper (shown in the layout) that the lower frequency dippers don't have.

Each dipper is complete (including the battery) except for the meter. The meters were omitted to save space and money, but can be included if you wish to use a slightly larger case.

Each dipper uses one RCA 2N3478 NPN silicon transistor. These transistors cost only $1.90 apiece, but it's likely that other transistors that are even cheaper could be used. The 2N3478 has odd basing—the only reference is the short case-shield lead—so don't shorten any leads until you're sure that you can keep track of the connections.

The copper side of the board for the dipper is shown in Fig. 2 with the component side in Fig. 3. Use glass or Teflon based board. Paper or bakelite board probably wouldn't be satisfactory. Trim the board to the proper shape with a nibbler. The inductor should be coated with coil dope to keep from shorting it when you use it.



Fig. 1. The etched circuit dipper is very simple. The circuit is almost identical to the one described by WA1CCH in the December 1965 73, but the construction is quite different. C1 is Johnson 160-104 (9 pF) for the two higher frequency dippers, and 160-107 (14 pF) for the 130-180 MHz model. There is a trimmer across C1 in the 130-180 MHz model; see text.

To mount the boards, you'll have to cut a thin slot near the edge of the Minibox used as a case. One way to do it is to drill a number of holes of the proper size in a row, then use a file to finish the slot. You'll have to bend that side of the Minibox out to get the board in. It's held in place by an extra set of nuts on the shafts of the potentiometer and the tuning capacitor. Be sure to trim the leads projecting from the copper side of the board so that they won't touch the metal of the case. The battery is held in place with a simple clip made from scrap metal.

The dipper is very easy to use. But before we get to that, let's check it out and calibrate it.



Fig. 3. Dial designs for the various MHz ranges, full size.



The three dippers shown here cover 130-480 MHz.



Here's the inside of one of the dippers.



Fig. 2. The copper side of the etched circuit board used in the dipper. This layout is full size. Use board suitable for these frequencies: fiber glass or Teflon.

Plug a 2 to 5 mA meter into the meter jack. You can use a more sensitive meter if you shunt it with a resistor that gives the proper scale. Put the resistor across the meter jack terminals in the dipper if you use the meter for other things.

Turn on the dipper by twisting the potentiometer knob clockwise until it clicks. The meter should show very low current. As you turn the pot, the current should suddenly jump to about 1 mA. That means that the transistor is oscillating. If you touch the coil, the meter reading should drop and the dipper may stop oscillating completely. Now tune the capacitor through its range. There should be a little variation in current, but not too much.

Now you're ready to calibrate the dipper. The easiest method is a sensitive wave meter that covers the range, but it's quite easy to do the job with a TV set. A TV set covers 176 to 216 MHz (channels 7-13) for the low calibration. Then the second harmonics of the dipper tuning 235 to 445 MHz can be received on a UHF TV set (470-890 MHz). If you have a two meter receiver, that gives you another maker at 146 MHz. You can put on the panel markings with Ami-Tron or Datak rub-on lettering.

The dipper should be complete now, and ready for use. Bring the dipper near a resonant circuit in the dipper's range and tune the frequency control. You should get a prominent dip in current when both circuits are tuned to the same frequency. The amount of dip depends on the setting of the pot in the dipper, the distance from the tuned circuit, the Q of the circuit, and the type of coupling.



Fig. 3. Component side of the dippers. There is a 7-45 pF ceramic trimmer across C1 in the lowest frequency model. See the text.

In many cases it's easiest to leave the dipper stationary and tune the other circuit.

The dipper can also be used for monitoring AM transmitters by plugging a set of headphones in the meter jack and adjusting the tuning and pot. You can also use the dipper for determining the frequency of another oscillator. Simply tune the oscillating dipper with headphones plugged in until you hear a slight click. You probably won't be able to get a zero beat at these frequencies.

Be careful that you don't use the dipper around an energized transmitter of more than a few watts output or the dipper may be damaged.

These dippers are simple, inexpensive and non-critical to build. After you've build them, you'll wonder how you ever tried to build UHF equipment without a good dipper.

UHF GRID DIPPER

J. Fisk WA6BSO

When building or testing equipment for the 420 mc band, amateurs invariably run into the problem of, "Where am I?". It becomes a little difficult to tell whether you are actually in the band or somewhere nearby. The uninitiated will counter that you should be able to figure close enough, after all the band is 30 mc wide; but even the experienced old timer will confirm that this just isn't so.

The 420-450 mc amateur band falls between the VHF and UHF television assignments and there is very little to use for a frequency reference point. It is nearly impossible to tell exactly where you are without resorting to expensive commercial gear or lecher wires. Nor is the problem confined to the ¾ meter band; when building crystal controlled converters for 432 or 1296, it's nice to know that the last tripler is really tripling and not doubling or quadrupling. Even with a 45 or 50 mc crystal, it's quite easy to tune up on the wrong harmonic. Remember that a 40 mc change at 400 mc is analogous to a 400 kc change on 75 meters.

There are several commercial instruments that fill this requirement nicely, but the cost of the least expensive of these would buy a pretty respectable all band receiver. Occasionally suitable test equipment appears on the surplus market, but again, the price is prohibitive. The simple UHF grid-dipper described in this article was designed specifically to economically fill this need. It covers the frequencies



C1,C2,C3	STANDOFF BUTTON BYPASS CAPACITORS
C4	BUTTON CAPACITOR (SEE TEXT)
C5	E F JOHNSON TYPE 160-104 VARIABLE
L	PLUG-IN COIL
P1	AMPHENOL 91-MC4M MALE CABLE PLUG
RFC's	8-1/2" No 2" ENAMELED WIRE WOUND ON 1/2 W, 100K COMPOSITION RESISTORS

Fig. 1. Schematic of the rf head of the UHF grid dipper.


GRID DIP METER
CARRIER
MODULATION
SENSITIVITY
OFF
DET
EXTERNAL MODULATOR
TUNING HEAD
PH
UHF TUNING HEAD

from 300 to 680 mc at a total cost that is comparable to a low-frequency kit-type grid-dipper. By using junk-box parts and smart horsetradesmanship this cost may be substantially reduced. I should hasten to point out that substitution of parts in the tuning head should be avoided if accurate dial calibration is desired.

This particular grid-dipper has been duplicated several times and in each case calibration has been within several percent of the original unit; at least as accurate as the familiar kit-type grid-dipper. This is helpful to the ham who does not have access to commercial equipment for calibration purposes. By using the layout and parts described in this article, the precalibrated dial illustrated in **Fig. 8** may be used with a minimum of error.

Although an accessory power supply, modulator and indicator are included in this design, an enterprising ham could use the power supply and meter presently available in any lower frequency tube type grid-dipper. Although using a modified low-frequency dipper is simple and inexpensive, the power/indicator box specifically designed for the UHF tuning head has several features that are not available in inexpensive kit-type units. These include internal 1,000 cycle modulation, provision for external modulation, and voltage regulation which provides the necessary stability at the ultra high frequencies.

The rf tuning head

The heart of this instrument lies in the tuning head itself. There is nothing particularly new or different about the circuit, but at these frequencies stray inductance and capacitance in circuit layout and construction will seriously affect the end result. All the lead lengths must be as short as humanly possible and physical circuit layout must follow standard UHF practice. One of the big problems in building tunable oscillators at UHF is to obtain an oscillator that will tune from one end of the range to the other with no "holes," frequency jumping or instability. The series tuned 6CW4 nuvistor oscillator shown in **Fig. 1** fills these requirements.

Insofar as possible, all the tuning head wiring is done on a point-to-point basis with the components mounted directly to the 6CW4 tube socket or button capacitor lugs as illustrated in **Fig. 3**. To obtain the desired accuracy with the precalibrated dial, this diagram should be followed as closely as possible.

To keep stray circuit inductance to a minimum, all wiring between the coil and tube socket is done with one-quarter inch wide strips of thin copper sheet. In addition, the rotor of the variable capacitor is connected to the 6CW4 grid (pin 4) with a short strip of the same material. The only tricky part of this wiring is the installation of the series capacitor C4. This capacitor is a 500 picofarad button type mounted as shown in **Fig. 5**. The "S" shaped bracket ("A") is made from a one-quarter inch wide copper strip, one and one half inches long and soldered to the mounting stud of the capacitor. Connection to the 6CW4 plate (pin 2) is made with the soldering lug on top of the button.


ALLIED 61 Z 411
27 2W
1N2860A (FOUR PLACES)
2A
125 VCT
50 MA
DETECTOR
MODULATION
CARRIER
OFF
S1A
SWITCH: MALLORY 3134J
6.3VAC, 2A
No 47
X
2K 2W
2K 2W
25 mfd 150v
25 mfd 150v
100V 10W ZENER
470K
47K
200 μa METER
5000 SENSITIVITY
1K
PHONES
1K
10K
3300
1K
.01
.01
.01
5600
5600
470K
2N3392
COLLECTOR
EMITTER
BASE
2N3392 BOTTOM VIEW
S1B
S1C
1
4
2
3
J1
X
EXTERNAL MODULATION
.01
AMPHENOL 91-PC4F
ALL RESISTORS 1/2 W UNLESS NOTED OTHERWISE

Fig. 2. Power supply and modulator for the UHF grid dipper.


RFC
R2
RI
2
12
RFC
RFC
C2
C3
CI

Fig. 3. Critical wiring around the 6CW4 socket.



OSCILLATOR SUPPORT
MAKE FROM 1/8" TEFLON SHEET
1/4 DIAMETER
3/8 DIAM
BEND LINE
OSCILLATOR SUPPORT ANGLE
CUT FROM 1/16" ALUMINUM AND FORM INTO ANGLE AS SHOWN
CUTOUT MADE BY PUNCHING TWO 5/8" HOLES AND FILING OUT CENTER AREA AS SHOWN.
NOTE: TEN CONNECTOR INSULATOR MOUNTING HOLES ARE MATCH-DRILLED FROM CONNECTOR INSULATOR.
1/4 DIAM
3/4 DIAM
TUNER CHASSIS
SCRIBED DIAL MARK
DIAL WINDOW MADE BY DRILLING FOUR 1/4" HOLES AND CUTTING OUT CENTER AREA AS SHOWN.
CONNECTOR INSULATOR
DIAL WINDOW
CHASSIS COVER

Fig. 4. Layout of the tuner chassis, chassis cover, dial, connector insulator, oscillator support and oscillator support angle.

Connection to the stator of the variable capacitor is accomplished with another short strip of thin copper as shown in **Fig. 5** ("B"). This piece of copper is bent so it touches both stator mounting pins when the unit is assembled; then it is soldered in place.

The oscillator and tuning mechanism are housed in a standard 2¼ × 2¼ × 4 inch chassis box laid out as shown in **Fig. 4.** Although the author's unit is based on an LMB type 107 chassis box, other manufacturers have similarly sized boxes which are equally suitable. The layout of the enclosure is straight-forward and no difficulty should be found in duplicating it. The dial and coil socket cutouts are made by drilling or punching round holes and then cutting out the area between them as shown in the drawing. This is easily done with an Adel "nibbling" tool. All of the small screw holes are drilled with a standard ⅛ inch drill to pass 4-40 screws; 5⁄32 inch holes will be required if 6-32 screws are used.

The dial window is cut from a sheet of 1⁄16 inch clear plastic to the dimensions shown in **Fig. 4.** A hairline is scribed in the center of this window; if a more distinct line is desired, this scribe mark may be filled in with black india ink. After the tuner enclosure is completed, this dial window is epoxied in place over the dial cutout.

The coil socket is made by installing two banana jacks (E. F. Johnson type 108-740) on 11⁄16 inch centers in the Teflon connector insulator illustrated in **Fig. 4** (if Teflon is not available, Polystyrene may be used). This "socket" is installed over the large oblong hole cut in the end of the chassis. The screw holes used for mounting the connector insulator are match-drilled to the holes in the insulator itself. In this way it is properly mated to the enclosure. Although nylon attaching screws were used in the original model, they are not necessary and regular metallic screws will not alter any of the oscillator's characteristics.

To reduce stray capacity to a minimum, the oscillator circuitry is mounted on an insulating sheet. Teflon was used for this purpose in the original unit, but epoxy board with the copper peeled off would be perfectly suitable. Sheet polystyrene is not too desirable in this location because of its susceptibility to heat. The envelope of the 6CW4 gets very hot and the ambient temperature within the confines of the small chassis is quite high.

The general layout of the Teflon oscillator support and associated support angle are also shown in **Fig. 4.** The angle is cut out from a piece of 1⁄16 inch aluminum sheet and bent in a vise to form the angle. When these two pieces are mated together, the metal angle will probably interfere with the lower nuvistor socket mounting screw. It must be drilled out using the hole in the oscillator support as a guide. This additional hole is not shown because its exact location will vary from unit to unit and depends upon the accuracy with which the parts are laid out.

The dial mechanism is not complicated, but it is hard to ascertain from the photographs exactly how it is put together. The exploded drawing of Fig. 6 should help in this respect. The vernier mechanism is an Eddystone 10:1 planetary drive that provides both smooth



305
310
320
330
350
360
380
405
410
420
440
460
485
500
520
540
560
580
600
630


PLUG-IN COIL
TUNER CHASSIS
E F JOHNSON 108-740 JACKS
A
B
500 pf BUTTON CAPACITOR (C4)
E F JOHNSON 160-104 VARIABLE

BOTH THE BUTTON CAPACITOR AND VARIABLE CAPACITOR CONNECTING STRAPS (A AND B RESPECTIVELY) ARE MADE FROM 3/16" WIDE THIN COPPER STRIPS AND FORMED INTO SHAPE AS SHOWN. NOTE THAT THE STATOR SUPPORTING PINS ON THE VARIABLE CAPACITOR HAVE LENGTHENED SOMEWHAT FOR PURPOSES OF THIS ILLUSTRATION

Fig. 5. Exploded view of the connections between the 6CW4 and the coil socket.



① CUT A PIECE OF No 10 AWG BARE COPPER WIRE TO THE LENGTH SHOWN IN THE DRAWINGS ABOVE

② INSTALL E F JOHNSON 108-754 BANANA PLUGS ON EACH END AND SOLDER IN PLACE BEFORE SOLDERING MAKE SURE WIRE IS FULLY SEATED

③ FORM COIL AROUND 1/2" MANDREL

① CUT A 1/4" WIDE STRIP FROM A PIECE OF .030 (1/32") THICK COPPER SHEET TRIM TO LENGTH SHOWN IN DRAWINGS ABOVE AND MARK BEND LINES 1/4" IN FROM EACH END. ROUND OFF CORNERS

② CUT OFF TOP SECTION OF BANANA PLUGS AT THE SHOULDER AND FILE SMOOTH

③ USING THE BEND LINES AS A GUIDE, BEND TWO 1/4" TABS AT RIGHT ANGLES TO THE STRIPS. SOLDER THE MODIFIED PLUGS TO THE TABS

④ FORM COIL AROUND 3/8" MANDREL

Fig. 7. The coils for the UHF grid dipper.

action and repeatability in a small package. Although this unit is manufactured in England, it is available from many of the larger electronics parts houses in this country.

Substitution of similar drives should be perfectly satisfactory as long as they don't extend more than one inch beyond the front panel of the tuner chasssis.

The vernier drive is connected to the variable capacitor through a ¼ inch polystyrene shaft 1-¼ inches long and the usual "¼ to ¼" shaft couplers. Polystyrene or some other insulator must be used here because the rotor of the capacitor must be isolated from ground. Because of the space limitations inside the enclosure, the coupler at the variable capacitor end of this shaft is only one-half of a standard coupler. A standard "¼ to ¼" coupler is sawed in two and one-half is epoxied to the end of the polystyrene shaft. Save the other half; it will be used for the dial drum hub.

The 8 pf variable capacitor was designed for screwdriver adjustment and its 3/16 inch shaft must be made compatible with the standard coupler. This is accomplished with a bushing made from sheet copper. A short piece of ¼ inch wide, 1/32 inch thick copper strap is formed around the capacitor shaft and takes up the slack between the shaft and the coupler.

The drum dial in the original unit was made from the metal top of a Johnson's Shoe Shine Kit (49¢ at the local grocer's), but any similar closed cylinder 1-15/16 inches in diameter and about 1-11/16 inches long should be suitable; other diameters will void the accuracy of the precalibrated dial. The "skirt" or bottom rim is cut off the metal can at the circumferential notch and a ¼ inch hole is drilled in the center of the top. The remaining half of the ¼ inch shaft coupler that was left over from the polystyrene shaft is then epoxied in place over the hole to provide a dial drum hub. Another hole is drilled in the side of the can 11/16 inches from the top; this provides access to the shaft coupler on the rear end of the vernier drive.

The precalibrated paper dial may now be cemented in place. It's a good idea to cement a piece of white paper the same size as the dial between the dial and the drum, otherwise the label on the can will show through the paper dial. Rubber cement is recommended at this point to prevent excessive wrinkling and distortion of the dial.

When all of the dial parts are completed, they are put together as shown in **Fig. 6**. It's a little crowded in the small box, but all of the parts *will* fit. However, in order to get all of the dial machinery into the box in the right order, a correct assembly sequence must be followed. First the polystyrene shaft and coupler are inserted into the dial drum from the rear. Next insert the Eddystone drive assembly through the hole in the front panel and mate it with the end of the polystyrene shaft. Place the bushing over the capacitor shaft, attach the polystyrene shaft and tighten the coupler; also tighten the coupler at the back end of the Eddystone drive thru the access hole provided in the dial drum. Install the vernier drive mounting screws. Now completely mesh the capacitor plates, center the low edge of the dial in the window and tighten up the dial drum hub. Disassembly must be accomplished in reverse order.

The tuning head is attached to the indicator/power unit through a four-conductor cable three feet long. This cable is attached to the box with a plastic cable clamp mounted in a hole provided immediately adjacent to the oscillator support angle and exits through a rubber grommeted hole at the front end of the enclosure. There is not enough room at the rubber grommet to use a cable clamp, so the cable is epoxied to the box at this point. Before installing the cable, however, check for sufficient clearance between it and the dial drum. It will probably be necessary to route the cable along the corner of the chassis to gain enough clearance.

Power indicator modulator

The power/indicator unit is housed in a standard 9 x 6 x 5 inch utility box (Bud type AU-1040 or equivalent). The layout of this



Fig. 6. Assembly of the dial.

circuitry is not at all critical, and just about anything that suits the builder may be used. The only particular caution that must be observed is with the transistorized 1 kc phase shift oscillator. This unit is built on a piece of perforated epoxy board (Vector 32AA18) 1-3/16 inches wide and 1-11/16 inches long. To preclude any 60 cycle pickup, this board is situated on the opposite side of the chassis from the power transformer.

In the author's case all the power/indicator components were mounted on a 4 x 5 x 1 inch aluminum chassis. This chassis was then mounted to the front panel of the utility box with the phone jack and power plug mounting nuts. Two large diameter holes (1-⅜ inch) are punched in the rear panel to provide access to the fuse holder and to pass the AC power plug. A chassis handle (Bud H-9168) on the top and rubber feet on the bottom just about complete the unit. There is one other addition however; five pairs of 5/32 inch holes, drilled on 11/16 inch centers along the rear edge of the top of the box provide convenient storage for the five frequency determining coils. A coat of spray paint and some Datak "Letraset" dry transfer labels are the finishing touches.

Calibration and operation

Without access to existing 420 mc equipment with known frequency characteristics, exact calibration in this band is impossible. However, this grid-dipper may be checked on the other ranges with the aid of an all-band television receiver. If the circuit layout and construction techniques described are closely followed, good correlation can be obtained and reasonable accuracy insured. The bands that are likely to be the furthest off are the lowest and the highest. In the lowest the coil spacing is quite critical and in the highest a slight change in length will move the frequency several megacycles. An accuracy of 2% at 600 mc is plus or minus 12 mc; close attention to the specified dimensions should provide accuracy better than this.

Operation of this grid-dipper is exactly the same as any lower frequency unit. It may be used in determining circuit resonance, detecting parasitic oscillations or as a signal generator. Because of its extended range, it has been found to be very useful in determining the series resonance point of rf chokes and ceramic bypass capacitors.

In the detect mode, this unit will indicate rf voltages as low as 50,000 microvolts. More sensitive operation may be obtained if it is used as an oscillating detector. In this case headphones are used and an audio beat note will be heard when the grid-dipper is tuned to the oscillator being checked. In the upper frequency ranges, it is usually difficult to obtain an actual beat note, and only a "tick" will be discernible when you tune by the frequency of the unknown energy.

When the oscillator is tuned between 605 and 650 mc, there is sufficient second harmonic energy to provide a strong reference signal in the 1215 mc amateur band. This is particularly useful in the initial tune-up of converters for this band. Use of the internal 1000 cycle modulation aids in distinguishing the grid-dipper signal from other rf sources that are present throughout the spectrum.



Fig. 8. Full size dial scale.

WIDE RANGE VHF-UHF DIPPER

Bill Hoisington K1CLL

Most dippers for amateurs that I have seen so far, not counting the $400 ones, stop around 200 MHz just as you are about to enter the fascinating UHF region. We do have the 432 and 1296 bands, so let's become more familiar with them.

After all these years of "grid-dipping" we find ourselves without a grid, so it just becomes a "dipper". To retain the prestige of a hyphenated name we can call it a "dipper-generator". Most grid-dippers have been used as generators, but this one has built-in modulation, variable input-output coupling, controlled Q, and several other interesting features. Best of all, it goes all the way up to 1296 MHz.

When this little unit is completed it may be used as a dipper for determining the resonant frequency of VHF and UHF circuits, as an indicating frequency meter with an adjustable Q-multiplier, a field strength meter and modulation monitor, a sensitive regenerative receiver, or a CW and MCW signal generator. You can also use it as a harmonic monitor or as a frequency transfer unit from one transmitter to another.

Several circuits must be considered when building a wide band instrument such as this. For example, you should change circuits around 100 MHz and again at 600 MHz, give or take a few hundred. Below 100 MHz coils are good; from there to 600 MHz you can use ¼ wave resonators, and after that the ½ wave job becomes rapidly the best method, up to 1300 MHz.

Plug-in rf heads

I have made no attempt to cover the complete range from 130 to 1300 MHz with one oscillator. By using plug-in tuners you may vary the components to suit the frequency. On 50 MHz for example, you may use a low cost transistor, a coil, and a 25 or 50 pF capacitor. From 100 to 600 MHz you use a better transistor, a ¼ wave strap, and a 10 or 15 pF capacitor. In the microwave region up to 1296 MHz you use the best transistor you've got, ½ wave lines,



Fig. 1. Basic VHF/UHF oscillator circuit.


1-1/4"
2-1/2"
SPRAGUE 2N1726
5/8" FROM BEND
VARIABLE LINK
1"
L1
1N295
C
B
E
1k
C1 30pF MINIATURE
1-1/8"
HANDLE
P1
COPPER
BAKELITE
J1-A
C4
C3
C2
RG-58/U
4 PINS OF 7-PIN METHODE PLUG
TO COLLECTOR METER JACK TO −12
TO DIPPER METER OR AF OUT
TO BASE BIAS CONT.
+12
J1-B
RF IN/OUT

Fig. 2. 130 to 300 MHz tuning head.

and a small butterfly capacitor of 3 to 5 pF.

If you break the circuit at the right point, it simplifies things—then the two halves may be connected through a miniature 7-pin socket and plug as shown in Fig. 2. All four leads are reasonably dead to rf. You can leave out some of the audio if you like, but it's very handy to have a modulated signal. If you're running triple or quadruple conversion, it's nice to know by it's modulation which is the signal and which might be a *birdie.* As far as dials are concerned—it makes calibration and reading a lot easier to have only one band or range per dial.

130 to 300 MHz oscillator

Fig. 1 shows the basic ¼ wave circuit; Fig. 2 the complete rf unit with control, af output and modulation.

The circuit itself is very simplified, as seen in Fig. 1; there being only one inductance, L1, and no choke coils. This should make for a flat tuning oscillator without power dips as it is tuned over a 2 to 1 range in frequency, and it does just that. With a 2N1726 in the circuit there is a smooth power output curve from about one volt rf at 130 MHz down to ½ volt at 300 MHz.

The rf coupling jack J1 couples the rf energy both in and out. This is because L1 acts as either a detector resonator or an oscillator resonator, as required. Actually this rf jack can be used as shown in Fig. 2. P1 is a variable link to L1 and is plugged into J1; J1A has a few inches of cable between the white ABS plastic front panel and the copper clad bakelite sub-panel. Because the phono plug is rotatable, a nice variation in rf coupling can be obtained. The coax cable and J1B get the rf out to the front panel for easy use with antennas, probes, cables, etc.


C4
C1
E
B
1k
C3
C2
VARIABLE LINK, SIMILAR TO FIG.2
1-1/8"
1/4" FROM BEND
COPPER
1N295
C1
3/4"
BAKELITE
TO C4
TO C3
TO C2
4 PINS OF 7-PIN METHODE PLUG
+12
BIAS
DIODE DC OUT
−12

Fig. 3. 300 to 600 MHz oscillator with variable link.

The emitter goes to a 1K resistor then through a coaxial bypass capacitor which gets the dc in and out and leaves the rf behind. These feed-through type bypasses are very necessary—do *not* skimp on this item.

300 to 600 MHz unit

Fig. 3 shows that this unit is essentially the same as the last, except for dimensions. I used a 2N1141 here although many others will work too. It tunes smoothly from 300 to 600 MHz; use the variable link feature as in Fig. 2.

900 to 1100 MHz

For this frequency range we need a little different approach. From Fig. 4 we can see that we now have two ¼ wave lines on which low-voltage points can be found to attach the base and collector resistors. Most of the ¼ wave portion of the lines on the transistor end are actually inside the case. The places where the base resistor and the 500 ohm collector resistor are attached to the ¼ wave lines can be found, or checked, by watching the rf meter and touching the lines with a pencil. At the proper point no change occurs in the rf output; sometimes it even increases.

The diode circuit of Fig. 6 is not ideal but it works. I have several of these around the shack and they work very well for detecting 1296 Mhz energy. Even ordinary hook-up wire will support the assembly of Fig. 6 about ¼ inch below the rf lines; you will soon find the best spot with the unit oscillating. The rf input jack and associated loop L3 are fastened so that L3 is in place over L1 and L2, and it's coupling can be varied in a semi-fixed fashion.

At this point we should mention that as a "dipper" the circuit is still working fine; also as a signal generator. It also serves as an rf detector but as the frequency gets up into the microwave ranges it is not quite as good as the tuned rf detectors featured in another article in 73 Magazine. Ideally, you should use the dipper on microwaves as a modulated generator and couple it into the unknown circuit; then a probe attached to *another* tuned detector should be coupled into the unknown circuit. There are quite a few variations using the dipper as an oscillator that you will find useful if you use a little ingenuity.


NOTE
L1 & L2 ARE THIN BRASS STRAP, 3/8" x 5/8"
4 PINS OF 7-PIN METHODE PLUG
+12
BIAS
DIODE
−12
1k
5k
.001
500Ω
2N1141
B
E
C
SEE FIG.6
L1
L2
5/8"
1"
RF OUTPUT/INPUT
J1
L3 (LINK-COUPLED OVER L1,L2)
1/2"
MAC BF-II BUTTERFLY
TERM. STRIP
PLASTIC PANEL

Fig. 4. 900 to 1120 MHz oscillator circuit.


+12
BIAS
DIODE DC OUT
−12
470
4.7k
2N2398
E
B
C
RFC 12 TURNS 1/8" DIA.
RFC 50 TURNS 1/8" DIA.
3/8"
SEE FIG. 6
FOLDED COPPER SHEET TAB
J1
NOTE
L1 & L2 ARE THIN BRASS 1" WIDE, 1-3/4" LG. (CLIP CORNERS)
L1
L2
C1 MAC BF-3
SUB-PANEL
GROUND PLANE
FRONT PANEL

Fig. 5. 1200 to 1300 MHz oscillator and layout.

In the microwave detector line, my experience indicates that the plunger tuned coax cavity line is the best, the tuned trough line next, and the circuit of Fig. 5 next best. As a dipper, generator and regenerative receiver it is still good at 1296 MHz. Just to check, I plugged an antenna into J1, put an audio amplifier across the diode and copied a small transistor oscillator across the room. The base bias control works as a very smooth regeneration control. Smooth regeneration, as we will see later, is very important for maximum sensitivity when looking for harmonics and weak signals.

1200 to 1300 MHz unit

Fig. 5 shows the 1296 unit; I have used this circuit for many months as a dipper, variable-frequency generator, modulated-oscillator source, and as a regenerative receiver for 1296. In this circuit I used a negative dc grounded collector return. Don't short the base plate to the modulator base. Note that one end of the diode is tied to the base plate; this lead is brought out as the minus 12 volt lead. You can also use it ungrounded as in Fig. 4—you can use a 5th lead in the 7-pin plug and keep the diode isolated from the minus 12 volts. Suit yourself, just remember that *all* units have to use the same leads, as they all plug into the single modulator rf unit.

I just plugged a little 12 element Yagi antenna into this dipper and it works nice and smooth as a regenerative receiver. Please note, this is only for test purposes around the shack. You can hear with it, but not *that* good!

I had to put a choke in the cathode lead on this one, and tune it (the choke) with a piece of copper foil. A choke was needed in the collector lead too; after all this is the L-band microwave region.

The rf input jack J1 is mounted on a bakelite upright. Be careful of vertical metal pieces attached to the base plate; they only need to be two inches long or so to become Marconi antennas on 1296! Bring the base resistor and the collector choke away from the lines in a perpendicular fashion—it helps.

The total length of the diode and it's two leads, from ground to the tiny .001 capacitor C2 is about 1½ inches; it is spaced about 3/16 from the ground plane. The bottom edges of the lines are about ½ inch from the ground plane.

The transistor presently in the unit is a selected 2N2398; about half of the dozen or so I have here go to 1300 MHz, a couple go to 1400, and the rest to 1100 or 1200.

Don't be alarmed that L1 and L2 are longer than those of Fig. 5, the smaller butterfly capacitor does that. You can make a choice as to capacity, length of brass, and desired rf range. You can use a 5 or 10 pF capacitor for C1, shorter lines, and tune over 1300 MHz. In fact, I have reached 1600 MHz with this circuit!

Modulation and control

Fig. 7 shows the circuitry for bias control, modulation and audio. Don't let it scare you. It's just the same old deal of doing what has to be done for control purposes, and from then on just turning the knobs to get what you want.

I have found that a very good plug and jack can be made by using an ordinary 7 pin socket and a Methode 7 pin bakelite plug. Unfortunately, I have never found a miniature tube with a bakelite base; they are always made of glass, so you will probably have to buy the 7 pin plug.

The minus 12 volt lead goes to the collector meter jack and then to the minus 12 volt of the power supply. This puts the rf panel ground at minus 12 volts and the audio af panel at plus 12. Of course, you don't have to ground the plus 12 on the audio panel, I just have that habit.

The base return goes through a 5K resistor and then to the bias control potentiometer. The diode dc/af output goes to af jack J2 and the meter M1 through the meter sensitivity control. This potentiometer is selected to suit the meter; I have used a 10 K unit with a 500 microampere meter. Note that part of this resistor should be used when af output is desired, otherwise the meter shorts out the af.

Audio modulation

You might think that just about everyone knows how to build an audio oscillator. Mine did oscillate, but the tone! And the wave-shapes, hoo-boy! I used an af transformer with the collector on one side and the base on the other. So, once again to the handbooks and once again practically zilch. I did get the idea for a phase shift oscillator out of one of them, even if the circuit didn't work at first. After considerable experimentation I can recommend the circuit shown in Fig. 7. It works! In addition, the modulation may be adjusted to exactly 1000 MHz. This is very useful as many microwave test amplifiers have built-in narrow band af audio filters centered on 1 KHz. There is also a modulation gain control. This helps if a nice tone is desired.



Fig. 6. RF detection loop for half-wave oscillators.



Fig. 7. Power control, modulation and audio circuitry. This circuit is used with all the rf heads.

Almost any small transistor output transformer will do the job for the af transformer, but don't go over 400 ohms impedance in the collector winding. Note the 1K resistor between the collector and the phase shift network; this reduces feedback to the base and may have to be increased or decreased depending on the gain of your transistor at 1000 Hertz.

I usually run the rf current (collector dc) between one and two mils with the 2N1726 transistors; other transistors may take more. A number 48 bulb in the collector lead may save you a $3 transistor. With the 2N1141 the rf output keeps climbing up to 4 or 5 mA collector current. You will readily find the best place to operate. When the collector mils keep climbing and the rf output starts to drop off, back off!

Operation

Dipper

As a general rule "dipping" is easier in the VHF region and gets more difficult as you go into the microwave region. On HF you couple one coil end on to the other; on VHF you bring it near, and on UHF you have to work to get the necessary coupling or use a probe.

With nothing near the dipper, swing the dial through the range to make sure it has no dips of it's own. The VHF/UHF units without chokes described here do not generally have such dips. Unwanted dips can be caused by chokes, resonant feed wire lengths, metal supports, and rf links and cables among other things.

When you do get a dip after coupling to the unknown circuit be sure and change the resonance of that circuit for a final check while watching the dipper meter. If the test circuit is a tuned circuit vary the tuning and see if the dipper will follow it—it *should*. If all else fails, use the dipper as a generator. Since it is very difficult to get the far end of a cable matched exactly over much of a frequency range, *expect* to find external dips in the dipper when using a cable.

Indicating frequency meter

Always keep the transistor plugged in and the base bias at zero so the diode is doing the work. When you advance the bias, collector capacity will cause the dipper frequency to change a little—more with some transistors than others.

For finding a weak signal you can use regeneration by turning up the base bias, but watch out for slight frequency changes. This regeneration can be very handy for finding weak oscillators or hard-to-find rf energy. Use the rf input loop with care; the least coupling is the best. Remember that some cables and terminations will detune L1.

Field strength meter and modulation monitor

The first part is obvious; use a small antenna or probe, get some signal in, and go ahead. Do not use any base bias to start with. If you are working with a very weak signal you might have to push the bias up for regeneration.

The modulation monitor is simply our often-described system of diode detector, transistor amplifier, and padded ear-phones. You can actually hear what your own transmitter sounds like to others. I use it on every new rig and after every circuit change. You don't need much of an antenna or probe when listening to your own rig; don't overload the diode when checking modulation. In fact, use light rf coupling and plenty of audio gain to hear yourself as others hear you.

Regenerative Receiver

Plug an audio amplifier into J2, Fig. 7, advance the bias control, and tune. I have heard several UHF TV stations from Massachusetts up here in Peterborough, so it is really sensitive. One nice feature of this circuit is that the regeneration turns into oscillation very smoothly. Stability is good too. You can heterodyne a crystal controlled two meter signal and copy CW with it. Not bad for a 144 MHz blooper!

To transfer signals from one transmitter (A) to another (B), just tune in A, then shut it off; listen for B and tune it in. That's all. Harmonic monitoring is easy: just tune over the suspected range in the regenerative condition. It is particularly good because only *one* frequency is present in the receiver. This is *not* the case when using a super-het receiver for monitoring harmonics.

Signal generator

One of the big features of this circuit is the presence of an rf meter right in the proper place circuit-wise. The modulation also helps, especially when running triple or quadruple conversion in a receiver. The modulation control is very convenient, at full on its spreads the signal across 20 or 30 kHz on a selective receiver. For checking a difficult to get at circuit, use a cable and probe, either capacitive or inductive, to get the signal into the unknown circuit.

I often use one of these units for antenna and receiver tests. I just plug a little two element beam into the rf jack and set it out away from the shack; often one or two hundred yards away. There is nothing like tuning up pre-amps with your antenna system connected. For antenna tests it is used in reverse.

EXTRA SERVICES FROM YOUR GRID-DIP OSCILLATOR

W. B. Cameron WA4UZM

One of the handiest instruments around the average ham shack is the grid dip oscillator, but many hams do not get all of the advantages this little instrument can offer. Most people know that it is useful for finding the resonant frequency of an LC circuit, or for generating a signal someplace in the range, although it is not quite a substitute for a well calibrated signal generator in this respect.

Many people do not realize that the grid dip oscillator makes an excellent crystal calibrator as well. The typical grid dip oscillator uses a two-terminal coil and a two-section variable capacitor, connected in the form of a Colpitts oscillator circuit, with the variable capacitor providing the voltage division for proper feedback. This same circuit, with a quartz crystal replacing the coil, becomes a very satisfactory crystal oscillator. In this case, the variable capacitor becomes a trimming capacitor capable of putting the crystal on the proper frequency with considerable accuracy and also allowing a fairly wide latitude higher or lower for checking bandpass.

The meter reading gives an index of crystal activity. What is required is an adapter to match the pins of the crystal holders to the coil socket of the grid dip oscillator. I have made up such an adapter for my particular unit which consists of a 1½ inch by 4½ inch piece of masonite which carries two banana plugs to insert into the oscillator socket, and several different sizes of crystal holders, all connected in parallel, to accommodate any crystals I happen to have around the shack. I carry in my tool kit various assorted crystals. These give me spot frequencies for band edges and other reference points on all of the amateur bands.



Crystal socket adapter for grid dip oscillator extends the unit's capability by enabling it to read crystal activity.

In checking the higher frequency bands, I find it useful to add a diode clipper and have one permanently wired on the same adapter board. This is a 1N69 which simply goes from one side of the crystal to a terminal point at which I can attach an antenna or a lead to the input jack of the receiver. By simply attaching a short length of wire approximating a quarter wavelength at this frequency, I can provide a strong enough signal from the shack to enable me to check out my direction finding loop in the automobile fifty feet away.

In tuning up my 2 meter FM gear, I plug in a 3061.25 crystal (which is the transmitter oscillator crystal for my Link 2m FM unit) and then couple from the 1N69 to the input of the receiver. This provides a signal stronger than most of the local signals on the band, and adequate for initial tune-up. For finer adjustment of the i-f strip, I clip the lead from the 1N69 to the chassis close to the antenna input jack and the leakage provides a signal of the order of .2 μV, which is useful for final adjustment of the critical tuned circuits, the squelch control, and others. For best results, I leave the oscillator and the receiver on for a half hour or so to warm up, and then with the variable capacitor in the grid dip oscillator, I zero-beat the incoming signal of a station generally considered to be on frequency. Once this is done, I have a signal source on the bench with which to check the receiver for passband balance as indicated on the microammeter connected to the discriminator output.

GDO TO FIND C

F. C. Rayer G3OGR

Most amateurs have a grid dip oscillator lying around, and an easy accessory can allow it to be used to read the values of unknown capacitances up to about 1000 pF. This is useful for unmarked surplus, those with obliterated markings, or to find the swing of small variables. Or we may check the best value found in some circuit position with a preset or variable, then measure this and substitute a near value fixed capacitor.

Figure 1 is the circuit. C1 and C2 are on the lid of an insulated box, carrying also spring terminals for CX. The capacitors have good knobs with pointers. Coil L can be half a dozen turns of stout wire, self-supporting, or anything which comes within a convenient range of the GDO (say 2.5–10 MHz) with both variables fully closed.

To calibrate, close C1 and C2 fully. Tune the GDO for the usual dip. Note the frequency on the box for future use. Take a few 1% capacitors, such as 100 pF, 200 pF, and so on, up to a total of about 1000 pF. Clip one to CX. Open C2 to restore the dip on the GDO. Mark the capacitor value on C2 dial. Series and parallel capacitors give more values. For example, 100 pF plus 200 pF in parallel gives 300 pF, while 500 plus 200 gives 700 pF, and so on.

Restore C2 to its fully closed mark. Repeat to calibrate C1, this time using capacitors such as 5 pF, etc., up to about 50 pF. When you see how the scales mark, estimate intermediate markings, to fill in.



Fig. 1. GDO to find C.

Once calibration is finished, it is easy to find a capacitance value from about 2.5 to 1000 pF. Close C1 and C2. Put the GDO near L and tune the GDO for dip. Clip the unknown capacitor across CX. Open C1 or C2, as appropriate, to restore the dip. Read off the value from the scale. That's all there is to it!

GDO COIL EXTENSION

Bill Turner WA0ABI

A grid dipper is a great piece of test equipment and belongs wherever rf equipment is to be designed, constructed, or serviced. All writings on the subject seem to be prefaced with this comment, and I hesitate to break tradition. Now that the formalities are over, we will proceed with the subject matter.

Probably the one most inconvenient feature of all grid dip meters is the physical size of the instrument. This holds true for the two unit commercial models as well as the more common self-contained types. It is not so much that they are large but rather that the head will not always fit into the nooks and crannies which seem to be designed into most equipment. This situation will more than likely become more severe as integrated circuits come into more general use. At lower frequencies the coil assembly is usually long enough to reach to within shouting distance of the desired circuit, but as the frequency is increased the dipper coil shrinks to perhaps an inch protruding from the case. Try getting this even near a circuit buried 2 or 3 in. deep in a chassis and you will fully appreciate the magnitude of the problem.

There is a way of relieving the difficulty which requires neither a great deal of time nor expense. It is only necessary to put to use some basic theory which each of us was required to know in order to get a ham license. Required are perhaps a 3 ft length of small coax (RG 174/U), 6 in. of hookup wire and a ballpoint pen casing. The innards of the pen are removed, and the business end reamed slightly to accept the ends of a ½ in. diameter one turn link formed of hookup wire. Inside the barrel of the pen the ends are soldered to the coax, insulated, and cemented in place. The remaining wire is formed into a 2 turn link which fits snugly on the coil form of your grid dipper. This link is soldered to the opposite end of the coax and secured. Shrinkable tubing is perfect to cover the joint.

The next time you face this perplexing problem hold your head high and fear not. Merely slip the link over the coil form, place your probe so as to allow coupling into the desired circuit and proceed as usual. The only difference will be a more or less fixed load on the oscillator which doesn't affect its ability to indicate resonance. As always, best results are obtained with minimum coupling.

Chapter VIII

Noise Generators

SIMPLE NOISE GENERATOR

George Rubis K9ONT

As anyone knows that has done any work at all on receivers, whether it is a conversion or simply substituting a "hotter" tube in the front end, we get to the point where we begin to wonder if the adaptation was worth while or have we been fooling ourselves.

A noise generator using one of the noise diodes (IN21 or IN23) can give an indication if any improvement has been made.

The circuit is straight forward, but with one addition that others that I have seen do not have. The voltage is regulated by a Zener diode.

The reason is obvious to anyone who has worked with the simpler type of noise generator. The results are not always consistent from measurement to measurement and from day to day. The voltage and current vary with the setting of the variable resistance and due to the normal aging of the battery.

The Zener Diode eliminates this by maintaining a constant line voltage. In our particular instrument it is six volts. Of course we must use a battery in excess of six volts. Nine volts is a good value. I have found that used transistor radio batteries still have enough life in most instances to last for many tests.

One of the main requisites of a noise generator is that it must be shielded throughout. Therefore we must give some thought as to the placement of the various components.

A Mini-box 2¼ x 2¼ x 4 is an ideal size. As for a connector I used the SO-239 coaxial. I find that this connector allows more flexibility than any other. If a direct connection to the receiver is desired merely attach it through the double connector type DKF-2 made by Dow Key. On the other hand if it is desired to have the controls of the noise generator close at hand merely connect a length of Coax of eighteen inches or so. I haven't been able to discover that it has affected any measurements to any degree.



To avoid excess wear and tear on the zener diode and the battery a 200 ohm resistor should be inserted between the 9 v battery and S1.



In the construction of this noise generator just remember a few basic rules. Keep all connections as short as possible. The noise diode and bypass condenser and resistor (50 or 75 ohms as the case may be) as close as possible to the output plug. Remember to use pliers to absorb the heat when soldering the leads of the diodes.

To mount the silicon diode, which has one large end and one small, we must improvise to a certain extent. For the small end a lug from one of the old tube sockets will do. For the large end use a small fuse clip.

Don't be too fussy about the variable resistor. For most purposes any value from 10M up to 50M can be used.

The battery you choose will determine the manner of mounting.

No need to give detailed instructions as to the use of this noise generator. There are ample instructions to be found in various magazines as well as handbooks.

. . . K9ONT

Parts List

2—¼ x 2¼ x 4 Minibox
Bt—9 volt battery
Cr1—6 Volt Zener Diode
Cr2—IN 21 or IN 23 Silicon Diode
R1—10M-50M Variable
R2—51 ohm or 75 ohm (according to your line)
C1—.001 to .005 disk ceramic
S1—S.P.ST. this may be on your variable resistance
P1—So-239

A CRYSTAL DIODE NOISE GENERATOR

Karl Tipple W5TEV

Most amateurs who do very much operating at the higher frequencies where receiver sensitivity rather than QRM often determines success eventually come to the conclusion that their present receiving equipment is not as sensitive as would be desirable and that a change is in order. And once that change has been made, whether it takes the form of a new converter or modification of existing rf stages, one nearly always wonders whether the new really *is* better than the old. Comparisons of signal strength with new and old equipment are erratic and unreliable at best and do not necessarily give the desired information since the absolute output level or "S" meter reading is not the problem. What is actually of concern is whether the signal to noise ratio of the receiving system has been improved. Or in other words, does a given rf signal produce an audio output signal from the new receiving equipment that is louder in comparison to the background noise than did the same input signal with the original receiving equipment. If it does, the noise figure of the new receiving equipment is smaller (better) and it should be possible to copy a weaker signal than before.

Unfortunately few of us own or have access to a signal generator of the proper frequency range, with an accurately calibrated attenuator and shielded output, for making the type of measurements mentioned above. For the majority of amateurs something less expensive and more readily available is needed. A crystal noise generator, which can be constructed for a few dollars and which will enable anyone to make before and after comparisons of noise figure, is such a device.

Briefly, the theory behind the use of the noise generator follows. The sensitivity of a receiver is highly dependent on the ability of the rf stages to amplify a weak signal as much as possible while adding a minimum amount of noise to the signal. Noise of this type will



RI = 10,000Ω POT-- LOG TAPEP PREFERRED
R2 = 1/2 WATT NON-INDUCTIVE RESISTOR EQUAL TO LINE IMPEDANCE

FIG. I



be heard at the receiver output as a familiar hiss or "rushing" sound. Now, if an external source of broadband or white noise (random noise independent of frequency) is connected to the receiver antenna terminals, an increase in noise or hiss will be noted at the receiver output. And if the noise generator output is adjusted to provide exactly twice as much receiver output noise as existed before the application of the noise generator, then the generator must be providing a noise signal equal to that generated in the receiver. Thus, if the receiver can be modified so as to reduce the noise generator signal required to double the receiver noise output, the noise figure of the receiver will have been improved.

A noise generator of the type described in this article can not be used for measurement of absolute noise figure without additional calibrating equipment. It can, however, be used for *comparison* of noise figures. It enables one to determine whether a receiver really has been improved and it can be used to determine which of a number of possible modifications will yield the best results in terms of minimum noise figure (maximum sensitivity). Use of the device will be discussed in more detail later.

A basic noise generator circuit is shown in Fig. 1. The noise is produced by CR1, a silicon diode of the 1N21 or 1N23 variety. These diodes have been widely available on the surplus market for several years. They are also readily available new at small cost; however as will be explained later, it may be desirable to use a surplus diode rather than a new one.



FIG. 2

R1 = 10,000 ohm pot—log taper preferred
R2 = 1/2 watt non inductive resistor equal to line impedance
Other parts same as Fig. 1

The current supplied to the diode from the battery and therefore the noise generated by the diode is determined by the setting of R1. The best value for R1 is necessarily a compromise since in its maximum resistance position it must limit the current to a low value but it must also not change resistance too rapidly at the low resistance end of the range or the normal operating range of the instrument will be limited to only a few degrees rotation of the R1 shaft. A 10,000 ohm log taper pot should prove satisfactory.

The value of R2 should be about the same as the transmission line impedance. A good value might be 56 or 68 ohms, although if it is desired to use the noise generator with equipment which normally operates from higher impedance lines, a larger value should be selected for R2. In this case one might compromise with a value of 100 ohms. C1 serves as bypass capacitor and may be either mica or disc ceramic.

A more elaborate arrangement was used in the construction of the unit shown in Photo. 3. A schematic of this generator appears in Fig. 2. Here a tapped battery (2 pencells) was used to minimize the range to be covered by R1. It should also be noted that the diode is shown reverse biased in Fig. 2. Many of the surplus diodes available have very poor reverse resistances, which will allow reverse bias operation, and when operated under these conditions will generate considerably more noise for the same bias current than when operated in the more conventional configuration shown in Fig. 1. The diode must have a reverse resistance of only a few thousand ohms or less if it is to work successfully in the reverse bias connection. Therefore unless the reader can obtain some surplus diodes and select one with a low reverse resistance, it will probably be necessary to operate the diode forward biased and to use the higher battery voltage of Fig. 1.

The meter range depends upon the battery voltage and the resistance of the diode in whichever connection it is used. The meter used in Fig. 2 was a 0-4 ma surplus meter. However, if the diode is operated in the forward biased connection a meter of somewhat higher current rating will probably be needed. Therefore, it is suggested that a low range meter be obtained and if more than full scale current is required for the diode to develop sufficient noise, a shunt resistance can be placed across the meter terminals to extend the meter range. An inexpensive meter can be used since all that is needed is a relative indication of current.



FIG. 3

For those not familiar with the IN21-1N23 type diodes it might be mentioned that they have no wire leads. The anode connection is a brass shell on one end of the unit and the cathode connection is a brass pin at the other end. Although external connecting wires might be soldered to the brass ends, there is danger that the diode will be over heated and destroyed by such techniques. It is safer to make connections by clamps made from small plate or grid caps or fahnstock clips.

It should be evident from the above discussion that there is nothing critical about the construction of a noise generator of this kind and that a number of different circuit variations are possible. Even if the device were constructed entirely of new components the cost should be less than $8 and with a little ingenuity the cost can be reduced substantially through the use of surplus parts.

Perhaps use of the noise generator can best be illustrated by considering an example of noise generator application. Suppose that you want to use either one of two available 6 meter converters with your low band receiver and that you wish to determine which converter will provide the best weak signal reception. A test set-up is shown in Fig. 3.

The ac voltmeter is used to measure the audio output of the receiver and may be either a multimeter or a VTVM. It can be connected across the speaker terminals or across the headphone line. Higher voltages can generally be obtained from the headphone output and this connection will probably have to be used if a multimeter without a very low ac range is used.

The measurements can be started by measuring the ac noise output voltage from the receiver with the noise generator turned "off". Then the noise generator should be turned "on" and the generator level adjusted until the output meter reading has doubled. At this point a note should be made of the noise generator setting. The above procedure can now be repeated with the second converter connected to the receiver. Whichever receiver-converter combination requires the smaller noise generator current setting to double the noise output is the combination that will provide the best weak signal reception.

The noise passed by the receiver is a function of the bandwidth of the receiver. Also the reading given by a particular output meter is dependent on its bandwidth. Therefore the bandwidth of the receiver should not be changed during measurements and the same output meter should be used thoughout a set of measurements.

The technique described above can also be used to determine which of a number of rf amplifier tubes will give the best performance. The noise generator can be used for alignment of rf stages.

For the man who constructs his own converters or receivers the device is a tremendous boon since such adjustments as determining the optimum antenna to grid coil coupling can be made simply by adjusting for maximum increase in noise when the generator is switched "on". (This technique gives the same results as adjusting for minimum noise generator setting to double noise output and it is a bit easier to use when adjustments must be made.) If the input circuit uses a single tapped coil instead of two coils, the best tap position can be determined.

The uses mentioned above are only a few of the possible applications of this noise generator, and for the amateur who constructs his own receiving equipment the device is indispensable.

TEMPERATURE LIMITED DIODE NOISE GENERATOR

F. L. Thomas



Recently I was confronted with the necessity for a good noise generator. All of the noise generator designs available in any of the amateur publications at hand were of the crystal diode type. The disadvantage of this type of instrument lies in the fact that the current through the diode has no simple relation to the noise output. Unless expensive calibration equipment is on hand this type of generator is useful only on a comparative basis. Consequently it was decided that a temperature limited diode noise generator would be built.

The noise output of a temperature limited diode noise generator is simply related to the current flowing through the diode.[1] The noise figure of a receiver may be calculated directly from the magnitude of the current by the following equation:[2]

Noise figure in db.$=10 \log (20 \text{ I R})-(1)$

Where I=current through temperature limited diode required to make the noise output power of the receiver double the value it was with no current through the diode.

R=antenna impedance

The actual noise generator is quite simple, consisting of half a 6AL5 with a milliammeter in the cathode leg and the appropriate resistance for the antenna circuit connected to the plate by means of a selector switch. The heater current is controlled by a 20 ohm potentiometer in series with the heater. The unit is battery operated for convenience. High current capacity, small sized mercury cells are used throughout. The whole unit is contained in a 3" x 4" x 5" Minibox.

Construction

The resistors are mounted on the switch, making the leads as short as possible. The tube socket is mounted on a small bracket screwed onto the side of the chassis, placed so that the distance from the switch is a minimum. The meter calibration potentiometer and the heater supply battery holders are mounted on another bracket placed over the meter as shown in the photograph.

Operation

To use the generator it is connected to the receiver antenna terminals, the AVC is turned off, and the audio output is measured with the generator off. The generator is then turned on and the current through the diode is increased until the power output is double what it was before. At this point the voltage output will only be 1.41 times the original. The current necessary to give this noise increase is noted and the noise figure calculated according to equation (1), or estimated from the figures given in Table I.



B1—four Mallory RM12 or RM12R in series (lifetime of this circuit should be greater than 10 operating hours)
B2—Mallory TR-135R
M—0-1 ma (Lafayette TM-60 or equivalent)
R1—20 ohm potentiometer
R2—20 ohm Potentiometer
J1—coax connector
S1—DP 5 pos miniature rotary switch

Noise Figure in db.	Current, ma., for antenna impedance of:			
	50Ω	72Ω	300Ω	600Ω
2	1.40	1.15	-	-
4	2.25	1.80	0.42	-
6	3.55	2.85	-	-
8	5.65	4.50	1.05	0.53
10	8.85	7.15	-	-
12	14.2	11.3	2.65	1.32
16	-	-	6.65	3.30
20	-	-	16.6	8.42

The unit described is useful for noise figures up to 13 db at 72 ohms. For higher noise figures a higher current capacity diode and a higher heater voltage and current supply is required, necessitating an ac operated power supply. With a suitable power supply a 6X4 may be satisfactorily operated up to a noise figure of about 22 db. In both cases the maximum noise is obtained by passing more than the allowable average current through the diode. Consequently readings at these extremes should be made and the current lowered again in only a few seconds, or damage to the diode will result.



Table I shows the current readings for various noise figures with different antenna impedances.

The generator will operate satisfactorily up to at least 50 mc, and probably considerably higher.

Editor's Note: By substituting flashlight batteries for the mercury cells and a 20 mA meter instead of the 1 mA meter with a shunt across it, the cost of construction can be greatly reduced.

REFERENCES

1. **Radiotron Designers Handbook**, fourth edition, page 1307, reproduced and distributed by RCA Victor Division, Radio Corporation of America, Harrison, N. J., 1953.

2. **Radio Engineering Handbook**, fifth edition, page 19-10, Edited by Keith Henney, Published by McGraw-Hill Book Company, 1959.

3. Terman, F. E., **Electronic and Radio Engineering**, fourth edition, Published by McGraw-Hill Book Company, 1955.

CALIBRATED NOISE GENERATOR FOR 432

Hank Olson W6GXN

As pointed out in previous articles—the temperature-limited noise diode is the best tool for measuring the sensitivity of one's receiver. The measurement made with this device is "noise-figure" or "noise-factor" and this is the magic number by which you can compare your VHF or UHF receiver with Joe's down the street, or Sam's in Massachusetts. These measurements will be comparable between any two receivers because bandwidth, type of detector, and other miscellaneous features (different for each receiver) do not affect the measurement, if it's carefully made (that is, if one's measurement of 3 db power increase, when the diode is turned on, is true).

Past amateur articles on noise-diodes and their use in noise-factor measurement have only shown how to construct units for up to about 200 mc. The noise generators described previously, for amateur use, have used the 5722, the diode wired 24G (3C24), or the diode wired 801A, as their tungsten-filament diodes. The 15E and 01A have also been used occasionally as diode-wired triodes, too. Commercial UHF noise generators use a variety of tungsten-filament tubes, all of which are a bit expensive for most hams. If you can lay your hands on one of these tubes, used or otherwise surplus, by all means employ it in your noise generator. Table I is a list of such gems.

Philco:	L1262A
RCA:	R6212
Bendix:	6144
Marconi:	CV2171

Table I

The tube I used is a triode, a Western Electric 708A, originally designed for grounded-grid UHF amplifier service. The grid and filament are used as the diode elements, ignoring the plate altogether; the plate, if used, could only increase transit time and shunt capacity. The tube is used, as it was intended to be used, with the metal shell (grid) grounded. The 50 Ω load is connected in the filament circuit; the filament power is fed in by means of a concentric inductor, which also tunes out the stray capacity of the tube.



RF Circuitry.



Fig. 1. Power supply.

C_1, a small "tweaker," adds in a tiny additional capacity to make adjustment to 432 mc easier; it makes tuning to anywhere in the 420 to 450 mc band possible. L_1 is constructed of a 1⅞″ length of ⅛″ copper tubing and has a piece of No. 20 teflon insulated wire inside it. The use of teflon insulated wire is only necessary because teflon will withstand the heat of soldering.

The effective circuit, then, is as in Figure 2.

At 432 mc, if $Cgk + C_1 = 3$ mmfd, then L must be 0.04 μh to be parallel resonant. The reactance of either $Cgk + C_1$ or L_1 is about 100 Ω, so the system has a Q of ½, and hence will be rather broad in its noise output spectrum—just as we want it to be.

The WE 708A tube was recently available from a Los Angeles surplus emporium at the price of 39 cents each or ten for a dollar. We bought a buck's worth, figuring some would be NG, but all were perfect and saturated well. One was lost in initial test, when we applied too much filament voltage; it was subsequently hack-sawed open to find out the details of its construction and to confirm connections. The details learned are presented in Figure 3 along with its saturation curve.

The filament is a single, fine, straight, tungsten wire through the grid helix. The grid helix is perhaps 1/16″ diameter and is welded every turn to the shell. All this adds up to: good cylindrical diode configuration, close cathode-grid spacing to cut down transit time, and low grid to case inductance. In short, we have a nearly ideal noise diode for a dime a piece.

Construction details: The rf section of the generator is constructed on an aluminum plate bent into an L, the WE 708A protrudes through a 1⅞″ round hole to expose its filament pins next to where the UG58A/U connector is mounted on the other side of the L. The WE 708A is held in place by five 8-32 binding-head screws that are tapped into the plate. The UG58A/U has four 200Ω, ½ w resistors soldered to it each at 90° to its neighbors to form a less inductive load, approximating a resistive sheet. These resistors are soldered to the UG58/U before it is mounted to the aluminum sheet to make soldering easier (less heat required). Then L_1 is formed and soldered from the WE 708A filament pin to C_3. The center filament lead of L_1 is fed through and soldered to the other filament pin and to C_4. C_2 is then soldered in; be sure this is the type called for or a similar low inductance stand-off ceramic. The rest is straight forward. Diode and power supply were each built in an LMB 141 box chassis. The details of wiring the diode circuitry are shown in Fig. 4.



Fig. 2. Basic noise generator circuit.

A word about R_1 (the "fine" adjust) is worthwhile. Make *sure* this one is a 2w type A.B. (ohmite) molded carbon pot, if not both R_1 and R_2. This will make smooth diode-plate current adjustment easy; a wire wound pot will cause the plate current to vary in steps because of the effect of the pot's sliding contact sequencially contacting each wire (the same applies if you use a Variac).



FIG 3

Fig. 3. Connections of 708A and graph of relationship between "plate" current and filament voltage.

To align on 432 mc, C_2 is temporarily removed and a UHF grid dip meter coupled to L_1, loosely. C_1 is adjusted for a dip at 432 mc. Then C_2 is reinstalled, and we should be ready for receiver checks.



Fig. 4. Circuit of diode noise generator.

The above noise generator was compared with a Hewlett Packard 343A noise diode using my own 432 mc converter as the "to be measured" device. The results showed less than 0.5 db difference.

The author wishes to thank Gene Howell, W4RLU, for his photography of the unit.

ANOTHER WAY TO MEASURE NOISE FIGURE

Jim Kyle K5JKX

Many times it's been said, but it can always bear repeating. Noise figure is probably the least-well-known measurement in any amateur station.

At least a part of the difficulty with noise figure lies in the means usually employed to measure it. While it's not too difficult to figure out the power input to your final, or even the power *output* (often a surprisingly different figure), measurement of receiver noise figure tends to be a complicated and somewhat inaccurate process at best. It requires special equipment, and even then may be no more accurate than plus-or-minus 100 percent.

The classic means of measuring noise figure is to use a noise generator and crank in additional noise until receiver output is doubled. This means, of course, that the noise generator output is then exactly equal to the original noise, and if the noise-generator output is accurately known then the original noise is also known. All this has been gone into in detail in another article.

However, a noise generator with accurate calibration isn't so easy to come by, and an inaccurate noise generator doesn't do much good for measurement purposes (although it's fine for tune-up).

There *is* another way to do it, which is actually much more in line with amateur practice. This other way also requires some test equipment, but it might be more easy to come by.

Before we get into the details of the "other way" to measure noise figure, let's take another look at the reason for using noise-figure measurement as a yardstick for receiver sensitivity in the first place.

To start, we're really interested in the answer to the question "How weak a signal can I hear?" In the 3-30 mc range, the question can be answered directly—how many microvolts must the receiver have to give readable output?

As the vhf region is entered, though, the fractional microvolts become alarmingly small.



DB Loss	R1, R2	R3
3	8.2	150
6	16	68
9	24	39
20	39	10

All resistors composition, ½ watt, 5%

Fig. 1. Construction of T-pads

Somebody figured out that most of the problem lay in the receiver's own internal noise, and came up with the idea of a "perfect" receiver which would have no noise at all. This is a noise figure of 0 db. Now by comparing existing receivers to this perfect ideal, and comparing the internal noise in db, we had a way of discussing receiver sensitivity.

Since we're now talking about noise, which is equally present at all frequencies throughout the spectrum, we can see that the amount of noise present in a receiver's output is at least partially determined by how much of the spectrum we are looking at. A broad receiver has more noise output than a narrow one, all other things being equal. If you don't believe it, fiddle with the selectivity switch on your own rig and listen to the change of noise output.

This dependence of noise on bandwidth is another reason for using noise figure as a comparison. The *actual* amount of noise is cancelled out in the comparison, leaving only the relative amounts of noise in the "perfect" receiver and the receiver under test to be measured.

When all this became established, nobody was paying much attention to receiver bandwidth and it was felt that a true determination of the effective noise bandwidth of a receiver was much more complicated than the comparison measurement. However, in these days of SSB and special filters, that's not so true any more.



Fig. 2. Test set up.

As you may have guessed by now, the "other method" of determining noise figure depends on a microvolt measurement and knowledge of the receiver's effective noise bandwidth. The only reason for converting the results back to noise figure is to allow comparison with measurements made in the more conventional manner.

With typical ham measurement techniques, the results won't be of National-Bureau-of-Standards accuracy. However, if you're reasonably careful, results using this method will be at least comparable in accuracy to those made with a homebrew noise generator. Ready? Let's go:

You'll need two items of test equipment (only one if you're really lucky). These are an rf signal generator covering the desired frequency range on fundamental output, and an rf VTVM reasonably accurate at the desired frequency. If you have access to a "microvolter" or similar laboratory signal generator, you won't need the VTVM.

In addition, you'll need a whole handful of 50 ohm T-pads; these can easily be put together in a hurry by following the schematic in Fig. 1. You'll probably need about 8 20-db pads, as well as one each in 3-db, 6-db, and 12-db values.

Turn on both the receiver and the signal generator and let them warm up. For protection against any leakage from signal-generator to receiver through the power lines, it's best to supply them from separate circuits and to use a power-line filter such as that used to eliminate rf interference between the power line and the unit.

Connect a string of six 20-db pads to the signal-generator output as shown in Fig. 2, and adjust output of the signal generator to 0.1 volt. If you have a microvolter or equivalent, use only one 20-db pad and set generator output to 1 microvolt.



Fig. 3. Noise figure vs. microvolts.

In either event, the output of the final T-pad will be a 0.1 microvolt CW signal. This should be more than adequate for any reasonably-sensitive receiver to allow spotting of the signal.

Switch the receiver's avc off and the bfo on, and place the selectivity switch in any position for which the selectivity is accurately known. The selectivity marked on the front panel will not be the effective noise bandwidth, but you can use it as a starting point to guesstimate the noise bandwidth. If your receiver uses a mechanical filter or other device with approximately the same skirt selectivity, effective noise bandwidth will be about 1½ times the bandwidth marked on the front panel. If it is one of the older types with reasonably broad skirts, noise bandwidth will be about 3 times the marked value. Both these correction factors are approximate, of course; if you have any means of measuring effective noise bandwidth, use it instead.

For a start, use a fairly broad selectivity position; this requires more signal and makes things a bit easier.

Now tune in the signal from the generator, leaving gain controls at maximum but tuning for maximum signal strength just as if it were the new state you need. The 0.1-microvolt signal should be easy to find.

Next step is to reduce the generator output by hooking in additional T-pads until you locate the point of "minimum discernible signal." The 3, 6, and 12 db pads may be hooked up in series in any combination to give you from 3 to 24 db additional attenuation in 3-db steps. Using another 20-db pad will give you from 20 to 44 db more attenuation, and the signal is sure to become too weak to copy before you reach 44 db below one-tenth of a microvolt!

The point of MDS is approximately equal to a 0-db signal-to-noise ratio for most of us, and is considerably easier to determine than would be a true output S/N ratio. When you find this point, record the db below 0.1 microvolt and the selectivity (in kilocycles) used.

Now switch to a different bandwidth on the receiver and repeat the test. Record its results also. For maximum accuracy, repeat each of the tests 10 to 12 times and average the result.

The signal level in microvolts corresponding to db below 0.1 microvolt is given in Table I. Locate it there and move to Fig. 3, the graph of signal versus bandwidth by noise figure.

Enter the graph from the side with effective noise bandwidth, and move across until you intersect the line corresponding to signal level in microvolts. The diagonal lines are noise figure; if one passes through the intersection point, read noise figure in db from it. If not, interpolate between the lines.

In reading Fig. 3, use the 10 kc-100 cps scale with the .01-.1 microvolt scale, and the 100 cps-1 cps scale with the .001-.01 microvolt scale. If your bandwidth-signal level combination falls off the graph to the left, use the *lower* signal-level scale with the *higher* bandwidth scale and subtract 20 db from the resulting noise figure.


EFFECTIVE NOISE BAND WIDTH
A
B
C
PERFECT CURVE
$BW_{NOISE} = BW_{SIGNAL}$
GOOD CURVE
$BW_{NOISE} \approx 1\frac{1}{2}\ BW_{SIGNAL}$
AVERAGE CURVE
$BW_{NOISE} = 3 \times BW_{SIGNAL}$

Fig. 4. Relation of noise and signal bandwidths.

In the happy event that all your errors (and our approximations) cancel out, you'll find the noise figure to be the same at both the narrow and the broad bandwidth positions. However, it's more likely that you'll measure different noise figures at different positions of the selectivity control. It's safest to take the highest noise figure measured as being closest to correct, but you can average them if you prefer. Either way, you will probably be within 1 db of the real figure—and this is as accurate as most noise-generator techniques can be, also.

That completes the measurement, but before we wind this up let's take a more detailed look at the idea of "effective noise bandwidth" which is such a key part of this measurement technique.

Most of us are familiar with the idea of a "perfect" curve for receiver selectivity such as that shown at A in Fig. 4. Here the receiver has equal response over the desired band, and response drops to zero at the band edge. Such a curve is said to have a shape factor of 1, and is of course impossible to achieve in practice.

Now back to noise; it's spread out equally over the spectrum. A noise bandwidth of 1000 cycles per second contains 10 times as much noise as one of 100 cps. Thus "noise bandwidth" inherently has a shape factor of 1.

Since such a shape factor is impossible to achieve, it follows that "noise bandwidth" and actual receiver bandwidth must differ. If receiver bandwidth is measured at the —60 db points, the noise bandwidth will always be smaller than this receiver bandwidth. If receiver bandwidth is measured at the points where response drops 1 db below peak, the noise bandwidth will always be greater.

The mathematical expression for noise bandwidth is an integral equation involving differential gain, which is a cumbersome thing to solve. In general, the noise bandwidth of a receiver is said to be approximately equal to the bandwidth between points which are 3 db down from peak response.

In practice, if the shape factor (6 to 60 db) of the receiver is 2, the effective noise bandwidth will be approximately 1.3 times the 6-db bandwidth. If shape factor is between 2 and 10, noise bandwidth will be approximately equal to the square root of the shape factor (6 to 60 db) times the 6-db bandwidth. Few receivers have shape factors greater than 10.

db BELOW 0.1 MICROVOLT	MICROVOLTS
3	.07
6	.05
9	.035
12	.025
15	.018
18	.013
20	.01
21	.009
23	.007
24	.0063
26	.005
29	.0035
32	.0025
35	.0018
38	.0013
41	.0009

Table I.

The approximations quoted earlier (1.5 times marked bandwidth for SSB-selectivity receivers, 3 times marked bandwidth for others) are based on these relations. If you're really interested in calibrating your receiver's noise bandwidth for using this measurement technique, however, you might take a converter and have it measured for noise figure by the generator technique, then run this technique backwards to determine the effective noise bandwidth of your receiver in each position of the selectivity control.

The technique described here, incidentally, assumes that no audio filters are used following the detector. If they are, all results are off, since the effective noise bandwidth will have been changed in an unpredictable manner by the audio filters.

However, you can remove the audio filters from the hookup for measurement purposes, determine noise figure, then return the audio filters to the circuit and run the measurement backward to find out your effective noise bandwidth with filters present. Don't be surprised if it comes out in the region from 1 to 10 cycles per second; a good audio filter can work wonders with weak-signal reception.

For additional details on this technique of measuring noise figure, you can consult Reference Data for Radio Engineers, 4th edition, published by IT&T and available from Radio Bookshop, or any good radar text.

Chapter IX

Attenuators and Dummy Loads

LOW POWER ATTENUATORS FOR THE AMATEUR BANDS

George Daughters WB6AIG
Will Alexander WA6RDZ

In the evaluation of rf amplifiers, filters and many other devices, a variable attenuator is indispensable. This article describes attenuators built and tested by the authors. These attenuators are flat from dc to over 50 MHz and usable to over 450 MHz. They use low cost parts, are very simple to build, and are more accurate than ordinarily required in amateur applications.

The basic attenuator section is the symmetrical pi shown in **Fig. 1**. Resistance values are given by the relations:

$$R_1 = R_s\,(\sqrt{K} + 1)/(\sqrt{K} - 1)$$
$$R_2 = R_s\,(K - 1)/(2\sqrt{K})$$

where R_s is the characteristic impedance of the pad (equal to the source and load impedance) and K is the attenuation factor, P_{in}/P_{out}.

Resistor values for the most commonly used impedance (50 ohms) are shown in **Table 1.**



Fig. 1. Basic pi-network attenuator section.

Nominal atten-uation in dB	R_1 in ohms	R_2 in ohms	Calculated atten-uation in dB	Measured atten-uation in dB
1	910	6.2	1.1	1.1- 1.2
2	430	12	2.1	2.1- 2.3
3	300	18	3.0	3.2
6	150	39	6.2	6.3- 6.6
10	91	68	10.2	9.6-10.1
20	62	240	19.6	19.5-19.7

Annenuation measured at 50 MHz and lower.

Table I. Resistor values for 50-Ω attenuators.

Notice that the use of standard value 5% half watt composition resistors allows accuracy within 1 dB of the calculated value of attenuation and within 1 dB of the desired nominal value.



Amateur low-power attenuator made from inexpensive slide switches, 5% resistors and fiber glass, copper-clad board.

The attenuators are built in small channel boxes made of copper-clad etched circuit board material. Aluminum channel boxes commercially available would probably work equally well. Small, inexpensive DPDT slide switches (H. H. Smith No. 518 cr equivalent) are soldered directly to the copper board and the resistors are soldered to the switch terminals (which have been cut short) with the shortest leads possible.

Two wiring variations have been tried, one with the series resistors (R_2) mounted between the switch wiper contacts (type B), and one with all resistors connected to the attenuator in terminals (type A). See **Fig. 2** and the photo of the interior of the attenuator. It was found that the latter arrangement, type A,



Fig. 2. Two types of attenuator construction. Type A has lower insertion loss than type B at high frequencies, so A is recommended. Resistors R1 and R2 are 5% composition, ½ watt. The switches are H. H. Smith 518 or equivalent. The connectors can be of any type to suit.



Details of attenuator construction. The top style, with complete shielding, is recommended.



Fig. 3. Insertion loss versus frequency for the two types of attenuator construction: all sections shielded (A) and only the 20 db section shielded (B).

provided less insertion loss than the former at high frequencies, so this type of construction is recommended. Also note that dividing shields are desirable between input and output elements of a single section. These shields prevent capacitive feedthrough at the high frequencies, and are desirable on the high attenuation sections (anything over 10 dB) even at low frequencies. On the low attenuation sections, very little difference is evident below VHF. See **Fig. 3** for the attenuation of the attenuators up to over 450 MHz. Building attenuators with greater than 20 dB attenuation per section by this method is not recommended for high frequency use.

S-UNIT ATTENUATOR

Ed Lawrence WA5SWD

Since the topic of "S meters" is a popular one among radio amateurs, a lot of time is spent describing these devices, usually along the lines of how generous or "Scotch" the meters are at the QTH of the parties in the QSO. After a few such QSO's, I decided to build an attenuator, calibrated in "S" units. My aim was to attain an accuracy of 1 db or better, using 5% ½w resistors and simple construction so it would be easy to duplicate.

As a sidelight, I started out by calculating both "tee" and "pi" pads, and used "pi" because all values of resistance are close to standard values, but (especially for high attenuation pads) the values for "tee" pads can get quite small; and expensive.

I figured the values required from the tables in the Allied's "Electronics Data Handbook", page 8, 5th edition. (Allied Radio, 75c, full of good info.)

Since "S" units are supposed to be 6 db, I figured data for steps of 1,2,4 and 8 times that amount, or 6,12,24 and 48 db. With these steps, any number from 0 to 15 "S" units of attenuation could be selected. However, 8 "S" units proved to be too much for one step, as shown by the lowered attenuation at 30 MHz, due to the inherent shunt capacitance of the resistor used in the series leg, plus the stray capacitance of the switch. So I removed the 8 "S" unit step and installed another 4 "S" unit step. This allows selected steps of attentuation from 0 to 11 "S" units.

Here are the values I calculated, and the actual values used, based on 51 ohms. The steps are switched in series, as required for the desired attenuation.



Looking inside the attenuator.

Resistance Values for 51 Ohm Attenuator:

		R1		R2	
"S" units	DB	ideal	actual	ideal	actual
1	6	154	150	38	39
2	12	85	82	96	100
4	24	58	56	405	390
8	48	51.5	51	6400	6800

After the attenuator was completed, the attenuation was measured at 3 kHz and at 30 MHz. With the test equipment available it was possible to measure more accurately at 30 MHz than at 3 kHz. Below is the data from the tests.

Atten Step "S" units	DB	Predicted atten DB	Measured at 3 kHz	Measured at 30 MHz
1	6	6.2	6.0	6.02
2	12	12.3	12.2	12.16
4	24	23.3	24.2	24.05
8	48	48.5	47.5	39.11

Now if we want to make an educated guess as to how far up we can expect good results, say 1 db error out of 24 db, then we can use the measured error in the 48 db step to calculate the capacitance across the series leg, and from that calculate the frequency where the 1 db error will occur. Go through the math if that is how you get your kicks, or take my word for it. It comes out to about 2 pF. And this will cause a reduction of 1 db at about 220 MHz. And since the resistor is of a lower value for the smaller steps, they should hold their values to even higher frequencies, but I expect other factors would get into the act along the line somewhere. I will state that still works well at 2 meters.



Fig. 1. Diagram for one step in the attenuator.

If you want to get fancy, you can always figure the values for 1, 2 and 3 db steps and have from 0 to 72 db attenuation in 1 db steps.

Referring to the photos; you can see I built my attenuator in a Bud Minibox CU-2102-A, 4" X 2-1/8" X 1-5/8". Four steps is the maximum in this size box, unless different switches are used. Mine are Cutler-Hammer 7592K6. The shielding was made from transformer strap, but could be any soft copper available. Try a Hobby Shop and get the thin sheet that is used for embossing if all else fails.



Front panel showing the switches for the various steps of attenuation.

Here are some of the uses an attenuator of this type is suited for:

Checking receiver "S" meter calibration.

Attenuating signals to aid in peaking receivers and converters.

Calibrating diode voltmeters for *rf* measurements.

Checking antenna gain. Or gain of that outboard *rf* stage.

P. S. My "S" meter lies, just as I thought!

THE EVER-USEFUL T-PAD

Jim Kyle K5JKX

Most of us have transmitters; let's hope that an equal number of us have receivers also. Antennas and microphones are usual station accessories, with a few determined diehards here and there clinging to the trusty old key. But how many of us have much in the way of test equipment?

Now and then somebody pops up with a VOM, and occasionally you can even find an operator who uses a scope. But the kind of special-purpose test gear you find in a well-equipped laboratory is almost always absent in the ham shack.

Which is more or less as it should be, since we're hams, not laboratory technicians. But with the present trends toward VHF, at least some specialized test gear is necessary. Otherwise, the regular station equipment can't be tuned for maximum performance.

One of the simplest such items is a noise generator, for getting the VHF receiver in perfect tune. This gadget has been described many times before, so we won't repeat it again —but we do have something which transforms the usual noise-generator lashup from a so-so item to an instrument capable of laboratory accuracy.

Before going into detail, let's look at the normal method of using a noise generator: you connect the generator to the antenna input, tie the converter to the receiver, turn the avc off, connect a voltmeter to the detector load resistor in the receiver (or put an ac voltmeter across the speaker leads), and measure the voltage produced by just noise. Then you turn on the generator and adjust it for a 3 db (1.4 times the voltage) increase in output; the object is to achieve the 3 db increase with the minimum amount of current flowing in the noise generator.

However, this technique of using the noise generator is pretty sloppy, since it assumes that the receiver's detector is absolutely linear for small signals—and this assumption is almost always incorrect.

A far better technique is to hook things up just as before, except now you place three T-pads in the line between converter and receiver. The T-pads on each end of the string serve merely to clamp the line impedance at 50 ohms, but the one in the center is built for precisely 3 db loss.

Now take the 3 db pad out and take your reading as before with the noise generator off; you don't have to turn off avc or hook up a voltmeter. The receiver's S-meter can be used instead, since we're not measuring anything with the meter itself. It merely serves as an indicator so we can come back to the same point.

Then replace the 3 db pad in the line, turn on the generator, and crank it up until you get the same meter reading as before. Since you now have 3 db of added loss between converter and receiver you must have increased the noise power output of the converter by that same 3 db, and you could care less about the linearity of the detector!

This whole method is far from new, but previous descriptions of it have left something to be desired in the way of telling how to build the T-pad. The gadget is so simple that it must have seemed obvious to previous writers—but it does have its tricky points too.

For instance, since a T-pad consists merely of 3 resistors, it is pretty easy to just wire them up by their leads. But they are hanging in the receiver antenna lead, and present-day receivers are rather sensitive. If you happen to find a 20-meter signal, it's going to foul up your measurements!



T-Pad construction details

One of the quickest ways to sidestep this problem is to shield the pad against all outside influences—but how do you shield anything so tiny?

The answer here is to use discarded 35-mm film cans, which all photographers who shoot 35-mm cameras have in abundance. The Kodak kind seem to work best. This type has a threaded cap, with a flat spot in its center just right for drilling a ¼ inch hole to take a single-hole-mounting phono jack. At the other end, a ⅜ inch hole can be punched and lined with a rubber grommet for coax cable to enter.

Next step is to place the jack in the hole in the lid, with its solder lug on the inside (be sure to clean the paint so that a good electrical contact will result). The T-pad can be assembled as shown in the drawing with shortest possible leads, and supported by its lead connecting to the jack. Thread a short length of RG-58 through the grommetted hole, and connect its center conductor to the other lead of the pad; the shield and shunt lead of the pad connect to the solder lug of the jack.

All that's left is to wire-brush the threads on the film can for good contact, and screw the lid down tight. Presto, a shielded T-pad. A phono connector should be put on the free end of the cable.

You can make up a whole bunch of these in various loss values, and get virtually any amount of loss you want by stringing them together. And this has a whole lot more use than just using with a noise generator . . .

For instance, when you want to test an antenna, arrange for a steady signal, strong enough to register on your S-meter with the back of the antenna pointed at it. Then swing the antenna in small steps, and bring the S-meter back to the same reading by inserting additional loss between converter and receiver with the T-pads. The difference between this and S-meter indications may amaze you.

Or if you are called upon to measure the difference in signal strength between two stations, the same approach can be used. Note the S-meter reading of the weaker, then knock the stronger one back to the same reading by putting T-pads in the converter-to-receiver line. Read the db off the pads and add them up.

You can even use this in place of an S-meter if you really want to know the signal-to-noise ratio of an incoming signal with accuracy; take a reading on noise, then knock the signal back to the same point. Total up the db, and there's your answer.

Though resistance values in the pad must be precise for absolute accuracy, the pad has an inherent tolerance of small errors and you should have better than 2 percent accuracy if you use 5-percent resistors. Specifically, a 10-percent error in the resistance value of any one arm produces less than ¾ db error in the pad loss, and less than 4 percent error in impedance. Using 5-percent resistors would, of course, cut these error limits in half.

If you want to follow the approach of using a string of these pads for all purposes in the shack, it's best to make them up on a "binary" approach since this gives you the maximum number of db values with the minimum number of parts. A basic assortment might be two 1 db pads, and one each of 2 db, 4 db, 8 db, 16 db, and 32 db. Using them in series in various combinations, you can get any whole number of db from 0 to 64, which pretty well covers the range of values you may ever need. For an example, to get 50 db you would use the 32 db pad, the 16, and the 2. For 60 db, you would use the 32, the 16, the 8, and the 4.

If the ability to increase loss in 1 db steps seems a bit exotic to you in view of the fact that 3 db is only half an S-unit, then you can use a binary progression in 3 db steps; this takes one 3 db pad, one 6 db, one 12 db, and one 24 db. The range is from 0 to 45 db, 3 db at a time.

For clamping a line's impedance, it's a good idea to use at least a 3 db pad and a 6 db unit might be even better. The lower-loss pads pads may not have the ability to swamp out impedance variations on their other sides.

About all that's left to make this complete is a chart of resistance values for various loss figures. Here it is; all are for use with a 50 ohm line; to use at any other impedance, multiply these values by the ratio of the new impedance to 50 ohms:

LOSS AMOUNT	R1, R2	R3
1 db	2.7	430
2 db	5.6	220
3 db	8.2	150
4 db	11	100
6 db	16	68
8 db	22	47
12 db	30	27
16 db	36	16
24 db	43	6.2
32 db	47	2.2

COMBINATION DUMMY LOAD/ ATTENUATOR NETWORK

John Schultz W2EEY

There are many instances when it is desired to use an existing transmitter as an exciter unit for a high-power linear amplifier. Many such linear amplifiers require a drive level that is only a fraction of the transmitter's output. To some degree, the transmitter can be detuned in order to reduce its output level, but this procedure is rarely possible when several orders of magnitude reduction in the power level are necessary. In such a case one can either internally modify the transmitter for a lower output level or use an alternator network between the transmitter and linear amplifier. In the latter case, the transmitter can be operated at its normal power input level and with its tuning controls at their normal settings.

The unit described in this article functions as both an *rf* attenuator and as a dummy load. The latter capability allows a transmitter to be properly tuned alone for correct operation before it is used to drive a linear amplifier. An optional wattmeter circuit is included which when calibrated allows direct reading, in watts, of the full transmitter output or of the drive level supplied to the linear amplifier.



A simple method of construction is employed. Based mainly on "sandwiching" the resistors used between two pieces of vectorboard. Details are given in the text. SO-239 is used as coax input connector. The circuit function switch is located below the output connector.

The unit described was built for use with a nominal 100 output transmitter used primarily for SSB service. The construction used, however, can be extended to other power levels for transmitters operating on 80-10 meters. Also, using the information

Power Reduction	Resistor Factors a	b
1/4 (6db)	.3	1.3
1/5 (7db)	.4	1.1
1/10 (10db)	.5	.7
1/20 (13db)	.6	.5



Fig. 1. Approximate resistor factors for "T" network attenuators over the ranges normally desired for exciter power output reduction.

supplied, the same type of attenuator/dummy load can be designed for other than 50 ohm transmission line systems. The attenuator was not designed as a precision network in order to allow the use of inexpensive resistors. However, the attenuation characteristics are quite satisfactory for the intended usage.

Besides its application as a power reducer when driving a linear amplifier, the unit can be used with a transmitter whenever a quick, known level of power output reduction is needed for operating purposes, approximate gain measurements, etc.

Circuit

Fig. 1 shows the circuit values for a generalized T network attenuator that can be used in any impedance unbalanced transmission line. The scaling factors are only shown for those power reduction levels most likely to be needed when driving a linear amplifier with a 75-200 watt transmitter, in order to avoid unnecessary detail. Factors for intermediate power reduction values can be found by interpolation to a satisfactory degree or one can consult an electronics handbook. The basis of the attenuator/dummy load network is to find the combination of resistor arms that will provide the desired attenuation and still be able to be connected together to form a dummy load of the correct value. **Fig. 2** shows one possible combination. Each resistor bank has a value of about 20 ohms (5 resistors of 100 ohms each in parallel). In one position of the DPDT switch, the resistor banks are formed into a "T" network attenuator. In the other switch position, all three banks are placed in series as a dummy load connected across the input only. The resistance values which result are not exactly those shown in **Fig. 1** for a 10db alternator. However, they are close enough to be effective and some tailoring of the individual legs is possible since each of the resistor bank values vary by a few ohms due to the tolerance of the resistors used. An optional voltmeter circuit is also shown in **Fig. 2** connected to one pole of the DPDT switch. It can be used as a relative power output indicator or if calibrated, as described later, actually measure the power output of the transmitter and of the attenuator.



Fig. 2. Circuit of one possible dummy load/attenuator network providing about 10 db power reduction. Optional wattmeter circuit is also included.

Many variations of the basic idea are possible. **Fig. 3** shows the use of four banks of 100 ohm resistors. All four are used to form an attenuator that comes reasonably close to the values required for 7db attenuation in a 50 ohm system. Only three are used in series for the dummy load function. In this case only a simple SPST switch is necessary to disconnect the output. The same *rf* voltmeter circuit as used in **Fig. 2** may be added if desired. The switch, in fact, could be eliminated entirely if one were willing to disconnect the output termination in order to use the dummy load feature.

Whatever combination of resistance banks are used in order to achieve a desired attenuation value and the correct dummy load resistance, care must be taken that each resistance bank has sufficient power dissipation capability. The dissipation in each leg of the "T" network varies according to the attenuation level and can be calculated by Ohms Law. In general, a continuous power rating for a resistor bank equal to about one-third of the SSB peak power rating seems to suffice, including for quick tune-up on CW. For keyed CW service, the power rating should be increased to at least one-half the key-down power level.



Fig. 3. Another dummy load/attenuator configuration possible with the 100 ohm resistor banks. It provides about a 1/5 power reduction (7db) when used as an attenuator.

Construction

The approach of using a relatively large number of 2 watt composition resistors is far less expensive than using specific value *rf* non-inductive resistors of 10-30 watts power rating. In quantities of more than 10, IRC type RC-2, 2 watt, 10% tolerance resistors cost about 9 cents each. So, one can achieve a 40 watt unit for less than $2 resistor cost. Banks composed of these resistors work well up to 30 mc as long as the interconnecting leads are kept short.



Fig. 4. Similar resistor banks are connected together on the underside of the assembly.

The photograph shows the construction used by the author for the circuit of **Fig. 2.** Similar construction can be used for larger size units as well. As shown in the photograph, the 15 resistors in rows of 5 each are sandwiched between two 1-1/8" x 1-7/8" pieces of vectorboard. None of the resistors physically touches. The wiring is done using the resistor leads. This construction is somewhat compact to expect full, continuous power dissipation from the unit but suffices for intermittent use. The frame measures 2¾" x 1½" x 1½". A cover is not absolutely necessary since the minor radiation that takes place is not important in this application. If a cover is used, it certainly should be of a perforated type to allow maximum air flow. A SD-239 connector is used at one end of the frame for the input. A dual connector is used at the other end, but normally one would use two RCA type phono jacks–one for the output and one for a meter circuit. The switch is located immediately below the output connector–a miniature Alco MST type.

Calibration

If it is desired to calibrate the voltmeter circuit as a wattmeter, it is necessary to use a probe and VTVM. Using the unit as a dummy load, the *rf* voltage is measured at the input and the power calculated. The 50K ohm potentiometer is used to set the meter at full scale for the highest power level used. The *rf* voltage is measured and the power level calculated in order to calibrate the meter for lesser power levels leaving the potentiometer at its "set" value. The same procedure is followed to calibrate the meter for the output power level by measuring the output *rf* voltage when the unit is used as a "T" attenuator and connected to a regular dummy load. The calibration should be made on the lowest frequency band used and rechecked on the highest frequency band used. If the readings differ significantly on the highest frequency band from those established, it may be necessary to add a few mmf capacitance across the diode in the voltmeter circuit in order to compensate for the slightest reactance present in the circuit.



Fig. 5. Sketch showing details of resistor "sandwich" assembly.

Operation

When used between a transmitter and the 50 ohm input of a linear amplifier, the unit is first used as a dummy load for tune-up of the transmitter. The unit is then switched (with the transmitter unkeyed) to its attenuator position. In most cases, no returning of the transmitter should be necessary unless the input of the linear amplifier is particularly reactive.

Summary

The unit described is not intended as a precision attenuator or power measuring device. However, it will perform very well for its intended applications and costs far less than more sophisticated units performing the same functions.

THE MINICAN

Sam Kelly W6JTT

The Heathkit "Cantenna" has proven to be a major breakthrough in the field of dummy loads for ham use. Unfortunately, it isn't the most convenient thing to use on a small work bench with low power rigs! Borrowing their idea, I built this load for use with transmitters in the 5 to 15 watt range. The parts are few: a Campbell soup tin can, four one watt resistors, a UG-254-A connector, a short piece of 5/16 inch brass tubing and transformer oil.

Fig. 1 is a sketch of the assembled unit. The 50 ohm resistance was made up of three 15 ohm and one 5 ohm one watt carbon resistors.

First sand a can lid from a larger size can until it is free of paint. Drill a ⅜ inch hole through the center of the lid, and a ¼ inch hole on the perimiter. Mount the coaxial connector through the center hole. Solder a 1 inch length of 5/16 in. brass tubing over the ¼ inch hole. Solder the resistors as shown. Center the lid on the can and solder the lid to the can. Use a file to remove all rough edges. Mask the connector with masking tape and paint the can to prevent rusting.



Fig. 1. Construction of the Minican. Main parts are a soup can, coax connector and resistors.



The Minicon in use with the companion detector.

Fill the can with transformer oil. A good grade of automatic transmission fluid was used in one load with no degredation in performance. However, it probably is not advisable as the fluid has a relatively low ignition temperature and might create a fire hazard.

The load was tested by running it for five hours with an input of 15 watts of 50 MHz rf. The can became warm, but the resistors showed no signs of overheating.

A maximum VSWR of 1.5:1 was obtained at 234 MHz. The measurement was made at this frequency because an automatic test set was available.

A companion rf detector unit shown in **Fig. 2** was built in a two inch section of ¾ inch square extruded brass stock. A Dage 394-1 BNC connector is mounted on one end for connecting to the RF circuit, while the DC output to the VTVM is a tip jack.



Fig. 2. Rf detector for use with the Minicon.

THE TINY TERMINATOR

Jim Kyle K5JKX

HAVE you ever felt the need for a dummy load which would also indicate accurately the actual rf output power of a transmitter?

You can buy such a beastie, you know. The Bird *Termaline*, standard of the two-way communication industry, shouldn't set you back much more than a C-note . . .

But you can also build one at considerable less outlay, and that's what this article is all about.

As the photographs show, there's almost nothing to the "Tiny Terminator"—nothing, that is, but a 50-ohm load for any transmitter, which will absorb 20 watts for days on end and will handle 40 watts for brief periods (a minor modification can double these ratings), will *not* radiate rf into the ether after the fashion of the "standard" light bulb load, will allow accurate measurement of output power up past 225 mc, and can be built in less than two hours for less than $5.

You can see by the schematic that there's nothing to the device electrically; the tricks are all mechanical. Electrically, the Tiny Terminator consists of 20 (that's what we said) 1000-ohm 1-watt resistors connected in parallel, with a crystal diode running from the hot end of the composite resistor to the meter jack and a 27 mmfd capacitor bypassing the meter.



Mechanically, the big problem with a unit such as this is the problem of keeping the load resistive regardless of frequency. Resistor leads have inductance (about 25 millimicrohenries per inch) so we get rid of the leads as completely as possible. This is done by punching holes in a flat plate, passing the lead through the hole until the resistor is flush with the plate, and soldering rapidly with a hot iron (an Ungar 47-watt 1100-degree tip was used in building the model shown) so that the resistor body won't cook before the leads and plate are joined.

The flat plate has capacitance. This is avoided by keeping the plate shielded from outside influences, and separated as far as possible from its shield.

The shield, incidentally, is the bottom of 1½ inches of a Canada Dry cola, soldered all around the edge to the front resistor plate. This confines all rf inside the terminator.





D1 = HIGH PIV DIODE



Addition of the crystal diode (a 1N34 was used, but a higher-voltage unit is recommended if you ever expect to measure power higher than 8 watts) and the bypass capacitor provide the power-measuring feature. These two components, in conjunction with an external voltmeter of at least 1000 ohms per volt sensitivity, provide you a peak-reading ac voltmeter. The voltage indicated on the meter will be equal to the peak value of rf voltage present across the load. Squaring the voltage and dividing by 50 (the resistance) will give you the *peak* power. Most power ratings are in rms values rather than peak; multiplying the indicated voltage by 0.707 before squaring will give you the rms power output.

The unit shown in the photos used perforated brass stock for the resistor plates; this happened only because a length of the brass was on hand in the junkbox at the time. A cut-out tin can lid will work equally well and will be much less expensive.

Not visible in the photos is the means of connecting the hot end of the resistor plate. A hole was punched in the middle of the hot plate and a length of No. 14 bare wire was soldered in, then filed off flush on the rear side. The bare wire was threaded through the coax connector and soldered to the center contact after checking for possible shorts.

The coax connector itself is held in place by a solder joint all around the rim of the cable-end aperture (see photo). This joint, if well made, provides plenty of strength.

Earlier, we mentioned that a minor modification would double the power rating. That modification is this: instead of 1-watt resistors, use the 2-watt variety. If you really want to go high-power, use 50 2700-ohm 2-watt resistors and have a terminator which will absorb 100 watts continuously and 200 watts ICAS. However, one that big will cost more—and you'll probably have to use a coffee can for the shield instead of the cola can used here.

Volume III
Test Equipment

INDEX

Absorption Wave Meter 39-40
Antenna Impedance Bridge 21-22
Antenna Measurements 28
Antennascope 21
Attenuator, RF 58, 101-6
Audio Frequency Oscillator 50

Capacitor Checking 28, 93
Citizen Band Alignment Aid 55
Crystal Calibrators 73-78

Dummy Loads 38, 101-6

Field Strength 39-46
Frequency Generator, Sweep 52-53
Frequency Measurement 28, 39-48

Grid Dip Oscillators 27, 79-94

Hot Carrier Diode RF Meter 36

Impedance Meter 27
Intermediate Frequency
  Alignment 28
  Spotter 51
  Sweep Generator 62

Lambda Lines 46
Light Bulb as Power Indicators 30
LM-15 Frequency Meter 49

Microwave Frequency Measurement 42-6

Neutralization 28
Noise Figure Measurement 95-100
Noise Generators 95-100

Oscillator Detector 28

Parasitic Oscillation Checking 28
Pulse Generator 69

"Q" 27-8

Radio Frequency
  Attenuation 58-9
  Impedance Bridges 21-9
  Power Meters 5, 16, 30-8
  Pulse Generator 69
  Signal Generators 47-72
  Sniffer 39
  Sweep Generator 62
Ramp Generator 67
Receiver Tweaker 55

Signal Generators 58-9
Slotted Line 14
Standing Wave Ratio 5-20
S-Unit Attenuator 102
Sweep Frequency Generator 52, 62

T-Pad 102
Transmission Line Attenuator 7
TVI Testing 28

UHF
  Dipmeters 85-93
  Frequency Measurement 42-6
  Noise Generator 97
  Signal Generator 57, 61
  SWR Bridge 13

VHF
  Dipmeters 90-3
  Dummy Load 38
  Frequency Measurement 46, 48
  SWR Meter 12-6
  Wattmeter 38
VSWR 5-20
Vacuum Tube Voltmeter 27

NOW FROM TEXAS INSTRUMENTS...
three machines in one.

programmable
slide-rule calculator
SR-52

TEXAS INSTRUMENTS
LUNAR LANDING GAME
SR-52
ON
A' A
B' B
C' C
D' D
E' E
2nd
INV
log lnx
CE
CLR
IND LRN
D.MS sin
D/R cos
P/R tan
LBL GTO
CMs STO
EXC RCL
PROD SUM
rtn SBR
fix EE
dsz (
π)
x² y^x
st flg ÷
del INS
bst SST
rset HLT
read RUN
7
8
9
if flg ×
4
5
6
if err −
1
2
3
if pos +
list 0
prt .
pap +/−
if zro =

- 10 user defined keys
- 224 program storage locations
- 23 preprogrammed key functions
- 8 preprogrammed condition statements
- 20 independent addressable memory registers
- Permanent program storage on magnetic cards

It took TEXAS INSTRUMENTS to invent the SR-52 calculator. It took C & S MARKETING ASSOCIATES to offer it at a price you can afford, now only $249.95. With such versatility and such an affordable price, you cannot afford to be without the problem solving power of card programability. Now solve problems in seconds that would take hours with any ordinary calculator or slideruler if they could be done at all.

For more information or the answer to any question you may have about the SR-52 calculator, call toll free (800-251-6771)*. Tenn. residents call (800-262-6706). Other TEXAS INSTRUMENT models available from $49.95.

Each TEXAS INSTRUMENT calculator comes with a 1-year warranty. Should your unit prove defective within 60 days, just return it for a new unit! Finally should you be dissatisfied with your calculator return it within 15 days for a prompt refund.

C&S MARKETING ASSOC.
P.O. Box 165 Algood, Tenn. 38501

QTY.________________PRICE $249.95 ea.

☐ CHECK ☐ M.O. ☐ C.O.D.

☐ LITERATURE ☐ INFORMATION

DIAL (800-251-6771)

IN TENN. DIAL (800-262-6706)

"New England's FRIENDLIEST HAM STORE"

complete stock

of the following lines:

- ATLAS
- VHF ENGINEERING
- STANDARD
- REGENCY
- BOMAR CRYSTALS FOR 2MTR FM
- 73 MAGAZINE PUBLICATIONS
- QST PUBLICATIONS
- NEWTRONICS
- TEN-TEC

Largest inventory of used equipment in the Boston area.

TUFTS Radio Electronics

386 Main St., Medford MA 02155
Phone: 617-395-8280

YOUR BEST
THEFT
PROTECTION!

FOILER

PATENT APPLIED FOR TM

Quick Release Adapter for Trunk Lip Antennas



USES YOUR EXISTING ANTENNA & MOUNT

MOUNTS EASILY INSIDE TRUNK WITH ONLY 2 SCREWS

DON'T ADVERTISE YOUR RADIO INSTALLATION TO THE RADIO THIEF

$4.95

IF YOUR DEALER DOESN'T HAVE THE FOILER IN STOCK, ORDER DIRECT. ADD 50¢ POSTAGE & HANDLING. TEXAS RESIDENTS ADD 5% SALES TAX. SEND CASHIER'S CHECK OR MONEY ORDER FOR PROMPT SHIPMENT.

– DEALER INQUIRIES INVITED –

SouthCom, Inc.
P.O. BOX 11212 FORT WORTH, TEXAS 76109

Tired of "CB-Quality" Cables?

INEXPENSIVE ASSURANCE OF THE MOST CRITICAL LINK IN YOUR 2-WAY SYSTEM!

Regardless of how much you spend on your radio and antenna system, they can't do their best job unless all of your output power gets from the radio to the antenna, and all of the weak signals get from antenna back to radio. The road both power and signals use for this trip is your coaxial cable. Obviously, then, if the cable is broken or contains losses, you won't get the performance you paid for, yet, very few radio operators pay any attention to the quality of the cable they buy, nor do they replace it periodically. Even the best of cable weathers, ages, and develops losses. The coax cable is the least expensive part of your system. The difference in the best and the cheapest you can buy is only a couple of dollars at worst and yet it can literally "make or break" your performance.

Most cable available today in ready-made lengths, and most cable furnished with new antennas, has three less-than-desirable characteristics.

First, most such cables have a single center wire, which breaks with bending, twisting, and day-to-day handling. SouthCom's cables have a 19-strand center wire, so all 19 strands must break before the cable loses connection.

Second, most cable does not have full shielding. You can peel back a small section of the outer black insulation, and you can see the inner insulation through "holes" in the braid. SouthCom's cable is fully shielded!

Third, most cable uses bare copper conductors, and you know how quickly bare copper can corrode. SouthCom's cables use tinned copper to resist corrosion.

Connectors vary widely. Solder-on types are the most common, yet they require a lot of heat which can partially melt the inner insulation, and distort the shape of the cable. In addition, you can't tell how much of the braid has actually been soldered through the four tiny holes in the fitting. SouthCom uses AMP, Inc. air-crimped connectors, which require no heat, and assure a solid bond to all of the braid. Because of the inner construction of the connector, it is almost impossible for a SouthCom cable to short.

In seven months of production, we have had only one report of a defective cable! Quite a record. Part of this record can be attributed to our quality control which checks every cable for SWR and power loss, not just continuity. We think the quality we build in, and the care with which we put our cables together makes them worth a little bit more. Since you're surely entitled to the performance you paid for when you bought your radio and antenna, you should insist on SouthCom cables. If your dealer won't get them for you, we will ship to you from the factory. Add $1.00 postage and handling, Texas residents add also 5% sales tax. Send cashier's check or money order for immediate shipment.

58-3	3-ft. cable/PL-259's	$3.98
58-6	6-ft. cable/PL-259's	4.85
58-12	12-ft. cable/PL-259's	5.65
58-20	20-ft. cable/PL-259's	6.50
58-20L	20-ft. cable, PL-259-solder lugs	5.95
58-50	50-ft. cable/PL-259's	9.95

REPLACE WITH SOUTHCOM CABLES TODAY . . .
GET THE PERFORMANCE YOU PAID FOR!

SouthCom, Inc.
P.O. BOX 11212 FORT WORTH, TEXAS 76109

S. D. SALES CO.

YOUR SOURCE

for

CHIPs, CLOCKs, etc.

Send for Flyer

S. D. SALES CO.

P. O. BOX 28810
DALLAS, TEXAS 75228

Exclusively Yours

Your BANKAMERICARD welcome here

WE HONOR master charge THE INTERBANK CARD

1 MORE TIME

Call your BANK AMERICARD or MASTER CHARGE
order in on our
CONTINENTAL UNITED STATES TOLL FREE WATTS:

1-800-527-3460

TEXAS RESIDENTS CALL COLLECT:

214/271-0022

Please call between 8:30 AM and 6:00 PM C.S.T. – Monday through Friday. You may also call to check stock or just ask a question. However, only B.A.C. and M.C. orders will be accepted. We do not ship C.O.D.

AST/SERVO SYSTEMS INC.


INSTRUMENTS & COMPONENTS
OFFERED AT A FRACTION OF MANUFACTURERS ORIGINAL COST

ELECTRONIC INSTRUMENTATION

SOLD LEASED
RENTED PURCHASED

- Oscilloscopes
- Oscillators
- DVM
- R.F. Volt Meters
- Power Supplies
- Transducers
- Recorders
- Synchros
- Servo Motors
- Generators
- Related Components & Systems

SEND FOR INSTRUMENTATION CATALOG

Name____________________

Address__________________

City_____________________

State________ **Zip**________

AST/SERVO SYSTEMS INC., 20 Republic Road, North Billerica, Mass. 01862 617-667-8541

ARRL's $19.95

RF Amplifier Classics


IN
TX
ON
PWR
DC
OUT
PTT

Practical design and construction details from the pages of ***QEX*** and ***QST***.

Contents

HF/MF/VHF Amplifiers (1 to 54 MHz)

An Easy-to-Build 25-Watt MF/HF Amplifier	Gary Breed, K9AY
A Compact 1-kW 2-50 MHz Solid-State Linear Amplifier	H.O. Granberg, K7ES/OH2ZE
A Broadband HF Amplifier Using Low-Cost Power MOSFETs–Parts 1 and 2	Mike Kossor, WA2EBY
A 1.8 to 54 MHz 5-Watt Amplifier	Zack Lau, KH6CP
An Experimental Solid-State Kilowatt Linear Amplifier for 2 to 54 MHz	Joel Paladino, N6AMG
An All-Band, 1500-Watt-Output 8877 Linear Amplifier–Parts 1 and 2	Jerry Pittenger, K8RA
High-Efficiency Class-E Power Amplifiers–Parts 1 and 2	David Rutledge, KN6EK, et al.
A 100-W MOSFET HF Amplifier	William E. Sabin, W0IYH
The FARA HF Project	Jim Valdes, WA1GPO

VHF/UHF Amplifiers

A Compact "Brick" for 6 Meters	Pat Bunn, N4LTA
A 300-W MOSFET Linear Amplifier for 50 MHz	Richard Frey, K4XU
A No-Bandswitch, Dual-Band VHF Desktop Amplifier	Paul Hewitt, WD7S
An 8-Watt, 2-Meter "Brickette"	Bob Larkin, W7PUA
903-MHz Linear Amplifiers–Parts 1 and 2	Dave Mascaro, WA3JUF
25-Watt Linear Amplifiers for 144 and 220 MHz	Dave Mascaro, WA3JUF
A High-Power 2-Meter Amplifier Using the New 3CX800A7	David Meacham, W6EMD
A Quick Powerhouse	Russ Miller, N7ART
A Cathode-Driven Tetrode for 6 Meters	David Munyon, W7DVB
A UHF Amplifier—from Scratch	John Reed, W6IOJ
A Solid-State 6-Meter Linear Amplifier You Can Build	Tarmo Tammaru, WB2TMD
Build a 6-Meter "Mini-Lini"	Wilson Hoag, WA5OLT
A Grounded-Grid Kilowatt Amplifier for 432 MHz	Stephen J. Powlishen, K1FO

Microwave Amplifiers

A Quarter-Kilowatt 23-cm Amplifier–Parts 1 and 2	E.R. "Chip" Angle, N6CA
A 2-W 13-cm Amplifier	Zack Lau, KH6CP
1296-MHz Solid-State Power Amplifiers	Al Ward, WB5LUA

Amplifier Maintenance

Amplifier Care and Maintenance	Ward Silver, N0AX

Foreword

If antenna gain alone is not sufficient to bridge the path between two stations, the alternative is to increase RF power. Hams have been aware of this fact since the earliest days, and that is why RF power amplifier projects have always been popular.

In *RF Amplifier Classics* we have assembled a collection of articles published in *QST* magazine, and its sister technical journal, *QEX*. The collection spans the early 1980s through 2003 and includes many prominent authors. In those few instances where an author provided a design revision (or correction) after the article was published, that revision is *included* in the article as presented in this book.

See the leatest issue of *QST* for other ARRL RF design-related publications, or visit our on-line bookstore at **www.arrl.org/catalog**. Please take a few minutes to give us your comments and suggestions on this book. There's a handy Feedback Form for this purpose at the back, or you can send e-mail to **pubsfdbk@arrl.org**.

Our thanks to the many authors whose work appears in this book. Without their willingness to share their knowledge with the amateur community, *RF Amplifier Classics* would not be possible.

Dave Sumner, K1ZZ
Executive Vice President
Newington, Connecticut
August 2004

By Gary Breed, K9AY **From *QST*, February 1994**

An Easy-to-Build 25-Watt MF/HF Amplifier

Do you need a medium-power linear amplifier for SSB or CW? Congratulations—you just found it!

Here's a 25-W, 1.8- through 30-MHz, class-A linear power amplifier that's simplicity itself. What makes it simple is the use of a self-biased transistor module requiring few external components. To control harmonic output, a set of five-section low-pass filters is included. Power-supply requirements are +28 V at 2.5 A and —5 V at 200 mA.[1] With a gain of about 13 dB, a 1- to 1.4-W driving signal is all that's needed to deliver 25 W output. Gain is flat within ±0.75 dB across the covered frequency range.

If 25W isn't enough for you, it's easy to directly apply the design information to build a 50-W amplifier—all you do is use a larger transistor module! Another step toward project simplicity is the availability of kits. Each kit contains all the major components for either a 25- or 50-W version.[2]



Amplifier Design

When designing a power amplifier, the first step is to select the right transistor(s). Excellent bipolar-junction transistors (BJTs) and field-effect transistors (FETs) are available from well-known companies such as Motorola, M/A-COM PHI, SGS-Thomson, Philips, Mitsubishi and others. A number of smaller companies also make power transistors, usually for more-specialized applications. MicroWave Technology, Polyfet RF Devices, and Directed Energy may be company names unfamiliar to you, but they all make power transistors for MF and HF applications.

In this amplifier, I use the SLAM-0111 from MicroWave Technology.[3] I didn't choose it because of its gain, its efficiency, or even its price; I selected it because it's very easy to use. The device consists of two power JFETs (the particular specialty of MicroWave Technology), operating in push-pull. Since JFETs behave similarly to triode vacuum tubes, the company dubbed them *Solid State Triodes*. SLAM (Solid-state-triode Linear Amplifier Module) devices include thick-film bias resistors in the package with the transistors. These resistors set the gate bias for class-A operation, and establish a 50-a input impedance. At the rated power and supply voltage, the push-pull output impedance is also 50 Ω!

With such convenient input and output impedances, matching the devices to a 50-Ω system merely requires 1:1 balun transformers at the input and output. Because the bias voltage is internally generated, the only other external circuitry required is a suitably bypassed and isolated 28-V power supply.

Circuit Description

The amplifier schematic is shown in Fig 1. The balun driving the gates of the push-pull transistors is a conventional transformer. The primary and secondary windings are each three turns of #28 wire, wound on a two-hole ferrite balun core of 73 material ($\mu_i = 2500$). These transformers are broadband enough to provide 1.8- to 30-MHz operation and offer dc isolation with no additional components. The input-transformer primary is center-tapped and bypassed to provide access to the gates for external dc bias (more on this later).

The output transformer is constructed in the same manner as the input transformer—it's just larger. Two ferrite beads of 77 material ($\mu_i = 2000$) make a two-hole core, with primary and secondary windings of three turns each, using #24 hookup wire. The primary (transistor side) is center-tapped and bypassed to provide dc voltage to the drains. Feeding dc through a center-tapped transformer eliminates the need for the usual bifilar RF choke seen in push-pull amplifiers—another reduction in the component count. Multiple bypass capacitor values (0.01, 0.1 and 10 μF) are used to cover the MF/HF range. That's the basic amplifier block: two transformers, a SLAM device, and a few bypass capacitors!

Class-A Operation Notes

By definition, transistors operating in class A conduct over the entire 360 degrees of the signal (that's all the time, of course). This operational mode assures that the transistor is always operating in the linear region of its input-to-output transfer characteristic. To do this, the device must be biased to handle the maximum signal at all times.

Obviously, this class of operation is pretty inefficient, since full current is drawn whenever the amplifier is on. A "perfect" transistor operating class A can only be 50-percent efficient, and real transistors



Fig 1—Schematic diagram of the 25-W class-A amplifier. Unless otherwise specified, resistors are 1/4-W, 5%-tolerance carbon-composition or film units. Equivalent parts can be substituted.

J1—Panel-mount BNC socket.
J2—SO-239 connector.
J3—Phono jack.
P1—4-pin male Jones plug.
K1—3PDT relay with a 24-V dc coil. A surplus Potter & Brumfield KHP series 4-pole relay is shown in Fig 6; one pole is unused. (All Electronics catalog number 4PRLY-24N [$4] or Ocean State Electronics R12-17D3-24 [$10.90] are suitable. See the Part Suppliers List on pp 35-40 of *The 1994 ARRL Handbook* for addresses and telephone numbers. —Ed.)
S1—2-pole, 7-position ceramic rotary switch. My switch is made from two surplus CRL 11-position switch wafers and an indexing assembly providing selectable stops. The wafers are spaced about 1 1/2 inches apart. CAL PA-200 series switch wafers and PA-300 series shaft and indexing assemblies are suitable (switches are available from Newark Electronics; tel 312-784-5100, fax 312-784-5100, ext 3107, to locate your nearest Newark distributor).
T1—Primary: 3 turns #28 AWG; secondary, 3 turns #28 AWG, center-tapped. Core: Fair-Rite #2873002402 balun (Amidon BN 73-2402).
T2—Primary, 3 turns #24, center-tapped; secondary, 3 turns #24. Core: two Fair-Rite #2677006301 beads (Amidon FB 77-6301).
U1—SLAM-0111 ultralinear 25-W, class-A, self-biased power FET module or SLAM-0122, 50-W version (Microwave Technology, 4268 Solar Way, Fremont, CA 94538, tel 510-651-6700, fax 510-651-2208).
Misc: RG-174 coax, enclosure (3 1/2 x 7/8 x 5 1/4 inches [HWD]), heat sink (3 x 4 1/8 x 1 3/8 inches [HWD]), PC-board material, knob, mounting hardware.

do no better than about 40 percent. This amplifier draws 2.5 A from a 28-V power supply for an input power of 70 W. When it is providing 25 W, it's 36-percent efficient. (When there is no input, it's 0-percent efficient!)

To help reduce the heat generated by an amplifier that requires 70 W, a negative bias can be applied to the gates when not transmitting. A bias of —5 V results in a 0.25-A standby drain current instead of the full 2.5 A. The internal bias resistors are about 50 ~ on each gate, and dissipate a maximum of I W. Under these biasing conditions, the resistors each dissipate 0.5 W. Don't try to cut off the transistors completely with greater bias voltage! You'll risk burning out the resistors.

Some may ask, "If class A is this power hungry, why use it?" In a word: linearity. If you want excellent linearity (which means minimum distortion caused by harmonics or intermodulation), class A is the way to go. For example, all small-signal amplifiers for receivers and low-level transmitter stages operate class A because they must handle signals without distortion. However, they operate at very low power, so power dissipation is rarely an issue. This power amplifier further minimizes distortion by using push-pull operation, which cancels even-order distortion products in the output and makes the next part of the design easier than usual.

Harmonic Filter Design

As mentioned previously, the amplifier uses several low-pass filters to cover the nine MF/HF amateur bands. Each filter was initially designed for a cutoff frequency 20 percent higher than the upper end of their respective 160, 80, 40, 30, 20, 15 and 10-meter ham bands. The 15-meter filter is also used for 17 meters, and the 10-meter filter for 12 meters.

With no filtering, even-order harmonics (2nd, 4th, etc) are more than 40 dB below the carrier, the result of good push-

Table 1

Filter Circuit and Comparison of Ideal and Final Component Values.

	Ideal Filter Values			*Actual Filter Values*		
Cutoff Freq. (MHz)	*C1, C5 (pF)*	*C3 (pF)*	*L2, L4 (µH)*	*C1, C5 (pF)*	*C3 (pF)*	*L2, L4 (µH)*
2.40	1521	2620	4.55	1470 (1000 + 470)	2880 (2200 + 680)	4.41 (30 t on T50-2)
4.80	761	1310	2.27	830 (560 + 270)	1430 (1000 + 430)	2.37 (22 t on T-50-2)
8.76	417	718	1.25	430	820	1.25 (16 t on T-50-2)
12.18	300	516	0.900	300	560	0.960 (14 t on T-50-2)
17.22	212	365	0.634	220	370 (270 + 100)	0.706 (12 t on T-50-6)
25.74	142	244	0.424	150	240	0.460 (10 t on T-50-6)
35.64	102	176	0.306	100	180	0.314 (8 t on T-50-6)

In some cases it is necessary to parallel two smaller-value capacitors to obtain the proper values of capacitance for C1, C2 and C5

The inductors are wound on T-50-2 or T-50-6 cores. Inductors for the 160- and 80-meter filters are wound with #26 AWG wire in order to fit all turns on the cores; the other inductors are wound with #22 wire.



Fig 2—Schematic of the filter used for each band.

pull balance using factory-matched transistors. The 3rd and 5th harmonics are more than 15 dB down. To reduce the 3rd harmonic to at least 50 dB below the carrier, a five-section Chebyshev filter with low passband ripple is an appropriate choice. This type of filter has a good SWR in the passband, and a smooth roll-off characteristic. The design process began by creating ideal designs using a public-domain filter design program.^{4}

Ideal designs rarely correspond to standard capacitor or inductance values that can be realized with a discrete number of turns on common toroid cores. Using a circuit analysis program,^{5} the ideal designs were analyzed to see the effects of such realworld limitations on harmonic rejection and SWR performance.

First, the ideal component values were entered into the program, and varied ±20 percent to see which ones had the greatest effect on performance. Cl and CS (see Fig 2 and Table 1) were found to be least sensitive to variations, L2 and L4 were moderately sensitive; varying C3 had the greatest effect on both passband and stopband performance. The ideal capacitor values were then replaced with standard capacitor values or—in some cases— parallel combinations of two common capacitor values. Inductors were given the nearest value available for coils wound on either T-50-2 or T-50-6 toroid cores. The final filter designs are the result of trade-offs between inductance, capacitance and filter performance. Table 1 shows the filter topology, along with a comparison of the original ideal filter component values and the values selected for the finished unit.

Construction

I built my amplifier and low-pass filter modules on single-sided PC boards, using pads to mount the components. No holes are drilled (except for mounting screws) and all leads are attached by soldering them to the pads. The PC-board patterns for the amplifier and filters are available (see Note 2).

Fig 3 shows the amplifier-assembly parts. This assembly is mounted to a heat sink (see Figs 4 and 5) capable of dissipating more than 40 watts without excessive temperature rise. (This assumes a worst case of 50-percent transmitting time, and 7-watts dissipation in standby.) A cutout in the middle of the amplifier board allows placement of the SLAM device. The PC board leaves a conducting path around the ends of the SLAM to maintain a ground potential across the entire board. Four mechanical components make up the amplifier assembly. The first is a 0.1875-inch-thick aluminum base plate to which the SLAM is mounted. Next are two aluminum 0.1-inch-thick spacers, which are placed between the base plate and the circuit board. These spacers set the proper distance from the base plate to SLAM leads. The SLAM is installed through the top of the PC board, and its leads are soldered to the traces on top of the board.



Fig 3—Mechanical assembly of the amplifier-module PC board, aluminum spacers and heat sink.



Fig 4—The assembled amplifier-module PC board in position and secured to the heat sink (see Fig 5, next page).



Fig 5—Rear view of the completed amplifier showing the hefty heat sink.



Fig 6—This interior view of the amplifier shows its simple and clean layout. The band switch is centered on the front panel. Immediately beneath the band switch is the filter assembly. Behind the switch and to the left is the TR relay, K1. A four-pin Jones plug power connector is mounted on the rear panel behind and to the left of the relay. On the bottom, near the outside lip of the rear panel, is J1. Above it is J2, with J3 to its right. Most of the rear panel—from its middle to the right lip—is occupied by the SLAM IC PC board and the aluminum spacers secured to the heat sink mounted on the rear panel's exterior. Rubber feet on the cabinet bottom help prevent scratching the supporting surface beneath and keep the amplifier from sliding. The band-switch knob center section is 1$^{1}/_{8}$ inches in diameter; the skirt flares to a diameter of 1$^{1}/_{2}$ inches.

Construction is easiest if the transformer connections to the SLAM are not soldered until after the SLAM is installed. This eliminates the possibility that the transformer connections will get in the way when you try to solder the SLAM into place. As with any power device, place a thin coating of thermal compound between the SLAM and the base plate, and between the base plate and the heat sink. Solder bypass capacitors directly to the transformer center tap and to the ground plane, with the minimum possible lead lengths.

The low-pass filter board is constructed one filter at a time. First, install the capacitor at the center (C3), then the inductors L2, L4), and finally the end capacitors (C1, C5). All inductors are wound with even spacing over three-quarters of the core circumference. Simply solder the capacitors to the pads and ground plane. Silver-mica capacitors were used in the prototype because they were on hand. Ceramic-disc capacitors with 200- to 500-V ratings will work equally well.

If the band switch is located close to the filter board (see Fig 6), short lengths of hookup wire can connect the filters to the switch wafers.

A spacious box houses the filter and amplifier assemblies, along with a TR relay that also switches the standby bias. Power and relay control leads are bypassed where they enter the enclosure.

Before final assembly, I gave the panels of the case a brushed look using a sanding block with oiled sandpaper. Band markings for the switch (see the title-page photo) are drawn on a large, adhesive-backed label attached to the front panel.

Performance

Amplifier gain ranges from 12.5 to 14 dB between 1.8 and 30 MHz. The gain flatness is basically a function of the input and output transformers. (It's possible to make the amplifier gain flat within 1 dB from 1 MHz to 100 MHz using transmission-line transformers and frequency compensation.) The required drive power for 25 watts output is 1.0 to 1.4 watts.

On-the-air performance is excellent. Besides low distortion in the SSB mode, a small advantage of linear amplification is a complete absence of rise and fall distortion of a CW waveform, which sometimes occurs in class-C amplifiers.

Summary

This project shows how new RF products can make home construction of amateur equipment very easy. Home-brewers can benefit from a growing trend in RF product engineering: reducing development time by using "super components" that require few external components and little engineering time to design them into a product.

A secondary purpose of this project is to show how even simple software tools can be used to speed up design. The programs used to design the amplifier's low-pass filters are inexpensive, and accurate at frequencies in the MF/HF bands. In this case, they made it possible to examine tradeoffs among standard-value components for seven different filters, without having to build, measure and tweak each one.

The result is a linear power amplifier with good gain and performance. Its uncomplicated design leaves little room for error, and no fancy test equipment is needed to successfully build it. Projects this easy can make an old-timer forget about the "simpler" days of vacuum tubes!

Notes

[1] Power supplies are available from Marlin P. Jones & Assoc, mc, P0 Box 12685, Lake Park, FL 33403-0685, tel 407-848-8236; fax 1-800-432-9937.

[2] Parts kits for this project are available from Crestone Engineering, PO Box 3702, Littleton, CO 80161, tel 303-770-4709. Each kit includes all electronic and mechanical components for the amplifier module and lowpass filter assembly, includin9 circuit boards, heat sink and rotary band switch. Kits do not include an enclosure, connectors, or TR relay. A 25-W kit using the SLAM-0111 is $115; a 50-W kit using the larger SLAM-0122 is $190. Add $6 per kit for shipping. Payment may be made by check, money order, VISA, MasterCard or American Express.

PC board patterns for the amplifier and filters are availablefreefrom the ARRL. Send your request to the Technical Department Secretary, ARRL, 225 Main St, Newington, CT 06111. With your request for the BREED AMPLIFIER PC-BOARD TEMPLATE, enclose a business-size envelope with one First-Class stamp.

[3] Microwave Technology, 4268 Solar Way, Fremont, CA 94538. Their products are distributed by Richardson Electronics, 40W267 Keslinger Road, LaFox, IL 60147, tel 708-208-2200.

[4] Mike Ellis, "A Comprehensive Filter Design Program," RF Design, July 1991. The program is available from the RF Design Software Service, PO Box 3702, Littleton, CO 80161-3702, tel 303-770-4709 (part #RFD0791, $15 postpaid).

[5] NOVA, a shareware program by Robert Stanton, also available from the RE Design Software Service (part #RFD-0391 ,$15 ppd).

By H.O. Granberg, K7ES/OH2ZE

From *QEX*, July 1990

A Compact 1-kW 2-50 MHz Solid-State Linear Amplifier

Solid-state high-power linear amplifiers are becoming more and more popular in the field of ham radio as the prices of HF power transistors continue to fall. 250-W devices are now available for almost half the price they were selling for a few years ago. RF power FETs are still more expensive, but eventually their prices will also fall, although not as fast since they are still novelty items and the manufacturing yields are low due to ESD problems and requirement for cleaner facilities for wafer processing.

General

It is much easier to design wideband power amplifiers with FETs than bipolar transistors mainly due to their higher input impedances at least up to VHF. Their input impedance also varies less with frequency than that of bipolar devices and changes in the output load line are reflected back to the input to a lesser degree because of the much lower value of feedback capacitance (collector to base vs drain to gate). Practically all RF power FETs on the market today are of the enhancement MOS type, meaning that positive voltage at the gate in respect to the source is required to turn the device on.

The 1-kW amplifier described here would be difficult, if not impossible, to design to cover four and a half octaves with comparable performance using inexpensive bipolar transistors. In addition, a series of power splitters and combiners would be required to reach high power levels. Biasing to class AB linear operation is also much simpler with FETs since the gate does not draw any dc current, whereas a current equal to $I_C(peak)/h_{FE}$ must be supplied to the base of a bipolar device. One example of this and the splitter-combiner complexity is presented in the Application Note AN-758 by Motorola, Inc.

This article features a state of the art extremely compact design using a pair of FETs rated for 600 W of power output each. It would be capable of a power output of 1.2 kW as a push-pull circuit, but with the output matching employed, which is optimized at around 800 W, the unit starts saturating at around 1 kW at a 50-V dc supply, resulting in high IM distortion. Similarly at a 40-V supply, it would be usable up to 800 W. The type output matching transformer employed allows only integers as 1:4, 1:9, 1:16, etc. The 1:16 impedance ratio transformer would make the output matching optimized at 1400 W, which would result in a poor efficiency at 1200 W and lower power levels. The only way to compensate for this would be to adjust the supply voltage accordingly, in this case 45-46 V. However, the 1:16 ratio transformer of this type is physically much more difficult to fabricate than the lower ratio ones, and may not be available in the commercial market.

The Bias Regulator

The gate bias regulator (IC1 in Fig 1) allows the main supply voltage to be varied or the use of an unregulated supply while keeping the gate bias voltages and the FET idle currents constant. Since the maximum operating voltage of the regulator IC is only 40 V, a Zener diode (D1) is employed to keep it at a safe level. The regulator supply terminals are separated from the main power supply permitting the use of a separate bias supply if desired. There is also an option for a thermistor connection to stabilize the idle currents against temperature changes. The thermistor should be in a physical contact preferably with a mounting flange of one of the FETs. The gate voltages are individually adjustable (R1, R2) making gate threshold voltage matching of the devices unnecessary. In case of a device failure, such as a drain-gate short, D2 and D3 block the full supply voltage from being fed back to destroy the regulator. R10, R11 and C3, C4 are merely AC filters to protect the regulator from possibly strong RF fields. To set the idle currents, Rl and R2 must be adjusted to minimum. R3 is then adjusted for a regulator output voltage of about double the FET gate threshold voltages (IC1, pin 3). The current is monitored at the main supply voltage point while adjusting Ri for a desired idle current, typically 800 mA-1.0 A. R2 is then advanced until the current is doubled, resulting in equal idle currents for both devices. After this procedure, the settings of R1 through R3 should remain until one or both FETs must be replaced.

The RF Path

The amplifier is designed to operate into the industry standard 50-ohm input and output interface. The impedance matching to the low impedance levels of the FETs is accomplished with broadband RF transformers. Both the input transformer (T1) and the output transformer (T2) are of the so-called conventional type in contrast to transmission line transformers.[1,3,4] Both employ only one turn in the low impedance winding. T2 is far more critical than T1 because it determines the efficiency and the high frequency end gain characteristics, plus it must be able to handle a large amount of RF power. For increased bandwidth characteristics, its low impedance, one turn winding consists of three paralleled 10-ohm coaxial cables, resulting in a tight and controllable coupling between the primary and secondary. According to formulas given in Reference 2, approximately twice the present 4.7 cm^2 ferrite cross sectional area would be required in order for the core not to saturate with the calculated 127 gauss flux density. The saturation mainly occurs at the lowest frequencies, in this case at 2-3 MHz. Unfortunately most ferrite manufacturers do not give information on saturation flux densities that applies to applications such as this. However, it is known that high permeability ferrites, in



Unless otherwise noted, all resistors are ½-W metal film type. All chip capacitors except C13 are ATC type 100/2008 or Dielectric Laboratories type C17.

(NOTE: The PCB mount BNC output connector used is type BNF34, available from ORA Electronics, tel 818-701-5848)

Fig 1—Circuit Diagram—2 to 50 MHz Amplifier 2-50 MHz Amplifier Components List

R1,R2—1 kΩ single-turn Trimpots
R3—10 kΩ single-turn Trimpot
R4—470 Ω, 2 watts
R5—10 Ω
R6,R12,R13—2 kΩ
R7—10 Ω
R8—Exact value depends on thermistor R9 used (typically 5-10 kΩ)
R9—Thermistor, Keystone RL1 009-5820-97-Di or equivalent
R10,R11—100 Ω, 1 W carbon
R14,R15—EMC Technology model 5308 or KDI Pyrofilm PPR 870-150-3 power resistors, 25 Ω
D1—1 N5357A or equivalent
D2,D3—1N4148 or equivalent
IC1 —MC1723 (723) voltage regulator
C1—1000-pF ceramic disc capacitor
C2,C3,C4—0.1-µF ceramic disc capacitor
C5—0.01-µF ceramic chip capacitor
C6,C12—0.1-µF ceramic chip capacitor
C7,C8—Two 2200-pF ceramic chip capacitors In parallel each
C9—820-pF ceramic chip capacitor
C10,C11—1000-pF ceramic chip capacitor
C13—0.47-µF ceramic chip capacitor or two smaller values in parallel
C14—Unencapsulated mica, 500 V. Two 1000-pF units is series, mounted under T2.
L1,L2—15 ηH, connecting wires to R14 and R15, 1.5 cm each #20 AWG
L3—10 µH, 10 turns #12 AWG enameled wire on Fair-Rite Products Corp ferrite toroid #5961000401 or equivalent
T1,T2—9:1 and 1:9 impedance ration RF transformers, types RF800-3 and RF2067-3 R, respectlvely (RF Power Systems, 3038 E Corrine Dr, Phoenix, AZ 85032)

general, saturate easier than low permeability materials. Thus, the lowest permeability material should be selected that will satisfy the minimum inductive reactance requirement at the lowest frequency of operation. The formula to calculate this is $NX_L = 2R_{S(L)}$, where: X_L=inductive reactance for one turn, N = number of turns, $R_{S(L)}$ = source or load impedance. Low permeability material is also less lossy at high frequencies, resulting in less heat generated in the transformer. T1, which must handle only 8-12 W of power, is made of higher permeability ferrite. This makes it possible to make the unit physically small as well. In Ti, the secondary consists of metal tubes (see Ref 1), where three turns of the primary wire is threaded through. Metal tubes are also used in T2, but only to hold the structure mechanically together.

At high-power levels generated with solid-state devices, which operate at relatively low voltages, the impedance levels automatically become low. This creates a problem for finding passive components, especially capacitors to handle the high RF currents involved. In vacuum tube circuits a similar problem exists, but in the form of high voltages. In this design, C14 gets the roughest treatment. It must be able to carry RF currents in excess of 10 amperes at the higher frequencies, although the voltage across it is only 75 V rms. At first, several good quality ceramic chip capacitors were tried in parallel, but temperature excursions caused them to crack resulting in AF arcs that burned the circuit board in the area as well. Finally, two unencapsulated mica capacitors (brand names such as Unelco, Underwood, Standex, Elmenco and Semco) were soldered in series by attaching the terminal tabs together, making it a sym-



FIGURE 2 — POWER OUTPUT VERSUS POWER INPUT

Fig 2



FIGURE 3 — POWER GAIN AND INPUT VSWR VERSUS FREQUENCY

Fig 3



FIGURE 4 — DRAIN EFFICIENCY VERSUS FREQUENCY

Fig 4



Fig 5


FEEDBACK RESISTOR CONNECTIONS
=BOARD SPACERS, 0.125" HIGH
=TERMINAL PINS
=FEED THROUGH EYELETS OR PLATED THROUGH HOLES

COMPONENT LAYOUT — BOTTOM SIDE

Fig 6


FEEDBACK RESISTOR CONNECTIONS
=BOARD SPACERS, 0.125" HIGH
=TERMINAL PINS
=FEED THROUGH EYELETS OR PLATED THROUGH HOLES

COMPONENT LAYOUT — BOTTOM SIDE

Fig 7

metrical structure. Since each is double the total value required and with double the number of plates, this increases the RF current carrying capability and provides a larger area to be soldered to the board metal foil to make the cooling more efficient. The low impedance winding terminals are then soldered to the tops of the capacitor metal casings, leaving the effective capacitance across the winding. For further fine tuning, an Arco (Elmenco) #469 or Sprague #GM-40900 compression mica trimmer can be soldered to the fronttop terminals of the transformer. Slot openings in the metal foil (Fig 7) located on each side of the output transformer, next to the drain terminals, were provided to increase the series inductance for certain highfrequency narrowband applications. This tunes out some of the FET output capacitance, resulting in increased efficiency. At lower frequencies (below 80 MHz) however, they only add to the IR loss and should be shorted. The location of C9 is also critical and should be placed approximately as shown in Fig 7. This will affect the input VSWR at frequencies above 30 MHz.

Bypass capacitors C10 through C12 must also be of good quality. The center tap of T2 should be free of AF if the circuit is balanced. This may not always be the case, in which case these capacitors will aid this function. L3 and C13 form an additional filter, ensuring that no RF energy is being fed back to the power supply. Switchmode power supplies especially are sensitive against RF and may actually get damaged from it.

Negative feedback is provided through the networks L1-R14 and L2-R15. Its purpose is to produce a relatively flat power gain versus frequency response. It also


INPUT
TEMP. COMP.
+ BIAS –
(A)
HOG 16A
HOG 16B
(B)
1 INCH

Figs 8A and 8B–Circuit Board–Top Side and Bottom Side



Fig 9—Amplifier mounted to the Heat Spreader.

improves the input return loss and helps to stabilize the amplifier at low frequencies, where the power gain would be 25-30 dB without it. The feedback is at its minimum at the high frequency end and at maximum at low frequencies, where most power is dissipated in R14 and R15. This power is roughly the difference in power input without the feedback between 2 and 50 MHz assuming a constant power output (in this case 25-30 W). A simple formula for calculating the feedback resistor values as well as their dissipation ratings is given in Reference 5. Reference 5 also includes information on physical construction of RF transformers such as used here.

Thermal Aspects

Assuming a 50% worst case efficiency for the unit, each FET dissipates 500 W of heat in an area of 1 x 1.5 inch. It is imperative that the transistors are mounted on the surface of a material with low thermal resistance such as copper. This is called a heat spreader as it is then attached to a heat sink made of material with poorer thermal resistance. It should extend about one inch beyond the edges of the FET mounting flanges at least on three sides. It is even more practical to make the heat spreader as large or larger than the amplifier itself. This would allow all circuit-board spacers to be an equal height of 0.125 inch. The thickness of the heat spreader should be a minimum of 0.375 inch. The heat spreader is then separately attached to the actual heat sink, which can be a 12-inch length of Wakefield Engineering type 4559 extrusion or equivalent[6]. Heat sink compound must be applied to all thermal interfaces and the recommended transistor mounting procedure should be followed, including the screw torque. Fig 9 shows the amplifier mounted to the heat spreader. Although the heat sink is not shown, one must be used for continuous operation and for test periods longer than a couple of minutes. For continuous operation, two 5-inch muffin fans under the heat sink will suffice. They will keep the device case temperature at below 80°C, and the die temperature, which equals to device thermal resistance x power dissipation + case temperature = 0.13 x 500 + 80, at less than 145°C, which is well below the 200-degree maximum recommended value. We must realize that the 500-watt dissipation is only valid when the unit is operated into a 50-ohm load. Under mismatched conditions, depending on the phase angle, the dissipated power may be lower or higher than this value.

Performance

Some of the amplifier performance characteristics are shown in Figs 2 through 5. Although at 30 MHz and above all harmonics are 25 dB or more below the fundamental, an output filter is required to comply with FCC regulations. However, it can be a simpler one than required for the low frequencies, where the third harmonic may be only attenuated 12-15 dB. In push-pull amplifiers, the even harmonics are not usually a problem since they are attenuated by the balanced operation of the circuit. Information on high power low-pass filters for applications as this can be found in Reference 7. These filters are automatically relay switched with BCD code available in most modern transceivers.

References

The circuit boards and other components for this design are available from Communication Concepts, Inc, 508 Millstone Drive, Xenia, OH 45385, tel 513-429-3811/ 220-9677.

[1] Motorola, Inc, Semiconductor Sector Application Notes AN-749 and AN-i 035.

[2] Hilbers, A.H., "Design of HF Wideband Power Transformers," Amperex (Philips) Application Laboratory Report EC06907 and ECO7213.

[3] Blocksome, Aoderick K., "Practical Wideband RF Power Transformers, Combiners and Splitters," *Proceedings of RF Expo*, February 1986.

By Mike Kossor, WA2EBY **From *QST*, March 1999**

A Broadband HF Amplifier Using Low-Cost Power MOSFETs

Part 1—With only 1 W of drive, you'll get over 40 W out—from 160 through 10 meters!

Many articles have been written encouraging experimenters to use power MOSFETs to build HF RF amplifiers. That's because power MOSFETs—popular in the design of switching power supplies—cost as little as $1 each, whereas RF MOSFET prices start at about $35 each!

Over the years, I tucked away several of these articles, waiting for an opportunity to experiment with them. That opportunity came when I received a call from Al, W2OBJ. Al wanted a low-cost linear amplifier to use with his 5 W QRP transmitter when band conditions got poor. Ideally, the amplifier would generate at least 25 W on all the HF bands. Al's inquiry renewed my interest in the topic and provided the motivation I needed to get my project underway.

Al provided me with an extensive list of RF-amplifier construction articles that use power MOSFETs.[1-8] These articles provided useful information about MOSFETs and general guidelines for working with them, including biasing, parasitic-oscillation suppression, broadband impedance-matching techniques and typical amplifier performance data. It was clear from the performance data that Al's desire to get 25 W output from power MOSFETs on 1.8 to 30 MHz was going to be a challenge! The RF output power of most of the amplifiers described in the articles drops off to 10 W or less as frequency increases just to 14 MHz.

An Idea Brews

After hundreds of hours of experimentation, I came up with a design that exceeds our original objective: One watt of input power produces over 40 W of output (after harmonic filtering) from 160 through 10 meters. To the basic amplifier, I added an RF-sensed TR relay and a set of low-pass filters designed to suppress harmonic out-





Figure 1—Jim Wyckoff, AA3X, "1 W In, 30 W out With Power MOSFETs at 80 M," Hints and Kinks, *QST*, Jan 1993, pp 50-51.


J1
XCVR Input
TR SWITCH
C17 0.001
R6 1 k
R7 4.7 k
D2 1N4148
D3 1N4148
C14 2.2 μF 25 V T
C15 0.01
C16 0.001
Q3 2N3904
D4 1N4004
K1A
1
5
D5 1N4744A 15 V 1 W
+28 V
K1B
2
3
4
K1C
6
7
8
to J4 or S1B, Fig 3*
J2 ANT
ATTENUATOR
R9*
R10*
R8*
L3
T1
1
2
3
4
C1 0.1
G
D
S
Q1 IRF510
L1
+5 V
R3 27
C3 0.1
R1 10 k BIAS ADJ
C5 0.1
T2
2
4
1
3
C7 0.1
C8 0.1
C9 47
T3
to J3 or S1A, Fig 3*
Q2 IRF510
C2 0.1
L2
R4 27
C4 0.1
R2 10 k BIAS ADJ
C6 0.1
+28 V
C10 100 μF 35 V
C11 10 μF 35 V
C12 1 μF 50 V
R11 2.4 k 1/2 W
+5 V Source
C13 10 μF 35 V
D1 1N4733A 5.1 V 1 W
Except as indicated, decimal values of capacitance are in microfarads (μF); others are in picofarads (pF); resistances are in ohms; k=1,000.
IC Pins not shown are unused.
T = Tantalum
* = See text.
● = Phasing

Figure 2—Schematic of the MOSFET all-band HF amplifier. Unless otherwise specified, resistors are 1/4 W, 5% tolerance carbon-composition or film units. Equivalent parts can be substituted. Part numbers in parentheses are Mouser (Mouser Electronics, 968 N Main St, Mansfield, TX 76063; tel 800-346-6873, 817-483-4422, fax 817-483-0931; **sales@ mouser.com**; **http://www.mouser.com**); see Note 9.

C1-C8—0.1 μF chip (140-CC502Z104M)
C9—47 pF chip (140-CC502N470J)
C10—100 μF, 35 V (140-HTRL35V100)
C11, C13—15 μF, 35 V (140MLR35V10)
C12—1 μF, 50 V (140-MLRL50V1.0)
C14—2.2 μF, 35 V tantalum (581-2.2M35V)
C15—0.01 μF chip (140-CC502B103K)
C16, C17—0.001 μF chip (140-CC502B102K)
D1—1N4733A, 5.1 V, 1 W Zener diode (583-1N4733A)
D4—1N4004A(583-1N4004A)
D2, D3—1N4148 (583-1N4148)
D5—1N4744A, 15 V, 1 W Zener diode (583-1N4744A)
J1, J2—SO-239 UHF connector (523-81-120)
K1—12 V DPDT, 960 Ω coil, 12.5 mA (431-OVR-SH-212L)
L1, L2—9 1/2 turns #24 enameled wire, closely wound 0.25-in. ID
L3—3 1/2 turns #24 enameled wire, closely wound 0.190-in. ID
Q1, Q2—IRF510 power MOSFET (570-IRF510)
Q3—2N3904 (610-2N3904)
R1, R2—10 kΩ trim pot (323-5000-10K)
R3, R4—27 Ω, 1/2 W (293-27)
R6—1 kΩ chip (263-1K)
R7— 4.7 kΩ chip (263-4.7K)
R8—130 Ω, 1 W (281-130); for 7 dB pad (5 W in, 1 W out)
R9—43 Ω, 2 W (282-43); for 7 dB pad (5 W in, 1 W out)
R10—130 Ω, 3 W (283-130); for 7 dB pad (5 W in, 1 W out)
R8, R10—300 Ω, 1/2 W (273-300); for 3 dB pad (2 W in, 1 W out)
R9—18 Ω, 1 W (281-18); for 3 dB pad (2 W in, 1 W out)
R11—2.4 kΩ, 1/2 W (293-2.4K)
T1—10 bifilar turns #24 enameled wire on an FT-50-43 core.
T2—10 bifilar turns #22 enameled wire on two stacked FT-50-43 cores.
T3—Pri 2 turns, sec 3 turns #20 Teflon-covered wire on BN-43-3312 balun core.
Misc: Aluminum enclosure 3.5∞8∞6 inches (HWD) (537-TF-783), two TO-220 mounting kits (534-4724), heat-sink compound (577-1977), amplifier PC board (see Note 9), heat sink (AAVID [Mouser 532-244609B02]; see text), about two feet of RG-58 coax, #24 enameled wire and #20 Teflon-insulated wire.



A rear panel view showing the heat sink.

put and comply with FCC requirements. The amplifier is built on double-sided PC board and requires *no tuning*. Another PC board contains the low-pass filters. Power-supply requirements are 28 V dc at 5 A, although the amplifier performs well at 13.8 V dc.

Several of these amplifiers have been built and exhibit similar performance. Al has been using his amplifier on each of the HF bands, logging well over 500 contacts in 18 months. Signal reports indicate a noticeable improvement in readability (about two S units on average) over his 5 W rig. No indications of in-stability, CW key clicks or distortion on SSB have been reported. To make it easy for you to duplicate this project, PC boards and parts kits are available, all at a cost of about $100![9]

An Overview of MOSFETs

MOSFETs operate very differently from bipolar transistors. MOSFETs are voltage-controlled devices and exhibit a very high input impedance at dc, whereas bipolar transistors are current-controlled devices and have a relatively low input impedance. Biasing a MOSFET for linear operation only requires applying a fixed voltage to its gate via a resistor. With MOSFETs, no special bias or feedback circuitry is required to maintain the bias point over temperature as is required with bipolar transistors to prevent thermal runaway.[10] With MOSFETs, the gate-threshold voltage increases with increased drain current. This works to turn off the device, especially at elevated temperatures as transconductance decreases and $R_{DS(on)}$ (static drain-to-source *on* resistance) increases. These built-in self-regulating actions prevent MOSFETs from being affected by thermal runaway. MOSFETs do not require negative feedback to suppress low-frequency gain as is often required with bipolar RF transistors. Bipolar transistor gain increases as frequency decreases. Very high gain at dc and low frequencies can cause unwanted, low-frequency oscillation to occur in bipolar transistor RF amplifiers unless negative feedback is employed to prevent it. Low-frequency oscillation can damage bipolar transistors by causing excess power dissipation, leading to thermal runaway.

MOSFET Limitations

Of course, MOSFETs do have their limitations. The high gate impedance and the device structure make them susceptible to electrostatic discharge (ESD) damage. Some easily applied precautions prevent this: Use a soldering iron with grounded tip; use a wrist strap connected to ground through a 1 MΩ resistor to bleed off excess body charge while handling MOSFETs and do all work on an anti-static mat connected to ground via a 1 MΩ resistor.

The sensitivity of a MOSFET's gate to static and high-voltage spikes also makes it vulnerable to damage resulting from parasitic oscillation. This undesired self-oscillation could result in excessive gate-to-source voltage that permanently damages the MOSFET's gate insulation. Another MOSFET limitation is gate capacitance. This parameter limits the frequency at which a MOSFET can operate effectively as an RF amplifier. I recommend reviewing the referents of Notes 1-3 if you are interested in more detailed information about MOSFETs.

Power MOSFET RF Amplifiers

Of the several power MOSFET amplifiers I built to check their performance, the one providing the best performance is the push-pull design described by Jim Wyckoff, AA3X, in *QST* (see Note 3). I used IRF510 power MOSFETs rather than the IRF511s specified. The performance of this power MOSFET amplifier design is summarized in Figure 1; its basic design is very similar to another amplifier described in the referent of Note 4, written 10 years earlier. That amplifier uses a pair of more-expensive MRF138 MOSFETs designed specifically for RF applications.

As Figure 1 shows, the Hints and Kinks amplifier performance is excellent from 1.8 MHz to 7 MHz and far exceeds the published figure of 30 W output on 3.5 MHz. As frequency increases above 10 MHz, however, output drops off rapidly, falling below 10 W above 21 MHz. (These levels were measured after harmonic filtering.)

Although the amplifier is identified as stable, my first attempt at duplicating the amplifier resulted in oscillations that destroyed one of the IRF510s. I was puzzled by this. At first, I thought the problem was caused by my substitution of the slightly more robust IRF510 MOSFETs for the called-for IRF511s. That idea proved wrong when my second attempt to power up the amplifier with IRF511 MOSFETs installed also resulted in a blown IRF511. (Thank goodness these are $1 power MOSFETs, not $35 RF MOSFETs!). I finally achieved good stability when I added a small amount of inductance in series with the MOSFET source to ground (just two turns of #24 wire, 0.125 inch diameter). With this added inductance, I was able to remove the ferrite beads from the circuit without any sign of instability. I believe the substitution of the IRF510 and minimizing source lead inductance are the reasons I obtained significantly higher RF output power and wider bandwidth than described in the referent of Note 3. This experiment underscores the need to observe *exact* construction techniques and physical layout if similar performance is to be expected. Even though I used PC board construction, I got significantly different results because my layout was not the same as the author's.

Modifying the Design

Although the amplifier performed better than expected, its bandwidth was significantly less than desired. Considerable experimentation (and I do mean considerable!) resulted in the circuit shown in Figure 2. This amplifier consists of two power MOSFETs operating in push-pull and employs an RF-sensed TR relay.

During receive, TR relay K1 is deenergized. Signals from the antenna are connected to J2 and routed through K1 to a transceiver connected to J1. (This path loss is less than 0.3 dB from 1.8 MHz through 30 MHz.) In transmit, RF voltage from the transceiver is sampled by C17 and divided by R6 and R7. D2 and D3 rectify the RF voltage and charge C16. Q3 begins conducting when the detected RF voltage across C16 reaches approximately 0.7 V. This energizes K1, which then routes the transmitted RF signal from J1



Figure 3—Low-pass filter schematic. In some cases, the actual filter component values differ from the calculated values of a standard 50 Ω-input filter. Such differences improve the impedance matching between the amplifier and the load. Capacitors are all dipped mica units.

C1, C3, C5—1500 pF (5982-19-500V1500)
C2—2700 pF (5982-19-500V2700)
C4, C6, C8—820 pF (5982-19-500V820)
C7, C9—430 pF (5982-15-500V430)
C10, C12, C14—330 pF (5982-19-500V330)
C11—560 pF (5982-19-500V560)
C13, C17—180 pF (5982-15-500V180)
C15—200 pF (5982-15-500V200)
C16, C18—100 pF (5982-10-500V100)
S1—2 pole, 6 position rotary (10YX026)
Misc: low-pass filter PC board (see Note 9)

to the input of the amplifier and sends the output of the amplifier to the antenna at J2. RF-sensed relay response is very fast. No noticeable clipping of the first CW character has been reported.

I made provisions to include an RF attenuator (consisting of R8, R9 and R10) to enable adjusting the amplifier input power to 1 W. (The parts list contains resistor values to reduce the output of 2 or 5 W drivers to 1 W.) The 1 W signal is then applied to the primary of T1 via an input impedance-matching network consisting of L3. T1 is a 1:1 balun that splits the RF signal into two outputs 180 degrees out of phase. One of these signals is applied by C1 to Q1's gate. The other signal is routed via C2 to Q2's gate. The drains of Q1 and Q2 are connected to the primary of output transformer T3, where the two signals are recombined in phase to produce a single output. T3 also provides impedance transformation from the low output impedance of the MOSFETs to the 50 Ω antenna port. Dc power is provided to the drains of Q1 and Q2 by phase-reversal choke, T2. This is a very effective method to provide power to Q1 and Q2 while presenting a high impedance to the RF signal over a broad range of frequencies. The drain chokes for Q1 and Q2 are wound on the same core, and the phase of one of the chokes (see the phasing-dot markings on T2) is reversed. C9 increases the bandwidth of impedance transformation provided by T3, especially at 21 MHz.

The 5 V bias supply voltage is derived from 28 V by Zener diode D1 and current-limiting resistor R11. Bypass capacitors C3, C4, C5, C6 and C13 remove RF voltages from the bias supply voltage. Gate bias for Q1 and Q2 is controlled independently. R1 adjusts Q1's gate-bias voltage via R3 and L1. R2 works similarly for Q2 via R4 and L2.

At low frequencies, the amplifier's input impedance is essentially equal to the series value of R3 and R4. L1 and L2 improve the input-impedance match at higher frequencies. The low value of series resistance provided by R3 and R4 also reduces the Q of impedance-matching inductors L1 and L2, which improves stability. Dc blocking capacitors C1 and C2 prevent loading the gate bias-supply voltage.

C14 keeps transistor Q3 conducting and K1 energized between SSB voice syllables or CW elements. Without C14, K1 would chatter in response to the SSB modulation envelope and fast keying. Increasing the value of C14 increases the time K1 remains energized during transmit. The reverse voltage generated by K1 when the relay is deenergized is clamped to a safe level by D4. D5 drops the 28 V supply to 13 V to power 12 V relay K1. D5 can be replaced with a jumper if K1 has a 28 V dc coil or if you intend to operate the amplifier with a 13.8 V dc supply.

Harmonic Filtering

Although biased for class AB linear operation, this amplifier (like others of its type) exhibits some degree of nonlinearity, resulting in the generation of harmonics. This push-pull amplifier design cancels even-order harmonics (2f, 4f, 6f, etc) in the output transformer, T3. Odd-order harmonics are not canceled. Second-order harmonics generated by the amplifier are typically less than 30 dBc (30 dB below the carrier) whereas third-order harmonics are typically only 10 dBc. FCC regulations require all HF RF-amplifier harmonic output power to be at least 40 dBc at power levels between 50 to 500 W. To meet this requirement, it is common practice for HF amplifiers to use low-pass filters. Separate low-pass filters are needed for the 160, 80, 40 and 30 meter bands. The 20 and 17 meter bands can share the same low-pass filter. So, too, the 15, 12 and 10 meter bands can share a common low-pass filter; see Figure 3.

Switching among the six filters can be a messy wiring problem, especially on the higher-frequency bands where lead lengths should be kept short for optimum performance. This problem is solved by mounting all six low-pass filters on a PC board. A two-pole, six-position rotary switch (S1) mounted directly on the same PC board manages all filter interconnections. One pole of S1 connects the amplifier output to one of the six filter inputs, while S1's other pole simultaneously connects the corresponding filter's output to the TR relay, K1. Only two coaxial-cable connections are required between the RF amplifier and the low-pass filter board.

Next Month

In Part 2, I'll wrap up with amplifier construction and adjustment, and discuss the amplifier's overall performance. See you then!

Notes

[1] Doug DeMaw, W1FB, "Power-FET Switches as RF Amplifiers," *QST*, Apr 1989, pp 30-33. See also Feedback, *QST*, May 1989, p 51.

[2] Wes Hayward, W7ZOI, and Jeff Damm, WA7MLH, "Stable HEXFET RF Power Amplifiers," Technical Correspondence, *QST*, Nov 1989, pp 38-40; also see Feedback, *QST*, Mar 1990, p 41.

[3] Jim Wyckoff, AA3X, "1 Watt In, 30 Watts Out with Power MOSFETs at 80 Meters," Hints and Kinks, *QST*, Jan 1993, pp 50-51.

[4] Doug DeMaw, W1FB, "Go Class B or C with Power MOSFETs," *QST*, March 1983, pp 25-29.

[5] Doug DeMaw, W1FB, "An Experimental VMOS Transmitter", *QST*, May 1979, pp 18-22.

[6] Wes Hayward, W7ZOI, "A VMOS FET Transmitter for 10-Meter CW," *QST*, May 1979, pp 27-30.

[7] Ed Oxner, ex-W9PRZ (SK), "Build a Broadband Ultralinear VMOS Amplifier," *QST*, May 1979, pp 23-26.

[8] Gary Breed, K9AY, "An Easy-to-Build 25-Watt MF/HF Amplifier," *QST*, Feb 1994, pp 31-34.

[9] Parts for this project are available in five modular kits. The following three kits are available from Mouser Electronics (Mouser Electronics, 958 N Main St, Mansfield, TX 76063; tel 800-346-6873, 817-483-4422, fax 817-483-0931; **sales@mouser.com**; **www.mouser.com**): Amplifier components (Mouser P/N 371-HFAMP1) consisting of the amplifier PC board and all PC-board-mounted components (except for the ferrite cores). Price: $35, plus shipping. Amplifier hardware kit (Mouser P/N 371-HFAMP2) consisting of the aluminum enclosure, two UHF connectors, two TO-220 mounting kits, AAVID heat sink and one container of heat sink compound. Price: $30 plus shipping. Low-pass filter kit (Mouser P/N 371-HFAMP3) consisting of the low-pass filter PC board, rotary switch and all PC-board-mounted capacitors (inductor cores are *not* included). Price: $35, plus shipping. Part-placement diagrams accompany the PC boards.

PC boards only are available from Mouser Electronics: HF amplifier board (#371-AMPPWB-2); filter PC board (#371-LPPWB-2). Price $15 each, plus shipping.

The following two kits are available from Amidon Inc (Amidon, Inc, 240 Briggs Ave, Costa Mesa, CA 92626; tel 1-800-898-1883, 714-850-4660, fax 714-850-1163): Amplifier ferrite kit (Amidon P/N HFAFC) containing the ferrite cores, balun core and magnet and Teflon wire to wind the transformers for the HF amplifier. Price: $3.50 plus shipping. Low-pass filter cores kit (Amidon P/N HFFLT) containing all iron cores and wire for the low-pass filters. Price: $4.50 plus ship.

[10] See Motorola Application Reports Q1/95, HB215, *Application Report AR346*.

Thermal runaway is a condition that occurs with bipolar transistors because bipolar transistors conduct more as temperature increases, the increased conduction causes an increase in temperature, which further increases conduction, etc. The cycle repeats until the bipolar transistor overheats and is permanently damaged.

By Mike Kossor, WA2EBY From *QST*, April 1999

A Broadband HF Amplifier Using Low-Cost Power MOSFETs

Part 2—Let's put the finishing touches on this all-band HF amplifier!

Last month,[11] *I covered the history and development of this 40 W (average) amplifier. I'm sure you're anxious to get* your *amplifier finished and on the air, so let's get going!*

Amplifier Construction

The amplifier is constructed on a double-sided PC board with plated through holes to provide top-side ground connections. I used chip resistors and capacitors to simplify construction, but leaded capacitors may work if lead lengths are kept short. First, assemble all chip capacitors and resistors on the PC board. Tweezers help to handle chip components. Work with only one component value at a time (chip caps and resistors are very difficult to identify!). Chip capacitor and resistor mounting is simplified by tinning one side of the PC board trace with solder before positioning the capacitor or resistor. Touch the soldering iron tip to the capacitor or resistor to tack it in place. Finish mounting by soldering the opposite side of the component. *Don't apply too much heat to chip capacitors.* The metalized contacts on the capacitor can be damaged or completely removed if too much heat is applied. Use a 15 to 20 W soldering iron and limit soldering time to five seconds.

Mount axial-leaded resistors, diodes and remaining capacitors next. To avoid damaging them, mount inductors and transformers last. L1 and L2 are wound on a 0.25-inch drill-bit shaft. By wrapping the wire around the shaft 10 times, you'll get 9½ turns. The last turn arcs only a half-turn before entering the PC board. L3 is wound on a 0.190-inch diameter drill bit with 3½ turns wound the same way as L1 and L2. Mounting K1 is simplified by first bending all its leads 90° outward so it lies flat on the PC board. Use a wrist strap connected to ground through a 1 MΩ resistor to bleed off static body charge while handling MOSFETs, and do the work on an anti-static mat connected to ground via a 1 MΩ resistor. The gate input can be damaged by electrostatic discharge!

When winding T3, wind the primary first and add the secondary winding over the primary. Be sure to use Teflon-insulated wire for T3's windings; the high operating temperatures encountered will likely melt standard hook-up wire insulation.



Figure 4—RF output power comparison of the Hint and Kink amplifier and this design.





Figure 5—Efficiency comparison of the Hint and Kink amplifier and this one.



Figure 6—Input SWR comparison of the two amplifiers.

Heat Sinking

Together, Q1 and Q2 dissipate up to 59 W. A suitable heat sink is required to prevent the transistors from overheating and damage. I used an AAVID 244609B02 heat sink originally designed for dc-to-dc power converters. The amplifier PC board and heat sink are attached to an aluminum enclosure by two #4-40 screws drilled through the PC board, enclosure and heat sink at diagonally opposite corners. A rectangular cutout in the enclosure allows Q1 and Q2 direct access to the heat sink. This is essential because of the large thermal impedance associated with the TO-220 package (more on this topic later). Mark the locations of the transistor-tab mounting-hole location in the center of the heat sink in between the cooling fins. Disassemble the heat sink to drill 0.115 inch holes for #4-40 mounting screws, or tap #4-40 mounting holes in the center of the heat-sink fins.

Use mica insulators and grommets when mounting Q1 and Q2 to prevent the #4-40 mounting screws from shorting the TO-220 package drain connections (tabs) to ground. Coat both sides of the mica insulator with a *thin* layer of thermal compound to improve the thermal conduction between the transistor tab and the heat sink. Be sure to install the mica insulator on the heat sink *before* assembling the amplifier PC board to the enclosure and heat sink. The mica insulators are larger than the cut outs in the PC board, making it impossible to install them after the PC board is mounted.

Low-Pass Filter Construction

Inductor winding information for the low-pass filters is provided in Table 1.

Single Band

A PC-board trace is available on the amplifier PC board next to amplifier output (J3) to allow the installation of a single-band low-pass filter between the terminals of J3 and K1's input, J4. This is handy if you intend to use the amplifier on one band only. The input inductor of the low-pass filter connects from J3 to the single PC trace adjacent to J3. The output inductor connects in series between the single PC trace to J4. The three filter capacitors connect from J3, J4 and the PC-board trace near J3 to ground. *This single trace is not used when multiple filters are required.* Remember to remove the single trace adjacent to J3 on the amplifier PC board before attaching the amplifier board between the RF connectors on the enclosure's rear panel.

Multiple-Band Filters

Using the amplifier on more than one band requires a different approach. A set of

Table 1
Low-Pass Filter Inductor Winding Information

(Refer to Figure 3 in Part 1))

Inductor Number	*No. of Turns*	*Core*
L1, L2	30 turns	T-50-2
L3, L4	22 turns	T-50-2
L5, L6	16 turns	T-50-2
L7, L8	14 turns	T-50-2
L9, L10	11 turns	T-50-6
L11, L12	8 turns	T-50-6

Note: All inductors are wound with #22 enameled wire except for L1–L4, which are wound with #24 enameled wire.



Figure 7—RF output power versus supply-voltage of this amplifier.



Figure 8—Thermal performance of the amplifier during key-down conditions.



Figure 9—Thermal performance of the amplifier during simulated CW conditions.

six low-pass filters is built on a double-sided PC board with plated through holes to provide top-side ground connections. A PC-board mount, two-pole, six-position rotary switch does all low-pass filter selection. Silver-mica, leaded capacitors are used in all the filters. On 160 through 30 meters, T-50-2 toroids are used in the inductors. T-50-6 toroids are used for inductors on 20 through 10 meters. The number of turns wound on a toroid core are counted on the toroid's OD as the wire passes through the core center (*The ARRL Handbook* [12] provides complete details for winding toroids). Assemble one filter section at a time starting with the 160, 80, 40-meter filter, then the 30-meter filter. With the switch mounting position at your upper left, the filter input (C1) is near the top edge of the board and the filter output (C3) is near the bottom edge. *The last two filters are out of sequence;* the 15-10 meter filter comes *before* the 20-17 meter filter) and the inputs/outputs are reversed to simplify the PC-board layout. The input capacitors, C13 and C16, are mounted on the board *bottom edge*, and output capacitors, C15 and C18, are on the *top edge*.

Use care when assembling the rotary switch. All 14 terminals must fit through the PC board without damaging or bending the pins. Make sure there are no bent pins before you attempt assembly. Insert the rotary switch into the PC board. Do *not* press the rotary switch all the way into the PC-board holes flush with the ground plane! If you do, the top flange of the signal pins may short to the ground plane.

Bias Adjustment

The biasing procedure is straightforward and requires only a multimeter to complete. First, set R1 and R2 fully counterclockwise, (0 V on the gates of Q1 and Q2). Terminate the RF input and outputs with a 50 Ω load. Next, connect the 28 V supply to the amplifier in series with a multimeter set to the 0-200 mA current range. Measure and record the idling current drawn by the 5 V bias supply. The value should be approximately 9.5 mA (28 – 5.1 V) / 2.4 kΩ = 9.5 mA). Set Q1's drain current to 10 mA by adjusting R1 until the 28 V supply current increases by 10 mA above the idling current (9.5 + 10 = 19.5 mA). Next, adjust R2 for a Q2 drain current of 10 mA. This is accomplished by adjusting R2 until the 28 V supply current increases by an additional 10 mA (to 29.5 mA).

Amplifier Performance

With a 28 V power supply and 1 W of drive, the RF output power of this amplifier exceeds 40 W from 1.8 MHz through 28 MHz. Peak performance occurs at 10 MHz, providing about 75 W after filtering! A performance comparison between this amplifier and my modified version of the Hint and Kink amplifier mentioned earlier is shown in Figure 4.

As shown in Figure 5, this amplifier achieves an efficiency of better than 50% over its frequency range, except at 7 MHz where the efficiency drops to 48%. In contrast, the Hint and Kink amplifier delivers greater efficiency between 1.8 and 7 MHz, but it drops rapidly to only 20% as frequency is increased.

Figure 6 compares the input SWR of the two amplifiers. The Hint and Kink amplifier's SWR is acceptable (< 2:1) only at 1.8 MHz. This amplifier is better, however it, too, exceeds 2:1 above 14 MHz. The input SWR of this amplifier can be improved to better than 2:1 on all bands by adding a 3 dB pad (R8-R10 of Figure 2) at the input and supplying 2 W to the pad input. This keeps the amplifier drive at 1 W.

Figure 7 graphs this amplifier's RF output power as a function of drain supply voltage. During this test, the amplifier RF drive level was kept constant at 1 W. As you can see, even when using a 13.8 V dc supply, the amplifier provides over 10 W output (a gain of more than 10 dB) from 1.8 to 30 MHz.

Operation

The amplifier requires no tuning while operating on any HF amateur band. You must, however, *be sure to select the proper low-pass filter prior to transmitting*. If the wrong low-pass filter is selected, damage to the MOSFETs may result. Damage will likely result if you attempt to operate the amplifier on a band with the low-pass filter selected for a lower frequency. For example, driving the amplifier with a 21 MHz signal while the 1.8 MHz low-pass filter is selected will likely destroy Q1 and/or Q2.

The amplifier can also be damaged by overheating. This limitation is imposed by the TO-220 packages in which Q1 and Q2 are housed. The thermal resistance from junction to case is a whopping 3.5°C/W. This huge value makes it virtually impossible to keep the junction temperature from exceeding the +150°C target for good reliability. Consider the following conditions: key down, 1 W input, 53 W output on 7 MHz (worst-case band for efficiency). The amplifier consumes 28 V × 4 A = 112 W, of which 53 W are sent to the antenna, so 59 W (112 W – 53 W = 59 W) are dissipated in Q1 and Q2. Assuming equal current sharing between Q1 and Q2, each transistor dissipates 29.5 W. To keep the transistor junction temperature below +150°C requires preventing the transistor case temperature from exceeding 46.8°C (150 – [3.5 × 29.5]) while dissipating 29.5 W. Also, there is a temperature rise across the mica insulator between the transistor case and heat sink of 0.5°C/W. That makes the maximum allowable heat-sink temperature limited to 46.8 – (0.5 × 29.5) = 32°C. In other words, the heat sink must dissipate 59 W (29.5 from each transistor) with only a 7°C rise above room temperature (25°C). Even if the junction temperatures were allowed to reach the absolute maximum of 175°C, the heat sink temperature must not exceed 57°C. Accomplishing this requires a heat sink with a thermal resistance of (57 – 25) / 59 = 0.54°C/W. This is far less than the 1.9°C/W rating of the AAVID 244609B02 heat sink I used. The situation may seem bleak, but all is not lost. These calculations make it clear that the amplifier should not be used for AM, FM or any other continuous-carrier operation. The amplifier should be used only for CW and SSB operation where the duty cycle is significantly reduced.

Thermal performance of the amplifier is illustrated in Figure 8. Data was taken under dc operating conditions with power-dissipation levels set equal to conditions under RF operation. A RadioShack brushless 12 V dc fan (RS 273-243A) blows air across the heat sink. Key down, the maximum rated junction temperature is reached in as little as five seconds as illustrated in Figure 8. Prolonged key-down transmissions should be avoided for this reason.

Under intermittent CW conditions, the situation is very different. Transistor-case temperatures reached 66°C after operating four minutes under simulated CW conditions at 20 WPM (60 ms on, 60 ms off). The corresponding junction temperature is +141°C (based on an equivalent RMS power dissipation of 21.7 W per transistor). This keeps the junction temperature under the 150°C target (see Figure 9). One simple way to reduce power dissipation is to reduce the power-supply voltage to 24 V. RF output power will decrease about 10 W from the maximum levels achieved with a 28 V supply.

From a thermal standpoint, the IRF510 power MOSFET is a poor choice for this RF amplifier application. Although I must say I am impressed with the robustness of these devices considering the times I spent testing them key down, five minutes at a time, without failure. Q1 and/or Q2 may need to be replaced after a year or so of operation because of the compromise in reliability. Considering their low cost, that is not a bad trade-off.

Stability

High gain, broad bandwidth and close input/output signal routing (within the TR relay) all work against stability. With a good load (< 2:1 SWR) the amplifier is stable from 1.8 MHz through 39 MHz. Oscillation was observed when the transmitter frequency was increased to 40 MHz. The output load match also affects stability. Oscillation was observed on 27.5 MHz when the load SWR was 3:1. This should not be a problem since the frequency is outside the ham bands. I spent a great deal of time trying to make this design unconditionally stable even with loads exceeding 3:1 SWR without sacrificing output power (gain) at 28 MHz without success. I did identify some reasonable compromises.

One of the easiest ways to improve stability and the input SWR seen by the RF source is to add an RF attenuator (pad) at the amplifier input. An attenuator is absolutely required if the transmitter (driver) provides more than 1 W to the amplifier. R8, R9 and R10 form an RF attenuator that attenuates the transmitter drive level, but does not attenuate received signals because it is only in the circuit when K1 is energized. To drive this amplifier with a 2-W-output transmitter requires use of a 3-dB pad. The pad improves the amplifier input SWR and the isolation between the amplifier's input and output. The drawback is that 1 W is wasted in the pad. Likewise, a 5-W driver requires use of a 7-dB pad, but 4 W are wasted in the pad. (Values for R8, R9 and R10 to make a 3-dB pad and a 7-dB pad are given in the parts list.) Installing a pad requires cutting the PC-board trace *under R9*, otherwise R9 would be shorted out by the trace. Make a small cut (0.1 inch wide) in the trace under R9 before soldering R9 in position. R8 and R10 have the same values, but may have different power ratings. Connect R10 between the RF input side of R9 and ground. Install R8 between the amplifier side of R9 and ground.

An impedance mismatch between the output of a 1-W-output driver and the amplifier input can be a source of instability. (Obviously, if the driving transmitter's output power is only 1 W, you can't use a pad as described earlier.) If you encounter stability problems, try these remedies: Place a resistor in parallel with L1 and L2 to decrease the Q of the amplifier matching network (try values between 50 and 220 Ω). Try reducing the value of L3 or eliminating L3 entirely. Both of these modifications improve stability, but reduce the amplifier's output power above 21 MHz.

Summary

This project demonstrates how inexpensive power MOSFETs can be used to build an all-band linear HF power amplifier. Frequency of operation is extended beyond the limits of previous designs using the IRF510 and improved input-impedance matching. Long-term reliability is recognized as a compromise because of the poor thermal performance of the low-cost TO-220 package.

If you have been thinking about adding an amplifier to your QRP station, this project is a good way to experiment with amplifier design and is an excellent way to become familiar with surface-mount "chip" components. I made arrangements with Mouser Electronics and Amidon Inc to provide parts kits for this project at a discounted price (see the parts list in Part 1). These parts kits make it very easy to get started and more economical to "homebrew" this project.

Acknowledgments

I want to thank the following individuals associated with this project: Harry Randel, WD2AID, for his untiring support in capturing the schematic diagram and parts layout of this project; Al Roehm, W2OBJ, for his continued support and encouragement in developing, testing, editing and publishing this project; Larry Guttadore, WB2SPF, for building, testing and photographing the project; Dick Jansson, WD4FAB, for thermal-design suggestions; Adam O'Donnell, N3RCS, for his assistance building prototypes; and my wife, Laura, N2TDL, for her encouragement and support throughout this project.

Notes

[11] Mike Kossor, "A Broadband HF Amplifier Using Low-Cost Power MOSFETs—*Part 1*," *QST*, Mar 1999, pp 40-43.

[12] R. Dean Straw, N6BV, *The 1999 ARRL Handbook for Radio Amateurs*, (Newington: ARRL), 76th ed, pp 25-23*ff.*

By Zack Lau, KH6CP/1 **From *QEX*, May 1992**

A 1.8 to 54 MHz 5-Watt Amplifier

Need a rugged and stable amplifier for your multiband QRP rig? Not only has the design been optimized on a pricey computer program called *Touchstone* (by eesof) for unconditional stability, it has actually survived a variety of poor loads—it was used to sweep filters with 5 W of RF. The gain of the two stage amplifier was measured to be between 28 and 30 dB in the amateur bands, though there is another dB of gain around 37 MHz.

For ruggedness and ease of design, a Motorola MRF 137 was selected as the final transistor. While the MRF 138 may be more linear, insufficient design information was available to ensure a stable design. While some amateurs will balk at the high cost of these devices ($24 in November 1991), such savings are easily lost if the cheaper device has a habit of blowing up. Also, one picks up a real clean SSB signal—the high-order IMD products are way down compared to typical bipolar amplifiers. For instance, the worst IMD on 3.5,7,14 and 28 MHz was –38 dB on 28 MHz, with the 5th order products 61 dB down (relative to PEP). The device was putting out 5-W PEP while being biased at 0.5 A (28-V supply).

Perhaps the biggest flaw is the power requirement— these FETs really like to see high voltages for best performance, and the MRF 137 is no exception. I biased the MRF 137 for 0.55 A and 28.2 V. It drew 0.6 A when putting out 4.6 W at 28 MHz. The driver runs off your normal 12-V supply.

The input amplifier shown in Fig 1a is pretty straightforward—a bipolar 2N5109 with the feedback networks adjusted to compensate the gain of the MRF 137. A series network of a 470-a resistor and a 12-pF capacitor was tacked between the collector and ground to ensure stability at all frequencies. The MRF 137 rolls off a few dB at 54 MHz, but the bipolar amplifier adequately compensates for this gain deficiency. The input return loss is better than 18 dB between 1.4 and 29.9 MHz, but degrades to 12 dB at 50 MHz. The input SWR was not tested with poor loads.

By itself, the MRF 137 amplifier stage shown in Fig 1b (see next page) makes an excellent 16-dB gain block between 1 and 32 MHz, having less than 0.5 dB of gain variation. The transmission line transformer on the input seems to help the input return loss/SWR, keeping these numbers above 18/below 1.3 to 1 between 1 and 50 MHz. I suppose that putting another transmission line transformer on the output could be used to get a more powerful amplifier with less gain over a similar frequency range, but this variation has not been investigated.

The simplest circuit board I could think of was used— I cut two pads in a piece of double-sided circuit board for the gate and drain leads. Then I wrapped the edges of the board with copper tape and soldered it down for good grounding. After making holes for the MRF 137 transistor and the mounting screws in the board and a spacer, made of 0.050-inch aluminum, I attached the spacer, the circuit board, and the MRF 137 to a heat sink tapped with 4-40 screw holes. Standard ground-plane construction was used to attach the other parts. The 2N5109 amplifier was built on its own ground plane—RF amplifiers work better if there isn't too much gain in one place. Three additional amplifiers were built by Mike Gruber, WA1SVF, for use in the lab. He noted that R8 had to be changed from 4.7 kΩ to 1 kΩ to bias the amplifiers at 0.5 amps. Apparently, the MRF 137s he used have a higher gate threshold voltage. Otherwise, performance was as expected.



Fig 1a—Low-level amplifier designed to compensate for the gain rolloff from the power amplifier.
Q1—2N5109, 2.5-W heat-sinked RF transistor, f_T is 1200 MHz.
T1—15 turns bifilar #28 on FT-37-43 toroid core.


R3
1.5 k
1/2 Watt
R4
1.2 k
1/2 Watt
L1
3.9 µH
+28
DC Input
R5
1.2 k
1/2 Watt
C4
4.7 µF T
50 V
C7
0.1
R6
1.0 k
1/2 Watt
RFC1
C3
0.1
RF
OUTPUT
+28
DC Input
RF
INPUT
T2
R2
8.2
C1
0.1
C2
0.1
Q2
MRF137
U1
78L05
R1
22
OUT
IN
GND
R10
1.5 k
C6
0.47 T
35 V
R8
4.7 k
R9
10 k
bias
adjust
R7
4.7 k
C5
0.1
(B)

Fig 1b—5-W TMOS power amplifier.
L1—26 turns no. 26 enameled wire on T-44-2 toroid, 3.9 µh.
Q2—MRF 137 transistor.
R9—10-kΩ turn potentiometer for bias setting.
RFC1—21 turns of no. 26 enameled wire on FR-37-67 toriod.
T2—4 turns 25-Ω coax on FT-50-43 toroid core. The 25-Ω coax is actually two 50-Ω coax run side-byside. The prototype used RG-196/U coax.
U1—78L05 5-V regulator.

By Joel Paladino, N6AMG

From *QST*, September 1992

An Experimental Solid-State Kilowatt Linear Amplifier for 2 to 54 MHz

Many kilowatt amplifiers could anchor a small boat, and don't cover 6 meters. Combined with its power supply, *this* kilowatt weighs less than 35 pounds.

This article describes progress toward achieving a well-defined goal: building the smallest possible MF/HF/VHF amplifier capable of at least 1000 watts output. Nicknamed the Solid State Kilowatt (SSKW), the project has its roots in an article by Helge Granberg of Motorola in October 1986 *RF Design*.[1] Two water-cooled amplifiers of that design, built by Mike Staal (K6MYC) of M2, had many problems. Some of them were device-related; others, power-supply related. (More about these issues later.) In February 1990 I rebuilt one of the water-cooled units using the old design and two new transistors. Optimized for 50 MHz, this amplifier could just reach the 1000-watt level. After using it for three weeks of South Pacific DXpeditioning, I decided to construct an air-cooled unit. I spent the spring, summer and fall of 1990 building the SSKW and getting it ready for another DXpedition in the fall.



Circuit Description

Motorola's article reprint AR-347 describes the basic amplifier design. July 1990 QEX also carried an article about it.[2] Fig 1 shows the amplifier schematic. Briefly, the circuit consists of two MRF154 RF power MOSFETs in push-pull. Each of these transistors is capable of 600 watts output up to 100 MHz. The input and output transformers, 9:1 and 1:9, respectively, use cores of #67 ferrite material. The output transformer's 1:9 ratio is a compromise that is optimum at about 800 watts.

Incorporating the Motorola building block into a DXpedition-ready package required experimentation and problem-solving, as I described at the 1991 Central States VHF Conference.[3] Here's where the system stands today.

TR Switching

The SSKW includes TR relays that bypass the Fig 1 circuitry in receive mode. I designed their control circuitry to eliminate the possibility of the high RF fields in the amplifier compartment causing relay falsing problems, and to simplifies field repair by keeping parts count low. The relays are sequenced to allow the output relay to close before the amplifier puts out power. Because relays take a few milliseconds to operate, sequencing is necessary to keep the relay from hot-switching the amplifier output. (Hot-switching 1 kW will destroy a relay rapidly!)

This design has two small problems. For the short time it takes the amplifier's input relay to close on switching from receive to transmit, the exciter operates without a load. This can be remedied by delaying the exciter keying. The other problem is the relay's closure time changes as the relay heats. This can be solved two ways: Use external electronics to do the delay, or temperature-compensate for the resistance change.

SWR Protection

I haven't yet built SWR protection into the amplifier. In January 1983 *QST*, Helge Granberg described an SWR-protection circuit for a 2- to 30-MHz amplifier.[4] A phone conversation with Helge indicated that this circuit will work to 54 MHz, so it should suffice. How much mismatch the MRF154s can tolerate is unknown, however, so I don't

6-Meters: DXpeditioning with a Difference

Making the most of 6 meter DXpeditioning depends on knowing where and when to go If you want to work Europe from the Canary Islands summertime is best because sporadic E propagation is best then If you want to work the US from EA8 go when fall shifts into winter to take advantage of east/west F2 layer propagation It s always more exciting to go to a rare place but not necessarily more fun'

Once you ye decided on a DXpedition site plan your travel on the assumption that you Il want to stay on site for at least two weeks This gives you about a 50% better chance of having good openings within a given month

Pay particular attention to the RF prospects of your accommodations Ideally you d be able to see ocean in all directions If that s not possible all s not lost A direct oceanic path isn t always the best propagation may be better over the backscatter path You Il want to get your antenna up as high as possible to minimize radiation angle and AFI And consider EMI and NI possibilities carefully Some areas of the world use NTSC channel 2; others, PAL on channel 1—right in the middle of the band! If your RF gets into a resort's CATV system you Il drive 60 televisions crazy rather than one or two.

Chapter 6 of *The ARRL Operating Manual* covers DXpedition power, health, licensing and logistical concerns in detail so see that book for more about those topics Ill add one thing though It helps to find a local ham with FAX capability as well as HF who can help you with questions on licensing and living accommodations

This can take 80% of the surprises out of the expedition!

Equipment

What I bring and use on 6-meter DXpeditions is based largely on the experiences of Jim Treybig, W6JKV, in his many years of 6 meter DXpeditioning. The core of the approach is pretty much this: Run as much power as permitted and bring as big an antenna as possible. There are practical limits to this, but let your ingenuity direct your thoughts. I consider 100 W as a minimum, 500 watts good and 1000 watts as optimum. High power lets you take advantage of scatter paths that simply won't work at 100 watts. It's very frustrating to hear a well equipped station that you cannot work!

Which Antenna?

A DXpedition antenna must be compact, light and reproducible The Yagi I use has six elements on a 30 foot boom. Optimized by Brian (K6STI) Beezley's Yagi optimization program *YO* it's fed with a T match and a half wave balun. Its boom folds down to two 40 inch sections, each 2 inches in diameter. Most of the element pieces fit inside the two 40-inch sections. The antenna is light enough to lift with one hand.

A rotatable antenna is *mandatory.* You'll need to turn your antenna to find the best direction of propagation. The antenna mast, 20 feet long overall, consists of 40 inch sections of 2-inch aluminum tubing joined with internal sleeves. The rotator is at the mast bottom and there's a slip ring at the mast top just below the Yagi (Having the rotator at the bottom makes putting the antenna up easier by minimizing weight at the upper end of the mast.)

I use Dacron rope for guying. How much rope should you

The author's setup at CN2JP, Rabat, Morocco. Efficiency counts more than neatness while you're busy making 900 contacts on 6 and 20 on 2-meter EME! *(DXpedition photos courtesy of the author)*



DXpeditioning would be no fun at all without antenna work!

want to use the SSKW to calibrate its own SWR-protection circuitry!

The amplifier's output can be reduced two ways: by turning down the exciter power via amplifier-generated ALC, or by reducing the amplifier bias. (These are enhancement-mode FETs, so positive bias is necessary to turn them on.) The ALC option is better because it does not affect the amplifier's linearity. A no-output-load condition must shut down the amplifier as quickly as possible.

Overdrive Protection

Overdrive can destroy power MOSFETs instantly, so a drive limit control is essential. A threshold detector should be incorporated. The SSKW's input includes a 5-dB attenuator so 100-watt exciters can drive the amplifier without damaging it. If the 5-dB pad fails to attenuate, or if the exciter puts out too much power, the amplifier must be shut down rapidly.

The amplifier must also be shut down if the transistors' flange temperature exceeds 40°C. Shutdown can be done two ways, depending on how the amplifier is used. The first way is to just turn down the bias, which changes the amplifier's linearity. The second way is to totally turn off the amplifier. This must be done gracefully so the amplifier does not shut down while producing full power. The following shutdown sequence is essential: (1) Turn down the bias; (2) open the input relay; and (3) open the output relay.

Bias

The SSKW's bias circuitry is straightforward. R8's value must be tailored to the particular MRF154s used. If the bias decreases too fast with rising temperature, increase the value of R8. The LM723's input voltage must never exceed 40 volts.

Output Filtering

Filtering must be added to make the amplifier comply with FCC signal-purity regulations. The reactance of these filters away from their intended passbands must be taken into account. Absorptive low-pass filters should be considered. Such filters dissipate harmonic energy as heat rather than reflecting it back to the amplifier transistors.

Packaging

I intended to make this amplifier as small and light as possible. Most of the amplifier's weight is its aluminum heat sink take? Simple: Estimate what you need, multiply by 2.5 and you might make it! I usually bring two diameters, $^{3}/_{16}$ and $^{1}/_{8}$ inch.

Radios

Bring at least two radios: one for HF liaison (usually at 10 meters) and another for 6 meters. I recommend maximizing redundancy by taking two radios that both cover 10 and 6. At least one of the 6-meter rigs should include an excellent noise blanker for power-line problems and motorbikes. It must also be able to drive a kilowatt amplifier to full output on 6. (I use one Kenwood TS-680S and one ICOM IC-575.) Receive coverage between 10 and 6 meters is another plus. Where it's allowed, listening to nonamateur services between 45 and 50 MHz can be very important in determining the direction of propagation.

Additional Gear

Bring 12-volt supplies capable of operating at the line voltage and frequency at your DXpedition destination. The supplies should also be able to handle wide line-voltage variations around nominal. Carry two of them—one for each radio. I modify mine by adding line filtering and fusing. Parallel a standard receptacle of some kind with your supplies' rig plug or cable. Two-prong, polarized Jones plugs work well. You can use them on everything for quick setup and breakdown.

Bring a memory keyer for use as a beacon and in normal CW operation. Also consider taking a laptop computer. I now use a computer for logging, taking notes, calculating beam headings, and determining the footprint of the sun.

DXpeditioning is also about meeting people. Here's Tarik Skiredj, CN8ST, and friends.

Operating

Several operating subjects are of prime importance. Ten-meter liaison comes first. You must use 10 meters to get up-to-date propagation information and find out who's being heard. When you're feeling your way through a pile of stations, you can sometimes miss very rare propagation opportunities if you don't check 10 meters often.

Six-meter contact procedures come next. It's very difficult making everyone happy on 6 meters when you're the DX. You must set rules and stick to them. Pick a frequency and do your best to keep it when the band gets busy. Try to not work the same stations over and over again, especially during pileups. Your goal is to give as many people as possible a new country. Work each station as quickly as possible. Don't discuss names and grid squares—the time it takes just gives fewer people a chance to work you. Leave that info to the QSL cards! Which should you operate—phone or CW? The answer is "Probably both." CW penetrates weak conditions better than phone, and it gives more people at the edge of propagation a chance at working you. Then, when you go to phone, everyone who can will worK you again. I favor CW DXpedition operation because of my experiences on the non-DX end.

Should you operate on a single frequency or split? Go to split when there's a massive opening and you're being QRMed by people calling you. This usually happens during intense backscatter openings. Hams on the 10-meter liaison frequency can tell you when QRM gets too heavy.

Conclusion

Six-meter DXpeditioning is a blast. And the SSKW makes it even more fun: I can devote more weight to antennas!—*N6AMG*

---

and copper heat spreader. How much heat sinking is needed depends on the duty cycle required. I decided that a duty cycle of 50% or less was acceptable. The resulting weight for the package, 14 pounds, is very acceptable. The SSKW is 8 inches wide, 12 inches long and 5 inches high.

The key to making the package light was to use the smallest possible heat spreader. I decided to use enough ¼-inch-thick copper to surround each MRF154 with at least 1 inch of spreader. I machined the spreader flat and attached it to the heat sink, also machined flat. After attaching the copper to the aluminum, I resurfaced the copper again at the transistor contact points to insure flatness. I spread a thin layer of heat-sink compound between the copper and aluminum, and another layer between the copper and the transistors.

With two high-pressure, 24-volt fans blowing on the sink, the resultant duty cycle limit is a little less than 50%. These fans are in series across the amplifier's 50-volt supply. The small fan in the compartment is a 12-volt unit that just barely fits. (The compartment needs to be a little deeper.) A fan is necessary here, however, because compartment airflow dramatically keeps the output transformer's ferrite from getting hot.

A heat sink with more fins and a thicker base, but the same fin depth, would raise the duty-cycle limit. (The copper spreader should be made larger as well.) These changes would also make the amplifier heavier.

Construction Techniques

A milling machine is required for surfacing all of the amplifier's heat-conductive interfaces. Physical flatness is essential for maximum heat conductivity and to avoid warping the transistor cases. The Motorola bulletin specifies the torque of the screws on the MRF154s' flanges. Tightening these screws uniformly assures that the flanges won't warp during temperature cycling.

R14 and R15, the feedback resistors, are flange-mounted. Their beryllium copper leads cannot be flexed very many times before they break. (According to their manufacturer, that may be only once!) These two resistors just barely fit. So, make sure the two MRF154s are separated properly.

Power Supply

To keep the amplifier small and light, I use a switching power supply. A Lambda


D2
1N4148
R10
MRF154
OUTPUT
R1
1 k
C3
0.1
R12
2 k
100
C7
4400
R14
25
INPUT
T1
L1 15 nH
22
C9
820
L2 15 nH
C14
500
C15
C12
0.1
C10
1000
C11
1000
C8
4400
R15
25
D3
1N4148
R11
R2
1 k
100
MRF154
T2
L3
10 μH
C4
0.1
R13
2 k
+
50 V
C13
0.47
−
R8
5–10 k
R6
2 k
4
5
3
6
R3
IC1
723
Regulator
10 k
C2
0.1
R9
t°
R5
10
2
7
10
13
C1
1000
BIAS
36 to
50 V
R4
470
12
11
D1
1N5357
R7
10 k

Except as indicated, decimal values of capacitance are in microfarads (μF); others are in picofarads (pF); resistances are in ohms; k=1,000.

Fig 1—The basic SSKW circuit can produce at least 1 kW from 2 to 54 MHz. Duplicating this circuit requires additional information not given here. Output filtering is also necessary to ensure compliance with FCC emission-purity rules. See the text, Motorola Application Note AN-287, July 1990 *QEX* and the *1991 Central States VHF Conference Proceedings* for details. The *Central States* write-up includes SSKW performance graphs and spectrograms in addition to a diagram of the amplifier's relay-control circuitry.

LFS-50-48 (net weight, 20 pounds) does the job, with good results. Sized at 15 inches long, 7.5 inches wide and 5 inches high, it can source 50 amperes at 50 volts. This power supply produces significant radio noise up to 30 MHz, most of it radiating from the supply's ac-line leads. I EMI-filtered the supply's leads with good success. (We need better, RF-quieter switching supplies!) Because linear supplies generate little or no RF EMI, they are superior to switching supplies for fixed-station use.

Overshoot is a regulated power supply characteristic that's particularly troublesome in switching supplies. Overshoot occurs when a regulator responds too slowly to keep its output voltage down in response to short-duration, high-current loading. In a 50-volt switching supply, and depending on the load, overshoot transients of more than *100 volts* may result. I've seen overshoot destroy expensive transistors! The SSKW supply must be able to safely handle the variable power-supply demand that occurs during SSB and CW transmission.

Power-supply RF sensitivity is another consideration. Some power supplies are sensitive to RF. Their output voltages may vary with the presence and amplitude of RF on their input and output leads. The SSKW's supply must be free of such effects.

Hints and Kinks

Be careful when applying dc to the amplifier for the first time. Do not use a high-current supply for initial tests. Use a



Two Motorola MRF154 RF power MOSFETS in push-pull make the SSKW perk. A 20-watt wxciter drives the amplifier to full output. (amplifier photos by Kirk Kleinschmidt, NT0Z)



Without its two 24-volt fans, the SSKW's heat sink and spreader would have to be much larger.



What luggage weight the SSKW amplifier conserves can be put to other uses—2-meter moonbounce gear, for instance. Operating as CN2JP, the author completed 20 EME contacts—Morocco's first—in November 1991. On the same trip, the SSKW performed like a heavyweight through 900 contacts with 56 countries on 6 meters.

Table 1
SSKW Performance Versus Frequency

Freq (MHZ)	*Drive Power (W)*	*Power Output (W)*	*I_D (A)*	*Gain (dB)*	*Efficiency (%)*	*Input SWR*	*V_{cc} (V)*
2	24.5	1000	39.1	16.1	51.2	1.41	50
4	21.0	1000	33.4	16.8	59.9	1.39	50
8	17	1000	32.4	16.8	59.9	1.39	50
15	15.5	1000	32.3	17.7	61.9	1.36	50
30	19.5	1000	41.5	17.1	48.2	1.87	50
50	29	1000	39.7	15.4	50.4	1.51	50

current-limited, 3- or 4-ampere supply to check the regulator and set the bias. The amplifier should have a reverse polarity protection diode rated at a voltage appropriate to the supply.

Make sure that you have a 50-ohm load on the amplifier output. The bias circuitry may not act correctly if there is no load. Slowly increase drive. Watch the output power and the current drain to make sure they are in line with efficiency. If the input match is bad, check C7 and C8. If the amplifier does not achieve its efficiency capability, RF that doesn't make it to the load may try to leave via the dc input line. This can cause C12 to explode off of the underside of the board. Also, under normal operation, the single unit Motorola specifies for C12 can barely handle the RF current that passes through it. I recommend paralleling 100-volt, 0.05- or 0.1-µF chip capacitors instead of using a single 0.1-µF chip.[5] This problem is difficult to analyze because C12 is on the underside of the board.

As mentioned earlier, the SSKW's bias circuitry may have to be tailored to the particular MRF154s used. One thing not mentioned on the schematics is the addition of an Arco 365 variable capacitor (C15 in Fig 1) across C14 to cancel some of the inductive reactance in the output transformer at 6 meters.

Performance

With a 50-volt power supply, the SSKW can produce over 1.1 kW from 2 to 54 MHz. At this power level, the MOSFETs' drain current runs at around 40 amperes, depending on the operating frequency. Table 1 shows amplifier performance data taken at six different frequencies. The SSKW can produce up to 1.5 kW below 30 MHz.

Especially below 30 MHz, the SSKW's harmonic output rises with output power. It may be possible to use only four low-pass filters to cover the 2 to 54 MHz range if a second harmonic of –40 dB can be tolerated. Since the transistors operate in push-pull, the second harmonic is usually not a problem.

Without its 5-dB input pad and operating with a 50-volt supply, the amplifier exhibits an input SWR of less than 2:1 (referred to 50 ohms) throughout its frequency range. Only below 5 MHz does its input SWR exceed 1.6:1. Inserting the 5-dB pad adds 10 dB of return loss and keeps the input SWR below 1.3:1 through the amplifier's operating range. I have not yet measured the amplifier's two-tone, thirdorder IMD performance.

Final Notes

For now, I can say that my goal of a compact, lightweight amplifier capable of at least 1 kW output is a reality. The SSKW has served me well in its intended DXpeditionary application. Nonetheless, the amplifier in its present form is still experimental. Before the SSKW could be acceptable for general use, output filtering and failureproof protection circuitry would have to be added. The next generation is on its way. The next project? Use the same 50-volt supply with power FETs capable of covering 144 to 432 MHz, and build it into a similar package!

Acknowledgment

I thank Helge Granberg for spending considerable time answering questions about this project.

Notes

[1] H. Granberg, "New MOSFETs Simplify High Power RF Amplifier Design," RF Design, Oct 1986, pp 43-48, 50, 52.

[2] H. Granberg, "A Compact 1-kW 2-50 MHz SolidState Amplifier," QEX, Jul 1990, pp 3-8.

[3] J. Paladino, "A Rapid Deployment Prototype Solid-State Kilowatt Linear Amplifier for 2 to 50 MHz Using MRF-154s," *1991 Central States VHF Conference Proceedings* (Newington: ARRL, 1991), pp 61-70. Available from the ARRL Bookshelf as #3614.

[4] H. Granberg, "MOSFET RF Power—An Update," Part 2, *QST*, Jan 1983, pp 30-33; also see Feedback, *QST*, Mar 1983, p 44. (Part 1 appeared in *QST*, Dec 1982, pp 13-16; also see Feedback, *QST*, Jan 1983, p 48.)

5American Technical Ceramics (ATC) has some new chip caps (the 900 series) that have higher voltage and current ratings than the capacitor Motorola specifies. I have samples but have not tried them yet.

By Jerry Pittenger, K8RA **From *QST*, September 1986**

An All-Band, 1500-Watt-Output 8877 Linear Amplifier

Part 1—This rock crusher, rated for continuous full-legal-limit output, can be built at home. It is, however, a major project requiring dedication and commitment.



This article is the result of a 10-month project to build a legal-limit linear amplifier. The amplifier uses the popular EIMAC 8877 (3CX1500A7) high-mu power triode that can provide a continuous RF output of 1500 W to the antenna.

In recent years, I have built several different linear amplifiers, and I must admit that this previous experience was necessary to obtain the results achieved with this project.[1-4] I hope that by sharing this experience, others will benefit from it. Any amplifier design depends on the various components used and individual preferences. Therefore, you may not want—or be able—to duplicate this amplifier exactly.

The comment I receive most often from the amateur fraternity is about the high cost to build an amplifier like this. The criticism is valid. This amplifier is not inexpensive to build. Plan to spend from $1000 to $1200 for the RF deck, and another $500 to $600 on the power supply. If you really think about it, though, these costs are a bargain when you consider the performance and quality of the final product and the cost of an equivalent commercial unit.

This article is presented in two parts. In this part, I will describe the RF deck and power supply in general terms. Schematic diagrams and parts considerations are included. Part 2 gives detailed instructions for constructing the two units and considerations for the final testing and operation.

Preliminary Thoughts

Finding Parts

Finding parts can be a big task. Even the most difficult parts to find, such as the vacuum variable capacitors, vacuum relays and door-knob capacitors are available, however, and appear for sale in the ads (*QST* Ham-ads and the Yellow Sheets), or at hamfests and flea markets.[5] Probably the best source of parts is other hams who are actively building equipment. Go talk to these people and let them know what you are looking for. It's amazing how others will help, and even let you into their personal stores. There are people, like myself, who like to build amplifiers. Once you learn who these individuals are, keep in touch with them. They can help find the key parts.

Table 1
Recommended Tools

- Drill press or drill fixture (with set of highspeed bits)
- Band saw capable of cutting 1/16-inch-thick metal
- Chassis punches (5/8 inch to 1 inch)
- Fly cutter, 2-inch radius
- Vise
- Set of taps
- Common handtools (screwdrivers, pliers, soldering iron and gun)
- Volt-ohmmeter
- Variable power supply (5-26 V, 1 A)
- Dip oscillator

Parts that are not available in the surplus market can be purchased new. This will be necessary for some parts, such as



Fig 1—Top interior view of the 8877 linear amplifier RF deck.

cabinets, etc. Just remember that when you buy a new commercial amplifier, you pay the new price for every component.

Tools

A good assortment of hand tools, as well as some power tools, are necessary to complete this project. Table 1 shows the tools I recommend. In particular, I recommend that a drill press and band saw be available. You can do the job without all of the tools listed, but the job will be much more difficult.

Time

Time is probably the most valuable resource for most of us, and the one that may prove hardest to find. This project took well over 250 hours to complete. The key is to do each step right, and not hurry. Build the amplifier in a place where you can leave the project on the table and walk away. Plan each step and build in discrete modules. Work an hour or so whenever possible, and slowly, but surely, the modules will take shape. It is amazing how much you can accomplish using these small time segments. Also, great strides can be made on a Saturday or a Sunday. Commitment and consistency are the virtues required to finish the job.

RF Deck Circuit Description

The RF deck is designed to be a tabletop unit (see title photo). The power supply is remotely controlled and can be located almost anywhere. The amplifier design is based on proven circuitry. Included are all circuits required to provide a clean signal as well as adequate protection devices for the metal-ceramic 8877 tube.

Control Circuitry

Fig 2 shows the schematic diagram for the amplifier control circuitry and low-voltage power supply. The 117-V ac input from the high-voltage power supply enters the RF deck through a 5-conductor interconnecting control cable. Each control line is terminated in a pi-section filter as it enters the RF deck, to prevent RF from getting into the control cable and power supply. The pisection filters are constructed as an independent module.

The amplifier is powered up by the FIL ON/OFF switch, S1. Engaging S1 turns on the blower, filament power and 26-V dc power supply. The current inrush to the tube is limited by Ri, in series with the filament transformer primary. After approximately 1 second, K1 energizes and K1A shorts Ri thus providing full filament voltage to the tube. The K1 delay is controlled by R2 and C1 across the relay coil. R3, in series with the other leg of the filament transformer primary, is adjusted to provide the proper filament voltage (4.85 V ac) to the tube under load.

The 8877 requires a 3-minute warmup period to reach proper operating temperature. A solid-state timing circuit, formed by Q1 and Q2, locks the amplifier out of operation until the warmup period has elapsed. When the 26 V dc comes on, C2 charges through the 500-kilohm time-delay adjust and 1.2-megohm resistors. Q1 and Q2 form a high-impedance Darlington circuit, and the emitter of Q2 follows the voltage rise on C2. The high-impedance Darlington circuit is required to prevent the capacitor charge from draining through the transistors. After approximately three minutes, the potential at the emitter of Q2 reaches 18 V at which point the 4PDT relay, K2, engages. K2A applies 26 V dc to the K2 relay coil, removing the relay current load from Q2. The voltage also turns on the TIME pilot light located on the amplifier front panel to indicate that the warmup period is over. The same line also applies 26 V dc to S2B of the HV-ON pushbutton switch, which, when engaged, sends 26 V dc to the RF input/output relay circuits. K2B connects a 100-kilohm resistor across C2 to drain the charge from C2. This resets the 3-minute timer should the amplifier be turned off and immediately back on.

K2C and K2D are wired in parallel and apply 117 V ac to HV-ON switch S2A to energize the high-voltage power supply. The high-voltage power supply can't be turned on even if the HV-ON switch is engaged until after the 3-minute warmup period has ended. IN/OUT switch S3 allows the amplifier to be put in the standby mode with the amplifier turned on. Both HV-ON and IN/OUT front-panel push-button switches must be engaged to key the amplifier, thereby making it impossible to operate the amplifier without high voltage on the tube.

The amplifier is keyed by grounding the base of Q3 through the exciter TR-relay contact. A transistor is used to limit the current switched by the exciter VOX relay. This avoids a potential problem if the exciter VOX relay sparks on closure, which could damage the relay contacts. The "grid trip" break in the relay line causes the relays to drop out if the grid trip circuit actuates from too much grid current (approximately 120 mA). During normal operation, the grid trip break is shorted by a normally closed set of contacts on K3 (see Fig 3).

When the amplifier is keyed, the output RF relay must be closed before drive is applied to the tube—otherwise the tube will transmit for a brief period without a 50-ohm antenna load. This would not only be harmful to the tube, but also cause the grid-trip circuit to actuate. Therefore, a timing circuit, comprised of a 50-ohm resistor and i00--~iF capacitor, is included across the RF input relay K4 to allow vacuum relay KS time to close. The capacitor value depends on the relay used. Do not make the delay too long, since during the delay time, the exciter does not have a proper 50-ohm load. Check the time delay by placing a low voltage across the relay contacts and monitoring the contact closure on a dual-trace scope. I used a delay of about 20 ms.

RF Amplifier Circuit Design

The RF amplifier circuit is shown in Fig 3. The amplifier uses a tuned input network to minimize distortion products and provide a proper impedance match between the exciter and the tube. The input network is remotely switched, using small DPDT relays, to connect the correct pi-section for the selected band. A homemade switch deck is mounted on the band-switch shaft, in front of the subpanel, to ground the 12-V dc line for the proper input relay as selected by the main band switch. On 160 meters, the switch also controls a solenoid relay to add a 160-pF capacitance in parallel with the TUNE vacuum variable capacitor.


+26 V DC
500 k 1/4 W
1.2 M
TIME DELAY ADJ
47µF 50 V
C2
Q1
2N3053
Q2
K2
D4
RF INPUT RELAY
RF OUTPUT RELAY
50
K4
D5
D6
K5
100µF 35 V
NC
K2B
100 k
D1
TIME
DS1
GRID TRIP TO K3A, FIG 3
NC
K2A
D2
S2B
S3
HV ON
IN/OUT
TIP31 Q3
Q3
DS2
DS3
2 k
J1
NC
K2D
NC
K2C
NOTE: PILOT LAMPS ARE PART OF SWITCH ASSEMBLY
TO EXCITER TR RELAY (GROUND TO TRANSMIT)
HV
S2A
AC FROM PS FIG 5
RFC
S1
RFC
AC TO PS FIG 5
0.01
0.01
FIL ON/OFF
25 20W
R1
K1A
0.01
0.01
DS4
T1
GROUND FROM PS FIG 5
BLOWER
M
117V AC
5 V AC
TO 8877 HEATER
R3
FIL VOLT ADJ
+12 V DC
POWER SUPPLY MODULE
+26 V DC
AC COMMON FROM PS FIG 5
RFC
0.01
0.01
D3
C1
150
K1
R2
100µF 50 V
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000, M = 1000 000.
POWER-SUPPLY MODULE
U3 REG
7812
IN OUT GND
FB
+12 V DC
100 2 W
0.02
T=TANTALUM
T2
117 V AC
25.2 V AC
AC
U2
AC
U1 REG
LM317
IN OUT ADJ
FB
+26 V DC
D7
270
1500µF 75 V
5 k 1/4 W
VOLTAGE ADJUST
0.02
0.1 T

Fig 2—Amplifier control circuit and low-voltage power-supply schematic diagram. Part numbers shown in parentheses are Radio Shack.

B—Blower, Dayton 4C004-i.
D1-D6—Diode, 1 kV, 2.5 A.
FB—Ferrite bead.
K1-K4—4PDT 24-V dc relay, Potter & Brumfield KHU17D11.
K5—SPDT vacuum relay, 26-V dc coil.
Q1,Q2—2N3053 NPN transistor.
Q3—TIP31 NPN transistor (276-2017).
R1—25 Ω, 20 W.
R2—150 Ω, 2 W.
R3—25 Ω, 25 W variable.
RFC—10 turns no. 14 enam wire on ¼-in-diam ferrite rod.
S1,S3—Alco 16TL5-11 SPST.
S2—Alco 16TL5-22 DPDT.
S4—Alco 16TZ pilot light.
Ti—Filament transformer, 5.0 V ac, 10 A, Peter Dahl Co.
T2—25.2 V ac, 1.0 A, Stancor P6469.
U1—50-V, 4-A bridge rectifier.

An effective ALC circuit, adjustable from a front-panel control, is included to avoid overdriving the tube. This feature is essential in this amplifier because the drive requirement is only about 80 W for 1500-W output. The ALC circuit samples the RF drive level through a 27-pF mica capacitor to generate a dc voltage that is fed back to the exciter for drive-power control.

The grid-trip-protection circuit shuts down the amplifier if grid current exceeds 120 mA. This protects the tube from tuning errors or other problems such as losing the antenna, or a tube flashover during operation. Although grid current flows through all paths from ground to the B – line, most of the grid current goes through R1. The current passing through R1 develops a voltage drop. For example, if 100 mA of grid current is drawn through Rl, 1 volt is developed (E = IR = 0.100 x 10). This voltage is used to turn on the transistor switch, Qi. When Qi turns on, the grid-trip relay, K3, energizes and opens the grid trip break in the RF relay control line to shut the amplifier down. R2 sets the current level at which Qi turns on. The front-panel GRID TRIP lamp goes out if the trip circuit is activated. The switch is reset by pressing S3.

The plate tank circuit uses a pi-L configuration because this design provides approximately 20-dB better harmonic suppression than the conventional pi design. The TUNE and LOAD capacitors are vacuum variable types to minimize space requirements and also optimize performance on 12 and 10 meters where small capacitance values are needed to achieve an acceptable tank-circuit Q. The 10- to 40-meter tank coil is homemade from ¼-inch copper tubing that is silver plated to minimize skin resistance. The 80-meter, 160-meter and L-coils are toroid designs to minimize space. Using a toroid for the L coil also helps isolate the L network from the rest of the tank circuit because of the toroid's self-shielding characteristics.

Metering circuits monitor plate and grid current, as well as filament voltage. Plate current is monitored by placing a meter in series with the B – line. Therefore, only a small dc voltage is across the meter. An additional position can be included on the FIL/GRID meter for plate voltage, but one is not shown in this design because a separate high-voltage meter is included in the power supply. It would be a good idea to include a high-voltage scale on the meter in case the RF deck is ever used with a different highvoltage supply. Grid current is monitored by measuring the voltage drop across R1. R3 is adjusted to give the cor-



1000 pF
10 kV
PC
L1
L2
L3
L4
V1
8877
RF INPUT
J3
A
K4A
INPUT NETWORK
(SEE FIG 3B)
0.01 M
0.01 M
0.01 M
RFC 5
RFC 1
RFC 2
0.005
6 kV
C1
TUNE
C5
S2B
(160 M SEE TEXT)
C2
LOAD
C3
160
1200 pF
5 kV
C4
10
S1A
10
S1B
L5
160
RFC 4
TO HIGH VOLTAGE FIG 5
TO T1, FIG 2
5 V AC
+ 26 V DC
27 M
10 k
ALC ADJUST
100 k
2 W
51 M
RF OUTPUT
J4
K5
A
RFC 3
0.01
D2
D3
0.01
D10
10 V
10W
18 k
10 W
F1
1A
K4B
0.01
D5
D6
M1
mA
0-5
Ip
D1
1N914
1M
1k
0.02
47 k
0.02
M2
mA
0-5
HEATER
GRID
25 k
1/4 W
R3
GRID CURRENT ADJUST
39 k
20 W
R1
10
2 W
D8
200
10 W
RFC
0.01
0.01
B-
J2
ALC OUT TO EXCITER
D11
3.1 V
1 W
D9
5k
HEATER CAL
0.01
0.01
TO T1, FIG 2
5 VAC
GRID TRIP PILOT
K3A
DS1
+26 V DC
NC
1000 μF
50 V
K3
D7
J5
VOX LINE TO EXCITER
K3B
NC
S3
NC
GRID TRIP RESET
K3C
2N3053
Q1
GRID TRIP ADJ
5 k
1/4 W
R2
100
D4
0.01
(A)

EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS; k=1000, M=1000 000.

Fig 3—RF amplifier schematic diagram (see Part B on next page).

C1—Vacuum variable capacitor, 375 pF, 10 kV.
C2—Vacuum variable capacitor, 1000 pF, 10 kV.
C3—Mica transmitting capacitor, 100 pF, 5 kV.
C4—Mica transmitting capacitor, 3 × 400 pF, 5 kV.
C5—Fixed vacuum capacitor, 2 × 80 pF, 20 kV.
D1—Diode, 600 V, 1 A.
D2-D9—Diode, 1 kV, 2.5 A, HEP 170.
D10—Zener diode, 10 V, 1 W.
D11—Zener diode, 3.1 V, 1 W.
K1-K7—DPDT 12-V dc DIP relay (275-213).
K8—SPST 12-V dc relay (275-241).
RFC—10 turns no. 14 enam wire on 1/4-in-diam ferrite rod.
RFC1—Plate choke, 2 A, Peter Dahl Co.
RFC2—Air-wound coil, 15 turns, 1/2-in diam.
RFC3—Choke, 1 mH, 800 mA.
RFC4—110 turns no. 20 enam wire on 1/2-in diam fiber rod.
RFC5—Filament choke, 18 bifilar turns no. 14 enam wire on 1/2-in-diam ferrite rod, 6 inches long.
PC—Three 150-ohm, 2-W carbon resistors in parallel with 2-inch horseshoe loop of 1/2-inch silver-plated strap.
L1-L5—See Table 2.
M1,M2—Simpson Wide-Vue panel meter, 01253 bezel and 01165 lighting kit (See text).
S1—9-position, 2-pole switch, Radio Switch model 88, 13-kV, 30-A.
S2—Solenoid-controlled switch; see text.
S3—SPST normally closed momentary switch, Alco 16TL-11 with 6T-2 red lens.



RF INPUT
L
C1
C2
RF OUTPUT
K1
L
C1
C2
10
12
K2
15
20
40
80
SPARE
160
CONTROL SWITCH ON MAIN BANDSWITCH SHAFT
K3-K6 AND ASSOCIATED INPUT NETWORKS
L
C1
C2
12 V DC
K7
160-METER SOLENOID 24-V DC COIL
26 VAC FROM T3 FIG 5
D1
50 µF 35 V
S2A
K8

BAND	C1 (pF)	L (µH)	C2 (pF)	Q	CORE	NO. OF TURNS	WIRE SIZE
160	4000	3.31	4000	2.35	T94-2	19	22
80	1240	2.06	1240	1.50	T94-2	15	22
40	680	1.03	680	1.67	T68-2	14	18
20	390	0.50	390	1.80	T68-2	9	18
15	270	0.32	270	1.90	T68-2	7	18
12	270	0.25	270	2.20	T68-2	6	18
10	160	0.27	160	1.50	T68-2	8	18

(B)

Fig 3B—see previous page.

rect gridcurrent meter reading. Filament voltage is measured by converting the ac voltage to dc and displaying the dc voltage on M2. The 3.1-V Zener diode expands the meter scale by not allowing conduction until the voltage reaches 3.1 V.

A vacuum relay is used for the amplifier output. The relay is small in size, quiet and capable of handling large RF currents.

RF Deck Parts Selection

Finding all the parts for the RF deck is a major task. If you are planning to build an amplifier, begin collecting parts as soon as possible. It is the first step because the physical layout of the amplifier will depend on the components available. Don't try to exactly duplicate the components I used. For example, vacuum variable capacitors come in many different shapes and sizes, with different mounting provisions. Actually, the parts you find may be better than the parts used in my RF deck. As an example, a 1500-pF vacuum variable LOAD capacitor would be much better than the 1000-pF unit I used.Therefore, use whatever resources you have available to acquire the parts— but a word of caution! Do not compromise too much when gathering components. If you cannot find what you need on the surplus market, buy the parts new. It may cost a little more, but if the project is not done right, you will never be happy with the final result.

Vacuum Variable Capacitors

Vacuum variable capacitors are often difficult to locate at reasnable prices. Plan to spend about $50 for the TUNE capacitor and $75 to $100 for the LOAD capacitor if vacuum capacitors are used. The TUNE capacitor should be at least 300 pF at 7 kV, and the LOAD capacitor should be at least 1000 pF at 3 kV.

An air variable capacitor can be used for the LOAD control, if desired. The minimum capacitance for the LOAD capacitor is 112 pF for 10 meters, which is not difficult to obtain with an air variable type. A rating of 1 kV, minimum, is recommended. However, it is a different story for the TUNE capacitor. The minimum required capacitance is 26 pF. The direct inter-electrode capacitance of the 8877 tube in grounded-grid service is 10 pF; therefore, the TUNE capacitor must have a minimum value of not more than 16 pF for 10 meters.

This is nearly impossible with a 300-pF air variable. In addition, the voltage requirements for the TUNE capacitor make any air variable rather large. For these reasons, a vacuum variable is recommended for the TUNE capacitor.

Meters

Good-quality meters with bezels are essential for good appearance. The Simpson Wide-Vue® meters I used were purchased at a hamfest. The bezels were ordered directly from Simpson because they seldom appear on the surplus market. Actually, almost any meter movement can be used, so don't pass up a good meter just because it reads 50 V or 100 mA on the scale. Any meter with a movement from 100 µA to 5 mA can be used. This allows use of approximately 90% of the meters available on the surplus market. I will give instructions later for calibrating any meter to read whatever current or voltage is required.

RF Band Switch

Good RF band switches are very difficult to locate. More problems are experienced with arcing band switches than with any other amplifier component. If the band switch selected has insufficient voltage insulation, it will arc to the wiper rotor on the high-impedance 10-meter position when operating on the lower-frequency bands. I obtained the band switch for my amplifier from Radio Switch Corp.[6] The model 88 switch is a 2-pole, 9-position unit with a 13-kV peak flashover/30-A contact rating. This switch will not arc! Its list price is currently $107, and it is well worth the money!

Miscellaneous Parts and Materials

Many of the small parts (capacitors, relays and resistors) can be purchased at Radio Shack. Their parts selection is good, and continues to increase. You can usually find a store around the corner in almost any city. Pioneer Electronics is also a good source for commercial-grade components.[7] Good-quality PC-board material can be found at almost any hamfest. Don't compromise here—use G10 glass-epoxy board. As for coils? Make them. Complete "how-to" instructions are given later.



Fig 4—High-voltage power supply top interior view.



High-Voltage Power-Supply Circuit Description

The key to continuous duty in a high-power linear amplifier is the power supply. It must be able to deliver the required voltage and current on a continuous basis. Power supplies are usually the limiting factor in commercial linear amplifiers.

A WORD OF CAUTION IS IN ORDER. The power supply is a very dangerous piece of equipment! Give it proper respect. One mistake can be fatal. Use proper precautions in the construction and testing of this unit, and be careful to build a safe unit.

I recommend that the power supply be built first. The construction is not complex and it can serve as a training ground for amplifier building techniques, particularly for the first-time builder.

Power-Supply Design

The power supply is shown in Fig 4, and the schematic diagram is shown in Fig 5. The hypersil power transformer has a 234-V ac primary, and a 3300-V ac secondary that is tapped at 2600 V. This selection of two output voltages allows for a high- and lowpower capability. An alternative to this approach is to include a Variac® or Powerstat® autotransformer on the transformer primary.

The primary circuit of the power transformer includes a step-start circuit to protect the diode bank during the initial charge of C1, the 53-µF filter capacitor, when the power supply is turned on. Two 50-ohm, 25-W resistors, one in each leg of the primary, are shorted by time-delayed relays approximately 3 to 4 seconds after application of power. The more current drawn through the resistors at start up, the more voltage drop realized and this, in turn, protects the diode bank. The delay is provided by the time constant of the 500-ohm resistor and 100-µF capacitor. The relays must be dc types. Those I used have 90-V dc coils which allows power to be supplied from one 117-V leg of the primary. If 90-V relays can't be obtained, 24-V dc relays can be substituted. A 24-V dc power source must be provided if this is done.

The rectifier unit is a full-wave bridge with eight diodes in each leg. A 470-kilohm resistor and a 0.01-µF, 1-kV capacitor are wired in parallel with each diode to equalize the voltage and protect the diodes from voltage spikes.

The power supply is controlled remotely from the RF deck. A test switch has been incorporated to allow the supply to be energized without the RF deck. A shorted Cinch-Jones plug must be inserted into a socket in the rear of the supply for test switch S1 to operate.

Two pilot lights are mounted on the front panel. One pilot light is on whenever 234 V ac is present in the supply. The other lights when the power supply is activated.

A high-voltage meter is included on the front panel. The metering is done across a 25-ohm, 5-W resistor in series with the bleeder resistor. This voltage divider keeps the total high voltage off the meter. A 50-ohm, 50-W resistor in series with the high-voltage B+ circuit protects the tube and power supply from any current surge resulting from a tube flashover or other cause. In addition, a 0.6-ohm, 1-W resistor in series with the B+ line acts as a fuse resistor. A large current surge will cause the resistor to explode—an inexpensive protection device should a problem occur.

High-Voltage Power Supply Parts Selection

Transformer

It is important to find a good power transformer that can provide the proper operating voltages for the tube. Remember that some voltage drop will occur when current is drawn from the transformer. The voltage drop depends largely on the quality of the transformer (core and wire size), and can range from 200 V to over 1 kV. The transformer should have a 234-V ac primary. Transformers with 117-V primaries are usable only if two identical units can be wired in series to provide a 234-V primary. The secondaries can by wired in series or parallel, depending on the voltage requirements. Remember that the transformers must be identical.

The required transformer secondary voltage depends on the fmal voltage requirement of the tube and the power-supply circuitry. If a bridge rectifier is used, the power-supply high voltage will be about 1.4 times the secondary voltage. If a voltage doubler is used, the high voltage will be about 2.8 times the secondary voltage. A voltage doubler requires two filter capacitors, or more, so if a single oil-filled filter capacitor is to be used, the design can't be a voltage doubler. The *ARRL Handbook* contains circuits for both types of power supplies.[8]

The power-handling capability of a transformer can usually be estimated by its weight. As a rule, the heavier the transformer, the greater the power capability. The transformer for a 1500-W, continuous-duty amplifier will weigh 60-80 lb. The transformer used in this power supply was obtained from Peter Dahl Co.[9] The hypersil design provides a good ratio of power capability to size and weight. I have used several Peter Dahl transformer designs in the past and found them to be of excellent quality and reasonably priced.

Filter Capacitor

Enough filter capacitance is required to obtain good voltage regulation. What is enough? I have used as little as 18 µF and as much as 100 µF in power supplies. The required capacitance can be obtained with a single oil-filled capacitor or with a series string of computer-grade electrolytics. Either way, I recommend at least 25 µF be used, with at least a 10% voltage safety factor. The filter capacitor used in this power supply is a single oil-filled unit rated at 53 µF at 5kV dc. The capacitor was obtained


DS1
AC ON
26 VAC
T2
117 V
AC
AC TO AMP
(FIG 2)
Ⓓ
Ⓒ
F1
15 A
234 V
AC
Z2
MOV
0.01
0.01
Z1
MOV
F2
15 A
50
10 W
K1A
K2A
K1B
K2B
3300
V AC
S2
VOLTAGE
3600-4600
2600
V AC
T1
234 V
AC
470 k
0.01
D1
HIGH
VOLTAGE
TO FIG 3
50
50W
0.6
1W
B+
0.001
6kV
103k
100W
103k
100 W
C1
53 μF
5 kV
25
5 W
TO FIG 3
Ⓔ
B−
50
10 W
GROUND
Ⓐ
TO FIG 3
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000.
S1
TEST
D2
50
10 W
SAFETY PLUG (SEE TEXT)
P1
Ⓑ
TO FIG 2
K1
500
K2
K3
+ 100 μF
150 V
1k
2W
CAL
M1
0-5
mA
0.01
D3
TO 160-M SOLENOID (FIG 3)
T3
117 V
AC
26 V
AC
DS2
AC
HOT
CONTROL CABLE CONNECTIONS
Ⓐ GROUND
Ⓑ AC FROM RF DECK
Ⓒ AC TO RF DECK
Ⓓ AC COMMON TO RF DECK
Ⓔ B− TO RF DECK

Fig 5—High-voltage power supply schematic diagram. Part numbers in parentheses are RadioShack.

C1—Oil-filled capacitor, 53 μF, 5 kV, Peter Dahl Co.
D1—Diode bridge rectifier assembly, Peter Dahl Co, see text.
D2,D3—Diode, 1 kV, 2.5 A.
F1,F2—Fuse, 15 A.
K1—2PDT mercury plunger relay, Dayton 6X598-3.
K2,K3—SPDT relay, Potter Brumfield PRD1 DYO/9OVDC.
M1—High-voltage meter, 3½-inch Simpson Wide-Vue, 01253 bezel and 01165 lighting kit.
Z1,Z2—MOV transient suppressor, 117 V ac (276-568)
P1—Two-pin Cinch-Jones socket and plug (274-201 and 274-202)
P2—Eight-pin Cinch-Jones connector.
S1—SPST switch (275-690)
S2—Modified 6PST switch, Fair Radio Sales.
T1—Power transformer, 2600/3300-V ac sec, Peter Dahl Co.
T2,T3—Transformer, 26 V ac, 300 mA (273-1386)
Miscellaneous
Pilot lamp—Alco 16TZ, 6T-4 (yellow) and 6T-2 (red) lenses.
Cabinet—CTS model MCLS 10-17-14 black and white, SPP 10-14 black side panels.

from Peter Dahl Co, and is physically very small for the voltage and capacitance rating.

Diode Bridge Rectifier

The full-wave, diode-bridge rectifier is made up with 1000-PIV diodes rated at 3 A. The unit is a commercial module sold by Peter Dahl Co. Each diode string is built on a separate glass-epoxy board. The module is supplied with 1-inch angle brackets on each end, but because of space restraints, the angle was removed and the module was mounted in a vertical position using two Nylon bolts.

Should you decide to build the rectifier assembly, use good-quality diodes, such as HEP-170s or 1N5408s. Be sure to parallel each diode with a 470-kilohm resistor and a 0.01-μF, 1-kV capacitor.

High- Voltage Switch

The transformer has two taps on the secondary to provide a high- and low-voltage capability. The front-panel VOLTAGE 3600-4600 switch is fabricated from a 6-position, heavy-duty ceramic switch (Radio Switch Corp p/n 65). The switch detent and all but the second and fifth contacts are removed. New stops are fabricated from glass-epoxy board. Full high voltage appears across this switch, and therefore, it must be well insulated. The switch is mounted on two pieces of ¾-inch Plexiglas® to provide 2-inch spacing from any chassis or panel ground. A fiber shaft protrudes from the switch through the front panel. To protect the contacts, this switch must never be actuated when the power supply is on.

Construction Details

Next month, I will describe the unique construction details for building this high-power linear amplifier and power supply. In the meantime, should you be so inclined, get out there and find the parts! Remember that you should build the power supply first, so concentrate on those components.

Notes

[1] J. L. Pittenger, "Modular Linear Amplifier for the High-Frequency Amateur Bands," *Ham Radio*, Jan 1981.

[2] J. L. Pittenger, "A 3CX800A7 Linear Amplifier," *Ham Radio*, Aug 1984.

[3] J. L. Pittenger, '3CX1200A7 10 to 80 Meter Amplifier," *Ham Radio*, Aug 1985.

[4] W. I. Orr, ed, Radio Handbook (Indianapolis: H.W. Sams, 1975), 20th edition, Sect 22-4, "A Modern 3-1000Z Linear Amplifier for 80-10 Meters."

[5] Ham Trader Yellow Sheets, PO Box 2057, Glen Ellyn, IL 60138-2057.

[6] Radio Switch Corp, Rte 79, Marlboro, NJ 07746, tel 201-462-6100.

[7] Pioneer Standard Industrial Electronics, 1900 Troy St, Dayton, OH 45404, tel 513-236-9900.

[8] M. Wilson, ed, *The 1986 ARRL Handbook* (Newington: ARRL, 1985).

[9] Peter Dahl Transformer Co, 4007 Fort Blvd, El Paso, TX 79930, tel 915-566-5365.

By Jerry Pittenger, K8RA **From *QST*, October 1986**

An All-Band, 1500-Watt-Output 8877 Linear Amplifier

Part 2—Here's what you've been waiting for: detailed instructions for building a 1500-W RF deck and power supply.

Last month I described the circuitry and parts required for the 8877 linear amplifier and high-voltage power supply. This month I will cover the construction of both units. The power supply construction details are given first. Assuming that we have all the required parts in hand, we can determine the physical design of the power supply. To avoid costly mistakes, it is important to do adequate upfront planning before the first hole is drilled.

Power Supply Construction

Meter Selection and Labeling

Any meter with a movement from 100 µA to 5 mA can be used for the high-voltage meter. This meter measures the voltage across the 25-ohm resistor at the bottom (B–) end of the bleeder string (see Fig 5 in Part 1). The more sensitive the meter, the higher the resistance setting of the variable 1-kilohm calibration resistor. The setting of the resistor is a simple Ohm's law problem. The maximum power-supply voltage on the meter scale causes a current equal to the meter-movement rating to flow through the meter, and thus give a full-scale reading. For example, the maximum scale on the meter in this supply is 5 kV dc. The meter has a 5-mA movement; therefore, if the supply is at 5 kV, 5 mA must flow through the calibration resistor and the meter for a fullscale reading. Looking at the complete bleeder string, the total resistance is the sum of the two 103-kΩ bleeder resistors plus the 25-ohm resistor, or 206,025 ohms. At 5 kV, approximately 24 mA (5000/206,025) flows through the string. The value of the calibration resistor, therefore, was selected to allow 5 mA through the meter and 19 mA through the 25-ohm resistor. Using Ohm's law, the value of the resistor should be approximately 95 ohms (19 mA x 25 ohms/5 mA). The required wattage rating of the resistor is 0.23 W ($I^2R = 0.005 \times 0.005 \times 95$), and a 1-kΩ, 2-W potentiometer was used. The meter used originally had a 0-50 scale. The scale was changed to read 0 to 5 kV.



Fig 6—Typical computer-prepared layout drawing. Some component labels have been enlarged for legibility.

Panel/Chassis Layout

I do all my layouts with an Apple® Macintosh computer. An example of this layout is shown in Fig 6. A manual method may be used, instead. Cut out a piece of poster board the size of the front panel or chassis, as well as all the major components. Shuffle the pieces until you get an acceptable layout. This may seem like a lot of extra work, but "one picture's worth 1000 words." You will save time in the long run by going through this procedure, and not have to correct errors that otherwise are certain to occur. The panel layout should be symmetrical. Align switches and center meters. Make sure that components are properly spaced to accommodate the physical size of the parts behind the panel.

The computer-generated or manual layouts serve as a guide during construction, but are by no means sacred. Once you start putting the parts in place, you probably will make minor changes. Go ahead and make the changes, but always update the documentation.

Front-Panel Assembly

You probably will not be ready to cut metal until you are 3 to 4 months into the project. Do the front panel first, since the parts locations are fixed for symmetry. Parts behind the front panel can be moved to accommodate the front-panel design.

Cover the front panel with 3-inch-wide masking tape. The tape not only protects the panel from scratches, but also provides a way to lay out the panel with a pencil or pen. Before any holes are drilled, place all the major parts in their proper place in the cabinet to be sure that nothing obstructs the area behind the panel. Remember you have only one chance. Miss and it means a new panel, or cabinet!

Remove the front panel from the cabinet and center punch the panel where holes are to be drilled, as marked on the tape. Carefully drill a very small hole at each punch mark to serve as a guide, then cut the holes to final size. Holes up to approximately 7/16 inch can be drilled with either a hand drill or a drill press. Holes larger than 7/16 inch should be made with chassis punches. The meter hole is rectangular and is cut with a nibbler after drilling an access hole. Cut the meter hole about 1/32 inch smaller than needed and finish with a large file to straighten the edges. Be careful using the file—it is very easy to let the file slip out of the hole and make a big scratch in the panel. The meter hole doesn't have to be perfect since a meter bezel is used.

After the front-panel metal work is complete, carefully remove the masking tape. The front panel should be labeled before mounting the components. Labeling is done with dry-transfer lettering available from art stores or Radio Shack. Apply the labeling by laying the letter or figure on the panel in the proper position and rubbing over it with a soft pencil. The character will be transferred to the panel. If a mistake is made, the character can be removed with masking or Scotch® tape. There is a mattefinish spray available to protect the lettering. I do not recommend using this spray. It will peel if bumped and does not work well.

The parts can now be mounted on the panel. The cabling to the front panel is connected through nylon multipin connectors (available from Radio Shack) to allow easy panel removal. The same technique is used in the RF deck.

Rear-panel Assembly

Placement of parts on the rear panel is not as critical as on the front panel. Attention should still be paid to symmetry, however. I have found that it is best to mount rear-panel parts after the major parts have been mounted inside the cabinet. The rear panel is drilled and labeled in a manner similar to the front panel. The black rear panel requires white lettering. White lettering kits are available at art supply stores and some electronics suppliers.

Fig 7 shows the inside rear panel of the power supply. The control and power cables enter the rear panel and are routed directly to barrier strips. Each terminal is labeled for clarity. The rear panel is accessible by removing the front panel and the transformer. It sounds like a big job, but it can be accomplished in about 10 minutes. It is necessary to provide good strain relief for the cables. Immediately inside the rear panel, a piece of 3/4-inch aluminum angle stock is mounted, to which each cable is clamped. Large rubber grommets are used in the holes for cable protection.

Major Chassis Assembly

Power-supply components are extremely heavy and a good supporting structure is required. The 1/16-inch-thick bottom cover supplied with the cabinet is replaced with a 1/4-inch-thick base plate to provide an adequate foundation. The heavy plate is cut to size on a commercial metal shear. After the transformer, relays and filter capacitor are mounted, rubber-wheeled casters are bolted to the bottom so that the supply can be rolled, rather than carried from place to place.

The cabinet sides are formed by two removable panels. Parts can be mounted to the inner panel using countersunk screws and then covered with the 1/8-inch painted cover plate to provide a professional appearance. A 1/4-inch-thick sheet of Plexiglas® is mounted above the filter capacitor to support the high/low voltage switch, the diode bank and the bleeder resistors. The Plexiglas is supported by drilled and tapped holes for no. 6-32 countersunk screws in the rear and side panel. A post of 1/2-inch aluminum bar stock supports the front-left corner of the Plexiglas.

The mercury-wetted power relay is mounted on the rear panel and must be positioned vertically. Mercury-wetted relays have a tendency to buzz if mounted on a solid surface. Use a rubber grommet to make a bushing in each mounting hole, or mount the relay on a rubber pad. The stepstart relays, K2 and K3, are also mounted on 1/4-inch-thick rubber sheet to minimize noise.

Once the major components are mounted, wire them together, performing as much testing as possible along the way.



Fig 7—Interior view of rear panel. Note the mercury plunger relay mounting. Relays K2 and K3 are at the lower right.

Front- and rear-panel components are mounted and wired before those that are mounted to the cabinet sides and base plate.

Power-Supply Testing

When you are satisfied that the power supply has been correctly wired and carefully checked, go have a cup of coffee and come back later when your mind is fresh and check the wiring one more time. *Remember that this power supply can be a lethal device. One wrong move could be fatal.*

Final testing of the power supply is accomplished in three steps. Remove the wiring from the primary of the transformer and place a temporary line cord with a small variable autotransformer directly from a 117-V ac line to the primary. Turn the 117 V on and slowly run the variable autotransformer up. At 117 V, the power supply should be reading half-scale voltage. This test verifies that the diode bank and filter capacitor are correctly wired. Now is a good time to calibrate the front-panel meter. Using the variable auto-transformer, set the output voltage at a level that another VOM can measure accurately. For example, most VOMs can measure 1 kV. Adjust the calibration resistor so that the front-panel meter reads the same as the VOM.

The second test checks the primary 234-V ac circuitry. With the 234-V lines still disconnected from the primary, plug the power-supply line cord into a 234-V source. Remember that the shorted two-contact plug must be inserted into the rear-panel socket. Turn the power supply on with the test switch and listen for a 3- to 4-second time delay for the step-start relays. Check that 234 V appears across the two wires disconnected from the primary.

The final test is to try the entire power supply with 234 V applied to the primary. Check the high- and low-voltage indications on the front-panel meter.

Power-Supply Performance

The design results in a husky supply that delivers about 4.6 kV and 3.8 kV (no load) on the high- and low-voltage positions, respectively. In either position the power supply drops less than 400 V under full load. This is the performance you need to achieve full-power capability and good linearity.

RF Deck Construction

The physical design of the RF deck requires planning long before construction begins. Again, I used the Macintosh computer for my initial "paper design," but the same process can be done using paper and pencil. The important thing is to lay out the major components so that everything fits properly before starting to drill holes and cut metal. You must have all the major components in hand before doing the physical design, so you know what you have to work with.

Fig 8 shows the scaled Macintosh designs for the front, top and bottom views of


TUNE
7.0
14.0
21.0
3.5
24.9
1.8
28.0
LOAD
ALC
S1
S2
S3
S4
S5
fil
grid
METER
FRONT
RF CHOKE
2000 pf
2000 pf
BLOCKING CAPS
8877 TUBE
RF VACUUM RELAY
10/12 METER TANK COIL
160 METER TOROID
L-COIL
160 METER PADDING CAPS
375 PF VACUUM VARIABLE
15-40 METER TANK COIL
RF SWITCH
80 METER TOROID
1000 PF LOAD CAP
1200 PF LOAD CAPS FOR 160
SOLENOID
SWITCH FOR INPUT NETWORK CONTROL
METER
METER
TOP
LEAD FILTER BOARD
RELAY MODULE
CATHODE CHOKE
FILAMENT CHOKE
9877 TUBE SOCKET
FIL XFMR
FILAMENT STEP START MODULE
FIL METER MODULE
ALC
GRID TRIP BOARD
INPUT NETWORK
26 VDC / 12 VDC POWER SUPPLY BOARD
JUNCTION BOARD
SWITCH
SWITCH
SWITCH
SWITCH
SWITCH
BOTTOM

Fig 8—Scale layouts of the RF deck front, top and bottom views, as prepared on the Macintosh computer. Some component labels have been enlarged for legibility.

the amplifier. It is necessary to match the designs so that the front-panel controls end up at the right place on the panel. Everything must be drawn to scale to obtain the relative positions of the components. When designing the bottom and top layouts, only the major circuit boards and components like the grid trip, input network, low-voltage power supply, coils, capacitors and filament transformer are considered. The smaller components can be fitted in later. It is important that the unit be designed with maintainability in mind. Every component, large and small, must be accessible after the unit is completed. The amplifier was constructed in the following steps. Each major step is discussed in more detail later.

- Fabricate, build and test all printed circuit boards for the RF deck.
- Cut the holes in the front panel.
- Perform the major metal work on the subpanel and chassis plate.
- Mount the vacuum capacitors and band switch to the subpanel.
- Mount the PC boards, filament transformer and tube socket to the chassis plate.
- Wire and test the under-chassis control circuits.
- Fabricate and install the RF tank circuit.
- Label and calibrate meters.
- Complete the front panel and mate it to the chassis and cabinet.
- System test the amplifier with the power supply.

Printed-Circuit Board Fabrication

Making PC boards can be tedious, but with a little practice, good results can be obtained. Grouping interconnected circuits on the same PC board minimizes the cable harness between modules in the amplifier. In this design, nine PC board modules are required.



Fig 9—Things don't always work out. Three attempts were made to fabricate the grid-trip and bias PC board. The good board at left was subsequently damaged, requiring a fourth effort.

	Board Size
1) Input network	4" × 6"
2) Low-voltage power supply and timer circuit	4" × 6"
3) Grid-trip and bias circuit	4" × 6"
4) Switch bank harness interface to front panel	1" × 6"
5) Filament step-start circuit	2¾" × 3¾"
6) RF input/output relay timing circuit	2¾"
7) Line filters for control cable and blower	1¾" × 5¼"
8) Filament-voltage-meter circuit	1⅛" × 2"
9) ALC circuit	1¾" × 2¼"

All boards, except nos. 4, 7, 8 and 9, are mounted on ½-inch channel to the chassis plate. Therefore, the PC board layouts include a ground strip on the edges of each board to mount the boards to the channel.

The Macintosh computer, with a software package called "Draw," was used to lay out the circuit boards. The design of PC boards with the computer is beyond the scope of this article. PC boards can also be laid out using pencil and paper. Once the design is laid out to scale, the layout must be transferred to the board. First wash the board with a mild detergent to remove all grease and dirt. Using tape and special dry transfers (Radio Shack p/n 276-1577), copy the design onto the board. The transfers are not exact, and the hand drawing only serves as a guide. Submerge the board into an etching solution to remove the exposed copper. I use ferric-chloride etchant. A flood lamp over the etching tray warms the solution and speeds the etching process. Agitate the solution occasionally. The final result should be a nicely etched board ready for drilling the holes for mounting parts. Believe me, however, it doesn't always go as planned.

Fig 9 shows three tries at making the grid-trip and bias board. Actually the third board, on the left, was damaged, and a fourth was necessary. However, once you get the hang of it, it usually goes well.

After etching the board, polish it with



Fig 10—In-process testing of the input-network PC board. Each coil was trimmed to produce a 1:1 SWR into a 50-ohm load. Note the power supply required to actuate relays.



Fig 11—Subpanel installation in the cabinet. Note position of chassis plate, vacuum variable capacitors and band switch. Aluminum angle stockis used to mount the subpanel to the chassis plate and cabinet sides.

fine steel wool and drill the component mounting holes with a small drill. Use dry transfers to label the connections required to the board, before mounting parts. This will avoid wiring mistakes when the wiring harness is installed. Finally, mount and solder the components onto the board.

Test each board as much as possible before final assembly. For example, Fig 10 shows the input network being tested by hooking up coaxial cable and running 100 W through each section into a 50-ohm dummy load. The coils were adjusted at this time to give a flat 1:1 SWR. A power supply is needed to energize the relay for the pi-section being tuned.

Front-panel Fabrication

Cover the front panel with masking tape to protect it from scratches, and mark the mounting positions of the components. Take your time with this step since it is hard to recover if an error is made. Mark the front panel where the holes are to be cut and carefully drill a small pilot hole followed by the correct hole size. The holes for the band switch, capacitor control shafts, ALC control and multimeter switch are 3/8-inch diameter and can be made with a regular drill bit. The holes for the power switches are 5/8-inch diameter and require a chassis punch. The meter-mounting holes are the most difficult to make. The rectangular cutouts are marked about 1/32-inch smaller than required to protect against overcutting. Use a nibbler to cut the holes carefully, then file them to the exact size of the meter bezels. Be careful that the file doesn't slip and scratch the panel (disaster!). Using a large file will help avoid this tragedy.

I recommend doing all the front-panel metal work at one time to ensure proper component layout. When the metal work is complete, leave the masking tape on the panel for protection as it will be used as a template to locate the parts mounted behind the front panel.

Chassis and Subpanel Metal Work

This amplifier design has very little metal work that requires more than a hacksaw and a file. The chassis plate was purchased with the cabinet. The only other panel, except for front and rear panels, is the subpanel that mounts perpendicular to the chassis plate, and 3 inches behind the front panel. The subpanel shields the meter compartment from RF and serves as a mounting support for the band switch, vacuum capacitors and 80-meter toroid coil.

The chassis is mounted 3½ inches from the bottom of the cabinet to allow room under the chassis plate for the filament transformer. Therefore, the subpanel is cut to 6¾ × 16½ inches. Referring to Fig 11, ½-inch aluminum angle is attached with screws to each edge of the subpanel to provide a mounting flange to the chassis plate and cabinet side walls. The top piece of angle stock provides a mounting surface for a piece of gold-plated finger stock that seals the subpanel to the cabinet top plate.

Two large holes are required. A 3-inch-diameter hole is required in the chassis plate for the tube socket. A 5-inch-diameter hole is cut in the cabinet top plate and aligned directly above the tube socket to vent the air flowing from the tube and chimney. Use a large fly-cutter, available at most hardware stores. For safety, the fly-cutter should be used only on a drill press—never with a hand drill. Therefore, if you don't have a drill press, find a friend who has one. Before cutting the large holes, use 3-inch masking tape to cover the chassis plate and top panel to mark where the holes are to be drilled, and to protect the surfaces. For safety, clamp the panels onto a board and the base of the drill press before drilling.

Cut a piece of perforated aluminum stock to be slightly larger than the hole in the cabinet top panel. Clean the perforated metal well, and spray with paint to match the cabinet color. Fasten the perforated piece to the inside top panel with several small countersunk screws painted to match the cabinet.

Mounting Vacuum Variable Capacitors and Band Switch

The vacuum variable capacitors and band switch are mounted to the subpanel, but their control shafts must be aligned with the front panel design. Allow enough slack in the positioning of these components to perform precise alignment with the front-panel holes when the front panel is installed. To mark the hole positions on the subpanel, slide the subpanel against the rear of the front panel while both the front panel and chassis plate are bolted into place in the cabinet. Cover the subpanel with masking tape and mark the exact centers of the holes for the components. Drill the two holes in the subpanel for the vacuum variable capacitors with hole saws. Mount the vacuum variable capacitors and band switch on the subpanel.

Mounting Major Components to the Chassis Plate

The major components (PC boards, filament transformer and tube socket) are mounted to the chassis plate as shown in Fig 12. The PC boards are first mounted to ½-inch aluminum channel using sheet-metal screws for easy removal. Cover the bottom of the chassis plate with masking tape. Position and mark the PC boards, filament transformer and tube socket according to the planned physical layout. Drill the mounting holes in the chassis plate, then redrill the holes from the top with a countersink bit to allow flat-head countersunk screws to be used for mounting. This retains the flat surface on top of the chassis plate. With the ½-inch channels on the PC boards, mark the hole positions on the bottom of each channel with a pencil, using the predrilled chassis-plate mounting holes as a template. Remove the channels from the PC boards, mount the channels on the chassis plate, and remount the PC boards on the channels.

Under-Chassis Wiring

Complete the under-chassis wiring, according to the schematic diagram, using Teflon®-insulated wire. The nylon connectors near the front of the chassis connect to the front-panel power switches, the ALC potentiometer and the multimeter switch. This allows the front panel to be easily removed for rear-panel access. The small board in the front center of the chas-



Fig 12—Bottom view of the RF deck showing placement of PC boards, transformer and tube socket.



Fig 13—Bottom view of the RF deck showing harness wiring in place.

sis provides an easy way to mate the 12-pin nylon connector going to the power switches with the wiring harnesses under the chassis plate (see Fig 13). When making the PC boards, try to put all the connections to the board on one side. This allows access to the boards for maintenance without removing the wiring. Just unscrew the board from the channel and fold the board upward.

Each wire is labeled at each end with numbered tags, because the Teflon wire used is mostly the same color. A version of the schematic diagram was maintained with the wire numbers noted for easy wire tracing. The final wiring is cabled into harnesses with plastic cable ties. Don't be afraid to use plenty of ties, but at first only put a tie every inch or two. The ties will undoubtedly be cut several times during wiring to put in missing wires that are overlooked. When all wiring is complete and tested, put a cable tie every ½ inch on the major harnesses.

Amplifier Tank Circuit

The plate tank-coil set is shown in Fig 14. Before making the coils, determine the tankcircuit parameters for the given tube plate impedance. The plate impedance can be determined from Eq 1.

Plate impedance = plate voltage/ (1.57 × plate current) (Eq 1)

Assuming the amplifier runs at 60% efficiency, the input power required for 1500-W output is approximately 2500 W. With 3200 V on the 8877 plate, plate current will be approximately 781 mA. From Eq 1, a tank circuit designed for approximately 2600 ohms is appropriate. A table of pi-L network component values is contained in Hoff's article, and the values used in this amplifier are summarized in Table 2.[10]

The 80- and 160-meter coils are wound on an assembly of three T225-2 toroid cores taped together with Scotch no. 27 glass-cloth tape. Use plenty of tape to provide good voltage insulation from the cores. The 80-meter coil is wound with 11 turns of no. 10 wire covered with Teflon sleeving. The 160-meter coil is wound with 19 turns of no. 12 wire, also covered with Teflon sleeving. The cores of both coils are mounted from 1 to 2 inches from the mounting wall on ceramic insulators. Each coil is sandwiched between two pieces of fiberglass material held together by a ceramic standoff running through the middle of each toroid (see Fig 15). Wind all coils in the same direction (clockwise or counterclockwise), to avoid a "bucking" action between coils.

The 10- through 40-meter coil is made from ¼-inch soft copper refrigerator tubing. Clean the tubing using fine steel wool (000) until the surface is smooth and bright. Use a piece of pipe with an OD equal to the desired coil ID and carefully wind the copper tubing around the pipe. After the smaller diameter part of the coil has been wound, change the pipe to a larger diameter, and wind the larger part of the coil. The inductance of the coil can be easily checked using a known fixed-mica capacitor with low internal inductance and a dip meter. After determining the resonant frequency, calculate the inductance using Eq 2.

Inductance = $1/(4\ \pi\ f^2C)$ (Eq 2)

Always wind the inductor with a few extra turns and then remove turns until the desired inductance is achieved. The induc-

---

[10] I.M. Hoff, "Pi Network Design for High Frequency Power Amplifiers," *Ham Radio*, Jun 1978.



Fig 14—Plate tank coil set. Above: the various coils of the tank circuit. Right: the L toroid mounted on the rear of the band switch.

Table 2

Pi-L Network Design Parameters (See Fig 3, Part 1)

Freq (MHz)	*C1 (pF)*	*L1-L4 (μH)*	*C2 (pF)*	*L5 (μH)*	*Q*
1.8	462	22.02	2121	8.90	13.1
3.5	244	10.99	1132	4.45	13.4
7.0	113	6.03	503	2.44	12.4
14.0	55	3.08	245	1.24	12.2
21.0	37	2.05	164	0.83	12.2
24.9	30	1.70	130	0.70	12.0
29.7	26	1.48	112	0.60	12.0

L1, 10-12 meters—6 turns ¼-inch silver-plated copper tubing, 2-inch outside diameter, 2 inches long. 10-m tap at 3 turns.

L2, 15-40 meters—12 turns ¼-inch silver-plated copper tubing, 3¼-inch outside diameter, 4 inches long. 15-m tap at 2 turns, 20-m tap at 4 turns, 40-m tap at 12 turns.

L3, 80 meters—11 turns of no. 10 wire in Teflon sleeving over three T225A-2 iron-powder toroidal cores taped together with Scotch no. 27 glass-cloth electrical tape.

L4, 160 meters—19 turns of no. 12 wire in Teflon sleeving over three T225A-2 toroidal cores taped together with Scotch no. 27 glass-cloth electrical tape.

L5, L Coil—20 turns of no. 20 wire in Teflon sleeving over two T300-2 iron-powder toroidal cores taped together with Scotch no. 27 glass-cloth electrical tape. Tap as follows:

Band	*10-12*	*15*	*20*	*40*	*80*	*160*
Turn no.	2	3	4	6	10	20



Fig 15—Mounting details of 80- and 160-meter toroids.

tance measurement is only an approximate value because there is always stray inductance introduced by the interconnecting leads and the band switch.

The copper tubing is silver plated only after the ends are configured to match the mounting lugs in the amplifier. Silver plating is simple with the right materials. Go to a photographic lab and get a couple of gallons of used fixer solution. Fixer solution is not usable when it becomes saturated with silver. The labs usually sell the spent fixer for silver recovery, so you may have to pay for it. Clean the coil by giving it another brushing with steel wool, wash it thoroughly in a mild detergent and rinse it well before plating. Put the fixer solution in a large plastic container and submerge the coil in it. A bright silver plate will form within seconds. The silver plate is not very thick, but it is sufficient to keep the copper from tarnishing. The coil taps are small wrap-around clamps made from silver-plated ½-inch-wide copper strap. Plate about 2 inches of copper strap, then drill a hole in one end for a no. 8-32 screw. Using a short piece of ¼-inch tubing as a jig, bend the end sharply around the tubing with a pair of duckbill pliers. Drill a second, matching hole, but squeeze the clamp in to provide a tight fit around the coil stock. Install the clamp with a flat washer on each side to provide a compression fit. The clamp should fit tightly. Don't solder the clamps until after the amplifier is tested. When the tap location is verified, heat the clamp and coil with a large solder gun and flow solder into the connection. After soldering the coil taps, spray the coil with a thin coat of clear plastic to retain the bright silver finish.

The L coil is wound on a pair of T300-2 toroid cores taped together with glass-cloth tape. The coil is mounted on the back of the band switch and supported by the connections to the coil. The leads are not soldered to the band switch, but are held in place with no. 6-32 screws.

Other major considerations in the RF tank circuit are the TUNE and LOAD capacitors. The TUNE capacitor is a 375-pF vacuum variable. Table 2 shows that though this capacitor will easily cover 10 through 80 meters, it is too small for 160 meters. One solution is to use a 500-pF vacuum variable, but units in this size class are not readily available in the surplus market, and you probably don't want to buy a new one at approximately $500. I solved the problem by switching in an additional 160-pF capacitor in parallel with the vacuum variable for 160 meters.

A 24-V dc solenoid, mounted on the subpanel, grounds a pair of 80-pF fixed vacuum capacitors. The solenoid is powered by a small 12-V relay that is energized by the 160-meter control line on the input network control switch. The grounding strap is made from a stiff piece of brass stock obtained at a hobby shop. A hinge is made by soldering a small piece of brass tubing to the strap and putting a solid rod through the tubing. The rod is supported on each end by a small piece of Plexiglas and allowed to pivot, thus forming a hinge. A piece of flexible braid is connected from the brass strap to ground for a good connection. The strap is held in the open position by a small spring pulling the strap back toward the subpanel. The contacts on the strap and the vacuum capacitors are from a 25-A power relay and soldered in place. A piece of ¼-inch brass bar stock is used to mount the contact on the vacuum capacitor side and to absorb the shock from the closure. A rubber grommet on the brass strap, where the rod from the solenoid hits the strap, also absorbs some of the shock. This scheme works smoothly and once thought out, took about one evening to install.

The LOAD capacitor is a 1000-pF, 3-kV unit with a fixed 100-pF, 5-kV fixed mica transmitting capacitor in parallel. This provides a total of 1100 pF for 80 meters. On 160 meters, the band switch adds an additional 1200 pF in parallel to provide a total of 2300 pF. The 1200-pF capacitor consists of three 400-pF mica transmitting capacitors in parallel.

Marking and Calibrating Meters

Any meter with a movement from 100 μA to 5 mA can be used for the front-panel meters. Use two identical meters, if possible, for esthetic reasons. In a very clean environment, begin by removing any internal meter shunts (on ammeters), or any series resistors inside the meter (on voltmeters) to obtain only the basic meter movement. Nothing else need be done for the multimeter, since the calibration resistors are a part of each metered circuit. A shunt resistor must be made for the plate-current meter. Wind about 2 feet of no. 22 enameled wire on a 2-W resistor of any value over 50 ohms, soldering the wire ends to the resistor terminals. Mount the resistor across the meter terminals to form a shunt. Connect the meter in series with another meter of known calibration and an adjustable power source. Trim the enameled wire 1 inch at a time until the meters read the same. If the meter being calibrated reads too low, the wire is too short. When the meters read the same, slip a piece of heat-shrink tubing over the resistor and seal the shunt.

Carefully remove the plastic face cover and the calibrated face plate from the meter. Do this in a clean environment because the magnet in the meter will attract metal shavings that could damage the movement. With a pencil eraser, rub off the original meter lettering, but not the analog scale tick marks. With small dry-transfer letters put the new numeric scale on the meter. Be careful not to bend the pointer when reassembling the meter.

Mounting the Front Panel

Remove the masking tape from the

panel, and carefully label the front panel with dry-transfer lettering before mounting any components. Mount the meters, potentiometer and switches in place, and complete the wiring. Wire nylon connectors to the power switches, ALC control, multimeter switch and meters to mate with the connectors in the RF deck. This will result in a totally removable panel.

When mounting the front panel to the cabinet, give careful attention to aligning the vacuum-capacitor and band-switch shafts. Loosen the component mounting screws and mate the shafts, then retighten the screws. Continue the alignment process until the controls operate smoothly.

Rear-Panel Assembly

Up to now, nothing has been done to the rear panel. Mount the panel and decide where the components should mount to obtain short connections. Lay the rear panel out in the same way as the front panel, and cut the necessary holes.

Mount the blower off the rear panel, located to allow good circulation of air up to the front of the under-chassis area and back to the tube socket. Positioning of the blower is not critical as long as air is not directly blown across the tube socket, which could cause backpressure.

Mount all components to the rear panel, and mount and wire the panel to the RF deck. The rear panel is not easily removable like the front panel.

Testing the Amplifier and Power Supply

Testing is the *big* moment and the climax of several months' work. First hook up the power-supply control cable and the ground cable. Leave the high-voltage cable off. Test the control circuits to ensure that the power supply can be turned on from the RF deck and the 3-minute time delay works. Make sure that the tube filaments are on. This isn't as easy as with a glass tube, which allows you to see the filaments glow. Let the tube run for about 10 minutes, then turn the power off. Immediately remove the tube and feel if the base is hot.

Test the amplifier first on 20 or 40 meters, since these bands use the midrange of the TUNE and LOAD capacitors. With high voltage applied to the tube, first key the amplifier with no input drive power. The resting idle current should be between 100 and 200 mA on the plate-current meter.

Now apply a little drive power to the tube. The plate current should rise. Move the TUNE and LOAD controls until power output is indicated on a wattmeter. Increase the drive while adjusting the TUNE and LOAD controls to achieve about 20 mA grid current and 650 to 700 mA of plate current, to realize 1500 W output. If the amplifier works properly on this band, proceed to the other bands and repeat the tests.

Efficiency should be at least 60% on all bands, except perhaps 10 and 12 meters, where efficiency may drop to 55%. If efficiency is poor, try moving the coil taps, but recognize that moving the taps also changes the Q of the coil. Decreasing the inductance and increasing the capacitance in the tank circuit will increase the Q. The amplifier may provide more power output over a larger frequency range with a lower tankcircuit Q, but harmonic suppression will also decrease and the amplifier could start generating interference or not meet FCC standards.

I must warn you one last time. *This device could kill you in one instant if you get tied into the high-voltage circuit. Put a good ground on both power supply and RF deck, and treat the equipment with proper respect!*

Conclusion

I have spent many enjoyable hours operating with this amplifier/power supply combination, with nothing but good signal reports. It was an exhausting task, but now that it's finished, I'm glad I did it. Try building one and you'll see what I mean.

By David Rutledge, KN6EK, et al. **From *QST*, May 1997**

High-Efficiency Class-E Power Amplifiers

Part 1—With 3 to 12 W of drive, you can push 300 to 500 W CW out of an $11 transistor! The trick is to use Class E.



These 300 and 500-W 40-meter amplifiers evolved from a series of undergraduate student projects at Caltech. Our goal was to design an inexpensive amplifier that amateurs can easily duplicate.[1] The amplifiers use inexpensive, readily available power MOSFETs that can be driven by a QRP transceiver; in our case, the NorCal 40A. A block diagram of our setup is shown in Figure 1. The components of the station are shown in Figure 2.

Our 300-W amplifier uses an International Rectifier (IR) IRFP440; the 500-W amplifier employs an IRFP450. These transistors are widely used in switching power supplies, but we have not seen them previously reported for use as RF amplifiers. The MOSFETs have a maximum drain voltage of 500 V, with maximum RMS drain currents of 8.8 A for the IRFP440, and 14 A for the IRFP450. Both transistors are available from Digi-Key: The 440 costs $8; the 450 costs $11.

Class-E amplifiers are extremely efficient—about 90%. Because of the low loss, no cooling fan is required. No TR switch is needed; the received signal is piped through the amplifier itself. Even without an external filter, the amplifiers meet the FCC requirements for spurious emissions. They can be built and tuned up with an RF power meter, a multimeter, oscilloscope and a dummy load. Tune-up consists of adjusting an input coil for matching and an output coil to set the power level.

Operational Classes

In addition to the well-known Class A, B, and C operational modes, there are Class D and E.[2] In Class D and E, the devices operate as switches, half the time completely on, and the other half completely off. But transistors are not perfect switches. The MOSFETs have a resistance of about 1 Ω when on, and a capacitance of several hundred picofarads when off. Losses are greatly reduced in switching amplifiers, but there is a penalty: The output power no longer depends on the *drive power*, but rather on the *supply voltage*. This means that switching amplifiers are *not* linear amplifiers, and they are *not* suitable for SSB without additional limiting and modulating circuits. However, they are fine for CW, FSK and FM.

In a Class-D amplifier, a pair of transistors switch on and off, out of phase across an output transformer. Fred Raab, WA1WLW, recently developed a Class-D power amplifier that produces 250 W on 40 meters with an efficiency of 75%.[3] However, Class-D amplifiers are relatively complex. On the other hand, the Class-E circuit has significant advantages for the homebrewer because only one transistor, without gate bias or output transformer, is needed, and it can be driven by a low-power transceiver.

The Class-E Amplifier

The Class-E amplifier was invented and patented by Nathan Sokal, WA1HQC, and Alan Sokal, WA1HQB, in 1975.[4] It minimizes heat loss by having as little overlap as possible between voltage and current. Figure 3 shows an idealized Class-E circuit. As the switch opens and closes, the current alternately flows in the switch and in the load network. The switch voltage and current waveforms are shown in Figure 4. It may be easiest to understand the waveforms by starting at the beginning of the off-time interval. When the transistor turns off, the current flows into the resonant load network, and there is a transient voltage that rises and falls. With a properly de-



Figure 1—Block diagram of the Class-E amplifier station.



Figure 2—The components of the Class-E amplifier station. Clockwise from bottom left: the diplexer, amplifier, resonant speaker, NorCal 40A and keyed power supply. The latter houses the keyer and a pulse-stretching and shaping circuit.



Figure 3—An idealized Class-E amplifier. The transistor is represented by a switch that opens and closes at RF.



Figure 4—Class-E voltage and current waveforms. Class-E amplifiers reduce loss by keeping the overlap between voltage and current low.

signed load network, the voltage returns to zero smoothly with zero slope. The transistor switches on when both the voltage and the current are small, keeping losses low even if the switching is slow or slightly mistimed. Once the transistor turns on, the current rises smoothly until it switches off again, and the cycle repeats. The resonant load network does limit a Class-E amplifier to single-band operation.

For a given dc input power, the power output of a 90% efficient Class-E amplifier is three times greater, and the dissipated power is seven times smaller, than that of a 30% efficient Class-A amplifier. This means that for a given dissipated power, we can get *21 times* more power from a Class-E amplifier.

The Caltech Power Amplifiers

Both amplifiers have a common diagram (Figure 5) and PC board, but use components with different values. Several components are added to the basic Class-E circuit for matching and filtering. The MOSFET's gate impedance is rather low, and primarily capacitive, with a reactance of about 4 Ω. There is also a resistive component of about 2 Ω from parasitic series resistance in the gate itself, and the drain *on* resistance that is capacitively coupled to the gate. T1 reduces the 50-Ω impedance of the drive circuit to about 2 Ω to match the low resistance of the gate and sets the dc bias to 0 V. L1 is adjusted to cancel the gate capacitance; the input SWR is typically 1.5:1. C1 shunts L1 at high frequencies to reduce ringing in the VHF range. The 0-V gate bias ensures that the transistor is off when it is not driven, because this is far below the threshold voltage, which is about 4 V. We have never seen oscillations in these amplifiers.

C3 and L2 form a resonant network that produces the rising and falling voltage waveform needed for the Class-E ampli-



Figure 5—Circuit diagram and parts list for the amplifiers. Mica capacitors are available from Newark. L2, L3 and L4 are made with #10 THWN solid, insulated house wire sold in hardware stores. T1's core is an RF400-0, available from Communications Concepts (see Note 1 for supplier information). L1 is a Toko 10K (2.2 µH), available from Digi-Key. RFC1 is a J. W. Miller type 5240, available from Newark.

C1—10 pF, 500 V mica
C2—300 W, 270 pF; 500 W, 390 pF; (For C2 through C5, Cornell Dubilier mica capacitors, type CDV19, 1 kV, 5%
C3—300 W, 1500 pF; 500 W, 2000 pF
C4—300 and 500 W, 100 pF
C5—300 W, 680 pF; 500 W, 820 pF
C6—0.01 µF, 1 kV ceramic disc
J1, J2—BNC or SO-239 connectors
L1—2.2 µH, Toko 10K; available from Digi-Key.
L2—300 W, 9 turns; 500 W, 8 turns #10 THWN wound on 1¼-inch-OD plastic-pipe form; spread turns to fit holes in PC board.
L3—300 W, 4 turns; 500 W, 3 turns #14 THWN wound closely spaced on a ½-inch-diam drill bit
L4—300 W, 5 turns; 500 W, 5 turns #14 THWN wound on a ½-inch-diam drill bit form, turns spaced to occupy 1 inch
P1—Cinch-Jones P302AB
Q1—IRFP440 for 300-W amplifier; IRFP450 for 500-W amplifier; (use International Rectifier transistors only)
RFC1—40 µH, 3 A
T1—Pri: 300 W, 5 turns; 500 W 6 turns #26 stranded hook-up wire; wound on RF400-0 core, available from Communications Concepts
Misc: Berquist K10-104 insulating pad (thermal resistance of 0.2-K/W, 6-kV breakdown rating); available from Digi-Key.



Figure 6—Inside the 500-W amplifier. The large coil is L2; L3 is the small coil. The circuit board is mounted on $^1/_2$-inch standoffs. BNC connectors are used for the RF input and output. No harm is done if the RF input and output are accidentally interchanged.



Figure 7—The measured efficiency plotted against RF input power. These measurements were taken with the heat sink at room temperature. In operation, the heat-sink temperature rises and the *on* resistance increases, so that the efficiency drops somewhat. Recommended drive power for the 300-W amplifier is 3 to 4 W; for the 500-W amplifier, 6 to 12 W. The dc input power was calculated from voltage and current measurements made with Fluke 87 multimeters; the RF output power was determined with a Bird 43P wattmeter using a 500-W element. Bird lists the accuracy of this wattmeter as ±25 W, but we were able to improve the accuracy of the measurement to an estimated 1% by thermal calibration. RF input power was measured with a Diamond SX-200 wattmeter.

fier. C5 and L3 act as a notch filter for the second harmonic. Without the notch filter, the second harmonic is typically between –25 and –30 dBc instead of the –40 dBc that the FCC requires on HF. In addition, C5 and L3 transform the 50-Ω antenna impedance to about 10 Ω, the appropriate load for a Class-E amplifier. RFC1 converts the 0 to 120-V dc input from the power supply to a current source, and C6 helps keep RF energy out of the power supply.

C4 and L4 form a low-pass filter to remove VHF harmonics. Without the filter, there are several harmonics at levels from –40 to –60 dBc in the frequency range from 130 to 210 MHz. With the filter, the VHF harmonics are reduced to the –70 to –80-dBc level.

Amplifier Construction

The 500-W amplifier is shown in Figure 6 with its cover removed. The transistor is mounted on a $3\infty4^{1}/_{8}$-inch heat sink with 1-inch fins (type HS50-3.0 from RF Parts, with a thermal resistance of 2 K/W with no fan) with a #6-32 bolt and nut. The transistor generates most of the heat (about 10% of the dc power) in the amplifier, so it must have good thermal contact to the heat sink. Because the transistor's case reaches high voltages, it must be electrically isolated from the heat sink. We use a Kapton pad manufactured by Berquist that has a thermal resistance of 0.2 K/W and a breakdown voltage of 6 kV. The heat-sink surface must be free of burrs, and the transistor should lie flat on the surface with minimal stress on the leads. If a torque screwdriver is available, International Rectifier recommends a mounting torque of 10 inch-pounds. The heat-sink baseplate is an aluminum L bracket bent from 0.050-inch-thick aluminum sheet. A U-shaped enclosure cover is made of 0.016-inch-thick aluminum sheet. A hole in the cover allows insertion of a plastic screwdriver for tuning L1.

Solder Q1 and C2 flush to the PC board to reduce VHF ringing on the gate signal. Good electrical contact is needed between Q1's source lead and the heat sink. Use a #6-32 bolt and nut, with washer spacers so that the source lead does not bend. Scope-probe pigtails soldered to Q1's gate and drain leads poke through holes in the baseplate. Rubber grommets in the holes prevent the pigtails from shorting to the chassis.

L4, L3 and L2 are made by winding solid insulated wire on pipe and drill-bit forms. Orient the coils at right angles to each other to reduce coupling between them. L2 has a 7-MHz Q of 350; L3 and L4, a Q of about 170. For C2, C3 and C5, use only 1-kV mica capacitors—even 500-V capacitors fail spectacularly with a burst of flame. If a 1-kV, 100-pF capacitor is not available for C4, substitute a series-connected pair of 500-V, 200-pF mica capacitors. For best filtering, mount C4 and L4 directly on the center pin and ground lug of J2. Mount L4 with its axis vertical to reduce coupling to the other coils.

The NorCal 40A Driver

For a driver, we use a NorCal 40A,[5] but its 2-W output is not enough to drive these amplifiers. Fortunately, the NorCal 40A can be modified to deliver greater power output.[6] We recommend 3 to 4 W drive for the 300-W amplifier, and 6 to 12 W for the 500-W amplifier. These drive levels give an efficiency in the 90% range (Figure 7). Drive levels lower than these give poor efficiency; higher drive levels increase the dissipated power without improving efficiency. Don't drive the 300-W amplifier with less than 2.3 W, and the 500-W amplifier with less than 5 W. At these low power levels, the transistor may not turn on fully at all supply voltages, subharmonic spurious components may be generated, and the amplifier may not key properly.

The recommended drive powers produce peak gate voltages of between 15 and 20 V. International Rectifier specifies a maximum peak gate voltage of 20 V to avoid rupturing the gate. Although the drive levels are close to this limit, experience shows them to be quite safe. The 20-V limit is more appropriate for the low frequencies used in power supplies than for RF voltages. In controlled tests, we've pushed the 300-W amplifier to 60-V gate-voltage peaks, *three times* the manufacturer's voltage limit, without damage.

Next month, we'll discuss the keyed power supply, keying waveform shaper and tune-up. Join us!

Notes

[1] A package of amplifier parts *only*, including PC board, components, connectors, heat sink and chassis is available at cost from Puff Distribution, Department of Electrical Engineering, MS 136-93, Caltech, Pasadena, CA 91125. Price: $50 for US orders, $60 for foreign orders. The price includes tax and shipping by surface mail. Make payment by check or money order only to "Caltech-Puff Distribution." Foreign checks must be drawn on a bank with a US branch office. Please provide your Amateur Radio call sign and specify which amplifier (the 300 or 500 W unit) you want. For more information, contact Dale Yee by e-mail at **yee@systems.caltech.edu**, fax 818-395-2137, or you can download an order form from: **http://www.systems.caltech.edu/EE/Faculty/rutledge/poweramp.html**. We do not offer power-supply components. Those parts are available from Communication Concepts, 508 Millstone Dr, Beavercreek, OH 45434-5840, tel 513-426-8600; Digi-Key, PO Box 677, Thief River Falls, MN 56701-0677, tel 800-344-4539, **http://www.digikey. com**;

Newark Electronics, (many branches throughout the US; check your telephone book for a branch near you); main office: 4801 N Ravenswood Ave, Chicago, IL 06040-4496, tel 800-463-9275, 312-784-5100, fax 312-907-5217; RF Parts, 435 South Pacific St, San Marcos, CA 92069, tel 800-737-2787; Mouser Electronics, 2401 Hwy 287 N, Mansfield, TX 76062, tel 800-346-6873, 817-483-4422, fax: 817-483-0931 e-mail **sales@mouser.com**; **http://www.mouser.com**.

A template package is *not* available from the ARRL.

[2] Historically, amateurs have built high-power amplifiers with vacuum tubes rather than transistors to avoid complicated power-combining networks and many low-power transistors. See Dick Ehrhorn, W4ETO, "RF Power Amplifiers and Projects," *The 1996 ARRL Handbook*, Chapter 13. Exceptions to this are the elegant designs by Helge Granberg, K7ES/OH2ZE (SK). *RF Application Reports*, published by Motorola Inc, in 1995, contains over 20 Application Notes and Engineering Bulletins written by Helge Granberg on amplifiers with output powers of 20 to 1200 W. Communication Concepts sells the boards and components for these amplifiers. *Radio Frequency Transistors*, by Norm Dye and Helge Granberg, published by Butterworth-Heineman, Boston, 1993, is recommended reading. Joel Paladino, N6AMG, adapted one of Granberg's transistor amplifiers (see "An Experimental Solid-State Kilowatt Linear Amplifier for 2 to 54 MHz," *QST*, Sep 1992, pp 19-23). However, the power transistors alone cost $900! This led us to look for a less-expensive way to make transistor power amplifiers.

[3] Fred Raab, WA1WLW, "Simple and Inexpensive High-Efficiency Power Amplifier," *Communications Quarterly*, Winter 1996, pp 57-63.

[4] Nathan Sokal, WA1HQC, and Alan Sokal, WA1HQB, "Class-E, A New Class of High-Efficiency Tuned, Single-Ended Switching Power Amplifiers," *IEEE Journal of Solid-State Circuits*, Vol SC-10, Jun 1975, pp 168-175. This paper by father and son is a classic in the radio engineering literature, and is still the basic reference for the Class-E amplifier.

[5] The NorCal 40A designed by Wayne Burdick, N6KR, is available in kit form for $129 from Bob Dyer, KD6VIO, at Wilderness Radio, PO Box 734, Los Altos, CA 94023-0734, tel 415-494-3806, **http://www.fix.net/jparker/wild.html**. The NorCal 40A Web address is: **http://www.fix.net/~jparker/norcal.html**.

[6] A number of NorCal 40 modifications were published in *QRPp*, the magazine of the Northern California QRP club that first made the NorCal 40 kit available. For information on subscriptions to *QRPp* and back issues, contact Jim Cates, 3241 Eastwood Rd, Sacramento, CA 95821. Wayne Burdick, N6KR, suggests increasing the supply voltage for more power. If you do this, increase the voltage rating of Zener diode D12 to accommodate a larger peak collector voltage. For 3 W output, we use an MRF237 at Q7, the PA. To further increase the power to 7 W, we reduced L7 from 18 turns to 11 turns, and L8 from 18 turns to 14 turns. We replaced C45 and C47 with 560-pF, 300-V mica capacitors, and C46 with a 1500-pF, 100-V mica capacitor. For other approaches to raising the output power, see Dave Meacham, W6EMD, "5 Watts from your NorCal 40A," *QRPp*, Mar 1995, pp 6-7, and Ron Manabe, KN6VO, "Increasing the Output Power of the NorCal 40," *QRPp*, Jun, 1994 pp 42-45. Ron reports an output power of 7 W.

By David Rutledge, KN6EK, et al. **From *QST*, June 1997**

High-Efficiency Class-E Power Amplifiers

Part 2—Class-E operation permits low-cost MOSFETs to develop considerable power.

Last month[7] we talked about Class-E amplifier fundamentals and began construction of a 40-meter unit. Now we'll tackle the power supply, keyed-waveform shaper and develop some power.

A Keyed Power Supply

Nonlinear Class-E operation sharpens the CW keying envelope, causing annoying key clicks. To prevent this, we key the power supply to shape the supply voltage. A separate 4×7×12-inch (HWD) enclosure houses the dc supplies, a stretcher circuit that delivers a stretched pulse to the driver and a shaper that produces the shaped pulse for the amplifier. Figure 8 shows how these circuits connect.

So that the RF drive does not end before the shaping pulse, the keying pulse to the NorCal 40A driver is stretched a few milliseconds. The stretcher (Figure 9) takes a keyer's CMOS logic signal and provides a buffered keying waveform to the shaper and a stretched keying waveform to the NorCal 40A driver. Dc supplies (Figure 10) provide 12 V dc to run the ICs and 0 to 120 V dc for the amplifier. A wave shaper (Figure 11) gives this 0 to-120 V dc supply voltage a controlled rise and fall time to avoid key clicks. Figure 12 shows the keyed power supply with its cover removed.

There are other advantages to using a keyed power supply to control the output power. The amplifier power dissipation is low at all supply voltage levels, so that loss is kept low throughout a keying pulse. Because the keyed power supply also acts as a solid-state TR switch, a relay is not needed. This is because the supply voltage is zero except during key down. (This feature works well with the NorCal 40A, because it, too, does not use a relay for switching.) At zero voltage, the drain-to-gate capacitance in a MOSFET is quite large, and the signal from the antenna is fed through the amplifier with a loss of only about 7 dB. The NorCal 40A receiver sensitivity is excellent,[8] and a 7 dB signal loss does not hurt reception at all. A 7-dB loss degrades the MDS to –130 dBm, still far below typical 40-meter antenna noise levels of –90 to –110 dBm. On the positive side, with 7 dB attenuation, the receiver is less susceptible to intermodulation distortion from other signals in the 40 meter band. In addition, the amplifier reduces AM broadcast signals by about 20 dB. The 7-dB loss does need to be made up at the audio end. For this, we mount a 2-inch-diameter speaker in a cardboard mailing tube cut to resonate at 650 Hz for CW reception. This gives a sound level that is quite adequate.[9]



Transceiver, amplifier, and power supply for a 40-meter, 500-W station. The NorCal 40A transceiver driver is on the left, a 500-W amplifier is in the center and the power supply on the right. The amplifier's heat sink and transistor mounting screws are visible. The large dial controls the variable autotransformer, varying the RF output power.



Figure 8—Block diagram showing the connections between the stretcher, dc supplies, shaper, NorCal 40A and the Class-E Amplifier. The stretcher, the dc supplies, and the shaper are in the keyed power supply. Power supply keying is done by a Curtis keyer IC (not shown) that provides a CMOS logic-level 1 during key down. The Curtis keyer IC and application note are available from MFJ Enterprises Inc, Box 494, Mississippi State, MS 39762, tel 800-647-1800, 601-323-5869, fax 601-323-6551; e-mail **mfg@mfjenterprises.com**; **http://www.mhjenterprises.com**.(Keyer circuits using Curtis ICs can be found in recent editions of *The ARRL Handbook*.—*Ed.*)

The Diplexer

For greater reduction of spurious emissions, we recommend following the amplifier with a band-pass diplexer (see Figure 13) to terminate out-of-band spurious components in a 50 Ω load.[10] Our diplexer (in a 3.5×6×10-inch [HWD] box) uses the equivalents of a 100-pF series capacitor, an 1800-pF shunt capacitor and air-wound inductors. Stretch or compress L2 to achieve minimum SWR. The measured loss of 40-meter signals was extremely low, only 4%. Our experience shows that a diplexer can reduce all spurious components to more than –55 dBc.

Tune-Up

Refer to Figure 3 in Part 1. There are two amplifier coil adjustments. First, with the cover on and the dc input off, L1 is set for minimum input SWR with full RF input. Typically, the SWR can be reduced to 1.5:1. If it cannot be brought below 2:1, try adding or subtracting a turn from L1.

Output power is peaked by stretching or squeezing L2. Note: For safety, the amplifier's cover should always be attached when the RF drive is applied. The cover also significantly lowers the inductance of L2. Be sure to turn off the supply voltage before you touch *any* amplifier parts! A high RF voltage will burn the skin. RF burns are deep and heal slowly. Having a keyed power supply helps here, because the amplifier supply voltage is zero except during key down.

Attach a dummy load and power meter to J2. With the RF input applied continuously, slowly increase the dc input voltage, while monitoring the gate and drain voltages using an oscilloscope with 10× high-impedance probes. (You should see waveforms similar to those in Figure 15, although the peak drain voltage should be about half of


+12 V
4011
14
6
5
U1A
4
7
+12 V
R1
2.2 M
C1
1 µF
Ceramic
from Keyer
1
2
U1B
3
C2
0.001 µF
R2
500 k
STRETCH
CONTROL
8
9
U1C
10
12
13
U1D
11
R3
4.7 k
Q1
2N2222A
D1
1N4005
C3
0.01 µF
J1
Keying Pulse
to Shaper
(Figure 11)
Stretched
Keying Pulse
to XCVR

Figure 9—Stretcher circuit diagram. **NAND** gate A acts as a buffer and produces a keying pulse for the shaper. One input has an RC delay to prevent keying glitches when the power is turned on. Gates B and C are connected by an RC network that causes a pulse to be triggered on a falling edge. R2 is adjusted to ensure that the RF output from the NorCal 40A lasts longer than the shaping pulse. The components are assembled on perfboard.


T1
120 V
250 VA
Isolation
XFMR
Variable
Transformer
T2
0-120 V AC
3 A
U1
400 PIV
4 A
R1
100 Ω
30 W
Off
S1B
On
L1
25 mH
4 A
C1
1000 µF
200 V
C2
2000 µF
200 V
C3
0.01
1 kV
R2
25 kΩ
20 W
0 to 120 V
to Shaper
(Figure 11)
P1
120 V AC
Input
Off
S1A
On
F1
8 A
250 V
DS1
120 V Neon
Bulb
Assembly
T3
12.6 V
300 mA
U2
400 PIV
1.5 A
C4
680 µF
35 V
U4
7812
Reg
IN
OUT
GND
+12 V

Figure 10—Dc supplies diagram. There are two isolated supplies: one with an unregulated 0 to 120-V output controlled by an autotransformer, and another with a +12-V regulated output. Two bleeder resistors help keep capacitor voltages at safe levels when the supply is turned off or its output reduced. The 4-A bridge rectifier is an RS404LR by Diodes, Inc, available from Digi-Key. The Panasonic 1000 and 2000-µF electrolytics in the filter are available from Digi-Key. The Stancor C-2686 25-mH choke is available from Newark. We scrounged the isolation transformer and variable autotransformer from old equipment. Look for them at swap meets, or purchase equivalents from Newark (Magnetek N55M 250-VA isolation transformer and the Staco 291 3-A variable autotransformer).

that in the figure.) The RF output should begin to rise. Increase the dc input until the forward RF output power is 25% of full power. Make sure the output SWR is 1.5:1 or less. Measure the dc input voltage, and adjust L2 to give 25% power at 60 V dc. Stretching L2 reduces its inductance and increases the output power, but usually lowers the amplifier's efficiency. Squeezing L2 reduces the output power and usually increases amplifier efficiency.

Increase the dc input voltage until the amplifier reaches maximum output power. The dc voltage should now be between 115 and 120 V, and the peak drain voltage of the RF-stage MOSFET should be between 380 and 420 V. Larger peak drain voltages run the risk of transistor failures. Lower voltages may indicate an excessive drain current, which can lead to a failure. If the voltage is too high, stretch the coils a bit more. If the voltage is too low, squeeze the coils. Check the RF drive and input SWR again. You may find that they have changed somewhat and that readjustment is needed. Measure the dc supply current and voltage, and calculate the amplifier efficiency to ensure that it is 85% or above. Use a 0.001-µF capacitor to bypass the voltmeter terminals because an RF voltage there can cause a significant measurement error. (In addition, you should realize that RF power meters often have error factors as high as 10%.)

Keyed-Waveform Shaping

The keying envelope is controlled by the three potentiometers in the shaper and stretcher circuits. R3 in the shaper circuit sets the rise time, R4 sets the fall time. R3 also helps control the power supply droop as the amplifier is keyed. R2 of Figure 9 determines the stretch in the pulse that keys the NorCal 40A, so that it does not stop transmitting before the end of the shaped


+12V
4049
U1A
3
1
2
8
5
4
U1B
Keying Pulse from Stretcher (Figure 9)
R1
270 Ω
R3
Turn On 5 kΩ
U1
PVI1050
2
5
6
7
3
8
U1C
7
6
U1D
9
10
R2
270 Ω
R4
Turn Off 5 kΩ
U2
PVI1050
0 to +120 V (from Figure 10)
Q1
IRFP340
D1
1N4005
C2
0.01 µF 1 kV
C1
0.01 µF 1 kV
Shaped Pulse to Class-E Amplifier
to Figure 5
J1
Cinch-Jones S302AB
Except as indicated, decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); resistances are in ohms; k= 1,000, M= 1,000,000
IC Pins Not Shown are Unused

Figure 11—Shaper circuit diagram. A pair of optically isolated MOSFET drivers (type PVI1050) turn Q1 on and off to bring the supply voltage up and down. Keying waveform rise and fall times are adjusted by R3 and R4, which control the current to each MOSFET driver. The 270-Ω resistors limit the LED current to a safe level. The TURN-ON potentiometer is also used to keep the overshoot from the unregulated power supply to a reasonable level. D1 prevents Q1's gate voltage from drifting negative. C1 and C2 are RF bypasses. To keep the supply voltage from appearing across exposed contacts, a female socket is used at J1. All components are available from Digi-Key. Point-to-point wiring on perfboard is used.



Figure 12—The keyed power supply with the cover removed, viewed from the side. T1 is mounted on the back plate, along with the fuse and connectors for the dc output, a keying line to the NorCal 40A and the ac line input. The **TUNE** switch keys the amplifier for testing. The variable autotransformer is on the left, mounted to the front panel. In the center foreground, mounted to the base plate, is L1, the 25-mH choke. Mylar sheets are taped to the perfboards for electrical isolation. The large components are attached directly to the box. The IRFP340 is mounted on the bottom of the box using a Berquist K10-104 Kapton insulating pad, #6-32 screw and a torque of 10 inch-pounds. The other shaping circuit components are mounted on perfboard. Layout is not critical.


40-Meter Diplexer
J1
XMTR
C1
C2
C3
C4
C5
C6
L1
J2
ANT
L2
C7
C8
R1
50 Ω 2 W
See Caption and Text for Component Values

Figure 13—Schematic of our diplexer. It uses six 150 pF capacitors, two 910-pF capacitors and air-wound inductors made of 3/16-inch-wide copper tape (see Note 1).

C1-C6—150 pF, 1 kV mica 5%-tolerance (Cornell Dubilier type CDV19; available from Newark Electronics, see Note 1)
C7, C8—910 pF (same type as above)
L1—24 turns of 3/16-inch-wide copper tape, 1 3/8 inch ID; see Note 1.
L2—4 turns of 3/16-inch wide copper tape, 1 inch ID; see Note 1.
R1—50-Ω, 2-W (approx) termination, Jameco part number 71458; available from Jameco Electronics, 1355 Shoreway Rd, Belmont, CA 94002, tel 415-592-8097; fax 415-592-2503 and 415-595-2664)



Figure 14—Keying waveform of the 500-W amplifier at 30 WPM. The horizontal axis is 10 ms per division. The rise and fall times are about 3 ms.



Figure 15—Drain waveform and ringing. Oscilloscope trace of the gate and drain voltages of the 300-W amplifier with 3 W drive. The dc supply voltage is 120 V; the input SWR is 1.6:1. Time scale is 20 ns per division; the transistor off and on times are shown. The transistor is off when the gate voltage is below the threshold, typically 4 V, and on when the gate voltage is several volts above the threshold. Peak gate voltage is 16 V, and the peak drain voltage is 400 V, safely within the manufacturer's ratings of 20 and 500 V, respectively.

pulse. We recommend using a keyer with adjustable weighting to offset the pulse stretching. The potentiometer settings interact somewhat, and there are variations at different sending speeds, so it is best to set them at the speed you commonly use. Adjust the controls for rise and fall times between 2 and 5 ms, and for a smooth keying envelope. Figure 14 shows keying at 30 WPM with rise and fall times of about 3 ms.

VHF Ringing

In many Class-E amplifiers, ringing in the VHF range can be seen on the gate and drain waveforms (Figure 15). This ringing can be quite pronounced, with bumps several volts high on the gate or drain or both. The bumps disappear when the RF input is removed, and that is why we refer to this as *ringing* rather than *oscillation*. We have compared measured spectral plots with *PSPICE* simulations and believe that the waves are driven by the sudden turn-on and turn-off of the transistor, acting rather like the gong of a bell.

We notice two distinct time periods and frequency ranges for the ringing. During the time the transistor is on, the ringing frequency is about 80 MHz. This appears to be a resonance of the external drain capacitor combined with the internal inductance of the capacitor and the transistor and may indicate a mismatched load. The on-ringing is usually small if the load is matched so that the drain voltage comes smoothly to zero before the transistor turns on.

The ringing while the transistor is off covers a broad range of frequencies—from 130 to 210 MHz. If the output low-pass filter is removed, the ringing can be seen easily on a spectrum analyzer at levels between −40 and −60 dBc. The off-ringing appears to be caused by a resonance of the external drain capacitor and its internal inductance, together with the transistor's internal drain capacitance and its inductance. The internal drain capacitance varies greatly with the drain voltage, so that the frequency is modulated as the drain voltage rises and falls. The low-pass filter reduces these harmonics to the −70 to −80 dBc range.

On the Air

The amplifiers meet the FCC requirements for spectral purity [confirmed in the ARRL Lab—*Ed.*]. NorCal 40A designer Wayne Burdick, N6KR, emphasizes that it is important to correctly tune the bandpass filter following the transmit mixer to minimize spurious emissions from the NorCal 40A.[11]

These amplifiers are excellent for chasing DX, schedules and "ragchews," particularly at this low point of the sunspot cycle. The amplifiers require no warm-up, no tune-up, and produce no fan or relay noise. We can vary the power from 1 W to full power via the variable autotransformer. The antenna SWR should be 1.5:1 or better because the amplifier is not protected against large mismatches. With a high SWR, the transistor will probably overheat. Check the dc voltage when the amplifier is delivering full power to the antenna to ensure that it remains between 115 V and 120 V. Readjust the coils if the voltage is too high or too low.

Our most common problem has been a poorly mounted PA transistor. If the transistor is not flat against the heat sink, heat transfer is poor and the transistor becomes quite hot; efficiency suffers (becoming usually less than 85%) and the amplifier may not reach full power. The output power may also drift downward, a sign that the transistor temperature is increasing and that the transistor is under stress.

Component temperature can be a good diagnostic tool. For the 500-W amplifier, our experience is that for CW QSOs longer than 30 minutes, the temperature of C3, C5 (Figure 5) and the heat sink rises to about 60× C. For the 300-W amplifier, the heat-sink temperature is about 50× C. This is hot to the touch, and it can be checked with a lab thermometer. The temperature will vary according to your operating style, and if the temperature is higher than you like, you can add a fan.

The Future

We see room for improvements: protection against antenna mismatches and employment of an inexpensive keyed *switching* power supply that is as lightweight as the amplifiers. Finally, it would be interesting to develop Class-E amplifiers for the other bands. We have built a 250-W amplifier for the 20 meter band that exhibits an efficiency of 88% with 10 W drive. We believe that Class-E amplifiers provide amateurs with good building challenges and operating fun at modest cost.

Acknowledgments

This work began as senior theses by Joyce Wong and Meng-Chen Yu at Caltech, and many of their ideas appear here. John Davis was supported by a scholarship from the James Irvine Foundation and the Army Research Office. Eileen Lau, Kai-Wai Chiu, and Jeff Qin received Caltech Summer Undergraduate Research Fellowships funded by the ETO Corporation and the Caltech Gates Grubstake Fund. We appreciate the help from all the people at the ETO Corporation, particularly Dick Ehrhorn, W0ID; Don Fowler, W1GRV; Tim Coutts; Chip Keen and Frank Myer. Mitsu Sakamoto, JA4FVE, of Kurashiki, Japan, sent us off-the-air recordings over the Internet. We would like to thank Wayne Burdick, N6KR; Wes Hayward, W7ZOI; and Bill Bridges, W6FA, for their advice.

Notes

[7] Eileen Lau, KE6VWU, et al, "High-Efficiency Class-E Amplifiers—*Part 1*," *QST*, May 1997, pp 39-42. The amplifier enclosures are $3\frac{1}{8}\times4\frac{1}{8}\times7\frac{1}{8}$ HWD.

[8] Rick Lindquist, KX4V, "Low-Power Transceiver Kits You Can Build," Product Review, *QST*, Jun 1996, pp 45-50.

[9] See J. B. and R. V. Heaton, "An Electro-Acoustic CW Filter," *QST*, Apr 1983, pp 35-36; Wally Millard, K4JVT, "A Resonant Speaker for CW," Hints and Kinks, *QST*, Dec 1987, p 43; and Richard Clemens, KB8OAB, "More on Resonant Speakers," Hints and Kinks, *QST*, Jan 1989, p 37.—*Ed.*

[10] David Newkirk, WJ1Z (now W9VES), and Rick Karlquist, N6RK, "Mixers, Modulators, and Demodulators," *The 1996 ARRL Handbook*, Chapter 15, p 15.22.

[11] Telephone conversation with Wayne Burdick. This tuning is done by carefully adjusting C50 to peak the output power.

By William E. Sabin, W0IYH

From *QEX*, November 1999

A 100-W MOSFET HF Amplifier

We had the power supply in Mar/Apr[1] and the diplexer filters in Jul/Aug,[2] here's the main event: a reliable FET power amplifier that needs only 10 dBm of drive to produce a pristine 100 W output.

The two-stage amplifier described in this article and shown in Fig 1 is intended for SSB/CW/Data operation on all nine HF amateur bands. An input ($R_{in} \approx 50\ \Omega$) of about 10 mW (+10 dBm) is amplified to 100 W (PEP or average), continuous duty, with a gain of 40 1.0 dB from 1.8 to 29.7 MHz. Third-order, two-tone intermodulation distortion (IMD) products are 35 to 40 dB below 100 W, and higher-order products are also within the high-quality range for amateur SSB equipment, as shown in Fig 2. The main goal for this amplifier is to operate as a driver, with low adjacent-channel interference, for a legal-limit 1500-W linear amplifier. At this power level, adjacent-channel reduction is especially important. And, of course, it is used in the barefoot mode as well.

The power supply (40 V at 8 A) for the push-pull, class-AB MRF150MP (matched-pair) MOSFET output stage was described previously (see Note 1). Six diplexer filters (see Note 2) also known as invulnerable filters provide more than adequate harmonic attenuation for all nine HF bands. They present a broadband load impedance to the MOSFETs that helps to assure freedom from regeneration and oscillation, and good IMD performance. A resistive load impedance between 45 Ω and 55 Ω is recommended for best performance.

The MRF 150 was chosen because it is designed for linear, class-AB SSB operation and because it has high gain (gm) at the 30-MHz end of the HF spectrum. A desirable feature of the MOSFET power transistor is its ability to achieve low values of the higherorder IMD products.[3,4] As mentioned previously, these products contribute to adjacent channel SSB interference. The first stage uses high-gain, class-A push-pull MRF426 (matched-pair) BJTs that require 13.5 V at about 1.0 A from a separate supply. This supply is also the main supply for other system components. Matched pairs of both transistors are available for a small extra fee from at least two sources.[5,6] They are both listed in the current Motorola manual.[7]

One main idea for this amplifier is to operate it in a very low-stress manner that helps assure a low probability of failure for a very long time, which offsets the initial cost of the high-quality transistors. The MRF150 is a 50-V transistor operated at 40 V; the MRF426 is a 28-V transistor operated at 13.5 V. The required input level is low enough that most of the amplification at the signal frequency occurs in one gain block. Because of the good layout, circuit design and decoupling, the 40-dB gain value does not result in any stability problems.

The balanced amplifier greatly reduces even-order harmonics—especially the second—prior to any output filtering, as shown in Fig 3 for a 7.0-MHz signal. It should be 40 dB or more below a 100-W CW signal for each amateur band. This reduction has been found reliable, once achieved. The lowlevel signal source that drives this amplifier must have at least 50 dB of second-harmonic attenuation, since this amplifier will not suppress that harmonic. This is easy to accomplish, but must be considered during the equipment system design (see Fig 9) and while bench-testing the amplifier as shown in Fig 4.



Fig 1—The 100-W broadband amplifier.



(A)

(B)

(C)

(D)

Fig 2—Two-tone IMD products: (A) 3.8 MHz, (B) 14.2 MHz, (C) 21.2 MHz, (D) 28.5 MHz.

Circuit General Discussion

Fig 5 is the schematic of the two-stage amplifier. It utilizes 1:1 choke baluns and 1:4 (impedance) step-up and step-down transmission line (Guanella) transformers. The choke baluns significantly improve the balance of the input and output stages. Notice also that T2, T3 and T4 have floating center taps rather than bypasses to ground. This is recommended to improve the even-harmonic balance[8] (verified). T4 and T5 run slightly warm as compared to conventional transformers that get quite hot. The 5-W feedback resistors get warm, but their large surface area limits their temperature rise. They also receive cooling air from the fan. All power resistors in the RF circuits are the excellent metal-oxide types (see Note 5) that are quite stable with age and temperature, and have very low reactance at 30 MHz (measured). Metal-film 1% resistors are used in several critical locations.

The first stage has resistance and inductance loading from collector to collector. A powerful free-running oscillation in the first stage at about 32.5 MHz was being triggered occasionally at the moment of dc supply turn-on while a fairly large 28.0 to 29.7 MHz input was present. The loading reduces stage gain and suppresses the parasitic collector circuit resonance that produced the oscillation. It also helps to flatten the amplifier frequency response.

The second stage has a very low value of RF resistance, 15 Ω, from each gate to ground that helps to assure stability. Because these resistors are in parallel with the large input capacitance of the MOSFETs, they also help to flatten the frequency response. Both stages have negative feedback networks that further assure stability and flatness of frequency response.

Two biasing networks are employed. The LM317 provides a highly regulated gate voltage for the second stage. The FET dissipation and linearity are very sensitive to this voltage; the bias voltage for SSB is fine-tuned for best signal purity using two-tone tests and a spectrum analyzer. Note the four 562-a resistors. If the LM317 fails short circuit, the voltage on the FET gates does not exceed 6.8 V, which will not damage the gates. The large drain current that results from this failure also does no damage because the 40-V power supply has current limiting and voltage fold-back that prevent harmful FET dissipation. The FETs are thus kept well within the safe-operating-area (SOAR) as defined in data sheets[9] (verified). It is important that each 56241 resistor from gate to ground be permanently attached directly between the gate and source tabs of the FETs themselves so that the gates are never floating. Wrap the resistor leads around the tabs so that they cannot come loose. This avoids accidental static charges that might ruin them. On the other hand, it is better to tack and not wrap the base-collector and gate-drain signal leads so that they can be easily disconnected. We want to be able to test individual segments of the circuitry easily. In my experience, the MRF150 has proven to be a rugged transistor, much more so when operated conservatively and with the power-supply safeguards that I mentioned.

The LM317 provides about 5.8 V for the particular pair of FETs that I used. Individual pairs of FETs will probably require an adjustment of this voltage for idling current and for IMD products that resemble Fig 2. The adjustment procedure is described later. This bias value is set to emphasize the reduction of the higher-order products rather than third- and fifth-order products. These lower-order products do not contribute as much to adjacent channel interference; in fact, an SSB speech processor will make them worse anyway. The higher-order products need to be reduced and the MRF150 has this capability.

The 2N3906 PNP transistor is a bias-current source. The value of this current is determined by the 4.7-Ω resistor and the base-to-ground voltage of the 2N3906. The two 562-Ω resistors force equal base currents into the MRF426s. This helps to assure equal performance. The 0.47-Ω resistor is part of a negative-feedback bias ioop. If collector current increases, the voltage across this resistor increases and this reduces the base current. Thermal runaway is avoided by this strategy because the reduced base bias restricts the current increase to a small value. Because of the low dissipation of the MRF426s and the good heat sink, this method is very effective. These transistors are also well inside their SOAR requirements. This stage is very linear and contributes almost nothing to the overall IMD products. To verify this, it is necessary to turn off the drain voltage to the MRF150s and connect a spectrum analyzer across one of the 15-Ω resistors.

The diplexer filter method was decided uponafter a lot of experimentation with other low-pass filter methods as a solution that is free of problems caused by complex interactions between the filters and the output transistors. A special peculiar problem is discussed later. The MRF150 has high gain into the VHF region; the diplexers eliminated all problems associated with this fact. This approach is recommended as a simple way to assure correct operation for HF amateur-band operation of these high-frequency MOSFETs. I was able to get good enough operation with the more conventional low-pass filters, but this approach was by far the most satisfactory for an amateur-band amplifier, as confirmed by swept-frequency tests at all power levels into a 50-Ω load. More about complex loads later.



Fig 3—Wideband spectrum for a 7-MHz signal.


Signal Generator 0.1 to 60 MHz
Two-Tone Generator for Each Band
Narrowband Filter for Each Band
Tracking Generator 1.0 to 30 MHz
Dual Beam 100 MHz Oscilloscope
Spectrum Analyzer 0.1 to 100 MHz
Attenuator 1.0 to 20 dB
Temperature Monitor
A
B
50 Ω
Balanced Low Distortion Preamp 20 dB
Attenuator 6 dB
Amplifier Under Test
Input 50 Ω
Attenuator −30 dB
Bypass
1 Foot or Shorter Coax
6 Diplexer Filters
Fwd
Directional Coupler −30 dB 1000 W
Wattmeter 100 W
Dummy Load 50 Ω 100 W
1.8 - 100 MHz Wideband

Fig 4—Block diagram for equipment setup, design and testing of the MOSFET amplifier.


IN 0.01 W 1.8-29.7 MHz
R1 270
R2 18
R3 270
−3 dB
T1
C1 160 SM
T2A
T2B
C2 0.1
C3 0.1
R4 178 MF
R5 3.9
C4 0.0033
C8 0.0033
R8 3.9
R9 178 MF
L1 0.68 µH
L2 0.68 µH
C5 0.047
C9 0.047
R6 12
R7 12
C6 0.1
C7 0.1
426 Bias
Q1 MRF426
Q2 MRF426
L3 0.8 µH
R10 51* 2 W
R11 100* 2 W
T3A
T3B
L4
C28 1.0 µF 35 V
R22 0.47 5 W
C26 1.0 µF 35 V
C27 470 µF 35 V
+13.5 V REG
R23 4.7
R25 390
D1 1N4454A
R24 5.6 k
Q5 2N3906
C29 470 µF 15 V
R26 562 MF
R27 562 MF
426 Bias
C10 0.1
C11 0.1
R12 15* 2 W
C12 0.1
R14 562 MF
Cx
R13 100 5 W*
R15 562 MF
C14 0.1
L5 2.7 µH
+5.5 V
C13 1.0 µF 35 V
C15 0.022 100 V
Q3 MRF150MP
T4A
T4B
C20 0.1
C21 0.1
R16 15 2 W*
C22 0.1
Cx
R17 100 5 W*
C19 0.022 100 V
R18 562 MF
R19 562 MF
Q4 MRF150MP
C23 0.1
L8 2.7 µH
+5.5 V
C25 1.0 µF 35 V
U1 LM317
Reg
IN
GND
OUT
R20 215 MF
R21 767 MF (See Note 1)
C16 0.022 100 V
C18 0.022 100 V
T5
L6 0.22 µH
C17 56 pF
Out 100 W
L7
C24 0.1 100 V
+40 V 8 A REG
G

Except as indicated, decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); resistances are in ohms; k=1,000.
Cx, See text
* See text
Note 1: Select for best I.M. Q-point.

Fig 5—(left) Schematic diagram of a two-stage, 100-W amplifier. Unless otherwise specified, use ¼ W, 5%-tolerance carbon composition or film resistors. Resistors marked with an asterisk are metal-oxide units. MF indicates metal-film resistors. Both the MRF426 and MRF150 devices are matched pairs. All capacitors are 50 V, unless otherwise indicated.



Fig 6—Gain variation, 1.8 MHz to 29.7 MHz, 1.0 dB per division vertical scale—The lower trace is a reference sweep that bypasses the 100-W amplifier—The response bump at low frequency is an artifact of the tracking generator.

Frequency Compensation

The bipolar transistors have gain values that decrease as frequency increases. The MOSFETS have large capacitances that also affect frequency-response roll-off. It was a major exercise to design networks that flatten the response from 1.8 to 29.7 MHz. Fig 5 shows the approach. The idea is to compensate smoothly from input to output in such a way that neither of the two stages is over-driven at any frequency. The criterion for this is to check IMD products and harmonics during the design process, which involves approximate analysis (see the MOSFET Stage Simulation sidebar) and negative feedback.[10] Beyond about 32 MHz, the gain falls off fairly rapidly (but not too rapidly). This is also desirable.

When testing the frequency response using the test setup of Fig 4, it is necessary to measure the frequency response of the signal path from tracking generator to spectrum analyzer while bypassing the 100-W amplifier. This reference response is then compared with the response with the amplifier in the path, as shown in Fig 6. Note the vertical scale: 1.0 dB per division. For the most credible results and ease of measurement, it is very desirable that the impedance looking back from the input be 50 Ω.

Signal Level Testing

We want to verify that the first stage is operating normally by measuring its RF voltages at 4.0 MHz. The class-A first-stage input impedance is close to 50 Ω, and the input level is +10 dBm. Temporarily disconnect the signal leads to the gates of the FETs. The voltage at each output of T3 is about 1.35 V. Reconnect the gate signal leads. The final output over the entire range into an unfiltered, wide-band 50-Ω load is then observed using the setup in Fig 4. A spectrum analyzer with tracking generator is very valuable for this. The accuracy of the wattmeter should be verified or calibrated by some means at both the 100-W and the 25-W levels (the power of each tone of a two-tone, 100-W PEP signal) in each amateur band.

If the second stage is working correctly, the output power is 100 W, or 71 V RMS across 50 Ω. These procedures assure that both stages are working properly and amplifying as intended. Because of the variations in the fabrication of the transistors, the total gain can vary a decibel up or down despite the use of negative feedback in each stage. I suggest the 3-dB attenuator at the input not be modified for simplicity reasons.

The drain-to-drain load impedance of the class-AB output stage is 12.5 Ω and the CW output power is 100 W, so the drain-to-drain ac voltage is 35.4 V. Fig 7 shows the dual-trace scope waveforms (chop mode) on each drain, superimposed on the 40-V supply, and also the drain-to-drain waveform that is confined to the linear region. The third-harmonic content is visible. It is interesting to note that although these waveforms show considerable non-linearity, the fundamental component is quite linear with respect to the gate signal level. I also found that a 50-V dc supply created more heat, but at 100W, did not improve linearity enough to make it worthwhile. The 35.4 V ac also appears across the two series-connected 100-Ω feedback resis-



(A)

(B)

Fig 7—(A) drain and (B) drain-to-drain oscilloscope waveforms.

tors; they dissipate about (35.42)/200 = 6.3 W, or 3.2 W per resistor (64% of the 5 W rating).

A broadband, untuned power amplifier with flat frequency response and low distortion is not, by necessity, especially energy-efficient (ratio of RF output power to dc power). The output stage is less than 40% efficient for this reason. For SSB use, where the average power is not more that 25 W, even with speech processing, this is no problem at all. For continuous key-down at 100 W, the cooling fan is more than adequate.

Here is an important caution about using oscilloscope probes at the FET drains and the output connector: A 10:1 probe could be damaged (it happened to me) if used directly at this RF voltage level, especially at the upper end of the HF range. Use instead the homemade probe described previously (see Note 2) with a 50-Ω terminating resistor.

The quality of balance is checked by looking at the second harmonic on a spectrum analyzer using the setup in Fig 4 with the diplexer filters out of the signal path. At 100 W output, check the harmonics in each of the nine amateur bands. Capacitor C_x in Fig 5 is used (if needed) to improve the secondharmonic phase balance on the higher amateur bands. If the value is not well below 40 dBc, use C_x at one gate or the other to achieve 45 dBc. Extra pads are provided on the PC board for this capacitor. A value of between 22 pF and 56 pF should be adequate. Overkill is neither necessary nor desirable: The output filters will do the rest. For each decibel of power output below 100 W, the second harmonic normally drops about two decibels.

Construction Notes

Fig 1 shows how my version of the amplifier is constructed. A 0.125-inch (or 0.062-inch) double-clad PC board, 3.25 × 8.0 inches, is firmly attached to the heat sink. I suggest using this compact size for best reproducibility. The heat sink shown may not be presently available from RF Parts (see Note 5), but I also purchased a Model 99 sink from CCI (see Note 6) that is 6.5×12 inches. This can be easily tailored to the appropriate size with a band saw that has a metal-cutting blade. Pieces of angle and sheet aluminum can then be creatively fashioned to accommodate the fan (RadioShack #273-242) and the PC board that contains the bias circuitry. The transistors are bolted directly to the heat sink (through cutouts in the PC board) using heat-sink compound and tapped (and carefully deburred) #4-40 holes. Careful mounting of the transistors is essential. The main PC board has small sections of copper removed underneath the base and collector tabs of the MRF426s and underneath the gate and drain tabs of the MRF150s, so that accidental grounding is avoided. Use a hobby knife to define the areas and a hot soldering iron to peel off the copper.

A bottom cover is advised, as shown, so that air is funneled through the heat-sink fins efficiently. For a 100-W, continuous, single-tone output, the exhaust air temperature reaches 50°C. I used a RadioShack #22-174 multimeter with its temperature probe mounted inside the fins to monitor temperature during the design and testing phase.

The components are mounted on a set of seven small PC boards, six of which are mounted vertically (as shown) and bolted to the drilled-andtapped heat sink through the PC board, using #4-40 screws and small angle brackets. I used stiff, right angle #6 solder lugs that worked out very nicely. The seven PC boards are cut from a single 4×6-inch two-sided PC board, shown in Fig 8. The bias circuit board has a ground plane; the others do not. This set of boards is available from FAR Circuits.[11]

I chose this method because it is easy, makes the amplifier more compact, reduces stray L and C that can degrade the wide-band frequency response and reduces stray couplings that can impair stability and harmonic balance. It also allows the ground plane to be one continuous surface, which is a plus factor. This approach worked out very well and I recommend it as a simple approach.

Temperature Rise

The cooling fan is important. This amplifier, as designed, should have the fan running, and I have found that a simple and reliable way to keep everything safe. It has been tested at 100 W continuously, for sev-



Fig 8—Etching pattern for a 4×6 inch (finished size) PC board that provides the seven individual boards.

MOSFET Stage Simulation

A simplified analysis of the second MOSFET stage is presented (Fig A) to illustrate the effect of the resistive negative feedback of the 100-Ω resistors and the 40-pF gateto-drain capacitance. The simulation diagram shows the voltagecontrolled current sources with a G_m of 6.0 S, which is assumed constant over frequency. The gate-to-source capacitance is 360 pF and the drain-to-source capacitance is 200 pF. These numbers are from the MRF150 data sheets.

The frequency plot (Fig B) obtained from the ARRL Radio Designer program shows the gain, MS21 (dB), with (lower trace) and without (middle trace) the 100-Ω feedback resistors. The gain variation is reduced from about 6 dB to about 1.5 dB. In this simplified model (good enough for this illustration), the gain drop is caused by the capacitors, especially the 40-pF capacitor whose influence is greatly magnified by the Miller effect. If this 40-pF capacitance is eliminated from the simulation, the frequency response variation—even without the feedback resistors—is less than 1.0 dB, as seen on the upper trace.

If the power output at 15 MHz is to be held constant, the turns ratio of the output transformer and the value of the feedback resistors can be manipulated to achieve that end. The simulation shows that a turns ratio of 1: $\sqrt{2}$ and a resistor value of 120 Ω does this. The FET load impedance is now 25 Ω instead of 12.5 Ω. The increased voltage gain makes the Miller effect greater and increases the gain variation (lower trace) to 2.3 dB. The drain-to-drain voltage is now 50 V instead of 35 V, and this results in higher drain efficiency for the MOSFETs. However, the push-pull 1: $\sqrt{2}$ -turns-ratio transmission-line transformer is not as simple as the 1:2 that uses 25-Ω coax, and for me, that was the determining factor.



Fig A—A circuit used to analyze the PA output stage with ARD.



Fig B—The analysis results.

eral hours. The MOSFETswell separated on a good heat sink and with efficient airflow do not have a temperature-controlled gate-bias arrangement because I did not find it necessary at this power level. Because of the spread in threshold voltage of individual matched pairs, a one-time adjustment of gate bias is needed. The following simple procedure is used:

- Replace R21 with a resistor decade box set at 750 11.
- Place a 0-10 A meter in the +40-V line.
- With *no* signal input, switch on the amplifier and let the current reach its final value, which should reach about 1.5 A as the FETs warm up.
- Adjust the resistor value until DD is 1.5 A. After each adjustment, allow time for the FETs to reach a steady current value. This final value is not critical, but should be within 10%.
- Check the two-tone IMD at 100 W PEP (50 W average) and make further small changes, if needed, to resemble the IMD patterns in Fig 2.

In this amplifier, we are able to use the self-limiting feature of the MOSFET. This approach would not be appropriate in higher-power, higher-temperature amplifiers because of thermal runaway possibilities, where the decrease with temperature rise of the gate threshold voltage exceeds the decrease of the dc transconductance.[12,13] If fan reliability is a concern, add a thermal cutout switch to the +40-V line.

Load Impedance

Swept- and fixed-frequency tests at many signal levels and voltage valuesusing various values of parallel conductance and capacitive/inductive susceptancedid not reveal instability problems at SWR values less than 2:1. A tendency to oscillate in a peculiar manner occurred in the 20.0 to 29.7 MHz range, but only with input signal applied (a driven oscillation) and certain values of drive level, supply voltages less than 30 V, SWR of 3:1 or more, and a certain range of shunt capacitance at the output of the amplifier itself or at the output of the 12/10 meter diplexer. The instability shows up as a Christmas tree pattern in which discrete, uniformly-spaced 2- to 4-MHz sidebands appear on the main carrier. It is due to a parametric effect[14] involving the voltage-variable capacitances of the MOSFET transistors that is somehow enhanced by the shunt test capacitance. Shunt inductance did not produce the problem. The amplitude modulation of the carrier by the low-frequency oscillation is clearly visible on an oscilloscope. The low-frequency oscillation itself can be seen on a spectrum analyzer. At SWR values less than 2:1 and drain voltages greater than 35 V (40 V is recommended), the safety margin is large. The 0.22-µH, 56-pF network at the output greatly assisted with this problem. A coax cable from the PA to the diplexer assembly that is a foot or less duplicates my test setup. Under these conditions, there is no stability problem on any band caused by load-impedance values that my testing could identify. Actually, a resistive load between 45 Ω and 55 Ω is recommended for best SSB linearity, as mentioned previously. While driving a high-power linear amplifier to its rated two-tone SSB output, adjust its input impedance to 50 Ω resistive as closely as possible on each band, using a 50-Ω directional wattmeter. A broadband (untuned) solid-state driver amplifier such as this one requires such attention to load value for best results as compared to pi-network vacuum-tube PAs that can transform a fairly wide range of complex load impedance values to the correct tube plate load resistance at resonance.

It is difficult to achieve stability in a broadband, transistor power amplifier. Having done so, it is still wise to operate into the correct 50-Ω load as closely as possible. The monitoring of forward and reflected power in Fig 9 is helpful for this and assures clean, stable and reliable operation. This circuitry will cut back the drive level to a value that protects the output stage from excessive drain current or gate drive. Incidentally, the first stage goes into saturation far below the level that would damage the MOSFETs.

System Design

Fig 9 suggests a system implementation of the amplifier. For the flattest frequency response of the complete system from 1.8 to 29.7 MHz, the circuitry that drives this amplifier should also have a flat response and a 50-Ω output resistance—both easy to achieve. If it is not perfectly flat or not exactly 50 Ω, it may be necessary to slightly adjust the drive level on each band, which is not difficult. As mentioned before, the second-harmonic production of the circuitry preceding this amplifier must be of sufficiently low level (50 dBc) that balanced, push-pull operation is necessary. Narrowband resonator filters are also very commonly used for amateur-band harmonic reduction in low-level exciter circuitry.[15,16]

The directional coupler detects excessive forward and reflected power. Both of these are displayed on a panel meter. The directional couplers forward port is also a

Parts List

C1—160 pF SM
C2, 3, 6, 7, 10-12, 14, 20-23—0.1 μF, 50-V CK05
C4, 8—0.0033 μF, 50-V CKO5
C5, 9—0.047 μF, 50-V CKO5
C13, 25, 26, 28—1.0 μF, 35-V tantalum
C15, 16, 18, 19—0.022 μF, 100-V CK05
C17—56 pF SM
C24—0.1 μF, 100-V CKO5
C27—470 μF, 35-V aluminum
C29—470 μF, 15-V aluminum
D1—1N4454A or equivalent
L1, 2—0.68 μH, T50-2 core, 10 turns #26 AWG
L3—0.80 μH, T50-2 core, 12 turns #26 AWG
L4—BN-43-3312, 4 1/2 turns #22 hookup wire
L5, 8—2.7 μH molded
L6—0.22 μH, T50-2 core, 5 turns #26
L7—2 FB-43-5621 cores, 1 1/2 turns #12 stranded
Q1, 2—MRF426 matched pair
Q3, 4—MRF150 matched pair
Q5—2N3906 PNP
R1, 3—270 Ω, 1/4 W, 5% tolerance
R2—18 Ω, 1/4 W, 5% tolerance
R4, 9—178 Ω, 1/8 W metal film, 1% tolerance
R5, 8—3.9 Ω, 1/4 W, 5% tolerance
R6, 7—12 Ω, 1/4 W, 5% tolerance
R10—51 Ω, 2 W metal oxide
R11—100 Ω, 2 W metal oxide
R12, 16—51 Ω, 2 W metal oxide
R13, 17—100 Ω, 5 W metal oxide
R14, 15, 18, 19, 26, 27—562 Ω, 1/8 W metal film, 1% tolerance
R20—215 Ω, 1/8 W metal film 1% tolerance
R21—767 Ω, 1/8 W metal film 1% tolerance, test selected
R22—0.47 Ω, 5W wire-wound
R23—4.7 Ω, 1/4 W 5% tolerance
R24—5.6 kΩ, 1/4 W, 5%
R25—390 Ω, 1/4 W, 5%
T1—BN-43-202, 2 1/2 turns #32 AWG, bifilar
T2A, B—BN-43-202, 2 1/2 turns #32 AWG, bifilar
T3A, B—BN-43-3312, 2 1/2 turns 25-Ω miniature coax*
T4A, B—(2) FB-43-5621, 1 1/2 turns 25-Ω miniature coax*
T5—(2) FB-43-5621, 2 1/2 turns 50-Ω miniature coax
U1—LM317 adjustable voltage regulator

Notes

*Microdot D260-4ii8-0000 available from Communication Concepts, Inc.
All cores are available from Amidon.
Closely matched transistor pairs are from RF Parts (see Note 5).



Fig 9—System implementation of the 100-W amplifier.

source of ALC voltage. These control voltages are fed back to the appropriate gain-controlled stages in the exciter. Gain control of the transistors in the 100-W amplifier is not recommended because changes in base or gate bias will degrade amplifier linearity, IMD products and possibly the flat frequency response. There are better ways to accomplish the gain-control task, such as preferably in a lowlevel IF amplifier. With respect to IMD, we are trying to control the odd-order curvature of the MOSFET transfer characteristic—especially for the higher-order products—by setting the gate-bias point. The bias value is found by looking at IMD on each amateur band and selecting the best compromise value. This was discussed previously in this article.

The diplexer filters are linked to the other band-switch circuitry so that the correct filter is always switched in. The TR relay is at the output of the diplexers. Do not hot-switch the diplexer filters because this might damage the inexpensive relays.

Conclusion

In conjunction with the power supply (see Note 1) and the diplexer filters (see Note 2), the amplifier described here is a basic module for homebrew equipment that should satisfy the requirements for a 100-W power level, a 1.8 to 29.7 MHz bandwidth and a high-quality signal. It should run trouble-free for a very long time. The initial cost of the four transistors is about $180, but they will last indefinitely if cared for properly. The ones that I use were abused considerably during the experimentation and continue to work perfectly. The approach that I suggest is best implemented with diplexer filters and a preamplifier that has very low second-harmonic output and low IMDboth easy to get at +10 dBm. The payoff for me is excellent performance and reliability, once the design was completed.

This project is suggested for the homebrew enthusiast who has at least some part-time access to lab-quality test equipment. Others who do not care to build may find the article, together with numerous other sources, interesting background information regarding MOSFET power-amplifier design and test methods.

Any attempt at building and testing this amplifier should also use the 40-V power supply in the referent of Note 1 or something similar. The automatic current limiting at 8 A, the automatic reduction of drain voltage, the short-circuit limiting to 4 A and the manual control down to 24 V help to protect the MOSFETs from mishaps that are bound to occur.

Notes

[1] W. Sabin, W0IYH, "Power Supply for a MOSFET Power Amplifier," *QEX*, Mar/Apr 1999, pp 50-54.

[2] W. Sabin, W0IYH, "Diplexer Filters for an HF MOSFET Power Amplifier," *QEX*, Jul/Aug 1999, pp 20-26.

[3] N. Dye and H. Granberg, *Radio Frequency Transistors* (New York: Butterworth-Heinemann, 1993), pp 42-43.

[4] W. Sabin and E. Schoenike, *HF Radio Systems and Circuits* (Tucker, Georgia: Noble Publishing Co, 1998), Chapter 12, Solid State Power Amplifiers, by R. Blocksome. This chapter is highly recommended regarding solid-state SSB power amplifiers. This book is also ARRL Order No. 7253. ARRL publications are available from your local ARRL dealer or directly from the ARRL. Mail orders to Pub Sales Dept, ARRL, 225 Main St, Newington, CT 06111-1494. You can call us toll-free at tel 888-277-5289; fax your order to 860-594- 0303; or send e-mail to **pubsales @arrl.org**. Check out the full ARRL publications line on the World Wide Web at **http://www.arrl.org/catalog**.

[5] RF Parts Co, 4355 Pacific St, San Marcos, CA 92069; tel 760-744-0700, 800-737-2787 (orders only), fax 760-744-1943; **rfp@rfparts.com**, **http://www.rfparts.com/**.

[6] Communication Concepts, Inc. (CCI), 508 Millstone Dr, Beavercreek, OH 45434; tel 937-426-8600, fax 937-429-3811; **cci.dayton@pobox.com**, **http://www. communication-concepts.com/**; ask for a catalog.

[7] *Motorola Wireless Semiconductor Solutions, Device Data*, Rev 9, Vol. II; Motorola #DL110/D. The data book is available from RF Parts (see Note 5). (A Motorola Selector Guide is available at **http://www.motsps.com/books/sguides/pdf/sg46rev18.pdf**. There is a MRF150 page at **http://www.mot-sps.com/products/rf_and_if/rf_transistors/high_power/power_mosfets/mrf150.html**. A MRF426 datasheet (MRF426/D) is available at **http://www.zettweb.com/CDROMs/cdrom013/pdf/mrf426rev0.pdf**, which is not a Motorola site—*Ed.*)

[8] Dye and Granberg, pp 113-115.

[9] *Motorola Wireless Semiconductor Solutions*; see pp 4.2-133 for the MRF151, similar to the MRF150. (See Note 7 for an MRF150 URL—*Ed.*)

[10] Dye and Granberg, Chapter 12.

[11] The set of boards costs $12 plus shipping and handling. FAR Circuits, 18N640 Field Ct, Dundee, IL 60118-9269; tel 847-836-9148 (Voice mail), fax 847-836-9148 (same as voice mail); **farcir@ais.net**, **http://www.cl.ais.net/farcir/**.

[12] Dye and Granberg, Chapter 4.

[13] H. Granberg, Wideband RF Power Amplifier, *RF design*, Feb 1988; also *Motorola RF Application Reports*, AR313, p 424.

[14] Dye and Granberg, similar top 124, Fig 7.7.

[15] *The ARRL Handbook* (Newington, CT: 1995-2000 editions), ARRL Order No. 1832; pp 17.60–17.66 and Fig 17.69. See Note 4 for purchasing information.

[16] W. Sabin, W0IYH, "Designing Narrow Band-Pass Filters with a BASIC Program," *QST*, May 1983, pp 23-29.

By Jim Valdes, WA1GPO

From *QST*, June 2003

The FARA HF Project

Would you like an economical and relatively easy to build 30 W HF amplifier? For about $130 worth of parts you can give that QRP rig an extra 12 dB of muscle!

One of the larger and more active radio clubs in the Cape Cod, Massachusetts area is the Falmouth Amateur Radio Association (FARA). Some of its members are affectionately referred to as the "hackers"–those who enjoy the construction phase of Amateur Radio. The renewed interest in low power (QRP) radios in the 2 to 5 W output range resulted in the desire for a 10 to 12 dB gain RF linear amplifier producing 30 to 40 W of output power. Commercial amplifiers capable of being driven with less than 50 W below 30 MHz are prohibited by FCC regulations.[1] As a radio amateur, you are permitted to construct one amplifier per year for your personal use. The amplifier described here is relatively easy to fabricate, given a basic knowledge of electronics and some familiarity with hand tools. This article describes in detail the construction of a 12 dB, nominal 30 W output, 1.8 to 30 MHz RF power amplifier. It is intended for 12 to 14.7 V dc operation, making it ideal for mobile use.



Figure 1—The completed 30 W amplifier. The band switch takes care of output low-pass filter switching.

Amplifier Description

The design of the amplifier is based upon common engineering practices. Ideas gathered from researching the handbooks published by the ARRL and The Radio Society of Great Britain (RSGB), as well as articles published in *QST* and other journals formed the basis of the design. This amplifier uses readily available components...many of the earlier designs were based on the Motorola MRF series of RF devices that are no longer available or are prohibitively expensive.

The amplifier is housed in a 5 × 7 × 2 inch aluminum box. It consists of two stacked circuit boards—an RF amplifier and a low-pass filter. The completed amplifier is shown in Figure 1. Figure 2 is the schematic diagram of the RF assembly together with the amplifier and low-pass filter parts list and Figure 3 is the low-pass filter schematic. The amplifier can be driven by 2 to 5 W at the RF input; an input attenuator consisting of R1, R2 and R3 must be selected (as noted in Figure 2) to ensure the proper drive level (2 W) for the push-pull (2SC2312C device types) class AB amplifier stage. T1 is wound on a small binocular core with a 4:1 ratio as detailed on the schematic. The low impedance secondary is a single turn center tapped; it carries the bias voltage to the output transistors. The bias voltage is derived from the LM317 regulator, which is operated as a switched current source. The LM317 is switched on when the internal PTT line is activated. Bias voltage is developed across the FES8J diode, which is in intimate thermal contact with the output transistors. The output transformer (T2) is also wound with a 4:1 ratio; it has a single-turn sense winding. The single-turn feedback winding provides some degree of negative feedback to flatten the gain and stabilize the input impedance over the HF frequency range. The RC network in the input base circuit establishes the overall gain. The 6.8 W series resistors determine the gain below 14 MHz, while the 4700 pF capacitors are effective above 14 MHz.

Figure 4 shows the output power versus frequency characteristics of the amplifier, including the second and third harmonic response. All measurements were made with an IFR1600S Communications Service Monitor. In all cases, harmonics were greater than 40 dB down referenced to the fundamental frequency (–40 dBc), and the amplifier meets current FCC requirements for spectral purity.[2] Note that the gain starts to decrease above 21 MHz, rolling off from a nominal 30 W to 20 W at 29 MHz. On 10 meters this still represents 10 dB of gain, a worthwhile improvement. The dc voltage to the output transistors is decoupled by the pi network at the center-tapped primary of the output transformer, T2. This winding carries substantial current and should be wound with #18 Teflon covered wire. Any IR drop in the dc circuit will severely degrade the amplifier performance. TR switching is provided by relay K1. The PTT line can be operated manually (pulled to ground) or RF activated switching circuitry can be installed to eliminate the need for external keying controls. The value of C12 (3.3 μF) determines the SSB time constant for the RF activated switch.


Amp In
R1
C1
0.01
R2
R3
C14
150
T1
4 : 1
C2
0.01
R4
6.8
Q3
2SC2312C
T2
Feedback
Loop
C16
4700
R8
120
R6
18
R7
18
C13
82
C15
200
C17
4700
R9
120
R5
6.8
Q4
2SC2312C
T2
1 : 4
RF Out
Filter In
Low - Pass Filter
Filter Out
Antenna
C11
0.1
C5
0.01
RFC1
Ferrite
Choke
Power In
R1
R2 = R3
5 W
18
300
2 W
2.7

Xcvr Out
Amp In
Ant
Filter Out
D7
1N4004
U1
LM317
REG
Out
In
Adj
2
3
1
R16
27
D6
FES8JT
C3
0.01
C4
0.01
R10
1.2 k
R11
10 k
C8
0.01
C19
0.001
+12 V
12 - 14 V dc
Chassis Mounted Components
10 A
D8
1N4004
GND
R15
1 k
Q2
2N2222
D2
1N914
D1
1N914
R14
4.7 k
R13
3.3 k
R14
3.3 k
D9
Green
D10
Red
D5
1N4004
K1
+12 V
C6
0.01
C7
0.01
TR Relay
Ext. PTT
C20
0.001
C12
3.3 µF
C10
0.01
Xcvr Out
C9
0.01
R12
3.3 k
D4
1N914
R17
4.7 k
D3
1N914
C18
0.001
Q1
2N2222

Optional - RF activated T/R network
omit if external PTT line is used

Except as indicated, decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); resistances are in ohms; k = 1,000.

T1 Prim 2T, Sec 1T CT on BN - 43 - 303 Core
T2 Prim 1T CT, Sec 2T, on T - 3/4 Core
with 1T Sampling Loop.
Wind with #24 Teflon Wire, T2 (sec) #18 Teflon

Figure 2—The RF amplifier schematic and parts list. (M) denotes Mouser Electronics, 1000 N Main St, Mansfield, TX 76063; tel 800-346-6873; **www.mouser.com**. (RF) denotes RF Parts Co, 435 S Pacific St, San Marcos, CA 92069; tel 800-737-2787; **www.rfparts.com**. (A) denotes Amidon, Inc, 240 Briggs Ave, Costa Mesa, CA 92626; tel 800-898-1883; **www.amidon-inductive.com**. (F) denotes FAR Circuits, 18N640 Field Ct, Dundee, IL 60118; tel 847-836-9148; **www.farcircuits.net**.

RF Amplifier Board
C1-10—0.01 µF capacitor, (M) 140-100Z5-103Z.
C11—0.1 µF capacitor, (M) 80-CK06BX104K.
C12—3.3 µF capacitor, (M) 80-C340C335M5U.
C13—82 pF capacitor, (M) 5982-15-500V82.
C14—150 pF capacitor, (M) 5982-15-500V150.
C15—200 pF capacitor, (M) 5982-15-500V200.
C16, 17—4700 pF capacitor, (M) 140-50P5-472K-TB.
C18-20—0.001 µF capacitor, (M) 140-100Z5-102Z.
D1-D4—1N914 diode, (M) 610-1N914.
D5, D7, D8—1N4004 diode, (M) 583-1N4004.
D6—FES8JT diode, (M) 625-FES8JT.
D9—LED, green, with mount, (M) 512-HLMP4719.
D10—LED, red, with mount, (M) 512-HLMP4700.
K1—Relay, 12 V dc coil, DPDT, (M) 551-MR-12USR.
Q1, Q2—Transistor, switching, 2N2222, (M) 511-2N2222A.
Q3, Q4—Transistor, RF, 2SC2312C, (RF) 2SC2312C.
R1—300 Ω, 1 W, (M) 281-300.
R2, R3—18 Ω, 1 W, (M) 281-18.
R4, R5—6.8 Ω, ¼ W, (M) 30BJ250-6.8.
R6, R7—18 Ω, ¼ W, (M) 30BJ250-18.
R8, R9—120 Ω, ¼ W, (M) 30BY250-120.
R10—1.2 kΩ, ¼ W, (M) 30BJ250-1.2K.
R11—10 kΩ, ¼ W, (M) 30BJ250-10K.
R12-14—3.3 kΩ, ¼ W, (M) 30BJ250-3.3K.
R15—1 kΩ, potentiometer, (M) 531-PTC10H-1K.
R16—27 Ω, 1 W, (M) 281-27.
R17—4.7 kΩ, ¼ W, (M) 30BJ250-4.7K.
RFC1—RF choke, (RF) VK-200-3R.
T1—Transformer core, (A) BN-43-303.
T2—Transformer core, (RF) T-¾ core.
U1—IC, LM317T, (M) 512-LM317T.

Misc
2—TO-220 mounting kit, (M) 534-4724.
2—TO-220 thermal insulator pad, (M) 526-NTETP0006.
PC board, FARA RF amplifier, (F).

Low-Pass Filter Board
(see Figure 3 for component delineation)
2—100 pF capacitor, (M) 5982-15-500V100.
3—180 pF capacitor, (M) 5982-15-500V180.
3—330 pF capacitor, (M) 5982-15-500V330.
2—430 pF capacitor, (M) 5982-15-500V430.
1—560 pF capacitor, (M) 5982-15-500V560.
3—820 pF capacitor, (M) 5982-15-500V820.
3—1500 pF capacitor, (M) 5982-19-500V1500.
1—2700 pF capacitor, (M) 5982-19-500V2700.
12—0.01 µF capacitor, (M) 140-100Z5-102Z.

[continued on next page]

[continuation of Figure 2]

12—Relay, 12 V dc coil, DPDT, (M) 655-T7NS5D1-12.
1—Switch, 1 pole, 6 pos, (M) 10-YXX026.
HF Filter Kit, (A) HFFLT. Contains the cores and wire necessary to build the low-pass filters.
PC board, FARA LP Filter, (F).

Chassis Parts

Chassis box, Bud, (M) 563-AC-402.
Chassis cover, Bud, (M) 563-BPA-1589.
Heat sink, (M) 532-244609B02.
4—4-40 hex-type standoff, (M) 534-2201.
9—4-40 × ¼ pan head screw.
4—4-40 × ½ pan head screw.
6—4-40 flat washer.
9—4-40 lock washer.
2—4-40 nut.
2—8-32 × ¼ pan head screw.
2—8-32 lock washer.
2—BNC socket, chassis mount, (M) 161-9323.
RCA-type socket, female, chassis mount, (M) 161-1005.
Switch, toggle, SPDT, (M) 10TC320.
Jones-type socket, chassis mount, male, 2 pin, polarized, (M) 538-13023.

The low-pass filter assembly utilizes relays to select the proper filter network for the various frequency ranges. Relays were chosen to simplify the RF switching and to minimize cost. The six filters cover the nine amateur bands from 1.8 to 30 MHz; the frequency ranges and circuit constants are as noted on the LPF schematic diagram. The inductor cores and wire to wind the coils are available as a kit of parts from Amidon.[3] The L/C constants are the same as those recommended by WA2EBY for the MOSFET RF amplifier in *The ARRL Handbook*.[4] The filters are not used when the amplifier is off or when the PTT line is not activated—this permits multi-band listening and limited VHF use when a wide frequency transceiver is in use (like the Yaesu FT-817). There is no provision for ALC feedback, so caution must be exercised so as not to overdrive the amplifier.

Construction Hints

Although no step-by-step instructions are provided, a few hints will ease the assembly process. The circuit boards pictured are the prototype assemblies; they are not solder-plated. However, the available circuit boards (from FAR Circuits) are plated but do not have plated through-holes, so through-holes must be pinned and soldered.[5] Detailed drawings of the PC boards, the parts layout, coil-winding data and chassis templates can be found at **www.arrl.org/files/qst-binaries/faraamp.zip**. Saul, K1BI, the FARA Webmaster has also set up a site for the project. It can be found at **www.falara.org/tektalk/tektalkfs.html**. The circuit boards as they appear before wiring can be seen in Figure 5.



Cores T - 50 - X Amidon
L in number of turns (#22)
C in pF
Band (E) Shown Selected.
K3, K4 Energized.

Band	L1/2	C1/3	C2	Core
160 (A)	30	1500	2700	2
80 (B)	22	820	1500	2
40 (C)	16	430	820	2
30 (D)	14	330	560	2
20 - 17 (E)	11	180	330	6
15 - 10 (F)	8	100	180	6

Figure 3—The low pass filter (LPF) schematic.

Circuit Board Preparation

- Given the large ground plane area, the boards must be clean or you will experience difficulty when soldering to the foil. Plated boards are best; they are easier to solder. Some solder flux may improve the solderability of the board, but be sure to use *only* rosin core solder and a *non-corrosive* flux.
- Carefully inspect all soldered connections for cold solder joints. Good soldering technique is crucial to the performance of the amplifier.
- Periodically, the flux should be removed from the board during the construction phase with a suitable chemical cleaner.
- There are a number of holes to be drilled and pinned on each board; these are noted on the parts placements diagrams. Wires should be inserted through the board, bent into the shape of a "Z," formed flat against the board, soldered and cut.
- The four corner holes on each board must be sized as a clearance hole for the 4-40 mounting hardware.
- Components should be mounted flush to the board—fixed capacitors should be mounted as close to the foil as possible.
- The large rectangular blocks on the RF board must be trimmed in order to mount the RF output transistors and the bias diode.



FT - 817, Power Output = 4.6 Watts ± .2 W (with −3 dB Pad)

FARA Amplifier Output Characteristics

Frequency (MHz)	RF Output (W)	2nd Harmonic (dB)	3rd Harmonic (dB)
1.8	23	-44	-43
3.5	33	-55	-63
7.2	33	-60	-50
10.1	28	-62	-45
14.2	31	-60	-50
18.1	31	-60	-52
21.2	30	-50	-47
24.9	25	-60	-53
28.4	21	-60	-56

Figure 4—Amplifier output data, including second and third harmonic response.

RF Amplifier Circuit Board

A view of the completed RF board can be seen in Figure 6. The following suggestions pertain to the amplifier board.

- Wind the secondary winding on T2 and mount it to the circuit board first.
- The emitters of the 2SC2312s (Q3, Q4) are intended to be grounded through a hole on the pad. The following modification is advised—bend a thin brass or copper strap into a "U" shape and solder it on both sides of the board. This lowers the impedance to ground.
- Next, mount the smaller fixed components, the resistors and capacitors.
- The semiconductors and the relay mount last.
- Do not mount D6, Q3 and Q4 until the assembly is fixed in the chassis and positioned relative to the heat sink.

Low-Pass Filter Circuit Board

This is a double-sided board; the reverse side is a ground plane with clearance etches for the various components. The LPF board can be seen in Figure 7. It may be necessary to form the capacitor leads slightly to conform to the hole spacing.

- Mount the filter components first, followed by the bypass capacitors and the jumper wires. Refer to the schematic for component values by frequency range.
- The relays mount last. Do not overheat their mounting pins when soldering.
- Do not mount the LPF assembly until the initial tune-up is completed. It is recommended that you pre-wire the band switch. It mounts between the two circuit boards when they are installed in the chas-



Figure 5—The circuit boards before wiring. The RF board is on the left and the LPF board is to the right. Note the pinned and soldered holes.



Figure 6—The completed RF assembly board.



Figure 7—The completed LPF board. Note the relays that are used as filter switches–they are selected by the band switch.

sis and it is difficult to get to.

Chassis, Panel and Heat Sink

Full size templates for the chassis and panel can be found on the Web site. Trim the templates to size and fold and tape them to the aluminum box and heat sink. It is important to center punch the holes and drill a small pilot hole at each location. Enlarge the holes to size according to the dimensions. Letter the panel with dry transfer lettering available at office supply stores. Spray on several light coats of clear lacquer to protect the lettering. Mount the heat sink and the panel components, but do not mount the bandswitch at this time. Mount the RF amplifier board using a couple of 4-40 flat washers as spacers between the chassis and the circuit board at each corner. Install the 4-40 standoffs to hold the assembly in place. Mount D6, Q3 and Q4, using the TO-220 thermal pads and hardware to isolate the transistor mounting tab from the chassis. It is not necessary to isolate D6. Use RG-174 miniature coaxial cable for the internal RF connections.

Tune-up and Testing

As this is a broadband design there is no tune-up; only the bias adjustment needs to be set. A 12 to 14 V dc current limited variable supply is recommended for initial adjustment and testing. Use a dummy load at the amplifier output. Drive levels refer to the attenuator output, if used.

- Connect a temporary jumper between the F_{in} and F_{out} pads on the RF board.
- Preset R15 (1 kΩ potentiometer) so that the wiper is at ground.
- Apply 12 V dc and ground the PTT line (the relay should pull in).
- Briefly drive the input with 1 W at 14 MHz and note the power output.
- Again apply 1 W and increase bias (R15) until the output increases about 15%.
- Increase drive to 2 W and note the power output (about 25 W).
- Increase voltage to 14.7 V dc; note the output with 2 W of drive (about 35 W).

Remove power; remove the temporary jumper; mount the band switch; connect and install the LPF board. Verify that the power output over the range of 1.8 to 29 MHz is as expected. A view inside the bottom of the amplifier, with the LPF board visible, is shown in Figure 8.

Final Comments

The FCC has placed strict limitations on power amplifiers used below 30 MHz. Please review the appropriate FCC regulations before constructing this amplifier.[6] Kits offered for sale, even partial amplifier kits that require additional parts, are prohibited by current FCC regulations.[7]



Figure 8—A bottom view inside the completed amplifier. The LPF board is mounted below the RF assembly.

Construction time, assuming that all the components are on hand and the boards are properly prepared, is about 4 hours. SSB operation results in the heat sink barely getting warm, and cooling under key-down conditions is more than adequate.

A project of this scope is more fun when others participate. Harry, W2RKB, provided the necessary prodding to get it started. He also fabricated the circuit boards and the filter assemblies for the prototype amplifiers. Dave Hosom assisted with the photographs. A generous thank you is extended to them both. Give the FARA amplifier a try... it's a practical and rewarding project!

Notes

[1] Federal Communications Commission, Sec 97.315.

[2] See Note 1.

[3] Amidon Associates, Inc, 240 Briggs Ave, Costa Mesa, CA 92626; 800-898-1883; **www.amidon-inductive.com**.

[4] *The 2003 ARRL Handbook*, pp 17.91-17.97.

[5] FAR Circuits, 18N640 Field Court, Dundee, IL 60118; tel 847-836-9148; **www.farcircuits.net**.

[6] Federal Communications Commission, Sec 97.3 (19).

[7] See Note 6.

By Pat Bunn, N4LTA — From *QST*, October 1990

A Compact "Brick" for 6 Meters

Does your six-meter signal need some extra kick? This inexpensive amplifier bridges the gap from 10 to 100 watts.

Most transceivers available for the 6-meter band provide 10 W output. This power level provides satisfactory communications during good sporadic-E openings, but is not adequate for making long-haul contacts on meteor scatter or during F-layer openings. For the average station, an output level of 100 W seems to be a reasonable compromise between a 10-W exciter and a kilowatt amplifier. Unfortunately, 50-MHz amplifiers in this power class are not readily available.

I began operating on the 6-meter band a few years ago, near the lowest point in sunspot cycle 21. Sporadic E kept my interest high, and soon it became evident that I needed an amplifier. Being a builder at heart, I decided to "roll my own" and began to search the Amateur Radio literature for design examples. I found very few solid-state amplifiers, and only one in the 100-W class.[1]

I built the amplifier as specified, and I got good results. My 6-meter effectiveness made a quantum leap! One highlight was working Europe with a 12-foot-boom Yagi. The amplifier performed so well that several of my friends asked me to build them duplicates of it. With each revision, I tried to add design innovations, including on-board TR relays, a carrier-operated-relay (COR) circuit and transistor biasing, as well as low-pass filtering and more compact packaging. The product of these efforts is described in this article. At least 25 of these units have been constructed and are now in use. Several of these amplifiers have been used on DXpeditions, in beacon service, and as drivers for kilowatt-class amplifiers, and results have been excellent.

If you are looking for a low-cost 100-W amplifier, this proven design would make a nice addition to your 6-meter station. This circuit can also be adapted for use with an MRF140 FET, which produces over 160 W output with less than 10 W drive. See the sidebar for more details.

6 METER AMPLIFIER
DELAY
POWER

Circuit Highlights

The amplifier circuit, shown in Fig 1, is a single-stage, 10-dB-gain, class-B design using the popular Motorola MRF492 transistor. The RF circuitry is based on a test circuit in Motorola's RF Device Data book.[2] Input and output impedance matching is done with low-Q lumped circuits rather than with broadband transformers. The amplifier's bandwidth is about 1.5 MHz, which covers the DX portion of the 6-meter band with plenty to spare. And, the output network has a secondary dip at about 53 MHz, allowing CW/SSB work and FM operation without the need to retune the amplifier. The narrowband nature of the matching networks helps reduce harmonics. A half-wave low-pass filter in the output circuit further reduces harmonic content to meet current FCC specifications (see Fig 2).

The COR circuit is based on a high-gain operational amplifier that provides the sensitivity required for SSB operation. This circuit is much more effective than the Darlington-transistor COR circuits found in most commercial amplifiers. It works well with low-power SSB rigs that do not have easily accessible PTT lines, although a separate PTT input is also included.

The amplifier PC board[3] is mounted in a die-cast aluminum box (Hammond 1590R, Bud CU-247 or Jameco® part no. B5006) with an extruded-aluminum heat sink bolted to the bottom. (I used a 6-inch length of Wakefield no. 1527 heat sink. Any aluminum heat sink with similar dimensions should work fine.) The completed amplifier is operated inverted, with the removable lid serving as the bottom. The enclosure is painted flat black and labeled with white rub-on lettering. Stick-on rubber feet are attached at the corners of the bottom cover. The finished product


J1
INPUT
K1
J2
OUTPUT
K2
J3
PTT
FB1
C2
+13.8 V
D1
C1
DS1
POWER
S1B
C4
C3
S1A
OFF
ON
R9
FB3
C19
R1
D2
C6
C7
C9
C10
C8
Half-Wave Filter
RFC1
C5
L4
L5
C20
L2
L1
L3
FB2
Q1
C13
C21
C12
C11
C22
C14
INPUT
TUNE
R2
OUTPUT
TUNE
+13.8 V
C16
C18
R8
D4
3
8
U1
1
R7
Q2
D3
C15
R3
2
4
C17
DS2
PTT
R6
S2
IN
DELAY
R4
R5
GAIN
IC pins not shown are unused.

Fig 1—Schematic of the 100-W 6-meter amplifier. Liberal use of bypass capacitors and ferrite beads helps ensure stability and keeps RF out of the power supply.

C1—10 pF, ceramic disc.
C2—0.01 µF, polyester film.
C3, C10—0.001 µF, ceramic disc.
C4, C6, C8, C9, C15-C19—0.1 µF, polyester film.
C5—9- to 180-pF mica compression trimmer, Arco no. 463.
C7—1000 µF, 6.3 V, aluminum electrolytic.
Cli —120 pF, 100 V, silver mica.
C12, C22—62 pF, 100 V, silver mica.
C13, C14, C20—50- to 380-pF mica compression trimmer, Arco no. 465.
C21—25- to 280-pF mica compression trimmer, Arco no. 464.
D1—1N4002.
D2—1N1200 stud-mount diode.
D3, D4—1N4148.
DS1—Green LED.
DS2—Red LED.
FB1, FB3—Ferrite bead, Amidon no. FB43-901 or similar.
FB2—VK-200 wide-band choke, 2½ turns no. 24 solid wire on Amidon no. FB43-5111 ferrite core.
J1, J2—Female RF connector (UHF, BNC, N, etc).
J3—Phono jack.
K1, K2—SPDT relay, 12-V dc coil, Omron no. G5L112P-PS-DC1 2. Available from Digi-Key.
L1, L2—4 turns no. 14 enam wire, 7/16 in. diam, 3/8 in. long.
L3—2 turns no. 14 enam wire, 3/8 in. diam, 1/2 in. long.
L4—no. 14 U-shaped wire loop, 3/8 in. diam, 9/16 in. finished length.
Q1—MRF492.
Q2—2N2222A.
R1—5-W bias resistor (see text).
R2—10 Ω, 1/2 W, carbon comp.
R3, R5—10 kΩ, 1/4 W, carbon comp.
R4—1 MΩ, 1/4 W, carbon comp.
R6—100-kΩ PC-board potentiometer.
R7-R9—1 kΩ, 1/4 W, carbon comp.
S1—DPDT miniature toggle.
S2—SPST miniature toggle.
U1—LM358.

Miscellaneous
Suitable die-cast-aluminum enclosure and heat sink.
Pair of binding posts or other suitable dc-supply connector.
Two 1- x 3-in, strips of double-sided foam tape.
Two LED holders.
Seven no. 4-40 × 1/4 in. machine screws.

looks professional, and also does a good job of cooling the power transistor and bias diode.

Construction

The amplifier is assembled on a double-sided printed circuit board. All RF components are surface-mounted on the component side of the PC board (see Fig 3). The COR components, including the relays, connect to traces on the other side of the board. The remaining non-component-side foil serves as a ground plane, and is electrically connected to the component-side ground plane via platedthrough holes. If you make your own PC board, you can replace these plated-through holes with no. 18 AWG wires soldered to both sides of the board, or, preferably, copper rivets such as those available from Frontier Microwave and Down East Microwave.[4] The relays also mount in plated-through holes. The PC-board patterns and part-placement overlay are available from the ARRL Technical Department Secretary.[5]

Drill the case for the switches, connectors and indicators you'll use. Begin PC-



Fig 2—Worst-case spectral display of the 100-W 6-meter amplifier. Vertical divisions are each 10 dB; horizontal divisions are each 10 MHz. Output power was approximately 100 W at 50.2 MHz. All harmonics and spurious emissions are at least 60 dB below peak fundamental output when the amplifier is tuned as described in the text. The 100-W amplifier complies with current FCC specifications for spectral purity for equipment in this power-output class and frequency range. Better spectral purity can be obtained by using an external output filter (see the referent of note 1 for a suitable filter circuit).

board construction by mounting the parts that are soldered to traces on the other side of the board. This includes the COR parts and relays, the RG-174 jumper, and diode D1. Make sure that the diodes and Q2 are properly oriented.

The solder-side parts are surface-mounted. Keep lead lengths to a minimum (no more than 1/4 inch) on these parts. The bypass capacitors should have the shortest possible leads, and should be surface-mounted on the PC board.

Wind the coils using 1/4- and 3/8-inch drill bits as temporary forms. Cut the coil leads to 1/4 inch, bend them 90°, scrape the insulation off the ends and solder the coils to the board. Some of the coils may need to be compressed or spread during tune-up to get maximum output power, so allow for this when mounting them. Use Fig 3 as a guide. Mount the mica trimmers by bending the solder tabs parallel to the board and surface-mounting them. (Some trimmers have extra tabs that may short to the PC board; I cut these off with side cutters to eliminate this risk.) When surface-mounting the larger components, a high-wattage soldering gun is useful, but be careful: The traces may separate from the PC board if excessive heat is used.

When the PC board is complete, temporarily place the MRF492 in its mounting hole in the PC board, making sure to orient the transistor properly (the beveled lead is the collector). Place the PC board inside the box assembly. Carefully mark the transistor-mounting holes and the single PC-board mounting hole on the enclosure, through the PC board. Remove the PC board from the case, then drill and tap these holes for no. 4-40 hardware. Mark and drill the heat sink using the enclosure as a guide.

Drill and tap four more no. 4-40 holes, near the corners of the case, through the case and into the heat sink. Apply heat-sink compound between the die-cast box and the heat sink, then use no. 4-40 screws in these holes to secure the heat sink to the case.



Fig 3—This inside view of the 100-W amplifier shows the circuit's simplicity. On the PC board, counterclockwise from upper left: the COR circuit; input-matching and bias networks, switches and indicators (lower left); MRF492 (lower center); collector choke and output network (lower right). The TA relays and connectors are at the upper center, and bias resistor R1 is just to the left of center.

Place the PC board into the case/heat-sink assembly again, and mark the location of the stud-mounted bias diode. Remove the board and drill and tap a 3/8-inch-deep no. 10-32 hole in the case/heat-sink assembly. The diode's threaded stud is more than 3/8 inch long, and should be carefully cut off (with a hacksaw) to 5/16 inch.

The rear of the PC board must be insulated from the box assembly, because many of the COR-circuit traces on the underside of the board are not at ground potential. I use 1/8-inch-thick double-sided foam tape to cover the solder-side traces and to support the board away from the case. Make sure the component leads are cut off closely at the rear of the PC board so that they don't punch through the foam tape and short to the box assembly. Mount the board inside the case, then screw the bias diode snugly into its mounting hole in the case/heat sink assembly.

Solder the MRF492 onto the board as the last step, *after* the transistor case has been mounted in the board and screwed into place. (This eliminates the possibility of cracking and ruining the $15 device!) Be sure to use a liberal amount of silicone heat-sink compound between the transistor and the box.

Mount the front-panel LEDs, switches and the RF connectors of your choice to the box. Any suitable RF connectors can be used. The connectors are wired to the PC board with no. 18 tinned bus-wire jumpers. Make these as short as possible. I used no. 24 insulated hookup wire to connect the switches and LEDs to the PC board. Finally, mount the dc-power binding posts to the rear panel. These are wired to the PC board with no. 18 bus wire run through FT-43-801 ferrite beads.

Initial Testing

After the switches, LEDs and connectors have been wired, carefully check all connections. Make certain that the jumper from the PC board to bias diode D2 is connected! If all looks good, connect the amplifier to a 13.8-V power supply capable of sourcing 1 A. (If you have one, a small, current-limited power supply is best for testing.) If your power supply does not have reliable current metering, a meter capable of measuring 0-500 mA should be placed in series with the positive supply lead.

With the amplifier turned off, turn on the power supply. The meter should indicate 0. Turn on the amplifier and note the total indicated current. It should be between 50 and 300 mA. If it is much greater than 300 mA, quickly turn off the power supply and look for problems.

If the current is within these limits, you can go about setting the operating bias. This involves changing the value of R1 until the collector current is between 75 and 175 mA. Note that this is not total circuit current, which includes the diode

Using a MOSFET to Get More Power from the Basic MRF492 Amplifier Circuit

The MRF492 amplifier circuit described in the main text is easily modified for use with an MRF140 VMOS power FET, which has about 15 dB gain and over 160 W output—substantially more than the MRF492. Even the device cases are the same, so the changes required to operate this circuit with an MRF140 are quite straightforward. Specific details of the modifications required, including a schematic diagram, are available from the author for an SASE.

The main differences between the devices are that the MRF140, a MOSFET, needs different biasing and a higher supply potential (28 V) than the MRF492, and is more expensive ($88 versus $15 for the MRF492, at this writing). But if you have a 28-V supply and need more than 100 W or have a 5-W exciter, the change is probably worthwhile. The MRF140 is easily biased with a three-terminal regulator (an LM317T works well), and requires very few component changes other than those in the bias circuit. An additional capacitor and inductor are also required at the MRF140's gate.

Because the modified amplifier requires a 24- to 28-V supply, different TR relays must be used, or, alternatively, 12-V-coil relays can be wired in series. (The COR circuit needs no modification because the LM358 works fine at 28 V.)

Good heat sinking is more critical to amplifier performance at the higher power level, so I used a 3- × 5- inch slab of 1/8-inch-thick copper between the device and the case as a heat spreader. A larger heat sink and/or forced-air cooling are also desirable.—*N4LTA*

current and POWER LED current. The best way to measure collector current is to lift FB3 and insert a milliammeter in series with the collector-supply lead at that location. An alternative method is to use the following equation to approximate collector current:

$$I_C = I_{TOTAL} - [(V_{R1} \div R1) + ([V_{CC} - 1] \div 1000)]$$

where

I_C = collector current in milliamperes
V_{R1}= measured voltage across R1
V_{CC} = measured supply voltage

This equation lets you calculate collector current by subtracting the current through R1 ($V_{R1} \div R_1$) and the current through the **POWER** LED ($[V_{CC} — 1] \div 1000$) from the total supply current.

Using either method, substitute different resistors at R1 until the collector current falls into the 75- to 175-mA range. In almost every case, a 5-W resistor of 82, 91, 100, 110, 120 or 130 Ω will bring the current into that region. (I have never had to substitute more than three resistors to arrive in this bias-current range.) These 5-W resistors can be purchased for less than $0.40 each, so, although a 200-Ω, 5-W wire-wound potentiometer could be used for R1, all six resistors can be purchased for far less. And, these days, high-wattage potentiometers are hard to find.

Tune-Up

When the bias current has been set, the amplifier can be initially tuned. For this procedure, the amplifier should be connected to a power supply capable of delivering at least 15 A at 13.8 V. A power meter capable of indicating at least 100 W at 50 MHz should be connected at the amplifier output, and the meter's output to a 50-Ω load. It is also desirable to measure input power from the exciter, as well as amplifier-input SWR, but these can be measured after initial tune-up if two meters aren't available.

Set the input-circuit trimmers (C5 and C14) near midrange. Because the output circuit can be tuned several ways for the proper impedance transformation, it's important to preliminarily adjust the output circuit by compressing C13 all the way, then backing off one full turn, before beginning tune-up. Do the same for C21, then back C20 out almost all the way. Turn on the amplifier and apply about 2 W drive. The COR should sense the input RF and switch immediately into transmit. Using a nonmetallic tool, tune the two input-circuit trimmers for maximum power output, then tune the three output trimmers (C13, C20 and C21) for peak output. These adjustments interact, so continue tweaking for maximum power.

During tuning, pay attention to the temperatures of these variable capacitors. If heating is noticeable (especially in C13), reset these capacitors and start again. Limit key-down periods to 10 seconds, and allow for cooling in between. Increase drive to about 9 W. Output should be 95 to 105 W, and the output-tuning capacitors should be cool to the touch just after RF drive is removed.

Input SWR should be less than 1.2:1. If not, adjust the input-circuit trimmers for the best compromise between low input SWR and maximum power output. The amplifier is now ready for operation. Some MRF492s seem to be "hotter" (exhibit more gain) than others; I have seen some devices produce 115 W easily and others strain to put out 95 W. On the air, the difference is so slight that it can't be detected. For best IMD performance, I recommend running the amplifier at about 85 W output on SSB.

FM Operation

This amplifier also works well on FM, but the power output should be limited to about 75 W because of FM's more demanding duty cycle. As mentioned earlier, the amplifier's bandwidth characteristic is double-humped; if it's tuned up at 50.1 MHz, the second hump falls in the 53-MHz area, allowing for SSB and FM operation without retuning.

If the amplifier is to be used for beacon, CW or FM operation exclusively, I suggest you configure it for class-C operation. Efficiency in class-C operation is in the 72% range, versus 60% for class B. To configure the amplifier for class-C use, connect the inductor using FB2 (the multi-hole ferrite bead) from Q1's base to ground, and eliminate all of the other bias components, including D2. If you like, you can add a panel switch to change between class-C and class-B operation.

The amplifier should never be operated class C on SSB. Doing so results in severe distortion.

Conclusion

I hope that you enjoy building this project, and will be motivated to try 50-MHz operation. As I write this, Japanese stations are being worked on the East Coast, and all continents are frequently heard. In the years to come, the regular occurrences of sporadic-E openings and meteor scatter will help fill the nulls between F-layer openings. Hurry and get in on the excitement on the "Magic Band"!

Notes

[1] T. Tammaru, "A Solid-State 6-Meter Linear Amplifier You Can Build," *QST*, May 1982, pp 11-14. This circuit was based on an MRF492 test circuit in Motorola's *RF Device Data* book.

[2] *Motorola RF Device Data*, Fourth edition (Motorola Inc: 1986), pp 3-552 through 3-555.

[3] A set of PC-board parts, including a high-quality PC board with plated-through holes, is available from the author for $100 (UPS delivery included). Switches, LEDs, enclosure, terminals, heat sink and connectors are not included. The PC board alone is available for $17 postpaid, and a black anodized-aluminum heat sink is available separately for $12 postpaid. (The ARRL and *QST* in no way warrant this offer.)

[4] Frontier Microwave, AD 1, Box 467, Ottsville, PA 18942, evening tel 215-795-2648; Down East Microwave, RR 1, Box 2310, Troy, ME 04987, tel 207-948-3741.

[5] Send a business-size SAE with return postage for 1 ounce with your request. Specify the information package for the 6-meter linear amplifier from October 1990 *QST*. This package includes full-size etching patterns for the front and rear sides of the amplifier PC board and a part-placement overlay.

By Richard Frey, K4XU **From *QEX*, May 1999**

A 300-W MOSFET Linear Amplifier for 50 MHz

Everyone is looking to go QRO on 6 meters. Build this “almost a brick” to boost your signals from 15 to 300 W.

In an earlier article, I described a 50 MHz, 125 V, 250 W, class-C amplifier using ARF448AJB highvoltage MOSFET devices.[1] This paper describes an improved version of an amplifier that is capable of class-AB linear operation. The design changes required and the procedures involved are explained and demonstrated. Complete descriptions of the amplifier and its construction are presented, as well as the measured performance.

High-voltage, high-power MOSFETs have been shown to be very capable RF power amplifiers.[2] The metal-gate architecture of the ARF series from Advanced Power Technology has raised the frequency limits for this type of device to 100 MHz. The APT448A/B is typical of the series. It has a 68,000square-mil die with a breakdown voltage rating, BV_{dss} of 450 V. The device is provided in the inexpensive TO-247 plastic package, and is available in common-source symmetric pairs. Like all MOSFETs, the gate threshold voltage, V_{th}, has a negative temperature coefficient. This makes operation as a linear amplifier difficult or impossible without compensation.

When forward biased with a constant gate voltage, the quiescent drain current rises as the temperature of the die increases. Operating at the typical drain voltage for these parts, about one third of the rated BV_{dss}, the power dissipation caused by the increasing ‘dq results in “hot spotting” and subsequent thermal runaway. This is an unstable system. The dissipation increases so rapidly that the outside surface of the case does not follow internal junction temperature well. As a result, a bias-compensation scheme that uses temperature sensing cannot keep up with the V_{th} shift, and the device is destroyed.

The power dissipation within the die is a direct function of the operating voltage. By lowering the operating voltage, the thermal loop gain can be reduced to a point where the gatethreshold shift can be compensated. Thermal stability can be achieved by sensing the case temperature. Linear operation thus becomes practical at 100 V and below. While this is less than 25% of the rated BV_{dss} and produces less gain, a very rugged and useful linear amplifier is the result.

Amplifier Description

The following were the design goals for the amplifier:

- Frequency range 50 to 51 MHz
- Input SWR < 1.5:1
- Gain> 13dB
- Output power 300 W PEP or CW
- Efficiency> 50%
- IMD3 > 25 dB below PEP

A push-pull topology was chosen for best output power and minimum harmonic content. The previously reported class-C design used $V_d = 125$ V. Since this is too high for reliable class-AB operation, 80 V was eventually chosen for this design. This is a compromise between gain, efficiency and thermal stability.

Since the gate input impedance is very low, it magnifies the effects of any stray inductance in the gate matching circuit. In a push-pull design, it is critical to maintain absolute symmetry between the two sides. This fact was demonstrated during the initial design work. One preliminary design had a slight asymmetry in the PCB artwork. The amplifier exhibited low efficiency, hot ferrite in the output transformer balun and poor distortion characteristics with asymmetrical IMD product amplitudes. This clearly demonstrates the benefit of symmetrically packaged devices.

A multiple-aperture ferrite bead was chosen for the input transformer. Brass tubing was used for the secondary, and the primary was wound inside the brass tubes to provide a very broadband balanced transformer design with minimum leakage reactance. Several cores and construction methods were evaluated, and this well-tried design proved best.

The typical HF push-pull amplifier employs a bifilar choke to decouple the drain-voltage feed. As frequency and power increase, this feed method becomes less practical because the need to reduce the number of windings to offset the stray capacity and the need to prevent core saturation conflict. In this design, a powdered-iron toroid was chosen for the feed choke core. This proved far superior to any of the ferrite cores evaluated. It is inexpensive and easy to reproduce.

Design

Three main areas must be addressed. The input matching must provide a balanced feed to a pair of low-impedance gates. The output must be matched to a suitable load impedance, and then transformed to a 50-Ω unbalanced load. The bias must be thermally compensated to track the negative temperature coefficient of the gate bias threshold.

The input is reasonably straightforward. Each gate input is 0.2 +*j*0.5, as estimated from the data sheet. The push-pull topology puts these two impedances in series, which makes the matching less difficult. A Smith Chart[3] program makes the actual design easy. The program used here is *WinSmith*.[4] The two gate impedances are added in series, and a network synthesized to transform the resulting impedance up to 50 Ω. The Smith Chart program only works with single-ended circuits, so the center tap was added later. See Fig 1.

The input-transformer design was chosen for its simplicity and relative ease of construction. Of several attempts using different material permeabilities, multiple beads and different conductor types, this proved to be the best and most consistent performer. The core is a Fair-Rite[5] “multi-


T1
2:1
L1
18 nH
TL1
L2
18 nH
C3
920 pF
C1
412 pF
C2
1000 pF
R1
1 k
TL1:
Zo (ohm): 30
Length (deg): 1.5
Freq (MHz): 50
Atten (db): 0.010000
Sweep Range:
Lower Freq: 50
Upper Freq: 51
Sample Points: 3
Terminations:
Reference (ohms): 50
Load R (ohms): 0.42
Load X (ohms): 0

Fig 1—Input matching network and calculation.


L1
143 nH
C1
76 pF
C2
75 pF
(Coss)
Load
Sweep Range:
Lower Freq: 50
Upper Freq: 51
Sample Points: 3
Terminations:
Reference (ohms): 50
Load R (ohms): 30.7
Load X (ohms): 0

Fig 2—Output matching network and calculation.

aperture" core, part number 2843010402. The type-43 material has a μ_i of 850. At 50 MHz, type-61 material (μ_i of 125) would also be satisfactory. This transformer is essential to provide balanced drive to the gates of the MOSFETs. The secondary winding is 3/16-inch brass tubing. Copper shim stock forms the connections to the brass tubing at each end of the transformer secondary. The two-turn primary is wound inside the tubing. This construction provides a very reproducible transformer with minimum leakage reactance and a very broad frequency response. It would be a suitable input transformer for a broadband amplifier covering 1 to 100 MHz.

The leakage reactance of the input transformer—referred to the secondary—is about 18 nH and is represented as Li on the simplified input schematic in Fig 1. The gate load is represented by the "Load R," L2 and C3. Using all three parts of the gate impedance allows proper evaluation of the network bandwidth. A pi network consisting of C1, TL1 and C2 is used to step-up the gate load to the 12.5 Ω needed by the transformer and compensates for T1's leakage reactance. Notice that the net stray inductance of the gate is almost enough to effect a match with a single shunt capacitor. This has actually been done, but it was not easy to fit all the parts in the available space; so it was judged unacceptable here. To transform the network into the required balanced configuration, the series TL1 is split into two equal parts; the shunt capacitors remain the same, and a neutral center tap is provided at the transformer secondary.

Because of the high currents circulating in the input network, it is imperative that C2 be a larger-sized, class-1 dielectric (C0G or NP0) capacitor. It must be a leadless, surfacemount chip type, or the value will need to be adjusted. The input tuning capacitor, a 900 pF mica compression trimmer, is mounted directly to the end of the input transformer.

The output network is also straightforward. The proper load impedance for class


R1
6.8 k
R5
2.2 k
R6
1 k
BIAS
C10
1 μF
35 V
D1
6.8 V
1 W
R47
4.7 k
2 W
C8
0.01
+
85 V
−
C7
1 n
L3
T
R3
10 k
R2
1 k
J1
Input
T1
TL1
C1
C2
1 n
TL2
Q1
Q2
L1
L2
C3
T2
C5
0.01
C6
1 n
C4
0.01
T3
J2
Output
R4
10 k
C9
0.01
Except as indicated, decimal values of capacitance are in microfarads (μF); others are in picofarads (pF); resistances are in ohms;
k=1,000.
n= nanofarad (10−9)

Fig 3—50 MHz amplifier schematic diagram.



Fig 4—Amplifier parts layout.

AB is calculated from the formula:

$$R_L = \frac{0.98\,V^2_{dd}}{2\,P_o} \qquad \text{(Eq 1)}$$

This is the load for each device, and P_O is one half of the total in a push-pull circuit. It is shunted by the output capacitance, C_{oss}. As was done for the gate circuit, both output impedances are series-connected to represent the total output impedance. The result for both devices in push-pull is 30.7 Ω in parallel with 75 pF, half the output capacitance of a single device. Though the design goal was 300 W PEP, the amplifier was actually designed for a 400 W load line. This gives a good compromise between efficiency and linearity.

In a classical design, a suitable transformer would be used to set the load impedance, and either the output power or the operating voltage would be adjusted to fit the available turns ratio. Normally, in a low-voltage HF design, the output capacitance is ignored because it is shunted by a much smaller load resistance. At 50 MHz, the effects of the output capacitance must be compensated, so a slightly different approach was taken in this circuit.

WinSMITH was used again to design the output matching. See Fig 2. The output impedance of 30 Ω is rotated south by the effect of the shunt output capacitance, C2. Two options present themselves for compensation. Some additional shunt capacitance could be added to further reduce the equivalent series real part to 12.5 Ω, a series L used to resonate the resulting series C, then a 4:1 transformer used to go to 50 Ω. However, building a reproducible low-loss 4:1 balanced transformer was very difficult, and compensating its leakage reactance further complicates the design. The second option was used: The equivalent series output capacitance was resonated first, then more series inductance was added to rotate the load all the way up to the $^1/_{50}$-mho conductance circle. Finally, a shunt capacitor was used to resonate the added X_L. The extra L and shunt C form an L-network, which transforms the 20-Ω equivalent series output impedance up to 50 Ω. This results in an easily duplicated design with a smooth, low-Q match.



Fig 5—PCB artwork (not to scale, original size 3.35 (7.00 inches).

The dc feed to the drains is provided through a shunt bifilar choke. At this frequency, most ferrite materials exhibit too much loss to be used at this impedance level. A powdered-iron core works famously here.

The balun-transformer function is provided by a simple coax and wire transformer. Two of the windings are provided by 50-Ω Teflon coax, and the third balancing winding by an additional single wire.

The bias network requires some explanation. Power MOSFETs have normal lot-to-lot variations in gate threshold voltage, V_{th}, forward transconductance, G_{fs}, and other parameters. A number of devices were checked for V_{th}, and they were all very close. They were all from the same die lot. The die lot number is marked on the package. For comparison, devices from another lot were checked and were uniformly a half a volt lower. Were this the case for the devices to be used in the amplifier, a dc block would need to be added to each side at the transformer, and the bias-feed network duplicated for each device. Since these devices were uniform, the additional complication of individual gate-bias adjustments was omitted in this design.

Because the gate-bias voltage required to maintain a particular value of idling drain current decreases as the temperature of the die increases, it is necessary to thermally compensate the gate-bias source, or the devices will "run away." A commonly available NTC resistor tracks the temperature of the case. (Refer to Fig 3.) This bias circuit has been in the literature for many years.[6] The ratio of R1 to R3 in part determines the degree of compensation. A smaller value of R1, or a larger value of R5, will increase the thermal sensitivity. A drop of thermally conductive glue keeps the thermistor in contact with the case. Proper operation is indicated when the set value of I_{dq} does not change after the heat sink gets hot from prolonged operation.

Construction

Refer to Fig 4 for the parts layout. A photo master of the artwork is shown in Fig 5. The original size of the artwork is 3.35x7 inches. The circuit board is 1-ounce-copper, double-sided $^1/_{16}$-inch G-10 PCB material. All four edges of the board and the three sides of the two rectangular cutouts for the transistors are wrapped with copper-foil tape that was soldered in place to



Fig 6—SSB IMD performance.



Fig 7—Amplifier efficiency and gain.

Table 1—Amplifier Parts List

C10—1µF, 35 V electrolytic capacitor
C1—215-790 pF Arco[8] #469 mica compression trimmer
C2, C6, C7—1000 pF, 500 V NPO chip cap, KD9 #2020N102J501P
C3—20-180 pF Arco #463 mica compression trimmer
C4-C5, C8-C9—0.01 µF, 500 V chip capacitor
D1—6.8 V, 1 W Zener diode
L1-L2—≈70 nH, 3t #18 AWG enameled wire 0.31-inch diameter 0.25-inch long
L3—2t #20 AWG on Fair-Rite #284301 0402 bead $\mu_i = 850$
Q1 —ARF448A
Q2—ARF448B
R3—10 kΩ NTC Fenwal[10] #140-103LAG-RB1
R6—1 kΩ, 0.5W 10-turn trimmer
T1—Primary 2t #20 PTFE, Secondary 3/16-inch brass tube on Fair-Rite #2843010402 balun core
T2—6t bifilar #20 PTFE on Amidon #T-94-2 toroid $\mu_i = 10$
T3—3t RG-316 coax, 3t #20 PTFE on three Fair-Rite #5961001801 toroids $\mu_i = 125$
TL1, TL2—30-Ω printed line, 0.6 inches long

provide a low-impedance continuous ground plane. The two cutouts for the transistors and the six mounting holes are the only holes in the board. All of the parts are surface mounted, which permits the board to be mounted directly to the heat sink.

This amplifier was built on a 7-inch length of AAVID #60765 heat-sink extrusion.[7] It is 3.5 inches wide, 1.5 inches deep and has nine fins. With 50 CFM of air blown across it, the devices will easily maintain thermal stability in a 30°C environment. The heat sink is not big enough for anything but very intermittent use without a fan to assure adequate airflow across the fins. The input and output connectors are each secured by two #4-40 screws and holes tapped into the base of the heat sink. A cover is recommended for safety; fairly high RF voltages are present.

Power Supply

Power for the amplifier needs to be fairly well regulated, since any ripple will show in the output signal as undesired 120-Hz AM. For on-air testing at the author's home, a very simple power supply was constructed using a 500 W, 120 to 240 V isolation transformer to drive a full-wave, centertapped rectifier circuit with 50,000 µF of filtering. Under SSB conditions, this is adequate. For CW, it needs some better regulation or the output power will sag over the length of a dash, and there will be some detectable hum. A regulated supply capable of providing 80 V at 6 A is needed.

Performance

This is the first-known, class-AB application of the ARF448 parts. Until now, the only other linear application is in a pulsed-mode linear amplifier for magnetic-resonance imaging. The SSB performance was encouraging because these devices were developed to serve the ISM plasma-generation market and no attention to linear performance was given in their design. The IMD performance with 200 mA of quiescent bias was better than expected. (See Fig 6.) The amplifier was tested with up to 0.5 A of I_{dq}. While the IMD performance improves somewhat at this level, the efficiency degrades significantly.

The gain and efficiency objectives have been met, as shown in Fig 7. The gain is 14.3 dB at 300 W PEP. The efficiency peaks at 51% at the same power. Under single-tone conditions, the drain efficiency is 61% at 250 W. The bandwidth of the amplifier is determined by the input network. The Smith-Chart plot of the input impedance shows the tracks for 50, 50.5 and 51 MHz. With the network adjusted for best match at 50.5 MHz, the SWR at the ± 0.5 MHz bandwidth points is 1.3:1. It would be difficult to increase this SWR bandwidth enough to cover the full 4 MHz of the amateur 6-m band without resorting to resistive loading, which would then reduce the available gain.

Conclusion

This paper has presented a 50 MHz, 300-W PEP linear amplifier using plastic-packaged, high-voltage MOSFET transistors. This is the first-known implementation of a full-duty-cycleclass-AB amplifier using these transistors. The design challenges, approaches to their solution and the resulting amplifier performance are shown. The parts, construction and mechanical layout all have been described in sufficient detail to permit duplication. The new line of plastic-packaged RF power transistors from APT offers designers a new cost-effective solution for efficient layout and performance.

Notes

[1] R. Frey, *A 50 MHz, 250 W Amplifier Using Push-Pull ARF448A/B*, APT9702, Advanced Power Technology Inc.

[2] R. Frey, "A Push-Pull 300 Watt Amplifier for 81.36 MHz," *Applied Microwaves and Wireless*, April 1998.

[3] Smith Chart is a trademark and property of Analog Instruments Co, New Providence, New Jersey.

[4] *WinSMITH*, copyright Eagleware Corp, 1995, available through Noble Publishing, Inc.

[5] Fair-Rite Products Corp, PO Box J, One Commercial Row, Walikill, NY 12589.

[6] H. Granberg, "Wideband RF Power Amplifier," *RF Design*, February 1988.

[7] AAVID Thermal Technologies Inc, Box 400, Laconia, NH 03247.

[8] Arco Electronics, 5310 Derry Aye, Agoura Hills, CA 91301.

[9] KD Components Inc, 2151 Challenger Way, Carson City, NV 89706.

[10] Fenwal Electronics, Inc, 450 Fortune Blvd, Milford, MA 01757.

By Paul Hewitt, WD7S **From *QEX*, July 2000**

A No-Bandswitch, Dual-Band VHF Desktop Amplifier

An old design idea together with new tubes yields legal-limit output on 6 and 2 meters from a small box.

Dual-band VHF amplifiers are by no means new in Amateur Radio. Several designs have appeared over the years, both commercial and homebrew.[1,2] The most recent commercial design was the Henry Tempo 6N2, now out of production for more than 20 years. There has never been a desktop capable of the new 1500-W PEP amateur power limit for both the 6- and 2-meter bands, until now. The amplifier I describe was designed primarily for meteor-scatter and weak-signal work, but the conservative design of the power supply and cooling system makes it well suited for EME (moonbounce) also. The amplifier uses a pair of Svetlana 3CX800A7s, operating in class AB2-push-pull on 2 meters and AB2-parallel on 6 meters. Features include: legal-limit output, no key-down time limit, no band switching, either-or operation, 50-60 W of drive for 1500 W PEP output on both bands, small size and light weight. In an effort to make this design easier to duplicate, off-the-shelf com-ponents and materials were used wherever possible. If you prefer not to "roll your own," Alpha Power should have a commercial version available soon.

Output Tank Circuit and Construction Details

Since this was a new tank design, I decided to use a box-in-a-box approach for the layout to make adjusting and debugging much easier. This should also make duplication of the tank circuits much easier for those of you who wish to use a separate, outboard power supply. The tank compartment (See Figs 1, 2 and 7) starts with a 7×7×2-inch Bud chassis with two surplus 11-pin ceramic sockets[3] mounted three inches apart (center-to-center) and four inches from the rear of the chassis. The sockets are mounted 1/4 inch below the chassis in 2 1/2-inch-square holes with each socket oriented at 45° to the hole (Fig 3). This is similar to an Eimac 2216 socket for the 8877. The Eimac #1906 chimneys were used in the normal manner. This is probably the upper frequency limit for this mounting scheme due to possible instability problems at UHF. One problem encountered while mounting the sockets this way is the small amount of tube exposed above the chimney to grasp for removal. This is easily solved by connecting several 1/4-inch-wide hose clamps together end to end, then clamping them to the anode cooler to serve as a temporary handle.

The front, top and sides of the tank com-



Fig 1—A top view of the amplifier. The plate transformer in the front right and high-voltage power assembly next to it occupy the majority of the control side with the blower, filament and control transformers sitting just behind. The tank compartment with the cover removed shows the plate line on its Plexiglas stand.



Fig 2—Side view of tank compartment. The 2-meter load capacitor on its ceramic standoffs mounted to the Plexiglas stand is in the center with the 6-meter tank coil just visible below the spline shaft assembly. The 6-meter tune capacitor on its **L** bracket is in the lower right front.



Fig 3—Bottom view of amplifier with cathode compartment cover removed The filament choke is to the right with the 2-meter input network visible centered between the tube sockets. Both input tuning capacitors are mounted on the rear panel and one of the 6-meter input coils is just visible on the left. Note the use of coax for exciter lines to keep feedback paths minimized.

partment are all made from 1/16-inch aluminum with 1/2×1/2×1/8-inch aluminum angle brackets at all corners. The completed compartment measures 7×6 1/4×14 1/2 inches (WHD). The front and right-side compartment panels extend to the top of the main cabinet cover to keep inlet and outlet air separated. The compartment cover (not shown) has 176 0.2-inch holes above the tubes for cooling exhaust. When this box is attached to the floor of the main cabinet, it leaves a 4×7-inch hole at the back before the rear panel is attached. This opening serves as access for a dip meter when checking the 2-meter tank resonance and tuning range.

The 2-meter tank circuit consists of a shorted $\lambda/4$ balanced line section, tuned by a homebrew split-stator capacitor at the tube end of the line. Designing this type of tank circuit is made very pain-less with information and design exam-ples provided in references.[4] There are several advantages of using a push-pull tank circuit instead of a parallel arrangement at 144 MHz. In the push-pull arrangement, C_{out} and C_{in} of the tubes are in series, allowing a total C_{out} and C_{in} that is one quarter of that with the parallel arrangement. This allows lower values of loaded Q, resulting in higher efficiency and reduced compo-nent heating, minimizing thermal drift. The low value of C_{out} in this case allows the use of a $\lambda/4$ line in place of a $\lambda/2$ line, increasing bandwidth and decreasing size.

The line section, L2 of Fig 4, is made from 3/4-inch type-K copper pipe; the shorted end is made from one standard 90° copper elbow and one "street" 90° copper elbow. The open ends of the line are closed with brass plugs of the same outside diameter as the pipe, with a portion machined to fit inside the pipe. Standard copper pipe caps could be substituted for these plugs. The total length of the line section is 7 3/4 inches, from the ends to the inside of the shorted end. The plate-to-anode connections are made with 1/16-inch copper plate fastened between copper fuse clips on the anode connectors and threaded holes in the ends of the brass plugs.

The line section is supported by a Plexiglas stand and held in place by two copper clamps. The stators of the 2-meter **TUNE** capacitor, C3, are sup-ported by 1 1/2-inch ceramic standoffs attached to the Plexiglas stand (Fig 5). A 3/8×5/8-inch ear from each stator attaches to a 3/8-inch-wide strap around each of the tubes' anode coolers. The rotor of C3 is a two-inch disk of 1/16-inch copper, which is mounted to a piece of 1/4×28 brass all-thread rod. The threaded rod is held by a brass fitting (tapped for 1/4×28) that is attached to the Plexiglas stand. The threaded rod is coupled to a sliding spline shaft consisting of 1/4-inch Plexiglas rod inside a 1/2-inch piece of Teflon rod that has been drilled through the center. The Teflon tube is attached to a short piece of 1/4-inch stainless-steel rod that exits the tank compartment through a 1/4-inch panel bushing. This shaft is coupled to the turns counter with a synchronous gear belt (Fig 6). This shaft relocation via the gear belt serves only to improve the front-panel appearance; it may be omitted if desired.

The 2-meter tank circuit is coupled to the antenna by an adjustable reso-nant link. The link position is adjusted by a #10-24 screw through a threaded Plexiglas block, to which the link is attached (Fig 2). One end of the adjusting screw is supported by the top-cover angle bracket and the other end by a 2-inch-long piece of 1/2-inch angle mounted to the front panel of the compart-



Fig 4—Details of 2-meter input and output tank indicators and the 2-meter TUNE capacitor stators.



Fig 5—Rear view with the plate line removed showing the 2-meter TUNE capacitor.

ment. The link is made from 3/8×1/16-inch silver-plated copper strap, covered with a 3/8-inch Teflon sleeve; it is attached to the Plexiglas block with four #10-32 nylon screws. Silver-plated coax braid attaches the link to the 2-meter **LOAD** capacitor, C2, and the isolation relay, K3. The link-adjustment screw is accessed through 3/8-inch hole in the main cabinet top cover during initial setup, then the hole is covered with a plastic plug.

As with all push-pull circuitry, the key to successful operation is symmetry. All stray capacitance must be divided equally between both sides of the line and tubes. Also, try to keep ferrous materials out of the tank compartment to prevent imbalance.

The 6-meter tank is a normal π network designed for a plate-load resistance of 1150 W with a loaded Q of approximately 22. The design parameters are shown in Table 1. The input of the π network is connected to the center of the shorted end of the balanced line section where a #10-32 brass stud has been soldered in place. This is the low-impedance point of the line section, and anything but a dead short can be attached here without affecting the performance of the line.[5] To verify that the physical center of the line is also the RF center, couple a dip meter to the line and tune for a dip around 144 MHz. Then without moving the dip meter (DM), touch the tip of a lead pencil at points along the line until you find the spot that has the least effect on the DM. This is the attachment point for the plate choke and the 6-meter tank.

To keep the loaded Q of the π network as low as possible, full 51-54 MHz opera-

Table 1—Print out of operating parameters for the 6-meter input and output networks

The values for the PI matching network were calculated with Elmer (W5FD) Wingfield's new formulas found in the more recent ARRL handbooks.
FREEWARE Courtesy of KD9JQ
Triode Amplifier Program Version 2.0
For Grounded Grid Operation

(2) USER Biased 3CX800A7 at 50.0 MHz Rated for FORCED AIR

DC Plate Volts	=	2150.0	V (2500 V Max)
Max Plate Voltage	=	2150.0	V
Peak Plate Swing	=	1900.0	V
Min Plate Voltage	=	250.0	V
Plate Current Peak	=	3.368	A
Plate Current DC	=	1.119	A
Grid Current DC	=	0.063	A
Cath Current Peak	=	3.651	A
Design Plate RL	=	1128.1	Ω
RL for Matching	=	1154.8	Ω
Plate Dissipation	=	805.5	W (1600 W Max)
Grid Dissipation	=	3.2	W (8 W Max)
Cathode Bias	=	8.2	V
Conduction Angle	=	187.8	Degrees
Peak Grid Voltage	=	36.8	V
Zin @ Cathode	=	24.6	Ω
Pin Drive (PEP)	=	41.0	W
P0 @ Plate (PEP)	=	1600.0	W
P0 to Load (PEP)	=	1637.9	W
DC Power Input	=	2405.5	W
Efficiency	=	66.5	%
Power Gain	=	16.0	dB
Cath to Grid Cap	=	52.00	pF
Plate to Grid Cap	=	12.20	pF

T Match Input

RS = 50.0 Ω
L2 = 0.521 μH
CI = 44.924 pF
L1 = 0.422 μH
RFC = 0.195 μH
Zin = 22.6 −*j* 9.9 Ω
QL = 5.0

Pi Match Output

RP = 1154.8 Ω
CI = 50.0 pF
L1 = 0.2377 μH
C2 = 232.0 pF
RL = 50.0 Ω
QL = 22.0

tion was not attempted. The 6-meter **TUNE** capacitor, C1, operates very near its minimum capacitance because of strays and the C_{out} of both tubes. These strays account for a large portion of the 6-meter tune capacitance, which causes the majority of the tank circulating current to flow through the blocking caps, C7-C8. I used parallel Centralab 858 "door-knobs" for the blocking capacitors and I haven't experienced any problems. Capacitors with larger current ratings (such as HT-57s) would be a better choice for longer duty cycles.

The 3-30 pF vacuum-variable capacitor is mounted to the floor of the tank compartment with an L-bracket bent from 1/16-inch aluminum. Use the bearing retainer nut to attach the capacitor to the bracket, but be sure to add shims to the bearing to make up for space lost by the thickness of the bracket, or backlash will occur. The other end of the capacitor is supported by a #6-32 brass screw in the end of the capacitor that passes through a piece of Teflon bar stock mounted to the floor of the cabinet. A #6-32 hex nut holds the end of L3 and a piece of 3/8-inch strap (which supports C7 and C8) tight to the end of the vacuum cap. The other end of L3 is supported by a 1/2×1-inch Teflon standoff. Silver-plated braid ties this end to the 6-meter **LOAD** cap, which is mounted on the sidewall of the tank compartment.

Setting the Output Tanks

The 6-meter tank can be checked for tuning range with an SWR analyzer at the output connector. Connect a 1.1 kΩ, noninductive resistor from one of the tube anodes to ground to simulate the 1100-W plate-load resistance. You should be able to achieve a 1:1 match at both ends of the desired tuning range. Some stretching or compression of L3 may be required to bring the tuning range to 50-51 MHz. Be sure the top cover of the tank compartment is in place, as the stray capacitance it introduces accounts for a portion of the tuning capacitance for 6-meters.

The 2-meter tank was set up entirely



Fig 6—Front view of the amplifier with front panel folded down showing the location of high-voltage power-supply components at right and the gear-belt layout on the left. The bar-graph display PC board is visible in the lower left with the control board just beyond the two panel meters.

Fig 7—RF deck schematic. Unless otherwise specified, use 1/4 W, 5%-tolerance carbon composition or film resistors. See Table 3 for part-supplier contact information.

C1—3-30 pF vacuum-variable capacitor
C2—150 pF air-variable, 1400 V capacitor
C3—Split-stator air-variable (see text and Fig 4)
C4—325 pF air-variable, 1400 V capacitor
C5, C6—4.3-75 pF APC-style air-variable trimmer capacitor
C7, C8—1000 pF, 5 kV doorknob capacitor
C9—2500 pF, 2.5 kV feedthrough capacitor
D1—8.2 V, 50 W stud-mount Zener diode, 1N2806B
K3—Jennings RJ1A SPDT vacuum relay, 26.5 V dc coil
K4, K5—DowKey model 260B with "C" option, coax relay 26.5 V coil
K6—SPDT relay, 10 A contacts, 24 V dc coil
L1—See Fig 4
L2—See Fig 4
L3—2 turns of 3/8×1/16-inch strap, 1 1/2-inch diameter, 2 inches long
L4—See Fig 4
L5—8.5 inches of #14 Teflon covered copper wire with 6 inches tied tightly inside L4
L6—7 turns, 1/2-inch ID×1 1/8-inch long Teflon covered #14 AWG copper wire
L7—9 turns 1/2-inch ID×1 1/2-inch long Teflon covered #14 AWG copper wire
L8—30 turns #26 AWG enameled wire on an Amidon T-37-17 powdered-iron core over center conductor of coax
M1—0-2 A, 3.5-inch Simpson panel meter
M2—0-100 mA, 3.5-inch Simpson panel meter
RFC1—36 turns #18 AWG enameled wire, tight-wound on 1/2-inch-diameter Teflon rod
RFC2, RFC3—Ohmite Z-50
RFC4—Ohmite Z-144
V1, V2—Svetlana 3CX800A7


2 M Out
6 M Out
K4B
K5B
L8
RFC3
C4
47 1 W
47 1 W
1N914
0.01
6 M Bar Graph
L3
C1 3 - 30 (Vacuum)
C8
C7
(2) 1000 5 Kv
RFC1
C9 2500 2.5 Kv
B+
50 Ω 1 W
K3
L2
C2
150 1400 V
100
499 k
1N914
5 k
0.01
RFC4
2 M Bar Graph
L1
C3
V1 3CX800A7
V2 3CX800A7
L4
L5
C5 4.3 - 75 pF
K5A
2 M In
6 M In
K4A
820 SM
L7
C6 4.3 - 75 pF
L6
RFC2
1000
F4 2 A
D1 1N2806B 8.2 V 50 W
15 k 25 W R3
25 k 25 W R2
10 Ω 25 W R1
K6
R4 5 k Grid - Meter Adjust
to High - Voltage Board (Fig 9)
Meter Switch
M2 0 - 100
mA
2 × 1N5408
0.01 1 kV
M1 0 - 2
A
to Grid Trip Control Board (Fig 11)
B−
2 × 1N5408
+
−

Except as indicated, decimal values of capacitance are in microfarads (μF); others are in picofarads (pF); resistances are in ohms; k = 1,000. SM = Silver Mica with a dip meter inserted through the opening in the back of the compart-ment. Set the output link about 3/8-inch from the top plane of the line; this is close to the final position and adds stray capacitance. To keep loaded Q low, try to set the line length so it doesn't take very much tune capacitance to resonate the line at 144 MHz. Start with a line section a little longer than shown and carefully trim it to resonance. Remem-ber that 1 inch of line length equals approximately 10 MHz of tuning range! The tank should resonate at 144 MHz with about 1/4 inch of space between the plates of C3. When the desired tuning range is found, install a 1/4×28 lock nut on the threaded shaft of C3 to stop travel at the upper frequency limit. This will prevent accidental tuning of the tank to the third harmonic of 50 MHz, which could potentially damage the front end of a 2-meter exciter. Remember that the isolation of most coax relays is very poor at 144 MHz: It was only 35 dB with the DowKey 260B used here. For this reason, a Jennings RJ1A vacuum relay, K3, was added in series with the 2-meter transfer relay. The vacuum relay disconnects the 2-meter link from the coax and terminates the coax in a resistive load during 6-meter operation. Make sure the electrical length of the coax between the relays is more than $\lambda/10$ and less than $3\lambda/8$ at 144 MHz. With these safety measures in place, third-harmonic energy at the 2-meter input port was measured at −17 dBm during 1500-W 6-meter operation.

Input Networks

The 2-meter input network consists of a single tuned-link, air-core transformer (Figs 3 and 4). This coupling method requires slightly more drive than a link-



Fig 8—View of the right-hand side panel folded down showing the two transfer relays and the low-voltage power supply. The filament transformer is visible to the right of the plate transformer. Note the use of 80-mm fan covers for the cooling air inlets.

Table 2—Operating parameters of the amplifier

Plate voltage no load, 2350 V
Plate voltage @ 1 A, 2150 V
Zero signal plate current, 35 mA
6-Meter drive, single tone, 49 W
6-Meter power output,1420 W
6-Meter plate current, 980 mA
6-Meter grid current, 75 mA
Apparent efficiency, 67.4% (feed-through power not subtracted)
2-Meter drive, Single tone, 50 W
2-Meter power output, 1275 W
2-Meter plate current, 950 mA
2-Meter grid current, 68 mA
Apparent efficiency 62.4% (feed-through power not subtracted)

Table 3—Parts suppliers

Fair Radio Sales Co, Inc
1016 East Eureka St
PO Box 1105
Lima, OH 45804
tel 419-227-6573, 419-223-2196
fax 419-227-1313
e-mail **fairadio@wcoil.com**
URL **http://www.fairradio.com/**

Mouser Electronics
2401 Hwy 287 N
Mansfield, TX 76063
tel 800-346-6873
fax 817-483-0931
e-mail **sales@mouser.com**
URL **http://www.mouser.com/**

Newark Electronics
4801 N. Ravenswood Ave
Chicago, IL 60640-4496
tel 800-463-9275, 773-784-5100
URL **http://www.newark.com/**

Peter W. Dahl Co, Inc
5869 Waycross Ave
El Paso, TX 79924
tel 915-751-2300
fax 915-751-0768
e-mail **pwdco@pwdahl.com**
URL **http://www.pwdahl.com/**

RF Parts Co
435 S Pacific St
San Marcos, CA 92069
tel 760-744-0700, 800-737-2787
(orders only)
fax 760-744-1943
e-mail **rfp@rfparts.com**
URL **http://www.rfparts.com/**

Surplus Sales of Nebraska
1502 Jones St
Omaha, NE 68102-3112
tel 402-346-4750, 800-244-4567
(Orders only)
fax 402-346-2939
e-mail **grinnell@surplussales.com**
URL **http://www.surplussales.com/**

Svetlana Electron Devices
8200 S Memorial Pkwy
Huntsville, AL 35802
tel 256-882-1344, 800-239-6900
fax 256-880-8077
e-mail **sales@svetlana.com**
URL **http://www.svetlana.com/**

coupled, half-wavelength resonant line, but saves a lot of space. Two references[6,7] give formulas and rules of thumb for designing this type of transformer, but it still required a lot of "cut and try" before suitable sizes for L4 and L5 were found. The loaded Q of the resonant input link is approximately 3.5 before the coupled-in resistance from the secondary modifies it. The degree of mutual coupling of air-core transformers is an elusive value that makes the final loaded Q difficult to calculate. The input tuning capacitor, C5, could be changed to a 25-pF unit since the one used here turned out to be much larger than needed. Both sides of C5 are above chassis ground; it requires a nonmetallic screwdriver to adjust.

Six-meter drive and B– are applied to the center tap of L4, providing parallel cathode drive for 50-MHz operation. A common **T** network, with a loaded Q of five, matches the 50-W line to the 24.6-Ω input impedance of the parallel tubes. All the cathode pins of the sockets are tied together with buss wire in a star pattern. One-inch-long bus-wire leads connect the ends of L4 to the center of the bus-wire stars on the sockets. Again, symmetry is all-important in balanced operation.

Both input networks were set up with an antenna analyzer and two 50-W carbon resistors to simulate the input load impedance. Tack-solder the resistors from cathode to ground on each socket with the shortest-possible leads. Short leads are very important on 2 meters because lead inductance and stray capacitance become quite significant. The resistors present


K1 A&B
K2
0.01
Hot
F1
R1
50
25 W
MOV
240 V ac
F2
Hot
T1
MOV
F3
D1 - D16
R16
7.5 M
7.5 kV
C1
54 µF
4500 V
R2A
50 k
50 W
R2B
50 k
50 W
R13
25 Ω
25 W
B+
R4
499 k
1 W
mf
R5
499 k
1 W
mf
S2
0.01
R14
250
25 W
Filament
Voltage
B1
T2
0.001
RFC1
V1
V2
0.001
RFC2
R6
499 k
1 W
mf
R7
499 k
1 W
mf
R8
499 k
1 W
mf
T3
U2
50 V
5 A
U1
LM7824
Reg
IN
OUT
GND
R9
499 k
1 W
mf
to HV - Sense
Control (Fig 12)
R10
3.9 k
1 W
mf
Neutral
Ground
K2
S3
Safety
S1
Power
C2
500 µF
50 V
F5
+24 V dc
to Control
Board
(Fig 12)
R15
5 k
Calibrate
to Meter
Switch
(Fig 7)
1N914
K1
R3
100
1 W
C3
500 µF
50 V
R11
1.5 k
1 W
B–
R12
70
25 W
Except as indicated, decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); resistances are in ohms; k = 1,000, M = 1,000,000
mf = Metal film

Fig 9—Power-supply schematic. Unless otherwise specified, use 1/4 W, 5%-tolerance carbon composition or film resistors. See Table 3 for part-supplier contact information.

B1—Dayton #4C761 squirrel-cage blower
C1—54 µF, 4500 V oil-filled electrolytic capacitor
C2, C3—500 µF, 50 V electrolytic capacitor
D1-D16—1N5409 1200 PIV, 3 A Silicon rectifiers, four diodes per string
F1, F2—20 A, 250 V ceramic fast-blow fuse
F3—3 A, 250 V fuse
F5—2 A slow-blow fuse
K1—DPST relay, 25 A contacts, 24 V dc coil
K2—3PST relay, 25 A contacts, 120 V ac coil
MOV—130 V metal oxide varistor, V130LA5
R1—150Ω 25 W wire-wound resistor
R2A, R2B—50 kΩ 50 W wire-wound resistor
R3—100 Ω, 1 W carbon resistor
R4-R9—499 kΩ, 1 W metal film resistor
R10—3.9 kΩ, 1 W metal film resistor
R11—1.5 kΩ, 1 W metal film resistor
R12—70 Ω, 25 W wire-wound resistor
R13—25 Ω, 25 W wire-wound resistor
R14—250 Ω, 25 W rheostat
R15—5 KΩ, 10-turn potentiometer
RFC1, RFC2—12 bifilar turns of #18 AWG enameled wire on 1/2-inch-diameter Teflon rod
S1—SPST 5 A lighted panel switch
S2—Temperature snap-disc control Grainger # 2E245
S3—SPDT 5 A microswitch
T1—Peter Dahl plate transformer: 240 V primary, 1800 V, 1 A CCS secondary
T2—240 V primary, 16 V, 5 A secondary
T3—120 V primary, 20 V, 2 A secondary
U1—LM7824 TO-3 case
U2—5 A, 50 V rectifier bridge

25 W to the parallel 6-meter network and 100 W to the 2-meter push-pull network. Connect the analyzer to the respective input ports and adjust each network for lowest SWR. Some adjustment of the 6-meter input coils (L6 and L7) may be required to achieve a 1:1 match. If the 2-meter network does not present a good match, some adjustment in length of L4 and L5 may be necessary. Again, the covers must be in place and tubes must be in their sockets when measuring the match. Both filament leads and the filament choke must be in their final positions because the cathode-to-filament capacitance affects input tuning at 144 MHz. Remember, this analyzer method only gets you close to the final tuning points; settings will be different under live conditions. Finally, don't forget to remove the temporary resistors from the cathode and tank circuits after the initial adjustments are done.

AC Mains and Low-Voltage Power Supplies

Several protective measures are built into the amplifier to protect the tubes and the operator. The ac mains are brought into the amplifier with four-conductor cord to keep the neutral and ground separated per the *NEC* (Fig 9). Three fuses are used to keep the blower's ac source separate from the fused plate transformer. This was done so the blower's cool-down delay still functions after a high-voltage fault, which removes ac from the entire amplifier in dual-fuse designs. A thermal snap switch in the tank compartment keeps the blower running after shutdown or a high-voltage fault if the exhaust air has been above 110°F and is not yet below 90°. This only happens after several minutes of continuous operation. You may want to use a switch with slightly higher ratings (120°F on, 110°F off) if your shack is often warmer than the 90° off point used here. The 3CX800A7's filaments dissipate only 20 W each during cutoff and natural convection is more than enough to cool the tubes when shut off.

AC voltage for K2, the main control relay, is also taken from F3, the blower fuse, to make sure blower voltage is available before the amplifier can be powered up. A safety switch that closes when the top cover is in place supplies ac to S1, the main power switch. Power-supply inrush protection is provided by K1, which closes approximately one second after K2 and effectively removes R1 from the transformer primaries. The delay period is set by R3 and C3. There are two MOVs across the ac lines after the contacts of K2 and K1. Arcing at the relay contacts can and will produce voltage spikes and spike protection on the fuse side of K2 will not always save the high-voltage diode strings and other components. Filament voltage is adjusted at the primary of T2 by R14, a 250-Ω, 25-W rheostat. Filament voltage is measured at the filament choke via two leads brought to the back panel of the amplifier. Purists may want to measure voltage at the filament pins, but the low filament-current demand of these tubes makes the voltage drop between the sockets and the choke negligible. The rheostat also provides passive filament-inrush protection.

The low-voltage supply—consisting of T3, U1 and U2—supplies regulated 24 V at 1 A. The bridge rectifier and 24-V regulator are mounted to a piece of 3/4×1-inch aluminum angle that is placed directly in the cooling-air inlet path (Fig 8).

High-Voltage Power Supply

The high-voltage power supply consists of a Peter Dahl Hypersil plate transformer and a full-wave bridge rectifier with capacitor input filter. The supply is capable of producing 2150 V at 1 A CCS. The entire supply is assembled as one piece, then installed on the floor of the main cabinet next to the plate transformer (Fig 6). The oil-filled filter capacitor is sandwiched between two 3×6½-inch pieces of Plexiglas, in turn held together with four #10-24×5-inch-long flat-head screws. The rectifier strings and high-voltage-meter multiplier resistors are mounted to a 3×6½-inch PC board supported by ¼-inch spacers on the same four screws. A 3×6½-inch piece of fiberglass board holding the two bleeder resistors, B+ current limiting resistor and B– float resistor tops off the



Fig 10—Layout of the blower modifications for sound reduction.



Fig 11—View of control board.


DS4 Trip
1N914
100 μF 50 V
C2
K9
Q3 2N2222A
1N914
0.01
1k
to M1 (Fig 7)
R3 1k Grid - Trip Level
S1 Reset
K9A
K9B
DS5 Ready
S2 OPR
DS6 OPR
to Keying Board (Fig 14)
DS7 Overdrive
1.5k
Q2 2N2222A
1N914
0.01
150
R2 1k Grid - Current Warning Adjust
DS3 HV
K8A
K8B
DS2 Warm - Up
3.3M
K7A
K7B
D1 1N4001
K8
Q4 2N2222A
1N914
K7
1N914
Q1 MPSA42
1N914
1N914
Warm - Up Delay R1 5M
22 μF 50 V
C1
0.01
5k
+24 V from Power Supply (Fig 9)
DS1 Power
HV Sense from Power Supply (Fig 9)

Except as indicated, decimal values of capacitance are in microfarads (μF); others are in picofarads (pF); resistances are in ohms; k = 1,000, M = 1,000,000

Fig 12—Control schematic. Unless otherwise specified, use ¼ W, 5%-tolerance carbon composition or film resistors. See Table 3 for part-supplier contact information.

C1—22 μF, 50 V electrolytic capacitor
C2—100 μF, 50 V electrolytic capacitor
DS1—24 V lamp part of S1 (see Fig 9)
DS2, DS3, DS5—24 V panel light
DS4—24 V lamp part of S1
DS6—24 V lamp part of S2
K7, K8, K9—DPDT 5 A DIP relay, 24 V dc coil
R1—5 MΩ PC-mount potentiometer
R2, R3—1 kΩ PC-mount potentiometer
S1—Normally closed momentary-contact lighted panel switch
S2—SPST lighted panel switch

stack. All of the power resistors on the top board are mounted on one-inch ceramic standoffs. High voltage is routed to the tank compartment with test-lead wire and a high-voltage feed-through capacitor. The diode strings do not use equalizing resistors or capacitors as they are from the same batch and there is plenty of PIV headroom. Spike protection for the string is in the transformer primary, where it belongs. The high-voltage supply has three bleed-down paths for the filter capacitor: the bleeder resistors, the high-voltage meter multipliers and a 7.5 MΩ, 7.5-kV resistor at the terminals of the capacitor itself. Even with these redundant safety measures, *never* assume that they are working. *Always follow standard safety procedures when working with any high voltage, including the ac mains: It can kill you.*

Cooling

Whole-cabinet cooling is accomplished via a Dayton model 4C761 squirrel-cage blower. Cooling air is drawn into the cabinet at the right-hand side through two 2¾-inch holes, one on each side of the plate transformer. This removes heat from the bleeder resistors and other components before it enters the blower inlet. The Svetlana 3CX800A7 datasheet recommends airflow of 11 cfm at a back pressure of 0.2 inches (of water), for 600 W dissipation at sea level and 25°C inlet air temperature per tube. For two tubes, this is 22 cfm at 0.2 inches for 1200 W of dissipation. At a 1500-W output level with 60% efficiency, the tubes only dissipate 960 W.

The socket sub-mounting method I used resulted in a back pressure of 0.2 inches with this blower, as measured on my bench with a home-brew manometer. Since the blower is rated for 43 cfm at 0.2 inches (sea level assumed), there should be plenty of headroom for different elevations and inlet air temperatures. Remember that the above calculations are for continuous dissipation, while SSB and CW operation rarely approaches 50% of these values.

The mounting flange at the bottom of the blower was cut off so the outlet can align with the 2-inch-tall cathode chassis. The blower motor was taken off its squirrel cage and mounted to an aluminum **L** bracket. The squirrel cage was mounted to a 4×4-inch piece of 1/16-inch aluminum that supports the **L** bracket through a piece of 1/4-inch foam (Fig 10). This sound-isolation method was borrowed from Alpha Power Inc, and it works very well.

Control Board and Metering

The control PC board (Fig 11) is mounted on nylon standoffs just below the panel meters and above the row of switches and panel lights. As with most indirectly heated, oxide-coated cathodes, a warm-up period is required; for the 3CX800A7, a minimum of three minutes is recommended. When the amplifier is turned on, regulated 24 V is applied to the warm-up



Fig 13—(right) View of panel showing K1 and K2. The bias heat sink and assembly is visible below the filament rheostat.



K4C
1.2 k
DS2
6 M TX
+24 V from OPR Switch (Fig 12)
J6
Aux
NC
K5D
1N914
K5
2 M
Q1
TIP31
D1
1N4001
J1
+5 V
FB
1N914
2.7 k
1N914
0.01
2.7 k
1N914
K6
Bias
+24 V from OPR Switch (Fig 12)
+24 V from OPR Switch (Fig 12)
2 k
20 k
1.2 k
J2
Ground to Transmit
FB
1N914
Q2
2N3904
D2
1N4001
K5C
DS1
2 M TX
1N914
0.01
4.7 k
1N914
K4
6 M
1N914
K3
Isolation
J3
+12 V
FB
1N914
2.7 k
Q3
TIP31
1N914
0.01
2.7 k
J5
Aux
NC
K4D
+24 V from OPR Switch (Fig 12)
2 k
20 k
J4
Ground to Transmit
FB
1N914
Q4
2N3904
1N914
0.01
4.7 k
Except as indicated, decimal values of capacitance are in microfarads (μF); others are in picofarads (pF); resistances are in ohms; k = 1,000.

Fig 14—Schematic of the dual keying-circuit PC board. Unless otherwise specified, use 1/4 W, 5%-tolerance carbon composition or film resistors. See Table 3 for part-supplier contact information.

delay circuit consisting of Q1, R1 and C1 (Fig 12). When sufficient voltage appears at the base of Q1, relay K7 closes, with one set of contacts latching the relay on while the other set of contacts resets C1. If high-voltage is present, Q4 is switched on and K8 closes, lighting DS3 and supplying 24 V to the rest of the amp-lifier. Diode D1 was added between the field of K8 and the field of K7 to make sure K7 closes first. The proximity of the control board to the magnetic field of the plate transformer affects the timing of K7 slightly.

With the low grid-dissipation rating of these tubes, grid over-current protec-tion is necessary. Grid current is mea-sured as voltage drop across R1 of Fig 7, a 10-Ω, 25-W wire-wound resistor. R3 on the control board is set to fire K9 with Q3 at a grid current of 120 mA. One set of contacts latches the relay on; the other set interrupts the 24-V line to the **OPR** (operate) switch. Capacitor C2—across the field of K9—stops relay chatter on voice peaks. Lamp DS4 is part of the grid-reset switch S1, and it lights while K9 is energized. A second grid-current-sensing circuit, using Q2, is set to light DS7 on the front panel at 75 mA. This LED is used as a grid-current warning indicator and can be set at the grid-current level you prefer. The trip points of these two circuits and the grid-current meter reading are ad-justed while the amplifier is discon-nected from the ac supply.

To do so, connect a 24-V external supply to the 24-V bus of the amplifier after the timing circuit. Connect the positive lead of a variable-voltage dc supply to the ungrounded side of R1 of Fig 7 through an accurate dc milliammeter. Connect the external-supply negative lead to the chassis. With the grid-current panel meter disconnected, slowly increase the voltage of the bench supply until the milliam-meter reaches the set points of 120 mA for grid trip and 75 mA for the warning LED. Adjust R3 and R2 (Fig 12), respectively, to set the trip points. After the trip points are set, reconnect the grid-current meter and adjust R4 (Fig 7) for a full-scale reading of 100 mA using the same method as for the trip points. This "cold" method of setting grid trip points is a lot safer for the tubes than removing B+ and then applying drive to induce grid current.

The panel meter, M2, serves as the high-voltage meter as well as the grid-current meter. The calibration of the high-voltage portion was "roughed in" with the amplifier off and all voltages removed. A 1.5-V dc supply was connected to the multiplier side of R15 on the high-voltage rectifier board, then R15 is adjusted for a full-scale reading on M2. This corresponds to a full-scale reading of 3000 V. Meter calibration was then checked with a high-voltage probe and an accurate DMM, after the amplifier was turned on.

Plate current is measured directly in the B– line of the high-voltage supply, which is held slightly above ground by R12 on the power-supply assembly. Both meters are protected by 1N5408 diodes; two series-connected diodes on the B– bus keep it below approximately 1.4 V and two more are connected back-to-back from the multimeter to ground.



Fig 15—Details of the 2- and 6-meter low-pass filters. See Table 3 for part-supplier contact information.

50 MHz
C1, C2—50 pF doorknob capacitor
L1, L3—4 turns #14 AWG copper, 5/16-inch IDx1/2-inch long
L2—5 turns #14 AWG copper, 5/16-inch ID x 5/8-inch long

144 MHz
C3, C6—25 pF doorknob capacitor
C4, C5—40 pF doorknob capacitor
L4-L6—3.5 turns #16 AWG silver-plated copper wire, 1/4-inch IDx5/16-inch long

There are relative-output bar-graph displays for each band above the tune and load controls. These displays use two LM3914 bar-graph drivers per 20-segment display. A current-transformer pickup unit is used for 6 meters and a voltage-sensing pickup for 2 meters. The dual-bar-graph-display schematic can be found in Forrest Mims' book[8] and the 6- and 2-meter pickups are shown in Fig 7. The displays look appealing but turned out to be more trouble than they are worth, since I still use external wattmeters while I tune. The bar-graph displays' rapid response time would be better suited for plate- and grid-current meters.

Bias and Keying

Operating bias is developed across D1 of Fig 7, an 8.2-V, 50-W stud-mounted Zener diode. The Zener, along with K6, R2 and R3, is mounted on a 2x3-inch piece of 0.100-inch aluminum that serves as a heat sink (Fig 13). The entire assembly is mounted on two 1/2-inch Teflon stand-offs on the back panel of the cabinet. The 2-A cathode fuse is mounted on the back panel alongside the ac-line fuses.

The keying PC board is mounted on the rear floor of the main cabinet (Fig 8). The PC board contains keying circuits for both 6 and 2 meters (Fig 14). Because they are identical, I'll only describe the operation of one.

At rest, Q2 is biased on, holding the base of Q1 low. Grounding J2 will take the base of Q2 low, turning it off. This allows voltage to appear at the base Q1, turning it on and energizing K5. Alternatively, applying +12 V to J1 will also turn Q1 on, keying the amplifier. Both keying inputs are logic-compatible. The bias relay is energized through D1 or D2, which comprise a two-input **OR** gate. Each transfer relay is a DowKey #260B with the "C" option, which is a pair of DPDT signaling switches. Each of the relays' supply voltages is routed through one of the opposite relay's normally closed signaling contacts. This mechanical **EXCLUSIVE-OR** gate keeps the amplifier from being simultaneously keyed on both bands. The normally open contacts are used to light transmit LEDs on the front panel; these are mounted between their respective tune and load controls to help eliminate confusion while tuning.

With this type of transfer relay, input and output relay sequencing is obviously



(A)

(B)

Fig 16—The completed amplifier ready for its ride to the mountain top. (A) Front view, (B) back panel.

not an option, and hot switching of the relays will result unless preven-tive measures are taken. One option is to key the amplifier and let it key the exciter. Each relay's spare set of signaling contacts was brought to the back panel for this possible use. Another option, which I employ, is to use an outboard keying sequencer. The sequencer takes care of my mast-mounted preamplifiers as well as the exciter-amplifier timing. A suitable sequencer can be found in the references.[9] When using separate exciters for each band, the spare set of signaling contacts can be used for audio muting of the unkeyed exciter while transmitting.

General Construction Notes

The entire amplifier cabinet was built using common hand and power tools. All aluminum was cut with carbide saw blades in a radial arm saw and table saw. Blades with a 5° negative hook angle seem to work best for aluminum. The main amplifier cabinet measures 18×16×7$^1/_2$-inches (WDH). The plate transformer determined the cabinet height. The entire cabinet is built from 0.100-inch aluminum sheet and $^3/_4$×$^3/_4$×$^1/_8$-inch aluminum angle stock. All outside corners are secured with #8-32 pan-head screws tapped into the angle stock. The area under the plate transformer and high-voltage supply assembly was beefed up with a second layer of 0.100-inch aluminum on the cabinet floor. A square hole cut in the cabinet floor provides access the cathode compartment; it is normally covered with a piece of $^1/_{16}$-inch aluminum. All round holes were cut with chassis punches. The cabinet was painted with Dupont Chromaclear, which is a two-step (color coat/clear coat) automotive paint. After the base coat was applied over the primer, dry transfer lettering was applied to the front panel controls and Brothers P-touch labels were applied to the rear panel. Two coats of clear were applied over the base coat to finish the job.

All interior wiring was done with scrap Teflon-coated wire. The wiring harnesses were arranged so that all side panels can be removed and laid flat next to the chassis for ease of alignment and debugging. The intern-al coax runs were made with Teflon-dielectric coax to handle these high power levels, most other coax falls short, particularly at 144 MHz.

Adjustment and Operation

Use an ohmmeter to check the ac paths and RF deck for possible shorts and wiring mistakes. Be sure to blow out the entire cabinet with compressed air to remove any hidden debris. Set the filament-voltage rheostat to maximum resistance. If you haven't already done so, apply 24 V from an external supply to the 24-V bus and check the timing, control and keying circuitry for proper operation. Connect the amplifier to a suitable ac mains supply and connect an accurate DMM to the filament-voltage test points. Connect a 2-meter exciter and dummy load. Turn on the main power switch and quickly set the filament voltage to 13.5 V, or slightly less. *Never* operate the filaments below the 12.9-V recommended minimum. Be sure to check the filament voltage again after 5 to 10 minutes to detect any thermal drift in the rheostat. Verify that the plate is at approximately 2375 V.

Both tank circuits should be set to the tuning values found during initial setup. After the three-minute delay has elapsed, key the amplifier with no drive and check for a cathode idling current of approximately 30-50 mA. Apply a little 144-MHz drive and tune C5 in the input circuit for minimum reflected power. The 2-meter output link should be preset approximately $^1/_2$ inch above the top plane of the balanced line. Still with little drive, adjust the 2-meter tuning capacitor for maximum power output. Adjust the 2-meter load capacitor for peak output power and then leave it there until you are finished. Next, adjust link spacing as you would a load capacitor. Keep increasing the drive while increasing the link coupling for maximum power output, without exceeding grid-current limits and while also touching up the main tune capacitor, C3. Once the desired output power level is reached, check the link coupling by slowly decreasing the coupling until a slight decrease in output power is observed. Then increase the coupling slightly past the point where output power peaks and grid current is reduced to within operating limits. This should be very close to critical coupling, which will result in maximum efficiency. Go back and touch up the input network for minimum reflected power. The link is now set for operation and any further tuning adjustments can be made with C2 and C3.

Tune the 6-meter tank circuit the same way you would any other p net-work: by slowly increasing drive and tuning for maximum power output and best efficiency while touching up the input network for lowest reflected power. Then increase loading until a 2% decrease in power output is observed.

With values of loaded Q below 30 in the output tanks, there is no way to keep harmonics below the 60-dB-down figure required by the FCC without outboard filtering. Harmonic filters are a very small price to pay for the higher efficiency, lower drive require-ment and reduced thermal drift that the lower loaded Q provides. I've included descriptions of two suitable filters from the references;[10,11] they are very easy to build. The silver-mica capacitors originally in the filters have been replaced with surplus door-knob capacitors for better power-handling capability. With both filters installed all harmonics and spurious signals are more than 70 dB down from the fundamental.

Final Thoughts

This amplifier was completed just before the summer E-skip season and was immediately put on the air. On-the-air signal reports were all good, and they compared well to the 8877 amplifier I normally use. Close in IMD testing was done with the help of NN7DX who is located nine miles away, over flat ground. Results showed no excessive signal bandwidth while our antennas were positioned to bring signals down to S-9 levels during 1500-W output testing. The amplifier runs cool to the touch even after several hours.

The biggest problem encountered with the operation of the amplifier had to do with interfacing with certain exciters. Some of the new multiband exciters provide multiple antenna ports that can be configured for HF, 6- and 2-meter outputs, but provide only one buffered keying line. The ICOM-746 is built this way, but it does provide two unbuffered keying lines: one for HF and 6 meters and one for VHF. The ICOM-706-series radios also provide two unbuffered lines but only two antenna ports. Both of these radios require some sort of external switching for the keying line—and the antenna line in the case of the '706—if this amplifier and an HF amplifier are both used. ICOM does provide band logic as a variable voltage at the radio's **ACC** plug. I've designed a simple decoder/buffer that uses this logic and the radio's internal power supply to automatically switch the keying line between HF, 6- and 2-meter amplifiers. The buffer will sink up to 3 A of relay current. It also selects from three separate ALC input lines for those of you that employ sequencers using the ALC line for transmit inhibit. The decoder is described in "Automatic Amplifier Selection for the ICOM IC-746, -736 and -706MKII Transceivers," *QST*, May 2000, pp 33-36. With the decoder in place, amplifier selection with an IC-746 becomes totally automatic when changing bands between HF, 6 and 2 meters. For the IC-706 series, an additional coaxial relay can switch one of the antenna ports between HF and 6 meters to allow automatic selection. The decoder also works with the ICOM IC-736, choosing between HF and 6 meters. Although not verified, I've been told that the Yaesu FT-847 does have separate buffered keying lines for each of its four antenna ports, making interface to this amplifier easy. Performance figures for the amplifier are listed in Table 2 and the completed amplifier is shown in Fig 16. Enjoy!

Acknowledgements

Thanks to Marv Gonsier, W6FR, and Roy Scanlon, NN7DX, for help in reviewing the text.

Notes

[1] C. M. Maer Jr, W0IC, "The Perseids Powerhouse," *QST*, Oct 1959, p 32.

[2] R. M. Richardson, W4UCH, "A Kilowatt Amplifier for 6 and 2 Meters," *QST*, June 1973, p 16.

[3] The surplus sockets have a built-in 0.005 µf grid/screen bypass capacitor. RF Parts has a limited supply of these sockets. Substitutes include Johnson #124-0311-110 (with a grid collet) and Eimac SK1900.

[4] G. R. Jessop, G6JP, *VHF/UHF Manual*, 4th edition, (Hertfordshire, England: Radio Society of Great Britain, 1983) Chapter 3.

[5] E. P. Tilton, W1HDQ, *The Radio Amateur's VHF Manual*, (Newington: ARRL, 1972) p 77.

[6] R. D. Straw, Ed., *The 1999 ARRL Handbook* (Newington: ARRL, 1998), pp 6-46 and 6-47.

[7] R. Myers, W1FBY, *The 1975 ARRL Handbook* (Newington: ARRL, 1974), p 46.

[8] F. M. Mims III, *The Forrest Mims Engineer's Notebook*, (San Diego, California: Hightext Publications Inc, 1992) p 107.

[9] *The 1999 ARRL Handbook*, pp 22-53 through 22-56.

[10] I. White, G3SEK, Editor, *The VHF/UHF DX Book*, Vol 1 First Edition (Buckingham, England: DIR Publishing, 1992) p 12-35.

[11] R. Schetgen, KU7G, Ed. *The 1993 ARRL Handbook*, (Newington: ARRL, 1992) p 31-37, Fig 95.

By Bob Larkin, W7PUA From *QST*, June 2000

An 8-Watt, 2-Meter 'Brickette'

Put 20 mW into this little amplifier and get a 26-dB increase in transmitted power! Although the amplifier was designed initially for use with the DSP-10 transceiver, any 20-mW-output 2-meter exciter can enjoy the boost!

The DSP-10 transceiver[1] can be used with UHF/microwave transverters or as a very-QRP all-mode rig on 2-meters. The rig's 20-mW power output is sufficient for "barefoot" QSOs with locals, but that's hardly a big signal at any distance. Adding this little amplifier increases your fun quotient by raising the power level to 8 W, the high end of the QRP plateau. This brickette can also be used to drive an even higher-power, cascaded amplifier. Being a linear amplifier, it's suitable for use on all modes, including SSB, CW and FM.

The amplifier's front panel is quite simple, consisting of five monitoring LEDs. Knowing that everything is working correctly justifies the small amount of circuitry needed to operate these lights. The functions monitored include dc power on, transmit/receive status, power output, SWR and dc overvoltage. All amplifier control is done at the transceiver. Two RF cables connect to the transceiver output and receiver input, avoiding the need for an input relay in the amplifier.

This amplifier isn't limited to use with the DSP-10; any 2-meter transmitter that can deliver an output of 20 mW to drive the amplifier should work fine. In some cases, it might be desirable to use an input TR relay; there is sufficient room in the amplifier for adding one.



The five LEDs on the Brickette's front panel signal the amplifier's operating status. The power-output (**RF OUT**) and SWR (**HIGH VSWR**) LEDs vary in brightness depending on the forward and reflected power levels.

Circuitry

At the heart of this amplifier is an integrated power-amplifier module, manufactured by Mitsubishi. Such modules are used in many commercially manufactured transceivers and using one here makes amplifier construction and alignment simple. Within the module are two cascaded linear-amplifier transistors, along with their associated matching networks and biasing circuits for class AB operation. The module has 50-Ω input and output impedances. All we need to do is add a circuit to turn on the bias supply during transmit, install a low-pass filter for harmonic control and include an antenna-switching relay. To monitor amplifier operation, we tack on some simple circuitry.

Refer to the schematic in Figure 1. At the input pin of the RF module, U1, we apply 20 mW of drive. Blocking capacitors for the RF input and output ports are included within the module. Bypass capacitors on the three power leads are external, however. Ferrite beads, L6 to L8, prevent problems that might occur if RF gets on the power leads.

An **L** network consisting of L1 and C4 improves the impedance match to the module. Adding the network increases the output power by about 0.25 dB. Following the amplifier is a directional coupler (discussed later). Next is a five-pole low-pass filter. For simplicity, it is configured with the same coil and capacitor types as are used in the directional coupler. This filter attenuates the second and higher-order harmonics.

Separate connectors are available on the DSP-10 for the transmitter output and the receiver input. This simplifies adding the antenna relay for the amplifier since no switching is required at the amplifier input. A miniature relay is adequate at the amplifier output. Providing an isolation of about 30 dB, the relay, along with the PIN attenuator that is part of the DSP-10, provides plenty of protection for the receiver.

A lumped-element directional coupler, consisting of L2, L3 and C5 to C10, delivers power samples of the forward and reflected output signals. This directional coupler works quite well, providing a coupling of about −28 dB and a directivity[2] of 20 dB, but only over a narrow (12-MHz) bandwidth. For our application, this is adequate. Two diode detectors, built around D6 and D7, generate low-level dc signals that indicate the forward and reflected powers. These signals, in turn, are amplified by two sections of op amp U2. The resulting voltages are displayed on two LEDs, green for **RF OUT** (forward) power and red for **HIGH VSWR** (reflected) power. The LEDs serve as rough indicators of proper amplifier operation.

The **OVERVOLTAGE** indicator lights when the dc supply voltage exceeds 14.5 V, but does not automatically shut down the amplifier. The idea here is to supply a warning mechanism. When RF is not applied to the amplifier, it is quite resistant to supply overvoltage. As long as the supply overvoltage condition sets an alarm light, an observant operator will defer applying RF until the voltage is reduced.

Amplifier control is handled by the DSP-10. That transceiver has software-controlled relay sequencing, providing +5 V during transmit. Q2 and Q3 drive the antenna relay from this control. A ferrite bead, L11, and C24 keep RF at the antenna relay from getting back into the control circuits. D10 shunts the inductive kick from the deactivated relay coil. An LED, D2 (**XMIT**), across the relay displays the amplifier TR status.

Q4 provides an output that can control a follow-on amplifier. This output is an open-collector, ground-on-transmit type, compatible with many commercial and homebuilt amplifiers. For added driver-circuit protection, a reverse-voltage shunting diode, D11, is used.

Building the Amplifier

You could build the amplifier on a scrap of PC board. In fact, my first version is built that way (see the sidebar). For many builders, however, a PC board[3] is a more convenient way to assemble the project and that is shown in the photos.

This PC board is double-sided, with plated through holes. The backside is a solid ground plane allowing the board to be fastened directly to the aluminum enclosure. Such construction works very well for RF boards because a low-inductance ground path can be maintained throughout, reducing any interactions between the various circuits. However, this mounting method does not allow component leads to extend beyond the bottom surface of the board. I dealt with this primarily by using surface-mount parts[4] and by carefully bending the component leads so they behave like surface-mount parts.

All of the chip resistors, chip capacitors, diodes, surface-mount ICs and ferrite-bead chips are soldered to their board pads conventionally. Install the amplifier module *after* the board is mounted in the box. The antenna relay, fuse clips and the variable resistor all have their leads bent away from their host. Avoid making any bends close to the component body; make the bends at a point about 1/16 inch away from the component body. This approach eliminates mechanical stress on the lead attachment. These components end up about 1/16 inch above the board's top surface after they are soldered in place.

Figure 2 shows the construction of the four toroidal inductors, L2 through L5. Experience shows the inductor values are quite repeatable if the turns are always distributed in the same manner around the core. As the turns are pushed closer together, the inductance increases considerably. The matching-network coil, L1, is noncritical and it should be wound as shown in the part list and Figure 2; it should need little, if any, adjustment.

The LEDs all have long leads and are soldered to the board after bending the lead ends by about 1/8 inch. Be sure to keep track of the LEDs' longer (anode) leads: Those leads connect to the current-limiting resistors.

Putting the Board in a Box

Once the PC board is assembled, use it as a template for marking the hole locations in the enclosure, a standard Hammond die-cast box. Mount the board flat against the box bottom using #4-40 hardware. Because there will likely be some mold marks and box-identification letters where the board and RF module lie, make the enclosure's inner-bottom surface reasonably flat; you can do this with 60-grit sandpaper. Bend the leads of the five LEDs to apply a slight forward pressure on the lights as they slide into the holes in the box front. That holds the LEDs in alignment without needing adhesive.

Take care when tightening the PA module mounting screws to be sure that no pressure is applied to the ends of the module cover. The leads from the module need some trimming. They are above the board and need forming to get to the board level for soldering. Don't apply pressure at the edge of the module cover when doing this. You may need to hold each lead with needle-nose pliers to keep from damaging the case. It should be possible for the leads to reach the board surface within 1/8-inch of the cover.

Three short pieces of 50-Ω coax attach the board to J1, J2 and J3. Solder lugs under the jacks provide for ground connections at one end and PC-board pads take care of the other end of the coax.

Three leads run between connectors J4, J5 and J6 and the PC board. Each of these leads has a bypass capacitor (C28, C6 and C27, respectively) at the connector. Short, low-inductance leads are important on these capacitors. To help keep the RF signals inside the box, a small inductor wound on a ferrite core (L14, L15 and L16) is placed on each wire. Position these inductors close to their connectors. If #22 or #24 stranded hook-up wire with thin insulation is used, it's possible to wind the coils with the hook-up wire.

Turning on the Amplifier

Now, to see it work! First, connect a 50-Ω noninductive dummy load to the amplifier output.[5] If you have a variable-voltage power supply to use for initial testing, slowly raise the dc supply voltage from 0 V to 13.8 V. Otherwise, you'll need to rely on the power-supply fuse as protection from any serious construction errors when apply-

Did the Amplifier Always Look Finished?

No, it didn't. Some people may be able to put a finished amplifier on a PC board and have it work fine. I don't seem to be able to do that!

My first step in designing the amplifier was to search for suitable RF modules, mostly via the Internet. Once I selected the M57732L as having suitable power, gain and dc operating voltage, I drew a schematic in my notebook. Originally, the circuit had automatic shutdown for high SWR and full voltage regulation to deal with overvoltage. This looked too complex. It was necessary to cut off the drive to the amplifier, and the regulator had to be a low-dropout type (for these, the difference in voltage between the input and the output need be only a fraction of a volt). I couldn't find an integrated regulator that met my requirements and the thought of building one using op amps and transistors used more parts than I could justify.

I opted for simplification, putting alarm lights on for SWR and overvoltage and turned the automatic part over to the operator! A new schematic resulted, not unlike that of Figure 1. I went to the *ARRL Radio Designer*† and simulated the directional coupler and low-pass filter. A little playing around with the simulation showed that a single inductor value could be used for both subcircuits.

Next, I built the "breadboard" version using scraps of PC board. Testing showed that almost everything worked as expected. The **overvoltage** light did not have snap action, though. That was caused by using a resistor where the ferrite bead, L13, is now. I ran the input voltage temporarily up to 16 V and everything continued to function. Next, I left the amplifier running for an hour and nothing overheated. I checked the intermodulation products and harmonics and found them to be at satisfactory levels.

It was now time to layout the PC board. The experience of putting the breadboard together allowed a smarter final layout. The first version was on two boards and some of the connectors ended up on the front panel. This was all worked out for the final design.

—Bob Larkin, W7PUA

†ARRL order no. 6796. ARRL publications are available from your local dealer, or directly from the ARRL. See the ARRL Bookcase elsewhere in this issue, or check out the ARRL Web site at: **http://www.arrl.org/catalog/**.


J1
RF POWER
from DSP-10 J213
50 Ω
IN_T
U1
M57732L
RF Module
POWER AMPLIFIER
GND
IN
Vcc 1
VBB
Vcc 2
OUT
GND
Flange
C1 0.22
C2 0.22
C3 0.22
L6 FB
L7 FB
L8 FB
L12 FB
C20 0.01
C21 0.01
Bias
+5 V On Transmit
L1
Matching Network
C4 6.8
C5 22
C6 22
C7 1
C8 1
DIRECTIONAL COUPLER
L2 52 nH
L3 52 nH
C9 22
C10 22
R1 51
R2 51
REFL
FWD
D6 BAR74
D7 BAR74
L9 FB
L10 FB
C15 0.01
C16 0.01
L4 52 nH
L5 52 nH
C11 22
C12 22
C13 22
C14 22
LOW-PASS FILTER
TR Relay
K1B
ANT
RCVR
50 Ω
J2 ANT
J3 to RCVR (DSP-10 J211)
C18 0.01
R3 100 k
R5 100 k
W2
Gain = 23
R4 2.2 M
R6 2.2 k
R7 2.2 k
U2B
D3 Green RF Out
Gain = 221
R8 10 k
R9 2.2 M
R10 100 k
R11 2.2 k
R12 2.2 k
U2D
D4 Red HIGH VSWR
U2C
Not Used
C17 0.01
J4 +11 to 14.5 V @ 1.6 A
C28 470
L14 1.5 µH
F1 2 A
D8 S5MCD1
C22 47 µF 16 V
+13 V
D1 Yellow POWER ON
R13 2.2 k
L13 FB
U3 78L05
Reg
IN
OUT
GND
5-V REG
+5 V
C23 0.22
W1
R18 4.7 k
Q1 FMMT3906
Switch
R28 1 k
D9 BAR74
C19 0.22
U2A LM324AM
R17 470 k
R14 10 k
R15 2 k
OVERVOLTAGE ADJ
R16 4.7 k
R19 2.2 k
R20 2.2 k
D5 Red OVERVOLT
J5
AMP CONTROL IN
(from DSP-10 J208-1)
+5 V On Transmit
C26 470
L15 1.5 µH
R21 4.7 k
R22 4.7 k
Q2 FMMT3904
R23 4.7 k
Q3 FMMT3906
W3
D10 BAR74
L11 FB
C24 0.01
+13 T
K1A ANT
R24 2.2 k
R25 2.2 k
D2 Green XMIT
R26 4.7 k
Q4 FMMT3904
Ground On Transmit
D11 S1KBD
L16 1.5 µH
C27 470
J6
AMP CONTROL OUT
to Following Amp

Except as indicated, decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); resistances are in ohms; k = 1,000, M = 1,000,000
R27 not used

Figure 1—Schematic of the 8-W amplifier. All resistors are 5% 1206 chips. These are available in small quantities from Mouser Electronics (Xicon). Unless otherwise noted all capacitors are either 1206 or 0805 chips (either size fits on the board). Capacitors less than 470 pF are NP0, while values from 470 pF and up are any general-purpose ceramic, such as X7R or Z5U. Component sources listed here are generally only a few of several that manufacture equivalent parts. If the amplifier is built without a pre-made PC board, change the chip components to leaded types. Component designations for the LEDs differ from *QST* style. Parts used in the amplifier are available from one or more of the following sources. Source abbreviations used in the parts list precede the company name: (DK) Digi-Key Corp, 701 Brooks Ave S, Thief River Falls, MN 56701; tel 800-344-4539, 218-681-6674; **http://www.digikey.com**; (ME) Mouser Electronics, 958 N Main, Mansfield, TX 76063; tel 800-346-6873, 817-483-4422; **http://www.mouser.com**; (RS) RadioShack—see your local distributor; **http://www.radioshack.com**; (RP) RF Parts, 435 South Pacific St, San Marcos, CA 92069; tel 800-737-2787, 760-744-0700; **http://www.rfparts.com**.

C22—47 µF, 16 V surface-mount electrolytic (DK PCE3033CT)
C26, C27, C28—470 pF, 50 V, leaded ceramic (ME 140-50P2-471K)
D1—Yellow T1 LED (DK160-1079)
D2, D3—Green T1 LED (DK 160-1080)
D4, D5—Red T1 LED (DK 160-1078)
D6, D7, D9, D10—BAR74 diode (DK BAR74ZXCT)
D8—5-A, 50-V power rectifier, SMC package (DK S5ACDICT)
D11—1-A, 100-V power rectifier, SMB package (DK S1BBDICT)
K1—SPDT 12-V dc miniature relay, Omron G5V-1-DC12 (DK Z774)
L1—2t, #20 or 22, ¹/₈-inch ID; see Figure 3.
L2-L5—52 nH; 5 turns, #26 enameled wire on a T-25-17 toroid; see Figure 3.
L6, L7, L9, L10, L11, L13—Ferrite SMT bead, 1206, 600 Ω at 100 MHz, Stewart HZ1206B601R (DK 240-1019-1)
L8, L12—Ferrite SMT bead, 3 A, 1206, 100 Ω at 100 MHz, Stewart HI1206N101R (DK 240-1008-1)
L14-L16—1.5 µH, 5 turns #22 or #24 enameled wire on an FT-23-43 core; see text.
F1—2-A, 5×20-mm fuse (DK F948) with two clips (DK F058)
J1, J5, J6—Phono jacks (RS 274-346)
J2, J3—BNC jack (RS 278-105)
J4—5.5-mm OD, 2.1-mm ID power connector (RS 274-1563)
Q1, Q3—FMMT3906 PNP transistor, SOT23 (DK FMMT3906CT)
Q2, Q4—FMMT3904 NPN transistor, SOT23 (DK FMMT3904CT)
R15—2 kΩ adjustable resistor, Bourns 3329H-1-202 (DK3329H-202)
U1—RF amplifier module, Mitsubishi M57732L, (RP M57732L)
U2—LM324AM dual op-amp (DK LM324AM)
U3—78L05 5-V positive regulator, SO-8 package (DK LM78L05ACM)
Misc: PC board, enclosure 3.7×4.7 ×1.3 inches, Hammond 1590BB (DK HM152), hardware.



Figure 2—Coil details. Arrange the turns on the four toroids as shown here. L2 and L3 might need to have their turns spacing adjusted during tune-up.



Figure 3—Measured power output and dc-supply current as a function of drive power. Notice that the output-power scale is not in decibels. This makes the output appear less compressed than it really is. The 1-dB compression point is at about 4 W.



Figure 4—Measured intermodulation distortion with a PEP output of 8 W. Third-order products are down about 28 dB from peak power, fairly typical of this amplifier type. Perhaps more important is that the fifth and higher-order products continue to drop off as the order increases. These higher-order products are farther from the operating frequency and thus generally more disruptive to nearby stations. The current drawn during this two-tone test was 670 mA.

ing the full 13.8 V. At full voltage, the current drawn by the amplifier during receive should be about 10 mA. Next, set the **OVERVOLTAGE** alarm. Adjust the voltage at the wiper terminal of R15 to 4.68 V.[6] If you can vary the dc supply voltage, the **OVERVOLTAGE** LED should light at about 14.5 V.

When making the following adjustments, it is necessary to adjust the turns spacing on the toroidal inductors. For safety, *do this only when no RF drive is applied.*

Connect the TR control to the DSP-10 and connect J1, the amplifier's RF input, to the DSP-10 antenna connector. In CW mode, increase the DSP-10's RF power slowly until the **RF OUT** LED (D3) glows. Then adjust the turns spacing on L2 and L3 to extinguish the **HIGH VSWR** light (D4). This indicator is about 10 times more sensitive than the **RF OUT** LED, but it should be possible to extinguish the **HIGH VSWR** LED completely. Continue this adjustment process while increasing the drive power. You can measure the voltage at the output of the SWR op amp



Pretty outside and pretty inside, the Brickette's construction reflects a caring hand. At the top-left rear the RF-amplifier module can be seen fastened to the base of the enclosure, which serves as a heat sink for the module. The relay is at the upper-right and a kludge area is visible at the lower right behind the front panel.



This rear-panel view of the 8-W Brickette shows compact but uncrowded I/O connectors clearly labeled.

(U2 pin 14) and continue to minimize this voltage, although the **VSWR** LED is not lit.

Optimize the amplifier matching by measuring the power output as indicated by the dc voltage at U2 pin 7 and adjusting L1's turn spacing (and perhaps changing the value of C4) for maximum output at high drive. Don't expect major changes with these adjustments as the amplifier is inherently quite well matched.

While in transmit, check that the bias voltage at pin 3 of U1 is about 4.9 V and that the idling current with no RF drive applied is about 140 mA.

Performance

Figure 3 shows the power output and current level for various drive levels. The CW output is over 8 W for the two devices that I tested. When tested with a two-tone input signal and an output of 8 W PEP, the IMD level is down 28 dB for third-order products and 43 dB for fifth-order products (see Figure 4). The strongest harmonic is the second (at about 292 MHz) and this is 65 dB down from peak output, more than enough to meet FCC 2002 requirements.[7]

Concluding Thoughts

Several areas on the PC board have either a ground plane section or pads for mounting transistors, resistors and other components. These areas are available to you to use for modifications or additions to the amplifier (perhaps you have an application that needs an input TR relay or you need a different control circuit).

Now you're ready to get on the air with a medium-sized signal. You can increase power even further by cascading another amplifier. Or, use some of the signal processing in the DSP-10 to work deeper into the noise. QRP power levels have pushed the idea of "working smarter instead of harder."

Notes

[1] Bob Larkin, W7PUA, "The DSP-10: An All-Mode 2-Meter Transceiver Using a DSP IF and PC-Controlled Front Panel," *QST*, —*Part 1*, Sept 1999, pp 33-41, —*Part 2*, Oct 1999, 34-40, —*Part 3*, Nov 1999, pp 42-45. Additional information on that project is available on the author's Web site, **http://www.proaxis.com/~boblark/dsp10.htm**. Any future information about this amplifier project will be placed at this Web site.

[2] The directivity of a coupler is the difference, in decibels, between the forward signal and the reflected signal, when the coupler is properly terminated in its designed load, in this case, 50 Ω. Couplers constructed from transmission lines have high directivity over a very wide frequency range. These lumped-element couplers are restricted in the frequency range where their isolation is high, but offer simplicity instead.

[3] Gerber files for making the PC board can be obtained from the author. Alternatively, unpopulated PC boards are available from Mashell Electric, PO Box 5, Eatonville, WA 98328. Price: $20 each in the US, $21 in Canada (air mail) and $22.50 (air mail) elsewhere. These boards have plated through holes, a solder mask on the component side and a silk-screened legend. Check their Web site **http://members.aol.com/w7slb/w7slb.htm** for details.

[4] See Sam Ulbing, N4UAU, "Surface Mount Technology—You Can Work with It!", *QST*—*Part 1*, Apr 1999, pp 33-39; —*Part 2*, May 1999, pp 48-50; —*Part 3*, Jun 1999, pp 34-36; —*Part 4*, pp 38-41. Additional comments from Avery Davis, WB4RTP, can be found in the *QST* Technical Correspondence, Feb 2000, p 70. Surface-mount techniques are used for the DSP-10 transceiver. Some people were initially concerned about dealing with the tiny components, but after constructing the board, most builders felt that it went well.

[5] A satisfactory dummy load for 144 MHz can be constructed from four 200-Ω, 3-W metal-oxide resistors. Arrange them in parallel around a coax connector. Short leads are important. *Do not use wire-wound resistors.*

[6] The **OVERVOLTAGE** alarm triggers when the dc supply voltage is greater than 14.5 V. If an adjustable dc supply is available, you can set this directly. Alternatively, set the voltage at the wiper of R15 to 0.360×(V – 0.6), where V is the dc supply voltage.

[7] Larry Price, W4RA, and Paul Rinaldo, W4RI, "WARC97, An Amateur Radio Perspective," *QST*, Feb 1998, pp 31-34. By these rules, an 8-W 2-meter transmitter must suppress the harmonics by at least 52 dB. Greater amounts of suppression are required for higher power levels.

By Dave Mascaro, WA3JUF **From *QST*, June 1990**

903-MHz Linear Amplifiers

Part 1—Looking for a gain block or two for your 903-MHz station? Here are *eleven* of them to cover just about any need you may have, from a simple receiving preamplifier to one with 23 dB gain and over 4 W output!



The 33-cm Amateur Radio band (902-928 MHz) is becoming well populated in many areas of the country. Propagation on 33 cm has traits similar to both 432 MHz and 1296 MHz, but has characteristics all its own at times, making it a very interesting band. It's pleasantly surprising what you can do with a few watts on 903 MHz with high-gain loop-Yagi antennas.

Articles have been published on transverters, amplifiers and receivers for 33 cm. I described a 759-MHz local oscillator[1] intended to be used with a 144-MHz IF for operation on 903 MHz. If you've built the transmit section of a transverter that gets you to the 10-mW level, or if you've purchased a commercial transverter such as Down East Microwave's low-power, no-tune unit,[2] you'll need to bring your transmitter power up to a usable level. Instead of showing a typical transmit-amplifier chain, many of which have been described in Amateur Radio literature, I will discuss eleven different gain blocks, for several different gains and power levels, in this two-part series.

I suggest that you build each amplifier in its own enclosure, rather than trying to build more than one amplifier in one box to eliminate connectors or reduce size. If you are building your own equipment, you probably aren't too concerned about size and compactness, and having separate enclosures makes for much easier tuning and troubleshooting. Many transistors used in 1296-MHz projects are suitable for use at 903 MHz; some even have more gain at 903.

Transistors with SD prefixes used in the following designs are manufactured by SGS-Thomson Microelectronics.[3] Some of these transistors don't operate at 12 V. Again, in building your own equipment, this shouldn't be a major problem. Gains listed are averages for several different devices tried. All of the amplifiers can be driven harder than indicated—for CW or FM operation only—but should be used at or below their rated power output for SSB work. All the designs can be used at lower power output; they are all linear amplifiers.

Construction

All of the amplifiers are built using similar techniques. Each design uses common $^{1}/_{16}$-inch-thick, G-10, double-sided, fiberglass-epoxy PC board for the microstrip circuitry. The ground-plane side of each PC board is unetched.

The microstrip boards can be made using what I call the "X-ACTO®-etch" method. This involves using a piece of clear tape as the resist. (Four-inch-wide clear tape is available at stationery stores.) After drawing the pattern on the board with a pencil or fine-tipped marker, cover it on both sides with clear tape and cut the pattern in the tape with an X-ACTO knife. Then, remove the tape from the areas to be etched and etch the boards in ferric chloride in a crock pot on low heat. Do this in a well-ventilated area! Etching takes about half an hour without agitation. The crock pot is a no-mess way to etch boards. Only an inch or so of ferric-chloride solution is needed. Of course, you can also use a photographic method to make boards, as I do for multiple or complicated boards.

After the PC board is etched, clean it with steel wool and drill holes at all dc- and RF-ground points using a no. 50 drill. No holes are needed for component leads, as all components are mounted on the microstrip side of each PC board. RF grounds must be located as close to the areas to be grounded as possible, to ensure low-inductance ground paths. There are at least two ways to do this. One is to install a rivet in each hole, flare it with an awl or ice pick, then flatten it by tapping with a small


E
SD1330
B
C
E
C5
100
chip
FB
D1
R1
1 k
1/4 W
100
chip
C6
R2
1 k
1/4 W
C8
FT
+12 V
C7
0.01
C9
10 µF
35 V
FB
RFC1
RFC2
Except as indicated, decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); resistances are in ohms; k=1,000.
C4
100
chip
50 Ω
Output
50 Ω
Input
C3
100
chip
Q1
INPUT
TUNE
C1

Fig 1—Schematic of the SD1330 receive preamplifier/low-level transmit stage. RFC1 and RFC2 consist of 8 turns of no. 24 enam wire closewound on a 0.1-inch-ID form (such as a 0.1-inch drill). D1 is a 9.1-V,½-W Zener. C1, a 12.5-pF trimmer, is available from Mouser (part no. 24AA071).



Fig 2—Amplifier No. 1, a 10-mW-output stage that's well suited to receiving applications, in prototype form.



hammer on an anvil or other hard surface. Then, solder the rivets on both sides of the PC board. Alternatively, pieces of bus wire can be used for grounding.

Because parts placement is quite straightforward, I haven't provided parts-placement drawings for all of the designs. The schematics and PC-board artwork should provide all the guidance you'll need to assemble the boards. I can help with any questions that you might have when building any of the amplifiers.

All of the amplifiers described, except those operating under the 300-mW level, require some heat sinking. A small brass sheet is sufficient for the studded parts, but a finned heat sink an inch or two square is needed for the flanged-device amplifiers.

Fig 3—Full-scale PC-board artwork for the 10-mW SD1330 amplifier. Black areas represent unetched copperfoil. All parts are mounted on the foil side of the board. Crop the finished boards as necessary.

Thermally conductive compound is required between the devices and their heat sinks. For studless devices, a small piece of brass shim stock soldered from the bottom of the device to the ground-plane side of the PC board should work fine.

An easy way to enclose an amplifier like those described is to make a housing using double-sided PC board or brass sheet for the four walls and bottom cover. The amplifier PC board makes the top cover. Input and output connectors (N, BNC or SMA) can be bolted or soldered to the end walls with their center pins soldered directly to the microstrip input/output lines in an end-launch configuration. When using PC-board material for housings, mount the side walls in such a way that the grounding is continuous from the connectors to the ground-plane side of the amplifier board.

Various die-cast aluminum boxes, such as Bud CU-123 and CU-124 and the Hammond 1590 series, also work great for enclosing these designs. Die-cast boxes usually provide sufficient heat sinking for amplifiers operating at less than 2 W output. Device studs or flanges should be attached directly to the boxes in these cases. All component leads must be kept as short as possible. This also applies to trimmer caps. Mount them flush to the PC board so that they act as capacitors—not as inductor/capacitor combinations. Use multiple rivets (or bus wires) to ground the trimmers.

Components

Use ceramic chip capacitors for the dc blocks and high-frequency bypassing. Some of the larger-value bypass capacitors, like 0.001 µF and 0.01 µF, are available in chip form also. These epoxy types are good for all the designs described here. I use inexpensive chip caps from Mouser Electronics.[4] Chip caps and Johanson piston trimmers are available from Microwave Components of Michigan.[5] Transistors are available from RF Parts[6] and RF Gain, Ltd.[7] Components, rivets and PC boards are available from Frontier Microwave.[8]

Tune-Up

In most of these amplifiers, the quiescent collector current I_{cq}) initially will have to be checked and set with no drive applied.

To check bias current, disconnect the cold end of the collector choke and insert a milliammeter in series with the choke. Adjust I_{cq} by changing the value of the collector-bias resistor or by changing the collector voltage. All amplifiers requiring 12 V can be powered directly from low-current, 12-V dc sources (a three-terminal, 12-V regulator, for example). Amplifiers running on 14-18 V dc or 21-23 V dc can be powered by an LM317T (or LM317K) adjustable regulator. Set the regulated voltage to a minimum, and adjust it upward from minimum while monitoring I_{cq}. Idling collector current can be adjusted to suit your gain and power-output requirements.



Fig 4—Schematic of the SD1333 and SD1359 amplifiers (Amplifiers No. 2 and No. 3). All components except Q1 are common to both designs (see text).

C1, C2—12.5-pF trimmer, Mouser no. 24AA071.
C7—0.01-µF disc ceramic.
D1—9.1-V, ½-W Zener.
RFC1, RFC3—8 turns of no. 24 enam wire, 0.1 inch ID, closewound.



Fig 5—Full-scale PC-board network for the 100- and 250-mW amplifiers. Black areas represent unetched copper foil. All parts are mounted on the foil side of the board.

Amplifier No. 1: A Receive Preamplifier or 10-mW-Output, 13-dB-Gain Transmit Stage

The amplifier shown in Figs 1 and 2 is a low-power stage using an SD1330, Motorola MRF901 or NEC NE64535. This stage is best suited to the receiving side of a transverter. With a noise figure (NF) of 2 dB, it makes a fine front end by itself. With a good, low-noise GaASFET preamplifier in front of it, you'll have all the sensitivity you need in front of the receive mixer. For transmitting applications, where a low noise figure isn't important, an MMIC amplifier would be better because it is a lot easier to build for the same results.

The SD1330 amplifier is built on 0-10 double sided board; the artwork appears in Fig 3. After etching the board, install rivets at the RF and dc grounds. To mount the device, drill a hole in the PC board the size of Q1's macro-X case. This allows all four leads to be soldered to the microstrip without bending them.

The idling current for this amplifier should be set to 5 mA or less for good noise figure. The idling current is kept constant for different transistors and over different voltages and temperatures by current-limiting resistors Rl and R2 and Zener diode Dl. Tune the input trimmer for best NF or maximum gain if an NF-measurement setup isn't available.

Amplifier No. 2: 10 mW In, 100 mW Out

The SD1333 transistor, a macro-X plastic-packaged device used in this design, delivers 100-125 mW. This device is capable of a reasonable noise figure (2-3 dB) and good dynamic range, which allows it to be used as a second stage (following a GaAsFET preamplifier) in a receiving system. (Motorola's BFR96/MRF961/MRF962 also work well in this circuit; the BFR96 has slightly less gain.) Fig 4 shows the amplifier schematic and Fig 5 shows the full-scale artwork.

Zener-diode bias is used for simplicity and some temperature compensation. Set the quiescent current to 40-50 mA (not critical) by varying R1. A pot can be used initially, then the pot can be replaced by a fixed-value resistor. Or the collector voltage can be varied slightly.

After the rivets are installed in the PC board, drill a hole the diameter of Q1's molded package in the PC board. Mount the device in the board so its unbent leads are soldered directly to the microstrip board. Use the small variable capacitors to tune for maximum gain.

Amplifier No. 3: 9 dB Gain, 250 mW Out

This unit is a slightly higher-power version of the previous amplifier, using an SD1359 or Motorola TRF559 plastic-packaged device. The artwork and schematic are identical to that of Amplifier No. 2. Idling current, 40-50 mA, can be optimized by adjusting the collector supply between 10 and 13 V to set the stage gain.

After the PC-board rivets are installed, drill a hole in the PC board to accept Q1. Mount the device in the board so its unbent leads are soldered directly to the microstrip board. Tuning is as discussed with Amplifier No. 2.



Fig 6—Schematic of the MSA 0204/MC5809L amplifier.

C7, C9—100-pF chip.
C8, C10—0.01-µF ceramic disc.
FL1—Two-stage Toko helical filter (Digi-Key no. TK23318).
RFC1—8 turns of no. 24 enam wire, 0.1 inch ID, closewound.
RFC2—1-µH molded choke.



Fig 7—The 200-mW-output MSA 0204/MC5809L amplifier. In this prototype, I used MSA 0204 stages before and after the helical filter to provide addiional gain. The biasing components (the 7808 and associated parts) are mounted on the outside of the enclosure for convenience.



Fig 8—Full-scale PC-board artwork for the 200-mW amplifier. Black areas represent unetched copper foil.

Amplifier No.4:0.8 mW In, 200 mW Out

The amplifier shown in Figs 6 and 7 is a high-gain unit that can be used to follow the output of your 903-MHz transmit mixer. An Avantek MSA 0204 or Mini-Circuits MAR-2 MMIC is used for the first stage, followed by a Toko two-stage helical filter.[10] (In the prototype amplifier shown in Fig 7, I used two MMIC stages, in addition to the helical filter, before the final stage.) The output stage is an NEC MC5809L thick-film hybrid module. This NEC hybrid module is one of four such units intended for hand-held cellular telephones operating in the 800- to 960-MHz range. The MC5809-series amplifiers are rated at 150 mW minimum power output at 7.5 V dc. Using a more readily available power source (a 7808 regulator), the NE5809s I tried were linear at over 200 mW output. These hybrid amps are easy to use and are stable into any load.

The full-scale PC-board artwork is shown in Fig 8. The helical filter is used between stages to clean up the transmitter signal by filtering out the local-oscillator and image frequencies, but isn't required for applications where such filtering is done in other stages. A three-stage Toko filter[11] will also fit on the board, and could be used for better filtering. The filter leads are bent to the side to allow soldering to the PCboard traces. See Fig 9 for parts placement.

This amplifier is easy to build and get working. Because both active stages and the filter are designed for 50 Ω in and out, the amplifier uses 50-Ω microstrip throughout. No trimmer capacitors are needed and no bias adjustments are necessary—just apply the dc voltages and the drive signal, and peak the helical filter for maximum power output at 903 MHz!

Because more gain is available from this design than I needed, I tried mixing two signals at the input of the first stage. Using a T connection at the input of the first stage, I used the circuit to mix a 759-MHz local oscillator with a 144-MHz IF signal. The 903-MHz output signal was about 175 mW and was fairly clean. Using MMIC amplifiers for gain blocks, almost anything can be used as a mixer!

Amplifier No. 5: 35 mW In, 350 mW Out

The amplifier shown in Fig 10 is practically as simple as an MMIC amplifier. The transistor, an SD1598, produces more than 350 mW output when mounted in a 50-Ω line. The SD1598 (originally another part number) was designed by Bill Olson, W3HQT, years ago, when he was employed by Solid State Microwave (now SGS-Thomson Microelectronics). I've used this transistor, which I refer to as a "hot 2N3866," in amplifiers and frequency multipliers at frequencies from 144 MHz to 3.3 GHz. The SD1598 is in a studded package and the SD1598-1 is a studless package; either style is suitable for use at 903 MHz. I've built two-stage SD1598 amplifiers with 50-Ω lines that work from 400-1300 MHz. Such a two-stage amplifier fits nicely into a 1.5 × 3.6 × 1-inch Bud CU-123 die-cast box. Gain is 10 dB per stage at 903 MHz and 8-9 dB per stage at 1296 MHz.

PC-board artwork isn't necessary for this amplifier, as the 50-Ω line can be easily made on a piece of G-10 PC board using an X-ACTO knife and a straight edge. A 50-Ω line on 0-10 PC board is about 0.1-0.11 inches wide. After cutting the edges of the 50-Ω line, cut another line about a quarter inch from, and parallel to, the 50-Ω line on each side of the 50-Ω line. Using a soldering iron, heat the quarterinch-wide strips between the 50-Ω line and the outer sections and remove them with the knife or a needle-nose pliers. Leave some copper near the transistor for connecting Ql's emitter leads to the microstripline.

Drill a hole in the board for the transistor such that the leads of the transistor can be soldered flush to the microstripline and ground foils. This is important: Excessive lead lengths drastically reduce the gain of this amplifier. Attach a small heat sink to the stud of the device.

The SD1598 can be powered by a 12- to 18-V supply, depending on the gain and power output required. Use an LM317T voltage regulator in the power supply, and vary the voltage to set the gain of this lowlevel stage. This is an easy way to match the drive levels needed by the following stages.

Set Ql's quiescent current, I_{cq}, to 30-50 mA. Vary Rl to get the correct idling current. This bias current is not critical, and depends on the device and the collector voltage used. Tune up is simple: Adjust C8 for maximum power output.

Amplifier No. 6: 100 mW In, 1 W Out

A pair of SDl598s and a Wilkinson power divider/combiner combination are used in this design. The schematic for the combined amplifier is shown in Fig 11, and the PC-board artwork is shown in Fig 12. I didn't make an effort to terminate the 75-Ω Wilkinson divider/combiner; the amplifier works fine as is. Power sharing between the two devices is excellent, and a 3-dB improvement in power output is available over a single device. Saturated power output is well over 1 W.

The supply voltage and idling currents are the same as single-device Amplifier



Fig 9—Parts-placement diagram for the 200-mW amplifier. All parts are mounted on the foil side of the board. Note the locations of rivets. At each V_{cc} lead on the MC5809L (pins 5 and 9), install a 100-pF chip capacitor and a 0.01-µF disc to ensure proper bypassing.



Fig 10—The 350-mW amplifier. Glue D1 to Q1's ceramic body for thermal composition.

C6—0.001-µF feedthrough.
C8—0.6- to 8-pF Johanson piston trimmer.
D1—1N4001.
Q1—SD1598.
R1—1.5-1.6 kΩ, ½ W.
RFC1, RFC2—8 turns of no. 26 enam wire, closewound, 0.1 inch ID.


FB
R1
FB
RFC2
C6
+14 – 18 V
D1
100 pF
chip
C2
100 pF
chip
C3
C5
0.01 µF
C7
10 µF
35 V
RFC1
RFC3
Q1
E
B
C
SD1598
E
C8
TUNE
C1
50-Ω
INPUT
100 pF
chip
C4
50-Ω
OUTPUT
100 pF
chip
Q2
C9
TUNE

Fig 11—The 2x SD1598 amplifier. Glue D1 to Q2's ceramic body for thermal composition.

C8, C9—0.6- to 8-pF Johanson piston trimmer.
D1—1N4001.

Q1, Q2—SD1598.
R1—1.5-1.6 kΩ, ½ W

RFC1, RFC3—8 turns of no. 26 enam wire, closewound, 0.1 inch ID.



Fig 12—Full-scale PC-board artwork for the 2x SD1598 amplifier. Black areas represent unetched copper foil.


100 pF
chip
C2
R1 100 Ω
FB
R2
FB
RFC3
C6
+15 – 18 V
C3
0.01 µF
C4
100 pF
chip
C5
10 µF
35 V
D1*
1N4001
RFC1
RFC2
Q1
C7
C1
50-Ω
RF INPUT
50-Ω
RF OUTPUT
Z1
100 pF
chip
Z3
Z5
100 pF
chip
Z6
Z2
Z4
E
B
C
* See caption.
SD1598, SD1598-1
E

Fig 13—The 500-mW broadband amplifier. For power levels over 500 mW output, glue D1 to Q1's ceramic body for thermal compensation. RFC1 and RFC2 are implemented as PC-board traces.

Q1—SD1598 or SD1598-1.
R2—1.5-1.6 kΩ, ½ W

RFC3—8 turns of no. 28 enam wire, closewound, 0.1 inch ID.

Z1-Z5—Microstriplines. See text and Fig 14.

No. 5 (Fig 10). If this amplifier is mounted in a die-cast box, no additional heat sinking is required; If not, a small heat sink should be attached to the stud of each device. Adjust C8 and C9 for maximum power output.

Amplifier No.7: 12dB Gain, 500mW Out

The amplifier shown in Fig 13 is a broadband design that's been around for about 6 years. Bill Olson, W3HQT, designed it as a 1296-MHz amplifier. (The 1296-MHz version differs in that it has a small piston trimmer on the output circuit, about an inch from Qi's ceramic cap.)

This amplifier is a very versatile design; it works from 900-1300 MHz and has a power gain of 10-13 dB over this range. I built two test amplifiers for this design: one for the studded transistor and one for the flanged version. Over a dozen different devices were tried in these test circuits, both at 903 MHz and at 1296 MHz. Classes A, AB, C and pulsed-class-C operation were all tried, and all worked well.

The studded SD1598 is used in this design. Full-scale artwork appears in Fig 14; Fig 15 shows parts placement. As with the other designs, rivets are used at all dc and RF grounds. After the rivets are soldered in place, drill a hole in the board for the device. Trim Q1's leads with scissors, then solder them directly to the microstriplines and ground foils. If the amplifier is to be mounted in a die-cast box, the box will provide sufficient heat sinking. If you use another mounting method, attach a small heat sink to Q1's stud.

Power output for SSB is 500 mW, and

Fig 14—Full-scale PC-board pattern for the broadband 500-mW SD1598 amplifier. Black areas represent unetched copper foil.




+Vcc
housing wall
C7
C5
R1
FB
R2
FB
RFC3
C2
RFC2
RFC1
C3
C4
Q1
C7
INPUT
OUTPUT
C1
D1
Rivets

Fig 15—Parts-placement diagram for the broadband 500-mW SD1598 amplifier. The PC-board edges are not shown. All components are mounted on the foil side of the PC board (except those mounted to the enclosure).


C2
100 pF
chip
R1
100 Ω
1/2 W
FB
R2
FB
RFC1
RFC2
100 pF
chip
C3
D1
C5
FB
R3
FB
100 pF
chip
100 pF
chip
C6
C8
0.01 µF
RFC5
+14 - 18 V
C10
C9
10 µF
35 V
RFC4
RFC3
Q2
E
B
C
E
SD1598, SD1598-1
C12
TUNE
Q1
50-Ω
INPUT
C1
100 pF
chip
C11
TUNE
C4
100 pF
chip
C7
100 pF
chip
50-Ω
OUTPUT
Q3
C13
TUNE

Fig 16—The two-stage, 1-W SD1598 amplifier. Glue D1 to Q2's ceramic body for thermal compensation.

C10—0.001-µF feedthrough.
C11, C13—0.6- to 8-pF Johanson piston trimmer.
Q1—SD1598 or SD-1598-1.
Q2, Q3—SD1598.
R2, R3—1.5-1.6 kΩ, ½ W.
RFC1-RFC5—8 turns of no. 24 enam wire, closewound, 0.1 inch ID.



Fig 17—Full-scale PC-board pattern for the two-stage, 1-W SD1598 amplifier. Black areas represent unetched copper foil.

up to 1 W for CW and FM, depending on the device. In applications where the device will deliver over 500 mW, a IN4001 (DI) diode can be glued to Q1 for thermal stabilization, as shown pictorially in Fig 15. Power gain at 1 W output is 7 dB or so. By varying R2, set Q1's I_{cq}, for 30-50 mA for power levels up to 500 mW, and 15-20 mA for higher levels.

For low-level stages (up to 200mW out), you can use the SD1598-1 studless part in this circuit. Solder the studless device to the microstrip, then solder a piece of hobby brass to the device's gold-plated bottom area and to the ground plane. This provides enough heat sinking to dissipate a few hundred milliwatts.

At 903 MHz, no output trimmer capacitor is required. Some improvement in the output match can be achieved by trimming the width of the output line by a few thousandths of an inch with an X-ACTO knife.

Amplifier No. 8: 10 mW In, 1 W Out

A second 1-watt amplifier, this one using a pair of SD1598's driven by a single SD 1598, is shown in Fig 16. This design is similar to that of Amplifier No.6, with the addition of a driver stage. The artwork appears in Fig 17.

For the driver transistor, you can use an SD1598-1 studless device, as Q1 must provide only a hundred milliwatts or so. The driver is mounted in a hole in the PC board. A small piece of brass shim stock is soldered to the bottom of the device and to the ground-plane side of the PC board for heat sinking.

This amplifier runs on 14-18 V dc. The idling current for each device is around 30-50 mA. Again, the supply voltage can be provided by an LM317T regulator. Adjust R2 and R3 to individually set each device's idling current. Then, tune the amplifier by adjusting C11, C12 and C13 for maximum output. Vary the supply voltage to optimize the required power output or gain.

The 2.4 × 4.4 × 1-inch Bud CU-124, or an equivalent die-cast box, is a suitable enclosure for this amplifier. Mount the connectors on the ends of the box, and place the amplifier PC board inside the box body, instead of on the inside of the cover. The box provides sufficient heat sinking for this amplifier.

Next month, I'll describe three more 903-MHz linear amplifiers, including two 4-W units.

Notes

[1] D. Mascaro,"A 759-MHz Local Oscillator," *QEX*, May 1988, pp 12-15.

[2] No-tune transverters, as well as antennas and microwave components, are available from Down East Microwave, Box 2310, RR 1, Troy, ME 04987, tel 207-948-3741. Catalog available.

[3] The amplifiers in this article use transistors manufactured by SGS-Thomson Microelectronics, 211 Commerce Dr, Montgomeryville, PA 18936, tel 215-362-8500.

[4] Mouser Electronics, 2401 Hwy 287 N, Mansfield, TX 76063, tel 817-483.4422. Catalog available.

[5] Microwave Components of Michigan, 17141 Merriman, Romulus, MI 48174, evening tel 313-753-4581. Parts list available.

[6] RF Parts, 1320 Grand Ave, San Marcos, CA 92069, tel 619-744-0728.

[7] SGS-Thomson Microelectronics transistors are available through RF Gain Ltd, 100 Merrick Rd, Rockville Center, NY 11570, tel 800-645-2322. $50 minimum order.

[8] Frontier Microwave, RD 1, Box 467, Mink Rd, Ottsville, PA 18942, evening tel 215-795-2648.

[9] D. Mascaro,. "A Transverter Band-Switching Display and Universal Power Supply," *QEX*, Aug 1987, pp 8-14.

[10] Available from Digi-Key Corp, 701 Brooks Ave South, PO Box 677, Thief River Falls, MN 56701-0677, tel 800-344-4539. Catalog available.

[11] Toko filters and other components are available from Steve Kostro, N2CEI, Box 341A, RD 1, Frenchtown, NJ 08825, evening tel 201-996-3584. Parts list available.

By Dave Mascaro, WA3JUF **From *QST*, July 1990**

903-MHz Linear Amplifiers

Part 2—Did you like the projects in Part 1? Here are three more amplifiers to suit your 903-MHz, 50-ohm gain-block needs.

In Part 1, I covered construction methods for building the 903-MHz linear amplifiers described in this twopart series. The amplifiers described this month cover a higher power range than those in Part 1, starting with a 2-W-output design, and finishing with a pair of 4-W output units (one with 13 dB gain, the other with 23 dB gain).

Amplifier No. 9: 100 mW In, 2 W Out

The transistor used in this amplifier, an SD1853, is a class-A device in a "strip-pac" flanged package. The PC-board artwork is shown in Fig 18, and the schematic appears in Fig 19. The parts-placement



Fig 18—Full-scale PC-board pattern for the 2-W SD1853 amplifier. Black areas represent unetched copper foil.


FB
D1
FB
RFC3
C7
R1
+21 – 23 V
C2
100 pF
chip
C3
0.01 µF
C4
100 pF
chip
C5
0.01 µF
100 pF
chip
C6
0.001 µF
FT
C8
100 µF
35 V
RFC1
RFC2
Z3
Z4
Q1
C9
Z5
Z1
C1
Z2
50-Ω
INPUT
100 pF
chip
50-Ω
OUTPUT
100 pF
chip
C11
OUTPUT
TUNE
E
B
C
E
SD1853
C10
INPUT
TUNE

Fig 19—The 2-W SD1853 amplifier. RFC1 and RFC2 are implemented as PC-board traces.

C10, C11—0.3- to 3-pF Johanson piston trimmer.
D1—1N4747A 20-V, 1-W Zener.
Q1—SD1853.
R1—2-3 Ω, 1 W.
RFC3—8 turns of no. 26 enam wire, closewound, 0.1" ID.
Z1-Z5—Microstriplines. See text and Fig 18.


housing wall
C8
R1
+ V_{CC}
C7
FB
D1
FB
C6
C2
C10
C4
RFC3
C3
RFC1
RFC2
C5
C1
C9
INPUT
OUTPUT
C11
Q1
Rivets

Fig 20—Parts-placement diagram for the 2-W SD1853 amplifier. The PC-board edges are not shown. All components are mounted on the trace side of the PC board (except those mounted to the enclosure).



Fig 21—The prototype 2-W amplifier.

diagram is shown in Fig 20, and a photo of my prototype appears in Fig 21.

After the board is etched and rivets are installed, cut a hole and file its edges to accept Q1's flange. The SD1853 must be mounted to a heat sink. (A Bud CU-124 or equivalent die-cast box is adequate.) Use a piece of G-10 PC board between the amplifier board and the heat sink, to allow the device to be mounted flush to the microstrip. The device flange is the emitter, and a low-inductance ground connection is a must. Make this connection by using a piece of copper-foil tape soldered to the microstrip ground plane and placed between Q1's flange and the heat sink. Mount the transistor to the heat sink with no. 4-40 screws. Use heat-sink compound between Q1 and the heat sink.

An LM317T (or LM317K) adjustable regulator can be used to supply the voltage required by this amplifier. Use a 10-turn pot for the ADJUST control; smooth adjustment of the supply voltage to this amplifier is a must. Insert a milliammeter in series with current-limiting resistor R1, and slowly adjust the regulator output up from minimum until the idling current is 200-225 mA without RF drive applied. The exact supply voltage depends on the beta of

Fig 22 (below)—The 4-W, 2 x SD1853 amplifier.
C4-C6—0.3- to 3-pF Johanson piston trimmer.
D1—1N4747A 20-V, 1-W Zener.
Q1, Q2—Sd1853.
R1—2-3 Ω, 1 W.
RFC1, RFC2—8 turns of no. 26 enam wire, closewound, 0.1" ID.
Z1-Z5—Microstriplines. See text and Fig 23.


D1
1N4747A
FB
FB
R1
+21 - 23 V
C2
100 pF
chip
RFC1
100 pF
chip
C3
C7
0.01 µF
C9
0.001 µF
FT
C10
10 µF
35 V
RFC2
Q1
C4
INPUT
TUNE
C6
OUTPUT
TUNE
50-Ω
INPUT
C1
100 pF
chip
C8
100 pF
chip
50-Ω
OUTPUT
Q1
C5
INPUT
TUNE


housing wall
C10
+Vcc
R1
C9
C2
FB
FB
D1
RFC
C4
C7
C3
RFC
C6
C5
INPUT
C1
OUTPUT
C8
Rivets

Fig 23—Parts-placement digram for the 2 x SD1853 amplifier. The PC-board edges are not shown. All components mount to the trace side of the PC board (except those mounted to the enclosure).

Q1, the value of R1, and D1's breakdown voltage. Idling current can be adjusted slightly to optimize gain and/or power output. The supply voltage must be removed during receive to minimize device heating.

Tune-up is simple. Apply drive and tune C10 and C11 alternately for maximum power output. If you have access to a return-loss bridge or network analyzer, you may want to trim the width of Z2 to improve the input return loss. Verify stability (as indicated by no output and no change in supply current) by tuning the trimmers through their ranges with no input signal applied.

Amplifier No. 10: 200 mW In, 4 W Out

This high-gain design consists of a pair of SD1853s combined in a Wilkinson power divider/combiner. As before, I made no effort to terminate the 75-Ω Wilkinson divider/combiner with balancing resistors. It worked just fine without them. Even the 1296-MHz version, which uses the same board layout, worked well in this configuration.

Fig 22 shows the schematic of this class-A amplifier, and Fig 23 shows parts placement. The PC-board pattern, the same



Fig 24—This prototype 4-W amplifier was built on a PC board with a spare driver stage that's bypassed with a brass strip.



Fig 25—The 4-W amplifier's heat sink, bolted directly to the devices, must be positioned such that cooling air can flow over it during amplifier operation.


D1
1N4747A
FB
FB
R3
+21 – 23 V
C10
0.001 µF
FT
C11
10 µF
35 V
100 pF
chip
C7
C9
0.01 µF
RFC4
C5
100 pF
chip
RFC3
+12–
15 V
100 pF
chip
C2
R1
100 Ω
1/2 W
FB
R2
FB
C3
100 pF
chip
RFC3
Q1
RFC2
C1
C6
50–Ω
INPUT
100 pF
chip
C4
DRIVER
TUNE
100 pF
chip
Q2
C12
INPUT
TUNE
C14
OUTPUT
TUNE
C8
100 pF
chip
50–Ω
OUTPUT
Q3
C13
INPUT
TUNE

Fig 26—The two-stage, 4-W, SD1598/SD1853 amplifier.
C4, C12-C14—0.3- to 3-pF Johanson piston trimmer.
D1—1N4747A 20-V, 1-W Zener.
Q1—SD1598.
Q2, Q3—SD1853.
R2—1.5-1.7 kΩ, ½ W. See text, Part 1, June 1990 *QST*, p 24.
R3—1-2 Ω, 2 W.
RFC1-RFC4—8 turns of no. 26 enam wire, closewound, 0.1" ID.

as that for Amplifier No. 8, is shown in Fig 17 (shown in Part 1). The board's driver-stage traces are by-passed with a brass strip in this amplifier. Fig 24 shows my prototype mounted in a PC-board enclosure. A single base-bias source, using a current-limiting resistor and Zener diode, feeds both devices. Total idling current, measured in series with R1, is 400-450 mA.

The same mounting arrangement used with the single-SD1853 amplifier (Amplifier No. 9) applies to this unit. The device flanges must have low-inductance ground connections. Mount the transistors to a heat sink about 2 × 3 inches with ½ inch or taller fins, as shown in Fig 25. Again, the supply voltage is switched on only during transmit. To tune this amplifier, adjust C4, C5 and C6 alternately for maximum output.

Amplifier No. 11: 20 mW In, 4 W Out

A second 4-W amplifier, using a pair of SD1853s driven by a single SD1598, is shown in Fig 26. The final stage is Amplifier No. 10, and the driver is the same as that used in Amplifier No. 8. The PC-board artwork is shown in Fig 17; the parts placement can be done using Figs 23 and 16 as guides.

The power-supply and bias adjustments are the same as those for the previously described amplifiers using these devices. Transistor mounting is also the same as before, but extra heat sinking is required with this unit because of the class of operation and the power output.

Higher Power Output

Higher-power devices usable at 903 MHz are available from several manufacturers. NEC's NEL1320 (2SC3542) produces 18-20 W linear output at 903 MHz. These devices also work on the 1296-MHz band. These transistors, as well as single- and dual-stage amplifiers based on them, are available from Down East Microwave (DEM). (The DEM two-stage 3318PA runs around 18 W output for about 1 W input).

SGS-Thomson Microelectronics also makes high-power devices for the 800- to 960-MHz range. For example, the SD1423 is a 4-W-in, 30-W-out class AB device, and the SD1660 is a class-AB transistor that runs a whopping 120 W output for about 35 W drive. Both of these devices run on 28 V dc.

Summary

As I've shown in this two-part series, there's really nothing difficult about building your own 903-MHz equipment—from the local oscillator to the final amplifier. This ease of construction is a vast improvement over what it was just a few years ago—and the 903-MHz band's population has grown as a reflection of that. See you on the microwaves!

By Dave Mascaro, WA3JUF **From *QST*, August 1988**

25-Watt Linear Amplifiers for 144 and 200 MHz

Do you need more punch from your hand-held or portable rig for 2 meters or 220 MHz? These little amplifiers can supply it!



Many hams have 2-meter and 220-MHz hand-held rigs and low-power portable SSB rigs these days. Unfortunately, many of these radios have limited usefulness because of their low power output. Also, as hand-held radios get smaller, so do the NiCd packs that power them—a few long-winded transmissions on high power and the battery is dead! The low-power mode is usually good only for short-range simplex operation, or repeater use when you're close to the repeater. High-capacity battery packs are available for most hand-held rigs, but using them takes away the size and weight advantage of today's smaller hand-held transceivers. Some rigs offer the option of removing the battery pack and plugging the unit directly into 12-V dc, which gives you a small, lightweight rig, but you're still stuck with relatively low power.

The solution to this problem is the addition of a linear amplifier. An amplifier after the hand-held transceiver or portable rig that can give you 25 to 30 W of output power (depending on the output of the driving rig) without imposing large weight, cost and current-drain constraints is a great addition to your VHF station. An amplifier also allows you to use the same low-powered rig in the house and in the car with high power output. You can mount an amplifier under the seat or in the trunk of your car, and minimize the possibility of theft by taking the radio with you when you leave the car.

Amplifier Design

The amplifiers described in this article are capable of 25 to 30W of RF output for the drive power available from common handheld and portable rigs. The 2-meter and 220-MHz designs are so similar that we can describe them both in one discussion. The differences in the designs are covered in detail. Design, assembly, tuning and use of the amplifiers is virtually identical for both versions. Both versions even use the same PC board! (Note that two different boards are shown in the lead photo—they were prototypes of the fmal board design.)

Receiving preamplifiers are included in both units. They, too, are quite similar, differing only in some component values.

This power amplifier uses a single SD1274 bipolar transistor manufactured by Thomson Components/Mostek Corp.[1] The device is operated class AB for all-mode operation. Nominal dc power-supply voltage is 13.8. The amplifier will operate on any dc supply voltage between 12 and 14.5 (the typical automobile supply voltage range).

The main amplifier PC board is a microstripline design on standard $^1/_{16}$-inch-thick, double-sided, G-10 fiberglass-epoxy board. Input and output tuning capacitors are provided for maximizing gain and power output in a given band segment. If desired, the amplifiers can be tuned for broadband operation with only a slight reduction in power output across the operating frequency range.

The 2-meter and 220-MHz amplifiers are narrow-band designs. The 2-meter version gives 25 W output for 2 W of drive from 138 to 150 MHz, with a single tuning setting. When tuned for narrow-band operation, the amplifier gives about 20 W output for 1 W of drive. With the Kenwood TH-21AT on high power, my 2-meter amplifier puts out 25 W. On low power, I can adjust the amplifier for a maximum narrow-band gain, which gives about 7 to 8 W output. Efficiency is 50 to 60%, depending on tuning and power output.

The tuning range of the 220-MHz amplifier is 200 to 230 MHz. When tuned for narrow-band operation, the amplifier gives about 16 W output for 1 W of drive. Driving the amplifier with my ICOM IC-3AT on high power (about 1.5 W), the amplifier puts out 20 W. With the IC-3AT on low


S1
MODE
FM
SSB
C1
R4
TX
D3
K1A
DS1
J2
TO
KEY LINE
OR INVERTER
(SEE INSET)
R1
Q2
MPS-A13
KEYING
D2
D1
C2
R2
SSB
DELAY
R3
RFC 6
5A
+13.8 V
C24
C25
C27
D5
C20
C18
C19
C3
C5
J1
XCVR
RFC 1
C4
K1B
C8
INPUT
TUNE
RFC 3
C15
C16
R9
RFC 5
SD1274
Q1
FILTER
TUNE
C23
K1C
C26
L3
FILTER
TUNE
J3
ANT
C34
C35
FILTER
C36
RFC 2
C9
C10
C12
C13
C17
C21
C22
RFC 4
PA
C7
C6
U1
BIAS REG
LM317T
FB
C14
R7
R8
IN
OUT
ADJ
R6
D4
R5
BIAS
ADJ
C11
Q2
E
B
C
U1
LM317T
ADJ
VIN
VOUT
E
B
C
Q1
E
2N2222
TO J2
3 kΩ
+8 TO 12 V
ON TX
3 kΩ
k=1000
KEYING INVERTER

Fig 1—Schematic of the 25-W VHF amplifiers. The 5-A fuse is included in the power lead (external to the amplifier). Be extremely careful when mounting the power transistor—see text for precautions. In the parts list below, values for the 220-MHz version are given in parentheses where they differ from those in the 2-meter version. Asterisks indicate parts not used in the 220-MHz version.

C1—15-µF, 6-V dc.
C2—470-pF disc.
C3—2-pF silver mica.
C4, C23, C26—270- to 470-pF silver mica or Unelco.
C8—270- to 470-pF (100 pF) silver mica or Unelco.
C5, C7, C14, C16, C19, C24—0.01-µF disc.
C6—0.22-µF disc.
C9—43-pF silver mica or Unelco.
C10—Arco 404—4 to 60 pF (Arco 403—4 to 40 pF).
C11, C15—1-µF, 15-V tantalum.
C12—180-pF (120-pF) Unelco.
C13, C18—220-pF Unelco.
C17—68-pF (51-pF) Unelco.
C20—10-µF, 35-V electrolytic.
C21*—33 pF silver mica or Unelco.
C22—Arco 404—4 to 60 pF (Arco 402—1.5 to 20 pF)
C25—0.1-µF disc.
C27—0.001-µF disc.
C34, C35—25-pF (18-pF) Unelco.
C36—10-pF trimmer.
D1, D2—1N4148 or 1N914.
D3, D4—1 N4001 or equiv.
D5—ECG 581 or equiv.
DS1—LED.
FB—Ferrite bead.
K1—Omron LZN2O3-UA-DC12 DPDT relay.
L3—3 turns (1 turn) no. 18, closewound, 0.2-in. (¼-in.) ID.
Q1—Thomson/Mostek SD1 274.
Q2—MPS-A13 NPN Darlington.
R1, R4—1.5-kΩ, ¼ W.
R2—500-kΩ, 10-turn potentiometer.
R3—10-kΩ, ¼ W.
R5—100-Ω miniature potentiometer.
R6—270-Ω, ¼ W.
R1, R8—10-Ω, ½ W.
R9*—15-Ω, ¼ W.
RFC1, RFC2, RFC4—0.47-µH molded choke.
RFC3*—0.15-µH molded choke.
RFC5—6 turns (5 turns) no. 16 enam, ¼-in. ID.
RFC6—VK200/4B ferrite choke.
S1—Miniature SPDT toggle.
U1—LM317T voltage regulator

Miscellaneous
2 BNC or N connectors (see text).
4 × 4 × 1½-in, heat sink.
5-A fuse and in-line holder.
2 × 1-in, scrap of thin sheet brass.

power (about 150 mW), I can tune the amplifier to give 4W output. Efficiency is about the same as the 2-meter version.

The saturated power output for both versions is more than 35 W in FM operation. The maximum FM power input is 4 W. Minimum power input for proper RF sensed keying operation is 100 mW.

The Power-Amplifier Circuit

See Fig 1. K1 is similar to relays used in VCR RF circuits. I have switched up to 40 W at 2 meters and 35 W at 220 MHz with these relays. They present a good match to 50 Ω. The loss through the amplifiers (when not in use) resulting from these relays is less than 1 dB. This is typical for 2-meter and 220-MHz amplifiers.

In addition to switching the transmitted and received signals, the relays also switch the dc supply voltage. In the transmit mode, K1 switches 13.8 V dc to the input of the bias regulator, U1. The regulator IC and its associated resistors (R7, R8) and bias diode (D5) supply a stiffer bias voltage to the base of Q1 than the more-common voltage-divider bias networks. This low-impedance bias source keeps the bias voltage constant over the range of RF drive levels. With a voltage-divider bias network, bias voltage can be upset by the base-emitter rectification (self bias) developed by the RF driving signal. In such a case, over-driving the amplifier causes the base bias to decrease, resulting in non-linear amplification. This effect is limited with the regulator-type bias



Fig 2—Main PC-board layout for the 2-meter and 220-MHz amplifiers. Artwork is full scale. Because this is a microstripline design, do not change the geometry or routing of board traces. The board must be drilled for rivets, mounting hardware and transistor mounting at the locations marked. The transistor-mounting hole is 0.38-in. diam and should be drilled at the + near the center of the PC board. All other holes (except for the relay-mounting holes near the output microstripline) are for rivets and no. 4-40 mounting hardware.

circuit used in these amplifiers.

TR switching is accomplished by an RF sensing circuit. A small amount of RF is sampled by C3 and rectified by D1 and D2, which turns on keying transistor Q2. Q2 pulls in K1, which switches the amplifier into the line.

When S1 is in the SSB position, a short drop-out delay is added in the RF-sensed-keying circuit to keep the amplifier keyed during brief pauses in speech. This delay is adjustable by varying R3. In the FM position, no delay is needed. S1 does not change the class of operation of Q1—it merely switches in the delay circuit.

The switching relays are wired so the amplifier can remain in-line at all times, with or without the supply voltage connected. Applying the supply voltage allows you to use the amplifier and preamp. Without the supply voltage connected, all transmitted and received signals pass through the amplifier.

The spectral output of these amplifiers is quite good, but to ensure clean signals, I've added filters to the output of each unit. Although there isn't much extra room for the filter components inside the amplifier cabinet, you can mount them on the back cover or in another small enclosure. The filters, shown in the title photo, are very simple to build and tune.

Construction

Each amplifier consists of two PC boards: the power-amplifier board and the preamp board (if used). After the PC boards are etched, holes are drilled with a no. 50 bit for installation of tinned grounding rivets at all RF and dc grounds (see Fig 2).[2] Install the rivets on the board as follows: After inserting the rivets, flare the inserted end with an awl. Next, flatten the rivet by tapping it lightly with a hammer, using an anvil or other solid surface under the PC board as a support. Solder the rivets on both sides of the PC board. Alternatively, pieces of wire can be soldered through the board—but because the wires will not be flush with the board, mounting the heat sink may be difficult.

Drill the holes for Q1 and the board-mounting screws as indicated in Fig 2. No holes are needed for component mounting because all parts are mounted on the trace side of the PC board. All the components except the preamp board are mounted next. (The preamp board is mounted after the amplifier has been tested, to prevent possible damage to the preamplifier.) Connect a piece of miniature 50-Ω Teflon® or RG-58 coaxial cable between K1 and the amplifier-input microstripline (see Fig 3).

After drilling or milling holes for Q1 in a suitable heat sink (see Fig 4), tap the mounting holes in the heat sink for no. 4-40 hardware, and mount the PC board to the heat sink. Trim the four leads of Q1 to about half their original length to make mounting easier.

Q1 can be mounted in one of several ways. The distance between the underside of the leads of Q1 and the heat-sink mounting area of Q1 is larger than the thickness of $^1/_{16}$-in. G-10 board material. Because of this, the heat sink must be milled (see Fig 4), or small pieces of copper or brass must be soldered under each lead of Q1 to make up the difference in height. Alternatively, a second piece of G-10 material can be cut to the same size as the amplifier PC board



Fig 3—Parts-placement diagram for the VHF amplifiers. All parts are mounted *on the foil-trace side* of the PC board. The power-transistor mounting stud passes through the board and into the heat sink. D5 is epoxied to the ceramic cap of Q1. R2 (10-turn potentiometer) is epoxied to the PC board as indicated, with the pins facing up.0

and used as a spacer between the PC board and heat sink.

Be careful not to crack the body of Q1 where the leads of the device meet it—this can release beryllium-oxide (BeO) dust, *which is lethal.* The leads of the transistor can be bent down slightly to the PC board without affecting RF performance, but never force them in the opposite direction after the transistor has been tightened to the heat sink. Mount the transistor to the heat sink *first,* then solder its leads to the board, and *not vice versa.* Use thermally conductive compound between Q1's mounting surface and the heat sink.

Cut a piece of hobby-store sheet brass about as wide as the bias regulator IC and twice as long as the body of the device. This will be a heat sink for the bias regulator. When mounting the regulator IC, use thermally conductive compound between it and the brass sheet, and between the brass and the main PC board. After tightening the IC hardware to the PC board, bend the brass sheet in a U shape over the IC, leaving enough clearance for heat to escape between the IC and the brass heat sink. This heatsink arrangement can be seen near the bottom center of each amplifier in the lead photograph.

The Preamplifier Circuit

The high gain and low noise figure (NF) of a GaAsFET preamp are not necessary in amplifiers in this power class. I designed the preamp circuit (Fig 5) to use an inexpensive U310 FET. It has more than enough gain to overcome the losses of the amplifier switching circuits and the feed line to the amplifier. The preamp has more than 12 dB gain and noise figure of about 2 dB.

When S2 is closed, K2 closes, activating the preamplifier by applying the dc supply voltage to the drain circuit of Q3 and to the preamp ON LED, DS2. In the transmit mode, K1 switches off the supply voltage to K2, allowing K2 to drop out.

The preamp circuit is optional, and I didn't include it on the main amplifier PC board. If you're not going to build the preamp, solder foil-tape or wire jumpers between the two points on the main amplifier PC board where the preamp connects during assembly.

Building the Preamplifier

The schematic of the preamplifier circuit is shown in Fig 5. As mentioned earlier, although some component values differ between the 2-meter and 220-MHz versions, the two are essentially the same in all other respects. Components that have different values for the two versions are marked with asterisks on the schematic and the parts list. Unlike the main amplifier PC board, most preamp components are mounted through the board and soldered on the bottom side. The PC-board layout and parts-placement diagrams are shown in Figs 6 and 7, respectively.

As with most FET VHF preamplifiers, a shield is necessary between the input inductor and the active device. Solder a piece of scrap brass sheet to the ground foil between these circuit elements. (This preamp shield can be seen in the right-hand amplifier in the lead photo, just behind L1.)

After building the preamplifier, tune it



Fig 4—Heat-sink drilling dimensions for the VHF amplifiers. Overall heat-sink size isn't critical, but should be close to the dimensions shown. As an alternative to milling the heat sink to accept Q1, a piece of $^1/_{16}$-in. double-sided PC-board material can be used as a shim. Be careful not to stress the transistor lead-to-body connections during mounting.

for maximum gain with a signal generator or an on-the-air signal. If one is available to you, use a noise-figure meter and tune the preamp for best NF.

Building the Output Filters

I built the output filters for each amplifier on scraps of PC-board material. The construction is shown in the title photo. After building the filters, it's a good idea to use some silicone sealant on the coil (especially in the 2-meter filter) to hold the coil turns in place. Install the filter in a suitable enclosure, or in the amplifier cabinet.

To tune the filters, you'll need a receiver capable of receiving the second harmonic of the fundamental (288 MHz for the 2-meter filter, and 440 MHz for the 220-MHz filter), and a signal generator or an on-the-air signal. Connect the filter between the antenna (or signal generator) and the receiver, and tune C36 for minimum second-harmonic signal level.

Enclosures

I used the main amplifier PC board as the top cover for the unit (with the heat sink mounted on it). I made the sides and bottom cover of the enclosure from PC-board material. The side walls are soldered to the amplifier board, and the bottom cover is attached to the side walls with small brackets (also made of PC-board material) soldered to the bottom cover. Alternatively, the amplifier can be mounted in an aluminum enclosure.

Although I used BNC connectors for RF input and output, N connectors can also be used. Make the connections from the input connector to the PC board with a piece of no. 16 wire or a $^1/_8$-inch-wide strip of brass to the input microstripline. At the output, connect dc-blocking capacitor C26 between the microstripline and the antenna connector. Check the board for proper component placement and good solder joints, and get ready to tune up the amplifier!

Amplifier Tune-Up

As with the amplifier-circuit design and description, the tune-up procedure is very similar for both. The only difference is the exciter you use. Here's how to tune either version.

Disconnect RFC4 from the base of Q1. Connect a voltmeter to the free end of RFC4. Apply 13.8 V dc to the amplifier supply voltage leads. Using the voltmeter, verify that R5 is mounted so that output of U1 increases with clockwise rotation of R5. Turn R5 fully counterclockwise (minimum U1 output voltage). Reconnect RFC4.

Set the quiescent (no-drive) current to Q1 as follows: Disconnect one end of RFC6 and connect an ammeter in series with it. Apply 13.8 V dc to the amplifier through a 5-A fuse. Turn the preamp off. Do not apply RF drive during this adjustment. Using a clip lead, ground the collector of Q2. This should actuate K1. Check the TX LED, DS1, for operation. (If K1 actuates and the TX LED does not light, the LED may be installed in reverse.) Slowly adjust R5 for an idling current (through RFC6) of 75 to 100 mA. The amplifier should be stable; instabilities are indicated by erratic variation of Q1's quiescent current as R5 is adjusted.

Disconnect the ground lead of Q2. Q1's collector current should drop to zero. If the collector current does not drop to zero, the amplifier is unstable. If all is well, remove the ammeter and reconnect RFC6. If the amplifier is unstable, check all bypass capacitors and solder connections.

Apply about 100 mW of drive to the amplifier and check that the COR and delay circuits work properly. Adjust C10 and C22 for maximum power output. Increase drive power and retune for maximum output. After final assembly, tune the amplifier for the desired frequency and power level.

Final Assembly

The preamplifier board can now be installed on the main PC board. Mount the preamp on its edge (refer to the title photo and Fig 3) and solder the input and output microstriplines in place. Solder the ground foil of the preamp board to the ground foil of the main board in a few places to support the preamp board. Connect S2 and DS2 to the preamp board with hook-up wire (see Figs 5 and 6 for connection points). Apply power and check for proper operation of S2, K2 and DS2.

The enclosure can now be painted if you wish. Use masking tape to cover the connectors and heat sink. (Mount the LEDs and switches after painting.) You may want to

Fig 5—Schematic of the preamplifier circuit. K2 is identical to K1 on the main amplifier board. S2 and DS2 are mounted on the front panel of the amplifier. In the parts list below, values for 220-MHz version are given in parentheses where they differ from those of the 2-meter version.

C28, C29, C33—0.01-µF disc.
C30—2-pF silver mica.
C31, C32—20-pF trimmer.
DS2—LED.
D6—1 N4001.
L1, L2—5 turns (4 turns) no. 16 enam, 0.3-in. ID.
K2—Omron LZN2O3-UA-DC12 DPDT relay.
Q3—U310 FET.
R10—1.5-kΩ, ¼ W.
R11—91-Ω, ¼ W.
RFC7, RFC8—0.47-µH molded choke.
S2—Miniature SPDT toggle.

Miscellaneous
1 × ½-in. strip of thin sheet brass





Fig 6—Full-size PC-board layout for the preamplifier circuit. Unlike the power-amplifier PC board, most of the preamplifier components are mounted on the non-trace side of the board.



Fig 7—Parts-placement diagram for the VHF preamplifier. Mount all components on the unetched ground-plane side except for C30 and C31. Use a drill to clear the foil away from all mounting holes on the ground-plane side of the board (except for through-board ground connections). Solder all ground connections on both sides of the PC board (see text for rivet-installation instructions). Solder a brass-strip shield to the ground foil between L1 and Q3 on the component side of the PC board.

add stick-on rubber feet to the bottom cover to keep it from sliding around and being scratched.

Amplifier Operation

The 2-meter amplifier works very well with my Kenwood TH-21AT hand-held and ICOM IC-202S SSB/CW transceiver. I use one in my shack and one mobile—both at more than 25 W output. I drive the 220-MHz version of the amplifier with an ICOM IC-3AT (in its high-power mode).

Limit the amplifier power output to 25 W during linear operation. *All SSB amplifiers have a rated linear power output that should not be exceeded, even though the amplifier may be driven above that level. To keep your signal clean, do not overdrive any amplifier.* For exciters with fixed power outputs that would overdrive the amplifier, use the loss of a length of RG-58, or a discrete attenuator, between the radio and the amplifier to prevent overdrive. The gain of the preamplifier (if used) will overcome the attenuator or cable loss during receiving.

When using any amplifier or transverter in the shack, it is a good practice to "hard key" it. Hard keying is simply forcing the amplifier or transverter into the transmit mode with a switch closure or an applied voltage. To do this, run a keying line from the exciter to the amplifier. (Ground the collector of Q2 to hard key these amplifiers.) I added a phono jack to the 220-MHz amplifier to facilitate hard keying. If a positive voltage is used for keying, a 2N2222 transistor inverter can be used between the transceiver and the collector of Q2 (see the inset in Fig 1).

Summary

These amplifiers have served me well in the car and at home. After building one of these amplifiers, you'll probably find what I did: They're so handy to have around, and so easy to build, that you can't build just one!

Notes

[1] Thomson Components/Mostek Corp, Semiconductor Division, Commerce Dr, Montgomeryville, PA 18966. Thomson transistors are available through RF Gain, Ltd, 100 Merrick Rd, Rockville Center, NY 11570, tel 516-536-8868 or 800-645-2322.

[2] The following parts are available from Frontier Microwave, RD 1 Box 467, Ottsville, PA 18942: 100+ tinned rivets: $2; relays (K1, K2): 2 for $8. Prices include shipping. The ARRL and *QST* in no way warrant this offer.

By David D. Meacham, W6EMD From *QST*, April 1984

A High-Power 2-Meter Amplifier Using the New 3CX800A7

Tired of hearing exotic DX on 2 meters but not being able to work it? Build this amplifier, and you'll transform your pip-squeak signal into a real rockcrusher.

The 3CX800A7 triode recently announced by Varian EIMAC has a plate dissipation rating of 800 W and modest cooling requirements. Its oxide cathode gives high emission with only 20 W of heater power. With full ratings up to 350 MHz, this tube is a scaled-up version of the 8874 — a proven performer in amateur and commercial gear.

The amplifier described here is based on a design presented by Raymond F. Rinaudo, W6ZO, in January 1972 QST. Most of the changes in the new amplifier (Fig. 1) are designed to accommodate the larger size of the 3CX800A7 and its attendant higher capacitances and currents. A plate-current meter is not included because my station power supply is already well metered. However, there is room on the front panel of the amplifier for a plate-current meter if another builder wishes to add one. Other changes to Rinaudo's design are minor.

Construction

The amplifier chassis is mounted on a standard 19-inch wide, 5¼-inch-high aluminum rack panel (Bud No. SFA-1833).[1] A 5 × 13 × 3-inch aluminum chassis (Bud No. AC-422) is spaced 1¾ inches behind the panel by two aluminum end brackets. A 3½ × 4½ × 1-inch aluminum chassis (Bud No. AC-1402) houses the input circuitry and is mounted on the larger chassis between it and the front panel. The right-hand end bracket has a large lip on the rear for mounting the heater transformer and connectors. Fig. 2 shows mechanical details of the chassis and end brackets. The cabinet chosen is a lightweight aluminum unit made by TenTec (No. 19-0525).



Input Circuit

In the cathode-driven configuration, the input impedance of the 3CX800A7 appears as a nominal capacitance of 26.5 pF in parallel with a resistive component that varies with operating conditions but is typically about 49 ohms. The computerdesigned input circuit of this amplifier operates at a loaded Q of about 2.1. It can be set anywhere in the 2-meter band for a VSWR of less than 1.3:1. C1 and C2 are predominantly matching and tuning controls, respectively; there is some interaction between them, however. When the input is tuned at 144.5 MHz, the input VSWR will he less than 1.4:1 from 144 to 145 MHz.

The tube socket is an EIMAC SK-1900 or a Johnson part No. 124-311-100. Its center is mounted 2 inches from the end of the input box, adjacent to the mounting bracket. The tube pins and input circuit are cooled by a small amount of air admitted to the input box from the pressurized output box. Three holes, made with a no. 50 drill, provide adequate flow. These holes are spaced in a close triangle and are located diagonally across from the variable capacitors. Air exhausts through the tuning holes. Fig. 3 shows details of the input circuitry.

The heater circuit includes two chokes, feedthrough capacitors, the filament transformer, a voltage-dropping resistor and a switch. The chokes are wound with a turn-to-turn spacing of about one-half the wire diameter. They are self-resonant (parallel resonant) just above the 2-meter band. Nominal heater voltage for the 3CX800A7 is 13.5 V. The closest available commercial transformer has a 14.0-V secondary, so R3 is used in the primary. Switching is set up so that the blower must be on before the heater can be activated. Conversely, this arrangement allows the blower to be left on after switching off the heater—a highly recommended practice.

Cathode bias is provided by a 5.1-V Zener diode, D3. Rl prevents the cathode voltage from soaring if the Zener fails. F2 will blow if excessive cathode current is drawn. R2 nearly cuts off plate current on receive. Because the grid is at dc ground, the negative supply lead must be kept above


C10
J2
OUTPUT
50
7.5 kV
C8
C9
C11
50
7.5 kV
V1
3CX800A7
4, 7, 11
RFC 4
L3
J1
INPUT
C1
1.7-14.1
L1
L2
C2
1.7-14.1
1, 2, 3,
8, 9, 10
5
6
1500
2.5 kV
C7
F.T.
RFC 1
RFC 2
RFC 3
C6
F.T.
R5
50
50 W
1000
500 V
C4
F.T.
1000
500 V
C5
F.T.
J4
B+
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k=1000, M=1000 000.
NOTE: CONNECT THE HOT SIDE OF THE 117-V AC LINE TO THE FUSE.
5.1 V
10 W
D3
R1
200
12 W
F2
T1
R3
35
12 W
DS1
B1
M
117-V AC
F1
S2
S1
GRID CURRENT
0-100
mA
M
R2
10 k
12 W
500
1 kV
C3
J3
B-
TR
TERMINALS
GND
D1
D2
R4
200
12 W

Fig. 1 — Schematic diagram of the 3CX800A7 amplifier.

B1 — Blower (Dayton 4C012 or equiv.); see text.
C1, C2 — 1.7-14.1 pF air variable (E. F. Johnson 189-505-4 or equiv.).
C3 — 500.pF, 1.kV disc ceramic.
C4, C5, C6 — Ceramic feedthrough, 1000 pF, 500 V (Erie 357-001).
C7 — EMI feedthrough filter, 1500 pF, 2.5 kV (Erie 1280-060).
C8, C9 — 50 pF, 7.5 kV, NP0 (HEC HT-50 852).
C10, C11 — See text.
D1, D2 — 1N4001.
D3 — Zener diode, 5.1 V, 10 W (1N3996A).
DS1 — NE51 in holder with built-in dropping resistor.
F1 — Slow-blow fuse, 2 A (Buss MDL-2 or equiv.).
F2 — 1.5 A fuse (Buss AGC 1½ or equiv.).
J1 — BNC bulkhead feedthrough connector (UG-492 A/U).
J2 — Type N female connector (part of C10 assembly — see text).
J3, J4 — High-voltage connector (Millen 37001 or equiv.).
L1 — 8 turns no. 16 tinned wire, ⅜-in ID, ¹¹⁄₁₆ in long.
L2 — 6 turns no. 16 tinned wire, ⅜-in ID, ¹¹⁄₁₆ in long.
L3 — Plate line, 1⁵⁄₁₆ in wide, 8³⁄₁₆ in long. See text and Fig. 4.
R1, R4 — 200 ohms, 12 W.
R2 — 10 kΩ, 12 W.
R3 — 35 ohms, 12 W.
R5 — 50 ohms, 50 W.
RFC1 — 1.0 µH choke, 300 mA (Miller 4602).
RFC2, RFC3 — 11 turns no. 20 HF wire on ⅜-in Noryl rod.
RFC4 — 10 turns no. 16 tinned wire, ½-in ID, 1³⁄₁₆ in long.
T1 — Filament transformer, 14.0-V, 2-A secondary (Triad F-215X or equiv.).

ground for grid-current metering by M1. R4 keeps the negative side of the plate supply from rising if M1, D1 and D2 all open up. D1, D2 and C3 protect the meter from transients and RF voltages.

Output Circuit

The output tank circuit is a silver-plated quarter-wave strip line (Fig. 4) foreshortened by the tube, loading and tuning capacitances at, and near, its open end. It operates at a loaded Q of approximately 20. The silver-plated anode collet (Fig. 4) is made of 0.062-inch-thick brass sheet with Tech-Etch 134B finger stock soldered on the inside. It is supported by two Teflon® standoffs ½-inch in diameter and 1 inch long. At the far end of the line, a silver-plated shorting block contacts the chassis and the strip line. This block (Fig. 4) is made from ⁷⁄₁₆-inch-thick brass 1¹⁵⁄₁₆ inches wide and 1 inch high. EIMAC CF-800 finger stock is screwed and then soldered on both top and bottom. The chassis and stripline are both slotted to allow ⁵⁄₁₆ inch of shorting-block travel to set the tuning range of the capacitive-tuning paddle. A 1-inch-long Teflon standoff supports the center of the line.

The tuning (C11) and loading (C10) paddles are 1³⁄₁₆-inch-diameter discs made from silver-plated, ¹⁄₁₆-inch-thick brass. They are spaced 1³⁄₈ inches center-to-center. The output loading paddle is nearest the tube, and its center is 1¹³⁄₁₆ inches from the tube cooler surface. Spacing between the paddle and line during operation is about 0.135 inch. The output tuning boss, EIMAC part No. 720362, is tapped for a ¼-28 threaded rod. The output loading control and output connector are two separate EIMAC assemblies combined into one unit. They are available from EIMAC as Support Assembly No. 720361 and Sliding Probe Assembly No. 720407. For this amplifier, the outer conductor was lengthened to reach the front panel. The grid collet is also available from EIMAC as part No. 720359.

In addition to RFC4 and feedthrough capacitor C7, an energy-absorbing resistor (R5) is wired in series with the dc plate supply. This resistor will protect the tube and power supply in the event of a highvoltage arc. It provides necessary protection while dissipating only 12.5 W at 500-mA dc plate current.

Cooling

The blower specified provides a measured 25 CFM airflow through the output box and tube cooler at 0.42 inch of water-column static pressure. This amount of cooling is sufficient for 800 W of plate dissipation at sea level with inlet air temperatures up to 35° C. It is adequate for the same dissipation at 5000 feet of altitude with inlet-air temperatures up to 25° C.

Not evident from the photographs is the care taken to separate outgoing hot air from incoming cool air. This is accomplished by the addition of a simple dividing wall inside the cabinet running from the rear chassis cover of the output box to the rear of the cabinet. The material used is rigid fiberglass insulation — the kind you cut with a saw. It provides a measure of blower-noise suppression in addition to assuring cool inlet air.

Hot air leaving the anode cooler is directed to a homemade "honeycomb" RFI filter through a chimney made from rolled-up Teflon sheet. The filter is made of brass tubing and sheet with the honeycomb material soldered in place. See Fig. 5 for construction details. This filter acts as a waveguide-beyond-cutoff having high attenuation at 144 MHz.

The equation for calculating attenuation by this type of filter is

$$A_a = 32\ D/d \qquad \text{(Eq. 1)}$$

where A_a = aperture attenuation (dB), D = length of pipe, and d = inside diameter of pipe. In this case, the "pipe" is each cell of the honeycomb. The basic material for the honeycomb is cadmium-plated brass heat-radiator core.[2] Each hexagonal-shaped cell has a width between flat sides (diameter) of 0.100 inch. The material is ½-inch thick. Plugging these values into the equation yields an A_a of 160 dB—more than enough! From a practical standpoint, it is usually sufficient to make cell length at least three times the nominal cell diameter.

Tune-up

Initial work may be done with a dip meter, particularly on the output circuit. With the tube in place, but with no voltages applied, the shorting block on the end of the plate line should be set to give a paddle-tuning range that straddles the desired operating frequency. Bear in mind that when the tube is "hot," the resonant frequency will be somewhat lower than it is without electron flow.

The input-tuning capacitor can be dip-meter resonated with the matching capacitor set at one-half mesh for a start. Further work here must be done "hot" with a VSWR measuring device on the input.

Set the initial spacing between the output paddle and the plate line to ⅛-inch. Connect the output to a 50-ohm dummy load capable of handling at least 700W at 144 MHz through an accurate VHF wattmeter, such as a Bird model 43. Connect a driver capable of delivering about 20 W to the input through a VSWR-measuring device.

The heater of the 3CX800A7 should be run for at least three minutes before applying plate voltage. After the warm-up, short the TR terminals and apply about 1000 V to the plate. This should result in a small amount of idling plate current. Next, apply enough drive to produce a rise in plate current, and adjust the plate tuning for a peak in output power. Now tune and match the input circuit for minimum input VSWR. Next, adjust the output loading paddle for maximum power output while keeping the plate current dipped with the plate tuning paddle. Apply full plate voltage and higher drive power, and then repeak the output tuning and loading controls. Touch up the input tuning and matching, and the amplifier is ready for service.


MAIN CHASSIS
7-7/8"
2-1/16"
1/2"
2-5/8"
9/16"
NO. 27 DRILL
1/2"
3/8" DIA.
1/8"
3/4"
5"
NO. 31 DRILL
1-3/8"
1-13/16"
13/16"
1-1/4"
5-1/8"
13"
5/8" DIA.
23/32"
4 HOLES NO. 31 DRILL
23/32"
NOTE: HOLES ON ENOS TO MATCH HOLES IN END BRACKETS
mm = IN. (") X 25.4
INPUT CIRCUIT CHASSIS
NO. 31 DRILL
LOCATION OF HOLES IN SMALL CHASSIS (SAME HOLES MATCH-DRILLED IN LARGE CHASSIS).
3 HOLES NO. 50 DRILL
THIS HOLE PUNCHED AND FILED TO SHAPE
4 HOLES NO. 27 DRILL
NO. 31 DRILL
3-13/16"
LEFT END BRACKET
11/32"
9/16"
RIGHT END BRACKET
9/16"
2-11/16"
5/16"
1/2"
3/4"
2 HOLES NO. 17 DRILL
4 HOLES NO. 31 DRILL
5"
3/4"
1/2"
4-13/16"
5"
4-13/16"

Fig 2—Mechanical details of the chassis and end brackets. The end brackets are made from 0.032-in aluminum, 5052 alloy or softer.



Fig 3—Close-up of the input circuitry and tube-socket wiring. Keep all leads as short as possible.



2-3/4"
1/2"
1-1/2"
HONEYCOMB MATERIAL
SOLDER TUBE TO FLANGE
3-11/16"
mm = IN.(") X 25.4
FLANGE
3.412"
4 HOLES NO. 31 DRILL

Fig 5—Mechanical details of the exhaust air RFI filter. The honeycomb material is soldered inside a 2¾-in OD, 0.065-in wall brass tube. The flange, which bolts to the chassis, is made from 0.125-in-thick brass sheet.



PLATE LINE
3/16"
8-3/16"
4-1/2"
3/16"
1-15/16"
15/16"
NO. 27 DRILL
NO. 31 DRILL
℄
3/4"
9/16"
9/32"
TWO SLOTTED HOLES 1/8" WIDE 7/16" LONG
SHORTING BLOCK
DRILL AND TAP 4-40 THREAD 3/8" DEEP 8 PLACES
3/4"
1-5/16"
TOP
7/16"
1/4"
5/8"
1"
SIDE
0.060"
1/8"
EIMAC CF-800 FINGER STOCK SCREWED AND SOLDERED ON
ASSEMBLY
ANODE COLLET
2 HOLES NO. 31 DRILL
3-3/4"
4-1/4"
15/16"
1-5/16"
1-9/16"
1-11/16"
DETAIL
0.062" BRASS SHEET
FINGER STOCK
SOLDER THE JOINT ALL AROUND THE HOLE
2 HOLES NO. 27 DRILL
1/2"
1/4"
2.74"
mm = IN.(") X 25.4

Fig 4 — Mechanical details of the plate line, anode collet and shorting block. The plate line is made from 0.032-in-thick silver-plated brass, although copper or aluminum (5052 alloy or softer) of the same thickness may be used. The lip on the plate line is screwed to the one end of the blocking capacitors. The anode collet, which is made from 0.062-in-thick silver-plated brass, is screwed to the other ends of the blocking capacitors. Tech-Etch no. 134B finger stock soldered around the inside of the anode collet grips the 3CX800A7. Finger stock on the silver-plated brass shorting block ensures good contact between the chassis and plate line.



Fig 6—Various views of the completed 3CX800A7 amplifier.



Fig 7—Rear view of the amplifier with the plate-compartment cover in place. Note the honeycomb RFI filter at the hot-air exhaust.

Table 1

Operating Conditions for the 3CX800A7 Amplifier

Plate supply voltage	2200 V
Zero-signal plate current*	65 mA
Single-tone plate current	500 mA
Grid bias (Zener bias)	–5.1 V
Single-tone grid current*	40 mA
Driving power	18.5 W
Output power	707 W
Gain	15.8dB
Efficiency**	64%

*Values may vary considerably from tube to tube.

**Actual tube efficiency is about one percent higher because of power loss in the 50-ohm series resistor in the plate lead (R5).

A few words of caution are in order. Remember that the heater voltage must never be applied without the blower running, and that the heater must warm up at least three minutes before applying plate voltage. Never exceed 60-mA dc grid current, even during tune-up. Also, because of the relatively low grid dissipation of the 3CX800A7, RF drive must never be applied unless plate voltage is applied to the tube and a suitable load is connected to the output. Following these simple rules will substantially increase tube life and amplifier reliability.

Typical Operating Conditions

With Zener-diode bias, the 3CX800A7 is best operated in Class AB2 for linear service. The data in Table 1 represent measured performance in linear service at 144 MHz. Complete data sheets are available from EIMAC. This amplifier is easily capable of conservative operation at 700-W output. Two of these tubes will run at the 1500-W output legal limit.

This amplifier uses straightforward construction techniques and is easily duplicated. Any builder will be rewarded with a great deal of satisfaction and a reliable amplifier.

Notes

[1] mm = in x 25.4; m = ft x 0.3048.

[2] One source for the honeycomb radiator core material is Technit West Division, 320 North Nopal St., Santa Barbara, CA 93103.

By Russ Miller, N7ART **From *QST*, December 1994**

The Quick Powerhouse

Tired of missing a new grid square while waiting for your amplifier to warm up? Build this almost-instant-on, 1.2-kW linear power amplifier for 2 meters.

It's that typical, early summer afternoon, when, out of the blue comes co-channel interference to the low-band (channels 2 through 6) TV channels. Time to turn on the 2-meter receiver. Whoops! There's a sporadic-E opening, and stations are booming in from over 1000 miles away. Quickly, I hit the switches to warm up my linear amplifier. Time marches on, and now the amp is ready—only took 3 or 4 minutes. But that juicy, far-away clatter via sporadic E is gone! Woe is me!

Having had this happen more than once, I was delighted to find that Eimac was producing a new tube with an almost-instant-warm-up filament that functions well at 2 meters—the 3CX1200Z7.[1] The Z7 is different from the 3CX1200A7 by virtue of its external grid ring, redesigned anode assembly and a 6.3-V ac filament. One advantage to the 3CX1200Z7 is the wide range of plate voltages that can be used, from 2000 to 5500. This amplifier looks much like the easily duplicated W6PO design,[2] except for the plate collet and the addition of some control circuitry. The plate collet is adapted from the W6PO 222-MHz design.[3] The RF deck is a compact unit, designed for table-top use (Figure 1). Table 1 gives some data on the 3CX1200Z7; Table 2 lists CW operating performance for this amplifier.

Input Circuit

The tuned-filament T network matches the 50-Ω drive source to the filament input impedance, providing a very low input SWR. Tuning is easy and docile. Grid bias is provided by an 8.2-V, 50-W Zener diode. Cutoff bias is provided by a 10-kΩ, 25-W resistor. A relay on the control board shorts out the cutoff-bias resistor, to place the amplifier in the TRANSMIT mode.

I didn't use a tube socket. Instead, I bolted the tube directly to the top plate of the subchassis, using the four holes (drilled to clear a #6 screw) in the grid flange. Connections to the heater pins are via drilled and slotted brass rods. The input circuit is contained within a 3½×6×7¼-inch (HWD) subchassis (Figure 3).



Figure 1—This table-top 2-meter power amplifier uses a quick-warm-up tube, a real plus when the band suddenly opens for DX and you want to join in.

Table 1
3CX1200Z7 Specifications
Maximum Ratings
Plate voltage: 5500 V
Plate current: 800 mA
Plate dissipation: 1200 W
Grid dissipation: 50 W

Table 2
CW Operating Data
Plate voltage: 3200 V
Plate current (operating): 750 mA
Plate current (idling): 150 mA
Grid current: 165 mA
DC Power input: 2400 W
RF Power output: 1200 W
Plate dissipation: 1200 W
Efficiency: 50%
Drive power: 85 W
Input reflected power: 1 W

Control Circuit

The control circuit (Figure 4) is a necessity. It provides grid overcurrent protection, keying control, and filament surge control. To protect the tube filament from stressful surge current, a timer circuit places a resistor in series with the primary of the filament transformer. After four seconds, the timer shorts the resistor, allowing full filament voltage to be applied. C2 and R4 establish the time delay.

Another timer inhibits keying for a total of 10 seconds, to give the internal tube temperatures a chance to stabilize. C1 and R3 determine the time constant of this timer. After 10 seconds, the amplifier can be keyed by grounding the keying line. When the amplifier is not keyed, it draws no plate current. When keyed, idle current is approximately 150 mA, and the amplifier only requires drive to produce output. A


C5
10
25 W
HV B+
to
Figure
8
RFC1
C1
C3
L1
L2
C2
C4
C6
C7
J2
RF
OUT
3CX1200Z7
J1
L3
L4
RF
INPUT
C8
C11
RFC2
RFC3
250
25 W
C9
C10
1A
D2
10 k
25 W
C12
6.3 V
8.2
50 W
B
B
to Figure 4
T1
M1
mA
M2
A
+
+
Grid
Current
Cathode
Current
120 V
HV B–
to
Figure
8
250
25 W
D1
10
25 W
MOT
1
to Control
Board
(Figure 4)
3A
120 V
B
W
G
H
H
to Figure 4
FILAMENT
BLOWER

Except as indicated, decimal values of capacitance are in microfarads (μF); others are in picofarads (pF); resistances are in ohms; k=1,000.

Figure 2—Schematic diagram of the 2-meter amplifier.

C1-C4—100 pF, 5 kV, type 850
C5—1000 pF, 5 kV
C6—Anode-tuning capacitor; see text and Figure 5 for details
C7—Output-loading capacitor; see text and Figure 7 for details
C8-C10—1000-pF silver mica, 500 V
C11—30-pF air variable
C12—0.01 μF, 1 kV
D1—1000 PIV, 3-A diode, 1N5408 or equiv
D2—8.2-V, 50-W Zener diode, ECG 5249A
J1—Chassis-mount BNC connector
J2—Type-N connector fitted to output coupling assembly (see Figure 7)
L1, L2—Plate lines; see text and Figure 6 for details
L3—5 t no. 14, $^1/_2$-inch diameter, close wound
L4—3 t no. 14, $^5/_8$-inch diameter, $^1/_4$-inch spacing
RFC1—7 t no.14, $^5/_8$-inch diameter, 1$^3/_8$ inch long
RFC2, RFC3—10 t no. 12, $^5/_8$-inch diameter, 2 inches long
T1—Filament transformer. Primary: 120 V; secondary: 6.3 V, 25 A, center tapped Available from Avatar Magnetics (Ronald C. Williams, W9JVF, 240 Tamara Trail, Indianapolis, IN 46217, 317-783-1211); part number AV-539
M1—Grid milliammeter, 200 mA dc full scale
M2—Cathode ammeter, 2 A dc full scale
MOT1 —140 free-air cfm, 120-V ac blower, Dayton 4C442 or equivalent.

Sources for some of the "hard to get parts" include:

Fair Radio Sales, 1016 E Eureka, Lima, OH 45802, tel 419-227-6573;
Surplus Sales of Nebraska, 1502 Jones Street, Omaha, NE 68102, tel 402-346-4750.



Figure 3—This view of the cathode-circuit compartment shows the input tuned circuit and filament chokes.

safety factor is built in: the keying circuit requires +12 V from the high-voltage supply. This feature ensures that high voltage is present before the amplifier is driven.

The grid overcurrent circuit should be set to trip if grid current reaches 200 mA. When it trips, the relay latches and the NORMAL LED extinguishes. Restoration requires you to press the RESET switch.

Plate Circuit

Figure 5 shows an interior view of the plate compartment.The anode collet is patterned after the one used in the W6PO 222-MHz amplifier. The differences are small. A 4×2$^1/_4$-inch tuning capacitor plate and a 2×2-inch output coupling plate are centered on the collet. These parts are the same size and shape as those used on the 2-meter W6PO amplifier. The remaining difference is the diameter of the hole for the 3CX1200Z7 anode. Sufficient clearance must be left for the fingerstock. The hole diameter will be approximately 3$^5/_8$ inches.


Keying Jack
KEYING INHIBIT (10 Seconds)
NC
K1B
DS1 PREHEAT
K1A
390
DS2
READY
K1
D1
Q1
R1 2.2 k
R3 1 M
Q3
+12 V
R4 1 M
R2 2.2 k
Q4
C1 22 µF 35 V
C2 22 µF 35 V
Q2
to Figure 2
H
H
NC
K3A
FILAMENT DELAY (4 Seconds)
K3
D2
B
to Figure 2
B
NC
K2A
K2
D4
KEYING RELAY
GRID OVERCURRENT
+12 V from HV Pwr Supply (Figure 8)
NC
390
NORMAL
DS3
+12 V
U1
Reg
OUT
IN
GND
C3 0.47
D5
T1
470 25 V
18 V
120 V
RESET
S1
to Figure 8
+12 V
D3
K4
Q5
D6
0.01
Set Grid Overcurrent Trip
10 k
15 1 W
to Grid Current Meter (Figure 2)

Except as indicated, decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); resistances are in ohms; k=1,000, M=1,000,000. NC=not connected.

Figure 4—Schematic diagram of the amplifier-control circuits.

C3—0.47-µF, 25-V tantalum capacitor
D1-D5—1N400i or equivalent
D6—1N4007 or equivalent
DS1—Yellow LED
DS2—Green LED
DS3—Red LED
K1—Keying-inhibit relay, DPDT, 12-V dc coil, 1-A contact rating (RadioShack 275-249 or equivalent)
K2—Amplifier keying relay, SPDT, 12-V dc coil, 2-A contact rating (RadioShack 275-248 or equivalent)
K3—Filament delay relay, SPST, 12-V dc coil, 2-A contact rating (RadioShack 275-248 or equivalent)
K4—Grid-overcurrent relay, DPDT, 12-V dc coil, 1-A contact rating (RadioShack 275-249 or equivalent)
Q1, Q2, Q5—2N2222A or equivalent
Q3—MPF1O2 or equivalent
Q4—2N38i9 or equivalent
S1—Normally closed, momentary pushbutton switch (RadioShack 275-1549 or equivalent)
T1—Power transformer, 120-V primary, 18-V, 1-A secondary
U1—+12 V regulator, 7812 or equivalent



Figure 5—This top view of the plate compartment shows the plate-line arrangement, C1-C4 and the output coupling assembly.


8-1/2"
1-1/8" OD 1/16" Wall Copper Tubing
8-1/8"
1-1/2"
1/2"
Solder to Tubing
2"
11/16"

Figure 6—Plate line details.


1/4" Teflon (Force Fit)
Center Pin
1-5/8"
Type-N Connector
7/8" OD
1-3/8" OD Copper
1-3/8"
2"
1/4" Diam.
Fingerstock
2-1/4"
Fingerstock

Figure 7—Details of the output coupling assembly.


CB1
25
25 W
240 V
K1B
K1A
T1
240 V
2250 V
D4
D1
D3
D2
3200 V
B+ to Figure 2
100 k
225 W
K1
32 μF
4.5 kV
15
1 W
470
1/2 W
25
25 W
B- to Figure 2
240 V
T2
M1
5 kV
250
25 W
120 V
+12 Vdc
MOT 1
120 V FAN
2.2 k
68 k
Q1
K2A
Q2
47 μF
35 V
K2
D5
2-SECOND TIMER
120 V
T3
D6
+12 V to Figure 2
470 μF
35 V

Except as indicated, decimal values of capacitance are in microfarads (μF); others are in picofarads (pF); resistances are in ohms; k=1,000

Figure 8—Schematic diagram of the high-voltage power supply recommended for use with the power amplifier.

D1-D4—Strings of 4 each, 1000-PIV, 3-A diodes, 1N5408 or equivalent
K1—DPST relay, 120-V ac coil, 240-V-ac, 20-A contacts (Midland Ross 187-321200 or equivalent)
K2—SPDT miniature relay, 12-V dc coil (Radio Shack 275-248 or equivalent)
M1—High-voltage meter, 5 kV dc full scale (1-mA meter movement used with series resistors shown in drawing)
MOT1—Cooling fan, Torin TA-300 or equivalent
Q1—2N2222A or equivalent
Q2—MPF102 or equivalent
S1—20-A hydraulic/magnetic circuit breaker (Potter and Brumfield W68X2Q12-20 or equivalent)
T1—High-voltage power transformer, 240-V primary, 2250-V, 1.2-A secondary (Avatar AV-538 or equivalent)
T2—Stepdown transformer, Jameco 112125, 240-V to 120-V, 100 VA
T3—Power transformer, Jameco 104379, 120-V primary; 16.4 V, 1-A secondary (half used)

Figure 6 is a drawing of the plate line and Figure 7 is a drawing of the output coupling asssembly.

Cooling

The amplifier requires an air exhaust through the top cover, as the plate compartment is pressurized. You can fashion a chimney from a $3\frac{1}{2}$-inch waste-water coupling (black PVC) and a piece of $\frac{1}{32}$-inch-thick Teflon sheet. The PVC should extend down from the underside of the amplifier cover plate by $1\frac{1}{8}$ inches, with the Teflon sheet extending down $\frac{3}{4}$ inch from the bottom of the PVC.

The base of the 3CX1200Z7 is cooled by using bleed air from the plate compartment, which is directed at the tube base, through a $\frac{7}{8}$-inch tube set into the sub-chassis wall at a 45° angle.

The recommended blower will supply more tban enough air for any temperature zone. A smaller blower is not recommended, as it is doubtful that the base area will be cooled adequately. The 3CX1200Z7 filament draws 25 A at 6.3 V! It alone generates a great deal of heat around the tube base seals and pins, so good air flow is critical.

Construction

The amplifier is built into a 12×12×10-inch enclosure. A 12×10-inch partition is installed $7\frac{1}{4}$ inches from the rear panel. The area between the partition and the front panel contains the filament transformer, control board, meters, switches, Zener diode and miscellaneous small parts. Wiring between the front-panel area and the rear panel is through a $\frac{1}{2}$-inch brass tube, located near the shorted end of the right-hand plate line.

High voltage is routed from an MHV jack on the rear panel, through a piece of RG-59, just under the shorted end of the left-hand plate line. The cable then passes through the partition to a high-voltage standoff insulator made from nylon. This insulator is fastened to the partition near the high-voltage feed-through capacitor. A 10-Ω, 25-W resistor is connected between the insulator and the feed-through capacitor.

The plate lines are connected to the dc-blocking capacitors on the plate collet with $1\frac{3}{4}$×2-inch phosphor-bronze strips. The bottom of the plate lines are attached to the sides of the subchassis, with the edge of the L-shaped mounting bracket flush with the bottom of the subchassis.

When preparing the subchassis top plate for the 3CX1200Z7, cut a $2\frac{11}{16}$-inch hole in the center of the plate. This hole size allows clearance between the tube envelope and the top plate, without putting stress on the envelope in the vicinity of the grid flange seal.

Table 3
Power Supply Specifications

High voltage: 3200 V
Continuous current: 1.2 A
Intermittent current: 2 A
Step/Start delay: 2 seconds

Exercise care in placing the movable tuning plate and the movable output coupling disc, to ensure they cannot touch their fixed counterparts on the plate collet.

Operation

When the amplifier is first turned on, it cannot be keyed until:

- 10 seconds has elapsed
- High voltage is available, as confirmed by presence of +12 V to the keying circuit

Connect the amplifier to a dummy load through an accurate power meter capable of indicating 1500 W full scale. Key the amplifier and check the idling plate current. With 3200-V plate voltage, it should be in the vicinity of 150 mA. Now, apply a small amount of drive and adjust the input tuning for maximum grid current. Adjust the output tuning until you see an indication of RF output. Increase drive and adjust the output coupling and tuning for the desired output. Do not overcouple the output; once desired output is reached, do not increase loading.

When you shut down the amplifier, leave the blower running for at least three minutes after you turn off the filament voltage. I found the 3CX1200Z7 to be an excellent tube. I tried it with exessive drive, plate-current saturation, excessive plate dissipation—all the abuse it's likely to encounter in amateur applications. I had no problems, but I don't recommend you repeat these tests!

A Companion Power Supply

A good, solid-state high-voltage power supply is a necessity to ensure linearity in SSB operation. Specifications of the power supply I built are given in Table 3. Figure 8 is a schematic diagram of the supply. A power supply for a high-power linear amplifier should operate from a 240-V circuit, for best line regulation. I have specified a special, hydraulic/magnetic circuit breaker that doubles as the main power switch. I don't recommend you substitute a regular switch and fuses for this breaker, as fuses won't operate quickly enough to protect the amplifier in case of an operating abnormality. The bleeder resistor dissipates about 100 W, so I included a small fan to remove the excess heat.

Power Supply Construction

The power supply can be built into a 17×13×10-inch cabinet. The power transformer is quite heavy, so use $\frac{1}{8}$-inch aluminum for the cabinet bottom, and reinforce it with aluminum angle for extra strength. The diode bridge consists of four legs, each containing five diodes.

Power Supply Operation

When the front-panel breaker is turned on, the two, 25-Ω resistors in the primary circuit limit inrush current as the filter capacitor charges. After two seconds, K1 activates, shorting both resistors and allowing full line voltage to be applied to the transformer.

As with all high-voltage power supplies, you must be extremely careful! Before opening the cabinet, remove the ac-line plug from its receptacle, and confirm that the filter capacitor is discharged before working on the supply.

Conclusion

This amplifier is a reliable and cost-effective way to generate a big 2-meter signal—almost as quickly as a solid-state amplifier.

To ensure that the output of my amplifier meets current spectral purity requirements, I use a high-power version of the half-wave output filter that appears as Figure 16 on page 39-10 of the 1993 and 1994 editions of *The ARRL Handbook*. Although I did not make spectral measurements of the output, I can run full output while my wife Mary Lou watches TV in a nearby room of our home.

Another suitable filter is the one that appears in the 1990 *ARRL Handbook* (Figure 150, on page 31-72) as part of the description of "A Legal-Limit 2-Meter Tetrode Amplifier."

Notes

[1] Suggested retail price of the 3CX1200Z7 is $625. You can obtain it from: Henry Radio, 2050 S Bundy Dr, Los Angeles, CA 90025, tel 310-820-1234; Richardson Electronics, 40 W 267 Keflinger Rd, La Fox, IL 60147, tel 708-208-2200; RF Parts, 435 South Pacific St, San Marcos, CA 92069, tel 619-744-0700.

[2] W. Orr, Editor, *Radio Handbook*, 23rd ed. (Indianapolis: Howard W. Sams and Co., 1987), pp 18-2 through 18-7.

[3] This project is also described in the *Radio Handbook*, pp 18-11 through 18-15.

By David Munyon, W7DVB From *QST*, September 1984

A Cathode-Driven Tetrode for 6 Meters

Stability, power, low cost: Is this what you're looking for in a 6-meter do-it-yourself project? If so, look what's here!



The advantages of grounded-grid amplifiers are numerous and have been proven over the years. They include: simplicity of design, good thirdorder IMD characteristics, inherent stability (generally without the need for neutralization) and noncritical tuning. The only requirement is abundant driving power. Usually, this is a small price to pay, unless the driver you intend to use is one of the many popular, low-power (10- to 25-W-output) VHF transceivers. Also, with the tremendous increase in the use of 100%-duty-cycle modes such as RTTY and SSTV, many of us would rather not operate our exciters at half to full bore while driving an amplifier. If you're willing to sacrifice only one of the aforementioned advantages—simplicity—the remaining attributes of grounded-grid operation can be made available at a considerable reduction in driving power.

Enter the Tetrode

For many years, tetrodes (most often connected as triodes) have been used in grounded-grid circuits. But we have good reasons to consider the tetrode as a cathode-driven performer in its own right. First, the drive requirements are reduced. A 4-400A requires 40W of drive power for full output when triode connected. Only half that amount is needed to drive its class-AB1 counterpart. The second reason is cost. Tetrodes are still available as hamfest and surplus items at a fraction of their original cost. (Some of the newer triodes cost more than the exciters that drive them!)

But not all tetrodes can be triode connected. All of the external anode family of tubes, and a few others, have internal geometry that allows the control grid dissipation to be greatly exceeded if the tube is operated as a triode. Therefore, those tubes should be cathode driven only as tetrodes. The usual way to do this is to ground the control and screen grids to RF with low-inductance bypass capacitors, and then place operating voltages on them. The cathode can be driven in a normal fashion, and the tube operated in any class consistent with linear service. Class-AB1 has the lowest drive requirements and is the easiest with which to work.

Tetrode Vs. Triode

I concede that the addition of a screen element complicates the overall circuit, especially if the screen-circuit provisions are made properly. But, the circuit need be no more complex than that of its grid-driven equivalent. The cathode-driven tetrode requires grid bias and a well-regulated screen supply. Also, there is no correct way to load a tetrode without a meter to monitor the screen-grid current. This device is invaluable and should not be omitted for the sake of economy.

No discussion of the screen-grid circuit would be complete without some mention of an overcurrent-protection circuit. Several solutions have been offered in the past (including the use of no protection circuit!), and each has its disadvantages. Sensitive relays are expensive and their use can have an adverse effect on screen-voltage regulation. Current-limiting supplies do an excellent job of protecting the tube, but do not inform you when something is wrong. Since screen current is extremely sensitive to minor plate-voltage excursions and plateloading conditions, the builder has to be absolutely certain that these are correct, and that plate voltage is always present with screen voltage, if the screen-protection circuit is to be eliminated. The protection circuit is well worth the small cost involved. This amplifier incorporates an inexpensive and simple circuit that contains none of the disadvantages mentioned earlier.


To Grid Bias (Fig 4)
RFC2
C9
M3
mA
0-500
C10
0.001
3 kV
0.001
3 kV
J2
High-Voltag Input
RF Out
M1
mA
0-20
C5
L2
C8
C1
0.001
R1
V1
4CX2508
PLATE
C6
C7
LOAD
RFC3
R2
750
1 W
R3
120
1 W
RF IN
K1B
0.001
2,4,
6,8
7
3
C4
0.001
R4
10 k
10 W
K2B
C2
C3
L1
100
GRID
RFC1
0.001
M2
0-50
0.001
0.001
T1
(See Fig 4)
To R7
(Fig 3)

* - See Text

Decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); Resistances are in ohms; k=1,000, M=1,000,000.

Fig. 1 — Schematic diagram of the 6-meter amplifier RF section. Unless otherwise specified, resistors are 1/2-W, 10%-tolerance types. Feedthrough capacitors have 500-V ratings; bypass capacitors are disc.ceramic, 1-kV.

C1 — 470-pF, 2.5-kV disc-ceramic (see text).
C2, C3 — 0.001-µF, 500.V silver mica.
C4 — Part of tube socket assembly (see text).
C5 — 500-pF, 5-ky ceramic (Centralab 858S-500 or equlv.).
C6 — See text (approx. 6 pF).
C7 — 140-pF air variable, receiving type.
C8 — 75-pF ceramic (Centralab 850S-75N or equiv.).
L1 — 4 1/2 turns no. 14 bare wire, 1/2-inch-dia, 1 1/2 inches long, tapped one turn from hot end.
L2 — 6 turns no. 10 bare wire, 1-inch-dia, 1 1/2 inches long.
RFC1 — 15 turns no. 16 enameled wire closewound on a 1/2-inch-dia ferrite rod.
RFC2 — 1 5/8 inches no. 22 enameled wire close-wound on a 3/8-inch-dia. Teflon® rod.
RFC3 — Ohmite Z50 (or equiv. 5-10 µH RF choke).
V1 socket — Eimac SK-600 or SK-620.
V1 chimney — Elmac SK-606.


TUBE SOCKET DETAIL
TO M1
R1
R2
C1
0.001
SOLDER LUG
C3
RFC 1
3
2
8
7
0.001
S.M.
TO INPUT CIRCUIT
TO K2A
0.001
1
R3
S.M. = SILVER MICA

Fig 2—Tube socket detail. See text.


TO SCREEN SUPPLY (FIG. 4)
K2A
D11
S3
TO X
SCR RESET
D12
A
G
D14
K
RESISTANCES ARE IN OHMS; k = 1000
FIG. 4
* 50 µF
25 V
C15
1.8 k
R7
9.1 *
TO Y
* - SEE TEXT
TO SCREEN OF V1 (FIG. 1)

Fig 3—Screen overcurrent-protection circuit. Resistors are 1/2-W, 10%-tolerance types.

D11, D12—1-kV, 2.5-A silicon diodes.
D14—4-A, 200-V SCR (Jameco C106B1, ECG 5455 or equiv.).
K2—DPDT 12-V dc relay, 1-A contacts (see text).

A Cathode-Driven 4CX250B

I became aware of the cathode-driven tetrode years ago while trying to get a 4-1000A to wotk on 50 MHz. The results were so good that, when it came time to build an amplifier for my new solid-state transverter, I decided that building a grid-driven amplifier would be a giant step backward.

The 4CX250B is an excellent tube for 6-meter use. This tube has a high plate-dissipation rating for its small physical size, has reasonable power-supply requirements, and requires approximately 10 W of drive in a cathode-driven, class-AB1 configuration. (If much more drive is available, an appropriate attenuator must precede the input circuit.) The only differences between this design and its grid-driven equivalent are the filament/cathode and control-grid circuits.

Filament/Cathode Circuit

In Fig. 1, notice that the cathode and one of the filament connections are tied together. Normally, the isolation created by the physical separation of the two elements is sufficient to ensure stability, and a filament choke would not be required. I felt that this would not be the case on 50 MHz, and a call to Eimac confirmed it. At Bill Orr's recommendation, I tied the cathode and filament together, and fed the filament through a choke. The cathode impedance is approximately 120 ohms. In the interest of best linearity and minimum, drive requirements, a tuned input circuit is used. The tank coil is tapped to present an input impedance of 50 ohms.

There are many sockets designed for use with this family of tubes. I recommend that you use one that incorporates a built-in screen bypass capacitor (1100 or 2700 pF); either one will do. A few of these types of sockets are so constructed that the four cathode pins are grounded internally; do not use one of these. An Eimac SK-600 or SK-620 socket is recommended. The four cathode pins (2,4, 6, 8) and one of the filament pins (7) of the socket must be wired together to form one low-inductance connection. The easiest way to do this is to carefully bend pins 1 and 3 parallel to the chassis, and then strap together pins 2, 4, 6, 7 and 8. Make certain that this strap forms a complete circle around the socket. For strap material, I use some stretched and flattened shield braid removed from RG-58 coaxial cable. All connections made to the cathode, or the filament (pin 7), can be made anywhere along this ring. See Fig. 2 for details.

Grid Circuit

The tube grid is accessed through the socket center connector and is bypassed to ground by C1. The capacitance of C1 is not as important as its physical size. C1 should be a high-voltage, disc-ceramic type (2 kV or more), whose body nearly spans the distance between the connection points. This provides for an absolute minimum lead


BLACK
F1
3A
S1
FIL
117-VAC
GREEN
WHITE
R6 *
0.001
M
B1
0.001
100
10 W
T1
(SEE FIG. 1)
K3B
NC
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k=1000
T2
* *
D1-D8
750/10 W
+ 315 V REG. TO R7 (FIG. 3)
C13
150 µF
450 V
V2
V3
V4
OC3
5
2
6.3 V
X
(TO FIG. 3)
5 V
Y
10 k
10 W
1 k
1 W
C12
150 µF
150 V
R5
1.6 k
2 W
D9
K3A
C11
150 µF
150 V
D13
87 V
3 W
8 k
5 k
BIAS
(TO FIG. 1)
12 k
K1C
NC
HV SUPPLY CONTROL
0.001
0.001
HV
680
K2C
NC
660
SCR O/C
* - SEE TEXT
* * - D1-D8, INCL.- EACH DIODE IS PARALLELED WITH A 0.01-µF/1-kV DISC CERAMIC CAPACITOR AND A 490 k, 1/2-W RESISTOR
T3
D10
50 µF
25 V
C14 *
1.8 k
OPERATE
S2
K1A
0.01
TO EXCITER (SEE TEXT)
J1
0.01
490k

Fig. 4 — Power-supply section of the 6-meter amplifier. Unless otherwise specified, resistors are ½-W, 10%-tolerance types; feedthrough and bypass capacitors have 500-V ratings.

B1 — Squirrel-cage blower, 56 CFM (minimum), 117-V ac motor.
D1-D10, incl. — 1-kV, 2.5-A silicon diodes.
D13 — 87-V, 5-W Zener diode.
K1 — 3PDT 12-V dc relay, 5-A contacts.
K3 — SPST 234-V ac relay, 3-A contacts (see text).
T1 — 117-V primary; 6-V. 2.6-A secondary (see text).
T2 — 117-V primary; 580-V c.t., 75-mA secondary with 6.3- and 5-V filament windings (see text).
T3 — 117-V primary; 12-V. 1-A secondary.

length. Use a solder lug on the grid pin, and solder the other capacitor lead directly to the inside of the air duct on the tube-socket bottom.

When my amplifier was first tested, I found that the plate current idled at about 40 mA, and was completely independent of grid voltage. This self-biasing was traced to a parasitic in the grid circuit, and was eliminated by the addition of a series-connected resistor, R1. If you wish to experiment, R1 should be a ½-W, carbon-composition resistor with a resistance value that is the minimum required for complete stability. R1 should be placed as shown in Fig. 2; I found that a 3.9-ohm resistor kept my amplifier unconditionally stable.

In the interest of stability, don't use chokes in place of R2 and R3 in the grid and screen circuits. M1, the grid-current meter, can have a range of from 0-1 mA to 0-20 mA or so, and is included only to ensure that grid current is never drawn, and the operation remains class-AB 1.

Screen Circuit

Relay contacts K2B are part of the screen overcurrent-protection circuit, the operation of which will be discussed later. Because the 4CX250B draws negative screen current on occasion, the screen-current meter should ideally be of the zero-center type. As these meters are expensive and not readily found, a standard meter can be pressed into service by using bleeder string, R4. Notice that 15 mA of bleeder current is drawn through the meter whenever K2 is open (normal). This offsets the actual zero reading of the meter to the 15-mA position and allows a negative current of 15 mA to be metered. This is more than adequate for the 4CX250B. If a zero-center meter is used, R4 may be eliminated unless the screen supply shunt regulator is replaced by a series regulator. In that case, the bleeder would be necessary to offset the effects of secondary emission.

For the overcurrent-protection circuit (Fig. 3), an SCR (D14) seems to be a natural. A very small gate voltage, developed across R7 by the screen current, turns on the SCR and causes K2 to close. This removes screen voltage from the tube and grounds the screen, preventing further abuse. A second set of relay contacts (K2C) is used to light a front-panel-mounted LED. D14 continues to lock out the screen voltage until the SCR is reset by removing its anode voltage. This is done by momentarily pushing the RESET switch, S3.

D11, C15 and the filament windings of T2 provide dc power for a 12-V relay at K2. A relay with a different voltage rating can be used if this supply is modified accordingly. The value for R7 was found experimentally by substituting a variable, low-voltage supply for the screen supply. A 0-100 mA meter and load resistor were placed in series with R7, and the voltage, slowly increased until the gate threshold was reached and the SCR fired. The threshold current was noted, and R7 varied until the desired current would trigger the SCR. With R7 equal to 9.1 ohms, the SCR fired consistently at 45 mA.

Since 15 mA of the current drawn through R7 will be bleeder current, this allows a maximum of 30 mA for screen current, which is well below the 12-W screen dissipation rating for the tube. Note that the entire overcurrent-protection circuit is hot with screen voltage, so proper precautions must be taken during construction. I built the protection circuit on a PC board, but it could have just as easily been chassis-mounted using terminal strips.

Construction

The amplifier is built on a 3 × 8 × 17-inch chassis; a 3 × 5 × 7-inch chassis houses the output network components. A 10½- × 19-inch rack panel is used for the amplifier front panel. The general physical layout should be followed, as it is well dictated by the flow of the circuit. All RF leads should be kept as short as possible, especially the bypass capacitor leads. Keep the dc leads cabled and



Fig 5—The final-amplifier-compartment cover has been removed for this photo.

as far away as possible from the RF leads. Most power-supply components are mounted on a fiberglass terminal board that is secured against the side of the chassis.

K3, D9, C11 and R5 (Fig. 4) constitute a time-delay circuit for filament inrush-current protection, and can be included if you feel that this is important. As it stands, the delay is approximately 1 second, which is more than ample. The 234-V ac relay is used on dc, and closes at about 70 V. The charging rate of C11 is controlled by its capacitance and the ohmic value of R5, and can be varied by changing their values.

Ideally, the input and output relays should be coaxial types; however, I used a single open-frame, 3PDT type and encountered no problems. The center pole is used for control (K1C), as that increases the isolation between the input and output circuits. In grid-driven amplifiers, I have never been able to use an open-frame relay for input and output switching. Because of the lower gain of this cathode-driven amplifier, I find no evidence of feedback or instability. Don't use plug-in type relays in their original form for K1. Remove the case, plug and connecting wires, and bolt the relay directly to the chassis. Use coaxial-cable braid to make the RF connections. The power supplies (Fig. 4) are of standard design. They may be replaced by any supplies yielding similar voltages, and need not reside on the same chassis as the amplifier. The high-voltage supply should produce 2-kV dc under load. Si turns on all supplies, including the external high-voltage supply. S2, the STANDBY/OPERATE switch, supplies power to K1, which allows the amplifier to be placed in operation; otherwise, the amplifier is simply bypassed.

If a 6.3-V ac filament transformer is used for T1, R6 will have to be.included to drop the filament voltage to 6 V. The ohmic value of R6 will have to be determined experimentally. Use a resistor with the highest wattage rating practical for good voltage stability. With an accurate voltmeter, measure the filament voltage at the tube socket with the filament choke in place, as there will be a slight voltage drop across the choke. Nothing will cause a 4CX250B to "go south" quicker than high filament voltage, and that means anything in excess of 6 V.

The filament choke (RFC1) consists of 15 bifilar turns of no. 16 enameled wire wound on half of an Amidon $^1/_2$-inch-diameter ferrite rod. The rod can be cut to a proper length by filing a small groove around its circumference, and then breaking it clean. Cover the rod with heat-shrink tubing or electrical tape before and after winding the choke. This will keep the rod and winding together, and make it self-supporting by its four leads.

The meters I used all have 0-1 mA movements and homemade shunts. The original meter-face calibration marks were carefully erased, and new ones applied using dry-transfer labels. Most such labels are ideal for panel marking, but are a bit too large for meter-face use. Your local stationery store should have transfers with smaller-sized numbers. During amplifier operation, care should be taken to avoid accidental contact with the plate-voltage meter, as it has high voltage on it.

Most VHF amplifiers have a higher-than-necessary Q in the output circuit because of the use of high minimum-capacitance air-variable capacitors. This is acceptable providing the rest of the output components are heavy-duty types and can handle the higher circulating currents. (Fhe small vacuum variable I used is admittedly first class, and it may not be used by many other builders.) Rather than using an air-variable capacitor, a homemade two-disc system is a preferred choice. If you can find a neutralizing capacitor with plates of 2-inch diameter or so, that would be ideal. If you must use an air-variable capacitor, use one with the least minimum capacitance; remove all unnecessary plates leaving just enough to do the job.

Tune-Up

Before the tube is placed in the socket, close S1 and check that all of the operating voltages are correct. Ground the bottom end of the bias string at K1C, and check that the BIAS potentiometer range will supply –50 to –60 V; then set it at –55 V. J1 should be connected to the external-circuit control jack of your exciter so that it is grounded when your exciter is keyed. Open S1 and make certain all voltages have bled down, then install the tube. Close S1 and S2. After the tube warms up, with no drive applied, key the exciter and adjust the BIAS potentiometer so that the plate idling current is exactly 100 mA.

While the tube is idling, rotate all the tuning controls throughout their respective ranges. If there are no sudden plate-current increases, the amplifier is stable. With a small amount of drive applied, tune the GRID and PLATE controls for maximum output. Once you are satisfied that both of these controls will provide resonance, apply full drive and retune the plate to resonance. Increase loading slowly, retuning the PLATE control each time, until a screen current of 5 mA (the meter actually reads 20 mA) is indicated. Observe how sensitive the screen current is to the operation of the LOAD control, and that it is by far the best indicator of plate resonance. If grid current is indicated, you're overdriving the amplifier.

Adjust the drive level and the plate TUNE and LOAD controls so that the platecurrent meter indicates 250 mA and the screen-current meter indicates 5 mA at resonance. Under these conditions, this amplifier develops a power output of about 310 W. With modulation, voice peaks should not exceed 150 mA on the plate-



Fig 6—A bottom view of the 6-meter amplifier. The screen-protection circuit is mounted on the PC board to the right of the tube socket.

current meter, and a small amount of negative screen current is normal.

Summary

This amplifier has been in operation now for over a year, and all reports of its operation have been complimentary. I hope that this amplifier will be duplicated by many who had previously resigned themselves to grid-driven designs. Much of the material presented here is general enough to encourage interest in the cathode-driven tetrode as a viable alternative to the grounded-grid triode. I will be glad to answer all letters of inquiry regarding this amplifier; please include an s.a.s.e.



Fig 7—Spectral photo of the 6-meter amplifier without external filtering. Vertical divisions are each 10 dB; horizontal divisions are each 50 MHz. The fundamental (second pip from the left) has been notched approximately 40 dB by means of notch cavities to prevent analyzer overload. The seventh harmonic is approximately 48 dB below peak fundamental output.



Fig 8—The addition of a simple filter (see Fig 9) at the amplifier output provides for excellent harmonic attenuation, and its use is recommended. All conditions are otherwise the same as those of Fig 7.



Fig 9—This simple harmonic-suppression filter, or one of similar characteristics, should be used at the output of the amplifier. The filter may be contained in a 2¼ × 2¼ × 5-in (HWD) aluminum box.

C16-C19, incl.—110 pF, 1-kV silver-mica capacitors.

L3, L5—4 turns no. 14, 5/16-in-ID, 1/2 in long.

L4—5 turns no. 14, 7/16-in-ID, 5/8 in long.

By John Reed, W6IOJ **From *QST*, August 1987**

A UHF Amplifier–from Scratch

Combine PC-board material, transistors and glue—what do you get? Two watts in and 45 watts out at 435 MHz!

Most UHF RF equipment designs involve undefined reactance. For example, the self-inductance of a variable capacitor, or simply the method of attaching a 50-ohm cable to the circuit may constitute reactance that is critical to the operation of the circuit. The result is that complete success in duplicating a circuit is not likely unless the components and layout are exactly the same as in the original. This is nearly always a limiting factor for the do-it-yourselfer wanting to duplicate a project. This class-C UHF amplifier project uses homemade components that anyone can assemble. Tests show that their use has resulted in little or no compromise in the performance of the amplifier over a design using far more expensive commercial parts. My amplifier shows more than 45 W output with less than 2 W input at 435 MHz. The output stage efficiency is approximately 60%, and includes a double-tuned filter for improved spectral purity.

The key to this design is the glue-down stripline technique I have used in many other UHF projects.[1] This method permits easy modification of stripline parameters for optimizing circuitry. Striplines are cut from double-sided, glass-epoxy PC board having the same dimensions that you would choose using the etched-PC-board method. One side of the stripline is smeared with glue (Radio Shack all-purpose adhesive, 64-2307) and firmly pressed against the common base PC board. Parts can be soldered to the stripline immediately (without waiting for the glue to dry). No dc connection is required between the glueline foils, and changes can be made within minutes by lifting the glue-down stripline with a knife and replacing it with one having altered dimensions. This project gives another example of how stripline parameters can be varied to optimize a circuit: homemade variable capacitors.



Circuit Details

See Fig 1. The two-stage amplifier uses an MRF641 (driver) and an MRF646 (final).[2] They were chosen primarily because of their availability in the surplus market. These are controlled-Q devices with a combined minimum gain of 12.6 dB. Although the output stage is rated at 45 W, typical saturated output with a 13.6-V collector supply is about 60 W (including drive power).

The home-brew compression-type variable capacitors, shown in Fig 2, dictated the overall design. I made them as small as possible (to minimize selfinductance), but kept them large enough to provide the necessary capacitance. The nominal $^{5}/_{8}$-inch-square compression plate results in a maximum capacitance of about 10 pF. The material used for the capacitor plates is 0.031-inch-thick Reynolds sheet aluminum, which is available at most hardware and home-supply stores. [Hobby store sheet brass works well in this application, is also commonly available, and is far easier to solder; it is a good alternative to aluminum—Ed.] The capacitor dielectric material is 2.7-mil polyethylene from a Dow Ziploc® heavy-duty freezer bag. Although I have tested this dielectric at a much higher voltage than it is subjected to in this application (at a high-impedance point in a vacuum-tube VHF amplifier), double thickness is used as a safeguard. The insulator between the adjustment screw and compression plate is made from plastic polymer. Most clear plastics used for miscellaneous household applications are of this type. I use plastic from a box used in packaging a tube of Grumbacher acrylic artists paint. Glass-epoxy insulation will work also, but at the higher-voltage


13 V DC,
2A
C12
C13
PENCIL-LEAD
RFC
(SEE TEXT)
RFC
PENCIL-LEAD
RFC
(SEE
TEXT)
RFC
C14
L2
C15
C16
C5
L3
2 W
DRIVE
435 MHz
P1
C1
L1
C2
C3
Q1
C4
C6
DRIVER
13 V DC,
6A
C17
C18
PENCIL-LEAD
RFC
(SEE TEXT)
RFC
C19
C20
C21
L4
Q2
L5
C7
C8
C9
C10
C11
L6
L7
J1
45 W
OUTPUT
FINAL

Fig 1—Schematic of the 435-MHz 45-W amplifier.

C1-C11—Homemade capacitors; see text and Fig 2 for details.
C12, C17—4.7-µF, 35-V electrolytic.
C13, 15, 16, 18, 20, 21—0.001-µF, 50-V disk ceramic.
C14, 19—0.1-µF, 50-V disk ceramic.
J1—Female BNC connector.
L1-L5—Glue-down striplines; see text and Fig 3 for details.
L6, L7—Air-gap striplines; see text and Fig 4 for details.
P1—Male BNC connector.
Q1—MRF641.
Q2—MRF646.
RFC—10 turns, no. 26 enameled copper, air-wound, $^3/_{16}$-in diameter.

applications (especially at C10 and C11) there will be some loss and component heating.

Once I settled on the capacitor configuration, the input and output stripline characteristics were determined experimentally for optimum matching to Q1 and Q2. The related glue-down stripline and pad details are shown in Fig 3. The L2 L4 $^1/_8$-inch-wide striplines act as RF chokes, making the inductance associated with the subsequent disc-ceramic capacitors uncritical. The pads include a number of the capacitor stators (C1, C4, C5, C6, C7 and C9). Foils which contact stator-adjustment screws are reamed out to approximately $^1/_8$-inch diameter to isolate the no. 2-56 screw from the stator. I did this with a large drill ($^3/_8$-inch). Screw contact with the bottom foil may also cause adjustment irregularities, so the foil was reamed appropriately. The stator plates must be completely deburred to prevent puncturing the plasticbag dielectric.

The amplifier output is coupled through C9 to a 1:1 inductively coupled, double-tuned filter. This 50-ohm filter consists of two striplines that are mounted parallel to each other and close together above the base PC board, as shown in Fig 4. Their close positioning establishes the necessary mutual coupling. Each line is tuned to resonance with a variable capacitor.

As indicated in Fig 1, dc-supply decoupling is identical for both stages. The 0.1-µF disk capacitors eliminate a bothersome low-frequency instability mode. RF chokes following these capacitors include two-turn sections with pencil-lead cores to minimize the possibility of parasitics. The 4.7-µF capacitors eliminate low-frequency power-supply instability problems.


C2,3,4,6,7,8
5/8"
5/8"
1/8"
1/4"
1/4"
C1,9
3/4"
1/2"
3/8"
1/4"
1/4"
C5
7/16"
7/8"
1/4"
1/4"
1/8"
5/8"
5/8"
1/8"
7/16"
1/4"
C10, C11
CAPACITOR
PLATE
TAB
NO. 2-56 CAPACITOR
ADJUSTMENT SCREW
3/8" DIA PLASTIC
WASHER
ALUMINUM PLATE
DIELECTRIC
GLUE DOWN STATOR PAD
BASE PC BOARD
NO. 2-56 NUT
SOLDERED TO
BASE PC BOARD
FOIL REAM
1/8" DIA

Fig 2—Variable-capacitor construction details. The "rotor" plates are made from 0.031-inch Reynolds aluminum sheet stock and polished with 320-grit sandpaper to ensure that no burrs are left that may puncture the dielectric material. Plate center holes are $^3/_{16}$-inch diameter. Connections are made to the capacitors by means of no. 26 tinned copper wire, tightly wrapped (and crimped in a vise) around the tab on the capacitor and soldered to the appropriate circuit board connection. Make these connections carefully to ensure good electrical contact. See text for details on the dielectric and washer materials.

Assembly

The transistor-lead configurations are slightly modified to accommodate the glue-down striplines. Both the base and collector leads are bent up into an S shape so that the lead will overlap the stripline by approximately 1/16 inch when the transistor and stripline are mounted flush with the base PC board. The leads are only 0.005-inch thick and can be bent easily with long-nose pliers. Care must be taken to minimize stress at the lead-ceramic junc-


L4, C7 STATOR
2"
SLOT 3/8" X 1/16"
1/8"
5/8"
1"
5/8"
3/16"
L2, C4, C5 STATOR
2"
SLOT 3/8" X 1/16"
SLOT 5/8" X 1/16"
1/8"
5/8"
9/16"
5/8"
7/8"
L3, C6 STATOR
3/16"
SLOT 3/8" x 1/16"
5/8"
3/4"
7/8"
C1, C9 STATOR
3/4"
1/2"
1/4"
1/4"
1/4" X 1/2"
2, 3
1/4" X 1/4"
1
TIE POINTS
1"
L1
3/16"

Fig 3—Glue-down stator pad construction details. Slots are cut with a hacksaw and then polished with a pattern file. The material is 0.062-inch-thick double-sided glass-epoxy circuit board material.[6] After cutting and filing, the pads must be polished with fine steel wool to remove any burrs.

tions. Also, $^3/_{32}$ inch of each emitter lead must be cut off with scissors to allow room for the glue-down pads.

Details of the mounting arrangement are shown in Fig 5. My transistor mounting method was dictated by the dimensions of an old $^1/_8$-inch-thick aluminum panel (with many miscellaneous holes), which I pressed into service as a heat sink. First, I mounted each transistor on separate aluminum subbases. I then fastened the sub-bases to the heat sink. Thermally conductive compound is used between the transistors and the subbases and between the sub-bases and the heat sink. This arrangement permits removal of the heat sink without disturbing the transistor mountings when I need access to the bottom PC-board foil. Note that the base PC board cutout includes notches at the base and collector leads of the transistors to prevent shorting to the common foil.

Detailed assembly like that shown in Fig 6 is easy once the transistors are mounted. Simply smear glue on the pads and fit them into position. Start by positioning L1, followed by the C1 stator, then C1, C2 and C3. Drill holes in the base PC board for the no. 2-56 capacitor-adjustment screws as you go along. At the same time, solder the no. 2-56 nuts on the reverse side (using a screw to hold them in position). Bend the capacitor tabs to make certain the plates will be flush with the stator, inserting the capacitor dielectric as the final step. Make certain the dielectric has been pushed in between the capacitor plates as far as possible (maximum safety margin), and use an awl to puncture the dielectric at the adjustment-screw position. The adjustment screw can then be easily started through the dielectric.

Operation

UHF transistors are great devices, but they can be damaged permanently with just one voltage transient. For example, an accidental short by a probe during a trouble-shooting exercise, or the discharge of a probe capacitor at the transistor's base lead can be disastrous. Another common problem is instability that causes selfoscillation and excessive collector voltage (no insta-


C9 STATOR
L6, L7
2 X 3/16 X 1/16-INCH
PC BOARD MATERIAL
COPPER
S BRACKET
C10, C11
SEE DETAIL
FIG 2
1/16"
1"
3/16"
COPPER
S BRACKET
TIE POINT (FOR RG-58)
1/4" X 1/4"
BASE
PC BOARD

Fig 4—Construction details of the double-tuned output filter. The assembly is supported by copper brackets and parts of the variable capacitors.


NO. 4-40 SCREW FASTENS BASE PC BOARD TO TRANSISTOR MOUNTING BASE AND HEAT SINK. (ONE ON EACH SIDE)
SPACER (TO MAKE CORRECT SPACING BETWEEN TRANSISTOR LEADS AND MOUNTING BASE)
Q1 OD CUT-OUT
EMITTER
BASE
COLLECTOR
BASE CUT-OUT NOTCH
COLLECTOR CUT-OUT NOTCH
GLUE-DOWN PAD L1
Q1
GLUE-DOWN PAD L2
BASE PC BOARD
Q1 MOUNTING SUB-BASE 5 X 2 X 1/8-INCH ALUMINUM
HEAT SINK 9 X 6 X 1/8-INCH ALUMINUM

Fig 5—Pictorial of transistor mounting method. The same scheme is used for both the driver and final transistors.

bility modes are evident in the amplifier described here). These possible failure modes can be avoided by limiting the collector supply to 5 V (or less) during tune-up, as practically all instability modes will be evident at this lower potential (particularly if the input drive is varied over a wide range). Following alignment at 5 V, it is surprising how little readjustment is required when the collector potential is increased to 13 V. (If you can't reduce your power supply voltage, you may want to use a 2N3055 as a pass transistor, driving it with an LM317T regulator [Radio Shack 276-2041 and 276-1778, respectively].) This low-voltage test procedure is mentioned in Motorola Application Note AN-548A.[3]


TIE POINT 2
TIE POINT 3
4.7μF
4.7μF
0.001
0.001
L2, C4, C5 STATOR
RFC
0.1
0.001
0.001
RFC
0.1
0.001
0.001
C10
C11
C1 STATOR
C2
RFC
C5
L3
RFC
C8
L6
L7
C1
Q1
Q2
C9
RG-58
RG-58
L1
C3
C4
C6
C7
C9 STATOR
TIE POINT 1
L4, C7 STATOR
3-1/8 INCHES
2-1/4 INCHES

Fig 6—Circuit board layout of the completed amplifier. Begin construction by measuring the center-to-center distance from Q1 to Q2 and then mount the transistors, working away from them as you mount the other components. Use great care when mounting and soldering the transistors into the circuit to avoid damaging them. The PC board measures 9$^1/_2$ in. x 6 in., and is made from double-sided, glass-epoxy material (Meshna PCB28—see note 1).

Initial Tune-Up

The dummy load/power-measuring assembly and narrow-band peak detector pick-off assembly used in tune-up are the same as the ones that I used with my 15-W transmitter.[4] The dummy load consists of ten $^1/_2$-W resistors connected in parallel and arranged in a circle to minimize self-inductance. Power measurements were made by calibrating dummy-load temperature rise with a dc input (ambient air-temperature conditions, no forced-air cooling). This information is then compared to the temperature rise of the dummy load resulting from the RF output of the amplifier. The "thermistor" used for measuring the temperature rise is a 1N34A (reading the reverse resistance).

Under key-down conditions during alignment, I place a blower at the chassis end to assist the limited heat-sink capabilities of the amplifier. Also, the dummy load requires forced-air cooling, as it becomes very hot in about two minutes under keydown conditions.

Miscellaneous lengths of RG-8/M and RG-58 were used as attenuators to increase power measurement capability of this system.[5] In testing the 45-W amplifier, I used a total cable attenuation of 6.4 dB. This increases the power-measurement capability by 4.4 times.

With a 5-V collector supply and 2 W of drive, first tune the input capacitors for maximum Q1 collector current, then tune the remaining capacitors for maximum power output. The output should be about 8 W. Increase the collector supply to 13 V; minor readjustment will probably be required. My final measurements showed an output of 48 W.

Summary

This is a well-behaved amplifier. After completing an experimental version on the breadboard, I built a new assembly using the data in this article. Alignment of this final model was completed without any problems, and operation is flawless. The glue-down stripline technique is very reliable in this application, and is simple to use.

Notes

[1] J. Reed, "A Simple 435-MHz Transmitter," *QST*, May 1985, pp 14-18, 45.

[2] These transistors are available from RF Parts Company, 1320-16 Grand Aye, San Marcos, CA 92069, tel 619-744-0728.

[3] This note is reproduced in *Motorola RF Device Data* (fourth edition, first printing, 1986) on pages 6-61 through 6-65. Thus book is available from Motorola Literature Distribution, PO Box 20912, Phoenix, AZ 85036, tel 602-994-6561. Cost is $4.75 (plus 15 percent of the total for shipping).

[4] See note 1.

[5] My 435-MHz measurements indicated that the RG-8/M I used has an attenuation of 9.0 dB per 100 feet (specified as 7.5 dB per 100 feet at 400 MHz); the RG-58 has 15.3 dB per 100 feet (specified as 12.0 dB per 100 feet at 400 MHz).

[6] Available from John J. Meshna, Jr. Inc, 19 Allerton St, Lynn, MA 01904, tel 617-595-2275.

By Tarmo Tammaru, WB2TMD **From *QST*, May 1982**

A Solid-State 6-Meter Linear Amplifier You Can Build

Does your 6-meter signal need a little more punch? This amplifier will solve your problem—without breaking the bank!



The new breed of 8-to 10-W, solid-state vhf transceivers offer compactness and relative freedom from TVI. However, there are times when 10 W will not do the job. This amplifier can correct that situation. I used it during the September vhf QSO party and was able to work every station I heard, except one.

The transistor used in the amplifier is a Motorola MRF-492, which is designed for use as an fm amplifier in the "vhf low" public-service band. In this service, the nominal output is rated at 75 W with a 12.5-V collector supply. The manufacturer's data sheet shows a maximum output of 120 W at 16 V. Hence, in ssb service, I felt it would be safe to operate at the 100-W PEP level from a 13.5-V supply. Although no numbers are given, the MRF492 is claimed to have "load mismatch capability at high line and rf overdrive."[1]

Circuit Description

The amplifier schematic diagram is shown in Fig. 1. Since I do not believe in "reinventing the wheel," the output matching network was taken directly from the Motorola data sheet. This network, incorporating L2 and L3 in the signal path, should provide excellent harmonic rejection. The network transforms the 50-Ω load impedance to the optimum transistor load of $0.6 + j1.0$ Ω. Note that this unit, like most rf amplifiers, does not have a 50-Ω output impedance. We simply adjust the output network to obtain the rated power into a 50-Ω load. Fig. 2A is an amplifier output spectral display. While the harmonic suppression is good, additional filtering is required before using the unit on the air. A simple, 5-pole, lowpass filter was placed at the amplifier output, and the resulting spectrum is shown in Fig. 2B. The low-pass filter circuit is given in Fig. 3.

Because the data sheet does not give values for input impedance in Class B service, the input circuit was derived basically by trial and error (the second version worked). The T matching network transforms the highly capacitive input impedance of approximately 1 Ω to a 50-Ω nonreactive load for the exciter.

In a Class B amplifier it is necessary to forward bias the base-emitter junction. There are basically two ways of doing this: the shunt diode method, and the emitter-follower method. The latter method undoubtedly results in lower inter-modulation products, but I have destroyed too many transistors using that method to try it with a $20 device. Forward bias is achieved by using the shunt regulator diode D1. This diode must be connected to the same heat sink as the MRF492, Q1. The voltage across D1 is adjusted to give a Q1 collector current of 100 mA with no drive applied. Do not attempt to set the bias point by measuring the base voltage of Q1 — use a milliammeter in the collector supply lead. I used an unmarked, surplus, 15-A rectifier diode for D1. Almost any diode will work, including power Zeners. I prefer a stud-mounted diode because it is easy to place in contact with the heat sink. Just be sure the polarity is such that the cathode is connected to the case. Several Motorola application notes specify a 1N4997 for this application. Unfortunately, this is a press-fit device. In any case, the heat sink must be grounded.

Parts Procurement

All parts, with the possible exception of an adequate heat sink, are readily available. The MRF492 has recently been advertised by Westcom[2] and Semiconductor Surplus.[3] RFC1 is a Nytronics shielded ferrite choke, designed to reduce coupling


BIAS
D1
100µF
5V
0.047
FB
FBs
+12V
0.01
0.1
25µF
20V
GND
RFC1
RFC2
L2
L3
C5
RF
OUT
MRF 492
Q1
RF
IN
C1
L1
C2
10Ω
1/2 W
C3
C4
E
Q1
TOP VIEW
B
C
E
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k=1000, M=1000 000.

Fig. 1 — The schematic diagram of the amplifier circuit board. Decimal value capacitors are disc ceramic and oolarized caoacitors are electrolytic. Resistors are 10% carbon type.

C1 — 9-to 180-pF mica compression trimmer, Arco 463 or equiv.
C2, C4, C5 — 50- to 380-pF mica compression trimmer, Arco 465 or equiv.
C3 — 80- to 480-pF mica compression trimmer, Arco 466 or equiv.
D1 — 15-A, 50-V rectifier diode (see text).
Fb — Ferrite bead, Radio Shack 273-1571 assortment or equiv.
L1 — 2 t. of no. 14 bare copper wire, $^{13}/_{32}$-inch iD, $^{3}/_{16}$-inch long.
L2— Half loop of no. 14 bare copper wire, $^{19}/_{32}$ inch high, $^{13}/_{32}$ inch long (see photograph).
L3— 2 t. of no. 14 bare copper wire, $^{13}/_{32}$-inch ID, $^{1}/_{4}$-inch long.
Q1 — Motorola rf power transistor, MRF492.
RFC1 — 6.8 µH, Nytronics SWD 6.8 or equiv. (see text).
RFC2 — No. 16 enameled wire, close wound over full length of a 330-Ω, 2-W carbon resistor.



Fig. 3 — A simple low-pass filter for use with the 6-meter amplifier. The design information for this filter was taken from the 1982 ARRL *Radio Amateur's Handbook*. If the filter is mounted outside the amplifier cabinet, it should be enclosed in a metal box for shielding.

C6, C7 — 82-pF, 1000-V sliver-mica capacitor.
L4, L6 — 4 t. of no. 14 enameied wire. $^{3}/_{8}$-inch ID, $^{3}/_{4}$-inch long with $^{1}/_{8}$-inch leads (approximateiy 0.1 µH).
L5 — 6 t. of no. 14 enameled wire, $^{3}/_{8}$-inch ID, $^{1}/_{2}$-inch iong with $^{1}/_{8}$-inch ieads (approximately 0.2 µH).



(A) (B)

Fig. 2 — The amplifier output matching network provides some harmonic suppression (A). To further reduce harmonics, a simple low-pass filter should be used (B). With the filter, au harmonics and spurious signais are more than 60 dB below the carrier, thus meeting current FCC spurious emission requirements for commercial equipment. In these displays, the carrier ievel has been reduced by means of a notch fiiter to avoid anaiyzer overload. Vertical divisions are each 10 dB and the horizontal divisions are each 50 MHz. These measurements were made in the ARRL lab.

between the base and collector circuit. The J. W. Miller 9250-682 should be as good. A toroidal inductor of 1 to 10 µH would also be suitable, since it is across an impedance of 1 Ω. Arco trimmers should be available from your local jobber. I used a surplus heat sink, measuring $3^{1}/_{2} \times 4^{1}/_{2} \times 1^{3}/_{4}$ inches, which is quite adequate for ssb.[4] Anything much smaller will require a fan. Remember, it must be flat on one side. A replacement heat sink for any of the 80- to 100-W 2-meter amplifiers would be ideal.

The Circuit Board

All the components shown in Fig. 1 mount on, or through, the circuit board (Fig. 4). Use double-sided glass epoxy board and cut away narrow channels to separate the various land (foil) areas. To form the channels, use a steel ruler and a sharp utility knife to cut through the foil. Next, pull a hot soldering iron along the strip of foil to be removed. You should see it curl up and away from the board. Start at one end, and pry up with the knife if it gets stuck. You will have to drill two holes, slightly more than $^{1}/_{2}$ inch in diameter, through the board to provide clearance for Q1 and D1. Use a small round file to make the two clearance areas for the flanges of Q1. Connect the ground foils on the top and bottom of the board together by placing short lengths of wire through holes drilled in the board. Place the wires close to the transistor emitter tabs and near each corner of the board. Use pieces of the same type of wire you used to make the inductors, and drill the holes just large enough to pass the wire. Solder the wire on both sides.

Assembly

Make sure you have all the parts on hand before you solder anything to the board. This will ensure that everything fits properly. To keep the inductors in place, I drilled holes through the board and stuck the ends of the wire into the holes. You will have to remove the foil from around these holes on the bottom of the board to keep from shorting the inductors to ground. A large drill bit works fine for this. Center the board on the heat sink, and drill the mounting holes for Q1 and D1. Although you may be able to use screws and nuts to attach Q1 and D1 (depending on the heat sink design), a better method is to tap the holes for the desired screw thread. Mount the board to the heat sink near the corners, shimming it with washers to the same depth as the Q1 mounting flange. Drop Q1 in from the top of the board. The tabs of Q1 should rest just above the top of the board when the flange is in contact with the heat sink. Do not put any upward pressure on the transistor tabs. Never cut or file an rf power transistor body — they contain berillium oxide. It is highly toxic in powdered form and could be inhaled or absorbed through the skin.

Fasten Q1 to the heat sink before sol-



Fig 4—Full-scale circuit-board pattern and parts-placement guide for the 6-meter amplifier. Black represents those areas where copper has been removed by cutting or etching. The 10-ohm base resistor is connected between the base and ground foils, and is positioned next to RFC1.


2V
FB
F1
15A
0.01
D2
+
A
-
M1
+12 V TO AMPLIFIER
+ 1000µF 20V
ND
GND
50Ω 5W
BIAS ADJ.
R1
30Ω 10W
FB
BIAS
+ 1000µF 5V
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS;

Fig 5—Schematic diagram of the bias-adjust circuit and other components not mounted on the circuit board. Decimal-value capacitors are disc ceramic, and polarized units are electrolytic type. Resistors are wire-wound type.

D2—20-A, 50-V rectifier diode.
RFC3—One turn of wire through a TV balun core (part of Radio Shack 273-1571 assortment or equiv.).

dering it in place. Use thermal grease when mounting Q1 and D1. Be sure to solder the full length of the tabs to the board, right up to the body of the transistor. This is especially important for the emitter tabs, because nanohenrys of inductance here translate to decibels of gain loss.

Break off the little tabs on the sides of the mica compression trimmers. Bend the ends of the mounting terminals with pliers to aid in soldering the trimmers to the board. In doing this, be sure the adjusting screw will not touch the board when it is all the way down. C2, C3 and C4 should be oriented so that the screw is connected to the ground end of the capacitor. For C1 and C5 let the screw end be the 50-Ω side.

Putting It All Together

I installed the circuit board and heat sink on the back wall of a $3^1/_2 \times 6 \times 10$-inch Minibox. This is much larger than necessary, but does provide room for relays and a receiving preamp for an eventual remote installation. I usually discard the top (plain U-shaped) half of these boxes and bend up a new piece that fits over the other half, instead of sliding into it.

Fig. 5 shows the biasing circuit and other chassis mounted parts. Control schemes for use with a transceiver are described by Kapplin[5] and Ridpath[6] (also see the ARRL *Radio Amateur's Handbook*). D2 does not have to be heat sinked. It only has to last long enough to blow the fuse in case the wrong supply polarity is inadvertently applied. On the other hand, the 50-Ω bias adjust control (R1) gets quite warm, and should be mounted to the enclosure. In wiring the bias circuit, attach one wire from R1 to D1 and another wire from D1 to the bias point on the circuit board; all other connections are made to the circuit board. If R1 were connected to the circuit board, with a strap going to D1, you would almost certainly damage the transistor if the strap to D1 broke.

Alignment

It is necessary to set the bias before aligning the rf circuits. For an initial check, disconnect the wire between D1 and the circuit board (R1 is connected to D1). Apply power and measure the voltage across D1. It should be possible to lower it to 0.65 V, or less, by varying R1. Set R1 for the lowest voltage and connect the wire from D1 to the circuit board. Now reduce the resistance of R1 until the collector current is 100 mA. Be sure you are measuring collector current and not total supply current (you have about 300 mA flowing into D1).

For aligning the trimmers you will need, at least, an SWR indicator and a 50-Ω dummy load. You will, of course, not know how much power you are getting unless you also have a wattmeter. Connect the amplifier output to a dummy load and apply about 1 W of drive to the input through the SWR indicator. Adjust C1 and C2 for an SWR of 1:1. With CS snug, but not tight, adjust C3 and C4 for minimum collector current. With the SWR indicator or wattmeter connected between the output and the dummy load, adjust all the trimmers for maximum output. If more than one setting gives the same power, pick the one that corresponds to the lowest collector current. Slowly bring up the drive and keep readjusting all the trimmers. With 8 W of drive you should get an output of 100 W. The collector current will be approximately 15 A. Readjust the input for a 1:1 SWR at full power. This may, or may not coincide with maximum gain and you may have to compromise.

During testing you might consider using a harmonica to generate a multitone signal to reduce the average power dissipation (keep the speech processor off). If at any time the heat sink gets so hot you cannot hold your hand on it for five seconds, let it cool off. As a rough indication of power output, I found that at 100 W, a



Interior view of the 6-meter amplifier showing the parts arrangement used by the author. The input matching network is at the right of the photo.

Drake DL 300 dummy load become too hot to hold after two minutes of key-down operation. To prevent rf burns, do not touch the dummy load while rf power is applied.

To maintain linearity, adjust the output circuits for 100 W, even if you are going to operate at 75 or 80 W. I evaluated the amplifier linearity by making two-tone IMD measurements with a spectrum analyzer. At a PEP output of 100 W, the third-order products were 25 dB below the PEP. At 80-W PEP they were down 30 dB. In over 100 contacts, I have not received any adverse comments on the signal quality.

Notes

[1] Motorola Inc., *Motorola Rf Data Manual*, 2nd ed. (Phoenix, AZ: Motorola Inc., 1980), p. 6-15.

[2] Westcom, 1320 Grand Ave., San Marcos, CA 92069.

[3] Semiconductor Surplus, 2822 N. 32nd St., No. 1, Phoenix, AZ 85008.

[4] mm = inches x 25.4.

[5] S. Kapplin, "Boots for QRP Rigs," *QST*, July 1981, pp. 15-20.

[6] I. Ridpath, "T-R Switching with PIN Diodes," *QST*, March 1981, pp. 19-21.

By Wilson Hoag, WA5OLT **From *QST*, April 1982**

Build A 6-Meter "Mini-Lini"

Tired of being a QRP station? Boost your low-level signal with a pair of sweep tubes.

Is low power enough for equality on 6 meters? Perhaps, but it has long been my contention that some stations are more equal than others! One of the great features of 6 meters is the ability to make contacts with just a few watts when the band is open. As solar activity begins to decline, band openings will be shorter and less frequent. This amplifier will add punch to your QRP signal.

The current offerings of solid-state 6-meter transceivers and transverters provide operating ease and good signal quality, but at the expense of rf power output. This, coupled with the paucity of linear amplifiers, resulting from the infamous amplifier ban, has caused an overall reduction in the average power output on 6 meters.

When I acquired my first solid-state rig (an IC-551) some time back, my tendency was to use its scan feature to locate a signal and then work the station with a 240-watt tube-type rig. A minor panic occurred when the tube rig "rolled over and died" midway through the '79-'80 F2 season. The Mini-Lini resulted from that panic.



Design Approach

The amplifier was designed to be compatible with common power supplies, use a readily available tube, provide push-to-talk operation with the IC-551 and have approximately the same rf output as most tube-type transceivers. Fortunately, a design incorporating most of these features had been developed by Ed White, WA5RIA.[1] The major changes I made were in the methods of switching and bias adjustment. The tube used is the 6JB6, which is inexpensive, available and "happy" at 50 MHz. The biasing arrangement, an idea borrowed from Doug DeMaw,[2,3] allows the tubes to be matched for safe parallel operation. This amplifier provides about 50 watts of output when driven by a 10-watt exciter. More than one year of almost daily use has been trouble free and productive (42 states, including KH6 and KL7, plus JA and several Europeans).

Circuit Details

The circuit is conventional and typical of many low-band amplifiers. The original design used a capacitive input, but I thought that the parallel-tuned input method shown in Fig. 1 would provide more output when used with other QRP drivers. This was proven in practice: The amplifier delivers about 20 watts of output when driven by an IC-502. The potential problem of operating unmatched tubes in parallel has been avoided by biasing each tube individually. Component values shown will allow coverage of the entire 6-meter band.

The output network will not reject harmonic energy, and the second harmonic, as measured in the ARRL lab, was less than 40 dB below the fundamental (Fig. 2). This works out to a healthy 5 mW at 100 MHz. Most fm receivers in the neighborhood will detect this easily. FCC requirements for a commercial amplifier at this frequency are to have all spurious radiation at least 60 dB below the fundamental.

To meet this requirement (and to prevent a lot of RFI complaints) a 7-pole Chebyshev low-pass filter was built from data given in the 1982 *Radio Amateur's Handbook*, pages 6-11 and -12. Details of a filter with 0.01-dB of ripple and a 60-MHz cutoff frequency are given in Fig. 3. The coils can be wound on toroids, or be air-core types. Amidon T44-10 (or larger) cores should be adequate. The number of turns required will depend on core size or coil diameter, and can be calculated from data given on pages 2-12 and 2-30 of the *Handbook*. This filter reduced the second harmonic output to more than 65 dB below the fundamental (completely gone for all practical purposes). See Fig. 4.


Z1
6JB6A
R1
BIAS ADJ
2
8
1,7
6
0.005
3
5
0.005
4
K1A
0.001
1 kV
n.c.
K1C
L1
C1
DRIVE TUNE
K1B
J3
Ant.
Z2
0.0022
3 kV
6JB6A
R2
BIAS ADJ
L2
L3
K1D
D1
0.005
RFC2
0.01
1.6 kV
C4
C5
LOAD TUNE
Q1
PLATE TUNE
Octal Plug
Octal Socket
RFC1
0 - 300
mA
3.3 k
Decimal values of capacitance are in microfarads (μF); others are in picofarads (pF); Resistances are in ohms; k=1,000, M=1,000,000.
800 to 1200 V dc
S1A
6.3 V ac
J2
DS2 Filaments ON
S1B
117 V ac
0.01
MOT
DS1
HV ON
S2A
2μF
300 V
Gnd
D2
To 8- or 9-Volt T-R Control
C2
S2B
12.6 V ac
D3
C3
HIGH VOLTAGE
S2C
HV Relay Control
117 V ac

Fig. 1 — Schematic diagram of the 6-meter linear amplifier. The tube filaments can be wired In series, eliminating the need for a separate 6.3.V supply.

C1 — 50-pF miniature air variable, Cardwell 148-4 or equlv.
C2, C3 — 220-μF electrolytic, 50 V.
C4 — 25-pf air-variable, wide-spaced Hammarlund HF30X or equlv.
C5 — 100-pF air variable, Johnson 149-5 or equiv.
D1 — 1N914.
D2, D3 — 1 A, 50 V.
J1, J3 — SO-239.
J2 — Phono Jack.
K1 — 3pdt 12-V dc coil, rf type preferred, or KRP14DG.
L1 — 6 turns no. 14 enameled wire, ½-inch ID x 1-inch long, tapped at approximately 1½ turns.
L2 — 5 turns no. 12 enameled wire, 1½ inch ID x 2½ inches long.
L3 — 2 turns no. 12 enameled wire, 1½ inch ID x ½-inch long.
mA — 0-300 mA dc meter.
MOT — 117-V fan motor.
P1 — Chassis-mount octal plug.
Q1 — NPN power transistor, TIP31 or equivalent, (RS no. 276-2017).
R1, R2 — 10-kΩ, 2-W potentiometer.
RFC1 — 300-μH choke with ferrite bead on the ground lead.
RFC2 — 83 turns no. 28 enameled wire on a ½-inch diameter ceramic form. The coil is 2 inches long.
Z1, Z2 — 1 turn no. 16 enameled wire on 47-Ω, 2-W resistor.



Fig 2—Spectral display of the amplifier output. Vertical divisions are each 10 dB, and horizontal divisions are each 10 MHz.

Construction

It should be possible to duplicate this amplifier for $40 or less, depending on the status of your junkbox. Oddly enough, the tube sockets proved to be the most difficult component to locate, since they are not a common catalog item. The 6JB6 uses a 9-pin NOVAR socket, and the best source turned out to be a shop that specialized in TV replacement parts. Tuning capacitor C4 is a junkbox item of questionable parentage. Any spacing greater than about 0.060 inch (mm = inches × 25.4) should be okay. RADIOKIT of Greenville, New Hampshire would be a good source for all of the variable capacitors.

My amplifier is constructed on an 8 × 10 × 2½ inch chassis (BUD AC-1418) for a base, with 8 × 8-inch end panels. The panels were flanged with ½ × ½-inch aluminum channel for attachment of a cane-metal cover for safety and TVI protection. Component placement is not critical, but all component leads should be as short as possible. The resulting layout was determined largely by some mid-project design changes aimed at making the unit compatible with a newly acquired IC-502. Visible on the lower-right front panel are potentiometers that were reserved for control of a planned rf-operated T-R relay.[4]

The tube sockets are modified slightly to ground the necessary tube elements. Copper washers, cut from flashing copper, fit inside


L1
L2
L3
L4
0.1057
0.2318
0.2318
0.1057
TO AMPLIFIER
C1 74
C2 87
C3 74
TO ANTENNA
INDUCTANCE VALUES ARE IN MICROHENRIES, CAPACITANCE VALUES ARE IN PICOFARADS

Fig 3—Schematic diagram of a 7-pole Chebyshev low-pass filter. Capacitors are silver-mica units, combined in parallel or series to obtain the design values. The text has information about winding the inductors.



Fig 4—Spectral display of the amplifier output with a 7-pole Chebyshev filter. Vertical divisions are each 10 dB, and horizontal divisions are each 10 MHz.



Fig 5—Bottom view of the amplifier chassis. Note the washers on the tube sockets, used to provide a ground connection for the appropriate pins.



Fig 6—Top view of the Mini-Lini chassis. Large heat-dissipating plate caps and a fan help maintain cool operation of the tubes.

the pins on the underside of the sockets. Pins 1, 4, 7, 8 and 9 are bent over and soldered to the washer. The washers are grounded to the chassis with short pieces of no. 14 wire on opposite sides of the socket. Pins 2 and 6 of both tubes are bypassed to ground by connecting 0.005-µF disc-ceramic capacitors from these pins to the copper washers (Fig. 5). The control grids are raised above dc ground while providing a path for rf return. It also permits us to apply a dc bias to the control grid. This will establish the class of operation and cut the tubes off during receive, if desired.

Coils L1, L2 and L3 are wound with solid TW-insulated house wire from the local hardware store. I stripped the insulation from the wire before winding L1 and L2, but left it on L3 to prevent accidental contact with L2. The inside diameters shown are more the result of available cylindrical shapes than any electrical calculation. Coil spacing was adjusted, with the tubes in place, using a dip meter to ensure resonance at the proper frequency.

Heat-dissipating plate caps and a small fan provide cooling for the tubes. See Fig. 6. No thermal distress has been evident under any operating condition. The fan can be wired through S1 or S2, depending on whether cooling is desired during standby operation. Power connections to the fan should be isolated from the chassis.

A possible modification, shown on the schematic diagram, involves the use of a 3pdt relay for K1. The ground legs of R1 and R2 can be wired through one of the normally open contacts. This lifts the potentiometers above ground in the receive mode, applying full bias voltage and cutting off the tubes.

The bias voltage source and relay driver are "hard wired" on a small piece of perf board. The signal for T-R switching is applied to J2. This + 8-V signal is obtained from pin 6 of the IC-551 accessory socket. For use with other rigs, a 9-V battery, wired through a foot switch, works well. Current drain on this battery is low. An rf-operated T-R relay could be used in place of the directly keyed one described in this article. S2 disables the relay driver by removing the 12.6-V ac source in the standby position to permit straight-through operation.

Tune-Up and Operation

Initial tune-up is simple and ordinary. Connect a dummy load and the power supply to the appropriate jacks. Any high-voltage power supply that has an output of 750- to 1200-V dc should be satisfactory. Turn on S1 and allow the heaters to warm up for a minute or more. Switch S2 to turn on the other voltages. Actuate K1 to ground the bias resistors, R1 and R2. Adjust R1 and R2 to obtain 15 mA of idling current for each tube (30 mA total).

Connect the exciter to the amplifier through an SWR indicator. Actuate K1 and apply a small amount of drive. Adjust the position of the tap on L1 for minimum SWR. Be sure to remove all voltages each time you move the tap position!

Next, apply drive to the amplifier and adjust C1, C4 and C5 for maximum power output. For those lacking a wattmeter, an SWR indicator set in the FORWARD position can be used in the line between the amplifer and the dummy load.

Conclusion

The Mini-Lini should be ideal for those looking for more output from their solid-state rigs. Typical operating parameters are 50 watts out for 10 watts of drive, with 1050-V dc on the plates. Reports of signal quality have been complimentary. Enhance your "equality" and come join the fun on 6! I would be happy to answer any questions about the amplifier — enclose an s.a.s.e., please.

Notes

[1] The design was taken from personal correspondence with Ed White, WA5RIA.

[2] D. DeMaw, "Some Ground Rules for Sweep-Tube Linear-Amplifier Design," *QST*, July 1968, p. 30.

[3] D. DeMaw, "Some Thoughts About TV Sweep Tubes," *QST*, Feb. 1980, p. 11.

[4] D. DeMaw and J. Rusgrove, "An RF-Sensed Antenna Change-over Relay," *QST*, Aug. 1976, p. 21.


B+
J3
R8
33k
1W
R7
1M
1W
R6
R5
C6
RF OUT
J2
RFC 4
C7
LOAD
W1
1, 2, 3,
8, 9, 10
V1, 8874
COLLET ONLY
C8
TUNE
RF
IN
J1
C1
15
L1
W2
5
6
L2
RFC1
RFC 2
RFC 3
C2
15
C3
C4
C5
HV
FROM
RF SAMPLER
M2
mA
0-1
S3
GRID
OUTPUT
J7
M1
mA
0-600
R2
400/10W
D1
CW
SSB
R3
10k/20W
F2
3A
8.2V/50W
D6 *
S4 *
K2B
NO
21V/50W
R4
D2
D3
R1
200/10W
SEC.
T1
PRI.
NC
K2C
R9
20/12W
B1
K1A
FIL.
POWER
S1
K1B
S2
T2
PRI.
SEC.
D4
D5
500µF
25V
C9
R10
K2A
J6
PTT
500µF
25V
C10
R11
F1
3A
J4
GND
B-
NEUTRAL
117
VAC
HOT
117
VAC
RELAY CONTACTS:
NO - NORMALLY OPEN
NC - NORMALLY CLOSED
K4A
K3A
AMPLIFIER
RF SWITCHING
(CONTACTS
NOT SHOWN)
J5
* OPTIONAL - SEE TEXT
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k = 1000, M = 1000 000.

Fig. 1 — Schematic diagram of the amplifier.

B1 — 50-ft^3 (1.4-m^3)/min blower, Ripley Sk2754-2A or equiv.
C1, C2 — Air-variable capacitor, 15 pF, E.F. Johnson 189-0565-001, 160-0107-001 or equiv.
C3-C5, incl. — Feedthrough capacitor, 500 pF, 300 V.
C6-C8, incl. — Homemade "flapper" capacitor. Details of construction in text and Fig. 3.
C9, C10 — Electrolytic capacitor, 500 µF, 25 V.
D1 — 50-watt, 8.2-volt Zener diode, IR Z-3307-C or equiv.
D2-D5, incl. — 1-A, 1000-PIV diode, 1N4007 or equiv.
D6 — 50-watt, 21-volt Zener diode (optional — see text).
F1, F2 — 3AG fuses.
J1 — Chassis mount BNC female connector, UG-1094/U.
J2 — Chassis mount N female connector, UG-58A/U.
J3 — High-voltage connector, Millen 37001.
J4, J5 — Power connectors, as available.
J6, J7 — RCA phono jacks.
K1 — Time-delay relay, 90 second, normally open contact, Amperite 115N090T.
K2 — Control relay, 28-volt coil, 1-A 4pdt contacts.
K3, K4 — Coaxial relays equipped with suitable connectors. K4 should have N connectors, K3 may be BNC or N.
L1 — $3\frac{1}{2}$ turns no. 16 enam. wire, $\frac{3}{4}$-inch (19 mm) long, $\frac{1}{4}$-inch (6 mm) diameter.
L2 — $1\frac{1}{2}$ turns no. 16 enam. wire, $\frac{5}{8}$-inch (16 mm) long, $\frac{1}{4}$ inch (8 mm) diameter.
M1 — 1-mA meter movement with shunt to provide 600-mA full-scale deflection.
M2 — 1-mA meter movement with shunts to provide 90-mA (grid current) and 3-kV (plate voltage) full-scale deflection.
R4 — Grid-current shunt.
RFC1 — 10 turns no. 18 enam. wire, close wound, $\frac{1}{4}$ inch (6 mm) diameter.
RFC2, RFC3 — 10 turns no. 16 enam. wire, close wound, $\frac{1}{4}$ inch (6-mm) diameter.
RFC4 — 5 turns no. 16 wire, one inch (25 mm) long, $\frac{1}{4}$ inch (6 mm) diameter.
S1 — Toggle switch, spst.
S2 — Toggle switch, spst.
S3 — Rotary switch, single pole, three position.
S4 — Toggle switch, spst (optional, see text).
T1 — Filament transformer, 6.3-volt, 3-A, Stancor P-6466 or equiv.
T2 — Transformer, 12.6 volts, 1 A.

By Stephen J. Powlishen, K1FO From *QST*, October 1979

A Grounded-Grid Kilowatt Amplifier for 432 MHz

Stable, linear operation for tropo or moonbounce DX... that's the end result of this project.

In the last few years I've built several high-power 432-MHz amplifiers that used tubes from the 4CX250 family. While they worked well in Class C, their performance when biased for linear operation left something to be desired. My previous experience with grounded-grid triode amplifiers on 2 meters was so good that I decided to try the same approach on 70 cm. An Eimac 8874 high-mu triode was selected for this design and a crude prototype was built in a few evenings. After the design was verified, the amplifier described in this article was built. It is stable, compact and delivers over 500 watts output while requiring only a high-voltage supply and a source of about 25 watts of drive. The amplifier has been trouble free in over three years of heavy usage.

Circuit Description

A schematic diagram of the 432-MHz kilowatt is given in Fig. 1. W1 is a half-wavelength stripline which is tuned and loaded by C6 and C7 respectively. Plate choke RFC4 is connected at the approximate electrical center of the plate line. C8 functions as the plate-bypass capacitor. The half-wavelength cathode line is comprised of W2, L2 and C2. L1 and C1 serve to match the tube input impedance to the amplifier 50-ohm input. As the grid is grounded for dc as well as rf, D1 is used to develop operating bias at the cathode. R3 is switched in to supply near-cutoff bias during standby periods. M1 is used solely to monitor plate current in the high-voltage supply negative-return Lead. M2 is switched to read grid current, high voltage and relative output. The latter function is by means of an external line sampler.[1] With the exception of the multimeter functions the metering and bias circuits are similar to those in a 220-MHz amplifier.[2]

Separate coaxial relays attached to the



The high-power uhf amplifier. The toggle switches control filament power and standby/operate functions respectively. Multimeter unction is selected with the switch located between the meters, while the plate tuning and loading controls are at the right. Modern nobs and homemade meter faces give the amplifier a commercial appearance.

input and output terminals allow the amplifier to be switched in and out of the line in a manner popular with hf amplifiers. Time-delay relay K1 prevents the amplifier from being switched into service for 90 seconds after the tube heater is energized, allowing the element to reach operating temperature. A normally closed contact of K2 applies full voltage to the heater during standby periods. The voltage is reduced during operation as recommended by the manufacturer.

Construction

Plate and cathode-compartment construction is from 0.032-inch (0.8-mm) thick aluminum sheet attached to $^1/_2$-inch (13-mm) aluminum angle stock. Some angle stock may be anodized, giving the surface a dull appearance. This material must be lightly sanded to remove the anodized metal, which is a poor conductor. Holes are drilled in the angle stock to allow attachment of the covers; these are tapped for no. 4-40 screws. Details of the 10.5 × 4 × 3-inch (267 × 102 × 76-mm) plate compartment may be seen in the top view photo. Construction of the cathode compartment is similar, and may be seen in the photo of the underside. It measures 4 × 4 × $1^3/_4$ inches (102 × 102 × 44 mm). The aluminum brackets holding the rf enclosures to the front panel also serve as end covers for the compartments. Compartment spacing from the panel is four inches (102 mm). A $5^1/_4$ × 19-inch (133 × 483-mm) rack panel is used.


Top view of the amplifier, with the plate compartment cover removed. The tube, plate line (W2) and RFC4 may be seen at the top of the photo. Note the large number of holes drilled in the plate compartment to receive the cover hold-down screws. A tight seal is required to prevent rf and air leaks.


This bottom view shows the cathode compartment and the shafts for C6 and C7. A cover is placed over the cathode compartment during tuneup and operation.

The plate line was fabricated from a piece of $^1/_{16}$-inch (1.6-mm) thick brass. Fig. 2 gives detailed information for making the line. In addition to brass, lines were made from copper, both unplated and silver plated, with no discernible difference in efficiency. Double-sided G-10 printed circuit board would probably work as well. Best thermal stability was obtained with the unplated solid-copper line. The line is supported by 1.5-inch (38-mm) long ceramic insulators, although standoffs made of Teflon will also serve. C6 and C1 are made from beryllium-copper sheet. Details of their construction appear in Fig. 3. These "flappers" are moved with fishing line which is tied to $^1/_4$-inch (6.4-mm) fiber shafts. These shafts may be seen in the underside view.

The anode collet (Eimac no. 008294) is secured to the bottom of W1 with standard 60/40 solder. Use no. 4-40 screws and nuts to hold the collet in place during the soldering operation. The grid collet (Eimac no. 882931) is attached to the chassis with eight no. 4-40 machine screws and nuts. A poor ground connection for the grid will greatly increase the amplifier drive requirements or make the unit totally inoperative.

C8, the plate-bypass capacitor, is made from two brass plates, one mounted on either side of the plate compartment. A 0.005-inch (0.13-mm) thick piece of Teflon sheet is used for the dielectric material. While this Teflon thickness may seem inadequate, it is rated at 1000 volts per mil (0.03 mm) thickness. It is necessary to coat the dielectric with Dow Corning type DC-4 silicone grease to fill in any imperfections in the surface that might allow a leakage path and subsequent capacitor breakdown. This silicone grease has dielectric properties similar to Teflon* A no. 8 (4-mm) brass screw is used to hold the plates in place, and also acts as the high-voltage feedthrough terminal. A 3/8-inch (10-mm) diameter washer was sliced from a Teflon rod and used to center the screw in the hole. Fig. 4 gives details of the remain-



Fig 2—Dimensions of the plate line are given here. The line may be constructed from $^1/_{16}$-inch (1.6-mm) thick copper or brass. Corners of the line should be filed to give a $^3/_{16}$-inch (5-mm) radius.

*Alternatively, an Erie 2498-001-X5U0-102M 1000-pF 4-kV feedthrough capacitor may be used. This component is available from ARCOS, P.O. Box 546, East Greenbush, NY 12061.

By E.R. "Chip" Angle, N6CA

From *QST*, March 1985

A Quarter-Kilowatt 23-cm Amplifier

Imagine, a linear amplifier with great efficiency and long-term stability that is super quiet and small in size. Sounds like HF? Not exactly...



To me, there is nothing more frustrating than having to dig through a construction article to find out exactly what performance you can expect from the finished product. So here it is:

1) Grounded-grid 7289/2C39 cavity amplifier, single tube.

2) Linear operation (what you put in, you get out, only more of it).

3) Covers 1240 to 1300 MHz.

4) Power. gain ranges froth 12-20 dB depending on output power, input power, loading, anode voltage and grid bias voltage.

5) 50-ohm input and output — no stub tuner required.

6) Power output greater than 200W with about 12-W drive.

This is Part 1 of a two-part article. In this installment, I describe the design and construction of the RF deck. Part 2 describes power-supply construction, testing and operation.

This amplifier is a tried and proven design. Much development work has gone into this project. The amplifier works well, is reliable and can be duplicated. More than 50 of these amplifiers have been built to date. I have successfully worked many 1296-MHz EME (earth-moon-earth) stations with one of these amplifiers and a 384-element loop-Yagi array during the past year. Amplifiers of this design were used on both ends of the first California-to-Hawaii QSO on 1296 MHz. Another unit has logged more than 20,000 hours of continuous operation at the KH6HME beacon.

General Design Approach

A cavity amplifier is similar to a conventional amplifier designed for lower frequencies. The tube anode excites a resonant circuit, and power is in turn coupled into a load, usually 50 ohms. Instead of using coils and capacitors, as at lower frequencies, the cavity provides the resonant circuit necessary to tune the amplifier output.

The anode cavity of this amplifier is a squat cylinder. Cylinder height is set by mechanical tube requirements. The inside diameter of the cylinder sets the highest resonant frequency. Any capacitance added from the top to the bottom of the cavity will lower its resonant frequency, as will increasing the cavity diameter.

This amplifier uses $^{1}/_{8}$-inch-thick copper plates for the cavity top and bottom, and a thick-wall aluminum ring, cut from tubing, for the walls.[1] This heavy construction virtually eliminates all resonant-frequency variations caused by thermal and mechanical changes.

Fig. 1 is a schematic diagram of the cavity amplifier. The circuit is simple. Filament voltage and cathode bias enter the RF deck through feed-through capacitors (C4, C5) and RFC1 and 2. High voltage is fed to the anode through RFC3. C8, the anode bypass capacitor, is homemade from Teflon® dielectric sandwiched between a copper plate and the chassis.

The input pi network easily tunes the entire band at any power level. it is made from two Johanson piston trimmer capacitors and a "coil" made from copper wire. An input cavity is not necessary at 23 cm.

Output coupling is through a rotatable loop that serves as a variable loading control. This allows amplifier-tuning flexibility; it may be tuned for maximum gain or for maximum power. Light loading can produce stable power gains of up to 20 dB.

Amplifier tuning is accomplished with a homemade cylindrical coaxial capacitor with Teflon dielectric (C6). There are no moving metal parts to cause erratic performance. The Teflon rod/tube screws in and



Fig. 1 — Schematic diagram of the 23-cm amplifier.

C1 — 3-pF dipped mica capacitor.
C2, C3 — 1- to 10-pF piston trimmer capacitor (Johanson no. 3957, 5201 or equiv.).
C6 — Anode-tuning capacitor. See text and Fig. 11.
C7 — Anode-bypass capacitor, 90 pF. Homemade from copper plate and Teflon sheet. See text and Figs. 5, 12 and 15.
C8 — Disc ceramic, 0.0047-µF, 3-kV capacitor.
J1 — 5-mm SMA connector, chassis mount, female.
J2 — Modified Type-N connector. See text and Fig. 7.
J3 — Female chassis-mount BNC connector.
Li — Loop of no. 18 bus wire soldered between C2 and C3. See Fig. 15.
L2 — Output-coupling loop. Part of output-connector assembly. See text and Fig. 7.
RFC1, RFC2 — 5 turns no. 20 bus wire, $^3/_{16}$-inch ID.
RFC3 — 3 turns no. 20 bus wire wound on a 20-ohm, 1-W carbon-composition resistor.



HOLES USED:
RING — A
ANODE PLATE — A, B, C, F, H
GRID PLATE — A, C, D, G, H
ANODE BYPASS-CAPACITOR PLATE — B, E, H
FRONT PANEL — C, G
I = RING ALIGNMENT NOTCH

- ALL HOLES 1/16" DIA. OR SMALLER
- MATERIAL: 1/16" ALUMINUM
- ALL DIMENSIONS IN INCHES
- ALL PLATES ARE VIEWED FROM FRONT PANEL
- HOLE DESIGNATIONS ARE MAINTAINED ON ALL DRAWINGS

Fig 2—Complete dimensions for the aluminum template.

out of the coaxial capacitor, increasing or decreasing the capacitance by changing the amount of Teflon dielectric inside the cylinder. With the rod all the way in, the dielectric is all Teflon; with the rod all the way out, the dielectric is all air.

Teflon has a relative dielectric constant (relative to air = 1) of 2.05, which means that the value of the capacitor with the rod all the way in is twice the value of the capacitor with the rod all the way out. Full capacitance will pull the resonant frequency of the amplifier down to 1240 MHz. Use of only one tuning adjustment means the amplifier will have more gain because cavity shunt capacitance has been minimized.

Thermal Considerations

The cavity walls are formed by a thick-wall aluminum ring, which is sandwiched between two thick copper plates. RF and thermal properties of these two metals are reasonably close, whereas brass is rather poor in both respects. The 7289/2C39 tube used in this amplifier is being run at 2-2½ times its normal dissipation rating; therefore it's important to have a cavity that remains thermally stable.

Most previously described amplifiers have used sheet brass in their construction. This has usually meant constant retuning of resonance to maintain output power at or near maximum.

The copper and aluminum construction in this amplifier has solved all thermal stability problems. The amplifier can easily be run key down for over an hour at 200-W output without retuning. This, of course, is obtained only with a good tube and water cooling. A practical water cooling system will be described in Part 2 of this article.

Water cooling keeps the internal structure of the tube thermally stable. When air cooling is used for output levels of 100 to 150 W, output power fluctuations are a direct result of internal tube changes. These changes vary from tube to tube and must be tested for. In some cases, otherwise perfectly good RF tubes have had poor thermal stability. Such tubes can make good drivers at lower power levels.

"Using Simple Hand Tools Will . . ."

Hand tools are great if you are skilled and patient. Most people want to hurry up and finish their new project. If that's you, then have a machine shop make all of the parts, leaving you only the final assembly. It should cost about $200. The parts are not difficult to fabricate, but the process is time consuming. If you have the time and patience to do it yourself, this amplifier can be very inexpensive.

Gathering the Materials

All of the materials used in this amplifier are fairly common and should be available from suppliers in most metropolitan areas. Some suppliers have "short sale" racks, where they sell odd pieces cut off standard lengths or sheets at reduced prices. The parts for this project are small enough to be fashioned from cutoff stock. Surplus-metal houses have some great buys, so start there if one is nearby.

The key to successfully completing this project is careful layout work before cutting or drilling any parts. Invest in a can of marking dye, a sharp scribe, an accurate rule, vernier calipers and several center punches. These tools are available at any machinists' supply shop. The marking dye will make cutting and filing lines much easier to see. Measure all dimensions as carefully as you can and then recheck them before cutting. Mark with a sharp scribe because the sharper the scribe, the finer the marked line, and the finer the marked line, the closer your cut will be to where it should be. Remember—the accuracy of your drilled holes is only as good as your center-punching ability, so use a fine punch for the first mark and then a bigger one to enlarge the mark enough for drilling.

Access to a drill press is a must. It's extremely difficult to drill holes accurately with a hand drill. Although they are not absolutely necessary, you should have access to a lathe or milling machine.

Other tools that will aid you with this project are a nibbling tool, a set of punches, a new set of files and some sharp drill bits. If you don't already have one, purchase a file card to clean metal shavings out of your files as you work. Clean, sharp files are faster and more accurate to work with. You'll also need an assortment of sandpaper for the final finish work.

The Template Approach

I highly recommend fabrication of a single template for marking and drilling the anode plate, anode bypass capacitor, cavity ring, grid plate and front panel. The template shown in Fig. 2 has all of the holes for these parts. If you use the template, you'll only have to make the careful measurements once — after that, it's simple to mark and drill the rest of the parts.

The template approach offers several other advantages. A template makes it much easier to maintain accuracy between the anode plate, cavity ring, grid plate and front panel; these parts will fit perfectly because they were all drilled from the same master. The template approach also makes it possible to set up a small production line if you decide to build more than one of these amplifiers and combine them for higher power, or if a friend wants to build an amplifier along with you.

See Fig. 2 for complete template dimensions. Start with a piece of 1/16-inch-thick aluminum stock that is larger than you need and degrease it with soap and water. Dry it off and spray it with marking dye. Scribe a 4-inch square on the stock and cut the template to size. A shear will make this job much easier, but it can be cut with hand tools and filed to size.

Carefully measure and scribe all holes. Note that holes A and B are on the circumference of circles. Use a compass to scribe the circles, and then locate the holes. After you have marked and checked all holes, centerpunch and drill them. The holes should be drilled with a 1/16-inch or smaller bit. Recheck all measurements. If you goof, start again. The time you spend making the template as perfect as you can will save you much time and aggravation when you make and assemble the other parts.

When you finish the template, mark the front side for future reference. All plates made from the template are marked and drilled from the front side (as viewed from the front panel).

Making the Copper Plates

Once you have completed the template, it will be easy to make the copper plates. The anode plate, grid plate and anode-bypasscapacitor plate are all made from ⅛-inch-thick copper. See Figs. 3, 4 and 5 for the dimensions of these pieces.

Measure and cut the three plates to the proper dimensions. Carefully break (deburr) all sharp edges to avoid small cuts to your fingers and hands.



HOLE: A — 0.144-IN DIA. (NO. 27 DRILL). COUNTERSINK BACK SIDE TO 1/4-IN DIA. WITH A 100°C SINK.
B — 0.106-IN DIA. (NO. 36 DRILL), TAPPED NO. 6-32.
C — 5/32-IN DIA. (0.156). FOR ANODE TUNING POST, THIS SIDE.
F — 0.089-IN DIA. (NO. 43 DRILL). TAPPED NO. 4-40 FOR ANODE BOX MOUNTING.
H — 1.500-IN DIA.

Fig 3—Drilling details for the anode plate. See Fig 2 for additional information on hole location.



HOLE: A — 0.144-IN DIA. (NO. 27 DRILL).
C — 7/16-IN DIA. (0.438). ANODE TUNING COLLAR INSERTS FROM THIS SIDE.
D — 1/8-IN DIA. (0.125). FOR CATHODE-GRID MOUNTING.
G — 0.144-IN DIA. (NO. 27 DRILL). FOR FRONT PANEL MOUNTING.
H — 7/8-IN DIA. FOR GRID FINGER STOCK. FINGERS PROTRUDE OUT BACK SIDE.
NOTE: BRASS INPUT ENCLOSURE MOUNTS ON THIS SIDE.

Fig 4—Drilling details for the grid plate. See Fig 2 for additional information on hole location.



HOLES: B — 1/4-IN DIA.
E — 0.070-IN DIA. (NO. 50 DRILL). TAPPED FOR NO. 2-56 FOR HIGH-VOLTAGE LUG.
H — 1-1/4-IN DIA. FOR ANODE FINGER STOCK; FINGERS PROTRUDE OUT BACK SIDE.

Fig 5—Drilling details for the anode bypass capacitor plate. See Fig 2 for additional information on hole location.

Clean the plates with alcohol and spray them with marking dye. Clamp the aluminum template to each plate, and carefully scribe the correct holes. Remember that all plates do not have the same holes. The anode plate uses holes A, B, C, F and H; the grid plate uses holes A, C, D, G and H. The anode-bypass-capacitor plate uses holes B, E and H.

Use a small center punch to punch all holes lightly. If they then look accurate, enlarge them enough for drilling.

Copper isn't the easiest metal to work with. It's very stringy, and drilling it can be frustrating. You'll need the proper drill bits for best results. Special drills can be purchased, or you can use a grinder to carefully remove the sharp points on the outer edge of the cutting surface of each side of a standard drill bit. This will eliminate any tendency for the copper to grab. Practice on an old bit and be sure to grind it symmetrically. Modified drill bits can still be used on aluminum and other metals.

Always start with a smaller drill and work up to the final hole size. It's safer and more accurate. The larger holes can be cut with a flycutter, or you can drill a series of smaller holes around the inside of a larger hole and file to finish. Either way is fine. Use lots of cutting fluid to lubricate the drill bit, and wear safety glasses and an old shirt. Remember, some cutting fluids are not to be used on aluminum.

Start with a no.50 (0.070-inch) or smaller bit and drill pilot holes at each of your punched marks. The details for finishing each hole are listed in the drawings. Some holes are countersunk or tapped. Pay attention to the details, and take your time.

When you are through drilling, you must deburr each hole. Copper is soft, so it tends to rise up around the hole during drilling and deburring. Use a flat file for the initial cut, and then remove any remaining material with a countersink. File the copper plates flat again; a flush fit on both sides of the aluminum ring is important.

When all copper work is done, you should be able to stack the plates and see all pertinent holes align correctly. Enough tolerance is included in the dimensions to accommodate minor errors. After the holes are drilled, it can be difficult to tell which side of each plate is which, so mark the front side of each plate with a permanent marker.

Machining the Ring

The aluminum ring that forms the cavity wall is cut (sliced) from a length of 3½-inch OD tubing with a ⅜-inch wall thickness. See Fig. 6. The tubing ID is about 2¾ inches. The dimensions of the ring are the most critical in this amplifier. Tolerance of the ring thickness is ± 0.005 inch to maintain full band coverage.

The ring can be hacksawed or bandsawed out of the tubing, but take extreme care to be accurate. Cutting tubing straight isn't easy. Clamp the tubing to prevent rotating on the band saw. The final finish cut is best done on a lathe or milling machine, but careful filing will work.

Once the ring is the correct thickness, deburr the sharp edges and spray it with marking dye. Notice that the outside and inside diameters are not concentric. This is normal for large tubing. Lay the ring flat and find the thickest wall section. Scribe a


NO. 5/8-24 TAPPED
OR NOTE X
0.402"
0.402"
TEMPLATE
ALIGNMENT
NOTCH
TEMPLATE
FLUSH WITH RING
THICKEST
SECTION
0.390" TYP
A
SCRIBE
LINE
FAB. FROM
3½"-OD ALU. TUBING
WITH 3/8" WALL
=2¾" ID.
NOTE
(11 PLACES)
0.360" TYP
SCRIBE
LINE
0.605"
± 0.005
CAVITY RING
(VIEWED FROM FRONT PANEL)
NOTE: HOLE A — 0.089-IN DIA. NO. 43 DRILL. DRILLED THRU AND TAPPED GREATER THAN 3/8-IN DEEP WITH NO. 4-40 TAP FROM EACH SIDE.
NOTE X: NO. 5/8-24 TAPPED OR 5/8-IN-DIA. TUBING WITH SET SCREW FROM GRID PLATE SIDE. (SEE TEXT).

Fig 6—Details of the cavity ring. See Fig 2 for additional information on hole location.


STANDARD N FEMALE CONNECTOR
5/8" OD
7/16" ID
FAB. FROM 5/8" D BRASS ROD
(OR BRASS TUBIN SEE TEXT)
5/8"
OUTPUT COUPLING SLEEVE
END OF COUPLING SLEEVE
OUTPUT COUPLING SLEEVE
0.675"
0.525"
SOLDER IN PLACE
SOLDER
5/32"
FAB. FROM 0.032" COPPER SHEE

Fig 7—Output-probe/connector assembly details.

line across the wall at this point, across the center of the ring and across the wall on the other side. The scribed lines on each side of the ring will be used to align the template. The output connector will be placed at the thick wall section.

Carefully align notch I on the template with the line scribed on the thickest wall section on the ring. Clamp the template onto the ring. Mark each of the 11 holes labeled A on the template. After you mark the holes and remove the template, check alignment with the copper plates just in case. If everything lines up, center punch all eleven holes on one side of the ring only, and drill each hole completely through the ring. Use lots of cutting fluid. File the ring flat before and after deburring, taking care not to change the wall thickness. Tap each hole to accept no. 4-40 machine screws. Each hole will have to be tapped to a depth of at least $^3/_8$ inch from both sides because long taps don't exist. The inside of the ring doesn't need to be polished.

The hole for mounting the output connector can now be drilled. There are two ways to mount this connector, and either scheme works fme. Read ahead to the section on making the output connector for more information. The first method of mounting the connector involves tapping the ring with a no. $^5/_8$-24 tap and using a lathe to cut matching threads on the output connector coupling sleeve. Large taps are expensive, but a tap and die for Type-N connectors are handy if you do much building.

If you don't have access to a lathe or a large tap, the second method is easier. Make the output connector coupling sleeve from $^5/_8$-inch-OD brass or copper tubing, and drill the ring to just clear it. Then drill and tap the grid-plate side of the ring above the output connector to accept a setscrew. Also, drill a clearance hole in the grid plate for the setscrew. Use the setscrew to secure the output connector.

Output Connector

A standard Type-N chassis-mount female connector (silver plated) is used for the output probe/connector. See Fig. 7. First, remove the flange with a hacksaw and file flush with the connector body. Next, make the output-coupling sleeve that is right for your application (threaded orunthreaded, depending on how you fabricated the ring). The sleeve will be the same length in either case. The output-coupling loop is fashioned from a piece of 0.032-inch-thick copper sheet that is $^5/_{32}$ inches wide. Bend it to the dimensions shown in Fig. 7. We will solder the output connector together later.

Grid Compartment

The grid compartment measures 2 inches square by $1^1/_2$ inches high. See Fig. 8. It is made from brass and can be sawed out of square tubing or bent from sheet. The cover can be made from any material.

I use two small PC boards (Fig. 9) for


0.475"
1.05"
Z C2 Z
X
X C3
Z
GRID PLATE
INPUT CONNECTOR
2.0"
0.800"
C C
H
ANODE TUNER
2.0"
VIEWED FROM FRONT PANEL
COVER, FAB. FROM 0.020" ALU. OR BRASS
NO. 4-40 TAPPED 3 PLACES
HOLES: X = 1/4" DIA.
Z = 7/32" DIA.
1.50"
Z C4 Z
Z
Z
C5
Z Z
7/8"
1/2"
3/4"
3/8"
GRID BOX
GRID PLATE
3/8"
7/8"
1-3/8"

Fig 8—Input-compartment details.


3/4"
3/4"
3/8"
3/8"
D
H
D
3/8
3/8"
HOLES: O = 1/8" DIA.
H = 1/2" DIA.
COPPER, BOTH SIDES
CATHODE FINGER STOCK
SOLDERED IN HOLE H.
CATHODE BOARD
5/16"
3/4"
5/16"
3/4"
D
H
D
5/16"
5/16"
HOLES: D = 1/8" DIA.
H = 5/16" DIA.
COPPER,
BOTH SIDES
FILAMENT PIN SOLDERED
IN HOLE H.
FILAMENT BOARD

Fig 9—Cathode and filament PC-board details.

holding the finger stock that makes contact with the filament pin and cathode ring on the 2C39 tube. These boards are cut from 1/16-inch-thick, double-sided G-10 glass-epoxy stock. The copper pattern is identical for both sides of each piece. Mark and drill or file the holes first, and then cut the boards to size. Small boards are difficult to hold while drilling them. Mark each side of each board and score the copper foil with a sharp knife.

The unwanted copper can be removed easily by heating the foil with a soldering iron and lifting it off. Use a flat file to deburr the boards. Do not use a countersink because the copper foil must be as close to the holes as possible to facilitate soldering the finger stock in place.

The input connector that I use is a 5-mm SMA type. This is an excellent RF connector, especially for low-power UHF applications. I highly recommend use of an SMA, but any small screw-on connector will do. If you really feel you have to use a BNC then do so, but it's a lousy connector at frequencies above 200 MHz. Remember to move the connector hole to accommodate its larger size.

The input connector must be as close as possible to the first input capacitor. The lead length of the input dc blocking capacitor must be as short as possible. The 3-pF capacitor is series resonant at 1200 MHz only with short (1/16-inch or less) leads.

Miscellaneous Bits and Pieces

There are still several small, but very important parts to fabricate. The front panel I use is shown in Fig. 10. It is made from a piece of 1/8-inch-thick aluminum sheet. Some builders may wish to mount the amplifier on a rack panel. Wash and dry your front-panel material and spray it with marking dye. Clamp it to the template and mark the holes. Check the hole alignment with the copper grid and anode plates. If all lines up correctly, center punch and drill the holes. The only front-panel control is for the anode tuning capacitor, which is adjusted by a 1/4-inch shaft protruding through a 3/8-inch panel bushing in hole C.

The anode tuning collar, shown in Fig. 11A, is made from a piece of 1/2-inch OD brass rod. This rod has a 3/8-inch hole drilled through its center, and it is turned down to 7/16-inch OD for half its length. The inside of the 1/2-inch-OD end is tapped to a depth of 1/4 inch to accept 3/8-24 threads. This collar will be inserted into hole C on the grid plate.

Fig. 11B also shows the anode tuning post. It is simply a length of 5/32-inch-OD brass rod that inserts into hole C on the copper anode plate. This rod will form one plate of the anode tuning capacitor.

The anode tuner (Fig. 11C) is machined from a piece of 3/8-inch-OD Teflon rod. One end of the rod is drilled out with a no. 21 drill. The outer wall of this end is threaded with a no. 3/8-24 tap. This is the end that will thread into the anode tuning collar and slip over the anode tuning post. The other end is turned down to fit inside a 1/4-inch shaft coupler.

Fig. 12 shows the remaining parts. The tuning shaft (A) is made from a piece of 1/4-inch brass rod. A coupler (B) to connect the tuning shaft to the anode tuner may be purchased or made. This also applies to the front-panel spacers (C). The Teflon dielectric for the anode bypass capacitor (D) is made from 0.010-inch-thick Teflon sheet. Use the template to locate holes B and H. Teflon washers and inserts (F) are used to insulate the mounting hardware for the anode bypass capacitor from the chassis. The inserts are made from 1/4-inch-OD Teflon rod. The washers are made from Teflon sheet. Sharpen a piece of 3/8-inch aluminum tubing and chuck it up in a drill press. This tool will cut neat, round washers from the sheet.

The box that encloses the anode compartment (Fig. 13) is fabricated from a Bud AU-1083 utility cabinet. Clean the chassis and spray it with marking dye. Secure the template to the side of the enclosure that contacts the anode plate and scribe the holes labeled F. Make sure that these holes line up with the holes on the copper anode plate. If they do, center punch and drill them to size. If air cooling is used, the blower will mount to this box.


4.0"
5¼"
G
G
C
G
G
FRONT PANEL
(VIEWED FROM FRONT)
HOLES: C - 3/8" DIA. PANEL BUSHING WITH EXCESS THREADS REMOVED. H.H.SMITH NO.119 OR EQUIV.
G - 0.144" DIA. (NO. 27 DRILL)
FAB. FROM ALU., RACK PANEL OR SHEET.

Fig 10—Front-panel details.


(A)
NO. 3/8-24 THREADS
1/4" LENGTH
1/4"
1/2" DIA.
7/16" OD
3/8" ID
FAB. FROM 1/2" OD BRASS ROD
1/2"
1/2"
INSERTS INTO HOLE C ON GRID PLATE
ANODE-TUNING COLLAR
(B)
1.325"
5/32" OD
FAB. FROM 5/32" OD BRASS TUBING
INSERTS INTO HOLE C ON ANODE PLATE
ANODE-TUNING POST
(C)
2.725"
COUNTER SINK
1-1/4"
1/16" HOLE TO AID IN CLEANING THREADS
3/8" OD
1/4" DIA.
NO. 3/8-24 THREADS
3/8"
0.159" DIA.
1-1/4" DEEP
(NO.21 DRILL)
FAB. FROM 3/8" OD TEFLON ROD
ANODE- TUNER

Fig 11—Anode-tuning capacitor details.


2-1/4"
1/4" DIA. BRASS ROD
DEBURR EDGES
TUNING SHAFT
(A)
3/4"
H.H. SMITH NO.120
COUPLER
1/2" OD
1/4" ID
SET SCREWS
SHAFT COUPLER
(B)
3-1/2"
ALU. ROD
TAPPED NO. 6-32
BOTH ENDS, 1/2" DEEP
1/4" DIA.
FRONT-PANEL SPACER
(4 REQ'D)
(C)
1-1/2"
1-1/2"
0.010"
1-1/2"
1-1/2"
B
B
B
B
H
ANODE-BYPASS-
CAPACITOR DIELECTRIC
(D)
FAB. FROM 0.010" TEFLON SHEET
HOLES: B = 5/32" DIA.
- PUNCH OUT
H = 1-1/16" DIA.
- COMPASS KNIFE CUT
0.144"
3/8"
0.020"
TEFLON
1/8"
1/4" OD
TEFLON
0.144 ID
ANODE-BYPASS-
CAPACITOR WASHER
ANODE-BYPASS-
CAPACITOR INSERT
(E)
(4 REQUIRED)

Fig 12—Miscellaneous parts necessary to complete the amplifier.


ANODE ENCLOSURE
F
F
F
F
ANODE PLATE
ATTACHES TO THIS SIDE
J3
5/8"
3/8" DIA.
1"

Fig 13—Anode-enclosure details.


4"
OR LARGER
1/2"
4" OR
LONGER
C
H
1/2" DIA.
1" DIA.
5/32" DEEP
TO ALIGN
GRID FINGER
STOCK
FAB. FROM ALU. PLATE
SOLDERING FIXTURE
5/32" DEEP

Fig 14—Dimensions of the soldering fixture. See Fig 2 for more information on hole location.

Soldering the Subassemblies

Once all copper and brass parts are drilled and deburred, they should be cleaned with alcohol and Scotch-Brite®, a nonmetaffic pot cleaner, and washed in alcohol again. Set the pieces aside and avoid touching them. Fingerprints will inhibit soldering.

I have found that the best way to solder the heavy brass and copper parts is to first build the soldering fixture shown in Fig. 14. This soldering fixture, made from 1/2-inch-thick aluminum plate, will evenly heat the entire assembly to be soldered. Even heating will allow you to do a much better soldering job than you could otherwise.

The soldering fixture should be preheated on a stove or hot plate until bits of solder placed on its surface just melt. At this point, reduce the heat slightly. Avoid excessive heat. If the copper parts placed on the fixture suddenly turn dark, it's too hot.

Solder the grid plate assembly first. You will need the copper grid plate, grid finger stock, anode tuning collar and brass input compartment.[2] Look at the drawings again to be sure that you know which parts go where. Insert the grid finger stock into hole H on the grid plate. As viewed from the front-panel side, the curved fingers will protrude out the back side, away from you. Apply liquid or paste flux and set the grid plate in the soldering fixture. The finger stock will fit in hole H in the fixture, allowing the grid plate to rest flush with the surface of the fixture. Next, apply flux to the anode tuning collar and insert it in hole C of the grid plate. Part of the tuning collar will slip into hole C in the soldering fixture. Make sure the collar seats flush with the grid plate. The flux should start to bubble.

Carefully apply solder directly to the joints of the installed parts. The solder should melt almost immediately and flow bright and smooth. Next, place the square brass input compartment in place and apply flux. In a few seconds, it can be soldered by running solder around the joints, inside and outside. If you have trouble getting it to flow on both sides, merely tap the brass box aside (1/16 inch) and return it to its original position.

Now comes the hard part — getting the soldered assembly away from the heat without disturbing the alignment. A pair of forceps is recommended, but long pliers will do. Carefully lift the assembly off the soldering fixture and set on a cooling rack. Do this without moving any part. The cooling rack can be any two pieces of metal that will allow clearance for the protruding parts. You can expedite cooling by using an ordinary hair dryer in the "cool" position to gently blow air across the assembly.

While the grid assembly is cooling, assemble the output connector. See Fig. 7. Place the modified Type-N female connector, threaded end down, on the soldering fixture. Apply flux to the top and install the output coupling sleeve. Allow both parts to heat before applying solder. Carefully remove the soldered output connector from thefixture. When it has cooled, solder one end of the loop to the center pin of the N connector and the other to the output coupling sleeve.

Now place the anode plate on the soldering fixture and allow to heat. Apply flux to hole C. Insert the anode tuning post (5/32-inch-OD brass tube) and allow to heat; apply solder. Remove the parts and cool. Next, solder the finger stock in hole H on the anode bypass capacitor plate.[3]

This completes the work with the soldering fixture. Be sure to let it cool off before handling! Save the fixture for future construction; you never know when you might want it again.

The anode plate and the anode-bypass-capacitor plate must be filed and then sanded flat on their butt surfaces to assure that there are no solder bumps or sharp points to puncture the Teflon dielectric. This must be done after soldering. The Teflon sheet is adequate insulation for many times the anode potential of this amplifier, but only if the surfaces it separates are smooth!

Next, clean the cathode and filament PC boards. Install the fmger stock in hole H of the cathode board. Apply flux to both sides of the board. Heat with a hot iron and apply solder around the circumference of hole H, soldering the finger stock on both sides of the board. Use the same technique to install the filament pin.[4]

After all parts have cooled, use a spray can of flux remover to clean them. Slight scrubbing with Scotch-Brite pot cleaner will finish them nicely. Congratulations: You have finished the pieces and are now


1/2" HEX SPACER NO. 4-40 THREADED
TUBE CENTER
NO. 4-40 x 3/8" SCREW
1/8"
D
H
D
FIL. BOARD
3/16" NO.4 SPACER
CATHODE BOARD
1/2"
GRID PLATE
NO. 4-40 x 3/8" SCREW
GRID FINGER STOCK
ANODE PLATE
CATHODE/FILAMENT ASSEMBLY
(A)
TEFLON
INSERT
WASHER
ANODE BYPASS CAPACITOR ASSEMBLY
(B)
NO.6-32 x 3/8" NYLON SCREW
TAPPED (HOLE B)
INPUT CONNECTOR
C1
C2
C3
RFC
BYPASS PLATE
ANODE PLATE
CATHODE BOARD
0.20"
0.25"
0.450"
0.20"
INPUT INDUCTOR
(C)
FAB. FROM NO.18 BUS WIRE

Fig 15—Assembly details for the filament and cathode boards (A), the anode-bypass capacitor (B) and the input pi network (C).

ready to bolt the amplifier together.

Silver Plating

Over the years, many people have pushed silver plating as the only way to go. You may wish to silver plate the amplifier components before soldering them together, but I do not think it's necessary. I ran several tests to prove how much various types of plating affect performance of this amplifier. Remember that the RF skin conductivity of aluminum and copper is pretty good at 23 cm; they are much better than brass.

Four amplifiers were built for this test. They were plated as follows:

1) Nickel plated
2) Tin plated
3) Silver plated
4) Unplated

There was no difference in performance among the tin-plated, silver-plated and unplated versions. The nickel-plated amplifier exhibited 3-dB less gain.

In other words, it is not necessary to silver plate this amplifier; however, it does improve appearance by making the parts a similar color. Silver does tarnish, especially with fingerprints. The decision to plate or not to plate is up to you.

Assembly

After fabrication of all parts, assembly is simple. Figs. 15 through 17 show assembly details. Loosely fasten the grid and anode plates to the ring. Mount the input connector and capacitors on the input compartment. Loosely install the cathode and filament boards and their respective spacers. See Fig. 15A.

Now insert a 7289/2C39 tube. This will center up all finger stock. Place the Teflon anode tuner in its collar on the grid plate and screw it most of the way in. Now tighten all of the screws. The 7289/2C39 tube should slide in and out snugly, and the anode tuner should screw in and out smoothly.


(A)
(B)
(C)
(D)

Fig. 16—The completed cavity ring and anode plate with anode tuning post soldered In place are shown at A. The photo at B shows the grid plate with finger stock, input compartment and anode tuning collar soldered in place. The completed anode tuner Is at the right. C shows the cavity ring attached to the anode plate. The anode-bypass capacitor is ready for installation. At D, the interior of the cavity as seen from the grid plate side is visible. The output probe/connector assembly is installed. The anode bypass capacitor and anode enclosure have been installed on the anode plate.


(A)
(B)

Fig 17—At A, the interior of the completed input compartment is visible. The photo at B shows the interior of the anode compartment with the anode bypass, RFC3, C8 and J3 installed.

The Teflon sheet and anode bypass capacitor plate can be installed now (Fig. 15B). Assemble the remaining input components, the filament feed-through capacitors and RFC5 (Fig. 15C). Screw the output probe into the cavity ring (or push in the probe and tighten the setscrew, depending on which method you chose). Install the high-voltage connector and other parts in the anode box. Mount the amplifier on the front panel and install the anode tuner shaft. This completes the assembly. Part 2 of this article will describe a complete power supply for the amplifier, a practical water cooling system, testing procedures, microwave radiation safety hazards, and amplifier tune-up and operation.

Notes

[1] mm = in x 25.4.

[2] The finger stock for this project is manufactured by Instrument Specialities, P.O. Box A, Delaware Water Gap, PA 18237. Contact them for the name of the closest distributor. The part numbers for this amplifier are: anode bypass capacitor plate, no. 97-70A; grid plate, no. 97-74A; cathode board, no. 97-420A; filament board, no. 97-280A.

[3] See note 2.

[4] See note 2.

By E.R. "Chip" Angle, N6CA **From *QST*, April 1985**

A Quarter-Kilowatt 23-cm Amplifier

Part 2—Last month, we described the design and construction of a 23-cm cavity amplifier. This installment describes the rest of the components needed to put it on the air.

After you complete Construction of the cavity amplifier described in March *QST*, you are ready to assemble the rest of the components needed to put it on the air. This month, I will discuss the filament, bias and high-voltage supplies; a whisper-quiet, high-efficiency water-cooling system; testing and hookup; and, finally, tune-up and operation.

Power Supplies

The filament and bias supplies for the cavity amplifier are shown schematically in Fig. 1. The manufacturer's specification for the 7289/2C39 filament is 6.0-V ac at 1 A. I have found that the use of a standard 6.3-V ac, 1-A transformer only slightly increases the tube emission without much loss of tube life. The filament should be allowed to warm up before operating the amplifier, so the filament, bias and high-voltage supplies incorporate separate primary switches.

Biasing

Many biasing schemes have been published for grounded-grid amplifiers. Fig. 1 shows a bias network that satisfies all of the following operating requirements:

1) external bias supply referenced to ground

2) low-power components

3) variable bias to accommodate tube-to-tube variations

4) TR switchable with relay contact or transistor to ground

5) bias-supply protection in case of a defective or shorted tube.

U2 provides a variable bias-voltage source, adjustable by R1. The output of U2 drives the base of Q1, which is used to increase the current-handling capability of


125 V
0.5 A
T1
6.3-V
AC
LED
FIL. ON
360
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k=1000
TO FILAMENT AND BIAS INPUT ON RF DECK
T2
U1
1000
35 V
1
35 V
T
REG.
U2
IN
LM317T
OUT
ADJ.
0.1
240
1N4007
2 k
1/2 W
1 k
Q1
2N5194
CATHODE CURRENT (Ik)
mA
0-500
125 V
0.5 A
Z1
Z2
R1
2.5 k
BIAS ADJ.
T = TANTALUM
J1
CLOSE TO TX

Fig 1—Schematic diagram of the cavity-amplifier filament and bias supplies. All resistors are ¼-W carbon types unless otherwise noted.

J1—Female chassis-mount photo connector.
T1—Filament transformer. primary, 117 V; secondary, 6.3 V at 1 A.
T2—Power transformer. Primary, 117 V; secondary, 24 to 28 V at 50 mA or greater.
U1—Bridge rectifier, 50 PIV, 1 A.
U2—Adjustable 3-terminal regulator (LM317T or equiv.).
Z1, Z2—20-V unipolar metal-oxide varistor (General Semiconductor SA20 or equiv.) or two 20-V, 1-W Zener diodes.



Fig 2—Schematic diagram of the amplifier high-voltage supply.

C1-C4—Electrolytic capacitor, 360 µF, 450 V.
D1-D4—Silicon rectifier, 1000 PIV, 3 A.
F1—High-voltage fuse, 2 kV, 1 A.
J1—Chassis-mount female BNC or MHV connector.
R3-R6—Wirewound resistor, 40 kΩ, 11 W.
T1—Variable autotransformer, 500 VA.
T2—High-voltage transformer. Primary, 117 V; secondary, 900 to 1050 V at 500 mA.

the bias supply. Q1 must be mounted on a heat sink. J1 is connected to the station TR switching system so that R1 is grounded on transmit and disconnected on receive. The approximate range of the bias supply is 6 to 20 V. Z1 and Z2 provide protection for Q1 in case of a shorted tube. The amplifier can be run without Z1 and Z2 if you keep the anode voltage below 1100 V.

High-Voltage Power Supply

A safe, reliable high-voltage power supply is described here. Of course, you can use any readily available HV supply; keep in mind, however, that the 7289/2C39 anode potential should never exceed 1400-V dc at full load and that the amplifier will withstand 1900-V dc at low cathode current and cut-off-bias conditions. For maximum power output, assuming adequate drive power is available, anode voltage under full load should be about 1200- to 1400-V dc.

Fig. 2 is a schematic diagram of the high-voltage supply. A power transformer (T2) that delivers 900- to 1050-V ac is ideal. The type of rectifier circuit used will depend on the type of transformer chosen. Each leg of the rectifier is made from two 1000-PIV, 3-A silicon diodes connected in series. Each diode is shunted with a 0.01-µF capacitor to suppress transient voltage spikes, and a 470-kΩ equalizing resistor.

Filtering is accomplished with a string of four 360-µF, 450-V electrolytic capacitors connected in series. R3-R6 equalize the voltage across each capacitor in the string and serve as bleeder resistors. Of course, a single oil-filled capacitor may be used here if available. Whatever type of filter you use, the total capacitance should be about 80 µF at a voltage rating of at least 1500-V dc. This value allows adequate "droop" of the anode voltage under high-current loads to protect the amplifier in case of RF overdrive or a defective tube.

Protective Circuitry

Some type of start-up protection should be incorporated in the primary. Fully discharged filter capacitors look like a dead short at supply turn-on. Initial surge current (until the capacitors charge) may be high enough to destroy the rectifiers. R1 and R2 provide some surge-current limiting, but either of the two primary configurations shown in Fig. 2 should be used. T1, a variable autotransformer (Variac and Powerstat are two common trade names), is ideal. In addition to allowing you to bring the primary up slowly (and charging the capacitors gradually), it also allows full control of amplifier output power by varying anode voltage.

The second method, a "step-start" system, uses a resistor in the T2 primary to limit the turn-on surge current. When the capacitors have charged, K1 is energized, shorting out R11 and applying full voltage to the T2 primary.

F1 and R7 protect against high-voltage arc-overs or short circuits. If sustained overcurrent is drawn, F1 will open and remove B+ from the RF deck. Use a high-voltage fuse here; standard fuses may arc when blown and not interrupt the B+ .R7 provides current limiting to protect the amplifier and power supply in case of a high-voltage arc.

Safety

An HV meter should always be used to monitor the status of the power supply. The values for R8-R10 shown in Fig. 2 will give a 1500-V dc full-scale reading on a 0-1 mA meter. RG-58 or -59 coaxial cable should be used for the high-voltage interconnection between the power supply and the RF deck. Ground the shield at both ends for safety and a good dc return.

Safety must be observed when working with all power supplies. These voltages are lethal! Always disconnect ac power and then discharge the filter capacitors before working on the power supply. Never guess or make assumptions about the status of a power supply. Assume it is hot.

Metering

Cathode-current monitoring is all that's really necessary for observing amplifier dc performance. Cathode current (I_K) is the sum of the plate (I_P) and grid (I_G) currents. Normally, when this amplifier is driven to 300- or 400-mA I_K, the grid current will be around 40 to 50 mA. The inclusion of a grid-current meter is not really necessary and only makes biasing and TR switching complicated.

Cooling

Desired output power and the level of drive power available will dictate what type of cooling to use. For intermittent duty (SSB, CW) at output levels less than 50 W, air cooling is satisfactory. Any small blower may be easily mounted to the aluminum box surrounding the tube anode. For high-duty-cycle modes and/or output levels greater than 50 W, water cooling is highly recommended. Greater than twice the normal air-cooled output power can be obtained from a water-cooled tube, and water cooling is quiet.

Tube Modification and Water Jacket

The first step is to remove the air radiator from the tube. The air radiator screws on, so it may simply be unscrewed without damage to the tube.

First, place a hose clamp around the tube anode. Secure the radiator fins in a vise and grip the hose clamp with a pair of large


1/4"
1/4"
WATER FLOW
1/2"
9/32" OD BRASS TUBING
SOLDER
SOLDER
SHIM
SOLDER
ANODE
2C39/7289
GRID
CATHODE
1" OD COPPER CAP
WATER JACKET
FIL ASSEMBLY

Fig 3—Details of the solder-on water jacket.


ALU. TUBING 9/32" OD, 1/4" ID 1" LENGTH
EPOXY IN PLACE
A
A
FAB. FROM 1-1/4" ALU. ROD
BOTTOM VIEW
RUBBER GASKET 1-3/16" OD, 3/4" ID 0.070" THICKNESS
ASSEMBLY
9/32"
℄
9/32"
DETAIL AA
PINCH-OFF TUBE CLEARANCE
1/4"
19/32"
5/8"
7/8"
NO. 3/8-16 THREAD
1/2"
3/4"
5/16"
5/16"
THREAD DEPTH
0.594"
0.625"
A
A
7289 ANODE WATER JACKET
3/16" DIA.
9/32" DIA.
1/2" DIA.

Fig 4—Details of the screw-on water jacket.


WATER-COOLING SYSTEM
TO 117-V AC
FAN
"CLEAN-OUT" CAP ADAPTER
3/8" ID
WATER LEVEL
F
E
E
3/8" ID TUBE, 12" LONG
F
HEAT EXCHANGER
0-50
μA
1/4" ID
7289/2C39
A
D
3" ID PLASTIC PIPE 24" LENGTH
TO 117-V AC
WATER JACKET
1/4" ID
A
FLOW INDICATOR
B
B
F
C
PUMP
C
D
T
DRAIN VALVE
3/8" ID TUBE, 18" LONG
3/8" ID TUBE, 6" LONG
3/8" ID

PART	DESCRIPTION		
A	1/4" TO 3/8" REDUCER.	D	3/8" OR 1/2" NPT TO 3/8" TUBE ADAPTER.
B	1/2" NPT TO 3/8" TUBE ADAPTER.	E	3/8" TUBE TO EXCHANGER ADAPTER.
C	3/8" TUBE TO PUMP ADAPTER.	F	3/8" OD COPPER TUBE W/WIRE SOLDERED TO IT. (SEE TEXT).

Fig 5—Details of the water-cooling system. Recommended pumps are: (1) Little Giant Pump Co. Model 1-42A or larger, available from most hardware stores; or (2) Calvert Engineering, Cal Pump Model 875S (160 gal/h), available from Calvert, 7051 Hayvenhurst Ave, Van Nuys, CA 91406, tel. 213-781-6029. The flow indicator (Model 15C; requires two $^{1}/_{2}$-inch NPT adapters) is available from Proteus Industries, 240 Polaris Ave, Mountain View, CA 94043 tel. 415-964-4163.

pliers. Gently unscrew the tube from the radiator. If the hose clamp slips slightly, tighten it.

Some 7289/2C39 tubes use an air radiator that is attached with setscrews. To remove the radiator, simply remove the setscrews and pull the radiator off.

The air radiator will be replaced with a water jacket that allows water to be circulated past the tube anode and through a radiator, where it is cooled and circulated past the tube anode again. I have successfully used two different types of water jackets; both are described here.

The water jacket shown in Fig. 3 will work with any type of 7289/2C39. It is fabricated from a 1-inch-OD copper tubing cap and two short pieces of $^{9}/_{32}$-inch-OD brass tubing. The copper tubing cap should be available from a local hardware store or plumbing supply house. Brass tubing is available from many hobby stores and metal supply houses.

Mark and drill the copper cap so that the brass tubing is a snug fit. Thoroughly clean the parts until they shine. Push the tubing into the holes in the end cap and degrease the assembly with alcohol. Using plenty of flux, solder the seam around each section of tubing. Allow the jacket assembly to cool.

Meanwhile, thoroughly clean the 7289/2C39 anode to a bright finish. Check the water jacket for fit. In some cases, you'll have to use a 0.005- to 0.010-inch-thick copper shim to fill the gap between the copper cap and the tube anode. This shim helps eliminate pin holes in the solder.

Using plenty of flux, solder the water jacket to the tube anode. Solder it quickly with a hot, high-wattage iron. Allow the tube to cool in the air after soldering to avoid thermal shock and possible breakage. After the tube has cooled, use plenty of alcohol to remove all traces of flux from the tube and water jacket.

The second type of water jacket is shown in Fig. 4. This jacket will work only with 7289/2C39 tubes that have a screw-on air radiator. It is designed to thread onto the tube anode just like the air radiator did. This jacket is machined from a piece of $1^{1}/_{4}$-inch aluminum rod. The water inlet and outlet tubes are made from $^{9}/_{32}$-inch-OD, $^{1}/_{4}$-inch-ID aluminum tubing that is epoxied in place. A rubber gasket seals the jacket against leaks.

If you have access to a lathe, you should have no trouble duplicating the jacket. You could have one made up at a local machine shop. Complete screw-on water jackets are also available from the author.

After you unscrew the air radiator from the 7289/2C39, check for and remove any burrs from the tube anode. The anode surface must be flat if the rubber gasket is to be effective. Screw the water jacket onto the tube. Tighten by hand only. Do not use any tools, or you could damage the tube or jacket! Do not use the water inlet and outlet tubes for leverage—they have thin walls and break easily.

Water System

Fig. 5 depicts the complete water-cooling system. Recommended pumps and accessories that have proven reliable and effective are listed in the caption.

Any small pump, such as a fountain pump, that can deliver 160 to 200 gallons per hour can be used here. Most inexpensive pumps are not self-priming, which means that they won't pump water if they have air in the rotor. Although water can be forced through the pump for the initial prime, my system uses gravity priming. The water reservoir is a 2-foot length of 3-inch-OD plastic pipe that is available from hardware or plumbing stores. The outlet is at the bottom, and the inlet about halfway up the column. The inlet is located here to eliminate aeration that ionizes the water and reduces its effectiveness. The outlet

Microwave Radiation Safety

Intense RF radiation concentrated on body tissues can produce heat damage; the extent and penetration will depend on the radio frequency in use and on exposure duration. You should be aware of the approximate intensity of RF radiation of the transmitting equipment and antennas you come in contact with.

RF intensity is commonly expressed in milliwatts per square centimeter (mW/cm^2), which is the power flowing away from a source through a unit sampling or interception area at some specified distance. Although the United States as yet has no federal RF protection standard, a useful interim guide is the 1982 standard of the American National Standards Institute (ANSI '82). The most stringent level in this standard is 1 mW/cm^2 for frequencies between 30 and 300 MHz. Above 300 MHz, the protection level rises until it reaches 5 mW/cm^2 at 1500 MHz. Beyond 1500 MHz, the recommended level remains at 5 mW/cm^2. These levels represent the average power density allowed over any six-minute period and are for the sum of all polarizations from a given source.

At 1296 MHz, where one wavelength (λ) equals 23 cm, a thick resonant dipole feeding a calibrated power meter with matched coaxial cable (itself free of pickup) may be used to obtain an indication of power density. A reasonably lossless resonant dipole has an effective aperture of $\lambda^2/8$; at 23 cm this is 66 cm^2. The power meter reading in milliwatts, divided by 66, is the indicated power density. For this to be a reliable indication, the dipole must be positioned far enough from the RF source to be in its far field. For a small source, the distance should be at least $\lambda/2$, and here that would be about 12 cm (45 inches). The dipole should be oriented for alignment with the dominant polarization. Note that the power meter must be capable of readings well below 1 mW.

This arrangement would be useful for checking leaks along the coaxial route that the high power (here 250 W) takes to a load, be it dummy load or antenna. Cable connectors may not be tightly secured, or they may be faulty. For equipment operating in the SHF region, waveguide flanges may not be clamped properly.

Direct measurement of electric field strength near an antenna (with a calibrated instrument, preferably one with the indicating meter shielded and possibly positioned at the center of the sampling dipole) is another way to check for adequate protection. A field strength of 60 V per meter (V/m) corresponds to 1 mW/cm^2; 134 V/m corresponds to 5 mW/cm^2. At a distance 60 cm (2 feet) from an isolated dipole fed with 26 watts, the field strength would be about 60 V/m. This is a far-field field strength for all frequencies where the half wavelength is less than 60 cm, or for frequencies above 250 MHz. For full 250 watts applied to the dipole, the 60 V/m level occurs at a distance of 1.8 meters (6 feet), and at this distance this holds for all frequencies above 80 MHz.

With SSB or CW keying, the fields during Amateur Radio operation are highly intermittent, and usually include considerable pauses or intervals for listening. These factors reduce the average power density over the six-minute averaging period.

Further information on RF safety and protection estimates can be found in Chapter 7 of *The Satellite Experimenter's Handbook,* published by the ARRL. The following rules of good practice for RF protection are recommended:

- Never operate an RF amplifier with equipment shielding removed.
- Never handle antennas with RF power applied.
- Never guess that RF levels are safe. Take the time to consult a reliable reference for an estimate, or measure levels carefully. Allow a "cushion" of about 6 dB (factor of four in power density). If possible, borrow an RF radiation monitor (after learning how to use it), or consult with a ham who is well informed on RF protection.
- Never look into an open end of a power waveguide; never point a powered directive antenna (a beam or a paraboloid, for example) toward people. Keep all VHF and UHF transmitting antennas as high as possible, distant from humans.
- Use good-quality, well-constructed coaxial cable and connectors to avoid RF leaks.
- Think RF and electrical safety first; test later!
- Watch *QST* for news on RF measurement techniques and progression, protection standards and proposed federal and state RE regulations.—*David Davidson, W1GKM*

directly feeds the pump. The pump and the reservoir outlet port should be mounted in the same plane. The pump should be oriented so that air bubbles will rise into the impeller output port and can be blown out once the pump starts running.

Flow Indicator and Heat Exchanger

Water cooling is best described as "super quiet." There is no noisy fan to reassure you that the tube is receiving adequate cooling. If water flow is reduced or cut off during amplifier operation, tube damage is virtually assured.

Flow interlocks and switches to shut down the amplifier if water flow is reduced are hard to find and expensive. Flow indicators, however, are inexpensive and reliable. A flow indicator has a spoked rotor that turns as water passes through the unit. If the wheel is turning, there is water flow; if not, you have a problem. Changes in flow rate can be observed by watching for speed changes in the rotor. A small lamp illuminates the flow indicator, making it easy to see rotation. The flow indicator should be mounted where it can be seen from the operating position and monitored during operation.

Heat exchangers, or radiators, remove the heat from water as it passes through. For this application, a small automobile transmission-oil cooler works great. Most auto- parts stores and speed shops have a good selection. Pick one that is similar in size and aspect ratio to a whisper fan (approximately 4 × 4 × 1 inches). Some come with mounting brackets. Look for a cooler with the input and output ports on the top so air bubbles will rise to the top and move on without becoming trapped. Trapped air degrades cooler performance.

If you use the amplifier for high-duty-cycle modes such as ATV or FM, or for long, slow-speed CW transmissions (EME, for example), you should use a small axial whisper fan to increase the effectiveness of the heat exchanger. A fan isn't necessary during normal operation, or even for sustained operation at moderate power levels, but I highly recommend one if you plan prolonged operation at maximum power. Locate the fan so the warm exhaust air won't heat up other equipment.

Hoses and Fittings

Most hardware stores carry a complete line of brass fittings and adapters that can be used for this project. Brass, however, will eventually corrode and pollute the water supply. Plastic fittings are cheaper and don't corrode, but they are harder to find. Recreational vehicle suppliers are my main source for these parts. They are used extensively in drinking water systems for mobile homes and travel trailers. Procure the fittings when you have the rest of the parts in hand, as there are many variables to consider.

You can use any relatively soft, thin-wall vinyl tubing for all water lines. The main runs are made from $^{3}/_{8}$-inch-ID hose, while $^{1}/_{4}$-inch-ID stock is used to connect to the 7289/2C39 water jacket. The $^{1}/_{4}$-inch-ID tubing fits snugly over the $^{9}/_{32}$-inch-OD inlet and outlet tubes on the water jacket, so no clamps are required. All other hose connections should be secured with stainless-steel clamps to prevent leaks. Any leaks mean air in the system and deterioration of cooling performance.

Safety

The tube anode, and hence the water jacket and water, are in direct contact with the high-voltage supply, so some safety precautions must be observed. Approximately 12 to 18 inches of tubing should run between the 7289/2C39 jacket and any other component in the cooling system. This will allow enough resistance in the water to provide adequate current limiting, should the water contact any components that are grounded.



Fig 6—Performance graph of the water-cooling system.

It is best to ground the water supply at the pump. Do this by replacing a short section of the tubing that runs to the flow indicator with a piece of brass or copper tubing. Solder a wire to this metal tubing and connect the other end of the wire to your station ground. Use at least 24 inches of vinyl tubing between the anode cooling jacket and the ground point.

On the warm-water side of the 7289/2C39, run 12 inches of vinyl tubing to a small metal fitting or short section of metal tubing, and then another 12 inches of vinyl tubing to a grounded point (this can be at the heat exchanger). You can measure the water leakage current to ground by placing a microammeter between the metal fitting that connects the two vinyl hoses and ground. Leakage current should be less than 10 µA with clean water and an anode potential of 1 kV. As the water ages, the leakage current will rise; when this happens, replace the water.

Grocery stores carry distilled water for use in steam irons. It may be deionized and not truly distilled, but it works fine for about four to six months in this application. Filters can be purchased from scientific supply houses, but they're not really worth buying because deionized water is so cheap.

Do not use tap water under any circumstances! When you turn on the water system for the first time, run a gallon of water through it for half an hour to wash out fabrication impurities. Replace with clean water before using the system to cool the amplifier.

Water was chosen because it's inexpensive, nontoxic, nonflammable and easy to clean up if you have a leak. Better liquid coolants are available, but they are toxic. Don't use them!

Cooling Performance

I have used water-cooling systems for several years with no problems whatsoever. Fig. 6 is a graph of several transmit/receive cycles on a water-cooled, 500-W output, 23-cm power amplifier. For this test, I used two of the amplifiers described in this article coupled with a pair of hybrid combiners. This particular cooling system used 1 gallon of water. Experiments indicate that, during extended operation, the water temperature rises only 30° to 35°F above ambient room temperature. Typically, the tube anode and water average 10° to 15°F above ambient during casual operating.

Flow rates in this system are typically 1/3 gallon per minute per tube, which is more than adequate. At this rate, more than 300 W of dissipation from a single inefficient 7289/2C39 were required to boil the water in the water jacket. The water should not be allowed to boil because this will heat the rubber gasket.

Tubes

It is not really necessary to buy a new 7289/2C39. Used tubes can be found surplus for around $1 to $5 and, in many cases, will perform as well as a new tube. Most used tubes have been sitting around for several years, so it's a good idea to run them through the dishwasher to clean them up and then run the filaments for about 24 hours. This will restore operation in many cases.

If you buy a new tube, you should be aware that the 7289/2C39 is being run far in excess of its ratings in this amplifier. The manufacturer's warranty will not cover tubes run in this application.

Contrary to popular opinion, glass tubes will work. Physically, they are not as rugged as the ceramic version, but the glass-to-metal seal seems to provide better shelf life than the ceramic seal. The glass tubes make great driver tubes and will work fine for power levels up to 100-W output. Pulse tubes (7815, 7211) are not recommended because of their poor thermal stability at high power levels. Also, they generally are 30 to 40 MHz lower in resonant frequency in this amplifier compared to the 7289/2C39. Some 7289 tubes can be as much as 30 MHz lower in frequency. Minor length adjustment of the anode-tuning post may be required to accommodate amplifier and tube differences.

Tube Insertion

Extreme care must be exercised when inserting the 7289/2C39 tube. Never force the tube in place, as damage (bending) of the cathode finger stock may result. Observe the layout of the finger stock to get an idea of how the tube inserts. Carefully position the tube so it is straight as you gently push. It should slide in snugly without any solid resistance.

Testing

After you have completed all of the parts for the amplifier, it's time to test everything before hooking it all together. Test the water-cooling system by turning it on and watching for steady water flow as indicated on the flow meter. The tube and water jacket can be removed from the cavity amplifier for this test.

Check all of the power-supply voltages first without connecting them to the RF deck. Then, without the tube in place, hook the bias and filament supplies to the cavity and check the voltages again at the tube finger-stock connections. Connect the high-voltage supply to the RF deck and bring the voltage up slowly with a variable autotransformer. Monitor the high voltage on the anode-bypass-capacitor plate, and look and listen for any possible arcing between the anode-bypass-capacitor plate and ground. Use extreme care when measuring and testing the high-voltage supply. If everything looks okay with the power supplies, shut them off and disconnect them.

You can make a safe, low-power test of the cavity resonance without applying any voltage. With the tube in place, insert a 2-inch-long coupling loop on the end of a piece of coaxial cable between the spring fingers of the anode down into the cavity. Connect the amplifier output probe/connector to a device capable of detecting low-level RF at 23 cm (for example, a spectrum analyzer or microwattmeter). Feed a signal from an L-band signal generator into cable attached to the wire coupling loop that you inserted into the cavity. Set the signal generator for various frequencies in the 23-cm band and tune the amplifier anode tuner. There will be sharp peak in output at cavity resonance.

This testing method can be used to determine cavity tuning range, anode-bypasscapacitor effectiveness and resonance of various tube types for use in this amplifier. Any cavity amplifier can be tested completely without ever applying high voltage. The better your test equipment, the easier the amplifier is to test. If all dimensions were followed strictly, the amplifier will tune as designed.

Amplifier Hookup

Installation and operation of this amplifier is relatively straightforward, but as with any amplifier, several precautions must be followed. If these are adhered to, the amplifier will provide years of reliable service.

The amplifier is designed to be operated in a 50-ohm system and should never be turned on without a good 50-ohm load connected to the output connector. Never operate it into an antenna that has not been tuned to 50 ohms!

Drive power to the amplifier should *never* exceed 15 W. *Never* apply drive power in excess of 1 W unless all operating voltages are present and the tube is biased on. Otherwise, the tube grid-dissipation rating will be exceeded and you will probably ruin it.

As in all TR-switched systems, some type of interlock or sequencing of transmit and receive functions should be incorporated. In most systems, the sequence for going into transmit is something like this: First, switch the antenna changeover relay from the receiver to the power amplifier. Next, bias the power amplifier on. Last, key the exciter and apply drive to the amplifier. To go to receive, unkey the exciter, remove operating bias from the amplifier and switch the antenna relay back to the receiver.

If the antenna relays are switched while the power amplifier is operating and putting out power, damage to the relay contacts and/or the amplifier is likely. If there is a momentary removal of the antenna while the power amplifier is biased on, oscillation may occur. This can damage the TR relay, the tube or even the receive preamplifier.

Tune-up and Operation

This is it — the big moment when you will see your project come to life! Connect an accurate UHF power meter and a 50-ohm antenna or load to the amplifier output connector. A Bird Model 43 wattmeter with a 100- or 250-W, 400-1000 MHz slug will give reasonable accuracy, depending on the purity of the drive signal. Apply filament power and tube cooling, and allow 3 to 5 minutes for the filaments to warm up. Turn on bias supply (the amplifier will draw maximum current if the anode voltage is applied without bias). Apply 300 to 400 V to the anode. There should be no current flowing in the tube as indicated on the cathode-current meter. Ground J1 on the bias supply to apply transmit bias and observe cathode current. As R1, the bias control, is turned clockwise, quiescent idling current should increase. Set for about 25 mA.



Fig 7—Performance of the cavity amplifier under different drive and plate-current conditions.

Apply 1 W of RF drive power. Turn the anode tuner while observing the RF output power meter and tune for maximum output. The output should go through a pronounced peak at'cavity resonance. Adjust C2 and C3 on the input tuning network for maximum amplifier output. If possible, use a directional wattmeter between the driver and the amplifier input to check that best input SWR and maximum amplifier output occur at roughly the same setting.

Depending on the amount of drive power available, you may want to tune the amplifier for maximum power output or maximum gain. Fig. 7 shows what you can expect from different drive levels.

Once the amplifier is tuned for best input SWR and maximum output with 1 W of drive, anode voltage and drive power can be increased. Increase both in steps; be sure to keep the anode tuner peaked for maximum output power. When you get to the 100-W output level, very carefully readjust the input circuit for maximum output. The input capacitor closest to the cathode is critical and should need to be rotated less than 90 degrees maximum. Maximum output power will be roughly coincident with best input SWR.

Increase the drive power and keep the anode tuner peaked for maximum output. Increase the drive until you reach the desired output level, but *do not exceed 400-mA I_K!* At 1400-V dc and 350-mA I_K, output power with a good tube should be about 230 to 250 W. At lower anode voltages, I_K will be higher for the same output power. Higher anode voltages result in higher gain, lower drive levels, lower grid current and lower plate current for a given output power.

The anode tuner's tuning rate is approximately 5 MHz per turn. Clockwise rotation of the tuner lowers the resonant frequency of the cavity. This control will require readjustment as you make large frequency excursions within the 23-cm band (for example, if you go from 1296 weak-signal work to the 1269-MHz satellite segment). You should also check the input SWR if you move more than 15 MHz. Generally, amplifier tuning does not change much after initial setup. You should be able to turn it on and use it without retuning as it heats up. Slight adjustments may be necessary, however, depending on cooling, inherent thermal differences from tube to tube and duty cycle of the operating mode. Always keep the anode tuner peaked for maximum output, and check it from time to time, especially while you are first learning how the amplifier operates.

The output loading control is the output connector and probe assembly. Loading is changed by minor rotational adjustment of the N connector. First loosen the jam-nut (or setscrew) slightly. While observing output power and keeping the anode tuner peaked, rotate the loading control ±30 degrees maximum for greatest output power. This should be done only once and should not need repeating unless another tube is installed. Even then it may not be required.

Conclusion

This cavity amplifier for the 23-cm band is capable of safe, reliable operation at output powers in excess of 200 W. More than 50 of these amplifiers are in operation, and you can build one, too. I would like to thank Mike Stahl, K6MYC, Bill Troetschel, K6UQH, William Jungwirth, AA6S, Lem Moeschler, W6KGS and Joseph Cadwallader, K6ZMW, for their help and encouragement during the development of this project.

References

Laakmann, "Cavity Amplifier for 1296 MHz," *QST*, Jan. 1968, pp. 17-22.

Laakmann, "Kilowatt Amplifier for 1296 MHz," *Ham Radio*, Aug. 1968, pp. 8-17.

"Power Amplifier for 23 cm," *VHF Communications*, April 1976, p. 222.

"Power Amplifier for 24 cm," *VHF Communications*, March 1978, p. 175.

Stefanskie, "1270 MHz ATV Power Amplifier," *Ham Radio*, June 1977, pp. 67-73.

Tech Report #6, Crawford Hill VHF Club, July 1971.

Tech Report #13, Crawford Hill VHF Club, Dec. 1972.

By Zack Lau, KH6CP/1 **From *QEX*, May 1994**

A 2-W, 13-cm Amplifier

This amplifier uses a resistively stabilized Hewlett Packard ATF-44101/AT-8140 power GaAs FET running class A to provide 14 dB of gain and a 2-W output. It wasn't too difficult to choose the device—there aren't that many linear devices that cover the 2.3 GHz band at this power level. Unfortunately, it is fairly pricey; the circa 1990 price was around $90. But since this transistor has been around a long time, it may be available surplus. Several hundred were sold at the bargain price of $3 each about a year and a half ago. I bought a few—I should have bought more.

Even if you do buy your FETs at bargain prices, you still will want to ensure that they are biased safely. As has been pointed out many times in the literature, having the negative gate bias supply fail while the drain supply is applied may result in the destruction of the device. Thus, designers have devised elaborate protection schemes to shut off the drain supply if the gate supply fails.

Fig 1 shows a simpler power-supply circuit. The drain supply is controlled by an ordinary 723 voltage regulator with current limiting. The current limiting protects the device—instead of the expensive FET getting hot and self-destructing, the cheap TIP 30 power transistor gets warm. Doing this eliminates the need for complex shutdown circuits to handle a failed bias supply. While there are more modern regulator chips than the 723, they aren't significantly better for this application. In fact, some are "improved" to the point where they are tougher to use. For example, chips with better current-sensing circuits often require special low-value resistors. While you could use the copper wire table in the *ARRL Handbook* to make your own low-value resistors from wire, it makes more sense to me to use a 723 with standard, readily available parts.

The gate bias supply is produced by an NE555 timer running as an oscillator and driving a voltage inverter. An LM337 adjustable 3-terminal voltage regulator controls the gate supply. Now, you have to be a little careful using adjustable voltage regulatorswith bias supplies. While I haven't experienced this myself, it is entirely possible that a noisy potentiometer could momentarily present an open circuit between the wiper and the resistance element. Conceivably, in some circuits, this could result in voltage spikes at the output of the voltage regulator as the voltage is adjusted. The cure for this is to wire the potentiometer so that it never presents an open circuit, even with an intermittent wiper, as I've done with R9 in Fig 1.

For some other GaAs FET circuits, it may be advantageous to use an active-bias supply which operates inside the feedback loop of the current limited supply. This allows the bias point to be unaffected by temperature variations. The current limiting acts as a failsafe, protecting the transistor if a more negative gate supply voltage is unable to turn off the transistor. I've successfully used this circuit when only a milliamp of bias current was needed. Due to the high current required by the gate circuit of the 2-W amplifier, I decided it was impractical to active-bias the FET in this application; the ICL7660 can't provide the needed current. But there are highercurrent versions of this chip, for those who don't mind the price.

RF Design

I found the AT-8140 rather difficult to get unconditionally stable. I ended up placing a 10041 chip resistor from gate to ground, which resulted in pretty good stability, except around 2.3 GHz. Unfortunately, it doesn't appear possible to dc decouple this resistor without adversely affecting stability, so quite a bit of bias current is needed. Because of this, it is conceivable that you may find a FET that needs too much gate voltage for a typical 10041 chip resistor to handle. Whether this is the case with a particular FET depends on both the threshold voltage and the transconductance of the device. The threshold voltage can vary quite a bit, particularly in older devices, though the manufacturers have tightened up this specification in recent data books. Worst case would be a large negative threshold voltage and a high transconductance. Stacking chip resistors in parallel might be a solution, though this might also invite unwanted parallel resonance effects, similar to what is seen with paralleled capacitors.

While in-band stability is not too critical, since the source and load impedance matching is usually pretty good at the operating frequency, I used a series resistor in the gate decoupling line to make the amplifier unconditionally stable, according to

Table 1—Measured Amplifier Performance

Input to MGF 1801 driver (dBm)	*Driver Output (dBm)*	*AT 8140 Output (dBm)*	*AT 8140 Gain (dB)*
–7.0	5.7	19.8	14.1
0.0	12.5	26.6	14.1
3.0	15.5	29.7	14.2
4.0	16.5	30.8	14.3
5.0	17.5	31.7	14.2
6.0	18.4	32.6	14.2
7.0	19.2	33.3	14.1
8.0	20.3	33.9	13.6
9.0	21.2	34.1	13.1
10.0	22.1	34.6	12.5
13.0	24.2	34.9	10.7

The 1-dB compression point is at 34.1/33.2 dBm output.
Comparing measurements made using an HP8563E spectrum analyzer against those made with an HP 453B/8481A power meter, a signal that measures 4.7 dBm on the spectrum analyzer reads out as 3.8 dBm on the power meter. The values listed are from the spectrum analyzer, taking into account a 30.2-dB, 25-W Bird attenuator inserted between the amplifier and the analyzer.


+10 to 15 V
12
V+
R1
100
11
Q1
TIP30
VOUT
10
VZ
9
NC
Current Limit
2
1
1 Watt
RS
Current Sense
3
Compensation
13
100
R3
3 k
4
VD
9 V
(Current
Regulated)
V+
R4
10 k
5
U1
LM723
R2
2200
Voltage
V+ Reference
7.15 V
VREF
6
1
NC
NC
14
NC
NC
8
NC
NC
V–
7
Drain Supply
+10 to 15 V
R7
10
8
4
R5
10 k
VCC
Reset
7
Discharge
U3
LM337
D2
1N4936
U2
LM555
3
C3
Reg
IN
OUT
ADJ
VG
R6
10 k
6
22 µF
16 V
C4
Threshold
2
D1
1N4936
22 µF
16 V
Trigger
R8
120
C1
2200
Control
GND
Voltage
1
5
C2
0.01
R9
500
C5
1 µF
16 V
Tantalum
Gate Supply

Fig 1—Power supply for the 2-W, 13-cm amplifier.

the computer model. This series resistor also improved the input match bandwidth, an important consideration if you don't want to tune the amplifier. Of course, improving the bandwidth with resistance also reduces the gain. The loss isn't too bad, however, seeing as this design is within a few dB of the maximum stable gain the data sheet specifies. The design was optimized with 150 Ω of series resistance, but I decided that such a high value was unwise. To accommodate such a high series resistance, it is entirely likely that the negative supply voltage would have to be more negative than the VGS limit. Then, if the 10041 resistor were to fail opencircuited, the supply could damage the gate of the transistor. For this reason, I chose to use a 5041 series resistor. I didn't reoptimize the design for 50 Ω of series resistance, since the likely improvement was small compared to the variations I've seen when optimizing the unit on the bench.

Finally, I discovered that additional gate circuit bypassing was required at audio frequencies to prevent the circuit from oscillating. This was done with a 1-µF capacitor that is not shown in the computer model. This frequency range wasn't covered by the model.

Several dB of additional saturated output power was obtained by modifying the output network with foil tabs. AT-8140s saturate at about 2.2 W output with around 200 mW of drive. An advantage to optimizing the circuit by modifying the 5041 striplines at the input and output of the amplifier is that the stability should not be adversely affected. But the board does have to be made larger to accommodate such tuning.

The original design was optimized using *Microwave Harmonica*, with the results shown in Table 2 and Fig 6. After I tweaked the output network to get maximum output power, I entered the changed circuit components into the computer and analyzed the circuit, resulting in the analysis shown in Table 3 and Fig 7. Table 1 shows the performance of the circuit in its final configuration.

Construction Notes

To ground the drain bypass capacitor and the gate resistor, I cut slots in the board and connected the pads to the ground plane with 1-mil copper foil. Copper foil was also used to connect the gate bypass capacitor, although in this case I trimmed the board so that it wasn't necessary to cut a slot.

For high-quality grounding without lots of tiny screws, I decided to try using a heat spreader made out of 1-mil copper foil. I cut a hole in the circuit board for the FET and then carefully soldered the foil across the hole in the circuit board, taking care not to put any solder where it would interfere with heat-sinking action. I didn't want any air pockets, as they are extremely poor conductors of heat. Then, after attaching the board to a piece of 0.25-inch sheet aluminum with suitably tapped holes, I used a scribe to punch holes for the 0-80 screws to


U1
MC1723CG
+10 to 15 V
AT8140 Power Supply
500 mA @9 V
U2
78L05
U3
ICL7660
R7
47
Reg
IN
OUT
GND
C3
0.47
C4
0.47
8
V+
2
C6
10 μF
5
OUT
GND
4
3
C5
10 μF
8
VCC
R1
100
VC
7
Q1
TIP32
R8
1000
R9
1 k
VG
VOUT
6
Q2
2N3906
R5
1 k
R6
8200
Current Limit
10
1
1/2 Watt
R5
Current Sense
1
VD
Compensation
9
C1
100
C2
10 μF
16 V
R3
3000
Error Amplifier
VCC
2
VEE
3
R4
10 k
VCC
R2
2400
Voltage Reference 7.15 V
VREF
4
VEE
VEE
5
* Vref 6.8 to 7.5 V

$$R_{sc} = \frac{V_{sense}}{Isc} = \frac{0.66}{Isc}$$

$$V_D \approx 7\frac{(R_4 + R_3)}{R_4} \quad R_2 = \frac{R_3R_4}{R_3 + R_4}$$

$$R_5 \approx R_6\frac{V_{be} + V_D - V_{dd}}{V_{dd} - V_{be}}$$

$$R_5 \cong R_6\left(\frac{1.04}{9.3 - 0.54}\right) = R_6(0.119)$$

Fig 2—An active biasing circuit suitable for use with amplifiers that draw minimal gate current. Do *not* use this with the 2-W amplifier.


TRL8
TRL9
C2
10
CHIP
TRL10
J2
Q1
ATF-44101/
AT8140
J1
TRL1
C1
10
CHIP
TRL2
Tee
TRL3
TRL4
Tee
TRL5
TRL6
Tee
TRL7
R1
100
CHIP
TRL11
TRL15
Bend
TRL12
R2
51
CHIP
TRL13
TRL14
−VGS
TRL16
+VDS
1000
CHIP
C3
C4
1 μF
16 V
Tantalum
1000
CHIP
C5

Fig 3—Schematic diagram for the 2-W amplifier.

C1, C2—10-pF, high-quality porcelain chip capacitors. I used 55-mil capacitors, although 100-mil capacitors should work just fine.
C3, C5—1000-pF NPO chip capacitors
C4—1-μF, 16-V tantalum capacitor.
J1, J2—SMA jacks.
Q1—Hewlett Packard ATF-44101/AT-8410 medium power GaAs FET. This device must be properly heat-sinked.
The absolute maximum channel temperature is 175°C. The case-to-junction thermal resistance is 23°C/W.
TRL1-16—Microstriplines etched on 0.031-inch-thick, ε_r = 2.55 Teflon circuit board.

Table 2—*Microwave Harmonica* Analysis (Original Circuit)

```
MICROWAVE HARMONICA PC V5.5  File: \mh\2304\qexamp.ckt   22-DEC-93 17:54:54

 Freq    MS11    PS11   MS21    PS21   MS12    PS12    MS22    PS22   MS21     K
 GHz      dB     deg    mag     deg    mag     deg      dB     deg     dB
          AMP    AMP    AMP     AMP    AMP     AMP      AMP    AMP    AMP     AMP

 1.000   -0.70 -167.5  2.084    19.3  0.017   -53.7   -6.01 -128.7    6.38   1.64
 1.100   -0.57 -177.2  1.988     0.1  0.018   -71.2   -5.35 -139.0    5.97   1.43
 1.200   -0.47  173.3  1.941   -17.8  0.020   -87.3   -5.02 -148.2    5.76   1.27
 1.300   -0.40  164.0  1.945   -35.0  0.022 -102.6   -4.96 -156.6    5.78   1.17
 1.400   -0.36  154.7  1.999   -52.0  0.024 -117.7   -5.13 -164.3    6.01   1.09
 1.500   -0.38  145.2  2.110   -69.2  0.028 -132.9   -5.59 -171.4    6.48   1.05
 1.600   -0.48  135.2  2.288   -87.3  0.032 -148.9   -6.43 -177.6    7.19   1.02
 1.700   -0.73  124.6  2.542 -106.8  0.039 -166.3   -7.84  178.8    8.10   1.01
 1.800   -1.26  113.0  2.872 -128.6  0.047  174.0   -9.91 -177.3    9.16   1.01
 1.900   -2.31  101.1  3.240 -153.5  0.056  151.3  -11.05 -156.6   10.21   1.01
 2.000   -4.14   90.9  3.547  178.8  0.064  125.8   -8.31 -138.3   11.00   1.02
 2.100   -6.75   87.5  3.682  149.7  0.070   98.9   -5.06 -141.0   11.32   1.04
 2.200   -9.11   95.3  3.655  121.2  0.073   72.6   -3.15 -153.0   11.26   1.06
 2.300  -10.01  108.4  3.587   93.9  0.075   47.6   -2.42 -167.3   11.09   1.07
 2.304  -10.02  108.9  3.585   92.8  0.075   46.6   -2.41 -167.9   11.09   1.08
 2.400  -10.08  120.9  3.583   66.5  0.078   22.4   -2.72  177.8   11.08   1.09
 2.500   -9.15  137.4  3.638   36.0  0.082   -5.9   -4.55  162.9   11.22   1.11
 3.000   -0.30   98.5  0.945 -114.5  0.025 -146.5   -1.26 -164.2   -0.49   1.17
 4.000   -0.74   28.9  0.159  140.2  0.006  122.2   -0.11  150.2 -15.96   1.91
 5.000   -2.01  -15.1  0.071   59.4  0.003   56.4   -0.08  123.6 -22.98  13.43
 6.000   -0.78    1.8  0.044  120.4  0.003  125.4   -0.07  100.6 -27.20   9.68
 7.000   -0.36  -60.0  0.158   68.8  0.014   86.8   -2.71  123.5 -16.02   8.12
 8.000   -0.77 -109.6  0.086  -76.3  0.010  -50.3   -0.74   73.6 -21.26  14.53
 9.000   -3.99  178.3  0.030  151.2  0.004 -174.8   -0.10   53.3 -30.56  50.93
10.000   -1.70 -138.8  0.016    5.4  0.003   45.4   -0.10   33.1 -36.06  75.19
11.000   -0.67  163.8  0.024  -91.2  0.006  -46.2   -0.47   12.8 -32.44  53.16
12.000   -0.95  116.5  0.031  106.0  0.010  152.0   -0.48   -0.6 -30.15  33.01
```

Table 3—*Microwave Harmonica* Analysis (Optimized for Output Power)

```
MICROWAVE HARMONICA PC V5.5  File: b:qexamp.ckt   22-DEC-93 18:04:28

 Freq    MS11    PS11   MS21    PS21   MS12    PS12    MS22    PS22   MS21     K
 GHz      dB     deg    mag     deg    mag     deg      dB     deg     dB
          AMP    AMP    AMP     AMP    AMP     AMP      AMP    AMP    AMP     AMP

 1.000   -0.72 -168.6  2.386    39.7  0.020   -33.3  -17.28  -86.0    7.55   1.63
 1.100   -0.67 -178.3  2.331    20.4  0.022   -50.9  -15.61 -117.3    7.35   1.42
 1.200   -0.64  172.6  2.299     2.0  0.023   -67.5  -14.05 -142.9    7.23   1.27
 1.300   -0.64  163.7  2.294   -15.7  0.026   -83.3  -12.69 -165.0    7.21   1.17
 1.400   -0.66  155.0  2.314   -32.9  0.028   -98.6  -11.48  175.0    7.29   1.09
 1.500   -0.71  146.5  2.365   -49.9  0.031 -113.6  -10.42  156.4    7.48   1.05
 1.600   -0.79  137.8  2.453   -66.8  0.035 -128.4   -9.50  138.6    7.79   1.02
 1.700   -0.91  128.9  2.588   -83.8  0.039 -143.3   -8.71  121.3    8.26   1.01
 1.800   -1.10  119.4  2.786 -101.2  0.045 -158.5   -8.08  103.9    8.90   1.01
 1.900   -1.42  108.8  3.071 -119.4  0.053 -174.6   -7.62   85.7    9.75   1.01
 2.000   -1.98   96.3  3.482 -139.1  0.063  167.9   -7.46   65.7   10.84   1.02
 2.100   -3.10   80.3  4.065 -161.7  0.078  147.5   -7.86   41.8   12.18   1.04
 2.200   -5.77   57.1  4.815  170.7  0.096  122.2   -9.64    9.1   13.65   1.05
 2.300  -14.58   10.6  5.418  135.8  0.113   89.5  -15.23  -52.9   14.68   1.07
 2.304  -15.31    6.6  5.428  134.2  0.113   88.0  -15.55  -57.2   14.69   1.07
 2.400  -10.67 -157.1  5.138   96.3  0.111   52.3  -13.32  174.5   14.22   1.09
 2.500   -4.22  165.0  4.086   61.5  0.092   19.6   -7.41  119.7   12.23   1.11
 3.000   -0.53   96.9  1.222  -35.2  0.032  -67.2   -2.33   21.6    1.74   1.17
 4.000   -0.75   29.2  0.494 -155.6  0.019 -173.6   -1.06  -79.0   -6.13   1.69
 5.000   -1.99  -15.1  0.261   93.6  0.013   90.6   -1.04 -169.9 -11.67  11.23
 6.000   -0.78    1.9  0.137  130.1  0.010  135.1   -0.55  116.4 -17.28   7.89
 7.000   -0.39  -60.0  0.101  160.7  0.009  178.7   -0.92   -3.1 -19.91   8.22
 8.000   -0.75 -109.9  0.196   -1.0  0.023   25.0   -6.65  -66.0 -14.17  14.18
 9.000   -4.01  178.4  0.126 -132.4  0.018  -98.4   -1.60 -147.6 -18.01  39.98
10.000   -1.70 -138.8  0.076   53.9  0.015   93.9   -2.18  130.1 -22.42  57.57
11.000   -0.66  163.8  0.071  -60.9  0.017  -15.9   -9.01   29.7 -22.92  50.28
12.000   -0.97  116.5  0.092  168.5  0.030 -145.5   -8.83  160.9 -20.71  31.18
```



Fig 4—Parts placement diagram for the 2-W amplifier. Points labeled XX should be connected to the ground plane using copper foil.



Fig 5—Etching pattern for the 2-W amplifier. Use 0.031-inch-thick, $\varepsilon_r = 2.55$ Teflon circuit board.



Fig 6—*Microwave Harmonica* analysis of the circuit's S parameters after computer optimization.



Fig 7—After the output network was optimized on the bench for maximum output power, *Microwave Harmonica* produced this analysis of the resulting circuit.

mount the FET. Ideally, clean holes would be punched into the copper, but I couldn't figure out a way to do that with the tools I have available. I used 0-80 screws, which are the largest screws I've found that will fit in the mounting holes. While I've used smaller screws in the past, I prefer using the largest screws possible since taps generally get tougher to use as they get smaller. I built one amplifier using 0.125-inch thick 6061 aluminum, but found that to be too thin to easily make the tapped holes for attaching the connectors and brass strips, although the finished mounting plate was stiff enough.

By Al Ward, WB5LUA From *QST*, December 1985

1296-MHz Solid-State Power Amplifiers

Explore the DX possibilities of the 23-cm band with these modern amplifiers.

With the ever-increasing number of ready-to-go 1296-MHz transverters available on the market today, there is a great demand for a simple and economical way to generate higher power than the typical 0.5 to 1 W output these transverters provide. If 1 W or less is used to drive a typical 2C39/7289 stripline or cavity amplifier, the low output power is often disappointing. A tube-type amplifier run with 1 kV on the plate typically offers a gain of 10 dB. This means that, at best, you can expect 5- to 10-W output from your 1-W or less input.

A popular way of generating higher power is to cascade two tube-type amplifiers for 50- to 100-W output. Here I will show you an alternative: two solidstate amplifiers that can replace the tubetype driver amplifier and provide 10- to 20-W output—enough to drive a two-tube amplifier to full output.

The NEC NEL1306 and the NEL1320 1300-MHz power transistors are an economical solid-state approach to generating moderate power levels (10-20W) at 1269 and 1296 MHz. These amplifiers can be used for terrestrial or satellite work. When OSCAR 10 was designed, it was thought that 10 W into a modest gain antenna (20 dBi) would produce usable signals from the satellite. Unfortunately, there were some problems, and the sensitivity of AO-10 was not as originally expected for the Mode-L uplink. These amplifiers can, however, be used as a driver for a higher-powered tube amplifier for Mode-L service. If all goes according to plan with the launch of AMSAT-OSCAR Phase IIIC, 10 to 20 W with a 20-dBi gain antenna will produce acceptable downlink signals.

The NEL1306 is rated for 6-W output at 1296 MHz at the 1-dB compression point; the NEL 1320 is rated at 20 W. These devices offer several advantages for amateur experimenters. They were designed for collector voltages of 12- to 13.6-V dc, making them ideal for portable and mobile operation. Although the price may seem high to someone familiar with HF parts, these devices are less expensive than most microwave power transistors. The NEL 1306 is in the $26 price range, while the NEL1320 costs about $42. California Eastern Laboratories makes these transistors available in single-lot quantities, so you don't have to be "in the business" to get your hands on them.[1]

The performance of the amplifiers I built and tested is shown in Table 1. The NEL1306 is a good buy. With 1.5-W input, 6- to 8-W output can be achieved. When the amplifier is tuned up at lower power levels, power gain can be as high as 10 dB. With 200-mW drive from my homemade transverter, an output power level of 2 W is attainable.[2]

Power gains as high as 17 dB are possible with a two-stage amplifier (an NEL1306 driving an NEL1320). With a mere 200 mW of drive, 10-W output is possible. When the pair of amplifiers is driven with 1 W and tuned for maximum power output, the 1-dB compression point of 18 W will be achieved.

Circuit Details

The basic design, shown schematically in Fig. 1, is an adaptation of a circuit described in the NEL1300 series data sheet. The design incorporates 30-ohm quarter-wavelength microstriplines on the input and output. C3, C4, C7 and C8, along with L1, form a pi network that matches the low input impedance of the device to 50 ohms. CS, C6, C9 and C10 and the 30-ohm transmission line (L2) form an output pi network that maximizes power transfer to 50 ohms. C10 is not always necessary, depending on variations among devices and circuit-board material.

I designed the amplifiers for 0.031-inch-thick, double-sided glass-epoxy circuit board. A 30-ohm line in this dielectric equates to a line width of 0.121 inch, which is equivalent to the width of the collector and base leads of the NEL1300 series

Table 1
Typical Operating Conditions for the 1296-MHz Solid-State Power Amplifiers

Device	*NE130681-12*	*NEL132081-12*
P_{out}(1-dB compression point)	7W	18W
Gain (1-dB compression point)	6 dB typ.	5 dB typ
Collector efficiency	40-50%	40-50%
Idling current	50 mA	150 mA
I_C @ 1-dB compression point	1.1 A	3.0 A
V_{CC}	13.5 V	13.5 V
Power input	14.9 W	40.5 W


INPUT
10
CHIP
C1
C7
6
L1
C8
6
5
CHIP
C3
Q1
5
CHIP
C4
R2
10
RFC 1
FB
R1
+BIAS
C11
10
CHIP
C12
100
CHIP
C13
0.1
D1
1N4007
5
CHIP
C9
C5
L2
5
CHIP
C6
10
CHIP
C2
OUTPUT
C10
RFC 2
FB
RFC 3
FB
+Vcc
10
CHIP
C17
R3
C14
100
CHIP
C15
0.1
C16
+
10µF
16 V
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF) ; OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS ; k = 1000, M = 1000 000.

Fig. 1—Schematic diagram of the NEL1306 and NEL1320 1296-MHz solid-state power amplifiers. The schematic is identical for both versions. Component values are the same except as noted.

C1, C2, C11, C17—10-pF chip capacitor.
C3, C4, C5, C6—3.6- to 5.0-pF chip capacitor.
C7, C8—1.8- to 6.0-pF miniature trimmer capacitor (Mouser 24AA070 or equiv. See text).
C9, C10—Same as C7 and C8 for the NEL1306 amplifier. For the NEL1320 version, 0.8- to 10-pF piston trimmers are used (Johanson 5200 series or equiv.).
C12, C14—100-pF chip capacitor.
C13, C15—0.1-µF disc ceramic capacitor.
C16—10-µF electrolytic capacitor.
D1—1N4007 diode.
L1, L2—30-ohm microstripline, ¼-wavelength long (see text).
Q1—NEC NEL130681-12 (6 W) or NEL132081-12 (18 W) transistor.
R1—82- to 100-Ω resistor, 2-W minimum. Vary for specified idling current.
R2—10-Ω, ¼-W carbon-composition resistor with "zero" lead length. See text.
R3—15-Ω, 1-W carbon-composition resistor.
RFC1—3t no. 24 wire, 0.125 inch ID, spaced 1 wire diam.
RFC2—1t no. 24 wire, 0.125 inch ID, spaced 1 wire diam.
RFC3—1-µH RF choke; 18t no. 24 enam. close-spaced on a T50-10 toroid core.


+ BIAS
+ VCC
Q1
C13
C11
C12
R1
R1
RFC 1
C3
C5
D1
R2
C8
C4
C6
C9
INPUT
C1
C7
C15
C17
C14
C16
RFC 2
R3
C2
C10
OUTPUT
1"
(25.4 mm)

Fig 2—Parts-placement diagram and full-size etching pattern for the solid-state 1296-MHz power amplifiers. All components mount on the etched side of the board. The same PC boards are used for each version.

devices. This minimizes the discontinuity between L1, L2 and Q1.

Bias is provided by R1, R2 and D1. R1 can be optimized, if desired, to adjust the collector idling current.

I selected RFC1 and RFC2 by choosing the lowest possible reactance that will not affect power gain or output power. The RF chokes and the 10-pF bypass capacitors afford adequate decoupling at the frequency of operation. The values of RFC1 and RFC2 are purposely made different to avoid oscillations caused by bias-choke coupling.

After building several of these amplifiers, I noticed that the transistors sometimes generated low-frequency spurious signals. Although these signals were very low in amplitude and caused no problems, they were annoying. I found that I could eliminate them by keeping the high-frequency RF chokes in the collector circuit as small as possible and adding the parallel R3/RFC3 combination, as well as bypass capacitors C14, C15, C16. RFC3 must be capable of handling 1 A for the NEL1306 and 3 A for the NEL1320, so I made special RF chokes to withstand the current.

Construction

Identical construction techniques are used for both amplifiers. Most of the components are mounted to the PC board, and



Fig 3—Construction details for the solid-state 1296-MHz power amplifiers. See text for additional information.

the board and transistor are mounted to an aluminum base plate made from 1/4-inch-thick stock. PC-board layout is shown in Fig. 2. Two separate boards are used—one for the input side and one for the output—and they are mirror images of each other. The copper is retained on the bottom side and serves as a ground plane. The grounded areas on the top side must have a good connection to the bottom ground plane for low-inductance grounding of the transistor emitter leads, matching capacitors and bias circuitry. Etched PC boards and partial parts kits for this project are available from A & A Engineering.[3]

Several effective methods of connecting the top and bottom ground planes are summarized here.

1) Plated-through holes at the critical grounding areas mentioned earlier.

2) Use of pins or screws that penetrate through the circuit board into the aluminum base plate at the critical areas.

3) Use of "wrap-around" foils on all edges of the ground plane.

Plated-through holes are often used in the commercial and military electronic marketplace but are not so easily reproduced in the average builder's circuitboard shop. I've found that the best technique for the home builder is a combination of methods 2 and 3. First, wrap thin copper or brass foil around the board edges and then solder the foil to the top and bottom. Sometimes called "shim stock," thin sheet metal is often available from hobby shops or metal suppliers. Next, drill holes through the board and use no. 4-40 screws to tie the circuit board to the base plate at the critical areas shown in Fig. 2.

The transistor must be mounted so that its leads lie flat against the PC board. This poses a slight problem, since the transistor leads protrude from the device 0.165 inch above the bottom of the flange, and the PC boards are only 0.031 inch high. There are a couple of ways around this problem. They work equally well, so choose the method that is easiest for you.

If you have access to a machine shop, you can mill out a 0.240-inch-wide by 0.090-inch-deep slot in the aluminum base plate to clear the transistor flange. This is a simple task on a milling machine, and you can probably find a local machine shop that will do small jobs when business is slow. The other method is to mount the transistor to the base plate and use a piece of 0.090-inch-thick aluminum sheet to bring the input and output PC boards up to the right height. The 0.090-inch dimension allows a wrap-around foil and solder buildup of 0.040 inch, maximum.

I used 1-inch-long screws to secure the transistor to holes drilled and tapped in the aluminum base plate. The extra screw length that protrudes from the bottom of the base plate allows the use of an external heat sink, which is suggested if continuous operation is desired.

The clearance holes in the NEL1300 devices are for no. 4-40 hardware. I drilled out the holes to accept no. 6-32 screws to make the assembly more rugged, although this may not be necessary. Be careful if you decide to drill out the holes to accept no. 6-32 hardware; the transistor flange is soft copper, and you could damage the device. Use a small vise to hold the transistor flange during the drilling operation.

Solder the components to pads on the board using surface-mounting techniques. Silver solder (2%) is recommended for the chip capacitors, but 5N63 will work fine. Use a 15-W iron and solder quickly to avoid burning the metallization off the capacitors.

The transistor leads should be soldered in place only after the circuit boards and transistor have been firmly bolted down to the base plate. This is necessary to minimize any buildup of stress in the transistor leads. Chip capacitors C3, C4, C5 and C6 should be soldered directly onto the leads of Q1 to ensure the shortest possible lead length. Keep D1 close to Q1. Thermal compound will enhance heat transfer to D1 to ensure minimal drift in idling current with temperature changes.

In the original design of these amplifiers, Johanson piston-trimmer capacitors (5200 series or equiv.) were used for C7, C8, C9 and C10. These capacitors are fairly large, and in some instances the coupling between the bodies of C8 and C9 was enough to cause an in-band oscillation. Smaller variable capacitors should be used if at all possible. I've used a 1.8- to 6.0-pF miniature ceramic trimmer capacitor, Mouser Electronics part number 24AA070, in the input and output networks of the NEL1306 amplifier and in the input network of the NEL1320 amplifier with no performance degradation.[4] I did use the Johanson piston trimmers in the output network of the NEL1320 amplifier because of the high RF currents involved.

The PC board makes use of end-launch SMA-type connectors. Fig. 3 illustrates this technique. Four-hole, flange-mount SMA connectors can be mounted to the edge of the base plate using two of the four mounting holes. Drill and tap the base plate for no. 2-56 hardware. Be careful—it's easy to accidentally cross-thread or overtorque the no. 2-56 hardware.

An alternative approach is to mount the amplifier in an aluminum die-cast box (Bud CU-124B or Hammond 1590B) and run miniature 50-ohm coaxial cable such as RG-174 from the amplifier board to the connector. The amplifiers shown in Figs. 4 and 5 use standard SMA connectors mounted to the walls of the metal box. BNC or Type-N connectors should work equally as well. When preparing each end of the coaxial cable, try to keep the pigtail leads as short as possible (1/8 inch or less); otherwise the mismatch will be difficult to tune out.

I compared the performance of an amplifier with end-launch connectors to that of another that used the approach just described. I could measure no difference in gain or 1-dB compression point.

Considerable effort was put forth to make sure the amplifiers are stable. The devices have fairly high gain at the frequency of operation, so layout and good construction practices are very important. Here are some construction hints that can help ensure amplifier performance and stability.

1) Use the smallest (physical) size variable capacitors that will still handle the RF current.

2) Use wrap-around ground foils as noted. Grounding screws are required at the critical RF-ground areas near the shunt variable capacitors, shunt bypass capacitors and Q1 emitters.

3) Connect braids from the coaxial-cable jumpers to the same ground as the shunt variable capacitors.

4) Use as little lead length as possible on R2—less than 1/8 inch.

5) In some instances when the large piston trimmers are used, a shield approximately 3/4 inch high mounted on top of Q1 and grounded via the mounting screws can improve isolation between C8 and C9.

Tune-up and Operation

Measuring RF power at 1296 MHz can be difficult. I used a calibrated 20-dB directional coupler along with enough attenuator pads to allow power to be read with a Hewlett Packard HP430C power meter and an HP477B thermistor mount. Even better is the HP431 power meter with its associated HP478A thermistor mount (a newer version of the HP430C that does not



Fig 4—This NEL1306 amplifier was built inside a die-cast box. Miniature coaxial cable runs to the connectors.



Fig 5—The NEL1320 amplifier is virtually identical to the NEL1306 version of Fig 4, except for the capacitors on the output strip line. C10 was not necessary on this version.

suffer from temperature-drift problems). Bird offers several low-power elements for the popular model 43 in this frequency range. Bird 400-1000 MHz elements are common, and they can be used with decreased accuracy.

Begin initial setup of each amplifier by terminating the input and output in good 50-ohm loads. I recommend that you use a fuse in the collector lead of Q1 to protect the device until you are sure everything is working normally. Start with all capacitors at minimum. Apply 12- to 13.5-V dc to the V_{CC} and bias terminals. The collector idling current should be as shown in Table 1. Vary the value of R1 for correct idling current.

For the NEL1306 amplifier, start out with 50 to 100 mW of drive. Adjust the output network for maximum power output and then peak the input network for maximum output power. Increase drive and repeak both matching networks for rated performance as shown in Table 1. Similarly, start out with approximately 1 W of drive for the NEL1320 and follow the same procedure. After a minute or two of operation at maximum power output, remove RF drive power and check to see that the collector idling current has not increased more than 25% over the initial setting. Keeping D1 in close contact with Q1 will minimize drift in idling current with temperature changes.

If you're going to use transistor switching to apply dc to the power amplifier stages during transmit, consider the following technique. Apply 13.5-V dc to the V_{CC} terminal during receive and transmit. Use a series transistor switch to apply 13.5-V dc to the bias terminal during transmit. A power transistor capable of carrying only a few hundred milliamperes of bias current, as opposed to several amperes of collector current, will be required. More important, the voltage drop across the transistor switch in the V_{CC} line will be eliminated. This will ensure maximum power output of the NEL1300 devices by keeping V_{CC} at 13.5-V dc.

Switching the bias port off during receive is important for another reason. Normally during receive periods, the amplifier is left unterminated. Sometimes the input port is also left open. Depending on the length of the unterminated 50-ohm cable on the amplifier ports, the unit may show signs of instability if it is drawing idling current.

Several amateurs in the Dallas area have duplicated these amplifiers with no problems. Other amplifiers of this design are in use in different parts of the country. The NEL1300 series amplifiers offer a simple and inexpensive means of generating medium power on 1296 MHz. You'll be amazed at what you can work with 18 W that you can't with 1 W.

I wish to thank everyone who offered technical advice, especially Wes Atchison, WA5TKU, for helping with the construction and evaluation of the prototype amplifiers.

Notes

[1] NEC transistors are available from California Eastern Laboratories, 3260 Jay St., Santa Clara, CA 95050, tel. 408-988-3500.

[2] Complete construction details for this transverter may be found in Chapter 32 of the *1986 ARRL Handbook.*

[3] A & A Engineering, 7970 Orchid Dr., Buena Park, CA 90620, tel. 714-521-4160.

[4] Mouser Electronics, 11433 Woodside Ave., Santee, CA 92071, tel. 619-449-2222.

By Ward Silver, N0AX **From *QST*, September 2003**

Amplifier Care and Maintenance

With few moving parts, your amplifier can be easy to overlook. Here are some ideas for taking care of amplifiers.

Amplifiers come in all shapes and sizes, large and small, light or heavy, tube or solid-state, VHF or HF. Regardless, they all need a little TLC from time to time. They can cost as much as top-of-the-line radios, so it's important that they get a little maintenance on a regular basis.

While this article focuses on amplifiers that use vacuum tubes, many of the ideas presented here can and should be applied to any amateur amplifier—HF or VHF/UHF. Solid-state amplifiers operate at lower voltages and generally have fewer points of failure, but they still need occasional maintenance.

Safety First

It is important to review good safety practices.[1] Tube amplifiers use power supply voltages well in excess of 1 kV and the RF output at full throttle can be hundreds of volts, as well. Almost every voltage in an amplifier can be lethal! Take care of yourself and use caution!

- *Power Control*—Know and control the state of both ac line voltage and dc power supplies. Physically disconnect line cords and other power cables when you are not working on live equipment. Use a lock-out on circuit breakers. Double-check visually and with a meter to be absolutely sure power has been removed.
- *Interlocks*—Unless specifically instructed by the manufacturer's procedures to do so, never bypass or "rig" an interlock. This is rarely required except in trouble-shooting and should only be done when absolutely necessary. Interlocks are there to protect you.
- *The One-Hand Rule*—Keep one hand in your pocket while making any measurements on live equipment. The hand in your pocket won't give current a chance to flow through you. It's also a good idea to wear shoes with insulating soles and work on dry surfaces. Current can be lethal even at milliampere levels—don't tempt the laws of physics.
- *Patience*—Repairing an amplifier isn't a race. Take your time. Don't work on equipment when you're tired or frustrated. Wait several minutes after turning the amplifier off to open the cabinet—capacitors can take several minutes to discharge through their bleeder resistors.
- *A Chicken Stick*—Make this simple safety accessory shown in Figure 1 and use it whenever you work on equipment in which hazardous voltages have been present. The ground wire should be heavy duty (12 gauge minimum) due to the high peak currents (hundreds of amperes) present when discharging a capacitor or tripping a circuit breaker. When equipment is opened, touch the tip of the stick to *every* exposed component and connection that you might come in contact with. Assume nothing—accidental shorts and component failures can put voltage in places it shouldn't be.
- *The Buddy System and CPR*—It's always a good idea to use the buddy system when working around any equipment that has the potential for causing serious injury. The buddy needn't be a ham, just anyone who can be nearby in case of trouble. Your buddy should know how to remove power and administer basic first aid. Since hams work around electrical equipment frequently, it would be a good idea to have your buddy or someone in the household know CPR, as well.[2]

Cleanliness

The first rule of taking good care of an amplifier is cleanliness. I realize that 90 percent of ham shacks have just failed the first rule. Amplifiers need not be kept sparkling new, but their worst enemy is heat. Excess heat accelerates component aging and stresses those expensive tubes and transformers. There are two areas to keep clean—the inside and the outside.

Outside the amplifier, you need to prevent dust and obstructions from blocking the paths by which heat is removed. This means keeping all ventilation holes free of the ever-present dust bunnies, pet hair and



# 10 Eye - Bolt
Solder Lug and Nut
3/4" PVC Pipe, 12 inches Long
3/4" PVC Pipe Cap
2 - 3 Feet of Heavy, Flexible Wire (12 Gauge Minimum)
Heavy - Duty Alligator - Type Clip

Figure 1—The "chicken stick" is a great way to ensure that everything inside the amplifier that should be discharged actually is. It can be a life saver.

insects. Fan intakes are particularly susceptible to inhaling all sorts of "goop." Get out the vacuum cleaner and clean not only the amplifier, but the surrounding areas. Don't even think about letting liquids anywhere near the amplifier. One spilled cup of coffee can cause hundreds of dollars of damage.

Keep papers or magazines off the amplifier—even if the cover is solid metal. Paper acts as an insulator and keeps heat from being radiated through the cover. Amplifier heat sinks must have free air circulation to be effective. There should be at least a couple of inches of free space surrounding an amplifier on its sides and top. If the manufacturer recommends a certain clearance, mounting orientation or air flow, follow those recommendations.

Just as the outside needs to be kept clean, so does the inside. High voltage (HV) circuits attract dust like crazy. The dust slows heat dissipation and will eventually build up to the point where it arcs or carbonizes. Our friend the vacuum cleaner should make another appearance to remove any dust or dirt. If you find insects (or worse) inside the amp, try to determine how they got in and plug that hole. Window screening works fine to allow airflow while keeping out visitors. While you're cleaning the inside, this is a great time to perform a visual inspection as described in the next section.

Vacuuming works best with an attachment commonly known as a "crevice cleaner." Figure 2 shows a crevice cleaning attachment being used with a small paintbrush to dislodge and remove dust. Don't use the vacuum cleaner brush attachment; they're designed for floors, not electronics. Some vacuums also have a blower mechanism, but these rarely have enough punch to clean as thoroughly as a brush. Besides, that dust you blow all over is going to wind up in some other equipment, so it's best to take it out of circulation, so to speak. The brush will root dust out of tight places and off components without damaging them or pulling on connecting wires.

If you can't get a brush or attachment close enough, a spray can of compressed air will usually dislodge dust and dirt. If you use a rag or towel to wipe down panels or large components, be sure not to leave threads or lint behind. Never use a solvent or spray cleaner to wash down components unless the manufacturer advises doing so—you might leave behind a residue or damage the component.

Visual Inspection

Once the amplifier has been cleaned, it's time for a visual inspection. Remove any internal covers or access panels and...*stop*! Get out the chicken stick, clip its ground lead securely to the chassis and touch every exposed connection. Now, using a strong light and possibly a magnifier, look over the components and connections. Amplifiers have far fewer components than transceivers do, so it's quite feasible to look at every component and insulator. Look for cracks, signs of arcing, carbon traces (thin black lines), discoloration, loose connections, melting of plastic, and anything else that doesn't "look right." This is a great time to be sure that mounting and grounding screws are tight. While you're in there, does anything smell burnt? The nose can quickly detect the odors of toasted transformer, cooked capacitor or roasted resistor. Learn the smells of healthy and not-so-healthy components.

Make a note of what you find, repair, or replace—even if it's absolutely nothing. If you don't keep a shack notebook, start one. A simple spiral notebook with notes about maintenance, wiring, color coding, antenna behavior and so forth can be a big time-saver.

Electrical Components

An amplifier contains many heavy-duty HV and RF components. These can be expensive and hard to replace, so it's important that you take good care of them. Let's start with the power supply.

There are three basic parts to amplifier power supplies—the ac transformer and line devices, the rectifier/filter and the metering/regulation circuitry. Transformers need little maintenance except to be kept cool and be mounted securely. Line components such as switches, circuit breakers and fuses, if mechanically sound and adequately rated, are usually electrically okay, as well.

Rectifiers and the capacitors that filter the HV dc require occasional cleaning. Look for discoloration around components mounted on a printed circuit board (PCB) and make sure that all wire connections are secure. HV capacitors are generally electrolytic or oil and should show no signs of leakage, swelling or outgassing around terminals.

Located at the output of the filter, components that perform metering and regulation of voltage and current can be affected by heat or heavy dust. If there has been a failure of some other component in the amplifier—such as a tube—these circuits can be stressed severely. Resistors may survive substantial temporary overloads, but may show signs of overload, such as discoloration or swelling.

Amplifiers contain two types of relays—control and RF. Control relays switch ac and dc voltages and do not handle input or output RF energy. The usual problem encountered with control relays is oxidation or pitting of their contacts. A burnishing tool can be used to clean relay contacts. In a pinch a strip of ordinary paper can be pulled between contacts gently held closed. [Avoid the temptation to over-clean silver-plated relay and switch contacts, as the author points out later. It is easy to remove contact plating with excessive polishing and while silver-plated relay and switch contacts may appear to be dark in color, oxidized silver (black) is still a good conductor. Once the silver's gone, it's gone; contact erosion will then be pervasive.—*Ed.*] If visual inspection shows heavy pitting or

S. COHEN, N1SC; R. SCHETGEN, KU7G



Figure 2—A small paintbrush and a vacuum cleaner crevice attachment make dust removal easy.

discoloration or resistance measurements show the relay to have intermittent contact quality, it is best replaced.

RF relays are used to perform transmit-receive (TR) switching and routing of RF signals through or around the amplifier circuitry. Amplifiers designed for full break-in operation will usually use a high-speed vacuum TR relay. Vacuum relays are sealed and cannot be cleaned or maintained. When you replace RF relays, use a direct replacement part or one rated for RF service with the same characteristics as the original.

Cables and connectors are subjected to heavy heat and electrical loads in amplifiers. Plastics may become brittle and connections may oxidize. Cables should remain flexible and not be crimped or pinched under clamps or tie-downs. It's a good idea to gently wiggle cables while watching the connections at each end for looseness or bending. Connectors can be unplugged and reseated once or twice to clear oxide on contact surfaces. Carefully inspect any connector that seems loose. Be especially careful with connectors and cables in amplifiers that have RF decks that are in separate enclosures from those of their power supplies. Those interconnects are susceptible to both mechanical and electrical stress and you don't want an energized HV cable loose on the operating desk. Check both the soldered electrical integrity and the mechanical stability of those cables and make sure they are tightly fastened.

As with relays, switches found in amplifiers are either control function orientated or RF routers. Adequately rated control switches, if mechanically sound, are usually okay. Bandswitches are the most common RF switch—usually a rotary phenolic or ceramic type. A close visual inspection should show no pitting or oxidation on the wiper (the part of the switch that rotates between contacts) or the individual contacts. Arcing or overheating will quickly destroy rotary switches. Figure 3 is a photo of a heavy-duty band switch that has suffered severe damage from arcing. Slight oxidation is acceptable on silver-plated switches. Phosphor-bronze contacts can sometimes be cleaned with a light scrub from a pink pencil eraser, but plating can be easily removed, so use caution with this method and be sure to remove any eraser crumbs. Rotary switch contacts cannot be replaced easily although individual wafer sections may be replaced if an exact matching part can be obtained.

Amplifiers use all types of capacitors and resistors. When replacing them, be sure to use a part rated for the use to which it will be put. Voltage and power-handling ratings are particularly important, especially of those handling high RF currents. An RF tank capacitor replacement should be checked carefully for adequate RF voltage and current ratings, not just dc. HV resistors are generally long and thin to prevent arcing across their surfaces. Even if a smaller (and cheaper) resistor has an equivalent power rating, resist the temptation to substitute it. In a pinch, a series string of resistors of the appropriate combined value can be used to replace one HV unit. Don't use carbon resistors for metering circuits, use metal or carbon film types. The carbon composition types are too unstable.

If you are repairing or maintaining an old amplifier and manufacturer-specific parts are no longer available, the ham community has many sources for RF and HV components. Fair Radio Sales and Surplus Sales of Nebraska are familiar names.[3] Hamfests and Web sites such as **www.eham.net** or **www.k1dwu.net/hamtrader** often have amplifier components for sale. You might consider buying another amplifier of the same type in non-working condition for parts use.

Tubes

The single most expensive component in an amplifier is usually the vacuum tube that performs the amplification. Good maintenance of tubes starts with proper operation of the amplifier. Follow the manufacturer's instructions for input drive levels, duty cycles, tuning and output power level. Frequently check all metered voltages and current to be sure that the tubes are being operated properly and giving you maximum lifetime. Penta Labs has an excellent Web page on maintaining power tubes.[4]

The internal mechanical structures of tubes generally do not deal well with mechanical shock and vibration, so be gentle. The manufacturer may also specify how the amplifier is to be mounted, so read the operating manual.

Tubes generate a lot of heat, so it's important that whatever cooling mechanism employed is kept at peak efficiency. Airways should be clean, including between the fins on metal tubes. All seals and chimneys should fit securely and be kept clean. Wipe the envelope of glass tubes clean after handling them—fingerprints should be removed to prevent baking them into the surface.

On metal tubes that use finger-stock contacts, be sure the contacts are clean and make good contact all the way around the tube. Partial contact or dirty finger stock can cause asymmetric current and heating inside the tube, resulting in warping of internal grids and possibly causing harmonics or parasitics.

Plate cap connections and VHF parasitic suppressors should be secure and show no signs of heating. Overheated parasitic suppressors may indicate that the neutralization circuit is not adjusted properly. Inspect socket contacts and the tube pins to be sure all connections are secure, particularly high-current filament connections. Removing and inserting the tubes once or twice will clean the socket contacts.

Adjustments to the neutralizing network, which suppresses VHF oscillations by negative feedback from the plate to grid circuit, are rarely required except when you are replacing a tube or after you do major rewiring or repair of the RF components. The manufacturer will provide instructions on making these adjustments. If symptoms of VHF oscillations occur without changing a tube, then perhaps the tube characteristics or associated components have changed. Parasitic oscillations in high-

H. WARD SILVER, N0AX



Figure 3—The band switch section on the left clearly shows the signs of destructive arcing.

power amplifiers can be strong enough to cause arcing damage. Perform a visual inspection prior to re-adjusting the neutralizing circuit.

Metering circuits rarely fail, but they play a key part in maintenance. By keeping a record of "normal" voltages and currents, you will have a valuable set of clues when things go wrong. This is perfect information for the shack notebook. Record tuning settings, drive levels, and tube voltages and currents on each band and with every antenna. When things change, you can refer back to the notebook instead of relying on memory.

Mechanical

While the amplifier is primarily an electronic beast, it has a significant number of mechanical parts that affect its well-being. Thermal cycling and heat-related stresses can result in mechanical connections loosening over time or material failures.

Switch shafts, shaft couplings and panel bearings all need to be checked for tightness and proper alignment. All mounting hardware needs to be tight, particularly if it supplies a grounding path. Examine all panel-mounted components, particularly RF connectors, and be sure they're attached securely. BNC and UHF connectors that are mounted with a single nut in a round panel hole are notorious for loosening with repeated connect/disconnections.

Rubber and plastic parts are particularly stressed by heat. If there are any belts, gears or pulleys, make sure they're clean and that dust and lint are kept out of their lubricant. Loose or slipping belts should be replaced. Check O-rings, grommets and sleeves to be sure they are not brittle or cracked. If insulation sleeves or sheets are used, check to be sure they are covering what they're supposed to. Never discard them or replace them with improperly sized or rated materials.

Enclosures and internal shields should all be fastened securely with every required screw in place. Watch out for loosely overlapping metal covers. If a sheet metal screw has stripped out, either drill a new hole or replace the screw with a larger size, taking care to maintain adequate clearance around and behind the new screw. Tip the amplifier from side to side while listening for loose hardware or metal fragments, which should all be retrieved.

A great time to clean the front and back panels and get gummy finger deposits off before they cause permanent finish damage is during maintenance. If the amplifier is missing a foot on the cabinet or an internal shock mount, replace it. A clean unit with a complete cabinet will have a significantly higher resale value than a dirty, grubby one, so it's in your interest to keep the equipment looking its best.

Shipping

When you are traveling with an amplifier or shipping it, some care in packing will prevent needless damage. Improper packing can also result in difficulty in collecting on an insurance claim, should damage occur. The original shipping cartons are a good method of protecting the amplifier for storage and sale, but they were not made to hold up to frequent shipping. If you travel frequently, it is best to get a sturdy shipping case made for electronic equipment.[5]

Some amplifiers require the power transformer to be removed before shipping. Check your owner's manual or contact the manufacturer to find out. Failure to remove it before shipping can cause major structural damage to the amplifier's chassis and case.

Tubes should also be removed from their sockets for shipment. It may not be necessary to ship them separately if they can be packed in the amplifier's enclosure with adequate plastic foam packing material. If the manufacturer of the tube or amplifier recommends separate shipment, however, do it!

Cleaning and Maintenance Plan

This discussion should have given you plenty to think about. It's easy to defer maintenance, but as with a vehicle, performance and lifetime are improved if a regular program is put into place. For amateur use, there is little need for maintenance more frequently than once per year. If there is a period of the year in which you are most active, put a note on the calendar about six weeks in advance to "open the hood," giving you time to obtain and replace any components.

Consider the maintenance requirements of your amplifier and what its manufacturer recommends. Sit down with your amplifier's manuals and make up a checklist of what major steps and tools are required. When maintenance time rolls around, you'll be prepared and be able to perform the job in the most efficient manner.

Troubleshooting

A benefit of regular maintenance will be familiarity with your amplifier should you ever need to repair it. Knowing what it looks (and smells) like inside will give you a head start on effecting a quick repair.

The following discussion is intended to illustrate the general flow of a troubleshooting effort, not be a step-by-step guide. Figure 4 shows a moderately-high-level troubleshooting flow chart. Before starting on your own amplifier, review the amplifier manual's "Theory of Operation" section and familiarize yourself with the schematic. If there is a troubleshooting procedure in the manual, follow it, of course.

You might be surprised how many "amplifier is dead" problems turn out to be simply a lack of ac power. Before even opening the cabinet of an unresponsive amplifier, be sure that ac is really present at the wall socket and that the fuse or circuit breaker is really closed. Assuming that ac power is present, trace through any internal fuses, interlocks and relays all the way through to the transformer primary terminals.

Hard failures in a high voltage power supply are rarely subtle, so it's usually clear if there is a problem and what components are involved. When you repair a power supply, take the opportunity to check all related components. If all defective components are not replaced, the failures may be repeated when the circuit is re-energized.

Rectifiers may fail open or shorted—test them using a DVM diode checker. An open rectifier will result in a drop in the HV output of 50 percent or more but will probably not overheat or destroy itself. A shorted rectifier failure is usually more dramatic and may cause additional rectifiers or filter capacitors to fail. If one rectifier in a string has failed, it may be a good idea to replace the entire string as the remaining rectifiers have been subjected to a higher-than-normal voltage.

High voltage filter capacitors usually fail shorted, although they will occasionally lose capacitance and show a rise in ESR (equivalent series resistance). Check the rectifiers and any metering components—they may have been damaged by the current surge caused by a shorted filter. Power transformer failures usually manifest themselves by insulation failures with consequent arcing of the windings. Either can result in the unmistakable aroma of overheated transformer. A failed transformer is generally not repairable.

Along with the HV plate supply, tetrode screen supplies occasionally fail, too. The usual cause is the regulation circuit that drops the voltage from the plate level. Operating without a screen supply can be damaging to a tube, so be sure to check the tube carefully after repairs.

If the power supply checks out okay and the tube's filaments are lit, check the resting or bias current. If it is excessive or very low, check all bias voltages and dc current paths to the tube, such as the plate choke, screen supply (for tetrodes) and grid or cathode circuits.

Having exhausted power supply and dc problems, you will then turn to the RF components or "RF deck." There is a natural tendency to forge ahead and swap in a known-good tube or tubes. Don't! Tubes are expensive and if the problem is elsewhere, you may damage the spares. Wait to swap tubes until you are sure that the tube is likely to be defective.

Check the input SWR to the amplifier. If it has changed (you did write down the normal SWR and drive levels, didn't you?) then you likely have a problem in the input circuitry or one or more tubes have failed. Perform a visual check of the input circuitry and the band switch, followed by an ohmmeter check of all input components.

If input SWR is normal and applying drive does not result in any change in plate current, you may have a defective tube, tube socket, or connection between the input circuits and the tube. Check the TR



Amplifier Condition is Unknown
Do All Indicators Light Up?
No
Troubleshoot Line and Control Circuits
Amplifier Suffers an Arc or Discharge
Yes
Do Meters Indicate Power Supply OK?
No
Troubleshoot Power Supply
Amplifier Has Low Output
Yes
Is Resting or Bias Current OK?
No
Troubleshoot Tube Supplies and Wiring
Check Tube
Yes
Does Output Tuning Peak Normally?
No
Check Output Tuning Network and RF Switching
Yes
Power Supplies and Resting Current OK, but Amplifier has Zero Output
Is Input SWR to the Amp OK?
No
Check Input Network
Check RF Switching
Yes

Figure 4—This moderate-level flow chart is a good way to identify amplifier problems quickly in lieu of a misplaced or nonexistent manufacturer's troubleshooting procedure.

control circuits and relay. If plate current changes, but not as much as normal, try adjusting the output tuning circuitry. If this has little or no effect, the tube may be defective or a connection between the tube and output circuitry may have opened. If retuning has an effect, but at different settings than usual, the tube may be defective or there may be a problem in the tuning circuitry. A visual inspection and an ohmmeter check are in order.

The key to finding the trouble with your amplifier is to be careful and methodical, and to avoid jumping to false conclusions or making random tests. The manufac-turer's customer service department will likely be helpful if you are considerate and have taken careful notes detailing the trouble symptoms and any differences from normal operation. There may be helpful guidelines on the manufacturer's Web pages or from other Internet resources. Sometimes there is more than one problem—they work together to act like one very strange puzzle. Just remember that most problems are very simple and can be isolated by careful, step-by-step tests.

Summary

Amplifiers have been part of ham radio for many years. They are simple, reliable pieces of equipment that respond well to basic care and common sense. Take the time to know your amp—inside and out. If you take care of it, it will reward you with reliable service and maximum tube lifetime.

Notes

[1] Chapter 9 of the current *ARRL Handbook for Radio Communications* is an excellent source of safety information. Available from your local dealer or the ARRL Bookstore. Order no. 1921 (softcover), no. 1948 (hardcover). Telephone toll-free in the US 888-277-5289, or 860-594-0355, fax 860-594-0303; **www.arrl.org/shop/**; **pubsales@arrl.org**.

[2] Instructions for CPR can be found at: **about-the-web.com/spiritworks/web/Kaiser/html/adult.htm**.

[3] Two sources of HV and RF parts include Surplus Sales of Nebraska (**www.surplussales.com**) and Fair Radio Sales (**www.fairradio.com**). Others can be found at the ARRL Technical Information Service database (**www.arrl.org/tis/tisfind.html**).

[4] Penta Labs, "Tube Maintenance & Education" (**www.pentalaboratories.com/maintenance.asp**).

[5] Pelican (**www.pelican-shipping-cases.com**) and Anvil (**www.anvilsite.com**) make excellent shipping cases suitable for carrying amplifiers and radio equipment.

Build safe and reliable amplifiers. Produce loud and clean signals.

Planning to build an amplifier compares well to the work of a cook searching for a recipe and all the ingredients. Find the right design, and then locate the parts and components to begin building.

Shorten your discovery work with *ARRL's RF Amplifier Classics*! Use this book to find classic tube and solid-state designs at power levels from 5 W to 1.5 kW. Included are two-dozen amplifier projects and articles published in ARRL's popular journals between 1980 and 2003. There are amps for HF, MF, VHF and microwave. These are high quality works from respected authors such as Gary Breed, K9AY; Jerry Pittenger, K8RA; Bill Sabin, W0IYH; Al Ward, W5LUA; Dave Meacham, W6EMD and others.

ARRL The national association for AMATEUR RADIO
225 Main Street,
Newington, CT 06111-1494 USA
ARRLWeb: www.arrl.org/



Turn dreams of constructing your first amp or next brick into reality!

ISBN 0-87259-931-0
51995
EAN
9 780872 599314
ISBN 0-87259-931-0 ARRL Order No. 9310

Wire Antennas for Ham Radio

Iulian Rosu YO3DAC / VA3IUL,
http://www.qsl.net/va3iul

Note: *Dimensions of the antennas presented below are either in: feet ('), inch ("), meters (m), or centimeters (cm)*

01 - Tee Antenna
02 - Half-Lamda Tee Antenna
03 - Twin-Led Marconi Antenna
04 - Swallow-Tail Antenna
05 - Random Length Radiator Wire Antenna
06 - Windom Antenna
07 - Windom Antenna - Feed with coax cable
08 - Quarter Wavelength Vertical Antenna
09 - Folded Marconi Tee Antenna
10 - Zeppelin Antenna
11 - EWE Antenna
12 - Dipole Antenna - Balun
13 - Multiband Dipole Antenna
14 - Inverted-Vee Antenna
15 - Sloping Dipole Antenna
16 - Vertical Dipole
17 - Delta Fed Dipole Antenna
18 - Bow-Tie Dipole Antenna
19 - Bow-Tie Folded Dipole Antenna for RX
20 - Multiband Tuned Doublet Antenna
21 - G5RV Antenna
22 - Wideband Dipole Antenna
23 - Wideband Dipole for Receiving
24 - Tilted Folded Dipole Antenna
25 - Right Angle Marconi Antenna
26 - Linearly Loaded Tee Antenna
27 - Reduced Size Dipole Antenna
28 - Doublet Dipole Antenna
29 - Delta Loop Antenna
30 - Half Delta Loop Antenna
31 - Collinear Franklin Antenna
32 - Four Element Broadside Antenna
33 - The Lazy-H Array Antenna
34 - Sterba Curtain Array Antenna
35 - T-L DX Antenna
36 - 1.9 MHz Full-wave Loop Antenna
37 - Multi-Band Portable Antenna
38 - Off-center-fed Full-wave Doublet Antenna
39 - Terminated Sloper Antenna
40 - Double Extended Zepp Antenna
41 - TCFTFD Dipole Antenna
42 - Vee-Sloper Antenna
43 - Rhombic Inverted-Vee Antenna
44 - Counterpoise Longwire
45 - Bisquare Loop Antenna
46 - Piggyback Antenna for 10m
47 - Vertical Sleeve Antenna for 10m
48 - Double Windom Antenna
49 - Double Windom for 9 Bands
50 - Collinear Trap Antenna
51 - Short Dipole Antenna for 40m - 80m - 160m
52 - Center Fed-Zepp Antenna for 80m - 40m
53 - All Bands Antenna
54 - All-Bands Dipole Antenna
147 - KE4PT OCEF All-Band Dipole
148 - Wire Quad Antenna for 40m
149 - Inclined Dipole Antenna for 80m, 40m
150 - Pyramidal Wire Antenna for 80m
151 - Random Wire Antenna All Bands
152 - Multiband Dipole Antenna for 80m, 40m,15m, 10m
153 - Slim Jim Wire Antenna for 4m
154 - Delta Loop for 6m
155 - Re-Configurable Antenna for 160m and 80m
156 - Very Low Frequency Inverted-L Antenna
157 - Reduced Size Half Sloper Antenna for 160m
158 - Tree-Mounted HF Antenna
159 - Multiband Vertical Antenna for 80m, 40m, 20m
160 - Marconi Antenna for 136 kHz
161 - Simple Killer Antenna for 40m
162 - Stub-Directed V Antenna for 80m
163 - KT0NY Over-and-Under DX Antenna for 20m
164 - Horizontal Loop Antennas
165 - Ribbon J-Pole for 2m
166 - Dual Band Ribbon J-Pole for 2m, 70cm
167 - Square Vertical Loop Antenna for 40m
168 - Tri-Band Quad Antenna for 20m, 15m, 10m
169 - 3D Quad Antenna for 80m, 40m, 20m, 15m, 10m
170 - Sloping Wire Antenna for 30m, 20m, 17m, 15m, 12m, 10m
171 - Broadband Dipole Antenna with Coaxial Resonator for 80m
172 - Resonant Feedline Dipole Antenna for 80m
173 - Dual-Band Loading Wire Antenna for 80m, 30m
174 - Stub Matching Antennas
175 - J-Style Vertical Wire Antenna for 10m
176 - Dual Band Vertical with Zepp Feeders for 40m, 20m
177 - RCA Double Doublet for 40m to 12m
178 - RCA Spiderweb Antenna for 40m to 6m
179 - Folded Dipole with Shorted Straps
180 - Twin-Lead Marconi Antenna for 160m, 80m
181 - Broadband Antenna Quarter-Wave Balun for 80m
182 - Three-Quarter-Wave Folded Doublet for Dual-Band
183 - Three-Quarter-Wave Folded Doublet No-Switch for Dual-Band
184 - Wideband Omni-Directional Discone Antenna
185 - Wideband Rhombic Antenna for 40m to 10m
186 - Pre-Cut Linear Array Antenna 3dB-Gain for 40m
187 - X-Array Antenna 6dB-Gain for 20m, 15m, 10m
188 - Double-Bruce Array Antenna 5dB-Gain for 20m, 10m
189 - Bi-Square Broadside Array 4dB-Gain for 20m, 15m, 10m
190 - Six-Shooter Broadside Array 7.5dB-Gain for 20m, 15m, 10m
191 - Triplex Flat-Top Beam 4.5dB-Gain for 20m, 15m, 10m
192 - Dual-Band Tilt Antenna for 20m, 10m
193 - Super Space Multiband Dipole Antenna for 80m to 10m
194 - Bi-Square Beam Antenna Gain=5.5dB for 10m
195 - Cousin of G5RV Multiband Antenna for 40m to 10m
196 - Cayman Quad Antenna for 20m
197 - Hentenna Gain=3dB with Bazooka Match for 6m
198 - X-Beam Antenna Gain=3dB for 20m

55 - Multiband Z Antenna
56 - Multiband Dipole Antenna
57 - Five-Bands No-Tuner Antenna
58 - Dualband Full-wave Loop Antenna for 80m-40m
59 - Loop Antenna for 10m
60 - Lazy Quad Antenna for 10m
61 - Tri-band Delta Loop Antenna for 80m - 40m - 30m
62 - Dual-band Loop Antenna for 30m - 40m
63 - Wire-Beam Antenna for 80m
64 - Dual-Band Sloper Antenna
65 - Inverted-V Beam Antenna for 30m
66 - ZL-Special Beam Antenna for 15m
67 - Half-Sloper Antenna for 160m
68 - Two-Bands Half Sloper for 80m - 40m
69 - Linear Loaded Sloper Antenna for 160m
70 - Super-Sloper Antenna
71 - Tower Pole as a Vertical Antenna for 80m
72 - Clothesline Antenna
73 - Curtain Zepp Antenna for 160m, 80m, 40m
74 - Collinear Array Antenna for 40m, 30m, 20m
75 - 160m Inverted Delta Loop
76 - Half Rhombic Unidirectional Vertical for 20m to 6m
77 - Capacitance Loaded Vertical Antenna for 160m
78 - Fan Dipole Antenna for 80m to 6m
79 - Wire Ground Plane Antenna
80 - Inverted Delta Loop Antenna for 160m
81 - Inverted-L for 160m
82 - 300ohm-Ribbon Dual Band Dipole
83 - Tri-Band Beam for 20m, 15m, 10m
84 - Mini-Horse Yagi Antenna
85 - Backpack J-Pole Antenna for 10m, 6m, 2m
86 - Fan-Dipole Antenna for 80m, 40m, 20m
87 - Capacity Tuned Folded Loop Antenna for 20m
88 - Indoor Loop Antenna for 80m to 30m
89 - Indoor Loop Antenna for 80m
90 - Double-Delta Antenna 80m and 40m
91 - Inductance-Loaded Shortened Dipole for 160m
92 - V-Beam Antenna for 15m
93 - Picnic Vertical Wire Antenna
94 - Laid-Back Quad Antenna for 80m
95 - Phased Loop Antenna
96 - Loop Antenna for TX for 160m
97 - Morgain-Dipole Antenna for 160m and 80m
98 - ZL-Special for 20m, 15m, 10m
99 - Biconical Antenna
100 - Directive Delta-Birdcage Antenna for 20m to 10m
101 - Dual Polarization Antenna for 80m and 40m
102 - Directive 300-ohm-Ribbon Folded Dipole for 15m
103 - Miniature Directive Antenna for 10m
104 - Biquad Antenna 12dBi-Gain for 2.4GHz
105 - Dual-Rhomboid Antenna for 435MHz to 870MHz
106 - Double-Bazooka Antenna for 80m
107 - J-Style Antenna
108 - Vertical / Horizontal / Circular Polarization Antenna
109 - Coax Inverted-L Antenna for 80m
110 - Indoor Compact Loop Antenna for 80m
111 - Helix Antenna
112 - Novice Vertical Antenna for 80m, 40m, 15m, 10m
113 - Stub-Loaded Shortened Dipole for 80m
114 - Six-Band Wire-Stub Trap Antenna for 40m-10m
115 - Multiband Half-Wave Delta-Loop Antenna
199 - Twin Delta Loop Antenna Gain=6dB for 160m, 80m, 40m
200 - Inverted-V Beam Antenna for 30m
201 - FD4 Windom Antenna for 80m, 40m, 20m, 10m
202 - Two Elements Phased Delta Loop for 40m
203 - Three Elements Wire Yagi for 10m
204 - Low Radiation Angle Full-Wave Loop Antenna for 80m
205 - Collinear Antenna Gain=3dB for 2m
206 - X-Ray Monoband Antenna Gain=6.5dBd
207 - Broadside Collinear Curtain Array for 20m
208 - Shrunk Loop Antenna for 80m, 40m
209 - λ/3 Multiband Dipole for 40m, 20m, 17m, 15m, 13m, 10m
210 - K3LR Sloper Antenna Gain=3dB for 160m
211 - Mini Folded Vertical Monopole Antenna for 160m, 80m, 40m
212 - Three Band Dipole for 80m, 40m, 20m
213 - Stub Matched Dipole Antenna
214 - Inverted-Vee Antenna with Bazooka Match
215 - Multiband Long Wire Antenna for 40m, 20m, 15m, 10m
216 - Converted Vee Antenna for 80m, 40m
217 - Swiss Quad Antenna for 20m, 15m, 10m
218 - Japanese Quad Antenna for 20m, 15m, 10m
219 - Seven-Elements Triangle Beam Antenna for 20m
220 - Log Periodic Wire Antenna for 40m
221 - Three-Elements 90-degrees Wire Beam for 20m
222 - Two-Elements Wire Beam for 20m
223 - Suitcase-Fit Dipole Antenna for 80m, 40m, 20m
224 - Multiband Coaxial Dipole for 80m, 40m
225 - Vertical Log Periodic Antenna for 80m, 40m
226 - Inverted Vertical Log Periodic Antenna for 40m
227 - Double Extended Zepp Antenna Gain=7dB for 15m
228 - Double Lazy-H Antenna G=10dB for 70cm
229 - Wire Log Periodic Antenna G=12dB for 15m, 20m
230 - Five-Elements Vertical Log Periodic for 80m, 40m, 20m
231 - Sloping Delta Loop Antenna for 40m
232 - Doublet Antenna for 160m
233 - Log Periodic Wire Beam for 40m
234 - G3LDO Wire Beam Antenna for 20m, 15m, 10m
235 - Phased Delta Loop Array for 20m
236 - Dual Band V-dipole for 80m, 40m
237 - Collinear Array 5dB-Gain for 15m
238 - Two-Band Quad Loop Antenna 80m, 40m
239 - K7CW Quad Antenna
240 - Broadband Short Dipole for 80m
241 - Off-Center Fed Dipole for 40m, 20m, 10m
242 - Broadband Sloper Antenna for 80m
243 - Two-Frequency Dipole Antenna for 80m
244 - Top Loaded Vertical Antenna for 160m
245 - Two Loop Beam Antenna for 20m, 15m
246 - Corner-Fed Delta Loop Antenna for 80m, 40m, 20m
247 - Loaded Delta Loop Antenna for 40m, 20m
248 - Compact Size Dipole for 80m
249 - JAWS 3dB Gain Antenna for 40m
250 - Inverted-V Antenna for 160m
251 - Lazy-U Antenna for 160m
252 - AF3V Compact Antenna for 160m
253 - Hot Beam Wire Antenna for 40m
254 - Sloping Delta Loop for 40m
255 - K6FD Multiband Antenna with T-tuner
256 - Dual Band Dipole Antenna for 17m, 10m
257 - Compact Travel Dipole Antenna for 10m, 15m, 20m
258 - End-Fire Antenna for 160m, 80m, 40m, 20m
259 - Four Band Loop for 40m, 20m, 15m, 10m

116 - Hybrid Vee for 20m, 17m
117 - Six-Shooter Array Antenna, Gain=7.5dB
118 - Multiband Ground-Plane Antenna for 10m, 15m, 20m
119 - Wire Superbeam Antenna for 10m, 15m, 20m
120 - Two Elements Delta-Loop Antenna
121 - Sterba Curtain Antenna
122 - Half-Wave Vertical Zepp Antenna
123 - Lazy-Loop Antenna for 40m
124 - Terminated Folded Dipole for 80m, 40m
125 - Short-Fat Antenna for 15m
126 - Cobra Antenna for 80m
127 - Log-Periodic Wire Antenna for 20m, 15m, 10m
128 - 5-Element Log-Periodic Vertical Antenna for 80m, 40m, 20m
129 - 2m Vertical Wire Antennas
130 - Earth-Mover Inverted-V Antenna for 40m
131 - Coax-Cable Collinear Antennas
132 - Double Bobtail Antenna for 20m
133 - Collinear Zepp Antenna
134 - Taylor Vee Antenna for 20m
135 - Collinear Vertical Antenna 6dB-Gain for 2m, 1.3m, 73cm
136 - Bi-Loop Antenna for 20m
137 - Wire Beam 6dBd-Gain for 10m
138 - Sloping Diamond Antenna 4dB-Gain for 40m
139 - Twisted Loop Antenna for 160m
140 - DX RX Loop Antenna for 160m
141 - Hentenna 3dB-Gain for 10m, 6m, 2m
142 - VK2AAR Wire Antenna for 20m
143 - 2-Elements Quad Antenna for 6m
144 - Hula-Loop Bidirectional 6dB-Gain Antenna for 17m
145 - Moxon Rectangle Beam for 15m-10m
146 - Double-D Beam 4dB-Gain
260 - Carolina Windom Antenna for 80 to 10m
261 - Shortened Loaded Dipole for 40m
262 - Shortened Loaded Dipole for 80m
263 - Low Radiation Angle Inverted Delta Loop for 80m
264 - Compact Dipole Antenna for 40m, 15m
265 - Vertical Delta Loop for 40m to 10m
266 - Delta Loop Antenna for 17m
267 - Bi-Square Beam Gain=3dBd for 17m
268 -Trap Dipole Antenna for 17m,13m
269 - Hanging Unipole Antenna for 160m, 80m
270 - Wideband Sloping Vee Antenna - 30m to 6m
271 - 5/8 Wavelength Antenna
272 - C-Pole Vertical Antenna
273 - Bobtail Antenna for 30m
274 - Bobtail Antenna for 40m
275 - Two Elements Vertical Loop Antenna for 40m
276 - Double Extended Zepp Antenna for 40m
277 - Reversible Moxon Flip Beam for 40m
278 - Spitwire Antenna for 40m
279 - Fork Antenna for 40m
280 - Veebeam Antenna 3dB-Gain for All Bands
281 - Vertical Moxon Antenna for 10m
282 - Half-Square Antenna for 30m
283 - Rotatable Vertical Delta Loop for 20m
284 - Mini-Horse Antenna 10dB-Gain for 40m-to-2m
285 - Compact Moxon Antenna 5dB-Gain for 40m
286 - Two Elements Sloping Delta Loop 8dB-Gain for 10m
287 - Two Elements Phased Vertical Antenna 3dB-Gain for 40m

---

01 - Tee Antenna


WIRE RADIATOR ELEMENT
(TYPICALLY 10 TO 40 METERS)
END INSULATOR
ROPE
ROPE
END INSULATOR
DOWNLEAD
LIGHTNING
ARRESTOR
ant
RECEIVER
Gnd
http://www.qsl.net/va3iul

02 - Half-Lamda Tee Antenna


2L
L
$2L = \frac{143}{F_{\text{MHz}}}$ meters
$L = \frac{71.5}{F_{\text{MHz}}}$ meters
http://www.qsl.net/va3iul

03 - Twin-Led Marconi Antenna


L
RADIALS
COAX TO
RECEIVER
GROUND
ROD
http://www.qsl.net/va3iul

04 - Swallow-Tail Antenna


http://www.qsl.net/va3iul
WIRES
ROPE
COAX TO RECEIVER
EARTH CONNECTION

05 - Random Length Radiator Wire Antenna


RANDOM LENGTH RADIATOR WIRE
COAX TO RECEIVER
ANTENNA TUNING UNIT
QUARTER WAVELENGTH RADIALS
EARTH CONNECTION
http://www.qsl.net/va3iul

06 - Windom Antenna


L
0.36L
DOWNLEAD
ATU
XCVR
http://www.qsl.net/va3iul

07 - Windom Antenna - Feed with coax cable



$\frac{\lambda}{4}$
$\frac{3\lambda}{4}$
ROPE
ROPE
$\frac{\lambda}{2}$
$\frac{\lambda}{2}$
4:1 BALUN TRANSFORMER
END INSULATOR
75 OHM COAX TO RECEIVER
END INSULATOR
http://www.qsl.net/va3iul

08 - Quarter Wavelength Vertical Antenna



http://www.qsl.net/va3iul
RADIATOR ELEMENT
$L_{\text{meters}} = \frac{75}{F_{\text{MHz}}}$
52-OHM COAX TO RIG OR RECEIVER
RADIALS

09 - Folded Marconi Tee Antenna



A
$A_{\text{meters}} = \frac{82}{F_{\text{MHz}}}$ meters
$B_{\text{meters}} = \frac{82(\text{VF})}{F_{\text{MHz}}}$ meters
B
52-Ohm Coax to Rig
http://www.qsl.net/va3iul
QUARTER WAVELENGTH RADIALS

10 - Zeppelin Antenna


ROPE
END INSULATORS
RADIATOR WIRE
END INSULATOR
ROPE
FEEDLINE
ANTENNA TUNER
COAX TO RIG
http://www.qsl.net/va3iul

11 - EWE Antenna


L2
L1
L1
T1
R 850 OHMS
TO RCVR
L1 = 3 m
L2 = 6.5 m
http://www.qsl.net/va3iul

12 - Dipole Antenna - Balun


B
A
A
1:1 BALUN TRANSFORMER
COAX TO RECEIVER OR TRANSMITTER
http://www.qsl.net/va3iul

13 - Multiband Dipole Antenna


26 FEET (7.93 M)
22.25 FEET (6.78 M)
19.5 FEET (5.94 M)
26 FEET (7.93 M)
22.25 FEET (6.78 M)
19.5 FEET (5.94 M)
1:1 BALUN TRANSFORMER
COAX TO RECEIVER OR TRANSMITTER
http://www.qsl.net/va3iul

14 - Inverted-Vee Antenna


http://www.qsl.net/va3iul
MAST
$L_{\text{meters}} = \frac{76}{F_{\text{MHz}}}$ meters
1:1
BALUN
END INSULATOR
WIRE ELEMENTS
COAX TO
RIG OR
RECEIVER
END INSULATOR
ROPE
ROPE
STAKE
STAKE
EARTH'S SURFACE

15 - Sloping Dipole Antenna


ROPE
http://www.qsl.net/va3iul
END INSULATOR
VERTICAL
SUPPORT
STRUCTURE
1:1
BALUN
λ/4 WIRE ELEMENTS
COAX TO
RIG OR
RECEIVER
END INSULATOR
ROPE
STAKE
EARTH'S SURFACE

16 - Vertical Dipole


OVERHEAD SUPPORT
http://www.qsl.net/va3iul
ROPE
END INSULATOR
QUARTER WAVELENGTH RADIATOR ELEMENTS
COAX TO RIG OR RECEIVER
END INSULATOR
ROPE
STAKE IN GROUND
EARTH'S SURFACE

17 - Delta Fed Dipole Antenna


A
B
B
C
A = 142/F_{MHz}
B = 54/F_{MHz}
C = 45/F_{MHz}
http://www.qsl.net/va3iul

18 - Bow-Tie Dipole Antenna


L
W
1:1 BALUN TRANSFORMER
W = 0.11 L
L = 415/F_{MHz}
http://www.qsl.net/va3iul

19 - Bow-Tie Folded Dipole Antenna for RX


A
B
B
4:1
XFMR
A = 465/F_{MHz}
B = 200/F_{MHz}
http://www.qsl.net/va3iul
75 OHM COAX
TO RECEIVER

20 - Multiband Tuned Doublet Antenna


145/F_{MHz}
450-OHM TWIN-LEAD
MATCHING SECTION
73/F_{MHz}
COAX TO
RECEIVER
http://www.qsl.net/va3iul

21 - G5RV Antenna


A
A
B
300-OHM OR
450-OHM
TWIN-LEAD
COAXIAL
CABLE
http://www.qsl.net/va3iul

$$A = \frac{220}{F_{\mathrm{MHz}}}\ \text{meters}$$

$$B = \frac{146V}{F_{\mathrm{MHz}}}\ \text{meters}$$

22 - Wideband Dipole Antenna


L = 146/F_MHz
M = 133/F_MHz
FOLDED DIPOLE
SPREADERS
30.5 CM
61 CM
CENTER-WIRE ELEMENT
450 OHM TWIN-LEAD (ANY LENGTH)
9:1 BALUN XFMR
COAX TO RECEIVER
http://www.qsl.net/va3iul

---

23 - Wideband Dipole for Receiving


6.7 m
12.2 m
2.45 m
12.2 m
6.7 m
1.8 m
RLN
1.8 m
1.8 m
RLN
1.8 m
4:1 BALUN
LEGEND
RLN RL NETWORK
END INSULATOR
INSULATING SPREADER
COAX TO RECEIVER
390 OHMS
18 µH
RL NETWORK
http://www.qsl.net/va3iul

---

24 - Tilted Folded Dipole Antenna


L
L
R1 390 OHM RESISTOR
A'
C'
W
A
C
W = 2.99/F_MHz
L = 54.3/F_MHz
4:1 BALUN XFMR
75-OHM COAX TO RECEIVER
http://www.qsl.net/va3iul

---

25 - Right Angle Marconi Antenna


λ/8
λ/8
http://www.qsl.net/va3iul

26 - Linearly Loaded Tee Antenna


A
(λ/3)
B
B
C = λ/4
$A = \frac{50}{F_{\mathrm{MHz}}}$ meters
$B = 25\,\mathrm{cm}$
$C = \frac{75}{F_{\mathrm{MHz}}}$ meters
PARALLEL LINE
ANTENNA TUNING UNIT
http://www.qsl.net/va3iul

27 - Reduced Size Dipole Antenna


λ/6
λ/6
λ/12
λ/12
ANTENNA TUNING UNIT
http://www.qsl.net/va3iul

28 - Doublet Dipole Antenna


B
A
A
$B = \frac{102}{F_{\text{MHz}}}$ meters
$C = \frac{32}{F_{\text{MHz}}}$ meters
$D = \frac{8.8}{F_{\text{MHz}}}$ meters
C
D
http://www.qsl.net/va3iul
4:1 BALUN
75 OHM COAX TO
RIG OR RECEIVER

---

29 - Delta Loop Antenna


L2
http://www.qsl.net/va3iul
L1
L3
L1 = L2 = L3 = λ/3
QUARTER WAVELENGTH
MATCHING SECTION
(75 OHM COAX)
52 OHM COAX TO RIG OR
RECEIVER (ANY LENGTH)

---

30 - Half Delta Loop Antenna


http://www.qsl.net/va3iul
λ/3
λ/6
EARTH

---

31 - Collinear Franklin Antenna


A
A
A
A
B
B
A = $\frac{\lambda}{2}$
B = $\frac{\lambda}{4}$
A
TO RECEIVER
http://www.qsl.net/va3iul

32 - Four Element Broadside Antenna


HALF-WAVELENGTH
VERTICAL ELEMENTS (4)
λ/2
λ/2
λ/2
λ/2
600-OHM OPEN
PARALLEL LINE
4:1
BALUN
COAX TO RIG
OR RECEIVER
http://www.qsl.net/va3iul

---

33 - The Lazy-H Array Antenna


λ/2
λ/2
λ/2
1 λ
1:1 BALUN
XFMR
COAX TO
RECEIVER
http://www.qsl.net/va3iul

---

34 - Sterba Curtain Array Antenna


B
A
B
A
A
$A = \frac{\lambda}{2}$
$B = \frac{\lambda}{4}$
B
B
B
B
4:1 BALUN XFMR
75-OHM COAX TO RECEIVER
http://www.qsl.net/va3iul

---

35 - T-L DX Antenna


$L1 = \frac{53.2}{f_{MHz}}$ meters
$L2 = \frac{39.8}{f_{MHz}}$ meters
$L3 = \frac{66.6}{f_{MHz}}$ meters
$L4 = \frac{21.3}{f_{MHz}}$ meters
$L5 = \frac{108.4}{f_{MHz}}$ meters
$L6 = \frac{94.2}{f_{MHz}}$ meters
$L7 = \frac{136.8}{f_{MHz}}$ meters
http://www.qsl.net/va3iul
L1
L2
L3
L5
L6
L4
50-Ohm Coax
Ground Rods
L7

---

36 - 1.9 MHz Full-wave Loop Antenna


http://www.qsl.net/va3iul
132′ 2–3/4″
No. 14 wire
50′
132′ 2–3/4″
132′ 2–3/4″
132′ 2–3/4″
Open–wire
or ladder line
(any length)
50′
To 4:1 balun XFMR and ATU

---

37 - Multi-Band Portable Antenna


1 IN. DIA. METAL RING
SEE DETAIL B
NYLON ROPE 1/8 IN. DIA.
22 1/2 IN. APPROX. SPACING
SOLDER 4 WIRES TO ONE COMMON LUG (ATTACH TO BALUN WITH WING-NUT)
NYLON ROPE 30 FEET 1/8 IN. DIA.
40 METER ANTENNA 32 FT. 11 1/2 IN.
20 METER ANTENNA 16 FT. 7 IN.
15 METER ANTENNA 11 FT. 1/2 IN.
10 METER ANTENNA 8 FT. 2 IN.
SEE DETAIL A
ONE HALF OF INVERTED VEE ANTENNA
(NOT DRAWN TO SCALE)
USE NO. 14 INSULATED BRAIDED ANTENNA WIRE
1/4 IN.
1 3/4 IN. (TYPICAL)
WOOD OR PLASTIC DOWEL 5 3/4 IN. X 5/16 IN. DIA.
DRILL HOLE FOR WIRE
1/2 IN. WIRE BRAD NAIL THROUGH ANT. WIRE (PREDRILL TIGHT HOLE FOR NAIL)
CUT AND FILE OFF PROTRUDING NAIL
DETAIL A
TYPICAL SPACER
40 METER ANT. WIRE
DETAIL B
1/8 IN. DIA. NYLON ROPE
1 TO 1 BALUN (1 KW) DO NOT PUT METAL AROUND BALUN (USE PLASTIC CLAMPS)
3 FT.
BAMBOO OR WOOD SECTION
CUT TOP POLE SECTION HERE
ADD STOP SCREW ON EACH POLE SECTION TO PREVENT BINDING WHEN ASSEMBLED
1 FT.
ADD 3 CLIPS AT 20 FOOT HEIGHT
SMALL QUICK DISCONNECT HOOKS (3 REQUIRED)
4 TO 5 FT. TYPICAL
1 1/4 IN. DIA.
BIRDS
ONE MAN SET-UP PROCEDURE
WARNING: DO NOT DO THIS NEAR STORMY WEATHER
23 FT. MEASURE WITH GUY ROPE
SET ANT. GUYS AFTER POLE IS UP
COAX LEAD-IN
24 TO 30 FT. POLE (SIX SECTIONS) SEE TEXT
24 FT. X 1/8 IN. DIA. NYLON ROPE (3 REQUIRED)
LARGE CHEAP PHILLIPS SCREWDRIVERS FOR ANCHOR POSTS AND 1 INCH DIA. METAL RING ON END OF EACH GUY ROPE (3 PLACES)
RG-58
http://www.qsl.net/va3iul

38 - Off-center-fed Full-wave Doublet Antenna


λ/2
λ/2
Rope
EI
EI
Rope
λ/4
1:1 BALUN
75-Ω coaxial cable
L_feet = 936 / F_MHz
http://www.qsl.net/va3iul

39 - Terminated Sloper Antenna


http://www.qsl.net/va3iul
Rope
EI
$\frac{\lambda}{4}$ radial
Wire antenna element (≥ 3/4 λ at lowest frequency)
Direction of reception
Coax to receiver
Mast
Ground
R_1
270 Ω
2-watt
Ground connection

---

40 - Double Extended Zepp Antenna


L_1
L_1
Rope
EI
EI
Rope
L_2
$L_{1feet} = \frac{600}{F_{MHz}}$
$L_{2feet} = \frac{103}{F_{MHz}}$
http://www.qsl.net/va3iul
($Z_L \approx 150\ \Omega$)

---

41 - TCFTFD Dipole Antenna


http://www.qsl.net/va3iul
L
D
30° ± 10°
C_2
R_1
390 Ω
(noninductive)
A_2
C_1
4:1 balun
A_1
L is 27 ft
Ht
$W \geq \frac{9.8}{F_{MHz}}$ ft
75-Ω coaxial cable
L
B
6ft
6ft

---

42 - Vee-Sloper Antenna


http://www.qsl.net/va3iul
ATU
Coax
To
RCVR
L
α
L
R
R
$R \approx 270\ \Omega$
$L > \lambda$

---

43 - Rhombic Inverted-Vee Antenna


http://www.qsl.net/va3iul
A>λ
A
Φ
A
Direction of reception
Mast
To RCVR
R_1

---

44 - Counterpoise Longwire


$\frac{\lambda}{4}$
>2λ
$\frac{\lambda}{4}$
Rope
EI
R1
EI
Rope
4:1 balun transformer
Radiator
Coax to transmitter
EI = end insulator
R = rope
R_1 = termination resistor (noninductive)
http://www.qsl.net/va3iul

---

45 - Bisquare Loop Antenna


Each side is λ/2
L side = 480/F MHz
λ/4 Matching section
1:1 BALUN transformer
52 Ω Coaxial cable to receiver
http://www.qsl.net/va3iul

46 - Piggyback Antenna for 10m


Existing Dipole
Center Insulator
Insulator *
Twisted Wire
Soft Copper Wire
1/2 λ = 468/f (MHz)
* Should be Long Enough to Prevent Tangling
Existing Feed Line
http://www.qsl.net/va3iul

47 - Vertical Sleeve Antenna for 10m


1/4–λ Whip
(Approx. 8 ft)
1/2 λ
1/4 λ
Sleeve of Copper
Shielding Braid
(Approx. 8 ft)
to
Station
http://www.qsl.net/va3iul

---

48 - Double Windom Antenna


to
support
13.8 m (45.28 ft)
6:1
Balun
27.7 m (90.88 ft)
to
support
4.69 m
(15.39 ft)
≈100°
9.38 m
(30.77 ft)
≈ 8.0 m
(26.25 ft)
to
support
50–Ω Coax
to TX
to
support
Ground
http://www.qsl.net/va3iul

---

49 - Double Windom for 9 Bands


to
ground
anchor
http://www.qsl.net/va3iul
25.88 m
(84.91 ft)
6:1
Balun
51.77 m
(169.85 ft)
to
ground
anchor
4.69 m
(15.39 ft)
9.38 m
(30.77 ft)
8.0 m
(26.25 ft)
to
ground
anchor
50–Ω Coax
to TX
to
ground
anchor
ground

---

50 - Collinear Trap Antenna


≈12′
≈12′
≈28.5′
21.2–MHz Trap
14.2–MHz Trap
C_2
L_2
14.2–MHz Trap
21.2–MHz Trap
C_1
L_1
7′
3/4 λ at 21.2 MHz
3/4 λ at 14.2 MHz
1/4 λ at 3.7 MHz
Z_1
Balun
http://www.qsl.net/va3iul
RG–8/U

C1, C2—25-pf. 6000-volt disk ceramic. See text.
L_1—Approx. 2 µH–4¾ turns No. 18, 2¼-inches diam., ⅜ inch long, or 5 turns No. 18, 2-inch diam., 16 tpi. See text.

L_2—Approx. 5 µH.—8 turns No. 18, 2¼-inch dia., ⅝ inch long, or 9 turns No. 18, 2-inch diam. 16 tpi. See text.
Z_1—1 to 1 balun.

51 - Short Dipole Antenna for 40m - 80m - 160m


1:1 Balun or Center Insulator
18.3 Feet
11 Feet
32.2 Feet
32.2 Feet
11 Feet
18.3 Feet
3.8–MHz Trap
7–MHz Trap
7–MHz Trap
3.8–MHz Trap
http://www.qsl.net/va3iul
Feed Line to Radio

52 - Center Fed-Zepp Antenna for 80m - 40m


http://www.qsl.net/va3iul
61′
Spreaders
53′
30′ TV Mast
30′ TV Mast
To Transmatch

53 - All-Bands Antenna


http://www.qsl.net/va3iul
65'
65'
"TV" Standoff Lag
30'
No. 14 Wire
To Stub Pole
To Stub Pole
14'
14'
Large Spike
One Spreader
Concrete

54 - All-Bands Dipole Antenna


1/2 λ
1/2 λ
1/2 λ
1/2 λ
"A"
"B"
"C"
"D"
"E"
"F"
Coaxial Transmission Line (Any Length)
http://www.qsl.net/va3iul

55 - Multiband Z Antenna


http://www.qsl.net/va3iul
70'
60'
α
60'
α
70'
100'
450 Ω
160–10 Meter
Transmatch

---

56 - Multiband Dipole Antenna


44'2" Insulated and
Stranded Copper Wire
44'2"
36'8" Twin Lead
(300 Ω)
Run Twin–Lead
to a Point Near
Transmitter
A
B
Load Here (see text)
7'2" ±2" of
RG–58/U Cable
Wound into a
3" Dia. Roll and
Taped in Three
Places
RF Choke
http://www.qsl.net/va3iul
To Transmitter

---

57 - Five-Bands No-Tuner Antenna


94'
End Insulator
End Insulator
Center Insulator
450-Ω Ladder Line (41')
1:1 Balun
50-Ω Coaxial Cable
http://www.qsl.net/va3iul

Frequency	*SWR*
3.56	7.6:1
7.1	2.4:1
14.2	1.5:1
18.1	2:1
24.9	1.5:1
29	2.4:1

---

58 - Dualband Full-wave Loop Antenna for 80m-40m


http://www.qsl.net/va3iul
m = Feet (') × .03048
104'
Nylon Rope
52'
12'
Nylon Rope
22'
50 - Ω Coaxial Cable to Station
75 - Ω RG - 59 Coaxial Cable 1/4 λ Transformer

---

59 - Loop Antenna for 10m


73"
146"
Coax
Gain = 1.7 dBd
3 turns,
1' diameter
http://www.qsl.net/va3iul

---

60 - Lazy Quad Antenna for 10m


λ/4
H1
8'
8 inch
Stubs
Loop 1
H2
73 Ω
Coax
8'
H3
Loop 2
8'
16' to Ground
http://www.qsl.net/va3iul

61 - Tri-band Delta Loop Antenna for 80m - 40m - 30m


Close-Up of Supports
Support Rope
Screen Door Spring
Insulator
Strain Limit Loop
Support (see inset)
Approx. 80 ft on both untrapped legs
40 M Trap
30 M Trap
Center Insulator
30 M Trap
40 M Trap
Support (see inset)
Support (see inset)
23 ft
7 ft
5 ft
RG-59/U Quarter-Wave Matching Section for 75 Meters (40.1 ft, including choke coil)
Choke Coil (5 turns approx. 1 ft diameter)
RG-8X (any length) to shack
http://www.qsl.net/va3iul

---

62 - Dual-band Loop Antenna for 30m - 40m


Insulator Block
Supported by
Tree or Pole
Weatherproof
Connection
23' RG-11
(Solid Dielectric)
47' Long
Each Side
PL-258 and
Two PL-259s
(Weatherproofed)
RG-8 to
Shack
Ceramic
Knife
Switch
Insulator
Insulator
to Anchor
to Anchor
12'
18" Tuning Wires to
Resonate Open Loop
at 10.125 MHz
http://www.qsl.net/va3iul
Total Length (in Feet) of Loop (at 40 M) = 1005 / F (MHz) or 141'

63 - Wire-Beam Antenna for 80m


http://www.qsl.net/va3iul
105'
Guy Radius
to Anchor
Guy Wire
136'
130'
Back Truss
Support
#16 Copper Wire
1/4" Delrin
Rod Spacers
35'
Switch Box at
Ground Level
120° Tower
Guy Pattern
Crossarm
36' Long
18"
# 14 Wire
1/2" Delrin Rod
Spreaders

64 - Dual-Band Sloper Antenna


http://www.qsl.net/va3iul
L1
L1
L2
L1
L1
RG - 8/U Transmission Line
D
Anchor
* = Insulators

	Band	
	75	40
L1	61.5′	32.7′
L2	30.7′	17′
D	60′	36′

65 - Inverted-V Beam Antenna for 30m


Nylon Rope
12′
1/2″ PVC Pipe Boom
1:1 Balun
Insulator
22′
23.5′
90° or Greater
1/2″ PVC Pipe
Nylon Rope
12′
Coaxial Cable to Shack
Coaxial "T" Connectors
1/4 λ RG-59/U
75-Ω Coaxial Cable
1/4-λ Stub 2 Pieces RG-59/U
50-Ω
http://www.qsl.net/va3iul

66 - ZL-Special Beam Antenna for 15m


http://www.qsl.net/va3iul
Max
20'6"
4"
5'6"
Max
Twin-Lead Stub
10' (see text)
12"
Coax to Rig
100 pF

---

67 - Half-Sloper Antenna for 160m


http://www.qsl.net/va3iul
Insulator
Two Wires, Each 130' Long
75'
50-Ω to Xmtr
L Network
80' of 300-Ω Twin Lead

---

68 - Two-Bands Half Sloper for 80m - 40m


Center Conductor to Wire, Shield to Mast
31 Ft
40 Ft
45°
T
4 Ft
40 Ft
90.2 Ft
RG–8/U
L
Any Length 50 Ω Coax to Shack
8.2 μH
T:
60 pF
(Resonant at 7.2 MHz)
≈2 μH
L:
http://www.qsl.net/va3iul

69 - Linear Loaded Sloper Antenna for 160m


http://www.qsl.net/va3iul
Slight Directivity
Strain Insulator
Connect Shield to Tower Leg with Hose Clamp
Ties
8–1/2"
6–1/2"
8'
Center Conductor
65'
Coax Taped to Tower Leg
No. 14 to 18 AWG Insulated, Stranded Wire
55'
Small Loops
Electrical Connection
Solder and Tape to Dowel
42'
20'
No Electrical Connection
Monofilament Fishing Line
Monofilament Fishing Line
50–Ω Coax to Radio
Grounded Tower
All Dimensions Approximate

70 - Super-Sloper Antenna


1/4 λ Offset Shown
Feedpoint
http://www.qsl.net/va3iul
λ/2
λ/2
λ/2
λ/2
λ/2
λ/2
Maximum Radiation
Parasitic Element
Nonconductive Pole
Spacing ≈0.02 to 0.04 λ
Driven Element
Tilt Angle

---

71 - Tower Pole as a Vertical Antenna for 80m


TH7
25 ft
65–ft Radials
RG–59 x 2 1/4 λ
75–Ω 1/2–in. CATV Line to Shack
(A)
http://www.qsl.net/va3iul
Matching Section
RG–59, 75 Ω
17 Ω
80 Ω
RG–59, 75 Ω
46 ft

---

72 - Clothesline Antenna


132 ft. for Base Frequency of 80 meters (3.5 MHz). 264 ft. for 160
Midpoint
Plastic Pulley
Insulator
Wire
Plastic Pulley
(A)
(B)
300 Ω Feed Line (any length)
6 : 1 Balun
Coax to Transceiver (any length)
http://www.qsl.net/va3iul

73 - Curtain Zepp Antenna for 160m, 80m, 40m


40 meter Trap
Insulator with jumper
42'
42'
42'
Insulator with jumper
42'
40 meter Trap
Window Line to EDZ
Bird House Detail
Window Line to Shack
Single wire to 160/80 meter Tuners
80'
80' Ladder Line
80'
70' Horizontal loading line 10' off ground
70' Horizontal loading line 10' off ground
Bird House Relay
Vertical ladder line shorted, Single wire feed to tuning house
Ladder line to shack 40 meter feed
Tuning House
RG8 to shack, 160/80 meters
http://www.qsl.net/va3iul

74 - Collinear Array Antenna for 40m, 30m, 20m


40 meter Trap Open
Insulator
Insulator
Insulator
40 meter Trap Open
Ladder line, equal lengths. Watch for phasing in-phase!
Bird House Relay
Ladder line to shack
http://www.qsl.net/va3iul

---

75 - 160m Inverted Delta Loop


86'
76'
76'
65'
70'
~ 5"
4'
Feed-thru Insulators
L1
75 UNUN 50
T1
"Dog House"
50/75 Ω UNUN available from Amidon Associates in either kit form or completely wired and tested.
Radial System
Coax to Shack
http://www.qsl.net/va3iul

---

76 - Half Rhombic Unidirectional Vertical for 20m to 6m


http://www.qsl.net/va3iul
200 feet
216 feet
Wire
40 foot
Mast
50 Ω Coax
to Radio
9:1
Unun
9:1
Unun
50 Ω
Dummy
Load
3 or 4
Short Radials
3 or 4
Short Radials

---

77 - Capacitance Loaded Vertical Antenna for 160m


http://www.qsl.net/va3iul
A
B
C
D
J
F
G
I
C1
E
H
K

C1 — Variable capacitor, 0-1500 pF, 7 kV.
A, B — Sloping segments of 66 foot, 4 inch pieces of #16 AWG enameled copper wire soldered to the top of segments C and D and forming a 45° angle.
C, D — 59 feet of 450 Ω open wire or window line or, alternatively, two parallel lengths of #16 AWG enameled copper wire with a 1 inch separation.
E — 1 inch triangle formed by the bottom ends of the open wire line. Solder them tightly at the vertex and connect to C1.
F, G — Distance between the lower ends of segments A and B from segments C and D, 51 feet.
H — Any length of 50 Ω coaxial cable (RG-213 in this case). The central conductor must be soldered to C1, and the braid to the ground radials.
I — Approximately 16 feet from ground to lower ends of sloping segments A and B.
J — 60 feet from antenna top to bottom.
K — Ground radials, 60 ¼ λ (the more the better — 32 will form a reasonable ground).

---

78 - Fan Dipole Antenna for 80m to 6m


Mast
Detail
Eye Bolt
Mast
(Schedule 80 PVC)
Rope
Ring cut from
PVC pipe
80 M
40 M
20 M
10 M
80 M
40 M
20 M
10 M
Split Bolt
Connectors
Center
Conductor
Coax
Braid
80 M, 66 ft
Vents
House
20 M, 16-1/2 ft
10 M, 8-1/4 ft
20 M, 16-1/2 ft
40 M, 32-1/2 ft
Mast
10 M, 8-1/4 ft
40 M, 32-1/2 ft
Rope
80 M, 66 ft
Garage
Tree
Fence
http://www.qsl.net/va3iul

79 - Wire Ground Plane Antenna



The lengths of all 3 sides is determined by the formula of a 1/4 wave antenna

This antenna configuration will work for all frequencies from 160 meters to VHF.

$$\text{Length (in feet)} = \frac{234}{\text{frequency in MHz}}$$

The vertical side uses the inner conductor of the coax. On the Budwig the is side the shows a "+" (plus sign). The outer (lower) legs use the outer braid or the "-" (minus sign).

Budwig Antenna
Connector
SO-239 Chassis mount, 4 hole
Generic Insulator Connection
Insulator
Inner Conductor
Outer
Braid
Transmission Line
from Transmitter
http://www.qsl.net/va3iul
Coax to XCVR or XMTR

80 - Inverted Delta Loop Antenna for 160m


86'
76'
76'
65'
70'
~ 5"
4'
Feed-thru Insulators
17 µH
L1
"Dog House"
50/75 Ω UNUN available from Amidon Associates in either kit form or completely wired and tested.
75 UNUN 50
T1
L1 is 17 turns, 2.5 inches in diameter,
Radial System
Coax to Shack
http://www.qsl.net/va3iul

---

81 - Inverted-L for 160m


234 f
As High as Practical
50 Ω Coax To Station
Ground System
http://www.qsl.net/va3iul

---

82 - 300ohm-Ribbon Dual Band Dipole


134 ft
67 ft
300Ω ribbon
Open end
Shorting link
Shorting link
Open end
300Ω ribbon
70Ω coaxial cable
Any length
4:1 balun
http://www.qsl.net/va3iul

83 - Tri-Band Beam for 20m, 15m, 10m


11ft 6in
8ft 3in
6ft
Approx position of small screw hooks – adjust to loops
Centre-end of bamboo spreader
Reflector elements
http://www.qsl.net/va3iul
Loop around wires
Small perspex insulator
1/4" max
20m
15m
10m
Nylon cord
Centre piece
Voltage feedback and reflector drive via light insulators
90° phase-shift produces cardoid beam pattern
Maximum signal
PLAN VIEW
Driven elements
Nylon cord
Clamp spreaders
Total loop lengths...
20m.....69ft
15m.....46ft 6in
10m.....34ft 9in
Plastic-covered stranded-wire used for elements
Driven elements
75Ω coaxial feeder
Alternative construction of spreader
8ft long dowel or bamboo
5ft of 3/4 in dia aluminium tube
18 x 18in thick ply-wood centre piece
No metal-work should be bonded together or to metal mast but should be left floating

84 - Mini-Horse Yagi Antenna


http://www.qsl.net/va3iul
Direction of Forward Gain
Director
2A
1 mm Insulated Wire
F
B
Support Lines
H
L
C
A
Radiator
D
Fishing Rod
G
E
50 Ω Coax
Reflector
1 mm Insulated Wire
QS1003-Hedman01

MHz	A	B	C	D	E	F	G	H	L
144	1' 2.2"	0' 4.7"	0' 3.5"	0' 1.8"	0' 7.1"	0' 4.7"	0' 6.5"	1' 4.5"	1' 4.3"
28	5' 11.6"	1' 10.8"	1' 6.9"	0' 9.4"	2' 11.8"	1' 10.8"	2' 8.3"	6' 11.4"	6' 11.0"
21	7' 11.6"	2' 6.3"	2' 1.2"	1' 0.6"	3' 11.6"	2' 6.3"	3' 6.9"	9' 3.0"	9' 2.6"
14	11' 11.3"	3' 9.7"	3' 1.8"	1' 6.9"	5' 11.2"	3' 9.7"	5' 4.6"	13' 10.9"	13' 9.7"
7.1	23' 10.5"	7' 7.3"	6' 3.6"	3' 1.8"	11' 10.5"	7' 7.3"	10' 9.1"	27' 9.8"	27' 7.4"

85 - Half-Rhombic Directive Antenna for 20m to 6m


http://www.qsl.net/va3iul
REMOVE SHADED AREA
5540 MHZ (INCHES)
1/2 WAVE RADIATOR
300 Ω RIBBON
2880 MHZ (INCHES)
1/4 WAVE MATCHING STUB
CENTER CONDUCTOR
SHIELD
50Ω COAX

Frequency (MHz)	28.0	28.5	29.0	50.0	51.0	52.0	144	145	146	147
Radiator (inches) ½ wave	197.8	194.3	191.0	110.8	108.6	106.5	38.4	38.2	37.9	37.7
Stub (inches) ¼ wave	102.8	101.0	99.3	57.6	56.4	55.3	20.0	19.8	19.7	19.6

86 - Fan-Dipole Antenna for 80m, 40m, 20m


http://www.qsl.net/va3iul
117'
66'
34'
Pulleys
AWG 12
4:1
Balun
Rope
Insulators
20'
Coax fed thru PVC

87 - Capacity Tuned Folded Loop Antenna for 20m


Shrink Tubing
And Rope
Capacity
Stub
24"
Loop
24' 8"
Feedline
27' 10"
http://www.qsl.net/va3iul
To Balun

---

88 - Indoor Loop Antenna for 80m to 30m


62.5"
CAPACITOR
MAIN
LOOP
66.5"
INPUT LOOP
62.5"
250 pF
66.5"
PL 259
3.5"
27"
http://www.qsl.net/va3iul

---

89 - Indoor Loop Antenna for 80m


18"
4"
http://www.qsl.net/va3iul
Gamma Tap
1/16" Wood
(see text)
1/4" x 1/4" x 6"
Corner Bracers
9" x 1/4" x 1/4"
Strip
Front View
Wire
Ends
6"
18"
6X Loop Turns
Spaced .6" Apart
Coupling
Turn
End View
9" x 1/4" x 1/4"
Strips

90 - Double-Delta Antenna 80m and 40m


LIMB ON TREE -
APPROX. 29 ft ABOVE GROUND
http://www.qsl.net/va3iul
ROPE
PLASTIC INSULATOR
WITH LOADING
RESISTOR
25 ft
25 ft
25 ft
25 ft
EGG
INSULATORS
7 ft
7 ft
7 ft
7 ft
3 ft
PLASTIC
INSULATOR
300Ω TRANSMISSION
LINE
WOOD
STAKES
3-4 in. SQ. PLEXIGLASS
1/4-1/2 in. THICK
LOADING
RESISTOR
120 Ω
(CORNING
RD25P)
WIRE JUMPERS
HOLE FOR ROPE
SUPPORT (KNOT END OF
ROPE UNDER INSULATOR)
3-4 in. SQ. PLEXIGLASS
1/4-1/2 in. THICK
JUMPERS
RETAINING CLAMP
TRANSMISSION LINE

91 - Inductance-Loaded Shortened Dipole for 160m


COIL
A
B
FEED LINE



Overall Length (ft.)	Element A Length	Number Of Coil Turns	Element B Length
246.3	full-size antenna		
221.3	66.5	10	44.3
197.1	59.1	20	39.4
172.4	51.7	33	34.5
147.8	44.3	48	29.6
123.2	36.9	65	24.6
98.5	29.6	86	19.7


COIL WOUND HERE AND ATTACHED TO THE BRIDLES
ALL DIMENSIONS IN INCHES
WINDINGS ARE CLOSE SPACE COPPER WITH 600 VOLT INSULATION.
2
1
1
1
END OF COIL SOLDER TO BRIDLE
BRIDLE WIRE
OVERALL LENGTH OF THE COIL FORM WILL DEPEND ON TOTAL NUMBER OF TURNS
ATTACH AND SOLDER ANTENNA ELEMENTS
http://www.qsl.net/va3iul

---

92 - V-Beam Antenna for 15m


DIRECTIONS OF MAXIMUM RADIATION (BIDIRECTIONAL 6-7 dB OVER DIPOLE)
GAIN FIGURE IS CONSERVATIVE - SEE TEXT
TO SUPPORT
TO SUPPORT
5/8in. NYLON ROPE (STRETCH TAUT)
4 in. INSULATOR (8 REQ'D)
104 ft. 9 in.
PATTERN OF MAJOR LOBES (BIDIRECTIONAL)
L4 2λ (720°) 91 ft. 4 in.
L3 2λ (720°) 91 ft. 4 in.
BISECTOR LINE
HEIGHT ABOVE GROUND = 23 FEET OR HIGHER
APEX 70° ANGLE
35° TILT ANGLE
55°
55°
TO SUPPORT
TO SUPPORT
1/4 in. NYLON ROPE
1/4 in. NYLON ROPE
PULLEY (5 REQ'D)
L1 1/2λ (180°)
L2 1/2λ (180°)
5 ft. 6 in.
L5 22 ft.
L6
5 ft. 6 in.
PULL OPEN-WIRE LINE TAUT
5 ft. 6 in.
4 in.
5 ft. 6 in.
GAIN - VEE BEAM = APPROX. 4.5 dB
GAIN - COLLINEAR - APPROX. 2.8 dB
GAIN - ANT. #1 + ANT. #2 = APPROX. 6-7 dB
TEST POINT "A"
4:1
L1
C1
LEADS NOT OVER 4 in.
WEATHERPROOF ENCLOSURE
1/4 in. NYLON ROPE
http://www.qsl.net/va3iul

---

93 - Picnic Vertical Wire Antenna



3.5 MHz	63 to 66 feet
7 MHz	32-1/2 to 33 feet
10 MHz	21 to 22-1/2 feet
14 MHz	16 to 17 feet
21 MHz	11 to 12 feet
28 MHz	8 to 8-1/2 feet

http://www.qsl.net/va3iul
33 ft.
33 ft.
END OF WIRE
NYLON STRING
POLE
PICNIC TABLE WITH RIG AND ANTENNA TUNER
PICNIC TABLE WITH RIG AND ANTENNA TUNER
POLE
STAKE

94 - Laid-Back Quad Antenna for 80m



http://www.qsl.net/va3iul
60ft. (1/4 λ)
DRIVEN ELEMENT
60ft. (1/4λ)
50Ω COAX TO TRANSMITTER
60 ft. ABOVE GROUND
62ft. (1/4 λ+)
REFLECTOR
62ft. (1/4λ+)
20ft
TV TWINLEAD
SHORTING PIN
7ft. ABOVE GROUND

95 - Phased Loop Antenna



λ/4
Wire or Rope
λ/4
λ/4
λ/4
λ/4
λ/4
λ/4
λ/4
Wire or Rope
λ/8
A
B
λ/8
λ/8
A1
B1
λ/8
B
B1
A
A1
1:1 Balun
300 Ohm Ribbon or 450 Ohm Ladder Line
50 Ohm Coax To Shack
http://www.qsl.net/va3iul
Max gain: 11.095 dBi @ 18.1 MHz

	λ/4	λ/8	300Ω Ribbon	450Ω Ladderline
40m	34.9 ft.	17.5 ft.	53.3 ft.	62.2 ft.
20m	17.6 ft.	8.8 ft.	27.0 ft.	31.2 ft.
17m	13.9 ft.	6.9 ft.	21.2 ft.	25.2 ft
15m	11.8 ft.	5.9 ft.	18.1 ft.	21.97 ft.
10m	8.67 ft.	4.33 ft.	13.2 ft.	15.33 ft.

96 - Loop Antenna for TX for 160m


Loop L1
C2
150
C1
150
Loading/Matching Coil L2
30 Turns
Lo-Z To Tx/Rx
36"
36"
6 Turn Loop
(L1)
5-1/4"
Coaxial Socket
Tuning/Matching Unit
Wood Base
http://www.qsl.net/va3iul
36"
1-1/4"
Corner Blocks
(Glue)
36"
3/8" Wood
Nylon Bolts
Thru Frame
And Box
Loop
Turns
1/2"
End Of Loop
Wire Turn

---

97 - Morgain-Dipole Antenna for 160m and 80m


http://www.qsl.net/va3iul
18,80m
90
18,80m
45
45
Kurzschlussbügel
300
300
Endstück (2x)
Koaxialkabel 50Ω
300
…
400
45
45
Ø28…30
Mittelstück 2…4 dick
110
90
110
alle Maße in mm,
außer Längen der
Dipoläste
Distanzstück
110
45
45
Drähte mit
Heißkleber
fixieren
Ø16

---

98 - ZL-Special for 20m, 15m, 10m


R
20cm
A
FEED POINT
X
X
S



	S	R	A	A
28 Mc/s	5·09m	5·39m	1·29m	$\frac{1}{8}\lambda$
	4·17m	4·42m	1·06m	$\frac{1}{10}\lambda$
21 Mc/s	6·85m	7·24m	1·72m	$\frac{1}{8}\lambda$
	5·62m	5·94m	1·41m	$\frac{1}{10}\lambda$
14 Mc/s	10·30m	10·85m	2·58m	$\frac{1}{8}\lambda$
	8·45m	8·90m	2·12m	$\frac{1}{10}\lambda$

http://www.qsl.net/va3iul

---

99 - Biconical Antenna


http://www.qsl.net/va3iul
S
T
H
W
D
SPACE
METAL ARMS
HEXAGONAL
SPREADER
FORMED BY
METAL ARMS

	H	W	D	T	S	SPACE	WIRE
3·5 – 15 Mc/s	43'	17'-8"	16'-10"	2'-2"	5'-10"	3"	NR 8
7 - 28 Mc/s	23'	9'-6"	9'	12"	3'-2"	2"	NR 10
14 - 56 Mc/s	12'	5'	4'-9"	8"	1'-8"	1"	NR 12

100 - Directive Delta-Birdcage Antenna for 20m to 10m


(a)
Stub
50Ω feeder
Reflector
1·03–1·02λ
Radiator
0·96λ
90°
90°
(b)
2·5m
Insulator
4·8m
(c)
Stub
RG8–U
Rotator
http://www.qsl.net/va3iul

101 - Dual Polarization Antenna for 80m and 40m


λ/2
λ/4
400–800Ω
open-wire
H V
http://www.qsl.net/va3iul

102 - Directive 300-ohm-Ribbon Folded Dipole for 15m


+3dB
* 1/4" approx gap
50 ohm coaxial feeder
14ft of 300 ohm ribbon, folded dipole, resonates at 30MHz
* When cut as shown, resonates at 21MHz
1/16" gap
4 x 6ft dowel spreaders
21MHz
-12 to 18dB
* 1/4" approx gap
http://www.qsl.net/va3iul

---

103 - Miniature Directive Antenna for 10m


4 x 4ft long wooden dowels
Y
50Ω coaxial cable feeder
Phase-shift and voltage-drive to resonant reflector via insulator
Small insulator with gap of approx 3/16"
Light 7-strand plastic covered wire
Z
http://www.qsl.net/va3iul

---

104 - Biquad Antenna 12dBi-Gain for 2.4GHz


http://www.qsl.net/va3iul
30.5mm
30.5mm



---

105 - Dual-Rhomboid Antenna for 435MHz to 870MHz


http://www.qsl.net/va3iul
3/16" POLYPROPYLENE CORD, 21'
3'
FEEDLINE
MAST
INSULATE CROSS-OVERS (3 PLACES)
E
C
BALANCED FEED POINT
TOP VIEW
G
R1
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20
FEET
A
I
≈ BALANCE POINT
J
B
R2
H
WOODEN CROSS SUPPORT (3 PLACES)
D
F

Dual rhomboid antenna for 435-870 MHz. Beamwidth ≈ 10° H x 6° V. Gain over DP ≈ 26 dB. Boom length: AB = 19’6”. Support spacing : AI = 7’; IJ = 5’6”; JB = 7’. Support length: CD = 7’3”; EF = 10’3”; GH = 3’0”. Rhomboid sides: AC, AD, EG, FH = 7’9.5”; AE, AF, CH, DG = 13’5.5”. Feedline: Wire needed: 14 AWG formvar, ≈ 86’0”. Boom material: AI, JB = wood; IJ = metal. Cross support: CD, EF, GH = wood. Terminators: R1, R2 = 600 Ohms; Watts

---

106 - Double-Bazooka Antenna for 80m


http://www.qsl.net/va3iul
END SECTION
ELECTRICAL NEUTRAL POINT
Antenna Length = 468 / Frequency in MHz
124.8'
λ/4 STUB
A
B
43.3' EACH STUB
SHIELD
INNER CONDUCTOR
SHIELD AND INNER CONDUCTOR SHORTED TOGETHER AT THIS POINT FOR BOTH STUBS
CO-AXIAL FEED LINE TO TRANSMITTER
Stub length = (246) (Velocity factor of coaxial cable) / Frequency in MHz

---

107 - J-Style Antenna


http://www.qsl.net/va3iul
CAN BE TACKED IN PLACE
CUT-AWAY PORTION OF TWINLEAD
λ/2 SECTION
in.=5540/fMHz*
300Ω TWIN-LEAD (CAN ALSO BE OPEN-WIRE LINE, BUT λ/4 SECTION WOULD THEN BE APPROXIMATELY A TRUE "FREE-SPACE" QUARTER-WAVELENGTH DUE TO VELOCITY FACTOR).
λ/4 SECTION
in.=2400/fMHz*
MAY BE GROUNDED FOR LIGHTNING PROTECTION IF INSTALLED OUTDOORS
50Ω COAX TO TRANSCEIVER OR TRANSMITTER – KEEP SHORT
RG-8/U OR RG-58/U

108 - Vertical / Horizontal / Circular Polarization Antenna


1/4λ
1λ LOOP
1λ LOOP
A' = 1/4λ-75Ω
B' = 1/4λ-75Ω
A = 1/4λ-75Ω
B = 1/4λ-75Ω
H
V
RL1
H
V
RL2
1/4λ
C
H-V
RL3
VERY SHORT LENGTH
RELAY BOX ENCLOSURE
TO RECEIVER/ TRANSMITTER
http://www.qsl.net/va3iul
RL1
RL2
RL3
VERT.
RELAY VOLTAGE
HORIZ.
R.H.
SP4T
L.H.

	RL1	RL2	RL3
Vertical polarization	On	On	Off
Horizontal polarization	Off	Off	Off
Right-hand circular	Off	On	On
Left-hand circular	On	Off	On

109 - Coax Inverted-L Antenna for 80m


3'
63'
NO 14 WIRE
http://www.qsl.net/va3iul
FEED LINE
CENTER CONDUCTOR
BRAID
63'
RADIALS


MAST OR TREE
NYLON ROPE & INSULATOR
ANTENNA
GROUND ROD

110 - Indoor Compact Loop Antenna for 80m


B
LOOP
A=B=C (14'0" EACH)
(HORIZONTAL)
A
C
HORIZONTAL
VERTICAL
(DROP DOWN)
3" DROP DOWN (90°)
PL1
PL2
SK1
SK2
C1
C2
C3
C4
C5
ATU
C1=150pF HV CERAMIC
C2,C5=33pF 750V
C3+C4=210+210pF VARIABLE
CAPACITOR WITH INTEGRAL
3:1 REDUCTION DRIVE
RG-58 TO T/R
http://www.qsl.net/va3iul
LARGE WINDOW
NYLON FISHING LINE
PL2
PL1
60°
60°
60°
WALL
WALL
N
W
E
S
14'0" (A=B=C)
DOOR
WALL
CEILING 8'0" HIGH
CORNER OF ROOM
BOX
LOOP WIRE ABOUT 9" BELOW CEILING
REMOTE TUNING SHAFT WITH KNOB
SHELF
SHELF
SHELF
NOTE: SHELVES USED FOR EQUIPMENT AND BOOKS (NOT SHOWN)
TX/RX
DESK
B)
FLOOR LEVEL

111 - Helix Antenna


g
A
d
b
L
HELIX AXIS
D
a
COAXIAL LINE
S
G
GROUND PLANE
SURFACE OF IMAGINARY CYLINDER

D = Diameter of the helix
S = Spacing between turns
α = Pitch angle = Arctan $\left(\frac{S}{\pi D}\right)$
L = Length of 1 turn
n = Number of turns
A = Axial length = nS
d = Diameter of conductor
g = Distance of ground plane to first turn
G = Ground plane diameter

$$L = \sqrt{(\pi D)^2 + S^2}$$

$D = 0.32\lambda$
$S = 0.22\lambda$
$G \geqslant 0.80\lambda$
$g = \frac{S}{2} = 0.12\lambda$



$$\beta = \frac{52}{C_\lambda \sqrt{nS_\lambda}} \text{ degrees}$$



Half-power beamwidth of axial mode

http://www.qsl.net/va3iul

---

112 - Novice Vertical Antenna for 80m, 40m, 15m, 10m


http://www.qsl.net/va3iul
TV ANTENNA
PULLEY
NYLON ROPE
ANTENNAS
INSULATOR
COAX
8 FT. GROUND ROD
BRAID
CLAMP
RADIALS
FIG.1A
INSULATORS
37 FT. TOWER
7.125 MHz
21.375 MHz
34 FT. 6 IN.
32 FT.
3.725 MHz
34 FT.
26.075 MHz
WOOD FENCE
INSULATOR
SHACK WINDOW
COAX
22 FT.

---

113 - Stub-Loaded Shortened Dipole for 80m


LIGHTNING SPIKE
IF METAL MAST
OR TOWER
PULLEY AND
HALYARD
17'
INSULATOR
AT LEAST 70'
POLE, TREE
OR MAST
17'
68'
72Ω TWINLEAD FEEDER
OR 1:1 BALUN AND COAX
17'
LOADING STUB
300Ω TV LINE
26.5' FOR 3.8MHz
SEE FIG. 1B
17'
TO 1:1
BALUN
AT LEAST 10'
CLEARANCE
DUE TO HV RF
60° OR
MORE
≈40'


http://www.qsl.net/va3iul
17'
17'
17'
17'
STUB CUTTING
CHART – APPROXIMATE
STUB LOADER
300Ω TV
LINE
72Ω FEEDER
26.5'
FOR 3.8MHz
LOADING STUB
CONNECT
AND SOLDER

f-MHz	FEET
3.5	30
3.6	29
3.7	28
3.8	26.5
3.9	25
4.0	24

114 - Six-Band Wire-Stub Trap Antenna for 40m-10m


33.42 ft.
25.9 ft.
22.28 ft.
18.8 ft.
16.71 ft.
33.42 ft.
25.9 ft.
22.28 ft.
18.8 ft.
16.71 ft.
E
D
C
B
A
A
B
C
D
E
STUBS
FEED
POINT
STUBS

Point	Length (feet)
A	8.37
B	9.40
C	11.14
D	12.95
E	16.72

40m
20m
17m
15m
12m
10m

http://www.qsl.net/va3iul

115 - Multiband Half-Wave Delta-Loop Antenna


http://www.qsl.net/va3iul
41'
300 Ohm Twin Lead
Loop
35'4"
To Balun
And Tuner

116 - Hybrid Vee for 20m, 17m


BAND VERTICAL DIAGONAL
20M 14.5' 16.5'
17M 12.9' 11.0'
3/4" PVC FEED POINT
12 AWG WIRE
12 AWG WIRE
TV RABBIT EAR ELEMENT (NOT USED IN 17M VERSION)
1 1/4" METAL FENCE RAIL OR PIPE
TV RABBIT EAR MAIN TRIMMER
3/4" PVC
1" PVC PIPE 10 FT. SECTION
RG-58 FEED LINE
3/4" PVC TEE
3" HOSE CLAMP
2" x 2" WOODEN CROSS ARM
ROTATOR
2" METAL FENCE POST 6 OR 8 FT.
http://www.qsl.net/va3iul

117 - Six-Shooter Array Antenna, Gain=7.5dB


λ/2
λ/2
λ/2
λ/2
1:6 BALUN
50 OHM COAX
http://www.qsl.net/va3iul

118 - Multiband Ground-Plane Antenna for 10m, 15m, 20m


http://www.qsl.net/va3iul
102"
CB WHIP
16'-6"
TOTAL
86"
1/2" PIPE
DIELECTRIC
PIPE UNION
12"
1" PIPE
17'
NO. 10 WIRE
45°
1 1/4" PIPE ANY LENGTH
FOR DESIRED HEIGHT
LENGTH OF ELEMENTS NOT CRITICAL.
FEED WITH 450 OHM OPEN WIRE FOR
USE ON 10, 15, 20 METERS.

119 - Wire Superbeam Antenna for 10m, 15m, 20m


WRAP WITH STRIPS
CUT FROM OLD TIRE
INNER TUBE & TAPE
TO MAKE TIGHT FIT
WITH U-BOLT (TO
PREVENT CRUSHING
POLE)
2 U-BOLTS
BAMBOO ARM
MOUNTING PLATE
(SIDE VIEW)
DETAIL I - HOW TO MOUNT
BAMBOO SUPPORT ARMS
http://www.qsl.net/va3iul
EXCESS WIRE
DROOPS OVER FRAME
20M REFLECTOR
ALL ELEMENTS
NO. 14 COPPER
WIRE
15M REFLECTOR
10M REFLECTOR
U-BOLTS
10 EACH
MOUNTING PLATE
16 in. X 17 in. MIN
1/4 in. ALUMINUM OR
THICK PIECE EXTERIOR
TYPE PLYWOOD
15 ft. 7 in. (SPACING
BETWEEN 20M
ELEMENTS)
4 EACH BAMBOO POLES
13 ft. LONG MIN
10M DRIVEN
15M DRIVEN
CENTER
INSULATOR
20M DRIVEN
5TH ARM
SUPPORT FOR FEEDLINE - BAMBOO POLE

		START WITH	
BAND	SPACING	DRIVEN	REFL
10M	7'7"	16'10"	17'9"
15M	10'3"	22'6"	23'9"
20M	15'7"	33'10"	35'6"

DIMENSIONS CHART

120 - Two Elements Delta-Loop Antenna


http://www.qsl.net/va3iul
CLAMP PLATES (2) BOLT TOGETHER
60°
4 IN.
1/2 IN. DIA AL. GAMMA ROD
MOUNTING PLATE 1/4 IN. AL. PLATE 2 1/2 IN. X 10
INSULATOR STANDOFF (SCRAP)
U-BOLT ELEMENTS TO PLATE AND BOOM
BRAID TO BOOM
140pF CAPACITOR TUNABLE (MOUNT IN WEATHER PROOF BOX)
RG-8 OR RG-58 COAX
DRIVEN ELEMENT DETAIL
10 FT.-0 IN.
1 3/4 IN. DIA. AL. TUBING
MOUNTING PLATE 4 IN. X 6 IN. X 1/4 IN. U-BOLT TO BOOM AND TO ANTENNA MAST
SIDE VIEW
Reflector total length = 1030 / f(MHz)
Driven total length = 1005 / f(MHz)
Element spacing = λ / 0.17 to λ / 0.20
NO. 12 COPPER WIRE
3/4 IN. AL. TUBING
16.1 FT. EACH SIDE
3/4 IN. AL. TUBING 36 GAMMA ROD
DRIVEN ELEMENT
NO. 12 COPPER WIRE
3/4 IN. AL. TUBING
15.7 FT. EACH SIDE
REFLECTOR

121 - Sterba Curtain Antenna


L/2
L
L/2
TRANSPOSED
L
FEED POINT
300 OHMS
L = 491/f
L IN FEET
f IN MHz
http://www.qsl.net/va3iul
Gain=6dB
DESIGN FREQUENCY MHz
14.300
29.600
LENGTH "L" FEET
34' - 4"
16' - 7"

122 - Half-Wave Vertical Zepp Antenna


http://www.qsl.net/va3iul
ENTIRE VERTICAL PORTION RADIATES
1/2 WAVE VERTICAL RADIATOR
MATCHING POINT
1/4 WAVELENGTH OPEN WIRE
TO XMTR
FEED POINT
BASE INSULATOR
GND
PLASTIC SUPPORT RODS
SHORTED END

123 - Lazy-Loop Antenna for 40m


1005/f(MHz) = total wire length in feet
DIRECTION OF RADIATION
NYLON SUPPORT CORDS TO POLES OR TREES AT EACH CORNER
B
#14 WIRE LOOP
INSULATOR
A
CENTER CONDUCTOR
http://www.qsl.net/va3iul
SHIELD
APPROX. 10 ft.*
COAX CONNECTORS
1/4λ 75-OHM COAX IMPEDANCE TRANSFORMER
TO SHACK
X
50-OHM COAX
246vf/f(MHz) = coax length feet
vf is the coax velocity

124 - Terminated Folded Dipole for 80m, 40m


INSULATOR (7)
http://www.qsl.net/va3iul
1/2 in. DOWEL ROD (ONE EACH END)
1/4 in. DOWEL RODS (EVENLY SPACED ALONG LENGTH OF ANTENNA TO MAINTAIN SEPARATION) DRILL HOLES TO ACCEPT ANTENNA WIRE
46 ft. 10 in.
40-meter version
390 OHM RESISTOR PACK
47 ft.
390Ω
32 ft.
18 in.
46 ft. 10 in.
300Ω TWIN LEAD TO TRANSMITTER
300 OHM TWIN LEAD
2 ft. 10 in.
6 ft.
40 ft.
80-meter version

125 - Short-Fat Antenna for 15m


3 in. DIA. PVC
22 TURNS
1 1/4 in. TUBING
22 TURNS
BOLT
6 in.
6 in.
6 in.
-
+
2 in.
3 in.
18 in.
36 in.
18 in.
18 in.
1 in. PVC
4 in. × 6 in. PLEXIGLASS
COAX
CUT 2 in. SLOT IN 2 in. PVC
CUT 3 in. SLOT IN 1 1/4 in. TUBING
http://www.qsl.net/va3iul

126 - Cobra Antenna for 80m


http://www.qsl.net/va3iul
70 feet
70 feet
WHITE
BLACK
BARE
75-120 Feet
Adjust as needed
for
Low S.W.R
To Tuner
Small Plexiglas plate,
cut and drilled
450 Ohm Ladder Line

127 - Log-Periodic Wire Antenna for 20m, 15m, 10m


3/16 in. NYLON
EGG INSULATORS
MAST A
36 ft.
20 ft.
MAST B
9.5 ft.
32.75
1/2 λ AT 20
8.6
30.0
1/8 in. NYLON
7.9
27.5
7.25
25.0
80 ft.
6.6
23.0
1/2 λ AT 15
6.0
21.0
5.5
19.5
MONOFILAMENT CAN BE USED FOR END INSULATORS IN PLACE OF LUCITE
5.1
17.75
4.9
16.0
1/2 λ AT 10
4.2
14.7
3.9
13.4
3.5
12.25
3.2
11.0
2.9
10.0
WIRE FOR ELEMENTS 311 ft.
+ 30
341
+CENTER FEED 160
TOTAL AL WIRE 501 ft.
6 EGG INSULATORS
13 LUCITE CENTER INSULATORS
4 MASTS (OR TREES)
1 SPOOL MONOFILAMENT (40 LB TEST) LINE
65 ft. 3/16 in. NYLON
175 ft. 1/8 in. NYLON
MAST C
NYLON
FEED
10 ft.
MAST D
BEAM
THIS SHOULD GIVE ABOUT 11 TO 12 dB GAIN
http://www.qsl.net/va3iul

128 - 5-Element Log-Periodic Vertical Antenna for 80m, 40m, 20m


MAST
1/4 in. NYLON CATENARY
BEAM
POLE
GROUND RADIALS
INSULATORS
http://www.qsl.net/va3iul
5-ELEMENT VERTICAL MONOPOLE LOG PERIODIC
S-1
S-2
S-3
S-4
L-1 VERTICAL ELEMENTS
L-2 (1/4 λ)
L-3
L-4
L-5
BEAM
1 1/2"-6" FEEDER SPACING
L-1
L-2
L-3
L-4
L-5
4:1 BALUN
COAX
NOT OVER 6 in.
1/4 λ FEED
BOOM LENGTH

MHz BAND –	NOTE 1 3.5-4.0	NOTE 2 3.8-4.0	NOTE 2 7.0-7.3	NOTE 1 14.0-14.
L-1 =	70'	65'	35'	17.5'
L-2 =	67	62	33	16.5
L-3 =	53	55	28	14.0
L-4 =	50	45	24.5	12.25
L-5 =	43	40	20	10.0
S-1 =	30'	26'	14'	7.0'
S-2 =	27	24	13	6.5
S-3 =	24	23	12	6.0
S-4 =	19	18	9	4.5
TOTAL LENGTH	100'	91'	48'	24'
MAST HEIGHT	80	75	50	30
POLE HEIGHT	45	40	25	20

NOTE 1 - ESTIMATED (NOT TESTED)

NOTE 2 - CONSTRUCTED & TESTED. SWR LESS THAN 1.5:1 OVER FREQUENCY SPECIFIED

---

129 - 2m Vertical Wire Antennas


18 1/2 in.
SO-239
19 1/2 in.
4 RADIALS

Simple 1/4λ 2-meter ground-plane antenna.

http://www.qsl.net/va3iul


44 in.
1 in. DOWEL
2 1/2 TURNS TAP AT 1 1/4 TURNS
3 1/2 in.
ARCO 404 TRIMMER CAPACITOR
4 RADIALS
19 1/2 in.

Experimental 5/8λ vertical with 1/4λ ground plane.

---

130 - Earth-Mover Inverted-V Antenna for 40m


http://www.qsl.net/va3iul
B
60'
DRIVEN DIPOLE ELEMENT
32' 6"
34'
PARASITIC REFLECTOR
A
34'
26'
90' COAX TO TRANSMITTER
INSET AT STATION END OF "A" LINE
SWITCH OPEN NO REFLECTOR 1/2 WAVE HEIGHT
SWITCH CLOSED REFLECTOR ACTIVE 1/4 WAVE HEIGHT

131 - Coax-Cable Collinear Antennas


1/4 WAVE ELEMENT WHIP
TOP IS SHORTED
1/4 WAVE ELEMENT
1/2 WAVE ELEMENT
1/2 WAVE ELEMENT
1/4 WAVE ELEMENT
JOHANSON TRIMMER
1/4 WAVE STUB
FEED LINE
TYPE N CONNECTOR
0°
90°
180°
270°
1 dB
3 dB
6 dB
10 dB
0°
90°
180°
270°
1 dB
3 dB
6 dB
10 dB
http://www.qsl.net/va3iul

8 elements = 6 dB. 16 elements = 9 dB

132 - Double Bobtail Antenna for 20m


C
17 ft.
A
17 ft.
D
#14 INSULATED COPPER
2 in.
ALUMINUM
TUBING
LADDER
LINE
16 ft. 6in.
17 ft.
16 ft. 6in.
L
6 TURNS
#12 WIRE
E
B
SPST SWITCH
F
C
150 pF
RG8
TUNED TO 14.2 MHz
http://www.qsl.net/va3iul
#1
SWITCH B OPEN (CLOSES A)
HALF WAVE SPACING
NO DELAY
#2
SWITCH B CLOSED (OPENS A)
HALF WAVE SPACING
HALF WAVE DELAY
#3
FULL WAVE SPACING
NO DELAY

133 - Collinear Zepp Antenna


180°
L3
180°
OR
230°
L1
180°
OR
230°
L2
180°
L4
S1
S2
300Ω LINE
300Ω LINE
PHASING
CAPACITOR
PHASING
CAPACITOR
L1-L2 = 180° - 468/f WHERE f = MHz
L1-L2 = 230° - 600/f WHERE f = MHz
S1-S2 = 246 × 0.82/f WHERE f = MHz
S1-S2 MADE FROM 300Ω TV RIBBON.
MAKE ABOUT 6inches LONGER THAN
CALCULATED VALUES. TRIM IF NECESSARY.
http://www.qsl.net/va3iul

134 - Taylor Vee Antenna for 20m


3/4" PVC TEE
FEED POINT
12 AWG WIRE
≅15 FT EACH SIDE
TV RABBIT EAR
ELEMENT
SOLDER WIRE TO ELEMENT
3/4 PVC
CONDUIT
1/4-20 MACHINE BOLT,
LOCK WASHER, FLAT
WASHER AND NUT
THREE LOCATIONS
1" PVC CONDUIT
10 FT SECTION EACH
SIDE
3/4" PVC TEE
3" HOSE CLAMPS
FOUR TYPICAL
1" U-BOLT
2" x 2" WOODEN
SUPPORT - 10 FT
MAST 1" EMT CONDUIT
TO ROTATOR
RG-58
http://www.qsl.net/va3iul

135 - Collinear Vertical Antenna 6dB-Gain for 2m, 1.3m, 73cm


TERMINAL RADIATOR
A
B
C
SOLDER
SOLDER
SOLDER
SOLDER
SOLDER TO BRAID
C
B
A
http://www.qsl.net/va3iul

DIMENSIONS inch

MHz	A	B	C
147	19''	13.3''	26.6''
220	12.66'	8.88''	17.75''
440	6.33''	4.44''	8.875''

---

136 - Bi-Loop Antenna for 20m


4'
NYLON ROPE
26' 2"
4'
NYLON ROPE
18'3"
18'3"
18'3"
18'3"
NYLON ROPE
INSULATORS
POLE
POLE
18'3"
18'3"
18'3"
18'3"
COAX
1 LB WEIGHTS
EARTH
WIRE
SOLDER LOOP WIRE
COAX
1/4" BAKELITE OR PLASTIC
WIRE WOUND TIGHT AROUND LOOP WIRE TO KEEP INSULATOR FROM SLIDING SIDEWAYS
INSULATOR
ROPE
http://www.qsl.net/va3iul

---

137 - Wire Beam 6dBd-Gain for 10m


DIRECTOR
43"
ARM
NYLON STRING
JUMPER WIRE
2×4 X-MOUNT
TAPE TAILS TO THE SUPPORT STRING
BALUN
FEEDLINE
1/2" DIA. CONDUIT 6'8" LONG
TAIL
49"
DRIVEN ELEMENT


http://www.qsl.net/va3iul
OUTPUT 12.5Ω BALANCED
ANY LENGTH FROM HERE
INPUT 50Ω UNBALANCED
DUMMY COAX
GROUND

138 - Sloping Diamond Antenna 4dB-Gain for 40m


35-1/2'
35-1/2'
31-1/2'
63-1/2'
35-1/2'
35-1/2'
X Y
Dimensions in Feet
- 1 dB Loss
3 - 4 dB Gain
http://www.qsl.net/va3iul

139 - Twisted Loop Antenna for 160m


1/2 Turn Twist
Open Capacitive Stub LC = 48" @ 1.8 MHz
Loop LL = 51' 6"
http://www.qsl.net/va3iul
300 Ohm Line To Balun & Tuner; Any Length
Shorted Stub LZ= 16' 11"
Dimensions in Feet

140 - DX RX Loop Antenna for 160m


L1 = 11 Turn Loop
Approx. 30" Diameter
Box
C1, C2 = 150 pF
C3, C4 = Dual 500 pF Variable
C5 = 470 pF
Skt 1 = 50 Ohm to Rcvr
Skt 2 = Optional Ground Socket
C5
C1
C2
C3
C4
Skt 1
Skt 2


11 Complete Turns Taken Counter-Clockwise Through 2 Amp Terminal Blocks
Ends of Loop Taken Through Grommet
Exit Grommet for RG58
http://www.qsl.net/va3iul

141 - Hentenna 3dB-Gain for 10m, 6m, 2m


1/6 wave
1/2 wave
F
F= 1/2 wave / 4.28
35 degrees
Vertical Half power Diagram
40 degrees
null
40 degrees
Horizontal Half Power Diagram
80 degrees
null
80 degrees
http://www.qsl.net/va3iul

Band	1/2 wave	1/6 wave	Feed point
10m	16' 6"	5' 6"	3' 10-1/4"
6m	8' 10"	2' 11-1/4"	2' 1/16 "
2m	3' 3"	1' 1"	9' 1/8"

Dimensions in Feet

142 - VK2AAR Wire Antenna for 20m


18'-4"
18'-4"
18'-4"
NYLON CORD
APPROX. 15° OUT OF SQUARE
NYLON CORD
9'-2"
9'-2"
75Ω CO-AX
http://www.qsl.net/va3iul

143 - 2-Elements Quad Antenna for 6m


DRIVEN ELEMENT LOOP
http://www.qsl.net/va3iul
FORWARD LOBE
FISHING LINE SUPPORT
LOADING WIRE ALONG SPREADER (EACH END)
REFLECTOR LOOP
FEED POINT FOR VERTICAL POLARIZATION
3/4" PVC CROSS COUPLING
BOOM
CAPACITOR MOUNTED INSIDE EACH END
LOADING WIRE
30 3/4" (EACH SIDE)
LOOP
C2 1-10pF
REFLECTOR SCHEMATIC
TAPE COAX TO MAST AND BOOM
MAST
30" (EACH SIDE)
THIS END OF SLEEVE OPEN
C1 1-10pF
RG-58 RECEIVER
CONNECT SLEEVE ONLY AT THIS POINT
37 1/2"
DRIVEN ELEMENT SCHEMATIC

144 - Hula-Loop Bidirectional 6dB-Gain Antenna for 17m


Nylon
Support
Lines
Diflector Element
(Outer)19' 1/2" Each Side
(Inner) 17' 11" Each Side
Driven Element
18'6" Each Side
Space
Between
Corners Is
7-13/16"
27' Above
Ground
1:1
Balun
8'8"
All Wire
#12 Stranded Copper
PVC Covered
λ
4
75 Ohm
Coax
50 Ohm
Coax

http://www.qsl.net/va3iul

145 - Moxon Rectangle Beam for 15m-10m


A
Driven element
feedpoint
B
C
Insulators
Coax cable
Insulators
E
Detail of
insulators
D

A = 98.26/f = (m); 322/f = (ft)
E = 53.96/f = (m); 177/f = (ft)

56.09/f = length of diagonal in metres
184/f = diagonal length in ft.

C = 560mm (22in) for 14MHz, 380mm (15in) for 21MHz and 250mm (10in) for 28MHz

http://www.qsl.net/va3iul

146 - Double-D Beam 4dB-Gain


Top view
Driven element
Reflector
D
A
E
E
A
C
C
Mast
Bamboo or glassfibre supports
B
Side view
Design data, (length in metres)
A & B = 79·00/f (MHz)
C = 55·89/f (MHz)
D = 16·41/f (MHz)
E = 31·41/f (MHz)
Total element length = 1417·83/f (MHz)
http://www.qsl.net/va3iul
Driven element
Reflector
Insulator
Nylon cord
E
A
Coaxial cable feeder
C
E
B

147 - KE4PT OCEF All-Band Dipole


KE4PT OCEF All-band Dipole
http://www.qsl.net/va3iul
Egg insulator
11.5 ft (3.5m) coax cable
connector, to antenna tuner
30 ft (9.1m) dipole leg (#20 or 22 stranded Teflon covered wire, extends from coax cable center conductor)
feed-point
ferrite current chokes

KE4PT Off center end fed (OCEF) All-band Dipole

Lengths are not critical, as long as they are not near a half wavelength on any frequency used.
Dipole radiating length is 30+11.5=41.5 ft, or 12.6 m.
Coax cable may be 50 or 75 ohm on left side of connector, short 50 ohm coax to antenna tuner.
Use antenna tuner for operation on any ham band 40m – 6m.
May be hung by Egg insulator at one end, or draped and drooped over a fiberglass pole.

148 - Wire Quad Antenna for 40m


http://www.qsl.net/va3iul
Boom Support Truss
18' Boom
70' High
Reflector
Driven Element
70' Tower
S0-239 Connectors
Insulated from Tower
10' Separator
Rope
≈ 25' High
Stay Ropes
140'


A
A
B
B
C
C
10'
Separator

	7050 kHz, CW	7200 kHz, SSB
Length A, Reflector	31"6"	30"10-¾"
Length B, Reflector	28"2-¼"	27"7"
Length C, Reflector	15"7-¼"	15"
Total, Half Reflector	75"3-½"	73"5-¾"
Resonant Frequency	7030 kHz	7205 kHz
Length A, Driven	30"7-¼"	30"
Length B, Driven	27"3-½"	26"8-½"
Length C, Driven	14"7-½"	14"
Length, Half Driven	72"6-¼"	70"8-½"
Self-Resonant Frequency	7295 kHz	7480 kHz

149 - Inclined Dipole Antenna for 80m, 40m


http://www.qsl.net/va3iul
1,22 m
L_1 = 10,21m
etwa 6,70 m
Sp1
120 µH
Sp2
L_2 = 1,15 m
120 µH
etwa 1,50 m
Koaxialkabel 60Ω
1,22 m

150 - Pyramidal Wire Antenna for 80m


13,4 m
≥ 12,5 m
B
A
13,4 m
13,4 m
≥ 3,0 m
Jsolatoren
Mastkopf
Jsolatoren
a
b
c
d
X X

a connected to c
b and d = feeding point

http://www.qsl.net/va3iul

---

151 - Random Wire Antenna All Bands


INSULATOR
INSULATOR
VENT PIPE
INSULATED LEAD-IN WIRE
BASEMENT WINDOW
TRANSMATCH
SEWER PIPE
GROUND WIRE
XCVR

---

152 - Multiband Dipole Antenna for 80m, 40m,15m, 10m


15-M RADIATOR
10 M
10 M
40 M
40 M
RG-58/U COAXIAL CABLE
80 M
80 M
ELEMENT LENGTHS
80 M: 109'
40 M: 59'
15 M: 22'
10 M: 17' 6"
mm = INCHES (") x 25.4
m = FEET (') x 0.3048

---

153 - Slim Jim Wire Antenna for 4m


10CM
spreader
Fiber glass Fishing pole
spreader
2.1m
3.224m
spreader
19cm
spreader
1.030m
Approx 125 mm - Adjust for best SWR
spreader



154 - Delta Loop for 6m


Boon 2 metres of plastic conduit
21.5 mm (3/4") pipe clip pop riveted to the boon
Total length of Wire 6.10 metres
Block connectors
99 cm of 75 ohm coax matching section
100 mm of 40 mm white PVC drain pipe
50 ohm coax to TX/RX

155 - Re-Configurable Antenna for 160m and 80m


Marine Grade Pulley
Tree or support pole
27.04m
Insulator
25.92m
Insulator
Marine Grade Pulley
27.04m
Jumper wires with in line connector
Insulator
Nylon Rope
Approx 15m of 450 ohm ladder line
Nylon Rope
Weight
Nylon Fishing line Used to configure as inverted Vee
Nylon Fishing line used to pull down insulator to aid configuration as OCFD
Nylon Fishing line Used to configure as inverted Vee
Balanced / Tee Switching
Auto Tune r
Weight
Ferrite Chokes
RF
Power
Tuned ground planes for 160 & 80m approx 0.6 x ¼ Wavelength stapled to fence at 2m height of 2m spaced 0.5m apart

156 - Very Low Frequency Inverted-L Antenna



f(kc)	X (ohms)	CALCULATED Rrad (ohms)
45	-j 785	0.49
50	690	0.60
60	555	0.85
70	450	1.20
80	375	1.55
90	320	2.00
100	268	2.40
120	188	3.6
140	125	5.2
160	75	7.2
180	30	9.9
195	0	12.8


158'
CONDUCTORS
5/8" DIA
600'
460'
600'
50'
170'
170'
475'
30'
(3-WIRES)
50'
3-500'
GROUNDED;
SELF-SUPPORTING
TOWERS

157 - Reduced Size Half Sloper Antenna for 160m


Coil
Coax balun
(16 turns)
RG-58/U
coax
1/8 λ sloping wire
(68.3 feet)
Insulator
To station
Radials
tower,
Coil
1/8 λ sloping wire
Rope
Coax balun
(16 turns)
Vertical wire
RG-58/U coax
To station
tree
Radials
26"
5 1/8"
5/8"
3/4" PVC Pipe
1/8 λ
Sloping wire
3/8"
90 Turn
Coil
Clamp to
tower leg
RG-58/U
coax

158 - Tree-Mounted HF Antenna


Insulator
$L_{FT} = \frac{234}{f_{MHz}}$
$L = \frac{234}{f_{MHz}}$
$L = \frac{234}{f_{MHz}}$
RG-58
Insulator
Insulator

---

159 - Multiband Vertical Antenna for 80m, 40m, 20m


℄
Symmetrical about ℄
44'
Cross Arm
20.5'
Wire
Trap
Rope *
Insulators (3)
3'
73.5'
Wire
Pulley
Rope *
Mast (Rohn 50)
* Dacron
Cross Arm
2'
Bottom Insulator
Side View
Cross Arm
Insulator
Wire
Rope *
Approx. 39'
Insulator
Wire
Approx. 18'
Cross Arm
20 m
40 m
150 pF
200 pF
Mast
Bottom Insulator
End View
1 - 1/2"
#10 - 24 x 1 - 1/4 inch Screws
500 pF
2500 V
SM
1 - 7/8"
(A)
(B)

---

160 - Marconi Antenna for 136 kHz


Detail of Matching and Loading Coils
Shorting Links for 136 kHz Operation
Matching Coil Mounted in Corner of Shack
to Antenna
Vacuum Capacitor
Antenna Loading Tapping Point
Loading Coil Mounted on Pole
Earth
Connections from Power Amplifier
Spreader
Antenna Wires
Nylon Cord
Insulator
48′
Metal Mast
32′
85′
Loading Coil
Low - Band Shack
48′

---

161 - Simple Killer Antenna for 40m


Insulator
33′
Rope
450 - Ω Ladder Line to Antenna Tuner
Insulators
Elevated Radials 33′ each

---

162 - Stub-Directed V Antenna for 80m


61.45 ft
(all)
5
6
12.5 ft
RG-213
23 ft
Open Stub
K1
10.5 ft
RG-213
Shorted Stub
When K1 is open and K2 is closed, the direction points from wire 4-3 to wire 6-5.
When K1 is closed and K2 is open, the direction points from wire 6-5 to wire 4-3.
53 ft
50 Ω
Feed
1
2
RG-213
80 ft
53 ft
To Shack
To Shack
Control Line
60 ft
3
4
12.5 ft
RG-213
23 ft
K2
10.5 ft
RG-213
Shorted Stub

163 - KT0NY Over-and-Under DX Antenna for 20m


Rope to front-yard tree
Pulley to back-yard tree
Carabiner
13.5 feet
Top wire is 98.5 feet long, fed 13.5 feet from end
28 feet
Support String
28 feet
450 Ohm Feed Line
600 Ohm Feed Line
Down Haul Rope


Insulators
(A)
Insulators
(B)

164 - Horizontal Loop Antennas


L = L1 + L2 + L3 + L4
L2
L3
L1
L4
Height
Ground
L (feet) = 1005 / F (MHz)
L2
L3
L4
L1
Ground

corner of angle-fed (AF) configuration

center-fed (CF) configuration



Loop Performance by Shape and Feed Point

	Circular Loop		Square Loop AF		Triangle Loop AF		Square Loop CF		Triangle Loop CF	
	Gain (dBi)	Elev	Gain (dBi)	Elev	Gain (dBi)	Elev	Gain (dBi)	Elev	Gain (dBi)	Elev
1.9 MHz	3.93	90°	3.46	90°	2.88	90°	3.70	90°	2.67	90°
3.9 MHz	8.47	90°	8.13	90°	7.76	90°	8.23	90°	8.04	90°
7.2 MHz	7.76	50°	7.35	50°	7.98	45°	7.64	45°	7.30	45°
10.1 MHz	8.34	35°	10.68	35°	7.35	30°	8.17	35°	7.24	30°
14.2 MHz	10.44	25°	12.50	25°	11.27	25°	10.25	25°	8.50	25°
18.1 MHz	11.18	20°	14.03	20°	12.32	20°	11.40	20°	8.84	20°
21.2 MHz	10.16	15°	14.55	15°	12.42	15°	11.28	15°	8.29	15°
24.9 MHz	10.77	15°	13.69	15°	14.09	15°	10.58	15°	10.10	15°
28.5 MHz	11.39	15°	12.85	10°	13.84	10°	11.19	10°	12.66	10°

165 - Ribbon J-Pole for 2m


300 Ω Twin Lead
¾ inch
PVC pipe
37-1/4"
Cut Out 1/4" Notch
15-1/4"
1-1/4"
RG-174A Coax
Splice and Short Together

166 - Dual Band Ribbon J-Pole for 2m, 70cm


¾ inch
PVC pipe
4" Nylon Tiewrap
for Hanging
Short Top Side
of RG-174A
Decoupling Stub
18"
Cut Out 1/4"Notches
4-1/4" RG-174A
11-1/2"
Cover these
sections with Heat
Shrink Tubing
Cut Out 1/4" Notch
16-1/4"
1-1/4 "
BNC
Connector
5' of RG-174A Coax
Splice and Short Together

167 - Square Vertical Loop Antenna for 40m


TOWER
FEEDER
ALTERNATE METHOD
44' (13 METERS)
27' (8 METERS)
NO. 16 OR
NO. 14
WIRE
GUYED
PIPE
MAST
7' (2.1 METERS)
50-OHM COAX
75-OHM RG-59/U
1/4 -WAVE
TRANSFORMER

168 - Tri-Band Quad Antenna for 20m, 15m, 10m


20-METER DIRECTOR
15-METER SECOND DIRECTOR
10-METER THIRD DIRECTOR
15-METER FIRST DIRECTOR
10-METER SECOND DIRECTOR
20-15-METER DRIVEN ELEMENT
10-METER FIRST DIRECTOR
10-METER DRIVEN ELE.
20-15-10-METER REFLECTOR
DIRECTION OF MAXIMUM RADIATION
C
G
L
K
F
J
E
B
I
A
D
H
7′0″
7′0″
6′0″
6′0″
¾ MATCHING SECTION OF RG-11/U
FIBER-GLASS SPREADER ARM
ELECTRICAL TAPE
SOLDER IN PLACE
SOLDER IN PLACE
DRIVEN ELEMENT
NYLON STRING

Band	*Reflector*	*Driven Element*	*First Director*	*Second Director*	*Third Director*
20 Meters	(A)72′ 8″	(B) 71′ 3″	(C) 69′ 6″	—	—
15 Meters	(D) 48′ 6½″	(E) 47′ 7½″	(F) 46′ 5″	(G) 46′ 5″	—
10 Meters	(H) 36′ 2½″	(I) 35′ 6″	(J) 34′ 7″	(K) 34′ 7″	(L) 34′ 7″

---

169 - 3D Quad Antenna for 80m, 40m, 20m, 15m, 10m


input power
30 m
90°
90°
21,3 m
15 m
5 m

---

170 - Sloping Wire Antenna for 30m, 20m, 17m, 15m, 12m, 10m


INSULATOR
MAXIMUM RADIATION 10° OFF WIRE AXIS
LENGTH 234-foot SF Wire
40' MAST
INSULATOR
RADIO

171 - Broadband Dipole Antenna with Coaxial Resonator for 80m


TEE
65' CROSSOVER
5.7'
LINK
26.3'
OPEN STUB
33'
OPEN
NO. 14 AWG
RG–8
SHORTED STUB
11.3'
65'
SHORT
53.7'
NO. 14 AWG

172 - Resonant Feedline Dipole Antenna for 80m


T Choke
Coaxial Cable
Coiled on Coil Form
13 Turns, 8" Diam
1/2 λ RG–8 or Mini–8
Coaxial Cable
(approx. 118')
Antenna Wire
(No. 12 Stranded or Copperweld)
to
Station
1/4 λ (approx. 59')
1/4 λ (approx. 59')
Distance Adjusted
for Resonance
(approx. 25")
Center of Dipole
(potted in Epoxy)

Choke Dimensions for RFD Antenna

Freq	*RG-213, RG-8*	*RG-58*
3.5	22 ft, 8 turns	20 ft, 6-8 turns
7	22 ft, 10 turns	15 ft, 6 turns
10	12 ft, 10 turns	10 ft, 7 turns
14	10 ft, 4 turns	8 ft, 8 turns
21	8 ft, 6-8 turns	6 ft, 8 turns
28	6 ft, 6-8 turns	4 ft, 6-8 turns

173 - Dual-Band Loading Wire Antenna for 80m, 30m


L_1
L_2
Feeding point
7.42m
59uH
4.2m
L_H
Zo = 500 ohm

---

174 - Stub Matching Antennas


λ/2 ANTENNA
INSULATORS
λ/4 STUB
NONRESONANT FEEDERS
SHORTING BAR OR LINK
λ/2 ANTENNA
INSULATORS
λ/2 STUB
NONRESONANT FEEDERS
SHORTING BAR OR LINK
λ/2 ANTENNA
FEEDER TAPS NEAR ANTENNA END OF STUB
λ/4 STUB
NONRESONANT FEEDERS
OPEN
λ/2
λ/2
λ/4 STUB
SHORTING BAR
NONRESONANT FEEDERS

---

175 - J-Style Vertical Wire Antenna for 10m


NO. 12 WIRE
INSULATORS
25 FT.
16-1/2 FT.
"TRANS-FORMER"
8 FT.
SHORTING BAR, ABOUT ONE FOOT FROM BOTTOM
3"
50-100 MMF
5 TURNS 2" DIA. SPACED 1 DIA.
ANTENNA MAST SECURED TO ROOF OR SIDE OF HOUSE

176 - Dual Band Vertical with Zepp Feeders for 40m, 20m


33 FT
33 FT
ANY LENGTH FEEDERS
C1
C2
ANT COIL
LINK TO TANK

177 - RCA Double Doublet for 40m to 12m


58'
29'
29'
16'-8"
16'-8"
20'
CROSS OVER
INSULATOR
AS HIGH
AS POSSIBLE
PREFERABLY
OVER 30FT
TRANSMISSION
LINE

178 - RCA Spiderweb Antenna for 40m to 6m


APPROX 37 FT
18"
A
B
G
L
C
D
HANGER
E
F
10'-6"
K
H
LINKS
TRANSFORMER
TRANSMISSION
LINE
INSULATORS

179 - Folded Dipole with Shorted Straps


404
FMC.
Ⓑ
300-OHM RIBBON
30
FMC.
30
FMC.

180 - Twin-Lead Marconi Antenna for 160m, 80m


$\frac{234}{F(MC)}$
300 OHM "RIBBON" LINE
WIRES SHORTED TOGETHER AT END
52 Ω COAXIAL FEED LINE

---

181 - Broadband Antenna Quarter-Wave Balun for 80m


110'
144"
FOR DETAIL SEE FIG. A
THE TWO WIRES MAY BE SPREAD EITHER HORIZONTALLY OR VERTICALLY.
PHENOLIC BLOCK 2"X1.5"X0.5"
WRAP CABLES AND BLOCK WITH SCOTCH ELECTRICAL TAPE.
SPACE BLOCKS 6' APART ALONG BALUN
66'
0.5"
1.5"
1.5"
1.5"
D
C
D
FIGURE A
FIGURE B
KEEP BALUN AT LEAST 6" CLEAR OF GROUND AND OTHER OBJECTS.
FOR DETAIL SEE FIGURE B
52 OHM RG-8/U, ANY LENGTH

FIGURE A

CUT OFF SHIELD AND OUTER JACKET AS SHOWN. ALLOW DIELECTRIC TO EXTEND PART WAY TO OTHER CABLE. COVER ALL EXPOSED SHIELD AND DIELECTRIC ON BOTH CABLES WITH A CONTINUOUS WRAPPING OF SCOTCH ELECTRICAL TAPE TO EXCLUDE MOISTURE.

FIGURE B

REMOVE OUTER JACKET FROM A SHORT LENGTH OF CABLE AS SHOWN HERE. UNBRAID THE SHIELD OF COAX C, CUT OFF THE DIELECTRIC AND INNER CONDUCTOR FLUSH WITH THE OUTER JACKET. DO NOT CUT THE SHIELD. WRAP SHIELD OF COAX C AROUND SHIELD OF COAX D. SOLDER THE CONNECTION, BEING VERY CAREFUL NOT TO DAMAGE THE DIELECTRIC MATERIAL. HOLD CABLE D STRAIGHT WHILE SOLDERING. COVER THE AREA WITH A CONTINUOUS WRAPPING OF SCOTCH ELECTRICAL TAPE. NO CONNECTION TO INNER CONDUCTORS.

DIMENSIONS SHOWN HERE ARE FOR THE 80 METER BAND. THIS ANTENNA MAY BE BUILT FOR OTHER BANDS BY USING DIMENSIONS THAT ARE MULTIPLES OR SUBMULTIPLES OF THE DIMENSIONS SHOWN. BALUN SPACING IS 1.5" ON ALL BANDS.

---

182 - Three-Quarter-Wave Folded Doublet for Dual-Band


0.94 X 3/4 λ OR 693/F MC = L
SW
6" FEEDER SPREADERS
L = 195' FOR 3550 KC. AND 7150 KC.
L = 98' FOR 7100 KC. AND 14250 KC.
L = 49.6' FOR 14200 KC. AND 28 MC.
600 OHM LINE
TO TRANSMITTER

183 - Three-Quarter-Wave Folded Doublet No-Switch for Dual-Band


693/F (MC)
6" FEEDER SPREADERS
600 Ω LINE
L
SHORTED END
600 OHM LINE
TO TRANSMITTER
L = 67 FT. WHEN ANTENNA IS 195 FT.
L = 33 FT. " " " 98 FT.
L = 16.5 FT. " " " 49.6 FT.

184 - Wideband Omni-Directional Discone Antenna


D
S
H
L
R
52 OHM COAXIAL FEED LINE
SWR (STANDING WAVE RATIO)
4.0
3.5
3.0
2.5
2.0
1.5
1
6 10 14 18 22 26 30 34 38 42 46 50 54 58
FREQUENCY (MC)
CUT-OFF FREQUENCY
DIMENSIONS
20, 15, 11, 10, 6 METERS
D=12' L=18'
S=10" R=18'
H=15'7"
15, 11, 10, 6 METERS
D=8' L=12'
S=6" R=12'
H=10'5"
11, 10, 6, 2 METERS
D=6' L=9'6"
S=4" R=9'6"
H=8'3"

---

185 - Wideband Rhombic Antenna for 40m to 10m


6'
315'
315'
TOTAL LENGTH
S
Nº 12 HARD DRAWN COPPER
LINE TO TX
Nº 14 SPACED 6"
SPACING BETWEEN SIDES S,=214 FEET
TOTAL LENGTH =592 FEET
H=50'
TERMINATING LINE
OF 250' OF Nº 26
NICHROME SPACED 6"
AND 800-OHM 16-WATT
CARBON RESISTOR AT
END. 8 2-WATT 100-OHM
RESISTORS IN SERIES

---

186 - Pre-Cut Linear Array Antenna 3dB-Gain for 40m


65'6"
65'6"
65'6"
32'9"
32'9"
MAKE STUBS OF # 14 E.
WIRE, SPACED 4" TO 6"
300Ω RIBBON TO
TRANSMITTER, ANY LENGTH
GAIN APPROX. 3 DB

187 - X-Array Antenna 6dB-Gain for 20m, 15m, 10m


L
D
L
S
P
P
P
P
GAIN APPROX. 6 DB
—75 Ω TRANSMISSION LINE

DIMENSIONS

	10M.	15M.	20M.
L	16'3"	22'	32'10"
S	20'	30'	40'
P	14'2"	21'3"	28'4"
D	3'6"	5'3"	7'0"

The entire array (with the exception of the 75-ohm feed line) is constructed of 300-ohm ribbon line. Be sure phasing lines (P) are poled correctly, as shown.

188 - Double-Bruce Array Antenna 5dB-Gain for 20m, 10m


L
L
L
L
L
600 Ω LINE
GAIN APPROX. 5 DB
ANTENNA TUNER
TRANSMITTER

DIMENSION L

10M.	15M.	20/10 M.
8'9"	13'	17'6"

189 - Bi-Square Broadside Array 4dB-Gain for 20m, 15m, 10m


L
L
L
L
POINTS OF MAXIMUM CURRENT
90°
90°
D
Q SECTION
#14 E. WIRE SPACED 4"
GAIN APPROX. 4 DB
150 Ω LINE TO TRANSMITTER

DIMENSIONS

	10M.	15M.	20M.
L	16'6"	24'9"	33'
D	8'3"	12'5"	16'6"

190 - Six-Shooter Broadside Array 7.5dB-Gain for 20m, 15m, 10m


L
L
L
S = 4"
D
300 Ω RIBBON LINE
GAIN APPROX. 7.5 DB

DIMENSIONS

	10M.	15M.	20M.
L	17'	22'3"	33'8"
D	17'6"	22'9"	34'6"

191 - Triplex Flat-Top Beam 4.5dB-Gain for 20m, 15m, 10m


ROPE
S
3-WIRE DOUBLETS
MAX. RADIATION
4.5 DB
CROSSOVER 300Ω TWIN LEAD
MAXIMUM RADIATION
4.5 DB
D
L
D
SPACING=6"
300 Ω LINE TO TRANSMITTER ANY LENGTH

DIMENSIONS

	10M.	15M.	20M	MATERIAL
L	15'8"	21'5"	32'2"	THREE #12 E. WIRES, SPACED 3"
S	5'6"	7'8"	11'	
D	7'2"	10'7"	14'4"	300 OHM RIBBON

---

192 - Dual-Band Tilt Antenna for 20m, 10m


PULLEY
INS.
INS.
SLEEVE
LIGHT GUY ROPE
INS.
LIGHT GUY ROPE
3/4" DURAL PIPE
33FT LONG
6" STANDOFF INSULATOR
FEEDER
ROPE

TWO BAND (10-20 METER) TILT ANTENNA — VERTICAL FOR 20 METERS - TILT 54° FROM HORIZON FOR 10 METERS

---

193 - Super Space Multiband Dipole Antenna for 80m to 10m


21.50 m
10.75 m
Nylon Roppe, Diameter = 6mm
2 x 20.5m Copper Wire 2mm
RG8/U

194 - Bi-Square Beam Antenna Gain=5.5dB for 10m


Feed at AF = Horizontal Polarization
Feed at E = Vertical Polarization
B
18'
18'
WOOD MAST
1"
3"
ROPE
TYPICAL INSULATOR
PULLEY
C
D
NO CONNECTIONS AT THIS POINT
FEEDLINE CONNECTS TO POINTS A–F VIA MATCHING TRANSFORMER
A
F
PULLEY
18'
18'
SIDE SUPPORT
E
Gain = 5.5dB
GROUND

195 - Cousin of G5RV Multiband Antenna for 40m to 10m


44'2" INSULATED AND STRANDED COPPER WIRE
44'2"
36'8" TWIN LEAD (300 OHM)
RUN TWIN LEAD TO A POINT NEAR TRANSMITTER
A
B
LOAD HERE (SEE TEXT)
7'2" ± 2" OF RG-58/U CABLE WOUND INTO A 3" DIA ROLL AND TAPED IN THREE PLACES
RF CHOKE
INCHES X 25.4 = mm
TRANS-MITTER

196 - Cayman Quad Antenna for 20m


THE ENDS OF THE SKYLINE GO OVER THE CROWNS OF TREES AND DOWN TO EARTH ANCHORS
SKY LINE
THROUGH TREE AND DOWN TO CLEAT
MAST ROPE
PULLEY
TOP SPACER POLE TIED TO MAST ROPE
MAST ROPE GOES THROUGH PULLEY AND IS USED TO RAISE AND LOWER THE ANTENNA
QUAD LOOPS
MIDDLE SPACER POLE
STEERING ROPES TIED TO MIDDLE SPACER POLES
STEERING ROPE
BOTTOM SPACER TIED TO MAST ROPE
MAST ROPE
CORAL ANCHOR
MIDDLE SPACER POLE
ALUMINUM STRAP
COPPER PIPE
END CAP
SPREADER POLE
HOSE CLAMP
WOOD DRILLED FOR SNUG PASSAGE OF COPPER PIPE
WOOD SAME THICKNESS AS SPACER
DRIVEN QUAD LOOP
CLEAR PLEXIGLAS PANEL
SHORT STAND-OFF INSULATORS
PL-259 COAX PLUG
QUARTER-WAVE 75-OHM MATCHING SECTION
SO-239 COAX JACK
RG-11/U COAX
COAX TAPED TO BOTTOM SPACER
HOSE CLAMPS HOLD PANEL IN PLACE
BOTTOM SPACER FITS THROUGH SNUG HOLE IN PLEXIGLAS PANEL

Length of one side of driven radiator: 250/f = 17.86 ft.
Length of one side of closed reflector: 258/f = 18.43 ft.
Spacing between loops: 118/f = 8.43 ft.

197 - Hentenna Gain=3dB with Bazooka Match for 6m


λ/6
λ/2
A
B
MATCHING SECTION
SOLDER AND TAPE
1/2" (10 mm)
1-1/4" (30 mm)
40.6" (1.03 m)

198 - X-Beam Antenna Gain=3dB for 20m


NYLON CORD
DIR.
13' 9" ARMS
6'8"
DIR.
TAIL
6'8"
DIR.
TAIL
NYLON
CORD
NYLON
CORD
D.E.
7'8"
D.E.
TAIL
7'8"
D.E.
TAIL
NYLON CORD
50-Ω
COAXIAL
CABLE

---

199 - Twin Delta Loop Antenna Gain=6dB for 160m, 80m, 40m


GROUND
RADIALS

Twin- Delta Loop, with the image in the ground plane.

Band	*Tower Height (ft)*	*Length of Sloping Wires (ft)*
160 m†	102.03	204.06
80 m	49.86	99.72
40 m	25.92	51.84

---

200 - Inverted-V Beam Antenna for 30m


COAXIAL "T" CONNECTORS
1/4 λ RG-59/U
(B)
75-Ω COAXIAL CABLE
1/4-λ STUB 2 PIECES RG-59/U
50-Ω
1-1/2" PVC PIPE BOOM
NYLON ROPE
12'
12'
m = FEET(') x 0.3048
mm = INCHES(") x 25.4
22'
23.5'
1:1 BALUN
90° OR GREATER
INSULATOR
1/2" PVC PIPE
12'
NYLON ROPE
COAXIAL CABLE TO SHACK
D.B. length = 476/f_{MHz}
Dir. length = 450/f_{MHz}
Spacing = 120/f_{MHz}

---

201 - FD4 Windom Antenna for 80m, 40m, 20m, 10m


INS
14m.
4:1 BALUN
28m.
INS
'FD4' Windom
75Ω COAX
3/8" ø
CLOSEWOUND
FERRITE ROD
SCREEN
ONE SIDE OF ANT
INNER
OTHER SIDE OF ANT
75Ω COAX.

---

202 - Two Elements Phased Delta Loop for 40m


DIRECTION OF BEAM
35'
EAST
WEST
SEE DETAIL A
47'
47'
SEE DETAIL A
50'
6'
3/4-WAVE, 75-Ω COAXIAL TRANSFORMERS
DOUBLE FEMALE CONNECTOR
52-Ω COAXIAL PHASING LINE
T CONNECTOR
52-Ω LINE (ANY LENGTH)
XCVR
DETAIL A
Gain = 3dB

203 - Three Elements Wire Yagi for 10m


DIRECTOR
DRIVEN ELEMENT 300-Ω TWIN-LEAD
NYLON CORD
0.125 λ
0.2 λ
BAMBOO SUPPORTS
50"
80"
REFLECTOR
BAMBOO SPREADER LENGTHS ARE 112" FROM THE CENTER
75-Ω COAXIAL CABLE
MAST
ELEMENT LENGTHS
DIRECTOR 184"
DRIVEN ELEMENT 203" *
REFLECTOR 212" *
* INCLUDING OVERHANG

204 - Low Radiation Angle Full-Wave Loop Antenna for 80m


TRIBAND
YAGI
INSULATOR
50'
NO. 12 WIRE
W1FB SYSTEM
RESONANCE = 3550 kHz
LOOP
70'
450-Ω LINE
4:1
BALUN
RG-8/U
TO STN.
Z ≈ 100 Ω
L (OVERALL) = 1005 / f (MHz) FEET
94.37' A
B 94.37'
94.37' C
6'
OPEN-WIRE
FEED
Z ≈ 100 Ω
6'
WOODEN POLE
m = FEET (') x 0.3048

205 - Collinear Antenna Gain=3dB for 2m


1/4 λ IN AIR (APPROX. 19")
SHORT
1/4 λ IN COAX (APPROX. 13")
1/2 λ IN
COAX
(APPROX.
26" EACH)
1/4 λ IN
COAX
(APPROX. 13")
HAIRPIN
(A)
FEED LINE
52 Ω
HAIRPIN DETAIL
USE NO. 14 COPPER
WIRE
0.8"
0.5"
2.1"
1.5"
(B)
mm = INCHES (") x 25.4

206 - X-Ray Monoband Antenna Gain=6.5dBd


INSULATOR (TYP)
L1
L1
GUY
α
α
h_min
PLAN VIEW
L1
L1
L1
L1
90° TYP
ELEVATION VIEW
L1
L1
L1
L1
RELAY
BALUN 1:1
BOX
FLEXIBLE LEADS (4 REQD)
CABLES
CENTRAL MAST

Band	*Element Length*	*Center Mast*
40 m	172 ft	67 ft
30 m	122 ft	46 ft
20 m	87 ft	34 ft
15 m	58 ft	22 ft
10 m (28.0-28.5 MHz)	43 ft 6 in	17 ft
10 m (28.5-29.0 MHz)	42 ft 9 in	
10 m (29.0-29.5 MHz)	42 ft	

207 - Broadside Collinear Curtain Array for 20m


Catenary Rope
Antenna Wire 43'5" (4 places)
Twine Support (3 places)
to Tree
to Tree
Insulator (6 places)
Lightweight Twinlead 43'5"
Support Rope 43'5" (2 places)
21'8"
Feed Line to Shack
Anchor Rope
Anchor Rope
Gain = 12dB

208 - Shrunk Loop Antenna for 80m, 40m


40m
50-Ω
Coax
Feed
40pF
40pF
TUNE
40pF
3-1/2'
4-1/2'
80m
MATCH
50-Ω
Coax
Feed
100pF
100pF
300pF
TUNE
100pF
3-1/2'
4-1/2'

209 - λ/3 Multiband Dipole for 40m, 20m, 17m, 15m, 13m, 10m


92'0"
350- to-380-Ω Ladder Line
(See text)
39' 8-1/2" long to Ⓐ, below
10' 10-3/4" 450-Ω
Ladder Line
(Impedance Transformer
for 15 Meters)
DPDT
Knife Switch
A
1:1 Bead Balun
(See text)
50-Ω Coaxial Cable
to Shack

210 - K3LR Sloper Antenna Gain=3dB for 160m


Anchor Point at 190 Feet Above Ground
3 to 4 Feet of Rope
Wire Length = 131' 8" (each leg)
Feed Point at 97 Feet
3 to 4 Feet of Rope
Anchor Point at 5 Feet Above Ground
Anchor Point at 198 Feet from Tower
Rope
Wire
Feed Line
Wire
Rope

---

211 - Mini Folded Vertical Monopole Antenna for 160m, 80m, 40m


H
L
SWR METER
XMTR
H
360 pF
SWR METER
XMTR

0.19λ MINI - MONOPOLE		
FREQ.(mc/s)	HEIGHT (H)	TUNING COIL (L)
1.825	100'	4.5 uH
1.925	90'	
3.5	51'	2.2 uH
4.0	46'	
7.0	25'6"	1.1 uH

0.075λ MINI MONOPOLE	
FREQ.(mc/s)	HEIGHT (H)
1.825	40'
1.925	36'
3.5	20'
4.0	18'
7.0	10'

---

212 - Three Band Dipole for 80m, 40m, 20m


C
C
17 FT
32 FT
32 FT
17 FT
L
L
NUMBER 12 OR 14 COPPER OR COPPER-CLAD STEEL WIRE
17½'
17½'
C= 60 pF
L= 8.12 uH
50-75 OHM TRANSMISSION LINE, ANY REASONABLE LENGTH

---

213 - Stub Matched Dipole Antenna


1/4 λ (20)
1/4 λ (20)
1/4 λ (20)
1/4 λ (10)
50/70 OHM LINE TO TRANSMITTER
20/10 METERS
1/4 λ (10.5 MHz)
1/4 λ (10.5 MHz)
1/4 λ (10.5 MHz)
1/4 λ (15)
15, 10 METERS
1/4 λ (40)
1/4 λ (40)
1/4 λ (40)
1/4 λ (20)
40, 20, 15 METERS

214 - Inverted-Vee Antenna with Bazooka Match


HANGER
$\frac{1}{4}\lambda$
a
FEEDLINE
HANGER
$\frac{1}{4}\lambda$ RG-8/U BALUN
length
246v/f, where v = 0.659
RG-8/U COAX TO TRANSMITTER

215 - Multiband Long Wire Antenna for 40m, 20m, 15m, 10m


(SLIGHT TILT)
271'
4-TO-1 BALUN
JUMPER (1 OF 5)
52 Ω COAX TO XMTR
8'1"
(10)
2'7"
(15)
5'6"
(20)
14'11"
(40)
BAND
(20)
1'10"
(10, 15)
24'9"
(40)
BAND

216 - Converted Vee Antenna for 80m, 40m


l2
l1
l3
FEEDPOINT
SPACER
SPACER
SPACER
EGG INSULATOR
SHORTED 83-1SP PLUG
l1 = 34.5 FEET
l2 = 60.5 FEET
l3 = 6.0 FEET

217 - Swiss Quad Antenna for 20m, 15m, 10m



Dimensions for the Swiss quad (in inches).

frequency (MHz)	reflector horizontal (R)	radiator horizonal (D)	vertical (H)	spacing (S)	gamma length (L)	gamma spacing (A)
14.05	248	223½	236	84	188½	4¼
14.2	245	221	233	83	186½	4¼
21.05	165	149	157	56	126	2½
21.2	162½	148	155½	55½	124½	2½
28.05	124	112	118	42	94½	2
28.5	122	110	116	41½	93	2

218 - Japanese Quad Antenna for 20m, 15m, 10m


B
B
A
A
STUB
FEEDLINE



Construction details of the Japanese quad (in inches).

frequency (MHz)	quad side (A)	spacing	coil location (B)	coil (μH)	winding info
14	152	101	38	3.0	17½ turns no. 14, 1½" diameter, 5" long
21	98	67	24½	2.0	11 turns no. 14, 1½" diameter, 3½" long
28	77	50	19¼	1.5	9½ turns no. 14, 1½" diameter, 3½" long

---

219 - Seven-Elements Triangle Beam Antenna for 20m


NYLON ROPE
13'
13'
13'
13'10"
10'4"
13'10"
NO. 14 WIRE
TO SET
STAKE
NYLON ROPE
STAKE
23'
23'
11'6"
11'6"
DRIVEN ELEMENT
26' 21' 20'6"
26' 21' 20'6"
REFLECTOR 26'
FIRST DIRECTOR 21'
OTHER DIRECTORS 20'6"

---

220 - Log Periodic Wire Antenna for 40m


0
14
27
39
48
14 ft
13 ft
12 ft
9 ft
1 to 2 in.
70 ft
64 ft (40M λ/2 RADIATOR)
56 ft
49 ft
40 ft
X XMIT
X REC
XX-300Ω FEEDER OR 4:1 BALUN & COAX
1
2
3
4
5
34 ft (approx λ/4)
Lo Z
Hi Z

221 - Three-Elements 90-degrees Wire Beam for 20m


6-1/2 ft
DIRECTOR
31 ft
16 ft
DRIVEN ELEMENT
16 ft
BALUN
RG-8/U COAX
SIGNAL DIRECTION
32 ft
REFLECTOR
33 ft

---

222 - Two-Elements Wire Beam for 20m


SIGNAL DIRECTION
NYLON BRIDLE
DIRECTOR
31 ft - 4 in.
NO. 14 AWG
6 ft - 6 in.
WOODEN SPREADER
BALUN
16 ft DRIVEN
16 ft ELEMENT
DRIVEN ELEMENT
(2)-16 ft LENGTHS HARDWALL ALUMINUM TUBING-1/2 in. O.D.
RG-8/U COAX

---

223 - Suitcase-Fit Dipole Antenna for 80m, 40m, 20m


33 in.
33 in.
PRUNING PIECE
PRUNING PIECE
50
50
206T
15T
84T
9T
153T
153T
9T
84T
15T
206T
PRUNING PIECE
PRUNING PIECE
20M TRAP
20M TRAP
100 40M TRAP
100 40M TRAP
BALUN
70 Ω COAX

224 - Multiband Coaxial Dipole for 80m, 40m


20 ft
33 ft
33 ft
20 ft
L1
L1
NO. 14 AWG
NO. 14 AWG
RG-58/U
47
47
COAXIAL FEEDLINE

Trap coil L1 is 21½ turns of B&W coil stock, 2" diameter, 8 turns per inch.

225 - Vertical Log Periodic Antenna for 80m, 40m


TOWER
http://www.qsl.net/va3iul
1/4" CATENARY LINE
45' WOOD POLE
70'
64'
57'
52'
47'
43'
39'
35'
32'
29'
26'
24'
22'
26'
24'
23'
22'
19'
17'
16'
14'
12.5'
11.5'
10'
9'
α = 13.5°
EXTEND FOR 80-40-20
EXTEND FOR 80-40-20-15
BEAM
204'
230'
FEED POINT

226 - Inverted Vertical Log Periodic Antenna for 40m


SIDE MAST
10-dB gain
RADIALS
SIDE MAST
REAR MAST
S1
S2
S3
S4
4:1 BALUN
E1
E2
E3
E4
E5
COAX
FRONT MAST
VERTICAL RADIATOR
SIDE MAST
SIDE MAST
dimensions (feet)
for 40 meters
E1 35 S1 14
E2 32 S2 13
E3 28 S3 12
E4 24.5 S4 9
E5 20
http://www.qsl.net/va3iul

227 - Double Extended Zepp Antenna Gain=7dB for 15m


27.5'
35.5'
35.5'
27.5'
7.68'
7.68'
OPEN WIRE FEEDLINE
http://www.qsl.net/va3iul

228 - Double Lazy-H Antenna G=10dB for 70cm


262
246
101
xx
187
354
221
125
10.8 dBd 21 dB F/B
xx - 50 Ohm, distance ~5mm
SWR = 1 @ 435 MHz
Material 3-5 mm dia aluminium
http://www.qsl.net/va3iul

229 - Wire Log Periodic Antenna G=12dB for 15m, 20m


http://www.qsl.net/va3iul
λ/2 AT 20 METERS
λ/2 AT 15 METERS
1.75'
36' (11.0m)
34' (10.37m)
31' (9.46m)
29' (8.85m)
26.5' (8.08m)
24' (7.32m)
22' (6.71m)
20' (6.1m)
18.5' (5.64m)
17' (5.19m)
16' (4.88m)
11.5' (3.51m)
10.0' (3.05m)
9.0' (2.75m)
8.5' (2.6m)
7.5' (2.29m)
7.0' (2.14m)
6.5' (1.98m)
6.25' (1.9m)
5.5' (1.68m)
5.0' (1.52m)
COAX OR 1:1 BALUN
16° (α = 8°)
2/4 λ ON 15
15M LOW Z
HIGH
LOW Z
4/4 λ ON 20
20M LOW Z
HIGH
LOW
HIGH
LOW Z
72' (22m)

230 - Five-Elements Vertical Log Periodic for 80m, 40m, 20m


S1
S2
S3
S4
E1
E2
E3
E4
E5
BEAM
E1 VERTICAL ELEMENTS
E2 (1/4 λ)
E3
E4
E5
1-1/2" (76mm) FEEDER SPACING
4:1 BALUN
COAX
SHORT EARTH GROUND
1/4 λ
TOTAL LENGTH

element	3.5-4.0[1]	3.8-4.0[2]	7.0-7.3[2]	14.0-14.35[1]
E1	70' (21.4 m)	65' (19.8 m)	35' (10.7 m)	17.5' (5.3 m)
E2	67' (20.4 m)	62' (18.9 m)	33' (10.0 m)	16.5' (5.0 m)
E3	58' (17.7 m)	55' (16.8 m)	28' (8.5 m)	14.0' (4.3 m)
E4	50' (15.3 m)	45' (13.7 m)	24.5' (7.5 m)	12.2' (3.7 m)
E5	43' (13.1 m)	40' (12.2 m)	20' (6.1 m)	10.0' (3.0 m)
S1	30' (9.2 m)	26' (7.9 m)	14' (4.3 m)	7.0' (2.1 m)
S2	27' (8.2 m)	24' (7.3 m)	13' (4.0 m)	6.5' (2.0 m)
S3	24' (7.3 m)	23' (7.0 m)	12' (3.7 m)	6.0' (1.8 m)
S4	19' (5.8 m)	18' (5.5 m)	9' (2.7 m)	4.5' (1.4 m)
total length	100' (30.5 m)	91' (27.8 m)	48' (14.6 m)	24' (7.3 m)
mast height	80' (24.4 m)	75' (22.9 m)	50' (15.3 m)	30' (9.2 m)
pole height	45' (13.7 m)	40' (12.2 m)	25' (7.6 m)	20' (6.1 m)

http://www.qsl.net/va3iul

231 - Sloping Delta Loop Antenna for 40m


http://www.qsl.net/va3iul
Total length 43·48m
14·49m
16m
14·49m
14·49m
2m
70Ω
7·02m
50Ω

232 - Doublet Antenna for 160m


32ft-8in
32ft-8in
8ft
8ft
69 turns, 1·25in dia, + 3 x 5in ferrite rods
33ft
14ft
14ft
A T U
http://www.qsl.net/va3iul

233 - Log Periodic Wire Beam for 40m


L1 21 METERS (+3.75cm) (69.5 FT.)(+1.5 IN.)
3.75cm (1.5 IN.)
S1 7.7 METERS (25.2 FT.)
L2 20 METERS (66 FT.)
S2 7.3 METERS (23.9 FT.)
L3 19 METERS (62.7 FT.)
S3 7 METERS (22.7 FT.)
L4 18 METERS (59.6 FT.)
TOTAL BOOM LENGTH 22 METERS (71.8 FT.)
FEED TO 4:1 BALUN OR TWO WIRE TUNED FEEDER
http://www.qsl.net/va3iul

234 - G3LDO Wire Beam Antenna for 20m, 15m, 10m


Data for the G3LDO wire-beam antenna. All dimensions are in inches and are for insulated wire; multiply by 1.04 for uninsulated wire. Dimension C is approximate.

band	reflector	driven element	A	B	C	D
20	452	417	245	263	180	33
15	302	279	154	166	113	22
10	225	208	114	122	85	15

http://www.qsl.net/va3iul
X = INSULATOR
Z = NYLON CORD
DRIVEN ELEMENT
REFLECTOR
COAXIAL CABLE FEEDER
DRIVEN ELEMENT
REFLECTOR
A
B
C
X
Z
PLAN VIEW
DRIVEN ELEMENT
REFLECTOR
BAMBOO OR GLASS-FIBER SUPPORTS
GENERAL CONSTRUCTION DETAILS WITH DIMENSION REFERENCES

235 - Phased Delta Loop Array for 20m


0.33λ
(20 meter band)
23'
(7 METERS)
D
20'
(6 METERS)
feedpoint
23'
23'
(7 METERS)
35'
(10.7 METERS)
TV mast
tie down
to transceiver

spacing wavelength	feet	(meters)	gain (dB)
0.33	23	(7)	2.0
0.40	27	(8)	2.8
0.50	34	(10)	4.0
0.65	44	(13)	4.8

http://www.qsl.net/va3iul

236 - Dual Band V-dipole for 80m, 40m


INSULATOR TO SUPPORT COAX
58'
INSULATOR (TYPICAL)
ABOUT 90°
WIRE STUB 3" LONG
A
8' POLE WITH STEPS
58'
COAX
WIRE STUB
B
RG-8/U
8' POLE WITH STEPS
30' WOOD MAST
THREE WIRE END SECTIONS FOR A AND B
JACK (TYP.)
1 FT = 0.305 METER
1 IN. = 2.54 CM
53"
25"
17"

http://www.qsl.net/va3iul

237 - Collinear Array 5dB-Gain for 15m


INSULATOR (TYPICAL)
ROPE
A
A
A
A
ROPE
B
B
LENGTHS
A = 22' 11"
B = 11' 2"
TO TUNER
USE 450-OHM "LADDERLINE" FOR B STUBS AND MAIN LINE
1 FT = 0.305 METER
1 IN. = 2.54 CM

http://www.qsl.net/va3iul

238 - Two-Band Quad Loop Antenna 80m, 40m


SUPPORT INSULATOR
34'
34'
34'
34'
ROPE
ROPE
75-OHM COAX LINE (RG-11/U)
40-50'
1 FT = 0.305 METER
40-METER STUB (±4' LONG)
http://www.qsl.net/va3iul

239 - K7CW Quad Antenna


X
H
C
E
A
D
COAX
http://www.qsl.net/va3iul

$X = \frac{1030}{9.84F}$ Where F = design frequency of antenna (3X = total distance around reflector loop).

$A = \frac{1005}{9.84F}$ 3A = total distance around driven element loop.

$H = \frac{X}{2}$ = distance from main hub to top of antenna (the imaginary plane which contains the tips of all four spreaders).

$D = .2\lambda$ where λ = wavelength at design frequency.
D = element spacing
= length of bottom spreader.

$E = \sqrt{X_2 - H^2} - H$ = distance from bottom spreader to main hub.

$C = \sqrt{2H^2 + \left(\frac{D}{2}\right)^2}$ = distance from hub to where loop is attached to main spreader.

antenna design frequencies (in mete

	3.575 MHz	3.8 MHz	7.05 MHz	7.2 MHz
X	29.2722	27.5389	14.8437	14.5344
Y	87.8165	82.6168	44.5311	43.6033
A	28.5617	26.8705	14.4834	14.1817
B	85.685	80.6116	43.4502	42.5450
H	14.6361	13.7695	7.42184	7.26722
D	16.7832	15.7895	8.51064	8.33333
E	10.7144	10.0800	5.43317	5.31998
C	22.3349	21.0124	11.3258	11.0899

	21.3 MHz	28.15 MHz	28.6 MHz	29 MHz
X	4.91305	3.71751	3.63902	3.60855
Y	14.7392	11.1525	10.9771	10.8257
A	4.79380	3.62728	3.57021	3.52097
B	14.3814	10.8818	10.7106	10.5629
H	2.45653	1.85876	1.82951	1.80428
D	2.81690	2.13144	2.09790	2.06897
E	1.79830	1.36070	1.33929	1.32082
C	3.74870	2.83649	2.79186	2.75335

Note: X = length of reflector loop side
Y = distance around reflector loop
A = length of driven element loop side
B = total distance around driven element loop
H = distance from hub to top of antenna
D = bottom spreader length
= element spacing
E = distance from bottom spreader to main hub
C = distance from hub to where loop is attached to main spreader, that is, spreader length

240 - Broadband Short Dipole for 80m


http://www.qsl.net/va3iul
14' (4.27m)
17' (5.18m)
18' (5.48m)
90°
17' (5.18m)
90°
1:1 BALUN
17' (5.18m)
14' (4.27m)
17' (5.18m)
90°
18' (5.48m)
14' (4.27m)
COAXIAL CABLE
14' (4.27m)
ROPE
17' (5.18m)
ROPE
17' (5.18m)
(OBLIQUE VIEW)

241 - Off-Center Fed Dipole for 40m, 20m, 10m


22'-11"
(7M)
44'-3"
(13.5M)
INSULATOR
4:1 BALUN
INSULATOR
COAX LINE
http://www.qsl.net/va3iul

242 - Broadband Sloper Antenna for 80m


ROPE AND INSULATOR (10 INCHES OR LESS)
http://www.qsl.net/va3iul
50 FOOT METAL TOWER
63'6" (19.35m)
SPREADER ASSEMBLY (TYPICAL)
ROPE
GROUND
TIE POINT
ABOUT 43' (13m)

80-meter WD4FAB broadband sloper. Spreader assemblies are made of 36-inch long fiberglass tubes. The four antenna wires are tied together about 24 inches past each spreader assembly. A nylon line may be required from the crossover point of the spreader to the outer insulator to prevent bowing. The SWR plot of the antenna falls below 1.4-to-1 at 3.5 MHz; 1.25-to-1 at 3.8 MHz and 1.4-to-1 at 4.0 MHz. Feedpoint resistance of the antenna may be changed by altering the slope angle. The resonant frequency is adjusted by changing length — no climbing necessary!

243 - Two-Frequency Dipole Antenna for 80m


ROPE
62'5"
62'5"
INSULATOR
1/2λ × 0.66 = 91'6"
RG-58/U
BALUN
EIGHT TURNS OF LINE PASSED THROUGH TOROID
SWITCH
L
http://www.qsl.net/va3iul
TO SWR METER AND TRANSMITTER

The W6TC two-frequency dipole for 80 meters. Antenna is cut for resonance at high frequency end of band. A single loading coil for operation at the low frequency end of the band is placed an electrical half-wavelength down the transmission line. The line is decoupled from the antenna by a simple balun placed directly at the antenna insulator. Toroid is powdered iron material T-200 (2″ OD) (1.25″ ID), 2-mix (red, μ = 10 (Amidon T-200-2), or equivalent.

244 - Top Loaded Vertical Antenna for 160m


http://www.qsl.net/va3iul
CONTINUOUS WIRE - NO INSULATOR
LOOP CONSTRUCTED FROM NO. 14 AWG HARD DRAWN COPPER
LEG 3
LEG 2
20' (6.1m) PVC PIPE SPREADER
JUMPER
JUMPER
TOP SPACER
LEG 4
LEG 1
12" (30cm) INSULATOR
JUMPER FROM FEEDER TO LOOP
12" (30cm) INSULATORS
3/8" (9.5mm) WOOD DOWEL SPACERS WITH 3 NO. 14AWG
POLE 70' (21m) HIGH
FEED POINT
POLE TO POLE DISTANCE - 95' (29m)

245 - Two Loop Beam Antenna for 20m, 15m


INSULATOR (TYP.)
WIRE OR NYLON ROPE
A
WIRE OR NYLON ROPE
A1 A2
A1, B1
A2, B2
B1 B2
1:1 BALUN
40' (12.2m) SUPPORT
40' (12.2m) SUPPORT
50 OHM COAX TO SHACK
OVERALL LENGTH OF LOOPS = 1005/f MHz (IN FEET--IN METERS, DIVIDE RESULT BY 3.28)
DIMENSION "A" EQUAL TO ONE SIDE OF LOOP.
4.5 dB over a dipole

The W2TBZ loop beam. The phasing lines are made of 300-ohm TV line. Length of phasing line = $\frac{468}{f_{MHz}}$ × velocity factor of 300-ohm line. Balun is supported at center of lower nylon rope.

http://www.qsl.net/va3iul

246 - Corner-Fed Delta Loop Antenna for 80m, 40m, 20m


21'
(6.40M)
21'
(6.40M)
29'
(8.84M)
50/75 OHM
COAX
http://www.qsl.net/va3iul
TX

DIMENSIONS FOR FULL-SIZE CORNER-FED DELTA LOOPS

frequency (MHz)	total loop circumference		length of each side		length of base	
	(feet)	(meters)	(feet)	(meters)	(feet)	(meters)
3.600	279 ft. 2 in.	(85.09)	82 ft.	(24.99)	115 ft. 2 in.	(35.10)
7.075	142 ft. 0 in.	(43.28)	42 ft.	(12.80)	58 ft. 0 in.	(17.68)
14.150	71 ft. 0 in.	(21.64)	21 ft.	(6.40)	29 ft. 0 in.	(8.84)

---

247 - Loaded Delta Loop Antenna for 40m, 20m


http://www.qsl.net/va3iul
3',(1.06M) BIAS
16'
(4.88M)
16'
(4.88M)
12"
(0.3M)
12"
(0.3M)
9'3"
(2.81M)
9'3"
(2.81M)
10'
(3.04M)
10'
(3.04M)

The final loaded loop for 14 MHz. All dimensions are doubled for operation on 7 MHz. Base loading wires are each 18 feet 4 inches (5.59 meters). The top loading wire is made taut by securing to base with thin light nylon cord.

---

248 - Compact Size Dipole for 80m


A
B
L3
L1
L2
INSULATOR (TYP.)
COAX TO STATION

design frequency (MHz)	A feet	A meters	B feet	B meters	L_1, L_2 (uH)	L_3 (uH)
3.5	66.85	20.38	16.71	5.09	43.4	2.0
3.6	65.00	19.81	16.25	4.95	42.0	1.9
3.8	61.57	18.77	15.39	4.69	39.6	1.8
4.0	58.50	17.83	14.62	4.46	37.3	1.7

antenna wire size: 14 AWG
L_1, L_2, L_3 diameter = 2 inches (5 cm)
(all coils are close wound)

3.5 L_1,L_2 = 36.5 turns, L_3 = 4.8 turns
3.6 L_1,L_2 = 35.0 turns, L_3 = 4.7 turns
3.8 L_1,L_2 = 34.0 turns, L_3 = 4.6 turns
4.0 L_1,L_2 = 32.5 turns, L_3 = 4.4 turns

http://www.qsl.net/va3iul

---

249 - JAWS 3dB Gain Antenna for 40m


X
34'5" (10.5m)
X
19'8" (6m)
34'5" (10.5m)
42'8" (13m)
GAMMA MATCHING SECTION
34'5" (10.5m)
1'8" (50cm)
1'8" (50cm)
X
X
X
X
X
34'5" (10.5m)
16'5" (5m)
COAXIAL CABLE FEEDER
19'8" (6m)

EACH RADIAL HAS A LENGTH OF 68'11" (21m)
APEX OF EACH IS FIXED TO A SUITABLE ANCHORING POINT
APEX 1'8" (50cm) APART
X - INSULATORS

http://www.qsl.net/va3iul

---

250 - Inverted-V Antenna for 160m


110'
(33.52M)
110'
(33.52M)
COAX CHOKE
4" (10.16cm)
SPACERS
60' (18.28M)
TO GROUND
http://www.qsl.net/va3iul

The inverted-V antenna for 160 meters at VE7BS. Wires all lie in the same plane. Apex is at 105 feet (32 meters).

---

251 - Lazy-U Antenna for 160m


80'
(24.38M)
50'
(15.24M)
COAX WIRE
50'
(15.24M)
10' (3.05M)
TO GROUND
http://www.qsl.net/va3iul

---

252 - AF3V Compact Antenna for 160m


L = 89μH. 59 turns No. 18 gauge enamel wire, 1-7/8 inches diameter, close wound about 2.8 inches long.
INSULATOR
L
17' (5.2 m)
32' (9.75 m)
ROPE
15' (4.6 m)
20' (6.1m)
SERIES CAPACITOR HERE IF DESIRED
FEED POINT
65' (19.8 m) COUNTERPOISE WIRE ON GROUND
RADIO GROUND
http://www.qsl.net/va3iul

253 - Hot Beam Wire Antenna for 40m


http://www.qsl.net/va3iul
140' FIR TREE
130' LEVEL
ROPE
APPROX 1/4λ SPACING
INSULATOR (TYP)
100' LEVEL
DRIVEN ELEMENT
33' (10m)
REFLECTOR
33' (10m)
DIRECTION OF FIRE
1:1 BALUN
1:1 BALUN
33' (10m)
33' (10m)
ROPE
RG8X
COAX TO SHACK (SEE NOTES FOR SPACING)
10' POST

254 - Sloping Delta Loop for 40m


http://www.qsl.net/va3iul
INSULATOR (TYP)
47.5' (14.5m) EACH SIDE
53' (16m)
RG-11/U
23' (7.02m)
6.5' (2m)
ABOVE GROUND
RG-8/U
RANDOM LENGTH

---

255 - K6FD Multiband Antenna with T-tuner


TUNER
50 OHMS
50 OHMS
L1
L2
C1
L1 = 16 TURNS, 2 1/2" (63.5mm) DIA, 2" (50.8mm) LONG
L2 = 40 TURN ROLLER COIL, 1 1/2" (38 mm) DIA., 3" (76.2 mm) LONG
26' (8m)
32.8' (10m)
RG-141/U COIL, 14 TURNS 3" (76.2mm) DIA
75°
40' (12m)
RG58/U TO TUNER 100' (33m)
32.8' (10m)
26' (8m)
http://www.qsl.net/va3iul

---

256 - Dual Band Dipole Antenna for 17m, 10m


29'6"
29'6"
11'
FLAT TOP = 1075 / f (MHz)
STUB = 200 / f (MHz)
F
F
http://www.qsl.net/va3iul

257 - Compact Travel Dipole Antenna for 10m, 15m, 20m


21'4"
72"
L1
4.85 µH
54"
L2
4.85 µH
J1
J2
http://www.qsl.net/va3iul

Loading coils:

L1,L2 24 turns 3/4-inch x 16 TPI coil stock (B&W No. 3011 or Air Dux 616T) or 14 turns 1-1/2 inch x 8 TPI coil stock (B&W No. 3018 or Air Dux No. 1008).

J1,J2 8-inch clip leads.

258 - End-Fire Antenna for 160m, 80m, 40m, 20m


INSULATOR (TYP)
TOTAL LENGTH = 102'6" (31.24m)
L = 10µH
TO TRANSMITTER
A
A
1
2
S1
POSITION 1 = 160M
POSITION 2 = 80-20M
C = 1500pF
C = 350pF VARIABLE PLUS 1500pF SWITCHED 500pF AT A TIME
A
A
GROUND AND RADIAL SYSTEM
http://www.qsl.net/va3iul

259 - Four Band Loop for 40m, 20m, 15m, 10m


26 ft 3 in
19 ft 8 in
19 ft 8 in
34 ft 3 in
TO
37 ft 9 in
TWO WIRE LINE
4-TO-1
BALUN
50Ω
http://www.qsl.net/va3iul

260 - Carolina Windom Antenna for 80 to 10m


131' 10"
INSULATOR
(TYP)
ROPE
4-TO-1
BALUN
81' 8"
50' 2"
RG-8A/U OR RG-11/U
RANDOM LENGTH
XMTR
LOW PASS
FILTER
TUNER
http://www.qsl.net/va3iul

261 - Shortened Loaded Dipole for 40m


213"
78.7"
78.7"
213"
4.5μH
4.5μH
http://www.qsl.net/va3iul
SWR
3.0
2.5
2.0
1.5
1.0
6.9
7.0
7.1
FREQ

262 - Shortened Loaded Dipole for 80m


25'10"
17'2.7"
17'2.7"
25'10"
http://www.qsl.net/va3iul
16.75µH
COAX (52OHMS)
16.75µH

---

263 - Low Radiation Angle Inverted Delta Loop for 80m


36.69m
L = 120' 4.75" *
http://www.qsl.net/va3iul
A = 75' 4" 22.96m
B = 15' 1.5" 4.95m
C = 60' 2.5" 18.91m
H = 43' 13.1m
h = 6' * 1.82m
H
h
A
B
C
50 OHM FEEDLINE
10 LB WEIGHT

---

264 - Compact Dipole Antenna for 40m, 15m


27'
27'
INSULATOR (TYP)
8'
1-TO-1 BALUN
TO COAX
http://www.qsl.net/va3iul

---

265 - Vertical Delta Loop for 40m to 10m


INSULATOR (TYP)
26'3"
19'7"
34'6"
20pF
4-TO-1 BALUN
TO COAX
http://www.qsl.net/va3iul

---

266 - Delta Loop Antenna for 17m


ROPE SUPPORT
INSULATOR (TYPICAL)
18'6"
18'6"
9'3"
9'3"
75Ω LINE
PL-258 SPLICE
50Ω LINE
http://www.qsl.net/va3iul

---

267 - Bi-Square Beam Gain=3dBd for 17m


26'6"
26'6"
37'
26'6"
26'6"
13'3"
600Ω
OPEN WIRE LINE.
NO 16 WIRE
SPACED 4"
9'0"
75Ω LINE
50Ω FEEDPOINT

http://www.qsl.net/va3iul

268 -Trap Dipole Antenna for 17m,13m


25"
19'2"
25"
B
50Ω
1.6μH
25pF
INS.
4"
TYPICAL
(2 PLACES)

http://www.qsl.net/va3iul

269 - Hanging Unipole Antenna for 160m, 80m


INSULATOR
TRIM LENGTH TO RESONATE
AT DESIRED FREQUENCY
84.5' FOR 1.9 MHz
19.5' FOR 3.8 MHz
ROPE
INSULATOR
ROPE
45'
THE TALLER THIS IS,
THE SHORTER THIS IS
6" LONG
SPACERS
COAX
GROUND AND
RADIAL SYSTEM
http://www.qsl.net/va3iul

---

270 - Wideband Sloping Vee Antenna - 30m to 6m


11:1
10:1
9:1
8:1
7:1
6:1
5:1
4:1
3:1
2:1
1:1
VSWR/50-OHM
10
15
20
25
30
35
40
45
50
55
60
FREQUENCY (MHz)
BALUN
RADIATING ELEMENT
64 FT
314
OHMS
69° APEX ANGLE
75 FT
RADIATING ELEMENT
64 FT
SHORTING
WIRE
TYPE-N
BARREL
307 OHMS
75 FT
VSWR
CALIBRATION
POINT
COAXIAL FEED
CABLE RG-213/U
http://www.qsl.net/va3iul
SECONDARY
SECONDARY
PRIMARY
PRIMARY
TO
TRANSMITTER
TO 50-OHM
DUMMY LOAD
2 TURNS
2 TURNS
7.5 TURNS
7.5 TURNS
BALUN 1
BALUN 2

SOURCES OF MATERIALS

The following companies are sources for materials and computer software for this project:

- Toroidal ferrite cores (Part No. FT240-43)—Radio Kit, Inc., P.O. Box 973, Pelham, NH 03076, (603) 635-2235
- Film power resistors—Power Film Systems, Inc., Yellville, AR 72687, (501) 449-4091
- Antenna design software—Phadean Engineering Co., Inc., P.O. Box 611, Shrewsbury, MA 01545, (508) 869-6077
- Phosphor-bronze wire—Astro Industries, Inc., Dayton, OH 43432, (800) 543-5810
- Fiberglass tubing—J. T. Ryerson Co., P. O. Box 1111, Boston, MA 02103. (617) 782-6900

-BACK-TO-BACK INSERTION LOSS TEST of baluns for sloping-vee antenna.

---

271 - 5/8 Wavelength Antenna


RADIATOR ELEMENT
5/8-wavelength radiator
L(ft) = 585 / F(in MHz)
L1 = 122 / F(in MHz) feet
L2 = 30 / F(in MHz) feet
L(ft) radials = 246 / F(in MHz)
5/8 λ
L1
L2
λ/4
RADIALS
λ/4
COAX TO XMTR

http://www.qsl.net/va3iul

272 - C-Pole Vertical Antenna


Suspension cord
Upper spreader
Spacer
Lower spacer
Ground rod
Balun
E
C
D
A
B

http://www.qsl.net/va3iul

Band (meters)	A (inches)	B (inches)	C (inches)	D (inches)	E (inches)	2:1 SWR bandwidth (kHz)
160	1666	924	994	60	80	58
80	840	460	360	30	40	120
60	591	322	249	20	26	250
40	450	240	190	20	20	260
30	320	167	139	14	14	360
20	177	85	84	8	40	400
15	124	60	60	4	20	600
10	87	46	37	4	20	800

Wire diameter is 1/16-inch. Height of the lower horizontal wire is 12 inches to 24 inches and is non-critical.

273 - Bobtail Antenna for 30m


Bobtail for 10 MHz
Inner conductor
Support line
A
50 ohm coax
Wire
B
Support line
3 ferrite beads
Spring
1438 cm
1438 cm
A
B
719 cm
719 cm
719 cm
1mm insulated wire
Support lines
http://www.qsl.net/va3iul

274 - Bobtail Antenna for 40m


Bobtail for 7 MHz.
1 mm insulated wire
Support lines
Spring
3 dB
20,47 m
20,47 m
3 dB
10,24 m
10,24 m
10,24 m
Plastic box
A
Bamboo pole
Earthpole
Antenna A
L = 24 turns, 82 mm long and diam = 50 mm.
C = 3 pieces 12 cm long of RG213 = 37 pF
C
L
4 turns
50 ohm coax
Earthpole
http://www.qsl.net/va3iul

275 - Two Elements Vertical Loop Antenna for 40m


2 el loop for 7 MHz
1 mm insulated line
Support lines
1690 cm
705 cm
1260 cm
1260 cm
Mast
1350 cm
50 ohm coax
485 cm 450 ohm ladder
100 pF condenser
380 cm
By adjusting condenser you can get the element to act either as an director or reflector element
http://www.qsl.net/va3iul

276 - Double Extended Zepp Antenna for 40m


Double Extended Zepp for 7,05 MHz
(bent to fit into garden)
Spring
16 m
3 dB
1 mm insulated wire
Support lines
11,24 m
3 dB
16 m
5,80 m
450 ohm ladder
11,24 m
Balun 1:1
25 mm VP-tube
50 ohm coax
Dipole
Double Extended Zepp
9 turn trifilar insulated wire
1,8 mm outer diameter.
http://www.qsl.net/va3iul

277 - Reversible Moxon Flip Beam for 40m


7.1 MHz Flip Beam Antenna (FBA)
Tot-gain [dBic]
Vertical plane
7.1 MHz
Support line to tree
2.23 m
0.14 m
2.23 m
4.60 m
7.37 m
2.23 m
2.23 m
7.37 m
2.5 cm
Fishing rod
1 mm insulated wire
Support line
12 m
10.72 m RG58
10.72 m RG58
Relaybox
50 ohm coax
http://www.qsl.net/va3iul

278 - Spitwire Antenna for 40m


Spitwire for 7 MHz.
1 mm insulated wire
Support lines
35 cm
Resonans:
Dir. = 7,705 MHz
Refl. = 7,321 MHz
1382 cm
1382 cm
900 cm
Loop on radiator
C = 340 pF
L = 13 varv
l = 30 mm
d = 25 mm
127 cm
468 cm
Switch
50 ohms coax
468 cm
127 cm
Switch
Alt. matching
300 cm
Radiator
Earthpole and/pr 10,4 m radials
C
L
90 cm RG58 (120 pF)
Plastic box
Balun 4:1
Pole and/or 10,4 m radials
50 ohm coax
Balun 4:1 backwards
http://www.qsl.net/va3iul

279 - Fork Antenna for 40m


Fork atenna for 7 MHz
Connected to tree
Connected to tree
F/B = 25-30 dB
515 cm
Rad
Plastic box
Gain
Dir
C1
Refl
C2
C3
1:6 balun
716 cm
1231 cm
1231 cm
Condenser C3 33 pF
Condenser C1 120 pF
Condenser C2 6,6 pF
1 mm insu-lated wire
Support lines
424 cm
638 cm
2 m
SO239
Choke made of quarterwave transformer (704 cm RG59).
Bamboo pole
Ground
50 ohm coax
Diagram
http://www.qsl.net/va3iul

280 - Veebeam Antenna 3dB-Gain for All Bands


Veebeam antenna
2 mm open copperwire
70 degrees angle
43 m
3-4 dB gain
43 m
600 ohm ladder
35 cm
7,5 cm spaced bamboo pieces
1 mm insulated wire
http://www.qsl.net/va3iul

281 - Vertical Moxon Antenna for 10m


Vertical Moxon for 10 meters
72 cm
59 cm
15 cm
146 cm
386 cm
A
2 m
1 mm insulated cu-wire
Fishing rod
Glassfibermast
Matching unit
50 ohm coax
Tot-gain [dBi]
28.3 MHz
Vertical plane
0 Z
-15
15
-30
30
-45
45
-60
60
-75
-90
90
XY
-5
-2
-1
-5
-10
-15
-25
70 dg
4.71 dB
bw: 25 dg
fb: 26.9 dB
Gain = 2.5 dBd
F/B = 25 dB
To antenna (A)
L
C
L = 3.25 μH
14 turns 1 mm (77 cm long) Cu-wire on T-200 core. Link is 3 turns Cu-wire on cold side (red wire).
C = 9,5 cm 50 ohm coax
http://www.qsl.net/va3iul

---

282 - Half-Square Antenna for 30m


Half Square for 10 MHz
Alternative matching
2 turns from cold end
Support line
Spring
Support line
1438 cm
Antenna
15,5 turns
1 mm Cu-wire
on 5 cm tube,
5,7 cm long
(7,3 μH)
5 pieces
of 7 cm
RG213
(35 pF)
719 cm
719 cm
4 turns
Coax
Matching unit
Ground rod
450 pF
Bamboo pole
Ground rod
50 ohm coax
1mm insulated wire
Support lines
http://www.qsl.net/va3iul

---

283 - Rotatable Vertical Delta Loop for 20m


Rotatable deltaloop for 14 MHz
Swivel
7.25 m
7.25 m
7.25 m
6.28 m
0.87 m
1.5 m
3.51 m 75 ohm coax
6 m
50 ohm coax to TX
1 mm insulated wire
Fishing rod
Bamboo
Support lines

http://www.qsl.net/va3iul

---

284 - Mini-Horse Antenna 10dB-Gain for 40m-to-2m


MH-Antenna
Gain = 10 dB
F/B = 20 dB
Units = cm
2A
B
H
L
B
F
F
C
C
D
D
A
A
G
G
E
E
50 ohm coax
2A
1 mm insulated wire
Fishing rod
Support lines

Freq	A	B	C	D	E	F	G	H	L
144	36	12	9	4.5	18	12	16.5	42	41.5
50.1	102.5	33	27	13.5	51	33	46.5	120	119
28.3	182	58	48	24	91	58	82	212	211
24.92	206	65	54	27	102	66	93	240	238
21.2	243	77	64	32	121	77	109	282	281
18.1	285	91	74	37	141	91	128	330	329
14.2	364	116	96	48	181	116	164	424	421
10.1	513	164	136	68	256	164	232	600	594
7.1	728	232	192	96	362	232	328	848	842

http://www.qsl.net/va3iul

---

285 - Compact Moxon Antenna 5dB-Gain for 40m


7 MHz Compact Moxon
moxon7MHz.out
7 7.01 7.02 7.03 7.04 7.05 7.06 7.07 7.08 7.09 7.1 MHz
Vertical plane
15.22 m
2.45 m
2.45 m
4.6 m
1.93 m
1.93 m
7.61 m
7.61 m
Gain = 5 dB
F/B = 13 dB
50 ohm coax
12 m
Fishing rod
1 mm insulated wire
Support lines

http://www.qsl.net/va3iul

286 - Two Elements Sloping Delta Loop 8dB-Gain for 10m


2 el sloping Delta loop for 28.3 MHz
Ga : 10.41 dBi = 0 dB (Horizontal polarization)
F/B: -7.90 dB; Rear: Azim. 120 dg, Elev. 60 dg
Freq: 28.300 MHz
Support line 27 cm
1.74 m RG59
75 ohm coax
2.3 m
2.5 m
2.82 m
2.82 m
50 ohm coax
From side
5 m
8 dBd
F/B = 8 dB
4.0 m
4.0 m
4.0 m
4.0 m
3.54 m
3.77 m
3.54 m
3.77 m
Coax connected
to radiator
Mast
Z = 150 ohm
From above
1 mm cu wire
4 fishing rod 2.82 m long
Mast
Support line
http://www.qsl.net/va3iul

---

287 - Two Elements Phased Vertical Antenna 3dB-Gain for 40m


2 el phased vertical for 40 meters
Tot-gain [dBi]
7.1 MHz
Vertical plane
To tree
To tree
10.5 m
10.5 m
10.1 m
L1 = 7 m 75 ohm coax
L2 = 7 m 75 ohm coax
L3 = 7 m 50 ohm coax
1 mm insulated wire
Support line
10.5 m
10.5 m
10.5 m
10.5 m
L1
L3
2 m
0.2 m
Coax to TX
L2
http://www.qsl.net/va3iul

References:

Antenna Toolkit - J. Carr
Practical Antenna Handbook - J. Carr
More Antenna Classics - C. Hutchinson
Amateur Radio Techniques - P. Hawker
The Radio Handbook - W. Orr (editor), 15th edition
The Radio Antenna Handbook - Engineering Staff of "Radio"
Jones Antenna Handbook - Frank C. Jones
SM0DTK - http://www.sm0dtk.se/antennas.htm
ARRL Antenna Handbook 1990-2007
ARRL Handbook 1937-2009
ARRL Antenna Compendium
73 Magazine 1970-2002
Funkamateur Magazine 1990-2011
RSGB Handbook - 2007 - 2010
QST Magazine - 1980 - 2010
Ham Radio Magazine - 1969 - 1990
Radio-Electronics Magazine - 1986 - 1990

home: http://www.qsl.net/va3iul

Live Traffic Feed

Watch Live | Get FEEDJIT

Richmond, California, United States arrived 0 secs ago.

United Kingdom arrived 2 mins ago.

Kundan, Kashmir, India arrived 3 mins ago.

San Francisco, California, United States arrived 9 mins ago.

Rostock, Mecklenburg-Vorpommern, Germany arrived 13 mins ago.

Russia arrived 16 mins ago.

Abu Dhabi, United Arab Emirates arrived 32 mins ago.

United States arrived 35 mins ago.

Menlo Park, California, United States arrived 58 mins ago.

Québec, Canada arrived 59 mins ago.

TAB
ELECTRONICS

PRACTICAL ANTENNA HANDBOOK

Fourth Edition



Joseph J. Carr

Copyrighted Material

Practical Antenna Handbook

Other Books by Joseph J. Carr

DC Power Supplies
Old Time Radios! Restoration and Repair
Secrets of RF Circuit Design

Practical Antenna Handbook

Fourth Edition

Joseph J. Carr

McGraw-Hill
New York Chicago San Francisco Lisbon London
Madrid Mexico City Milan New Delhi San Juan Seoul
Singapore Sydney Toronto

McGraw-Hill

A Division of The McGraw-Hill Companies

Copyright ©2001 by The McGraw-Hill Companies, Inc. All rights reserved. Manufactured in the United States of America. Except as permitted under the United States Copyright Act of 1976, no part of this publication may be reproduced or distributed in any form or by any means, or stored in a database or retrieval system, without the prior written permission of the publisher.

0-07-138931-8
The material in this eBook also appears in the print version of this title: 0-07-137435-3.

All trademarks are trademarks of their respective owners. Rather than put a trademark symbol after every occurrence of a trademarked name, we use names in an editorial fashion only, and to the benefit of the trademark owner, with no intention of infringement of the trademark. Where such designations appear in this book, they have been printed with initial caps.

McGraw-Hill eBooks are available at special quantity discounts to use as premiums and sales promotions, or for use in corporate training programs. For more information, please contact George Hoare, Special Sales, at george_hoare@mcgraw-hill.com or (212) 904-4069.

TERMS OF USE

This is a copyrighted work and The McGraw-Hill Companies, Inc. (“McGraw-Hill”) and its licensors reserve all rights in and to the work. Use of this work is subject to these terms. Except as permitted under the Copyright Act of 1976 and the right to store and retrieve one copy of the work, you may not decompile, disassemble, reverse engineer, reproduce, modify, create derivative works based upon, transmit, distribute, disseminate, sell, publish or sublicense the work or any part of it without McGraw-Hills prior consent. You may use the work for your own noncommercial and personal use; any other use of the work is strictly prohibited. Your right to use the work may be terminated if you fail to comply with these terms.

THE WORK IS PROVIDED “AS IS.” McGRAW-HILL AND ITS LICENSORS MAKE NO GUARANTEES OR WARRANTIES AS TO THE ACCURACY, ADEQUACY OR COMPLETENESS OF OR RESULTS TO BE OBTAINED FROM USING THE WORK, INCLUDING ANY INFORMATION THAT CAN BE ACCESSED THROUGH THE WORK VIA HYPERLINK OR OTHERWISE, AND EXPRESSLY DISCLAIM ANY WARRANTY, EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO IMPLIED WARRANTIES OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE. McGraw-Hill and its licensors do not warrant or guarantee that the functions contained in the work will meet your requirements or that its operation will be uninterrupted or error free. Neither McGraw-Hill nor its licensors shall be liable to you or anyone else for any inaccuracy, error or omission, regardless of cause, in the work or for any damages resulting therefrom. McGraw-Hill has no responsibility for the content of any information accessed through the work. Under no circumstances shall McGraw-Hill and/or its licensors be liable for any indirect, incidental, special, punitive, consequential or similar damages that result from the use of or inability to use the work, even if any of them has been advised of the possibility of such damages. This limitation of liability shall apply to any claim or cause whatsoever whether such claim or cause arises in contract, tort or otherwise.

DOI: 10.1036/0071389318

Dedication

Dedicated in memoriam to Johnnie Harper Thorne, K4NFU:
a friend and colleague for nearly 30 years who is sorely missed.
Johnnie was a genius who knew some real smoke about antennas.
Killed by a drunk driver. . .

From the Publisher

The fourth edition of this book is published in memory of Joe Carr who passed away shortly after completing his manuscript. Joe was a valuable member of the McGraw-Hill family of authors and the electronics community as a whole. He will be missed by us all.

Scott L. Grillo
Editor-in-Chief

This page intentionally left blank

Contents

Introduction to the Fourth Edition *ix*

1 Introduction to Radio Broadcasting and Communications *1*

2 Radio-wave Propagation *5*

3 Transmission Lines *59*

4 The Smith Chart *95*

5 Fundamentals of Radio Antennas *123*

6 High-Frequency Dipole and Other Doublet Antennas *141*

7 Vertically Polarized HF Antennas *173*

8 Multiband and Tunable-Wire Antennas *203*

9 Longwire Directional Antennas *213*

10 Hidden and Limited-Space Antennas *231*

11 Directional Phased Vertical Antennas *245*

12 Directional Beam Antennas *255*

13 Antennas for Shortwave Reception *271*

14 Large Wire Loop Antennas *287*

15 Small Loop Receiving Antennas *299*

16 Small Transmitting Loop Antennas *319*

17 Antenna Modeling Software *327*

18 VHF/UHF Transmitting and Receiving Antennas *339*

19 Microwave Waveguides and Antennas *369*

20 Antenna Noise Temperature *417*

21 Antennas for Radio Astronomy *421*

22 Adjusting, Installing, and Troubleshooting Antennas and Transmission Lines *433*

23 Antennas for Radio Direction Finding (RDF) *439*

24 Impedence Matching in Antenna Systems *457*

25 Mobile, Emergency, Portable, and Marine Antennas *479*

26 Antennas for Low-Frequency Operation *501*

27 Measurement and Adjustment Techniques *515*

28 General Antenna Mechanical Construction Techniques *543*

29 Grounding the Antenna: What Is a Good Ground? *573*

Index *583*

McGraw-Hill Terms of Use

Introduction to the fourth edition

It was with great pleasure that I wrote this fourth edition of *Practical Antenna Handbook*. The original intent when the first edition was planned was to provide the reader with a practical, yet theoretical, book that could be used with only a minimal effort to actually design and install radio antennas. It was assumed that the readership would possess a wide range of levels of antenna sophistication, from the novice "newbie" to the professional engineer. That assumption proved to be correct as I have received letters from a wide variety of people.

The success of the three previous editions of *Practical Antenna Handbook* has been most gratifying. Clerks in radio stores told me that this book was outselling other titles 2:1. They confirmed that the types of people who buy the book meet the profile above. It was with surprise and delight that I noted that clerks in one radio store could cite the McGraw-Hill catalog number from memory, when they could not do that for other antenna books.

While the sales are deeply appreciated (they are an honor), there was one comment that stood out. The salesman at one radio store introduced me to an instructor from a U.S. Government communications school. He typically bought twenty copies of *Practical Antenna Handbook* at a time for use by his students in a training class. He told me that the reason why he selected my book over others was "...it's the *only book on the market* that people can give to a secretary, or clerk-typist, and expect them to be able to put up a working half-wavelength dipole two hours later." And, he stated, in his business that could literally happen any time.

Antennas have changed a lot over the years. Figure I-1 shows how antennas were between 1913 and 1940. This facility was the first U.S. Navy radio station (NAA) in Arlington, VA.[1] Those two 600- and 400-ft towers were taken down in 1940 to make room for National Airport (Washington, D.C.). The towers were reassembled in Annapolis, MD, where they lasted until recently.

Antenna technology has changed since 1940. In preparing this fourth edition of *Practical Antenna Handbook* all previous material was reviewed for accuracy and relevance. Additional material was added for the following topics:

- Wire antenna construction methods
- Antenna modeling software (miniNEC, WinNEC, and EZNEC for Windows)
- Antenna noise temperature
- Antennas for radio astronomy
- Antennas for Radio Direction Finding

I hope that you find this fourth edition as useful as the previous three editions. And thank you very much for honoring me by spending your hard-earned money on my book.

Joseph J. Carr, MSEE

---

[1] The NAA callsign has since been reassigned to the VLF station at Cutler, ME.



I-1 Massive antenna towers at Navy “Radio Arlington” (1913-1940). (Courtesy of the NAA.)

This page intentionally left blank

1
CHAPTER

Introduction to radio broadcasting and communications

RADIO BROADCASTING AND COMMUNICATIONS SEEMS TO HOLD A STRANGE KIND OF magical allure that attracts a wide variety of people and holds them for years. There is something fascinating about the ability to project yourself over vast intercontinental distances.

Radio communications have been with us now for the entire twentieth century and into the twenty-first. Experiments are on record as early as 1867, and by the turn of the century "wireless telegraphy" (as radio was called then) sparked the imaginations of countless people across the world. Radio communications began in earnest, however, when Guglielmo Marconi successfully demonstrated wireless telegraphy as a commercially viable entity. The "wireless" aspect to radio so radically changed communications that the word is still used to denote radio communications in many countries of the world. Marconi made a big leap to international fame on a cold December day in 1903, when he and a team of colleagues successfully demonstrated transatlantic wireless telegraphy. Until that time, wireless was a neighborhood—or crosstown at best—endeavor that was of limited usefulness. Of course, ships close to shore, or each other, could summon aid in times of emergency, but the ability to communicate over truly long distances was absent. All that changed on that fateful day in Newfoundland when Marconi heard the Morse letter "S" tickle his ears.

Wireless telegraphy was pressed into service by shipping companies because it immediately provided an element of safety that was missing in the prewireless days. Indeed, a ship that sank, leaving its crew and passengers afloat on a forbidding sea, was alone. Any survivors often succumbed to the elements before a chance encounter with a rescue vessel. Some early shipping companies advertised that their ships were safer because of wireless aboard. It was not until 1909, however, that wireless telegraphy proved its usefulness on the high seas. Two ships collided in the foggy Atlantic Ocean and were sinking. All passengers and crew members of both ships were in imminent danger of death in the icy waters. But radio operator Jack

Copyright 2001 - the McGraw-Hill Companies

Binns became the first man in history to send out a maritime distress call. There is some debate over which distress call Binns transmitted, but one thing is certain: It was not “SOS” (today’s distress call), because SOS was not adopted until later. Binns probably transmitted either “CQD” or “CQE,” both of which were recognized in those days before standardization. Regardless of which call was sent, however, it was received and relayed from ship to ship, allowing another vessel to come to the aid of the stricken pair of ships.

All radio prior to about 1916 was carried on via telegraphy (i.e., the on-off keying of a radio signal in the Morse code). But in 1916 some more magic happened. On a little hill in Arlington, Virginia, on a site that now overlooks the Pentagon and the U.S. Marine Corps base called *Henderson Hall*, there were (and still are) a pair of two-story brick buildings housing the naval radio station NAA (callsign since reassigned to the VLF station at Cutler, ME). On a night in 1916, radio operators and monitors up and down the Atlantic seaboard—from the midwest to the coast and out to sea for hundreds of miles—heard something that must have startled them out of their wits, for crackling out of the “ether,” amidst the whining of Alexanderson alternators and “ZZZCHHT” of spark-gap transmitters, came a new sound—a human voice. Engineers and scientists at the Naval Research Laboratory had transmitted the first practical amplitude-modulated (AM) radio signal. Earlier attempts, prior to 1910, had been successful as scientific experiments, but they did not use commercially viable equipment.

Although radio activity in the early years was unregulated and chaotic, today it is quite heavily regulated. Order was brought to the bands (don’t laugh, ye who tune the shortwaves) that was lacking before. Internationally radio is regulated by the International Telecommunications Union (ITU) in Geneva, Switzerland through the treaties arising from World Administrative Radio Conferences (WARC) held every 10 to 15 years. In the United States, radio communications are regulated by the Federal Communications Commission (FCC), headquartered in Washington, D.C.

Amateur radio has grown from a few thousand “hams” prior to World War I to more than 900,000 today, about one-third of them in the United States. Amateur operators were ordered off the air during World War I, and almost did not make a comeback after the war. There were, by that time, many powerful commercial interests that greedily coveted the frequencies used by amateurs, and they almost succeeded in keeping postwar amateurs off the air. But the amateurs won the dispute, at least partially. In those days, it was the frequencies with wavelengths longer than 200 m (i.e., 20 to 1500 kHz) that were valuable for communications.

The cynical attitude attributed to the commercial interests regarding amateurs was, “put ’em on 200 meters and below . . . they’ll never get out of their backyards there!” But there was a surprise in store for those commercial operators, because the wavelengths shorter than 200 m are in the high-frequency region that we now call “shortwaves.” Today, the shortwaves are well-known for their ability to communicate over transcontinental distances, but in 1919 that ability was not suspected.

I once heard an anecdote from an amateur operator “who was there.” In the summer of 1921 this man owned a large, beautiful wire “flattop” antenna array for frequencies close to 200 m on his family’s farm in southwestern Virginia. Using those frequencies he was used to communicating several hundred miles into eastern Ohio and down to the Carolinas. But, in September 1921 he went to college to study electrical engineering at the University of Virginia in Charlottesville. When he returned home for Thanksgiving he noticed that his younger brother had replaced the long flattop array with a short dipole antenna. He was furious, but managed through great effort to contain the anger until after dinner. Confronting his brother over the incredible sacrilege, he was told that they no longer used 150 to 200 m, but rather were using 40 m instead. Everyone "knew" that 40 m was useless for communications over more than a few blocks, so (undoubtedly fuming) the guy took a turn at the key. He sent out a "CQ" (general call) and was answered by a station with a callsign like "8XX." Thinking that the other station was in the 8th U.S. call district (WV, OH, MI) he asked him to relay a message to a college buddy in Cincinnati, OH. The other station replied in the affirmative, but suggested that ". . . you are in a better position to reach Cincinnati than me, I am *FRENCH* 8XX." (Callsigns in 1921 did not have national prefixes that are used today.) The age of international amateur communications had arrived! And with it came a new problem—the national identifiers in call signs became necessary (which is why American call signs begin with K, W, or N).

During the 1930s, radio communications and broadcasting spread like wildfire as technology and techniques improved. World War II became the first war to be fought with extensive electronics. Immediately prior to the war, the British developed a new weapon called RADAR (radio detection and ranging; now spelled radar). This tool allowed them to see and be forewarned of German aircraft streaming across the English Channel to strike targets in the United Kingdom. The German planes were guided by (then sophisticated) wireless highways in the sky, while British fighters defended the home island by radio vectoring from ground controllers. With night fighters equipped with the first "centimetric" (i.e., microwave) radar, the Royal Air Force was able to strike the invaders accurately—even at night. The first kill occurred one dark, foggy, moonless night when a *Beaufighter* closed on a spot in the sky where the radar in the belly of the plane said an enemy plane was flying. Briefly thinking he saw a form in the fog, the pilot cut loose a burst from his quad mount of 20-mm guns slung in the former bomb bay. Nothing. Thinking that the new toy had failed, the pilot returned to base—only to be told that ground observers had reported that a German *Heinkle* bomber fell from the overcast sky at the exact spot where the pilot had his ghostly encounter.

Radio, television, radar, and a wide variety of services, are available today under the general rubric "radio communications and broadcasting." Homeowners, and other nonprofessionals in radio, can own a receiver system in their backyard that picks up television and radio signals from satellites in geosynchronous orbit 23,000 mi out in space. Amateur operators are able to communicate worldwide on low power, and have even launched their own "OSCAR" satellites.

Some people had written off the HF radio spectrum in recent years, citing satellite technology as the reason. But the no-code license for amateur radio operators, which does not carry HF privileges, has proven to be a stepping stone to higher-class licenses, which do. Also, the shortwave broadcasting market received a tremendous boost during the Gulf War. When the troops of *Operation Desert Shield* and *Desert Storm* were assembling to take back Kuwait from the Iraqis, the sales of shortwave receivers jumped dramatically. And, following January 16, 1991, when the forces started pouring across the border into the actual fight, the sales skyrocketed out of sight. One dealer told me that he couldn't keep receivers in stock, and that he had sold out most models. That interest seems to have matured into long-term interest on the part of a significant number of listeners and new ham operators.

The antenna is arguably one of the most important parts of the receiving and/or transmitting station (Fig. 1-1). That is what this book is all about.

1-1 This AM/FM broadcast antenna tower bristles with two-way antennas.

2
CHAPTER
Radio-wave propagation

THE PROPAGATION OF RADIO SIGNALS IS NOT THE SIMPLE MATTER THAT IT SEEMS AT first glance. Intuitively, radio signal propagation seems similar to light propagation; after all, light and radio signals are both electromagnetic waves. But simple inverse square law predictions, based on the optics of visible light, fall down radically at radio frequencies because other factors come into play. In the microwave region of the spectrum, the differences are more profound because atmospheric pressure and water vapor content become more important than for light. For similar reasons, the properties of microwave propagation differ from lower VHF and HF propagation. In the HF region, solar ionization of the upper reaches of the atmosphere causes the kind of effects that lead to long-distance "skip" communications and intercontinental broadcasting. This chapter examines radio propagation phenomena so that you have a better understanding of what an antenna is used for and what parameters are important to ensure the propagation results that you desire.

Radio waves

Although today it is well recognized that radio signals travel in a wave-like manner, that fact was not always so clear. It was well known in the first half of the nineteenth century that wires carrying electrical currents produced an *induction field* surrounding the wire, which is capable of causing action over short distances. It was also known that this induction field is a magnetic field, and that knowledge formed the basis for electrical motors. In 1887, physicist Heinrich Hertz demonstrated that radio signals were *electromagnetic waves*, like light. Like the induction field, the electromagnetic wave is created by an electrical current moving in a conductor (e.g., a wire). Unlike the induction field, however, the *radiated field* leaves the conductor and propagates through space as an electromagnetic wave.

Copyright 2001 - the McGraw-Hill Companies

The *propagation* of waves is easily seen in the "water analogy." Although not a perfect match to radio waves, it serves to illustrate the point. Figure 2-1 shows a body of water into which a ball is dropped (Fig. 2-1A). When the ball hits the water (Fig. 2-1B), it displaces water at its point of impact, and pushes a leading wall of water away from itself. The ball continues to sink and the wave propagates away from it until the energy is dissipated. Although Fig. 2-1 shows the action in only one dimension (a side view), the actual waves propagate outward in all directions, forming concentric circles when viewed from above.

The wave produced by a dropped ball is not continuous, but rather is *damped* (i.e., it will reduce in amplitude on successive crests until the energy is dissipated and the wave ceases to exist). But to make the analogy to radio waves more realistic, the wave must exist in a continuous fashion. Figure 2-2 shows how this is done: a ball is dipped up and down in a rhythmic, or cyclic manner, successively rein-


Falling object
Surface of water
A
Leading wave forms at instant object strikes water
B
Spray
Leading wave moves radially outward
C
Point of original disturbance
A
B
D

Notes: A Amplitude of leading wave
B Corresponds to 1 cycle of oscillation

2-1 A ball dropped into water generates a wavefront that spreads out from the point of original disturbances.

forcing new wave crests on each dip. The waves continue to radiate outward as long as the ball continues to oscillate up and down. The result is a *continuous wave train*.

There are two related properties of all waves that are important to radio waves as well: *frequency* (*f*) and *wavelength* (λ). The frequency is the number of oscillations (or cycles) per unit of time. In radio waves, the unit of time is the second, so frequency is an expression of the number of *cycles per second* (*cps*). If the period of time required for the leading wave to travel from point "A" to "B" is one second (1 s), and there are two complete wave cycles in that space, then the frequency of the wave created by the oscillating ball is 2 cps.

At one time, radio frequencies (along with the frequencies of other electrical and acoustical waves) were expressed in cps, but in honor of Heinrich Hertz, the unit was renamed the hertz (Hz) many years ago. Because the units are equal (1 Hz = 1 cps), the wave in Fig. 2-2 has a frequency of 2 Hz.

Because radio frequencies are so high, the frequency is usually expressed in kilohertz (kHz—1000s of Hz) and megahertz (MHz—1,000,000s of Hz). Thus, the frequency of a station operating in the middle of the AM broadcasting band can be properly expressed as 1,000,000 Hz, or 1000 kHz, or 1 MHz, all of which are equivalent to each other. Radio dials in North America are usually calibrated in kHz or MHz. In Europe and the rest of the world, on the other hand, it is not uncommon to find radio dials calibrated in meters, the unit of wavelength, as well as in frequency. In most equations used in radio antenna design, the proper units are hertz, kilohertz, and megahertz.



2-2 Bobbing ball on a string demonstrates continuous wave generation action.

The *wavelength* of any wave is the distance between like features on the waveform. In the case of Fig. 2-2, the wavelength (λ) is the distance between successive positive peaks. We could also measure the same distance between successive negative peaks, or between any two similar features on successive waves. In radio work, the wavelength of the signal is expressed in *meters or its subunits*.

The wavelength is proportional to the reciprocal of the frequency. The wavelength of any wave is related to the frequency so that $f\lambda = v$, where f is the frequency in Hz, λ is the wavelength in meters, and v is the *velocity of propagation* in meters per second (m/s). Because radio waves propagate at the speed of light (which is also an electromagnetic wave), approximately 300,000,000 m/s in both free space and the earth's atmosphere, the lowercase letter c is used to represent velocity (rather than v), so you can rewrite this expression in the form

$$f_{\text{Hz}} = \frac{c}{\lambda_{\text{meters}}} = \frac{300{,}000{,}000}{\lambda_{\text{meters}}} \qquad \textbf{[2.1]}$$

These equations are sometimes abbreviated for use with the units kHz and MHz:

$$F_{\text{kHz}} = \frac{300{,}000}{\lambda_{\text{meters}}} \qquad \textbf{[2.2]}$$

$$f_{\text{MHz}} = \frac{300}{\lambda_{\text{meters}}} \qquad \textbf{[2.3]}$$

You can get an idea of the order of length of these waves by solving Eq. 2.3 for several different frequencies: 100 kHz, 1 MHz (in the AM broadcast band), 10 MHz (in the shortwave bands), and 1000 MHz (microwave bands). If you work the equations, then you will find that these wavelengths are 3000 m (100 kHz), 300 m (1 MHz), 30 m (10 MHz), and 0.3 m, or 30 cm (1000 MHz). You can see from these numbers why 1 MHz is in what is called the *medium-wave band*, 10 MHz is in the *short wave band*, and 1,000 MHz is in the *microwave* ("very small" wave) band. At 100 kHz, which is 0.1 MHz, the wavelength is 3000 m, so this frequency is in the *long-wave band*.

The place where the water analogy falls down most profoundly is in the nature of the medium of propagation. Water waves move by moving water molecules; water is said to be the *medium* in which the wave propagates. At one time, scientists could not conceive of the "action at a distance" provided by radio waves, so they invented a hypothetical medium called *ether* (or *aether*) for propagating electromagnetic waves (such as radio waves and light). It was not until the late nineteenth century that American physicists Michaelson and Morley proved that the ether does not exist. Nonetheless, radio enthusiasts still refer to the "stuff" out of which radio waves arrive as the "ether." This terminology is merely an archaic, linguistic echo of the past.

The electromagnetic field: a brief review

A great deal of heavily mathematical material can be presented about electromagnetic waves. Indeed, developing Maxwell's equations is a complete field of study for specialists. In this section, you will not use this rigorous treatment because you can refer to engineering textbooks for that depth of information. The purpose here is to present a descriptive approach that is designed to present you with a basic understanding of the phenomena. The approach here is similar to the learning of a "conversational" foreign language, rather than undertaking a deep study of its grammar, syntax, and context. For those whose professional work routinely involves electromagnetic waves, this treatment is hopelessly simplistic. For that I make no apology, because it serves a greater audience. The goal here is to make you more comfortable when thinking about the propagation of electromagnetic fields in the radio portion of the electromagnetic spectrum.

Radio signals are *transverse electromagnetic* (TEM or EM) *waves* exactly like light, infrared (IR), and ultraviolet (UV), except for frequency. Radio waves have much lower frequencies than light, IR, or UV, hence they have much longer wavelengths. The TEM (EM) wave consists of two mutually perpendicular oscillating fields (see Fig. 2-3) traveling together in phase. One of the fields is an *electric field* and the other is a *magnetic field*.

Radio-wave intensity

The radio wave is *attenuated* (i.e. reduced in apparent power) as it propagates from the transmitter to the receiver. Although at some very high microwave frequencies, there is additional path loss as a result of the oxygen and water vapor content of the air. At other frequencies other losses exist. Radio waves at all frequencies suffer losses due to the *inverse square law*. Let's take a look at that phenomenon.

The electric field vector falls off in direct proportion to the distance traveled. The E field is measured in terms of volts per meter (V/m), or in the subunits millivolts per meter (mV/m) or microvolts per meter (μV/m). That is, if an E field of



2-3 Electromagnetic wave consists of right angle electric and magnetic fields.

10 V/m crosses your body from head to toe, and you are about 2 m tall, then an electrical voltage is generated of (2 m)×(10 V/m), or 20 V. The reduction of the E field is linearly related to distance (i.e., if the distance doubles the E-field voltage vector halves). Thus, a 100 mV/m E field that is measured 1 mi from the transmitter will be 50 mV/m at 2 mi.

The power in any electrical system is related to the voltage by the relationship

$$P = \frac{E^2}{R} \tag{2.4}$$

where

P is the power in watts (W)
R is the resistance in ohms (Ω)
E is the electrical potential in volts (V)

In the case of a radio wave, the R term is replaced with the impedance (Z) of free space, which is on the order of 377 Ω. If the E field intensity is, for example, 10 V/m, then the *power density* of the signal is

$$P = \frac{(10\ \text{V/m})^2}{377\ \Omega} = 0.265\ \text{W/m}^2 = 26.5\ \text{mW/m}^2 \tag{2.5}$$

The power density, measured in watts per square meter (W/m^2), or the subunits (e.g., mW/cm^2), falls off according to the square of the distance. This phenomenon is shown graphically in Fig. 2-4. Here, you can see a lamp emitting a light beam that falls on a surface (A), at distance L, with a given intensity. At another surface (B), that is $2L$ from the source, the same amount of energy is distributed over an area (B) that is twice as large as area A. Thus, the power density falls off according to $1/d^2$, where d is the difference in distance. This is called the *inverse square law*.

Isotropic sources

In dealing with both antenna theory and radio wave propagation, a theoretical construct called an *isotropic source* is sometimes used for the sake of comparison, and for simpler arithmetic. You will see the isotropic model several places in this book. An isotropic source assumes that the radiator (i.e., an "antenna") is a very tiny spherical source that radiates energy equally well in all directions. The radiation pattern is thus a sphere with the isotropic antenna at the center. Because a spherical source is uniform in all directions, and its geometry is easily determined mathematically, the signal intensities at all points can be calculated from basic geometric principles.

For the isotropic case, you can calculate the average power in the extended sphere from

$$P_{\text{av}} = \frac{P_t}{4\pi d^2} \tag{2.6}$$



2-4 As a wave propagates, it spreads out according to the inverse square law, i.e., the area of *B* is 4 times that of *A* because it is twice as far from the source.

where

P_{av} is the average power per unit area
P_t is the total power
d is the radius of the sphere in meters (i.e., the distance from the radiator to the point in question)

The *effective aperture* (A_e) of the receiving antenna relates to its ability to collect power from the EM wave and deliver it to the load. Although typically smaller than the surface area in real antennas, for the theoretical isotropic case $A_e = \lambda^2/4\pi$. The power delivered to the load is

$$P_L = P_{\text{av}} A_e \quad \textbf{[2.7]}$$

By combining the two previous equations, the power delivered to a load at distance d is given by

$$P_L = \frac{P_t \lambda^2}{(4\pi)^2 d^2} \quad \textbf{[2.8]}$$

where

P_L is the power to the load
λ is the wavelength (c/F) of the signal

From these expressions, there can then be derived an expression for ordinary path losses between an isotropic transmitter antenna and a receiver antenna:

$$L_{\text{dB}} = 10 \log \left(\frac{P_t}{P_L} \right) \quad \textbf{[2.9]}$$

or, by rearranging to account for individual terms:

$$L_{\mathrm{dB}} = [20 \log d] + [20 \log F_{\mathrm{MHz}}] + k \qquad \textbf{[2.10]}$$

where

L_{dB} is the path loss in decibels (dB)
d is the path length
F_{MHz} is frequency in megahertz (MHz)
k is a constant that depends on the units of d as follows:

$k = 32.4$ if d in kilometers
$= 36.58$ if d in statute miles
$= 37.80$ if d in nautical miles
$= -37.87$ if d in feet
$= -27.55$ if d in meters

The radiated sphere of energy gets ever larger as the wave propagates away from the isotropic source. If, at a great distance from the center, you take a look at a small slice of the advancing wavefront you can assume that it is essentially a flat plane, as in Fig. 2-5. This situation is analogous to the apparent flatness of the prairie, even though the surface of the earth is nearly spherical. You would be able to “see” the electric and magnetic field vectors at right angles to each other in the flat plane wavefront.

The *polarization* of an EM wave is, by definition, the *direction of the electric field*. Figure 2-6A shows vertical polarization, because the electric field is vertical with respect to the earth. If the fields were exchanged (as in Fig. 2-6B), then the EM wave would be horizontally polarized.

These designations are especially convenient because they also show the type of antenna used: vertical antennas produce vertically polarized signals, while hori-



2-5 When viewed as a plane, the fields appear at right angles to each other.



2-6 Wave polarization is determined by the direction of the electric field lines of force: (A) vertical polarized electromagnetic wave; (B) horizontally polarized wave.

zontal antennas produce horizontally polarized signals. At least one text erroneously states that antennas will not pick up signals of the opposite polarity. Such is not the case, especially in the high-frequency (HF) and lower very high-frequency (VHF) regions. At VHF, ultrahigh frequency (UHF), and microwave frequencies a loss of approximately 20 to 30 dB can be observed due to cross-polarization.

An EM wave travels at the speed of light, designated by the letter *c*, which is about 300,000,000 m/s (or 186,000 mi/s). To put this velocity in perspective, a radio signal originating on the sun's surface would reach earth in about 8 minutes. A terrestrial radio signal can travel around the earth seven times in one second. The velocity of the wave slows in dense media, but in air the speed is so close to the “free-space” value of *c*, that the same figures are used for both air and the near vacuum of outer space in practical problems. In pure water, which is much denser than air, the speed of radio signals is about one-ninth that of the free-space speed. This same phenomenon shows up in practical work in the form of the *velocity factor* (*V*) of transmission lines. In foam dielectric coaxial cable, for example, the value of *V* is 0.80, which means that the signal propagates along the line at a speed of 0.80*c*, or 80 percent of the speed of light.

This coverage of radio propagation considers the EM wave as a very narrow “ray” or “pencil beam” that does not diverge as it travels. That is, the ray remains the same width all along its path. This convention makes it easy to use ray tracing diagrams. Keep in mind, however, that the real situation, even when narrow-beamwidth microwave signals are used, is much more complicated. Real signals, after all, are sloppier than textbook examples: they are neither infinitesimally thin, nor nondivergent.

The earth’s atmosphere

The electromagnetic waves do not need an atmosphere in order to propagate, as you will undoubtedly realize from the fact that space vehicles can transmit radio signals back to earth in a near vacuum. But when a radio wave does propagate in the earth’s atmosphere, it interacts with the atmosphere, and its path of propagation is altered. A number of factors affect the interaction, but it is possible to break the atmosphere into several different categories according to their respective effects on radio signals.

The atmosphere, which consists largely of oxygen (O_2) and nitrogen (N) gases, is broken into three major zones: *troposphere*, *stratosphere*, and *ionosphere* (Fig. 2-7). The boundaries between these regions are not very well defined, and change both diurnally (over the course of a day) and seasonally.

The troposphere occupies the space between the earth’s surface and an altitude of 6 to 11 km (4 to 7 mi). The temperature of the air in the troposphere varies with altitude, becoming considerably lower at greater altitude compared with ground temperature. For example, a +10°C surface temperature could reduce to –55°C at the upper edges of the troposphere.

The stratosphere begins at the upper boundary of the troposphere (6 to 11 km), and extends up to the ionosphere (≈50 km). The stratosphere is called an *isothermal region* because the temperature in this region is somewhat constant, despite altitude changes.

The ionosphere begins at an altitude of about 50 km (31 mi) and extends up to approximately 300 km (186 mi). The ionosphere is a region of very thin atmosphere. Cosmic rays, electromagnetic radiation of various types (including ultraviolet light from the sun), and atomic particle radiation from space (most of these from the sun also), have sufficient energy to strip electrons away from the gas molecules of the atmosphere. These freed electrons are called *negative ions*, while the O_2 and N molecules that lost electrons are called *positive ions*. Because the density of the air is so low at those altitudes, the ions can travel long distances before neutralizing each other by recombining. Radio propagation on some bands varies markedly between daytime and nighttime because the sun keeps the level of ionization high during


Height in kilometers
350
300
250
200
150
100
50
25
Sea level
Height in miles
200
150
100
50
20
Sea level
Atomic particles
Particle radiation
Cosmic rays
X-rays
Barometric pressure
Nighttime short-wave reflection F2 region
Daytime short-wave reflection F1 region
0.000001 mm
E2 region
Broadcast-wave reflection E1 region
0.001 mm
Long-wave reflection D region
2 mm
Ozone layer
Stratosphere
Isothermal layer
Troposphere
760 mm
Ocean
Sial
Basaltic layer
Meteor trail
Ultraviolet light
High-frequency nighttime reflection
High-frequency radio waves (1,500-30,000 kHz)
Medium-frequency radio waves (500-1,500 kHz)
Low-frequency radio waves (20-500 kHz)
Temperature
−40°C
−55°C
−80°C
+10°C

2-7 Radio propagation in the ionosphere is affected by a number of different physical factors: cosmic rays, atomic particles, solar radiation.

daylight hours, but the ionization begins to fall off rapidly after sunset, altering the radio propagation characteristics after dark. The ionization does not occur at lower altitudes because the air density is such that the positive and negative ions are numerous and close together, so recombination occurs rapidly.

EM wave propagation phenomena

Because EM waves are waves, they behave in a wave-like manner. Figure 2-8 illustrates some of the wave behavior phenomena associated with light and radio waves: *reflection*, *refraction*, and *diffraction*. All three play roles in radio propagation.

Reflection and refraction are shown in Fig. 2-8A. Reflection occurs when a wave strikes a denser reflective medium, as when a light wave strikes a glass mirror. The incident wave (shown as a single ray) strikes the interface between less dense and more dense mediums at a certain *angle of incidence* (a_i), and is reflected at exactly the same angle (now called the *angle of reflection* (a_r). Because these angles are equal, a reflected radio signal can often be traced back to its origin.

Refraction occurs when the incident wave enters a region of different density, and thereby undergoes both a velocity change and a directional change. The amount and direction of the change are determined by the ratio of the densities between the two media. If Zone B is much different from Zone A, then bending is great. In radio



2-8A Reflection and refraction phenomena.

systems, the two media might be different layers of air with different densities. It is possible for both reflection and refraction to occur in the same system. Indeed, more than one form of refraction might be present. These topics will be covered in greater depth shortly.

Diffraction is shown in Fig. 2-8B. In this case, an advancing wavefront encounters an opaque object (e.g., a steel building). The shadow zone behind the building is not simply perpendicular to the wave, but takes on a cone shape as waves bend around the object. The "umbra region" (or diffraction zone) between the shadow zone ("cone of silence") and the direct propagation zone is a region of weak (but not zero) signal strength. In practical situations, signal strength in the cone of silence rarely reaches zero. A certain amount of reflected signals scattered from other sources will fill in the shadow a little bit. The degree of diffraction effect seen in any given case is a function of the wavelength of the signal, the size of the object, and its electromagnetic properties.

Propagation paths

There are four major propagation paths: *surface wave*, *space wave*, *tropospheric,* and *ionospheric*. The ionospheric path is important to medium-wave (MW) and HF propagation, but is not important to VHF, UHF, or microwave propagation. The space wave and surface wave are both *ground waves*, but they behave differently enough to warrant separate consideration. The surface wave travels in direct contact with the earth's surface and it suffers a severe frequency-dependent attenuation caused by absorption into the ground.

The space wave is also a ground-wave phenomenon, but it is radiated from an antenna many wavelengths above the surface. No part of the space wave normally travels in contact with the surface; VHF, UHF, and microwave signals are usually space waves. There are, however, two components of the space wave in many cases: *direct* and *reflected* (see Fig. 2-9).

The tropospheric wave is lumped with the direct space wave in some texts, but it has properties that actually make it different in practical situations. The troposphere



2-8B Diffraction phenomena.



2-9 Space wave propagation.

is the region of earth's atmosphere between the surface and the stratosphere, or about 4 to 7 mi above the surface. Thus, most forms of ground wave propagate in the troposphere. But because certain propagation phenomena (caused mostly by weather conditions) only occur at higher altitudes, tropospheric propagation should be differentiated from other forms of ground wave.

The ionosphere is the region of earth's atmosphere that is above the stratosphere. The peculiar feature of the ionosphere is that molecules of air gas (O_2 and N) can be ionized by stripping away electrons under the influence of solar radiation and certain other sources of energy. In the ionosphere, the air density is so low that ions can travel relatively long distances before recombining with oppositely charged ions to form electrically neutral atoms. As a result, the ionosphere remains ionized for long periods of the day—even after sunset. At lower altitudes, however, air density is greater and recombination thus occurs rapidly. At those altitudes, solar ionization diminishes to nearly zero immediately after sunset, or never achieves any significant levels even at local noon.

Ionization and recombination phenomena in the ionosphere add to the noise level experienced at VHF, UHF, and microwave frequencies. The properties of the ionosphere are important to microwave technology because of the noise contribution. In satellite communications, there are some additional transionospheric effects.

Ground-wave propagation

The *ground wave*, naturally enough, travels along the ground, or at least in close proximity to it. There are three basic forms of ground wave: *space wave*, *surface* *wave*, and *tropospheric wave*. The space wave does not actually touch the ground. As a result, space wave attenuation with distance in clear weather is about the same as in free space (except above about 10 GHz, where H_2O and O_2 absorption increases dramatically). Of course, above the VHF region, weather conditions add attenuation not found in outer space.

The surface wave is subject to the same attenuation factors as the space wave, but in addition it also suffers ground losses. These losses are caused by ohmic resistive losses in the conductive earth. In other words, the signal heats up the ground. Surface wave attenuation is a function of frequency, and it increases rapidly as frequency increases. Both of these forms of ground-wave communications are affected by the following factors: wavelength, height of both the receiving and transmitting antennas, distance between the antennas, and the terrain and weather along the transmission path. Figure 2-10 is a nomograph that can be used to calculate the line of sight distances in miles from a knowledge of the receiver and transmitter antenna heights. Similarly, Figs. 2-11A and 2-11B show power attenuation with frequency and distance (Fig. 2-11A) and power attenuation in terms of field intensity (Fig. 2-11B).

Ground-wave communications also suffer another difficulty, especially at VHF, UHF, and microwave frequencies. The space wave is like a surface wave, but it is radiated many wavelengths above the surface. It is made up of two components (see Fig. 2-9 again): the *direct* and *reflected* waves. If both of these components arrive at the receiving antenna, they will add algebraically to either increase or decrease signal strength. There is always a phase shift between the two components because the two signal paths have different lengths (i.e., D_1 is less than $D_2 + D_3$). In addition, there may possibly be a 180° (π radians) phase reversal at the point of reflection (especially if the incident signal is horizontally polarized), as in Fig. 2-12. The following general rules apply in these situations:

- A phase shift of an odd number of half wavelengths causes the components to add, increasing signal strength (*constructive interference*).
- A phase shift of an even number of half wavelengths causes the components to subtract (Fig. 2-12), thus reducing signal strength (*destructive interference*).
- Phase shifts other than half wavelength add or subtract according to relative polarity and amplitude.

You can characterize the loss of signal over path D_1 with a parametric term n that is defined as follows:

$$n = \frac{S_r}{S_f} \qquad \textbf{[2.11]}$$

where

n is the signal loss coefficient
S_r is the signal level at the receiver in the presence of a ground reflection component
S_f is the free-space signal strength over path D_1 if no reflection took place.



2-10 Nomograph showing the line-of-sight transmission distance as a function of receiving and transmitting antenna heights.



2-11A Power in a free-space field (normalized to 1 W).

You can calculate as follows:

$$n^2 = 4 \sin^2\left(\frac{2\pi h_t h_r}{\lambda D_1}\right) \qquad \textbf{[2.12]}$$

or

$$n = 2 \sin\left(\frac{2\pi h_t h_r}{\lambda D_1}\right) \qquad \textbf{[2.13]}$$

The reflected signal contains both amplitude change and phase change. The phase change is typically π radians (180°). The amplitude change is a function of frequency and the nature of the reflecting surface. The *reflection coefficient* can be characterized as

$$\gamma = pe^{j\phi} \qquad \textbf{[2.14]}$$



2-11B Relation of field strength to signal field power.



2-12 Out-of-phase waves cancel.

where

γ is the reflection coefficient
p is the amplitude change
ϕ is the phase change
j is the imaginary operator ($\sqrt{-1}$)

For smooth, high-reflectivity surfaces and a horizontally polarized microwave signal that has a shallow angle of incidence, the value of the reflection coefficient is close to –1.

The phase change of the reflected signal at the receiving antenna is at least π radians because of the reflection. Added to this change is an additional phase shift that is a function of the difference in path lengths. This phase shift can be expressed in terms of the two antenna heights and path length.

$$s = \pi + \left(\frac{4\pi h_t h_r}{\lambda D_1}\right) \qquad \textbf{[2.15]}$$

A category of reception problems called *multipath phenomena* exists because of interference between the direct and reflected components of the space wave. The form of multipath phenomena that is, perhaps, most familiar to many readers is ghosting in off-the-air television reception. Some multipath events are transitory in nature (as when an aircraft flies through the transmission path), while others are permanent (as when a large building, or hill, reflects the signal). In mobile communications, multipath phenomena are responsible for reception dead zones and "picket fencing." A *dead zone* exists when destructive interference between direct and reflected (or multiply reflected) waves drastically reduces signal strengths. This problem is most often noticed at VHF and above when the vehicle is stopped; and the solution is to move the antenna one-half wavelength (which at VHF and UHF is a matter of a few inches). *Picket fencing* occurs as a mobile unit moves through successive dead zones and signal enhancement (or normal) zones, and it sounds like a series of short noise bursts.

At VHF, UHF, and microwave frequencies, the space wave is limited to so-called line-of-sight distances. The horizon is theoretically the limit of communications distance, but the radio horizon is actually about 15 percent farther than the optical horizon (Fig. 2-13). This phenomenon is caused by refractive bending in the atmosphere around the curvature of the earth, and it makes the geometry of the situation look as if the earth's radius is $\frac{4}{3}$ the actual radius.

The refraction phenomenon occurs at VHF through microwave frequencies, but not in the visible light spectrum, because water and atmospheric pressure (which relates to the effects of atmospheric gases on microwave signals) become important contributors to the phenomenon. The *K factor* expresses the degree of curvature along any given path, while the *index of refraction n* measures the differential properties between adjacent zones of air.

The *K* factor, also called the *effective earth's radius factor*, is defined according to the relationship of two hypothetical spheres, both centered at the exact center of



2-13 Phenomenon by which "greater than line of sight" communications occurs.

the earth. The first sphere is the earth's surface, which has a radius r_o (3440 nmi or 6370 km). The second sphere is larger than the first by the curvature of the signal "ray path," and has a radius r. The value of K is approximately

$$K = \frac{r}{r_o} \tag{2.16}$$

A value of $K = 1$ indicates a straight path (Fig. 2-14); a value of $K > 1$ indicates a positively curved path (refraction); and a value of $K < 1$ indicates a negatively curved path (subrefraction). The actual value of K varies with local weather conditions, so one can expect variation not only between locations, but also seasonally. In the arctic regions, K varies approximately over the range 1.2 to 1.34. In the "lower 48" states of the United States, K varies from 1.25 to 1.9 during the summer months (especially in the south and southeast), and from 1.25 to 1.45 in the winter months. The index of refraction n can be defined in two ways, depending on the situation. When a signal passes across boundaries between adjacent regions of distinctly different properties (as occurs in temperature inversions, etc.), the index of refraction is the ratio of the signal velocities in the two regions. In a homogeneous region n can be expressed as the ratio of the free-space velocity c to the actual velocity in the atmosphere V:

$$n = \frac{c}{V} \tag{2.17}$$

At the surface, near sea level, under standard temperature and pressure conditions, the value of n is approximately 1.0003, and in homogeneous atmospheres it will decrease by 4×10^{-8} per mile of altitude. The units of n are a bit cumbersome in equations, so the UHF/microwave communities tend to use a derivative parameter, N, called the *refractivity of the atmosphere*:

$$N = (n - 1) \times 10^6 \tag{2.18}$$



2-14 Refraction changes path length.

The value of N tends to vary from about 280 to 320, and both n and N vary with altitude. In nonhomogeneous atmospheres (the usual case), these parameters will vary approximately linearly for several tenths of a kilometer. All but a few microwave relay systems can assume an approximately linear reduction of n and N with increasing altitude, although airborne radios and radars cannot. There are two methods for calculating N:

$$N = \left(\frac{77.6}{T}\right)\left(P + \frac{4810 e_s H_{\mathrm{rel}}}{T}\right) \tag{2.19}$$

and

$$N = \frac{77.6}{T}\left(\frac{3.73 \times 10^5 e_s}{T^2}\right) \tag{2.20}$$

where

P is the atmospheric pressure in millibars (1 torr = 1.3332 mbar)
T is temperature in kelvins
e_s is saturation vapor pressure of atmospheric water in millibars
H_{rel} is the relative humidity expressed as a decimal fraction (rather than a percentage)

Ray path curvature (K) can be expressed as a function of either n or N, provided that the assumption of a linear gradient d_n/d_h holds true:

$$K = \frac{1}{\left(1 + \frac{r_o d_n}{d_h}\right)} \tag{2.21}$$

or

$$K = \frac{1}{\left(1 + \frac{d_N/d_h}{157}\right)} \tag{2.22}$$

For the near-surface region, where d_n/d_h varies at about 3.9×10^{-8} m, the value of K is 1.33. For most terrestrial microwave paths, this value ($K = 4/3 = 1.33$) is called a *standard refraction*, and is used in calculations *in the absence of additional data*. For regions above the linear zone close to the surface, you can use another expression of refractivity:

$$N_a = N_s e^{-C_e(h_r - h_t)} \tag{2.23}$$

where

N_1 is the refractivity at 1 km altitude
h_r is the height of the receiver antenna
h_t is the height of the transmit antenna

$C_e = L_n(N_s/N_1)$
N_a is the refractivity at altitude
N_s is the refractivity at the earth's surface

For simple models close to the surface, you can use the geometry shown in Fig. 2-15. Distance d is a curved path along the surface of the earth. But because the earth's radius r_o is about 4000 statute miles, and it is thus very much larger than a practical antenna height h, you can simplify the model in Fig. 2-15A to that in Fig. 2-15B. The underlying assumption is that the earth has a radio radius equal to about $\frac{4}{3}$ ($K = 1.33$) of the actual physical radius of its surface.



2-15A Geometry for calculating radio distances.



2-15B Simplified geometry.

The value of distance d is found from the expression

$$d = \sqrt{2r_c h_{\text{ft}}} \quad \textbf{[2.24]}$$

where

d is the distance to the radio horizon in statute miles
r_o is the normalized radius of the earth
h_{ft} is the antenna height in feet

Accounting for all constant factors, the expression reduces to

$$d = 1.414\sqrt{h_{\text{ft}}} \quad \textbf{[2.25]}$$

all factors being the same as defined above.

Example 2-1 A radio tower has a UHF radio antenna that is mounted 150 feet above the surface of the earth. Calculate the radio horizon (in statute miles) for this system.

Solution:

$$\begin{aligned} d &= 1.414\ (h_t)t \\ &= (1.414)(150\text{ ft})^{1/2} \\ &= (1.414)(12.25) \\ &= 17.32\text{ mi} \end{aligned}$$

For other units of measurement:

$$d_{\text{nmi}} = 1.23\sqrt{h_{\text{ft}}}\quad \text{nmi} \quad \textbf{[2.26]}$$

and

$$d_{\text{km}} = 1.30\sqrt{h_{\text{ft}}}\quad \text{km} \quad \textbf{[2.27]}$$

Surface-wave communications The surface wave travels in direct contact with the earth's surface, and it suffers a severe frequency-dependent attenuation because of absorption by the ground.

The surface wave extends to considerable heights above the ground level, although its intensity drops off rapidly at the upper end. The surface wave is subject to the same attenuation factors as the space wave, but in addition, it also suffers ground losses. These losses are caused by ohmic resistive losses in the conductive earth, and to the dielectric properties of the earth. In other words, the signal heats up the ground. Horizontally polarized waves are not often used for surface wave communications because the earth tends to short-circuit the E-field component. On vertically polarized waves, however, the earth offers electrical resistance to the E-field and returns currents to following waves (Fig. 2-16). The conductivity of the soil determines how much energy is returned. Table 2-1 shows the typical conductivity values for several different forms of soil.



2-16 Distortion of vertically polarized electric field by lossy ground resistance.

Table 2-1. Sample soil conductivity values

Type of soil	Dielectric constant	Conductivity (siemens/meter)	Relative quality
Salt water	81	5	Best
Fresh water	80	0.001	Very poor
Pastoral hills	14–20	0.03–0.01	Very good
Marshy, wooded	12	0.0075	Average/poor
Rocky hills	12–14	10	Poor
Sandy	10	0.002	Poor
Cities	3–5	0.001	Very poor

The wavefront of a surface wave is tilted because of the losses in the ground that tend to retard the wavefront's bottom (also in Fig. 2-16). The tilt angle is a function of the frequency, as shown in Table 2-2.

Table 2-2. Tilt angle as a function of frequency

Frequency (kHz)	Tilt angle ratio	Earth/seawater (degrees)
20	2.07	4.3/2.08
200	104	13.4/0.13
2,000	64	32.3/0.5
20,000	25	35/1.38

Surface-wave attenuation is a function of frequency, and increases rapidly as frequency increases. For both forms of the ground wave, reception is affected by these factors: *wavelength, height* of both the receiving and transmitting antennas, *distance* between antennas, and both *terrain* and *weather* along the transmission path. In addition, the surface wave is affected by the ground losses in Table 2-1. Because of the ground loss effects, the surface wave is attenuated at a much faster rate than the inverse square law.

Ground-wave propagation frequency effects The frequency of a radio signal in large measure determines its surface-wave behavior. In the very low-frequency (VLF) band (<300 kHz), ground losses are small for vertically polarized signals, so medium-distance communications (up to several hundred miles) are possible. In the medium-wave band (300 to 3000 kHz, including the AM broadcast band), distances of 1000 mi are possible with regularity—especially at night. In the high-frequency (HF) band, ground losses are more considerable, so the surface-wave distance reduces drastically. It is possible, in the upper end of the HF band (3000 to 30,000 kHz) for surface-wave signals to die out within a few dozen miles. This phenomenon is often seen in the 15- and 10-m amateur radio bands, as well as the 11-m (27-MHz) Citizen's Band. Stations only 20 mi apart cannot communicate, but both can talk to a third station across the continent via ionospheric skip. Thus, the two stations close together must have a station more than 2000 mi away relay messages between them.

Tropospheric propagation The troposphere is the portion of the atmosphere between the surface of the earth and the stratosphere (or about 4 to 7 mi above the surface). Some older texts group tropospheric propagation with ground-wave propagation, but modern practice requires separate treatment. The older grouping overlooks certain common propagation phenomena that simply don't happen with space or surface waves.

Refraction is the mechanism for most tropospheric propagation phenomena. The dielectric properties of the air, which are set mostly by the moisture content (Fig. 2-17), are a primary factor in tropospheric refraction. Recall that refraction occurs in both light or radio-wave systems when the wave passes between mediums of differing density. Under that situation, the wave path will bend an amount proportional to the difference in density.

Two general situations are typically found—especially at UHF and microwave frequencies. First, because air density normally decreases with altitude, the top of a beam of radio waves typically travels slightly faster than the lower portion of the beam. As a result, those signals refract a small amount. Such propagation provides slightly longer surface distances than are normally expected from calculating the distance to the radio horizon. This phenomenon is called *simple refraction*, and was discussed in a preceding section.

A special case of refraction called *superrefraction* occurs in areas of the world where warmed land air goes out over a cooler sea (Fig. 2-18). Examples of such areas have deserts that are adjacent to a large body of water: the Gulf of Aden, the southern Mediterranean, and the Pacific Ocean off the coast of Baja California are examples. VHF/UHF/microwave communications up to 200 mi are reported in such areas.

The second form of refraction is weather-related. Called *ducting*, this form of propagation (Fig. 2-19) is actually a special case of superrefraction. Evaporation of sea water causes temperature inversion regions to form in the atmosphere—that is, layered air masses in which the air temperature is greater than in the layers below it. (*Note*: air temperature normally decreases with altitude, but at the boundary with an


Low dielectric constant
(low moisture content)
Direction of propagation
High dielectric constant
(high moisture content)
Surface of earth
A
High dielectric constant
Direction of propagation
Low dielectric constant
Surface of earth
B

2-17 Refraction in the troposphere.

inversion region, it increases.) The inversion layer forms a “duct” that acts like a waveguide. In Fig. 2-19, the distance D_1 is the normal “radio horizon” distance, and D_2 is the distance over which duct communications can occur.

Ducting allows long-distance communications from lower VHF through microwave frequencies, with 50 MHz being a lower practical limit and 10 GHz being an ill-defined upper limit. Airborne operators of radio, radar, and other electronic equipment can sometimes note ducting at even higher microwave frequencies.

Antenna placement is critical for ducting propagation. Both the receiving and transmitting antennas must be either (1) inside the duct physically (as in airborne cases) or (2) able to propagate at an angle such that the signal gets trapped inside the duct. The latter is a function of antenna radiation angle. Distances up to 2500 mi


High temp
Low temp
Refracted path
Direct path
Hot desert
Cold sea

2-18 Superrefraction phenomena.


Tropospheric wave
Temperature inversion zone
Space wave
h
D1
D2
Earth's surface

2-19 Ducting phenomenon.

or so are possible through ducting. Certain paths where frequent ducting occurs have been identified: the Great Lakes to the Atlantic seaboard; Newfoundland to the Canary Islands; across the Gulf of Mexico from Florida to Texas; Newfoundland to the Carolinas; California to Hawaii; and Ascension Island to Brazil.

Another condition is noted in the polar regions, where colder air from the land mass flows out over warmer seas (Fig. 2-20). Called *subrefraction*, this phenomena bends EM waves away from the earth's surface—thereby *reducing* the radio horizon by about 30 to 40 percent.



2-20 Subrefraction phenomena.

All tropospheric propagation that depends upon air-mass temperatures and humidity, shows diurnal (i.e., over the course of the day) variation caused by the local rising and setting of the sun. Distant signals may vary 20 dB in strength over a 24-hour period. These tropospheric phenomena explain how TV, FM broadcast, and other VHF signals can propagate great distances, especially along seacoast paths, at some times while being weak or nonexistent at others.

Diffraction phenomena Electromagnetic *waves* diffract when they encounter a radio-opaque object. The degree of diffraction, and the harm it causes, is frequency-related. Above 3 GHz, wavelengths are so small (approximately 10 cm) compared to object sizes that large attenuation of the signal occurs. In addition, beamwidths (a function of antenna size compared with wavelength) tend to be small enough above 3 GHz that blockage of propagation by obstacles is much greater.

Earlier in this chapter, large-scale diffraction around structures (such as buildings) was discussed. The view presented was from above, so it represented the horizontal plane. But there is also a diffraction phenomenon in the vertical plane. Terrain, or man-made objects, intervening in the path between UHF microwave stations (Fig. 2-21A) cause diffraction, and some signal attenuation. There is a minimum clearance required to prevent severe attenuation (up to 20 to 30 dB) from diffraction. Calculation of the required clearance comes from Huygens-Fresnel wave theory.

Consider Fig. 2-21B. A wave source A, which might be a transmitter antenna, transmits a wavefront to a destination C (receiver antenna). At any point along path A-C, you can look at the wavefront as a partial spherical surface (B_1-B_2) on which all wave rays have the same phase. This plane can be called an *isophase plane*. You can assume that the d_n/d_h refraction gradient over the height extent of the wavefront is small enough to be considered negligible.

Using ray tracing we see rays r_a incoming to plane [B_1-B_2], and rays r_b outgoing from plane [B_1-B_2]. The signal seen at C is the algebraic sum of all rays r_b. The signal pattern will have the form of an optical interference pattern with wave cancellation occurring between r_b waves that are a half-wavelength apart on [B_1-B_2]. The ray im-



2-21A Terrain masking of VHF and higher-frequency signals.

pact points on plane [B_1-B_2] form radii R_n called *Fresnel zones*. The lengths of the radii are a function of the frequency and the ratio of the distances D_1 and D_2 (see Fig. 2-21B). The general expression is

$$R_n = M\sqrt{\frac{N}{F_{\text{GHz}}}\left(\frac{D_1D_2}{D_1 + D_2}\right)} \qquad \textbf{[2.28]}$$

where

R_m is the radius of the nth Fresnel zone
F_{GHz} is the frequency in GHz
D_1 is the distance from the source to plane B_1-B_2
D_2 is the distance from destination to plane B_1-B_2
N is an integer (1, 2, 3, . . .)
M a constant of proportionality equal to

17.3 if R_m is in meters and D_1, D_2 are in kilometers and

72.1 if R_m is in feet and D_1, D_2 are in statute miles

If you first calculate the radius of the critical first Fresnel zone (R_1), then you can calculate the nth Fresnel zone from

$$R_n = R_1\sqrt{n} \qquad \textbf{[2.29]}$$

Example 2-2 Calculate the radius of the first Fresnel zone for a 2.5-GHz signal at a point that is 12 km from the source and 18 km from the destination.


Isophase spherical wave surface
B_1
γ_a
γ_b
A
S
C
B_2
D_1
D_2
$D_1 = A\text{-}S$
$D = S\text{-}C$
R_N
$R_{N\text{-}1}$
S
(Rotated view)

2-21B Fresnel zone geometry.

Solution:

$$R_1 = M\sqrt{\frac{N}{F_{\text{GHz}}}\left(\frac{D_1 D_2}{D_1 + D_2}\right)}$$

$$R_1 = (17.3)\ \sqrt{\frac{1}{2.5}\left(\frac{12 \times 18}{12 + 18}\right)}$$

$$R_t = (17.3)\sqrt{(0.4)\ (7.2)}$$

$$R_1 = (17.3)\ (2.88) = 29.4\ \text{m}$$

For most terrestrial microwave systems an obstacle clearance of $0.6R_1$ is required to prevent diffraction attenuation under most normal conditions. However, there are conditions in which the clearance zone should be more than one Fresnel zone.

Fading mechanisms Fading is defined as a reduction in amplitude caused by reduced received signal power, changes in phase or polarization, wave cancellation, or other related problems that are not caused by a change in the output power level or other parameters associated with either the transmitter or its antenna system. You would not ordinarily think that line-of-sight radio relay links would experience fading, but that is not true. Fading does, in fact, occur, and it can reach levels of 30 dB in some cases (20 dB is relatively common). In addition, fading phenomena in the VHF-and-up range can last several hours, with some periods being reported of several days in duration (although very rare). There are several mechanisms of fading, and these will be dealt with in this section. HF fading caused by ionospheric mechanisms will be covered later.

Any or all of the mechanisms shown in Fig. 2-22 can occur in a given system. In all cases, two or more signals arrive at the receiver antenna (R_x). Ray *A* represents the direct path signal that is, ideally, the only signal to reach the destination. But it is also possible that a signal, in an elevated layer or other atmospheric anomaly, will cause refraction or subrefraction of the wave creating a second component, *B*. If this second signal arrives out of phase with *A*, then fading will occur (signal reinforcement—



2-22 Multiple paths for signal to take between transmitter and receiver.

in phase—can also occur). It is also possible to see subrefraction fading, as in D. The classical multipath situation represented by ray C and its reflected component C' is also a source of fading.

These mechanisms are frequency-sensitive, so a possible countermeasure is to use *frequency diversity*. Hopping over a 5 percent frequency change will help eliminate fading in many cases. In cases where either system constraints, or local spectrum usage prevents a 5 percent delta (change), then try for at least 2 or 3 percent.

Over ocean areas or other large bodies of water there is a possibility of encountering fair weather surface ducting as a cause of fading. These ducts form in the mid latitudes, starting about 2 to 3 km from shore, up to heights of 10 to 20 mi; wind velocities are found in the 10 to 60 km/h range. The cause of the problem is a combination of power fading, due to the presence of the duct, and surface reflections (see Fig. 2-23). Power fading alone can occur when there is a superrefractive duct elevated above the surface. The duct has a tendency to act as a waveguide and focus the signal (Fig. 2-24). Although the duct shown is superrefractive, it is also possible to have a subrefractive duct.

Attenuation in weather Microwave communications above about 10 GHz suffer an increasingly severe attenuation because of water vapor and oxygen in the atmosphere. Figure 2-25 shows the standard attenuation in dB/km for microwave frequencies. Note that there are several strong peaks in an ever-increasing curve. Setting a system frequency in these regions will cause poor communications or will require a combination of more transmit power, better receiver sensitivity, and better antennas on receiving and transmitting locations. The curves shown in Fig. 2-25 assume certain standardizing conditions. Rain and other weather conditions can severely increase the attenuation of signals. In addition to attenuation, radar exhibits severe clutter problems when signals backscatter from rain cells.



2-23 Multihop interference.



2-24 Wave interference.

Ionospheric propagation

Now let's turn your attention to the phenomenon of skip communications. Ionospheric propagation is responsible for the ability to do intercontinental broadcasting and communications. Long-distance radio transmission is carried out on the high-frequency (HF) bands (3 to 30 MHz), also called the *shortwave* bands. These frequencies are used because of the phenomenon called *skip*. Under this type of propagation, the earth's ionosphere acts as though it is a "radio mirror." Although the actual phenomenon is based on refraction (not reflection, as is frequently believed), the appearance to the casual observer is that shortwave and low-VHF radio signals are reflected from the ionosphere. The actual situation is a little different.

The key lies in the fact that this radio mirror is produced by ionization of the upper atmosphere. The upper portion of the atmosphere is called the *ionosphere* because it tends to be easily ionized by solar and cosmic radiation phenomena. The reason for the ease with which that region (30 to 300 mi above the surface) ionizes, is that the air density is very low. Energy from the sun strips away electrons from the outer shells of oxygen and nitrogen molecules. The electrons become negative ions, while the remaining portion of the atom forms positive ions. Because the air is so rarified at those altitudes, those ions can travel great distances before recombining to form electrically neutral atoms again. As a result, the average ionization level remains high in that region.

Several sources of energy will cause ionization of the upper atomosphere. Cosmic radiation from outer space causes some degree of ionization, but the majority of ionization is caused by solar energy.

The role of cosmic radiation was noticed during World War II, when British radar operators discovered that the distance at which their equipment could detect German aircraft was dependent upon whether or not the Milky Way was above the horizon. Intergalactic radiation raised the background microwave noise level, thereby adversely affecting the signal-to-noise ratio.



2-25 Atmospheric absorption of radio signals at microwave frequencies.

Events on the surface of the sun sometimes cause the radio mirror to seem to be almost perfect, and this situation makes spectacular propagation possible. At other times, however, solar disturbances (Fig. 2-26A) disrupt radio communications for days at a time.

There are two principal forms of solar energy that affect shortwave communications: *electromagnetic radiation* and *charged solar particles*. Most of the radiation is above the visible spectrum, in the ultraviolet and x-ray/gamma-ray region of the spectrum. Because electromagnetic radiation travels at the speed of light, solar events that release radiation cause changes to the ionosphere about 8 minutes later. Charged particles, on the other hand, having a finite mass must travel at a considerably slower velocity. They require two or three days to reach earth.

Various sources of both radiation and particles exist on the sun. Solar flares can release huge amounts of both radiation and particles. These events are unpredictable and sporadic. Solar radiation also varies over an approximately 27-day period, which is the rotational period of the sun. The same source of radiation will face the earth once every 27 days, and so events tend to be somewhat repetitive.

Solar and galactic noise affect the reception of weak signals. Solar noise can also affect radio propagation and act as a harbinger of changes in propagation patterns. Solar noise can be demonstrated by using an ordinary radio receiver and a directional antenna, preferably operating in the VHF/UHF regions of the spectrum (150 to 152 MHz frequently is used). Aim the antenna at the sun on the horizon at either sunset or sunrise. A dramatic change in background noise will be noted as the sun slides across the horizon.

2-26A Solar event that can affect radio propagation on earth.

Sunspots A principal source of solar radiation, especially the periodic forms, is sunspots (Fig. 2-26B). Sunspots can be as large as 70,000 to 80,000 miles in diameter, and generally occur in clusters. The number of sunspots varies over a period of approximately 11 years, although the actual periods since 1750 (when records were first kept) have varied from 9 to 14 years. The sunspot number is reported daily as the statistically massaged *Zurich Smoothed Sunspot Number*, or *Wolf Number*. The number of sunspots greatly affects radio propagation via the ionosphere. The low was in the range of 60 (in 1907), and the high was about 200 (1958).

Another indicator of ionospheric propagation potential is the *solar flux index* (SFI). This measure is taken in the microwave region (wavelength of 10.2 cm, or 2.8 GHz), at 1700 UTC at Ottawa, Canada. The SFI is reported by the National Institute for Standards and Technology (NIST) radio stations WWV (Fort Collins, CO) and WWVH (Maui, Hawaii).

The ionosphere offers different properties that affect radio propagation at different times. Variations occur not only over the 11 year sunspot cycle, but also diurnally and seasonally. Obviously, if the sun affects propagation in a significant way, then differences between nighttime and daytime, and between summer and winter, must cause variations in the propagation phenomena observed.

The ionosphere is divided, for purposes of radio propagation studies, into various layers that have somewhat different properties. These layers are only well defined



2-26B Sunspots.

in textbooks. However, even there you find a variation in the precise altitudes of the layers above the earth's surface. In addition, the real physical situation is such that layers don't have sharply defined boundaries, but rather fade one into another instead. Thus, the division into layers is somewhat arbitrary. These layers (Fig. 2-27) are designated D, E, and F (with F being further subdivided into F1 and F2 sublayers).

D layer The D layer is the lowest layer in the ionosphere, and exists from approximately 30 to 50 mi above the surface. This layer is not ionized as much as the higher layers, because all forms of solar energy that cause ionization are severely attenuated by the higher layers above the D layer. The reason for this is that the D layer is much more dense than the E and F layers, and that density of air molecules allows ions to recombine to form electroneutral atoms very quickly.

The extent of D layer ionization is proportional to the elevation of the sun, so it will achieve maximum intensity at midday. The D layer exists mostly during the warmer months of the year because of both the greater height of the sun above the horizon and the longer hours of daylight. The D layer almost completely disappears after local sunset. Some observers have reported sporadic incidents of D layer activity for a considerable time past sunset. The D layer exhibits a large amount of absorption of medium-wave and shortwave signals (to such an extent that signals below 4 to 6 MHz are completely absorbed by the D layer).

E layer The E layer exists from approximately 50 to 70 mi above the earth's surface, and it is considered the lowest region of the ionosphere that is important to radio communications. Like the D layer, this region is ionized only during the daylight hours, with ionization levels peaking at midday. The ionization level drops off sharply in the late afternoon, and almost completely disappears after local sunset.

During most of the year, the E layer is absorptive and it will not reflect radio signals. During the summer months, however, E layer propagation does occur. A phenomenon called "short skip" (i.e., less than 100 mi for medium wave and 1000 mi for shortwave signals) occurs in the E layer during the summer months, and in equatorial regions at other times.

A propagation phenomenon associated with the E layer is called *sporadic E propagation*. This phenomenon is caused by scattered zones of intense ionization in the E layer region of the ionosphere. The sporadic E phenomenon varies seasonally, and it is believed to be caused by the bombardment of solar particles. Sporadic E propagation affects the upper HF and lower VHF region. It is observed most frequently in the lower VHF spectrum (50 to 150 MHz), but it is also sometimes observed at higher frequencies. The VHF bands occasionally experience sporadic E propagation. Skip distances on VHF can reach 500 to 1500 miles on one hop—especially in the lower VHF region (including the 6-m band).

F layer The F layer of the ionosphere is the region that is the principal cause of long-distance shortwave communications. This layer is located from about 100 to 300 mi above the earth's surface. Unlike the lower layers, the air density in the F layer is low enough that ionization levels remain high all day, and decay slowly after local sunset. Minimum levels are reached just prior to local sunrise. Propagation in the F layer is capable of skip distances up to 2500 mi on a single hop. During the day there are actually two identifiable and distinct sublayers in the F layer region, and these are designated the Fl and F2 layers. The F1 layer is found approximately


300 mi
F2
150 mi
F layer
F1
100 mi
70 mi
E
50 mi
D
30 mi
4–7 mi
Troposphere
Earth's surface

2-27 Classification of the earth's atmosphere for radio propagation.

100 to 150 miles above the earth's surface, and the F2 layer is above the F1 extending up to the 270- to 300-mi limit. Beginning at local sundown, however, the lower regions of the F1 layer begin to deionize because of recombination of positive and negative ions. At some time after local sunset, the F1 and F2 layers have effectively merged to become a single reduced layer beginning at about 175 mi.

The height and degree of ionization of the F2 layer varies over the course of the day, with the season of the year, and with the 27-day sunspot cycle. The F2 layer begins to form shortly after local sunrise and reaches maximum shortly before noon. During the afternoon, the F2 layer ionization begins to decay in an exponential manner until, for purposes of radio propagation, it disappears sometime after local sunset. There is some evidence that ionization in the F layer does not completely disappear, but its importance to HF radio communication does disappear.

Measures of ionospheric propagation

There are several different measures by which the ionosphere is characterized at any given time. These measures are used in making predictions of radio activity and long-distance propagation.

The *critical frequency* and *maximum usable frequency* (MUF) are indices that tell us something of the state of ionization and communications ability. These frequencies increase rapidly after sunrise and international communications usually begin within 30 minutes.

Critical frequency F_c The *critical frequency*, designated by F_c, is the highest frequency that can be reflected when a signal strikes the ionosphere as a vertical (90° with respect to the surface) incident wave. The critical frequency is determined from an *ionogram*, which is a cathode-ray tube (CRT) oscilloscope display of the height of the ionosphere as a function of frequency. The ionogram is made by firing a pulse vertically (Fig. 2-28) at the ionosphere from the transmitting station. The critical frequency is that frequency that is just sufffficient to be reflected back to the transmitter site. Values of F_c can be as low as 3 MHz during the nighttime hours, and as high as 10 to 15 MHz during the day.

Virtual height Radio waves are refracted in the ionosphere, and those above a certain critical frequency are refracted so much that they return to earth. Such waves appear to have been reflected from an invisible radio "mirror." An observer on the earth's surface could easily assume the existence of such a mirror by noting the return of the "reflected" signal. The height of this apparent "mirror" is called the *virtual height* of the ionosphere. Figure 2-29 shows the refraction phenomenon by which a radio wave is bent sufficiently to return to earth. Virtual height is determined by measuring the time interval required for an ionosonde pulse (similar to that used to measure critical frequency) to travel between the transmitting station and a receiving station (Fig. 2-30). A radio signal travels at a velocity of 300,000,000 m/s (the speed of light). By observing the time between transmitting the pulse and receiving it, you can calculate the virtual height of the ionosphere.

Maximum usable frequency (MUF) The *maximum usable frequency* is the highest frequency at which communications can take place via the ionosphere over a given path. The MUF between a fixed transmitter site and two different, widely separated, receivers need not be the same. Generally, however, the MUF is approximately


Layer 2
Ionospheric layers
Layer 1
Waves at critical frequencies
Waves above critical frequency (no reflection back to surface)
c = speed of light
t = time (seconds)
$H_{\text{meters}} = {}^1/_2 ct$
Earth

2-28 Finding critical height of the ionosphere.


C'
B
C
Lower edge of the ionosphere
H_V
A
D

2-29 Finding virtual height of the ionosphere.



2-30 Finding virtual height of ionosphere.

3 times higher than the critical frequency. Both the MUF and the critical frequency vary geographically, and they become higher at latitudes close to the equator.

It is a general rule that the best propagation occurs at frequencies just below the MUF. In fact, there is a so-called *frequency of optimum traffic* (FOT) that is approximately 85 percent of the MUF. Both noise levels and signal strengths are improved at frequencies near the FOT.

Lowest usable frequency (LUF) At certain low frequencies, the combination of ionospheric absorption, atmospheric noise, miscellaneous static, and/or receiver signal-to-noise ratio requirements conspire to reduce radio communications. The lowest frequency that can be used for communications, despite these factors, is the *lowest usable frequency*.

Unlike the MUF, the LUF is not totally dependent on atmospheric physics. The LUF of a system can be varied by controlling the signal-to-noise ratio (SNR). Although certain factors that contribute to SNR are beyond our control, the effective radiated power (ERP) of the transmitter can be changed; a 2-MHz decrease in LUF is available for every 10-dB increase in the ERP of the transmitter.

Ionospheric variation and disturbances

The ionosphere is an extremely dynamic region of the atmosphere, especially from a radio operator's point of view, because it significantly alters radio propagation. The dynamics of the ionosphere are conveniently divided into two general classes: *regular variation* and *disturbances*. This section covers both types of ionospheric change.

Ionospheric variation There are several different forms of variation seen on a regular basis in the ionosphere: *diurnal*, *27-day* (monthly), *seasonal*, and *11-year cycles*.

Diurnal (daily) variation The sun rises and falls on a 24-hour cycle, and because it is the principal source of iononization of the upper atmosphere, you can expect diurnal variation. During daylight hours the E and D levels exist, but these disappear at night. The height of the F2 layer increases until midday, and then it decreases until evening, when it disappears or merges with other layers. As a result of higher absorption in the E and D layers, lower frequencies are not useful during daylight hours. On the other hand, the F layers reflect higher frequencies during the day. In the 1- to 30-MHz region, the higher frequencies (>11 MHz) are used during daylight hours, and the lower frequencies (<11 MHz) at night.

27-day cycle Approximately monthly, this variation is caused by the rotational period of the sun. Sunspots are localized on the surface of the sun, so they will face the earth only during a portion of the month. As new sunspots are formed, they do not show up on the earthside face until their region of the sun rotates earthside.

Seasonal cycle The earth's tilt varies the exposure of the planet to the sun on a seasonal basis. In addition, the earth's yearly orbit is not circular; it is elliptical. As a result, the intensity of the sun's energy that ionizes the upper atmosphere varies with the seasons of the year. In general, the E, D, and F layers are affected—although the F2 layer is only minimally affected. Ion density in the F2 layer tends to be highest in winter, and less in summer. During the summer, the distinction between F1 and F2 layers is less obvious.

11-year cycle The number of sunspots, statistically averaged, varies on an approximately 11-year cycle. As a result, the ionospheric effects that affect radio propagation also vary on an 11-year cycle. Radio propagation, in the shortwave bands, is best when the average number of sunspots is at its highest.

Disturbances Disturbances in the ionosphere can have a profound effect on radio communications—and most of them (but not all) are bad. This section will briefly examine some of the more common forms.

Sporadic E layer A reflective cloud of ionization sometimes appears in the E layer of the ionosphere; this layer is sometimes called the E_s *layer*. It is believed that the E_s layer forms from the effects of wind shear between masses of air moving in opposite directions. This action appears to redistribute ions into a thin layer that is radio-reflective.

Sporadic E propagation is normally thought of as a VHF phenomenon, with most activity between 30 and 100 MHz, and decreasing activity up to about 200 MHz. However, about 25 to 50 percent of the time, sporadic E propagation is possible on frequencies down to 10 or 15 MHz. Reception over paths of 1400 to 2600 mi are possible in the 50-MHz region when sporadic E is present. In the northern hemisphere, the months of June and July are the most prevalent sporadic E months. On most days when sporadic E is present, it lasts only a few hours.

Sudden ionospheric disturbances (SIDs) The SID, or *Dellinger fade,* mechanism occurs suddenly, and rarely gives any warning. The SID can last from a few minutes to many hours. It is known that SIDs often occur in correlation with solar flares, or "bright solar eruptions," that produce an immense amount of ultraviolet radiation that impinges the upper atmosphere. The SID causes a tremendous increase in D layer ionization, which accounts for the radio propagation effects. The ionization is so intense that all receiver operators on the sunny side of the earth experience profound loss of signal strength above about 3 MHz. It is not uncommon for receiver owners to think their receivers are malfunctioning when this occurs. The sudden loss of signals on sunny side receivers is called *Dellinger fade*. The SID is often accompanied by variations in terrestrial electrical currents and magnetism levels.

Ionospheric storms The *ionospheric storm* appears to be produced by an abnormally large rain of atomic particles in the upper atmosphere, and is often preceded by SIDs 18 to 24 hours earlier. These storms tend to last from several hours, to a week or more, and are often preceded by two days or so by an abnormally large collection of sunspots crossing the solar disk. They occur, most frequently, and with greatest severity, in the higher latitudes, decreasing toward the equator. When the ionospheric storm commences, shortwave radio signals may begin to flutter rapidly and then drop out altogether. The upper ionosphere becomes chaotic; turbulence increases and the normal stratification into layers, or zones, diminishes.

Radio propagation may come and go over the course of the storm, but it is mostly dead. The ionospheric storm, unlike the SID, which affects the sunny side of the earth, is worldwide. It is noted that the MUF and critical frequency tend to reduce rapidly as the storm commences.

An ionospheric disturbance observed in November 1960 was preceded by about 30 minutes of extremely good, but abnormal, propagation. At 1500 hours EST, European stations were noted with S9+ signal strengths in the 7000- to 7300-kHz region of the spectrum, which is an extremely rare occurrence. After about 30 minutes, the bottom dropped out and even AM broadcast band skip (later that evening) was nonexistent. At the time, the National Bureau of Standards* radio station, WWV, was broadcasting a "W2" propagation prediction at 19 and 49 minutes after each hour (which is terrible!). It was difficult to hear even the 5-MHz WWV frequency in the early hours of the disturbance, and it disappeared altogether for the next 48 hours. This signal's fade-out occurred during the weekend of the annual ARRL "Sweepstakes" contest.

Ionospheric sky-wave propagation

Sky-wave propagation occurs because signals in the ionosphere are refracted so much that they are bent back toward the earth's surface. To observers on the surface, it looks like the signal was reflected from a radio mirror at the virtual height of the ionosphere. The *skip distance* is the surface distance between the transmitter point (*A* in Fig. 2-31) and the point where it returns to earth (point *C* in Fig. 2-31). The *ground-wave zone* is the distance from the transmitter site (*A* in Fig. 2-31) to where the ground wave fades to a low level, below usefulness (point *B* in Fig. 2-31). The *skip zone* is the distance from the outer edge of the ground-wave zone to the skip distance, or the distance from *B* to *C* in Fig. 2-31.

It is possible for the sky wave and the ground wave to interfere with each other at some frequencies, under some circumstances. When this happens, the sky wave has a relative phase that depends on its path length (among other

---

* Now the National Institute of Standards and Technology.



2-31 Relationship between ground wave and different cases of sky wave.

things), so it will arrive at some seemingly random phase relative to the ground wave. Thus, the sky wave can selectively strengthen or cancel the ground wave, giving rise to a type of fading.

Incident angle One of the factors that affects the length of the skip distance is the incident angle of the radio wave. This angle is partially a function of the frequency, and partially a function of the natural radiation angle of the antenna (α_r). The frequency effects are seen as a function of the ionization level and how much a given frequency is refracted.

The antenna radiation angle is the angle of the main vertical lobe with respect to the earth's surface; it is partially a function of its design, and partially of its installation configuration. For example, a ⅝-wavelength vertical antenna tends to have a lower angle of radiation than a ¼-wave vertical antenna. Similarly, the dipole's angle of radiation is a function of its height above ground.

Figure 2-32 shows how the angle of radiation affects skip distance. Low-angle-of-radiation signals tend to travel farther with respect to the earth's surface before refracting, so they produce the longest skip distances. Higher angles of radiation have shorter skip distances because they tend to return to earth more rapidly. In summertime, some high-frequency bands (e.g,. the 11-m—27 MHz—Citizens Band) offer high-angle "short skip" during the summer, and longer skip during the other months. At higher angles of radiation, there will be a *critical angle* wave and *escape angle* waves that are not returned to earth. These waves are not used for terrestrial communications or broadcasting. Figure 2-33 shows the difference between single-hop skip and multihop skip, as a function of incident angle. It is generally true that a multihop transmission is more subject to fading, and is weaker, than a single-hop transmission.

Using the ionosphere

The refraction of high-frequency and some medium-wave radio signals back to earth via the ionosphere gives rise to intercontinental HF radio communications. This phenomenon becomes possible during daylight hours and for a while after sunset when the ionosphere is ionized. Figure 2-34 reiterates the mechanism of long-distance skip communications. The transmitter is located at point *T*, while receiving stations


Escape wave
Critical angle wave
High angle wave
Low angle wave
α_r

2-32 Sky-wave propagation as a function of antenna radiation angle.


Ionosphere
Single-hop transmission
Two-hop transmission
Transmitter
Receiver

2-33 Single-skip and multihop-skip communications.

are located at sites R_1 and R_2. Signals 1 and 2 are not refracted sufficiently to be refracted back to earth, so they are lost in space. Signal 3, however, is refracted enough to return to earth, so it is heard at station R_1. The skip distance for signal 3 is the distance from T to R_1. At points between T and R_1, signal 3 is inaudible, except within ground-wave distance of the transmitter site (T). This is the reason why two stations 40 mi apart hear each other only weakly, or not at all, while both stations can communicate with a third station 2000 mi away. In amateur radio circles, it is common for South American stations to relay between two U.S. stations only a few miles apart. For an example of this problem, listen to the Inter-American and Halo Missionary



2-34 Effects of radiation angle on distance.

Nets on 21.290 MHz (15 m) daily from about 1700Z to 2100Z (ending time dependent upon traffic).

Multihop skip is responsible for the reception of the signal from transmitter T at site R_3. The signal *reflects* (not refracts) from the surface at R_1, and is retransmitted into the ionosphere, where it is again refracted back to earth.

Figure 2-35 shows a situation where skip signals are received at different distances depending upon the *angle of radiation* of the transmitting antenna. A high angle of radiation causes a shorter skip zone, but a lower angle of radiation results in a longer skip zone. Communication between any particular locations on any given frequency requires adjustment of the antenna radiation angle. Some international shortwave stations have multiple antennas with different radiation angles to ensure that the correct skip distances are available.

Great circle paths A *great circle* is a line between two points on the surface of a sphere, such that it lays on a plane through the earth's center and includes the two points. When translated to "radiospeak," a great circle is the shortest path on the surface of the earth between two points. Navigators and radio operators use the great circle for similar, but different, reasons. The navigator's reason is in order to get from here to there, and the radio operator's is to get a transmission path from here to there.

The heading of a directional antenna is normally aimed at the receiving station along its great circle path. Unfortunately, many people do not understand the concept well enough, for they typically aim the antenna in the wrong direction. For example, I live near Washington, D.C., which is on approximately the same latitude as Lisbon, Portugal. If I catch a lift on Superman's back, and he flies due East, we'll have dinner in Lisbon, right? Wrong. If you head due east from Washington, DC, across the Atlantic, the first landfall would be west Africa, somewhere near Zaire or Angola. Why? Because the great circle bearing 90° takes us far south. The *geometry of spheres*, not flat planes, governs the case.



2-35 Skip propagation.

Figure 2-36 shows a great circle map centered on the Washington, D.C. area. These maps, or computer tabulations of the same data, can often be purchased for your own location by supplying your latitude and longitude to the service company that does the job. By drawing a line from your location at the center of the chart to the area you want to hear, and then extending it to the edge of the chart, you will obtain the beam heading required.

Long path versus short path The earth is a sphere (or more precisely, an oblate spheroid), so from any given point to any other point there are two great circle paths: the *long path* (major arc) and the *short path* (minor arc). In general, the best reception occurs along the short path. In addition, short-path propagation is more nearly "textbook," compared with long path reception. However, there are times when long path is better, or is the only path that will deliver a signal to a specific location from the geographic location in question.

Gray line propagation The *gray line* is the twilight zone between the nighttime and daytime halves of the earth. This zone is also called the *planetary terminator* (Fig. 2-37). It varies up to +23° either side of the north-south longitudinal lines, depending on the season of the year (it runs directly north-south only at the vernal and autumnal equinoxes). The D layer of the ionosphere absorbs signals in the HF region. This layer disappears almost completely at night, but it builds up during the day. Along the gray line, the D layer is rapidly decaying west of the line, and has not quite built up east of the line.

Brief periods of abnormal propagation occur along the gray line. Stations on either side of the line can be heard from regions, and at distances, that would otherwise be impossible on any given frequency. For this reason, radio operators often prefer to listen at dawn and dusk for this effect.

Scatter propagation modes

Ionospheric scatter propagation occurs when clouds of ions exist in the atmosphere. These clouds can exist in both the ionosphere and the troposphere, although


N
S
E
W
JAVA
SUMATRA
BORNEO
MANILA
CANTON
CALCUTTA
PEIPING
A S I A
GUAM
TOKYO
PERTH
NEW GUINEA
AUSTRALIA
EUROPE
LONDON
SUEZ
A F R I C A
MADAGASCAR
HONOLULU
SAN FRANCISCO
NORTH AMERICA
WASHINGTON
PACIFIC OCEAN
ATLANTIC OCEAN
SYDNEY
MELBOURNE
EQUATOR
PANAMA
SOUTH AMERICA
RIO DE JANEIRO
BUENOS AIRES
NEW ZEALAND
CAPE TOWN
10
20
30
40
50
60
70
80
90
100
110
120
130
140
150
160
170
180
190
200
210
220
230
240
250
260
270
280
290
300
310
320
330
340
350

2-36 Azimuthal map centered on Washington, D.C. (*Courtesy of The ARRL Antenna Book.*)

the tropospheric model is more reliable for communications. Figure 2-38 shows the mechanism for scatter propagation. Radio signals from the transmitter are reflected from the cloud of ions to a receiver location that otherwise might not receive it. Scatter propagation occurs mostly in the VHF region, and it allows communications over extended paths that are not normally available.

There are at least three different modes of scatter from ionized clouds: *backscatter*, *side scatter*, and *forward scatter*. The backscatter mode is a bit like radar, in that the signal is returned back to the transmitter site, or to regions close to the transmitter. Forward scatter occurs when the reflected signal continues in the same azimuthal direction (with respect to the transmitter), but is redirected toward the earth's surface. Side scatter is similar to forward scatter, but the azimuthal direction might change.

Unfortunately, there are often multiple reflections from the ionized cloud, and these are shown as "multiple scatter" in Fig. 2-38. When these reflections are able to


Alaska 4:14
Mountain 6:14
Greenland 9:14
European 14:14
Greenwich 12:14
London 13:14
Moscow 16:14
Chicago 7:14
Washington 8:14
Los Angeles 5:14
Peking 20:14
Tokyo 21:14
New Delhi 17:44
Atlantic Ocean
Hawaii 2:14
Pacific Ocean
Indian Ocean
Australia 22:14
Rio de Janeiro 9:14
Johannesburg 14:14
Buenos Aires 9:14
Sydney 22:14
Jun. 6, 1988 12:14 pm

2-37 The planetary terminator ("gray line") provides some unusual propagation effects. (*Courtesy of MFJ Enterprises.*)


Higher layer
Multiple scatter
Scattering cloud
Backscatter
Side scatter
Forward scatter
Transmitting antenna
Receiving antenna

2-38 Various modes of scatter propagation.

reach the receiving site, the result is a rapid, fluttery fading that can be of quite profound depths.

Auroral propagation

The *auroral effect* produces a luminescence in the upper atmosphere resulting from bursts of particles released from the sun 18 to 48 hours earlier. The light emitted is called the *northern lights* and the *southern lights*. The ionized regions of the atmosphere that create the lights form a radio reflection shield, especially at VHF and above, although 15 to 20 MHz effects are known. Auroral propagation effects are normally seen in the higher latitudes, although listeners in the southern tier of states in the United States are often treated to the reception of signals from the north being reflected from auroral clouds.

Meteor scatter propagation

When meteors enter the earth's atmosphere, they do more than simply heat up to the point of burning. The burning meteor leaves a wide, but very short duration, transient cloud of ionized particles in its path. These ions act as a radio mirror that permits short bursts of reception between sites correctly situated. Meteor scatter reception is not terribly reliable, although at least two companies offer meteor scatter communications services for users in the higher latitudes.

Other propagation anomalies

The ionosphere is a physically complex place, and even the extensive coverage in this chapter is not sufficient to do it justice. Indeed, entire books are available on the subject, and it is a valid engineering subspecialty. It is therefore not surprising that a number of propagation anomalies are known.

Nonreciprocal direction If you listen to an amateur band receiver on the East Coast of the United States, you will sometimes hear European stations—especially in the late afternoon. But when you try to work those stations there is no reply whatsoever. They simply don't hear you! This propagation anomaly causes the radio wave to travel different paths dependent on which direction it travels; i.e., an east→west signal is not necessarily the reciprocal of a west→east signal. This anomaly can occur when a radio signal travels through a heavily ionized medium in the presence of a magnetic field, which is exactly the situation when the signal travels through the ionosphere in the presence of the earth's magnetic field.

Another anomaly seen in the radio literature of the 1930s is the *Radio Luxembourg effect*. It is named after the radio station where it was first noticed. In a nonlinear ionosphere, it is sometimes noted that the modulation of superpower (i.e., > 500,000 W) shortwave broadcasters will be transferred to the carrier of a weaker signal in the same or nearby band. The interchange noted in the 1930s when this phenomenon was first discovered was between Radio Luxembourg and Britain's British Broadcasting Corporation (BBC) overseas outlets.

Propagation predictions

Propagation predictions for the VLF through low VHF bands are published each month in several magazines. Ham radio operators often use those in *QST* magazine (Fig. 2-39), while SWLs and others tend to prefer those published in magazines such as *Monitoring Times*. These charts relate the time of day in Universal Coordinated Time (UTC, formerly, GMT) and the frequency for transmission to different parts of the world.

Fading

Skip communications are not without problems. One phenomenon is fading (i.e., a variation in signal strength as perceived at the receiver site). This problem can sometimes be overcome by using one of several diversity reception systems. Three forms of diversity technique are used: *frequency diversity*, *spatial diversity*, and *polarity diversity*.

In the frequency diversity system (Fig. 2-40), the transmitter will send out two or more frequencies simultaneously with the same modulating information. Because the two frequencies will fade differentially, one will always be strong.

The spatial diversity system (Fig. 2-41) assumes that a single transmitter frequency is used. At the receiving site, two or more receiving antennas are used, spaced one-half wavelength apart. The theory is that the signal will fade at one antenna while it increases at the other. A three-antenna system is often used. Three separate, but identical, receivers, often tuned by the same master local oscillator, are connected to the three antennas. Audio mixing, based on the strongest signal, keeps the audio output constant while the radio-frequency (RF) signal fades.

Polarity diversity reception (Fig. 2-42) uses both vertical and horizontal polarization antennas to receive the signal. As in the space diversity system, the outputs of the vertical and horizontal receivers are combined to produce a constant level output.

Another form of fading, *selective fading*, derives from the fact that fading is a function of frequency. The carrier and upper and lower sidebands of an AM signal have slightly different frequencies, so they arrive out of phase with each other. Although this type of fading is lessened by using single-sideband (SSB) transmission, that does not help AM users. In those systems, some people use a filtering system that eliminates the carrier and one sideband; it then reconstitutes the AM signal with a product detector.

SSB receivers with stable local and product detector oscillators, and a sharp intermediate-frequency (IF) bandpass filter, can be used to reduce the effects of differential fading of AM signals because of the phasing of the lower sideband (LSB), upper sideband (USB), and carrier components. Carefully tune the receiver to only one sideband of the signal, and note when the heterodyne beatnote disappears. The correct point is characterized by the fact that you can then switch among USB, LSB, and continuous-wave (CW) modes without changing the received signal output.



2-39 Propagation prediction charts appear in magazines such as *QST* every month. (*Courtesy of the American Radio Relay League.*)


F_1 and F_2
XMTR 1
F_1
XMTR 2
F_2
Σ
÷
RCVR 1
RCVR 2
AF_1
AF_2
Σ
Composite audio out
$F_2 \neq F_1$
$F_2 = F_1 \pm \Delta F$

2-40 Frequency diversity reduces fading.


Antenna 1
Antenna 2
Antenna 3
λ/2
λ/2
RCVR 1
RCVR 2
RCVR 3
AF_1
AF_2
AF_3
Σ
Composite audio output
Master local oscillator

2-41 Spatial diversity.


Horizontal antenna
RCVR 1
H audio
Σ
Composite audio output
Vertical antenna
RCVR 2
V audio

2-42 Polarization diversity.

3
CHAPTER
Transmission lines

TRANSMISSION LINES AND *WAVEGUIDES* ARE CONDUITS FOR TRANSPORTING RF SIGNALS between elements of a system. For example, transmission lines are used between an exciter output and transmitter input, and between the transmitter input and its output, and between the transmitter output and the antenna. Although often erroneously characterized as a "length of shielded wire," transmission lines are actually complex networks containing the equivalent of all the three basic electrical components: resistance, capacitance, and inductance. Because of this fact, transmission lines must be analyzed in terms of an *RLC* network.

Parallel and coaxial lines

This chapter will consider several types of transmission lines. Both step-function and sine-wave ac responses will be studied. Because the subject is both conceptual and analytical, both analogy and mathematical approaches to the theory of transmission lines will be used.

Figure 3-1 shows several basic types of transmission line. Perhaps the oldest and simplest form is the *parallel line* shown in Figs. 3-1A through 3-1D. Figure 3-1A shows an end view of the parallel conductor transmission line. The two conductors, of diameter d, are separated by a dielectric (which might be air) by a spacing S. These designations will be used in calculations later. Figure 3-1B shows a type of parallel line called *twin lead*. This is the old-fashioned television antenna transmission line. It consists of a pair of parallel conductors separated by a plastic dielectric. TV-type twin lead has a characteristic impedance of 300 Ω, while certain radio transmitting-antenna twin lead has an impedance of 450 Ω. Another form of twin lead is *open line*, shown in Fig. 3-1C. In this case, the wire conductors are separated by an air dielectric, with support provided by stiff (usually ceramic) insulators. A tie wire (only one shown) is used to fasten each insulator end to the main conductor. Some users of open line prefer the form of insulator or supporter shown in Fig. 3-1D. This

Copyright 2001 - the McGraw-Hill Companies



S
d
d
(End view)

3-1A Parallel line transmission line (end view).



3-1B Twin-lead transmission line.



Conductors
Insulator
Tie

3-1C Parallel line construction details.



3-1D Horseshoe parallel line spreader.

form of insulator is made of either plastic or ceramic, and is in the form of a U. The purpose of this shape is to reduce losses, especially in rainy weather, by increasing the leakage currents path relative to spacing S.

Parallel lines have been used at VLF, MW, and HF frequencies for decades. Even antennas into the low VHF are often found using parallel lines. The higher impedance of these lines (relative to coaxial cable) yields lower loss in high-power applications. For years, the VHF, UHF, and microwave application of parallel lines was limited to educational laboratories, where they are well suited to performing experiments (to about 2 GHz) with simple, low-cost instruments. Today, however, printed circuit and hybrid semiconductor packaging has given parallel lines a new lease on life, if not an overwhelming market presence.

Figure 3-1E shows a form of parallel line called *shielded twin lead*. This type of line uses the same form of construction as TV-type twin lead, but it also has a braided shielding surrounding it. This feature makes it less susceptible to noise and other problems.

The second form of transmission line, which finds considerable application at microwave frequencies, is *coaxial cable* (Figs. 3-1F through 3-1L). This form of line consists of two cylindrical conductors sharing the same axis (hence “coaxial”), and separated by a dielectric (Fig. 3-1F). For low frequencies (in flexible cables) the dielectric may be polyethylene or polyethylene foam, but at higher frequencies *Teflon* and other materials are used. Also used, in some applications, are dry air and dry nitrogen.



3-1E Shielded twin-lead transmission line.



3-1F Coaxial cable (end view).

Several forms of coaxial line are available. Flexible coaxial cable is perhaps the most common form. The outer conductor in such cable is made of either braid or foil (Fig. 3-1G). Television broadcast receiver antennas provide an example of such cable from common experience. Another form of flexible or semiflexible coaxial line is *helical line* (Fig. 3-1H) in which the outer conductor is spiral wound. *Hardline* (Fig. 3-1I) is coaxial cable that uses a thin-wall pipe as the outer conductor. Some hardline coax used at microwave frequencies has a rigid outer conductor and a solid dielectric.

Gas-filled line is a special case of hardline that is hollow (Fig. 3-1J), the center conductor is supported by a series of thin ceramic or Teflon insulators. The dielectric is either anhydrous (i.e., dry) nitrogen or some other inert gas.

Some flexible microwave coaxial cable uses a solid “air-articulated” dielectric (Fig. 3-1K), in which the inner insulator is not continuous around the center conductor, but rather is ridged. Reduced dielectric losses increase the usefulness of the


Outer insulator
Inner conductor
Braid
Inner insulator

3-1G Coaxial cable (side view).


Insulating sheath
Dielectric
Shield
Inner conductor

3-1H Coaxial hardline cable.


Rigid outer conductor
Dielectric
Inner conductor

3-1I Rigid coaxial line.


Insulators
Center conductor
Outer conductor

3-1J Gas-filled hollow coaxial line.


Dielectric (vaned)

3-1K Articulated coaxial line.


Insulating sheath
Outer insulator
Inner insulator
Center conductor
Outer shield
Inner shield

3-1L Double-shielded coaxial line.

cable at higher frequencies. Double-shielded coaxial cable (Fig. 3-1L) provides an extra measure of protection against radiation from the line, and EMI from outside sources, from getting into the system.

Stripline, also called *microstripline* (Fig. 3-1M), is a form of transmission line used at high UHF and microwave frequencies. The stripline consists of a critically sized conductor over a ground-plane conductor, and separated from it by a dielectric. Some striplines are sandwiched between two groundplanes and are separated from each by a dielectric.

Transmission line characteristic impedance (Z_o)

The transmission line is an *RLC* network (see Fig. 3-2), so it has a *characteristic impedance* Z_o, also sometimes called a *surge impedance*. Network analysis will show that Z_o is a function of the per unit of length parameters *resistance* R, *conductance* G, *inductance* L, and *capacitance* C, and is found from

$$Z_o = \sqrt{\frac{R + j\,\omega L}{G + j\,\omega C}} \qquad \textbf{[3.1]}$$

where

Z_o is the characteristic impedance, in ohms
R is the resistance per unit length, in ohms
G is the conductance per unit length, in mhos
L is the inductance per unit length, in henrys
C is the capacitance per unit length, in farads
ω is the angular frequency in radians per second ($2\pi F$)



3-1M Stripline transmission line.



3-2 Equivalent circuit of transmission line.

In microwave systems the resistances are typically very low compared with the reactances, so Eq. 3.1 can be reduced to the simplified form:

$$Z_o = \sqrt{\frac{L}{C}} \tag{3.2}$$

Example 3-1 A nearly lossless transmission line (R is very small) has a unit length inductance of 3.75 nH and a unit length capacitance of 1.5 pF. Find the characteristic impedance Z_o.

Solution:

$$Z_o = \sqrt{\frac{L}{C}}$$

$$= \sqrt{\frac{\left(3.75\ \text{nH} \times \dfrac{1\ \text{H}}{10^9\ \text{nH}}\right)}{\left(1.5\ \text{pF} \times \dfrac{1\ \text{F}}{10^{12}\ \text{pF}}\right)}}$$

$$= \sqrt{\frac{3.75 \times 10^{-9}\ \text{H}}{1.5 \times 10^{-12}\ \text{F}}}$$

$$= \sqrt{2.5 \times 10^3} = 50\ \Omega$$

The characteristic impedance for a specific type of line is a function of the conductor size, the conductor spacing, the conductor geometry (see again Fig. 3-1), and the dielectric constant of the insulating material used between the conductors. The dielectric constant e is equal to the reciprocal of the velocity (squared) of the wave when a specific medium is used:

$$e = \frac{1}{v^2} \tag{3.3}$$

where

e is the dielectric constant (for a perfect vacuum $e = 1.000$)
v is the velocity of the wave in the medium

(a) Parallel line

$$Z_o = \frac{276}{\sqrt{e}} \log\left(\frac{2S}{d}\right) \tag{3.4}$$

where

Z_o is the characteristic impedance, in ohms
e is the dielectric constant
S is the center-to-center spacing of the conductors
d is the diameter of the conductors

(b) *Coaxial line*

$$Z_o = \frac{138}{\sqrt{e}} \log\left(\frac{D}{d}\right) \qquad \textbf{[3.5]}$$

where

D is the diameter of the outer conductor
d is the diameter of the inner conductor

(c) *Shielded parallel line*

$$Z_o = \frac{276}{\sqrt{e}} \log\left(2A \quad \frac{(1-B^2)}{(1+B^2)}\right) \qquad \textbf{[3.6]}$$

where

$A = s/d$
$B = s/D$

(d) *Stripline*

$$Z_o = \frac{377}{\sqrt{e_t}} \left(\frac{T}{W}\right) \qquad \textbf{[3.7A]}$$

where

e_t is the relative dielectric constant of the printed wiring board (PWB)
T is the thickness of the printed wiring board
W is the width of the stripline conductor

The relative dielectric constant e_t used above differs from the normal dielectric constant of the material used in the PWB. The relative and normal dielectric constants move closer together for larger values of the ratio W/T.

Example 3-2 A stripline transmission line is built on a 4-mm-thick printed wiring board that has a relative dielectric constant of 5.5. Calculate the characteristic impedance if the width of the strip is 2 mm.

Solution:

$$Z_o = \frac{377}{\sqrt{e_t}} \left(\frac{T}{W}\right)$$

$$= \frac{377}{\sqrt{5.5}} \left(\frac{4\text{ mm}}{2\text{ mm}}\right)$$

$$= \frac{377}{2.35}\ (2) = 321\ \Omega$$

In practical situations, we usually don't need to calculate the characteristic impedance of a stripline, but rather design the line to fit a specific system impedance (e.g., 50 Ω). We can make some choices of printed circuit material (hence dielectric constant) and thickness, but even these are usually limited in practice by the availability of standardized boards. Thus, stripline *width* is the variable parameter. Equation 3.2 can be arranged to the form:

$$W = \frac{377\ T}{Z_o\sqrt{e}} \tag{3.7B}$$

The impedance of 50 Ω is accepted as standard for RF systems, except in the cable TV industry. The reason for this diversity is that power handling ability and low loss operation don't occur at the same characteristic impedance. For example, the maximum power handling ability for coaxial cables occurs at 30 Ω, while the lowest loss occurs at 77 Ω; 50 Ω is therefore a reasonable tradeoff between the two points. In the cable TV industry, however, the RF power levels are minuscule, but lines are long. The tradeoff for TV is to use 75 Ω as the standard system impedance in order to take advantage of the reduced attenuation factor.

Transmission line characteristics

Velocity factor

In the section preceding this section, we discovered that the velocity of the wave (or signal) in the transmission line is less than the free-space velocity (i.e., less than the speed of light). Further, we discovered in Eq. 3.3 that velocity is related to the dielectric constant of the insulating material that separates the conductors in the transmission line. Velocity factor v is usually specified as a decimal fraction of c, the speed of light (3×10^8 m/s). For example, if the velocity factor of a transmission line is rated at "0.66," then the velocity of the wave is $0.66c$, or $(0.66)\ (3 \times 10^8 \text{ m/s}) = 1.98 \times 10^8$ m/s.

Velocity factor becomes important when designing things like transmission line transformers, or any other device in which the length of the line is important. In most cases, the transmission line length is specified in terms of *electrical length*, which can be either an angular measurement (e.g., 180° or π radians), or a relative measure keyed to wavelength (e.g., one-half wavelength, which is the same as 180°). The *physical length* of the line is longer than the equivalent electrical length. For example, let's consider a 1-GHz half-wavelength transmission line.

A rule of thumb tells us that the length of a wave (in meters) in free space is $0.30/F$, where frequency F is expressed in gigahertz; therefore, a half-wavelength line is $0.15/F$.

At 1 GHz, the line must be 0.15 m/1 GHz = 0.15 m. If the velocity factor is 0.80, then the *physical length* of the transmission line that will achieve the desired *electrical length* is [(0.15 m) (v)]/F = [(0.15 m) (0.80)]/1 GHz = 0.12 m. The derivation of the rule of thumb is “left as an exercise for the student.” (*Hint*: It comes from the relationship between wavelength, frequency, and velocity of propagation for any form of wave.)

There are certain practical considerations regarding velocity factor that result from the fact that the physical and electrical lengths are not equal. For example, in a certain type of phased-array antenna design, radiating elements are spaced a half-wavelength apart, and must be fed 180° (half-wave) out of phase with each other. The simplest interconnect is to use a half-wave transmission line between the 0° element and the 180° element. According to the standard wisdom, the transmission line will create the 180° phase delay required for the correct operation of the antenna. Unfortunately, because of the velocity factor, the physical length for a one-half electrical wavelength cable is shorter than the free-space half-wave distance between elements. In other words, the cable will be too short to reach between the radiating elements by the amount of the velocity factor!

Clearly, velocity factor is a topic that must be understood before transmission lines can be used in practical situations. Table 3-1 shows the velocity factors for several types of popular transmission line. Because these are nominal values, the actual velocity factor for any given line should be measured.

Table 3-1. Transmission line characteristics

Type of line	**Z_o (ohms)**	**Velocity factor v**
½-in. TV parallel line (air dielectric)	300	0.95
1-in. TV parallel line (air dielectric)	450	0.95
TV twin lead	300	0.82
UHF TV twin lead	300	0.80
Polyethylene coaxial cable	*	0.66
Polyethylene foam coaxial cable	*	0.79
Air-space polyethylene foam coaxial cable	*	0.86
Teflon	*	0.70

* Various impedances depending upon cable type.

Transmission line noise

Transmission lines are capable of generating noise and spurious voltages that are seen by the system as valid signals. Several such sources exist. One source is the coupling between noise currents flowing in the outer conductor and the inner conductor. Such currents are induced by nearby electromagnetic interference and other sources (e.g., connection to a noisy groundplane). Although coaxial design reduces noise pickup, compared with parallel line, the potential for EMI exists. Selection of high-grade line, with a high degree of shielding, reduces the problem.

Another source of noise is thermal noises in the resistances and conductances. This type of noise is proportional to resistance and temperature.

There is also noise created by mechanical movement of the cable. One species results from the movement of the dielectric against the two conductors. This form of noise is caused by electrostatic discharges in much the same manner as the spark created by rubbing a piece of plastic against woolen cloth.

A second species of mechanically generated noise is *piezoelectricity* in the dielectric. Although more common in cheap cables, one should be aware of it. Mechanical deformation of the dielectric causes electrical potentials to be generated.

Both species of mechanically generated noise can be reduced or eliminated by proper mounting of the cable. Although rarely a problem at lower frequencies, such noise can be significant at microwave frequencies when signals are low.

Coaxial cable capacitance

A coaxial transmission line possesses a certain capacitance per unit of length. This capacitance is defined by

$$C = \frac{24e}{\log\ (D/d)} \ \frac{\text{pF}}{\text{m}} \qquad \textbf{[3.8A]}$$

A long run of coaxial cable can build up a large capacitance. For example, a common type of coax is rated at 65 pF/m. A 150-m roll thus has a capacitance of 65 pF/m × (150 m), or 9750 pF. When charged with a high voltage, as is done in breakdown voltage tests at the factory, the cable *acts like a charged high-voltage capacitor*. Although rarely (if ever) lethal to humans, the stored voltage in new cable can deliver a nasty electrical shock and can irreparably damage electronic components.

Coaxial cable cutoff frequency F_o

The normal mode in which a coaxial cable propagates a signal is as a transverse electromagnetic (TEM) wave, but others are possible—and usually undesirable. There is a maximum frequency above which TEM propagation becomes a problem, and higher modes dominate. Coaxial cable should *not* be used above a frequency of

$$F = \frac{6.75}{(D + d)\sqrt{e}} \text{ GHz} \qquad \textbf{[3.8B]}$$

where

F is the TEM-mode cutoff frequency
D is the diameter of the outer conductor, in inches
d is the diameter of the inner conductor, in inches
e is the dielectric constant

When maximum operating frequencies for cable are listed, it is the TEM mode that is cited. Beware of attenuation, however, when making selections for microwave frequencies. A particular cable may have a sufficiently high TEM-mode frequency, but still exhibit a high attenuation per unit length at X or Ku bands.

Transmission line responses

In order to understand the operation of transmission lines, we need to consider two cases: *step-function response* and the *steady-state ac response*. The step-function case involves a single event when a voltage at the input of the line snaps from zero (or a steady value) to a new (or nonzero) value, and remains there until all action dies out. This response tells us something of the behavior of pulses in the line, and in fact is used to describe the response to a single-pulse stimulus. The steady-state ac response tells us something of the behavior of the line under stimulation by a sinusoidal RF signal.

Step-function response of a transmission line

Figure 3-3 shows a parallel transmission line with characteristic impedance Z_o connected to a load impedance Z_L. The generator at the input of the line consists of a voltage source V in series with a source impedance Z_s and a switch S_1. Assume for the present that all impedances are pure resistances (i.e., $R + j0$). Also, assume that $Z_s = Z_o$.

When the switch is closed at time T_o (Fig. 3-4A), the voltage at the input of the line (V_{in}) jumps to $V/2$. In Fig. 3-2, you may have noticed that the LC circuit resembles a delay line circuit. As might be expected, therefore, the voltage wavefront propagates along the line at a velocity v of:

$$v = \frac{1}{\sqrt{LC}} \qquad \textbf{[3.9]}$$

where

v is the velocity, in meters per second
L is the inductance, in henrys
C is the capacitance, in farads



3-3 Schematic example of transmission line.



3-4 Step-function propagation along transmission line at three points.

At time T_1 (Fig. 3-4B), the wavefront has propagated one-half the distance L, and by T_d it has propagated the entire length of the cable (Fig. 3-4C).

If the load is perfectly matched (i.e., $Z_L = Z_o$), then the load absorbs the wave and no component is reflected. But in a mismatched system (Z_L is not equal to Z_o), a portion of the wave is reflected back down the line toward the generator.

Figure 3-5 shows the rope analogy for reflected pulses in a transmission line. A taut rope (Fig. 3-5A) is tied to a rigid wall that does not absorb any of the energy in the pulse propagated down the rope. When the free end of the rope is given a vertical displacement (Fig. 3-5B), a wave is propagated down the rope at velocity v (Fig. 3-5C). When the pulse hits the wall (Fig. 3-5D), it is reflected (Fig. 3-5E) and propagates back down the rope toward the free end (Fig. 3-5F).

If a second pulse is propagated down the line before the first pulse dies out, then there will be two pulses on the line at the same time (Fig. 3-6A). When the two pulses interfere, the resultant will be the algebraic sum of the two. In the event that a pulse train is applied to the line, the interference pattern will set up *standing waves*, an example of which is shown in Fig. 3-6B.

Reflection coefficient

The *reflection coefficient* Γ of a circuit containing a transmission line and load impedance is a measure of how well the system is matched. The absolute value of the re-


A
B
C
V
D
V
E
V
F
V

3-5 Rope analogy to transmission line.



3-6A Interfering opposite waves.



3-6B Standing waves.

flection coefficient varies from –1 to +1, depending upon the magnitude of reflection; $\Gamma = 0$ indicates a perfect match with no reflection, while –1 indicates a short-circuited load, and +1 indicates an open circuit. To understand the reflection coefficient, let's start with a basic definition of the resistive load impedance $Z = R + j0$:

$$Z_L = \frac{V}{I} \qquad \textbf{[3.10]}$$

where

Z_L is the load impedance $R + j0$
V is the voltage across the load
I is the current flowing in the load

Because there are both reflected and incident waves, we find that V and I are actually the sum of incident and reflected voltages and currents, respectively. Therefore:

$$Z_L = \frac{V}{I} \qquad \textbf{[3.11A]}$$

$$Z_L = \frac{V_{\text{inc}} + V_{\text{ref}}}{I_{\text{inc}} + I_{\text{ref}}} \qquad \textbf{[3.11B]}$$

where

V_{inc} is the incident (i.e., forward) voltage
V_{ref} is the reflected voltage
I_{inc} is the incident current
I_{ref} is the reflected current

Because of Ohm's law, you can define the currents in terms of voltage, current, and the characteristic impedance of the line:

$$I_{\text{inc}} = \frac{V_{\text{inc}}}{Z_o} \qquad \textbf{[3.12]}$$

and

$$I_{\text{inc}} = \frac{-V_{\text{ref}}}{Z_o} \qquad \textbf{[3.13]}$$

(The minus sign in Eq. 3.13 indicates that a direction reversal has taken place.)

The two expressions for current (Eqs. 3.12 and 3.13) may be substituted into Eq. 3.11 to yield

$$Z_L = \frac{V_{\text{inc}} + V_{\text{ref}}}{\dfrac{V_{\text{inc}}}{Z_o} - \dfrac{V_{\text{ref}}}{Z_o}} \qquad \textbf{[3.14]}$$

The reflection coefficient Γ is defined as the ratio of reflected voltage to incident voltage:

$$\Gamma = \frac{V_{\text{ref}}}{V_{\text{inc}}} \qquad \textbf{[3.15]}$$

Using this ratio in Eq. 3.14 gives

$$\Gamma = \frac{Z_L - Z_o}{Z_L + Z_o} \qquad \textbf{[3.16]}$$

Example 3-3 A 50-Ω transmission line is connected to a 30-Ω resistive load. Calculate the reflection coefficient Γ.

Solution:

$$\Gamma = \frac{Z_L - Z_o}{Z_L + Z_o}$$

$$= \frac{(50\ \Omega) - (30\ \Omega)}{(50\ \Omega) + (30\ \Omega)}$$

$$= \frac{20}{80} = 0.25$$

Example 3-4 In Example 3-3, the incident voltage is 3 V rms. Calculate the reflected voltage.

Solution:

If

$$\Gamma = \frac{V_{\text{ref}}}{V_{\text{inc}}}$$

then

$$\begin{aligned} V_{\text{ref}} &= \Gamma\, V_{\text{inc}} \\ &= (0.25)\ (3\ \text{V}) = 0.75\ \text{V} \end{aligned}$$

The phase of the reflected signal is determined by the relationship of load impedance and transmission line characteristic impedance. For resistive loads ($Z = R + j0$): if the ratio Z_L/Z_o is 1.0, then there is no reflection; if Z_L/Z_o is less than 1.0, then the reflected signal is 180° out of phase with the incident signal; if the ratio Z_L/Z_o is greater than 1.0 then the reflected signal is in phase with the incident signal. In summary:

Ratio	**Angle of reflection**
$Z_L/Z_o = 1$	No reflection
$Z_L/Z_o < 1$	180°
$Z_L/Z_o > 1$	0°

The step-function (or pulse) response of the transmission line leads to a powerful means of analyzing the line, and its load, on an oscilloscope. Figure 3-7A shows (in schematic form) the test set-up for *time domain reflectometry* (TDR) measurements. An oscilloscope and a pulse (or square-wave) generator are connected in parallel across the input end of the transmission line. Figure 3-7B shows a pulse test jig built by the author for testing lines at HF. The small shielded box contains a TTL square-wave oscillator circuit. Although a crystal oscillator can be used, an *RC* timed circuit running close to 1000 kHz is sufficient. In Fig. 3-7B, you can see the test pulse generator box is connected in parallel with the cable under test and the input of the oscilloscope. A closer look is seen in Fig. 3-7C. A BNC “tee” connector and a double male BNC adapter are used to interconnect the box with the ’scope.

If a periodic waveform is supplied by the generator, then the display on the oscilloscope will represent the sum of reflected and incident pulses. The duration of the pulse (i.e., pulse width), or one-half the period of the square wave, is adjusted so that the returning reflected pulse arrives approximately in the center of the incident pulse.

Figure 3-8 shows a TDR display under several circumstances. Approximately 30 m of coaxial cable, with a velocity factor of 0.66, was used in a test setup similar to Fig. 3-7. The pulse width was approximately 0.9 microseconds (μs). The hori-


Oscilloscope
Z_o
$Z_s=Z_o$
Z_L
Z_s
Pulse
generator

3-7A Time domain reflectometry setup.


465
OSCILLOSCOPE
VOLTS/DIV
CH 1
CH 2

3-7B Test setup for impromptu time domain reflectometry.



3-7C Close-up of RF connections.



3-8A Idealized TDR pulse. Small "pip" on top is reflected signal interfering with forward pulse.

zontal sweep time on the 'scope was adjusted to show only one pulse—which, in this case, represented one-half of a 550-kHz square wave (Fig. 3-8B).

The displayed trace in Fig. 3-8B shows the pattern when the load is matched to the line ($Z_L = Z_o$). A slight discontinuity exists on the high side of the pulse, and this represents a small reflected wave. Even though the load and line were supposedly matched, the connectors at the end of the line presented a slight impedance discontinuity that shows up on the 'scope as a reflected wave. In general, any discontinuity in the line, any damage to the line, any too-sharp bend, or other anomaly, causes a slight impedance variation, and hence a reflection.



3-8B TDR pulse with no significant reflection.

Notice that the anomaly occurs approximately one-third of the 0.9-μs duration (or 0.3 μs) after the onset of the pulse. This fact tells us that the reflected wave arrives back at the source 0.3 μs after the incident wave leaves. Because this time period represents a round-trip, you can conclude that the wave required 0.3 μs/2, or 0.15 μs to propagate the length of the line. Knowing that the velocity factor is 0.66 for that type of line, you can calculate its approximate length:

$$\begin{aligned}\text{Length} &= cvT \qquad \textbf{[3.17]}\\ &= \frac{(3\times10^{8}\text{ m/s})}{\text{s}}\times(0.66)\times(1.5\times10^{-7}\text{ s})\\ &= 29.7\text{ m}\end{aligned}$$

which agrees "within experimental accuracy" with the 30 m actual length prepared for the experiment ahead of time. Thus, the TDR setup (or a TDR instrument) can be used to measure the length of a transmission line. A general equation is

$$L_{\text{meters}} = \frac{cvT_d}{2} \qquad \textbf{[3.18]}$$

where

L is the length in meters
c is the velocity of light (3×10^8 m/s)
v is the velocity factor of the transmission line
T_d is the round-trip time between the onset of the pulse, and the first reflection

Figures 3-8C through 3-8H show the behavior of the transmission line to the stepfunction when the load impedance is mismatched to the transmission line (Z_L not equal to Z_o). Figure 3-8C shows what happens when the load impedance is less than the line impedance (in this case, $0.5Z_o$). The reflected wave is inverted, and



3-8C $Z_L<Z_o$.



3-8D $Z_L>Z_o$.

sums with the incident wave along the top of the pulse. The reflection coefficient can be determined by examining the relative amplitudes of the two waves.

The opposite situation, in which Z_L is $2Z_o$, is shown in Fig. 3-8D. In this case, the reflected wave is in phase with the incident wave, so it adds to the incident wave as shown. The cases for a short-circuited load and an open-circuited load are shown in Figs. 3-8E and 3-8F, respectively. The cases of reactive loads are shown in Figs. 3-8G and 3-8H. The waveform in Fig. 3-8G resulted from a capacitance in series with a 50-Ω (matched) resistance; the waveform in Fig. 3-8H resulted from a 50-Ω resistance in series with an inductance.

The ac response of the transmission line

When a CW RF signal is applied to a transmission line, the excitation is sinusoidal (Fig. 3-9), so it becomes useful for us to investigate the steady-state ac response of the line. The term *steady-state* implies a sine wave of constant amplitude, phase, and



3-8E $Z_L = 0$.



3-8F $Z_L = \infty$.



3-8G $Z_L = 50 - jX_C$.



3-8H $Z_L = 50 + jX_L$



3-9 AC-excited transmission line.

frequency. When ac is applied to the input of the line, it propagates along the line at a given velocity. The ac signal amplitude and phase will decay exponentially:

$$V_R = Ve^{-yl} \quad \textbf{[3.19]}$$

where

V_R is the voltage received at the far end of the line
V is the applied voltage
l is the length of the line
y is the *propagation constant* of the line

The propagation constant y is defined in various equivalent ways, each of which serves to illustrate its nature. For example, the propagation constant is proportional to the product of impedance and admittance characteristics of the line:

$$y = \sqrt{ZY} \qquad \textbf{[3.20]}$$

or, since $Z = R + j\,\omega\,L$ and $Y = G + j\,\omega\,C$, we may write:

$$y = \sqrt{(R + jwl)\ (G + jwC)} \qquad \textbf{[3.21]}$$

You can also write an expression for the propagation constant in terms of the *line attenuation constant* a and *phase constant* B:

$$y = a + jB \qquad \textbf{[3.22]}$$

If you can assume that susceptance dominates conductance in the admittance term, and reactance dominates resistance in the impedance term (both usually true at microwave frequencies), then we may neglect the R and G terms altogether and write:

$$y = j\omega\sqrt{LC} \qquad \textbf{[3.23]}$$

We may also reduce the phase constant B to

$$B = \omega\sqrt{LC} \qquad \textbf{[3.24]}$$

or

$$B = \omega Z_o C \qquad \text{rad/m} \qquad \textbf{[3.25]}$$

and, of course, the characteristic impedance remains:

$$Z_o = \sqrt{LC} \qquad \textbf{[3.26]}$$

Special cases

The impedance "looking into" a transmission line (Z) is the impedance presented to the source by the combination of load impedance and transmission line characteristic impedance. Below are presented equations that define the looking-in impedance seen by a generator (or source) driving a transmission line.

The case where the load impedance, and line characteristic impedance, are matched is defined by

$$Z_L = R_L + j0 = Z_o$$

In other words, the load impedance is resistive and equal to the characteristic impedance of the transmission line. In this case, the line and load are matched, and the impedance looking in will be a simple $Z = Z_L = Z_o$. In other cases, however, we find different situations where Z_L is not equal to Z_o.

1. Z_L is not equal to Z_o in a random-length lossy line:

$$Z = (Z_o)\left[\frac{Z_L + Z_o \tanh(yl)}{Z_o + Z_L \tanh(yl)}\right] \qquad \textbf{[3.27]}$$

where

Z is the impedance looking in, in ohms
Z_L is the load impedance, in ohms
Z_o is the line characteristic impedance, in ohms
l is the length of the line, in meters
y is the propagation constant

2. Z_L not equal to Z_o in a lossless, or very low loss, random-length line:

$$Z = (Z_o)\left[\frac{Z_L + jZ_o \tan(Bl)}{Z_o + jZ_L \tan(Bl)}\right] \qquad \textbf{[3.28]}$$

Equations 3.27 and 3.28 serve for lines of any random length. For lines that are either integer multiples of a half-wavelength, or odd-integer (i.e., 1, 3, 5, 7, . . ., etc.) multiples of a quarter-wavelength, special solutions for these equations are found—and some of these solutions are very useful in practical situations. For example, consider . . .

3. Half-wavelength lossy lines:

$$Z = (Z_o)\left[\frac{Z_L + Z_o \tanh(al)}{Z_o + Z_L \tanh(al)}\right] \qquad \textbf{[3.29]}$$

Example 3-5 A lossless 50-Ω (Z_o) transmission line is exactly one-half wavelength long and is terminated in a load impedance of $Z = 30 + j0$. Calculate the input impedance looking into the line. (*Note*: in a lossless line $a = 0$.)

Solution:

$$Z = (Z_o)\left[\frac{Z_L + Z_o \tanh(al)}{Z_o + Z_L \tanh(al)}\right]$$

$$Z = (50\ \Omega)\left\{\frac{30 + 50\ \tanh\ [(0)\ (\pi)]}{50 + 30\ \tanh\ [(0)\ (\pi)]}\right\}$$

$$= (50\ \Omega)\left[\frac{30 + 50\ \tanh\ (0)}{50 + 30\ \tanh\ (0)}\right]$$

$$= (50\ \Omega)\left(\frac{30 + 0}{50 + 0}\right)$$

$$= (50\ \Omega)\ (30/50) = 30\ \Omega$$

In Example 3-5 we discovered that the impedance looking into a lossless (or very low loss) half-wavelength transmission line is the load impedance:

$$Z = Z_L \qquad \textbf{[3.30]}$$

The fact that line input impedance equals load impedance, is very useful in certain practical situations. For example, a resistive impedance is not changed by the line length. Therefore, when an impedance is inaccessible for measurement purposes, the impedance can be measured through a transmission line that is an integer multiple of a half wavelength.

Our next special case involves a quarter-wavelength transmission line, and those that are *odd* integer multiples of quarter-wavelengths (of course, *even* integer multiples of a quarter wavelength obey the half-wavelength criteria).

4. Quarter-wavelength lossy lines:

$$Z = (Z_o)\left[\frac{Z_L + Z_o\ \coth\ (al)}{Z_o + Z_L\ \coth\ (al)}\right] \qquad \textbf{[3.31]}$$

and

5. Quarter-wavelength lossless or very low loss lines:

$$Z = \frac{(Z_o)^2}{Z_L} \qquad \textbf{[3.32]}$$

From Eq. 3.32, you can discover an interesting property of the quarter-wavelength transmission line. First, divide each side of the equation by Z_o:

$$\frac{Z}{Z_o} = \frac{[Z_o]^2}{Z_L Z_o} \qquad \textbf{[3.33]}$$

$$= \frac{Z_o}{Z_L} \qquad \textbf{[3.34]}$$

The ratio Z/Z_o shows an inversion of the load impedance ratio Z_L/Z_o, or, stated another way,

$$\frac{Z}{Z_o} = \frac{1}{Z_L/Z_o} \tag{3.35}$$

Again, from Eq. 3.32, you can deduce another truth about quarter-wavelength transmission lines:
If

$$Z = \frac{\sqrt{Z_o}}{Z_L} \tag{3.36}$$

then

$$ZZ_L = \sqrt{Z_o} \tag{3.37}$$

which means

$$Z_o = \sqrt{ZZ_L} \tag{3.38}$$

Equation 3.38 shows that a quarter-wavelength transmission line can be used as an *impedance matching network*. Called a *Q section*, the quarter-wavelength transmission line used for impedance matching requires a characteristic impedance Z_o—if Z is the source impedance and Z_L is the load impedance.

Example 3-6 A 50-Ω source must be matched to a load impedance of 36 Ω. Find the characteristic impedance required of a Q section matching network.

Solution:

$$\begin{aligned} Z &= \sqrt{ZZ_L} \\ &= \sqrt{(50\ \Omega)\ (36\ \Omega)} \\ &= \sqrt{1800\ \Omega^2} = 42\ \Omega \end{aligned}$$

6. Transmission line as a reactance: Reconsider Eq. 3.28, which related impedance looking in to load impedance and line length:

$$Z = (Z_o)\left[\frac{Z_L + jZ_o \tan (Bl)}{Z_o + jZ_L \tan (Bl)}\right] \tag{3.39}$$

Now, for the case of a shorted line (i.e., $Z_L = 0$), the solution is

$$Z = (Z_o)\left[\frac{(0) + jZ_o \tan (B\,l)}{Z_o + j(0) \tan (B\,l)}\right] \tag{3.40}$$

$$Z = (Z_o)\left[\frac{jZ_o \tan (Bl)}{Z_o}\right] \tag{3.41}$$

$$Z = j\,Z_o \tan (Bl) \tag{3.42}$$

Recall from Eq. 3.25 that

$$B = WZ_oC \tag{3.43}$$

Substituting Eq. 3.43 into Eq. 3.42 produces

$$Z = j\,Z_o \tan (\omega Z_oCl) \tag{3.44}$$

or

$$Z = j\,Z_o \tan (2\pi FZ_oCl) \tag{3.45}$$

Because the solutions to Eqs. 3.44 and 3.45 are multiplied by the j operator, the impedance is actually a reactance ($Z = 0 + jX$). It is possible to achieve almost any possible reactance (within certain practical limitations) by adjusting the length of the transmission line and shorting the “load” end. This fact leads us to a practical method for impedance matching.

Figure 3-10A shows a circuit in which an unmatched load is connected to a transmission line with characteristic impedance Z_o. The load impedance Z_L is of the form $Z = R \pm jX$, and, in this case, it is equal to $50 - j20$.

A complex impedance load can be matched to its source by interposing the complex conjugate of the impedance. For example, in the case where $Z = 50 - j20$, the matching impedance network will require an impedance of $50 + j20\ \Omega$. The two impedances combine to produce a result of 50 Ω. The situation of Fig. 3-10A shows a matching stub with a reactance equal in magnitude, but opposite in sign, with respect to the reactive component of the load impedance. In this case, the stub has a reactance of $+j20\ \Omega$ to cancel a reactance of $-j20\ \Omega$ in the load.

A *quarter-wavelength shorted stub* is a special case of the stub concept that finds particular application in microwave circuits. *Waveguides* (Chap. 19) are based on the properties of the quarter-wavelength shorted stub. Figure 3-10B shows a quarter-wave stub and its current distribution. The current is maximum across the short, but wave cancellation forces it to zero at the terminals. Because $Z = V/I$, when I goes to zero, the impedance becomes infinite. Thus, a quarter-wavelength stub has an infinite impedance at its resonant frequency, and redundant acts as an insulator. This concept may be hard to swallow, but the stub is a “metal insulator.”

Standing wave ratio

The reflection phenomenon was noted earlier during the coverage of the step-function and single-pulse response of a transmission line; the same phenomenon also applies when the transmission line is excited with an ac signal. When a transmission


Transmission line (Z_o = 50 Ω)
To source
R = 50 Ω
X= $-j20$ Ω
$Z_o = 50 - j20$ Ω
Z_o = 50 Ω
Shorted matching stub ($X = +j20$ Ω)

3-10A Stub matching system.

line is not matched to its load, some of the energy is absorbed by the load and some is reflected back down the line toward the source. The interference of incident (or "forward") and reflected (or "reverse") waves creates *standing waves* on the transmission line.

If the voltage or current is measured along the line, it will vary, depending on the load, according to Fig. 3-11. Figure 3-11A shows the voltage-versus-length curve for a matched line (i.e., where $Z_L = Z_o$). The line is said to be "flat" because the voltage (and current) is constant all along the line. But now consider Figs. 3-11B and 3-11C.

Figure 3-11B shows the voltage distribution over the length of the line when the load end of the line is *shorted* (i.e., $Z_L = 0$). Of course, at the load end the voltage is zero, which results from zero impedance. The same impedance and voltage situation is repeated every half-wavelength down the line from the load end toward the generator. Voltage *minima* are called *nodes*, and voltage *maxima* are called *antinodes*.

The pattern in Fig. 3-11C results when the line is unterminated (open) (i.e., $Z_L = \infty$). Note that the pattern is the same shape as Fig. 3-11B (shorted line), but the phase is shifted 90°. In both cases, the reflection is 100 percent, but the phase of the reflected wave is opposite.

Figure 3-11D shows the situation in which Z_L is not equal to Z_o, but is neither zero nor infinite. In this case, the nodes represent some finite voltage, V_{min}, rather



3-10B Quarter-wavelength stub.

than zero. The *standing wave ratio* (SWR) reveals the relationship between load and line.

If the current along the line is measured, the pattern will resemble the patterns of Fig. 3-11. The SWR is then called ISWR, to indicate the fact that it came from a current measurement. Similarly, if the SWR is derived from voltage measurements it is called VSWR. Perhaps because voltage is easier to measure, VSWR is the term most commonly used in most radio work.

VSWR can be specified in any of several equivalent ways:

1. *From incident voltage* (V_i) *and reflected voltage* (V_i):

$$\text{VSWR} = \frac{V_i + V_r}{V_i - V_r} \qquad \textbf{[3.46]}$$

2. *From transmission line voltage measurements (Fig. 3-11D):*

$$\text{VSWR} = \frac{V_{\max}}{V_{\min}} \qquad \textbf{[3.47]}$$

3. *From load and line characteristic impedances:*

$$(Z_L > Z_o)\ \text{VSWR} = Z_L/Z_o \qquad \textbf{[3.48]}$$

$$(Z_L < Z_o)\ \text{VSWR} = Z_o/Z_L \qquad \textbf{[3.49]}$$

4. *From incident (P_i) and reflected (P_r) power:*

$$\text{VSWR} = \frac{1 + \sqrt{P_r/P_i}}{1 - \sqrt{P_r/P_i}} \qquad \textbf{[3.50]}$$

5. *From reflection coefficient (Γ):*

$$\text{VSWR} = \frac{1 + \Gamma}{1 - \Gamma} \qquad \textbf{[3.51]}$$

It is also possible to determine the reflection coefficient Γ from a knowledge of VSWR:

$$\Gamma = \frac{\text{VSWR} - 1}{\text{VSWR} + 1} \qquad \textbf{[3.52]}$$

The relationship between reflection coefficient Γ and VSWR is shown in Fig. 3-11D.

VSWR is usually expressed as a *ratio*. For example, when Z_L is 100 Ω and Z_o is 50 Ω, the VSWR is $Z_L/Z_o = 100\ \Omega/50\ \Omega = 2$, which is usually expressed as VSWR = 2:1. VSWR can also be expressed in decibel form:

$$\text{VSWR} = 20 \log (\text{VSWR}) \qquad \textbf{[3.53]}$$

Example 3-7 A transmission line is connected to a mismatched load. Calculate both the VSWR and VSWR decibel equivalent if the reflection coefficient Γ is 0.25.

Solution:

$$(a)\ \text{VSWR} = \frac{1 + \Gamma}{1 - \Gamma}$$

$$= \frac{1 + 0.25}{1 - 0.25}$$

$$= \frac{1.25}{0.75} = 1.67{:}1$$

$$(b)\ \text{VSWR}_{\text{dB}} = 20 \log (\text{VSWR})$$

$$= (20)\ (\log 1.67)$$

$$= (20)\ (0.22) = 4.3\ \text{dB}$$



3-11 Voltage versus electrical length: (A) Matched impedances, (B) $Z_L = 0$, (C) Z_L = infinite.



3-11 Continued: (D) Z_L not equal to Z_o.

The SWR is regarded as important in systems for several reasons. The base of these reasons is the fact that the reflected wave represents energy lost to the load. For example, in an antenna system, less power is radiated if some of its input power is reflected back down the transmission line, because the antenna feedpoint impedance does not match the transmission line characteristic impedance. The next section covers the problem of mismatch losses.

Mismatch (VSWR) losses

The power reflected from a mismatched load represents a loss, and will have implications that range from negligible to profound, depending on the situation. For example, one result might be a slight loss of signal strength at a distant point from an antenna. A more serious problem can result in the destruction of the output device in a transmitter. The latter problem so plagued early solid-state transmitters that designers opted to include shutdown circuitry to sense high VSWR, and turn down output power proportionally.

In microwave measurements, VSWR on the transmission lines (that interconnect devices under test, instruments, and signal sources) can cause erroneous readings—and invalid measurements.

Determination of VSWR losses must take into account *two* VSWR situations. Figure 3-9 shows a transmission line of impedance Z_o interconnecting a load impedance Z_L, and a source with an output impedance Z_s. There is a potential for impedance mismatch at *both ends* of the line.

In the case where one end of the line is matched (either Z_s or Z_L), the *mismatch loss* caused by SWR at the mismatched end is

$$\mathrm{ML} = -10 \log \left[1 - \left(\frac{\mathrm{SWR} - 1}{\mathrm{SWR} + 1} \right)^2 \right] \qquad \textbf{[3.54]}$$

which from Eq. 3.52 is

$$\text{ML} = -10 \log (1 - \Gamma^2) \qquad \textbf{[3.55]}$$

Example 3-8 A coaxial transmission line with a characteristic impedance of 50 Ω is connected to the 50-Ω output (Z_o) of a signal generator, and also to a 20-W load impedance Z_L. Calculate the mismatch loss.

Solution:

(*a*) First find the VSWR:

$$\begin{aligned}\text{VSWR} &= Z_o/Z_L \\ &= (50\ \Omega)/(20\ \Omega) = 2.5{:}1\end{aligned}$$

(*b*) Mismatch loss:

$$\begin{aligned}\text{ML} &= -10 \log \left[1 - \left(\frac{\text{SWR} - 1}{\text{SWR} + 1} \right)^2 \right] \\ &= -10 \log \left[1 - \left(\frac{2.5 - 1}{2.5 + 1} \right)^2 \right] \\ &= -10 \log \left[1 - \left(\frac{1.5}{3.5} \right)^2 \right] \\ &= -10 \log [1 - (0.43)^2] \\ &= -10 \log [1 - 0.185] \\ &= -10 \log [0.815] \\ &= (-10)\ (-0.089) = 0.89\end{aligned}$$

When both ends of the line are mismatched, a different equation is required:

$$\text{ML} = 20 \log [1 \pm (\Gamma_1 \times \Gamma_2)] \qquad \textbf{[3.56]}$$

where

Γ_1 is the reflection coefficient at the source end of the line, $(VSWR_1 - 1)/(VSWR_1 + 1)$

Γ_2 is the reflection coefficient at the load end of the line, $(VSWR_2 - 1)/(VSWR_2 + 1)$

Note that the solution to Eq. 3.56 has two values: $[1 + (\Gamma_1\Gamma_2)]$ and $[1 - (\Gamma_1\Gamma_2)]$.

The equations reflect the mismatch loss solution for low-loss or “lossless” transmission lines. This is a close approximation in some situations; however, it is insufficient when the line is lossy. Although not very important at low frequencies, loss becomes higher at microwave frequencies. Interference between incident and reflected waves produces increased current at certain antinodes—which increases ohmic losses—and increased voltage at certain antinodes—which increases dielectric losses. It is the latter that increases with frequency. Equation 3.57 relates reflection coefficient and line losses to determine total loss on a given line.

$$\text{Loss} = 10 \log \left(\frac{n^2 - \Gamma^2}{n - n\Gamma^2} \right) \qquad \textbf{[3.57]}$$

where

Loss is the total line loss in decibels
Γ is the reflection coefficient
n is the quantity $10^{(A/10)}$
A is the total attenuation presented by the line, in decibels, when the line is properly matched ($Z_L = Z_o$)

Example 3-9 A 50-Ω transmission line is terminated in a 30-Ω resistive impedance. The line is rated at a loss of 3 dB/100 ft at 1 GHz. Calculate (a) loss in 5 ft of line, (*b*) reflection coefficient, and (*c*) total loss in a 5-ft line mismatched per above.

Solution:

$$(a)\ A = \frac{3\text{ dB}}{100\text{ ft}} \times 5\text{ ft} = 0.15\text{ dB}$$

$$(b)\ \Gamma = \frac{Z_L - Z_o}{Z_L + Z_o}$$

$$= \frac{50 - 30}{50 + 30}$$

$$= 20/80 = 0.25$$

$$(c)\ n = 10^{(A/10)}$$

$$= 10^{(0.15/10)}$$

$$= 10^{(0.015)} = 1.04$$

$$\text{Loss} = 10 \log \left(\frac{n^2 - \Gamma^2}{n - n\Gamma^2} \right)$$

$$= 10 \log \left[\frac{(1.04)^2 - (0.25)^2}{1.04 - (1.04)\ (0.25)^2} \right]$$

$$= 10 \log \left[\frac{1.082 - 0.063}{1.04 - (1.04)\ (0.063)} \right]$$

$$= 10 \log \left(\frac{1.019}{1.04 - 0.066} \right)$$

$$= 10 \log \left(\frac{1.019}{0.974} \right)$$

$$= 10 \log (1.046)$$

$$= (10)\ (0.02) = 0.2 \text{ dB}$$

Compare the matched line loss ($A = 0.15$ dB) with the total loss (Loss = 0.2 dB), which includes mismatch loss and line loss. The difference (i.e., Loss – A) is only 0.05 dB. If the VSWR was considerably larger, however, the loss would rise.

4
CHAPTER

The Smith chart

THE MATHEMATICS OF TRANSMISSION LINES, AND CERTAIN OTHER DEVICES, BECOMES cumbersome at times, especially in dealing with complex impedances and “nonstandard” situations. In 1939, Phillip H. Smith published a graphical device for solving these problems, and an improved version of the chart followed in 1945. That graphic aid, somewhat modified over time, is still in constant use in microwave electronics, and other fields where complex impedances and transmission line problems are found. The *Smith chart* is indeed a powerful tool for the RF designer.

Smith chart components

The modern Smith chart is shown in Fig. 4-1. It consists of a series of overlapping orthogonal circles (i.e., circles that intersect each other at right angles). This chapter will dissect the Smith chart, so that the origin and use of these circles is apparent. The set of orthogonal circles makes up the basic structure of the Smith chart.

The normalized impedance line

A baseline is highlighted in Fig. 4-2, and bisects the Smith chart outer circle. This line is called the *pure resistance line*, and forms the reference for measurements made on the chart. Recall that a complex impedance contains both resistance and reactance, and is expressed in the mathematical form:

$$Z = R \pm jX \qquad \textbf{[4.1]}$$

Copyright 2001 - the McGraw-Hill Companies


NAME
TITLE
DWG. NO.
SMITH CHART FORM 82-BSPR (9-66)
KAY ELECTRIC COMPANY, PINE BROOK, N.J. © 1966. PRINTED IN U.S.A.
DATE
IMPEDANCE OR ADMITTANCE COORDINATES
INDUCTIVE REACTANCE COMPONENT (+jX/Zo), OR CAPACITIVE SUSCEPTANCE COMPONENT (+jB/Yo)
CAPACITIVE REACTANCE COMPONENT (−jX/Zo), OR INDUCTIVE SUSCEPTANCE COMPONENT (−jB/Yo)
RESISTANCE COMPONENT (R/Zo), OR CONDUCTANCE COMPONENT (G/Yo)
WAVELENGTHS TOWARD GENERATOR
WAVELENGTHS TOWARD LOAD
ANGLE OF REFLECTION COEFFICIENT IN DEGREES
ANGLE OF TRANSMISSION COEFFICIENT IN DEGREES
RADIALLY SCALED PARAMETERS
TOWARD LOAD
TOWARD GENERATOR
SWR
RET'N LOSS dB
REFL. COEFF. P
REFL. COEFF. E OR I
ATTEN. 1dB MAJ. DIV.
S.W. LOSS COEFF.
REFL. LOSS dB
S.W. PEAK (CONST. P)
TRANSM. COEFF. E OR I
TRANSM. COEFF. P
CENTER
ORIGIN

4-1 The Smith chart. (*Courtesy of Kay Elementrics*)

where

Z is the complex impedance
R is the resistive component of the impedance
X is the reactive component of the impedance*

The pure resistance line represents the situation where $X = 0$, and the impedance is therefore equal to the resistive component only. In order to make the Smith chart universal, the impedances along the pure resistance line are *normalized* with reference to system impedance (e.g., Z_o in transmission lines); for most microwave RF systems the system impedance is standardized at 50 Ω. In order to normalize the actual impedance, divide it by the system impedance. For example, if the load impedance of a transmission line is Z_L, and the characteristic impedance of the line is Z_o, then $Z = Z_L/Z_o$. In other words,

$$Z = \frac{R \pm jX}{Z_o} \quad \textbf{[4.2]}$$

The pure resistance line is structured such that the system standard impedance is in the center of the chart, and has a normalized value of 1.0 (see point A in Fig. 4-2). This value derives from the fact that $Z_o/Z_o = 1.0$.

To the left of the 1.0 point are decimal fraction values used to denote impedances less than the system impedance. For example, in a 50-Ω transmission line system with a 25-Ω load impedance, the normalized value of impedance is 25 Ω/50 Ω or 0.50 ("B" in Fig. 4-2). Similarly, points to the right of 1.0 are greater than 1 and denote impedances that are higher than the system impedance. For example, in a 50-Ω system connected to a 100-Ω resistive load, the normalized impedance is 100 Ω/50 Ω, or 2.0; this value is shown as point C in Fig. 4-2. By using normalized impedances, you can use the Smith chart for almost any practical combination of system, and load and/or source, impedances, whether resistive, reactive, or complex.

Reconversion of the normalized impedance to actual impedance values is done by multiplying the normalized impedance by the system impedance. For example, if the resistive component of a normalized impedance is 0.45, then the actual impedance is

$$Z = (Z_{\text{normal}})\,(Z_o) \quad \textbf{[4.3]}$$

$$= (0.45)\,(50\ \Omega) \quad \textbf{[4.4]}$$

$$= 22.5\ \Omega \quad \textbf{[4.5]}$$

The constant resistance circles

The *isoresistance circles*, also called the *constant resistance circles*, represent points of equal resistance. Several of these circles are shown highlighted in Fig. 4-3. These circles are all tangent to the point at the righthand extreme of the pure resis-

---

*According to the standard sign convention the inductive reactance (X_L) is positive (+) and the capacitive reactance (X_c) is negative (–). The term X in Eq. 4.1 above is the difference between the two reactances ($X = X_L - X_c$).


NAME
TITLE
DWG. NO.
DATE
SMITH CHART FORM 82-BSPR(9-66)
KAY ELECTRIC COMPANY, PINE BROOK, N.J., © 1966. PRINTED IN U.S.A.
IMPEDANCE OR ADMITTANCE COORDINATES
B
A
C
RESISTANCE COMPONENT (R/Zo), OR CONDUCTANCE COMPONENT (G/Yo)
INDUCTIVE REACTANCE COMPONENT (+jX/Zo), OR CAPACITIVE SUSCEPTANCE COMPONENT (+jB/Yo)
CAPACITIVE REACTANCE COMPONENT (-jX/Zo), OR INDUCTIVE SUSCEPTANCE COMPONENT (-jB/Yo)
WAVELENGTHS TOWARD GENERATOR
WAVELENGTHS TOWARD LOAD
ANGLE OF REFLECTION COEFFICIENT IN DEGREES
ANGLE OF TRANSMISSION COEFFICIENT IN DEGREES
RADIALLY SCALED PARAMETERS
TOWARD LOAD
TOWARD GENERATOR
SWR
dBS
RTN. LOSS, dB
REFL. COEFF. P
REFL. COEFF. E OR I
ATTEN. 1 dB MAJ. DIV.
S.W. LOSS COEFF.
REFL. LOSS, dB
S.W. PEAK CONST. P
TRANSM. COEFF. P
TRANSM. COEFF. E OR I
CENTER
ORIGIN

4-2 Normalized impedance line. (*Courtesy of Kay Elementrics*)


NAME
TITLE
DWG. NO.
DATE
SMITH CHART FORM 82-BSPR (9-66)
KAY ELECTRIC COMPANY, PINE BROOK, N.J., © 1966 PRINTED IN U.S.A.
IMPEDANCE OR ADMITTANCE COORDINATES
A
RESISTANCE COMPONENT (R/Zo), OR CONDUCTANCE COMPONENT (G/Yo)
INDUCTIVE REACTANCE COMPONENT (+jX/Zo), OR CAPACITIVE SUSCEPTANCE COMPONENT (+jB/Yo)
CAPACITIVE REACTANCE COMPONENT (-jX/Zo), OR INDUCTIVE SUSCEPTANCE COMPONENT (-jB/Yo)
WAVELENGTHS TOWARD GENERATOR
WAVELENGTHS TOWARD LOAD
ANGLE OF REFLECTION COEFFICIENT IN DEGREES
ANGLE OF TRANSMISSION COEFFICIENT IN DEGREES
RADIALLY SCALED PARAMETERS
TOWARD LOAD
TOWARD GENERATOR
SWR
dBS
RET'N LOSS, dB
REFL. COEFF, P
REFL. COEFF, E OR I
ATTEN. 1dB MAJ. DIV.
S.W. LOSS COEFF
REFL. LOSS, dB
S.W. PEAK (CONST. P)
TRANSM. COEFF, P
TRANSM. COEFF, E OR I
CENTER
ORIGIN

4-3 Constant resistance circles. (*Courtesy of Kay Elementrics*) tance line, and are bisected by that line. When you construct complex impedances (for which X = nonzero) on the Smith chart, the points on these circles will all have the same resistive component. Circle *A*, for example, passes through the center of the chart, so it has a normalized constant resistance of 1.0. Note that impedances that are pure resistances (i.e., $Z = R + j0$) will fall at the intersection of a constant resistance circle and the pure resistance line, and complex impedances (i.e., X not equal to zero) will appear at any other points on the circle. In Fig. 4-3, circle *A* passes through the center of the chart, so it represents all points on the chart with a normalized resistance of 1.0. This particular circle is sometimes called the *unity resistance circle*.

The constant reactance circles

Constant reactance circles are highlighted in Fig. 4-4. The circles (or circle segments) *above* the pure resistance line (Fig. 4-4A) represent the *inductive reactance* ($+X$), and those circles (or segments) *below* the pure resistance line (Fig. 4-4B) represent *capacitive reactance* ($-X$). In both cases, circle *A* represents a normalized reactance of 0.80.

One of the outer circles (i.e., circle *A* in Fig. 4-4C) is called the *pure reactance circle*. Points along circle *A* represent reactance only; in other words, an impedance of $Z = 0 \pm jX$ ($R = 0$).

Figure 4-4D shows how to plot impedance and admittance on the Smith chart. Consider an example in which system impedance Z_o is 50 Ω, and the load impedance is $Z_L = 95 + j55\ \Omega$. This load impedance is normalized to

$$Z = \frac{Z_L}{Z_o} \qquad \textbf{[4.6]}$$

$$= \frac{95 + j55\ \Omega}{50\ \Omega} \qquad \textbf{[4.7]}$$

$$= 1.9 + j1.1 \qquad \textbf{[4.8]}$$

An *impedance radius* is constructed by drawing a line from the point represented by the normalized load impedance, $1.9 + j1.1$, to the point represented by the normalized system impedance (1.0) in the center of the chart. A circle is constructed from this radius, and is called the *VSWR circle.*

Admittance is the reciprocal of impedance, so it is found from

$$Y = \frac{1}{Z} \qquad \textbf{[4.9]}$$

Because impedances in transmission lines are rarely pure resistive, but rather contain a reactive component also, impedances are expressed by complex notation:

$$Z = R \pm jX \qquad \textbf{[4.10]}$$


NAME
TITLE
DWG. NO.
DATE
SMITH CHART FORM 82-BSPR (9-66)
KAY ELECTRIC COMPANY, PINE BROOK, N.J., © 1966 PRINTED IN U.S.A.
IMPEDANCE OR ADMITTANCE COORDINATES
A
WAVELENGTHS TOWARD GENERATOR
WAVELENGTHS TOWARD LOAD
INDUCTIVE REACTANCE COMPONENT (+jX/Zo), OR CAPACITIVE SUSCEPTANCE COMPONENT (+jB/Yo)
CAPACITIVE REACTANCE COMPONENT (-jX/Zo), OR INDUCTIVE SUSCEPTANCE COMPONENT (-jB/Yo)
RESISTANCE COMPONENT (R/Zo), OR CONDUCTANCE COMPONENT (G/Yo)
ANGLE OF REFLECTION COEFFICIENT IN DEGREES
ANGLE OF TRANSMISSION COEFFICIENT IN DEGREES
RADIALLY SCALED PARAMETERS
TOWARD LOAD
TOWARD GENERATOR
SWR
RET'N dBS
RET'N LOSS dB
REFL. COEFF. P
REFL. COEFF. E OR I
ATTEN. 1 dB MAJ. DIV.
S.W. LOSS COEFF.
S.W. PEAK CONST. P
TRANSM. COEFF. P
TRANSM. COEFF. E OR I
CENTER

4-4A Constant inductive reactance lines. (*Courtesy of Kay Elementrics*)


NAME
TITLE
DWG. NO
DATE
SMITH CHART FORM 82-BSPR(9-66)
KAY ELECTRIC COMPANY, PINE BROOK, N.J., © 1966 PRINTED IN U.S.A.
IMPEDANCE OR ADMITTANCE COORDINATES
WAVELENGTHS TOWARD GENERATOR
WAVELENGTHS TOWARD LOAD
INDUCTIVE REACTANCE COMPONENT (+jX/Zo) OR CAPACITIVE SUSCEPTANCE COMPONENT (+jB/Yo)
RESISTANCE COMPONENT (R/Zo), OR CONDUCTANCE COMPONENT (G/Yo)
CAPACITIVE REACTANCE COMPONENT (-jX/Zo) OR INDUCTIVE SUSCEPTANCE COMPONENT (-jB/Yo)
ANGLE OF REFLECTION COEFFICIENT IN DEGREES
ANGLE OF TRANSMISSION COEFFICIENT IN DEGREES
A
RADIALLY SCALED PARAMETERS
TOWARD LOAD
TOWARD GENERATOR
SWR
dBS
RET'N LOSS, dB
REFL. COEFF, P
REFL. COEFF, E OR I
ATTEN. 1dB MAJ. DIV.
S.W. LOSS COEFF
REFL. LOSS, dB
S.W. PEAK (CONST. P)
TRANSM. COEFF, P
TRANSM. COEFF, E OR I
CENTER
ORIGIN

4-4B Constant capacitive reactance lines. (*Courtesy of Kay Elementrics*)


NAME
TITLE
DWG. NO
SMITH CHART FORM 82-BSPR(9-66)
KAY ELECTRIC COMPANY, PINE BROOK, N.J. © 1966 PRINTED IN U.S.A.
DATE
IMPEDANCE OR ADMITTANCE COORDINATES
A
B
C
WAVELENGTHS TOWARD GENERATOR
WAVELENGTHS TOWARD LOAD
INDUCTIVE REACTANCE COMPONENT (+jX/Zo), OR CAPACITIVE SUSCEPTANCE COMPONENT (+jB/Yo)
CAPACITIVE REACTANCE COMPONENT (-jX/Zo), OR INDUCTIVE SUSCEPTANCE COMPONENT (-jB/Yo)
RESISTANCE COMPONENT (R/Zo), OR CONDUCTANCE COMPONENT (G/Yo)
ANGLE OF REFLECTION COEFFICIENT IN DEGREES
ANGLE OF TRANSMISSION COEFFICIENT IN DEGREES
RADIALLY SCALED PARAMETERS
TOWARD LOAD
TOWARD GENERATOR
SWR
RET'N LOSS dB
REFL. COEFF. P
REFL. COEFF. E OR I
ATTEN (dB MAJ. DIV.)
S.W. LOSS COEFF.
REFL. LOSS dB
S.W. PEAK CONST. P
TRANSM. COEFF. P
TRANSM. COEFF. E OR I
CENTER
ORIGIN
A MEGA-CHART
D
E
F
G

4-4C Angle of transmission coefficient circle. (*Courtesy of Kay Elementrics*)


NAME
TITLE
DWG. NO.
DATE
SMITH CHART FORM 82-BSPR(9-66)
KAY ELECTRIC COMPANY, PINE BROOK, N.J., © 1966 PRINTED IN U.S.A.
IMPEDANCE OR ADMITTANCE COORDINATES
VSWR circle
Impedance radius
Z = 1.9 + j1.1
Y = 0.39 − j0.23
RESISTANCE COMPONENT (R/Zo) OR CONDUCTANCE COMPONENT (G/Yo)
INDUCTIVE REACTANCE COMPONENT (+jX/Zo) OR CAPACITIVE SUSCEPTANCE COMPONENT (+jB/Yo)
CAPACITIVE REACTANCE COMPONENT (−jX/Zo) OR INDUCTIVE SUSCEPTANCE COMPONENT (−jB/Yo)
WAVELENGTHS TOWARD GENERATOR
WAVELENGTHS TOWARD LOAD
ANGLE OF REFLECTION COEFFICIENT IN DEGREES
ANGLE OF TRANSMISSION COEFFICIENT IN DEGREES
RADIALLY SCALED PARAMETERS
TOWARD LOAD
TOWARD GENERATOR
SWR
RET'N LOSS dBS
REFL. COEFF. P
REFL. COEFF. E OR I
ATTEN. 1dB MAJ. DIV.
S.W. LOSS COEFF.
S.W. PEAK (CONST. P)
TRANSM. COEFF. P
TRANSM. COEFF. E OR I
CENTER
ORIGIN

4-4D VSWR circles. *(Courtesy of Kay Elementrics)*

where

Z is the complex impedance
R is the resistive component
X is the reactive component

In order to find the *complex admittance*, take the reciprocal of the complex impedance by multiplying the simple reciprocal by the complex conjugate of the impedance. For example, when the normalized impedance is $1.9 + j1.1$, the normalized admittance will be:

$$Y = \frac{1}{Z} \qquad \textbf{[4.11]}$$

$$= \frac{1}{1.9 + j1.1} \times \frac{1.9 - j1.1}{1.9 - j1.1} \qquad \textbf{[4.12]}$$

$$= \frac{1.9 - j1.1}{3.6 + 1.2} \qquad \textbf{[4.13]}$$

$$= \frac{1.9 - j1.1}{4.8} = 0.39 - j0.23 \qquad \textbf{[4.14]}$$

One of the delights of the Smith chart is that this calculation is reduced to a quick graphical interpretation! Simply extend the impedance radius through the 1.0 center point until it intersects the VSWR circle again. This point of intersection represents the normalized admittance of the load.

Outer circle parameters

The standard Smith chart shown in Fig. 4-4C contains three concentric calibrated circles on the outer perimeter of the chart. Circle A has already been covered and it is the pure reactance circle. The other two circles define the wavelength distance (B) relative to either the load or generator end of the transmission line, and either the transmission or reflection coefficient angle in degrees (C).

There are two scales on the *wavelength* circle (B in Fig 4-4C), and both have their zero origin on the left-hand extreme of the pure resistance line. Both scales represent *one-half wavelength for one entire revolution*, and are calibrated from 0 through 0.50 such that these two points are identical with each other on the circle. In other words, starting at the zero point and travelling 360° around the circle brings one back to zero, which represents one-half wavelength, or $0.5\ \lambda$.

Although both wavelength scales are of the same magnitude (0 – 0.50), they are opposite in direction. The outer scale is calibrated clockwise and it represents *wavelengths toward the generator*; the inner scale is calibrated counterclockwise and represents *wavelengths toward the load*. These two scales are complementary at all points. Thus, 0.12 on the outer scale corresponds to (0.50 – 0.12) or 0.38 on the inner scale.

The *angle of transmission coefficient* and *angle of reflection coefficient* scales are shown in circle *C* in Fig. 4-4C. These scales are the relative phase angle between reflected and incident waves. Recall from transmission line theory (see Chap. 3), that a short circuit at the load end of the line reflects the signal back toward the generator 180° out of phase with the incident signal; an open line (i.e., infinite impedance) reflects the signal back to the generator in phase (i.e., 0°) with the incident signal. These facts are shown on the Smith chart by the fact that both scales start at 0° on the right-hand end of the pure resistance line, which corresponds to an infinite resistance, and it goes halfway around the circle to 180° at the 0 end of the pure resistance line. Note that the upper half-circle is calibrated 0 to +180°, and the bottom half-circle is calibrated 0 to –180°, reflecting indictive or capacitive reactance situations, respectively.

Radially scaled parameters

There are six scales laid out on five lines (*D* through *G* in Fig. 4-4C and in expanded form in Fig. 4-5) at the bottom of the Smith chart. These scales are called the *radially scaled parameters*—and they are both very important, and often overlooked. With these scales, we can determine such factors as VSWR (both as a ratio and in decibels), return loss in decibels, voltage or current reflection coefficient, and the power reflection coefficient.

The *reflection coefficient* Γ is defined as the *ratio of the reflected signal to the incident signal*. For voltage or current:

$$\Gamma = \frac{E_{\text{ref}}}{E_{\text{inc}}} \tag{4.15}$$

and

$$\Gamma = \frac{I_{\text{ref}}}{I_{\text{inc}}} \tag{4.16}$$

Power is proportional to the square of voltage or current, so:

$$P_{\text{pwr}} = \Gamma^2 \tag{4.17}$$

or

$$\Gamma_{\text{pwr}} = \frac{P_{\text{ref}}}{P_{\text{inc}}} \tag{4.18}$$

Example 10 W of microwave RF power is applied to a lossless transmission line, of which 2.8 W is reflected from the mismatched load. Calculate the reflection coefficient.

$$\Gamma_{\text{pwr}} = \frac{P_{\text{ref}}}{P_{\text{inc}}} \tag{4.19}$$


RADIALLY SCALED PARAMETERS
TOWARD LOAD
TOWARD GENERATOR
CENTER
ORIGIN
A MEGA-CHART
SWR
RET'N LOSS, dB
REFL. COEFF. P
REFL. COEFF. E OR I
ATTEN 1dB MAJ. DIV.
S.W. LOSS COEFF.
S.W. PEAK (CONST. P)
TRANSM. COEFF. P
TRANSM. COEFF. E OR I
CAPACITIVE REACTANCE COMPONENT (-jX/Zo), OR INDUCTIVE SUSCEPTANCE COMPONENT (-jB/Yo)
WAVELENGTHS TOWARD
IN DEGREES
A
B
C
D

4-5 Radially scaled parameters.

$$\Gamma_{\text{pwr}} = \frac{2.8\ \text{W}}{10\ \text{W}} \qquad \textbf{[4.20]}$$

$$= 0.28 \qquad \textbf{[4.21]}$$

The voltage reflection coefficient Γ is found by taking the square root of the power reflection coefficient, so in this example it is equal to 0.529. These points are plotted at *A* and *B* in Fig. 4-5.

Standing wave ratio (SWR) can be defined in terms of reflection coefficient:

$$\text{VSWR} = \frac{1+\Gamma}{1-\Gamma} \qquad \textbf{[4.22]}$$

or

$$\text{VSWR} = \frac{1+\sqrt{\Gamma_{\text{pwr}}}}{1-\sqrt{\Gamma_{\text{pwr}}}} \qquad \textbf{[4.23]}$$

or, in our example,

$$\text{VSWR} = \frac{1+\sqrt{0.28}}{1-\sqrt{0.28}} \qquad \textbf{[4.24]}$$

$$= \frac{1+0.529}{1-0.529} \qquad \textbf{[4.25]}$$

$$= \frac{1.529}{0.471} = 3.25{:}1 \qquad \textbf{[4.26]}$$

or, in decibel form,

$$\text{VSWR}_{\text{dB}} = 20 \log (\text{VSWR}) \qquad \textbf{[4.27]}$$

$$= 20 \log (20) \qquad \textbf{[4.28]}$$

$$= (20)\ (0.510) = 10.2\ \text{dB} \qquad \textbf{[4.29]}$$

These points are plotted at *C* in Fig. 4-5. Shortly, you will work an example to show how these factors are calculated in a transmission line problem from a known complex load impedance.

Transmission loss is a measure of the one-way loss of power in a transmission line because of reflection from the load. *Return loss* represents the two-way loss, so it is exactly twice the transmission loss. Return loss is found from

$$\text{Loss}_{\text{ret}} = 10 \log (\Gamma_{\text{pwr}}) \qquad \textbf{[4.30]}$$

and, for our example in which $\Gamma_{\text{pwr}} = 0.28$,

$$\text{Loss}_{\text{ret}} = 10 \log (0.28) \qquad \textbf{[4.31]}$$

$$= (10)\ (-0.553) = -5.53\ \text{dB} \qquad \textbf{[4.32]}$$

This point is shown as *D* in Fig. 4-5.

The *transmission loss coefficient* can be calculated from

$$\text{TLC} = \frac{1 + \Gamma_{\text{pwr}}}{1 - \Gamma_{\text{pwr}}} \qquad \mathbf{[4.33]}$$

or, for our example,

$$\text{TLC} = \frac{1 + (0.28)}{1 - (0.28)} \qquad \mathbf{[4.34]}$$

$$= \frac{1.28}{0.72} = 1.78 \qquad \mathbf{[4.35]}$$

The TLC is a correction factor that is used to calculate the attenuation caused by mismatched impedance in a lossy, as opposed to the ideal “lossless,” line. The TLC is found from laying out the impedance radius on the *loss coefficient* scale on the radially scaled parameters at the bottom of the chart.

Smith chart applications

One of the best ways to demonstrate the usefulness of the Smith chart is by practical example. The following sections look at two general cases: *transmission line problems* and *stub matching systems*.

Transmission line problems

Figure 4-6 shows a 50-Ω transmission line connected to a complex load impedance Z_L of $36 + j40\ \Omega$. The transmission line has a velocity factor v of 0.80, which means that the wave propagates along the line at $\frac{8}{10}$ the speed of light (c = 300,000,000 m/s). The length of the transmission line is 28 cm. The generator V_{in} is operated at a frequency of 4.5 GHz and produces a power output of 1.5 W. See what you can glean from the Smith chart (Fig. 4-7).

First, normalize the load impedance. This is done by dividing the load impedance by the systems impedance (in this case, $Z_o = 50\ \Omega$):

$$Z = \frac{36 + j40\ \Omega}{50\ \Omega} \qquad \mathbf{[4.36]}$$

$$= 0.72 + j0.8 \qquad \mathbf{[4.37]}$$

The resistive component of impedance *Z* is located along the 0.72 pure resistance circle (see Fig. 4-7). Similarly, the reactive component of impedance *Z* is located by traversing the 0.72 constant resistance circle until the $+j0.8$ constant reactance circle is intersected. This point graphically represents the normalized load impedance $Z = 0.72 + j0.80$. A VSWR circle is constructed with an impedance radius equal to the line between 1.0 (in the center of the chart) and the $0.72 + j0.8$ point.



4-6 Transmission line and load circuit.

At a frequency of 4.5 GHz, the length of a wave propagating in the transmission line, assuming a velocity factor of 0.80, is

$$\lambda_{\text{line}} = \frac{c\ v}{F_{\text{Hz}}} \qquad \textbf{[4.38]}$$

$$= \frac{(3 \times 10^8 \text{ m/s})\ (0.80)}{4.5 \times 10^9 \text{ Hz}} \qquad \textbf{[4.39]}$$

$$= \frac{2.4 \times 10^8 \text{ m/s}}{4.5 \times 10^9 \text{ Hz}} \qquad \textbf{[4.40]}$$

$$= 0.053 \text{ m} \times \frac{100 \text{ cm}}{\text{m}} = 5.3 \text{ cm} \qquad \textbf{[4.41]}$$

One wavelength is 5.3 cm, so a half-wavelength is 5.3 cm/2, or 2.65 cm. The 28-cm line is 28 cm/5.3 cm, or 5.28 wavelengths long. A line drawn from the center (1.0) to the load impedance is extended to the outer circle, and it intersects the circle at 0.1325. Because one complete revolution around this circle represents one-half wavelength, 5.28 wavelengths from this point represents 10 revolutions plus 0.28 more. The residual 0.28 wavelengths is added to 0.1325 to form a value of (0.1325 + 0.28), or 0.413. The point 0.413 is located on the circle, and is marked. A line is then drawn from 0.413 to the center of the circle, and it intersects the VSWR circle at $0.49 - j0.49$, which represents the input impedance Z_{in} looking into the line.

To find the actual impedance represented by the normalized input impedance, you have to "denormalize" the Smith chart impedance by multiplying the result by Z_o:


NAME
TITLE
DWG. NO
DATE
SMITH CHART FORM 82-BSPR(9-66)
KAY ELECTRIC COMPANY, PINE BROOK, N.J., © 1966. PRINTED IN U.S.A.
IMPEDANCE OR ADMITTANCE COORDINATES
$Z = 0.72 + j0.8$
VSWR circle
Impedance radius
$Z_{\text{in}} = 0.49 - j0.49$
$Y = 0.62 - j0.69$
0.413
RESISTANCE COMPONENT $\left(\frac{R}{Z_0}\right)$, OR CONDUCTANCE COMPONENT $\left(\frac{G}{Y_0}\right)$
INDUCTIVE REACTANCE COMPONENT $\left(\frac{+jX}{Z_0}\right)$, OR CAPACITIVE SUSCEPTANCE COMPONENT $\left(\frac{+jB}{Y_0}\right)$
CAPACITIVE REACTANCE COMPONENT $\left(\frac{-jX}{Z_0}\right)$, OR INDUCTIVE SUSCEPTANCE COMPONENT $\left(\frac{-jB}{Y_0}\right)$
WAVELENGTHS TOWARD GENERATOR
WAVELENGTHS TOWARD LOAD
ANGLE OF REFLECTION COEFFICIENT IN DEGREES
ANGLE OF TRANSMISSION COEFFICIENT IN DEGREES
RADIALLY SCALED PARAMETERS
TOWARD LOAD
TOWARD GENERATOR
2.6
1.5
7 dB
− 1.05
0.2
0.44
CENTER
ORIGIN

4-7 Solution to example. (*Courtesy of Kay Elementrics*)

$$Z_{\text{in}} = (0.49 - j0.49)\ (50\ \Omega) \quad \textbf{[4.42]}$$

$$= 24.5 - j24.5\ \Omega \quad \textbf{[4.43]}$$

It is this impedance that must be matched at the generator by a conjugate matching network.

The admittance represented by the load impedance is the reciprocal of the load impedance, and is found by extending the impedance radius through the center of the VSWR circle until it intersects the circle again. This point is found, and represents the admittance $Y = 0.62 - j0.69$. Confirming the solution mathematically:

$$Y = \frac{1}{Z} \quad \textbf{[4.44]}$$

$$= \frac{1}{0.72 + j0.80} \times \frac{0.72 - j0.80}{0.72 - j0.80} \quad \textbf{[4.45]}$$

$$= \frac{0.72 - j0.80}{1.16} = 0.62 - j0.69 \quad \textbf{[4.46]}$$

The VSWR if found by transferring the "impedance radius" of the VSWR circle to the radial scales below. The radius (0.72 – 0.8) is laid out on the VSWR scale (topmost of the radially scaled parameters) with a pair of dividers from the center mark, and we find that the VSWR is approximately 2.6:1. The decibel form of VSWR is 8.3 dB (next scale down from VSWR), and this is confirmed by

$$\text{VSWR}_{\text{dB}} = 20 \log (\text{VSWR}) \quad \textbf{[4.47]}$$

$$= (20) \log (2.7) \quad \textbf{[4.48]}$$

$$= (20)\ (0.431) = 8.3\ \text{dB} \quad \textbf{[4.49]}$$

The transmission loss coefficient is found in a manner similar to the VSWR, using the radially scaled parameter scales. In practice, once you have found the VSWR you need only drop a perpendicular line from the 2.6:1 VSWR line across the other scales. In this case, the line intersects the voltage reflection coefficient at 0.44. The power reflection coefficient Γ_{pwr} is found from the scale, and is equal to Γ^2. The perpendicular line intersects the power reflection coefficient line at 0.20.

The angle of reflection coefficient is found from the outer circles of the Smith chart. The line from the center to the load impedance ($Z = 0.72 + j0.8$) is extended to the *angle of reflection coefficient in degrees* circle, and intersects it at approximately 84°. The reflection coefficient is therefore 0.44/84°.

The transmission loss coefficient (TLC) is found from the radially scaled parameter scales also. In this case, the impedance radius is laid out on the *loss coefficient* scale, where it is found to be 1.5. This value is confirmed from:

$$\text{TLC} = \frac{1 + \Gamma_{\text{pwr}}}{1 - \Gamma_{\text{pwr}}} \quad \textbf{[4.50]}$$

$$= \frac{1 + (0.20)}{1 - (0.21)} \quad \textbf{[4.51]}$$

$$= \frac{1.20}{0.79} = 1.5 \quad \textbf{[4.52]}$$

The *return loss* is also found by dropping the perpendicular from the VSWR point to the *RET'N LOSS, dB* line, and the value is found to be approximately 7 dB, which is confirmed by

$$\text{Loss}_{\text{ret}} = 10 \log (\Gamma_{\text{pwr}}) \text{ dB} \quad \textbf{[4.53]}$$

$$= 10 \log (0.21) \text{ dB} \quad \textbf{[4.54]}$$

$$= (10)\,(-0.677) \text{ dB} \quad \textbf{[4.55]}$$

$$= 6.77 \text{ dB} = -6.9897 \text{ dB} \quad \textbf{[4.56]}$$

The reflection loss is the amount of RF power reflected back down the transmission line from the load. The difference between incident power supplied by the generator (1.5 W in this example), $P_{\text{inc}} - P_{\text{ref}} = P_{\text{abs}}$ and the reflected power, is the *absorbed power* (P_a); or in the case of an antenna, the radiated power. The reflection loss is found graphically by dropping a perpendicular from the TLC point (or by laying out the impedance radius on the *REFL*. *LOSS*, *dB* scale), and in this example (Fig. 4-7) is –1.05 dB. You can check the calculations:

The return loss is –7 dB, so

$$-7 \text{ dB} = 10 \log \left(\frac{P_{\text{ref}}}{P_{\text{inc}}} \right) \quad \textbf{[4.57]}$$

$$-7 = 10 \log \left(\frac{P_{\text{ref}}}{1.5 \text{ watts}} \right) \quad \textbf{[4.58]}$$

$$\frac{-7}{10} = \log \left(\frac{P_{\text{ref}}}{1.5 \text{ watts}} \right) \quad \textbf{[4.59]}$$

$$10^{(-7/10)} = \frac{P_{\text{ref}}}{1.5 \text{ W}} \quad \textbf{[4.60]}$$

$$0.2 = \frac{P_{\text{ref}}}{1.5 \text{ W}} \quad \textbf{[4.61]}$$

$$(0.2)(1.5 \text{ W}) = P_{\text{ref}} \quad \textbf{[4.62]}$$

$$0.3 \text{ W} = P_{\text{ref}} \quad \textbf{[4.63]}$$

The power absorbed by the load (P_a) is the difference between incident power P_{inc} and reflected power P_{ref}. If 0.3 W is reflected, then that means the absorbed power is (1.5 – 0.3), or 1.2 W.

The reflection loss is –1.05 dB, and can be checked from:

$$-1.05\ \text{dB} = 10 \log\left(\frac{P_a}{P_{\text{inc}}}\right) \qquad \textbf{[4.64]}$$

$$\frac{-1.05}{10} = \log\left(\frac{P_a}{1.5\ \text{W}}\right) \qquad \textbf{[4.65]}$$

$$10^{(-1.05/10)} = \frac{P_a}{1.5\ \text{W}} \qquad \textbf{[4.66]}$$

$$0.785 = \frac{P_a}{1.5\ \text{W}} \qquad \textbf{[4.67]}$$

$$(1.5\ \text{W}) \times (0.785) = P_a \qquad \textbf{[4.68]}$$

$$1.2\ \text{W} = P_a \qquad \textbf{[4.69]}$$

Now check what you have learned from the Smith chart. Recall that 1.5 W of 4.5-GHz microwave RF signal was input to a 50-Ω transmission line that was 28 cm long. The load connected to the transmission line has an impedance of $36 + j40$. From the Smith chart:

Admittance (load)	0.62 – j0.69
VSWR	2.6:1
VSWR (dB):	8.3 dB
Reflection coefficient (E)	0.44
Reflection coefficient (P)	0.2
Reflection coefficient angle	84 degrees
Return loss	–7 dB
Reflection loss	–1.05 dB
Transmission loss coefficient	1.5

Note that in all cases the mathematical interpretation corresponds to the graphical interpretation of the problem, within the limits of accuracy of the graphical method.

Stub matching systems

A properly designed matching system will provide a conjugate match to a complex impedance. Some sort of matching system or network is needed any time the load impedance Z_L is not equal to the characteristic impedance Z_o of the transmission line. In a transmission line system, it is possible to use a *shorted stub* connected in parallel with the line, at a critical distance back from the mismatched load, in order to effect a match. The stub is merely a section of transmission line that is shorted at the end not connected to the main transmission line. The reactance (hence also susceptance) of a shorted line can vary from –λ to +λ, depending upon length, so you can use a line of critical length L_2 to cancel the reactive component of the load impedance. Because the stub is connected in parallel with the line it is a bit easier to work with admittance parameters, rather than impedance.

Consider the example of Fig. 4-8, in which the load impedance is $Z = 100 + j60$, which is normalized to $2.0 + j1.2$. This impedance is plotted on the Smith chart in Fig. 4-9, and a VSWR circle is constructed. The admittance is found on the chart at point $Y = 0.37 - j0.22$.

In order to provide a properly designed matching stub, you need to find two lengths. L_1 is the length (relative to wavelength) from the load toward the generator (see L_1 in Fig. 4-8); L_2 is the length of the stub itself.

The first step in finding a solution to the problem is to find the points where the unit conductance line (1.0 at the chart center) intersects the VSWR circle; there are two such points shown in Fig. 4-9: $1.0 + j1.1$ and $1.0 - j1.1$. Select one of these (choose $1.0 + j1.1$) and extend a line from the center 1.0 point through the $1.0 + j1.1$ point to the outer circle (*WAVELENGTHS TOWARD GENERATOR*). Similarly, a line is drawn from the center through the admittance point 0.37 – 0.22 to the outer circle. These two lines intersect the outer circle at the points 0.165 and 0.461. The distance of the stub back toward the generator is found from:

$$L_1 = 0.165 + (0.500 - 0.461)\ \lambda \qquad \textbf{[4.70]}$$



4-8 Matching stub length and position.


NAME
TITLE
DWG. NO.
DATE
SMITH CHART FORM 82-BSPR(9-66)
KAY ELECTRIC COMPANY, PINE BROOK, N.J., © 1966 PRINTED IN U.S.A.
IMPEDANCE OR ADMITTANCE COORDINATES
0.165
Y = 1.0 + j1.1
Y = 00
0.250
G = 1.0
Y = 0.37 − j0.22
Y = 0 − j1.1
0.461
Y = 1.0 − j1.1
0.368
RESISTANCE COMPONENT, OR CONDUCTANCE COMPONENT
INDUCTIVE REACTANCE COMPONENT OR CAPACITIVE SUSCEPTANCE COMPONENT
CAPACITIVE REACTANCE COMPONENT
WAVELENGTHS TOWARD GENERATOR
WAVELENGTHS TOWARD LOAD
ANGLE OF REFLECTION COEFFICIENT IN DEGREES
ANGLE OF TRANSMISSION COEFFICIENT IN DEGREES
RADIALLY SCALED PARAMETERS
TOWARD LOAD
TOWARD GENERATOR
SWR
dBS
RET'N LOSS, dB
REFL. COEFF., P
REFL. COEFF., E OR I
ATTEN. 1dB MAJ. DIV.
S.W. LOSS COEFF.
S.W. REFL. LOSS, dB
S.W. PEAK (CONST. P)
TRANSM. COEFF., P
TRANSM. COEFF., E OR I
CENTER
ORIGIN

4-9 Solution to problem. (*Courtesy of Kay Elementrics*)

$$= 0.165 + 0.039\ \lambda \quad \textbf{[4.71]}$$

$$= 0.204\ \lambda \quad \textbf{[4.72]}$$

The next step is to find the length of the stub required. This is done by finding two points on the Smith chart. First, locate the point where admittance is infinite (far right side of the pure conductance line); second, locate the point where the admittance is $0 - j1.1$. (Note that the susceptance portion is the same as that found where the unit conductance circle crossed the VSWR circle.) Because the conductance component of this new point is 0, the point will lay on the $-j1.1$ circle at the intersection with the outer circle. Now draw lines from the center of the chart through each of these points to the outer circle. These lines intersect the outer circle at 0.368 and 0.250. The length of the stub is found from

$$L_2 = (0.368 - 0.250)\lambda \quad \textbf{[4.73]}$$

$$= 0.118\lambda \quad \textbf{[4.74]}$$

From this analysis you can see that the impedance, $Z = 100 + j60$, can be matched by placing a stub of a length 0.118λ at a distance 0.204λ back from the load.

The Smith chart in lossy circuits

Thus far, you have dealt with situations in which loss is either zero (i.e., ideal transmission lines), or so small as to be negligible. In situations where there is appreciable loss in the circuit or line, however, you see a slightly modified situation. The VSWR circle, in that case, is actually a spiral, rather than a circle.

Figure 4-10 shows a typical situation. Assume that the transmission line is 0.60λ long, and is connected to a normalized load impedance of $Z = 1.2 + j1.2$. An "ideal" VSWR circle is constructed on the impedance radius represented by $1.2 + j1.2$. A line (A) is drawn, from the point where this circle intersects the pure resistance baseline (B), perpendicularly to the *ATTEN, 1 dB/MAJ. DIV.* line on the radially scaled parameters. A distance representing the loss (3 dB) is stepped off on this scale. A second perpendicular line is drawn, from the –3 dB point, back to the pure resistance line (C). The point where line C intersects the pure resistance line becomes the radius for a new circle that contains the actual input impedance of the line. The length of the line is 0.60λ, so you must step back (0.60 – 0.50)λ or 0.1λ. This point is located on the *WAVELENGTHS TOWARD GENERATOR* outer circle. A line is drawn from this point to the 1.0 center point. The point where this new line intersects the new circle is the actual input impedance (Z_{in}).The intersection occurs at $0.76 + j0.4$, which (when denormalized) represents an input impedance of $38 + j20\ \Omega$.

Frequency on the Smith chart

A complex network may contain resistance, inductive reactance, and capacitive reactance components. Because the reactance component of such impedances is a function of frequency, the network or component tends to also be frequency-sensitive.


NAME
TITLE
DWG. NO.
DATE
SMITH CHART FORM 82-BSPR (9-66)
KAY ELECTRIC COMPANY, PINE BROOK, N.J., © 1966. PRINTED IN U.S.A.
IMPEDANCE OR ADMITTANCE COORDINATES
0.1
$Z_{\text{in}} = 0.76 + j0.4$
$Z = 1.2 + j1.2$
VSWR circle
D
B
A
C
3 dB
RESISTANCE COMPONENT (R/Zo), OR CONDUCTANCE COMPONENT (G/Yo)
WAVELENGTHS TOWARD GENERATOR
WAVELENGTHS TOWARD LOAD
ANGLE OF REFLECTION COEFFICIENT IN DEGREES
ANGLE OF TRANSMISSION COEFFICIENT IN DEGREES
RADIALLY SCALED PARAMETERS
TOWARD LOAD
TOWARD GENERATOR
CENTER
ORIGIN

4-10 Solution. (*Courtesy of Kay Elementrics*)

You can use the Smith chart to plot the performance of such a network with respect to various frequencies. Consider the load impedance connected to a 50-Ω transmission line in Fig. 4-11. In this case, the resistance is in series with a 2.2-pF capacitor, which will exhibit a different reactance at each frequency. The impedance of this network is

$$Z = R - j\left(\frac{1}{\omega C}\right) \qquad \textbf{[4.75]}$$

or

$$Z = 50 - j\left(\frac{1}{2\,\pi\,F\,C}\right) \qquad \textbf{[4.76]}$$

And, in normalized form,

$$Z' = 1.0 - \frac{j}{(2\,\pi\,F\,C) \times 50} \qquad \textbf{[4.77]}$$


Z_o
Z_S
V_{in}
$R = 50\ \Omega$
Z_L
$C = 2.2$ pF
$Z_o = 50 + j0$
$Z_S = 50 + j0$
$Z_L = 50 - jX_C$
$X_C = \frac{1}{2\pi FC} = \frac{72.3}{F_{GHz}}$
$X_C^1 = X_C/Z_o = X_C/50$

Freq. (GHz)	X_C	
1	$-j72.3$	$-j1.45$
2	$-j36.2$	$-j0.72$
3	$-j24.1$	$-j0.48$
4	$-j18$	$-j0.36$
5	$-j14.5$	$-j0.29$
6	$-j12$	$-j0.24$

4-11 Load and source impedance transmission line circuit.


NAME
TITLE
DWG. NO.
DATE
SMITH CHART FORM 82-BSPR (9-66)
KAY ELECTRIC COMPANY, PINE BROOK, N.J. © 1966. PRINTED IN U.S.A.
IMPEDANCE OR ADMITTANCE COORDINATES
$-j0.24$
$-j0.29$
$-j0.48$
$-j0.36$
$-j0.72$
$-j1.45$
RESISTANCE COMPONENT (R/Zo), OR CONDUCTANCE COMPONENT (G/Yo)
INDUCTIVE REACTANCE COMPONENT (+jX/Zo), OR CAPACITIVE SUSCEPTANCE COMPONENT (+jB/Yo)
CAPACITIVE REACTANCE COMPONENT (-jX/Zo), OR INDUCTIVE SUSCEPTANCE COMPONENT (-jB/Yo)
WAVELENGTHS TOWARD GENERATOR
WAVELENGTHS TOWARD LOAD
ANGLE OF REFLECTION COEFFICIENT IN DEGREES
ANGLE OF TRANSMISSION COEFFICIENT IN DEGREES
RADIALLY SCALED PARAMETERS
TOWARD LOAD
TOWARD GENERATOR
SWR
dBS
RET'N LOSS, dB
REFL. COEFF. P
REFL. COEFF. E OR I
ATTEN. 1 dB MAJ. DIV.
S.W. LOSS COEFF.
S.W. PEAK (CONST. P)
REFL. LOSS, dB
TRANSM. COEFF. P
TRANSM. COEFF. E OR I
CENTER
ORIGIN

4-12 Solution. (*Courtesy of Kay Elementrics*)

$$= 1.0 - \frac{j}{6.9 \times 10^{-10} F} \quad \textbf{[4.78]}$$

$$= 1.0 - \frac{j \times 7.23 \times 10^{10}}{F} \quad \textbf{[4.79]}$$

Or, converted to gigahertz,

$$Z' = 1.0 - \frac{j72.3}{F_{\text{GHz}}} \quad \textbf{[4.80]}$$

The normalized impedances for the sweep of frequencies from 1 to 6 GHz are therefore

$$Z = 1.0 - j1.45 \quad \textbf{[4.81]}$$

$$Z = 1.0 - j0.72 \quad \textbf{[4.82]}$$

$$Z = 1.0 - j0.48 \quad \textbf{[4.83]}$$

$$Z = 1.0 - j0.36 \quad \textbf{[4.84]}$$

$$Z = 1.0 - j0.29 \quad \textbf{[4.85]}$$

$$Z = 1.0 - j0.24 \quad \textbf{[4.86]}$$

These points are plotted on the Smith chart in Fig. 4-12. For complex networks, in which both inductive and capacitive reactance exist, take the difference between the two reactances (i.e., $X = X_L - X_C$).

This page intentionally left blank

5
CHAPTER

Fundamentals of radio antennas

AN UNFORTUNATE OVERSIGHT IN MANY BOOKS ON RADIO ANTENNAS IS A LACK OF coverage on the most basic fundamentals of antenna theory. Most books, including the first draft of this one, start with a discussion of dipoles, but overlook that certain physical mechanisms are at work. An antenna is basically a *transducer* that converts electrical alternating current oscillations at a radio frequency to an electromagnetic wave of the same frequency. This chapter looks at the physics of how that job is accomplished.

The material in this chapter was adapted from a U.S. Army training manual on antennas and radio propagation. Although unfortunately no longer in print, the manual contained the best coverage of basics the author of this book could find. Given that U.S. government publications are not protected by copyright, this information can be brought to you in full.

Antenna fundamentals

The electric and magnetic fields radiated from an antenna form the electromagnetic field, and this field is responsible for the transmission and reception of electromagnetic energy through free space. An antenna, however, is also part of the electrical circuit of a transmitter (or a receiver); because of its distributed constants, it acts as a circuit containing inductance, capacitance, and resistance. Therefore, it can be expected to display definite voltage and current relationships in respect to a given input. A current through it produces a magnetic field, and a charge on it produces an electrostatic field. These two fields taken together form the induction field. To gain a better understanding of antenna theory, a review of the basic electrical concepts of voltage and electric field and of current and magnetic field is necessary.

Copyright 2001 - the McGraw-Hill Companies

Voltage and electric field

When a capacitor is connected across a source of voltage, such as a battery (Fig. 5-1), it is charged some amount, depending on the voltage and the value of capacitance. Because of the emf (electromotive force) of the battery, negative charges flow to the lower plate, leaving the upper plate positively charged. Accompanying the accumulation of charge is the building up of the electric field. The flux lines are directed from the positive to the negative charges and at right angles to the plates.

If the two plates of the capacitor are spread farther apart, the electric field must curve to meet the plates at right angles (Fig. 5-2). The straight lines in A become arcs in B, and approximately semicircles in C, where the plates are in a straight line. Instead of flat metal plates, as in the capacitor, the two elements can take the form of metal rods or wires. The three-dimensional view in Fig. 5-3 depicts the electric field more accurately. In A of Fig. 5-3, the wires are approximately 30° apart, and the flux lines are projected radially from the positively charged wire to the negatively charged wire. In B of Fig. 5-3, the two wires lie in a straight line, and the flux lines form a pattern similar to the lines of longitude around the earth. To bring out the picture more clearly, only the lines in one plane are given.

Assume that the sphere marked *E* in Fig. 5-3B is a transmitter supplying RF energy. The two wires then can serve as the antenna for the transmitter. RF energy is radiated from the antenna and charges move back and forth along the wires, alternately compressing and expanding the flux lines of the electric field. The reversals in polarity of the transmitter signal also reverse the direction of the electric field.



5-1 Charges on plates of a capacitor.



5-2 Electric field between plates at various angles.



5-3 Electric field between wires at various angles.

When a charge is put on the plates of a capacitor by means of a battery, an electric field is set up between its plates. The flow of charge from source to capacitor ceases when the capacitor is fully charged, and the capacitor is said to be charged to a *voltage* equal, and of opposite polarity, to that of the source. The charged capacitor can be used as a source of emf since it stores energy in the form of an electric field. This is the same as saying that *an electric field indicates voltage*. The presence of an electric field about an antenna also indicates voltage. Since the polarity, and the amount of charge, depend on the nature of the transmitter output, the antenna voltage also depends on the energy source. For example, if a battery constitutes the source, the antenna charges to a voltage equal and opposite to that of the battery. If RF energy is supplied to a half-wave antenna, the voltage across the antenna lags the current by 90°. The half-wave antenna acts as if it was a capacitor, and it can be described as being *capacitive*.

Current and magnetic field

A *moving* charge along a conductor constitutes a current and produces a magnetic field around the conductor. Therefore, the flow of charge along an antenna also will be accompanied by a magnetic field. The intensity of this field is directly proportional to the flow of charge. When the antenna is uncharged, the current flow is maximum, since there is no opposing electric field. Because of this current flow, a charge accumulates on the antenna, and an electric field builds up in increasing opposition to the emf of the source. The current flow decreases and when the antenna is fully charged, the current no longer flows.

The magnetic field in the space around a current-carrying device has a specific configuration, with the magnetic flux lines drawn according to a definite rule (Fig. 5-4). Whereas, in the electric field, the electric lines are drawn from a positive charge to a negative charge, in the magnetic field, the flux lines are drawn according to the *left-hand rule*. The direction of current flow is upward along both halves of the antenna. The lines of magnetic flux form concentric loops that are perpendicular to the direction of current flow. The arrowheads on the loops indicate the direction of the field. If the thumb of the left hand is extended in the direction of current flow and the fingers are clenched, then the rough circles formed by the fingers indicate the direction of the magnetic field. This is the left-hand rule, or convention, which is used to determine the direction of the magnetic field.

Combined electric and magnetic fields

When RF energy from a transmitter is supplied to an antenna, the effects of charge, voltage, current, and the electric and magnetic fields are taking place simultaneously. These effects (Fig. 5-5) have definite time and space relationships to each other. If a half-wave antenna is used, the relations between charge and current flow can be predicted, because of the capacitive nature of this antenna. The voltage will lag the current by 90°, and the electric and magnetic fields will be 90° out of phase. With no electric field present (no charge), the current flow is unimpeded, and the magnetic field is maximum. As charge accumulates on the antenna, the electric field builds up in opposition to current flow and the magnetic field decreases in intensity. When the electric field reaches its maximum strength, the magnetic field has decayed to zero.

A reversal in polarity of the source reverses the direction of current flow as well as the polarity of the magnetic field, and the electric field aids the flow of current by



5-4 Magnetic field about a half-wave antenna (left-hand rule).

discharging. The magnetic field builds up to a maximum, and the electric field disappears as the charge is dissipated. The following half-cycle is a repetition of the first half-cycle, but in the reverse direction. This process continues as long as energy is supplied to the antenna. The fluctuating electric and magnetic fields combine to form the induction field, in which the electric and magnetic flux maximum intensities occur 90° apart in time, or in *time quadrature*. Physically, they occur at right angles to each other, or in *space quadrature*. To sum up, the electric and magnetic fields about the antenna are in space and time quadrature.

Standing waves

Assume that it is possible to have a wire conductor with one end extending infinitely, with an RF transmitter connected to this wire. When the transmitter is turned on, an RF current in the form of sine waves of RF energy moves down the wire. These waves of energy are called *traveling waves*. The resistance of the conductor gradually diminishes the amplitude of the waves, but they continue to travel so long as the line does not come to an end.

The antenna, however, has some finite length. Therefore, the traveling waves are halted when they reach the end of the conductor. Assume that the RF transmitter is turned on just long enough to allow one sine wave of energy to get on the line (Fig. 5-6A). This traveling wave is moving down the antenna toward the end. When the wave reaches the end of the conductor, the current path is broken abruptly. With the stoppage of current flow, the magnetic field collapses. A voltage is induced at the end of the conductor that causes current to flow *back toward the source*, as in Fig. 5-6B. The wave is reflected back to the source, and, if a continual succession of


H
E
H
E
H
F
I
I
I
+
−
Electric field intensity
E
0
Downward moving flux lines
Upward moving flux lines
Time
Magnetic field intensity
H
0
Clockwise flux lines
Counter-clockwise flux lines

5-5 Electric and magnetic fields 90° out of phase.

waves is sent down the line, waves will be reflected in the same continual pattern. The wave moving from the transmitter toward the end is called the *incident* wave, and its reflection is called the *reflected* wave.

A continuous flow of incident waves results in a continuous flow of reflected waves. Because there is only one conductor, the two waves must pass each other. Electrically, the only current that actually flows is the *resultant* of both of these waves. The waves can reinforce or cancel each other as they move.

When they reinforce, the resultant wave is maximum; when they cancel, the resultant wave is minimum. In a conductor that has a finite length, such as an antenna, the points at which the maxima and minima of the resultant wave occur (Fig. 5-6C) are *stationary*. In other words, the maximum and minimum points stand still, although both the incident and reflected waves are moving. The resultant wave stands still on the line, only its amplitude being subject to change. Because of this effect, the resultant is referred to as a *standing wave*.

The development of the standing wave on an antenna by actual addition of the traveling waves is illustrated in Fig. 5-7. At the instant pictured in A, the incident and reflected waves just coincide. The result is a standing wave having twice the amplitude of either traveling wave. In B, the waves move apart in opposite directions, and



5-6 Traveling waves on an antenna and a typical resultant wave.

the amplitude of the resultant decreases, but the points of maximum and minimum do not move.

When the traveling waves have moved to a position of 180° phase difference, the resultant is zero along the entire length of the antenna, as shown in C. At this instant, there can be no current flow in the antenna. The continuing movement of the traveling waves, shown in D, builds up a resultant in a direction opposite to that in A. The in-phase condition of the traveling waves results in a standing wave, in E, equal in amplitude, but 180° out of phase with the standing wave in A.

If the progressive pictures of the standing wave are assembled on one set of axes, the result is as in Fig. 5-8. The net effect of the incident and reflected waves is apparent. The curves are lettered with reference to Fig. 5-7. As the traveling waves move past each other, the standing wave changes only its amplitude. The fixed minimum points are called *nodes*, and the curves representing the amplitude are called *loops*.

The concept of the standing wave can be applied to the half-wave antenna with reference to either current or voltage distribution at any instant. This application is possible because there are traveling waves of both voltage and current. Because voltage and current are out of phase on the half-wave antenna, the standing waves also are found to be out of phase.


Resultant
A
Resultant
B
Resultant
C
Resultant
D
Resultant
E

5-7 Development of standing wave from traveling wave.



5-8 Standing waves.

Voltage and current distribution on half-wave antenna

When an RF transmitter is feeding a half-wave antenna, positive and negative charges move back and forth along the antenna (Figs. 5-9 and 5-10). The first picture shows the position of the charges at some arbitrary time, T_0. The RF charges being observed are at the ends of the antenna, and there is a maximum difference in potential between the ends, *A* and *B*. The remaining illustrations show the instantaneous positions of the charges at regular intervals of 22.5° throughout a complete cycle.

To the right of each instantaneous position of the charges are curves representing the current and voltage *at that particular time* for any point on the antenna. For example, at time T_0, the positive and negative charges are at points *A* and *B* on the antenna. The voltage between these points represents a maximum difference of potential. The current, being 90° out of phase in respect to the voltage, is everywhere zero. These distribution curves are *standing waves* derived in the same manner as those covered in the previous paragraph.

The next illustration shows the position of the charges at time T_1. The standing wave of current is a relative maximum at the center of the antenna. This current loop has nodes that remain at the ends of the antenna, and it is, therefore, 90° out of phase with the standing wave of voltage.

At T_2 and T_3, the charges move closer together, and the standing wave of voltage slowly decreases in amplitude. Conversely, the current loop increases in magnitude. When the charges meet after 90° of the RF cycle (T_4), the effect is that of having the positive and negative charges cancel. The voltage loop accordingly is zero everywhere on the antenna, and the current loop rises to its maximum value, unimpeded by any charge on the antenna.

At time T_5, the charges have passed each other, each charge having moved past the center point of the antenna. The polarity of the voltage loops is reversed, and they build up in the opposite direction, keeping the node always at the center point of the antenna. The reversal of polarity is shown in the charge positions at T_3, T_4, and


Distribution curves
Voltage
Current
Movement of points of charge
A
B
℄
T I M E
T_0
T_1
T_2
T_3
T_4
T_5
T_6
T_7
T_8
22.5°
45°
67.5°
90°
112.5°
135°
157.5°
180°
+
0
–

5-9 Voltage and current distribution in terms of positive and negative charges.


Movement of points of charge
TIME
Voltage
Current
A
B
A
B
A
℄
T8
T9
T10
T11
T12
T13
T14
T15
T16
180°
202.5°
225°
247.5°
270°
292.5°
315°
337.5°
360°
+
0
−

5-10 Voltage and current distribution in terms of positive and negative charges.

T_5. The separation of the charges also is accompanied by a decrease in the amplitude of the current loop.

From T_5 to T_8, the charges move out to the ends of the antenna. During this time, the voltage loops increase and the current loops decrease in amplitude. At time T_8, which occurs 180° after T_0 in the RF cycle, the charges have moved to opposite ends of the antenna. Compare the picture in T_0 to the picture in T_8. It is seen that the negative charge is now at point *A* and the positive charge at point *B*. Because the positions of the charges have been reversed from T_0 to T_8, the voltage loops in T_8 are 180° out of phase, compared with the loops in T_0.

From T_8 to T_{16} in Fig. 5-10, the movement of the charges is shown in the opposite direction, the current loop reaching a maximum at T_{12}. When the entire RF cycle is completed at time T_{16}, the charges have returned to the positions that they occupied at T_0. The distribution curves of voltage and current also are in their original conditions. The entire process then is repeated for each RF cycle.

Standing waves of voltage and current The distribution curves of the current and voltage are standing waves. This means that they are the resultants obtained by adding two traveling waves. The two traveling waves are associated with the positive and negative charges. The wave caused by the negative charge can be called the *incident wave* and the wave caused by the positive charge the *reflected wave*. This, however, is clearer when the concept of negative and positive charges is used.

The positive charge, taken at time T_0 in Fig. 5-9, produces a traveling wave of voltage, shown by the dashed line in Fig. 5-11A. The negative charge at the opposite end of the antenna produces an identical traveling wave (dash-dot curve). These two add together to produce the T_0 voltage distribution curve, which is the resultant wave of Fig. 5-9A. Both of these waveforms are identical, being the *standing wave of voltage* at time T_0. All of the following distribution curves of Fig. 5-11 are produced in the same manner. They are the standing wave resultants caused by the traveling waves accompanying the charges.

In Fig. 5-11B, each of the traveling waves has moved 45°, the positive traveling wave moving to the right and the negative traveling wave moving to the left. This time corresponds to T_2 in Fig. 5-9. The standing wave produced corresponds to the voltage distribution curve at T_2. The standing waves of current are produced in the same manner. The current curves at D, E, and F of Fig. 5-11 correspond to times T_0, T_2, and T_4 of Fig. 5-9.

Standing waves of voltage In Fig. 5-12A, voltage standing waves occurring at different times are brought together on one axis, *AB*, representing a half-wave antenna. Essentially, these are the same curves shown progressively in Figs. 5-9 and 5-10 as voltage distribution curves. They can be used to determine the voltage at any point on the antenna, at any instant of time. For example, if it is desired to know the variations of voltage occurring at point *Y* on the antenna over the RF cycle, the variations are graphed in respect to time, as shown in Fig. 5-12B. At T_0, the voltage at *Y* is maximum. From T_0 through T_3, the voltage decreases, passing through zero at T_4. The voltage builds up to a maximum in the opposite direction at T_8, returning through zero to its original position from T_8 to T_{16}.

Between T_0 and T_{16}, therefore, an entire sine-wave cycle, *Y*, is reproduced. This is also true of any other point on the antenna, with the exception of the node at *X*.



5-11 Standing waves of voltage and current.



5-12 Standing waves of voltage at a point on the antenna.

The peak amplitude of the sine wave produced at any point depends on its position on the antenna. The nearer the point is to either end, the greater its peak amplitude.

Standing waves of current The standing waves of current occurring at various times through the RF cycle are assembled on a single axis in Fig. 5-13. This axis, AB, represents the half-wave antenna. If the current variations at point Y from T_0 to T_{16} are graphed in respect to time, the result is the sine wave in Fig. 5-13B. This is true for any point along the antenna with the exception of the nodes at the ends. The current has its greatest swing at *X*, the center of the antenna. Comparison of the voltage variation curve (Fig. 5-12A) with the current variation curve (Fig. 5-13A) shows the voltage curve leading the current curve by 90° at *Y*. This relation can be expected on any half-wave device.


T_4 T_2 T_1 T_0
Time
T_4 T_6 T_7 T_8 T_9 T_{10} T_{12}
T_{16} T_{15} T_{14} T_{12}
A
Y
X
B
Current distribution
A
Current
T_0 T_1 T_2 T_3 T_4 T_5 T_6 T_7 T_8 T_9 T_{10} T_{11} T_{12} T_{13} T_{14} T_{15} T_{16}
Current at X
Current at Y
B

5-13 Standing waves of current at a point on the antenna.

Measurement of standing waves In Fig. 5-14, the standing waves of voltage *E* and current *I* are indicated along the antenna. There are current nodes at *A* and *B* and a voltage node at *X*. These standing waves are found on any half-wave antenna. A meter that indicates the effective value (0.707 of peak) of the ac signal can be used to measure the standing waves present on the half-wave antenna.

Velocity of propagation and antenna length

In free space, electromagnetic waves travel at a constant velocity of 300,000 km (or approximately 186,000 mi) per second. The RF energy on an antenna, however, moves at a velocity considerably less than that of the radiated energy in free space



5-14 Standing waves measured with a meter.

because the antenna has a *dielectric constant* greater than that of free space. Because the dielectric constant of free space (air or vacuum) is approximately 1, a dielectric constant greater than 1 retards electromagnetic-wave travel.

Because of the difference in velocity between the wave in free space and the wave on the antenna, the *physical* length of the antenna no longer corresponds to its *electrical* length. The antenna is a half-wavelength electrically, but somewhat shorter than this physically. This is shown in the formula for the velocity of electromagnetic waves,

$$V = f\lambda \qquad \textbf{[5.1]}$$

where V is the velocity, f is the frequency, and λ is the wavelength. Since the frequency of the wave remains constant, a decrease in the velocity results in a decrease in the wavelength. Therefore, the wave traveling in an antenna has a shorter wavelength than the same wave traveling in free space, and the physical length of the antenna can be shorter.

The actual difference between the physical length and the electrical length of the antenna depends on several factors. A thin wire antenna, for example, has less effect on wave velocity than an antenna with a large cross section. As the circumference of the antenna increases, the wave velocity is lowered, as compared with its free-space velocity. The effect of antenna circumference on wave velocity is illustrated in the graph of Fig. 5-15.

Other factors are involved that lower wave velocity on the antenna. Stray capacitance, for example, increases the dielectric constant and lowers wave velocity. This capacitance can be caused by the line connecting the antenna to the transmitter, the insulators used to give physical support to the antenna, or nearby objects made of metallic or dielectric materials. The change in velocity resulting from stray capacitance is called *end effect* because the ends of the antenna are made farther apart electrically than they are physically. End effect is counteracted by making the physical length about 5 percent shorter than the electrical length, as expressed in the formula

$$\begin{aligned} L &= 0.95\left(\frac{492}{f}\right) \\ &= \frac{468}{f} \end{aligned} \qquad \textbf{[5.2]}$$

where L is the physical length in feet and f is the frequency in megahertz. This formula is accurate for all practical purposes in determining the physical length of a half-wavelength antenna at the operating frequency.

The capacitive end effect also slightly changes the standing waves of voltage and current. When the standing waves are measured, it is found that the nodes have some value and do not reach zero, because some current is necessary to charge the stray capacitance. The standing waves measured in Fig. 5-16 show the results of end effect.



5-15 Effect of antenna circumference on wave velocity.



5-16 Impedance along half-wave antenna.

Resonance, resistance, and impedance

The antenna is a circuit element having distributed constants of inductance, capacitance, and resistance, which can be made to form a resonant circuit. The half-wave antenna is the shortest resonant length of antenna. However, antennas which are two or more half-wavelengths can also be resonant. Such antennas are said to operate on *harmonics*. If an antenna is four half-wavelengths at the transmitter frequency, it is being operated at the fourth harmonic of its lowest resonant frequency. In other words, this antenna is a half-wavelength at one-quarter of the frequency of operation. An antenna operating on the third harmonic is shown in Fig. 5-7.

Resistance A current flowing in the antenna must contend with three kinds of resistance. With the antenna considered as a radiator of energy, the power expended in the form of radiation can be thought of as an I^2R_t loss. R_t is called the *radiation resistance*. With the antenna considered as a conductor, a certain amount of energy is dissipated in the form of heat. In this I^2R_0 loss, R_0 is the *ohmic resistance*. There is also an I^2R loss because of the *leakage resistance* of dielectric elements, such as insulators. This R usually is included in the ohmic resistance.

The purpose of the antenna is to dissipate as much energy as possible in the form of radiation. The energy dissipated by the radiation resistance, therefore, is the useful part of the total power dissipated. Because the actual power loss depends on the ohmic resistance, this resistance should be kept as low as possible. In the half-wave antenna, the radiation resistance is large compared to the ohmic resistance, and most of the available energy is radiated. The half-wave antenna is, therefore, a very efficient radiator for most purposes.

For a half-wave antenna fed at the center point, the radiation resistance is equal to 73 Ω. The reference point is the center of the antenna at the time of peak current flow. Ohmic resistance is referred to this point. The total resistance is of importance in matching the antenna to a transmission line.

Impedance Because the half-wave antenna has different conditions of voltage and current at different points, and because impedance is equal to the voltage across a circuit divided by the current through it, the impedance will vary along the length of the antenna. If E is divided by I at each point of the voltage and current curves in Fig. 5-16, the result is the impedance curve, Z. The impedance is about 73 Ω at the center point and rises to a value of about 2500 Ω at the ends.

The impedance of the half-wave antenna usually is considered to be the impedance as *seen* by the transmitter at the input terminals. This impedance consists of both resistance and reactance. If the antenna is cut to a length of exact resonance, the reactance is zero and the impedance is purely resistive. However, if the antenna is longer or shorter than resonance, reactance is present. When the antenna is made shorter, capacitive reactance is present; when the antenna is made longer, inductive reactance is present.

The impedance at the antenna input terminals is important in terms of power efficiency. If the transmitter is feeding a nonresonant antenna, a power loss is caused by the reactive component of the antenna impedance. Conversely, if the frequency of the transmitter is changed, the electrical length of the antenna also changes. If the frequency is made somewhat higher, the electrical length is made greater, and inductive reactance is added to the impedance. If the frequency is lowered, the electrical length is shortened, and capacitive reactance is added to the impedance.

6
CHAPTER

High-frequency dipole and other doublet antennas

A MYTH AROSE IN RADIO COMMUNICATIONS CIRCLES SOME TIME AGO. PEOPLE CAME TO believe (especially in the ham and CB communities) that large antenna arrays are absolutely necessary for effective communications, especially over long distances. Overlooked, almost to the point of disdain, were effective (but simple) antennas that can be erected by inexperienced people and made to work well. The simple *dipole*, or *doublet*, is a case in point. This antenna is also sometimes called the *Hertz*, or *hertzian*, antenna because radio pioneer Heinrich Hertz reportedly used this form in his experiments.

The half-wavelength dipole is a balanced antenna consisting of two radiators (Fig. 6-1) that are each a quarter-wavelength, making a total of a half-wavelength. The antenna is usually installed horizontally with respect to the earth's surface, so it produces a horizontally polarized signal.

In its most common configuration (Fig. 6-1), the dipole is supported at each end by rope and end insulators. The rope supports are tied to trees, buildings, masts, or some combination of such structures.

The length of the antenna is a half-wavelength. Keep in mind that the physical length of the antenna, and the theoretical electrical length, are often different by about 5 percent. A free-space half-wavelength is found from

$$L = \frac{492}{F_{\text{MHz}}}\ \text{ft} \qquad \textbf{[6.1]}$$

In a perfect antenna, that is self-supported many wavelengths away from any object, Eq. 6.1 will yield the physical length. But in real antennas, the length calculated

Copyright 2001 - the McGraw-Hill Companies



6-1 Simple half-wave dipole antenna.

above is too long. The average physical length is shortened by up to about 5 percent because of the velocity factor of the wire and capacitive effects of the end insulators. A more nearly correct *approximation* (remember that word, it's important) of a half-wavelength antenna is

$$L = \frac{468}{F_{\text{MHz}}} \text{ ft} \qquad \textbf{[6.2]}$$

where

L is the length of a half-wavelength radiator, in feet
F_{MHz} is the operating frequency, in megahertz

Example Calculate the approximate physical length for a half-wavelength dipole operating on a frequency of 7.25 MHz.

Solution:

$$\begin{aligned} L &= \frac{468}{F_{\text{MHz}}} \text{ ft} \\ &= \frac{468}{7.25} \text{ ft} = 64.55 \text{ ft} \end{aligned}$$

or, restated another way:

$$L = 64 \text{ ft } 6.6 \text{ in}$$

It is unfortunate that a lot of people accept Eq. 6.2 as a universal truth, a kind of immutable law of The Universe. Perhaps abetted by books and articles on antennas that fail to reveal the full story, too many people install dipoles without regard for reality. The issue is *resonance*. An antenna is a complex *RLC* network. At some frequency, it will appear like an inductive reactance ($X = +jX_L$), and at others it will appear like a capacitive reactance ($X = -jX_C$). At a specific frequency, the reactances are equal in magnitude, but opposite in sense, so they cancel each other out: $X_L - X_C = 0$. At this frequency, the impedance is purely resistive, and the antenna is said to be resonant.

The goal in erecting a dipole is to make the antenna resonant at a frequency that is inside the band of interest, and preferably in the portion of the band most often used by the particular station. Some of the implications of this goal are covered later on, but for the present, assume that the builder will have to custom-tailor the length of the antenna. Depending on several local factors (among them, nearby objects, the shape of the antenna conductor, and the length/diameter ratio of the conductor) it might prove necessary to add, or trim, the length a small amount to reach resonance.

The dipole feedpoint

The dipole is a half-wavelength antenna fed in the center. Figure 6-2 shows the voltage (V) and current (I) distributions along the length of the half-wavelength radiator element. The feedpoint is at a voltage minimum and a current maximum, so you can assume that the feedpoint is a current antinode.

At resonance, the impedance of the feedpoint is $R_o = V/I$. There are two resistances that make up R_o. The first is the ohmic losses that generate nothing but heat when the transmitter is turned on. These ohmic losses come from the fact that conductors have electrical resistance and electrical connections are not perfect (even when properly soldered). Fortunately, in a well-made dipole these losses are almost negligible. The second contributor is the *radiation resistance* R_r of the antenna. This resistance is a hypothetical concept that accounts for the fact that RF power is radiated by the antenna. The radiation resistance is the fictional resistance that would dissipate the amount of power that is radiated away from the antenna.



6-2 Graph of current, voltage, and impedance along half-wavelength dipole.

For example, suppose we have a large-diameter conductor used as an antenna, and it has negligible ohmic losses. If 1000 W of RF power is applied to the feedpoint, and a current of 3.7 A is measured, what is the radiation resistance?

$$R_r = \frac{P}{I^2} \qquad \textbf{[6.3]}$$

$$= \frac{1000\ \text{W}}{(3.7)^2} \qquad \textbf{[6.4]}$$

$$= 73\ \Omega \qquad \textbf{[6.5]}$$

It is always important to match the feedpoint impedance of an antenna to the transmission-line impedance. Maximum power transfer always occurs (in any system) when the source and load impedances are matched. In addition, if some applied power is not absorbed by the antenna (as happens in a mismatched system), then the unabsorbed portion is reflected back down the transmission line toward the transmitter. This fact gives rise to standing waves, and the so-called standing wave ratio (SWR or VSWR) discussed in Chap. 3. This is a problem to overcome.

Matching antenna feedpoint impedance seems to be simplicity itself because the free-space feedpoint impedance of a simple dipole is about 73 Ω, seemingly a good match to 75-Ω coaxial cable. Unfortunately, the 73-Ω feedpoint impedance is almost a myth. Figure 6-3 shows a plot of approximate radiation resistance (R_r) versus height above ground (as measured in wavelengths). As before, we deal in approximations in Fig. 6-3; in this case, the ambiguity is introduced by ground losses.

Despite the fact that Fig. 6-3 is based on approximations, you can see that radiation resistance varies from less than 10 Ω, to around 100 Ω, as a function of height. At heights of many wavelengths, this oscillation of the curve settles down to the free-space impedance (72 Ω). At the higher frequencies, it might be possible to install a dipole at a height of many wavelengths. In the 2-m amateur radio band (144 to 148 MHz), one wavelength is around 6.5 ft (i.e., 2 m × 3.28 ft/m), so "many wavelengths" is relatively easy to achieve at reasonably attainable heights. In the 80-m band (3.5 to 4.0 MHz), however, one wavelength is on the order of 262 ft, so "many wavelengths" is a practical impossibility.

There are three tactics that can be followed. First, ignore the problem altogether. In many installations, the height above ground will be such that the radiation resistance will be close enough to present only a slight impedance mismatch to a standard coaxial cable. The VSWR is calculated (among other ways) as the ratio:

1. $Z_o > R_r$:

$$\text{VSWR} = \frac{Z_o}{R_r} \qquad \textbf{[6.6]}$$

2. $Z_o < R_r$:



6-3 Radiation resistance versus height above ground.

$$\text{VSWR} = \frac{R_r}{Z_o} \qquad \textbf{[6.7]}$$

where

Z_o is the coaxial-cable characteristic impedance
R_r is the radiation resistance of the antenna

Consider an antenna mounted at a height somewhat less than a quarter-wavelength, such that the radiation resistance is 60 **Ω**. Although not recommended as good engineering practice (there are sometimes practical reasons) it is nonetheless necessary to install a dipole at less than optimum height. So, if that becomes necessary, what are the implications of feeding a 60-Ω antenna with either 52- or 75-Ω standard coaxial cable? Some calculations are revealing:

For 75-Ω coaxial cable:

$$\text{VSWR} = \frac{Z_o}{R_r} \tag{6.8}$$

$$= \frac{75\ \Omega}{60\ \Omega} = 1.25{:}1 \tag{6.9}$$

For 52-Ω coaxial cable:

$$\text{VSWR} = \frac{R_r}{Z_o} \tag{6.10}$$

$$= \frac{60\ \Omega}{52\ \Omega} = 1.15{:}1 \tag{6.11}$$

In neither case is the VSWR created by the mismatch too terribly upsetting.

The second approach is to mount the antenna at a convenient height, and use an impedance matching scheme to reduce the VSWR. In Chap. 23, you will find information on various suitable (relatively) broadbanded impedance matching methods including Q-sections, coaxial impedance transformers, and broadband RF transformers. “Homebrew” and commercially available transformers are available to cover most impedance transformation tasks.

The third approach is to mount the antenna at a height (Fig. 6-3) at which the expected radiation resistance crosses a standard coaxial cable characteristic impedance. The best candidate seems to be a height of a half-wavelength because the radiation resistance is close to the free-space value of 72 Ω, and is thus a good match for 75-Ω coaxial cable (such as RG-11/U or RG-59/U).

The dipole radiation pattern

The radiation patterns of various antennas are covered in this book. Some basic theory of patterns is repeated at each section, not to fill space, but rather to drive home a point and refresh reader memories. We keep harking back to the concepts *directivity* and *gain* (which are actually different expressions of the same thing).

Antenna theory recognizes a point of reference called the *isotropic radiator*. This device is a theoretical construct consisting of a spherical point source of RF radiation in all directions (see Chap. 2). It is truly *omnidirectional* (“all directions”) because it creates an ever-expanding sphere as the RF wavefront propagates outward. Antenna gain is a measure of how the antenna focuses available power away from a spherical wavefront to a limited number of directions (two, in the case of the dipole). Thus are related the concepts *directivity* and *gain*.

Always keep in mind that *directivity and gain are specified in three dimensions*. Too many times, people simplify the topic too much by publishing only part of the radiation pattern (azimuth aspect). In other words, the reader is given a pattern viewed from above that shows the directivity in the horizontal plane. But a signal does not propagate away from an antenna in an infinitely thin sheet, as such presentations seem to imply; rather, it has an elevation extent in addition to the azimuth extent. Thus, proper evaluation of an antenna takes into consideration both horizontal and vertical plane patterns.

Figure 6-4 shows the radiation pattern of a dipole antenna in free space "in the round." In the horizontal plane (6-4A), when viewed from above, the pattern is a "figure


C
Antenna axis
B
End view of vertical plane (rotated 90° from solid figure)
A
Top view of horizontal plane (rotated 90° from solid figure)
315°
270°
0°
45°
90°

6-4 Idealized dipole radiation pattern.

8" that exhibits bidirectional radiation. Two main "lobes" contain the RF power from the transmitter, with sharp nulls of little or no power off the ends of the antenna axis. This pattern is the classical dipole pattern that is published in most antenna books.

Also shown, however, is the vertical plane pattern for a dipole antenna in free space. Note that when sliced in this aspect the radiation pattern is circular (Fig. 6-4B). When the two patterns are combined in the round, you can see the three-dimensional doughnut-shaped pattern (Fig. 6-4C) that most nearly approximates the true pattern of an unobstructed dipole in free space.

When a dipole antenna is installed close to the earth's surface, not in free space, as is the case at most stations, the pattern is distorted from that of Fig. 6-4. Two effects must be taken into consideration. First, and most important, is the fact that the signal from the antenna is reflected from the surface and bounces back into space. This signal will be phase-shifted both by the reflection and by the time required for the transit to occur. At points where the reflected wave combines in phase with the radiated signal, the signal is reinforced; in places where it combines out of phase, the signal is attenuated. Thus, the reflection of the signal from the ground alters the pattern from the antenna. The second factor is that the ground is lossy, so not all of the signal is reflected; some of it heats the ground underneath the antenna. Thus, the signal is attenuated at a greater rate than the inverse square law, so it further alters the expected pattern.

Figure 6-5 shows patterns typical of dipole antennas installed close to the earth's surface. The views in this illustration correspond to Fig. 6-4B, in that they are looking at the vertical plane from a line along the antenna axis. Therefore, the antenna is represented by *R* in each case shown. Figure 6-5A shows the case for a dipole



6-5 Vertical extent of dipole antenna at (A) ⅛ wavelength, (B) ¼ wavelength, and (C) ½ wavelength above ground.

installed at 1/8 wavelength above the surface. For this antenna, most of the RF energy is radiated almost straight up (not very useful). This type of antenna is basically limited to ground wave and very short skip (when available). The second case (Fig. 6-5B) shows the pattern when the antenna is a quarter wavelength above the earth's surface. Here the pattern is flattened, but it still shows considerable energy in the vertical direction (where it is useless). Finally, you can see the pattern obtained when the antenna is installed a half-wavelength above the surface. In this case, the pattern is best for long-distance work because energy is redirected away from straight-up into lobes at relatively shallow angles.

Tuning the dipole antenna

There are two issues to address when tuning an antenna (any antenna, not just the dipole): *resonance* and *impedance matching*. Although frequently treated in the literature as the same issue, they are not. This section deals mostly with the process of tuning the antenna to resonance. Although not all forms of antenna are resonant, the dipole *is* an example of a resonant antenna.

There is a lot of misinformation abroad concerning the tuning of antennas. Perhaps much of what is believed comes from the fact that VSWR is used as the indicator of both impedance matching and resonance. Quite a few people honestly, but erroneously, believe that the VSWR can be "tuned out" by adjusting the length of the feedline. That myth probably derives from the fact that voltage or current sensing instruments are used for VSWR measurement, and these are affected by transmission line length. But that fact is caused by a weakness in the instruments, not by radio physics.

There is only one proper way to tune a dipole antenna: *adjust the length of the antenna elements*, not the transmission line. It was in order to make these adjustments that we purposely did not initially tell you to solder the electrical connections at the center insulator.

Resonance The indicator of resonance is the minimum point in the VSWR curve. Figure 6-6 shows a graph of VSWR vs. frequency for several different cases. Curve *A* represents a disaster: a high VSWR all across the band. The actual value of VSWR can be anything from about 3.5:1 to 10:1, or thereabouts, but the cause is nonetheless the same: the antenna is either open or shorted; or it is so far off resonance as to appear to be open or shorted to the VSWR meter.

Curves *B* and *C* represent antennas that are resonant within the band of interest. Curve *B* represents a broadbanded antenna that is relatively flat all across the band and does not exhibit excessive VSWR until the frequency is outside of the band. Curve *C* is also resonant within the band, but this antenna has a much higher *Q* than curve *B.* In the naive sense, the broadbanded antenna is best, but that statement is true only if the broadness is not purchased at the expense of efficiency. Losses tend to broaden the antenna, but also reduce its effectiveness. So, if broad bandedness is purchased at the risk of increased loss, then it is less than desirable.

Curves *D* and *E* are resonant outside the band of interest. The curve marked *D* is resonant at a frequency on the low side of the band, so the dipole is too long. In this case, you need to shorten the antenna a bit to raise the resonant point inside



6-6 VSWR versus frequency for several cases.

the band. Curve *E* represents an antenna that is resonant outside the upper limit of the band, so this antenna is too short, and must be lengthened. Because this situation is possible, the antenna elements are typically made longer than needed when they are first cut.

How much to cut? That depends on two factors: how far from the desired frequency the resonant point is found, and which band is being used. The latter requirement comes from the fact that the "frequency per unit length" varies from one band to another. Look at an example of how to calculate this figure. The procedure is simple:

1. Calculate the length required for the upper end of the band.
2. Calculate the length required for the bottom end of the band.
3. Calculate the difference in lengths for the upper and lower ends of the band.
4. Calculate the width of the band in kilohertz by taking the difference between the upper frequency limit and the lower frequency limit.
5. Divide the length difference by the frequency difference; the result is in kilohertz per unit length.

Example 6-1 Calculate the frequency change per unit of length for 80 and for 15 m.

Solution For 80 m (3.5 to 4.0 MHz):

1. $L_{\text{ft}} = \dfrac{468}{4\text{ MHz}} = 117\text{ ft}$
2. $L_{\text{ft}} = \dfrac{468}{3.5\text{ MHz}} = 133.7\text{ ft}$
3. Difference in length: 133.7 ft – 117 ft = 16.7 ft
4. Frequency difference: 4000 kHz – 3500 kHz = 500 kHz
5. Calculate $\dfrac{\text{frequency}}{\text{unit length}} : \dfrac{500\text{ kHz}}{16.7\text{ ft}} = 30\text{ kHz/ft}$

For 15 m (21.0 – 21.45 MHz):

1. $L_{\text{ft}} = \dfrac{468}{21.45} = 21.82\text{ ft}$
2. $L_{\text{ft}} = \dfrac{468}{21} = 22.29\text{ ft}$
3. Difference in length: 22.29 ft – 21.82 ft = 0.47 ft
4. Convert to inches: 0.47 ft × 12 in/ft = 5.64 in
5. Frequency difference: 21,450 kHz – 21,000 kHz = 450 kHz
6. Calculate $\dfrac{\text{frequency}}{\text{unit length}} : \dfrac{450\text{ kHz}}{5.64\text{ in}} = 80\text{ kHz/in}$

At 80 m, the frequency change per foot is small, but at 15 m small changes can result in very large frequency shifts. You can calculate approximately how much to add (or subtract) from an antenna under construction from this kind of calculation. If, for example, you design an antenna for the so-called “net frequency” on 15 m (21,390 kHz), and find the actual resonant point is 21,150 kHz, the frequency shift required is 21,390 – 21,150, or 240 kHz. To determine how much to add or subtract (as a first guess):

1. The factor for 15 m is 80 kHz/in, which is the same as saying 1 in/80 kHz.
2. The required frequency shift is 240 kHz.
3. Therefore:

$$\text{Length change} = 240\text{ kHz} \times \frac{1\text{ in}}{80\text{ kHz}} \tag{6.12}$$

$$= 3\text{ in} \tag{6.13}$$

Each side of the antenna must be changed by half of the length calculated above, or 1.5 in. Because the first resonant frequency is less than the desired frequency, the length should be shortened 1.5 in. Once the length is correct, as proven by the VSWR curve, the connections at the center insulator are soldered and made permanent, and the antenna rehoisted to the operating level.

Impedance matching The difference between resonance and impedance matching is seen in the value of the VSWR minimum. While the minimum indicates the resonant point, its value is a measure of the relationship between the feedpoint impedance of the antenna and the characteristic impedance of the transmission line. Earlier in this chapter you learned that

1. $Z_o > R_r$:

$$\text{VSWR} = \frac{Z_o}{R_r} \qquad \textbf{[6.14]}$$

2. $Z_o < R_r$:

$$\text{VSWR} = \frac{R_r}{Z_o} \qquad \textbf{[6.15]}$$

where

Z_o is the coaxial-cable characteristic impedance
R_r is the radiation resistance of the antenna

Although knowledge of the VSWR will not show which situation is true, you can know that there is a high probability that *one* of them is true, and you can experiment to find which is the case. Of course, if the VSWR is less than about 1.5:1 or 2:1, then forget about it—the improvement is not generally worth the expense and cost. When coupled to a transmitter that is equipped with the tunable output network (most tube-type transmitters or final amplifiers), then it can accommodate a relatively wide range of reflected antenna impedances. But modern solid-state final amplifiers tend to be a little more picky about the load impedance. For these transmitters, a coax-to-coax *antenna tuning unit* (ATU) is needed.

Other dipoles

Thus far, the dipoles covered in this chapter have been the classic form, in which a half-wavelength single-conductor radiator element is connected to a coaxial transmission line. This antenna is typically installed horizontally at a half-wavelength above the earth's surface (or wherever convenient if that is impossible). This section looks at other forms of the dipole. Some of these dipoles are in every way the equal of the horizontal dipole, and others are basically compensation antennas in that they are used when a proper dipole is not practical.

Inverted-vee dipole

The *inverted-vee dipole* is a half-wavelength antenna fed in the center like a dipole. By the rigorous definition, the inverted-vee is merely a variation on the dipole theme. But in this form of antenna (Fig. 6-7), the center is elevated as high as possible from the earth's surface, but the ends droop to very close to the surface. Angle a can be almost anything convenient, provided that $a > 90$ degrees; typically, most inverted-vee antennas use an angle of about 120 degrees. Although essentially a compensation antenna for use when the dipole is not practical, many operators believe that it is essentially a better performer on 40 and 80 m in cases where the dipole cannot be mounted at a half-wavelength (64 ft or so).

By sloping the antenna elements down from the horizontal to an angle (as shown in Fig. 6-7), the resonant frequency is effectively lowered. Thus, the antenna will


L
L
a
Coaxial cable to transmitter
$L \approx \frac{220}{F_{\text{MHz}}}$ Feet
Insulated support
R
S
I
I
R
S

I = Insulator
S = Support stake
R = Rope

6-7 Inverted-vee dipole.

need to be shorter for any given frequency than a dipole. There is no absolutely rigorous equation for calculation of the overall length of the antenna elements. Although the concept of "absolute" length does not hold for regular dipoles, it is even less viable for the inverted-vee. There is, however, a rule of thumb that can be followed for a starting point: Make the antenna about 6 percent shorter than a dipole for the same frequency. The initial cut of the antenna element lengths (each quarter wavelength) is

$$L = \frac{220}{F_{\text{MHz}}} \text{ ft} \qquad \textbf{[6.16]}$$

After this length is determined, the actual length is found from the same cut-and-try method used to tune the dipole in the previous section.

Bending the elements downward also changes the feedpoint impedance of the antenna and narrows its bandwidth. Thus, some adjustment in these departments is in order. You might want to use an impedance matching scheme at the feedpoint, or an antenna tuner at the transmitter.

Sloping dipole ("sloper" or "slipole")

The *sloping dipole* (Fig. 6-8) is popular with those operators who need a low angle of radiation, and are not overburdened with a large amount of land to install the antenna. This antenna is also called the *sloper* and the *slipole* in various texts. The author prefers the term "slipole," in order to distinguish this antenna from a sloping vertical of the same name. Whatever it is called, however, it is a half-wavelength dipole that is built with one end at the top of a support, and the other end close to the



6-8 "Slipole" or "sloper."

ground, and being fed in the center by coaxial cable. Some of the same comments as obtained for the inverted-vee antenna also apply to the sloping dipole, so please see that section also.

Some operators like to arrange four sloping dipoles from the same mast such that they point in different directions around the compass (Fig. 6-9). A single four-position coaxial cable switch will allow switching a directional beam around the compass to favor various places in the world.

Broadbanded dipoles

One of the rarely discussed aspects of antenna construction is that the length/diameter ratio of the conductor used for the antenna element is a factor in determining the bandwidth of the antenna. In general, the rule of thumb states that large cross-sectional area makes the antenna more broadbanded. In some cases, this rule suggests the use of aluminum tubing instead of copper wire for the antenna radiator. On the higher-frequency bands that is a viable solution. Aluminum tubing can be purchased for relatively small amounts of money, and is both lightweight and easily worked with ordinary tools. But, as the frequency decreases, the weight becomes greater because the tubing is both longer and (for structural strength) must be of greater diameter. On 80 m, aluminum tubing is impractical, and at 40 m it is nearly so. Yet, 80 m is a significant problem, especially for older transmitters, because the band is 500 kHz wide, and the transmitters often lack the tuning range for the entire band.

Some other solution is needed. Here are three basic solutions to the problem of wide-bandwidth dipole antennas: *folded dipole*, *bowtie dipole*, and *cage dipole*.



6-9 Directional antenna made of four slopers (top view).

Figure 6-10A shows the *folded dipole* antenna. This antenna basically consists of two half-wavelength conductors shorted together at the ends and fed in the middle of one of them. The folded dipole is most often built from 300-Ω television antenna twin-lead transmission line. Because the feedpoint impedance is nearly 300 Ω, the same type of twin lead can also be used for the transmission line. The folded dipole will exhibit excellent wide-bandwidth properties, especially on the lower bands.

A disadvantage of this form of antenna is that the transmitter has to match the 300-Ω balanced transmission line. Unfortunately, most modern radio transmitters are designed to feed coaxial-cable transmission line. Although an antenna tuner can be placed at the transmitter end of the feedline, it is also possible to use a 4:1 balun transformer at the feedpoint (Fig. 6-10B). This arrangement makes the folded dipole a reasonable match to 52- or 75-Ω coaxial-cable transmission line.

Another method for broadbanding the dipole is to use two identical dipoles fed from the same transmission line, and arranged to form a “bowtie” as shown in Fig. 6-11. The use of two identical dipole elements on each side of the transmission line has the effect of increasing the conductor cross sectional area so that the antenna has a slightly improved length/diameter ratio.

The *bowtie dipole* was popular in the 1930s and 1940s, and became the basis for the earliest television receiver antennas (TV signals are 3 to 5 MHz wide, so they require a broadbanded antenna). It was also popular during the 1950s as the so-called Wonder Bar antenna for 10 m. It still finds use, but it has faded somewhat in popularity.

The *cage diople* (Fig. 6-12) is similar in concept, if not construction, to the bowtie. Again, the idea is to connect several parallel dipoles together from the same transmission line in an effort to increase the apparent cross-sectional area. In the case of the cage dipole, however, spreader disk insulators are constructed to keep the wires separated. The insulators can be built from plexiglass, lucite, or ceramic.


L
300-Ω
parallel
line or
twinlead
To
XMTR

6-10A Folded dipole fed with 300-Ω line.


4:1
BALUN
75-Ω coax
to XMTR

6-10B Folded dipole fed with coaxial cable.


I
R
I
I
R
75-Ω coax
to XMTR
I = Insulator
R = Rope

6-11 Bowtie dipole.



6-12 Cage dipole.

They can also be constructed of materials such as wood, if the wood is properly treated with varnish, polyurethene, or some other material that prevents it from becoming waterlogged. The spreader disks are held in place with wire jumpers (see inset to Fig. 6-12) that are soldered to the main element wires.

A tactic used by some builders of both bowtie and cage dipoles is to make the elements *slightly* different lengths. This "stagger tuning" method forces one dipole to favor the upper end of the band, and the other to favor the lower end of the band. The overall result is a slightly flatter frequency response characteristic across the entire band. On the cage dipole, with four half-wavelength elements, it should be possible to overlap even narrower sections of the band in order to create an even flatter characteristic.

Shortened coil-loaded dipoles

The half-wavelength dipole is too long for some applications where real estate is at a premium. The solution for many operators is to use a coil-loaded shortened dipole such as shown in Fig. 6-13. A shortened dipole (i.e., one which is less than a half-wavelength) is capacitive reactance. There is no reason why the loading coil cannot be any point along the radiator, but in Figs. 6-13A and 6-13B they are placed at 0 percent and 50 percent of the element length, respectively. The reason for this procedure is that it makes the calculation of coil inductances easier, and it also represents the most common practice.

Figure 6-13C shows a table of inductive reactances as a function of the percentage of a half-wavelength, represented by the shortened radiator. It is likely that the percentage figure will be imposed on you by the situation, but the general rule is to pick the largest figure consistent with the available space. For example, sup-



C

$L_1 = L_2 = L$

$C = 2A$

$A = \frac{1}{2}C$

$$C = \frac{468M}{F_{\text{MHz}}}$$

$O \leq M \leq 1$

Percent of half-wavelength	Coils at feedpoint (Ω)	Coils at middle of radiators (Ω)
20	1800	2800
30	950	1800
40	700	1800
50	500	1300
60	360	950
70	260	700
80	160	500
90	75	160
95	38	80
98	15	30



6-13 Shortened or loaded dipole. (A) inductors at feedpoint; (B) inductors midway along elements; (C) chart of reactances for coils; (D) commercially available coils; (E) homemade coil based on commercial coil stock.

pose you have about 40 ft available for a 40-m antenna that normally needs about 65 ft for a half-wavelength. Because 39 ft is 60 percent of 65 ft, you could use this value as the design point for this antenna. Looking on the chart, a 60 percent antenna with the loading coils at the midpoint of each radiator element wants to see an inductive reactance of 700 Ω. You can rearrange the standard inductive reactance equation ($X_L = 6.28\,FL$) to the form

$$L_{\mu H} = \frac{X_L \times 10^6}{6.28F} \qquad \textbf{[6.17]}$$

where

$L_{\mu H}$ is the required inductance, in microhenrys
F is the frequency, in hertz (Hz)
X_L is the inductive reactance calculated from the table in Fig. 6-13C.

Example 6-2 Calculate the inductance required for a 60 percent antenna operating on 7.25 MHz. The table requires a reactance of 700 Ω for a loaded dipole with the coils in the center of each element (Fig. 6-15B).

Solution:

$$L_{\mu H} = \frac{X_L \times 10^6}{6.28F} \qquad \textbf{[6.18]}$$

$$= \frac{(700)\ (10^6)}{(6.28)\ (7{,}250{,}000)} \qquad \textbf{[6.19]}$$

$$= \frac{7 \times 10^8}{4.6 \times 10^7} \qquad \textbf{[6.20]}$$

$$= 15.4\ \mu H \qquad \textbf{[6.21]}$$

The inductance calculated above is approximate, and it might have to be altered by cut-and-try methods.

The loaded dipole antenna is a very sharply tuned antenna. Because of this fact, you must either confine operation to one segment of the band, or provide an antenna tuner to compensate for the sharpness of the bandwidth characteristic. However, efficiency drops, markedly, far from resonance even with a transmission line tuner. The function of the tuner is to overcome the bad effects on the transmitter, but it does not alter the basic problem. Only a variable inductor in the antenna will do that trick (at least one commercial loaded dipole once used a motor-driven inductor at the center feedpoint).

Figures 6-13D and E show two methods for making a coil-loaded dipole antenna. Figure 6-13D shows a pair of commercially available loading coils especially designed for this purpose. The ones shown here are for 40 m, but other models are also available. The inductor shown in Fig. 6-13E is a section of commercial coil stock connected to a standard end or center insulator. No structural stress is assumed by the coil—all forces are applied to the insulator, which is designed to take it.

Inductance values for other length antennas can be approximated from the graph in Fig. 6-14. This graph contains three curves for coil-loaded, shortened dipoles that are 10, 50, and 90 percent of the normal half-wavelength size. Find the proposed location of the coil, as a percentage of the wire element length, along the horizontal axis. Where the vertical line from that point intersects with one of the three curves, that intersection yields the inductive reactance required (see along vertical axis). Inductances for other overall lengths can be "rough-guessed" by interpolating between the three available curves, and then validated by cut and try.

Tunable dipoles

Dipoles are resonant antennas, so they naturally tend to prefer one frequency over the others. The VSWR will be quite low at the resonant point (assuming no feedline mismatch problems), and will rise at frequencies above and below resonance. If the antenna is a *high-Q* model, then the effect is quite profound, and it might render the antenna nearly useless at frequencies on the other end of the same band (especially where modern transmitters equipped with VSWR shutdown circuitry are used). Figure 6-15 shows a method for overcoming this problem. Here is how it works.

An antenna that is too long for the desired resonant frequency will act inductively (i.e., it will show a feedpoint impedance of the form $Z = R + jX_L$). To counteract the inductive reactance component $+jX_L$ it is necessary to add a bit of capacitive reactance $-jX_c$. This approach is taken in tuning certain antenna forms and it can be used with dipoles to make the antenna tunable over a range of about 15 percent of the frequency.

The tunable dipole of Fig. 5-15 is longer than other dipoles and it has an overall length of

$$L' = \frac{505}{F_{\mathrm{MHz}}} \qquad \textbf{[6.22]}$$

Note that the velocity constant is 505, rather than the 468 that is used with ordinary dipoles.

The required capacitive reactance, which is used to electrically shorten the antenna, is provided by C_1. In one effective design that I've tested, the capacitor was a 500-pF transmitting variable type. When the Heath Company was making kits, they offered an antenna tuner based on this idea. It was a motor-driven 500-pF variable capacitor inside of a weather-resistant metal-shielded case. The Heath tuner can be used on inverted vees and dipoles (if a center support is provided). A low-voltage (which is necessary for safety reasons) dc motor drives the shaft of the capacitor to tune the antenna to resonance.

Stacked dipoles

Figure 6-16 shows a *double dipole* (i.e., two half-wavelength dipole antennas spaced a half-wavelength apart). The transmission lines are connected in parallel at the receiver. This antenna provides about 3-dB gain over a single dipole, and it adds a bit of fade protection because two side-by-side antennas provide a bit of space diversity (see the end of Chap. 2 for information on diversity reception).



6-14 Inductive reactance versus coil location for shortened inductance-loaded dipole.


L'
R
I
I
R
R = rope
I = insulator
DC motor
Coax to
RIG or RCVR
L' = 505/F$_{MHZ}$

6-15 Electrically reducing the length of a dipole antenna by placing a capacitor at the feedpoint.


R
I
1:1
BALUN
I
R
I
1:1
BALUN
I
R
75 Ω coax
Box
(see text)
XMTR
R = Rope
I = Insulator

6-16 Phased dipoles provide a 3-dB gain over single dipole.

The two dipoles are supported by a common structure consisting of ropes (R) and end insulators (I) to support masts on the ends. In the center, a half-wavelength space is taken up by a rope so that the structure is maintained. The space is determined by

$$\text{Space}_{\text{feet}} = \frac{492}{F_{\text{MHz}}} \qquad \textbf{[6.23]}$$

and, for the dipoles,

$$\text{Length}_{\text{feet}} = \frac{468}{F_{\text{MHz}}} \qquad \textbf{[6.24]}$$

The stacked dipole gets a bit lengthy on low-frequency bands, but is easily achievable by most people on the upper HF bands.

The feedlines for the two dipoles can be connected directly in parallel and fed from the transmitter, provided that the antenna tuning unit will support one-half the normal expected impedance. Alternatively, a box can be provided that includes a matching transformer for 1:2 ratio. These can be built like a balun transformer on a toroidal core. A trifilar winding is used. Alternatively, a phasing box can be built that will allow altering the directionality of the antenna by 90°. This is done by using the switching circuit to reverse the sense of L_3.

Off-center-fed full-wave doublet (OCFD) antennas

An antenna that superficially resembles the Windom is the off-center-fed doublet (OCFD) antenna of Fig. 6-17. It is a single-band antenna, although at harmonics it will begin to act as a resonant, standing wave, longwire antenna. The overall length is one wavelength long:

$$L_{\text{feet}} = \frac{936}{F_{\text{MHz}}} \qquad \textbf{[6.25]}$$

This antenna works best at heights of at least λ/2 above ground, so practical considerations limit it to frequencies above about 10 MHz (i.e., 30-m band). The feedpoint of the antenna is placed at a distance of λ/4 from one end, and is a good match for 75-Ω coaxial cable. A 1:1 balun transformer at the feedpoint is highly recommended. The pattern of a 1λ antenna is a four-lobe "cloverleaf," with the major lobes being about 53° from the wire. The gain is about 1 dB.



6-17 Off-center-fed 1-wire antenna.

Off-center-fed nonresonant sloper (OCFS)

Perhaps more viable for many people is the *nonresonant off-center-fed sloper* (OCFS) antenna of Fig. 6-18. This antenna consists of a wire radiator that must be longer than 3λ/2 at the lowest frequency of operation. The feedpoint is elevated at least λ/4 above ground at the lowest operating frequency. The antenna is fed with 75-Ω coaxial cable. The shield of the coax is connected to a λ/4 resonant radial (counterpoise ground). There should be at least one radial (more is better) per band of operation.

The far end of the radiator element is sloped to ground, where it is terminated in a 270-Ω noninductive resistor. The resistor should be able to dissipate up to one-third of the power level applied by the transmitter.

Double extended Zepp antenna

The *double extended Zepp* antenna (Fig. 6-19) provides a gain of about 2 dB over a dipole at right angles to the antenna wire plane. It consists of two sections of wire, each one of a length

$$L_{1\text{feet}} = \frac{600}{F_{\text{MHz}}} \qquad \textbf{[6.26]}$$


Rope
EI
Wire antenna element (≥ 3/4 λ at lowest frequency)
$\frac{\lambda}{4}$ radial
Direction of reception
Coax to receiver
Mast
R_1
270 Ω
2-watt
Ground
Ground connection

6-18 Terminated sloper antenna.



6-19 Double extended Zepp antenna.

Typical lengths are 20.7 ft on the 10-m band, 28 ft on the 15-m band, 42 ft on the 20-m band, and 84 ft on the 40-m band.

The double extended Zepp antenna can be fed directly with 450-Ω twin lead, especially if a balanced antenna tuner is available at the receiver. Alternatively, it can be fed from a quarter-wavelength matching section (made of 450-Ω twin lead, or equivalent open air parallel line), as shown, and a balun if coax is preferred. The length of the matching section should be

$$L_{2\text{feet}} = \frac{103}{F_{\text{MHz}}} \qquad \textbf{[6.27]}$$

The double extended Zepp will work on several different bands. For example, a 20-m-band double extended Zepp will work as a Zepp on the design band, a dipole on frequencies below the design band, and as a four-lobed cloverleaf antenna on frequencies above the design band.

Collinear "Franklin" array antenna

Perhaps the cheapest approach to very serious antenna gain is the collinear Franklin array shown in Fig. 6-20. This antenna pushes the dipole and double extended Zepp concepts even farther. It consists of a half-wavelength dipole that is center-fed with a 4:1 balun and 75-Ω coaxial cable. At each end of the dipole, there is a quarter-wavelength *phase reversal stub* that end-feeds another half-wavelength element. Each element is a half-wavelength (λ/2) long, and its length can be calculated from

$$\frac{\lambda}{2} = \frac{492}{F_{\text{MHz}}} \qquad \textbf{[6.28]}$$

The phase reversal stubs are a quarter-wavelength long, or one half the length calculated by Eq. 6.28.



6-20 Wire collinear antenna.

The version of the "Collinear" shown in Fig. 6-20 has a gain of about 3 dB. There is no theoretical reason why you can't extend the design indefinitely, but there is a practical limit set by how much wire can be held by your supports, and how much real estate you own. A 4.5-dB version can be built by adding another half-wavelength section at each end, with an intervening quarter-wavelength phase reversal stub in between each new section, and the preceding section. Once you get longer than five half-wavelengths, which provides the 4.5-dB gain, the physical size becomes a bit of a bother for most folks.

The TCFTFD dipole

The *tilted, center-fed, terminated, folded dipole* (TCFTFD, also called the T^2FD or TTFD) is an answer to both the noise pickup and length problems that sometimes affect other antennas. For example, a random-length wire, even with antenna tuner, will pick up considerable amounts of noise. A dipole for 40 m is 66 ft long.

This antenna was first described publicly in 1949 by Navy Captain C. L. Countryman, although the U.S. Navy tested it for a long period in California during World War II. The TCFTFD can offer claimed gains of 4 to 6 dB over a dipole, depending on the frequency and design, although 1 to 3 dB is probably closer to the mark in practice, and less than 1 dB will be obtained at some frequencies within its range (especially where the resistor has to absorb a substantial portion of the RF power). The main attraction of the TCFTFD is not its gain, but rather its *broad bandedness*.

In addition, the TCFTFD can also be used at higher frequencies than its design frequency. Some sources claim that the TCFTFD can be used over a 5 or 6:1 frequency range, although my own observations are that 4:1 is more likely. Nonetheless, a 40-m antenna will work over a range of 7000 to 25,000 kHz, with at least some decent performance up into the 11-m Citizen's Band (27,000 kHz).

The basic TCFTFD (Fig. 6-21) resembles a folded dipole in that it has two parallel conductors of length *L*, spaced a distance *W* apart, and shorted together at the



6-21 TTFD antenna.

ends. The feedpoint is the middle of one conductor, where a 4:1 balun coil and 75-Ω coaxial-cable transmission line to the transceiver are used. A noninductive, 390-Ω resistor is placed in the center of the other conductor. This resistor can be a carbon-composition (or metal-film) resistor, but it must not be a wirewound resistor or any other form that has appreciable inductance. The resistor must be able to dissipate about one-third of the applied RF power. The TCFTFD can be built from ordinary no.14 stranded antenna wire.

For a TCFTFD antenna covering 40 through 11 m, the spread between the conductors should be 19½ in, while the length *L* is 27 ft. Note that length *L* includes one-half of the 19-in spread because it is measured from the center of the antenna element to the center of the end supports.

The TCFTFD is a sloping antenna, with the lower support being about 6 ft off the ground. The height of the upper support depends on the overall length of the antenna. For a 40-m design, the height is on the order of 50 ft.

The parallel wires are kept apart by spreaders. At least one commercial TCFTFD antenna uses PVC spreaders, while others use ceramic. You can use wooden dowels of between 1-in and ⅝-in diameter; of course, a coating of varnish (or urethane spray) is recommended for weather protection. Drill two holes, of a size sufficient to pass the wire, that are the dimension *W* apart (19 in for 40 m). Once the spreaders are in place, take about a foot of spare antenna wire and make jumpers to hold the dowels in place. The jumper is wrapped around the antenna wire on either side of the dowel, and then soldered.

The two end supports can be made of 1 × 2 in wood treated with varnish or urethane spray. The wire is passed through screw eyes fastened to the supports. A support rope is passed through two holes on either end of the 1 × 2 and then tied off at an end insulator.

The TCFTFD antenna is noticeably quieter than the random-length wire antenna, and somewhat quieter than the half-wavelength dipole. When the tilt angle is around 30°, the pattern is close to omnidirectional. Although a little harder to build than dipoles, it offers some advantages that ought not to be overlooked. These dimensions will suffice when the "bottom end" frequency is the 40-m band, and it will work well on higher bands.

Vee-sloper antenna

The *vee-sloper antenna* is shown in Fig. 6-22. It is related to the vee beam (covered in Chap. 9), but it is built like a sloper (i.e., with the feed end of the antenna high above ground). The supporting mast height should be about half (to three-fourths) of the length of either antenna leg. The legs are sloped downward to terminating



6-22 Vee-sloper antenna.

resistors at ground level. Each wire should be longer than 1λ at the lowest operating frequency. The terminating resistors should be on the order of 270 Ω (about one-half of the characteristic impedance of the antenna), with a power rating capable of dissipating one-third of the transmitter power. Like other terminating resistors, these should be noninductive (carbon composition or metal film).

The advantage of this form of antenna over the vee beam is that it is vertically polarized, and the resistors are close to the earth, so they are easily grounded.

Rhombic inverted-vee antenna

A variation on the theme is the vertically polarized rhombic of Fig. 6-23. Although sometimes called an *inverted vee*—not to be confused with the dipole variant of the same name—this antenna is half a rhombic, with the missing half being "mirrored" in the ground (similar to a vertical). The angle at the top of the mast (Φ) is typically ≥ 90°, and 120 to 145° is more common. Each leg (A) should be ≥λ, with the longer lengths being somewhat higher in gain, but harder to install for low frequencies. A requirement for this type of antenna is a very good ground connection. This is often accomplished by routing an underground wire between the terminating resistor ground and the feedpoint ground.

Multiband fan dipole

The basic half-wavelength dipole antenna is a very good performer, especially when cost is a factor. The dipole yields relatively good performance for practically no in-



6-23 Inverted-vee antenna.

vestment. A standard half-wavelength dipole offers a bidirectional figure-8 pattern on its basic band (i.e., where the length is a half-wavelength), and a four-lobe cloverleaf pattern at frequencies for which the physical length is 3λ/2. Thus, a 40-m half-wavelength dipole produces a bidirectional pattern on 40 m, and a four-lobe cloverleaf pattern on 15 m.

The dipole is not easily multibanded without resorting to traps (covered in Chap. 8). One can, however, tie several dipoles to the same center insulator or balun transformer. Figure 6-24 shows three dipoles cut for different bands, operating from a common feedline and balun transformer: A1–A2, B1–B2, and C1–C2. Each of these antennas is a half-wavelength (i.e., $L_{\text{feet}} = 468/F_{\text{MHz}}$).

There are two points to keep in mind when building this antenna. First, try to keep the ends spread a bit apart, and second, make sure that none of the antennas is cut as a half-wavelength for a band for which another is 3λ/2. For example, if you make A1–A2 cut for 40 m, then don't cut any of the other three for 15 m. If you do, the feedpoint impedance and the radiation pattern will be affected.

The counterpoise longwire

The *longwire antenna* is an end-fed wire more than 2λ long. It provides considerable gain over a dipole, especially when a very long length can be accommodated. Although 75- to 80-m, or even 40-m longwires are a bit difficult to erect at most locations, they are well within reason at the upper end of the HF spectrum. Low-VHF



6-24 Multiband dipole antenna.

band operation is also practical. Indeed, I know one fellow who lived in far southwest Virginia as a teenager, and he was able to get his family television reception for very low cost by using a TV longwire (channel 6) on top of his mountain.

There are some problems with longwires that are not often mentioned. Two problems seem to insinuate themselves into the process. First, the Zepp feed is a bit cumbersome (not everyone is enamored of parallel transmission line). Second, how do you go about actually grounding that termination resistor? If it is above ground, then the wire to ground is long, and definitely not at ground potential for RF. If you want to avoid both the straight Zepp feed system employed by most such antennas, as well as the resistor-grounding problem, then you might want to consider the *counterpoise longwire antennas* shown in Fig. 6-25.


$\frac{\lambda}{4}$
>2λ
$\frac{\lambda}{4}$
Rope
EI
R1
EI
Rope
4:1 balun transformer
Radiator
Coax to transmitter
EI = end insulator
R = rope
R_1 = termination resistor (noninductive)

6-25A Longwire with λ/4 radials used as counterpoise ground at feedpoint and terminating resistor.


Wire ≥ 2λ long
$\frac{\lambda}{4}$ Radial
T1
4:1 balun
transformer
Rope
EI
EI
Rope
EI = end insulator
R = rope support
75-Ω
coaxial cable
to receiver

6-25B Balun transformer feed for longwire antenna.

A counterpoise ground is a structure that acts like a ground, but is actually electrically floating above real ground (and it is not connected to ground). A groundplane of radials is sometimes used as a counterpoise ground for vertical antennas that are mounted above actual earth ground. In fact, these antennas are often called *ground plane verticals*. In those antennas, the array of four (or more) radials from the shield of the coaxial cable are used as an artificial, or counterpoise, ground system.

In the counterpoise longwire of Fig. 6-25A, there are two counterpoise grounds (although, for one reason or another, you might elect to use either, but not both). One counterpoise is at the feedpoint, where it connects to the "cold" side of the transmission line. The parallel line is then routed to an antenna tuning unit (ATU), and from there to the transmitter. The other counterpoise is from the cold end of the termination resistor to the support insulator. This second counterpoise makes it possible to eliminate the earth ground connection, and all the problems that it might entail, especially in the higher end of the HF spectrum, where the wire to ground is of substantial length compared with 1λ of the operating frequency.

A slightly different scheme used to adapt the antenna to coaxial cable is shown in Fig. 6-25B. In this case, the longwire is a resonant type (nonterminated). Normally, one would expect to find this antenna fed with 450-Ω parallel transmission line. But with a λ/4 radial acting as a counterpoise, a 4:1 balun transformer can be used to effect a reasonable match to 75-Ω coaxial cable. The radial is connected to the side of the balun that is also connected to the coaxial cable shield, and the other side of the balun is connected to the radiator element.

7
CHAPTER

Vertically polarized HF antennas

IN PREVIOUS CHAPTERS, YOU HAVE FOUND THAT THE POLARITY OF AN ANTENNA IS THE direction of the electrical (E) field. Because the transmitted signal is an orthogonal electromagnetic wave, the magnetic field radiated from the antenna is at right angles to the electric field. The direction of the electric field, which sets the polarity of the antenna, is a function of the geometry of the radiator element. If the element is vertical, then the antenna polarity is also vertical. The signal propagates out from the radiator in all directions of azimuth, making this antenna an "omnidirectional" radiator.

Figure 7-1A shows the basic geometry of the vertical antenna: an RF generator (transmitter or transmission line from a transmitter) at the base of a radiator of length L. Although most commonly encountered verticals are quarter-wavelength ($L = \lambda/4$), that length is not the only permissible length. In fact, it may not even be the most desirable length. This chapter covers the standard quarter-wavelength vertical antenna (because it is so popular), and other-length verticals (both greater and less than quarter-wavelength).

The quarter-wavelength vertical antenna is basically half of a dipole placed vertically, with the "other half" of the dipole being the ground. Because of this fact, some texts show the vertical with a double-line ghost radiator, or image antenna, in the earth beneath the main antenna element. Figure 7-1B shows the current and voltage distribution for the quarter-wavelength vertical. Like the dipole, the quarter-wavelength vertical is fed at a current loop, so the feedpoint impedance is at a minimum (typically 2 to 37 Ω, depending upon nearby objects and design). As a result, the current is maximum and the voltage is minimum at the feedpoint. As you will see, however, not all vertical antennas are fed directly at the current loop. As a result, some designs require antenna tuning units to make them match the antenna impedance to the transmitter output impedance.

Figure 7-1C and 7-1D show the two basic configurations for the HF vertical antenna. Figure 7-1C shows the ground-mounted vertical antenna. The radiator

Copyright 2001 - the McGraw-Hill Companies



7-1A Basic elements of the vertical antenna.


Voltage
Current
Max
Min

7-1B Current and voltage distribution along vertical.



7-1C Simple coaxial-fed vertical antenna. There is a slight mismatch, but it usually is within tolerable limits.



7-1D Mast-mounted vertical uses radials as a counterpoise ground.

element is mounted at ground level, but it is insulated from ground. Because the antenna shown is a quarter-wavelength, it is fed at a current loop with 52-Ω coaxial cable. The inner conductor of the coaxial cable is connected to the radiator element, and the coaxial cable shield is connected to the ground. As you will see shortly, the ground system for the vertical antenna is critical to its performance. Normally, the feedpoint impedance is not 52 Ω, but rather is somewhat lower (37 Ω). As a result, without some matching there will be a slight VSWR, but in most cases, the VSWR is a tolerable tradeoff for simplicity. If the antenna has a feedpoint impedance of 37 Ω, which is the value usually quoted, then the VSWR will be 52 Ω/37 Ω, or 1.41:1.

A vertical mounted above the ground level is shown in Fig. 7-1D. This antenna is equally as popular as the ground mounted. Amateurs and CB operators find it easy to construct this form of antenna because the lightweight vertical can be mounted at reasonable heights (15 to 60 ft) using television antenna slip-up telescoping masts that are reasonably low in cost. A problem with the non-ground-level vertical antenna is that there is no easy way to connect it to ground. The solution to the problem is to create a counterpoise (artificial) ground with a system of quarter-wavelength radials.

In general, at least two radials are required for each band, and even that number is marginal. The standard wisdom holds that the greater the number of radials, the better the performance. Although that statement is true, there are both theoretical and practical limits to the number of radials. The theoretical limit is derived from the fact that more than 120 radials returns practically no increase in operational effectiveness, and at more than 16 radials, the returned added effectiveness per new radial is less than is the case for fewer radials. That is, going from 16 to 32 radials (doubling the number) creates less of an increase in received field strength at a distant point than going from 8 to 16 radials (both represent doubling the density of the radial system). The practical limit is 16 radials.

The radials of the off-ground-level vertical antenna can be at any angle. In Fig. 7-1D, they are "drooping radials" (i.e., the angle is greater than 90° relative to the vertical radiator element). Similarly, Fig. 7-1E shows a vertical antenna that is equipped with radials at exactly 90° (no common antenna has radials less than 90°). Both of these antennas are called *ground plane vertical antennas*.

The angle of the vertical's radials is said to affect the feedpoint impedance and the angle of radiation of the vertical antenna. Although those statements are undoubtedly true in some sense, there are other factors that also affect those parameters, and they are probably more important in most practical installations. Before digging further into the subject of vertical antennas, take a look at the subjects of angle of radiation and gain in vertical antennas.

Angle of radiation

Long-distance propagation in the HF region depends upon the ionospheric phenomena called "skip." (See Chap. 2 for a more extensive explanation.) In this type of propagation, the signal leaves the transmitting antenna at some angle a, called the *angle of radiation*, and enters the ionosphere where it is refracted back to earth at a distance D from the transmitting station. The signal in the zone between the outer edge of the antenna's ground-wave region and the distant skip point is weak or nonexistent.

The distance covered by the signal on each skip is a function of the angle of radiation. Figure 7-2 shows a plot of the angle of radiation of the antenna, and the distance to the first skip zone. The angle referred to along the vertical axis is the angle of radiation away from the antenna relative to the horizon. For example, an angle of


Quarter-wave
vertical radiator
Insulator
Quarter-wave
ground-plane rods
Coaxial
transmission
line

Ground-plane antenna


Ground-plane antenna
Horizontal plane

Radiation pattern

7-1E Ground-plane vertical antenna.



7-2 Effect of radiation angle on skip communications.

10° is elevated 10° above the horizon. Shorter distances are found when the angle of radiation is increased. At an angle of about 30°, for example, the distance per skip is only a few hundred miles.

Although you might expect on first blush to see a single line on the graph, there is actually a zone shown (shaded). This phenomenon exists because the ionosphere is found at different altitudes at different times of the day and different seasons of the year. Generally, however, in the absence of special event phenomena in the ionosphere, you can expect from 1500 to 2500 mi per bounce in the HF bands for low angles of radiation. Note, for example, that for a signal that is only a degree or two above the horizon the skip distance is maximum.

At distances greater than those shown in Fig. 7-2, the signal will make multiple hops. Given a situation where the skip distance is 2500 mi, covering a distance of 7500 mi requires three hops. Unfortunately, there is a signal strength loss on each hop of 3 to 6 dB, so you can expect the distant signal to be attenuated from making multiple hops between the earth's surface and the ionosphere. For maximizing distance, therefore, the angle of radiation needs to be minimized.

So what is the ideal angle of radiation? It is standard—but actually erroneous—wisdom among amateur radio operators (and even commercial operators, it turns out) that the lower the angle of radiation, the better the antenna. That statement is only true if long distance is wanted, so it reflects a strong bias toward the DX community. The correct answer to the question is: "It depends on where you want the signal to go." For example, I live in Virginia. If I want to communicate with stations in the Carolinas or New England, then it would behoove me to select a higher angle of radiation for radio conditions represented in Fig. 7-2 so that the signal will land in those regions. But if I wanted to work stations in Europe or Africa or South America, then a low angle of radiation is required. Because of the difference between performance of high and low angles of radiation, some stations have two antennas for each band: one each for high and low angles of radiation.

Figure 7-3 shows a signal from a hypothetical antenna located at point 0, in order to show what angle is meant by "angle of radiation." The beam from the antenna is elevated above the horizon (represented by the horizontal "tangent to horizon" line). The angle of radiation a is the angle between the tangent line and the center of the beam. This angle is not to be confused with the beamwidth, which is also an angle. In the case of beamwidth, we are talking about the thickness of the main lobe of the signal between points where the field strength is –3 dB down from the maximum signal (which occurs at point P); these points are represented by points X and Y in Fig. 7-3. Thus, angle b is the beamwidth, and angle a is the angle of radiation.

Gain in vertical antennas

Vertical antennas are considered *omnidirectional* because they radiate equally well in all directions. "Gain" in an antenna is not the creation of power, but rather a simple refocusing of energy from all directions to a specific direction; gain therefore infers directivity. According to the convention, then, the vertical antenna cannot have any gain because it radiates in all directions equally . . . gain infers directivity. Right? No, not really. Let's develop the theme more carefully.

Again consider the idea of an isotropic radiator (the word *isotropic* means equal power in all directions). Consider a spherical point source radiator located at point O in Fig. 7-4. Whatever the level of power available from the transmitter, it will be spread equally well over the entire surface of the sphere as it radiates out into space away from point O. If you measure the power distributed over some area A at a distance R from the source, then the power available will be a fraction of the total power:

$$P_{\text{avail}} = \frac{\text{total available power} \times A}{\text{total surface area of sphere}}$$



X, Y: −3 dB points
P: center beam
Angle a: elevation angle
Angle b: 3-dB beam width

7-3 Side view of vertical extent radiation pattern.

or, in math symbols:

$$P_a = \frac{P_s}{4\pi r^2} \qquad \textbf{[7.1]}$$

where

P_a is the power available per solid degree
P_s is the total radiated power, in watts
r is the radius of the sphere (i.e., the distance from O to P).

A practical rule of thumb for this problem is to calculate from the surface area of the sphere. If you perform the right calculations, you will find that there are approximately 41,253 square degrees on the surface of a sphere. By calculating the surface area of the beam front (also in square degrees), you can find the power within that region.

Now for the matter of gain in a vertical antenna. The vertical is not gainless because it does not, in fact, radiate equally well in all directions. In fact, the vertical is quite directional, except in the horizontal (azimuth) plane. Figure 7-5 shows the radiation pattern of the typical free-space vertical radiator. The pattern looks like a giant doughnut in free space (see solid pattern in Fig. 7-5). When sliced like a bagel, the pattern is the familiar circular "omnidirectional" pattern. When examined in the vertical plane, however, the plane looks like a sliced figure-8. The "gain" comes from the fact that energy is not spread over an entire sphere, but rather it is concentrated



7-4 Spherical or "isotropic" radiation pattern.

to the toroidal doughnut-shaped region shown. Therefore, the power per unit area is greater than for the isotropic (truly omnidirectional) case.

Non-quarter-wavelength verticals

The angle of radiation for a vertical antenna, hence the shape of the hypothetical doughnut radiation pattern, is a function of the length of the antenna. (*Note:* Length in terms of vertical antennas is the same as height, and is sometimes expressed in degrees of wavelength, as well as feet and/or meters.) Figure 7-6A shows the approximate patterns for three different-length vertical antennas: quarter-wavelength, half-wavelength, and ⅝-wavelength. Note that the quarter-wavelength antenna has the highest angle of radiation, as well as the lowest gain of the three cases.


Horizontal polar pattern
Antenna
Horizontal plane
Antenna (inside)
Vertical pattern
Null
Lobe
Lobe
Solid pattern
Vertical plane
Null

7-5 Vertical antenna radiation pattern.



7-6A Vertical radiation pattern as a function of element length: Ideal.

The ⅝-wavelength antenna is both the lowest angle of radiation and the highest gain (compared with isotropic).

The patterns shown in Fig. 7-6A assume a perfectly conducting ground underneath the antenna. However, that is not a possible situation for practical antennas; all real grounds are lossy. The effect of ground losses is to pull in the pattern close to the ground (Fig. 7-6B). Although all of the patterns are elevated from those of Fig. 7-6A, the relationships still remain: the ⅝-wavelength radiator has the lowest angle of radiation and highest gain.

The feedpoint impedance of a vertical antenna is a function of the length of the radiator. For the standard quarter-wavelength antenna, the feedpoint radiation resistance is a maximum of 37 **Ω**, with only a very small reactance component. Figure 7-7 shows the approximate feedpoint impedances for antennas from nearly zero effective length to 120° of length.

Antenna length expressed in degrees derives from the fact that one wavelength is 360°. Thus, a quarter-wavelength antenna has a length of 360°/4 = 90°. To convert any specific length from degrees to wavelength, divide the length in degrees by 360. Thus, for a 90° antenna: 90°/360° = ¼ wavelength. The graph in Fig. 7-7A shows the antenna feedpoint impedance, both reactance and radiation resistance, for antennas from 60 to 120°; Fig. 7-7B shows the radiation resistance for antennas from near zero to 60°. Note that the radiation resistance for such short antennas is extremely small. For example, an antenna that is 30° long ($30/360$ = 0.083 wavelengths) has a resistance of approximately 3 **Ω**. It is generally the practice on such antennas to use a broadband impedance-matching transformer to raise the impedance of such antennas to a higher value (Fig. 7-8).



7-6B Accounting for ground losses.



7-7A Antenna impedance as a function of antenna length.



7-7B Radiation resistance as a function of antenna length.

The ground system for the vertical antenna

The vertical antenna works well only when placed over a good ground system. Chapter 28 gives details of proper ground systems for all radio antennas, verticals included, so only certain specifics are included here. The reader should also examine Chap. 28, however, in order to get a firmer grasp of the problem.

The usual way to provide a good ground for a vertical is to use a system of radials such as Fig. 7-9A. This case shows a view (from above) of 16 quarter-wavelength radials arranged to cover the full circle around the antenna. Each radial is a quarterwavelength, so it will have a length (in fact) of $246/F_{\mathrm{MHz}}$. All of the radials are connected together at the base of the antenna, and the ground side of the transmission line is connected to this system. The radials can be placed either on the surface or underground. One friend of the author built an extensive radial system on the bare dirt when his house was built, so when the sod was installed he had a very high-quality underground radial system.



7-8 Impedance matching through broadband transformer.

If you decide to use an aboveground radial system, however, be sure to prevent people from tripping over it. There might be liability implications for people who trip and injure themselves, even when the person is an intruder or trespasser.

Some experts prefer to place a copper wire screen at the center of the radial system. The minimum size of this screen is about 2m square (6 × 6 ft). Connect it to the radials at the points shown using solder. Other experts will drive ground stakes into the ground at these points. Still another method is shown in Fig. 7-9B. This case shows a "spider web" of conductors shorting the radials at points a meter or two from the antenna. Again, some authorities recommend that ground rods be driven into the earth at the indicated points.

The exact number of radials to use depends in part on practical matters (how many can you physically install?). Use at least two radials per band, with four per band preferred for simple, low-cost systems. However, even four is considered a compromise case. The general rule is: *the more the better*. But it's also true that there is a law of diminishing returns as the number of radials is increased. Figure 7-9C shows the approximate field intensity (mV/m) as a function of the number of radials. Notice that the field intensity does not increase as rapidly with the number of radials above 20 or so. Note that the Federal Communications Commission requires AM band (550 to 1700 kHz) stations to use 120 radials, but that number is not necessary for amateur stations. A practical upper limit of 16 radials is usually accepted for amateur radio work, and four radials work quite well.



7-9A Comprehensive ground system for vertical antenna.

For vertical antennas mounted above ground, there is an optimum height above ground for the base of the antenna. This height is a quarter-wavelength above the actual ground plane. Unfortunately, that distance might not be the height above the surface. Depending upon ground conductivity and groundwater content, the height can be exactly a quarter-wavelength above the surface or slightly lower. The point is found from experimentation, and will, unfortunately, vary over the year if climatic changes are usual.

Variations on the vertical antenna theme

Thus far, the vertical antennas have been standard quarter- or ⅝-wavelength models. This section looks at several variations on the theme. Consider Fig. 7-10. This antenna is the vertical half-wavelength dipole. The vertical dipole is constructed in exactly the



7-9B "Spider web" ground system.

same manner as the horizontal dipole, but is mounted in the vertical plane. In general, the section of the radiator that is closest to the ground should be connected to the shield end of the coaxial cable transmission line.

Like the horizontal dipole, the approximate length of the vertical dipole is calculated from

$$L_{\mathrm{ft}} = \frac{468}{F_{\mathrm{MHz}}} \qquad \textbf{[7.2]}$$

where

L_{ft} is the length, in feet
F_{MHz} is the operating frequency, in megahertz

Example Calculate the length of a half-wavelength vertical dipole for operation on a frequency of 14.250 MHz in the 20-m amateur radio band.



7-9C Effect of increasing the number of radials on field strength.

Solution:

$$L_{\text{ft}} = \frac{468}{F_{\text{MHz}}}$$

$$L_{\text{ft}} = \frac{468}{14.250} = 32.8 \text{ ft}$$

Note: The 0.8 ft part of this calculated length can be converted to inches by multiplying by 12: 0.8 × 12 = 9.6 in.

Each leg of the vertical dipole is one half of the calculated length, or

$$\frac{32.8 \text{ ft}}{2} = 16.4 \text{ ft}$$

The vertical dipole antenna is used in many locations where it is impossible to properly mount a horizontal dipole, or where a roof- or mast-mounted antenna is impossible to install because of logistics, a hostile landlord, and/or a homeowners' association. Some row house and town house dwellers, for example, have been successful with the vertical dipole. In the 1950s and 1960s, the vertical dipole was popular among European amateurs because of space restrictions found in many of those locations.

The construction of the vertical dipole is relatively straightforward. You must find or build a vertical support structure. In the case shown in Fig. 7-10, the support



7-10 Vertical half-wavelength dipole antenna.

is a wooden or PVC mast erected for that purpose. Ropes and insulators at either end support the wire elements from the ends and keep the antenna taut. If the neighbors are a problem, then try to find some white PVC pipe that will make a fine flagpole and be patriotic—with a vertical dipole hidden inside of the pipe. In other cases, if your home is not metal-sided, and if it is high enough, then a support from the roof structure (or soffits) will make a proper mount.

One problem with the vertical dipole, and one that liability-conscious people need to consider, is that a high-impedance current node is found at the ends of a half- wavelength dipole. Anyone touching the antenna will likely receive a nasty RF burn (or shock) from this antenna.

A *coaxial vertical* is similar to the vertical dipole (and, in fact, it can be argued that it is a form of vertical dipole) in that it uses a pair of vertical radiator elements. In the case of the coaxial vertical antenna, however, the radiator that is closest to the ground is coaxial with the transmission line and the main radiator element. An example is shown in Fig. 7-11A. An insulator at the feedpoint separates the two halves of the radiator; in most cases, it is of smaller diameter than the coaxial sleeve (also called the *shield pipe* in some publications). The reasons for this arrangement are not entirely electrical, for the most part, but mechanical. The coaxial cable transmission line passes through the sleeve, and is itself coaxial to the sleeve.

The overall length of the coaxial vertical antenna is a half-wavelength, which consists of two quarter-wavelength sections. Both the radiator and the sleeve are quarter-wavelength. The length of each is found (approximately) from

$$L_{\mathrm{ft}} = \frac{234}{F_{\mathrm{MHz}}} \qquad \textbf{[7.3]}$$

or

$$L_{\mathrm{meters}} = \frac{72}{F_{\mathrm{MHz}}} \qquad \textbf{[7.4]}$$

You should recognize these as similar to the equation used previously to calculate half-wavelength antennas, but reduced by a factor of 2.

The coaxial vertical antenna was once popular with CB operators, and as such was called the *collinear antenna*. In some cases, you can find hardware from these antennas on the hamfest or surplus markets, and the pieces can be modified for amateur radio use. In the situation where a 10-m-band antenna is being built, it is a simple matter to cut the 11-m CB antenna for operation on a slightly higher frequency. In the case of the lower-frequency bands, however, it is a little more difficult and it is likely that only the insulator and mounting assembly are salvageable. Keep in mind, however, the fact that adjacent sizes of aluminum tubing are designed such that the inside diameter (ID) of the larger piece is a slip-fit for the outside diameter (OD) of the smaller piece. You can, therefore, connect adjacent sizes of aluminum tubing together without the need for special couplers, etc. With that in mind, salvaged insulator assemblies can be cut off with just 6 to 10 in of the former radiator and sleeve, and new radiators from “adjacent size” tubing installed.

The configuration shown in Fig. 7-11A is the manner of construction used by commercial antenna manufacturers for VHF and CB collinear vertical dipoles, but is a little difficult for amateurs (unless they happen to own a machine shop) to make the center insulator. For those people, some other method is indicated before this antenna is practical.



7-11A Construction of the vertical coaxial antenna.

Figure 7-11B shows a construction method that has been used by amateurs with good results. The radiator and shield pipe (sleeve) are joined together in an insulating piece of thick-wall PVC plumbing pipe, Lucite, or plexiglass tubing; 6 to 10 in of tubing are needed.

A gap of about 2 in is left between the bottom end of the radiator pipe and the top end of the shield pipe in order to keep them electrically insulated from each



7-11B Vertical dipole made from tubing.

other, and to allow the coaxial cable to be passed through to the outside world. A hole in the insulator pipe is drilled for this purpose.

The aluminum tubing pieces for the radiator and the sleeve are fastened to the insulator with at least two heavy machine screws each. One of the machine screws on each can be used as the electrical connection between the coaxial cable and the pipes, provided that a larger hole is cut in the insulator at that point to admit the washer that provides the electrical pathway between the screw head and the aluminum pipe.

If you depend upon the machine screw touching the pipe at the edges of the hole cut for it, then there will probably be intermittent connection and all of the aggravation that ensues.

Mounting of the homebrew coaxial vertical antenna can be a “pain in the neck.” Normally, this antenna is mounted high in the air above ground, so some form of support is needed. Fortunately, you can use small-area metal supports connected to the sleeve for this purpose. Figure 7-11C shows one method for mounting that is popular. A pair of television antenna standoff mounting brackets are used to support the sleeve. Those brackets can be bought in sizes from 6 to 24 in. Note that a 2 × 4 piece of lumber is used between the building wall and the brackets. This wood serves as an



7-11C Mast mounting system for verticals.

insulator, so it should be varnished or painted. It is held to the wall with lag bolts, wing bolts, or some other effective method of anchoring. Keep in mind that the forces on the brackets increase tremendously during wind storms!

It is possible for the two vertical antennas shown previously to become a shock hazard to anyone who touches them. Both of these antennas are half-wavelength radiators and are of the dipole form of construction. The center point is used for feeding the antenna, so it forms the low-impedance point in the antenna. As a result, the ends of the antenna, one of which is close to the ground, are the high-impedance points—hence the voltages at those points within reach of prying hands playing in the yard can be high. It is wise to either mount the antennas so far above the ground that they cannot be reached, or build a small nonconductive fence around the bottom end of the antenna.

Vertical antenna construction

There are two general cases for installing vertical antennas: ground-level-mounted and non-ground-mounted. This section takes a brief look at both forms of mounting. We will concentrate on installation of homebrew verticals rather than commercial, because it is assumed that the vendors of such antennas will provide their own instructions.

The ground-level-mounted vertical is shown in Fig. 7-12. The typical vertical antenna is 8 to 40 ft high. Thus, although the actual weight of the antenna is small, the forces applied to the mounting structure (especially during windstorms) can be quite high. Don't be fooled by the apparent light weight of the antenna in this respect.

The mounting structure for the vertical antenna can be a metal or wooden fence post buried in the ground. At least 2 ft of the fence post should be above ground. In the case of Fig. 7-12, a 4 × 4 wooden fence post is used as the mounting, but the principles are similar for all forms of post. A fence post hole is provided that is at least 2 ft deep. In some cases, it might be possible to use a 1-ft-deep gravel fill topped with back-filled dirt. In other cases, especially where a steel fence post is used, a concrete plug is placed at the bottom of the hole over a 4-in layer of gravel.

The antenna radiator element is installed onto the fence post using standoff insulators. Unfortunately, these insulators are difficult to find, so they might have to be omitted. Given that varnished or painted wood is not a terribly good conductor, it is not unreasonable to bolt the radiator directly to the 4 × 4 fence post. Use $\frac{5}{16}$-in (or larger) bolts, and make them long enough to fit completely through both the antenna element and the 4 × 4 post. Thus, 6-in-, 7-in-, or 8-in-long $\frac{5}{16}$-in bolts are the candidates for this job. Use at least two bolts, one at the bottom of the antenna radiator element, and one near the top of the fence post. A third bolt, halfway between the other two, would not be out of order.

If the antenna is quarter-wavelength, then no matching is generally necessary. Although the feedpoint impedance is not exactly 52 Ω, it is close enough (37 Ω) to form a reasonable match for 52-Ω coaxial cable (with VSWR = 1.4:1). The center conductor of the coaxial cable is connected to the radiator element, while the shield is connected to the ground system. In the example shown in Fig. 7-12, two ground methods are used. First, an 8-ft ground rod is driven into the earth at the base of the


Radiator
element
Standoff
insulators
Treated
4×4 fence post
Coax to
XMTR
Ground level
Back fill
$\lambda/4$ radial
> 2 ft
Gravel
Ground rod
(8 ft)

7-12 Ground-mounted vertical.

antenna; second, a system of quarter-wavelength radials is used. Remember that the ground system is absolutely essential.

A method for installing a vertical antenna above ground is shown in Fig. 7-13. In this case, a wooden support (2 × 4 or 4 × 4) is installed in a manner similar to Fig. 7-12, but with a deeper hole to counter the longer length. Alternatively, the wooden support is affixed to the side of a building wall, shed, or other preexisting structure. Once the support is arranged, however, the method of attachment of the radiator element is the same for the previous case, so that will not be repeated here.

Electrical connections to the antenna are also shown in Fig. 7-13. Because the antenna is above ground level, an electrical counterpoise ground consisting of a system of radials is absolutely essential; at least two radials per band must be provided. A small L bracket is used to support the radials and to provide an SO-239 coaxial connector for the coax. This connector is a chassis-mounted type with its center conductor connected to the radiator element. The shield of the connector is connected to the bracket, so it is also connected to the radial system.

In some installations, the antenna support structure will require guy wires to keep the structure stable. Do not use the radials as guy wires. The type of wire that normally works well for radials is too soft, and too easily stretched, for guy wire service. Use regular steel guy line, available where TV antenna supplies are sold, for this antenna. Make the lengths nonresonant, and break the guy lines up with egg insulators, if necessary, to achieve the nonresonance.

⅝-Wavelength verticals

Figure 7-14 shows the configuration for the ⅝-wavelength vertical antenna. Such an antenna generally gives a lower angle of radiation than the more common quarter-wavelength radiator, so presumably it works better for long distance.

The radiator of this antenna is made from 0.5-in to 1.5-in aluminum tubing. Again, remember that adjacent sizes fit together snugly to form longer sections. The physical length of the ⅝-wavelength radiator is found from

$$L_{\mathrm{ft}} = \frac{585}{F_{\mathrm{MHz}}} \tag{7.5}$$

or, in meters,

$$L_{\mathrm{meters}} = \frac{180}{F_{\mathrm{MHz}}} \tag{7.6}$$

The radials are the usual quarter-wavelength, and are made of no. 12 or no. 14 copper wire. These lengths are found from:

$$L_{\mathrm{ft}} = \frac{246}{F_{\mathrm{MHz}}} \tag{7.7}$$


Stand-off
insulators
Radiator
element
Wooden
support
Metal
bracket
Radials

7-13 Details of feedpoint circuit on vertical.



7-14 Using a Q section to match the feedpoint impedance of a vertical antenna.

or, in meters,

$$L_{\text{meters}} = \frac{75}{F_{\text{MHz}}} \qquad \textbf{[7.8]}$$

The feedpoint impedance of the ⅝-wavelength antenna is about 1600 Ω, not a good match for the ordinary coaxial cables that are routinely available on the amateur market. Some form of impedance matching is needed.

One option is to use a broadbanded RF transformer. These transformers will work throughout the HF spectrum, and match a wide variety of impedances to the 50-Ω standard system impedance.

Another option, especially for a single-band antenna, is to use a coaxial cable impedance transformer, such as shown in Fig. 7-14. The transformer consists of two sections of coaxial cable joined together, shown as L_1 and L_2 in Fig. 7-14. The lengths are found from

$$L_1 = \frac{122}{F_{\text{MHz}}} \text{ ft} \qquad \textbf{[7.9]}$$

or

$$L_1 = \frac{38}{F_{\mathrm{MHz}}} \text{ m} \tag{7.10}$$

and

$$L_2 = \frac{30}{F_{\mathrm{MHz}}} \text{ ft} \tag{7.11}$$

$$L_2 = \frac{9}{F_{\mathrm{MHz}}} \text{ m} \tag{7.12}$$

Grounded vertical antennas

The vertical antennas presented thus far in this chapter are called *series-fed verticals*, because the generator is essentially in series with the radiator element. Such an antenna must be insulated from ground. The other class of vertical is the *shunt-fed vertical*, which is grounded at one end (Fig. 7-15). There are three methods of shunt-feeding a grounded vertical antenna: *delta, gamma*, and *omega*. All three matching systems have exactly the same function: to form an impedance transformation between the antenna radiation resistance, at the feedpoint, and the coaxial cable characteristic impedance, as well as cancelling any reactance in the system.

The delta feed system is shown in Fig. 7-15A. In this case, a taut feed wire is connected between a point on the antenna, which represents a specific impedance on



7-15A Delta-fed grounded vertical.

the antenna, and an antenna tuner. This method of feed is common on AM broadcast antennas (which are usually—perhaps always—verticals). Although you would think that the sloping feed wire would distort the pattern, that is not the case. The distortion of the pattern, if any, is minimal, hence it can be neglected.

The gamma feed system is shown in Fig. 7-15B. This method is commonly used by amateurs to feed Yagi beam antennas, so it is quite familiar in the amateur radio world. The feed system consists of a variable capacitor to tune the system, and a matching rod that parallels the antenna radiator element. It is important that the rod not be anywhere near a quarter-wavelength, or it would become a vertical antenna in its own right, and in fact would resemble the so-called *J-pole antenna*. A review of the gamma match is given in Chap. 12. The omega feed (shown in Fig. 7-15C) is similar to the gamma match except that a shunt capacitor is used.

Conclusion

The vertical antenna is a viable alternative for many situations, especially where real estate is at a premium. Contrary to popular opinion, the vertical antenna works well when installed properly and when due consideration has been given to matters such as the grounding and angle of radiation desired.



7-15B Gamma-fed grounded vertical.



7-15C Omega-fed grounded vertical.

8
CHAPTER

Multiband and tunable-wire antennas

MOST COMMUNICATIONS OPERATORS REQUIRE MORE THAN ONE BAND, AND THAT MAKES the antenna problem exactly that—a problem to be solved. Amateur radio, commercial, and military operators are especially likely to need either multiple antennas for different bands, or a multiband antenna that operates on any number of different bands. This situation is especially likely on the high-frequency (HF) bands from 3.5 to 29.7 MHz.

Another problem regards the tunability of an antenna. Some amateur bands are very wide (several hundred kilohertz), and that causes any antenna to be highly variable from one end of the band to another. It is typical for amateurs to design an antenna for the portion of the band that they use most often, and then tolerate a high VSWR at the other frequencies. Unfortunately, when you see an antenna that seems to offer a low VSWR over such a wide range, it is almost certain that some problem exists that reduces the Q, and the antenna efficiency, to broaden the response. However, it is possible to tune an antenna for a wide band. It is also possible (now that amateurs have new HF bands) to use a single antenna between them, and then tune the difference out. For example, designing a single antenna for 21/24 MHz, 14/18 MHz, or 7/10 MHz should prove possible.

In this chapter we will take a look at both problems: the multiband and the tunable antenna.

Multiband antennas

Although a triband Yagi or quad beam antenna will undoubtedly work better than a wire antenna (when installed correctly!), the low-budget amateur operator need not lament any supposed inability to "get out" on wire antennas. To quote an old saying: "'Better' is the enemy of 'good enough.'" Or, to put it in terms of *Carr's law:* "If it's 'good enough' then don't waste a lot of energy fretting over making it 'better' unless you really want to make it *a lot better*."

Copyright 2001 - the McGraw-Hill Companies

Trap dipoles

Perhaps the most common form of multiband wire antenna is the *trap dipole* shown in Fig. 8-1A. In this type of antenna, one (or more) pairs of parallel resonant traps are placed in series with the quarter-wavelength elements of the dipole. The purpose of the traps is to block their own resonant frequency, while passing all other frequencies.

In the example of Fig. 8-1A, a 10-m trap isolates the first 8 ft or so (quarter-wavelength on 10 m) so that the antenna resonates on that band. A 40-m or 15-m signal, on the other hand, passes through the traps and uses the whole length of the antenna. (*Note*: A half-wavelength 40-m dipole works as a 3/2-wavelength antenna on 15 m.)

The overall length of the trap dipole will be a little less than the natural "non-trap" length for the lowest frequency of operation. At the low frequencies, the traps add a little inductance to the circuit so that the resonant point is lower than the natural resonant frequency. In general, most trap dipoles are just a few percent shorter than nontrap dipoles at the same band. The actual amount of shortening depends upon the values of the components in the traps, so consult the data for each trap purchased. Where more than one pair of traps is used in the antenna, make sure they are of the same brand and are intended to work together.

Another solution to this problem is shown in Fig. 8-1B. This type of antenna actually has two or more half-wavelength dipoles fed from the same transmission line. In this illustration, a total of three dipoles are fed from the same 75-Ω transmission line. There is no theoretical limit to how many dipoles can be accommodated, although there is certainly a practical limit. For one thing, there is a mechanical limit to how many wires are supportable (or desirable) hanging from any given support. There is also an electrical limit, although it is less defined. Having a lot of dipoles increases the possibility of radiating harmonics and other spurious emissions from your transmitter.

The 75-Ω coaxial cable is connected to the center feedpoint of the multidipole either directly or through a 1:1 balun transformer, as shown in Fig. 8-1B. Each an-



A=10-meter segment
A+B=15-meter/40-meter segment

8-1A Trap dipole for multiband operation. (*Courtesy of Hands-On Electronics and Popular Electronics*)



8-1B Multiband dipole consists of several dipoles fed from a common feedline.

tenna (*A-A*, *B-B*, or *C-C*) is a half-wavelength. Therefore, the overall length is found approximately from the standard dipole expressions:

Overall length ($A + A$, $B + B$, or $C + C$):

$$L_{\mathrm{ft}} = \frac{468}{F_{\mathrm{MHz}}} \tag{8.1}$$

or, for each element alone (*A*, *B*, or *C*):

$$L_{\mathrm{ft}} = \frac{234}{F_{\mathrm{MHz}}} \tag{8.2}$$

As always, close to the earth's surface, these equations are approximations, and are not to be taken too literally. Some experimentation will probably be necessary to optimize resonance on each band. Also, be aware that the drooping dipoles (*B* and *C* in this case) may act more like an inverted-vee antenna (see Chap. 7) than a straight dipole, so the equation length will be just a few percent too short. In any event, a little spritzing with this antenna will yield results.

Some amateurs build the multiple dipole from four- or five-wire TV rotator lead. That type of wire is used to control antenna rotators, and has either four or five parallel wires in a flat arrangement similar to lamp cord. Cut each wire to the length required for a band, and strip off any unused portions.

Another possibility is the link-tuned dipole shown in Fig. 8-1C. In this situation, a single conductor is used for each half of the dipole, or actually inverted vee. The conductors are broken into segments A, B, and C (or more, if desired). Each segment is separated from the two adjacent sections by inline insulators (standard end insulators are suitable). Segment A is a quarter-wavelength on the highest frequency band of operation, $A + B$ is a quarter-wavelength on the next highest band of operation, and $A + B + C$ is a quarter-wavelength on the lowest frequency band of operation.

The antenna is "tuned" to a specific band by either connecting, or disconnecting, a similar wire (see inset) jumper across the insulator that breaks the connection between the segments. Either a switch or an alligator clip jumper will short out the insulator to effectively lengthen the antenna for a lower band. Some amateurs use single-pole 110-Vac power line switches to jumper the insulator. Although I have not tried this method, it should work.



8-1C Multiband inverted vee uses shorting links to change bands.

A big disadvantage to this type of multiband antenna is that you must go out into the yard and manually switch the links to change bands, which probably explains why other antennas are a lot more popular, especially in northern latitudes.

Tuned feeder antennas

Figure 8-2A shows the tuned feeder type of antenna. This antenna can be used from 80 through 10 m, but it requires a special tuner and a length of parallel transmission line. There are two ways to get parallel transmission line: make it or buy it. Using no. 14 or 12 wire, and specially made insulators (also called *spreaders*), you can make 300-, 450-, or 600-Ω parallel transmission line. But that's a pain in the *ptusch* because you can also buy parallel line rather cheaply. I paid $16 for 100 ft of 450-Ω line recently.

One form of parallel line is ordinary TV-type twin lead, which has an impedance of 300 Ω. This line will take up to about 250 W, although some people use it at higher powers (not recommended!). The antenna of Fig. 8-2A uses 450-Ω parallel line. You can buy insulated 450-Ω twin lead (see Fig. 8-2B) that can be handled as easily as TV twin lead—and a lot more easily than open (uninsulated) parallel line.

The G5RV multiband dipole

Figure 8-3 shows the popular G5RV antenna. Although not without some problems, this antenna is very popular. It can be used either as a horizontal dipole, a sloper, or an inverted-vee antenna (which is how I used it). The dipole elements are each 51 ft long. The feedline can be either 300- or 450-Ω twin lead. For 300-Ω cases, use 29 ft of line, and for 450-Ω line, use 34 ft. One end of the parallel transmission line is connected to the antenna, and the other end is connected to a length of 50-Ω coaxial


135 Feet
80-10 meter antenna
450-Ω or 600-Ω parallel line (any length)
Balanced antenna tuner
Coax
XMTR
A
B

8-2 Tuned feeder antenna can be used on several bands. (*Courtesy of Hands-On Electronics and Popular Electronics*)

8-3 G5RV antenna.
(*Courtesy of Hands-On Electronics and Popular Electronics*)


51'
51'
L
50-Ω coax (any length)

Twin lead Z_0	L (Feet)
300 Ω	29
450 Ω	34

cable. Although most articles on the G5RV claim that any length of 50-Ω line will work, J. M. Haerle (*HF Antenna Systems: The Easy Way*) recommends that the 50-Ω segment should be at least 65 ft long.

Haerle is a little caustic in his comments on the G5RV, but his criticism is well taken. If you don't have a parallel transmatch, then the G5RV will work (especially if your rig can tolerate a 3:1 VSWR on some selected frequencies). Otherwise, use the antenna of Fig. 8-2A (or a transmatch with the G5RV).

Figure 8-4 shows the once-popular end-fed Zepp antenna. This antenna is a “monopole” in that it uses a half-wavelength radiator, but it is fed at a voltage loop rather than a current loop (i.e., the end of the antenna rather than the center). A 450- or 600-Ω parallel transmission line is used to feed the Zepp antenna. Although the line can theoretically be any length, practicality dictates a quarter-wavelength because of the fact that the antenna is fed at a high RF voltage point.

The Zepp (as shown) is a single-band antenna unless the transmission line is fed with a good, widerange transmatch, or other antenna tuner unit. The antenna tuner required is a balanced type, although a standard transmatch with a 4:1 balun transformer at the output will also work well. Using the Zepp on many bands is easy, but keep in mind that it is voltage-fed, and (at frequencies for which the parallel line is not an odd integer multiple of a quarter-wavelength) there will be a high-voltage node at the transmatch. That raises the possibility of “RF in the shack”—“hot” snippets of RF on the grounded chassis of station equipment (including microphones, where it is uncomfortable when touched to the lips).

Feeding parallel transmission line

Parallel transmission line is *balanced* with respect to ground, but coaxial cable is *unbalanced* to ground (i.e., one side of the coax is usually grounded). As a result, the standard amateur transmitter output will not drive parallel (balanced) feedline properly. You need to do one of two things: (1) buy (or build) an antenna tuner that is balanced on the output and unbalanced on the input or (2) convert a standard "coax-to-coax" transmatch or other form of antenna coupler to “coax-to-balanced” configuration. In some cases you can use a 4:1 balun transformer at the output of the coaxial cable tuner. Keep in mind, however, that some tuner manufacturers recommend against this practice. If you use the standard tee-network (or SPC) transmatch



8-4 End-fed Zepp antenna.

then it is possible to make a balun for this purpose from some no.12 formvar- or enamel-covered wire and either a ferrite toroid or a short piece of PVC plumbing pipe. Figure 8-5 shows a balun coil construction project. Use 12 turns of no.12 formvar or enameled wire over a 1-in outside diameter piece of PVC pipe or tubing.

Next, we have the so-called longwire antenna. I use the term *so-called* because not all long wire antennas are truly longwires. A true longwire is longer than two wavelengths at the lowest frequency of operation. In Fig. 8-6 we see a longwire, or "random-length," antenna fed from a tuning unit. If the antenna length *L* is greater than a quarter-wavelength, then the tuner consists of a single series capacitor (see below); and if it is shorter than a quarter-wavelength, the tuner is a series inductor. The standard tuner for this type of antenna, regardless of length, is a simple L-section coupler (also shown), which can be selected for L-section, series-L or series-C operation.

The Windom antenna (Fig. 8-7) has been popular since the 1920s. Although Loren Windom is credited with the design, there were actually a number of contributors. Coworkers with Windom at the University of Illinois were John Byrne, E. F. Brooke, and W. L. Everett, and they are properly cocredited. The designation of Windom as the inventor was probably due to the publication of the idea (credited to Windom) in the July 1926 issue of *QST* magazine. Additional (later) contributions were rendered by G2BI and GM1IAA (Jim MacIntosh). We will continue the tradition of crediting Loren Windom, with the understanding that others also contributed to this antenna design.

The Windom is a roughly half-wavelength antenna that will also work on even harmonics of the fundamental frequency. The basic premise is that the antenna radiation resistance varies from about 50 Ω to about 5000 Ω, depending upon the


Connect only if parallel line connected to A and B
Coaxial output (disconnect if parallel line is connected to A and B)
L_1
A
L_2
Ceramic feed-through insulators
L_3
B
● Indicates same magnetic polarity of coil

8-5 Balun transformer converts coaxial line to parallel line feed system.



8-6 Random-length (a.k.a., if erroneously, "longwire") antenna.

selected feedpoint. When fed in the exact center, a current loop, the feedpoint impedance will be 50 Ω; similarly, end feeding the antenna finds a feedpoint impedance of about 5000 Ω. In Fig. 8-7A the feedpoint is tapped away from the center at a point that is about one-third the way from one end, at a point where the impedance is about 600 Ω.

The Windom antenna works well—but with some caveats. For example, the antenna has a tendency to put "RF in the shack" because of the fact that it is voltage-fed. Second, there is some radiation loss from the feedline. Finally, the antenna works poorly on odd harmonics of the fundamental frequency.

The antenna tuning unit can be either a parallel resonant, link-coupled *LC* tank circuit (see inset to Fig. 8-7A); or a reversed pi network. In the case of the Windom, the pi network is turned around backward from the usual configuration: C_1 is at the low-impedance end of the network, so it is larger than C_2. Design a pi network (see programs at end of book) to match 50 Ω on the transmitter end and 600 Ω on the antenna end.

A reasonable compromise Windom that reduces feedline radiation losses is shown in Fig. 8-7B. In this antenna a 4:1 balun transformer is placed at the feed point, and this in turn is connected to 75-Ω coaxial transmission line to the transmitter. A transmatch, or similar antenna tuner, is then connected between the transmitter and the transmission line.


Insulator
$A = 0.18\lambda$
$B = 0.32\lambda$
Insulator
Rope
Downlead
(#12 or #14)
$A = 0.18\lambda$
$B = 0.32\lambda$
$A+B = 0.50\lambda = \frac{468}{F_{MHz}}$ Feet
Coax
to
XMTR
Tuner
Coax
to
XMTR
Ant
— or —
Lo-Z
Hi-Z
Ant
XMTR
C1
C2

8-7A Windom antenna.


136'
44.33'
4:1 BALUN
Tuner
XMTR

8-7B Coaxial-fed Windom.

This page intentionally left blank

9
CHAPTER
Longwire directional antennas

YOU'VE HEARD IT DOZENS OF TIMES: THE RANDOM-LENGTH LONGWIRE ANTENNA IS THE "perfect" solution to awkward antenna problems. Whether it's a lack of real estate, cranky landlords, or a profound lack of dollars, the random-length longwire will do the job for you. Right? Well, now, that depends on who you ask, and what they did to make it work— or not work. One person says the longwire is not worth a plugged nickel; another is very ho-hum about it because his "kinda works"; still another is enthusiastic because hers is installed correctly and it works better than anything "since sliced pickle and liverwurst sandwiches." Over the years my various living arrangements have forced me to use longwires at many QTHs, as well as on Field Day. Why does the random-length longwire have such a varied reputation? Before we answer that question let's find out (for those who came in late) just what is a longwire antenna.

As an aside, let me point out that random-length wire antennas (less than 2λ) are not true longwire antennas. However, common (if erroneous) usage compels the inclusion of both types.

Longwire antennas

Longwire antennas are any of several types of resonant and nonresonant antennas. Any given longwire antenna may be both resonant and nonresonant, depending upon the operating frequencies used. In the "old days," when I was first starting in amateur radio, most resonant longwires were resonant over all HF bands because those bands were harmonically related to each other. But with the addition of the 10-, 18-, and 24-MHz band segments, that relationship no longer holds true for all cases.

Figure 9-1 shows the classic random length, nonresonant longwire antenna. It consists of a wire radiator that is at least a quarter-wavelength long, but is most often longer than a quarter-wavelength. The specific length is not critical, but it must be *greater than a quarter-wavelength at the lowest frequency of operation anticipated*. If you have a 90-ft wire, it will work on all HF bands above 3.5 MHz. In

Copyright 2001 - the McGraw-Hill Companies



9-1 Random-length antenna.

most installations, the wire is no.12 and no.14 *copperweld*, or hard-drawn copper wire. I have successfully used both no.12 and no.14 house wire, but because it is solid (not stranded) it is not the best material. Stranded wire lasts longer in the wind, because solid wire fatigues and breaks quicker.

The longwire antenna is capable of providing gain over a dipole and a low angle of radiation (which is great for DX operators!). But these advantages are only found when the antenna is several wavelengths long, so it occurs only on typical HF antennas in the 21- through 29-MHz bands.

The longwire is end-fed, and therefore has a high impedance, except in those cases where the radiator happens to be quarter-wavelength. Because of this fact, it is necessary to use an antenna tuner between the low-impedance transmitter output (usually limited to 50- to 75-Ω impedances) and the antenna. You can buy any of several commercial antenna tuners, or make one yourself. Figure 9-2 shows a typical antenna tuner for longwires. It is an L-section coupler consisting of a series inductance and a shunt capacitance, both variable. The inductor can be homemade, or it can be made from a B&W miniductor (3029 is suitable). Alternatively, you can buy a used roller inductor from a hamfest. If you opt for the homemade or miniductor alternatives, then an alligator clip lead (short!) connected to one end of the coil can be used to short out unneeded turns when adjusting the inductance. I prefer the roller inductor method, because it allows the whole “shootin’ match” to be installed inside a shielded cabinet, helping the TVI/BCI (television interference/broadcast interference) situation.



9-2 L-section coupler.

The capacitor (also available from the same sources) should be 150-pF to 250-pF maximum capacitance high-voltage variable. So-called transmitting variables are usually ok if the plate spacing is at least ⅛ in.

Tuning of the longwire is simplicity itself. If the tuner does not have a built-in VSWR meter, then install one in the line between the transmitter output and the tuner input. Adjust both L_1 and C_1 (they are a bit interactive so do it several times) for the lowest VSWR. If you use the alligator clip method, *turn off the darn transmitter before adjusting the clip position—RF burns are nasty!*

So what's the problem?

Ok, so we have decided to install a longwire. How do we make it work? First, make sure that it is long enough. The bare minimum lengths for HF bands are 70 ft for 3.5 MHz and up, 34 ft for 7 MHz and up, and so on. In general, the longer the better. The second problem is a *good ground*. The importance of a good ground cannot be underestimated, and it accounts for about 99 percent of the difference in reported performance of longwires.

A good ground consists of a short wire to either one very long ground rod or multiple ground rods spaced a couple feet apart. An important factor is the length of the ground wire. It must be considerably less than a quarter-wavelength. Use no.10 stranded wire (several parallel lengths) or braid.

When I was in college I lived on the second floor of a whacky student boarding house in Norfolk, VA. The ground was 24 ft away, and that made "short ground wire" a joke—and my longwire nearly inoperative. But I figured out a way around the problem. A quarter-wave radial was dropped out the window (see Fig. 9-3). Use more than one radial if possible. In one case, when the landlord was particularly cranky, I tacked the radial to the baseboard of my room (insulated on standoffs at the far end to protect against the high RF voltages present). It worked well!

A new product also comes to the rescue of those reader-hams who cannot put up a good longwire. The MFJ Enterprises (Box 494, Mississippi State, MS, 39762, 1-800-647-1800) model MFJ-931 artificial RF ground is installed in the ground line (see Fig. 9-4) and is used to tune the ground wire. Adjust the capacitance and inductance controls for maximum ground current as shown on the built-in meter. Be sure to follow the instructions, however, because high RF voltages can appear on a nonresonant ground wire. I wish I'd had one of these when I was in that whacky boarding house; discussing existentialist poetry can't hold a candle to DXing.


Random length
(> λ/4)
Coax
to
XMTR
Antenna
tunner
λ/4 Radials

9-3 Radials improve the "ground" of random-length antenna.


Tuner
Coax
Antenna wire
MFJ-931
Ground
system

9-4 MFJ ground line tuner installation.

When is a long wire a longwire?

For many years, the longwire has been a popular form of antenna. It is cheap, it is easy to construct, and—although reports vary—it has the potential to perform well. Properly constructed, it has a lot of utility. But what is a *real* longwire antenna? In past columns, I have used the term to mean an antenna such as Fig. 9-1. This form of antenna is popularly called a *longwire* if it is more than a quarter-wavelength. I and other authors have used the term longwire to mean this antenna, but that's not rigorously correct. A *true* longwire is an antenna that is many wavelengths long, or to be a little more rigorous, an antenna that is *more than two wavelengths long*. Although I will still use the term *longwire* for both forms of longwire antenna, proper rigor requires Fig. 9-1 to be called a "random-length antenna."

True longwire antennas

Figure 9-5 shows the true resonant longwire antenna. It is a horizontal antenna, and if properly installed, it is not simply attached to a convenient support (as is true with the random length antenna). Rather, the longwire is installed horizontally like a dipole. The ends are supported (dipole-like) from standard end insulators and rope.

The feedpoint of the longwire is one end, so we expect to see a voltage antinode where the feeder is attached. For this reason we do not use coaxial cable, but rather either parallel transmission line (also sometimes called *open-air* line or some such



9-5 End-fed longwire with suitable tuner.

name), or 450-Ω twin lead. The transmission line is excited from any of several types of balanced antenna tuning unit (see Fig. 9-5). Alternatively, a standard antenna tuning unit (designed for coaxial cable) can be used if a 4:1 balun transformer is used between the output of the tuner and the input of the feedline.

What does "many wavelengths" mean? That depends upon just what you want the antenna to do. Figure 9-6 shows a fact about the longwire that excites many users of longwires: It has gain! Although a two-wavelength antenna only has a slight gain over a dipole; the longer the antenna, the greater the gain. In fact, it is possible to obtain gain figures greater than a three-element beam using a longwire, but only at nine or ten wavelengths.



9-6 Antenna length versus gain over dipole.

What does this mean? One wavelength is $984/F_{\text{MHz}}$ ft, so at 10 m (29 MHz) one wavelength is about 34 ft; at 75 m (3.8 MHz) one wavelength is 259 ft long. In order to meet the two-wavelength criterion a 10-m antenna need only be 68 ft long, while a 75-m antenna would be 518 ft long! For a ten-wavelength antenna, therefore, we would need 340 ft for 10 m; and for 75 m, we would need nearly 2,600 ft. Ah me, now you see why the longwire is not more popular. The physical length of a nonterminated resonant longwire is on the order of

$$L_{\text{feet}} = \frac{492(N - 0.025)}{F_{\text{MHz}}} \qquad \textbf{[9.1]}$$

(N is number of half-wavelengths in the radiator elements.)

Of course, there are always people like my buddy (now deceased) John Thorne, K4NFU. He lived near Austin, TX on a multiacre farmette that has a 1400-ft property line along one side. John installed a 1300 ft longwire and found it worked excitingly well. He fed the thing with homebrew 450-Ω parallel (open-air) line and a Matchbox antenna tuner. John's longwire had an extremely low angle of radiation, so he regularly (much to my chagrin on my small suburban lot) worked ZL, VK, and other Southeast Asia and Pacific basin DX, with only 100 W from a Kenwood transceiver.

Oddly enough, John also found a little bitty problem with the longwire that textbooks and articles rarely mention: electrostatic fields build up a high-voltage dc charge on longwire antennas! Thunderstorms as far as 20 mi away produce serious levels of electrostatic fields, and those fields can cause a buildup of electrical charge on the antenna conductor. The electric charge can cause damage to the receiver. John solved the problem by using a resistor at one end to ground. The "resistor" is composed of ten to twenty 10-MΩ resistors at 2 W each. This resistor bleeds off the charge, preventing damage to the receiver.

A common misconception about longwire antennas concerns the normal radiation pattern of these antennas. I have heard amateurs, on the air, claim that the maximum radiation for the longwire is

1. Broadside (i.e., 90°) with respect to the wire run or
2. In line with the wire run

Neither is correct, although ordinary intuition would seem to indicate one or the other. Figure 9-7 shows the approximate radiation pattern of a longwire when viewed from above. There are four main lobes of radiation from the longwire (A, B, C, and D). There are also two or more (in some cases many) minor lobes (E and F) in the antenna pattern. The radiation angle with respect to the wire run (G–H) is a function of the number of wavelengths found along the wire. Also, the number and extent of the minor lobes is also a function of the length of the wire.



9-7 Radiation pattern of longwire antenna.

Nonresonant single-wire longwire antennas

The resonant longwire antenna is a *standing wave antenna*, because it is unterminated at the far end. A signal propagating from the feedpoint, toward the open end, will be reflected back toward the source when it hits the open end. The interference between the forward and reflected waves sets up stationary standing current and voltage waves along the wire.

A *nonresonant longwire* is terminated at the far end in a resistance equal to its characteristic impedance. Thus, the incident waves are absorbed by the resistor, rather than being reflected. Such an antenna is called a *traveling wave antenna*. Figure 9-8 shows a terminated longwire antenna. The transmitter end is like the feed system for other longwire antennas, but the far end is grounded through a terminating resistor R_1 that has a resistance R equal to the characteristic impedance Z_o of the antenna (i.e., $R = Z_o$). When the wire is 20 to 30 ft above the ground, Z_o is about 500 to 600 Ω.

The radiation pattern for the terminated longwire is a unidirectional version of the multilobed pattern found on the unterminated longwires. The angles of the lobes vary with frequency, even though the pattern remains unidirectional. The directivity of the antenna is partially specified by the angles of the main lobes. It is interesting to note that gain rises almost linearly with $n\lambda$, while the directivity function changes rapidly at shorter lengths (above three or four wavelengths the rate of change diminishes considerably). Thus, when an antenna is cut for a certain low frequency, it will work at higher frequencies, but the directivity characteristic will be different at each end of the spectrum of interest.

A two-wavelength (2λ) pattern is shown in Fig. 9-7. There are four major lobes positioned at angles of ±36° from the longwire. There are also four minor lobes—the strongest of which is –5 dB down from the major lobes—at angles of ±75° from the longwire. Between all of the lobes, there are sharp nulls in which little reception is possible. As the wire length is made longer, the angle of the main lobes pulls in tighter (i.e., toward the wire). As the lobes pull in closer to the wire, the number of minor lobes increases. At 5λ, there are still four main lobes, but they are at angles of ±22° from the wire. Also, the number of minor lobes increases to 16. The minor lobes are located at ±47°, ±62°, ±72°, and ±83° with respect to the wire. The minor lobes tend to be –5 to –10 dB below the major lobes. When the longwire gets very



9-8 Longwire (greater than 2λ) antenna is terminated in a resistance (typically 400 to 800 Ω). Radials under the resistor improve the grounding of the antenna.

much longer than 5λ, the four main lobes begin to converge along the length of the wire, and the antenna becomes bidirectional. This effect occurs at physical lengths greater than about 20λ.

In general, the following rules apply to longwire antennas:

- On each side of the antenna, there is at least one lobe, minor or major, for each half-wavelength of the wire element. For the overall element, there is one lobe for every quarter-wavelength.
- If there are an even number of lobes on either side of the antenna wire, then half of the total number of lobes are tilted backward, and half are tilted forward; symmetry is maintained.
- If there are an odd number of lobes on either side of the wire, then one lobe on either side will be perpendicular to the wire, with the other lobes distributed either side of the perpendicular lobe.

Vee beams and rhombic beams

Longwire antennas can be combined in several ways to increase gain and sharpen directivity. Two of the most popular of these are the *vee beam* and the *rhombic* antennas. Both forms can be made in either resonant (unterminated) or nonresonant (terminated) versions.

Vee beams The *vee beam* (Fig. 9-9A) consists of two equal-length longwire elements (wire 1 and wire 2), fed 180° out of phase with each other, and spaced to produce an acute angle between them. The 180° phase difference is inherent in connecting the two wires of the vee to opposite conductors of the same parallel conductor feedline.



9-9A Radiation pattern of vee beam antenna consists of the algebraic sum of the two longwire patterns that make up the antenna.

The unterminated vee beam (Fig. 9-9A) has a bidirectional pattern that is created by summing together the patterns of the two individual wires. Proper alignment of the main lobes of the two wires requires an included angle, between the wires, of twice the radiation angle of each wire. If the radiation angle of the wire is β, then the appropriate included angle is 2β. To raise the pattern a few degrees, the 2β angle should be slightly less than these values. It is common practice to design a vee beam for a low frequency (e.g., 75-/80- or 40-m bands), and then to use it also on higher frequencies that are harmonics of the minimum design frequency. A typical vee beam works well over a very wide frequency range *only* if the included angle is adjusted to a reasonable compromise. It is common practice to use an included angle that is between 35° and 90°, depending on how many harmonic bands are required.

Vee beam patterns are based on an antenna height that is greater than a half-wavelength from the ground. At low frequencies, such heights will not be practical, and you must expect a certain distortion of the pattern because of ground reflection effects.

Gain on a vee beam antenna is about 3 dB higher than the gain of the single-wire longwire antenna of the same size, and it is considerably higher than the gain of a dipole (see Fig. 9-9B). At three wavelengths, for example, the gain is 7 dB over a dipole. In addition, there may be some extra gain because of mutual impedance effects—which can be about 1 dB at 5λ and 2 dB at 8λ.

Nonresonant vee beams Like the single-wire longwire antennas, the vee beam can be made nonresonant by terminating each wire in a resistance that is equal to the antenna's characteristic impedance (Fig. 9-10). Although the regular vee is a standing wave antenna, the terminated version is a traveling wave antenna and is thus unidirectional. Traveling wave antennas achieve unidirectionality because the terminating resistor absorbs the incident wave after it has propagated to the end of the wire. In a standing-wave antenna, that energy is reflected backwards toward the source, so it can radiate oppositely from the incident wave.

Rhombic beams The *rhombic beam antenna*, also called the *double vee*, consists of two vee beams positioned end-to-end with the tips connected. The unidirectional, nonresonant (terminated) rhombic is shown in Fig. 9-11. The unterminated resonant form gives approximately the same gain and directivity as a vee beam of the same size. The nonresonant rhombic has a gain of about 3 dB over a vee beam of the same size (see Fig. 9-9 again).

Two angles are present on the rhombic antenna. One-half of the included angle of the two legs of one wire is the *tilt angle* (ϕ), while the angle between the two wires is the *apex angle* (θ). A common rhombic design uses a tilt angle of 70°, a length of 6λ for each leg (two legs per side), and a height above the ground of 1.1λ.



9-9B Gain versus length of vee beam and rhombic beam antennas.



9-10 Nonresonant vee beam antenna.

The termination resistance for the nonresonant rhombic is 600 to 800 **Ω**, and must be noninductive. For transmitting rhombics, the resistor should be capable of dissipating at least one-third of the average power of the transmitter. For receive-only rhombics, the termination resistor can be a 2-W carbon composition or metal-film type. Such an antenna works nicely over an octave (2:1) frequency range.

Beverage or "wave" antennas

The *Beverage* or *wave antenna* is considered by many people to be the best receive antenna available for very low frequency (VLF), AM broadcast band (BCB), medium



9-11 Terminated rhombic antenna.

wave (MW), or tropical band (low HF region) DXing. The Beverage was used by RCA at its Riverhead, Long Island (NY) station in 1922, and a technical description by Dr. H. H. Beverage (for whom it is named) appeared in *QST* magazine for November 1922, in an article titled “The Wave Antenna for 200-Meter Reception.” In 1984, an edited and updated version of the 1922 article appeared in the same magazine. In 1921, Paul Godley, under sponsorship of the American Radio Relay League, journeyed to Scotland to erect a receiving station at Androssan. His mission was to listen for amateur radio signals from North America. As a result of politicking in the post–World War I era, hams were consigned to the supposedly useless shortwave ($\lambda < 200$ m), and it was not clear that reliable international communications were possible. Godley went to Scotland to see if that could happen; he reportedly used a wave antenna for the task (today, called the *Beverage*).

The Beverage antenna is a longwire of special design, more than one wavelength (1λ) long (Fig. 9-12), although some authorities maintain that $>0.5\lambda$ is minimally sufficient. The Beverage provides good directivity and good gain, but is not very efficient.

As a result, it is preferred for receiving, and is less useful for transmitting. This is an example of how different attributes of various antennas make the Law of Reciprocity an unreliable sole guide to antenna selection. Unlike the regular longwire, which is of a different design, the Beverage is intended to be mounted close to the earth's surface (typically $< 0.1\lambda$); heights of 8 to 10 feet is the usual prescription.

Figure 9-12 shows the basic single-wire Beverage antenna. It consists of a single conductor (no.16 to no.8 wire, with no.14 being most common) erected about 8 to 10 ft above ground. Some Beverages are unterminated (and bidirectional), but most of them are terminated at the far end in a resistance R equal to the antenna's characteristic impedance Z_o. The receiver end is also terminated in its characteristic impedance, but generally requires an impedance matching transformer to reduce the antenna impedance to the 50-Ω standard impedance used by most modern transmitters.

The Beverage works best in the low-frequency bands (VLF through MW), although at least some results are reportedly relatively easy to obtain up to 25 m (11.5 MHz). Some questionably successful attempts have been made at making Beverage antennas work as high as the 11-m Citizens Band or the 10-m ham band (29.7 MHz).

The Beverage antenna works on vertically polarized waves arriving at low angles of incidence. These conditions are normal in the AM BCB, where nearly all transmitting antennas are vertically polarized. In addition, the ground- and sky-wave propagations found in these bands (VLF, BCB, and low HF) are relatively consistent. As the frequency increases, however, two factors become increasingly dominant. First, the likelihood of horizontal polarization increases because of the size of a wavelength at those frequencies. The polarization of the received signal not only changes in those bands, but does so constantly when conditions are unsettled. It is the strong dependence of the



9-12 Beverage antenna.

Beverage on relatively constant vertical polarization that makes me suspect the claims of Beverage-like performance above the 25- or even 31-m bands.

The Beverage depends on being erected over poorly conductive soil, even though the terminating resistor needs a good ground. Thus, one source claimed that sand beaches adjacent to salty marshes make the best Beverage sites (a bit of an overstatement). Figure 9-13 shows why poorly conductive soil is needed. The E-field vectors are launched from the transmitting antenna perpendicular to the earth's surface. Over perfectly conducting soil, the vertical waves would remain vertical. But over imperfectly conducting soil, the field lines tend to bend close to the point of contact with the ground. As shown in the inset of Fig. 9-13, the bending of the wave provides a horizontal component of the E-field vector, and this provides the means of generating an RF current in the conductor wire.

A debate among Beverage antenna fans regards the best length for the antenna. Some sources state that the length can be anything greater than or equal to 0.5λ, yet others say greater than or equal to1λ is the minimum size. One camp says that the length should be as long as possible, while others say it should be close to a factor called the *maximum effective length* (MEL), which is

$$\mathrm{MEL} = \frac{\lambda}{4\left(\frac{100}{K} - 1\right)} \qquad \textbf{[9.2]}$$

where

MEL is the maximum effective length, in meters
λ is the wavelength, in meters
K is the velocity factor, expressed as a percent

Misek, who may well be the leading exponent of the Beverage antenna, uses numbers like 1.6λ to 1.7λ over the 1.8- to 7.3-MHz region, and 0.53λ to 0.56λ on frequencies lower than 1.8 MHz. Doctor Beverage was once quoted as saying that the optimum length is 1λ.

Like the longwire antenna, the Beverage needs a termination resistor that is connected to a good ground. This requirement might be harder to meet on Beverage antennas because they work best over lossy ground, which doesn't make a very good ground connection. As in the longwire case, insulated or bare wires, a quarter-wavelength long, make the best radials. However, a substantial improvement in the ground is possible using just bare wires measuring 15 to 20 ft long (which is much less than λ/4), buried in the soil just below the surface (far enough to prevent erosion from bringing it to the surface). Many articles and books on Beverages show ground rods of 2 or 3 ft long, which borders on the ridiculous. Poor soil requires longer ground rods, on the order of 6 to 8 ft. Copper-clad steel makes the best rods.

In addition to the radials and ground rod, Misek also recommends using a wire connection between the ground connection at the termination resistor, and the



9-13 Performance of Beverage antenna over different values of ground conductance.

ground connection at the receiver transformer (see again Fig. 9-12). According to Misek, this wire helps to stabilize the impedance variations at higher frequencies.

Installation of the Beverage antenna is not overly critical if certain rules are followed. The antenna should be installed at a height of 6 to 10 ft off the ground, and it should be level with the ground over its entire length. If the ground is not flat enough to make a level installation possible, then try to use a height that is 6 to 10 ft above the average terrain elevation along its run. A popular installation method is to erect 16-ft 4 × 4 lumber, such that 3 to 4 ft are buried in a concrete-filled posthole. Use lumber that is treated for outdoor use (i.e., pressure-treated lumber sold for decks and porches. The wire can be fastened to the 4 × 4 posts using either ceramic standoff (“beehive”) insulators or electric fence insulators (which some people deem preferable). Try to use one contiguous length of wire for the antenna, if possible, in order to avoid soldered splices and joints.

One of the Beverage installation difficulties shared with the longwire is the need to slope down to a point where a termination resistor can be easily installed close to the ground. While the longwire can be sloped over a large portion of its length, the Beverage should be sloped downward only over the last 60 ft or so.

Steerable notch Beverage antennas

A Beverage erected with two wires—parallel to each other, at the same height, spaced about 12 in apart (Fig. 9-14), with a length that is a multiple of a half-wavelength—is capable of *null steering*. That is, the rear null in the pattern can be steered over a range of 40° to 60°. This feature allows strong, off-axis signals to be reduced in amplitude so that weaker signals in the main lobe of the pattern can be received. There are at least two varieties of the *steerable wave Beverage* (SWB).

If null steering behavior is desired, then a phase control circuit (PCC) will be required—consisting of a potentiometer, an inductance, and a variable capacitor in series with each other. Varying both the "pot" and the capacitor will steer the null. You can select the direction of reception, and the direction of the null, by using a switch to swap the receiver and the PCC between port A and port B.



9-14 Beverage antenna with a steerable null.

This page intentionally left blank

10

CHAPTER

Hidden and limited-space antennas

ONE OF THE MOST SIGNIFICANT IMPEDIMENTS TO AMATEUR RADIO OPERATORS, CB operators, and shortwave listeners is the space available for their antennas. In many thousands of other cases, the limitation is less one of space, but of regulators. More and more subdivisions are built with covenants on the deed that prohibit the buyer from installing outdoor antennas. Once limited to townhouse developments, where that breed of contemptible vermin (called the Homeowners Committee) routinely intruded on the affairs of people who mistakenly think they "own" their townhouse (ownership implies right of use, which is limited by the covenants). These onerous covenants are now routinely placed on single-family dwellings as well. In fact, it is the single most serious threat to amateur communications people in the country today. Other homeowners are no longer angered by the restriction on antennas because their television reception is now carried to them via cable systems in most parts of the country. Even where cable is not available, most users can install a moderately sized television antenna in their attic, or use rabbit ears. In other cases, the townhouse community will install a single master TV antenna and then distribute signals to each unit. The result is that the amateur radio operator, CB operator, and shortwave listener are left to fend for themselves without assistance from neighbors.

In this chapter we will examine some of the alternatives available to those readers who have either a limited space situation (such as a small city lot), or are unable to move out of a subdivision where there are stupid rules against outdoor antennas. The suggestions contained in this chapter are not universal, and indeed the author recommends that you adapt, as well as adopt, these recommendations, and come up with some of your own. Creativity within the constraints of the laws of physics governing radio antennas is encouraged.

Copyright 2001 - the McGraw-Hill Companies

Hidden antennas

A hidden antenna is one that is either completely shielded from view or disguised as something else. Alternatively, you could also include in this category antennas that are in semiopen view, but which are not too obvious (except to the trained and diligent eye). Some people have opted for "hidden" longwires made of very fine wire (no. 26 enameled wire is popular). The user will install the wire in the open, high off of the ground (as in an apartment installation), and operate without anyone knowing the difference. One chap used no. 22 wire suspended between two 16-story apartment house buildings that were 100 yards apart. He had one of the best working longwires in town until a windy day when the whole thing came down. No one was injured; but had someone been hurt, there might have been a lawsuit. Hidden antennas must be designed with an eye toward causing others no harm. It is neither ethical nor smart to place others at risk in enjoying our hobbies.

The dipole is a popular antenna with both shortwave listeners and amateur radio operators. Indeed, for the CB operator who wants to get on the air from an apartment or townhouse (or restricted single-family home), the dipole can represent a respectable alternative.

As you learned in Chap. 6, the dipole is a horizontal wire (or pipe) antenna that is a half-wavelength long and fed in the center (ideally) with 75-Ω coaxial cable. In the "townhouse" dipole, it is possible to build the antenna entirely inside the attic of the building. The length of the dipole is given approximately by

$$L_{\text{ft}} = \frac{468}{F_{\text{MHz}}} \qquad \textbf{[10.1]}$$

If you do some quick calculations you will find that antennas for the 10-, 13-, 15-, and (possibly) even 18- and 20-m bands, will fit entirely inside the typical townhouse attic. This statement is also true of the 11-m citizen's band antenna: It will fit inside the standard townhouse attic. But what about the lower frequency bands?

Figure 10-1 shows a possible solution to the use of the lower frequencies in the townhouse situation. The two quarter-wavelength arms of the dipole are ideally installed in line with each other, as was shown in the chapter on horizontal antennas. But in a sticky situation we can also install the dipole with the arms bent to accommodate the space available. In this example, only one of many possible methods for accomplishing this job is shown. Here each quarter-wavelength section is composed of two legs, *AB* and *CD*, respectively. Ideally, segments *B* and *C* are the longest dimensions. Also, if possible, make segments *A* and *D* equal lengths. Another method is to reverse the direction of one end leg, say for example *D*, and run it to the other corner of the building over the peak of the roof.

The author is almost hesitant to offer only one drawing, despite space constraints, in the fear that readers will take the offered pattern as the only authorized version, or solution. In reality, you might not be able (for a variety of reasons) to use the exact pattern shown (so ad lib a little bit).

How about performance? Will the constrained dipole of Fig. 10-1 work as well as a regular dipole installed a wavelength or two off the ground and away from objects?



10-1 Installing dipole in attic.

In a word: no. But that is not the problem being solved; getting on the air at all is the present problem. You will find that the pattern of the constrained dipole is distorted compared with that of the regular dipole. In addition, the feedpoint impedance is not going to be 73 Ω (except if by fluke), so you will be required to use an antenna tuner of some kind. You are well advised to read the chapter on antenna instruments and measurements so that you can be prepared to figure out any feed problems that crop up—as well they might.

The wire used in the constrained dipole (or other forms of attic antenna) should be mounted on TV-type screw-in standoff insulators. Almost any outlet that sells TV antennas, or installation parts, will have them. These standoff insulators are also available in many hardware stores, and department stores that sell TV antennas or "Harry and Harriet Homeowner" supplies, in addition to electronics parts suppliers. Do not simply tape the wire to the wooden underside of your roof. The reason is simple: in a poorly tuned antenna, voltages can get high enough at the ends to produce *corona* effects; arcing could be a fire hazard. Also, use insulated wire to avoid accidental contact in the event that someone is in the attic when you are operating. Be aware that the insulation might affect the propagation velocity of signals in the wire, so it will slightly alter the required length.

Another alternative for the attic antenna, and one that avoids some of the problems of corona effects, is the nonresonant loop shown in Fig. 10-2. Although specified as a top view, the loop can be installed in the configuration that best uses the space. In fact, the best performance will be bidirectional when the loop is installed vertically. In this case, a large loop (as large as can be accommodated in the space available) is installed in the attic. Again, use standoff insulators and insulated wire for the installation.

The giant loop is fed with parallel line, and is tuned with a balanced antenna tuning unit. As was true with the constrained dipole, the performance is not to be equated with the performance of more regular antennas; but, with the prospect of not being on the air at all . . . ! Once again we have a compromise antenna for a compromising situation.

Another ploy is the old “flagpole trick” shown in Fig. 10-3. Some developments allow homeowners to vent their patriotism by installing flagpoles—and flagpoles can be disguised antennas. In the most obvious case, you can install a brass or aluminum flagpole and feed it directly from an antenna tuning unit. For single-band operation, especially on the higher frequencies, you can delta-feed the “flagpole” unobtrusively, and call your flagpole a vertical antenna. But that is not always the best solution.

Figure 10-3 shows two methods for creating a flagpole antenna, and both depend on using white PVC plumbing pipe as the pole. The heavier grades of PVC pipe



10-2 Large loop antenna.

are self-supporting to heights of 16 to 20 ft, although lighter grades are not self-supporting at all (hence are not usable).

Figure 10-3A shows the use of a PVC flagpole in which a no. 12 (or no. 14) wire is hidden inside. This wire is the antenna radiator. For some frequencies, the wire will be resonant, and for others, it will surely be nonresonant. Because of this problem an antenna tuning unit is used either at the base of the antenna or inside at the transmitter.


Flag
Taut
#14 or #12 wire
hidden inside
PVC
plumbing
pipe
Tuner
Coax
to
XMTR

10-3A Flagpole antenna made from thick-walled PVC pipe.

If the wire is too long for resonance (as might happen in the higher bands), then place a capacitor in series with the wire. Various settings may be required, so use a multisection transmitting variable that has a total capacitance selectable to more than 1000 pF. Alternatively, use a vacuum variable capacitor of the same range.

In cases where the antenna is too short for resonance, as will occur in the lower bands, insert an inductance in series with the line to “lengthen” it. Another alternative is to use an L-section tuner at the feedpoint.

A good compromise situation is the use of a 16-ft length of “flagpole” pipe with a 16-foot wire embedded inside. The 16-foot wire is resonant at 20 m, so it will perform like a vertical antenna at those frequencies. The tuner will then accommodate frequencies above and below 20 m.

Another alternative is the version shown in Fig. 10-3B. In this case the wire radiator is replaced with a section of aluminum tubing. A wooden or plastic insert is fashioned with a drill and file to support the aluminum tubing inside the PVC tubing. One way to make the support is to use a core bit in an electric drill to cut out a disk that fits snugly inside the PVC tubing. Rat out the center hole, left by the core bit pilot, to the outside diameter of the aluminum tubing. The support can be held in place with screws from the outside, or simply glued in place.

The problem of operating with a hidden antenna is a serious challenge. But with some of these guidelines and a little creativity, you can get on the air and enjoy your amateur radio hobby.

Limited-space antennas

Many people live in situations where it is permissible to install an outdoor antenna, but it is not practical to install a full-size antenna. I once lived in a house that was 16 ft wide and 37 ft long, on a 33 × 100-ft lot. Very few full-sized antennas could be installed on that lot because of the space constraints. Beam antennas were out because county laws required that the antenna not hang over the property line. Although vertical antennas were possible, there was a period of time when I used other antennas that were easier to install. In this chapter, you will examine some of the options open to those with limited space for amateur radio, CB, or SWL antennas.

Once again we return the simple dipole as the basis for our discussion. In Fig. 10-4, you see several alternatives for installing an outdoor antenna in a limited space. In Fig. 10-4A, the slanted dipole (or slipole) antenna uses the standard dipole configuration, but one end is connected to the high point of the building, while the other is anchored near the ground. The coaxial cable is connected to the midpoint of the antenna in the usual manner for regular dipoles. If the end of the dipole is within reach of people on the ground, then they may get a nasty RF burn if the antenna is touched while you are operating. Take precautions to keep people and pets away from this lower end.

Another method is the vee dipole shown in Fig. 10-4B. In a regular dipole installation, the ends of the antenna are along the same axis (in other words, at an angle of 180°). In the example of Fig. 10-4B, however, the angle between the elements is less than 180°, but greater than 90°. In some cases we might want to bend the elements, rather than install them in a vee shape. Figure 10-4C shows an angled dipole with four segments. For the best performance (but not as good as that


End cap
Wooden or plastic plug
PVC plumbing pipe (sectioned view)
1/2 inch to 1 1/4 inch aluminum tubing
Feedpoint

10-3B PVC flagpole hiding an aluminum tubing vertical.

of a regular dipole), make $A = D$ and $B = C$. In all three examples, Figs. 10-4A through 10-4C, you can expect to find the length needed for resonance varies somewhat from the standard $468/F_{\text{MHz}}$ value, and that the feedpoint impedance is other than 73 **Ω**. Also, the pattern will be distorted with respect to the regular dipole. Although these antennas do not work as well as a properly installed dipole, the performance is sufficient to allow successful operation.



10-4A Sloper dipole.

Another limited-space wire antenna is the (so-called) half-slope shown in Fig. 10-4D. Although single-band versions are often seen, the example in Fig. 10-4D is a multiband version. Resonant traps separate the different band segments. This antenna operates like the vertical, but it is not omnidirectional. Also, the feedpoint impedance will be different from the regular vertical situation. If the impedance varies too much for comfort, insert an antenna tuner, such as the Transmatch, in the coaxial line between the transmitter and the antenna.

Figure 10-5 shows another antenna that's useful for limited-space situations. Although it is easily constructed from low-cost materials, the antenna is also sold by several companies under various rubrics including "cliff-dweller," "apartment house," "townhouse," or "traveler's" antennas. The antenna consists of a 4- to 16-ft section of aluminum or copper tubing. Some of the commercial antennas use a telescoping tubing that can be carried easily in luggage. As was true with the longwire, the window-sill antenna is tuned to resonance with an L-section coupler.

The L-section coupler must be tuned to produce the lowest possible VSWR, so either an RF power meter or a VSWR meter must be installed in the coaxial cable between the transmitter and the tuner. Again, a good ground (or radial system) will



10-4B Vee dipole.

greatly improve the operation of this antenna. The performance should be considerably less than that of a good longwire, but it will work DX for you even on lower frequencies. Once again it is not the best antenna made, but it will get you on the air.

Figure 10-6 shows the use of a mobile antenna for a fixed or portable location. I used this type of antenna at one QTH to good effect. Mount a mobile antenna, such as the Hustler, on the window sill, or other convenient mount (at least one amateur radio operator uses one mounted on the roof of the house). Grounding is essential for this antenna, as was also true for the longwire and window-sill antenna (Fig. 10-5). The operation of this antenna is improved by installing at least two radials per band as a counterpoise ground. My installation worked well, even though only two radials were present.

A directional *rotatable* dipole is shown in Fig. 10-7. This antenna is made from a pair of mobile antennas connected “back-to-back” on a horizontal length of 1 × 2 lumber and fed in the center with a coaxial cable. The end pieces of the mobile antenna set the resonance, and you must recognize that adjusting one requires a countervailing adjustment of the other as well.

Two examples of *helically* wound antennas are shown in Fig. 10-8. In this type of antenna, an insulating mast is wound with a half-wavelength of antenna wire. The overall length of the antenna is considerably less than a half-wavelength, except at the highest frequencies. In order to dissipate the high voltages that tend to build up at the ends of these antennas, a capacitance hat is used. These “hats” are either disks (pie tins work well) or rods of conductor about 16 to 24 in long. The version shown in Fig. 10-8A is a vertical antenna, and like other verticals, it must be installed over either a good ground or a counterpoise ground. The version shown in Fig. 10-8B is horizontally polarized.


Rope
A
B
Insulator
Center insulator
Coax
Rope
C
D
Insulator

10-4C Bent dipole.


Insulator
Rope
Band traps
Insulator
Rope
Coax
to
XMTR

10-4D Sloper trap vertical.


4- to 16-foot pipe
L
Coax
C
Wooden wedge
Window sill

10-5 Window sill antenna.


Mobile
antenna
Metal
plate
Mobile
mount
Optional
radial
Coax
Wooden support
Window sill

10-6 Use of mobile antenna as a window sill antenna.


Two mobile antennas
Coax
1×2 Wood
Pipe flange
Mounting pipe

10-7 Use of two mobile antennas as a rotatable dipole.


Short adjustable whip for tuning
4 to 20 foot PVC pipe wrapped with λ/2 of #12 or #14 wire
Coax

10-8A Helically vertical antenna.


Capacitance hats
Dowel or plastic pipe wrapped with wire
Feedpoint

10-8B Helically wound dipole antenna.

This page intentionally left blank

11
CHAPTER

Directional phased vertical antennas

THE VERTICAL ANTENNA IS A PERENNIAL FAVORITE WITH RADIO COMMUNICATIONS users. The vertical is either praised, or cursed, depending upon the luck of the owner. “DXability” is usually the criterion for judging the antenna’s quality. Some amateurs can’t get out of their backyards with a vertical, and they let everyone within earshot know that such and such a brand is no good. Yet, another person routinely works New Zealand or Australia on 15 m using exactly the same brand of vertical. The proper installation of vertical antennas is dealt with in another chapter, so, for the present, let’s look at another problem attributed to vertical antennas.

That problem is that vertical antennas are *omnidirectional* in the azimuth aspect; that is, they send out and receive equally well from all directions. Some people moan that this pattern dissipates their power, and gives them a weaker signal “out where it counts” (true). However, the main disadvantage of the omnidirectional pattern is noise (QRN and QRM). “QRN” is natural noise from thunderstorms and other sources. “QRM” is man-made noise, and can consist of other stations or the many assorted forms of electrical filth that pollute the airwaves. All forms of noise, however, have one thing in common: they are directional with respect to the station. In other words, if you could null signals coming from the direction of the noise source (or undesired station), you would be able to hear desired stations much better. A directional antenna performs this task, so let’s look at some vertically polarized directional antennas.

Although most amateurs seem to think that the effective radiated power (ERP) increase that the directional antenna gives them is the real reason to own one, the main benefit is actually on receive. Think about it for a moment. With anywhere from 100 to 1500 W available, the increase or decrease in signal strength (due to the directivity of the antenna) results in a minimal difference on the receive end, especially during good DX conditions. If we rotate the directional pattern, to null out interference, then we usually find that the change in our signal strength perceived by the other guy is small; the S meter reading of the desired station is minimally affected; but the amplitude of the interference source is greatly attenuated! The overall effect is an apparent increase

Copyright 2001 - the McGraw-Hill Companies

in the other guy's signal, even though the S meter tells a slightly different story. The improvement of signal-to-noise ratio (SNR) is tremendously improved.

Directivity and phasing

So, how does a vertical antenna owner get the benefit of directivity without the kilobuck investment that a beam or quad costs? The usual solution is to use phased verticals. AM broadcast stations, with more than one tower, are using this type of system (although for different reasons than hams). The idea is to place two or more antennas in close proximity and feed them at specific phase angles to produce a desired radiation pattern. A lot of material is available in the literature on phased vertical antenna systems, and it is far too much to be reproduced here. There are "standard patterns" dating from before World War II that are created with different spacings and different phase angles of feed current. In this chapter, we will consider only one system.

Figure 11-1 shows the patterns for a pair of quarter-wavelength vertical antennas spaced a half-wavelength (180°) apart. Without getting into complex phase shifting networks, there are basically two phasings that are easily obtained: 0° (antennas in phase) and 180° (antennas out of phase with each other).

When the two antennas (*A* and *B*) are fed in phase with equal currents (Fig. 11-1A), the radiation pattern (shown somewhat idealized here) is a bidirectional figure 8 that is directionally perpendicular to the line of centers between the two antennas; this pattern is called a *broadside* pattern. A sharp null exists along the line of centers (*A*-*B*).

When the antennas are fed out of phase with each other by 180° (Fig. 11-1B), the pattern rotates 90° (a quarter way around the compass) and now exhibits directivity along the line of the centers (*A*-*B*); this is the "end fire" pattern. The interference cancelling null is now perpendicular to line *A*-*B*.

It should be apparent that you can select your directivity by selecting the phase angle of the feed currents in the two antennas. Figure 11-2 shows the two feeding



11-1A Pattern of two radiators in-phase, spaced a half-wavelength apart.

11-1B Pattern of two radiators out of phase, spaced a half-wavelength apart.





11-2A Feeding a phased array antenna in phase.

systems usually cited for in-phase (Fig. 11-2A) and out-of-phase (Fig. 11-2B) systems. Figure 11-2A shows the coax from the transmitter coming to a coax tee connector. From the connector to the antenna feedpoints are two lengths of coax (L_1 and L_2) that are equal to each other, and identical. Given the variation between coaxial cables, I suspect that it would work better if the two cables were not merely the same length ($L_1 = L_2$), but also that they came from the same roll.

The second variation, shown in Fig. 11-2B, supposedly produces a 180° phase shift between antenna *A* and antenna *B*, when length L_3 is an electrical half-wavelength. According to a much-publicized theory, the system of Fig. 11-2B ought to



11-2B Feeding a phased array antenna out of phase.

produce the pattern of Fig. 11-1B—yet experience shows this claim is false. It seems that there are several problems with the system in Fig. 11-2B.

First, coax has a property called *velocity factor* (V_F), which is the fraction of the speed of light at which signals in the cable propagate. The V_F is a decimal fraction on the order of 0.66 to 0.90, depending upon the type of coax used. Unfortunately, the physical spacing between A and B is a real half-wavelength ($L_3 = 492/F$), but the cable length is shorter by the velocity factor [$L_3' = (V_F \times 492)/F$].

Consider an example. A 15-m phased vertical antenna system will have two 11-ft radiators, spaced 22 ft apart (approximately, depending upon exact frequency). If we use foam coax, with $V_F = 0.80$, the cable length is 0.8 × 22 ft, or 17.6 ft. In other words, despite lots of publicity, the cable won't fit between the towers!

Second, the patterns shown in Fig. 11-1 are dependent upon one condition: the *antenna currents are equal*. If both of them are the same impedance, and are fed from the same transmitter, then it is reasonable to assume that the currents are equal—right? No, wrong! What about coax loss? Because of normal coax loss, which increases at higher frequencies, the power available to antenna B in Fig. 11-1B is less than the power available to antenna A. Thus, the pattern will be somewhat distorted, because the current produced in B is less than the current in A, when they should be equal.

The first problem is sometimes fixed by using unequal lengths for cables L_1 and L_2 (Fig. 11-2A), and using it for the out-of-phase case. For example, if we make L_1 one-quarter wavelength and L_2 three-quarter wavelength (Fig. 11-2C), antenna A is fed with a 90° phase lag (relative to the tee connector signal), while antenna B is fed with a 270° phase shift. The result is still a 180° phase difference. Unfortunately, we



11-2C Corrected feed for a phased array antenna.

have not solved the current level problem, and may have actually made it worse by adding still more lossy cable to the system.

There is still another problem that is generic to the whole class of phased verticals. Once installed, the pattern is fixed. This problem doesn't bother most point-to-point commercial stations, or broadcasters, because they tend to transmit in only one direction. But amateurs are likely to need a rotatable pattern. Neither the antennas in Fig. 11-1A nor that in Fig. 11-1B is rotatable without a lot of effort—like changing the coax feeds, or physically digging up the verticals and repositioning them.

Fortunately, there is a single solution to all three problems. Figure 11-3 shows a two-port phasing transformer made from a toroidal balun kit. Use the kind of kit that makes a 1:1 balun transformer. Although we are not making a balun, we will need enough wire to make three windings, and that is the normal case for 1:1 baluns. Amidon Associates and others make toroidal balun kits.

Wind the three coils in trifilar style, according to the kit instructions. The dots in Fig. 11-3 show the "sense" of the coils, and they are important for correct phasing; call one end the "dot end" and the other end the "plain end" to keep them separate. If the dot end of the first coil is connected to J_3 (and the transmitter), then connect the dot end of the second coil to the 0° output (J_1, which goes to antenna A). The third coil is connected to a DPDT RF relay or switch. In the position shown, S_1 causes the antennas to be 180° out of phase. In the other position, the "sense" of the third coil is reversed, so the antennas are in phase.

Another phasing method is shown in Fig. 11-4. In this scheme, two convenient, but equal, lengths of coaxial cable (L_1 and L_2) are used to carry RF power to the antennas. One segment (L_1) is fed directly from the transmitter's coaxial cable (L_3), while the other is fed from a phasing switch. The phasing switch is used to either by-



11-3A Phasing transformer circuit.

pass or insert a phase-shifting length of coaxial cable (L_4). For 180° phasing use the following equation to find the length (L_4):

$$L = \frac{492\ V_F}{F_{\mathrm{MHz}}} \text{ ft} \qquad \textbf{[11.1]}$$

where

L is the length of L_4, in feet
V_F is the velocity factor (a decimal fraction)
F_{MHz} is the operating frequency, in megahertz

Some people use a series of switches to select varying amounts of phasing shift from 45° to 270°. Such a switch allows them to select any number of other patterns for special situations.

360° directional array

The phased vertical antenna concept can be used to provide round-the-compass control of the antenna pattern. Figure 11-5A shows how three quarter-wavelength verticals (arranged in a triangle that is a half-wavelength on each side) can be used to provide either end-fire or broadside patterns from any pair (*A-B*, *A-C*, or *B-C*). Any given antenna (*A*, *B*, or *C*) will be grounded, fed at 0°, or fed with 180°. The table in Fig. 11-5B shows the relative phasing for each direction that was labelled in Fig. 11-5A. Either manual phase changing or switch-operated phase changing can be used, although the latter is preferred for convenience. Some international showcase broadcasters use antenna arrays formed into two or more concentric circles of vertical elements, with one element at the center. Selection of elements and phasing determines directivity and gain.


A
B
λ/4
λ/4
λ/2
Length = $D_1 = D_2$
D_1
D_2
J_1
J_2
J_3
Phasing transformer

11-3B Connection to antennas.



11-4 Phase-shifting antenna circuit.


NW2
N
NE1
NW1
NE2
C
W
A
B
E
SE1
SW2
SE2
S
SW1

11-5A Three-element phased array.

Direction	Ant A	Ant B	Ant C
N-S	0°	0°	GND
NE1-SW1	0°	GND	180°
NE2-SW2	GND	0°	0°
E-W	0°	180°	GND
SE1-NW1	0°	GND	0°
SE2-NW2	GND	0°	180°

11-5B Table of feed phasing for the three-element array. Ant = antenna. GND = ground

12
CHAPTER

Directional beam antennas

THE DIRECTIONAL BEAM ANTENNA DOES SEVERAL JOBS. FIRST, IT PROVIDES AN APPARENT increase in radiated power, because it focuses available transmitter power into a single (or at worst limited) direction. For this reason, a bidirectional dipole has a gain of approximately 2 dB over an isotropic radiator. Add one or more additional elements, and the focusing becomes nearly unidirectional, which increases the *effective radiated power* (ERP) even more. Second, the beam increases the received signal available at the inputs of the receiver. Antennas are generally reciprocal, so they will work for receiving as they do for transmitting. Finally, the directivity of the beam antenna allows the operator to null interfering stations. In fact, it is the last attribute of the beam that is most useful on today's crowded bands. All in all, if your funds are too little to provide both increased RF power and a good antenna system, then spend what is available on the antenna—not on the power.

In this chapter we will focus on directional antennas that can be built relatively easily. It is assumed that most readers who want a triband multielement Yagi will prefer to buy a commercial product, rather than build a homebrew model. The material herein concentrates on homebrew projects that are within the reach and capabilities of most readers. The first of these is not a beam antenna at all, but rather a *rotatable dipole.*

Rotatable dipole

The *dipole* is a bidirectional antenna with a figure-8 pattern (when viewed from above). The dipole is a half-wavelength and is usually installed horizontally, although vertical half-wavelength dipoles are known. Although the length of the dipole is too great for rotatability at the lower bands, it is within reason for the higher band. For example, the size of the halfwave dipole is approximately 16 ft on 10 m and 22 ft on 15 m. Even the 33-ft length on 20 m is not unreasonable for amateur constructors. The length of the dipole is found from

Copyright 2001 - the McGraw-Hill Companies

$$L = \frac{468}{F_{\mathrm{MHz}}}\ \mathrm{ft} \qquad \textbf{[12.1]}$$

This length is approximate because of end effects and other phenomena, so some "cut and try" is required.

Example 12-1 Find the length of a dipole antenna for a frequency of 24.930 MHz in the 12-m amateur radio band.

Solution:

:

$$L = \frac{468}{F_{\mathrm{MHz}}}\ \mathrm{ft}$$

$$= \frac{468}{24.930\ \mathrm{MHz}} = 18.77\ \mathrm{ft}$$

The half-wave dipole is fed in the center by coaxial cable. Each element of the dipole is one-half of the overall length (or, in the example given, about 9.4 ft).

Figure 12-1 shows a rotatable dipole that can be designed for use on 15, 12, and 10 m. The radiator elements are made from 10-ft lengths of $^3\!/_4$-in aluminum tubing. The tubing is mounted on "beehive" standoff insulators, which in turn are mounted on a 4-ft length of 2 × 2 lumber. The lumber should be varnished against weathering. In a real pinch, the elements can be mounted directly to the lumber without the insulators, but this is not the recommended practice.

The mast is attached to the 2 × 2 lumber through any of several means. The preferred method is the use of a 1-in pipe flange. These devices are available at hardware stores under the names *floor flange* and *right-angle flange.*

The 10-ft lengths of pipe are the standard lengths available in hardware stores, so it was selected as being closest to the required 22 ft for 15 m. A 0.14-µH loading coil is used at the center, between the elements, in order to make up for the short length. The dimensions of the coil are 4 to 5 turns, 0.5-in diameter, 4-in length. For low power levels, the coil can be made of no. 10 (or no. 12) solid wire—and, for higher levels, $^1\!/_8$-in copper tubing.

There are two basic ways to feed the antenna, and these are shown in details A and B in Fig. 12-1. The traditional method is to connect the coaxial cable (in parallel) across the inductor. This method is shown in Fig. 12-1, detail A. A second method is to link couple the coil to the line through a one- to three-turn loop (as needed for impedance matching). This is the method that would be used for a toroidal inductor.

Lower frequencies can be accommodated by changing the dimensions of the coil. The coil cannot be scaled, simply because the relative length of the antenna changes as the frequency changes. But it is possible to cut and try by adding turns to the coil, one turn at a time, and remeasuring the resonant frequency. Adding inductance to the coil will make the antenna usable on 17 m and 20 m, as well as on 15 m.

Another method for building a rotatable dipole for lower frequencies is to increase the element lengths. On 17 m, the overall length is approximately 27.4 ft, so each element length is 13.7 ft long. This length can be achieved by either of two methods. First, adjacent sizes of aluminum tubing are designed so that the smaller will be a slip-fit inside of the larger. What constitutes "adjacent sizes" depends on the wall thickness, but for one common brand, the $^7\!/_8$-in is adjacent to the $^3\!/_4$-in size. You



12-1 Rotatable dipole antenna. Inset A shows conventional feed; inset B shows transformer feed.

can use two smaller lengths to make the larger lengths of pipe, and cut it to size. This method is only available to those readers who have a commercial or industrial metals distributor nearby, because the 16-ft lengths are not generally available from hardware stores.

Bands higher than 15 m (i.e., 12 and 10 m) can be accommodated by using the 10-ft lengths of tubing, but without the inductor. The tubing is cut to the desired half-wavelength size and used directly.

Yagi beam antennas

A *Yagi* antenna is one member of a class of directional beam antennas that are popular in the HF bands. Figure 12-2 shows the pattern (viewed from above) typical of the beam antenna. The antenna is located at point P and fires signals in the direction shown by the arrow. The beamwidth of the antenna is the angle a between the points on the main lobe that are −3 dB down from the center point C.



12-2 Pattern of beam antenna.

A perfect beam antenna will have only the main lobe, but that situation occurs only in dreams. All real antennas have both sidelobes and backlobes, also shown in Fig. 12-2. These lobes represent wasted power transmitted in the wrong direction during transmission and interference opportunities while receiving. The goal of the antenna designer is to increase the main lobe while decreasing the sidelobes and backlobes.

Figure 12-3 shows, schematically, the basic *Yagi-Uda* antenna (usually called simply *Yagi*). The driven element is a simple half-wavelength dipole fed in the center. There are two additional elements: *reflectors* and *directors.* These are called *parasitic elements* because they are not directly excited by RF, but rather, they receive energy radiated from the driven element and then reradiate it. The reflector is placed behind the driven element, and is typically about 4 percent longer than the driven element. The director is placed in front of the driven element (relative to the direction of propagation). The director is typically about 4 percent shorter than the driven element. Although there is no fixed rule regarding the number of either reflectors or directors, it is common practice to use a single director and a driven element for two-element beams, and a single reflector and a single director, in addition to the driven element, for three-element beams. Again, additional reflectors can be added for four- and more element beams, but standard practice calls for addition of directors instead.

The length of the elements is given by

$$L = \frac{K}{F_{\mathrm{MHz}}}\ \mathrm{ft} \qquad \textbf{[12.2]}$$

where

L is the length, in feet
F_{MHz} is the frequency, in megahertz
K is a constant

The spacing of the elements is typically from 0.15 to 0.308 wavelengths, although 0.2 and 0.25 are the most common values.



12-3 Basic Yagi-Uda antenna.

Example Calculate the approximate element lengths for a three-element 15-m beam designed to operate on a frequency of 21.39 MHz.

Solution:

1. Driven element ($K = 478$):

$$\begin{aligned} L &= \frac{K}{F_{\text{MHz}}}\ \text{ft} \\ &= \frac{478}{21.39\ \text{MHz}}\ \text{ft} \\ &= 22.34\ \text{ft} \end{aligned}$$

2. Reflector ($K = 492$):

$$\begin{aligned} L &= \frac{K}{F_{\text{MHz}}}\ \text{ft} \\ &= \frac{492}{21.39\ \text{MHz}}\ \text{ft} \\ &= 23\ \text{ft} \end{aligned}$$

3. Director ($K = 461.5$):

$$\begin{aligned} L &= \frac{K}{F_{\text{MHz}}}\ \text{ft} \\ &= \frac{461.5}{21.39\ \text{MHz}}\ \text{ft} \\ &= 21.58\ \text{ft} \end{aligned}$$

4. Element Spacing (K = 142):

$$\begin{aligned} L &= \frac{K}{F_{\text{MHz}}}\ \text{ft} \\ &= \frac{142}{21.39\ \text{MHz}}\ \text{ft} \\ &= 6.64\ \text{ft} \end{aligned}$$

The elements of a rotatable beam antenna can be built in a manner similar to the rotatable dipole described earlier. In the beam antenna, however, a boom is needed between the elements to support them. The boom can be made of metal or wood. In the case of a metal boom, the driven element must be insulated from the boom, even though the parasitic elements can be mounted directly to it. In general, it is usually better to use wood as a matter of convenience. Metal boom antennas can be obtained from commercial sources. The wood boom is easy to build and maintain, even though a little less durable than a metal boom.

The feedpoint impedance of a dipole is on the order of 72 Ω in free space, although the actual impedance will vary above and below that figure for antennas close to the earth's surface. In addition, adding parasitic elements reduces the impedance even more. The feedpoint impedance of the antenna is too low to be directly fed with coaxial cable, so some means of impedance matching is needed. Some people feed the antenna through an impedance matching balun transformer. Figure 12-4 shows the *gamma match* system. The driven element of the Yagi is not broken in the center, as in the case of the simple dipole. The outer conductor, or shield, of the coaxial cable is connected to the center point of the driven element. The center conductor is connected to the gamma match element. The dimensions of the gamma match are

1. Gamma match length: $L/10$
2. Gamma match director: $D/3$
3. Spacing of gamma match from driven element: $L/70$

where

L is the length of the driven element
D is the diameter of the driven element

The capacitor in series with the center conductor of the coaxial cable has a value of approximately 8 pF per meter of wavelength at the lowest frequency in the band of operation, or approximately,

$$C = \frac{2400}{F_{\mathrm{MHz}}}\ \mathrm{pF} \qquad \textbf{[12.3]}$$

The capacitor must be a high-voltage transmitting variable type. In general, the gamma match capacitors are either air or vacuum variables.

There are three aspects to the adjustment of the Yagi antenna. Resonance is determined by the length of the element. The length is increased or decreased in order to find the resonant point. This point can be determined by the use of a noise bridge, VSWR meter or other means. The capacitor, and the shorting bar/clamp, are adjusted to match the impedance of the antenna to the transmission line impedance. For the dimensions shown, the coaxial cable should be 52 Ω (RG-58 or RG-8).

It is not necessary to use tubing or pipes for the antenna elements in order to obtain the benefits of the Yagi beam antenna. An example of a wire beam is shown in Fig. 12-5. The wire beam is made as if it were two half-wavelength dipoles, installed parallel to and about 0.2 to 0.25 wavelengths apart from each other. Although multielement wire beams are possible, the two-element version is the most common. Perhaps the most frequent


L
D
Center
Shorting clamp
Insulator
L/70
D/3
C
$L = \frac{K}{F_{\mathrm{MHz}}}$ Feet
L/10
$C = \frac{8\ \mathrm{pF}}{\mathrm{Meter}(\lambda)}$

12-4 Gamma feed provides impedance matching.

use of the wire beam antenna is on the lower bands (e.g., 40 m and 75/80 m) where rotatable beams are more difficult to build.

20-m ZL-special beam

The antenna shown in Fig. 12-6 is a close relative of the Yagi beam. It consists of a pair of folded dipoles, mounted approximately 0.12 wavelengths apart. The elements are 30.5 ft in length, and the spacing is 7.1 ft. The elements can be built from aluminum tubing if the antenna is to be rotatable. Alternatively, for a fixed antenna, the elements can be made of 300-Ω television-type twin lead. If the tubing type of construction is selected, then make the size of the tubing, and its spacing, sufficient for 300-Ω parallel transmission lines, according to

$$Z_o = 276 \log \frac{2S}{d} \qquad [12.4]$$


Insulators
Rope
0.96L
Insulators
Rope
Insulators
Rope
Driven element
Insulators
Rope
L
(Top view)

12-5 Wire beam useful for low frequencies.


30.5'
BALUN
2:1
Coax
7.1"
7.2' of
300-Ω
cable
Connections
twisted

12-6 ZL-special beam antenna.

where

Z_o is the impedance of the line (300 Ω)
S is the center-to-center spacing of the parallel conductors on the elements
d is the diameter of the conductors

The two half-wavelength elements of the ZL-special are fed 135° out of phase with each other. The feedline is connected to one of the dipoles directly; and then to the other through a length of 300-Ω twin lead that has an electrical length of about 45° (λ/8).

The feedpoint impedance is on the order of 100 to 150 Ω, so it will make a good match to either 52- or 75-Ω coaxial cable if a 2:1 impedance matching transformer is used.

Cubical quad beam antenna

The *cubical quad* antenna is a one-wavelength square wire loop. It was designed in the mid-1940s at radio station HCJB in Quito, Ecuador. HCJB is a Protestant missionary shortwave radio station with worldwide coverage. The location of the station is at a high altitude. This fact makes the Yagi antenna less useful than it is at lower altitudes. According to the story, HCJB originally used Yagi antennas. These antennas are fed in the center at a current loop, so the ends are high-voltage loops. In the thin air of Quito, the high voltage at the ends caused corona arcing, and that arcing periodically destroyed the tips of the Yagi elements. Station engineer Clarence Moore designed the cubical quad antenna (Fig. 12-7) to solve this problem. Because it is a full-wavelength antenna, each side being a quarter wavelength, and fed at a current loop in the center of one side, the voltage loops occur in the middle of the adjacent sides—and that reduces or eliminates the arcing. The elements can be fed in the center of a horizontal side (Figs. 12-7A and 12-8A), in the center of a vertical side (Fig. 12-8B), or at the corner (Fig. 12-8C).

The antenna shown in Fig. 12-7A is actually a quad loop rather than a cubical quad. Two or more quad loops, only one of which needs to be fed by the coax, are used to make a cubical quad antenna. If only this one element is used, then the antenna will have a figure-8 azimuthal radiation pattern (similar to a dipole). The quad loop antenna is preferred by many people over a dipole for two reasons. First, the quad loop has a smaller “footprint” because it is only a quarter-wavelength on each side (A in Fig. 12-7A). Second, the loop form makes it somewhat less susceptible to local electromagnetic interference (EMI).

The quad loop antenna (and the elements of a cubical quad beam) is mounted to spreaders connected to a square gusset plate. At one time, carpets were wrapped around bamboo stalks, and those could be used for quad antennas. Those days are gone, however, and today it is necessary to buy fiberglass quad spreaders. A number of kits are advertised in ham radio magazines.

The details for the gusset plate are shown in Fig. 12-7B. The gusset plate is made of a strong insulating material such as fiberglass or $\frac{3}{4}$-in marine-grade plywood. It is mounted to a support mast using two or three large U bolts (stainless steel to prevent corrosion). The spreaders are mounted to the gusset plate using somewhat smaller U bolts (again, use stainless steel U bolts to prevent corrosion damage).


MOUNTING
MAST
GUSSET
PLATE
RADIATOR
ELEMENT
A
A
SPREADERS
INSULATOR

12-7A Quad loop antenna.


SPREADER
MOUNTING
MAST
SPREADER
SMALL
U-BOLTS
GUSSET
PLATE
LARGE
U-BOLTS
SPREADER
SPREADER

12-7B Quad loop antenna.



12-8 Feed options for the quad.

There is a running controversy regarding how the antenna compares with other beam antennas, particularly the Yagi. Some experts claim that the cubical quad has a gain of about 1.5 to 2 dB higher than a Yagi (with a comparable boom length between the two elements). In addition, some experts claim that the quad has a lower angle of radiation. Most experts agree that the quad seems to work better at low heights above the earth's surface, but the difference disappears at heights greater than a half-wavelength.

The quad can be used as either a single-element antenna or in the form of a beam. Figure 12-9 shows a pair of elements spaced 0.13 to 0.22 wavelengths apart. One element is the driven element, and it is connected to the coaxial-cable feedline directly. The other element is a reflector, so it is a bit longer than the driven element. A tuning stub is used to adjust the reflector loop to resonance.

Because the wire is arranged into a square loop, one wavelength long, the actual length varies from the naturally resonant length by about 3 percent. The driven



$0.13\lambda \leq S \leq 0.22\lambda$

12-9 Quad beam antenna.

element is about 3 percent longer than the natural resonant point. The overall lengths of the wire elements are

1. Driven element: $$L = \frac{1005}{F_{\text{MHz}}} \text{ ft} \qquad \textbf{[12.5]}$$

2. Reflector: $$L = \frac{1030}{F_{\text{MHz}}} \text{ ft} \qquad \textbf{[12.6]}$$

3. Director: $$L = \frac{975}{F_{\text{MHz}}} \text{ ft} \qquad \textbf{[12.7]}$$

One method for the construction of the quad beam antenna is shown in Fig. 12-10. This particular scheme uses a 12 × 12-in wooden plate at the center, bamboo (or fiberglass) spreaders, and a wooden (or metal) boom. The construction must be heavy-duty in order to survive wind loads. For this reason, it is probably a better solution to buy a quad kit consisting of the spreaders and the center structural element.

More than one band can be installed on a single set of spreaders. The size of the spreaders is set by the lowest band of operation, so higher frequency bands can be accommodated with shorter loops on the same set of spreaders.

This quad antenna is an example of a multielement, large loop antenna. Additional information on large loops, but not in a beam antenna array, is found in Chap. 14.

Inverted bobtail curtain (Thorne array)

The *bobtail curtain* antenna is a fixed array consisting of three individual quarter-wavelength elements spaced a half-wavelength apart, and fed from the top by a



12-10 Quad construction.

shorting element or wire. The *inverted bobtail curtain,* or *Thorne array,* consists of an *upside down* bobtail curtain as shown in Fig. 12-11. The radiator elements are each a quarter-wavelength long. Their lengths are found from

$$L = \frac{246}{F_{\text{MHz}}} \text{ ft} \qquad \textbf{[12.8]}$$

The lengths of spacing between the elements are exactly twice above the value, or

$$L = \frac{492}{F_{\text{MHz}}} \text{ ft} \qquad \textbf{[12.9]}$$

The antenna is fed at the base of the center element, through a parallel resonant tuner. The capacitor is a 100- to 200-pF transmitting variable, while the inductor is set to resonate at the band desired (with the capacitor at half to three-quarters full capacitance). A loop or link coupling scheme connects the tuner to the transmission line.

An alternate feed method (Fig. 12-12) worked out by the late J. H. Thorne (K4NFU/5), feeds the end elements from the shield of the coaxial cable, and the center element of the array is fed from the center conductor of the coaxial cable. A coaxial impedance-matching section is used between the cable transmitter and the antenna feedpoint.



12-11 Inverted bobtail curtain.



$\frac{\lambda}{2}$
$\frac{\lambda}{2}$
$\frac{\lambda}{4}$
Matching section (75 Ω)
Coax to XTMR (52 Ω)

12-12 Thorne array.

This page intentionally left blank

13
CHAPTER

Antennas for shortwave reception

ALTHOUGH MOST OF THIS BOOK ADDRESSES ANTENNAS FOR TRANSMITTING, THERE IS A certain body of material that pertains purely to receiving antennas. This material also needs to be addressed, and that is the function of this chapter. There are two readers in mind for this chapter. First, and foremost, is the shortwave listener (SWL). Second, however, is the amateur radio operator who wants to either use a separate receiving antenna on the main station receiver or use an ancillary receiver (common among DXers).

The law of reciprocity

Antennas possess a property called *reciprocity.* That is a fancy way of saying that an antenna works on reception the same way it does for transmission. Although articles occasionally appear in the literature claiming an HF or VHF design which violates the *law of reciprocity,* to date all have depended on either variable definitions, false premises, or faulty measurements. There is even a school of thought that falsely argues against antenna reciprocity based on an ionospheric anomaly in which propagation depends on the *direction* traveled (see the end of Chap. 2). The bottom line of reciprocity, for the SWL, is that every antenna described in this book can be also used with equal results on receive. For example, a half-wavelength dipole works equally well as a receiver antenna, or as a transmitter antenna.

Which properties are important?

Selecting a receiver antenna is a function of several factors. Assuming that you want more than a simple longwire (which we will deal with shortly), you will want to home in on the properties desired for your particular monitoring application. Is the antenna to be fixed or rotatable? Do you want omnidirectional or directional reception? In which plane? What about gain?

Copyright 2001 - the McGraw-Hill Companies

What about gain? What is gain, for that matter? The concept of antenna gain derives from the fact that directional antennas focus energy. Two kinds of gain figure are often quoted: gain referenced to a dipole antenna on the same frequency, and gain relative to a theoretical construct called an *isotropic radiator.* In the isotropic case, the reference radiator to which the antenna is compared is a spherical point source that radiates equally well in all directions. The dipole exhibits a figure-8 radiation and reception pattern.

The gain of an antenna is merely the ratio (usually expressed in decibels) of the power radiated in a given direction by two antennas (i.e., the reference antenna and the test antenna). If an antenna gain is listed as "8-dB gain over isotropic," this means that, in the direction specified, the power radiated is 8 dB higher than the same total power applied to an isotropic radiator.

So, of what use is antenna gain? Two answers immediately present themselves. First, by accumulating more signal, the antenna essentially makes your receiver more sensitive. Note that the gain of the antenna does not create a higher powered signal, it merely increases the apparent signal power by focusing energy from a given direction. And, note well that *gain* implies *directivity.* Any antenna that claims to provide gain, but that is truly omnidirectional in all planes, is a fraud. The fundamental assumption is that *gain implies directivity.*

The concept of directivity (hence also of gain) is often taken to mean *horizontal directivity,* which is the case of a dipole antenna. But all forms of antenna radiate in three-dimensional space. Azimuth angle of radiation, and elevation angle of radiation, are both important. Certain 2-m vertical antennas are listed as "gain antennas," yet the pattern in the horizontal direction is 360°—implying omnidirectional behavior. In the vertical plane, however, lost energy is compressed into a smaller range of elevation angles, so gain occurs by refocusing energy that would have been radiated at a higher than useful angle.

The second application of directivity is in suppressing interfering signals. On the regular AM and FM broadcast bands, channelization permits receiver selectivity to overcome adjacent channel interference in most cases. But in the HF amateur radio and international broadcast bands, channelization is either nonexistent, poorly defined, or ignored altogether. In these cases, interfering "adjacent" channel signals can wipe out a weaker, desired station. Similarly, with cochannel interference (i.e., when both stations are on the same frequency), two or more signals compete in a "dog fight" that neither will ever totally win. Consider Fig. 13-1A. Assume that two 9540-kHz signals, S_1 and S_2, arrive at the same omnidirectional vertical antenna. Either both signals will be heard, or the stronger signal will drown out the weaker signal.

Now, consider Fig. 13-1B. Here, a dipole is used as the receiving antenna, so a little directivity is obtained. The main lobes of the dipole are wide enough to provide decent reception of signal S_1, even though the antenna is positioned such that S_1 is not along the maximum line (dotted). But the positioning shown places the interfering cochannel signal (S_2) in the null off the ends of the dipole, so it weakens it considerably. The result will be enhanced reception of S_1. In Fig. 13-1B, the idea is not to exploit the ability of the gain antenna to increase the level of S_1. Indeed, by placing the antenna as shown, we are not getting S_1 levels as high as might otherwise be



13-1A Omnidirectional antenna picks up cochannel interfering signals equally well.



13-1B Directional antenna can discriminate against unwanted signal.

possible. The idea here is to place the unwanted signal (S_2) into the "notch" in order to make it considerably weaker. Note that the notch is sharper than the peak of the main lobe. If the dipole is placed on a mast, with an antenna rotator, this ability is increased even more.

Another antenna parameter, of considerable interest, is *angle of radiation* a, which (by reciprocity) also means angle of reception. Because HF propagation over long distances is created by skip phenomena, the angle at which the signal hits the ionosphere becomes extremely important. Figure 13-2 shows two situations from the same station. Signal S_1 has a high angle of radiation (a_1), so its skip distance (D_1) is relatively short. On signal S_2, however, the angle of radiation (a_2) is low, so the skip distance (D_2) is much longer than D_1.

So which situation do you want in your antenna? The impulsive answer would be the long distance angle of radiation (a_2), but that is often wrong. The correct answer is: "It depends!" The desired angle of radiation is a function of whether you want to receive a station from point A or point B.

The angle of radiation of the antenna is fixed by its design, that is, by antenna physics. The desired angle is a function of the ionospheric properties at the time of interest, and the operating frequency. For this reason, some well-equipped radio hobbyists have several antennas, of differing properties, to enhance their listening.

Connection to the receiver

It's simply too naive to state, I suppose, but let's do it anyway: An antenna must be properly connected to the receiver before it can be effective. If your antenna uses coaxial cable, and the receiver accepts coax, then no discussion is needed: Attach



13-2 Skip phenomena dependence on angle of radiation.

the proper coax connector and plug in. But in other cases, non-coaxial-cable antennas are used.

There are two major forms of antenna input connector used on shortwave receivers. One form uses two (or three) screws intended for either wrapped wire leads or spade lugs, while the other is one or more varieties of coaxial connector. This section covers how each type is connected to a single-wire antenna lead-in.

Consider first the screw-type connector (Fig. 13-3A). Depending upon the design, there will be either two or three screws. If only two screws are found, then one is for the antenna wire and the other is for the ground wire. These screws will be marked something like "A/G" or "ANT/GND," or with the schematic symbols for antenna and ground.

Three-screw designs are intended to accommodate balanced transmission lines such as twin lead, or parallel ladder line. Shortwave listeners can sometimes use ordinary ac line cord (called *zipcord*) as an antenna transmission line. Zipcord has an impedance that approximates the 75-Ω impedance of a dipole. When parallel lines of any type are used, connect one lead to A1 and the other to A2. Of course, the ground terminal (G) is connected to the earth ground.

For single-lead antenna lines connect a jumper wire or bar (i.e., a short piece of bare no. 22 solid hookup wire) between A2 and G. This jumper converts the balanced input line to unbalanced. The A2/G terminal is connected to earth ground, while A1 is connected to the single-lead antenna wire.



13-3A Connection of wire antenna to balanced antenna terminals on receiver.

On receivers that use an SO-239 coaxial connector, we can use either of two techniques to connect a single-lead wire. First, we can obtain the mating PL-259 plug, and solder the antenna lead to the center conductor pin. The PL-259 connector is then screwed into the mating SO-239 chassis connector. Regardless of the type of coaxial connector, however, the mate can be used for the antenna lead wire. But for SO-239 connectors another alternative is also available. Figure 13-3B shows a “banana plug” attached to the lead wire and inserted into the receptacle of the SO-239.

DANGER!

Certain low-cost receivers, especially older vacuum-tube models, have a so-called ac/dc or transformerless internal dc power supply. On most receivers, the dc common is the chassis, which also serves as the RF signal common. But on ac/dc models the neutral wire of the ac power line serves as the dc common, and it is kept floating as a “counterpoise” ground above the chassis ground used by the RF signals. A capacitor (C_1 in Fig. 13-4) sets the chassis and counterpoise ground at 0-V RF potential, while keeping the counterpoise isolated for dc and 60 Hz ac. A danger exists if either the ac plug is installed backwards or someone plugs the socket in the wall incorrectly (often happens!). Even if C_1 is intact, *a nasty shock can be felt by touching the antenna ground* (G or GND) *terminal.* The capacitive reactance of C_1 is about 2.7 MΩ for 60-Hz ac, so at least a “bite” is going to happen. But if that capacitor is shorted, which is likely on older receivers, then the bite is considerably worse, and might even prove *fatal.* The problem, in that case, is that reversed ac line polarity will set the hot line from the ac socket on the ground lead. The least to expect is massive fireworks and a possible fire hazard; the most to expect is a fire, and your possible electrocution.

The usual advice given to owners of such radios is to make sure that C_1 is intact before using the radio. I prefer a better solution: buy, install, and use a 120:120 Vac isolation transformer to isolate your receiver from the ac power lines. Such a transformer is standard practice in repair shops, and it should also be standard practice in your house.



13-3B Connection of wire antenna to coaxial input receiver.



13-4 Dangerous form of antenna/receiver circuitry.

Wire antennas

This section reviews simple wire antennas that are suitable for the reception of shortwave signals, although not necessarily for transmitting. Once again, you are reminded that the law of reciprocity permits you to use any transmitting antenna found in other chapters for receiving also.

Figure 13-5 shows the common receiving longwire. The antenna element should be 30 to 150 ft in length. Although most texts show it horizontal to the ground (and indeed, a case can be made that performance is better that way), it is not strictly necessary. If you must slope the wire, then it is doubtful that you will notice any reception problems.

The far end of the wire is attached to a supporting structure through an insulator and a rope. The support structure can be another building, a tree, or a mast installed especially for this purpose. Chapter 28 deals with antenna construction practices.

Wind will cause motion in the antenna wire and its supporting structure. Over time, the wind movement will fatigue the antenna wire and cause it to break. Also, if a big enough gust of wind (or a sustained storm) comes along, then even a new antenna can either sag badly or break altogether. You can do either of two things to reduce the problem. First, as shown in Fig. 13-5, a door spring can be used to provide a little variable slack in the wire. The spring tension is selected to be only partially expanded under normal conditions, so wind will increase the tension, and stretch the spring. Make sure that the spring is not too strong to be stretched by the action of wind on the antenna, or no good is accomplished.


House
Screw eyelet
Insulator
30 to 150 feet antenna wire
Mast, tree or other support
Rope
Downlead
Insulator
Screw eyelet
Lightning arrestor
Antenna wire
Window
Doorspring or counterweight
Ground tab
Ground wire
RX
Ground rod

13-5 Longwire SWL antenna.

Another tactic is to replace the spring with a counterweight that is heavy enough to keep the antenna nearly taut under normal conditions, but not so heavy that it fails to move under wind conditions. In other words, the antenna tension should exactly balance the counterweight under normal conditions, and not be too great that it stretches the antenna wire excessively.

The antenna wire should be either no. 12 or no. 14 hard-drawn copper, or *Copperweld* stranded wire. The latter is actually steel-core wire, but has a copper coating on the outside. Because of skin effect, RF signals flow only in the outer copper coating. Soft-drawn copper wire will stretch and break prematurely, so it should be avoided.

The downlead of the antenna must be insulated, and it should also be stranded wire (which breaks less easily than solid wire). Again, no. 12 or no. 14 wire should be used, although no. 16 would be permissible. The point where the downlead and antenna are joined should be soldered to prevent corrosion of the joint. Mechanical strength is provided by proper splicing technique (see Fig. 13-6). Do not depend on the solder for mechanical strength, for it has none.

There are several ways to bring a downlead into the building. First, if you can tolerate a slight crack in the junction of the sash and sill, then run the wire underneath the sash and close the window. Alternatively, you can buy a flat strap connector to pass under the window. This method is electrically the same as running the lead, but is mechanically nicer. Chapter 28 deals with several methods, and should be consulted.

Grounding

The ground lead should be a heavy conductor, such as heavy wire or braid. The shield stripped from RG-8 or RG-11 coaxial cable is suitable for most applications. For reception purposes only, the ground may be a cold-water pipe inside the house. Do not use the hot-water pipes (which are not well grounded) or gas pipes (which



13-6 Construction details.

are dangerous to use). Also, be aware that residential air conditioner liquid lines look like copper cold-water pipes in some cases. Don't use them. Chapter 29 deals with grounding.

The lightning arrester is a safety precaution, and it *must* be used! Its purpose is to supply an alternative path to ground in the event of a lightning strike. Although at least one text calls the arrester optional, it is not. Besides the obvious safety reasons (which are reason enough), there are also legal and economic reasons for using the arrester. Your local government building and/or fire codes might require a lightning arrester for outdoor antennas. Also, your insurance company might not honor your homeowner's policy if the lightning arrester (required by local code) is not used. The antenna lightning arrester is *not optional,* so use it.

WARNING! DO NOT EVER ATTEMPT TO INSTALL AN ANTENNA BY CROSSING A POWER LINE! **EVER!** NO MATTER WHAT YOU BELIEVE OR WHAT YOUR FRIENDS TELL YOU, IT'S NEVER SAFE AND IT COULD KILL YOU.

The rest of this discussion touches on antennas, other than the receiver longwire. Because construction details are similar, we will not repeat them. You are, by the way, encouraged to also read Chap. 28 to glean more details on antenna construction methods.

The flattop antenna

The "flattop" antenna is shown in Fig. 13-7. This antenna is a relative of the longwire, with the exception that the downline is at the approximate center of the antenna section. The flattop should be at least a half-wavelength ($492/F_{\mathrm{MHz}}$) at the lowest frequency of operation. The advantage of the flattop is that it allows the maximum use of space in the configuration shown.

Vertical antennas

It is also possible to build shortwave listener antennas in vertical polarization. Figure 13-8 shows one version of this type of antenna. The support (which could


Insulator
Insulator
Rope
Rope
Downlead
Ground wire

13-7 Flattop SWL antenna.


Insulator
Support
Insulator
Coax
or lead

13-8 Wire vertical SWL antenna—works for hams too.

be a tree or building) should have enough height to be at least a quarter-wavelength on the lowest frequency of operation. The antenna is fed at the base with coaxial cable. The center conductor of the coax is connected to the antenna element, and the shield is connected to the ground rod at the base of the structure. You are encouraged to see Chap. 10, which deals with limited space and hidden antennas, for a different version of this antenna. It is possible to install the wire (or multiple wires of different lengths) inside of a length of PVC plumbing pipe. The pipe serves as the support structure, and the conductors are placed inside.

Different lengths of conductor are required for different bands of operation. You can calculate the length (in feet) required for quarter-wavelength vertical antennas from $L_{\text{ft}}=246/F_{\text{MHz}}$. Figure 13-9A shows how several bands are accommodated from the same feedline on the same support structure. In this particular case eight different antenna elements are supported from the same tee bar. Be sure to insulate them from each other, and from the support structure. Again, PVC piping can be used for the support. Another method for accommodating several different bands is to tie the upper ends of the wires to a sloping rope (as in Fig. 13-9B).

Wire directional antenna

A directional antenna has the ability to enhance reception of desired signals, while rejecting undesired signals arriving from slightly different directions. Although directivity normally means a beam antenna, or at least a rotatable dipole, there are certain types of antenna that allow fixed antennas to be both directive and variable. See Chap. 7 for fixed but variable directional antennas and Chap. 11 for fixed and non-variable directive arrays. Those antennas are transmitting antennas, but they work equally well for reception. This section shows a crude, but often effective, directional antenna that allows one to select the direction of reception with pin plugs or switches.

Consider Fig. 13-10. In this case, a number of quarter-wavelength radiators are fanned out from a common feedpoint at various angles from the building. At the near end of each element is a female banana jack. A pair of balanced feedlines from the receiver (300-Ω twin lead, or similar) are brought to the area where the antenna elements terminate. Each wire in the twin lead has a banana plug attached. By selecting which banana jack is plugged into which banana plug, you can select the directional pattern of the antenna. If the receiver is equipped with a balanced antenna input, then simply connect the other end of the twin lead direction to the receiver. Otherwise, use one of the couplers shown in Fig. 13-11.

Figure 13-11A shows a balanced antenna coupler that is tuned to the frequency of reception. The coil is tuned to resonance by the interaction of the inductor and the capacitor. Antenna impedance is matched by selecting the taps on the inductor to which the feedline is attached. A simple RF broadband coupler is shown in Fig. 13-11B. This transformer is wound over a ferrite core, and consists of 12 to 24 turns of no. 26 enameled wire, with more turns being used for lower frequencies, and fewer for higher frequencies. Experiment with the number of turns in order to determine the correct value. Alternatively, use a 1:1 balun transformer instead of Fig. 13-11B; the type intended for amateur radio antennas is overkill powerwise, but it will work nicely.


Crossbar
Insulators
All wires
joined together

13-9A Multiband wire vertical SWL antenna: tee bar style.


Rope
Wires
Ground rod

13-9B Multiband wire vertical SWL antenna: fan style.



13-10 Directional SWL antenna (view from above).

The antenna of Fig. 13-10 works by phasing the elements so as to null, or enhance (as needed), certain directions. This operation becomes a little more flexible if you build a phasing transformer, as shown in Fig. 13-11C and 13-11D. Windings L_1, L_2, and L_3 are wound “trifilar” style onto a ferrite core. Use 14 turns of no. 26 enameled wire for each winding. The idea in this circuit is to feed one element from coil L_2 in the same way all of the time. This port becomes the 0° phase reference. The other port, B, is fed from a reversible winding, so it can either be in phase or 180° out of phase with port A. Adjust the DPDT switch and the banana plugs of Fig. 13-10 for the best reception.



13-11A Antenna matching tuner.



13-11B Antenna matching transformer.



13-11C Phase-switching antenna matcher.



13-11D Phasing box permits phasing antennas 0° to 180°.

14
CHAPTER

Large wire loop antennas

THERE ARE TWO BASIC FORMS OF LOOP ANTENNAS: SMALL AND LARGE. THESE TWO TYPES have different characteristics, work according to different principles, and have different purposes. Small loops are those in which the current flowing in the wire has the same phase and amplitude at every point in the loop (which fact implies a very short wire length, i.e., less than 0.2λ). Such loops respond to the magnetic field component of the electromagnetic radio wave. A large loop antenna has a wire length greater than 0.2λ, with most being either λ/2, 1λ, or 2λ. The current in a large loop varies along the length of the wire in a manner similar to other wire antennas.

λ/2 large loops

The performance of large wire loop antennas depends in part on their size. Figure 14-1 shows a half-wavelength loop (i.e., one in which the four sides are each λ/8 long). There are two basic configurations for this antenna: *continuous* (S_1 closed) and *open* (S_1 open). In both cases, the feedpoint is at the midpoint of the side opposite the switch.

The direction of the main reception, or radiation lobe (i.e., the direction of maximum reception), depends on whether S_1 is open or closed. With S_1 closed, the main lobe is to the right (solid arrow); and with S_1 open, it is to the left (broken arrow). Direction reversal can be achieved by using a switch (or relay) at S_1, although some people opt for unidirectional operation by eliminating S_1, and leaving the loop either open or closed.

The feedpoint impedance is considerably different in the two configurations. In the closed-loop situation (i.e., S_1 closed), the antenna can be modeled as if it were a half-wavelength dipole bent into a square and fed at the ends. The feedpoint ($X_1 - X_2$) impedance is on the order of 3 kΩ because it occurs at a voltage antinode (current node). The current antinode (i.e., I_{max}) is at S_1, on the side opposite the feedpoint. An antenna tuning unit (ATU), or RF impedance transformer, must be used to match the lower impedance of the transmission lines needed to connect to receivers.

The feedpoint impedance of the open-loop configuration (S_1 open) is low because the current antinode occurs at $X_1 - X_2$. Some texts list the impedance as "about 50 Ω," but my own measurements on several test loops were somewhat higher (about 70 Ω). In either case, the open loop is a reasonable match for either 52- or 75-Ω coaxial cable.

Copyright 2001 - the McGraw-Hill Companies


λ/8
λ/8
λ/8
λ/8
X_1
X_2
S_1
Direction of main lobe (S_1 closed)
Direction of main lobe (S_1 open)

14-1 Half-wave square loop antenna with reversal switch.

Neither λ/2 loop configuration shows gain over a dipole. The figure usually quoted is −1-dB forward gain (i.e., a loss compared with a dipole), and about 6-dB front-to-back ratio (FBR). Such low values of FBR indicate that there is no deep notch ("null") in the pattern.

A lossy antenna with a low FBR seems like a born loser, and in most cases it is. But the λ/2 loop finds a niche where size must be constrained, for one reason or another. In those cases, the λ/2 loop can be an alternative. These antennas can be considered limited-space designs, and can be mounted in an attic, or other limited-access place, as appropriate.

A simple trick will change the gain, as well as the direction of radiation, of the closed version of the λ/2 loop. In Fig. 14-2, a pair of inductors (L_1 and L_2) are inserted into the circuit at the midpoints of the sides adjacent to the side containing the feedpoints. These inductors should have an inductive reactance X_L of about 360 Ω in the center of the band of operation. The inductance of the coil is

$$L_{\mu H} = \frac{3.6 \times 10^8}{2\pi F_{Hz}} \qquad \textbf{[14.1]}$$

where

$L_{\mu H}$ is the coil inductance, in microhenrys (µH)
F_{Hz} is the midband frequency, in hertz (Hz)

Example Find the inductance for the coils in a loaded half-wavelength closed-loop antenna that must operate in a band centered on 10.125 MHz.

Solution:

[*Note:* 10.125 MHz = 10,125,000 Hz]

$$L_{\mu H} = \frac{3.6 \times 10^8}{2\pi\ (10{,}125{,}000\ \text{Hz})} = 5.7\ \mu\text{H}$$

The coils force the current antinodes toward the feedpoint, reversing the direction of the main lobe, and creating a gain of about +1 dB over a half-wavelength dipole.

The currents flowing in the antenna can be quite high, so when making the coils, be sure to use a size that is sufficient for the power and current levels anticipated. The 2- to 3-in B&W Air-Dux style coils are sufficient for most amateur radio use. Smaller coils are available on the market, but their use is limited to low-power situations.



14-2 Use of inductive loading to reduce the size of antenna, and make the pattern more uniform.

1λ large loops

If size is not forcing you to a λ/2 loop, then a 1λ loop might be just the ticket. It produces a gain of about +2 dB over a dipole in the directions that are perpendicular to the plane of the loop. The azimuth patterns formed by these antennas are similar to the figure-8 pattern of the dipole. Three versions are shown: the square loop (Fig. 14-3), the diamond loop (Fig. 14-4), and the delta loop (a.k.a. D-loop and triangle—Fig. 14-5). The square and diamond loops are built with λ/4 on each side, and the delta loop is λ/3 on each side. The overall length of wire needed to build these antennas is

$$L_{\text{feet}} = \frac{1005}{F_{\text{MHz}}} \quad \textbf{[14.2]}$$

The polarization of the three loop antennas is horizontal, because of the location of the feedpoints. On the square loop, moving the feedpoint to the middle of either vertical side will provide vertical polarization. Similarly, on the diamond loop vertical polarization is realized by moving the feedpoint to either of the two adjacent apexes. On the delta loop, placing the feedpoint at either of the two other apexes produces a diagonal polarization that offers approximately equal vertical and horizontal polarization components.



14-3 Quarter-wavelength square loop (single-element quad).


$\frac{\lambda}{4}$
$\frac{\lambda}{4}$
$\frac{\lambda}{4}$
$\frac{\lambda}{4}$
X_1
X_2

14-4 Bottom-fed loop.


$\frac{\lambda}{3}$
$\frac{\lambda}{3}$
$\frac{\lambda}{3}$
X_1
X_2

14-5 Delta loop antenna.

The feedpoint impedance of the 1λ loop is around 100 Ω, so it provides a slight mismatch to 75-Ω coax and a 2:1 mismatch to 52-Ω coax. A very good match to 52-Ω coax can be produced using the scheme of Fig. 14-6. Here, a quarter-wavelength coaxial cable matching section is made of 75-Ω coaxial cable. The length of this cable should be

$$L_{\text{feet}} = \frac{246V}{F_{\text{MHz}}} \tag{14.3}$$

where

L_{feet} is the length, in feet (ft)
V is the velocity factor of the coax
F_{MHz} is the frequency, in megahertz (MHz)

The impedance Z_o of the cable used for the matching section should be

$$Z_o = \sqrt{Z_L Z_s} \tag{14.4}$$


To X_1 and X_2
$\frac{\lambda}{4}$ matching section (75 Ω coax)
$\frac{\lambda}{4} = \frac{246V}{F_{\text{MHz}}}$ ft
52Ω coax to receiver (any length)

14-6 Quarter-wavelength coaxial matching section.

where

Z_o is the characteristic impedance of the coax used in the matching section, in ohms
Z_L is the feedpoint impedance of the antenna, in ohms
Z_s is the source impedance (i.e., the 52-Ω characteristic impedance of the line to the receiver in standard systems)

When Eq. 14.4 is applied to this system, where $Z_s = 52\ \Omega$, $Z_L = 100\ \Omega$:

$$Z_o = \sqrt{(100\ \Omega)(52\ \Omega)} = 72\ \Omega \qquad \textbf{[14.5]}$$

This is a very good match to 75-Ω coaxial cable.

Demiquad loop antenna

The *demiquad* is a single-element 1λ quad antenna. The length of the antenna is, like the cubical quad beam antenna (see Chap. 12), one wavelength. Figure 14-7 shows a type of demi-quad based on the tee-cross type of mast.

The impedance-matching section is a quarter-wavelength piece of 75-Ω coaxial cable (RG-58/U or RF-11/U). The length of the matching section is determined from:

$$L = \frac{246V}{F_{\mathrm{MHz}}} \qquad \textbf{[14.6]}$$

where

L is the overall length, in feet
F_{MHz} is the frequency, in megahertz
V is the velocity factor of the coaxial cable (typically 0.66, 0.70, or 0.80)

Delta loop

The *delta loop antenna,* like the Greek uppercase letter “delta” (Δ) from which it draws its name, is triangle-shaped (Fig. 14-8). The delta loop is a full wavelength, with elements approximately 2 percent longer than the natural wavelength (like the quad). The actual length will be a function of the proximity and nature of the underlying ground, so some experimentation is necessary. The approximate preadjustment lengths of the sides are found from:

$$L_1 = \frac{437}{F_{\mathrm{MHz}}}\ \text{ft} \qquad \textbf{[14.7]}$$

$$L_2 = L_3 = \frac{296}{F_{\mathrm{MHz}}} \qquad \textbf{[14.8]}$$

The delta loop antenna is fed from 52-Ω coaxial cable through a 4:1 balun transformer. The delta loop can be built in a fixed location, and will offer a bidirectional pattern.


Wire
Mast
Coax to
XMTR
(52 Ω)
Matching
section
(75 Ω)

14-7 Demiquad antenna.


L_1
L_2
L_3
$L_1 = \frac{437}{F_{\text{MHz}}}$ Feet
$L_2 = L_3 = \frac{296}{F_{\text{MHz}}}$ Feet
4:1 BALUN

14-8 Delta loop antenna.

Half-delta sloper (HDS)

The *half-delta sloper* (HDS) antenna (Fig. 14-9) is similar to the full delta loop, except that (like the quarter-wavelength vertical) half of the antenna is in the form of an "image" in the ground. Gains of 1.5 to 2 dB are achievable. The HDS antenna consists of two elements: a λ/3-wavelength sloping wire and a λ/6 vertical wire (on an insulated mast), or a λ/6 metal mast. Because the ground currents are very important, much like the vertical antenna, either an extensive radial system at both ends is needed, or a base ground return wire (buried) must be provided.

The HDS will work on its design frequency, plus harmonics of the design frequency. For a fundamental frequency of 5 MHz, a vertical segment of 33 ft and a sloping section of 66 ft is needed. The lengths for any frequency are found from

$$\frac{\lambda}{3} = \frac{328}{F_{\text{MHz}}} \qquad \textbf{[14.9]}$$

and

$$\frac{\lambda}{6} = \frac{164}{F_{\text{MHz}}} \quad \textbf{[14.10]}$$

The HDS is fed at one corner, close to the ground. If only the fundamental frequency is desired, then you can feed it with 52-Ω coaxial cable. But at harmonics, the feedpoint impedance changes to as high as 1000 Ω. If harmonic operation is intended, then an antenna tuning unit (ATU) is needed at point *A* to match these impedances.

Bisquare loop antenna

The *bisquare antenna,* shown in Fig. 14-10, is similar to the other large loops, except that it is λ/2 on each side, making a total wire length of two wavelengths. This antenna is built like the diamond loop shown earlier (i.e., it is a large square loop fed at an apex that is set at the bottom of the assembly). In this case, the loop is fed either with an antenna tuning unit (to match a 1000-Ω impedance) or a quarter-wavelength matching section made of 300-Ω or 450-Ω twin-lead transmission line. A 1:1 balun transformer connects the 75-Ω coaxial cable to the matching section.


Good electrical
and mechanical
connection
λ/3
λ/6
Metal mast
or wire
Earth
A
52 Ω
Coax
Buried ground return wire (bare)

14-9 Half-delta loop antenna.


Each side is $\frac{\lambda}{2}$
$L_{\text{side}} = \frac{480}{F_{\text{MHz}}}$
$\frac{\lambda}{4}$ Matching section
1:1 BALUN transformer
52 Ω Coaxial cable to receiver

14-10 Bisquare 2λ square loop antenna.

The bisquare antenna offers as much as 4-dB gain broadside to the plane of the antenna (i.e., in and out of the book page), in a figure-8 pattern, on the design frequency. It is horizontally polarized. When the frequency drops to one-half of the design frequency, the gain drops to about 2 dB, and the antenna works like the diamond loop covered previously.

This page intentionally left blank

15
Chapter

Small loop receiving antennas

Radio direction finders and people who listen to the AM broadcasting bands, VLF, medium-wave, or the so-called low-frequency tropical bands are all candidates for a small loop antenna. These antennas are fundamentally different from large loops and other sorts of antennas used in these bands. Large loop antennas have a length of at least 0.5λ, and most are quite a bit larger than 0.5λ. Small loop antennas, on the other hand, have an overall length that is less than 0.22λ, with most being less than 0.10λ.

The small loop antenna responds to the magnetic field component of the electromagnetic wave instead of the electrical field component. One principal difference between the large loop and the small loop is found when examining the RF currents induced in a loop when a signal intercepts it. In a large loop, the current will vary from one point in the conductor to another, with voltage varying out of phase with the current. In the small loop antenna, the current is the same throughout the entire loop.

The differences between small loops and large loops show up in some interesting ways, but perhaps the most striking is the directions of maximum response—the main lobes—and the directions of the nulls. Both types of loops produce figure-8 patterns but in directions at right angles with respect to each other. The large loop antenna produces main lobes *orthogonal,* at right angles or "broadside," to the plane of the loop. Nulls are off the sides of the loop. The small loop, however, is exactly the opposite: The main lobes are off the sides of the loop (in the direction of the loop plane), and the nulls are broadside to the loop plane (Fig. 15-1A). Do not confuse small loop behavior with the behavior of the loopstick antenna. Loopstick antennas are made of coils of wire wound on a ferrite or powdered-iron rod. The direction of maximum response for the loopstick antenna is broadside to the rod, with deep nulls off the ends (Fig. 15-1B). Both loopsticks and small wire loops are used for radio direction-finding and for shortwave, low-frequency medium-wave, AM broadcast band, and VLF listening.

The nulls of a loop antenna are very sharp and very deep. Small changes of pointing direction can make a profound difference in the response of the antenna. If you point a loop antenna so that its null is aimed at a strong station, the signal strength of

Copyright 2001 - the McGraw-Hill Companies



15-1A Large loop antenna.

the station appears to drop dramatically at the center of the notch. Turn the antenna only a few degrees one way or the other, however, and the signal strength increases sharply. The depth of the null can reach 10 to 15 dB on sloppy loops and 30 to 40 dB on well-built loops (30 dB is a very common value). I have seen claims of 60-dB nulls for some commercially available loop antennas. The construction and uniformity of the loop are primary factors in the sharpness and depth of the null.



15-1B Loopstick antenna.

At one time, the principal use of the small loop antenna was radio direction-finding, especially in the lower-frequency bands. The RDF loop is mounted with a compass rose to allow the operator to find the direction of minimum response. The null was used, rather than the peak response point, because it is far narrower than the peak. As a result, precise determination of direction is possible. Because the null is bidirectional, ambiguity exists as to which of the two directions is the correct direction. What the direction-finder “finds” is a line along which the station exists. If the line is found from two reasonably separated locations and the lines of direction are plotted on a map, then the two lines will cross in the area of the station. Three or more lines of direction (a process called *triangulation*) yields a pretty precise knowledge of the station’s actual location.

Today, these small loops are still used for radio direction-finding, but their use has been extended into the general receiving arena, especially on the low frequencies. One of the characteristics of these bands is the possibility of strong local interference smothering weaker ground-wave and sky-wave stations. As a result, you cannot hear cochannel signals when one of them is very strong and the other is weak. Similarly, if a cochannel station has a signal strength that is an appreciable fraction of the desired signal and is slightly different in frequency, then the two signals will heterodyne together and form a whistling sound in the receiver output. The frequency of the whistle is an audio tone equal to the difference in frequency between the two signals. This is often the case when trying to hear foreign BCB signals on frequencies (called *split frequencies*) between the standard spacing. The directional characteristics of the loop can help if the loop null is placed in the direction of the undesired signal.

Loops are used mainly in the low-frequency bands even though such loops are either physically larger than high-frequency loops or require more turns of wire. Loops have been used as high as VHF and are commonly used in the 10-m ham band for such activities as hidden transmitter hunts. The reason why low frequencies are the general preserve of loops is that these frequencies are more likely to have substantial ground-wave signals. Sky-wave signals lose some of their apparent directivity because of multiple reflections. Similarly, VHF and UHF waves are likely to reflect from buildings and hillsides and so will arrive at angles other than the direction of the transmitter. As a result, the loop is less useful for the purpose of radio direction-finding. If your goal is not RDF but listening to the station, this is hardly a problem. A small loop can be used in the upper shortwave bands to null a strong local ground-wave station in order to hear a weaker sky-wave station. Finally, loops can be useful in rejecting noise from local sources, such as a “leaky” electric power line or a neighbor’s outdoor light dimmer.

Let’s examine the basic theory of small loop antennas and then take a look at some practical construction methods.

Grover’s equation

Grover’s equation (Grover, 1946) seems closer to the actual inductance measured in empirical tests than certain other equations that are in use. This equation is

$$L_{\mu\mathrm{H}} = (K_1 N^2 a) \times \left\{ \ln\left[\frac{K_2 a N}{(N+1)\,b}\right] + K_3 + \left[\frac{K_4\,(N+1)\,b}{aN}\right]\right\}$$

where $L_{\mu\mathrm{H}}$ is the inductance, in microhenrys (μH)
a is the length of a loop side, in centimeters (cm)
b is the loop width, in centimeters (cm)

n is the number of turns in the loop
K_1 through K_4 are shape constants and are given in Table 15-1
ln is the natural log of this portion of the equation

Air core frame loops ("box" loops)

A wire loop antenna is made by winding a large coil of wire, consisting of one or more turns, on some sort of frame. The shape of the loop can be circular, square, triangular, hexagonal, or octagonal. For practical reasons, the square loop seems to be most popular. With one exception, the loops considered in this section will be square, so you can easily duplicate them.

The basic form of the simplest loop is shown in Fig. 15-2. This loop is square, with sides the same length A all around. The width of the loop (B) is the distance from the first turn to the last turn in the loop, or the diameter of the wire if only one turn is used. The turns of the loop in Fig. 15-2 are *depth wound,* meaning that each turn of the loop is spaced in a slightly different parallel plane. The turns are spaced evenly across distance B. Alternatively, the loop can be wound such that the turns are in the same plane (this is called *planar winding*). In either case, the sides of the loop (A) should be not less than five times the width (B). There seems to be little difference between depth- and planar-wound loops. The far-field patterns of the different shape loops are nearly the same if the respective cross-sectional areas (πr^2 for circular loops and A^2 for square loops) are less than $\lambda^2/100$.

The reason why a small loop has a null when its broadest aspect is facing the signal is simple, even though it seems counterintuitive at first blush. Take a look at Fig. 15-3. Here, we have two identical small loop antennas at right angles to each other. Antenna A is in line with the advancing radio wave, whereas antenna B is broadside to the wave. Each line in the wave represents a line where the signal strength is the same, i.e., an "isopotential line." When the loop is in line with the signal (antenna A), there is a difference of potential from one end of the loop to the other, so current can be induced in the wires. When the loop is turned broadside, however, all points on the loop are on the same potential line, so there is no difference of potential between segments of the conductor. Thus little signal is picked up (and the antenna therefore sees a null).

The actual voltage across the output terminals of an untuned loop is a function of the angle of arrival of the signal α (Fig. 15-4), as well as the strength of the signal and the design of the loop. The voltage V_o is given by

Table 15-1. Shape constants

Shape	K_1	K_2	K_3	K_4
Triangle	0.006	1.155	0.655	0.135
Square	0.008	1.414	0.379	0.33
Hexagon	0.012	2.00	0.655	0.135
Octagon	0.016	2.613	0.7514	0.0715



15-2A A simple loop antenna.

$$V_o = \frac{2\pi A N E_f \cos(\alpha)}{\lambda}$$

where V_o is the output voltage of the loop
A is the area of the loop, in square meters (m^2)
N is the number of turns of wire in the loop
E_f is the strength of the signal, in volts per meter (V/m)
a is the angle of arrival of the signal
λ is the wavelength of the arriving signal

Loops are sometimes specified in terms of the *effective height* of the antenna. This number is a theoretical construct that compares the output voltage of a small loop with a vertical piece of the same kind of wire that has a height of

$$H_{eff} = \frac{2\pi N A}{\lambda}$$

If a capacitor (such as C_1 in Fig. 15-2) is used to tune the loop, then the output voltage V_o will rise substantially. The output voltage found using the first equation is multiplied by the loaded Q of the tuned circuit, which can be from 50 to 100:

$$V_o = \frac{2\pi A N E_f Q \cos(\alpha)}{\lambda}$$

Even though the output signal voltage of tuned loops is higher than that of untuned loops, it is nonetheless low compared with other forms of antenna. As a result, a loop preamplifier usually is needed for best performance.


A
B
ADVANCING RADIO WAVE

15-3 Two small loop antennas at right angles to each other.


ADVANCING RADIO WAVE
α
LOOP
LOOP AXIS

15-4 An untuned loop antenna.

Transformer loops

It is common practice to make a small loop antenna with two loops rather than just one. Figure 15-5 shows such a transformer loop antenna. The main loop is built exactly as discussed above: several turns of wire on a large frame, with a tuning capacitor to resonate it to the frequency of choice. The other loop is a one- or two-turn *coupling loop.* This loop is installed in very close proximity to the main loop, usually (but not necessarily) on the inside edge not more than a couple of centimeters away. The purpose of this loop is to couple signal induced from the main loop to the receiver at a more reasonable impedance match.

The coupling loop is usually untuned, but in some designs a tuning capacitor (C_2) is placed in series with the coupling loop. Because there are many fewer turns on the coupling loop than on the main loop, its inductance is considerably smaller. As a result, the capacitance to resonate is usually much larger. In several loop antennas constructed for purposes of researching this chapter, I found that a 15-turn main loop resonated in the AM BCB with a standard 365-pF capacitor, but the two-turn



15-5 A transformer loop antenna.

coupling loop required three sections of a ganged 3 × 365-pF capacitor connected in parallel to resonate at the same frequencies.

In several experiments, I used computer ribbon cable to make the loop turns. This type of cable consists of anywhere from 8 to 64 parallel insulated conductors arranged in a flat ribbon shape. Properly interconnected, the conductors of the ribbon cable form a continuous loop. It is no problem to take the outermost one or two conductors on one side of the wire array and use them for a coupling loop.

Tuning schemes for loop antennas

Loop performance is greatly enhanced by tuning the inductance of the loop to the desired frequency. The bandwidth of the loop is reduced, which reduces front-end overload. Tuning also increases the signal level available to the receiver by a factor of 20 to 100 times. Although tuning can be a bother if the loop is installed remotely from the receiver, the benefits are well worth it in most cases.

There are several different schemes available for tuning, and these are detailed in Fig. 15-6. The parallel tuning scheme, which is by far the most popular, is shown in Fig. 15-6A. In this type of circuit, the capacitor (C_1) is connected in parallel with the inductor, which in this case is the loop. Parallel resonant circuits have a very high impedance to signals on their resonant frequency and a very low impedance to other frequencies. As a result, the voltage level of resonant signals is very much larger than the voltage level of off-frequency signals.

The series resonant scheme is shown in Fig. 15-6B. In this circuit, the loop is connected in series with the capacitor. A property of series resonant circuits is that they offer a high impedance to all frequencies except the resonant frequency (exactly the opposite of the case of parallel resonant circuits). As a result, current from the signal will pass through the series resonant circuit at the resonant frequency, but off-frequency signals are blocked by the high impedance.

There is a wide margin for error in the inductance of loop antennas, and even the precise-looking equations to determine the required values of capacitance and inductance for proper tuning are actually only estimations. The exact geometry of the loop "as built" determines the actual inductance in each particular case. As a result, it is often the case that the tuning provided by the capacitor is not as exact as desired, so some form of compensation is needed. In some cases, the capacitance required for resonance is not easily available in a standard variable capacitor, and some means must be provided for changing the capacitance. Figure 15-6C shows how this is done. The main tuning capacitor can be connected in either series or parallel with other capacitors to change the value. If the capacitors are connected in parallel, then the total capacitance is increased (all capacitances are added together). If the extra capacitor is connected in series, however, then the total capacitance is reduced. The extra capacitors can be switched in and out of a circuit to change frequency bands.

Tuning of a remote loop can be a bother if it is done by hand, so some means must be found to do it from the receiver location (unless you enjoy climbing into the attic or onto the roof). Traditional means of tuning called for using a low-rpm dc motor, or stepper motor, to turn the tuning capacitor. A very popular combination was the little 1- to 12-rpm motors used to drive rotating displays in retail store show


A
C1
TO
RECEIVER
B
C1
TO
RECEIVER
C
C3
TRIMMER
C2
C1
MAIN
TUNE

15-6 Various tuning schemes: (A) parallel, (B) series resonant, (C) series or parallel.

windows. But this approach is not really needed today. We can use varactor voltage-variable capacitance diodes to tune the circuit.

A varactor works because the junction capacitance of the diode is a function of the applied reverse-bias voltage. A high voltage (such as 30 V) drops the capacitance, whereas a low voltage increases it. Varactors are available with maximum capacitances of 22, 33, 60, 100, and 400 pF. The latter are of most interest to us because they have the same range as the tuning capacitors normally used with loops.

Figure 15-7 shows how a remote tuning scheme can work with loop antennas. The tuning capacitor is a combination of a varactor diode and two optional capacitors: a fixed capacitor (C_1) and a trimmer (C_2). The dc tuning voltage (V_t) is provided from the receiver end from a fixed dc power supply (V+). A potentiometer (R_1) is used to set the voltage to the varactor, hence also to tune the loop. A dc blocking capacitor (C_3) keeps the dc tuning voltage from being shorted out by the receiver input circuitry.

The sports fan's loop

OK, sports fans, what do you do when the best game of the week is broadcast only on a low-powered AM station and you live at the outer edge of their service area where the signal strength leaves much to be desired? You use the sports fan's loop antenna, that's what! I first learned of this antenna from a friend of mine, a professional broadcast engineer, who worked at a religious radio station that had a pipsqueek signal but lots of fans. It really works—*one might say it's a miracle.*

The basic idea is to build a 16-turn, 60-cm^2 tuned loop and then place the AM portable radio at the center so that its loopstick is aimed such that its null end is broadside of the loop. When you do so, the nulls of both the loop and the loopstick are in the same direction. The signal will be picked up by the loop and then coupled to the radio's loopstick antenna. Sixteen-conductor ribbon cable can be used for making the loop. For an extra touch of class, place the antenna and radio assembly on a dining room table lazy Susan to make rotation easier. A 365-pF tuning capacitor is used to resonate the loop. If you listen to only one station, then this capacitor can be a trimmer type.

Shielded loop antennas

The loop antennas discussed thus far in this chapter have all been unshielded types. Unshielded loops work well under most circumstances, but in some cases their pattern is distorted by interaction with the ground and nearby structures (trees, buildings, etc.). In my own tests, trips to a nearby field proved necessary to measure the depth of the null because of interaction with the aluminum siding on my house. Figure 15-8 shows two situations. In Fig. 15-8A we see the pattern of the normal "free space" loop, i.e., a perfect figure-8 pattern. When the loop interacts with the nearby environment, however, the pattern distorts. In Fig. 15-8B we see some filling of the notch for a moderately distorted pattern. Some interactions are so severe that the pattern is distorted beyond all recognition.


LOOP ANTENNA
D1
NTE-418
OR EQUIV.
C1
C2
R1
10K
TUNE
V+
V_T
R2
47K
C3
0.1 uF
TO RECEIVER
ANTENNA INPUT
TERMINALS

15-7 Remote tuning scheme.



15-8A A normal "free space" loop.



15-8B Filling of the notch.

The solution to the problem is to reduce interaction by shielding the loop, as in Fig. 15-9. Loop antennas operate on the magnetic component of the electromagnetic wave, so the loop can be shielded against voltage signals and electrostatic interactions. In order to prevent harming the ability to pick up the magnetic field, a gap is left in the shield at one point.

There are several ways to shield a loop. You can, for example, wrap the loop in adhesive-backed copper-foil tape. Alternatively, you can wrap the loop in aluminum foil and hold it together with tape. Another method is to insert the loop inside a copper or aluminum tubing frame. Or—the list seems endless.

Using a loop antenna

Most readers will use a loop for DXing rather than hidden transmitter hunting, navigation, or other RDF purposes. For the DXer, there are actually two uses for the



15-9 Shielding the loop.

loop. One is when you are a renter or live in a community that has routine covenants against outdoor antennas. In this situation, the loop will serve as an active antenna for receiving AM BCB and other low-frequency signals without the neighbors or landlord becoming PFJs ("purple-faced jerks").

The other use is illustrated by the case of a friend of mine. He regularly tunes in clear channel WSM (650 kHz, Nashville) in the wee hours between Saturday evening ("Grand Ole Opry" time) and dawn. However, this "clear" channel of WSM is not really so clear, especially without a narrow filter in the receiver. He uses a loop antenna to null out a nearby 630-kHz signal that made listening a bit dicey and can now tape his 1940s–1950s vintage country music.

It is not necessary to place the desired station directly in the main lobes off the ends of the antenna but rather to place the nulls (broadside) in the direction of the offending station that you want to eliminate. So what happens if the offending station and the desired station are in a direct line with each other and your receiving location is in the middle between them? Both nulls and lobes on a loop antenna are bidirectional, so a null on the offending station also will null the desired station in the opposite direction.

One method is to use a sense antenna to spoil the pattern of the loop to a cardioid shape. Another method is to use a spoiler loop to null the undesired signal. The spoiler loop is a large box loop placed 1 to 3 ft (found experimentally) behind the reception loop in the direction of the offending signal. This method was first described by Levintow and is detailed in Fig. 15-10. The small loopstick may be the antenna inside the receiver, whereas the large loop is a box loop such as the sports fan's loop. The large box loop is placed about 33 to 100 cm behind the loopstick and in the direction of the offending station. The angle with respect to the line of centers should be 60° to 90°, which also was found experimentally. It is also possible to use two air core loops to produce an asymmetrical receiving pattern.

Sharpening the loop

Many years ago, the *Q-multiplier* was a popular add-on accessory for a communications receiver. These devices were sold as Heathkits, and many construction projects could be found in magazines and amateur radio books. The Q-multiplier has the effect of seeming to greatly increase the sensitivity of a receiver, as well as greatly reducing the bandwidth of the front end. Thus it allows better reception of some stations because of increased sensitivity and narrowed bandwidth.

A Q-multiplier is an active electronic circuit placed at the antenna input of a receiver. It is essentially an Armstrong oscillator, as shown in Fig. 15-11, that does not quite oscillate. These circuits have a tuned circuit (L_1/C_1) at the input of an amplifier stage and a feedback coupling loop (L_3). The degree of feedback is controlled by the coupling between L_1 and L_3. The coupling is varied by varying both how close the two coils are and their relative orientation with respect to each other. Certain other circuits use a series potentiometer in the L_3 side that controls the amount of feedback.

The Q-multiplier is adjusted to the point that the circuit is just on the verge of oscillating, but not quite. As the feedback is backed away from the threshold of oscillation, but not too far, the narrowing of bandwidth occurs, as does the increase in sensitivity. It takes some skill to operate a Q-multiplier, but it is easy to use once you get the hang of it and is a terrific accessory for any loop antenna.

Loop amplifier

Figure 15-12 shows the circuit for a practical loop amplifier that can be used with either shielded or unshielded loop antennas. It is based on junction field effect transistors (JFET) connected in cascade. The standard common-drain configuration is used for each transistor, so the signals are taken from the source terminals. The drain terminals are connected together and powered from the +12-V dc power


LARGE BOX
LOOP ANTENNA
2 TO 3 FEET
BEHIND
LOOPSTICK
LOOPSTICK
AXIS
LOOPSTICK
60 to 90
DEGREES
INTERFERING
STATION
DESIRED
STATION

15-10 Use of a spoiler loop to null an undesired signal.


TO RECEIVER PREAMPLIFIER
L2 COUPLING LOOP
+9 VOLTS DC
C3 0.1 uF
C2 200 uF
+
Q1 MPF-102 Q-MULTIPLIER
LOOP ANTENNA L1
C1
R1 100K
L3 Q MULTIPLIER FEEDBACK

15-11 A Q-multiplier.

supply. A 2.2-μF bypass capacitor is used to put the drain terminals of Q_1 and Q_2 at ground potential for ac signals while keeping the dc voltage from being shorted out.

The two output signals are applied to the primary of a center-tapped transformer, the center tap of which is grounded. To keep the dc on the source terminals from being shorted through the transformer winding, a pair of blocking capacitors (C_4, C_5) is used.

The input signals are applied to the gate terminals of Q_1 and Q_2 through dc blocking capacitors C_2 and C_3. A pair of diodes (D_1, D_2) is used to keep high-amplitude noise transients from affecting the operation of the amplifier. These diodes are connected back to back in order to snub out both polarities of signal.

Tuning capacitor C_1 is used in lieu of the capacitor in the loop and is used to resonate the loop to a specific frequency. Its value can be found from the equation given earlier.

The transistors used for the push-pull amplifier (Q_1, Q_2) can be nearly any general-purpose JFET device (MPF-102, MPF-104, etc.). A practical approach for many people is to use transistors from service replacement lines, such as the NTE-312 and NTE-316 devices.


+12 VDC
C6 22 uF
+
C5 0.1 uF
R5 100 OHMS
RF OUTPUT
T1
C4 0.1 uF
C5 0.1 uF
Q1 (SEE TEXT)
Q2 (SEE TEXT)
+
R4 3.3K
R3 3.3K
C7 2.2 uF
R1 1 MEG
R2 1 MEG
C2 0.1 uF
C3 0.1 uF
D2
D1
C1
A
GND
B

15-12 A practical loop amplifier.

Special problem for VLF/LF loops

A capacitance is formed whenever two conductors are side by side. A coil produces capacitance as well as inductance because the turns are side by side. Unfortunately, with large multiturn loops, this capacitance can be quite large. The "distributed capacitance" of the loop causes a self-resonance with the inductance. The loop does not work well at frequencies above the self-resonant point, so it is sometimes important to raise the self-resonance to a point where it does not affect operation at the desired frequencies.

Figure 15-13 shows a solution that raises the self-resonant point. The turns are broken into two or more groups and separated by a space. This method reduces the effective capacitance by placing the capacitances of each group of wires in series with the others.



15-13 Raising the self-resonant point.

Coaxial-cable loop antennas

One of the more effective ways to make a shielded loop is to use coaxial cable. Figure 15-14 shows the circuit of such a loop. Although only a single-turn loop is shown, there can be any number of turns. One reader made a 100-kHz LORAN (a navigation system) loop using eight turns of RG-59/U coaxial cable on an 8-ft diameter.

Note the special way that the coaxial cable is connected. This method is called the *Faraday connection* after the fact that the shield of the coax forms a *Faraday shield.* At the output end, the center conductor of the coaxial cable is connected to the center conductor of the coaxial connector. The coax shield is connected to the connector ground/shield terminal. At the other end of the loop, the shield is left floating, but the center conductor is connected to the shield. Note very carefully that the center conductor at the far end is connected to the shield *at the connector,* not at just any convenient point.



15-14 A coaxial-cable shielded loop.

16
Chapter

Small transmitting loop antennas

Small transmitting loops are those which are less than one-third wavelength (λ/3) according to Hart (1986) or between 0.04λ and 0.10λ according to Belrose (1993). Other sources claim that loops up to about 0.20λ are small. The key characteristic is that the current is equal in all points of the loop rather than varying with loop length the way the current in a large loop (or other antenna) does.

One of the parameters of the small loop antenna is a very low radiation resistance (it is a function of the area of the loop). The radiation resistance of the small loop antenna is less than 1 Ω and often considerably less than this figure (e.g., 0.05 Ω). This means that the copper or aluminum losses of the antenna must be kept very, very low. For such reasons, it is common to assemble the small transmitting loop antenna from 1- to 4-in copper or aluminum pipe. For this reason, the square (Fig. 16-1A) or octagon (Fig. 16-1B) shapes are preferred. The reason this is true is purely mechanical: The square loop can be built with 90° elbow joints, and the octagon can be built with 45° elbow joints. For antennas whose circumference is greater than λ/8, standard ¾-in copper pipe can be used in construction, but for smaller-sized loops, larger-sized copper piping is used.

The small transmitting loop tends to be highly inductive in its reactance. Values of inductive reactance to 1000 Ω are not unusual, although closer to 100 Ω is the norm. Because of this inductive reactance, the small transmitting loop antenna is tuned by one or more series capacitors.

A sample loop was modeled by Belrose (1993). It was 1 m in diameter and was made of 2.54-cm (1-in) copper pipe. For this loop, the gains were

10 MHz	2.88 dBi
14 MHz	0.22 dBi
21 MHz	1.14 dBi
30 MHz	1.42 dBi

Note that the gains were all less than that of a dipole (12.15 dBi) but in the upper regions of the frequency spectrum were quite decent. Even at 10 MHz, the 1-m

Copyright 2001 - the McGraw-Hill Companies



16-1 Small transmitting loop antennas: (A) square, (B) octagon.

small loop antenna was only −5.03 dBi less than the dipole. The loop probably would show similar gains up to the point of self-resonance.

Calculations of the current and voltage within the loop are substantial. The loop impedance at 10 MHz is $0.088\ 1\ j161\ \Omega$. This means that a 150-W transmitter, certainly modest for these frequencies, would produce 41 A circulating inside the loop and a voltage across the tuning capacitor of 6600 V. As Belrose (1993) warns: “Don’t touch your loop when transmitting!”

The tuning capacitor in Belrose’s loop should be rated for at least 10,000 V to guard against anyone using more than 150 W. Keep in mind that a power of 500 W will produce potentials across the capacitor of 30,000 V, so you will need a capacitor with at least $^{1}/_{2}$-in spacing. A 1-in spacing is good for about 75,000 V. It is probably best to use a vacuum-variable capacitor for the tuning capacitor of a small loop antenna if you can afford one. Regardless, the loop power should be kept under control!

The Q of the antenna at any given resonant frequency is very, very high. For the 1-m loop antenna described earlier, the Q at 10 MHz was 1824, which resulted in a bandwidth of 5.5 kHz (although in practice it is twice this amount before VSWR tolerances on the transmitter are exceeded). Regardless, the bandwidth of the resonated loop is tiny, so some means must be provided for retuning the loop as you shift frequency. If you do not shift frequency, then the loop can be tuned and forgotten, but for the rest of the radio fraternity, perhaps a remotely tuned capacitor is in order. Getting a large capacity variable in the voltages that are required for operation with a good power level is a bit tricky.

Design equations

The design equations developed by Hart (1986) are as follows:

Radiation resistance (R_R):

$$R_R = 3.38 \times 10^{-8} (F^2 A)^2 \qquad \textbf{[16.1]}$$

Loss resistance (R_L):

$$R_L = \frac{9.96 \times 10^{-4} S \sqrt{F}}{D} \qquad \textbf{[16.2]}$$

Efficiency (η):

$$\eta = \frac{R_R}{R_R + R_L} \qquad \textbf{[16.3]}$$

Inductance (L):

$$\mathrm{L} = 1.9 \times 10^8 \mathrm{S} \left(7.353 \log_{10} \frac{96S}{\pi D} - 6.386\right) \qquad \textbf{[16.4]}$$

Inductive reactance (X_L):

$$X_L = 2\pi F L \times 10^6 \qquad \textbf{[16.5]}$$

Tuning capacitance (C):

$$C = \frac{1}{2\pi F X_L \times 10^6} \qquad \textbf{[16.6]}$$

Quality factor (Q):

$$Q = \frac{F}{\Delta F} = \frac{X_L}{2\,(R_R + R_L)} \qquad \textbf{[16.7]}$$

Bandwidth (ΔF):

$$\Delta F = \frac{F}{Q} \qquad \textbf{[16.8]}$$

Distributed capacitance (C_D):

$$C_D = 0.82S \qquad \textbf{[16.9]}$$

Capacitor voltage (V_C):

$$V_C = \sqrt{P X_L Q} \qquad \textbf{[16.10]}$$

where

A is the area of the loop, in square feet (ft2)
S is the length of the loop conductor, in feet (ft)
D is the diameter of the conductor, in inches (in)
P is the applied transmitter output power, in watts (W)

Some sample loop antennas

The Patterson (1967) loop antenna is shown in Fig. 16-2. It is made from 1.5-in copper tubing. Segments are cut and are joined together by eight 45° elbow joints, giving the octagon shape. Each segment is 0.5 ft long. The tuning is accomplished by three capacitors, two of which are a split-stator unit (two capacitors on the same shaft). The tuning control is the split-stator capacitor, whereas the loading control is a single capacitor.



16-2 A Patterson loop antenna.

Another loop antenna is shown in Fig. 16-3. This antenna has a Faraday feed system rather than a capacitor-coupled feed system, as did the Patterson loop. The tuning is accomplished by C_A, the series tuning capacitor. The requirement must be met that $D_1/D_2 = 5$.

Still another loop is shown in Fig. 16-4. This loop relies on magnetic coupling to perform the coupling of the transmitter. In this loop antenna, the coupling is via a small coupling loop and 50-Ω coaxial cable to the transmitter. Capacitor C_1 is used to resonate the loop, whereas capacitors C_2 and C_3 serve the purposes of loading and resonating the coupling loop. According to Mozzochi (1993), the voltages and currents with respect to the capacitors are

$$V_{C1} = 1800\sqrt{P} \qquad \textbf{[16.11]}$$

$$V_{C2} = 18\sqrt{\mathrm{P}} \qquad \textbf{[16.12]}$$

$$V_{C3} = 17\sqrt{\mathrm{P}} \qquad \textbf{[16.13]}$$

$$I_{C1} = 2.2\sqrt{\mathrm{P}} \qquad \textbf{[16.14]}$$

$$I_{C2} = 0.21\sqrt{P} \qquad \textbf{[16.15]}$$



16-3 A loop antenna with a Faraday feed system.



16-4 A loop antenna with magnetic coupling.

$$I_{C3} = 0.15\sqrt{P} \qquad \textbf{[16.16]}$$

The radiation patterns for the loop antenna are shown in Fig. 16-5. Note that four elevations are given (0°, 20°, 45°, and 60°).

The bottom line is that small transmitting loop antennas are not very good for those who can afford to put up a better antenna, but for those whose tight quarters permit only a small transmitting loop, they are quite viable.

References

Belrose, John S. (1993), "An Update on Compact Transmitting Loops," *QST,* November.

Erwin, David (1991), "Very Small Transmitting and Receiving Only Antennas," in *HF Antenna Collection,* Radio Society of Great Britain, Potters Bar, Herts., UK, Chap. 5.

Grover, F. W. (1946), *Inductance Calculation-Working Formulas and Tables,* Van Nostrand, New York.

Hart, Ted (1986), "Small, High-Efficiency Loop Antennas: An Alternative Antenna for Small Spaces," *QST,* June.

Koontz, Floyd (1993), "A High-Directivity Receiving Antenna for 3.8 MHz," *QST,* August, pp. 31–34.

McCoy, L. (1968), "The Army Loop in Ham Communications," *QST,* March, pp. 17–18, 150; see also "Technical Correspondence" column, *QST,* May, pp. 49–51, and November, pp. 46–47.


180°
60° Elevation
45° Elevation
20° Elevation
0° Elevation
270°
90°
LOOP
0°

16-5 Radiation patterns.

Mozzochi, Charles J. (1993), "A Small Loop Antenna for 160 Meters," *QST,* pp. 32–34.

Orr, William (1994), "Feedback on Hart's article," *QST,* July.

Patterson, K. (1967), "Down-to-Earth Army Antennas," *Electronics,* August 21, pp. 111–114.

Somerfield, A. (1952), *Electrodynamics,* Academic Press, New York.

This page intentionally left blank

17
CHAPTER
Antenna modeling software

One of the significant contributions of computer technology to antenna design is the improvement of modeling and simulation. Modeling and simulation are used in a wide variety of applications, including management, science, and engineering. We can now model just about any process, any device, or any circuit that can be reduced mathematically. The purpose of modeling, at least in engineering, is to do the design cheaply on the computer before "bending metal." The old "cut and try" method works, to be sure, but it is costly in time and money (two things perpetually in short supply). If performance issues and problems can be solved on a computer, then we are time and money ahead of the game. Also, modeling and simulation make it possible to look at more alternatives and to gauge the effect of a change in an antenna design before the change is made.

Modeling is used not just in engineering but also in other processes. Organizations and management consultants use modeling and simulation to study their operations and find the most efficient way of doing things. I saw an example where an inefficient truck terminal and warehouse operation was improved significantly by modeling on a Windows desktop computer. The operators modeled the existing system and several alternative systems, and found that one particular rule (involving bulk deliver trucks such as tankers and dry bulk carriers) was jamming up the normal package deliveries at the warehouse dock. They could have tried different sets of rules over a couple of years, collected lots of data, presented scores of viewgraphs to management committees, and still have overlooked the actual cause of the problem. The model showed the problem in only a few minutes, however.

What is a model?

Models are no big mystery. If you have fingers and can count, then you can make models. In fact, you probably do make models mentally, e.g., when you look at how much cash you have in your pocket when confronted with several different purchase choices but cannot afford all of them. The "model" is the "what if" considerations that lead to your selection.

Copyright 2001 - the McGraw-Hill Companies

Youngsters in the schools are learning that the equations and formulas they learn in algebra and trigonometry are "models." This designation was not used when I was in school, but it is an apt description in most cases.

One of the earliest modeling methods for the masses was the computer-based spreadsheet program. Software such as Microsoft Excel can be used to test various scenarios by entering different values into the cells. I have seen spreadsheets used for the originally intended business applications, as well as engineering applications (including antenna design).

Antenna modeling software tends to use the "method of moments," in which each wire in the system is broken into 1 to N segments, and the current in each segment is calculated.

Some common programs

Some years ago an antenna modeling program came on the scene. Developed by the Navy, this program used numerical methods to perform the complex calculations needed to model an antenna. Called the *Numerical Electromagnetic Computation* (NEC) *program,* a smaller version soon became available known as miniNEC (which runs on PCs). You can download miniNEC-3 from several sources in the amateur radio newsgroups in the United States or United Kingdom, or from the Navy Postgraduate School Web site. A miniNEC-4 version is also available, but I understand that it requires a license to use and cannot be exported without a permit from the U.S. government.

There are also a number of private vendors who offer the miniNEC at a price. Some of the better vendors offer their own versions, based on the miniNEC concept, but with some value added to make it worthwhile to buy theirs instead of using the "freebie" version.

The miniNEC programs model wire antennas using the coordinate system shown in Fig. 17-1. This is a standard three-dimensional Cartesian coordinate system in which the y axis is horizontal, the z axis is vertical, and the x axis is orthogonal to both the y and z axes. The idea is to specify the starting and ending points of the wires making up the antenna in terms of the xyz coordinate system. Figure 17-2 shows a single-wire antenna laid out in the x axis. This axis is in the horizontal plane but orthogonal to the y axis. The antenna designer will specify X_1 and X_2, which are the starting and ending points of the wire.

The antenna can consist of a large number of wires, although the larger the number, the longer is the processing time. Each wire is broken into a number of different segments for calculation purposes.

NEC-4

The NEC-4 software is the latest in the NEC series and is proprietary to the University of California, from whom a license must be obtained to use it. Because of national defense considerations, an export license is required to take NEC-4 overseas. The NEC-4 software will produce modeling of underground radials, elements of varying diameter, and carefully constructed close-spaced parallel wires.



17-1 *XYZ* coordinate system for NecWin modeling software.

EZNEC Professional

Roy Lewallen, W7EL, provides the EZNEC Pro software. This software has an option for NEC-4, provided that the license is obtained from the University of California (again, export restrictions apply).

GNEC

Nittany-Scientific makes a version of NEC-4 known as GNEC. It permits the use of catenary wires, helices, networks, and other possibilities. Outputs include 3-D, polar plots, and rectangular plot graphs, as well as a large array of tabular reports.



17-2 Example of a single wire laid out on *XYZ* coordinate system.

NEC-2

This is a high-capability version of the NEC software, and it is in the public domain. It is limited to antenna elements of constant diameter, although some software providers who base their wares on NEC-2 provide corrections for multidiameters. It is fitted with the Sommerfield-Norton ground model for modeling horizontal wires close to the earth's surface.

NECWin Plus

This software is provided by Nittany-Scientific. It features true spreadsheet geometry. The software also offers stepped-diameter corrections, a gain-averaging test, a

CAD file (*.dxf), 2-D and 3-D plots, 2-D and 3-D antenna views, and certain graphic outputs. There are two versions, NECWin Pro and NECWin Basic (NECWin Basic is reviewed in this chapter).

EZNEC for Windows

Roy Lewallen's EZNEC for Windows is available in both NEC-2 and NEC-4 versions, although the NEC-4 version requires a license from the University of California to operate. It offers 2-D and 3-D plots, 3-D plots with 2-D slicing, ground-wave output, stepped-diameter correction, and various shortcuts to antenna modeling. The standard EZNEC is limited to 500 segments (the Pro version handles a much larger number of segments).

Expert MiniNEC

This new version of MiniNEC can handle sharp angles in antenna geometry directly and handles antennas close to the ground much more accurately than MiniNEC. Several versions of Expert MiniNEC are available from EM Scientific. These are MiniNEC for Windows and MiniNEC Broadcast Professional.

MiniNEC

MiniNEC Version 3.13 is the latest of the public-domain MiniNEC code. It runs on a PC in the DOS mode. It handles element lengths of changing diameter. Horizontal antennas must be at least 0.2λ above ground for accurate results to occur.

NEC4Win95

Orion (Canada) offers a Windows 95/98 version of MiniNEC known as NEC4Win95. It offers spreadsheet antenna geometry input, pull-down boxes for all other antenna parameters, and a pattern-plotting routine that includes lobe identification and bandwidth.

NECWin Basic

Many amateur and professional users have been increasingly dissatisfied with the commercial miniNEC-based antenna modeling programs on the market (mostly because they only run in the DOS environment and are clumsy to use). A low-cost Windows-based modeling program is NecWin Basic for Windows. This program appears to be a DOS-based NEC engine run with a Windows graphic user interface written in Visual Basic 3.0. The vendor offering NecWin Basic for Windows is Nittany Scientific, Inc. [Airline Highway, Suite 361, Hollister, CA, 95023-5621; phone: (408) 634-0573; Web site: *www.nittany-scientific.com*]. The basic version (which I test drove and now use) costs less than $100, and there is a professional version for a higher price.

NecWin Basic for Windows allows you to specify the geometry of the antenna in the *xyz* coordinate system. This process is made a lot easier by the fact that it uses a "spreadsheet-like" grid (Fig. 17-3). Once the geometry is entered, you can select from several different ground situations (including "none" for free-space calculations), the operating frequency, and units of measure used for the antenna wires (meters is default). You also can customize the calculations using the "Output" button. Once the geometry and parameters are entered, you can visualize the geometry in "stick form" using the "Eye" button on the toolbar. The "Traffic Light" button performs the NEC calculations, whereas the “Polar Coordinates” button creates the elevation and azimuth pattern graphics. When you “Save Screen” in the “File” menu, you will produce a bitmap (*.bmp) file of the pattern.

The particular geometry entered in Fig. 17-3 is for a long-wire antenna (Fig. 17-4) that is two wavelengths long and has a quarter-wavelength radial used as a counterpoise ground. There are no wires in the y and z planes, so the values of Y_1, Y_2, Z_1, and Z_2 are zero. The antenna is described with the coordinates $X_1 = 0.000$ and $X_2 = 14.56$ m. The operating frequency is set to 25-MHz on another screen. When the NEC calculations are made and the patterns displayed, the azimuth (Fig. 17-5) and elevation (Fig. 17-6) patterns can be printed out.


NEC-WIN [LONGWIR1]
File Edit Options Settings Help
Comments
Ground
Frequency
Output
Units: meters

Wire	X1	Y1	Z1	X2	Y2	Z2	Dia.	Seg.	Src/Ld	Conduct
1	.0000	.0000	.0000	14.5600	.0000	.0000	14 AWG	13	1/0	Perfect
2										

17-3 NecWin screen.



17-4 Off-center fed doublet antenna.



17-5 Modeled horizontal pattern.

NecWin Basic for Windows also will print out a data table of the frequency, wavelength, and VSWR. You can set the starting frequency, number of calculations, and step frequency.

If there is any criticism of the NecWin Basic for Windows program, it is that it does not graph the VSWR versus frequency curve. This is a little harder in Visual Basic 3.0 than in later versions, but users who also have Microsoft Excel on their computers can hand enter the numbers from the NecWin Basic for Windows output report and get a chart similar to Fig. 17-7.

The low price of NecWin Basic for Windows makes it useful to amateur radio operators, shortwave and scanner enthusiasts, and other amateur antenna builders. If



17-6 Modeled vertical pattern.

you are serious about antennas, then you need to obtain this software. It will perform well for many professional users, as well as student users in schools. However, professional users might want to consider buying the higher-priced NecWin Professional for Windows version.

EZNEC for Windows

Roy Lewallen, W7EL, produces the EZNEC for Windows software. The software extends Roy's earlier work on DOS versions of EZNEC but is still based on the NEC-2 engine (a NEC-4 professional version is available for those with the required license from the University of California).

Figure 17-8 shows the basic window that opens when you open an antenna project (in this case, a 10-MHz dipole). Given in the active window are file name, frequency, wavelength (in meters), number of wires and segments, number of sources, number of loads, transmission lines, ground type, wire loss, the units being calculated



17-7 VSWR curve of the modeled antenna.


My Computer
My Documents
Recycle Bin
FREE! Instant Messenger
Internet Explorer
McAfee VirusSc...
eFax Messenger
MSDN Library - January 2000
Explorer
EZNEC v. 3.0
File Options Outputs Plot Setups View Utilities Help
Open
Save As
Currents
Src Dat
Load Dat
FF Tab
NF Tab
SWR
View Ant
FF Plot
Start
14:55

Dipole in free space

File	Dipole1.ez
Frequency	10 MHz
Wavelength	29.9793 m
Wires	1 Wire, 11 segments
Sources	1 Source
Loads	0 Loads
Trans Lines	0 Lines
Ground Type	Free Space
Wire Loss	Zero
Units	Meters
Plot Type	Azimuth
Elevation Angle	0 Deg.
Step Size	1 Deg.
Ref Level	0 dBi
Alt SWR Z0	75 ohms

17-8 Basic window of EZNEC for Windows.

(meters, feet, etc.), plot type (azimuth, elevation), elevation angle, step size, a reference level, and an alternate SWR Z_o.

There are command buttons to the left of the main window. These include Open, Save As, Currents, Sto Dat, Load Dat, FF Tab, NF Tab, SWR, View Antenna, and FF Plot. The "View Antenna" button provides a view of the *xyz* coordinate system along with the wires (Fig. 17-9). The "FF Plot" button plots the far field of the antenna, and the "SWR" button plots the SWR curve based on parameters you give it (starting frequency, stopping frequency, frequency step).

The "View Antenna" window is shown in Fig. 17-9. This antenna view provides the *xyz* coordinate system, along with the wires. There are scroll bars to the left of the main window where the antenna appears that are used to vary the image to better see it. A series of three "Reset" buttons resets the image to the initial setting.

If you wish to plot the radiation pattern (azimuth or elevation) of the antenna, then press "FF Plot" in the main window. The result will be as shown in Fig. 17-10. Some data appears in the lower window on the plot. The data in this case are elevation angle, outer ring gain, slice gain maximum, front-to-side ratio, beamwidth, side-


View Antenna: Dipole in free space
File Edit View Options Reset
Zoom
Display
Current
Reset
Reset
Move Image
X
Y
Z
Reset
☐ Center Ant Image
EZNEC
Z
X
Y
Start
Mi...
Ex...
Vi...
E...
V...
15:00

No wires selected

17-9 View Antenna window of EZNEC for Windows.



Azimuth Plot
Elevation Angle 0.0 deg.
Outer Ring 1.75dBi

Slice Max Gain 1.75 dBi @ Az Angle = 0.0 deg.
Front/Side 99.99 dB
Beamwidth 89.8 deg.; -3dB @ 315.1, 44.9 deg.
Sidelobe Gain 1.75 dBi @ Az Angle = 180.0 deg.
Front/Sidelobe 0.0 dB

Cursor Az 0.0 deg.
Gain 1.75 dBi
0.0 dBmax

17-10 Result of pressing "FF Plot" button in main window of EZNEC for Windows.

lobe gain, front/sidelobe, cursor azimuth, and gain. You can print out the plot of the radiation pattern with either the data present or the data hidden.

One of the really nice things about EZNEC for Windows is the availability of VSWR plots without going to the professional edition. Figure 17-11 shows the plot for the dipole under consideration. Note that the data given include the starting frequency, the SWR at the starting frequency, the impedance at the starting frequency, the reflection coefficient at the starting frequency, and the source impedance.

References

Burke, G. J., and A. J. Poggio, "Numerical Electromagnetics Code (NEC)—Method of Moments," Naval Ocean Systems Center Technical Document 116, January 1981.

King, R. W. P., *Tables of Antenna Characteristics,* IFI/Plenum Data Corporation, New York, 1971.

Prasad, S., and R. W. P. King, "Experimental Study of L-, T- and Related Transmission Line Antennas," *Journal of Research of the National Bureau of Standards—D Radio Propagation,* Vol. 65D(5): 1961.


SWR Plot: Dipole in free space
File Edit View Options Reset
Z0
50 ohms
Alt (75 ohms)
1
Source #
INF
10
5
SWR
3
2
1.5
1.1
1
9.5
Freq MHz
10.5
Start
15:08

Freq 9.5 MHz
SWR 5.47
Z 62.11 - j 105.9 ohms
Refl Coeff 0.6911 at -40.11 deg.
Source # 1
Z0 50 ohms

17-11 VSWR plot of a dipole with EZNEC for Windows.

Rockway, J. W., and J. C. Logan, MiniNEC Professional for Windows, EM Scientific, Inc., Carson City, NV, 1995.

Rockway, J. W., and J. C. Logan, MiniNEC Broadcast Professional for Windows, EM Scientific, Inc., Carson City, NV, 1996.

Rockway, J. W., and J. C. Logan, "Advances in MiniNEC," *IEEE Antennas and Propagation Magazine,* 37(4): 1995.

18
CHAPTER

VHF/UHF transmitting and receiving antennas

THE VHF/UHF SPECTRUM IS COMMONLY ACCEPTED TO RANGE FROM 30 MHZ TO 900 MHZ, although the upper breakpoint is open to some differences of opinion. The VHF spectrum is 30 MHz to 300 MHz, and the UHF spectrum is 300 MHz to 900 MHz. Above 900 MHz is the microwave spectrum. These bands are used principally for local "line-of-sight" communications, according to the standard wisdom. However, with the advent of OSCAR satellites, the possibility of long-distance direct communications is a reality for VHF/UHF operators. In addition, packet radio is becoming common; this means indirect long-distance possibilities through networking. For the low end of the VHF spectrum (e.g., 6-m amateur band), long-distance communications are a relatively common occurrence.

In many respects, the low-VHF region is much like the 10-m amateur band and 11-m Citizens Band: skip is not an infrequent occurrence. Many years ago, I recall an event where such skip caused many a local police officer to skip a heart beat. In those days, our police department operated on 38.17 MHz, which is between the 6-m and 10-m amateur bands. They received an emergency broadcast concerning a bank robbery at a certain Wilson Boulevard address. After a race to the county line, they discovered that the reported address would be outside of the county, and in fact did not exist even in the neighboring county (a number was skipped). The problem was traced to a police department in a southwest city that also had a Wilson Boulevard, and for them the alarm was real.

The principal difference between the lower frequencies and the VHF/UHF spectrum is that the wavelengths are shorter in the VHF/UHF region. Consider the fact that the wavelengths for these bands range from 10 m to 1 m for the VHF region, and from 1 m to 33 cm for the UHF region. Most antenna designs are based on wavelength, so that fact has some implications for VHF/UHF antenna design. For example, because bandwidth is a function of length/diameter ratio for many classes of antenna, broadbanding an antenna in the VHF/UHF region is relatively easy. If, say, 25-mm (i.e., 1-in) aluminum tubing is used to make a quarter-wavelength vertical, then the approximate *L/D* ratio is 790 in the 8-m band and 20 in the 2-m band. This feature is fortunate, because the VHF/UHF bands tend to be wider than the HF bands.

Copyright 2001 - the McGraw-Hill Companies

Another point to make is that many of the mechanical chores of antenna design and construction become easier for VHF/UHF antennas. One good example is the delta impedance-matching scheme. At 80 m, the delta-match dimensions are approximately 36 × 43 ft, and at 2 m they are 9.5 × 12 *inches.* Clearly, delta matching is a bit more practical for most users at VHF than at HF.

Types of antennas usable for VHF/UHF

The concept "VHF/UHF antenna" is only partially valid because virtually all forms of antenna can be used at HF, MW, and VHF/UHF. The main limitations that distinguish supposedly VHF/UHF designs from others are mechanical: there are some things that are simply much easier to accomplish with small antennas. Besides the delta match mentioned previously, there is the ease of construction for multielement antennas. A 14-element 20-m beam would be a wonderful thing to have in a QRM-laden DX pile-up, but is simply too impractical for all but a few users because of its size. If you look on embassy rooftops around the world you will see many-element Yagi and log periodic HF antennas supported on massive towers…and some of them use a standard Size 25 tower (common for amateur use) as the *antenna boom*! A 14-element 80/75-m Yagi approaches impossibility. But at 2 m, a 14-element Yagi beam antenna can be carried by one person, in one hand, unless the wind is acting up.

Safety note Large array beams, even at VHF/UHF, have a relatively high "windsail area," and even relatively modest winds can apply a lot of force to them. I once witnessed a large, strong technician blown off a ladder by wind acting on a modest, "suburban" sized, TV antenna. *It can happen to you, too. So always install antennas with a helper, and use hoists and other tools to actually handle the array.*

Lower band antennas on VHF/UHF

Between 1958 and 1962, a friend and I had access to a radio club amateur radio station in a Red Cross chapter house in Virginia. The "antenna farm" consisted of a 14-element 2-m beam, a three-element triband HF beam (10, 15, and 20 m), and a five-band (80 to 10 m) trap dipole. All of the coaxial cables came into the station through a wall; they were kept disconnected and shorted out when not in use because of the senior Red Cross official's concern over lightning.

One night, attempting to connect the 2-m beam to the Gonset "gooney box" 2-m AM transceiver, my friend accidentally used the cable from the five-band trap dipole instead. We worked a lot of stations that contest weekend, and scored lots of points. Later, we discovered the error, and asked a more technically competent adult (we were teenagers), "Why the good reports?" He then gave us a lesson in longwire antenna theory. A good longwire is many wavelengths long. Consider that a half-wave antenna on 2 m is 80 m/2 m or 40 wavelengths shorter than an 80-m half-wave antenna. Thus, the 80-m antenna, counting foreshortening of physical lengths because of the traps, was on the order of 35 to 38 wavelengths long on 2 m. We had a highly directional, but multilobed, pattern.

Similarly, 40- to 10-m and 80- to 10-m trap verticals are often usable on VHF/UHF frequencies without any adjustments. Similarly, Citizens Band 11-m antennas, many of which are $\frac{5}{8}$-wavelength (18 ft high), will sometimes work on VHF frequencies. Check the VSWR of an HF antenna on 2 m with a reliable VHF/UHF VSWR meter (or RF wattmeter) to discover the truth about any particular antenna. Always use the low-power setting on the transmitter to limit damage in cases where the specific antenna is not usable on a specific frequency.

The lesson to be learned is that antennas are often usable on frequencies much higher than the design frequency, even though useless on nearby bands. Care must be exercised when initially checking out the antenna, but that is not an inordinate difficulty.

VHF/UHF antenna impedance matching

The VHF/UHF antenna is no more or less immune from the need for impedance matching than lower-frequency antennas. However, some methods are easier (coax baluns, delta match, etc.) and others become either difficult or impossible. An example of the latter case is the tuned *LC* impedance-matching network. At 6 m, and even to some limited extent 2 m, inductor and capacitor *LC* networks can be used. But above 2 m other methods are more reasonable. We can, however, mimic the *LC* tuner by using stripline components, but that approach is not always suited to amateur needs.

The balun transformer makes an impedance transformation between *bal*anced and *un*balanced impedances. Although both 1:1 and 4:1 impedance ratios are possible, the 4:1 ratio is most commonly used for VHF/UHF antenna work. At lower frequencies it is easy to build broadband transformer baluns, but these become more of a problem at VHF and above.

For the VHF/UHF frequencies, a 4:1 impedance ratio coaxial balun (Fig. 18-1A) is normally used. Two sections of identical coaxial cable are needed. One section (*A*) has a convenient length to reach between the antenna and the transmitter. Its characteristic impedance is Z_o. The other section (*B*) is a half-wavelength long at the center of the frequency range of interest. The physical length is found from

$$L = \frac{5904\,V}{F_{\mathrm{MHz}}} \qquad \textbf{[18.1]}$$

where

L is the cable length, in inches
F_{MHz} is the operating frequency, in megahertz
V is the velocity factor of the coaxial cable

The velocity factors of common coaxial cables are shown in the following table.

Coaxial cable velocity factors

Regular polyethylene	0.66
Polyethylene foam	0.80
Teflon	0.72



$$L = \frac{5904\ V}{F_{\text{MHz}}}\ \text{Inches}$$

18-1A Coaxial 4:1 balun transformer.

Example 18-1 Calculate the physical length required of a 146-MHz 4:1 balun made of polyethylene foam coaxial cable.

Solution:

$$L = \frac{5904\ V}{F_{\text{MHz}}}$$

$$= \frac{(5904)\ (0.80)}{146\ \text{MHz}}$$

$$= \frac{4723.2}{146\ \text{MHz}} = 32.4\ \text{in}$$

A mechanical method of joining the coaxial cables is shown in Fig. 18-1B. In this example, three SO-239 coaxial receptacles are mounted on a metal plate. This arrangement has the effect of shorting together the shields of the three ends of coaxial cable. The center conductors are connected in the manner shown. This method is used especially where a mounting bracket is available on the antenna. The lengths of coaxial cable need PL-259 coax connectors installed in order to use this method.

The "delta match" gets its name from the fact that the structure of the matching element has the shape of the Greek letter delta, or a triangle. Figure 18-2A shows the basic delta match scheme. The matching element is attached to the driven element of the antenna (symmetrically, about the center point of the antenna). The width (A) of the delta match is given by

$$L = \frac{1416}{F_{\text{MHz}}}\ \text{in} \qquad \textbf{[18.2]}$$

While the height of the match (B) is

$$L = \frac{1776}{F_{\text{MHz}}}\ \text{in} \qquad \textbf{[18.3]}$$

The transmission line feeding the delta match is balanced line, such as parallel transmission line or twin lead. The exact impedance is not terribly critical because the dimensions (especially A) can be adjusted to accommodate differences. In general, however, either 450- or 600-Ω line is used, although 300-Ω line can also be used. Figure 18-2B



18-1B Practical implementation of 4:1 balun using connectors.


L
A
D
D
B
Center line
Delta match
600-Ω line

$$L = \frac{468}{F_{\mathrm{MHz}}}$$

$$A = \frac{118}{F_{\mathrm{MHz}}} = 2D$$

$$B = \frac{148}{F_{\mathrm{MHz}}}$$

18-2A Delta feed matching system.


Center
Driven element
Metal rods
BALUN

18-2B Practical VHF delta match.

shows a method for using coaxial cable with the delta match. The impedance is transformed in a 4:1 balun transformer (see Fig. 18-1A). The elements of the delta match can be made from brass, copper, or aluminum tubing, or a bronze brazing rod bolted to the main radiator element.

A stub-matching system is shown in Fig. 18-3. In this case, the impedance transformation is accomplished despite the half-wavelength shorted stub of transmission line. The exact impedance of the line is not very critical, and is found from

$$Z_o = 276 \log_{10} \frac{2S}{d} \qquad \textbf{[18.4]}$$

The matching stub section is made from metal elements such as tubing, wire, or rods (all three are practical at VHF/UHF frequencies). For a $\frac{3}{16}$-in rod, the spacing is approximately 2.56 in to make a 450-Ω transmission line. A sliding short circuit is used to set the electrical length of the half-wave stub. The stub is tapped at a distance



18-3 Stub matching.

from the antenna feedpoint that matches the impedance of the transmission line. In the example shown, the transmission line is coaxial cable, so a 4:1 balun transformer is used between the stub and the transmission line. The two adjustments to make in this system are: (1) the distance of the short from the feedpoint and (2) the distance of the transmission line tap point from the feedpoint. Both are adjusted for minimum VSWR.

The gamma match is basically a half delta match, and operates according to similar principles (Fig. 18-4). The shield (outer conductor) of the coaxial cable is connected to the center point of the radiator element. The center conductor of the coaxial cable series feeds the gamma element through a variable capacitor.

VHF/UHF antenna examples

Although it is probably not necessary to reiterate the point, VHF/UHF antennas are not substantially different from HF antennas, especially those for the higher bands. However, for various practical reasons there are several forms that are specially suited, or at least popular, in the VHF/UHF bands. In this section we will take a look at some of them.

Coaxial vertical

The coaxial vertical is a quarter-wavelength vertically polarized antenna that is popular on VHF/UHF. There are two varieties. In Fig. 18-5A we see the coaxial antenna made with coaxial cable. Although not terribly practical for long-term installation, the coax-coax antenna is very useful for short-term, portable, or emergency applications. For example, a boater found himself adrift, and in dire trouble, after a storm damaged the boat. The mast-top VHF antenna was washed away, leaving only the end of the coaxial cable dangling loose. Fortunately, the boat operator was a two-way radio technician, and he knew how to strip back the coaxial cable to make an impromptu coaxial vertical.

The coax-coax antenna shown in Fig. 18-5A uses a quarter-wavelength radiator and a quarter-wavelength sleeve. The sleeve consists of the coax braid stripped back and folded down the length of the coax cable. The maximum length is found from the equation below (actual length is trimmed from this maximum):



18-4 Gamma matching.


Seal end with RTV or caulk
Center conductor with insulation left on
Seal with RTV or caulk
Coax braid folded back
Seal with solder
To XMTR
λ/4
λ/2
λ/4

18-5A Coaxial vertical based on coaxial cable.

$$L = \frac{2952\ V}{F_{\text{MHz}}}\ \text{in} \qquad \textbf{[18.5]}$$

The antenna is mounted by suspending it from above by a short piece of string, twine, or fishing line. From a practical point of view, the only problem with this form of antenna is that it tends to deteriorate after a few rainstorms. This effect can be reduced by sealing the end, and the break between the sleeve and the radiator, with either silicone *RTV* or bathtub caulk.

A more permanent method of construction is shown in Fig. 18-5B. The sleeve is a piece of copper or brass tubing (pipe) about 1 in in diameter. An end cap is fitted over the end and sweat-soldered into place. The solder is not intended to add mechanical strength, but rather to prevent weathering from destroying the electrical contact between the two pieces. An SO-239 coaxial connector is mounted on the end cap. The coax is connected to the SO-239 inside the pipe, which means making the connection before mounting the end cap.


Radiator element
Insulator
PL-259
End cap
Pipe
λ/4
λ/4

18-5B Tubing coaxial vertical.

The radiator element is a small piece of tubing (or brazing rod) soldered to the center conductor of a PL-259 coaxial connector. An insulator is used to prevent the rod from shorting to the outer shell of the PL-259. (Note: an insulator salvaged from the smaller variety of banana plug can be shaved a small amount with a fine file and made to fit inside the PL-259. It allows enough center clearance for $\frac{1}{8}$-inch or $\frac{3}{16}$-inch brass tubing.)

Alternatively, the radiator element can be soldered to a banana plug. The normal-size banana plug happens to fit into the female center conductor of the SO-239.

Collinear vertical

Gain in antennas is provided by *directivity.* In other words, by taking the power radiated by the antenna, and projecting it into a limited direction, we obtain the appearance of higher radiated power. In fact, the *effective radiated power* (ERP) of the antenna is merely its feedpoint power multiplied by its gain. Although most antenna patterns are shown in the horizontal dimension (as viewed from above), it is also possible to obtain gain by compressing the vertical aspect. In this manner it is possible to have a vertical antenna that produces gain. Figure 18-6 shows a collinear gain antenna, with vertical polarization and a horizontally omnidirectional pattern. Incidentally, when mounted horizontally the pattern becomes bidirectional.

The collinear antenna shown in Fig. 18-6 is basically a pair of stacked collinear arrays. Each array consists of a quarter-wavelength section *A* and a half-wavelength section *C* separated by a quarter-wavelength phase reversing stub *B.* The phase reversal stub preserves in-phase excitation for the outer element (referenced to the inner element).

The feedpoint is between the two elements of the array (i.e., between the *A* sections). The coaxial-cable impedance is transformed by a 4:1 balun transformer (see Fig. 18-1A). Alternatively, 300-Ω twin lead can be used for the transmission line. If this alternative is used, then the use of UHF shielded twin lead is highly recommended. If the transmitter lacks the balanced output needed to feed twin lead, then use a balun at the input end of the twin lead (i.e., right at the transmitter).

Yagi antennas

The Yagi beam antenna is a highly directional gain antenna, and is used both in HF and VHF/UHF systems. The antenna is relatively easy to build at VHF/UHF. In fact, it is easier than for HF systems. The basic Yagi was covered in Chap. 12, so we will only show examples of practical VHF devices. A 6-m Yagi antenna is shown in Fig. 18-7. This particular antenna is a four-element model. The reflector and directors can be mounted directly to a metallic boom, because they are merely parasitic. The driven element, however, must be insulated from the metal boom.

The driven element shown in Fig. 18-7 is a folded dipole. While this is common practice at VHF, because it tends to broadband the antenna, it is not strictly necessary. The dimensions of the driven element are found from Eq. 18.4. Set the equation equal to 300 Ω, select the diameter of the tubing from commercially available sources, and then calculate the spacing.

Example 18-2 Calculate the spacing of a 300-Ω folded dipole when $\frac{3}{4}$-in tubing is used in its construction.



C
38 in
B
1 in.
19.5 in
19 in
A
VHF balun
4:1
Coax to XMTR
A
19 in
19.5 in
1 in.
B
C
38 in

18-6 Vertical collinear antenna.


2.62 m
Director No. 2
144.8 cm
2.67 m
Director No. 1
116.9 cm
2.79 m
Driven element
4:1
VHF balun
116.8 cm
Coax to XMTR
Reflector
2.95 m

18-7 Six-meter beam antenna.

Solution:

$$Z_o = 276 \log_{10} \frac{2S}{d}$$

$$300\ \Omega = 276 \log_{10} \frac{2S}{d}$$

$$\frac{300}{276} = \log_{10} \frac{2S}{d}$$

$$1.08 = \log_{10} \frac{2S}{d}$$

$$10^{1.08} = \frac{2S}{d}$$

Using 0.75-in pipe results in

$$10^{1.08} = \frac{2S}{0.75}$$

$$12.02 = 2.67S$$

so

$$S = 4.5 \text{ in}$$


F
E
D
C
B
A
30 cm
30 cm
30.5 cm
31 cm
50 cm
2×2 Wood
Director no. 4
Director no. 3
Director no. 2
Director no. 1
Driven element
Reflector
Coax (see text)
Mast
A:102 cm
B:98 cm
C:91.5 cm
D:90 cm
E:89 cm
F:88 cm
Tie wire
Solder
2×2 Boom
Solder

18-8 Two-meter vertical beam.

Two-meter yagi

Figure 18-8 shows the construction details for a six-element 2-meter Yagi beam antenna. This antenna is built using a 2 × 2-in wooden boom and elements made of either brass or copper rod. Threaded brass rod is particularly useful, but not strictly necessary. The job of securing the elements (other than the driven element) is easier when threaded rod is used, because it allows a pair of hex nuts, one on either side of the 2 × 2-in boom, to be used to secure the element. Nonthreaded elements can be secured with RTV sealing a press-fit. Alternatively, tie wires (see inset to Fig. 18-8) can be used to secure the rods. A hole is drilled through the 2 × 2 to admit the rod or tubing. The element is secured by wrapping a tie wire around the rod on either side of the 2 × 2, and then soldering it in place. The tie wire is no. 14 to no. 10 solid wire.

Mounting of the antenna is accomplished by using a mast secured to the boom with an appropriate clamp. One alternative is to use an end-flange clamp, such as is sometimes used to support pole lamps, etc. The mast should be attached to the boom at the center of gravity, which is also known as the *balance point.* If you try to balance the antenna in one hand unsupported, there is one (and only one) point at which it is balanced (and won't fall). Attach the mast hardware at, or near, this point in order to prevent normal gravitational torques from tearing the mounting apart.

The antenna is fed with coaxial cable at the center of the driven element. Ordinarily, either a matching section of coax, or a gamma match, will be needed because the effect of parasitic elements on the driven element feedpoint impedance is to reduce it.

$\frac{5}{8}$-wavelength 2-m antenna

The $\frac{5}{8}$-wavelength antenna (Fig. 18-9) is popular on 2 m for mobile operation because it is easy to construct, and it provides a small amount of gain relative to a dipole. The radiator element is $\frac{5}{8}$-wavelength, so its physical length is found from:

$$L = \frac{7380}{F_{\mathrm{MHz}}} \text{ in} \tag{18.6}$$

The $\frac{5}{8}$-wavelength antenna is not a good match to any of the common forms of coaxial cables. Either a matching section of cable, or an inductor match, is normally used. In Fig. 18-9 an inductor match is used. The matching coil consists of 2 to 3 turns of no. 12 wire, wound over a $\frac{1}{2}$-in OD form, $\frac{1}{2}$-in long. The radiator element can be tubing, brazing rod, or a length of heavy "piano wire." Alternatively, for low-power systems, it can be a telescoping antenna that is bought as a replacement for portable radios or televisions. These antennas have the advantage of being adjustable to resonance without the need for cutting.

J-pole antennas

The *J-pole antenna* is another popular form of vertical on the VHF bands. It can be used at almost any frequency, although the example shown in Fig. 18-10 is for 2 m. The antenna radiator is $\frac{3}{4}$-wavelength long, so its dimension is found from

$$L = \frac{8838}{F_{\mathrm{MHz}}} \text{ in} \tag{18.7}$$

and the quarter-wavelength matching section length from

$$L = \frac{2952}{F_{\mathrm{MHz}}} \text{ in} \tag{18.8}$$

Taken together the matching section and the radiator form a parallel transmission line with a characteristic impedance that is 4 times the coaxial cable impedance. If 50-Ω coax is used, and the elements are made from 0.5 in OD pipe, then a spacing of 1.5 in will yield an impedance of about 200 Ω. Impedance matching is accomplished by a gamma match consisting of a 25-pF variable capacitor, connected by a clamp to the radiator, about 6 in (experiment with placement) above the base.


L
#12 Wire
2 to 3
turns
0.5 in. dia.
0.5 in. long

$$\text{For } \frac{5\lambda}{8};\ L_{\mathrm{FT}} = \frac{615}{F_{\mathrm{MHz}}}$$

$$L_{\mathrm{IN}} = \frac{7380}{F_{\mathrm{MHz}}}$$

18-9 $\frac{5}{8}$-wavelength 2-m antenna.


3λ/4
Insulator
λ/4 Matching section
λ/4
A
B
C
D
B
C
A
D
SO-239

18-10 J-pole antenna.

Groundplane

The *groundplane antenna* is a vertical radiator situated above an artificial RF ground consisting of quarter-wavelength radiators. Groundplane antennas can be either $\frac{1}{4}$-wavelength or $\frac{5}{8}$-wavelength (although for the latter case impedance matching is needed—see the previous example).

Figure 18-11 shows how to construct an extremely simple groundplane antenna for 2 m and above. The construction is too lightweight for 6-m antennas (in general), because the element lengths on 6-m antennas are long enough to make their weight too great for this type of construction. The base of the antenna is a single SO-239 chassis-type coaxial connector. Be sure to use the type that requires four small machine screws to hold it to the chassis, and not the single-nut variety.

The radiator element is a piece of $\frac{3}{16}$-in or 4-mm brass tubing. This tubing can be bought at hobby stores that sell airplanes and other models. The sizes quoted just happen to fit over the center pin of an SO-239 with only a slight tap from a lightweight hammer—and I do mean *slight* tap. If the inside of the tubing and the connector pin are pretinned with solder, then sweat soldering the joint will make a good electrical connection that is resistant to weathering. Cover the joint with clear lacquer spray for added protection.

The radials are also made of tubing. Alternatively, rods can also be used for this purpose. At least four radials are needed for a proper antenna (only one is shown in Fig. 18-11). This number is optimum because they are attached to the SO-239 mounting holes, and there are only four holes. Flatten one end of the radial, and drill a small hole in the center of the flattened area. Mount the radial to the SO-239 using small hardware (4-40, etc.).

The SO-239 can be attached to a metal L bracket. While it is easy to fabricate such a bracket, it is also possible to buy suitable brackets in any well-equipped hardware store. While shopping at one do-it-yourself type of store, I found several reasonable candidate brackets. The bracket is attached to a length of 2 × 2-in lumber that serves as the mast.

Halo antennas

One of the more saintly antennas used on the VHF boards is the halo (Fig. 18-12). This antenna basically takes a half-wavelength dipole and bends it into a circle. The ends of the dipole are separated by a capacitor. In some cases, a transmitting-type mica “button” capacitor is used, but in others (and perhaps more commonly), the halo capacitor consists of two 3-in disks separated by a plastic dielectric. While air also serves as a good (and perhaps better) dielectric, the use of plastic allows mechanical rigidity to the system.

Quad beam antennas

The quad antenna was introduced in the chapter on beams. It is, nonetheless, also emerging as a very good VHF/UHF antenna. It should go without saying that the antenna is a lot easier to construct at VHF/UHF frequencies than it is at HF frequencies! Figure 18-13 shows a modest example.

There are several methods for building the quad antenna, and Fig. 18-13 represents only one of them. The radiator element can be any of several materials,


3/16 In. (or 4-mm) brass tubing
L-bracket
2×2 Mast
Sweat solder
End flattened
SO-239
Radials (four or more)

18-11 Small VHF groundplane construction.



18-12 Halo antenna.

including heavy solid wire (no. 8 to no. 12), tubing, or metal rods. The overall lengths of the elements are given by:

Driven element:

$$L = \frac{11{,}826}{F_{\text{MHz}}}\ \text{in} \tag{18.9}$$

Reflector:

$$L = \frac{12{,}562}{F_{\text{MHz}}}\ \text{in} \tag{18.10}$$

Director:

$$L = \frac{11{,}248}{F_{\text{MHz}}}\ \text{in} \tag{18.11}$$

There are several alternatives for making the supports for the radiator. Because of the lightweight construction, almost any method can be adapted for this purpose. In the case shown in Fig. 18-13, the spreaders are made from either 1-in furring strips, trim strips, or (at above 2 m) even wooden paint stirring sticks. The sticks are cut to length, and then half-notched in the center (Fig. 18-13, detail B). The two spreaders for each element are joined together at right angles and glued (Fig. 18-13, detail C). The spreaders can be fastened to the wooden boom at points *S* in detail C. The usual rules regarding element spacing (0.15 to 0.31 wavelength) are followed. See the information on quad antennas in Chap. 12 for further details. Quads have been successfully built for all amateur bands up to 1296 MHz.

Overall lengths:

$$\text{Reflector: } L = \frac{12{,}562}{F_{\text{MHz}}} \text{ in}$$

$$\text{Director: } L = \frac{11{,}248}{F_{\text{MHz}}} \text{ in}$$

$$\text{Driven element: } L = \frac{11{,}826}{F_{\text{MHz}}} \text{ in}$$



18-13 Quad loop construction on VHF.

VHF/UHF scanner band antennas

The hobby of shortwave listening has always had a subset of adherents who listen exclusively to the VHF/UHF bands. In those bands are found a rich variety of services from commercial two-way radios, police and fire systems, and others. Many of these people are serious DXers, but others have a little of the voyeur in them (they like to listen to what's going on in the community by monitoring the police frequencies). As long as they neither respond to the scene of a police or fire action, nor use the information gained from monitoring in an illegal manner, they are perfectly free to listen in.

A few people have an unusually practical element to their VHF/UHF listening. At least one person known to the author routinely tunes in the local taxicab company's frequency as soon as she orders a cab. She then listens for her own address. She knows from that approximately when to expect the cab.

In the early 1960s, when all VHF monitor receivers were crystal-controlled (and relatively expensive), the listener had a very limited selection of frequencies to choose from. Having worked in various shops that sold those receivers, I can recall that most of our customers tended to be police officers, fire fighters (or volunteers), or journalists covering the local crime news. However, modern scanners operate on both major VHF bands (low and high), plus UHF bands and others.

Scanner-vision antennas

The antennas used by scanner listeners are widely varied, and (in some cases) overpriced. Although it is arguable that a total coverage VHF/UHF antenna is worth the money, and it probably is, there are other possibilities that should be considered.

First, don't overlook the use of television antennas for scanner monitoring! The television bands (about 80 channels from 54 MHz to around 800 MHz) encompass most of the ordinarily used scanner frequencies. Although antenna performance is not optimized for the scanner frequencies, it is also not "zero" on those frequencies. If you already have an "all channel" TV antenna installed, then it is a simple matter to connect the antenna to the scanner receiver. (Note: if the antenna uses 300-Ω twin lead, then install a 4:1 balun transformer that accepts 300 Ω in and produces 75 Ω out. These transformers are usually available at TV shops, video shops—including videotape rental places—and Radio Shack stores.)

The directional characteristic of the TV antenna makes it both an advantage and a disadvantage to the scanner user. If the antenna has a rotator, then there is no problem. Just rotate the antenna to the direction of interest. However, if the antenna is fixed, and the station of interest is elsewhere than where the antenna is pointed, then there is a bit of a problem. Nevertheless, some reception is possible for at least three reasons. One is that the main beam of the antenna is not infinitely thin, so the station of interest might well be within the beam—even if off the point a little bit. Second, there are always sidelobes on an antenna. These are areas outside of the main beam that offer reduced, but nonzero, reception characteristics. Finally, the sidelobes and main lobe of the antenna are optimized for the TV bands, and may not obtain the same directivity on certain scanner frequencies. It is, therefore, possible that a TV antenna will have an unusual lobe in the direction of interest for the scanner channel.

The TV antenna also offers other possibilities. The hardware and electronics, normally found useful on TV antenna systems, are also useful for scanner antennas. The use of the mounting hardware is obvious, but less obvious is the use of components such as multiset couplers, impedance transformers, and wideband amplifiers. For example, Fig. 18-14 shows two scanner antennas joined together into a single



18-14 Combining two antennas with TV hardware.



18-15 VHF/UHF "bowtie" dipoles for broadband reception**.**

transmission line using a two-set coupler. Although intended to allow two television sets to receive a signal from the same antenna, the device also works to combine two antennas into a single transmission line. Two popular TV uses include two antennas for different directions and VHF and UHF antennas that share the same downlead. Be sure to buy a weatherproof model if you intend to mount the coupler on the antenna mast (the correct place for it) (Fig. 18-15).

TV antenna amplifiers are used to increase the weak signal from a distant station to a level compatible with the TV receiver. Because these amplifiers are wideband designs, they will also work well for the scanner bands that are inclusive within the 54- to 800-MHz TV bands. Some models are intended to be part of the antenna, while others are mounted indoors, some distance from the antenna. The basic rule of thumb is to place the amplifier as close as possible to the "head end" of the system where the antenna is located. This situation will permit signals to be built up to a level considerably above the noise level before being attenuated in the transmission line losses.

TV/FM receiver folded dipoles made of twin-lead transmission line also work well at other VHF/UHF frequencies. Figures 18-16A and 18-16B show the details of their construction.

Scanner skyhooks

Other antennas not to be overlooked are the CB, or amateur radio, high-frequency (shortwave) antennas. Many amateur radio operators use their 80-m dipole antenna



18-16A Receiver folded dipole antenna made of 300 Ω twin lead.



18-16B Poles made of twin-lead transmission VHF frequencies.

on 2 m (144 to 148 MHz) and find that it has the gain and directivity characteristics of a longwire antenna. Similarly, with vertical "ham" and CB antennas, they have apparent gain on some VHF frequencies and will at least perform to some extent on others.

Even the lowly "random length" wire antenna used for your shortwave receiver ought to turn in decent performance as a VHF/UHF longwire antenna. These antennas are simply a 30- to 150-ft length of no. 14 wire attached to a distant support.

Figure 18-17 shows two variants to an antenna that is popular with VHF/UHF receiver operators: the *drooping dipole.* These antennas are similar to the inverted-vee dipole, in that they consist of two quarter-wavelength radiator elements. Unlike the ordinary dipole, the ends of the radiators, in the single-band drooping dipole of Fig. 18-17A, are lowered. The drooping dipole can be made using an SO-239 UHF coaxial connector as the support for either stiff wire, brass hobbyist tubing, or brazing rod elements cut to λ/4 each. The antenna can be made into a multiband, or very wideband, antenna by connecting several pairs of drooping dipoles in parallel, as in Fig. 18-17B.



18-17A Drooping dipole.



18-17B Multiband drooping dipole.



18-18A Vertical dipole.

The vertical dipole (Fig. 18-18A) also finds use in the VHF/UHF region. Each element is λ/4 long, and its physical length can be found from

$$L = \frac{2832}{F_{\text{MHz}}} \text{ in} \qquad \textbf{[18.12]}$$

This antenna can be built with the same types of materials as the drooping dipole. Although several different construction techniques are popular, the method of Fig. 18-18B is probably the most popular with homebrew builders.

A groundplane antenna for VHF/UHF frequencies is shown in Fig. 18-19. The antenna sits on an L bracket mounted to a 2 × 4-in wooden mast or support. The L bracket can be manufactured for the purpose, or purchased at Happy Harry's hardware emporium. The base of the antenna is a chassis-mount SO-239 UHF coaxial connector. A quarter-wave radiator element is made from $\frac{1}{8}$-in brass tubing, or brazing rod, soldered to the center conductor pin of the SO-239. Similarly, radials can be made from the same type of material, but soldered directly to the body of the SO-239 (this action connects it to the coaxial cable shield). The four mounting holes of the SO-239 make reasonable anchors for the radials. Solder them for electrical integrity.



18-18B Construction of VHF vertical dipole.

A coaxial vertical can be made from 1-in brass tubing or copper plumbing pipe, and either brazing rod or brass tubing (Fig. 18-20). The sleeve is fitted with an end cap that has an SO-239 mounted on it (see inset). The radiator element can be made with a mate to the SO-239, namely the PL-259 coaxial plug. The radiator element is soldered to the center conductor, and it is insulated from the shield. You can buy coaxial whips with this type of construction, so you may not have to actually build the radiator element.

Additional gain, about +3 dB, can be achieved by stacking VHF/UHF antennas together. Figure 18-21 shows a typical arrangement in which two half-wavelength dipole antennas are connected together through a quarter-wavelength harness of RG-59/U coaxial cable. This harness is shorter than a quarter wavelength by the velocity factor of the coaxial cable:


Brass tubing
or brazing
rod element
L-bracket
SO-239
Radials
Wooden
support

18-19 Construction of VHF groundplane for receivers.

$$L = \frac{2832V}{F_{\mathrm{MHz}}} \qquad \textbf{[18.13]}$$

where

L is the length, in inches
V is the velocity factor (typically 0.66 or 0.80 for common coax)
F_{MHz} is the frequency, in megahertz

The antennas can be oriented in the same direction to increase gain, or orthogonally (as shown in Fig. 18-21) to make it more omnidirectional.

Because the impedance of two identical dipoles, fed in parallel, is one-half that of a single dipole, it is necessary to have an impedance-matching section


Coax
thru
Pipe
end
cap
PL-259
Radiator
Cap
Sleeve
Coaxial cable

18-20 Coaxial dipole vertical.


λ/2
λ/4-RG-59/U
λ/2
λ/4-RG-58/U
Matching section
RG-59/U
Main transmission
line

18-21 Stacking VHF antennas.

made of RG-58/U coaxial cable. This cable is then fed with RG-59/U coax from the receiver.

There is nothing magical about scanner receivers that require any form of antenna that is significantly different from other VHF/UHF antennas. Although the designs might be optimized for VHF or UHF, these antennas are basically the same as others shown in this book. As a matter of fact, almost any antennas, from any chapter, can be used by at least some scanner operators.

19
CHAPTER

Microwave waveguides and antennas

THE MICROWAVE PORTION OF THE RADIO SPECTRUM COVERS FREQUENCIES FROM ABOUT 900 MHz to 300 GHz, with wavelengths in free-space ranging from 33 cm down to 1 mm. Transmission lines can be used at frequencies from dc to about 50 or 60 GHz, although, above 5 GHz, only short runs are practical, because attenuation increases dramatically as frequency increases. There are three types of losses in conventional transmission lines: *ohmic, dielectric,* and *radiation.* The ohmic losses are caused by the current flowing in the resistance of the conductors making up the transmission lines. Because of the skin effect, which increases resistance at higher frequencies, these losses tend to increase in the microwave region. Dielectric losses are caused by the electric field acting on the molecules of the insulator and thereby causing heating through molecular agitation. Radiation losses represent loss of energy as an electromagnetic wave propagates away from the surface of the transmission line conductor.

Losses on long runs of coaxial transmission line (the type most commonly used) cause concern even as low as the 400-MHz region. Also, because of the increased losses, power handling capability decreases at high frequencies. Therefore, at higher microwave frequencies, or where long runs make coax attenuation losses unacceptable, or where high power levels would overheat the coax, *waveguides* are used in lieu of transmission lines.

What is a waveguide? Consider the light pipe analogy depicted in Fig. 19-1. A flashlight serves as our "RF source," which (given that light is also an electromagnetic wave) is not altogether unreasonable. In Fig. 19-1A the source radiates into free space and spreads out as a function of distance. The intensity per unit area, at the destination (a wall), falls off as a function of distance (D) according to the *inverse square law* ($1/D^2$).

But now consider the transmission scheme in Fig. 19-1B. The light wave still propagates over distance D, but is now confined to the interior of a mirrored pipe. Almost all of the energy (less small losses) coupled to the input end is delivered to the output end, where the intensity is practically undiminished. Although not

Copyright 2001 - the McGraw-Hill Companies



19-1 Waveguide analogy to light pipe.

perfect, the light pipe analogy neatly summarizes, on a simple level, the operation of microwave waveguides.

Thus, we can consider the waveguide as an "RF pipe" without seeming too serenely detached from reality. Similarly, fiber-optic technology is waveguidelike at optical (IR and visible) wavelengths. In fact, the analogy between fiber optics and waveguide can withstand more rigorous comparison than the simplistic light pipe analogy.

The internal walls of the waveguide are not mirrored surfaces, as in our optical analogy, but are, rather, electrical conductors. Most waveguides are made of aluminum, brass, or copper. In order to reduce ohmic losses, some waveguides have their internal surfaces electroplated with either gold or silver, both of which have lower resistivities than the other metals mentioned above.

Waveguides are hollow metal pipes, and can have either circular or rectangular cross sections (although the rectangular are, by far, the most common). Figure 19-2 shows an end view of the rectangular waveguide. The dimension a is the wider dimension, and b is the narrower. These letters are considered the standard form of notation for waveguide dimensions, and will be used in the equations developed in this chapter.

Development of the rectangular waveguide from parallel transmission lines

One way of visualizing how a waveguide works is to develop the theory of waveguides from the theory of elementary parallel transmission lines (see Chap. 3). Figure 19-3A shows the basic parallel transmission line which was introduced in Chap. 3. The line consists of two parallel conductors separated by an air dielectric. Because air won't support the conductors, ceramic or other material insulators are used as supports.

There are several reasons why the parallel transmission line *per se* is not used at microwave frequencies. Skin effect increases ohmic losses to a point that is unacceptable. Also, the insulators supporting the two conductors are significantly more



19-2 Rectangular waveguide (end view).


A
Fields not confined in this direction
B
Field confined in this direction
End view of two wire line

19-3 Development of waveguide from parallel line.

lossy at microwave frequencies than at lower frequencies. Finally, radiation losses increase dramatically. Figure 19-3B shows the electric fields surrounding the conductors. The fields add algebraically (either constructively or destructively), resulting in pinching of the resultant field along one axis, and bulging along the other. This geometry increases radiation losses at microwave frequencies.

Now let's consider the quarter-wavelength shorted stub. The "looking-in" impedance of such a stub is infinite. When placed in parallel across a transmission line (Fig. 19-4A) the stub acts like an insulator. In other words, at its resonant frequency, the stub is a *metallic insulator,* and can be used to physically support the transmission line.

Again, because the impedance is infinite, we can connect two quarter-wavelength stubs in parallel with each other across the same points on the transmission line (Fig. 19-4B) without loading down the line impedance. This arrangement effectively forms a half-wavelength pair. The impedance is still infinite, so no harm is done. Likewise, we can parallel a large number of center-fed half-wavelength pairs along the line, as might be the case when a long line is supported at multiple points. The waveguide is analogous to an *infinite number of*



19-4A
Quarter-wave stub analogy.



19-4B
Quarter-wave stub analogy extended.



19-4C
Quarter-wave stub analogy extended even further.

center-fed "half-wave pairs" of quarter-wave shorted stubs connected across the line. The result is the continuous metal pipe structure of the common rectangular waveguide (Fig. 19-4C).

On first glance, relating rectangular waveguide to quarter-wavelength shorted stubs seems to fall down, except at the exact resonant frequency. It turns out, however, that the analogy also holds up at other frequencies, so long as the frequency is higher than a certain minimum cutoff frequency. The waveguide thus acts like a high-pass filter. There is also a practical upper frequency limit. In general, waveguides support a bandwidth of 30 to 40 percent of cutoff frequency. As shown in Fig. 19-5, the center line of the waveguide (which represents the points where the conductors are in the parallel line analogy) becomes a "shorting bar" between segments, and that "bar" widens or narrows according to operating frequency. Thus, the active region is still a quarter-wavelength shorted stub.

Below the cutoff frequency, the structure disappears entirely, and the waveguide acts like a parallel transmission line with a low-impedance inductive reactance shorted across the conductors. When modeled as a pair of quarter-wavelength stubs, the *a* dimension of the waveguide is a half-wavelength long. The cutoff frequency is defined as the frequency at which the *a* dimension is less than a half-wavelength.

Propagation modes in waveguides

The signal in a microwave waveguide propagates as an electromagnetic wave, not as a current. Even in a transmission line, the signal propagates as a wave because the current in motion down the line gives rise to electric and magnetic fields, which behave as an electromagnetic field. The specific type of field found in transmission lines, however, is a *transverse electromagnetic* (*TEM*) field. The term *transverse* implies things at right angles to each other, so the electric and magnetic fields are perpendicular to the direction of travel. In addition to the word "transverse," these right-angle waves are said to be "normal" or "orthogonal" to the direction of travel—three different ways of saying the same thing: right-angledness.


λ/4
λ/4
a
b
c
d
λ/4
λ/4
a
b
c
d
λ/4
λ/4
"a"
Dimension

A. Operating frequency

B. Increasing frequency

C. Decreasing frequency

19-5
Changing frequency does not affect the analogy.

Boundary conditions

The TEM wave will not propagate in a waveguide because certain *boundary conditions* apply. Although the wave in the waveguide propagates through the air (or inert gas dielectric) in a manner similar to free-space propagation, the phenomenon is bounded by the walls of the waveguide, and that implies certain conditions must be met. The boundary conditions for waveguides are

1. The electric field must be orthogonal to the conductor in order to exist at the surface of that conductor.
2. The magnetic field must not be orthogonal to the surface of the waveguide.

In order to satisfy these boundary conditions the waveguide gives rise to two types of propagation modes: *transverse electric mode* (TE mode), and *transverse magnetic mode* (TM mode). The TEM mode violates the boundary conditions because the magnetic field is not parallel to the surface, and so does not occur in waveguides.

The transverse electric field requirement means that the E field must be perpendicular to the conductor wall of the waveguide. This requirement is met by use of a proper coupling scheme at the input end of the waveguide. A vertically polarized coupling radiator will provide the necessary transverse field.

One boundary condition requires that the magnetic (H) field must not be orthogonal to the conductor surface. Because it is at right angles to the E field, it will meet this requirement (see Fig. 19-6). The planes formed by the magnetic field are parallel to both the direction of propagation and the wide dimension surface.

As the wave propagates away from the input radiator, it resolves into two components that are not along the axis of propagation, and are not orthogonal to the walls. The component along the waveguide axis violates the boundary conditions, so it is rapidly attenuated. For the sake of simplicity, only one component is shown in Fig. 19-7. Three cases are shown in Fig. 19-7: high, medium, and low frequency. Note that the angle of incidence with the waveguide wall increases as frequency drops. The angle rises toward 90° as the cutoff frequency is approached from above. Below the cutoff frequency the angle is 90°, so the wave bounces back and forth between the walls without propagating.



19-6 Magnetic fields in waveguide.



A. High frequency



B. Medium frequency



C. Low frequency
(approaching cutoff)

θ = ∠ of incidence
θ = ∠ of reflection

19-7
Frequency effect on propagating wave.

Coordinate system and dominant mode in waveguides

Figure 19-8 shows the coordinate system used to denote dimensions and directions in microwave discussions. The a and b dimensions of the waveguide correspond to the x and y axes of a cartesian coordinate system, and the z axis is the direction of wave propagation.

In describing the various modes of propagation, use a shorthand notation as follows:

$$Tx_{m,n}$$

where

x is E for transverse electric mode, and M for transverse magnetic mode
m is the number of half-wavelengths along the x axis (i.e., a dimension)
n is the number of half-wavelengths along the y axis (i.e., b dimension)

The TE_{10} mode is called the *dominant mode, and is the best mode for low attenuation propagation in the z axis*. The nomenclature TE_{10} indicates that there is one half-wavelength in the *a* dimension and zero half-wavelengths in the *b* dimension. The dominant mode exists at the lowest frequency at which the waveguide is a half-wavelength.

Velocity and wavelength in waveguides

Figures 19-9A and 19-9B show the geometry for two wave components, simplified for the sake of illustration. There are three different wave velocities to consider with respect to waveguides: *free-space velocity c, group velocity V_g,* and *phase velocity V_p.* The free-space velocity is the velocity of propagation in unbounded free space (i.e., the speed of light $c = 3 \times 10^8$ m/s).



19-8 Rectangular waveguide coordinate system.



19-9A Antenna radiator in capped waveguide.



19-9B Wave propagation in waveguide.

The *group velocity* is the straight line velocity of propagation of the wave down the center line (*z* axis) of the waveguides. The value of V_g is always less than c, because the actual path length taken, as the wave bounces back and forth, is longer than the straight line path (i.e., path *ABC* is longer than path *AC*). The relationship between c and V_g is

$$V_g = c \sin a \qquad \textbf{[19.1]}$$

where

V_g is the group velocity, in meters per second
c is the free-space velocity (3×10^8 m/s)
a is the angle of incidence in the waveguide

The *phase velocity* is the velocity of propagation of the spot on the waveguide wall where the wave impinges (e.g., point B in Fig. 19-9B). This velocity, depending upon the angle of incidence, can actually be faster than both the group velocity and the speed of light. The relationship between phase and group velocities can be seen in the beach analogy. Consider an ocean beach, on which the waves arrive from offshore at an angle other than 90°. In other words, the arriving wavefronts are not parallel to the shore. The arriving waves have a group velocity V_g. But as a wave hits the shore, it will strike a point down the beach first, and the "point of strike" races up the beach at a much faster phase velocity V_p, that is even faster than the group velocity. In a microwave waveguide, the phase velocity can be greater than c, as can be seen from Eq. 19.2:

$$V_p = \frac{c}{\sin a} \tag{19.2}$$

Example 19-1 Calculate the group and phase velocities for an angle of incidence of 33°.

Solution:

(*a*) *Group velocity*

$$\begin{aligned} V_g &= c \sin a \\ &= (3 \times 10^8)(\sin 33°) \\ &= (3 \times 10^8)(0.5446) = 1.6 \times 10^8 \text{ m/s} \end{aligned}$$

(*b*) *Phase velocity*

$$\begin{aligned} V_p &= c/\sin a \\ &= (3 \times 10^8 \text{ m/s})/\sin 33° \\ &= (3 \times 10^8 \text{ m/s})/(0.5446) \\ &= 5.51 \times 10^8 \text{ m/s} \end{aligned}$$

For this problem the solutions are

$$c = 3 \times 10^8 \text{ m/s}$$

$$V_p = 5.51 \times 10^8 \text{ m/s}$$

$$V_g = 1.6 \times 10^8 \text{ m/s}$$

We can also write a relationship between all three velocities by combining Eqs. 19.1 and 19.2, resulting in

$$c = \sqrt{V_p V_g} \qquad \textbf{[19.3]}$$

In any wave phenomenon the product of *frequency* and *wavelength* is the *velocity.* Thus, for a TEM wave in unbounded free space we know that:

$$c = F\lambda_o \qquad \textbf{[19.4]}$$

Because the frequency F is fixed by the generator, only the wavelength can change when the velocity changes. In a microwave waveguide we can relate phase velocity to wavelength as the wave is propagated in the waveguide:

$$V_p = \frac{\lambda \times c}{\lambda_o} \qquad \textbf{[19.5]}$$

where:

V_p is the phase velocity, in meters per second
c is the free-space velocity (3×10^8 m/s)
λ is the wavelength in the waveguide, in meters
λ_o is the wavelength in free space (c/F), in meters (see Eq. 19.4)

Equation 19.5 can be rearranged to find the wavelength in the waveguide:

$$\lambda = \frac{V_p \lambda_o}{c} \qquad \textbf{[19.6]}$$

Example 19-2 A 5.6-GHz microwave signal is propagated in a waveguide. Assume that the internal angle of incidence to the waveguide surfaces is 42 degrees. Calculate (*a*) phase velocity, (*b*) wavelength in unbounded free space, and (*c*) wavelength of the signal in the waveguide.

Solution:

(*a*) *Phase velocity*

$$\begin{aligned} V_p &= \frac{c}{\sin a} \\ &= \frac{3 \times 10^8 \text{ m/s}}{\sin 42°} \\ &= \frac{3 \times 10^8 \text{ m/s}}{0.6991} = 4.5 \times 10^8 \text{ m/s} \end{aligned}$$

(*b*) *Wavelength in free space*

$$\begin{aligned} \lambda_o &= c/F \\ &= (3 \times 10^8 \text{ m/s})/(5.6 \times 10^9 \text{ Hz}) \\ &= 0.054 \text{ m} \end{aligned}$$

(*c*) *Wavelength in waveguide*

$$\lambda = \frac{V_p \lambda_o}{c}$$

$$= \frac{(4.5 \times 10^8 \text{ m/s})(0.054 \text{ m})}{3 \times 10^8 \text{ m/s}} = 0.08 \text{ m}$$

Comparing, we find that the free-space wavelength is 0.054 m, and the wavelength inside of the waveguide increases to 0.08 m.

Cutoff frequency (F_c)

The propagation of signals in a waveguide depends, in part, upon the operating frequency of the applied signal. As covered earlier, the angle of incidence made by the plane wave to the waveguide wall is a function of frequency. As the frequency drops, the angle of incidence increases toward 90°.

The propagation of waves depends on the angle of incidence and the associated reflection phenomena. Indeed, both phase and group velocities are functions of the angle of incidence. When the frequency drops to a point where the angle of incidence is 90°, then group velocity is meaningless.

We can define a general mode equation based on our system of notation:

$$\frac{1}{(\lambda_c)^2} = \left(\frac{m}{2a}\right)^2 + \left(\frac{n}{2b}\right)^2 \qquad \textbf{[19.7]}$$

where

λ_c is the longest wavelength that will propagate
a, b are the waveguide dimensions (see Fig. 19-2)
m, n are integers that define the number of half-wavelengths that will fit in the a and b dimensions, respectively

Evaluating Eq. 19.7 reveals that the longest TE-mode signal that will propagate in the dominant mode (TE_{10}) is given by

$$\lambda_c = 2a \qquad \textbf{[19.8]}$$

from which we can write an expression for the cutoff frequency:

$$F_c = \frac{c}{2a} \qquad \textbf{[19.9]}$$

where

F_c is the lowest frequency that will propagate, in hertz
c is the speed of light (3×10^8 m/s)
a is the wide waveguide dimension

Example 19-3 A rectangular waveguide has dimensions of 3 × 5 cm. Calculate the TE_{10} mode cutoff frequency.

Solution:

$$F_c = \frac{c}{2a}$$

$$= \frac{(3 \times 108 \text{ m/s}}{(2)\left(5 \text{ cm} \times \dfrac{1 \text{ m}}{100 \text{ cm}}\right)}$$

$$= \frac{3 \times 10^8 \text{ m/s}}{(2)(0.05 \text{ m})} = 3 \text{ GHz}$$

Equation 19.7 assumes that the dielectric inside the waveguide is air. A more generalized form, which can accommodate other dielectrics, is

$$F_c = \frac{1}{2\sqrt{ue}} \sqrt{\left(\frac{m}{a}\right)^2 + \left(\frac{n}{b}\right)^2} \qquad \textbf{[19.10]}$$

where

e is the dielectric constant
u is the permeability constant

For air dielectrics, $u = u_o$ and $e = e_o$, from which

$$c = \frac{1}{\sqrt{u_o e_o}} \qquad \textbf{[19.11]}$$

To determine the cutoff wavelength, we can rearrange Eq. 19.10 to the form:

$$\lambda_c = \frac{2}{\sqrt{\left(\dfrac{m}{a}\right)^2 + \left(\dfrac{n}{b}\right)^2}} \qquad \textbf{[19.12]}$$

One further expression for air-filled waveguide calculates the actual wavelength in the waveguide from a knowledge of the free-space wavelength and actual operating frequency:

$$\lambda_g = \frac{\lambda_o}{\sqrt{1 - \left(\dfrac{F_c}{F}\right)^2}} \qquad \textbf{[19.13]}$$

where

λ_g is the wavelength in the waveguide
λ_o is the wavelength in free space
F_c is the waveguide cutoff frequency
F is the operating frequency

Example 19-4 A waveguide with a 4.5-GHz cutoff frequency is excited with a 6.7-GHz signal. Find (*a*) the wavelength in free space and (*b*) the wavelength in the waveguide.

Solution:

(*a*)

$$\lambda_o = c/F$$

$$= \frac{3 \times 10^8 \text{ m/s}}{6.7 \text{ GHz} \times \dfrac{10^9 \text{ Hz}}{1 \text{ GHz}}}$$

$$= \frac{3 \times 10^8 \text{ m/s}}{6.7 \times 10^9 \text{ Hz}} = 0.0448 \text{ m}$$

(*b*)

$$\lambda_g = \frac{\lambda_o}{\sqrt{1-\left(\dfrac{F_c}{F}\right)^2}}$$

$$= \frac{0.0448 \text{ m}}{\sqrt{1-\left(\dfrac{4.5 \text{ GHz}}{6.7 \text{ GHz}}\right)^2}}$$

$$= \frac{0.0448 \text{ m}}{1 - 0.67}$$

$$= \frac{0.0448}{0.33} = 0.136 \text{ m}$$

Transverse magnetic modes also propagate in waveguides, but the base TM_{10} mode is excluded by the boundary conditions. Thus, the TM_{11} mode is the lowest magnetic mode that will propagate.

Waveguide impedance

All forms of transmission line, including the waveguide, exhibit a characteristic impedance, although in the case of waveguide it is a little difficult to pin down conceptually. This concept was developed for ordinary transmission lines in Chap. 3. For a waveguide, the characteristic impedance is approximately equal to the ratio of the electric and magnetic fields (E/H), and converges (as a function of frequency) to the intrinsic impedance of the dielectric (Fig. 19-10). The impedance of the waveguide is a function of waveguide characteristic impedance (Z_o) and the wavelength in the waveguide:



19-10 Impedance versus frequency.

$$Z = \frac{Z_o \lambda_g}{\lambda_o} \qquad \textbf{[19.14]}$$

Or, for rectangular waveguide, with constants taken into consideration:

$$Z = \frac{120\,\pi\,\lambda_g}{\lambda_o} \qquad \textbf{[19.15]}$$

The *propagation constant B* for rectangular waveguide is a function of both cutoff frequency and operating frequency:

$$B = W\sqrt{eu}\,\sqrt{1-\left(\frac{F_c}{F}\right)^2} \qquad \textbf{[19.16]}$$

from which we can express the TE-mode impedance:

$$Z_{\mathrm{TE}} = \frac{\sqrt{ue}}{\sqrt{1-\left(\frac{F_c}{F}\right)^2}} \qquad \textbf{[19.17]}$$

and the TM-mode impedance:

$$Z_{\mathrm{TM}} = 377\sqrt{1-\left(\frac{F_c}{F}\right)^2} \qquad \textbf{[19.18]}$$

Waveguide terminations

When an electromagnetic wave propagates down a waveguide, it must eventually reach the end of the guide. If the end is open, then the wave will propagate into free-space. The horn radiator is an example of an unterminated waveguide. If the waveguide terminates in a metallic wall, then the wave reflects back down the waveguide, from whence it came. The interference between incident and reflected waves forms standing waves (see Chap. 3). Such waves are stationary in space, but vary in the time domain.

In order to prevent standing waves, or more properly, the reflections that give rise to standing waves, the waveguide must be *terminated* in a matching impedance. When a properly designed antenna is used to terminate the waveguide, it forms the matched load required to prevent reflections. Otherwise, a *dummy load* must be provided. Figure 19-11 shows several types of dummy load.

The classic termination is shown in Fig. 19-11A. The “resistor” making up the dummy load is a mixture of sand and graphite. When the fields of the propagated wave enter the load, they cause currents to flow, which in turn cause heating. Thus, the RF power dissipates in the sand-graphite rather than being reflected back down the waveguide.

A second dummy load is shown in Fig. 19-11B. The resistor element is a carbonized rod critically placed at the center of the electric field. The E field causes currents to flow, resulting in I^2R losses that dissipate the power.

Bulk loads, similar to the graphite-sand chamber, are shown in Fig. 19-11C, D, and E. Using bulk material such as graphite or a carbonized synthetic material, these loads are used in much the same way as the sand load (i.e., currents set up, and I^2R losses dissipate the power).

The resistive vane load is shown in Fig. 19-11F. The plane of the element is orthogonal to the magnetic lines of force. When the magnetic lines cut across the vane, currents are induced, which gives rise to the I^2R losses. Very little RF energy reaches the metallic end of the waveguide, so there is little reflected energy and a low VSWR.

There are situations where it isn’t desirable to terminate the waveguide in a dummy load. Several reflective terminations are shown in Fig. 19-12. Perhaps the simplest form is the permanent end plate shown in Fig. 19-12A. The metal cover must be welded or otherwise affixed through a very-low-resistance joint. At the substantial power levels typically handled in transmitter waveguides, even small resistances can be important.

The end plate (shown in Fig. 19-12B) uses a quarter-wavelength cup to reduce the effect of joint resistances. The cup places the contact joint at a point that is a


A
Sand & graphite
filled chamber
B
Resistive
rod
C
$\lambda/2$
Wedge

19-11 Dummy loads: (A) sand-graphite chamber; (B) resistive rod; (C) wedge.


λ/2
D
Double wedge
Waveguide
E
Absorptive pyramid wedge
Waveguide
Vane dummy load
F

19-11 Dummy loads: (D) double wedge; (E) pyramid wedge; (F) vane dummy load.


A
Permanent plate at end
Contact is at
point of
minimum current
λ/4
B
Removable
λ/4 wave end piece
Removable short circuit
Actual short here
λ/4
Thumb
screw
Virtual short here
C
Half wave channel
Adjustable plunger

19-12
End terminations.

quarter-wavelength from the end. This point is a minimum-current node, so I^2R losses in the contact resistance become less important.

The adjustable short circuit is shown in Fig. 19-12C. The walls of the waveguide and the surface of the plunger form a half-wavelength channel. Because the metallic end of the channel is a short circuit, the impedance reflected back to the front of the plunger is zero ohms, or nearly so. Thus, a virtual short exists at the points shown. By this means, the contact (or joint) resistance problem is overcome.

Waveguide joints and bends

Joints and bends in any form of transmission line or waveguide are seen as impedance discontinuities, and so are points at which disruptions occur. Thus, improperly formed bends and joints are substantial contributors to a poor VSWR. In general, bends, twists, joints, or abrupt changes in waveguide dimension can deteriorate the VSWR by giving rise to reflections.

Extensive runs of waveguide are sometimes difficult to make in a straight line. Although some installations do permit a straight waveguide, many others require directional change. This possibility is especially likely on shipboard installations. Figure 19-13A shows the proper ways to bend a waveguide around a corner. In each case, the radius of the bend must be at least two wavelengths at the lowest frequency that will be propagated in the system.

The "twist" shown in Fig. 19-13B is used to rotate the polarity of the E and H fields by 90°. This type of section is sometimes used in antenna arrays for phasing the elements. As in the case of the bend, the twist must be made over a distance of at least two wavelengths.

When an abrupt 90° transition is needed, it is better to use two successive 45° bends spaced one-quarter wavelength apart (see Fig. 19-13C). The theory (behind this kind of bend) is to cause the interference of the direct reflection of one bend, with the inverted reflection of the other. The resultant relationship between the fields is reconstructed as if no reflections had taken place.

Joints are necessary in practical waveguides because it simply isn't possible to construct a single length of practical size for all situations. Three types of common joints are used: *permanent, semipermanent,* and *rotating.*

To make a permanent joint the two waveguide ends must be machined extremely flat so that they can be butt-fitted together. A welded or brazed seam bonds the two sections together. Because such a surface represents a tremendous discontinuity, reflections and VSWR will result unless the interior surfaces are milled flat and then polished to a mirror-like finish.

A *semipermanent joint* allows the joint to be disassembled for repair and maintenance, as well as allowing easier on-site assembly. The most common example of this class is the *choke joint* shown in Fig. 19-14.

One surface of the choke joint is machined flat and is a simple butt-end planar flange. The other surface is the mate to the planar flange, but it has a quarter-wavelength circular slot cut at a distance of one-quarter wavelength from the waveguide aperture. The two flanges are shown in side view in Fig. 19-14A, and the slotted end view is shown in Fig. 19-14B. The method for fitting the two ends together is shown in the oblique view in Fig. 19-14C.



Narrow dimension

Wide dimension

Side view

19-13 Bends in waveguide must be gentle.



19-14 Choke joint.

Rotating joints are used in cases where the antenna has to point in different directions at different times. Perhaps the most common example of such an application is the radar antenna.

The simplest form of rotating joint is shown in Fig. 19-15. The key to its operation is that the selected mode is symmetrical about the rotating axis. For this reason, a circular waveguide operating in the TM_{01} mode is selected. In this rotating choke joint, the actual waveguide rotates but the internal fields do not (thereby minimizing reflections). Because most waveguide is rectangular, however, a somewhat more complex system is needed. Figure 19-16 shows a rotating joint consisting of two circular waveguide sections inserted between segments of rectangular waveguide. On each end of the joint, there is a rectangular-to-circular transition section.

In Fig. 19-16, the rectangular input waveguide operates in the TE_{10} mode that is most efficient for rectangular waveguide. The E-field lines of force couple with the circular segment, thereby setting up a TM_{01} mode wave. The TM_{01} mode has the required symmetry to permit coupling across the junction, where it meets another transition zone and is reconverted to TE_{10} mode.

Waveguide coupling methods

Except possibly for the case where an oscillator exists inside a waveguide, it is necessary to have some form of input or output coupling in a waveguide system. There are three basic types of coupling used in a microwave waveguide: *capacitive* (or *probe*), *inductive* (or *loop*), and *aperture* (or *slot*).

Capacitive coupling is shown in Fig. 19-17. This type of coupling uses a vertical radiator inserted into one end of the waveguide. Typically, the probe is a quarter-wavelength in a fixed-frequency system. The probe is analogous to the vertical antennas used at lower frequencies. A characteristic of this type of radiator is that the E field is parallel to the waveguide top and bottom surfaces. This arrangement satisfies the first boundary condition for the dominant TE_{10} mode.

The radiator is placed at a point that is a quarter-wavelength from the rear wall (Fig. 19-17B). By traversing the quarter-wave distance (90° phase shift), being reflected from the rear wall (180° phase shift), and then retraversing the


Choke joint
Stationary section
Rotating section
Rotating joint

19-15 Basic rotating joint.


TE_{10} Mode
Choke joint
Rotating
Stationary
TM_{01} Mode
TE_{10} Mode

19-16
Representative practical rotating joint.



19-17
Probe (capacitive) coupling.

quarter-wavelength distance (another 90° phase shift), the wave undergoes a total phase shift of one complete cycle, or 360°. Thus, the reflected wave arrives back at the radiator in phase to reinforce the outgoing wave. Hence, none of the excitation energy is lost.

Some waveguides have an adjustable end cap (Fig. 19-17C) in order to accommodate multiple frequencies. The end cap position is varied to accommodate the different wavelength signals.

Figure 19-17D shows high- and low-power broadband probes that are typically not a quarter-wavelength except at one particular frequency. Broadbanding is accomplished by attention to the diameter-to-length ratio. The *degree of coupling* can be varied in any of several ways: the *length* of the probe can be varied; the *position* of the probe in the E field can be changed; or *shielding* can be used to partially shade the radiator element.

Inductive, or loop coupling, is shown in Fig. 19-18. A small loop of wire (or other conductor) is placed such that the number of magnetic flux lines is maximized. This form of coupling is popular on microwave receiver antennas, in order to make a waveguide-to-coaxial cable transition. In some cases, the loop is formed by the pigtail lead of a detector diode that, when combined with a local oscillator, downconverts the microwave signal to an IF frequency in the 30- to 300-MHz region.

Aperture, or slot coupling, is shown in Fig. 19-19. This type of coupling is used to couple together two sections of waveguide, as on an antenna feed system. Slots can be designed to couple either electric, magnetic, or electromagnetic fields. In Fig. 19-19, slot *A* is placed at a point where the E field peaks, so it allows electrical field coupling. Similarly, slot *B* is at a point where the H field peaks, so it allows magnetic field coupling. Finally, we see slot *C,* which allows electromagnetic field coupling.

Slots can also be characterized according to whether they are *radiating* or *nonradiating.* A nonradiating slot is cut at a point that does not interrupt the flow of currents in the waveguide walls. The radiating slot, on the other hand, does interrupt currents flowing in the walls. A radiating slot is the basis for several forms of antenna, which are discussed at the end of this chapter.



19-18
Loop (inductive) coupling.



19-19 Slot coupling.

Microwave antennas

Antennas are used in communications and radar systems at frequencies from the very lowest to the very highest. In both theory and practice, antennas are used until frequencies reach infrared and visible light, at which point optics becomes more important. Microwaves are a transition region between ordinary “radio waves” and “optical waves,” so (as might be expected) microwave technology makes use of techniques from both worlds. For example, both dipoles and parabolic reflectors are used in microwave systems.

The purpose of an antenna is to act as a *transducer* between either electrical oscillations or propagated “guided waves” (i.e., in transmission lines or waveguides) and a propagating electromagnetic wave in free space. A principal function of the antenna is to act as an *impedance matcher* between the waveguide, or transmission line, impedance and the impedance of free space.

Antennas can be used equally well for both receiving and transmitting signals because they obey the *law of reciprocity.* That is, the same antenna can be used to both receive and transmit with equal success. Although there might be practical or mechanical reasons to prefer specific antennas for one or the other mode, electrically they are the same.

In the transmit mode, the antenna must radiate electromagnetic energy. For this job, the important property is *gain* G. In the receive mode, the job of the antenna is to gather energy from impinging electromagnetic waves in free space. The important property for receiver antennas is the *effective aperture* A_e, which is a function of the antenna’s physical area. Because of reciprocity, a large gain usually infers a large effective aperture and vice versa. *Effective aperture* is defined as the area of the impinging radio wavefront that contains the same power as is delivered to a matched resistive load across the feedpoint terminals.

The isotropic “antenna”

Antenna definitions and specifications can become useless unless a means is provided for putting everything on a common footing. Although a variety of systems exist for describing antenna behavior, the most common system compares a specific antenna with a theoretical construct, called the *isotropic radiator.*

An isotropic radiator is a spherical point source that radiates equally well in all directions. By definition, the directivity of the isotropic antenna is unity (1), and all antenna gains are measured against this standard. Because the geometry of the sphere and the physics of radiation are well known, we can calculate field strength and power density at any point. These figures can then be compared with the actual values from an antenna being tested. From spherical geometry, we can calculate isotropic power density at any distance R from the point source:

$$P_d = \frac{P}{4\pi R^2} \qquad \textbf{[19.19]}$$

where

P_d is the power density, in watts per square meter
P is the power in watts input to the isotropic radiator
R is the radius in meters at which point power density is measured

Example 19-5 Calculate the power density at a distance of 1 km (1000 m) from a 1000-W isotropic source.

Solution:

$$\begin{aligned} P_d &= \frac{P}{4\pi R^2} \\ &= \frac{(1000\ \text{W})}{4\pi\ (1000\ \text{m})^2} \\ &= 7.95 \times 10^{-5}\ \text{W/m}^2 \end{aligned}$$

The rest of this chapter covers antenna gains and directivities that are relative to isotropic radiators.

Near field and far field

Antennas are defined in terms of *gain* and *directivity,* both of which are measured by looking at the radiated field of the antenna. There are two fields to consider: *near field* and *far field.* The patterns published for an antenna tend to reflect far-field performance. The far field for most antennas falls off according to the *inverse square law.* That is, the intensity falls off according to the square of the distance ($1/R^2$), as in Eq. 19.19.

The near field of the antenna contains more energy than the far field because of the electric and magnetic fields close to the antenna radiator element. The near field tends to diminish rapidly according to a $1/R^4$ function. The minimum distance to the edge of the near field is a function of both the wavelength of the radiated signals and the antenna dimensions:

$$r_{\min} = \frac{2\,d^2}{\lambda} \qquad \textbf{[19.20]}$$

where

$r_{\min}$ is the near-field distance
d is the largest antenna dimension
λ is the wavelength of the radiated signal (all factors in the same units)

Example 19-6 An antenna with a length of 6 cm radiates a 12-cm wavelength signal. Calculate the near-field distance.

Solution:

$$r_{\min} = \frac{2d^2}{\lambda}$$

$$= \frac{(2)\ (6\text{ cm})^2}{12\text{ cm}}$$

$$= \frac{72}{12} = 6\text{ cm}$$

Antenna impedance

Impedance represents the total opposition to the flow of alternating current (e.g., RF), and includes both resistive and reactive components. The reactive components can be either capacitive or inductive, or a combination of both. Impedance can be expressed in either of two notations:

$$Z = \sqrt{R^2 + (X_L - X_c)^2} \qquad \textbf{[19.21]}$$

or

$$Z = R \pm jX \qquad \textbf{[19.22]}$$

Of these, Eq. 19.22 is perhaps the more commonly used in RF applications. The reactive part of antenna impedance results from the magnetic and electrical fields (close to the radiator) returning energy to the antenna radiator during every cycle. The resistive part of impedance consists of two elements: *ohmic losses* R_o and *radiation resistance* R_r. The ohmic losses are due to heating of the antenna conductor elements by RF current passing through, as when current passes through any conductor.

The radiation resistance relates to the radiated energy. An efficiency factor k compares the loss and radiation resistances:

$$k = \frac{R_r}{R_r + R_o} \qquad \textbf{[19.23]}$$

The goal of the antenna designer is to reduce R_o to a minimum. The value of R_r is set by the antenna design and installation, and is defined as the quotient of the voltage over the current at the feedpoint, less losses.

Dipole antenna elements

The *dipole* is a two-pole antenna (Fig. 19-20) that can be modeled as either a single radiator fed at the center (Fig. 19-20A) or a pair of radiators fed back to back (Fig. 19-20B). RF current from the source oscillates back and forth in the radiator element, causing an electromagnetic wave to propagate in a direction *perpendicular* to the radiator element. The polarity of any electromagnetic field is the direction of the electrical field vector (see Chap. 2). In the dipole, the polarization is parallel to the radiator element: a horizontal element produces a horizontally polarized signal, while a vertical element produces a vertically polarized signal.



19-20A Basic dipole antenna showing propagation.



19-20B Basic dipole antenna.

Figure 19-21 shows the radiator patterns for the dipole viewed from two perspectives. Figure 19-21A shows the pattern of a horizontal half-wavelength dipole as viewed from above. This plot shows the *directivity* of the dipole: maximum radiation is found in two lobes perpendicular to the radiator length. The plot in Fig. 19-21B shows the end-on pattern of the dipole. This omnidirectional pattern serves for a vertically polarized dipole viewed from above. The end-on pattern of a horizontal dipole would be similar, except that it is distorted by ground effects unless the antenna is a very large number of wavelengths above the ground.



19-21A
Dipole pattern (horizontal).



19-21B
Dipole pattern (vertical).

A microwave dipole is shown in Fig. 19-22. The antenna radiator element consists of a short conductor at the end of a section of waveguide. Although most low-frequency dipoles are a half-wavelength, microwave dipoles might be either a half-wavelength, less than a half-wavelength, or greater than a half-wavelength, depending upon application. For example, because most microwave dipoles are used to illuminate a reflector antenna of some sort, the length of the dipole depends upon the exact illumination function required for proper operation of the reflector. Most, however, will be a half-wavelength.

Antenna directivity and gain

The dipole discussed illustrated a fundamental property of the type of antenna generally used at microwave frequencies: *directivity* and *gain.* These two concepts are different but so interrelated that they are usually discussed at the same time. Because of the directivity, the antenna focuses energy in only two directions, which means that all of the energy is found in those directions (Fig. 19-21A), rather than being distributed over a spherical surface. Thus, the dipole has a gain approximately 2.1 dB greater than isotropic. In other words, the measured power density at any point will be 2.1 dB higher than the calculated isotropic power density for the same RF input power to the antenna.

Directivity The directivity of an antenna is a measure of its ability to direct RF energy in a limited direction, rather than in all (spherical) directions equally. As shown in Fig. 19-21A, the horizontal directivity of the dipole forms a bidirectional figure-8 pattern. Two methods for showing unidirectional antenna patterns are shown in Fig. 19-23. The method of Fig. 19-23A is a polar plot viewed from above. The main lobe is centered on 0°. The plot of Fig. 19-23B is a rectangular method for displaying the same information. This pattern follows a (sin x)/x function or, for power, $[(\sin x)/x]^2$.

Directivity D is a measure of relative power densities:

$$D = \frac{P_{\text{max}}}{P_{\text{av}}} \tag{19.24}$$

Or, referenced to isotropic,

$$D = \frac{4\pi}{\Phi} \tag{19.25}$$

where

D is the directivity
P_{max} is the maximum power
P_{av} is the average power
Φ is the solid angle subtended by the main lobe



19-22
Microwave dipole radiator.



19-23A
Directional antenna pattern (top view).

The term Φ is a solid angle, which emphasizes the fact that antenna patterns must be examined in at least two extents: horizontal and vertical.

A common method for specifying antenna directivity is *beamwidth* (BW). The definition of BW is the angular displacement between points on the main lobe (see Figs. 19-23A and 19-23B), where the power density drops to one-half (−3 dB) of its maximum main lobe power density. This angle is shown in Fig. 19-23A as *a*.

In an ideal antenna system, 100 percent of the radiated power is in the main lobe, and there are no other lobes. But in real antennas certain design and installation anomalies cause additional minor lobes, such as the *sidelobes* and *backlobe* shown in Fig. 19-23A. Several problems derive from the minor lobes. First is the loss of usable power. For a given power density required at a distant receiver site, the transmitter must supply whatever additional power is needed to make up for the minor lobe losses.

The second problem is intersystem interference. A major application of directional antennas is the prevention of mutual interference between nearby cochannel stations. In radar systems, high sidelobes translate to errors in detected targets. If, for example, a sidelobe is large enough to detect a target, then the radar display will show this off-axis target as if it was in the main lobe of the antenna. The result is an azimuth error that could be important in terms of marine and aeronautical navigation.

Gain Antenna gain derives from the fact that energy is squeezed into a limited space instead of being distributed over a spherical surface. The term *gain* implies that the antenna creates a higher power when, in fact, it merely concentrates the power into a single direction that would otherwise be spread out over a larger area. Even so, it is possible to speak of an apparent increase in power. Antenna-transmitter systems are often rated in terms of *effective radiated power* (ERP). The ERP is the product of the transmitter power and the antenna gain. For example, if an antenna has a gain of +3 dB, the ERP will be twice the transmitter output power. In other words, a 100-W output transmitter connected to a +3-dB antenna will produce a power density at a distant receiver equal to a 200-W transmitter feeding an isotropic radiator. There are two interrelated gains to be considered: *directivity gain* G_d *and power gain* G_p.

The directivity gain is defined as the quotient of the maximum radiation intensity over the average radiation intensity (note the similarity to the directivity definition). This measure of gain is based on the shape of the antenna radiation pattern, and can be calculated with respect to an isotropic radiator ($D=1$) from:

$$G_d = \frac{4\pi P_a}{P_r} \tag{19.26}$$



19-23B Graphically presented pattern.

where

G_d is the directivity gain
P_a is the maximum power radiated per unit of solid angle
P_r is the total power radiated by the antenna

The power gain is similar in nature, but slightly different from directivity gain; it includes dissipative losses in the antenna. Not included in the power gain are losses caused by cross-polarization or impedance mismatch between the waveguide (or transmission line) and the antenna. There are two commonly used means for determining power gain:

$$G_p = \frac{4\pi P_a}{P_n} \qquad \textbf{[19.27]}$$

and

$$G_p = \frac{P_{\mathrm{ai}}}{P_i} \qquad \textbf{[19.28]}$$

where

P_a is the maximum radiated per unit solid angle
P_n is the net power accepted by the antenna (i.e., less mismatch losses)
P_{ai} is the average intensity at a distant point
P_i is the intensity at the same point from an isotropic radiator fed the same RF power level as the antenna

(Equations assume equal power to antenna and comparison isotropic source.)

Provided that ohmic losses are kept negligible, the relationship between directivity gain and power gain is given by:

$$G_p = \frac{P_r G_d}{P_n} \qquad \textbf{[19.29]}$$

(All terms as previously defined.)

Relationship of gain and aperture Antennas obey the law of reciprocity, which means that any given antenna will work as well to receive as to transmit. The function of the receiver antenna is to gather energy from the electromagnetic field radiated by the transmitter antenna. The aperture is related to, and often closely approximates, the physical area of the antenna. But in some designs the effective aperture A_e is less than the physical area A, so there is an effectiveness factor n that must be applied. In general, however, a high-gain transmitter antenna also exhibits a high receiving aperture, and the relationship can be expressed as

$$G = \frac{4\,\pi A_e n}{\lambda^2} \qquad \textbf{[19.30]}$$

where

A_e is the effective aperture
n is the aperture effectiveness (n=1 for a perfect, lossless antenna)
λ is the wavelength of the signal

Horn antenna radiators

The horn radiator is a tapered termination of a length of waveguide (see Fig. 19-24 (A-C) that provides the impedance transformation between the waveguide impedance and the free-space impedance. Horn radiators are used both as antennas in their own right, and as illuminators for reflector antennas. Horn antennas are not a perfect match to the waveguide, although standing wave ratios of 1.5:1 or less are achievable. The gain of a horn radiator is proportional to the area A of the flared open flange ($A = ab$ in Fig. 19-24B), and inversely proportional to the square of the wavelength:

$$G=\frac{10A}{\lambda^2} \qquad \textbf{[19.31]}$$

where

A is the flange area
λ is the wavelength (both in same units)

The −3-dB beamwidth for vertical and horizontal extents can be approximated from:

Vertical

$$\Phi_v = \frac{51\lambda}{b} \quad \text{degrees} \qquad \textbf{[19.32]}$$



19-24 Horn radiators.

Horizontal

$$\Phi_h = \frac{70\lambda}{a} \qquad \text{degrees} \tag{19.33}$$

where

Φ_v is the vertical beamwidth, in degrees
Φ_h is the horizontal beamwidth, in degrees
a, b are dimensions of the flared flange
λ is the wavelength

A form of antenna, related to the horn, is the cavity antenna of Fig. 19-25. In this type of antenna, a quarter-wavelength radiating element extends from the waveguide (or transmission line connector) into a resonant cavity. The radiator element is placed a quarter-wavelength into a resonant cavity; and is spaced a quarter-wavelength from the rear wall of the cavity. A tuning disk is used to alter cavity dimensions in order to provide a limited tuning range for the antenna. Gains to about 6 dB are possible with this arrangement.

Reflector antennas

At microwave frequencies, it becomes possible to use *reflector antennas* because of the short wavelengths involved. Reflectors are theoretically possible at lower frequencies, but because of the longer wavelengths, the antennas would be so large that they become impractical. Several forms of reflector are used (Figs. 19-26 and 19-27). In Fig. 19-26 we see the *corner reflector* antenna, which is used primarily in the high-UHF and low-microwave region. A dipole element is placed at the "focal point" of the corner reflector, so it receives (in phase) the reflected wavefronts from the surface. Either solid metallic reflector surfaces or wire mesh may be used. When mesh is used, however, the holes in the mesh must be $\frac{1}{12}$-wavelength or smaller.

Figure 19-27 shows several other forms of reflector surface shape, most of which are used in assorted radar applications.

Parabolic "dish" antennas

The parabolic reflector antenna is one of the most widespread of all the microwave antennas, and is the type that normally comes to mind when thinking of microwave systems. This type of antenna derives its operation from physics similar to optics, and is possible because microwaves are in a transition region between ordinary radio waves and infrared/visible light.

The dish antenna has a paraboloid shape as defined by Fig. 19-28. In this figure, the dish surface is positioned such that the center is at the origin (0,0) of an x-y coordinate system. For purposes of defining the surface, we place a second vertical axis called the *directrix* (y') a distance behind the surface equal to the focal length (u). The paraboloid surface follows the function $y^2 = 4ux$, and has the property that a line from the focal point F to any point on the surface is the same length as a line from that same point to the directrix (in other words, MN = MF).

If a radiator element is placed at the focal point F, then it will illuminate the reflector surface, causing wavefronts to be propagated away from the surface in


Antenna radiator element
$\lambda/4$
$\lambda/4$
(Cavity)
λ
Microwave window
Tuning disk
Waveguide or coaxial cable fitting
Tuning adjustment screw

19-25 Cavity antenna.


λ
Dipole element
a_R
λ
a_I

19-26 Corner reflector.

phase. Similarly, wavefronts, intercepted by the reflector surface, are reflected to the focal point.

Gain The gain of a parabolic antenna is a function of several factors: dish diameter, feed illumination, and surface accuracy. The dish diameter D should be large compared with its depth. Surface accuracy refers to the degree of surface irregularities. For commercial antennas, $\frac{1}{8}$-wavelength surface accuracy is usually sufficient,



A. Paraboloid

B. Truncated paraboloid (surface search)

C. Truncated paraboloid (height finding)

D. Orange-peel paraboloid



E. Cylindrical paraboloid

F. Corner reflector

19-27 Reflector antennas.

although on certain radar antennas the surface accuracy specification must be tighter.

The feed illumination refers to how evenly the feed element radiates to the reflector surface. For circular parabolic dishes, a circular waveguide feed produces optimum illumination, and rectangular waveguides are less than optimum. The TE_{11} mode is desired. For best performance, the illumination should drop off evenly from the center to the edge, with the edge being 210 dB down from the center. The diameter, length, and beamwidth of the radiator element (or horn) must be optimized for the specific *F/d* ratio of the dish. The cutoff frequency is approximated from

$$f_{\text{cutoff}} = \frac{175{,}698}{d_{\text{mm}}} \qquad \textbf{[19.34]}$$

where

f_{cutoff} is the cutoff frequency
d is the inside diameter of the circular feedhorn

The gain of the parabolic dish antenna is found from

$$G = \frac{k\,(\pi D)^2}{\lambda^2} \qquad \textbf{[19.35]}$$

where

G is the gain over isotropic
D is the diameter
λ is the wavelength (same units as D)
k is the reflection efficiency (0.4 to 0.7, with 0.55 being most common)

The −3-dB beamwidth of the parabolic dish antenna is approximated by

$$\mathrm{BW} = \frac{70\,\lambda}{D} \qquad \textbf{[19.36]}$$

and the focal length by

$$F = \frac{D^2}{16d} \qquad \textbf{[19.37]}$$

For receiving applications, the effective aperture is the relevant specification and is found from

$$A_e = k\pi(D/2)^2 \qquad \textbf{[19.38]}$$

The antenna pattern radiated by the antenna is similar to Fig. 19-23B. With horn illumination, the sidelobes tend to be 23 to 28 dB below the main lobe, or 10 to 15 dB below isotropic. It is found that 50 percent of the energy radiated by the parabolic dish is within the −3-dB beamwidth, and 90 percent is between the first nulls on either side of the main lobe.


Parabolic ($y^2 = ux$) reflector surface
y^1
y
B
N
M
$MN = MF$
u
u
(0,0)
x
F
(Focal point)
Advancing wavefronts
D
Directrix
A

19-28 Ray tracing shows operation of parabolic antenna.

If a dipole element is used for the feed device, then a *splash plate* is placed ¼-wavelength behind the dipole in order to improve illumination. The splash plate must be several wavelengths in diameter, and is used to reflect the backlobe back toward the reflector surface. When added to the half-wave phase reversal inherent in the reflection process, the two-way quarter-wavelength adds another half-wavelength and thereby permits the backwave to move out in phase with the front lobe wave.

Parabolic dish feed geometries Figure 19-29 shows two methods for feeding parabolic dish antennas, regardless of which form of radiator (horn, dipole, etc.) is used. In Fig. 19-29A we see the method in which the radiator element is placed at the focal point, and a waveguide (or transmission line) is routed to it. This method is used in low-cost installations such as home satellite TV receive-only (TVRO) antennas.

Figure 19-29B shows the *Cassegrain feed* system. This system is modeled after the Cassegrain optical telescope. The radiator element is placed at an opening at the center of the dish. A hyperbolic subreflector is placed at the focal point, and it is used to reflect the wavefronts to the radiator element. The Cassegrain system results in lower-noise operation because of several factors: less transmission line length, lower sidelobes, and the fact that the open horn sees sky instead of earth



19-29A
Parabolic antenna conventional feed.



19-29B Parabolic antenna Cassegrain feed.

(which has lower temperature); on the negative side, galactic and solar noise might be slightly higher on a Cassegrain dish.

Figure 19-30A shows the *monopulse* feed geometry. In this system, a pair of radiator elements are placed at the focal point, and fed to a power splitter network that outputs both *sum* and *difference* signals (Fig. 19-30B). When these are combined, the resultant beam shape has improved −3-dB beamwidth as a result of the algebraic summation of the two.

Array antennas

When antenna radiators are arranged in a precision array, an increase in gain occurs. An array might be a series of dipole elements, as in the broadside array of Fig. 19-31 (which is used in the UHF region), or a series of slots, horns, or other radiators. The overall gain of an array antenna is proportional to the number of elements, as well as the details of their spacing. In this, and other antennas, a method of *phase shifting* is needed. In Fig. 19-31, the phase shifting is caused by the crossed feeding of the elements, but in more modern arrays, other forms of phase shifter are used.

Two methods of feeding an array are shown in Fig. 19-32. The *corporate feed* method connects all elements, and their phase shifters, in parallel with the source. The *branch feed* method breaks the waveguide network into two (or more) separate paths.

Solid-state array antennas Some modern radar sets use solid-state array antennas consisting of a large number of elements, each of which is capable of shifting the phase of a microwave input signal. Two forms are known: *passive* (Fig. 19-33A) and *active* (Fig. 19-33B). In the passive type of element, a ferrite (or PIN diode) phase shifter is placed in the transmission path between the RF input and the radiator element (usually a slot). By changing the phase of the RF signal selectively, it is possible to form and steer the beam at will. A 3-bit (i.e., three discrete state) phase


F_1
F_2
Sum
Difference

19-30A
Monopulse feed.



19-30B
Monopulse patterns.



19-31
Reflector array antenna.

shifter allows the phase to shift in 45° increments, while a 4-bit phase shifter allows 22.5° increments of phase shift.

The active element contains, in addition to a phase shifter, a transmit power amplifier (1 or 2 W) and a low-noise amplifier (LNA) for receiving. A pair of transmit/receive (T/R) switches select the path to which the RF signal is directed. The total output power of this antenna is the sum of all output powers from all elements in the array. For example, an array of one thousand 2-W elements makes a 2000-W system.

Slot array antennas

A resonant slot (cut into a wall of a section of waveguide) is somewhat analogous, if not identical, to a dipole. By cutting several slots in the waveguide, we obtain the advantages of an array antenna in which the elements are several slot radiators. Slot array antennas are used for marine navigation radars, telemetry systems, and the reception of microwave television signals in the Multipoint Distribution Service (MDS) on 2.145 GHz.

Figure 19-34 shows a simple slot antenna used in telemetry applications. A slotted section of rectangular waveguide is mounted to a right-angle waveguide flange. An internal wedge (not shown) is placed at the top of the waveguide and serves as a matching-impedance termination to prevent internal reflected waves. Directivity is enhanced by attaching flanges to the slotted section of waveguide parallel to the direction of propagation (see end view of Fig. 19-34).

Figure 19-35 shows two forms of *flatplate array* antennas constructed from slotted waveguide radiator elements (shown as insets). Figure 19-35A shows the rectangular array, and Fig. 19-35B shows the circular array. These flatplate arrays are used extensively in microwave communications and radar applications.

The feed structure for a flatplate array is shown in Fig. 19-35C. The antenna element is the same sort as shown in Figs. 19-35A and 19-35B. A distribution waveguide is physically mated with the element, and a coupling slot is provided between the two waveguides. Energy propagating in the distribution system waveguide is


Branch
feed
Antenna
elements
Phase shifters
RF Microwave
generators
Corporate
feed

19-32 Branch feed and corporate feed.


Binary
control
inputs
RF input
PIN diode
or ferrite
phase shifter
Radiator
element

19-33A Phase shifter.


Binary control inputs
PA
RF port
PIN diode or ferrite phase shifter
T/R
T/R
ANT.
LNA

19-33B Phase-shift T/R element.


Right-angle waveguide feed flange
Directivity flanges
(Front view)
End view
Slots
Waveguide

19-34 Slot antenna (front view).

coupled into the antenna radiator element through this slot. In some cases metallic or dielectric phase-shifting stubs are also used in order to fine-tune the antenna radiation pattern.

Microwave antenna safety note

Microwave RF energy is dangerous to your health. Anything that can cook a roast beef can also cook you! The U.S. government sets a safety limit for microwave exposure of 10 mW/cm^2 averaged over 6 minutes; some other countries use a level one-tenth of the U.S. standard. The principal problem is tissue heating, and eyes seem especially sensitive to microwave energy. Some authorities believe that cataracts form from prolonged exposure. Some authorities also believe that genetic damage to offspring is possible as well as other long-term effects as a result of cumulative exposure.

Because of their relatively high gain, microwave antennas can produce hazardous field strengths in close proximity—even at *relatively low RF input power levels.* At



19-35A Flatplate slot array.



19-35B
Flatplate antenna.



19-35C Flatplate antenna feed coupling.

least one technician in a TV satellite earth station suffered abdominal adhesions, solid matter in the urine, and genital dysfunction after servicing a 45-m-diameter 3.5-GHz antenna with RF power applied.

Be very careful around microwave antennas. Do not service a radiating antenna. When servicing nonradiating antennas, be sure to stow them in a position that prevents the inadvertent exposure of humans, should power accidentally be applied. A *Radiation Hazard* sign should be prominently displayed on the antenna. Good design practice requires an interlock system that prevents radiation in such situations. “Hot” transmitter service should be performed with a shielded dummy load replacing the antenna.

This page intentionally left blank

20
CHAPTER

Antenna noise temperature

RADIO RECEPTION IS ESSENTIALLY A MATTER OF SIGNAL-TO-NOISE RATIO (SNR). SIGNALS must be some amplitude above the noise floor of the system in order to be received properly. All electronic systems (receivers and antennas included) have inherent noise, even if there is no power flowing in them. One of the goals of the antenna designer is to minimize the noise so that weak signals are not obscured. One of the basic forms of noise seen in systems is the *thermal noise.* Even if the amplifiers in the receiver add no additional noise (they will!), there will be thermal noise at the input.

If you replace the antenna with a resistor matched to the system impedance that is totally shielded, there will still be noise present. The noise is produced by the random motion of electrons inside the resistor. At all temperatures above absolute zero (about −273.16°C) the electrons in the resistor material are in random motion. At any given instant there will be a huge number of electrons in motion in all directions. The reason why there is no discernible current flow in one direction is that the motions cancel each other out even over short time periods. The noise power present in a resistor is:

$$P_N = KTBR \qquad \textbf{[20.1]}$$

where

P_N is the noise power, in watts
T is the temperature, in kelvins (K)
K is Boltzmann's constant (1.38×10^{-23} K)
B is the bandwidth, in hertz
R is the resistance, in ohms

Note: By international agreement T is set to 290 K.

Consider a receiver with a 1-MHz bandwidth and an input resistance of 50 Ω. The noise power is $(1.38 \times 10^{-23}\ \text{K}) \times (290\ \text{K}) \times (1{,}000{,}000\ \text{Hz}) \times (50\ \Omega) = 2 \times 10^{-13}$ W. This noise is called *thermal noise, thermal agitation noise,* or *Johnson noise.*

A resonant antenna can be modeled as an impedance consisting solely of a resistor with a value equal to the feedpoint impedance. If an antenna has a 50-Ω feedpoint

Copyright 2001 - the McGraw-Hill Companies

impedance, then it will generate exactly the same amount of thermal noise as a resistor of the same value.

Noise factor, noise figure, and noise temperature

The noise performance of a receiving system can be defined in three different, but related, ways: *noise factor* F_n, *noise figure (NF),* and *equivalent noise temperature* T_e; these properties are definable as a simple ratio, decibel ratio, or kelvin temperature, respectively.

Noise factor (F_n)

For components such as resistors, the noise factor is the ratio of the noise produced by a real resistor to the simple thermal noise of an ideal resistor. The noise factor of a radio receiver (or any system) is the ratio of output noise power P_{no} to input noise power P_{ni}:

$$F_n = \left. \frac{P_{\text{no}}}{P_{\text{ni}}} \right|_{T=290\text{ K}} \qquad \textbf{[20.2]}$$

In order to make comparisons easier, the noise factor is usually measured at the standard temperature (T_o) of 290 K (standardized room temperature), although in some countries 299 K or 300 K is commonly used (the differences are negligible).

It is also possible to define noise factor F_n in terms of output and input signal-to-noise ratios:

$$F_n = \frac{S_{\text{ni}}}{S_{\text{no}}} \qquad \textbf{[20.3]}$$

where

S_{ni} is the input signal-to-noise ratio
S_{no} is the output signal-to-noise ratio

Noise figure (NF)

The noise figure is a frequently used measure of a receiver's "goodness," or its departure from "idealness." Thus, it is a *figure of merit.* The noise figure is the noise factor converted to decibel notation:

$$\text{NF} = 10 \log F_n \qquad \textbf{[20.4]}$$

where

NF is the noise figure, in decibels
F_n is the noise factor
LOG refers to the system of base 10 logarithms

Noise temperature (T_e)

The noise "temperature" is a means for specifying noise in terms of an equivalent temperature. Evaluating the noise equations shows that the noise power is directly proportional to temperature in kelvins, and also that noise power collapses to zero at the temperature of absolute zero (0 K).

Note that the equivalent noise temperature T_e is *not* the physical temperature of the amplifier, but rather a theoretical construct that is an *equivalent* temperature that produces that amount of noise power. The noise temperature is related to the noise factor by

$$T_e = (F_n - 1)\, T_o \qquad \textbf{[20.5]}$$

and to noise figure by

$$T_e = KT_o \log^{-1}\left(\frac{\mathrm{NF}}{10}\right) - 1 \qquad \textbf{[20.6]}$$

Noise temperature is often specified for receivers and amplifiers in combination with, or in lieu of, the noise figure. The noise temperature concept is also applied to antennas where it is related to the amount of thermal noise generated by the resistive component of the antenna feedpoint impedance.

The antenna-receiver system will be afflicted by three different noise sources external to the receiver. The first is the thermal noise temperature of the feedpoint impedance (T_R). The sky exhibits a noise temperature that depends on where the antenna main lobe is pointed. Similarly, the ground has a noise temperature that consists of components reflected from the sky as well as components of its own caused by whatever thermal agitation exists. In a typical system (Fig. 20-1) the



20-1 Contributors to antenna noise temperature.

main lobe will be pointed toward the sky noise source, while the sidelobes will pick up noise from the ground. The total noise temperature of the antenna is

$$T_{\text{ANT}} = (M \times T_{\text{SKY}}) + \xi\,(1 - M)T_{\text{GND}} + T_R \qquad \textbf{[20.7]}$$

where

T_{ANT} is the equivalent noise temperature of the antenna
T_{SKY} is the noise temperature of the sky
T_{GND} is the noise temperature of the ground
T_R is the feedpoint resistance noise temperature
M is the fraction of the total energy that enters the main lobe
ξ is the fraction of sidelobes that are viewing the ground (only one of several sidelobes is shown in Fig. 20-1)

21
CHAPTER

Antennas for radio astronomy

FOR CENTURIES ASTRONOMERS HAVE SCANNED THE HEAVENS WITH OPTICAL TELESCOPES. But today, astronomers have many more tools in their bag, and one of them is *radio* astronomy. The field of radio astronomy emerged in the 1930s and 1940s through the work of Grote Reber and Carl Jansky. Even during World War II, progress was made as many tens of thousands of operators were listening to frequencies from dc to near daylight (well, actually, the low-end microwave bands). British radar operators noted during the Battle of Britain that the distance at which they could detect German aircraft dropped when the Milky Way was above the horizon.

Although there is a lot of amateur radio astronomy being done, most of it requires microwave equipment with low-noise front ends. However, there are several things that almost anyone can do.

The topic of antennas for radio astronomy can include nearly all forms of directional gain antenna. It is common to see Yagis, ring Yagis, cubical quads, and other antennas for lower-frequency use (18 to 1200 MHz). Microwave gain antennas can be used for higher frequencies. Indeed, many amateur radio astronomers appropriate TV receive-only (TVRO) satellite dish antennas for astronomy work. In this chapter we will cover some antennas that are not found in other chapters, at least not in this present context.

Jupiter reception

Jupiter is a strong radio source (next to the sun, it's the strongest in the sky). It produces noiselike signals over the spectrum 5 to 40 MHz, with peaks between 18 and 24 MHz. One source claims that the radio signals come from massive storms on the largest planet's surface, apparently triggered by the transit of the jovian moons through the planet's magnetic field. The signals are plainly audible on the HF band any time Jupiter is above the horizon, day or night. However, in order to eliminate the possibility of both local and terrestrial skip signals from interfering, Jupiter DXers prefer to listen during the hours after 2100 [or whenever the maximum usable frequency (MUF) drops significantly below 18 MHz] and local sunup. Listen to the

Copyright 2001 - the McGraw-Hill Companies

amateur 17- or 15-m bands. If you hear zilch activity, then it's a good bet that the MUF has dropped enough to make listening worthwhile. Even during the day, however, it is possible to hear jovian signals, but differentiating them from other signals or solar noise is difficult.

So what do you need to DX Jupiter? It would help to have a decent radio receiver that works well over the range 18 to 24 MHz. Some cheaper radio receivers are not desirable, but most modern communications receivers are fine. The radio signals are rising and falling "swooshing" noises. The chances of receiving a signal from Jupiter are about 1 in 6, according to several radio astronomers.

The antenna can be a simple dipole cut for the middle of the 18- to 24-MHz band, which happens to be a 15-m amateur radio band antenna. The antenna should be installed in the normal manner for any dipole, except that the wire must run east-west in order to pick up the southerly rising planet.

Figure 21-1 shows a broadband dipole that covers the entire frequency region of interest (18 to 24 MHz) by paralleling three different dipoles: one cut for 18 MHz, one cut for 21 MHz, and one cut for 24 MHz. The dimensions are

A	19.5 ft	24 MHz
B	22.3 ft	21 MHz
C	26 ft	18 MHz

There are several approaches to making this type of antenna. One is to use three-conductor wire, and cut the wires to the lengths indicated above. Another is to use a homemade spacer to spread the wires apart.

Ring antenna

Another popular jovian radio antenna is the ring radiator, two versions of which are shown in Fig. 21-2. This antenna is made of a 5-ft-diameter loop of ½-in-diameter soft-drawn copper plumbing pipe. The single-ended version is shown in Fig. 21-2A. In this antenna the loop is open-ended. The center conductor of the coaxial cable feedline is connected to one end of the ring radiator, while the coax shield is connected to the chicken wire ground plane. The balanced version (Fig. 21-2B) has an RF transformer (T_1) at the feedpoint.

The ring radiator antenna should have a bandpass preamplifier. The preamp is needed because of the low pickup of this kind of antenna, and that preamp should be mounted as close as possible to the antenna. The bandpass characteristic is obtained by filtering. The idea is to get rid of terrestrial signals in the adjacent bands. The typical preamplifier is broadbanded (which is what we want), so will pick up not only the desired signals but others as well (which is what we don't want). Even a 5-W CB transmitter a few blocks away can drive the preamplifier into saturation, so it's wise to eliminate the undesired signals before they get into the preamplifier. In the case of the single-ended amplifier, a single-ended preamplifier is used. But for the balanced version (Fig. 21-2B) a differential preamplifier is used.

The loop (both versions) is mounted about 7 or 8 in above a groundplane made of chicken wire, metal window screen, copper sheeting, or copper foil. The copper sheeting


1:1 BALUN
XFMR
A
A
C
C
B
B
75-OHM COAX
TO HF
RECEIVER

21-1 Wideband dipole such as might be used for Jupiter reception.


RING RADIATOR
COAX
TO
RCVR

21-2A Ring radiator: single-ended.



21-2B Ring radiator: balanced.

or foil is best, but costs a lot of money, and turns ugly green after a couple weeks in the elements. If you use screen, make sure that it is a metallic screen. Some window and porch screening material is made of synthetic materials that are insulators.

Figure 21-3A is a mechanical side view of the ring radiator antenna, while Fig. 21-3B is a side view. The antenna is mounted above the screen with insulators. These can be made of wood, plastic, or any other material. The frame holding the groundplane screen (Fig. 21-3B) can be made from 1 × 2-in lumber. Note that the frame has interior crosspieces to support the antenna, as well as the outer perimeter. The larger outer perimeter is needed because the screen groundplane should extend beyond the diameter of the radiator element by about 10 to 15 percent.

DDRR

The directional discontinuity ring radiator (DDRR) antenna is shown in Fig. 21-4A, while a side view showing the mounting scheme is shown in Fig. 21-4B. It is typically


ANTENNA ELEMENT
INSULATOR
SCREEN & FRAME
A
AMPL
COAX
TO
RCVR
B

21-3 Ring radiator mounted over a ground screen.



21-4A DDRR antenna.



21-4B DDRR antenna: side view.

mounted about 1 ft off the ground ($H=12$ in). The DDRR consists of two sections, one vertical and one horizontal. The short vertical section has a length equal to the height H of the antenna above the ground. One end of the vertical segment is grounded. The horizontal section is a loop with a diameter D.

The conductor diameter E is at least 0.5 in at 28 MHz, and 4 in at 4 MHz. Because of the loop, some people call this the hula hoop antenna. One author recommends using a 2-in automobile exhaust pipe bent into the correct shape by an auto muffler dealer. The far end of the loop is connected to ground through a small-value tuning capacitor C_1. The actual value of C_1 is found experimentally and is used to resonate the antenna to a particular operating frequency.

The feedline of the DDRR antenna is coaxial cable connected such that the shield is grounded at the bottom end of the vertical section. The center conductor is connected to the ring radiator a distance F from the vertical section. The length F is determined by the impedance that must be matched. The radiation resistance is approximated by

$$R_T = \frac{2620H^2}{\lambda_2} \qquad \textbf{[21.1]}$$

where

R_T is the radiation resistance, in ohms
H is the height of the antenna off the ground
λ is the wavelength

(Both H and λ are in the same units.)

The approximate values for the various dimensions of the DDRR are given below in general terms, with examples in Table 21-1:

D	0.078λ
H	$0.11D$
F	$0.25H$
E	0.5 to 4 in
G	See Table 21-1

Table 21-1. Examples of dimensions for DDRR

	Band (MHz)							
Dimension	**1.8**	**4**	**7.5**	**15**	**22**	**30**	**50**	**150**
G (in)	16	7	5	3	2.5	2	1.5	1
C_1 (pF)	150	100	75	35	15	12	10	6
F (in)	12	6	6	1.5	1.5	1	1	0.5
H (in)	48	24	11	6	4.75	3	1.5	1
D (ft)	36	18	9	4.5	3.33	2.33	1.4	6
E (in)	5	4	2	1	0.75	0.75	0.5	0.25

The construction details of the DDRR are so similar to those of the ring radiator that the same diagram can be used (see Fig. 21-3 again).

The normal attitude of the DDRR for communications is horizontal. However, for Jupiter radio reception, the antenna groundplane screen can be tilted to face Jupiter's point in the sky.

Helical antennas

The helical antenna (Fig. 21-5) provides moderately wide bandwidth and circular polarization. Because of the polarization some people find the helical antenna to be particularly well suited to radio astronomy reception. The antenna (of diameter D) will have a circumference C of 0.75λ to 1.3λ. The pitch of the helix (S) is the axial length of one turn, while the overall length $L=NS$ (where N is the number of turns). The ratio S/C should be 0.22λ to 0.28λ. At least three turns are needed to produce axial-mode main lobe maxima.

The diameter or edge of the groundplane G should be on the order of 0.8λ to 1.1λ if circular and/or square, respectively. The offset between the groundplane and the first turn of the helix is 0.12λ.

The approximate gain of the helical antenna is found from

$$\text{Gain} = 11.8+10\log(C^2NS) \qquad \text{dBi} \tag{21.2}$$

The pitch angle ϕ and turn length γ for the helical antenna are given by

$$\phi = \tan^{-1}\left(\frac{\pi D}{S}\right) \tag{21.3}$$

and

$$\gamma = \sqrt{(\pi D)^2+S^2} \tag{21.4}$$

The beamwidth of the helical antenna is

$$\Theta = \frac{K}{\sqrt{NS}} \tag{21.5}$$

where

Θ is the beamwidth, in degrees
N is the number of turns
S is the pitch, in wavelengths
C is the circumference, in wavelengths
K is 52 for the −3-dB beamwidth and 115 for the beamwidth to the first null in the pattern

The short section between the helix and the groundplane is terminated in a coaxial connector, allowing the antenna to be fed from the rear of the groundplane. The feedpoint impedance is approximately 140 Ω.

Multiple helical antennas

Stacking helical antennas allows a radiation pattern that is much cleaner than the normal one-antenna radiation pattern. It also provides a good way to obtain high gain with only a few turns in each helix. If two helixes are stacked, then the gain will be the same as for an antenna that is twice the length of each element, while for four stacked antennas the gain is the same as for a single antenna 4 times as long. Figure 21-6 shows a side view of the stacked helixes.

The feed system for stacked helixes is a little more complex than for a single helix. Figure 21-7A shows an end view of a set of four stacked helical antennas. Tapered lines (TL) are used to carry signal from each element and the coaxial connector (B). In this case, the coaxial connector is a feed-through “barrel” SO-239 device at the center of the groundplane (B). A side view of the tapered line system


S
G
D
C
A
SIDE VIEW
END VIEW

21-5 Helical antenna.



21-6 Dual/quad helical antenna.

Chap21_Carr 4/10/01 3:57 PM Page 430


A1
SA
B
SA
SCREEN
A2
SCREEN
A1
A3
TL
B
TL
A2
A4

B

A

21-7 Frontal view of quad helical antenna.

is shown in Fig. 21-7B. The length of the tapered lines is 1.06λ, while the center-to-center spacing between the helical elements is 1.5λ. The length of each side of the groundplane is 2.5λ. In the case of Fig. 21-7, the antenna is fed from the front of the groundplane.

Interferometer antennas

The resolution of an antenna is set by its dimensions a relative to the wavelength λ of the received signal. Better resolution can be achieved by increasing the size of the antenna, but that is not always the best solution. Figure 21-8 shows a *summation interferometer array.* Two antennas with aperture a are spaced S wavelengths apart. The radiation pattern is a fringe pattern (Fig. 21-9). This pattern consists of a series of maxima and nulls. The resolution angle ϕ to the first null is

$$\phi = \frac{S+a}{57.3} \tag{21.6}$$

The interferometer can be improved with additional antennas in the array. Professional radio astronomers use very wide baseline antennas. With modern communications it is possible to link radio telescopes on different continents to make the widest possible baseline.



21-8 Interferometer array.



21-9 Interferometer pattern.

22
CHAPTER

Adjusting, installing, and troubleshooting antennas and transmission lines

ANTENNA AND TRANSMISSION LINE MEASUREMENTS SHOULD BE MADE WHEN THE ANTENNA is first installed and periodically thereafter. If some difference in operation is noted, the same measurements should be repeated. Many antenna measurements are difficult to make with any degree of accuracy. There are some things about antennas that can and should be measured, however, regardless of the difficulty. For example, VSWR and the resonant frequency of the antenna are readily accessible. It's also possible to measure the impedance of the antenna feedpoint. You can measure the VSWR either with a special VSWR meter (often built into transmitters or antenna tuning units), or by using an RF wattmeter.

By frequency stepping through the band and testing the VSWR at various frequencies, one can draw a VSWR curve (Fig. 22-1) that shows how the antenna performs across the band. The resonant frequency is the point where the VSWR dips to a minimum (which may or may not be the much sought-after 1:1).

You can use the resonant frequency to figure out whether the antenna is too long (resonant frequency lower than the hoped-for design frequency), or too short (resonant frequency above the design frequency). Figure 22-2 shows all three situations. Curve A represents the desired or ideal curve that is centered on the desired frequency F_D. If the antenna is too long, however, the resonant frequency will be shifted downward towards F_1, and curve B will be observed. Similarly, if the antenna is too short, curve C will be found as the resonant frequency shifts upband to F_2.

But resonant frequency and VSWR curves are not the entire story because they don't tell us anything about the impedance presented by the antenna. One cannot get the VSWR to be 1:1 unless the antenna impedance and transmission line impedance are the same. For example, a dipole has a nominal textbook impedance of 73 Ω,

Copyright 2001 - the McGraw-Hill Companies



22-1 VSWR-vs-frequency plot.



22-2 VSWR-vs-frequency plot for three frequencies.

so it makes a very good match to 75-Ω coaxial cable. But the actual impedance of a real dipole may vary from a few ohms to more than 100 Ω. For example, if your antenna exhibits a feedpoint impedance of (say) 25 Ω, using 75-Ω coaxial cable to feed it produces a VSWR=75/25=3:1. Not too great. Measuring the feedpoint impedance is therefore quite important to making the antenna work properly.

There are any number of instruments on the market that will aid in making antenna measurements. Some of them are quite reasonably priced (or can be built), while others are beyond the reach of all but the most ardent and well-endowed enthusiasts. In this chapter we will look at a newer breed of more universal instrument called the *SWR analyzer.*

VSWR analyzers

One basic premise in this chapter is that the instruments used for measuring VSWR must be accessible to people who don't have a commercial or ham operator's license, as well as those who do (we must remember our SWL and scanner friends). Some of the instruments used by hams meet that requirement, but a relatively new breed of instrument called the SWR analyzer provides a lot of capability to the SWL, scanner operator, and ham radio operator alike. It uses a low-power RF signal generator and some clever circuitry to measure the VSWR of the antenna. One model also measures the feedpoint resistance.

The MFJ-259 VSWR analyzer (MFJ Enterprises, Inc., P.O. Box 494, Mississippi State, MS, 39762) is shown in Fig. 22-3. This instrument combines a VSWR analyzer with a digital frequency counter, and operates over the range 1.8 to 170 MHz. A band switch is set to the desired band, and then the *tune* control is set to the desired frequency. The meter will then read the VSWR at the design frequency. Alternatively, you can adjust the tune control until the minimum VSWR is found. This frequency is the actual, versus the desired, resonant frequency of the antenna. The front panel of the MFJ-259 has two meters, *SWR* and *RESISTANCE.* The SWR meter is calibrated up to 3:1, with a little uncalibrated scale to indicate higher SWRs.

The resistance meter is calibrated from 0 to 500 Ω, which is consistent with the SWR range. Two controls on the front panel are *tune* and *frequency* (a band switch). The MFJ-259 has a digital frequency meter to measure the operating frequency of the internal oscillator. This frequency counter can also be used to measure the frequency of external signal sources. (*Do not* connect the counter to the output of a transmitter; the instrument will be destroyed.) The top end of the MFJ-259 has a number of controls and connectors. An SO-239 UHF-style coaxial connector is provided for the antenna connection. A BNC coaxial connector is provided to apply external signal to the frequency counter, while a push button *input* switch is available to switch the counter from internal to external signal sources. Another push button switch is used to set the gate timing of the counter (a red LED on the front panel blinks every time the gate is triggered). The tuning is from 1.8 MHz to 174 MHz, while the counter will measure up to 200 MHz.

The MFJ-259 will work from an external 12-Vdc source, or from an internal battery pack consisting of eight size-AA standard cells. MFJ recommends that either alkaline or rechargeable batteries, rather than ordinary zinc-carbon cells, be used in order to reduce the possibility of leakage that can damage the instrument (this is good practice in all battery-powered instruments).

Unlike many lesser SWR meters, this instrument is not fooled by antennas that have impedances consisting of both resistance and reactance elements. An example in the manual demonstrates an impedance of $25+j25\ \Omega$ (i.e., R is 25 Ω and reactance X is also 25 Ω). When connected to a 50-Ω load one might be tempted to think the VSWR is 1:1, and some cheaper meters will so indicate. But the actual SWR is 2.6:1, which is what the MFJ-259 will read.


MFJ HF/VHF SWR ANALYZER
1.8-170 MHz
MODEL MFJ-259
FREQUENCY COUNTER
SWR
RESISTANCE
26.2-62.5
10-26.2
62.5-113
4-10
113-170
1.8-4
TUNE
FREQUENCY
MHz

22-3 MFJ-259 VSWR analyzer.

The resistance measurement assumes a resistive load (i.e., the measurement is made at the antenna's resonant frequency), and is referenced to 50 Ω. The VSWR and resistance measurements should be consistent with each other. If the VSWR is 2:1, then the resistance should be either 100 Ω (100/50 = 2:1) or 25 Ω (50/25 = 2:1). If the resistance is not consistent with the VSWR reading, then you should assume that the impedance has a significant reactive component and take steps to tune it out.

In addition to antenna measurements, the MFJ-259 is equipped to measure a wide variety of other things. It will measure the velocity factor of transmission line, help in tuning or adjusting matching stubs or matching networks, measure capacitance or inductance, and determine resonant frequency of *LC* networks.

Doping out coaxial cable

When you install an antenna, or do a bit of preventive maintenance, or find the antenna is not working properly, one thing to check is the transmission line. Two basic measurements are popular. Figure 22-4 shows how to make ohmic checks. The cable consists of an inner conductor and an outer conductor (shield). With terminals A and B open there should not be any resistive path across the input terminals (as shown). If a high resistance is seen, then there might be some contamination in the system, or the insulation has failed, permitting a current path. A low resistance indicates a short circuit. If the cable has been cut, or an object passed through, or the connector is messed up, then a short can result.

If terminals A-B are shorted together, a low resistance should be noted. If not, then it is likely that the center conductor is open. Of course, if connectors are on the line, either the shield or center conductor could be at fault.

The other issue is loss of the transmission line. Cable losses get higher as cables age, so low loss on installation does not guarantee low loss later on. Losses in new cables run from 0.2 dB/100 ft at 4 MHz. At 30 MHz the losses are 0.7 dB/100 ft to 2.6 dB/100 ft. At VHF/UHF frequencies the losses rise considerably.

Figure 22-5 shows a test setup for coaxial cable. It is necessary to know the length of the piece of coax under test. For ease of calculations a 100-ft section



22-4 Ohmmeter used to test coax.


M1
RF
WATTMETER
COAX BEING TESTED
M2
RF
WATTMETER
MATCHED
DUMMY LOAD
RF POWER
SOURCE

22-5 Attenuation test for coax.

should be used. Two RF power meters (M_1 and M_2) are used to measure the input power to the line (M_1) and the delivered power (M_2). The difference in power determines the loss. The loss is

$$\text{Loss}_{\text{dB}} = 10 \log \left(\frac{P_{M2}}{P_{M1}} \right) \qquad \textbf{[22.1]}$$

where

Loss is the loss of the cable, in dB
P_{M1} is the power reading on M_1
P_{M2} is the power reading on M_2

If the cable length is 100 ft, then you already have the loss in dB/100 ft. But if length L is anything other than 100 ft, then you need to make the following calculation:

$$\text{Loss}_{\text{dB/100ft}} = \frac{\text{Loss}_{\text{dB}}}{\text{L}_{\text{ft}}} \times 100 \qquad \textbf{[22.2]}$$

23
CHAPTER

Antennas for radio direction finding (RDF)

RADIO DIRECTION FINDING IS THE ART AND PRACTICE OF EITHER LOCATING YOURSELF OR A radio station by using a directional radio antenna and receiver. When the FCC wants to locate an illegal station that is transmitting, they will use radio direction finders to triangulate the position. If they find the bearing from two stations they will locate the station at the intersection. However, there is a fair degree of ambiguity in the measurement. As a result, radio direction finders typically use three or more (hence "*tri*angulate") sites. Each receiving site that can find the bearing to the station reduces the overall error.

At one time aviators and seafarers relied on radio direction finding. It is said that the Japanese air fleet that attacked Pearl Harbor, Hawaii, on December 7, 1941 homed in on a Honolulu AM radio station. During the 1950s and early 1960s AM radios came with two little circled triangle marks at the 640-kHz and 1040-kHz points on the dial. These were the CONALRAD frequencies that you could tune to in case of a nuclear attack (right before you kissed your butt good-bye, I suspect). All other radio stations were off the air except the CONALRAD stations. The enemy was prevented from using these frequencies for RDF because the system used several stations that transmitted in a rapidly rotating pattern. No one station was on the air long enough to allow a "fix." The result was a wavering sound to the CONALRAD station (which we heard during tests) that would confuse any enemy who tried to DX his way into our cities with nuclear weapons.

Radio direction finders based on the AM broadcast band (BCB) looked a bit like Fig. 23-1. A receiver with an S meter (which measures signal strength) is equipped with a rotatable ferrite loopstick antenna to form the RDF unit. A degree scale around the perimeter of the antenna base could be oriented toward north so that the bearing could be read.

Loopstick antennas have a figure-8 reception pattern (Fig. 23-2A) with the maxima parallel to the loopstick rod and the minima off the ends of the rod. When the antenna is pointed at the signal, maximum reception strength is achieved. Unfortunately, the maxima are so broad that it is virtually impossible to find the true point on the compass dial where the signal peaks. The peak is too shallow for that

Copyright 2001 - the McGraw-Hill Companies


ROTATABLE
LOOPSTICK
ANTENNA
CALIBRATED
DEGREES
SCALE
1390 KHz
S-METER

23-1 Radio direction finding (RDF) receiver using a loopstick antenna.



23-2A Pattern of loopstick antenna: not oriented towards signal.



23-2B Pattern of loopstick antenna: oriented towards signal.

purpose. Fortunately, the minima are very sharp. You can get a good fix on the direction of the signal by pointing the minima toward the station. This point is found by rotating the antenna until the audio goes to zip or the S meter dips to a minimum (Fig. 23-2B).

The loopstick is a really neat way to do RDF—except for one little problem: The darn thing is bidirectional. There are two minima because, after all, the pattern is a figure 8. You will get exactly the same response from placing either minima in the direction of the station. As a result, the unassisted loopstick can only show you a line along which the radio station is located, but can't tell you which direction it is. Sometimes this doesn't matter. If you know the station is in a certain city, and that you are generally south of the city, and can distinguish the general direction from other clues, then the line of minima of the loopstick will refine that information. A compass helps, of course. Shortly we will take a look at an impromptu radio direction finder using a portable radio.

The solution to the ambiguity problem is to add a sense antenna to the loopstick (Fig. 23-3). The sense antenna is an omnidirectional vertical whip, and its signal is combined with that of the loopstick in an *RC* phasing circuit. When the two patterns are combined, the resultant pattern will resemble Fig. 23-4. This pattern is called a *cardioid* because of the heart shape it exhibits. This pattern has only one null, so it resolves the ambiguity of the loopstick used alone.



23-3 Addition of sense antenna overcomes directional ambiguity of the loopstick.



23-4 Cardioid pattern of sense-plus-loopstick antennas.

Field improvisation

Let's suppose you are out in the woods trekking around the habitat of lions, tigers, and bears (plus a rattlesnake or two for good measure). Normally you find your way with a compass, a Geological Survey 7.5-min topological map, and a Global Positioning System (GPS) receiver. Those little GPS marvels can give you real good latitude and longitude indication. But what happens if it breaks or a bear eats it? The answer to your direction finding problem might be the little portable AM BCB radio (Fig. 23-5) that you brought along for company.

Open the back of the radio and find the loopstick antenna. You will need to know which axis it lies along. In the radio shown in Fig. 23-5 the loopstick is along the top of the radio, from left to right. In other radios it is vertical, from top to bottom. Once you know the direction, you can tune in a known AM station and orient the radio until you find a null. Your compass can give you the bearing. If you know the approximate location of the station, then you can reverse the compass direction from it and mark the line on the topo map. Of course, it's still a bidirectional indication, so all you know is the line along which you are lost.

But then you tune into a different station in a different city (or at least wide enough from the line to the other station to make a difference) and take another reading. Your approximate location is where the two lines cross. Take a third, fourth, and fifth reading and you will home in pretty tight. If you were smart enough to plan ahead, you will have selected candidate stations in advance and located their latitude and longitude. Alternatively, you would have bought the topo map that covers their location as well as where you want to hike, and from those maps you can find the latitudes and longitudes of the distant stations.



23-5 AM portable radio. Dark bar represents position and direction of internal loopstick.

Regular loop antennas

Regular wire loop antennas (Fig. 23-6) are also used for radio direction finding. In fact, in some cases the regular loop is preferred over the loopstick. The regular loop antenna may be square (as shown), circular, or any other regular "n-gon" (e.g., hexagon), although for practical reasons the square is easier to build. The loop has pretty decent inductance even with only a few turns. One loop I built was 24 in square (A in Fig. 23-6) and had, if I recall correctly, about 10 turns of wire spaced over a 1-in width (B in Fig. 23-6). It resonated to the AM BCB with a standard 365-pF "broadcast" variable capacitor.

When you use a regular loop antenna be aware that the antenna has a figure-8 pattern like the loopstick, but it is oriented 90° out of phase with the loopstick antenna. In the regular loop the minima (nulls) are perpendicular to the plane of the loop, while the maxima are off the sides. In Fig. 23-6 the minima are in and out of the page, while the maxima are left and right (or top and bottom).

Fox hunting

An activity popular with ham radio operators in the 1960s was "fox hunting." A fiendishly clever ham (the "fox") would go hide with a mobile or portable transmitter (usually on either 10 or 75 m). The "hunters" would then RDF the fox's brief transmissions and try to locate the transmitter. If you could locate the antenna, you located the station (according to the most common set of rules). Sometimes the hunt got a little wild as hunters raced each other (a no-no) in the final stretch.

One friend of mine had an interesting experience. He drove a 1949 Plymouth that was painted hideous dark green with fire-engine-red hub caps. It looked just plain awful (especially since the paint looked like it was put on with a whisk broom!). He used a Gonset converter linked to the AM BCB receiver installed in the car. The antenna was a wire loop on the end of a broom handle, similar to Fig. 23-7. The antenna was mounted about where you would expect the left-side rear view mirror to be located. He could reach his hand out the window and rotate the antenna while listening for the minima on the receiver. Worked rather well, and he won some fox hunts.

The fox hunts in his area were usually held on Saturday or Sunday morning, and after it was all over the whole crew would get to a restaurant for brunch or beer or something. One morning, however, my buddy with the hideous green car was racing down a residential street to be the first to the transmitter. Others were in the area, and the end game was in motion. Unfortunately, a little old lady called the police complaining about a "…nut racing up and down the street in a strange car waving a cross out the window." Breakfast had to wait that morning, I bet.

Shortwave and AM BCB "skip" RDF

Radio direction finding is most accurate over relatively short distances. If you can use the ground wave, then all the better (which is what you use during daylight hours for nearly all AM BCB stations). Skip rolls in on the AM BCB after local



23-6 Wire loop antenna.



23-7 "…waving a cross out the window" antenna.

sundown, so you can hear all manner of stations all up and down the dial. You can RDF distant stations. Some rather interesting sites have turned up when SWL DXers RDF'ed some of the infamous “numbers stations.” Those stations transmit either CW or voice numbers groups, and are believed to be sending messages to spies around the world. RDFing by DXers has located some of these transmitters at, well, “interesting” sites.

Unfortunately, there are some problems with skip RDFing. When we look at propagation drawings of skip in textbooks we usually see a one plane view. The curvature of the earth shows, as does the transmitter and receiver site. A “pencil beam” radio signal travels at some angle up the ionosphere, where it is “reflected” (actually, it's a refraction phenomenon but looks like reflection to an observer on the surface) back to earth. We can tell from the drawing that the angle of incidence equals the angle of reflection, just like they told us in high school science classes. Oops! The real world is not so neat and crisp, however.

In the real world the wave might encounter a different ionization density along its path of travel and therefore be deflected from its original path. It might return to earth at a location offset from the direction it appears. If we look at the true bearing from the receiver site to the transmitter site, and then note the azimuthal angle of arrival of the signal, we note that something is amiss.

Actual reflection also causes some problems, especially when RDFing a station in the high end of the HF band or the VHF/UHF bands. Radio waves will reflect from geological features such as mountains, as well as man-made structures (e.g., buildings). If the reflection is strong enough it might appear to be the real signal, and cause a severe error in RDFing. Be wary of RDF results when the “skip is in.”

Sense antenna circuit

Figure 23-8 shows a method for summing together the signals from an RDF antenna (such as a loop) and a sense antenna. The two terminals of the loop are connected to the primary of an RF transformer. This primary (L_{1A}) is center-tapped and the center tap is grounded. The secondary of the transformer (L_{1B}) is resonated by a variable capacitor C_1. The dots on the transformer coils indicate the 90° phase points.

The top of L_{1B} is connected to the sense circuit, and to the receiver antenna input. The phasing control is a potentiometer (R_1). The value of this pot is usually 10 to 100 kΩ, with 25 kΩ being a commonly seen value. Switch S_1 is used to take the sense antenna out of the circuit. The reason for this switch is that the nulls of the loop or loopstick are typically a lot deeper than the null on the cardioid pattern. The null is first located with the switch open. When the switch is closed you can tell by the receiver S meter whether or not the correct null was used. If not, then reverse the direction of the antenna and try again.

Adcock antennas

The Adcock antenna has been around since 1919 when it was patented by F. Adcock. Figure 23-9 shows the basic Adcock RDF array. This antenna consists of two center-fed nonresonant (but identical) vertical radiators. Each side of each element is at least 0.1λ long, but need not be resonant (which means the antenna can be used



23-8 Sense circuit for a loop/sense antenna RDF.

over a wide band). The elements are spaced from 0.1λ to 0.75λ, although the example shown here is spaced 0.125λ.

The Adcock antenna is vertically polarized, so it will respond to the vertically polarized wave very much like loop or phased array antennas of similar size. The horizontally polarized wave, however, affects all elements the same, so the currents are essentially cancelled, resulting in no pattern. This characteristic makes the Adcock antenna suitable for high-frequency shortwave RDFing.

The pattern for an Adcock antenna is shown in Fig. 23-10. This pattern was generated using the NecWin Basic for Windows program (Chap. 17). The example antenna is a 10-MHz (30-m band) Adcock that uses 1.455-m elements (total 2.91 m on each side), spaced 4 m apart. The pattern is a traditional figure-8 with deep nulls at 0° and 180°. The antenna can be rotated to find a null in the same manner as a loop.

Watson-Watt Adcock array

Figure 23-11 shows the Watson-Watt Adcock RDF array. It consists of two Adcock arrays arranged orthogonally to each other. It is common practice to arrange one Adcock in the east-west direction and the other in the north-south direction. These are fed to identical receivers that are controlled by a common local oscillator (LO). The outputs of the receivers are balanced, and are used to drive the vertical and horizontal plates of a cathode-ray oscilloscope (CRO). Figure 23-12 shows the patterns achieved by signals of various phases arriving at the Watson-Watt array. The patterns of Figs. 23-12A and 23-12B are made from signals 180° out of phase, while the signal of Fig. 23-12C has a 90° phase difference.


0.125 λ
0.1λ
0.1λ
0.1λ
0.1λ

23-9 Adcock array RDF antenna.



23-10 Adcock pattern.


EAST
NORTH
SOUTH
WEST
OSCILLOSCOPE
E-W RCVR
N-S RCVR
V
H

23-11 Watson-Watt Adcock array.



23-12 Patterns for different signals on the Watson-Watt array.

Doppler RDF antennas

Figure 23-13 shows the basic concept of a Doppler RDF antenna. The Doppler effect was discovered in the nineteenth century. A practical example of the Doppler effect is seen when a wailing ambulance siren is approaching you, and then passes you and heads away from you. The wailing pitch will rise as the sound source approaches, and then fall as the sound source recedes in the opposite direction.

In a radio system, when the antenna and signal source move with respect to each other, a Doppler shift is generated. This shift is proportional to the relative speed difference. The Doppler RDF antenna of Fig. 23-13 uses a rotating antenna. The signal approaches from a single direction, so there will be a predictable Doppler shift at any point on the circular path of the antenna. The magnitude of the phase shift is

$$S = \frac{R\omega F_c}{c} \qquad \textbf{[23.1]}$$



23-13 Doppler antenna.

where

S is the Doppler shift, in hertz
R is the radius of rotation, in meters
ω is the angular velocity of the antenna, in radians per second
F_c is the carrier frequency of the incoming signal, in hertz
c is the velocity of light (3×10^8 m/s)

In theory this antenna works nicely, but in practice there are problems. One of the big problems is getting a large enough Doppler shift to easily measure. Unfortunately, the rotational speed required of the antenna is very high—too high for practical use. However, the effect can be simulated by using a number of antennas, arranged in a circle, that are sequentially scanned. The result is a piecewise approximation of the effect seen when the antenna is rotated at high speed.

Wullenweber array

One of the problems associated with small RDF antennas is that they have such a small aperture that relatively large distortions of their pattern result from even small anomalies. Follow that? What it means is that the pattern is all messed up by small defects. If you build a wide-aperture direction finder (WADF), however, you can average the signals from a large number of antenna elements distributed over a large-circumference circle. The Wullenweber array (Fig. 23-14) is such an antenna. It consists of a circle of vertical elements. In the HF band the circle can be 500 to 2000 ft in diameter.

A goniometer rotor spins inside the ring to produce an output that will indicate the direction of arrival of the signal as a function of the position of the goniometer. The theoretical resolution of the Wullenweber array is on the order of 0.1°, although practical resolutions of about 2.8° are commonly seen.



23-14 Wullenweber RDF array.

Time difference of arrival (TDOA) array

If you erect two antennas with distance *d* apart, then arriving signals can be detected by examining the time-of-arrival difference. Figure 23-15A shows an example signal. If the advancing wavefront is parallel to the line between the antennas, then it will arrive at both antennas at the same time. The TDOA is zero in that case. But if the signal arrives at an angle (as in Fig. 23-15A), it will arrive at one antenna first. From the difference between the time of arrival at the two antennas we can discern the direction of arrival.

There is an ambiguity in the basic TDOA array in that the combined output will be the same for conjugate angles, i.e. at the same angle from opposite directions. This problem can be resolved by the system shown in Fig. 23-15B. The signals from ANT1 and ANT2 are designated V_1 and V_2, respectively. These signals are detected by receivers (RCVR1 and RCVR2), and are then threshold detected in order to prevent signal-to-noise problems from interfering with the operation. The outputs of the threshold detectors are used to trigger a sawtooth generator that controls the horizontal sweep on an oscilloscope.

The two signals are then delayed, and one is inverted. The reason for inverting one signal is to allow the operator to distinguish them on the CRT screen. The reason why this is necessary is the ambiguity. If the antennas in Fig. 23-15A are arrayed east to west, then the line perpendicular to the line between them is north to south.

If we designate north as 0°, then the signal shown arrives at an angle of 330°. That means it will arrive at ANT1 before it arrives at ANT2. A signal arriving from a bearing of 30° will produce the same output signal, even though it arrives at ANT2 before ANT1. All signals of bearing $0 \leq x < 180°$ will arrive at ANT2 first, while all


ANT1
ANT2
ADVANCING WAVEFRONT
V1
V2

23-15A Time difference of arrival (TDOA) RDF array.


V1
RCVR1
THRESHOLD DETECTOR
DELAY
INVERTER
V2
RCVR2
THRESHOLD DETECTOR
DELAY
OSCILLOSCOPE
TRIGGER SWEEP TIMEBASE GENERATOR
H
V

23-15B Block diagram of typical TDOA circuit.

signals 180 ≤ x < 360° will arrive at ANT1 first. Yet both will produce the same blip on the oscilloscope screen. The solution to discerning which of the two conjugate angles is intended is to invert the ANT1 signal. When this is done, the ANT1 signal falls below the baseline on the CRT screen, while the ANT2 signal is above the baseline. By noting the time difference between the pulses, and their relative position, we can determine the bearing of the arriving signal.

Switched-pattern RDF antennas

Suppose we have a unidirectional pattern such as the cardioid shown in Fig. 23-16. If we can rapidly switch the pattern back and forth between two directions that are 180° apart, then we can not only discern direction, but also we can tell whether an off-axis signal is left or right. This feature is especially useful for mobile and portable direction finding.

In Fig. 23-16 we have three different positions for a signal source. When the signal source is at point *A,* it will affect the pattern to the left more than the pattern to the right, so the meter will read left. If the signal source is at point *B,* on the other hand, the signal affects both pattern positions equally, so the meter reads zero. Finally, if the signal arrives from point *C,* it affects the right-hand pattern more than the left-hand pattern, so the meter reads right.

Figure 23-17 shows how such a system can be constructed. This system has been used by amateur radio operators with "rubber ducky" VHF antennas and a sin-



23-16 Switched-pattern RDF system.


ANT-1
ANT-2
D1
HALF WAVELENGTH LINE
HALF WAVELENGTH LINE
D2
RFC1
RFC2
TRANSMISSION LINE TO RECEIVER
RFC3
SQUARE WAVE GENERATOR
C1
470 pF
J1
TO RCVR
+V
0V
-V

23-17 Double-ducky RDF system based on the switched-pattern system.

gle receiver, where it is commonly called the *double-ducky direction finder* (DDDF). The antennas are spaced from 0.25 λ to 1λ apart over a good groundplane (such as the roof of a car or truck). If no groundplane exists, then a sheet metal groundplane should be provided.

In Fig. 23-17 we see the antennas are fed from a common transmission to the receiver. In order to keep them electrically the same distance apart, a pair of identical half-wavelength sections of transmission line are used to couple to the antennas.

Switching is accomplished by using a bipolar square wave and PIN diodes. The bipolar square wave (see inset to Fig. 23-17) has a positive peak voltage and a negative peak voltage on opposite halves of the cycle. The PIN diodes (D_1 and D_2) are connected in opposite polarity to each other. Diode D_1 will conduct on negative excursions of the square wave, while D_2 conducts on positive excursions. The antenna connected to the conducting diode is the one that is connected to the receiver, while the other one is parasitic. The active antenna therefore switches back and forth between ANT1 and ANT2.

This antenna is coupled to the receiver through a small-value capacitor (C_1) so that the square wave does not enter the receiver. This allows us to use the transmission line for both the RF signal and the switching signal. An RF choke (RFC_3) is used to keep RF from the antenna from entering the square-wave generator.

The DDDF antenna produces a phase modulation of the incoming signal that has the same frequency as the square wave. This signal can be heard in the receiver output. When the signal's direction of arrival is perpendicular to the line between the two antennas, the phase difference is zero, so the audio tone disappears.

The pattern of the DDDF antenna is bidirectional, so there is the same ambiguity problem as exists with loop antennas. The ambiguity can be resolved by either of two methods. First, a reflector can be placed $\lambda/4$ behind the antennas. This is attractive, but it tends to distort the antenna pattern a little bit. The other method is to rotate the antenna through 90° (or walk an L-shaped path).

Conclusion

Radio direction finding can be very useful for locating RF noise sources, illegal stations, and other RF sources. It can also be used to locate yourself if you can get bearings on at least two stations. The lines of bearing will cross at a location approximately where you are standing—try it, you'll like it.

24
CHAPTER

Impedance matching in antenna systems

ONE OF THE FIRST THINGS THAT YOU LEARN IN RADIO COMMUNICATIONS AND broadcasting is that antenna impedance must be matched to the transmission line impedance, and that the transmission line impedance must be matched to the output impedance of the transmitter. The reason for this requirement is that maximum power transfer, between a source and a load, always occurs when the system impedances are matched. In other words, more power is transmitted from the system when the load impedance (the antenna), the transmission line impedance, and the transmitter output impedance are all matched to each other.

Of course, the trivial case is where all three sections of our system have the same impedance. For example, we could have an antenna with a simple 75-Ω resistive feedpoint impedance (typical of a half-wave dipole in free space), and a transmitter with an output impedance that will match 75 Ω. In that case, we need only connect a standard-impedance 75-Ω length of coaxial cable between the transmitter and the antenna. Job done! Or so it seems.

But there are other cases where the job is not so simple. In the case of our "standard" antenna, for example, the feedpoint impedance is rarely what the books say it should be. That ubiquitous dipole, for example, is nominally rated at 73 Ω, but even the simplest antenna books tell us that value is an approximation of the theoretical free-space impedance. At locations closer to the earth's surface, the impedance could vary over the approximate range of 30 to 130 Ω and it might have a substantial reactive component.

But there is a way out of this situation. We can construct an impedance-matching system that will marry the source impedance to the load impedance. This chapter examines several matching systems that might prove useful in a number of antenna situations.

Copyright 2001 - the McGraw-Hill Companies

Impedance-matching approaches

Antenna impedance can contain both reactive and resistive components. In most practical applications, we are searching for a purely resistive impedance ($Z = R$), but that ideal is rarely achieved. A dipole antenna, for example, has a theoretical free-space impedance of 73 Ω at resonance. As the frequency applied to the dipole is varied away from resonance, however, a reactive component appears. When the frequency is greater than resonance, then the antenna tends to look like an inductive reactance, so the impedance is $Z = R + jX$. Similarly, when the frequency is less than the resonance frequency, the antenna looks like a capacitive reactance, so the impedance is $Z = R - jX$. Also, at distances closer to the earth's surface the resistive component may not be exactly 73 Ω, but may vary from about 30 to 130 Ω. Clearly, whatever impedance coaxial cable is selected to feed the dipole, it stands a good chance of being wrong.

The method used for matching a complex load impedance (such as an antenna) to a resistive source (the most frequently encountered situation in practical radio work) is to interpose a matching network between the load and the source (Fig. 24-1). The matching network must have an impedance that is the *complex conjugate* of the complex load impedance. For example, if the load impedance is $R + jX$, then the matching network must have an impedance of $R - jX$; similarly, if the load is $R - jX$ then the matching network must be $R + jX$. The sections to follow look at some of the more popular networks that accomplish this job.

L-section network

The L-section network is one of the most used, or at least the most published, antenna matching networks in existence: it rivals even the pi network. A circuit for the L-section network is shown in Fig. 24-2A. The two resistors represent the source (R_1) and load (R_2) impedances. The elementary assumption of this network is that $R_1 < R_2$. The design equations are

$$R_1 < R_2 \text{ and } 1 < Q < 5 \qquad \textbf{[24.1]}$$


SOURCE
MATCHING DEVICE
LOAD
Resistive output or source impedance
Complex conjugate impedance network
Complex impedance load
Z_S
Z'_L
Z_L

$Z_S = R$

If:

$Z_L = R + jX$, then $Z'_L = R - jX$

$Z_L = R - jX$, then $Z'_L = R + jX$

24-1 Transmitter, matcher, and antenna system.



24-2 (A) L-section network; (B) reverse L section; (C) inverted L-section network.

$$X_L = 6.28FL = Q \times R_1 \qquad \textbf{[24.2]}$$

$$X_C = \frac{1}{6.28FC} \qquad \textbf{[24.3]}$$

$$Q = \sqrt{\frac{R_2}{R_1} - 1} \qquad \textbf{[24.4]}$$

also,

$$Q = \frac{X_\mathrm{L}}{R_1} = \frac{R_2}{X_\mathrm{C}} \qquad \textbf{[24.5]}$$

You will most often see this network published in conjunction with less-than-quarter-wavelength longwire antennas. One common fault of those books and articles is that they typically call for a "good ground" in order to make the antennas work properly. But they don't tell you (1) what a "good ground" is and (2) how you can obtain it. Unfortunately, at most locations a good ground means burying a lot of copper conductor—something that most of us cannot afford. In addition, it is often the case that the person who is forced to use a longwire, instead of a better antenna, cannot construct a "good ground" under any circumstances because of landlords (and/or logistics) problems. The very factors that prompt the use of a longwire antenna in the first place also prohibit any form of practically obtainable "good ground." But there is a way out: *radials*. A good ground can be simulated with a counterpoise ground constructed of quarter-wavelength radials. These radials have a length in feet equal to $246/F_{\text{MHz}}$, and as few as two of them will work wonders. Another form of L-section network is shown in Fig. 24-2B. This circuit differs from the previous circuit in that the roles of the L and C components are reversed. As you might suspect, this role reversal brings about a reversal of the impedance relationships: in this circuit the assumption is that the driving source impedance R_1 is larger than the load impedance R_2 (i.e., $R_1 > R_2$). The equations are shown below:

$$R_2 > R_1 \tag{24.6}$$

$$X_L = R_2 \sqrt{\frac{R_1}{(R_2 - R_1)}} \tag{24.7}$$

$$X_C = \frac{(R_1 R_2)}{X_L} \tag{24.8}$$

Still another form of L-section network is shown in Fig. 24-2C. Again, we are assuming that driving source impedance R_1 is larger than load impedance R_2 (i.e., $R_1 > R_2$). In this circuit, the elements are arranged similar to Fig. 24-2A, with the exception that the capacitor is at the input rather than the output of the network. The equations governing this network are:

$$R_1 > R_2 \text{ and } 1 < Q < 5 \tag{24.9}$$

$$X_L = 6.28FL = \sqrt{(R_1 R_2) - (R_2)^2} \tag{24.10}$$

$$X_C = \frac{1}{6.28FC} = \frac{R_1 R_2}{X_L} \tag{24.11}$$

$$C = \frac{1}{6.28FX_C} \tag{24.12}$$

$$L = \frac{X_L}{6.28F} \tag{24.13}$$

Thus far, we have considered only matching networks that are based on inductor and capacitor circuits. But there is also a possibility of using transmission line segments as impedance-matching devices. Two basic forms are available to us: quarter-wave sections and the series matching section.

Pi networks

The pi network shown in Fig. 24-3 is used to match a high source impedance to a low load impedance. These circuits are typically used in vacuum tube RF power amplifiers that need to match low antenna impedances. The name of the circuit comes from its resemblance to the Greek letter pi. The equations for the pi network are:

$$R_1 > R_2 \text{ and } 5 < Q < 15 \tag{24.14}$$

$$Q > \sqrt{\frac{R_1}{R_2} - 1} \tag{24.15}$$

$$X_{C2} = \frac{R_2}{\sqrt{\left(\frac{R_2}{R_1}\right)(1 + Q^2) - 1}} \tag{24.16}$$

$$X_{C1} = \frac{R_1}{Q}$$

$$X_L = \frac{R_1\,\{(Q + (R_2/X_{C2})\}}{Q^2 + 1} \tag{24.17}$$

Split-capacitor network

The split-capacitor network shown in Fig. 24-4 is used to transform a source impedance that is less than the load impedance. In addition to matching antennas, this circuit is also used for interstage impedance matching inside communications equipment. The equations for design are

$$R_1 < R_2 \tag{24.18}$$

$$Q > \sqrt{\frac{R_1}{R_2} - 1} \tag{24.19}$$

$$X_L = \frac{R_2}{Q} \tag{24.20}$$



24-3 Pi network.



24-4 Split-capacitor network.

$$X_{C1B} = \sqrt{\frac{R_1 (Q_2 + 1)^2}{R_2}} - 1 \qquad \textbf{[24.21]}$$

$$X_{C1A} = \frac{R_2\, Q}{Q^2 + 1} \left(1 - \frac{R_1}{Q\, X_{C1A}} \right) \qquad \textbf{[24.22]}$$

Transmatch circuit

One version of the *transmatch* is shown in Fig. 24-5. This circuit is basically a combination of the split-capacitor network and an output tuning capacitor (C_2). For the HF bands, the capacitors are on the order of 150 pF per section for C_1, and 250 pF for C_2. The collar inductor should be 28 μH. The transmatch is essentially a coax-to-coax impedance matcher, and is used to trim the mismatch from a line before it affects the transmitter.



24-5 Split-capacitor transmatch network.

Perhaps the most common form of transmatch circuit is the tee network shown in Fig. 24-6. This network is lower in cost than some of the others, but suffers a problem. Although it does, in fact, match impedance (and thereby, in a naive sense, “tunes out” VSWR on coaxial lines), it also suffers a high pass characteristic. The network, therefore, does not reduce the harmonic output of the transmitter. The simple tee network does not serve one of the main purposes of the antenna tuner: harmonic reduction.

An alternative network, called the *SPC transmatch*, is shown in Fig. 24-7. This version of the circuit offers harmonic attenuation, as well as matching impedance.

Figure 24-8 shows commercially available antenna tuners based on this transmatch design. The unit shown in Fig. 24-8A is manufactured by MFJ Electronics, Inc. It contains the usual three tuning controls, here labeled *transmitter, antenna, and inductor*. Included in this instrument is an antenna selector switch that allows the operator to select a coax antenna through the tuner, to connect input to output (coax) without regard to the tuner, select a balanced antenna, or connect an internal dummy load. The instrument also contains a multifunction meter that can measure 200 W or 2000 W (full scale), in either forward or reverse directions. In addition, the meter operates as a VSWR meter.



24-6 Tee-network transmatch.



24-7 Improved transmatch offers harmonic attenuation.

Figures 24-8B through 24-8D show an imported tuner from the United Kingdom. This instrument, called the *Nevada* model, is a low-cost model, but contains the three basic controls. For proper operation, an external RF power meter, or VSWR meter, is required. The tuner is shown in Fig. 24-8B; also shown is a Heathkit transmatch antenna tuner. The rear panel of the Nevada instrument is shown in Fig. 24-8C. There are SO-239 coaxial connectors for input and unbalanced output, along with a pair of posts for the parallel line output. A three-post panel is used to select which antenna the RF goes to: unbalanced (coax) or parallel. The internal circuitry of the *Nevada* is shown in Fig. 24-8D. The roller inductor is in the center and allows the user to set the tuner to a wide range of impedances over the entire 3- to 30-MHz HF band.

MFJ VERSA TUNER II
TRANSMITTER
ANTENNA SELECTOR
COAX
ANTENNA
INDUCTOR
DUMMY LOAD
WIRE BAL LINE
COAX DIRECT
SWR SET
METER
MFJ

24-8A MFJ antenna tuner.

24-8B Author's Heathkit antenna tuner and the Nevada tuner from the United Kingdom.



24-8C Rear of Nevada tuner.



24-8D Inside of Nevada tuner.

Coaxial cable BALUNS

A balun is a transformer that matches an unbalanced resistive source impedance (such as a coaxial cable), to a "balanced" load (such as a dipole antenna). With the circuit of Fig. 24-9, we can make a balun that will transform impedance at a 4:1 ratio, with $R_2 = 4 \times R_1$. The length of the balun section of coaxial cable is

$$L_{\text{ft}} = \frac{492V}{F_{\text{MHz}}} \qquad \textbf{[24.23]}$$

where:

L_{ft} is the length, in feet
V is the velocity factor of the coaxial cable (a decimal fraction)
F_{MHz} is the operating frequency, in megahertz

Matching stubs

A shorted stub can be built to produce almost any value of reactance. This fact can be used to make an impedance-matching device that cancels the reactive portion of a complex impedance. If we have an impedance of $Z = R + j30\ \Omega$ we need to make a stub with a reactance of $-j30\ \Omega$ to match it. Two forms of matching stub are shown in Figs. 24-10A and 24-10B. These stubs are connected exactly at the feedpoint of the complex load impedance, although they are sometimes placed farther back on the line at a (perhaps) more convenient point. In that case, however, the reactance required will be transformed by the transmission line between the load and the stub.



24-9 Coaxial balun transformer.


Load impedance
$Z = R \pm jX$
Matching stub
Transmission line to source

24-10A Stub match scheme.



24-10B Coaxial stub matching.

Quarter-wave matching sections

Figure 24-11 shows the elementary quarter-wavelength transformer section connected between the transmission line and the antenna load. This transformer is also sometimes called a *Q section*. When designed correctly, this transmission line transformer is capable of matching the normal feedline impedance Z_s to the antenna feedpoint impedance Z_R. The key factor is to have available a piece of transmission line that has an impedance Z_o of

$$Z_o = \sqrt{Z_s Z_R} \qquad \textbf{[24.24]}$$

Most texts show this circuit for use with coaxial cable. Although it is certainly possible, and even practical in some cases, for the most part there is a serious flaw in using coax for this project. It seems that the normal range of antenna feedpoint impedances, coupled with the rigidly fixed values of coaxial-cable surge impedance available on the market, combines to yield unavailable values of Z_o. Although there are certainly situations that yield to this requirement, many times the quarter-wave section is not usable on coaxial-cable antenna systems having standard impedance values.

On parallel transmission line systems, on the other hand, it is quite easy to achieve the correct impedance for the matching section. We use the equation above to find a value for Z_o, and then calculate the dimensions of the parallel feeders. Be-



24-11 Quarter-wavelength Q section.

cause we know the impedance, and can more often than not select the conductor diameter from available wire supplies, you can use the equation below to calculate conductor spacing:

$$S = D \times 10^{(Z/276)} \qquad \textbf{[24.25]}$$

where

S is the spacing
D is the conductor diameter
Z is the desired surge impedance.
From there you can calculate the length of the quarter-wave section from the familiar $246/F_{\mathrm{MHz}}$. D *and* S are in the same units.

Series matching section

The quarter-wavelength section, covered in the preceding section, suffers from drawbacks: it must be a quarter-wavelength and it must use a specified (often nonstandard) value of impedance. The series matching section is a generalized case of the same idea, and it permits us to build an impedance transformer that overcomes these faults. According to *The ARRL Antenna Book*, this form of transformer is capable of matching any load resistance between about 5 and 1200 Ω. In addition, the transformer section is not located at the antenna feedpoint.

Figure 24-12 shows the basic form of the series matching section. There are three lengths of coaxial cable: L_1, L_2, and the line to the transmitter. Length L_1 and the line to the transmitter (which is any convenient length) have the same characteristic impedance, usually 75 Ω. Section L_2 has a different impedance from L_1 and the line to the transmitter. Note that only standard, easily obtainable values of impedance are used here.

The design of this transformer consists of finding the correct lengths for L_1 and L_2. You must know the characteristic impedance of the two lines (50 Ω and 75 Ω given as examples), and the complex antenna impedance. In the case where the antenna is non resonant, this impedance is of the form $Z = R \pm jX$, where R is the resistive portion, X is the reactive portion (inductive or capacitive), and j is the so-called imaginary operator (i.e., square root of minus one). If the antenna is resonant, then $X = 0$, and the impedance is simply R.

The first chore in designing the transformer is to *normalize* the impedances:

$$N = \frac{Z_{L1}}{Z_o} \qquad \textbf{[24.26]}$$

$$R = \frac{R_L}{Z_o} \qquad \textbf{[24.27]}$$

$$X = \frac{X_L}{Z_o} \qquad \textbf{[24.28]}$$

The lengths are determined in electrical degrees, and from that determination we can find length in feet or meters. If we adopt ARRL notation and define $A = \tan L_1$, and $B = \tan L_2$, then the following equations can be written:

If: $Z_L = R \pm jX_L$



24-12 Series matching section.

$$\tan L_2 = B = \frac{(r-1)^2 + X^2}{r\{N - (1/N)^2\} - (r-1)^2 - X^2} \qquad \textbf{[24.29]}$$

$$\tan L_1 = A = \frac{\{N - (r/R)\} \times B + X}{r + (XNB) - 1} \qquad \textbf{[24.30]}$$

where:

$$N = \frac{Z_1}{Z_o}$$

$$r = \frac{R_L}{Z_o}$$

$$Z = \frac{X_L}{Z_o}$$

Constraints:

$$Z_1 > Z_o \sqrt{\text{VSWR}} \qquad \textbf{[24.31]}$$

$$Z_1 < Z_o \sqrt{\text{VSWR}} \qquad \textbf{[24.32]}$$

If $L_1 < 0$, then add 180°
If $B < 0$, then Z_1 is too close to Z_o
Z_1 not equal to Z_o
$Z_o \sqrt{\text{VSWR}} < Z_1 < Z_o \sqrt{\text{VSWR}}$

Physical length in feet:

$$L_1 = \frac{L_1 \lambda}{360} \qquad \textbf{[24.33]}$$

$$L_2 = \frac{L_2 \lambda}{360} \qquad \textbf{[24.34]}$$

where

$$\lambda = \frac{984 \times \text{velocity factor}}{\text{frequency in megahertz}} \qquad \textbf{[24.35]}$$

The physical length is determined from arctan A and arctan B, divided by 360 and multiplied by the wavelength along the line and the velocity factor.

Although the sign of B can be selected as either – or +, the use of + is preferred because a shorter section is obtained. In the event that the sign of A turns out negative, add 180° to the result.

There are constraints on the design of this transformer. For one thing, the impedance of the two sections L_1 and L_2 cannot be too close together. In general, the following relationships must be observed:

Either

$$Z_{L1} > Z_o \times \text{SWR} \tag{24.36}$$

or

$$\frac{Z_{L1} < Z_o}{\text{SWR}} \tag{24.37}$$

Ferrite core inductors

The word *ferrite* refers to any of several examples of a class of materials that behave similarly to powdered iron compounds, and are used in radio equipment in the form of inductors and transformers. Although the original materials were of powdered iron, and indeed the name *ferr*ite still implies iron, many modern materials are composed of other compounds. According to the Amidon Associates literature, ferrites with a permeability u of 800 to 5000 are generally of the manganese-zinc type of material, and cores with permeabilities of 20 to 800 are of nickel-zinc. The latter are useful in the 0.5- to 100-MHz range.

Toroid cores

A *toroid* is a doughnut-shaped object, so one can reasonably expect a toroidal core to be an inductor (or transformer) form, made of a ferrite material, in the general shape of a doughnut. The type of core must be known for application purposes, and is given by the type number. The number will be of the form: FT – *xx* – *nn*, where FT means ferrite toroid and describes the shape, *xx* indicates the size, and *nn* indicates the material type. The F in FT is sometimes deleted in parts lists, and the core defined as a "T-*xx*-*nn*."

A chart is provided by Amidon that gives the dimensions, and a description of the properties of the different types of material, along with a lot of other physical data. Some of these data are also available in the annual ARRL publication *The ARRL Handbook for the Radio Amateur* (the same material has appeared in earlier editions also).

Tables are derived in part from both Amidon and ARRL sources. From these tables, you can see the sizes and properties of various popular toroids. These tables, incidentally, are not exhaustive of either the variety of toroids available, or all of the properties of the toroids mentioned. Using the nomenclature mentioned, a T-50-2 core refers to a core that is useful from 1 to 30 MHz, has a permeability of 10, is painted red, and has the following dimensions: OD = 0.500 in (1.27 cm), ID = 0.281 in (0.714 cm) and a height (i.e., thickness) of 0.188 in (0.448 cm).

Toroidal transformers

A magazine reader once asked a question of this author concerning the winding protocol for toroidal transformers as seen in textbooks and magazine articles. My correspondent included a partial circuit (Fig. 24-13A) as typical of the dilemma. The question was "How do you wind it?" and a couple of alternative methods were proposed. At first I thought it was a silly question because the answer was "obvious,"



24-13 Broadband RF transformer.

and then I realized that perhaps I was wrong, and to many people the answer was not at all that obvious.

The answer to the question is that all windings are wound together in a "multifilar" manner. Because there are three windings, in this case we are talking about "trifilar" windings. Figure 24-13B shows the trifilar winding method. For the sake of clarity, I have patterned all three wires differently so that you can follow them. This practice is also a good idea for practical situations. Since most small construction projects use no.26, no.28 or no.30 enameled wire to wind coils, I keep three colors of each size on hand, and wind each winding with a different color [Note: for transmitting antenna transformers use no.16, no.14, no.12, or no.10 wire]. Otherwise, label the ends with adhesive labels.

The dots in the schematic, and on the pictorial, are provided to identify one end of the coil windings. Thus, the dot and no-dot ends are different from each other, and it usually makes a difference to circuit operation which way the ends are connected into the circuit (the issue is signal phasing).

Figure 24-14 shows two accepted methods for winding a multifilar coil on a toroidal core. Figure 24-14A is the same method as in Fig. 24-13B, but on an actual toroid instead of a pictorial representation. The wires are laid down parallel to each other as shown previously. The method in Fig. 24-14B uses twisted wires. The three wires are “chucked up” in a drill and twisted together before being wound on the core. With one end of the three wires secured in the drill chuck, anchor the other end of the three wires in something that will hold it taut. Some people use a bench vise for this purpose. Turn on the drill at slow speed and allow the wires to twist together until the desired pitch is achieved.

Be very careful when performing this operation. If you don’t have a variable speed electric drill (so that it can be run at very low speed), then use an old-fashioned manual hand drill. If you use an electric drill, then wear eye protection. If the wire breaks, or gets loose from its mooring at the end opposite the drill, it will whip around wildly until the drill stops. That whipping wire will cause painful welts on the skin, and can easily damage eyes permanently.

Of the two methods for winding toroids, the method of Figs. 24-13B and 24-14A is preferred. When winding toroids, at least those of relatively few windings, pass the wire through the “doughnut hole” until the toroid is about in the middle of the length of wire. Then, loop the wire over the outside surface of the toroid, and pass it through the hole again. Repeat this process until the correct number of turns is wound onto the core. Be sure to press the wire against the toroid form, and keep it taut as you wind the coils.

Enameled wire is usually used for toroid transformers and inductors and that type of wire can lead to a problem. The enamel can chip and cause the copper conductor to contact the core. On larger cores, such as those for antenna-matching tranformers (and baluns used at kilowatt power levels), the practical solution is to wrap the bare toroid core in a layer of fiberglass packing tape. Wrap the tape exactly as if it was wire, but overlap the turns slightly to ensure covering the entire circumference of the core.

On some projects, especially those in which the coils and transformers use very fine wire (e.g., no.30), you may experience a tendency for the wire windings to unravel after the winding is completed. This problem is also easily curable. At the ends of the windings, place a tiny dab of rubber cement or RTV silicone sealer.



24-14 Winding a toroidal transformer
A) parallel wound,
B) twist wound.

Mounting toroid cores Now that you have a properly wound toroidal inductor or transformer, it is time to actually mount it in a circuit being constructed. There are three easy ways to do this job. First, you might be able to ignore it. If the wire is heavy enough, then just use the wire connections to the circuit board or terminal strip to support the component. But if this is not satisfactory, and in mobile equipment (or wherever else vibration is a factor) it won't be, then try laying the toroid flat on the board and cementing it in place with silicone seal or rubber cement. The third method is to drill a hole in the wiring board and use a screw and nut to secure the toroid. Do not use metallic hardware for mounting the toroid! Metallic fasteners will alter the inductance of the component and possibly render it unusable. Use nylon hardware for mounting the inductor, or transformer.

How many turns? Three factors must be taken into consideration when making toroid transformers or inductors: *toroid size, core material,* and *number of turns of wire.* The toroid size is selected as a function of power-handling capability, or for convenience of handling. The core material is selected according to the frequency range of the circuit. The only thing left to vary is the number of turns. The size and core material yields a figure called the A_L factor. The required value of inductance and the A_L factor are used in the following equation:

$$N = 100\sqrt{\frac{L_{\mu H}}{A_L}} \qquad \textbf{[24.38]}$$

where:

N is the number of turns
$L_{\mu H}$ is the inductance in microhenrys
A_L is the core factor, in microhenrys per 100 turns

Example Calculate the number of turns required to make a 5-μH inductor on a T-50-6 core. The A_L factor is 40.

Solution:

$$N = 100\sqrt{\frac{L_{\mu H}}{A_L}}$$

$$= 100\sqrt{\frac{5_{\mu H}}{40}}$$

$$= 100\ \sqrt{0.125}$$

$$= (100)\ (0.35) = 35$$

Don't take the equation value too seriously, however, because it is my experience that a wide tolerance exists on amateur-grade ferrite cores. Although it isn't too much of a problem when building transformers, it can be critical when making inductors for a tuned circuit. When you find that the tuned circuit takes considerably more (or less) capacitance than called for in the standard equation, and all of the stray capacitance is properly taken into consideration, then it may be that the actual A_L value of your particular core is different from the table value.

Ferrite rods

Another form of ferrite core available on the market is the rod, shown in Fig. 24-15A. This type of core is used to make RF chokes, such as the RFC used in the vacuum tube filament lines of a linear amplifier power tube (Fig. 24-15B). They are also used for baluns by some people. The two windings are wound in a bifilar manner over the ferrite rod. Of course, the wires used must be heavy enough to carry the filament current of the tube. As was true in the toroidal transformer, I use two different wire colors in order to make it easy to identify windings.

Ferrite rods are also used in receiving antennas. Although the amateur use is not extensive, there are places where a ferrite rod antenna (or "loopstick") is used. For example, in radio direction finding antennas, it is common to see the ferrite loop. Also, some amateurs report that they use a loopstick receiving antenna when operating on crowded bands, such as 40 and 75 m. The small loopstick has an extremely directional characteristic, so it is capable of nulling out interfering signals. Of course, you would not want to use the loopstick for transmitting, so some means must be found for transferring the antennas over between the transmit and receive functions.

Mounting ferrite rods Ferrite rods can be mounted in several ways, two of which are analagous to the methods used on toroids. We can, for example, mount the rod using either its own wires for support or by using a dab of cement or silicone sealer to fasten it to the board. Although we cannot use simple nylon screws the way we can on toroids, we can use insulating cable clamps to secure the ends of the rod to the board.

Toroid broadbanded impedance matching transformers

The toroidal transformer forms a broadbanded means for matching antenna impedance to the transmission line, or matching the transmission line to the transmitter. The other matching methods (shown thus far) are frequency-sensitive, and must be readjusted whenever the operating frequency is changed even a small amount. Although this problem is of no great concern to fixed-frequency radio stations, it is of critical importance to stations that operate on a variety of frequencies.

Figure 24-16A shows a trifilar transformer that provides a 1:1 impedance ratio, but it will transform an unbalanced transmission line (e.g., coaxial cable) to a



24-15 Ferrite rod inductor (A) construction, (B) use in amplifier.

balanced signal required to feed a dipole antenna. Although it *provides no impedance transformation*, it does tend to balance the feed currents in the two halves of the antenna. This fact makes it possible to obtain a more accurate figure-8 dipole radiation pattern in the horizontal plane. Many station owners make it standard practice to use a balun at the antenna feedpoint.

The balun shown in Fig. 24-16B is designed to provide the unbalanced to balanced transformation, while also providing a 4:1 impedance ratio. Thus, a 300 Ω folded dipole feedpoint impedance will be transformed to 75 Ω unbalanced. This type of balun is often included inside antenna tuners, including all three models shown in Figs. 24-8A and 24-8B. A variable (or at least settable) broadbanded transformer is shown in Fig. 24-16C. In this case the output winding is tapped, and the operator selects the correct tap needed to provide the desired impedance ratio. The usual turns ratio criterion applies.

Another multiple-impedance transformer is shown in Fig. 24-16D. In this case, the operator can select impedance transformation ratios of 1.5:1, 4:1, 9:1 or 16:1. A commercial version of this type of transformer is shown in Fig. 24-16E. It is manufactured by Palomar Engineers, and is intended for vertical antenna feeding in the HF bands. It will, however, work well on antennas other than simple verticals. A top view of the vertical antenna feeding transformer is in Fig. 24-16F.



24-16A BALUN 1:1.



24-16B Balun 1:4.


16:1
9:1
4:1
1.5:1
R_1
R_2

24-16C Tapped BALUN.



24-16D Multi-impedance BALUN.

24-16E Vertical antenna feeding transformer.



24-16F Top view of Fig. 24-16E.

This page intentionally left blank

25
CHAPTER

Mobile, emergency, portable, and marine antennas

MOBILE OPERATION OF RADIO COMMUNICATIONS EQUIPMENT DATES BACK TO ONLY A little later than "base station" operation. From its earliest times, radio buffs have attempted to place radio communications equipment in vehicles. Unfortunately, two-way radio was not terribly practical until the 1930s, when the earliest applications were amateur radio and police radio (which used frequencies in the 1.7- to 2.0-MHz region). Over the years, the land mobile and amateur radio mobile operation has moved progressively higher in frequency because of certain practical considerations. The higher the frequency, for example, the shorter the wavelength; and, therefore, the shorter a full-size antenna. On the 11-m Citizens Band, for example, a quarter-wavelength whip antenna is 102 in long, and for the 10-m amateur band only 96 in long. At VHF frequencies, antennas become even shorter. As a result, much mobile activity takes place in the VHF and UHF region.

The amateur 144-, 220-, and 440-MHz bands are popular because of several factors, not the least of which is the ease of making ¼- and ⅝-wavelength antennas. Because low-cost commercial antennas are available for these frequencies, however, we will not examine such antennas in this chapter. Rather, we will concentrate on high-frequency antennas.

Mobile HF antennas

High-frequency (HF) mobile operation requires substantially different antennas than VHF or UHF. Quarter-wavelength antennas are feasible only on the 11- and 10-m bands, with some argument in favor of 13 m as well. But by the time the frequency drops to the 21-MHz (15-m) band, the antenna size must be approximately 11 ft long, and that is too long for practical mobile operation. Because of practical considerations,

Copyright 2001 - the McGraw-Hill Companies

you must limit antenna size to 8 or 9 ft; in the amateur radio bands the 8-ft antenna is most popular because it is resonant on 10 m. At all lower frequencies, the 8-ft whip becomes capacitive, and therefore requires an equal inductive reactance to cancel the capacitive reactance of the antenna.

Figure 25-1 shows three basic configurations of coil-loaded HF antennas for frequencies lower than the natural resonant frequency of the antenna. In each case, the antennas are series fed with coaxial cable from the base; point *A* is connected to the coaxial cable center conductor, and point *B* is connected to the shield, and the car body (which serves as ground). The system shown in Fig. 25-1A is base-loaded. Although convenient, there is some evidence that the current distribution is less than optimum. The version shown in Fig. 25-1B is center-loaded, and results in an improved current distribution. This configuration is probably the most common among commercially available HF mobile antennas, although the coil is often located slightly above the center point. Finally, we see the top-loaded coil system in Fig. 25-1B. In all three cases, the point is to use the inductance of the coil to cancel the capacitive reactance of the antenna.

A modified version of the coil-loaded HF mobile antenna is shown in Fig. 25-2A. In this configuration the loading inductance is divided between two individual coils, L_1 and L_2. Coil L_1 is adjustable with respect to the antenna, while L_2 is fixed; coil L_2 is tapped, however, in order to match the impedance of the antenna to the charac-



25-1 Loaded mobile antennas.



25-2A Practical mobile antenna for HF bands below 10 m; L_1 resonates, L_2 matches impedance.

teristic impedance of the coaxial-cable transmission line. When tuning this antenna, two instruments are needed: a field strength meter and a VSWR meter. The field strength meter gives a relative indication of the amount of power radiated from the antenna, while the VSWR meter helps determine the state of the impedance match. A pair of relative field strength meter projects are discussed later in this chapter.

Variations on the theme are shown in Figs. 25-2B and 25-2C. A helical whip is shown in Fig. 25-2B. In this configuration, the inductor is distributed along the length of a fiberglass antenna rod. The conductor is a wire that is helically wound on the fiberglass shaft. An adjustable tip sets the antenna to resonance. The length of this tip can be set by a local field strength meter. Fixed versions of this type of antenna are very popular on the Citizens Band where they may be as short as 30 in, or as long as 48 in. There are also some amateur radio commercial antennas based on this concept.

The other variant is shown in Fig. 25-2C. In this case, the lower end of the radiator consists of a metal tube topped with a loading coil. An adjustable shaft at the top end is used to tune the antenna to resonance. This form of antenna is popular among commercial makers of HF mobile antennas, such as the Hustler. The fixed shaft tends to be universal for all bands, while the coil and adjustable shaft form a separate “resonator” for each band. Multiband operation of this form of antenna can be accomplished by using a bracket such as shown in Fig. 25-2D. Although early versions of this scheme were homebrewed, several manufacturers currently make factory-built versions. The idea in Fig. 25-2D is to mount two or more resonators to a common fixed shaft.


Adjustable tip
Helically wound wire embedded in fiberglass
A
B

25-2B Helically wound mobile antenna.


Adjustable shaft
Loading coil
Fixed shaft
A
B

25-2C Top-loaded mobile antenna common in amateur radio.


Resonator #1
Resonator #2
Resonator #3
Bracket
Fixed shaft

25-2D Multiband top-loaded antenna.

A common problem with all coil-loaded mobile antennas is that they tend to be very high *Q* antennas. In other words, they are very sharply tuned. The VSWR tends to rise rapidly as the operating frequency departs from the frequency to which the antenna is tuned; as little as 25-kHz change of operating frequency will detune the antenna significantly. Although an antenna tuner at the output of the transmitter will reduce the VSWR to a point that allows the transmitter to operate, that type of tuner is merely a line flattener that does not fully address the problem. The actual problem is that the antenna is not resonant. The efficiency of the antenna drops off rapidly as the frequency changes. The only cure for this problem is to readjust the resonator's adjustable shaft as the band segment is changed (not merely the band, but the *band segment*). Unfortunately, this solution requires tools, and the operator must get out of the vehicle in order to do a good job of retuning. Another solution is to use a motor-driven variable inductor for the loading coil. Several manufacturers offer both base-loaded and center-loaded coils that are either motor-driven or relay-selectable to permit frequency changing from the operator's seat.

Tuning HF mobile antennas

Although the procedures for tuning certain specific antennas might be different from those given below, the basic principles are the same, and can easily be adapted to any given situation. There are two situations to consider. First is the antenna in which there is either a single adjustable (or tap-selectable) loading coil, or a fixed loading coil and an adjustable shaft resonator. Second is the case (Fig. 25-2A) where there is an adjustable or tapped coil in series with a tapped impedance-matching coil at the base.

Case no. 1. In this case, we assume that the antenna has a single adjustment, either a shaft resonator or adjustable coil. In this case we need to use a field strength meter (FSM) to measure the relative field strength of the radiated signal. The antenna resonator is adjusted until the radiated field strength is maximum. Of course, this procedure must be done in steps, keying the transmitter after each adjustment to see what happened. Alternatively, a VSWR meter can be used to set the resonator to a minimum VSWR.

Case no. 2. Here, we have a coil at the base that is fixed with respect to the antenna radiator element, but is tapped with respect to the coaxial cable from the transmitter. A second coil is also used in the antenna (see Fig. 25-2A), which can be either in the center or at the top. This coil is adjustable for setting resonance. Alternatively, this coil may be fixed, and an adjustable resonator shaft may be used to set operating frequency. In this type of antenna the upper coil, or resonator shaft, is adjusted to resonance by using a field strength meter. The lower coil is adjusted for minimum VSWR. Both adjustments are needed to complete the job.

Field strength meters

A *field strength meter* (FSM) is an instrument that measures the radiated field from an antenna. Commercial engineering-grade instruments are calibrated in terms of either watts/square centimeter or volts/meter, and are used for jobs such as broadcast station "proof-of-performance" tests and other professional jobs. For adjusting antennas, however, a considerably different instrument is sufficient. This section describes two simple, passive (which means no dc power is required) field strength meters usable for adjusting HF radio antennas, including both CB and amateur radio antennas.

Two forms are shown in Fig. 25-3; both are basically variations on the old-fashioned "crystal set" theme. Figure 25-3A shows the simplest form of untuned FSM. In this circuit a small whip antenna (used for signal pickup) is connected to one end of a grounded RF choke (RFC). The RF voltage developed across the RFC is applied to a germanium diode detector; either IN34 or IN60 can be used. Silicon diodes are normally preferred in signal applications, but in this case we need the lower contact potential of germanium diodes in order to improve sensitivity (V_g is 0.2 to 0.3 V for Ge and 0.6 to 0.7. V for Si). A potentiometer is used both as the load for the diode and as a sensitivity control to set the meter reading to a convenient level.

The untuned version of the FSM is usable even at low powers, but suffers from a lack of sensitivity. Only a certain amount of signal can be developed across the RFC, so this limits the sensitivity. Also, the RFC does not make a good impedance match to the detector diode D_1. An improvement is possible by adding a tuned circuit and an impedance-matching scheme, as shown in Fig. 25-3B. In this case a variable capacitor C_3 is used as a tune control. The tuning capacitor is parallel resonant with inductor L_1. A tapped capacitive voltage divider (C_1/C_2) is used to provide impedance matching to the diode. Figure 25-3C gives values of capacitance and inductance for various bands.

Operation of the tunable FSM is simple and straightforward. Set the sensitivity control to approximately half-scale, and then key the transmitter; adjust the tuning control (C_3) for maximum deflection of the meter pointer (readjustment of the sensitivity control may be needed). After these adjustments are made, the tunable FSM works just like any other FSM.



25-3A Simple field strength meter.



25-3B Tuned field strength meters.

25-3C Values chart for field strength meters.

Band (meters)	L_1 (µH)	C_1 (pF)	C_2 (pF)
75/80	27	25	100
40	10	15	68
30	4.4	15	68
20	2.25	10	68
17	1.7	10	56
15	1.3	10	47
13	0.8	10	39
10	0.5	10	39

Antennas for emergency operations

Some time ago, I met an interesting character at a convention. As a medical doctor, he was a medical missionary working at a relief station in Sudan. Because of his unique business address, he was able to discuss mobile and portable antennas for communications from the boondocks. His *bona fides* for this knowledge includes the fact that he is licensed to operate on both the amateur radio bands, and as a landmobile (or point-to-point) station in the 6.2-MHz band. The desert where he travels is among the worst in the world. The path they euphemistically call a “road” is occasionally littered with camel corpses because of the harsh conditions. The doctor’s organization requires him to check in twice daily on either 6.2 MHz or

3.885 MHz (which some missionary hams in Africa use as an unofficial calling frequency). If he misses two check-ins in a row, then the search and rescue planes are sent up. As a result of his unique "house calls," he does a lot of mobile and portable operating in the lower-HF region of the spectrum. His problem is this: How do you reliably get through the QRM and tropical QRN with only 200 W PEP and a standard loaded mobile antenna?

Another fellow I once met works in Alaska for a government agency. He faces many of the same problems as the doctor in Sudan, but at close to 100° colder. He frequently takes his 100-W mobile rig into the boondocks with him in a four-wheel drive vehicle. Again, with only 100 W into a poor-efficiency loaded mobile antenna, how does one reliably cut through the interference to be heard back at the homestead?

An earthquake, or hurricane, strikes your community. Antenna towers collapse, tribanders become tangled masses of aluminum tubing, dipoles are snarled globs of no.14 Copperweld, and the rig and linear amplifier are smashed under the rubble of one corner of your house. All that remains is the 100-W HF rig in your car. How do you reliably establish communications in "kilowatt alley" with a 100-W mobile driving a 75-W loaded whip? Of course, you always got through one way or another before, but now communications are not for fun—they are deadly serious. Somehow, the distant problems of a Sudanese missionary doctor and a KL7 government forester don't seem too very far away.

For these operators, communications often means life or death for someone, perhaps themselves. Given the inefficiency of the loaded whips typically used as mobile antennas in the low-HF region, the generally low power levels used in available mobile rigs, and the crowded band conditions on the 80-, 75-, and 40-m bands, it becomes a matter of more than academic interest how you might increase the signal strength from your portable (or mobile) emergency station. Anything we can do, easily and cheaply, to improve the signal is like having money in the bank. Fortunately, there are several tricks of the trade that will help us out in a pinch.

Figure 25-4 shows a typical mobile antenna for a low-HF band. Because quarter-wavelength antennas on these frequencies are 30 to 70 ft high, full-size vertical whip antennas are not practical. In fact, at frequencies below 10 m, full-size whips are not generally used. Short antennas exhibit capacitive reactance, so we add a loading coil (inductor L in Fig. 25-4) to the radiator to make up the difference (its inductive reactance cancels the capacitive reactance of the antenna). The inductor in such a loaded antenna can be placed almost anywhere along the radiator, although base-, center-, and top-loaded designs predominate. The actual inductance needed varies somewhat with coil placement, as does antenna performance. The "resonators" used on commercial low-HF mobile antennas are loading coils encapsulated in a weathertight housing.

The mobile configuration is inefficient by its nature, and little can be done to improve matters. Of course, an antenna-matching device or tuner will help in optimizing the power transfer to the antenna, and should always be used in any event (especially with solid-state final amplifiers, which don't tolerate VSWR as easily as do tube finals). In the portable configuration, however, we can both improve the performance of "mobile" antennas and look into antenna options not open to the mobile



25-4 Basic mobile antenna system often proves unsatisfactory in marginal cases.

operator. We can make a basic assumption for these improvements: The operator needing emergency or urgent communications is not driving down the interstate somewhere, but is stopped in the back country and needs to call out.

In cases of emergencies on most highways, we are in range of some repeater, so we would use a VHF band (probably 2 m) to contact police or other emergency services through a repeater autopatch. In fact, with the wide availability of repeaters around the country it behooves any amateur, backpacking or four-wheeling into remote areas, to be familiar with repeater locations and frequencies. From hilltops, especially, it is often possible to hit repeaters from a surprisingly long distance. I have seen hand-held 2-m rigs trigger mountain top repeaters from the mountains of southwestern Virginia, and presume that other areas of the country are as well off repeaterwise. This chapter deals with HF rigs, especially those operating in the lower end of the HF spectrum, in situations where a temporary antenna must be erected.

Most amateurs, who have low-HF mobile rigs, will testify that getting out is a pain in the mike button. Antenna efficiencies are simply too poor. One factor in this dismal equation is that the vehicle body makes a very poor antenna ground system. One could, I suppose, carry a supply of 6- or 8-ft copper-clad steel ground rods, and a 9-lb sledge hammer to drive them into the earth wherever a portable station is needed. Somehow, that solution doesn't seem too appealing at this point! Besides, have you ever tried to remove an effective 8-ft ground rod from the ground? Forget it, it's too much pain for too little gain. A better solution is to provide a counterpoise groundplane, as shown in Fig. 25-5. In Fig. 25-5A we see the electrical situation and connection, while in Fig. 25-5B we see the mechanical scheme for a specific situation: A groundplane consists of two or more (even *one* helps) quarter-wavelength radials connected to the antenna ground point (i.e., where the coaxial cable shield connects to the vehicle body). The radials are made of no. 14 wire, so are relatively easy to stow.

Figure 25-5B shows a workable system that will improve the performance of a mobile rig in stationary situations. The mobile antenna uses the normal base mount attached to the rear quarter panel of the car adjacent to the trunk lid. An all-metal grounding-type binding post is installed through an extra hole drilled in the base


Less than $\frac{\lambda}{4}$
L
Coax to transmitter
Antenna tuner
Radials: $\frac{\lambda}{4} = \frac{246}{F_{MHz}}$
Two or more $\frac{\lambda}{4}$ Radials

25-5A Two or more radials improve efficiency of mobile antenna used in a portable communications setup.


$\frac{\lambda}{4} = \frac{246}{F_{MHz}}$
Mobile antenna
$\frac{\lambda}{4}$ Radials
Insulators
Rope
Ground

25-5B Multiple radials are even better.


Whip
Grounding type binding post
#14 Radial
Base mounting
Car body
Ground point
Coax to transmitter or tuner

25-5C Connection of radials to mobile antenna.

insulator (see Fig. 25-5C). Radials for portable operation are attached at this point. Although the binding post is small, it easily accommodates two no. 14 radials. The owner used the vehicle for camping, and the radials were used to improve antenna efficiency. I don't believe the dramatic accounts enthusiastically reported by the owner of the car, but my own Field Day experience (and the testimony of the Sudanese missionary doctor) lead me to expect considerable improvement over the unaided loaded whip.

A potential solution to the inefficiency problem is to replace the mobile antenna with a more efficient, but stowable, antenna that can be brought out and erected when needed. One candidate is a surplus military HF whip antenna. Intended for jeeps and communications trucks, these antenna/tuner combinations are collapsible and are as efficient as any on the market. Although my Alaskan friend could use such a surplus find, my Sudanese friend could not. He told me that Americans in the boonies, even (perhaps especially) missionaries, are always suspected by pinheaded local authorities of being agents of the dreaded “Cuban Invasion Authority.” Showing up “out there” with obviously military radio equipment serves only to seal that belief!

The common dipole is often looked down upon by the owners of massive array antennas, but those old-fashioned antennas are capable of turning in some impressive results. The dipole is made by connecting two quarter-wavelength pieces of wire to a coaxial-cable transmission line. One length is connected to the center conductor, and the other is connected to the shield of the coax. In a pinch, zip (i.e., lamp) cord and twisted pairs of hookup wire will do for a transmission line. Figure 25-6 shows the common dipole and the normal equation for determining *approximate* length. The actual length is found by trimming length until the VSWR drops to its lowest point, a nicety that might not seem altogether important in an emergency. The ends of the dipole must be supported on trees, masts, or some other elevated structure. Unfortunately, mounting points aren't easily found. My Sudanese friend doesn't see many trees!

Figure 25-7 shows another alternative antenna that works well for portable operation. Based on the dipole, this inverted-vee dipole does not require two end supports but rather a single center support. The length of each leg is 6 percent longer than for a nominal dipole. Because the application is both emergency-related and temporary in nature, we can get away with construction methods that would be unthinkable in more permanent installations.



25-6 Basic dipole.



25-7 Portable inverted-vee antenna.

Three problems present themselves. First, the antenna must be portable for backpackers, or stowable in the case of those people who motor into the back country. Size and weight are major constraints in both cases, even though the vehicular case is a lot easier to work with than the backpacker. Second, what materials and means of construction are needed for the mast? Third, how is the mast supported? Because the answer to the third question depends in part on the answer selected for the second, we will deal with it first. The first question is avoided at this point because I have selected the vehicular case.

One alternative is to use a telescoping TV antenna mast to support your antenna. We can either mount a mobile whip and its associated radials at the top, or install an inverted-vee per Fig. 25-7. These masts collapse to 6 or 8 ft in length, but can be slipped up to heights of 18, 25, 30, 40, or 50 ft, depending upon the type selected. Keep in mind, when shopping for these masts, that the larger models are considerably heavier than shorter models, and they require two or more people to install them. Erecting a 40- or 50-ft telescoping mast is not a single-person job, even though you might know someone who has done it. I've done it, and won't do it again! Even the 30-ft models are a bit hairy to install alone.

Another mast that can be used for the inverted vee is made from PVC plastic plumbing pipe. If it can be carried on or in the vehicle, then lengths up to 10 ft are available. Longer lengths are made at the site of erection by joining together 10-ft or shorter sections with couplings (also available at plumbing supply outlets). Be careful of using PVC pipe that is too small, however. PVC pipe is relatively thin walled, and it is therefore flexible. Sizes below 1.5-in diameter will not easily stand alone without guying. While a single 10-ft section might be self-supporting, two or more sections together will not support themselves and the weight of the antenna. Guying can be accomplished with ropes, or on a temporary basis, heavy twine.

Still another alternative is to carry steel TV antenna masts. Available in 5- and 10-ft lengths, these masts are flared on one end and crimped on the other, so that they can be joined together to form longer lengths. In addition, the same sources that sell these masts also sell the guy wire rings that help support the mast when installed. There is also a variety of rooftop mounting devices that aid also in ground mounting the antenna.

I used the TV mast solution on Field Day expeditions for many years. The inverted-vee antenna is, of course, a natural for this solution. Once, however, we used a Hustler mobile antenna mounted at the top of a 20-ft mast, with four radials, and it worked surprisingly well with the 30-W limit for extra points credit then available for Field Day contestants.

There are, then, several alternatives for masts that slip up, snap together, or are otherwise easily unstowed and installed. Let's now turn our attention to base mounting schemes that can be used to support the mast. Of course, in a life or death pinch, you could always just pile rocks around the base, or hold the darn thing up as you transmit. But a little forethought could eliminate those problems easily.

One of the first solutions I'll deal with was seen on the Outer Banks of North Carolina, and was provided to me by a CB operator. Surf fishers on the Outer Banks use four-wheel drive vehicles to get out on the beach (to the surf, where the big sea bass lurk). Welded to either the front or rear bumper attachments are steel tubes (see Fig. 25-7) used for mounting the very, very long surf casting rods they use to catch fish. The CB operator had a 20-ft mast consisting of two 10-ft TV mast sections mounted in one of the rod holders. At the upper end of the mast was his 11-m groundplane antenna. The same method of mounting would also support similar amateur antennas, inverted-vee dipoles, or VHF/UHF antennas.

Given that the antenna installation will be temporary, lasting only a few hours or a couple of days in the worst case, we need not worry about long-term integrity, or the practicality of the installation. Mounting the mast to the back of a four-wheeler or pickup truck with a pair of U bolts is not terribly practical if you must move the vehicle, but works nicely if you plan to camp (or are stranded) for a few days.

For lightweight masts, up to about 25 ft, the base support could be an X-shaped base made of 2 × 4-in lumber (Fig. 25-8A), or even a Christmas tree holder. Alternatively, a TV antenna rooftop tripod mount (Fig. 25-8B) is easily adopted for use on the ground. None of these three alternatives can be depended upon for self-supporting installations, and must be guyed even if used for only a short period. Again, because of the temporary nature of the installation, aluminum or wooden tent pegs can be used to anchor the guy wires. Although they are insufficient for long-term installations, they work fine for the short run.



25-8A Wooden antenna stand.



25-8B TV-antenna tripod also works in portable situation for HF antenna masts.

Another problem

Field Day is a reasonably good training ground for people who anticipate operating radio equipment under primitive conditions. If you pay attention to the sometimes humorous foul-ups seen while getting on the air from atop High Peak Mountain in Goose Bump National Park, then you might avoid some of the same mistakes when foul-ups mean more than a quick drive to the nearest town. You will learn, for example, which simple tools are a must for constructing and repairing simple antennas (including the 12-Vdc soldering iron that runs off the vehicle battery). You will also learn a bit about electricity needed to run the rig.

Two alternatives present themselves. First, you could use 12 Vdc from the vehicle electrical system, which makes sense with the current crop of 12 Vdc HF rigs on the market. Or, you could operate from 120 Vac generated by a light plant generator.

When boondocking in a four-wheeler (or other vehicle), it is wise to use a dual battery system such as shown in Fig. 25-9. Two separate 12-Vdc auto batteries (preferably high ampere-hour capacity) are connected essentially in parallel with the alternative charging system. Diodes D_1 and D_2 are rated at 100 A, 50 V peak inverse voltage (PVI), and are used to isolate the two batteries from each other. Diode assemblies such as this can be built, or purchased from van conversion and recreational



25-9 Diode pack allows charging two batteries from system charger.

vehicle shops. Van and RV owners' use is the same as yours: It's a darn shame to run down the battery needed to start the vehicle just by operating your rig. You not only cannot start the vehicle in such a case, but cannot muster enough power to call for the wilderness equivalent of "Triple A."

One experienced boondocker I met in southern Arizona totes either a 450-W Kawasaki or 500-W Honda mini light plant generator in the back of his Bronco. These models are surprisingly lightweight and quiet operating. One of the generators has a 12-Vdc, 8-A outlet that can be used to charge a dead battery. The other has only the 110-Vac outlet, but can be used for battery charging if a small charger is provided. Simple 10-A battery chargers can usually be bought at auto parts or accessories stores, for about $60.

Operating radio communications equipment successfully under primitive conditions depends upon two major factors: available electrical power and a proper, efficient, antenna system. Although dealing in detail with the means of obtaining power in remote locations is beyond the scope of this book, we have provided some ideas from which you can start planning your own "survival" radio system.

Marine radio antennas

Radio communications considerably lessened the dangers inherent in sea travel. So much so, in fact, that the maritime industry took to the new "wireless telegraphy" earlier than any other segment of society. In the early days of radio, a number of exciting rescues occurred because of wireless. Even the infamous *S.S. Titanic* sinking might have cost less human life if the wireless operator aboard a nearby ship had been on duty. Today, shore stations and ships maintain 24-hour surveillance, and vessels can be equipped with autoalarm devices to wake up those who are not on duty. Even small pleasure boats are now equipped with radio communications, and these are monitored around the clock by the U.S. Coast Guard.

The small shipboard operator can have a selection of either HF single-sideband communications or VHF-FM communications. The general rule is that a station must have the VHF-FM, and can be licensed for the HF SSB mode only if VHF-FM is also aboard. The VHF-FM radio is used in coastal waters, inland waters, and harbors. These radios are equipped with a high/low power switch that permits the use of low power (1 W typically) in the harbor, but higher power when under way. The HF SSB radios are more powerful (100 W typically), and are used for offshore long-distance communications beyond the line-of-radio-sight capability of the VHF-FM band.

The problems of antennas on boats are the same as for shore installations, but are aggravated by certain factors. Space, for one thing, is less on a boat so most HF antennas must be compensation types. Also, grounds are harder to come by on a fiberglass or wooden boat, so external grounds must be provided.

A typical powerboat example is shown in Fig. 25-10. The radio is connected to a whip antenna through a transmission line (and a tuner on HF), while also being grounded to an externally provided groundplate. Over the years, radio grounds have taken a lot of different forms. For example, the ground might be copper or aluminum foil cemented to the boat hull. Alternatively, it might be a bronze plate or hollow bronze tube along the center line of the boat, or along the sides just below the water line. The ground will also be connected to the engine. Careful attention must be paid



25-10 Motorboat grounding system.

to the electrical system of the boat when creating external grounds to prevent electrolytic corrosion from inadvertent current flows.

On sailboats the whip antenna (especially VHF-FM) might be mast-mounted as shown in Fig. 25-11. The same grounding scheme applies with the addition of a metal keel or metal foil over a nonmetallic keel.

The whips used for boat radios tend to be longer than land mobile antennas for the same frequency. The VHF-FM whip (Fig. 25-12) can be several quarter-wavelengths and take advantage of gain characteristics thereby obtained. Whips for the HF bands tend to be 10 to 30 ft in length, and often look like trolling rods on power boats. You will also see Citizens Band radios on board boats, and the CB antennas are also whips. It is not a good idea to rely solely on CB for boat communications, because it is a lot less



25-11 Sailboat grounding.



25-12 VHF-FM boat antenna.
Courtesy of Antenna Specialist Company

likely to be useful in emergencies. Also, some boaters use amateur radio sets, often illegally, for emergency communications in lieu of a proper HF-SSB unit.

Longwire antennas also find use in marine service. Figure 25-13 shows two installations. The antenna in Fig. 25-13A shows a wire stretched between the stern and bow by way of the mast. The antenna is end-fed from an antenna tuner or “line flattener.” The longwire shown in Fig. 25-13B is similar in concept, but runs from the bottom to the top of the mast. Again, a tuner is needed to match the antenna to the radio transmission line. Notice that the antennas used in this manner are actually not “longwires” in the truly rigorous sense of the term, but rather “random length” antennas.

The format of the tuner can be any of several designs, shown in Fig. 25-14. The reversed L-section coupler shown in Fig. 25-14A is used when the antenna radiator element is less than a quarter-wavelength. Similarly, when the antenna is greater than a quarter-wavelength, the circuit of Fig. 25-14B is the tuner of choice. This circuit is a modified L-section coupler that uses two variable capacitors and the inductor.


Radio
Tuner

25-13A Sailboat HF antenna.


Mast
Wire
Tuner
Radio

25-13B Mast antenna.



25-14 Antenna tuners for broad HF antennas.

Finally, we see in Fig. 25-14C the coupler used on many radios for random-length antennas. Two variable inductors are used; L_1 is used to resonate the antenna, and L_2 is used to match the impedance looking back to the transmitter to the system impedance. In some designs, the inductors are not actually variable, but rather use switch-selected taps on the coils. The correct coil taps are selected when the operator selects a channel. This approach is less frequently encountered today, when frequency synthesizers give the owner a selection of channels to use. In those cases, either the antenna must be tuned every time the frequency is changed, or an automatic (or motor-driven) preselected tuner is used.

The line flattener (Fig. 25-15) is a standard transmatch antenna tuner that flattens coaxial-cable transmission line for VSWR. This type of tuner is especially useful for transmitters with solid-state finals that are not "happy" with high VSWR. Some of those designs incorporate shutdown circuits that reduce (and then cut off) power as the VSWR increases. The line flattener basically tunes out the VSWR at the transmitter. It does nothing to tune the antenna, but only makes the transmitter operable.



25-15 Line flattener tuner.

26
CHAPTER

Antennas for low-frequency operation

LOW-FREQUENCY OPERATION (E.G., 160- AND 75/80-METER BAND) POSES CERTAIN difficulties for the antenna. Of course, the first thing that springs to mind is the large size of those antennas. A half-wavelength dipole is between 117 and 133 ft long on 75/80 m, and on 160 m it is about twice that length. On my own suburban lot, I cannot erect a half-wave 75/80-m band antenna and stay within the property lines.

A similar situation is seen with vertical antennas. Although a 40-m vertical (33 ft high) is not an unreasonable mechanical job, the 66 ft 75/80-m vertical (never mind the 120-ft 160-m vertical) is a nightmare. In addition, the local authorities might not require any special inspections or permits (check!) on the 33-ft antenna, yet impose rigid and very exacting requirements on the higher structure. On suburban or urban lots, a typical 40-m antenna might well be able to fall over and still not cross the property line—or come in close proximity to power lines. A longer antenna, however, almost inevitably suffers one—or the other—problem when it falls.

Grounding

Still another problem involves grounding. The ground system of a higher-frequency vertical antenna can be installed using $\lambda/4$ radials buried a few inches below the surface. But that same idea becomes problematic when the radials are 66 or 125 ft long. Burying half a dozen 125-ft radials might remind your neighbors of the Galloping Gung-Ho Gopher—and not to their amusement!

There are, however, some solutions to the problem—without having you buy a farm in the flatter regions of the midwest. For example, the length problem can be solved by using one of the bent dipoles covered in Chap. 10. No, they are not

Copyright 2001 - the McGraw-Hill Companies

as effective as an antenna that is correctly installed. But they will serve to get you on the air. Some of them work surprisingly well.

The ground radial problem can be solved by bending the radial system around your property (Fig. 26-1). You will never have to cross your neighbor's line. And, as for the gopher track appearance, it is not necessary to work sloppily, and you can install radials so that nary an eye, practiced or otherwise, can see their location.

Shortened vertical antennas

The biggest problem for most low-frequency DXers, as you have seen, is the excessive size of antennas for those frequencies; it is "not for nothing" that those AM broadcast band (<1.6 MHz) towers are usually hundreds of feet tall. But there are ways to shorten an antenna—not for free, because the TANSTAAFL* principle still



26-1 Methods for laying out low-frequency radials in a cramped space.

---

*TANSTAAFL = There ain't no such thing as a free lunch!

applies—to a point where it becomes mechanically possible. Let me reiterate once again that these compensation antennas will not work as well as a properly installed full-sized antenna, but they will serve to get you on the air on frequencies where it is otherwise utterly impossible. Several different compensation configurations are popular, and these are shown in Fig. 26-2.



26-2 Inductance loading of vertical antennas: (A) center; (B) top; (C) base; (D) linear or length-loaded; (E) linear hairpin-loaded.

The basic foundation for these antennas is a very short vertical antenna. The "standard" vertical antenna is a quarter-wavelength ($\lambda/4$) (i.e., 90° electrical length), and it is unbalanced with respect to ground.

Recall that a vertical antenna that is too short for its operating frequency (i.e., less than $\lambda/4$) will exhibit capacitive reactance. In order to resonate that antenna, it is necessary to cancel the capacitive reactance with an equivalent inductive reactance, such as $|X_L| = |X_C|$. By placing an inductance in series with the antenna radiator element, therefore, we can effectively "lengthen" it electrically. Of course, what is really happening is that the effects of the lower operating frequency are being accommodated (i.e., "cancelled out") of a too-short antenna.

An antenna that is reactance-compensated for a different frequency is said to be *loaded*, or in the case of a very low frequency antenna, *inductively loaded*. Three basic forms of loading are popular: *discrete loading, continuous loading,* and *linear loading*.

Discrete loading means that there is a discrete, or lumped, inductance in series with the antenna radiator (Figs. 26-2A through 26-2C). These antennas are so constructed that a loading coil is placed at the center (Fig. 26-2A), top (Fig. 26-2B), or bottom (Fig. 26-2C) of the radiator element.

You will recognize these configurations as being the same as those found on mobile antennas. Indeed, low-band mobile antennas can be used in both mobile and fixed installations. Note, however, that although it is convenient to use mobile antennas for fixed locations (because they are easily available in "store bought" form); they are less efficient than other versions of the same concept. The reason is that the mobile antenna, for low frequencies, tends to be based on the standard 96- to 102-in whip antenna used by amateur operators on 10 m or Citizens Band operators on 11 m. In fixed locations, on the other hand, longer radiator elements (which are more efficient) are more easily handled. For example, a 16- to 30-ft high aluminum radiator element can easily be constructed of readily available materials. The 16-ft element can be bought in the form of one or two lengths of 1- to 1.5-in aluminum tubing at do-it-yourself outlets.

A problem seen with these antennas is that they tend to be rather high Q, so the bandwidth is necessarily narrow. An antenna might work in the center of a band, but present a high VSWR at the ends of the band, and thus be unusable. This problem is solved by making the inductor variable so that slightly different inductance values can be selected at different frequencies across the band. For the base-loaded version (Fig. 26-2C), this is particularly easy: a rotary inductor (perhaps motor driven for remote operation) can be used. For the other configurations, a tapped fixed inductor can be used instead. Each tap represents a different inductance value. Either clip connectors, or relay connections, can be used to select which tap is used.

A continuously loaded antenna has the inductance distributed along the entire length of the radiator (Fig. 26-2D). Typical of these antennas is the helically wound verticals in which about a half-wavelength of insulated wire is wound over an insulating form (such as a length of PVC pipe or a wooden dowel); the turns of the coil are spread out over the entire length of the insulated support.

Linear loading (Fig. 26-2E) is an arrangement whereby a section of the antenna is folded back on itself like a stub. Antennas of this sort have been successfully built from the same type of aluminum tubing as regular verticals. For 75/80-m (3.75-MHz) operation a length of 30 ft for the radiator represents 41°, while a normal λ/4 vertical is 90°. The difference between 90° and 41° of electrical length is made up by the "hairpin" structure at the base.

Shortened horizontal antennas

The same strategies that worked for vertical antennas also work for horizontal antennas, although in the horizontal case we are simulating a half wavelength (180°) balanced antenna—rather than a λ/4 unbalanced antenna. Figure 26-3 shows several different shortened, low frequency antennas that are based on the same methods as the verticals shown previously.

Figures 26-3A through 26-3C show discretely loaded dipole antennas. Figures 26-3A and 26-3B are center-loaded versions, and Fig. 26-3C is a center (of each element) -loaded version. In each case, it is assumed that the radiator elements are the same physical length. In the example of Fig. 26-3A, the coil is tapped to provide a match to either 52- or 75-Ω transmission line. In some variants, the shield of the coaxial-cable transmission line is connected directly to the junction of the coil and one radiator element, and the coax center conductor is connected to the tap that best matches the impedance of the line.

The impedance-matching problem is solved a little differently in Fig. 26-3B. In this type of antenna, the coil is used to center-load the dipole, but the transmission line is connected to a link wound on the same form as the loading inductor. The turns ratio between the loading inductor and the coupling link determines the impedance match.

A "hairpin" linear loading scheme is shown in Fig. 26-3D. This design is basically the same as for the vertical case, but it is balanced out of respect for the design of the dipole. This type of design is used for both the driven and parasitic elements on some commercial 40-m beam antennas. In addition, some "add-on" 40-m dipoles (designed for beam antennas that were intended for operation at frequencies in the 20-m and higher bands) use this method. Such antennas are essentially rotatable dipoles.

The continuously loaded dipole of Fig. 26-3E is constructed like the helical vertical (i.e., about a half-wavelength of insulated wire is wound over the entire length of an insulated rod or pipe of some sort). The winding can be either broken at its center point to accommodate the feedline, or link-coupled to the transmitter, or receiver, as shown in Fig. 26-3F. Of the two feed methods, the most popular appears to be the type that breaks the winding into two pieces.

The form of continuously loaded dipole in Fig. 26-3E has a combination of the two methods of feed. The distributed loading coil is broken into two sections, as is often done on continuously loaded dipoles. But in this case, a portion of the overall inductance is made by using a discrete inductor that is part of a toroidal transformer T_1. The length of the wire used for the continuous loading coil is somewhat shorter (find by experimentation) than otherwise would be the case because of the inductance of the transformer secondary. Transformer T_1 can be wound using the same sort of toroidal ferrite or powdered iron core used for Balun transformers.


To XMTR
A
To XMTR
B
To XMTR
C
To XMTR
D
To XMTR
E
T_1
To XMTR
F

26-3 Inductance loading of a dipole: (A) center loading with impedance tapped coil; (B) center loading with transformer coupling; (C) loading at center of elements; (D) linear loading (hairpin); (E) linear or length loading; (F) transformer coupling.

Loaded tower designs

Many amateur radio stations and other services use a rotatable beam antenna on top of a tower. Typical towers are from 30 to 120 ft in height. In my locality, towers to 30 ft, or less than 3 ft above the roof line, whichever is taller, can be erected without a permit as long as they are attached to the house and will not fall onto a power line, or across the property line, in a catastrophic failure. Higher towers must be erected under a mechanical permit, and properly inspected by the county. These towers typically support a two-element (or more, three is popular) Yagi /Uda beam antenna, or a quad, or some other highly directional antenna. But they can also be treated as a vertical antenna under the right circumstances.

If the tower is close to 66 ft high (which is a popular height for amateur radio towers), then the tower (already λ/4) can be used as a resonant vertical on 75/80 m. The same tower can also be used on lower frequencies if proper antenna tuning unit (ATU) components are provided.

Figure 26-4 shows a situation in which an 80- to 110-ft tower is insulated from ground, and is considered a random-length vertically polarized Marconi antenna. Like other such antennas, it is fed by a simple L-section, or reverse L-section, ATU. Note the approximate values of the inductors and capacitors in each configuration, and also their relationships. On the 40- and 75/80-m versions, the tower is too long, so a series capacitance and shunt inductance are used for the ATU (i.e., Reverse L-section coupler). On the other hand, the tower is too short for 160 m, so the inductor and capacitor are reversed.

There is only one small problem with the design of Fig. 26-4: Compared with grounded towers, insulated towers are expensive to buy and install. In addition, lightning protection is probably better in the grounded tower. So how do we work a grounded tower? See Fig. 26-5. In this antenna, the tower is grounded at its base. If the tower is mounted to a concrete pedestal (the usual arrangement), then a separate ground rod and ground wire adjacent to the pedestal must be provided. Concrete is not a good insulator, but it is also not a good conductor. A *delta feed* system is used with this antenna. That is, a single wire from the ATU is connected to a point on the antenna where an impedance match can be achieved. It is important that the ATU be spaced away from the tower base (as shown), and the wire must be run straight to the feedpoint on the antenna. This system is an example of several possible *shunt feeding* systems.

Random-length Marconi

One of the old standbys for all bands is the random-length Marconi antenna. Such antennas consist of a length of wire, typically (but not always) less than λ/4, and fed at one end with coaxial cable and an L-section coupler (Fig. 26-6). The antenna radiator element can be angled in any direction as needed, but it works best if the radiator is either as horizontal, or vertical, as possible (for pure polarization). The usual situation, however, is to run the wire at an inclined angle, or with about equal portions horizontal and vertical (see the inverted L) which yields complex polarization.


90' tower
6 µH
440 pF
160
75/80
440 pF
To
XMTR
Tower
insulator
40
15 µH
440 pF
2 µH

26-4 Method for impedance matching a tower antenna.


Single-conductor feedline
(delta feed)
ATU
Coax to XMTR

26-5 Delta matching a grounded vertical tower antenna.


Rope
Radiator $<\frac{\lambda}{4}$
End insulator
L_1
C_1
Coupler
(interchange L_1 and C_1
when antenna $>\frac{\lambda}{4}$)

26-6 Random-length wire antenna.

The L-section coupler shown in Fig. 26-6 is set up for the case where the antenna radiator element is less than λ/4 (i.e., a series inductor and a shunt capacitor). If the antenna is longer than λ/4 on some frequency, then reverse the positions of the capacitor and inductor.

Inverted-L antennas

Another popular antenna for low frequencies is the *λ/4 inverted-L* (Fig. 26-7). In this type of antenna, two sections are erected at a 90° angle with respect to each other; one vertical and the other horizontal. One way to think of this antenna is bent λ/4 vertical, although some people liken it to a top-loaded vertical. The feedline can be 52- or 75-Ω coaxial cable.

It is generally the case that the sections of the inverted-L are equal in length (λ/8 each), but that is not strictly necessary. As the vertical section becomes longer (with overall length remaining at λ/4), the angle of radiation depresses.

One popular method of construction is to use a tower for the vertical section, and a run of wire for the horizontal section. If you already have a 60-ft tower to accommodate the beam antenna used on higher frequencies, then it is relatively easy to build an inverted-L antenna for 160 m.



26-7 L-section quarter-wavelength antenna.

The linearly loaded "tee" antenna

A "tee" antenna consists of a horizontal radiator element fed at the center with a single conductor wire (not coax) that is a quarter-wavelength long, and goes away from the radiator at a right angle. Such antennas were popular prior to World War II in the United States, although popularity fell off in the late 1930s as other types (and reasonably priced transmission lines) became available. The tee is possibly one of the oldest forms of radio transmitting antennas. Like other antennas at low frequencies, however, it is far too long for easy use in most locations.

We can, however, linearly load the tee by folding the ends of the radiator back on themselves to form the zigzag pattern of Fig. 26-8. Popular in Europe for some time, this antenna can provide reasonable performance on the lower frequencies without using too much horizontal space.

The radiator element consists of three sections that are each about $\lambda/6$ long ($L_1 = 164/F_{\mathrm{MHz}}$), and spaced 8 to 12 in apart; they are parallel to each other. The quarter-wavelength transmission line is connected to the center point of the middle section of the radiator element.

Figure 26-9 shows how the linearly loaded tee antenna could be built using wire for the radiator elements. Spreaders made of 24-in-long 1 × 2-in lumber (treated against the weather), plastic, or some other synthetic material can be used. Each spreader has three holes drilled in it spaced about 10 in apart. Spreaders A and E are end spreaders, and are identical—except for being upside down with respect to each other. In each case, one of the radiator element conductor sections is terminated, while the other passes through to the back of the spreader to join the center radiator element. The other spreaders are used either for center support, as in C (note the transmission line attachment), or for interim support between the center insulator and the end insulators.


L_1
S
S
$\frac{\lambda}{4}$
ATU
To XMTR

$$L_1 = \frac{164}{F_{\mathrm{MHz}}}$$

$$\frac{\lambda}{4} = \frac{246}{F_{\mathrm{MHz}}}$$

26-8 Tee-loaded antenna.


Wire
Screw eye
A
B
C
D
E
Screw eye
Wire
Spreaders
λ/4 to ATCU
Tie
wire

26-9 Shortened tee antenna.

This page intentionally left blank

27
CHAPTER

Measurements and adjustment techniques

THIS CHAPTER EXAMINES SOME OF THE INSTRUMENTS AND TECHNIQUES FOR TESTING antenna systems, whether brand new installations, or in troubleshooting situations on older antenna. The basic radio system is shown in Fig. 27-1. We have several elements in the system: transmitter, low-pass filter, impedance-matching unit, a coaxial relay if the receiver is separate from the transmitter, and the antenna. Connecting these elements are lengths of transmission line. In most modern radio systems below the microwaves, the transmission line is coaxial cable.

The low-pass filter and matching unit may be considered optional by some, but some designers regard them as essentially standard equipment, especially for HF and low-band VHF systems. The low-pass filter has the job of removing harmonics from the output signal that could interfere with other radio systems or radio and TV broadcast reception. It will pass only those frequencies below a certain cutoff point. The impedance matching unit is used to "tune out" impedance mismatches that cause the transmitter to see an excessive VSWR. These units are common in VLF, MW, and HF communications stations, as well as AM broadcasting stations. The matching unit also provides additional attenuation of the harmonics, so it makes the output even cleaner than is possible with the low-pass filter alone.

Another reason to use the matching unit is to allow the radio transmitter to put out the maximum allowable RF power. Modern solid-state final amplifiers are not tolerant of VSWR. In addition, these units use fixed-tuned low-pass filters for each band rather than the wide-range pi networks common on vacuum tube transmitters. Solid-state transmitters usually include a feedback *automatic load control* (ALC) that reduces output power when a high VSWR is sensed. The VSWR cut-in knee begins around 1.5:1 and completely shuts off the transmitter when the VSWR gets high (typically above 2.5:1 or 3:1). The external T/R relay is not used on most modern systems because the receiver and transmitter are typically housed inside of the same box. The coaxial relay was used in days past, when

Copyright 2001 - the McGraw-Hill Companies



27-1 Basic communications radio station setup.

a separate receiver needed to use the same antenna. In addition, many modern solid-state equipments use PIN diode T/R switching.

Transmission lines

The transmission line is not merely a wire that carries RF power to the antenna. It is actually a complex circuit that simulates an infinite *LC* network. There is a characteristic impedance Z_o, also called *surge impedance*, which describes each transmission line. This impedance is the square root of the ratio of the capacitance and inductance per unit of length. When a load having a "resistive-only" impedance equal to the surge impedance of the transmission line is connected, then we will see maximum transfer of power between the line and the antenna.

We cannot deal extensively with transmission-line theory here, and refer the reader instead to previous chapters. We must, however, have at least some idea of what the circuit looks like. Figure 27-2 shows a model of a transmission line in which Z_o is the surge impedance of the line, R_1 is the load impedance of the antenna, and R_2 is the output impedance of the transmitter. In a properly designed system all three impedances either will be equal ($Z_o = R_1 = R_2$) or a matching network will make them equal.

We must consider the electrical situation along the transmission line in order to understand the readings that we see on our instruments. Figure 27-3 shows several possible situations. These graphs are of the RF voltage along the line, with voltage on the vertical axis and transmission line length (expressed in wavelengths of the RF signal) along the horizontal axis. When the system is matched ($Z_o = R_1$), the voltage



L = Inductance per unit length
C = Capacitance per unit length

27-2 Equivalent circuit of transmission line.

is the same everywhere along the line (Fig. 27-3A). This line is said to be “flat.” But when Z_o and R_2 are not equal, then the voltage varies along the line with wavelength. In mismatched systems, not all of the power is radiated by the antenna, but rather is reflected back to the transmitter. The forward and reflected waves combine algebraically at each point along the line to form standing waves (Fig. 27-3B). We can plot the voltage maxima ($V_{\max}$) and minima ($V_{\min}$). Keep this graph in mind for a few minutes because you will refer again to it when we deal with VSWR.

Two special situations occur in transmission line and antenna systems that yield similar results. The entire forward power is reflected back to the transmitter (none radiated) if the load (i.e., antenna) end of the transmission line is either open or shorted. The voltage plot for an open transmission line (R_2 is infinite) is shown in Fig. 27-3C, and that for the shorted line is shown in Fig. 27-3D. Note that they are very similar to each other except for where the minima ($V_{\min} = 0$) occur. The minima are offset from each other by 90° (i.e., quarter-wavelength).

Calculating standing wave ratio

The VSWR can be calculated from any of several bits of knowledge. Even if you don’t have a VSWR meter, therefore, it is possible to determine VSWR. If the antenna load impedance (R_2) is not equal to Z_o, then we can calculate VSWR from one of the following:

If Z_o is greater than R_2:

$$\text{VSWR} = \frac{Z_o}{R_2} \qquad \textbf{[27.1]}$$

If Z_o is less than R_2:

$$\text{VSWR} = \frac{R_2}{Z_o} \qquad \textbf{[27.2]}$$



27-3 Voltage along line versus line electrical length: (A) flat line with matched impedance; (B) unequal impedances; (C) open load; (D) shorted load.

We can also measure the forward and reflected power, and calculate the VSWR from those readings:

$$\mathrm{VSWR} = \frac{1 + \sqrt{(P_r/P_f)}}{1 - \sqrt{(P_r/P_f)}} \qquad \textbf{[27.3]}$$

where

VSWR is the voltage standing wave ratio
P_r is the reflected power
P_f is the forward power

If we can measure either the voltage maximum and minimum, or the current maximum and minimum, then we can calculate SWR:

$$\mathrm{VSWR} = \frac{V_{\max}}{V_{\min}} \qquad \textbf{[27.4]}$$

Finally, if the forward and reflected voltage components at any given point on the transmission line can be measured, then we can calculate the VSWR from:

$$\mathrm{VSWR} = \frac{V_f + V_r}{V_f - V_r} \qquad \textbf{[27.5]}$$

where

V_f is the forward voltage component
V_r is the reflected voltage

The last equation, based on the forward and reflected voltages, is the basis for many modern VSWR and RF power meters.

Impedance bridges

We can make antenna impedance measurements using a variant of the old-fashioned Wheatstone bridge. Figure 27-4A shows the basic form of the bridge in its most generalized form. The current flowing in the meter will be zero when $(Z_1/Z_2) = (Z_3/Z_4)$. If one arm of the bridge is the antenna impedance, then we can adjust the others to make the bridge null to make the measurement. A typical example is shown in Fig. 27-4B. The antenna connected to J_2 is one arm of the bridge, while R_2 is a second. The value of R_2 should be 50 Ω or 75 Ω, depending upon the value of the expected antenna impedance. The choice of 68 Ω is a good compromise for meters to operate on both types of antennas. The other two arms of the bridge are the reactances of C_{1A} and C_{1B}, which is a single differential capacitor. Tune C_1 until the meter is nulled, and then read the antenna from the dial. At least one instrument allows the technician to plug in a resistor element equal to system impedance.

Calibrating the instrument is simple. A series of noninductive carbon composition resistors having standard values from 10 to 1000 Ω are connected across J_2. The meter is then nulled, and the value of the load resistor is inscribed on the dial at the point.


RF
source
Z_1
Z_3
Detector
Z_2
Z_4

27-4A Basic Wheatstone bridge.


J_1
RF
input
R_1
4.7 kΩ
C_{1A}
C_{1B}
R_2
68 Ω
J_2
Antenna
CR_1
1N60
$R3$
10 kΩ
RFC_1
1 mH
C_2
0.01 µF
M_1
0–100 µA dc
meter

27-4B SWR bridge.

The basic circuit of Fig. 27-4B is useful only to measure the resistive component of impedance. We can modify the circuit as shown in Fig. 27-4C to account for the reactive component. An example of a commercial hand-held radio antenna impedance bridge is shown in Fig. 27-5.

The RF noise bridge

This section explores a device that was once associated only with engineering laboratories, but turns out to have applications in general communications servicing as well: the *RF noise bridge*. It is one of the most useful, low-cost, and often overlooked test instruments in our armamentarium.

Several companies have produced low-cost noise bridges: Omega-T, Palomar Engineers, The Heath Company, and, most recently, MFJ. The Omega-T and the Palomar Engineers models are shown in Fig. 27-5. The Omega-T device is a small cube with minimal dials, and a pair of BNC coax connectors (*antenna* and *receiver*). The dial is calibrated in ohms, and measures only the resistive component of impedance. The Palomar Engineers device is a little less eye appealing, but does everything the Omega-T does; in addition, it allows you to make a rough measurement of the reactive component of impedance. The Heath Company added their Model HD-1422 to the lineup. And the latest entry is the MFJ-204B antenna bridge.

Over the years, some people have found the noise bridge very useful for a variety of test and measurement applications, especially in the HF and low-VHF regions.



27-4C Circuit with balance control added.



27-5 Commercially available amateur noise bridges.

Those applications are not limited to the testing of antennas (which is the main job of the noise bridge). In fact, although the two-way technician (including CB) or amateur radio operator, will measure antennas, tuned circuits, and resonant cavities with the device, consumer electronics technicians will find other applications.

Figure 27-6 shows the circuit of a noise bridge instrument. The bridge consists of four arms. The inductive arms (L_{1b} and L_{1c}) form a trifilar wound transformer over a ferrite core with L_{1a}, so a signal applied to L_{1a} is injected into the bridge circuit. The measurement consists of a series circuit of a 200-**Ω** potentiometer and a 120-pF variable capacitor. The potentiometer sets the range (0 to 200 **Ω**) of the resistive component of measured impedance, while the capacitor sets the reactance component. Capacitor C_2 in the unknown arm of the bridge is used to balance the measurement capacitor. With C_2 in the circuit, the bridge is balanced when C is approximately in the center of its range. This arrangement accommodates both inductive and capacitive reactances, which appear on either side of the "zero" point (i.e., the midrange capacitance of C). When the bridge is in balance, the settings of R and C reveal the impedance across the unknown terminal.

A reverse-biased zener diode (zeners normally operate in the reverse-bias mode) produces a large amount of noise because of the avalanche process inherent in zener operation. Although this noise is a problem in many other applications, in a noise bridge it is highly desirable: the richer the noise spectrum the better the performance. The spec-



B1
9 Vdc
− +
+
C10
4.7 μF
−
C9
0.1 μF
R5
1000 Ω
R4
22 kΩ
R6
680 Ω
C5
0.01 μF
C8
250 pF
reactance
R7
10 kΩ
Q2
ECG-222
T1
R8
200 Ω
linear
type-AB
J2
RCVR
R5
1500 kΩ
C3
0.01 μF
Q1
ECG-222
C2
0.02 μF
D3
6.8 Vdc
(noise source)
8
4
3
5
IC1
555
timer
7
1
6
2
R1
6800 kΩ
D1
D1, D2,
IN914
or
IN4148
D2
R2
6800 Ω
C1
0.01 μF
C6
40 pF
balance
C7
100 pF
S.M.
T1: toroid trifilar
transformer
10T, no. 26 over
FT-50-43 core
Antenna
J1

27-6 Noise bridge circuit.

trum is enhanced because of the 1-kHz square-wave modulator that chops the noise signal. An amplifier boosts the noise signal to the level needed in the bridge circuit.

The detector used in the noise bridge is a tunable receiver covering the frequencies of interest. The preferable receiver uses an AM demodulator, but both CW (morse code) and SSB receivers will do in a pinch. The quality of the receiver depends entirely on the precision with which you need to know the operating frequency of the device under test.

Adjusting antennas

Perhaps the most common use for the antenna noise bridge is finding the impedance and resonant points of an HF antenna. Connect the *receiver* terminal of the bridge to the *antenna* input of the HF receiver through a short length of coaxial cable as shown in Fig. 27-7. The length should be as short as possible, and the characteristic impedance should match that of the antenna feedline. Next, connect the coaxial feedline from the antenna to the *antenna* terminals on the bridge. You are now ready to test the antenna.

Set the noise bridge resistance control to the antenna feedline impedance (usually 50 to 75 Ω for most common antennas). Set the reactance control to midrange (zero). Next, tune the receiver to the *expected* resonant frequency (F_{exp}) of the antenna. Turn the noise bridge *on*, look for a noise signal of about S9 (will vary on different receivers), and if—in the unlikely event that the antenna is resonant on the expected frequency—you will find yourself right in the middle of the null.

Adjust the *resistance* control R on the bridge for a null, i.e., minimum noise as indicated by the S meter. Next, adjust the *resistance* control C for a null. Repeat the adjustments of the R and C controls for the deepest possible null, as indicated by the lowest noise output on the S meter (there is some interaction between the two controls).



27-7 Connection of noise bridge.

A perfectly resonant antenna will have a reactance reading of zero ohms, and a resistance of 50 to 75 Ω. Real antennas might have some reactance (the less the better), and a resistance that is somewhat different from 50 to 75 Ω. Impedance-matching methods can be used to transform the actual resistive component to the 50- or 75-Ω characteristic impedance of the transmission line. The results to expect:

1. If the resistance is close to zero, then suspect that there is a short circuit on the transmission line. Suspect an open circuit if the resistance is close to 200 Ω.
2. A reactance reading on the X_L side of zero indicates that the antenna is too long, while a reading on the X_C side of zero indicates an antenna that is too short.

An antenna that is too long or too short should be adjusted to the correct length. To determine the correct length, we must find the actual resonant frequency F_r. To do this, reset the *reactance* control to zero, and then *slowly* tune the receiver in the proper direction—downband for too long and upband for too short—until the null is found. On a high-Q antenna, the null is easy to miss if you tune too fast. Don't be surprised if that null is out of band by quite a bit. The percentage of change is given by dividing the expected resonant frequency $F_{\exp}$ by the actual resonant frequency F_r, and multiply by 100:

$$\text{Change} = \frac{F_{\exp} \times 100\%}{F_r} \qquad \textbf{[27.6]}$$

Connect the antenna, noise bridge, and receiver in the same manner as above. Set the receiver to the expected resonant frequency (i.e., approximately 468/F for half-wavelength types and 234/F for quarter-wavelength types). Set the resistance control to 50 Ω or 75 Ω, as appropriate for the normal antenna impedance and the transmission line impedance. Set the reactance control to zero. Turn the bridge on and listen for the noise signal.

Slowly rock the reactance control back and forth to find on which side of zero the null appears. Once the direction of the null is determined, set the reactance control to zero, and then tune the receiver toward the null direction (downband if null is on X_L side and upband if it is on the X_C side of zero).

A less-than-ideal antenna will not have exactly 50- or 75-Ω impedance, so some adjustment of R and C to find the deepest null is in order. You will be surprised how far off some dipoles and other forms of antennas can be if they are not in "free space," (i.e., if they are close to the earth's surface).

Nonresonant antenna adjustment

We can operate antennas on frequencies other than their resonant frequency if we know the impedance:

$$X_C = X = \frac{55}{68 - C} - 2340 \qquad \textbf{[27.7]}$$

or

$$X_L = X = 2340 - \frac{159{,}155}{68 + C} \qquad \textbf{[27.8]}$$

Now, plug *"X"* calculated from Eq. 27.7 or 27.8 into $X_f = X/F$ where F is the desired frequency in MHz.

Other jobs

The noise bridge can be used for a variety of jobs. We can find the values of capacitors and inductors, determine the characteristics of series- and parallel-tuned resonant circuits, and adjust transmission lines.

Transmission line measurements Some antennas and non-noise measurements require antenna feedlines that are either a quarter-wavelength or half-wavelength at some specific frequency. In other cases, a piece of coaxial cable of specified length is required for other purposes: for instance, the dummy load used to service depth sounders is nothing but a long piece of shorted coax that returns the echo at a time interval that corresponds to a specific depth. We can use the bridge to find these lengths as follows:

1. Connect a short circuit across the *unknown* terminals and adjust R and X for the best null at the frequency of interest. (*Note*: both will be near zero.)
2. Remove the short circuit.
3. Connect the length of transmission line to the *unknown* terminal—it should be longer than the expected length.
4. For quarter-wavelength lines, shorten the line until the null is very close to the desired frequency. For half-wavelength lines, do the same thing, except that the line must be shorted at the far end for each trial length.

The velocity factor of a transmission line (usually designated by the letter V in equations) is a decimal fraction that tells us how fast the radio wave propagates along the line relative to the speed of light in free space. For example, foam dielectric coaxial cable is said to have a velocity factor of $V = 0.80$. This number means that the signals in the line travel at a speed 0.80 (or 80 percent) of the speed of light.

Because all radio wavelength formulas are based on the velocity of light, you need the V value to calculate the physical length needed to equal any given electrical length. For example, a half-wavelength piece of coax has a physical length of $(492 \times V)/F_{\text{MHz}}$ feet. Unfortunately, the real value of V is often a bit different from the published value. You can use the noise bridge to find the actual value of V for any sample of coaxial cable as follows:

1. Select a convenient length of the coax more than 12 ft in length and install a PL-259 RF connector (or other connector compatible with your instrument) on one end, and short-circuit the other end.
2. Accurately measure the physical length of the coax in feet; convert the "remainder" inches to a decimal fraction of a foot by dividing by 12 (e.g., 32 ft 8 in= 32.67 ft because 8 in/12 in = 0.67). Alternatively, cut off the cable to the nearest foot and reconnect the short circuit.
3. Set the bridge *resistance* and *reactance* controls to zero.
4. Adjust the monitor receiver for deepest null. Use the null frequency to find the velocity factor $V = FL/492$, where V is the velocity factor (a decimal fraction); F is the frequency in megahertz; and L is the cable length in feet.

Tuned circuit measurements An inductor/capacitor (*LC*) tuned "tank" circuit is the circuit equivalent of a resonant antenna, so there is some similarity between the two measurements. You can measure resonant frequency with the noise bridge to within ±20 percent (or better if care is taken). This accuracy might seem poor, but it is better than you can usually get with low-cost signal generators, dip meters, absorption wavemeters, and the like.

A *series tuned circuit* exhibits a low impedance at the resonant frequency and a high impedance at all other frequencies. Start the measurement by connecting the series tuned circuit under test across the *unknown* terminals of the dip meter. Set the *resistance* control to a low resistance value, close to zero ohms. Set the *reactance* control at midscale (zero mark). Next, tune the receiver to the expected null frequency, and then tune for the null. Make sure that the null is at its deepest point by rocking the R and X controls for best null. At this point, the receiver frequency is the resonant frequency of the tank circuit.

A *parallel resonant circuit* exhibits a high impedance at resonance and a low impedance at all other frequencies. The measurement is made in exactly the same manner as for the series resonant circuits, except that the connection is different. Figure 27-8 shows a two-turn link coupling that is needed to inject the noise signal into the parallel resonant tank circuit. If the inductor is the toroidal type, then the link must go through the hole in the doughnut-shaped core and then connect to the *unknown* terminals on the bridge. After this, proceed exactly as you would for the series tuned tank measurement.

Capacitance and inductance measurements The bridge requires a 100-pF silver mica test capacitor and a 4.7-μH test inductor, which are used to measure inductance and capacitance, respectively. The idea is to use the test components to form a series-tuned resonant circuit with an unknown component. If you find a resonant frequency, then you can calculate the unknown value. In both cases, the series tuned circuit is connected across the *unknown* terminals of the dip meter, and the series tuned procedure is followed.



27-8 Noise bridge connection to *LC* tank circuits.

To measure inductance, connect the 100-pF capacitor in series with the unknown coil across the *unknown* terminals of the dip meter. When the null frequency is found, find the inductance from

$$L = \frac{253}{F^2} \tag{27.9}$$

where

L is the inductance, in microhenries
F is the frequency, in megahertz

Connect the test inductor across the *unknown* terminals in series with the unknown capacitance. Set the *resistance* control to zero, tune the receiver to 2 MHz, and readjust the *reactance* control for null. Without readjusting the noise bridge control, connect the test inductor in series with the unknown capacitance and retune the receiver for a null. Capacitance can now be calculated from:

$$C = \frac{5389}{F^2} \tag{27.10}$$

where:

C is in picofarads
F is in megahertz

Dip oscillators

One of the most common instruments for determining the resonant frequency of an antenna is the so-called dip oscillator or dip meter. Originally called the *grid dip meter*, the basis for this instrument is the fact that its output energy can be absorbed by a nearby resonant circuit (or antenna, which is an electrically resonant LC tank circuit). When the inductor of the dip oscillator (see Fig. 27-9) is brought into

SOLID STATE
DIP METER

27-9 Dip meter.

close proximity to a resonant tank circuit, and the oscillator is operating on the resonant frequency, then a small amount of energy is transferred. This energy loss shows up on the meter pointer as a slight "dipping" action. The dip is extremely sharp, and is easily missed if the meter frequency dial is tuned too rapidly.

Antennas are resonant circuits, and can be treated in a manner similar to *LC* tank circuits. Figure 27-10A shows one way to couple the dip oscillator to a vertical antenna radiator. The inductor of the dipper is brought into close proximity to the base of the radiator. Figure 27-10B shows the means for coupling the dip oscillator


Radiator
Dip meter
Base insulator
Mount

27-10A Direct coupling the dip meter to antenna.


Dip meter coil
2–3 turn loop
Coax to antenna
2–3 turn loop
For antennas with coax connector at feedpoint

27-10B Coupling the dip meter to coaxial cable.

to systems where the radiator is not easily accessed (as when the antenna is still erected). We connect a small two- or three-turn loop to the transmitter end of the transmission line, and then bring the inductor of the dipper close to it. A better way is to connect the loop directly to the antenna feedpoint.

There are two problems with dip meters that must be recognized in order to best use the instrument. First, the dip is very sharp. It is easy to tune past the dip and not even see it. To make matters worse, it is normal for the meter reading to drop off gradually from one end of the tuning range to the other. But if you tune very slowly, then you will notice a very sharp dip when the resonant point is reached.

The second problem is the dial calibration. The dial gradations of inexpensive dip meters are too close together and are often erroneous. It is better to monitor the output of the dip oscillator on a receiver and depend upon the calibration of the receiver for data.

Selecting and using RF wattmeters and antenna VSWR meters

A key instrument required in checking the performance of, or troubleshooting, radio transmitters is the RF power meter (or "wattmeter"). These instruments measure the output power of the transmitter, and display the result in watts, or some related unit. Closely related to RF wattmeters is the antenna VSWR meter. This instrument also examines the output of the transmitter and gives a relative indication of output power. It can be calibrated to display the dimensionless units of *voltage standing wave ratio.* Many modern instruments, a couple of which will be covered as examples in this chapter, combine both RF power and VSWR measurement capabilities.

Measuring RF power

Measuring RF power has traditionally been notoriously difficult, except perhaps in the singular case of continuous-wave (CW) sources that produce nice, well-behaved sine waves. Even in that limited case, however, some measurement methods are distinctly better than others.

The peak voltage of a waveform is 100 V (i.e., peak-to-peak 200 V). Given that the CW waveform is sinusoidal, we know that the root mean square (RMS) voltage is 0.707 V. The output power is related to the RMS voltage across the load by

$$P = \frac{(V_{\mathrm{rms}})^2}{Z_o} \qquad \textbf{[27.11]}$$

where:

P is the power, in watts
V_{rms} is the RMS potential, in volts
Z_o is the load impedance, in ohms

If we assume a load impedance of 50 Ω, then we can state that the power in our hypothetical illustration waveform is 100 W.

We can measure power on unmodulated sinusoidal waveforms by measuring either the RMS or peak values of either voltage or current, assuming that a constant-value resistance load is present. But the problem becomes more complex on modulated signals. The various power readings on a Bird model 4311 peak power meter, the peak (PEP) and average powers, vary markedly with modulation type.

One of the earliest forms of practical RF power measurement was the thermocouple RF ammeter (see Fig. 27-11). This instrument works by dissipating a small amount of power in a small resistance inside the meter, and then measuring the heat generated with a thermocouple. A dc current meter monitors the output of the thermocouple device, and indicates the level of current flowing in the heating element. Because it works on the basis of the power dissipated heating a resistance, *a thermocouple RF ammeter is inherently an RMS-reading device*. Because of this feature it is very useful for making average power measurements. If we know the RMS current and the resistive component of the load impedance, and if the reactive component is zero or very low, then we can determine RF power from the familiar expression:

$$P = I^2 \times R_i \qquad \textbf{[27.12]}$$

There is, however, a significant problem that keeps thermocouple RF ammeters from being universally used in RF power measurement: those instruments are highly frequency-dependent. Even at low frequencies, it is recommended that the meters be mounted on insulating material with at least ⅜-in spacing between the meter and its metal cabinet. Even with that precaution, however, there is a strong frequency dependence that renders the meter less useful at higher frequencies. Some meters are advertised to operate into the low-VHF region, but a note of caution is necessary. That recommendation requires a copy of the calibrated frequency response curve for that specific meter, so that a correction factor can be added (or subtracted) from



27-11 Circuit for thermocouple RF ammeter.

the reading. At 10 MHz and higher, the readings of the thermocouple RF ammeter must be taken with a certain amount of skepticism unless the original calibration chart is available.

We can also measure RF power by measuring the voltage across the load resistance (see Fig. 27-12). In the circuit of Fig. 27-12, the RF voltage appearing across the load is scaled downward to a level compatible with the voltmeter by the resistor voltage divider (R_2/R_3). The output of this divider is rectified by CR_1 and filtered to dc by the action of capacitor C_2.

The method of measuring the voltage in a simple diode voltmeter is valid only if the RF signal is unmodulated and has a sinusoidal waveshape. While these criteria are met in many transmitters, they are not universal. If the voltmeter circuit is peak reading, as in Fig. 27-12, then the peak power is

$$P = \frac{V_o^2}{R_1} \qquad \textbf{[27.13]}$$

The average power is then found by multiplying the peak power by 0.707. Some meter circuits include voltage dividers that precede the meter and thereby convert the reading to RMS, and thus convert the power to average power. Again, it must be stressed that terms like RMS, average, and peak have meaning only when the input



27-12 RF voltmeter "wattmeter."

RF signal is both unmodulated and sinusoidal. Otherwise, the readings are meaningless unless calibrated against some other source.

It is also possible to use various bridge methods for measurement of RF power. Figure 27-13 shows a bridge set up to measure both forward and reverse power. This circuit was once popular for VSWR meters. There are four elements in this quasi-Wheatstone bridge circuit: R_1, R_2, R_3, and the antenna impedance (connected to the bridge at J_2). If R_{ant} is the antenna resistance, then we know that the bridge is in balance (i.e., the null condition) when the ratios R_1/R_2 and R_3/R_{ant} are equal. In an ideal situation, resistor R_3 will have a resistance equal to R_{ant} , but that might overly limit the usefulness of the bridge. In some cases, therefore, the bridge will use a compromise value such as 67 **Ω** for R_3. Such a resistor will be usable on both 50- and 75-**Ω** antenna systems with only small errors. Typically, these meters are designed to read relative power level, rather than the actual power.

An advantage of this type of meter is that we can get an accurate measurement of VSWR by proper calibration. With the switch in the *forward* position, and RF power applied to J_1 (XMTR), potentiometer R_6 is adjusted to produce a full-scale deflection on meter M_1. When the switch is then set to the *reverse* position, the meter will read reverse power relative to the VSWR. An appropriate VSWR scale is provided.



27-13 A bridge arrangement to measure both forward and reverse power.

A significant problem with the bridge of Fig. 27-13 is that it cannot be left in the circuit while transmitting because it dissipates a considerable amount of RF power in the internal resistances. These meters, during the time when they were popular, were provided with switches that bypassed the bridge when transmitting. The bridge was only in the circuit when making a measurement.

An improved bridge circuit is the capacitor/resistor bridge in Fig. 27-14; this circuit is called the micromatch bridge. Immediately, we see that the micromatch is improved over the conventional bridge because it uses only 1 Ω in series with the line (R_i). This resistor dissipates considerably less power than the resistance used in the previous example. Because of this low-value resistance, we can leave the micromatch in the line while transmitting. Recall that the ratios of the bridge arms must be equal for the null condition to occur. In this case, the capacitive reactance ratio of C_1/C_2 must match the resistance ratio R_1/R_{ant}. For a 50-Ω antenna, the ratio is $\frac{1}{50}$, and for 75-Ω antennas it is $\frac{1}{75}$ (or, for the compromise situation, $\frac{1}{68}$). The small-value trimmer capacitor (C_2) must be adjusted for a reactance ratio with C_1 of $\frac{1}{50}$, $\frac{1}{75}$, or $\frac{1}{68}$, depending upon how the bridge is set up.

The sensitivity control can be used to calibrate the meter. In one version of the micromatch, there are three power ranges (10, 100, and 1000 W). Each range has its own sensitivity control, and these are switched in and out of the circuit as needed.

The monomatch bridge circuit in Fig. 27-15 is the instrument of choice for HF and low-VHF applications. In the monomatch design, the transmission line is segment



27-14 Micromatch wattmeter.



27-15 Monomatch wattmeter.

B, while RF sampling elements are formed by segments A and C. Although the original designs were based on a coaxial-cable sensor, later versions used either printed circuit foil transmission line segments or parallel brass rods for A, B, and C.

The sensor unit is basically a directional coupler with a detector element for both forward and reverse directions. For best accuracy, diodes CR$_1$ and CR$_2$ should be matched, as should R_1 and R_2. The resistance of R_1 and R_2 should match the transmission line surge impedance, although in many instruments a 68-Ω compromise resistance is used.

The particular circuit shown in Fig. 27-15 uses a single dc meter movement to monitor the output power. Many modern designs use two meters (one each for forward and reverse power).

One of the latest designs in VSWR meter sensors is the current transformer assembly shown in Fig. 27-16. In this instrument, a single-turn ferrite toroid transformer is used as the directional sensor. The transmission line passing through the hole in the toroid “doughnut” forms the primary winding of a broadband RF transformer. The secondary, which consists of 10 to 40 turns of small enamel wire, is connected to a measurement bridge circuit ($C_1 + C_2$ + load) with a rectified dc output.

Figures 27-17 and 27-18 show instruments based on the current transformer technique. Shown in Fig. 27-17 is the Heath model HM-102 high-frequency VSWR/power meter. The sensor is a variant on the current transformer method. This


T_1
Conductor
J_1
XMTR
J_2
ant
C_1
10 pF
D_1
IN60
D_2
IN60
C_2
10 pF
C_3
330 pF
R_1
68 kΩ
R_2
68 kΩ
C_4
330 pF
L_1
1 mH
$L2$ 1 mH
C_5
0.001 μF
10 kΩ
cal
S_1
REV
FWD
10 kΩ
cal
C_6
0.001 μF
S_2
VSWR PWR
C_7
0.01 μF
M_1
0–100 μA

27-16 Current transformer wattmeter.

27-17 Amateur radio RF wattmeter.

instrument measures both forward and reflected power, and it can be calibrated to measure VSWR.

The Bird model 43 Thruline RF wattmeter shown in Fig. 27-18 has for years been one of the industry standards in communications service work. Although it is slightly more expensive than lesser instruments, it is also versatile, and it is accurate and rugged. The Thruline meter can be inserted into the transmission line of an

27-18 Bird model 43 RF wattmeter.

antenna system with so little loss that it may be left permanently in the line during normal operations. The Model 43 Thruline is popular with land mobile and marine radio technicians.

The heart of the Thruline meter is the directional coupler transmission line assembly shown in Fig. 27-19A; it is connected in series with the antenna, or dummy load, transmission line. The plug-in directional element can be rotated 180° to measure both forward and reverse power levels. A sampling loop and diode detector are contained within each plug-in element. The main RF barrel is actually a special coaxial line segment with a 50-**Ω** characteristic impedance. The Thruline sensor works due to the mutual inductance between the sample loop and center conductor of the coaxial element. Figure 27-19B shows an equivalent circuit. The output voltage from the sampler (e) is the sum of two voltages, e_r and e_m. Voltage e_r is created by the voltage divider action of R and C on transmission line voltage E. If R is much less then X_C, then we may write the expression for e_r as

$$e_r = \frac{RE}{X_C} = RE(j\omega \mathrm{C}) \qquad \textbf{[27.14]}$$

Voltage e_m, on the other hand, is due to mutual inductance, and is expressed by

$$e_m = I(j\ \omega) \pm M \qquad \textbf{[27.15]}$$

We now have the expression for both factors that contribute to the total voltage e. We know that:

$$e = e_r + e_m \qquad \textbf{[27.16]}$$

so, by substitution,

$$e = j\omega M\left[\left(\frac{E}{Z_o}\right) \pm I\right] \qquad \textbf{[27.17]}$$


ELEMENT CIRCUIT
XMTR or load
Load or XMTR
Directional coupling
Crystal diode
Element
dc connector
Meter
Bypass
Meter cable
dc contact

27-19A Thruline sensor circuit.

27-19B Circuit of pick-up element in a Model 43 wattmeter.



At any given point in a transmission line, E is the sum of the forward (E_f) and reflected (E_r) voltages, and the line current is equal to

$$I = \frac{E_f}{Z_o} - \frac{E_r}{Z_o} \qquad \textbf{[27.18]}$$

where Z_o is the transmission line impedance.

We may specify e in the forms

$$e = \frac{j\,\omega\,M(2E_f)}{Z_o} \qquad \textbf{[27.19]}$$

and

$$e = \frac{j\,\omega\,M(2E_r)}{Z_o} \qquad \textbf{[27.20]}$$

The output voltage e of the coupler, then, is proportional to the mutual inductance and frequency (by virtue of $j\omega M$). But the manufacturer terminates R in a capacitive reactance, so the frequency dependence is lessened (see Fig. 27-19C). Each element is custom-calibrated, therefore, for a specific frequency and power range. Beyond the specified range for any given element, however, performance is not guaranteed. There are a large number of elements available that cover most commercial applications. The Thruline meter is not a VSWR meter, but rather a power meter. VSWR can be determined from the formula, or by using the nomographs in Fig. 27-20. Some of the Thruline series intended for very high power (Fig. 27-19D) applications use an in-line coaxial cable coupler (for broadcast-style hardline) and a remote indicator.



27-19C Power-frequency calibration.



27-19D High-power RF wattmeters.



27-20 Forward versus reflected power graphs.

Dummy loads

A *dummy load* is a substitute antenna for making measurements and tests. In fact, British radio engineers often refer to dummy loads as “artificial aerials.” There are several uses for these devices. Radio operators should use dummy loads to tune up on crowded channels and (only then) transfer to the live antenna.

The other use is in troubleshooting antenna systems. Suppose we have a system in which the VSWR is high enough to affect the operation of the transmitter. You can disconnect each successive element and connect the dummy load to its output. If the VSWR goes down to the normal range, then the difficulty is downstream (i.e., toward the antenna). You will eventually find the bad element (which is usually the antenna itself).

Figure 27-21 shows the most elementary form of dummy load, which consists of one or more resistors connected in parallel, series, or series-parallel so that the total resistance is equal to the desired load impedance. The power dissipation is the sum of the individual power dissipations. *It is essential that noninductive resistors be used for this application.* For this reason, carbon-composition or metal-film resistors are used. For very low frequency work, it is permissible to use special counter wound wire low-inductance resistors. These resistors, however, cannot be used over a few hundred kilohertz.

Several commercial dummy loads are shown in Figs. 27-22 through 27-24. The load in Fig. 27-22A is a 5-W model, and is typically used in Citizens Band servicing. The resistor is mounted directly on a PL-259 coaxial connector. These loads typically work to about 300 MHz, although many are not really useful over about 150 MHz. A higher-power version of the same type is shown in Fig. 27-22B. This device works to the low VHF region, and dissipates up to 50 W. I have used this dummy load for servicing high-VHF land mobile rigs, VHF-FM marine rigs, and low-VHF land mobile rigs. Very high power loads are shown in Fig. 27-23. These devices are *Bird Electronics* “coaxial resistors,” and operate to power levels up to 10, 30, and 40 kW. These high-power loads are cooled by flowing water through the body of the resistor and then exhausting the heat in an air-cooled radiator.

Our final dummy load resistor is shown in Fig. 27-24. The actual resistor is shown in Fig. 27-24A, and a schematic view is shown in Fig. 27-24B. The long, high-power noninductive resistor element is rated at 50 **Ω**, and can dissipate 1000 W for



27-21 A very basic dummy load.



27-22A CB-style 5-W dummy load.



27-22B 15-W dummy load.

WATTS
X1
X10
BLACK SCALE
RED SCALE

27-23 Termaline RF wattmeter.



27-24A Drake DL-1000 dummy load.

several minutes. If longer times, or higher powers, are anticipated, then forced air cooling is applied by adding a blower to one end of the cage. The device is modified by adding the BNC sampling jack. This jack is connected internally to either a two-turn loop, made of no.22 insulated hookup wire, or brass rods that are positioned alongside the resistor element. It will therefore pick up a sample of the signal so that it can be viewed on an oscilloscope, or used for other instrumentation purposes.


Shield
50-Ω noninductive resistor
J_1
SO-239
RF input
J_2
BNC
sampling
100 Ω
Brass tubing or
2–3 turn loop of
no. 22 wire

27-24B HF dummy load with pickup loop.

28
CHAPTER

General antenna mechanical construction techniques

ANTENNA INSTALLATION CHORES VARY IN COMPLEXITY FROM THE SIMPLE, WHICH A teenager, with no assistance, can execute properly and safely, all the way up to large-scale projects that are best left to professional antenna riggers. If your only antenna installation chore is a dipole handing between the peak of your house roof and a nearby tree, then little need be said besides "Be careful."

The purpose of this chapter is to cover both wire and intermediate installation jobs that can be done by amateurs if instructed properly. Keep in mind when planning an installation, however, that the information given herein is merely informal guidance. Always have your plans reviewed by a professional mechanical or structural engineer licensed to practice in your state. In many locales, there are good insurance reasons for this step. Also, learn and abide by local mechanical, electrical, and building codes. It is simply not worth the pain, and risk, to skirt around local laws.

Antenna erection safety

Before dealing with the radio and performance issues, let's deal first with a few antenna safety matters. You do not want to be hurt either during installation or during the next wind storm. Two problems present themselves: *reliable mechanical installation* and *electrical safety.*

Radio antennas are inherently dangerous to erect if certain precautions are not followed. It is not possible to foresee all the situations you might face in erecting an antenna. I would like to give you all possible warnings, but this is not even possible. You are on your own and must take responsibility for installing your own antenna. I can, however, give you some general safety guidelines. Knowledge of what you face and some hard-nosed, sound judgment, modulated by a little bit of common sense are the best tools on any antenna job.

Copyright 2001 - the McGraw-Hill Companies

One rule that is an absolute is that no antenna should *ever* be erected where the antenna, the feedline, or any part thereof crosses over or under a power line or pole transformer—*ever*! This is a “no kidder”—don’t do it. Every year we read sad news in magazines or newspapers about a colleague being electrocuted while installing or working on an antenna. In all these tragic cases, the antenna somehow came into contact with an ac power line. Keep in mind one dictum and make it an absolute:

There is never a time or situation when it is safe to let an antenna contact the electrical power lines!

This advice includes dipoles and other long wire antennas “thrown over” supposedly insulated lines, as well as antennas built from aluminum tubing. The excuse that the power lines are insulated is hogwash. Old insulation crumbles on contact with even a thin wire antenna. *Don’t do it*! The operant word is *never*!

Power lines look insulated, but there are often small breaks or weakened spots (especially more than a couple days after installation) that can bring the antenna into contact—lethal contact—with a “hot” power line. Every year or so we hear about an SWL, scanner/monitor buff, or ham operator being *killed* by tossing an antenna wire over a power line. Avoid making yourself into a high-powered resistor—it might blow your “life fuse.”

And the same rule applies to situations where the antenna can fall onto a power line if it fails mechanically. You have to examine the situation to see if there is any possible way for that antenna or its support structure to fall onto a power line if it breaks in any way whatsoever. Figure 28-1 is a diagram of my lot in Virginia. A 23-ft mast is erected at the back of the house, and its 23-ft “fall radius” is plotted. It should not intersect either the power lines or the cable TV line, even when it fails and is wind-whipped.

Note that the antenna could fall over the property line onto the next lot to the rear. After consultation with the other landowner and the county mechanical inspector, it was determined that my rear fence is sufficient protection for the other homeowner. Because it is technically on my land, the fence damage is my responsibility. However, should the other homeowner change his mind or a new homeowner buys the place, then my antenna may have to be moved.

Another caution is that you must be physically fit to do the work. While the on-the-ground portion of the work is usually not too strenuous, any climbing at all, even on ladders, can be taxing. Antenna materials are deceptively lightweight on the ground, but when you get up on even a small ladder, they are remarkably difficult to handle. Attempting to manhandle a 22-ft vertical once wiped my back out to the extent that I needed 800-mg of ibuprofen three times a day for about a week—and I consider myself lucky that the pain hit me after I had dismounted the ladder. Besides, if you could see me, you would wonder why a man my size was on any ladder in the first place!

Before using a ladder, learn how to use a ladder. A lot of homeowners, whether putting up antennas or painting the upstairs windows, fall off ladders that were being used incorrectly. There is a right way and a wrong way to use each of the different types of ladder; learn to use them correctly.

If the wind blows even a few kilometers per hour, the danger is magnified considerably. I recall a friend, who is a large, strong “bear of a man,” attempting to install



28-1 Antenna installation on suburban lot.

a 26-element television "all channel" rotatable antenna on the roof of his two-story beach house. He wanted to be able to pick up Richmond, VA; Norfolk, VA; Washington, DC; and Baltimore, MD, on television, plus scanner bands, from his beach house on the Chesapeake Bay. The antenna was handled easily with one hand on the ground and with no wind blowing. But up on the roof, it was a different story! "Big Al" was on the peak of the roof when an off-shore gust of wind came up suddenly and caught the antenna. It acted like a hang glider and pulled Al off the roof, plunging him down two stories to the patio below. He fractured his pelvis and busted a leg. Two months of orthopedic casts and a year of physical therapy followed—not to mention lost wages. Expensive TV antenna, I reckon. *Be careful*!

One good rule is to always work under the "buddy system." Ask as many friends as are needed to do the job safely, and always have at least one assistant, even when you think you can do it alone.

Always use quality materials and good work practices. Antennas, being potentially dangerous, always should have the best of both materials and workmanship in order to keep quality high. It is not just the electrical or radio reception workings that are important but also the ability to stay up in the air and be safe.

When planning an antenna job, keep in mind that pedestrian traffic in your yard possibly could affect the antenna system. Wires are difficult to see, and if an antenna wire is low enough to intersect someone's body, then it is possible to cause very serious injuries to passersby. In the United States, even when the person is a trespasser (or even a burglar!), the courts may hold a homeowner liable for injuries caused by an inappropriately designed and installed antenna. Take care for safety not only of yourself but also of others.

Consider a typical scenario involving a four- or five-band trap vertical antenna (Fig. 28-2). It will be 18 to 26 ft tall, judging from the advertisements in magazines, and will be mounted on a roof or mast 12 to 30 ft off the ground. Consider the case of a 25-ft-tall trap vertical installed atop a 15-ft-high telescoping TV antenna mast. The total height above ground will be the sum of the two heights: 15 ft + 25 ft = 40 ft. The tip of the vertical is 40-ft above ground level. You must select a location at which a 40-ft aluminum pole can fit—and fall. This requirement limits the selection of locations for the antenna. If this is done, then a wind storm cannot result in a shorted or downed power line if the antenna falls over.

When installing a vertical antenna, especially one that is not ground-mounted, make sure that you have help. It takes at least two people to safely install a standard HF vertical antenna, and more may be needed for especially large models. If you are alone, then go find some friends to lend an arm or two. Wrenched backs, smashed antennas, crunched house parts, and other calamities simply do not happen as often on a well-organized work party that has sufficient hands to do the job safely.

The second issue pertaining to installing antennas is old-fashioned mechanical integrity. Two problems are often seen. First, you must comply with local building



28-2 Mast-mounted vertical antenna.

codes, regulations, and inspections. The local government has a reasonable interest and absolute right to impose reasonable engineering standards on the electrical and mechanical installation of radio antennas. The second issue is that it is in your own best interest to make the installation as good as possible. Consider the local regulations as the minimum acceptable standard, not the maximum.

Both these mechanical integrity issues become extremely important if a problem develops. For example, suppose that a wind or snow storm wrecks the antenna, plus part of your house. Your insurance company may not pay off if your local government requires an inspection and you failed to get one. Make sure that the mechanical and/or electrical inspector (as required by the law) leaves a certificate or receipt proving that the final inspection was done. It could come in handy when disputing the insurance company over damage.

A quality installation starts with the selection of good hardware for the installation. Any radio-TV parts distributor who sells TV antenna hardware will have what you need in most cases. I used Radio Shack standoff brackets, ground pin, and a 19-ft telescoping mast in one installation. Wherever you buy, select the best-quality, strongest materials that you can find. Opt for steel masts and brackets over aluminum, no matter what the salesperson behind the counter tells you. Keep in mind that although salespeople can be knowledgeable and even helpful, you, not they, are responsible for the integrity of the installation.

Local government One necessary reminder is that your local government might have some interesting ideas—legal requirements, actually—concerning your antenna installation. The electrical, mechanical, and zoning codes must be observed. There is a great deal of similarity between local codes because most of them are adaptations (even adoptions) from certain national standards. But there are enough differences that one needs to consult local authorities. Indeed, you may need a license or building permit to install an antenna in the first place.

One problem that SWLs and scanner/monitor buffs face in the United States is that their antennas are not protected by the Federal Communications Commission, as are ham antennas. Local governments have limited rights to regulate ham antennas—only “reasonable” mechanical and electrical standards can be imposed. It may be illegal for you to install any type of antenna.

Save all paperwork regarding your building permit, including the inspection certificates, decals, letters or papers, and the original drawings (with the local building inspector’s stamps). If a casualty occurs, then your insurance company may elect not to pay off if you have violated an electrical, mechanical, building, or zoning code. This advice may be overlooked by an enthusiastic antenna builder, but it could prove to be a costly oversight if something bad happens.

In some jurisdictions, there might be another limitation on antenna location. Some local governments have a requirement that the antenna be able to fall over and land entirely on your own property. About 30 years ago, a Maryland county required that antennas be installed double their own length plus 50 ft from the nearest property line—until a local ham radio club sued on grounds that about 99.99 percent of the rooftop TV antennas in the county were noncompliant. In one humorous scene, a group of amateur radio operators went down to the county offices and asked for about 50,000 complaint forms. They filled out several thousand against homeowners with TV antennas before they were stopped by the county officer. Before installing any antenna, check with the local building codes!

Wire antenna construction

Volumes have been written on wire antennas. Indeed, many of my antenna books spend a lot of space on the topic. What seems to be missing in many books is details on the mechanical aspects of wire antenna construction and installation. Although some books cover the mechanical details, much is often missing. Let's take a look at some of the basics.

The basic wire antenna

Wire antennas come in a bewildering variety of forms, but for our purposes, the "standard model" is our old friend the half-wavelength horizontal dipole (Fig. 28-3). The overall length (A) in meters is found from $144/F_{\text{MHz}}$. Each element (B) is one-half the overall length, or $72/F_{\text{MHz}}$. The antenna's nominal feedpoint impedance at resonance is 73 Ω, so it is a good match to standard 75-Ω coaxial cable. It is common practice to use a 1:1 balun transformer at the feedpoint in order to balance currents and keep the pattern according to textbook predictions.

Center insulators

It was once common (but poor) practice to strip a few centimeters of coaxial cable, part the braid and center conductor, and connect them to each side of the dipole. We could then wonder why the darn thing fell down in the next wind storm. Even if you elect to not use the balun transformer, a ready-made center insulator is a must. Figure 28-4A shows a common form of center insulator for use with dipoles and other wire antennas. There is an SO-239 UHF coaxial connector on the bottom to accept the feedline and two eyebolts mounted with solder connectors for the antenna elements on the sidewalls. At the top is a small eyebolt that is used to strain-relieve the system, or to hang it from a center support (as when inverted-V dipoles are built).

A larger form of center insulator is shown in Fig. 28-4B. The enlarged down section indicates that this device contains either a 4:1 or 1:1 impedance ratio balun



28-3 Dipole antenna.



28-4A Center insulator.

transformer. The 1:1 size is recommended for ordinary dipoles, whereas a 4:1 unit is used for folded dipoles and certain other wire antennas.

Connections to the device, whether straight center insulator or balun form, are shown in Fig. 28-5. For simplicity, only one side is shown (the other side is identical). The elements (*B* in Fig. 28-3) typically are made of no. 12 or no. 14 antenna wire. The best wire is stranded and is copper-clad steel core wire (Copperweld).

The end of the antenna wire is passed through the eyebolt and then doubled back and twisted onto itself 7 to 10 times. The remainder of the wire is then soldered to the terminal. Some people prefer to use a separate "pigtail" wire to connect the antenna element to the solder terminal. It is fastened to the antenna element wire between the 7- to 10-turn twist and the eyebolt.

When preparing the center connector/balun, it is good practice to use steel wool or sandpaper on the solder lug to remove oxidation. Oxidation makes it hard to solder and forces you to use too much heat to make a good connection. Also, be sure to have a large pair of pliers to crimp the wings of the solder lugs onto the wire.

Solder assists in making a good connection at the solder lugs, but the crimp should be good enough to do the job. The solder then provides corrosion protection. Also, tin the 7- to 10-turn twist section with solder. This does not increase the strength or provide better electrical connection—it is protection against the corrosion that will occur with copper wires.

Note Use only resin-core solder for antennas! Typical solder is 50/50 or 60/40 lead/tin ratio and may be labeled "radio-TV" or "electronic" or something similar. Plumber's solder is acid core and will destroy your antenna within a short time after it is erected.



28-4B Balun/center insulator.

Figure 28-6 shows the dipole installed. The ends of the two wire elements are connected to end insulators, which are in turn supported by rope to a vertical support (e.g., mast, tree, roof line of the house, etc.). Although shown nice and straight here, the actual installation will droop a bit in the center due to the weights of the center insulator or balun, the coaxial cable, and the wire itself. Gravity!

Note that the coaxial cable is formed into a 15- to 25-cm loop just below the coaxial connector to the center insulator or balun. This forms a species of RF choke to keep currents from flowing in the outer shield and improves the pattern. The coaxial cable loop is bound together with black electrician's tape or some similar adhesive medium and then fastened to the top eyelet with stout string or fishing line for strain relief.



28-5 Center insulator/balun connections.

Support rope

The support rope selected should be large enough to provide support but small enough to fit through the holes of the end insulators. Cotton rope is singularly unsuited to this task because it weathers poorly and will rot through in short order. Nylon rope, sail rope, and parachute rope are perhaps the best types, especially if a particular lot has been tested for high tensile strength. Remember, the wind loading of your antenna, even a short dipole, can be tremendous!

End insulators

End insulators come in a large variety of shapes and sizes (I have even seen one chap use old toothbrushes, suitably drilled, of course). The main categories, however, are represented in Fig. 28-7. The version in Fig. 28-7A is the standard form, whereas that in Fig. 28-7B is an “egg” insulator. The egg insulator has two sets of wire grooves and through-holes that are orthogonal to each other (only one set is shown). Wire passes through one hold and set of grooves, and the supporting rope passes through the other hole/groove set.

The standard form shown in Fig. 28-7A has a number of grooves or ridges cut along the body. These grooves are intended to lengthen the electrical path between


END INSULATOR
ROPE TO SUPPORT
WIRE SPLICES
STOUT STRING
COAX LOOP
(15-25 CM DIAM.)
COAXIAL CABLE TO RECEIVER
OR TRANSMITTER
1:1 BALUN OR
CENTER INSULATOR

28-6 Dipole and wire antenna installation.

ends of the insulator and therefore serve to reduce losses in the insulator. Typical materials used to construct insulators include ceramic, glass, nylon, and plastics.

Figure 28-8 shows the connections to the end insulator. The electrical connections to the antenna wire are the same as for the center insulator. The only proviso here is that for transmitting antennas, it is wise not to leave any sharp points sticking up. The end of the dipole is at high RF voltages, so sharp points tend to cause corona sparking. Cut off any extraneous leads that form sharp points, and then smooth the whole affair down with tinning (i.e., solder).

The rope is treated in a similar manner as the wire, but it must be knotted in some manner that tends to pull together as the rope is pulled into tension. Some people use the "hangman's knot," but this seems a bit excessive.

Strain relief of the antenna

Figure 28-9 shows a method of strain relief for the center insulator or balun. This point is at the highest tension and probably is the weakest because of the number of


A

B

28-7 End insulators.



28-8 Connections to end insulators.



28-9 Strain relieving the center insulator or balun.

connections and things that can break. A suspension rope is run between the antenna's vertical supports, parallel to the antenna wire. It is tied to the top eyelet on the center insulator or balun by a short bit of rope about 15 to 20 cm long.

Special case of the folded dipole

The folded dipole (Fig. 28-10) is a special case of the half-wavelength horizontal dipole. It consists of two close-spaced conductors shorted together on the extreme ends. One of the conductors is split in the center and used as the feedpoint. The feedpoint impedance at resonance is around 280 Ω, so it makes a good match to 300-Ω television antenna twin lead. The usual practice is to build the entire antenna and feedline out of twin lead. An alternative (as shown in Fig. 28-10) is to provide a 4:1 balun transformer at the feedpoint to match 75-Ω coaxial cable. Despite the fact that 300-Ω TV twin lead is disappearing from the market, the folded dipole maintains a certain following among SWLs and hams.

The problem is how to install the antenna such that the terribly weak 300-Ω twin lead wires do not break at the slightest provocation. Figure 28-11 shows a solution used by one fellow (admittedly a fine worker in plastics and other materials). He fashioned a center insulator and the end insulators from a piece of strong Lucite material.

The 300-Ω TV twin lead is prepared as shown in Fig. 28-11A. The antenna element is notched in the center (break along the bottom) for about 1 to 1.5 cm. A hand punch is used to place two or three holes in the center insulation on either side of the break. Either a large-size leather punch or a paper punch can be used to make


A
B
B
4:1
BALUN
75-OHM
COAX

28-10 Folded dipole.


SIDE VIEW
FILL
B
C
TWIN-LEAD PREPARED BEFORE ASSEMBLY
A

28-11 Center insulator for ribbon cable folded dipole: (A) cable preparation, (B) front/back view, (C) edge view.

the holes. In a test, I was able to make the required holes using a hand-operated paper punch, but it required a large force (and turned my hand temporarily purple!).

The center insulator is shown in Fig. 28-11B. It is made from a piece of strong plastic, Lucite, or other insulating material. Two identical sections, front and back, are needed. A number of 5-mm holes are drilled into both pieces at the points shown to clamp the twin lead. A pair of solder lugs is provided to make connections between the antenna element and the transmission line (either twin lead or leads from a balun). The screws and nuts used to fasten the two halves of the insulator are made of nylon to prevent interaction with the antenna.

A side view is shown in Fig. 28-11C. Note that the twin lead causes a gap that can catch water. It also makes it possible to break one or both insulators by overtightening the nuts. In order to prevent this, a gasket of similar material is glued into the space as filler. The gasket material should be about as thick as the twin lead.

If you opt for a balun transformer, then it can be wired to the downleg of the tee insulator using the holes that normally would clamp the twin-lead transmission line.

An end insulator for twin-lead antennas is shown in Fig. 28-12. It is constructed in a similar manner to the center insulator. Two scenarios are possible. The first, and that used in a test antenna, is to make the clamping fixture from metal such as 3- to 6-mm brass or copper stock. The ends of the antenna wires are shorted, so this is not a great problem.

An end insulator is then used with a rope in the normal manner. A chain-link section is used to fasten the clamping fixture and the end insulator. I attempted this with a nylon chain link, about 1.5 × 2.5 in, from a do-it-yourself hardware store. It was only with a bit of difficulty that the ends were pulled apart, slipped into both the end insulator and the clamping fixture, and then reclosed.

The second approach is to make the clamping fixture out of the same material as the center insulator. It then becomes the end insulator, so the other end insulator and that cursed chain link can be ignored. If you opt for this approach, it is a good idea to smooth and polish the rope hole on the clamping fixture to prevent chaffing of the rope.

Masts and other supports for wire antennas

The end supports of the antenna can be anything that provides height: a mast, a tree, or the roof line of a building. Figure 28-13 shows the use of a mast, but either of the other forms of support could be used as well. The support rope is not tied off at the



28-12 Folded dipole end insulator.



28-13 Mounting mast schemes.

top, as is true in all too many installations, but rather is brought down to ground level. This approach facilitates raising and lowering the antenna for maintenance and tuning. Be sure to provide enough "dead slack" to make lowering the antenna feasible.

The antenna support rope is connected to a spring on one end and a counterweight on the other end. The spring should be stout enough so that it is only slightly extended when the full weight of the antenna places it in tension. I have used doorsprings for this task, but only the stoutest varieties.

The counterweight should be just enough to balance the weight of the antenna and keep it not quite taut. As wind moves the antenna up and down, the counterweight raises and lowers, thereby reducing the chances of straining the antenna wires to their limit. Any number of counterweights can be used. I have seen a number of types: drapery cord weights, a small bucket of rocks, a gaggle of fishing weights, and (in one case) a burned-out automobile starter motor (the mounting hole on the front boss of the motor was ideal for accepting the rope).

Figures 28-14A and 28-14B show two methods for making the connections at the top of the mast. Although egg insulators are shown here for the sake of fairness (the alternate form was shown earlier), either form can be used. A pulley is mounted on the top of the mast with a link section and a stout eyebolt that passes through the mount. In the case of a tree, I have used a steel band of the type used to mount TV antennas to house chimneys. By making the down rope a closed loop, you gain the



28-14 Two alternate pulley systems for wire antenna mounting.

ability to raise and lower the antenna. But do not let a loose end slip, or you will be chasing the rope up the mast as it slips through the pulley.

Pulleys work nicely, but they are mechanical contraptions that tend to fail occasionally. When they fail, the rope gets stuck. Pulleys also can corrode rather badly, with the same end result. All in all, a pulley is not the best solution for most people.

Figure 28-15 shows a better way. In this approach, a U-bolt is fastened to the top of the support mast. If the U-bolt is made of brass, then all the better, for it will not corrode. The rope can be passed through the U-bolt as in the pulley system but without the mechanical failure problem. Be sure to install the U-bolt all the way up to the threads so that the rope will not chafe against them.

The method shown in Fig. 28-16 can only be used by a horse lover! This method uses a brass stirrup in place of the U-bolt. If you have switched to cars or trucks and no longer need your horse stirrups, then perhaps this is a viable means of attaching the support rope to the top of the mast.



28-15 U-bolt end mounting.



28-16 Stirrup end mounting.

Installing vertical antennas

Despite continuous (and mostly untrue) stories of very poor performance, the four- or five-band commercially manufactured trap vertical antenna remains one of the most popular amateur radio "antlers" in the HF bands. They are economical compared with directional rotating beam antennas, easy to erect, and do not have to occupy a lot of real estate (the "footprint" of the vertical can be very small, especially if you bury the radials). Unfortunately, a misinstalled vertical is both dangerous and a very poor performer. This section covers both problems in order to give you a good chance of success.

Electrical installation

Figure 28-17 shows the usual form of multiband trap vertical antenna. Each trap (*TR1–TR3*) is a parallel resonant LC tank circuit that blocks a certain frequency but passes all others. In Fig. 28-17, *TR1* is the 10-m trap, *TR2* is the 15-m trap, and *TR3* is the 20-m trap. No 40-m trap is needed because the antenna resonates the entire length of the tubing on 40 m. Each section (except perhaps the 10-m section) is actually a little shorter than might be expected from the standard quarter-wavelength formulas. This is because the traps tend to act inductively and so lessen the length required to resonate on any given band.

The vertical antenna manufacturer might give suggested lengths for the various segments between traps. Do not make the mistake of assuming that these are absolute numbers. They are only recommended starting points, even though the literature packed with the antenna may suggest otherwise. Loosely (meaning do not tighten the clamps too much) but safely install the antenna, and then adjust each segment for resonance. Start with the 10-m band, and then work each lower-frequency band in succession: 10-15-20-40, etc. After each lower band is adjusted, recheck the higher bands to make sure that nothing has shifted, because there might be a little interaction between bands. Once the antenna is properly resonant, tighten the clamps, and make the final installation. I know this is a pain in the neck, and means putting the antenna up and taking it down a couple of times, but it pays dividends in the end. I failed to do this once and found that the 15-m band was useless; it resonated at 19.2 MHz.

Radials make or break a vertical antenna; they form the ground plane for the antenna. AM broadcast stations typically use vertical antennas and must have 120 radials for the ground plane. Antenna reference books usually contain a graph plotted to show the effectiveness of radials and demonstrate a decreasing return on investment after about 32 radials. For amateur work, I recommend not less than 2 radials per band, and preferably 4, arranged so that they are equally spaced around the antenna. If you cannot space them correctly, never fear; they will work anyway. On a four-band antenna, this means 16 radials, which really is not a lot. Of course, the general rule is that the more radials, the better is the antenna, at least up to the point where diminishing returns are realized.

The radials are made of no. 14 wire and must be a quarter wavelength ($246/F_{\mathrm{MHz}}$). Figure 28-18 shows how to mount the radials on a mast-mounted (or roof-mounted) installation, and Fig. 28-19 shows radials in a ground-mounted situa-



28-17 Mounting commercial trap vertical.

tion. I do not recommend radials on the surface for ground-mounted antennas. It is too easy for a guest or even a trespasser to trip over the radials, and this could land you in court. Wire radials can be buried using a spade tip to cut a 3- to 4-in slit, and they even make for a better ground.

Ground mounting verticals and masts

In the preceding section, the essential assumption was that the antenna is mounted above ground, on a mast or other support. In this section you will take a look at the methods of ground mounting the antenna or its mast. The same mast ideas are also useful for erecting supports for dipoles and other wire antennas.

Figure 28-20 shows a standard chain-link fence post used as a support for either a vertical antenna or a mast (which could be metal, PVC, or wood). The typical fence post is 1.25 to 2.00 in outside diameter and made of thick-wall galvanized steel. Thus such a pipe makes a tough installation. Some authorities believe that the pipe will last longer if painted its entire length (especially the underground portion) with a rust-inhibiting paint such as Rustoleum.


Coax to
transmitter
Radials
Insulator
Rope
Insulator
Rope
Insulator
Rope
Insulator
Rope

28-18 Feeding the mast-mounted vertical antenna.


3 to 4 in. or more
Coax
to XMTR
Ground level
Buried radials

28-19 Feeding the ground-mounted vertical antenna.

The beauty of the fence post as an antenna support is that it is relatively easy to install, and supplies are obtained easily from hardware stores. The post is mounted in a concrete plug set at depth *D* in the ground (see again Fig. 28-20). The depth *D* is a function of local climate and local building codes. In the absence of local regulations to the contrary, make the hole at least 24 in deep (or more). The depth is determined by the 100-year depth of the frost line in your area, a figure well familiar to local building experts. Keep in mind, however, that shallower depths may be legal for



28-20 Fence post mounting.

fence posts, but installation of a vertical antenna (or mast) on top of the fence post changes the mechanical situation considerably.

The hole can be dug with a post-hole digger tool or an earth-auger-bit tool. The latter often can be rented in either gasoline engine, electrical motor, or manual versions from tool rental stores.

Once the hole is dug, place about 4 in (or local requirement) of gravel at the bottom of the hole. This gravel can be bought in bags from hardware stores for small jobs. The post is installed at this point and made plumb (i.e., it is made to sit vertical in the hole). Gravel can be used to force the post to remain upright as the job is finished. On top of the gravel is a concrete plug that fills the hole to at least 4 in below the surface. The rest of the hole is backfilled with dirt, unless you want the plug to extend all the way to the surface. Do not put anything on top of the post for at least 4 days or whatever period of time the concrete manufacturer recommends. Concrete needs time to cure, and 4 to 7 days seems to be the recommended period of time. It is probably a good idea to install the post one weekend and then complete the antenna installation the following weekend.

Chain-link fence posts tend to be about 4 ft high, and this is sufficient for installation of masts for inverted-V and dipole support. However, for vertical installation, make the height *H* of the post about 18 in (otherwise, the antenna tries to act differently from the instructions).

If the antenna is a standard vertical with the usual form of offset base (as shown in Fig. 28-20), then use either the mounting brackets that come with the antenna or U-bolts fastened around the fence post. Never use a single mounting point; always use at least two-point mounting to prevent the antenna from pivoting and shearing off the mounting hardware.

Figure 28-21 shows how to mount a 2 × 4 mast to a fence post. Good-quality 2 × 4 lumber can be purchased in lengths up to 20 ft, although, 8-, 10-, 12-, and 16-ft lengths are the most commonly available (in my area, 16- and 20-ft lengths have to be bought at professional "contractor" lumberyards rather than those which serve homeowners). The 2 × 4 selected should be kiln-dried and pressure-treated. It also should be painted in order to minimize the effects of weathering on the mechanical integrity of the installation. Good-quality 2 × 4 lumber is relatively inexpensive, but



28-21 Making a mast mounted to a fence post.

the less costly material (which is only marginally less costly than the best) will warp and ruin the installation within 1 year.

The 2 × 4 is attached to the fence post using U-bolts. A 2 × 4 scrap is used as a wedge to take up the difference between the post and the mast. In some installations the U-bolt will go around the perimeter of the 2 × 4, whereas in others a pair of holes will be drilled in the 2 × 4 to admit the U-bolt arms. The U-bolt must be at least $^1/_4$-in no. 20 thread, and either a $^5/_{16}$-in bolt or a $^3/_8$-in bolt is highly recommend if the mast supports any significant weight. Some installers like to place a brick at the base of the 2 × 4. This support bears the static and dynamic loads (i.e., gravity and wind) that eventually would cause the mast to list because of the eccentric loading on the footer. The auxiliary purpose is to keep the butt end of the 2 × 4 off the ground and thereby prevent rot. Some additional mechanical stability might be afforded by replacing the brick with a cinder block that is filled with concrete. Another approach is to install a pressure-treated 4 × 4 of the sort used to support decks (Fig. 28-22). Hardware stores and lumber yards sell the specially treated 4 × 4 posts and the concrete for the footers. These footers are dropped onto a gravel bed at the bottom of a hole (see the preceding section for a discussion of how deep the hole must be). A typical deck footer has a plastic or heavy-duty metal mount to support the 4 × 4. After the footer and mount are installed, the hole is backfilled with soil. Some people prefer to backfill, at least to a point above the mount, with builder's gravel (of the same sort as used beneath the concrete footer), or concrete can be used for maximum stability.

Installing towers

Antenna towers are used extensively in amateur and commercial radio communications systems for a very obvious reason: Antennas tend to work better "at altitude" than on the ground. Amateur operators tend to install 30- to 100-ft towers, although the 40- and 50-ft models probably predominate for practical (and in some areas



28-22 A 4 × 4 antenna support.

legal) reasons. Local laws vary considerably, from one area to another. Be sure to consult the bureaucracy before erecting a tower.

In my own area, a 30-ft tower that is physically attached to a two-story house does not need a permit or inspection (but must be constructed according to certain regulations), although anything mounted away from the house (or at a height greater than 30 ft, if attached to the house) requires a permit and the usual mechanical inspection. The law requires that an inspection be performed when the hole for the footing is completed and 4 in of gravel is on the bottom. The inspector will take a yardstick and measure both the depth of the hole and the depth of the gravel. A final inspection is performed when the antenna is installed. Prior to all this mess, a permit must be obtained (which means drawings submitted).

Several different types of towers are used by amateurs. Some are square-base designs, and others are triangular-base designs. At least one commercial model is a round pipe that has a rotator at the base. In this model, the entire tower turns when the antenna is rotated. Several tower configurations are seen commonly. Figure 28-23 shows the fixed form of tower. This type of tower costs the least, and a case can be



28-23 Antenna tower on hinged baseplate.

made for it also being the most stable. It is made of 10-ft sections and an 8- to 12-ft top section that contains the thrust bearing for the antenna mast and rotator mounting platform. Some fixed towers are self-supporting up to a point, but the use of guy wires is always recommended unless a firm mounting point (against the side of a building, for example) is provided about 18 ft above the surface. The fixed tower can be made to tilt over at the base by using a hinged baseplate on the mounting pedestal.

The tilt-over tower is shown in Fig. 28-24. This type of tower uses the same sort of construction as the fixed model but is hinged at a point between one-third and one-half the total height. A winch at the base drives a steel wire that is used to raise or lower the tower between fully extended and fold-over positions.

Still another configuration is shown in Fig. 28-25. This type of tower is the slip-up variety. A wide base section supports a smaller movable upper section. A winch is used to lift the upper section into its fully extended position. Typical examples will raise from a low position of 20 ft, to a height of 40 ft or so when fully extended (or 20/50 ft). When the tower is fully extended, it is locked into place at the bottom of the upper section with steel bolts. A lot of shear force is applied to these bolts, so it is wise to use several very hard stainless steel bolts for the lockdown.

There is a serious danger inherent in the design of the slip-up tower: the guillotine effect. If the upper section comes loose while you are working on it, it will come plummeting down the shaft formed by the lower section and shear off any arms, legs, or other body parts that get in the way. Whenever you work on this form of tower, use steel fence posts (or similar pieces of metal) as a safety measure (Fig. 28-26); at least two should be used, and both should be attached securely at both ends with



28-24 Fold-over tower.



28-25 Slip-up tower.

rope. The purpose of the rope is to prevent the safety pipes from working loose and falling out. These pipes are used in addition to, not instead of, the normal bolt fasteners that keep the antenna tower erect.

The antenna tower, regardless of its configuration, is typically installed on a buried pedestal made of concrete (Fig. 28-27). The construction must follow local laws, but there are some general considerations to keep in mind. The surface area of the pedestal is 242 to 362 in. The top surface is fitted with either a fixed or hinged baseplate (which must be installed before the concrete sets). The depth of the


Steel safety pipes
IN ADDITION TO
normal fasteners

28-26 Safety precaution.


Hinged or
fixed
baseplate
6 Inches
Concrete
pedestal
D
Gravel
4 Inches

28-27 Ground pedestal.

pedestal and the depth of the gravel base tend to reflect the local frost line. Regardless of how general local law is, good advice is to make the pedestal at least 28 in deep—even if local law permits less.

Raising the tower can be accomplished by either of two methods, although, in my opinion, only one of them is safe. Figure 28-28 shows a method by which the tower is laid out on the ground and then raised with a heavy rope over a high support (such as the peak of the house roof). This method is dangerous unless certain precautions are taken. For example, a support must be placed beneath the antenna as it is raised. This requirement means that a constantly increasing height of the tower demands a constantly increasing lower support.

The end-over-end method of raising a tower is shown in Fig. 28-29. A "gin pole" is required for this job. The gin pole is a length of pipe fitted with a pulley at the top and a pair of clamps at the bottom. The gin pole is clamped onto the top end of the highest section so that it can be used to raise the next 10-ft section into place, where it can be bolted down. The gin pole is then raised to the top of the newly installed section, where the operation is repeated again. The end-over-end method is preferred by tower manufacturers and is the method recommended by most of them.

The antenna tower will be most stable if guy wires are installed at appropriate places determined by the tower manufacturer. Although many people are inclined to install towers "free standing" and some towers are advertised as such, it is always good practice to use guy wires attached to at least one point (or more, for tall towers). Use at least four guy wires on a square tower or three on a triangle tower (one in each direction). Figure 28-30 shows two methods for securing the guy wires to the ground. One approach is to bury a heavy concrete or metal "deadman" weight underground. Alternatively, use at least one 4- to 6-ft pipe (1 to 1.5-in in diameter) buried up to a length of 12 to 24 in (18 in is shown in Fig. 28-30).

Note It is absolutely essential to use safety belts when climbing a tower. Use two belts that are completely independent of each other so that no "single-point failure" can eliminate the belt's function. Always keep one belt fastened to the tower; when climbing, unhook one belt and move it up on the tower, and then disconnect the other only when the first is reattached. Be sure to inspect the belts prior to use. Leather and metal wear out and break, and you do not want to find that failure at 50 ft up. Also, do not buy cheap belts.



28-28 Dangerous method for erecting tower.


Next section
Gin pole

28-29 Proper tower installation using gin pole.


Guy wire
Strain relief
Turnbuckle
Buried
"dead man"
Guy wire
Turnbuckle
Strain relief
18
Inches
1 to 1.5 Inch
steel pipes
4 to 6 feet long

28-30 Ground stakes for guy wires.

29
CHAPTER

Grounding the antenna: What is a good ground?

THE SUCCESS OR FAILURE OF A RADIO ANTENNA SYSTEM OFTEN (PERHAPS USUALLY) hangs on whether or not it has a good RF ground. Poor grounds cause most antennas to operate at less than best efficiency. In fact, it is possible to burn up between 50 and 90 percent of your RF power heating the ground losses under the antenna, instead of propagating into the air. Ground resistances can vary from very low values of 5 Ω, up to more than 100 Ω (5 to 30 Ω is a frequently quoted range). RF power is dissipated in the ground resistance. The factors that affect the ground resistance include the conductivity of the ground, its composition, and the water content. The ideal ground depth is rarely right on the surface, and depending on local water table level might be a couple meters or so below the surface.

It is common practice among some amateur radio operators to use the building electrical ground wiring for the RF antenna ground of their station. Neglecting to install an outdoor ground that will properly do the job, they opt instead for a single connection to the grounded “third wire” in a nearby electrical outlet. Besides being dangerous to work with, unless you know what you are doing, this is also a very poor RF ground. It is too long for even the low RF bands, and radiates RF around the house in large quantity. Stations that use the household electrical wiring as the radio ground tend to cause TV interference, broadcast interference, and other electromagnetic interference both in their own building and in nearby buildings.

Fortunately, there are some fixes that will help your situation. We can reduce the ground resistance by either altering the composition of the earth surrounding the ground point, or by using a large surface area conductor as the ground point.

Figure 29-1 shows the traditional ground rod used on small radio stations, including amateur stations. Use either a copper (or copper-clad steel) rod at least 6 ft long (8 ft preferred). Electrical supply houses, as well as amateur radio and communications equipment suppliers, also sell these ground rods. Do not use the nonclad

Copyright 2001 - the McGraw-Hill Companies



29-1 Single ground rod works—almost.

steel types sold by some electrical supply houses. They are usable by electricians when making a service entrance ground on your home or workplace, but RF applications require the low skin resistance of the copper-clad variety. The rod need not be all copper, because of skin effect forcing the RF current to flow only on the outer surface of the rod. Try to use an 8-ft rod if at all possible, because it will work better than the shorter kind. Do not bother with the small TV-antenna 4-ft ground rods; they are next to useless for HF radio stations. Drive the ground rod into the earth until only 6 in or so remains above the surface. Connect a ground wire from your station to the ground rod.

The ground wire should be as short as possible. Furthermore, it should be a low-inductance conductor. Use either heavy braid (or the outer conductor stripped from RG-8 or RG-11 coaxial cable) or sheet copper. You can buy rolls of sheet copper from metal distributors in widths from 4 in up to about 18 in. Some amateurs prefer to use 7-in-wide foil that is rated at a weight of 1 lb/linear ft. Sweat-solder the ground wire to the rod. You can get away with using mechanical connections like the electricians use, but you will eventually have to service the installation when corrosion takes its toll. I prefer to use soldered connections, and then cover the joint with either petroleum jelly or acrylic spray lacquer.

Another alternative is to use a copper plumbing pipe as the ground rod. The pipe can be purchased in 8-ft through 16-ft lengths from plumbing supply shops or hardware stores. The pipe selected should be ¾ in or larger. Some people report using up to 2-in pipe for this application. The surface area of the hollow pipe is greater than that of a solid rod of the same diameter. Because of certain current flow geometries in the system, however, the ground resistance is not half the resistance of a rod of the same diameter, but is nonetheless lower.

Driving a long pipe into the ground is not easily done. Unlike the copper-clad steel rod, the pipe has no compression strength and will deform when you hit it with a hammer or other driving tool. To overcome this problem (see Fig. 29-2) you can use a garden hose as a water drill. Sweat solder a tee joint on the top end of the pipe, and then sweat-solder a faucet fitting that matches the garden hose end on one end of the tee joint. Cap off the other port of the tee joint. Use the tee



29-2 Hose method of installing ground pipe.

joint as a handle to drive the pipe into the ground. When water pressure is applied, the pipe will sink into the ground as you apply a downward pressure on the tee handle. In some cases, the pipe will slip into the ground easily, requiring only a few minutes. In other cases, where the soil is hard or has a heavy clay content, it will take considerably greater effort and more time. When you finish the task, turn off the water and remove the garden hose. Some people also recommend unsoldering and removing the tee joint.

Altering soil conductivity

The conductivity of the soil determines how well, or how poorly, it conducts electrical current (Table 29-1). Moist soil over a brackish water dome conducts best (southern swamps make better radio station locations), and the sand of the western deserts makes the worst conductor. Figure 29-3 shows a method for reducing the soil electrical resistance by treating with one of two chemicals: copper sulfate or common rock salt. The rock salt is one of several salt materials used for snow and ice melting in snow-prone areas of the country. If you cannot locate rock salt in a hardware store, then look for a store that sells ice-cream-making supplies. Rock salt is a principal ingredient in the process (but not the product).

Table 29-1. Sample soil conductivity values

Type of soil	Dielectric constant	Conductivity (siemens /meter)	Relative quality
Salt water	81	5	Best
Fresh water	80	0.001	Very poor
Pastoral hills	14–20	0.03–0.01	Very good
Marshy, wooded	12	0.0075	Average/poor
Sandy	10	0.002	Poor
Cities	3–5	0.001	Very poor



29-3A Ground rod with “improved” ground.



29-3B Trenching pattern.

Figures 29-3A and 29-3B show side and top views (respectively) of a slit trench method of applying the chemical treatment. Dig a 6- to 10-in-deep trench, about 12 to 24 in from the ground rod. Fill that trench with a 4- or 5-in layer of rock salt or copper sulfate. Cover the remaining depth with soil removed when you dug the trench. Water the trench well for about 15 minutes. The treatment will need to be repeated every 12 to 36 months, depending upon local rainfall and soil composition.

Figure 29-3C shows an alternative method: the salt pipe. Use either copper or PVC plumbing pipe, up to 4 in diameter (although 2 to 3 in is easier to work). The overall length of the pipe should be at least 18 to 24 in, although longer is useful.



29-3C Slow release ground treatment pipe.

Drill a large number of small holes in the pipe (no hole over ⅜ in), sparing only the end that will be above the surface. Fill with rock salt or copper sulfate and cap off both ends.

Install several salt pipes around the ground rod. Installation is best accomplished with a fence posthole digger. Drop the salt pipe into the hole and backfill with water. Remove the top endcap and hose down for about 15 minutes. Refill the pipe occasionally to account for the salt leaching out.

Multiple ground rods

The key to a low-resistance ground is the surface area in contact with soil. One means for gaining surface area, and thereby reducing ground resistance, is to use multiple ground rods. Although multiple 4-ft rods are better than a single 4-ft ground rod, the use of 6- or 8-ft rods is recommended even in cases where multiple rods are used.

Figure 29-4A shows the use of three ground rods in the same system. The 8-ft rods are placed 12 to 18 in apart for low- and medium-power levels, and perhaps 30 in for higher amateur power levels. An electrical connection is made between the rods on the surface using either copper stripping or copper braid. The connections are sweat-soldered in the manner described above, with the feedpoint at the center rod.

Figure 29-4B shows a more complex system with a larger number of rods laid out in an array. The rods are arrayed about 24 in apart. As in the previous case, the rods are electrically connected (by braid or foil) on the surface. Again, connection to the system is made from the rod at the geometric center of the array.

Radials/counterpoise grounds

The effectiveness of the ground system is enhanced substantially by the use of radials either above ground or buried under the surface. Figure 29-5 shows a vertical



29-4A Multiple ground rod system.



29-4B Connection scheme.

antenna with three different forms of radials: aboveground, subsurface, and ground rod. It is not unreasonable to use both radials and a ground rod. Note (from Chap. 7) that vertical antennas are relatively ineffective unless provided with a good ground system, and for most installations that requirement is best met through a system of ground radials.

An effective system of radials requires a large number of radials. Although as few as two quarter-wavelength resonant radials will provide an improvement, the best performance is to use more. Broadcasters in the AM band (550 to 1640 kHz) are advised to use 120 half-wavelength radials. Installing more than 120 radials is both expensive and time-consuming, but does not provide any substantial improvement. For amateur and small commercial stations, use a minimum of 16 quarter-wavelength radials.

Above ground, the use of insulated wire is recommended, but not required. Below ground, noninsulated wire is preferred. Although some sources claim that any



29-5 Combining ground rod and buried radials.

size wire from no. 26 up to no. 10 can be used, it is best to use larger sizes in that range (i.e., no. 14 through no. 10). Either solid or stranded wire can be used.

The layout for a system of radials in a vertical antenna system is depicted in a view from above in Fig. 29-6. Here, the radials are laid out in a uniform pattern around the antenna element. This coverage provides both the lowest resistance and the best radiation pattern for the antenna. Solder all radials together at a common point, which might be the ground or mounting rod used to support the vertical antenna.

Station grounding

It does no good to provide a topflight ground system, such as those shown earlier in this chapter, if the connection between the station equipment and the ground system is substandard. Figure 29-7 shows a method used by the author to good effect. On the back of the operating position is a sheet of copper, 7 in wide, running the length of the equipment platform. This form of copper, in the 1-lb/sq ft weight, is used on older houses for roofing flashing. Each piece of equipment is connected to the ground sheet through a short length of braid harvested from RG-8 or RG-11 coaxial cable shield. RF accessories, such as the low-pass TV interference filter (if used—it should be) are mounted directly to the copper sheet. In one installation, the



29-6 Radial pattern.

author was able to drop the copper sheet down from the table to connect directly to the ground system outside the building. The run was less than 40 in. But in other cases, a short length of braid wire will be more practical.

Tuning the ground wire

An alternative that some operators use is the ground wire tuner. These instruments insert an inductor or capacitor (or a *LC* network) in series with the ground line. You


Equipment
Tuner
Amplifier
XMTR
Low-pass filter
Spout filter
7-in- wide
1-lb/sq ft
copper sheet
To
ground rod

29-7 Ground system inside shack.

adjust the ground line tuner for maximum ground current at the operating frequency. MFJ Electronics, Inc., Mississippi State, MS, makes one of these devices.

Conclusion

A high-quality, low-resistance ground might seem costly to install, but in reality it pays rich dividends in the functioning of your antenna. Don't overlook the quality of the ground, or you might be in the position of being penny wise and pound foolish.

This page intentionally left blank

Index

Copyright 2001 - the McGraw-Hill Companies

This page intentionally left blank

Note: boldface numbers indicate illustrations; italic *t* indicates a table.

A

absorbed power (P_a), transmission lines, 113–114
absorption of microwaves, **38**
Adcock antennas, 446–447, **448, 449**
Adcock, F., 446
adjustable plunger or short-circuit termination, microwave waveguides and antennas, 388, **388**
adjustment techniques (*See* measurement and adjustment techniques)
admittance, 100, 105, 112–114
air core frame loops (“box” loops), 303–305, **304**
air-articulated line, 62–63, **63**
airborne radio, 30
Alexanderson alternators, 2
aluminum vs. copper radiators, in high–frequency dipoles and doublets, 154
AM radio, 47, 55
  Beverage or “wave” antenna in, 224–228, **226, 228, 229**
  vertically polarized HF antennas in, 186
  radio direction finding (RDF) antennas in, 439
AM/FM broadcast antenna tower, **4**
amateur radio, 2, 3, 29, 49, 55
  loop antennas, small receiver-type in, 302
  multiband and tunable-wire antennas in, 203
  vertically polarized HF antennas in, 176, 179, 186
ammeter, 530, **530**
amplifier, for loop antennas, small receiver-type, 313–316, **316**
amplitude modulation (AM), 2, 8, 29
angle of incidence, 16, **16**, 22
angle of radiation, 50, 214, 274, **274**
angle of reflection, 16, **16**, 75
angle of reflection coefficient, **103**, 106, 112
angle of transmission coefficient circle, Smith charts, **103**, 106
angled or bent dipole antenna, 236–237, **240**
antenna matching tuner, 281, **285**
antenna noise temperature, 417–420
antenna tuning unit (ATU) (*See also* tuning), 463–464, **464, 465**
  in (λ/2 large loop antennas, 287
  in high–frequency dipoles and doublets, 152, 172
  in longwires, 214
  in multiband and tunable-wire antennas, 210
antenna tuning unit (ATU) (*Cont.*):
  in vertically polarized HF antennas, 173
antinodes, 87
aperture and aperture (slot) coupling, waveguides and antennas, 390–393, **393**, 402–403
apex angle, rhombic beam longwire, 223
approximation, in high–frequency dipoles and doublets, 142–143
arcing, 233
Armstrong oscillator circuit, 313, **315**
array antennas:
  branch feed systems for, 409, **412**
  corporate feed systems for, 409, **412**
  flatplate array antennas, 411, 413, **414, 415**
  phase shifting in, 409, **412, 413**
  slot array antennas, 411–413, **413**
  solid-state array antennas in, 408–411
  Watson-Watt Adcock array antennas, 447–450, **449, 450**
astronomy (*See* radio astronomy antennas)
atmospheric layers and radio propagation, 14–16, **15**, 18, 40–43,**42**
atmospheric pressure vs. radio propagation, 25

attenuation, 9–10, 28, 32, 36, 82, 377
attic-installed antennas, 232–234, **233**
auroral propagation, 54
automatic load control (ALC), 515
azimuth aspect, high–frequency dipoles and doublets, 147

B
backlobes in microwave waveguides and antennas, 400, **400, 401**
backscatter, 52
balanced transmission line, in multiband and tunable-wire antennas, 208–209, **209**
  (*See also* baluns)
baluns:
  coaxial cable, 465, **466**
  in directional phased vertical antennas, 249
  in high–frequency dipoles and doublets, 155, 171, **171**
  in longwires, 171, **171**
  multi-impedance, 476, **477**
  in multiband and tunable-wire antennas, 208–209, **209**, 210
  strain relief for, 553–554, **554**
  tapped, 476, **477**
  in VHF/UHF transmitting/receiving antennas, 341–346, **342, 343**
bandwidth, 2
  in loop antennas, small transmitter-type, 320–321, 320
  in VHF/UHF transmitting/receiving antennas, 339
basic radio system, 515, **516**
battery chargers/battery packs, 126, 493–494, **494**
beam antennas:
  cubical quad beam antennas, 263–267, **264, 266, 267**
  inverted bobtail curtain (Thorne array) antenna, 267–269, **268, 269**
  quad beam VHF/UHF antenna, 356, 358, **359**
  VHF/UHF transmitting/receiving antennas, 349–352, **351, 352**
  Yagi antennas, 257–262, **259**, 265, 349–352, **351, 352**
beam antennas (*Cont.*):
  ZL-special beam antenna, 20-m, 262–263,**262**
beamwidth:
  microwave waveguides and antennas, 400, **400, 401**
  parabolic "dish" antennas, 407
bends in microwave waveguides and antennas, 388–390, **389, 390**
bent dipole antenna, 236–237, **240**
Beverage or "wave" antenna, 224–228, **226, 228, 229**
  grounding of, 227–228, **228**
  installation of, 228
  insulators in, 228
  maximum effective length (MEL) in, 227
  steerable notch Beverage antennas, 229, **229**
Beverage, H.H., 225
Binns, Jack, first maritime radio distress call, 1–2
bidirectionality of loopsticks in RDF antennas, 441
bisquare loop large antenna, 296–297, **297**
boundary conditions in microwave waveguides and antennas, 375–376
"bowtie" dipoles, 154, 155, **156, 361**, 362
"box" loops, 303–305
branch feed systems for array antennas, 409, **412**
bridges:
  impedance bridges, 519–521, **520, 521**
  noise bridge, 521–522, **521, 522, 523**
  RF noise bridge, 522–527, **521**
  RF power measurement using, 532, **532**
British Broadcasting Corporation (BBC), 54
broadband impedance matching, in high–frequency dipoles and doublets, 146
broadbanded dipoles, 154–157
broadside radiation pattern in directional phased vertical antennas, 246
Brooke, E.F., 209
burn or shock hazard through antennas, 191, 195, 215, 233, 276, 279
Byrne, John, 209

C
cable TV, 67
cage dipoles, 154, 155, 157, **157**
call signs, 3
capacitance, 126, 138, 526–527
  coaxial cable, 69
  loop antennas, small receiver-type, 317
  loop antennas, small transmitter-type, 321
  transmission lines, 64
capacitance tuning of loop antennas, small receiver-type, 307–309
capacitive (probe) coupling in microwave waveguides and antennas, 390–393, **392**
capacitive antennas, 126
capacitive reactance, 140
  in high–frequency dipoles and doublets, 143
  impedance matching and, 458
  using Smith charts, 100, **102**, 117
capacitors, 124–126, **124**
  in longwires, 215
  in loop antennas, small receiver-type, 304, 307–309
  in loop antennas, small transmitter-type, 320, 321
  in Yagi antennas, 261
cardioid radiation pattern of sense antenna in RDF antennas, 441, **442**
Cartesian coordinate system used in modeling software, 328, **329, 330**
Cassegrain feed for parabolic "dish" antennas, 408–409, **409**
cavity antennas, 404, **405**
center insulators, 548–550, **549, 550, 551**
characteristic impedance (Z_o), 516
  of Beverage antenna, 226
  of longwires, 223
  of microwave waveguides and antennas, 383–384
  of transmission line, 64–67, 89

charge, 124–126, **124**, 127, 131–137, **132, 133**
charged solar particles vs. propagation, 39
choke joints in microwave waveguides and antennas, 389, **390**
circular loop transmitter antenna, 323, **323**
Citizens' Band (CB) radio, 29, 48, 166, 176, 191, 341, 496
coaxial cable, 59, 61–62, **61, 62**
  baluns, 465, **466**
  capacitance in, 69
  characteristic impedance of, 66
  coaxial vertical scanner antenna using, 365–368, **367, 368**
  cutoff frequency (F_o) of, 69
  doping out, 437–438
  Faraday connection in, 318
  Faraday shield in, 318
  length of, calculating, 438
  loop antennas made using, 318, **318**
  losses in, 369, 438
  matching section of, quarter-wavelength coax, 292
  multiband and tunable-wire antennas and, 208
  testing, 437–438, **437, 438**
  velocity factor (V_F) of, 248
  vertical coax VHF/UHF antenna, 346–349, **347, 348**
coaxial vertical antennas, 191–194, **192, 193**
coaxial vertical scanner antenna, 365–368, **367, 368**
cochannel interference in loop antennas, small receiver-type, 302
coil-loaded mobile antenna, 480–481, **480**
collinear "Franklin" array antenna, 165–166, **166**
collinear vertical VHF/UHF antenna, 349, **350**
commercial operators, multiband and tunable-wire antennas, 203
complex admittance, Smith charts, 105
complex conjugates in impedance matching, 458
CONALRAD station frequencies, 439
conductance of transmission lines, 64
conductivity of soil, 27, 28*t*
cone of silence, 17
constant reactance circles, Smith charts, 100–105
constant resistance circles, Smith charts, 97–100, **99**
construction techniques (*See* installation and construction techniques)
constructive interference, 19
continuous loading in low-frequency operation antennas, **503**, 504–505, **506**
continuous wave (CW), 55
continuous wave trains, 7, **7**
coordinate system to denote dimensions in microwave waveguides and antennas, 376–377, **377**
coordinate system used in modeling software, 328, **329, 330**
copper plumbing pipes as ground rod, 574
copper sulfate to alter soil conductivity, 575–576
copperweld wire, 214
core material of transformers, 474
corner reflector antennas, 404, **405, 406**
corona effects, 233
corporate feed systems for array antennas, 409, **412**
cosmic radiation noise, 37
counterpoise grounds, 577–579, **579**
  in emergency operations antennas, 487–488, **488**
  in longwire, 170–172, **171**
coupling loop antennas, 306–307, **306**
coupling methods for microwave waveguides and antennas, 390–393
CQD/CQE distress calls, 2
critical angle, 48
critical frequency (F_c), 43, **44**
cross–polarization, 13
cubical quad beam antennas, 263–267, **264, 266, 267**, 421
current, 123, 126, 128, 129, 131–137, **132, 133**
current (*Cont.*):
  in directional phased vertical antennas, 248
  in (λ/2 large loop antennas, 289
  in high–frequency dipoles and doublets, 143–146, **143**
  in loop antennas, large designs, 299
  in loop antennas, small receiver-type, 299
  in loop antennas, small transmitter-type, 320
  standing waves of, 134, **135**, 136, **137**, 139
  in vertically polarized HF antennas, 173, **174**
  in loop antennas, small transmitter-type, 323
current standing wave ratio (ISWR), 88
current transformer wattmeter, 534–538, **535, 536, 537**
cutoff frequency (F_c):
  in microwave waveguides and antennas, 381–383
  in parabolic "dish" antennas, 406
cycles per second, 7

D

D layer of ionosphere, 41, **42**, 46, 51
D loop (1λ) large antenna, 290–293, **291**
damping, 6
dead zones, 23
Dellinger fade, 46–47
delta feed match systems:
  in low-frequency operation antennas, 507, **509**
  in VHF/UHF transmitting/receiving antennas, 343, **344**, 345
delta loop (1λ) large antenna, 290–293, **291**, **295**
delta-fed grounded vertical antenna, 200–201, **200**
demiquad loop large antenna, 293, **294**
depth wound loop antennas, small receiver-type, 303
design equations for loop antennas, small transmitter-type, 321–322
destructive interference, 19

diamond loop (1λ) large antenna, 290–293, **291**
dielectric constants, 138
dielectric loss, 369
dielectric properties of air, 29–30, **30**
diffraction, 16–17, **17**, 32–35
dip oscillator/dip meter, 527–529, **527, 528**
dipoles and doublets, 141–172, **142**
  aluminum vs. copper radiators in, 154
  angled or bent dipole, 236–237, **240**
  antenna tuning unit (ATU) for, 152, 172
  approximation of, 142–143
  attic installation of, 232–234, **233**
  azimuth aspect of, 147
  baluns in, 155, 171, **171**
  "bowtie" dipoles in, 154, 155, **156, 361**, 362
  broadband impedance matching in, 146
  broadbanded dipoles in, 154–157
  cage dipoles in, 154, 155, 157, **157**
  capacitive reactance in, 143
  center insulators, 548–550, **549, 550, 551**
  collinear "Franklin" array antenna in, 165–166, **166**
  counterpoise longwire in, 170–172, **171**
  current in, 143–146, **143**
  directivity in, 146–247
  double dipoles in, 160
  double extended Zepp antenna in, 164–165, **165**
  drooping dipole scanner antenna in, 363, **363**
  electrical vs. physical length of, 141, 142–143, 149–151, 160, **162**
  emergency operations antennas, 490, **490**
  end or egg insulators, 551–553, **553**
  feedpoint in, 143–146, 256–257, **257**
  floor flanges mounting hardware in, 256
  folded dipole, 154–155, **156**, 362, **362**, 554–556, **555, 556**
dipoles and doublets (*Cont.*):
  gain in, 146–147
  ground plane verticals in, 172
  height of antenna vs. radiation patterns in, 148–149, **148**
  height of antenna vs. resistance in, 145–146, **145**
  hidden and limited-space antennas, 232–234, **233**
  high-Q models of, 160
  high–frequency dipoles and doublets, 141–172, **142**
  impedance and impedance matching in, 143–146, 149, 151–152, 155, 237
  inductive reactance in, 143, 157, 158*t*, 159–160, **161**
  installation plan for, **552**
  insulators for, 141, 256, 548–550, **549, 550, 551**, 551–553, **553**
  inverted-vee dipole in, 152–153, **153**, 490–491, **491**
  isotropic radiation in, 146
  length of, 141, 142–143, 149–151, 160, 232, 255–257
  limited-space designs for, 236–244
  loading coils in, 157–160, **157**
  losses in, 143–146
  microwave waveguides and antennas and, elements of, 396–398, **397, 399**
  mounting of, 141, 233, 256
  multiband fan dipole in, 169–170, **170**
  off-center-fed full-wave doublet (OCFD) in, 163, **163**
  off-center-fed nonresonant sloper (OCFS), 164, **164**
  ohmic loss in, 143–146
  ominidirectionality of, 146
  phase reversal stubs in, 165
  Q-factor in, 160
  Q-sections in, 146
  radiation patterns of, 146–152, **147**
  radiation resistance in, 143–146
  radiators of, 141
  reactance in, 143
  resistance in, 143–146, **145**
  resonance in, 143, 149–151, **150**, 237
  rhombic inverted-vee antenna in, 169, **169**
dipoles and doublets (*Cont.*):
  right-angle flange mounting hardware in, 256
  RLC networks and, 143
  rotatable dipole antennas, 239, **242**, 255–257, **257**
  shortened coil-loaded dipoles in, 157–160, **158**
  shortwave reception antennas, 272, **273**, 274
  sloping ("sloper" or "slipole") dipole in, 153–154, **154, 155**, 236, **238**
  space diversity in, 160
  stacked dipoles in, 160–163, **162**
  stagger tuning of, 157
  standing waves and standing wave ratio (SWR) in, 144
  strain relief in, 553–554, **554**
  support ropes for, 551
  three-dimensional (ideal) radiation pattern of, 147–148, **147**
  tilted, center-fed, terminated, folded dipole (TCFTFD or T + 2 + FD, TTFD) in, 166–168
  transformers for, 146
  tunable dipoles in, 160
  tuning of, 149–152
  vee dipoles, 236, **239**
  vee-sloper antenna in, 168–169, **168**
  vertical dipole scanner antenna in, 364, **364, 365**
  vertical plane radiation pattern of, 148–149, **148**
  voltage in, 143–146, **143**
  voltage standing wave ratio (VSWR) in, 144, 146, 149–151, **150**, 160
  wavelength measurement of, 141–142
  wire antenna, basic design, 548, **548**
  Zepp antenna in, 164–165, **165**, 171
direct vs. reflected space waves, 17–19, **18**
direction of radio waves, 54
directional array, 360-degree phased, 250–254, **253**, 254*t*
directional beam antennas, 255–269

directional beam antennas (*Cont.*):
  cubical quad beam antennas, 263–267, **264, 266, 267**
  directivity of, 255
  effective radiated power (ERP) in, 255
  electromagnetic interference (EMI), 263
  feedpoints, 256–257, **257** 260–261, **261**, 263, **265**
  floor flanges mounting hardware in, 256
  gamma match feed system for, 260–261, **261**
  insulators, 256
  inverted bobtail curtain (Thorne array) antenna, 267–269, **268, 269**
  length of, 255–257, 259–260
  mounting of, 256
  quad loop antennas in, 263–267, **264, 266, 267**
  right-angle flange mounting hardware in, 256
  rotatable dipole as, 255–257, **257**
  Yagi antennas as, 257–262, **259**, 265
  Yagi-Uda antenna as, 258
  ZL-special beam antenna, 20-m, 262–263,**262**
directional discontinuity ring radiator (DDRR) antenna, 424–427, **426**, 427*t*
directional phased vertical antennas, 245–254
  broadside radiation pattern in, 246
  current in, 248
  directivity of, 246–250
  effective radiated power (ERP) in, 245–246
  feed phasing table for, 254*t*
  feedpoint in, 247–248, **247, 248**
  length of, variable lengths in, 248–249, **249**
  noise in, 245
  omnidirectionality of, 245
  phase-shifting circuit for, **252**
  phasing in, 246–250
  phasing switch in, 249–250, **252**
  radiation patterns in, 246–250, **246, 247**
  signal-to-noise ratio (SNR) in, 246
directional phased vertical antennas (*Cont.*):
  360-degree directional array, 250, **253**, 254*t*
  three-element, 250, **253**
  transformers in, 249–250, **250, 251**
  two-port phasing transformer for, 249–250, **250, 251**
  velocity factor (V_F) of coax in, 248
directional wire antenna, for shortwave reception, 281–286, **284**
directivity:
  in directional beam antennas, 255
  in directional phased vertical antennas, 246–250
  in high–frequency dipoles and doublets, 146–247
  in microwave waveguides and antennas, 395, 397, 398–403, **400**
  in shortwave reception antennas, 272
  in VHF/UHF transmitting/receiving antennas, 349
directivity gain (G_d) in microwave waveguides and antennas, 401–402
directors, Yagi antennas, 258–259
directrix, parabolic "dish" antennas, 404
discrete loading in low-frequency operation antennas, **503**, 504–505
dish antennas (*See* parabolic "dish" antennas)
distance between antennas, 28
distance calculation, for radio, 26–27, **26**
distress calls, 2
distributed capacitance, in loop antennas, small transmitter-type, 321
disturbance, ionospheric, 45–47
diurnal (*See* time–of–day variations)
diversity propagation/reception, 55–58, **57, 58**, 160
dominant mode in microwave waveguides and antennas, 376–377
Doppler antennas, 450–451, **451**
double dipoles, 160
double ducky direction finders (DDDF), 455–456, **455**
double extended Zepp antenna, 164–165, **165**
double vee longwire antennas, 223
double-shielded coaxial, 63, **63**
doublet antennas (*See* high–frequency dipoles and doublets)
drooping dipole scanner antenna, 363, **363**
drooping dipole multiband antennas, 205
"drooping radials," in vertically polarized HF antennas, 176, **177**
ducting, 29–31, **31**, 36
dummy loads, 385–388, **386**, 540–542, **540, 541, 542**
DXing using loop antennas, small receiver-type, 311–313

E

E layer of ionosphere, 41, **42**, 46
effective aperture (A_e), 11, 394, 407
effective Earth's radius factor (K factor), 23–27
effective height of antennas, 304
effective radiated power (ERP), 45
  in directional beam antennas, 255
  in directional phased vertical antennas, 245–246
  in microwave waveguides and antennas, 401
  in VHF/UHF transmitting/receiving antennas, 349
efficiency, in loop antennas, small transmitter-type, 321
E–field components, 27
electric field, 123, 124–126, **125**, 127, **128**
  in longwires, 219
  in microwave waveguides and antennas, 383, 395–396
  in vertically polarized HF antennas, 173
electrical installation, vertical antennas, 560–561
electrical vs. physical length, 137–140, **139**
  of high–frequency dipoles and doublets, 141–143, 149–151, 160, **162**

electrical vs. physical length (*Cont.*):
  impedance matching and, 470–471
  of longwires, 213–214, 217–219, 221
  of transmission line, 67–68
electromagnetic fields, 8–16, **9**, 123, 125–127
electromagnetic interference (EMI), 263
electromagnetic radiation vs. propagation, 39
electromagnetic waves, 5
electrostatic fields/discharge, in longwires, 219
eleven–year cycle of radio propagation, 46
EM Scientific, 331
emergency operations antennas, 485–493
  battery packs for, 493–494, **494**
  counterpoise ground plane for, 487–488, **488**
  dipoles in, 490, **490**
  grounding and ground systems for, 487–488
  increasing signal strength from portable/mobile stations for, 486
  inverted-vee dipole in, 490–491, **491**
  mobile antennas and, 486–487, **487**
  mounting of, on vehicles, 491–492
  multiple radials from vehicle-mounted antenna for, 488, **489**
  radial-to-mobile-antenna connection detail in, 488, **489**
  repeaters and, 487
  telescoping antennas for, 491
  temporary antenna construction for, 487–488, **488**
  temporary mast mount for, 492, **493**
  VHF band for, 487
end effect, 138–139
end or egg insulators, 551–553, **553**
end plates/end terminators, in microwave waveguides and antennas, 385, 388, **388**
end-fed longwire, 217–219, **217**
end-fed Zepp antenna, 208, **208**
environmental/natural noise (QRN), 245
erecting antennas safely, 543–548
escape angle, 48
ether, 8
Everett, W.L., 209
Expert MiniNEC modeling software, 331
EZNEC for Windows modeling software, 331, 334–337, **335, 336, 337**
EZNEC Professional modeling software, 329

F

F layer of ionosphere, 41–43, **42**, 46
fading, 35–36, 35, 55–58, 55
  Dellinger fade, 46–47
  selective fading, 55
fan dipole, multiband, 169–170, **170**
far field calculations in microwave waveguides and antennas, 395–396
Faraday connection, 318
Faraday shield, 318
Federal Communications Commission (FCC), 2
feed geometries for parabolic “dish” antennas, 408–409, **408, 409**
feed illumination in parabolic “dish” antennas, 406
feeding transformer, 476, **477**
feedpoints:
  λ/2 large loop antennas, 287–288
  dipoles, 256–257, **257**
  directional beam antennas, 256–257, **257**, 260–261, **261**
  directional phased vertical antennas, 247–248, **247, 248**
  high–frequency dipoles and doublets, 143–146
  longwires, 217–218
  multiband and tunable-wire antennas, 204, 210
  one/1λ large loop antennas, 292
  quad beam antennas, 263, **265**
  vertically polarized HF antennas, 197, **198**
  Yagi antennas, 260–261, **261**
fence posts as supports for vertical antennas, 561–565, **563, 564**
ferrite core inductors, 471–477
ferrite rods, 475, **475**
fiber optics, 370
field strength meters (FSM), for mobile HF antennas, 483–485, **484, 485**, 485*t*
field strength, 21, **22**
figure of merit, 418
filters, 55, 515
five-eighths-wavelength antennas, 197–200
  2-meter VHF/UHF antenna, 353, **354**
  vertical antenna, 181, **182**
flagpole-installed antennas, 234–236, **235, 237**
flatplate array antennas, 411, 413, **414, 415**
flattop antennas, shortwave reception, 279, **280**
floor flanges mounting hardware, 256
flux, magnetic, 126, 127
FM, marine radio antennas, 495
fold- or tilt-over tower, 567, **567**
folded dipole, 154–155, **156**
  installation of, 554–556, **555, 556**
  tilted, center-fed, terminated, folded dipole (TCFTFD or T^{2}FD, TTFD) in, 166–168, **167**
  VHF/UHF antennas, 362, **362**
forward power, 538, **539**
forward scatter, 52
“fox hunting” antenna, 444, **445**
“Franklin” array antenna, 165–166, **166**
free space, 14, 19, **21**, 67–68, 137–138
free-space velocity (C) in microwave waveguides and antennas, 377, 380
frequency, 2, 7, 9
  in microwave waveguides and antennas, 373, **374**, 375, **376**, 380, 383–384, **384**
  using Smith charts, 117–121, **119, 120**
  tilt angle vs., 28, 28*t*
  VHF/UHF transmitting/receiving antennas, 339, 341
  VSWR vs., 434–437, **435**
frequency diversity, 36, 55, **57**
frequency modulation (FM), 32

frequency of optimum traffic (FOT), 45
Fresnel zones, 33–34, **34**, 35
fundamentals of radio antennas, 123–140

G

G5RV multiband dipole antenna, 206–208, **207**
gain:
- in λ/2 large loop antennas, 288–289, **289**
- in high–frequency dipoles and doublets, 146–147
- in longwires, 214, 218, **218**, 223
- in loop antennas, small transmitter-type, 319–320
- in microwave waveguides and antennas, 394–395, 398–403
- in microwave waveguides and antennas, vs. aperture in, 402–403
- in parabolic “dish” antennas, 405–408
- in shortwave reception antennas, 272
- in vertically polarized HF antennas, 179–181
- in VHF/UHF transmitting/receiving antennas, 349

galactic noise, 39, 421
gamma match feed system:
- in Yagi antennas, 260–261, **261**
- in VHF/UHF transmitting/receiving antennas, 346, **346**

gamma rays, 39
gamma-fed grounded vertical antenna, 200–201, **201**
gas-filled line, 62, **63**
ghost radiator, vertically polarized HF antennas, 173
gin pole to raise towers, 570, **571**
Global Positioning System (GPS), 443
GNEC modeling software, 329–330
graphite-sand dummy load in microwave waveguides and antennas, 385
gray line transmission, 51, **53**
great circle paths, 50–51, **52**
grid dip meter, 527–529, **528**
ground losses, vertically polarized HF antennas, 183
ground plane vertical antennas, 172, 176, **177**
ground rods, 573–574, **574**, 575, **575**, 577, **578**
ground stakes and guy wires, 570, **572**
ground wave, 17–29, **18**, 47–48, **48**, 302
ground-mounted vertical antennas, 561–565, **562**
grounded vertical antennas, 200–201
grounding and ground systems, 573–581
- in Beverage antenna, 227–228, **228**
- copper plumbing pipes as ground rod, 574
- copper sulfate to alter soil conductivity in, 575–576
- counterpoise grounds, 577–579, **579**
- in emergency operations antennas, 487–488
- ground rods for, 573–574, **574**, 574–575, **575**, 577, **578**
- in hidden and limited-space antennas, 238–239
- impedance matching and, 459–460
- interference and, 573
- length of ground wires in, 574
- in longwires, 215–216, **216**
- in low-frequency operation antennas, 501–502, **502**
- in marine radio antennas, 495–496, **495, 496**
- radials for, 577–579, **579, 580**
- “salt pipe” to apply chemical soil-conductivity improvers, 576–577, **577**
- salt to alter soil conductivity in, 575–576
- in shortwave reception antennas, 276, **277**, 278–279, **279**
- soil conductivity and, altering, 575–577, 576*t*, **576, 577**
- station grounding, 579–580, **581**
- trenching to apply chemical soil-conductivity improvers, 576, **576**

grounding and ground systems (*Cont.*):
- tuning ground wire, 580–581
- in vertically polarized HF antennas, 176, 185–187, 195–197, **196**

groundplane VHF/UHF antenna, 356, **357**
groundplane scanner antenna, 364, **366**
group velocity (V_g) in microwave waveguides and antennas, 377–379
Grover’s equation, for loop antennas, small receiver-type, 302–303, 303*t*
guy wires and ground stakes, 570, **572**

H

“hairpin” loading scheme, 505, **506**
half-delta sloper (HDS), 295–296, **296**
half-slope vertical antenna, 238, **240**
half-wave antennas, 126, 181, **182**
- current distribution in, 131–137, **132, 133**
- electric vs. physical length of antenna, 137–139, **139**
- impedance matching in, 139–140, **139**
- standing waves and, 129
- voltage distribution in,131–137, **132, 133**

half-wavelength line, 83
halo VHF/UHF antenna, 356, **358**
hardline, 62, **62**
harmonics, 140, 209, 210, 515
height of antenna, 19, **20**, 25, 28
- distance calculation for, 26–27, **26**
- in high–frequency dipoles and doublets, vs. radiation patterns in, 148–149, **148**
- in high–frequency dipoles and doublets, vs. resistance in, 145–146, **145**
- in loop antennas, small receiver-type, 304
- in vertically polarized HF antennas, 181, 187

helical antennas, 427–428, **429**
helical line, 62

helical whip mobile antenna, 481, **482**
helically wound antennas, **239**, 242, **243**
hertz as unit of frequency, 7
Hertz or hertzian antenna (*See* high–frequency dipoles and doublets)
Hertz, Heinrich, 5, 7
heterodyning, 55
hidden and limited-space antennas, 231–244
  angled or bent dipole, 236–237, **240**
  attic-installed, 232–234, **233**
  dipoles as, 232–234, **233**, 236
  flagpole installation for, 234–236, **235, 237**
  ground system for, 238–239
  half-slope vertical antenna as, 238, **240**
  helically wound antennas as, **239**, 242, **243**
  L-section couplers in, 238–239
  limited-space designs for, 236–244
  longwires as, 232
  mobile antenna used as windowsill-mounted, 239, **241**
  mounting of, 233
  nonresonant loop antennas as, 234–235, **234**
  rotatable dipole antennas as, 239, **242**
  safety issues for, 233
  sloping (“sloper” or “slipole”) dipole as, 236, **238**
  vee dipoles as, 236, **239**
  voltage standing wave ratio (VSWR) in, 238
  window-sill antennas as, 238, **241**
high frequency (HF), 3, 13, 17, 29, 35, 37, 41, 48, 61, 170–171, 203, 479–485
high-frequency dipoles and doublets (*See* dipoles and doublets)
high-power RF wattmeters, 538, **538**
high-Q dipoles and doublets, 160
hinged baseplate tower, 566–567, **538**
history of radio broadcasting and communications, 1–4
hopping, 36
horizontal low-frequency operation antennas, 505
horizontal polarization, 12–13, **13**, 27, 55, 173
  Beverage antenna and, 226–227
  helically wound antennas and, **239**, 242, **243**
horn antenna radiators, 403–404, **403**
Huygens–Fresnel wave theory, 32

I
I^2R losses in microwave waveguides and antennas, 385
image antenna, vertically polarized HF antennas, 173
imaginary operator (j), 22
impedance and impedance matching, 140, 433, 457–477, 525
  antenna tuners for, 463–464, **464, 465**
  in antennas, 139, **139**
  approaches to, 458–462, **458**
  in Beverage antenna, 226
  capacitive reactance in, 458
  characteristic impedance (Z_o) of transmission line and, 64–67
  in coaxial cable baluns, 465, **466**
  complex conjugates in, 458
  in dipoles, 237
  electrical vs. physical length calculations in, 470–471
  feeding transformer for, 476, **477**
  ferrite core inductors in, 471–477
  ferrite rods in, 475, **475**
  grounding and, 459–460
  in high–frequency dipoles and doublets, 143–146, 149, 151–152, 155
  impedance bridges in, 519–521, **520, 521**
  impedance matching network (Q sections) in, 85
  inductive reactance in, 458
  L-section network for, 458–460, **459**
  in λ/2 large loop antennas, 287–288
  in longwires, 214, 223
  in low-frequency operation antennas, 505
impedance and impedance matching (*Cont.*):
  matching stub systems for, 465–466, **466, 467**
  matching units for, 515
  in microwave waveguides and antennas, 383–384, **384**, 394, 396
  multi-impedance balun for, 476, **477**
  in multiband and tunable-wire antennas, 210
  noise and, 417–418
  normalization of impedance in, 469–470
  in 1λ large loop antennas, 292–293, **292**
  pi networks for, 461, **461**
  quarter-wave matching (Q section) sections for, 467–468, **468, 469**
  radials in, 460
  series matching section for, 468–471
  using Smith charts, 110–112, **111**, 115, 119–121, **119**
  using Smith charts, impedance radius in, 100
  using Smith charts, normalized impedance line in, 95–97, **98**
  SPC transmatch network in, 463, **463**
  split-capacitor networks for, 461–462, **462**
  stub matching systems for, 115
  tapped balun for, 476, **477**
  tee-network transmatch for, 463, **463**
  toroid broadbanded transformers for, 475–477, **476**
  toroid cores and, 471, **472**
  toroidal transformers and, 471–475, **472**
  in towers, 507, **508**
  transmatch circuits for, 462–471, **462**
  in transmission lines, 71, 72, 82–86, 109, 110–112, **111**, 112
  in vertically polarized HF antennas, 173, 175–176, 183, **184, 186**, 195–197, 199–200, **199**
  in VHF/UHF transmitting/receiving antennas, 341–346, **342**

- impedance and impedance matching (*Cont.*):
  - Wheatstone bridge in, 519–521, **520**
  - in Yagi antennas, 260–261, **261**
- impedance bridges, 519–521, **520, 521**
- incident angle, 48
- incident power (P_I) of transmission lines, 89
- incident waves, 128, 134
- index of refraction, 23–24
- inductance, 526–527
  - ferrite core inductors in, 471–477
  - Grover's equation in, 302–303, 303*t*
  - in longwires, 214
  - in loop antennas, small receiver-type, 307
  - in loop antennas, small transmitter-type, 321
  - in transmission lines, 64
- induction fields, 5, 123, 127
- inductive (loop) coupling in microwave waveguides and antennas, 390–393, **393**
- inductive loading in low-frequency operation antennas, **503**, 504–505
- inductive reactance, 140
  - in high–frequency dipoles and doublets, 143, 157, 158*t*, 159–160, **161**
  - impedance matching and, 458
  - in $\lambda/2$ large loop antennas, 288–289, **289**
  - in loop antennas, small transmitter-type, 319, 321
  - using Smith charts, 100, **101**, 117
- infrared (IR) radiation, 9
- installation and construction techniques, 433–438, 543–572
  - center insulators, 548–550, **549, 550, 551**
  - electrical installation, vertical antennas, 560–561
  - end or egg insulators, 551–553, **553**
  - fence posts as supports for vertical antennas, 561–565, **563, 564**
  - fold- or tilt-over tower, 567, **567**
- installation and construction techniques (*Cont.*):
  - folded dipole installation, 554–556, **555, 556**
  - four/4x4 support posts for, 565, **565**
  - gin pole to raise towers, 570, **571**
  - ground-mounted vertical antennas, 561–565, **562**
  - guy wires and ground stakes, 570, **572**
  - hinged baseplate tower, 566–567, **538**
  - insulators, 548–550, **549, 550,** 551–553, **551, 553**
  - mast-mounted vertical antenna, 546, 560–561, **546**, **561, 562**
  - masts and supports, 556–559, **557, 558**
  - pedestals for towers, 568–570, **569**
  - permits, zoning, and regulations, 547–548
  - pulley system for mounting, 557–558, **558**
  - raising towers, 570, **570, 571**
  - safety issues, 543–548
  - slip-up tower, 567–568, **568, 569**
  - stirrup-end mounting hardware, 558, **559**
  - strain relief, 553–554, **554**
  - support ropes, 551
  - suburban lot installation plan, **545**
  - tower installation, 565–572, **538**
  - U-bolt mounting hardware, 558, **559**
  - vertical antenna installation, 560–572
  - wire antenna, basic design, 548, **548**
- insulators (or spreaders), 548–550, **549, 550, 551**, 551–553, **553**
  - in Beverage antenna, 228
  - in dipoles, 256
  - in directional beam antennas, 256
  - in high–frequency dipoles and doublets, 141
  - in microwave waveguides and antennas, 371–372
  - in multiband and tunable-wire antennas, 206
  - in vertically polarized HF antennas, 175, 195
- intensity of radio waves, 9–10
- interference, 19, 36, **36, 37**, 573
  - electromagnetic interference (EMI), 263
  - in longwires, 214
  - in loop antennas, small receiver-type, 302
  - in microwave waveguides and antennas, 400–401
  - in shortwave reception antennas, 272, **273**, 274
- interferometer antennas, 431, **431, 432**
- intermediate frequency (IF), 55
- International Telecommunications Union (ITU), 2
- inverse square law ($1/D^2$), 9–10, **11**, 369–370
- inverted bobtail curtain (Thorne array) antenna, 267–269, **268, 269**
- inverted-L antenna, 510, **510**
- inverted-vee antenna, rhombic, 169, **169**
- inverted-vee dipole, 152–153, **153**
  - emergency operations antennas, 490–491, **491**
  - multiband and tunable-wire antennas, 205, **206**
- ionization, 5, 14–16, **15**, 18, 37, 41, 46, 47, 51, 52, 54
- ionograms, 43
- ionosphere, 14–16, **15**, 18, 37, 40–43, **42**, 176
- ionospheric disturbances, 45–47
- ionospheric propagation, 17–18, **18**, 37–43, 176
- ionospheric scatter propagation, 51–54, **53**
- ionospheric storms, 47
- ionospheric variation, 45–47
- iosthermal region of atmosphere, 14, **15**
- isophase plane, 32
- isopotential line, loop antennas, small receiver-type, 303
- isoresistance circles, using Smith charts, 97–100, **99**
- isotropic antenna waveguide, 394–403
  - backlobes in, 400, **400, 401**
  - beamwidth in, 400, **400, 401**

isotropic antenna waveguide (*Cont.*):
  dipole antenna elements and, 396–398, **397, 399**
  directivity in, 397, 398–403, **400**
  gain in, 398–403
  gain vs. aperture in, 402–403
  impedance in, 396
  interference and, 400–401
  near field and far field calculations in, 395–396
  ohmic loss in, 396
  radiation patterns and, 397, **398**
  radiation resistance in, 396
  sidelobes in, 400, **400, 401**
isotropic radiation:
  in high–frequency dipoles and doublets, 146
  in microwave waveguides and antennas, 394
  in shortwave reception antennas, 272
  in vertically polarized HF antennas, 179–181, **181**
isotropic sources, 10–14
ISWR (*See* current standing wave ratio)

J

J-pole antennas, 201, 353–355, **355**
Jansky, Carl, 421
JFET amplifier for loop antennas, small receiver-type, 313–316, **316**
Johnson noise, 417
joints and bends in microwave waveguides and antennas, 388–390, **389, 390**
Jupiter reception antenna, 421–422, **423**

K

K factor, 23–27
kilohertz as unit of frequency, 7
Ku bands, 69

L

L-section coupler, 214, **215**, 238–239
L-section network for impedance matching, 458–460, **459**
lag, voltage, 126
$\lambda/2$ large loop antennas, 287–289, **288, 289**
$\lambda/4$ inverted-L antenna, 510, **510**
Law of Reciprocity, 226, 271, 394
LC tank circuit, 526, **526**
leakage resistance, 140
left-hand rule, 126, **127**
length of antenna elements:
  in coaxial cable, 438
  in dipoles, 141, 142–143, 149–151, 160, 232, 255–256
  in directional beam antennas, 255–257, 259–260
  in directional phased vertical antennas, variable lengths in, 248–249, **249**
  in high–frequency dipoles and doublets, 141, 142–143, 149–151, 160, 232, 255–256
  in longwires, 213–215, 218–219, **218**, 221, 223
  in low-frequency operation antennas, 504
  in microwave waveguides and antennas, 392
  in multiband and tunable-wire antennas, 204
  in vertical antennas, 504
  in vertically polarized HF antennas, 181, 183, **184**
  in VHF/UHF transmitting/receiving antennas, 339
  in Yagi antennas, 259–260
Lewallen, Roy, 329, 331, 334
licensing, 3
light, speed, 8, 9, 13–14, 39, 525
limited-space antennas, 231–244
line attenuation constant, 82
line flattener tuner for marine radio antennas, 500, **500**
line-of-sight transmission, 19, **20**, 23–24, **23**, 35, 339
linear loading in low-frequency operation antennas, **504–505**
linearly loaded tee antenna, 511, **512**
link-tuned dipole, multiband and tunable-wire antennas, 205
loaded tower designs, 507
loading, **503**, 504–505, **506**
  automatic load control (ALC), 515
  in low-frequency operation antennas, **503**, 504–505, **506**
loading (*Cont.*):
  in low-frequency operation antennas, loaded tower designs for, 507
loading coils, dipoles and doublets in, 157–160, **157**
long path transmission, 51
long wave band, 8
longwires, 213–229
  angle of radiation in, 214
  antenna tuning unit (ATU) in, 172, 214
  apex angle in, 223
  baluns in, 171, **171**
  Beverage or “wave” antenna in, 224–228, **226, 228, 229**
  capacitors for, 215
  characteristic impedance in, 223, 226
  counterpoise, 170–172, **171**
  double vee antennas, 223
  electrical vs. physical length of, 213–214, 217, 218–219, 221
  electrostatic fields and electric charge in, 219
  end-fed longwire, 217–219, **217**
  feedpoint in, 217–218
  flagpole installation of, 234–236, **235, 237**
  gain in, 214, 218, **218**, 223
  ground plane verticals in, 172
  grounding of, 215–216, **216**
  as hidden and limited-space antennas, 232
  impedance and impedance matching in, 214, 223, 226
  inductors for, 214
  interference and, 214
  L-section coupler for, 214, **215**
  length of, 213–215, 218–219, **218**, 221, 223
  as marine radio antennas, 497, **498**
  maximum effective length (MEL) in, 227
  as multiband and tunable-wire antennas, 209, **210**
  non-resonant single-wire longwire antennas in, 220
  nonresonant vee beams, 223, **224**
  quarter-wavelength, 214, 217
  radials for, 215

longwires (*Cont.*):
  radiation patterns in, 219, **220**, 220–221, **222**
  random-length type, 213–214, **214**
  resonant vs. non-resonant types in, 213
  rhombic beam, 221, 223–224, **225**
  safety issues in, 215
  as shortwave reception antennas, 277–278, **278**
  as standing wave antennas, 220
  steerable notch Beverage antennas and, 229, **229**
  terminated antennas as, 220, **221**
  tilt angle in, 223
  transmission line for, 217–218
  traveling wave antennas in, 220, 223
  true longwire antenna, 217–219, **217**
  tuning of, 214, 215, **215**
  vee beam, 221–223, **222**
  VHF/UHF transmitting/receiving antennas, 340–341
  voltage standing wave ratio (VSWR) in, 215
  wavelength-measurement in, 217, 218–219
  window-sill antennas, 238, **241**
  wire used in, 214
  Zepp antenna in, 164–165, **165**
"looking in" impedance, 82–86, 372
loop antennas, 129, 131
loop antennas, large design, 287–297, 299
  (*See also* loop antennas, small receiver-type; loop antennas, small transmitter-type)
  antenna tuning unit (ATU) in, 287
  bisquare loop large antenna, 296–297, **297**
  current in, 289
  delta loop (1λ) large antenna, 290–293, **291**
  delta loop large antenna, 293, **295**
  demiquad loop antenna, 293, **294**
  diamond loop (1λ) large antenna, 290–293, **291**
  feedpoints in, 287–288, 292
  gain in, 288–289, **289**
  half-delta sloper (HDS), 295–296, **296**
loop antennas, large design (*Cont.*):
  impedance and impedance matching in, 292–293, **292**
  impedance in, 287–288
  inductive reactance in, 288–289, **289**
  λ/2 large loop antennas in, 287–289, **288, 289**
  loss in, 288–289, **289**
  nulls in, 299–300, **300, 301**
  (1λ) large loop antennas, 290–293, **290, 291**
  orthogonal lobes in, 299–300, **300, 301**
  radiation patterns in, 287, 299–300, **300, 301**
  square loop (1λ) large antenna, 290–293, **290**
loop antennas, small receiver-type, 299–318
  (*See also* loop antennas, large design; loop antennas, small transmitter-type)
  air core frame loops ("box" loops) in, 303–305, **304**
  amateur radio, 302
  amplifier for, 313–316, **316**
  angle of arrival of signal in, voltage vs., 303, **305**
  Armstrong oscillator circuit for, 313, **315**
  capacitance and capacitors in, 304, 307–309, 317
  capacitance tuning of, 307–309
  coaxial cable loop antennas, 318, **318**
  cochannel interference, 302
  coupling loops in, 306–307, **306**
  current in, 299
  depth wound loops in, 303
  DXing using, 311–313
  effective height of, 304
  Faraday connection and Faraday shield in, 318
  Grover's equation in, 302–303, 303*t*
  height of, 304
  inductance in, 307
  isopotential line in, 303
  low frequency (LF), 302
  nulls in, 299–300, **300, 301**, 303, **305**
  parallel tuning of, 307–309, **308**
  planar windings in, 303
loop antennas, small receiver-type (*Cont.*):
  preamplifiers for, 304
  Q–multipliers for, 313, **315**
  radiation patterns in, 299–300, **300, 301**, 303, 313
  radio direction finding (RDF) using, 301
  remote tuning in, 307–309, **310**
  self-resonant point in, 317, **317**
  series resonant tuning in, 307–309, **308**
  shape constants in, 303, 303*t*
  sharpening of, 313
  shielded loop antennas as, 309–311, **311, 312**
  split frequencies in, 302
  spoiler loop for, 313, **314**
  sports fan's loop as, 309
  transformer loops in, 306–307, **306**
  triangulation of radio signal using, 302
  tuning of, 304, 307–309, **308**, 312–313
  UHF, 302
  use of, 311–313
  varactor tuning in, 309, **310**
  VHF, 302
  VLF/LF loops, special problems in, 317
  voltage in, 303, 304
loop antennas, small transmitter-type, 319–325
  (*See also* loop antennas, large designs ; loop antennas, small receiver-type)
  bandwidth of, 320–321
  capacitance and capacitors in, 320–321
  capacitor voltage in, 321
  circular loop transmitter antenna as, 323, **323**
  current in, 320, 323
  design equations for, 321–322
  distributed capacitance in, 321
  efficiency in, 321
  gain in, 319–320
  inductance in, 321
  inductive reactance in, 319, 321
  loss resistance in, 321
  octagonal loop transmitter antenna in, 319, **320**, 322, **322**, 323, **324**

loop antennas, small transmitter-type (*Cont.*):
  Patterson octagonal loop transmitter antenna as, 322, **322**
  quality factor (Q) in, 320–321
  radiation patterns in, 324, **325**
  radiation resistance in, 319, 321
  resistance in, 319, 321
  square loop transmitter antenna in, 319, **320**
  tuning capacitance in, 320–321
  voltage in, 320, 323
  voltage standing wave ratio (VSWR) in, 320
loss, 11–12, 19, 27, 140
  in coaxial cable, 438
  in high–frequency dipoles and doublets, 143–146
  in λ/2 large loop antennas, 288–289, **289**
  loss coefficient scale in, 109
  in microwave waveguides and antennas, 396
  in multiband and tunable-wire antennas, 210
  in Smith charts, 108–109
  in transmission lines, 83–84, 91–94, 369
  in vertically polarized HF antennas, 183
loss coefficient scale, 109, 112–113
loss resistance, in loop antennas, small transmitter-type, 321
lossy circuits, Smith charts, 117, **118**
low frequency (LF), 421
  loop antennas, small receiver-type, 302
  low-frequency operation antennas, 501–513
  VHF/UHF transmitting/receiving antennas vs., 339
low-frequency operation antennas, 501–513
  continuous loading in, **503**, 504–505, **506**
  delta feed systems in, 507, **509**
  discrete loading in, **503**, 504–505
  grounding and ground systems for, 501–502, **502**
  "hairpin" loading scheme in, 505, **506**
  impedance matching in, 505
low-frequency operation antennas (*Cont.*):
  impedance matching in, of towers, 507, **508**
  inductance loading of vertical antennas in, **503**
  inductive loading in, **503**, 504–505
  inverted-L antenna for, 510, **510**
  λ/4 inverted-L antenna for, 510, **510**
  length of vertical antenna in, 504
  linear loading in, **503**, 504–505
  linearly loaded tee antenna for, 511, **512**
  loaded tower designs for, 507
  loading in, **503**, 504–505, **506**
  radial layout for, 502, **502**
  random-length Marconi antenna for, 507–510, **509**
  shortened horizontal antennas for, 505
  shortened tee antenna, 511, **513**
  shortened vertical antennas for, 502–505, **503**
  shunt feed systems in, 507
lower sideband (LSB), 55
lowest usable frequency (LUF), 45

M

magnetic fields, 123, 126, 127, **128**,
  in microwave waveguides and antennas, 375–376, **375**, 383, 395–396
magnetic flux, 126, 127
man-made noise (QRM), 245
Marconi, Guglielmo, 1
marine radio antennas, 1–2, 494–497, **497**
  Citizens Band radios and, 496
  grounding and ground systems for, 495–496, **495, 496**
  HF SSB mode in, 495
  line flattener tuner for, 500, **500**
  longwire antennas, 497, **498**
  tuners, 497–500, **499, 500**
  VHF-FM use in, 495
  whip antennas for, 496–497, **497**
mast-mounted vertical antenna, 546, **546**, 560–561, **561, 562**
masts and supports, 556–559, **557, 558**
matching section, quarter-wavelength coax, 292
matching stub systems, 465–466, **466, 467**
maximum effective length (MEL), 227
maximum usable frequency (MUF), 43–45, 47
Maxwell's equations, 8–9
measurement and adjustment techniques, 433–438, 515–542
  antenna adjustment in, 523–524
  automatic load control (ALC) in, 515
  basic radio system in, 515, **516**
  bridge to measure RF power in, 532, **532**
  capacitance measurement in, 526–527
  current transformer wattmeter in, 534–538, **535, 536, 537**
  dip oscillator/dip meter in, 527–529, **527, 528**
  dummy loads in, 540–542, **540, 541, 542**
  filters in, 515
  forward power in, 538, **539**
  grid dip meter in, 527–529, **528**
  harmonics in, 515
  high-power RF wattmeters for, 538, **538**
  impedance bridges in, 519–521, **520, 521**
  impedance in, 525
  inductance measurement in, 526–527
  LC tank circuit in, 526, **526**
  matching unit in, 515
  micromatch wattmeter in, 533, **533**
  monomatch wattmeter in, 533–534, **534**
  nonresonant antenna adjustment in, 524–525
  parallel resonant circuits in, 526
  power in, 515, 531–532
  power-frequency calibration in, 538, **538**
  reactance testing/adjustment in, 524
  reflected power in, 538, **539**
  resistance testing/adjustment in, 523–524
  resonance testing/adjustment in, 524

measurement and adjustment techniques (*Cont.*):
  RF noise bridge in, 521–522, **521**
  RF power measurements in, 529–539
  RF wattmeters for, 529–539, **531**
  series tuned circuits in, 526
  surge impedance (Z_o) in, 516
  thermocouple for RF ammeter in, 530, **530**
  transmission lines in, 516–517, 525
  tuned circuit measurements in, 526
  tuning antennas in, 524
  voltage measurement in, 531
  voltage standing wave ratio (VSWR) in, 515, 517–519, 529, 532
  Wheatstone bridge in, 519–521, **520**
medium wave (MW), 8, 17, 29, 48, 61, 224–228, **226, 228, 229**
meteor scatter propagation, 54
micromatch wattmeter, 533, **533**
microwave transmissions, 3, 5, 8, 13, 17, 18, 19, 22, 23, 29, 30, 32, 37, 40, 61, 69, 369
microwave waveguides and antennas , 369–415, 421
  (*See also* parabolic “dish” antennas)
  adjustable plunger or short-circuit termination in, 388, **388**
  antenna design using, 394
  aperture (slot) coupling in, 390–393, **393**
  aperture in, 402–403
  array antennas in, 409–411
  attenuation in, 377
  backlobes in, 400, **400, 401**
  beamwidth in, 400, **400, 401**
  boundary conditions in, 375–376
  branch feed systems for, 409, **412**
  capacitive (probe) coupling in, 390–393, **392**
  cavity antennas, 404, **405**
  characteristic impedance in, 383–384
  choke joints in, 389, **390**
  coordinate system to denote dimensions in, 376–377, **377**
  corner reflector antennas, 404, **405, 406**
microwave waveguides and antennas (*Cont.*):
  corporate feed systems for, 409, **412**
  coupling methods for, 390–393
  cutoff frequency (F_c) in, 381–383
  dielectric loss, 369
  dipole antenna elements and, 396–398, **397, 399**
  directivity gain (G_d) in, 401–402
  directivity in, 395, 397, 398–403, **400**
  dominant mode in, 376–377
  dummy loads in, 385–388, **386**
  effective aperture (A_e) in, 394
  effective radiated power (ERP) in, 401
  electric fields in, 383, 395–396
  end plate in, 385, 388, **388**
  flatplate array antennas, 411, 413, **414, 415**
  free-space velocity (C) in, 377, 380
  frequency in, 373, **374**, 375, **376**, 380, 383–384, **384**
  gain in, 394, 395, 398–403
  gain vs. aperture in, 402–403
  graphite-sand dummy load in, 385
  group velocity (V_g) in, 377, 378–379
  horn antenna radiators in, 403–404, **403**
  I^2R losses in, 385
  impedance and impedance matching in, 383–384, 394, 396
  inductive (loop) coupling in, 390–393, **393**
  insulators in, 371–372
  interference and, 400–401
  inverse square law ($1/D^2$), 369–370
  isotropic antenna waveguide, 394–403
  isotropic radiation in, 394
  joints and bends in, 388–390, **389, 390**
  law of reciprocity and, 394
  length in, 392
  losses in, 396
  magnetic fields in, 375–376, **375**, 383, 395–396
  materials used in, 370
  near field and far field calculations in, 395–396
microwave waveguides and antennas (*Cont.*):
  ohmic loss in, 369, 371, 396
  parabolic “dish” antennas as, 404–409, **407, 408, 409**
  phase shifting in, 409, **412, 413**
  phase velocity (V_p) in, 377, 379, 380
  pipe analogy of, 369–370, **370**
  power gain (G_p) in, 401–402
  propagation constant (B) in, 384
  propagation modes in, 373–381
  quarter-wavelength shorted stub vs., 372–373, **372, 373, 374**
  radiating vs. nonradiating slots in, 393
  radiation loss in, 369, 372
  radiation patterns and, 397, **398**
  radiation resistance in, 396
  rectangular waveguide using parallel transmission lines and, 370–373, **371**
  reflector antennas, 404, **405, 406**
  resistive vane dummy load in, 385
  rotating joints in, 390, **391**
  safety issues, 413–415
  semipermanent joints in, 389
  shielding in, 392
  sidelobes in, 400, **400, 401**
  skin effect in, 369, 371
  slot array antennas in, 411–413, **413**
  solid-state array antennas in, 408–411
  terminations for, 385–388
  transducer action of, 394
  transverse electric mode (TE mode) in, 375
  transverse electromagnetic (TEM) fields in, 373
  transverse magnetic mode (TM mode) in, 375
  velocities in, 377–381, **378**
  voltage standing wave ratio (VSWR) in, 388
  wavelength in, 377–381, **378**
  wedge dummy loads in, 385, **386, 387**
military radio, multiband and tunable-wire antennas, 203
MiniNEC modeling software, 331
miniNEC-3/miniNEC-4 for modeling software, 328–329

“mirroring” of radio waves, 43, 54
mismatch (VSWR) losses, transmission lines, 91–94
mixing, 55
mobile HF antennas, 479–485
  coil-loaded antenna as, 480–481, **480, 351**
  field strength meters (FSM) for, 483–485, **484, 485**, 485*t*
  helical whip antenna as, 481, **482**
  multiband top-loaded antenna as, 481, **482**
  Q factor in, 483
  radial-to-mobile-antenna connection detail in, 488, **489**
  resonance in, 483
  top-loaded antenna as, 481, **482**
  tuning of, 483–485
  voltage standing wave ratio (VSWR) in, 483
  used as windowsill-mounted, 239, **241**
modeling software for antennas, 327–338
  coordinate system used in, 328, **329, 330**
  Expert MiniNEC, 331
  EZNEC for Windows, 331, 334–337, **335, 336, 337**
  EZNEC Professional, 329
  GNEC, 329–330
  MiniNEC, 331
  miniNEC-3/miniNEC-4, 328–329
  NEC-2, 330
  NEC4Win95, 331
  NECWin Basic, 331–334, **332**
  NECWin Plus, 330–331
  Numerical Electromagnetic Computation (NEC) programs in, 328
  radiation patterns displayed in EZNEC for Windows, 336–337, **337**
  radiation patterns displayed in NECWin Basic, 332, **333, 334**
  voltage standing wave ratio (VSWR) modeling in, 333, **335**
  voltage standing wave ratio (VSWR) modeling in, 337, **338**
monomatch wattmeter, 533–534, **534**
monopulse feeds, parabolic “dish” antennas, 409, **410**
monthly variations in radio propagation, 46
Morse code, 1, 2
mounting (*See also* construction and installation techniques)
  Beverage antenna, 228
  dipole, 233, 256
  directional beam antenna, 256
  emergency operations antenna, on vehicles, 491–492
  fence posts as supports for vertical antenna, 561–565, **563, 564**
  floor flanges in, 256
  hidden and limited-space antenna, 233
  high–frequency dipole and doublet, 141
  mast-mounted vertical antenna, **546**
  pulley system for, 557–558, **558**
  right-angle flange hardware in, 256
  shortwave reception antenna, 277–278, **278**
  stirrup-end hardware in, 558, **559**
  temporary mast mount for emergency antenna, 492, **493**
  U-bolt hardware, 558, **559**
  vehicle-mounted emergency antenna, 491–492
  vertically polarized HF antenna, 186, 189–190, 194–195, **194**, 195–197, **196**, 560–565, **561**
  VHF/UHF transmitting/receiving antenna, 347
multi-impedance balun, 476, **477**
multiband and tunable-wire antennas, 203–212
  antenna tuning unit (ATU) for, 210
  balanced transmission line and, 208
  balancing line, 208–209, **209**
  baluns for, 208–209, **209**, 210
  coaxial cable in, 208
  dipoles in, 204–205, **205**
  end-fed Zepp antenna in, 208, **208**
  feeding parallel transmission line for, 208–212
  feedpoint in, 204, 210
  G5RV multiband dipole antenna in, 206–208, **207**
multiband and tunable-wire antennas (*Cont.*):
  harmonics in, 210
  impedance in, 210
  insulators (spreaders) in, 206
  inverted-vee dipole for, 205, **206**
  length of, 204
  link-tuned dipole for, 205
  longwires for, 209, **210**
  losses in, 210
  quad beam antennas for, 203
  random-length longwire antennas in, 209, **210**
  transformers for, 210, **211**
  transmatches in, 208–209, **209**
  trap dipoles in, 204–206, **204, 205**
  tunability of, 203
  tuned feeder antennas in, 206, **207**
  tuning of, 205
  voltage standing wave ratio (VSWR) and, 203
  Windom antenna as, 209–210, **211**
  Yagi antennas as, 203
multiband fan dipole, 169–170, **170**
multiband top-loaded mobile antenna, 481, **482**
multifilar windings in transformers, 472
multihop communication, 23, **49**, 49–50
multihop interference, 36, **36**
multiple helical antennas, 428–431, **429, 430**
multiple radials from vehicle-mounted antenna, 488, **489**

N

NAA radio station, 2
National Bureau of Standards (*See* National Institute of Standards and Technology)
national identifiers in call signs, 3
National Institute for Standards and Technology (NIST), 40, 47
Naval Research Laboratory, 2
near field and far field calculations in microwave waveguides and antennas, 395–396
NEC-2 modeling software, 330
NEC4Win95 modeling software, 331
NECWin Basic modeling software, 331–334, **332**

NECWin Plus modeling software, 330–331
Nittany-Scientific, 329, 330, 331
nodes, 87, 129
noise, 37, 68–69
  antenna noise temperature as, 417–420
  contributors to antenna noise temperature and, 419–420, **419**
  environmental/natural noise (QRN) in, 245
  figure of merit and, 418
  impedance and, 417–418
  Johnson noise in, 417
  man-made noise (QRM) in, 245
  noise bridge in, 521–522, **521, 522, 523**
  noise factor (F_n) in, 418
  noise figure (NF) in, 418
  noise temperature (T_e) in, 418–420
  omnidirectionality vs., 245
  piezoelectric, 69
  RF noise bridge in, 521–522, **521**
  signal-to-noise ratio (SNR) in, 246
  sky noise sources, 419–420
  thermal agitation noise, 417
  thermal noise in, 417–420
  in transmission lines, 68–69
  in Yagi antennas, 261
noise bridge, 521–522, **521, 522, 523**
noise factor (F_n), 418
noise figure (NF), 418
noise temperature (T_e), 418–420
nonreciprocal direction propagation, 54
nonresonant antenna adjustment, 524–525
nonresonant loop antennas, 234–235, **234**
nonresonant single-wire longwire antennas, 220–220
nonresonant vee beam longwire antenna, 223, **224**
normalization of impedance, 95–97, **98**, 469–470
northern lights, 54
null steering, 229
nulls, in loop antennas, 299–300, **300, 301**, 303, **305**
Numerical Electromagnetic Computation (NEC) programs, 328

O

1λ large loop antennas, 290–293, **290, 291**
octagonal loop transmitter antenna, 319, **320**, 322, **322**, 323, **324**
off-center-fed full-wave doublet (OCFD), 163, **163**
off-center-fed nonresonant sloper (OCFS), 164, **164**
ohmic loss, 143–146, 369, 371, 396
ohmic resistance, 19, 27, 140
ohmmeter, coaxial cable test, 437–438, **437**
Ohm's law, transmission lines, 74
Ω-fed grounded vertical antenna, 200–201, **202**
ominidirectionality:
  in high–frequency dipoles and doublets, 146
  noise vs., 245
  in shortwave reception antennas, 272, **273**
  in vertically polarized HF antennas, 173, 179–181
open line, 59
Orion, 331
orthogonal lobes, in loop antennas, 299–300, **300, 301**
OSCAR satellite communications, 3, 339
out–of–phase waves, **22**

P

parabolic "dish" antennas, 404–409, **407, 408, 409**, 421
  beamwidth in, 407
  Cassegrain feed in, 408–409, **409**
  cutoff frequency in, 406
  directrix in, 404
  effective aperture in, 407
  feed geometries for, 408–409, **408, 409**
  feed illumination in, 406
  gain in, 405–408
  monopulse feeds, 409, **410**
  ray tracing showing operation of, **407**
  splash plates in, 408
  x-y coordinates in, 404
parallel lines, 59–63, **60**, 65–66
parallel resonant circuits, 526
parallel tuning in loop antennas, 307–309, **308**
parasitic elements in Yagi antennas, 258–259
paths, 17–18, **18**
Patterson octagonal loop transmitter antenna, 322, **322**
pedestals for towers, 568–570, **569**
permits, zoning, and regulations, 547–548
phase, 126, **128**
phase constant, 82
phase control circuit (PCC), 229
phase reversal stubs, collinear "Franklin" array antenna in, 165–166, **166**
phase shift, 19, 21–23, 129, 409, **412, 413**, 450–451, **451**
phase velocity (V_p) in microwave waveguides and antennas, 377, 379, 380
phase-shifting circuit, directional phased vertical antennas, 252, **252**
phase-switching antenna matcher, shortwave reception antennas, 284, **285**
phasing box, shortwave reception antennas, 284, **286**
phasing switch, directional phased vertical antennas, 249–250, **252**
phasing transformer, 249–250, **250, 251**
phasing, phased radials, directional phased vertical antennas, 246–250
pi networks, 461, **461**
"picket fencing," 23
piezoelectricity, 69
planar windings in loop antennas, 303
planetary terminator, 51, **53**
plunger or short-circuit termination, microwave waveguides and antennas, 388, **388**
polarity, 126-127, 131, 134
  reversal of, 126–127, 131, 134
polarization of radio waves, 12–13, **13**, 27, **28**, 29, 55, 173
  in Beverage antenna, 226–227
  in directional phased vertical antennas (*See* directional phased vertical antennas)

polarization of radio waves (*Cont.*):
  in vertically polarized HF antennas, 173–202
polarization diversity, 55, **58**
power, 11, **21**, 140, 515, 531–532
  in RF power measurements, 529–539
  in vertically polarized HF antennas, 180
power density, 10
power fading, 36
power gain (G_p) in microwave waveguides and antennas, 401–402
power-frequency calibration in, 538, **538**
preamplifiers for loop antennas, 304
predictions of propagation, 55, **56**
propagation constant (B), 82, 384
propagation modes in microwave waveguides and antennas, 373–381
propagation of radio waves, 5–58
propagation predictions, 55, **56**
pulley system for mounting, 557–558, **558**
pure reactance circle, Smith charts, 100, **103**
pure resistance line, Smith charts, 95–97, **98**

Q

Q–multipliers for loop antennas, small receiver-type, 313, **315**
QRM noise, 245
QRN noise, 245
quad beam VHF/UHF antenna, 356, 358, **359**
quad beam antennas, 203
quad loop antennas, 263–267, **264, 266, 267**
quality factor (Q), 85, 160, 320–321, 483
quarter-wave matching (Q section) sections, 85, 146, 199–200, **199**, 467–468, **468, 469**
quarter-wave vertical polarized HF antenna, 173
quarter-wavelength longwires, 214, 217
quarter-wavelength lines, 84–85
quarter-wavelength shorted stub
  “looking in” impedance in, 372
  microwave waveguides and antennas vs., 372–373, **372, 373, 374**
  transmission lines and, 86, **87, 88**
quarter-wavelength vertical antenna, 181, **182**, 183, 187

R

radar, 3, 30, 52
radial-to-mobile-antenna connection detail, 488, **489**
radially scaled parameters, Smith charts, 106–109, **107**
radials:
  in grounding and ground systems, 577–579, **579, 580**
  in impedance matching, 460
  in longwires, 215
  in low-frequency operation antennas, 502, **502**
  multiple, from vehicle-mounted antenna for, 488, **489**
  radial-to-mobile-antenna connection detail in, 488, **489**
  in vertically polarized HF antennas, 176, 186, **189**, 560–561
radiated fields, 5
radiating vs. nonradiating slots, microwave waveguides and antennas, 393
radiation angle, 30, 48–50, **50**
radiation loss, 369, 372
radiation patterns:
  in Adcock antenna, **449**
  in beam antennas, 257–258, **258**
  cardioid, 441, **442**
  in directional phased vertical antennas, 246–250, **246, 247**
  EZNEC for Windows modeling of, 336–337, **337**
  in high–frequency dipoles and doublets, 146–152, **147**
  in isotropic antenna waveguide, 397, **398**
  in λ/2 large loop antennas, 287
  in longwires, 219, **220**, 220–221, **222**
  in loop antennas, large designs, 299–300, **300, 301**
  in loop antennas, small receiver-type, 299–300, **300, 301**, 303, 313
radiation patterns (*Cont.*):
  in loop antennas, small transmitter-type, 324, **325**
  in loopstick antennas, 439, **440, 441**
  NECWin Basic modeling of, 332, **333, 334**
  in sense antennas, 441, **442**
  in switched-pattern RDF antenna, 454–456, **454**
  in vertically polarized HF antennas, 178–181, **181, 182**
  in Watson-Watt Adcock array antennas, **450**
  in Yagi antennas, 257–258, **258**
radiation resistance, 140
  in high–frequency dipoles and doublets, 143–146
  in loop antennas, small transmitter-type, 319, 321
  in microwave waveguides and antennas, 396
  in vertically polarized HF antennas, 183, **184, 185**
radiators, high–frequency dipoles and doublets, 141
radio astronomy antennas, 421–432
  directional discontinuity ring radiator (DDRR) antenna in, 424–427, **426**, 427*t*
  helical antennas in, 427–428, **429**
  interferometer antennas in, 431, **431, 432**
  Jupiter reception antenna, 421–422, **423**
  multiple helical antennas in, 428–431, **429, 430**
  ring antenna, 422–424, **423, 424, 425**
  summation interferometer array antenna, 431, **431**
radio direction finding (RDF), 439–456
  Adcock antennas for, 446–447, **448, 449**
  AM broadcast band (BCB) in, 439
  birdirectionality of loopsticks in, 441
  cardioid radiation pattern of sense antenna in, 441, **442**
  CONALRAD station frequencies and, 439
  Doppler antennas, 450–451, **451**

radio direction finding (RDF) (*Cont.*):
  double ducky direction finders (DDDF) in, 455–456, **455**
  “fox hunting” antenna in, 444, **445**
  Global Positioning System (GPS) and, 443
  improvisation of, using portable AM radio receiver, 443, **443**
  loop antennas in, small receiver-type, 301
  loopstick antennas in, 439–440, **440**
  measurements in, 433
  radiation patterns of loopsticks in, 439, **440, 441**
  regular wire loop antennas for, 444, **445**
  “rubber ducky” VHF antennas in, 454–456, **455**
  S meters in, 439
  sense antenna for, 441, **442**, 446, **447**
  shortwave and AM BCB “skip” in, 444–446
  switched-pattern RDF antenna in, 454–456, **454**
  time difference of arrival (TDOA) array antenna in, 452–454, **453**
  triangulation of radio signal in, 439
  Watson-Watt Adcock array antennas in, 447–450, **449, 450**
  wide-aperture direction finder (WADF) in, 451
  Wullenweber array antennas in, 451, **452**
Radio Luxembourg effect, 54
radio system, 515, **516**
radio vectoring, 3
radio wave configuration, 5–6
random-length longwires, 209, **210**, 213–214, **214**, 507–510, **509**
ray tracing, 32–33, **407**
reactance, 140, 524
  (*See also* capacitive reactance; inductive reactance)
  in high–frequency dipoles and doublets, 143
  Smith charts, 109, 117
  Smith charts, capacitive reactance in, 100, **102**
reactance (*Cont.*):
  Smith charts, constant reactance circles in, 100–105
  Smith charts, inductive reactance in, 100, **101**
  Smith charts, pure reactance circle in, 100, **103**
  in transmission lines, 85–86, 109, 525
  in vertically polarized HF antennas, 183, **184**
Reber, Grote, 421
receivers, 123
reciprocity, law, 226, 271, 394
recombination phenomena, 18
rectangular waveguide using parallel transmission lines, 370–373, **371**
reflected power (P_r), 89, 538, **539**
reflected waves, 128, 134
reflection, 16–17, 21, 22, 50, 52, 161
reflection coefficient, 21, 22
  Smith charts, **103, 106**, 106–109, 112, 114
  transmission lines, 71–79, 89, 112, 114
reflection loss, 113–114
reflector antennas, 404, **405, 406**
reflectors, Yagi antennas, 258–259
refraction, 16–17, 16, 23–24, **24**, 29–30, **30**, 48
refractivity of atmosphere, 24–27
regular wire loop antennas, 444, **445**
remote tuning, loop antennas, small receiver-type, 307–309, **310**
repeaters for emergency operations antennas, 487
resistance, 27, 140, 369, 434–437, 523–524
  in high–frequency dipoles and doublets, 143–146, **145**
  in loop antennas, small transmitter-type, 319, 321
  in Smith charts, constant or isoresistance circles in, 97–100, **99**
  in Smith charts, pure resistance line in, 95–97, **98**
  in Smith charts, unity resistance circle in, 100
  in transmission lines, 64, 525
resistance (*Cont.*):
  in vertically polarized HF antennas, 183
resistive vane dummy load in microwave waveguides and antennas, 385
resonance, 140, 524
  in dipoles, 237
  in high–frequency dipoles and doublets, 143, 149–151, **150**
  in mobile HF antennas, 483
resonant frequency, 433
resonant vs. non-resonant longwires, 213
return loss, 108–109, 113, 114
RF ammeter, 530, **530**
RF noise bridge, 521–522, **521**
RF power measurements, 529–539
RF wattmeters, 529–539, **531**
rhombic beam longwire antenna, 221, 223–224, **225**
rhombic inverted-vee antenna, 169, **169**
right-angle flange mounting hardware, 256
ring antenna, 422–424, **423, 424, 425**
RLC networks, 59, 143
rotatable dipole antennas, 239, **242**, 255–257, **257**
rotating joints in microwave waveguides and antennas, 390, **391**
“rubber ducky” VHF antennas, 454–456, **455**

S

S meters in RDF antennas, 439
safety issues, 543–548
  burns or shocks from RF through vertical antennas, 191, 195
  hidden and limited-space antennas, 233
  longwires, 215
  microwave waveguides and antennas, 413–415
  shortwave reception antennas, 276, **277**, 279
  VHF/UHF transmitting/receiving antennas, 340
“salt pipe” to apply chemical soil-conductivity improvers, 576–577, **577**

- salt to alter soil conductivity, 575–576
- satellite communications, 3, 339, 421
- scanner band VHF/UHF antennas, 360–368
- scanner skyhook VHF/UHF antennas, 362–368, **363**
- scanner-vision antennas, 360–362, **361**
- scatter propagation, 51–54, **53**
- seasonal variations in radio propagation, 24, 40, 41, 46, 51, 178
- selective fading, 55
- self-resonant point, loop antennas, small receiver-type, 317, **317**
- semipermanent joints in microwave waveguides and antennas, 389
- sense antenna in RDF, 441, **442**, 446, **447**
- series matching section, 468–471
- series resonant tuning, loop antennas, small receiver-type, 307–309, **308**
- series tuned circuits, 526
- series-fed vertical antennas, 200
- shape constants, loop antennas, small receiver-type, 303, 303*t*
- shielded loop antennas, 309–311, **311, 312**
- shielded parallel line, characteristic impedance of, 66
- shielded twin lead, 61, **61**
- shielding in microwave waveguides and antennas, 392
- shocks hazards from RF through antennas, 191, 195, 215, 233, 276, 279
- short path transmission, 51
- short skip, 41
- short-circuit termination, in microwave waveguides and antennas, 388, **388**
- shorted lines, 87
- shorted stubs, transmission lines, 86, **87**
- shorted stubs (*See* stub matching systems)
- shortened coil-loaded dipoles, 157–160, **158**
- shortened tee antenna, 511, **513**
- shortwave and shortwave reception antennas, 2–4, 8, 37, 41, 54–55, 271–286
- shortwave and shortwave reception antennas (*Cont.*):
  - angle of radiation in, 274, **274**
  - antenna matching transformer in, 281, **285**
  - antenna matching tuner in, 281, **285**
  - connection to receiver in, 274–276, **275, 276**
  - dipole as, 272, **273**, 274
  - directional wire antenna in, 281–286, **284**
  - directivity of, 272
  - flattop antennas for, 279, **280**
  - gain in, 272
  - grounding for, 276, **277**, 278–279, **279**
  - interference and, 272, **273**, 274
  - isotropic radiation in, 272
  - law of reciprocity in, 271
  - longwire antennas for, 277–278, **278**
  - mounting for, 277–278, **278**
  - multiband wire vertical antennas for, 281, **282, 283**
  - omnidirectionality in, 272, **273**
  - phase-switching antenna matcher in, 284, **285**
  - phasing box for, 284, **286**
  - properties of importance in, 271–274
  - radio direction finding (RDF) antennas for, 444–446
  - safety issues in, 276, **277**, 279
  - skip propagation and, 274
  - transformers in, 281
  - vertical antennas for, 279–281, **280, 282, 283**
- shunt feed systems, 200, 507
- side scatter, 52
- sidelobes in microwave waveguides and antennas, 400, **400, 401**
- signal-to-noise ratio (SNR), 37, 45, 246
- simple refraction, 29
- single-sideband (SSB), 55, 495
- skin effect, 369, 371
- skip distance, 47–48, **48**, 47
- skip propagation, 5, 29, 37, 41, 47–48, **48, 49, 51**, 55
  - radio direction finding (RDF) antennas and, 444–446
- skip propagation (*Cont.*):
  - shortwave reception antennas and, 274
  - vertically polarized HF antennas and, 176–179, **178**
  - VHF/UHF transmitting/receiving antennas and, 339
- skip zone, 47–48, **48**
- sky noise sources, 419–420
- sky wave, 47–48, **48, 49**, 302
- skyhook VHF/UHF antennas, 362–368, **363**
- slip-up tower, 567–568, **568, 569**
- sloping (“sloper” or “slipole”) dipole, 153–154, **154, 155**, 236, **238**
  - half-delta sloper (HDS), 295–296, **296**
  - off-center-fed nonresonant sloper (OCFS), 164, **164**
  - vee-sloper antenna in, 168–169, **168**
- slot array antennas, 411–413, **413**
- Smith charts, 95–121, **96**
  - absorbed power (P_a) in, 113–114
  - admittance in, 100, 112, 114
  - angle of reflection coefficient circle in, **103**, 106, 112
  - angle of transmission coefficient circle in, **103**, 106
  - applications for, 109–121
  - capacitive reactance in, 100, **102**, 117
  - complex admittance in, 105
  - components of, 95–109
  - constant reactance circles in, 100–105
  - constant resistance circles in, 97–100, **99**
  - frequency in, 117–121, **119, 120**
  - impedance and impedance matching, 110–112, **111**, 115, 119–121, **119**
  - impedance radius in, 100
  - inductive reactance in, 100, **101**, 117
  - isoresistance circles in, 97–100, **99**
  - loss coefficient scale in, 109, 112–113
  - lossy circuits and, 117, **118**
  - normalized impedance line in, 95–97, **98**

Smith charts (*Cont.*):
  pure reactance circle in, 100, **103**
  pure resistance line in, 95–97, **98**
  radially scaled parameters in, 106–109, **107**
  reactance in, 109, 117
  reflection coefficient in, 106–109, 114
  reflection loss in, 113–114
  return loss in, 108–109, 113, 114
  standing wave ratio (SWR) in, 108
  stub matching systems problems solved using, 109, 114–117, **115, 116**
  susceptance in, 117
  transmission line problems solved using, 109–114
  transmission loss coefficient (TLC) in, 112, 114
  transmission loss in, 108–109
  unity resistance circle in, 100
  voltage standing wave ratio (VSWR) circle in, 100, **104**, 112, 114, 115, 117
  wavelength calculation in, 110, 115
  wavelength circles in, **103**, 105
Smith, Phillip H., 95
soil conductivity, 27, 28*t*, 575–577, 576*t*, **576**, 577
solar flares vs. radio propagation, 37, 39, 46–47
solar flux index (SFI), 40
solar storms, 47
solid-state array antennas, 408–411
SOS, 2
southern lights, 54
space diversity, high–frequency dipoles and doublets, 160
space quadrature fields, 127
space waves, 17–19, **18**
spark–gap transmitters, 2
spatial diversity, 55, **57**
SPC transmatch network, 463, **463**
“spider web” ground system, vertically polarized HF antennas, 185, **188**
splash plates, parabolic “dish” antennas, 408
split frequencies, loop antennas, small receiver-type, 302
split-capacitor networks, 461–462, **462**
spoiler loop, loop antennas, small receiver-type, 313, **314**
sporadic E propagation, 41, 46
sports fan’s loop antennas, small receiver-type, 309
spreaders, multiband and tunable-wire antennas, 206
square loop (1λ) large antenna, 290–293, **290**
square loop transmitter antenna, 319, **320**
stacked dipoles, 160–163, **162**
stagger tuning in high–frequency dipoles and doublets, 157
standard refraction, 25
standing wave antennas, 220
standing wave ratio (SWR), 434
  in high–frequency dipoles and doublets, 144
  in Smith charts, 108
  in transmission lines, 86–91, **90**
standing waves, 87, 127–131, **130, 131**
  current, 134, **135**, 136, **137**, 139
  in high–frequency dipoles and doublets, 144
  measurement of, 137, 138
  in transmission lines, 71, **72, 73**
  voltage, 134–136, **135, 136**, 139
station grounding, 579–580, **581**
stationary waves, 128
steady-state ac response, transmission lines, 70, 79–82, **81**
steerable notch Beverage antennas, 229, **229**
step–function response, transmission lines, 70–71, **70, 71**
stirrup-end mounting hardware, 558, **559**
storms, ionospheric, 47
strain relief, 553–554, **554**
stratosphere, 14, **15**, 18
stray capacitance, 138
stripline or microstripline, 63, **64**, 66–67
stub matching systems, 114–117, **115**, 465–466, **466, 467**
  impedance matching in, 115
  length of stub calculation in, 117
  shorted stubs, 114
  Smith charts for, 109, 114–117, **115, 116**
stub matching systems (*Cont.*):
  in VHF/UHF transmitting/receiving antennas, 345–346, **345**
  voltage standing wave ratio (VSWR) in, 115, 117
  wavelength calculation in, 115
subrefraction, 31, **32**, 36
sudden ionospheric disturbances (SIDs), 46–47
summation interferometer array antenna, 431, **431**
sunspots vs. radio propagation, 40–41, **40**, 43, 46, 47
superrefraction, 29, **31**, 26
support posts, 565, **565**
support ropes, 551
suburban lot installation plan, **545**
surface waves, 17–19, **18**, 27–29
surge impedance (*See* characteristic impedance)
susceptance, Smith charts, 117
switched-pattern RDF antenna, 454–456, **454**
SWR analyzer, 434

T
360-degree directional array, 250, **253**, 254*t*
tapped balun, 476, **477**
tee antennas, 511, **512, 513**
tee-network transmatch, 463, **463**
Teflon, 61, 62
telegraph, 1, 2
telescoping antennas, emergency operations, 491
television, 3, 32
television interference/broadcast interference (TVI/BCI), 214
television-scanner VHF/UHF antennas, 360–362, **361**
temperature effect on propagation, 29–32, **32**
temporary antenna construction, emergency operations, 487–488, **488**
temporary mast mount for emergency antennas, 492, **493**
terminated longwire antennas, 220, **221**
terminations for microwave waveguides and antennas, 385–388
terrain effects, 28, 32, **33**
thermal agitation noise, 417

thermal noise, 68, 417–420
thermocouple for RF ammeter, 530, **530**
Thorne array antenna, 267–269, **268, 269**
three-dimensional (ideal) radiation pattern, dipoles and doublets, 147–148, **147**
tilt angle of surface wave, 28, 28*t*
tilt angle, rhombic beam longwire, 223
tilted, center-fed, terminated, folded dipole (TCFTFD or T^{2}FD, TTFD), 166–168, **167**
time difference of arrival (TDOA) array antenna, 452–454, **453**
time domain reflectometry (TDR), 75–79, **76, 77, 78, 79, 80, 81**
time quadrature fields, 127
time-of-day variations in radio propagation, 14, 16, 32, 39–41, 43, 46, 51, 178
top-loaded mobile antenna, 481, **482**
toroid broadbanded transformers, 475–477, **476**
toroid cores, 471, **472**, 474
toroidal transformers, 471–475, **472**
towers, **538**, 565–572
  fold- or tilt-over, 567, **567**
  gin pole to raise, 570, **571**
  guy wires and ground stakes for, 570, **572**
  hinged baseplate, **538**, 566–567
  impedance matching in, 507, **508**
  low-frequency operation antennas, loaded tower designs for, 507
  masts and supports for, 556–559, **557, 558**
  pedestals for, 568–570, **569**
  raising of, 570, **570, 571**
  safety issues in, 543–548
  slip-up, 567–568, **568, 569**
transducer action, microwave waveguides and antennas, 394
transformer loop antennas, 306–307, **306**
transformers, 199–200
  core material in, 474
  current transformer wattmeter in, 534–538, **535, 536, 537**
transformers (*Cont.*):
  in directional phased vertical antennas, 249–250, **250, 251**
  feeding type, 476, **477**
  ferrite rods in, 475, **475**
  in high–frequency dipoles and doublets, 146
  multi-impedance balun and, 476, **477**
  in multiband and tunable-wire antennas, 210, **211**
  multifilar windings in, 472
  in shortwave reception antennas, 281
  tapped balun and, 476, **477**
  toroid core mounting in, 471, **472**, 474
  toroid broadbanded, for impedance matching, 475–477, **476**
  toroidal type, 471–475, **472**
  in transformer loop antennas, 306–307, **306**
  trifilar windings in, 472
  turns in, 474
  in VHF/UHF transmitting/receiving antennas, 341–346, **342, 343**
  windings in, 472–473, **473**
transmatch circuits, 208–209, **209**, 462–471, **462**
transmission lines, 59–94, 516–517
  absorbed power (P_a) in, 113–114
  adjustments to, 433–438
  admittance in, 112, 114
  air-articulated line as, 62–63, **63**
  angle of reflection in, 75
  antinodes in, 87
  attenuation constant of, 82
  balanced transmission line and, 208
  cable TV, 67
  capacitance in, 64, 69
  characteristic impedance (Z_o), 64–67, 89
  coaxial cable, 59, 61–62, **61, 62**, 66, 69, 208
  (*See also* coaxial cable)
  conductance in, 64
  current standing wave ratio (ISWR) in, 88
  cutoff frequency (F_o) in, 69
  dielectric loss in, 369
  double-shielded coaxial as, 63, **63**
transmission lines (*Cont.*):
  electrical vs. physical length of, 67–68
  equivalent circuit for, **64**, 516, **517**
  gas-filled line as, 62, **63**
  half-wavelength line as, 83
  hardline as, 62, **62**
  helical line as, 62
  impedance and impedance matching, 71, 72, 82–86, 109–112, **111**
  impedance matching network (Q section) in, 85
  incident power (P_I) in, 89
  inductance in, 64
  installation tips for, 433–438
  insulators in, 61
  load impedance in, 109–110
  longwires and, 217–218
  “looking-in” impedance of, 82–86
  loss coefficient scale in, 112–113
  loss in, 83–84, 91–94, 369
  measurement and adjustment techniques for, 516–517, 525
  mismatch (VSWR) losses in, 91–94
  multiband and tunable-wire antennas and, feeding, 208–212
  nodes in, 87
  noise and, 68–69
  ohmic loss in, 369
  Ohm’s law and, 74
  open line as, 59
  parallel lines as, 59–63, **60**, 65–66
  phase constant of, 82
  propagation constant of, 82
  Q section in, 85
  quarter-wavelength lines as, 84–85
  quarter-wavelength shorted stubs in, 86, **87, 88**
  radiation loss in, 369
  reactance in, 85–86, 109, 525
  rectangular waveguide using parallel type, 370–373, **371**
  reflected power (P_r) in, 89
  reflection coefficient in, 71–79, 89, 112, 114
  reflection loss in, 113–114
  resistance in, 64, 525
  responses in, 70–94
  return loss in, 113, 114
  RLC networks and, 59

- transmission lines (*Cont.*):
  - shielded parallel line as, 66
  - shielded twin lead as, 61, **61**
  - shorted lines and, 87
  - shorted stubs, 86, **87**, 114
  - (*See also* stub matching systems)
  - skin effect in, 369
  - Smith charts for, 109–114
  - standing wave ratio (SWR) in, 86–91, **90**
  - standing waves in, 71, **72, 73**, 87
  - steady-state ac response in, 70, 79–82, **81**
  - step–function response in, 70–71, **70, 71**
  - stripline or microstripline as, 63, **64**, 66–67
  - stub matching systems (*See* stub matching systems)
  - surge impedance (Z_o) in, 516
  - time domain reflectometry (TDR) measurements in, 75–79, **76, 77, 78, 79, 80, 81**
  - transmission loss coefficient (TLC) in, 112, 114
  - troubleshooting tips for, 433–438
  - twin lead as, 59, **60**
  - velocity factor of, 67–68, 68*t*, 525
  - voltage minima and maxima in, 87
  - voltage standing wave ratio (VSWR) in, 88–94, **90**, 112, 114, 517, **518**
  - waveguides vs., 86
  - wavelength calculation in, 110
- transmission loss, using Smith charts, 108–109
- transmission loss coefficient (TLC), 112, 114
- transmitters, 123
- transmitting antennas, small loops (*See* loop antennas, small transmitter-type)
- transverse electric mode (TE mode) in microwave waveguides and antennas, 375
- transverse electromagnetic (TEM) fields, 9, 69, 373–375
- transverse magnetic mode (TM mode) in microwave waveguides and antennas, 375
- trap dipoles, 204–206, **204, 205**
- traveling wave antennas, 220, 223
- traveling waves, 127, 128–129, **129**, 134
- trenching to apply chemical soil-conductivity improvers, 576, **576**
- triangle loop (1λ) large antenna, 290–293, **291**
- triangulation of radio signal, 302, 439
- trifilar windings in transformers, 472
- tropical band, Beverage or "wave" antenna in, 224–228, **226, 228, 229**
- troposphere, 14, **15**, 29, 51
- tropospheric propagation, 17–19, **18**, 29–32
- troubleshooting tips, 433–438
- true longwire antenna, 217–219, **217**
- tubing construction of vertical dipole,192–194, **193**
- tunability, multiband and tunable-wire antennas, 203
- tunable dipoles, 160
- tunable-wire antennas, 203–212
- tuned circuit measurements, 526
- tuned feeder antennas, 206, **207**
- tuning, 524
  - antenna matching tuner in, 281, **285**
  - of ground wires, 580–581
  - of high–frequency dipoles and doublets, 149–152
  - of longwires, 214, **215**, 215
  - of loop antennas, small receiver-type, 304, 307–309, **308**, 312–313
  - of marine radio antennas, 497–500, **499, 500**
  - of mobile HF antennas, 483–485
  - of multiband and tunable-wire antennas, 203–205
  - of shortwave reception antennas, 281
- tuning antennas, 203
- tuning capacitance and capacitors, loop antennas, small transmitter-type, 320–321
- turns in transformers, 474
- TV receive-only (TVRO) satellite dishes, 421
- twenty–seven day cycle of radio propagation, 46
- twin lead, 59, **60**
- two-meter Yagi VHF/UHF antenna, 352–353, **352**
- two-port phasing transformer for directional phased vertical antennas, 249–250, **250, 251**

U

- U-bolt mounting hardware, 558, **559**
- ultrahigh frequency (UHF), 13, 17–19, 23, 29, 32, 39, 61
  - in loop antennas, small receiver-type, 302
  - in VHF/UHF transmitting/receiving antennas, 339–368
- ultraviolet (UV) radiation, 9, 39
- umbra region, 17
- unity resistance circle, Smith charts, 100
- Universal Coordinated Time (UTC), 55
- upper sideband (USB), 55

V

- varactor tuning, in loop antennas, small receiver-type, 309, **310**
- variation, ionospheric, 45–47
- vee beam longwire antennas, 221–223, **222**
- vee dipole, 236, **239**
- vee-sloper antenna, 168–169, **168**
- velocity factor (V_F), 14, 525
  - of coax, 248
  - of microwave waveguides and antennas, 377–381, **378**
  - of transmission lines, 67–68, 68*t*
- velocity of propagation, 8, 13–14, 137–139, **139**
- vertical antennas (*See* vertically polarized HF antennas)
- vertical coax VHF/UHF antenna, 346–349, **347, 348**
- vertical dipole scanner antenna, 364, **364, 365**
- vertical extent radiation pattern, vertically polarized HF antennas, 179, **180**
- vertical plane radiation pattern, high–frequency dipoles and doublets, 148–149, **148**
- vertical polarization, 12–13, **13**, 27, **28**, 55, 173

vertical polarization (*Cont.*):
  Beverage antenna, 226–227
  helically wound antennas, **239**, 242, **243**
  vertically polarized HF antennas, 173–202
vertically polarized HF antennas, 173–202, **174**
  above-ground mounted, 197
  angle of radiation in, 176–179, **178**
  antenna tuning units (ATU) in, 173
  coaxial vertical antennas in, 191–194, **192, 193**
  coaxial vertical scanner antenna in, 365–368, **367, 368**
  coaxial-fed, **175**
  collinear vertical VHF/UHF antenna, 349, **350**
  collinear vertical antennas in, 191–194, **192**
  construction of, 195–197
  current in, 173, **174**
  delta-fed grounded vertical antenna in, 200–201, **200**
  directionally phased (*See* directional phased vertical antennas)
  “drooping radials” in, 176, **177**
  electric fields in, 173
  electrical connections for,197, **198**, 560–561
  feedpoint circuits for, 197, **198**
  fence posts as supports for vertical antennas, 561–565, **563, 564**
  five-eighths-wavelength antenna, 181, **182**, 183, 197–200
  four/4x4 support posts for, 565, **565**
  gain in, 179–181
  gamma-fed grounded vertical antenna in, 200–201, **201**
  ghost radiator in, 173
  ground losses in, 183
  ground plane vertical antennas in, 176, **177**
  ground-mounted, 176, 195–197, **196**, 561–565, **562**
  grounding and ground system for, 176, 185–187, **188**, 195–197, **196**, 200–201
  half-slope vertical antenna, 238, **240**
vertically polarized HF antennas (*Cont.*):
  half-wave vertical dipole in, 187–191, **190**
  half-wavelength antenna, 181, **182**
  height of antenna in, 181, 187
  helically wound antennas, **239**, 242, **243**
  image antenna in, 173
  impedance and impedance matching, 173, 175–176, 183, **184**, **186**, 195–197, 199–200, **199**
  installation of, 560–572
  insulators in, 175, 195
  isotropic radiation in, 179–181, **181**
  J-pole antennas in, 201
  length of, 181, 183, **184**
  limited-space designs, 238, **240**
  losses in, 183
  low-frequency operation antennas, 502–505, **503**
  mast-mounted, **175**, 194–195, **194, 546**, 560–561, **561, 562**
  mounting, 186, 189–190, 194–197, **194, 196**, 560–565, **561**
  non-ground-mounted, 195, 197
  non-quarter-wavelength verticals in, 181–185
  omega-fed grounded vertical antenna in, 200–201, **202**
  omnidirectionality in, 173, 179–181
  power calculation in, 180
  Q-sections in, 199–200, **199**
  quarter-wavelength antenna, 173, 181, **182**, 183, 187
  radials used in, 176, 186, **189**, 560–561
  radiation patterns in, 178–181, **181, 182**
  radiation resistance in, 183, **184, 185**
  reactance in, 183, **184**
  resistance in, 183
  safety issues, burns or shocks from RF through vertical antennas, 191, 195
  series-fed vertical antennas in, 200
  shortwave reception antennas, 279–281, **280, 282, 283**
vertically polarized HF antennas (*Cont.*):
  shunt-fed vertical antennas in, 200
  skip propagation and, 176–179, **178**
  “spider web” ground system for, 185, **188**
  tower installation, **538**, 565–572
  transformers in, 199–200
  tubing construction of vertical dipole,192–194, **193**
  vertical coax VHF/UHF antenna, 346–349, **347, 348**
  vertical dipole scanner antenna in, 364, **364, 365**
  vertical extent radiation pattern in, 179, 180
  VHF/UHF transmitting/receiving antennas, 340–341
  voltage in, 173, **174**
  voltage standing wave ratio (VSWR) in, 176, 195
  window-sill antennas, 238, **241**
  Yagi antennas and, 201
very high frequency (VHF), 13, 17–19, 23, 29, 30, 32, 39, 41, 46, 54, 55, 170–171
  emergency operations antennas and, 487
  loop antennas, small receiver-type and, 302
  marine radio antennas and, 495
  vertically polarized HF antennas and, 191
  VHF/UHF transmitting/receiving antennas and, 339–368
very low frequency (VLF), 29, 55, 61
  Beverage or “wave” antenna in, 224–228, **226, 228, 229**
VHF/UHF transmitting/receiving antennas, 339–368
  baluns in, 341–346, **342, 343**
  bandwidth of, 339
  beam antennas in, 349–352, **351, 352**
  “bowtie” dipoles in, **361**, 362
  citizens’ band antennas as, 341
  coaxial vertical antenna for, 346–349, **347, 348**
  coaxial vertical scanner antenna in, 365–368, **367, 368**
  collinear vertical antenna, 349, **350**

VHF/UHF transmitting/receiving antennas (*Cont.*):
- delta feed match for, 343, **344**, 345
- design limitations in, 340
- directivity in, 349
- drooping dipole scanner antenna in, 363, **363**
- effective radiated power (ERP) in, 349
- five-eighths-wavelength 2-meter antenna for, 353, **354**
- folded dipoles in, 362, **362**
- frequency spectrum of, 339, 341
- gain in, 349
- gamma match system for, 346, **346**
- groundplane antenna for, 356, **357**
- groundplane scanner antenna in, 364, **366**
- halo antenna for, 356, **358**
- impedance matching in, 341–346, **342**
- J-pole antenna for, 353–355, **355**
- length of, 339
- line-of-sight communications and, 339
- longwires as, 340–341
- low frequency (LF) vs., 339
- lower band antennas on VHF/UHF, 340–341
- mounting, 347
- OSCAR satellite communications and, 339
- quad beam antenna for, 356, 358, **359**
- safety issues in, 340
- satellite communications and, 339
- scanner band antennas, 360–368
- scanner skyhook antennas in, 362–368, **363**
- scanner-vision antennas in, 360–362, **361**
- size of, as limiting factor, 340
- skip propagation in, 339
- stub matching system for, 345–346, **345**
- transformers in, 341–346, **342, 343**
- two-meter Yagi antenna, 352–353, **352**
- vertical antennas as, 340–341
- vertical dipole scanner antenna in, 364, **364, 365**

VHF/UHF transmitting/receiving antennas (*Cont.*):
- voltage standing wave ratio (VSWR) in, 341
- wavelength in, 339
- Yagi antennas in, 349–352, **351, 352**

virtual height, 43, **44, 45**

voltage, 123–120, 131–137, **132, 133**, 531
- (*See also* voltage standing wave ratio)
- in high–frequency dipoles and doublets, 143–146, **143**
- lag, 126
- in loop antennas, small receiver-type, 303, 304
- in loop antennas, small transmitter-type, 320, 323
- minima and maxima of (*See* antinodes; nodes)
- standing waves of, 134–136, **135, 136**, 139
- in vertically polarized HF antennas in, 173, **174**

voltage standing wave ratio (VSWR), 88–91, **90**, 515, 517–519, 529, 532
- calculation of, 517–519
- EZNEC for Windows modeling of, 337, **338**
- frequency vs., 434–437, **435**
- in hidden and limited-space antennas, 238
- in high–frequency dipoles and doublets in, 144, 146, 149–151, **150**, 160
- in longwires, 215
- in loop antennas, small transmitter-type, 320
- measurement of, 433, 435–437, **436**, 529, 532
- in microwave waveguides and antennas, 388
- in mobile HF antennas, 483
- in multiband and tunable-wire antennas, 203
- NECWin Basic modeling of, 333, **335**
- using Smith charts circle, 100, **104**, 112, 114, 115, 117
- in stub matching systems, 115, 117
- in transmission lines, 91–94, 112, 114, 517, **518**

voltage (*Cont.*):
- in vertically polarized HF antennas, 195
- in VHF/UHF transmitting/receiving antennas, 341
- in Yagi antennas, 261

W

water analogy of radio wave propagation, 6–7

Watson-Watt Adcock array antennas, 447–450, **449, 450**

wattmeters, 529–539, **531, 533, 534, 535, 536, 537, 538**

waveguides, 86, 369–415
- (*See also* microwave waveguides and antennas)

wavelength calculation, using Smith charts, **103**, 105, 110, 115

wavelength, 7–8, 28
- high–frequency dipoles and doublets, 141–142
- longwires, 217, 218–219
- microwave waveguides and antennas, 377–381, **378**
- VHF/UHF transmitting/receiving antennas, 339

“wave” antenna, 224–228, **226, 228, 229**

weather–related propagation phenomena, 28, 36

wedge dummy loads, in microwave waveguides and antennas, 385, **386, 387**

Wheatstone bridge, 519–521, **520**

whip antennas for marine radio, 496–497, **497**

wide-aperture direction finder (WADF), 451

windings in transformers, 472–473, **473**

Windom antenna, 209–210, **211**

Windom, Loren, 209

window-sill antennas, 238, **241**

wire antenna, basic design, 548, **548**

wire used in longwires, 214

wireless telegraphy, 1–2

Wolf Number, 40

World Administrative Radio Conferences (WARC), 2

Wullenweber array antennas, 451, **452**
WWV radio station, 40, 47
WWVH radio station, 40

X
X bands, 69
x-ray radiation, 39

Y
Yagi antennas, 203, 257–262, **259**, 421
  capacitors in, 261
  directors in, 258–259
  feedpoints, 260–261, **261**
Yagi antennas (*Cont.*):
  gamma match feed system for, 260–261, **261**
  impedance matching in, 260–261, **261**
  length of, 259–260
  noise and VSWR in, 261
  parasitic elements in, 258–259
  quad beam antennas vs., 265
  radiation pattern of, 257–258, **258**
  reflectors in, 258–259
  two-meter Yagi VHF/UHF antenna, 352–353, **352**
  vertically polarized HF antennas, 201
Yagi antennas (*Cont.*):
  VHF/UHF transmitting/receiving antennas, 349–352, **351, 352**
  Yagi-Uda antenna, 258

Z
Zepp antenna, 164–165, **165**, 171
  end-fed multiband, 208, **208**
zipcord, 275
ZL-special beam antenna, 20-m, 262–263, **262**
Zurich Smoothed Sunspot Number, 40

About the Author

Joe Carr was a military electronics technician and author. Along with the best-selling *Practical Antenna Handbook*, his other books with McGraw-Hill include *Secrets of RF Circuit Design*. Carr also contributed a monthly column to *Nuts & Volts* magazine entitled “Open Channel.”

This page intentionally left blank

This page intentionally left blank

SOFTWARE AND INFORMATION LICENSE

The software and information on this diskette (collectively referred to as the "Product") are the property of The McGraw-Hill Companies, Inc. ("McGraw-Hill") and are protected by both United States copyright law and international copyright treaty provision. You must treat this Product just like a book, except that you may copy it into a computer to be used and you may make archival copies of the Products for the sole purpose of backing up our software and protecting your investment from loss.

By saying "just like a book," McGraw-Hill means, for example, that the Product may be used by any number of people and may be freely moved from one computer location to another, so long as there is no possibility of the Product (or any part of the Product) being used at one location or on one computer while it is being used at another. Just as a book cannot be read by two different people in two different places at the same time, neither can the Product be used by two different people in two different places at the same time (unless, of course, McGraw-Hill's rights are being violated).

McGraw-Hill reserves the right to alter or modify the contents of the Product at any time.

This agreement is effective until terminated. The Agreement will terminate automatically without notice if you fail to comply with any provisions of this Agreement. In the event of termination by reason of your breach, you will destroy or erase all copies of the Product installed on any computer system or made for backup purposes and shall expunge the Product from your data storage facilities.

LIMITED WARRANTY

McGraw-Hill warrants the physical diskette(s) enclosed herein to be free of defects in materials and workmanship for a period of sixty days from the purchase date. If McGraw-Hill receives written notification within the warranty period of defects in materials or workmanship, and such notification is determined by McGraw-Hill to be correct, McGraw-Hill will replace the defective diskette(s). Send request to:

Customer Service
McGraw-Hill
Gahanna Industrial Park
860 Taylor Station Road
Blacklick, OH 43004-9615

The entire and exclusive liability and remedy for breach of this Limited Warranty shall be limited to replacement of defective diskette(s) and shall not include or extend to any claim for or right to cover any other damages, including but not limited to, loss of profit, data, or use of the software, or special, incidental, or consequential damages or other similar claims, even if McGraw-Hill has been specifically advised as to the possibility of such damages. In no event will McGraw-Hill's liability for any damages to you or any other person ever exceed the lower of suggested list price or actual price paid for the license to use the Product, regardless of any form of the claim.

THE McGRAW-HILL COMPANIES, INC. SPECIFICALLY DISCLAIMS ALL OTHER WARRANTIES, EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO, ANY IMPLIED WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE. Specifically, McGraw-Hill makes no representation or warranty that the Product is fit for any particular purpose and any implied warranty of merchantability is limited to the sixty day duration of the Limited Warranty covering the physical diskette(s) only (and not the software or in-formation) and is otherwise expressly and specifically disclaimed.

This Limited Warranty gives you specific legal rights; you may have others which may vary from state to state. Some states do not allow the exclusion of incidental or consequential damages, or the limitation on how long an implied warranty lasts, so some of the above may not apply to you.

This Agreement constitutes the entire agreement between the parties relating to use of the Product. The terms of any purchase order shall have no effect on the terms of this Agreement. Failure of McGraw-Hill to insist at any time on strict compliance with this Agreement shall not constitute a waiver of any rights under this Agreement. This Agreement shall be construed and governed in accordance with the laws of New York. If any provision of this Agreement is held to be contrary to law, that provision will be enforced to the maximum extent permissible and the remaining provisions will remain in force and effect.

Radio and Electronics Cookbook

Radio and Electronics Cookbook

Edited by
Dr George Brown, CEng, FIEE, M5ACN

Newnes
OXFORD AUCKLAND BOSTON JOHANNESBURG MELBOURNE NEW DELHI

Newnes
An imprint of Butterworth-Heinemann
Linacre House, Jordan Hill, Oxford OX2 8DP
225 Wildwood Avenue, Woburn, MA 01801-2041
A division of Reed Educational and Professional Publishing Ltd

A member of the Reed Elsevier plc group

First published 2001

© Radio Society of Great Britain 2001

All rights reserved. No part of this publication may be reproduced in any material form (including photocopying or storing in any medium by electronic means and whether or not transiently or incidentally to some other use of this publication) without the written permission of the copyright holder except in accordance with the provisions of the Copyright, Designs and Patents Act 1988 or under the terms of a licence issued by the Copyright Licensing Agency Ltd, 90 Tottenham Court Road, London, England W1P 0LP. Applications for the copyright holder's written permission to reproduce any part of this publication should be addressed to the publishers

British Library Cataloguing in Publication Data
A catalogue record for this book is available from the British Library

ISBN 0 7506 5214 4

RSGB
Lambda House
Cranborne Road
Potters Bar
Herts
EN6 3JE

Composition by Genesis Typesetting, Laser Quay, Rochester, Kent
Printed and bound in Great Britain

PLANT A TREE
BTCV
British Trust for Conservation Volunteers
FOR EVERY TITLE THAT WE PUBLISH, BUTTERWORTH-HEINEMANN WILL PAY FOR BTCV TO PLANT AND CARE FOR A TREE.

Contents

Preface ix

1. A medium-wave receiver 1
2. An audio-frequency amplifier 4
3. A medium-wave receiver using a ferrite-rod aerial 9
4. A simple electronic organ 12
5. Experiments with the NE555 timer 17
6. A simple metronome 21
7. What is a resistor? 24
8. Waves – Part 1 27
9. A beat-frequency oscillator 31
10. What is a capacitor? 34
11. Waves – Part 2 38
12. An LED flasher 41
13. Waves – Part 3 44
14. Choosing a switch 46
15. An aerial tuning unit for a receiver 49
16. A simple 2 m receiver preamplifier 52
17. Receiving aerials for amateur radio 54
18. The Colt 80 m receiver – Part 1 58
19. A crystal radio receiver 62
20. The varactor (or varicap) diode 64
21. A portable radio for medium waves 65
22. The Colt 80 m receiver – Part 2 70

23. A simple transistor tester 73
24. An introduction to transmitters 77
25. The Colt 80 m receiver – Part 3 81
26. A two-way Morse practice system 88
27. The Colt 80 m receiver – Part 4 91
28. A simple crystal set 95
29. A crystal calibrator 100
30. A simple short-wave receiver – Part 1 104
31. A fruit-powered medium-wave radio 106
32. A capacitance bridge 109
33. A simple short-wave receiver – Part 2 113
34. A basic continuity tester 117
35. A charger for NiCad batteries 119
36. An 80 metre crystal-controlled CW transmitter 123
37. A solar-powered MW radio 129
38. A receiver for the 7 MHz amateur band 133
39. Diodes for protection 137
40. An RF signal probe 140
41. An RF changeover circuit 142
42. A low-light indicator 146
43. A J-pole aerial for 50 MHz 149
44. Measuring light intensity – the photometer 153
45. A 70 cm Quad loop aerial 156
46. A UHF field strength meter 160
47. Christmas tree LEDs 162
48. An audio signal injector 166
49. Standing waves 168
50. A standing-wave indicator for HF 170
51. A moisture meter 174
52. Simple aerials 177
53. A breadboard 80 cm CW transmitter 182

54. A 7-element low-pass filter for transmitters 186
55. Radio-frequency mixing explained 189
56. A voltage monitor for a 12 V power supply 192
57. A 1750 Hz toneburst for repeater access 196
58. A circuit for flashing LEDs 201
59. Digital logic circuits 205
60. A resistive SWR indicator 210
61. An audio filter for CW 213
62. An electronic die 215
63. The absorption wavemeter 222
64. An HF absorption wavemeter 224
65. A vertical aerial for 70 cm 228
66. A UHF corner reflector aerial 230
67. A switched dummy load 234
68. A simple Morse oscillator 238
69. A bipolar transistor tester 240
70. The ‘Yearling’ 20 m receiver 245
71. Adding the 80 metre band to the Yearling receiver 251
72. How the Yearling works 255
73. A field strength meter 258
74. Preselector for a short-wave receiver 261
75. An audible continuity tester 265
76. An experimental 70 cm rhombic aerial 268
77. Water level alarm 272
78. A delta loop for 20 metres 275
79. A simple desk microphone 279
80. Morse oscillator 284
81. A simple 6 m beam 287
82. An integrated circuit amplifier 291
83. A novice ATU 293
84. CW QRP transmitter for 80 metres 297

85. An audio booster for your hand-held 303
86. A grid dip oscillator 306
87. A CW transmitter for 160 to 20 metres 312
88. Matching the end-fed random-wire aerial 315

Preface

Although we are surrounded by sophisticated computerised gadgets these days, there is still a fascination in putting together a few resistors, capacitors and the odd transistor to make a simple electronic circuit. It is really surprising how a handful of components can perform a useful function, and the satisfaction of having built it yourself is incalcuable.

This book aims to provide a wide variety of radio and electronic projects, from something that will take a few minutes to a more ambitious weekend's worth. Various construction techniques are described, the simplest requiring no more than a small screwdriver, the most complex involving printed circuit boards.

Originally published by the Radio Society of Great Britain, the projects were all chosen to be useful and straightforward, with the emphasis on practicality. In most cases the workings of the circuit are described, and the projects are backed up by small tutorials on the components and concepts employed. In the 21st century it may seem strange that few of the published circuits use integrated circuits (chips). This is intentional as it is much easier to understand how the circuit works when using discrete components.

Anyone buying the *Radio and Electronics Cookbook* will find that it will lead to hours of enjoyment, some very useful and entertaining gadgets, and increased knowledge of how and why electronics circuits work, and a great sense of satisfaction. Beware, electronic construction is addictive!

WARNING: This book contains construction details of transmitters. It is illegal to operate a transmitter without the appropriate licence. Information on how to obtain an Amateur Radio Licence can be obtained from the Radiocommunications Agency, tel. 020 7211 0160.

1 A medium-wave receiver

Introduction

Let us start off with something that is really quite simple and yet is capable of producing a sense of real satisfaction when complete – a real medium-wave (MW) radio receiver! It proves that receivers *can* be simple and, at the same time, be useful and enjoyable to make. To minimise the confusion to absolute beginners, *no* circuit diagram is given, only the constructional details. The circuits will come later, when you have become accustomed to the building process. In the true amateur spirit of ingenuity and inventiveness, the circuit is built on a terminal strip, the coil is wound on a toilet roll tube (as amateur MW coils have been for 100 years!), and the receiver is mounted on a piece of wood.

Putting it together

Start by mounting the components on the terminal strip as shown in **Figure 1**, carefully checking the position and value of each one. The three capacitors are all the same, and so present no problem. They (and the resistors) may be connected either way round, unlike the two semiconductors (see later). The resistors are coded by means of coloured bands. You can refer to Chapter 7 if you have difficulty remembering the colours and their values.



Figure 1 Terminal strip – position of components

1.	Brown, Black, Yellow	100 000 ohms	(R1, R5, R6)
2.	Green, Blue, Brown	560 ohms	(R2)
3.	Red, Violet, Brown	270 ohms	(R3)
4.	Brown, Black, Orange	10 000 ohms	(R4)

The integrated circuit (the ZN414Z) and the transistor (the BC184) *must* be connected correctly. Check Figure 1 carefully before fitting each device.

Now wind the coil. Most tubes are about 42 mm diameter and 110 mm long. Don't worry if your tube is slightly different; it shouldn't matter. Make two holes, about 3 mm apart, about 40 mm from one end, as shown in **Figure 2**. Loop your enamelled wire into one hole and out of the other, and draw about 100 mm through; loop this 100 mm through again, thus anchoring the wire firmly. Now wind on 80 turns, keeping the wire tight and the turns close together but not overlapping. After your 80th turn, make another two holes and anchor the wire in the same way as before. Again, leave about 100 mm free after anchoring. Using another piece of enamelled wire (with 100 mm ends as before), loop one end through the same two holes which contain the end anchor of the last winding, wind two turns and anchor the end of this short winding using another pair of holes. Figure 2 shows the layout.



Figure 2 The layout of the parts on the wooden base

With some glass paper, remove the enamel from the ends of both pieces of wire which go through the same holes (i.e. the bottom of the large coil and the top of the small coil), then twist these bare ends together. Remove the enamel from the remaining ends of the coil. The coil is now finished!

The baseboard can be any piece of wood about 150 mm square. Fix the coil near the back edge using drawing pins and connect the wires from the coils to the terminal strip as shown in Figure 2. Using short pieces of PVC-insulated wire (and with assistance if you have never soldered before), solder one piece across the two outer tags of the variable capacitor, shown by the dotted line in Figure 2, and then two longer pieces to the centre tag and one outside tag. Connect these to the terminal strip. Then solder two more insulated wires on to the jack socket (into which you will plug your crystal earpiece), the other ends going to the terminal strip. The last two wires (one must be red) need to be soldered on to the battery box, their other ends going to the terminal strip also. Make sure the red wire goes to the *positive* terminal on the battery, and is connected to terminal 9. The other connection to the battery goes to terminal 10.

Attach the terminal strip to the baseboard with small screws or double-sided sticky tape. The other parts can be mounted the same way.

Listening is done ideally with the recommended crystal earpiece. Don't be tempted to use your Walkman earpieces; they are not the same and will not perform anything like as well. The receiver should work without an extra aerial, but one can be attached to terminal 1 if necessary. A long piece of wire mounted as high as possible is ideal. The *Audio-frequency Amplifier* project will enable you to use a loudspeaker with your receiver, using the signal from the jack socket. No circuit modifications will be needed!

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1, R5, R6	10 kilohms (kΩ)
R2	560 ohms
R3	270 ohms
R4	10 kilohms (kΩ)

Capacitors

C1, C2, C3	100 nanofarads (nF)
	500 picofarads (pF)

Semiconductors

ZN414Z, BC184

Additional items
- 12-way 2 A terminal strip
- 22 metres of 28 SWG enamelled copper wire
- A few short pieces of coloured PVC-insulated wire
- Crystal earpiece
- 3.5 mm jack socket
- 1.5 V AA-size battery and box
- Toilet roll tube
- Double-sided sticky tape or selection of screws

Tools required

Small screwdriver, soldering iron.

2 An audio-frequency amplifier

Introduction

This simple amplifier can be built by anyone who is able to solder reasonably well. It doesn't require any setting up and, provided our instructions are followed exactly, will work very well. The circuit diagram is included for the benefit of our more advanced readers, but it is not needed in the construction process. Please practise your soldering before you start, and don't use a printed circuit board (PCB) until you are confident that your soldering is up to scratch.

The amplifier can be used with other projects; it will provide plenty of sound from the MW Radio or from the Morse Sounder projects. It will usually be built into other pieces of equipment, so a box is not supplied with the kit. There is no reason why it shouldn't be put into a box and used as a general-purpose amplifier to help test other projects.

The components

Before you start, you should check that you have *all* the components to hand. A list and some helpful hints are given below.

1. PCB. The plain side is the *component side* and the soldered side is the *track side*. **Figure 1** shows the track side full size. Make the PCB from the pattern given in Figure 1. Otherwise, build the circuit on a matrix board.
2. Three resistors. Locate the gold or silver band around the resistor, and turn the resistor until this band is to the right. There are three coloured bands at the left-hand end of the resistor. Find the resistor whose colours are YELLOW, VIOLET, RED, and look at the resistor colour code chart which you will find in Chapter 7. From this, you will see that YELLOW indicates the value 4, VIOLET the value 7, and RED the value 2. The first two colours represent real numbers, and the last value is the number of zeros (noughts) which go *after* the two numbers. So, the value is 47 with two zeros, i.e. 4700 ohms. In this way, the resistor coloured BROWN, GREY, BROWN has a value of 180 ohms, and the last one, BROWN, RED, GREEN, has a value of 1 200 000 ohms. The ohm (often written as the Greek letter omega (Ω)) is the unit of resistance. If you do not yet feel confident in identifying resistors by their colours, use the Resistor Colour Codes given in Chapter 7.
3. Four capacitors. The two small 'beads' are tantalum capacitors and will be marked 4.7 µF or 4µ7, with a '+' above one lead. A tubular capacitor with wires coming from each end should be marked 220 µF, with one end marked '+' or '–'. This is called an *axial* capacitor because the wires lie on the axis of the cylinder. This is in contrast to the final capacitor, where both wires emerge from the same end. This is a *radial* capacitor, and will be marked 47 µF. Again, one lead will be marked '+' or '–'. Capacitors marked like this are said to be *polarised*, and it is vital that these are placed on the PCB the right way round, so take notice of those signs!
4. Two diodes. These are tiny glass cylinders with a band around one end, and may be marked 1N4148; this is their type number. Like polarised capacitors, they *must* be put on the PCB the correct way round!



Figure 1 The toil pattern of the PCB – looking from the track side

5. Three transistors. One should be a BC548 (or a BC182), the other two should be BC558 (or BC212).
6. One volume control with internal switch.
7. One loudspeaker. This is quite fragile – don't let anything press against the cone.
8. One PP3 battery clip with red and black leads.

Putting it together

Lay the PCB on a flat, clean surface with the track side downwards. It is always useful to compare the layout with the circuit diagram, given here in **Figure 3**. Although you can't see it, the D-i-Y Radio sign should be at the top. Compare the hole positions with those shown in **Figure 2**. Bend the resistor wires at right angles to their bodies so that they fit cleanly into the holes in the PCB. Push each resistor towards the board so that it lies flat on the board. Then supporting each one, turn the board over and splay out the wires *just* enough to prevent the resistor falling out. Then, solder each wire to its pad on the PCB, and cut off the excess wire. When you have more confidence, you can cut of the excess wire *before* soldering; it often makes a tidier joint.



Figure 2 Positions of the components on the printed circuit board (PCB)


LOUD-
SPEAKER
R2
4k7
TR3
BC548
C3
47µ
D2
1N4148
R1
180R
C4
220µ
9 V
D1
1N4148
INPUT
C1
4µ7
R3
1M2
TR2
BC558
VR1
25k
Log
C2
4µ7
TR1
BC548
S1 on
back of
VR1

Figure 3 The amplifier's circuit diagram

Now fit the four capacitors. Each must be connected the right way round, so look at each component, match it up with the diagram of Figure 2, bend its wires carefully and repeat the soldering process you performed with the resistors, making sure that the components are close to the board and not up on stilts! Fit the two diodes the correct way round, and solder then as quickly as you can – they don't like to be fried!

Mount the transistors about 5 mm above the PCB. Make sure the correct transistors are in the correct places, and that the flats on the bodies match up with those shown in Figure 2.

Mount the volume control so that the spindle comes out from the front of the board. Use a piece of red insulated wire to the pad marked + on the PCB, and a black piece to the pad marked –, and solder these to the tags on the back of the control, as shown in **Figure 4**. Connect the two leads from the battery clip to the other tags on the switch; Figure 4 will help you. Finally, use two pieces of insulated wire about 100 mm long, twisted together, to connect the loudspeaker to the PCB.


PP3 Battery Clip
RED
BLACK
0V (-)
on PCB
+9 V

Figure 4 Connections to switch on back of VR1

Box clever!

If you wish to put the amplifier into a box, there is no problem; almost any box that is big enough will do. All that is needed is one hole big enough to accept the bush of the volume control; the PCB will be supported by the volume control. The prototype was not fitted into a box, but mounted on an odd piece of aluminium, bent into an L-shape and screwed on to a wooden base. The loudspeaker was mounted on the aluminium panel by two small pieces of aluminium with 3 mm holes drilled in them, which acted as clips around the edge of the speaker. Drill a few holes in the panel in the position of the speaker to let the sound get out!

Your input signal can be connected to the amplifier with two short pieces of wire, but if the connection needs to be long, use screened cable, with the braid connected as shown in Figure 2.

If you decide to use a different loudspeaker, make sure that its impedance (the resistance value marked on the back of the magnet) is at least 35 ohms. Anything lower may damage TR2 and TR3, and will certainly run down your battery very quickly. You will be surprised at the uses you can find for this little amplifier!

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1	180 ohms (Ω)
R2	4.7 kilohms (kΩ)
R3	1.2 megohms (MΩ)
VR1	25 kilohms (kΩ) log with DPST switch

Capacitors: all rated at 25 V minimum

C1, C2	4.7 microfarads (μF)
C3	47 microfarads (μF)
C4	220 microfarads (μF)

Semiconductors

TR1, TR3	BC548 npn
TR2	BC558 pnp
D1, D2	1N4148

Additional items
  PCB
  Speaker >35 ohms
  PP3 battery clip and battery

3 A medium-wave receiver using a ferrite-rod aerial

Introduction

This design came from the Norfolk Amateur Radio Club, and enables you to build a simple Amplitude Modulation (AM) receiver for frequencies between 600 kHz and 1600 kHz. It should take you around 2 hours to build, and can be used with Walkman-type earpieces. **Figure 1** shows the circuit diagram.


On/Off switch
Coil
VC1
Radio chip
ZN416E
1
2
3
4
5
6
7
8
C4
Headphones
Battery
+
−
Wrapped over ferrite rod
C1
C3
C2
HOW IT WORKS
Coil + VC 1
Radio signal
Radio chip + C1, C2, C3 and C4
Sound signal
Headphones
Allows you to select or 'tune' the radio signal
Magnify the radio signal and change it into a sound signal
Change the sound signal into sound you can hear
Battery
Supplies electricity (energy) to keep it all working

Figure 1 Circuit and block diagrams of the radio

Description

The whole circuit is built on a 50 mm by 50 mm printed circuit board (PCB) designed to fit on the inside of the lid of a plastic box, and is stuck there using sticky pads, the shaft of the variable capacitor going through a hole in



Figure 2a The PCB, solder side



Figure 2b The PCB, component side

the lid. Only two pairs of leads are soldered to the board – one pair goes to the 1.5 V battery in its holder, and the other to the earphone socket. **Figures 2a** and **2b** show the printed circuit and the component layout double size for clarity. You are not obliged to build the circuit on a PCB.

Building it

1. **Check and identify components**. Tick the parts list.
2. **Carefully unwind the wire.** Use paper to make an insulating tube (called a 'former') around the centre of the ferrite rod and secure it with Sellotape. Now, close-wind *all* the wire (leave no gaps between adjacent turns) around the paper former. Secure the winding with more Sellotape, leaving 50 mm of wire free at each end for connection to the circuit. See **Figure 3a.**
3. **Solder in VC1.**
4. **Solder in the integrated circuit holder.** There is a notch in one end of the holder; this should face VC1. Solder also the wire link and the capacitors. Be careful to avoid solder 'bridges' between adjacent tracks on the PCB.
5. **Solder the battery leads.** These must be connected properly – the red battery lead to the + (positive) area and the black lead to the – (negative) area.
6. **Strip bare 1 cm of insulation from the ends of two wires**. Solder them between the PCB and the headphone socket (see **Figure 3b**). Use the end tabs on the socket. Using another pair of insulated wires connect the ON/OFF switch to the PCB tabs shown in Figure 2b.



Figure 3 Details of coil and headphone socket

7. **Fix the elastic band.** This goes through the holes at the top of the PCB, with the ferrite rod being slipped through the two end loops. (Note: although the coating on the copper wire is designed to melt away during soldering, it is quite common for difficulty to be experienced in obtaining a good soldered joint; to be on the safe side, remove the coating *before* soldering (with a small piece of sandpaper).) Carefully place the wire ends of the coil through the PCB just above VC1, and solder on the track side.
8. **Fit IC1 into its holder.** This should be done carefully, making sure that *all* the pins are located above their respective clips *before* applying any pressure! Make sure also that the notch on the IC (as shown in Figure 2b) matches the notch in the holder, and faces VC1.
9. **Put battery in its holder.** Listen for some noise in the headphones as VC1 is rotated. Make sure the headphone plug is fully inserted into its socket.
10. **Fix the working board to the lid.** Use the sticky pads and apply *gentle* pressure. Fit the tuning knob, the ON/OFF switch and the earphone socket.
11. **Test again.** If all is still working, fit the lid screws and admire your completed radio!

Parts list

Capacitors	
C1, C2	0.01 microfarad (μF)
C3, C4	0.1 microfarad (μF)
VC1	500 picofarads (pF)
Semiconductor	
IC1	ZN416E

Additional items
- Plastic box (recommended size 76 × 64 × 50 mm internal)
- 8-pin DIL socket for IC1
- Printed circuit board
- Tuning knob for VC1
- Wire link for PCB
- 2 m of 30 SWG copper wire, self-fluxing
- Piece of paper 25 × 50 mm, to make the coil former
- Ferrite rod 70 mm long by 10 mm diameter, approximately
- Battery, AA size 1.5 V, with holder and attached wires
- Miniature earphone socket (3.5 mm stereo jack)
- ON/OFF switch (push-button SPST latched or slide switch)
- 4 off 100 mm insulated connecting wires, for jack socket and ON/OFF switch
- Pair Walkman-type earphones
- Elastic band, to attach ferrite rod to PCB
- 4 off sticky pads for securing PCB to box lid

Kits

Ready-made PCBs may be available from Alan J. Wright, G0KRU, Hewett School, Cecil Road, Norwich NR1 2PL.

4 A simple electronic organ

Introduction

This project has nothing to do with radio but, let's admit it, *any* electronics project is good experience! Why not build this little organ – it will keep the children amused at least! It uses the popular NE555 integrated circuit, which contains a circuit which will periodically switch the voltage on the output pin between the supply voltage and zero. Just how frequently this switching occurs depends upon the components external to the integrated circuit. If this switching occurs several hundred or thousand times a second, the change in voltage produced will generate a musical note when connected to a small loudspeaker. The circuit is shown in **Figure 1**.


+9V
R1
7
4
8
IC1
6
3
P1
P10
2
1
S
(350Ω)
R2
C1
-

Figure 1 Circuit diagram

Putting it together

(a) Using a PCB. The job is very simple. The placement of components on the unsoldered side of the board is shown in **Figure 2** and the design on the copper track is illustrated in **Figure 3**. Put each component, in turn, on the board, making sure that it lies flat on the board with its tags or wires going cleanly through the holes provided for it; then, solder the wires to the board, cropping them before or after the soldering,


C 523
D 587
E 659
F 698
F# 740
G 784
A 880
B 988
C 1046
D 1174
Frequency (Hz)
Solder pins
P1
P2
P3
P4
P5
P6
P7
P8
P9
P10
R1
R2
IC1
C1
+
S
S -
Battery clip
9V
Loudspeaker

Figure 2 Position of components on the printed circuit board (PCB)



Figure 3 The connections

depending on your preference. If you choose to use a holder for your integrated circuit (highly recommended if your soldering is less than perfect), make sure that the end with a notch in it faces R1 and R2, as shown in Figure 2. Solder the two leads to the speaker to the tabs marked S (either way round), having looped them through the two holes to the right of the tabs in Figure 2. Looping them through the holes acts as a strain relief, ensuring that the soldered joints are not subjected to pulling and bending as you move the wires about. Do the same with the battery leads, the red lead going to the + tab and the negative lead to the – tab (which also has one speaker lead already attached to it). **Figure 4** shows this in detail. Treat the loudspeaker with care – the cone is quite fragile and must not be touched.



Figure 4 Battery plug and loudspeaker connections

(b) Without a PCB. This is more difficult, and you may need to enlist some help. Using some matrix board (such as Veroboard) is probably the best way of replacing the PCB. You could arrange your circuit in exactly the same way as in the PCB in Figure 3, using wires to replace the copper track.

A simple ‘keyboard’

The keyboard is a row of solder pins along the rear edge of the PCB, one for each note covering the range shown in Figure 2. A flying lead with a small spade on it is provided to touch any of the pins in turn, producing any one of ten different notes.

Testing

Check first that each component is in the correct place. When inserting the NE555 chip, first make sure that the end carrying the notch lies over the end of the holder with the notch; then, make sure each pin of the chip lies directly above the hole into which it fits, before pressing *gently* to insert the chip into the socket. Make sure the battery connections are correct, and insert the battery into the clip. Nothing should happen, except for a click from the loudspeaker; touching the spade on any of the pins should produce a coarse note from the speaker. If nothing happens, check everything again; don’t *assume* that wires go where you think they go!

After you get the first note, all the others should work, too, but they will sound off-tune at first. The organ needs tuning up by adjusting the 10 preset variable resistors P1 to P10. The approximate frequency to which each note should be tuned is given in Figure 2; if you can beg, borrow or steal a frequency counter, setting up is easy. If you have a piano, the organ can be tuned by comparison of the notes with those on the piano. The frequencies are given in Hertz (abbreviation Hz), and represent the number of times the IC switches on and off every second. If the sound coming from the loudspeaker is too loud or very distorted, then try putting an 330 Ω resistor (colour code orange, orange, brown) in series with the loudspeaker. This is done by taking the resistor and cutting its leads to about 5 mm; then, disconnect one speaker lead from the tab on the PCB (it doesn’t matter which). Solder one end of the resistor to the vacated speaker tab, and the free speaker lead to the other end of the resistor. This will limit the volume of sound from the speaker, and lengthen the life of your battery. If it is still too loud, try a resistor of a larger value, or use a smaller resistor to make it louder.

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1	2.7 kilohms (kΩ)
R2	1 Megohm (MΩ)
P1–P5	Preset resistor 100 kilohms (kΩ)
P6, P7	Preset resistor 50 kilohms (kΩ)
P8	Preset resistor 25 kilohms (kΩ)
P9, P10	Preset resistor 10 kilohms (kΩ)

Capacitor

C1	100 nanofarads (nF) or 0.1 microfarad (μF)

Integrated circuit

IC1	NE555 timer chip

Additional items

S	Loudspeaker >60 ohms (Maplin)
	1 off battery clip (for PP3 battery)
	1 off spade terminal
	12 off solder pins ‘Veropins’
	3 off 10 cm lengths of ‘hook-up’ wire

(This article is based on projects originally designed by Radio Scouting, Netherlands.)

5 Experiments with the NE555 timer

Introduction

Several of the projects in this book use the NE555 timer, an integrated circuit which is at the heart of many circuits whose processes are determined by time intervals. **Figure 1** shows the circuit diagram of an audio oscillator using the 555. The timing voltages (governing the frequency of oscillation) are produced by R1, R2 and C2; a voltage appears at pin 3 which ‘switches’ at this frequency between zero and a voltage close to the supply voltage, which in this case can be anywhere between 6 V and 14 V. The output current, when applied through R3 to a small loudspeaker, produces an audible tone, provided that there is a DC path between the two test leads.


Positive test lead
Negative test lead
R1 4k7
R2 39k
C2 22n
4
8
7
6
2
3
1
IC1 NE555
R3 330R
Loudspeaker
C1 100µ 25V
+
−
6 to 14 Volts DC
Pin 5 of IC1 is not used
Dot
Notch
There will either be a notch or a dot in the plastic body of IC1 which tells you which way round to mount it – mount IC1 as shown
1
2
3
4
8
7
6
5
IC1 looks like this
Markings (type number, manufacturer, country of origin, etc)

Figure 1 The circuit diagram

Construction

The simplest way to mount the components is on a piece of matrix board (Veroboard), available from any of the good suppliers. The prototype of this circuit used the type of board with copper strips along the underside; these strips are used like the copper tracks on a PCB, to join components together. Firstly, cut the four strips between the positions of the pins of the IC socket, as shown in **Figure 2**. You can buy a tool for this purpose, but a small twist drill (about 3 mm diameter) is just as good. Turn it between your fingers – if you use a drill you will end up with holes right through the board! Then solder in the IC socket (with the notch in the position shown), followed by the four links made with single-conductor insulated wire. Put in each component as shown, ensuring that C1 (an *electrolytic* or *polarised* capacitor) is connected correctly. When all the components have been soldered in, take the 555 chip and lay it on its socket, with its own notch lying above that of the holder. Then, making sure that each pin lies *directly* above its corresponding socket, press down *gently* on the chip, with the board supported on a flat surface.

Testing

Connect the circuit to a battery or small power supply, ensuring that the positive and negative leads are the right way round. Always use red and black leads here, then you are less likely to get it wrong! Switch on. Nothing


1 2 3 4 5 6 7 8 9 10 11 12 13
A B C D E F G H I J K
Positive test lead
Negative test lead
Loudspeaker
IC socket
IC1
1 2 3 4 5 6 7 8
R1
R2
R3
C1
C2
+
–
L
Positive lead to battery / power supply
This marking shows negative lead of C1
R2 is mounted vertically
Negative lead to battery/ power supply

⊗ Copper strips cut here between IC socket pins (E5, F5, G5 and H5)

←——→ Direction of the eleven copper strips (each strip must have thirteen holes)

Note that copper strips C, D and I are not used

L indicates insulated wire links

Figure 2 Veroboard layout. If you can read a circuit diagram, the project can be built using other methods

should happen until you short together the two test leads, when there should be a note from the loudspeaker. If this doesn't happen, switch off, disconnect the circuit and check your wiring and soldering. Is it exactly like Figure 2? Are the soldered joints round and shiny? If any are dull, then 'sweat' them briefly with a hot soldering iron until the solder runs, remove the iron, and check that they are as shiny as the rest. Check that there are no solder 'bridges' between adjacent tracks by holding your board up to a strong light. Then, reconnect, switch on and touch the test leads together. All should now work!

Uses of your circuit

1. As a Morse practice oscillator. Simply connect the two test leads to your key and, each time the key is pressed, you should hear a note from the speaker. The frequency of the note may be altered by putting a resistor in series with the key. To do this, remove one test lead from the key and select a resistor; connect one end of the resistor to the free test lead and the other to the empty terminal on your key. Selecting the value of resistor that you need will be a useful experiment in itself.
2. As a continuity tester. You can check fuses and lamp bulbs by connecting them across your test leads. If the speaker remains silent, the fuse or bulb has blown.
3. To indicate changes of resistance. Hold the ends of the test leads in each hand; you should hear a low note, because of the high resistance of your body. Squeeze the ends harder, and the frequency of the note should rise, because you are now making better contact. Repeat this with damp hands and the frequencies will be higher still.
4. As a thermometer. Connect the test leads to a thermistor (a device whose resistance changes with temperature) and warm it with a hair-dryer, or even in your hands, and you will hear the pitch changing with the temperature of the thermistor. A suitable 'bead' thermistor is available from Maplin (order code FX21).
5. As a diode tester. Use any diode, and connect the negative test lead to the end of the diode marked with the ring. This is the cathode of the diode. The other end, the anode, should be connected to the positive test lead, and a note should be heard from the speaker. This does not necessarily mean that the diode is working – yet. Reverse the connections and *nothing* should be heard. If this is the case, the diode *is* working.
6. As a light meter. Use a photoconductive cell (a device whose resistance changes with light intensity) connected between the test leads. A note should be heard. Shading the device with your hand will increase its resistance and the note should decrease in frequency. A suitable device is the ORP12 cell from Maplin (order code HB10).

There are many more applications. **Do not connect the test leads to other circuits that are switched on.** Your circuit, or the circuit you are connecting it to could be damaged. Think of a *passive* device or circuit (i.e. one *not* requiring a power supply or battery) where changes of resistance occur, and you have found another application!

Parts list

Resistors: all 0.25 watt carbon film types

R1	4.7 kilohms (kΩ) – yellow, violet, red
R2	39 kilohms (kΩ) – orange, white, orange
R3	330 ohms (Ω) – orange, orange, brown

Capacitors

C1	100 microfarads (μF) 25 V radial electrolytic
C2	22 nanofarads (nF) or 0.022 microfarad (μF) polyester type with 10 mm lead spacing

Integrated circuit

IC1	NE555

Additional items

Miniature loudspeaker (preferably 35, 40 or 80 ohm)
8-pin DIL socket for IC1
0.1 inch Veroboard (‘stripboard’), size 11 strips by 13 holes
PVC-covered stranded wire for test leads, loudspeaker and battery connections
PVC-covered solid wire for links on the board
A power source of between 6 V and 14 V, such as a 9 V battery (PP3)

Component sources

Cirkit
Tandy – many high street shops

6 A simple metronome

Introduction

A metronome is a device used by musicians to indicate the tempo of a piece of music. Until electronics came on the scene, this 'beating of time' was achieved in much the same way as a clock keeps time, i.e. with a pendulum device, the clicking of the escapement indicating the beats of the music.

Those of you who have already built the Morse Key and Buzzer from the designs in this book, will recognise the circuit of this metronome – it is exactly the same as was used to produce the note of the buzzer. This circuit is shown in **Figure 1**.

The circuit

Three components determine the speed at which the circuit oscillates – the speaker (LS), the resistors (VR1 + R1) and the capacitor (C1). VR1 is a variable resistor, so that the speed at which the oscillator operates can be varied. Compared with the component values of the Morse Buzzer (which operated at around 800 Hz), these components now give an oscillation frequency of around 1.25 Hz, which is far too low to be heard as a note. What we *do* hear, however, is a series of clicks, as the voltage across the speaker changes quickly from 0 to 9 V and back again.



Figure 1 The metronome circuit is rather like the Morse oscillator


4cm x 4cm of plain perforated board
(without copper strips)
S1
+9V
RV1
R1
TR2
e
b
c
LS
c
b
TR1
e
+ C1
-ve
LS
● indicates solder joint
-----indicates wires on underside of board

Figure 2 The component wires are pushed through holes in the circuit board and joined together underneath

Variation of speed could be achieved by varying resistance or capacitance. However, as you may already know, variable capacitors have values in the picofarad range, not the tens of microfarads used here, so it is very simple to employ a variable resistor (potentiometer) to control the oscillator. You could use a multi-way switch to switch in one of several capacitors, as well as having the variable resistor, but this was found to be an unnecessary complication. This design operates between about 100 clicks per minute and 200 clicks per minute.

Making the prototype

A single piece of plain matrix board (no copper strips) measuring about 40 × 40 mm is sufficient to hold all the components except the potentiometer and switch (see later). The case can be plastic or aluminium, and one measuring 65 × 100 × 50 mm is about right. Make sure there are holes in the case beside the speaker cone to let the sound out, and larger holes for the potentiometer and switch. If a potentiometer is used with a combined ON/OFF switch, then the extra hole for the switch is not necessary! It is advisable to construct the circuit *before* putting it in the box, so that it can be tested to ensure that everything is working. If it is, then you can exercise your ingenuity in mounting the speaker, battery and board inside the box. A final test can be made before starting the calibration process.

Calibration

There is no ‘easy’ way to do this. The frequencies involved are too low to be measured with the average frequency counter, so you will need to resort to using a stopwatch and counting the number of clicks per minute.

Parts list

Resistors: 0.25 watt, 5% tolerance

R1	10 kilohms (kΩ)	
VR1	47 kilohms (kΩ) linear potentiometer	

Capacitor

C1	33 microfarads (μF) electrolytic	

Transistors

TR1	2N3053	npn
TR2	2N2905	pnp

Additional items

S1	SPST	ON/OFF switch
LS	3 ohms (Ω)	loudspeaker
	Knob with pointer for VR1	
	PP3 battery and connector	
	Aluminium case, 65 × 100 × 50 mm	
	Matrix board (plain), 40 × 40 mm	

7 What is a resistor?

Introduction

Materials that carry electricity easily are called **conductors**. They include all metals and salt water, for example. We use wire as a conductor, and the ease with which it passes an electric current depends upon the material, its thickness and its length. Silver (symbol Ag), gold (Au), copper (Cu) and aluminium (Al) are the best metallic conductors. Most wires are made of copper, although the best conductor, weight for weight, is aluminium.

Materials that *don't* carry current (or, at least, do so very badly) are called **insulators**, and they include dry wood, rubber, plastic and glass among their number. Wires are often coated with a layer of insulator to prevent adjacent wires touching and causing an accident.

Resistors

If there wasn't such a thing as resistance, the subject of electronics wouldn't exist; only infinite currents would flow and voltages wouldn't exist either! We need to reduce the flow of current if we are to make current do something useful for us. Components that resist the flow of current are called **resistors**, and they are said to have a **resistance** which is measured in ohms (Ω), named after Georg Ohm, who formulated the law (also named after him) by which the voltage and current through a conductor are related. His law gave rise to the formula *everyone* remembers:

$$I = \frac{V}{R},$$

where I is the current flowing, measured in amps,
V is the voltage across the conductor, and
R is the resistance of the conductor, measured in ohms.

From this equation, you can see that, for a constant value of voltage, V, if the resistance goes up, the current will go down, and vice versa. The circuit symbols for resistors are shown in **Figure 1**. You will find the upper symbol in older magazines; it is still preferred by many engineers. The lower symbol is the prevalent standard symbol.

Resistors are made in several ways, the cheapest using carbon; another type is usually made from a ceramic cylinder (used only as a support) on which



Figure 1 Circuit symbols for resistors

is placed a very thin film of metal – the thinner the film, the greater the resistance. All resistors are coated with a thin film of insulation, for the same reason we discussed earlier.

The colour code

Each resistor has coloured bands on it which enable us to see what value of resistance it has. There are normally three (but sometimes four) at one end, and a single one at the other (see **Figure 2**). The colours indicate figures, according to the list below.

Colour	*Value*	*Colour*	*Value*
Black	0	Green	5
Brown	1	Blue	6
Red	2	Violet	7
Orange	3	Grey	8
Yellow	4	White	9



Figure 2 Some examples of resistor colour codes; top 4700 Ω (4.7 kΩ) and bottom 100 Ω

Using the colour codes is easy, once you see the logic behind it. Hold the resistor so that the single band is towards the right. The three colours on the left are read in the normal order from left to right. The first two bands *always* indicate numbers; the third band gives the number of zeros to add to the right of these two numbers. So, looking at the top resistor in Figure 2, yellow, violet, red means 4, 7, and two zeros, giving 4700 ohms! Looking at the lower resistor, brown, black, brown means 1, 0, and one zero, giving 100 ohms.

Remembering the order of the colours may be difficult at first. The colours from red to violet are the colours of the rainbow, in order, so if you know those, you're almost there! Around those colours are black and brown below the red, and grey and white above the violet, which you can imagine as getting brighter from black to white (well, almost!). It won't be long before you don't need to remember them at all.

The isolated band on the right-hand side is not part of the resistor's value; it indicates its *tolerance*, i.e. how close it might be to the indicated value. A brown band indicates ±1%, a red band ±2%, a gold band ±5% and a silver band ±10%. For example, a resistor marked as being 100 ohms with a ±5% tolerance will have an *actual* value somewhere between 95 ohms and 105 ohms.

8 Waves – Part 1

Introduction

Waves are responsible for most of the processes in life where energy is transferred from one place to another. Heat and light energy from the sun, for example, come to us as *electromagnetic waves*. Sound travels through the air as a wave; it is not the same sort of wave as light or heat, but it obeys many of the same properties. Damage is caused to coastal margins by the waves of the sea – again, another type of wave, but still obeying many of the same properties. Radio waves are of the same type as heat and light waves, as are gamma rays, X-rays, ultra-violet waves and infra-red waves. So, once we begin to understand what radio waves do, we are also learning about a huge chunk of physics at the same time! All these waves are part of the *electromagnetic spectrum*. The word ‘spectrum’ simply means a ‘range’, so what we have is a range of electromagnetic waves – that’s all!

Sensing things

Light waves are invisible, but our eyes can detect the *effect* they have on different materials because the waves produce an effect on the retina of the human eye which the brain can interpret. We cannot see heat waves either, but we can feel the *effect* they have on our skin. Gamma rays and X-rays are also invisible, but their detrimental *effects* on human tissue are well known. It is not surprising, then, that we cannot see radio waves. We cannot sense them, either, until we produce a device upon which they have an *effect*. That device is a **radio receiver**; it is able to process certain characteristics of radio waves, and make these characteristics audible by generating sound waves from the loudspeaker or headphones. Other characteristics of the same waves may be turned into light as a TV picture on a cathode-ray tube, or as a fax image on a sheet of paper.

Visible waves

Let’s start our description with some waves that we can actually see! When a small stone is thrown into a pond, we see circular water waves *radiating* from the point where the stone fell into the water, as **Figure 1** shows. (Notice that we use the word *radiating*, even with water waves; it is not a radio term, but one which describes any motion where the *radius* of a circle is increasing. In this case, it is the radius of the circular waves which is


Splosh!
Waves spread out in all directions

Figure 1 The waves move out from the point where the stone landed

increasing.) If you were to watch the water waves down at the water level, perpendicular to the direction in which they are travelling, you would see something like the illustration in **Figure 2**.

The horizontal line represents the water level before the wave started, and the vertical line represents the direction in which the water is displaced at any instant.

All waves are described in the same way

'Freezing' the motion of the water in this way allows us to define two very important characteristics of a wave, characteristics which we talk about every day – *wavelength* and *amplitude*. The wavelength of a wave is simply the distance (measured in metres) from any point on one wave to the same point on the adjacent wave. Look at the diagram and you will see what is meant by 'the same point on the adjacent wave'. The amplitude of a wave



Figure 2 A water wave, viewed in cross-section

is always measured from the centre (undisturbed) position of a wave to the peak (or the trough) of the wave. Both these positions are shown, the arrow indicating that the measurement is taken *from* the centre *to* the peak or trough. The amplitude of a wave is defined as the maximum displacement of the wave from the centre position – the direction (up or down) of that displacement does not matter. Waves of greater amplitude carry more energy with them.

If we now 'unfreeze' the wave, we will see it travel from left to right (or right to left, depending on where we are looking). The speed at which it moves is called its *velocity*, and is measured in metres per second.

Another useful word is *propagate*; it means *travel*. We talk about radio waves propagating from a transmitter to a receiver. This velocity of propagation (for electromagnetic waves) is very fast indeed – they will cover 300 million metres in one second. This is virtually incomprehensible, so think of a radio wave travelling around the earth – it can travel 7½ times round the earth in one second! We use the symbol *c* for the velocity of radio waves (which is the same as the velocity of light, of course – all electromagnetic waves travel at this speed through air and space).

The last thing we need to know about the wave is its *frequency*. Imagine a cork floating on the water in the path of the wave; it will bob up and down. If we were able to count the number of times it went through its highest position in one second, then that number would be its frequency. Any periodic motion like this is said to go through one *cycle* each time one complete wave passes a point (in this case, our cork). We are thus counting the number of cycles per second of the cork's motion. The unit of frequency is thus 'cycles per second'; this unit is now named after Hertz, a radio pioneer, and is abbreviated to Hz.

Our description of the wave is now quite simple – we need only four quantities:

(a) **Frequency** symbol f – unit, hertz (Hz)
(b) **Wavelength** symbol λ (Greek letter lambda, pronounced 'lamb-da') – unit, metre (m)
(c) **Amplitude** symbol a – unit depends on application
(d) **Velocity** symbol c – unit, metres per second (m/s or ms^{-1})

The basic formula

Whatever may happen to a wave while it travels through different media (vacuum, air, brick, wood, etc.), one thing and **only** one thing remains constant – its frequency. Its wavelength, amplitude *and* velocity may change, but its frequency never does. Three of the four characteristics already identified are connected by the simple relationship

$$c = f \times \lambda.$$

Remember that *c* is constant if the wave travels in air or in a vacuum. This means that waves having higher frequencies (*f* large) must have smaller wavelengths (λ small) and vice versa. You can imagine frequency and wavelengths being on opposite ends of a see-saw!

Divisions of units

Because the frequencies of radio waves are so high (despite them having the lowest frequencies in the electromagnetic spectrum!) we have a problem with writing them down. Do you write in your log book that you have just heard a station on 14 100 000 Hz? Of course not, you write it as 14.1 MHz, knowing that the prefix mega (M) means 'one million'. The prefixes which you need to know (when applied to frequency) are:

kHz	kilohertz	meaning	1000 Hz
MHz	megahertz	meaning	1 000 000 Hz
GHz	gigahertz	meaning	1 000 000 000 Hz.

Notice that the 'k' in kilohertz is a lower case letter. It is **incorrect** to write it as an upper case letter. 'K' is a computer-related prefix meaning **not** 1 000 but 1 024!

When we come on to discuss heat and light waves, we will use wavelengths rather than frequencies, because of the see-saw effect – as the frequencies get larger and larger, the wavelengths get smaller, and hence are numbers which are more manageable, both to talk about and to write down!

Bands

Gamma rays, X-rays, ultra-violet waves, light waves, infra-red waves are all part of the electromagnetic spectrum, but we divide them up because they have different properties. This is why we divide up our radio frequencies into different bands. The radio waves of top-band signals (around 2 MHz) have completely different properties compared with those in the 20 metre band, so we are dividing up the *radio spectrum* in the same way – by property.

9 A beat-frequency oscillator

Introduction

Many readers will know that, although they have a short-wave radio which covers at least one of the amateur bands (e.g. 7 MHz or 14 MHz), they are unable to listen to SSB or Morse signals. This is because the receiver lacks a Beat-Frequency Oscillator (BFO). We need the ‘carrier’ frequency of a BFO to replace the carrier that has been removed from the signal at the transmitter. When listening to Morse signals, the BFO signal ‘beats’ with the incoming signal to produce a note in the loudspeaker. If you are a musician, you will be familiar with the method of using ‘beats’ to tune one musical instrument from another; in the BFO, the beat frequency produced is the tone signal you hear.

In the more complex amateur radio receiver, a BFO is incorporated as part of the whole system. In our model, it is an external circuit that sits alongside your radio. The circuit diagram is shown in **Figure 1**.

Construction

Built on a small piece of matrix board about 80 × 50 mm, the circuit can be fitted inside a small plastic box. For once, we *don’t* want to screen the circuit to prevent it interfering with other equipment; we *want* it to interact


+9V
R1
27k
TR1
2N2222A
b
c
e
2
3
6
4
C3
10µ
25V
+
+
9V
PP3
Battery
−
R2
4k7
C1
100n
R3
1k0
RV1
4k7
lin
C2
47n
R4
2k2
IFT1
collector
emitter
TR1
2N2222A
base
Viewed from
underside
4
2
6
3
IFT1
YHCS11100

Figure 1 Circuit diagram of the BFO



Figure 2 Matrix board layout shown from the component side. Adjust IFT1 carefully for the best results

with our receiver! This is why we use a plastic box. Maplin Electronic Components supply a suitable box, complete with the matrix board to fit inside (order code YU46).

Look at **Figure 2** carefully before you start to build the circuit, so that you can position the components correctly. Firstly, inspect the intermediate frequency (IF) transformer, IFT1, and remove its metal screening can very carefully. Again, this is to allow some signal to escape from our circuit and enter our radio. Having done this, solder the components, using the matrix board as a support. Underneath the board, the components are linked by single-conductor, insulated wire. Take particular care with the polarity of the electrolytic capacitor, C3, and the connections to the transistor, TR1 (see Figure 1).

The variable resistor, VR1, has a switch mounted behind the control itself, and the insulated leads to it from the battery should be about 10 cm long. Connect these before fitting VR1 into the case, so that the BFO can be calibrated (adjusted) correctly.

Calibration

After a final check that all the components have been fitted and soldered correctly, connect the battery, switch on, and hold the transistor between your fingers, to check that it is not getting hot. Place the circuit close to your receiver, and set RV1 to mid-position. Tune your receiver to find an amateur SSB transmission; the frequencies listed below will help you in knowing where to look. It may sound very strange, but don't worry. *Slowly* turn the core of IFT1 with a small, non-metallic screwdriver or with the correct 'trimming tool'. The core into which the blade fits is very fragile, so attempt this process with care. When the speech sounds as natural as you can get it, leave the core at this position, and use RV1 to make the speech sound natural.

Using the BFO

For best results, you may have to move the BFO nearer or further away from your radio. At the lower end of most bands (for instance just above 7.000 MHz or 14.000 MHz) you should be able to resolve Morse code (CW) signals. If you find that the BFO signal is a little weak, solder a 15 cm length of insulated wire to pin 2 of IFT1, and place it alongside your radio. This should improve signal intelligibility. When you are happy with the performance, switch off, drill a 10.5 mm hole in the box and fit RV1, followed by the matrix board assembly. Screw the base to the box, fit the knob, and the BFO is complete!

Where to listen

Band	**Frequencies (MHz)**
15 m	21.000–21.450
17 m	18.068–18.168
20 m	14.000–14.350
30 m	10.100–10.150
40 m	7.000–7.100
80 m	3.500–3.800

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1	27 kilohms (kΩ)
R2	4.7 kilohms (kΩ)
R3	1 kilohm (kΩ)
R4	2.2 kilohms (kΩ)
VR1	4.7 kilohms (kΩ), linear, with DPST switch

Capacitors

C1	100 nanofarads (nF) or 0.1 microfarad (μF), ceramic
C2	47 nanofarads (nF) or 0.047 microfarad (μF), ceramic
C3	10 microfarads (μF), 25 V radial, electrolytic

Additional items

TR1	2N2222A npn
IFT1	Toko type YHCS11100
Box	plastic, approximate size 100 × 70 × 45 mm
Board	matrix, to fit inside the box
Connector	for PP3 battery
Knob	for RV1

10 What is a capacitor?

Introduction

A capacitor is a device that stores energy in the form of electricity. Much less energy than a battery, and for a shorter time, however. The simplest form of capacitor takes the form of two flat metal sheets separated by air; connections are made to each plate, as **Figure 1** shows. If you imagine a pair of these plates, 30 cm square and separated from each other in air by 1 mm, the capacitance of this device would be almost exactly 80 picofarads (pF), i.e. 80 million-millionths of the unit of capacitance, the farad. Now this is quite a small value, you will agree, and it comes about because the farad is such a large unit. Nevertheless, as you will probably know, we may have capacitors of value 10 000 microfarads (μF) in our radio equipment, and they can be smaller than your little finger, so they are obviously not made the same way!



Figure 1

Large and small

We cannot go into the manufacture of capacitors here – after all, we are users of the devices, not the designers! First of all, beware of incorrect statements; the words ‘capacitor’ and ‘capacitance’ are *not* the same. For example, a large capacitor would be a description of one the size of a toilet roll. It need not have as large a capacitance as one the size of your little finger. A ‘large capacitor’ is one which is physically *big*, a ‘large capacitance’ refers to a capacitor which can store a larger amount of energy when a certain voltage is applied between its plates. The capacitors in a mains power supply are usually big **and** have large capacitances. High-power RF amplifiers may have large capacitors with small capacitances!

Electrolytics . . .

Electrolytic capacitors usually have capacitances of 1 µF or above. They differ from other capacitors in that they **must** be connected the right way round (i.e. they have positive and negative connections, just like a battery). They may explode if the connections are reversed!

. . . and the others

Other capacitors may be connected either way round, despite their names. We have *polystyrene*, *ceramic*, *silver-mica* and *tantalum*. Each has its own advantages and disadvantages, and the parts list for a project will always tell you which type is best.

Storing energy

If you were to connect a large capacitance across a 12 V power supply, nothing would appear to happen. Removing the capacitor from the supply and connecting it to a voltmeter would show that the capacitor has 12 V between its ends. This shows that, while the capacitor was connected to the supply, energy flowed from the supply into the capacitor. We say that the capacitor was *charged up* by the supply. If you are using an *analogue* voltmeter (i.e. one with a meter and pointer), you will notice that the indicated voltage slowly drops until, eventually, there is no voltage across the capacitor. This is because the capacitor has *discharged* its energy into the voltmeter. If you had used a smaller capacitance, the same would happen, except that the voltage would drop to zero more quickly – the capacitor stores a smaller amount of energy because its capacitance is smaller. Capacitors behave like other things in life – a small car can move more quickly than a large bus – a small piccolo emits a higher note than a flute – the voltages in a circuit containing a small capacitance will change more quickly than those in a circuit with large capacitance.

Varying the capacitance

Some capacitors are capable of having their capacitance changed manually; these are called *variable capacitors*. They work like the basic capacitor of Figure 1. Imagine moving the top plate of the pair a little to one side; the capacitance is determined, not just by the size of the two plates, but by their *area of overlap*. As this decreases, so does the capacitance. Such devices are limited in their capacitance, about 500 pF being the maximum value.

AC and DC

Because the plates of a capacitor do not touch each other, a direct current (DC) cannot pass between them. However, an alternating voltage on one plate can induce an identical alternating voltage on the opposite plate, and thus a capacitor appears to pass an alternating signal, even though currents as such, do not pass between the plates. This property of passing AC and not DC is very important, and a capacitor used in this way is called a *DC blocking capacitor* or, simply, a *blocking capacitor.* A blocking capacitor can be used at the same time, to couple a signal from one circuit to the next; here it would be known as a *coupling capacitor. Decoupling capacitors* are to be found where the capacitor is employed to remove an AC signal while retaining a DC component.

Finally . . .

Unlike resistors, the manufacture of capacitors renders them susceptible to excess voltage, so if you find a capacitor labelled 10 μF 16 V, it means that operating it above 16 V may fatally damage the device (and the circuit around it). This voltage is called the *working voltage* of the capacitor; on some electrolytics, you may find it expressed as *volts working* (i.e. 8 μF 450 V WKG).

Many smaller capacitors have their properties marked on them in a colour code, like resistors. **Figure 2** shows these codes, and their meaning, and the table below summarises the values of the colours.

Table 1

Colour	*Value*	*Voltage (tantalum capacitor)*	*Voltage (polyester capacitor)*
Black	0	10	–
Brown	1	–	100
Red	2	–	250
Orange	3	–	–
Yellow	4	6.3	400
Green	5	16	–
Blue	6	20	–
Violet	7	–	–
Grey	8	25	–
White	9	3	–


TC
1st
2nd
M
T
TANTALUM CAPACITORS
1st
2nd
M
V
+
Tip
1st
2nd
M
T
CERAMIC CAPACITORS
1st
2nd
M
T
V
POLYESTER CAPACITORS

Figure 2 Some capacitors have coloured bands or stripes, rather like resistors. The colour code, which is the same as the resistor code, is shown in Table 1. The band shown on the chart as '1st' is the first number of the capacitor's value in pico-Farads, '2nd' is the second number and 'M' is the Multiplier or number of noughts. For example, a capacitor reads from the top: Brown, Black, Yellow, Black, Red. Its value is One, then Nought, then Four more noughts = 100 000 pF (also referred to as 0.1 μF or 100 nF). Its tolerance (Black) is 20% and the working voltage (Red) is 250 V. The 'V' means the maximum working voltage. The band marked 'T' shows the tolerance, just like resistors, and the one marked 'TC' is only used on special capacitors designed to change their value with temperature

11 Waves – Part 2

Introduction

We left Part 1 with the concept that radio waves are divided up into bands which have different properties. Not *all* the properties are different, though. We need to discuss several wave properties, so we will start with what happens to waves as they propagate over long distances.

Getting weaker

Imagine a torch battery connected to a bulb by wires about 1 metre long. The bulb lights normally. If we now take the bulb 100 metres away from the battery and wire it up, we would expect the bulb to be somewhat dimmer, which is exactly what would happen. It happens because of the resistance of the wires – the wires do not form a perfect conductor. A similar situation occurs with radio waves.

All waves suffer from *attenuation* – they get weaker the further they travel. In cases of extreme attenuation, we need to apply some *amplification* before the attenuated wave can be used in a receiver.

Carrying information

When we speak over the telephone, the range of frequencies in our voices extends from very low frequencies up to about 15 or 20 kHz. In audio terms, this is quite a large *bandwidth* (meaning a wide band of frequencies). For communications purposes, however, most of this bandwidth is not needed, and in the telephone system (and in our transceivers), this is cut down so that it extends from about 200 Hz to 3 kHz, a reduction in bandwidth from 20 kHz to about 3 kHz. A bandwidth of 3 kHz has been found to be sufficient to convey speech intelligibly which, after all, is just what we need!

The radio waves coming from an amateur transmitter convey our speech signals over long distances. By themselves, the speech signals do not travel very far, so they have to be combined with a radio signal that *will* travel long distances. This extra signal is called the *carrier wave* (or just the *carrier*), because its job is to *carry* the speech signals along with it! The process of combining the speech (or Morse code) with the carrier is called *modulation*.

Wider and wider

Sending Morse code is achieved simply by switching (or *keying*) the carrier on and off. The bandwidth of the transmitted signal is only about 100 Hz. Speech, with its reduced bandwidth of 3 kHz, will produce a *single-sideband* (SSB) transmitted signal with a bandwidth of 3 kHz. If the same speech signal were used to produce an *amplitude-modulated* (AM) signal from the transmitter, it would have a bandwidth of about 6 kHz. Perhaps you can now understand why the bandwidths needed to produce hi-fi broadcasts need to be so large. TV signals need bandwidths running into tens of megahertz!

Waves need aerials

Radio waves are produced whenever changing currents flow through a wire, and when that wire is made in such a way as to maximise the *radiation* from the wire, it is called an *aerial* or *antenna*. The same piece of wire will receive radiation from other aerials; an aerial will transmit and receive. This is an important property of the aerial: when a current flows through it, electromagnetic waves are launched into the air; when electromagnetic waves in the air encounter the aerial, currents are produced in it.

From the simplest transmitting aerial, waves travel in all directions, like the waves on the pond that we considered in Part 1. They will travel a long way through air and space before they become too week to be received. They won't travel very far into the earth, however! The earth will *reflect* some of the wave and will *absorb* the rest. That portion of the wave which is reflected will again travel through air and space until it is totally attenuated.

Look at **Figure 1**; A represents a radio transmitter, with B1, B2 and B3 being receiving stations. The two arrows pointing 'downwards' from A represent two of the waves from A which just graze the earth's surface. Waves above



Figure 1 Stations between B2 and B3 receive the *ground wave*

these will travel on into space; waves below them will either be absorbed and reflected by the earth or received by aerials. B1 will not receive any signals from A, because it is below A's horizon. B2 and B3 can receive A's signals because they are *just* on A's horizon. Any stations between B2 and B3 will also receive A's signals, which are known as *ground-wave signals*. The wave at C represents one which is reflected by the ground and travels into space.

This description begs the question of how signals are received from stations well beyond the ground-wave range.

Mirrors in space

Suppose that there was something, out in space, that would reflect radio waves. Waves from A that travel out into space could be reflected off it and return to earth, enabling stations such as B1 to receive A's signals. The situation just described is illustrated in **Figure 2**.



Figure 2 Reception of A's signals at B1 using the *sky wave*

Just such a mirror in the sky really *does* exist. It is not man-made, of course! The earth is surrounded by the atmosphere, a mixture of many gases, such as nitrogen and oxygen. The energy contained in the radiation from the sun is more than sufficient to *ionise* these gases, thus making them into electrical conductors. When a gas is ionised, some of its electrons are physically stripped out of the atoms and are free to move about, just as the electrons of a metal do in a wire. Consequently, we can regard this part of the atmosphere (the part illuminated by the sun) as acting like a sheet of metal, which *reflects* radio signals! It is not a perfect reflector, but is sufficient to produce long-range (DX) radio propagation via the *sky wave* under the right conditions. (A more down-to-earth example of ionised gases conducting electricity can be found in the fluorescent tube and the neon sign – many gases glow when they are continuously ionised.)

This conducting region at the extremity of the atmosphere is called the *ionosphere*, and it exists in layers between 60 km and 700 km above the earth's surface. When the ionosphere is sufficiently ionised, it glows; this is the natural phenomenon known as the *aurora borealis*, or the *northern lights*.

The property of the ionosphere that enables radio waves to be reflected does not act in a uniform way; it is very selective about which waves it reflects, and which waves go straight through it and into outer space. In general, it reflects only those waves with frequencies below about 30 MHz – the HF bands!

In Part 3 we will look at families of waves.

12 An LED flasher

Introduction

The LM3909 is an integrated circuit (IC) which will flash a light-emitting diode (LED). Using only two extra components and a battery, the circuit is cheap and has a very low current drain from a 1.5 V cell. The circuit can be used as a novelty flasher, an indicator for a dummy alarm bell box, or it could be attached to a torch so that it could be found easily in the dark! The simple circuit is shown in **Figure 1**.



Figure 1 Circuit diagram of the LED Flasher. Pins 1, 3 and 7 of the IC are not used

Assembly

The circuit can be built on a small piece of Veroboard (the piece shown in **Figure 2** measures 15 holes by 10 strips). Using such a board, follow these instructions.

1. Depending on how far away you want the LED from the circuit board, solder a length of insulated wire to each lead of the LED. Use different colours of insulation – say, red and black, connecting the *red* lead to the *anode* (a) lead (the longer one) of the LED, and the black one to the *cathode* (k). Figure 2 shows these leads.
2. Cut the copper tracks as shown in Figure 2, using a 3 mm (⅛ inch) diameter drill, rotated between thumb and forefinger, or use the proper tool. Make *absolutely* sure that the tracks are completely broken!
3. Fit the IC holder in the correct position, using the cut tracks as guides, and make sure the small notch is facing towards the top of the board. Solder the pins to the copper tracks.
4. Mount the capacitor, positive end to the left, so that the positive lead is soldered to track F, which connects it to pin 2 of the IC; the negative lead is soldered to the right-hand side of track E, this being connected to pin 8 of the IC.
5. Solder on the battery leads, positive to the right, and the extended LED leads, positive downwards.



Figure 2 Board layout viewed from the component side. The tracks are cut under the board where shown

6. Check the circuit, and hold up the board to a bright light and look carefully for solder bridges between the tracks and pieces of copper swarf which may have escaped your inspection in 2 above! Remove whatever you find.
7. When all seems well, put the IC into the socket, ensuring that the notch or dot on the upper surface of the IC lines up with the notch on the holder. Line up each pin on the IC with the hole below it before pressing *gently* on the IC with the board supported on a firm surface.
8. Connect the battery; the LED should start to flash. The circuit is complete and working!

If you prefer, the whole circuit (battery included) can be mounted in a small plastic box, with the LED mounted on a clip and protruding through the panel. There are many other possibilities, and it is up to you to find an application for your own use.

Parts list

		Maplin code
LM3909	Integrated circuit	WQ39N
IC socket	8-pin DIL	BL17T
LED	5 mm diameter	WL27E
100 microfarad (μF)	Electrolytic capacitor (10 V)	FB48C
Battery holder	For AA-size cell	YR59P
Battery	1.5 V AA cell	

Small piece of Veroboard (15 holes by 10 strips)
Small plastic box (if required)
LED clip (if required)
Two lengths of coloured, insulated wire for LED (as required)

Availability

All parts can be obtained from Maplin Electronics Ltd.

13 Waves – Part 3

Introduction

When we talk about the spectrum being divided up into bands, this is just for our convenience; there are no natural divisions although, as we have seen, some of the properties of different bands really *are* different! Let's look at **Figure 1**, and see how the frequencies are divided up.

The divisions

- **Very low frequencies** (VLF) cover the range from a few kilohertz up to 30 kHz. Very long-range communication is possible, but at *very* small bandwidths. It is used for special purposes.
- **Long waves** (LW) are used for medium-distance commercial broadcasting and have frequencies from 30 kHz to 300 kHz.
- **Medium waves** (MW) are used for commercial broadcasting, and use frequencies from 300 kHz to about 1.5 MHz (1500 kHz). Typical range is about 200 km.
- **Short waves** (SW) encompass both the low-frequency (LF) and high-frequency (HF) amateur radio bands. There are nine narrow amateur bands in the SW spectrum between 1.8 MHz and 30 MHz. Some of these bands give round-the-world communication.
- **Very high frequencies** (VHF) span the range between 30 MHz and 300 MHz. Relatively short-range communication is possible. They were once used for broadcast TV before it moved to UHF. There are now three



Figure 1 Diagram of radio frequency spectrum

amateur bands here – 6 m, 4 m, and 2 m. Repeaters are used to extend the usable range of mobile stations. VHF waves are not usually reflected by the ionosphere, but when they are, ranges of several thousand kilometres are possible. Weather affects these waves on a regular basis, however. In addition to amateur users, the VHF part of the spectrum is also used by the police, the fire and ambulance services, weather satellites, and many others,

- **Ultra-high frequencies**, sometimes called *centimetre waves*, cover the range from 300 MHz to 1000 MHz (or 1 GHz). The only amateur band in this range is the 70 cm band, and we share it with radar, TV and cellular telephone users as well.
- **Microwaves** begin at 1 GHz and extend to about 400 GHz. They are *never* reflected by the ionosphere, are partially attenuated by buildings, and are reflected from aircraft and cars. Microwave absorption in the atmosphere is quite significant, and rain and fog can attenuate microwaves quite heavily.
- **Heat, light** . . . Above 400 GHz we run into the infra-red bands and on into the visible light and ultra-violet bands. We generally take 400 GHz as being the limit of what we class as radio waves.

Bandwidth again

Complex signals need more bandwidth than simple signals. Even if it were possible, we would not be able to transmit a single television channel in the whole of the MW broadcast band! When TV used part of the VHF band, only five channels were possible in the range from 45 MHz to 68 MHz. By moving TV to the UHF band, we now have 47 channels between 470 MHz and 855 MHz!

It’s your choice!

The number of permutations you have amongst all the modes and all the bands is enormous! Only you can decide what you are interested in and what you want to learn about. That is the attraction of amateur radio!

14 Choosing a switch

Simple, but be careful!

A switch is the simplest electronic component, but care is needed in choosing the correct one for the job. Here is a list of the main characteristics of a switch, which will help you to select what you want.

1. **Rating**. This gives the maximum voltage and current that a switch can handle. For example, a 250 V 1.5 A switch will switch mains voltage at a current not exceeding 1.5 A. If the current is greater than 1.5 A, the switch may get hot and fail. If the voltage is too great, the switch may arc each time it is switched off, thus wearing away the contacts.
2. **Number of poles**. A single switch can control many circuits; the number of poles tells you *how many* different circuits it can handle. See **Figure 1**.
3. **Number of throws**. This tells you the number of positions each pole can have. This is best illustrated in Figure 1. The simplest ON/OFF switch is a Single-Pole, Single-Throw (SPST) switch. A Single-Pole,


SPST
Single-pole, single-throw
Single-pole, double-throw (also known as a changeover switch i e, SPCO)
Double-pole, double-throw (also known as a 2-pole, 2-way switch)
Push-button switch

Figure 1 Some circuit symbols for different types of switch

Double-Throw (SPDT) switch may also be used as an ON/OFF switch, but is used mainly to change between two parts of a circuit, and is commonly known as a Single-Pole Change-Over (SPCO) switch. Two or more SPCO switches can be operated at once; Figure 1 shows an example. The two switches are said to be *ganged*. See also 'Types of switch' below.

4. **Number of ways**. When a switch has more than one throw, we tend to use the word 'ways' instead. This means that if a switch has one pole and six throws, we would normally call it a '1-pole 6-way' switch. Such switches tend to be rotary switches, as are described below.

Types of switch

(a) **Push-button**. These are found on calculators, telephones, electronic games and most equipment with a digital display.

(b) **Rotary**. These are switches controlled by a knob, and are turned instead of moved up and down. **Figure 2** shows the rear of such a switch and its circuit symbol. The commoner types of rotary switch are: 1-pole, 12-way; 2-pole, 6-way; 3-pole, 4-way; 4-pole, 3-way; 6-pole, 2-way. All these switches have 12 click positions, as you may have guessed, but each one comes with an adjustable end-stop so that you can set the correct number of ways according to the contacts on the switch.

(c) **Slide**. This switch is common on the cheaper types of radio, mainly as an ON/OFF or band-changing switch. They are not very rugged, but are small and cheap to produce. Very small types are manufactured for use on PCBs.

Figure 2 The rotary switch can select several different circuits at once



(d) **Toggle**. Available as two-way types or three-way, with a centre-off position. Can be manufactured to handle very high currents.
(e) **Micro-switch**. These are devices which are usually operated indirectly, such as when the cover is removed from a high-voltage power supply, or when the door of a fridge is opened. The 'micro' part of the name doesn't refer to the size of the switch, but to the *small* movement that is required to activate it.



15 An aerial tuning unit for a receiver

Introduction

Any length of wire will act as an antenna (or aerial) but, to get the best results from a transceiver or receiver, an aerial tuning unit (ATU) is required. This matches the *impedance* of your aerial to the impedance at the aerial socket of your radio. Impedance is like resistance, and is measured in ohms, but it is used for alternating currents, and hence is common in audio and RF engineering. Most receivers have an impedance at the aerial socket of about 50 ohms (Ω); aerial impedance, on the other hand, can be anywhere between 20 Ω to over 1000 Ω, depending on its length and its height above ground.

Fortunately, you don't *need* to be able to calculate your aerial's impedance; all you need is a device that will perform the matching operation for aerials with a large range of impedances, and this is exactly what is described here! The subject of *matching* is a complex one, but all you need to know is that most signals will become clearer, and that there will be less noise and interference. Stations will become louder, so you will probably be able to reduce the setting of your RF gain control (always a good thing to do).

This design of ATU covers all amateur and broadcast bands from 10 m (28 MHz) to 80 m (3.5 MHz), and is very easy to build. The circuit is shown in **Figure 1**.



Figure 1 Circuit diagram of the Antenna Tuning Unit, showing the use of a 2-pole, 6-way rotary switch to select inductors (L) and capacitors (C)

Construction

1. Firstly, you will need a simple plastic case in which to house the ATU. The size should be approximately 85 × 145 × 50 mm.
2. Start by drilling two 10.5 mm holes in the front of the case; these are for the 6-way switch and the tuning capacitor.
3. Drill three 8 mm diameter holes in the left-hand side of the box, for the three sockets, coloured blue, yellow and green.
4. On the right-hand side of the box, drill two 8 mm diameter holes for the red and black sockets.
5. Now, fit the 6-way switch (SW1), the tuning capacitor (VC1), and all the sockets to the case. Check that the vanes of the capacitor rotate smoothly when the shaft is turned.
6. Wire up the inductors (coils). Figure 1 and the wiring diagram of **Figure 2**, will help with this. As you can see, each one side of each coil is connected to two switch connections, the other end going to VC1.
7. Solder in the fixed capacitors. One end of each goes directly to the ground socket (black), and the other end goes to the switch.
8. Solder a wire between the green and black sockets. The output from the ATU comes from the red socket, and this is connected to the two tags in the centre of the switch, as Figure. 2 shows clearly.
9. Finally, connect the blue and yellow sockets to the tuning capacitor, and the ATU construction is complete.



Figure 2 The internal view of the case shows the main tuning capacitor, VC1. This is a solid dielectric type, which has adjustable brass plates

In practice . . .

Figures 3 and **4** show two different ways of connecting your aerial to your ATU. In each case you will need to select each switch position in turn, and rotate the tuning capacitor through its full range while listening to a station. You should find that one switch position enables VC1 to produce a peak in the signal strength in the loudspeaker. At this point, your aerial and receiver are said to be *matched*. Stations in the same band will probably peak with VC1 at the same setting of SW1, but different bands will almost certainly require different positions of SW1.


ATU
Blue
Yellow
Green
Red
Black
Antenna input
RECEIVER
Ground

Figure 3 You may find that parallel tuning gives best results with your antenna


ATU
Blue
Yellow
Green
Red
Black
Antenna input
RECEIVER
Ground

Figure 4 In other cases, series tuning could be the most effective arrangement

Parts list

Capacitors (all rated at 16 V or more)

C1	220 picofarads (pF) polystyrene
C2	470 picofarads (pF) polystyrene
C3	1000 picofarads (pF) or 1 nanofarad (nF) polystyrene
C4	2200 picofarads (pF) or 2.2 nanofarads (nF) polystyrene

Inductors

L1	1.2 microhenries (μH)
L2	8.2 microhenries (μH)
L3	68 microhenries (μH)

Switch

SW1	2-pole 6-way rotary

Sockets

4 mm type, one each of red, black, yellow, blue, green

Additional items

Plastic or metal case, e.g. Maplin type YU54
Two large knobs for SW1 and VC1

16 A simple 2 m receiver preamplifier

Introduction

Designed specifically to complement the modified air-band portable (also described in this series), this can be used with some success on many receivers suffering from ‘deafness’ on VHF.

The circuit

An RF preamplifier is a device which improves the input signal to an existing receiver, enabling it to work more effectively. Because of the noise which is added to the signal by the preamplifier, *very* weak signals may not be usefully enhanced, but stronger signals will be improved considerably.



Figure 1 The integrated circuit is mounted upside down. Make sure you identify pin 1 which has a small dot next to it

This little circuit (shown in **Figure 1**) uses a GEC/Plessey integrated circuit type SL560C. With the addition of four capacitors, it is used between your aerial and the aerial input of the radio's PCB.

Putting it together

1. Use a small piece of prototype (matrix) board about 25 mm square. Use an 8-pin DIL socket for the integrated circuit (don't risk soldering the chip – it is seldom a risk worth taking). Figure 1 shows the connections to the socket, *looking from underneath*.
2. Make special note of the pin numbers, so that you know how to put the chip into the socket when you have finished. The positive and negative connections to the circuit are taken from the main PCB *after* the ON/OFF switch – so that the switch operates the preamplifier, too.
3. Unsolder the lead to the radio's telescopic aerial and connect it to the free end of C4, as shown. Then solder a short lead between the telescopic aerial and C2.
4. Sometimes it is possible to cajole your little preamplifier into the radio's plastic case, provided there is room and that you make sure that none of the soldered joints on your little board touch any of the metal inside the case when you replace the back and screw it on again.
5. If there is not enough room inside, then put the preamplifier into its own box, with battery and switch, and its own aerial. Keep the lead from the preamplifier to the aerial connection of the radio as short as possible – perhaps using screened cable.

Because your preamplifier is untuned, you will find not only that it helps with reception on 2 metres, but also that reception on the FM broadcast band is improved!

Parts list

Integrated circuit	
IC1	GEC/Plessey SL560C
Capacitors	
C1	1 nanofarad (nF) ceramic
C2, C4	10 picofarads (pF) ceramic
C3	10 nanofarads (nF) ceramic
Additional item	
Prototype broad approx. 25 × 25 mm	

17 Receiving aerials for amateur radio

Introduction

For any radio receiver to work well, it must have some form of antenna, or aerial. In almost all domestic transistor radios, the aerial is built into the set, either as a ferrite rod (which looks like a rod of dark grey metal) on which are wound coils of wire, or as a chromium-plated telescopic metal rod. Some radios have both forms of aerial, using the ferrite rod aerial for long waves (LW) and medium waves (MW) and the metal rod for very high-frequency (VHF) stations using frequency modulation.

There's broadcast reception . . .

No aerial is perfect, and these two types are *far* from perfect! As in most mass-produced equipment, *they serve their purpose*, which is not critical, and they allow the radio to be carried around easily, because they are not big and bulky. The broadcast stations are very powerful, usually quite close, and the circuits in the radio are quite sensitive, so the need for large aerials disappears.

. . . and there's amateur DX

Here we have an application which, in comparison with the broadcast situation, couldn't be much more different. The stations do not use much power, they may be half the world away, and the requirement for good aerials and very sensitive receivers is paramount. The aerials must be large and they must be as high as possible, away from buildings and trees, which cause reduction in signal strength, and away from man-made sources of interference.

You may not have thought about this but, in general, the larger an aerial becomes, the longer the cable (or 'feeder') must be in order to reach your shack and the receiver inside it. Cables reduce the received signal, so what your aerial gains by being large, the feeder (if you're not careful) will lose!

A simple aerial . . .

We now know that a 'good' aerial is essential. But what is a 'good' aerial? It depends on your purse, your property and your enthusiasm! One of the simplest (and, incidentally, one which is *not* subject to the cable loss problem discussed above) is the **Long Wire**, shown in **Figure 1**. This is, quite literally, a long piece of wire going from a chimney stack to a tree or pole



Figure 1 A tree at the bottom of the garden can provide a useful antenna support. Insulators can usually be obtained from Tandy stores or TV aerial suppliers

at the end of the garden. The longer it is, the better. Notice that the wire itself is *not* used to loop around the tree or chimney. Rope is used for both, and is secured to the end of the wire using an insulator of the 'dog bone' or 'egg' variety, to be found in profusion at rallies.

The wire is brought into the house through a window into the shack where the receiver is situated. The long wire aerial is best used with an aerial tuning unit (ATU), which is also described in this book. One of the advantages of the long wire is that it can be used on several frequency bands.

. . . and more complicated ones

Next up the ladder of complexity is the **dipole** (meaning two poles, or two elements). One form of dipole for lower frequencies would take the same basic form as the long wire, except that the feed to the receiver is taken, not from the end, but from the centre. The wire is essentially cut into two halves, and the two ends at the centre are connected to one end of a coaxial cable, which is then taken to the receiver. A smaller form of this is shown in **Figure 2**, which is conveniently mounted in a house loft. Aerials should always be mounted outside for best results, but will work when mounted inside, and the loft space is the logical situation.

The total length of the dipole should ideally be one-half of the wavelength of operation – hence the term 'half-wave dipole'. For example, a dipole for use on 20 m should be about 10 m long. Dipoles are thus 'single-band' aerials. They can be modified for use on several bands, and then become known as 'trapped dipoles', having coils and capacitors at certain points along their lengths.


I.... insulator
I
TV coaxial cable
To shack
Wire fixed to roof timbers with tacks or drawing pins – use insulated (covered) wire

Figure 2 An indoor antenna should be mounted as high as possible

Indoor aerials

For flat- or apartment-dwellers, an indoor aerial is often the only solution, in which case the dipole of Figure 2 may be of great use. Other popular types include the **loop aerial**, of which several types are shown in **Figure 3**. The shape of the loop is of secondary importance, but it should be as large as possible.


Continuous wire loop – as large as possible
(a)
I
I .... insulator
TV coaxial cable
To shack
(b)
I
(c)
I
(d)
I

Figure 3 Try different shapes of loop antenna to see which works best

Ingenuity is called for when considering indoor aerials. A dipole can be mounted along a picture rail or pelmet. A vertical loop of aluminium foil can be stuck to an inside wall and covered with wallpaper! The designs are limited only by your imagination, and will give you hours of listening pleasure

Outdoor aerials

If you want to venture beyond the simple long-wire discussed earlier, then the erection of outdoor aerials can be a bit tricky; they can be more than a one-man job, and can involve seeking planning permission. Get some help advice from someone who has done it before – what about your local radio club? Plenty of designs for aerials appear in *RadCom*, so you should never be short of ideas!

18 The Colt 80 m receiver – Part 1

Introduction

This is the first of four parts detailing the design and construction of a simple radio capable of good reception of amateur radio signals on the 80 metre band. If you can solder and have some basic hand tools, at the end of Part 4 you will have a working receiver, in which you can take pride, and start some serious listening on 80 m! For testing, all you will need is another receiver and a multimeter.

Description

The radio will be built in three modules, or stages, as illustrated in **Figure 1**. Each of these is built on a printed-circuit board (PCB) or matrix board and can be tested in its own right. The case will need some holes drilled, and care will be needed to mount the PCBs in the case.

Get to it!

Surprisingly enough, when you are building a radio section by section (which is *always* the best way), it is easiest to start at the output and work


Simple tuner
Audio amplifier
(a)
Mixer board
Audio amplifier
VFO
(b)
Mixer board
IF board
Audio amplifier
VFO
(c)
© RSGB

Figure 1 Build your Colt and watch it grow. A simple crystal set (a) becomes a direct conversion receiver (b) and finally an 80 metre amateur band superhet (c)

towards the input, and you can test what you have done stage by stage. You will see what this means as you progress with your construction.

Every receiver needs some audio frequency (AF) amplification to make the sound signals big enough for you to hear. The circuit for the AF amplifier is shown in **Figure 2**. It uses the TDA7052 integrated circuit (IC) plus a handful of extra components. R1 in conjunction with C2 and C3 *decouple* the battery supply, preventing any audio signals getting through to it and affecting other parts of the radio, when they are connected. C1 acts to prevent high frequencies (above the 3 kHz bandwidth) going into the amplifier input. A volume control, VR1, is connected across the amplifier input, so that the amplifier can accept signal inputs over a wide range. **Figure 3c** shows the connections, which are made with screened cable. The


R1
22R
+9V
C2
100n
+ C3
220µ
16V
Input
1
VR1
2
TDA7052
5
+
Output
8
C1
100n
3
6
© RSGB X146

Figure 2 The Philips TDA7052 integrated circuit (IC) used in the audio amplifier needs very few extra components. It has a signal voltage gain of 100 times and the output is suitable for a loudspeaker or headphones

centre conductor of the left lead goes to the point marked ‘input’ in Figure 2, the braid being connected to the amplifier earth (0 V) tag. The right lead to VR1 goes to whatever signal source you have for testing – see later. VR1 is *not* mounted on the PCB.

The circuit is constructed on a small PCB or matrix board. Make sure that the electrolytic capacitor, C3, is soldered into the board the correct way – its positive and negative connections are shown in **Figure 3b** for reference. If you are **at all** concerned about soldering the IC into the board, enlist some help, *or*, obtain an 8-pin DIL socket, which you can solder in and then carefully insert the chip into the socket, making sure that is the correct way round. The markings on the chip are shown in **Figure 3a**.

The output leads from the amplifier go to a plastic 6.3 mm (¼ inch) mono jack socket, so that *neither* output lead is connected to the metal case. The amplifier will drive a pair of headphones or a small 8 Ω loudspeaker.

The battery leads must be the right way round also; the battery itself can be a PP3 or PP9, or you can use a small DC power supply.

Testing

First, check that all the components are in the right places, that your soldering is good, and that you have headphones or a loudspeaker connected. Set VR1 about halfway along its travel. Connect the battery.



Figure 3 It is important to check the component connections carefully. The diagram shows (a) top view of the IC, (b) electrolytic capacitor and (c) volume control (VR1) connected across the input of the amplifier

A slight hissing noise should be heard; touching the input lead to the amplifier (the centre of the three connections on VR1) should produce a loud buzz. Touching the shaft at the same time will make the buzz quieter. This is the quickest way of confirming that your amplifier *seems* to be working. The only real test is to give it something meaningful to amplify! See the design of our *Crystal Radio Receiver* for full details.

Parts list

Resistors: all 0.25 watt, 5% tolerance	
R1	22 ohms (Ω)
VR1	10 kilohms (kΩ) log
Capacitors	
C1, C2	0.1 microfarad (μF)
C3	220 microfarads (μF) electrolytic 16 V
Integrated circuit	
IC1	TDA7052 audio amplifier
Additional item	
PCB	(see below)
Component suppliers:	
Maplin	

The next part . . .

The metal case will be marked out ready to receive the completed modules.

19 A crystal radio receiver

Introduction

Here's a quick project to fill in a winter's evening! It was originally designed as a piece of test gear for the *Colt* receiver, but can be successfully used by anyone as a first radio project. Another use for it would be as test gear for any audio amplifier project requiring an audio input for test purposes; this is ideal, as it does not require any power supply!

Details

The initial rough-and-ready test for the audio amplifier of the *Colt* receiver will have whetted your appetite; you will want to prove more conclusively that your amplifier works, and in a way that others in the household will appreciate. Buzzing noises are not convincing in this respect! You are going to put together a simple crystal set – the simplest type of radio that there is – and use it as a signal injector for your amplifier. In this way, you build a real medium-wave (MW) receiver which drives a loudspeaker, as an intermediate product of the construction of an 80 metre amateur band receiver!

The circuit diagram is shown in **Figure 1**. It has a 60-turn coil mounted on a small piece of paper or card wrapped round a ferrite rod. The coil has a connection made to its centre-tap (the middle turn of the coil). The tuning capacitor, VC1, is the most expensive part of the circuit but don't worry, it will be used in the final design of the receiver also! Connect the diode, D1, from the centre-tap to the input to the potentiometer of the amplifier circuit of the *Colt*. Be careful to connect the aerial to the *vanes* of VC1, and not to its *frame*, or you will experience some strange effects when you are tuning. If your amplifier is working correctly, you should be able to receive local stations on medium-waves quite well.

If you think the crystal set will be of use to you in the future as a signal injector, all you will need will be another variable capacitor! If you do not intend to use the amplifier, a small crystal earpiece will allow you to listen. Walkman-type headphones will *not* work!


VC1
VC1 vanes
30 turns
D1
OA91
Inner
L1
30 turns
To audio amplifier
VC1 frame
Screen

Figure 1 Both sets of moving vanes are joined as shown. L1 is wound on a ferrite rod with 32 SWG wire and centre-tapped. A single winding (no tap) can be used, joining D1 to the top of the winding

Parts list

Variable capacitor

VC1	125 + 125 picofarads (pF) twin-gang

Ferrite rod

About 100 mm to 140 mm long

Diode

D1	OA91 germanium diode

Additional items

Wire	2 m of enamelled copper wire, between 23 SWG and 32 SWG
Earpiece	High-impedance crystal type (only needed if you are not using the amplifier)

20 The varactor (or varicap) diode

Introduction

Many of the circuits for receivers and transmitters presented in this series rely upon the variable capacitor as a means of tuning. Another method of varying capacitance (without any moving parts) is provided by the *varactor diode*, sometimes called a varicap diode. This is a component which changes its capacitance as the voltage across it is varied.

The details

Figure 1 shows how a varactor diode might be connected to demonstrate its operation. Its symbol is that of an ordinary diode, with a capacitor symbol next to it. A variable voltage is applied across it in such a way that the diode is *reverse-biased*. This means that virtually no current passes through it – the positive voltage is applied to the cathode. Varactors are cheaper than variable capacitors, and they are tiny in comparison, very suitable for today's miniature circuits. If A and B were connected across the tuning coil in a simple receiver (with a series capacitor to block the DC from the battery reaching the coil), the tuning operation would be accomplished by turning the knob on the 10 kilohm potentiometer.

Varactors are available with different values, from less than 20 picofarad (pF) for VHF applications to 500 pF for medium-wave radios. They are



Figure 1 The capacitance of the varicap diode (between A and B) increases as the voltage is reduced, using the variable resistor

tuned usually by voltages between 2 V and 9 V. For a real application of varactors, you should consult the circuit diagram of the *Yearling* 20 metre receiver, elsewhere in this book.

In some circuit designs, several circuits are all tuned to the same frequency in order to improve the overall *selectivity* (the ability of the circuit to reject signals very close in frequency to the wanted signal). Special dual- and triple-varactors are available for circuits like this. Having been made at the same time from the same materials makes their individual characteristics virtually identical. Like all other diodes, they must be correctly wired into the circuit – their *polarity* is important.

Changes in temperature will cause the capacitance to change which, if it were part of an oscillator circuit, would cause the oscillator to drift – you would have to keep retuning the radio! This can be corrected by using a special integrated circuit called a *phase-locked loop* (PLL). Modern TV sets and satellite receivers use varactors and PLLs in this way.

Some useful varactor types

Type No.	*Tuning range*		*Description*
	pF/V	*pF/V*	
BB204B	42/2.0	15/12	Dual VHF
BB212	560/0.5	22/8	AM tuning
KV1235	450/2.0	30/8.5	Triple AM
KV1236	450/2.0	30/8.5	Dual AM
MV1404	120/2.0	9/10.0	HF tuning

21 A portable radio for medium waves

Introduction

The ZN415E integrated circuit (IC) can be used to make a very efficient AM portable MW broadcast radio with a built-in loudspeaker. Here's how!

The circuit

Figure 1 shows the circuit diagram of the portable radio. It's not as complicated as it may appear, especially after you have got started. L1 is a coil of wire mounted on a ferrite rod, acting as an aerial; VC1 is a variable capacitor which works, with L1, to tune in different stations. IC1 contains circuits of its own which boost the selected signal and it includes a *detector* which extracts the audio signal from the incoming RF signal. Earphones could be connected to the output of IC1 (between pins 4 and 5), but the output would not be powerful enough to drive a loudspeaker.

More sound

This is where IC2, an LM386 comes in. This is a small audio *power* amplifier which produces audio signals with enough power to drive a small


TR1
BC548
e
c
b
R2
5k6
6V0
nc...no connection
S1
On / Off
1V9
anode
cathode
LED1
1V3
+
C5
100µ
nc
8
nc
1
6
2
3
4
5
7
IC2
LM386
C8
100µ
+
C9
100µ
+
B1
6V
-
L1
VC1
Tune
IC1
ZN415E
1
8
2
3
4
5
6
7
C1
10n
C3
100n
C2
100n
C4
10n
R1
68R
C6
10µ
+
C7
100n
R3
10R
LS1
8R0
Dot
Notch
Flat face (marked)
There will either be a notch or a dot in the plastic body – this tells you which way round to mount the IC
1
2
3
4
8
7
6
5
Marking
IC1 and IC2
Collector
Base
Emitter
TR1
Bend leads here
Anode (longer lead)
Cathode
LED1
Marking to show negative lead
C5,6,8 and 9
©RSGB

Figure 1 The circuit diagram of our easy-to-build portable radio. Take care to mount the ICs and LED the correct way round

loudspeaker, LS1. The radio uses a 6 volt battery, which is made by connecting four 1.5 volt AA cells in series (4 × 1.5 V = 6 V) using a battery holder designed for this purpose. Although a 6 V supply is ideal for IC2, it is far too great for IC1, which needs only about 1.3 V. This lower voltage is provided from the 6 V supply by TR1 (an npn transistor), R2 and LED1 (a light-emitting diode). When current passes through an LED (see the description of the LED in this series) a reasonably constant voltage of 1.9 V appears between the anode and the cathode. Because of the voltage (0.6 V) that *always* exists between the base and emitter of a working transistor, the voltage on the emitter is about 1.9 V – 0.6 V = 1.3 V, and this is used as the power supply for IC1.

To keep the radio as simple as possible, no volume control has been fitted. Instead, you can use the directional properties of the ferrite rod aerial (see the information on ferrites in this book) to reduce the volume by rotating the set about a vertical axis using the handle provided.

Putting it all together

1. Start by covering the ferrite rod with Sellotape, or alternatively wrap a piece of paper tightly around it, and secure it with Sellotape. Then, with at least 2 metres of 24 SWG enamelled copper wire, wind 75 turns tightly around the rod. To be safe, leave about 50 mm of wire at the ends of the coil, then wrap the whole coil with Sellotape to hold the turns in place, leaving only the ends free. Then, using a small piece of sandpaper, remove the enamel from the last centimetre of each end of the coil.
2. Most of the components are mounted on a piece of Veroboard (the type with parallel copper strips on one side). The piece used on the prototype measured 32 holes by 10 strips, as **Figure 2** shows. Before you start fitting components, cut the copper strips as shown. It is easier to do it now than when the board is littered with components! The strips may be cut with a 3 mm (⅛ inch) twist drill rotated between thumb and forefinger. Resist the temptation to use a hand drill – the idea is just to cut the copper, **not** to drill right through the board!
3. Solder the IC sockets and the other components on the board as shown in Figure 2. Make sure that the IC sockets are fitted with their notches towards the *top* of the board, as viewed in Figure 2. Do not insert the chips yet. Always keep the wires left over from cropping resistors and capacitors, they will come in handy at times like this: make the wire links that are clearly shown in Figure 2. Connect the electrolytic capacitors (C5, C6, C8 and C9), the transistor and the LED the correct way round; then check it again when you have done it!
4. Finally, solder lengths of stranded insulated wire to act as ‘flying leads’ for future connection to L1, VC1, LS1, S1 and the battery connector.
5. Apart from the battery holder, everything is mounted on the case *lid*. This makes assembly and testing much easier, and eases fault-finding if


© R508
Ferrite rod
S
L1 — 75 turns
S
S indicates Sellotape strip
L1, VC1 and S1 are not to scale
VC1
nc
O
G
A
S1
Red
+ to Battery holder
Red
A
B
C
D
E
F
G
H
I
J
c
b
e
TR1
R2
IC1
C2
C3
C4
C1
C5
anode
cathode
LED1
R1
IC2
C6
C7
C8
C9
R3
To LS1
1 2 3 4 5 6 7 8 9 10 15 20 25 30 32
1 ◄——► 32 Direction of the ten copper track strips (each track must have thirty-two holes)
Track H is not used
Black
– to Battery holder
⊗ Copper strips are cut here
IC1 and IC2 are mounted in IC sockets

Figure 2 Veroboard layout for the Portable Radio. Make sure that all the wire links are included

the need arises! At the speaker position, make one large hole or a series of small holes to let the sound out. The ferrite rod may be stuck to the lid, as may the loudspeaker. Drill holes of the correct size to fit the particular types of variable capacitor (VC1) and switch (S1) that you are using. The Veroboard may be held in position by Blu-Tack or double-sided sticky tape.

6. Before inserting IC1 and IC2, connect the battery and switch S1 on. The LED should glow dimly (you may have to shield it with your hand in order to see it). If you have a test meter, check that there is about 1.3 V between pins 6 and 4 of IC1. If the reading is around 6 V or there is no glow, you may have connected the LED the wrong way round! When everything seems normal, switch off and disconnect the battery. Insert IC1 and IC2, making sure that the pins are straight and lie immediately above their corresponding holes in the sockets, and that the notches line up with the notches in the holders. Then push *gently* downwards on each IC in turn until the chip is firmly seated in its socket.
7. Switch on! By rotating the tuning capacitor, VC1, you should now be able to tune in many stations, rotating the radio to give you some volume control.

Final touches . . .

The handle was made with part of an old leather belt, secured to the case with 'number plate' nuts and bolts from Halfords. The loudspeaker grille is the lid from a *pot-pourri* container, and some extra holes were drilled in the back to improve the sound. See what you can find to finish off your radio!

Parts list

Maplin order codes are given for most of the parts, but you should get used to using the 'beg, borrow or steal' technique, or to use your ever-expanding junk box.

		Maplin code
Resistors: all 0.25 watt, 5% tolerance		
R1	68 ohms (Ω)	M68R
R2	5.6 kilohms (kΩ)	M5K6
R3	10 ohms (Ω)	M10R
Capacitors		
C1, C4	10 nanofarads (nF) or 0.01 microfarad (μF) ceramic	BX00A
C2, C3, C7	100 nanofarads (nF) or 0.1 microfarad (μF) ceramic	YR75S
C5, C8, C9	100 microfarads (μF) electrolytic, at least 10 V	FF10L
C6	10 microfarads (μF) electrolytic, at least 25 V	FF04E
Semiconductors		
IC1	ZN415E radio chip	
IC2	LM386 audio power amplifier	UJ37S
LED1	3 mm green LED	WL33L
TR1	BC548 npn transistor	QB73Q
Additional items		
LS1	Miniature 8 ohm loudspeaker	WB08J
S1	Miniature SPST toggle switch	FH97F
Ferrite rod	Length approx. 100 mm	YG20W
	24 SWG enamelled copper wire	BL28F

Additional items (*continued*)

VC1	Tuning capacitor 140 to 300 picofarads (pF)	FT78K
	Tuning knob	FK41U
	8-pin DIL IC sockets (two required)	BL17T
	4 × AA-size battery holder (long)	HF94C
	PP3-type clip for battery holder	HF28F
	Plastic box approx. 158 × 95 × 54 mm	LH51F
	0.1 inch Veroboard, min. size 32 holes × 10 strips	JP46A

Plus
Stranded insulated conductor for flying leads
Multicore solder
Materials for handle and speaker grille
Double-sided sticky tape or Blu-Tack
Sellotape
Glue
Four AA-size 1.5 V batteries

22 The Colt 80 m receiver – Part 2

Introduction

In Part 1 we constructed the audio amplifier module for the system and tested it in a very simple way. If you did what was suggested and built the simple Crystal Set to use as a signal source, you will know just how well the amplifier works.

The case

Metal cases for the project are available from Maplin, telephone 01702 554 161 (code XB67). From the photograph on p. 72 you can see the way the components are mounted. The audio amplifier is seen at the top right of the base, to the right of the tuning capacitor VC1. The next in this series will deal with the variable-frequency oscillator (VFO) and VC1. The current part deals with preparing the case to receive the components.


Rear
I F
board
Mixer
board
VFO
board
VC1
mounting
screws
Audio
amplifier
board
© RSGB

Figure 1 Fixing holes for each module are best measured from each printed circuit board or matrix board


Front
Volume
control
RF gain
control
Headphone
socket
Mounting for
Slow-motion drive
On/Off
switch
© RSGB

Figure 2 Position the slow motion drive to allow viewing of the tuning dial

Figures 1 and **2** show the markings for preparing the front panel and base. All the circuit boards and the tuning capacitor are mounted on the base using 10 mm stand-off pillars with 6BA bolts. The board locations are shown in Figure 1. The front panel control positions are shown in Figure 2, together with the small rectangular hole for viewing the tuning dial.

The best way to mark out the holes for the boards is to lie the boards flat on the base (before you've started soldering the components in) and marking the base through the holes in the boards. This minimises the scope for errors!

A *reduction drive* is used between the tuning knob and the capacitor shaft. This is simply a gear mechanism that slows down the capacitor shaft by a factor of six compared with the tuning knob, and makes tuning very much easier. The recommended variable capacitor also has a pulley wheel mounted on the shaft. Glued to this wheel will be a scale marked with frequency and is visible through the rectangular hole in the front panel.

The next part . . .

The variable-frequency oscillator and mixer will be added to the project.



23 A simple transistor tester

Introduction

Although transistors aren't used as much as they were before integrated circuits came along, a transistor tester is still a useful piece of test equipment to have around the shack. This design is about the simplest possible and will produce an indication of whether a transistor is giving any current gain; this does not necessarily mean that the transistor is perfect but that it is working to a certain extent. This tester will **not** test field-effect transistors (FETs). If you buy a bag of transistors at a rally, this tester is useful for giving a yes/no indication of which ones go straight in the bin and which are kept for further use.

How it works

Figure 1 shows the simple wiring circuit. In order to explain the working of the circuit, a circuit diagram is shown in **Figure 2**, with the npn transistor, TR1, under test shown as part of the circuit. The pnp/npn selector switch, SW1, is omitted for clarity.



Figure 1 Circuit diagram of the transister tester



Figure 2 Testing an npn transistor

Any current that flows through the transistor, TR1, must flow from the battery, through the meter, M1, and through the protective resistor, R2. R2 prevents excessive current flowing through the meter and damaging it. Even if there is a short-circuit between emitter and collector, the maximum current that will flow is given by the simple equation

$$I = \frac{V}{R},$$

where I is the current flowing in amps,
V is the battery voltage, and
R is the total circuit resistance in ohms.

Putting in the correct values, gives

$$I = \frac{9}{47\ 000} = 0.000191 \text{ A, or 191 microamps } (\mu\text{A}).$$

The resistance of the meter, M1, will cut this down a little more, but it is within the indicating range (200 µA) of the meter.

As shown, with the push-button switch, PB1, *open*, a good transistor will not draw any current from the battery, and M1 will thus remain at zero. When PB1 is *pressed*, a *very small* current is injected into the base of the transistor. If the transistor is working, it will produce a much larger current between the collector and emitter, and this current will also flow through M1 and R2, giving a significant reading on M1, showing that all appears to be well. If an appreciable current flows when PB1 is *open*, then your transistor is suspect.

Don't be put off by the apparently complicated switch, SW1. It is there to allow the other type of transistor, the pnp type, to be tested. All it does is reverse the battery connections, so that the emitter goes to the *negative* battery terminal for testing an npn transistor, and to the positive terminal for a pnp type!

Most transistors in common use are of the npn type, which is why Figure 2 shows the testing of an npn type. The connections to the different transistor *encapsulations* (shapes) are given in any good component catalogue. Avoid the trial-and-error method to discover the connections to a transistor. This is unscientific, and can be very frustrating, particularly if the transistor is faulty in the first place!



Figure 3 This shows how to wire up the tester

Construction

The unit can be built into a small plastic box, the components being soldered directly to the fixed terminals of the meter and the two switches; no circuit board is necessary! Use different colours of wire for the three test leads, and make sure you know which is which! Check the connections against the wiring diagram of **Figure 3**. When you are confident that all is correct, connect the battery and make sure there is no reading on the meter when nothing is connected to the crocodile clips!

Find any transistor for which you know the connections and the type (npn or pnp). Set the npn/pnp switch accordingly. Connect the three clips, making sure that they do not touch each other. A small reading on the meter at this stage means the transistor is suspect; a large reading means it is not working and should be thrown away! Press PB1 and watch the meter; a reading greater than half of full-scale indicates a good transistor. If it is less than half, you may have a transistor with ‘low gain’; it may be usable for non-critical applications, but if you are in any doubt – throw it away!

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1	100 kilohms (kΩ)
R2	47 kilohms (kΩ)

Additional items

PB1	Push-button switch
SW1	DPDT (double-pole double-throw) switch
M1	Micro-ammeter – *not* less than 200 μA full-scale deflection
	Crocodile clips (3 needed)
	PP3 battery and connector
	Plastic box about 10 × 7 × 3 cm

Common types of transistor

BC108, BC109, 2N2369A

These are small-signal npn types, used in audio amplifiers. They are in metal cases (called TO18) and have a tab next to the emitter lead. Common types have a B or C suffix (e.g. BC109C). The C suffix indicates a higher current gain than those with a B suffix. The 2N2369A is specially designed for radio use at high frequencies.

2N3703, BC212L, BCY71

These are pnp transistors, and so must be used with the collector and base *negative* with respect to the emitter. These three types are used in small amplifiers and audio oscillators. The first two have plastic encapsulations (TO92), while the BCY71 has a metal case (TO18).

BFY50, BFY51, BFY52

For slightly higher powers, these are ideal. They have been used in novice transmitters up to 600 milliwatts (mW). The TO5 case is a scaled-up version of the TO18 case. They are all npn types.

2N3055, 2N3773, TIP35C

These are high-power transistors in bigger encapsulations. The thick metal TO3 case of the 2N3055 and 2N3773 is designed to bolt to a heat sink, a large piece of metal which conducts the heat into the air more rapidly than the transistor itself can. The TIP35C is made of plastic but has a thick metal tab by which it, too, can be bolted to a heat sink.

24 An introduction to transmitters

Introduction

We usually think of a transmitter as being a 'black box'. However, that is the form a transmitter takes for our use on the amateur bands. Many electrical circuits are transmitters, even though transmitting may not be their primary function!

Anything that emits electromagnetic energy at *any* frequency is a transmitter, from radio at the low-frequency end of the spectrum, to gamma rays at the high-frequency end. We all know that a magnet will attract certain metals and that a comb rubbed on your coat sleeve will pick up small pieces of paper. The former is an example of the effect of a magnetic field, the latter of an electric field. Electromagnetic fields are combinations of both types of field, and are produced whenever an electromagnetic wave is transmitted.

What frequency?

Many everyday objects have a natural frequency of oscillation. This is called their *resonant frequency*. A wine glass will ring when struck gently; an empty wine bottle will sound if you blow across the top; a guitar string will vibrate when plucked. These are all examples of resonance, and the resonant frequencies will **not** change unless the objects themselves are changed physically in some way. These are resonances in *sound*; we are primarily interested in electrical resonances.

The basic electrical resonant circuit is the combination of an inductor (coil) and a capacitor, as shown in **Figure 1**.



Figure 1 The basic electrical resonator. The energy in the circuit alternates between the inductor and the capacitor

A pulse of energy applied to this *tuned circuit* will make it *ring* (oscillate) at its resonant frequency. The energy in the circuit transfers between the inductor and the capacitor every cycle of the oscillation. Just like the wine glass, its oscillation dies away because it is losing some energy to its surroundings – it is transmitting! The frequency of the resonance depends on the values of L and C.

Keeping it going

If we want to keep the circuit oscillating, rather than having it die away, we must supply the circuit with just enough energy to replace the energy lost both by radiation and by losses in the circuit itself. Because of this, you will find in all oscillator circuits, a transistor, valve or FET working with the tuned circuit to provide this extra energy.

As it stands, of course, even with its transistor, our oscillator will not radiate very far. Connecting an aerial to it, and a Morse key to interrupt the power supply, it would become a very low-power CW transmitter. Add a couple more transistors to form a radio-frequency (RF) amplifier, and you have the basis of a simple low-power (QRP) transmitter.

Resonant circuits can also be made using quartz crystals; these work at the crystal frequency only, and this is marked on the crystal case.

A tiny spark transmitter

This is a simple piece of test gear that will increase your knowledge and understanding of resonance. You can use it to estimate the resonant frequency of most of the inductor/capacitor (LC) tuned circuits that you build. The circuit is shown in **Figure 2**. It operates around a relay. Any relay that operates from a 6 V to 9 V source and has contacts which are normally closed (i.e. closed when the battery is not connected). Fit the relay, a toggle switch and the battery in a metal box, and connected up as shown in the diagram. Some foam rubber inside the box may help to reduce the escaping noise of the relay. A small hole in the side of the box enables the 2-turn loop to emerge. This should be about 40 mm diameter, made with insulated wire. Switch on; there should be a loud buzzing noise from the relay. If not, you have probably chosen the wrong contacts on the relay!

When it is working, bring the loop close to the aerial of a radio – it should produce a loud noise from the speaker!

How it works

When you switch on, current flows through the relay contacts and through the relay coil. The relay operates and opens the contacts, causing the relay to 'drop out'. When it does, the circuit is completed again and the contacts are opened, and the cycle repeats. Each time the relay contacts open, there is a small spark between them, causing very rapid current surges through the wire loop. This makes the loop transmit RF energy, very briefly. In the early days of radio, this type of circuit was known as a *spark transmitter.*



Figure 2 The current path is interrupted when relay is energised as shown above

Make a tuned circuit

Use a discarded toilet-roll centre, and wind about 10 turns of enamelled copper wire round it, keeping each turn close to the next. Scrape off the enamel for about 1 cm at each end, and solder a 100 picofarad (pF) capacitor (or a variable capacitor of about the same value) between the ends. The resonant frequency should be about 10 MHz. If you have used fewer turns or a smaller capacitor, the frequency will be higher.

Measuring the resonant frequency

Set up the buzzer as shown in **Figure 3**, with the loop around one end of your coil. Then make a similar loop, solder it to the end of a piece of coaxial cable going to the aerial socket of a calibrated receiver. Set the buzzer going, tune the receiver around 10 MHz, and search for the maximum noise level from the speaker. When you have found it, move the two loops as far away as possible from the main coil. This is called reducing the *coupling* between the coils, and it may result in a slightly different, but more accurate, resonant frequency.



Figure 3 Experiment with the spacing between the loop and the tuned circuit

Parts list

Any small relay which operates between 6 V and 9 V
Metal box – do not use a plastic box!
9 volt battery and connector
On/off (SPST) toggle switch
Plastic foam, as required

25 The Colt 80 m receiver – Part 3

Introduction

In Part 2 we marked out the case ready for installation of the modules when they are completed. In this part, the building of the variable-frequency oscillator (VFO) and mixer will be described. This will produce a type of receiver known as *direct-conversion*, because it converts the radio-frequency (RF) signal directly into an audio-frequency (AF) signal which we can hear in a loudspeaker after amplification. A block diagram of the system is shown in **Figure 1**. The modifications needed to make a full superheterodyne receiver will be left until later.

The direct-conversion receiver covers the 80 metre amateur band and will receive both Morse (CW) and speech (SSB) signals. The audio amplifier was covered in Part 1, so your *Colt* is rapidly taking shape! By the time your construction has reached the end of this part, you will have a receiver ready to use, even if the project is not yet complete!

The direct conversion process

Like most things in radio, the principles of direct conversion are not difficult. From the aerial, the signal we want to hear is selected by the *tuned filter*, which rejects the signals we don't want. The signal then enters the


Antenna
Radio signals
Audio signal
$F_{AUDIO} = F_{VFO} - F_{RADIO}$
Audio (sound) signals
Tuned filter
Mixer
Audio amplifier
VFO signal
Loudspeaker
VFO
© RSGB

Figure 1 Stages of direct-conversion receiver

mixer, along with the signal from the *VFO*. The VFO produces a sine wave whose frequency can be varied across the whole of the 80 metre amateur band (3.5–3.8 MHz), by turning the knob on the tuning capacitor, VC1. The mixer produces, at its output, *two* signals; one signal is at the frequency of the **sum** of the signal and VFO frequencies, the other is at the **difference** of the two frequencies. It is the latter that we want. Let's look at the numbers involved. If the signal is at 3650 kHz and the VFO is at 3651 kHz, then the sum frequency is 7301 kHz, and the difference frequency is 1 kHz. If we feed the output of the mixer into our audio amplifier, the 7301 kHz signal is automatically removed (it is far too high to be considered an audio signal!) and the resulting 1 kHz signal is amplified and fed to the speaker, producing a note which we can hear!

Building the VFO

Figure 2 shows the circuit of the VFO. It is a tried and tested circuit, and should work first time. It uses a *field-effect transistor* (FET) for TR1, the oscillator itself. RFC is a *radio-frequency choke*, a coil of wire which will pass a direct current (DC) but which will prevent radio-frequency (RF) signals getting through.

All VFOs have a tuned circuit which, in this case, is formed by the coil L1 and the capacitors C1 and VC1. The frequency will also be affected to some extent by C2, C3, C4 and C5. Transistor TR2 is an *emitter follower*, a stage which gives no voltage gain but provides a good *buffer* stage, isolating the VFO from the effects of the stages that follow it. When building a VFO, the



Figure 2 The variable-frequency oscillator uses a field-effect transistor (FET)

parts must be securely mounted. If components move, so does the frequency! At worst, the oscillation will become unstable and the VFO will be useless. Keep the component leads as short as possible – this improves their mechanical stability as well as their electrical stability!

Mount the parts on the printed-circuit board (PCB) or matrix board and, when completed, the VFO should look like the one shown on the left in the photograph on p. 72. Make sure that TR1, TR2 and D1 are the right way round.

On completion, check the component positions then mount it in the case as shown in the photograph, to the left of the tuning capacitor when viewed from the rear. The VFO coil, L1, will need some adjustment, but that will have to wait until the mixer is built. Connections to the other boards are made with screened cable.

The mixer board

So far, we have an audio-frequency (AF) amplifier and a VFO; the addition of a mixer board gives us a complete direct-conversion receiver for 80 m. The mixer circuit diagram is shown in **Figure 3**. Let's follow the signal path.

- From the aerial, the RF signal goes to the gain control potentiometer, RV1. This reduces very strong signals, to prevent them overloading the mixer.
- To select the required band of signals, a *bandpass* filter is made up of RF transformers T1 and T2; these are tuned by C1 and C3, and are coupled together by C2.



Figure 3 The mixer board has a bandpass filter and stabilised supply

- After the filter, the signal is coupled into the integrated circuit (IC) mixer type NE602, by the capacitor C4. Capacitors C5 and C8 *decouple* the supply line, to prevent unwanted signals on the supply from disturbing the VFO operation. The use of the term *decouple* is exactly the opposite of *couple*; when two circuits are *coupled* together, the signal passes from one to the other; when two circuits are *decoupled*, signals **cannot** pass from one to the other.
- The NE602 works with a 6 V supply; it is produced here from the 9 V supply by the *Zener diode* ZD1 and the resistor R1. ZD1 operates at 6.2 V, and gives a steady output for the mixer. The audio output from the mixer appears at pin 4 or IC1. This is taken to the audio amplifier board via C9 and the volume control (see Part 1).

Care must still be taken to insert some components the right way round. These are the electrolytic capacitors, C8 and C9, the Zener diode, ZD1, and the integrated circuit, IC1. Check all component positions and make sure all your soldered joints are bright and shiny.

Putting it together

The interboard wiring, shown in **Figure 4**, uses screened cable; ideally, this should be thin coaxial cable, but screened microphone cable is suitable. The diagram shows how the two controls, the RF Gain and Volume, are connected to the boards. The leads marked '+9 V' are all connected to the battery supply via a miniature on/off toggle switch. Double check all connections before connecting the battery.

Setting the VFO

Very little adjustment is needed to get the receiver going. Firstly, the VFO must be adjusted to cover the required band, in this case 3.5–3.8 MHz.

If you have a frequency counter, connect it to the output of the VFO. If you haven't, read this part anyway so you understand the process, then another means of setting the VFO will be given especially for you! Rotate VC1 until the vanes are fully meshed. Very carefully, adjust the core of the VFO coil (L1) with a plastic trimming tool so that the frequency approaches and settles at 3.500 MHz. When you rotate VC1, the frequency should increase to **at least** 3.800 MHz at the far end of its travel.

In the absence of a frequency counter, borrow a communications receiver, set it for SSB reception (USB or LSB) on exactly 3.500 MHz. Set VC1 with the vanes fully meshed and turn the core of L1 in both directions until you hear a whistle in the communications receiver. Rotate the core so that the whistle reduces in frequency. It will eventually fade out at around 200 Hz;


Screen connections
RF gain
Antenna
Variable frequency oscillator
+9V
Screen connections
Volume
Speaker
Audio amplifier
+9V
Mixer
+9V
©RSGB X168

Figure 4 Make sure that interconnections between the boards are correct, including cable screens

turn the core a little further and then leave it at that position. Rotate VC1 right to the other end of its travel, and search for the whistle with the tuning knob of the communications receiver. Check that the VFO frequency is at least 3.800 MHz.

Then, whichever method you are using for frequency measurement, mark the dial with frequency steps of 50 kHz. Setting and calibration are finished!

Setting the mixer

Again, there are various ways of doing this. If you have a signal generator, inject a signal at a frequency within the 80 m band, and adjust the cores of T1 and T2 sequentially for maximum output.

If you haven't a signal generator, connect an aerial to the mixer input, set the RF Gain to maximum (fully clockwise), and find a consistent signal. Adjust the volume control to a comfortable level. Rotating the core of T2 with your trimming tool, maximise the output. Then do the same with T1, although this will have much less effect. Find another station, and check that the positions of the cores aren't too different for a maximum signal.

You may find that your receiver benefits from the insertion of an aerial tuning unit (ATU) between the aerial and the input, to compensate for the impedance of your aerial not being 50 Ω. A design for such an ATU is presented in another part of this series. If the signals are still weak, connect the ATU to the junction of C1 and C2 via a 100 pF capacitor.

Try listening!

Remember that 80 m is a variable band. During daylight hours, your will hear Morse signals at the lower end of the band, and some British and closer continental stations between 3.7 and 3.8 MHz. In the evenings, stations up to 1000 miles away should be heard. Look for Novices around 3.7 MHz!

Parts list – VFO board

Resistors: all 0.25 watt, 5% tolerance		
R1	100 kilohms (kΩ)	
R2, R5, R6	100 ohms (Ω)	
R3, R4	10 kilohms (kΩ)	
RV1	1 kilohm (kΩ) linear	
Capacitors		
C1	12 picofarads (pF) polystyrene	
C2	100 picofarads (pF) polystyrene	
C3	470 picofarads (pF) polystyrene	
C4, C5	1 nanofarad (nF) polystyrene	
C6, C8, C9	10 nanofarads (nF) polystyrene	
C7	100 picofarads (pF) min. ceramic	
VC1	140 + 140 picofarads (pF) variable	
Semiconductors		
TR1	MPF102	FET
TR2	BC182	npn
D1	1N914	silicon
Inductors		
L1	Toko KANK3334	
RFC	1 mH	RF choke

Parts list – mixer board

Resistors: 0.25 watt, 5% tolerance

R1	1 kilohm (kΩ)
VR1	1 kilohm (kΩ) potentiometer (linear)

Capacitors

C1, C3	47 picofarads (pF) min. ceramic
C2	3.3 picofarads (pF) min. ceramic
C4	100 picofarads (pF) min. ceramic
C5	100 nanofarads (nF) min. ceramic
C6, C7	10 nanofarads (nF) min. ceramic
C8	220 microfarads (μF) electrolytic 16 V
C9	1 microfarad (μF) electrolytic 16 V

Integrated circuit

IC1	Philips NE602 or NE602A

Additional items

T1/T2	Toko KANK3333
	On/off switch
	Miniature toggle switch

The next part . . .

The IF amplifier and the Beat-Frequency Oscillator will be added to convert the *Colt* into a superheterodyne receiver.

26 A two-way Morse practice system

Introduction

It is said that the pleasure of sending and receiving Morse code more than compensates for the learning effort needed. Transmitters for Morse code can be much simpler than those needed for any of the speech modes.

Many people choose to learn sending and receiving on their own. It can be much more fun if you have someone to learn with you, and it is for this reason that the following project arose. It comprises just one small circuit, and you build an identical circuit for each of the people who want to learn with you. All the individual circuits are connected with their output leads in *parallel*, as the two-way circuit of **Figure 1** shows.

A simple circuit

This diagram shows two identical circuits, as would be used if two people wanted to learn together. The circuit centres around our old friend the NE555 integrated circuit (IC). As it is connected here, it works as an *astable multivibrator*, a daunting name for what is essentially an oscillator. Each circuit is self-contained, having its own battery, Morse key, sounder and


© RSGB
STATION A
STATION B
RV1 100k
R1 10k
R2 10k
9V
IC1 555
R3 1kΩ
C1 22n
C2 47n
Morse key
E1 . High impedance ear-piece
Twin inter-connecting cable
E1
1
2
3
4
5
6
7
8

Figure 1 The circuit diagram shows two stations, but you could connect several more if needed

plastic box. The Morse key makes and breaks the power supply to the circuit, thus turning on and off the note emitted by the earpiece. The frequency of the note is controlled by the variable resistor RV1, resistors R1 and R2, and the capacitor C1. The range given by RV1 is approximately from 500 Hz to 2200 Hz.

R3 protects the output of the IC against accidental shorting either to the 0 V or to the 9 V supply rails. For best results, a crystal earpiece or high-impedance headphones should be used. You could try Walkman-type headphones, but the volume may be too low for you.

The units may be interconnected with thin twin cable (the sort used for wiring doorbells) and can be comfortably separated by 25 m, more than enough to communicate between rooms, or even with a neighbour!

In use

When an operator presses his key, the note is heard by himself and by everyone else who is connected. If more than one key is pressed at the same time, two or more notes are heard by everyone! It helps if each person adjusts his own potentiometer, RV1, to give a note which is different from the others. When one operator stops sending, the other can start immediately, without pausing to change from transmit to receive. In practice, this technique is known as *full break-in*.

The current drawn by the circuit is only 10 milli-amps (mA) when the key is down, meaning that the life of a typical PP3 battery will be virtually its shelf-life! No switch is needed, because the key acts as the switch. The current drain will be even less if the NE555 is replaced by an ICM7555 IC. It has exactly the same pin connections as the NE555, so no circuit modifications are needed.

The circuit board

The circuit is constructed easily on a small piece of Veroboard of the copper-strip type. **Figure 2** shows the layout of the prototype, the board measuring 18 holes by 10 strips. **Be aware that there is no row 'I' when you are transferring mental images of where the parts are to real positions on the board!** Break the copper tracks where shown with a 3 mm (⅛ inch) twist drill, rotated carefully between thumb and forefinger. Hold the board up to a bright light to make sure that the tracks are completely broken and that there are no fragments of copper swarf shorting adjacent tracks. Then, solder in the wire links shown in Figure 2, followed by the resistors, RV1, and the capacitors, C1 and C2. Solder the battery connector leads to tracks A and G, G being positive. Use insulated wire to connect from the board to the jack sockets used as connectors for the key and the earphones. If you use


© RSGB
1 2 3 4 5 6 7 8 9 10 12 14 16 18
A
B
C
D
E
F
G
H
J
K
Morse key
9V
PP3
Ear-piece
Inter-connection
R3
R2
C2
C1
R1
1
IC1
VR1
Cut in copper track
Solder
Insulated wire link

Figure 2 The Morse Duet is an easy project to build on stripboard (Veroboard)

different sized jack sockets (i.e. 2.5 mm and 3.5 mm) you won't plug the earphones into the key socket! A two-screw terminal strip is useful to connect the cable runs between operators.

The key

The circuit is designed to be used with a *straight key* (one that moves up and down). It is a requirement of the UK Morse test that a straight key is used, so it is very sensible to learn sending with a straight key before you try anything more complex! You will find many to choose from at rallies.

Parts list

		Maplin order codes
For each board, you will need:		
Resistors: all 0.25 watt, 5% tolerance		
R1, R2	10 kilohms (kΩ)	M10K
R3	1 kilohm (kΩ)	M1K0
RV1	100 kilohm (kΩ) min. preset (horizontal mounting)	UH06G
Capacitors		
C1	22 nanofarads (nF) ceramic, 25 V	WX78K
C2	47 nanofarads (nF) ceramic, 25 V	RA47B

Integrated circuit	
IC1 NE555	QH66W
Additional items	
8-pin DIL socket	BL17T
Jack plug and socket 2.5 mm	HF76H, HF78K
Jack plug and socket 3.5 mm	HF80B, HF82D
Battery type PP3	
Battery connector	HF28F
Plastic box with lid 114 × 76 × 38 mm	LH14Q
Veroboard 0.1 inch with copper strips 18 holes × 10 strips	JP46A
Terminal strip (two section)	FE78K
Crystal earpiece	LB25C
Morse key	

27 The Colt 80 m receiver – Part 4

Introduction

In Parts 1 to 3 of this series, the design of an 80 metre direct-conversion receiver has been described. In this final part, we are going to change the circuit to operate as a superheterodyne receiver, or *superhet*. Most radio receivers are superhets, and they change the incoming signal to another frequency, known as the *intermediate frequency*, or IF, before producing an audio signal. The use of a superhet in a good receiver is mandated by the requirements for good *sensitivity* and *selectivity.*

Sensitivity and selectivity

Figure 1 shows the block diagram of the receiver. If you look closely, you will see that it is two similar circuits, one after the other. The incoming



Figure 1 This is how the different stages of the Colt go together to make a superhet receiver

signal is filtered and fed to a mixer where it is combined (mixed) with the signal from the variable-frequency oscillator (VFO). This oscillator operates at a frequency which is 455 kHz higher than the incoming signal from the aerial, and the mixer output is therefore at a frequency of 455 kHz. If you are not sure about this, please refer to the section 'The direct conversion process' in Part 3 of this project. This new frequency is called the *intermediate frequency*, or IF. This frequency doesn't change; the tuning is accomplished by the VFO, and the mixer output is *always* at 455 kHz. The extraction of the audio signal from the IF signal is identical with the direct conversion process which is used in your existing receiver.

This may seem a long-winded way of doing things, but it has its advantages. A receiver must have a good *sensitivity*, or gain, so that it can receive very weak signals. In very general terms, it is easier to handle low-frequency signals than it is to handle high-frequency signals. We are changing our signal frequency from around 3.6 MHz down to 0.455 MHz (455 kHz), which is much lower and can be filtered and amplified relatively easily. A second advantage is that it is easier to provide gain at a fixed frequency than at a variable frequency. Remember that the IF is fixed, and providing gain is, again, relatively simple.

Our receiver also needs good *selectivity*, the ability to separate (or select) one station from another very close to it in frequency. This requirement is significantly simplified by the fact that the IF is fixed, and a good filter in the IF circuits can do wonders for the rejection of adjacent-frequency stations! Several stages of IF amplification and filtering are possible in more adventurous designs.

The filtered signal at 455 kHz passes to another mixer which has an associated oscillator, usually called a *beat frequency oscillator* (BFO). When receiving CW (Morse) signals, the BFO is usually tuned about 1 kHz above or below the IF (i.e. at 454 or 456 kHz) to produce a 1 kHz beat note as the audio signal. This signal is then amplified and fed to a loudspeaker or headphones.

The circuit

Figure 2 shows the circuit of the IF section shown in the photograph on p. 94; this section is added to the existing circuit to make it a superhet. The existing mixer board (described in Part 3) is used as the first mixer. Between it and the audio amplifier is connected the new IF board.

The signal output from the first mixer (at 455 kHz IF) is fed into a *crystal filter*, the most expensive part in the whole receiver. It provides the selectivity which makes the Colt such a good receiver. Another NE602 mixer/oscillator chip follows the filter. The oscillator section is controlled by the tuned circuit in T1, the frequency of which can be altered by rotating the core inside the coil. Once set, it remains fixed.



Figure 2 The IF board is connected between the mixer and audio amplifier

At this stage you should have built the first mixer and the audio amplifier, and proved that they *both* work by using the circuit as a direct-conversion receiver. When you have finished constructing and checking the IF board, you will need to add it to your existing circuits.

Adjusting and testing

There are three pairs of connections to the IF board – the 9 V supply leads, the input leads and the output leads. The IF board should be mounted on the metal baseplate, along with the other boards. **In making the following connections, make absolutely sure that the braid of each piece of coaxial**

cable is soldered to the correct connection on each board. The same applies to the polarity of the 9 V leads. Disconnect the screened lead which presently goes from the first mixer board to the AF amplifier at the amplifier end. Connect it instead to the *input* of the IF board. Connect a new piece of screened cable from the IF output to the vacated AF input. Now connect the 9 V supply leads to the same points as the supply leads from the other boards. Check these newly made connections.

You should have confidence at this point that things should be right. After all, you *have* tested the direct-conversion process and you *know* it works. All that you are now testing is the IF board. This is the attraction of building a receiver in modules, working from the speaker backwards, and testing as you go!

The VFO and BFO need to be correctly adjusted. Mesh the vanes of the tuning capacitor and, using the same frequency measurement method as you did originally, set the VFO frequency to 3.955 MHz (which is 3.500 MHz + 0.455 MHz, if you hadn't guessed!). The BFO can be set using a frequency counter, but it is just as good to set it by listening to SSB or CW signals. A high-pitched hissing sound should be heard in the speaker. As you rotate the core, the pitch should reduce, go through a minimum, then increase again. Set the core at the minimum pitch position. You may want to readjust the two cores a little as your listening skills improve but, once you are happy, they will never need to be altered again!

In conclusion . . .

You should now have built a superhet receiver capable of excellent results. It uses the same type of circuit as that found in far more advanced receivers.



The superhet is far more sensitive than the direct-conversion type, and can weed out those elusive DX stations. You may have found that a station will appear at two places on the dial of the direct-conversion receiver; you will have no such problem with the superhet.

Parts list

Resistor

R1	1 kilohm (kΩ), 0.25 watt, 5% tolerance

Capacitors

C1, C2	10 nanofarads (nF) min. ceramic
C3, C6	100 nanofarads (nF) min. ceramic
C4	22 nanofarads (nF) min. ceramic
C5	1 microfarad (μF) 16 V electrolytic
C7	220 microfarad (μF) 16 V electrolytic

Integrated circuit

IC1	NE602

Additional items

ZD1	Zener, 6.2 V 0.5 watt
FL1	Crystal filter, Murata CFM455J
T1	Tuned inductor, Toko YHCS11100AC

28 A simple crystal set

Introduction

There are many designs of crystal set – they are all ‘simple’, and even the most seasoned radio amateur will build one of these every so often because it is something that never ceases to amaze! Although using modern components, the design is a period piece!

Design and construction

The circuit diagram of **Figure 1** shows the simplicity of the circuit. The prototype was constructed on a wooden baseboard with an aluminium front panel, although this could be made of wood if you prefer.

Winding the coil always causes the most groans but when finished, gives the most satisfaction. The construction of the coil is detailed in **Figure 2**. A discarded toilet roll centre is an ideal *former* on which to wind the coil. The coil will take up about 7 cm of the length of the tube, so assuming the tube is about 11 cm long, the ends of the coil will be about 2 cm in from each end of the tube.

The aerial coil, the *primary winding* of this radio-frequency (RF) transformer, is made from about 30 turns of 26 SWG enamelled copper wire, wound on the matchstick ribs. These ribs should be about 2 cm long, and are glued on **top** of the end of the secondary coil *after* the secondary coil has been wound. The *secondary winding* has 140 turns with *taps* every 10 turns for 70 turns. This coil covers most of the length of the cardboard tube. To make your coil-winding easier, here are some tips for completing the coil and still having some hair left at the end!

- Support the reel of wire on a dowel rod or pencil, clamped in a vice or held rigid in a vertical position by some other means. Don't leave it to trail around on the floor.
- Have a small piece of sandpaper handy to remove the enamel from the copper wire, starting with the end coming from the reel. Remove about 1 cm only, until the shiny copper is visible all round the end of the wire.



Figure 1 Circuit diagram of the crystal set


C
Taps every 10 turns
Primary or antenna coil, 30 turns
Approx 40mm dia
A
6 matchstick ribs glued in position
Secondary or tuning coil, 140 turns closewound with 26swg, or similar, enamelled copper wire
D
B

Figure 2 The coil is mounted on a cardboard tube as shown. Exact size is not too important. Try different taps for best results

- This part is the most difficult of all. Seasoned coil winders may have their own favourite ways of doing this, but for first-timers, play it safe and do it this way! Have a second bobbin (or a piece of stout card) ready, on which you will need to wind the wire loosely while you prepare the taps. Then, starting from the free end of the wire, measure 125 cm and, at this point, remove about 2 cm of the enamel with the sandpaper. Bend the wire firmly back on itself in the middle of the bared area, and *tin* (cover with solder) the exposed copper. This is your first tap. Then repeat this six more times at 125 cm intervals, thus giving you seven taps; wrap the wire as you go, on to the second bobbin or piece of card. After the seven taps, you are half-way down your coil so, to begin winding it in earnest, wind the wire carefully from the second bobbin or card **back** on to the original reel of wire.
- Looking at Figure 2, make two small holes about 3 mm apart, about 2 cm down from the top of the tube, where wire C will be entering. Poke the end of the wire into one hole, then bring it out again through the other; leave about 10 cm of wire on the free end. Loop this wire in and out once more, thus anchoring the wire firmly.
- Then, begin winding; keep the wire tight and make adjacent turns touch neatly. As you pass each tap, make sure it sticks outwards while avoiding flexing the wire too much; the wire is inherently weak at each tap.
- When you reach the last 10 cm of wire, stop. Put two more holes, like the first, beside your stopping point, and anchor the end, D, of the coil in the same way as you did with end C. The secondary winding is complete. Take a break *after* you have completed the next step!

- Prepare the six matchsticks for supporting the primary coil and glue these every 60 degrees around the end of the coil at D. Remove the enamel from the free end of the new copper wire on your reel and, using your favourite quick-drying cement, put a drop over the wire on one of the matchsticks, leaving 10 cm free as before. If you are using 26 SWG enamelled copper wire, its diameter is 0.46 mm, so 30 turns should occupy 14–15 mm of the 20 mm matchstick length. This will allow you to position the glued point such that the coil will be roughly in the centre of the matchsticks. When the glue has set, wind the 30 turns and anchor this end of the coil in the same way. Then remove the enamel at the end of the 10 cm lead.

Assembly

The coil former can be screwed to the baseboard at each end, *before* the front panel is screwed to the baseboard! As the photograph on the next page shows, the tuning capacitor is mounted in the centre of the front panel. Five solder tags (or drawing pins as a last resort) should be screwed into the baseboard. The two to the left of the photograph are the connections to the earphones, the two along the rear edge have the diode, D1, soldered to them. One end of the diode (and, for once, you can connect the diode either way round!) is connected to one earphone tag. The other end has a flying lead of about 10 cm attached to it and terminated in a crocodile clip which is used to connect to one of the taps on the coil. The fifth tag secures the end, A, of the primary coil, to which you will attach the aerial. The earth tag on the tuning capacitor, C1, serves as an anchor point for the ground connections to B and D and to the other earphone tag.

Use

The longest piece of wire you have available to use as an aerial should be connected to the aerial tag just mentioned. If you can connect the earth tag of the tuning capacitor to a good electrical earth, this will help also. You should be able to hear something as you turn the tuning knob. Try adjusting the tapping connections on the coil – change only one at a time, or you will never find the optimum positions. You now have a fully operational crystal set!

Simple it may be, but this circuit illustrates some important principles which are used even in the most expensive receivers. Firstly, the coil, L1, and the capacitor, C1, form a *tuned circuit* which *resonates* at the frequency of the station you have tuned in. This *selects* the signal you want to hear. The *modulation* on this signal is removed by the *detector*, D1, and fed to the earphones, which act as *transducers*, turning the electrical energy into sound energy which you can hear. It doesn't need a battery or other power supply either!



Parts list

Capacitors

C1	Variable capacitor of between 200 and 500 picofarads (pF) maximum
C2	100 picofarads (pF) min. ceramic

Additional items

D1	Germanium, type OA47 or OA90
	High impedance crystal earphone (not Walkman type)
	Tuning knob
	Wooden base, approx. 110 mm square
	Aluminium (or wood) front panel, approx. 80 × 100 mm
	Cardboard tube (toilet roll centre), about 110 mm long, 40 mm diameter
	Reel of 26 SWG enamelled copper wire for both windings of L1

29 A crystal calibrator

Introduction

A crystal calibrator is a device that produces oscillations of a precise frequency which are rich in *harmonics*. A harmonic is an integer multiple of the fundamental frequency; for example, if our fundamental frequency was 100 kHz (as it is in this circuit), there would be harmonics of this frequency at 200 kHz, 300 kHz, 400 kHz, and so on. These harmonics can be used, when picked up by any receiver, to calibrate that receiver, as the harmonics are quite accurate in frequency (see later for an assessment of accuracy). However, a gap of 100 kHz between harmonics is rather wide for most purposes, so we reduce this frequency to 25 kHz, so that the harmonics are then 25 kHz apart, thus producing a much more useful set of *marker points*. A calibrator such as this is often called a *crystal marker*, producing these marker points from 25 kHz to beyond 30 MHz.

The circuit

The circuit diagram is shown in **Figure 1**. The circuit around TR1 is the fundamental oscillator, and its frequency is controlled by the quartz crystal, X1. Even crystal oscillators are not 100% accurate, and the small trimmer capacitor, TC1, is able to 'pull' the frequency to one which is nearer the


© RSGB
R5
2k2
R6
150R
TC1
6–
60p
R1
180k
X1
3
7
100
kHz
C2
1n0
R4
1k0
TR2
2N3904
D1
5V1
0W4
C4
100n
SW1
On/Off
R2
15k
b
c
e
TR1
2N3904
C1
2n2
C3
1n0
R3
6k8
2 3 4 6 7 10
1
IC1
74LS73
9
C5
12p
Output
(Phono
socket)
+
9V
PP3
Battery
−
5 12 11
TR1
7
X1
3
TC1
Base view of
crystal socket (B7G)
e b c
Base view of
transistor
2N3904
D1 5V1 0W4
Zener diode
7 1
8 14
IC1
7473 or 74LS73

Figure 1 Circuit diagram of the calibrator which uses easily obtainable components

correct one. TR2 is a *buffer* stage, which isolates the oscillator from the rest of the circuit. It acts as a switch, and applies a good signal (switching between 0 and 5 V) to the input of IC1.

IC1 is an integrated circuit which can be connected to do several things. It is connected here to divide the incoming frequency by a factor of 4, producing on pin 9 an output frequency of 25 kHz.

The combination of R6, C4 and D1 produces a supply of 5 V for IC1; it would be damaged if the battery voltage were applied to it. You will no doubt be ready to assemble the circuit, so here is some information for you.

Construction

If possible, always build a circuit in individual stages, which you can test as you go along. It is not always easy in small projects like this, but even the crystal calibrator can be split into two for construction and testing.

It is an ideal project for assembly on Veroboard of the copper-strip type; the prototype layout is shown in **Figure 2**, on a board measuring 11 holes by 24 strips. First of all, remove the copper strip at the locations shown, using a 3 mm drill rotated between the fingers. Hold the board up to the light to ensure that there are no pieces of copper swarf bridging adjacent strips, and that the copper is completely removed where it should be! Assemble the circuit from left to right, but do not wire up anything around IC1. Be aware that the diagram shows the board *from the component side*. Although you


© RSGB
Crystal
pin 7
TC1
11 holes x 24 holes
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24
A B C D E F G H I J K
IC1
7
8
14
D1
TR1
TR2
R1
R2
R3
R4
R5
R6
C1
C2
C3
C4
–ve
+9V via SW1
Out 25kHz to phono socket
indicates break in copper track
indicates insulated wire link on copper track side

Figure 2 Stripboard, such as Veroboard, should be cut as shown to approx. 62 × 28 mm

can use virtually any kind of crystal, you will need to mount it firmly. If you use a small one, it can be soldered directly in position on the board. With one in a valve envelope, you will need a B7G valveholder. Be prepared to mount the circuit in a **metal** container; the prototype used an (empty) tin of tuna! The valveholder mounts well on any metal case.

Disconnect the aerial of your receiver, and replace it with about 30 cm of wire laid near your oscillator circuit. Connect the battery and switch on. Tune the receiver around until you can hear a whistle on SSB. Rotate the tuning knob to reduce the frequency of the whistle and, as the whistle becomes too low to hear, you have reached one of the calibration markers, and your frequency will be an integer multiple of 100 kHz. If you are already using a calibrated receiver, you will be able to verify this. Going up or down in frequency should locate another marker 100 kHz away, and so on right through the receiver's tuning range. If the signals coming from the circuit are very weak, switch off the calibrator and connect another 30 cm piece of insulated wire to the collector of TR2, and lay it close to (but *not* touching) the wire from the aerial connector. Switch on an try again; you should not now have a problem! If you have access to a multimeter, check that the voltage at the collector of TR1 is very close to 5 V. If it is close to 9 V, you have connected the diode, D1, the wrong way round!

Having verified that the oscillator is working, you can now wire up the integrated circuit socket, being careful to put the notched end of the socket pointing towards R4, the collector resistor for TR2.

Check your connections around IC1, and when you are satisfied that they are correct, line up IC1 with its socket, making sure that the notched ends are together, and press down *gently* to insert the IC into its socket. Insert the 30 cm piece of insulated wire into the output socket, connect the battery and switch on. You should still hear whistles in your receiver, but now they should be 25 kHz apart, rather than 100 kHz apart.

All that now remains to be done is to mount the circuit rigidly inside whatever casing your have chosen. Make sure that none of the connections under the board touch the metal case, and secure the valveholder, on/off switch and output connector to the case. You now have a completed crystal calibrator.

Calibration

The simplest way to calibrate your circuit is with a frequency counter. Most clubs will have one of these and, if not, will know someone who has! Connect it to the collector of TR2, where the frequency should be 100 kHz. Do *not* connect it to any part of the circuit around TR1, or you may alter the frequency you are trying to measure! If the frequency is not exactly 100.000 kHz, rotate TC1 until it is (or is as close as you can get it). Now your calibrator is as accurate as the counter with which you have calibrated it.

Accuracy

Despite your best efforts at calibration, by whatever means, your crystal will *never* have a constant frequency. Such a thing is a scientific impossibility. It is usual to express the accuracy of a crystal in parts-per-million (ppm), and it is governed by many things, principally its temperature. You will be *very* fortunate if your circuit maintains an accuracy better than about ±10 ppm. Expressed in figures, it means that the true frequency can be anywhere between 99.999 kHz and 100.001 kHz, i.e. within 1 Hz of the correct frequency.

Although this may seem more than adequate, it is as well to remember that the accuracy degrades as the frequency increases. At 1 MHz the error will be ±10 Hz and at 10 MHz it will be ±100 Hz. At 30 MHz it will be 300 Hz. Even so, this should be acceptable for most non-critical applications.

Parts list

Resistors: all 0.25 watt, 5% tolerance		**Maplin code**
R1	180 kilohms (kΩ)	M180K
R2	15 kilohms (kΩ)	M15K
R3	6.8 kilohms (kΩ)	M6K8
R4	1 kilohm (kΩ)	M1K0
R5	2 kilohms (kΩ)	M2K0
R6	150 ohms (Ω)	M150R
Capacitors		
C1, C2, C3	1 nanofarad (nF) or 1000 picofarads (pF)	WX68Y
C4	100 nanofarads or 0.1 microfarad (µF)	YR75S
C5	12 picofarads (pF)	WX45Y
TC1	60 picofarads (pF) trimmer	WL72P
Semiconductors		
TR1, TR2	2N3904 npn	QR28F
IC1	7473 or 74LS73N dual JK flipflop	YF30H
D1	5.1V 500 mW Zener	QH07H
Additional items		
100 kHz crystal		
B7G valveholder (found at most rallies)		
14-pin DIL IC socket		BL18U
Phono socket		YW06G
PP3 battery connector		HF28F
PP3 battery		
On/off switch		FH00A
Veroboard		JP47B
Metal case as required		

30 A simple short-wave receiver – Part 1

Introduction

No apologies for yet another design of short-wave radio. This is the beauty of our hobby – there is always something new to try. Not all circuits operate in the same way; not all circuits work equally well; sometimes a simple design suits the operator better than a complicated design. So here is another one for your consideration; it's a good project for a novice, *and* a good one-evening project for someone more experienced.

A basic description

Figure 1 gives the block diagram of the receiver, which employs a *regenerative detector*, one of the earliest techniques by which excellent *selectivity* (the ability to separate two stations very close in frequency) could be combined with good *sensitivity* (the ability to pick up very weak stations) using a very simple circuit. The receiver falls into the category known as *tuned radio frequency* (TRF), meaning that the whole circuit (prior to the extraction of the modulation from the carrier) operates at the incoming radio frequency. In other words, it is *not* a superhet.

As you can see, the regenerative detector has what is called a *feedback loop*, which feeds a small amount of the output signal back to the input. You have heard the effects of feedback with a public address system, when the microphone gain is too great – everything becomes very loud and then bursts into a deafening squeal! This is exactly what the feedback does here, except that it is carefully controlled, thus providing both gain and selectivity. The resulting audio is then amplified for use with headphones.



Figure 1 Just two simple stages make up the circuit

The circuit

The circuit of **Figure 2** shows the complete system. TR1 is an untuned *field-effect transistor* (FET) stage, and is used to match the aerial to the next stage. Occasionally, a regenerative detector produces unwanted signals, and TR1 also prevents them from reaching the aerial and being transmitted! The smaller of the two windings on T1 (the *primary* winding) will match a low-impedance aerial, the capacitor input matching a high-impedance aerial.

Ignore TR2 for the moment – the next stage in the signal path is TR3, the detector, using another FET. The tuned circuit is formed by T2, VC1 and VC2 (remember TR1 is untuned). The primary winding on T2 taking the output from TR1. The reason for having two variable tuning capacitors, one large, the other small, is that the large capacitor is the main tuning capacitor, while the small one is used as a *bandspread* control (for very fine tuning). The tuned signals are then detected (converted to audio frequencies) by TR3.


© RSGB
C1 27p
Hi-Z
Antenna
Lo-Z
T1
R2 270R
C2 100n
TR1 2N3819
d
g
s
R1 330R
C4 10n
T2
C5 33µ
VR1 10-turn Pot
C3 10n
R3 22k
VC2 200/200p
VC1 10p
R4 47k
C6 10n
C7 68p
C8 330p
C9 330p
TR2 BC182
R5 270R
R6 3k3
C10 10n
R7 4k7
TR3 2N3819
C11 33µ
C12 10n
D1 6V2
R8 27k
R9 470k
C14 10n
C13 10n
C15 1n0
A
B
0V
C
R10 330R
+9V
R11 270R
C16 10µ
R12 4k7
TR4 BC182
R13 2k7
C17 10µ
C18 100n
VR2 10k
C20 10µ
IC1 LM386
1
2
3
4
5
6
7
8
R14 10R
C21 150µ
C23 150µ
C22 100n
R15 10R
R16 1k0
LS 8Ω Loudspeaker
0V

Figure 2 The circuit diagram showing the 10-turn potentiometer VR1. This is the regeneration control for the circuit

TR2 is a *Q-multiplier* stage. It is a Colpitts-type oscillator which uses C8 and C9 to give feedback and produce the oscillation. C7 couples the tuned circuit (and the input to TR3) to TR2. The tuned circuit thus controls the frequency of oscillation of TR2 and the signal passed on to TR3.

The secret of the ease of operation of this receiver is VR2, a 10-turn potentiometer (or *helipot*). The resistance wire is wound in the form of a helix, giving a much greater wire length than in a normal potentiometer, and the shaft must be turned ten times to cover the whole length. Helipots are very useful when very fine adjustments have to be made. Here, VR2 sets the regeneration (or *reaction*) level, depending on the type of signal you are receiving, as will be discussed in Part 2.

TR4 provides the first stage of audio amplification and, after the volume control, VR2, the audio amplifier integrated circuit, IC1, will drive a small loudspeaker or headphones.

In Part 2, the construction will be discussed, together with the choice of aerial, the parts list, and advice on using the receiver.

31 A fruit-powered medium-wave radio

Introduction

This is a one-evening project that will result in a working medium-wave (MW) radio, and will also teach you a little about the way electricity can be generated from the right metals and a little (safe) acid. All you need are three lemons or other citrus fruit, three pieces of copper and three pieces of zinc (or galvanised metal) for your power supply.

Construction

Figure 1 shows the circuit and **Figure 2** its layout on a simple ‘plug-in’ prototype board. The six pieces of metal are connected as shown, to wire the three lemons in series; use ordinary wire between each lemon and the next. If you have a meter to measure the total voltage, it should be about 1.8 V. Use a standard ferrite rod, and wind on it about 40 turns of single-conductor PVC-insulated wire.


Antenna input
VC1
Tuning capacitor
Earpiece socket
V+
Coil wound on ferrite rod
Interconnecting tracks are shown dotted
V–
C1
D1
R1
R2
TR1
c
b
e

Figure 1 Most parts are plugged into the board as shown – soldering is not required


Wire antenna
C1
1n0
D1
OA91
diode
R2
1M0
R1
10k
Crystal earpiece
TR1
BC107
transistor
b
c
e
Coil wound on ferrite rod. 40-turns. 10mm dia
VC1
between 250p and 500p
CT
ZT
+
–
Lemon batteries
CT copper terminal
ZT zinc terminal

Figure 2 Three lemons power the radio, which gives good results for such a simple circuit

Wire up the circuit on the board as illustrated in Figure 2. Soldering is not required with this type of board – just plug in the components and the wires. Only one transistor is needed. The tuning capacitor, VC1, selects the station you want to hear, and D1 helps to remove the carrier from the RF signal. The resulting audio signal is fed to TR1, a small transistor audio amplifier, which makes the signal big enough to drive a crystal earpiece comfortably. Walkman-type earphones will not work, so invest in a crystal earpiece which you can use in several other projects, too! If you use a smaller capacitor than that specified for VC1, you will need more turns on the aerial coil.

Tests on the prototype indicated that the radio will run for about a week on three lemons!

Parts list

Resistors: all 0.25 watt, 5% tolerance	
R1	1 megohm (MΩ)
R2	10 kilohm (kΩ)
Capacitors	
C1	1 nanofarad (nF) min. ceramic
VC1	250–500 picofarad (pF) variable
Semiconductors	
TR1	BC107 npn (or BC108, BC109C)
D1	OA90, OA91 germanium (not silicon)
Coil	
L1	2 metres of single-conductor insulated wire on a standard ferrite rod

Additional items
- Plug-in prototype board, e.g. Maplin YR84F
- Wire aerial at least 3 m long
- Crystal earpiece
- Three juicy fruits



32 A capacitance bridge

Introduction

It is always valuable to have a means of measuring capacitors amongst your test gear. Universal LCR bridges (i.e. systems that can measure inductance, capacitance and resistance) can be found at most rallies, and you can work your way up to owning one of these. In the meantime, a piece of home-made equipment gives you experience as well as resulting in a useful measuring instrument.

The circuit described here is called a *capacitance bridge*, because it balances the effects of one resistor/capacitor pair against another; if one capacitor has an unknown value, then the other can be calculated. The basic bridge circuit is shown in **Figure 1**. To avoid having calculations to perform, this instrument will be calibrated by using capacitors of known values. The bridge is a useful way of performing measurements, because a knob is turned until there is a null in the signal from an earpiece or loudspeaker. The ear is very precise in being able to perceive nulls, which makes the bridge easy to use and reasonably accurate. At the null, the bridge is said to be *balanced*.

How does it work?

Figure 2 is the circuit diagram for this capacitance bridge. Transistors TR1 and TR2 form an oscillator. This is the audio oscillator shown in Figure 1, and produces an alternating voltage which is fed to the bridge. RV1 (in the collector lead of TR2) replaces both R1 and R2 in Figure 1 – that part of



Figure 1 Simplified circuit of a capacitance bridge. R1 is adjusted for minimum sound


R1
10k
R2
100k
R3
100k
VR1
10k
lin
SK1
Phones
C3
100p
SW1
On/Off
C1
10n
C2
10n
C4
47µ
16V
Cx
9V
PP3
c
b
e
TR1
BC108
TR2
BC108
Crocodile clips
Case
Base view of BC108

Figure 2 Transistors TR1 and TR2 give an audio signal which is adjusted by variable resistor RV1

RV1 *above* the wiper represents R1, while that part *below* the wiper represents R2. The voltage on one side of the earpiece is determined by the ratio of these values, and is adjusted by rotating RV1. The voltage on the other side of the earpiece is determined by the ratio of C3 to Cx, where Cx is the unknown-valued capacitor. When these two voltages are the same, the bridge is balanced and there is no current through the earpiece.

Figure 3 shows the layout of the components on the matrix board of the prototype. It measures 10 holes by 14 holes, and is of the plain type, i.e. no copper strips. All earth connections are taken to a single solder tag. When


+9V via SW1
1
2
3
4
5
6
7
8
9
10
R1
R2
R3
C1
C2
TR1
TR2
c
b
e
To VR1
To crocodile clip
Solder tag (6BA bolt to case)
1 2 3 4 5 6 7 8 9 10 11 12 13 14
Perforated board 10 x 14 holes

Figure 3 Components are soldered together on a small prototype board


VR1
With pointer, knob and scale
−ve
C4
C3
SW1
+9V
Perforated component board
SK1
Plastic or Perspex isolator
Crocodile clips
Cx
©RSGB X184

Figure 4 Layout of the parts inside an aluminium box. The earpiece socket is insulated from the case

mounting the board inside a metal box, a long screw is used with extra nuts, to earth the board to the case while providing a stand-off, thus preventing any unwanted short-circuits between the board connections and the case. Be aware that a *crystal* earpiece must be used; low-impedance headphones of the Walkman type are not satisfactory. Solder two flying leads as shown in **Figure 4**, about 15 cm long, terminated in small crocodile clips for attaching to the unknown capacitor.

Calibration

After checking the circuit carefully, attach the battery and switch on; a buzzing noise should be heard in the earpiece. This is the first sign that everything should be OK. If there is no buzz, switch off and recheck the connections.

You will now need a range of close-tolerance (1%) silver-mica capacitors covering the range 10 to 1000 picofarads (pF). Arrange the capacitors in ascending order and connect them to your bridge in sequence. After having prepared a neat piece of card or paper mounted behind the knob on the front panel, mark the dial at the positions of the nulls for all the capacitors. You have now calibrated your capacitance bridge. If you are more likely to want to measure larger capacitors, replace C3 by a 1 nanofarad (nF) capacitor, and the bridge will measure up to 10 nF approximately.

Parts list

Resistors: all 0.25 watt, 5% tolerance	
R1	10 kilohms (kΩ)
R2, R3	100 kilohms (kΩ)
RV1	10 kilohms (kΩ) linear
Capacitors	
C1, C2	10 nanofarads (nF) ceramic
C3	100 picofarads (pF) silver mica or polystyrene
C4	47 microfarads (μF) 16 V electrolytic
Semiconductors	
TR1, TR2	BC108 npn
Additional items	
SW1	SPST on/off switch
	Battery connector, PP3 type
	Earpiece, crystal type
SK1	3.5 mm jack socket for earpiece
	Battery, 9 V PP3
	Matrix board, approx. 10 holes by 14 holes
	Aluminium case, approx. 10 × 8 × 5 cm

33 A simple short-wave receiver – Part 2

Introduction

In Part 1, the design of this receiver was discussed in some detail. Now we are going to put it all together and see how it works. The receiver is laid out on a printed-circuit board (PCB) or on a matrix board.

Construction

The layout of the components is shown in **Figure 1**. Identify each part separately, insert it into the holes in the board and solder carefully. Long leads may be cropped before or after soldering, depending on your skill and preference. All electrolytic capacitors, T1, T2 and IC1, must be connected correctly. The front-panel controls are connected to the PCB terminals shown in Figure 1.

The layout of the controls and the placing of the board inside the case are matters of personal preference. The size of the prototype front panel is shown in **Figure 2**. The prototype had a slow-motion drive fitted to VC2, the main tuning capacitor. This required the capacitor to be fitted on its own small panel. The bandspread control does not need any form of


150µ
150µ
150µ
100n
LM386
1k0
10µ
100n
1n0
10R
10R
270R
4k7
2k7
10µ
10µ
10n
1n0
10n
330R
470k
270R
27k
TR4
10n
3k3
TR2
10n
D1
6V2
10n
10n
TR3
22k
47k
68p
330p
330p
T2
33µ
4k7
270R
10n
TR1
27p
T1
10n
330R
33µ
Hi-Z
Antenna
Lo-Z
0V
+9V
LS
Volume control
VR2
10-turn Pot
VR1
Tuning capacitors
VC1, 2

Figure 1 Layout of the receiver circuit board



Figure 2 The case can be metal or made from PCB material

slow-motion drive. A tuning dial may be fitted behind the tuning knob on VC2 if required. The volume control, VR2, has its own on/off switch for the battery, which can be mounted behind the back panel, on which are mounted the aerial input sockets and the headphone/speaker socket. Check your soldering carefully, together with all the wiring between the board, the potentiometers and variable capacitors. When you are confident that everything is perfect, connect the battery and switch on.

The first tests

If you have a good aerial and are using an aerial tuning unit (ATU), use the low-impedance input. Excellent results are possible, though, with about 3 metres of wire connected to the high-impedance input. Set the volume control to give a gentle hiss in the headphones or speaker. Advance the reaction control to give a definite hiss. As you tune in an AM station, the hiss will change to a whistle; back off the reaction until the oscillation *just* stops. The receiver is now correctly set for AM reception.

On the amateur bands, the stations will be SSB or CW, and the reaction needs to be set *just above* the oscillation point, and will need slight adjustment from time to time for different qualities of signal. Juggling with the volume, reaction and tuning is part of the pleasure of using regenerative receivers!

In action

Practice is needed for best results. The regenerative receiver is renowned for its versatility in being able to be set up *exactly* for all types and strengths of signal. The basic receiver tunes from 6.5 MHz to 11 MHz approximately; this includes two amateur bands at 7.0 MHz and 10.1 MHz and two broadcast bands.

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1, R10	330 ohms (Ω)
R2, R5, R11	270 ohms (Ω)
R3	22 kilohms (kΩ)
R4	47 kilohms (kΩ)
R6	3.3 kilohms (kΩ)
R7, R12	4.7 kilohms (kΩ)
R8	27 kilohms (kΩ)
R9	470 kilohms (kΩ)
R13	2.7 kilohms (kΩ)
R14, R15	10 ohms (Ω)
R16	1 kilohm (kΩ)
VR1	10 kilohm (kΩ) linear 10-turn potentiometer
VR2	10 kilohm (kΩ) log potentiometer

Capacitors

C1	27 picofarads (pF)
C2, C18, C22	100 nanofarads (nF)
C3, C4, C6, C10, C13, C14	10 nanofarads (nF)
C5, C11	33 microfarads (μF) 16 V electrolytic
C7	68 picofarads (pF)
C8, C9	330 picofarads (pF)
C15	1 nanofarad (nF)
C16, C17, C20	10 microfarads (μF) 16 V electrolytic
C21, C23	150 microfarads (μF) 16 V electrolytic
VC1	10 picofarads (pF) variable
VC2	200 picofarads (pF) variable

Semiconductors

TR1, TR3	2N3819
TR2, TR4	BC182
IC1	LM386
D1	6.2 V 0.5 W Zener

Inductors

T1	3 turns primary, 15 turns secondary, wound on 2-hole ferrite bead, with 28 SWG wire
T2	2 turns primary, 17 turns secondary, wound on a T68-2 toroidal former, with 28 SWG wire

Additional items
- Printed-circuit board
- Battery connector
- PP3 battery
- 8-pin DIL socket
- 8 ohm speaker or headphones (Walkman type)
- Case to suit



34 A basic continuity tester

Introduction

This little device can be built on a plug-in breadboard, and is ideal for testing fuses and cables, as well as doubling as a signal source for testing amplifiers, etc. It can even be used for testing npn transistors by replacing either of the transistors in the circuit, and seeing if the circuit still works!

Simple and quick to build

Using a plug-in breadboard, this circuit is so simple it could almost be built when you need it, and then dismantled again! If you want the circuit to make a different sound, the components to change are R2, R3, C1 and C2. Always make sure that R2 = R3 and C1 = C2, or the sound may be excessively 'edgy' and lacking in volume.

Basically, the circuit is an oscillator which drives a little loudspeaker directly. The fuse or cable you are testing is connected between the crocodile clips. If there is a current path between the two clips, the current also flows through the circuit, thus operating the oscillator and producing a sound from the loudspeaker.


© RSGB
+9V
(Battery +)
Crocodile clips
LS1
R1
12k
R2
47k
R3
47k
R4
390R
C3
100n
R5
100k
C1 47n
C2 47n
Optional audio output
TR1
BC108
TR2
BC108
0V
(Battery −)

Figure 1 The circuit diagram of the continuity tester

If you want to use the circuit to produce a signal to test an amplifier, for instance, connect the croc clip which comes directly from the battery to the junction of R1, R2, R3 and R4. This supplies current to the circuit while, at the same time, bypassing the loudspeaker. Use the two components R5 and C3 between the oscillator and your amplifier. The loudspeaker is bypassed because you will want to listen to the output from your amplifier, *not* from the oscillator!

Remember, NEVER test any equipment which is still connected to the mains electricity supply. Avoid testing anything which is switched on and has its own power supply. You may damage both your tester ***and*** the circuit you are 'testing'!

Parts list

Resistors: all 0.25 watt, 5% tolerance	
R1	12 kilohms (kΩ)
R2, R3	47 kilohms (kΩ)
R4	390 ohms (Ω)
R5	100 kilohms (kΩ) optional
Capacitors	
C1, C2	47 nanofarads (nF) ceramic
C3	100 nanofarads (nF), 0.1 microfarads (μF) ceramic optional
Semiconductors	
TR1, TR2	BC108 npn
Additional items	
LS1	Loudspeaker (8 Ω)
	2 crocodile clips
	Prototype circuit board
	PP3 battery connector
	PP3 battery

35 A charger for NiCad batteries

Introduction

The cost of replacing dry batteries can be alleviated to a great extent by the use of rechargeable batteries such as those containing nickel and cadmium (called *NiCads*). They are more expensive than the batteries they replace, but they can be charged hundreds of times and thus prove cheaper in the long run.

NiCads produce only 1.2 V per cell, compared with the 1.5 V of ordinary cells, so before you rush out and buy lots of these, please make sure that the equipment on which you plan to use them will work on the reduced voltage! For example, if you are using four cells to give you a 6 V supply, NiCads will give you only 4.8 V, which is quite a reduction. Using six cells to replace a 9 V battery will give you only 7.2 V. Not all equipment is happy with these reductions!

However, we all use them when we can, and they save substantial amounts of money. Here is the circuit of a charger to keep them in prime condition.

Charging NiCads – the ampère-hour

NiCads require charging at constant current, which means that connecting one across a normal power supply (constant *voltage*) is useless and can destroy it. They need pampering to the extent of needing a long charge (around 16 hours) at a rate dependent upon the *capacity* of the battery. By the capacity of a battery, we mean how much energy it can store. You will probably know that energy is measured in joules. For the purposes of storing energy in batteries, the joule is *not* the ideal unit, so we use one that is! This unit is the ampère-hour (Ah), and must be interpreted with some realism. For example, if the battery is rated at 2 Ah, it will deliver a current of 0.5 amp for 4 hours, or 0.25 amp for 8 hours. Provided the current is not too high, the product of the current (in amps) and the time for which it will flow (in hours) before the battery is flat will always be around 2 Ah. A workable ‘rule of thumb’ for calculating the charging current is that its value should be around one-tenth of the numerical value of the capacity; so, for our 2 Ah battery, a charging current of around 200 mA (2 ÷ 10 = 0.2 A or 200 mA) would be used.

Constant voltage to constant current

Many integrated circuit (IC) chips are available for use as voltage regulators, i.e. they supply a constant voltage. Most of these can be persuaded to become constant current supplies with one external resistor!

The voltage regulator IC usually has only three connections – ‘input’, ‘output’ and ‘common’. It is designed (in the case of the LM7805) to produce a constant 5 V output between the ‘output’ and the ‘common’ connections, at currents of up to 1 A. If a resistor is connected between these, the IC will maintain 5 V across it. If you look at **Figure 1**, you will see the circuit performing this conversion.



Figure 1 Voltage regulator arranged to produce a constant current

For the previous example, we derived a charging current of 200 mA, so we now need to calculate the value of resistor that will produce this current. Using the equation which is derived from Ohm’s law:

$$I = \frac{V}{R}, \text{ from which } R = \frac{V}{I},$$

where R = R1, the resistance in ohms that we are calculating,
V is the voltage across R1 (5 V), and
I is the current flowing (200 mA).

So,

$$\text{R1} = \frac{5}{0.2} = 25\,\Omega.$$

25 ohms is not a ‘common’ or ‘preferred’ resistor value, so we must choose the next *largest* value, which is 27 Ω. This reduces the current, but only slightly – it is now 185 mA. When calculating resistor values in power supply circuits, we must *always* check the power that they dissipate and make sure we specify and fit a suitable resistor.

Power (in watts) is the product of the voltage across and the current through a device, so in this case it is given by:

$$\text{Power} = V \times I = 5 \times 0.185 = 0.925\,\text{W}.$$

Rather than use a 1 watt resistor operating very near its limit, it is safer to use a 2 watt resistor operating well within its limits.

Looking again at Figure 1, we now have a constant-current source producing 185 mA, when R1 is a 27 Ω, 2 W resistor. For use with NiCads requiring charging currents other than 200 mA, you will need to repeat the two equations above, using a new value for *I*.

The full circuit and its assembly

This is shown in **Figure 2**, and can be broken down into two parts. The first is the AC to DC conversion produced by the mains transformer, T1, the bridge rectifier, BR1, and the smoothing capacitor, C1. The second is the constant-current section already discussed.



Figure 2 The complete circuit including mains components

The prototype was assembled on matrix board measuring 18 holes by 12 strips, although, as **Figure 3** shows, this is much larger than is strictly necessary. No strip cutting is needed, but make sure that IC1 and C1 are inserted correctly.

Warning! Before you attempt to wire up the transformer and the bridge rectifier, be aware that you will eventually be connecting the circuit to the mains supply, so there are three possibilities for you: (1) get a qualified friend to supervise your completion and testing of the circuit; (2) get your qualified friend to complete and test the circuit for you; (3) replace the transformer and bridge rectifier with a mains adapter.



Figure 3 The charger can be built on Veroboard

If you decide to use the mains adapter, its output is connected directly across C1, because T1 and BR1 are now no longer needed. Make sure the polarity (positive and negative) is correct and that the adapter output is set to 12 V.

A quick test

If you have built the mains version, make sure all connections are correct, and that there are no soldered joints which will touch other parts of the circuit. The box must be securely closed before tests begin. The RSGB cannot be held responsible for damage to equipment or batteries! The version using the mains adapter need not be closed during tests.

Switch on. With nothing connected to the output, the unit should run cold. If this is not the case, switch off and recheck your circuit. If all is well, switch on again and connect a DC multimeter (on the current range) across the output. It should indicate only a slight difference from the calculated value of 185 mA. You can now charge your NiCads!

Other charging currents can be set by having different values for R1, perhaps selectable by a rotary switch. Remember to make sure that the values of both resistance *and* power dissipation are correct, and don't exceed the 250 mA rating of the transformer (or the 1 amp rating of the IC if you are using a bigger transformer).

Parts list

		Maplin code
Resistor		
R1	As required – see text	
Capacitor		
C1	1000 microfarads (µF) 35 V electrolytic	FF18U
Semiconductors		
IC1	LM7805 5 V, 1 A regulator	CR14Q
BR1	W005 50 V, 1 A full-wave rectifier	QL37S
Transformer		
T1	9–0–9 V, 250 mA sub-min. transformer	YN15R
Additional items		
Case		FG41U
Veroboard, 18 holes by 12 strips		
Plug to suit NiCads		
Double-sided sticky tape as required		
Insulated wire for battery connections		

36 An 80 metre crystal-controlled CW transmitter

Introduction

A simple transmitter is ideally suited to anyone venturing into our marvellous hobby for the first time. If you are put off by the complexities and prices of the 'black boxes' then this is the transmitter you've been looking for!

The circuit

The complete circuit is shown in **Figure 1**. It is a single-transistor crystal oscillator which is *keyed* (switched on and off) by the Morse key in the +12 V supply rail. The circuit first appeared in *QST* (the American equivalent of *RadCom*) in 1982, and has since appeared in a modified form in the *ARRL Handbook*. The circuit can produce about 2 watts on 80 m, and can be constructed on a piece of plain matrix board; the prototype board measured 7 cm by 3 cm, and its layout is shown in **Figure 2**.

Note that a bare copper wire runs along the bottom edge of the board to act as an earth wire for the relevant components. The only ‘difficult’ part of the construction is the winding and wiring of T1. The main winding is 38 turns of 26 SWG enamelled copper wire, and there are two link windings of four turns each. Make sure that all windings are wound the correct way round the toroid – Figure 1 shows this and should be studied carefully. If the windings do not have the correct *sense* (i.e. a clockwise coil has been wound anticlockwise, or vice versa), or have been connected incorrectly to the rest of the circuit, the oscillator will not work!

When putting components on the board, wire in the crystal socket *without the crystal in it*. Crystals do not like to be subjected to the horrors of a soldering iron, so keep your crystal to one side during the construction process!


© RSGB
C2078
TR1
2SC2078
b c e
TR1
collector
+12V
4-turn
link
To VC1
38-turns
T1
4-turn
link
To L1
T1... 38-turns of 26swg wire wound
on T-50-2 toroid - 2 link windings of
4-turns (each) wound with 26swg wire
C1
1000p
(1n0)
C2
100p
Crystal
TR1
2SC2078
Ferrite
bead
b
c
e
C4
100p
D1
1N
4148
R1
12k
L1 ... 21-turns of 22swg
wire wound on
T-50-2 toroid
T1
VC1
100p
C3
100p
RF out to
changeover
switch
L1
C7a
680p
C7b
68p
C8a
680p
C8b
68p
C5
10n
+
C6
10µ
25V
Key
+12V

Figure 1 The simplest form of transmitter is a keyed crystal oscillator. Note that L1, C7 and C8 make up a *low-pass filter* which reduces unwanted *harmonics* (outputs at the transmitter frequency multiplied by 2, 3, 4, etc.)


7 x 3cm perforated board
To +12V via key
Crystal
C2
C1
C6
C5
R1
L1
To changeover switch
RFout
C7a
C8a
C7b
C8b
To crystal
T1
TR1
b
c
e
D1
C4
VC1
To TR1 base
C3 mounted on underside
Large heatsink for TR1
------ wires on underside of board
Ferrite bead on TR1 base lead
RG174 miniature coaxial cable or screened audio lead
To L1
To antenna socket on rear panel
To receiver socket on rear panel
Changeover switch
To key
+12V socket on rear panel
no connection
© RSGB

Figure 2 Component layout is straightforward on a 'matrix board' (it has holes but no copper strips). The dotted lines are the connecting wires. The lower part shows the connections for the transmit/receive switch

The output filter, which comprises C7, C8 and L1, is a *low-pass* filter, which helps reduce any *harmonics* present in your signal. Harmonics are integral multiples of your transmitter frequency, so if you are transmitting on a frequency, *f*, harmonics will be present at frequencies 2*f*, 3*f*, 4*f*, . . . and so on. L2 is another inductance using 22 SWG enamelled copper on a ferrite toroid. The changeover switch is external to the transmitter board, and is used to switch your aerial between the transmitter and the receiver; its wiring is shown in Figure 2.

Use a dummy load

A dummy load enables you to test your circuit without actually transmitting a signal. If you haven't such a thing already, it is easy to construct one to use with this transmitter. Don't use it for transmitters of more than 2 watts output, though. Use two 100 ohm, 1 watt resistors, connected in parallel across the end of a short piece of coaxial cable, terminated in a BNC, PL259 or N-type free plug, as shown in **Figure 3**. Plug this into the aerial socket on your transmitter, plug in your crystal and connect the transmitter to a 12 V supply. Have another receiver switched on and tuned to the crystal frequency. Although the radiation from your dummy load is minimal, it will

Figure 3 A simple 2 W dummy load can be made from two 100 Ω (ohm) resistors in parallel. The plug should match the socket on your transmitter



be enough to be picked up by a receiver in the same room. Send dashes with the Morse key, and adjust VC1 until the received note is *clean*. It should not sound rough, or have a *chirp* (change its frequency during a dash or dot). Avoid tuning for maximum power; this is seldom the correct setting!

You will need to put your completed transmitter in a metal box, using sockets for the power supply, aerial, receiver and Morse key. The sockets can be chosen to match your existing equipment.

Figures 4–7 are taken from the RSGB book *Practical Antennas for Novices*, and may give you some ideas on the type of aerial to be used with your transmitter.

Figure 4 A simple dipole can be very effective. For the 3.5 MHz band, length L is 40 metres and height H should be as large as possible. The far support S can be a tree, pole or building. Insulators I may be home made from strong plastic and the feeder F should be 50 Ω (ohm) coax cable



Figure 5 Your signal is radiated mostly from the centre of the dipole so the ends can droop or even be bent but the length may need shortening by a few centimetres because the ground and the bends will detune the dipole. Cords C are best made from strong plastic rope from a sailing or camping shop




© RSGB
20m
10m

Figure 6 An 'inverted-L' takes up less space than a dipole and doesn't need coax cable. Like the dipole, the end can droop or be bent to save space as in this case most of the radiation comes from the area around the top of the vertical part


Wire to
antenna 1 (switched)
ATU
Transmitter/Receiver
SWR Meter
50Ω
50Ω
50Ω
Earth
wire
Coaxial feeder
to antenna 2 (switched)
© RSGB

Figure 7 Almost any length of wire more than 10 m or so long will work (though it will work better the longer and higher it is) but an Aerial System Tuning Unit (ASTU or ATU) will be needed



Parts list

Resistor

R1	12 kilohms (kΩ), 0.25 watt, 5% tolerance

Capacitors

C1	1000 picofarads (pF) polystyrene
C2	100 picofarads (pF) polystyrene
C7a, C8a	680 picofarads (pF) polystyrene
C7b, C8b	68 picofarads (pF) polystyrene
C3, C4	100 picofarads (pF) ceramic
C5	10 nanofarads (nF) polyester
C6	10 microfarads (μF) electrolytic 25 V
VC1	100 picofarads (pF) trimmer

Semiconductors

D1	1N4148
TR1	2SC2078 (see sources list)

Inductors

T1	38 turns 26 SWG enamelled copper on T–50–2 toroid, with two link windings of four turns
L1	21 turns 22 SWG enamelled copper on T–50–2 toroid

Additional items

- Ferrite bead
- Crystal (e.g. 3.579 MHz) and holder
- Metal box
- Socket for Morse key.
  This must be totally isolated from the metal of the box, as *both* connections can be at +12 V.
- Sockets for 12 V supply, aerial and receiver
- Switch – DPDT
- Heat sink for TR1
- RG174 miniature coaxial cable for signal leads (see Figure 2)

Component sources

Special components

2SC2078	Cricklewood Electronics Ltd, 40 Cricklewood Broadway, London, NW2 3ET.

37 A solar-powered MW radio

Introduction

What could be more ecologically friendly than a radio powered by the sun's energy? This design is quite standard, and if you have built any of the other medium-wave radios in this series, then this one should present few problems.

The solar panel

The solar panel is to the solar cell as the battery is to the cell; in other words a solar panel is several solar cells connected in series. The solar panel quoted for this radio will generate about 9 V at a current of around 30 mA on a sunny day. The circuit will operate on a supply of around 2 V, so bright sunshine is *not* necessary for satisfactory operation. The volume will be less, of course.

The circuit

The radio uses the ZN415E integrated circuit (IC), connected as shown in **Figure 1**, the complete circuit diagram. The signal is tuned in by the combination of L1 and VC1. L1 is made by winding about 35 turns of 24 SWG enamelled copper wire on a ferrite rod. A standard ferrite rod of 10 cm length and 1 cm diameter is used.

Signals selected by the tuned circuit are passed to IC1, which amplifies the signals and removes the audio component, which is then amplified further by IC2 for driving a small loudspeaker. The removal of the audio component is the process we call *detection*. In addition to this, IC1 provides *automatic gain control* (AGC), which helps to keep the audio signal constant, even when the incoming RF signal may vary due to fading.

The prototype board

Veroboard (also known as matrix board or stripboard) is ideal for the construction of the radio. The layout is shown in **Figure 2**. The board size is 11 strips by 30 holes (**please note that there is no row 'I', so take care with your counting!**). Using a 3 mm (1/8 inch) twist drill rotated between


R1
3k3
C2
220µ
D1
1N4148
D2
1N4148
C7
1000µ
nc
LS1
32 to 64R
Solar panel
L1
VC1
Tune
IC1
ZN415E
IC2
TDA7052
C6
10µ
C5
10n
R2
100R
VR1
1k0
C3
100n
C4
100n
C1
10n
nc
nc – no connection
Dot
Notch
There will either be a notch or a dot in the plastic body – this tells you which way round to mount the IC
IC1 and IC2
Diodes D1 and D2
© RSGB

Figure 1 The radio uses just two integrated circuits (chips) and operates at any voltage from 2 to 9 V


1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
A
B
C
D
E
F
G
H
J
K
L
R1
C2
C7
D1
C4
C3
IC1
IC2
C6
C5
R2
D2
C1
Solar cell + terminal
Loudspeaker
32 to 64R
Solar cell – terminal
VR1 Volume control
Ferrite rod
L1 approx 35-turns
S
S
S indicates Sellotape strip
VC1
Tuning capacitor
L1, VC1 and VR1 are not to scale
⊗ Copper strips are cut here
●——● indicates insulated wire links on the copper strip side
Track J is not used
IC1 and IC2 are mounted in IC sockets
© RSGB

Figure 2 Follow the layout carefully, making sure that all connections are neatly soldered

your thumb and forefinger, break the strips at the points marked with a cross inside a circle. Hold the board up to the light to ensure that the tracks *have* been broken and that there is no copper swarf shorting tracks together.

Firstly, solder in the 8-pin DIL sockets for the ICs, making sure that the notches in the sockets are facing upwards, as shown on the diagram. Then, solder in the wire links, resistors, capacitors and diodes, making sure that the electrolytic capacitors (C2, C6 and C7) and the diodes (D1 and D2) are connected the correct way round. Use different colours of wire for the connections to the volume control, VR1, to avoid incorrect connections. Note the wiring of the tuning capacitor (VC1) shown in Figure 2; a two-section type is used, and both sections are wired in parallel to give twice the capacitance of a single section.

There is no on/off switch – just turn the volume down when you are finished using the set! The solar panel can be mounted parallel to the top of the case, or angled to receive the maximum energy from the sun, as shown in the photograph. You could have a battery available as a standby source to use the radio after dark; any battery of between 6 V and 9 V will do. Wire it with a simple changeover switch, so you can switch between solar and battery power. Ask a friend for help with this if you are not sure how to do it.

You may need to adjust the number of turns on L1 to get the best results, but it should be possible to receive at least five stations at good volume with your sun-powered radio!



Parts list

		Maplin code
Resistors: 0.25 watts, 5% tolerance		
R1	3.3 kilohms (kΩ)	M3K3
R2	100 ohms (Ω)	M100R
VR1	1 kilohm (kΩ) log	FW21X
Capacitors		
C1, C5	10 nanofarads (nF) ceramic	BX00A
C2	220 microfarads (μF) electrolytic (10 V)	FB60Q
C3, C4	100 nanofarads ceramic	YR75S
C6	10 microfarads (μF) electrolytic (10 V)	FB22Y
C7	1000 microfarads (μF) electrolytic (10 V)	FB81C
VC1	140–300 picofarads (pF)	FT78K
Semiconductors		
IC1	ZN415E (or ZN416E)	UR70M
IC2	TDA7052	UK79L
D1, D2	1N4148	QL80B
Solar panel	9 V at 50 mA	RK23A
Additional items		
LS1	32–64 ohm miniature loudspeaker	YT28F
	Ferrite rod	YG20W
	24 SWG enamelled copper wire	BL28F
	Plastic box, approx. 220 × 140 × 70 mm	YN39N
	Veroboard, cut to size	JP47B
	8-pin DIL sockets, 2 required	BL17T
	Knobs, 2 required	FD67X
	Material for speaker grille	
	Connecting wire	

38 A receiver for the 7 MHz amateur band

Introduction

Listening on the 40 metre band (from 7.0 to 7.1 MHz) can be very rewarding – it is a popular haunt for HF Special Event stations, and at night there are signals to be heard from all over Europe. This receiver is designed purely for the 40 m band, and is ideal for those who have built the simpler receivers and are looking for something a little more challenging. The more experienced constructor may prefer to build this on prototype board.

The circuit and its construction

Figure 1 shows the circuit diagram. The receiver will work well with headphones or loudspeaker. Walkman-type headphones and speakers are ideal for use here.



+5V
Out
IC3
In
Com
+9V
SW1
+9V
(Battery+)
C2 47μ 16V
C6 100n
+5V stab
C15 1000μ 16V
L1
C1 470p
VR1 4k7 lin
IC1
C5 100p
L2
IC2
R2 1k5
R3 1k5
R4 100k
IC4a
R6 12k
R7 12k
C13 47n
IC4b
C16 1μ0 16V
R5 220R
C14 10n
R8 10k
IC5
LS
C12 470μ 16V
0V
(Battery −)
IC1 ... NE602
IC2 ... NE602
IC3 ... 78L05
IC4 ... TL072
IC5 ... TDA7052
C3 47p
C4 100p
X1
X1 — Crystal = 4·608MHz
L3 10μ
C10 1n0
C8 2n2
C11 10n
+5V stab
VR2 4k7 lin
VR3 47k lin
R1 100k
C7 100n
C9 1n0
D1 ½ KV1236
INTEGRATED CIRCUITS
IC1, 2, 4 and 5
8 7 6 5
1 2 3 4
Top view of pins
© RSGB
COILS
L1 and L2
Base view
VARICAP DIODE
Cut here
36Z 112
36Z 112
0V
R1
Lettering side
IC3
78L05
+5V Out
0V Com
+9V In
Base view of pins
EXTERNAL DC CONNECTOR
PP3 9V
To SW1
To PCB
Rear view

Figure 1 The receiver gives good performance on the 7 MHz amateur band as well as being simple to construct and align

Signals arriving at the aerial are coupled into IC1 via gain control VR1, which also functions as the on/off switch. Tuning is provided by varying the voltage on the *varactor diode* (or varicap), D1. VR3 is the main tuning control, and VR2 is the *bandspread* (fine tuning) control. The varactor diode is supplied as a dual device, which must be cut down the middle *carefully* with a sharp knife; with the lettering upwards, the ground lead (0 V) is on the left-hand side, as Figure 1 illustrates.

Solder in the IC sockets first, followed by the coils. After this come the links, resistors, capacitors and varactor diode. Ensure that IC3, the voltage regulator, is wired correctly, and check the polarity of the electrolytics. The crystal, X1, is very fragile, so take extra care with it. The wiring of the three controls is shown in **Figure 2**.

Before putting the ICs in their sockets, connect up the battery and check the following voltages with the negative voltmeter lead connected to the negative terminal of the battery:

Pin 8	IC1	5 V
Pin 8	IC2	5 V
Pin 8	IC4	9 V
Pin 1	IC5	9 V

When all these have been found to be correct, switch off and put the ICs carefully into their sockets. Use wire of different-coloured insulation to wire up the front-panel controls.

The case can be a small plastic box of size 22 cm by 15 cm by 8 cm, with three 10.5 mm holes drilled in the front and two 8 mm holes in the side for the aerial and earth connections. On one side are a 6 mm hole for the speaker socket and an 11 mm hole for the optional external power supply.



Figure 2 Rear view of the variable resistors. Check the connections carefully to make sure the wires are fitted correctly

Testing and tuning

The aerial for the receiver should be between 30 and 70 feet of wire, mounted as high as you can make it, away from trees and buildings if possible. Connect the battery and switch on. Adjust L1 and L2 for the best results. Tune slowly with VR3; you should find CW stations at the lower end of the band (anticlockwise) and SSB stations at the upper end (clockwise). You may find that it is easiest to make these adjustments *before* mounting the board in the case with double-sided sticky tape or pads. If you are planning to use an external DC supply, make sure it is a safety approved stabilised 9 V type, and **disconnect the battery before you use such a supply!**

If you suspect that the tuning doesn't quite cover the lower CW end of the band, try increasing C9 to 1200 pF. If it is the upper SSB end which is missing, decrease C9 to 820 pF.

It is always advisable to use an aerial tuning unit (ATU) between your aerial and the receiver. A suitable design of ATU is included as a project in this book.

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1, R4	100 kilohms (kΩ)
R2, R3	1.5 kilohms (kΩ)
R5	220 ohms (Ω)
R6, R7	12 kilohms (kΩ)
R8	10 kilohms (kΩ)
VR1	4.7 kilohms (kΩ) linear, with SPST switch
VR2	4.7 kilohms (kΩ) linear
VR3	47 kilohms (kΩ) linear

Capacitors: all rated 16 V or more

C1	470 picofarads (pF) polystyrene 5%
C2	47 microfarads (μF) electrolytic
C3	47 picofarads (pF) polystyrene 5%
C4, C5	100 picofarads (pF) polystyrene 5%
C6, C7	100 nanofarads (nF) ceramic
C8	2.2 nanofarads (nF) polystyrene 5%
C9, C10	1 nanofarad (nF) polystyrene 5%
C11, C14	10 nanofarads (nF) ceramic
C12	470 microfarads (μF) electrolytic
C13	47 nanofarads (nF) ceramic
C15	1000 microfarads (μF) electrolytic
C16	1 microfarad (μF) electrolytic

Inductors	
L1	Toko KANK3335R
L2	Toko KANK3333R
L3	10 μH 5%, e.g. Toko 283AS–100
Semiconductors	
IC1, IC2	NE602 or NE602A
IC3	78L05 5 V, 100 mA
IC4	TL072
IC5	TDA7052
Additional items	
D1	Toko KV1236 cut into two sections (one half used)
X1	4.608 MHz (available from Cirkit)
	3 × silver knobs, one with pointer
	Plastic case approx. 22 × 15 × 8 cm
	Speaker 8–32 Ω, or headphones
	4 × 8-pin DIL sockets for IC1, IC2, IC4, IC5
	2 × 4 mm sockets (red and black) for aerial and earth
	3.5 mm chassis-mounting jack socket for speaker
	DC power socket for external supply (if required)
	Prototype board

Kits

A complete kit is available from JAB Electronic Components.



39 Diodes for protection

Introduction

Many semiconductor devices can be destroyed in an instant if their supply is reversed. With the use of batteries as power sources, it is quite common for the battery to be connected ‘the wrong way round’, and the scope for damaging equipment is significant and very real. Diodes can protect equipment in several ways, and you may do worse than to consider one of these approaches to protect your next expensive project.

Choose wisely!

All the diode circuits given here are so simple as to invite calamity. The circuits are not foolproof but, with a little care, will work first time. Remember that a semiconductor diode has a forward voltage drop of between 0.5 V and 0.7 V, depending on its type and the current flowing. This will be mentioned later.

The first thing you need to do is to insert a good multimeter *in series* with the circuit you want to protect; set the range to Amps DC, and switch on. Check that the circuit works properly. Then, decrease the current range on the meter until a good reading is indicated. Make a note of this current, as it is the normal running current of your circuit.

To choose a diode, you must consult the catalogues or data sheets and find one where the quoted *maximum forward current* exceeds the current you have measured; preferably it should be at least twice your measured current. Secondly, the diode will have a *peak inverse voltage* (PIV); this is the maximum voltage it can withstand when the cathode is made positive with respect to the anode, i.e when it is *reverse-biased* and not conducting. This voltage must be greater than your battery voltage, again by a factor of about 2. Except in the case of the bridge rectifier (see later), these criteria will enable the selection of a suitable diode to be made easily.

The series diode

The simplest and most obvious way to protect equipment is to insert a diode in the positive supply lead, as shown in **Figure 1**, with the diode passing current *only* when the supply is of the correct polarity. Because of the 0.6 V that exists across the diode, your equipment will normally operate on a



Figure 1 Series diode protection

slightly lower voltage. If you imagine reversing the supply to this circuit, you will see that the negative terminal of the battery is connected to the anode of the diode; the diode becomes reverse-biased and will not conduct any current, thus protecting the load. Your equipment will not operate when the battery connections are reversed.

The parallel diode

The circuit of **Figure 2** overcomes this voltage drop. It places the diode in parallel with the load (your equipment) but in a normally reverse-biased condition so that it draws no current when the battery is correctly connected. Reverse the battery connections, however, and a very large current will flow through the diode, thus blowing the fuse! For this technique to work successfully, the current drawn by the diode when the battery connections are reversed *must* be much greater than the maximum current drawn by the equipment, in order to blow the fuse. This is usually not a problem, however.



Figure 2 Parallel diode and fuse

The diode bridge

For sheer elegance, the circuit of **Figure 3** takes the biscuit! It uses four diodes connected in the form known as a *bridge rectifier*. Such rectifiers exist, and do not have to be made up from four discrete diodes.



Figure 3 The diode bridge

Follow the current round the circuit from the supply, assuming initially that the top wire is positive and the bottom wire negative. It flows from the positive supply

(a) through D2
(b) through the load (top to bottom)
(c) through D4

and back to the negative of the supply.

Now assume that the bottom supply lead is positive and the top lead negative. The current flows from the positive supply

(a) through D3
(b) through the load (top to bottom)
(c) through D1

and back to the negative of the supply.

So, whichever way round the battery is connected, the current will *always* flow the same way through your equipment!

The circuit does have a drawback, however. Whichever way round the battery is connected, there are always **two** diodes conducting the current at any time. In the first case it is D2 and D4; in the second case, D1 and D3. This means that there is a total voltage drop of about 1.2 V. If your equipment can tolerate that reduction in voltage, then you will not have a problem.

Decoupling

Whenever the supply rail to a piece of equipment, or even to an individual stage of a circuit, is broken for the insertion of a device that will drop voltage, strange things can happen. This is because the supply for any circuit is assumed to have a low resistance to DC and a low *impedance* to AC. (Impedance is the AC equivalent of DC resistance.) These two are not the same, and the insertion of a diode or diodes is certain to make a big difference to them both. To overcome any irregularities in the operation of the circuit you are protecting in any of the ways described previously, the protected supply needs to be *decoupled* with a capacitor.

If the circuit handles audio frequencies only, placing an electrolytic capacitor directly across the load in all three circuits should solve the problem. The parallel circuit of Figure 2 is less at risk than the other circuits. The size of the capacitor will be determined by the current taken by the circuit, and may need to be chosen within the range 100 μF to 10 000 μF, with a working voltage greater than the supply voltage.

If the circuit is mainly handling RF currents, placing a capacitor of 0.01μF across the load should prevent any problems. A second capacitor, also across the load, of between 10 μF and 100 μF may be needed. Again, the parallel circuit of Figure 2 is less at risk than the other two.

Don't be afraid to experiment, but confine your experimenting (at first) to small equipment and low currents, until you get a 'feel' for the technique.

40 An RF signal probe

Introduction

A radio-frequency (RF) diode probe is a simple device which, when used with a conventional multimeter, enables the measurement of RF voltages in a circuit. When constructed, this will be one of the most useful pieces of test equipment for the experimenter who revels in the construction of transmitters and receivers.

The circuit

Figure 1 shows the simple circuit diagram. It is *almost* the same as a common diode rectifier circuit, but with a simple change to make it more sensitive. The circuit is known as a *voltage-doubler*, and is often found in high-voltage supplies, with beefier capacitors and diodes, of course! Because we are dealing with high frequencies and smaller voltages, the diodes and capacitors can be physically very small. The diode circuit of D1 and D2 *rectifies* or *detects* the RF from the probe, and any remaining AC is removed (short-circuited to ground) by C2. This produces, at the output, a constant voltage proportional to the peak-to-peak RF voltage present at the input; the output voltage is fed to an ordinary multimeter (on a voltage range).


C1
10n
Probe
(Stiff wire)
D2
+
To multimeter
Screen
D1
C2
10n
Ground
lead
-
D1 and D2 are germanium diodes
C1 and C2 are 10nF ceramic capacitors
(Crocodile clip)
© RSGB

Figure 1 The diode probe can be made from four electronic components

Construction

Although the circuit layout is not critical, a description of the prototype is given here for your information. **Figure 2** has the details. The components are soldered to square pieces of copper-clad printed-circuit board (PCB) glued to a larger piece of PCB. The larger piece serves as a ground connection. Use a stiff copper wire as the probe, and an insulated flexible wire with a crocodile clip to connect the probe to the ground of the circuit under test.

Cut a piece of plain PCB, 30 mm by 45 mm and another of 15 mm by 45 mm. Cut the smaller piece into three measuring about 15 mm square. Stick the three small pieces to the larger piece, ensuring that there are small gaps between each, as Figure 2 shows. Solder the components in place. The connection to the multimeter should be thin coaxial cable or screened microphone cable. If you use unscreened cable, there may be RF pickup here which can lead to false readings.

Simple to use

Using the probe is simple. Connect it to the multimeter and set the meter to around 10 V DC – you may need to reduce this, depending upon the magnitude of the RF voltage you are trying to measure. Hold the probe by


To wire
probe
To
multimeter
D2
C1
D1
C2
Screen
Ground
lead
© RSGB

Figure 2 The components are mounted on a copper-clad PCB

its base, being careful *not* to touch any of the components. Connect the croc clip to a ground point on the circuit and touch the probe on the circuit point to be tested. If an RF signal is present, there should be a reading on the multimeter. That’s all there is to it!

Parts list

Capacitors	
C1, C2	10 nanofarads (nF), or 0.01 microfarad (μF) ceramic
Semiconductors	
D1, D2	Any *germanium* signal diode, e.g. OA91 or AA119

Additional items
- Stiff copper wire
- Insulated flexible wire
- Copper-clad PCB
- Crocodile clip
- Coaxial or screened cable

Source

All components are available from Maplin.

41 An RF changeover circuit

Introduction

The simplest entry route to operating an HF station is to buy or build a receiver, and to add a simple CW (Morse) transmitter. In theory, this sounds so simple, yet in practice there is one significant hurdle to be overcome. How can they both share the same aerial? A manually operated changeover switch is the obvious solution, but it takes time to perform the switching operation, by which time someone else has squeezed in before you and contacted the DX station! This small circuit accomplishes the changeover automatically, as soon as the transmitter is keyed.

How it's done

The circuit is shown in **Figure 1**, and uses the signal from the transmitter to operate a relay. A relay is a switch which is operated electrically in the following way. A coil of wire with an iron core is used as an electromagnet. When current flows through the coil, it produces a magnetic field which, in turn, is used to pull a set of switch contacts. These contacts will be used to switch the aerial from transmitter to receiver and vice versa. The relay used here has a double-pole changeover (or DPDT, or DPCO) switch. If you are confused by the different types of switch, look at the basic descriptions elsewhere in this book. The *pole* of a switch is the part that doesn't move; in Figure 1, one pole is connected to L1 and the other to the aerial output. In a circuit diagram, the switch contacts are always shown in their *normal* state, i.e. when *no* current flows in the relay coil. The changeover switch is normally in the receive position, so we say the receive switch is *normally closed*, and the transmit switch is *normally open*. We choose to have the circuit in the receive position normally, because everyone spends a lot more time receiving than transmitting. The relay is energised only when you are transmitting.

There are three RF sockets – one for the transmitter, one for the aerial, and one for the receiver. When the transmitter is not in use, there is a direct connection (via the Rx normally closed contacts of the relay) between the aerial and the receiver. The transmitter (which is not keyed at this time) is connected to a 50 ohm dummy load, R1.

When the transmitter is activated by pressing the Morse key, an RF signal appears at the transmitter socket. The wire carrying the signal to the relay



Figure 1 RF activated relay

Tx contacts passes through a toroid (a ferrite coil former, looking like a black Polo mint), which has a five-turn coil wrapped around it. This five-turn coil picks up the signal, which is then detected by D1 and D2, and converted to a steady voltage. C1 removes any remaining RF and C2 provides *hang*. Without it, the circuit would detect the gaps between every dot and dash being sent, and switch the aerial over very rapidly and very frequently! This is *not* what we want. We need the relay to remain in the transmit condition at normal Morse keying speeds, and then return to receive when the sending is complete. The combination of C2 and R3 achieves this.

The voltage appearing across C2 is fed to a VMOS field-effect transistor (FET), TR1, which acts as an electronic switch. When a voltage appears across C2, the FET switches on and passes a current through the relay coil, changing the contacts from receive to transmit. The diode, D3, across the relay winding protects the FET from being damaged by the large reverse-voltage spike which occurs across the coil when the FET switches off.

Construction

This is very simple – a circuit board is not required. The prototype was built into an old 50 g tobacco tin. All ground leads are soldered directly to the tin, thus supporting the components automatically. Phono sockets were used for the aerial, receiver and transmitter; you could use whatever connectors matched the rest of your station. The 12 V supply is fed through the tin using a 1000 pF feed-through capacitor, C3.

The 'dummy load', R1, must be able to withstand the RF output power of the transmitter. For novice use, 4 watts is adequate. Two suggestions for making up R2 from standard resistors are shown in **Figure 2**. Six 330 ohm, 1 watt resistors in parallel have a combined resistance of 330/6 = 55 Ω at 6 W. Two 100 ohm, 2 watt resistors in parallel have a combined resistance of 100/2 = 50 Ω at 4 W.



Figure 2 Component details

Make sure all the contacts to the relay are correct; also ensure that TR1, C2, D1, D2 and D3 are correctly wired.

Winding the toroid, L1, is very simple. It is made from PVC-insulated hook-up wire. Each time the wire passes through the centre of the toroid counts as one turn. The wire from the transmit socket to the relay simply passes through the centre! Use thin 50 Ω coax for the leads to the three sockets.

What happens to the receiver?

On transmit, the receiver is not connected to the aerial, but is only the separation of the switch contacts (about 0.5 mm!) away from the transmit lead. The receiver *will* pick up the transmitted signal, and there is a possibility that this signal will be enough to damage the receiver's sensitive input circuits. This can be prevented with the simple addition shown in **Figure 3**. Two diodes are connected back to back across the receiver socket. These act as a *limiter*, reducing the amount of signal that can enter the receiver. Solder these directly between the receiver socket and the tin.



Figure 3 Receiver input protection

Warning

The wiring **must** be thoroughly checked. If the relay switch connections are wrong, there is a **great probability** that the full RF power will be applied to your receiver! You can check these connections as follows. With the 12 V supply connected, check that the relay energises (clicking sound heard) when the FET drain (d) is shorted to earth. Check the aerial and receiver connections with an ohmmeter or continuity tester. Disconnect the 12 V supply, and check that there is continuity between the centre pins of the aerial and receiver sockets. Reconnect the 12 V supply, short the FET drain to earth again (this will not damage the FET) and check that there is continuity between the centre pins of the aerial and transmitter sockets. If these tests show correct operation, disconnect the drain shorting wire (*most* important!) and your aerial auto-changeover is ready for use! Avoid using the device without the lid fitted.

Parts list

Resistors: 0.25 watt, 5% tolerance, unless otherwise stated

R1	50 ohms (Ω) – see text and Figure 2
R2	1 kilohm (kΩ)
R3	10 kilohms (kΩ)
Capacitors	
C1	100 nanofarads (nF), 0.1 microfarad (μF)
C2	47 microfarads (μF) 15 V electrolytic
C3	1000 picofarads (pF) feedthrough
Semiconductors	
D1, D2, D4, D5	1N914
D3	1N4001
TR1	VN10KM
Additional items	
L1	T37–43 toroid
	Relay 12 V DPDT (DPCO) relay
	Three sockets to suit (phono, SO239, etc.)
	Thin coax cable and hook-up wire

42 A low-light indicator

Introduction

This is a simple one-evening project that can be built for the pure fun of it, or to use as the basis of a more complex project to switch your shack lights on when it gets dark! In its prototype form, it simply flashes an LED when the ambient light level drops to a preset point.

Operation

The heart of the circuit shown in **Figure 1** is a *photo-conductive cell*, also called a *light-dependent resistor* (LDR), a device whose resistance changes according to the amount of light falling on it. In bright light, the resistance is low (about 1 kΩ), whereas in the dark, its resistance is very high (up to 10 MΩ). The cell is made from a semiconducting material known as cadmium sulphide (CdS), and is enclosed in a small plastic container. The semiconductor is laid on a flat insulating surface in the form of a small flat ribbon. The ribbon construction gives a good area of surface for a given


VR1
22k
pre-set
R1
220R
+
LED1
-
+
9V
PP3
battery
-Ve
R2
1k
B
C
E
TR1
2N3053
LDR
ORP12

Figure 1 Circuit diagram

©RSGB DY107

length of ribbon, and the length of the ribbon is maximised by laying it out in a zig-zag pattern, as can be seen diagrammatically in **Figure 2**. In the dark, CdS is an insulator; when light falls on it, electrons are released inside the CdS, making it conduct. The more light there is, the more electrons there are, and the resistance falls.

In this circuit, the LDR is connected across the 9 V supply in series with a variable resistor, VR1. In this arrangement, the voltage that exists across the LDR will be determined by the light level. As the light intensity increases, the resistance of the LDR falls, dropping a smaller voltage across it. The


LED
Flat
c
b
e
TR1 base
- +
- to TR1 collector
+ to R1
Battery +
VR1
R1
+
LED
-
LDR
R2
c
TR1
b
e
Battery -

Figure 2 Component layout on tagstrip

©RSGB DY108

reverse happens when the light intensity falls – the voltage across the LDR increases. This voltage is used to drive an npn transistor, TR1, connected as an electronic switch. As the voltage on the base (B) rises, it will reach a point where TR1 will suddenly start to pass current, just as an ordinary switch does when pressed. The current flowing through TR1 also flows through a flashing light-emitting diode (LED), D1 and its series resistor, R1. D1 can be a steadily glowing type, if preferred. If you want to make the circuit switch the LED on at a different ambient light level, adjust VR1.

Construction

The prototype was made on an eight-tag tagboard (Figure 2). The resistors R1 and R2 can be laid on the tagboard for soldering, the rest of the components lying above or to the side of the board. Check the circuit after you have soldered everything on, then connect the battery. The LED should flash if you put your hand over the LDR, and VR1 can be adjusted to vary the point at which the LED lights. The project can be housed in a small plastic box with holes provided for the LDR and LED and an on/off switch if you want one.

Parts list

Resistors: all 0.25 ohm, 5% tolerance

R1	220 ohms (Ω)
R2	1 kilohm (kΩ)
VR1	22 kilohms (kΩ) linear pre-set

Semiconductors

LDR	ORP12
TR1	2N3053 npn
LED1	Flashing LED

Additional items

Plastic box
Tagboard with 8 tags
PP3 battery connector

43 A J-pole aerial for 50 MHz

Introduction

For FM communication (i.e. voice and data) on the VHF bands, a vertical aerial is used to give all-round (non-directional) coverage. This is a half-wave aerial which can be fed at the end, thus removing the principal problem with the conventional vertical centre-fed half-wave dipole, which is that the feeder should leave the dipole at right angles. This is no problem when the dipole is horizontal, but can be difficult for the vertical dipole.

Basic facts

A feeder must be connected to an aerial at a point where the *impedance* (AC 'resistance') of the aerial closely matches that of the feeder. The difference between the two impedances gives rise to the voltage standing-wave ratio (VSWR), which is unity only when the two impedances are the same. With 50 Ω feeders, the feed point of a half-wave aerial is at the centre, where the aerial impedance is around the same value. At the end of a half-wave aerial, the impedance is high, so it is *not* a suitable point to connect a 50 Ω feeder.

Connection at this point can be effected using an RF transformer. RF transformers act in the same way as ordinary transformers, except that they are much smaller, and usually comprise wires of particular lengths adjacent to each other. **Figure 1** is a good starting point. It shows the aerial in its diagrammatic form. Notice that the aerial is in the form of an elongated letter 'J'; this shape gives rise to its nickname – the *J-pole*. The quarter-wave RF transformer is the lower 'U' section below the half-wave element. At the bottom of the U section, the impedance is zero (this may become clearer later) and at the top of the U section it is high, thus matching the aerial impedance. The coaxial feeder cable is connected part-way up the U section, where the impedance is around 50 Ω.

The practicalities

Figure 2 shows the aerial as constructed. As it is about 4.5 metres high, it may be too high for the average house loft, but is ideal for mounting outside, supported by a non-metallic pole or hung from a tree branch. The upper half-wave section is made from 1.5 mm insulated copper wire, as used in domestic mains wiring. The quarter-wave transformer below the half-wave section is made from 300 Ω balanced line ('ribbon cable'). The



Figure 1 Overall dimensions of the 6 metre J-antenna

wires at the bottom of the transformer section are stripped of their insulation, twisted and soldered. At the upper end, only one wire of the balanced line is soldered to the bottom of the half-wave section. The other wire of the pair is not connected and is left insulated.

At the feed point of the transformer, the insulation needs to be carefully stripped from the balanced line. You will need a standing-wave meter (VSWR meter) in the coaxial line between your transmitter and the aerial, and you will need to adjust the position of the feed point. 45 cm from the bottom was the best point on the prototype, but this position is dependent upon the immediate surroundings of the aerial, and *must* be done when the aerial is in its final operating position. **Warning: *Never* make adjustments to the feed point when the transmitter is on. Make a VSWR measurement, switch off, move the feed point, switch on again, make another measurement, and so on.** You will need to aim for the lowest VSWR you can – certainly better than 2:1. Having found the best position, wrap all the exposed wires with self-amalgamating tape, to seal them against the ingress of moisture.


©RSGB DY111
Nylon cord to support antenna
1·5mm diameter insulated wire antenna element
Soldered connection
Coaxial cable connected to ribbon cable (see text)
300 ohm ribbon cable matching section
Coaxial cable to transceiver
Coaxial connector
End of ribbon cable insulation removed and wires joined and soldered

Figure 2 Construction details

How it performs

Figure 3 shows a computer prediction of how the J-pole radiates. It is called a *polar diagram*, and shows the distribution of your transmitted power when viewed 'from the end of your garden'. Most of your signal is sent at a fairly small angle to the horizontal; very little signal goes upwards, which is a good thing, of course. This also shows why the J-pole (or any other vertical aerial) should not be called 'omnidirectional', which means it radiates in all directions. It is omnidirectional *only* in the horizontal plane.



Figure 3 This polar diagram computed for the J-pole

Safety

Where you mount your aerial is a matter of personal preference and the restrictions of height and space, but the following safety rules *must* be applied.

1. Never fix an aerial where it may come into contact with power lines or telephone lines.
2. When climbing a ladder to put up an aerial outside, make sure the ladder is safe and that it is secured.
3. Don't do this alone. Preferably have someone with you. If this is not possible, make sure someone knows where you are.

Parts list

3.00 metres	1.5 mm insulated copper wire
1.50 metres	300 ohm balanced line
As required	50 ohm coaxial cable
As required	Self-amalgamating tape

44 Measuring light intensity – the photometer

Introduction

Before the days of automatic 'point-and-shoot' cameras, a photographer would use a light meter or *photometer* to measure the light level, then manually convert this reading into shutter speed and lens aperture settings to ensure a correctly exposed negative. Modern cameras have quite sophisticated photometers, which control the shutter speed and iris settings automatically.

A short explanation

A simple photometer circuit is shown in **Figure 1**, and is based on a device called a *light-dependent resistor*, or LDR. As its name tells us, its resistance depends upon the amount of light falling on it. In bright light, the resistance is relatively low (about 1 kΩ), whereas in the dark, its resistance is very high (up to 10 MΩ). The cell is made from a semiconducting substance known as cadmium sulphide (CdS), and is enclosed in a small plastic container. The semiconductor is laid on a flat insulating surface in the form of a small flat ribbon. The ribbon construction gives a good area of surface for a given length of ribbon, and the length of the ribbon is maximised by laying it out in a zig-zag pattern. In the dark, CdS is an insulator; when light falls on it, electrons are released inside the CdS, making it conduct. The more light there is, the more electrons there are, and the resistance falls.



Figure 1 Circuit diagram of photometer

The photometer circuit

The circuit is simply a series connection of four things – the battery, the LDR, a variable resistor and a meter. A switch is also provided. The combination of the LDR resistance and that of VR1 determines the current flowing, which is indicated on the meter. Altering the resistance of VR1 sets the *sensitivity* of the photometer – you may want full-scale deflection of the meter needle for a bright light, or for a dim light.

It is simple to make, and a plug-in type matrix board is ideal to test the circuit, so that you can decide if you want to make a permanent version. Connect all the components in series; the only change you may want to make is the connection to VR1. If you find that the sensitivity control seems to work 'backwards', simply unsolder the wire from the end tag of VR1 and solder it to the opposite end tag. Problem solved!

In use

As soon as you connect up the battery, you will probably have a meter reading because of the daylight falling on the LDR. Shading it with your hand should reduce the reading. If the meter needle is hard over against the end-stop, turn VR1 until it indicates about half-scale. The LDR is very sensitive, and will read zero only in a dark room. If you put on a torch to see what the meter reading is, the LDR will detect the torch light, and will give a reading!

Here is a simple project where you can use the photometer in an experiment which has an analogy in radio. Draw a circle on a large (A3 or bigger) sheet of paper and divide it up into 30-degree sectors, as shown in **Figure 2**. Draw a series of smaller circles which divide the maximum radius into five. Look at the figure if you're not sure about this. Bring the LDR away from the circuit by using two long, flexible wires. The experiment must be performed in a darkened room (preferably in total darkness). Prepare a table with two columns, the left-hand one headed 'Angle (degrees)' and the right-hand one 'Meter reading'. Fill in the left-hand column 0, 30, 60 . . . and so on up to 360°.

Place the torch in the position shown, with its lens at the centre of the circle and pointing along the 0° line; switch it on. Place the LDR facing the torch and adjust VR1 until you have full-scale deflection of the meter needle. Suppose the meter indicates 10 units at this point. Enter this into your table in the 0° row. Keeping the torch the same distance from the circle centre, and pointing at it, move the LDR round all 30° positions and record the meter readings. Switch off the torch and take the sheet of paper and your tabulated results into daylight!

Lay the large sheet of paper on a table with your results beside it; then, at each 30° interval, plot the point along the radius corresponding to the meter



Figure 2 Torch light intensity pattern plotted at RSGB HQ

reading. Then, join up all the points and you have what is called a *polar diagram* of light intensity. The use of the word 'polar' implies that the readings have been taken in a circle and plotted that way.

Light waves and radio waves are both examples of *electromagnetic radiation*. The torch is designed to 'beam' its radiation in a particular direction, just like an aerial does. Hence the use of the word 'beam' for a directional aerial. If a similar polar diagram is drawn for a Yagi-type aerial, it will show the same general characteristics as does Figure 2, namely a main direction (or 'lobe') where most of the energy is concentrated, with evidence of *sidelobes*, indicated by 'lumps' on the otherwise smooth main lobe.

Also in this book you will find a project for the construction of a UHF field-strength meter, which you could use to carry out a measurement of the polar diagram of a UHF aerial.

Parts list

Resistor

VR1	50 kilohms (kΩ) linear

Semiconductor

LDR1	ORP12

Additional items
Meter, 50 or 100 μA
Battery clip for single AA cell
AA cell

45 A 70 cm Quad loop aerial

Introduction

This is a description of how to make an aerial for the 70 cm band which has gain compared with the 'rubber duck' or the dipole aerial. It can easily be dismantled and reassembled, making it ideal for contest use.

The principles

Most aerials which comprise several similar *elements* arranged along a *boom* are variations of the design originated by Yagi and Uda, and which takes the name (for historical reasons) of the former, and is know as the Yagi array. Let us suppose we have a Yagi aerial beaming left to right in front of us. The elements get progressively shorter from the left (look at almost any TV aerial to see this). All the elements on a Yagi aerial are classified as follows:

- The *reflector* – the leftmost element as we look at the array. It is the longest. Next to it is:
- The *driven element* – this is the element connected to the feeder, which in turn runs down to the transceiver. It is slightly shorter than the reflector.
- All the elements beyond the driven element are called *parasitic elements*, or *directors*. They are shorter than the driven element and usually get progressively shorter as we progress to the right along the boom. The directors are mainly responsible for the *directivity* (or *beamwidth*) of the array.

The progression from a simple dipole (a driven element in isolation) to a Yagi array is simple, but is nevertheless important. To make an aerial of two elements, a reflector (*not* a director) is added to the driven element. For three or more elements, directors are added to the two-element design. Adding more and more directors soon becomes impractical, the reduction in beamwidth (such as it is) does not warrant the extra expense, weight and wind resistance that is incurred.

Instead of using linear (straight) elements, as in the generic Yagi, this design uses loops. Designs using squares of wire instead of loops are known as *Quad* aerials, and HF designs require large X-shape frames to support the large squares of wire. At 70 cm, however, the use of wire loops is easier, and they are self-supporting.

Construction

This is quite simple. Any type of material (metal, plastic, wood) can be used for the *boom* (the support for the elements) and for the mast. The elements are made from 14 SWG enamelled copper wire. 16 SWG hard-drawn aerial wire, which is not enamelled, has also been used with success. Thinner wire might result in a rather ‘floppy’ aerial! The separate parts of the aerial are held together with *jubilee clips* (hose clips).

The driven element is secured to the boom with a jubilee clip and a three-connector plastic connector block as shown in detail in **Figure 1**, and in the photograph. Cut the wire for the driven element 70 mm longer than the 700 mm indicated in Figure 1. Then, using sandpaper, remove the enamel from one end to a distance of 20 mm, and from the other to a distance of 50 mm. After forming the loop of the driven element, bend both stripped ends through 90°, and insert them into the first to holes of the plastic connector block (Figure 1). Do not tighten the screws yet. Push both ends into the block as far as they will go, then bend the 50 mm end back on itself and pull the ends back through the connector block so that the end you have just bent goes into the third hole in the block. Now tighten the screws in the block and in the jubilee clip.

Each director and the reflector should be made 40 mm longer than the circumferences shown in Figure 1. Strip the enamel, as before, from the last 20 mm at each end. Form the wire into the loop, slip the ends under the jubilee clip (Figure 1) and tighten it. You may find that it helps to solder the stripped ends together before securing the jubilee clip.

The boom is fixed to the mast using jubilee clips and wire, as shown in Figure 1. Solder the feeder cable to the driven element, with the braid soldered to the end of the driven element which is connected to the boom (this applies to metal booms; with plastic or wooden designs, the feeder connections are not critical).


©RSGB DY112
170 mm
180 mm
180 mm
Reflector
Driven element
Director 1
Director 2
Wire dimensions refer to the circumference of the elements
780mm
700mm
640mm
632mm
Jubilee clip
Connector block
Boom
Wire element
Coax
Jubilee clip
Wire element
Boom
Stiff copper or steel wire (one each side of boom)
Jubilee clips
Boom
Mast

Element to boom detail

Element to boom join detail

Boom to mast connector detail

Figure 1 70 cm 4 element quad construction, with detail of how hose clamps are used in the construction

You will need a plug on the shack end of your feeder to suit the transceiver, aerial tuning unit (ATU) or the standing-wave meter (SWM) you are using. Always connect these in the order: transceiver – SWM – ATU – aerial.

Testing

Always test aerials outside and away from buildings (if possible!). This avoids getting misleading results.

Use a rubber duck, or whatever aerial you usually use, and tune around to find a repeater or beacon signal which is consistent. Note the reading on the S-meter. Then, connect your new Quad loop. Rotate it to give the strongest S-meter reading (don't forget it is directional). Verify that the meter reading varies as you rotate it. How does the S-meter reading compare with the original reading? Much depends on the siting of your original aerial; if you are comparing your Quad loop at ground level with a vertical on the chimney, you wouldn't expect your new aerial, even with its gain, to outperform a vertical which is well elevated!

Now a test on transmit is called for. The use of an SWR meter is essential here. Find a clear frequency and check that it *really is clear* before announcing your presence and carrying out the test. A reading of 1:1 is excellent, but any value less than about 1.8:1 would be acceptable. You can measure the directivity of your aerial using the field strength meter, also described in this series.

Materials

4 metres of 14 SWG enamelled copper wire
Material for boom and mast
15 amp connector block
7 Jubilee clips

The enamelled copper wire is available from AA&A Ltd, Sycamore House, Northwood, Wem, Shropshire SY4 5NN. Everything else is available from most hardware stores.



46 A UHF field strength meter

Introduction

It is always interesting, and often useful, to know just *where* the radiation is going from your aerial. How much of your radiated energy is going in the general direction of the station you are in contact with, and how much is being effectively wasted? Some of these questions can be answered with the use of a *field strength meter.* A field strength meter is simply a receiver, stripped down to its bare essentials, such that it responds only to the magnitude of the carrier. The use of a field strength meter assumes that the aerial under test is radiating a continuous carrier. Don't forget to find a clear frequency and identify your transmissions at least every quarter-hour, in order to comply with the terms of your licence.

Description

Two types of field strength meter are shown in **Figure 1**. You will recognise both circuits (Figure 1b particularly) as being types of 'crystal set' with a meter replacing the headphones. Figure 1a is a broad-band HF design (there is no tuning provision) and Figure 1b is tuned in the same way as the crystal set; with a loop of wire as an aerial, it will perform well in the VHF/UHF range.



Figure 1 Construction of the UHF field strength meter

A tuned field strength meter also doubles as an *absorption wavemeter* if it is well calibrated. Such devices are useful for detecting transmitter harmonics also. This design is intended for use in the UHF band, so it will have to be sensitive around 432 MHz.

Construction

The field strength meter comprises a loop of wire, 600 mm long, which acts both as aerial and as the tuning inductance, a diode, a capacitor, a connector block, a meter and a length of twin wire. All the components, with the exception of the meter, are fixed to a pole with a jubilee clip, as shown in **Figure 2**. The meter should have a sensitivity of between 50 μA and 100 μA, or a multimeter can be used. The multimeter is more flexible, as you can select different current ranges, giving you a range of sensitivities.

Using the field strength meter

Connect your meter to the ends of the twin wire from the pole. Place a hand-held transceiver about 2 metres away, and press Transmit. If there is no meter reading switch off the transmitter and check the wiring. If the needle attempts to go negative, simply reverse the wires to the meter. If the reading is too high, either move the transmitter further away, or increase the current range on the multimeter. Try changing the orientation of the transmitter aerial, and note how the signal varies.


Wire loop
(600mm long,
not critical)
100p
capacitor
Connector
block
Hose clip
Diode
OA79 or
OA91
Pole
Wires to
meter
©RSGB DY119

Figure 2 Assembly of the field strength meter

To measure the *polar diagram* (a graph of the signal strength against the angle between the aerial boom and the field strength meter, plotted on polar axes) of a beam aerial, mount the loop as far away from the aerial as you can, preferably at the same height, and rotate the aerial, say 15 degrees at a time, and record the signal strength, until the aerial has been turned through 360 degrees. If you need help plotting the graph, enlist the help of a friend who has done it before, or one who knows about polar graphs! If you have already built the Photometer project, you will have measured and plotted the polar diagram of the light intensity from a torch. Now you will see the great similarity!

Parts list

Capacitor	100 picofarads (pF)
Diode	Germanium, OA79 or OA91
Connector block	10 A, 3-way
Wire	600 mm of 16 SWG enamelled copper
	Length of twin cable for meter connection
Clip	Jubilee (hose) clip

47 Christmas tree LEDs

Introduction

A novelty ideal for the festive season, this circuit causes one LED at a time to light up around a small cardboard Christmas tree.

Warning

This circuit uses members of the integrated circuit family known as CMOS (complementary metal-oxide semiconductor). These use very little current and can be completed destroyed if they come into contact with the magnitudes of static electricity that most of us carry about when we walk on carpets and wear rubber shoes. You will never know if this wanton destruction has happened – all you will discover is that your circuit doesn't work and that you have tested *everything*. To avoid this problem do the following things:

1. **Before you open the little packet in which each IC is supplied, touch something which you *know* to be earthed – the metalwork of any equipment which is mains-earthed, for example. Then open the packet.**
2. **Let the IC fall gently on the bench – don't pick it out with your fingers. Touch your earthed metalwork again. Pick up the IC and insert it gently into its holder.**
3. **Repeat the process with the second IC.**

The circuit is safe from destruction while it is connected to the battery. However, when the battery is removed, the same care should be exercised with its handling, because there are no supply decoupling capacitors across each IC.

Description

Figure 1 shows the layout, and how the wires are connected from the circuit board to the LEDs around the tree. The circuit, shown in **Figure 2**, is quite complicated, so you need to be confident in your logical approach to circuit-building before you attempt this one! It uses two common integrated circuits (ICs). IC1 is simply an oscillator which provides timing pulses for IC2, which 'counts' up to a maximum of 10. The outputs of the counter are indicated by light-emitting diodes (LEDs); red, orange, yellow and green are common colours which you can use.

The circuit is built on a single piece of Veroboard measuring 29 holes by 12 strips. **Be aware that there is no strip labelled 'I', so don't make mistakes in your counting!**

First of all, cut the tracks in the positions shown in Figure 1 using a 3 mm ($\frac{1}{8}$ inch) twist drill rotated between thumb and forefinger. Then, solder in the IC sockets, the notches facing row M. Wire up and solder in the links and then the Veropins for the connections to the LEDs and battery. Having done this, the resistors and the capacitor should be fitted. When wiring the LEDs, each cathode (the lead adjacent to the 'flat' on the LED encapsulation) is connected to R4, and the anodes go to separate pins on IC2.

Testing

Hold up your circuit board to the light and check carefully for solder bridges between adjacent tracks. Then check again that the wiring is correct. Place the ICs in their holders, with the notched ends lining up with those on the holders. Connect the battery, and the LEDs should illuminate in sequence.

If you have no success, you are now wishing you had checked the circuit more carefully! Learn something from your mistake and it will not have


−ve
1
5
10
15
20
25
29
A
B
C
D
E
F
G
H
J
K
L
M
9V
PP3
battery
+ve
R1
R2
R3
R4
C1
IC1
IC2
Component side of board shown
= Pin
= Link
= Cut in copper track

©RSGB DY137

Figure 1 Christmas tree, component layout


C1
470n
Clock
+Ve
R1
680k
R2
10k
R3
10k
14 13 12 11 10 9 8
IC1
1 2 3 4 5 6 7
16 15 14 13 12 11 10 9
IC2
1 2 3 4 5 6 7 8
R4
470
Diodes
on
badge
D6 D2 D1 D3 D7 D4 D5

©RSGB DY138

Figure 2 Christmas tree, circuit diagram

been in vain! The first thing to check is that the LEDs are the correct way round. If that is OK, then check the positions where the tracks are broken (intentionally!). After that, are the wire links in the right places – had you forgotten there is no row ‘I’? Check *all* the wiring, then check *again* for solder bridges, and switch on again. One of these tests should have revealed a fault. If it *still* refuses to work, perhaps one (or both) of your ICs were damaged by static electricity, despite your precautions – or did you choose to ignore them?

Parts list

Resistors: all 0.25 watt, 5% tolerance	
R1	680 kilohms (kΩ)
R2, R3	10 kilohms (kΩ)
R4	470 ohms (Ω)
Capacitor	
C1	0.47 microfarad (μF) min. metallised polyester film
Semiconductors	
IC1	4011
IC2	4017
Additional Items	
D1–D7	5 mm LEDs in choice of colours
	14-pin DIL socket for IC1
	16-pin DIL socket for IC2
	PP3 battery clip and battery
	Veroboard, Veropins
	Insulated wire for links

48 An audio signal injector

Introduction

An audio signal injector is a device used to test audio frequency circuits. It is simply an oscillator running at a frequency in the audio range, so that when its output is fed to the input of an amplifier, it will produce a sound in the loudspeaker if the amplifier is working. The oscillation is so rich in harmonics that the signal can also be heard (sounding rather different) when injected into an RF circuit.

The design

The circuit is shown in **Figure 1**, and is a basic *astable multivibrator*, a free-running oscillator producing a roughly rectangular-wave output. The two transistors, TR1 and TR2, operating as switches, switch on and off alternately at a frequency around 500 Hz. The prototype was constructed on plain matrix board (no copper strips), as illustrated in **Figure 2**.

Both transistors are type BC108, which are only a few pence each new, and can be found at almost any rally. You can add an on/off switch, or simply disconnect the battery when you are finished using it. To make the unit in one piece, the battery can be taped to the board, as the diagram shows.

The probe itself is made from a short piece of stiff insulated wire, soldered to a tag on the board; an earth lead is also soldered to the board, and terminated in a crocodile clip to attach to the ground lead of the equipment under test.



Figure 1 Circuit diagram of the signal injector


©RSGB DY131
+Ve red
10cm x 3cm perforated board
Solder tag and 6BA nut and bolt
Probe
Insulation
Tape
PP3 battery
R1
R2
R3
R4
C1
C2
C3
TR1
TR2
Crocodile clip
−Ve black
------ Wires under board

Figure 2 Component layout of the signal injector

Using it

After checking the wiring of the circuit, connect the battery. Find a transistor radio that is known to work. Carefully remove the case, switch on and apply the probe to the centre tag of the volume control. A *very* loud buzz should be heard from the speaker, indicating that the audio circuits of the radio are working. Using the injector to fault-find equipment you have made yourself is rather more instructive and rewarding, because you *know* where to inject the signal, and you should *know* what to expect when you do.

Warning

Do *not* work on any equipment connected to the AC mains. Work only on battery-powered circuits, for your own safety.

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1, R4	10 kilohms (kΩ)
R2, R3	330 kilohms (kΩ)

Capacitors

C1, C2, C3	10 nanofarads (nF) or 0.01 microfarad (μF) ceramic

Semiconductors

TR1, TR2	BC108

Additional items
- PP3 battery and connector
- Matrix board 10 cm by 3 cm
- 6BA solder tags
- Thick insulated wire for probe
- Crocodile clip

49 Standing waves

Introduction

Everyone has, or *should* have, a standing-wave ratio (SWR) meter as part of his/her array of test gear. Most people know how to use it, but what does it really do?

Before attempting to answer that question, we need to look at some aerial fundamentals. An aerial is a *transducer*, the word meaning ‘to lead across’. We use it whenever one form of energy is converted into another form. A bulb is a transducer; it converts electrical energy in the filament to radiated heat and light energy. **Figure 1** shows the situation.

An aerial, or antenna, is also a transducer; it converts radio-frequency (RF) energy in the feeder (or *transmission line*, to give it its proper name) into radiated electromagnetic energy, in the manner shown in **Figure 2**. The aerial has resistance, just like the bulb filament, and if the filament had zero resistance, there would be no radiated energy. In the same way, if the aerial had no resistance, there would be no radiation from it.

Transmission lines should convey RF energy from transmitter to aerial with the minimum power loss. A common form of transmission line is the *coaxial*



Figure 1 The light bulb converts electrical energy to electromagnetic light energy



Figure 2 The antenna converts RF current to electromagnetic radio waves

cable. As you might expect, any feeder cable has a DC resistance caused by the resistance of the copper wire from which it is made. It also has an AC resistance, caused by the capacitance between the centre conductor and the braid, and by the inductance of the cable itself. This means that the feeder has an *impedance*, which is constant for the particular type of cable. This is what we call the *characteristic impedance* and, for the cables used in most amateur radio applications, it is 50 Ω.

If this impedance can be made the same as that of the aerial (it is already the same as the impedance of the transmitter output), then the transfer of energy will occur with minimum loss. If the aerial and cable impedances are *not* the same, then there is a *mismatch*, which causes some of the RF energy to be reflected back towards the transmitter. We now have a situation where RF energy is flowing along the cable from the transmitter to the aerial (the *forward* wave) and, at the same time, flowing from the aerial to the transmitter (the *reflected* wave). The two waves interact along the cable and form a stationary pattern of voltage and current. The pattern is known as a *standing wave*, and can be visualised from the waveforms in **Figure 3**. The ratio of the maximum voltage to the minimum voltage on a given wave defines the *voltage standing-wave ratio* (VSWR), or just *standing-wave ratio* (SWR) for short.

The SWR meter is easy to use. It is positioned in the feeder between the transmitter and the aerial tuning unit (ATU) if there is one, or between the transmitter at the aerial otherwise. Most meters have a single meter and a four-position switch. The transmitter is first keyed and, with the switch in



Figure 3 Standing waves on a transmission line

the 'calibrate' position, the sensitivity control is adjusted to give full-scale deflection on the meter. The switch is then changed to 'forward' to read the forward power, to 'reflected' to read the reflected power, and to 'SWR' to read the value of the standing-wave ratio. When there is no reflection (see Figure 3), the meter should read 1:1 or, simply, 1.

Most SWR meters remain in the feeder line while the transmitter is operating, so the condition of the aerial and feeder can be constantly monitored. Problems with the aerial (such as water entering the feeder at its junction with the driven element) are immediately shown up. Without the use of the SWR meter, the situation would slowly deteriorate over several months and you would be left wondering why so few stations were answering your calls!

50 A standing-wave indicator for HF

Introduction

The standing-wave ratio (SWR) meter shows how well the aerial system, including the feeder, is *matched* to the output of the transmitter. This design does not *measure* SWR, but it gives an indication of when the SWR is minimum for a given system of aerial and feeder. The design is usable on the HF bands from 1.8 to 28 MHz, and can be used at 50 MHz with reduced sensitivity.

How it works

There are two types of wave in any feeder: the *forward* wave, which travels from the transmitter to the aerial; the *reflected* wave, which travels back to the transmitter from the aerial. The presence of a reflected wave is evidence that some of your transmitted power is not being radiated, but is being returned to the transmitter to be lost as excess heat. When aerial and feeder are perfectly matched, there is *no* reflected wave, and all the power from the transmitter is radiated.

Referring to the circuit of **Figure 1**, a tiny fraction of the signal is removed by the transformer, T1, and by the capacitors, VC1 and C1. It is then detected by the germanium diodes, D1 and D2, and any residual RF removed by the capacitors, C2 and C3. The currents through the diode and meter (depending on the position of switch, S1) represent the forward and reflected signals. VR1 acts as a sensitivity control for the meter.

It pays to shop around for a suitable meter. Surplus types from tape recorders and hi-fi equipment are usually ideal for this purpose. A new one would cost several pounds. The more sensitive the meter, the more sensitive your indicator will be. Meter sensitivity is given by the current required to give full-scale deflection (FSD) of the pointer. One with an FSD of between 50 and 200 micro-amps (μA) is suitable for this circuit. The higher the FSD, the less sensitive the circuit.

Construction

The meter circuit and the sampling transformer (see **Figure 2**) are built and mounted on Veroboard of the copper-strip variety. It simplifies construction



Figure 1 Circuit diagram of the SWR meter



Figure 2 Component layout of the SWR meter

but reduces the operational range of the meter to below 30 MHz because of the capacitive coupling between strips. The board has 13 strips by 30 holes, although you can reduce this if you have a smaller case.

Firstly, cut the tracks at the three points shown. Then insert and solder Veropins for connections to the external components, the switch, variable resistor and the meter. Solder in the components starting with the resistors and followed by the capacitors and the diodes, ensuring that the diodes are inserted correctly.

Now you have to wind the transformer, T1, on a small toroidal ferrite core. Wind the secondary with 15 turns of 36 SWG enamelled copper wire, spaced evenly over about two-thirds of the former. The turns should not overlap, and considerable care must be taken; the wire is very thin, will kink easily and will break if you apply too much tension. The ‘primary’ is an 8 cm length of 50 Ω coaxial cable which passes through the toroid on its way between the input and output connectors. The braid of the cable is connected to the case at only *one* of the connectors (see Figure 1); this prevents the screen and the metal case between the two sockets forming a single, shorted turn.

The ends of the secondary winding must be carefully stripped of their enamel with sandpaper, before attaching the toroid to the board with cotton or nylon fishing line. On no account must wire be used for this!

Solder the secondary connections of T1 to the board and thread through the coaxial cable ready for soldering to the connectors.

The case used was an aluminium box (Maplin LF02C), but any suitable metal box could be used. Aluminium is preferable, as it is easily drilled with simple tools. Use standoff insulators to mount the board in the case. Once this has been done, the leads from the board to the chassis-mounted components can be soldered. So can the coaxial cable passing through the toroid. Make the lead from the input socket to VC1 as short as possible.

Setting up

You will need a 50 Ω dummy load and a transmitter to set up your indicator. Connect the transmitter to SK1 and the dummy load to SK2. Set the toggle switch, S1, to *forward* and the sensitivity control, VR1, to mid-travel. Switch on the transmitter, and set VR1 for maximum meter deflection. Switch to *reflected* and adjust VC1 until the reading is minimum (ideally zero). This completes the setting up!

Using the indicator

For setting up an aerial, connect your circuit between the transmitter and the cable leading to the aerial. With S1 in the *forward* position, key the transmitter and adjust VR1 for maximum reading on the meter. Switch to *reflected*, and then adjust your ATU to give minimum reflected power. If your adjustments are to be made to the aerial itself, to give minimum reflected power, you must make a note of the reflected reading, switch off the transmitter, make a change to the aerial, key the transmitter, and note whether the reflected power is greater or less than before. Then, make more changes to the aerial. **Never adjust your aerial with the transmitter on**. Make your adjustments on an unused frequency, and do it as quickly as possible, thus avoiding (or minimising) interference to other stations.

Parts list

Resistors: all 0.25 watt, carbon 5% tolerance
(or Maplin 0.6 watt metal film)

R1, R2	27 ohms (Ω)
R3	2.2 kilohms (kΩ)
VR1	10 kilohms (kΩ) linear

Capacitors

C1	220 picofarad (pF) disc ceramic 50 VDC
C2, C3	0.1 microfarad (μF) disc ceramic 50 VDC
VC1	20 picofarad (pF) trimmer

Semiconductors

D1, D2	OA91 germanium

Additional items

S1	Single-pole changeover (SPDT or SPCO)
SK1, SK2	Coaxial sockets to suit station standards
	Veroboard – 13 strips by 30 holes
	Veropins (7 off)
	Amidon FT 50–43 ferrite toroid
	Meter, less than 200 μA FSD
	36 SWG enamelled copper wire
	Short length of UR43 or RG58 coaxial cable
	Insulated stranded wire
	Aluminium box
	Standoff insulators for mounting the board
	Knob for the sensitivity control

51 A moisture meter

Introduction

Dry rot (*Merulius Lacrymans*) can strike havoc in buildings, causing the timbers to decay and crumble to dust – hence the term *dry rot*. Wood is attacked only if its moisture content rises above 20%.

Construction

The circuit of the moisture meter is shown in **Figure 1**. The two probes touch the wood, and the current that flows between them depends on the moisture content of the wood. If the moisture is sufficiently high, the current, after amplification, will be enough to light the LED.

The meter can be made on a piece of plain matrix board (no copper strips), as **Figure 2** shows. The board is big enough (10 cm by 2.5 cm) to accommodate the PP3 battery, taped on. No case is needed, unless you want


Probes
R1
100k
b
c
e
R2
15k
R3
180R
TR1
BC108
TR2
BC108
C1
100n
+
LED
−
+
PP3
9V
−
c
b
e
TR1 and TR2
base view
LED
Flat
Short
lead
−
+
©RSGB DY148

Figure 1 Circuit diagram of a moisture meter


Solder tag probes
bolted on with 6BA bolts
+9V
R3
R2
+
LED
−
c
TR1
b
e
c
TR2
b
e
R1
C1
Tape
PP3
battery
Snap
Perforated board
10 x 2·5cm
Solder wires
on tags
−ve
Battery secured with
rubber band or tape
+9V
−ve
©RSGB DY149

Figure 2 Moisture meter, component layout

to leave the meter in a damp location for a protracted period! Make sure that the transistors and LED are mounted correctly. In Figure 2, the connections as shown to TR1 and TR2 are illustrated as if the transistors were transparent. An on/off switch is not really necessary, as only a very small current flows when the probes do not touch anything. Use solder tags, screwed to the board, to act as probes.

After the assembly is completed, check your circuit one final time, and then connect the battery. Nothing should happen at first. If you lick your forefinger and hold it across the probes, the LED should light.

Using it

The prototype was compared with a commercial moisture meter, and the LED lit when the moisture was around 20%. This was quite fortuitous, as the point at which the LED lights depends both on the separation of the probes and on the gain of the two transistors.

In addition to searching for dry rot, the instrument may be used to monitor the moisture in the soil of household plants. In this case, probes made of 16 SWG copper (*not* enamelled) should be soldered on to the two tags, and should penetrate the soil to a depth of several centimetres, and R1 may require adjusting so that the LED extinguishes if the soil is too dry, and lights if the soil is sufficiently moist. If you wanted to leave the meter with the probes in the soil, an on/off switch *would* be necessary.

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1	100 kilohms (kΩ)
R2	15 kilohms (kΩ)
R3	180 ohms (Ω)

Capacitor

C1	0.1 microfarad (μF) polyester

Semiconductors

TR1, TR2	BC108
LED	Any shape or colour will do

Additional items
- PP3 battery and connector
- Solder tags (2 off) for probes
- Matrix board 10 cm by 2.5 cm

52 Simple aerials

Introduction

The performance of *any* receiver or transceiver, no matter how expensive it is, is limited by the aerial that feeds it. Two of the most frequently asked questions are:

- Which is the best sort of aerial to use?
- Where is the best place to locate an amateur radio aerial?

To answer these questions, you must ask yourself what sort of operation you want to do. Are you interested in local, chatty contacts on the lower bands or VHF, or are you more disposed towards long-distance (DX) contacts, and on what band?

A house with a moderately sized garden is assumed in the diagrams here, to illustrate the configurations of some simple aerials. You would not need all these aerials festooned around your house, because one or two would be sufficient for your needs. The problems incurred by properties with more restricted space will be covered later.

VHF aerials

For VHF operation, the aerial should be mounted as high as possible, either on a mast or on a chimney. For all-round coverage on FM and the local repeaters, a vertical colinear is a good choice. For SSB and CW DX operation, a horizontal rotatable beam is needed. If satellite working is envisaged, you will need to contemplate mounting an elevator on top of your rotator, so that your beam can point in *any* direction, including vertically upwards! An advantage of satellite working is that the aerials do not *necessarily* have to be up in the air, provided you have a relatively uncluttered site. Your rotator and elevator can be at ground level, which is good!

If the VHF aerial is mounted on the chimney, use a double mounting bracket, particularly if you have a beam and rotator. Keep the TV, broadcast FM and amateur aerials as far apart as possible, and keeping the feeders separated is also a good plan.

The dipole aerial

One of the simplest types of aerial for single-band operation is the half-wave dipole. (The name ‘dipole’ simply means ‘two poles’ or ‘two elements’, and



Figure 1 Layout for a dipole aerial

in this case the total length of the dipole is approximately half a wavelength at the operating frequency.) It is usually fed in the centre by coaxial cable as shown in **Figure 1**. The length of the dipole for the lowest frequency in each band is shown in **Table 1**. Normally, the length of the aerial will be 'trimmed' to be tuned to the centre frequency of the part of the band in which you will operate. This is done using the data in the right-hand column of Table 1. As an example, suppose you wanted your aerial to be resonant at 3.7 MHz. The table gives an overall dipole length of 42.86 m for 3.5 MHz. To resonate the aerial 200 kHz *higher*, then this length must be shortened by 2 × 0.595 m = 1.190 m. Your dipole would thus be 41.67 m long. Remember to allow extra wire for fixing the dipole ends to the insulators.

Table 1 Dipole lengths for lowest frequency of each band and the length to be trimmed from each to raise the resonant frequency by 100 kHz

Band (MHz)	*Dipole length (m)*	*Trim each end (mm/10 kHz)*
1.8	83.33	2190
3.5	42.86	595
7	21.43	150
10	14.85	70
14	10.71	35
18	8.33	20
21	7.14	15
24	6.03	12
28	5.36	10
50	3.00	6

On the lower-frequency bands, the lengths become rather large. In this case, you can 'bend' your dipole, as illustrated in **Figure 2**. The length of wire required to give an acceptable value of SWR (less than 2:1 on transmit) may need to be different from the calculated value, so be prepared to experiment!

Dipoles are single-band aerials, although they will often work acceptably on the third harmonic of their design frequency: a 7 MHz dipole often operates reasonably well on 21 MHz. It is possible to operate several dipoles in parallel, as **Figure 3** shows. Interaction between the elements can occur if the spacing between them is less than about 10 cm. A multi-band dipole, as shown in Figure 3, has the elements separated with plastic spacers, and drooping ends to produce maximum spacing between the elements' ends.


End insulator
Insulated support
Nylon cord support
Centre insulator
Coax feeder
End insulator
Nylon cord supports
©RSGB DY152

Figure 2 Possible layout for a dipole aerial in a confined space


Spacers at ≈ 300mm centres
Centre insulator
Coaxial cable to rig
100mm or more between dipoles
©RSGB DY153

Figure 3 Multi-band dipole aerial

The long-wire aerial

This aerial is simple, cheap, easy to erect, and suits most houses and gardens, as **Figure 4** shows. Using an aerial tuning unit (ATU), an end-fed long wire can function on several bands when used with a set of radials or a counterpoise. **Figure 5** illustrates the setup. The length of the aerial will determine the bands which will be covered.


Nylon cord support
Insulators
Antenna wire
©RSGB DY154

Figure 4 Long-wire or inverted-L aerial


©RSGB DY155
Long wire antenna
Transmitter/receiver
SWR meter
ATU
50Ω
Safety earth
¼-wave counterpoise wires for each band

Figure 5 How to connect a radio to a long-wire aerial

A wire length of 10.5 m will work on the 40, 30, 17, 15 and 12 m bands.

A wire length of 15.5 m will work (with an ATU) on the 80, 40, 20 and 12 m bands and possibly (depending on your ATU) on the 17 and 15 m bands.

A wire length of 26.5 m will operate on all bands, but may be difficult to load on 10 m.

The wire lengths given here may need some adjustment because of the geometry of your particular house and garden. For receive-only purposes, the lengths are far less critical.

In general, you cannot get a good radio-frequency (RF) earth from a first-floor (or higher) shack. Unless a good RF earth exists within a small fraction of a wavelength of the transceiver, an *artificial ground* comprising a single $\frac{\lambda}{4}$ radial or counterpoise will be needed. You will need one counterpoise for each band you intend to use, and the wire can be concealed around the skirting-board of the shack, or under the carpet. Make sure that the free end

Table 2 Lengths of elements for vertical antennas, radials for verticals and counter-poises for end-fed long wire antennas

Band (MHz)	*Element length (m)*
1.8	39.66
3.5	20.40
7	10.20
10	7.14
14	5.1
18	3.96
21	3.4
24	2.95
28	2.55

of each counterpoise is well insulated; this point can carry a *very high voltage* when you transmit; anyone coming into contact with this can suffer very severe RF burns. Counterpoise lengths can be read from **Table 2**.

The vertical aerial

The single-band vertical aerial is sometimes used by DX operators because it has a low angle of radiation, which favours long-distance propagation. However, it must be sited clear of obstructions and must have a *good* counterpoise or radial system. Illustrations of the vertical aerial are shown, and the lengths of the vertical and radial sections are given in Table 2. The centre of the coaxial feeder is connected to the vertical section, and the braid to the counterpoise or radial system, which is made up of four or more wires buried just below the surface and joined together near the base of the aerial.

Cable entry to the house

Bringing coaxial cable into the house by an open window must be regarded as a temporary measure. Wooden window frames can be drilled, one hole for each feeder. Make the holes slope downwards from inside to out to prevent rain entering, and treat these with wood preservative. Leads from long-wire and inverted-L aerials should be kept separate from other cables.

Alternatively, a plastic pipe large enough to take all your feeders could be fitted into the brickwork (again, sloping downwards towards the outside). You may want to let a friendly builder do this for you.

53 A breadboard 80 m CW transmitter

Introduction

In the early days of radio, many circuits were built on a wooden baseboard, the parts being screwed down on the board. This was called breadboard construction, because it was a breadboard that was frequently commandeered for the process! Wives have always been generous in this respect, it appears!

This circuit was originally designed by GM3OXX, and became known as the *Oner*, because it was built on a circuit board one inch square! The circuit appeared in the G QRP Club journal *Sprat* and, since that time, many hundreds of *Oner* circuits have been built and used on the air. It is a well-proven circuit.

The transmitter has no tuned circuits in the power amplifier (PA) and thus has a rather high *harmonic* content. It **must** be used with the ***low-pass filter*** described elsewhere in this book. Without the low-pass filter, interference will be caused to other stations.

Simple aerial changeover switching is provided, which allows this circuit to be used with any of the 80 m receivers, such as the *Colt*, described in this book. It can also be used with any kit or commercial receiver for the 80 metre band.

The circuit

The transmitter circuit is shown in **Figure 1**. TR1 is a crystal oscillator, the frequency of which is controlled by crystal X1. A small trimmer capacitor, TC1, is added to allow the frequency of X1 to be varied by a small amount. If adjustment of this trimmer is made possible from the front panel, it is useful to adjust the transmit frequency to avoid other stations already on the crystal frequency. The collector load resistor, R2, of the oscillator transistor, TR1, determines the power output; a value of 3.3 kΩ seems to work well in producing an output of 3 watts.

TR1 is directly coupled to TR3, a VMOS transistor (a type of field-effect transistor (FET)). This acts as the power amplifier (PA) stage. TR3 should


ZTX651/
751
VN10KM
e
b
c
s
g
d
Viewed on flat
Net and transmit/
receive swtch
+12V
TR2
ZTX751
To filter &
Antenna
e
c
C2
100n
R2
b
R3
RFC
C1
1k
Key
100n
TC1
C3
100n
R1
100k
d
X1
g
c
b
s
Receiver
TR1
ZTX651
e
TR3
VN10KM
©RSGB DY140

Figure 1 Circuit diagram of the breadboard transmitter

give about 3 W output, which is then coupled to the output by C3. The radio-frequency choke (RFC) providing the drain load of TR3 is simply a few turns of wire on a ferrite bead.

TR2 is an interesting addition to the circuit. It is used as a switch to 'key' the PA, TR3. The transmitter *could* be built without TR2, just placing the Morse key between the top of the RFC and the 12 volt supply. Adding TR2 is helpful, because it means that one side of the Morse key can be grounded (always a good thing), and some degree of *shaping* of the output RF waveform is provided by R3 and C1. This makes the transmission sound a little better and reduces the possibility of spurious frequencies being generated and transmitted. TR2 is a pnp transistor; note that it is the *emitter* of this transistor which is connected to the positive side of the supply.

Some form of changeover switching is needed for the aerial. A double-pole changeover toggle switch can be used. See the chapter on switches, later on in this book. One pole is used to switch the aerial between transmitter and receiver; the other pole is connected in the 12 volt supply line, and is labelled RECEIVE/TRANSMIT – NETTING. Its use will be described later. In this simple circuit, the PA cannot work when the key is open, because the key breaks its supply (via the RFC). When the key closes, TR2 switches on and applies the 12 volt supply to the top of the RFC. C2 is a *decoupling* capacitor, which prevents any residual RF signals at the top of the RFC reaching TR2.

Building

The prototype was put together as follows. Take a piece of plain printed-circuit board (PCB) measuring 5 cm by 4 cm. Then, with a *new*, *sharp blade* in a junior hacksaw, draw the blade horizontally across the surface of the copper in order to make a pattern of 6 squares along the 5 cm side and 5 squares along the 4 cm side. No more pressure should be applied than is necessary to cut through the copper! All the parts will be soldered on these pads in a form of surface-mount construction. To do this, each active pad (i.e. one that is going to have a component soldered to it) needs to be *tinned*. This means coating the pad's surface with solder, and is carried out as follows. Place the hot tip of the soldering iron on to the pad, and hold it there for a second or so. Then, with the tip still in place, touch the end of your reel of solder *on the pad*, not the tip of the iron. The solder should flow evenly all over the pad, and you can remove the iron. The solder should solidify in a rounded, shiny blob! This provides a good surface for making soldered joints.

To join component leads to the pads, cut each lead about 1 cm long, and then bend the last 2 mm at right angles to the rest of the lead. As you did before, tin the 2 mm length of each lead. Place the tinned portion on to the pad, and place the tip of your iron *on the pad*, close to the lead. The solder on the pad and on the lead will melt and run together; remove the iron and *hold the component still* until the solder solidifies. When the joint has cooled, give the lead a gentle tug to make sure you have a good joint (a good *mechanical* joint is usually a good *electrical* joint, too!). Each transistor straddles three pads, so the centre lead will need to be shorter than the other two. Take care here to get the lead lengths right – if you do, you will be surprised how much more firmly the transistor is held than if you just botched the lead lengths by bending them to fit! Make sure the connections to the transistors are correct.

Winding the RFC is quite simple. Seven (or more) turns of thin (32 SWG) enamelled copper wire are threaded through a small ferrite bead. This requires care, because the bead is small and the wire is thin. Trim the ends to within about 1 cm of the bead, remove the enamel carefully with sandpaper and tin the bare ends, prior to soldering the choke to the board.

After completion of the wiring, check the circuit against Figure 1. Bread-boarding a circuit like this has its advantages, but it can have disadvantages, too. One of these disadvantages is that it can make circuit checking difficult. For a simple circuit like this, it is not too bad! Check that no solder has run between the pads. Plug in your crystal for the 80 m band, and connect up the 12 V power supply. Do not connect the Morse key yet and do not switch on the power.

Testing and operating

Clear your workbench of all metallic objects, slivers of copper, bits of wire, etc., switch on your power supply. With an external receiver, listen on and around your crystal's frequency for a signal. Remember that the oscillator runs all the time and, because you haven't yet connected the Morse key, your receiver is close enough to pick up the signal from the oscillator. This confirms that your oscillator is running. Switch off.

Connect the station aerial to the transmitter's aerial socket, and the receiver to the transmitter's receiver socket. Connect the Morse key, put the Receive/Transmit–Netting switch in the receive position and switch on. You should be able to hear stations in the normal way. Now put the switch in the Transmit–Netting position. Signals in the receiver should almost disappear, as the circuit has disconnected the receiver's aerial.

Tune the receiver until you can hear your own crystal oscillator signal. This is known as *netting*, tuning your receiver and transmitter to the same frequency. Pressing the key will now transmit your signals when the switch is in the Transmit–Netting position; switch back to the receive position to listen for stations answering your call. As soon as you are happy that your circuit is functioning properly, **you must build the low-pass filter circuit** before using the transmitter regularly.

Parts list

Resistors: all 0.25 watt, 5% tolerance	
R1	100 kilohms (kΩ)
R2	See text
R3	1 kilohm (kΩ)
Capacitors	
C1, C2, C3	100 nanofarads (nF), or 0.1 microfarad (μF)
TC1	3–60 picofarads (pF) trimmer
Semiconductors	
TR1	ZTX651
TR2	ZTX751
TR3	VN10KM
Additional items	
RFC	7 turns of 32 SWG enamelled copper on a ferrite bead
Switch	Double-pole changeover (DPDT or DPCO) toggle
Crystal	For 80 m band
Crystal holder	HC25 type
Sockets	According to station fittings



54 A 7-element low-pass filter for transmitters

Introduction

The simpler the transmitter, the more likely it is to radiate *harmonics* of its fundamental frequency. Harmonics are integral multiples of the frequency on which the transmitter is *designed* to operate. If you think you are transmitting on a frequency, *f*, for instance, you will also be radiating the harmonics of *2f*, *3f*, *4f*, . . . and so on. This results in your signals being heard on *several frequencies*, spread over a very wide frequency range. You are also contravening the terms of your licence. To avoid this, it is always advisable to use a *low-pass* filter between your transmitter and aerial. This is a filter which will *pass* your signal frequency, *f*, and all frequencies *below* it, but will *not pass* (attenuate) frequencies above *f* to any significant extent. The value of *f* is known as the *cutoff frequency* of the filter.

A design of 7-element low-pass filter

A 7-element low-pass filter (LPF) is so called because it has seven components, as the circuit diagram of **Figure 1** shows. Filters containing any odd number of elements are possible: a 3-element filter would



Figure 1 Circuit diagram of filter

comprise C1, L2 and C3 only, and is sometimes called a pi-network because the element disposition resembles the Greek letter pi (π); a 5-element filter would comprise C1, L2, C3, L4 and C5 only, and so on. In general, the more elements the filter has, the more effectively it attenuates signals above *f*.

The circuit of Figure 1 is designed to have an input and an output impedance of 50 Ω, which means that it can be placed in the aerial feed of any common transmitter. Filter design is a very complex business, and is best left to the experts. One such expert is W3NQN, who produced a number of computer designs of LPF using commonly available (*preferred value*) capacitors, and aimed specifically for use on amateur frequencies. The results of this work are condensed into **Table 1**. The inductors are wound on standard toroidal cores, and their details are included in the table.

Table 1 Filter component values for each brand

Band metres	*C1,7 pF*	*C3,5 pF*	*L2,6 turns*	*L4 turns*	*Core type*	*Wire SWG*
80	470	1200	25	27	T37-2	28
40	270	680	19	21	T37-2	26
30	270	560	19	20	T37-6	26
20	180	390	16	17	T37-6	24
15	82	220	12	14	T37-6	24
10	56	150	10	11	T37-6	22

Making the filter

The filter was made originally as an adjunct to the *Breadboard 80 m CW transmitter*, which you will also find in this book. It uses the same constructional technique, based on a single piece of plain, copper-clad



Figure 2 Layout and construction of filter

PCB, with 'pads' created by using a sharp blade in a junior hacksaw. The cuts in the copper are shown in the layout diagram of **Figure 2**. There are two ways of mounting the components: the first way is to drill small holes in each pad, as shown in Figure 2, and mount the components through the holes in the normal PCB manner; the second way is to solder the components directly to the pads, in the way that was described for the *Breadboard transmitter.*

Winding the inductors is quite simple. All you need to remember is that each time the wire passes through the core counts as one turn. Cut off the spare wire at each end of each coil to about 1 cm, scrape off the enamel with sandpaper, and tin the exposed copper. See the transmitter description if you are unsure of how to do this. Note the wire links between each of the lower pads, forming a solid 'ground' for the elements. The prototype had a plug and socket on the ends, to match the transmitter and aerial terminations.

The type of capacitor used in the design is not critical; the polystyrene type works well.

55 Radio-frequency mixing explained

Introduction

Mixers find widespread use in electronic circuitry. Many of the projects in this book, together with every TV set and radio in the home, contain mixer circuits – a good indication of their usefulness.

Confused?

Audio mixers (as used in recording studios and radio broadcast stations) are used to **add** or ‘balance’ the signals from various sources such as microphones, CD players, etc. These have nothing whatsoever to do with radio-frequency (RF) mixers, and should never be confused with them.

RF mixers and beat frequencies

Instead of **adding** signals (as in the audio mixer), the RF mixer **multiples them together.** As you might expect, this has an entirely different effect. The two signals entering the mixer *beat* or *heterodyne* with each other to produce *signals on other frequencies*. One example of this occurs in sound, when two musical notes of almost the same frequency are heard together. Instead of hearing two separate notes, the listener hears one note whose *intensity* (*loudness*) appears to increase and decrease. This intensity variation is called a *beat*, and its frequency is equal to the difference in the frequencies of the two original notes. The technique is used by musicians to tune their instruments. If one note is known to be a correct frequency, the other can be tuned to it by making the beat frequency as close to zero as is possible.

Multiplying together

The process of mixing presupposes that we have a device which will automatically multiply two signals together. Fortunately, this is easy; so easy, in fact, that it often occurs when we do not want it! Multiplying is achieved by any device which is *non-linear*; this means a device whose output is not a constant factor larger than its input, something that can be achieved by many electronic devices and circuits.



Figure 1 The effect of multiplying (or mixing) two signals together

Let us look now at what a mixer does in concrete terms. Suppose two signals, of frequencies *f*1 and *f*2 go into our mixer. These signals are shown in **Figure 1**. Putting numbers in, to make the situation clearer, suppose *f*1 is 1.000 MHz and *f*2 is 160 kHz. The beat frequency is the *difference* of these: 1.000 MHz – 0.160 MHz = 0.840 MHz, or 840 kHz. A mixer *also* produces an output at the *sum* of these frequencies; in this case the new frequency would be 1.000 MHz + 0.160 MHz = 1.160 MHz.

Suppose you fed the output of your mixer, operating with these input frequencies, into a receiver and tuned around to find what frequencies were present. You would find two signals, one at 840 kHz and one at 1.160 MHz, showing that the two 'new' frequencies were very real!

In addition to drawing out the waveform of the resultant signal, as in Figure 1, we can draw the inputs and outputs on a frequency axis, to form a *spectrum* of the signal components. This is done in **Figure 2**. The top two diagrams show the input signals at *f*1 and *f*2. The bottom diagram shows the output signals in relation to the input signals. Depending on the type of mixer used, one or both of the input signals would be removed.



Figure 2 The result of multiplying or mixing two signals together as seen on a spectrum analyser

A mixer in every radio

Basically, a mixer is used to change a signal from one frequency to another, something it does without altering the characteristics of the incoming signal. If the incoming signal is amplitude modulated (AM), then the frequency-changed signal would be AM also. The same applies to FM, SSB, CW, and all other modulation forms you can think of. This explains why mixers are often called *frequency changers*.

Frequency changing is the key process in the type of radio known as a *superheterodyne* (or *superhet*). By mixing the incoming signal with a variable-frequency *local oscillator* as **Figure 3**, shows, the signal can be converted to the fixed frequency of a filter and amplifier. This is useful


Incoming signal
Mixer
Fixed frequency amplifier and filter
Variable frequency 'local' oscillator
©RSGB DY147

Figure 3 The basic idea of a superhet receiver

because it is easier to make a very high-quality filter and amplifier at a single fixed frequency, than at a variable frequency.

All TV receivers and virtually all radio receivers (and transmitters) use mixers. Both the *Yearling* and *Colt* receivers (see the relevant projects) are superhets, and use mixers.

56 A voltage monitor for a 12 V power supply

Introduction

If for any reason, the stabilisation of your main 12 volt power supply unit (PSU) breaks down, it is possible that a voltage much higher then the nominal 13.8 V will be applied to your precious equipment. If you would like to know the instant that this occurred, and hence be able to switch things off before it was too late, then this circuit is what you need. It will give audible *and* visual indications if the voltage rises above 14.4 V, and a visual indication only if the voltage is reduced.

The circuit

The circuit uses three ICs and is shown in **Figure 1**. The circuit is powered by the PSU whose output is being monitored, and the circuit's immunity to supply line variations is secured by the 6 volt regulator, IC1. The heart of the circuit is IC2, an LM3914; it is a *bargraph driver*, which operates ten LEDs in a display resembling a thermometer – the string of lit LEDs increases in length as the voltage on pin 5 increases.

The input voltage range on pin 5 is 1.2 V maximum, making each LED correspond to one-tenth of this, which is 0.12 V, the *step size*. R1 and R2 act as a voltage divider, so that voltages of up to the maximum of 14.4 V may be applied to R1 without exceeding 1.2 V at pin 5. R3 sets the brightness of the LEDs and R4 determines the step size.

IC3 is an *opto-isolator*, a device containing an LED and a phototransistor in one package. This enables the piezoelectric sounder to operate without affecting the operation of the bargraph driver. The input to IC3 is provided by the voltage on D8, so that if any of the LEDs at or above D8 are lit, the



Figure 1 PSU monitor, circuit diagram

sounder will operate, indicating overvoltage. Despite the fact that some of your other equipment might be damaged by this overvoltage, the monitor circuit itself is unaffected.

Construction

The prototype was built on two pieces of Veroboard of the copper-strip variety. The main (circuit) board measured 15 strips by 25 holes, and the display (LED) board measured 4 strips by 30 holes. Track cuts are necessary in each board. The correct places are shown for the main board in **Figure 2**, but there is sufficient flexibility in the layout of the display board for a prescriptive layout not to be needed. All the anodes of the LEDs are connected to the same strip, which makes things comparatively simple!

For the main board, insert the Veropins and the wire links first, and solder them to the copper strips. Then fit the IC holders and the resistors. Fit the IC holders with their notches towards the top of the board. When fitting the voltage regulator, IC1, note than the centre lead (the ‘common’ lead in Figure 1) does *not* go to position A3; the track should be cut at A3, and the common lead soldered at B3. This is indicated in Figure 2.

Wire up the LED board with its ten LEDs and 11 connecting wires, each about 10 cm long. This length depends on how far away from the main


Note:
Cut in copper track
at A3 not shown
+ve supply
Component side of board
1
IC1
5
10
15
20
25
A
B
C
D
E
F
G
H
I
J
K
L
M
N
O
P
D1
D2
D3
D4
D5
D6
D7
D8
D9
D10
IC2
IC3
R1
R2
R3
R4
LS1+
Sounder
LS1–
0V supply
+ve supply
● = Pin
●—● = Link
= Cut in copper track
A3
D9, E9, F9, G9, H9, I9, J9, K9, L9
D15, E15, F15, G15, H15, I15, K15, L15
I19, J15, K15
©RSGB DY158

Figure 2 PSU monitor, PCB layout

board you are planning to mount the display. The LEDs should have different colours: three orange, four green and three red, to indicate ‘low’, ‘medium’ and ‘high’ voltage.

Now solder the other ends of these leads to the Veropins on the main board, making sure that the order is correct. Finally, connect the piezoelectric sounder to the main board; the polarity is important, so make sure the red lead goes to pin 4 of IC3 and the black lead to the ground rail. If you were careful to fit the IC holders with their notches in the correct positions, match these up with the notches on the ICs before pushing home the ICs *gently*. Check your circuit for solder bridges and unwanted pieces of copper swarf before screwing the small heat sink to the voltage regulator, IC1.

Testing

(a) **With a variable-voltage PSU**. Set the PSU for 10 V, connect the circuit and switch on. Increase the voltage slowly, and check that each LED lights up after the one before it. As the voltage exceeds about 14.4 V, the first red LED should light and the sounder should operate. If an LED does not illuminate, you should immediately suspect either a dry joint or an incorrect LED polarity. The voltage at which the first red LED lights can be adjusted by varying R1; increase R1 if the LED comes on too early; decrease R1 if the LED comes on too late.

(b) **Without a variable-voltage PSU**. For your ‘variable supply’, you can use several AA-type 1.5 V cells (or 1.2 V NiCad cells) in series. The voltages produced by a range of cells is shown in **Table 1** – because of the lower voltage of NiCad cells, more of them are needed to produce a given voltage.

Once the operation of the circuit has been checked, it can be fitted into a plastic or metal box. Only two connections are needed for the PSU. You may want to drill some holes in the case to increase the apparent loudness of the sounder.

Table 1 Test voltages available from batteries in series

No. of batteries	*Voltage, nicads*	*Voltage, dry cells*
7	8.4	10.5
8	9.6	12
9	10.8	13.5
10	12	15
11	13.2	–
12	14.4	–
13	15.6	–

Parts list

Resistors: all 0.25 watt, 5% tolerance

R1	11 kilohms (kΩ) – see text
R2	1 kilohm (kΩ)
R3	1.2 kilohms (kΩ)
R4	18 kilohms (kΩ)

Semiconductors

IC1	L7806
IC2	LM3914
IC3	Opto-isolator – Maplin code WL35Q
D1–D3	3 mm LED, orange
D4–D7	3 mm LED, green
D8–D10	3 mm LED, red

Additional items

LS1	Piezoelectric sounder, wire leads
	6-pin DIL socket for IC3
	18-pin DIL socket for IC2
	Veroboard – two pieces for main and display boards, see text for sizes
	Veropins
	Heat sink for IC1
	Single-core insulated wire for links
	Insulated stranded wire for interconnecting the boards
	Case as required

57 A 1750 Hz toneburst for repeater access

Introduction

Repeaters across the UK and much of Europe need an access tone to switch the transmitter from standby ready for use. Commonly, this is a 1750 Hz tone of duration no greater than half a second. Although many UK repeaters may now be accessed using the *continuous tone-coded squelch system* (CTCSS – see the *RSGB Yearbook*), you may wish to access a repeater whose CTCSS frequency you don't know; in this case, using the universal 1750 Hz tone will gain you access. Commercial transceivers are usually fitted with an automatic toneburst, but if you are using a home-made design, then you may want to incorporate this little circuit.

Warning

This circuit uses a member of the integrated circuit family known as CMOS (complementary metal-oxide semiconductor). These use very little current

and can be completed destroyed if they come into contact with the magnitudes of static electricity that most of us carry about when we walk on carpets and wear rubber shoes. You will never know if this wanton destruction has happened – all you will discover is that your circuit doesn't work and that you have tested *everything*. To avoid this problem do the following things:

1. **Before you open the little packet in which the IC is supplied, touch something which you *know* to be earthed – the metalwork of any equipment which is mains earthed, for example. Then open the packet.**
2. **Let the IC fall gently on the bench – don't pick it out with your fingers. Touch your earthed metalwork again. Pick up the IC and insert it gently into its holder.**

The circuit is safe from destruction while it is connected to the battery.

Circuit description

The circuit is shown in **Figure 1**. The tone is generated by an integrated circuit oscillator (IC1), whose frequency is controlled by a *ceramic resonator*, XL1. Its frequency is very high, and is divided down to the 1750 Hz needed by the same chip. The ceramic resonator is designed to operate at 455 kHz, the intermediate frequency of many receivers. Because all divider circuits use powers of 2, we need the oscillator to run at 448 kHz so that when it is divided by 256 ($256 = 2^8$), we end up with 1750 Hz. Try it on your calculator:

$$\frac{448\ 000}{256} = 1750.$$



Figure 1 Toneburst module, circuit diagram

We use C1, C2 and R1 to *pull* the frequency of the oscillator away from 455 kHz to 448 kHz. The divider chain has eight *counters* in it, and each counter divides the frequency of the signal it sees by two, giving the final division of 256.

This counting process can be stopped at any time by taking the voltage on the *reset* pin (pin 12) up to the supply voltage. When the circuit is switched on by closing S1, pin 12 is at 0 V because C3 is discharged. The oscillator runs, producing the output frequency of 1750 Hz. As time progresses, C3 charges up through R2 and the voltage on pin 12 rises. When this has risen sufficiently, and in a time determined by the values of C3 and R2, the counter resets and stays in the reset state; no division takes place and there is no output. The duration of the toneburst is thus governed by C3 and R2.

When S1 is opened, the circuit is switched off, and C3 is discharged through D1 and R3, ready for the next toneburst. If you have used a repeater, you will know that a toneburst is needed **only** to activate a repeater in the standby condition; it is not needed once a contact has been established.

VR1 adjusts the amplitude of the tone fed to the microphone, and C4 prevents any voltage that may be present on your microphone connector from damaging the integrated circuit.

Construction

The prototype circuit was built on Veroboard of the copper-strip variety, measuring 20 holes by 14 strips. The layout is shown in **Figure 2**. Make the track cuts first, and check that there are no slivers of copper wedged between adjacent tracks. Then, solder in the IC socket (with the notched end



Figure 2 Veroboard component layout

facing towards track A), the wire links and the three Veropins. Having done this, solder in the resistors, capacitors and diode, making sure that D1 and C3 are the right way round! Using your best soldering technique, solder in the ceramic resonator quickly, to prevent heat damage. Recheck your circuit, check for solder splashes and bridges, and then gently insert IC1 into its socket, matching up its notch with that of the socket.

Testing

Set VR1 to half-way and connect a crystal earpiece to the output; apply power to the circuit. You should hear the tone, lasting for about half a second. If there is no tone, disconnect your circuit from the power supply, and check for dry joints in the vicinity of pin 12. Is the diode, D1, the correct way round? Is C3 the correct way round? Did you choose to ignore the CMOS safety precautions given earlier?

Once the circuit is working, you need to decide how you are going to connect it to your transmitter. Two options are shown in **Figure 3**. If you have access to a point in your transmitter circuit that has between 9 V and 12 V positive on it during transmit, you can use this to power your circuit. As the toneburst is needed only for repeaters, the switch, S1, disconnects it when not needed, as shown in Figure 3a. If you want the circuit to be self-powered, then a 9 volt PP3 battery may be used; Figure 3b shows this configuration.



Figure 3 Toneburst module: two alternative switching arrangements

The output from the circuit board is fed directly into the microphone socket, in parallel with the microphone itself; use thin coaxial or screened cable for this lead, or you may induce hum into the microphone circuit and suffer from RF breakthrough into the audio circuits. To adjust the setting of VR1, start with it at the zero output position and connect a dummy load to your transmitter. Slowly, increase the output while monitoring your transmitted signal on another nearby receiver. Make sure you do **not** increase the output so far that the signal sounds distorted. If you would prefer that the tone was on continuously while you made this adjustment, simply connect a wire across C3 remembering, of course, to remove it as soon as you have completed the test!



Parts list

Resistors: all 0.25 watt, 10% tolerance (or better)

R1	1 megohm (MΩ)
R2	150 kilohms (kΩ)
R3	12 kilohms (kΩ)
VR1	10 kilohms (kΩ) horizontal preset

Capacitors: all 16 V WKG or higher

C1, C2	1 nanofarad (nF) disc ceramic
C3	4.7 microfarad (μF) tantalum bead
C4	47 nanofarads (nF) disc ceramic

Semiconductors	
IC1	4060
D1	1N4148
Additional items	
XL1	XR455
	Veroboard (see text for size)
	Veropins (3)
S1	Switch (momentary action push-to-make SPST)
	16-pin DIL socket for IC1
	Single-core insulated wire for links
	Coaxial or screened cable for microphone connection

58 A circuit for flashing LEDs

Introduction

There are many occasions when one's attention needs drawing to the fact that something important has happened. A single red light coming on is seldom sufficient to attract attention, particularly if it is surrounded by other lights and indicators. The eye is known to be very sensitive to *changes* in its peripheral vision; such changes can be brought about by movement or by differences in light level – a flashing light, for example. So, a circuit that flashes a single LED or a pair of LEDs finds plenty of uses in the amateur station.

Warning

This circuit uses a member of the integrated circuit family known as CMOS (complementary metal-oxide semiconductor). These use very little current and can be completed destroyed if they come into contact with the magnitudes of static electricity that most of us carry about when we walk on carpets and wear rubber shoes. You will never know if this wanton

destruction has happened – all you will discover is that your circuit doesn't work and that you have tested *everything*. To avoid this problem do the following things:

1. **Before you open the little packet in which the IC is supplied, touch something which you *know* to be earthed – the metalwork of any equipment which is mains earthed, for example. Then open the packet.**
2. **Let the IC fall gently on the bench – don't pick it out with your fingers. Touch your earthed metalwork again. Pick up the IC and insert it gently into its holder.**

The circuit is safe from destruction while it is connected to the battery. However, when the battery is removed, the same care should be exercised with its handling, because there is no supply decoupling capacitor across the IC.

Basic description

LEDs can be made to flash (switch on and off) by driving them from sources that switch on and off. Such a source is an *astable multivibrator*. If you have built or read about *A basic continuity tester*, elsewhere in this book, you will have come across such a beast before. That circuit used an astable multivibrator made from two transistors. This new circuit achieves the same behaviour from a single integrated circuit, the CMOS 4011. To give it its full description, the 4011 is a *quad 2-input NAND gate*. Quite a mouthful, but all it means is that inside the chip are four NAND gates, each with two inputs.

A NAND gate needs a positive voltage (known as a *logic 1*) on *both* inputs in order to produce zero volts (known as *logic 0*) at the output. Two NAND gates can be connected, as are A and B in **Figure 1**, to make our astable multivibrator. The combination of A and B has been described as the most perverse circuit in electronics; as soon as the output goes to logic 1, the circuit decides that it would prefer to have a logic 0 there, and switches over. With logic 0 at the output, the circuit now prefers to have logic 1 there, and so it goes on! We are going to use this continuous switching backwards and forwards to flash two LEDs. The rate at which A and B 'change their minds' is the frequency at which our LEDs will flash, and is controlled by the charging and discharging times of C1 through R2 and C2 through R1. As the values of R1 and R2 are the same, and those of C1 and C2 are the same, the ON and OFF states of the circuit are the same.

Gates C and D do not contribute to the flashing action; they act as *buffers* to isolate the LEDs from the multivibrator circuit itself. You will find in electronics that an oscillator is seldom used to drive another device *directly*; there is usually a buffer between it and the stage it drives.



Figure 1 Flashing LEDs, circuit diagram

A characteristic of all multivibrators, astable or not, is that they have two outputs. In this case, those outputs are at pins 3 and 10, which are then buffered and appear at pins 4 and 11, respectively. When one output is at logic 1, the other is at logic 0, and vice versa. This means that LED1 is off when LED2 is on, and LED1 is on when LED2 is off, the two states switching backwards and forwards at the frequency of the oscillator.

Construction

Read the warning at the beginning of this article again. It is not intended to scare you off from building this, but is a genuine piece of advice which can save you time and irritation when all your labours result in a circuit that doesn't work! That extra bit of care can make all the difference!

Veroboard (the copper strip type) is used for the layout, shown in **Figure 2**. It measures 20 holes by 12 strips. **Be aware that there is no row 'I' in the layout, so don't miscount when you are placing components on the board!**

Firstly, cut the tracks using a 3 mm (1⁄8 inch) twist drill held between thumb and forefinger; check that there are no slivers of copper bridging any of the tracks, and that the tracks have been completely cut by the drill. Solder in the components carefully. Leave the IC in its carrier for the time being, and solder in the IC socket, with the notched end facing row A. On completion, check the circuit carefully. If you are happy that it is correct, follow the instructions given earlier and fit IC1 into its socket, matching up the two notches. Connect the battery and switch on. The two LEDs should flash on and off alternately. If only one LED flashes, you have probably connected the other one the wrong way round. Switch off, check and correct if necessary. If neither LED flashes, you must have a significant error in your circuit, which will need checking *again*! Or did you choose to ignore the handling precautions for the CMOS chip?

Figure 2 Flashing LEDs, component layout


Component side of board shown
+ve via SW1
©RSGB DY178
1
5
10
15
20
A
B
C
D
E
F
G
H
J
K
L
M
R1
R4
IC1
C1
C2
R3
R2
+LEDs
LED 1 −ve
LED 2 −ve
−ve 9V
= Wire link
= Cut in copper track C16, C11, D5, D11, E11, F11, G11, G16, H5, H11, J6, J11, J17
−
+
a
k

The board can be mounted near to the point where you want your flashing LEDs to be seen, although long leads to the LEDs are acceptable. The LEDs can be different colours – it's all up to you now!

Parts list

Resistors: all 0.25 watt, 10% tolerance or better

R1, R2	4700 ohms (Ω)
R3, R4	1 kilohm (kΩ)
Capacitors	
C1, C2	47 microfarads (μF) 12 V WKG
Semiconductors	
IC1	4011
Additional items	
LED1, LED2	Any size of LED, any colour
S1	SPST on/off
	Plastic box if needed, 8.5 by 5 by 2.5 cm

Source

Components are available from Maplin.

59 Digital logic circuits

Introduction

Logic circuits form the backbone of even the most advanced computer, yet their basic operation can be demonstrated by a couple of switches, a battery and a bulb.

Logic using switches

Everyone reading this article will look at **Figure 1** and know immediately how it works and be able to write down something like ‘When switch A and switch B are closed, the light will come on’. Without knowing it, you have written down a logic statement involving the so-called **AND** operation; the light comes on only when switches A **AND** B are ON. Below the circuit in Figure 1, is a table showing the only possible positions of the two switches and the state of the bulb for each position. This is called a *truth table*, and is frequently used in logic analysis.



A	B	Lamp
Off	Off	Off
On	Off	Off
Off	On	Off
On	On	On

©RSGB DY182

Figure 1 Switches and lamp AND gate

Figure 2 shows a different circuit. Here, the two switches are in parallel rather than in series, as was the case in Figure 1. Again, if you analyse the circuit in words, you would say that the light will be on when switch A **OR** switch B is ON. This is an example of the **OR** operation, and its truth table is shown in Figure 2. The statement above is not complete, however; can you see why? The truth table will show you. The light comes on if A is ON, **OR** if B is ON, ***OR*** if A **AND** B are both ON. That third condition is easy to miss, but don’t worry about it!



A	B	Lamp
Off	Off	Off
Off	On	On
On	Off	On
On	On	On

©RSGB DY184

Figure 2 Switches and lamp OR gate

Believe it or not, some very complicated logic is possible (in theory) using switches and lights, but it is highly impractical and would be very slow. This is where electronic logic circuits come in.

Switches with no moving parts

You may have come across projects in this book where a statement is made such as '. . . the transistor is being used as a switch . . .'. Transistors *can* be used as switches, as were thermionic valves in the world's first programmable computer *Colossus*, at Bletchley Park. However, technology has moved on from valves, through transistors to *logic gates*, combinations of electronic switches designed specifically to perform logic functions.

These act on voltage levels as their inputs and produce changes in voltage levels as their outputs. A positive voltage is called *logic 1*, and corresponds to a switch being ON in our previous descriptions; a zero voltage is called *logic 0*, and corresponds to a switch being OFF. The output from a logic gate (normally labelled Q) is also logic 1 or logic 0, corresponding to our light being ON or OFF, respectively, in our switch analogy.

Many logic devices operate from a stabilised 5 V supply, and this determines the *ideal* voltages corresponding to the two logic states:

logic 0 ≡ 0 V,

logic 1 ≡ 5 V.

The world isn't an ideal place, so the *real* voltage ranges used by the logic gates are:

logic 0 ≡ 0.0 to 0.4 V,

logic 1 ≡ 3.0 to 5.0 V.

The **AND** circuit of Figure 1 is now called an **AND gate**, and requires logic 1 inputs on A **AND** B to produce a logic 1 at the output. **Figure 3** shows this. The truth table is identical with that of Figure 1 – logic 1 replaces ON and logic 0 replaces OFF. Now compare Figure 2 with **Figure 4** – circuits and truth tables for the **OR** function. Again, we have exact similarity.



Inputs		Output
A	B	Q
0	0	0
0	1	0
1	0	0
1	1	1

©RSGB DY183

Figure 3 Electronic AND gate



Inputs		Output
A	B	Q
0	0	0
0	1	1
1	0	1
1	1	1

©RSGB DY190

Figure 4 Electronic OR gate

There is another very common logic gate, which performs the **NOT** function. It is easy to understand. Just ask yourself the question 'What is **NOT** logic 0?', and the answer is obviously 'logic 1'. Similarly, logic 0 is **NOT** logic 1. A **NOT** gate simply changes the logic state of the input; it is also known (because of this behaviour) as an *inverter*. Its symbol and truth table can be found in **Fig 5**. Note the little circle on the output of the gate in Figure 5. In logic circuits, this symbol always implies inversion, or the presence of a **NOT** gate. Keep an eye open for it!

So far, the logic functions we have discussed have all been words which we use in everyday language, which has made the electronic interpretation of them relatively easy. Now we must introduce a function for which there is *no* analogy in normal speech – the **NAND** function. This means a



Input	Output
1	0
0	1

©RSGB DY185

Figure 5 Electronic NOT gate

combination of an **AND** gate and a **NOT** gate, and the sharp-eyed reader will have spotted the little circle added on to the normal **AND** gate symbol in **Figure 6**!

To make things easier to understand, the truth table in Figure 6 has four columns, not three as in previous tables. The third column is the standard **AND** output – compare it with the third column in Figure 3. That is the output from the **AND** gate *before* it encounters the little circle that inverts it, so the final output from the **NAND** gate is the output of the **AND** gate, inverted! The third and fourth columns are the inverse of each other.



Inputs		and	Output
A	B		Q
0	0	0	1
0	1	0	1
1	0	0	1
1	1	1	0

©RSGB DY186

Figure 6 Electronic NAND gate



Inputs		or	Output
A	B		Q
0	0	0	1
0	1	1	0
1	0	1	0
1	1	1	0

©RSGB DY187

Figure 7 Electronic NOR gate

We can add the inverting operation to the output of an **OR** gate also, producing a **NOR** gate! The symbol and its truth table are shown in **Figure 7**. Again, notice that the final output is that of the ordinary **OR** gate, inverted!

These new functions of **NAND** and **NOR** are used more than the **AND** and **OR** functions because it makes other circuits easier to design using combinations of these gates.

A taste of Boolean algebra

The design of circuits using combinations of logic gates usually begins with a little mathematics, where the functions to be implemented are analysed. The mathematics used is surprisingly simple, and is a slightly changed version of ordinary algebra called *Boolean algebra*, which allows manipulation of logic functions to be made. Normal algebra has operations in it such as addition, subtraction and multiplication and division. The mathematician Boole found that the logical **AND** operation could be handled by the algebraic operation of *multiplication* (symbols × or •), and the **OR** operation by the algebraic operation of *addition* (symbol +). The **NOT** operation involved a new symbol, that of a bar over the input being inverted, such as $\overline{A}$.

So, our five basic logic operators can now be written in a mathematical form:

AND	$Q = A \times B$
OR	$Q = A + B$
NOT	$Q = \overline{A}$
NAND	$Q = \overline{A \times B}$
NOR	$Q = \overline{A + B}$.

Using logic operations in a mathematical form enables the most complex logic to be designed, simplified and converted into circuit diagram form in a very efficient and rapid way. There are more logic operators than the five we have considered here but, in general, they can all be broken down into combinations of these gates alone!

60 A resistive SWR indicator

Introduction

When a transmitter produces some output power, we want to make sure that as much as possible of this power is radiated by the aerial. This often requires the use of an *aerial tuning unit* (ATU), which matches the aerial impedance to that of the transmitter.

How do you know when this matching has been achieved? The most usual way is to use a *standing-wave ratio* (SWR) indicator. If the impedance of the aerial does not match that of the transmitter output, some of your transmitter power (also known as the *forward* power) is reflected back along the aerial feeder and back into the transmitter, where it causes excess heating. The forward and reflected waves interact along the feeder to produce a wave whose position remains constant, and which is therefore called a *standing wave* or a *stationary wave*. An SWR meter simply indicates forward power and reflected power, and adjustments are made to your ATU until the reflected power is as small as possible (ideally zero, of course). If there is no reflected power then, by a process of elimination, all your forward power is reaching the aerial!

Sampling the RF

Whatever type of SWR indicator you use, it must use some sort of sampling circuit to pick up the forward and reflected waves. The project *A standing-wave indicator for HF*, elsewhere in this book, uses a toroidal transformer to separate the readings for the forward and reverse waves. This design differs in that it measures the voltages across resistors through which the RF current is passing. Its advantages are:

(a) it uses cheap parts – four resistors, two capacitors and a diode, together with a rotary switch, a surplus meter, a preset potentiometer and two sockets;

(b) within this SWR indicator, there is always a resistive path for the RF current from the transmitter, formed by R1, R2 and R3; this can prevent damage to simpler home-made transmitters, which may be damaged during adjustment of the ATU when using more conventional SWR indicators.

The only disadvantage of this form of indicator is that it must be switched out of circuit once the ATU has been adjusted for a particular band.

Construction

The SWR indicator is very simple to build, as most of the components can be mounted on the back of the 3-way rotary switch. This is shown in **Figure 1**. The switch is a 4-pole, 3-way rotary type, of which only two poles are used.



Figure 1 Resistive SWR meter, circuit diagram

Because the other switch contacts are not being used, they can be employed as support tags for other components. The ground wires are all soldered on to the metal frame of the switch. If your switch frame is of all-plastic construction, then a 12 SWG copper wire run around the switch will make a good earth connection to the metal case for the leads shown in Figure 1. The preset potentiometer used to control the sensitivity of the circuit can be mounted directly on the meter tag.

Resistors R1, R2 and R3 handle the RF power during the tuning-up process. If you have them, use 1 watt resistors; otherwise, you can use two 100 ohm half-watt resistors in parallel for each of R1, R2 and R3. The meter, M1, can be any DC type of sensitivity around 200 µA.

In use

First, find a clear frequency, and without the indicator in circuit, check that the frequency really *is* clear by asking and identifying yourself. If it is, connect the indicator between the transmitter and the ATU which, in turn, is connected to your aerial. Turn SW1 to the SET position and key the transmitter. Adjust VR1 until the meter reads full scale. Switch off the transmitter. Turn SW1 to the REF position and key the transmitter again. Adjust the ATU until the lowest reading is obtained on the meter. Switch off the transmitter. For the chosen frequency, you have adjusted your ATU for minimum reflected power and hence the lowest SWR. You will need to repeat the process when you change bands, and possibly when you change frequency within the same band. Switching SW1 to the OUT position, you are ready to transmit. You may have noticed that it is good practice to switch the transmitter off when operating SW1. Get into that habit!

Parts list

Resistors	
R1, R2, R3	47 ohm (Ω) 1 watt (or 2 × 100 Ω, ½ watt, see text)
R4	1 kilohm (kΩ) 0.25-watt
VR1	10 kilohms (kΩ) preset
Capacitors	
C1	1 nanofarad (nF)
C2	10 nanofarads (nF)
Semiconductors	
D1	1N914 or similar
Additional items	
SW1	4-pole 3-way rotary switch, of which only 2 poles are used
M1	200 μA DC
	Case

61 An audio filter for CW

Introduction

This is a simple passive circuit (it has no power supply) that adds some audio selectivity for Morse code reception and also includes a very simple noise limiter that gives a visual indication of when noise spikes are being removed!

The circuit

Figure 1 shows the complete circuit. The tuned circuit of C1 and L1 resonates very close to 800 Hz, so initially you will have to tune a signal in carefully until it sounds loudest – you will soon be able to do this without thinking. The two LEDs connected back to back across the signal path act as a noise limiter, reducing the amplitudes of static crashes and noise from car ignition systems, etc. The LEDs blink when they conduct – this is not necessary to the operation of the circuit, but adds a little colour to your listening! The noise limiter *does* make listening more comfortable, though.



Figure 1 CW filter, circuit diagram

Construction

The circuit layout is shown in **Figure 2**. Point-to-point wiring is used, with a small tag-strip being the only item used for the extra support of C2 and R1. The LEDs and SW1 support the other components. An aluminium box (**Figure 3**) is used to make the circuit tidy and usable.


Earth
connection
D1
C2
PL to Rx
S1
Braid
J1 low Z
phones
(walkman
wired mono)
D2
L1
R1
C1
Aluminium box 11 x 6 x 2·5cm
©RSGB DY203

Figure 2 CW filter, component layout


To Rx
©RSGB DY204
LED's
IN
OUT
Phones

Figure 3 CW filter, front panel

You must use low-impedance headphones for the circuit to perform properly. Plug the completed unit into the headphone socket of your receiver and adjust the volume so that the LEDs are just *not* blinking on normal audio. The unit should be switched out of circuit for speech listening; this is the purpose of the toggle switch, SW1.

Parts list

Resistor

R1	10 ohms (Ω), 0.25 watt, 10% tolerance

Capacitors

C1	470 nanofarads (nF)
C2	100 microfarads (μF) electrolytic, 16 V WKG

Inductor

L1	82 millihenries (mH)

Semiconductors

D1, D2	LEDs

Additional items

SW1	DPDT
J1	3.5 mm jack socket
PL	Jack plug to suit receiver
	Aluminium box, approx. 11 by 6 by 2.5 cm

Source

Components are available from Maplin.

62 An electronic die

Introduction

Throwing a die is a venerable way of generating a 'random' number between 1 and 6. A die is easy to lose, so here is an electronic die-throwing circuit which brings the technique up to date and serves as another application of logic circuits. If you need a reminder of the basics of logic, refer to *Digital logic circuits*.

Warning

This circuit uses members of the integrated circuit family known as CMOS (complementary metal-oxide semiconductor). These use very little current and can be completed destroyed if they come into contact with the

magnitudes of static electricity that most of us carry about when we walk on carpets and wear rubber shoes. You will never know if this wanton destruction has happened – all you will discover is that your circuit doesn't work and that you have tested *everything*. To avoid this problem do the following things:

1. **Before you open the little packet in which the IC is supplied, touch something which you *know* to be earthed – the metalwork of any equipment which is mains-earthed, for example. Then open the packet.**
2. **Let the IC fall gently on the bench – don't pick it out with your fingers. Touch your earthed metalwork again. Pick up the IC and insert it gently into its holder.**

The circuit is safe from damage while it is connected to the battery.

Description

The circuit is shown in **Figure 1**. IC1a and IC1b form an *astable multivibrator*, similar to that used in 'An LED Flasher' also in this book. It runs constantly, and its output is fed to IC2 via a single NAND gate, IC1c. The other input of IC1c is held at 0 V by R3 and C3. Whenever one input of a NAND gate is logic 0 (or 0 V), there can be *no output* from the gate, irrespective of what is happening at other inputs. So, despite the fact that the oscillator (or *clock*) is running all the time, its square-wave output never


+ve
SW1
R1
C2
R2
IC1
pin 14
12
11
13
IC1d
1
3
2
IC1a
C1
5
4
6
IC1b
7
1
3
14
4
9
10
16
IC2
+ve
SW2
9
10
15
11
8
IC1c
6
D5
D1
D3
D7
D6
D2
D4
5 8 12 13
C3
R3
IC1
pin 7
R7
R6
R4
R5
+
9V
−
©RSGB DY205

Figure 1 Electronic dice, circuit diagram

reaches IC2 until the ‘other’ input of IC1c is brought away from logic 0. This happens when SW2 is pressed. Pressing SW2 momentarily, as is normally done, charges up C3 to 9 V, putting a logic 1 on the second input of IC1c and allowing the clock signal through to IC2. As the switch is released, C3 begins to discharge through R3, gradually lowering the voltage on pin 8 of IC1c. As this voltage crosses 4.5 V (half the supply voltage), IC1c then treats this input as logic 0, which cuts off the clock signal from IC2 again. Thus, when SW2 is momentarily pressed, the clock signal is fed to IC2 for a short interval of time, before being blocked again.

IC2 is a binary counter, and the outputs that concern us are from pins 14, 11 and 6. Pin 14 is the *most significant bit* and pin 6 the *least significant bit*. See the panel for an explanation of what happens here.

To understand these outputs, you should be able to count in binary, using three bits. At the start of the counting process, all the bits have zero values, i.e. 000. The left-most bit is called the *most significant bit*, and the right-most bit is called the *least significant bit*. (When we write numbers normally, a number 1 in the left-hand position represents one hundred, 1 in the middle column represents ten, while the number 1 in the right-hand position means one. One hundred is a more significant number than one, hence the nomenclature.)

The three bits of our binary number have values, from left to right, of 4 (=2^2), 2 (=2^1) and 1 (=2^0). This means that a number 1 in the left-hand column signifies the normal number four, in the middle column it would represent two, and in the right-hand column, it would represent one. This should help you understand the patterns of bits which emerge as the clock waveform is counted, as the next paragraph explains.

As each cycle of the clock enters IC2, it increments its internal counter and the values of that counter are shown by the states of pins 14, 11 and 6. After the first pulse, these three pins would have states corresponding to 001; after the second, 010; after the third, 011; after the fourth, 100; after the fifth, 101; after the sixth, 110. This sequence of 3-bit numbers represents a binary count from 1 to 6 in ‘normal’ parlance. These six states are used to illuminate the conventional pattern of dots on a die, using LEDs.

As the clock cycles are counted, the LEDs flicker as the die is ‘rolled’. Resistors R4 to R7 are used to limit the current through the LEDs. When the counter stops, it can be in any of the positions shown in **Table 1**. Because of

Table 1 Dice number relative to counter output

Step	*Pins*			*Dice number*
	14	*11*	*6*	
1	0	0	1	4
2	0	1	0	2
3	0	1	1	6
4	1	0	0	1
5	1	0	1	5
6	1	1	0	3

the way in which the dots are grouped on the faces of a die, the wiring of the LEDs is simpler than it might otherwise be. You can see from Figure 1 that there are really only three sets of connections to the LEDs – one from each bit of the counter output. When pin 14 is at logic 1, four LEDs are lit, corresponding to the number four. For the number five, pins 14 and 6 will be at logic 1. For the number one, only pin 6 is at logic 1. For three, pins 11 and 6 are at logic 1, for six, pins 14 and 11 are at logic 1, and for two, only pin 11 is at logic 1. These conditions are summarised in Table 1.

Construction

Two pieces of Veroboard (of the strip type) are needed – one for the main circuit (**Figure 2**) and the other for the display LEDs (**Figure 3**). The display board is easier to build, so we will do that first. It measures 20 holes by 18 strips.

Cut the tracks as shown in Figure 3, using a 3 mm (^{1}/inch) twist drill rotated between thumb and forefinger. Insert and solder the Veropins, resistors and the wire links. Then solder the LEDs in place, making sure their polarities are correct. The LEDs are mounted proud of the board (**Figure 4**, which will help when you come to fix the board into a case.

The main board measures 32 holes by 18 strips. As before, remove the tracks in the places shown in Figure 2. Note that track 'L' is *not* broken under the position for IC2. Solder in the IC holders and the links. Solder in R1 and R2 vertically, and R3 horizontally. Then solder in C1, C2 and C3; these all being electrolytics, check their polarities. Solder in the Veropins and prepare the connections to those components not on the main board, using stranded, insulated wire. Check the circuit carefully, and read the handling precautions given earlier before carefully inserting the two ICs.


To battery via SW1
+
To SW2
Component side of board
1
5
10
15
20
25
30
A
B
C
D
E
F
G
H
I
J
K
L
M
N
O
P
Q
R
R1
R2
C1
C2
IC1
IC2
R3
C3
To Pin A1 (display board)
To Pin G2 (display board)
To battery
−
To Pin R1 (display board)
To SW2
To Pin F1 (display board)
= Pin
= Link
= Cut in copper track
E10, E18, F10, F18, G10, H10, H24, I10, I18, I24
J10, J18, J24, K10, K18, K24, L18, M18, M24
N24, O18, O24
©RSGB DY208

Figure 2 Main board, component layout


1
5
10
15
20
A
B
C
D
E
F
G
H
I
J
K
L
M
N
O
P
Q
R
D1
D3
D5
D7
D6
D2
D4
R7
R6
R4
R5
= Pin
Component side of board
= Link
= Cut in copper track
B10, G12, M10, N10
©RSGB DY206

Figure 3 Board for the six LEDs



Figure 4 D7 lead bending

Testing and use

When the circuit is switched on, it is likely that the centre LED only will be lit. Press SW2, the 'throw' switch. All the LEDs should flicker, even after the switch is released, but only for a second or so. Then a standard pattern should show, signifying numbers between one and six. If this does not happen, switch off and check your circuit again. Are there any missing links? Are there any obvious dry joints (usually dull instead of shiny)? Can you see any solder bridges between tracks? Did you choose to ignore the handling precautions? If none of these results in a working circuit, try some fault-finding.

- Disconnect the lead to D7 on the main board (marked 'to pin F1' on Figure 2). Touch the lead on to the positive supply rail. D7 should light. Now transfer this lead on to pin 4 of IC1. If it flickers, then the oscillator is running (which it should).
- Transfer this lead to pin 10 of IC2. D7 should flicker when SW2 is pressed, but should be on permanently when it is released. This means that the correct signals are reaching IC2 from IC1.
- If one of the chains of LEDs (i.e. D1 and D2, D3 and D4, D5 and D6) does not light, you may have one *or both* LEDs the wrong way round.

When the die is working, you may care to experiment with the values of R1 and R2, but you should keep their values the same, i.e. R1 = R2. The larger the values of these, the more slowly the die will appear to 'roll'.

Finishing touches

On completion of the project, you will want to mount it in a smart case; any plastic box is suitable for this, with the display board mounted so that the

LEDs protrude through the top and are fixed to it using LED clips. The way in which you mount both boards to the case is entirely up to you.

Parts list

Resistors: all 0.25 watt, 10% tolerance, or better

R1, R2	5600 ohms (Ω)
R3	15 kilohms (kΩ)
R4–R7	470 ohms (Ω)

Capacitors

C1, C2	1 microfarad (μF) electrolytic, 16 V WKG
C3	68 microfarads (μF) electrolytic, 16 V WKG

Semiconductors

IC1	4011
IC2	4029
D1–D7	LEDs, any size and colour

Additional items

SW1	On-off switch SPST toggle
SW1	Push-to-make, non-latching
	Veroboard, 2 pieces, see text for sizes
	Veropins, 10
	Stranded insulated wire for general wiring
	Single-core insulated wire for links
	PP3 battery clip
	PP3 battery
	Plastic box to suit
	LED mounting clips (7)
	Means of mounting boards to box

Source

Components are available from Maplin.

63 The absorption wavemeter

Introduction

The purpose of the absorption wavemeter is to check that a transmitter is radiating within the correct waveband, and to detect any spurious *harmonic* emissions. A harmonic frequency is an integral multiple of the carrier frequency – e.g. if the carrier is at a frequency *f*, the harmonics are at frequencies 2*f*, 3*f*, 4*f* . . . and so on.

It can also be employed as a relative field-strength indicator, being used in experimentation with aerials. What it *cannot* do is to measure the transmitted frequency accurately; all it can do is to place the signal within a particular band, say the 7 MHz or the 18 MHz band (or their harmonics).

How it works

You may recognise the circuit of **Figure 1** as a crystal set with a meter replacing the headphones. It is simply the parallel combination of an inductance with a variable capacitance, which constitutes a resonant circuit with a variable frequency. A dial on the variable capacitor can be roughly calibrated with frequency. The fixed capacitor across the meter helps to improve the meter reading by making it read the peak value of the carrier wave rather than the average value.



Figure 1 Absorption wavemeter circuit

When the wavemeter is situated in the vicinity of a relatively strong radio-frequency (RF) field, the inductor absorbs a small amount of energy from that field. If the circuit is resonant at the same frequency as that of the transmitter, an RF voltage is produced across the coil and is proportional to the strength of the RF field. The RF voltage is *rectified*, or *detected* (turned from AC into DC) by the diode and the second capacitor, and is displayed by the meter.

The tuned circuit

The formula for calculating the resonant frequency of a coil and capacitor is relatively simple. It is

$$f = \frac{1}{2\pi\sqrt{LC}},$$

where f is the resonant frequency (Hz),
L is the inductance (H), and
C is the capacitance (F).

If this formula puts you off, there is this slightly easier version:

$$f = \frac{159}{\sqrt{LC}},$$

where f is the frequency in **MHz**,
L is the inductance in **microhenries** (**μH**), and
C is the capacitance in **picofarads** (**pF**).

When a variable capacitor is specified, it is usual to quote its maximum capacitance, i.e. the value when the vanes are fully meshed. When the value of the capacitor is small, it is usual to quote its minimum capacitance also, the value when the vanes are fully open. If you use a variable capacitor of 10–100 pF with a 100 μH inductor, you will use the value of 10 pF to calculate the maximum resonant frequency, and the value of 100 pF to calculate the minimum resonant frequency, giving a tuning range of 1.6 MHz to 5 MHz. Check it yourself!

64 An HF absorption wavemeter

Introduction

An absorption wavemeter is basically a simple tunable detector circuit, such as would be used in a crystal set, but with the headphones replaced by a meter, in order to indicate the strength of the received signal.

The circuit

Figure 1 shows the circuit of the wavemeter. It is designed to cover all the HF bands from 1.8 MHz to 28 MHz in four switchable ranges. There is no built-in method of amplification, so a sensitive meter is needed in order to indicate sufficiently using the available absorbed energy. The meter does not need calibrating, it serves to produce only an indication of the absorbed power, *not* its absolute value.

An absorption wavemeter does not have outstanding selectivity, mainly because of the loading effect of the meter. This problem is ameliorated here (but only slightly) by the inclusion of R1 in series with the meter. It gives



Figure 1 HF absorption wavemeter, circuit diagram

improved selectivity at the expense of a slight loss of sensitivity. The appearance of capacitor C1 across the meter is discussed in *The Absorption Wavemeter*, in the previous section.

Coils

These can be purchased (see the parts list) or hand-wound on short lengths of PVC water pipe or conduit, and the coil-winding details are given in **Table 1**. In theory, the 100 pF tuning capacitor would cover all the HF bands with only three coils, omitting the 22 μH coil. Sample calculations are explained in the previous article. However, its inclusion avoids the common problem of having some bands cramped at the extreme edges of the tuning scales.

Table 1 Close-wound coil values

L (μH)	No of turns	Span (mm)	SWG
PVC FORMER OF OUTSIDE DIAMETER 25 mm			
2.2	9	9	20
10	24	24	20
22	44	44	20
100	110	60	26
PVC FORMER OF OUTSIDE DIAMETER 20 mm			
2.2	10	10	20
2.2	9	5	26
10	32	32	20
10	24	12	26
22	63	62	20
22	41	21	26
100	134	70	26
PVC FORMER OF OUTSIDE DIAMETER 19 mm			
2.2	11	11	20
2.2	9	5	26
10	35	34	20
10	25	13	26
22	68	67	20
22	44	22	26
100	157	79	26

Construction

Hand-wound coils, using 19–25 mm PVC formers, have single-layer windings, with their ends secured by threading the wires through two small holes drilled in the formers at each end of each winding.

You may have wondered about the use of the two-pole switch SW1, as all the lower ends of the coils are grounded anyway. The answer lies in the ease of construction. Each coil can be mounted on the tags of the switch for support. If you are using the commercial coils, they are small enough to be accommodated on a miniature rotary switch; a larger rotary switch is required for hand-wound coils. The specification of a 6-way switch allows for the addition of extra frequency ranges at little extra cost. Rotary switches such as the 2-pole, 6-way variety have an adjustable end-stop which allows the number of ways to be set anywhere between 2-ways and 6-ways. Remove the nuts from the switch, and a 'washer' will fall out. It is not a washer, really, and has a little piece of metal bent over at right angles to the washer. This fits into one of 12 holes in the body of the switch, and prevents the shaft from turning through 360° and selecting the number of ways.

Calibration

This process needs a commercial amateur-bands transceiver, if it is to be done quickly and accurately.

- Connect the transceiver to a dummy load, and connect a piece of flexible wire from point A in Figure 1 and wrap two or three turns around the cable between the transceiver and the dummy load.
- Turn the transceiver power level control to minimum, and set the frequency at 1.81 MHz and the mode to FM or AM. Switch to transmit.
- With the wavemeter set to its lowest frequency range (i.e. 1.8–3.5 MHz), rotate the tuning capacitor until maximum deflection is obtained from the meter needle. Write the frequency on the inner ring of the wavemeter scale at that point.
- Switch off and retune the transmitter to 3.5 MHz. Repeat the above process.
- Repeat, using switch range 2 for 3.5, 7 and 10 MHz, range 3 for 7, 10 and 14 MHz, and range 4 for 14, 18, 21, 24 and 28 MHz.

An alternative source of calibration signal could be an HF signal generator, with a single-turn loop of wire at the remote end of its cable, and the wire from the wavemeter brought close to the loop.

Remember that the marks on the scale represent frequency *bands*, not precise frequencies.

Extending the range

If you would like to experiment with increasing the range to the lower VHF band, then 50 MHz should be achievable with an additional self-supporting coil (no former). Try three turns of 20 SWG enamelled copper wire of 25 mm ID (internal diameter). Wind it on some 25 mm PVC pipe, as before, then slide out the pipe! The same result could be achieved with four turns of 19 or 20 mm ID, or 12 turns of 7.1 mm ID.

Parts list

Resistor	
R1	2200 ohms (Ω) 0.25 watt, 10% tolerance
Capacitors	
C1	1 nanofarad (nF) min. ceramic
VC1	100 picofarad (pF) variable
Inductors	
L1	100 microhenries (μH)
L2	22 microhenries (μH)
L3	10 microhenries (μH)
L4	2.2 microhenries (μH)
Semiconductors	
D1	Germanium OA91 or 1N4148
Additional items	
SW1	Rotary 2-pole, 6-way
	Moving-coil meter, 50 or 100 μA FSD (any meter of this sensitivity will do)
	Plastic box, approx. 150 by 80 by 50 mm
	Connecting wire, coloured

65 A vertical aerial for 70 cm

Introduction

If the range of your hand-held transceiver is very limited, what you need is a vertical aerial mounted outside. This design is a half-wave dipole fed at the end instead of the middle. Because the impedance of the dipole is high at its ends (and low in the centre), a matching circuit is needed so that this high impedance can be matched to that of the low-impedance coaxial cable. All that is needed is a coil, which increases the *electrical length* of the aerial to ⅝-wavelength. (Note that the *electrical* length (i.e. the length as it appears to an RF signal) is not necessarily the same as the *actual* length.)

Construction

The aerial element and the coil are made from a single piece of 1.5 mm welding (brazing) rod, and the dimensions are given in **Figure 1**. Wind the coil around a 4 mm rod or the shank of a twist drill. The lower end is filed to a point and then soldered into the centre conductor of a 4-hole panel-mounting BNC socket. (Try to obtain a good-quality BNC socket with PTFE insulation – the insulation of cheaper sockets is easily damaged.) Trim the element to 427 mm (top of element to top of coil) *after* the wire has been soldered to the socket.

The base coil causes the aerial to be rather ‘whippy’, so a piece of 5 mm plastic knitting needle can be cut to the length of the coil and then forced into it.

The radials are made from four lengths of 3 mm welding rod. These are bent and soldered into the four mounting holes of the socket, and then cut to the lengths shown in Figure 1.

Testing

Using a standing-wave-ratio (SWR) meter connected between your aerial and the transceiver, measure the SWR (or obtain some indication of the reflected power) on transmit. If it is greater than 1.5, switch off the transmitter, trim about 3 mm off the end of the element, and try again. Repeat the process until the measured SWR (or the reflected power) is as low as you can get it.


Insert
suitable bung
to water proof
Antenna
cover tube
Slots to
accept radials
Coupler
Base tube
427mm
5 turns
163mm
(all 4 radials)
©RSGB RC327

Figure 1 Construction of the 70 cm antenna

Installation

The aerial is made waterproof by enclosing it in a 22 mm diameter PVC waste water pipe. It is 'weldable', and available at plumbers' merchants, usually by the metre. A coupler is slotted to take the radials (Figure 1). File the BNC socket as required, so that it slides inside the coupler until the radials poke out of the slots. Cut a length of plastic tubing which is 30 mm longer than the aerial, and push it into the coupler. You will then need a plastic bung or screw-top to waterproof the top end.

Plastic welding solution is now applied to the joints, sealing the aerial inside the tube. The coupler has been weakened as a result of making the slots, so it is worthwhile applying PVC tape around this joint until the welding solution sets.

A support for the aerial is made from an off-cut of tube pushed into the lower end of the coupler and held with a self-tapping screw.

Parts list

1	4-hole panel-mounting BNC socket
1 m	3 mm brazing rod (may be available from a small garage)
1 m	1.5 mm brazing rod
1 m	22 mm PVC waste water pipe
1	22 mm straight coupler
	Plastic welding solution

66 A UHF corner reflector aerial

Introduction

The corner reflector is a well-known design and is capable of good performance on the VHF and UHF bands. At UHF, the practical implementation of the corner reflector is an ideal constructional project.

Some details

Expressed quite simply, the aerial consists of a $\frac{\lambda}{2}$ dipole (where λ is the standard symbol for wavelength, making a '$\frac{\lambda}{2}$ dipole' a half-wave dipole).

Nothing new in that, you might say. However, the interesting feature is the reflector, which is not the usual single element, but a 90° metal 'corner', acting rather like a parabolic dish as used for satellite signal reception. The wind resistance of this type of reflector makes it impractical so, to reduce the 'windage' quite significantly, we make the 'corner' from closely spaced rods, as illustrated in **Figure 1**.



Figure 1 70 cm corner reflector antenna

©RSGB DY215

The reflector consists of a number of 0.6λ rods, spaced from each other by 0.1λ. The aerial frame can be made of metal or wood, but wood is easier to work with, and mounting the elements to the frame is simpler. The prototype was made with wood of 20 mm by 15 mm cross-section, as **Figure 2** shows. The wood was varnished for protection. The elements were made from 1.5 mm diameter copper wire, because a large reel of the wire happened to be available. The wire diameter is not critical; tubing could be used just as successfully. 14 SWG hard-drawn copper aerial wire would be even better than that used in the prototype.


0·5cm
17·5cm
17·5cm
1cm
Dipole driven element
41·4cm
21·2cm
Driven element
45°
45°
Driven element mount
90°
45°
2cm
4cm
3cm
6·9cm
10 holes spaced at 6·9cm
69cm
Reflector mount
©RSGB DY216

Figure 2 Driven element dimensions, together with boom dimensions for driven element and reflectors

Construction

This project is just as much a woodworking project as a radio project! Follow the instructions carefully, and you should have little trouble.

- Cut the booms for the reflectors, as shown in Figure 2. A mitre block is invaluable here in producing the 45° corners.
- Using the dimensions given on the diagram, mark the hole positions for the reflector elements, and then drill holes of a size which holds the elements firmly.
- Cut the driven element boom according to the diagram, and mark the point midway along the longer side, which will assist you later in positioning the driven element.
- Cut the back plate to size (about 120 mm by 80 mm). You may need to alter this size depending on the size of the U-bolt you will be using to clamp the aerial to the mast.

- If you want to be extra cautious in your construction, use the belt-and-braces approach, commonly known as 'screw-and-glue' to fix the booms to each other and to the back plate.
- Fix the reflector booms to the back plate first, then slide in the driven-element boom until it will go no further, then apply the wood glue and screw the two ends tightly to the reflector booms. Leave for the period prescribed by the glue manufacturers for the glue to harden.
- Varnish the whole structure.
- Cut the driven element to the correct size plus a couple of centimetres (the reason for this will be evident in the *Testing* section), and fix it to the centre of its boom (at the position you marked earlier) with a 'chocolate block' connector to which the coaxial feeder cable will eventually be connected.
- Cut and fix the reflector elements in place. If you find that these are a loose fit in the holes then, *for each element*, drill a pilot hole through the boom to intersect the hole for the element. File off the point of a woodscrew, and screw it gently into the pilot hole until it meets the element and grips it in place. You will now see why the point was filed off! Alternatively, you can glue the elements in place.

Testing

Place the aerial on a mast, clear of obstructions. Connect it to a transceiver with a length of coaxial cable, with a standing-wave-ratio (SWR) meter in circuit. Find a clear frequency, identify your transmission and ask if the frequency *really is* clear. If so, key the transmitter again and note the SWR. **Do not stand in front of any aerial when it is radiating!** The length of the driven element must be adjusted to obtain an SWR of less than 2. If you have to shorten the dipole, bend the ends over rather than cut them off. That way, if you go too far, your can lengthen them again! The dipole was initially cut too long intentionally, to allow for adjustment here! Bending the ends over also reduces the risk of physical damage to clothing, skin and eyes. You may like to consider applying the same technique to the reflector elements for that reason alone.

Moving on . . .

Once you have warmed to the idea of the corner reflector as an aerial, you might like to ring the changes regarding the reflector. How about replacing the 20 reflector elements with a wire mesh, such as garden centres sell as 'chicken wire'? Choose the finest mesh if there is a choice. Some extra support may be needed around the edges of the mesh, but you could go on to make a comparison of aerial gain between the two types, using the *UHF Field Strength Meter* described elsewhere in this book.

Materials

Stiff wire or thin-walled tubing for dipole and reflector
Frame – wood, 15 mm by 20 mm cross-section, lengths given in text
Back plate – stout plywood, dimensions given in text
U-bolt to suit mast
Wood screws
Wood glue
50 W coaxial cable for feeder
2-terminal ‘chocolate block’ for dipole connection to feeder
Varnish

67 A switched dummy load

Introduction

A dummy load is a pure resistor of value 50 ohms which can replace your transmitting aerial and enable you to operate the transmitter for test purposes without radiating a signal. It sounds simple enough, but there are two main problems. Firstly, it is impossible to delve into your junk box and emerge with a resistor that will dissipate 100 W PEP and still retain its marked resistance value. Secondly, a ‘pure resistance’ is very difficult to achieve. A pure resistance is a device which has resistance but no reactance. All common resistors have significant reactance at radio frequencies, particularly the wire-wound varieties, which have a helical (i.e. wound like a coil) construction. This is particularly annoying, because wire-wound construction is normally used for large-wattage resistors.

Although all resistors have *some* reactance, not all are quite as bad as the wire-wound type. Carbon film resistors are made by depositing a thin film of carbon on the surface of a small, hollow ceramic cylinder, the thickness of the film of carbon determining the value of the resistor. Provided the lead lengths are kept short, these resistors have a tolerably small reactance, and will be used in this project.

Bearing the load

A 2 W carbon film resistor is hardly going to withstand our 100 W PEP of SSB, so it is obvious that the design of our dummy load must be a little more complex than a single resistor and a switch, despite what **Figure 1** might suggest! In fact, it uses 20 resistors, each of value 1000 Ω (1 kΩ). How does this solve our problem?

Perhaps a little theory is in order here, but no more than is required by the Radio Amateurs' Examination.

When two *equal* resistors of value *r* are combined in parallel (i.e. side by side), the total resistance, R_T, is given by:

$$\frac{1}{R_T} = \frac{1}{r} + \frac{1}{r}.$$

Adding 1/*r* to 1/*r* gives 2/*r*, therefore:

$$\frac{1}{R_T} = \frac{2}{r}, \quad \text{i.e. } R_T = r/2.$$

So, by connecting *two* equal resistors in parallel, we get a combined resistance which is *half* the individual resistances. If we combine *three* in parallel, we get a *third* of the resistance, and so on.

Here, we are connecting *20* resistors of 1 kΩ in parallel, so we will produce an overall resistance of *one-twentieth* of the individual resistance, i.e. 1000/20 = 50 Ω, which is what we set out to achieve!



Figure 1 Basic circuit diagram

This is not the only advantage, though. Each resistor is capable of dissipating 2 W, so 20 of them will safely dissipate 40 W, for short periods at least. This power dissipation is approximately the same as 100 W PEP of normal speech, so the design should be capable of use in an 'average' amateur station. The power-handling ability of any dummy load can be improved by providing a 'heat sink' which helps to conduct the heat energy away from the resistors, thus lowering their temperature. One popular heat sink is a can of transformer oil, into which the resistors are immersed. This design uses a rather more mundane heat sink, but which is adequate for the job in hand.

Figure 2 PCB resistor supports


10mm
©RSGB DY213
22mm

2 PCBs (single sided) 100 x 35mm, 20 holes
1 'earth' PCB with two 3mm holes


120 x 95 x 53mm
die cast aluminium box
To transmitter
To
antenna
S1
(10A - 2 way)
COM
PCB
A
A
'Earth' PCB
Bolt 'earth' PCB
to side of box
2mm gap
between
resistors
18swg aluminium
20 x 130mm
bent up each end
with two 3mm holes
Heat sink
compound
Twenty 1k 2W
resistors
Two 5 x 20 x 100mm
ceramic wall tile
Section A-A
©RSGB DY214

Figure 3 Switched dummy load, component layout

Pouring the heat away

Two basic PCBs are needed, the details being given in **Figure 2**. Both measure 11 × 35 mm. Each has a set of 20 holes of diameter about 1 mm to take the ends of the resistors. Only one of them has two 3 mm holes which are used for mounting the completed load. **Figure 3** shows how the heat sink is assembled. Solder one end of each resistor into the 'earth' PCB, and then mount this to the box using the two bolts as shown in the diagram. Between each rank of resistors is a 'sandwich' consisting of an aluminium strip and two pieces of ceramic wall tile, to act as a heat sink for the resistors. Heat sink compound is used to provide good thermal contact between the resistors and the tiles, and between the tiles and the aluminium strip. This is shown in the lower part of Figure 3. Thread the loose wires of the resistors through the holes in the second PCB, solder into place, and crop the protruding wires.

Switching

A changeover switch must be used so that the transceiver can be switched between the dummy load and the aerial without unscrewing connectors. For most purposes, an ordinary 10 A 230 V changeover switch will suffice, as found in many electrical shops and DIY stores.

Wire this into the circuit as shown in Figure 1 and Figure 3. Check your wiring. Put S1 in the 'dummy load' position. If you have a multimeter which includes an ohmmeter, measure the resistance across the socket, J1, before connecting it to the transceiver. It should be very near 50 Ω. With S1 in the 'aerial' position, there should be an infinite resistance across J1. Move your ohmmeter to read the resistance across J2. It should be infinite for both positions of S1. If all seems correct, close the box and your dummy load is ready for use!

Parts list

Resistors
  1000 Ω (1 kΩ) 2 W carbon film, 20 required
Additional items
  10 A 230 V changeover (SPDT) switch
  SO–239 sockets, 2 required
  Aluminium box 120 × 95 × 53 mm or similar
  Ceramic wall tile cut as required
  Aluminium strip, 18 SWG
  Nuts and bolts as required

68 A simple Morse oscillator

Introduction

This is an excellent project which uses the 'junk box' as its source of components. If you have trouble in finding the bits for this one, a good source of the components for this and many other similar projects is to be found with the parts list at the end of the project.

The circuit

This is shown in **Figure 1**, and uses an 'unknown' Plessey chip, which makes the overall circuit extremely easy to build. A 0.1 µF capacitor is connected between pins 7 and 8, a speaker (in the popular 8 to 25 Ω impedance range) is connected between pins 8 and 9. If a 9 V battery is connected with its positive terminal to pin 8 and its negative terminal to pin 1, 3 or 5, a tone will be produced in the speaker.

To make this circuit into a good Morse practice oscillator, it is necessary only to insert a Morse key into the supply rail from the battery.

However, there is another refinement which you may care to build into the circuit. The tone from the loudspeaker is different, depending upon which of pins 1, 3 or 5 you use. In the prototype, a single-pole changeover switch was used to select the tones from pin 1 or pin 3, and the Morse key would be connected to the circuit via a small jack socket. There is no need for an on/off switch, as the Morse key performs that function. The switch and the jack socket can be seen in the photograph.



Figure 1 Morse oscillator, circuit diagram

The case

Almost any small loudspeaker will do; the higher the impedance the better. The ‘impedance’ is the figure usually printed on the rear of the speaker magnet. It is a value given in ohms (Ω). For simple circuits like this, you will usually find that the higher the impedance (within reason), the louder the sound it will produce. Speakers from old transistor radios will work, although their impedances can be rather low sometimes.

Any case big enough to house the components and the battery will be suitable. The prototype used a ‘Walkman’-type speaker and case, and is shown in the photograph.

To use the circuit, simply attach a 3.5 mm jack plug to your Morse key, and insert it into the socket. Nothing should happen until you press the key, when a tone should be heard from the loudspeaker.

Another application

Try soldering the two wires of a ‘twisted pair’ to the 3.5 mm jack plug. Touching the wires together produces a tone from the speaker. This simple circuit can then be used as a ‘continuity tester’. Touch the two wires to the ends of a fuse. If there is no sound, then the fuse is blown. There are many other such tests you could perform with this device – to check whether there really *is* a connection between one end of a wire and the other, for example.



Warning

You must **never** make such tests on any equipment which is connected to the mains supply, even if it is switched off. If you want to make any such tests, make sure you are supervised by someone who understands what you are doing and is competent to advise and supervise you.

Parts list

Plessey oscillator chip
0.1 μF capacitor (disc ceramic)
Loudspeaker 8 to 25 Ω
3.5 mm jack socket (and 3.5 mm jack plug if needed)
Single-pole changeover switch

The Plessey oscillator chip is available from J. Birkett, 25 The Strait, Lincoln LN2 1JF, tel: 01522 520 767.

John Birkett may also provide a kit of parts (the chip, capacitor and loudspeaker).

69 A bipolar transistor tester

Introduction

This is a circuit which will test normal transistors, i.e. npn or pnp. It has the advantage of being able to test devices while they are still connected in their original circuits. However, when such tests are made, **the circuit containing the transistor under test must not be switched on**.

The circuit and how it works

The circuit runs from a 9 V battery such as a PP3 or six AA-type 1.5 V cells. Alkaline cells are to be preferred, as their electrolyte leakage properties are better. The circuit shown in **Figure 1** uses a single CMOS integrated circuit type 4001 or 4011. CMOS circuits require special handling precautions which are described in the project *Christmas Tree LEDs*, elsewhere in this book.


+9V
S1
IC1 pin 14
Ⓐ Used in text
Ⓑ to explain operation
R5 100R
D1 - D4 1N4148
C1 1µ
R1 5k6
R2 5k6
Ⓐ
D1
D3
R4 100R
D2
D4
Ⓑ
R3 100R
8
9
10
IC1a
C2 1µ
13
12
11
IC1b
1
2
3
IC1c
5
6
4
IC1d
D5
D6
IC1 pin 7
0V
Base
Collector
Emitter
©RSGB DY229

Figure 1 Transistor tester, circuit diagram

Inside the IC are four logic gates (see *Digital Logic Circuits*) which are all connected as inverters, which means that the output signal is always the logical ‘opposite’ of the input. The first two gates are connected as an oscillator; the circuit being the same as that used in *An Electronic Die*.

The output of the oscillator, at pin 11, is connected to the input of a buffer stage, IC1c, which helps to isolate the oscillator from the circuit that follows it. The buffer output appears on pin 3, which we shall label as *test point A* for future use. Another inverter, IC1d, follows this, its output at pin 4 being labelled *test point B*.

There are two LEDs connected back to back at the circuit output. These are D5 and D6, D5 being red and D6 being green. Whatever the output of the oscillator at any instant, one of the LEDs must be lit and the other unlit. With point A positive and point B zero, the red LED is lit, when A is zero and B is positive, the green LED is lit. Because the oscillator output is repeatedly switching from one polarity to the other, the lit LED is alternately red and green. They switch between the two colours much faster than we can see, so what we think we see are both LEDs lit together.

The two 100 ohm resistors, R3 and R4, provide the bias to the base of the transistor under test. When A is positive and B is zero, the base-emitter junction of the transistor will be forward-biased, and the transistor will switch on (if it is a working npn type). When the transistor is on, it effectively short-circuits D5 (the red LED) and it extinguishes. When point A is zero and B is positive, an npn transistor will be switched off and the green LED (D6) will light. Thus, for a working npn transistor, only the green LED is lit.

If the transistor under test is a pnp type, it will switch on when A is zero and B positive, thus short-circuiting the red LED (D6). When A is positive and B zero, the transistor is off and the red LED (D5) is lit. Thus for a working pnp transistor, only the red LED is lit.

To summarise, the states of the LEDs indicate the following conditions:

- Both LEDs apparently lit: no transistor connected, or transistor permanently open circuit.
- Neither LED lit: a collector-emitter short-circuit is almost certain.
- Red LED alone: pnp transistor in working order.
- Green LED alone: npn transistor in working order.

Construction

The prototype tester was built on a piece of Veroboard measuring 15 strips by 18 holes. Cut the tracks using a track-cutting tool or a 3 mm (⅛ inch) twist drill, as shown in **Figure 2**. Notice that, in this diagram, there is no


+ve
1
5
10
15
20
A
B
C
D
E
F
G
H
J
K
L
M
N
P
Q
R
Emitter probe and LEDs
−ve
Base probe
Collector probe
R2
C2
C1
R1
R3
R4
R5
D4
D2
D1
D3
Diodes
= Pin
= Link
= Cut in copper track C10, D10, E10, F10, G10, H10, J10, Q7
©RSGB DY230

Figure 2 Transistor tester, component layout

track ‘I’, so try to avoid miscounting when you translate diagram positions to real positions on the board. Hold the board up to a strong light to ensure that there is no copper swarf shorting adjacent tracks together, and that you have made the cuts in the correct places.

Having done this, insert and solder Veropins for all the connections to be made to components not on the board itself. Then solder in the IC holder and the wire links. Then insert the other components in the order resistors, capacitors and diodes D1–D4. Some resistors are mounted vertically so that their connections are on adjacent tracks. Double check the diode polarities – it is easy to make a mistake when wiring diodes in anti-parallel! Next, connect up the off–board components, again making sure that the LEDs have the correct polarity. The probe leads for the emitter, base and collector should be made from different colours of wire and terminated in probe clips (small insulated crocodile clips).

Check carefully for dry joints and errant blobs of solder. Plug the IC into its holder, ensuring that it is inserted the right way round, as shown in Figure 2.

Testing

Without a transistor in circuit, and the battery connected, both LEDs should be lit. Connect a known good npn transistor and verify that the green LED lights. Now simulate two transistor faults: disconnect the base lead and both LEDs should light; remove the transistor and connect the emitter and collector leads together. Neither LED should light.

Repeat the tests with a known good pnp transistor. The results should be the same, except that the correct indication should now be a lit red LED. On your computer, make a small label of the bulleted list above, to fit on your tester showing the states of the LEDs and what they mean. It will act as a useful *aide mémoire* when you use the tester in future.

Using

The circuit will test transistors in isolation or in an existing circuit, i.e. prior to use. You can check the lead identifications in component catalogues such as the Maplin catalogue. The tester is ideal for going through the large bags of unmarked transistors that you can buy for a song at rallies. You can sort them into three piles – npn, pnp and dud!

Parts list

Resistors: all 0.25 watt, 10% tolerance or better

R1, R2	5600 ohms (Ω)
R3, R4, R5	100 ohms (Ω)

Capacitors

C1, C2	1 microfarad (μF) electrolytic, 16 V WKG

Semiconductors

D1–D4	1N4148 general-purpose silicon diodes
D5	Red LED
D6	Green LED

Integrated circuit

IC1	CMOS 4001 or 4011

Additional items
- Veroboard, 15 strips by 18 holes
- Veropins
- PP3 battery and connector (or 6 × AA cells in PP3 clip holder)
- Switch, SPST
- Connecting wire
- One each of known working npn and pnp transistors for test purposes.

Source

Components are available from Maplin.

70 The ‘Yearling’ 20 m receiver

Introduction

Published to celebrate the first anniversary of *D-i-Y Radio*, this excellent receiver design forms a suitable ‘second receiver project’ for those who have successfully completed the MW receivers earlier in this series. The receiver is powered from a PP3 battery or from a mains adaptor, and can be built with the help of an experienced constructor, on a prototype board. The circuit diagram and some of the components used are shown in the separate diagram. Headphones or a loudspeaker can be used and, once the radio is completed, a few simple adjustments will make the *Yearling* spring to life!

Building the receiver

Before starting the constructional process, start by identifying all the parts. One by one, tick them off against the parts list. Are their values correct? The varactor diode is a twin type (see circuit diagram overleaf), and must be cut *carefully* down the middle, producing two devices, D1 and D2, with two wires each.

First, solder the IC sockets, followed by the coils (inductors); L1 is pink inside the top, and L2 is yellow inside. Then, solder in the varactors; the lettering on D1 should be next to coil L1, and the lettering on D2 should face resistor R7. After those, the capacitors, wire links and resistors should be soldered to the board. Take care to wire the voltage regulator, IC3, correctly. Solder in the crystal X1 as quickly and deftly as you can – crystals do *not* take kindly to having their leads bent and being fried with a soldering iron! Make sure that the electrolytic capacitors C2, C12, C15 and C16 are fitted the right way round. Most electrolytic capacitors have only the negative lead marked.

Figure 1 shows the rear of the front panel, illustrating the connections from the board and antenna socket to the controls. All normal connecting wires are 22 SWG or thereabouts, with insulation. Their lengths should be about 15 cm, except for the battery lead to the switch, which is about 8 cm. It is recommended that you use different-coloured wire for each connection to a control. **Figure 2** shows this. The variable resistor section of VR5, the AF gain control, uses single screened cable connected to 0 V (ground) at the

Amateur Radio

D-i-Y

RSGB

Year



Antenna Socket

Variable Inductor



Crystal


C2
10µ
C6
100n
+5V
stab
IC3
78L
8
L1
1
4
2
6
3
C1
180p
RV1
1k0
lin
D1
½ KV1236
IC1
NE602
1
2
4
5
3
6
7
C5
180
P
L2
IC2
NE602
R3
1k5
R4
1k5
C3
47p
C4
100p
X1
Earth
X1.....
Crystal – between
8·8 and 9·0MHz
C10
330p
L3
10µH
C9
220p
C11
10n
R1
100k
+5V
stab
RV3
1k0
lin
RV4
47k
lin
R9
100k
RV2
47k
lin
C7
100n
R2
10k
C8
100n
D2
½ KV1236
INTEGRATED CIRCUITS
IC1, 2, 4 and 5
8 7 6 5
1 2 3 4
Top view of pins

Resistor



Varicap Diode

Most radio amateurs enjoy building par
is Do-it-Yourself (D-i-Y) Radio, and it is
successfully built yourself. License
allowed (by the Government) to use ho
can see how radio components are dra
circuit diagram for the

D-i-Y Radio, RSGB, Lambda House, Cra

– Do It Yourself

RADIO

rling


Polyester Capacitor

Electrolytic Capacitor


05
R5
100k
IC4a
TL072
2
3
1
8
R6
12k
R8
12k
C13
47n
+9V
C15
100μ
16V
S1
9V
PP3
External
DC power
connector
IC4b
TL072
5
6
7
4
C16
1μ0
16V
+9V
R7
220R
C14
10n
RV5
10k
log
IC5
TDA7052
1
2
3
5
6
8
To
Speaker
C12
100μ
16V
Earth
COILS
L1 and L2
4
1
2
6
3
Base view
VARICAP DIODES
Cut here
D1
367
112
367
112
D2
0V
R9
L1
C1
Lettering side
IC3
78L05
+5V
0V
+9V
Base view of pins
EXTERNAL DC CONNECTOR
To S1
To
PCB
PP3
9V
Rear view


AF Gain Control

of their radio stations themselves, this
very satisfying to use a radio you have
d radio amateurs are the only people
me-built transmitters. On this page you
wn on a circuit diagram. This is the full
e *D-i-Y Radio* Yearling.

Fixed Inductor


Integrated Circuit

nborne Road, Potters Bar, Herts. EN6 3JE


VR3
To RV4
To PCB
(+5V stab)
VR2
To PCB
(+5V stable)
To PCB
(0V)
To PCB
(C7)
9V DC
to PCB
To DC power
connector
VR5/SW1
Cable
screen
To PCB
(RV5 ground)
To PCB
(RV5 middle)
To PCB
(C16)
VR4
To RV3
To PCB
(R2)
To PCB
(R9)
VR1
To earth
socket
To PCB
(0V)
To PCB
(L1)
To antenna
socket

©RSGB DY233

Figure 1 Rear view of the variable resistors. Check the connections carefully to make sure the wires fit the correct holes


Red
Green
Yellow

©RSGB DY234

Figure 2 It is helpful to use different colour insulated connecting wires. Wires between each variable resistor and the board should be twisted together to give a neat wiring outfit.

board end. Now fit the ICs into their sockets. Make sure that they are the right way round (see circuit diagram) and that each pin lies directly above its corresponding socket before applying *gentle* pressure with the back of the board firmly supported.

Check that all the connections are correct (don't *assume* this – check the ends of each wire against the circuit diagram) and that all your soldered joints are shiny. Lastly, drill the five 10.5 mm diameter holes for the main controls. On the side of the case, a 6.3 mm diameter hole is needed for the speaker socket, and 8 mm holes for the antenna and earth sockets. The external power socket requires an 11 mm diameter hole.

Adjusting it

Before you can make adjustments, and in order to hear *anything* on your *Yearling*, you will need to connect an antenna (aerial) to the antenna socket. About 8 metres of wire, preferably outdoors and as high as possible, is all you need to connect to the socket. Connect the 3.5 mm jack socket for the speaker, and a 3.5 mm jack to your speaker leads. Connect a battery and switch on.

1. Using a very small screwdriver or, better still, a non-metallic 'trimming tool', *gently* screw in the core of L2 as far as it will go, but *don't force it*. Then unscrew it by three turns anticlockwise.
2. Set VR1, VR2 and VR4 to mid-position and rotate the core of L1 anticlockwise until the hissing noise you hear reaches a maximum intensity. Then adjust L2 for maximum noise.
3. If you now tune carefully with the main tuning control, VR4, you should hear some amateur Single-Sideband (SSB) speech signals. You may have to adjust the bandspread (fine tuning) control, VR3, to make the speech sound normal.
4. Having verified that everything is working, switch off and mount the controls on the front panel and the sockets on the side. To do this, it is much safer to disconnect all the controls and sockets, mount them in their final positions, and then wire them up again.
5. Fit the front panel knobs, connect your aerial and switch on again, checking that everything is working. Then, locate the cluster of CW (Morse) signals to be found at the bottom of the 20 metre band, set the bandspread control to mid-position and slacken off the main tuning knob. Turn the knob (but *not* the control!) until the pointer lies a little clockwise of 14.0 MHz. The SSB signals should now lie roughly between the dial centre and 14.35 MHz. Tighten up the knob.
6. Finally, fix the board to the rear panel, and secure the battery (if you are using one). Attach the rear panel to the back of the box, and you are finished!

Listening!

Make a habit of keeping the bandspread control in its centre position when searching for stations; then you can adjust it either way to make the signals readable. Unless you have a very big aerial, it is best to have the 'RF Gain' control, VR1, at maximum. Use the 'Antenna Tune' control, VR2, to give the best signal, and control the volume with the 'OFF/AF Gain' control. You will find some excellent DX stations with your *Yearling* receiver, and it will serve you well.

Parts list

Resistors (all 0.25 W, 5%)

R1, R5, R9	100 kilohms (kΩ)
R2	10 kilohms (kΩ)
R3, R4	1.5 kilohms (kΩ)
R6, R8	12 kilohms (kΩ)
R7	200 ohms (Ω)

Capacitors (all rated at 16 V or more, tolerance *at least* what is quoted)

C1, C5	180 picofarads (pF) polystyrene 5%
C2	10 microfarads (μF) electrolytic
C3	47 picofarads (pF) polystyrene 5%
C4	100 picofarads (pF) polystyrene 5%
C6, C7, C8	100 nanofarads (nF) or 0.1 microfarad (μF) ceramic
C9	220 picofarads (pF) polystyrene 2%
C10	330 picofarads (pF) polystyrene 2%
C11, C14	10 nanofarads (nF) or 0.01 microfarad (μF) ceramic
C12, C15	100 microfarads (μF) electrolytic
C13	47 nanofarads (nF) or 0.047 microfarad (μF) polyester, 5%
C16	1 microfarad (μF) electrolytic

Variable resistors

VR1, VR3	1 kilohm (kΩ) linear
VR2, VR4	47 kilohms (kΩ) linear
VR5	10 kilohms (kΩ) log with switch

Inductors

L1	Toko KANK3335R
L2	Toko KANK3334R
L3	10 microhenries (μH), 5%

Semiconductors	
IC1, IC2	Philips/Signetics NE602 or NE602A
IC3	78L05 5 V 100 mA regulator
IC4	TL072 Dual Op-Amp
IC5	Philips TDA7052 audio amplifier
Additional items	
D1, D2	Varactor diode Toko KV1236 (cut into two sections – see text)
X1	Crystal 8.86 MHz type (from Maplin, etc.)
4 off	8-pin DIL sockets for IC1, IC2, IC4 and IC5
2 off	4 mm sockets aerial (red) and earth (black)
1 off	3.5 mm chassis-mounting speaker jack socket
1 off	DC power socket for external supply (if required)
4 off	Red knobs with pointers
1 off	Tuning knob with pointer (e.g. 37 mm PK3 type)
1 off	Printed-circuit board or prototype board
1 off	Plastic case approx 170 × 110 × 6 mm (e.g. Tandy number 270-224)
1 off	Speaker 8–32 Ω impedance (or headphones)

71 Adding the 80 metre band to the Yearling receiver

Background

You will have noticed that your *Yearling* receiver has a dial which shows coverage of the 80-metre amateur band (3.5–3.8 MHz). This band is used for local contacts during the day, and contacts up to about 1600 miles in darkness. Longer distances are possible, particularly in the middle of winter.

The modifications

Only a few extra parts are required, as you may have noticed from the parts list. A low-pass filter, FL1 (one which passes low frequencies and rejects higher frequencies), is switched into the circuit on 80 m. The circuit of the


Antenna
To PCB 'a'
To PCB 'b'
To PCB 'c'
VR1
RF
gain
control
Cx
100p
S1 switch
Cy
100p
Solder wire
links as shown
To
earth
socket on
case
To PCB 'd'
FL1 filter
©RSGB DY235

Figure 1 The circuit diagram shows the extra components for 80 m operation. Note the connections to the PCB 'a', 'b', 'c' and 'd'


a
b
Cut track
here
c
d
©RSGB DY236

Figure 2 The underside of the PCB. Wires are connected from the switch and filter as shown

switch and its connections is shown in **Figure 1**. Before making the modifications, dismantle the receiver so that you have easy (and safe) access to the case and the track side of the PCB.

1. The first thing to do is to drill a 6.5 mm diameter hole in the side of the case into which the switch fits.
2. Then, using a sharp Stanley knife or scalpel, carefully cut the track on the PCB as shown in **Figure 2**, making a gap about 1 mm wide.
3. Using 10 cm lengths of different-coloured insulated wire, make the four connections, a, b, c and d, to the PCB, as shown in Figure 2.
4. Solder the two links on the filter, and then make the connections to the switch, capacitors and PCB. You will have to disconnect the existing wire between the RF gain control, VR1, and pin 4 of L1 on the PCB.
5. Lastly, check your new connections carefully, then mount the switch in the new hole and fix the filter to the bottom of the case with a little glue, as shown in **Figure 3**. Reassemble the circuit, and replace the back of the case.

More testing!

Firstly, switch your new switch, S1, into the 20 m position, to check that the original circuit still works! If you find that the ‘Antenna Tune’ control peaks at a slightly different position, don’t worry.



Figure 3 Internal view of the Yearling case. The filter FL1 is attached to the base with glue

Now switch to 80 m, and tune around the anticlockwise end of the dial; you should hear some SSB stations, particularly in the evenings and at weekends, when may people are on the air. At the other end of the travel of the tuning control, you should hear CW (Morse) stations.

The Radio Society of Great Britain broadcasts amateur radio news every Sunday morning on or about 3.65 MHz; the table below has the details. Finally, a good antenna is more important than ever for 80 metre reception – aim for more height and length, and then consider the project concerned with making an Antenna Tuning Unit (ATU)!

Parts list

Capacitors (all rated at 16 V or more, tolerance 10% or better)

Cx, Cy	100 picofarads (pF) polystyrene

Filter

FL1	Toko 237LVS1110 low-pass filter

Additional items

SW1	2-pole 2-way (changeover) toggle switch
7 off	Short lengths of insulated wire of different colours

The RSGB news broadcasts, GB2RS – Sunday mornings

Frequency (MHz)	*Local time*	*Reception area*
3.650	0900	SE England
3.650	0930	Midlands
3.650	1000	SW England
3.650	1100	Yorkshire
3.640	1130	Aberdeen
3.660	1130	Glasgow

The Midlands transmission is repeated at 1800 (6pm) local time on 3.650 MHz. All frequencies are approximate in order to avoid interference, and use lower sideband (LSB). If you also have a 40 metre receiver, there are GB2RS news broadcasts on 7.048 MHz at 0900 local time from Northern Ireland and from 1100 local time from the north midlands.

72 How the Yearling works

Introduction

The *Yearling* was designed to provide an introduction to *Amateur Radio* on the 20 m amateur band. Let's look at how the different sections (or 'stages') of a radio work, and how they fit together to form a complete receiver. **Figure 1** shows a block diagram which you can follow and compare with the circuit diagram of your *Yearling* receiver.

The antenna (or aerial)

Connected to your receiver, it will pick up not only amateur signals, but all other signals as well! This means that the receiver has to select the one signal that interests you, while rejecting all the others. The following stages do just that.

The RF filter

This stage (centred around L1) selects the band of radio frequencies (RF) containing the signal you want, in this case, those having wavelengths around 20 m. Signals from the 40 m band, for example, would not get through.

The crystal oscillator

This is an oscillator circuit designed around a quartz crystal (X1), and has a very stable frequency. It produces a single, very pure frequency to feed into the mixer. A crystal having a frequency between 8.800 MHz and 9.000 MHz is suitable for this circuit. The oscillator and mixer functions are both carried out inside IC1.

The first mixer

Yes, this stage 'mixes' two signals together. In this case, the two signals are (i) from the aerial via the RF Filter, and (ii) from the crystal oscillator. Two



Figure 1 Block diagram of the Yearling, showing how the various stages fit together to make a complete radio receiver

bands of signals emerge from the mixer. The first is centred upon a frequency equal to the incoming signal frequency **added** to the crystal frequency, and the second is centred upon a frequency equal to the incoming signal frequency **subtracted** from the crystal frequency. Look at an example – if the signal is at 14 MHz and the oscillator at 9 MHz, then the mixer outputs will be 14 + 9 = 23 MHz and 14 – 9 = 5 MHz.

Intermediate frequency (IF) filter

It is the purpose of the IF filter (centred around L2) to select only one of these two bands of frequencies emerging from the mixer. In this case, it is the lower band of frequencies (around 5 MHz) which we select. This is because, in general, lower frequencies are easier to handle than higher ones.

Variable-frequency oscillator (VFO)

The VFO (part of IC2) enables us to tune into a particular station, and operates over a band of frequencies between 5 MHz and 5.35 MHz in this receiver. You will notice that IC1 and IC2 are the same type of chip, so that you will be expecting another mixer stage to be associated with the VFO. You are quite right!

The second mixer

This mixer obeys exactly the same rules as those of mixer 1. Sum and difference frequencies are produced, like this. Mixing is between the incoming IF signals (around 5 MHz) and the VFO signals (around 5 MHz), producing output frequency bands centred upon 10 MHz and 0 MHz. The use of the words ‘band of frequencies’ throughout this explanation is intentional. If all the signals were pure, there would be no bands; the bands are produced because of one thing – the modulation imposed on the pure frequencies at the transmitter. So, the 'bands' contain the one thing that we want to extract from the signal, and that is the speech or Morse code that the signal contains. The band of frequencies at 0 MHz is just that – the audio frequencies we want in the loudspeaker. Because of this, the audio frequency output of the second mixer is selected and passed on for amplification.

The audio preamplifier

Preliminary amplification of the minute audio signal which emerges from the second mixer is provided by IC4a, which will respond only to audio signals, automatically rejecting the 10 MHz signal.

The audio filter

The bandwidth of normal speech when transmitted by an amateur station is around 3 kHz, so there is no advantage to be gained in amplifying frequencies greater than this. IC4b is known as a low-pass filter, because it passes (lets through) lower frequencies and rejects higher ones.

The power amplifier

IC5 produces the final audio amplification and provides enough power (about 350 milliwatts (mW) to drive a small speaker.

How does it work on 80 m?

If you have fitted the 80 m modification to your receiver, you are probably wondering how the circuit works at this different frequency. Firstly, the filter which you fitted selects the 80 m band instead of the 20 m band. The only other slight difference lies in the way the first mixer stage works. Its job is to produce sum and difference frequencies from the incoming signal and crystal frequencies. On 20 m, it did this by subtracting the crystal frequency (9 MHz) from the incoming frequency (14 MHz) to produce an IF output of 5 MHz. On 80 m, the incoming frequency (3.5 MHz) is subtracted from the crystal frequency (9 MHz) to produce an IF output of 5.5 MHz, which is still within the tuning range of the VFO in the next stage.

73 A field strength meter

Introduction

Having a reliable field strength meter is always useful. There are two basic types – the tuned variety (also known as an absorption wavemeter) and the broad-band variety. A project centred on the tuned variety can be found in this book (*An HF absorption wavemeter*), and the way it works is also presented (*The absorption wavemeter*). This project describes an untuned or broad-band type which is every bit as useful as the tuned type, when it is the level of RF in which you are principally interested.

With the possible exception of the meter, you may have all the parts needed in your junk box. The prototype was distinguished by its meter, found at a rally, and marked 'Safe', 'Dangerous' and 'Explosive' on its scale.

How it works

The basic field strength meter uses the circuit of a crystal set, but with a meter replacing the headphones. A better design, which is used here, is that of a voltage doubler, giving more sensitivity. **Figure 1** illustrates the voltage doubler circuit.

The AC input shown will be our RF input, which will be explained soon. Diode D1 will pass the positive half of the signal and use it to charge up C1 to the peak value of the signal. D2 uses the negative half of the signal to charge up C2 to the same value. Because C1 and C2 are in series, the peak voltage appearing across *both* of them (which is the DC output voltage) is equal to *twice* the peak input voltage, hence the name voltage doubler. If you're wondering why DC is present at the output when AC comes in at the



Figure 1 Voltage doubler circuit

input, remember that capacitors pass AC (RF) but block DC; thus the RF is shorted out through C1 and C2, but the steady voltage (DC) remains across the two capacitors. The voltage is thus proportional to the size of the RF signal applied at the input.

The circuit

The voltage doubler is converted into a field strength meter using the circuit of **Figure 2**. A piece of wire serves as the aerial to provide an RF signal across the radio-frequency choke (RFC). A choke is an inductor which is large enough to prevent the RF passing through it – it 'chokes' the RF. This produces the maximum RF signal at the input to the voltage doubler, and the DC output from it is measured on the meter.



©RSGB DY227

Figure 2 Field strength meter

The parts used are not very critical. The RF choke can have any value between about 1 mH and 2.5 mH. Almost any common diode such as the 1N914 or 1N4148 can be used for D1 and D2. The two capacitors could be any value between 1 nF and 100 nF (0.001 µF and 0.1 µF). The meter should be reasonably sensitive, with a full-scale deflection (FSD) in the range 50 µA to 100 µA. Look for VU meters at rallies – these are ideal.

Construction

The prototype circuit was made on matrix board. If you don't want to use pins with the board, simply push the component leads through the holes and make the connections on the underside of the board, either with the excess component leads themselves, or with ordinary connecting wire.



Figure 3 Board layout and interconnections

Component side of board shown.
All connections are under board

Figure 3 shows how the parts are placed and connected. The matrix board can be mounted directly on the meter using its terminal bolts!

In use

Needing no power supply other than an RF signal, just connect it all up and leave it to work! A short length of insulated wire is enough to pick up some RF and display it on the meter. Using a 200 μA meter, about 3 metres of wire gave a good deflection on the meter. To increase deflection, the wire can be wrapped around the aerial lead, provided that the wire is PVC covered and doesn't come into contact with the aerial wire.

This requires a little experimentation. Try a long piece of wire first and adjust its position until the meter needle kicks whenever there is a transmission. It is very reassuring to see the meter moving during a transmission. Although SWR meters also indicate power, they are usually set to read reverse power, and show little or no movement during transmission.

Parts list

D1, D2	1N914, 1N4148 or similar
C1, C2	10 nF disc ceramic
RFC	Miniature axial choke (1 mH)
Meter	Surplus VU meter or similar
Matrix board or similar	

Components are available from Maplin.

74 Preselector for a short-wave receiver

Introduction

A preselector is a simple RF tuned amplifier which is inserted between the aerial and the receiver. It provides some extra gain and may improve the overall performance of the receiver. This project uses a Field-Effect Transistor (FET) amplifier in grounded-gate mode.

The design has a tuned circuit at both the input and output which, with excessive gain and poor construction, would produce only one thing – oscillation! So, to avoid this happening, we will have only a low gain, and use a circuit which provides good isolation between input and output. The grounded-gate FET amplifier fulfils both these criteria. It will also cover a frequency range from about 7 to 30 MHz, which includes most of the HF amateur bands.

The circuit

This is shown in **Figure 1**. The signal from the aerial arrives at an RF transformer, the secondary of which is tuned with capacitor VC1a. The output from the tuned circuit is taken from a tap on the secondary to the source of the FET. The gate is grounded (earthed) and the amplified signal appears at the FET drain, which is then fed to the primary of another RF transformer, which is tuned by VC1b. The output to the receiver comes from the secondary of the RF transformer.


C1
100n
Ant
Rx
L1
L1a
Tap
R1
270R
R2
15R
s
d
g
VC1a
250p
VC1b
250p
TR1
MPF102
L2
L2a
R3
100R
C2
100n
Twin gang
+9V PP3
via S1
d s g
MPF102
L1, L2 = 19 turns 26SWG
on T-50-6 toroid
(tap L1 4 turns from ground)
L1a, L2a = 3 turns
©RSGB DY256

Figure 1 HF preselector, circuit diagram

Notice that the two RF transformers are identical, but they are used 'back to back', with the secondary of the first and the primary of the second being tuned. They are tuned with identical capacitors, fitted on the same shaft of a variable capacitor. We say that the two capacitors are 'ganged'. Because L1 and L2 are the same, and VC1a and VC1b are the same, both RF transformers should be resonant at the same frequency, no matter what that frequency is.

Construction

The final layout should look something like that shown in **Figure 2**. The external connectors and controls being two SO-239 sockets for connection to your receiver and aerial, a tuning control and its associated scale, and an on/off switch.

The circuit can be put together on a plain matrix board, using pins to anchor the components, or simply by pushing the component leads through the board and making connections on the underside. The layout of the prototype is shown in **Figure 3**. Mounting the board to the aluminium box is accomplished with bolts, solder tags and stand-off insulators.

Check your construction against the circuit diagram and against the layout diagram. Wire in the PP3 battery clip, put the switch in the 'off' position, and fit the battery. Testing can be carried out without fitting the top of the box.



Figure 2 HF preselector, front panel layout

Testing

Don't fit your preselector yet. Tune your radio to a broadcast station, preferably a fairly weak one. Disconnect the aerial and fit your preselector between the aerial and receiver. Switch it on and rotate the tuning knob slowly. You should find a position where your original station is received more clearly than before. If it doesn't work at all, recheck your wiring. Is there a positive voltage on the drain of the FET? If not, work back towards the positive battery terminal. Is there a voltage at the junction of L2 and R2? Is there a voltage at the junction of L2 and R3? Is there a voltage at the junction of R3 and the battery lead? If there isn't a voltage at that point, then you have probably mounted your switch upside down, and it is off, not on! It's a common mistake.

Calibration

This is not obligatory, surprisingly enough. However, if having a frequency scale appeals to you, then using an RF signal generator (or using the services of a friend who has one) is the simplest solution. Feed in a weak modulated


VC1
Aluminium box
12 x 9 x 3cm
Perforated
board 5 x 4cm
Tap
VC1a
VC1b
In from
antenna
Out to
Rx
L1
L2
MC
L1a
L2a
C1
R3
R3
C2
MC
d
s
g
R1
TR1
Solder
tag under
– Black
S1
PP3
battery
+ Red
©RSGB DY258

Figure 3 HF preselector, component layout

signal from the generator to the preselector, and rotate VC1 until the signal is maximum. Mark this frequency on your dial. Repeat the process for the frequencies shown on the dial in Figure 2.

If you have a commercial transceiver, feed its output into a dummy load (such as the type described in *A Switched Dummy Load*, elsewhere in this book) using a distinctive modulating signal such as an idling RTTY signal. Set the receiver to the same frequency with the preselector out of circuit. Insert it into the aerial lead, and search for the signal with VC1 until it gives the maximum deflection on your S-meter, then mark the frequency on your dial.

Parts list

Resistors: all 0.25 W carbon film or better

R1	270 Ω
R2	15 Ω
R3	100 Ω

Capacitors

C1, C2	100 nF (0.1 μF) ceramic
VC1	250/250 pF polyvaricon

Inductors

L1, L2	19 turns 26 SWG enamelled copper on T.50.6 toroid L1 has a tap 4 turns from ground end L1a and L2a – 3 turns wound over previous winding

Semiconductors

TR1	MPF102 FET

Additional items

Matrix board	To fit aluminium box (see Figure 3)
Aluminium box	12 × 9 × 3 cm
Battery and connector	PP3 9 V
S1	SPST on/off switch
Knob	As required
SO239	Sockets – 2 required

75 An audible continuity tester

Introduction

This is not the only continuity tester in this book. This alone attests to their use, so you may well want to experiment with several designs, then come up with one of your own! The very simplest form of continuity tester is probably a battery and a bulb in series, with the circuit being closed by connecting it to a fuse or other object being tested for continuity. The bulb could be replaced by a buzzer to give an audible indication. The current taken by the buzzer could damage some components, however. An ohmmeter can also be used, and is very popular for the purpose, as it indicates whether the circuit is low, medium or high resistance. This project has the advantages of indicating whether there is no continuity, some resistance or good continuity, and making an audible sound, so that you don't have to move your eyes from the circuit while making the test.

The circuit

Using only one integrated circuit, four components and a battery, this is a particularly simple circuit, as **Figure 1** shows. IC1 is usually used to flash an LED from a 1.5 V source, and to have a low current consumption. By changing the component values, IC1 is made to oscillate at audio frequencies, and we can hear these through the loudspeaker, LS1. Low-impedance speakers can be used, but result in an increased current drain, so the higher the impedance, the better.



Figure 1 Continuity tester, circuit diagram

Construction

The layout of the circuit on Veroboard measuring 7 strips by 15 holes is shown in **Figure 2**. Start by making the four track cuts which will lie underneath the IC. Use a track cutter or a 3 mm (⅛ inch) twist drill rotated between thumb and forefinger for this. Solder the Veropins in place, followed by the wire link. Then solder in the IC holder, the resistor and the capacitors, making sure that the electrolytic capacitor, C1, is connected the correct way round.

Check, with the board against a bright light, that there are no shorted tracks, either by large blobs of solder or by copper swarf from the track-cutting process. Then insert IC1 into its holder the right way round. The probes can be ordinary connecting wire, the free ends being tinned with solder to prevent wire whiskers from touching components other than the one you are testing.

If you are happy that the circuit and the wiring appear to be correct, fit the battery into its clip. Nothing should happen until the probes are touched together, when you should hear a note from the loudspeaker. If nothing happens, all you can do is to recheck your circuit, as there is nothing else to go wrong!


= Pin
= Link
= Cut in copper track
C8, D8, E8, F8
©RSGB DY260
1
5
10
15
A
B
C
D
E
F
G
H
I
R1
C1
C2
IC1
8
4
5
+
To LS
To battery −ve
To LS and probe
Component side of board shown

Figure 2 Continuity tester, component layout

Any box can be used; there is no justification for a metal case, unless you want to make use of something, which is to hand, such as a tobacco tin. Alternatively, any suitable plastic box will do.

Use

The tester will give different pitch notes for resistances of different values. The higher the resistance, the higher the pitch from the speaker. Try it with small inductors, and you will learn to recognise the different tones produced by the IC.

Safety notice

Using the continuity tester on components *in situ* is not advisable, as the results could be misleading. It can be dangerous to make measurements *in situ* on equipment, which is operating. If you must make such tests, always disconnect the equipment form its power source first.

Parts list

Resistor

R1	1000 Ω (1 kΩ), 0.25 W carbon, 10% or better

Capacitors

C1	10 μF electrolytic, 16 V
C2	0.1 μF subminiature polyester or ceramic

Integrated circuits	
IC1	LM3909N
Additional items	
	Veroboard 7 strips by 15 holes
LS1	64 Ω miniature loudspeaker
	IC holder
	Veropins
	Connecting wire
	Test leads
	1.5 V AA alkaline battery

76 An experimental 70 cm rhombic aerial

Introduction

Most commonly used aerials can be classed as *resonant* or *standing-wave* aerials. There is another class known as *non-resonant* or *travelling-wave*. Resonant aerials, such as the dipole, are narrow-band; this occurs because resonance occurs only over a narrow band of frequencies. Travelling-wave aerials, on the other hand, can operate over a wide band of frequencies.

The *rhombic* is an example of a non-resonant or travelling-wave aerial. It is often employed for fixed commercial and military short-wave radio links. Made with wire, it has a diamond shape when looking down on it from above. The four corners are supported on four masts. It is a very effective aerial, and has good gain, a quality which can be judged from the *polar diagram* shown in **Figure 1**. This has been obtained from a computer program, and so is the perfect shape for a rhombic aerial.

Theory (but only a little)

A polar diagram shows graphically the ability of an aerial to radiate (or receive) more effectively in one direction at the expensive of the radiation in other directions. Figure 1 shows the polar diagrams of two aerials, a simple 70 cm dipole and the rhombic described in this project. The dipole has the



©RSGB DY262

Figure 1 The horizontal polar diagrams of the small rhombic antenna and a dipole compared

well-known figure-of-eight shape, showing a symmetrical angular behaviour about the direction of the aerial and about a direction perpendicular to the aerial. That of the rhombic, on the other hand, is quite irregular by comparison, but is still symmetrical about one axis only, not two. It's this asymmetry that gives the rhombic its gain, by virtue of its *front-to-back ratio*. This is the ratio of the power radiated forwards to that being radiated backwards. Notice the large *lobe* (lump) at the top of the polar diagram; this is the direction in which the aerial transmits best. The lobe in the opposite direction has been reduced significantly, allowing more power to be directed forwards, not backwards

Problems

The rhombic is not found in every amateur's back garden, despite its attractions. To work best each edge of the diamond shape should be about two wavelengths long. Hence, a rhombic for the 20 metre band could be about 80 m from tip to tip! Another disadvantage is that, because of its size, it cannot be rotated.

It will operate well over a range of frequencies. An HF rhombic could work on the 7, 10, 14, 18, 21 and 28 MHz bands. One for the lower VHF frequencies could operate on the 50, 70 and 144 MHz bands.

Its large size is less of a problem at UHF. A portable rhombic can be made for 70 cm which can be used with a hand-held transceiver. The aerial design to be described here will give a gain of up to 9 dB relative to a dipole. This is written as 9 dBd, the second 'd' meaning 'relative to a dipole'. This is equivalent to improving your signal by 1.5 S-points at the receiver or (and you may be surprised by this) by fitting a linear amplifier to your transceiver that would take 5 W input and produce 40 W output to a normal dipole! Consider the relative costs of the two approaches to producing the same received signal. You will also receive everyone else's signals 1.5 S-points better than before!

Unlike the popular Yagi aerial, this design has no critical dimensions and can be folded up for transport by car or bicycle. It has a fairly high input (or feed) impedance, being fed usually by balanced twin feeder. To feed it with standard 50 Ω coaxial cable, a matching transformer in the form of a *balun* is required. A balun will convert the *bal*anced (symmetrical) aerial impedance to the *un*balanced and lower impedance of the coaxial cable. The details of how to build the balun, which in this case is a half-wave transformer, are included in the constructional details.

Construction

The aerial frame is made up of 1 cm × 2 cm strips of wood fixed to a plywood centre using 30 mm long M4 bolts, as shown in **Figure 2a**. The outer bolts fixing the front and side supports can be removed for folding prior to transportation, as shown in **Figure 2b**.

The wires are fixed to the front and rear supports using screw connectors, sometimes called 'chocolate block' connectors. Detail X and Y of Figure 2 show how this is done. The side supports have holes in the ends through which the wire is threaded.

The aerial must be mounted in the horizontal plane using a small shelf bracket attached to the centre plate, using the same bolts that hold the rear support. The other half of the bracket may be mounted to a vertical mast using screws or jubilee clips (hose clips).

The balun

Cut a 23 cm length of coaxial cable; this is to be our half-wave transformer. Cut and remove 2 cm from each end of the sheath. Make the braid into a pigtail at each end. Cut and remove 1 cm of the inner insulator from each


300Ω resistor made from two 600Ω resistors in parallel (see text)
X
Detail X
Coaxial feeder to transmitter
Coaxial cable (23cm long) balun
Braiding of coaxial cables joined together
Detail Y
Wooden wire supports
Wire routed through support
8mm thick x 210mm square
10 x 20mm wood
92cm (x 2)
122cm (x 2)
1mm insulated wire
Y
©RSGB DY255
(a)
(b)

Figure 2 Construction of the UHF rhombic antenna

end, leaving 1 cm of the centre conductor exposed. Fasten this piece of cable to the chocolate block connector together with the coaxial feeder cable as shown in Detail Y of Figure 2. The braids of all three prepared ends are soldered together, but are not connected to anything else. The inner conductor of the feeder from the transceiver is soldered to one end of the centre conductor of the 23 cm piece, and is connected to one end of the rhombic by one side of the chocolate block. The other end of the half-wave transformer also goes to the chocolate block, where it is connected to the other side of the rhombic loop.

The opposite corner of the rhombic, as shown in Detail X of Figure 2, shows that the loop is broken at the chocolate block, and is 'terminated' by two 600 Ω resistors in parallel. This makes the aerial a broad-band travelling-wave device, and gives it its directivity and gain. There is a rule of thumb, which includes a safety factor, which says that the terminating resistor must be able to absorb one-half of the maximum transmitter output power. So, if you use two 2 W 600 Ω carbon resistors (*not* wire-wound resistors) in parallel, you can use a transmitter with an output of 8 W, which is more than adequate for 70 cm hand-helds.

Using the rhombic

Fit the aerial to a pole or mast in the horizontal plane, if you intend to use CW or SSB, but in the vertical plane if you want to concentrate on FM work. In the latter case, a wood or fibreglass pole is mandatory. Tune to a local repeater, whose signal strength you know. Rotate the aerial to face the repeater, and you should see that the signal strength is greatly improved! Verify the directional properties of the aerial by rotating it and observing the changes in signal strength on your S-meter.

77 Water level alarm

Introduction

This is a simple device which, when you have built it, you begin to wonder how you ever managed without it! It will sound a buzzer when the level of water reaches a particular point, which you can set and vary at will.

Detecting water

Water is not too difficult to detect electrically, because it is a conductor of electricity. Not a good one, but sufficiently so to carry enough current to control a warning circuit.

The circuit is shown in **Figure 1**. If you imagine a resistor placed between the ends marked 'water detector', the circuit is then recognisable as a transistor used as an electronic switch. Whether the switch is off or on depends on the value of this resistor. If the resistance is low, the transistor switches on and the buzzer sounds. If the resistance is high, the transistor switches off and the buzzer stops.


Water
detector
WD1
+
6V
buzzer
+V
9V
PP3
−ve
b
c
e
R1
10k
TR1
BFY51
c
b
e
TR1 base
©RSGB DY298

Figure 1 Circuit diagram of the water level detector

Construction

The unit is made in two separate sections – the detector board (**Figure 2**) and the main board (**Figure 3**). The main board is plain perforated board (without copper strips). The components are pushed through holes in the main board and connected together on the underside. The battery is held on with sticky tape. No on/off switch is used, as the circuit consumes virtually no current when it is not sounding the buzzer.

Unlike some buzzers, this type is polarised, and the red lead must go to the supply as shown in Figs 1 and 3.

The detector board is a piece of standard matrix board – the type with copper strips along one side. It measures 9 strips by 15 holes, and is wired in such a way that alternate strips are connected together, as Figure 2 shows. This gives a greater surface area for the water to touch, thus increasing the sensitivity of detection.


©RSGB DY300
1
5
10
15
A
B
C
D
E
F
G
H
I
To main board
Wire links
Copper strips on underside of board
Component side of board shown

Figure 2 Layout of the main board


Tie to relieve strain on wires
+ Red
Buzzer
Tape to hold battery
To detector
–ve Black
+ve
TR1
R1
–ve
Perforated board 3·5 x 10cm
9V PP3 battery
Wires under board
©RSGB DY299

Figure 3 Water detector constructed from stripboard

The two boards are connected by ordinary twisted pair, enabling the detector to hang over the edge of the water container, with the buzzer circuit safely out of the way. When positioning the detector board, the left-hand edge (as shown in Figure 2) should face downwards, with the connecting-wire edge facing upwards. When the water level rises, the water causes current to flow between adjacent strips, and the higher the water, the lower the resistance between them. Eventually, the resistance will be low enough to turn on the transistor and sound the alarm.

Parts list

Resistor

R1	10 000 Ω (10 kΩ), 0.25 W

Semiconductor

TR1	BFY51

Additional items

WD1	6 V miniature buzzer (polarised)
	Battery PP3
	Battery connector
	Strip board 9 strips by 15 holes
	Perforated board 3.5 × 10 cm

78 A delta loop for 20 metres

Introduction

HF aerials take up a lot of room when they are straight. Space can be saved by bending them and, at the same time, giving them properties which are quite different from their original linear forms. The delta loops shown in the accompanying diagrams have the shape of the Greek upper-case letter delta (Δ) upside down. It can be upright, except that it is more practical to have the feed point at the bottom than at the top.

Putting the loop together

This is the design for a loop to be used on the 20 metre band. It is a very popular band and carries most of the amateur radio DX traffic. The aerial is light in weight and operates best if the top section is at least 30 ft above the ground, with the feeder point being about 6 ft above ground. All you need is some good wire, some polypropylene rope, some insulators and a method of matching the output of this 75 Ω balanced aerial to the 50 Ω unbalanced coaxial input of your transceiver or receiver.

Each of the three sides must be 7.2 m long. Using tent pegs or six-inch nails, mark out the three corners on the lawn, making sure that each pair of pegs or nails is exactly 7.2 m apart. Put the wire around the nails, together with two insulators on the wire for the two top corners. These insulators can be of the ‘dog bone’ variety, or of the home-made type, using a piece of flat plastic with holes in each end. The use of these is shown in **Figure 1**. Located at the positions of two of the tent pegs or nails, they must be secured at those points by any convenient means.

Now attach a support rope to the free end of each of the insulators, ready for suspension, as shown in the diagrams, from any convenient supports (house, tower, tree, etc.). The top section of the loop could be taped to a continuous piece of rope between the two supports. You might like to try this if you think it is easier. Then, when you find some dog-bone insulators, you can change the design and see if there is any noticeable change of performance.

Connecting to the radio

If you are the proud possessor of an aerial tuning unit (ATU) with a balanced output, all you will need is a length of twin cable soldered to the


Delta loop
Twin 75Ω feeder any length or
18 gauge twin moulded speaker cable
Z match ATU with
twin balanced inputs
Transceiver
©RSGB DY302

Figure 1 Multiband version of the delta loop connected to the ASTU using 75 Ω twin feeder

ends of your delta loop and connected to the balanced output terminals on the ATU, as Figure 1 shows.

Another way is to buy a ferrite-cored 1:1 balun, and use it as indicated in **Figure 2**. This produces an aerial which will operate over the whole range of amateur and commercial short-wave frequencies, when used with an ATU.


Delta loop
Wide band ferrite 1 : 1 balun
50Ω coaxial cable direct to receiver
no tuner required
©RSGB DY303

Figure 2 Multiband version of the delta loop using 75 Ω coaxial cable. This arrangement requires an ASTU if used with a multiband antenna



Figure 3 Single band version of the loop antenna using a coaxial balun. The direction of maximum signal strength is indicated by the arrows

However, since this aerial is designed to be a single-band type, there is a simpler answer to the problem of matching the aerial to your 50 Ω coaxial cable – **Figure 3** shows this. Make a tuned balun with a length of plastic water pipe, 25 cm long and 4 cm diameter and a piece of good-quality TV aerial cable. TV aerial cable has a characteristic impedance of 75 Ω, compared with the 50 Ω of the coaxial feeder that we usually use with amateur radio equipment. Use the type with a brown sheath and a closely knit earth braid, not the type having an earth foil inside the sheath.

The length we need for the balun is 3.8 m, but always allow between 3 and 4 cm extra for preparing the ends. Drill two small holes diametrically opposed in the top of the tube; these will be used to anchor the two ends of the delta loop, as shown in Figure 3. Drill another single hole in the bottom end of the tube, which will be used to anchor a nylon line going to the ground to add stability to the loop. Then, after drilling a pilot hole, drill a 5 or 6 mm hole near the top end of the tube, as shown in **Figure 4**. Prepare both ends of the coaxial cable, then feed one end into the tube, far enough for its ends to be soldered to the ends of the loop when the assembly reaches that stage.

Now, close-wrap the cable around the tube until only about 3 cm remain. Holding the cable tightly, drill another 6 mm hole beside the free end of the cable and feed it into this hole. At this point, feed the two ends of the loop into the top two holes and twist it back on itself. Figure 4 shows how this is done. Then, solder the ends of the coaxial balun to the ends of the loop.


Delta loop wires
Cable ends joined inside the tube to hold coil in place
3·8m cable wound tightly onto former
75Ω television coaxial cable
50Ω radio coaxial cable to receiver
One connection to inner conductor. Join braids together. Insulate inner from braid with insulation tape
Nylon line to ground stake
©RSGB DY305

Figure 4 Construction of the balun

The bottom ends of the balun are then soldered to the 50 Ω coax which goes to your shack and to the transceiver.

Hoist the aerial into position carefully, being careful not to pull too hard on the support lines. Then, take the nylon line from the bottom of the balun to a peg in the ground. This adds stability to the aerial.

Using the delta loop

It is a directional aerial, as Figure 3 shows. It produces maximum power (and has maximum receive sensitivity) along a direction perpendicular to its own plane. Don't be too concerned with which direction it is pointing at first. Give it a try 'on the air' and see how it performs. Then you can contemplate how to point it in your favourite direction, to the USA, or Australia, for example.

Experimenting

You may want to enclose the balun in some sort of weatherproof container. Plastic ice cream containers are favourites for this sort of job. Seal all the holes where wires enter it with silicone sealant or self-amalgamating tape.

If you have used ordinary single-strand or multi-strand wire for your aerial, it will stretch over time under its own weight and that of the balun. Its operating frequency will fall slightly as a result. If you notice a significant difference, then dismantle it, remeasure and fix the sides and erect it again, perhaps facing a different direction. You can buy pre-stretched or hard-drawn wire for such purposes, if you feel that periodic tweaking of your aerial is a chore.

You can make a delta loop for different frequencies simply by scaling the lengths of wire for the loop and for the balun according to the design frequency. If your maths isn't quite up to this, enlist the help of someone well versed either in maths or aerial design!

79 A simple desk microphone

Introduction

A hand-held transceiver is usually the first type used by most novices. It is ideal when used out of doors, in the shack or mobile. However, using one in the shack with an outside aerial is not the best of solutions.

This article describes the design of a desk microphone which can be used either for transceivers using a common microphone and push-to-talk (PTT) line, or for those using a separate PTT line.

It is a simple design, using the barrels of two plastic pens, the lid of an old coffee jar, and the plastic sheath of a DIN plug.

Construction

The end caps and the ink tubes should be removed from two ball-point pens, leaving only the two plastic shells. One of them is used for the vertical microphone support, while the other is used to hold the microphone element.

The vertical support should have the pointed end shaped so that it holds the microphone support at a convenient angle, as **Figure 1** shows.

The base should be prepared next – see **Figure 2**. Four holes are required. Two, A and B, are small holes for the cable to be fed through. A third, C, is slightly larger and is used to take one of the plastic end caps. The fourth hole, D, is determined by the type of switch that you want to use for the PTT function.


Remove
shaded
area
©RSGB DY286

Figure 1 Vertical support made from ball-point pen shell


A and B
for cable
C for
stand
A
B
C
D
All holes
appropriate
D for
PTT
©RSGB DY287

Figure 2 The microphone stand base

Some epoxy resin such as Araldite Rapid is used to mount the separate parts. Mix only a small amount at a time, and glue each part of the base assembly and allow to harden before moving on. Be sure to read and follow the instructions for the use of the glue to prevent accidents.

Firstly, glue the end cap to the base, feeding it underneath and pushing it up through hole C. Then, the vertical pen body is placed over the protruding end cap and glued into place, making sure that the top (shaped) end is pointing in the right direction to hold the other plastic tube carrying the microphone. While the glue hardens, place the DIN plug sheath on the second pen body. Place and glue this pen body on the shaped top of the vertical support, making sure that the whole assembly is supported while the glue sets. What you should have now ought to resemble **Figure 3**, but without the microphone and wiring. Leave everything to set for 24 hours.

Any switch of the press-to-make variety can be used for your PTT switch, but choose one which does not apply too much force to operate! If you find the whole assembly is too light and slides over your table, some plasticine can be pushed into the base when all the wiring has been completed.



Figure 3 Complete microphone stand assembly

The circuit

A small electret condenser microphone is used, powered by a DC supply. Most hand-held radios use a single screened lead for both the PTT line and the microphone audio lead. In such cases, the circuit of **Figure 4** will operate the PTT function. Note that the PTT switch is in series with the audio lead from the microphone. If you find that the PTT switch does not switch your radio into transmit, reduce R1 from its normal value of 33 kΩ to 27 kΩ. You should find that the original value works with most hand-helds.



Figure 4 Wiring diagram for hand-held radios

For radios with a separate PTT lead, the circuit of **Figure 5** is used. However, a power supply is needed for the electret microphone. This can be a PP3 battery, or can (in most cases) be derived from the microphone socket on the transceiver. You will need to consult the makers' handbook for this information. Figure 5 shows the PTT switch wired in a 'ground-to-transmit' configuration, which is correct for most base-station transceivers. If you're in any doubt about what your radio needs, consult an experienced friend.



Figure 5 Wiring diagram for radios which use separate PTT lines

The last connections

The microphone element should be connected with screened cable. Tape (masking or insulating) should be wound around the electret insert until it is a snug fit inside the DIN plug sheath. Feed the screened cable through the barrel of the pen until it emerges from the far end. Poke it through hole B and make the connections under the coffee jar lid. The components can all be mounted on the PTT switch or on a small piece of Veroboard mounted under the top surface. The output lead emerges through hole A and is of sufficient length to reach your transceiver. A suitable plug needs to be fitted to it.

Parts list

Resistors: all 0.25 W carbon, 5% tolerance

R1 (Figure 4)	33 000 Ω (33 kΩ)
R1 (Figure 5)	1000 Ω (1 kΩ)

Capacitors

C1 (Figure 4 and 5)	0.1 microfarads (0.1 μF) disc
C2	10 microfarads (10 μF) electrolytic

Additional items

S1	Push-to-make
Mic	Electret microphone (Maplin type FS34W)
Screened cable	As required
Plug	As required by your radio
Veroboard	If required
PP3 battery and clip	If required

Two old plastic ball-point pens
Lid of coffee jar
Plastic sheath from DIN plug
Araldite or similar epoxy resin glue

80 Morse oscillator

Introduction

This is not the simplest Morse oscillator to build, but it differs from the simple circuits in that it produces a pure note, not a coarse, rasping sound. People who have practised Morse using a non-sinusoidal oscillator sometimes find that they have trouble copying Morse code with a pure tone. As the pure tone is the correct way to receive Morse code, it is important that you should learn to listen to the code from a pure oscillator – so here's one!

The twin-T

There are many oscillator circuits, and there are many variations of the twin-T oscillator that we are going to use. **Figure 1** shows one version of a very useful circuit. All oscillators must have positive feedback in order to work. The feedback determines the frequency of the note produced by the oscillator.


b
BC109
e
c
R4
10k
Key
(via socket)
S1
+9V
PP3
c
b
TR1
BC109
e
R1
18k
R2
18k
C7
22μ
C1
10n
C2
10n
nc
4
7
2
6
IC1
LM386
5
C9
220μ
C4
100n
3
R3
4k7
RV1
10k
log
pot
(vol)
8
C8
100n
C3
47n
1
C5
22n
C6
10μ
R5
10R
LS
8Ω
©RSGB DY312

Figure 1 Circuit diagram of the sinewave oscillator and amplifier

Here, the feedback circuit looks like two letter Ts. If you look at Figure 1, one T is formed by R1, R2 and C3, the other by C1, C2 and R3 – hence the name ‘Twin-T’. Notice that the two Ts are connected in parallel between the collector and base of TR1, so any signal appearing at the collector is fed into both Ts. What emerges is then fed back into the base, producing in turn a signal at the collector. And so it goes on, producing a sine wave output.

The oscillator output is fed into an integrated circuit amplifier for output via a small loudspeaker.

Putting it together

The prototype was constructed on plain matrix board (the type *without* the copper strips), as shown in **Figure 2**. The components have their leads pushed through the holes in the board, and connections are made underneath.

Build the amplifier circuit first, using a socket for IC1. Connect the 9 V supply and touch pin 3 with an ordinary piece of wire. If a buzz is heard from the speaker, all should be well. If not, check your circuit and make changes until it does.

Build the oscillator circuit, and connect its output to the volume control VR1 via C4. Set VR1 half-way along its travel and switch on. A note should be heard from the speaker when the Morse key is depressed. The component values making up the twin-T determine the frequency of the note. Try varying them if you think your note is too high or too low. Whatever changes you make, either to the resistors or the capacitors, always ensure that R1 = R2 and that C1 = C2.


Plain perforated board 3·5 x 9cm
To +9V via key socket
To +9V via S1
------- Wires under board
R4
C7
C2
nc
8 7 6 5
C1
R1
R2
C6
IC1
C8
C9
LS
C4
R3
1 2 3 4
C5
R5
C3
6BA solder tag
Earth wire 24SWG tinned copper wire
RV1 (top)
RV1 (wiper)
RV1 (btm)
LS
©RSGB DY313

Figure 2 Component layout and interconnection diagram

Parts list

Resistors: all 0.25 W carbon film

R1, R2	18 000 ohms (18 kΩ)
R3	4700 ohms (4.7 kΩ)
R4	10 000 ohms (10 kΩ)
R5	10 ohms (10 Ω)

Capacitors

C1, C2	10 nF (0.01 μF)
C3, C8	47 nF (0.047 μF)
C4	100 nF (0.1 μF)
C5	22 nF (0.022 μF)
C6	10 μF electrolytic, 16 V WKG
C7	22 μF electrolytic, 16 V WKG
C9	220 μF electrolytic, 16 V WKG

Semiconductor

TR1	BC109

Integrated circuit

IC1	LM386

Additional items

VR1	10 kΩ log potentiometer with switch
LS	8 Ω loudspeaker

Matrix board 3.5 × 9 cm
Small jack socket for key input
Box
PP3 battery and clip

81 A simple 6 m beam

Introduction

The attraction of building your own aerials is an abiding feature of our hobby. You can *buy* almost any shape or size of aerial, but one you have made yourself can often work every bit as well as a commercial device costing ten times as much.

The design

This aerial, designed for use on the 6 m band, is essentially a two-element Yagi, with the elements bent in order to reduce the physical size. It is known


Total length of reflector
3 m
Elements fixed to spreaders
using plastic insulating tape
Insulator A
Insulator A
Tail (see text)
Tail (see text)
Coax to Tx
Total length of driven element
2·98m
Feed point
insulator B
©RSGB DY310

Figure 1 Plan view of the complete 50 MHz VK2ABQ antenna

as the VK2ABQ beam, and was designed originally for the 20, 15 and 10 m bands, principally because of its space-saving qualities. It is made using a wooden frame and wire elements, and is ideal for portable operation.

Tools ready?

The beam is shown in **Figure 1**. The driven element is the one whose centre is fed by the coaxial cable, and lies between the two insulators marked A and the feedpoint at B. The reflector is also anchored at the points A, and lies over the upper half of the frame.

The wooden centrepiece is used to support the cross-pieces and to mount the aerial on the mast, using a common shelf bracket. The cross-pieces, known as *spreaders*, can be wooden canes or dowelling, and are mounted to the centrepiece using cable clips and adhesive. **Figure 2** shows how this is done.

If the aerial is to be a permanent installation, the spreaders should be weatherproofed using a good-quality exterior varnish. The wire elements are PVC covered and fed through holes in the spreaders.



Figure 2 Centre support piece

The end insulators are made of drilled perspex, and the wire passed through the two holes and twisted, as shown in **Figure 3**.

Note: if you have not drilled holes in perspex before, take care! The drill bit must be well-lubricated because it generates a lot of heat (enough to melt the perspex and jam the drill). Never turn the drill for more than a few seconds at a time, and moisten the bit in between. Start with a pilot hole and use bits of increasing size until the hole is the size you want.

Another perspex insulator is used to secure the feeder to the aerial, as shown in Figure 3. The feeder then passes directly to the centrepiece, where it is fastened with a cable clip and then passes down the mast.


1cm
1cm
2cm
1·6mm dia hole
Side view showing how wire is fixed
Insulator A
2cm
To transceiver
4·5cm
1·6mm dia hole
1cm
Top view showing connections
Insulator B
©RSGB DY311

Figure 3 Details of insulators

Adjustment

The driven element (A–B–A) in Figure 1 is fixed to the end insulators in such a way as to have 'pigtails' which are about 10 cm long. Using an SWR meter between the aerial and the transmitter, trim the pigtails equally at each end for minimum SWR in that portion of the 6 m band in which you plan to work. Make sure that the transmitter is off when you trim the ends, as high voltages can be present there. Always listen on the frequency before you transmit and, when you do, ask if the frequency is in use and identify yourself. Use as little power as possible.

The prototype had an SWR of 1.2 at 50.2 MHz and performed well. If you look at Figure 1, which is a view of the aerial from above, you will immediately see that when the aerial is horizontal, it radiates with horizontal polarisation in a direction from the top of the page to the bottom. A metal pole or mast can be used for horizontal polarisation, but if you intend to use the aerial for vertical polarisation, it is much better to use a wooden or fibreglass pole.

Portable use

If you plan to operate portable with this aerial, the only real modifications you need are to the centrepiece and how it supports the spreaders. Instead of using glue and cable clips, nuts and bolts through the spreaders and centrepiece would allow the spreaders to be 'hinged' closed for transport.

Materials

Centrepiece	Hardwood, 15 × 15 × 25 mm
4 spreaders	110 cm long (cane or 6 mm dowel)
Wire	1.5 mm PVC-covered copper
50 Ω coaxial cable	RG58 or similar
Cable clips	6 mm (12 off)
Varnish	Polyurethane for waterproofing
Tape	Self-amalgamating, to waterproof all soldered joints
Insulators	See text

82 An integrated-circuit amplifier

Introduction

A simple audio-frequency amplifier is a very useful building-block in many more advanced electronic circuits. It is also a very useful piece of test equipment. To have one spare in the shack can be a life-saver at times.

Planning

Get into the habit of planning your project. How do you want it to look when it is finished. Do you want it in a box? Do you want it 'open-plan', with all the components on view?

The 'minimalist' approach to any project is simply a front panel and a baseboard, on to which all the components are fitted. In this case, the front panel would accommodate the loudspeaker, the volume control and the input and output jack sockets, and the baseboard would support the circuit board. Once you have decided these things, and know the size of the board, speaker and volume control, you can decided how big the panel and baseboard should be.

The amplifier

Instead of building the amplifier from discrete components (i.e. transistors), as was done in the project *An audio-frequency amplifier* (which you will find elsewhere in this book), we are going to use an integrated-circuit (IC) amplifier. External resistors and capacitors are still needed but, compared with the number of components *inside* the chip, these are very few indeed!

The IC we are going to use is the TBA820M. The circuit may look complicated, but with the use of a matrix circuit board it becomes quite simple. **Figure 1** shows the circuit diagram and **Figure 2** the layout on the board. The external connections to the PCB are shown in **Figure 3**.

To avoid having a separate switch to switch off the power supply when the amplifier is not being used, a volume control which incorporates a switch is used.


+
12V
–
C7
680p
R4
51R
C5
0µ1
Input
from
volume
control
6
3
1
7
+
C1
100µ
TBA
820
5
2
8
IC1
4
+
C3
220µ
L/S
R1
10k
R2
120R
+
C2
100µ
+
C4
47µ
R3
1R
C6
0µ1

©RSGB DY331

Figure 1 Audio amplifier, circuit diagram


Input
L/S
+12V
100µ
0µ1
120R
220µ
10k
100µ
680p
56R
220µ
47µ

©RSGB DY332

Figure 2 Audio amplifier, component layout

©RSGB DY333


To battery
positive connection
Volume
control
VR1
To battery
negative connection
Input from
earlier stages of
the receiver
Input
AF amp
PCB
+ supply
Speaker

Figure 3 Connecting the circuit board to the speaker, volume control/switch and battery

What power supply?

If the amplifier is to be used only for short periods, as a test instrument, for example, then it can be run from a PP3 battery, which can be mounted on the baseboard. If you intend to use it often, then a connection to an external power supply is preferable. For this option, you may want to consider fixing two terminals to the baseboard for this connection.

83 A novice ATU

Introduction

Having an aerial tuning unit (ATU) is always useful. It is used for adjusting the aerial impedance, as 'seen' by the transceiver, to be the same as that of the transceiver itself, usually 50 Ω. This process is called *matching*, and ensures that the receiver and the power amplifier (PA) stage of the transmitter work efficiently.

This design is due to the late Doug DeMaw, W1FB, and uses readily available components. It will handle up to about 5 W, and operates over the frequency range 1.8 to 30 MHz.

Circuit evolution

The basic circuit of one type of ATU is shown in **Figure 1**. On transmit, the input signal at L1 is coupled into L2, which forms a resonant circuit with C1. The signal across the resonant circuit is fed to the aerial by C2. The combination of L2 and C1 helps to remove signal harmonics, because they are not at the resonant frequency and are shunted to earth. On receive, only those signals which are within the pass-band of L2 and C1 will pass into the receiver. This improves receiver performance by rejecting many out-of-band signals which the simpler receiver doesn't like.



Figure 1 Basic circuit of the ATU

For this design, the all-important resonant frequency is chosen to be in the 80 metre band. If we want to make the circuit operate on other bands, we need to change either L2 or C1. It is easy to change L2 by using a set of switched inductors (L3–L5) as shown attached to S1 in **Figure 2**. Forget about S2 and L6 for the moment.



Figure 2 L6 added for 160 m

When S1 is in position 1, the circuit reverts to that of Figure 1. S2 should be brought into circuit only when S1 is in position 1. Looking at the way the circuit is drawn, you can see that when S2 is in position 2, we have two coils in series, which is equivalent to adding more turns to L2. More turns means more inductance, which lowers the resonant frequency still more, and gives coverage of the 160 m band.

Rather than having to remember to flick S2 to the correct position *and* move S1 to position 1 when we want to operate on 160 m, both functions can be combined into one rotary switch with two wafers. This circuit is shown in **Figure 3**.


L6
2
3
4
1
S1b
Input
C2
Output
1
S1a
4
C1
L1
L2
2
3
L3
L4
L5
©RSGB DY325

Figure 3 Two-pole switch for all bands

In all positions of S1a *except* position 1, the extra coil, L6, is shorted out. The two halves of the switch, S1a and S1b, move together, as the shaft is turned, so both halves are in position 1 at the same time, position 2 at the same time, and so on. The two switches, S1 and S2, are said to be *ganged*.

Construction

L1 is formed by winding four turns of 22 SWG enamelled copper wire over L2, as in **Figure 4**. L2 already exists on the purchased former. After scraping the enamel off the ends of the wire (with a sharp knife or sandpaper), one end of L1 must be soldered to one end of L2, as shown in Figure 4. The free end of L1 goes to the transceiver aerial socket.

All components except the capacitors are assembled on the switch. Note that the rotor of C1 is earthed, but neither side of C2 is earthed. This means that the metal shaft of C2 is not earthed, and touching it will detune the ATU. Using a plastic knob for C2 will minimise this effect. If you decide to use a metal box, take precautions to ensure that no part of C2 is in electrical contact with the box.


L1
(4 turns of
22SWG wire)
To input
socket
L2
(as purchased)
L1 connected
to L2 here.
This is now
the earth end
for both coils
This pin
to S1b
©RSGB DY326

Figure 4 L1 is wound over L2 as shown

The capacitors are mounted using M2.5 screws. Make sure that the screws do not foul the vanes of the capacitor. If your screws are too long, a few washers between the box and the capacitor will solve the problem!

In use

The best indication of a good match is obtained with a standing-wave meter between the ATU and the transceiver. The controls are adjusted alternately to ‘feel’ your way to a better and better match.

For receive-only use, the same alternate adjustments are used, watching for the maximum signal strength on the S-meter or, for a very weak signal, making the signal from the loudspeaker as large as possible.

Parts list

Capacitors	
C1, C2	350 pF variable
Inductors	
L1	See text
L2	27 μH
L3	10 μH
L4	2.2 μH
L5	1 μH
L6	65 μH
Additional items	
SO239 sockets (2 off)	
S1	2-pole 6-way rotary
Box	as required
Plastic knobs (2 off)	
Stick-on feet (4 off)	
M2.5 screws for capacitors	
Screws, nuts and washers for mounting the input and output sockets.	

84 CW QRP transmitter for 80 metres

Introduction

This is a relatively simple transmitter design having an output of 1 W. The design is not new, having been described before in other amateur radio publications. The components are all available new and the total cost should not exceed £15.

The circuit

Like other simple transmitters (see *An 80 Metre Crystal-Controlled CW Transmitter* and *A Breadboard 80 m CW Transmitter* elsewhere in this book) this one is crystal controlled. This assures frequency stability, but limits the usefulness of the transmitter. The key to increased frequency coverage without a conventional Variable Frequency Oscillator (VFO) is the use of a low-cost 3.58 MHz *ceramic resonator*. The 'pulling' range of a 3.58 MHz ceramic resonator covers the UK novice 80 m sub-band and some of the CW segment below 3.525 MHz.

A ceramic resonator is like a crystal, but not quite as stable in frequency. Its main advantage is its large pulling range.

The block diagram is shown in **Figure 1**. It is very similar to a crystal-controlled transmitter, and includes an oscillator, buffer and final amplifier.


©RSGB DY340
+12V Tx
Tx
Rx
+12V DC
BC640 transistor switch
+12V
key down
4069
3·58MHz
Oscillator
Buffer
VN10KM power amplifier
Tx
Rx
Antenna
1·5W out 3·5MHz
Ceramic resonator
Frequency adjust
To receiver

Figure 1 Block diagram of the ceramic resonator controlled 80 m CW transmitter

This amplifier is keyed, the oscillator remaining running all the time. This improves frequency stability because the oscillator is not being continuously stopped and started by the key. It is switched off while receiving, though, to avoid interference with the received signal. Transmit/receive switching is accomplished by a panel-mounted switch controlling both the aerial, oscillator and buffer switching.

Figure 2 shows the transmitter circuit diagram. An unusual aspect of this transmitter is the use of a digital CMOS integrated circuit (IC) type 4069 for the buffer and oscillator stages. The IC houses six inverters, four of which are used in the circuit. One is used as the oscillator, two are used for the buffer stage, and the fourth provides an output for a direct-conversion receiver, should one be added at a later date.

The frequency of the oscillator is changed by varying the capacitance in the ceramic resonator circuit. This is provided by VC1.

The power amplifier (PA) is a small MOSFET (metal oxide semiconductor field-effect transistor), TR1. This is capable of providing an output power of 2 W but, in this circuit, it is run conservatively to give 1.5 W. The output can be varied by changing the resistance (R5 + R6) in the gate circuit. Attempts



©RSGB DY341
1
14
4069
7
8
VN
10k
s g d
BC
640
e c b
6V8
To direct
conversion
receiver
(see text)
O G A
Variable
capacitor
connections
6·8V regulated
R
x
12V
y
T S1a
C1
100n
D1
6V8
R3
270R
C4
1n
R5
1M5
C6
10n
c
e
C10
10n
Key
TR2
BC640
b
R7
1k
Rx
C11
100n
1
2
3
14
4
11
10
7
IC1
4069
9
8
R1
10M
R2
2k2
C5
10n
R6
1M5
RFC2
10µH
d
R
Ant
XC1
3·58MHz
5
6
g
s
TR1
VN10KM
C7
100n
RFC3
2·2µH
T S1b
RFC1
8·2µH
13
12
R4
1M
C8
560p
C9
820p
C2
100p
C3
47p
VC1
10-
160p
Oscillator
3·518 - 3·558MHz
Buffer
Power amplifier
Pi network

Figure 2 Circuit diagram of 80 metre transmitter

to raise the output power by decreasing the values of these resistors may result in immediate MOSFET failure.

A pi-network (C8, RFC, C9) provides impedance matching to 50 Ω, together with harmonic suppression. Like all inductors in this transmitter, the pi-network inductor is a pre-wound RF choke. A pi-network is so called because the components are arranged in the shape of the Greek letter pi (π).

Keying is carried out by a pnp transistor switch, TR2. Closing the key earths the base and supplies 12 V to the collector of TR2 and to the drain of the MOSFET, TR1, allowing the PA to operate.

Construction

You must house your transmitter in a metal box, to avoid hand-capacity effects and the radiation of spurious frequencies. Size is not important, provided it is large enough to accommodate the transmitter without cramping the components. You may want to allow space for future additions such as a direct-conversion receiver, break-in keying, sidetone or a small power amplifier. A good size is 5 × 15 × 15 cm. You can make your own box, buy it, or even use a biscuit tin!

Front and rear panel connectors can be fitted first. The choice of these is a personal matter, but a good working choice would be:

(a) Power socket – 2.1 mm panel socket – centre pin positive.
(b) Key socket – ¼ inch jack socket.
(c) Aerial and receiver connectors – panel-mounting SO239 type.

Particular attention must be paid to the mounting of the variable capacitor, VC1. Make sure the hole for the shaft is amply big enough, and if you use screws to mount the capacitor on the front panel, then make sure they are not too long, otherwise they will touch the vanes of the capacitor! Mounting can be by means of glue, sparingly applied and kept well away from the shaft.

A board size of about 6 × 10 cm is adequate. Component layout on the board is suggested in **Figure 3**. The prototype used ordinary matrix board, which is preferable to stripboard for a design like this; stripboard has undue capacitance between adjacent strips. Component leads are fed through holes in the board and are connected underneath. Make sure that leads and connections are rigid because, if they can move, there is always the danger of short-circuiting, and capacitance changes.

To facilitate construction, servicing and testing, it is advisable to use Veropins for connections to the variable capacitor, transmit/receive switch,


Matrix board 6 x 10cm
T/R switch
y
x
BC640
e
b
c
12V
100p
3·58MHz
ceramic
resonator
10M
100
n
270
R
6V8
1
1M5
1k
100n
10n
Key
socket
100n
10µH
47p
2k2
1n
1M5
2·2µH
T/R switch
8·2µH
g
d
s
10n
10n
4069
VN10KM
1M
560p
820p
G
O
A
Frequency
adjust
● Solder joint
● PC circuit board pin
©RSGB DY342

Figure 3 Component layout of the 80 metre transmitter. The transmit/receive switch is not mounted on the board and is not shown in this diagram

aerial and power sockets. Use screws and spacers to mount the circuit board to the box. Mounting the board horizontally assists troubleshooting.

Use a socket for the IC, and observe the CMOS handling precautions given in *An Electronic Die*, elsewhere in this book. When soldering the leads to the ceramic resonator, do it quickly – excessive heat damages the device. The earth lead running acoss the bottom of the board must be connected to the metal case by a short length of stout wire.

Testing

After carefully checking your wiring, both against the circuit diagram and the layout diagram, it is time to test your circuit. You will need a multimeter, an 80 m SSB receiver and a 50 Ω dummy load. A good design of dummy load can be found in the project *A Switched Dummy Load*, also in this book. An RF power meter and frequency counter will also be useful, although if your receiver has a digital frequency readout and S-meter, the latter two items are not really necessary. You will also need a 12 V 1 A power supply unit (PSU) to power the transmitter.

Switch the transmitter to receive and switch on the transmitter. No current should be consumed. Switch to transmit and check that pin 14 of IC1 is 6.8 V positive. With the dummy load connected to the aerial socket, press the key. The voltage on TR2 collector should now be 12 V, dropping to zero when the key is released.

Now check the operation of the oscillator. In transmit mode, you ought to be able to find a strong carrier signal with the receiver, even though the dummy load is connected. Adjusting the variable capacitor should change the frequency. At the lower end of the frequency range, you may find that the oscillator is unreliable in starting, because the circuit is attempting to pull the resonator too low in frequency. If this is the case, set the trimmer at the back of VC1 to minimum capacitance. If your version of VC1 has two trimmers, and you don't know which one to set, set them *both* to minimum capacitance. If there is still a problem, reduce the value of RFC1 to 6.8 or 4.7 μH.

In all probability, the unmodified circuit of Figure 2 will not require any of the changes outlined here. A coverage of 3.518 to 3.558 MHz should be possible, while preserving good frequency stability and reliable oscillation.

A signal probe (see *An RF Signal Probe*, elsewhere in this book) is useful for checking the operation of the oscillator and PA. Alternatively, an RF power meter or the receiver's S-meter can be used. With the PA running, the unit should draw between 200 and 300 mA. If TR1 becomes too hot to touch after a few seconds of transmitting, increase R5 or R6 to limit the transistor's heat dissipation. A small 6.3 V bulb connected across the aerial output is a simple way to check that the PA is working. An orange/white glow when the key is pressed is indicative of correct operation.

The final test is to monitor keying 'quality'. With your dummy load connected, press the key and listen to the note on the receiver's loudspeaker. Then operate the key, sending a string of dits, for example. What you hear should be free of chirps and clicks, as well as being stable in frequency. This test is sometimes better performed with no aerial connected to the receiver, thus preventing receiver overload and its associated plops. No problems should be encountered here.

Frequency tuning

A peculiarity of ceramic resonators is that, every now and again, their frequency changes abruptly by 100 Hz or so, then remains stable for some time. This is certainly noticeable in the received signal, but does not detract from the QSO and no characters are lost as a result. Try to keep the area around the ceramic resonator cool, to avoid temperature variations.

Parts list

Resistors: all 0.25 W, 5% tolerance

R1	10 megohms (MΩ)
R2	2200 ohms (2.2 kΩ)
R3	270 ohms (270 Ω)
R4	1 megohm (1 MΩ)
R5, R6	1.5 megohms (1.5 MΩ)
R7	1000 ohms (1 kΩ)

Capacitors

C1, C7	100 nF
C2	100 pF
C3	47 pF
C4	1 nF
C5, C6, C10	10 nF
C8	560 pF
C9	820 pF
VC1	10–160 pF variable

Inductors

RFC1	8.2 μH
RFC2	10 μH
RFC3	2.2 μH

Semiconductors

IC1	4069
TR1	VN10KM
TR2	BC640
D1	6V8 Zener

Additional items
- Matrix board (see text)
- 14-pin DIL socket
- Pointer knob
- Sockets (see text)

85 An audio booster for your hand-held

Introduction

The audio output from many hand-held transceivers and receivers usually leaves much to be desired, so this little amplifier was designed to increase the output at minimal expense.

All that is needed is a separate amplifier and bigger loudspeaker. This is accomplished using a single integrated circuit (IC), a few components, and a loudspeaker from the junk box. This circuit will enable the output from your hand-held to be heard easily in a car.

The circuit

This is shown in **Figure 1**. It uses only those components necessary to operate the IC amplifier. VR1 is the preset volume control, and varies the signal coming from the 'External speaker' jack on the hand-held before feeding it into the IC for amplification. C1 blocks any constant voltage present on the input.


TDA 2003
5
4
3
2
1
R4
470R
Red LED
Input from handheld radio
+12V
C5 220n
C6 100µ 25V
3 amp fuse
On/Off switch
VR1 1k0
C1
10µ 25V
IC1 TDA2003
C4
1000µ 25V
R1 15R 1W
R2 220R
C3 220n
C2 470µ 25V
Speaker 4R (6W)
R3 2R2
−ve
©RSGB DY376

Figure 1 Circuit diagram of the audio amplifier. The power is derived from the cigarette lighter socket and the fuse is in-line with the lead

The IC output comes from pin 4 and is fed via the electrolytic capacitor, C4, to the loudspeaker. The circuit is provided with an on/off switch, fuse and LED to indicate when the circuit is switched on.

Construction

The box is made of aluminium. This is necessary to help to dissipate some of the heat generated by the IC. Do not build the circuit inside a plastic box unless you take special precautions! The IC has a metal mounting tab with a hole, specifically designed to be mounted to a metal box or other metal heat sink. Apply plenty of heat sink compound between the tab and the box, tighten the nut and bolt, and then wipe off any excess compound. The box will get slightly warm in operation.

The size of the box is not specified. You may want to decide on this when you find a loudspeaker. Choose one which will be able to handle 6 W


Heat sink
TDA 2003
1 2 3 4 5
Wires under perforated board
Plain perforated board 4cm x 6cm
Input screen lead
R1
C1
C3
C5
C4
VR1
R2
C2
R3
+12V (C6 & fuse) (LED & On/Off switch)
To speaker
Solder tags underside
−ve
©RSGB DY377

Figure 2 Layout of the components within the box

output. Drill all the holes in the box first. Holes for the speaker, input phono socket and the LED. The amplifier can be constructed on ordinary matrix board, which can be mounted inside the box with screws and spacers.

The layout is shown, for your guidance, in **Figure 2**. The components are mounted by pushing their leads through the holes in the board and making connections on the underside. The preset volume control, VR1, is set such that the hand-held's volume control is sufficient to control the final output over a good volume range. Use a screened lead from the 'External speaker' jack socket to the phono plug.

An external power supply is needed for this circuit. The normal dry battery which we usually use for small projects in this book will *not* work here, so you will need a proper mains power supply producing a stabilised 12 V. If you are going to use the unit principally in a car, then the cigar lighter socket can supply this voltage easily. Do make sure that the polarity is correct before you switch on!

When you plug the jack plug from your booster into the 'External speaker' socket on your hand-held, its internal speaker will be muted, so don't think that something dire has gone wrong! Adjust VR1 for a good volume range on your booster, when the volume control is turned on the hand-held.

Parts list

Resistors: all 0.25 W, 5% tolerance, unless otherwise stated

R1	15 ohms (15 Ω) 1 W
R2	220 ohms (220 Ω)
R3	2.2 ohms (2.2 Ω)
R4	470 ohms (470 Ω)
VR1	1000 ohms (1k Ω)

Capacitors

C1	10 μF 25 V
C2	470 μF 25 V
C3, C5	220 nF (0.22 μF) Mylar
C4	1000 μF 25 V
C6	100 μF 25 V

Semiconductor

LED	5 mm Red

Integrated circuit

IC1	TDA2003

Additional items
- Heat sink compound
- Nuts and bolts
- Loudspeaker 4 Ω 6 W
- 3 A fuse
- On/off switch (SPST)
- Matrix board 4 × 6 cm
- Solder tags
- Plugs and screened cable for connecting lead
- Aluminium box

86 A grid dip oscillator

Introduction

When an inductor and a capacitor are connected, whether in series or parallel, they form a circuit with a natural (or *resonant*) frequency. The circuit stores energy, and this energy is being constantly shifted from the inductor to the capacitor and back again.

The dip oscillator is a simple instrument used to measure the resonant frequency of a tuned circuit without having to make any direct connection to the circuit. The circuit is more commonly known as the *grid dip oscillator* (GDO), from the days when the active device in the circuit was a valve. The FET or Field-Effect Transistor operates in a way which is very similar to that of the valve, so it is not quite a misnomer to call this instrument a grid dip oscillator, too.

The circuit

The GDO uses a calibrated, tunable FET oscillator in the circuit of **Figure 1**. It has a frequency range of 1.6 to 35.2 MHz in four ranges using a set of plug-in coils, shown in **Figure 2**. When the oscillator coil, L1, is placed near an external resonant circuit, some of its RF energy is coupled into the external circuit. A gain in energy of the external circuit must mean a loss of energy in the GDO circuit, resulting in a change of current through TR1, which is measured by the meter, M1.

The current through TR1 is of the order of 5 to 8 mA, but the change of current may be only a few microamps. To measure a very small


RFC
1mH
RF out
C8
1n
C9
100n
C1
22p
C4
100p
R2
56R
*
R7
1k
*
R8
5k6
R4
5k6
L1
VC1
2x
365p
*
C10
6p8
RV1
1k
lin
TR1
J304
C3
100p
M1
100μA
meter
+
−
R6
4k7
S1
LED
+
9V
−
C2
22p
D1
1N4148
R1
100k
R3
1k
C5
100n
C6
1n
C7
100n
R5
560R

* These components only required if you want to couple the GDO to a frequency counter

©RSGB DY380

Figure 1 Circuit of an FET GDO. The coils are wound on DIN speater plugs, which provide both a plug-in base and a coil former


L1 winding
(see caption)
2-pin DIN
loudspeaker
plug
©RSGB DY390

Figure 2 Details of coil construction:
Range 1: 1.6–4.0 MHz 55 turns of 30 SWG
Range 2: 3.3–7.9 MHz 27 turns of 30 SWG
Range 3: 6.3–4.0 MHz 14 turns of 26 SWG
Range 4: 11.9–4.0 MHz 7 turns of 24 SWG.

change superimposed on a much larger standing current, the method of *offset* can be used.

One connection to the meter goes to the source of the FET, while the other goes to a variable offset voltage set by VR1. M1 has a full-scale deflection (FSD) of 100 μA. If the current through TR1 changes, the voltage across R3 changes. When there is no resonance, the voltage at the wiper of VR1 is set to be very slightly greater than that across R3, and there is a 75% FSD meter deflection. When the voltage across R3 decreases very slightly, due to external circuit resonance, a significant 'dip' in the meter deflection is produced, hence the name of the instrument.

The circuit is not difficult to make on standard matrix board. Provided you can follow a circuit and translate it into a good component layout, then this project is probably only an evening's work.

The most important part of the GDO is the tuning capacitor and its associated frequency-calibrated dial. New, air-spaced tuning capacitors can cost you up to £20, so it is worth delving around in junk boxes, or scouring the tables at a local boot sale or rally. The tuning capacitor from an old transistor radio should be perfect. It may even have a slow-motion drive and a dial which can be remarked for the project.

Choose a coil plug and socket arrangement that is practical. Think about crystal holders or phono plugs and sockets. The prototype shown in Figure 1 and Figure 2 used 2-pin DIN plugs, with the coil wound on the outside of the plastic plug cover. Figure 2 shows the coil construction and the winding details.

If you use a variable capacitor, VC1, with a value different from that shown in the parts list, then the frequency ranges will be different. This does not matter, as it will be taken into account during calibration.

Position VC1 so that the dial will be easy to see and to operate, while locating the coil socket as close to it as possible. **Figure 3** shows the traditional layout of the GDO.

Calibration

Because the GDO also radiates a very small amount of energy, a general coverage receiver can be used to calibrate the dial. Don't try to aim for great accuracy and clutter the dial with marks and figures! If you include C10, R7 and R8 in your circuit, you can connect a frequency counter directly to the GDO and leave it in circuit all the time.

The GDO in use

Always try to place the external tuned circuit with its coil coaxial with the plug-in coil, as shown in Figs 1 and 3. If the coils are at right angles, the GDO may not produce any resonance. Set the offset control to give about 75% FSD and slowly tune L1 through its whole range. If no dip occurs, you may have the wrong coil plugged in. When you eventually find a dip, move the external coil further away until only a minute dip is seen. You may have to retune the dip meter as you do this, but it gives a much more accurate reading of frequency.

Remember that you cannot 'dip' a coil by itself – there must always be a capacitor present.


Coil
Capacitor
Parallel tuned circuit
Plug-in coil
VC1 with calibrated dial to read frequency
GRID DIP METER
M1 100μA meter
RV1 meter zero control
S1
Power on LED
©RSGB DY381

Figure 3 Layout of a typical GDO. The dial, meter and the location of the coil to the circuit under test can all be viewed at the same time. It is shown measuring resonance of a tuned circuit

Aerial resonance

Figure 4 shows how to check the resonance of a dipole aerial. Disconnect the coax feed at the aerial and place a short piece of wire, terminated with crocodile clips, across the centre insulator to short together the two ends of the aerial. By placing the GDO close to the shorting link, a dip should be seen on the meter while VC1 is turned. Alternatively, a loop in the element can be made around the coil, as in Figure 4, or the shorting link can be made long enough to loop over the coil. The latter method does not require tampering with the mounting and tensioning of the dipole wires.


Coax
disconnected
Loop in antenna
element held
by tape
*
*
Crocodile
clip
* Remove insulation to
allow clips to make
a good connection
Insulator bridged
by wire link
GRID DIP METER
©RSGB DY391

Figure 4 A wire antenna element can be looped into a single turn coil for increased coupling to the GDO

Parts list

Resistors: all 0.25 W, 5% tolerance

R1	100 000 ohms (100 kΩ)
R2	56 ohms (56 Ω)
R3	1000 ohms (1 kΩ)
R4	5600 ohms (5.6 kΩ)
R5	560 ohms (560 Ω)
R6	4700 ohms (4.7 kΩ)
R7	1000 ohms (1 kΩ)
R8	5600 ohms (5.6 kΩ)
VR1	1000 (1 kΩ) linear

Capacitors

C1, C2	22 pF
C3, C4	100 pF
C5, C7, C9	100 nF (0.1 μF)
C6, C8	1 nF (1000 pF)
C10	6.8 pF
VC1	2 × 365 pF

Semiconductors

TR1	J304 or similar
D1	1N4148
LED	

Additional items

L1	See Figure 2
RFC	1 mH
S1	SPST
M1	100 μA

Source

Components are available from Maplin.

87 A CW transmitter for 160 to 20 metres

Introduction

This very small transmitter is designed to work on any band from top band (160 m) to 20 m, with an RF output of 1 W. It will work on higher frequencies but with a reduced output.

The circuit

The three-transistor circuit is shown in **Figure 1**. It comprises a crystal oscillator using a BC182 transistor which drives a 2N3866 power amplifier (PA) keyed by a ZTX750 PNP transistor. The oscillator and PA are coupled by a capacitor and resistor; this provides a very small amount of positive bias to the PA.

The oscillator can be used as a basic crystal oscillator but, by including a variable series capacitor as shown in Figure 1, the crystal frequency can be 'pulled' slightly, making the oscillator a *variable crystal oscillator* (VXO).

Construction

The PCB layout is shown in **Figure 2** and in the photograph. Although the prototype was built around a PCB, this circuit is equally amenable to


33k
100R
100n
BC182
Xtal
100p
1k
Optional
variable
capacitor
100p
1k
100n
RFC
100n
ZTX750
2N3866
33R
33R
100n
1k
100n
47µ
+12V in
To Rx
To
antenna
Key
©RSGB DY396

Figure 1 Transmitter circuit diagram


Output
+9 to
+12V
33k
100
R
100n
10n
RFC
100n
Electrolytic
47μ
ZTX750
100n
1k
Optional
variable
capacitor
BC182
2N3866
1k
100p
100p
Xtal
100n
100n
1k
33R
33R
Key
©RSGB DY397

Figure 2 Component placing on the PCB. The external connections are also shown

construction on a matrix board. Populating the PCB is very simple, and you can expect to be able to do this in about one hour. The radio-frequency choke (RFC) is made by winding 10 turns of 33 SWG wire on a ferrite bead. The enamel coating of the wire is intended to vaporise when soldered into the board, thus obviating the need to remove the enamel manually with a knife or sandpaper. However, if you do have problems with the PA either not working or keying intermittently, it is suggested that you investigate the RFC connections immediately!

If you decide to make the VXO version, you will have to cut the track between the crystal and earth, and connect the variable capacitor (250 pF) across the break.

In use

After performing the usual checks on the accuracy of your circuit building and the wiring of the external components, it is time to connect a 12 V battery between the points shown in Figure 2. Do not switch on yet. An aerial needs to be connected to the output via an ATU and a crystal, of frequency matching that of the aerial, fitted. The variable capacitor should give you a tuning range from about 14.058 to 14.064 MHz. ‘Netting’ (the process of tuning your transmitter to the same frequency as that of a received station) is achieved simply, because the oscillator is always running, and the leakage of the signal (despite the fact that the PA is not powered) is sufficient to bring the two frequencies to zero beat.





Warning

Note that the transmitter has no filtering; harmonics are not suppressed. It is strongly recommended that you use this transmitter in conjunction with the excellent low-pass filter described in the project *A 7-element low-pass filter for transmitters*, described elsewhere in this book.

88 Matching the end-fed random-wire aerial

Introduction

Many amateurs who do not have the space (or money) for a multi-band beam aerial, make use of the simplest possible alternative – the longest piece of wire that they can erect, with its end connected to the transceiver or receiver by an aerial tuning unit (ATU).

The length of the wire is not of major importance. Any length between 10 m and 80 m, with bends if necessary, will suffice. A good earth connection to the radio is just as important. Bends in the aerial wire can have some interesting effects on the directional properties of the aerial; V- or L-bends, or even a square shape are permitted. The only thing *not* permitted is to fold the wire back on itself in a tight hairpin bend!

Longish wire aerials

The term ‘long wire’ is usually used (incorrectly) to describe an end-fed aerial. How long is a piece of string? It depends what you mean by ‘long’. In aerial parlance, it means ‘long with respect to one wavelength’. Again, this depends on the band you are using. A long wire at 20 m is somewhat different from a long wire at 160 m. However, if you have sufficient real estate for a long wire on the 160 m band it must, by definition, be a long wire on all the other bands, too!

This should put you on your guard when analysing published data about feed-point impedance and the directional properties of a long wire aerial. Such theoretical data relate to a *real*, *ideal* long wire which is straight, horizontal, very high above perfect (conducting) ground, and not obstructed in any way. So your aerial doesn't quite match these criteria? Join the club!

Don't let this dampen your ardour when it comes to evaluating what the longish wire can do for you. The following should explain why.

Feed-point impedance

The impedance at the end of a longish-wire aerial can vary from a few tens of ohms to several thousand ohms, depending on the frequency in use and the wire length. It is also affected by factors such as bends, height above ground, proximity to buildings and wire diameter.

The actual value doesn't matter, provided we can make the aerial *appear* to have a 50 Ω impedance at the aerial socket of the transmitter. This process is what we call *impedance matching*, or simply *matching*. It maximises the power transfer from the transmitter to the aerial, and from the aerial to the receiver.

That is why an aerial tuning unit, or ATU, is almost (but not necessarily) obligatory.

The ATU

Many commercially produced HF receivers and transceivers have single 50 Ω coaxial sockets as their one and only means for connecting an external aerial. This means that an external aerial should have a 50 Ω feed impedance if it is to work efficiently, and it rules out most of the aerials being used by amateurs on the HF bands. Some means is necessary to change the aerial feed impedance to 'match' that of the transceiver. Such impedance-matching, or Z-matching (because Z is the symbol for impedance, just as L is the symbol for inductance) is the rôle of the ATU.

These can be bought and will accommodate either an end-fed or a coax-fed aerial. They can be bought ready for use or in kit form. Whether you want one for receiving only, or for use with a low-power (QRP) or high-power (QRO) transmitter, will determine what you need and how much you pay.

A simple single-band ATU

The simplest form of ATU is shown in **Figure 1**. It is simply a parallel LC (coil and capacitor) circuit, resonant at the chosen frequency, with taps on the coil for the aerial and the coaxial feed to the transceiver. If we assume the circuit is resonant, a high impedance exists at the top of the coil, and a low impedance at the bottom.

We said earlier that the end-fed longish wire presented an impedance which was high (or at least higher than 50 Ω). This explains why the aerial is tapped to the coil near the top, where the impedance is high, and the 50 Ω coax is tapped near the bottom, where the impedance is low.



Figure 1 Parallel tuned circuit as single-band ATU for end-fed longish-wire antenna

Because the feed-point impedance of the aerial changes with frequency, so must the point at which the aerial is tapped to the coil to achieve impedance matching. The value of C must be changed also, to ensure that the circuit is resonant, and the 50 Ω tap will require tweaking also.

Setting up an ATU is quite simple. Make up an LC parallel-tuned circuit consisting of 50 turns of enamelled copper wire on an empty 35 mm film plastic container (or similar), tuned with a 500 pF variable capacitor. Make sure the enamel is removed from the ends of the wire before soldering.

Solder the inner wire of the coaxial cable from the radio to the first or second turn of the coil from its grounded end. Then solder the braid to the grounded end. Connect the aerial about one-third of the way down the coil from the top, removing the enamel at the connection point.

Adjust the variable capacitor for maximum noise or signal strength in the receiver. Then, try different tapping points from the aerial, to maximise the signal again. This matches the aerial impedance to that of the tuned circuit. Repeat the process with the coax tap, thus matching the impedance of the radio and the cable to that of the tuned circuit.

You will no doubt find that the tapping process on the coil was not easily accomplished, especially when the enamel must be removed at each tapping point without shorting adjacent turns together. It is therefore logical to produce a design where the taps have been prepared during the winding of the coil, and are selected with a rotary switch. To this end, the following multi-band design is described.

A multi-band ATU

The same type of coil design around a 35 mm film container is used (see **Figure 2**). The tapping points can be prepared in advance by a little judicious planning. Dismantle your original coil and measure the length of wire on it. It will be a little more than a calculation of $50 \times \pi D$ would suggest (where D is the diameter of the film container), due to the lack of tension in the coil and the wire diameter itself. You will need aerial tapping points at turns 1, 2, 3, 5, 10, 15, 20, 25, 30, 35, 40 and 45, corresponding to all the bands from 28 MHz to 1.8 MHz. The coaxial cable tap is fixed at turn 2 (an acceptable compromise). All the turns are counted from the earthy end.

Cut another piece of enamelled copper the same length as you used originally. Then, with the aid of an ordinary calculator, work out the positions of the points where the enamel must be removed for the taps. For example, turn 15 will have to be made $\frac{15}{50}$ of the way along the wire, turn 20 tap made at $\frac{20}{50}$ of the way along. So, if the length of wire is, say 4.7 metres, the two taps in question will be made at $\frac{15}{50} \times 4.7 = 1.41$ m and $\frac{20}{50} \times 4.7 = 1.88$ m from one end. This must be repeated for each of the tap positions, and the enamel removed ready for the wire to be soldered to it. With a



Figure 2 Simple multi-band ATU for end-fed longish-wire antennas

soldering iron, tin each tap point while the copper is shiny, thus ensuring a good, low-resistance connection. Do not solder on the taps yet.

The coil can now be wound as before. The taps can be soldered on, taking the lead from each one to the wafer of a single-pole 12-way rotary switch, the pole being connected to the aerial.

The tuning of the ATU is carried out by the same 250 pF capacitor, with a single-pole 5-way rotary switch used to select the band. Its tapping points will need to be chosen manually, using the method described earlier. Don't attempt to make new tapping points on the coil for this – use the taps available on the wafer of the other rotary switch, and find which is optimum for each band.

Notes

- For the aerial, use PVC-covered stranded tinned copper, of size 16/0.2 mm or 24/0.2 mm.
- Make the wire as long as possible, but anything over 10 m should be OK.
- Keep the wire as high as you can, in the clear and away from obstructions.
- Don't worry about bends, but don't use hairpin bends.
- Use a good insulator to attach your aerial – anything plastic will do.
- Anchor the wire near the point of entry to the building, but use a U-bend to prevent ingress of water.
- The wire can be brought in through the corner of a window, the PVC acting as an insulator. If you must drill a hole in the brickwork, make sure it slopes upwards from outside, so that water is deterred from entering.
- Use a good RF earth (as opposed to an electrical earth) such as half a dozen bare copper wires buried under the lawn in a fan shape. They should be joined together at the point of the fan and strapped to the earth connector of your ATU.

Antenna Technology

Zana Lane

First Edition, 2012

ISBN 978-81-323-3025-7

© All rights reserved.

Published by:
Research World
4735/22 Prakashdeep Bldg,
Ansari Road, Darya Ganj,
Delhi - 110002
Email: info@wtbooks.com

Table of Contents

Chapter 1 - Dipole Antenna

Chapter 2 - Horn Antenna

Chapter 3 - Radio Telescope

Chapter 4 - Parabolic Antenna

Chapter 5 - Antenna (Radio)

Chapter 6 - Television Antenna

Chapter 7 - Radio Masts and Towers

Chapter 8 - Omnidirectional Antenna & Directional Antenna

Chapter 1

Dipole Antenna



A schematic of a half-wave dipole antenna that a shortwave listener might build.

A **dipole antenna** is a radio antenna that can be made of a simple wire, with a center-fed driven element. It consists of two metal conductors of rod or wire, oriented parallel and collinear with each other (in line with each other), with a small space between them. The radio frequency voltage is applied to the antenna at the center, between the two conductors. These antennas are the simplest practical antennas from a theoretical point of view. They are used alone as antennas, notably in traditional "rabbit ears" television antennas, and as the driven element in many other types of antennas, such as the Yagi. Dipole antennas were invented by German physicist Heinrich Hertz around 1886 in his pioneering experiments with radio waves.



Electric fields *(blue)* and magnetic fields *(red)* radiated by a dipole antenna

Elementary doublet



An elementary doublet is a small length of conductor $\delta\ell$(small compared to the wavelength λ) carrying an alternating current:

$$I = I_0 e^{i\omega t}.$$

Here $\omega = 2\pi f$is the angular frequency (and $f$the frequency), and $i$is $\sqrt{-1}$, so that $I$is a phasor.

Note that this dipole cannot be physically constructed because the current needs somewhere to come from and somewhere to go to. In reality, this small length of conductor will be just one of the multiple segments into which we must divide a real antenna, in order to calculate its properties. The interest of this imaginary elementary antenna is that we can easily calculate the electrical far field of the electromagnetic wave radiated by each elementary doublet. We give just the result:

$$E_\theta = \frac{-i I_\circ \sin\theta}{2\varepsilon_\circ c r}\frac{\delta l}{\lambda} e^{i(\omega t - kr)}$$

Where,

- E_θ is the far electric field of the electromagnetic wave radiated in the θ direction.
- ε_0 is the permittivity of vacuum.
- c is the speed of light in vacuum.
- r is the distance from the doublet to the point where the electrical field E_θ is evaluated.
- k is the wavenumber $k=\frac{2\pi}{\lambda}$

The exponent of e accounts for the phase dependence of the electrical field on time and the distance from the dipole.

The far electric field E_θ of the electromagnetic wave is coplanar with the conductor and perpendicular with the line joining the dipole to the point where the field is evaluated. If the dipole is placed in the center of a sphere in the axis south-north, the electric field would be parallel to geographic meridians and the magnetic field of the electromagnetic wave would be parallel to geographic parallels.

Near Field

The above formulas are valid for the far field of the antenna ($r \gg \lambda/(2\pi)$), and are the only contribution to the radiated field. The formulas in the near field have additional terms that reduce with r^2 and r^3. These are,

$$E_r = \frac{Z}{2\pi} I_0\, \delta l \left(\frac{1}{r^2} - i\,\frac{\lambda}{2\pi r^3}\right) e^{i(\omega t - kr)}\ \cos(\theta)$$

$$E_\theta = i\frac{Z}{2\lambda} I_0\, \delta l \left(\frac{1}{r} - i\,\frac{\lambda}{2\pi r^2} - \frac{\lambda^2}{4\pi^2 r^3}\right) e^{i(\omega t - kr)}\ \sin(\theta)$$

$$H_\phi = i\frac{1}{2\lambda} I_0\, \delta l \left(\frac{1}{r} - i\,\frac{\lambda}{2\pi r^2}\right) e^{i(\omega t - kr)}\ \sin(\theta)$$

where $Z = \sqrt{\mu/\epsilon} = 1/(\epsilon c) = \mu c$. The energy associated with the term of the near field flows back and forward out and into the antenna.

Short dipole



A short dipole is a physically feasible dipole formed by two conductors with a total length Lvery small compared with the wavelength λ. The two conducting wires are fed at the centre of the dipole. We assume the hypothesis that the current is maximal at the centre (where the dipole is fed) and that it decreases linearly to be zero at the ends of the wires. Note that the direction of the current is the same in both the dipole branches - to the right in both or to the left in both. The far field $E_\theta$of the electromagnetic wave radiated by this dipole is:

$$E_\theta = \frac{-i I_0 \sin\theta}{4\epsilon_0 c r}\frac{L}{\lambda}e^{i(\omega t - kr)}.$$





Emission is maximal in the plane perpendicular to the dipole and zero in the direction of wires which is the direction of the current. The emission diagram is circular section torus shaped (right image) with zero inner diameter. In the left image the doublet is vertical in the torus centre.

Knowing this electric field, we can compute the total emitted power and then compute the resistive part of the series impedance of this dipole due to the radiated field, known as the radiation resistance:

$$R_{series} = \frac{\pi}{6} Z_0 \left(\frac{L}{\lambda}\right)^2 \text{ (for } L \ll \lambda\text{).}$$

where Z_0 is the impedance of free space. Using a common approximation of $Z_0 = 120\pi$ ohms, we get:

$$R_{series} = 20\pi^2 \left(\frac{L}{\lambda}\right)^2 \text{ ohms}$$

Antenna gain

Antenna gain is the ratio of surface power radiated by the antenna to the surface power radiated by a hypothetical isotropic antenna:

$$G = \frac{\left(\frac{P}{S}\right)_{ant}}{\left(\frac{P}{S}\right)_{iso}}$$

The surface power carried by an electromagnetic wave is:

$$\left(\frac{P}{S}\right)_{ant} = \frac{1}{2} c\epsilon_0 E_\theta^2 \simeq \frac{1}{120\pi} E_\theta^2$$

The surface power radiated by an isotropic antenna feed with the same power is:

$$\left(\frac{P}{S}\right)_{iso} = \frac{\frac{1}{2} R_{series} I_0^2}{4\pi r^2}$$

Substituting values for the case of a short dipole, final result is:

$$G = \frac{\pi\left(\frac{L}{\lambda}\right)^2}{c\epsilon_0 \frac{2\pi}{3\epsilon_0 c}\left(\frac{L}{\lambda}\right)^2} = 1.5 = 1.76 \text{ dBi}$$

dBi simply means decibels gain, relative to an **i**sotropic antenna.

Half-wave antenna



Typically a dipole antenna is formed by two quarter wavelength conductors or elements placed back to back for a total length of $\lambda/2$. A standing wave on an element of a length ~$\lambda/4$ yields the greatest voltage differential, as one end of the element is at a node while the other is at an antinode of the wave. The larger the differential voltage, the greater the current between the elements.



Assuming a sinusoidal distribution, the current impressed by this voltage differential is given by:

$$I = I_\circ e^{i\omega t} \cos k\ell$$

For the far-field case, the formula for the electric field of a radiating electromagnetic wave is somewhat more complex:

$$E_\theta = \frac{-iI_\circ}{2\pi\varepsilon_\circ cr} \frac{\cos\left(\frac{\pi}{2}\cos\theta\right)}{\sin\theta} e^{i(\omega t - kr)}$$

But the fraction $\frac{\cos\left(\frac{\pi}{2}\cos\theta\right)}{\sin\theta}$ is not very different from $\sin\theta$.

The resulting emission diagram is a slightly flattened torus.





The image on the left shows the section of the emission pattern. We have drawn, in dotted lines, the emission pattern of a short dipole. We can see that the two patterns are very similar. The image at right shows the perspective view of the same emission pattern.

This time it is not possible to compute analytically the total power emitted by the antenna (the last formula does not allow), though a simple numerical integration or series expansion leads to the more precise, actual value of the half-wave resistance:

$$R_{\frac{\lambda}{2}} = 60\mathrm{Cin}(2\pi) = 60\left[\ln(2\pi\gamma) - \mathrm{Ci}(2\pi)\right] = 120\int_0^{\frac{\pi}{2}} \frac{\cos\left(\frac{\pi}{2}\cos\theta\right)^2}{\sin\theta}d\theta,$$
$$= 15\left[2\pi^2 - \frac{1}{3}\pi^4 + \frac{4}{135}\pi^6 - \frac{1}{630}\pi^8 + \frac{4}{70875}\pi^{10} \ldots - (-1)^n\frac{(2\pi)^{2n}}{n(2n)!}\right],$$
$$\approx 73.13\Omega;$$

This leads to the gain of a dipole antenna, $G_{\frac{\lambda}{2}}$:

$$G_{\frac{\lambda}{2}} - \frac{60^2}{30R_{\frac{\lambda}{2}}} - \frac{3600}{30R_{\frac{\lambda}{2}}} - \frac{120}{R_{\frac{\lambda}{2}}} - \frac{1}{\int_0^{\frac{\pi}{2}} \frac{\cos\left(\frac{\pi}{2}\cos\theta\right)^2}{\sin\theta}d\theta},$$
$$\approx \frac{120}{73.1296} \approx 1.64 \approx 2.15\,\mathrm{dBi};$$

The resistance, however, is not enough to characterize the dipole impedance, as there is also an imaginary part——it is better to measure the impedance.

In the image below, the real and imaginary parts of a dipole's impedance are drawn for lengths going from $0.4\ \lambda$ to $0.6\ \lambda$, accompanied by a chart comparing the gains of dipole antennas of other lengths (note that gains are **not** in dBi but in natural number):


SCHWARZB
λ/2-Dipo
1.5 - 3 (4)
UHA 9125

UHF–Half–Wave Dipole, 1.0–4 GHz



Gain of dipole antennas

length **L** in λ	Gain	Gain(dB)
≪0.1	1.50	1.76dB
0.5	**1.64**	**2.15dB**
1.0	1.80	2.55dB
1.5	2.00	3.01dB
2.0	2.30	3.62dB
3.0	2.80	4.47dB
4.0	3.50	5.44dB
8.0	7.10	8.51dB

Quarter-wave antenna



The antenna and its image form a $\frac{\lambda}{2}$dipole that radiates only upward.

The quarter wave monopole antenna is a single element antenna fed at one end, that behaves as a dipole antenna. It is formed by a conductor $\frac{\lambda}{4}$ in length. It is fed in the lower end, which is near a conductive surface which works as a reflector. The current in the reflected image has the same direction and phase as the current in the real antenna. The quarter-wave conductor and its image together form a half-wave dipole that radiates only in the upper half of space.

In this upper side of space the emitted field has the same amplitude of the field radiated by a half-wave dipole fed with the same current. Therefore, the total emitted power is one-half the emitted power of a half-wave dipole fed with the same current. As the current is the same, the radiation resistance (real part of series impedance) will be one-half of the series impedance of a half-wave dipole. As the reactive part is also divided by 2, the impedance of a quarter wave antenna is $\frac{73+i43}{2}=36+i21$ohms. Since the fields above ground are the same as for the dipole, but only half the power is applied, the gain is twice (3dB over) that for a half-wave dipole ($\frac{\lambda}{2}$), that is 5.14 dBi.

The earth can be used as ground plane, but it is a poor conductor: the reflected antenna image is only clear at glancing angles (far from the antenna). At these glancing angles, electromagnetic fields and radiation patterns are thus the same as for a half-wave dipole.

Naturally, the impedance of the earth is far inferior to that of a good conductor ground plane -- this can be improved (at cost) by laying a copper mesh.

When ground is not available (such as in a vehicle) other metallic surfaces can serve as a ground plane (typically the vehicle's roof). Alternatively, radial wires placed at the base of the antenna can simulate a ground plane. For VHF bands, the radiating and ground-plane elements can be constructed from rigid rods or tubes.

Dipole characteristics

Frequency versus length

Dipoles that are much smaller than the wavelength of the signal are called *Hertzian, short, or infinitesimal dipoles*. These have a very low radiation resistance and a high reactance, making them inefficient, but they are often the only available antennas at very long wavelengths. Dipoles whose length is half the wavelength of the signal are called *half-wave dipoles*, and are more efficient. In general radio engineering, the term *dipole* usually means a half-wave dipole (center-fed).

A half-wave dipole is cut to length l for frequency f MHz according to the formula $l = \frac{143}{f}$ where l is in metres or $l = \frac{468}{f}$ where l is in feet. This is because the impedance of the dipole is resistive pure at about this length. The length of the dipole antenna is about 95% of half a wavelength at the speed of light in free space.

The magic numbers above are derived from a one Hz wavelength which is the distance that light radio travels in one second. Speed of light in vacuum is 299,792,458 m/s, which is divided by 1 million to account for MHz rather than Hz, which is then divided by 2 for a half-wave dipole antenna. A fudge factor of approximately 0.95 is multiplied to account for the damping due to radiation, which results in the magic number of 143 m·MHz or 468 ft·MHz.

Radiation pattern and gain

Dipoles have an omnidirectional radiation pattern, shaped like a toroid (doughnut) symmetrical about the axis of the dipole. The radiation is maximum at right angles to the dipole, dropping off to zero on the antenna's axis. The theoretical maximum gain of a Hertzian dipole is 10 log 1.5 or 1.76 dBi. The maximum theoretical gain of a λ/2-dipole is 10 log 1.64 or 2.15 dBi.



Radiation pattern of a half-wave dipole antenna. The scale is linear.



Gain of a half-wave dipole (same as left). The scale is in dBi (decibels over isotropic).

Feeder line

Ideally, a half-wave (λ/2) dipole should be fed with a balanced line matching the theoretical 73 ohm impedance of the antenna. A folded dipole uses a 300 ohm balanced feeder line.

Many people have had success in feeding a dipole directly with a coaxial cable feed rather than a ladder-line. However, coax is not symmetrical and thus not a balanced feeder. It is unbalanced, because the outer shield is connected to earth potential at the other end. When a balanced antenna such as a dipole is fed with an unbalanced feeder, common mode currents can cause the coax line to radiate in addition to the antenna itself, and the radiation pattern may be asymmetrically distorted. This can be remedied with the use of a balun.

Common applications

Set-top TV antenna



A "rabbit-ears" antenna with a UHF loop antenna.

The most common dipole antenna is the type used with televisions, often colloquially referred to as "**rabbit ears**" or "**bunny ears**." While in most applications the dipole elements are arranged along the same line, rabbit ears are adjustable in length and angle. Larger dipoles are sometimes hung in a V shape with the center near the radio equipment on the ground or the ends on the ground with the center supported. Shorter dipoles can be hung vertically. Some have extra elements to get better reception such as loops (especially for UHF transmissions), which can be turnable around a vertical axis, or a dial, which modifies the electrical properties of the antenna at each dial position.

Folded dipole



Folded dipole antenna

Another common place one can see dipoles is as antennas for the FM band - these are folded dipoles. The tips of the antenna are folded back until they almost meet at the feedpoint, such that the antenna comprises one entire wavelength. This arrangement has a greater bandwidth than a standard half-wave dipole. If the conductor has a constant radius and cross-section, at resonance the input impedance is four times that of a half-wave dipole.

Shortwave antenna

A DIY-made dipole antenna with mast

Dipoles for longer wavelengths are made from solid or stranded wire. Portable dipole antennas are made from wire that can be rolled up when not in use. Ropes with weights on the ends can be thrown over supports such as tree branches and then used to hoist up the antenna. The center and the connecting cable can be hoisted up with the ends on the ground or the ends hoisted up between two supports in a V shape. While permanent antennas can be trimmed to the proper length, it is helpful if portable antennas are adjustable to allow for local conditions when moved. One easy way is to fold the ends of the elements to form loops and use adjustable clamps. The loops can then be used as attachment points.

It is important to fit a good insulator at the ends of the dipole, as failure to do so can lead to a flashover if the dipole is used with a transmitter. Various purchased or improvised insulators can be used.

Whip antenna

The whip antenna is probably the most common and simplest-looking antenna. These are monopoles, and the most common and practical is the quarter-wave monopole which could be considered as half of a dipole using a ground plane as the image of the other half. The commonly referred-to end-fed dipole is actually just a half-wave monopole whip antenna.

Dipoles versus whip antennas

Dipoles are generally more efficient than whip antennas (quarter-wave monopoles). The total radiated power and the radiation resistance are twice that of a quarter-wave monopole. Thus, if a whip antenna were used with an infinite perfectly conducting ground plane, then it would be as efficient in half-space as a dipole in free space an infinite distance from any conductive surfaces such as the earth's surface.

Dipole towers

Large constructed half-wavelength dipole towers include the Warsaw radio mast — the only half-wave dipole for longwave ever built — and Blaw-Knox Towers.

Military

US Military personnel occasionally use a 'doublet' antenna, especially during dismounted unconventional warfare. A radio operator may choose to bring several doublet antennas for different frequencies, such as an antenna cut to length for the set MEDEVAC (medical evacuation) frequency, NCS (net control station) frequency, and tactical frequency (the frequency used by troops in the field). This approach may not be acceptable depending on the mission. Note that a doublet antenna will not work with the standard SINCGARS radio when using frequency hopping(FH) but is effective for single channel (SC). A doublet antenna is more practical for radios not intended for FH.

Collinear antenna systems based on dipoles



J-Pole Antenna

Dipoles can be stacked end to end in phased arrays to make collinear antenna arrays, which exhibit more gain in certain directions—the toroidal radiation pattern is flattened out, giving maximum gain at right angles to the axis of the colinear array.

Slim Jim or J-pole

A Slim Jim or J-pole is a form of end-fed dipole connected to a quarter-wave stub matching section.

Dipole types

Ideal half-wavelength dipole

This type of antenna is a special case where each wire is exactly one-quarter of the wavelength, for a total of a half wavelength. The radiation resistance is about 73 ohms if wire diameter is ignored, making it easily matched to a coaxial transmission line. The directivity is a constant 1.64, or 2.15 dB. Actual gain will be a little less due to ohmic losses.

If the dipole is not driven at the centre then the feed point resistance will be higher. If the feed point is distance *x* from one end of a half wave (λ/2) dipole, the resistance will be described by the following equation.

$$R_r = \frac{75}{\sin^2\left(\frac{2\ \pi\ x}{\lambda}\right)}$$

If taken to the extreme then the feed point resistance of a $\lambda/2$ long rod is infinite, but it is possible to use a $\lambda/2$ pole as an aerial; the right way to drive it is to connect it to one terminal of a parallel LC resonant circuit. The other side of the circuit must be connected to the braid of a coaxial cable lead and the core of the coaxial cable can be connected part way up the coil from the RF ground side. An alternative means of feeding this system is to use a second coil which is magnetically coupled to the coil attached to the aerial.

Folded dipole

A folded dipole is a half-wave dipole with an additional wire connecting its two ends. If the additional wire has the same diameter and cross-section as the dipole, two nearly identical radiating currents are generated. The resulting far-field emission pattern is nearly identical to the one for the single-wire dipole described above; however, at resonance its input (feedpoint) impedance R_{df} is four times the radiation resistance of a single-wire dipole. This is because for a fixed amount of power, the total radiating current I_0 is equal to twice the current in each wire and thus equal to twice the current at the feed point. Equating the average radiated power to the average power delivered at the feedpoint, we may write

$$\frac{1}{2}R_{\frac{\lambda}{2}}I_0^2 = \frac{1}{2}R_{fd}\left(I_0/2\right)^2 .$$

It follows that

$$R_{fd} = 4R_{\frac{\lambda}{2}} = 292.52\Omega.$$

The folded dipole is therefore well matched to 300-Ohm balanced transmission lines.

Hertzian dipole (current element)

The Hertzian dipole is a theoretical short dipole (significantly smaller than the wavelength) with a uniform current along its length. A true Hertzian dipole cannot physically exist, since the assumed current distribution implies an infinite accumulation of charge at its ends.

The radiation resistance is given by:

$$R_r = \frac{2\pi}{3}Z_0\left(\frac{\ell}{\lambda}\right)^2 .$$

where Z_0 is the impedance of free space. This is precisely four times the radiation resistance of the real short dipole with the linearly tapered current distribution.

The radiation resistance is typically a fraction of an ohm, making the infinitesimal dipole an inefficient radiator. The directivity D, which is the theoretical gain of the antenna assuming no ohmic losses (not real-world), is a constant of 1.5, which corresponds to

1.76 dB. Actual gain will be much less due to the ohmic losses and the loss inherent in connecting a transmission line to the antenna, which is very hard to do efficiently considering the incredibly low radiation resistance. The maximum effective aperture is:

$$A_e = \frac{3\lambda^2}{8\pi}$$

A surprising result is that even though the Hertzian dipole is minute, its effective aperture is comparable to antennas many times its size.

Dipole as a reference standard

Antenna gain is sometimes measured as "*x* dB above a dipole", which means that the antenna in question is being compared to a dipole, and has *x* dB more gain (has more directivity) than the dipole tuned to the same operating frequency. In this case one says the antenna has a gain of "*x* dBd". More often, gains are expressed relative to an isotropic radiator, which is an imaginary aerial that radiates equally in all directions. In this case one uses dBi instead of dBd. As it is impossible to build an isotropic radiator, gain measurements expressed relative to a dipole are more practical when a reference dipole aerial is used for experimental measurements. 0 dBd is often considered equal to 2.15 dBi.

From Babinet's principle, a dipole antenna is complementary to a slot antenna consisting of a slot the same size and shape as a dipole cut from an infinite sheet of metal; both give the same radiation pattern.

Dipole with baluns



Coax and antenna both acting as radiators instead of only the antenna.

A dipole, being composed of two symmetrical ungrounded elements, works best when fed by a balanced transmission line, such as ladder line. When a dipole with an unbalanced feedline such as coaxial cable is used for transmitting, the shield side of the cable, in addition to the antenna, radiates. This can induce RF currents into other electronic equipment near the radiating feedline, causing RF interference. Furthermore, the antenna is not as efficient as it could be because it is radiating closer to the ground and its radiation (and reception) pattern may be distorted asymmetrically. At higher frequencies, where the length of the dipole becomes significantly shorter than the diameter of the feeder coax, this becomes a more significant problem. To prevent this, dipoles fed by coaxial cables have a balun between the cable and the antenna, to convert the unbalanced signal provided by the coax to a balanced symmetrical signal for the antenna.

Several type of baluns are commonly used to transmit on a dipole: current baluns and coax baluns.

Current balun



Dipole with a current balun.

A current balun is a bit more expensive but has the characteristic of being more broadband. It can also be as simple as winding the coax cable over a ferrite core. Or nothing but coax cable:

Coax balun



Here is a dipole using a coax balun.

A coax balun is a cost effective method to eliminate feeder radiation, but is limited to a narrow set of operating frequencies.

- One easy way to make a balun is a (λ/2) length of coaxial cable. The inner core of the cable is linked at each end to one of the balanced connections for a feeder or dipole. One of these terminals should be connected to the inner core of the coaxial feeder. All three braids should be connected together. This then forms a 4:1 balun which works correctly at only a narrow band of frequencies.

Sleeve balun



Here is a dipole using a sleeve balun.

At VHF frequencies, a sleeve balun can also be built to remove feeder radiation.

- Another narrow band design is to use a λ/4 length of metal pipe. The coaxial cable is placed inside the pipe; at one end the braid is wired to the pipe while at the other end no connection is made to the pipe. The balanced end of this balun is at the end where the pipe is wired to the braid. The λ/4 conductor acts as a transformer converting the infinite impedance at the unconnected end into a zero impedance at the end connected to the braid. Hence any current entering the balun through the connection, which goes to the braid at the end with the connection to the pipe, will flow into the pipe. This balun design is impractical for low frequencies because of the long length of pipe that will be needed.

Chapter 2

Horn Antenna



Pyramidal microwave horn antenna, with a bandwidth of 0.8 to 18 GHz. A coaxial cable feedline attaches to the connector visible at top. This type is called a ridged horn; the curving fins visible inside the mouth of the horn increase the antenna's bandwidth.

A **horn antenna** or **microwave horn** is an antenna that consists of a flaring metal waveguide shaped like a horn to direct the radio waves. Horns are widely used as antennas at UHF and microwave frequencies, above 300 MHz. They are used as feeders (called feed horns) for larger antenna structures such as parabolic antennas, as standard calibration antennas to measure the gain of other antennas, and as directive antennas for such devices as radar guns, automatic door openers, and microwave radiometers. Their advantages are moderate directivity (gain), low SWR, broad bandwidth, and simple construction and adjustment.

One of the first horn antennas was constructed in 1897 by Indian radio researcher Jagadish Chandra Bose in his pioneering experiments with microwaves. In the 1930s the first experimental research (Southworth and Barrow, 1936) and theoretical analysis (Barrow and Chu, 1939) of horns as antennas was done. The development of radar in World War 2 stimulated horn research. The corrugated horn proposed by Kay in 1962 has become widely used as a feed horn for microwave antennas such as satellite dishes and radio telescopes.

An advantage of horn antennas is that since they don't have any resonant elements, they can operate over a wide range of frequencies, a wide bandwidth. The useable bandwidth of horn antennas is typically of the order of 10:1, and can be up to 20:1 (for example allowing it to operate from 1 GHz to 20 GHz). The input impedance is slowly-varying over this wide frequency range, allowing low VSWR over the bandwidth. The gain of horn antennas ranges up to 25 dBi, with 10 - 20 dBi being typical.

Description

A horn antenna is used to transmit radio waves from a waveguide (a metal pipe used to carry radio waves) out into space, or collect radio waves into a waveguide for reception. It typically consists of a short length of rectangular or cylindrical metal tube (the waveguide), closed at one end, flaring into an open-ended conical or pyramidal shaped horn on the other end. The radio waves are usually introduced into the waveguide by a coaxial cable attached to the side, with the central conductor projecting into the waveguide. The waves then radiate out the horn end in a narrow beam. However in some equipment the radio waves are conducted from the transmitter or to the receiver by a waveguide, and in this case the horn is just attached to the end of the waveguide.

How it works



Corrugated conical horn antenna used as a feed horn on a Hughes Direcway home satellite dish.

A horn antenna serves the same function for electromagnetic waves that an acoustical horn does for sound waves in a musical instrument such as a trumpet; it provides a gradual transition structure to match the impedance of a tube to the impedance of free space, enabling the waves from the tube to radiate efficiently into space.

If a simple open-ended waveguide were to be used as an antenna, without the horn, the sudden end of the conductive walls causes an abrupt impedance change at the aperture, from the characteristic impedance of the waveguide to the impedance of free space, 377 ohms. When radio waves travelling through the waveguide hit the opening, it acts as a bottleneck, reflecting most of the wave energy back down the guide toward the source, so only part of the power is radiated. It acts similarly to an open-circuited transmission line, or to a boundary between optical mediums with a high and low index of refraction, like a glass surface. The reflected waves cause standing waves in the waveguide, increasing the VSWR, wasting energy and possibly overheating the transmitter. In addition, the small aperture of the waveguide (around one wavelength) causes severe diffraction of the waves issuing from it, resulting in a wide radiation pattern without much directivity.

To improve these poor characteristics, the ends of the waveguide are flared out to form a horn. The taper of the horn changes the impedance gradually along the horn's length. This acts like an impedance matching transformer, allowing most of the wave energy to radiate out the end of the horn into space, with minimal reflection. The taper functions similarly to a tapered transmission line, or an optical medium with a smoothly-varying refractive index. In addition, the wide aperture of the horn projects the waves in a narrow beam

The horn shape that gives minimum reflected power is an exponential taper. Exponential horns are used in special applications that require minimum signal loss, such as satellite antennas and radio telescopes. However conical and pyramidal horns are most widely used, because they have straight sides and are easier to fabricate.

Radiation pattern

The waves travel down a horn as spherical wavefronts, with their origin at the apex of the horn. The pattern of electric and magnetic fields at the aperture plane of the horn, which determines the radiation pattern, is a scaled-up reproduction of the fields in the waveguide. However, because the wavefronts are spherical, the phase increases smoothly from the center of the aperture plane to the edges, because of the difference in length of the center point and the edge points from the apex point. The difference in phase between the center point and the edges is called the *phase error*. This phase error, which increases with the flare angle, reduces the gain and increases the beamwidth, giving horns wider beamwidths than plane-wave antennas such as parabolic dishes.

At the flare angle, the radiation of the beam lobe is down about -20 dB from its maximum value.

The increasing phase error limits the aperture size of practical horns to about 15 wavelengths; larger apertures would require impractically long horns. This limits the gain of practical horns to about 1000 (30 dB) and the corresponding minimum beamwidth to about 5 - 10°.

Optimum horn

Large pyramidal horn used in 1951 to detect the 21 cm (1.43 GHz) radiation from hydrogen gas in the Milky Way galaxy.

For a given frequency and horn length, there is some flare angle that gives minimum reflection and maximum gain. The reflections in straight-sided horns come from the two locations along the wave path where the impedance changes abruptly; the mouth or aperture of the horn, and the throat where the sides begin to flare out. The amount of reflection at these two sites varies with the *flare angle* of the horn (the angle the sides make with the axis). In narrow horns with small flare angles most of the reflection occurs at the mouth of the horn. The gain of the antenna is low because the small mouth approximates an open-ended waveguide. As the angle is increased, the reflection at the mouth decreases rapidly and the antenna's gain increases. In contrast, in wide horns with flare angles approaching 90° most of the reflection is at the throat. The horn's gain is again low because the throat approximates an open-ended waveguide. As the angle is decreased, the amount of reflection at this site drops, and the horn's gain again increases.

This discussion shows that there is some flare angle which gives maximum gain and minimum reflection. This is called the *optimum horn*. Most practical horn antennas are designed as optimum horns. In a pyramidal horn, the dimensions that give an optimum horn are:

$$a_E = \sqrt{3\lambda L_E} \qquad a_H = \sqrt{2\lambda L_H}$$

For a conical horn, the dimensions that give an optimum horn are:

$$d = \sqrt{3\lambda L}$$

where

a_E is the width of the aperture in the E-field direction
a_H is the width of the aperture in the H-field direction
L_E is the slant length of the side in the E-field direction
L_H is the slant length of the side in the H-field direction.
d is the diameter of the cylindrical horn aperture
L is the slant length of the cone from the apex.
λ is the wavelength

An optimum horn does not give maximum gain for a given *aperture size*; this is achieved by a very long horn. It gives the maximum gain for a given horn *length*. Tables showing dimensions for optimum horns for various frequencies are given in microwave handbooks.

Gain

Horns have very little loss, so the directivity of a horn is roughly equal to its gain. The gain G of a pyramidal horn antenna (the ratio of the radiated power intensity along its beam axis to the intensity of an isotropic antenna with the same input power) is:

$$G = \frac{4\pi A}{\lambda^2} e_A$$

For conical horns, the gain is:

$$G = \left(\frac{\pi d}{\lambda}\right)^2 e_A$$

where

A is the area of the aperture,
d is the aperture diameter of a conical horn
λ is the wavelength,
e_A is a dimensionless parameter called the *aperture efficiency*,

The aperture efficiency ranges from 0.4 to 0.8 in practical horn antennas. For optimum pyramidal horns, $e_A = 0.511.$, while for optimum conical horns $e_A = 0.522$. So an approximate figure of 0.5 is often used. The aperture efficiency increases with the length of the horn, and for aperture-limited horns is approximately unity.

Types of horn antennas

Aperture-limited corrugated horn, used as a feed horn in a radio telescope for millimeter waves.

These are the common types of horn antenna. Horns can have different flare angles as well as different expansion curves (elliptic, hyperbolic, etc.) in the E-field and H-field directions, making possible a wide variety of different beam profiles.

- Pyramidal horn - a horn antenna with the horn in the shape of a four-sided pyramid, with a rectangular cross section. They are the most widely used type, used with rectangular waveguides, and radiate linearly polarized radio waves.
- Sectoral horn - A pyramidal horn with only one pair of sides flared and the other pair parallel. It produces a fan-shaped beam, which is narrow in the plane of the flared sides, but wide in the plane of the narrow sides.
    - E-plane horn - A sectoral horn flared in the direction of the electric or E-field in the waveguide.
    - H-plane horn - A sectoral horn flared in the direction of the magnetic or H-field in the waveguide.
- Conical horn - A horn in the shape of a cone, with a circular cross section. They are used with cylindrical waveguides.
- Corrugated horn - A horn with parallel slots or grooves, small compared with a wavelength, covering the inside surface of the horn, transverse to the axis. Corrugated horns have wider bandwidth and smaller sidelobes and cross-

polarization, and are widely used as feed horns for satellite dishes and radio telescopes.

- Ridged horn - A pyramidal horn with ridges or fins attached to the inside of the horn, extending down the center of the sides. The fins lower the cutoff frequency, increasing the antenna's bandwidth.
- Septum horn - A horn which is divided into several subhorns by metal partitions (septums) inside, attached to opposite walls.
- Aperture-limited horn - a long narrow horn, long enough so the phase error is a fraction of a wavelength, so it essentially radiates a plane wave. It has an aperture efficiency of 1.0 so it gives the maximum gain and minimum beamwidth for a given aperture size. The gain is not affected by the length but only limited by diffraction at the aperture. Used as feed horns in radio telescopes and other high-resolution antennas.



50 ft. Holmdel horn antenna at Bell labs in Holmdel, New Jersey, USA, with which Arno Penzias and Robert Wilson discovered cosmic microwave background radiation in 1964.



Large 177 ft. Hogg horn antenna at AT&T satellite communications facility in Andover, Maine, USA, used in 1960s to communicate with the first direct relay communications satellite, Telstar.



Hogg microwave relay antennas on roof of AT&T telephone switching center, Seattle, Washington, USA
Hogg antennas

Hogg horn antenna

A type of antenna that combines a horn with a parabolic reflector is the Hogg antenna, invented by D. C. Hogg at Bell labs around 1960. It consisted of a horn antenna with a reflector mounted in the mouth of the horn at a 45 degree angle so the radiated beam is at right angles to the horn axis. The reflector is a segment of a parabolic reflector, so the device is equivalent to a parabolic antenna fed off-axis. The advantage of this design over a standard parabolic antenna is that the horn shields the antenna from radiation coming from angles outside the main beam axis, so its radiation pattern has very small sidelobes.

Also, the aperture isn't partially obstructed by the feed and its supports, as with ordinary front-fed parabolic dishes. The disadvantage is that it is far larger and heavier for a given aperture area than a parabolic dish, and must be mounted on a cumbersome turntable to be fully steerable. This design was used for a few radio telescopes and communication satellite ground antennas during the 1960s. Its largest use, however, was as fixed antennas for microwave relay links in the AT&T Long Lines microwave network. Probably the most photographed and well-known example is the 15 meter (50 foot) long Holmdel Horn Antenna at Bell Labs in Holmdel, New Jersey, with which Arno Penzias and Robert Wilson discovered cosmic microwave background radiation in 1965, for which they won the 1978 Nobel Prize in Physics.

Chapter 3

Radio Telescope



The 64 meter radio telescope at Parkes Observatory

A **radio telescope** is a form of directional radio antenna used in radio astronomy. The same types of antennas are also used in tracking and collecting data from satellites and space probes. In their astronomical role they differ from optical telescopes in that they operate in the radio frequency portion of the electromagnetic spectrum where they can detect and collect data on radio sources. Radio telescopes are typically large parabolic ("dish") antennas used singly or in an array. Radio observatories are preferentially located far from major centers of population to avoid electromagnetic interference (EMI) from radio, TV, radar, and other EMI emitting devices. This is similar to the locating of optical telescopes to avoid light pollution, with the difference being that radio observatories are often placed in valleys to further shield them from EMI as opposed to clear air mountain tops for optical observatories.

Early radio telescopes



Full-size replica of the first radio telescope, Jansky's dipole array now at the US National Radio Astronomy Observatory

The first radio antenna used to identify an astronomical radio source was one built by Karl Guthe Jansky, an engineer with Bell Telephone Laboratories, in 1931. Jansky was assigned the job of identifying sources of static that might interfere with radio telephone service. Jansky's antenna was an array of dipoles and reflectors designed to receive short wave radio signals at a frequency of 20.5 MHz (wavelength about 14.6 metres). It was mounted on a turntable that allowed it to rotate in any direction, earning it the name "Jansky's merry-go-round". It had a diameter of approximately 100 ft (30 m). and stood 20 ft (6 m). tall. By rotating the antenna on a set of four Ford Model-T tires, the direction of the received interfering radio source (static) could be pinpointed. A small shed to the side of the antenna housed an analog pen-and-paper recording system. After recording signals from all directions for several months, Jansky eventually categorized them into three types of static: nearby thunderstorms, distant thunderstorms, and a faint steady hiss of unknown origin. Jansky finally determined that the "faint hiss" repeated on a cycle of 23 hours and 56 minutes. This period is the length of an astronomical sidereal day, the time it takes any "fixed" object located on the celestial sphere to come back to the same location in the sky. Thus Jansky suspected that the hiss originated well beyond the Earth's atmosphere, and by comparing his observations with optical astronomical maps, Jansky concluded that the radiation was coming from the Milky Way Galaxy and was strongest in the direction of the center of the galaxy, in the constellation of Sagittarius.



Reber's first "dish" radio telescope - Wheaton, IL 1937

An amateur radio operator, Grote Reber, was one of the pioneers of what became known as radio astronomy when he built the first parabolic "dish" radio telescope (9 metres (30 ft) in diameter) in his back yard in Illinois in 1937. He was instrumental in repeating Karl Guthe Jansky's pioneering but somewhat simple work at higher frequencies, and he went on to conduct the first sky survey at very high radio frequencies. The rapid development of radar technology during World War II was easily translated into radio astronomy technology after the war, and the field of radio astronomy began to blossom.

Types



A *cylindrical paraboloid* antenna.

The range of frequencies in the electromagnetic spectrum that makes up the radio spectrum is very large. This means that the types of antennas that are used as radio telescopes vary widely in design, size, and configuration. At wavelengths of 30 meters to 3 meters (10 MHz - 100 MHz), they are generally either directional antenna arrays similar to "TV antennas" or large stationary reflectors with moveable focal points. Since the wavelengths being observed with these types of antennas are so long, the "reflector" surfaces can be constructed from coarse wire mesh such as chicken wire. At shorter wavelengths “dish” style radio telescopes predominate. The angular resolution of a dish style antenna is determined by the diameter of the dish expressed as a number of wavelengths of the electromagnetic radiation being observed. This dictates the dish size a radio telescope needs for a useful resolution. Radio telescopes that operate at wavelengths of 3 meters to 30 cm (100 MHz to 1 GHz) are usually well over 100 meters in diameter. Telescopes working at wavelengths shorter than 30 cm (above 1 GHz) range in size from 3 to 90 meters in diameter.

Big dishes

RT-70 planetary radar



World's largest single-aperture radio telescope at Arecibo Observatory in Puerto Rico

ALMA construction site

The world's largest filled-aperture telescope (i.e., a full dish) is the Arecibo radio telescope located in Arecibo, Puerto Rico, whose 305 m (1,001 ft) dish is fixed in the ground. It was designed by engineer Bill Gordon (d. 2010). The suspension system was designed by George and Helias Doundoulakis, for which Helias Doundoulakis received a patent along with assignee William J. Casey, ex-Central Intelligence Agency Director under President Ronald Reagan. The antenna beam is steerable (by means of a moving receiver) within about 20° of the zenith. The largest individual radio telescope of any kind is the RATAN-600 located near Nizhny Arkhyz, Russia, which consists of a 576-meter circle of rectangular radio reflectors, each of which can be pointed towards a central conical receiver.

The largest radio telescope in Europe is the 100-meter diameter antenna in Effelsberg, Germany, which also was the world's largest fully-steerable telescope for 30 years until the slightly larger Green Bank Telescope was opened in West Virginia, United States, in 2000. The third-largest fully-steerable radio telescope is the 76-metre Lovell Telescope at Jodrell Bank Observatory in Cheshire, England. The fourth-largest fully-steerable radio telescopes is four the 70-metre radio telescopes: RT-70, Goldstone. Feature of these telescopes is that it is the world's largest planetary radars (except Suffa RT-70).

A typical size of the single antenna of a radio telescope is 25 meters. Dozens of radio telescopes with comparable sizes are operated in radio observatories all over the world.

China officially started construction of the world's largest single-aperture radio telescope in 2009, the FAST. The FAST, with a dish area as large as 30 football fields, will stand in a region of typical Karst depressions in Guizhou, and will be finished by 2013.

Radio interferometry

The Very Large Array, an interferometric array formed from many smaller telescopes, like many larger radio telescopes.

One of the most notable developments came in 1946 with the introduction of the technique called astronomical interferometry. Astronomical radio interferometers usually consist either of arrays of parabolic dishes (e.g., the One-Mile Telescope), arrays of one-dimensional antennas (e.g., the Molonglo Observatory Synthesis Telescope) or two-dimensional arrays of omni-directional dipoles (e.g., Tony Hewish's Pulsar Array). All of the telescopes in the array are widely separated and are usually connected together using coaxial cable, waveguide, optical fiber, or other type of transmission line. Recent advances in the stability of electronic oscillators also now permit interferometry to be carried out by independent recording of the signals at the various antennas, and then later correlating the recordings at some central processing facility. This process is known as VLBI (Very Long Baseline Interferometry). Interferometry does increase the total signal collected, but its primary purpose is to vastly increase the resolution through a process called Aperture synthesis. This technique works by superposing (interfering) the signal waves from the different telescopes on the principle that waves that coincide with the same phase will add to each other while two waves that have opposite phases will cancel each other out. This creates a combined telescope that is equivalent in resolution (though not in sensitivity) to a single antenna whose diameter is equal to the spacing of the antennas furthest apart in the array. A high quality image requires a large number of different separations between telescopes. Projected separation between any two telescopes, as seen from the radio source, is called a baseline. For example, the Very Large Array (VLA) near Socorro, New Mexico has 27 telescopes with 351 independent baselines at once, which achieves a resolution of 0.2 arc seconds at 3 cm wavelengths). Martin Ryle's group in Cambridge obtained a Nobel Prize for interferometry and aperture synthesis. The Lloyd's mirror interferometer was also developed independently in 1946 by Joseph Pawsey's group at the University of Sydney. In the early 1950s the Cambridge Interferometer mapped the radio sky to produce the famous 2C and 3C surveys of radio sources. The largest existing physically-connected radio telescope array is the Giant Metrewave Radio Telescope, located in Pune, India. A larger array, LOFAR (the 'LOw Frequency ARray') is currently being constructed in western Europe, consisting of 25 000 small antennas over an area several hundreds of kilometres in diameter. VLBI systems using post-observation processing have been constructed with antennas thousands of miles apart. Radio interferometers have also been used to obtain detailed images of the anisotropies and the polarization of the Cosmic Microwave Background, like the CBI interferometer in 2004.

Astronomical observations

Many astronomical objects are not only observable in visible light but also emit radiation at radio wavelengths. Besides observing energetic objects such as pulsars and quasars, radio telescopes are able to "image" most astronomical objects such as galaxies, nebulae, and even radio emissions from planets.

Chapter 4

Parabolic Antenna

A parabolic antenna at Erdfunkstelle Raisting, the biggest facility for satellite communication in the world, based in Raisting, Bavaria, Germany. It has a Cassegrain type feed.

A **parabolic antenna** is an antenna that uses a parabolic reflector, a surface with the cross-sectional shape of a parabola, to direct the radio waves. The most common form is shaped like a dish and is popularly called a **dish antenna** or **parabolic dish**. The main advantage of a parabolic antenna is that it is highly directive; it functions analogously to a searchlight or flashlight reflector to direct the radio waves in a narrow beam, or receive radio waves from one particular direction only. Parabolic antennas have some of the highest gains, that is they can produce the narrowest beam width angles, of any antenna type. They are used as high-gain antennas for point-to-point radio, television and data communications, and also for radiolocation (radar), on the UHF and microwave (SHF) parts of the radio spectrum. The relatively short wavelength of electromagnetic radiation at these frequencies allows reasonably sized reflectors to exhibit the desired highly directional response.

With the advent of TVRO and DBS satellite television dishes, parabolic antennas have become a ubiquitous feature of the modern landscape. They are also widely used for terrestrial microwave relay links, ground based and airborne radar antennas, wireless WAN/LAN links, satellite and spacecraft communication antennas, and radio telescopes.

History

The idea of using parabolic reflectors for radio antennas was taken from optics, where the power of a parabolic mirror to focus light into a beam has been known since classical antiquity. The designs of some specific types of parabolic antenna, such as the Cassegrain and Gregorian, come from similarly named analogous types of reflecting telescope, which were invented by astronomers during the 15th century.

German physicist Heinrich Hertz constructed the world's first parabolic reflector antenna in 1888. The antenna was a cylindrical parabolic reflector made of zinc sheet metal supported by a wooden frame, and had a spark-gap excited dipole along the focal line. Its aperture was 1.2 meters wide, with a focal length of 0.12 meters, and was used at an operating frequency of about 450 MHz. With two such antennas, one used for transmitting and the other for receiving, Hertz demonstrated the existence radio waves which had been predicted by James Clerk Maxwell some 22 years earlier.

The first parabolic antenna used for satellite communications was established in 1962 at Goonhilly in Cornwall, England, UK and was intended to communicate with Telstar.

Types


Parabolic reflector
Axial feed
Feed antenna
Supports
Off-axis or Offset feed
Cassegrain
Convex secondary reflector
Gregorian
Concave secondary reflector

Main types of parabolic antenna feeds.

Parabolic antennas are distinguished by their shapes:

- *Paraboloidal* or *dish* - The reflector is shaped like a paraboloid. This is the most common type. It radiates a narrow pencil-shaped beam along the axis of the dish.
    - *Shrouded dish* - Sometimes a cylindrical metal shield is attached to the rim of the dish. The shroud shields the antenna from radiation from angles outside the main beam axis, reducing the sidelobes. It is sometimes used to prevent interference in terrestrial microwave links, where several antennas using the same frequency are located close together. The shroud is coated

    inside with microwave absorbent material. Shrouds can reduce back lobe radiation by 10 dB.

- *Cylindrical* - The reflector is curved in only one direction and flat in the other. The radio waves come to a focus not at a point but along a line. The feed is often a dipole antenna located along the focal line. It radiates a fan-shaped beam, narrow in the curved dimension, and wide in the uncurved dimension. The curved ends of the reflector are sometimes capped by flat plates, to prevent radiation out the ends, and this is called a *pillbox* antenna.
    - *"Orange peel"* - Another type is very long and narrow, shaped like the letter "C". This is called an *orange peel* design, and radiates an even wider fan beam. It is often used for radar antennas.

They are also classified by the type of *feed*; how the radio waves are supplied to the antenna:

- *Axial* or *front feed* - This is the most common type of feed, with the feed antenna located in front of the dish at the focus, on the beam axis. A disadvantage of this type is that the feed and its supports block some of the beam, which limits the aperture efficiency to only 55 - 60%.
- *Offset* or *off-axis feed* - The reflector is an asymmetrical segment of a paraboloid, so the focus, and the feed antenna, are located to one side of the dish. The purpose of this design is to move the feed structure out of the beam path, so it doesn't block the beam. It is widely used in home satellite television dishes, which are small enough that the feed structure would otherwise block a significant percentage of the signal.
- *Cassegrain* - In a Cassegrain antenna the feed is located on or behind the dish, and radiates forward, illuminating a convex hyperboloidal secondary reflector at the focus of the dish. The radio waves from the feed reflect back off the secondary reflector to the dish, which forms the main beam. An advantage of this configuration is that the feed, with its waveguides and "front end" electronics does not have to be suspended in front of the dish, so it is used for antennas with complicated or bulky feeds, such as large satellite communication antennas and radio telescopes. Aperture efficiency is on the order of 65 - 70%
- *Gregorian* - Similar to the Cassegrain design except that the secondary reflector is concave, (ellipsoidal) in shape. Aperture efficiency over 70% can be achieved.

Design

The operating principle of a parabolic antenna is that a point source of radio waves at the focal point in front of a parabolic reflector will be reflected into a collimated plane wave beam along the axis of the reflector. Conversely, an incoming plane wave parallel to the axis will be focused to a point at the focal point.

A typical parabolic antenna consists of a parabolic reflector with a small feed antenna at its focus, pointed back toward the reflector. The reflector is a metallic surface formed into a paraboloid of revolution and usually truncated in a circular rim that forms the diameter of the antenna.

The reflector dish can be of sheet metal, metal screen, or wire grill construction, and it can be either circular or various other shapes to create different beam shapes. A mesh screen reflects radio waves as well as a solid metal surface as long as the holes are smaller than 1/10 of a wavelength, so screen reflectors are often used to reduce weight and wind loads on the dish. To achieve the maximum gain, it is necessary that the shape of the dish be accurate within a small fraction of a wavelength, to ensure the waves from different parts of the antenna arrive in phase. Large dishes often require a truss structure behind them to provide the required stiffness.

The feed antenna at the reflector's focus is typically a low-gain type such as a half-wave dipole or more ofteh a small horn antenna called a feed horn. In more complex designs, such as the Cassegrain and Gregorian, a secondary reflector is used to direct the energy into the parabolic reflector from a feed antenna located away from the primary focal point. The feed antenna is connected to the associated radio-frequency (RF) transmitting or receiving equipment by means of a coaxial cable transmission line or waveguide.

Feed pattern

The radiation pattern of the feed antenna has a strong influence on the *aperture efficiency*, which determines the antenna gain. Radiation from the feed that falls outside the edge of the dish is called "*spillover*" and is wasted, reducing the gain and increasing the backlobes, possibly causing interference or (in receiving antennas) increasing susceptibility to ground noise. However, maximum gain is only achieved when the dish is uniformly "illuminated" with a constant field strength to its edges. So the ideal radiation pattern of a feed antenna would be a constant field strength throughout the solid angle of the dish, dropping abruptly to zero at the edges. However, practical feed antennas have radiation patterns that drop off gradually at the edges, so the feed antenna is a compromise between acceptably low spillover and adequate illumination.

Gain

The directive qualities of an antenna are measured by a dimensionless parameter called its gain, which is the ratio of the power received by the antenna from a source along its beam axis to the power received by a hypothetical isotropic antenna. The gain of a parabolic antenna is:

$$G = \frac{4\pi A}{\lambda^2} e_A = \frac{\pi^2 d^2}{\lambda^2} e_A$$

where:

- A is the area of the antenna aperture, that is, the mouth of the parabolic reflector
- d is the diameter of the parabolic reflector

- λ is the wavelength of the radio waves.
- e_A is a dimensionless parameter called the *aperture efficiency*. The aperture efficiency of typical parabolic antennas is 0.55 to 0.70.

The largest dish antenna in the world, the radio telescope at Arecibo Observatory, Puerto Rico, 305 meters (1000 feet) in diameter. It has a gain of 10 million, or 70 dBi, at 2.38 GHz.

It can be seen that, as with any *aperture antenna*, the larger the aperture is, compared to the wavelength, the higher the gain. The gain increases with the square of the ratio of aperture width to wavelength, so large parabolic antennas, such as those used for spacecraft communication and radio telescopes, can have extremely high gain. Applying the above formula to the 25-meter-diameter antennas used by the VLA and VLBA radio telescopes at a wavelength of 21 cm (1.42 GHz, a common radio astronomy frequency) yields an approximate maximum gain of 140,000 times or about 50 dBi (decibels above the isotropic level).

As of 2009, the largest "dish" antenna in the world is the Arecibo Observatory's radio telescope, at Arecibo, Puerto Rico, which has a diameter of 1,000 ft. (305 m). It has a gain of about 10 million, or 70 dBi, at 2.38 GHz. The dish is built into a valley in the landscape, so it is not steerable. To steer the beam to different points in the sky, the feed antenna is moved. For this reason, the dish actually has a spherical rather than a parabolic shape. A spherical reflector does not have a single focal "point", however, the Arecibo antenna is a three-reflector variety of Gregorian telescope, and uses its secondary and tertiary reflectors to focus the radio waves to a single point.

Aperture efficiency e_A is a catchall variable which accounts for various losses that reduce the gain of the antenna from the maximum that could be achieved with the given aperture. The major factors reducing the aperture efficiency in parabolic antennas are:.

- *Feed spillover* - Some of the radiation from the feed antenna falls outside the edge of the dish and so doesn't contribute to the main beam.
- *Feed illumination taper* - The maximum gain for any aperture antenna is only achieved when the intensity of the radiated beam is constant across the aperture area. However the radiation pattern from the feed antenna usually tapers off toward the outer part of the dish, so the outer parts of the dish are "illuminated" with a lower intensity of radiation. Even if the feed provided constant illumination across the angle subtended by the dish, the outer parts of the dish are farther away from the feed antenna than the inner parts, so the intensity would drop off with distance from the center. So the intensity of the beam radiated by a parabolic antenna is maximum at the center of the dish and falls off with distance from the axis, reducing the efficiency.
- *Aperture blockage* - In axis-fed parabolic dishes where the feed antenna is located in front of the dish in the beam path, the feed structure and its supports block some of the beam. In small dishes such as home satellite dishes, where the size of the feed structure is comparable with the size of the dish, this can seriously reduce the antenna gain. To prevent this problem these types of antennas often use an *off-axis* feed, where the feed antenna is located to one side, outside the beam area. The aperture efficiency for these types of antennas can reach 0.7 to 0.8.
- *Shape errors* - random surface errors in the shape of the reflector reduce efficiency. The loss is approximated by Ruze's Equation.

For theoretical considerations of mutual interference (at frequencies between 2 and c. 30 GHz - typically in the Fixed Satellite Service) where specific antenna performance has not been defined, a *reference antenna* based on Recommendation ITU-R S.465 is used to calculate the interference, which will include the likely sidelobes for off-axis effects.



Wire grid-type parabolic antenna (Wi-Fi / WLAN antenna) at 2.4 GHz).

Beamwidth

C-band Satellite dish, Bucharest, Romania

The angular width of the beam radiated by high-gain antennas is measured by the *half-power beam width* (HPBW), which is the angular separation between the points on the antenna radiation pattern at which the power drops to one-half (-3 dB) its maximum value. For parabolic antennas, the HPBW θ is given by:

$$\theta = k\lambda/d$$

where k is a factor which depends on the shape of the reflector and the feed illumination pattern. For a "typical" parabolic antenna $k = 70$ when θ is in degrees.

For a typical 2 meter satellite dish operating on C band (4 GHz), like the one shown at right, this formula gives a beamwidth of about 2.6°. For the Arecibo antenna at 2.4 GHz the beamwidth is 0.028°. It can be seen that parabolic antennas can produce very narrow beams, and aiming them can be a problem. Some parabolic dishes are equipped with a boresight so they can be aimed accurately at the other antenna.

It can be seen there is an inverse relation between gain and beam width. By combining the beamwidth equation with the gain equation, the relation is:

$$G - \left(\frac{\pi k}{\theta}\right)^2 \epsilon_A$$

Chapter 5

Antenna (Radio)

Whip antenna on car


SCHWARZ
λ/2-Dip
1.5 - 3 (4)
UHA 9125

Half-wave dipole antenna

Large parabolic antenna for communicating with spacecraft

Rooftop directional antennas, typical for use at VHF and UHF frequencies

An **antenna** (or **aerial**) is an electrical device which couples radio waves in free space to an electrical current used by a radio receiver or transmitter. In reception, the antenna intercepts some of the power of an electromagnetic wave in order to produce a tiny voltage that the radio receiver can amplify. Alternatively, a radio transmitter will produce a large radio frequency current that may be applied to the terminals of the same antenna in order to convert it into an electromagnetic wave (radio wave) radiated into free space. Antennas are thus essential to the operation of all radio equipment, both transmitters and receivers. They are used in systems such as radio and television broadcasting, two-way radio, wireless LAN, mobile telephony, radar, and satellite communications.

Typically an antenna consists of an arrangement of metallic conductors (or "elements") with an electrical connection (often through a transmission line) to the receiver or transmitter. A current forced through such a conductor by a radio transmitter will create an alternating magnetic field according to Ampère's law. Or the alternating magnetic field due to a distant radio transmitter will induce a voltage at the antenna terminals, according to Faraday's law, which is connected to the input of a receiver. In the so-called far field, at a considerable distance away from the antenna, the oscillating magnetic field is coupled with a similarly oscillating electric field; together these define an electromagnetic wave which is capable of propagating great distances.

Light is one example of electromagnetic radiation, along with infrared and x-rays, while radio waves differ only in their much lower frequency (and much longer wavelength). Electronic circuits can operate at these lower frequencies, processing radio signals conducted through wires. But it is only through antennas that those radio frequency electrical signals are converted to (and from) propagating radio waves. Depending on the design of the antenna, radio waves can be sent toward and received from all directions ("omnidirectional"), whereas a directional or beam antenna is designed to operate in a particular direction.

The first antennas were built in 1888 by Heinrich Hertz (1857–1894) in his pioneering experiments to prove the existence of electromagnetic waves predicted by the theory of James Clerk Maxwell. Hertz placed dipole antennas at the focal point of parabolic reflectors for both transmitting and receiving. He published his work and installation drawings in *Annalen der Physik und Chemie* (vol. 36, 1889).

Terminology

The words *antenna* (plural: *antennas*) and *aerial* are used interchangeably; but usually a rigid metallic structure is termed an antenna and a wire format is called an aerial. In the United Kingdom and other British English speaking areas the term aerial is more common, even for rigid types. The noun *aerial* is occasionally written with a diaeresis mark—*aërial*—in recognition of the original spelling of the adjective *aërial* from which the noun is derived.

The origin of the word *antenna* relative to wireless apparatus is attributed to Guglielmo Marconi. In 1895, while testing early radio apparatuses in the Swiss Alps at Salvan, Switzerland in the Mont Blanc region, Marconi experimented with early wireless equipment. A 2.5 meter long pole, along which was carried a wire, was used as a radiating and receiving aerial element. In Italian a tent pole is known as *l'antenna centrale,* and the pole with a wire alongside it used as an aerial was simply called *l'antenna.* Until then wireless radiating transmitting and receiving elements were known simply as aerials or terminals. Marconi's use of the word *antenna* (Italian for *pole*) would become a popular term for what today is uniformly known as the *antenna*.

In common usage, the word *antenna* may refer broadly to an entire assembly including support structure, enclosure (if any), etc. in addition to the actual functional components.

Especially at microwave frequencies, a receiving antenna may include not only the actual electrical antenna but an integrated preamplifier and/or mixer.



"Rabbit ears" dipole antenna for television reception

Cell phone base station antennas

Satellite link antenna used by Himalaya Television Nepal



Bundesarchiv, Bild 183-20802-0001
Foto: Braun | April 1955

Yagi antenna used for mobile military communications station, Dresden, Germany, 1955



"Super Turnstile" type transmitting antenna for VHF low band television broadcasting station, Germany.



Folded dipole antenna



Large Yagi antenna used by amateur radio hobbyist

A vertical mast radiator, Chapel Hill, North Carolina

Overview

Antennas are required by any radio receiver or transmitter in order to couple its electrical connection to the electromagnetic field. Radio waves are electromagnetic waves which carry signals through the air (or through space) at almost the speed of light with almost no transmission loss. Radio transmitters and receivers are used to convey signals (information) in systems including broadcast (audio) radio, television, mobile telephones, wi-fi (WLAN) data networks, trunk lines and point-to-point communications links (telephone, data networks), satellite links, many remote controlled devices such as garage door openers, and wireless remote sensors, among many others. Radio waves are also used directly for measurements in technologies including RADAR, GPS, and radio astronomy. In each and every case, the transmitters and receivers involved require antennas, although these are sometimes hidden (such as the antenna inside an AM radio or inside a laptop computer equipped with wi-fi).

According to their applications and technology available, antennas generally fall in one of two catagories:

1. Omnidirectional or only weakly directional antennas which receive or radiate more or less in all directions. These are employed when the relative position of the other station is unknown or arbitrary. They are also used at lower frequencies where a directional antenna would be too large, or simply to cut costs in applications where a directional antenna isn't required.
2. Directional or *beam* antennas which are intended to preferentially radiate or receive in a particular direction or directional pattern.

In common usage "omnidirectional" usually refers to all horizontal directions, typically with reduced performance in the direction of the sky or the ground (a truly isotropic radiator is not even possible). A "directional" antenna usually is intended to maximize its coupling to the electromagnetic field in the direction of the other station, or sometimes to cover a particular sector such as a 120° horizontal fan pattern in the case of a panel antenna at a cell site.

One example of omnidirectional antennas is the very common *vertical antenna* or whip antenna consisting of a metal rod (often, but not always, a quarter of a wavelength long). A dipole antenna is similar but consists of two such conductors extending in opposite directions, with a total length that is often, but not always, a half of a wavelength long. Dipoles are typically oriented horizontally in which case they are weakly directional: signals are reasonably well radiated toward or received from all directions with the exception of the direction along the conductor itself; this region is called the antenna blind cone or null.

Both the vertical and dipole antennas are simple in construction and relatively inexpensive. The dipole antenna, which is the basis for most antenna designs, is a balanced component, with equal but opposite voltages and currents applied at its two terminals through a balanced transmission line (or to a coaxial transmission line through a so-called balun). The vertical antenna, on the other hand, is a *monopole* antenna. It is typically connected to the inner conductor of a coaxial transmission line (or a matching network); the shield of the transmission line is connected to ground. In this way, the ground (or any large conductive surface) plays the role of the second conductor of a dipole, thereby forming a complete circuit. Since monopole antennas rely on a conductive ground, a so-called grounding structure may be employed in order to provide a better ground contact to the earth or which itself acts as a ground plane to perform that function regardless of (or in absence of) an actual contact with the earth.

Antennas fancier than the dipole or vertical designs are usually intended to increase the directivity and consequently the gain of the antenna. This can be accomplished in many different ways leading to a plethora of antenna designs. The vast majority of designs are fed with a balanced line (unlike a monopole antenna) and are based on the dipole antenna with additional components (or *elements*) which increase its directionality.

For instance, a phased array consists of two or more simple antennas which are connected together through an electrical network. This often involves a number of parallel dipole antennas with a certain spacing. Depending on the relative phase introduced by the network, the same combination of dipole antennas can operate as a "broadside array" (directional normal to a line connecting the elements) or as an "end-fire array" (directional along the line connecting the elements). Antenna arrays may employ any basic (omnidirectional or weakly directional) antenna type, such as dipole, loop or slot antennas. These elements are often identical.

However a log-periodic dipole array consists of a number of dipole elements of *different* lengths in order to obtain a somewhat directional antenna having an extremely wide bandwidth: these are frequently used for television reception in fringe areas. The dipole antennas composing it are all considered "active elements" since they are all electrically connected together (and to the transmission line). On the other hand, a superficially similar dipole array, the Yagi-Uda Antenna (or simply "Yagi"), has only one dipole element with an electrical connection; the other so-called parasitic elements interact with the electromagnetic field in order to realize a fairly directional antenna but one which is limited to a rather narrow bandwidth. The Yagi antenna has similar looking parasitic dipole elements but which act differently due to their somewhat different lengths. There may be a number of so-called "directors" in front of the active element in the direction of propagation, and usually a single (but possibly more) "reflector" on the opposite side of the active element.

Greater directionality can be obtained using beam-forming techniques such as a parabolic reflector or a horn. Since the size of a directional antenna depends on it being large compared to the wavelength, very directional antennas of this sort are mainly feasible at UHF and microwave frequencies. On the other hand, at low frequencies (such as AM broadcast) where a practical antenna must be much smaller than a wavelength, significant directionality isn't even possible. A vertical antenna or loop antenna small compared to the wavelength is typically used, with the main design challenge being that of impedance matching. With a vertical antenna a *loading coil* at the base of the antenna may be employed to cancel the reactive component of impedance; small loop antennas are tuned with parallel capacitors for this purpose.

An antenna lead-in is the transmission line (or *feed line*) which connects the antenna to a transmitter or receiver. The *antenna feed* may refer to all components connecting the antenna to the transmitter or receiver, such as an impedance matching network in addition to the transmission line. In a so-called aperture antenna, such as a horn or parabolic dish, the "feed" may also refer to a basic antenna inside the entire system (normally at the focus of the parabolic dish or at the throat of a horn) which could be considered the one active element in that antenna system. A microwave antenna may also be fed directly from a waveguide in lieu of a (conductive) transmission line.

An antenna counterpoise or ground plane is a structure of conductive material which improves or substitutes for the ground. It may be connected to or insulated from the natural ground. In a monopole antenna, this aids in the function of the natural ground, particularly where variations (or limitations) of the characteristics of the natural ground interfere with its proper function. Such a structure is normally connected to the return connection of an unbalanced transmission line such as the shield of a coaxial cable.

An electromagnetic wave *refractor* in some aperture antennas is a component which due to its shape and position functions to selectively delay or advance portions of the electromagnetic wavefront passing through it. The refractor alters the spatial characteristics of the wave on one side relative to the other side. It can, for instance, bring the wave to a focus or alter the wave front in other ways, generally in order to maximize the directivity of the antenna system. This is the radio equivalent of an optical lens.

An antenna coupling network is a passive network (generally a combination of inductive and capacitive circuit elements) used for impedance matching in between the antenna and the transmitter or receiver. This may be used to improve the standing wave ratio in order to minimize losses in the transmission line (especially at higher frequencies and/or over longer distances) and to present the transmitter or receiver with a standard resistive impedance (such as 75 ohms) that it expects to see for optimum operation.

Reciprocity

It is a fundamental property of antennas that the characteristics of an antenna described in the next section, such as gain, radiation pattern, impedance, bandwidth, resonant frequency and polarization, are the same whether the antenna is transmitting or receiving. For example, the "*receiving pattern*" (sensitivity as a function of direction) of an antenna when used for reception is identical to the radiation pattern of the antenna when it is *driven* and functions as a radiator. This is a consequence of the reciprocity theorem of electromagnetics. Therefore in discussions of antenna properties no distinction is usually made between receiving and transmitting terminology, and the antenna can be viewed as either transmitting or receiving, whichever is more convenient.

A necessary condition for the above reciprocity property is that the materials in the antenna and transmission medium are linear and reciprocal. *Reciprocal* (or *bilateral*) means that the material has the same response to an electric or magnetic field, or a current, in one direction, as it has to the field or current in the opposite direction. Most materials used in antennas meet these conditions, but some microwave antennas use high-tech components such as isolators and circulators, made of nonreciprocal materials such as ferrite or garnet. These can be used to give the antenna a different behavior on receiving than it has on transmitting, which can be useful in applications like radar.

Parameters

There are several critical parameters affecting an antenna's performance that can be adjusted during the design process. These are resonant frequency, impedance, gain, aperture or radiation pattern, polarization, efficiency and bandwidth. Transmit antennas may also have a maximum power rating, and receive antennas differ in their noise rejection properties. All of these parameters can be measured through various means.

Resonant frequency

Many types of antenna are tuned to work at one particular frequency, and are effective only over a range of frequencies centered on this frequency, called the resonant frequency. These are called *resonant antennas*. The antenna acts as an electrical resonator. When driven at its resonant frequency, large standing waves of voltage and current are excited in the antenna elements. These large currents and voltages radiate intense electromagnetic waves, so the power radiated by the antenna is maximum at the resonant frequency.

In antennas made of thin linear conductive elements, the length of the driven element(s) determines the resonant frequency. To be resonant, the length of a driven element should typically be either half or a quarter of the wavelength at that frequency; these are called half-wave and quarter-wave antennas. The length referred to is not the physical length, but the electrical length of the element, which is the physical length divided by the velocity factor (the ratio of the speed of wave propagation in the wire to c_0, the speed of light in a vacuum). Antennas are usually also resonant at multiples (harmonics) of the lowest resonant frequency.

Some antenna designs have multiple resonant frequencies, and some are relatively effective over a very broad range of frequencies. or bandwidth. One commonly known type of wide band antenna is the logarithmic or log-periodic antenna.

The resonant frequency also affects the impedance of the antenna. At resonance, the equivalent circuit of an antenna is a pure resistance, with no reactive component. At frequencies other than the resonant frequencies, the antenna has capacitance or inductance as well as resistance. An antenna can be made resonant at other frequencies besides its natural resonant frequency by compensating for these reactances by adding a loading coil or capacitor in series with it. Other properties of an antenna change with frequency, in particular the radiation pattern, so the antenna's operating frequency may be considerably different from the resonant frequency to optimize other important parameters.

Gain

Gain is a parameter which measures the degree of directivity of the antenna's radiation pattern. An antenna with a low gain emits radiation with about the same power in all directions, whereas a high-gain antenna will preferentially radiate in particular directions. Specifically, the *antenna gain*, *directive gain*, or *power gain* of an antenna is defined as the ratio of the intensity (power per unit surface) radiated by the antenna in the direction of its maximum output, at an arbitrary distance, divided by the intensity radiated at the same distance by a hypothetical isotropic antenna.

The gain of an antenna is a passive phenomenon - power is not added by the antenna, but simply redistributed to provide more radiated power in a certain direction than would be transmitted by an isotropic antenna. An antenna designer must take into account the application for the antenna when determining the gain. High-gain antennas have the advantage of longer range and better signal quality, but must be aimed carefully in a particular direction. Low-gain antennas have shorter range, but the orientation of the antenna is relatively inconsequential. For example, a dish antenna on a spacecraft is a high-gain device that must be pointed at the planet to be effective, whereas a typical Wi-Fi antenna in a laptop computer is low-gain, and as long as the base station is within range, the antenna can be in any orientation in space. It makes sense to improve horizontal range at the expense of reception above or below the antenna. Thus most antennas labelled "omnidirectional" really have some gain.

In practice, the half-wave dipole is taken as a reference instead of the isotropic radiator. The gain is then given in **dBd** (decibels over **d**ipole):

NOTE: **0 dBd = 2.15 dBi**. It is vital in expressing gain values that the reference point be included. Failure to do so can lead to confusion and error.

Radiation pattern



polar plots of the horizontal cross sections of a (virtual) Yagi-Uda-antenna. Outline connects points with 3db field power compared to an ISO emitter.

The radiation pattern of an antenna is a plot of the relative field strength of the radio waves emitted by the antenna at different angles. It is typically represented by a three dimensional graph, or polar plots of the horizontal and vertical cross sections. The pattern of an ideal isotropic antenna, which radiates equally in all directions, would look like a sphere. Many nondirectional antennas, such as monopoles and dipoles, emit equal power in all horizontal directions, with the power dropping off at higher and lower angles; this is called an omnidirectional pattern and when plotted looks like a torus or donut.

The radiation of many antennas shows a pattern of maxima or "*lobes*" at various angles, separated by "*nulls*", angles where the radiation falls to zero. This is because the radio waves emitted by different parts of the antenna typically interfere, causing maxima at angles where the radio waves arrive at distant points in phase, and zero radiation at other angles where the radio waves arrive out of phase. In a directional antenna designed to project radio waves in a particular direction, the lobe in that direction is designed larger than the others and is called the "*main lobe*". The other lobes usually represent unwanted radiation and are called "*sidelobes*". The axis through the main lobe is called the "*principle axis*" or "*boresight axis*".

Impedance

As an electro-magnetic wave travels through the different parts of the antenna system (radio, feed line, antenna, free space) it may encounter differences in impedance (E/H, V/I, etc.). At each interface, depending on the impedance match, some fraction of the wave's energy will reflect back to the source, forming a standing wave in the feed line. The ratio of maximum power to minimum power in the wave can be measured and is called the standing wave ratio (**SWR**). A SWR of 1:1 is ideal. A SWR of 1.5:1 is considered to be marginally acceptable in low power applications where power loss is more critical, although an SWR as high as 6:1 may still be usable with the right equipment. Minimizing impedance differences at each interface (impedance matching) will reduce SWR and maximize power transfer through each part of the antenna system.

Complex impedance of an antenna is related to the electrical length of the antenna at the wavelength in use. The impedance of an antenna can be matched to the feed line and radio by adjusting the impedance of the feed line, using the feed line as an impedance transformer. More commonly, the impedance is adjusted at the load (see below) with an antenna tuner, a balun, a matching transformer, matching networks composed of inductors and capacitors, or matching sections such as the gamma match.

Efficiency

Efficiency is the ratio of power actually radiated to the power put into the antenna terminals. A dummy load may have an SWR of 1:1 but an efficiency of 0, as it absorbs all power and radiates heat but very little RF energy, showing that SWR alone is not an effective measure of an antenna's efficiency. Radiation in an antenna is caused by radiation resistance which can only be measured as part of total resistance including loss resistance. Loss resistance usually results in heat generation rather than radiation, and reduces efficiency. Mathematically, efficiency is calculated as radiation resistance divided by total resistance.

Bandwidth

The *bandwidth* of an antenna is the range of frequencies over which it is effective, usually centered on the resonant frequency. The bandwidth of an antenna may be increased by several techniques, including using thicker wires, replacing wires with *cages* to simulate a thicker wire, tapering antenna components (like in a feed horn), and combining multiple antennas into a single assembly (array) and allowing the natural impedance of suitable inductive RF filter traps to select the correct antenna. All these attempts to increase bandwidth by adding capacitance to the surface area have a detrimental effect on efficiency by reducing the Q factor. They also have an adverse effect on the rejection of unwanted harmonics, on both received and transmitted signal frequencies. Small antennas are usually preferred for convenience, but there is a fundamental limit relating bandwidth, size and efficiency.

Polarization

The *polarization* of an antenna is the orientation of the electric field (E-plane) of the radio wave with respect to the Earth's surface and is determined by the physical structure of the antenna and by its orientation. It has nothing in common with antenna directionality terms: "horizontal", "vertical" and "circular". Thus, a simple straight wire antenna will have one polarization when mounted vertically, and a different polarization when mounted horizontally. "Electromagnetic wave polarization filters" are structures which can be employed to act directly on the electromagnetic wave to filter out wave energy of an undesired polarization and to pass wave energy of a desired polarization.

Reflections generally affect polarization. For radio waves the most important reflector is the ionosphere - signals which reflect from it will have their polarization changed unpredictably. For signals which are reflected by the ionosphere, polarization cannot be relied upon. For line-of-sight communications for which polarization can be relied upon, it can make a large difference in signal quality to have the transmitter and receiver using the same polarization; many tens of dB difference are commonly seen and this is more than enough to make the difference between reasonable communication and a broken link.

Polarization is largely predictable from antenna construction but, especially in directional antennas, the polarization of side lobes can be quite different from that of the main propagation lobe. For radio antennas, polarization corresponds to the orientation of the radiating element in an antenna. A vertical omnidirectional WiFi antenna will have vertical polarization (the most common type). An exception is a class of elongated waveguide antennas in which vertically placed antennas are horizontally polarized. Many commercial antennas are marked as to the polarization of their emitted signals.

Polarization is the sum of the E-plane orientations over time projected onto an imaginary plane perpendicular to the direction of motion of the radio wave. In the most general case, polarization is elliptical, meaning that the polarization of the radio waves varies over time. Two special cases are linear polarization (the ellipse collapses into a line) and circular polarization (in which the two axes of the ellipse are equal). In linear polarization the antenna compels the electric field of the emitted radio wave to a particular orientation. Depending on the orientation of the antenna mounting, the usual linear cases are horizontal and vertical polarization. In circular polarization, the antenna continuously varies the electric field of the radio wave through all possible values of its orientation with regard to the Earth's surface. Circular polarizations, like elliptical ones, are classified as right-hand polarized or left-hand polarized using a "thumb in the direction of the propagation" rule. Optical researchers use the same rule of thumb, but pointing it in the direction of the emitter, not in the direction of propagation, and so are opposite to radio engineers' use.

In practice, regardless of confusing terminology, it is important that linearly polarized antennas be matched, lest the received signal strength be greatly reduced. So horizontal should be used with horizontal and vertical with vertical. Intermediate matchings will lose some signal strength, but not as much as a complete mismatch. Transmitters mounted on vehicles with large motional freedom commonly use circularly polarized antennas so that there will never be a complete mismatch with signals from other sources.

Transmission and reception

All of the antenna parameters are expressed in terms of a transmission antenna, but are identically applicable to a receiving antenna, due to reciprocity. Impedance, however, is not applied in an obvious way; for impedance, the impedance at the load (where the power is consumed) is most critical. For a transmitting antenna, this is the antenna itself. For a receiving antenna, this is at the (radio) receiver rather than at the antenna. Tuning is done by adjusting the length of an electrically long linear antenna to alter the electrical resonance of the antenna.

Antenna tuning is done by adjusting an inductance or capacitance combined with the active antenna (but distinct and separate from the active antenna). The inductance or capacitance provides the reactance which combines with the inherent reactance of the active antenna to establish a resonance in a circuit including the active antenna. The established resonance being at a frequency other than the natural electrical resonant frequency of the active antenna. Adjustment of the inductance or capacitance changes this resonance.

Antennas used for transmission have a maximum power rating, beyond which heating, arcing or sparking may occur in the components, which may cause them to be damaged or destroyed. Raising this maximum power rating usually requires larger and heavier components, which may require larger and heavier supporting structures. This is a concern only for transmitting antennas, as the power received by an antenna rarely exceeds the microwatt range.

Antennas designed specifically for reception might be optimized for noise rejection capabilities. An *antenna shield* is a conductive or low reluctance structure (such as a wire, plate or grid) which is adapted to be placed in the vicinity of an antenna to reduce, as by dissipation through a resistance or by conduction to ground, undesired electromagnetic radiation, or electric or magnetic fields, which are directed toward the active antenna from an external source or which emanate from the active antenna. Other methods to optimize for noise rejection can be done by selecting a narrow bandwidth so that noise from other frequencies is rejected, or selecting a specific radiation pattern to reject noise from a specific direction, or by selecting a polarization different from the noise polarization, or by selecting an antenna that favors either the electric or magnetic field.

For instance, an antenna to be used for reception of low frequencies (below about ten megahertz) will be subject to both man-made noise from motors and other machinery, and from natural sources such as lightning. Successfully rejecting these forms of noise is an important antenna feature. A small coil of wire with many turns is more able to reject such noise than a vertical antenna. However, the vertical will radiate much more effectively on transmit, where extraneous signals are not a concern.

Basic antenna models



Typical US multiband TV antenna (aerial)

There are many variations of antennas. Below are a few basic models. More can be found in Category:Radio frequency antenna types.

- The isotropic radiator is a purely theoretical antenna that radiates equally in all directions. It is considered to be a point in space with no dimensions and no mass. This antenna cannot physically exist, but is useful as a theoretical model for comparison with all other antennas. Most antennas' gains are measured with reference to an isotropic radiator, and are rated in dBi (decibels with respect to an isotropic radiator).
- The dipole antenna is simply two wires pointed in opposite directions arranged either horizontally or vertically, with one end of each wire connected to the radio and the other end hanging free in space. Since this is the simplest practical antenna, it is also used as a reference model for other antennas; gain with respect to a dipole is labeled as dBd. Generally, the dipole is considered to be omnidirectional in the plane perpendicular to the axis of the antenna, but it has deep nulls in the directions of the axis. Variations of the dipole include the folded dipole, the half wave antenna, the ground plane antenna, the whip, and the J-pole.
- The Yagi-Uda antenna is a directional variation of the dipole with parasitic elements added which are functionality similar to adding a reflector and lenses (directors) to focus a filament light bulb.
- The random wire antenna is simply a very long (at least one quarter wavelength) wire with one end connected to the radio and the other in free space, arranged in any way most convenient for the space available. Folding will reduce effectiveness and make theoretical analysis extremely difficult. (The added length helps more than the folding typically hurts.) Typically, a random wire antenna will also require an antenna tuner, as it might have a random impedance that varies non-linearly with frequency.
- The horn is used where high gain is needed, the wavelength is short (microwave) and space is not an issue. Horns can be narrow band or wide band, depending on their shape. A horn can be built for any frequency, but horns for lower frequencies are typically impractical. Horns are also frequently used as reference antennas.
- The parabolic antenna consists of an active element at the focus of a parabolic reflector to reflect the waves into a plane wave. Like the horn it is used for high gain, microwave applications, such as satellite dishes.
- The patch antenna consists mainly of a square conductor mounted over a groundplane. Another example of a planar antenna is the tapered slot antenna (TSA), as the Vivaldi-antenna.

Practical antennas

"Rabbit ears" set-top antenna

Although any circuit can radiate if driven with a signal of high enough frequency, most practical antennas are specially designed to radiate efficiently at a particular frequency. An example of an inefficient antenna is the simple Hertzian dipole antenna, which radiates over wide range of frequencies and is useful for its small size. A more efficient variation of this is the half-wave dipole, which radiates with high efficiency when the signal wavelength is twice the electrical length of the antenna.

One of the goals of antenna design is to minimize the reactance of the device so that it appears as a resistive load. An "antenna inherent reactance" includes not only the distributed reactance of the active antenna but also the natural reactance due to its location and surroundings (as for example, the capacity relation inherent in the position of the active antenna relative to ground). Reactance diverts energy into the reactive field, which causes unwanted currents that heat the antenna and associated wiring, thereby wasting energy without contributing to the radiated output. Reactance can be eliminated by operating the antenna at its resonant frequency, when its capacitive and inductive reactances are equal and opposite, resulting in a net zero reactive current. If this is not possible, compensating inductors or capacitors can instead be added to the antenna to cancel its reactance as far as the source is concerned.

Once the reactance has been eliminated, what remains is a pure resistance, which is the sum of two parts: the ohmic resistance of the conductors, and the radiation resistance. Power absorbed by the ohmic resistance becomes waste heat, and that absorbed by the radiation resistance becomes radiated electromagnetic energy. The greater the ratio of radiation resistance to ohmic resistance, the more efficient the antenna.

Effect of ground

Antennas are typically used in an environment where other objects are present that may have an effect on their performance. Height above ground has a very significant effect on the radiation pattern of some antenna types.

At frequencies used in antennas, the ground behaves mainly as a dielectric. The conductivity of ground at these frequencies is negligible. When an electromagnetic wave arrives at the surface of an object, two waves are created: one enters the dielectric and the other is reflected. If the object is a conductor, the transmitted wave is negligible and the reflected wave has almost the same amplitude as the incident one. When the object is a dielectric, the fraction reflected depends (among others things) on the angle of incidence. When the angle of incidence is small (that is, the wave arrives almost perpendicularly) most of the energy traverses the surface and very little is reflected. When the angle of incidence is near 90° (grazing incidence) almost all the wave is reflected.

Most of the electromagnetic waves emitted by an antenna to the ground below the antenna at moderate (say < 60°) angles of incidence enter the earth and are absorbed (lost). But waves emitted to the ground at grazing angles, far from the antenna, are almost totally reflected. At grazing angles, the ground behaves as a mirror. Quality of reflection depends on the nature of the surface. When the irregularities of the surface are smaller than the wavelength reflection is good.



The wave reflected by earth can be considered as emitted by the image antenna

This means that the receptor "sees" the real antenna and, under the ground, the image of the antenna reflected by the ground. If the ground has irregularities, the image will appear fuzzy.

If the receiver is placed at some height above the ground, waves reflected by ground will travel a little longer distance to arrive to the receiver than direct waves. The distance will be the same only if the receiver is close to ground.

In the drawing at right, we have drawn the angle θfar bigger than in reality. Distance between the antenna and its image is d.

The situation is a bit more complex because the reflection of electromagnetic waves depends on the polarization of the incident wave. As the refractive index of the ground (average value $\simeq 2$) is bigger than the refractive index of the air ($\simeq 1$), the direction of the component of the electric field parallel to the ground inverses at the reflection. This is equivalent to a phase shift of πradians or 180°. The vertical component of the electric field reflects without changing direction. This sign inversion of the parallel component and the non-inversion of the perpendicular component would also happen if the ground were a good electrical conductor.



The vertical component of the current reflects without changing sign. The horizontal component reverses sign at reflection.

This means that a receiving antenna "sees" the image antenna with the current in the same direction if the antenna is vertical or with the current inverted if the antenna is horizontal.

For a vertical polarized emission antenna the far electric field of the electromagnetic wave produced by the direct ray plus the reflected ray is:

$$|E_{\perp}| = 2\,|E_{\theta_1}|\left|\cos\left(\tfrac{kd}{2}\sin\theta\right)\right|$$

The sign inversion for the parallel field case just changes a cosine to a sine:

$$|E_{\parallel}| = 2\,|E_{\theta_1}|\left|\sin\left(\tfrac{kd}{2}\sin\theta\right)\right|$$

In these two equations:

- $E_{\theta 1}$is the electrical field radiated by the antenna if there were no ground.
- $k=\frac{2\pi}{\lambda}$is the wave number.
- $\lambda$is the wave length.

- d is the distance between antenna and its image (twice the height of the center of the antenna).



Radiation patterns of antennas and their images reflected by the ground. At left the polarization is vertical and there is always a maximum for $\theta=0$. If the polarization is horizontal as at right, there is always a zero for $\theta=0$.

For emitting and receiving antenna situated near the ground (in a building or on a mast) far from each other, distances traveled by direct and reflected rays are nearly the same. There is no induced phase shift. If the emission is polarized vertically the two fields (direct and reflected) add and there is maximum of received signal. If the emission is polarized horizontally the two signals subtracts and the received signal is minimum. This is depicted in the image at right. In the case of vertical polarization, there is always a maximum at earth level (left pattern). For horizontal polarization, there is always a minimum at earth level. Note that in these drawings the ground is considered as a perfect mirror, even for low angles of incidence. In these drawings the distance between the antenna and its image is just a few wavelengths. For greater distances, the number of lobes increases.

Note that the situation is different–and more complex–if reflections in the ionosphere occur. This happens over very long distances (thousands of kilometers). There is not a direct ray but several reflected rays that add with different phase shifts.

This is the reason why almost all public address radio emissions have vertical polarization. As public users are near ground, horizontal polarized emissions would be poorly received. Observe household and automobile radio receivers. They all have vertical antennas or horizontal ferrite antennas for vertical polarized emissions. In cases where the receiving antenna must work in any position, as in mobile phones, the emitter and receivers in base stations use circular polarized electromagnetic waves.

Classical (analog) television emissions are an exception. They are almost always horizontally polarized, because the presence of buildings makes it unlikely that a good emitter antenna image will appear. However, these same buildings reflect the electromagnetic waves and can create ghost images. Using horizontal polarization, reflections are attenuated because of the low reflection of electromagnetic waves whose magnetic field is parallel to the dielectric surface near the Brewster's angle. Vertically polarized analog television has been used in some rural areas. In digital terrestrial television reflections are less obtrusive, due to the inherent robustness of digital signalling and built-in error correction.

Mutual impedance and interaction between antennas



Mutual impedance between parallel $\frac{\lambda}{2}$dipoles not staggered. Curves **Re** and **Im** are the resistive and reactive parts of the impedance.

Current circulating in any antenna induces currents in all others. One can postulate a **mutual impedance** Z_{12}between two antennas that has the same significance as the $j\omega M$in ordinary coupled inductors. The mutual impedance Z_{12}between two antennas is defined as:

$$Z_{12} = \frac{v_2}{i_1}$$

where $i_1$is the current flowing in antenna 1 and $v_2$is the voltage that would have to be applied to antenna 2–with antenna 1 removed–to produce the current in the antenna 2 that was produced by antenna 1.

From this definition, the currents and voltages applied in a set of coupled antennas are:

$$\begin{array}{ccccccccc} v_1 & = & i_1 Z_{11} & + & i_2 Z_{12} & + & \cdots & + & i_n Z_{1n} \\ v_2 & = & i_1 Z_{21} & + & i_2 Z_{22} & + & \cdots & + & i_n Z_{2n} \\ \vdots & & \vdots & & \vdots & & & & \vdots \\ v_n & = & i_1 Z_{n1} & + & i_2 Z_{n2} & + & \cdots & + & i_n Z_{nn} \end{array}$$

where:

- v_i is the voltage applied to the antenna *i*
- Z_{ii} is the impedance of antenna *i*
- Z_{ij} is the mutual impedance between antennas *i* and *j*

Note that, as is the case for mutual inductances,

$$Z_{ij} = Z_{ji}$$

This is a consequence of Lorentz reciprocity. If some of the elements are not fed (there is a short circuit instead a feeder cable), as is the case in television antennas (Yagi-Uda antennas), the corresponding v_i are zero. Those elements are called parasitic elements. Parasitic elements are unpowered elements that either reflect or absorb and reradiate RF energy.

In some geometrical settings, the mutual impedance between antennas can be zero. This is the case for crossed dipoles used in circular polarization antennas.

Antenna

Antennas and antenna arrays

A Yagi-Uda beam antenna.



Rooftop TV antenna. It is actually three Yagi antennas. The longest elements are for the low band, while the medium and short elements are for the high and UHF band.

Examples of US 136-174 MHz base station antennas.



Low cost LF time signal receiver, antenna (left) and receiver (right).



"Rabbit ears" antenna



AM loop antenna

Antennas and supporting structures



A building rooftop supporting numerous dish and sectored mobile telecommunications antennas (Doncaster, Victoria, Australia).



A water tower in Palmerston, Northern Territory with radio broadcasting and communications antennas.



A three-sector telephone site in Mexico City.



Telephone site concealed as a palm tree.

Diagrams as part of a system


LEGEND
Receive coaxial cables
Transmit coaxial cables
Controller Data
T=Transmit frequency
R=Receive frequency
Receive antenna
Transmit antenna
Central Controller
Receiver Multicoupler
Channel 1
T860.0375 MHz
R815.0375 MHz
Antenna Combining Network
Channel 2
T857.3375 MHz
R812.3375 MHz
Channel 3
T858.3375 MHz
R813.3375 MHz
Antenna Combining Network
Channel 4
T859.3375 MHz
R814.3375 MHz
Channel 5
T860.3375 MHz
R815.3375 MHz

Antennas may be connected through a multiplexing arrangement in some applications like this trunked two-way radio example.


ANTENNA
TRANSMIT/RECEIVE SWITCH
RECEIVER
TRANSMITTER
CONTROL AND POWER SUPPLY
BANDPASS CAVITY
ISOLATOR
RADIO BASE STATION

Antenna network for an emergency medical services base station.

Chapter 6

Television Antenna



A Winegard HD-7084P 68 element VHF/UHF aerial antenna

A **television antenna**, or **TV aerial**, is an antenna specifically designed for the reception of over the air broadcast television signals, which are transmitted at frequencies from about 41 to 250 MHz in the VHF band, and 470 to 960 MHz in the UHF band in different countries. To cover this range antennas generally consist of multiple conductors of different lengths which correspond to the wavelength range the antenna is intended to receive. The length of the elements of a TV antenna are usually half the wavelength of the signal they are intended to receive. The wavelength of a signal equals the speed of light (c) divided by the frequency. The design of a television broadcast receiving antenna is the same for the older analog transmissions and the digital television transmissions which are replacing them Sellers often claim to supply a special "digital" or "high definition" antenna advised as a replacement for an existing analog antenna, even if satisfactory: this is misinformation to generate sales of unneeded equipment.

Simple/indoor



Very common "rabbit ears" set-top antenna of older model

Simple half-wave dipole VHF antennas or UHF loop antennas that are made to be placed indoors are often used for television (and VHF radio); these are often called "rabbit ears" or "bunny aerials". because of their appearance. The length of the telescopic "ears" can be adjusted by the user, and should be about one half of the wavelength of the signal for the desired channel. These are not as efficient as an aerial rooftop antenna since they are less directional and not always adjusted to the proper length for the desired channel. Dipole antennas are bi-directional, that is, they receive evenly forward and backwards, and also cover a broader band than antennas with more elements. This makes them less efficient than antennas designed to maximise the signal from a narrower angle in one direction.

Coupled with the poor placing, indoors and closer to the ground, they are much worse than multi-element rooftop antennas at receiving signals which are not very strong, although often adequate for nearby transmitters, in which case they may be adequate and cheap. These simple antennas are called set-top antennas because they are often placed on top of the television set or receiver.

The actual length of the ears is optimally about 91% of half the wavelength of the desired channel in free space. Quarter-wave television antennas are also used. These use a single element, and use the earth as a ground plane; therefore, no ground is required in the feed line.*a*

Outdoor



An aerial or rooftop antenna generally consists of multiple conductive elements that are arranged such that it is a directional antenna. The length of the elements is about one half of the signal wavelength. Therefore, the length of each element corresponds to a certain frequency.

In a combined VHF/UHF antenna the longer elements (for picking up VHF frequencies) are at the "back" of the antenna, relative to the device's directionality, and the much shorter UHF elements are in the "front", and the antenna works best when "pointing" to the source of the signal to be received. The smallest elements in this design, located in the "front", are UHF director elements, which are usually identical and give the antenna its directionality, as well as improving gain. The longest elements, located in the "back" of the antenna form a VHF phased array. Other long elements may be UHF reflectors Another common aerial antenna element is the corner reflector, a type of UHF reflector which increases gain and directionality for UHF frequencies.

An antenna can have a smaller or larger number of directors; the more directors it has (requiring a longer boom), and the more accurate their tuning, the higher its gain will be. For the commonly used Yagi antenna this is not a linear relationship. Antenna gain is the ratio of the signal received from the preferred direction to the signal from an ideal omnidirectional antenna. Gain is inversely proportional to the antenna's acceptance angle. The thickness of the rods on a Yagi antenna and its bandwidth are inversely proportional; thicker rods provide a wider band. Thinner rods are preferable to provide a narrower band, hence higher gain in the preferred direction; however, they must be thick enough to withstand wind.

Two or more directional rooftop antennas can be set up and connected to one receiver. Antennas designed for rooftop use are sometimes located in attics.

Sometimes television transmitters are organised such that all receivers in a given location need receive transmissions in only a relatively narrow band of the full UHF television spectrum and from the same direction, so that a single antenna provides reception from all stations.

Types of outdoor antenna



A UHF television antenna

An antenna pole setup in a chimney, reaching 35 feet (10.7 meters) off the ground

Small multi-directional: The smallest of all outdoor television antennas. They are designed to receive equal amounts of signal from all directions. These generally receive signals up to a maximum of thirty miles away from the transmitting station, greatly depending on the type. But, things such as large buildings or thick woods may greatly affect signal. They come in many different styles, ranging from small dishes to small metal bars, some can even mount on existing satellite dishes.

Medium multi-directional: A step up from the small multi-directional, these also receive signals from all directions. These usually require an amplifier in situations when long cable lengths are between the television receiver and the antenna. Styles are generally similar to small multi-directionals, but slightly larger.

Large multi-directional: These are the largest of all multi-directional outdoor television antennas. Styles include large "nets" or dishes, but can also greatly vary. Depending on the type, signal reception usually ranges from 30 to up to 70 miles.

Small directional: The smallest of all directional antennas, these antennas are multi-element antennas, typically placed on rooftops. This style of antenna receives signals generally equal to that of large multi-directionals. One advantage that small directionals hold, however, is that they can significantly reduce "ghosting" effects of television picture.

Medium directional: These antennas are the ones most often seen on suburban rooftops. Usually consisting of many elements, and slightly larger than the small directionals, these antennas are ideal for receiving television signals in suburban areas. Signal usually ranges from 30 to 60 miles away from the broadcasting station.

Large directional: The largest of all common outdoor television antennas, these antennas are designed to receive the weakest available stations in an area. Larger than the medium directional, this type of antenna consists of many elements and is usually used in rural areas, where reception is difficult. When used in conjunction with an amplifier, these antennas can usually pick up stations from 60 up to and over 100 miles, depending on the type.

The use of outdoor antennas with an amplifier can improve signal on low signal strength channels. If the signal quality is low repositioning the antenna onto a high mast will improve signal

Installation

A short antenna pole next to a house; this setup would only work well for receiving signals on that side of the house as they would not go through stone, especially.

Multiple Yagi TV aerials in Israel

Antennas are commonly placed on rooftops, and sometimes in attics. Placing an antenna indoors significantly attenuates the signal available to it. Directional antennas must be pointed at the transmitter they are receiving; in most cases great accuracy is not needed. In a given region it is sometimes arranged that all television transmitters are located in roughly the same direction and use frequencies space closely enough that a single antenna suffices for all. A single transmitter location may transmit signals for several channels.

Analog television signals are susceptible to ghosting in the image, multiple closely-spaced images giving the impression of blurred and repeated images of edges in the picture. This was due to the signal being reflected from nearby objects (buildings, tree, mountains); several copies of the signal, of different strengths and subject to different delays, are picked up. This was different for different transmissions. Careful positioning of the antenna could produce a compromise position which minimized the ghosts on different channels. Ghosting is also possible if multiple antennas connected to the same receiver pick up the same station, especially if the lengths of the cables connecting them to the splitter/merger were different lengths or the antennas were too close together. Analog television is being replaced by digital, which is not subject to ghosting.

Rooftop and other outdoor antennas

Aerials are attached to roofs in various ways, usually on a pole to elevate it above the roof. This is generally sufficient in most areas. In some places; however, such as a deep valley or near taller structures, the antenna may need to be placed significantly higher, using a lattice tower or mast.

The higher the antenna is placed, the better it will perform. An antenna of higher gain will be able to receive weaker signals from its preferred direction. Intervening buildings, topographical features (mountains), and dense forest will weaken the signal; in many cases the signal will be reflected such that a usable signal is still available. There are physical dangers inherent to high or complex antennas, such as the structure falling or being destroyed by the weather. There are also varying local ordinances which restrict and limit such things as the height of a structure without obtaining permits. For example, in the USA, the Telecommunications Act of 1996 allows any homeowner to install "An antenna that is designed to receive local television broadcast signals", but that "masts higher than 12 feet above the roof-line may be subject to local permitting requirements."

Indoor antennas

As discussed previously, antennas may be placed indoors where signals are strong enough to overcome antenna shortcomings. The antenna is simply plugged into the television receiver and placed conveniently, often on the top of the receiver ("set-top"). Sometimes the position needs to be experimented with to get the best picture. Indoor antennas can also benefit from RF amplification, commonly called a TV booster. Indoor antennas will never be an option in weak signal areas.

Attic installation

Sometimes it is desired not to put an antenna on the roof; in these cases, antennas designed for outdoor use are often mounted in the attic or loft, although antennas designed for attic use are also available. Putting an antenna indoors significantly decreases its performance due to lower elevation above ground level and intervening walls; however, in strong signal areas reception may be satisfactory. One layer of asphalt shingles, roof felt, and a plywood roof deck are considered to attenuate the signal to about half.

Multiple antennas, rotators



Two aerials setup on a roof. Spaced horizontally and vertically

It is sometimes desired to receive signals from transmitters which are not in the same direction. This can be achieved, for one station at a time, by using a rotator operated by an electric motor to turn the antenna as desired. Alternatively, two or more antennas, each pointing at a desired transmitter and coupled by appropriate circuitry, can be used. To prevent the antennas interfering with each other, the vertical spacing between the booms must be at least half the wavelength of the lowest frequency to be received (Distance=λ/2). The wavelength of 54 MHz (Channel 2) is 5.5 meters (λ x f = c) so the antennas must be a minimum of 2.25 meters, or ~89 inches apart. It is also important that the cables connecting the antennas to the signal splitter/merger be exactly the same length, to prevent phasing issues,which cause ghosting with analog reception. That is, the antennas might both pick up the same station; the signal from the one with the shorter cable will reach the receiver slightly sooner, supplying the receiver with two pictures slightly offset. There may be phasing issues even with the same length of down-lead cable. Bandpass filters or "signal traps" may help to reduce this problem.

For side-by-side placement of multiple antennas, as is common in a space of limited height such as an attic, they should be separated by at least one full wavelength of the lowest frequency to be received at their closest point.

Often when multiple antennas are used, one is for a range of co-located stations and the other is for a single transmitter in a different direction.

Safety

- TV antennas are large conductors of electricity and attract lightning, acting as a lightning rod. The use of a lightning arrestor is usual to protect against this. A large grounding rod connected to both the antenna and the mast or pole is required.

- Properly installed masts, especially tall ones, are guyed with galvanized cable; no insulators are needed. They are designed to withstand worst-case weather conditions in the area, and positioned so that they do not interfere with power lines if they fall.

- There is inherent danger in being on the rooftop of a house, required for installing or adjusting a television antenna.

Chapter 7

Radio Masts and Towers

Masts of the Rugby VLF transmitter in England

A dismantled radio mast in sections

Radio masts and towers are, typically, tall structures designed to support antennas (also known as aerials) for telecommunications and broadcasting, including television. They are among the tallest man-made structures. Similar structures include electricity pylons and towers for wind turbines.

Masts are sometimes named after the broadcasting organisations that use them, or after a nearby city or town.

The Warsaw Radio Mast was the world's tallest supported structure on land, but it collapsed in 1991, leaving the KVLY/KTHI-TV mast as the tallest.

In the case of a mast radiator or radiating tower, the whole mast or tower is itself the transmitting antenna.

Mast or tower?

A radio mast base showing how virtually all support is provided by the guy-wires

The terms "mast" and "tower" are often used interchangeably. However, in structural engineering terms, a tower is a self-supporting or cantilevered structure, while a mast is held up by stays or guys. By contrast, in broadcast engineering, a tower is an antenna structure attached to the ground, whereas a mast is a vertical antenna support mounted on some other structure (which itself may be a tower, a building, or a vehicle). Masts (to use the civil engineering terminology) tend to be cheaper to build but require an extended area surrounding them to accommodate the guy wires. Towers are more commonly used in cities where land is in short supply.

There are a few borderline designs which are partly free-standing and partly guyed. For example:

- The Gerbrandy tower consists of a self-supporting tower with a guyed mast on top.
- The few remaining Blaw-Knox towers do the opposite: they have a guyed lower section surmounted by a freestanding part.
- Zendstation Smilde a tall tower with a guyed mast on top (guys go to ground)

- Torre de Collserola a guyed tower, with a guyed mast on top. (Tower portion is not free-standing.)

Materials

Steel lattice

Steel lattice tower

The steel lattice is the most widespread form of construction. It provides great strength, low weight and wind resistance, and economy in the use of materials. Lattices of triangular cross-section are most common, and square lattices are also widely used.

When built as a stayed mast, usually the whole mast is parallel-sided. One exception is the Blaw-Knox type.

When built as a tower, the structure may be parallel-sided or taper over part or all of its height. When constructed of several sections which taper exponentially with height, in the manner of the Eiffel Tower, the tower is said to be an Eiffelized one. The Crystal Palace tower in London is an example.

Tubular steel

Guyed masts are sometimes also constructed out of steel tubes. This construction type has the advantage that cables and other equipment is protected from weather influence and that the structure may look nicer. They are mainly used for FM-/TV-broadcasting, but sometimes also as mast radiator, wherefore the big mast of Mühlacker transmitting station is a good example. A disadvantage of this mast type is that it is much more affected by winds than masts with open bodies. In fact several tubular guyed masts collapsed: in the UK, these were masts the Emley Moor and Waltham TV stations, which collapsed in the 1960s, in Germany that of Bielstein transmitter, which collapsed in 1985. Not in all countries such masts were built: while in Germany, France, UK, Czech, Slovakia and the former Soviet Union multiple tubular guyed masts were built, there are nearly none in Poland and North America.

At several cities in Russia and Ukraine, between 1960 and 1965 several tubular guyed masts with crossbars running from the mast structure to the guys were built. All these masts are exclusively used for FM and TV transmission and are except of the mast in Vinnytsia between 150 and 200 metres tall. The crossbars of these masts are equipped with a gangway and are equipped with smaller antennas. Their main purpose is oscillation damping.

First modern TV Tower in Stuttgart

Reinforced concrete

Reinforced concrete towers are relatively expensive to build but provide a high degree of mechanical rigidity in strong winds. This can be important when antennas with narrow beamwidths are used, such as those used for microwave point-to-point links, and when the structure is to be occupied by people.

In the 1950s, AT&T built numerous concrete towers, more resembling silos than towers, for its first transcontinental microwave route. Many are still in use today.

In Germany and the Netherlands most towers constructed for point-to-point microwave links are built of reinforced concrete, while in the UK most are lattice towers.

Concrete towers can form prestigious landmarks, such as the CN Tower in Toronto. As well as accommodating technical staff, these buildings may have public areas such as observation decks or restaurants.

The Stuttgart TV tower was the first tower in the world to be built in reinforced concrete. It was designed in 1956 by the local civil engineer Fritz Leonhardt.

Tokyo Tower

Fibreglass

Fibreglass poles are occasionally used for low-power non-directional beacons or medium-wave broadcast transmitters.

Wood

There are fewer wooden towers now than in the past. Many were built in the UK during World War II because of a shortage of steel. In Germany before World War II wooden towers were used at nearly all medium-wave transmission sites, but all of these towers have since been demolished, except for the Gliwice Radio Tower.

Ferryside Relay is an example of a TV relay transmitter using a wooden pole.

Other types of antenna supports and structures

Poles

Shorter masts may consist of a self-supporting or guyed wooden pole, similar to a telegraph pole. Sometimes self-supporting tubular galvanized steel poles are used: these may be termed monopoles.

Buildings

In some cases, it is possible to install transmitting antennas on the roofs of tall buildings. In North America, for instance, there are transmitting antennas on the Empire State Building, the Willis Tower ,and formerly on the World Trade Center towers. When the buildings collapsed, several local TV and radio stations were knocked off the air until backup transmitters could be put into service. Such facilities also exist in Europe, particularly for portable radio services and low-power FM radio stations.

Disguised cell-sites



Completed in December 2009 at Epiphany Lutheran Church in Lake Worth, Florida, this 100' tall cross conceals equipment for T-Mobile.

Many people view bare cellphone towers as ugly and an intrusion into their neighbourhoods. Even though people increasingly depend upon cellular communications, they are opposed to the bare towers spoiling otherwise scenic views. Many companies offer to 'hide' cellphone towers in, or as, trees, church towers, flag poles, water tanks and other features. There are many providers that offer these services as part of the normal tower installation and maintenance service. These are generally called "stealth towers" or "stealth installations".

The level of detail and realism achieved by disguised cellphone towers is remarkably high; for example, such towers disguised as trees are nearly indistinguishable from the real thing, even for local wildlife (who additionally benefit from the artificial flora). Such towers can be placed unobtrusively in national parks and other such protected places, such as towers disguised as cacti in Coronado National Forest.

Even when disguised, however, such towers can create controversy; a tower doubling as a flagpole attracted controversy in 2004 in relation to the U.S. Presidential campaign of that year, and highlighted the sentiment that such disguises serve more to allow the installation of such towers in subterfuge away from public scrutiny rather than to serve towards the beautification of the landscape.

Mast radiators

A mast radiator is a radio tower or mast in which the whole structure works as an antenna. It is used frequently as a transmitting antenna for long or medium wave broadcasting.

Structurally, the only difference is that a mast radiator may be supported on an insulator at its base. In the case of a tower, there will be one insulator supporting each leg.

Telescopic, pump-up and tiltover towers

A special form of the radio tower is the *telescopic mast*. These can be erected very quickly. Telescopic masts are used predominantly in setting up temporary radio links for reporting on major news events, and for temporary communications in emergencies. They are also used in tactical military networks. They can save money by needing to withstand high winds only when raised, and as such are widely used in amateur radio.

Telescopic masts consist of two or more concentric sections and come in two principal types:

- Pump-up masts are often used on vehicles, and are raised to their full height pneumatically or hydraulically. They are usually only strong enough to support fairly small antennas.
- Telescopic lattice masts are raised by means of a winch, which may be powered by hand or an electric motor. These tend to cater for greater heights and loads than the pump-up type. When retracted, the whole assembly can sometimes be lowered to a horizontal position by means of a second tiltover winch. This enables antennas to be fitted and adjusted at ground level before winching the mast up.

Balloons and kites

A tethered balloon or a kite can serve as a temporary support. It can carry an antenna or a wire (for VLF, LW or MW) up to an appropriate height. Such an arrangement is used occasionally by military agencies or radio amateurs. The American broadcasters TV Martí broadcast a television program to Cuba by means of such a balloon.

Other special structures

For two VLF transmitters wire antennas spun across deep valleys are used. The wires are supported by small masts or towers or rock anchors. The same technique was also used for the Criggion VLF transmitter.

For ELF transmitters ground dipole antennas are used. Such structures require no tall masts. They consist of two electrodes buried deep in the ground at least a few dozen kilometres apart. From the transmitter building to the electrodes, overhead feeder lines run. These lines look like power lines of the 10 kV level, and are installed on similar pylons.

Design features

Economic and aesthetic considerations

A radio amateur's do it yourself steel-lattice tower

Felsenegg-Girstel TV-tower

Uetliberg TV-tower

Communications tower, camouflaged as a slim tree

- The cost of a mast or tower is roughly proportional to the square of its height.
- A guyed mast is cheaper to build than a self-supporting tower of equal height.
- A guyed mast needs additional land to accommodate the guys, and is thus best suited to rural locations where land is relatively cheap. An unguyed tower will fit into a much smaller plot.
- A steel lattice tower is cheaper to build than a concrete tower of equal height.
- Two small towers may be less intrusive, visually, than one big one, especially if they look identical.
- Towers look less ugly if they and the antennas mounted on them appear symmetrical.
- Concrete towers can be built with aesthetic design - and they are, especially in Continental Europe. They are sometimes built in prominent places and include observation decks or restaurants.

Masts for HF/shortwave antennas

For transmissions in the shortwave range, there is little to be gained by raising the antenna more than a few wavelengths above ground level. Shortwave transmitters rarely use masts taller than about 100 metres.

Access for riggers

Because masts, towers and the antennas mounted on them require maintenance, access to the whole of the structure is necessary. Small structures are typically accessed with a ladder. Larger structures, which tend to require more frequent maintenance, may have stairs and sometimes a lift, also called a service elevator.

Aircraft warning features

Tall structures in excess of certain legislated heights are often equipped with aircraft warning lamps, usually red, to warn pilots of the structure's existence. In the past, ruggedized and under-run filament lamps were used to maximize the bulb life. Alternatively, neon lamps were used. Nowadays such lamps tend to use LED arrays.

Height requirements vary across states and countries, and may include additional rules such as requiring a white flashing strobe in the daytime and pulsating red fixtures at night. Structures over a certain height may also be required to be painted with contrasting color schemes such as white and orange or white and red to make them more visible against the sky.

Light pollution and nuisance lighting

In some countries where light pollution is a concern, tower heights may be restricted so as to reduce or eliminate the need for aircraft warning lights. For example in the United States the 1996 Telecommunications Act allows local jurisdictions to set maximum heights for towers, such as limiting tower height to below 200 feet and therefore not requiring aircraft illumination under U.S. Federal Communications Commission (FCC) rules. The limit is more commonly set to 190 or 180 feet to allow for masts extending above the tower.

Wind-induced oscillations

One problem with radio masts is the danger of wind-induced oscillations. This is particularly a concern with steel tube construction. One can reduce this by building cylindrical shock-mounts into the construction. One finds such shock-mounts, which look like cylinders thicker than the mast, for example, at the radio masts of DHO38 in Saterland. There are also constructions, which consist of a free-standing tower (usually from reinforced concrete), onto which a guyed radio mast is installed. The best known such construction is the Gerbrandy Tower in Lopik (the Netherlands). Further towers of this building method can be found near Smilde (the Netherlands) and Fernsehturm, Waldenburg, Baden-Württemberg, Germany).

Hazard to birds

Radio, television and cell towers have been documented to pose a hazard to birds. Reports have been issued documenting known bird fatalities and calling for research to find ways to minimize the hazard that communications towers can pose to birds.

Law

Since June 2010, Telecom operators in the USA can erect new telecom masts or towers as the government has lifted the moratorium, which was earlier placed on the issuance of permits for the construction of telecommunication towers.

Chapter 8

Omnidirectional Antenna & Directional Antenna

Omnidirectional Antenna



Omnidirectional radiation pattern of a vertical dipole antenna. In this graph the antenna is at the center of the "donut". Radial distance from the center represents the power radiated in that direction. The power radiated is maximum in horizontal directions, dropping to zero directly above and below the antenna.

An **omnidirectional antenna** is an antenna which radiates power uniformly in all directions in one plane, with the radiated power decreasing with elevation angle above or below the plane, dropping to zero on the antenna's axis. This radiation pattern is often described as "donut shaped". Note that this is different from an isotropic antenna, in which the gain is uniform in *all* directions ("spherical"). Omnidirectional antennas oriented vertically are widely used for nondirectional antennas on the surface of the Earth because they radiate equally in all horizontal directions, while the power radiated drops off with elevation angle so little radio energy is aimed into the sky or down toward the earth and wasted. Omnidirectional antennas are widely used for radio broadcasting antennas, and in mobile devices that use radio such as cell phones, FM radios, walkie-talkies, Wifi, cordless phones, GPS as well as for base stations that communicate with mobile radios, such as police and taxi dispatchers and aircraft communications.

Types

Common types of low gain omnidirectional antennas are the whip antenna, "Rubber Ducky", ground plane antenna, vertically oriented dipole antenna, discone antenna, mast radiator and the horizontal loop antenna (or halo antenna) (Sometimes known colloquially as a 'circular aerial' because of the shape).

Higher gain omnidirectional antennas can also be built. "Higher gain" in this case means that the antenna radiates less energy at higher and lower elevation angles and more in the horizontal directions. High gain omnidirectional antennas are generally realized using collinear dipole arrays. These arrays consist of half-wavelength dipoles with a phase shifting method between each element that ensures the current in each dipole is in phase. The Coaxial Colinear or COCO antenna uses transposed coaxial sections to produce in-phase half-wavelength radiatiors. A Franklin Array uses short U-shaped half-wavelength sections whose radiation cancels in the far-field to bring each half-wavelength dipole section into equal phase.

Types of higher gain omnidirectional antennas are the Coaxial Colinear (COCO) antenna and Omnidirectional Microstrip Antenna (OMA).

Some planar antennas (constructed from printed circuit board) are omnidirectional antennas.



Vertical polarized VHF- UHF biconical antenna 170 – 1100 MHz with omni directional H-plane pattern.

Analysis

Omnidirectional radiation patterns are produced by the simplest practical antennas, monopole and dipole antennas, consisting of one or two straight rod conductors on a common axis. Antenna gain (G) is defined as antenna efficiency (e) multiplied by antenna directivity (D) which is expressed mathematically as: $G = eD$. A useful relationship between omnidirectional radiation pattern directivity (D) in decibels and half-power beamwidth (HPBW) based on the assumption of a $\sin b\theta / b\theta$ pattern shape is:

$$D = 10\log_{10}\left(\frac{101.5}{HPBW - 0.00272(HPBW)^2}\right)\ dB$$

Directional Antenna

Log-periodic dipole array

A **directional antenna** or **beam antenna** is an antenna which radiates greater power in one or more directions allowing for increased performance on transmit and receive and reduced interference from unwanted sources. Directional antennas like yagi antennas provide increased performance over dipole antennas when a greater concentration of radiation in a certain direction is desired.

All practical antennas are at least somewhat directional, although usually only the direction in the plane parallel to the earth is considered, and practical antennas can easily be omnidirectional in one plane.

The most common types are the yagi antenna, the log-periodic antenna, and the corner reflector, which are frequently combined and commercially sold as residential TV antennas. Cellular repeaters often make use of external directional antennas to give a far greater signal than can be obtained on a standard cell phone. Satellite Television receivers usually use parabolic antennas.

For long and medium wavelength frequencies, tower arrays are used in most cases as directional antennas.



RFID

Design Fundamentals and Applications

Albert Lozano-Nieto

CRC Press
Taylor & Francis Group

RFID

Design
Fundamentals
and
Applications

© 2011 by Taylor and Francis Group, LLC

RFID
Design Fundamentals and Applications

Albert Lozano-Nieto

CRC Press
Taylor & Francis Group
Boca Raton London New York

CRC Press is an imprint of the
Taylor & Francis Group, an **informa** business

© 2011 by Taylor and Francis Group, LLC

CRC Press
Taylor & Francis Group
6000 Broken Sound Parkway NW, Suite 300
Boca Raton, FL 33487-2742

© 2011 by Taylor and Francis Group, LLC
CRC Press is an imprint of Taylor & Francis Group, an Informa business

No claim to original U.S. Government works

Printed in the United States of America on acid-free paper
10 9 8 7 6 5 4 3 2 1

International Standard Book Number: 978-1-4200-9125-0 (Hardback)

This book contains information obtained from authentic and highly regarded sources. Reasonable efforts have been made to publish reliable data and information, but the author and publisher cannot assume responsibility for the validity of all materials or the consequences of their use. The authors and publishers have attempted to trace the copyright holders of all material reproduced in this publication and apologize to copyright holders if permission to publish in this form has not been obtained. If any copyright material has not been acknowledged please write and let us know so we may rectify in any future reprint.

Except as permitted under U.S. Copyright Law, no part of this book may be reprinted, reproduced, transmitted, or utilized in any form by any electronic, mechanical, or other means, now known or hereafter invented, including photocopying, microfilming, and recording, or in any information storage or retrieval system, without written permission from the publishers.

For permission to photocopy or use material electronically from this work, please access www.copyright.com (http://www.copyright.com/) or contact the Copyright Clearance Center, Inc. (CCC), 222 Rosewood Drive, Danvers, MA 01923, 978-750-8400. CCC is a not-for-profit organization that provides licenses and registration for a variety of users. For organizations that have been granted a photocopy license by the CCC, a separate system of payment has been arranged.

Trademark Notice: Product or corporate names may be trademarks or registered trademarks, and are used only for identification and explanation without intent to infringe.

Library of Congress Cataloging-in-Publication Data

Lozano-Nieto, Albert.
  RFID design fundamentals and applications / author, Albert Lozano-Nieto.
    p. cm.
  "A CRC title."
  Includes bibliographical references and index.
  ISBN 978-1-4200-9125-0 (hardcover : alk. paper)
  1. Radio frequency identification systems. I. Title.

TK6570.I34L69 2011
006--dc22 2010029742

Visit the Taylor & Francis Web site at
http://www.taylorandfrancis.com

and the CRC Press Web site at
http://www.crcpress.com

© 2011 by Taylor and Francis Group, LLC

To Debbie, for her unconditional and always present love and support. For having changed my life.

To Ramon Pallas-Areny, for having been a role model. For instilling in me his passion for education and research.

© 2011 by Taylor and Francis Group, LLC

Contents

Preface....ix
About the Author....xi

1 Basic Principles of Radiofrequency Identification....1

2 Antennas for RFID Transponders....13

3 Transponders....49

4 Antennas for Interrogators....85

5 Interrogators....119

6 Interrogator Communication and Control....155

7 The Air Communication Link....177

8 Commands for Transponders....203

References and Further Reading....253

Index....257

© 2011 by Taylor and Francis Group, LLC

Preface

Although the basic concepts of radiofrequency identification (RFID) were developed during World War II, only recently has RFID become a ubiquitous technology in today's industry, market, and society. In 2005, the U.S. Department of Defense required all suppliers to affix passive RFID tags to cases and pallets used for shipment. Almost simultaneously, large private enterprises, such as Wal-Mart, required similar tagging for their own supplies. These two initiatives were instrumental in the acceptance and use of RFID as a tool to increase productivity. More importantly, these mandates have permeated a large number of large and medium-sized businesses that are incorporating RFID techniques to reduce costs and increase revenue. Even small companies are currently considering using this technique in their operations. RFID systems are widely used in the chain supply and logistics industry, for example, to track pallets and cases of products. Large companies benefit from the increased accuracy of their inventory as well as the automation of these processes. Retailers use this technology to prevent theft of their products using tags embedded in the packaging. When the product is purchased by the customer, the cashier or checkout clerk changes the code in the tag, for example, by waving it over a reader or writer, making the tag invisible to the reader located in the exit doors. However, when the product is stolen or the cashier has failed to change the code in the tag, the readers located near the exit doors detect the signal from the tag and start an alarm. RFID is also being used to authenticate that the cold chain in food products has not been compromised, to combat the counterfeit of pharmaceutical drugs, and to establish the authenticity and history of critical parts, for example, in the repair and maintenance of aircraft. New and enhanced applications of using RFID are being developed every day as the number of industries that incorporate this technology expands. This increase in the market size of RFID technologies will, in turn, drive the need for an increasing number of professionals proficient in the evaluation and deployment of these systems.

This book gives the reader an understanding of the fundamental principles involved in the design and characterization of RFID technologies. While the documentation that the manufacturers of each individual component provide is extensive and complete, synthesizing and using this information can represent a challenge to the user: the required information is complex and, more importantly, it is necessary to consult and integrate the information from several manufacturers of different components. This book seeks to solve this problem by presenting a systematic approach in analyzing the different components that make up the whole RFID system, giving the reader the necessary tools to have a clear understanding of them. Readers may

© 2011 by Taylor and Francis Group, LLC

choose to read the entire book or just to focus on specific chapters of interest without detriment.

This book contains eight chapters, each one of them a systematic approach to studying the different components that constitute the RFID system. Chapter 1 presents an overview of RFID with a focus on the main components that make up the system. Chapter 2 discusses the types of antennas used in transponders, also known as *tags*. Chapter 3 studies the different parts that make up the transponder, such as its power-harvesting and analog circuits, the different memory structure, and logic circuits. It also discusses the mechanical characteristics of these circuits and their requirements for handling and placement on the transponders. Chapter 4 describes the types of antennas used for RFID interrogators, also known as *readers*, focusing on their design and construction to meet specific requirements. Because of their intrinsic differences, this chapter discusses separately the requirements for antennas based on the frequency of transmission. Chapter 5 discusses the structure and parts that make up the interrogator with a special emphasis on the different types of modulation being used. The chapter also describes the organization and characteristics of commercially available transponders. Chapter 6 studies the different types of communication links between the interrogator and its host computer, either proprietary protocols used by specific manufacturers or standardized communication protocols. Chapter 7 describes the air communications link that is the link between transponders and interrogators. This chapter addresses the different elements of the communication link, the different mode of operation for transponders operating at different frequencies, as well as the principles of arbitration and anticollision. The last chapter in the book, Chapter 8, presents an overview of the different commands used by transponders. This chapter does not pretend to be an exhaustive repository of the available commands for any transponder in the market. Instead, it focuses on the commonalities between the most frequently used functions in the commands employed by different manufacturers. The book finishes with a series of references that can be used by interested readers to explore in depth some of the aspects described in this book.

The majority of books on RFID today are focused on the deployment and the commercial uses of RFID. This book, in turn, is focused on explaining how the different components that make up the RFID system are designed and how they interact with each other. The book is directed toward professionals and students in electronics, telecommunications, and new technologies. However, it will also be useful for those who want to experiment with or enhance their knowledge of RFID systems.

© 2011 by Taylor and Francis Group, LLC

About the Author

Albert Lozano-Nieto is professor of engineering at Penn State. His main teaching responsibilities are focused on the baccalaureate degree in electrical engineering technology at the Wilkes-Barre campus. A native of Barcelona, Spain, he joined Penn State in 1996. Dr. Lozano-Nieto received his doctoral degree in electrical engineering in 1994 and his baccalaureate degree in telecommunication engineering in 1988, both from the Polytechnic University of Catalonia, Barcelona, Spain. He is also an RFID+ certified professional, awarded by the Computing Technology Industry Association (CompTIA), since 2008.

Dr. Lozano-Nieto's research interests focus on the study of errors associated with bioelectrical impedance measurements, as well as on developing new pedagogical approaches to enhance engineering and engineering technology education. On a personal level, he has a strong interest in infrared photography, high-altitude balloons, and amateur rocketry.

© 2011 by Taylor and Francis Group, LLC

1

Basic Principles of Radiofrequency Identification

CONTENTS

1.1 Basics of RFID 1
1.2 Passive versus Active RFID Systems 5
1.3 Functional Classification of RFID Transponders 6
1.4 Applications and Frequency Selection 7

Although the widespread use of radiofrequency identification (RFID) is recent, the technology itself is several years old. RFID was first developed during World War II in order to distinguish between friend and enemy aircraft. Several years later, thanks to the technological advances in microelectronics, wireless communications, and computer networks, RFID has come of age. It has now become a technology that is mature enough to be mass-marketed at competitive cost and become a critical player in the global market. This chapter introduces the reader to the different parts that make up a RFID system and provides an overview of the different concepts that will be described in depth in the upcoming chapters.

1.1 Basics of RFID

The basic function of an RFID system is to automatically retrieve the information that has been previously inserted into specific integrated circuits, as seen in Figure 1.1. RFID systems were first developed in automatic identification laboratories as a natural evolution of the different technologies they use. Different automatic identification systems use different methods to transmit the identifying information. For example, bar code technology uses light as the transmission media, while RFID systems use radio waves. In this context, the two main elements of RFID systems are the devices used to carry this information and the equipment used to automatically capture or retrieve the information.

The devices that store and carry the information are called *transponders* or *tags* and are shown in Figure 1.2. Although the industry commonly refers to them as *tags* mainly due to their physical shape and the fact that they are

© 2011 by Taylor and Francis Group, LLC


Object X
Information X
Object Y
Information Y
Automatic Identification System
Information 1
Object 1
Information 2
Object 2
...
...
Information Z
Object Z

FIGURE 1.1
Information transfer in an automatic identification system.



FIGURE 1.2
Several types of transponders used in RFID systems.

© 2011 by Taylor and Francis Group, LLC

mostly used to tag pallets or cases of goods, the name *transponder* reflects better the function of these devices.

The device that is used to capture and transfer information is commonly called a *reader*, because in earlier RFID systems they were only able to read the information sent by the transponders. However, with the development of new functions and applications of RFID systems, the name *interrogator* reflects better the function of this subsystem. Therefore, this book will use the names *transponder* and *interrogator* when referring to these elements.

Transponders must have the circuitry needed to harvest power from the electromagnetic fields generated by the interrogator, the necessary memory elements, as well as the different control circuits. The simplest transponders contain only read-only memory (ROM), while more sophisticated transponders also include random access memory (RAM) and nonvolatile programmable read-only memory (PROM) or electrically erasable programmable read-only memory (EEPROM). ROM usually contains the identification string for the transponder and instructions for its operating system. RAM is normally used for temporary data storage when the transponder communicates with the interrogator. PROM or EEPROM is normally used to incorporate additional functionality depending on the application. The memory capacity of transponders ranges from a single bit to several kilobits. Single-bit transponders are typically used in retail electronic surveillance in which there are only two possible states: *article paid* and *article not paid*. Memory sizes of up to 128 bits are enough to store the individual transponder identification number with several check bits. Memories up to 512 bits are normally user programmable, in which in addition to the individual identification number the memory can hold additional information required by its application. Higher capacity memories can be seen as carriers for the transport of data files. They are also used in applications in which there are several sensors attached to the transponder.

Interrogators have vastly different complexity levels depending on the type of transponders they support as well as their specific purpose. In any case, they all must provide the basic functionality to communicate with the transponders, first by energizing them and second by establishing a communications link. The complexity of the communications link can also vary considerably depending on the desired reliability. The reliability of the communications link between transponder and interrogator can be enhanced by adding parity checks, error detection, and error detection and correction. However, the use of these schemes will result in a lower transmission rate. Figure 1.3 shows a picture of a basic interrogator in which it is possible to see the coiled antenna and some of the electronic circuits.

RFID systems contain more elements in addition to the transponder and interrogator. First, the communication between transponder and interrogator is not possible—or becomes extremely deficient—without the appropriate radiant elements that will transfer the information between these two subsystems in the form of electromagnetic energy. Both transponder and

© 2011 by Taylor and Francis Group, LLC



FIGURE 1.3
Basic RFID interrogator operating in the low-frequency (LF) range.

interrogator need to use the appropriate antennas to transfer information. As will be discussed in Chapter 2, the antenna dimensions in commercially available transponders and interrogators are much shorter than their ideal dimensions. This results in seriously limiting the transfer of energy between interrogators and transponders.

In addition to the transponders, the interrogators, and their antennas, the RFID system requires a *host computer* connected to the interrogator. This host computer provides a certain level of intelligence and acts like the interface between the RFID system and the ultimate application. Therefore, the interrogator must have the means to at least perform basic communication functions with the interrogator. A large number of today's applications require more than one interrogator running on a network rather than the single, stand-alone interrogator that was typical of earlier systems. Finally, an *edge server* is normally used between the host computer and the network in which the application is running.

In addition to these elements (shown in Figure 1.4), most of them hardware based, a typical RFID system contains several software elements. The *firmware* is the software that runs inside the interrogator in order to provide it with its basic functions. Some interrogators may also run one or more software *applications* that enhance the versatility of the interrogator. The name *middleware* encompasses the software applications that run in the background of the system, typically after the host computer. Finally, most applications require the use of one or several *databases* used to link the stored message

© 2011 by Taylor and Francis Group, LLC



FIGURE 1.4
Basic structure of an RFID system.

sent by the transponder with more detailed information that can identify the transponder and provide additional information.

1.2 Passive versus Active RFID Systems

Passive RFID systems are those systems that use passive transponders. Passive transponders do not have an internal power source. They harvest the energy needed by their internal circuits from the electromagnetic field generated by the interrogator. For this reason, they have a short range, limited to a few feet and often, more realistically, to a few inches. Because they don't have an internal source of energy, the user does not need to worry about the status of the battery. Furthermore, their manufacturing and production costs are very low. The RFID transponders and systems described in this book are all passive.

Active RFID systems, on the other hand, use active transponders. Active transponders have an internal power source, typically a battery that allows broadcasting the signal to the interrogator. Because of not being limited to the power harvested by the antenna, they have an extended read range, typically several hundred feet. However, the inclusion of the power source increases their cost in two ways: the cost of the battery itself as well as the maintenance costs required to check the status of the internal power source and replace it when it has reached an unacceptably low level. The cost of an active transponder is approximately 100 times higher than the cost of a passive transponder. Active transponders typically operate in the ultra-high-frequency (UHF) and microwave ranges. A new type of active RFID transponder is

© 2011 by Taylor and Francis Group, LLC

linked to the use of RFID-enabled cell phones that can emulate an active tag. In this case, the problem of battery maintenance is solved as the user keeps the cell phone charged as part of its regular maintenance.

A third type of transponder is called *semipassive* or *battery-assisted transponder*. These transponders also include a battery, but contrary to active transponders, the battery is not used to generate the power to transmit the signal to the interrogator. Instead, the battery is used to support secondary functions like the data logging from different types of sensors. These transponders also harvest the energy from the electromagnetic field generated by the interrogator to power its internal circuits other than the sensing and data-logging parts.

1.3 Functional Classification of RFID Transponders

A functional classification of RFID transponders is based on their electronic product code (EPC) class. EPC is the application of one specific type of RFID technology within the consumer packaged goods industry. Within this classification, RFID transponders are divided into different classes and generations:

Generation 1, Class 0: Passive tags with read-only functionality. These are also called *write one, read many* (WORM) transponders. These transponders are programmed at the factory with their unique identification number. The user is not able to change it or include additional information.

Generation 1, Class 0+: These are also WORM transponders. They differ from Generation 1, Class 0 transponders in that it is the user who programs them. After they have been programmed by the user, no further programming or changing of data is allowed.

Generation 1, Class 1: These transponders were similar to Generation 1, Class 0 or 0+ transponders, but could be read by interrogators from other companies. Gen 1, Class 1 transponders have evolved into the different transponders from Generation 2.

Whereas Generation 1 transponders employ proprietary data structures and can be read only by interrogators manufactured by the same vendor, Generation 2 transponders are vendor neutral in their specifications. This means that as they have developed (following agreed upon standards), they can be read with interrogators from multiple vendors. These transponders provide additional features, for example the elimination of duplicate reads within the read range. They are also more reliable than Generation 1 transponders and support faster read rates. The user of Generation 2 transponders

© 2011 by Taylor and Francis Group, LLC

can access specific parts of their memory as these are rewritable transponders.

Generation 2, Class 1: These transponders are WORM transponders. They are also programmed at the factory, but they can be read with equipment from different vendors, support the higher read rates, and have more noise immunity than the Generation 1 transponders.

Generation 2, Class 2: These transponders are rewritable transponders. They can be written several times by the user using equipment different from the vendor's equipment.

Generation 2, Class 3: These transponders are the semipassive or battery-assisted transponders.

Generation 2, Class 4: This refers to active transponders.

Generation 2, Class 5: These transponders are essentially interrogators. Transponders that follow Generation 2, Class 5 must be able to power other transponders.

1.4 Applications and Frequency Selection

RFID systems come in different flavors from the point of view of the frequency they use. Selecting the most adequate frequency is a function of two variables: the technological developments of systems at the different operating frequencies—directly related to the cost of systems—as well as the properties of electromagnetic waves at those different frequencies.

The initial users of RFID systems found systems operating in the low-frequency (LF) range followed a few years later by systems operating in the high-frequency (HF) range. Therefore, their selection of systems was limited to these two broad frequency ranges even if those were not the most adequate for their specific applications. Recent years have seen an increase in the number of available RFID systems operating in the UHF range as well as a reduction of their economic cost. It is possible to expect a similar trend in upcoming years for RFID systems operating in the microwave range to become more available and more affordable. This will help the final users to make decisions on what type of RFID systems to deploy based on technical reasons rather than based on the availability and cost of these systems.

Table 1.1 presents a broad view of the frequency spectrum used by RFID systems as well as the most common frequencies for each band. It is necessary to note that Table 1.1 is not exhaustive because it is possible to find systems, within each frequency band, operating at other frequencies.

The LF band has been used by RFID systems for several years. This fact, together with the less stringent requirements of the electronics operating in this frequency range, has made these systems very cost-effective. Their

© 2011 by Taylor and Francis Group, LLC

TABLE 1.1

Commonly Used Frequency Band for RFID Systems

Frequency Band	Frequency Range	Typical Frequencies Used in RFID Systems
Low Frequency (LF)	100 kHz – 500 kHz	125 kHz 134.2 kHz
High Frequency (HF)	10 MHz – 15 MHz	13.56 MHz
Ultra High Frequency (UHF)	400 MHz – 950 MHz	866 MHz Europe 915 MHz United States
Microwaves (μW)	2.4 GHz – 6.8 GHz	2.45 GHz 3.0 GHz

major drawback is that due to the low frequency of the carrier, these systems can only communicate at low frequency rates. The main advantage of LF RFID systems is that electromagnetic waves operating in the LF range are the least affected by the presence of metals due to the penetration depth of these frequencies. This makes them ideal to be used in applications in which the transponders are surrounded by large metallic masses. Furthermore, LF waves can travel through water with minimal attenuation compared to waves of higher frequencies. This property makes them the frequency range of choice for the identification of animals due to their high water content. Most of these applications are based on implanting these transponders in livestock and pets. Figure 1.5 shows a picture of two different transponders that operate in the LF range in which it is possible to see the multiple loops used by these transponders.

RFID systems operating in the HF range can support higher read rates than LF systems. Although signals in the HF range are more affected by metal and have more attenuation when traveling through water, the transponders used for HF systems can be manufactured at a lower cost than the transponders operating in the LF range. This is due to the fact that the antennas for HF transponders can be made smaller, as shown in the two transponders seen in Figure 1.6. The need for less conductive material to construct the antennas results in a lower cost. Finally, the global uniformity across the world in the frequency of 13.56 MHz makes HF systems able to operate in any country.

While HF RFID systems operate at the single frequency of 13.56 MHz, UHF RFID systems can operate at different frequencies in the UHF band. Moreover, different countries have established different frequency ranges for their UHF RFID operation, making the compatibility between systems more difficult. For example, in North America the assigned band is from 902 MHz to 928 MHz, while in Europe it is from 860 MHz to 868 MHz and in Japan is from 950 MHz to 956 MHz. Other countries and regions have other different allocated frequency ranges. Despite this challenge and due to the developments in microelectronics that allowed the decrease in cost for these

© 2011 by Taylor and Francis Group, LLC



FIGURE 1.5
Low-frequency (LF) RFID transponders require antennas of several hundred feet of coiled wire.



FIGURE 1.6
High-frequency (HF) RFID transponders can use shorter, smaller antennas.

© 2011 by Taylor and Francis Group, LLC

systems, UHF systems have established themselves as a viable alternative to the existing LF and HF systems. One of the main advantages of UHF RFID systems is that their higher carrier frequency allows for a much faster read rate of the transponder information, thus allowing the transmission of higher amounts of data. The communication between transponder and interrogator used in UHF systems is by electrical field instead of the magnetic coupling used by LF and HF systems. The antennas required by UHF systems can also be smaller than the antennas used for LF and HF systems, resulting in higher efficiency. These last two factors contribute to extended read ranges for UHF RFID systems. However, UHF systems also present several drawbacks compared to HF and LF systems. The antennas for transponders operating in the UHF range have very different physical dimensions depending on the parameters that the manufacturer wants to optimize in a given transponder. Figures 1.7 and 1.8 show examples of several UHF transponders in which it is possible to notice these differences.

UHF systems do not work well around metals as these reflect their electromagnetic waves. In addition, water absorbs UHF waves, making them unusable for animal implantation. Furthermore, the extended read range of UHF transponders may become a drawback for those applications that want to keep the read of transponders confined to a certain area.

Although 2.45 GHz is within the UHF range (UHF extends from 300 MHz to 3 GHz), the RFID systems operating in the frequency range extending from 2.45 GHz to 5.8 GHz are commonly called *microwave RFID systems*. In this frequency range, the propagation is limited to line of sight. Microwave signals are also attenuated by water and reflected by metallic objects. The cost of interrogators and transponders used in the microwave range is higher



FIGURE 1.7
Ultra-high-frequency (UHF) RFID transponder.

© 2011 by Taylor and Francis Group, LLC



FIGURE 1.8
Several types of antennas used by ultra-high-frequency (UHF) RFID transponders.

than for any other type of system. On the positive side, it is possible to achieve very high read rates, and with the help from spread spectrum techniques, it is possible to achieve very high reliability rates and noise immunity. The higher end of the range, from 5.5 GHz to 6.8 GHz, is still currently under research and development.

© 2011 by Taylor and Francis Group, LLC

2

Antennas for RFID Transponders

CONTENTS

2.1 Review of Basic Antenna Theory for RFID Transponders 14
  2.1.1 Antennas for RFID Transponders Operating in the LH and HF Regions 14
  2.1.2 Inductance of Coil Antennas Operating in the LF and HF Regions 17
  2.1.3 Antennas for RFID Transponders Operating in the UHF Region 24
2.2 Antenna Tuning for RFID Transponders 29
2.3 Antenna Matching for RFID Transponders 33
2.4 Antennas in Commercial RFID Transponders 37
2.5 The Connection between the Chip and the Antenna in RFID Transponders 43
2.6 Additional Factors That Affect the Performance of Antennas in RFID Transponders 47

The purpose of the antenna in the transponder of an RFID system is multiple: first, it has to collect power from the electromagnetic field generated by the interrogator. In addition, the antenna must transfer the collected power to its load that is the chip in the transponder in order to turn it on. Finally, the antenna must radiate the data signals generated by the chip back to the interrogator. The antenna should be optimized to minimize energy losses during this process by choosing the type and dimensions of the antenna suited for a specific application and matching its impedance to the impedance of the load. Because these requirements may lead to contradictory solutions, the designer of the system must evaluate them carefully when considering the possible solutions.

This chapter explores the design and performance considerations for antennas in transponders. It starts by presenting a basic review of antenna theory with special emphasis on the differences used for systems in the low-frequency (LF) and high-frequency (HF) ranges compared to the antennas used for ultra-high-frequency (UHF) systems. The chapter continues by describing the types of antennas found in commercial transponders. This is followed by considering the requirements for antenna tuning and

© 2011 by Taylor and Francis Group, LLC

antenna matching. The following section describes the different methods for attaching the antenna to the chip on the transponder. The chapter finishes with a review of other antenna factors that affect their performance.

2.1 Review of Basic Antenna Theory for RFID Transponders

2.1.1 Antennas for RFID Transponders Operating in the LH and HF Regions

Electrical current flowing through a conductor generates electromagnetic fields. From the point of view of the concepts described in this chapter, it is possible to distinguish two field regions. The first region is called the *far-field region*. In this region, the generated fields are radiated fields, meaning that the energy propagates through the space with an energy density proportional to the inverse of the distance. The second area is called the *near-field region*. In this area, radiated fields are not prevalent. Instead, attenuating fields, in which the strength of the field decreases with $1/r^3$, are dominant. Furthermore, the power in this region is reactive.

Given these two regions, it seems obvious that antennas for RFID transponders should be designed to operate in the far-field region. However, the boundaries between far-field and near-field regions depend on the relationship between the physical dimensions of the antenna and the wavelength of the propagating signal. In particular, the dimensions of the antenna should be comparable to the wavelength of the signal in order to achieve optimal performance. The wavelength of signals operating in the LF region is around 2.4 km (1.5 miles), while the wavelength for signals operating in the HF region is 24 m (78 feet). Therefore, at these frequencies it would not be practical to build antennas with dimensions similar to the wavelength of their signals. Any antennas that can be built in a practical manner for RFID transponders operating in the LF or HF ranges will be electrically small and therefore highly inefficient. In contrast, RFID signals operating in the UHF region have a wavelength of approximately 30 cm. Although this dimension is still very large for building practical antennas, the following sections will explore how they can be modified to obtain antennas for UHF transponders that will operate in the far-field region.

RFID transponders operating in the LF or HF frequencies cannot use dipole antennas because of the mismatch in dimensions. An alternative solution to this problem is to use a small-loop antenna instead of a dipole. While the near fields radiated by a dipole are mainly electrical fields, the near field from a loop antenna is a magnetic field. A small-loop antenna is a closed loop with a maximum dimension that is less than about a tenth of the wavelength of the signal. It can be shown that the small-loop antenna is the dual equivalent of an ideal dipole, thus making it suitable for antennas incorporated in transponders operating at LF or HF frequencies.

© 2011 by Taylor and Francis Group, LLC

Let's consider a conductor of infinite length carrying a magnitude of current of I amps. The magnetic field (B_Φ) measured at a distance of r meters from the conductor can be found using Ampere's law as

$$B_\phi = \frac{\mu_0 I}{2\,\pi\, r} \ (Weber / m^2) \tag{2.1}$$

where μ_0 is the permeability of free space ($4\,\pi\,10^{-7}$ H/m).

However, a conductor of infinite length is not realistic. Its practical implementation is based on building a loop antenna by bending the original, finite wire, which carries a current of I amps in a circle with a radius of a meters. In practice, the wire is bent in such a way that produces a total of N turns as this allows using a longer wire with a relatively small diameter. In this situation, the value of the magnetic field in the z-coordinate direction (B_z) for a point located at a distance of r meters from the plane of the coil and located along the axis of the coil, as shown in Figure 2.1, can be found as

$$B_z = \frac{\mu_0 I N a^2}{2\,(a^2 + r^2)^{3/2}} \ (Weber / m^2) \tag{2.2}$$

where a is the radius of the loop in meters.

Assuming that the distance at which the field is measured, r, is much larger than the radius of the coil ($r^2 >> a^2$), equation (2.2) can be simplified as follows:



FIGURE 2.1
Magnetic field produced by loop antenna.

© 2011 by Taylor and Francis Group, LLC

$$B_z = \frac{\mu_0 I N a^2}{2 r^3} \quad (Weber / m^2) \tag{2.3}$$

As shown by equation (2.3), the magnetic field created by the small-loop antenna is dependent on $1/r^3$. This causes a strong decrease of field intensity as one moves away from the location of the coil antenna, and will seriously limit the read range of transponders using this type of antenna. However, even with this limitation, the small-coil antenna is more desirable than an electrically small dipole.

The antenna in the RFID transponder has to be both a receiving antenna and a transmitting antenna. It has to collect enough energy from the electromagnetic field generated by the interrogator to be able to power its integrated circuit, and it also has to transmit the data signal generated by the chip back to the interrogator. The *reciprocity theorem* indicates that the receiving and transmitting patterns for a given antenna are identical, and therefore the same antenna can be used for either task.

The voltage induced in a coil consisting of N loops immersed in a time-variant magnetic field can be calculated using Faraday's law as

$$V = -N \frac{d\Psi}{dt} \tag{2.4}$$

with Ψ being the magnetic flux.

The magnetic flux, in turn, can be calculated as

$$\Psi = \int B \bullet dS \tag{2.5}$$

where

B = the magnitude of the time-variant magnetic field

S = the surface area of the coil

$\cdot$ = the inner product operator

Equation (2.5) indicates that the magnetic flux, and consequently the voltage induced in the coil, is dependent on the relative orientation between the coil and the magnetic field. This has some important implications at the time of using interrogators and transponders. Assuming that the magnetic field B was generated by the interrogator using another loop antenna, the maximum received voltage will occur when both coils are placed parallel to each other. Because the voltage generated in the coil that will be used to power the chip in the transponder is proportional to the intensity of the magnetic field (B), this voltage will also be dependent on ($1/r^3$). This is important because

© 2011 by Taylor and Francis Group, LLC

it limits the maximum distance between the interrogator and transponder coils that will produce the threshold voltage necessary to power the chip on the transponder.

Although the previous equations describe the full underlying relationships between the variables involved in this process, it is more desirable from a practical point of view to study how these equations evolve in specific cases. Assuming that the coil is specifically tuned to the frequency of the time-variant magnetic field, the induced voltage in the coil is as follows:

$$V_0 = 2\pi f N S Q B_0 \cos\beta \tag{2.6}$$

where

V_0 = the induced voltage in the coil

f = the frequency of the time-variant magnetic field

B_o = the intensity of the field

N = the number of loops in the coil

Q = the quality factor of the coil antenna

S = the area of the coil

β = the angle between the plane of the coil and the direction of the field

Keeping in mind that the magnetic field generated by the coil in the interrogator is perpendicular to its plane, and that equation (2.6) will be maximized when $\beta = 0$, the induced voltage will be maximized when the interrogator and transponder coils are placed parallel to each other. Once again, the limiting factor in equation (2.6) comes from the intensity of the magnetic field (B_0) decreasing with the cube of the distance between coils ($1/r^3$).

2.1.2 Inductance of Coil Antennas Operating in the LF and HF Regions

Because, as shown in equation (2.6), the induced voltage is proportional to the quality factor (Q factor) of the coil antenna, it is desirable to increase the Q factor as much as possible. This can be achieved by carefully choosing the value of the inductance of the antenna. This section discusses the values of inductance found in typical antennas operating in the LF and HF regions.

Typical RFID systems use inductance values for antennas in transponders of few mH, while antennas for the interrogators have typical values between 10 and 100 times lower. It is necessary to keep in mind that the calculation of inductance values presented here can only be considered as approximated values. These calculations do not take into consideration the finite value of the conductivity of the wire that results in Ohmic losses, and, more importantly, they do not take into account the distributed stray capacitances that appear in the coil. A more detailed and comprehensive analysis and calculations of inductance values in antennas are beyond the scope of this book, but

© 2011 by Taylor and Francis Group, LLC

they can be found in any book on electromagnetism. If the designer requires an accurate value of inductance, the best option is to measure it with a complex impedance meter. This instrument is also able to measure the Q factor of the antenna, providing good characterization of the antenna.

The inductance of the coil shown in Figure 2.2, made with a single layer of wire and with n turns and a core of air, is approximately:

$$L = \frac{d^2\, n^2}{18d + 40l}\ (\mu H) \tag{2.7}$$

where

d = the diameter of the coil in inches

n = the number of turns

l = the length of the coil in inches

Equation (2.7) shows the square relationship between inductance and number of turns; if the number of turns is doubled, the resulting inductance is quadrupled.

Example 2.1:

Calculate the number of turns required to achieve an inductance of 10 μH by winding a piece of wire over an air core with a diameter of 1 inch. The length of the resulting coil must be equal to 1.25 inches.

Solution:

In this situation, l = 1.25 inches, and d = 1.0 inches. Therefore, we can write

$$10 = \frac{(1.0)^2\, n^2}{18 \cdot 1.0 + 40 \cdot 1.25}$$

Solving for n gives n = 26.07 turns. Given the limitations of the approximation for equation (2.7) plus the stray capacitance issues mentioned earlier, a good starting point would be to choose 26 turns. In this case, the value of inductance that we would measure in practice is likely to differ from 10 μH. The designer would have to adjust the number of turns after measuring the actual value of inductance. A recommended procedure is to start by choosing a larger number of turns and therefore a larger number of inductance, and proceed by removing turns until the coil achieved the required inductance.

Although this type of structure to create the antenna for an RFID system is not the most commonly used, it is nevertheless employed in some applications, especially in those that required a hermetically sealed transponder. Figure 2.3 shows an RFID transponder operating in the LF frequency in which it is possible to see the coil antenna and its windings.

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.2
Single-layer, air-core coil.



FIGURE 2.3
Detail of coil antenna in a commercial radiofrequency identification (RFID) transponder for the low-frequency (LF) range.

The practical problem associated with the use of this type of antenna is the three-dimensional space that it requires. Such antennas are not practical for applications that require a flat transponder, such as a credit card, and they are limited to applications that can support the tubular shape, for example in animal implantation. For this reason, the majority of transponders in the LF and HF frequency regions use antennas formed on a single plane, using several layers of conductor to achieve the desired inductance. Figure 2.4 shows this configuration for a multilayer circular coil with *n* turns.

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.4
Multilayer, circular-coil, *N*-turn antenna.

The inductance of this coil is

$$L = \frac{0.31 a^2 n^2}{6a + 9h + 10b} \quad (\mu H) \tag{2.8}$$

where

a = the radius of the coil in cm
n = the number of turns
b = the winding thickness of the coil in cm
h = the winding height in cm

This configuration allows building coils with the required amount of inductance with minimal thickness, therefore minimizing the transponder's footprint. A variation of this antenna that results in an even thinner antenna is the spiral wound coil with a single layer shown in Figure 2.5.

The inductance of a single-layer spiral antenna is

$$L = \frac{0.3937\, a^2 n^2}{8a + 11b} \quad (\mu H) \tag{2.9}$$

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.5
Single-layer, spiral-coil antenna.

where

a = the average radius of the coil in cm $(a = \frac{r_i + r_o}{2})$

b = ro – ri in cm

n = the number of turns in the spiral

This structure results in a thinner antenna, although the number of turns in the antenna is limited to the number of turns that is possible to pack in a single layer. This limits the inductance of the antenna as this value depends on the square of the number of turns. Other forms of planar coil antennas are the multilayer square-loop coil antenna with n turns and the multilayer rectangular-loop coil antenna, also with n turns, shown in Figure 2.6.

The inductance for the planar multilayer square loop coil antenna with n turns, shown in Figure 2.6(a), is

$$L = 0.008\, a\, n^2 \left[2.3 \log\left(\frac{a}{h+b}\right) + 0.2235\, \frac{b+h}{a} + 0.726 \right] (\mu H) \tag{2.10}$$

where

n = the number of turns

a = the distance from the center of the coil to the side in cm

h = the thickness of the winding in cm

b = the width of the winding in cm

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.6
(a) Multilayer, square-coil antenna. (b) Multilayer, rectangular-coil antenna.

© 2011 by Taylor and Francis Group, LLC

The inductance for the planar multilayer rectangular-loop antenna with *n* turns, shown in Figure 2.6(b), is

$$L = \frac{0.0276\, n^2 \left(x+y+2h\right)^2}{1.908\ \left(x+y+2h\right)+9b+10h} \quad (\mu H) \tag{2.11}$$

where

x and y = the dimensions of the coil in cm
h = the thickness of the coil in cm
b = the width of the winding in cm
n = the number of turns

It is necessary to state once again that these equations, used to calculate the inductance of various coils are only approximations and need to be taken with some care. In particular, equation (2.11) is valid only when the dimensions *x* and *y* of the coil are quite different. For example, if the two dimensions of the coil in equation 2.11 (*x* and *y*) were identical, thus resulting in a square coil, the inductance values calculated by equations (2.10) and (2.11) will be different. These equations are provided as a starting point for the designer of antennas for RFID transponders.

Some antennas in transponders are configured as planar rectangular spiral structures, as shown in Figure 2.7. Figure 2.8 shows an example of a commercial transponder using this type of antenna.

There is not a full and closed equation to calculate the inductance of this type of antenna. However, its inductance can be calculated as the sum of the self-inductances for all the straight segments minus the sum of the mutual inductances existing in the arrangement. The mutual inductance is



FIGURE 2.7
Single-layer, rectangular planar spiral antenna.

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.8
Commercial transponder using a planar, rectangular-spiral antenna.

the inductance that results from the magnetic fields produced by adjacent conductors. This mutual inductance will be positive when the direction of the current in the conductors is the same, and it will be negative when it is opposite.

2.1.3 Antennas for RFID Transponders Operating in the UHF Region

When the transponder is operating in the UHF region, the wavelength of the electromagnetic radiation is now comparable to the dimensions of the antenna. Because the antenna is no longer electrically small, a dipole can now be used. A *short dipole* is defined as a dipole whose length does not exceed one-fiftieth of the wavelength of the current signal. A short dipole, as depicted in Figure 2.9, produces an electric field that in near-field conditions has both radial and zenithal components, as given by equation (2.12):

$$\begin{aligned} E_r &= \frac{2I_0 l}{4\pi} k^2 \eta_0 \, e^{-jkr} \left(\frac{1}{(kr)^2} - \frac{j}{(kr)^3} \right) \cos\theta \\ E_\theta &= \frac{I_0 l}{4\pi} k^2 \eta_0 \, e^{-jkr} \left(\frac{j}{kr} - \frac{1}{(kr)^2} - \frac{j}{(kr)^3} \right) \sin\theta \end{aligned} \tag{2.12}$$

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.9
Electric field produced by a short dipole.

where

k = the wavenumber $\left(k = \frac{2\pi}{\lambda}\right)$

η_0 = the intrinsic impedance of free space $\left(\eta_0 = \sqrt{\frac{\mu_0}{\varepsilon_0}} \approx 120\pi\right)$

r = the distance for the center of the dipole at which the field is measured

θ = the zenith angle at which the field is measured

Assuming that the far-field approximation is valid ($r \gg \lambda$), the radial component of the electrical field can be neglected, and therefore equation (2.12) becomes

$$E_\theta = \frac{jI_0 l}{4\pi} k\eta_0 \frac{e^{-jkr}}{r} \sin\theta \tag{2.13}$$

The short dipole, however, does not radiate effectively because it has a very small radiation resistance, normally below 1 Ω, making it unsuitable for a good impedance match. Therefore, other dipole alternatives are preferred when possible, such as the half-wave dipole. The *half-wave dipole,* depicted in Figure 2.10, receives its name because its length equals half of the wavelength of the current signal traveling through the antenna.

A half-wave dipole also produces an electric field only in the zenith component that can be described by equation (2.14):

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.10
Electric field produced by a half-wave dipole.

$$E_\theta = \frac{j\,60 I_0}{r}\left(\frac{\cos\left(\frac{\pi}{2}\cos\theta\right)}{\sin\theta}\right)e^{-jkr} \tag{2.14}$$

One of the main advantages of the half-wave dipole is that its radiation resistance, around 73 Ω, is much larger than the radiation resistance of the short dipole. This makes the half-wave dipole better suited to match the impedance presented by its load, the integrated circuit in the transponder.

The wavelength for the typical UHF RFID frequency of 915 MHz is approximately 33 cm. Therefore, the length of a half-wave dipole is 16.5 cm. This value is valid only for free space; for an antenna mounted on an inlay, the actual value of its half wavelength decreases as the dielectric constant of the substrate increases. Although this distance is achievable, it presents some drawbacks. First of all, 16.5 cm may still be too large for some applications that require or would benefit from smaller transponders. More importantly, the power transfer characteristics for this antenna are very small and therefore require substantial matching approaches. Antenna matching is described in further detail in Section 2.2.

The space required by the antenna can be shortened while keeping the length of the conductors to the required 16.5 cm, for example by bending or even folding the wires that make up the dipole, as shown in Figure 2.11. This process can be repeated several times, bending the wires of the antenna in different directions as shown in Figure 2.12, which results in the structure known as the *meandered dipole*.

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.11
Strategies for reducing the size of ultra-high-frequency (UHF) antennas. (a) Original half-wave dipole. (b) Bent dipole. (c) Folded dipole.



FIGURE 2.12
Examples of meandered dipole antennas. (a) Meandered dipole in a single direction. (b) Meandered dipole in two directions.

© 2011 by Taylor and Francis Group, LLC



(b)

FIGURE 2.12 (Continued)
Examples of meandered dipole antennas. (a) Meandered dipole in a single direction. (b) Meandered dipole in two directions.



FIGURE 2.13
Detail of the inner loop used in some UHF antennas.

However, bending the dipole degrades the electrical characteristics of the antenna: the current lines flowing in opposite directions through adjacent paths have a canceling effect that in turn increases the radiation resistance of the antenna. Because this effect depends on the distance between the paths, the canceling effect becomes stronger when the antenna has multiple bends closely packed. In practice, the total length of a bent or meandered dipole is longer than the straight half-wave wavelength, although the total size of the antenna will be smaller.

Some antennas operating at the UHF range also incorporate a low DC resistance path closer to the center of the antenna known as the *inner loop*. This inner loop, shown in Figure 2.13, presents a series of advantages that makes its use common in this type of antenna.

© 2011 by Taylor and Francis Group, LLC

First, the inner loop presents a low DC resistance that helps reduce the potential of damage to the integrated circuit due to high-voltage electrostatic discharges that may occur in the antenna or its vicinity. Second, the inductance of the inner loop can be used in conjunction with the input capacitance of the integrated circuit to form a resonance circuit that will couple with the magnetic near field, producing enough voltage to power the integrated circuit. Near-field communications for UHF RFID systems, although not very common yet, are growing rapidly. Third, the inner loop can be used like a transformer to help match the impedance of the integrated circuit to the antenna. Finally, the impedance of the antenna can be lowered or increased by changing the width of the trace in the inner loop.

2.2 Antenna Tuning for RFID Transponders

Antenna tuning for RFID transponders operating at LF or HF frequencies attempts to make the antenna resonant at the frequency of transmission, thus maximizing the current or the voltage in the system. Because the antenna has a marked inductive component, resonance is achieved by placing a capacitor of the adequate value in series or in parallel with the antenna.

When the capacitor is placed in series with the antenna, the resulting series resonant circuit has an impedance minimum at the resonance frequency and therefore maximizes the current being delivered to its load. This type of configuration is typical for interrogators and will be studied in Chapter 4. When the capacitor is placed in parallel with the antenna, the result is a parallel circuit that exhibits an impedance maximum at the resonant frequency and therefore maximizes the voltage across its terminals. This is the typical configuration for transponders. The tuning capacitor in RFID transponders can be created over the same substrate as shown in Figure 2.14.

The resonant circuit can therefore be modeled as a parallel circuit, similar to the one shown in Figure 2.15, in which L represents the inductance of the antenna, C represents the capacitance of the capacitor that must be added, R represents the resistance of the load that is the integrated circuit that must be powered, and the value r represents the resistance of the coil. Because normally $r \ll R$, the value r will be ignored in the calculations needed to find the value of required capacitance. However, the resistance r of the inductor contributes to degrading the overall performance of the antenna. These effects will be studied in the last section of this chapter.

The complex impedance presented by the circuit shown in Figure 2.15, neglecting the Ohmic losses r, is

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.14
Tuning capacitor in the antenna of a high-frequency (HF) transponder.



FIGURE 2.15
Parallel resonant model used to analyze antenna resonance. L: antenna inductance. C: external tuning capacitor. R: load (chip to energize). r: Ohmic losses in the antenna.

$$Z(j\omega) = \frac{\frac{j\omega}{C}}{\left(\frac{1}{LC} - \omega^2\right) + j\frac{\omega}{RC}} \tag{2.15}$$

where $\omega = 2\pi f$.

The resonant frequency for the parallel circuit is the frequency that creates the maximum for $Z(j\omega)$. This frequency is

$$\begin{gathered} \omega_o = \sqrt{\frac{1}{LC}} \quad or \\ f_o = \frac{1}{2\pi\sqrt{LC}} \end{gathered} \tag{2.16}$$

© 2011 by Taylor and Francis Group, LLC

From equation (2.15), it can be seen that at the resonant frequency, the impedance of the parallel circuit is real and equal to the value of the resistance of the load. This is the maximum value for the impedance.

Example 2.2:

Consider the value of inductance for the antenna in Example 2.1 (10 μH). Calculate the value of parallel capacitance required to make the antenna resonant at the typical RFID frequencies of (a) 125 kHz for LF systems and (b) 13.56 MHz for HF systems.

Solution:

Solving for C in equation (2.16) yields

$$C = \frac{1}{L(2\pi f)^2}$$

Therefore, the values of capacitance required for resonance are as follows:
$C_{125\ \text{kHz}} = 162\ \text{nF}$
and
$C_{13.56\ \text{MHz}} = 13.7\ \text{pF}$

The same calculations for resonant frequency can be applied to the devices that communicate data by tuning and detuning the antenna. This can be accomplished by using, for example, two capacitors or two inductors in the parallel RCL circuit. In order to detune the antenna, the controlling device can, for example, shorten one of the capacitors or inductors, resulting in a new resonant frequency. This, in turn, results in a minimal transfer of energy back to the interrogator.

The devices MCRF355 and MCRF360 from Microchip Technologies operate following this principle. Figure 2.16 shows one of the configurations used. Here, the antenna will be tuned when both inductors are active and will be detuned when the device shortens the inductor L_2.

Using equation (2.13), the resonant frequency when the antenna is tuned is $f_{\text{tuned}} = 1/2\pi\sqrt{L_T\, C}$, with L_T being the total inductance between point A and ground. When the device detunes the antenna by shortening inductor L_2, the new resonant frequency becomes $f_{\text{detuned}} = 1/2\pi\sqrt{L_1\, C}$. Because $L_T > L_1$ ($L_T = L_1 + L_2 + 2k\sqrt{L_1 L_2}$, with k being the coupling coefficient between the coils), $f_{\text{tuned}} < f_{\text{detuned}}$.

The difference between the tuned and detuned frequencies must be chosen to maximize the Modulation Index and the read range. If it is necessary to choose the tuned and detuned frequencies such as $f_{\text{tuned}} < f_{\text{detuned}}$, this can be achieved by using the configuration shown in Figure 2.17.

The operation is similar as shown before. Here, $f_{\text{tuned}} = 1/2\pi\sqrt{L\, C_T}$, with $C_T = C_1C_2/\ C_1 + C_2$. The device detunes the circuit by shortening the capacitor

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.16
Tuned and detuned circuit using two inductors and one capacitor. This configuration results in $f_{\text{tuned}} < f_{\text{detuned}}$.



FIGURE 2.17
Tuned and detuned circuit using two capacitors and one inductor. This configuration results in $f_{\text{tuned}} > f_{\text{detuned}}$.

C_2, resulting in the following detuned frequency: $f_{\text{detuned}} = 1/2\pi\sqrt{L\,C_1}$. Because $C_T < C_1$, this results in $f_{\text{tuned}} < f_{\text{detuned}}$.

Equation (2.15) can also be used to calculate the bandwidth of the system defined as its –3 dB cutoff. This is

$$B = \frac{1}{2\pi\,RC} \quad (Hz) \tag{2.17}$$

An important parameter in a resonant circuit is its quality factor (Q), which compares the energy stored in the circuit with the energy that it dissipates:

© 2011 by Taylor and Francis Group, LLC

$$Q = \frac{f_o}{B} \tag{2.18}$$

Equation (2.17) can be rewritten taking into account the values of components in the resonant circuit by combining equations (2.16) and (2.17):

$$Q = R\sqrt{\frac{C}{L}} \tag{2.19}$$

Equation (2.6), found earlier, was used to calculate the voltage induced in the coil. Substituting equation (2.19) into equation (2.6) yields

$$V_0 = 2\pi f N S Q B_0 \cos\beta \;=\; 2\pi f N S R\sqrt{\frac{C}{L}}\, B_0 \cos\beta \tag{2.20}$$

This equation indicates that the voltage induced in the antenna transponder is inversely proportional to the square root of its inductance, and proportional to both the number of turns in the coil and its surface.

2.3 Antenna Matching for RFID Transponders

The purpose of matching an antenna to its load is to ensure that the antenna transfers the maximum amount of power to its load. In an RFID transponder, the load of the antenna is the integrated circuit that will be powered by the energy supplied by the antenna. Antenna matching is generally based on altering the complex impedance presented by the antenna at its operating frequency, by modifying its physical dimensions, inserting a reactive component, or a combination of both.

Consider a simple circuit, as shown in Figure 2.18. The power transferred by the voltage source V_s to the load resistance R_L is

$$P_L = \frac{R_L}{(R_L + R_s)^2}\, V_s^2 \tag{2.21}$$

The goal of power matching is to find a relationship between R_s and R_L that will maximize the power transferred to the load. In mathematical terms, this

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.18
Simplified model for power transfer calculations.

is equivalent to finding the relationship between R_L and the rest of the circuit elements that will make the first derivative of equation (2.21) zero. That is,

$$\frac{dP_L}{dR_L} = \frac{(R_L + R_s)^2 - 2R_L\ (R_L + R_s)}{(R_L + R_s)^4} V_s^2 = 0 \quad \Rightarrow \; R_L = R_s \tag{2.22}$$

In a transponder, the voltage source models the voltage induced in the antenna, and the load models the integrated circuit that must be powered. These are not purely resistive elements such as those depicted in Figure 2.18, but they have resistance and reactance. Therefore, a more accurate model for this situation is shown in Figure 2.19.

Equation (2.23) shows the power transferred to the load that is the real part of the impedance of the integrated circuit:

$$P_L = \frac{R_{ic}}{2\left[\left(R_{ant} + R_{ic}\right)^2 + \left(X_{ant} + X_{ic}\right)^2\right]} V_{ant}^2 \tag{2.23}$$

There are now two conditions that must be met in order to transfer the maximum amount of power between the source (voltage generated by the antenna) and the load (integrated circuit to be powered). These are

$$\begin{cases} R_{ic} = R_{ant} \\ X_{ic} = -X_{ant} \end{cases} \tag{2.24}$$

Equation (2.24) can now be understood by saying that the amount of power transferred from the antenna to the integrated circuit will be maximum when their impedances are conjugate. This is an advantageous condition for RFID systems as the impedance of the antenna has an inductive behavior and the

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.19
Model for power transfer calculations in an RFID transponder.

input impedance of the integrated circuit presents a capacitive behavior. The model shown in Figure 2.19 can be further refined as the model shown in Figure 2.20.

It is necessary to point out that the series impedance model used in Figure 2.20 is not the most common way to represent the input impedance of an integrated circuit or any other electronic device. Generally, input impedance is expressed using a parallel model with the input resistance and the input capacitance. However, to preserve the parallelism used in Figures 2.18 and 2.19, it is more convenient to express it using the series model. Given the values of parallel resistance and capacitance, it is possible to find their equivalent series values using equation (2.25):

$$\begin{cases} R_s = \dfrac{R_p}{1+\left(\omega R_p C_p\right)^2} \\[2ex] C_s = \dfrac{1+\left(\omega R_p C_p\right)^2}{\omega^2 R_p^2 C_p} \end{cases} \tag{2.25}$$

Example 2.3:

The specifications for the chip MCRF200 from Microchip used in RFID transponders indicate a parallel capacitance of 2 pF. Assuming a parallel resistance of 3 kΩ, find the equivalent series model at the frequency of 915 MHz.

Solution:

Equation (2.25) gives the following values of the equivalent series model:

$R_s = 2.6\ \Omega$ and $C_s = 1.96$ pF. In general, the values of series and parallel capacitance will be approximately the same. However, the values of the series and parallel resistances are very different for each model.

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.20
Series model for the transponder antenna and chip to be energized.

It is also interesting to calculate the gain or attenuation between the voltage delivered to the integrated circuit and the voltage generated by the antenna in the optimal case of maximum power transfer. Using the model shown in Figure 2.16, the voltage across the integrated circuit produced by the antenna can be calculated as follows:

$$V_{ic} \approx j\frac{1}{2\pi\omega R_{ic} C_{ic}} V_{ant} \tag{2.26}$$

Example 2.4:

Using the values given in Example 2.3, calculate the voltage gain or attenuation at the input of the integrated circuit at the frequency of 915 MHz.

Solution:

Using equation (2.26), V_{ic} / V_{ant} is equal to 34. This means that the voltage at the input of the integrated circuit in the transponder at the resonance frequency will be 34 times larger than the voltage generated by the antenna. In practice, this number will be lower because equation (2.26) has not considered factors such as the effect of the Q factor and other losses in the system. Typical voltage gains in practice are around 10 to 15. In any case, this represents an important benefit for the designer of the RFID system.

It is necessary to consider that, in practice, there will be some mismatch between the impedance of the integrated circuit and the impedance of the antenna as these will not be perfect conjugates. This mismatch will produce losses in the power being delivered to the integrated circuit, resulting in decreasing the sensitivity and read range for the transponder. This factor becomes more important for UHF antennas designed for global operations that have a frequency bandwidth of 860 MHz to 960 MHz rather than those

© 2011 by Taylor and Francis Group, LLC

designed for operation at a single frequency. In this case, the usual design approach is to place the matched frequency at the geometrical mean of the two frequency ends, resulting in 908 MHz. This will result, however, in mismatch losses at frequencies close to 860 MHz and frequencies close to 960 MHz.

2.4 Antennas in Commercial RFID Transponders

Coil antennas are used in the different type of encapsulated glass transponders, similar to Figure 2.21, operating in the LF region manufactured by Texas Instruments. Glass transponders are hermetically sealed, making them waterproof and therefore suitable to be immersed in water and other fluids.

These transponders are marketed toward access control, vehicle identification, container tracking, asset management, animal identification, and waste management applications, as described by the literature provided by their manufacturer. Texas Instruments has different versions of these transponders depending on the size of the memory in the chip and its ability to be rewritten by the user. The transponders are also available in different sizes, in particular lengths of 12 mm, 23 mm, and 32 mm. Figure 2.22 shows the different sizes of these glass transponders that operate at the central frequency of 134.2 kHz, corresponding to the LF range. Other operational characteristics of these glass transponders are listed in Table 2.1.



FIGURE 2.21
Glass transponder used for RFID applications in the LF range.

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.22
Three commercial glass transponders of different sizes used for application in the LF range.

TABLE 2.1
Operational Characteristics of Glass Transponders

Main Operational Parameters Glass Transponders Texas Instruments – LF Region	
Modulation	FSK: 134.2 kHz and 123.2 kHz
Transmission Principle	Half Duplex
Read Range	Less than 100 cm
Maximum Operating Temperature Range	– 25°C to + 85°C
Read Time	Less than 70 ms
Case material	Glass
Protection	Hermetic seal
Weight	0.8 grams
Memory on board	4 different options depending on specific part number

Other transponders operating in the LF region use planar coil antennas similar to those shown in Figure 2.23. The dimensions of the larger transponder are 25 mm for the outer ring and 20 mm for the inner ring, while the dimensions for the smaller antenna are 14 mm for the outer ring and 9 mm for the inner ring.

These antennas consist of a length of conductor wire coiled multiple times in order to create the desired inductance. The manufacturer specifies their use for the same general type of applications as the glass transponders, with the advantage of being much thinner.

Antennas for transponders operating in the HF frequency (13.56 MHz) are normally planar antennas, having a structure similar to the planar antennas used in the LF region. However, because HF antennas require a lower

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.23
Commercial planar coil antennas.

inductance, the number of turns for these antennas is much lower, normally less than 10 turns. Planar antennas for RFID transponders operating in the HF region are also manufactured in different sizes and thicknesses depending on the intended application. Figure 2.8 showed a picture of an HF transponder manufactured by Texas Instruments under the name of Tag-it™. This type of transponder is marketed toward product authentication, library applications, supply chain management, asset management, and ticketing or stored value applications. The antennas are built over a polyethylene-terephthalate (PET) substrate giving a maximum thickness of 0.085 mm for the antenna area and 0.355 mm for the chip area. Figure 2.24 shows three antennas from this same family. The larger rectangular antenna has maximum dimensions of 75 mm × 45 mm and consists of seven turns; the small rectangular antenna has a maximum dimension of 39 mm × 22 mm and has six turns; the square antenna has maximum dimensions of 45 mm × 45 mm and contains nine turns.

The number and type of different antennas for transponders operating in the UHF region are higher as each commercial product has been optimized with an application in mind in terms of the different antenna parameters or the type of substrate better suited for a specific purpose. Figures 2.25, 2.26, and 2.27 show three examples of the diverse UHF transponders manufactured by Alien Technology.

Figure 2.25 shows the Alien ALN-9640 Squiggle® Inlay from Alien Technology. This is a general-purpose transponder used for packages that

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.24
Diverse planar rectangular antennas used in commercial HF transponders.



FIGURE 2.25
Commercial UHF transponder based on a meandered dipole and using capacitive tip loading.

include metal or water. The largest length dimension of this antenna is 98 mm, and the largest width of the overall antenna is 8 mm. This antenna exhibits a radiation pattern similar to a half-wave dipole. This antenna is based on a half-wave dipole that has been made shorter by bending the wires and adding shunt and series inductors to create the adequate resonant frequency for the integrated circuit that will be powered by the antenna. The large conductive areas located at each end of the antenna serve as capacitors

© 2011 by Taylor and Francis Group, LLC

used to increase the antenna capacitance. This technique is known as *capacitive tip loading*. Since the magnitude of capacitive reactance decreases as the capacitance increases, a tip-loaded dipole exhibits a more inductive behavior than a dipole of the same length without the additional capacitance at its ends.

Figure 2.26 shows the Alien ALN-9534 2x2 Inlay from Alien Technology. This antenna exhibits a more omnidirectional radiation pattern and is marketed toward item-level tagging applications such as apparel or baggage. The maximum dimensions of this antenna are 46 mm × 40 mm. This type of antenna, in which the conductors are thicker than the previously studied wire antennas, presents the advantage of having higher capacitance and lower inductance than the wire antennas, therefore making it easier to match to the characteristics of its integrated circuits. Furthermore, these antennas made with thicker conductors exhibit a wider bandwidth than the wire antennas.

Figure 2.27 shows the Alien ALN-9554 M Inlay from Alien Technology. This antenna exhibits a better omnidirectional radiation pattern and is marketed toward tagging plastic totes, pallets, and other reusable assets. The maximum dimensions of this antenna are 98 mm × 38 mm. This type of antenna presents the higher bandwidth for the same reasons described earlier. When using conductive inks to create the antenna, the additional ink required to create them results in a cost increase for this type of antenna.

Figure 2.28 shows an example of a meandered dipole antenna with an inner loop for use in the UHF range manufactured by RSIID technologies.



FIGURE 2.26
Commercial UHF transponder using a more omnidirectional antenna.

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.27
Commercial UHF transponder having a higher bandwidth response.



FIGURE 2.28
Meandered dipole antenna for UHF applications.

The maximum dimensions of this antenna are 67 mm × 13.5 mm, thus making it suitable for applications with limited available space. Figure 2.28 is just one example of the different configurations available for meandered dipoles.

Figure 2.29 shows a dual dipole transponder. These transponders have two dipole antennas to make them more insensitive to the orientation of the transponder in reference to the interrogator. The potential drawback of this approach is the additional space required by the transponder that may not be suitable for all products. Furthermore, the front end of the integrated circuit that will be powered by the antenna increases in complexity as it needs to respond to two different antennas. However, for longer range applications in which the position of the object can change, this type of antenna presents a clear advantage.

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.29
Dual dipole antenna for UHF transponders.

While the majority of transponders operating in the UHF range are powered by far-field electromagnetic radiation, in some cases the relatively large area that they require may be larger than the available surface in the transponder. The solution in this case is to use UHF antennas that operate in the near-field region, accepting the drawbacks associated with this mode of operation. These antennas operate based on the same inductive coupling principles used by LF and HF antennas. However, it is possible to add shunt and series inductors or capacitive tip loads to create what are known as *hybrid antennas*. These hybrid antennas, examples of which are shown in Figures 2.30 and 2.31, are able to operate in the near and far fields even though the performance in the far-field region is degraded compared to the performance of a typical dipole antenna.

2.5 The Connection between the Chip and the Antenna in RFID Transponders

A critical step in the manufacture of RFID transponders is the connection between the antenna and the integrated circuit in the transponder. There are main methods of doing this connection: chip-on-board and direct die attachment.

Chip-on-board (COB) is an assembly technology for semiconductors in which the electronic chip is directly mounted on and connected to its final board instead of undergoing the traditional packaging process for integrated circuits. This process reduces space requirements and cost, and also increases the performance of the system due to the decrease in connection lengths and increase in reliability. This approach is normally used for wire-wound antennas. During the COB process, the capacitor used to create resonance is also packaged in the device. The device is then covered in epoxy in such a

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.30
Hybrid UHF antenna able to communicate in near field and far field.



FIGURE 2.31
Hybrid UHF antenna with tip loading.

way that only the two cables to connect to the antenna emerge from the package, as shown in Figure 2.32. The majority of COB packages are used in cards that need to meet the requirements for standard thickness of these cards at 0.76 mm. With this requirement, the typical thickness of COB packages is about 0.41 mm. Although the COB package is designed to protect the internal silicon device during the card lamination process, it is necessary to be careful to prevent mechanical cracks on the device as a result of the mechanical pressures and hot temperatures.

Direct die attachment can be achieved using two techniques: wire bonding or flip-chip. Flip-chip is a technology for interconnecting semiconductor

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.32
Connection of the antenna wires to the chip in the transponder.

devices by creating conductive bumps in the pads of the chip. In order to connect the chip, this has to be flipped so the bond pads are in contact with the matching pads in the circuit. In the wire-bonding technology, the chip is mounted upright and wires are used to connect the chip to the circuit. In the case of RFID transponders, the bumps or wires are connected to the antenna, thus being an ideal method to use for printed, etched, or stamped antennas. In this case, the resonance capacitor can also be etched on the substrate of the transponder, and therefore this technology does not require binding it with the chip as COB does. Figure 2.33 shows an example of this type of connection.

The choice between printing, etching, or stamping the antenna is a trade-off between cost and performance. The Q factor of the antenna, which as discussed earlier has a strong effect on the read range for the transponder, is inversely proportional to the resistance of the antenna. With this in mind, it is desirable to use an etched antenna instead of a printed antenna made of conductive material. The etching process is also less expensive than the printing process. For large antennas, however, etching and stamping waste too much unwanted material. In this case, a printed antenna becomes a more desirable solution. Figure 2.34 shows the general structure of the chip-to-antenna connection, independently of the specific technique being used. The antenna is connected between one of the terminals in the die and its ground connection (GND).

This connection creates a problem due to the crossing of the connection to the antenna with the ground ring around the die, creating a parasitic

© 2011 by Taylor and Francis Group, LLC



FIGURE 2.33
Direct connection between the chip and the antenna in the transponder.


Integrated circuit die
Ground ring
Test pads
ANT
Antenna

FIGURE 2.34
Strategy for reducing the stray capacitance when connecting the chip to the antenna in an RFID transponder.

© 2011 by Taylor and Francis Group, LLC

capacitance. Depending on the technology being used to make this connection, the parasitic capacitance can have a value of up to 20 fF, influencing the resonant frequency for the antenna. To limit this effect, the ground ring around the die is narrowed in the vicinity of the pad for the antenna connection, thus reducing the parasitic capacitance.

2.6 Additional Factors That Affect the Performance of Antennas in RFID Transponders

As discussed in the preceding sections, the quality factor of an antenna is influenced by its Ohmic losses. For the coil antennas used for transponders operating in the LF region, these Ohmic losses come from the wire used to build the coil. The resistance in DC of a conductor of length l, with a uniform cross-section S, is

$$R_{DC} = \frac{l}{\sigma S} \tag{2.27}$$

where σ is the conductivity of the material.

Because of the need to manufacture the antenna as small as possible, designers opt for choosing the narrowest possible diameter, resulting in an increase in its resistance as shown by equation (2.27). More important, however, for the design of antennas is their losses in AC. The density of AC current through a wire is not constant through its surface, but the current tends to flow through the outer section of the wire, thus decreasing its effective area. This is known as the *skin effect*. Similarly, the *skin depth* for a conductor is defined as the value of its depth at which the current density falls to 37% of the current density along the surface. As shown in equation (2.28), for a given material, its skin depth is dependent on the frequency of the AC current:

$$\delta = \frac{1}{\sqrt{\pi \mu \sigma f}} \tag{2.28}$$

where

δ = the skin depth

μ = the permeability of the material

σ = the conductivity of the material

f = the frequency of the AC current through the material

© 2011 by Taylor and Francis Group, LLC

Example 2.5:

Calculate the skin depth for copper wire at (a) 125 kHz and (b) at 13.56 MHz.

Solution:

Copper has a relative permeability of 1, so its total permeability is $\mu = 4\pi\ 10^{-7}$ H/m. Its conductivity is equal to $\sigma = 5.8\ 10^{7}$ mho/m. Therefore, equation (2.28) can be rewritten for copper as

$$\delta = \frac{0.066}{\sqrt{f}} \quad (m)$$

A. The skin depth of copper at 125 kHz is equal to 0.186 mm. This means that the current density of a point located 0.186 mm away from the surface of the conductor is only 37% of the current density on the surface.
B. The skin depth of copper at 13.56 MHz is equal to 0.018 mm. At this frequency, the skin depth is about one-tenth of the skin depth at 125 kHz. Therefore, at 135 MHz the majority of the current is flowing through the surface of the conductor.

The total resistance of a wire to AC current (R_{ac}) is a combination of its DC resistance (R_{DC}) and its skin depth (δ):

$$R_{ac} = R_{DC}\frac{a}{2\delta} \tag{2.29}$$

where a is the radius of the wire.

For etched coil antennas, commonly found in planar transponders, the AC resistance is given by equation (2.30):

$$R_{ac} = \frac{1}{(w+t)}\sqrt{\frac{\pi\mu f}{\sigma}} \tag{2.30}$$

where

w = the width

t = the thickness of the conductor on the substrate

Etching is a wasteful process as metal is removed from the substrate in order to create the antenna. Although some of the materials may be recycled, etching also requires large amounts of chemicals and energy to use in the process. To respond to this concern, newer processes based on conductive inks or copper deposits have been developed, especially for antennas operating in the UHF frequency range. Because of the higher conductivity of copper compared to silver-based conductive inks, antennas made with deposited copper can be substantially thinner than those made with conductive inks. In general, both materials can be effectively used to create antennas.

© 2011 by Taylor and Francis Group, LLC

3

Transponders

CONTENTS

3.1 The Analog Front End 50
  3.1.1 Radiofrequency Stage 50
  3.1.2 Power Management 54
3.2 Signals in the Transponder 57
  3.2.1 Signal Encoding 57
  3.2.2 Modulation and Demodulation 59
3.3 The Logic System 66
  3.3.1 Data Memory 66
  3.3.2 Cyclic Redundancy Check for Error Detection 75
3.4 Transponder Programming 77
3.5 Summary of Electrical Specifications for RFID Transponders 79
3.6 Mechanical Considerations and Transponder Assembly 81

The two main components of a transponder are its internal circuits and its antenna. The antenna, studied in Chapter 2, is used to collect energy from the electromagnetic fields in which the transponder is embedded as well as to transmit the information back to the interrogator. The integrated circuit, also known as the *chip* or *device*, is the key component in the transponder, and for this reason this chapter uses the names *transponder, chip,* and *device* interchangeably. The integrated circuits have the ability to store information to be transmitted to the interrogator, execute a series of commands, and, in some cases, store new information sent by a remote station.

This chapter describes the fundamental blocks that make up the transponder. Because there are a large number of transponders in the market, each one with its own specific differences, this chapter focuses on the functional blocks common to them using commercial transponders to illustrate these concepts. Therefore, the devices used in the examples should not be seen as an exhaustive list of transponders but just as examples used to illustrate specific concepts and ideas. This chapter starts by describing the analog front end commonly encountered in these devices. The analog front end contains the radiofrequency section that is necessary to match the electrical properties of the device to the electrical properties of the antenna as well as the circuits used for harvesting and managing the power necessary to turn on the device. This section is followed by the description of the main encoding and modulation methods commonly used by transponders. This is followed

© 2011 by Taylor and Francis Group, LLC


Antenna
Modulator/ demodulator
Encoder
User memory
RF section
Power
To rest of circuits
Read/write
Control
System memory
Analog front-end
Contact programming
Error checking
Anti-collision logic
Functional testing
Functional verification

FIGURE 3.1
Block diagram of a generic RFID transponder highlighting its main functional components.

by the description of the different memory structures to store data and configuration parameters as well as the codes used to ensure the integrity of the digital data. The next section briefly describes the methods for programming the transponder by either a contact programmer or a contactless programmer. The last two sections in this chapter present a summary of the electrical and mechanical specifications found in commercial transponders as well as a description of their most common assembly methods.

Figure 3.1 depicts the block diagram of a basic and generic RFID transponder showing its main functional blocks. It is important to note that not all the blocks shown in the figure will be always present in any transponder depending on its use, intended application, and cost.

3.1 The Analog Front End

3.1.1 Radiofrequency Stage

When the transponder is immersed in an electromagnetic field of the appropriate frequency, a radiofrequency voltage appears across the antenna terminals. The task of the front-end stage is to rectify that radiofrequency voltage and convert it into a continuous voltage (DC) with a value high enough to power the rest of the circuits inside the device. Different transponders have

© 2011 by Taylor and Francis Group, LLC

different requirements regarding the minimum voltage required to become operational depending on their internal structure and fabrication technology.

The first step in the energy conversion process between the electromagnetic field and the DC voltage is the resonant circuit tuned to the frequency of the field. The different possible configurations for the external resonant circuit described in Section 2.2 are now studied, taking into account the structures used in commercial transponders. Figure 3.2 shows the possible alternatives for the external resonant circuit using two commercial devices: the MCRF355 and the MCRF450, both from Microchip Technology and both operating at 13.56 MHz.

Some devices incorporate one or two capacitors inside their integrated circuit, eliminating the need for using an external capacitor and therefore reducing the size required for the overall transponder inlay. Figure 3.3 shows the resonant circuit using commercial devices that incorporate one or two capacitors in their internal circuitry.

The devices MCRF360, MCRF451, and MCRF455 from Microchip Technology have a single internal capacitor with values of 100 pF, 95 pF, and 50 pF, respectively. The device MCRF422, also from Microchip Technology, has two internal capacitors of 50.6 pF and 65.4 pF. All these devices operate at 13.56 MHz.


C
L1
L2
MCRF355/450
$f_{\text{tuned}} = \frac{1}{2\pi\sqrt{L_T C}}$
$f_{\text{detuned}} = \frac{1}{2\pi\sqrt{L_1 C}}$
$L_T = L_1 + L_2 + L_M$ *with* $L_M = k\sqrt{L_1 L_2}$ $(0 \le k \le 1)$ *and* $L_1 > L_2$
C1
C2
L
MCRF355/450
$f_{\text{tuned}} = \frac{1}{2\pi\sqrt{L\,C_T}}$
$f_{\text{detuned}} = \frac{1}{2\pi\sqrt{L\,C_1}}$
$C_T = \frac{C_1 C_2}{C_1 + C_2}$ *and* $C_1 > C_2$

FIGURE 3.2
Alternatives for the external resonant circuit found in commercial transponders. These transponders require a capacitor in the inlay to create the resonant circuit. The inductor in the circuits models the antenna.

© 2011 by Taylor and Francis Group, LLC



$$f_{\text{tuned}} = \frac{1}{2\pi\sqrt{L_T\,C_{\text{int}}}} \qquad f_{\text{detuned}} = \frac{1}{2\pi\sqrt{L_1\,C_{\text{int}}}}$$

Internal capacitance values:

MCRF360:	100 pF
MCRF451:	95 pF
MCRF455:	50 pF

$$f_{\text{tuned}} = \frac{1}{2\pi\sqrt{L\,C_T}} \qquad f_{\text{detuned}} = \frac{1}{2\pi\sqrt{L\,C_{\text{in1}}}}$$

$C_{\text{int1}} = 50.6$ pF
$C_{\text{int2}} = 65.4$ pF
$C_{\text{Tequiv}} = 30$ pF

FIGURE 3.3
Alternatives for the external resonant circuit for devices that incorporate the resonance capacitor in the die of the integrated circuit. (a) Structure with a single internal capacitor. (b) Structure with two internal capacitors.

The path between one of the antenna connection nodes and ground, shown in Figures 3.2 and 3.3, is shortened according to a control signal. The path is shortened using a transistor, called a *modulation transistor,* that exhibits a low ON resistance, normally below 5 Ω and a very high OFF resistance of several MΩ. In this situation, the transponder exhibits two different resonant frequencies.

The resulting resonance frequency when the modulation transistor is OFF is chosen to be equal to the frequency of the electromagnetic field emitted by the interrogator. As shown in Figure 3.4, because of the resonance condition, the energy of the field is transmitted through the front end to the device, resulting in the radiofrequency voltage at the input of the device being maximal. This situation is called *uncloaking*. When the modulation transistor is turned ON, it shortens one of the inductors or capacitors, resulting in a resonant frequency for the circuit different from the frequency of the electromagnetic field. When it shortens one of the two inductors connected

© 2011 by Taylor and Francis Group, LLC



FIGURE 3.4
Cloaking and uncloaking modes produced by the control transistor in the transponder and the different resonant frequencies generated. (a) Uncloaked. (b) Cloaked.

in series, the resulting resonant frequency is higher than the frequency of the field; when it shortens one of the two capacitors connected in series, the resulting resonant frequency is lower. In any case, the frequency of the circuit and the frequency of the field are different, and therefore most of the energy of the electromagnetic field is rejected by the filter, resulting in the voltage generated at the input of the device being minimal, ideally zero. This situation is called *cloaking*. The same cloaking–uncloaking approach is used by the transponder to transmit data to the interrogator. Using this approach, the digital signal controls the modulation transistor.

Example 3.1:

Calculate the values of the external inductors needed to use in a transponder based on the MCRF451 device.

Solution:

The MCRF451 has an internal capacitance of 95 pF and operates at a frequency of 13.56 MHz. Using the equations shown in Figure 3.3, the total inductance

© 2011 by Taylor and Francis Group, LLC

necessary is L_T = 1.45 μH. With this inductance, the circuit resonates at 13.56 MHz, and therefore the energy from the electromagnetic field is passed to the device. The L_T = 1.45 μH of external inductance will be split between L_1 and L_2.

The value of L_1 can be calculated using the equations from Figure 3.3 now for the case of detuned frequency. The detuned frequency should be between 3 MHz and 6 MHz away from the tuned frequency. For the structure used by the MCRF451 device, the detuned frequency will be higher than the tuned frequency. Using for example a frequency shift of 4 MHz, the detuned frequency becomes 17.56 MHz, resulting in a value of L_1 equal to 864 nH. Assuming initially a value for the coupling coefficient between L_1 and L_2 equal to zero ($k = 0$), the required value for L_2 is 586 nH. It can be observed that $L_1 > L_2$ as it is required. In a more realistic situation, the value of the coupling coefficient will be between 0 and 1, resulting in a lower value for L_2.

3.1.2 Power Management

In order to be operative, the transponder needs to convert the radiofrequency voltage detected by the antenna into a DC voltage. The voltage required to bias the internal components in the transponder is higher than the voltage detected by the antenna. Therefore, the transponder requires the use of voltage multipliers to reach the values necessary by the biasing voltage.

A voltage multiplier is a circuit that converts a lower AC voltage into a higher DC voltage. Figure 3.5 shows the basic structure of a simple voltage multiplier called a *voltage doubler.*

Assuming initially ideal diodes for simplicity, diode D1 is forward biased during the phase of negative input voltage, while diode D2 is reverse biased and therefore capacitor C2 is disconnected from the rest of the circuit. In this stage, capacitor C1 charges to a DC voltage ideally equal to the amplitude of the AC signal. Afterward, during the phase of positive input voltage, the biasing of the diodes reverses: D2 is forward biased, and D1 becomes reverse biased. This causes capacitor C2 to be directly connected to the input of the AC signal. Taking into consideration the voltage at which capacitor C1 was originally charged, the DC voltage at capacitor C2 will be equal to twice the amplitude of



FIGURE 3.5
Structure of a single-stage basic voltage multiplier. V_{RF} models the voltage generated by the electromagnetic field in which the transponder is immersed.

© 2011 by Taylor and Francis Group, LLC

the input voltage. Considering now the minimum ON voltage for real diodes, the voltage at the output of the structure shown in Figure 3.5 is

$$V_{out} = 2(V_p - V_{ON}) \tag{3.1}$$

where

V_{out} = the output DC voltage,

Vp = the peak voltage detected at the antenna terminals

V_{ON} = the minimum direct voltage across the diode to turn it on

Figure 3.6 shows the intermediate signals observed at the different nodes in the voltage doubler structure. The voltage supply models the radiofrequency signal detected at the terminals of the antenna in the transponder. The graph of the output voltages shows how the output capacitor is being charged until it reaches the steady-state level predicted by equation (3.1). Once the transient disappears, the output voltage stabilizes and will remain at that level as long as the transponder is immersed in that electromagnetic field.

In practical RFID systems, because the RF voltage detected at the antenna terminals is relatively small, the voltage doubler structure shown in Figure 3.5 does not produce a high enough voltage to power the integrated circuit in the transponder. This situation can be resolved by connecting additional voltage doublers. The resulting structure is known as a *Dickson charge pump*, resulting in an output DC voltage equal to



FIGURE 3.6
Signals observed at diverse points in the single-stage voltage multiplier. (a) Input signal. (b) Intermediate signal consisting of the input signal plus a DC component equal to its peak value. (c) Output signal. After the transient disappears, the output signal is a DC signal with a value equal to the double of the peak amplitude of the input signal.

© 2011 by Taylor and Francis Group, LLC

$$V_{out} = 2N(V_p - V_{ON}) \tag{3.2}$$

where N is the number of basic voltage doubler cells.

Figure 3.7 shows a three-stage Dickson charge pump. Its output voltage is equal to six times the peak voltage for the input minus the turn-on voltage for the diodes. Figure 3.8 shows the intermediate signals observed at several nodes in this structure. The sensitivity of the different graphs in volts per division has been kept the same to better observe how at each intermediate node, the AC signal has an additional offset equal to its peak value. The final DC output voltage is predicted by equation (3.2).

There is, however, a practical limit to the number of stages that is reasonable to consider for use in a practical application. As the number of stages increases, the number of required diodes increases by a factor of 2, and therefore the power dissipated by the charge pump also increases in the same ratio, decreasing the overall efficiency of the circuit. The efficiency of the charge pump is given by equation (3.3):

$$\eta_{pump} = \frac{P_{load}}{P_{load} + P_{consumed}} = \frac{V_{out}}{V_{out} + 2N\,V_{ON}} \tag{3.3}$$

where N is the number of stages in the charge pump.


Voltage doubler structure
Voltage doubler structure
Voltage doubler structure
V_out
V_RF
+
−

FIGURE 3.7
Dickson charge pump structure used to increase the DC voltage extracted from the radiofrequency signal generated by the electromagnetic field in which the transponder is immersed.

© 2011 by Taylor and Francis Group, LLC



FIGURE 3.8
Signals observed at different points in the Dickson charge pump. After each stage, the overall signal increases its DC component until it only contains a DC component at the output of the last stage.

Equation (3.3) shows that the efficiency of the charge pump will increase by using diodes with a lower turn-on voltage. To this extent, several types of devices have been used and several more types are being currently investigated. The most common approach is to use Schottky diodes due to their electrical characteristics that make them extremely attractive for this purpose. However, using Schottky diodes increases the complexity of manufacturing the transponder, thus resulting in a higher cost. For this reason, the use of ultra-low-power complementary metal oxide semiconductor (CMOS) diodes appears to be an attractive alternative as they can be manufactured with the rest of the transponder and therefore they will not increase the cost of manufacturing the transponder.

3.2 Signals in the Transponder

3.2.1 Signal Encoding

The digital signals in the transponder are encoded using one or more of these common encoding schemes that are represented in Figure 3.9.

© 2011 by Taylor and Francis Group, LLC



FIGURE 3.9
Common signal-encoding techniques. (a) Nonreturn-to-zero (NRZ): *1* represented by a high logic level; *0* represented by a low logic level. (b) Differential biphase: *1* represented by a change in level at the start of the clock period; *0* represented by no change in level at the start of the clock period. There is always a change of level at the middle of the clock period. (c) Manchester: *1* represented by a high-to-low transition at the middle of the clock period; *0* represented by a low-to-high transition at the middle of the clock period.

These encoding techniques are as follows:

NRZ (nonreturn to zero): There is no data encoding done. The 1′s and 0′s are clocked from the data array directly to the output transistor that will close or open the switch in the analog front end, as was shown in Figure 3.4. Although extremely simple, this encoding technique presents problems if the data to transmit have long strings of 1′s or 0′s because these may be misunderstood as the presence of a DC voltage in the line.

Differential biphase: Multiple encoding approaches using this method. This method embeds clocking information with the data and will help to synchronize the interrogator to the bit stream. In this approach, a level change occurs at the middle of every bit clock period. *1* is represented by a change in level at the start of the clock. *0* is represented by no change in level at the start of the clock.

Manchester code (biphase level, biphase_L, or split phase): This is a variation of the previous encoding method. There is not always a transition at the clock edge, but there is always a transition in the middle of the clock cycle, thus allowing one to extract the clock signal from the data signal. In Manchester code, a *1* is represented by a high to low level change in the middle of the clock. A *0* is represented by a low to high level change at the start of the clock. This type of encoding is used in the MCRF355/360 and the MCRF45X family of transponders manufactured by Microchip Technology.

© 2011 by Taylor and Francis Group, LLC

Example 3.2:

Assume that we are using a biphase-L format (Manchester) for encoding the digital data at a frequency of 70 kHz. The data bit *0* is sent by first detuning (cloaking) the device during 7 μs and then tuning (uncloaking) the device for an additional 7 μs. The data bit *1* is sent by uncloaking the device and then cloaking it for the same time periods.

3.2.2 Modulation and Demodulation

Modulation refers to changing one or more parameters in the carrier radiofrequency signal as a method to transmit the encoded signal. In practice, only one of the parameters (amplitude, frequency, or phase) of the radiofrequency is usually changed when transmitting simple digital data.

When the amplitude of the carrier changes depending on the encoded signal, the resulting modulated signal is called *amplitude shift keying*, or ASK. In this case, a high voltage in the envelope of the radiofrequency signal signifies a logic level *1*, while a low voltage in the envelope signifies a logic level *0*, following the appropriate signal-encoding method being used. ASK modulation is also known as *direct modulation* in RFID systems. ASK modulation offers the possibility of high data rates due to the simplicity of the process. The spectrum of the ASK signal is relatively narrow as it contains only energy at the frequency of the carrier signal and at each of the two sidebands. One sideband is located at the frequency of the carrier minus the frequency of the modulating signal, and the other sideband is located at the frequency of the carrier plus the frequency of the modulating signal. The bandwidth efficiency of a binary-modulated ASK signal is 1 bit/second/Hz. The detection of the ASK signal can be done using a coherent detector or a noncoherent detector. Noncoherent detection increases the simplicity of the overall system, although it reduces the ability to differentiate between the desired signal and noise. The immunity to noise can be increased by using a coherent detector, although the immunity to noise is overall lower than using an FSK or PSK modulation process. The bit error probability for noncoherent ASK modulation, assuming an additive white Gaussian noise limited channel, is

$$P\Big|_{\substack{ASK\\NONCOH}} = 0.5e^{\frac{-E_b}{4N_0}} + 0.5erfc\left(\sqrt{E_b/2N_0}\right) \tag{3.4}$$

where

P = the bit error probability

E_b/N_0 = the average bit power

$erfc(x)$ = the complementary error function for the argument x

© 2011 by Taylor and Francis Group, LLC

Similarly, the bit error probability for coherent ASK modulation is

$$P\big|_{\substack{ASK\\COH}} = 0.5erfc\left(\sqrt{E_b/2N_0}\right) \tag{3.5}$$

Figure 3.10 shows the bit error probability values obtained using equations (3.4) and (3.5) for different values of energy transmitted. From this graph it is possible to observe the decrease in bit error rates for coherent ASK modulation, which is especially significant when increasing the energy per bit transmitted.

When the encoding signal changes the amplitude of the carrier being transmitted, the resulting modulated signal is called *frequency shift keying*, or FSK. When the modulating signal is binary, FSK results in using two different frequencies for transmitting the digital data. The most common approach to FSK in RFID systems is called Fc/8/10: this means that a *0* is transmitted as an amplitude modulated clock cycle with a period corresponding to the carrier frequency divided by 8, and a *1* uses a period that corresponds to the carrier frequency divided by 10. Figure 3.11 shows the time representation for this FSK modulation.

The logic level *0* is transmitted by sending a total of eight cycles of the RF signal; the first four cycles have a higher amplitude than the last four cycles. The logic level *1* is transmitted by sending a total of ten RF cycles,



FIGURE 3.10

Error probability (Ps) for coherent and noncoherent ASK modulation as a function of the energy received (Eb/No).

© 2011 by Taylor and Francis Group, LLC



FIGURE 3.11
Structure of the FSK-modulated signal. The symbol *1* is represented by sending 10 RF cycles, while the symbol *0* is represented by sending 8 RF cycles. The message sent in the figure is *10011*.

with the first five cycles having a higher amplitude than the last five cycles. The change in amplitude between the first and second halves of the cycles allows one to count the number of cycles between transitions and therefore to differentiate between logic levels. In other words, the *1* and *0* are differentiated by looking at the number of periods between transitions.

Other FSK approaches used by other transponders are Fc/10/8, Fc/5/8, and Fc/8/5. Table 3.1 lists the relation between the encoding signal and the data transmitted.

The bandwidth required by the FSK signal is dependent on the existence or not of phase changes when changing frequencies. Obviously, in those FSK modulation approaches that exhibit abrupt phase changes, there will be more spectral components at higher frequencies, thus increasing the bandwidth. The bandwidth efficiency of a binary-modulated FSK signal depends on how the modulation process has been performed, but it approaches 2 bits/second/Hz. Similarly to ASK modulation, FSK signals can be recovered using noncoherent detectors or coherent detectors, with a coherent detector providing stronger noise immunity. The calculation of the bit error rate for FSK signals depends on the separation between the frequencies used to transmit the FSK signal. The optimal frequency selection occurs when these frequencies are a multiple of the frequency of the encoding signal. These are called *orthogonal frequencies*.

The bit error probability for noncoherent FSK modulation, assuming an additive white Gaussian noise limited channel, is

$$P\,\Big|_{\substack{FSK\\NONCOH}} = 0.5e^{\frac{-E_b}{2N_0}} \tag{3.6}$$

© 2011 by Taylor and Francis Group, LLC

TABLE 3.1

Different FSK Modulation Approaches

	Logic Level "0"	Logic Level "1"
Fc/8/10	8 RF cycles	10 RF cycles
Fc/10/8	10 RF cycles	8 RF cycles
Fc/5/8	5 RF cycles	8 RF cycles
Fc/8/5	8 RF cycles	5 RF cycles



FIGURE 3.12
Error probability (Ps) for noncoherent FSK and coherent FSK as a function of the energy received (Eb/No).

The bit error probability for coherent FSK modulation is

$$P\big|_{\substack{FSK\\COH}} = 0.5erfc\left(\sqrt{E_b/2N_0}\right) \tag{3.7}$$

Comparing equations (3.5) and (3.7) shows that if the two frequencies that make the FSK signal are chosen to be orthogonal, then the bit error rates for coherent ASK and coherent FSK signals are essentially the same. Figure 3.12 shows the probability of bit error as predicted by equations (3.3) and (3.4) for different values of energy per bit. This figure shows that the difference in performance between noncoherent detection and coherent detection for FSK signals is lower than for ASK signals. This has resulted in the widespread use of noncoherent FSK modulation due to its simplicity.

© 2011 by Taylor and Francis Group, LLC

Example 3.3:

Calculate the bit error rate for coherent and noncoherent ASK and FSK demodulation for the following signal-to-noise ratios (E_b/N_o): (a) 5 dB, (b) 10 dB, and (c) 15 dB.

Solution:

The bit error rates for each type of demodulation are given by equations (3.4) to (3.7). The first step is to express the signal-to-noise ratio in linear units. This results in the following values:

A. $E_b/N_o = 5$ dB ➔ $E_b/N_o = 3.16$ (linear units)
B. $E_b/N_o = 10$ dB ➔ $E_b/N_o = 10.0$ (linear units)
C. $E_b/N_o = 15$ dB ➔ $E_b/N_o = 31.6$ (linear units)

Bit error rates for noncoherent ASK demodulation are predicted by equation (3.4), resulting in the following:

With $E_b/N_o = 3.16$ (5 dB): $P_s = 0.264$ (approximately 1 error every 4 bits transmitted)
With $E_b/N_o = 10.0$ (10 dB): $P_s = 0.042$ (approximately 1 error every 24 bits transmitted)
With $E_b/N_o = 31.6$ (15 dB): $P_s = 0.185\ 10^{-3}$ (approximately 1 error every 5400 bits transmitted)

Bit error rates for coherent ASK demodulation are predicted by equation (3.5), resulting in the following:

With $E_b/N_o = 3.16$ (5 dB): $P_s = 0.037$ (approximately 1 error every 30 bits transmitted)
With $E_b/N_o = 10.0$ (10 dB): $P_s = 0.78\ 10^{-3}$ (approximately 1 error every 1300 bits transmitted)
With $E_b/N_o = 31.6$ (15 dB): $P_s = 9.47\ 10^{-9}$ (approximately 1 error every 100 million bits transmitted)

Bit error rates for noncoherent FSK demodulation are predicted by equation (3.6), resulting in the following:

With $E_b/N_o = 3.16$ (5 dB): $P_s = 0.103$ (approximately 1 error every 10 bits transmitted)
With $E_b/N_o = 10.0$ (10 dB): $P_s = 3.37\ 10^{-3}$ (approximately 1 error every 300 bits transmitted)
With $E_b/N_o = 31.6$ (15 dB): $P_s = 6.87\ 10^{-8}$ (approximately 1 error every 14.5 million bits transmitted)

Bit error rates for coherent FSK demodulation are predicted by equation (3.7), resulting in the following:

With $E_b/N_o = 3.16$ (5 dB): $P_s = 0.037$ (approximately 1 error every 30 bits transmitted)
With $E_b/N_o = 10.0$ (10 dB): $P_s = 0.78\ 10^{-3}$ (approximately 1 error every 1300 bits transmitted)
With $E_b/N_o = 31.6$ (15 dB): $P_s = 9.47\ 10^{-9}$ (approximately 1 error every 100 million bits transmitted)

© 2011 by Taylor and Francis Group, LLC

> These results show that the performance of coherent demodulation has a much better performance than noncoherent demodulation. Even for relatively noisy signals, coherent ASK shows a much lower bit error rate than when the demodulation is performed noncoherently. Therefore, it seems obvious to choose a coherent demodulation scheme when using ASK. While coherent FSK demodulation also shows a lower bit error rate than noncoherent FSK demodulation, the difference is not as strong as in the ASK case. For this reason, a noncoherent FSK demodulation may be preferred as it will reduce the complexity of the system without excessively degrading its performance.

When the encoding signal changes the phase of the carrier, the resulting modulated signal is called *phase shift keying* (PSK), as shown in Figure 3.13. PSK is basically the same approach as FSK with the difference being that only one frequency is used. The information is encoded here in the change of phase between clock cycles. PSK also allows for different approaches on this encoding. Because the receiver is only looking for changes of phase, it is possible to transmit information in a smaller number of radiofrequency cycles, resulting in using faster data transfer rates compared to FSK.

Some devices like the MCRF200 and the MCRF250, both from Microchip Technology, support two PSK modulation modes called PSK_1 and PSK_2. In PSK_1, the phase of the RF signal changes when the encoding data change. This means that, for example, the phase of the RF signal will change when the encoding signal changes from *1* to *0* or from *0* to *1*. In



FIGURE 3.13
A generic PSK-modulated signal. The figure shows that the PSK signal requires less RF cycles to transmit the digital data.

© 2011 by Taylor and Francis Group, LLC



FIGURE 3.14
Two variations of PSK modulation. In PSK_1, the phase of the carrier changes every time there is a change in the symbol transmitted. In PSK_2, the phase of the carrier changes every time the symbol transmitted is *1*.

PSK_2, the phase of the RF signal changes every time the encoding data have the logic level *1*. For example, the phase will change when the encoding data change from *0* to *1* or from *1* to *1*, but it will not change when the encoding data move from *1* to *0* or from *0* to *0*. Figure 3.14 depicts these two PSK modulation approaches.

A third PSK modulation mode available in some other devices—for example, the T5557 from Atmel®—is based on a phase change on the rising edge of the encoding signal.

The spectral occupancy of the PSK signal is identical to the ASK signal assuming that there are no phase changes abruptly occurring at the symbol boundaries. However, in contrast to ASK and FSK, the detection of PSK signals requires a coherent demodulator. The bit error rate for PSK signals is

$$P\big|_{\substack{PSK\\COH}} = 0.5erfc\left(\sqrt{E_b / N_0}\right) \tag{3.8}$$

When comparing the different modulation methods and assuming equal average energy per symbol transmitted, the different PSK modulation approaches present the strongest immunity against noise. Coherent FSK modulation with orthogonal symbols or coherent ASK modulation is the next best approach followed by the noncoherent FSK modulation. Noncoherent ASK modulation exhibits the poorest performance. For example, a bit error rate of 10^{-6} requires a value of Eb/No slightly above 10 dB for a PSK signal, but it will require a value of Eb/No of about 18 dB for a noncoherent ASK signal. Similarly, an energy Eb/No of 10 dB will result in a bit error rate of 1.5 10^{-5} in using PSK, but the bit error rate will increase up to 1.5 10^{-2} when using noncoherent ASK. This represents moving from 1.5 errors every 100,000 bits transmitted (PSK) to 1.5 errors every 100 bits transmitted (noncoherent ASK).

© 2011 by Taylor and Francis Group, LLC

3.3 The Logic System

3.3.1 Data Memory

The memory of RFID transponders is divided into data memory and configuration memory. Data memory stores the information that will be transmitted back to the interrogator. Configuration memory stores data regarding the configuration parameters for the transponder. Memory varies in size, rewriting capabilities, structure, and characteristics similar to those found in memory used in other products. The size of the memory ranges from 1 bit to 64 kbits or even larger, with the most common values being around a few hundred bits. One of the most important differences between transponders is whether the data stored in their memory can be rewritten by the user. This gives rise to the distinction between *read-only* transponders and *read/write* transponders. Because memory types, sizes, and structures can greatly differ between different transponders, the following examples are not intended to be viewed as a comprehensive guide, but to highlight some of the most commonly used approaches to memory in transponders.

The device MCRF200 from Microchip Technology contains a memory of 140 bits; 128 bits are data bits, and the remaining 12 bits are used for the configuration register. This is a one-time programmable (OTP) device that operates as a read-only device once it is programmed. The data memory can be programmed by the user using a contactless programmer or can be directly programmed by the factory at the time of production. The configuration register can only be programmed at the time of production. The manufacturer specifies memory data retention better than 200 years.

Figure 3.15 shows the block diagram of this device. The EEPROM memory is addressed by the column and row decoders at the clock rate. The output from the memory array is a bit stream that is directly fed into the modulation control and modulation circuit in order to be transmitted back to the interrogator. Figure 3.16 shows the description of the different bits for the configuration register in this memory.

CB12 is the bit that allows programming the device. Once CB12 is set to 1, the device cannot be programmed or erased. Because the MCRF200 does not support anticollision, bit CB11 is always 0. However, for the device MCRF250 that is similar to the MCRF200 with the only exception that MCRF250 supports anticollision, its bit CB11 is always set to 1. CB10 is used to establish the transmission rate when PSK modulation has been selected. Bits CB9 and CB8 establish the modulation for the encoded data using the modulation types shown in Section 3.2.2. Bits CB7 and CB6 determine how the data are encoded, as described in Section 3.2.1. Bit CB5 is always set to 0. Bits CB4, CB3, and CB2 are used to set the baud rate at which data are transferred. The default timing (CB4 = CB3 = CB2 = 0) is MOD128, meaning that the transmission rate is set at 128 RF cycles for bit.

© 2011 by Taylor and Francis Group, LLC



FIGURE 3.15
Structure of the circuitry for memory reading, writing, and control.

Because the MCRF250/251 device operates in the LF range, assuming a carrier frequency of 128 kHz, this setting will result in a transmission rate of 1 kHz. Conversely, the fastest transmission rate is MOD16, which will result in a transmission rate of 8 kHz. It is also important to keep in mind that MOD128 is the data rate used when programming the device. Finally, CB1 is used to specify the size of the data memory of 128 bits or 96 bits depending upon the needs of the user.

Example 3.4:

The configuration register for a MCRF 200 device is set to \$08D. Describe the settings for the device.

Solution:

The binary values for the configuration register are shown as follows:

CB12	CB11	CB10	CB9	CB8	CB7	CB6	CB5	CB4	CB3	CB2	CB1
0	0	0	0	1	0	0	0	1	1	0	1

CB12 = 0. The device has not been programmed yet.
CB11 = 0. MCRF200 does not support anticollision; therefore, CB11 is set to 0.
CB10 = 0. Rate of PSK modulation is equal to half of the carrier frequency.
CB9 = 0 and CB8 = 1. The modulation chosen is PSK_1. This means that the phase of the modulation signal changes at the change of the encoded data.
CB7 = CB6 = 0. Data encoded using nonreturn to zero level (NRZ_L).
CB5 = 0. No special meaning because CB5 is always set to 0.
CB4 = 1; CB3 = 1; CB2 = 0. Baud rate is MOD32, resulting in a 4 kHz baud rate.
CB1 = 0. Memory size is 128 bits.

© 2011 by Taylor and Francis Group, LLC

CB12	CB11	CB10	CB9	CB8	CB7	CB6	CB5	CB4	CB3	CB2	CB1
Lock	Anticol.	PSK	Modulation		Encoding		Sync	Baud Rate			Size

CB12: Memory array lock bit
0: User memory not locked
1: User memory locked

CB11: Anti-collision option
0: Disabled

CB10: PSK Rate
0: Carrier/2
1: Carrier/4

CB9, CB8: Modulation

CB 9	CB 8	Modulation
0	0	FSK (fig. 3.11)
0	1	PSK_1 (fig. 3.14)
1	0	ASK
1	1	PSK_2 (fig. 3.14)

CB7, CB6: Encoding

CB 7	CB 6	Encoding (fig 3.9)
0	0	NRZ
0	1	Manchester
1	0	Diff. Biphase
1	1	Inverted manchester

CB5: Sync
CB5 = 0 always

CB4, CB3, CB2: Baud rate

CB 4	CB 3	CB 2	Rate
0	0	0	MOD 128
0	0	1	MOD 100
0	1	0	MOD 80
0	1	1	MOD 32
1	0	0	MOD 64
1	0	1	MOD 50
1	1	0	MOD 40
1	1	1	MOD 16

CB1: User memory size
0: 96 bits
1: 128 bits

FIGURE 3.16
Configuration bits used in the MCRF200 transponder.

© 2011 by Taylor and Francis Group, LLC

Example 3.5:

State the configuration register for a transponder based on the MCRF250 device with the following parameters:

Blank (not programmed device)
Modulation: PSK_1.
PSK rate: Frequency half of the carrier frequency
Data encoding: NRZ_L
Baud rate: MOD 32
Memory size: 128 bits

Solution:

The MCRF250 is a device similar to the MCRF200, with the only difference being that it supports anticollision. Therefore, the configuration bit CB11 will be set to 1. The rest of the configuration bits have the same meaning as the MCRF200. The values of the configuration bits in this case are as follows:

CB12	CB11	CB10	CB9	CB8	CB7	CB6	CB5	CB4	CB3	CB2	CB1
0	1	0	0	1	0	0	0	1	1	0	1

Therefore, the hexadecimal value stored in the configuration register is $48D.

The devices MCRF355 and MCRF360, also manufactured by Microchip Technology, operate at the HF frequency of 13.56 MHz. They both have a total of 154 bits of memory that must be programmed using a contact programmer. This makes them act as read-only devices when they are used in the field but gives them the flexibility to be reprogrammed by the user when necessary. The data retention specified by the manufacturer is also better than 200 years.

The family of devices MCRF450/451/452/455 also operates in the HF frequency range at 13.56 MHz. As was discussed in Chapter 2, the different devices in this family use internal or external capacitors to modulate the radiofrequency signal. In discussing their internal memory structure, the concepts described for the device MCRF450 are also valid for the rest of the devices in this family. All of these devices have their memory organized in two areas: main memory and stored cyclic redundancy check (SCRC) memory. SCRC memory is used in the operation of the cyclic redundancy code necessary for the operation of the anticollision algorithm, as all of these devices support anticollision. The explanation of the CRC procedure is shown in Section 3.3.2.

The main memory of the MCRF450 and similar devices contains a total of 1024 bits and is structured in 32 blocks, each one with 32 bits. The SCRC memory is organized in 32 blocks, each one with 16 bits. Figure 3.17 shows the structure of the user memory in these devices.

The first three blocks (B0–B2) of the main memory are used to set up the operation of the device in a manner similar to a configuration register, while the remaining 29 blocks (B3–B31) are for user data. All the blocks of the main

© 2011 by Taylor and Francis Group, LLC



	BYTE 3								BYTE 2								BYTE 1								BYTE 0							
	32	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1
Block 0	FR	TF	TFT		DF		MT		TM			Available touser																				
Block 1									32-bit unique identification code for transponder																							
Block 2								Bits for write-protect mode. Each bit write-protects one block																								
Block 3									Data Fields for Fast Read Response (LS Block)																							
Block 4									Data Fields for Fast Read Response																							
Block 5									Data Fields for Fast Read Response (MS Block)																							
Block 6	DATA																															
Block 7	DATA																															
...	...																															
Block 31	DATA																															

FIGURE 3.17
Structure of the user memory for the MCRF 450 family of transponders.

memory with the exception of Block 1, which contains the ID or serial number of the transponder, can be individually rewritten block by block by a contactless programmer. Block 1 is programmed at the factory and is protected against being rewritten. The main memory is read or written in blocks of 32 bits, with the exception of bits 30 and 31 in Block 0 that can be selected individually. Blocks 3 to 5 constitute the fast read field (FRF) that is used by the interrogator in the transmission of commands to the transponder.

Block 0 is split into 21 bits of general memory available to the user and 11 bits containing operational parameters for the transponder. These operational bits, shown in Figure 3.17, are as follows:

FR (Bit 31). When FR = 0, the transponder will respond to the *fast read bypass* (FRB) command but will not respond to the *fast read request* (FRR) command from the interrogator. When FR = 1, the previous situation is reversed. These interrogator commands are further explained and described in Chapter 6.

TF (Bit 30). TF = 0 sets the transponder in *interrogator talks first* (ITF) mode. This means that it will wait for an FRR command. TF = 1 sets the transponder in *tag talks first* (TTF) mode if FR = 1. In this case, the transponder will send a *fast read response* without waiting for an FRR.

TFT (Bits 29–28). These two bits set the value for the parameter TCMAX when the transponder is in TTF mode. TCMAX is the number of

© 2011 by Taylor and Francis Group, LLC

TABLE 3.2

Configurations for TFT Bits

Bit 29	Bit 28	TCMAX
0	0	1
0	1	2
1	0	4
1	1	Continuous

TABLE 3.3

Configuration for DF Bits

Bit 27	Bit 26	TCMAX
0	0	32 Bits
0	1	48 Bits
1	0	64 Bits
1	1	96 Bits

fast read responses that the transponder can send after an FRR command, as shown in Table 3.2. For example, TCMAX = 2 means that the transponder can send its response twice for acknowledgment. If TCMAX is set to continuous mode, the transponder will send its response approximately every 80 ms until it receives the correct response from the interrogator. This is the default mode.

DF (Bits 27–26). These two bits set the length of the data transmitted by the transponder according to Table 3.3. The default data length is 32 bits.

MT (Bits 25–24). These two bits are hardwired and cannot be changed by the user. At the current state of production, these two bits are both set to 0. The remaining values are reserved for future applications.

TM (Bits 23–22–21). These three bits set up the total memory size. These three bits are also hardwired. Currently, there are only two possibilities allowed: 000 and 001. The code *000* describes a transponder with 512 bits of memory, while the code *001* describes a transponder with a memory size of 1 kbit.

Block 1 contains a unique 32-bit identification number for the transponder. This identification word is serialized by the manufacturer.

Block 2 contains the bits that set each block in write-protect mode. Each bit corresponds to its 32-bit block. For example, bit 5 will set Block 5 as writable or write-protected. When the write-protect bit is set to 1, the block is writable; when the bit is set to 0, the block is write-protected. It is important to note that once a block is write-protected, it cannot be changed back to being

© 2011 by Taylor and Francis Group, LLC

writable. The transponders are shipped to the user with all the write-protect bits to 1 with the exception of bit 1. This means that Block 1, which contains the unique ID for the transponder, cannot be changed by the user. Bits 31 and 30 in Block 0 (bits FR and TF) are not write-protectable, thus allowing the user to change how the transponder is operating. Finally, it is also important to note that Block 2 can also be set to be write-protected.

Blocks 3 to 5 contain data bits for the fast response. The size of the fast response was set by bits 27 and 26 (bits DF) in Block 0.

The SCRC memory section is organized into 32 blocks, each one with 16 bits as shown in Figure 3.18. The blocks contain the CRC code for the corresponding memory block sent back to the interrogator in order to check for anticollision.

One of the family of transponders operating at 13.56 MHz manufactured by Atmel® has an internal user memory ranging from 1 kbit to 64 kbits with the distinct feature that this memory is encrypted, thus providing an additional layer of protection. The *CryptoRF EEPROM* family offers user memory of 1 kbit, 2 kbits, 4 kbits, 8 kbits, 16 kbits, 32 kbits, and 64 kbits. In addition to the user memory, all these devices have a configuration memory of 2 kbits. This configuration memory is used to store eight sets of passwords for reading and writing, four crypto key sets, security access registers for each user zone and password, and key registers for each zone. The transponders in this family also support anticollision. Figure 3.19 shows the block diagram for these types of devices. As shown in the figure, while the analog front end is similar to that of any transponder, it differs in the existence of authentication and password verification prior to the device sending data.

Bit #	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
Stored CRC Block 0																
Stored CRC Block 1																
…	…															
Stored CRC Block 31																

FIGURE 3.18
Structure of the stored CRC memory used in the MCRF 450 family of transponders.

© 2011 by Taylor and Francis Group, LLC


Antenna
Power
RF section
Control
User memory
Authentication encryption and certification
Error detection
Random number generator
Password verifi-cation
Analog front-end
Anticollision

FIGURE 3.19
Transponder with encrypted memory showing the additional components needed for this process.

In the transponders with user memory size of 64 kbits, 32 kbits, or 16 kbits, the EEPROM user memory is divided into 16 user zones. Figure 3.20 shows the memory map for the 64 kbit memory transponder. As seen in the figure, each user zone is configured for storing 512 bytes (4096 bits), giving a total user memory of 64 kbits. For the 32 kbit transponder, its memory is also divided into 16 user zones, each one of 256 bytes (2048 bits); for the 16 kbit memory, the size of each user zone is 128 bytes (1024 bits).

The transponder from the same family with a memory of 8 kbits has a similar structure, although the memory is divided into eight different user zones. Each zone can store 128 bytes (1024 bits). The memory for the transponders with 4 kbits, 2 kbits, and 1 kbit of user memory are all divided into four user zones. For the 4 kbit memory, each user zone stores 128 bytes (1024 bits); for the 2 kbit memory, each user zone stores 64 bytes (512 bits); and for the 1 kbit memory, each user zones stores 32 bytes (256 bits).

In all cases, the access to the user zones is only possible after having some security requirements are met. These are defined by the user during the setup of the device. The initial state for the transponders in this family is to have all the security features disabled. The user must set up the level of protection by configuring the security requirements for the transponder. These security requirements are stored in the configuration memory.

All the transponders in the CryptoRF family have a configuration memory of 2048 bits. This memory stores passwords, keys, codes, and security

© 2011 by Taylor and Francis Group, LLC

	Address	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
User Zone 0	0								
	1								
	...	Total of 512 bytes (4096 bits) in Zone 0							
	512								
User Zone 1	0								
	1								
	...	Total of 512 bytes (4096 bits) in Zone 1							
	512								
User Zones 2 to 14	...								
User Zone 15	0								
	1								
	...	Total of 512 bytes (4096 bits) in Zone 15							
	512								

FIGURE 3.20
Memory map divided into 16 user zones, each one containing 4096 bits for a total of 65,536 bits (64 kbits).

definitions for each one of the user zones. The access rights to the configuration memory are defined in the control logic and cannot be altered by the user. The transponder can be programmed so each zone uses a different set of passwords. This is especially useful in the case of different users accessing the transponder. In addition, the transponders include three fuses that must be blown during the setup process. The fuses lock some of the portions of the configuration memory.

Atmel® also manufactures families of transponders that operate in the LF range, as well as in the UHF range. For example, the transponder ATA5558 can operate between 100 kHz and 200 kHz, while the ATA5590 operates in the UHF range from 860 MHz to 960 MHz. Both devices contain an internal EEPROM divided into a user memory of 1024 bits and a system memory of 320 bits. The user memory is organized in pages of 128 bits, and each page in blocks of 32 bits. Each one of the blocks must be programmed separately. Pages are protected against overwriting by the use of a lock bit that, as shown in Figure 3.21, is the most significant bit of each block.

The system memory in the ATA5590 transponder contains a page with the identification information for the transponder (Tag_ID page), a page with system-level information available to the user, and two blocks with system-level information for the manufacturer of the transponder.

© 2011 by Taylor and Francis Group, LLC



FIGURE 3.21
Memory map with lock bit. The lock bit is located at the MSB in each address.

3.3.2 Cyclic Redundancy Check for Error Detection

The cyclic redundancy check is the most used method for ensuring the integrity of the digital signals in some RFID transponders. In particular, CRC is used as a method of error detection in the digital stream transmitted and received by the transponders that support CRC. It is important to note that although the CRC algorithms detect the existence of errors, they do not make corrections.

The CRC method is based on appending additional information to the message being transmitted. This additional information is mathematically related to the message and therefore is redundant. At the receiving end, the receiver checks this additional information to verify that it agrees with the message being transmitted. This allows the receiver to determine with a certain degree of probability the existence of an error in the transmission. However, this method implies that not all errors are subject to detection. Simply stated, the CRC method is implemented by dividing the entire numeric binary value of the message by a constant. This constant is called a *generator polynomial*. The reminder in the division is then appended to the message. The polynomial that is used for the division is chosen from a family of polynomials with certain mathematic properties whose study is beyond the scope of this book. The transponders from Atmel and Microchip both use a polynomial known as the CRC-CCITT-16, although their specific

© 2011 by Taylor and Francis Group, LLC

implementation is somewhat different. This polynomial is also used in other digital transmissions such as CDMA and Bluetooth, among others. The CRC-CCITT-16 polynomial is

$$CRC - CCITT - 16: x^{16} + x^{12} + x^{5} + x^{0}$$

Reading the polynomial from most significant bit (MSB) to least significant bit (LSB) (normal representation) results in a value of 1021 hexadecimals. We must take into consideration that CRC polynomials have always had their MSB equal to 1, and for this reason it is not considered in the calculation of their values. Reading the polynomial from LSB to MSB (reverse representation) results in the value of 8048 hexadecimals. Microchip Technology uses reverse representation, while Atmel® uses normal representation.

CRC can be hardware-implemented using shift registers and exclusive-OR (XOR) gates in the feedback process shown in Figure 3.22. The encoder shown in Figure 3.22 consists of 16 shift registers and the exclusive-OR gates. The initial value loaded into the shift registers is $FFF in the Microchip Technology approach and $000 for the Atmel approach. The encoder performs the exclusive-OR function and shifts the registers until the last bit of the data stream is entered. At that point, the CRC value of the data set is equal to the values in the shift registers. When the transponder transmits data, the calculated CRC value is attached to the data.

The receiver performs an identical process and verifies that the CRC code generated by the receiver is equal to the CRC code appended to the message. The advantage of the CRC method is that the current state of one of the shift registers is a result of considerable past history, as it has to go through a lengthy process. Therefore, it is unlikely that a burst of errors will produce a CRC code equal to the one generated in the absence of errors. In fact, the CRC-CCIT-16 code is able to detect all error bursts of 16 bits or less as well as 99.9% of error bursts of more than 16 bits.



FIGURE 3.22
Structure of a generic CRC encoder using the CRC-CCITT-16 polynomial.

© 2011 by Taylor and Francis Group, LLC

Different manufacturers may also follow different approaches as to whether they append the CRC value with its LSB or MSB first. The specification documents for the transponders describe how the CRC value is attached to the data. The previous section described the structure of memory in some specific transponders. For example, the user memory for the MCRF450 family of transponders from Microchip Technology is divided into 32 blocks. When the interrogator tries to write data into any of these blocks, before doing any processing, the transponders check the CRC. If the CRC data are correct, the transponder proceeds with storing the data and the CRC in memory. Then, the transponder immediately transmits back the data and stored CRC to the interrogator for verification. If the CRC received by the transponder is incorrect, the transponder ignores the received message and waits for the next command with a valid CRC.

3.4 Transponder Programming

The programming of the transponders can be done by the manufacturer at the time of production or by the end user. *Programming the transponders* means to store a unique identification number in its memory, as well as to set up the configuration parameters for the communication between the transponder and the interrogator and additional parameters such as password protection. Transponders can be programmed using contact or noncontact methods.

The MCRF200/250 family of transponders manufactured by Microchip Technology is an example of a contactless programmable device. Because the MCRF200/250 family is made up of one-time programmable devices, the device can only be programmed when it is blank from the manufacturing process. Programming this device requires a specific sequence of radiofrequency signals applied following this sequence:

Initial, power-up RF signal (125 kHz for the MCRF200/250 family) lasting between 80 μs and 180 μs.

Absence of RF field lasting between 50 μs and 100 μs.

A continuous FSK signal that serves as a *verify* signal, lasting 131 ms. This signal is required for the transponder to be energized in order to output all the data contained in its 128 bits of memory. Because the device is blank at the time of programming, the output data are all *1*.

Programming data: After completing the verify mode, the device enters the programming mode. The device is programmed starting with bit 1 and finishing with bit 128. The symbol *1* is programmed by sending a low-power RF signal with an amplitude similar to the one used for the initial power-up. The symbol *0* is programmed by sending a high-power RF signal with an amplitude approximately equal to 2.2 times the amplitude used for the symbol *1*.

© 2011 by Taylor and Francis Group, LLC

Device response: After the 128 bits have been programmed, the device responds by transmitting the programmed data.

The MCRF355/360 family of transponders, also from Microchip Technology, has 154 bits of memory that can be programmed by using a contact programmer. Also, the memory in this family of devices can be reprogrammed. Figure 3.23 shows the pin diagram for this device.

Note that Pin 3 (Ant. A) and Pin 6 (Ant. B) are used to connect the external capacitors and inductors, as was shown in Figures 2.16 and 2.17, while Pin 5 (Vss) serves a ground. In order to program these devices, Pins 3, 6, and 5 are connected to ground, Pin 8 (Vdd) is connected to the positive voltage source, Pin 2 (CLK) is connected to the clock, and Pin 1 (Vprg) is connected to the signal that will be programmed in the transponder.

Some specific codes are used to carry out specific functions in the memory of the device. For example, because this device is reprogrammable, when the user wants to write new data into memory, the existing data must be erased first. This is done by sending the code 0111010100 through the VPRG pin, as shown in Figure 3.24.

Similarly, to start the programming sequence, the user must transmit the code 0111010010, followed by the data bits to store in memory. In total, there will be a total of 166 bits sent to the device: the first 12 bits are the command to program, and the remaining 154 bits are the data to be stored in memory. Finally, the data stored in memory can be read by transmitting the code 0111010110 to the device. After this code has been transmitted, the device will output the data stored in its memory.



Pin	Function
1	VPRG
2	CLK
3	Antenna A
4	NC
5	V_{ss}
6	Antenna B
7	NC
8	V_{dd}

FIGURE 3.23
Pins for the MCRF355/360 transponders.

© 2011 by Taylor and Francis Group, LLC



FIGURE 3.24
Code sent to erase existing data in memory using a contact programmer.

3.5 Summary of Electrical Specifications for RFID Transponders

The manner in which manufacturers specify the performance of their transponders varies greatly, not only among different manufacturers but also for devices from the same manufacturer. Tables 3.4 to 3.7 attempt to show the most important performance specifications from different manufacturers of RFID transponders. Table 3.4 does not pretend to be an exhaustive list of available devices, but just aims to show specific examples of device performance. The values of the parameters found in Tables 3.4 to 3.7 should be seen as somewhat typical performance values.

Table 3.4 shows the performance characteristics of three RFID transponders manufactured by Microchip Technology. The device MCRF200 is listed as a *125 kHz microID® Passive RFID Device*; the MCRF250 is exactly similar to the MCRF200 but incorporates anticollision; the MCRF355/360 family of devices is listed as *13.56 MHz Passive RFID Devices with Anti-Collision Feature*; and the devices in the MCRF450 family are listed as *13.56 MHz Read/Write Passive RFID Devices.*

Table 3.5 shows the electrical performance characteristics for four transponders manufactured by Atmel®. The ATA5567 device is listed as a *Multifunctional 330-Bit Read/Write RF Identification IC*; the ATA5570 is listed as a *Multifunctional 330-Bit Read/Write RF Sensor Identification IC*; the ATA 5558 is listed as a *1 kbit R/W IDID® with Deterministic Anticollision*; and the T5557 is listed as a *Multifunctional 330-Bit Read/Write RF Identification IC.*

Table 3.6 shows the performance parameters of two additional transponders from Atmel®. The device TK5530 is listed as a *read-only transponder,* while the TK5551 is listed as a *standards read/write ID transponder with anticollision.* The difference between these transponders and those evaluated earlier is

© 2011 by Taylor and Francis Group, LLC

TABLE 3.4

Summary of Electrical Parameters for Several RFID Transponders Manufactured by Microchip Technology

Parameter	MCRF 200/250	MCRF 350/360	MCRF 450/451/452/455
Operating frequency	100 kHz to 400 kHz	13.56 MHz	2 MHz to 35 MHz
Dynamic coil current	50 µA		
Operating current	5 µA	7 µA	20 µA
Maximum current through antenna pads	50 mA	40 mA	40 mA
Current leakage		10 nA	
Turn-on voltage	10 Vpp between antenna pads 2 V_{DC}		
Reading voltage		2.4 V	2.8 V
Testing voltage		4.0 V	
Programming voltage		V_{IH}: 2.8 V V_{IL}: 1.2 V	
Coil voltage while reading		4 Vpp	4 Vpp
Coil clamp voltage		32 Vpp	
Programming time	2 sec (for all 128 bit array)		5 ms (for a 32-bit block)
Sleep time		50 ms to 200 ms	
Modulation resistance		< 4 Ω	< 5 Ω
Internal capacitance	2 pF	100 pF	95 pF (MCRF451) 30 pF (MCRF 452) 50 pF (MCRF 455)
Data retention	200 years	200 years	200 years
Maximum storage temperature	-65°C to +150°C	-65°C to +150°C	-65°C to +150°C
Maximum ambient temperature	-40°C to +125°C		-40°C to +125°C
Maximum dissipated power			500 mW

[a] Blank spaces in the table indicate that the manufacturer did not provide information for that specific parameter.

that the ones shown below incorporate the coil for the antenna within the transponder. Moreover, the operating characteristics are given as strength of magnetic field instead of voltage or current.

Table 3.7 summarizes the most important characteristics of several transponders manufactured by Texas Instruments under their Tag-it™ commercial name. The manufactured has also chosen to specify their reading and writing thresholds as field intensity.

© 2011 by Taylor and Francis Group, LLC

TABLE 3.5

Summary of Electrical Parameters for Several RFID Transponders Manufactured by Atmel®

Parameter	**ATA5567**	**ATA5570**	**ATA5558**	**T5557**
Operating frequency	100 kHz – 150 kHz	100 kHz – 150 kHz	100 kHz – 250 kHz	100 kHz – 150 kHz
Supply current read mode	4 µA	4 µA	7 µA	4 µA
Supply current programming	40 µA		40 µA	40 µA
Maximum DC current	20 mA	20 mA	20 mA	20 mA
Maximum AC current	20 mA	20 mA	20 mA	20 mA
Coil voltage normal mode	3.6 V		4 V	4 V
Coil voltage Read / Write	> 6 V	> 10 V	> 6 V	> 6 V
Coil voltage Programming	> 8 V		> 6 V	> 8 v
Clamp voltage	17 V – 23 V	17 V – 23 V	7 V – 16 V	17 V – 23 V
Internal capacitance	78 pF	340 pF	78 pF	78 pF
Start-up time	< 1 msec	< 3 msec	< 3 msec	< 3 msec
Programming cycles	100,000 cycles	100,000 cycles	100,000 cycles	100,000 cycles
Data Retention	50 years	50 years	50 years	50 years
Maximum storage temperature	-40°C to +150°C	-40°C to +150°C	-40°C to +150°C	-40°C to +150°C
Maximum operating temperature	-40°C to +85°C	-25°C to +105°C	-40°C to +85°C	-40°C to +85°C
Maximum dissipated power	100 mW	100 mW	100 mW	100 mW

3.6 Mechanical Considerations and Transponder Assembly

The integrated circuits or chips in which the transponders are based are available in different packages. While commercial transponders use the chip-on-board (COB) technique described in Chapter 2, this package is not adequate for the development of prototypes. For this reason, most of the transponders are also available in the more common plastic dual-in-line packages (PDIPs) or small outline plastic packages (SOICs).

For example, some of the transponders described in this chapter, such as the MCRF200/250, the MCRF355/360, and the family of MCRF450 transponders, all manufactured by Microchip Technology, are available in these three packages (COB, SOIC, and PDIP). In their SOICs or PDIPs, these are available in eight pins; four of the pins are for testing purposes, two of the pins are for

© 2011 by Taylor and Francis Group, LLC

TABLE 3.6

Summary of Electrical Parameters for Several RFID Transponders Manufactured by Atmel®

Parameter	TK5530	TK5551
Resonance frequency	121.4 kHz – 129.2 kHz	120 kHz – 130 kHz
Inductance	3.95 mH	3.8 mH
Quality factor	13	13
Max field strength before modulation	2 A/m	4 A/m
Field strength operation	30 A/m (-40°C) – 17 A/m (+85°C)	30 A/m (-40°C) – 17 A/m (+85°C)
Field strength programming mode		50 A/m
Modulation Range	4.0 V (20 A/m) – 8.0 V (100 A/m)	4.0 V (20 A/m) – 8.0 V (100 A/m)
Programming time		16 ms per block
Data retention		10 years
Programming cycles		100,000 cycles
Absolute maximum field strength	1000 A/m	1000 A/m
Maximum storage temperature	-40°C to +125°C	-40°C to +125°C
Maximum operating temperature	-40°C to +85°C	-40°C to +85°C

connecting the transponder antenna, and the two remaining pins are not-connect pins. The devices ATA5570 and ATA5567/5558 from Atmel® are also available in COB packages and PDIPs, also using eight pins. The ATA5570 uses four not-connect pins, two pins for connecting the antenna, one pin for ground, and one pin for connecting the output of an external sensor. Because the ATA5567 and ATA5558 do not use an external sensor, their pinout is much simpler using six not-connect pins and two pins for connecting the external antenna. The dimensions of the COB version for all these transponders are 8 mm × 5 mm with a thickness of 0.4 mm. This extremely reduced size makes it ideal for incorporating the transponder and its antenna into the inlay. Transponders, especially in their COB form, are extremely sensitive to issues such as electrostatic discharge and their exposure to ultraviolet light that may result in erasing the contents in their memory cells. However, the use of X-rays for die inspection does not harm the device or erase their memory cell contents.

The process for assembling the whole transponder varies depending on the frequency range at which it will operate as well as the specifications for the final product. For transponders operating in the LF region, the assembly process starts by preparing the die and the capacitor and testing the functionality of the combined die-capacitor element. This is followed with preparing the antenna coil used in this frequency range and creating the inlay formed by the coil and the COB. After the inlay has successfully passed the test, the finished transponder is processed depending on the

© 2011 by Taylor and Francis Group, LLC

TABLE 3.7

Summary of Electrical Parameters for Several RFID Transponders Manufactured by Texas Instruments (Tag-it™)

Parameter	**RI-I11-112A**	**RI-I02-112A**	**RI-I03-112A**	**RI-I15-112B**	**RI-I16-112A**	**RI-I17-112A**
Resonance frequency	13.86 ± 0.2 MHz	13.86 ± 0.2 MH	13.86 ± 0.2 MH	14.1 ± 0.2 MH	13.70 ± 0.4 MH	13.80 ± 0.4 MH
Typical required field for read	96 dBμA/m	94 dBμA/m	107 dBμA/m	98 dBμA/m	113 dBμA/m	110 dBμA/m
Maximum required field for read	101 dBμA/m	97 dBμA/m	109 dBμA/m	101 dBμA/m	116 dBμA/m	113 dBμA/m
Typical required field for write	101 dBμA/m	97 dBμA/m	111 dBμA/m	101 dBμA/m	116 dBμA/m	113 dBμA/m

© 2011 by Taylor and Francis Group, LLC

desired final product, such as card lamination and plastic molding. The last step in this process is a final functional test.

Transponders operating in the HF region can be assembled using three different methods. The first method, which results in the transponder with the COB, is based on the same assembly process as described earlier for LF transponders. A second method results in creating the transponder with direct wire bonding to the antenna that can be etched, printed, or stamped. This assembly method starts by preparing the die; preparing the antenna on the substrate etched, printed, or stamped; and then making the inlay by direct wire bonding to the antenna. After the inlay test, the finished transponder is created by using card lamination, plastic molding, or another method. The last step is a final functional test. The third method creates a transponder with a flip-chip process using a bumped die. The process starts by die bumping for flip-chip assembly, preparing the antenna on the substrate by etching, printing, or stamping it. The inlay is then created using the flip-chip process to attach the antenna to the die. This is also followed by the inlay test, and the finishing of the transponder by lamination or plastic molding. As always, the last step is a final functional test.

© 2011 by Taylor and Francis Group, LLC

4

Antennas for Interrogators

CONTENTS

4.1 Antennas for HF and LF Interrogators 86
  4.1.1 Design of Antennas for HF and LF Interrogators 86
  4.1.2 Antenna Matching 96
  4.1.3 Multiple Antenna Systems 103
4.2 Auxiliary Elements for LF and HF Interrogator Antennas 104
  4.2.1 Antenna-Tuning Indicators 104
  4.2.2 Antenna Multiplexers 104
  4.2.3 Preamplifiers 105
4.3 Antennas for UHF Interrogators 106
  4.3.1 Design of Antennas for UHF Interrogators 106
  4.3.2 Transmission Lines and Connectors for UHF Interrogators 111
4.4 Commercial Antennas for RFID Interrogators 114
  4.4.1 Antennas for RFID Interrogators 114
  4.4.2 Tuning Boards for Interrogator Antennas 116

This chapter describes the principles of design for interrogator antennas. The basic theory that describes the behavior of the antennas used in interrogators is the same that was used to describe the behavior of antennas used in transponders. However, in the case of antennas for interrogators, the size of the antenna is much less critical: because the interrogator has less size restrictions, the antenna can have larger dimensions. This results in an increased antenna performance. Furthermore, antennas for interrogators can be created with thicker conductors that can substation higher currents, resulting in stronger electromagnetic fields. The chapter starts by describing the basic principles used in the design of antennas for interrogators operating in the high-frequency (HF) and low-frequency (LF) bands. It continues by describing auxiliary elements such as tuning indicators, multiplexers, and preamplifiers used with those antennas in order to improve the overall performance of the system. The next section describes the basic principles used in the design of antennas in interrogators operating in the ultra-high-frequency (UHF) band. The last section in this chapter shows different examples of commercially available antennas for interrogators.

© 2011 by Taylor and Francis Group, LLC

4.1 Antennas for HF and LF Interrogators

4.1.1 Design of Antennas for HF and LF Interrogators

Antennas for interrogators operating in the HF and LF ranges are designed for parameters such as maximum read distance for transponders, transponder read rate, as well as regulations such as the maximum field allowed in some specific conditions. The majority of antennas used in HF and LF interrogators are variations of the coil antenna that generates a magnetic field. These antennas are typically called *portal antennas* because due to their physical dimensions and geometry, they can be placed in portals. A small number of antennas for HF and LF interrogators are based on a small dipole that generates an electric field. These antennas are normally called *stick antennas*.

In general, the distance at which a transponder can be read increases with the size of the antenna. However, this size cannot increase arbitrarily. This is due to the practical limitations in using an antenna of a large size and also to the limitations due to regulatory issues. Examples of these factors are the decrease in the signal-to-noise ratio as the size of the antenna increases; the potential for exceeding the regulatory limits of field strength; the need for shielding nearby electronic equipment to avoid unwanted interaction with the generated field; the increase in the area of null zones in which the generated field is zero; and the increase in the inductance of the antenna to a point that makes matching the antenna to the reader extremely difficult, if not impossible.

Interrogators working in the HF range expect an antenna tuned at the frequency of 13.56 MHz, with an input impedance of 50 Ω and a loaded quality factor (Q factor) of less than 20. Similarly, interrogators operating in the LF range expect an antenna tuned to the appropriate LF frequency, an input impedance of 50 Ω, and a loaded Q factor of less than 20. In both cases, for best performance, the match of the interrogator with the antenna should have a *voltage standing wave ratio* (VSWR) lower than 1.2.

The VSWR is a measure of how much of the energy sent through a transmission line is reflected back to the transmitter instead of being transferred to the antenna in order to be converted to the electromagnetic field. Standing waves occur as a result of the existence of incident and reflected waves. The ratio of reflected voltage to incident voltage is called the *reflection coefficient* and is denoted by the symbol Γ. Mathematically, the reflection coefficient is

$$\Gamma = \frac{E_r}{E_i} \tag{4.1}$$

where

Γ = the reflection coefficient

E_{r} = the reflected voltage

E_{i} = the incident voltage

© 2011 by Taylor and Francis Group, LLC

The reflection coefficient can also be expressed in terms of the impedance of the transmission line and the impedance of the load as

$$\Gamma = \frac{Z_L - Z_o}{Z_L + Z_o} \tag{4.2}$$

where Z_L = the impedance of the load and Z_o = the characteristic impedance of the transmission line.

Equation (4.2) shows that when the transmission line is terminated with a load with an impedance equal to its characteristic impedance, the reflection coefficient is zero. This means that all the energy present in the line has been transferred to the load. When the line is terminated with either an open circuit or a short circuit, the absolute value of the reflection coefficient is equal to 1. This indicates that none of the energy present in the line has been transferred to the load, but is being reflected back to the transmitter. For any other terminations, including complex impedance values, the value of the reflection coefficient is, in absolute value, between 0 and 1. This indicates that a portion of the energy present in the line has been transferred to the load and some other portion of the energy remains in the line.

The VSWR is defined as the ratio of the maximum voltage in the line ($E_{\max}$) compared to the minimum voltage in the line ($E_{\min}$):

$$VSWR = \frac{E_{\max}}{E_{\min}} \tag{4.3}$$

The VSWR can also be defined as a function of the reflection coefficient (Γ):

$$VSWR = \frac{1 + |\Gamma|}{1 - |\Gamma|} \tag{4.4}$$

Equation (4.4) shows that in the case of maximum reflection due to the transmission line terminated in an open or a short circuit, which results in $|\Gamma| = 1$, the value of the VSWR is infinity. Conversely, when the line is terminated with its characteristic impedance that results in $|\Gamma| = 0$, the value of VSWR is equal to zero.

Example 4.1:

The designer of a RFID system specifies a match between an interrogator and the antenna, resulting in a VSWR better than 1.2 using a 50 Ω coaxial cable as the transmission line. Calculate the maximum reflection coefficient and the allowed range of antenna impedance, assuming it is perfectly resistive.

© 2011 by Taylor and Francis Group, LLC

Solution:

The relationship between VSWR and the reflection coefficient is given by equation (4.4). Algebraic manipulation of this equation yields $|\Gamma| = 0.1$. This is the maximum value allowed for the reflection coefficient.

The relationship between the reflection coefficient and the impedance of the load is given by equation (4.2). When solving for the value of Z_L using this equation, it is necessary to consider the two signs associated with the previous result of $|\Gamma| = 0.1$ as the impedance of the load can exceed or be below the impedance of the line.

$\Gamma = 0.1$ results in $Z_L = 61\ \Omega$, while $\Gamma = -0.1$ results in $Z_L = 41\ \Omega$. Therefore, an antenna impedance ranging from 41 Ω to 61 Ω will result in a VSWR better than 1.2.

Note than the range of allowed load impedances is not symmetric referred to the impedance of the line (Z_o). There is more tolerance for values above Z_o than for values below Z_o.

A transmission line that is not perfectly matched (i.e., a VSWR value higher than 1) reduces the amount of power from the interrogator that reaches the antenna. More importantly, however, is the fact that a fraction of the power that remains in the transmission line can break down the dielectric of the line or increase its temperature due to the power dissipated. Therefore, it is critical to achieve the best possible matching.

Antenna analyzers are a very versatile and useful tool at the time of designing antennas and matching them to their transmission lines. Figure 4.1 shows an image of a low-cost antenna analyzer. The configuration of this analyzer is done through software, and the results are displayed and stored in a personal computer.



FIGURE 4.1
Antenna analyzer from Array Solutions. The control of the unit and the display of results are done by software.

© 2011 by Taylor and Francis Group, LLC

This unit shown in Figure 4.1 allows the measurement of the complex impedance of a transmission line or an antenna, the measurement of reflection coefficient, insertion losses, and other parameters of interest. The front panel only contains an ON/OFF switch, two light-emitting diodes (LEDs) that indicate whether the unit is energized and whether the unit is running a test, and a single Bayonet Neill-Concelman (BNC) connector. The back panel contains the power supply connection and a DB9 connector for a serial cable from the control computer to configure the instrument and transmit the results. The user can select the range of frequencies for the sweep-starting frequency, ending frequency, and step-or central frequency and bandwidth. This unit can also act as a fixed radio frequency source by generating a user-selected single frequency signal. The output values are shown graphically on the screen as conventional graphs (parameter versus frequency) or Smith charts. The data can also be stored as a text file for further processing. The graph can display one or more of the following parameters: impedance magnitude, impedance phase, reflection coefficient, return loss, stationary wave ratio, series load circuit, or parallel load circuit. Figure 4.2 shows an example of the output showing the magnitude and phase of a transmission line between 25 MHz and 40 MHz.

Figure 4.2 depicts the magnitude and phase of the impedance measured by the antenna analyzer for a transmission line with an electrical length


Antenna Analyzer - AIM 4170 version 623
File
Functions
Calibrate
Setup
Bands
Utilities
Help
Zmag
Rp,Xp
Theta
5000
100
2500
50
0
-2500
-50
-5000
-100
25.00
30.00
35.00
40.00
FREQ (1.00 MHz/div)
Scan
Rescan
Recycle
Point Data
Limits
Scales
Smith
Comment
Halt
Quit

Min SWR = 84.757 @ 30.300 MHz
Resonant freq: 33.0864

AVG= 4

Freq = 33.074
Freq Step = 0.100
Zo = 50.000

SWR = 88.847
Zmag = 4376.980
Theta = 2.716

Refl Coef = 0.978
% refl power = 95.6

Equivalent Circuit:
Rs = 4372.064
Xs = 207.390
Ls = 0.998 uH

Rp = 4381.901
Xp = 92376.245
Lp = 444.526 uH

FILES:
calibration 1.acal
aim_623_default.cfg

Mar 4, 08 16:14:48

FIGURE 4.2
Frequency behavior of a transmission line terminated with a short circuit for frequencies around a quarter wavelength. This display shows the magnitude and the phase of the impedance at the near end.

© 2011 by Taylor and Francis Group, LLC

equal to one-quarter of the wavelength, terminated in a short circuit. Due to the impedance transformations at this specific electrical length, the theoretical value of the transformed impedance seen at the near end of the line is infinity. In practice, the losses of the line make the impedance have a large, yet finite, value. The output also displays other values described earlier in this section, such as the reflection coefficient and the VSWR, among others. Similar results could also be obtained using other commercially available antenna analyzers.

When designing the antenna, it is also necessary to take into consideration the write range of transponders that is about 70% of their read range. This is due to the higher amount of power needed to rewrite a transponder compared with just reading it. The orientation of the antenna with respect to the transponder is also a factor in determining the maximum read range in a given application. As shown in Figure 4.3, the field generated by the coil antenna does not have the same strength in all the spatial directions, but instead it has regions of maximum values alternating with regions of minimal strength.

An additional parameter that may limit the maximum read range of a system is the presence of metal objects in the vicinity of the antenna. Metal objects close to the antenna have the effect of detuning it, and therefore it loses its efficiency at the desired frequency. As the size of the antenna increases, the minimum required separation distance between the antenna and the metal objects also increases. For antennas operating in the HF frequency range, the minimum distance between antenna and metal has to be greater than 10 cm.



FIGURE 4.3
The radiation diagram for the loop antenna in the interrogator shows areas of maximum and minimum field strength.

© 2011 by Taylor and Francis Group, LLC

Even at 30 cm of separation, there is a considerable decrease in the reading range. When the distance between antenna and metal object reaches 50 cm, there is no measurable difference. Similarly, the presence of other antennas in the vicinity also affects the overall performance of the system.

Antennas can be built using any conductive material. However, they are normally built using copper or aluminum. The type of material used for the antenna and the dimensions of the tube or strip lines depend on the desired mechanical parameters of the antenna as well as the maximum inductance that must be matched to the interrogator. In addition to the conductors, the matching process requires the use of capacitors and resistors. These must be rated for the high voltages that may arise in resonant antennas as well as for the power that they must dissipate. Typical power values for these resistors range from 2 W to 50 W.

The dimensions of the antenna have an effect on the read distance between interrogators and transponders. The strength of the magnetic field for an electrically small-loop antenna is

$$B_z = \frac{\mu_0 I N a^2}{2\,(a^2 + r^2)^{3/2}} \quad (Weber / m^2) \tag{4.5}$$

with a being the radius of the loop and r being the radial distance from the center of the loop. To study the effects of the antenna radius, the rest of the parameters in equation (4.5) can be considered constant. Assuming that all antennas have the same amount of current and also the same number of turns, the only parameter that changes is the radius of the loop. Figure 4.4 depicts the values of magnetic fields for coils with three different radii (0.2 m, 0.4 m, and 0.8 m). Because the graph is only intended to highlight the dependence of the field with the distance from the center of the coil, it uses arbitrary units for the strength of the field depicted in the vertical axis.

It is interesting to note that, although larger coils produce stronger fields, this only happens after a certain distance threshold has been reached. In particular, for read distances closer to the antenna, the stronger fields are produced by the coils with the smallest radius. Antennas with smaller radii produce stronger fields in the vicinity of the antenna, but these fields decrease faster for longer distances. Therefore, the design of the antenna must consider the range of distances between transponders and the interrogator when selecting the size of the loop.

The resonant frequency of an antenna (ω_o or f_o) is

$$\begin{gathered} \omega_o = \sqrt{\frac{1}{LC}} \quad or \\ f_o = \frac{1}{2\pi\sqrt{LC}} \end{gathered} \tag{4.6}$$

© 2011 by Taylor and Francis Group, LLC



FIGURE 4.4
Strength of the magnetic field as a function of the distance from the coil for loop antennas of different diameters.

An antenna will reach its resonant frequency when its inductive impedance is equal to its capacitive impedance. The loop antenna has an inherently inductive behavior. Therefore, it needs an external capacitor to provide the capacitive impedance required for resonance. The value of this external capacitor can be calculated using equation (4.6). It is important to note that the capacitance and inductance of the antenna are inversely related. A problem may arise if the inductance of the antenna increases to a point that may make it difficult to use a capacitor of suitable value. For example, a loop antenna with an inductance of 5 μH operating in the HF range requires a matching capacitor of 27 pF. For these small capacitance values, the parasitic capacitances that have not been taken into account when modeling the antenna may contribute significantly to the overall capacitance and therefore modify its resonant frequency. It is then important for antennas to be designed with lower inductive values. This may require one to use, for example, low-resistance conductive tube instead of wire at the expense of increasing its physical dimensions.

The inductance of the antenna made with copper tube, shown in Figure 4.5, can be estimated as

$$L(\mu H) = 0.008\ a\left[\ln\left(0.707\,\frac{a}{d}\right) + 0.379\right] \tag{4.7}$$

where

L = the estimated value of inductance

d = the diameter of the tube in cm

© 2011 by Taylor and Francis Group, LLC



FIGURE 4.5
Basic structure of a loop antenna made with copper tube.

a = the length of the side of the antenna from center to center (as shown in Figure 4.5)

Example 4.2:

An interrogator operating at HF uses a loop antenna made of copper tube with a diameter of 2 cm, with a rectangular shape of 60 cm × 60 cm. Estimate the value of the inductance for the antenna. Estimate also the value of the capacitor required to tune the antenna for resonance.

Solution:

Using equation (4.7) with $d = 2$ and $a = 59$ yields $L = 1.6$ μH. This value of inductance can now be used in equation (4.6) to calculate the estimated value of capacitance. The estimated value of capacitance is 86 pF.

The previous equations provide an estimated value of antenna inductance. After the antenna has been built, its inductance must be measured in order to choose the correct value for the tuning capacitor. This can be done with an impedance analyzer that allows the selection of the measurement frequency. However, impedance analyzers are expensive and may not be available in most cases. In this case, a low-cost LCR (inductance [L], capacitance [C], and resistance [R]) meter that operates at the frequency of 1 kHz can give a reasonable approximation of the antenna inductance. The antenna analyzer shown in Figure 4.1 is another low-cost alternative for measuring

© 2011 by Taylor and Francis Group, LLC

the inductance of the antenna and the resonant frequency of the antenna-capacitor system.

The last parameter that needs to be calculated and measured when designing the antenna is its Q factor. The Q factor is a measure the frequency selectivity of an antenna. The Q factor is related to the range of frequencies above and below its resonant frequency that the antenna will be able to transmit or receive with losses below 3 dB. The Q factor can be estimated as

$$Q = \frac{f_r}{BW_{-3dB}} \tag{4.8}$$

where Q is the quality factor of the antenna, f_r is its resonant frequency, and $BW_{-3\text{dB}}$ is the bandwidth of the antenna at 3dB of attenuation.

A high Q factor indicates an antenna that is very narrow in frequency, that is, highly selective. This may be good in order to reject interfering signals that otherwise would be detected by the antenna. However, the RFID signal has a certain bandwidth. If the antenna is too selective, it may distort the components of the transmitted signal that fall outside the selectivity of the antenna, as shown in Figure 4.6. A good experimental compromise is to choose a Q factor of around 20.

If the Q factor of the system made of the antenna and capacitor is higher than 20, it needs to be brought down by using a dampening resistor in parallel with the antenna in order to widen its bandwidth. This technique is shown in Figure 4.7.

The introduction of the dampening resistor produces Ohmic losses in the system, lowering the Q factor. The Q factor is related to the parallel resistance as

$$Q = \frac{R_{par}}{2\pi f L} \tag{4.9}$$

An additional problem arises when using equation (4.9) in order to select the value of the parallel dampening resistor: the value R_{par} in the equation is the combination of the external dampening resistor (R_{damp}) in parallel with the resistance of the antenna at the frequency of interest (R_{ant}). The measurement of the resistance of the antenna at the operating frequency is difficult and requires the use of expensive instrumentation. However, the Q factor for an antenna is relatively easy to measure experimentally with an antenna analyzer or using a radiofrequency signal generator and a spectrum analyzer. Therefore, the resistance of the antenna R_{ant} at the operating frequency can be calculated indirectly by measuring the Q factor of the antenna without an external dampening resistor. Once this value has been found, it is now possible to calculate the required value of the total parallel resistance R_{par} to achieve the desired value of Q. Because R_{par} is the parallel of R_{ant} and the

© 2011 by Taylor and Francis Group, LLC



FIGURE 4.6
Q factor of an antenna and its relationship with the antenna performance. (a) A very low quality factor (Q factor) does not provide adequate selectivity. (b) A very high Q factor may reject components of the transmitted signal.



FIGURE 4.7
Dampening resistor connected in parallel with the antenna. This is used to lower the Q factor to the desired value.

external dampening resistor R_{damp}, it is now possible to estimate the value of this external resistor. Example 4.3 illustrates this procedure.

Example 4.3:

Consider the antenna for the RFID system from Example 4.2. Estimate the value of the external dampening resistor necessary for the system to achieve a Q factor of 20. The initial measurement of the Q factor for the antenna-capacitor system resulted in a value of 55.

© 2011 by Taylor and Francis Group, LLC

Solution:

Using equation (4.9) with a Q factor of 55, an inductance value for the antenna of 1.6 μH, and a frequency of 13.56 MHz results in a resistance equal to 7.5 kΩ. Because the Q factor of 55 was measured without the use of external resistors, the value of resistance obtained is the resistance of the antenna: $R_{ant} = 7.5$ kΩ.

Now, we must calculate the value of the total parallel resistance needed to reduce the Q factor to the desired value of Q. We use again equation (4.9) with the same operational parameters as before, with the exception that the new value for Q results in a resistance equal to $R_{par} = 2.7$ kΩ.

Considering that the total value of the resistance found above is equal to the resistance of the antenna in parallel with the dampening resistor ($R_{par} = R_{ant}$ // R_{damp}), it is now possible to calculate the value of the external dampening resistor. This results in $R_{damp} = 4.2$ kΩ. Because this is not a standard resistor value, the designer should use the next standard value, which is 4.3 kΩ.

Therefore, the addition of 4.3 kΩ results in lowering the Q factor from its initial value of 55 to the desired value of 20. Because the value of inductance used for this calculation could be an estimated value, the design process involves measuring the Q factor with the external dampening resistor of 4.3 kΩ and adjusting its value if necessary to reach a Q factor of 20. Finally, it is also necessary to keep in mind that this external dampening resistor must be sized to dissipate the power transmitted by the interrogator.

4.1.2 Antenna Matching

Matching the impedance of the antenna to the impedance of the transmission line (normally a coaxial cable of 50 Ω) ensures that all the power from the interrogator is transferred to the antenna, and there is no power reflected in the line. In practice, a VSWR of 1.2 or lower is acceptable as the majority of the power is transmitted to the antenna. From the several approaches to match an antenna to its transmission line, the most widely used matching methods for interrogator antennas in RFID systems are gamma matching, T-matching, transformer matching, and capacitance matching.

Gamma matching is a technique based on connecting the two conductors of the coaxial cable that make up the transmission line to the two points in the antenna that exhibit a resistive impedance equal to 50 Ω. The shield of the coaxial cable is normally connected to the point in the antenna that is opposite to the gap used to connect the resonance capacitor and the dampening resistor. The central connector of the coaxial cable is then connected, by means of an additional conductor, to the appropriate point in the antenna as shown in Figure 4.8.

In practice, the point at which the central conductor of the coaxial cable is connected (point A) must be determined by experimentation. The designer of the system connects an antenna analyzer at the far end of the coaxial cable and moves point A until the antenna analyzer reads a VSWR value equal to 1. This indicates that the impedance of the antenna between point A and the connection of the central conductor is equal to 50 Ω. The value of the capacitor used to tune the antenna to the resonance frequency was

© 2011 by Taylor and Francis Group, LLC



FIGURE 4.8
Connections for gamma matching.

determined using an approximation for the value of the antenna inductance. Therefore, a variable capacitor is initially used in order to tune the antenna to its resonant frequency. Once the correct value of capacitance has been determined, it is then possible to substitute the bulkier variable capacitor with a fixed capacitor.

T-matching is similar to gamma matching with the difference being that in T-matching, both the internal and external conductors of the coaxial cable are tapped to two points in the antenna, as shown in Figure 4.9. It is based on the fact that two points of the antenna, equidistant from the center, exhibit a purely resistive impedance.

The two tapping points are located symmetrically with respect to the gap used for connecting the tuning capacitor and the dampening resistor. The

© 2011 by Taylor and Francis Group, LLC



FIGURE 4.9
T-matching.

two tapping points are found by using an antenna analyzer until the VSWR value is equal to 1. Higher values of the Q factor results in the two matching points being closer together.

Transformer matching has the advantage that it electrically isolates the antenna from the interrogator, thus breaking the Ohmic continuity between these two parts of the system. This is useful when the RFID system is affected by noise as it breaks any ground loop that may exist. Figure 4.10 shows the electric diagram of transformer matching. It is important to note that the matching occurs at the gap in the antenna that is used to connect the resonance capacitor and the damping resistor instead of their opposite point, as it happens with gamma and T-matching.

Transformer matching requires the design of two elements: the matching transformer and a balum (balanced–unbalanced) transformer. The design of the matching transformer requires one to size the number of turns of the primary (*N*) that is connected to the transmission line and the secondary (*M*)

© 2011 by Taylor and Francis Group, LLC



FIGURE 4.10
Transformer matching. Notice how the matching point is the same point at which the capacitor and resistor are connected.

that is connected to the antenna. The ratio of turns can be found using the following:

$$\left(\frac{N}{M}\right)^2 = \frac{Z_o R_{par}}{(2\pi f L)^2} \tag{4.10}$$

where (N/M) is the primary to secondary ratio of turns, Z_o is the impedance of the transmission line, R_{par} is the parallel resistance of the antenna and the dampening resistor, and L is the inductance of the antenna.

Example 4.4:

Using the values from the previous examples in this chapter, calculate the number of turns for the primary and secondary of the matching transformer. Assume a characteristic impedance of 50 Ω.

Solution:

Using equation (4.10) with $R_{par} = 2.7$ kΩ, L = 1.6 μH, and f = 13.56 MHz, the ratio of turns is equal to 2.7. Using, for example, M = 3 results in N = 8 windings.

The balum transformer is used to connect unbalanced transmission lines such as a coaxial cable to balanced antennas such as the loop antenna. Although they can be connected directly, as with the gamma matching, the common mode currents that appear in the antenna and line due to the unbalance may cause excessive noise and disturb the circuits. In this case, the connection of a balum transformer between line and transformer

© 2011 by Taylor and Francis Group, LLC



FIGURE 4.11
A balum is used to connect unbalanced transmission lines to balanced antennas.

solves these problems. The structure of a balum transformer is shown in Figure 4.11.

Both the matching transformer and the balum transformer are normally made with a toroid ferrite core. The balum transformer can be tested by connecting a 50 Ω load to the balanced side and measuring the VSWR through a coaxial cable connected to the unbalanced side. The VSWR should be close to 1.0.

Capacitance matching attempts to match the antenna and its transmission line by adding to external capacitors between the resonance capacitor and the dampening resistor, as shown in Figure 4.12.

Because of the stray capacitances inherent to the system, it is very difficult to predict the adequate values for the two matching capacitors, which requires extensive experimentation. Furthermore, for larger antennas, the values of the two matching capacitors tend to be very small, making the matching process very sensitive to stray capacitances. In Figure 4.12, the series combination of C_1 and C_2 must be equal to the capacitance value required to tune the antenna at the correct frequency.

The value of the matching capacitor C_{m1} can be estimated as

$$C_2 = C_{tuning}\sqrt{\frac{R_{par}}{R_{out}}} \tag{4.11}$$

where C is the total capacitance required for tuning the antenna, R_{par} is the equivalent value of the AC resistance of the antenna in parallel with the damping resistor, and R_{out} is the desired matching impedance, typically 50 Ω. The value of C_1 can be calculated through the series capacitance of C_1 and C_2.

© 2011 by Taylor and Francis Group, LLC



FIGURE 4.12
Capacitance matching.

Example 4.5:

The antenna used in Example 4.4 must be matched to a 50 Ω transmission line using capacitance matching. Calculate the values of the two matching capacitors required.

Solution:

The required tuning capacitor has a value of 86 pF, and the parallel resistance has a value of 2.7 kΩ. The required value for R_{out} is 50 Ω. Using equation (4.11) yields a value of C_2 = 632 pF. The equivalent series capacitance is 86 pF, allowing one to calculate the value of C_1 equal to 99 pF.

© 2011 by Taylor and Francis Group, LLC



FIGURE 4.13
Balanced capacitance matching.

Some antennas require a matched capacitance so the capacitance seen by both conductors of the coaxial cable is the same. This can be achieved by using the structure shown in Figure 4.13. In this structure, the value of C_1 is doubled and added to each side of C_2.

Example 4.6:

Using the results of Example 4.5, calculate the capacitor values required for balanced matched capacitance.

© 2011 by Taylor and Francis Group, LLC

Solution:

From Example 4.5: $C_1 = 99$ pF and $C_2 = 632$ pF. To achieve balanced capacitance, $C_{1A} = C_{1B} = 198$ pF. C_2 remains at the same value of 632 pF.

4.1.3 Multiple Antenna Systems

It is not uncommon for several antennas to be located in close proximity. This may be due to different interrogators being close to each other or for multiple antennas to be connected to a single interrogator. When designed correctly, the mutual coupling between the antennas can enhance the performance of the overall system. However, a careless positioning of the multiple antennas may result in their mutual coupling, severely degrading their performance.

When several single-antenna interrogators coexist in close vicinity to each other, it is necessary to minimize their interaction with each other. The coupling between these antennas depends on the distance between them as well as their relative angles. Although the radiation pattern of a single antenna is well known and easy to predict, this radiation pattern becomes distorted due to the coupling. The best approach for locating the optimal placement of two or more antennas is by using an antenna analyzer in order to find the minimum of radiation by measuring the voltage generated in the nearby antenna.

A technique sometimes used to enhance the radiation pattern of the antenna in a single interrogator is to place another matched but unconnected antenna, opposite to the antenna connected to the interrogator. This connected antenna is a *driven antenna*, while the unconnected antenna is a *reflective antenna*. The combination of both antennas directs the energy from the driven antenna to a narrower area. Once again, an antenna analyzer should be used in order to determine the best arrangement between the two antennas.

Instead of leaving the second antenna unconnected, making it a reflective antenna, it is also possible to drive it with the signal from the interrogator by means of a splitter. In this case, the output of the interrogator is connected to the input of the splitter, and each output from the splitter is connected to a matched antenna. Splitters also offer the possibility to have the two output signals in-phase or out-of-phase. Splitters introduce losses, but when the two signals are connected in-phase, the reading distance between interrogator and transponders increases more than the reading distance with just one antenna without the losses from the splitter. The increase in the reading distance is at the cost of reducing the radiation pattern in the directions perpendicular to the arrangement of antennas. Therefore, this technique is only useful when the transponders are located only in known areas. When the signals fed to the two antennas are out-of-phase, the radiation pattern changes significantly, resulting in a pattern opposed to when the two signals are in phase. This gives the designer of the system the ability to configure the radiation pattern depending on the needs of the system.

Other techniques based on systems with multiple antennas are directed toward specific applications. In one of them, two identical antennas located

© 2011 by Taylor and Francis Group, LLC

in a crossed arrangement are connected to the output of a splitter but use different lengths of transmission line. In particular, if the different between lengths is a quarter of a wavelength, the two fields are shifted in 90°. This produces a field that changes the direction of its maximum, giving the appearance of a rotating field. Some other commercial antennas have an additional input that allows connecting an out-of-phase signal from a complementary antenna in order to maximize field strength in a single direction.

4.2 Auxiliary Elements for LF and HF Interrogator Antennas

4.2.1 Antenna-Tuning Indicators

Tuning indicators are used to facilitate the process of antenna tuning without the need to use antenna analyzers or other instrumentation. They present the advantage of being a self-contained system that has been optimized for specific interrogators and antennas. On the other hand, because of their specific nature, they can only be used with a limited number of antennas.

For example, Texas Instruments manufactures the RI-ACC-ATI2 antenna-tuning indicator used to help tune their LF antennas. The tuning indicator is connected to the interrogator and indicates to the user if the inductance or capacitance in the interrogator needs to be increased or decreased until the optimal value has been achieved. Some interrogators have a tuning capacitor, while some others have a tuning inductance that can be adjusted for optimal performance.

4.2.2 Antenna Multiplexers

Antenna multiplexers are used to connect multiple antennas to a single interrogator. This can be done to take advantage of the multiple coupling between antennas or when it is necessary to read data from multiple interrogators located at distant points not covered by a single antenna. The majority of multiplexers in the market work with two, four, or eight antennas. The multiplexer is connected between the radiofrequency output of the interrogator and the antennas, as shown in Figure 4.14.

It is not necessary for all the antennas connected to the multiplexer to have the same inductance. This presents the advantage of being able to choose the antenna most adequate for a specific application without having to physically connect and disconnect them from the interrogator. However, because most multiplexers do not include a tuning feature, each antenna must be tuned to the appropriate resonance frequency with their own individual tuning method described in Sections 2.2 and 2.3.

Antenna multiplexers are normally created by the manufacturers of interrogators, although there are some third-party companies that also

© 2011 by Taylor and Francis Group, LLC



FIGURE 4.14
Multiplexer for connecting multiple antennas to a single interrogator.

manufacture them. For example, Skyetek manufactures multiplexers for the HF frequency range that can control four or eight antennas, having insertion losses lower than 0.7 dB and isolation between adjacent channels better than 45 dB.

4.2.3 Preamplifiers

Increasing the reading distance between interrogators and transponders requires a double approach. First, the electromagnetic field transmitted by the interrogator has to increase in order to generate enough power to turn on the distant transponders. This is relatively easy to do and is mainly limited by standards and regulations on maximum power and maximum allowed field strength. Second, reading distant transponders requires the interrogator to detect signals closer to the noise level. The increase in the detection sensitivity can be achieved with the use of preamplifiers, as shown in Figure 4.15.

The factor that limits the read range in RFID is ultimately the inherent noise that accompanies the signal received by the interrogator. A correctly designed preamplifier is able to increase the level of the signal without degrading the signal-to-noise ratio. The design of the main preamplifier is normally based on a low pass filter in order to reject the frequency generated by the field and

© 2011 by Taylor and Francis Group, LLC



FIGURE 4.15
Preamplifier for extending reading distance.

allow the transmission of data. This stage is followed by an AC amplifier that increases the signal levels to the point that can be easily understood by the interrogator. The design of the preamplifier must consider the trade-offs between increasing the reading distance and the settling time required by the system. This means that the interrogator will be optimized for reading distance or for settling time, but cannot be optimized for both parameters.

Even when using preamplifiers, it is necessary to minimize the other potential sources of noise in the system. These can be the use of bad connectors between the interrogator and the antenna, improper installation of the transmission line between interrogator and antenna, an antenna that is not tuned correctly, the existence of interfering signals from nearby electronic equipment, and noise emanating from the power supply lines, among others. The designer of the RFID system should ensure that all these sources are minimized or at least known, and their values measured.

4.3 Antennas for UHF Interrogators

4.3.1 Design of Antennas for UHF Interrogators

Given the wavelength of signals in the UHF range, it is possible to design antennas for interrogators that operate in the far-field region as interrogators do not have the same space limitations of transponders. The resulting radiation pattern of two dipoles located at a short distance from each other can be easily modified by carefully arranging the distance between them as well as the phase shift of the signals that they radiate. A further modification of the radiation pattern comes from placing a large metal surface at a

© 2011 by Taylor and Francis Group, LLC

specific distance from the two dipoles. The metal surface acts like a shield that effectively removes half of the radiation pattern. Furthermore, if the distance between the antennas and the metal shield is one-fourth of the signal wavelength, the phase shift due to the distance between antenna and shield, combined with the phase shift created by the reflection in the metal shield, places the reflected signals in phase with the signals originated by the antenna. This, in turn, has the effect of doubling the power transmitted in the area away from the metal shield, as shown in Figure 4.16. It is necessary to remember that the increase of power in that specific direction comes at the expense of having no power in the area behind the metal shield, also known as a *passive reflector*. This structure is commonly used in *patch* or *flat* antennas.

An additional advantage of working in the far-field region is the possibility to take advantage of polarization. Polarized signals have their electric fields oscillating in a known and constant direction in space. This way, the signal recovered by the receiving antenna has a marked dependence on the geometrical relationship between the direction of the electric field and the direction of the antenna. Therefore, the energy recovered by the antenna in the interrogator ranges from a maximal value to zero depending on the relative orientation between the antennas in the interrogator and transponder. Using polarized signals allows discriminating between transponders. When the discrimination between transponders is



FIGURE 4.16
Metal shield increases effective radiated power in one specific direction.

© 2011 by Taylor and Francis Group, LLC



FIGURE 4.17
(a) Basic structure of a patch antenna. (b) Parallel equivalent circuit for a patch antenna.

not required, the use of dual dipole antennas in the transponders ensures that the interrogator will receive an adequate amount of energy.

The design of an antenna for the UHF RFID band represents an increased engineering challenge compared to designing it for the HF or LF bands because of the higher bandwidth needed for signals in the UHF band. It also becomes more difficult to maximize the performance of the antenna over the wider frequency range allocated for RFID systems in the UHF band. For this reason, while most of the HF and LF antennas follow the same basic design, engineers have developed several approaches to the design of UHF antennas for interrogators based on different performance parameters. This is especially critical for handheld applications in which the limited size of the antenna degrades its performance.

The patch antenna shown in Figure 4.17(a) is one of the most commonly used antennas for UHF interrogators. In its basic form, it consists of a metal patch of approximately one-half of a wavelength long and mounted over a ground plane. Figure 4.17(b) shows its equivalent electrical model.

Typical values for the equivalent circuit shown in Figure 4.17(b) are around 150 Ω for the radiation resistance of the antenna, between 9 and 10 pF for its capacitance, and from 2 to 4 nH for its inductance. The matching of the transmission line with a 50 Ω characteristic impedance to the relative high radiation resistance of the antenna is done by changing the location at which the transmission line feeds into the metal patch away from its center. The bandwidth of the patch antenna is a function of its dimensions and the separation between the metal patch and the ground plane. The type of dielectric used between the planes is also important, as dielectrics other than air will increase its equivalent capacitance.

© 2011 by Taylor and Francis Group, LLC

The patch antenna, by its very own design of using a ground reference as part of the antenna, is an unbalanced antenna. Because unbalanced antennas do not operate well when they are close to dielectric materials, and the human body can be essentially considered as a dielectric material at UHF frequencies, patch antennas are not the best choice for handheld interrogators. Furthermore, the size and weight limitations required by mobile and handheld interrogators further limit the use of patch antennas in these applications. A better solution for handheld and mobile interrogators are balanced antennas, that is, antennas with symmetric and opposed currents as shown in Figure 4.18.

When the antenna is fed using an unbalanced transmission line, such as a coaxial cable, it is necessary to use a balum transformer to match the unbalanced line to the balanced antenna. The basic theory behind this balum is the same as was described for HF and LF antennas. Although the structure shown in Figure 4.18 is technically feasible, an additional problem may arise due to the size required by half of a wavelength, especially for handheld interrogators. At the frequency of 915 MHz, the length of half of a wavelength is equal to 16 cm. While this is a very reasonable distance for a stationary antenna, it may be excessively large for applications involving handheld readers. In this case, it is possible to bend the dipoles in a similar way as is done for the antennas in transponders, as shown in Figure 4.19.

The reduction in size for the bent dipoles comes at the expense of degrading the electrical specifications of the antenna. In particular, its radiation resistance decreases and therefore the bandwidth of the bent dipole structure also decreases compared to the bandwidth of the regular dipole.

A different type of antenna used in UHF interrogators (either stationary or mobile) is based on the Yagi-Uda antenna. This structure, shown in Figure 4.20, consists of a driven element and two or more parasitic elements: one reflector and one or more directors. The parasitic elements direct the majority of the



FIGURE 4.18
Balanced half-wavelength antenna.

© 2011 by Taylor and Francis Group, LLC


Balum
Unbalanced transmission line (coaxial cable)
~ 6 cm
~ 6 cm

FIGURE 4.19
Bent dipole for a UHF interrogator antenna.


0.25 λ
0.25 λ
0.25 λ
0.55 λ
0.5 λ
0.45 λ
0.35 λ
Reflector
Driven element
Directors

FIGURE 4.20
Yagi-Uda antenna.

energy radiated by the antenna toward the director. Therefore, this structure helps to minimize the interaction of the radiated field with a person who may be holding an antenna for handheld interrogators. Moreover, because this is a balanced antenna, this interaction between the energy radiated by the antenna and that radiated by the human body is further minimized.

In its original form, however, Yagi-Uda antennas can still be considered too large to use with handheld interrogators. In this case, it is possible to bend the dipole and longer elements, as described above. The existence of the parasitic elements will provide additional gain compared to the single dipole.

© 2011 by Taylor and Francis Group, LLC

4.3.2 Transmission Lines and Connectors for UHF Interrogators

Contrary to LF and HF systems, the coaxial cables and connectors typically used in UHF RFID systems have the potential to extremely degrade the signal they transmit. The main reason for this problem is the skin depth. *Skin depth* describes the effect that the current flowing through a conductor flows through a portion of its inner surface. Equation (4.12) shows that the skin depth (δ) is inversely proportional to the frequency of the signal:

$$\delta = \sqrt{\frac{1}{\pi \mu \sigma f}} \tag{4.12}$$

where δ is the skin depth, μ the magnetic permeability of the conductor, σ its conductivity, and f the frequency of the current flowing through the conductor.

Therefore, an increase in the signal frequency results in a smaller portion of the conductor being used to transmit the signal. For a typical conductor made of copper, the skin depth for an LF signal is 0.2 mm, the skin depth for an HF signal is 55 μm, and for a UHF signal it is 2 μm. Consider a copper conductor with a radius of 0.2 mm. At LF frequencies and below, the current will flow through all the conductor area. When the frequency increases to 13.56 MHz, only the first 55 μm are actually available as a path for the current. The effective area has been reduced to a half of the area available for an LF signal. Because the conductivity of the conductor depends on its area, the conductivity of this conductor at HF is about half of its conductivity at LF. The situation changes more dramatically at UHF frequencies, as the skin depth of 2 μm means that current can flow only through the outer 1 percent of the conductor. With this, the conductivity of the copper wire for UHF signals has been reduced in a factor of 62 compared to the conductivity at LF. This strong decrease in conductivity introduces considerable losses that may render the system unusable. Figure 4.21 further illustrates this situation.



Area at LF = A Area at HF = 0.47 A Area at UHF = 0.016 A

FIGURE 4.21
Skin effect at (a) low frequency (LF), (b) high frequency (HF), and (c) ultra-high frequency (UHF). Current flows through the shaded areas.

© 2011 by Taylor and Francis Group, LLC

With these considerations, the layout of the transmission line used to connect the UHF interrogator to its antenna becomes critical. The most effective approach to improving the performance of the system is to minimize the length of transmission line between the output of the interrogator and its antenna. It can also be possible to use transmission lines with larger diameter wires; however, the slight increase in effective area does not compensate for the additional cost of these lines or their increased rigidity. It is also important to choose a coaxial cable that has a continuous outer conductor instead of a multistrand ribbon for its shield.

The use of adequate connectors is also critical for RFID systems working in the UHF band. The BNC connectors that are commonly used in the LF and HF bands could be used without significant performance degradation in UHF applications. However, other types of connectors, specifically designed for higher frequencies, produce more reliable results. TNC connectors were conceived as a threaded version of the BNC connectors, being suitable for use up to 10 GHz. Type-N connectors are commonly used in high-frequency applications as they are suitable to carry signals up to 10 GHz and even 18 GHz with their recent enhancements. They are also mechanically robust and well suited for outdoor use. Figure 4.22 shows a male type-N connector, while Figure 4.23 shows a female type-N connector.

Because type-N connectors are available in 50 Ω and 75 Ω versions and the connectors are typically not labeled, it is very easy to confuse them, originating an impedance mismatch. Furthermore, the dimensions of their inner conductors are slightly different, so mismatching the connectors may



FIGURE 4.22
Male type-N connector.

© 2011 by Taylor and Francis Group, LLC



FIGURE 4.23
Female type N-connector.



FIGURE 4.24
Male and female subminiature version A (SMA) connectors.

also damage them physically. Subminiature version A (SMA) connectors, shown in Figure 4.24, are perhaps the most widely used microwave connector and are becoming more used in RFID systems. SMA connectors can transfer signals up to 18 GHz and have a 50 Ω impedance. The main problem using this type of connector is that they have not been designed to be connected and disconnected constantly, like for example a BNC connector. Even with the best of care, they cannot exceed a few hundred connections and disconnections.

© 2011 by Taylor and Francis Group, LLC

4.4 Commercial Antennas for RFID Interrogators

4.4.1 Antennas for RFID Interrogators

Antennas for interrogators are available from the same manufacturers that make transponders and interrogators, as well as third-party vendors that build interrogator antennas for specific applications. Some manufacturers offer systems in which the antenna and the interrogator are integrated together, as is the case with handheld RFID systems.

Texas Instruments manufactures two types of antennas for the LF band under the generic name of Series 2000. These antennas are divided into *gate antennas* and *stick antennas*. Table 4.1 shows the specifications of these antennas.

As shown on Table 4.1, gate antennas mainly differ in their size. Designers of RFID systems choose the size of the antennas based on the required application, depending on the area that they have to cover. The stick antennas S01C and S02C are identical, with the only difference being the length of their coaxial cable: 1 meter for S01C and 3 meters for S02C. Choosing between gate antennas and stick antennas is also application dependent. In general, gate antennas offer a larger read zone and more read distance, while stick antennas offer a more focused zone. Therefore, if for example it is necessary to distinguish between different transponders, stick antennas will be more useful due to their more defined radiation field.

Some manufacturers have designed HF antennas that are shaped in a particular way for a specific application. For example, Unified Transponder Concepts, Inc., produces several antennas specific for laundry systems. One of them is shaped like a garment portal to be used with standard garment racks for clothes with an embedded RFID transponder. Another example from the same manufacturer is an antenna in the shape of a chute, used for the detection and control of deposited items tagged with the appropriate transponders. In addition, they also manufacture the more traditional panel and handheld antennas. The power levels accepted by these antennas ranges from 1 W to 4 W, and they all exhibit a resistance of 50 Ω at 13.56 MHz.

TABLE 4.1

Specifications for Some Texas Instruments Series 2000 Antennas Operating in the LF Band (134.2 kHz)

	Model	Inductance	Dimensions	Weight
Gate Antennas	G01E	27 μH	0.7 m x 0.2 m	745 grams
	G02E	27 μH	0.2 m x 0.2 m	425 grams
	G04E	26 μH	1.1 m x 0.52 m	2500 grams
Stick Antennas	S01C	27 μH	0.14 m x 2mm (Ø)	134 grams
	S02C	27 μH	0.14 m x 2 mm(Ø)	185 grams
	P02A	116 μH	0.13 m x 21.3 mm (Ø)	105 grams

© 2011 by Taylor and Francis Group, LLC

TABLE 4.2

Specifications for UHF Antennas Manufactured by NetHome

	Dimensions (mm)	Gain	Polarization	Connector
NT-900-SPP	90 x 90 x 25	0 dBi	Right / Left hand	SMA
NT-900-MPP	120 x 120 x 25	0 dBi	Circular	SMA
NT-900-CP	200 x 200 x 25	6 dBi	Right / Left had	SMA
NT-900-FP	360 x 260 x 25	6 dBi	Circular	TNC

TABLE 4.3

Specifications for MTI Wireless Edge Antennas Operating in the 400 MHz Range

Model	Frequency (MHz)	Dimensions (mm)	Gain	Polarization	Connector
MT182018	430 – 440	305 x 305 x 25	3.5 dBi	Circular LH	N-type Female
MT182016	430 – 437	370 x 370 x 30	9 dBi	Circular LH	N-type Female
MT181033	430 – 440	305 x 305 x 25	3 dBi	Linear	N-type Female
MT182011	405 – 450	370 x 370 x 40	8 dBi	Linear	N-type Female

TABLE 4.4

Specifications for MTI Wireless Edge Antennas Operating in the 865 MHz to 870 MHz Range

Model	Dimensions (mm)	Gain	Polarization	Connector
MT242032	190 x 190 x 30	7 dBi	Circular LH or RH	N-type Female
MT242040	190 x 190 x 30	7.5 dBi	Circular LH or RH	N-type Female
MT242033	540 x 470 x 220	8.5 dBi	Circular LH or RH	N-type Female
MT242034	685 x 626 x 220	8.5 dBi	Circular LH or RH	N-type Female
MT242027	260 x 260 x 30	8.5 dBi	Circular LH or RH	N-type Female
MT242014	305 x 305 x 25	8.5 dBi	Circular LH or RH	N-type Female
MT242017	371 x 371 x 40	10 dBi	Circular LH or RH	N-type Female
MT243017	650 x 320 x 40	11 dBi	Circular LH or RH	N-type Female

There is a larger number of independent manufacturers for antennas operating in the UHF range. For example, the Korean manufacturer NetHom offers flat, patch antennas that operate in the 902 MHz to 928 MHz range and have an input impedance of 50 Ω, as shown in Table 4.2.

Another manufacturer, MTI Wireless Edge Ltd., offers a vast array of standalone antennas for a wide number of frequencies and applications. Table 4.3 shows specifications for their line of antennas in 400 MHz UHF RFID range. All the antennas shown in Table 4.3 have a maximum input power of 6 W and an input impedance of 50 Ω.

The same manufacturer also offers antennas that operate in the 865 MHz to 870 MHz frequency range, have an input impedance of 50 Ω, and have a maximum allowable power of 6 W. Table 4.4 shows the rest of the specifications for these antennas.

© 2011 by Taylor and Francis Group, LLC

TABLE 4.5

Specifications for MTI Wireless Edge Antennas Operating in the 2.4 GHz Range

Model	Dimensions (mm)	Gain	Polarization	Connector
MT343024	190 x 190 x 30	13 dBi	Circular LH or RH	N-type Female
MT344034	305 x 305 x 15	15.5 dBi	Circular LH or RH	N-type Female
MT345014	371 x 371 x 40	19 dBi	Circular LH or RH	N-type Female



FIGURE 4.25
Schematic for the tuning board in the Series 2000 Reader from Texas Instruments.

It is also possible to purchase antennas similar to those shown in Table 4.4 dual polarized, that is, being both right-hand (RH) and left-hand (LH) circularly polarized. In this case, the antennas have two N-type female connectors, one for each polarization. Other models for antennas in the same frequency range of 865–870 MHz are available for linear polarization. In addition, this manufacturer also offers antennas for the 902–928 MHz and 950–956 MHz frequency ranges with dimensions and gains similar to those shown in Table 4.4 for either single or dual polarization.

Table 4.5 shows the specifications for a sample of antennas from MTI Wireless Edge Ltd. operating in the 2.4 GHz to 2.5 GHz frequency band and having an input impedance of 50 Ω.

Once again, antennas with similar dimensions and gains for the 2.4 GHz range are also available for single- and dual-linear polarizations.

4.4.2 Tuning Boards for Interrogator Antennas

Tuning boards are the circuits that are used to provide the high resonance needed to increase the strength of the field generated by the antennas in the system. Tuning boards can be found as stand-alone systems or as part of the interrogators. This subsection describes the Antenna Tuning Board that is part of the 2000 Series Reader System manufactured by Texas Instruments as an example of this type of circuits. As shown in Figure 4.25, the tuning board consists of a series of capacitors that are connected in parallel with the inductance of the antenna by means of several switches

© 2011 by Taylor and Francis Group, LLC

TABLE 4.6

Resulting Capacitance for Different Configurations of Switches in Tuning Board

Switch	Capacitance (nF)	Connection
SW1	33	C_2 ON
SW2	16.5	C_1, C_2 in series
SW3	33	C_1 ON
SW4	33	C_4 ON
SW5	16.5	C_3, C_4 in series
SW7	15	C_6 ON
SW8	7.5	C_5, C_6 in series
SW9	15	C_5 ON
SW10	10	C_8 ON
SW11	5	C_7, C_8 in series

(SW1–SW11) in the same board, thus allowing one to match a wide range of antenna inductances.

Table 4.6 shows the capacitive effect of each one of the switches in the tuning module. It can be seen that the lowest capacitance occurs when only SW11 is closed, resulting in a total capacitance of 5 nF. The highest capacitance that can be achieved with the board is equal to 139 nF, which occurs when SW1, SW3, SW4, SW7, SW9, and SW10 are closed.

The initial, coarse tuning adjustment is done with the capacitors, while the fine tuning due to the steps in the overall capacitance is done with the tuning coil located at the end of the tuning board. This process is repeated while monitoring the strength of the field generated by the antenna until it reaches a maximum.

© 2011 by Taylor and Francis Group, LLC

5

Interrogators

CONTENTS

5.1 Transmitter and Receiver 120
5.2 Modulator and Demodulator 126
  5.2.1 Amplitude-Shift Keying (ASK) Modulation 126
  5.2.2 Frequency-Shift Keying (FSK) Modulation 127
  5.2.3 Phase-Shift Keying (PSK) Modulation 129
5.3 Long-Range Considerations 133
5.4 Interrogator Synchronization 134
  5.4.1 No Synchronization at the Interrogator Level 134
  5.4.2 Wireless Synchronization 135
  5.4.3 Wired Synchronization 137
  5.4.4 Combined Wired–Wireless Synchronization 137
  5.4.5 Master–Slave Synchronization 137
  5.4.6 Carrier Phase Synchronization 139
5.5 Structure of Commercially Available Interrogators 140
  5.5.1 Interrogators for LF RFID Systems 140
    5.5.1.1 Radiofrequency Modules 141
    5.5.1.2 Control Module 144
  5.5.2 Interrogators for HF RFID Systems 149
  5.5.3 Single-Chip Interrogators 150

Interrogators have two basic functions: to generate and transmit the radiofrequency signal used to energize the transponders and to receive and decode the backscattered signal generated by the transponders. In addition, some interrogators may also transmit specific commands to the transponders. The interrogator also handles the bidirectional communication with a host computer used to process the information from the transponders and to issue commands to the interrogator. Figure 5.1 shows a basic block diagram of a generic interrogator with its basic constituent blocks.

If the transponder is able to accept commands from the interrogator, the radiofrequency signal generated by the interrogator has to be further modulated with the specific code; otherwise, the interrogator will only transmit the radiofrequency carrier. In either case, the radiofrequency signal is then amplified to specific power levels and passed through the tuning circuits before reaching the antenna. The antenna is also used to detect the backscatter signal generated by the transponder, which, after being filtered, is

© 2011 by Taylor and Francis Group, LLC



FIGURE 5.1
Basic block diagram of a generic interrogator.

then amplified and demodulated if necessary. The resulting signal is then sent to a microcontroller that will transmit it to the host computer using the appropriate communications protocol. The microcontroller also manages the timing for the interrogator to act as a transmitter or a receiver.

This chapter starts describing the transmitter and receiver sections in an interrogator. It continues by studying the most commonly used digital modulations in RFID systems. Afterwards, the chapter discusses issues related to extending the read range between transponder and interrogator as well as the requirements for interrogator synchronization when two or more interrogators coexist within the same general area. The last section in this chapter provides a description of the structure in different commercial interrogators.

5.1 Transmitter and Receiver

The basic structure of the transmitter section in the RFID interrogator contains an oscillator operating at the frequency of interest, a voltage or power amplifier, and the tuning circuits to match the impedance of the transmitter to the characteristics of the antenna. In addition to providing the radiofrequency signal to energize the transponders, some interrogators also transmit commands to the transponder. They can also be able to write new data into

© 2011 by Taylor and Francis Group, LLC

the transponder's memory. Transmitters in a RFID system must generate an accurate radiofrequency signal while minimizing the spurious radiation that they produce. *Spurious radiation*, common to all transmitters, is the amount of energy that falls outside the desired transmission band. In addition, they have to be as efficient as possible in order to reduce the amount of energy dissipated as heat. Excessive heat can severely reduce the life span of electronic components and must be reduced to acceptable levels.

For read-only transponders, the interrogator continuously transmits the radiofrequency signal and receives the response from the transponders. This mode of operation is known as *tag talks first*. When read/write transponders are being used, the interrogator must send commands for reading or writing them. For example, in the devices used by Microchip Technology, the interrogator uses amplitude modulation to transmit commands to the transponders. The communication starts by the interrogator sending specially timed gap pulses called *fast read request* (FRR) and *fast read bypass* (FRB). These gaps that are periods of time without electromagnetic field, are 175 µs wide, having a 100% modulation depth. The FRR or FRB pulses contain five of these gaps within 1.575 ms, as shown in Figure 5.2.

For RFID systems using magnetic coupling, one of the easiest approaches to drive the resonant circuit connected to the antenna is by using a D-drive circuit. Although either a full-bridge or a half-bridge will work correctly, most of the circuits use the half-bridge structure as it is less costly and easier to implement. Figure 5.3 shows a basic schematic for the half-bridge drive.

With a digital signal driving the circuit, the voltage at the node V_S is a square signal with voltages between V_{SS} and V_{DD}. Depending on the resonant quality factor (Q factor), the voltage across the antenna can reach a few hundred volts peak to peak. This is important to note at the time of selecting the electronic components used. An additional advantage of this structure is that although the driving digital signal has a very rich harmonic component,



FIGURE 5.2
Fast read request (FRR) and fast read bypass (FRB) pulses.

© 2011 by Taylor and Francis Group, LLC

the signal across the antenna consists mostly of the fundamental component due to the filtering effect and the high Q factor value at the antenna. There are several devices commercially available that integrate the inverter and the two metal oxide semiconductors (MOSs) or metal oxide semiconductor field effect transistors (MOSFETs) in a single package. In addition to being able to operate at the high voltages generated, the capacitors used must have very low tolerance values due to the requirements for an elevated Q factor.

The typical rise and fall times for the signals using the circuit shown in Figure 5.3 range between 120 μs and 200 μs. This limits the data transmission rate that can be achieved. A modification of the circuit to increase transmission rates by reducing rise and fall times needs to accelerate the turn-on or turn-off response of the driver. This can be achieved by using the modified driver circuit shown in Figure 5.4.



FIGURE 5.3
Half-bridge structure used to drive the resonant circuit.



FIGURE 5.4
Modified bridge for increased transmission rates.

© 2011 by Taylor and Francis Group, LLC

The idea behind this circuit is to decrease the start-up time by starting the driver in full-bridge mode until the voltage has reached the desired value, at which point it can be switched back to half-bridge mode. Because the driver is started by driving the two half-bridges 180° out of phase, it effectively operates like doubling the input source voltage. With this structure, the circuit can respond up to three times faster. It is also necessary to keep in mind that the voltage across the capacitor will also increase and therefore the capacitor must be rated for that higher voltage. In order to reduce the electromagnetic interference generated by the circuit, the Triac is typically fired at zero.

The basic structure of the receiver in the RFID interrogator also contains a detector, typically an envelope detector, a signal amplifier, filters, and the appropriate pulse-shaping circuits. These circuits convert the distorted received signal at the output of the filters into pulses. These pulses are, in turn, connected to the input of a microcontroller that will send the appropriate data to the middleware or host computers for further processing.

Selectivity and sensitivity are key parameters for any radiofrequency receiver. *Selectivity* is defined as the extent to which a receiver can differentiate between the desired signal and unwanted signals present in its bandwidth. *Sensitivity* is defined as the minimum input signal that produces the minimal required output to be interpreted as information. Other important characteristics for receivers are their dynamic range, cross-modulation, and intermodulation distortion. *Dynamic range* refers to the range of signal levels simultaneously applied to the input for which the receiver will operate correctly. *Cross-modulation* and *intermodulation distortion* originate as a result of the nonlinear effects in the receiver that cause it to create new, undesired components.

For RFID systems with magnetic coupling, the transponder communicates with the interrogator by changing the value of the magnetic field. The transponder is magnetically coupled to the front end of the receiver in the interrogator. In this structure, changes in the magnetic field become voltage changes at the antenna in the interrogator. Figure 5.5 shows a basic block diagram following this approach. The peak detector extracts the envelope of the signal being transmitted. The peak detector is followed by a filter to remove the DC component of the envelope. A further low-pass filter removes the radiofrequency component, leaving only the envelope of the modulated signal. The output of the comparator is a digital signal with the information from the transmitted signal.

The peak detector must operate with the relative high voltages that may appear at the input of the tuning circuit. Moreover, it should not become a load to the tuning circuit either. Other requirements for the peak detector are to reduce the ripple in the carrier as much as possible, maintain the modulation of the signal, and possess low setting times, among others. It is not possible to optimize all these parameters simultaneously, thus requiring the designer of the system to find an acceptable compromise depending on its overall requirements.

© 2011 by Taylor and Francis Group, LLC



FIGURE 5.5
Basic structure for the detector in the RFID interrogator.

Example 5.1:

Discuss possible solutions for reducing ripple in the carrier.

Solution:

The ripple in the carrier can be reduced by increasing the value of the capacitor used in the peak detector. However, increasing the value of the capacitor will degrade the settling time for the detector, and will increase its loading effects. A possible solution would be to use an active peak detector. However, given the range of voltages expected at the input of the detector, the cost of the detector would significantly increase.

The voltage at node V_1 increases quickly when the input voltage increases due to the low impedance of the diode in forward mode. When the input voltage decreases, the voltage at node V_2 decreases extremely slowly due to the very high impedance presented by the diode in reverse conduction. This situation could be solved to some extent by placing a resistor in parallel with capacitor C_1 to help discharge it. However, this resistor has to be large enough for the peak detector to avoid loading the input circuits. A value of 10 MΩ is typically used.

The goal for the decoupling stage is to reject the high DC voltages present in the signal without excessive loading the front end. This stage should also have a fast dynamic response and stabilize quickly after detecting energy. The time constant of this stage is equal to the product of the resistance by capacitance C_2. The component values can be calculated by considering the delay time in establishing the communication after detecting the presence of radiofrequency energy as well as the minimum allowable voltage after the settling time. The cutoff frequency of the resulting high-pass filter has a strong effect in distorting and attenuating the digital signal that contains the information. With these conflicting requirements for the time constant, the

© 2011 by Taylor and Francis Group, LLC

simple RC circuit is not appropriate for removing the DC component of the received signal. Instead, it is necessary to use a circuit with either a nonlinear or a controllable time constant, as shown in Figure 5.6.

The diodes start conducting when the voltage across the resistor is above $(V_{REF} + V_{ON})$ or below $-(V_{REF} + V_{ON})$. This results in lowering the effective resistance seen by the circuit, and therefore it lowers its time constant. An additional benefit from using the diodes is that they protect the low-pass filter against positive or negative voltage spikes. The additional resistor R_2 is controlled by the switch. The switch is closed during transient periods and opened when data are being received by the circuit.

The low-pass filter stage is best implemented using an operational amplifier configured as an inverting amplifier, as shown in Figure 5.7. This structure not only allows controlling the gain in the pass band, but also minimizes its output impedance.

The cutoff frequency depends on the values of R_f and C_f. This frequency should be chosen at least two decades above the cutoff frequency from the DC blocker. It is also necessary to limit the gain of the filter to avoid the saturation of the operational amplifier. For some systems, the simple filter shown in Figure 5.7 may not provide enough attenuation at the desired frequencies. If this is the case, it can be substituted by a more complex filter. The three most common active filter topologies are Chebyshev, Butterworth, and Bessel filters. Chebyshev filters have the steepest transition between the pass and stop band, although they have ripple in the pass band. Butterworth filters have the flattest pass band, but their transition is not as steep as Chebyshev filters. Bessel filters have linear phase response with a smooth transition between



FIGURE 5.6
Circuit for implementing a nonlinear time constant.

© 2011 by Taylor and Francis Group, LLC



FIGURE 5.7
Low-pass filter stage.

pass band and stop band. When selecting one of these filter structures, it is necessary to consider not only their frequency response but also their transient response. For example, although Chebyshev filters have the best frequency response due to the fast transition between pass and stop bands, this results in an underdamped transient response with overshoot and ringing. Therefore, it has a very long settling time. Although Butterworth filters have a better transient response, they still exhibit some overshoot. The Bessel filter, although it has the worst frequency response, exhibits the best and fastest transient response and therefore is a very attractive candidate for this type of application.

The final stage is a comparator with some degree of hysteresis. The level of hysteresis is chosen to provide the required immunity against noise. The output of the comparator should be a digital signal that can be directly connected to the input of a microcontroller for further processing and transmission.

5.2 Modulator and Demodulator

5.2.1 Amplitude-Shift Keying (ASK) Modulation

Amplitude-shift keying (ASK) is the most basic form of modulation for digital signals. In ASK, data are represented as variations in the amplitude of the radiofrequency carrier. In binary ASK, there are only two symbols to be transmitted: the symbol *1* is normally represented by the full amplitude of the carrier, while the symbol *0* is represented by the minimal amplitude of the carrier. In this case, these two different symbols are represented by a single bit. In general, for *M*-ary ASK symbols, *n* bits are used to represent *M* symbols as

$$M = 2^n \tag{5.1}$$

© 2011 by Taylor and Francis Group, LLC



FIGURE 5.8
Detector in the receiver section of a commercial interrogator.

A M-ary ASK system requires distinguishing between M different amplitude levels for the radiofrequency carrier. While M-ary systems increase the transmission rate because each symbol encodes n different bits, the amplitude levels of the different symbols become closer to each other, making the system more susceptible to transmission errors. Therefore, there is a tradeoff between the transmission rate and acceptable transmission errors.

The ASK signal is demodulated by detecting the envelope of the carrier, normally using a half-wave rectifier. This detects the peak amplitude of the signal generated by the transponder and feeds it into an RC circuit that charges and discharges accordingly. The time constant of the RC circuit must be chosen with these two considerations: (1) it must be small enough so the voltage across the capacitor diminishes fast enough in order to keep with the changes in the envelope of the signal, and (2) it must be high enough to avoid excessive ripple in the detected signal. After the envelope has been detected, the resulting signal is passed through a low-pass filter and a signal-shaping circuit and finally fed into a microcontroller. Figure 5.8 shows the schematic of the detector in the receiver section of a commercially available interrogator working in the LF range at 125 kHz.

The capacitor C_1 provides the resonance for the inductance of the antenna. An additional advantage of this structure is that because C_1 is grounded, the carrier finds a path to ground. The diode and C_2 form the half-wave rectifier for which the resistor R_1 provides a discharging path. The time constant of this circuit is approximately 850 μs. The signal is further low-pass and high-pass filtered before entering the comparator for processing.

5.2.2 Frequency-Shift Keying (FSK) Modulation

Frequency-shift keying (FSK) is a form of modulation in which the digital signal to be transmitted changes the frequency of the carrier within a predetermined set of available frequencies. The most basic case, in which only two instantaneous frequencies can be transmitted, is called *binary FSK* (2FSK). For more complex systems, and in order to increase the bit transmission rate, the number

© 2011 by Taylor and Francis Group, LLC

of possible instantaneous carrier frequencies is higher, normally a power of 2. This situation is called *M*-ary FSK, where *M* represents the total number of different possible instantaneous frequencies, as shown in equation (5.1).

Binary FSK transmits two different frequencies f_0 and f_1 to represent a logic *0* or a logic *1* following an established protocol. The transmission of 2FSK can be easily accomplished by having two oscillators operating at frequencies f_0 and f_1, followed by a switch that selects one or the other based on the digital input. Although this is a simple procedure, it results in discontinuities of the carrier frequency at the time of switching, thus resulting in a greater prominence of high-frequency components that implies the need for a much wider bandwidth transmission. 2FSK can also be generated using the VCO approach as is done for analog signals. Because the digital modulating signal will never have a zero rise or settling time, this digital modulation is in fact an analog modulation with a very short transition time. In this case, the carrier has a continuous and smooth transition, therefore guaranteeing phase continuity and requiring a narrower spectrum for transmission. This method is known as continuous-frequency shift keying (CPSK) and can also be readily applied for multilevel modulation systems.

FSK signals can be detected by *noncoherent detection* or *coherent detection*. Noncoherent detection is based on simultaneously injecting the 2FSK signal into two band-pass filters, each one tuned to the transmitted frequencies, f_0 or f_1, as shown in Figure 5.9. In this case, the output of each filter is connected to an envelope detector and their outputs are combined to reconstruct the baseband modulating signal.

An alternative method for noncoherent FSK detection is based on injecting the FSK signal to the input of a phase-locked loop (PLL). The output of the internal *voltage-controlled oscillator* (VCO) will switch between frequencies following the signal at the output of the PLL, thus locking on to the incoming FSK signal so that the output changes between the logic levels of *0* and *1*, depending on the frequency of the incoming signal.

Figure 5.10 shows the basis for coherent detection of FSK signals. This approach requires the generation of two carriers with the same exact frequencies and phases as those used by the transmitter. In this case, only one



FIGURE 5.9
Noncoherent frequency-shift keying (FSK) demodulator.

© 2011 by Taylor and Francis Group, LLC



FIGURE 5.10
Coherent FSK demodulator.

of the filter outputs contains a signal at any given time. Therefore, after the addition of the two paths, the transmitting signal is recovered.

The coherent detection of FSK-modulated signals requires a more complex receiver than the noncoherent detection of the same signal, although it decreases the rate of errors for the transmission. Consequently, the designer of the system must consider the trade-offs between bit error rates and system complexity.

5.2.3 Phase-Shift Keying (PSK) Modulation

Phase-shift keying (PSK) modulation is one of the most effective methods to transmit digital signals. In PSK, the information is contained in the instantaneous phase of the modulated carrier. Usually, this phase is imposed and measured with respect to a known and selected phase of the carrier. For 2PSK, in which the modulating signal has two levels, the phase states are 0° and 180°. In M-ary modulation systems, the phase associated to each transmitted symbol is distributed equidistantly from each other around the 360° circle. When $M = 4$ ($n = 2$ bits), the resulting modulation is called *quadriphase phase-shift keying* (QPSK). QPSK, in which the phases are separated by 90°, is a common modulation used in communication systems.

Figure 5.11 shows a simplified version of one of the methods to generate a 2PSK signal. After the radiofrequency carrier is shifter by 180°, the resulting signal as well as the original signal are fed at the input of a 2-to-1 selector. This selector is driven by the digital signal. The output of the selector is either signal (a) or signal (b), depending on the value of the digital signal that controls the output of the selector.

PSK signals always require coherent demodulation, and therefore the PSK detector needs to know perfectly the phase of the unmodulated carrier. This requirement can be problematic as any phase error of the locally generated carrier reduces the effective voltage at the output of the detector in cos(Φ), thus degrading the signal-to-noise ratio. A solution to this problem is by the

© 2011 by Taylor and Francis Group, LLC



FIGURE 5.11
Binary phase-shift keying (2PSK) generation.



FIGURE 5.12
2PSK demodulation.

demodulator itself deriving a phase coherent reference to use in the demodulation process, as shown in Figure 5.12.

The output of the squaring circuit contains information at DC as well as at a double of the radiofrequency carrier. The band-pass filter eliminates the DC component. The frequency divider divides the frequency of the resulting signal by two and shifts its phase. The resulting signal is then multiplied by the original 2PSK signal that, after being filtered, will result in a DC signal with amplitude either positive or negative, thus shifted in 180°.

Figure 5.13 shows the generation process for QPSK signals. The digital-modulating signal $v_m(t)$ is connected to a 2-bit serial to parallel converter, so the resulting signals $v_1(t)$ and $v_2(t)$ change at half the rate of $v_m(t)$. This has the

© 2011 by Taylor and Francis Group, LLC


V1(t)
cos ωct
Vm(t)
Serial to Parallel Converter
90° Phase Shift
Summing Amplifier
QPSK
V2(t)

FIGURE 5.13
Quadriphase phase-shift keying (QPSK) generation.


V1(t)
LPF
cos ωct
QPSK signal
Parallel to Serial Converter
−sin ωct
LPF
V2(t)

FIGURE 5.14
QPSK demodulation.

advantage of reducing the required transmission bandwidth as is the case of *M*-ary modulations. The output QPSK signal contains two components at the same frequency but shifted in 90°, and therefore there is no interference between them as they are in quadrature. That is, all the spectral components of the first term are 90° out of phase with those of the second term, making them independent from each other.

© 2011 by Taylor and Francis Group, LLC

The detection of the QPSK signal, as shown in Figure 5.14, follows an inverse process. The intermediate output signals $V_1(t)$ and $V_2(t)$ contain energy at DC as well as a frequency double the radiofrequency signal. This last component is eliminated by the low-pass filter, resulting in two separate streams of digital data. There are combined into a single data stream by the parallel-to-digital converter, thus recovering the original digital-modulating signal. QPSK modulation allows for sending information at twice the speed of 2PSK using the same bandwidth without compromising the performance of the system from the point of view of error rates.

Figure 5.15 shows a basic diagram of a 2PSK demodulator used in a commercial RFID interrogator operating in the LF range at 125 kHz. Capacitor C_1 provides the capacitance for resonance with the inductance of the antenna. The two diodes are used for detecting the envelope of the signal; each diode is on during half of the cycle. The 1 MΩ resistor is used to discharge the voltage store in capacitor C_2 used for the envelope detection. The envelope signal is fed into a series of active filters and pulse-shaping circuits not shown in Figure 5.15. The output of the last pulse-shaping circuit is a square wave at a frequency that is half of the radiofrequency carrier signal. This signal exhibits a 180° phase shifts according to the digital data sent by the transponders. This signal is now used as the clock for a D-type flip-flop. The input to the flip-flop is a signal at the same frequency derived from the transmitting signal. As the phase of the detected signal V_{out} changes, the output of the flip-flop also changes, thus recovering the digital information sent by the transponder.

One of the major problems with the design shown previously is that the phase of the returned signal can be, in certain conditions, unpredictable. For example, if the transitions of the incoming signal and the reference signal occur at the same time, the output of the flip-flop becomes unpredictable. This situation can be avoided with additional circuitry that intentionally shifts the phase between the signals to 90°, making it ideal for PSK detection.



FIGURE 5.15
2PSK demodulator in a commercial interrogator.

© 2011 by Taylor and Francis Group, LLC

5.3 Long-Range Considerations

When evaluating the read range of transponders, it is necessary to understand that long-range operation may not always be a desirable condition. For example, in an environment where several interrogators communicate with their own transponders, it is necessary to ensure that a specific interrogator reads data from only the transponders that it has been assigned. Data from a distant transponder would then be treated like an interfering signal.

If long range is truly needed, it can be achieved by one or more of the following design considerations:

Increasing the transmitter output power. This can be achieved by designing the power amplifiers in the transmitter section in the interrogator with higher gain. Alternatively, when it is not possible to modify the interior of the interrogator, it is then possible to use an external preamplifier. In any case, it is necessary to comply with the limits set by the appropriate regulatory agencies on limits of power for different frequency range. Also, some regulatory agencies may also limit the ability of a user to modify a system that has already been approved and certified by the regulatory agency. This comes from the fact that the modification of the gain in the amplifiers can have effects on the frequency stability, spectral purity, and other characteristics of the transmitted signal that are specified by the regulatory agencies.

Modifying the size of the antenna. As described in Chapter 4, the size of the antenna and its quality factor (Q factor) affect the characteristics of the signal being transmitted and therefore the range at which transponders receive enough energy to activate their internal circuits. A correctly sized antenna becomes critical for long-range applications.

Optimizing the sensitivity of the receiver. Merely increasing the power in the transmitter section may not have a significant effect in the read range of the system if the signals generated by the transponder cannot be detected by the receiver. Therefore, interrogators to be used for long-range applications must have front-end amplifiers with high enough sensitivity that will allow them to detect the signals from the transponders at the longest distance from the interrogator that has been specified. In addition to the optimal design of the receiver, the sensitivity of the interrogator can be increased by reducing the amount of noise and interference added to the desired signal. This can be achieved by appropriate shielding of the front-end components, by placing the interrogator away from electrically noisy sources and using pass-band filters.

© 2011 by Taylor and Francis Group, LLC

5.4 Interrogator Synchronization

Synchronization is used to prevent interference between the interrogators in applications that have multiple interrogators operating in the same area. Synchronization is based on preventing interference by coordinating their transmission and reception windows. Synchronization is only required when the different interrogators are located physically close to each other. Therefore, when working with multiple interrogators, it is critical to determine if synchronization is required. However, the distance between interrogators alone is not sufficient to determine the need for synchronization. The electrical path between interrogators is affected by the presence of metallic structures such as buildings, the existence of conveyors, the layout of nearby power or data cables, and even the existence of reinforcing metal bars in concrete floors. Assuming only radiated signals, Texas Instruments has published some guidelines for the maximum distances that require synchronization for interrogators using some of their antennas as shown in Table 5.1. It is important to note that Table 5.1 assumes the two interrogators are using the same antenna type.

Table 5.1 shows that antennas with larger dimensions require more separation. Because this table assumes only radiated signals, in more realistic situations, this distance can be highly reduced due to the additional paths available to the different radiofrequency signals. This table can also be used as a starting point when working with interrogators using different antennas.

The next step, after determining that synchronization between interrogators is needed, is to decide on the method used to synchronize them. Although the following are the synchronization methods available to some of the Texas Instruments interrogators, the same methods are used by interrogators from other manufacturers.

5.4.1 No Synchronization at the Interrogator Level

This method can only be used with a single reader or in the case of synchronization by software. It represents the fastest method for receiving

TABLE 5.1

Separation between Interrogators After Which Synchronization Is No Longer Necessary Assuming Only Radiated Signals

Antenna Type	Antenna Dimensions	Minimum Separation Distance
S02-C (stick antenna)	Ø = 21 mm; l =140 mm	18 meters
G02-E (gate antenna)	200 mm x 200 mm	32 meters
G01-E (gate antenna)	715 mm x 170 mm	55 meters
G04-E (gate antenna)	1018 mm x 518 mm	105 meters

© 2011 by Taylor and Francis Group, LLC

information from the transponders. If all the interrogators are connected to the same network, the coordination can be carried out by the host computer issuing commands to read transponders simultaneously and buffering the results, or issuing different commands to different interrogators in turn. In any case, the coordination is done by the host computer rather than by the interrogators.

5.4.2 Wireless Synchronization

In wireless synchronization, when a specific interrogator detects increased energy at the frequency of the carrier, it assumes that this energy has been generated by another interrogator. This makes it stop itself before starting its own cycle. Obviously, this method only works when the background noise is low for the type of antenna being used. Larger antennas, which are more sensitive, present a clear disadvantage in this situation. When the environmental conditions change and there are additional reflections of signals in the immediate electrical environment, this approach is not valid either.

The receiver in each individual interrogator is adjusted in order to determine the level of background noise in the absence of signals from other interrogators. This determines the level after which the interrogator assumes that another interrogator is transmitting and therefore waits for a predetermined amount of time before starting its own cycle. This situation is illustrated in two situations depicted in Figure 5.16.

Figure 5.16(a) shows a time diagram involving wireless synchronization when the interrogator has not detected the presence of other signals. The interrogator starts by transmitting the radiofrequency signal for 50 ms that is used to energize the transponder. After the transponder is energized and recognizes the end of the radiofrequency energy burst, it starts transmitting its data for 20 ms. Once the transponder has finished sending its data, the interrogator waits for another 20 ms before starting the whole process again. This additional period is build as a precaution to avoid corrupting the data from other transponders to other interrogators. Because the interrogator does not detect any signals during this last 20 ms period, the whole cycle takes 90 ms.

In Figure 5.16(b), however, after the transponder has completed sending its information to the interrogator, the interrogator detects the presence of radiofrequency energy, and therefore responds by waiting 70 ms before starting its new cycle. This additional period gives enough time for the second interrogator to finish its own cycle. After the 140 ms have elapsed, the first interrogator starts its own cycle regardless of the presence of radiofrequency energy. This is done in order to prevent the interrogators always giving priority to other interrogators and therefore not being able to read their own transponders.

Wireless synchronization has the advantages that it does not need wires to interconnect the interrogators and all the interrogators are autonomous

© 2011 by Taylor and Francis Group, LLC


Reader
Energize transponder
50 ms
40 ms
50 ms
Transponder
ID data
20 ms
20 ms
90 ms
(a)
Reader
Energize transponder
50 ms
Transponder
ID data
20 ms
70 ms
140 ms
(b)

FIGURE 5.16
Wireless synchronization: (a) no other interrogators detected, and (b) delayed cycle due to other interrogators detected.

as there is not a master unit. It is very useful when handheld units have to coexist with fixed interrogators for these reasons. Wireless synchronization, however, is not adequate when large antennas are used in noisy environments because these large antennas are too sensitive to the background noise levels. Also, it cannot be used when the environmental conditions change, for example when vehicles enter or leave the read area as it changes the background energy. Finally, it cannot be used when other interrogators write data to the transponders.

© 2011 by Taylor and Francis Group, LLC



FIGURE 5.17
Structure of the control modules in interrogators using wired synchronization.

5.4.3 Wired Synchronization

The approach in wired synchronization is the same as for wireless synchronization with the only difference being that it uses wires to detect the presence of other interrogators instead of detecting radiofrequency energy. Therefore, the cycle for a single interrogator lasts 90 ms or 140 ms as described for wireless synchronization. This presents the advantage of being able to operate regardless of the environmental noise level, using a single twisted pair cable. This approach does not need a master unit. The main problem with wired synchronization is that if the power for a single interrogator fails, the bus fails and therefore the whole system fails. It is also not suitable for read/write transponders. Figure 5.17 shows the standard connection for the control modules of the interrogators using wired synchronization using the following nomenclature:

SYNC RX+: Noninverted data input
SYNC RX–: Inverted data input
SYNC TX+: Noninverted data output
SYNC TX–: Inverted data output
GND: Signal ground

5.4.4 Combined Wired–Wireless Synchronization

Using this approach, interrogators synchronized using a hard wire connection are also detecting the amount of radiofrequency energy to decide if another interrogator is already operational. This method resolves the individual disadvantages of each single approach.

5.4.5 Master–Slave Synchronization

In this approach, which is probably the most commonly used method of synchronization, one of the interrogators is configured as the master while the rest of the interrogators are configured as its slaves. Master–slave synchronization can be carried out using three variants:

© 2011 by Taylor and Francis Group, LLC

Master–slave without acknowledgment. This method is the fastest approach for reading transponders as it assumes that all the interrogators are part of the same synchronization bus. This requires the interrogators to have a synchronization bus that connects all the readers, using for example a single twisted pair as shown in Figure 5.18.

Once the master has finished a complete read cycle, it transmits a synchronization pulse in the bus. Any slave that has finished its own cycle is waiting for this pulse in order to start a new cycle, as shown in Figure 5.19.

This approach presents the advantage of needing only a single twisted pair. It also has the fastest read rate and can be used when transponders are rewritten by interrogators. It is necessary, however, to keep in mind that if the master fails, the rest of the units stop working. Also, if a slave reads a transponder and the master does not, the slave may miss the next pulse as it is busy processing the information from its transponder.

Master–slave with acknowledgment. In this approach, the master has to wait until all the slaves have completed their cycles before starting a new master cycle. This requires using four wires: two for the pulse from the master and two for the information from the slaves to the master, as shown in Figure 5.20.

All the interrogators are running free while buffering the data via a point of data connection. A slave will not respond to a command from the host computer unless it has received the pulse from the master. This method presents the advantage that all the interrogators wait for the slowest to be complete and all the units are able to write to the transponders. This happens at the price of using a twin twisted pair instead of a single.

Master–slave triggered synchronization. This is similar to the previous approach, although in this case, the pulse is generated by an external device instead of an interrogator in the chain. All the interrogators



FIGURE 5.18
Structure of the control modules in interrogators using master–slave synchronization without acknowledgment.

© 2011 by Taylor and Francis Group, LLC


Energize
transponder
Energize
transponder
Reader
50 ms
20 ms
ID
data
Transponder
70 ms

FIGURE 5.19
Master–slave synchronization without acknowledgment.


SYNC RX+
SYNC RX–
SYNC TX+
SYNC TX–
SYNC RX+
SYNC RX–
SYNC TX+
SYNC TX–
SYNC RX+
SYNC RX–
SYNC TX+
SYNC TX–
SYNC RX+
SYNC RX–
SYNC TX+
SYNC TX–

FIGURE 5.20
Structure of the control modules in interrogators using master–slave synchronization with acknowledgment.

are configured as slaves with the external master issuing the synchronization pulses at suitable intervals. This is required for interrogators that must read and write to multipage transponders in which different interrogators require different window times. In this case, the master has total control over the coordination of the devices in the chain. However, the master must be a more complex system and requires additional intelligence.

5.4.6 Carrier Phase Synchronization

This method is used when several antennas are located close together with the possibility that the field generated by each one of them may interact with the others. Because of the different transmission phases at each interrogator, the interaction may result in destructive interference. To avoid this effect, all the interrogators must be operated from the same carrier signal.

© 2011 by Taylor and Francis Group, LLC

5.5 Structure of Commercially Available Interrogators

Interrogators for RFID systems take different approaches depending on the specific needs of their intended application: from large and complex systems to single-chip interrogators. The following pages describe these different approaches through examples from commercial interrogators. It is necessary to view them just as specific examples as the number of available systems is higher, each one of them using a different approach. However, these examples provide valuable information about the structure of interrogators.

5.5.1 Interrogators for LF RFID Systems

The Series Reader 2000 from Texas Instruments is an example of a complex interrogator for an RFID system operating in the low-frequency range. Its main component is the S251B reader. This interrogator has a communications interface as RS232, RS422, or RS485; eight general-purpose input/output lines; two open collector outputs; one synchronization bus; one carrier phase synchronization bus; as well as a power connector and an antenna connector. Table 5.2 shows the electric specifications of the eight general-purpose input/output (I/O) lines in this unit.

This interrogator supports two different communication protocols: the ASCII protocol or Texas Instruments' own TIRIS protocol. The ASCII protocol that is used to send commands to the interrogator can only be used with the RS232 or RS422 interface. The TIRIS bus protocol is a binary protocol between a host computer and one or more interrogators.

The interrogator has two main modules: the *control module* and the *radiofrequency module*. The control module contains all the electronics needed for the communication between the interrogator and the host computer in order to control the radiofrequency module. It also has circuits used to optimize the performance of the antenna by correctly tuning the module. The radiofrequency module handles all the analog functions needed to generate the

TABLE 5.2

Electrical Specifications of S251B Reader (Texas Instruments)

Parameter		Minimum	Maximum
General Purpose I/O Voltage			
	Low Level	---	0.9 V
	High Level	3.15 V	5.25 V
General Purpose I/O Current			
	Low Level	----	25 mA
	High Level	----	16 mA
General Purpose I/O 1 to 4 Total output current		----	10 mA
General Purpose I/O 5 to 8 Total output current		----	10 mA

© 2011 by Taylor and Francis Group, LLC

signal that energizes the transponders, send commands to the transponders, and detect their responses. These two modules will be studied in deeper detail in Sections 5.5.1.1 and 5.5.1.2.

The synchronization bus operates in differential mode with a maximum data rate of 10 Mbits/s and allows for a maximum cable length of 1200 m. It can handle up to 32 different drives or receivers on the line. The outputs of the bus are protected against short circuits with a current limit of 150 mA to ground and 250 mA to the power supply. In addition, this unit contains three banks of dual in-line package (DIP) switches that allow for configuration changes. One of the banks is for setting up the control module, another bank for the settings of the communications protocol, and the third one for synchronization settings.

5.5.1.1 Radiofrequency Modules

The functions of the radiofrequency modules in the RFID system are to transmit the radiofrequency signal to the transponder via the antenna, to receive and demodulate the response of the transponder, and to write information to the transponder. Figure 5.21 shows a simplified block diagram of a generic radiofrequency unit in an interrogator.

For the modules that are part of the Series 2000 Reader manufactured by Texas Instruments, it is possible to distinguish the following submodules:

> *Power supply.* This submodule provides the necessary voltage to power the rest of the electronics in the radiofrequency module. The majority


Unregulated voltage
Power Management
Voltage digital circuits
Voltage RF circuits
PWM
Power amplifier
To antennas
Antenna Tuning Circuits
BPF
Signal amplifier
Demodulator
Digital Interface
From antennas
Multiplexer

FIGURE 5.21
Simplified block diagram for the radiofrequency unit.

© 2011 by Taylor and Francis Group, LLC

of modules contain two voltage regulators, one to power the logic circuits and the other to power the rest of the module.

The manufacturer stresses not using a switching power supply, as at their typical frequency of operation their harmonics will create strong interfering signals.

Transmitter. The radiofrequency signal is generated by a crystal oscillator operating at the RFID frequency of 134.2 kHz. This signal is then fed into the pulse width modulator for which the user can select the width ratio between 3% and 50%. It is necessary to consider that decreasing this ratio also decreases the energy of the transmitted signal, thus providing a method to control the power transmitted by the interrogator.

Antenna circuit. The purpose of this submodule, shown in Figure 5.22, is to match the impedance of the transmitter to the impedance of the antenna in order to maximize the radiated power as well as its Q factor.

The circuit consists of the inductance of the antenna in series with an adjustable inductance for fine tuning as well as the capacitive part formed by the capacitors C_1, C_2, C_3, C_4, and C_{couple}. The switch is used to connect or disconnect C_4 for coarse tuning. It is necessary to connect several capacitors in series because of the high voltages that can be developed across the antenna terminals during resonance.



FIGURE 5.22
Antenna-tuning circuit.

© 2011 by Taylor and Francis Group, LLC

The capacitive resonator is driven by the *pulse-width modulation* (PWM) signal from the transmitter by two MOSFET power transistors through the inductor L_{couple}.

Receiver. The receiver in this module demodulates the FSK signals generated by the transponders, with a low symbol specified by a frequency of 134.2 kHz and a high symbol by a frequency of 123.2 kHz. The module can operate with a single antenna used for transmission and reception or with specific transmission and reception antennas. The path for the received signal depending on the type of antenna used is selected by the multiplexer at the front end.

Table 5.3 describes the different pins and its connections for the standard radiofrequency module in the Series 2000 Reader from Texas Instruments. Modules from other manufacturers have similar connections.

The most important electrical characteristics for these pins and connectors are shown in Table 5.4.

As shown in Table 5.4, the radiofrequency module incorporates a signal strength detector whose output is the RXSS- pin. This allows adjusting the threshold level for the detection of radiofrequency energy required by wireless synchronization. The adjustment is done by means of a potentiometer on the board. Different types of antennas require different threshold levels even if they operate in the same environment.

TABLE 5.3

Pins and Connectors in Standard Radiofrequency Module

Signal Name	Connection	Description
GND	IN	Ground logic circuits
TXCT-	IN	Transmitter control input for activation
VSL	IN	Supply voltage
RXDT	OUT	Receiver data signal output
RXSA	IN / OUT	Adjustment for receiver threshold level
RXCK	OUT	Clock output receiver
GNDP	IN	Ground power stage
RXA0	IN	Select signal for multiplexer
GNDP	IN	Ground power stage
RDTP	OUT	Test pin for receiver
VSP	IN	Supply voltage power stage
RSTP	OUT	Test pin for receiver
VSP	IN	Supply voltage power stage
RXSS-	OUT	Signal strength output in receiver
VD	IN / OUT	Internally regulated voltage
RCTP	OUT	Test pin for receiver

© 2011 by Taylor and Francis Group, LLC

TABLE 5.4

Summary of Electrical Characteristics Radiofrequency Module

Parameter	Min	Typ	Max	Unit
Internal regulated voltage	4.75	5.00	5.25	V
Supply current receive mode		9.0		mA
Supply current transmit mode		11.0		mA
Low level input voltage at TXCT- and RXA0	0		0.8	V
High level input voltage at TXCT- and RXA0	2.4		5.0	V
Low level output voltage at RXDT and RXCK	0		0.8	V
High level output voltage at RXDT and RXCK	4.0			V
Low level output voltage at RXSS-			0.8	V
Cable length for connection to control module		0.5	2.0	m
Number of slave modules that can be driven		1	5	
Inductance of antenna tuning coil	1.3	3.0	4.7	µH
Total antenna resonator capacitor	46	47	48	nF

This radiofrequency module, as well as most of the modules available in the market, can be used with the transmit–receive antenna or with special receive-only antennas. The type of antenna to be used is selected by a multiplexer in the receiver section.

5.5.1.2 Control Module

The control modules provide the functionality needed for the radiofrequency module to communicate with the rest of the devices. They control the Transmit and Receive commands from the radiofrequency modules according to the commands sent by the host computer. They also process the information from the transponders received by the radiofrequency modules, decode them, check their validity, and convert the signals to the protocol used for communication with the host computer. The control modules used in conjunction with the radiofrequency modules described in the previous section are available using the RS232C, RS422, or RS422/485 interfaces depending on the needs of the user. These control modules also handle the different synchronization methods described in Section 5.4 that need to be followed when more than a single interrogator is being used.

During the *charge time*, the control module activates the transmitter in the radiofrequency module. As long as this is active, the antenna resonates at the oscillator frequency and generates a radiofrequency field around its vicinity. This field charges the capacitor incorporated in the transponders energizing them. The typical length of the charge time is 50 ms. During this time, the receiver is disabled and cannot read any data. The charge time is followed by the *read time*, as shown in Figure 5.23. This time typically lasts 20 ms, during which the transponder sends the information back to the interrogator.

© 2011 by Taylor and Francis Group, LLC



FIGURE 5.23
Charge and read times.

All the data formats consist of 128 bits. After being received by the radio-frequency module, they are checked by the control module. The different types of transponders supported by these interrogators are differentiated from each other by using different Start, Stop, and End bytes. The data structure for these transponders is shown in Figure 5.24. It is important to note that the first bit being transmitted is the least significant bit (LSB) and the last bit is the most significant bit (MSB).

The data structure for read-only transponders is shown in Figure 5.24(a). The data format starts with 16 pre-bits that are all set at zero, followed by the start byte ($7E). The next 64 bits are the identification data bits programmed into the transponder at the time of manufacturing; they cannot be changed by the user. The next 16 bits comprise the data protection bits (BCC). The following byte is the stop byte, which has the same structure as the start byte ($7E). Afterward, the transponder sends 16 end bits, all of them set to zero. During the last bit, the transponder discharges its capacitor, therefore deenergizing its internal circuits.

Figure 5.24(b) shows the data structure for read/write transponders. It also starts with the 16 pre-bits set at zero followed by the start byte that in this case is set at $FE. This tells the interrogator that the data come from a read/write transponder. The next 80 bits are the data bits that can be programmed by the user. The manufacturer recommends splitting these bits into 64 bits of data identification transmitted first and 16 bits for data protection bits (block check character, or BCC). The stop byte that is transmitted next has the same value as the start byte ($FE). The final 16 bits reflect the 16 LSBs of the read data that must be checked for validity by the control module. Once again, the last of these 16 bits makes the transponder discharge its capacitor and deenergize its internal circuits.

The data structure for the multipage read/write transponder is shown in Figure 5.24(c). The data start again with the 16 pre-bits set at zero, followed by the start byte with a value of $7E. This start byte is the same as for read-only transponders, meaning that the distinction between these two structures will be possible after the reception of the read address and read address frame

© 2011 by Taylor and Francis Group, LLC


$00
$7E
$7E
$00
Discharge
16
8
64
16
8
16
LSB
Pre-bits
Start
ID data
Data BCC
Stop
End
MSB
(a)
$00
$7E
$7E
Discharge
16
8
64
16
8
16
Pre-bits
Start
ID data
Data BCC
Stop
Ident data
LSB
MSB
(b)
$00
$7E
Discharge
16
8
64
16
8
16
Pre-bits
Start
ID data
Data BCC
Read address
Read frame BCC
LSB
MSB
(c)

FIGURE 5.24
Data structure for several transponders: (a) read-only transponders, (b) read/write transponders, and (c) multipage read/write transponders.

BCC. The start byte is followed by 80 data bits that can be programmed by the user. The manufacturer also recommends splitting them into the first 64 data identification bits and 16 bits for protection data (BCC). The next 8 bits make up the read address byte; this contains a status field (2 bits), which is transmitted first, and a page field (6 bits). The 2 bits that make up the status field inform the control module about the function that the transponder has executed and the type of page that has been received. The final 16 bits make up the read frame BCC. One bit after having sent the first 128 bits, the transponder discharges the capacitor and deenergizes its internal circuits.

The function of the 16 pre-bits is to give enough time to the radiofrequency module to recover from the overload that it may have experienced during the 50 ms in which the transmitter has generated the radiofrequency signal. This is especially important because the transponders may start transmitting data immediately after having been energized. This period is known as the *waiting time*, lasting less than 1 ms.

After this time has elapsed, it is necessary to detect the first low-to-high transition for the start byte. After successful detection, the radiofrequency module synchronizes its clock and its data. The control module must also ensure that it receives all the high bits in the start byte. Otherwise, if a low bit is received, the process tops and the control module goes back to waiting for the detection of the low-to-high transitions. If the start byte has been successfully detected,

© 2011 by Taylor and Francis Group, LLC

the control module receives the next 80 bits and starts the generation of the cyclic redundancy check (CRC) to ensure the validity of the data. The last step in the decoding process is to determine whether the transponder that generated the data stream was a read-only transponder or a multipage read/write transponder as they both use the same start byte. This is done by checking the content of the CRC generator at the end of the process. If this value is equal to $0000, this indicates that a multipage read/write transponder originated the data. Otherwise, it indicates that it came from a read-only transponder. Figure 5.25 shows an overview of this sequence for the control module.


READ
Start Clock Counter
Activate Transmitter
50 ms Elapsed?
NO
YES
Deactivate Transmitter
Charging transponder process
Start Timer Counter
1 ms Elapsed?
NO
YES
Wait for Start Byte
Store Data Check BCC
Decide Type Transponder
Read transponder data
END

FIGURE 5.25
Control module sequence.

© 2011 by Taylor and Francis Group, LLC

The control module is also used to control the flow for writing to the transponder. Writing to the transponder is used to transfer commands, addresses, and data to the transponder. Before writing to the transponder, this must be energized. Therefore, writing to the transponder occurs after the transmitter has sent the 50 ms radiofrequency pulse to energize the circuits in the transponder. The actual process of writing is done by switching the transmitter off and on. To write a high bit, the transmitter is inactive during 1 ms followed by being active during 1 ms. To write a low bit, the transmitter is inactive during 0.3 ms followed by being active during 1.7 ms. The total time for writing a single bit is 2.0 ms.

To program the write data into the transponder's memory, the transmitter must be active for at least 15 ms immediately after the previously described write function has been executed. This is known as the *programming time*. Having the transmitter on for this time enables it to energize the circuits in the transponder. The write data format is shown in Figure 5.26.

All the data bits are transmitted to the transponder with the LSB first. The 8-bit write keyword ($BB) and the 8-bit write password ($EB) are sent to the transponder to initiate the transmission of the 80-bit data. The manufacturer recommends splitting the 80-bit data into 64-bit identification data transmitted first followed by 16 protection data bits (BCC). The write data format is terminated by a 16-bit write frame that must be set to $0300. After write frame, the transmitter will be active for 15 ms to allow the transponder to program the received data into its memory. The actual programming will only take place if the write keyword and write password bytes are received, the write data have the correct number of bits, and the radiofrequency field generated by the transmitter is high enough to produce the voltage required to program the transponder's memory. This voltage exceeds the voltage required to read the memory. Once after the programming time has elapsed, the transponder responds by sending the data that it has stored into its memory. This data follow the 128-bit format described previously in this section. If the read data received are structurally valid, they must be compared against the write data that were sent to the transponder to ensure that the correct data were written into the transponder. If the structure or the contents of the read data are not valid, the process must be repeated.

The last main function for the control module is to handle the synchronization tasks between different interrogators. For this to occur, a synchronization



FIGURE 5.26
Format for writing data.

© 2011 by Taylor and Francis Group, LLC



FIGURE 5.27
Synchronization sequence.

time must exist before the transmitter in the interrogator generates the radiofrequency signal to energize the transponders, as shown in Figure 5.27.

The synchronization allows the different interrogators in the overall system to detect each other and delay the activation of their own transmitters until other interrogators have finished their read functions. For this reason, the synchronization times vary depending on the number of interrogators in the application as well as the relative order of one interrogator in reference to the others in its vicinity.

5.5.2 Interrogators for HF RFID Systems

The Series Reader 6000 from Texas Instruments is an example of an RFID interrogator that operates in the HF range. The structure of the system is similar to the 2000 Series Reader described in the previous section. The Midrange Reader Module in this system provides the communication between transponder and interrogator. Output power levels can be adjusted between 100 mW and 1000 mW by means of a potentiometer placed on the radiofrequency module of the interrogator. The communication from the interrogator to the transponder is by ASK modulation, normally at 20%. The communication from the transponder to the interrogator is done by FSK modulation.

The TRF7960/1 also from Texas Instruments comprises multistandard fully integrated circuits containing the analog front end and the data-framing system. Their internal receiver enables them to modulate ASK and PSK, and it also includes automatic gain control and selectable bandwidth. In addition, the receiver includes a framing system allowing one to perform CRC checks, parity checks, or both. The output data are then sent to a microcontroller. The output of the transmitter only needs to be connected to the same impedance-matching circuit used for reception. Figure 5.28 shows the basic structure of the RFID system using this integrated circuit.

The receiver has two inputs that must be connected to an external filter. The external filter also converts the PSK modulation from the transponder into an amplitude-modulated signal. The two receiver inputs are multiplexed to two receiver channels: a main receiver and an auxiliary receiver. The main receiver contains a radiofrequency detection stage, a gain, a filter with automatic gain control, a digitizing stage, and an indicator for the strength of the received signal. The auxiliary receiver has a similar structure, although it is mainly used to measure the strength of the received signal.

© 2011 by Taylor and Francis Group, LLC



FIGURE 5.28
Structure of an interrogator using the TRF7960/1 circuits.

This is done by measuring the voltage of the demodulated signal and latching at its peak value.

The digital part of the receiver contains the bit decoders for the various protocols that supports the framing logic. The bit decoders convert the decoded signal into a bit stream. It has been specifically designed for maximum error tolerance, thus allowing the correct decoding of signals that have been partially corrupted due to noise or interference. The framing section packages the received bits into bytes, removing the control bytes sent by the transponder. This results in raw data that are sent to the microcontroller.

The transmitter contains the radiofrequency oscillator at 13.56 MHz, the processing circuits, and the radiofrequency power stage. The power levels available are 20 dBm (100 mW) or 23 dBm (200 mW) when the circuit is powered with 5V. When it is powered with 3 V, the available power levels are 15 dBm (33 mW) or 18 dBm (70 mW). The digital portion of the transmitter is very similar to that of the receiver as these circuits frame the command signals originated by the microcontroller.

5.5.3 Single-Chip Interrogators

In contrast to the complex systems described earlier, some interrogators have minimal components, normally an integrated circuit containing the transmitter and receiver and circuitry to communicate with a microcontroller or a microprocessor.

The core of the Series 6000 Reader from Texas Instruments is the RI-R6C-001 Integrated Circuit manufactured by the same company. This chip, whose block diagram is depicted in Figure 5.29, is a transceiver that provides the transmit and receive functions necessary for communication with transceivers operating at that frequency range.

© 2011 by Taylor and Francis Group, LLC


From antenna
Rectifier
BPF
To antenna
LPF
Control
Decoder Receiver
Error
Data out
Mode Register
External crystal
HF oscillator
Decoder Transmitter
Data in
Clock sync
RI-R6C

FIGURE 5.29
Simplified structure of the RI-R6C integrated circuit.

This transceiver integrated circuit communicates with its remote controller, normally a microprocessor, by a simple three-wire serial link. The communication between the transceiver and the transponders is generated by the microprocessor that sends the commands directly to the transceiver. The transceiver, in turn, applies the necessary carrier modulation and generates the radiofrequency signal.

The U2270B integrated circuit manufactured by Atmel® is another example of a single chip that serves as an interrogator. As shown in Figure 5.30, the U2270B incorporates an on-board power supply, an oscillator, tuning circuits, and other signal-processing circuits to produce an output that can be read by a microcontroller.

This specific chip has been designed to operate in the low-frequency range. It can be configured to work with different ranges of voltages for power supplies (from 5 V to 16 V). The low-pass filter in the receiver is a fourth-order Butterworth designed to remove the remaining energy of the carrier signal and other high frequencies after the demodulation process. The cutoff frequency can be selected by the user depending on the type of communication between the chip and the transponder that is being used. The possible choices are a Manchester code or biphase modulation typically at 5 kbaud.

© 2011 by Taylor and Francis Group, LLC


Control
Frequency
Adjustment
Power
Management
LPF
Rectifier
DC
Removal
Compar-
ator
to μC
U2270B
Enable

FIGURE 5.30
Simplified structure of the U2270B integrated circuit.


Damping
Power
Management
Rectifier
EEPROM
Memory
Low-power
Micro Controller
Modulator
Demodulator
Communications
Interface
U3280M

FIGURE 5.31
Simplified structure of the U3280M integrated circuit.

© 2011 by Taylor and Francis Group, LLC

One of the main applications of this chip is as an electronic immobilizer for the automotive industry in order to reduce auto theft. The interrogator and the associated microcontroller are located inside the vehicle, while the transponder with its unique identifier code is carried by the lawful owner or user in the vehicle. Unless the interrogator receives a valid code from a transponder, the microcontroller keeps the electronic ignition of the vehicle disabled. An additional benefit of this approach is that because the power to the transponder is supplied by the interrogator through the electromagnetic field it generates, the user of the vehicle does not need to worry about carrying fresh batteries like in traditional wireless fobs.

Atmel® also manufactures another chip, the U3280M shown in Figure 5.31, which, although marketed as a transponder interface for microcontrollers, functions as an interrogator. The chip can supply the energy required to power an external microcontroller and can also accept an external battery. The distribution of power is controlled by a power management circuit that either operates in automatic mode or is controlled by the microcontroller. The communication of this device with its microcontroller is carried out following a serial format. Modulation is carried out by changing the magnetic field generated by the antenna by varying its load. For example, a high logic level results in an increase of current through the antenna while the voltage becomes damped. The low logic level is generated by a decrease of current through the antenna that results in an increase in its voltage.

© 2011 by Taylor and Francis Group, LLC

6

Interrogator Communication and Control

CONTENTS

6.1 TIRIS Bus Protocol: Texas Instruments 155
6.2 ASCII Protocol for TIRIS Interrogators: Texas Instruments 159
6.3 Series 2000 Micro-Reader System: Texas Instruments 160
6.4 High-Frequency Interrogators: Texas Instruments............................... 166
    6.4.1 TIRIS Protocol for Series 6000 Reader System Interrogators... 166
    6.4.2 Host Protocol for Tag-it™ Series 6000 Reader System Interrogators 166

Interrogators communicate with the host computers in order to transmit commands to the transponders and collect their information. This chapter explores some of the protocols used for linking interrogators with the host computers using as examples the different protocols employed by some interrogators manufactured by Texas Instruments. These examples show the basic communication processes between interrogators and their host computers as a stepping-stone to understand the control of interrogators from other manufacturers. The chapter starts by describing the TIRIS Bus Protocol, developed by Texas Instruments. It continues by studying how the ASCII protocol is used in some commercial interrogators. The next section explains the protocol used in some LF interrogators manufactured by Texas Instruments. The chapter ends by describing the communication protocols used in interrogators operating in the HF range.

6.1 TIRIS Bus Protocol: Texas Instruments

The TIRIS Bus Protocol is a proprietary protocol developed by Texas Instruments for communications between its interrogators or between interrogators and a host. This is a half-duplex byte-count protocol. It allows efficient communication between a single master and multiple slaves. The protocol allows communication with a single slave unit on a RS232 line and up to 31 slaves on a RS422 or RS485 line or using parallel links.

All the data transfers using the TIRIS protocol are initiated by the host; the slave units only send data upon request from the host unit, therefore

© 2011 by Taylor and Francis Group, LLC

eliminating the possibility of data collision on the bus. Furthermore, the protocol uses positive acknowledgment with the slave units indicating the reception of a message from the master. All the messages have the same format independently of the direction they travel. Table 6.1 shows the structure of an *N*-byte message using this protocol.

Command-message-codes describe the action that the master requires from the slave. Its most significant bit (MSB; Bit 7) is the *queued-response flag*, while the following seven bits contain the command code. When the queued-response flag is set to 1, it indicates to the destination unit that it should acknowledge and execute the command but its response should be queued until requested by the master. This is normally used with commands that have a delayed response in order to avoid suspension of the line activity. When the flag is set to zero, the response is immediate following the execution of the command.

TABLE 6.1

TIRIS Bus Protocol Format

Byte	Content
0	Start Mark[a]
1	Destination Address[b]
2	Source Address[c]
3	Message Code[d]
4	Data length
5	Data field (1)
6	Data field (2)
…	…
N + 4	Data field (N)
N + 5	MSB for CRC-field (1)
N + 6	CRC – field
N + 7	End Mark

[a] The *start mark* signifies the beginning of a message and is represented by $01. This corresponds to the ASCII character Start-of-Heading.

[b] The second byte, *destination address,* indicates the address of the unit to which the message is directed. The binary value of this byte corresponds to the ID of the destination address. The ID for the different units ranges from $00 to $FE, although the maximum number of units in a specific application is limited by the physical limitations of the link. Broadcast messages are indicated by using a destination address of $FF.

[c] The *source address* is the third byte in the message format. It indicates the ID of the unit sending the message.

[d] The fourth byte is the *message code* byte. This byte is used to define the content of the message. When the message is from the master to the slave, this byte is a *command-message-code*. When the message is from slave to master, this byte is a *response-message-code*.

© 2011 by Taylor and Francis Group, LLC

The response-message-code describes the acknowledgment that the slave unit has received the command. The four MSBs in the code are flags, while the four remaining least significant bits (LSBs) are the response code. The different flags are as follows:

The MSB (Bit 7) is the *error-flag*. When it is set to 1, it indicates that the slave has detected an error in the transmission or in the contents of the command. The error code is indicated in the last four bits.

Bit 6 is the *busy-flag*. When it is set to 1, it indicates that the slave is temporarily unable to accept commands.

Bit 5 is the *data-available-flag*. When it is set to 1, it indicates to the master that there is at least one message in the output queue in the slave. In order to read this message, the master must send the appropriate command.

Bit 4 is the *broadcast-received-flag*. When it is set to 1, it indicates that a broadcast message, issued previously, has been received correctly. The response to the broadcast command is placed in the queue. The master can read the response by issuing the appropriate commands at which point the flag is reset to 0.

Bits 5-8 in the Response-Message-Code byte indicate the type of response. Their meaning varies depending on the state of the Error-Flag bit as shown in Table 6.2.

Bit 5 in the TIRIS protocol is the *data length* byte. This byte shows the number of bytes that follow as data field. If the command or response does not require any data, this value will be zero.

The following N bytes in the TIRIS protocol make up the *data field,* with N being the value specified in the previous byte (Data Length byte). The content of this field depends on the message being sent.

The two bytes after the Data-Field bytes are *CRC-field* bytes. These bytes contain the Cyclic Redundancy Check values to ensure the integrity of the message. The TIRIS Bus protocol supports two methods of generating the CRC field. The first method is the Reverse CRC-CCITT algorithm that was described in Section 3.3.2. The second method supported by this protocol is called Longitudinal Redundancy Check (LRC). This is based on XORing each character with the previous value and storing the result in the LSB byte fin the CRC-Field. The MSB byte of the CRC-Field is generated by storing the 1′s complement of the LSB byte. Using this method, if the MSB and LSB are ANDed together, the result should be zero. Consequently, any value different from zero indicates an error in the received message. This method is not as secure as the Reverse CRC method but it is faster.

The final byte is the *end mark* byte that indicates the end of the message. This is represented by $04 that corresponds to the ASC II character *end of transmission*.

© 2011 by Taylor and Francis Group, LLC

TABLE 6.2

Response Codes

Bit	Error-Flag = 0 Process Response		Error-Flag = 1 Error-Response	
0	Command Complete	A non-queued command received and executed correctly	Transmission Error	Slave received a message with its ID but found error on data
1	Accepted	A queued response command received correctly. Response will be placed on the queue	Command Invalid	Message received correctly but command code is not valid for this slave
2	Queue Empty	No message in the queue	Error – Data field length	Data field length wrong. Command not executed
3	Nothing to Resend	No information to resend available	Error - Parameter	Invalid parameter. Command not executed

Note: The following *N* bytes make up the *data field,* with *N* being the value specified in the previous byte (data length byte). The content of this field depends on the message being sent.

Using a two-wire, half-duplex circuit is not possible to execute flow control. Therefore, all the units in the bus must be able to receive and buffer the maximum length of the message at the operating speed for the line. When a unit is unable to handle correctly the incoming data, it cannot send an error message until the original message has ended. At that point, it can transmit the appropriate error message.

The data flow for the commands that do not require queuing from the slaves is always controlled by the master. The first steps for the master unit are to enable the transmitter, send the command message, and disable the transmitter. The slave unit, which is always monitoring the line, receives the incoming message and checks for the correct destination address. If the destination address is incorrect, it ignores the message and returns to monitoring the line. Because in this case the slave does not give any response to the master, the master will resend the command.

If the destination address is correct, the slave unit checks for errors in the message. If it detects errors, it sends an error response to the master, disables its transmitter, and returns to monitoring the line. Upon reception of the error response, the master unit processes the error code and resends the original command. If no errors are detected, the slave unit processes the command, sends the appropriate response message, disables the transmitter, and returns to monitoring the line. Upon reception of the response message, the master processes it and proceeds to transmitting the next command.

Broadcast messages transmitted by the master are not acknowledged in the normal way. After the master has sent the broadcast command, the slave checks for errors in the received message. If it detects errors, it ignores the message, sets the error flag, and returns to monitoring the line. If it does not detect errors, it sets the broadcast-received flag, processes the command, and places the response in its queue. The master accesses the special status bit in

© 2011 by Taylor and Francis Group, LLC

the response-code field in the slave's response to evaluate the correct reception of the previous message.

Example 6.1:

Describe the operations taken by a master unit that wants to initiate an operation on all slaves simultaneously.

Solution:

The master unit sends a command with a destination ID of $FF. The master unit then waits the expected operation time and proceeds to poll each individual slave. The master is looking for the *broadcast-received-flag* that verifies the correct reception of the command. The absence of this flag in a slave unit triggers the master to broadcast the command again.

Queued messages use a slightly different format from the format used by broadcast or immediate commands. The *N*th data field byte contains a sequence number, given by the master, that is used to have a reference when the queued messages are requested from the slave units. The slave unit indicates that a command requiring a queued response has been received and is being processed by sending a response message to the master with the accepted flag set. This response is not transmitted directly by the slave unit, but it is placed on its queue for the master unit to access it when ready.

When interrogators are asked to queue a response, these responses are placed in a 30-position circular buffer. The buffer has two pointers: store-next-message and read-next-message. Because of the circular structure of the buffer, it is not necessary to delete responses as they are overwritten when the pointer is incremented.

6.2 ASCII Protocol for TIRIS Interrogators: Texas Instruments

Some of the interrogators from Texas Instruments accept commands using a simple ASCII protocol. This ASCII protocol can only be used with a RS232 or RS422 communications line. Once the interrogator reinitializes, the first character to be transmitted is $02 (Start of Text, or STX), followed by $0D (Carriage Return) and $0A (Line Feed) through the serial interface. Any characters that may have been transmitted before the STX character are treated as random characters generated by the start-up process and therefore discarded.

Using this protocol, the interrogator can operate on four different modes: execute, normal, line, and gate. In execute mode, the interrogator triggers a single command, while in the other modes the read function is continuously triggered. The interrogators are also able to distinguish between three types of transponders: read-only, read/write, and multipage. The serial communications protocol from the interrogator to the host computer is

© 2011 by Taylor and Francis Group, LLC

introduced as a single character that describes the type of interrogator that originated the message: R (read-only), W (read/write), or M (multipage).

After receiving data from a transponder, the interrogator performs a data check. The result of this data check is one of the following: *identification received correctly*, *identification invalid*, or *no identification detected*. After receiving a correct identification, the interrogator proceeds to send the information through the bus. This is done by placing the identification string in a buffer that is accessed, read, and cleared by the host computer. The TIRIS protocol can distinguish between two groups of transponder identification: animal code numbers and industrial (nonanimal) code numbers.

6.3 Series 2000 Micro-Reader System: Texas Instruments

The Series 2000 RFID interrogators operate in the LF range. Table 6.3 describes the structure of an *N*-byte message sent from the host computer to the interrogator in these systems.

The following set of bytes are the *data field* bytes. These bytes only exist if required by the command field.

TABLE 6.3

Series 2000 Host-to-Interrogator Message Format

Byte	Content
0	Start Mark[a]
1	Message length[b]
2	Command Field[c] (1)
3	Command Field (2) - not always present
4	Data field (1)
5	Data field (2)
…	…
N + 3	Data field (N)
N + 4	BCC

Note: If the second command field is not used, the length of the message is $N + 3$ bytes. In addition, messages are limited to a total of 41 bytes.

[a] The first byte is the *start mark* that indicates the start of a message.

[b] The second byte is the *message length* byte that indicates the length, in bytes, of the command and data fields that follow.

[c] The third and fourth bytes (when the second command field byte exists) are the *command field* bytes. These bytes define the mode of operation for the interrogator and determine the operation that the interrogator must carry out on the transponder. Depending on the type of command, the information in the data fields may or may not be transmitted to the transponder. The meaning of the different bits for the command field (1) is described in Table 6.4.

© 2011 by Taylor and Francis Group, LLC

TABLE 6.4

Command Field (I) Bit Description

Bit	Description	Value	Operation
0 and 1	Operation Mode	00	Perform single command
		01	Read in continuous Normal Mode
		10	Read in continuous Line Mode
		11	Send interrogator software version
2	FBCC Calculation	0 or 1	1 = interrogator calculates FBCC
3	Power burst I	0 or 1	1 = duration determined in data field
4	Power burst pause	0 or 1	1 = duration determined in data field
5	Power burst II	0 or 1	1 = duration determined in data field
6	Data	0 or 1	1 = determined in data field
7	Command Expansion Field	0 or 1	1 = Command Field (2) is used

TABLE 6.5

Command Field (2) Bit Description

Bit	Description	Value	Operation
0	Special write timing	0 or 1	1 = Must be determined in data field.
1	Wireless synchronization	0 or 1	1 = Wireless synchronization being used.
2	Database consistency check (DBCC) calculation	0 or 1	1 = Interrogator calculates DBCC.
3 to 7	Reserved	0 or 1	Reserved.

The following set of bytes are the *data field* bytes. These bytes only exist if required by the command field.

The last byte in the message is the *block check character* (BCC) byte. This is a one-byte value that results from XORing each one of the bytes in the preceding message with the exception of the start mark byte.

As shown in Table 6.4, the existence of command field (2) is set by bit 7 of command field (1). Table 6.5 shows the meaning of the bits in command field (2) when it is present in the message.

Example 6.2:

Calculate the BCC for a message containing the following hex bytes: 04 23 38.

Solution:

BCC is calculated by XORing the bytes of the message. Start by first XORing 04 and 23:

04	0000 0100
23	0010 0011
XOR	0010 0111

The resulting value (0010 0111) is now XORed with 38:

Previous XOR	0010 0111
38	0011 1000
XOR	0001 1111

Therefore, the resulting BCC is $1F.

© 2011 by Taylor and Francis Group, LLC

The following three examples illustrate the structure of messages between the host computer and the interrogator for a variety of different commands and applications.

Example 6.3:

The following is the structure of a message transmitted from the host computer to the interrogator in commanding the interrogator to read a read-only transponder:

Byte	Code	Content	Description
0	$01	Start Mark	Start Mark
1	$02	Length	Two bytes follow (excludes BCC)
2	$08	Command Field (1)	Perform single command – Power burst
3	$32	Data Field (1)	Power burst for 50 ms to energize transponder
4	$38	BCC	BCC over previous bytes excluding Start Mark

Example 6.4:

The following is the structure of a message transmitted from the host computer to the interrogator in commanding the interrogator to write the following data in a read/write transponder.

```
00  0A      FE      32      66      00      00      01
MSB                                                 LSB
```

Byte	Code	Content	Description
0	$01	Start Mark	Start Mark
1	$11	Length	17 bytes follow (excludes BCC)
2	$E8	Command Field (1)	Perform single command, no FBCC calculations, send power burst to energize transponder for reading and writing. Data command on following field
3	$06	Command Field (2)	Use wireless synchronization
4	$32	Data Field (1)	Power burst to energize transponder for reading (50 ms)
5	$0F	Data Field (2)	Power burst to energize transponder for writing (15 ms)
6	$0C	Data Field (3)	12 data bytes follow
7	$BB	Data Field (4)	Write Keyword
8	$EB	Data Field (5)	Write Password
9	$01	Data Field (6)	LSB of data to write
10	$00	Data Field (7)	Data to write
11	$00	Data Field (8)	Data to write
12	$66	Data Field (9)	Data to write
13	$32	Data Field (10)	Data to write
14	$FE	Data Field (11)	Data to write

© 2011 by Taylor and Francis Group, LLC

Byte	Code	Content	Description
15	$0A	Data Field (12)	Data to write
16	$00	Data Field (13)	MSB of data to write
17	$00	Data Field (14)	Write frame
18	$03	Data Field (15)	Write frame
19	$9C	BCC	BCC over previous bytes excluding Start Mark

Example 6.5:

The following is the structure of a message transmitted from the host computer to the interrogator in commanding the interrogator to read page 2 of a multipage transponder.

Byte	Code	Content	Description
0	$01	Start Mark	Start Mark
1	$04	Length	Four bytes follow (excludes BCC)
2	$48	Command Field (1)	Perform single command – Power burst with data
3	$32	Data Field (1)	Power burst for 50 ms to energize transponder
4	$01	Data Field (2)	One data field follows
5	$08	Data Field (3)	Write address specifying general read of page 2
6	$77	BCC	BCC over previous bytes excluding Start Mark

The structure of the messages sent from the interrogator to the host computer is described in Table 6.6.

The bytes following BCC are the *data* field bytes.

TABLE 6.6

Series 2000 Interrogator-to-Host Message Format

Byte	Content
0	Start Mark[a]
1	Message length[b]
2	Status[c]
3	Data field (1) LSB byte
4	Data field (2)
…	…
N + 2	Data field (N) MSB byte
N + 3	BCC

[a] The first byte is the *start mark* that indicates the start of a message.

[b] The second byte is the *message length* byte that indicates the length, in bytes, of the command and data fields that follow.

[c] The third byte is the *status byte*. This provides feedback about the preceding read or programming operation according to Table 6.7.

© 2011 by Taylor and Francis Group, LLC

TABLE 6.7

Description of Bits in the Status Byte

Bit	Value	Operation
0 and 1	00	Read Only transponder
	01	Read/Write transponder
	10	Multipage transponder
	11	Other transponder
2	0 or 1	1 = Start byte was successfully detected
3	0 or 1	1 = DBCC was successfully performed
4	0 or 1	1 = DBCC was successfully performed
5	0 or 1	1 = Software version for interrogator follows
6–7	Reserved	

TABLE 6.8

Description of Data Field Bytes

Type of Response	Number of Bytes in Data Field	Description
Read Only	8	Identification data. LSB first
Read/Write	8	Identification data. LSB first
Multipage	9	Identification data. LSB first and Read Address
Other	14	Complete transponder protocol without pre-bits assuming a successful start byte was detected
No Read	0	No data fields, no start byte. Status is $03
Software version	1	Software version. For example $12 means software version 1.2

The last byte in the message is the *BCC* byte. This is a one-byte value that results from XORing each one of the bytes in the preceding message with the exception of the start mark byte.

The length and meaning of the data field bytes are shown in Table 6.8.

Example 6.6:

The following is the structure of a message transmitted from the interrogator to the host computer after a successful read of a read-only transponder.

Byte	Code	Content	Description
0	$01	Start Mark	Start Mark
1	$09	Length	Nine bytes follow (excludes BCC)
2	$0C	Status	Valid RO, Start byte detected, DBCC is correct
3	$6A	Data Field (1)	Identification data (LSB)
4	$58	Data Field (2)	Identification data

© 2011 by Taylor and Francis Group, LLC

Byte	Code	Content	Description
5	$4C	Data Field (3)	Identification data
6	$00	Data Field (4)	Identification data
7	$00	Data Field (5)	Identification data
8	$00	Data Field (6)	Identification data
9	$00	Data Field (7)	Identification data
10	$00	Data Field (8)	Identification data (MSB)
11	$7B	BCC	BCC over previous bytes excluding Start Mark

Example 6.7:

The following is the structure of a message transmitted from the interrogator to the host computer after an unsuccessful read attempt.

Byte	Code	Content	Description
0	$01	Start Mark	Start Mark
1	$01	Length	One byte follows (excludes BCC)
2	$03	Status	Other, no Start byte detected, DBCC is not correct
3	$02	BCC	BCC over previous bytes excluding Start Mark

Example 6.8:

The following is the structure of a message transmitted from the interrogator to the host computer after successfully programming page 2 of a multipage transponder.

Byte	Code	Content	Description
0	$01	Start Mark	Start Mark
1	$0A	Length	Ten bytes follow (excludes BCC)
2	$1E	Status	Valid Multipaage, Start byte detected, DBCC is correct
3	$47	Data Field (1)	Identification data (LSB)
4	$C6	Data Field (2)	Identification data
5	$2D	Data Field (3)	Identification data
6	$00	Data Field (4)	Identification data
7	$00	Data Field (5)	Identification data
8	$00	Data Field (6)	Identification data
9	$00	Data Field (7)	Identification data
10	$00	Data Field (8)	Identification data (MSB)
11	$09	Data Field (9)	Read address specifying successful programming of page 2
12	$7B	BCC	BCC over previous bytes excluding Start Mark

© 2011 by Taylor and Francis Group, LLC

6.4 High-Frequency Interrogators: Texas Instruments

6.4.1 TIRIS Protocol for Series 6000 Reader System Interrogators

The Series 6000 Reader System interrogators are RFID interrogators operating in the HF band, manufactured by Texas Instruments. These interrogators use a RS232 line to communicate with the host computer. The data packet from the host to the interrogator is known as the *request*, while the data from the interrogator to the host are known as the *response*. All communication sequences are initiated by the host that is the primary station. Using this protocol, the host waits for the response before continuing, thus assuring that the host does not have to handle large sequences of open requests. This is a binary, byte-count-oriented protocol in which the data length is passed as a parameter in the message.

Table 6.9 shows the structure of the messages used by these interrogators for the request message (host to interrogator).

The contents of byte 5 (command flags) are used to control the actions of the interrogator. The meanings of the different bits in this byte are shown in Table 6.10.

The BCC, used to ensure the integrity of the message, is a 16-bit code calculated on all the bytes of the packet including the start mark. The BCC contains two parts: its least significant byte is a longitudinal redundancy check (LCR) calculated by performing a cumulative XOR operation on all the bytes of the packet. The most significant byte in the BCC is the one's complement of the LCR.

The structure of the message sent from the interrogator to the host (response) is shown in Table 6.11. Most of these bytes are similar to the bytes in the request message.

The data field in response messages is limited to a maximum of 23 bytes. The contents of byte 5 (command flags) are used to report on the actions of the interrogator. The meanings of the different bits in this byte are shown in Table 6.12.

The different error codes that the interrogator transmits to the host computer when bit 4 of the command flag byte is set to 1 are described in Table 6.13.

The contents of byte 5 (command flags) are used to control the actions of the interrogator. The meanings of the different bits in this byte are the same as for the request message shown in Table 6.10.

6.4.2 Host Protocol for Tag-it™ Series 6000 Reader System Interrogators

This protocol defines the communications between the Tag-it™ Series 6000 Reader System Interrogators and the host computer. It handles the communication between the host and the interrogator, and carries out the requests

© 2011 by Taylor and Francis Group, LLC

TABLE 6.9

Series 6000 Host-to-Interrogator Message Format

Byte	Content
0	Start of Frame[a]
1	Message length[b] - LSB
2	Message length - MSB
3	Node address[c] - LSB
4	Node address - MSB
5	Command flags[d]
6	Command[e]
7	Data[f]
8	Data
…	Data
N+6	Data
N+7	BCC[g]
N+8	BCC

[a] The first byte is the *start mark* that indicates the start of a message. This byte is equal to $01.

[b] The second and third bytes are the *message length* bytes that indicate the length of the whole packet, including the start mark.

[c] Bytes 3 and 4 constitute the *node address*. Its value is $0000.

[d] Byte 5 is the *command flags* byte. It controls the actions taken by the interrogator. The value of this byte is dependent on the command being transmitted.

[e] Byte 6 is the *command* byte. It specifies the actions that must be taken by the interrogator. The value of this byte is dependent on the command being transmitted.

[f] The following *N* bytes are the *data* bytes. These contain the parameters and the data for the command.

[g] The last two bytes are the *BCC* bytes used to ensure the integrity of the preceding message. BCC is performed on the previous bytes, including the start mark.

TABLE 6.10

Bit Functionality in Command Flag Byte (Request)

Bit	Description
0	Reserved for future use
1	Reserved for future use
2	Reserved for future use
3	Reserved for future use
4	1 = Command to be performed only on transponders with an address that matches the data section of the message
5	Reserved for future use
6	Reserved for future use
7	Reserved for future use

© 2011 by Taylor and Francis Group, LLC

TABLE 6.11

Series 6000 Interrogator-to-Host Message Format

Byte	Content
0	Start of Frame
1	Message length - LSB
2	Message length - MSB
3	Node address - LSB
4	Node address - MSB
5	Command flags
6	Command
7	Data
8	Data
…	Data
N+6	Data
N+7	BCC
N+8	BCC

TABLE 6.12

Bit Functionality in Command Flag Byte (Response)

Bit	Description
0	Reserved for future use
1	Reserved for future use
2	Reserved for future use
3	Reserved for future use
4	Error flag. 1 = command was unsuccessful. Data section of response packet contains the code of the error
5	Reserved for future use
6	Reserved for future use
7	Reserved for future use

TABLE 6.13

Error Codes

Code	Description
$01	Transponder not found
$02	Command not supported
$03	Packet BCC invalid
$04	Packet flags invalid for command
$05	General write failure
$06	Write failure because of locked blocks
$07	Transponder does not support command
$0F	Undefined error

© 2011 by Taylor and Francis Group, LLC

for commands as well as their responses. Additionally, the protocol manages some aspects of the functionality of the reader and enhances the functionality of basic transponders by requesting the execution of compounded commands. This protocol is intended for point-to-point, half-duplex communications in which the host is the primary station. In some situations, however, the host may receive responses without sending a request first. This is a binary, byte-count-oriented protocol in which the data length is passed as a parameter in the message. Similar to the TIRIS protocol, the message from the host to the interrogator is called a *request*, while the message from the interrogator to the host is called a *response*.

The communication between host and interrogator is performed using a frame structure. The frame structure is essentially the same for requests and responses with the exception of the flag as they have different meanings. Requests use control flags, while responses use status flags. In this protocol, the length of the message data is limited to 4091 bytes. Table 6.14 describes the structure of the request and response frames.

In *pass-through-service* mode, the interrogator passes the information that it has received from the host to the transponder immediately without doing any other action. When the interrogator receives a response from the transponder, it also passes it directly to the host without further action. If the interrogator does not receive a response from the transponder in a specified period of time, it sends a message to the host with the error flag set and the

TABLE 6.14

Structure of Request and Response Frames

	Description	
Byte	**Request Frame**	**Response Frame**
1	Start Code[a]	Start Code
2	Data Length[b]	Data Length
3	Data Length	Data Length
4	Service Code[c]	Service Code
5	Control Flag	Status Flag
6	Message Data	Message Data
…	Message Data	Message Data
N-1	Message Data	Message Data
N+6	BCC	BCC
N+7	BCC	BCC

[a] The first byte contains the *start code*. This is the start frame delimiter using the value $D5.

[b] The next block is the two *data length* bytes that specify the number of data bytes that follow that block. The minimum length is 4 bytes (the service code, control flag, and two BCC bytes), while the maximum length is limited to 4095 bytes.

[c] The *service code* indicates the type of command that is being sent, as shown in Table 6.15.

© 2011 by Taylor and Francis Group, LLC

TABLE 6.15

Service Codes

Code	Description
$01	Pass-through Service
$02	Single Service
$03	Compound Service
$04	Ancillary Service

appropriate error code. Using pass-through service, the host directly controls the transponder.

In *single-service* mode, after receiving a request from the host, the interrogator analyzes and verifies it before formatting and sending a single command to the transponder. Also, when the interrogator receives a response from the transponder, it analyzes it, verifies it, formats it, and sends a unique response to the host.

The *compound-service* mode is used by the host to instruct the interrogator to perform specific actions on transponders using the transponder protocol. The difference between these actions and the actions from a single-service request is that in compound service, the interrogator performs complex operations involving multiple commands before returning a response to the host computer. After receiving a compound-service request, the interrogator also analyzes and verifies it before sending the appropriate commands to the transponder. The interrogator also analyzes and verifies all the responses received from the transponder before sending a single response to the host. This response, however, may consist of more than one frame depending on its size. Compound service increases the performance of the system because, for example, it takes less time to send a single command to read four blocks of memory and transmit the information to the host, rather than issuing four different reading commands while transmitting the intermediate information to the host after each one has been performed.

Ancillary-service mode is used to instruct the interrogator to perform certain actions that do not involve communication with the transponder. Examples of such actions are interrogator reset, read interrogator version, and perform interrogator diagnostics. They are also used to upload new software versions in the interrogator or to set up new communication parameters.

Table 6.16 lists the available service codes with the exception of the pass-through-service codes as they are defined by the transponder protocol. The different transponder protocols are described in Chapter 7. The different commands are described in further detail in the next sections of this chapter. Table 6.16 can also be used to understand the type of commands available for each service code.

For control flags, four of the bits in byte 5 are used to specify instructions to the interrogator or they carry information about the message, as shown in Table 6.17.

© 2011 by Taylor and Francis Group, LLC

TABLE 6.16

Commands Available for Different Service Codes

		Service Code		
Command	**Command Code**	**Single**	**Compound**	**Ancillary**
Tag Version	$03	$02		
Read Block	$12	$02		
Read Multiblock	$02	$02	$03	
Read Block SID	$FE		$03	
Read Multiblock SID	$FD		$03	
Write Block	$05	$02		
Write and Lock Block	$07	$02		
Write Multiblock	$06	$02	$03	
Lock Block	$08	$02		
Lock Multiblock	$09	$02	$03	
Repeat Last Request	$01			$04
Send Last Request	$02			$04
Stop Continuous	$04			$04
Start Synch	$05			$04
Reader Reset	$10			$04
Reader Version	$11			$04
Reader Diagnostic	$12			$04
Read Reader Setup	$13			$04
Start Flash Loader	$16			$04
Factory Lock Block	$3D	$02		
Write SID Code	$3E	$02		
Factory Programming Off	$3F	$02		

The next byte, byte 5, is the *control flags* byte. This byte has a different meaning depending on the direction of the message. For Request Frames (host-to-interrogator), byte 5 is called the *control flag byte*. For response frames (interrogator-to-host), byte 5 is called the *status flag byte*.

For status flags, four of the bits in byte 5 are used to provide information about the result of the request, as shown in Table 6.18.

Bit 0 (exception flag) indicates whether the request was successfully routed to the interrogator. When bit 0 is reset to 0, it indicates that no exception occurred and the request was completed satisfactorily. When bit 0 is set to 1, it indicates that an exception occurred. In this case, the error code that describes the exception can be found in the first byte of the message. These errors are shown in Table 6.19.

Bit 1 (more flag) informs the interrogator whether more data follow (bit 1 = 1). Bit 2 (emulation flag) informs the interrogator whether the transponder completed the request using a compound command to emulate a complex command (bit 2 = 1). Bit 3 (auto-repeat flag) informs the interrogator where

© 2011 by Taylor and Francis Group, LLC

TABLE 6.17

Bits for Control Flags

Code	Description
0 (LSB)	Reserved
1[a]	More Flag
2[b]	Emulation Flag
3[c]	Auto Repeat Flag
4[d]	BCC Flag
5 to 7	Reserved

[a] When bit 1 (more flag) is set to 1, it indicates to the interrogator that it should expect more frames until the host sends a frame in which bit 1 is reset to 0. When bit 1 is reset to 0, it indicates to the interrogator that there are no more data associated with the request either in a single message or at the end of a series of messages.

[b] Bit 2 (emulation flag) indicates the interrogator if it is allowed to emulate a complex request by sending multiple single requests. This results in substituting a complex command with a compound command. When bit 2 is set to 1, this means that if the command cannot be performed using the current transponder version, the interrogator will attempt to use a compound command. When bit 2 is reset to 0, the substitution is not allowed.

[c] Bit 3 (auto-repeat flag) specifies whether or not the interrogator should automatically repeat the execution of the request. When Bit 3 is set to 1, auto-repeat is on. In this case, the interrogator will execute the request, send the response it has received from the transponder back to the interrogator, wait for a specified amount of time, and send the request again. This process is repeated until it receives another instruction with bit 3 reset to 0.

[d] Bit 4 is the BCC flag. It specifies the type of block code check used to ensure the integrity of the message. When bit 4 is reset to 0, the message uses CRC-CCIT, while when bit 4 is set to 1, the message uses LRC. Although LRC is simpler to implement and requires less processing time than CRC, it does not offer as much protection as CRC.

TABLE 6.18

Bits for Status Flags

Code	Description
0 (LSB)	Exception Flag
1	More Flag
2	Emulation Flag
3	Auto Repeat Flag
4	BCC Flag
5 to 7	Reserved

© 2011 by Taylor and Francis Group, LLC

TABLE 6.19

Error Messages Associated to Exception Flag

Code	Description
$00	Reserved
$01	Request data corrupted and not executed
$02	Application not supported
$03	Data format error and request aborted
$04	Continuous mode not available for this request
$05	Reserved
$06	Reserved
$07	Reserved
$08	Reserved
$09	Reserved
$0A	Reserved
$0B	Reserved
$0C	Reserved
$0D	Reserved
$0E	Reserved
$0F	Undefined error and request aborted

TABLE 6.20

Structure of Single Service Messages

Length	Description
5 bytes	Frame
1 byte	Command
1 byte	Format
1 byte	Synch
≤ 4088 bytes	Message Data
2 bytes	Frame

the transponder performed the request once (bit 3 = 0) or continuously (bit 3 = 1). Bit 4 (BCC flag) specifies the method used to generate the BCC byte: CRC (bit 4 = 0) or LRC (bit 4 = 1).

The next byte or set of bytes are the *message data* bytes that carry the actual message. The actual format of the message depends on the type of command that was specified in the service code byte. In pass-through-service messages, the interrogator is transparent to the request from the host to the transponder. The communication from the host to the transponder uses the transponder protocol. Because this is a bit-oriented protocol, it may be necessary to add the necessary bits to the message to ensure that the whole frame falls within a byte-oriented protocol. These are called *pad bits*. The structure for single-service messages is shown in Table 6.20.

© 2011 by Taylor and Francis Group, LLC

TABLE 6.21

Format Byte for a Request Message

Bit	Name	Description
0 (LSB)	Reserved	
1	Code Extension	0 = No extension code 1 = Code extension used
2	Addressing	0 = Not addressed 1 = Addressed. Address contained in first 4 bytes of data field
3	Format	0 = Fixed format 1 = Variable format
4	Transmitter control	0= Turn transmitter off after executing command 1 = Leave transmitter on
5	Reserved	
6	Reserved	
7 (MSB)	Reserved	

TABLE 6.22

Format Byte for a Response Message

Bit	Name	Description
0 (LSB)	Error	0 = No error 1 = Error occurred. Status code is first byte of data field after any address information
1	Code Extension	0 = No extension code 1 = Code extension used
2	Addressing	0 = Not addressed 1 = Addressed. Address contained in first 4 bytes of data field
3	Format	0 = Fixed format 1 = Variable format
4	Reserved	
5	Reserved	
6	Reserved	
7 (MSB)	Reserved	

The structure for single-service messages is shown in Table 6.20.

The format byte contains information about the format and status of the message. The contents are different depending on whether the message is a request or a response. Table 6.21 shows the description of the format byte for a request message, while Table 6.22 shows the description of the format byte for a response message.

Table 6.23 shows the meaning of the synchronization codes for both request and response messages.

The structure for compound messages is shown in Table 6.24.

Tables 6.25 and 6.26 show the structure of the format byte for request messages and response messages, respectively.

© 2011 by Taylor and Francis Group, LLC

TABLE 6.23

Synch Byte for a Request or for a Response Message

Bit	Name	Description
0–2	Synchronization type	000 = No synchronization 001 = Master Slave synchronization (Master) 010 = Master Slave synchronization (Slave) 011 = Cascaded synchronization
3	Action on "No Transponder"	0 = All responses sent to host 1 = "No transponder" responses not sent to host
4	Alternate Operation during continuous mode	0 = All valid data responses sent to host 1 = Identical responses sent to host only once
5	Reserved	
6	Reserved	
7	Reserved	

TABLE 6.24

Structure of Compound Messages

Length	Description
5 bytes	Frame
1 byte	Command
1 byte	Format
1 byte	Synch
≤ 4088 bytes	Message Data
2 bytes	Frame

TABLE 6.25

Format Byte for a Request Compound Message

Bit	Name	Description
0 (LSB)	Reserved	
1	Reserved	
2	Addressing	0 = Not addressed 1 = Addressed. Address contained in first 4 bytes of data field
3	Format	0 = Fixed format 1 = Variable format
4	Transmitter control	0= Turn transmitter off after executing command 1 = Leave transmitter on
5	Reserved	
6	Reserved	
7 (MSB)	Reserved	

© 2011 by Taylor and Francis Group, LLC

TABLE 6.26

Format Byte for a Response Compound Message

Bit	Name	Description
0 (LSB)	Error	0 = No error 1 = Error occurred. Status code is first byte of data field after any address information
1	Reserved	
2	Addressing	0 = Not addressed 1 = Addressed. Address contained in first 4 bytes of data field
3	Format	0 = Fixed format 1 = Variable format
4	Reserved	
5	Reserved	
6	Reserved	
7 (MSB)	Reserved	

TABLE 6.27

Structure of Ancillary Messages

Length	Description
5 bytes	Frame
1 byte	Command
≤ 4090 bytes	Message Data
2 bytes	Frame

Note: Because this type of command does not involve communication with the transponder, it does not require the format or sync bytes present in the other types of messages. The last two bytes contain the BCC code of either CRC or LRC. This is performed over all the preceding data with the exception of the start-of-frame byte.

The description of the synchronization bit is the same as for single messages that was shown in Table 6.23. The structure of ancillary messages is shown in Table 6.27.

The method of flow control demands for each request to receive a response. The flags in the response message indicate the presence of an error or other exceptions. After a certain time without receiving a response, the request can time out. The control is done by the host that acts as the primary station. Data lengths are variable for each message, although the maximum data length in a single message is 4091 bytes.

© 2011 by Taylor and Francis Group, LLC

7

The Air Communication Link

CONTENTS

7.1 Communication Protocols 178
  7.1.1 Communication Protocols for Systems Operating in the LF and HF Ranges 178
  7.1.2 Communication Protocols for Systems Operating in the UHF Range 181
7.2 The Communications Link 184
  7.2.1 Elements of the Communications Link 184
  7.2.2 Forward Link 186
  7.2.3 Return Link 189
7.3 Transponder Operating Modes 191
  7.3.1 Transponders Operating in the LF and HF Bands 191
  7.3.2 Transponders Operating in the UHF Bands 193
7.4 Arbitration for Transponders 196
  7.4.1 Principles of Arbitration 196
  7.4.2 Principles of Anticollision 197
  7.4.3 Deterministic Anticollision Procedures 199
  7.4.4 Aloha-Based Anticollision Procedures 200

This chapter describes the communication methods used to transfer information from the interrogator to the transponder and from the transponder to the interrogator. The communication from interrogator to transponder is usually known as the *forward communications link*. This consists mostly of commands sent from the host computer to the transponder via the interrogator. It also contains the data to be written for those transponders whose memories can be rewritten. The communication from transponder to interrogator is known as the *return link* or the *backscattered communication*. This consists mostly of the transmission of the data stored in the transponder's memory.

While there are several standards that specify the critical elements of the communications protocol, the implementation of these standards especially varies not only among different manufacturers but also among different products from the same manufacturers. Therefore, this chapter does not pretend to be a comprehensive collection of all the air communication methods employed by RFID systems. Instead, this chapter explores the most common

© 2011 by Taylor and Francis Group, LLC

approaches to the communication between these elements of the RFID system using specific systems as general examples. This should give the readers the basic information while preparing them to search for more specific details if they so require.

This chapter starts by describing the different air communication protocols followed by the study of the elements that make up the forward and the return communications link. It continues by talking about the different modes of operation available to transponders. The last section in this chapter describes the different arbitration methods and the anticollision procedures that allow effective communication when there is more than a single transponder in the radiofrequency field.

7.1 Communication Protocols

7.1.1 Communication Protocols for Systems Operating in the LF and HF Ranges

The T5557 is a transponder with a 300-bit memory manufactured by Atmel® that operates in the low-frequency range and is similar to other transponders from different families of manufacturers. The communication between transponder and interrogators starts with the chip in the transponder being initialized after it has reached its threshold voltage. Afterward, the chip will be ready or will experience an additional delay of 67 ms depending on the status of one of its configuration bits. In read mode, the data from the memory are transmitted serially by modulating the load across the antenna terminals, starting with bit 1 from block 1. This process continues until the last bit from the specified number of blocks has been transmitted. The number of blocks to be read is defined by one of the bits in the transmitted command.

The transmission from the transponder to the interrogator uses amplitude-shift keying (ASK) modulation by switching a load connected to the antenna terminals on and off. Figure 7.1 shows the waveform across the load for different types of coding.

The transponder has the ability to insert a special pattern in order to synchronize the interrogator before transmitting the first block. This pattern consists of four bit periods in which the modulation is turned off and on, as shown in Figure 7.2.

In order to write data to the transponders, the interrogator uses on-off keying. It interrupts on and off the electromagnetic field generated as shown in Figure 7.3. The time between the gaps is used to encode the data to be transmitted: 24 periods of the RF field for a *0* and 54 periods of the RF field for a *1*. The process finishes after the transponder has detected that there is no gap

© 2011 by Taylor and Francis Group, LLC


Manchester
Biphase
Anticollision Dual Pattern
Symbol '0'
Symbol '1'
or
or
T_d

FIGURE 7.1
Waveforms across load for different types of coding.


Data
Manchester
FSK

FIGURE 7.2
Synchronization patterns for Manchester and frequency-shift keying (FSK) modulations.


Read Mode
Write Mode
10 to 50
clock cycles
8 to 30 clock cycles
'1': 48 to 63 clock cycles
'0': 16 to 31 clock cycles

FIGURE 7.3
Gap sequences used in data transmission.

© 2011 by Taylor and Francis Group, LLC

for more than 64 periods. The initial gap triggers the communication from the interrogator to the transponder. This initial gap can be accepted at any time after the system has been initialized.

After the initial gap, the transponder expects to receive a valid command sequence. A standard write command needs the operation code, the lock bit, the 32 bits that make up the data, and the 3-bit address. Writing to a protected transponder requires the additional 32-bit password that is placed between the operation code and the data address bits. The password bits are compared bit by bit with the contents of the password stored in memory. If the bits do not match, the transponder returns to read mode. The complete writing process is shown in Figure 7.4.

After all the information has been correctly received, the transponder can be programmed. There is, however, a delay of one clock period between the end of the writing sequence and the start of the programming. The typical programming time is 5.6 ms, including the reading for data verification. Figure 7.5 displays the voltage measured across the antenna after programming a memory block.

For the Tag-it™ family of transponders manufactured by Texas Instruments, the communication between interrogator and transponder is done by amplitude modulation of the carrier. This allows the interrogator to generate enough energy to power the chips on board the transponders while simultaneously sending data. The encoding for the logic symbols *1* and *0* is done



FIGURE 7.4
Writing sequence.


Write
Programming and Data Verification
Read Programmed Memory Block
POR
Read
...
...
...
...

FIGURE 7.5
Voltage across antenna terminals after programming a block.

© 2011 by Taylor and Francis Group, LLC

by pulse width modulation: *1* is encoded as a power burst lasting 150 μs, while *0* is encoded by power bursts lasting 100 μs. Data are framed between a start-of-frame (SOF) signal and end-of-frame (EOF) signal. SOF consists of a 50 μs burst followed by a standard duration pulse, terminating with a 150 μs pulse. The EOF signal consists of a 50 μs burst followed by a standard duration pulse, terminating with a 100 μs pulse.

The communication between the transponder and the interrogator uses the modulation of the antenna as it tunes and detunes the signal to generate the backscattered information. The signals being transmitted are encoded using a Manchester code, taking advantage of the clock frequency being embedded in the transmitted signal. With the load modulation, a Manchester high level is represented by a frequency of 423.75 kHz, while a Manchester low level is represented by a frequency of 484.29 kHz.

7.1.2 Communication Protocols for Systems Operating in the UHF Range

Transponders operating in the UHF range manufactured by Atmel® are based on the *interrogator talks first* (ITF) approach to establish communication with the interrogator. The communication always starts with a forward message, that is, a message from the interrogator to the transponder. After receiving this initial message, the transponder responds by backscattering a message to the interrogator. This is known as the *return link*. This backscatter communication is done using a binary phase-shift keying (2PSK) modulation based on changing the imaginary part of the input impedance in the transponder as a function of the message between sent.

The communication is based on a system of frames, as shown in Figure 7.6. The first frame is the header frame that is used to adjust the timing. The second frame is the data frame that is used to transport the data. The length of this frame depends on the command sent and the addressing mechanism being used. The last frame is the end-of-transmission (EOT) frame that marks the end of the transmission. Once the transmission has finished, the interrogator enters into listening mode after having received another header frame.

While the interrogator is transmitting data, the transponder remains in listening mode. During the transmission of the interrogator header frame, it is possible for the transponder to operate in full duplex. It transmits data back to the interrogator in a loop until the EOF frame is sent.



FIGURE 7.6
Frame communications during default transmissions.

© 2011 by Taylor and Francis Group, LLC

The communication between transponder and interrogator must be reliable even in the noisy environments in which these systems normally operate. To improve the reliability of the communication link, the interrogator transmits periodic clock ticks to the transponders, ensuring reliability because it helps to block other radiofrequency sources. In addition, the link between transponder and interrogator operates synchronously, and because the interrogator controls the speed and modulation ticks, the resulting transmission has a higher signal-to-noise ratio than an asynchronous communication.

The general structure of the frames is different between the forward or return link as well as the type of commands that it carries. All the frames start with a header frame. The data frame in the forward link depends on the type of command carried, as shown in Figure 7.7, which shows frames for different types of commands. Data frames contain the command and its cyclic redundancy check (CRC), data-setting parameters, address information, and data for programming. For example, short commands consist of 6 bits and its 2-bit CRC, while long commands consist at least of the command fame, the CRC, and the parameter field. In the transmission of a long command, these frames are followed by a CRC frame of 16 bits. The transmission ends with an end-of-transmission frame that is made of two EOF symbols.

Figure 7.8 shows the general structure for the return link frames. The communication link starts with a header frame that is used to obtain reference symbols, adjust modulation, and set the timing for the EOF characters. This is followed by a data frame, a CRC frame 16 bits long, and an


Header
Command
CRC
48 bits: Parameter, address, and programming data
CRC
EOT
Header
Command
CRC
40 bits: Parameter and programming data
CRC
EOT
Header
Command
CRC
Parameter
CRC
EOT

FIGURE 7.7
Examples of data frames in a forward link.


EOT
Silent Frame
Header
Data
CRC
EOT

FIGURE 7.8
General structure for return link frames.

© 2011 by Taylor and Francis Group, LLC

end-of-transmission frame. The data frame can have a length of 8 or 16 bits depending on the type of data carried. The silent frame shown in Figure 7.8 is only used during programming. During the silent frame period, the interrogator only transmits a continuous wave. The length of this period depends on the strength of the electromagnetic field.

The general structure of the communications flow for these transponders is shown in Figure 7.9. The transponder is continuously waiting for a notch indicating the presence of the external field. After it has been received, it will check for a valid header frame that indicates the beginning of a transmission. After the header frame has been received correctly, the transponder performs several additional verifications while transmitting the different parts of the message, including checking for the anticollision requests. The process ends after receiving the EOF data.


Init
Wait for notch
Check header
Not valid header
New command
Receive data
Not valid data
Program
Receive return header
Wait on notch for carrier
Set subcarrier
Backscat-tered
Anti-collision
Back data & CRC
Set status
EOT

FIGURE 7.9
General structure of communications flow.

© 2011 by Taylor and Francis Group, LLC

7.2 The Communications Link

7.2.1 Elements of the Communications Link

Because the transponder is powered by the electromagnetic field generated by the interrogator, it must measure the strength of this field continuously. If the strength of the field decreases in such a way that causes the voltage after the rectifier to be lower than a certain threshold, the circuits in the transponder activate an internal reset. For voltages higher than this threshold, the oscillator and the rest of the circuits in the transponder circuit are enabled. Figure 7.10 shows the time events between the different signals involved after the transponder is turned on for some transponders manufactured by Atmel®.

The duration of the power on reset (POR) period depends on how fast the signal ramps up. This in turn depends on the strength of the electromagnetic field. After the POR has executed, there is an additional waiting period called the *band gap* that is needed for stabilization of the rest of the internal circuits before the signal to enable the oscillator switches its state. Finally, there is a delay of 64 clock cycles (approximately 160 µs) before the oscillator in the transponder achieves operational status.



FIGURE 7.10
Chronogram of signals during power up.

© 2011 by Taylor and Francis Group, LLC

When the electromagnetic field decreases, the voltage after the internal rectifier also decreases. Once it reaches a certain threshold level, the oscillator stops. This results in lowering the current required by the circuit that in turn results in the voltage supply decreasing with a lower slope as shown in Figure 7.11. Finally, if the voltage decreases below another threshold, the circuit executes a reset. The difference between the two voltage levels allows for taking into account variations in the strength of the field without having to execute a reset.

The communication between transponder and interrogator normally happens in a noisy environment. Therefore, the designers of the system must ensure bit error rates as low as possible. This is achieved by using a combination of several techniques including generating notches in the system clock, making the return link synchronous to notch signals generated by the interrogator, using different coding techniques, and using CRC to protect the integrity of the data. CRCs for commands are 2 bits long, while CRCs for data are 16 bits long. Figure 7.12 shows the concept of notch timing, which results from generating notches at periodic intervals in the signal generated. For a typical value of signal level between 450 mV and 600 mV, T_1 lasts 4 μs and T_{notch} lasts 2 μs.

Other techniques include using *pulse interval encoding* to define the symbols *1* and *0*, whose timing and timing differences are controlled by the interrogator as an additional element to increase the robustness of the link. The fact that the return link is synchronous to the interrogator allows it to close the communication as soon as it detects a transmission error.

The communication from the interrogator to the transponder is known as the *forward link*, while the communication from the transponder back to the interrogator is known as the *return link*. The forward link carries the different type of commands to the transponder, while the return link carries the data from the transponder to the interrogator. These data will only be available for those commands that require the return of data. Because the



FIGURE 7.11
Chronogram of signals during power down.

© 2011 by Taylor and Francis Group, LLC



FIGURE 7.12
Notch timing chronogram.

handover mechanism from the forward to the return link happens synchronously, there is no need to wait for a cycle between them. Once the forward link sends its last frame that consists of an end-of-transmission message, the transponder is ready to transmit its return link header.

Texas Instruments RFID systems operating at low frequency use a frequency of 134.2 kHz to encode a low bit and a frequency of 123.2 kHz to encode a high bit. Because each bit uses 16 radiofrequency cycles to transmit, the duration of a low bit is different from the duration of a high bit. The low bit needs 119.9 µs to transmit, while a high bit needs 129.2 µs. The interrogator sends information to the transponder to transfer commands, addresses, or data. The writing process is always initiated by turning the radiofrequency transmitter on for a period of time of up to 50 ms. Afterward, the interrogator starts sending the bits that make up the command and associated data. Write bits last 2 ms. The differentiation between high and low bits is based on the duty cycle for each one of these bits. As shown in Figure 7.13, a high bit has a duty cycle approximately equal to 50%, while the low bit has a duty cycle approximately equal to 20%. The program phase consists of a continuous radiofrequency field for the duration of this period.

7.2.2 Forward Link

The forward header in most Atmel® transponders has four symbols, as shown in Figure 7.14. This header is accepted by the transponder if the length of the symbols *check1* and *EOF** is larger than the length of the symbol *0**.

Figure 7.15 shows that the information being transmitted is encoded in the timing between pulses. After the frame has been accepted and the

© 2011 by Taylor and Francis Group, LLC


Write
Program
High bit
Low bit
RF transmitter ON
RF transmitter OFF
...

FIGURE 7.13
Write and program signals.


Clock control
0*
Check1
EOF*

FIGURE 7.14
The four symbols in the forward header.


Reference pulses
0*
EOF*
Data pulses
Symbol '0'
Symbol '1'
Symbol EOF

FIGURE 7.15
Pulse timing used to encode information.

© 2011 by Taylor and Francis Group, LLC

interrogator transmits data, the transponder measures the time between two pulses or notch signals. This is used by the transponder to decide whether the received symbol is a *0* or a *1* by comparing its length with the length of the symbols *0** and *EOF**, as shown in Figure 7.15.

This figure shows that a symbol will be interpreted as a *0* if its timing is shorter than the time that was sent in the Header for the symbol *0**. A symbol will be interpreted as a *1* if the time used by that symbol is longer than for the symbol *0** but shorter than the time used in the header for the symbol *EOF**. Finally, EOF will be interpreted for a symbol that lasts longer than the *EOF** symbol. This approach increases the reliability of the link as the transponder does not have to measure absolute but relative time intervals.

The communication from the interrogator to the transponder for the Series 2000 Texas Instruments RFID systems is based on transmitting bursts of energy of specific duration at specific intervals. For example, the commands used to read read-only or read/write transponders consist of an initial power burst lasting 50 ms followed by a period of 20 ms in which the radiofrequency field is turned off. In fact, all these transponders use the 50 ms power burst as the initial identifier for an upcoming command in addition to providing the energy to power the transponder. The following are some examples of formats for the different commands supported by these transponders. Figure 7.16 shows the protocol to transmit the command used to program a rewritable transponder.

The command starts with the 50 ms power burst followed by the specific command keyword and the password if necessary. These are followed by the 80 data bits used by this family of transponders and the 16 bits that make up the write frame. The last information being sent is the PBII, after which the transponder will read the new data stored in its memory to be verified by the interrogator. Figures 7.17 and 7.18 show the communication protocols for the commands *lock page* (of multipage transponders) and *selective read page* (of multipage transponders), respectively.



FIGURE 7.16
Protocol used to transmit a command to program a rewritable transponder.

© 2011 by Taylor and Francis Group, LLC


24 bits
8 bits
16 bits
128 bits
RF transmitter ON
RF transmitter OFF
Power burst 50 ms
Write address 16 ms
Write frame BCC 32 ms
PBII 15 ms
Read/ discharge 20 ms
133 ms

FIGURE 7.17
Protocol for the *lock page* command.


8 bits
8 to 32 bits
16 bits
128 bits
RF transmitter ON
RF transmitter OFF
Power burst 50 ms
Write address 16 ms
Selective address 16 to 64 ms
Write frame BCC 32 ms
Read/ discharge 20 ms
1334 to 182 ms

FIGURE 7.18
Protocol for the *selective read page* command.

7.2.3 Return Link

The return link in the majority of Atmel® transponders uses synchronous communication and angular modulation (binary PSK) in order to increase the signal-to-noise ratio and reduce the bit error rates because the return signals have extremely low power values. The synchronicity occurs as the transponder transmits its signal between two notches from the signal generated by the interrogator.

The return link starts with the return link header that is used to provide the timing information for the signal similar to the forward link header. Figure 7.19 shows the structure of the return link header for different types of coding styles used for the communication. In any case, the return link header always contains four symbols. The function and structure of each one of these symbols are shown in Table 7.1.

The return link header waits for a notch in the radiofrequency field generated by the interrogator before starting the generation of the reference timing. The data in the return link can be encoded using any of these coding techniques: bit stream (raw data), notch-locked non-return-to-zero-inverted (NRZI) encoding, soft-locked NRZI, FM0, and 3phase1. The EOT frame contains two EOF symbols.

© 2011 by Taylor and Francis Group, LLC



FIGURE 7.19
Structure of the return link header for different coding styles.

TABLE 7.1
Function of the Symbols in the Return Link Header

Symbol	Function	Additional Comments
1st	Main timing and power management	Used by interrogator to affect transmission rate of return link
2nd	Timing Reference	Used for anticollision control
3rd	Same timing as symbol 4	When using NIRZ, modulation is on
4th	Timing reference for EOF detection	

Figure 7.20 shows the transmission protocol used by the transponder to send information back to the interrogator as its response to a Read Data command for Texas Instruments transponders using their TIRIS protocol. All parts of this message are transmitted, with the least significant bit (LSB) being the first bit transmitted.

© 2011 by Taylor and Francis Group, LLC



FIGURE 7.20
Transponder data sent back to the interrogator.



FIGURE 7.21
Return link for a multipage transponder.

After transmitting the pre-bits and eight bits that specify the start sequence, the transponder sends the 80 bits stored in its memory. The 64 first bits are the data bits, while the following 16 bits are the block check code (BCC) used to ensure the integrity of the data. These are followed by the stop and end bits. In order to be ready for a new activation, the transponder finishes the process by discharging its internal capacitor at the end of the transmission. The same protocol is used for rewritable transponders. Figure 7.21 shows the return link when accessing a multipage transponder.

In this case, following the BCC data, the transponder transmits the read address. This consists of a 2-bit status field that provides information about the function that that transponder has executed and a 6-bit page field that provides information about the page that was affected by the execution. The data format ends with reading the frame block check character (FBCC).

7.3 Transponder Operating Modes

7.3.1 Transponders Operating in the LF and HF Bands

After the transponders are initialized, they can enter into two different states, *interrogator talks first* (ITF) or *public mode* or *electronic surveillance*, depending on the status of their operating mode flags. In ITF mode, the data stream received through modulation from the interrogator

© 2011 by Taylor and Francis Group, LLC

undergoes different verifications. If they all result in a valid status, the transponder is synchronized with the data stream. At that point, the transponder is ready for communication. This communication always starts with a forward message, which is a message from the interrogator to the transponder. This communication method is used in multitransponder applications due to its anticollision capabilities. In this mode of operation, the transponder can be in any of the following states: *power down*, *ready*, *selected*, or *quiet*.

When the transponder is not able to harvest enough energy from the surrounding electromagnetic field to energize its internal chip, it enters power down state. The transponder can also enter the ready state after having received a reset command. The transponder enters the selected mode after having received an explicit command with its own serial number from the interrogator. It is possible to set several transponders into the ready state by sending a specific command containing a matching partial identification number. It is necessary to set a transponder into the selected mode before being able to access it. The quit state is entered after a selected state after the interrogator selects another transponder or receives a specific command to enter this state.

Public mode communications start with the SOF pattern, which is followed by continuously streaming the data from the user memory. As shown in Figure 7.22, the first bit being sent is bit 31 from data block 0. When the transponder reaches its final data block, it starts transmitting data block 0 again. This process terminates when the electromagnetic field that energizes the transponder is turned off or when the transponder receives the appropriate command from the interrogator.

Electronic surveillance mode is a particular operating mode in which the transponders are attached to specific retail articles. By programming all bits in block 0 of the user memory to *0*, the transponder is set to an *unpaid state*. After the article has been purchased, the cash register sets the bits of block 0 to *1*, thus entering the *paid state*. Additional security can be achieved by protecting the bits of block 0 with a write password. If a transponder in the *unpaid state* enters the electromagnetic field generated by the interrogator located at the doors of the store, it will modulate the field. Consequently, the presence of a transponder marked in the *unpaid state* will be detected by the



FIGURE 7.22
Initial sequence for the public mode.

© 2011 by Taylor and Francis Group, LLC



FIGURE 7.23
Signals from the transponder in electronic surveillance mode: (a) article unpaid, and (b) article paid.

interrogator, triggering the appropriate alarms. Conversely, a transponder marked as being in the *paid state* will not alter the electromagnetic field and will be transparent to the interrogator. Figure 7.23 shows the signals for these two cases.

Figure 7.24 shows the relationships between the different states for the transponders depending on their operational mode.

7.3.2 Transponders Operating in the UHF Bands

The possible states for the transponders manufactured by Atmel® operating in the UHF band are RF Field OFF, RF Field ON, Start, Mute, Observe, Ready, Active, and Isolated. These states and the paths between them are shown in Figure 7.25 and discussed here.

- The initial state is the *RF Field Off* state. Here, the transponder is not able to operate because there is no external radiofrequency field for which it can draw power. The transponder is able to store some configuration information for about 8 seconds after the field has ceased. After this time, the contents of these registers become undefined.
- When the transponder enters a region with an existing radiofrequency field whose magnitude allows the transponder to power

© 2011 by Taylor and Francis Group, LLC


Power ON
(Public mode or EAS)
PM
ready
Power
down
Reset to
ready
Power ON
Ready
Reset to
ready
Reset to
ready
Quiet
Select
Selected

FIGURE 7.24
Different transponder states.


RF_on
RF_off
Isolated
Start
Mute
Observe
Active
Ready

FIGURE 7.25
Operational states for UHF transponders.

© 2011 by Taylor and Francis Group, LLC

its internal circuitry, this generates a power on reset. This is the *RF Field On* state. After the POR has occurred, the internal oscillator in the transponder is switched on. It is important to note that for this process to occur, the frequency of the external radiofrequency field must match the resonant frequency of the transponder's antenna and associated circuitry. Once this process has finished, the transponder moves into the *Start* state.

- In the *Start* state, the transponder refreshes the contents of the status registers and reads their configuration from its memory, enabling or disabling its trigger function. After this process, the transponder is able to detect the modulation ticks that signify information being sent from the interrogator. From this state, the transponder can move to the *Mute* state or to the *Observe* state.
- In the *Mute* state, the transponder cannot respond to operations such as programming, arbitration, or backscattering data. The transponder leaves the *Mute* state after some of its internal configuration registers have been modified.
- The *Observe* state allows the transponder to become synchronous with the interrogator for performing operations such as programming. To become synchronous the transponder checks that the forward header received from the interrogator is valid, that the command received is within the list of known commands, and that its CRC is also valid. If all these checks are passed successfully, the transponder moves to the *Ready* state.
- During the *Ready* state, the transponder receives the parameters associated with the type of commands sent by the interrogator. If any of the parameters are false, the transponder enters the *Mute* state. Otherwise, the transponder enters the *Active* state.
- In the *Active* state, the transponder is able to execute the command sent by the interrogator after receiving and checking the rest of the forward frame. If there are any errors in the information sent after the header frame, the transponder moves into an *Isolated* state or *Mute* state depending on the type of errors received. If the information sent in the forward frame is correct, the transponder executes the command. Once the transponder has finished the execution it moves back into the *Ready* state. Figure 7.26 shows with more detail the processes that occur during the *Active* state.
- The first step in this process is to verify the length of the received stream. If this is correct, the transponder checks for the validity of the position of the end-of-transmission frame. Depending on the result of this check, the transponder knows if the anticollision procedure has been activated in order to select that specific transponder. If this is the case, the transponder will enter the appropriate

© 2011 by Taylor and Francis Group, LLC


Ready
Observe
Length check
Check EOT
Check CRC
Receive data
Isolated
Wakeup slot
Program
Arbitration
Status2
Mute
Check loop
Return CRC
Ready
Read operations

FIGURE 7.26
Processes during the active state of transponders.

anticollision and arbitration procedures. The transponder can also enter into receiving wakeup commands or other types of commands sent by the interrogator.

- In the *Isolated* state, the transponder is isolated and waits for either a POR or reset command to leave this state.

7.4 Arbitration for Transponders

7.4.1 Principles of Arbitration

When there is more than one transponder immersed in the electromagnetic field generated by an interrogator, it is necessary to develop and establish a

© 2011 by Taylor and Francis Group, LLC

procedure to select a single transponder or a specific group of transponders for carrying out specific functions. Alternatively, it can also be necessary to isolate a specific transponder or a group of transponders so they do not disturb communications. In some applications it may also be interesting to know whether there are transponders in the field or not. All these functions require the use of arbitration procedures. The two main types of arbitration procedures are *deterministic arbitration procedures* and time-slot based procedures, also known as *aloha procedures*.

Deterministic procedures are based on a *tree-walking function* in which the interrogator acting as the control node uses the individual IDs of transponders to select one or a group of them. The interrogator starts by polling all the transponders in the field. If there is more than one, their responses will collide and the interrogator will not receive the message. Therefore, in the next step, the interrogator polls only a specific subgroup of transponders based on their IDs. If the responses also collide, the interrogator reduces the population by polling only a specific subgroup from the previous subgroup. This process is repeated until the interrogator receives a response from a single transponder.

Aloha procedures are controlled by slot commands. After the transponders are turned on, they calculate random values for as long as they are powered. Once the transponder has received a slot command, it creates a random number from its generator, which points to a slot number in the chip. After receiving a start command, the transponders transmit their information to the reader during the first slop. If the random number matches the first slot number, it calculates a new one during this slot. When the random number matches the slot number controlled by the interrogator, that transponder becomes active. This allows the transponder to communicate with the interrogator. If the numbers do not match, the transponder enters a mute state and therefore does not respond to any commands. When the transponder receives a new slot command, it calculates if it is supposed to be active or mute.

7.4.2 Principles of Anticollision

The aim of anticollision procedures is to detect and identify the transponders that are present within the range of the electromagnetic field generated by the interrogator. While the implementation of specific anticollision procedures may vary between manufacturer and models, the principles of anticollision are common to all of them. For transponders manufactured by Atmel®, the communication with a single transponder or a group of transponders is controlled by the interrogator. The arbitration is initiated by the interrogator issuing a command for the transponders to transmit their identification numbers. The command can be tailored to the transponders that the interrogator expects to be in its area of influence. If the interrogator does not know anything about the transponders that are expected to be, the command is general and the detection encompasses all transponders. Otherwise,

© 2011 by Taylor and Francis Group, LLC

the command can use parameters such as a partial transponder identification number that will cause only transponders with partially matching IDs to respond to the command.

After the interrogator receives responses from the transponders, it scans their ID number from the most significant to the least significant bits. Each time slot corresponds to a specific bit position in the ID number. Because all transponders respond simultaneously with their modulated signal, their responses will be superimposed on one another. Therefore, because of the modulation being used, a damped signal overwrites a nondamped signal. With this, a logical *1* prevails over a logical *0*. Consequently, the transponders with these ID numbers are removed from the process. When the interrogator detects a logical *1*, it responds by broadcasting a gap in the radiofrequency field. The detection of a logical *0* does not originate any response from the interrogator. The gap in the field that is created as a response to the logical *0* is monitored by the transponders in the field and deduces, by comparing their ID number to the gap that was just broadcasted, if that specific transponder should continue in the current anticollision loop or eliminate itself from it. The transponders that are eliminated are muted and return to the ready state, in which they will remain until the interrogator initiates a new anticollision loop.

The transponders that have not been eliminated remain in the current loop as long as the final bit of the identification number has not been reached yet, and the process repeats itself. By the time the last bit has been interrogated, there will be a single transponder active as all the other transponders will have been eliminated through the previous steps. At this point, the interrogator is able to identify the associated ID for that specific transponder, and the transponder enters into the Selected state. Now, the transponder can establish direct communication with the interrogator and can be read or written. The transponder remains in the Selected state until the interrogator starts a new anticollision loop.

The MCRF450 family of transponders manufactured by Microchip Technology also supports anticollision. Their algorithm is based on time division multiplexing the transponder responses in which each transponder is only allowed to communicate with the interrogator during its time slot. This algorithm contains four control loops: Detection, Processing, Sleeping, and Reactivation.

The control of these loops is done by five commands as well as the transponder internal flag bits. The commands that control the anticollision loops are as follows:

- *Fast read request (FRR).* With an internal flag set, the transponder will respond only to an FRR command. An FFR command consists of five timed gap pulses, as shown in Figure 7.27, in which the period of the gap contains specific information. There are a total of nine possible pulse positions allowed in this protocol.

© 2011 by Taylor and Francis Group, LLC



FIGURE 7.27
Structure of a fast read request (FRR).

- *Fast read bypass (FRB).* This command is used in the reactivation loop. Upon reception of this command, the transponder responds with a block of data. The structure of this command is similar to the FRR command, with the difference being in the period of the gaps.
- *Matching code 1 (MC1).* This command is used with the transponder and does not require any further processing. The command consists of time calibration pulses and pulse position modulation (PPM) signals. Upon the reception of this command, a transponder in the detection loops enters the sleeping loop.
- *Matching code 2 (MC2).* When a transponder in the detection loop receives this command, it enters the processing loop. The structure of this command is similar to that of MC1.
- *End process (EP).* This command causes a transponder in the processing loop to exit it and enter the sleeping loop.

Transponders can enter the detection loop by waiting for an FFR command or by transmitting a fast read (FR) response without waiting for a command. The first operation mode is called *interrogator talks first* (ITF), while the second operation mode is called *tag talks first* (TTF). The read and write operations are carried out during the processing loop. Only transponders with a special flag set in this loop respond to write or read operations. The sleeping loop is used to keep all processed devices in a silent condition in which they do not respond to external commands. The reactivation loop is used as an intermediate step by the interrogator to set transponders into different loops depending on the command that is transmitted to transponders in this loop.

7.4.3 Deterministic Anticollision Procedures

Deterministic anticollision procedures are based on the transponder backscattering the information to the interrogator only if the result of a compare condition is true. The compare condition is set up by the interrogator while broadcasting a specific command. Deterministic anticollision procedures are also called tree-based procedures. The interrogator sends a series of queries, each one with a prefix that is part of the transponder's ID code. Only those transponders with matching IDs respond to the interrogator's query. If there is more than one transponder with matching partial IDs, these transponders respond at the same time

© 2011 by Taylor and Francis Group, LLC

and their messages collide. The interrogator recognizes the collision of messages as the existence of more than one transponder with the prefix that was sent. At this point, the interrogator further refines its prefix, making it one bit longer, and the process repeats itself. Because all the transponders have different IDs, there will be a point at which only one transponder will respond to the query. This uniquely identifies the transponder that responds to the specific prefix.

Example 7.1:

Assume three transponders are in the read region of an interrogator with the following IDs. Explain the deterministic anticollision process.

Transponder 1: 1111
Transponder 2: 1101
Transponder 3: 0010

Solution:

Let's assume that the interrogator starts its process by broadcasting the prefix *0*. Upon receiving this query, only transponder 3 responds because the first bits of transponders 1 and 2 do not match the prefix broadcasted. Because the interrogator receives a message from a transponder that has not collided with messages from other transponders, it uniquely identifies transponder 3 as being the only transponder in the field with an ID that starts with *0*.

Let's assume now that the interrogator starts its process by broadcasting the prefix *1*. Upon receiving this query, transponder 1 and transponder 2 respond, and therefore their responses collide. The interrogator then knows that there is more than a single transponder with an ID number starting with *1*. The interrogator proceeds to refine its query by increasing the original prefix by one bit, broadcasting the new prefix as *10*. Upon receiving this query, none of the transponders responds. This indicates to the interrogator that none of the transponders that had collided with the message *1* collides now. Therefore, the IDs of the transponders must contain the prefix *11*. The interrogator continues by increasing the length of the prefix, now to *110*. After receiving this query, only transponder 2 responds, and thus is uniquely identified.

This process does not require transponders with memory other than the memory used to store their ID numbers. This makes it an attractive protocol when used with low-cost transponders.

7.4.4 Aloha-Based Anticollision Procedures

Aloha-based procedures are based on a slot mechanism. In its most basic form, this mechanism starts working when the transponder calculates a slot out of 32 possible slots based on a random number. Within each slot, a transponder can communicate with the interrogator only if the calculated slot value is the same as the slot number that is under the interrogator's control. Figure 7.28 depicts the algorithm used in the most basic aloha protocol for anticollision.

© 2011 by Taylor and Francis Group, LLC


Start Aloha
Start counter random
Slot = random?
No
Yes
Mute wait on specific commands
Send ID wait cmd next random
Repeat?
Yes
No
Action
Wait next command
End Aloha?
Yes
No
Set ID
New slot?
No
Yes
Slot = 1?
Yes
No
Set ID
Close slot?
No
Yes
Increment slot
End Aloha

FIGURE 7.28
Structure of the basic aloha algorithm.

© 2011 by Taylor and Francis Group, LLC

After a transponder receives a slot command, it broadcasts the random value as well as the contents of its identification number. The identification number is also broadcasted if the slot number is the same as the number transmitted by the reader and the transponder was selected previously. The slot is then incremented by one repeating the process.

Aloha procedures can be further divided into three versions: slotted aloha, framed slotted aloha, and dynamic framed slotted aloha. Slotted aloha follows the procedure described earlier. That is, the time is divided into several slots and transponders can only transmit data during the time slot they have selected. Framed slotted aloha is a variation of the basic slotted aloha. Here, one frame consists of several slots and the transponder chooses one slot in the frame to transmit data. The interrogator decides the size of the frame. This size remains constant during the process. Transponders generate a random number that is used to select a slot in a frame. Because the interrogator identifies transponders with multiple frames, it can identify the diverse transponders. The process for dynamic framed slotted aloha is similar, although in this variant the size of the frame is variable. This results in a more efficient algorithm for identifying transponders.

© 2011 by Taylor and Francis Group, LLC

8

Commands for Transponders

CONTENTS

8.1 Commands in the Texas Instruments Series 2000 Systems.................204
    8.1.1 Commands Supported by the TIRIS Bus Protocol....................204
    8.1.2 Commands Supported by the ASCII Bus Protocol...................209
8.2 Commands for Texas Instruments High-Frequency Interrogators.... 214
    8.2.1 Commands Supported by the TIRIS Protocol for Series 6000 Interrogators.. 214
    8.2.2 Commands Supported by HF Tag-It Transponders..................220
8.3 Command Supported by Texas Instruments Series 4000 Multifunction Interrogators...229
    8.3.1 Commands Supported by Tag-it Transponders 230
    8.3.2 Commands Supported by the ISO 14443 Protocol....................235
8.4 Commands for the Texas Instruments UHF Gen 2 Protocol...............235
8.5 Commands Supported by the Atmel® Family of Transponders.........246
    8.5.1 Commands Supported by LF Atmel® Transponders................246
    8.5.2 Commands Supported by HF Atmel® Transponders...............247
    8.5.3 Commands Supported by UHF Atmel® Transponders............247

The communication from interrogators to transponders consists mostly in the interrogators issuing commands to be executed by the transponders. After the transponders have received the commands, they transmit information back to the interrogator. This information can be the requested data, status of their internal parameters, acknowledgment flags, or error codes.

This chapter explores the structure and configuration of commands for transponders as well as the different status and error messages transmitted by the transponders as response to these commands. Because of the diversity in the number of transponders in the market, this chapter focuses on describing the commands in representative examples of transponders. This will give the reader enough information to understand the structure of commands used in other types of transponders. This chapter starts by describing the commands in the Series 2000 systems from Texas Instruments that operate in the low-frequency (LF) band. It continues by studying the commands used in diverse transponders from Texas Instruments operating in the high-frequency (HF) band. The third section describes the commands supported in the Series 4000 interrogators from Texas Instruments that can operate in the LF and HF bands. The next section describes the commands used by the transponders from Texas Instruments operating in the ultra-high-frequency (UHF) band.

© 2011 by Taylor and Francis Group, LLC

Finally, the last section in this chapter is focused on the commands used by transponders manufactured by Atmel® in the different frequency ranges.

8.1 Commands in the Texas Instruments Series 2000 Systems

8.1.1 Commands Supported by the TIRIS Bus Protocol

The commands supported by the TIRIS Bus Protocol can be divided into four different types of commands:

Group 0: These commands are generally used to control the queue of the message traffic. They have codes $00 to $1F.

Group 1: These commands typically result in reading or writing the RFID transponders. They have codes $20 to $3F.

Group 2: These commands set up parameters in registers that execute auxiliary input/output functions. They have codes $40 to $5F.

Group 3: These commands are for user add-on tasks. They have codes $60 to $7F.

Table 8.1 describes the commands in Group 0. It is necessary to note that although the protocol can support 32 different commands, there are only five commands actually implemented. All these commands operate as *immediate commands.*

TABLE 8.1

TIRIS Bus protocol Group 0 commands

Command Number	Description
$00[a]	Send count of records
$01[b]	Send next record from queue
$02[c]	Send record *N* from queue
$03[d]	Resend last record
$04[e]	Clear queue
$05	Reserved
…	…
$1F	*Reserved*

[a] Command $00 (*Send count of records*) returns the number of records that are buffered in the queue. This command does not require one to pass any additional data or parameters. The response is stored as an unsigned character.

[b] Command $01 (*Send next record from queue*) returns the next message that is buffered in the queue. This command does not require data either.

[c] Command $02 (*Send record* N *from queue*) returns the *N*th message from the queue. This command requires the value *N* as its data argument. The response is stored in a record.

[d] Command $03 (*Resend last record*) resends the last sent message. This command does not require any data, nor does it produce data as response.

[e] Command $04 (*Clear queue*) clears all the messages buffered in the queue. The command does not require any data, nor does it produce data as response.

© 2011 by Taylor and Francis Group, LLC

TABLE 8.2

TIRIS Bus Protocol Group 1 Commands

Command Number	Description
\$20[a]	Charge only read
\$21[b]	Read page *N*
\$22[c]	Read page *N* (80 bit)
\$23[d]	Selective read
\$24	Reserved
\$25	Reserved
\$26	Reserved
\$27	Reserved
\$28	Reserved
\$29	Reserved
\$2A	Reserved
\$2B[e]	Program 64 bit
\$2C[f]	Program page *N*
\$2D[g]	Program page *N* (80 bit)
\$2E[h]	Selective program
\$2F[i]	Program 80 bit to read/write transponder
\$30	Reserved
\$31	Reserved
\$32[j]	Lock page *N*
\$33[k]	Lock page *N* (SAMPT)
\$34	Reserved
…	…
\$3F	Reserved

[a] Command \$20 (*Charge-only read*) performs a single charge-only read. Its execution does not require any parameters. The response contains a status code and a data field whose length is variable depending on the status code. The meaning of the different status codes is shown in Table 8.3. A data field length equal to 1 corresponds to one of the following status codes:
NO_READ
INCOMPLETE
MPTRERR_SPC_DATA
MPTRERR_STATUS

A data field length equal to 9 corresponds to the following status codes, with the data fields 1 to 8 containing the ID of the transponder being read:
RO_TRP
RW_TRP
MPTCOTRP_U
MPTCOTRP_L

The meaning of the different status codes is shown in Table 8.3.

[b] Command \$21 (*Read page* N) performs a single read of the specified page (*N* page) in a multi-page transponder. This command needs to have the number of the page to read as a parameter. This parameter can range from \$01 to \$3F. The response contains a data field of variable length depending on the different status codes. A data field length equal to 1 corresponds to the same status codes as Command \$20. A data field length equal to 9 corresponds to the following status codes, with the data fields 1 to 8 containing the ID of the transponder being read:

(*Continued*)

© 2011 by Taylor and Francis Group, LLC

TABLE 8.2 (CONTINUED)

TIRIS Bus Protocol Group 1 Commands

RO_TRP
RW_TRP

A data field length equal to 10 corresponds to the following status codes. Here, data fields 1 to 8 contain the ID of the transponder and data field 9 contains the read page number:

MPTRP_U
MPTRP_L
MPTRERR_PAGE_U
MPTRERR_PAGE_L

[c] Command $22 (*Read Page* N *[80 bit]*) performs a single read of the specified page in a multipage transponder with 80 bits. It needs a parameter that specifies the page to be read. The response contains a data field of variable length depending on the different status codes. A data field length equal to 1 corresponds to the same status codes as Command $20. A data field length equal to 11 corresponds to the following status codes, with the data fields 1 to 10 containing the ID of the transponder being read:

RO_TRP
RW_TRP
RO_TRP_80
RW_TRP_80

A data field equal to 11 corresponds to the following status codes. Data fields 1 to 10 contain the ID of the transponder being read, while data field 11 contains the read page number:

MPTRP_U
MPTRP_L
MPTRERR_PAGE_U
MPTRERR_PAGE_L
MPTRP_80_U
MPTRP_80_L

[d] Command $23 (*Selective read*) performs a selective read of a specified page in a multipage transponder. It needs the following three parameters: the type of transponder to read, the page to read, and the address within the page. The response contains a data field of variable length depending on the different status codes. A data field length equal to 1 corresponds to the same status codes as Command $20. A data field length equal to 9 corresponds to the following status codes, with the data fields 1 to 8 containing the ID of the transponder being read:

RO_TRP
RW_TRP

A data field length equal to 10 corresponds to the following codes, with data fields 1 to 8 containing the ID of the transponder being read and data field 9 containing the number of the page:

MPTRP_U
MPTRP_L
MPTRERR_PAGE_U
MPTRERR_PAGE_L

[e] Command $2B *(Program 64-bit transponder*) writes a 64-bit ID into a read/write transponder. It needs a parameter with the information to write. The response always has a data field equal to 1 with the following possible status codes:

PROG_OK
PERR_FALSE_ID
NO_READ
INCOMPLETE
RO_TRP

© 2011 by Taylor and Francis Group, LLC

TABLE 8.2 (CONTINUED)

TIRIS Bus Protocol Group 1 Commands

---

[f] Command $2C (*Program page* N) performs a write in the *N*th page of a multipage transponder. It needs two parameters: the page to write and the 64-bit data to write in the transponder. The response always has a data field equal to 1 with the following possible status codes:
PROG_OK
PERR_FALSE_ID
NO_READ
INCOMPLETE
MPTPRERR_STATUS
MPTPERR_UNREL
MPTERR_PAGE_U
MPTERR_PAGE_L
MPTPERR_SPC_DATA
MPTPERR_LOW_VOLT
MPTPERR_LOCK
RO_TRP
RW_TRP

[g] Command $2D (*Program page N [80 bit]*) performs a write in the *N*th page of a multipage transponder. It needs two parameters: the page to write and the 64-bit data to write in the transponder. The response always has a data field equal to 1 with the same status codes as Command $2C.

[h] Command $2E (*Selective programming*) performs a selective write into the *N*th page of a multipage transponder. It needs four parameters: the type of multipage transponder, the page number to write to, the address, and the ID of the transponder. The response always has a data field equal to 1 with the same status codes as Command $2C.

[i] Command $2F (*Program 80-bit data to transponder*) writes 80-bit data into a read/write transponder. It requires the 80-bit data to write as parameter. The response always has a data field length equal to 1 with the same status codes as for Command $2B.

[j] Command $32 (*Lock Page* N) locks the specified page in a multipage transponder. It requires the page number as a parameter. The response always has a data field length equal to 1 with the following status codes:
MPTLERR_FS_DROP
MPTLERR_UNREL
MPTLERR_STATUS
MPTLERR_PAGE_U
MPTLERR_PAGE_L
RO_TRP
RO_TRP

[k] Command $33 (*Selective lock page* N) performs a selective lock of the specified page in a multipage transponder. It requires the following three parameters: the type of multipage transponder, the page to be locked, and the address. The response always has a data field length equal to 1 with the same status codes as Command $32.

© 2011 by Taylor and Francis Group, LLC

TABLE 8.3

Status Code Name and Description for Results of Group 1 Commands

Status Code Value	Status Code Name	Status Code Description
$00	RO_TRP	Read Only transponder successfully read
$01	RW_TRP	Read/Write transponder successfully read
$02	MPTCOTRP_U	Successful read of unlocked page 1 in a Multipage transponder as a result of charge-only read
$03	MPTCOTRP_L	Successful read of locked page 1 in a Multipage transponder as a result of charge-only read
$04	MPTRP_U	Successful read of an unlocked page of a Multipage transponder as a result of a read command
$05	MPTRP_L	Successful read of a locked page of a Multipage transponder as a result of a read command
$06	MPTRP_80_U	Successful read of an unlocked page of Multipage transponder as a result of a read command in 80 bit mode
$07	MPTRP_80_L	Successful read of a locked page of Multipage transponder as a result of a read command in 80 bit mode
$08	RO_TRP_80	Read Only transponder successfully read in 80 bit mode
$09	RW_TRP_80	Read/Write transponder successfully read in 80 bit mode
$30	PROG_OK	Writing to a Read/Write or Multipage transponder completed successfully
$31	LOCK_OK	Locking of a Multipage transponder completed successfully
$40	NO_READ	No transponder data received
$41	INCOMPLETE	The start byte of the transponder was detected, but CRC failed
$42	MPTERR_CRC	Frame of multipage transponder is correct, but the data CRC failed
$43	MPTRERR_STATUS	Returned invalid status after reading a Multipage transponder
$44	MPTRERR_PAGE_U	Read unlocked of a multipage transponder but it is different than the requested page
$45	MPTRERR_PAGE_L	Read locked of a multipage transponder but it is different than the requested page
$46	MPTRERR_SPC_DATA	Special data status returned reading a multipage transponder
$47	MPTRERR_STATUS	Invalid status returned writing a multipage transponder
$48	PERR_FALSE_IDE	Different ID returned from writing a Read/Write or a Multipage transponder
$49	MPTRERR_LOW_VOLT	Programming voltage is too low to write a multipage transponder
$4A	MPTRERR_UNREL	Writing to a multipage transponder not reliable
$4B	MPTRERR_LOCK	Attempt to write a locked page of a multipage transponder
$4C	MPTRERR_SPC_DATA	Received special data status on writing a multipage transponder

© 2011 by Taylor and Francis Group, LLC

TABLE 8.3 (CONTINUED)

Status Code Name and Description for Results of Group 1 Commands

Status Code Value	Status Code Name	Status Code Description
$4D	MPTRERR_ PAGE_U	Read unlocked page of a multipage transponder as a result of writing but it is different than the requested page
$4E	MPTRERR_ PAGE_L	Read locked page of a Multipage transponder as a result of writing but it is different than the requested page
$4F	MPTRERR_ STATUS	Invalid status returned on locking a multipage transponder
$50	MPTRERR_FS_ DROP	Field strength dropped whole locking a multipage transponder
$51	MPTRERR_ UNREL	Locking of a multipage transponder not reliable
$52	MPTRERR_ PAGE_U	Read unlocked page of a multipage transponder as a result of writing but it is different than the requested page
$53	MPTRERR_ PAGE_L	Read locked of a multipage transponder as a result of writing but it is different than the requested page

All Group 1 commands can be sent requiring an immediate, broadcasted, or queued response (see Table 8.3).

Table 8.4 shows the Group 2 commands. As with Group 0 and Group 1 commands, several command codes are reserved for future implementation.

Group 3 commands define user add-on tasks. For this reason, each use may develop his or her specific commands according to the intended applications.

8.1.2 Commands Supported by the ASCII Bus Protocol

The command supported by the ASCII Bus Protocol is divided into three types: commands for use with 64-bit read/write transponders, commands for use with multipage transponders, and general commands that can be used with either group of transponders. Table 8.5 lists the general commands for the ASCII Bus Protocol.

Example 8.1:

Describe the communications from the host computer to the interrogator using Command H.

Solution:

Host computer → Interrogator	H
Interrogator → Host computer	H (echoes it back)
Host computer → Interrogator	I2 (additional parameters)
Interrogator → Host computer	03<CR><LF> Return ports status: 0 to 3 I/O lines 0&1 port 0…3 set to 1 I/O lines 2&3 port 0…3 set to 0

© 2011 by Taylor and Francis Group, LLC

TABLE 8.4

TIRIS Bus Protocol Group 2 Commands

Command Number	Description
\$40[a]	Get Version
\$41[b]	Set RF parameter
\$42[c]	Get RF parameter
\$43[d]	Set Antenna
\$44[e]	Get Antenna
\$45[f]	Write *electrically erasable programmable read-only memory* (EEPROM)
\$46[g]	Read EEPROM
\$47	Reserved
\$48	Reserved
\$49[h]	Read byte from input
\$4A	Reserved
\$4B	Reserved
\$4C	Reserved
\$4D[i]	Write byte to output
\$4E	Reserved
\$4F	Reserved
\$50	Reserved
\$51	Reserved
\$52	Reserved
\$53	Reserved
\$54	Reserved
\$55[j]	Get count of buffered ID records
\$56[k]	Set Read Mode
\$57[l]	Delete ID records
\$58[m]	Get Read Mode
\$59	Reserved
\$5A[n]	Get ID records from ID buffer
\$5B[o]	Put ID records to the ID buffer
\$5C	Reserved
\$5D[p]	Read block of data from memory
\$5E[q]	Write block of data to memory
\$5F[r]	Reset Interrogator

[a] Command \$40 (*Get version*) returns a string of characters that contain the software version for the interrogator. This is a command with an immediate response that does not require any parameter.

[b] Command \$41 (*Set RF parameter*) sets the period of time used to energize the transponder (charge time) and the duty cycle pause. This command can generate an immediate or a broadcast response. The command requires two parameters: the charge period and the duty cycle pause.

[c] Command \$42 (*Get RF parameter*) returns the current RF setting as for the current charge time and duty cycle pause. This command can also generate an immediate or broadcast response. The command does not require any parameters. The response contains two fields: the charge period and the duty cycle pause, both in milliseconds.

© 2011 by Taylor and Francis Group, LLC

TABLE 8.4 (CONTINUED)

TIRIS Bus Protocol Group 2 Commands

[d] Command $43 (*Set antenna*) selects the active antenna in those interrogators with two antenna ports. This command generates an immediate or broadcast response. It requires a parameter (0 or 1) to select the active antenna.

[e] Command $44 (*Get antenna*) returns the currently selected antenna. This command can also generate an immediate or broadcast response. The response is either 0 or 1 indicating the active antenna.

[f] Command $45 (*Write EEPROM*) writes one or more bytes into the EEPROM in the interrogator. This command can generate an immediate, broadcast, or queued response. The command requires two parameters: the address to start the writing process and the data to be written.

[g] Command $46 (*Read EEPROM*) reads one or more bytes from the EEPROM in the interrogator. This command can also generate an immediate, broadcast, or queued response. The command requires two parameters: the start address in the EEPROM and the number of bytes to be read. The response contains the read data.

[h] Command $49 (*Read byte from input*) reads the status of one of the input/output ports in the interrogator, specified by the port identifier. This command can generate an immediate or broadcast response. It requires the identification of the port. The response contains the status of the port.

[i] Command $4D (*Write byte to output*) writes a value to the output port of the interrogator specified by the port identifier. The command can generate an immediate or broadcast response. It requires three parameters: the port identifier, the port value, and the logical operation to perform. The output value is the result of the logical operation of the current port setting and the parameter passed to the function:
$00 = write port value direct to the output.
$01 = read status ANDed with port value.
$02 = read status ORed with port value.
$03 = read status exclusive-ORed (XORed) with port value.
$04 = invert current port setting.

[j] Command $55 (*Get count of buffered ID records*) returns the count of buffered ID records. This command can only generate an immediate response. The command does not require any parameter. The output is the number of buffered records.

[k] Command $56 (*Set read mode*) sets the read mode in the interrogator. This command can generate an immediate, broadcast, or queued response. It requires a single parameter that is the following read mode: 0 = idle mode, and 1 = gate mode. Gate mode is a charge-only function to interrogate transponders continuously without having to execute a single read command each time.

[l] Command $57 (*Delete ID records*) deletes a specific number of ID records from the ID memory. It is necessary to specify the start record and the number of records to be deleted. The command generates an immediate or broadcast response.

[m] Command $58 (*Get read mode*) returns the current state selected by read mode. This command generates an immediate response. It does not require any parameters. The response contains the currently selected read mode.

[n] Command $5A (*Get ID records from the ID buffer*) returns the number of ID records stored in the buffer specified in the command. This command generates an immediate response. The command uses three parameters: the starting record, the number of records, and the length of the record. The response of the command has a number of fields equal to the number of ID records requested plus one. The first field specifies the actual number of records being transmitted, while the rest of the fields contain the ID records. The initial field is required because if the number of records requested exceeds the length of the total records, the command will only transmit the available number of records.

(*Continued*)

© 2011 by Taylor and Francis Group, LLC

TABLE 8.4 (CONTINUED)

TIRIS Bus Protocol Group 2 Commands

---

[o] Command $5B (*Put ID records into the ID buffer*) writes a given number of ID records into the buffer. This command also generates an immediate response only. The command requires the following three parameters: the start record, count of records, and length of the ID records. This is followed then by the ID records to be written in the buffer. This command does not return any data in its response.

[p] Command $5D (*Read block of data from data memory*) returns a given number of bytes from the data memory in the interrogator. This command generates an immediate response. The command requires two parameters: the start address and the number of bytes to be read. The response contains the contents in the selected memory areas.

[q] Command $5E (*Write block of data to the data memory*) writes a specified number of data records into the data memory in the interrogator. This command generates an immediate or a broadcast response. It requires as parameters the different data records to be written. The command does not return any data in its response.

[r] Command $5F (*Reset reader*) resets the interrogator unit. This command generates an immediate or a broadcast response. It does not require any parameters or return any data.

As mentioned in Table 8.5's notes, Table 8.6 shows the relationship between the ASCII character following the *set outputs* command and its effects on the output lines.

Example 8.2:

Describe the effect of sending the character ***1*** after the character ***Y***.

Solution:

The character *Y* triggers the set outputs command. The character *1* specifies the status of the output lines as follows:

Output line 4 → 1
Output line 3 → 0
Output line 2 → 0
Output line 2 → 0

The commands for use with 64-bit read/write transponders are listed in Table 8.7.

The commands for use with the multipage transponder are listed in Table 8.8.

As mentioned in the notes for Table 8.8, Table 8.9 shows that the selection of the receiving antenna is done with input/output lines 6 and 7, while the selection of the transmitting antenna is done with input/output lines 4 and 5.

Example 8.3:

Describe the operation of command sequence LM4201.

Solution:

The first two characters put the interrogator into line-multiplexed mode. The interrogator will read continuously page 1 of a multipage transponder, switching the

© 2011 by Taylor and Francis Group, LLC

TABLE 8.5

ASCII Bus Protocol General Commands

Command Character	Command Name
B	Readout buffer[a]
C	Clear[b]
F	Format[c]
H	Set outputs and get input-output status[d]
J	Input-output Status[e]
V	Version[f]
Y	Set outputs[g]
Z	Set charge period[h]

[a] *Readout buffer* command is triggered by the ASCII character *B*. With this, the interrogator transmits the character *B* ($42) and the contents of the buffer to the host computer. This is followed by a carriage return ($0D) and line feed ($0A) characters. If the buffer is empty, the interrogator only sends the character *B* followed by $0D and $0A.

[b] *Clear* command is triggered by the ASCII character *C*. This command erases the identification buffer, and the ID counter is reset to zero. After performing this task, the interrogator sends back the ASCII character *C* ($43) followed by a carriage return ($0D) and the line feed ($0A).

[c] *Format* command is triggered by the ASCII character *F*. Sending this command to the interrogator causes a change in the output format for page and identification numbers from decimal to hexadecimal. The interrogator transmits back the ASCII character *F* ($46) followed by a carriage return ($0D) and line feed ($0A) characters once the command has been accepted. The format will continue being hexadecimal until the *escape* command ($1B) is received.

[d] The ASCII character *H* combines and extends two specific commands: the *I/O status* command and *set outputs* command. After the interrogator receives the ASCII character *H*, it echoes it back to the host computer, indicating that it is ready to receive further parameters that are needed to specify the operation of the input/output ports. These parameters are the ASCII character *I* to indicate input ports followed by a number from 0 to 4 that specifies the port, or the ASCII character *O* to indicate output ports followed by the port specified (0 to 3), the logical operation, and the port value.

[e] *Input/output status* command is triggered by the ASCII character *J*. This command causes the interrogator to transmit the current status of the four lower I/O lines and the four higher I/O lines. Originally, the interrogators are configured with lines 0 to 3 as inputs and 4 to 7 as outputs, although these can be changed using the appropriate commands. When the interrogator receives the ASCII character *J* ($4A), it echoes it back to the host computer followed by the ASCII characters that represent the status of the input and output lines. These are followed by a carriage return ($0D) and the line feed ($0A).

[f] *Version* command is triggered by the ASCII character *V*. This causes the interrogator to transmit the version number of the software, followed by a carriage return ($0D) and the line feed ($0A).

[g] *Set outputs* command is triggered by the ASCII character *Y* followed by an ASCII character in the range from 0 to F. For the command to operate correctly, one of the I/O line groups must be set to output. The command reads the configuration information and sets the output level of the lines that are considered outputs. In the case that both sets of lines are configured as outputs, the command only acts on the higher lines. If both sets of inputs are configured as inputs, the command does not have any effect. Table 8.6 shows the relationship between the ASCII character following the *set outputs* command and its effects on the output lines.

(*Continued*)

© 2011 by Taylor and Francis Group, LLC

TABLE 8.5 (CONTINUED)

ASCII Bus Protocol General Commands

---

[h] *Set charge period* command is triggered by ASCII character *Z*. This command sets up the charge time in the range of 15 ms to 255 ms in 1 ms increments. The character *Z* is followed by two further ASCII characters (in the range from 0 to F) that specify the charge time once the hexadecimal number has been converted into a decimal. The resulting number sets the charge time. For example, sending the characters *64* results in a charge time of 100 ms, and sending the characters *3C* results in a charge time of 60 ms.

TABLE 8.6

Effect of ASCII Character Sent After Set Outputs Command

ASCII character	I/O line 7	I/O line 6	I/O line 5	I/O line 4
0	0	0	0	0
1	0	0	0	1
2	0	0	1	0
3	0	0	1	1
4	0	1	0	0
5	0	1	0	1
6	0	1	1	0
7	0	1	1	1
8	1	0	0	0
9	1	0	0	1
A	1	0	1	0
B	1	0	1	1
C	1	1	0	0
D	1	1	0	1
E	1	1	1	0
F	1	1	1	1

control output lines for a four-channel transmit multiplexer and a two-channel receive multiplexer.

8.2 Commands for Texas Instruments High-Frequency Interrogators

8.2.1 Commands Supported by the TIRIS Protocol for Series 6000 Interrogators

The Series 6000 Reader System, described in Chapter 5, is a family of RFID interrogators operating in the HF band, manufactured by Texas Instruments. The data for the communication from the interrogator to the transponder are known as the *request packet*, while the data used in the communication from the transponder to the interrogator are known as the *response packet*.

© 2011 by Taylor and Francis Group, LLC

TABLE 8.7

ASCII Bus Protocol Commands for Read/Write Transponders

Command Character	Command Name
Esc	Normal mode or escape[a]
G	Gate mode[b]
L	Line function[c]
N	Number[d]
P	Program[e]
R	RAM fill[f]
S	Store[g]
U	Antenna[h]
X	Execute[i]
?	Read memory[j]

[a] *Normal mode* or the *escape* command is triggered by the ASCII character *escape*. The normal function provides a continuous readout of transponders at high speed. When this mode is used, the valid IDs received are compared against the identification already in the buffer. If the ID received is a new one, it overwrites the buffer and then transmits the information to the host computer. The transfer consists of the transponder type character, space, application code, space, identification code, carriage return, and line feed. The ASCII character *escape* ($1B) activates the readout function. The ASCII character *E* ($45), a carriage return ($0D), and the line feed ($0A) are returned by the interrogator.

[b] *Gate mode* command is triggered by the ASCII character *G*. In this mode, each correct identification number is compared with the identification stored in the identification memory. When a new identification number is received, it is then stored in memory. The interrogator confirms the reception of the command by sending back the ASCII character *G* ($47), followed by a carriage return ($0D) and the line feed ($0A). Each time a new identification number is detected, the ASCII character *G* ($47), the transponder type character, space, the actual memory count number, space, the application code, space, the identification code, a carriage return, and the line feed are transmitted via the interface.

[c] *Line function* command is triggered by the ASCII character *L*. This command switches the interrogator into a special continuous readout mode in which each correct identification causes the direct transmission of the ASCII character *L* ($4C), the transponder type character, space, the application code, space, the identification code, a carriage return, and the line feed without doing any comparison in the buffer. In the case that no identification is received or, when received, it is not valid, the ASCII character *L* together with the carriage return ($0D) and line feed ($0A) characters are transmitted.

[d] *Number* command is triggered by the ASCII character *N*. This command is used by the host computer to check the number of stored identifications. After receiving it, the interrogator transmits the ASCII character *N* ($4E), space, the number of identifications in the memory in hexadecimal format, followed by a carriage return ($0D) and line feed ($0A).

[e] *Program* command is triggered by the ASCII character *P*. This command is used to program a read/write transponder. The host computer first sends the ASCII character *P* to the interrogator. When the character is echoed, the host computer transmits the 16 hexadecimal characters that specify the identification number to be programmed into the transponder. After the interrogator receives the 16 characters, it performs a block check character (BCC) calculation. Then, the transponder is charged up, and the identification data including the BCC are sent to the transponder.

(*Continued*)

© 2011 by Taylor and Francis Group, LLC

TABLE 8.7 (CONTINUED)

ASCII Bus Protocol Commands for Read/Write Transponders

Once the programming cycle is complete, the transponder sends the programmed data back to the interrogator to compare it with the original string. After the comparison is done, the interrogator sends a status character followed by a carriage return ($0D) and line feed ($0A) to the host computer. The meanings of the different status characters are as follows:

0 = transponder correctly programmed.
1 = ID received from transponder different from ID transmitted.
2 = interrogator did not receive any ID from the transponder.

It is important to note that the programming cycle is longer than regular reading cycles. For this reason, there may be collisions with other interrogators in the area. Also, it is important to note that the programming distance is lower than the reading distance due to the stronger power requirements during programming.

[f] *RAM fill* command is triggered by the ASCII character *R*. This is used by the host computer to test the memory in the interrogator by filling it with predetermined codes and reading it to check for consistency. Two ASCII characters (in the range from 0 to F) are used to specify an 8-bit test pattern. After the memory is filled, the interrogator transmits the ASCII character *R* ($52), followed by a carriage return ($0D) and the line feed ($0A) to the host computer.

[g] *Store* command is triggered by the ASCII character *S*. This command causes the transmission of all stored identification numbers from the interrogator's memory to the host computer together with their memory addresses. Each transmitted line consists of the transponder type, space, the memory location, space, the application code, space, the identification code, a carriage return, and the line feed. After the transmission has finished, the interrogator transmits the ASCII character *S*, carriage return, and line feed.

[h] *Antenna* commands are triggered by the ASCII character *U*. This command allows the user to choose a specific antenna in the interrogator. This is done by transmitting the character *0*, *1*, or *2* after the character *U*. The character *1* selects Antenna 1, the character *2* selects Antenna 2, and the character *0* toggles the selected antenna. If the character transmitted after the character *U* is different from *0*, *1*, or *2*, the whole command is ignored.

[i] *Execute* command is triggered by the ASCII character *X*. This causes the interrogator to switch to a single readout mode and triggers a single readout sequence. After the command is executed, the interrogator remains in an idle loop waiting for the next command. After receiving an identification number from a transponder, the interrogator transmits the character *X*, the transponder type character, space, the four-digit application code, space, the 16-digit identification code, a carriage return, and the line feed to the host computer. If the interrogator does not read an identification number, the interrogator transmits the character *X* ($58) followed by a carriage return ($0D) and the line feed ($0A). If the interrogator received an identification number but this was invalid, it transmits the character *X* ($58), the character *I* ($49), followed by a carriage return ($0D) and line feed ($0A).

[j] *Read memory* command is triggered by the ASCII character *?* After echoing back this character, the interrogator transmits space, the memory location, space, the 16-digit identification code, the transponder type information, a carriage return, and the line feed

© 2011 by Taylor and Francis Group, LLC

TABLE 8.8

ASCII Bus Protocol Commands for Multipage Transponders

Command Character	Command Name
Esc	Normal mode[a] or escape
L	Line function[b]
O	Lock page[c]
P	Program[d]
U	Antenna[e]
X	Execute[f]

Note: Before being able to access multipage transponders, the interrogator must be configured for this operational mode. This allows the interrogator to generate a protocol that includes additional information such as the page in the multipage transponder as well as additional information concerning a particular command. The interrogator enters multipage mode after receiving the character *K* followed by the character *1*. Similarly, the interrogator reverts back to a read/write transponder mode after receiving *K 0*. The interrogator echoes these characters followed by the carriage return and line feed characters.

[a] The *normal* mode is triggered by the ASCII character *escape* followed by a page number. The ASCII character *E*, carriage turn, and line feed are echoed back to the host computer by the interrogator to acknowledge the reception of the command. Normal mode provides a continuous readout of a certain transponder page at high speed. When reading a multipage transponder, it will send back the antenna number, the read status, the transponder type character, space, the page, the pace, the application code, space, the identification code, a carriage return, and the line feed.

[b] *Line function* is triggered by the ASCII character *L*. If this character is followed by a page number, the system continuously reads the specified page. If the character *L* is followed by the character *M*, the interrogator is switched into multiplexed mode. When the transponder is continuously reading the specified page, each correct identification is transmitted directly to the host computer without comparing the received value against a value in the buffer. In addition, before each identification number, the interrogator transmits the ASCII character *L*, the antenna number, the read status information, and the transponder type. If the interrogator does not receive any identification, or the received value is not valid, it transmits the ASCII character *L*, the antenna port used, a carriage return, and the line feed. For the interrogator to operate in multiplexed mode, after the characters *L* and *M*, it must receive the following additional parameters: the number of transmit multiplex antennas, the number of receive multiplex antennas, and the page information to read a multipage transponder. The selection of the receiving antenna is done with input/output lines 6 and 7, while the selection of the transmitting antenna is done with input/output lines 4 and 5, as shown in Table 8.9.

[c] *Lock page* command is triggered with ASCII character *O*. This command enables the user to disable for programming a specific page of a multipage transponder. After the interrogator receives the character *O*, it echoes it back to the host computer, indicating that it is now ready to receive the page number that will be locked. The status command can be used to verify that the page has been successfully locked. When the interrogator has been able to communicate with the transponder, it sends the following information to the host computer: antenna number, status, transponder type, space, page, space, application code, space, identification number, carriage return, and line feed. If the interrogator has not been able to communicate with the transponder effectively, it sends the following information to the host computer: antenna number, carriage return, and line feed.

(*Continued*)

© 2011 by Taylor and Francis Group, LLC

TABLE 8.8 (CONTINUED)

ASCII Bus Protocol Commands for Multipage Transponders

---

[d] *Program* command allows programming a multipage transponder. To initiate the programming process, the interrogator must receive the ASCII character *P*, two characters containing the page number ($01 to $11), and 16 additional hexadecimal characters containing the ID to be programmed into the specified page. After the interrogator receives the last character from the host computer, it performs a block check character (BCC) calculation and sends the entire string to the transponder. Once the programming has finished, the interrogator receives the identification number and the address from the transponder to be compared with the data sent to the transponder. If the comparison is successful, the interrogator transmits the following information to the host computer: antenna number, programming status, transponder type, space, page, space, application code, space, identification number, carriage turn, and line feed. If the comparison fails, it transmits the antenna number, status information 2, carriage return, and line feed.

[e] *Antenna* command is triggered by the ASCII character *U* followed by a character in the range from *0* to *2*. This command allows the user to specify a particular receiving antenna. The character *1* selects Antenna 1, the character *2* selects Antenna 2, and the character 0 toggles the selected antenna. If the character transmitted after the character *U* is different from *0*, *1*, or *2*, the whole command is ignored.

[f] *Execute* command is triggered by the ASCII character *X* followed by a page number ($01 to $11) or the character *M*. When the characters $01 to $11 follow the character *X*, the interrogator operates in a single readout mode, reading the page specified by the $01 to $11 characters. When the character *M* follows the character *X*, the interrogator enters into a multiplexed mode operating similarly to its operation mode for a read/write transponder.

The commands supported by this protocol are divided into the following functional categories:

- Tag-it HF commands
- Miscellaneous commands
- ISO/IEC 15693-3 commands

Table 8.10 shows the different Tag-it HF commands. These commands are specific for working with the Tag-it family of HF transponders. These commands can be applied to addressed and nonaddressed blocks.

The commands in the *miscellaneous* category are shown in Table 8.11.

The packet for the request (interrogator to transponder) consists of a header, the packet length, the node address, command flags, the interrogator command ($60), the ISO/ECI 15963-3 command, and data bytes 0 to *n* and checksum, as shown in Table 8.12. Table 8.13 describes its contents.

For the commands that follow the ISO/IEC 15963-3, the command field always contains $60. The actual command to be executed by the interrogator is contained in the data field. The response packet has a similar structure; it consists of a header, the packet length, the node address, command flags, the interrogator command ($60), the ISO/IEC 15963-3 command and data bytes, and a checksum, as shown in Table 8.14. Table 8.15 describes the contents of the response packet.

© 2011 by Taylor and Francis Group, LLC

TABLE 8.9

Selection of Antennas in Multiplexed Mode

RX Antenna Controlled with I/O Lines 6 and 7		
	I/O 6	*I/O 7*
RX antenna 1	0	0
RX antenna 2	1	0
RX antenna 3	0	1
RX antenna 4	1	1
TX Antenna Controlled with I/O Lines 6 and 7		
	I/O 4	*I/O 5*
TX antenna 1	0	0
TX antenna 1	1	0
TX antenna 1	0	1
TX antenna 1	1	1

For commands that follow the ISO/IEC 15963-3 protocol, the command field is always equal to $60. Table 8.16 shows the commands that comply with the ISO/IEC 15963 Part 3 (15963-3) transmission protocol.

For Table 8.16, Commands $01 and $02 are considered *mandatory commands*. Command $01 is the *inventory command*. Figure 8.1 shows the format of this command. It can be seen how the request command packet follows the format outlined in Figure 8.1, while the specifics for this command are included into the ISO command data field. The packet format as a response to the inventory command is shown in Figure 8.2.

The field *valid data flags* contains 16 bits that specify whether or not each one of the possible 16 time slots received valid data. Bits 0–7 in the LSB byte correspond to time slots 1 to 8, while bits 0 to 7 in the MSB byte correspond to time slots 9 to 16. The reception of valid data is indicated when the appropriate bit is set to 1. The field *collision flags* contains 16 bits that specify whether or not a collision occurred in the possible 16 time slots. The structure of these bits follows the structure described for the valid data flags. A collision in a specific time slot is indicated by the appropriate bit set to 1.

Command $02 is the *ISO stay quiet request* command. After a transponder following the ISO 15963-3 protocol receives this command, it enters in quiet state and will not initiate a response. The request format follows the same structure as the other ISO commands, with the ISO command data shown in Figure 8.3. It is necessary to note that after receiving this command, the transponder does not issue a response.

The rest of the ISO commands are considered optional commands. The structure of their diverse command data fields follows the standard structure with each specific command code.

© 2011 by Taylor and Francis Group, LLC

TABLE 8.10

Tag-it HF Commands for TIRIS Protocol Series 6000

Command Code	Command Name
$02	Read block[a]
$03	Write block[b]
$04	Lock block[c]
$05	Read transponder details[d]
$0F	Special read block[e]

[a] Command code $02 (*read block*) reads a single block of data from an HF Tag-it transponder. When the address flag is set, the address is part of the data section with its least significant bit (LSB) first. This is followed by a byte that contains the number of the block to be read. When the address flag is clear, the address is not sent.

[b] Command code $03 (*write block*) writes the specified data into a block in an HF Tag-it transponder. When the address flag is set, the address is part of the data section with its LSB first. This is followed by a byte that contains the number of the block to be read. The data to be written follow the block number. When the address flag is clear, the address is not sent and only the block and data are being sent. The response follows a similar structure in which the data have been changed to $00 in order to indicate a successful operation.

[c] Command code $04 (*lock block*) locks a single block of data in an HF Tag-it transponder. When the address flag is set, the address forms the first part of the data section. This is followed by a single byte containing the number of the block to lock. The response contains $00 in the data section, indicating a successful lock operation.

[d] Command code $05 (*read transponder details*) reads the details of an HF Tag-it transponder. The data section in the response contains the transponder address, the manufacturer code, the version number of the transponder, the number of blocks, and the number of bytes per block.

[e] Command code $0F (*special read block*) reads blocks of data from an HF Tag-it transponder. The data section contains a single byte that specifies the number of blocks to be read. Each bit in this byte represents a block of data. Each bit that is set to 1 marks that block number to be read.

8.2.2 Commands Supported by HF Tag-It Transponders

The following describes the commands supported by the HF Tag-it transponders manufactured by Texas Instruments. While some of these commands may be used in a nonaddressed mode, it is necessary to be extremely careful when using this method, as it may produce undesired effects in nearby transponders. For example, a *lock block* command executed in a nonaddressed mode will effectively lock all the transponders within its write range. For this reason, it is recommended to specify the specific address of the transponders.

Command $01 (*read block*) reads the contents of a single block of data from a transponder. The request message has two fields: 4 bytes for the address field and 1 byte for the number of the block to be read. The data in the response message have the fields shown in Table 8.17.

© 2011 by Taylor and Francis Group, LLC

TABLE 8.11

Miscellaneous Commands for TIRIS Protocol Series 6000

Command Code	Command Name
$D0	Initiate FLASH Loader[a]
$D8	Send Data to FLASH[b]
$F0	Reader Versionc[c]
$F1	Reader Inputs[d]
$F2	Write Reader Outputs[e]
$F4	RF Carrier[f]
$FF	Baud Rate[g]

[a] Command code $D0 *(initiate Flash loader)* is used to initialize and transfer control to the Flash loader software. The response of the system contains $00 in the data place if the command has been successful.

[b] Command code $D8 (*send data Flash*) is used to load up to 132 bytes of data into the Flash memory. The data bytes are followed by 2 checksum bytes. If the command is successful, the response contains $00 in the data place.

[c] Command $F0 (*reader version*) requests the version of the interrogator. The response is similar to the request packet, with the data section containing the 2-byte version LSB first followed by a single byte representing the type of interrogator.

[d] Command code $F1 (*reader inputs*) reads the state of the different interrogator's inputs. The data section in the response contains a byte representing the state of the inputs, with bit 0 representing input 1 and bit 1 representing input 2.

[e] Command $F2 (*write reader outputs*) writes the state of the interrogator's outputs. The meaning of the different bits for the 1-byte data being sent is as follows:

Bit 0	1 = Output 1 pulled to ground
Bit 1	1 = Output 2 pulled to ground
Bit 2	Reserved
Bit 3	Reserved
Bit 4	1 = Bit 0 enabled
Bit 5	1 = Bit 1 enabled
Bit 6	Reserved
Bit 7	Reserved

[f] Command $F4 (*RF carrier*) switches the radiofrequency carrier on and off. The carrier is turned on by loading the $FF into the data section and turned off by loading $00 into the data section.

[g] Command $FF (*baud rate*) sets up the baud rate for the interrogator. The data section consists of 1 byte linked to the baud rate as follows:

09 = 57,600 baud
08 = 38,400 baud
07 = 19,200 baud
06 = 9600 baud

In addition to supporting the proprietary Tag-it protocol, the Series 6000 interrogators also comply with the ISO/IEC 15963 protocol. Under this protocol, the communication from the interrogator to the transponder uses amplitude-shift keying (ASK) at a modulation rate of either 100% or between 10% and 30%. The response from the transponder to the reader uses frequency-shift keying (FSK). These parameters are set by the configuration byte that is ISO command data byte 0.

© 2011 by Taylor and Francis Group, LLC

TABLE 8.12
Structure of the Request Packet for TIRIS Protocol Series 6000

Header	Packet Length	Address Node	Command Flag	Command	Command Data	Checksum
$01	LSB MSB	LSB MSB	Flags	$60	$XX Data	Byte1 Byte2
1 byte	2 bytes	2 bytes	1 byte	1 byte	Byte0 Bytes 1–*n*	2 bytes
					1 byte *N* bytes	

TABLE 8.13
Format of Request Packet for TIRIS Protocol Series 6000

Field	Length	Description
Header	1 byte	Start of packet $01
Packet Length	2 bytes	Length of packet. Includes checksum
Node Address	2 bytes	Interrogator's address
Command Flags	1 byte	Specifies execution of command
Command	1 byte	Command for interrogator to execute
Data	0 to n bytes	Data required to execute command
Checksum	2 bytes	Byte 1 is XOR of all elements from header to last byte. Byte 2 is calculated XORing Byte 1 with $FF.

TABLE 8.14
Structure of the Response Packet for TIRIS Protocol Series 6000

Header	Packet Length	Address Node	Command Flag	Command	Command Data	Checksum
$01	LSB MSB	LSB MSB	Flags	$60	Data	Byte1 Byte2
1 byte	2 bytes	2 bytes	1 byte	1 byte	*m* bytes	2 bytes

TABLE 8.15
Format of Response Packet for TIRIS Protocol Series 6000

Field	Length	Description
Header	1 byte	Start of packet $01
Packet Length	2 bytes	Length of packet. Includes checksum
Node Address	2 bytes	Interrogator's address
Command Flags	1 byte	Response of interrogator to request. Bit 4 defines the error status. If bit 4 = 1, error has occurred.
Command	1 byte	Command that the interrogator executed
Data	0 to m bytes	Data returned by interrogator in response to command
Checksum	2 bytes	Byte 1 is XOR of all elements from header to last byte. Byte 2 is calculated XORing Byte 1 with $FF.

© 2011 by Taylor and Francis Group, LLC

TABLE 8.16

ISO/IEC 15963-3 Protocol

Command Code	Command Name
$01	Inventory
$02	Stay Quiet
$20	Read Single Block
$21	Write Single Block
$22	Lock Block
$23	Read Multiple Blocks
$27	Write AFI
$28	Lock AFI
$29	Write DSFID
$2A	Lock DSFID
$2C	Get Multiple Block Security Status


Header
Length of packet
Address node
Flags
cmd
Data for command
Config
DATA
Check sum
$01
2 bytes
2 bytes
1 byte
$60
byte 0
bytes 1 .. n
2 bytes
SOF
Flags
In-ventory cmd
AFI
Mask length
Mask value
CRC
EOF
Not used
1 byte
$01
1 byte
1 byte
0 to 7 bytes
not used
Not used

FIGURE 8.1
Structure of the request packet when sending the *inventory* command.

Command $02 (*read multiblock*) reads the contents of more than one block of data from a transponder. The request message contains three fields: the 4-byte address for the transponder, the number of the first block to be read, and the number of blocks to be read. The data in the response message follow the format shown in Table 8.18.

Command $03 (*tag version*) reads the information from a transponder that was programmed at the factory and cannot be altered. The request message has a single field that contains the 4-byte address for the transponder being interrogated. The data in the response message follow the format shown in Table 8.19.

© 2011 by Taylor and Francis Group, LLC



Header	Length of packet	Address node	Flags	cmd	Response data DATA	Check sum
$01	2 bytes	2 bytes	1 byte	$60	bytes 0 .. m	2 bytes

SOF	Valid data flags	Collision flags	Response to command	Etc	CRC	EOF
Not used	2 bytes	2 bytes	10 bytes	Etc	Not used	Not used

FIGURE 8.2
Structure of the response packet for the *inventory* command.



Request data
DATA
bytes 0 .. m

SOF	Flags	cmd	UID	CRC	EOF
Not used	1 byte	$02	8 bytes	Not used	Not used

FIGURE 8.3
Request data for the *stay quiet* command.

TABLE 8.17
Format of Data Response for Read Block Command

Field Name	Number of Bytes	Description	Comments
Address	4	Transponder address	
Block Number	1	Number of block to read	$00 to $07
Lock Status	1	Status of block lock	$00 = unlocked $01 = locked by user $02 = locked by factory
Block Data	4	Data	

© 2011 by Taylor and Francis Group, LLC

TABLE 8.18

Format of Data Response for Read Multiblock Command

Field Name	Number of Bytes	Description	Comments
Address	4	Transponder address	
Number of blocks read	1	Specified the number of times that the next three fields are repeated	
Block number	1	Number of block	\$00 to \$07
Lock status	1	Status of block lock	\$00 = unlocked \$01 = locked by user \$02 = locked by factory
Block data	4	Data	
Error number	1	Field will be present if not all requested blocks were read	Specific error codes: \$11 = At least one block not available \$15 = At least one block not read

TABLE 8.19

Format of Data Response for Tag Version Command

Field Name	Number of Bytes	Description	Comments
Address	4	Transponder address	
Manufacturer Code	1	Identifies manufacturer of transponder	Only 7 LSBs
Chip Version	2	Chip version used	Only 9 LSBs
Block Size	1	Size of each block for this transponder	Counts on bytes starting from zero. Only 5 LSBs
Number of blocks	1	Number of blocks in transponders	Counts starting from zero

More general commands:

- Command \$04 (*stop continuous*) causes the interrogator to stop operating in continuous mode. This command has no effect if the interrogator is not operating in continuous mode. There are no data associated with this command.
- Command \$05 (*write block*) writes a single block of data to the transponder. The request message contains three fields: the 4-byte address for the transponder, the number of the block to be written, and the 4-byte data to write. The data in the response message contain a single field that is the transponder address.
- Command \$06 (*write multiblock*) writes data to more than one block in the transponder. The request message contains four fields: the 4-byte

© 2011 by Taylor and Francis Group, LLC

address for the transponder, the number of the first block, the number of blocks, and the 4-byte data to write. The data in the response message contain two fields: the 4-byte transponder address and an optional field with the error number. This field is not present if the command was executed without errors. Some specific error codes are as follows:

$11 = At least one block not available
$13 = At least one block already locked
$17 = At least one block not successfully written

- Command $07 (*write and lock block*) writes a single block of data to a transponder and locks it. The request message contains three fields: the 4-byte address for the transponder, the number of the block to be written, and the 4-byte data to write. The data in the response message contain only one field that is the transponder address.
- Command $08 (*lock block*) locks a single block of data in a transponder. The request message contains two fields: the 4-byte address of the transponder and the block number. The data in the response message contain a single field that is the transponder address.
- Command $09 (*lock multiblock*) locks more than one block of data in a transponder. The request message contains three fields: the 4-byte address of the transponder, the first block number, and the number of blocks to lock. The data in the response message contain two fields: the 4-byte transponder address and an optional field with the error number. This field is not present if the command was executed without errors. Some specific error codes are as follows:

$11 = At least one block not available
$13 = At least one block already locked
$19 = At least one block not successfully locked

- Command $10 (*reset reader*) causes the interrogator to perform a software reset. Prior to executing the reset, the interrogator completes the command that is currently executing. After the reset, any temporary settings or data stored in volatile memory are lost. There are no data associated with this command.
- Command $11 (*reader version*) makes the interrogator send the version of the firmware that is running. There are no data associated with this request. The data in the response message contain two fields: a 3-byte field for the firmware version and a 1-byte field for

© 2011 by Taylor and Francis Group, LLC

the firmware type. This can be either the standard version (bit 0 = 0) or engineering version (bit 0 = 1).

- Command $12 (*reader diagnostic*) makes the interrogator perform self-diagnosis operations. The request message contains the 1-byte operation to be performed following this code:

  $01 = Self-test
  $02 = Reserved
  $03 = Transmitter ON
  $04 = Transmitter OFF
  $05 = Detailed error messages
  $06 = Normal error messages

  The response contains a single 1-byte field that describes the status of the interrogator after the execution of the operation:
  $01 = Self-test failed
  $FF – Self-test passed
  $02 = Reserved
  $03 = Transmitter turned ON
  $04 = Transmitter turned OFF
  $05 = Detailed error messages ON
  $06 = Normal error messages ON

- Command $13 (*read reader setup*) makes the interrogator send the current setup and configuration data from its on-board Flash memory. There are no data associated with this request. The data in the response message are a single field of up to 12 bytes containing the data stored in its on-board memory.
- Command $16 (*start Flash loader*) is used to reprogram the Flash memory, for firmware upgrades, or to set up data alteration. After the Flash loader has started, the interrogator ceases communicating using the host protocol and instead uses the one from the loader. The Flash loader is deactivated by a soft or a hard reset. There are no data associated with this request or a response.
- Command $3D (*factory lock block*) locks a single block of data on a transponder. This is a factory command not available to general users.
- Command $3E (*write SID code*) stores the session ID (SID) code into the transponder. This SID code becomes the new address for the

© 2011 by Taylor and Francis Group, LLC

transponder. The request message contains a single field with the 4-byte address of the transponder. The data in the response message also contain the address of the transponder.

- Command $3F (*factory programming off*) clears the factory programming bit, in turn disabling all factory programming functions. This is also a factory command not available to general users.
- Command $FD (*read multiblock SID*) reads the contents of more than one block of data from all the transponders within reading range. This command cannot be executed in addressed mode. The maximum number of transponders that is possible to read in a single pass is 100. The request message contains three fields: the first block number to be read, the number of blocks, and a field indicating the options for the response. The data in the response message follow the format shown in Table 8.20.
- Command $FE (*read block SID*) reads the contents of a single block of data from all the transponders within reading range. This command cannot be executed in addressed mode. The maximum number of

TABLE 8.20

Format of Data Response for Read Multiblock SID Command

Field Name	Number of Bytes	Description	Comments
Response Options	1	Specifies how data will be returned	Bit 0: 0 = do not send addresses 1 = show addresses Bit 1: 0 = no version data 1 = version data
Address	4	Transponder address (not always present)	
Manufacturer code	1	Identifies manufacturer of transponder	Only 7 LSBs
Chip version	2	Chip version used	Only 9 LSBs
Block size	1	Size of each block for this transponder	Counts on bytes starting from zero. Only 5 LSBs
Number of blocks	1	Number of blocks in transponders	Counts starting from zero
Number of blocks read	1	Determines how many times the following 3 fields will be repeated	
Block number	1	Number of blocks	$00 to $07
Lock status	1	Locked status of block	$00 = unlocked $01 = locked by user $02 = locked by factory
Block data	4	Data	

© 2011 by Taylor and Francis Group, LLC

TABLE 8.21

Format of Data Response for Read Block SID Command

Field Name	Number of Bytes	Description	Comments
Response Options	1	Specifies how data will be returned	Bit 0: 0 = do not send addresses 1 = show addresses Bit 1: 0 = no version 1 = data Bit 2: 0 = response with block data 1 = response with address only
Number of transponders found	1	Number of times the following 3 fields are repeated	
Address	4	Transponder address (not always present)	
Manufacturer code	1	Identifies manufacturer of transponder	Only 7 LSBs
Chip version	2	Chip version used	Only 9 LSBs
Block size	1	Size of each block for this transponder	Counts on bytes starting from zero. Only 5 LSBs
Number of blocks	1	Number of blocks in transponders	Counts starting from zero
Block number	1	Not always present	
Lock status	1	Not always present	
Block data	4	Not always present	

transponders that is possible to read in a single pass is 100, although each single response message carries information for up to 50 transponders. The request message contains two fields, the block number to be read and an options field that determines how the data will be returned. The data in the response message follow the format shown in Table 8.21.

8.3 Command Supported by Texas Instruments Series 4000 Multifunction Interrogators

The Series 4000 transponders from Texas Instruments are able to operate in the HF and LF ranges. For this reason they need to communicate with

© 2011 by Taylor and Francis Group, LLC

different types of transponders following different protocols. This section explores the different commands supported by the different transponders that can communicate with the Series 4000 Interrogators.

8.3.1 Commands Supported by Tag-It Transponders

Many of the responses produced by these commands contain a field called *response flag*. The response flag bits, shown in Table 8.22, are the least significant bits in this field. The host computer must take them into account when decoding the response given to the interrogator because their contents vary depending on the settings being used.

- Command $41 (*find token request*) is used by the host computer to check if a transponder is present. If multiple transponders are present, the command returns the first found. The request packet contains three fields: entity ID (set to $05), the command code ($41), and the loop count field that specifies the number of attempts to find a transponder. The first four fields of the response packet are the entity ID (Set to $05), the issued command ($41), the status showing the error codes, and the library entity ID set to $05. The following 16 commands contain the ID of the tokens being detected.
- Command $45 (*pass-through request*) allows the host to have a direct communication with the radiofrequency module in the interrogator. The request packet contains four fields: entity ID (set to $05), the command code ($45), the number of bits in the next field, and the data field containing the communication to the specific module. The response packet has five fields: the entity ID (Set to $05), the issued command ($45), the status showing the error codes, the number of

TABLE 8.22

Response Flag Bits

Bit Number	Flag
0	Error Flag: 0 = No error 1 = Error
1	Reserved. Set to 0 by protocol
2	Address Flag: 0 = Non-addressed 1 = Addressed
3	Format type. Set to 0 by protocol
4	Unused. Set to 0
5	Unused. Set to 0
6	Unused. Set to 0
7	Unused. Set to 0

© 2011 by Taylor and Francis Group, LLC

bits for the next field, and the data field that contains the number of bits in the reply if one was issued.

- Command $48 (*transmitter ON request*) turns on the transmitter in the interrogator for a specific entity that is specified in the request packet. The request packet contains two fields: the entity ID ($05) and the issued command ($48). The response packet contains three fields: the entity ID (set to $05), the issued command ($48), and the status showing the error codes.
- Command $49 (*transmitter OFF request*) turns off the transmitter for a specific identity that is specified in the request packet. The request packet contains two fields: the entity ID ($05) and the issued command ($49). The response packet contains three fields: the entity ID (Set to $05), the issued command ($49), and the status showing the error codes.
- Command $61 (*get block request*) gets data from one memory block of the responding transponder. The request packet contains four fields: the entity ID ($05), the issued command ($61), and the block number and ID of the transponder. In addition to the data read from the transponder, the response packet also contains a block security status field that indicates the write status of the block specified in the request. The structure of the response packet is shown in Table 8.23.
- Command $62 (*get IC version request*) returns information regarding the integrated circuit in the transponder such as version, manufacturer, memory size, number of blocks, and so on. The request packet contains three fields: the entity ID ($05), the issued command ($62), and the ID of the transponder. The response packet contains four fields: the entity ID (Set to $05), the issued command ($49), the status field with the standard error codes, and the response data. The

TABLE 8.23

Structure of Response Packet for Get Block Command

Field	Bytes	Value (Range)	Comments
Cmd 1	1	$05	Entity ID
Cmd 2	1	$61	Get block command
Status	1	$00 to $FF	Error codes
Command code	1	$01	Get block
Response Flag	1	$00 to $04	Response flags
SID	0 to 4	$00 to $FF	ID of transponder
Block Number	1	$00 to $FF	Block number
Lock Status	1	$00 to $03	Write status
Block Data	n	$00 to $FF	Data

© 2011 by Taylor and Francis Group, LLC

response data comprise an 11-byte field in which the contents of the bytes are as follows:

Byte 1: Command code
Byte 2: Response flags
Bytes 3 to 6: ID of transponder
Byte 7: Manufacturer code
Bytes 8 and 9: Chip version
Byte 10: Block bytes minus one
Byte 11: Number of blocks minus one

If the interrogator does not receive a response from the transponder, the last field is substituted by a *no data* field that is zero bytes long.

- Command $63 (*put block request*) writes data to a memory block. To use this command, it is necessary to know the size of the memory block that can be obtained through the *Get IC version* command. Table 8.24 shows the structure of the request packet, and Table 8.25 shows the structure of the response packet.

TABLE 8.24

Structure of Request Packet for Put Block Request Command

Field	Bytes	Value (Range)	Comments
Cmd 1	1	$05	Entity ID
Cmd 2	1	$63	Put block command
Blk Num	1	$00 to $FF	Specifies block to write
BlkBits	1	$00 to $FF	Number of bits next field
BlkData	1 to 32	$00 to $FF	Data to be written
SID	0 to 4	$00 to $FF	ID of transponder

TABLE 8.25

Structure of Response Packet for Put Block Request Command

Field	Bytes	Value (Range)	Comments
Cmd 1	1	$05	Entity ID
Cmd 2	1	$63	Put block command
Status	1	$00 to $FF	Standard Error Codes
CmdCode	0 to 1	$05	Command code
RespFlags	0 to 1	$00 to $05	Response Flags
SID	0 to 4	$00 to $FF	ID of transponder
ErrorResp	0 to 1	$00 to $FF	Error code

© 2011 by Taylor and Francis Group, LLC

- Command $64 (*put block lock request*) writes data to one memory block and locks it to further write operations. The host must also know the size of the memory block. Table 8.26 shows the structure of the request packet, and Table 8.27 shows the structure of the response packet.
- Command $65 (*lock block request*) protects one memory block against writing. If the command is used in a nonaddressed manner without the SID field being present, the command acts on all the transponders in its write zone. The structure of the request packet contains four fields: the entity ID ($05), the issued command ($65), the block number, and the ID of the transponder. The structure of the response packet is shown in Table 8.28.
- Command $66 (*SID poll request*) is used to acquire the IDs of transponders in the interrogator's read area. The possibility of collision among all these transmissions can be reduced by issuing further commands to the transponders to respond in a predetermined slot based on a portion of their ID numbers. Table 8.29 shows the structure of the request packet, and Table 8.30 shows the structure of the response packet.
- Command $67 (*slot marker/end-of-frame request*) is used together with other commands as part of an exchange sequence. The purpose of this command is to send the end-of-frame marker as in the SID

TABLE 8.26

Structure of Request Packet for Put Block Lock Request Command

Field	Bytes	Value (Range)	Comments
Cmd 1	1	$05	Entity ID
Cmd 2	1	$64	Put block lock
Blk Num	1	$00 to $FF	Specifies block to write
BlkBits	1	$00 to $FF	Number of bits next field
BlkData	1 to 32	$00 to $FF	Data to be written
SID	0 to 4	$00 to $FF	ID of transponder

TABLE 8.27

Structure of Response Packet for Put Block Lock Request Command

Field	Bytes	Value (Range)	Comments
Cmd 1	1	$05	Entity ID
Cmd 2	1	$64	Put block lock
Status	1	$00 to $FF	Standard Error Codes
CmdCode	0 to 1	$07	Command code
RespFlags	0 to 1	$00 to $05	Response Flags
SID	0 to 4	$00 to $FF	ID of transponder
ErrorResp	0 to 1	$00 to $FF	Error code

© 2011 by Taylor and Francis Group, LLC

TABLE 8.28

Structure of Response Packet for Lock Block Request Command

Field	Bytes	Value (Range)	Comments
Cmd 1	1	$05	Entity ID
Cmd 2	1	$65	Lock block
Status	1	$00 to $FF	Standard Error Codes
CmdCode	0 to 1	$08	Command code
RespFlags	0 to 1	$00 to $05	Response Flags
SID	0 to 4	$00 to $FF	ID of transponder
ErrorResp	0 to 1	$00 to $FF	Error code

TABLE 8.29

Structure of Request Packet for SID Poll Request Command

Field	Bytes	Value (Range)	Comments
Cmd 1	1	$05	Entity ID
Cmd 2	1	$66	SID Poll Command
ReqVersion	1	$00 to $FF	0 = request only SID in reply
MskLen	1	$00 to $20	Number of bits in next field
MskVal	0 to 4	$00 to $FF	Anti collision maks

TABLE 8.30

Structure of Response Packet for SID Poll Request Command

Field	Bytes	Value (Range)	Comments
Cmd 1	1	$05	Entity ID
Cmd 2	1	$66	SID Poll Command
Status	1	$00 to $FF	Error codes
Command code	1	$0A	Get Phase-Locked Loop (PLL)
Response Flag	1	$00 to $0F	Response flags
SID	4	$00 to $FF	ID of transponder
VersionDat	0 to 5	$00 to $7F	Byte 1: Manufacturer code
		$00 to $FF	Byte 2–3: Chip Version
		$00 to $1F	Byte 4: Block bytes -1
		$00 to $FF	Byte 5: Number of blocks -1

sequence; this marker is understood as a “slot marker” for anticollision. The request packet contains three fields: the entity ID ($05), the issued command ($67), and a command for formatting the reply. The structure of the response packet is shown in Table 8.31.

- Command $68 (*quiet request*) is used to silence a transponder in order to prevent it from responding to any nonaddressed commands

© 2011 by Taylor and Francis Group, LLC

TABLE 8.31

Structure of Response Packet for Slot Marker and End-of-Frame (EOF) Request

Field	Bytes	Value (Range)	Comments
Cmd 1	1	$05	Entity ID
Cmd 2	1	$67	SID Poll Command
Status	1	$00 to $FF	Error codes
Command code	1	$0A	Get Pll
Response Flag	1	$00 to $0F	Response flags
SID	4	$00 to $FF	ID of transponder
VersionDat	0 to 5	$00 to $7F	Byte 1: Manufacturer code
		$00 to $FF	Byte 2–3: Chip Version
		$00 to $1F	Byte 4: Block bytes -1
		$00 to $FF	Byte 5: Number of blocks -1

within its range. The command does not prevent, however, responses to addressed commands. The request packet contains three fields: the entity ID ($05), the issued command ($68), and the SID field. The response packet contains three fields: the entity ID ($04), the command issued (*quiet*), and the status field containing the standard error codes.

8.3.2 Commands Supported by the ISO 14443 Protocol

The ISO 14443 protocol is used by RFID systems operating in the HF range. The protocol is divided into different subparts depending on the anticollision protocols that they use (ISO 14443-3 Type-A and ISO 14443-3 Type-B) and ISO 14443-4 Type-B.

Table 8.32 lists the command supported by the ISO 1444-3 Type-A protocol. While some commands have the same code as those supported by the Tag-it protocol, it is necessary to state that they form parts of separate command sets.

Table 8.33 lists the commands supported by the ISO 14443-3 Type-B protocol.

8.4 Commands for the Texas Instruments UHF Gen 2 Protocol

Table 8.34 lists the different commands supported by the Texas Instruments UHF Gen 2 transponders.

As soon as the integrated circuit in the transponder is immersed in the radiofrequency field generated by the interrogator, it enters the *ready* state and is able to accept the *select* command. The *select* command is sent to all

© 2011 by Taylor and Francis Group, LLC

TABLE 8.32

Commands for ISO 14443-3 Type A

Command code	Command
$41[a]	Find Token Request
$45	Pass-through Request
$48	Transmitter ON Request
$49	Transmitter OFF Request
$61/$62[b]	REQA/WUPA Request
$63[c]	HLTA Request
$64[d]	Anticollision Select Request
$65[e]	RATS (Request Answer to Select) Request
$66[f]	PPS (Protocol and Parameter Selection Request

[a] Commands $41 (*find token request*), $45 (*pass-through request*), $48 (*transmitter ON request*), and $49 (*transmitter OFF request*) operate in the same form as described for Tag-it transponders.

[b] Commands $61 and $62 (*REQA/WUPA request*) are used by the host computer to request to send a REQA/WUPA data packet over the radiofrequency interface. Command $61 requests the REQA packet, while Command $62 requests the WUPA packet. If the command produces data, the response packet contains four fields: the first field is the entity ID for the ISO 14443 ($02), the second field is the requested command ($61 or $62), the third field contains the standard error codes, and the last field contains bytes 1 and 2 for the ATQA (Answer to Request Type A) data from the token.

[c] Command $63 (*HLTA request*) is used by the host computer to request to send an HLTA data packet. The response contains three fields: the first field is the entity ID for the ISO 14443 ($02), the second field is the requested command ($63), and the third field contains the standard error codes.

[d] Command $64 (*anticollision select request*) is used by the host computer to request the transponder to send either an anticollision or a select packet. The response packet contains three common fields: the entity ID for the ISO 14443 ($02), the requested command ($64), and the standard error codes. If the host requested an anticollision packet, the fourth field varies from 2 to 7 bytes and contains the anticollision packet. If the host requested the select data, the fourth field varies from 2 to 5 bytes containing the SAK (Select Acknowledge) data as well as the CRC over the SAK data.

[e] Command $65 (*RATS [request answer to select] request*) is used by the host computer to request the transponder to send RATS data. Before this command can be used, however, the transponder must have been previously activated by a REQA/WUPA, anticollision, or select commands. The response contains the following four fields: the first field is the entity ID for the ISO 14443 ($02), the second field is the requested command ($65), the third field contains the standard error codes, and the last field contains the CID data assigned to the transponder.

[f] Command $66 (*PPS [protocol and parameter selection] request* is used by the host to request a PPS packet. Once again, before this command can be executed, the transponder must have been previously activated. The response contains the following four fields: the first field is the entity ID for the ISO 14443 ($02), the second field is the requested command ($66), the third field contains the standard error codes, and the last field contains the PPS data, including a CRC over the data sent.

© 2011 by Taylor and Francis Group, LLC

TABLE 8.33

Commands for ISO 14443-3 Type-B Protocol

Command code	Command
$41[a]	Find Token Request
$45	Pass-through Request
$48	Transmitter ON Request
$49	Transmitter OFF Request
$61/$62	REQA/WUPA Request
$63[b]	Slot Marker Request
$64[c]	ATTRIB Request
$65[d]	HLTB Request (Halt type B)

[a] The first five commands are similar to those described for the Type-A protocol, and therefore they will not be repeated here. A difference, however, is that the first field in the request and response packets, the entity ID field, is equal to $03 instead of $02 used for Type-A transponders.

[b] Command $63 (*slot marker request*) is used by the host to request the transponder to send a slot marker packet. The number of available slot markers is between 0 and 15. The response packet contains the following four fields: the first field is the entity ID for the ISO 14443 ($03), the second field is the requested command ($63), the third field contains the standard error codes, and the fourth field is a 14-byte field containing the information requested including a CRC.

[c] Command $64 (*ATTRIB [attribute] request*) is used by the host to request to the transponder to send an ATTRIB packet. The response packet contains the following four fields: the first field is the entity ID for the ISO 14443 ($03), the second field is the requested command ($64), the third field the standard error codes, and the fourth field contains the requested information including a CRC over its data.

[d] Command $65 (*HLTB request*) is used to request a HLTB packet. The response packet contains the following four fields: the first field is the entity ID for the ISO 14443 ($03), the second field is the requested command ($65), the third field contains the standard error codes, and the fourth field contains the requested information including a CRC over its data.

the transponders in the interrogator's reading region to inform them that the inventory process will be coming. The *select* command does not require a response from the transponder.

Each one of the inventory rounds starts with a *query* command. This command passes a value from which the transponder generates a slot counter number. If the transponder generates a slot counter equal to zero, it is allowed to reply to the interrogator by sending a 16-bit random number and at the same time entering its *reply* state. The other transponders enter in a waiting mode. After the interrogator has successfully received the response from the transponder, it generates an *acknowledged* (ACK) command and sends it to the transponder along with the same 16-bit number that it first received from the transponder. This allows the transponder to send back its electronic product code (EPC) number and change the state to *acknowledged*. If it is necessary to perform additional operations in the transponder, the interrogator generates a *Req_RN* command, after which

© 2011 by Taylor and Francis Group, LLC

TABLE 8.34

Commands Supported by Texas Instruments UHF Gen 2 Protocol

Command	Binary Code	Operational Group
Select	1011	Select
ACK	01	Inventory
NAK	11000000	Inventory
Query	1000	Inventory
Query_Adjust	1001	Inventory
Query_Rep	00	Inventory
Req_RN	11000001	Inventory
Read	11000010	Access
Write	11000011	Access
Kill	11000100	Access
Lock	11000101	Access
Access	11000110	Access
Block Write	11000111	Access
Block Erase	11001000	Access

the transponder generates and sends a new 16-bit random number called a *handle* and changes its state to *open*. At this point, the transponder is able to accept operations such as *reading*, *writing*, *lock*, and *kill*. The exchange terminates when the interrogator sends a *Query_Adjust* command, after which the transponder reverts to ready mode. The *Query_Adjust* command causes to lessen the value of the slot counters in the other transponders in the vicinity. The transponder whose slot counter reaches zero is allowed to respond. This process is repeated until all the transponders in the reading area have been found. If two different transponders were to respond at the same time and the interrogator was unable to identify one of them, they will time out and their slot counters will regenerate. These different commands are as follows:

- The *Select* command is the first message that is sent to the transponder. The parameters that are sent with this command are as follows:
  - *Target*: Instructs the transponder to select one of four sessions and either the SL flag or the Inventory flag associated with the session.
  - *Action*: How to set the flag being selected.
  - *MemBank*: Selects a memory bank.
  - *Pointer*: Where to look in the memory bank.
  - *Length*: How many bits (0 to 255) from the memory bank.
  - *Mask*: Data string that will be compared with the data selected in the memory bank.

© 2011 by Taylor and Francis Group, LLC

  - *Truncate*: If a query command specifies Sel = 10 or Sel = 11, the response is truncated to only the EPC data instead of the complete 96 bits.
- *CRC-16*: 16-bit CRC calculated over the command string.

Table 8.35 shows an example of use for the select command.

- The *ACK c*ommand is used by the interrogator to acknowledge the reception of the 16-bit random number sent by the transponder. This command does not need any parameters. When the transponder receives the ACK command, it responds with its EPC data.
- The *not acknowledged* (NAK) command is used to return all the transponders back to the *arbitrary* state. The command does not require any parameter. The command does not generate any responses from the transponders.
- The *query* command initiates the inventory process in order to identify individual transponders. The following parameters are sent with this command:

Divide ratio. Defines the frequency of transmission between the transponder and the interrogator.

Cycles per second. Sets the data rate and the modulation format.

TRext. Used to switch ON or OFF the preamble pilot tone.

Sel. Selects the transponders that will respond (all of them or a selection)

Session. Starts a session. Sessions are named S0, S1, S2, and S3.

Target. Selects between A and B inventory flags.

Q. Sets the number of slots for the inventory round to be used by the slot counter.

CRC-5. 5-bit CRC calculated over the command string.

- The *query adjust* command is used to instruct the transponder to increment or decrement its slot counter value. There are two parameters sent with this command:

Session. S0, S1, S2, or S3. This command ensures that the interrogator is talking to the correct transponder.

Up/Dn. Instructs the transponder to count up or down.

- The *Query_Rep* command is used to instruct the transponder to decrement its slot counter value. If the resulting value is zero, it

© 2011 by Taylor and Francis Group, LLC

TABLE 8.35
Example of Packet Request Structure Using the Select Command

Select Command	Target: SL	Action	EPC Memory Bank (01)	Start Address	Length (8 bits)	Mask	Trunc	CRC-16
1010	100	000	10	01111000	0001000	00000000	1	0111100000010011

© 2011 by Taylor and Francis Group, LLC

transmits a random 16-bit number to the interrogator. This command only needs one parameter:

Session. S0, S1, S2, or S3 is needed to confirm the session from the inventory round.

- The *Req_RN* command is used by the interrogator to instruct the transponder to generate and return a new 16-bit random number. This new random number is called the *handle* and will be used as the identifier between the transponder and interrogator for further commands. After transmitting back this number, the transponder changes its state to open or secure depending on the status of the password. In either state, the transponder is able to accept and process new commands from the interrogator.
- The *read* command allows reading the memory in the transponder in multiples of 16-bit blocks. The *read* command requires the following parameters:

MemBank. Specifies which memory areas will be read.

WordPtr. Defines the address for the first word to be read.

WordCount. Defines the number of 16-bit words that will be read.

Handle. 16-bit identifier between transponder and interrogator.

crc-16. 16-bit CRC calculated from the first command bit to the last CRC bit.

- The *write* command allows writing a word of data to any of the memory locations in the transponder. Before this command can be executed, it is necessary to request a new 16-bit random number. The parameters used with this command are as follows:

MemBank. Specifies which memory areas will be read.

WordPtr. Defines the address for the first word to be read.

Data. 16-bit data word to be written. These data are XORed with the newly generated 16-bit random number.

Handle. 16-bit identifier between transponder and interrogator.

CRC-16. 16-bit CRC calculated on the command string.

- The *kill* command is used to disable a transponder permanently. Due to the irreversible process, the command needs some additional steps to prevent the accidental killing of other transponders in the vicinity of the interrogator. First, the interrogator requests a new 16-bit random number (RN16) from the transponder. Then, the 16 MSBs of the *kill* password are XORed by the interrogator with RN16, and the resulting bits are sent to the transponder. The interrogator

© 2011 by Taylor and Francis Group, LLC

requests a new RN16 that is then XORed with the 16 LSBs of the kill password. After receiving this transmission, the transponder will not respond to any request or commands from the interrogator.

- The *lock* command is used to lock individual passwords preventing reading and writing the password, to lock individual banks preventing new writing to the banks, or to make the password or memory bank permanently locked and unchangeable. The *lock* command requires the following parameters:

Payload. This is a 20-bit mask indicating the memory locations and locking actions to be performed at those locations.

Handle. 16-bit identifier between transponder and interrogator.

CRC-16. 16-bit CRC calculated on the previous data string.

Table 8.36 displays the meaning of the 20 bits that comprise the payload. For the first 10 bits (mask bits), the bit set to *0* means to keep the current settings, ignoring that particular action, while the bit set to *1* means to implement the action that is associated with the action field that is composed of the 10 last bits. The meaning of these last 10 bits (action bits) is shown in Table 8.37. Table 8.38 describes the effects of the different password and lock bits.

- The *access* command is necessary when the access password is different than zero and the transponder has been put into a secured state. To execute the access command, the interrogator requests a new RN16 from the transponders. The bits of this new RN16 number are XORed with the 16 MSBs of the password and sent to the transponder. The interrogator proceeds to request a new random number

TABLE 8.36
Payload Bits in Lock Command

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20
Kill mask		Access mask		EPC mask		TID mask		User mask		Kill action		Access action		EPC action		TID action		User action	

TABLE 8.37
Action Bit Options

Action Bit	Kill Action		Access Action		EPC Action		TID Action		User Action	
Option	1	2	3	4	5	6	7	8	9	10
	Passwd read or write	Perm lock	Passwd read or write	Perm lock	Passwd write	Perm lock	Passwd write	Perm lock	N/A	N/A

© 2011 by Taylor and Francis Group, LLC

TABLE 8.38

Effect of the Different Combinations of Password and Lock Bits

Password status	**Perm lock status**	**Effect**
Passwd Write = 0	Perm lock = 0	Memory bank writable from Open or Secure states
Passwd Write = 0	Perm lock = 1	Memory bank permanently writable from Open or Secure states. Can never be Locked
Passwd Write = 1	Perm lock = 0	Memory bank writable from Secure state but not from Open state
Passwd Write = 1	Perm lock = 1	Memory bank not writable
Passwd Read/Write = 0	Perm lock = 0	Password readable and writable from Open or Secure states
Passwd Read/Write = 0	Perm lock = 1	Password permanently readable and writable from Open or Secure states
Passwd Read/Write = 1	Perm lock = 0	Password only readable and writable from Secured state
Passwd Read/Write = 1	Perm lock = 1	Password not readable or writable from any state

from the transponder that in turn is XORed with the 16 LSBs from the password and sent to the transponder. After having transmitted successfully the second set of XORed bits, the transponder is set into the secure state.

- The *block write* command allows one to write multiple words into the EPC or reserved memory in the transponder using a single command. The parameters used in this command are as follows:

  MemBank. Specifies the memory area to write.

  WordPtr. Defines the address for the first word to be written.

  WordCount. Defines the number of 16-bit words that will be written.

  Data. Data to write.

  Handle. 16-bit identifier between transponder and interrogator.

  CRC-16. 16-bit CRC calculated on the data string.

- The *block erase* command allows erasing multiple words using a single command. The command uses the following parameters:

  MemBank. Specifies the memory bank to be erased.

  WordPtr. Defines the address for the first word to be erased.

  WordCount. Defines the number of 16-bit words that will be erased.

  Handle. 16-bit identifier between transponder and interrogator.

  CRC-16. 16-bit CRC calculated on the data string.

© 2011 by Taylor and Francis Group, LLC

TABLE 8.39

Commands Supported by LF Atmel® Transponders

Command	SOC	OpCode	Description
Read Single Block[a]	00	01	Read single 32-bit data block
Read Multiple Blocks[b]	00	01	Read multiple data blocks
Write Single Block[c]	00	01	Write a single data block
Login_Write[d]	00	0111011110	Login for write password protected access
Login_Read[e]	00	0111011010	Login for read password protected access
Get_ID[f]	00	0000	Starts a complete new anticollision loop
Get_ID (Tag ID – partial even)[g]	00	0000	Anticollision loop with partial ID. Even number of matching ID bits
Ged ID (Tag ID- partial odd)	00	001	Anticollision loop with partial ID. Odd number of matching ID bits
Select[h]	00	0000	Puts specified transponder into selected state
Select_All[i]	00	1000	Selects all transponders within range
Select_Group[j]	00	100[0]n1	Selects a specified group of transponders
Select_N_Group[k]	00	101[0]n1	Selects all transponder that are not members of the group
Reset_Selected[l]	00	11100000	Resets selected transponder to Ready state without reloading configuration register
Reset_to_Ready[m]	00	11000000	Resets all transponders in the field to Ready state. Reloads configuration register from system memory
Arm_Clear[n]	00	11001000	Arms transponder for Clear_All command
Clear_All[o]	00	01011111	Clears memory except traceability data

[a] *Read single block* command reads a complete data block (32 bits) for a transponder in the *selected* state. An optional CRC for the block address can be included in the command. If this is available, the transponder checks the CRC and aborts the operation if the command is not compatible with the received address. When the CRC check is valid or it is not included, the transponder responds with the 32-bit data followed by a CRC. This CRC code is generated over the 32-bit data as well as the memory address used. If the attempted read address is not existent or it is protected, the returned data will be a string of 1′s. In order to read protected memory blocks, this command must be preceded by a successful LoginRead command. The request packet for this command requires the 6-bit block address that is transmitted with its MSB first.

[b] *Read multiple blocks* command reads an array of consecutive 32-bit data blocks from a start address in a transponder that is in the *selected* state. An optional CRC for the address can also be included with the command. When the CRC check is valid or it is not included, the transponder responds with the 32-bit data followed by a CRC. This CRC code is generated over the 32-bit data as well as the memory address used. If the attempted read address is not existent or it is protected, the returned data will be a string of 1′s. In order to read protected memory blocks, this command must be preceded by a successful LoginRead command. The request packet for this command requires two parameters: 6 bits for the address of the start block, and 6 bits for the address of the end block.

[c] *Write single block* command programs a specific memory address in a transponder with a 32-bit block of data and associated lock command. To perform this command, the transponder must be in the *selected* state. If the destination block is password protected, a LoginWrite must be executed before writing. Memory blocks for which their lock bit is set to 1 cannot be written.

© 2011 by Taylor and Francis Group, LLC

TABLE 8.39 (CONTINUED)

Commands Supported by LF Atmel® Transponders

Attempting to write to a locked address results in the immediate termination of the command followed by the appropriate error codes. The command includes a CRC that can be mandatory or optional depending on the status of the configuration register. After successfully receiving the write single block command, the transponder starts the sequence for programming the EEPROM. The programming process includes an automatic read verification to ensure the integrity of the data. To signal the completion of a successful programming cycle, the transponders return an SOF string. The request packet requires three parameters: the 6-bit block address, the lock bit status after programming (2 bits), and the 32-bit data to be written in memory.

[d] *Login_Write* command is used to release the protection against writing on all write-protected data blocks. If the password transmitted with the command is successful, the transponder will generate an SOF string to indicate the success; otherwise, the SOF will be followed by the appropriate error code. After executing this command successfully, all the write-protected memory blocks can be modified as long as the addressed memory block is not already locked. The request command requires three parameters: the string 110111, the string 10, and the 32-bit write password.

[e] *Login_Read* command is used to release the protection against reading on all the data blocks that are set to be read-protected. If the password transmitted with the command is successful, the transponder will generate an SOF string to indicate the success; otherwise, the SOF will be followed by the appropriate error code. After executing this command successfully, all the read-protected memory blocks can be read normally. The request packet requires three parameters: the string 110110, followed by the string 10, and followed by the 32-bit read password.

[f] *Get_ID* command causes all transponders in a ready state to engage into the anticollision loop. This command does not require any additional parameters.

[g] *Get_ID (partial)* command is used following the Get_ID command. All transponders with partial matching IDs reply with their own anticollision response by transmitting the SOF string followed by their IDs.

[h] The *select* command causes the addressed transponder to respond with the 16-bit CRC for its ID, followed by entering into the selected state. After issuing this command, the interrogator can communicate with the addressed transponder until it selects another one. In this case, the first transponder enters the quiet state. This parameter requests the ID of the selected transponder as parameter.

[I] The *Select_All* command causes all transponders in the ready state to enter into the selected state and answer with an SOF string. This command allows for global configuration of a set of transponders without having to program each one of them sequentially. This command does not require additional parameters.

[j] The *Select_Group* command causes all transponders in the ready state with matching partial IDs to enter the selected state and answer with the SOF string. The length of the partial ID can vary. This information is the parameter required by the command.

[k] The *Select_N_Group* command causes all transponders in the ready state with no matching partial IDs to enter the selected state and answer with the SOF string. The length of the partial ID can vary. This information is the parameter required by the command.

[l] The *Reset_Selected* command resets the selected transponders back to the ready state. After receiving the command, transponders respond with the SOF string indicating that they are able to participate in future anticollision sequences. This command does not require any additional parameters.

(*Continued*)

© 2011 by Taylor and Francis Group, LLC

TABLE 8.39 (CONTINUED)

Commands Supported by LF Atmel® Transponders

[m] The *Reset_to_Ready* command sets all the transponders in the radiofrequency field into the ready state. Depending on the configuration of the transponders, these may start transmitting data. After receiving the command, transponders respond with the SOF string indicating that they are able to participate in future anticollision sequences. This command does not require any additional parameters.

[n] The *Arm_Clear* command prepares transponders for the subsequent Clear_All command as long as the master key was not set to 6. If this command is followed by any command other than the Clear_All command, it becomes disabled. This command does not require additional parameters.

[o] The *Clear_All* command clears all the memory blocks and their lock bits for all transponders that had been previously armed with the Arm_Clear command. The clearing of the EEPROM can be understood as a programming process of writing 0's to all memory locations, thus following the same rules as writing to memory. After the transponder memory has been successfully cleared, the transponders respond with the SOF string. If the command fails for any reason, the transponder generates the appropriate error codes. Because of its work with the Arm_Clear command to prepare the transponders for clearing, it can be seen as an additional step in avoiding accidental erasing of data in the memory of the transponders. This command requires three parameters: 011111, followed by 00, followed by 32 bits cleared to *0*.

8.5 Commands Supported by the Atmel® Family of Transponders

The functions of the logic system in the Atmel® family of transponders are the initialization and reloading of configuration in the EEPROM memory control of data read and write, data transmission, command decoding, CRC check, error detection, and handling. These functions are common to all the Atmel® transponders described in this section.

8.5.1 Commands Supported by LF Atmel® Transponders

Atmel® transponders operating in the LF range are available in different memory sizes, with some of them incorporating anticollision capabilities. The commands used for these transponders, shown in Table 8.39, are divided into two parts. The first two bits, called *start of command* (SOC), are always set to 00 as they are used for autocalibration purposes. The rest of the bits, called the *OpCode*, carry the specific command information.

Table 8.40 describes the codes that can be generated as a response to an invalid command for the type of transponder receiving the command, or as a response to an invalid command sequence.

© 2011 by Taylor and Francis Group, LLC

TABLE 8.40

Error Codes for LF Atmel® Transponders

Error code	Error
0111	Incorrect number of bits in command format
1110	Corrupt command encoding
0010	Attempt to write a locked block
0100	Attempt to write a protected block without previous login
1000	Command format error for Login or Write
1101	Incorrect password for Login
1011	CRC error
1010	Program 0 verification error
0110	Program 1 verification error
Other codes	Reserved

8.5.2 Commands Supported by HF Atmel® Transponders

Table 8.41 shows the commands supported by Atmel® transponders operating in the HF RFID band along with their functional classification. All these commands have a length of 12 bytes.

Table 8.42 summarizes the parameters of these data transfer commands.

8.5.3 Commands Supported by UHF Atmel® Transponders

The Atmel® transponders operating in the UHF band support two types of commands, long commands and short commands, as shown in Table 8.43.

Long commands consist of the 6-bit command and a 2-bit CRC code that the interrogator transmits to the transponder. After the transponder evaluates the CRC positively, the transponder interprets the next 8-bit stream as a parameter field. This can be followed by an address field, data field, or both depending on the command being used. The command ends with an end-of-transmission code that is built by using two end-of-file (EOF) symbols.

The *reset* command is the only command used for IC control. This is used to reset the control logic in the transponder or to reset the contents of the Status1 register. When the whole control logic is reset, the transponder does not transmit any information back to the interrogator. Group selection commands are used to address the whole memory. The page start address is fixed by the Group_ID or Group_AFI commands. Anticollision commands are used to address the whole memory. The page stat address is fixed by the Anticollision_ID command.

Short commands consist of a 4-bit command, a 2-bit modulation mode, and a 2-bit CRC code. Short commands do not have a parameter field following the actual command. The 2-bit modulation code is as follows:

© 2011 by Taylor and Francis Group, LLC

TABLE 8.41

Commands for HF Atmel® Transponders

Command	Functional Classification
REQB/WUPB[a]	Anticollision
ATTRIB[b]	Anticollision
HLTB[c]	Anticollision
SlotMARKER[d]	Anticollision
READ[e]	Data Transfer
WRITE[f]	Data Transfer
LOCK[g]	Data Transfer
CHECK_PASSWORD[h]	Data Transfer
DESELECT[i]	Data Transfer
COUNT[j]	Data Transfer

[a] *REQB/WUPB* command is used by the interrogator to search for transponders in its radio-frequency field or to wake up those transponders in the halt state. The first byte in this command must be $05, and the second byte must be either $00 or $01. The third byte of the command is used to select between the REQB (search for transponders in the field) and WUPB (wake up transponders) functions. The response to this command by the transponder is a packet containing information about its identification data, application data, and other parameters of interest.

[b] *ATTRIB* command is used to select the transponders that have responded to an REQB/WUPB command. The transponder responds to ATTRIB commands with bytes that match their identification stored in memory. Those transponders that respond to this command are placed in the active state, allowing responding to data transfer commands.

[c] *HLTB* command is used to set a transponder into a halt state. In the halt state, transponders can only respond to the WUPB command.

[d] *SlotMARKER* command is used by the interrogator to query transponders for their random number status used for anticollision protocols.

[e] *READ* command causes the transponder to transmit the 64-bit data to the interrogator. A password is not required to read pages 0, 1, and 2 for these interrogators, but is necessary to access other pages. Page 3, which stores the password, cannot be read directly. The response of a valid READ command is a 12-byte data frame containing the referenced 64-bit data.

[f] *WRITE* command stores data into the 64-bit page referenced with the command. The data to write are sent immediately following the command. Those pages are read-only, are locked, or, in cases where the proper password has not been used, cannot be written. This generates the appropriate error code.

[g] *LOCK* command locks the memory address specified in the command to future changes, although pages can still be read using the appropriate password.

[h] *CHECK_PASSWORD* command is used to open a transponder to future commands. The 64-bit data embedded with the command are checked against the stored password in page 3 of the transponder. This command needs to be executed before issuing most commands. Once the transponder is open, the password can be changed by writing new data into page 3 that store the password using the WRITE command.

[i] *DESELECT* command is used to put the transponder into the halt state. This command has the same effects as the HLTB command used for anticollision functions.

[j] *COUNT* command is used to write to page 2 of the memory that contains the identification data and the count counter. The counter is a 16-bit data block that is incremented each time that this command is executed until it reaches the value $8000, after which it cannot be further incremented. At this point, page 2 becomes locked against future modifications.

© 2011 by Taylor and Francis Group, LLC

TABLE 8.42

Data Transfer Parameters for Selected Commands

Command	**Byte 1**	**Byte 2**	**Bytes 3–10**	**Bytes 11–12**
READ	$4	Address	----	CRC
WRITE	$3	Address	64-bit data	CRC
LOCK	$2	----	32 first bits ignored 32 lasts bits data	CRC
CHECK_ PASSWORD	$6	----	64-bit data	CRC
DESELECT	$A	----	----	CRC
COUNT	$E	----	16 first bits ignored 48 lasts bits data	CRC

00: NRZI soft locked
01: 3Phase1
10: NRZI notch locked
11: FMO

© 2011 by Taylor and Francis Group, LLC

TABLE 8.43

Commands Supported by UHF Transponders

Short / Long Command	Command Type	Command Name	Command Code	Description
Long	IC Control	Reset[a]	001010	Reset of circuit or parts of status1 register
Long	Group Selection	Group_ID	000011	Select group through ID
Long	Group Selection	Group_AFI	000001	Select group through AFI
Long	Group Selection	Group_p	010010	Group select supporting address and bit pointer
Long	Group Selection	Group_p_leeq	010110	Group select supporting address and bit pointer
Long	Group Selection	Group_p_greq	010111	Group select supporting address and bit pointer
Long	Anticollision	Anticollision_ID	000000	Anticollision targeting ID
Long	Anticollision	Anticollision_p	010011	Anticollision supporting address and bit pointer
Long	Anticollision	Anticollision_p_random	010101	Anticollision supporting address, bit pointer and random
Long	Reading	Read32[b]	000100	Read 32 bits in loop
Long	Reading	Read32c	100100	Read 32 bits in loop
Long	Reading	Read128[c]	001100	Read 128 bits in loop
Long	Reading	Read128c	100110	Read 128 bits in loop
Long	Program	Program4byte[d]	001000	Immediate 32-bit programming
Long	Program	Program4bytec	100000	Immediate 32-bit programming
Long	Program	Programnbyte[e]	011000	Up to 32-bit programming. Possible to select 8 bit portions
Short	Reading	Get_ID_page[f]	0101	Same as read128c
Short	Reading	Get_system[g]	0110	Reads system information
Short	Anticollision	Wakeup_s	0001	Answer in one of 16 slots (selected transponders)
Short	Anticollision	Wakeup_sb	0010	Answer in one of 16 slots (nonselected transponders)
Short	Anticollision	Repeat_arb	0100	Repeats long arbitration

© 2011 by Taylor and Francis Group, LLC

Short	Anticollision	Slot	1000	Aloha
Short	Anticollision	Slot_selected	1001	Aloha
Short	Anticollision	Slot_not_selected	1010	Aloha
Short	Anticollision	Slot_repeat	1011	Aloha
Short	Anticollision	Skip_slot	1100	Aloha
Short	Anticollision	Slot_close	1101	Aloha
Short	Temporary	Repeat_arb		Speed up anticollision
Short	Temporary	Skip_slot		Aloha

---

[a] The *reset* command generates a complete or partial soft reset in the transponder. The reset command must be followed by the 8-bit parameter specifying the actions of the command and the 16-bit CRC. When bit 7 (MSB) of the parameter is set to *1*, the transponder does not transmit a response packet.

[b] The *Read32* and *Read32c* commands are used to read memory. Read32 reads a 32-bit block of user memory, while Read32c reads a 32-bit block of the control memory. Other than this distinction, both commands are similar. The Read32 or Read32c commands must be followed by the 8-bit parameter, the optional address field that is only used in the long addressing mode, the CRC code, and two end-of-file (EOF) symbols. After executing the command successfully, the transponder returns the status2 register, the 32-bit data block that has been read, and the CRC code.

[c] The *Read128* and *Read128c* commands are also used to read memory. Read128 reads a full page of user memory, while Read128c reads a full page of the control memory. Both commands must be followed by the 8-bit parameter, the optional address field that is only used in the long addressing mode, the CRC code, and two end-of-file (EOF) symbols. After executing the command successfully, the transponder returns the status2 register, the 128-bit data block that has been read, and the CRC code.

[d] The *Program4byte* and *Program4bytec* commands enable the interrogator to write the user and control memory respectively. These commands can be used in long mode (addressed) or short mode (nonaddressed). After receiving the command, the interrogator must transmit the 8-bit parameter, the address (only in long mode), the 32-bit data, and the CRC code.

[e] The *Programnbyte* command is a long command that requires an address field. This command is used to write to a portion of the selected block. The block number and page information are transmitted in the address field.

[f] The *Get_ID_page* command returns the ID stored in memory. This is a short command that does not require an address or an additional parameter. After the transponder has received the command, it transmits the 8-bit Status2 register data, followed by the 128-bit ID page, finishing with the CRC code for all of the data stream.

[g] The *Get_system* command is also a short command. The transponder transmits the 8-bit Status2 register data, the 320-bit system memory data, followed by the CRC code.

© 2011 by Taylor and Francis Group, LLC

References and Further Reading

Because radiofrequency identification (RFID) is a relatively new technology, the most current information about the different parts that compose the whole RFID system come directly from the manufacturers. For this reason, the majority of the documents that are referenced here are data sheets and application notes from the key manufacturers of RFID components. Although these references do not contain URLs because of their frequent change, interested readers should not experience any problems locating these documents in the manufacturer's websites. The books listed in this section discuss fundamental work in their subject area.

1 Books

Balanis, C. *Antenna theory: Analysis and design*, 3rd ed. Hoboken, NJ: Wiley-Interscience, 2005.

Cheng, D. *Fundamentals of engineering electromagnetics*. Reading, MA: Addison-Wesley, 1993.

Dobkin, D. M. *The RF in RFID: Passive UHF RFID in practice*. Burlington, MA: Newness, 2008.

Johnson, R. *Antenna engineering handbook*, 3rd ed. New York: McGraw-Hill Professional, 1992.

Schmitt, R. *Electromagnetics explained: A handbook for wireless/RF, EMC, and high-speed electronics*. Burlington, MA: Addison-Wesley, 2002.

Ulaby, F. *Fundamentals of applied electromagnetics*. Upper Saddle River, NJ: Addison-Wesley, 2004.

2 Technical Literature from Atmel®

2.1 Application Notes from Atmel®

ATA5590 Tag antenna connection. Document 4936B-RFID-08/07.

ATA5590 Tag antenna matching. Document Rev. 4843A-RFID-02/05.

Tag tuning/RFID. Document Rev. 2055A-RFID-07/02.

U2270B Electronic immobilizers for the automotive industry. Document Rev. 4661A-RFID-06/03.

U2270B Extended RFID reading distance by using U2270B with an additional preamplifier. Document Rev. 4592A-RFID-12/02.

© 2011 by Taylor and Francis Group, LLC

2.2 Data Sheets from Atmel®

AT88RF020 13.56 Mhz, 2048-bit RFID EEPROM. Document Rev. 2010C-RFID-2/06.

AT88SC6416CRF. 13.56 MHz CryptoRF EEPROM memory 64 kbits. Document Rev. 5006CS-CRRF-12/06.

AT88SC3216CRF. 13.56 MHz CryptoRF EEPROM memory 32 kbits. Document Rev. 5005CS-CRRF-12/06.

AT88SC1616CRF. 13.56 MHz CryptoRF EEPROM memory 16 kbits. Document Rev. 5026CS-CRRF-12/06.

AT88SC0808CRF. 13.56 MHz CryptoRF EEPROM memory 8 kbits. Document Rev. 5027CS-CRRF-12/06.

AT88SC0404CRF. 13.56 MHz CryptoRF EEPROM memory 4 kbits. Document Rev. 5023CS-CRRF-12/06.

AT88SC0204CRF. 13.56 MHz CryptoRF EEPROM memory 2 kbits. Document Rev. 5022CS-CRRF-12/06.

AT88SC0104CRF. 13.56 MHz CryptoRF EEPROM memory 1 kbits. Document Rev. 5021CS-CRRF-12/06.

ATA5558 Preliminary. 1 kbit R/W IDI© with deterministic anticollision. Document Rev. 4681C-RFID-09/05.

ATA5567 Multifunctional 330-bit read/write RF identification IC. Document 4874E-RFID-10/07.

ATA5590 TAGIDU™. 1.3-kbit UHF R/W IDIC© with anti-collision function. Document 4817C-RFID-03/07.

TK5530 Read-only transponder. Document Rev. 4683D-RFID-11/05.

TK5551 Standard read/write ID transponder with anti-collision. Document 4709F-RFID-06/06.

U2270B Read/write base station. Document 4684E-RFID-02/08.

U3280M Transponder interface for microcontroller. Document 4688D-RFID-03/07.

3 Technical Literature from Microchip

3.1 Application Notes from Microchip

AN232 Low-frequency magnetic transmitter design. Document DS00232B. 2008.

AN678 RFID coil design. Document DS00678B. 1998.

AN680 Passive RFID basics. Document DS00680D. 2004.

AN680 RFID tag and COB development guide with Microchip's RFID devices. Document DS00830B. 2002.

AN707 MCRF 355/360 application note: Mode of operation and external resonant circuit. Document DS00707B. 2001.

AN710 Antenna circuit design for RFID applications. Document DS00710C. 2003.

AN752 CRC algorithm for MCRF45X read/write device. Document DS00752A. 2001.

AN759 Interface control document for the 13.56 MHz anti-collision interrogator. Document DS00759B. 2002.

AN912 Designing LF talkback for a magnetic base station. Document DS00912A. 2004.

ASK Reader reference design. Document DS5116C. 1998.

© 2011 by Taylor and Francis Group, LLC

FSK Reader reference design. Document DS51137B. 1998.
FSK Anti-collision reader reference design. Document DS5167B. 1998.
PSK Reader reference design. Document DS51138B. 1998.
MCRF2XX using the microID® programmer. Document DS51139C. 2004.
MCRF355/360 Reader reference design. Document DS21311B. 2001.
MCRF45X Reference design. Document DS21654C. 2004.

3.2 Data Sheets from Microchip

MCRF200 125 kHz microID® passive RFID device. Document DS21219H. 2003.
MCRF 355/360 13.56 MHz passive RFID device with anti-collision feature. Document DS21287F. 2002.
MCRF450/451/452/455 13.56 MHz read/write passive RFID device. Document DS40232H. 2003.

4 Technical Literature from Texas Instruments

4.1 Application Reports from Texas Instruments

Antenna selection guide. Application note AN058. Document SWRA161.
Constructing a 1000 x 600 HF antenna. Document 11-08-26-007. 2003.
HF antenna cookbook. Document 11-08-26-001. 2004.
HF antenna design notes. Document 11-08-26-003. 2003.
Integrated TIRIS™ RF module TMS3705A Introduction to low frequency radar. Document SCBA020. 1999.
LF reader synchronization. Document SCBA019. 2004.

4.2 Reference Guides from Texas Instruments

Antenna reference guide. Document SCBU025. 1996.
Antenna tuning indicator. RI-ACC-ATI2. Document SCBU031. 2001.
Series 2000 reader system. 4-channel TX/RX multiplexer module for remote antenna RFM RI-MOD-Tx8A. Document 11-06021-039. 2000.
Series 2000 reader system. ASCII protocol. Document SCBU028. 2000.
Series 2000 reader system. Control modules RI-CTL-MB2A, RI-CTL-MB6A. Document SCBU024. 2000.
Series 2000 reader system. High performance reader frequency module. RI-RFM-007B. Document SCBU022. 2002.
Series 2000 reader system. High performance remote antenna-reader. Frequency module RI-RFM-008B. Antenna tuning board RI-ACC-008B. Document SCBU023. 2002.
Series 2000 reader system. Micro-reader RI-STU-MRD1. Document SCBU027. 2000.
Series 2000 reader system. Mini-RFM RI-RFM-003B. Document SCBU021. 2000.
Series 2000 reader system. Reader S251B RI-STU-251B. Document SCBU025. 2000.
Series 2000 reader system. RFM sequence control. Document 11-06021-049. 1999.

© 2011 by Taylor and Francis Group, LLC

Series 2000 reader system. Standard radio frequency module RI-RFM-104B. Document 11-06-21-035. 2002.

Series 2000 reader system. TIRIS bus protocol. Document SCBU026. 2000.

Reader series 4000. S4100 Multi-function reader module RF-MGR-MNMN. Base application protocol reference guide. Document 11-01-21-700. 2003.

Reader series 4000. S4100 Multi-function reader module RF-MGR-MNMN. ISO 14443 library reference guide. Document 11-01-21-702. 2003.

Reader series 4000. S4100 Multi-function reader module RF-MGR-MNMN. ISO 15693 library reference guide. Document 11-06-21-707. 2004.

Reader series 4000. S4100 Multi-function reader module RF-MGR-MNMN. Tag-it™ library reference guide. Document 11-06-21-708. 2003.

HF reader system series 6000. S6350 Midrange reader module RI-STU-TRDC-02. Document 11-06021-700. 2002.

HF reader system series 6000. S6700 Multi-protocol transceiver IC RI-R6C-001A. Document SCBU030. 2005.

HF reader system series 6000. Gate antenna RI-ANT-T01A. Document 11-06-21-058. 2001.

Tag-it™ Transponder inlays. Document 11-09-21-055. 2001.

Tag-it™ HF-I pro transponder inlays. Document SCBU009. 2005.

Tag-it™ HF-I standard transponder inlays. Document SCBU006. 2005.

Tag-it™ HF-I plus transponder inlays. Document SCBU004. 2005.

Tag-it™ reader system series 6000. Host protocol. Document 11-04-21-001. 1999.

Tag-it™ reader system series 6000. Reader module RI-R00-3230A. Reader module with RS232 interface RI-R00-321A. Document 11-06-21-048. 2001.

Tag-it™ transponder protocol. Document SCBU032. 2000.

Texas Instruments registration and identification system. Description of multi-page, selective addressable and selective addressable (secured) transponders. Document SCBU020. 1999.

TI UHF Gen2 protocol. Document SCBU001. 2006.

TI UHF Gen2 IC antenna design. Document SCBU015. 2006.

4.3 Data Sheets from Texas Instruments

113.56 MHz encapsulated standard transponder. Document RF-HDT-DVBE-N0. 2006.

Series 2000 antennas. Document SCBS845. 2002.

Series 2000 stick antenna. Document SCBS581. 2005.

Series 2000 control module. Document SCBS845. 2003.

Series 2000 high performance remote antenna RFM and tuning module. Document SCBS850. 2001.

Series 2000 reader S251B. Document SCB852. 2001.

HF reader system series 6000 gate antenna. 2001.

S4100 multi-function reader module data sheet. 2003.

Tag-it™ HF-I transponder inlay—square. 2005.

Tag-it™ HF-I transponder inlay—large rectangle. Document SCBS820. 2005.

Tag-it™ HF-I plus transponder inlays—large rectangle. 2005.

© 2011 by Taylor and Francis Group, LLC

The ARRL Guide to
Antenna Tuners

A Radio Amateur's Guide to Antenna Matching



Joel R. Hallas, W1ZR

The ARRL Guide to
Antenna Tuners

A Radio Amateur's Guide to Antenna Matching



Joel R. Hallas, W1ZR

On the Cover

The group of special purpose antenna tuners made by the late George Badger, W6TC, is shown beneath his rotary antenna system. The inset shows a general purpose L-network antenna tuner built by Barry Shackleford, W6YE, who took both photos. Both are discussed in Chapter 15.

Production
Michelle Bloom, WB1ENT
Jodi Morin, KA1JPA
David Pingree, N1NAS

Cover
Sue Fagan, KB1OKW

Copyright © 2010-2012 by
The American Radio Relay League, Inc.

Copyright secured under the Pan-American Convention

International Copyright secured

All rights reserved. No part of this work may be reproduced in any form except by written permission of the publisher. All rights of translation are reserved.

Printed in Canada

Quedan reservados todos los derechos

IBSN13: 978-0-87259-098-4

1st Edition
2nd Printing

Foreword

Antenna Tuners are mystical devices that are sometimes needed between antenna systems and transmission lines or radios to make everything play the way it's supposed to. They are the subject of considerable confusion and misunderstanding by many Amateur Radio operators.

This book is intended to assist readers who have a basic knowledge of antennas, such as conveyed by *Basic Antennas — Understanding Practical Antennas and Designs*, in gaining an understanding of whether or not they need an antenna tuner in their station.[1] If it turns out one is needed, this book will help the reader decide the type of tuner needed and where in the system it should be applied. Also provided are descriptions of appropriate applications of such devices and antennas that are well suited for such use.An additional chapter provides data collected from ARRL Laboratory product reviews of representative antenna tuners to assist in tuner selection. Design methodology and specific design details are also provided for those who wish to build their own tuners.

As with all ARRL books, be sure to check to see if there are any last minute changes that didn't get into the book before it went to the printer. Updates and errata, if any, can be found at **www.arrl.org/product-notes/**.

David Sumner, K1ZZ
Executive Vice President
Newington, Connecticut
October 2010

---

[1] J. Hallas, W1ZR, *Basic Antennas — Understanding Practical Antennas and Designs,* Available from your ARRL dealer or the ARRL Bookstore, ARRL order no. 9994. Telephone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.org/arrl.store/**; **pubsales@arrl.org**.

Acknowledgements

I would like to offer my special thanks to the ARRL production and editorial staff who made this book come together smoothly. In addition, thanks go to my long-suffering wife Nancy, W1NCY, who put up with the countless hours of my writing to make this happen.

I especially appreciated the tireless efforts of ARRL Technical Advisor Barry Shackleford, W6YE, who carefully examined every page of the manuscript in an effort to make sure there were neither technical nor grammatical errors and that all points were made clearly.

About the ARRL

The national association for Amateur Radio

The seed for Amateur Radio was planted in the 1890s, when Guglielmo Marconi began his experiments in wireless telegraphy. Soon he was joined by dozens, then hundreds, of others who were enthusiastic about sending and receiving messages through the air—some with a commercial interest, but others solely out of a love for this new communications medium. The United States government began licensing Amateur Radio operators in 1912.

By 1914, there were thousands of Amateur Radio operators—hams—in the United States. Hiram Percy Maxim, a leading Hartford, Connecticut inventor and industrialist, saw the need for an organization to band together this fledgling group of radio experimenters. In May 1914 he founded the American Radio Relay League (ARRL) to meet that need.

Today ARRL, with approximately 150,000 members, is the largest organization of radio amateurs in the United States. The ARRL is a not-for-profit organization that:

- promotes interest in Amateur Radio communications and experimentation
- represents US radio amateurs in legislative matters, and
- maintains fraternalism and a high standard of conduct among Amateur Radio operators.

At ARRL headquarters in the Hartford suburb of Newington, the staff helps serve the needs of members. ARRL is also International Secretariat for the International Amateur Radio Union, which is made up of similar societies in 150 countries around the world.

ARRL publishes the monthly journal *QST*, as well as newsletters and many publications covering all aspects of Amateur Radio. Its headquarters station, W1AW, transmits bulletins of interest to radio amateurs and Morse code practice sessions. The ARRL also coordinates an extensive field organization, which includes volunteers who provide technical information and other support services for radio amateurs as well as communications for public-service activities. In addition, ARRL represents US amateurs with the Federal Communications Commission and other government agencies in the US and abroad.

Membership in ARRL means much more than receiving *QST* each month. In addition to the services already described, ARRL offers membership services on a personal level, such as the ARRL Volunteer Examiner Coordinator Program and a QSL bureau.

Full ARRL membership (available only to licensed radio amateurs) gives you a voice in how the affairs of the organization are governed. ARRL policy is set by a Board of Directors (one from each of 15 Divisions) elected by the membership. The day-to-day operation of ARRL HQ is managed by a Chief Executive Officer.

No matter what aspect of Amateur Radio attracts you, ARRL membership is relevant and important. There would be no Amateur Radio as we know it today were it not for the ARRL. We would be happy to welcome you as a member! (An Amateur Radio license is not required for Associate Membership.) For more information about ARRL and answers to any questions you may have about Amateur Radio, write or call:

ARRL—The national association for Amateur Radio
225 Main Street
Newington CT 06111-1494
Voice: 860-594-0200
Fax: 860-594-0259
E-mail: **hq@arrl.org**
Internet: **www.arrl.org/**

Prospective new amateurs call (toll-free):
800-32-NEW HAM (800-326-3942)
You can also contact us via e-mail at **newham@arrl.org**
or check out *ARRLWeb* at **http://www.arrl.org/**

Table of Contents

Chapter 1	Why Might I Need an Antenna Tuner
Chapter 2	A Look at a Typical Configuration
Chapter 3	So Just What is an Antenna Tuner?
Chapter 4	Tuning an Antenna Tuner
Chapter 5	The Internal Tuner — How Does it Help?
Chapter 6	An External Tuner at the Radio
Chapter 7	Transmission Lines and Loss
Chapter 8	Moving the Tuner to the Back 40
Chapter 9	Transmission Line Choices for Low Loss
Chapter 10	Balanced versus Unbalanced Lines
Chapter 11	So What's a Balun, an Unun, a Choke?
Chapter 12	Balanced Antenna Tuners
Chapter 13	Antennas that Work Well with Tuners
Chapter 14	A Survey of Available Tuners
Chapter 15	Making Your Own Tuner
Appendix A	Using Decibels for Loss Calculations

Chapter 1

Why I Might Need an Antenna Tuner

Amateur Radio station W1ZR, home station of the author. The unit on the far left is an early Ten-Tec 238 manual antenna tuner.

Contents

Radio Incompatibility? 1-2

Does My Antenna Have to be a Resistor? 1-2

So What's the Problem? 1-3

What Happens if the Radio and Antenna Aren't Matched? 1-3

So What Can We Do? 1-4

What's in a Name? 1-5

Review Questions 1-6

To transmit radio signals, you need a transmitter, often the transmitter side of a *transceiver* — a combined transmitter and receiver — and an antenna. Of course you will need a few other things such as legal authority to transmit, from the FCC in the US, a power source and an information source, such as a telegraph key, microphone or PC. In this book we will focus on the interconnection between the transmitter and the antenna, leaving the other topics to other books.

You might notice that, in spite of the book's title, we didn't mention antenna tuners — a device that goes between the transmitter and antenna. This is because, strictly speaking, an antenna tuner isn't necessary, at least not in all cases. The antenna tuner is only required if the transmitter can't put its output power into the antenna because of an incompatibility between them.

Radio Incompatibility?

A radio transmitter comes with a set of specifications. For proper operation, the owner is responsible to ensure that the requirements listed in the specifications are met. Some are straightforward, such as "power required: 13.8 V dc at 20 A max." If we plugged such a radio into a 120 V ac outlet, we wouldn't have a right to expect it to operate properly — in fact we might expect to see smoke and flames. We would need an intermediate device, called a power supply, to transform the 120 V ac in our outlet to the 13.8 V dc our radio wants.

The compatibility issue we will be considering here is one relating to the *ANTENNA IMPEDANCE* specification. While not all transmitter specifications include an explicit antenna specification, most will say something like *ANTENNA IMPEDANCE, 50 Ω (Unbalanced)* or possibly *ANTENNA IMPEDANCE, 50 Ω (Unbalanced) with SWR of 2:1 or less.* These specifications indicate the load that the antenna system must present to the radio for proper operation. We will discuss the different parts of this specification and what they mean as we go forward. As with the power supply, if the antenna doesn't meet the specification's requirements, we might need an intermediate device — possibly an antenna tuner.

Does My Antenna Have to be a Resistor?

The indication "50 Ω" does sound a lot like a resistor. The radio will be very happy to put its power into an actual 50 Ω resistor, in fact that's how we often test a radio when we don't want the radio signal to go out over the air. Unfortunately, a resistor absorbs the transmitter power and turns it into heat — it does not make a good antenna.

In a properly designed antenna, it is often the case that the antenna's radiating properties will be converted into a load that acts like a 50 Ω resistor to the radio, but actually radiates the power as radio waves.

So What's the Problem?

It would seem that we can solve our incompatibility problem by just buying (or building) an antenna that has a compatible specification of a 50 Ω resistive impedance and connecting it to our radio. This is quite true, and can be very successful — within certain constraints (see **Figure 1-1** for the ideal case). This compatible case is referred to as a *matched* system. Unfortunately, the real world rears its ugly head in a few ways:


ARRL0624
100 W Radiated Power
50 Ω Antenna Impedance
100 W Transmitter with 50 Ω Output Impedance
50 Ω Lossless Transmission Line

Figure 1-1 — Radio and antenna system with matched impedances.

- The biggest issue is that any antenna will have its particular design impedance on a single frequency. This is not an issue with many radio services — broadcast stations, for example — that operate on a single assigned frequency. Some services, such as the Amateur Radio service, operate within assigned bands. Shifting frequency from one end of the band to the other can result in a significant change in antenna impedance.
- A real antenna is always installed at some height above the local terrain. The electrical properties of the soil and the height above ground will have a significant impact on antenna impedance. For example, perhaps the simplest antenna, a half wave horizontal dipole has an impedance that varies from around 40 to 100 Ω as it moves from 0.1 to 0.35 λ (wavelengths) above ground.

What Happens if the Radio and Antenna Aren't Matched?

Most radios can tolerate a certain amount of mismatch from an antenna system without any problems. This is often specified in terms of standing wave ratio (SWR), a measure of mismatch. Often the allowed value is 2:1; which, for a 50 Ω system, would represent resistive values of 25 or 100 Ω (50/2, or 50 × 2).[1] Note that while the radio will operate without damage at this level of mismatch, it may not operate quite as well as if it were matched.

A mismatched load impedance in early solid state transmitters could result in damage to components in the power amplifier stages due to higher voltages or currents than it was designed to handle. Modern transceivers have *fold-back* circuitry that senses the mismatch and reduces transmitter power to avoid damage. Note that while the transmitter will not be damaged, and still can be used, it will put out less power, sometimes beginning to fold back at an SWR as low as 1.5:1. This is perhaps the most common reason that we might notice our 100 W transmitter actually putting out 25 W.

---

[1] In addition to these two resistive values, there is a whole set of combinations of resistive and reactive impedance components that will also result in an SWR of 2:1.

So What Can We Do?

Perhaps not surprisingly, one solution to this issue is something that is generally called an *antenna tuner*. The antenna tuner is a variable impedance transforming device that can transform the impedance of an antenna system so that it appears to the transmitter as a 50 Ω load, while causing almost all of the transmitter power to be radiated from the antenna, just as if everything were matched.

As shown in **Figure 1-2**, the antenna tuner can be placed directly at the transmitter and connect directly to an antenna. In many cases, a *transmission line* is used between the transmitter and the antenna. We will discuss transmission lines in more detail later, but for now be aware that a transmission line is frequently used if the transmitter and antenna are not in the same place. As shown in **Figures 1-3** and **1-4**, the antenna tuner can be placed at either the antenna end or the radio end of a transmission line interconnecting the radio and antenna. It could even be put at an intermediate point.

Much of this book will discuss the details of the different configurations and requirements of antenna tuners and where they are located, so you can make the most informed decision on what type of tuner to buy or build and where to install it.


ARRL0625
Almost 100 W
Radiated Power
100 W Transmitter with
50 Ω Output Impedance
Antenna
Tuner
Unknown Antenna
Impedance
50 Ω Load
Impedance

Figure 1-2 — Antenna tuner collocated with the radio and the antenna. All the transmitter power reaches the antenna except for any loss in the tuner, generally less than 5%.


ARRL0626
Almost 100 W
Radiated Power
Unknown
Antenna
Impedance
100 W Transmitter with
50 Ω Output Impedance
Antenna
Tuner
50 Ω Load
Impedance

Figure 1-3 — Radio and antenna system with tuner located at the radio end of the transmission line.


ARRL0627
Almost 100 W
Radiated Power
Antenna
Tuner
Unknown
Antenna
Impedance
100 W Transmitter with
50 Ω Output Impedance
50 Ω Coax Cable
50 Ω Load
Impedance

Figure 1-4 — Radio and antenna system with tuner located at the antenna end of the transmission line.

What's in a Name?

Over the years there has been some discussion of what to call this device I call an *antenna tuner*. There are those who would say that *antenna tuner* is a misnomer because it doesn't actually tune the antenna, but really tunes the transmission line in most applications.

Over the years many other terms have been used to describe this device. You will see references to an *antenna coupler*, *antenna tuning unit* (ATU) and a *transmatch* — all within various ARRL magazines and books. They all mean the same thing and refer to the same type of device.

The best name I've heard for this function is *antenna system matching device*. Since that doesn't resolve itself to an easy to pronounce acronym, throughout this book I will use the most common term *antenna tuner* with neither apology nor regret.

Review Questions

1-1 Under what conditions is there no requirement for an antenna tuner in a transmitting system?

1-2 How can you tell if an antenna tuner is needed?

1-3 What are the likely consequences of not having an antenna tuner, or having a misadjusted antenna tuner?

1-4 If an antenna tuner is properly adjusted on one frequency, what must be done if the operating frequency is changed?

Chapter 2

A Look at Typical Configurations



The classic half-wave dipole — an antenna mainstay at many amateur stations.

Contents

A Transmission Line — The Piece in the Middle.......................2-2

Dipole for the 40 Meter Amateur Band..2-3

The Dipole for the 80 Meter Amateur Band.......................................2-4

Fractional Bandwidth 2-5

Review Questions...2-6

A very popular antenna for a new radio amateur is called a *half-wave dipole*. This antenna is easy to construct from two pieces of wire with a total length of about 468/f, where f is the frequency in MHz and the result is in feet. The antenna is often fed with 50 Ω coaxial cable as shown in **Figure 2-1**. Generally, the antenna length is trimmed equally on each side of center until the closest match to 50 Ω is found. While it will function as shown, more predictable performance is often obtained by inserting a device between the inherently balanced antenna and unbalanced (with respect to ground) coaxial cable to provide an appropriate transition between them. This device is generally called a balun — for balanced to unbalanced transition. We will discuss this in detail later in the book.



Figure 2-1 — The half wave dipole antenna. This is a very effective antenna, considering its ease of construction and low cost.

A Transmission Line — The Piece in the Middle

In most cases the antenna and radio are located in separate areas. Most often, the optimum location for the radio is somewhere that a person can comfortably operate a radio. For many types of radio systems, this means indoors. The antenna, on the other hand, is typically located outside so it can radiate with minimal obstructions and with at optimum height above the terrain.

It is possible to meet both requirements if an antenna is connected to the radio system through a *transmission line*. An ideal transmission line conveys energy from one end to the other in a totally transparent manner. A real transmission line, on the other hand does so with some limitations:

- Each type of transmission line has a characteristic impedance, Z_0. If the transmission line is terminated with an impedance equal to the Z_0, the same impedance will be seen at any length of line. Fortunately, there are many types of line that have a Z_0 of 50 Ω, so such a line connected to an antenna with a 50 Ω impedance will present a 50 Ω load to the radio no matter the length of the line. It is worth mentioning briefly at this point that if the line is terminated in an impedance other than its Z_0, the impedance at the far end in general will be neither the terminating impedance nor the Z_0 of the line.

These topics will be covered in much more detail later, but it's good to have an idea as we go through the basics.

- Real transmission lines have some associated losses. Thus not all the power put into the bottom by the transmitter comes out at the antenna. The attenuation is higher with increasing frequency, for a given type of line. The attenuation is also directly proportional to line length. In addition, the attenuation increases with standing wave ratio (SWR, a measure of mismatch) — another reason to have a matched system, if possible. We will discuss this phenomenon later.
- SWR is generally determined by measuring the ratio of reflected power to forward power. An SWR of 1:1 results in no reflected power. If the line has significant attenuation, both the power getting to the antenna, and any reflected power will be attenuated. Thus a measurement of SWR at the radio end will appear to be lower than the real SWR at the antenna end.

Dipole for the 40 Meter Amateur Band

If we were to make a dipole of the form of Figure 2-1 for the center of the US 40 meter band, we would use the formula 468/f, with the f equal to 7.15 MHz to result in a starting length of 65.45 feet, or 65 feet, 5.4 inches. As noted previously, this will vary with height, but let's say we get it all correct and have a height that provides close to a 50 Ω load at that frequency. If we then measure the standing wave ratio (SWR) across the band, 7.0 – 7.3 MHz, we would observe a set of SWR data very much like that plotted in **Figure 2-2.**[1,2]

Note that, as desired, we observe an almost perfectly matched condition (SWR of 1:1) at our design frequency of 7.15 MHz. Note also that as we change frequency across the band, our SWR rises to 2:1 at each band edge. Thus, even though our antenna is only closely matched at the band center, if the transmitter can operate at full power with a 2:1 SWR, this antenna will be usable across the band, if trimmed very carefully.

What About Height?

We have previously mentioned that changing height will also change the

---

[1] Notes appear on page 6.


SWR Plot: 40 meter 50 ohm dipole
File Edit View Options
Z0
● 50 ohms
○ Alt (400 ohms)
1
Source #
INF
10
5
SWR
3
2
1.5
1.1
1
7
Freq MHz
7.3

Freq 7.15 MHz
SWR 1.044
Z 52.17 - j 0.1674 ohms
Refl Coeff 0.0213 at -4.32 deg.
Source # 1
Z0 50 ohms

Figure 2-2 — Plot of SWR of a 40 meter dipole with height and length adjusted for 50 Ω at 7.15 MHz.


SWR Plot: 40 meter 50 ohm 33 ft dipole
File Edit View Options
Z0
● 50 ohms
○ Alt (400 ohms)
1
Source #
INF
10
5
SWR
3
2
1.5
1.1
1
7
Freq MHz
7.3

Freq 7.15 MHz
SWR 1.63
Z 81.62 + j 1.35 ohms
Refl Coeff 0.2405 at 1.86 deg.
Source # 1
Z0 50 ohms

Figure 2-3 — Plot of SWR of a 40 meter dipole with height set to λ/4, about 33 feet.


SWR Plot: 40 meter 50 ohm 66 ft dipole
File Edit View Options
Z0
● 50 ohms
○ Alt (400 ohms)
1
Source #
INF
10
5
SWR
3
2
1.5
1.1
1
7
Freq MHz
7.3

Freq 7.25 MHz
SWR 1.41
Z 70.32 - j 3.442 ohms
Refl Coeff 0.1712 at -7.97 deg.
Source # 1
Z0 50 ohms

Figure 2-4 — Plot of SWR of 40 meter dipole of Figure 2-3 raised to a height of λ/2, about 66 feet. Note the change in frequency of minimum SWR. It could be tuned back to mid-band by lengthening.


SWR Plot: 40 meter 50 ohm 132 ft dipole
File Edit View Options
Z0
● 50 ohms
○ Alt (400 ohms)
1
Source #
INF
10
5
SWR
3
2
1.5
1.1
1
7
Freq MHz
7.3

Freq 7.25 MHz
SWR 1.48
Z 74.16 + j 1.579 ohms
Refl Coeff 0.195 at 3.01 deg.
Source # 1
Z0 50 ohms

Figure 2-5 — Plot of same antenna raised to 1 λ, about 132 feet.


SWR Plot: 40 meter 50 ohm 132 ft dipole

Z0: ● 50 ohms ○ Alt (400 ohms)

Source # 1

Freq 7.15 MHz
SWR 1.5
Z 74.78 - j 1.658 ohms
Refl Coeff 0.199 at -3.07 deg.
Source # 1
Z0 50 ohms

Figure 2-6 — Plot of SWR of a 1 λ high 40 meter dipole trimmed for mid band.

antenna impedance. In fact it will also change the resonant frequency of the antenna. To obtain the plot in Figure 2-2, we lowered the antenna to a height of 12 feet. While such an antenna will operate, the combination of its direct signal and the signal reflected from the ground will result in most of the radiation going skyward. This makes it suitable for short and medium range communication. In many cases antennas are raised higher to increase low angle radiation to support communication over longer distances.

Impedance and Resonant Frequency at Greater Height

Figs 2-3 through **2-5** are a series of SWR plots of the same antenna as it is raised, first to 33 feet (λ/4), then 66 feet (λ/2) and finally 132 feet (1 λ). Observe the two phenomena happening as the antenna is raised — first, the impedance is changing and second the resonant frequency (frequency at which the impedance is resistive) is changing. Note that the impedance shown is that close to the resonant frequency.

To improve the SWR, we can adjust the length by making it long enough so that the resonant frequency is moved back to mid band. The result is shown in **Figure 2-6**. Note that the antenna now has an SWR range across the band of 2:1 or less so it might still work well across the band without a tuner. Note that to achieve this result, it must be very carefully trimmed.

A Dipole for the 80 Meter Amateur Band

A dipole for 80 meters (don't worry, this is the last example) has a very different result. The US 80 meter (sometimes called 75 and 80 meters) band is wider than 40 meters, covering 3.5 to 4 MHz. The result, again with the height lowered and length adjusted to match 50 Ω at mid band is shown in **Figure 2-7**. This is a very different result from our 40 meter dipole's impedance over the band. The SWR at the band edges is now above 7:1, and the bandwidth over which the SWR is 2:1 or less, the SWR bandwidth, is about 150 kHz — about half what it was on 40 meters.


SWR Plot: 80/75 meter 50 ohm low dipole

Z0: ● 50 ohms ○ Alt (400 ohms)

Source # 1

Freq 3.75 MHz
SWR 1.078
Z 52.07 + j 3.253 ohms
Refl Coeff 0.03773 at 55.76 deg.
Source # 1
Z0 50 ohms

Figure 2-7 — Plot of SWR of a 80/75 meter dipole with height and length adjusted for 50 Ω at 3.75 MHz.

Fractional Bandwidth

The reduced bandwidth on 80 meters illustrates a few interesting principles. First, for a band this wide at this frequency, it would take at least three dipoles with slightly different lengths to cover the whole band if we didn't have a device to transform the impedance to a value we wanted — an *antenna tuner*. Second, we note that the key factor is not the bandwidth itself, but rather the fraction (or percentage) of the center frequency that we wish to be able to cover.

In the case of 40 meters, we were able to cover a bandwidth (7300 – 7000) of 300 kHz with an SWR of 2:1. This is the fraction 300/7150 = 0.042, or 4.2%. Note that on 80 meters we had about 150/3750 = 4%. We can use this as a predictor of whether a single thin dipole can cover each amateur band with the results shown in Table 2-1.

Table 2-1

Percentage Bandwidth of Each HF and VHF US Amateur Band.

Band (Meters)	*Upper Frequency (kHz)*	*Lower Frequency (kHz)*	*Bandwidth (kHz)*	*Bandwidth (%)*
160	2000	1800	200	10.5
80	4000	3500	500	13.3
60	5407	5330	77	1.4
40	7300	7000	300	4.2
30	10,100	10,150	50	0.5
20	14,000	14,350	350	2.5
17	18,068	18,168	100	0.6
15	21,000	21,450	450	2.1
12	24,890	24,990	100	0.4
10	28,000	29,700	1700	5.9
6	50,000	54,000	4000	7.7
2	144,000	148,000	4000	2.7
1.25	222,000	225,000	3000	1.3
70 cm	420,000	450,000	30,000	6.9

Clearly, the problem is most pronounced on 80 meters, perhaps why we chose that example. In addition, 160, 10 and 6 meters are wider than our threshold, as is the 70 cm band. Fortunately, the higher three of these bands have operations divided by mode, so that it is not unreasonable to have, for example, a horizontal 6 meter antenna centered at the low end for CW and SSB operation and a separate vertical antenna for FM designed for the high end. Many operators, however, like to work all portions of 160 and 80 meters, so that can be an issue.

Notes

[1] This plot was obtained using an antenna modeling program named *EZNEC*. We will call upon this program repeatedly throughout the book. Several versions of *EZNEC* antenna modeling software, including a free trial version, are available from developer Roy Lewallen, W7EL, at **www.eznec.com**.

[2] For an introduction to *EZNEC* modeling, see Appendix A of J. Hallas, W1ZR, *Basic Antennas — Understanding Practical Antennas and Design*. Available from your ARRL dealer or the ARRL Bookstore, ARRL order no. 9994. Telephone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.org/arrl-store**; **pubsales@arrl.org**. See chapters 2-6.

Review Questions

2-1 Under what conditions might a ½ wave dipole not be compatible with a radio system?

2-2 Why can a transmission line tend to mask a high SWR?

2-3 If a dipole should be able to cover a complete amateur band, but doesn't because the minimum SWR is higher than the middle of the band, what can you do to improve the situation?

2-4 If you have no antenna tuner, how many separate dipoles would be required to cover the entire 10 meter amateur band with an SWR of less than 2:1?

Chapter 3

So Just What Is an Antenna Tuner?



On the left, inside view of a manually tuned 1500 W L-network HF tuner (Ten-Tec 238); on the right, a computer controlled 100 W automatic tuner (Elecraft KAT3) designed to fit inside the compact Elecraft K-3 HF and 6 meter transceiver.

Contents

What's In an Antenna Tuner 3-2

Antenna Tuner Controls 3-3

Sidebar — A Quick Discussion of Standing Wave Ratio 3-4

Where are the Knobs on an Automatic Antenna Tuner? 3-8

What's the Best Tuner for You? 3-9

Review Questions 3-10

As noted in Chapter 1, *the antenna tuner is a variable impedance transforming device that can transform the impedance of an antenna system to appear to the transmitter as a 50 Ω load, while causing almost all of the transmitter power to be radiated from the antenna, just as if everything were matched.* This sounds like just what we need to solve the problem of using an antenna system that has an SWR that the transmitter doesn't like to deal with.

While an antenna tuner may well be just what we need — they come in many flavors, shapes and sizes — not to mention specification ratings. Much of this book will deal with how to choose the best type of antenna tuner, as well as to determine the best place in the system to locate it.

What's In an Antenna Tuner?

In order to perform its transformation function, an antenna tuner must deal with any load that is within its specified limits (everything has its limits — no antenna tuner can match absolutely everything!). As noted in the sidebar, an SWR greater than 1:1 happens if the load of the antenna system is different from the specified output load impedance of the transmitter, 50 Ω for most current designs. Table B in the sidebar shows some representative values of resistance and capacitive or inductive series reactance that result in various values of SWR.

Note that we could categorize the load impedance into four general categories that could all have different solutions:

1. The load is a resistive impedance of 50 Ω. In this case the SWR is 1:1 and we don't need an antenna tuner at all. We could bundle with this all loads that work well with the transmitter without change — perhaps those with an SWR of less than 2:1. There may be a bit of extra loss here or there, but generally everything will work well.

2. The load is a resistive impedance other than 50 Ω , and not close enough to allow proper operation. This could be loads with a 2:1 SWR such as 25 Ω or 100 Ω, a 3:1 SWR such as 16.7 Ω or 150 Ω, or a 10:1 SWR such as 5 Ω or 500 Ω. All of these loads share the fact that they could be matched through the use of an ideal transformer, just as you would match an 8 Ω speaker to a 600 Ω audio line with an audio transformer.

For use in radio rather than audio frequencies, such transformers must be constructed differently to avoid also introducing reactive components, but the approach is feasible and sometimes encountered. One classic example is the matching arrangement employed in a wideband antenna often used at HF called a rhombic. It offers an almost resistive load of around 600 Ω over a 4:1 frequency range and is often fed through a wideband 12:1 impedance ratio transformer by a 50 Ω system. **Figure 3-1** shows the idea. While most folks would call it a transformer rather than an antenna tuner, there's no question that it is performing one possible class of the function we're talking about.

3. The load is composed of a combination of a 50 Ω resistive component and a series reactance. A load with a parallel reactance can be transformed into one with a series reactance, but we'll focus on the series version since it may be easier to visualize.

This makes for an easy to imagine antenna tuner. If the series reactance of the load is inductive ($+X_L$), all the antenna tuner need contain is a component with a capacitive reactance of the same magnitude, ($-X_C$). The series combination of the two is just 0 Ω reactive, so the resultant is the


ARRL0630
50 Ω Load to Transmitter
600 Ω Transmission Line
To Wide Band 600 Ω Load such as a Rhombic Antenna
Transformer with 12:1 Impedance Transformation Ratio

Figure 3-1 — A wide-band impedance transformer can serve the function of an antenna tuner for a resistive load.


ARRL0631
"Antenna Tuner"
Non-matched Antenna System
50 Ω Load to Transmitter
35 Ω Inductive Reactance
35 Ω Capacitive Reactance
50 Ω
50 Ω Resistive Load in Series with 35 Ω Capacitive Reactance

Figure 3-2 — Antenna tuner for special case of reactance in series with resistive part equal to Z_0.

resistive component —50 Ω as shown in **Figure 3-2**.

Note that, unlike the wideband transformer, this will likely work only on a single frequency. If the antenna has an inductive reactance, it will tend to increase with frequency ($X_L = 2 \times \pi \times f \times L$), at least over a limited frequency range. In order to keep the total impedance resistive, we will need a variable capacitor, so we can adjust the capacitive reactance to match the changing inductive reactance of the load. Note that our "antenna tuner" now has a knob on the front, and is starting to look more like an antenna tuner.

4. The load is a combination of resistive and reactive components that have an SWR greater than we can deal with and that falls in none of the other three categories. This is the general case — the one all general purpose antenna tuners must deal with, at least over some range of SWR.



(A) Unbalanced Tuned Variable Transformer

(B) L-network for Z < Z_0

(C) L-network for Z > Z_0

(D) π-network

(E) T-network (High-pass)

(F) T-network (Low-pass)

Figure 3-3 — Antenna tuner configurations that can be used to match the more general mismatched load.

There are a number of circuit configurations that can be employed that will do a combination of cancelling the reactance and transforming the resistive impedance. We have cataloged them in **Figure 3-3** so you will recognize the configurations as we discuss them. In many cases, if constructed of the same quality components, they will provide equivalent performance. As with all general purpose devices, there are certain advantages and disadvantages of each, and some may be more appropriate for some applications than for others.

Another categorization that can be made is whether the tuner is designed to feed an unbalanced load, typically fed with coaxial cable or a single wire against ground, or is intended to feed a balanced load such as a dipole fed with balanced open wire transmission line. Each of these configurations can be adapted to either task, however, we will defer that discussion until later.

Antenna Tuner Controls

Not surprisingly, many of the different manual antenna tuner configurations have different control arrangements.

L-Network Tuner Controls

The L-network has two primary adjustments, an inductor and a capacitor. In the Ten-Tec 238 tuner shown in **Figure 3-4**, and in most L-network tuners, each control is adjustable throughout its entire range on any band, providing maximum flexibility. In addition, there is a switch to move



Figure 3-4 — Front panel view of an L-network tuner, an early version of the Ten-Tec 238.

A Quick Discussion of Standing Wave Ratio

We discussed standing wave ratio in Chapter 2 and noted that a matched antenna system has a standing wave ratio (SWR) of 1:1. That is the case in which there are no standing waves and all energy from the transmitter is delivered to the load with no reflections on the transmission line. This is a very straightforward situation that is easy to understand. Getting into the details of this topic can get lengthy and there are entire books devoted to the topic.[A] Fortunately, we won't need to get that deeply involved to understand antenna tuners and their applications. Still, we need to have some idea about SWR, what it means and what its consequences are to understand, when and if it is a problem and how to solve it.

The Matched Transmission Line

If we were to connect a battery to a long real transmission line with no load and monitor the current that would flow with a high speed oscilloscope we would notice an interesting effect. The combination of the line series inductance and shunt capacitance, and to a lesser effect the wire resistance, would result in an initial current that would flow, even though there is an open circuit at the far end.

The current will continue to flow until the signal propagates to the end of the line and returns. When it reaches the end of the line (traveling somewhat slower than the speed of light) a *reflected* wave of the opposite polarity will propagate back because there can be no current flow at the open circuit. When the reflected wave returns to the source end of the line the combination of the forward and reflected wave will result in zero current — just what we would expect for an open transmission line.

The ratio of the applied voltage to initial current is an impedance and we call this the characteristic impedance or Z_0 of the transmission line. This is the current that would flow into an infinite length of line no matter what is at the far end. Note that we didn't say anything about signal frequency here, this is strictly a matter of the way the line is constructed, especially the capacitance and inductance that is distributed along its length. For the usual low loss line, ignoring resistance, we can determine Z_0 as follows:

$$Z_0 = \sqrt{L/C}$$

where L and C are the inductance and capacitance per unit length, typically per foot or per meter. These values can often be found in many manufacturers' specification sheets.

The Matched Transmission Line

If, instead of having an infinite line, we put a resistor with a resistance equal to the line Z_0 on the far end of the line it will absorb the power as it arrives and there will be no reflection. The voltage and current relationship at the signal end of the line will appear as if it were the same resistor, just located at the source.

This is exactly what we wanted! If the source is a radio designed to drive a 50 Ω load, Z_0 is 50 Ω and our load is an antenna with an impedance of 50 Ω, we get just what we want — to our transmitter it appears as if the antenna is connected directly to the antenna. There is no reflected power, the SWR is 1:1 and all is well with the world.

The Mismatched Transmission Line

There are an infinite number of cases in which a transmission line is terminated, not with its Z_0, nor with an open or short, but with some other impedance. This results in a reflection of a signal that is smaller than the signal that was sent down the line. It is important to note that this signal does not represent lost power, because it is re-reflected from the transmitter back up to the line. It is true that the power delivered to the antenna will equal the forward power less the reflected power, however, because the power is re-reflected at the transmitter so the numbers go up together. This is illustrated in **Table A** for the case of perfect (lossless) transmission line, assuming the transmitter can put power into the SWR shown.

So What's the Big Deal

The key is the two reasonable assumptions noted above. Let's discuss each:

- Transmission lines are not lossless, and their losses increase with increasing SWR as we will discuss. Whether or not that's a problem depends on the line

Table A

Example of Net Transmitted Power with 100 W Transmitter versus SWR with Lossless Transmission Line

SWR	*Reflection %*	*Forward Power*	*Reflected Power*	*Antenna Power*
1:1	0	100	0	100
2:1	10	111	11	100
3:1	25	133	33	100

the variable capacitor between the two ends of the inductor to allow tuning of both high and low impedance loads.

This particular tuner uses a rotary inductor (see **Figure 3-5**) for adjustment of inductance. The coil turns with rotation of the shaft on the left end. As it turns, its point of connection to the small wheel on the top in the picture is moved up and down the coil. It requires about 30 turns of the knob to adjust from the minimum to the maximum amount of inductance. Some tuners use a switched inductance instead. The switch allows a quicker change of settings, but does not provide for values of inductance between the switched taps. This is not generally a problem, although there are some loads that can't be tuned to a 1:1 SWR at some frequencies — still close enough works. Note that there is no bandswitch, on this model, since any available adjustment type, frequency and SWR as we will discuss later.

- Often a more serious problem is that somewhere in the range of SWR in Table A, typically by an SWR of 2:1, transmitters will reduce power to avoid damage due to the higher current or voltage that results from the higher than specified SWR.

Note that the second problem is not a fundamental issue of SWR itself, but rather a design choice made by transmitter designers. Still, for transmitters that we may choose to use, it is a real problem that we have to deal with.

What Kind of Load Results in High SWR

Any load that is different from Z_0 of the transmission line will result in a SWR greater than 1:1. For the case of the frequently encountered 50 Ω coaxial cable, that means any load that is not 50 Ω resistive. This can mean a load that is resistive with a value of other than 50 Ω or a load that is resistive, but also has capacitive (–X) or inductive (+X) reactance, or any of an infinite number of combinations of the two. Some examples of loads with different SWRs are shown in **Table B**.

Note that it is very easy to determine the SWR for the resistive case — it's just Z_0/R or R/Z_0 depending on whether the load is greater or less than the Z_0.

Thus it is important to know not just the resistive part, but also the equivalent series inductive or capacitive reactance to determine the SWR.

Table B

Impedance of Loads that Result in Different SWRs.

For Ideal 50 Ω Coaxial Cable

R (Ω)	*X (Ω)*	*SWR*
50	0	1:1
25	0	2:1
100	0	2:1
50	±35	2:1
30	±18	2:1
16.7	0	3:1
150	0	3:1
50	±58	3:1
30	±40	3:1
5	0	10:1
500	0	10:1
50	±142	10:1
250	±250	10:1

Determining SWR from Impedance Data

While the case for resistive loads is simple, the case for loads with reactance or complex loads is well — more complex. Still, there are at least three ways that I know of to determine the SWR of a complex load, not counting measuring with an SWR meter, as follows:

- Use the software TLW (Transmission Line for Windows) that comes packaged with recent editions of The ARRL Antenna Book.[B] If you plug in the R and X values and the appropriate transmission line Z_0, it provides the SWR at each end of the line. You can select which end of the line has the measured Z (input or load). This is very handy since it will also calculate the line loss.
- This may be the most simple calculation to make graphically with a Smith Chart.[C] Recall that if the Z is just resistive (X=0), the SWR is either Z_0/Z or Z/Z_0, depending on whether the Z is lower or higher than the Z_0. Recall also that a circle on a Smith Chart represents constant SWR. Thus if you enter the Z on the Smith Chart and draw a circle centered on the chart center, it will show the transformed Z for any length of line. Either point at which the circle crosses the resistive axis can be used to calculate the SWR as described above.
- If you have neither computer nor Smith Chart, you can compute the SWR directly. This can be found, for example, in a book I had as a text many years ago, a classic by the late John Kraus, W8JK, *Antennas*. In the first edition it is in the appendix on page 507. The calculation is done in two steps:

1. Find the voltage reflection coefficient σ:
$\sigma = (Z - Z_0)/(Z + Z_0)$
Note that the Z is a complex number, so the calculation is a bit tedious.
2. Find the SWR = $(1 + |\sigma|) / (1 - |\sigma|)$
where $|\sigma|$ indicates the magnitude of the complex reflection coefficient, σ, found in step 1.

Notes

[A] W. Maxwell, W2DU, *Reflections*, check his Web site for information on availability of the latest edition at **w2du.com**.

[B] R. D. Straw, Editor, *The ARRL Antenna Book,* 21st Edition. Available from your ARRL dealer or the ARRL Bookstore, ARRL order no. 9876. Telephone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.org/shop**; **pubsales@arrl.org**.

[C] Paper copies of 50 Ω Smith Charts are available from your ARRL dealer or the ARRL Bookstore, ARRL order no. 1341. Telephone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.org/shop**; **pubsales@arrl.org**.

is usable on any band — you just crank until you are within range. It may even be helpful for upper body development.

The capacitor can be a single, or multiple section type or a combination of a variable and fixed capacitors. In my tuner, the switch that moves the capacitor from one end of the inductor to the other has additional positions that switch in fixed capacitors in parallel to extend the tuning range. The fixed and variable combination allows somewhat finer tuning, but in multiple steps. A larger variable with a multi-turn vernier dial may be equivalent, and may be quicker to adjust.

An advantage of the L-network tuner is that there is only a single combination of L and C that will match a given load. As noted below, some tuners can offer more than one, but only one is optimum.



Figure 3-5 — Close up of a rotary inductor.

Pi- and T-Network Tuner Controls

Pi- and T-network tuners have three tuning controls — usually one inductor and two capacitors. Pi-network tuners that started out in the age of vacuum tube transmitters with pi-network output circuits often are built with similar components and are thus bandswitched as in the Drake MN-2000 tuner shown in **Figure 3-6**. In this tuner, the bandswitch sets the inductance to a preset coil tap for the middle of the expected range and the capacitors on both ends are used to provide the closest match. This configuration can be useful, but generally has less tuning range than those with adjustable or switched inductors in small increments.

Note that a pi-network tuner set to minimum capacitance on either of the capacitors essentially becomes an L-network tuner, with the high or low impedance determination dependent on which capacitor is set to around zero.

With either the pi- or T-network tuners, sometimes multiple very different settings can be found that will tune a particular load. In general, a setting with the minimum inductance is more efficient since the wire resistance of the inductor can dissipate power.

Tuned Transformer Tuner Controls

The tuned transformer is essentially the same as an output circuit from an earlier, before the pi-network, kind of transmitter. It typically has a balanced tuned circuit designed to resonate on a particular band (there weren't as many back then) using a fixed inductor and variable capacitor. The typically balanced transmission line was tapped symmetrically on the coil — close to the center for low impedance loads, close to the ends for high impedance loads. Small clips were generally used to provide load connection points. Very low impedance loads were connected in series with the center of the inductor.

Any reactance in the load would detune the tuned circuit that would then be readjusted by retuning the variable capacitor. The usual transmitter side connection was a link of a few turns that could be mechanically moved in and out of the center of the coil to provide adjustable coupling.

It was actually simpler to adjust than describe. Once the tap points were located for a particular band using the usual single antenna, the clips were fixed in place, and this became just one more coil to be changed while changing frequencies. Both transmitters and receivers of the pre WW2 era often had plug-in coils that required changing each time a band change was desired.

The 1950s era E. F. Johnson *Matchbox* antenna tuner (see **Figure 3-7**) was a radical design change to the tuner transformer type of tuner. This was the era in which transmitters and receivers were generally bandswitched and the Matchbox was an effort to make antenna tuning just as easy. What made the matchbox unique was a patented differential capacitor design that allowed a variable capacitance to be made of two capacitors — one that increased and one that decreased as it was rotated.

A pair of these were placed across the tuner resonant circuit allowing the transmission lines in the middle of each to be tapped across the resonant circuit using capacitive "taps" instead of the previous inductive taps. This allowed a continuously adjustable impedance setting to be made from the front panel. The bandswitching allowed bands to be changed without changing coils. This was very popular at the time, and they are still popular today. They do have some limitations, principally that they only work on the amateur bands of that day, not 30, 17 and 12 meters — although they may



Figure 3-6 — 1970's vintage bandswitched ~~pi-network~~ PI-C tuner.

THE DRAKE MN-2000 IS NOT A PI-TYPE CIRCUIT BUT A PI-C CIRCUIT WITH THE INPUT CAPACITOR AND THE COIL BEING FIXED (BAND-SWITCHED) AND THE TWO OUTPUT CAPACITOR BEING VARIABLE. THIS IS VERY CLEVER DESIGN, THE Q IS



Figure 3-7 — 1950's vintage E. F. Johnson *Matchbox* antenna tuner.

drive some loads on the higher bands by setting to an adjacent band.

Antenna Tuner Metering

Many antenna tuners include metering, either directional power meters or an SWR bridge. These can be used to monitor progress while adjusting the antenna tuner — either for minimum reflected power, or for minimum SWR. Arguably, this is somewhat redundant if the connected radio transmitter also has SWR or reflected power measurement capability, although some meters in tuners may be more sensitive or easy to read.

While there is certainly no harm in having redundant metering, if your radio meter is easily visible from the antenna tuner location, and has sufficient sensitivity to allow proper tuning, there isn't much benefit in my opinion. The early transceivers, and especially pre-transceiver transmitters, did not generally include that function, perhaps explaining why most tuner manufacturers still provide them. For most users with metering in the transmitter, transmission line current meters on the output side of the tuner would actually be more useful. To my knowledge, alas, no tuner manufacturers now include these.[1,2]

Tuner Limitations

All tuners are composed of combinations of inductors and capacitors in various combinations. Since the impedance at a high SWR can vary widely, the tuner needs to have a wide range of values in order to be able to accommodate all possibilities at every frequency within its range. It is generally the case that the lower the frequency, the more inductance and capacitance will be required. Thus the maximum available inductance and capacitance, generally determines the low frequency limit of operation.

In the case of high power tuners with large components, it is not unusual for tuners that cover down to 160 meters (1.8 MHz) to be in larger enclosures simply because the size of the components is larger. In a similar way, it is the minimum capacitance and inductance that sets the high frequency limit. In this case, one must often look beyond the specified values of the components themselves and look to the stray capacitance of wires and component frames to the cabinet, as well as the inductance of connecting wires between components. Some tuners have trouble matching loads on 10 meters (28 to 29.7 MHz in the US) that would be easy to match at lower frequencies for this reason.

Increasing power with high SWR can result in very high currents and voltages within the tuner, requiring large components for high power tuners. The large components, in addition to making the box much bigger, also make the control of stray inductance and capacitance more of a challenge for the designer.

---

[1] Notes appear on page 9.

CONSTANT (18) OVER THE TUNING RANGE AND THERE IS ONLY ONE MATCH FOR A GIVEN IMPEDANCE IN CONTRARY TO THE T-TUNER.

Where are the Knobs on an Automatic Antenna Tuner?

Automatic antenna tuners don't generally have tuning knobs. Instead, they have a microcontroller that monitors SWR or reflected power and uses an algorithm to step through allowable values of L and C until a match is found. Any of the tuner topologies in Figure 3-3 could be used in an automatic tuner with an appropriate control mechanism.

Some automatic tuners use rotating variable capacitors and rotary inductors, just as in many manual tuners. In fact some are adaptations of manual tuners with servo motors and controllers added on as an additional physical and logical layer.

I do think it is safe to say, however, that the majority of auto tuners use a set of discrete components instead of variable ones. A range of inductance is provided by using relays to switch different sizes in series to reach the desired value. Similarly, a range of capacitance can be provided by having multiple capacitors switched in parallel. By having values available in a series such as 1, 2, 4, 8, 16, 32, 64, 128, 256 for example, any value from 1 to 511 (either pF or µH) can be obtained in steps of 1 unit. Thus any needed resolution and range can be easily provided.

While such switching, if done manually with toggle switches, might make us go over the top, it's duck soup for a microprocessor. The hard part may be defining a computer algorithm that can quickly find the right values without trying all combinations. Fortunately, that just needs to be done once and is provided "free" with the tuner. Most auto tuners can find a suitable match within a defined threshold, often 1.5:1, within a few seconds with no additional information about the antenna being tuned.

Many auto tuners have the capability to memorize the appropriate settings for a particular load once it's found. There are two approaches to this, both can be quite successful:

Memory stored by frequency. Perhaps most commonly found in tuners is the storage of tuning data based on frequency. Of course, this requires that the tuner measure the frequency before it can tune.[3] Most tuners have a number of frequency "bins" of a certain bandwidth, for example perhaps 25 kHz. If the frequency is within that bin, the last successful setting from a frequency within that bin will be used. If it doesn't meet the threshold, the tuner will start tuning over.

Obviously, the smaller the bin, the more successful the tune is likely to be, assuming the same antenna is used. On the other hand, this depends on previous operation within the bin, so it takes longer to accumulate data for all bins. Most tuners seem to have it about right, in terms of trade off.

Memory stored by past success. A different approach is to just keep track of the last number of successful tuner settings, independent of frequency. Let's say the tuner remembers the last 100 successful tuner settings. It just very quickly tries all those before it initiates its regular tuning algorithm. It is quite likely that recent conditions will be repeated. This approach is particularly advantageous for a single port tuner that is switched between multiple antennas making multiple successful tuner settings appropriate within a single frequency bin. Of course an advantage for the manufacturer is that the tuner doesn't need to measure or otherwise determine transmitting frequency.

What's the Best Tuner for You?

The best tuner for a particular application will depend largely depend on your antenna system and operational needs. Automatic antenna tuners inside transceivers are convenient and don't require extra space or wiring. Check the specs carefully, many do not cover a wide impedance range (many are spec'd at 3:1, although some may do better than spec). Interestingly, the internal tuners from Elecraft, FlexRadio and Ten-Tec do provide wide range (to 10:1 SWR) tuning, perhaps others will follow in this direction. The other disadvantage of internal tuners is that you will need a tuner with a higher power rating if you use, or consider using a linear amplifier. A high power tuner will work fine at low power, if the linear is in your plans.

Manual Tuners often offer antenna switching and control functions, not present in many auto tuners. Manual tuners also often provide continuous tuning to allow setting the controls for an exact 1:1 SWR, although that doesn't really provide a significant benefit.

Automatic tuners have a number of advantages and not many disadvantages. Some can be operated remotely at or near the antenna to reduce system losses. Either of the memory tuner types can reduce the tuning time for previously encountered antennas from a few seconds to a few tenths of seconds. Arguably either is significantly quicker to get into operation than a manual tuner, even with recorded dial settings.

The rest of the book will explore these issues in more detail.

Notes

[1] E. Nichols, KL7AJ, "Keeping Current with Antenna Performance," *QST*, Feb 2009, pp 34-36.

[2] P. Danzer, N1II, "A Simple Transformer to Measure Your Antenna Current," *QST*, Sep 2009, p 35.

[3] Internal, or brand specific tuners have the advantage that the frequency information can be made instantly available from the radio circuitry.

Review Questions

3-1 What are two reasons to provide a matched, or nearly matched, load to a transmitter?

3-2 What is the SWR of a 50 Ω cable with a 500 Ω resistive load? How about a 500 Ω transmission line with a 50 Ω resistive load?

3-3 If a 100 W output transmitter is connected to a lossless antenna system with a 3:1 SWR and it can deliver its full power, how much power reaches the antenna? How much power is reflected from the load?

Chapter 4

Tuning an Antenna Tuner


TEN-TEC
TRANSMITTER MATCH
INDUCTANCE
LOAD MATCH
ANTENNA COUPLER
MODEL 231
TEN-TEC
MODEL 238
SWR SET
BYPASS
LOW Z
HIGH Z
ANTENNA
MN-2000 MATCHING NETWORK

Tuning controls of three manual tuners. On top, a 100 W Pi-network, in the middle a 1500 W L network tuner and on the bottom a bandswitched 1000 W Pi-network tuner.

Contents

Tuning an Automatic Tuner 4-2
Tuning a Manual Tuner 4-3
A Simple Transformer to Measure Antenna Current..............4-6
Review Questions...4-7

By now we, hopefully, know what an antenna tuner is, and why it may be a good idea. The next question should be "how do we work it?" The answer to this depends a bit on the type of tuner and your configuration. In all cases, the most important rule is: *Don't interfere with other users of the band!* This is an issue because all types of tuners require the transmission of RF for at least the final adjustment.

This is because tuning is considered complete only if the SWR is close to 1:1, and it takes a signal to be able to measure SWR. Even if the signal is of a reduced amplitude, people have been known to make worldwide contacts with transmitters running less than 1 W, so don't assume a low powered TUNE signal won't go anywhere.

If you are worried about loosing track of the current frequency that has a particularly desirable station; just put it in memory, tune off the frequency, adjust the tuner and, when tuning is complete, recall the desired frequency from the memory. You should be good to go, and you won't ruin it for someone else.

Tuning an Automatic Tuner

As its name implies, tuning an automatic tuner should be, well *automatic*. If it's a tuner that is part of the radio, or designed to operate with the radio, there is likely a TUNE button that reduces power, sends a carrier on the desired frequency and then forces the tuner to tune. Many after-market automatic tuners first measure the frequency and try the settings that worked the last time you used that frequency, or one close to it.

If the tuner is one that is not designed to work with the radio, you generally will need to initiate the process in some way. In many cases, if a transmitted RF signal is sent to the tuner it will measure the SWR and automatically initiate the tuning process if it needs to. There are two concerns here — first, many tuners want adjustments to be made at reduced power to avoid burning relay contacts — second, reduced power should also be used during tuning to avoid potential transmitter damage from trying to feed a mismatched load, as well as to reduce interference to others.

You will need to find a way to easily reduce power for tuning. Some radios do exactly that with a TUNE button. On my transceiver, I have such a button and a menu selection allows me to set the tune power to any level I want. Pushing the TUNE button sends a reduced carrier out of the transmitter until I push it again. This button is also useful to start tuning a linear amplifier. If you don't have a TUNE button, you may need to manually reduce power and then hit a key to send a signal. Note that I said *key*, as in radiotelegraph mode. Hitting the push-to-talk button on a SSB voice transmitter will switch to transmit, but not put out a signal until you start talking — so that doesn't work well for this application. If your transmitter supports AM voice, it will usually put out a carrier of about 25% of full PEP when keyed, so that is a possibility as well, although that is usually somewhat more power than desired.[1]

[1] Transmitters such as the early R. L. Drake vacuum tube series use controlled carrier in AM mode and may not put out a carrier without speech.

Tuning a Manual Tuner

To tune a manual tuner, you can actually start with the transmitter turned off. First look at the instruction manual and see if it provides suggested settings for each band. While your actual settings will be somewhat different, since you will have a different impedance on each band, they should make a good starting point. Hopefully the controls on your tuner have calibration marks on each control, if not, imagine an analog clock face on each control.

Next, practice tuning your tuner into a dummy load. Even though the tuner usually isn't needed to match the 50 Ω dummy load to the transmitter, if the tuner is in line, the tuner will require just as careful adjustments to tune into that load. Try the tuner on each band and record the settings.

Adjusting a Manual Tuner

Most manual antenna tuners have three controls. If it's a Pi- or T-network, they will all be adjustable inductors or capacitors, usually one of the former and two of the latter. An L-network will just have one of each but will usually have a switch to move the variable capacitor between the input and output side of the inductor as shown in Figure 3-3 in Chapter 3. Because the three controls interact to some degree, finding the right settings can be arduous, can stress the transmitter and can also cause interference to others as you try to find the right settings, hence the recorded table. I provide the following suggestions.

- Many antenna tuner instruction manuals have tables of typical values for each band. Use these as a starting point.
- Practice tuning your antenna tuner into a dummy load, as discussed above.
- First tune as close as you can using the receiver as an indicator. If there are signals on the band, adjust for maximum S-meter indication. If there are no signals adjust for loudest band noise or meter indication.
- If you have an antenna analyzer, use it instead of the radio to find settings that offer a matched load to the radio port as shown in **Figure 4-1**.
- If you can't quite get to a 1:1 SWR, shift one of the controls off its minimum position and adjust the other one (or two) for minimum. If the result is better, move the first control a bit more in the same direction. Repeat until it starts to get worse. If it's still not satisfactory, repeat the procedure with a different control.



Figure 4-1 — Using an antenna analyzer to adjust your antenna tuner reduces both stress to your radio and interference to other users of the band. The coax switch shown can be used to switch the output of the antenna tuner to either the radio or the antenna analyzer.

- If there are multiple settings yielding a match, as there will likely be with T- and Pi-network tuners, select the one with minimum inductance — it will be more efficient because inductors tend to have more loss than air variable capacitors. The following example illustrates the point.

A fairly typical "random" length of wire likely to be matched with an antenna tuner would be 57.5 feet long fed against ground. This would have an impedance of 25.6 Ω resistive in series with 100 Ω capacitive reactance at 3.7 MHz — a 10:1 SWR, just within the design range of most wide range tuners. A low-pass L-network tuner will just have a single value of L and C that would mach this impedance. It would be, according to *TLW* software (discussed later in detail), 5.29 μH and 1000 pF. The loss in the L-network tuner would be 0.11 dB or 2.5%.

With a high-pass T-network tuner, there are an infinite number of combinations of tuner components that can result in a satisfactory match. Setting one value requires the other two components each be set to a particular value to obtain a match. As shown in **Table 4-1**, listed by selected value of output capacitor, not all combinations will have the same efficiency. It shows dramatically that by having a

Table 4-1

Examination of High-Pass T-Network Tuner Efficiency as a Function of Tuning: Load 25.6 Ω Resistive in Series with 100 Ω Capacitive at 3.7 MHz.

Capacitor Output (pF)	*Intput (pF)*	*Inductor (μH)*	*Loss (dB)*	*Loss (%)*
5	9.2	130.6	8.5	85.9
10	12.5	82.1	5.4	71.3
30	25.7	34.4	2.4	41.7
50	37.5	22.5	1.6	29.9
100	63.2	12.8	0.9	18.4
200	102.6	7.8	0.5	11.5
500	171.2	4.7	0.3	6.8
1000	223.2	3.7	0.23	5.2
2000	264	3.2	0.19	4.4
5000	297	2.6	0.17	3.9

Table 4-2

W1ZR Antenna Tuner Settings Table

Antenna Tuner Settings — 100 Ft Dipole (4)

					AMP SET	
FREQ	*C*	*IMPED*	*L*	*SWR*	*Load*	*Tune*
1.8	8.0	L5	4 - 9.9	2.5	0.0	8.0
3.55	5.6	H1	20 - 6.9	12.0	4.0	5.8
3.8	1.0	H1	18 - 1.9	9.8	8.8	4.7
5.3	4.3	H1	12 - 9.5	5.8		
7.0	1.2	H2	6 - 5.0	4.6	7.8	2.7
7.2	8.5	H1	8 - 1.0	5.6		
10.1-.15	8.8	H1	4 - 6.3	4.4		
14.0	2.0	H1	4 - 5.6	4.0	7.0	1.5
14.2	1.3	H1	4 - 6.4	3.7	7.0	1.4
18.068-.168	4.1	H1	2 - 7.7	2.9	7.0	2.0
21.0	3.0	L1	2 - 6.5	3.7	6.2	1.5
21.2	2.6	L1	2 - 6.2	4.3		
21.3	2.5	L1	2 - 6.3	4.5	6.0	1.3
24.890-.990	1.5	H1	1 - 1.8	1.8		
28.0	1.0	L1	3 - 5.4	1.6	5.0	2.0
28.5	1.0	L1	2 - 9.6	2.5	4.5	2.0
29.0	1.0	L1	2 - 6.0	3.6		

Antenna Tuner Settings — Tri-Band (2)

					AMP SET	
FREQ	*C*	*IMPED*	*L*	*SWR*	*Load*	*Tune*
10.1-.15	4.0	L1	9 - 1.3	5		
18.068-.168	3.3	L1	4 - 8.2	5	7	2.0

Antenna Tuner Settings — Ground Plane (3)

					AMP SET	
FREQ	*C*	*IMPED*	*L*	*SWR*	*Load*	
3.6	10.0	L1	9 - 1.7	2.3	4	5.8

high inductance value, the loss will be higher than if an inductor with a lower value were used. All combinations will provide a 1:1 match to the transmitter which will happily pump power into the system. While some values would likely not be realizable at 3.7 MHz, the reactances all would be easily employed at 30 MHz. A 1500 W transmitter with the 86% loss of the first entry would dissipate 1290 W in the tuner as heat. The tuner would likely melt before your eyes!

Note that Table 1 indicates that the highest efficiency is with the lowest inductance value — often the case. It also can happen that the high Q of a low inductance solution can result in large circulating currents resulting in additional loss. The best way to be sure is to measure the relative current going from the tuner to the antenna. The solution with the highest current will be the most efficient.

The actual value of the current isn't usually significant since the antenna impedance is unknown. For any given antenna on a given frequency, what is important is that you have the solution that provides the most current towards the antenna with the transmitter operating into its design load and within ratings. Unfortunately, I am not aware of any tuners now available that provide for the measurement of antenna current. RF ammeters are available on the surplus market and one is available from MFJ. Alternately, a fairly simple antenna current transformer project article in *QST* described how to make your own. It is reproduced in the following sidebar.

Once you have a match, reduce the inductance, retune the capacitors, and see if you can still obtain a match with an even higher current. Once you have the settings for a particular antenna, you won't need to measure the current again unless something changes in the system.

- Record your data! All manual antenna tuners I've seen have calibrated scales on their front panel for each control. As soon as you have a match, write down the settings you found for future reference and use them for a starting point next time. I find that having a set of dial readings for at least the phone and CW portions of the band is useful. **Table 4-2** is the actual table that I use at my station. Note that there are separate table segments for three different antennas. The fourth position is connected to a dummy load for testing and amplifier adjustment purposes.

The Controls in My Table

Since there's a bit more here than you might need, let me explain the columns I have included in my chart. The tuner I use is an early Ten-Tec 238 with front panel layout shown in the chapter title (center) figure. This is a 1.5 kW rated L-network tuner that provides four antenna connection ports, one of which (# 4) can be set up for either a balanced or unbalanced load using an internal balun on the output side.

- FREQ is the approximate frequency that I made the adjustment for.
- C is the approximate setting of the variable capacitor dial. It has 10 divisions, but I "eyeballed" how far between the marks the setting was to get the tenths position.
- IMPED is a switch that can set the configuration for high (H) or low (L) impedance and has five fixed capacitor settings for each, hence the numbers 1 through 5, in addition to the letter.
- L is the setting for the variable inductor. The inductor setting has two numbers because it is a multiple turn rotary inductor. The first number is the value of the TURNS scale, while the second is the knob setting from the skirt on the knob.[2]

---

[2] Current models of this tuner have an improved drive for the rotary inductor that provides a single reading for the L value.

- SWR is the SWR measured with the tuner bypassed. This doesn't play a part in the tuning, but is useful as a check to make sure the antenna hasn't changed or fallen down since it was installed. The tuner will just as happily tune the antenna if it breaks and falls down, but the signal won't go as far.
- The two AMP SET adjustments are for my linear amplifier tuning controls. They share the spreadsheet because, as with the antenna tuner, if I change bands or modes, they need adjustment. These columns save having an additional piece of paper on the operating desk. If you don't have a linear amplifier you don't need these.

Your tuner may have different control labels, and you may not want to include all my data, however, it should give you a starting point for your own record keeping. I maintain my records on a PC spreadsheet, although any convenient medium can be used. A small set of data might fit on a 3 × 5 (or perhaps 5 × 7) inch file card. The spreadsheet has the advantage that it can be easily updated as antennas are changed or added. In my experience, amateur stations are never quite done!

A Simple Transformer to Measure Your Antenna Current

SWR doesn't give you the whole story — you need an RF current meter.

Paul Danzer, N1II

In a recent *QST* article, Eric Nichols, KL7AJ, presented a good idea — monitoring the RF current into your antenna system to insure optimum tuning.[1] Actually, it was the second time it was mentioned to me — George Peters, K1EHW, suggested the same thing to me several months before. At the end of Eric's article, he proposed using a current transformer to do the monitoring.



Figure 1 — View of the transformer and simple circuitry that make up the relative RF current meter.

Making a Current Transformer

This could be as simple as a turn of wire through a ferrite core and several turns of wire around the core to form a transformer.[2] The output of the transformer would be proportional to the current through the wire.

Making it Happen

This seemed simple enough, and the result of one hour's work is shown in Figure 1. The core used was a T37-6. T37 designates the size (0.37 inches OD), picked so the insulated center conductor of RG-58 (or RG-59) would fit comfortably through the core center. The –6 designation relates to the frequency application of the ferrite mix, in this case 2 to 50 MHz.

Searching the ARRL suppliers' data base, it appears that Alstar Magnetics offers this core; an alternate would be a Palomar F37 with mix 61. There is no criticality here — if you want to try it, strip a core from any old source — perhaps from a junked PC power supply or computer cable. It may not be the most efficient RF transformer ever built, but if it works it will do the job.

Wrap 20 turns of 24 gauge enameled wire as the transformer secondary. The secondary is connected to half wave rectifier consisting of a silicon diode (1N914), a 10 kΩ resistor as the load and a 0.1 μF capacitor as a filter (see Figure 2). A high-impedance voltmeter (the $10 variety) is connected to the two pin jacks to serve as an indicator.

The unit shown was tested with a 100 W transmitter on all bands from 80 through 10 meters. Performance across each band was relatively uniform, considering the probable variation of SWR and power though the feed line as the frequency was varied.

Hook up the rest of the circuit as shown in Figure 2 and connect a meter to the terminals.

What we Have

The object here was not to get an exact measure of the antenna current. What I wanted was a relative measure, so I could see if anything was going wrong, or use it as a way to adjust my antenna tuner for the maximum signal to the antenna. Commercial stations use a current meter, mounted at the connection of the feed line to the antenna, to monitor output. Since they know the antenna impedance and their meters are calibrated, they can determine precise power into the antenna.

If you enjoy low power (QRP, typically 5 W or less) or very low power (QRPP, less than 1 W) operation, more turns may be needed and can easily be added.[3] Similarly, if your meter does not have enough sensitivity, more turns may be called for. If after assembly the core is not firmly in place, held by the friction of the secondary on the primary wire, a drop of glue can be used to secure it all together.



Figure 2 — Schematic diagram of the relative RF current meter. Nothing about the circuit is critical. See text for parts information.

Putting it to Use

The current meter consumes a miniscule fraction of the output power, so, can be left in the line, or removed when not in use. You may even find a meter case and a surplus meter at a hamfest that will work with it to give continuous indication without tying up your bench meter. I suggest writing the relative current indication for each band in your log. Later, if something seems amiss, it is then an easy job to compare your readings to the recorded ones to find out if the problem is in your antenna system.

Notes

[1] E. Nichols, KL7AJ, "Keeping Current with Antenna Performance," *QST*, Feb 2009, pp 34-36.

[2] Each pass through the center of a toroid counts as a full turn.

[3] Low power operators may obtain better results using a germanium diode, such as a 1N34, in place of the silicon diode due to its lower forward voltage drop.

ARRL Member Paul Danzer, N1II, was first licensed in 1953, and now holds an Amateur Extra class license. Paul has been operating 40 meter CW almost constantly since he first started. He uses his years of experience as an electronic engineer to design and build small, one-night ham radio projects. Currently he is a Professor of Computer Science at Housatonic Community College in Connecticut. He can be reached at **n1ii@arrl.net**.

From September 2009 QST © ARRL

Review Questions

4-1 Why is it important to listen to the operating frequency before you start the tuning process?

4-2 Why is it a good idea to manually initiate tuning with your auto-tuner before transmitting on a new frequency at full power?

4-3 If there are more than one set of tuner settings that provide a 1:1 SWR, which should you choose?

Chapter 5

The Internal Tuner — How Does it Help?

The Yaesu FT-2000 transceiver, one of many modern transceivers equipped with an automatic internal antenna tuner.

Contents

The Flavors of Internal Tuners 5-2
Tuner Impedance Range 5-2
Impedance Limits of Internal Tuners 5-3
That Coax Connector 5-3
Coax Loss — If Things Seem Too Good to Be True 5-3
What Else is Going to be in Your Station? 5-3
Review Questions 5-4

So far, our discussions about antenna tuners have made it appear that they are a separate device that is inserted between a transceiver and an antenna system. While that's often true, we should also consider the case of a transceiver that has an internal, almost always automatic, antenna tuner.

The idea of an automatic antenna tuner is that it can sense the SWR and adjust the tuner to minimize it. This is most commonly accomplished by a configuration consisting of a collection of inductors and capacitors that can be switched in or out of a matching network until the lowest SWR is obtained. A few automatic tuners actually rotate the shaft of a variable capacitor using an electric motor as the driving element.

The Flavors of Internal Tuners

Some transceivers offer an internal tuner as an extra cost option, in many cases one that can be added if needed. In other cases, the transceiver with tuner is essentially a separate model that has to be specified at the time of purchase. Other transceiver lines come only with or only without an internal tuner. Thus, if you're in the process of deciding on your next (or first) transceiver it's good to think carefully about your requirements before you make a decision. **Figures 5-1 – 5-3** illustrate radios with some of the choices.

Figure 5-1 — The Elecraft K-3 is an entirely modular design, including the option of a wide-range internal antenna tuner.



Figure 5-2 — The ICOM IC-7600 is only available with a built in antenna tuner.

Figure 5-3 — The Kenwood TS-480 is available as either a 100 W version with internal tuner (TS-480 SAT) or 200 W version without (TS-480 HX).

Tuner Impedance Range

As noted previously, all antenna tuners have limits on the range of impedances that they can transform to the desired load — almost always 50 Ω. In many cases the range of values is dependent on the frequency, often narrower on 6 meters than on the HF bands. Most tuner designs are limited on the low frequency end by the maximum values of the inductors and capacitors, and on the high frequency end by their minimum values, often the minimum capacitance of the elements to the metal case.

Thus it is often the case that the range of impedance values that the tuner is able to match is greater in the middle of the range than on the ends — typically 80 or 160 meters on the low end and 10 or 6 meters on the high end. Most manufacturers provide a single specification such as "tunes SWR at least 10:1" or "matches from 5 to 500 Ω." Note that the latter specification is not as general as the first — does it mean it only matches resistive loads? Probably not, since it would be hard to design a tuner that just did that, nor would it be very useful. I tend to think that both ratings actually mean the same 10:1 SWR.

If they deliver on their promise, that would mean that they would actually tune the 10:1 range on the highest and lowest bands, and actually tune a wider range in the middle — and many seem to do just that.

Impedance Limits of Internal Tuners

While most external tuners have rating similar to the 10:1 discussed above, many transceivers have internal tuners rated at a 3:1, or 16.5 to 150 Ω tuning range. This seems to be particularly true of the radios provided by the large Japanese companies — ICOM, Kenwood and Yaesu. In contrast, the US made HF transceivers, Elecraft, FlexRadio and Ten-Tec, offer internal tuners specified to tune a 10:1 range.

The tuners with a 3:1 range are intended to deal with a matched antenna operated somewhat away from its design frequency. A look at the SWR plots in Chapter 2 provides the idea. While a 3:1 range will easily cover a 40 meter dipole across the whole band, it will only cover about 300 kHz of the 500 kHz width of 80 meters with a standard 80 meter wire dipole (see Figure 2-7).

The tuners with a tuning range of 10:1 or greater are what I call *wide range* tuners. These tuners can not only deal with an 80 meter dipole across the whole band, but can be used to match a whole spectrum of antenna types ranging from random, non resonant, wires to dipoles fed on multiple bands and exotic high gain antennas such as V beams or rhombics.

That Coax Connector

All current internal tuners terminate on the back of the radio in a coax connector, just as do radios without a tuner. This is a signal that they are intended to drive into coax fed *unbalanced* antenna systems. We will discuss the various benefits of balanced and unbalanced transmission lines a bit later, however, it is worth pointing out that many external tuners are set up to drive either. If your antenna system is balanced, you will need to make the transition from coax to balanced line outside the radio, tending to reduce the "all in one box" benefit of the internal tuner.

Coax Loss — If Things Seem Too Good to Be True...

It is tempting to try to use the antenna tuner to "force fit" an antenna to work on a band other than the one it's designed for. This can often appear to work, but appearances can be deceiving. Let's take one example.

Say you have a 20 meter dipole fed with 100 feet of RG-58 coaxial cable. The antenna works very well on 20 meters, and requires just a bit of trimming with the tuner for proper operation. So far so good.

All of a sudden sunspots reappear after years of absence and 10 meters is wide open with great signals world wide (sooner or later it's bound to happen). You have no antenna for 10 meters, so try using your 20 meter dipole. Wonder of wonders, it actually tunes with the internal tuner — a perfect match! You hear your neighbors working distant stations right and left, but no one hears you — what's the story?

This is an interesting case that provides a cautionary tale, as well as outlines one of the challenges of designing multiband antennas. On 20 meters, our dipole (depending on height) will have an SWR of around 1:1. The 100 feet of RG-58 coax will have a loss of about 37% (less than 2 dB), not noticeable in most cases, and all will be fine.[1]

Move to 10 meters and the 20 meter dipole will no longer provide a good match. In fact, my model indicates that its impedance will be 3836 Ω resistive in series with 790 Ω capacitive reactance — an SWR of 81:1! The high SWR increases the loss of the transmission line to about 15 dB. That means that of our 100 W, only 3.1 W will reach the antenna — that explains why we aren't being heard as well as our neighbors!

The perhaps more interesting aspect of this is that the power reflected by the mismatched antenna also is reduced by 15 dB on its way back to the tuner. Because of this, the tuner only sees an SWR at the bottom of the cable of about 3:1 and will happily adjust for a match. Thus the radio is happily transmitting, but 97% of its power output is heating up the transmission line.

What Else is Going to be in Your Station?

Another consideration as to whether an internal tuner will be your best choice is whether you have, or expect to have, a linear amplifier following your transceiver. For some types of operation, being able to select whether you transmit 100 or 1500 W can make a big difference.

If you have a linear amplifier and need a tuner, you will need an antenna tuner on the output side of your linear. A tuner in your transceiver can adjust for a mismatch in the input side of the amplifier (rarely needed), but can't help with tuning the antenna system. That has to be done at the output of the amplifier — and at the higher power level. If the amplifier is turned off, the radio's tuner can be used to match the antenna, but you will want to disable it when you switch to high power.

Thus, if you have or expect to have, a linear amplifier as a part of your station; you may want to consider a transceiver without a tuner and instead purchase a tuner with a power rating that can handle your linear. Note that this is mostly a monetary statement, since there is no harm in having the additional tuner in your transceiver. It can be turned off if you don't need it. I actually have one in my transceiver and another following the linear. I find the transceiver's internal tuner handy when I take my transceiver on vacation and am forced to use "antennas of opportunity."

---

[1] We will use decibels (dB) to express gain and loss ratios throughout the book. If you need a refresher on the topic, please see Appendix A.

Review Questions

5-1 What are some of the advantages of an internal antenna tuner in a transceiver?

5-2 What kind of antennas can be tuned with a tuner that can tune an SWR of 3:1?

5-3 Why isn't an antenna that can be tuned with an internal tuner always effective?

Chapter 6

An External Tuner at the Radio


MFJ DIFFERENTIAL-T TUNER
HIGH POWER ANTENNA TUNER
VECTRONICS
INDUCTOR
DIRECT
TUNED
INPUT
OUTPUT
AT1500CV
TRANSMITTER
ANTENNA
INDUCTANCE

Five high power (1 kW or higher rating) manual tuners, one choice for an external tuner to place near the transceiver

Contents

Automatic versus Manual Tuners..6-2
Review Questions..6-4

In place of an antenna tuner that is built into the transceiver, another option is to have one next to the radio. Note that this is the functional equivalent of an internal tuner, and shares the potential problem of appearing to work well with an inappropriate antenna, as described in the previous chapter.

There are many available choices for such a device, including automatic tuners from some radio manufacturers that integrate directly with radio controls. There are others from after market manufacturers that offer additional features and, in some cases, are less expensive than internal tuners. While you do have to have an extra box on or near your radio, external tuners may offer some significant advantages:

- As discussed in Chapter 3, they can have a wider tuning range than many internal tuners.
- If you think you may want to add (or if you have) a high powered linear amplifier, you can select a tuner compatible with the higher power.
- Some external tuners offer both balanced and unbalanced outputs.
- Some external tuners offer multiple switched connections so different antennas can be quickly brought on line.
- If you have multiple radios, they can be switched to the tuner input so only one tuner is needed.

Automatic versus Manual Tuners

The first decision you will be faced with if you want an external tuner is whether you prefer an automatic or a manual one. As the name implies, an automatic antenna tuner finds the optimum, or near optimum, settings by itself. The manual tuner usually has three controls that require adjustment to obtain the best match.



Figure 6-1 — High power (1 kW or greater) automatic antenna tuners from Palstar, LDG and MFJ).

In the past, automatic tuners were not available at high power levels, so those with high powered stations had no choice but to use manual tuners. That is no longer the case, as automatic tuners are available at all legal amateur power levels (See **Figure 6-1**). Over the years, the ARRL has tested many manual and automatic tuners as part of *QST* product reviews. I was surprised to find that to our level of measurement precision, there was not a big difference in efficiency between tuners in the two groups. Still, there are some benefits to manual tuners and many amateurs are happy with the results they receive.

Automatic Antenna Tuners

To operate an automatic, you just feed it some power, hit a TUNE button and listen and watch while it finds satisfactory settings. Many tuners can do this in tens of seconds the first time and often remember the settings so the next time it takes just a few seconds or less for that antenna at that frequency.

In my experience there's not a lot not to like about an automatic antenna tuner. I have a number of them for particular applications, although I still use a manual tuner for my main station tuner. The key is to select a tuner that will operate with your radio — some are radio independent, while some work with the same radio controls that would operate one from the manufacturer of the radio.

One issue with some automatic tuners is just what happens if they sense a mismatch as you operate. Most automatic tuners are rated to tune at reduced power to avoid excessive arcing at relay contacts. If you change frequency or even if the wind blows your antenna around and the tuner starts tuning, the results could be dramatic. Some allow disabling the auto tune function once you have it tuned, others automatically cut back on power. In my opinion, it's better to be able to take control yourself.

Manual Antenna Tuners

Manual tuners do often provide an additional level of control capability. Some have switch selectable outputs for multiple balanced and unbalanced antenna connections. One can be dedicated to a dummy load, if you don't (yet) have enough antenna connections to fill up the jacks. Manual tuners often provide SWR and power metering independent of that of the radio.

Most automatic tuners tune until they reach what they consider a reasonable match, perhaps 1.5:1. Hopefully it is a value that will allow your radio to operate at full power. The manual tuner let's you set it to whatever threshold you think is best — although if your transmitter can put out full power, it won't make much difference.

Review Questions

6-1 What are three potential benefits of using an external tuner at the radio rather than an internal tuner in the radio?

6-2 What are the benefits of an internal tuner?

6-3 What limitation is common to either internal or external tuners located at the radio?

Chapter 7

Transmission Lines



Transmission lines come in many forms, serving many applications.

Contents

Characteristic Impedance 7-2
Propagation Velocity 7-3
Attenuation 7-3
What Can We Do to Reduce Transmission Line Loss? 7-5
Sidebar: Determining the Input Impedance of an Unmatched Transmission Line 7-6
Review Questions 7-7

As we have mentioned previously, frequently the antenna and radio are not in exactly the same place. There are some notable exceptions, particularly in portable hand-held systems and various microwave communications and radar systems. In most other cases, optimum performance requires the transmitter and receiver to be at some distance from the antenna. It may also be a matter of combat survival, especially if your enemy is equipped with anti-radiation weaponry designed to home in on a signal. The component that makes the interconnection is called a *transmission line.*

Transmission lines are used in places besides radio systems — for example, power distribution lines are a kind of transmission line, as are telephone wires and cable TV connections. In addition to just transporting signals, transmission lines have some important properties that we will need to understand to allow us to make proper use of them. This section will briefly discuss the key parameters.

Characteristic Impedance

A transmission line generally is composed of two conductors, either parallel wires such as we see on power transmission poles, or one wire surrounding the other as in coaxial cable TV wire. The two configurations are shown in **Figure 7-1**. Either type has a certain inductance and capacitance per unit length and can be modeled as shown in **Figure 7-2**, with the values determined by the physical dimensions of the conductors and the properties of the insulating material between the conductors. If a voltage or signal is applied to such a network, there will be an initial current flow independent of what's on the far end of the line, but based only on the L and C values. The initial current will be the result of the source charging the shunt capacitors through the series inductors and will be the same as if the source were connected to a resistor whose value is equal to the square root of L/C.

If the far end of the line is terminated in a resistive load of the same value, all the power sent down the line will be delivered to the load. This is called a *matched* condition. The impedance determined in this way is called the *characteristic impedance* of the transmission line, and is perhaps the most important parameter associated a transmission line. Common coaxial transmission lines have characteristic impedances (referred to as Z_0) between 35 and 100 Ω, while balanced lines are found in the range of 70 to 600 Ω. What this means to us as radio people, is that if we have an antenna that has an impedance of 50 Ω and a radio transmitter designed to drive a 50 Ω load, we can connect the two with any length of the appropriate 50 Ω coaxial cable and the transmitter will think it is right next to the antenna. The antenna will receive most (see next section) of the transmitted power and all is well with the world!



Figure 7-1 — Parallel wire and coaxial transmission lines.



Figure 7-2 — Lumped constant equivalent of an ideal transmission line.

Propagation Velocity

Signals in air dielectric transmission lines propagate at almost the speed of light in air. Other dielectric materials between the conductors cause the signals in transmission lines to slow down just as we observe with light rays traveling through water. In many cases, this is not a matter of concern, since we often only care that the signals get out the other end, however, there are some exceptions.

The velocity can be shown to be reduced by a factor of one over the square root of the relative dielectric constant of the insulating material. Some cable specifications provide the relative velocity as a fraction of the speed of light. If not, and you know the material, most engineering handbooks include tables of properties of materials. For example, polyethylene is a common cable insulating material and has a relative dielectric constant of 2.26. The square root of 2.25 is 1.5, so the propagation velocity in polyethylene insulated coaxial cable is about $3/1.5 \times 10^8$ or 2×10^8 m/sec.

Some applications actually use coaxial cables to provide delayed signals in pulse and other applications. Having a way to accurately predict the delay just by knowing the cable characteristics and measuring the length of the cable can save a lot of lab time.

Attenuation

The ideal transmission line model shown in Figure 7-2 passes all input power to a matched load at the output. A real transmission line also has resistance associated with the wire conductors and some loss of signal due to the nature of the insulating material. As transmission lines are made larger, the resistance is reduced and as the dielectric material gets closer to low-loss air, the losses are reduced. The skin effect causes currents to travel nearer to the surface of the conductors at higher frequencies, and the effective loss thus increases as the frequency is increased.

Figure 7-3 provides some real world examples of the losses as a function of frequency for the most common types of transmission line. Note that the loss increases linearly with length and the values are for a length of 100 feet. Note also that the losses shown are for transmission lines feeding into loads matched to their Z_0. As will be discussed shortly, losses can increase significantly if the line is not matched. The "open wire"



Figure 7-3 — Loss of some typical transmission lines in dB per 100 feet as a function of frequency. The RG-58 transmission lines are 50 Ω polyethelene insulated coaxial cable slightly less than ¼ inch in diameter. The RG-8 through RG-216 are 50 and 70 Ω polyethelene insulated transmission lines with a diameter somewhat less than ½ inch. The "hardline" types have a foam dielectric very near to air.

line shown consists of two parallel wires with air dielectric and infrequent spacers, typically resulting in a Z_0 of around 600 Ω. While the losses of such a line are low, they only work well if spaced from metal objects and lossey material and not coiled up, while coaxial cables have higher loss, all the signal is within the outer conductor and they can be run in conduit, coiled up, placed next to other wires and are therefore much more convenient to work with.

Sometimes a long straight run of open wire line will be transformed to 50 Ω at the ends with coaxial cable used at the antenna and radio ends to take advantage of the benefits of both.



Figure 7-4 — Additional loss of a transmission line when mismatched. This loss needs to be added to the loss in Figure 7-3 for mismatched lines.

Lines with Unmatched Terminations

In our discussions so far, we have been talking about transmission lines feeding terminations matched to their characteristic impedance. In that case, the voltage-current relationship at the load will reflect the impedance of the load — not the characteristic impedance. Along the line the voltage and current will vary with distance providing a load to the transmitter end that is generally neither that of the far end Z_L, nor the Z_0 of the transmission line. The transmitter load can be calculated knowing the Z_L, the Z_0 and the electrical length of the line as discussed in the sidebar.

The ratio of maximum voltage on the line to minimum voltage on the line is called the *standing wave ratio* or SWR. A matched line has an SWR of 1:1, a 50 Ω line terminated with a 25 or 100 Ω load will have an SWR of 2:1. There are a whole family of complex impedances that will also have a 2:1 SWR, by the way. The computation is easier with resistive loads.

There are some interesting special cases with a mismatched line. The load impedance, resistive or complex, repeats every λ/2, for example. The impedance goes to the opposite extreme in odd multiples of a λ/4. For example our 25 Ω load would get transformed to 100 Ω in λ/4 or ¾ λ transmission line sections and vice versa. This effect can be used to our advantage if we wish to transform impedances at a specific frequency. In this case, the line is actually acting like a kind of antenna tuner.

A generally less desirable effect of mismatched lines is that the losses increase. This is easy to see, if voltages and currents are higher, we might expect losses to increase as well. **Figure 7-4** provides the additional loss for a mismatched line that needs to be added to the matched loss in Figure 7-3. As is evident, the combination of matched loss and high SWR results in dramatic increases in loss. This is why antenna designs that don't use matched transmission lines often use air-dielectric lines.

What Can We Do to Reduce Transmission Line Loss?

By now you should have a clear understanding of what can happen to a signal if applied to an antenna system through even a relatively short length of coaxial cable that has a high SWR. Depending on the matched loss, length and SWR, much of your signal can disappear before it gets to the antenna.

The insidious aspect of this is that while this is happening, the SWR at the radio with a collocated or internal tuner looks great — a perfect match and easy to get it. Losses are like that — they tend to result in a wide SWR bandwidth, as does a dummy load. Not a good thing if you want to communicate over the air. Fortunately, there are three fairly straightforward approaches to solving this problem:

- Change the antenna to one with either a wide enough bandwidth to cover all frequencies of interest, or one that covers multiple amateur bands with low SWR. This is not a topic for a book on antenna tuners, but is covered in many books on antennas.[1,2]
- Move the antenna tuner to, or close to, the antenna location. This is the subject of Chapter 8, or;
- Use a transmission line that has low enough matched loss so that even a high SWR doesn't result in high losses. This is the subject of Chapter 9.

Notes

[1] J. Hallas, W1ZR, *Basic Antennas — Understanding Practical Antennas and Designs,* Available from your ARRL dealer or the ARRL Book-store, ARRL order no. 9994. Tele-phone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.org/arrl-store/**; **pubsales@arrl.org**. See Chapter 11, "Wideband Dipole Arrays;" Chapter 12 "Multiband Dipole Arrays" or Chapter 21 "Log Periodic Dipole Arrays," for example.

[2] R. D. Straw, Editor, *The ARRL Antenna Book,* 21st Edition. Available from your ARRL dealer or the ARRL Bookstore, ARRL order no. 9876. Telephone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.org/arrl-store/**; **pubsales@arrl.org**.

Determining the Input Impedance of an Unmatched Transmission Line

The input impedance of a transmission line of any length with any terminating impedance can be determined in a number of different ways.

The most straightforward way is through direct calculation. Unfortunately, this is also perhaps the most time consuming and perhaps most error prone method, at least until you have it set up on a spreadsheet or other program that can handle he hyperbolic function.

My favorite way to determine the input impedance, standing wave ratio (SWR) as well as the line loss, is to use *TLW* (*Transmission Line for Windows*) software that comes with *The ARRL Antenna Book*.[3] The main screen is shown in Figure 7-A performing an analysis of an antenna with a complex load impedance fed through 100 feet of coaxial cable.


TLW
Help
Graph
Tuner
Print
Exit

TLW, Transmission Line Program for Windows

Version 2.0, Copyright 2000-2003, ARRL, by N6BV, July 22, 2003

Cable Type: RG-58A (Belden 8259)

● Feet ○ Meters Length: 100.000 Feet 1.556 Lambda Frequency: 10.1 MHz

Use "w" suffix for wavelength (for example, 0.25w)

Characteristic Z0: 50.0 - j 0.92 Ohms Matched-Line Loss: 1.555 dB/100 Feet

Velocity Factor: 0.66 Max Voltage: 1400 V Total Matched-Line Loss: 1.555 dB

Source: ● Normal ○ Autek ○ Noise Bridge

● Load ○ Input Resistance: 74.3 Reactance: 16.1 Ohms

● Volt./Current ○ Resist./Reac.

SWR at Line Input: 1.40 SWR at Load: 1.62 Rho at Load: 0.23679

Additional Loss Due to SWR: 0.106 dB Total Line Loss: 1.661 dB

Impedance at Input: 69.02 - j 6.23 Ohms = 69.30 Ohms at -5.15 Degrees

Figure 7-A — The main screen of *TLW* (*Transmission Line for Windows*) software is shown performing an analysis of the condition of the L/D of 10,000 case.

The antenna input impedance (74.3 + *j*16.1) is inserted in the LOAD box. The + *j*16.1 indicates an inductive reactance with a value of 16.1 Ω at the frequency of interest (10.1 MHz). A –*j* value would indicate a capacitive reactance, which would be entered with a minus sign. The output impedance through 100 feet of RG-58A 50 Ω coax is provided at the bottom in both rectangular (69.02 – *j*6.23) and polar coordinates (69.53 @ –5.15°), along with the SWR at line input (1.40:1) and output (1.62:1) as well as line loss (1.661 dB) — both for the matched case (1.555 dB) and the additional loss due to mismatch (0.106 dB). That's about everything I could think to ask, except which pile in the basement has the RG-58A!

A third way to evaluate the input impedance is through a graphical method. A Smith chart, see Figure 7-B, can be used to determine the input impedance of a transmission line. This was very commonly used before the personal computer became ubiquitous. In addition to the accuracy limitations due to the input and output resolution inherent in a chart, the Smith chart assumes that the line is lossless. This may result in significant errors depending on the amount of line loss.


SMITHCHART
WAVELENGTHS TOWARDS GENERATOR
WAVELENGTHS TOWARD LOAD
ANGLE OF REFLECTION COEFFICIENT IN DEGREES
INDUCTIVE REACTANCE COMPONENT (+jX/Zo), OR CAPACITIVE SUSCEPTANCE (+jB/Yo)
CAPACITIVE REACTANCE COMPONENT (-jX/Zo), OR INDUCTIVE SUSCEPTANCE (-jB/Yo)
RESISTANCE COMPONENT (R/Zo), OR CONDUCTANCE COMPONENT (G/Yo)
RADIALLY SCALED PARAMETERS
TOWARD GENERATOR
TOWARD LOAD
STANDING WAVE
VOLT RATIO
IN DB
TRANS LOSS
1 DB STEPS
LOSS COEFF
REFLECTION COEFF
VOLT
PWR
RETN LOSS IN DB
REFL.
CENTER

Figure 7-B — A Smith chart used for the graphical determination of the input impedance of a lossless transmission line.

[3] *TLW* is supplied with *The ARRL Antenna Book*, 20th Edition, available from the ARRL Bookstore at **www.arrl.org/catalog/** order number 9043 — $39.95.

Review Questions

7-1 Describe three reasons it might be desirable to have a transmitter and an antenna in different locations.

7-2 If you want to make a $\lambda/4$ section of RG-213 for our 10 MHz system, how long would you make it?

7-3 A 1000 W transmitter at 15 MHz is feeding a matched load through 200 feet of RG-8 transmission line. How much power reaches the antenna? Repeat if the frequency is 150 MHz. Repeat both cases if the antenna has an SWR of 3:1.

Chapter 8

Moving the Tuner to the Back 40

LDG Electronics
1445 Parran Road
St. Leonard, MD 20685
Antenna
Transmitter
Remote Interface
RT-11 Automatic Tuner
LDG

Automatic antenna tuners designed for remote mounting. On top, one from SGC, beneath a model from LDG.

Contents

An Example of Using a Remote Tuner to Minimize Loss.... 8-2

Intermediate Steps 8-4

Remote Antenna Tuners — the Downside........................ 8-5

Review Questions.. 8-6

Some automatic antenna tuners are designed to be mounted remotely, rather than being collocated with the radio. We can take advantage of this in order to minimize losses in the transmission line between the antenna system and the transceiver. With the tuner at the antenna end, the load at the antenna end of the transmission line provides very close to a 1:1 SWR. The line will then have only the matched loss between the radio and the tuner, not the additional loss due to mismatch.

An Example of Using a Remote Tuner to Minimize Loss

Figure 8-1 shows the configuration of a transceiver with a remote automatic antenna tuner at the antenna. Let's assume that the transmission line is RG-58 and that it is 100 feet between the radio and the tuner plus the tuner is connected directly to the feed point of the coax fed antenna.

We will again use the example from Chapter 4 of a 20 meter dipole tuned by the tuner to operate on 10 meters where its impedance will



Figure 8-1 — Configuration of a transceiver with a remote automatic antenna located at the antenna.

Table 8-1
Comparison of System Losses for Remote and Collocated Tuners — RG-58

Loss Element	*Tuner at Radio*	*Remote Tuner Beneath Antenna*
Loss in 100' Cable (dB)	14.7	2.9
Percent Power Lost (%)	96.6	48.1
Power to Antenna at 100 W (W)	3.4	51.9

Table 8-2
Comparison of System Losses for Remote and Collocated Tuners — LMR-400

Loss Element	*Tuner at Radio*	*Remote Tuner Beneath Antenna*
Loss in 100' Cable (dB)	8.62	0.66
Percent Power Lost (%)	86.3	14.1
Power to Antenna at 100 W (W)	13.7	85.8

be 3836 Ω resistive in series with 790 Ω capacitive reactance — an SWR of 81:1. **Table 8-1** provides the comparison in loss for a 100 W output transceiver, in each case assuming the antenna tuner contributes no loss. While this is slightly optimistic, that loss is usually very small. The result is rather dramatic and illustrates why just hitting the TUNE button on your internal tuner may not provide satisfactory results even if the resulting radio SWR ends up at a perfect match.

Perhaps you will also not be satisfied with moving your tuner to the antenna and still losing almost half your power in the RG-58. The lesson here is that RG-58, while available and relatively inexpensive, is not the best choice for even a 100 foot run at 28 MHz. Of course, it's much worse as you move to VHF, and keep in mind that it effects both transmit and receive signals.

One of the lowest loss flexible coaxial transmission lines that fits the usual UHF coax connectors is Times Wire LMR-400. There are similar cables by other manufacturers. **Table 8-2** repeats the exercise shown in Table 1 with the lower loss cable. Note that while there is measurable loss even for the matched case, it is less than 1⁄10 of an S-unit, so hardly noticeable, and much less than the loss for the tuner located at the radio that will result in about a 1.5 S-unit reduction on the receiving station's meter.[1]

[1] Notes appear on page 5.

Intermediate Steps

Not all antenna systems are structured in a way to allow a tuner to be at a feed point. An example might be a dipole suspended between two supports with a transmission line hanging in the middle. In this case, it is tempting to consider a short coax run from the antenna itself to the tuner as shown in **Figure 8-2**. This arrangement may also be necessary if the tuner is not waterproof and requires shelter from the elements.

This is a feasible arrangement; however, while a substantial portion of the loss can be eliminated in this way, the loss in the section between the tuner and the antenna can still be surprisingly high. For example, for the RG-58 case of Table 8-1, a 30 foot run between the antenna and the tuner would have a loss of 4.4 dB, or 64% of the power, leaving only 36 W from your 100 W transmitter to be radiated — if it got to and through the tuner without other losses.

A better way to accomplish this in many cases will be to use a section of the low loss transmission line discussed in Chapter 9 between the antenna and the tuner.


Dipole
Coax Cable
HF Transceiver
Coax
Lightning Arrestor
Multiple Turns on Ferrite Core
Remote Antenna Tuner
888888
ARRL0634

Figure 8-2 — Configuration of a transceiver with a remote automatic antenna located beneath the antenna.

Remote Antenna Tuners — the Downside

The use of a remote antenna tuner has a few disadvantages. I currently use three in various station locations and am quite happy with them in spite of the downsides:

- One remote tuner is located near my main basement station. I share antennas with my spouse (Nancy, W1NCY), who has an upstairs station. With an automatic tuner that can be patched to antennas from the W1ZR main station, she has access to any W1ZR antenna with low loss in the 100 foot coax run to her desktop setup.
- On our sailboat, I use an insulated backstay as an HF antenna. This non-resonant system has a high SWR on all bands and requires a tuner at the feed point to feed it against ground. I have a short lead from a corner under the lazerette beneath the antenna feed with another short lead to the engine block where a ground connection is available. Not only does it work well on all HF bands, but by keeping the radiating portion of the system in the corner of the boat, I minimize interference between the radio and marine navigation systems.
- I also have a remote tuner in the trunk of my car for my mobile HF system. Typical HF mobile antennas have very narrow SWR bandwidths. By using a remote antenna tuner at the antenna base, I can cover entire bands, or even tune to lower frequency bands than the antenna is designed for. While this sort of operation isn't as efficient as adjusting the antenna itself, it is much easier than making adjustments while driving at highway speeds!

There are a few aspects of remote tuner operation that might be disadvantageous for some. One is the fact that in most such installations the tuner becomes integrated into a particular antenna structure. If we have multiple antennas, each will need its own tuner — a potentially expensive proposition.[2] It also is the case that in addition to providing coaxial cable to the tuner, one must also provide operating power and sometimes control signals to the tuner. Some tuner manufacturers package the coax, power and control into extension cable assemblies that can be used for this purpose. Another possibility is to use a *bias-T* to insert the power onto the coax cable, sharing it between the two functions.[3]

Notes

[1] The Collins Radio established, now industry standard, S-meter calibration is that S-9 equals 50 µV at the antenna terminals and each S-unit represents a change of 6 dB. To say that not all amateur S-meters follow this standard would be an understatement.

[2] Remotly controlled antenna switches may be used to solve this problem, although commercial units cost as much as some remote 100 W antenna tuners.

[3] S. Ford, WB8IMY, "Short Takes — MFJ-4712 Two-Position Remote Antenna Switch," *QST*, Sep 2006, p 48.

Review Questions

8-1 Why is the quality (loss) of a transmission line more important in the mismatched than the matched case?

8-2 If using an internal tuner in a transceiver, why might the SWR *before* tuning be an important indicator of antenna system efficiency?

8-3 Why is the SWR *before* tuning insignificant if an antenna located tuner can match to the transmission line Z_0?

Chapter 9

Transmission Line Choices for Low Loss



Coaxial cables going up one of the towers at W1AW, the ARRL Headquarters station

Contents

Hello Real World!.. 9-2

How Can We Determine Loss?.. 9-3

How is Transmission Line Made? 9-4

Know What's Happening at the Shack —

Sidebar: What's Happening at the Other End of my Feed Line? 9-5

Review Questions.. 9-6

The ideal transmission line accepts the output power (as well as received signal) from its source and delivers it to its destination load without loss. If the characteristic impedance (Z_0) is the same as the source and load impedances, it delivers it with the same ratio of voltage to current. That means, for all practical purposes, the ideal transmission line is invisible to the system. Devices connected to both ends act as if they were collocated, except for the delay in signal arrival time, unimportant except in special circumstances.

Hello Real World!

Unfortunately, ideal transmission lines don't exist, although for many applications we can come remarkably close. The primary issue in most cases is loss. We just don't get as much power to the far end as we put in. There are three primary mechanisms that result in transmission line loss. They are conductor resistance, dielectric loss and leakage or radiation.

Conductor Resistance

Figure 7-1 shows the geometry of the two primary types of transmission line. At (A) is a balanced transmission line, while at (B) we have coaxial cable of the type discussed in the earlier chapters of the book. Both propagate signals down the line as currents with their associated electric and magnetic fields. In a properly terminated transmission line, the magnitude of I_1 will equal that of I_2 with the result that fields at some distance will cancel. In the case of coaxial cable they cancel at the shield, while for balanced line they exist for some distance around the line.

The action of the currents in an ideal line can be modeled as shown in Figure 7-2 in Chapter 7. The model can be analyzed with reasonable accuracy in comparison to real cable if there are at least 10 sections per wavelength, and if the inductors and capacitors are modeled as real elements, including the resistance of the wire and the dielectric loss of the capacitors.

For the case of dc, the wire loss just equals the dc resistance of the wire, a function of its diameter and material. As frequencies increase, *skin effect* results in the current moving to the outer edge of each conductor. This makes the wires electrically appear as tubes, with the tube walls getting thinner as the frequency rises. The thinner walls decrease the effective cross sectional area of the conductors resulting in an increase in resistance and thus increased loss with frequency.

Dielectric Loss

An ideal transmission line would consist of conductors with the insulation between them a perfect lossless vacuum. While some transmission lines approach this, with air (or even special gasses) as the primary dielectric, real lines always have some lossey material between the conductors.

A lossey dielectric has two significant effects on signals: First, it slows the signal to some fraction of the speed of light. This is often an important consideration in multielement driven antennas that rely on accurate phasing of signals, but does not enter into this discussion.

Second, dielectric loss results in yet another contribution to line loss, and this also increases with increasing frequency.

Radiation or Leakage Loss

While generally less significant a loss factor than the previous two, some signal is lost in a real line due to it leaving the transmission line before it reaches the intended load. In a sense this is more a misdirected signal than a lost signal, and, because the signals end up in undesired places, the interference to other systems may be more important than the slight reduction in signal delivered to the desired load. Still, for either reason it can represents a significant issue for real lines.

In the case of coaxial cable, a portion of the shield resistance (depending on the shield coverage) results in a current that appears on the outside of the shield. The outer shield current actually makes the outside of the shield act as an antenna with resulting radiation detectable along the length of the shield. For balanced transmission line, the fields cancel wherever the distance to both wires is the same. For a perfectly installed line, that means all the places on a plane centered between the conductors and perpendicular to the line between them.

If the line is not perfectly installed, there will be some unbalance between the capacitance of each wire to ground resulting in a current unbalance that results in radiation. A similar effect occurs if the load is not perfectly balanced. Even in the case of perfect balance, there is some radiation in directions in which the distance to the wires is different. If the spacing is a small fraction of a wavelength, this radiation is diminished within a few times the wire spacing.

How Can We Determine Loss?

Transmission line loss is a design parameter that is specified by each manufacturer for their cables. The line loss is generally specified over the usual operating range at a number of frequencies, often 1, 10, 100, 1000 and 10,000 MHz.

Matched Loss

Figure 7-3 shows the *matched* loss per 100 feet of representative transmission line types. As you make choices of transmission line, it is important to note that this data is representative — the variation between attenuation of different manufacturers, and even different part numbers from the same manufacturer, can be striking. Check the manufacturer's Web page for the data sheet of the transmission line you are considering to be sure you know what you are getting.

For lengths other than 100 feet, the loss scales linearly. For example if a line has a matched loss of 2 dB at 100 feet, the same line, at the same frequency, will have a loss of 1 dB if 50 feet long, and 5 dB if 250 feet long.

Additional Loss Due to Mismatch

By now it should come as no surprise to find that a mismatched line has more loss than a matched one. The additional loss due to mismatch is a function of both the mismatch and the loss if matched. Figure 7-4 shows the additional loss in dB that occurs as a result of a line not being matched.

Note that the SWR shown is the SWR as measured, or calculated, at the load not the SWR measured at the transmitter end of the cable. This is particularly important in the case of a lossey line since the loss will reduce both the power reaching the antenna and the power of the reflected wave that is used to determine the SWR. This can give very optimistic, and erroneous results.

To give an example of this effect, consider a 100 W transmitter driving a 100 feet of coax with a loss of 3 dB (50% loss). The antenna will see 50 W of power. Lets say 20% of the power is reflected due to the antenna mismatch. That will result in 10 W being reflected back toward the source. The 3 dB loss results in 5 W showing up as reflected power at the bottom of the cable. This is quite different than if the 100 W were applied to the antenna on lossless line — in that case, a reflected power of 20 W, not 5 W, would, show up at the SWR measurement device.

Table 9-1 summarizes what we have at the two locations. Note the rather distressing result. A very acceptable measurement of an SWR of 1.6:1 at the bottom of the coax is the result of an unpleasant SWR of 4:1 at the antenna. In this example, our 100 W of power results in only 40 W radiated from the antenna — yet all of our measurements make us think we're doing well. Unfortunately, this example is not unusual, especially at the upper end of HF into the VHF range. If it happens at higher frequencies, it is usually more evident since nothing much ends up going in or out of the system! The sidebar discusses ways that this can be calculated, and perhaps avoided, through the use of software.[1]

Table 9-1
Forward and Reflected Power and SWR as Seen at Each End of a Transmission Line with 3 dB Loss

Measurement	*Bottom of Cable*	*Top of Cable*
Forward Power (W)	100	50
Reflected Power (W)	5	10
Indicated Reflection Coefficient	0.224	0.447
Indicated SWR	1.6	4.0

---

[1] J. Hallas, W1ZR, "I Know What's Happening at the Shack — What's Happening at the Other End of my Feed Line?" *QST*, Feb 2007, p 63.

How is Transmission line Made?

You may wonder what is it about transmission lines that makes their loss performance so different. It all comes down to how and of what they are made. **Figure 9-1** shows typical construction techniques of parallel and coaxial transmission line types. Not shown are lines with mostly air as a dielectric, the lines with the least loss. Parallel line, so-called open-wire line, consists of two parallel bare wires with occasional spacers designed to keep them apart and at about the same distance. The traditional insulators were ceramic, however, recent lines have used plastic or PVC spacers. Mostly air-dielectric coax is sometimes encountered. Such cable that I've seen is formed from two concentric copper tubes with ceramic donut shaped spacers every foot or so.

The characteristic impedance of cable is a function of conductor diameter and spacing. Thus as line gets larger, each conductor gets larger for the same Z_0 and thus the resistance is reduced, resulting in lower loss with larger cable.

The balanced line (more next chapter) has progressively less attenuation as the Z_0 gets higher (the ratio of series resistance to load resistance goes down) and as the polyethylene dielectric is replaced by air, partially in the case of window line (C) and more completely in open wire line described above.

Coaxial cable loss is similar in that foam dielectric is part polyethylene and part air. The lines with double (E) and solid metal (F, G) shields have lower resistance and much less leakage.

Perhaps not surprisingly, all the factors that make line have lower attenuation, make it more expensive. Still, in most systems, for reasonable distances, transmission line cost is a small part of total system cost, and often provides a worthwhile investment.


(A)
300-Ohm Twin-Lead
Conductors
Polyethylene Insulation
(B)
75-Ohm Twin-Lead
Conductors
Polyethylene Insulation
(C)
450-Ohm "Window" Line
Conductors
Outer Conductor (Braid)
Single-Shielded
(D)
Center Conductor
Dielectric
Outer Insulation (Vinyl Jacket)
Double-Shielded
(E)
Braid No. 2
Vinyl
Braid No 1
Vinyl
Hardline
(F)
Inner Conductor
Foam Dielectric
Aluminum Outer Conductor (Available with vinyl jacket)
Heliax
(G)
Foam Dielectric
Corrugated Copper Shield
Vinyl Jacket
ANT0862

Figure 9-1 — Construction techniques used in making flexible transmission lines.

I Know What's Happening at the Shack — What's Happening at the Other End of my Feed Line?

If you want to find out — here's the easy way using TLW.

Joel R. Hallas, W1ZR
Technical Editor, QST

I'm told that one of the more frequent questions received by *QST's* "Doctor" has to do with folks wanting to determine the impact of transmission line losses on the effectiveness of their antenna system. These questions are often along the lines of "I measure an SWR of 2.5:1 at the transmitter end of 135 feet of RG-8X coaxial cable. My transceiver's auto-tuner can tune it to 1.1, but how can I tell what my losses are?" or "How much difference will I have if I have a tuner at the antenna instead of using the built-in tuner?"

These are important questions that almost every amateur operator is faced with from time to time. An approximate answer can be obtained by using the graphs found in any recent edition of The ARRL Antenna Book showing the loss characteristics of many transmission line types, plus adding in the effect of an SWR greater than 1:1. The SWR at the antenna end can be determined from the bottom end SWR and the cable loss. Using these graphs requires a bit of interpolation or Kentucky windage, but can result in useful data.

But There's an Even Better Way!

Packaged with each of the last few editions of *The ARRL Antenna Book* is a CD containing the pages of the whole Antenna Book as well as some very useful software. The program that I use almost daily is one written by Antenna Book Editor R. Dean Straw, N6BV, called *TLW* for Transmission Line for Windows.

TLW provides a very easy to operate mechanism to determine everything I usually need to know about what's happening on a transmission line. When you open the program, you are presented with a screen as shown in Figure A. This has the values plugged in from the last time you used it, often saving a step. Let's take a quick tour of the inputs:

Cable Type — This allows you to select the cable you would like to analyze. A drop-down box provides for the selection of one of 32 of the most common types of coax and balanced lines. An additional entry is provided for User Defined Transmission Lines that can be specified by propagation velocity and attenuation.



TLW, Transmission Line Program for Windows

Version 2.0, Copyright 2000-2003, ARRL, by N6BV, July 22, 2003

Cable Type: RG-8X (Belden 9258)

● Feet ○ Meters Length: 135.000 Feet 4.890 Lambda Frequency: 28.5 MHz
Use "w" suffix for wavelength (for example, 0.25w)

Characteristic Z0: 50.2 - j 0.48 Ohms Matched-Line Loss: 1.87 dB/100 Feet
Velocity Factor: 0.8 Max Voltage: 300 V Total Matched-Line Loss: 2.525 dB

Source: ● Normal ○ Autek ○ Noise Bridge
○ Load ● Input Resistance: 125 Reactance: 0 Ohms
● Volt./Current ○ Resist./Reac.

SWR at Line Input: 2.49 SWR at Load: 7.45 Rho at Input: 0.42671
Additional Loss Due to SWR: 3.070 dB Total Line Loss: 5.595 dB
Impedance at Load: 15.73 - j 58.55 Ohms = 60.62 Ohms at -74.96 Degrees

Figure A — The opening screen of *TLW*, illustrating the process described in the article.

Length — In feet or meters, your choice.

Frequency — This is an important parameter when dealing with transmission line effects.

Source — This defines the form of the input impedance data. Generally, you can use NORMAL.

Impedance — The impedance can be specified as what you measure, resistive (real) and reactive (imaginary, minus means capacitive). This could come from your antenna analyzer at either end of the transmission line. Note, if you only know the SWR, not the actual impedance, all is not lost — see below.

Now for the Outputs

SWR — The SWR is provided at each end of the cable. This is an important difference that many people miss, important even with a moderate SWR at the transmitter end, as we'll see — the SWR at the antenna will be much higher due to the cable loss. With TLW, you instantly know the SWR at both ends, and the loss in the cable itself

Rho at Load — This is the reflection coefficient, the fraction of the power reflected back from the load.

Additional Loss Due to SWR — This is one of the answers we were after.

Total Loss — And this is the other, the total loss in the line, including that caused by the mismatch.

But Doctor, What if I can Only Measure the SWR — Not the Actual Impedance?

Often the only measurement data available is the SWR at the transmitter end of the cable. Because the losses are a function of the SWR, not the particular impedance, you can just put in an arbitrary impedance with that same SWR and click the INPUT button. An easy arbitrary impedance to use is just the SWR times the Z_0 of the cable, usually 50 Ω. For example, you could use a resistance of 125 Ω to represent an SWR of 2.5:1. This is what we've done in Figure A, using 135 feet of popular Belden RG-8X.

The results are interesting. Note that the 2.5:1 SWR as seen at the radio on 28.5 MHz results from a 7.45:1 SWR at the antenna — perhaps this is an eye-opener! Note that of the 5.6 dB loss, more than half, or 3.1 dB, is due to the mismatch. Note that if we used something other the actual measured impedance, we can't make use of the impedance data that TLW provides. We can use the SWR and loss data, however, but that's probably what we wanted to find out.

We can now do some "what ifs." We can see how much loss we have on other bands by just changing the frequency. For example, on 80 meters, with the same 2.5:1 at the transmitter end, the SWR at the antenna is about 3:1 and the loss is slightly more than 1 dB. We could also plug in an impedance calculated at the antenna end and see what difference other cable types would make. For example, with the same 28.5 MHz SWR of 7.45 at the antenna and 135 feet of 1/2 inch Andrew Heliax, we will have a total loss of 1.5 dB at 28.5 MHz. Note that the SWR seen at the bottom will now be 5.5:1 and our radio's auto-tuner might not be able to match the new load.

But Wait There's More!

You can also click the GRAPH button and get a plot of either voltage and current or resistance and reactance along the cable. Note that these will only be useful if we have started with actual impedance, rather than SWR.

Pushing the TUNER button results in a page asking you to select some specifications for your tuner parts. TLW effectively designs a tuner of the type you asked for at the shack end of the cable. It also calculates the power lost in the tuner and gives a summary of the transmitted and lost power in watts, so you don't need to calculate it!

When you've finished, be sure to hit the EXIT button, don't just close the window. Otherwise TLW may not start properly the next time you want to use it.

Review Questions

9-1 What parameters make a difference in the matched loss of transmission line, mismatched loss?

9-2 Why is it important to know the SWR at the load, rather than at the transmitter to determine transmission line loss?

9-3 Does coaxial cable or parallel line transmission line tend to have the lowest matched loss?

Chapter 10

Balanced vs Unbalanced Lines



View of three popular types of balanced line. On far left, TV type 300 Ω twinlead, nominal 450 Ω "window" line and 600 Ω open-wire line.

Contents

What's the Story About Balanced Line? 10-2

The Benefits of Balanced Line 10-3

The Downside of Balanced Line 10-4

What About Unbalanced Currents on Coax? 10-4

What Happens If I Feed my Dipole Directly with Coax? 10-5

Review Questions 10-6

The careful observer might have noted that in Figure 7-3, in Chapter 7, the lowest loss line was not the fancy, expensive "hardline" coax, but rather the much less expensive balanced open-wire and window line. This is a hard combination to beat — low cost and low attenuation, which explains its popularity. The other side of the coin is that most current radio equipment is designed to operate with unbalanced coaxial line.

What's the Story About Balanced Line?

Before we can go too far, we need to discuss what we mean by balanced and unbalanced. By a balanced system, we mean one in which the two sides are at the same impedance above ground. For example feeding the non ground end of two 100 Ω resistors (see **Figure 10-1**) that have the other end grounded will result in a balanced 200 Ω system. In such a case the voltage on each side will be the same magnitude but 180° out of phase. The magnitude of the currents on each side will also be the same since the voltages and resistances are equal.

Note that the system would be balanced whether or not the ground connection were there. No current flows in the ground lead of the perfectly balanced system, so it could be removed without changing the operational properties. **Figure 10-2** shows two examples of inherently balanced


QS0903-Doc03
100 Ω
100 Ω
I_1
I_2
$|I_1| = |I_2|$
$|V_1| = |V_2|$
V_1
V_2

Figure 10-1 — Perfectly balanced load, both the current and voltage on each side will be in balance.


Ground
Plane
Unbalanced
Transmission
Line
ARRL0636

Figure 10-3 — Unbalanced resistive load. The signal is applied with reference to ground.


Boom at Center
λ/2 Dipole
(A)
Delta Match
Balanced Line to
Transition and Radio
λ/2 Dipole
(B)
Balanced Line to
Transition and Radio
ARRL0635

Figure 10-2 — Two examples of inherently balanced antennas, one (delta matched dipole) with a central ground (A) and one (split dipole) without (B).


Boom at Center
(A)
Gamma Match
Coax Cable
to Radio
(B)
Artificial or Real Ground
Coax Cable
to Radio
ARRL0637

Figure 10-4 — Two examples of inherently unbalanced antennas, a gamma matched dipole at (A) and a vertical monopole at (B).

antennas, one with a central ground (A) and one without (B). The ground in the first is not actually necessary, but can be beneficial for lightning protection purposes. For both cases, we note that some kind of transition is required to shift to an unbalanced system for connection to the radio. The types of transition will be the subject of the next chapter.

An unbalanced system, on the other hand, is fed with respect to ground. That is, one side of the load is at ground potential. **Figure 10-3** is an example of an unbalanced resistive load, and **Figure 10-4** is shows two antennas with inherently unbalanced feed points.

The Benefits of Balanced Line

As noted earlier, balanced line has two primary benefits in comparison to coaxial cable. Most balanced lines, especially those with large portions of air dielectric, such as window line or ladder line, have a significantly lower matched loss than most coaxial cables. Even though their characteristic impedance is often higher than desired for many antenna systems, the total of matched and mismatched loss is generally much less than the loss of coax — particularly if the coax is not well matched to the impedance of the load.

Balanced line is often very conveniently connected to balanced antennas and is most often encountered in that application. It is also frequently found in very long runs from unbalanced antennas in which the losses (or cost) of coax would be prohibitive. In that case, it may be worth the effort to transition (Chapter 11) from unbalanced to balanced near the antenna and then back at the radio end.



Figure 10-5 — One method of making homemade low loss open wire line. By putting the line in slots and securing with tie wires, sliding the insulators the length of the line can be avoided.

Most balanced line is relatively inexpensive when compared to coax — often an important consideration. Excellent homemade open wire line can be fabricated at low cost from two rolls of wire (stranded works best, in my experience, particularly if subject to flexing) and insulators made from inexpensive household PVC tubing. **Figure 10-5** shows one technique.

The Downsides of Balanced Line

As with most aspects of life, there are downsides of balanced line as well as benefits. While coax cable, with its fields contained within the shield, can be rolled, buried (if it has a direct burial rating) or installed within or near pipes without impacting performance, this is not true of balanced line. With balanced line, the fields conveying the signal down the line are significant not only between the wires but outside as well for a distance of a few times the wire spacing. This means that balanced line can't be placed on the ground, run in metal ducts, run through lossey material or rolled up, without causing additional loss.

While fields at a distance from balanced line are small, nearby fields can cause interference to other systems, particularly those interconnected by wiring. In addition, on receive, balanced line can pick up interfering signals from computers and other systems if run too close to them.

Another potential issue, particularly with the twinlead or window line variants of balanced line is a change in characteristics when wet. Rainwater can accumulate on the web material between the conductors resulting in a change to the dielectric properties of the line.[1]

There are a few things that can be done if this is a problem:

- Some have been known to carefully cut away some of the web to reduce the water collection surface. To avoid weakening the line, don't cut into the wire if you try this.
- In the "old days," some amateurs waxed their twinlead. This was reputed to cause the water to bead up and run off. Remaining water would be concentrated in droplets leaving most of the dielectric clear. I haven't seen any data on how effective this actually is, nor have I heard of any modern amateurs having the patience to actually do it!

In many cases, these potential problems can be largely avoided through careful planning and installation design. If not, it is sometimes efficient to make a transition to coax cable for some portion of the transmission line run.

---

[1] B. Allison, WB1GCM, J. Hallas, W1ZR," A Closer Look at Window Transmission Line," *QST*, Nov 2009, pp 66-67.

What About Unbalanced Currents on Coax?

In the above section, it probably sounded as if the fields in coax are completely within the coax, thus avoiding the downsides of parallel or balanced line. That is true for the ideal case of properly terminated coax, however, there are at least three ways in which coax can suffer the same limitations as balanced line in this regard. In all cases, this results in currents on the outside of the shield. I have listed them in order of likelihood and severity, based on my experience.

- The coax is not terminated in a properly unbalanced load. This happens if the coax shield is not connected to a ground reference at the antenna. The result is that the current to the shield splits between the inside and outside of the shield.
- The coax run is coupled to the antenna such that the net coupling is not balanced at the cable. For a center fed antenna, coax should be run perpendicular to the antenna element so the coupling from each side cancels. If not, even with proper termination, there will be currents induced on the outside of the shield. For some antennas, monopoles or off center fed antennas for example, it is almost impossible to avoid such coupling.
- The coax shield itself can be leaky. The shield of most coax is not perfect and some is far from it. The specification sheets often list "percent coverage" indicating how well the shield covers the center conductor. Cables with lower numbers will be leakier than those with higher coverage. The current tends to increase as it is coupled over longer distances.

In many cases, the effects of such currents are small, but be aware that they exist and check them out if strange problems appear. A quick test is to note the antenna tuning or SWR as you run your hand along the cable. With properly installed and isolated coax, the tuning shouldn't change.

What Happens If I Feed my Dipole Directly with Coax?

Many amateurs connect their coax directly to a balanced center fed dipole — center conductor to one side, shield to the other as shown in **Figure 10-6**. This is a topic of some controversy with as many folk swearing that it works fine, as there are those who say it causes problems.

The reason for the disagreement may be that there are actually people who end up in both camps because of the dimensions of their system. Recall that due to skin effect, the currents on the inside of the shield of a coax cable are within a small thickness from the inside wall. Thus the outside of the coax acts like a completely different conductor — it's as if the insulated coax were installed in a pipe that is connected to the shield at the antenna end.



Figure 10-6 — Dipole fed directly with coax. The current on the left side divides between the left side antenna segment and the outside of the coax inversely proportional to the impedances as shown.

If the half wave dipole in Figure 10-6 had a center impedance of 50 Ω, typical for relatively low dipoles, the balanced antenna would act like a 25 Ω load to each connection of the coax, Z_{ANT} in Figure 10-6. The impedance of the outside of the shield at the antenna is a bit less obvious. This impedance depends on the impedance to ground at the bottom of the cable, usually at a ground level and grounded entrance panel, and the length of the cable between the antenna and the ground terminal.

Just as with an antenna wire or transmission line, this impedance varies depending on electrical length. If the ground impedance is low and the length is a multiple of a half wave, the impedance at the top will repeat and also be low. On the other hand, if the length is an odd number of quarter wavelengths, the impedance will reverse and be high. Lengths in between will result in intermediate values of impedance, both resistive and reactive.

If the impedance at the top of the shield is of the same order as the half dipole impedance, the current will divide between the two paths. This can have three effects:

- If the ground at the bottom is not of a very low impedance, RF currents can enter the radio room and cause a number of strange equipment problems such as feedback or transmitter lockup.
- The radiation from the transmission line will distort the antenna pattern, usually adding an omnidirectional vertical component. For a single element antenna, this may not be all bad, since it may tend to fill in the nulls that otherwise would be in some directions. For a directional array, however, such radiation will reduce both forward gain and front-to-back ratio — not good things.
- If the transmission line runs past sensitive electronic systems, fire or intrusion alarm wiring, computers or telephone systems, for example, the radiation may cause harmful interference in either direction.

Note that for a low impedance antenna, such as our dipole and most coax fed antennas, there are a small number of lengths that will result in such problems. With a multiband antenna the possibilities of problems increase directly with the number of bands covered. Thus it is not surprising that many don't think any precautions are necessary. Still, it can't hurt to avoid them, much of the subject of the next chapter.

Review Questions

10-1 Under what conditions is unbalanced transmission line most appropriate for antenna to radio connections?

10-2 Repeat question 10-1 for balanced transmission line.

10-3 Why do some people report problems with balanced antennas connected directly to coax while others observe no difficulties?

Chapter 11

So What's a Balun, an Unun, a Choke?



Two homemade baluns surround a commercial balun. On the left a 1:1 choke balun made of miniature coax, in the center a commercial 9:1 balun designed for 450 Ω systems and on the right a homemade 4:1 (200:50 Ω) balun.

Contents

When are Baluns Necessary? 11-2
What Do We Mean by Balanced to Unbalanced? 11-3
Balun Location 11-4
The Different Balun Configurations 11-5
Selecting Baluns for Use in Your System 11-7
Review Questions 11-8

Baluns are devices that provide a transition between unbalanced and balanced systems, impedance transformation or a combination of both. The name *balun* comes from *BAL*anced to *UN*balanced and each part is pronounced the same way as in the separate words.

Sometimes you will encounter an *unun*. The unun (*UN*balanced to *UN*balanced) provides an interconnection between two unbalanced systems, either to change the system impedance, to force all currents into the inside of a coaxial transmission line or usually both.

A *choke* refers to an inductance that offers a high impedance over a particular frequency range. A choke wound with coaxial cable has its high impedance only to currents on the outside of the coax shield, the inductances of the inner conductors effectively cancel. As we will discuss, such a choke can be used either as a balun or an unun.

When are Baluns Necessary?

We have discussed unbalanced line such as coax cable, balanced line such as twinlead, window or ladder line as well as balanced and unbalanced loads. We should point out that virtually all transmitters or transceivers built since the 1950s are designed to work into an unbalanced load — made evident by the coaxial connector used for the antenna connection.[1]

There are many antennas designed to operate with a coaxial cable connection. These antennas can be connected directly to the radio with coaxial cable if they present the desired load to the transmitter. In this case, no transition is required, the entire system is unbalanced. This system can work well and neither an antenna tuner, nor a balun, is required for proper operation. The one exception occurs if there is coupling from the antenna to the transmission line, resulting in undesired coax shield current in which case a common mode choke is recommended.

What's Wrong with this Picture?

The unbalanced antenna, unbalanced transmission line and unbalanced radio make a simple and straightforward arrangement that is easy to operate. Unfortunately, in many cases, the antenna only provides an appropriate match over a narrow frequency range — often narrower than an amateur band, for example. This has two effects:

- If the SWR at the transmitter reaches a higher value than the transmitter can operate into, it will usually reduce the power output to avoid damage to internal components.
- While the losses for matched coaxial cable can be made acceptable by selecting the proper cable for the frequency and length, the losses generally go up quickly with increasing SWR. As noted previously, this actually makes the SWR at the transmitter look better; however, significant power may be lost (turned into heat) in the cable.

Many amateurs choose instead to use a balanced antenna fed with lower loss balanced line in this case. As will be discussed later, this often makes what would be a single band antenna, if fed with coax, into a multiband antenna. We then are faced with a balanced load and an unbalanced transmitter output connector.

What Happens if We Plug the Balanced Line into our Coax Connector?

While not recommended. you can actually make the connection, if pressed. Arguably, it is not much worse than the previously discussed case of hooking unbalanced coax line to a dipole antenna. In this case, however, the shield side of the transmitter output is connected to ground and a fraction of your output power will flow in that direction radiating within the room instead of towards the desired direction. If the ground is not solid, you can end up with RF on all your equipment, causing various strange and sometimes uncomfortable effects.

---

[1] The shift to the use of coaxial cable happened because coaxial cable became available after WW2 coincidentally with the popularity of broadcast television. Transmitters with shielding, filtering and coaxial RF connections were less likely, if properly designed, to cause interference problems with TV sets.

What do We Mean by Balanced to Unbalanced?

The balun makes the transition from an unbalanced system, such as the transceiver, to a balanced system, such as a balanced transmission line. A balun can be used between a balanced dipole and a coaxial cable to avoid the problem of current being driven down the shield of the coax, or it can be used between the unbalanced transmitter and a balanced line to result in the current going towards the antenna as shown in **Figure 11-1**.

As noted previously, sometimes a balun is also used to transform impedances. For example, in the case of a 50 Ω antenna, a 50 Ω transmitter and the use of low loss 450 Ω transmission line, a balun with a 9:1 impedance transformation ratio allows a straightforward interconnection as shown in **Figures 11-2** and **11-3**.

Of course there is still no such thing as a free lunch. In order to use the low loss balanced line in this configuration, the added loss in each of the two baluns must be considered as part of the equation. Measurements I've taken of commercial HF 9:1 baluns have indicated that losses of about 0.5 dB each should be anticipated. It doesn't usually take too long a run of line before the balun loss is compensated for by the higher loss of the coax. This depends on both length and frequency.



Figure 11-3 — Photo of a model of the system of Figure 11-2 using commercial 9:1 baluns. The twist in the window line is intentional. An occasional twist reduces wind effects and tends to maintain balance in the system if near objects.


Balanced Antenna
Balanced Transmission Line
50 Ω Unbalanced Output Transmitter
Balun
Unbalanced Coax Cable
ARRL0640

Figure 11-1 — A balun inserted between the unbalanced output of a transmitter or transceiver and a balanced antenna system.


Long Run of Low Loss Line
450 Ω Balanced Line
450 Ω Balanced Line
9:1 Balun
9:1 Balun
50 Ω Coax Cable to Transmitter
50 Ω Coax Cable to Antenna
ARRL0641

Figure 11-2 — The use of baluns with a 9:1 impedance transformation ratio makes it easy to use low loss 450 Ω balanced transmission line for long runs.

Balun Location

A balun can be inserted anywhere in a system between a coaxial connection and the balanced load. As shown in **Figures 11-4** and **11-5**, the connection between an unbalanced radio and a balanced dipole can include a balun at either end of the transmission line run. Here we have used a dipole with a *delta match* adjusted to provide a 450 Ω balanced load at the antenna.

While the configurations of Figures 11-4 and 11-5 appear to be equivalent, and both can work well as shown, there are advantages to each:

- The configuration of Figure 11-4, using a long run of 450 Ω balanced line, will usually have less loss than the system in Figure 11-5 due to the characteristics of the transmission line. The difference will depend on the frequency, line length and type of coax. Some representative loss figures are shown in **Table 11-1**.
- Using coaxial cable for the run, as in Figure 11-5, has its own advantages. The principal one is that coax is less fussy about how it is placed than is balanced line. While coax can be run in metal conduit, coiled up and some types can be buried — this is not the case with balanced line. With properly installed coax, the fields are entirely within the coax, making it insensitive to its surroundings. Parallel conductor balanced line, on the other hand, has significant fields between the conductors and extending out to a few times the wire separation in all directions. In order to obtain the benefits of such line, it needs to be spaced that far from metal structures and lossey media.

Note also that it is not necessary to have the run entirely with one type of line. For example, a long aerial run of balanced line can be transitioned to coax near the radio with a short run of coax going through conduit or other balanced line hostile environments.

Table 11-1

Comparison of Transmission Line Losses of Different Lines at Different Frequencies

Line Type	*Matched Loss at Frequency (MHz, dB per 100 feet)*			
Balanced Line	*1*	*10*	*100*	*1000**
300 Ω Transmit Twinlead	0.09	0.3	1.1	3.9
450 Ω Window Line	0.02	0.08	0.3	1.1
600 Ω Open Wire Line	0.02	0.06	0.2	0.75
Coax Cable	*1*	*10*	*100*	*1000*
RG-58	0.37	1.4	5.3	20
RG-213	0.18	0.7	2.5	8.6
LMR-400	0.12	0.39	1.3	4.2

*Spacing may be too wide for efficient operation at this frequency.


λ/2 Delta Matched Dipole
450 Ω Antenna Impedance
Long Run of 450 Ω Balanced Line
9:1 Balun
Short 50 Ω Coax Cable to Transmitter
50 Ω Output Transmitter
ARRL0642

Figure 11-4 — Delta matched 450 Ω dipole fed by low loss 450 Ω balanced line to a 9:1 balun at the transmitter.


λ/2 Delta Matched Dipole
450 Ω Antenna Impedance
9:1 Balun
Long 50 Ω Coax Cable to Transmitter
50 Ω Output Transmitter
ARRL0643

Figure 11-5 — Dipole fed by a 9:1 balun and 50 Ω coaxial cable to the transmitter.

The Different Balun Configurations

There are a number of different balun configurations. They range from simple chokes that force (most of) the current that otherwise would be on the shield of coax to the intended load to more complex devices that combine balanced to unbalanced transitions and impedance transformations in a single device. The following is a summary of the more common types.

Choke Baluns

Choke baluns are found on the coax side of a balanced to unbalanced transition. As noted previously, if a balanced load, such as a dipole antenna, is fed directly by coax, the current on the shield side of the connection will split between the connected half dipole and the outside of the shield in a ratio inversely proportional to the two impedances. The idea of the choke balun is to increase the impedance of the outside of the shield by adding inductance and thus reducing the current that flows down the outside of the shield. If no current were to flow down the shield the current to the each side of the antenna would be the same as if the coax were a balanced line on the antenna side.

Air wound coax loops — The simplest form of choke is just a coil of coaxial cable as shown in **Figure 11-6**. Note that for the so called *differential mode* signal, the desired signal inside the coax, this coil just acts like a few feet of transmission line. The *common mode* signal, any undesired signal on the outside of the coax, sees the effect of the coil inductance.

This configuration has been evaluated at length with results reported in *The ARRL Antenna Book.*[2] An example is a six turns in single layer coil of coax with a diameter of 4.25 inches. This coil will have an impedance ranging from 514 Ω at 14 MHz to 1079 Ω at 29 MHz, very suitable for feeding a dipole or triband Yagi, for example. Such coils are sometimes scramble wound rather than being wound in a single layer. While



Figure 11-7 — Choke balun made by passing multiple turns of coax through a ferrite toroidal core.



Figure 11-6 — Choke balun made from a coil of coax. Such a balun can be effective over about a 2:1 frequency range.



Figure 11-8 — Using multiple single turn "coils" in series — a good solution for large diameter or stiff coax.

---

[2] R. D. Straw, Editor, *The ARRL Antenna Book,* 21st Edition. Available from your ARRL dealer or the ARRL Bookstore, ARRL order no. 9876. Telephone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.org/arrl-store**; **pubsales@arrl.org.**



Figure 11-9 — The bazooka quarter wave choke balun made by providing a shorted line section around the shield of a coax cable.



Figure 11-10 — The ½ wave 4:1 impedance transforming balun.

they can be moderately effective, they usually suffer at higher frequencies due to excessive capacitance between turns. The only other effect of the coax coil is any attenuation due to the additional length of coax, in this case about 7 feet.

Ferrite toroid coils — The effectiveness of a choke coil can be improved by winding it on a ferrite toroidal core, as shown in **Figure 11-7**. The coil can be either a pair of wires wound together around the core or coax cable, either extra thin coax**,** or the type used for the transmission line. A coil of 12 turns of thin coax on a type FT240-61 core makes an effective choke over the range from 1.8 to 30 MHz.

A popular alternate method is to use a number of single turn ferrite "coils" in series as shown in **Figure 11-8**. While this can be effective, it is worth pointing out that the inductance of N such inductors in series equals N times the inductance of a single inductor. On the other hand, the inductance of multiple turns through a single toroid goes up by the square of the number of turns. Still if the coax is thick, or hard to bend tightly, this is a very workable solution. It has the additional advantage that the capacitance between "turns" is less than with a coil, so it will tend to be more effective at higher frequencies.

Ferrite rod coils — Some baluns are wound on sections of ferrite rod rather than the toroid, donut shaped, cores. These can work as well as the toroids, however, the toroids have the advantage that the fields are contained within the core, while the rods have fields between the ends outside the core, making them more fussy about their surroundings. Sometimes the available space will point towards one versus the other. All other things being equal, I prefer the self shielding toroids, if feasible.

Transmission line sections — A quarter wave long section of transmission line, shorted at the far end, has a high impedance at the near end. This property can be used as a choke at the particular frequency that the line section is that length (or odd multiples). This is called a bazooka, due to the use of large concentric structures as shown in **Figure 11-9**. This is a particularly popular arrangement at VHF and higher, since the dimensions are reasonable and wideband properties of the ferrite baluns and chokes are often not required.

Transformer Baluns

The half-wave coax loop — One of the early forms of transforming balun was also made of coax cable, this time an electrical ½ wave long. This cable was formed into a loop with one end on each side of the balanced load as shown in **Figure 11-10**. The unbalanced line was connected to one side of the balanced load.

The half wave loop provides a copy of the signal from the coax feedline delayed by 180°, and thus out of phase. Each of the two signals see an impedance of half of total 300 Ω load, or 150 Ω. Because the impedance on a halfwave (or multiple) of a transmission line repeats itself, the loop will bring the 150 Ω impedance back to the feedline junction. The parallel combination of the two 150 Ω signals at the feedline junction is thus ¼ of the total load or 75 Ω. Note that since a half wave length of transmission line repeats whatever impedance is there, this will transform any impedance to ¼ the value on the single frequency.

The half-wave loop transforming balun is very efficient, with the only loss or imbalance a result of the loss in the loop of coax. A disadvantage is that they only operate on (or close to) the frequency at which the loop is ½ wave (or multiples) long. These are frequently used to feed VHF and UHF Yagis that operate on a narrow band of frequencies making the narrow bandwidth irrelevant.

Ferrite transformers — Broadband



Figure 11-11 — Schematic and pictorial view of a broadband ferrite core 4:1 impedance transforming balun.

baluns can be made using the same kind of ferrite structures described previously as transformers. They frequently are made with multiple windings that can be connected in series or parallel to provide multiple transformation ratios. The 4:1 balun shown in **Figure 11-11** is an example of such a balun that functions similarly to the ½ wave coax loop balun.

Current and Voltage Baluns — Depending on the details of their design, a balun can be made to force either the current *or* the voltage on the balanced side to equal each other. Note that in a perfectly balanced load, in which each side has the same impedance to ground, if the voltages are equal so will be the currents and vice versa.

Unfortunately, in our real world, often an intended balanced load, isn't quite. For example, an otherwise balanced antenna may become unbalanced if one side is closer to the ground, or to a metal structure, than the other. If the balun is intended, as most are, to keep currents off the outside of coax shields, then by forcing the currents to be equal your objective is most likely to be met.

Selecting Baluns for Use in Your System

Within the constraints listed above, any of the general type of baluns described can be selected for use. Most baluns have a specified input and output impedance and power rating. These should be matched to your application. The transformation ratio does not apply for any impedance, rather for the design center of the balun. For example a 4:1 balun designed to transform a 200 Ω balanced load to 50 Ω coax, can not counted on to provide a 4:1 transformation to a 2000 Ω balanced load.

In practice, the transformation is likely to be close to the specified ratio for perhaps a 4:1 mismatch — in the previous case that would be from 50 to 800 Ω. Outside of that range, they may continue to function as a balun, however, the transformation ratio will be different and the losses will tend to increase.

A mismatch will also increase the stress on the balun. The current or the voltage will be higher by the square root of the SWR or mismatch ratio and thus the ratings should be increased appropriately. After use (with power off) a good check at a 100 W or higher power station is to put a finger on the balun to check the temperature. Any increase above ambient is cause for reconsideration.

Review Questions

11-1 Provide three reasons for using a balun.

11-2 What are the relative advantages of having a balun at a balanced antenna feed point versus having a long run of balanced line to a balun near the transmitter?

11-3 What are the consequences of operating a balun at an impedance far from its design point?

Chapter 12

Balanced Antenna Tuners

Johnson Viking
MATCHBOX
TUNING
MATCHING

A classic 275 W E. F. Johnson "Matchbox" balanced antenna tuner from the 1950s. Still a viable tuner useful to 750 W PEP and available at hamfests and auction sites. A 1 kW model, useful above the US legal limit, was also offered.

Contents

What's a Balanced Tuner? 12-2

A Balanced Tuner versus an Unbalanced Tuner with a Balun 12-3

Another Possibility — The "Hot" Tuner 12-4

Review Questions.. 12-5

We've been talking about antenna tuners and balanced line in the same sentence, even though we haven't addressed the issue of the kind of tuners to use with a balanced load. Now it's time.

What's a Balanced Tuner?

While we haven't specifically addressed the question, the tuners we've been talking about so far have been really what could be called *unbalanced* tuners. You can usually spot an unbalanced tuner by its input and output connector arrangements. In some cases, they have a coax connector for unbalanced cable on both the radio and antenna system sides. Other unbalanced tuners have a coax connector for the radio side and a single terminal intended for a wire antenna and another for a ground connection.

Some unbalanced tuners have another pair of connectors that are designated for "balanced loads" but the transition occurs after the tuner function using an internal balun. While these can be useful for driving balanced loads, as we will discuss, they are really two distinct pieces, an unbalanced tuner followed by a balun.

Enter a Truly Balanced Tuner

The tuner configurations shown in Figure 3-3, in Chapter 3, are all inherently unbalanced since ground is on one side of each. Any of them can be converted to a balanced configuration by essentially providing a mirror image on the other side of ground. The configurations of Figure 3-3 are shown in balanced form in **Figure 12-1**. A quick look at the figure will indicate that we now have something we probably didn't want — a balanced to balanced tuner!

The one configuration that can be easily transformed to a balanced to unbalanced tuner is the tuned transformer in Figure 12-1 (A). This is because the transformer coupling to the radio (left) side of the transformer does not maintain the same ground reference. Thus one side of the primary (left) winding can be grounded resulting in an unbalanced connection. This is exactly what the 1950s era Johnson Matchbox did, perhaps explaining why it is still in demand today.

Unbalancing One Side

The other configurations in Figure 12-1 require a balun on the 50 Ω side to fit into coaxial fed systems. While this may seem about the same as putting the balun on the antenna side of the tuner (more in next section), the difference here is that we transform the widely variable balanced antenna system impedance on the right side to a 50 Ω balanced load on the left in Figure 12-1. We then can use a 1:1 50 Ω balun to transform to unbalanced for coax connectivity. Alternately, some tuners are designed to transform to a 200 Ω balanced load, to be followed by a 4:1 balun for connectivity to 50 Ω coax.

In either the 1:1 or 4:1 case, we have the advantage that the baluns are operating at their design impedance. They will offer minimum loss and will operate with their expected transformation ratios.

There's Always a Price

A possible downside of the balanced antenna tuner designs is that the nature of the beast requires significantly more — but not quite twice — as many components as the same unbalanced configuration. The usual antenna tuner components, for medium to high power tuners, are both large and pricy. This results in ramifications in terms of both cost and size. There is, after all, still no such thing as a free lunch.



(A) Balanced Tuned Variable Transformer

(D) Balanced π-network

(E) Balanced High-pass T-network

(B) L-network for $Z < Z_0$

(C) L-network for $Z > Z_0$

(F) Balanced Low-pass T-network

Figure 12-1 — Configurations of balanced antenna tuner versions of the unbalanced tuners in Figure 3-3, in Chapter 3.

A Balanced Tuner versus an Unbalanced Tuner with a Balun

As you look over the features of commercial antenna tuners, you will see many with "balanced outputs." In most cases, these are inherently unbalanced tuners, with a balun on the antenna side to transform to a balanced load. Many people, including your humble servant, have been happily using such tuners for years — so what's the problem?

Well, the simple answer is — there may not be a problem! If the impedance at the bottom of your balanced feed line (generally quite different from either the antenna impedance or the transmission line characteristic impedance, if the line is not matched to the antenna) can transform to an unbalanced impedance through the balun without difficulty — there is no problem — you're done!

On the other hand, if the impedance at the balun is very different from its design point, you may have a number of problems, most significantly loss in the balun. While balun loss is not great in its own right — toroid cores are not very good heat radiators. Any balun loss will transform itself into heat and may destroy the balun's ferrite core in the process.

The Good News Is

While there are exceptions, many unbalanced tuners, including those with a balun for balanced loads, offer additional features compared to many "balanced" tuners. My fairly typical unbalanced L-network tuner, for example, has three outputs for unbalanced coax terminations and a fourth that can either be coax or balanced, using an internal 4:1 balun on the output side. In addition to my main balanced multiband antenna, I have a few other antennas that are fed by coax. Thus the tuner provides a convenient point for them all to come together with easy switching between them. With a single switch on the tuner, I can instantly select any of the four antennas — either through the tuner, or bypassing the tuner, if they are matched systems. Most balanced tuners just provide a connection to a single balanced antenna system.

In terms of keeping common mode RF currents out of your station, it really doesn't matter which side of the tuner has the balun — its choking impedance has the same effect.

If it Doesn't Play

If an unbalanced tuner with a balun doesn't work well with your antenna system on a particular band, you may be able to recover. The fact that it doesn't tune usually means that the balanced line has a high SWR (if it were matched, to say 450 Ω, the tuner and balun combination could probably handle it without difficulty). Because of the nature of the mismatched line, changing the length will have a profound effect on the impedance as seen by the tuner. Try inserting about ⅛ wavelength of line and see what happens. Be sure to observe the usual cautions about balanced line — such as not coiling it up.

Another Possibility — The "Hot" Tuner

Impedance transformation through an unbalanced tuner will not "know" it is unbalanced unless one side of the tuner is grounded. Thus it is quite possible to use an inherently unbalanced tuner into a balanced load if it is isolated from ground. This can be accomplished as shown in **Figure 12-2** for a remote automatic tuner.

The configuration in **Figure 12-3** makes this quite convenient, however, it can also be accomplished using a manual tuner in the station. The difficulty with the tuner in the station is that it generally is designed so that the cabinet is at what it thinks is "ground" potential. If it is isolated from ground, the whole cabinet is at the potential of half the RF voltage feeding the antenna. This can be uncomfortable for the operator, unless she uses oven mitts to make adjustments. An unsuspecting cat can get quite a curl as it passes by during a transmission!


Grounded Outer Chassis/Cabinet
Inner Chassis Insulated from Grounded Outer Cabinet
50 Ω Output Transmitter
50 Ω Choke Balun
Insulated Unbalanced Antenna Tuner
"Antenna"
Balanced Antenna Output
"Ground" (to ~~Inner~~ OUTER Chassis only)
Insulated Control Shafts
ARRL0646

Figure 12-3 — Manually tuned version of an unbalanced tuner isolated from ground driving a balanced load. Note the insulated additional layer of cabinetry.

The hot chassis problem has been solved by at least one published design in which what would be the cabinet is insulated from and inside an additional cabinet with insulated shaft extensions on the controls as shown in **Figure 12-3**. I'm not aware that this has been offered as a commercial product, however, it is feasible — if not simple to implement.


HF Transceiver
8.8.8.8.8.8
Coax
Control
Lightning Arrestor
Multiple Turns on Ferrite Core
Remote Antenna Tuner
Dipole
ARRL0598

Figure 12-2 — Unbalanced tuner isolated from ground driving a balanced load. The common mode choke on the radio side maintains the balance on the antenna side. Note that it is necessary to provide a choke on all ~~balun~~ REMOTE TUNER connections, as shown, in order to elevate the whole tuner above RF ground.

Review Questions

12-1 Why might an inherently balanced tuner be a good idea?

12-2 What difference does it make whether a balun is on the input or output of an antenna tuner?

12-3 What kind of problems might you have using an unbalanced tuner with a balanced load?

Chapter 13

Antennas That Work Well with Antenna Tuners


130 Feet
ARRL0648
450 or 600 Ω
Balanced Line
50 Ω
Coax
Antenna
Tuner
HF
Transceiver
3923.0000
Lightning
Arrestor
Station Earth
Ground

The center-fed Zepp is a very popular antenna with those having a wide-range antenna tuner.

Contents

The Coax Fed Dipole.. 13-2
Tuned Yagi Arrays.. 13-3
Single Wire Fed Antennas.. 13-4
The Vertical Monopole... 13-5
Balanced Antenna Systems.. 13-7
Mobile Antenna Systems.. 13-8
Review Questions.. 13-10

There's no magic antenna that goes well with a tuner — in fact, virtually any antenna can benefit from a tuner under some circumstances. Here we will discuss how a tuner can increase the flexibility and usefulness of some popular antennas.

The Coax Fed Dipole

In Chapter 2, we discussed the nominally matched dipole and the limitations on its bandwidth within a given SWR. For example, to have a single low 80 meter dipole be useful across the entire band, we may need to deal with an SWR as high as a 10:1 as shown in Figure 2-7, in Chapter 2, although at many heights, the SWR will not rise beyond 5 or 6:1 at band edges. Most other examples shown in Chapter 2 have more reasonable SWR characteristics. Still, in many cases an SWR higher than 2:1 may be encountered, requiring an antenna tuner to permit proper transmitter operation at band edges.

A Dipole Operated on an Odd Harmonic

A special case of the dipole is one used on its third harmonic. A very popular amateur antenna is a 40 meter (7 to 7.3 MHz in the US) dipole also operated on 15 meters (21 to 21.450 MHz). This is often stated as if it were a straightforward arrangement, however, it is just a bit more difficult to achieve than would be implied by some. A tuner makes it much easier. The difficulties arise particularly due to two factors:

- The nominal impedance of a ¾ λ dipole in free space is about 110 Ω, rather than 72 Ω for a λ/2 dipole. While the actual impedance will vary above and below this number, depending on height above ground, this often gives us a higher SWR than 2:1 to start with.
- The third harmonic of 7.15 MHz, the center of the 40 meter band, is 21.45 MHz, the very top of the 15 meter band.

Figure 13-1 shows the modeled SWR of a wire 40 meter dipole cut for mid band at a height of 40 feet. **Figure 13-2** shows the SWR of the same antenna operated on 15 meters. Obviously, this isn't going to work out as well as some folks hypothesize.

Many wide range tuners could compensate for the SWR at the transmitter. As discussed in Chapter 7, however, the losses in a coax cable with a 10:1 SWR at 21 MHz may result in more loss than can generally be tolerated, although it certainly could be used in a pinch. Because the losses in mismatched coax are less at lower frequencies, the concept can be salvaged by optimizing the dipole as a 15 meter ¾ λ dipole with the results shown in **Figures 13-3** and **13-4**.

Note that the lengthened antenna has an SWR of less than 3:1 across all of 15 meters, significantly reducing the transmission line loss associated with Figure 13-2. While the SWR on 40 meters is no longer delightful, it is reasonable from a transmission line loss standpoint. The resulting antenna can work well with some nominal "3:1" SWR tuners that work beyond



```
Freq        7 MHz                          Source #  1
SWR         2.06                           Z0        50 ohms
Z           82.24 - j 34.51 ohms
Refl Coeff  0.3456 at -32.32 deg.
```

Figure 13-1 — 50 Ω SWR of a 40 meter dipole at 40 feet cut for mid band.



```
Freq        21.2 MHz                       Source #  1
SWR         6.69                           Z0        50 ohms
Z           97.11 - j 145.9 ohms
Refl Coeff  0.74 at -27.34 deg.
```

Figure 13-2 — SWR of the 40 meter dipole of Figure 13-1 across 15 meters.



Z0
● 50 ohms
○ Alt (88 ohms)

1 Source #

Freq 21.2 MHz
SWR 2.18
Z 107.5 - j 11.22 ohms
Refl Coeff 0.3708 at -6.97 deg.
Source # 1
Z0 50 ohms

Figure 13-3 — SWR of the 40 meter dipole of Figure 13-1 lengthened to be optimized for 15 meters across 15 the 15 meter band.



Z0
● 50 ohms
○ Alt (88 ohms)

1 Source #

Freq 7 MHz
SWR 1.87
Z 90.09 + j 14.68 ohms
Refl Coeff 0.3031 at 14.13 deg.
Source # 1
Z0 50 ohms

Figure 13-4 — SWR of the lengthened (15 meter optimized) 40 meter dipole of Figure 13-3 across 40 meters.

their specs, and is an easy job for wider range tuners.

Dipoles Can Benefit

The preceding examples illustrate ways in which a simple dipole can benefit from an antenna tuner. For any dipole, the tuner can compensate for imperfect length adjustment, often a convenience. The one caution is that even if the tuner can match the resulting impedance, the loss in the mismatched transmission line between the tuner and the antenna can be an issue, even if all seems well at the transmitter. Take another look at Chapter 7.

Tuned Yagi Arrays

We often think of the popular HF Yagi beam antenna as one that is fed directly with 50 Ω coax with low SWR and without any need for a tuner. This is certainly the sense one gets from the specification sheet, yet some highly tuned Yagis, particularly those operating on multiple bands, have trouble providing a close match from band edge to band edge, particularly if optimized for the CW or SSB segment. In most cases, even though the SWR may be marginal at the far edge, there is still beneficial gain and front to back ratio. This is exactly the place for a limited range internal tuner to be applied, since the SWR is often less than 3:1. My sense is this is what they had in mind when these 3:1 tuners were designed — compensating for the just out of tune coax fed dipole or Yagi.

Single Wire Fed Antennas

There are a number of antennas that are designed to be fed as a single wire, without any transmission line. Some are field expedients, however, others are well thought out designs that can offer excellent performance.

Single Wire Antennas

Single wire antennas go back to the very beginning of amateur radio — the days before anyone thought of a transmission line. The most commonly used transmitting antenna in the early days was a short vertical (we're talking below 200 meters, so everything was short!) with top capacitance loading of multiple horizontal wires. They were used on shipboard, shore and ham stations alike, and worked well enough to get the signals through.

These days, a "random length" single wire is often used as an easy to deploy temporary antenna or, for some, using very thin wire, as an unnoticeable stealthy antenna if neighbors or deed restrictions object to "antennas." They can be effective, especially if fed against a good ground system, and if they are at least λ/4 long at the lowest frequency. Such a λ/4 wire fed against ground even has a name! This is called a Marconi antenna, and yes. it dates back more than a century.

Random wire antennas will still work if shorter, but ground losses rapidly reduce efficiency as lengths get much shorter than λ/4.

The success of such single wiere antennas depends on all the usual factors including height, length, and ground conditions all played against desired frequency and geographical coverage. With a ground mounted radio and a higher wire antenna, there will always be some vertically and often horizontally polarized radiation as well. The combination can provide a useful mix of coverage, although the coverage in any direction will not be as good as that of an antenna designed for the job.

The key element in making such an antenna play is a wide range antenna tuner that can match the widely variable load of the single wire on multiple bands to the 50 Ω that modern radios require. So we have a place here for the antenna tuner, the question is "which place."

Antenna Tuner at the Shack — This can work and has been done, but in the most successful implementations, the antenna tuner is near the boundary between indoors and out. In some stations, that boundary is within or at the edge of the shack eliminating the distinction.

A portion of a radiating antenna inside a building is generally asking for some kind of trouble. First there is the RF safety issue as applied to any people inside the structure. Even if your transmit power level does not require a formal assessment, you are not released from the requirement to not expose people to excessive levels of RF. Second, your indoor receiving antenna will pick up electrical noise from other equipment in the building. Third, if the building contains any sensitive electronic systems, your signal has a good chance of causing trouble, such as setting off fire alarms, or getting in to a television receiver while a spouse is watching an important show. In any case, any radiation that occurs within the building structure is not likely to help you get your signal where you want it.

None of this is to suggest that indoor antennas can't be used, however all of the above issues need to be considered. Here we are talking about an antenna that is partly inside a building, and partly outside. The point is that having as much as possible outside is generally a better solution.

Antenna Tuner at the Antenna — The antenna tuner can also be located at the antenna, if it's remotely tuned or sometimes remotely switched. Some remote tuners are waterproof, while others will need a waterproof enclosure to make them last. With the tuner at or near the antenna feed point, matched coax can run from the tuner back to the station, as discussed previously. By running the coax from the station out to the antenna feed point, the issues of radiation within the building can be largely avoided.

This is the configuration used for

Table 13-1

Random Wire Antenna Lengths that Should be Avoided Due to Resonance and High Impedance.

Band (Meters)	*0.5 λ*	*1 λ*	*1.5 λ*	*2 λ*	*2.5 λ*	*3 λ*
160	234 to 260	468 to 520	702 to 780	936 to 1040	1170.0 to 1300.0	1404.0 to 1560.0
80	117.0 to 133.7	234.0 to 267.4	351.0 to 401.1	468.0 to 534.9	585.0 to 668.6	702.0 to 802.3
40	64.1 to 66.9	128.2 to 133.7	192.3 to 200.6	256.4 to 267.4	320.5 to 334.3	384.7 to 401.1
30	46.1 to 46.3	92.2 to 92.7	138.3 to 139.0	184.4 to 185.3	230.5 to 231.7	276.7 to 278.0
20	32.6 to 33.4	65.2 to 66.9	97.8 to 100.3	130.5 to 133.7	163.1 to 167.1	195.7 to 200.6
17	25.8 to 25.9	51.5 to 51.8	77.3 to 77.7	103.0 to 103.6	128.8 to 129.5	154.6 to 155.4
15	21.8 to 22.3	43.6 to 44.6	65.5 to 66.9	87.3 to 89.1	109.1 to 111.4	130.9 to 133.7
12	18.7 to 18.8	37.5 to 37.6	56.2 to 56.4	74.9 to 75.2	93.6 to 94.0	112.4 to 112.8
10	15.8 to 16.7	31.5 to 33.4	47.3 to 50.1	63.0 to 66.9	78.8 to 83.6	94.5 to 100.3
6	8.7 to 9.4	17.3 to 18.7	26.0 to 28.1	34.7 to 37.4	43.3 to 46.8	52.0 to 56.2

many marine HF antennas. On a sailboat, the typical HF antenna is an insulated backstay fed by a remote single wire tuner located near the antenna base and fed against the ship ground system, including salt water, if possible.

But Watch Out for Tricky Lengths! — The so called *random length* wire antenna is not really random since any antenna does have a specific length. Such an antenna will work better at some lengths than others, making it best if not entirely random in its installation. The problems most often show up if the length happens to be a multiple of λ/2. At this length, the impedance hits a maximum, often in the 1000 to 2000 Ω range, depending on the usual factors. This results in an SWR of 20 to 40:1, higher than even a wide range tuner promises to deal with.

The impedance gets somewhat lower with each multiple of a λ/2, but may still be a problem. A second concern is that the voltage on the end at the tuner is high. The voltage can be nearly 500 V_{RMS} with a 100 W transmitter. This can stress tuner capacitors as well as pose a safety hazard to unsuspecting people. Instead of the shock experienced by coming in contact with dc or 60 Hz ac, contact with RF results in a painful burn that is usually slow to heal.

While it sounds like it should be an easy task to select a length, the multiplicity of bands without harmonic relationship makes it difficult to find a length that won't be likely a problem on some band. A look at **Table 13-1**, indicating approximate λ/2 resonant lengths for each band, along with multiples, provides a list of lengths to avoid for the amateur bands. There are so few lengths available, that sometimes it makes sense to just try the length that fits the available spot and, if it has problems tuning on a band, add a few feet and try again.

The Vertical Monopole

A popular antenna with those who like to operate long distances on the lower HF and MF bands is a vertical monopole. This can perhaps be considered a special case of the random wire antenna, except that it is generally of specific electrical length — typically λ/4 or ⅝ λ, depending on frequency and available supports. While a λ/4 vertical monopole can usually be fed directly with 50 Ω coax against ground, the other lengths do require matching networks or an antenna tuner for operation with a transmission line. A low impedance ground is a requirement for efficient operation of such antennas.

A 43 foot tall vertical made from wire or tubing is a very popular antenna in some quarters. It is a ⅝ λ long monopole on 20 meters and thus provides the optimum low angle radiation from a single vertical radiator (see **Figure 13-5**), yet can provide excellent low angle performance on 40 meters where it is somewhat longer than λ/4, as well as on 80 meters where it is somewhat less than λ/4, but generally a manageable height. All the lengths share a complex feed point impedance that responds nicely to a remote tuner at the base, although at these frequencies, a short run of high quality coax may have sufficiently low in loss to be suitable for use with a tuner at the station.



Figure 13-5 — Vertical radiation patterns of a 43 foot, ⅝ λ, vertical on 20 meters (solid) compared to a ¼ λ monopole. Note the increased radiation at low elevation angles.

THE DOTTED PATTERN IS FOR THE 1/4 λ MONOPOLE.

Inverted L

A popular variant of the vertical monopole, particularly on the lower frequency bands, is the inverted L. A λ/4 monopole for 160 meters, for example, needs to be around 130 feet long — a bit of a stretch for most as a vertical arrangement. The inverted L is obtained by taking the same length of wire and going as high as feasible, then bending the remainder horizontally. The antenna has the appearance of an upside down letter L — hence its name.

The lower (vertical) portion has the highest current and will thus provide low angle radiation very similar to that of a full sized monopole. At the λ/4 frequency, the inverted L can often be fed directly by 50 Ω coax with a reasonable SWR. An additional advantage of this arrangement, if fed with a wide range tuner at its base, is that it will provide low angle vertically polarized radiation at higher frequencies up to the frequency at which the vertical portion is just longer than ⅝ λ. Note the earlier concerns about feeding an antenna that is a multiple of λ/2, and if multiband operation is in the plan, make the inverted L longer than λ/4 on the lowest band.

The Bobtail Curtain

An interesting, inexpensive and surprisingly effective directional array called the Bobtail Curtain is composed of three λ/4 vertical elements fed in phase and driven from the single wire center element as shown



Figure 13-6 — The Bobtail Curtain three element vertical phased array fed by a single wire.



Figure 13-7 — Azimuth pattern of a Bobtail Curtain array at 10° elevation. Note the high gain over 60° on each side, broadside to the array.



Figure 13-8 — Elevation pattern of a Bobtail Curtain array (solid) compared to a full wave center fed antenna on the same supports (dashed). Note the superior low angle coverage.


ARRL0650
132 feet
42.5 feet
Single Wire Transmission Line
Unbalanced Antenna Tuner
Common Mode Choke
HF Transceiver 80, 40, 20 and 10 meters

Figure 13-9 — Single wire fed Windom antenna configuration for 80, 40, 20 and 10 meters.

in **Figure 13-6**.[1] This antenna is composed of just four pieces of wire, yet provides significant gain in two fixed directions as shown in **Figure 13-7**. The low angle gain of this antenna favors long distance communication (see **Figure 13-8**) and is higher than that of horizontal antennas of the same height.

The Bobtail Curtain can be fed by a single wire tuner located at the source shown in Figure 13-6, although the impedance is quite high, as discussed in the previous section. Making the middle wire a few feet longer may make it usable with most wide range tuners. The antenna can be used on other bands as a kind of top loaded monopole, although the results will not be in the same league as those at its design frequency.

Single Wire Fed Windom

An unbroken half wave antenna off-center fed by a single wire was quite a popular multiband radiator in the 1930s, following publication of a note by Windom in *QST*.[2] The Windom antenna, as shown in **Figure 13-9,** with a fundamental frequency in the lower portion of 80 meters, was said to operate equally well on 40, 20 and 10 meters, thus covering all the amateur HF bands of the day.

There is some controversy over just how well this antenna works as a horizontal antenna; however, there is no question that it can work. Figure 13-9 shows a choke or current balun in the coax from the tuner to the radio, since there will likely be significant common mode current that should be kept out of the radio room.

---

[1] For more about the Bobtail Curtain array, see J. Hallas, W1ZR, *Basic Antennas — Understanding Practical Antennas and Designs,* Chapter 15. Available from your ARRL dealer or the ARRL Bookstore, ARRL order no. 9994. Telephone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.org/shop/**; **pubsales@arrl.org**.

[2] L. Windom, W8GZ, "Notes on Ethereal Adornments," *QST*, Sep 1929, pp 19-22, 84.

Balanced Antenna Systems

For many amateurs, the antenna tuner really earns its keep by matching balanced systems for multiple bands. The classic system is one that is often called a center-fed Zepp, although there are some who suggest it really should have different names on different bands.

The Center-Fed Zepp

This antenna is actually a half-wave dipole if fed on its lowest band. The difference between it and the usual dipole is that it is fed with low-loss balanced transmission line, such as open wire line or window type line. Since it doesn't really need to be resonant to work well, and thus can be almost any length, a more accurate name might be the *not always resonant tuned feeder dipole.* Still more folk will know what you mean if you call it a center-fed Zepp (CFZ). The configuration is shown in **Figure 13-10**.



Figure 13-10 — Traditional center-fed Zepp antenna. With the length shown, the antenna will work well from 80 through 6 meters, and may even tune on 160 meters. The antenna length is not critical, however, it works best if close to $\lambda/2$ on the lowest operating frequency as described in the text.

For the case in which it is resonant at its half wave frequency, the radiation pattern is the same as any half-wave dipole at the same height. The difference is that the SWR on the transmission line will be in the range of 4:1 to 10:1 depending on the height of the antenna and the transmission line type. While the loss with this kind of mismatch would be a problem with coax, it isn't with low loss line. Including the loss due to mismatch, the total loss is comparable or even less than most matched coax situations at the same frequency.

The antenna can easily be fed with a wide range antenna tuner, preferably a balanced antenna tuner, but usually also with an unbalanced tuner equipped with a balun. The antenna will work very well on higher bands — into the VHF range. There may be some lengths of transmission line that will result in an impedance that the tuner can deal with on all bands.

The antenna patterns become fairly complex at higher frequencies. For resonant antennas, there are generally 2 × N main lobes where N is the number of full wavelengths.

As mentioned, the antenna has no particular need to be resonant anywhere to work well. The impedance is easier to match if the antenna is at least a half wave long at its lowest frequency, but there is nothing magic about that length. I use a 100 foot long dipole, center fed with 450 Ω window line quite successfully on all bands from 80 through 6 meters, for example.

Another popular length is 86 feet. This provides the optimum gain on 20 meters in single lobes in each direction perpendicular to the wire. While the lobes are sharp compared to a dipole, 35.6° on either side compared to 83°, the gain at the peak is more than 3 dB higher than a dipole.



Figure 13-11 — End-fed Zepp antenna for 40, 20, 15 and 10 meters. This works as a horizontal antenna if the length is a multiple of $\lambda/2$ on each frequency used. On other frequencies the feed line will also radiate, usually with vertical polarization, and precautions must be taken to keep common mode currents from the radio equipment. Lightning arrestor not shown.

This length will usually be useable from 80 meters through the higher frequency bands, although some transmission line lengths may have problems with some wide range tuners on 80 meters.

If there are problems matching particular impedances, usually an extra 10 feet or so of the transmission line will change the impedance enough to make the match possible. Be sure to check the other bands to make sure you haven't just moved the problem around. Usually a length can be found that will work on all bands. Be sure to avoid coiling up the excess balanced line. Always keep it off the ground and away from metal — at least three or four times the distance between the conductors.

The End-Fed Zepp

A half wave antenna fed on the end with a λ/4 matching section of low loss balanced line is called an end-fed Zepp. This is often a convenient antenna if the station is close to a property boundary, making a center-fed antenna a difficult proposition. The matching section transforms the high impedance on the end, typically close to 2000 Ω, to a relatively low impedance that can be fed by a transmitter, or a narrow range tuner. This is the original Zeppelin antenna that was deployed beneath the aircraft's gondola. It is also popular as a VHF vertical called a "J-antenna."

Some have had better results by providing a λ/10 or so of wire as a counterpoise on the other side of the transmission line, particularly if using it on multiple bands. On bands at which the antenna is a multiple of λ/2, it provides mostly horizontal polarization with minimal common mode current on the transmission line. It can be made to work on bands at which it is not resonant, however, there will be a pronounced lack of balance on the transmission line.

While the λ/4 matching section is a key part of the original Zepp design, it is not necessary if a wide range antenna tuner is provided to perform the matching as shown in **Figure 13-11**.

The unbalanced line currents result in two effects.

- First, the line will radiate. This may not be a terrible thing, if the line is in the clear, but can cause problems if it is running near other equipment.
- Second, the line will bring common mode current into the station. This can usually be addressed through a common mode choke at the point at which a transition to coax is made. Make sure the coax run is short, since the mismatch will result in much higher losses in coax.

Mobile Antenna Systems

Antennas used in vehicles operate under the same principles as antennas in other applications, however, they often provide unique challenges. Antennas for MF and the lower portion of the HF region must be shortened considerably in order to be practical on most motor vehicles, large ships are a notable exception. In addition, unlike the usual antenna environment, these antennas are usually quite close to both the radio equipment as well as the vehicle body. With the exception of aircraft antennas, most mobile antennas are also quite close to the ground.

While none of the above differences by itself results in major problems, they all lead to certain limitations in



Figure 13-12 — Typical vehicle mounted monopole for the lower HF range. Because of practical limitations to do with garages, tunnels and trees, lengths tend to be 8 feet or less, from about ⅛ to 1⁄32 wavelength. The center loading shown improves efficiency.

antenna design and performance.

HF Mobile Antennas on Land Vehicles

The lower HF bands, especially 80, 40 and 20 meters, are popular with mobile operators. Depending on the sunspots and time of day, one or more can usually be counted on for reliable medium to long range communication. The usual antenna is a relatively short monopole antenna mounted on, and fed against, the vehicle body as shown in **Figure 13-12**.

As in the antenna in Figure 13-12, center loading is often used because it results in higher current in the lower section and thus less loss, although base loading, or even just using a solid whip with a tuner at the base are often encountered. A limitation of such an antenna is its SWR bandwidth, a typical case shown in **Figure 13-13** — much narrower than a full size antenna.



Figure 13-13 — Typical SWR plot of a mobile antenna of the type shown in Figure 13-12. The 2:1 SWR bandwidth is likely to range from 20 to 50 kHz, with antennas having less efficiency tending to have wider bandwidth.

This makes the shortened mobile antenna a good candidate for a wide range antenna tuner. The tuner can be used to allow full band coverage to be obtained. I have even used a tuner to allow a 40 meter mobile whip to be used on 80 meters, although it is not as efficient as the center loaded 80 meter arrangement.

HF Mobile Antennas on Other Vehicles

Those using HF on boats or aircraft do not generally share the same size restrictions as on land vehicles. Often either will use a convenient length of wire, for example the insulated backstay on a sailboat, or a wire from a short mast to a handy surface on an aircraft, to form an antenna similar to the random wire described earlier. This is almost always accompanied by a remote, usually automatic, antenna tuner very near one end or the other of the wire. This system can work very well if fed against the aircraft body or a metal hull. On my fiberglass sailboat, I feed it against the ship ground system.

Review Questions

13-1 Under what circumstances can an antenna tuner be of benefit in feeding a simple coax fed λ/2 dipole?

13-2 Why is it important to use low-loss transmission line such as window or ladder line if using a dipole on multiple bands?

13-3 What are the possible consequences of common mode currents on a transmission line?

Chapter 14

A Survey of Available Tuners



A selection of modern balanced antenna tuners on the left with a 1950s John Matchbox tuner.

Contents

Key Tuner Parameters 14-2

Product Review Testing 14-4

Selected QST antenn Tuner Product Review Articles
QST Reviews Five High Power Antenna Tuners 14-5

Automatic Antenna Tuners — A Sample of the Field 14-12

Medium to High Power Auto Antenna Tuners —
The Evolution Continues 14-19

A New Generation of Balanced Antenna Tuners............... 14-26

Review Questions... 14-36

Key Tuner Paramaters

Virtually every configuration of antenna tuner, capable of operation at every legal power level, is available commercially from one or more vendors. This can make selecting a commercial tuner a bit of a challenge, just as it is much tougher to select a meal from a restaurant with many good choices, compared to just a few.

Fortunately, the choices can be quickly reduced if one can make a few decisions on key tuner parameters. I will try to organize them in a way that will help make the selection easier. The following are the major decisions to be made, in this person's opinion:

What Frequencies Do You Want the Tuner to Cover?

When talking about antenna tuners, we almost always are talking about the HF range, although there are also some tuners for VHF bands. This means that we want to cover the amateur bands from 80 through 10 meters — that's a *given*. Most current amateur transceivers also cover 160 meters. Is that of interest? If so, because it often doubles the size of many tuner components, it will likely add significantly to the cost and size of a tuner, all other things being equal. The 160 meter band is gaining in popularity since it provides interesting operational conditions at the bottom of the sunspot cycle, as I write this. If you have room for effective 160 meter antennas, having a tuner that supports operation here may be a good choice.

On the other end of the spectrum is 6 meters. More and more current amateur "HF" transceiver cross into operation on our lowest VHF band. This band is also quite popular now since there are long distance modes that don't depend on sunspot activity. If you have, or expect to have, a dedicated 6 meter antenna, the chances are that it will be suitable to be fed directly with 50 Ω coax and a tuner will not be needed. On the other hand, if you will need to use your all band tuner fed antenna, such as the center-fed Zepp, on this band, you will want to include that capability in your tuner.

The other frequency decisions may be more subtle. Operation on 10 meters is sometimes a problem with larger tuners that have trouble ending up with sufficiently low minimum inductance and capacitance to provide the same impedance coverage on 10 meters as on the other bands — check the specifications to get an idea. In a similar vein, some tuners don't have quite enough maximum inductance or capacitance to provide the tuning capability to cover 80 (or 160) meters with the same range as on the other bands.

How Much Power Do You Expect to Run?

For any given tuner design, there is no factor that influences tuner cost and size more than power level. This should not be a surprise since higher power means higher voltage and current stress on the components within. The obvious answer might be to pick a tuner with a power rating equal to the most power that your transmitter can put out — but be careful, there are four issues hidden here:

- The power rating is based on the manufacturer's SWR specification (if they did a proper design job). If it says a tuner is good for an SWR of 10:1, typical for a wide range tuner, and you tune an antenna with a 20:1 SWR, you may be able to get a match, but either the voltage or the current in the tuner can be higher by a factor of $\sqrt{(20/10)}$, or 1.41 times. That may explain the arcing, or the burning smell, you observe on some frequencies! The answer may be to go somewhat higher in power rating than you expect to actually run.
- So you now have that shiny new 100 W transceiver — you love it to death and can't imagine that you will ever need more power. You buy a 100 W antenna tuner (or better a 200 W tuner, as discussed above) and happily make many contacts with your stealthy antenna. Now you decide to try for DXCC and notice that the DXpedition in Outer Slovenia can almost hear you, but can't quite copy your call letters. A bigger antenna is out of the question — the only solution is a high power amplifier. Oops, now you have an almost new 100 W tuner that you can no longer use.
- In addition to taking up more space, and more lawnmowing money, high power tuners often, because of the physical size of the components, have trouble providing the tuning range some antennas need on the higher bands. Some switch out portions of the circuit on higher bands to avoid the problem, but some don't. Keep your eye on that ball, if looking at higher power tuners.
- On the plus side, higher power tuners usually have inductors that are wound with heavier wire. This reduces losses, although it may not be noticeable in the test results.

Do You Want a Balanced or Unbalanced Tuner?

If you expect to be feeding single wire or coax-fed antennas, an unbalanced antenna tuner will be fine. If you want to feed an antenna such as a center fed Zepp with balanced line, you will need to have some provision to feed a balanced load. This can be handled in one of three ways:

- A fully balanced tuner is ideally suited to matching to balanced loads within its matching range. These are available in multiple power ranges and can work quite well. A disadvantage of these is that many do not include all the switching options of many unbalanced tuners — not a problem if you expect to use a single antenna.
- Many inherently unbalanced

tuners include an output connection through an internal balun. These work best with balanced loads within about 4:1 SWR of the balun design impedance. Most use 4:1 baluns designed for a 200 Ω load. That means they will work reasonably well with resistive loads from 50 to 800 Ω, and with complex loads of a similar SWR. They will also work outside that range, although their response can be a bit unpredictable. If they don't get hot, they are probably putting the power where you want it.

•The same kind of balun can be added outside of an unbalanced tuner if you decide to move from coax to a balanced feeder system. The same concerns as noted above apply. However there are some advantages such as that you can custom design the balun for the impedance that each antenna has, and you can have the balun some distance from the station equipment — but watch out for mismatched coax losses if the distance is more than a few feet.

Do Your Want a Remote or Local Tuner?

An antenna tuner that is located next to the radio in the station area offers a lot of plusses in terms of control and monitoring. Some antennas, however, really want the impedance matching performed at the antenna. A big consideration here is that if the tuner is located with the antenna, it usually can only operate with that single antenna, although remote switching is possible. If the antenna tuner is near the radio, switching between antennas systems is usually much easier — sometimes provided within the tuner, sometimes outside — but always within reach.

Do you Want a Manual or an Automatic Tuner?

A manual tuner requires adjusting two or three controls (and often switches) every time either frequency is changed, typically by around 50 kHz, depending on what band is selected or what type antenna is used. The adjustments can be tedious, although recording them makes returning to a proper tune under previously encountered conditions fairly easy.

An automatic tuner, on the other hand, just requires a push of the button to obtain a tune. Many have some sort of memory arrangement so they can quickly return to previous settings. The tuning usually takes a few seconds the first time, a fraction thereafter. While it is possible to imagine a remote manual tuner, to my knowledge, all remote tuners are of the automatic flavor. So if you want remote, you get automatic.

The idea of an automatic tuner sounds pretty good, and it is. There are just a few items to be aware of, as noted below:

•In general, an auto tuner will make a match within its specified SWR threshold, often 1.5:1, but check and compare with your radio's requirement. With your manual tuner, you can usually find a 1:1 setting. If the radio will put out its full power into the load, this is not worth worrying about.

•Watch out for tuners that initiate a tune on their own. Some can be just *too* automatic to suit me. You tune your radio 25 kHz off your previous frequency to capture a neat DX station, start to call, and hear your antenna tuner relays clacking. Chances are the up and down tuning will result in the station missing some part of your call sign.

Of more concern, if there is no circuitry to prevent it, many automatic tuners that can handle 100 W, for example, want tuning to occur at a lower power level to avoid burning relay contacts. If it starts up while you are operating, you can easily hit it at full power before you know what's happening. In the mobile environment, this can also happen as you pass that 18 wheeler with a giant piece of aluminum detuning your antenna (it can also serve as a reflector, if you get it in the right place!).

•I once thought that the small components in the usual compact automatic antenna tuner would result in more losses compared to the larger components, especially inductors, in the usual manual tuners. To my surprise, following the test results presented below, this does not seem to be the case, although it might be buried in the 5% minimum loss, below which we don't report due to measurement uncertainty. If it is a loss of that level (0.2 dB), in my opinion, it should not be part of the decision process.

Product Review Testing

The American Radio Relay League (ARRL), the US Amateur Radio organization publishes a monthly magazine, *QST*, for its members. In addition to its many technical and general interest features, each month's issue includes detailed reviews of products of interest to its readers. These Product Reviews generally include laboratory evaluation of equipment operational parameters using professional grade, independently calibrated test instruments. Over the years, we have had many such reviews of antenna tuners and I have reproduced the results from some here.

While many of the reviews include currently available equipment, some models covered are no longer available as new equipment. Even so, it may be of benefit in two ways:

- There is an active used equipment market in Amateur Radio equipment. This may provide a way to knowledgeably purchase an antenna tuner at a lower cost.
- In some cases, manufacturers have made relatively small changes to equipment, so data on previous models may be directly applicable.

ARRL Lab Antenna Tuner Testing Methodology

The following method was used in the ARRL Lab to measure the loss of the tuners presented below. Two test fixtures were built which would hold combinations of high power 50 Ω "non-inductive" carbon resistors (one fixture for parallel combinations and one for series), one shown in **Figure 14-1**. Even with the non-inductive resistors, some net fixture inductance was apparent at some frequencies, so a variable capacitor was used to compensate. The fixture accuracy was measured using the Lab's vector impedance meter.

Each fixture used an input connection (for the tuner) and an output connection. The output connection went to a 50 Ω input power attenuator, which took the place of one of the resistors in the load (for the series loads, it was always the one on the ground side of the network). The output of the power attenuator was connected to a high accuracy laboratory wattmeter, and the actual attenuation was measured for each frequency. The tuners were matched at low power, then 100 W of RF was applied at the input, with the output being measured by the Lab's wattmeter.

Each tuner was connected to the load fixture at each resistive impedance level for testing in the ARRL Lab. A 100 W RF source fed the input of the tuner. The resistive load was connected to the antenna output. The load was connected to a 50 Ω. power attenuator, which took the place of the final resistors. This is a close-up of the parallel load test fixture. The variable capacitor was used to compensate for fixture inductance encountered at some frequencies. While complex impedance loads could have been tested as well, the additional data points would have made testing impractical. We believe that the results at a particular SWR should be representative of other loads with the same SWR.

Note that the reviews were conducted over a period of a few years and the data taken, as well as the presentation, varied slightly from review to review. Please make sure that you are comparing equivalent data.



Figure 14-1 — Close up of test figure used to test antenna tuner efficiency into loads from 50 Ω down using paralleled 50 Ω noninductive loads.

QST Reviews Five High Power Antenna Tuners

Reviewed by Jim Parise, W1UK
ARRL Technical Advisor
QST *February, 2003*

One piece of gear that finds its way into most everyone's shack at one time or another is an HF antenna tuner. First of all, the name antenna tuner is something of a misnomer. It does not tune the antenna at all, but acts as an impedance transformer that provides your transmitting equipment with the proper load, usually 50 Ω.

Who needs an antenna tuner? Well, anyone who has the need to match an antenna with an impedance outside the range of their transmitter or amplifier's output circuits. Modern transceivers often have built-in tuners that are capable of matching SWR mismatches up to 3:1. Beyond that they need help, and if you use an amplifier you most surely will need one. Many hams find themselves with limited antenna choices and the desire to operate on frequencies other than what they were designed for, or use non-resonant multiband antennas that require a tuner. The five HF tuners we tested are all in the kilowatt class, meaning the manufacturer rates their power handling capability at 1 kW output or more.

With the wide range of frequencies in the HF spectrum and the huge diversity of antenna types in use, tuners are expected to perform under an incredible number of possible combinations. Some are more efficient at it than others. A measure of a tuner's ability to transform impedances efficiently is energy loss. Under extreme conditions a tuner can get quite hot or arc over at power levels well under the manufacturers rating. Heat in a tuner is a product of loss. RF energy being dissipated as heat is lost power that will not find its way to your antenna and onto the air.

Tuner losses generally get higher as the impedance of the load decreases. If a ham were running 1500 W into a tuner that was 50% efficient, 750 W would be dissipated in the tuner. Most of the loss in a tuner occurs in the coil, and no coil can withstand 750 W of power. A high-power tuner could probably be safely used at 50% efficiency and 100 W, but hams should be careful with high SWR and high power, or a tuner failure is a real possibility. Each tuner was tested into resistive impedances that ranged from 6.25 to 400 Ω, and their respective percentage of loss and 1.5 SWR bandwidth measured. The tuners were also used in everyday communications on all bands at power levels up to 1 kW, matching a G5RV fed with balanced ladder line and a 160 meter inverted L fed with coax.

The characteristicvs of the five uners tested are described in **Table 14-1**. Each tuner is described separately below.

Table 14-1
Comparison of Five Antenna Tuners

	Ameritron ATR-30	*MFJ MFJ-986*	*Palstar AT1500 CV*	*Ten-Tec 238A*	*Vectronics HFT-1500*
Circuit Type	T-network	T-network	T-network	L-network	T-network
SWR/wattmeter	Cross-needle	Cross-needle	Cross-needle	Single-needle	Cross-needle
Balun type	4:1 current	4:1 current	4:1 voltage	4:1voltage	4:1 voltage
Manufacturer's claimed PEP rating	3000 W	3000 W	1500 W	2000 W	2000 W
Manufacturer's claimed Matching range	35-500	35-500	20-1500	5-3000	Not specified
Physical dimensions (HWD) in inches	5.25x13x14.4	4.1x11x15.2	4.5x12.5x12	5.5x13x11	5.5x12.5x12

AMERITRON ATR-30

The ATR-30 (**Figures 14-2, 3, 4**) is Ameritron's legal limit T-network antenna tuner offering. It is housed in a plain, all black aluminum enclosure with a scratch resistant coated front panel. A look under the cover reveals two large variable capacitors and an air core edge wound silver plated roller inductor. Like most of the other tuners reviewed here, the capacitors are adjusted with vernier reduction drives, and although they tune smoothly, they require a lot of force to turn. The roller inductor is adjusted with a plastic lever type knob and is quite stiff to crank. The roller itself is a pinch roller, and the physical resistance in turning the crank may be offset by lessoned contact resistance.

The balun is constructed with three large cores and wound with wire covered with Teflon tubing. The cross-needle meter displays both average and peak power in switchable 300 W or 3 kW ranges. The wattmeter requires dc to function. It is illuminated by either a 12 V barrel connector on the back panel or a 9 V battery accessible through a trap door on the bottom of the unit. With 12 V, both the meter and inductor turns counter are illuminated. When a 9 V battery is used, the meter will function, but the panel lamps will not light.

Finding a match on 80 meters on the G5RV required quite a bit of time finding the right combination of capacitor tuning and inductance, and the stiff controls didn't make it much fun. Finding the sweet spot on the higher bands was much easier. There are three coax outputs on the ATR-30, including two that may be switched direct or through the T-network and a third direct only. Single or balanced feed lines connect to large ceramic binding posts with wing nuts. Test results are summarized in **Table 14-2**.

Manufacturer: Ameritron, 116 Willow Rd, Starkville, MS 39759; tel 662-323-8211; fax 662-323-6551; **www. ameritron.com**. 2003 price: $599.95.

Table 14-2
Ameritron ATR-30 Loss and Bandwidth Test Results

SWR	*Load (Ω)*		*160 m*	*80 m*	*40 m*	*20 m*	*10 m*
8:1	6.25	Power Loss %	20	12	<10	<10	<10
		1.5 SWR BW	1	3	>5	4	>5
4.1	12.5	Power Loss %	15	<10	<10	<10	<10
		1.5 SWR BW	3	4	>5	>5	>5
2:1	25	Power Loss %	10	<10	<10	<10	<10
		1.5 SWR BW	4	>5	>5	>5	>5
1:1	50	Power Loss %	<10	<10	<10	<10	<10
		1.5 SWR BW	>5	>5	>5	>5	>5
2:1	100	Power Loss %	<10	<10	<10	<10	<10
		1.5 SWR BW	>5	>5	>5	>5	>5
4:1	200	Power Loss %	<10	<10	<10	<10	<10
		1.5 SWR BW	>5	>5	>5	>5	5
8:1	400	Power Loss %	<10	<10	<10	<10	<10
		1.5 SWR BW	>5	>5	>5	>5	3

Notes
Power losses are expressed as a percentage. A 21% loss of power is 1 dB.
The 1.5-SWR Bandwidth (SWR BW) represents the bandwidth over which an SWR of 1.5:1 or less was maintained as a percentage of the measurement frequencies (1.8, 3.5, 7.2, 14.2 and 29.7 MHz).



Figure 14-3 — Interior circuitry of the Ameritron ATR-30.


TRANSMITTER
ANTENNA
INDUCTANCE
COAX 1
COAX 2
COAX 3 DIRECT
WIRE BAL LINE
COAX 2 DIRECT
COAX 1 DIRECT
METER
PEAK
AMERITRON
ATR-30
ANTENNA TUNER

Figure 14-2 — Front panel of the Ameritron ATR-30.


BAL LINE
Install Jumpers For Balanced Line Operation
WIRE
COAX 3 DIRECT
COAX 2
METER LAMP
12V DC
TRANSMITTER
COAX 1
AMERITRON
MODEL No: ATR-30
Serial No
GND
AMERITRON
STARKVILLE, MS USA

Figure 14-4 — Rear panel connections on the Ameritron ATR-30.

MFJ-986

The '986 is one of more than 20 antenna tuner products offered by the prolific MFJ (in 2003). It is rated for 1500 W PEP within the 35-500 Ω impedance range, positioning it alongside the '989C as one of their high power units. Unlike the traditional T-network with a pair of variable capacitors, the '986 (**Figures 14-5, 6, 7**)makes use of a single variable capacitor and a wire wound air core roller inductor with a three digit turns counter. The tuner uses what MFJ describes as a "differential" capacitor. It has two discrete sets of fixed plates and one variable set, with a single capacitor control, forming a T-network with the inductor.

The cabinet is narrow and extends nearly 18 inches deep. The cross-needle meter has a high (3000 W) and low (300 W) setting switched by a front panel button, and it can display average and peak power as well as SWR. Providing 12 V to the connector on the back panel brightly illuminates the meter. Both the capacitor and roller inductor are directly driven. The inductance knob has a finger depression, which are often found on a transceiver's tuning knob. It is somewhat awkward to turn due to binding. The tuner had a tendency to creep around the operating desk when the inductor is rapidly turned. A check inside revealed several loose screws holding the inductor to the chassis. Tightening these did improve the smoothness somewhat.

The '986 provided a match to both antennas quickly, but arced over on 80 meters with the inverted L at 900 W. While this tuner does provide ease of use, one should give careful consideration to the loss figures in the tables. During operation the meter developed an intermittent problem with both needles going off scale even with very low power applied and a low SWR. Movement of the SWR bridge circuit board on the inside back panel seemed to correct the problem.

Two coax outputs are provided that can be switched to bypass the tuning circuit, as well as a third output for a dummy load. Balanced and single-wire feed lines connect to large ceramic feed through posts with wing nuts. A 4:1 two-core current balun is provided at the output. Test results are summarized in **Table 14-3**.

Manufacturer: MFJ Enterprises, Inc, PO Box 494, Mississippi State, MS 39762; tel 800-647-1800; fax 662-323-6551; **www.mfjenterprises.com**. 2003 price: $329.95.

Table 14-3
MFJ-986 Loss and Bandwidth Test Results

SWR	*Load (Ω)*		*160 m*	*80 m*	*40 m*	*20 m*	*10 m*
8:1	6.25	Power Loss %	47	31	21	16	13
		1.5 SWR BW	1	1	2	4	>5
4.1	12.5	PowerLoss %	33	22	14	12	11
		1.5 SWR BW	1	1	4	5	>5
2:1	25	PowerLoss %	25	20	10	<10	10
		1.5 SWR BW	1	2	4	>5	>5
1:1	50	PowerLoss %	22	12	<10	<10	<10
		1.5 SWR BW	2	3	>5	>5	>5
2:1	100	PowerLoss %	15	10	<10	<10	19
		1.5 SWR BW	3	5	>5	>5	>5
4:1	200	PowerLoss %	11	<10	<10	<10	<10
		1.5 SWR BW	3	>5	>5	>5	>5
8:1	400	PowerLoss %	10	<10	<10	11	16
		1.5 SWR BW	3	>5	>5	>5	5

Notes

Power losses are expressed as a percentage. A 21% loss of power is 1 dB.

The 1.5-SWR Bandwidth (SWR BW) represents the bandwidth over which an SWR of 1.5:1 or less was maintained as a percentage of the measurement frequencies (1.8, 3.5, 7.2, 14.2 and 29.7 MHz).



Figure 14-6 — Interior circuitry of the MFJ-986.


MFJ DIFFERENTIAL-T TUNER
ROLLER INDUCTOR TUNER
DIFFERENTIAL CAPACITANCE
INDUCTANCE
ANTENNA
COAX 1
COAX 2
EXT. DUMMY LOAD
BAL LINE
COAX 2 DIRECT
COAX 1 DIRECT
LAMP
ON
OFF
POWER
HI
LO
PEAK
AVG
METER

Figure 14-5 — Front panel of the MFJ-986.


DUMMY LOAD
COAX 2
METER LAMP
12V DC
WIRE
BAL LINE
MFJ ENTERPRISES, INC.
STARKVILLE, MS USA
COAX 1
TRANSMITTER
Install Jumper For Balanced Line Operation
GND

Figure 14-7 — Rear panel connections on the MFJ-986.

PALSTAR AT1500CV

The Palstar AT1500CV (**Figures 14-8, 9, 10**) is a T-network tuner solidly constructed in a compact aluminum enclosure. Inside, the metering and SWR bridge circuitry are encased in their own aluminum boxes. The moderately sized variable capacitors are mounted side by side and feature large calibrated dials and silky smooth vernier tuning that allows for precise adjustment. Palstar indicates that newer units incorporate a roller bearing assembly which makes inductor adjustment smoother. The roller inductor is quite large. It is an air core silver plated edge wound coil with heavy-duty ceramic forms. Control of the inductor is via a lever handle and mechanical turns counter. It is not as smooth as some of the other tuners and tends to lurch as it is rotated during fine adjustments. The cross-needle meter displays SWR and average forward and reflected power in 300 and 3000 W ranges, with no option for peak power metering. It is illuminated with 12 V from an included wall adapter.

Achieving a 1:1 SWR on the G5RV was possible on all bands from 80 through 10 meters at its rated power maximum of 1000 W single tone. Similar results were noted on the inverted L. Although the tuning chart provided in the manual does not include settings for 30 meters, the tuner easily matched both antennas on that band. This tuner has a solid feel to it and doesn't creep around while making adjustments.

In laboratory tests, the AT1500CV had more difficulties on 160 meters than on other bands. A 1:1 SWR was only obtainable with the 25 and 50 Ω loads, the power losses at 160 meters were measurably greater than those on other bands at the same loads. The variable capacitors are 240 pF maximum, which explains the 160 meter performance. The tradeoff results in lighter weight.

Antenna connections on the back panel include three coax inputs. Two are available direct or through the tuning network and one is bypassed

Table 14-4
Palstar AT1500CV Loss and Bandwidth Test Results

SWR	*Load (Ω)*		*160 m*	*80 m*	*40 m*	*20 m*	*10 m*
8:1	6.25	Power Loss %	No Match	25	16	12	12
		1.5 SWR BW		1	2	>5	3
4.1	12.5	Power Loss %	No Match	16	13	<10	11
		1.5 SWR BW		2	4	>5	>5
2:1	25	Power Loss %	21	13	<10	<10	<10
		1.5 SWR BW	2	3	>5	>5	>5
1:1	50	Power Loss %	13	<10	<10	<10	<10
		1.5 SWR BW	3	>5	>5	>5	>5
2:1	100	Power Loss %	No Match	<10	<10	<10	13
		1.5 SWR BW		>5	>5	>5	>5
4:1	200	Power Loss %	No Match	<10	<10	<10	12
		1.5 SWR BW		>5	>5	>5	>5
8:1	400	Power Loss %	No Match	<10	<10	<10	<10
		1.5 SWR BW		>5	>5	>5	5

Notes
"No Match" means that a 1:1 SWR could not be obtained.
Power losses are expressed as a percentage. A 21% loss of power is 1 dB.
The 1.5 SWR Bandwidth (SWR BW) represents the bandwidth over which an SWR of 1.5:1 or less was maintained as a



Figure 14-10 — Interior circuitry of the Palstar AT1500CV.



Figure 14-8 — Front panel of the Palstar AT1500CV.



Figure 14-9 — Rear panel connections on the Palstar AT1500CV.

straight through. The bypass output can also be used with an optional 4:1 balun available for $39.95 [2003]. Balanced or single wire feed lines are attached to Delrin terminal posts with wing nuts.

Longer threaded material on the terminal posts would be a welcome improvement and make attachment of larger gauge wire much easier. In one isolated circumstance during lab testing, our engineer felt an RF bite on 10 meters through the metal portion of the inductor crank. This did not seem to be a pervasive problem, and Palstar indicates that the grounding on the crank has also recently been improved. Test results are summarized in Table 14-4.

Manufacturer: Palstar, Inc, 9676 N Looney Rd, PO Box 1136, Piqua, OH 45356; tel 937-773-6255; fax 937-773-8003; **www.palstarinc.com**. 2003 price: $429.95, optional 4:1 balun $39.95.

TEN-TEC 238A

The Ten-Tec 238A (**Figures 14-11, 12** and **13**) is the only tuner in our roundup to utilize an L-network. Using an innovative switching arrangement, the '238A actually provides five different circuit configurations to maximize efficiency. A look at the low loss figures in the table confirms this. The well-constructed tuner makes use of a single variable capacitor and a smooth turning wire-wound roller inductor to match impedances up to 3000 Ω. Additional capacitance can be switched into the circuit by means of a front panel switch. Five settings each are available for high and low impedances, as well as a bypass choice. A ceramic feed through post on the back panel provides a connection to add an additional 1000 pF capacitor (included with the tuner) to the circuit for matching 160 meter antennas. The small dual use meter can be switched to display SWR or RF power in either a 2000 or 200 W range. The meter lamp is powered by 12 V on the back panel.

The '238A handily matched all bands on both test antennas at full legal limit power. On 10 meters using the G5RV, the capacitor and inductor controls were a bit sensitive to small adjustments. One minor complaint: Measuring forward power in the high power range on the meter caused the indicator to slap the right extreme position during CW keying.

In laboratory tests, the '238A did not match on 160 meters into a 6.25 Ω until 2700 pF of external capacitance was added. Ten-Tec indicates they will provide additional capacitors to purchasers at no extra charge. Also, the power losses on 10 meters were considerably greater than those on other bands. However, the '238A performed very admirably on most other bands, quite often exhibiting the least losses on given band and load combinations.



Figure 14-13 — Interior circuitry of the Ten-Tec 238A.



Figure 14-11 — Front panel of the Ten-Tec 238A.



Figure 14-12 — Rear panel connections on the Ten-Tec 238A.

Table 14-5
Ten-Tec 238A Loss and Bandwidth Test Results

SWR	*Load (Ω)*		*160 m*	*80 m*	*40 m*	*20 m*	*10 m*
8:1	6.25	Power Loss %	No Match	<10	<10	<10	28
		1.5 SWR BW		>5	>5	>5	2
4.1	12.5	Power Loss %	<10	10	<10	<10	22
		1.5 SWR BW	>5	>5	>5	>5	2
2:1	25	Power Loss %	<10	10	<10	<10	17
		1.5 SWR BW	>5	>5	>5	>5	3
1:1	50	Power Loss %	<10	<10	<10	<10	<10
		1.5 SWR BW	>5	>5	>5	>5	>5
2:1	100	Power Loss %	<10	<10	<10	<10	20
		1.5 SWR BW	>5	>5	>5	>5	4
4:1	200	Power Loss %	<10	<10	<10	<10	20
		1.5 SWR BW	>5	>5	>5	>5	4
8:1	400	Power Loss %	<10	<10	<10	10	13
		1.5 SWR BW	>5	>5	>5	>5	1

Notes

"No Match" means that a 1:1 SWR could not be obtained, even with the included 1000 pF external capacitor attached. A match on 160 m at 6.25 was achieved with 2700 pF of external capacitance; the power loss was less than 10%, and the 1.5 SWR BW was greater than 5%.

Power losses are expressed as a percentage. A 21% loss of power is 1 dB. The 1.5-SWR Bandwidth (SWR BW) represents the bandwidth over which an SWR of 1.5:1 or less was maintained as a percentage of the measurement frequencies (1.8, 3.5, 7.2, 14.2 and 29.7 MHz).

The four-position antenna switch on the front panel allows selection of four coax outputs or a balanced/random wire. The balanced output and one coax connector share position four. A two-core balun is provided for matching the balanced output. The '238A is the only one of the five tuners reviewed here without an air-core inductor. The inductor here has a linen phenolic core.

Since we purchased our review unit, Ten-Tec has produced a substantially identical antenna tuner, the '238B. The Tennessee manufacturer is now selling only the '238B model. Test results are summarized in **Table 14-5**.

Manufacturer: Ten-Tec, 1185 Dolly Parton Pky, Sevierville, TN 37862; tel 865-453-7172; fax 865-428-4483; **www.tentec.com.** 2003 price: $475.00 ('238B).

VECTRONICS HFT-1500

The first thing you notice about the HFT-1500 (**Figures 14-14, 15** and **16**) is the LED bar graph on the front panel that is used to display relative peak forward power. The bright green bar graph is adjusted to its maximum scale with a level control on the front panel to a known forward power reading on the cross-needle wattmeter. While it doesn't show actual power readings, it does give a quick visual indication of peak power. The cross-needle meter displays only average power and SWR in two power ranges selected by a pushbutton switch.

The traditional T-network design uses two 4.5 kV variable capacitors adjusted with large comfortable



Figure 14-16 — Interior circuitry of the VECTRONICS HFT-1500.


VECTRONICS
LAMP
ON
OFF
RANGE
300W
3000W
LEVEL
OFF
DELAY
Peak Forward Power
INDUCTOR
DIRECT
TUNED
COAX 2
COAX 1
COAX 1
COAX 2
BYPASS
WIRE/BAL
ANTENNA
TRANSMITTER
Model HFT1500 Digital Peak Reading Antenna Tuner

Figure 14-14 — Front panel of the VECTRONICS HFT-1500.


VECTRONICS
STARKVILLE, MS, USA
Serial No.
VECTRONICS
Starkville, MS, USA
DC INPUT
+ 13Vdc, 300mA
RF INPUT
GROUND
BALANCED LINE
COAX 2
COAX 1
WIRE
BYPASS

Figure 14-15 — Rear panel connections on the VECTRONICS HFT-1500.

Table 14-6
Vectronics HFT-1500 Loss and Bandwidth Test Results

SWR	*Load (Ω)*		*160 m*	*80 m*	*40 m*	*20 m*	*10 m*
8:1	6.25	Power Loss %	45	42	16	15	8
		1.5 SWR BW	1	<1	2	5	>5
4.1	12.5	Power Loss %	32	31	11	<10	<10
		1.5 SWR BW	>5	>5	3	>5	>5
2:1	25	Power Loss %	19	24	<10	<10	<10
		1.5 SWR BW	2	1	>5	>5	>5
1:1	50	Power Loss %	12	<10	<10	<10	<10
		1.5 SWR BW	3	>5	>5	>5	>5
2:1	100	Power Loss %	12	<10	<10	<10	<10
		1.5 SWR BW	3	>5	>5	>5	>5
4:1	200	Power Loss %	<10	<10	<10	<10	<10
		1.5 SWR BW	4	>5	>5	>5	>5
8:1	400	Power Loss %	<10	<10	<10	11	16
		1.5 SWR BW	4	>5	>5	>5	4

Notes

Power losses are expressed as a percentage. A 21% loss of power is 1 dB.

The 1.5-SWR Bandwidth (SWR BW) represents the bandwidth over which an SWR of 1.5:1 or less was maintained as a percentage of the measurement frequencies (1.8, 3.5, 7.2, 14.2 and 29.7 MHz).

knobs and very smooth vernier tuning. This tuner stays put on the desk while you utilize a lever handle and gear driven five digit mechanical turns counter to adjust the air wound roller inductor.

Tuning the 160-meter inverted L and the G5RV on all bands except 10 meters was easily accomplished, with no problems handling 1 kW. In the field, the best SWR that could be obtained on 10 was 2.33:1; this is possibly due to the additional "loading" when a human touches the all-metal inductor crank. The ARRL Lab adjusted the inductor with a wooden pencil in some cases to obtain a match.

The HFT-1500 provides two coax inputs and a third that completely bypasses the tuning network. The balanced and single wire inputs are Delrin terminal posts connected to a large single core 4:1 voltage balun. In some circumstances during lab testing, our engineer felt RF bites through the metal portion of the inductor crank. Later units feature a metal shaft bushing that provides a better ground. This was not experienced in field testing, but tuner adjustments were not made at high power. Test results are summarized in **Table 14-6**.

Manufacturer: Vectronics, 300 Industrial Park Rd, Starkville MS 39759; tel 662-323-5800; fax 662-323-6551; **www.vectronics.com**. 2003 price: $459.95.

Automatic Antenna Tuners — A Sample of the Field

Reviewed by Joel R. Hallas, W1ZR
QST *Technical Editor*
QST *May, 2004*

Automatic antenna tuners can provide a quick and easy method of matching multiband or nonresonant antennas quickly and effortlessly. Performance is on par with manual tuners and there is now a selection available providing a fit to most requirements. A few years back, we surveyed the antenna tuner market in these pages. All those tuners were manual ones.

A few automatic tuners were available at that time, but they were the exception rather than the rule. Since then, a number of manufacturers have focused their attention on automatic antenna tuners and it seems as if there's now one for every application.

For this review we selected representative tuners from a number of manufacturers (see **Figure 14-17**). There are two general configurations: those providing remote tuning, with the tuner intended to be near the antenna, and those intended to be collocated with the station equipment. For those manufacturers having models in each camp, we selected one of each.

As noted in the specifications, each tuner is different and they don't exactly line up head-to-head, so a direct comparison is not always appropriate. Still, for each we will provide the basic data you would need to decide if one of these is a good fit for your needs. If you like the looks of a particular manufacturer, but the tuner reviewed doesn't exactly meet your requirements, check their Web page or your dealer for other models at different power levels or with different features.

For this review we stuck to those at the 100 to 200 W level and tried for a representative self-contained and remote tuner from each manufacturer. For these tests, we looked at units designed to work with any radio. In addition to these, most HF radio manufacturers offer external auto tuners designed to operate exclusively with their radios. One manufacturer, LDG, also offers tuners with the capabilities to operate with specific radios' commands. Many HF radio manufacturers also offer internal auto-tuners as a part of their transceivers. We generally review these as a part of the radios. We elected to stick to general purpose models for this review.

Those selected for this test include the RT-11 and Z-100 from LDG, the MFJ-991 and from SGC the SG-237 and MAC-200.

Remote vs Collocated Autotuners

It's probably worth a paragraph or two to discuss the relative merits and appropriateness of the two configurations. If the antenna(s) to be matched terminate right at the station equipment, without a transmission line (or with a very short one), there is no particular advantage to having a remote tuner.

On the other hand, that setup often results in problems with "RF in the shack," or EMI within the house. I have one antenna setup of that form and whenever I use it, the RF resets the kitchen FM radio, causing it to lose track of time and memory. Most find it a better solution to have the antenna system stop somewhere outside the house and have a transmission line interconnect the radio and antenna.

With a remote tuner, the matching can be at or near the antenna, resulting in a well matched transmission line coming back to the radio. With the tuner at the radio, the matching takes place near the radio, and the SWR on the line out to the antenna will often be high. Note that in both cases the radio will be provided a good match and will happily put full power into the system. With the remote tuner, often more of the power will be radiated by the antenna and less will be dissipated as heat by the transmission line.

Some radios now come with automatic tuners as part of the radio. These can be functionally equivalent to the local tuner. The separate tuner does offer two advantages over the



Figure 14-17 — Automatic tuners from LDG, MFJ and SGC — ready for test.

internal tuner — it can support multiple radios, and most can match a higher SWR than many of the internal tuners. The key factor in deciding between a local and a remote tuner then becomes how much of the transmitter power actually reaches the antenna system and how much will heat up the transmission line. This is a function of operating frequency, SWR and line length.

The place to start the analysis is with *The ARRL Antenna Book.*[1] Figure 23 in Chapter 24 provides the attenuation in 100 feet of *matched* transmission line for each of the common types. Table 14 in the same chapter provides the *additional* loss for the non-matched case as a function of SWR and matched loss. [The same data is in Chapter 7 of this book.] Using the two tables, you can determine the total loss of your transmission line.

If the loss is acceptable, you can tune at the transmitter end. If not, by tuning at the antenna end you can eliminate most of the additional loss due to mismatch.

An example might be helpful. A multiband antenna such as my G5RV might have a 5:1 SWR on parts of 10 meters. If we feed it with 150 feet of RG-58 cable we have a matched loss of about 3.5 dB and the 5:1 SWR adds about another 2 dB for a total of 5.5 dB loss or about 71% of our power heating up the line! By moving the tuner to the antenna end of the coax, we reduce that to 55%. Another option is to change the transmission line (my solution immediately after making that calculation!).

If we go with lower loss RG-8 instead, we have a matched loss of about 2 dB (1.3 dB per 100 ft) and the SWR adds about another 0.3 dB for a total of 2.3 dB, or a loss of about 41% of our power. With the tuner at the antenna, the total loss would be the 2 dB or 37%—not much of a difference. Note that I didn't consider the tuner losses here, under the assumption that they would be the same at either location. The numbers get much more grim as the SWR goes up, by the way.

Two notes of caution—first, if you measure the SWR at the shack end of the cable, it will appear better than it is, due to the cable loss; second, the matched loss from Figure 23 is the *best* matched loss for new and dry cable. The actual loss can only go up from there, especially if the cable came from some dark corner of your basement, or worse, from an unknown source at a flea market.

Note that all of these tuners are designed for unbalanced (coax) cable between the tuner and the radio and, with the exceptions noted, unbalanced operation on the antenna side (coax or single wire antennas) as well. In order to use these tuners with a balanced load, it is best to decouple the ground side of the tuner from the transmission line. A coax choke can be used, or a balun (balanced to unbalanced transformer) can be employed. If you are using a balun, it is best to keep the line impedance within a SWR of about 4:1 (with respect to the usual 200 Ω impedance of a 4:1 balun) to avoid heating, loss and possible balun damage. A subsequent planned review will look at the special class of unbalanced to balanced tuners that sidestep this issue in an elegant way and are once again appearing on the market.

A word or two about the data shown may be in order. Please note that we used the same precision resistive load set for each tuner. In most cases, this includes data outside the manufacturers' specification range. We measured at a single frequency in each band, and for 6 meters we just measured the case with a 1:1 load for all the tuners that claimed operation there.

LDG RT-11 and Z-100

A look at LDG's Web page, **www.ldgelectronics.com**, will show you their selection of tuners and accessories. In addition to the RT-11 remote control tuner and the Z-100 local tuner, tested (see **Figure 14-18**), they offer an autotuner rated at 1000 W. As this review was being prepared in 2004, they also announced a much more feature rich desktop unit to complement the very basic, but lower cost Z-100.



Figure 14-18 — LDG RT-11 (left) with control box and Z-100. A 12 ounce beverage container provides scale.

---

[1] Notes appear on page 14-35.

LDG RT-11

The RT-11 is a rugged, weatherproof tuner designed to be used inside or outdoors. It has coax connectors on input and output and is rated at 125 W from 1.8 to 30 and 50 W to 54 MHz. It is rated to match antennas with an SWR of 10:1 to 30 MHz and 3:1 from 50 to 54 MHz. This unit has an optional remote control designed to be used up to 100 feet from the tuner (15 foot cable supplied).

The remote control provides the ability to force a new tune, set for semi or full auto operation, keep the unit from tuning and allows bypassing of the tuner (straight through operation for matched antennas or out of band receive). In addition, LED indicators let you know the status and whether the SWR is below 1.5:1. One caution with the remote, the mounting bracket screws are not captive so you may want to use double-sided tape to secure it to a surface.

The RT-11 also has a jack to allow interfacing to radios designed to control proprietary tuners by emulating their commands. Special cables are offered to hook to various Alinco, ICOM, Kenwood and Yaesu radios for this purpose.

In my trials at home, I found that the RT-11 effortlessly tuned every antenna I had on all bands with a very low SWR, always well below 1.5:1. The tuning seemed to take about 5 seconds and hit the result the first time.

While automatic operation is possible without radio interface or remote control, I would have trouble imagining it and would suggest the remote for those without a compatible radio. For one thing, once tuned, it won't automatically restart the tuning process until the SWR reaches 3:1, a value that might cause many radios to "fold back" (reduce power) significantly.

The manual mentions that tuning should take place at the 25 W level, with full power applied only after tune is achieved, so that relay life will not be reduced. They also indicate that if a radio has the common power output fold back with high SWR it will automatically reduce power appropriately. I wouldn't count on that providing sufficient reduction, especially as the match is approached; I would instead manually reduce power while tuning.

LDG Z-100

The Z-100 is a self contained desk top unit with a 125 W rating (50 W on 6 meters). This unit is the first of a new series of tuners being released by LDG, with others providing additional features and controls. This is a basic unit corresponding to its low price, but none the less provides the needed tuning functions with straightforward "one button" operation. It includes memory of the settings for the last 200 matches made and tries those before it branches to its *unknown tune* algorithm. This is a clever idea that avoids the need to measure frequency. It is particularly useful for the case in which more than one antenna is used, since it really doesn't care — if it made the match before it will do it again, in a fraction of a second.

A feature of this unit is that it only draws power when actually tuning. Upon completion, the relays remain latched without power required until

Table 14-7
LDG RT-11 Remote Automatic Antenna Tuner

Manufacturer's Specifications	*Measured in ARRL Lab*
Input SWR range: to 10:1 (3:1 on 6 meters).	See below.
Output SWR range: not specified.	See below.
Frequency coverage: 1.8 to 54 MHz.	As specified.
Input power: 0.1 to 125 W, 50 W on 6 meters.	Tested at 50 W on HF, 20 W on 6 meters.
Power requirements: 11 to 14 V dc, 7 to 250 mA.	Idle 0 mA, max 140 mA at 13.8 V dc.

Measured power loss into resistive loads (%) / Input SWR at match:

SWR	*Load (Ω)*	*160 Meters*	*80 Meters*	*40 Meters*	*20 Meters*	*10 Meters*	*6 Meters*
16:1	3.125	No Match	No Match	27 <1.5:1	22 2.6:1	<10 <1.5:1	
8:1	6.25	No Match	17 <1.5:1	17 <1.5:1	19 <1.5:1	20 <1.5:1	
4:1	12.5	11 <1.5:1	11 <1.5:1	12 <1.5:1	13 <1.5:1	26 <2:1	
2:1	25	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	23 2.1:1	
1:1	50	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	21 2.1:1
2:1	100	<10 <2:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	17 <1.5:1	
4:1	200	<10 <2:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	15 <1.5:1	
8:1	400	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	28 <1.5:1	
16:1	800	<10 <1.5:1	12 <1.5:1	<10 <1.5:1	<10 <1.5:1	19 <1.5:1	

Table 14-8
LDG Z-100 Desktop Automatic Antenna Tuner

Manufacturer's Specifications	*Measured in ARRL Lab*
Input SWR range: to 10:1 (3:1 on 6 meters).	See below.
Output SWR range: not specified.	See below.
Frequency coverage: 1.8 to 54 MHz.	See text.
Input power: 0.1 to 125 W, 50 W on 6 meters.	Tested at 50 W on HF, 20 W on 6 meters.
Power requirements: 7 to 18 V dc, 250 mA.	Idle 0 mA, max 160 mA at 13.8 V dc.

Measured power loss into resistive loads (%) / Input SWR at match:

SWR	*Load (Ω)*	*160 Meters*	*80 Meters*	*40 Meters*	*20 Meters*	*10 Meters*	*6 Meters*
16:1	3.125	No Match	No Match	15 <1.5:1	10 <1.5:1	<10 <1.5:1	
8:1	6.25	No Match	13 2.6:1	15 <2:1	15 <1.5:1	20 <2:1	
4:1	12.5	No Match	<10 <1.5:1	<10 <1.5:1	<10 <2:1	<10 <1.5:1	
2:1	25	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	17 <1.5:1	
1:1	50	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	20 <2:1
2:1	100	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	
4:1	200	<10 2.1:1	<10 2.2:1	<10 <1.5:1	11 <1.5:1	<10 <1.5:1	
8:1	400	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	11 <1.5:1	<10 <2:1	
16:1	800	11 2.2:1	14 2.3:1	15 <1.5:1	33 <1.5:1	43 <1.5:1	

the next tune is requested. This is particularly appealing for portable low power operations in which every milliamp-hour is carried in.

The operation of this tuner is fundamentally different from the others in that it will only tune when the TUNE button is pushed. This has an advantage in that it will not start tuning inadvertently on high SWR, potentially applying full power during tune. Upon changing frequency, the operator can decide whether or not to initiate the tune cycle. By pushing the button for less than 0.5 seconds, the tuner goes to bypass. Between 0.5 and 3 seconds the tuner will attempt to find a match from memory (typically less than half a second), and only initiate a full tune if needed. If the button is pushed for more than 3 seconds a full tune cycle is initiated, ignoring any memorized settings.

This is easier to deal with than it sounds since the LEDs provide a confirmation of tuning mode. A green LED also indicates if the match is less than 1.5:1 or between 1.5 and 2:1. An early production unit exhibited some inconsistent tuning results on 6 meters. The manufacturer has developed a method of improved internal decoupling that solved this problem and the results reflect that change. LDG states that this will be included in future production units and that anyone having problems with 6 meter tuning on early units should contact them directly.

Manufacturer: LDG Electronics Inc, 1445 Parran Rd, PO Box 48, St Leonard, MD 20685; tel 877-890-3003; fax 410-586-8475; **www.ldgelectronics.com**. 2004 prices: RT-11 Tuner, $209; Remote head, $39; Z-100, $149; 12 V power cube for either tuner, $10.

MFJ-991



Figure 14-19 — MFJ-991 Autotuner.

MFJ has recently announced a series of autotuners. All are in the typical indoor/ colocated configuration, but with the available remote kit (ordered, but not received in time for the review) can be used as a remote tuner if kept out of the weather. They offer the MFJ-991 (tested, as shown in **Figure 14-19**) 150 W rated tuner, a tuner with similar features rated at 600 W and a 300 W autotuner with digital display, balun and two port antenna switch. As with the LDG, the MFJ tuners require their tuning be accomplished at reduced power.

The MFJ-991 front panel provides full control capability and forward and reflected power metering with "crossed-needle" SWR measurement display. Two features of the '991 are not found on other tested units and are worth mentioning. First, the '991 has the capability to allow manually adjusting the C and L values of the tuner while in receive. This is helpful if you are using your radio for receive only and wish to attempt to match in order to increase signal strength. The second feature is the ability to select the SWR threshold at either 1.5 or 2:1.

In our testing the tuner went to the best match it could find in either case. The difference was in how far you could change frequency before it would automatically retune when you transmitted. If your radio can tolerate a 2:1 SWR, this could provide a benefit. The '991 could tune my G5RV on all bands and remembered the last setting for each frequency (1000 memories), with a one-click reset. Tuning the first time on a frequency was typical of the cycle time of the other units. This unit sounded somewhat louder (it has 18 heavy duty relays) than the other test samples, although not an issue for the single click associated with a memorized tune.

The MFJ-991 can interoperate with ICOM and Alinco tuner control commands. Appropriate interface cables are available from MFJ.

In addition to the obvious controls and indicators, there are some subtle ones as well. There are a number of meter "signals" sent to the operator that will not be clear without a cruise through the manual. For example, if you forget to reduce power before tuning, the power meter swings to full scale and the tuner is bypassed. If you toggle between 1.5 and 2:1 SWR threshold, the meter briefly jumps up to indicate that SWR.

Manufacturer: To order, or for your nearest MFJ dealer, call MFJ Enterprises at 800-647-1800 or order at **www.mfjenterprises. com**, fax 662-323-6551; or write MFJ Enterprises, Inc, 300 Industrial Park Rd, Starkville, MS 39759. [2004] Price: $220.

Table 14-9
MFJ-991 Desktop/Remote Automatic Antenna Tuner

Manufacturer's Specifications	*Measured in ARRL Lab*
Input Impedance range: 6 to 3200 Ω.	See below.
Output SWR range: 1.5:1 or 2:1 selectable.	See below.
Frequency coverage: 1.8 to 30 MHz.	As specified.
Input power: 5 to 150 W.	Tested at 50 W.
Power requirements: 12 to 15 V dc, 1.0 A.	Idle 90-300 mA, max 500 mA at 13.8 V dc.

Measured power loss into resistive loads (%) / Input SWR at match:

SWR	*Load (Ω)*	*160 Meters*	*80 Meters*	*40 Meters*	*20 Meters*	*10 Meters*
16:1	3.125	No Match	27 <1.5:1	20 <1.5:1	15 <1.5:1	<10 <2:1
8:1	6.25	12 <1.5:1	14 <1.5:1	15 <1.5:1	24 <1.5:1	19 2.6:1
4:1	12.5	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	12 <1.5:1
2:1	25	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1
1:1	50	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1
2:1	100	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1
4:1	200	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1
8:1	400	<10 <1.5:1	<10 <1.5:1	<10 <1.5:1	11 <1.5:1	11 <1.5:1
16:1	800	<10 <1.5:1	16 <1.5:1	<10 <1.5:1	<10 <1.5:1	23 <1.5:1

SGC SG-237 and MAC-200

SGC has been making automatic antenna tuners for many years, and offers a wide selection. Until recently, they concentrated on remote tuners, usually the weatherproof type, at power ratings of 100 to 500 W. More recently, they have introduced a number of variations of their SG-237, a board version to build into your own radio or antenna cabinet, an open enclosure model for remote but indoor use and one with controls and indicators intended for portable use. They have recently released a Multiple Antenna Controller, MAC-200. The units we tested were an SG-237 (one that has fed the backstay of my sailboat for some years) and a relatively new combination unit, the MAC-200 (as shown in **Figure 14-20**).



Figure 14-20 — SGC SG-237 (left) and MAC-200.

SGC SG-237 Autotuner

The SG-237 was the first in a series of SGC tuners that were much more compact than their previous (and continuing) line, the SG-230 (200 W, 1.6-30 MHz), SG-231 (100 W, 1-60 MHz) and SG-235 (500 W, 1.8-30 MHz). The SG-237 is rated at 100 W PEP, both for operation and for tuning (40 W continuous carrier power). The transmitter connection is via a 9 foot combined RF, control and power cable (25 and 50 foot extensions are available), while the antenna connection is via a single ceramic insulated terminal. While the tuner is designed to feed a single wire against ground, I have successfully employed mine into coax fed antennas as well as loops and single wires.

This is a rugged unit in a compact waterproof aluminum enclosure that can slide in almost anywhere. It needs no remote control box to work, and I've used mine that way for years. An optional remote control is offered (and we tested with it) to provide a positive indication of match and to allow a lockout or a forced reset. The lockout can be handy in a portable or mobile environment to avoid the tuner attempting to retune due to the temporary proximity of outside objects while in motion, for example.

The '237 provides a memory function that uses the measured transmitter frequency to result in the tuner settings last used to successfully tune to that frequency. This means that instead of taking 5 to 10 seconds to tune, the previously stored settings for a frequency are applied in milliseconds and used if the resulting SWR

Table 14-10
SGC SG-237 Remote Automatic Antenna Tuner

Manufacturer's Specifications	*Measured in ARRL Lab*
Input SWR range: corresponding to a minimum 7 foot antenna above 3.5 MHz, 23 feet above 1.8 MHz.	See below.
Output SWR range: 1.4:1 typical.	See below.
Frequency coverage: 1.8 to 60 MHz.	As specified.
Input power: 3 to 100 W.	Tested at 50 W.

Power requirements: 10.5 to 18 V dc, 300 mA. Idle and tuning 270 to 480 mA at 13.8 V dc.

Measured power loss into resistive loads (%) / Input SWR at match:

SWR	*Load (Ω)*	*160 Meters*	*80 Meters*	*40 Meters*	*20 Meters*	*10 Meters*	*6 Meters*
16:1	3.125	21	21	19	No Match	<10	
		<1.5:1	<1.5:1	<1.5:1		<1.5:1	
8:1	6.25	16	18	20	24	23	
		<1.5:1	2.1:1	<1.5:1	<1.5:1	<1.5:1	
4:1	12.5	11	12	15	17	23	
		<1.5:1	<1.5:1	<1.5:1	<1.5:1	<1.5:1	
2:1	25	<10	11	21	18	26	
		<1.5:1	<1.5:1	<2:1	<2:1	<1.5:1	
1:1	50	<10	<10	<10	<10	12	29
		<1.5:1	<1.5:1	<1.5:1	<1.5:1	<1.5:1	<1.5:1
2:1	100	<10	<10	<10	13	14	
		<2:1	<2:1	<1.5:1	<1.5:1	<1.5:1	
4:1	200	No Match	<10	<10	16	10	
			2.1:1	<1.5:1	<1.5:1	<1.5:1	
8:1	400	No Match	<10	10	16	18	
			2.1:1	<1.5:1	<1.5:1	<1.5:1	
16:1	800	<10	<10	14	30	58	
		<1.5:1	<1.5:1	<1.5:1	<1.5:1	<2:1	

is less than 2:1. In some cases they won't be right (and a new tune will be initiated), if a different antenna is used, for example, but their concept is that this tuner is out where the antenna is and thus should see the same impedance for a given frequency each time that frequency is employed.

SGC MAC-200 Multiple Antenna Controller

This device combines a 200 W autotuner, a five port automatic or manual antenna switch, power and SWR meters and a balun in one compact package. This is a nice unit and quickly grew on me in operation. It has enough controls and indicators to keep me entertained even when the bands aren't open.

For some time, most manual tuners have had provisions for switching antennas as well as tuning them. This is very handy, since even those with just one antenna should have a dummy load to switch to for tune up. I have no numbers, but I would guess more hams have more than one HF antenna than have only one. I don't have fancy HF antennas, but I have a G5RV I use on 80 through 10, a Lazy-H, perpendicular to the G5RV for 30 through 10 meters and a 70 foot wire vertical for use when it makes sense (not often in my part of New England).

With the MAC-200, I can memorize which antenna to use on which band. It switches antennas on the first dot of a CW string (full power—no problem) and I'm there. As noted, at my station, on some bands the antenna is a function of the direction to the distant station, I can just touch the MANUAL button and I can select a different antenna by touching a button numbered 1 to 5.

As configured, antenna one is intended for balanced feed, antenna two has a terminal for a single wire feed, and three through five are terminated in UHF (SO-239) coax connector jacks.

The separate meters for power and SWR are handy. The SWR meter is especially convenient in that it computes and indicates SWR independent of power level without an adjustment. The manual warns that the meters are not of the precision type and I can attest to that. Their meter indicated 80 W while my Bird 43 showed 100. This is still very useful to let you know if all is well.

This is a handy unit, in a cabinet matching the cross section of the SGC-2020 transceiver (but somewhat longer), it can be made to fit in most shacks. In mine it can slide beneath the shelf that holds my equipment three inches above the desk, for example.

The one limitation some may have is it provides a "typical" match of 2:1. Well 2:1 is fine for some transmitters, while others may start to "fold back" above 1.5:1 and this may be a problem if yours is in that group. On the other hand, looking at the data it is clear that most of the time it was below 1.5:1 with our loads.

Our original unit remembered which antenna to use on each band, but didn't memorize tuner settings. A warranty replacement unit had a flawless memory function.

Manufacturer: SGC Inc, 13737 SE 26th St, Bellevue, WA 98005; tel 425-746-6310; fax 425-746-6384; **www.sgcworld.com**. 2004 price: SG-237, $360; Smartlock remote control, $59; MAC-200, $360.

Table 14-11
SGC MAC-200 Desktop Automatic Antenna Tuner and Controller

Manufacturer's Specifications	*Measured in ARRL Lab*
Input impedance range: 5-1000 (feed line) 0.2-5000 (long wire).	See below.
Output SWR range: 2:1 typical.	See below.
Frequency coverage: 1.8 to 60 MHz.	As specified.
Input power: 1.5 to 200 W.	Tested at 50 W.
Power requirements: 10 to 18.5 V dc, 230 mA. Idle 240 mA, max 490 mA at 13.8 V dc (meter light off)	Idle 280 mA, max 530 mA at 13.8 V dc (meter light on)

Measured power loss into resistive loads (%) / Input SWR at match:

SWR	*Load (Ω)* *6 Meters*	*160 Meters*	*80 Meters*	*40 Meters*	*20 Meters*	*10 Meters*	*6 Meters*
16:1	3.125	No Match	39	24	<10	<10	
			<2:1	<2:1	<1.5:1	<1.5:1	
8:1	6.25	No Match	16	18	15	30	
			<1.5:1	<1.5:1	<1.5:1	<1.5:1	
4:1	12.5	<10	<10	<10	18	27	
		<1.5:1	<1.5:1	<1.5:1	<1.5:1	<1.5:1	
2:1	25	<10	<10	<10	<10	25	
		<1.5:1	<1.5:1	<1.5:1	<1.5:1	2:1	
1:1	50	<10	<10	<10	<10	12	27
		<2:1	<1.5:1	<1.5:1	<1.5:1	<2:1	<2:1
2:1	100	<10	<10	<10	<10	14	
		<1.5:1	<2:1	<2:1	<2:1	<1.5:1	
4:1	200	<10	<10	<10	<10	14	
		<1.5:1	<1.5:1	<1.5:1	<1.5:1	<2:1	
8:1	400	<10	<10	13	15	17	
		<1.5:1	<1.5:1	<1.5:1	<1.5:1	<1.5:1	
16:1	800	No Match	22	14	25	31	
			<1.5:1	<1.5:1	<1.5:1	<1.5:1	

Medium to High Power Auto Antenna Tuners — The Evolution Continues

Reviewed by Joel R. Hallas, W1ZR
QST *Technical Editor,*
QST *August 2006*

We last looked at a selection of automatic antenna tuners in May 2004 (see previous section). At that time, we picked four examples, two designed for remote operation and two desktop units. While different in many ways, they all were limited to 100 to 200 W. Higher powered automatic antenna tuners have been available, but they were either built into high powered amplifiers (ICOM or Yaesu, for example), were designed for remote operation as in the SGC SG-235, or have been discontinued, as in the case of the Ten-Tec 253.[2]

High powered automatic antenna tuners initially appeared in the 1980s — the Heath 2500, J.W. Miller AT2500, and Daiwa CNA-1001 — but they were not as sophisticated as the units reviewed here, requiring some manual adjustment or presetting of the inductor for best operation.[3,4,5]

Modern solid state transceivers and linear amplifiers with their "no tune" output stages have been well received, especially by those of us who grew up in the vacuum tube era.

The typical transmitter of that time required careful adjustment of the transmitter TUNE, LOAD and DRIVE controls, at a minimum, every time we changed frequency. Failure to do it right could result in destruction of the final amplifier tubes — sometimes a pricey proposition. The other side of the coin is that those transmitters could be adjusted to match antenna loads with a much higher SWR than the current crop of radio gear.

The modern no-tune feature generally means "no tune if the SWR is 1.5:1 or less," something that often doesn't fit with real world antennas and wide amateur bands. The answer has been an antenna system matching unit, often called an antenna tuner, even though many would argue that it doesn't really tune the antenna — rather it transforms the impedance at the bottom of an antenna system to the 50 Ω the radio equipment wants to operate into. Setting semantics aside, it seems that the controls we used to have to adjust haven't disappeared but have moved from the radio to another box — the antenna tuner.

Enter the Automatic Antenna Tuner

To extend the no-tune concept all the way to the antenna requires a no-tune, or *automatic*, antenna tuner. As noted, these have been generally available for some time at the power levels of modern transceivers, Each of these tuners can effectively add an automatic antenna matching system to your medium to high power HF station, at least up to their power limits. Honor the caveats and you will appreciate the freedom they provide.

For this review we have selected three desktop models that span the medium to high power range and highlight some other differences as well. While they all fill the same spot in a station block diagram, they are quite different in several respects and thus should not be directly compared on a 1:1 basis. Rather, determine if one or more will meet your needs, desires and budget.

All of the tuners reviewed in the 2004 report shared the same adjustment mechanism — fixed inductors and capacitors switched by relays. The LDG and MFJ tuners reviewed here share that architecture as well, but with beefier components designed to meet the higher power requirements of their ratings. The Palstar AT-Auto is of a completely different design, a T network with a differential variable capacitor, half on each side of a shunting rotary inductor. The Palstar makes its adjustments via stepper motors rather than relays. Interestingly, while standalone tuners have tended to be of the relay type, many internal tuners have used motor driven capacitors. Motor driven components were also used in the high powered automatic tuners from the 1980s mentioned previously, so this is a time-tested approach. We'll look at each tuner in alphabetical order. These tuners from LDG, MFJ and Palstar offer the convenience of automatic tuning at medium to high power levels.

AT-AUTO
LDG
AT-1000
MFJ

Figure 14-21 — Medium power tuners from Palstar, LDG and MFJ.

LDG AT-1000 Automatic Memory Antenna Tuner

The LDG AT-1000 sits squarely in the middle of the pack, both in terms of price and power rating. The 1000 W level fits nicely with a good selection of popular, not quite legal limit, linear amplifiers, including a couple announced at Dayton in 2006. All of the tuners reviewed here cover 160 through 10 meters, but the AT-1000 offers operation on 6 meters at the 100 W level as well.

The LDG, in common with the other units, has memories to allow a rapid return to the last previously matched settings. In the case of the AT-1000, there are 200 memory locations and the tuner will reset to them in less than half a second. If the antenna you are tuning does not have a memorized setting that works, the tuner can spend up to 8 seconds finding a match, but will remember for the next time.

The LDG approach to memory management is different from some. Some others tuners store settings based on frequency. This is a great approach if you will be tuning a single antenna for each band. In the LDG AT-1000, the last 200 successful matches are stored independent of frequency. A new match request quickly cycles through the 200 to see if a match is found before it begins its tune algorithm. This is a particularly beneficial approach if you switch the tuner output to different antennas on the same band, since it doesn't have to relearn parameters for a particular frequency every time you change antennas. It also avoids the need for frequency measuring circuitry within the tuner.

The AT-1000 has a fairly Spartan front panel that doesn't immediately show its capabilities. LDG has made

Table 14-12
LDG AT-1000

Manufacturer's Specifications

Maximum power, 1000 W SSB, 750 W CW,
500 W digital, 100 W 6 meters.
20 W while tuning (100 W with foldback),
75 W (3:1 SWR), 125 W (1:1 SWR).
Minimum power for tuning: 5 W.
Frequency range: 1.8 to 54 MHz.

Tuning time: 1 to 8 seconds.
0.5 second if memorized
Input impedance: 6 to 800 ..
Power required: 11 to 15 V, 1 A.
Dimensions (height, width, depth):
3 × 13 × 9 inches.
Weight: 6 pounds.

Measured power loss into resistive loads (%) / Input SWR at match. Tested at 50 W.

SWR	*Load (Ω)*	*160 m*	*80 m*	*40 m*	*20 m*	*10 m*
16:1	3.125	No match n/a	No match n/a	No match n/a	No match n/a	No match n/a
8:1	6.25	No match n/a	No match n/a	* **	20 1.6:1	22 **
4:1	12.5	12 2.3:1	* **	* **	* **	18 2.2:1
2:1	25	* **	* **	* **	* **	* **
1:1	50	* **	* **	* **	* **	* **
2:1	100	* **	* **	* **	* 2.1:1	* **
4:1	200	* **	* **	* **	* **	* **
8:1	400	16 2.1:1	* **	* **	22 2.1:1	17 **
16:1	800	No match n/a	18 **	17 **	55 **	No match n/a

*Power loss less than or equal to 10%.
**Matched SWR less than or equal to 1.5:1.



Figure 14-23 — Rear panel connections on the LDG AT-1000.



Figure 14-22 — Front panel of the LDG AT-1000.



Figure 14-24 — Interior circuitry of the LDG AT-1000.

maximum use of the cross needle wattmeter on the front panel, going further with information delivery than I would have imagined with such a straightforward display. The cross needle wattmeter has two scales, reading forward (1000 W) and reflected (180 W) power simultaneously. The point at which the meter pointers cross is a third scale directly reading in SWR. So far it's just like every other cross needle meter we've seen.

What sets the AT-1000 apart is that LDG has additional indicator functionality that appears as a set of semaphore signals between tuner and operator. Each needle is driven independently in this mode and each can vary in speed and position as it fills you in on the tuner's condition and status. For example, if during a tuning cycle, both arms quickly raise fully (in surrender?) it means too much power has been supplied to allow it to safely tune. It then switches to bypass mode and goes on break until you reduce power and restart the tuning cycle.

Another feature is the ability to change the inductance and capacitance parameters manually. This can be a benefit in at least two ways. First it allows manual fine trimming of the tuning in case you want a better SWR than the tuner finds automatically. Manual tuning can also be used to peak up the receive signal strength if you're listening to a station on a frequency that you can't transmit on. This could include shortwave broadcast frequencies or bands or segments for which you don't yet have license privileges.

How'd it Work? At my station the AT-1000 did everything I asked of it without problems. My antennas tuned satisfactorily on all bands. Memorized settings were recalled without difficulty in a fraction of a second. The 15 page multicolor manual does a good job of describing how to set up and use the tuner. A table of "meter bounce codes" is included, and you will likely want to keep a copy at hand, unless your memory is much better than mine. ARRL Lab test results are shown in **Table 14-12**.

Manufacturer: LDG Electronics, 1445 Parran Rd, St Leonard, MD 20685; tel 410-586-8475; **ldg@ldgelectronics.com**; **www. ldgelectronics.com**. 2006 price: $599.

MFJ-994 Intellituner Automatic Antenna Tuner

At first glance, the MFJ-994 appears to be a very similar tuner to the AT-1000. It has almost the same controls and indicators as the LDG tuner, although they are on opposite sides of the front panel. It makes use of a similar set of semaphore indications. The major differences are:

- The MFJ tuner has a lower maximum power rating (600 vs 1000 W PEP and 300 vs 750 W CW) and a correspondingly lower price.
- The '994 provides an interface to allow operation using the TUNE button on Alinco, ICOM, Kenwood or Yaesu radios equipped to control an antenna tuner. An accessory cable is required to activate this function.
- The '994 has more memory locations, all indexed by frequency.
- The '994 offers a choice of two power meter scales, 3000 or 300 W forward power with corresponding 600 or 60 W reflected power at full scale.

During the review process, we determined that the MFJ-994 has now been superseded by the MFJ-994B. The functionality and operation are similar, with the same tuning and switching elements. The main difference seems to be the memory management function, with the B


MFJ ENTERPRISES, INC. STARKVILLE, MS USA
TRANSMITTER
POWER 12VDC 1A
REMOTE PORT
RADIO INTERFACE
GROUND
ANTENNA
WIRE
Do not connect WIRE and ANTENNA at same time!

Figure 14-26 — Rear panel connections on the MFJ-994.



Figure 14-25 — Front panel of the MFJ-994.



Figure 14-27 — Interior circuitry of the MFJ-994.

Table 14-13
MFJ-994

Manufacturer's Specifications
Maximum power, 600 W PEP SSB, 300 W CW, 20 W while tuning (100 W with foldback).
Minimum power for tuning: 10 W.
Frequency range: 1.8 to 30 MHz.
Input impedance: 12 to 800.
Power required: 12 to 15 V, 1 A.
Dimensions (height, width, depth) 2.8 × 10.1 × 9.2 inches.
Weight: 3.7 pounds.

Measured power loss into resistive loads (%) / Input SWR at match. Tested at 50 W.

SWR	*Load (Ω)*	*160 m*	*80 m*	*40 m*	*20 m*	*10 m*
16:1	3.125	No Match	No Match	10	12	*
		n/a	n/a	2.6:1	2.2:1	2.0:1
8:1	6.25	13	13	*	13	15
		2.4:1	1.8:1	**	**	2.2:1
4:1	12.5	*	*	*	*	15
		**	**	**	**	1.8:1
2:1	25	*	*	*	*	*
		**	**	**	**	**
1:1	50	*	*	*	*	*
		**	**	**	**	**
2:1	100	*	*	*	*	*
		**	**	**	**	**
4:1	200	*	*	*	*	*
		**	**	**	**	**
8:1	400	*	*	*	14	*
		**	**	**	**	1.8:1
16:1	800	*	17	16	11	*
		**	**	**	1.8:1	1.7:1

*Power loss less than or equal to 10%.
**Matched SWR less than or equal to 1.5:1.

model including a virtual memory function said to store up to 10,000 frequency data points versus 1000 in the earlier '994. The other difference noted in the specs is that the new one can tune with a minimum of 2 W, versus 10 W in the original.

The MFJ has some control flexibility hidden behind its few buttons. The "tuned" threshold can be set to either 1.5:1 or 2:1. With the 1.5:1 setting, the match is closer, but it will take a bit longer to find. While 2:1 should happen more quickly, some radios won't put out full power into a 2:1 load. It's nice to have the choice. An "auto tune" function is also provided that causes the tuner to activate if the SWR goes above your threshold by a user selectable 0.5, 1.0 or 1.5. This is handy as you change frequency, but be careful it doesn't drop into tuning mode while you are at full power. Pushing in the AUTO button unambiguously disables the auto tune function, entirely avoiding this concern.

In Summary The MFJ-994 did everything just as promised. It showed no problem handling the 600 W we could deliver, the only tuner of the group that we could test to the limit! It was too quick for me to stopwatch the tuning speed, but my sense was, as expected, that the frequency based memories were a bit quicker if all operations were using the same antenna. It also appeared that the MFJ relays were a bit quieter than the other relay operated tuner, but that could have been because there were generally fewer cycles needed before it was matched. ARRL Lab test results are shown in **Table 14-13**.

MFJ provided a comprehensive 23 page, well illustrated, instruction manual that was clear in its description of how the unit operated and what to expect of it.

Manufacturer: MFJ Enterprises, 300 Industrial Park Rd, Starkville, MS 39759; tel 662-323-5869, fax 662-323-6551; **www. mfjenterprises. com**. 2006 price: $359.95. Auto tuner radio interface cables: MFJ-5124A for Alinco, $19.95 MFJ-5124I for ICOM, $19.95 MFJ-5124K for Kenwood, $59.95; MFJ-5124Y for Yaesu, $59.95.

PALSTAR AT-AUTO

As noted previously, the AT-Auto is of a different architecture than the other tuners in this review. Palstar is noted for its line of high quality manual antenna tuners, so it should not be a surprise that Palstar decided to build its first auto tuner using the same type of in-house constructed parts that have been successful in their other offerings.

This is a large and complex device with features that I haven't seen before in any tuner. The first feature you might notice is the cross needle wattmeter that takes up the left side of the front panel. This is the same display and circuitry built into their PM2000A standalone wattmeter. It provides both average and peak forward and reflected power readings at full scale power levels of 3000/600 (forward/reflected) and 300/60 W. This is an upgrade to the Palstar WM150 wattmeter reviewed in July 2002 with the addition of a PEAK HOLD setting with a 2 second hold time.

The right side of the panel includes a two-line liquid crystal display (LCD), a knob for manual tuning (more later), MANUAL/AUTO and SELECT buttons. It is on this side of the panel that interesting things happen. As with most auto tuners, you apply power and it starts to match your antenna to 50 Ω. What's different with the AT-Auto's tuning sequence is that it first measures frequency, tells you the operating frequency and then politely asks you to turn off your transmitter while it finds a close match. It has a default set of L and C values for each frequency and runs its quiet motors until they are in range. It then asks for another dose of RF to refine the tune. Every time it does this, like a good smart machine, it memorizes its settings and uses them the next time you use that frequency. This approach minimizes interference to others.

A well thought out and, to my knowledge, unique feature of this tuner is its use of a radio interface. This, and many other auto tuners, make use of a radio's tuner interface to initiate the tuning sequence and cause a reduced-power tune signal to be sent from the radio. The AT-Auto has an additional connection from the radio's CAT (computer interface) port. The CAT port provides frequency data from the radio to the tuner. As you tune the receiver, the tuner indicates the frequency and follows along with either its default or memorized values. This means that, if you've been on that frequency before, the tuner will be tuned before you hit the key or PTT! If you haven't been there before, it will use its default values and still be pretty close.

This is particularly handy if you are listening to a frequency at which you aren't licensed to transmit, for example WWV or shortwave broadcast frequencies. The cable for ICOM radios is provided. You do have to think a bit while you use it (yes we have to be even smarter than our smart devices!). The CAT frequency data reflects the frequency of whichever VFO is active. If you are operating split frequency, it will tune back and forth between the two VFO frequencies as you switch between them. This is not likely much of an issue if you are operating in the typical "up five" (VFOs just 5 kHz apart) environment, but could be a disaster if you are operating cross-band split for some reason. The solution — while you have the VFO on your transmit frequency and the tuner properly tuned, tap the MANUAL/AUTO button so that it will be in manual mode and the automation will take a break.

The CAT function, as we wrote this, is available only for radios that support ICOM's CI-V protocol. Palstar expects to have cables and software upgrades to allow interoperation with Kenwood and Yaesu radios soon. Speaking of software, Palstar kindly provides a 9-pin serial cable designed to allow you to install



Figure 14-29 — Rear panel connections on the Palstar AT-Auto.



Figure 14-28 — Front panel of the Palstar AT-Auto.



Figure 14-30 — Interior circuitry of the Palstar AT-Auto.

upgraded software when it is available. As we write this, there is no information on how to do this in either the manual or on the Palstar Web site. On the other hand, there is no new software either, so presumably when there's something new to download, they will tell us how to do it. We did successfully download upgraded software for their ZM-30 Antenna Analyzer during that review, so they seem to be able to deal with the process. We understand from Palstar that revised firmware to improve 10 meter operation has been developed and will be available shortly.

Another nice feature of the AT-Auto is that it has provisions for switch selection (via the front panel SELECT button) of either a balanced (through a 4:1 balun at the output) or an unbalanced (coax connected) antenna. The switch doesn't just insert the balun, but provides two completely independent antenna connections, so both can be always available. The memory associates the settings with each antenna port separately, so if you switch between antennas while on the same band, it thoughtfully remembers the settings for each.

New production tuners will also include BYPASS selection. A factory upgrade is said to be available for early production units. Want to do it Yourself? Poke the MANUAL/AUTO button and you are into manual tuning mode. The single knob below the LCD display is used to change the inductance or capacitance. It comes up ready to tune the C; push the knob in briefly and it changes the L. The value of L and C are displayed on the LCD panel as you change them, so you can record the values for later reference. It moves the adjustments via the stepper motors, so minimum effort is required — no heavy cranking needed.

So how'd it work? We really liked the concept of this tuner. By its nature it can provide finer adjustment than the relay types we have seen, although their resolution could be made arbitrarily fine with additional relays and smaller increments of C and L, and higher cost. We also liked the quietness of the motors compared to the clacking relays. The downside can be tuning time. As noted above, with a CATconnected radio and memorized settings it rapidly follows you as you tune. A change in bands can take longer. We measured the following times to retune between bands:

From (Meters)	*To*	*Tune Time (Seconds)*
80	40	11
40	30	4
30	20	3
20	15	2
15	10	2
160	10	45

The times shown are between memorized settings. To tune from a default setting to a finely tuned condition takes about 2 additional seconds if there isn't already a memorized setting for the frequency. It seems especially quick with the CAT function, since it feels like it's all tuned and waiting for you to catch up!

The AT-Auto comes with a well illustrated 20 page manual. The manual assumes you know why you wanted an antenna tuner and where you are going to connect it. This wasn't much of a problem since it has such an informative display, although, if you're expecting "open left flap, remove tuner from box..." type instructions, this manual isn't quite up to that standard.

On the down side, we had just a few disappointments. Initially, the tuner wouldn't match my antenna on 12 and 10 meters. On 12 meters, my measured SWR was 6:1 at the tuner. While it couldn't find a perfect match, and announced MATCH NOT FOUND! on the LCD panel, it actually got to within a 2.4:1 SWR, which my radio found acceptable. On 10 meters my antenna showed an SWR of 3:1 and the best the tuner could do was 2.78:1. In both of these cases, the LCD panel noted that the inductance was at L=000.

This suggested to me that it was the particular value of complex impedance rather than the SWR that was causing the problem. I put in an additional 6 feet of 50 Ω coax to move "around the Smith Chart" and the tuner was then able to find a perfect match in both cases. This is a good trick to keep in mind if faced with this kind of problem with any tuner. The indicator was very helpful in pointing me in the right direction.

A less significant problem was that the frequency metering system required more power to determine the frequency on the higher bands. On 160 through 15 meters, the 10 W that the ICOM transceiver put out in TUNE mode was plenty to allow the frequency to be read and the tune function to be initiated. On 12 and 10 meters, at 10 W, I received a FREQUENCY ERROR CHECK CARRIER LEVEL message on the LCD. It took more power to allow the frequency to be read. This was no problem with another transceiver that allows me to crank it up as far as I want when the TUNE button is pressed, but the ICOM had a fixed level. A quick fix is to switch to AM or FM mode to put out more power. Just hit the bar on your PTT microphone or use a straight key in CW mode.

Upon further investigation, I found that it worked fine on all bands with 10 W to a matched load. At some impedances, apparently there was not enough signal for the measuring circuits. Another workaround would be to manually set it within range and then let the AT-Auto fine tune to perfection. A handy feature of this tuner is that it can be tuned at 1500 W with no relay contacts to burn. This is good since it sometimes notices a bit of reflected power and trims the adjustment after you turn on the amplifier. ARRL Lab test results are shown in **Table 14-14**.

Manufacturer: Palstar Inc, 9676 N Looney Rd, Piqua, OH 45356; tel 800-773-7931, fax 937-773-8003; **info@palstar.com**; **www.palstar.com**. 2006 price: $1195.

In Summary

Each of these tuners did what they said they would over most of their frequency range and each could be of benefit to operators using higher power than that handled by other automatic antenna tuners. Some care needs to be taken with their operation, beyond that found in the lower

Table 14-14
Palstar AT-Auto

Manufacturer's Specifications

Maximum power: 1500 W single tone.
Frequency range: 1.8 to 30 MHz.
Input impedance: 160 to 20 meters, 1200 ±j1200; 15 to 10 meters 1000 ±*j*1000.
Tuning time: 1-30 seconds.
Dimensions (height, width, depth): 5.5 × 12.5 × 16 inches.
Weight: 25 pounds.

Measured power loss into resistive loads (%) / Input SWR at match. Tested at 50 W.

SWR	*Load (Ω)*	*160 m*	*80 m*	*40 m*	*20 m*	*10 m*
16:1	3.125	54 **	33 **	19 **	* **	No Match n/a
8:1	6.25	42 **	24 **	15 **	12 **	No Match n/a
4:1	12.5	30 **	17 **	14 **	* **	No Match n/a
2:1	25	24 **	12 **	* **	* **	26 **
1:1	50	16 **	* **	* **	* **	* **
2:1	100	13 **	* **	* **	* **	20 **
4:1	200	11 **	* **	* **	12 **	43 **
8:1	400	12 **	* **	11 **	23 **	42 **
16:1	800	16 1.6:1	25 **	24 **	55 **	49 **

*Power loss less than or equal to 10%.
**Matched SWR less than or equal to 1.5:1.

powered units, because of the power involved and particularly because of the difference between "tuning power" and "operating power." Each unit is specified to be tuned using reduced power from the exciter at somewhere in the 10 to 100 W range.

Each tuner finds a match at that power level and then it should be safe to switch on the linear amplifier — but is it? With the MFJ and Palstar tuners, there were conditions under which it would initiate the tuning cycle again at full power, even after being within specification at the lower tuning power. The reason is likely a combination of a larger sample of RF to make reflected power measurement and nonlinearity of the detectors, not surprising for analog circuitry. Different tuners will react differently under this circumstance. The Palstar actually doesn't mind tuning at 1500 W and will calmly trim up without a whimper. The MFJ tuner will note that it is tuning above the specified tuning power spec and switch to bypass — whoops, you had the linear pre-tuned with a dummy load so that it would be ready to go, and now it sees a 9:1 SWR, or whatever your antenna has, going directly to the amplifier. This could cause a catastrophic reaction in your amplifier! The LDG tuner is different in this regard. It only initiates a tune cycle if the TUNE button is pressed.

So what to do? There are two potential solutions. One, manually trim up the tuning for an even lower SWR using the L and C up and down buttons. If the reflected power is fully nulled, it should avoid this problem. The other approach is to switch the tuner to manual mode after it finds its initial match. That will prevent it from automatically retuning while high power is applied. Or do both. Arguably this changes tuner operation from "auto" to "semi-auto," but I recommend it for any high power relay switched tuner. The consequences of not doing so could be extreme to either the amplifier or the relay contacts or both.

A New Generation of Balanced Antenna Tuners

Reviewed by Joel R. Hallas, W1ZR
QST *Technical Editor*
QST *September 2004*

A new breed of antenna tuner available in different flavors from multiple manufacturers addresses concerns about using baluns with high SWR to feed balanced antenna systems. Paul Danzer's article in the April 2004 issue of *QST* brought to paper a concern many of us have had for some time — the use of baluns at the output of antenna tuners.[6] As noted in his article, if the balanced load is near the balun's design impedance (typically 200 Ω for the usual 4:1 balun) all is well.

Unfortunately, the typical random sized center fed antenna with random length ladder line feed has an impedance at the feed point that varies dramatically with frequency. The result can be heating and loss (and occasional damage) at the balun. These effects were well documented in a series of *QST* articles by Frank Witt and later in a performance evaluation of unbalanced tuners with both balanced and unbalanced loads.[7,8]

So How Do We Fix the Problem?

As Danzer noted, the classic solution has been the use of an inherently balanced tuner. The commercially manufactured E.F. Johnson Matchbox tuners of the '50s worked reasonably well in their day, and over the bands that they covered (we didn't have the 60, 30, 17 and 12 meter bands back then). Now at least three manufacturers have begun offering balanced antenna tuners of a different configuration. For this review we selected the MFJ-974H and the Palstar AT1500BAL and AT4K. Interestingly, each of the three uses a different architecture, and each is different from the design of the old Matchbox!

In addition to those units, SGC has announced a low power self-contained auto-tuner, the SG-211, which shares the design concept of the AT4K and will be the subject of an upcoming Short Takes column. We thought it would be good to evaluate the performance of the medium and high-power units and provide a comparison to the old Johnson tuner.

What's in the New Tuners?

Glad you asked! As noted, each of the tuners uses a different design configuration. Each can be directly compared to some of the common unbalanced configurations. Note that the power ratings and price of the Palstar tuners put them in a different category from the MFJ units and thus, direct comparisons may not be appropriate. Both the MFJ and the Palstar AT1500BAL are fully balanced tuners — the MFJ a dual T section design with shunt L, and the Palstar a dual L section with shunt C. The Palstar AT4K tuner takes a completely different approach. It uses the insulated unbalanced scheme suggested in Paul's article and described in detail in *The ARRL Antenna Book*.[9]

The relationship of the designs to their more commonly encountered unbalanced configurations are shown in simplified schematics in **Figures 14-32** through **14-33**. The other differences between the units are in their ratings. The MFJ tuner covers 160 through 6 meters, while the Palstar tuners top out at 10 meters. Both Palstar tuners are rated at 1500 W or greater (the AT4K has a reduced rating below a 25 Ω load) while the MFJ tuner is rated at 300 W PEP, 150 W CW.

The ratings of the Johnson Matchboxes were established in a day when amateur power levels were specified based on average dc power *input*, rather than the current PEP RF *output*



Figure 14-31 — From the top the MFJ-974H, the Palstar AT1500BAL and AT4K. On the right, they are being scrutinized by their logical ancestor, the Johnson Matchbox.


Hi - Lo Z
Balanced
50 Ω Unbalanced
50 Ω Unbalanced
Hi - Lo Z
Balanced
QS0409-ProdRev01
(A)
(B)

Figure 14-32 — At A, the traditional balanced antenna tuner. At B, the Johnson Matchbox antenna tuner. Simplified view without bandswitching.

power. A "275 W" Johnson matchbox was thus rated to work with transmitters running 275 W dc input, or about 200 W average output. This was in the day of plate modulated AM service, so that rating further translates to 800 W PEP under today's rules. Similarly, a "kW Matchbox" would likely be rated today as a 3 kW PEP tuner.


QS0409-ProdRev02
(A)
50 Ω
Unbalanced
Hi - Lo Z
Unbalanced
(B)
50 Ω
Unbalanced
1:1 Balun
50 Ω
Balanced
Hi - Lo Z
Balanced
(C)
50 Ω
Unbalanced
1:1 Balun
50 Ω
Balanced
Hi - Lo Z
Balanced

Figure 14-33 — At A, an unbalanced T-network tuner. At B, a balanced T-network tuner. At C, an unbalanced T-network tuner for balanced loads.


QS0409-ProdRev03
Lo Z
Hi Z
50 Ω
Unbalanced
Hi - Lo Z
Unbalanced
(A)
50 Ω
Unbalanced
1:1 Balun
50 Ω
Balanced
Lo Z
Hi Z
Lo Z
Hi Z
Hi - Lo Z
Balanced
(B)

Figure 14-34 — At A, an unbalanced L-network tuner with switched capacitor. At B, a balanced L-network tuner with switched capacitor.

MFJ-974(H) Balanced Antenna Tuner

MFJ provides two versions of their '974, with ('974H) and without ('974) the capability to cover 160 meters. Both are rated at 300 W PEP, and 150 W CW. At only 7½ inches wide, it takes up a small amount of desk space. Interestingly, it has about the same shape as the old 275 W Johnson Matchbox, but is 1 to 2 inches smaller in each dimension. As noted above, this unit uses a T section design as in **Figure 14-33B**, so it is not necessary to switch capacitors from one side to the other as the impedance changes from high to low.

The inductor is varied by selecting among 12 steps. The H model has an extra inductance for 160 meters that changes the tuning range as needed. A cross-needle two-range (30 and 300 W full scale) power/SWR meter can be set to read peak or average power. Both the power level and null matched the meter on my transceiver quite closely. The capacitors are direct (1:1) drive, with plastic gearing between the ganged units. I found them easy to turn and to get a null. I used the old trick of tuning for maximum receive signal, first with the L switch, then with the capacitors.

MFJ provides a page of nominal settings by band that you may find helpful. When you switch to adjusting the tuner while transmitting, be sure to note their caution about not changing the inductor switch with power applied. You may burn the contacts otherwise. I also make it a practice to always tune at reduced power to avoid hitting my finals with a heavy mismatch at full power. When you have it set, turn up the power and confirm that all is well.

One caution that applies to all T section tuners is to note that multiple settings can result in low SWR. Unfortunately, some will have higher losses than others. The rule of thumb is to use the setting with the smallest inductance (the L switch position on

Table 14-15
MFJ-974H Balanced Antenna Tuner

Manufacturer's Specifications	*Measured in ARRL Lab*
Input load range: 12 to 2000 Ω.	See below.
Output SWR range: Not specified.	See below.
Frequency coverage: 1.8 to 54 MHz.	See below.
Input power: 150 W average, 300 W PEP.	Not tested.
Size: 6 × 7.5 × 9 inches (HWD).	

SWR	*Load (Ω)*		*160 Meters*	*80 Meters*	*40 Meters*	*20 Meters*	*10 Meters*	*6 Meters**
		Power Loss %	55	41	32	20	16	
8:1	6.25	SWR BW %	0.9	0.6	1.0	2.0	2.0	Not Tested
		Imbalance**	0	0	0	0	0	
		Power Loss %	40	33	23	<10	10	
4:1	12.5	SWR BW %	0.6	0.9	1.4	2.8	3.4	Not Tested
		Imbalance	0	0	0	0	0	
		Power Loss %	25	22	<10	<10	<10	
2:1	25	SWR BW %	0.8	1.1	3.2	4.9	2.4	Not Tested
		Imbalance	0	0	0	0	0	
		Power Loss %	22	15	32	20	<10	<10
1:1	50	SWR BW %	1.1	1.4	2.1	2.1	12	10
		Imbalance	0	0	0	0	0	0
		Power Loss %	18	<10	<10	<10	<10	
2:1	100	SWR BW %	1.1	1.7	4.1	7.0	25	Not Tested
		Imbalance	0	0	0	0	0	
		Power Loss %	17	<10	<10	<10	<10	
4:1	200	SWR BW %	1.1	2.8	2.5	9.1	10	Not Tested
		Imbalance	0	0	0	0	0	
		Power Loss %	12	<10	<10	<10	<10	
8:1	400	SWR BW %	1.5	3.4	7.5	7.0	3.7	Not Tested
		Imbalance	0	0	0	0	0	
		Power Loss %	10	<10	<10	<10	<10	
16:1	800	SWR BW %	1.9	4.3	8.3	7.7	3.7	Not Tested
		Imbalance	0	0	0	0	0	
		Power Loss %	<10	<10	<10	10	11	
32:1	1600	SWR BW %	2.1	2.6	5.6	4.4	3.0	Not Tested
		Imbalance	0	0	0	0	0	

Notes
Power losses are expressed as a percentage. A 10% power loss represents less than half (0.46) a dB.
The SWR bandwidth is the percentage of the measurement frequency that can be changed with the SWR staying under 1.5:1.
*The ARRL test fixture is only usable at 50 . on 6 meters.
**As defined in F. Witt, "Evaluation of Antenna Tuners and Baluns—An Update," *QEX*, Sep-Oct 2003, pp 3-14.

this tuner) and highest capacitance that will provide a match. One limitation of the switched rather than roller inductor is that you can't get values in between. I didn't find that much of a problem, as I was always able to get to 1.5:1 or better SWR with my antennas.

As you make adjustments, I suggest you log the settings for each frequency in a table such as the one supplied in the back of the manual. You may want to make photocopies or set up a spreadsheet so you will be able to repeat the process for your next antenna. If you find that you can't get a match at some frequency, try adding 6 feet of ladder line at a time. The different length will move the impedance around and may solve the problem, but you will have to retune on the other bands and hope to find a length that will tune properly on all bands.

Balanced loads are connected via standard (¾ inch) spaced multipurpose binding posts. These accept wire ends, or dual banana plugs, a handy connector for balanced feed lines at this power level. The '974H also provides a capability to match unbalanced loads and provides a coax connector for that purpose. It is necessary to provide a jumper between the lower balanced load binding post and the ground terminal to complete the unbalanced hookup. Note that the output is not switched, so an antenna should be connected to either the coax connector or the balanced jacks, but not both.



Figure 14-35 — MFJ-974H, inside view.

Note that while the '974 is specified to match a wide range of impedances on 6 meters, neither the Lab nor W1ZR could test at any impedance other than 50 Ω. I tried the unbalanced connection arrangement with my coax-fed G5RV. It worked fine until I tried it on 160 meters, not one of the bands the antenna is supposed to operate on. I was able to quickly find a match at low power. When I turned up the power past 70 W, arcing was evident inside the unit. I opened it up and was surprised to find that rather than the expected arcing tuner element, I found the arcing source was at the metering circuit board. Measured Lab data is shown in **Table 14-15**.

The unit went back to MFJ for repair under their warranty. Upon return, it worked fine at 100 W (my maximum power with the transceiver) and I was told by MFJ that a signal wire had been dressed too close to the meter board and arced. It was repositioned and MFJ installed the intended tie-wrap to hold it away from the meter board. The tuner was retested and had exhibited no problems.

Manufacturer: MFJ Enterprises Inc, 300 Industrial Park Rd, Starkville, MS 39759; tel 800-647-1800; fax 662-323-6551; **www.mfjenterprises.com**. 2004 price: MFJ-974, $179.95; MFJ-974H, $199.95.

Palstar AT4K Antenna Tuner

Unlike the other tuners in this review, the AT4K might best be described as an unbalanced tuner designed to feed unbalanced or balanced loads. This sounds contradictory, but really isn't, as described in footnotes 1 and 6. If you just think of this tuner as a "four-terminal black box" (see **Figure 14-33C**) connecting a balanced load to a balanced source, followed by a 1:1 balun going to the transceiver, you may get the picture.

An unbalanced T section, isolated from ground within the box, performs the required impedance transformation to match the impedance at the bottom of the balanced transmission line to 50 Ω to operate properly through the internal balun. This tuner also provides a heavy duty relay to connect the common points of the input, output and inductor to the chassis to convert it to a typical T section tuner for unbalanced loads.

An additional feature, not found in any of the other tuners in this review, is antenna switching capability. The AT4K has a single pair of balanced output terminals, but also has three coax outputs. Two can be tuned, or switched to straight through, while the third provides straight though operation only. This is a great spot to connect a dummy load, or a well matched Yagi.

The inside view gives a sense of the heavy duty construction of this massive tuner. The rotary inductor is fabricated from silver plated strip stock, rather than the usual wire, and the rolling contact is designed to grip a significant portion or the coil, not just the edge. The inductor is driven by a smooth turn-count dial reading out to 1/10 of a turn and resetable in

Table 14-16
Palstar AT4K Balanced/Unbalanced Antenna Tuner

Manufacturer's Specifications	*Measured in ARRL Lab*
Input load range: 8 to 2000 Ω.	See below.
Output SWR range: Not specified.	See below.
Frequency coverage: 1.8 to 30 MHz.	See below.
Input power: 2500 W single tone.	Not tested.
Size: 5 × 15 × 16 inches (HWD).	

SWR	*Load (Ω)*		*160 Meters*	*80 Meters*	*40 Meters*	*20 Meters*	*10 Meters*	*6 Meters**
		Power Loss %	24	14	10	10	34	
8:1	6.25	SWR BW %	1.1	2.6	6.4	4.9	0.5	
		Imbalance	0.6	0.7	0	0.6	5.2	
		Power Loss %	12	<10	<10	<10	18	
4:1	12.5	SWR BW %	1.9	4.0	17	8.5	0.7	
		Imbalance	0	0.4	0	0.4	1.7	
		Power Loss %	<10	<10	<10	<10	<10	
2:1	25	SWR BW %	3.0	7.4	39	21	1.5	
		Imbalance	0	0.2	0	0.5	0	
		Power Loss %	<10	<10	<10	<10	<10	
1:1	50	SWR BW %	5.5	16	69	42	3.0	
		Imbalance	0.3	0	0	0.4	0.3	
		Power Loss %	<10	<10	<10	<10	<10	
2:1	100	SWR BW %	6.1	26	49	44	10	
		Imbalance	0.4	0	0	0	0	
		Power Loss %	<10	<10	<10	<10	37[1]	
4:1	200	SWR BW %	6.9	22	24	32	0.8	
		Imbalance	0.5	0	0	0	3.4	
		Power Loss %	<10	<10	<10	<10	Note 1	
8:1	400	SWR BW %	7.8	15	14	15		
		Imbalance	1.5	0.3	0	0		
		Power Loss %	<10	<10	<10	<10	Note 1	
16:1	800	SWR BW %	7.2	10	10	8.5		
		Imbalance	2.6	0.5	0	0		
		Power Loss %	<10	<10	<10			
32:1	1600	SWR BW %	4.4	6.9	5.6	No Match	No Match	
		Imbalance	4.9	0	0			

Notes

[1] According to the owner's manual for the AT4K, the matching range is limited on 10 meters. In testing, it was found that matches (SWR <1.5:1) could be obtained on 10 meters with some higher impedance loads by using a large amount of inductance. However, it is very likely that the tuner was close to self-resonance under these conditions, and this type of operation should be avoided due to the high losses in the tuner.

Power losses are expressed as a percentage. A 10% power loss represents less than half (0.46) a dB.

The SWR bandwidth is the percentage of the measurement frequency that can be changed with the SWR staying under 1.5:1.

between marks. As with its sister units, the capacitors are driven by 5:1 reduction drives with 0 to 100 logging scales.

One design challenge with a tuner built of these large parts is to keep the minimum capacitance low enough so the unit will meet specifications at 10 meters. As shown in the data, Palstar has done a reasonably good job with this, but the limitations should be noted. I found that this unit could match all my antennas, balanced or unbalanced, except on 17 and 10 meters where not all impedances are within range. Again, a change in transmission line length may move your impedance to a value within the tunable range.

The metering was consistent with my other wattmeters, both in position of reflected null and forward power. I was able to easily return to a previous setting using the resolution of the dial scales. Measured Lab data is shown in **Table 14-16**.


Figure 15-36 — Palstar AT4K, inside view.

Palstar AT1500BAL Balanced Antenna Tuner

The Palstar AT1500BAL is of the configuration shown in **Figure 14-34B**. It is a legal limit device and a look inside makes me believe that it can handle serious power. The rotary inductors, two edge-wound silver plated ball-bearing monsters, driven by a toothed fiberglass belt and turns counting dial take up a lot of the interior space. The rest is largely occupied by a 450 pF 4.5 kV variable driven by a smooth 5:1 vernier dial.



Figure 14-37 — Palstar AT1500BAL, inside view.

The inductors and capacitor are made in-house and work very well. I was particularly impressed with the resetability of the controls. The turns counter reads out to tenths of a turn, and can be easily reset to ½ a tenth out of the 32 turns end-to-end. The vernier drive has a dial with 100 divisions and no perceivable backlash. Once you make up a table of tuning values by frequency, retuning should be a snap. I found the tuner easy to use at W1ZR, matching all reasonable antenna configurations I tried. I am only able to test at the 500 W level and, as expected, encountered no difficulties.

The cross-needle meter (300 and 3000 W full scale ranges for forward average power) agreed closely with those on my equipment. One note, on many tuners, power is only required for meter lighting. On this unit, relays are used — both to switch capacitors from one end to the other and to switch in additional capacitance. The tuner will work only in the "high impedance/ no extra capacitance" mode if you neglect to plug in the

Table 14-17
Palstar AT1500BAL Balanced Antenna Tuner

Manufacturer's Specifications	*Measured in ARRL Lab*
Input load range: 160 to 20 meters, 2500 ± j2500 Ω.	See below.
20 meters 1000 ± j1000 Ω; 10 meters, 500 ± j500 Ω.	See below.
Output SWR range: Not specified.	See below.
Frequency coverage: 1.8 to 30 MHz.	See below.
Input power: 1500 W PEP.	Not tested.
Size: 6.5 × 12.5 × 15 inches (HWD).	

SWR	*Load (Ω)*		*160 Meters*	*80 Meters*	*40 Meters*	*20 Meters*	*10 Meters*	*6 Meters**
		Power Loss %	<10	<10	<10			
8:1	6.25	SWR BW %	No Match	No Match	9.9	6.6	5.4	
		Imbalance	0.3	0	0			
		Power Loss %	<10	<10	<10			
4:1	12.5	SWR BW %	No Match	No Match	1.3	1.3	10	
		Imbalance			0	0	0	
		Power Loss %	<10	<10	<10	17	<10	
2:1	25	SWR BW %	1.5	46	42	19	13	
		Imbalance	0	0	0	0	0	
		Power Loss %	<10	<10	<10	<10	<10	
1:1	50	SWR BW %	>100	>100	>100	>100	20	
		Imbalance	0.3	0	0	0	0	
		Power Loss %	<10	<10	<10	<10	<10	
2:1	100	SWR BW %	>100	54	58	56	61	
		Imbalance	0	0	0	0	0	
		Power Loss %	<10	<10	<10	<10	<10	
4:1	200	SWR BW %	>100	29	26	30	3.7	
		Imbalance	0.2	0	0	0	0	
		Power Loss %	<10	<10	<10	<10	13	
8:1	400	SWR BW %	17	23	18	20	1.7	
		Imbalance	0	0	0	0	0	
		Power Loss %	<10	<10	<10	<10	18	
16:1	800	SWR BW %	11	11	13	13	4.0	
		Imbalance	0	0	0	0	0	
		Power Loss %	<10	<10	<10	<10		
32:1	1600	SWR BW %	5.6	8.0	7.8	5	No Match	
		Imbalance	0	0	0	0		

Notes
Power losses are expressed as a percentage. A 10% power loss represents less than half (0.46) a dB.
The SWR bandwidth is the percentage of the measurement frequency that can be changed with the SWR staying under 1.5:1.

supplied wall-wart or connect an external 12 V dc supply. I found I needed to exercise both relays to tune my antenna on all bands.

Just after we purchased the AT1500BAL tuner for evaluation, Palstar added the AT1KBAL tuner to their line. In spite of their product numbers, they both are specified to handle the US legal limit. There is a key difference, however. The AT1KBAL tuner has the capacitors on the output side only. This results in a tuner that is designed to match from around 100 Ω up and is similar to an early balanced tuner described by Measures.[10,11]

Palstar has informed us that later this year they will replace the AT-1500BAL and the newer (and not tested) AT1KBAL with a new balanced tuner, the model BT1500A. This tuner will share the basic architecture and design of the AT1500BAL. It will make use of a new switched two-section variable capacitor designed to reduce minimum capacitance. This is intended to improve the tuning range, particularly on 10 meters. It will also have the inductors driven in tandem, removing the requirement for the drive belt and said to make for smoother tuning. Palstar expects to offer the BT1500A as their only balanced tuner once material for the others is exhausted. Measured Lab data is shown in **Table 14-17**.

Manufacturer: Palstar Inc, 9676 N Looney Rd, PO Box 1136, Piqua, OH 45356; tel 937-773-6255; fax 937-773-8003; **www.palstar.com**. 2004 prices: AT4K, $895; AT1500BAL, $695.95; AT1KBAL, $595.

E. F. Johnson Matchbox Antenna Tuners

Before WW II, the E. F. Johnson Company of Waseca, Minnesota, manufactured high quality variable capacitors, inductors and ceramic parts for electronics. By 1950 they were advertising their innovative Viking I transmitter in *The ARRL Radio Amateur's Handbook* and the next year their Matchbox antenna tuner for $48.95. A kW version was advertised in 1957. These tuners were based on the classic prewar balanced tuned circuit tuner (**Figure 14-32A**), but with an added twist. While the classic tuner of the day used plug-in coils to change bands, and manually attached tap points on the coil to change impedances, the Matchbox was bandswitching and had a unique differential capacitor arrangement to adjust the transformation ratio from the front panel, as shown in **Figure 14-32B**.

Models were available with and without SWR metering and the units included a TR relay useful for the typical separate transmitter and receiver setups of the day. By the '60s, the typical amateur antenna system had become one designed for resonant matched operation using coaxial cable without antenna tuners. Radios moved from AM to SSB, and Johnson changed their focus from amateur equipment to the commercial two-way FM radio market.

Their tuners are still a popular item at flea markets and on electronic auction sites. While not exactly a part of this review, Matchbox data reported by Witt in his earlier article is presented for comparison. As noted in the tables, the Matchbox tuners work well, but over a typically smaller impedance range than their modern counterparts. They also do not have band switch positions for any of the newer bands, although there is enough tuning range so they can typically cover 17 and 12, but not 30 or 60 meters. Within these limits, however, they can still be put to good use. Until the units discussed in this review became available, the Matchboxes were the only commercial tuner

Table 14-18
E. F. Johnson 275 W Matchbox, Balanced Antenna Tuner

Manufacturer's Specifications	*Measured in ARRL Lab*
Input load range: 25 to 1250 Ω.	See below.
Output SWR range: not specified.	See below.
Frequency coverage: 80, 40, 20, 15 and 10 meters	See below.
Input power: 275 W dc input.	Not tested.
Size: 7 × 10 × 10.5 inches (HWD).	

SWR	*Load (Ω)*		*80 Meters*	*40 Meters*	*20 Meters*	*15 Meters*	*10 Meters*
4:1	12.5	Power Loss %	No Match	No Match	No Match	No Match	No Match
		SWR BW %					
		Imbalance					
2:1	25	Power Loss %	No Match	No Match	No Match	<10	<10
		SWR BW %				4	4
		Imbalance				0	0
1:1	50	Power Loss %	<10	No Match	<10	<10	<10
		SWR BW %	2		>5	>5	3
		Imbalance	0	0	0	0	
2:1	100	Power Loss %	<10	<10	12	11	<10
		SWR BW %	2	4	>5	>5	3
		Imbalance	0	0	0	0	0
4:1	200	Power Loss %	11	<10	<10	<10	11
		SWR BW %	2	4	>5	>5	3
		Imbalance	0	0	0	0	0
8:1	400	Power Loss %	12	<10	<10	<10	11
		SWR BW %	2	4	>5	>5	3
		Imbalance	0	0	0	0	0
16:1	800	Power Loss %	10	<10	<10	<10	11
		SWR BW %	2	4	>5	>5	3
		Imbalance	0	0	0	0	0
32:1	1600	Power Loss %	10	<10	No Match	No Match	No Match
		SWR BW %	2	4			
		Imbalance	0	0			
64:1	3200	Power Loss %	10	No Match			
		SWR BW %	2				
		Imbalance	0				

Notes
Power losses are expressed as a percentage. A 10% power loss represents less than half (0.46) a dB.
The SWR bandwidth is the percentage of the measurement frequency that can be changed with the SWR staying under 1.5:1.

in wide use specifically designed to work with balanced antenna systems. Measured data from Frank Witt is shown in **Tables 14-18** and **14-19**.[12]

Notes

[1] R. D. Straw, Editor, *The ARRL Antenna Book,* 21st Edition. Available from your ARRL dealer or the ARRL Bookstore, ARRL order no. 9876. Telephone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.org/shop**; **pubsales@arrl.org**.

[2] The SG-235 is a 500 W version of the SG-230 with similar specifications, except needing a longer antenna. The SG-230 was reviewed in *QST* in November 1993.

[3] P. Pagel, "Product Review: Heath SA-2500 Antenna Tuner," *QST*, Mar 1985, pp 39-41.

[4] L. Aurick, "Product Review: J.W. Miller Automatic Antenna Tuner Auto-Trak Model AT2500," *QST*, Jul 1981, pp 42-43.

[5] S. Gerli, "Product Review: Daiwa CNA-1001 Automatic Antenna Tuner," *QST*, Nov 1981, pp 41-42.

[6] P. Danzer, N1II, "Open Wire Feed Line—A Second Look," *QST*, Apr 2004, pp 34-36.

[7] F. Witt, AI1H, "How to Evaluate Your Antenna Tuner—Parts 1 and 2," *QST*, Apr 1995, pp 30-34 and May 1995, pp 33-37.

[8] R. Lindquist, N1RL, "Product Review—QST Compares: Four High-Power Antenna Tuners," *QST*, Mar 1997, pp 73-77.

[9] R. D. Straw, Editor, *The ARRL Antenna Book,* 21st Edition. Available from your ARRL dealer or the ARRL Bookstore, ARRL order no. 9876. Telephone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.org/shop**; **pubsales@arrl.org**.

[10] Most center-fed antennas longer than 0.5 Ω are likely to meet this criterion. Very short antennas, or some low impedance driven arrays (8JK, for example) may have problems with this configuration, depending on feed line length.

[11] R. Measures, AG6K, "A Balanced Balanced Antenna Tuner," *QST*, Feb 1990, pp 28-32.

[12] See Note 7.

Table 14-19
E. F. Johnson kW Matchbox, Balanced Antenna Tuner

Manufacturer's Specifications	*Measured in ARRL Lab*
Input load range: 50 to 2000 Ω.	See below.
Output SWR range: not specified.	See below.
Frequency coverage: 80, 40, 20, 15 and 10 meters	See below.
Input power: 1000 W dc input.	Not tested.
Size: 12.5 × 17.25 × 11 inches (HWD).	

SWR	*Load (Ω)*		*80 Meters*	*40 Meters*	*20 Meters*	*15 Meters*	*10 Meters*
4:1	12.5	Power Loss %	No Match	No Match	No Match	15	<10
		SWR BW %				1	3
		Imbalance				0	0
2:1	25	Power Loss %	No Match	No Match	<10	13	<10
		SWR BW %			2	2	4
		Imbalance			0	0	0
1:1	50	Power Loss %	No Match	<10	<10	<10	<10
		SWR BW %		2	2	2	4
		Imbalance		0	0	0	0
2:1	100	Power Loss %	<10	<10	<10	<10	<10
		SWR BW %	1	2	2	2	4
		Imbalance	0	0	0	0	0
4:1	200	Power Loss %	<10	<10	11	<10	<10
		SWR BW %	1	2	2	2	4
		Imbalance	0	0	0	0	0
8:1	400	Power Loss %	<10	<10	<10	14	11
		SWR BW %	1	2	2	2	4
		Imbalance	0	0	0	0	0
16:1	800	Power Loss %	10	<10	<10	11	11
		SWR BW %	1	3	2	2	4
		Imbalance	0	0	0	0	0
32:1	1600	Power Loss %	10	<10	<10	No Match	No Match
		SWR BW %	1	2	2		
		Imbalance	0	0	0		
64:1	3200	Power Loss %	10	No Match	No Match	No Match	No Match
		SWR BW %	2				
		Imbalance	0				

Notes

Power losses are expressed as a percentage. A 10% power loss represents less than half (0.46) a dB.

The SWR bandwidth is the percentage of the measurement frequency that can be changed with the SWR staying under 1.5:1.

Review Questions

14-1 What are some of the key issues to keep in mind if selecting a commercial tuner?

14-2 What is the major advantage of an automatic antenna tuner?

14-3 Why might it be important to use a remotely tuned antenna tuner near the antenna feed point?

Chapter 15

Building Your Own Tuners



Contents

Why Build a Tuner....................15-2

Special Purpose Tuners....................15-2

Home Built General Purpose Tuners....................15-7

Review Questions....................15-12

Why Build a Tuner

A quick look at the schematic diagram of a basic manual antenna tuner (see Chapter 3), not counting metering and switching functions, reveals perhaps the simplest of amateur equipment schematics. A tuner has very few parts, and very few connections. That should make it easy to duplicate — and it does. Unfortunately each of the parts can be quite expensive and perhaps hard to find. On the other hand, if you have — or can easily obtain — the needed parts, there is no reason not to try building one or more tuners.

Special Purpose Tuners

Most of the tuners we have discussed heretofore have been of the general purpose variety. That is, they were designed to match varying loads on multiple frequencies from a single box. In any given amateur station, that may not be what is needed. You may have a need to match your particular antenna system to your particular radio on a particular frequency. That describes a "tuner" that needs no knobs or controls — just a fixed matching network.

The fixed network is more common than we may think. Every Yagi antenna with a gamma, T or hairpin match at the driven element has essentially done exactly that. Each is a matching network located at the antenna to provide a match from the antenna to the transmission line for a low loss run to the radio.

In a similar way, we can provide a network for each of our antennas that provides needed matching. The chapter title figure, a shot of a collection of specialized antenna matching systems at, W6TC, the advanced Amateur Radio station of the late George Badger, illustrates the point. None of those networks looks quite like any of the usual commercial antenna tuners of the last chapter! Another shot of this collection of networks, annotated with descriptions of each tuning element is shown in **Figure 15-1**.

Designing Your Special Purpose Tuner

While the usual circuit design and analysis tools of an electronic engineer can be used to design an impedance matching network, it can be a much simpler proposition for the amateur with a few software and hardware tools. The steps are straightforward:

- *Determine the (complex) impedance that the antenna system will present to the radio or transmission line.*

Determining the impedance can be done in a number of ways. The best approach is probably to measure the impedance at the location that will have the tuner by using an antenna analyzer. Such analyzers include tun-

1 — RG-213 coax cable from shack to input of vacuum relay box behind board (37) to connect to SteppIR Yagi antenna or 30, 40, 60, 80 and 160 meter loop tuners.
2 — RG-213 coax cable to SteppIR antenna.
3 — Coax connector to 30 and 40 meter balun (38).
4 — 30 meter tuning inductor.
5 — 30 meter vacuum variable capacitor.
6 — 30/40 meter vacuum relay connected to loop.
7 — 30/40 meter vacuum relay connected to loop.
8 — 40 meter phone/CW vacuum relay.
9 — 40 meter phone/CW inductor.
10 — 40 meter tuning capacitor.
11 — Motor drive for 40 meter tuning capacitor.
12 — 40 meter tuning inductor.
13 — 40 meter matching inductor.
14 — Coax connector to 60 meter balun.
15 — 60 meter balun.
16 — 60 meter tuning inductor.
17 — 60 meter tuning vacuum variable capacitor.
18 — 60 meter vacuum relays.
19 — 80 meter coax connector to 80 meter balun.
20 — 80 meter balun.
21 — Motor drive for 80 meter vacuum variable capacitor.
22 — Limit switches for 80 meter vacuum variable capacitor.
23 — 80 meter vacuum variable capacitor.
24, 25 — 80 meter tuning and matching inductors.
26 — 80/160 meter vacuum relay.
27 — 160 meter open end vacuum relay.
28, 29 — Connection to loop on tower.
30 — 160 meter receive vacuum relay.
31-33 — 160 meter receive RC network.
34 — Spark gap protector for 160 meter receive RC network.
35, 36 — 25-pair control cable to shack.
37 — Vacuum relay switch box to connect to SteppIR Yagi or loop.
38 — 30 and 40 meter balun.
39, 40 — Feed-through to 80 and 160 meter radial system.
41 — Remote motor control.
42 — Control shaft for 30 meter vacuum variable capacitor (5).
43 — Motor control relay.
44 — 160 meter balun.
45 — Manual control for 60 meter vacuum variable capacitor.
46 — Connector to 160 meter balun.

PHOTO AND ANNOTATION BARRY SHACKLEFORD, W6YE



Figure 15-1 — Example of perhaps the extreme in homemade antenna tuning arrangements. This collection of remotely controlled special purpose antenna tuners, all on an outside panel (cover removed for photo), was made to switch between and tune the multiple antenna systems of the late George Badger, W6TC, the designer and builder. The annotations refer to the elements in the list below.

The tuner panel includes separate remote controlled matching networks and connections for each of the HF bands from 30 to 160 meters. It is mounted at the base of the tower. At the top of the tuner panel are two connectors that connect to the two lower ends of the 30, 40, 60, 80 and 160 meter loop that extends from the left connector up to the 5 foot fiberglass boom extension on the left, up and over the 8 foot fiberglass mast extension at the top to the boom extension on the right, then down to the right connector.

able RF generators and displays that indicate actual complex (resistive and reactive) impedance, not just SWR. These are available from a number of manufacturers for a few hundred dollars, and are a valuable tool for the antenna inclined amateur. **Figure 15-2** shows a sampling that were tested for a *QST* product review.[1]



Figure 15-2 — A sampling of hand held antenna analyzers from Autek, Kuranishi, MFJ and Palstar.



Figure 15-3 — 40 meter dipole used as the example for the determination of a special purpose matching network.

Some analyzers provide the resistive value of the impedance and the magnitude, but not the sign of the reactive part. In order to design a matching network, it is important to know whether the reactance is positive (inductive) or negative (capacitive). Fortunately, it is usually easy to determine this. Just make a slight change in frequency and note the change in the value of reactance. If the reactance goes up as the frequency goes up it is inductive (+). If it goes down with increasing frequency, it is capacitive (–). This only works if the reactance does not go to zero between the two data points. Note that many programs use a lower case italicized letter *j* as part of the reactive value. This indicates that it should be mathematically considered perpendicular to the resistive value, or calculated as if an imaginary number. Don't let this bother you if it is not a familiar concept.

Another approach is to use antenna modeling software to determine the antenna, or the antenna system, impedance. The procedure I will outline will work with either. While modeling will result in a reasonable estimate of the impedance, it is rare that it provides an exact result, since generally not all conditions (ground parameters, for example) are fully known. This is what I did in the example that follows.

A third approach is to rely on manufacturers' or other published data. This also has its limitations in terms of the effect of the actual conditions at your location.

Figure 15-3 provides the basis for a short example of how this process can easily be conducted. The antenna under consideration is a dipole cut for the low end of the 40 meter amateur band. Instead of feeding it directly with coax, which would likely not require a matching network, we have selected to use 70 feet of nominal 450 Ω window line, so it can be fed efficiently on multiple bands. In order to use it on 40 meters, we determine (using *EZNEC* antenna modeling software) that the impedance at the center and each end of the band at the antenna feed point is as shown in **Table 15-1**.[2]

We then use the transmission line analysis program *TLW*, furnished with recent editions of *The ARRL Antenna Book*, to determine the impedance at the bottom of the mismatched transmission line as shown in **Table 15-2**.[3] Note that we could have gone directly to Table 15-2 using many antenna analysis programs that are equipped with transmission line models. My version of *EZNEC* included an early transmission line capability that did not take losses into account, so I used *TLW* instead. Since we need *TLW* for the next step, it wasn't any extra effort. One hint about using *TLW* — when finished don't just close the program window — click on the EXIT button to avoid problems with it starting properly next time.

- *Design a network that will transform the impedance to the desired impedance of the radio or transmission line.*

There are many techniques that could be employed to design a matching network to match any of the im-

[1] Notes appear on page 11.

Table 15-1

Impedance Predicted at the Antenna (Z_{ANT}) as Shown in Figure 15-1.

Frequency(MHz)	*Resistive Part (Ω)*	*Reactive Part (Ω)*	*50 Ω SWR*
7.0	82.3	–34.0	2.0
7.15	88.0	–0.37	1.8
7.3	94.1	+33.1	2.2

Table 15-2

Impedance Predicted at Bottom of the 70 Foot Transmission Line (Z_{IN}) as Shown in Figure 15-1.

Frequency(MHz)	*Resistive Part (Ω)*	*Reactive Part (Ω)*	*450 Ω SWR*
7.0	87.7	+82.9	4.9
7.15	103.3	+148.6	4.6
7.3	236.5	+229.7	4.3

pedances in Table 15-2 to our desired 50 Ω transmitter. Perhaps the easiest is to just click the TUNER button on the *TLW* screen shown in **Figure 15-4**. The screen shown in **Figure 15-5** will then appear, providing a place to input some common parameters including transmitter power and physical component properties.

While the design power is a straightforward parameter, some of the other terms may not be. The inductor and capacitor Q are related to the losses in the components. Typically, the biggest loss in an HF tuner, especially one with an air dielectric capacitor(s), is due to coil wire resistance. If you are buying a coil, it will likely specify the Q. If not, you can measure the impedance of the coil on your antenna analyzer at the operating frequency. The Q is just X_L/R, both available on an antenna analyzer screen.[4] Values in the hundreds are typical, and the good news is the program results are not very sensitive to the value of Q. A 100% change in Q, in this example, results in less than a 0.5% change in the value of the specified inductor and capacitor — smaller than the usual component tolerance, thus we specify a Q of 200 and the resulting design should be fine for most real inductors.

The OUTPUT STRAY CAPACITANCE value represents the capacitance of the wiring and components on the output side to the chassis. All wiring and components in the usual metal chassis or cabinet have capacitance to the metal walls. This is most important as the frequency goes up. Values in the tens of picofarads are common depending largely on component size and placement.

The other choice on this screen is the TUNER NETWORK TYPE. There really isn't too much to say about this — pick the one you like best, or better yet — try them all. I am somewhat partial to the low-pass L-network because it only has two components and provides some attenuation of harmonic signals. It also has only one solution for any load — more later. Pick any one to start, you will likely want to look at them all to find which one has components that are available or easiest to obtain.

If you pick any configuration besides the L-network, it will ask you for a value to use for the capacitor on the output side (towards antenna). It will try to design a tuner for any value you pick. If it can't make a tuner work with your value it will suggest making it larger or smaller. Make note of the power loss and try different values of output capacitor



TLW, Transmission Line Program for Windows

Version 3.00, Copyright 2000-2006, ARRL, by N6BV, Mar 14, 2006

Cable Type: 450-Ohm Window Ladder Line

● Feet
○ Meters

Length: 70.000 Feet 0.559 Lambda Frequency: 7.15 MHz

Use "w" suffix for wavelength (for example, 0.25w)

Characteristic Z0: 404.9 - j 0.63 Ohms Matched-Line Loss: 0.068 dB/100 Feet

Velocity Factor: 0.91 Max Voltage 10000 V Total Matched-Line Loss: 0.048 dB

Source
● Normal
○ Autek
○ Noise Bridge

● Load
○ Input

Resistance: 88 Ohms
Reactance: -.37

● Volt./Current
○ Resist./Reac.

SWR at Line Input: 4.49 SWR at Load: 4.60 Rho at Load: 0.64295

Additional Loss Due to SWR: 0.076 dB Total Line Loss: 0.124 dB

Impedance at Input: 103.25 + j 148.56 Ohms = 180.92 Ohms at 55.20 Degrees

Figure 15-4 — Input screen of *TLW* transmission line analysis software used to determine the impedance at the bottom of the mismatched transmission line of Figure 15-1.



Tuner Selection, TLW

Default Values

Unloaded Inductor Q: 200

Unloaded Capacitor Q: 1000

Transmitter Power, W: 100

Tuner's Input Resistance: 50

Output Stray Capacitance, pF: 10

Output voltage phase, deg.: 0

Tuner Network Type
○ High-Pass L-Network
● Low-Pass L-Network
○ Low-Pass Pi-Network
○ High-Pass Tee Network

Figure 15-5 — Antenna tuner Input screen of *TLW* software. Note the tuner configuration selected, LOW-PASS L-NETWORK, the power level, 100 W, that determines component ratings as well as the other parameters as described in the text.



```
Low-Pass L-Network
450-Ohm Window Ladder Line          Length:  70.000 feet        Frequency:  7.15 MHz
At load:  88 - j  .37 ohms =  88 ohms, at -.2 degrees    Load SWR =  4.6
Eff. Q = 2.3    1.5:1 SWR BW = 1257.3 kHz (17.6%)  2:1 SWR BW = Large
Estimated power lost in tuner for 100 W input:   2 W (0.07 dB = 1.5% lost)
Transmission-line loss = 0.12 dB.  Total loss = 0.19 dB.  Power into load = 95.7 W
At 100 W:            L1              C2
Unloaded Q           200             1000
Reactance            114.747         -84.107
Peak Voltage         229 V           250 V
RMS Current          1.4 A           2.1 A
Est. Pwr Diss.       1 W             0 W
RMS Vin:   70.71 V at 66.70 deg.     RMS Vout:  176.69 V at 0.00 deg.
```

Figure 15-6 — Antenna tuner output (design) screen of *TLW* software. Note the tuner schematic with parts values shown. The data and table above provide additional important information.

until you achieve a design that has an acceptable amount of loss and reasonably sized components. This illustrates the fact that the three element tuners — Pi- and T-network — have more than one set of adjustments that will provide a satisfactory match to the radio. Unfortunately, while they will all look good to the radio, some will have more loss than others.

Push the DRAW TUNER button. The screen shown in **Figure 15-6** should appear providing the design details for the low-pass L-network tuner I selected. In addition to the component values needed to provide the match, the table above the schematic provides information on component stress levels and other key data. The primary selection criterion can be found by looking at the resulting tuner designs (next paragraph) in each configuration and seeing which ones have component values that are reasonable, and even better, that you have on hand. A look at the resulting efficiency, expressed as POWER INTO LOAD, may also help you select a preferred topology.

Table 15-3 shows the resulting design for the middle and both edges of the 40 meter band. This design can be used as a starting point for a single frequency, single load, matching network. I say starting point because even with careful analysis there are a few variables that are not known exactly, including actual component values — typical tolerances are ±10% — for example. This is often taken into account by making one or both components variable, or trying slightly different component values until the desired result is obtained.

Alternately, if coverage of the entire band is desired, the components could be made variable over the ranges shown. It is also possible that the values for the middle of the band will provide a satisfactory match over at least a portion of a band without requiring change. This can be determined by trial and error, or simulated in an antenna analysis program by using modeled lumped "loads" at the bottom of the transmission line.

- *Build and test the network.*

As noted, the hardest part is often finding the needed components, especially those needed for high power networks. Hamfest flea markets are often a good source for such items, although they often come with a level of uncertainty regarding ancestry and component value. Again, the trusty antenna analyzer can be used to measure the reactance. Fixed or tapped inductors can be easily wound using plastic rod or tubing as a form. *The ARRL Handbook* provides a source of formulae for winding the desired inductance.

As with all RF projects, keep leads short and direct. To minimize stray capacitance, keep the components some distance from the cabinet edges. Use high quality connectors and make sure you have provided direct connectivity for all needed interconnections.

The best way to test the network is to start with the antenna analyzer. With the network connected to the proper place on the transmission line, the impedance should read close to 50 Ω at the design frequency. Now take *swept frequency* type data by measuring the impedance and SWR every 25 or 50 kHz. By plotting these on a graph, you should have a good idea of what the network will do and whether or not it will work across the range. If it isn't quite right, make a small change in one value and repeat the sweep. You should see an indication of the extent and direction of the change. Since there are only two or three components, you should quickly converge on your result.

Next hook it to your radio tuned to an unused frequency and note the transceiver's SWR reading. It should be close to that of the analyzer. Slowly increase the power to just below the level you designed to. Turn off the transmitter and check to see if any components have become hot — they shouldn't!

Table 15-3
Matching Network Components for 100 W Low-Pass L-Network to Match Z of Table 15-2 to 50 Ω.

Frequency(MHz)	*Inductance (μH)*	*Inductor Current (A_P)*	*Capacitance (pF)*	*Capacitor Voltage (V_P)*	*Efficiency (%)*
7.0	1.72	1.4	339.4	181	96.1
7.15	2.55	1.4	264.7	250	95.7
7.3	3.28	1.4	205.2	317	95.4

160 and 80 Meter Matching Network for Your 43 Foot Vertical — *Part 1*

The popular 43 foot vertical works best with matching at the antenna base — here's a way to do it for our two MF bands.

Phil Salas, AD5X

I've recently made the move to a 43 foot vertical for much of my lower frequency operations. This length antenna offers higher radiation resistance than shorter loaded monopoles. Increased radiation resistance improves efficiency by reducing the effects of ground losses, especially when you have an electrically short antenna — a characteristic of even a 43 foot antenna on 160 and 80 meters. If fed with a 1:4 unbalanced to unbalanced transformer (unun), a 43 foot antenna has a reasonable compromise SWR on 60 through 10 meters, which means that cable and unun losses are pretty much negligible on these bands.

This antenna is really not a good performer on 160 meters, and to a lesser extent on 80 meters, unless you provide matching right at the antenna base. This is due to the high capacitive reactance and still relatively low radiation resistance of a 43 foot antenna on 160 and 80 meters. This makes the mismatch so bad that it is almost impossible to efficiently match from your shack. If you can match the antenna system from your shack, you will throw away a lot of power in your coax and unun due to the very bad mismatch at the antenna.

I thus started experimenting with matching networks and wound up with two external impedance matching devices designed to significantly reduce SWR related coax losses and unun mismatch losses, and to help the inside tuner match on 160 and 80 meters. This month we'll look at the simpler version of the two matching networks. This version requires manual insertion of the matching network whenever you want to operate on 80 or 160 meters.



Figure 1 — Schematic diagram of the two band matching unit. 80 meter connections shown with dashed lines.



Figure 2 — T400A-2 160 and 80 meter matching unit.

The Matching Requirement

According to my AIM4170C antenna analyzer, my 43 foot vertical antenna has a capacitive reactance of about 580 Ω on 160 meters. This will vary based on the particular construction of your 43 foot vertical, its proximity to other objects, and other factors. The reactance will almost certainly be in the 550 to 650 Ω range. This amount of capacitive reactance needs approximately 50 µH of inductance in order to resonate the antenna. On 80 meters, approximately 9 µH is needed to resonate the antenna. A 50 µH high Q inductor is going to be large. For this first solution, I elected to go with a toroidal inductor in order to keep the matching unit as compact as possible.

Toroid Inductor Matching Solution

This compact design will handle the full legal limit on 80 and 160 meters for low duty cycle SSB and CW modes. The inductor consists of 35 turns of #14 AWG solid copper insulated house wiring wound on a T400A-2 toroid core. The antenna feed point is tapped two turns from the ground end for 80 meters, and three turns from the ground end for 160 meters. You should start with 38 turns total on your toroid, but then remove turns as necessary to get the network to resonate where you want it in the 160 meter band (more on this later).

I mounted the toroid assembly in a 6 × 6 × 4 inch NEMA enclosure using a 2½ inch long #10 machine screw and associated hardware along with a 2 × 4 inch piece of unplated fiberglass PC board material. Before you mount the toroid, prepare

Table 1
160 Meter Toroid Impedance Matching Assembly Parts List

Description	*Source/Part Number**
Banana plug (4 required)	Mouser 174-R802-EX
Binding post, black (4 required)	Mouser 164-R126B-EX
Binding post, red	Mouser 164-R126R-EX
NEMA Enclosure, 6 × 6 × 4 inch	Lowes/Home Depot
Glass cloth tape, 3M #27	ACE Hardware
SO-239 connector	Mouser 601-25-7350
Toroid, T400A-2 powdered iron	Amidon T400A-2

*Amidon parts are available from **www.amidoncorp.com** and Mouser parts from **www.mouser.com**.



Figure 3 — 160 and 80 meter input tap points.



Figure 4 — 80 meter coil shorting jacks.

it by scraping the insulation off the outside second, third and 11th through 13th wire turns. Because of the high voltages possible at legal limit power levels, especially on 160 meters, wrap the toroid with two layers of 3M #27 glass cloth electrical tape for added insulation between the #14 AWG wires and the toroid core.

Figure 1 is the schematic of the matching assembly, Figure 2 shows the internal details of the assembly, and Table 1 lists the parts necessary. To select between 160 and 80 meter operation, I used external jumpers across binding posts as shown in Figures 3 and 4. Stainless steel #8 hardware (screws, washers, lockwashers and nuts) are used for the matching unit ground and RF output terminals. Internal to the matching unit, I used a 2 inch wide strip of aluminum duct repair tape as a good low impedance ground between the UHF connector and the ground screw on the bottom of the case. Finally, I used #14 AWG stranded insulated wire for all internal connections.



Figure 5 — Measured SWR across 160 meters indicating a 2:1 SWR bandwidth of approximately 50 kHz.

Tuning the Matching Network to Resonance

Your particular installation will almost certainly require you to change the resonant frequency of the matching network. This is because there will be some variations of the antenna impedance based on your particular antenna physical construction, proximity to other objects and final length, as well as your desired operating frequency range. The design is such that the overall inductance is too large for 160 meters, so the network should resonate at or below the lower band edge. Therefore, you will need to remove one or more of the upper inductor turns in order to resonate the network for the desired frequency on 160 meters.

To do this, first solder wires from the second and third turn tap points on the coil to the two outer binding posts by the SO-239 connector. The input tap points tend to be fairly noncritical and will probably be the same for all installations. Now solder a short wire from the SO-239 center pin to the middle binding post. Next, externally jumper the middle binding post to the 160 meter binding post (third turn).



Figure 6 — SWR across 80 meters indicating a measured 2:1 SWR bandwidth of about 150 kHz.

Connect the matching assembly to the base of your 43 foot vertical and see where the minimum SWR point is on 160 meters using your antenna analyzer. If the resonant frequency is too low, remove a turn of wire and see where the minimum SWR point is again. You'll see about a 50 kHz upward move in frequency per turn of wire removed. When you have your desired resonant point on 160 meters, it is time to move to 80 meters. Externally jumper the input tap middle binding post to the 80 meter binding post (second turn), and use a clip lead to short from the top of the coil to turn number 12 and see where your minimum SWR frequency occurs. Move the tap point up or down until your resonance point (lowest SWR) is where you want it. Solder a wire from this tap point to one of the binding posts. Solder another wire from the top of the coil to another binding post. Now you will be able to externally jumper these binding posts to select either 160 or 80 meters.

My final test results for 160 and 80 meters are shown in Figures 5 and 6 as measured with my RigExperts AA-200 antenna analyzer connected directly to the matching network input at the base of the antenna. I'm a CW operator, so I favor resonance in the lower part of these bands, but you can adjust for your favorite portion of each band. The 2:1 SWR bandwidth on 160 meters is about 50 kHz, and about 150 kHz on 80 meters. Even a 3:1 SWR on these bands results in negligible SWR related cable losses for any reasonable length cable and is easily matched with my MFJ-998 in-shack tuner or most transceivers' internal tuners.



Figure 7 — Matching unit at the base of the author's 43 foot antenna. In this view, it is strapped for 80 meters.

Operation

Using the matching unit is simple. Just disconnect your normal unun when you want to operate on 160 or 80 meters and connect this matching unit to the base of the antenna. Select either 160 or 80 meters with the external straps. You can connect both the unun and this matching unit to the antenna at the same time, and just leave off the ground wire from the unit that is not used. The matching unit connected to the base of my 43 foot vertical is shown in Figure 7.

Conclusion

The matching network discussed in this article will permit very effective operation of your 43 foot vertical on the 160 and 80 meter bands. In Part 2, we'll look at a remotely switchable 160, 80 and 60 through 10 meter base matching unit. It is more complex, but it is also more convenient. Until then, see you on top band!

Amateur Extra class operator and ARRL Life Member Phil Salas, AD5X, was first licensed as WN3BCQ in 1964. Ham radio became the reason he subsequently pursued a career in electrical engineering. Phil earned BSEE and MSEE degrees from Virginia Tech and SMU, respectively, and worked in new product development for the next 33 years. Phil is now retired and spends his days split between ham radio related projects and enjoying time with his wife, Debbie, N5UPT. You can reach Phil at 1517 Creekside Dr, Richardson, TX 75081 or at **ad5x@arrl.net**.

160 and 80 Meter Matching Network for Your 43 Foot Vertical — *Part 2*

This dual band matching section design provides for remote band changing.

Phil Salas, AD5X

In Part 1, I described a simple 160 and 80 meter base matching assembly for a 43 foot antenna. While that unit is very effective and inexpensive to build, it is also a little inconvenient in that you must connect it when it is needed, and you must also manually enable 160 or 80 meter operation using straps. This month, we'll look at a more versatile matching assembly that is completely remote-controllable for operation on all bands. Again, this base matching network will significantly eliminate SWR-related coax losses and unun mismatch losses, and assist inside tuners in providing a match on 160 and 80 meters.

The All Band Matching Solution

As discussed in Part 1,[1] a 43 foot vertical antenna requires approximately 50 μH of inductance to resonate the antenna. On 80 meters, approximately 9 μH is needed for resonance. For the matching solution shown in Figure 1, I used an MFJ 404-0669 air wound coil and two Array Solutions RF-30 relays for up to full legal limit matching on all bands from 160 to 10 meters. A 2.1 × 5.5 mm dc power jack located below the SO-239 connector provides for relay control voltage inputs of 0 V, +12 or –12 V dc. The control input MOVs and bypass capacitors are mounted on a 6 terminal strip inside the matching assembly.

The matching unit operates as follows: With no control voltage applied, the inductor is disconnected and the unun is connected across the antenna feed point thereby preserving the original compromise SWR on 60-10 meters.

When +12 V is applied, the inductor is connected across the antenna feed point and inductor turns are shorted to resonate the antenna on 80 meters.

When the voltage is reversed, the short across the coil is removed and the matching section resonates the antenna on 160 meters. In both the 160 and 80 meter cases, the unun secondary taps into the inductor at the 200 Ω point, providing a proper match to the unun on these bands. This keeps the unun secondary voltage reasonable, and the feed line and unun losses very low as well.

I built the matching unit into an 8 × 8 × 4 inch NEMA weatherproof box available from home supply stores (see Figure 2). This box is too small to fit the entire inductor length needed, so I split the inductor into two pieces as can be seen in Figure 1. The long inductor section consists of 61 turns, and the short inductor section consists of 12 turns. While I preferred the more compact size of this box, you may wish to use the larger 12 × 12 × 4 inch NEMA box that can contain the full uncut inductor length needed.

All internal wiring uses insulated #14 AWG stranded wire. I attached the wires to the coil tap points using the MFJ coil clips called out in the parts list. You can solder the wires directly to the coil, but this is difficult due to the #12 AWG size of the coil wire and the spacing of the turns. The coil is mounted with #8 stainless steel screws, washers, lock washers and nuts also used for the ground and antenna feed terminals. Figure 1 shows the final matching unit with all components mounted. Note the terminal strip with the MOVs and bypass capacitors.

Since the antenna is unbalanced, a current balun or voltage unun is typically used. A voltage unun should be wired as shown in Figure 2.

Relay Connections

Some comments are necessary regarding the relay connections. See the sidebar on the *QST* binaries Web site for a discussion of how high the peak voltage across the full coil can be on 160 meters. As you can see, I connected relay contacts in series to increase the overall breakdown voltage. Also, the tap points on the inductor provide additional voltage above ground, which helps with the overall breakdown voltage.

The main concern is with the contact-to-coil 5.3 kV peak breakdown rating. When I examined the relays, I observed that the outer SPDT contacts are connected via insulated internal wires that are well separated from the coil by 0.1 to 0.2 inches. The problem is with the center SPDT relay common wire, which is in contact with the coil. While the coil and common wire are both insulated, there is no air-gap separation between them. This common wire-to-coil contact is obviously what



Figure 1 — All parts mounted in the NEMA enclosure.

---

[1] Notes appear on page 35.

determines the breakdown voltage rating. The way I got around this problem was to use the center SPDT relay contacts for the lowest potential interfaces as indicated in the schematic (Figure 2).

For the switched control voltage input, I used a 12 V, 1 A wall wart to keep the +12 V control voltages separate and isolated from the regular station voltage. This is to eliminate any possibility of shorting the main power supply when the control voltage polarity is flipped.

I mounted the switch in a small plastic box that I attached to my transceiver support shelf. The unlabeled center-off position is for 60 through 10 meter operation. The separate switch you see in the photo is for controlling other outdoor accessories, as I have two voltage feeds going out to my antenna location.



Figure 3 — The completed all band remotely controlled switching and impedance matching network mounted at the antenna base.

Matching Network Resonance

As with the previous matching network, you will almost certainly need to adjust the resonant frequency of the matching network due to variations in particular antenna physical construction, proximity to other objects and final length, as well as your desired operating frequency range. The overall starting inductance is too large for 160 meters, so the network will resonate at or below the lower band edge. Therefore, you can simply short one or more of the upper (short coil) inductor turns in order to tune the network higher to your desired 160 meter frequency.

To do this, first leave off the wire leads that attach between the relay contacts and the tap points on the coil. Build up short jumpers using the test-clips and micro-clips (perfect for the coil turn taps) called out in the parts list, and attach these between the relay contacts and coil, using the suggested tap points shown on the schematic.

Connect the matching assembly to the base of your 43 foot vertical (see Figure 3). Then enable 160 meter operation by applying −12 V dc, and jumper turns on the 12 turn inductor with a short clip lead until you find your desired 160 meter resonance point. Next, move the 160 meter relay tap point until you get minimum SWR. Now permanently short the turns on the short coil by soldering a piece of #16 AWG buss wire across these turns.

As you can see from my photos, I needed to short six turns on this coil. Next enable 80 meter operation (apply +12 V to the relays assembly) and select the coil shorting point for your desired resonant frequency and the tap point for best SWR. Finally remove the test clips leads, attach the coil clips, and solder wires between the coil clips and relay.

The 2:1 SWR bandwidth on 160 meters is about 50 kHz, and about 150 kHz on 80 meters. Even a 4:1 SWR on these bands results in negligible SWR related cable and unun loss, and is easily matched with my MFJ-998, an in-shack tuner.



Figure 2 — Schematic of the remotely controlled matching network. The parts list is on the QST binaries version.[2]

Operation

Operation of this matching unit couldn't be simpler. When no control voltage is applied, the antenna functions as it always has on 60 through 10 meters. For 80 meter operation, apply +12 V dc, and for 160 meter operation apply −12 V dc. The matching unit connected to the base of my 43 foot vertical is shown in Figure 10.

Conclusion

The matching network discussed in this article will permit very effective operation of your 43 foot vertical on all bands from 160 through 10 meters. Although on 10, 12 and 15 meters the elevation angle of the peak is higher than optimum for DX, it will still allow contacts. Feel free to experiment a little. You might prefer to use the toroid from Part 1 in this design instead of the air-core inductor. If you are not running more than about 500 W, the less expensive RF-10 relays are all you will need. Have fun, and I'll see you on the low bands.

Notes

[1] P. Salas, AD5X, "160 Meter Matching Network for Your 43 Foot Vertical — *Part 1*," *QST*, Dec 2009, pp 30-32.

[2] **www.arrl.org/files/qst-binaries.**

See Part 1 for Phil's bio. You can reach Phil at 1517 Creekside Dr, Richardson, TX 75081 or at **ad5x@arrl.net**.

Home Built General Purpose Tuners

There are a number of approaches to the design and construction of general purpose antenna tuners. Perhaps the easiest is to replicate existing successful designs, although finding the exact parts called for is sometimes a problem. Fortunately, the exact values are not very critical. It is also possible, if somewhat tedious, to go through the *TLW* based procedure described above at the extremes of frequency and mismatch to determine the range of values needed and then construct a tuner with variable and/or switched elements, often in combination, that will cover the needed range.

I have done this for the most popular configurations, see **Figure 15-7**, the high-pass T-network, Pi-network and low pass L-network with the results shown in **Tables 15-4** through **15-6**. I have provided the values for matching loads with a 10:1 SWR, the usual spec for a wide range tuner. In addition to the resistive loads at 5 and 500 Ω, I have made runs for moderate reactive loads of 25 ± *j*25 Ω and extreme reactive loads of 250 ± *j*250 Ω, all with approximately a 10:1 SWR.

As noted in Chapter 4, the Pi- and T-network tuners have multiple solutions for any load, while the L-network has a single solution. It is worth stressing this in case you use one, whether a commercial unit or a home-built one. Look again at Table 4-1, in Chapter 4, to get the idea.

Such "HF" tuners sometimes include the MF 160 meter amateur band as well as the 80 through 10 meter HF bands. I have provided data for 160, 80 and above the top of 10 meters so you can decide which way you want to go. Note that the addition of 160 meters makes a big difference in the component values required, one reason it often is not included. In addition, in some cases the larger inductor and capacitor(s) may have too high a minimum value to allow proper operation on 10 meters.



Figure 15-7 — Schematic diagrams of a high-pass T-network (A), Pi-Network (B) and a low-pass L-network (C) used as design examples in the text and Tables 15-4 to 15-6 on the following pages.

A T-Network Tuner from Surplus Parts

A T-network tuner that I made some years back and used effectively for some time is shown in **Figure 15-8**. This is an example of a "use what you have and see what it does" approach to tuner design. The unit is built around a chassis and panel from a WW2 surplus plug in tuning unit from a BC-375 transmitter used in bomber aircraft. The capacitor controls nice 4:1 planetary drives with calibrated scales, along with the rotary indicator and its turns count dial also came from a cannibalized BC-375. Today they would all be preserved as antiques, but in 1965, they were sources of cheap or free parts for new transmitting equipment.

Figure 15-9 shows the inside of the tuner, including a home built "Monimatch Mark II" type SWR indicator, along with a battery holder for the meter amplifier.[5] Modern transceivers include SWR indication, so these may no longer be needed. The variable capacitors, one above the other on the right side, were of a few hundred pF each, and the rotary inductor (on left) was probably around 15 μH. In those days, no one knew for sure — but it successfully matched any of my antennas for years.

Simple Breadboard Antenna Tuners

Home-built antenna tuners don't need to be as mechanically complex as my old T-match. Barry Shackleford, W6YE, has constructed a few using available variable capacitors and inductors fabricated in his workshop. While these won't handle full power,

Table 15-4

Component Requirements for High-Pass (Shunt L) T-Network Antenna Tuners at 10:1 SWR

Frequency/Z (Ω)	*Capacitor*		*Inductor (µH)*	*Capacitor Voltage (V_P)*		*Efficiency (%)*
1.8 MHz	*Input (pF)*	*Output (pF)*		*100 W*	*1500 W*	
5	1136	3000	2.1	180	710	96
500	548	500	13.9	323	1250	98
25 + *j*100	343	300	10.3	790	3070	92
25 – *j*100	170	300	20	1040	4030	86
250 + *j*250	308	200	10.5	380	1470	98
250 – *j*250	337	300	16.9	525	2030	96
Frequency/Z (Ω)	*Capacitor*		*Inductor (µH)*	*Capacitor Voltage (V_P)*		*Efficiency (%)*
3.5 MHz	*Input (pF)*	*Output (pF)*		*100 W*	*1500 W*	
5	563	1500	1.1	190	720	96
500	265	200	7.3	343	1330	98
25 + *j*100	275	200	3.5	613	2373	95
25 – *j*100	104	200	8.6	880	3403	88
250 + *j*250	333	100	5.6	381	1475	98
250 – *j*250	136	100	10.8	670	2600	94
Frequency/Z (Ω)	*Capacitor*		*Inductor (µH)*	*Capacitor Voltage (V_P)*		*Efficiency (%)*
30 MHz	*Input (pF)*	*Output (pF)*		*100 W*	*1500 W*	
5	79	200	0.12	160	640	96
500	29	50	0.77	370	1470	97
25 + *j*100	91	30	0.24	400	1560	98
25 – *j*100	24	100	0.46	440	1710	93
250 + *j*250	36	100	0.9	300	1150	98
250 – *j*250	29	100	0.6	360	1410	97

Table 15-5

Component Requirements for Low-Pass (Series L) L-Network Antenna Tuners at 10:1 SWR

Frequency/Z (Ω)	*Capacitor*		*Inductor (µH)*	*Capacitor Voltage (V_P)*		*Efficiency (%)*
1.8 MHz	*Input (pF)*	*Output (pF)*		*100 W*	*1500 W*	
5	5254	n/a	1.34	100	390	98
500	n/a	536	13.5	310	1210	98
25 + *j*100	n/a	1408	12	290	1120	98
25 – *j*100	1760	n/a	11	100	390	97
250 + *j*250	n/a	713	13	310	1210	98
250 – *j*250	n/a	359	13	310	1210	98
Frequency/Z (Ω)	*Capacitor*		*Inductor (µH)*	*Capacitor Voltage (V_P)*		*Efficiency (%)*
3.5 MHz	*Input (pF)*	*Output (pF)*		*100 W*	*1500 W*	
5	2700	n/a	0.69	100	400	98
500	n/a	275	6.8	310	1200	98
25 + *j*100	n/a	720	6.2	290	1120	98
25 – *j*100	926	n/a	5.6	100	390	97
250 + *j*250	n/a	367	6.8	310	1210	98
250 – *j*250	n/a	184	6.8	310	1210	98
Frequency/Z (Ω)	*Capacitor*		*Inductor (µH)*	*Capacitor Voltage (V_P)*		*Efficiency (%)*
30 MHz	*Input (pF)*	*Output (pF)*		*100 W*	*1500 W*	
5	315	n/a	0.08	100	390	98
500	n/a	32	0.79	310	1210	98
25 + *j*100	n/a	85	0.72	290	1120	98
25 – *j*100	140	n/a	0.58	100	390	97
250 + *j*250	n/a	43	0.79	310	1210	98
250 – *j*250	n/a	22	0.79	310	1210	98

Table 15-6

Component Requirements for Low-Pass Pi-Network Antenna Tuners at 10:1 SWR

Frequency/Z (Ω)	*Capacitor*		*Inductor (µH)*	*Capacitor Voltage (V_P)*		*Efficiency (%)*
1.8 MHz	*Input (pF)*	*Output (pF)*		*100 W*	*1500 W*	
5	5256	500	1.4	100	390	98
500	2602	1000	9.6	310	1200	96
25 + *j*100	966	1500	12.5	280	1110	97
25 – *j*100	3410	500	7.5	280	1100	96
250 + *j*250	1931	1000	11.3	310	1210	97
250 – *j*250	1284	500	12.9	310	1210	97
Frequency/Z (Ω)	*Capacitor*		*Inductor (µH)*	*Capacitor Voltage (V_P)*		*Efficiency (%)*
3.5 MHz	*Input (pF)*	*Output (pF)*		*100 W*	*1500 W*	
5	2706	500	0.7	100	390	98
500	1287	500	5.1	310	1200	96
25 + *j*100	643	800	6.2	280	1110	97
25 – *j*100	1886	300	3.7	280	1430	95
250 + *j*250	934	500	6.0	310	1200	97
250 – *j*250	859	300	6.2	310	1200	97
Frequency/Z (Ω)	*Capacitor*		*Inductor (µH)*	*Capacitor Voltage (V_P)*		*Efficiency (%)*
30 MHz	*Input (pF)*	*Output (pF)*		*100 W*	*1500 W*	
5	321	200	0.08	100	390	98
500	118	50	0.7	310	1200	97
25 + *j*100	103	100	0.7	290	1100	97
25 – *j*100	205	30	0.5	285	1100	96
250 + *j*250	71	50	0.8	310	1200	97
250 – *j*250	77	30	0.8	310	1200	97



Figure 15-8 — Front view of an early homemade antenna tuner. The unit is completely built of surplus parts. Note the handy tuning chart that was part of the BC-375 transmitter tuning drawer.



Figure 15-9 — Inside view of the home brew T-network tuner. The SWR meter (in 2 × 2 × 5 inch box in left partition) and associated circuitry would likely not be needed to use with current transceivers.



Figure 15-10 — Homebrew breadboard T-network tuner made by Barry Shackleford, W6YE. This tuner uses smaller variable capacitors with a voltage rating appropriate for 100 W use. The inductor was homemade, as described in the text. Note the inductance can be changed by moving (with transmitter off) the alligator clip to a different turn.



Figure 15-11 — Another view of Shackleford's T-network tuner.

they should be fine at the 100 W level. **Figures 15-10** and **15-11** show a T-network tuner that Barry made. Note the simplicity of construction. The only complication may be the homemade inductors. Barry used acrylic stock, cut and notched with his table saw, using a jig to set the spacing. You could use any technique that allowed the turns to be spaced so that his alligator clip tuning method can be employed. Barry stretched the wire before winding to work harden it and then secured it in his form with hot glue.

Barry also made the L-network tuner shown in **Figure 15-12**. This uses two capacitors in parallel, one an old broadcast three-gang unit, making up the single capacitor for the L-network. The smaller capacitor makes it easy to make fine adjustments, once you're close with the larger unit.

Making Tuners for Balanced Loads

Many tuners; home made as well as commercial units, provide for balanced loads by including a balun between an unbalanced tuner and the balanced load. This is an appropriate approach if the load is within perhaps 4:1 of the typical 200 to 50 Ω balun often used for the purpose. If beyond that range, the balun does not perform very well and losses and even damage may result.

A different approach was presented by Richard Measures, AG6K, in a *QST* article some years back.[6] Measures presented a design that first transformed the balanced antenna system load to 50 Ω balanced and then made the transition from balanced to unbalanced using a 1:1 choke balun operating at its design impedance.

Measures used a balanced L-network to perform the transition to 50 Ω and followed it with a coax choke. The schematic is shown in **Figure 15-13**, with a photo of his breadboard version, less balun, in **Figure 15-14**. He went on to show an elegant design suitable for remote control using stepper motors with remote position indicators, available on the ARRL members Web site. However, for many, a duplication of his breadboard design may be more feasible.

Measures found that inductors in the range of 15 to 20 μH maximum inductance were suitable, with a 5 A current rating for 1.5 kW use. Inductors may be found at hamfests, or are available from MFJ (**www.mfjenter-**



Figure 15-12 — An L-network tuner made by Barry Shackleford, W6YE. The two capacitors are in parallel making a single equivalent capacitance with the smaller one used for fine adjustment.



Figure 15-13 — The balanced L-network tuner designed by Richard Measures, AG6K.



Figure 15-14 — Photo of Measures' balanced L-network tuner. The choke-balun is not shown.

prises.com). Suitable sprockets and drive belts to couple the inductors together are available from McMaster-Carr (**www.mcmaster.com**), or they may be coupled end-to-end with some loss of symmetry.

Capacitors should be in the 200 to 300 pF range, with a 1.5 kV rating if used at the 1.5 kW level. Note that both sides of the capacitor are hot with RF, so to avoid burns use an insulated shaft coupling on the way to the knob. Trust me, the set screw in an insulated knob will get you if you don't!

For the choke balun, Measures suggests using solid (not foam) dielectric RG-213, or equivalent, coax wound in a single layer on a 1 foot long, 5 inch diameter, PVC pipe. Other choke configurations may be used, including winding the coax on a ferrite toroid core. An adaptation of the design is to use the L-network to transform to 200 Ω, rather than 50 Ω, and then use a 4:1 balun to finish the impedance transformation and make the transition to unbalanced coax.

As shown, the L-network is designed to transform loads higher then 50 Ω. This is often, but not always the case with ladder and window line systems. If a lower impedance load is encountered, it will be necessary to move the capacitor to the other side of the inductors.

Notes

[1] J. Hallas, W1ZR, "Product Review — A Look at Some High-End Antenna Analyzers" *QST*, May 2005, pp 65-69.

[2] Several versions of *EZNEC* antenna modeling software are available from developer Roy Lewallen, W7EL, at **www.eznec.com**.

[3] R. D. Straw, Editor, *The ARRL Antenna Book,* 21st Edition. Available from your ARRL dealer or the ARRL Bookstore, ARRL order no. 9876. Telephone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.org/arrl-store**; **pubsales@arrl.org**.

[4] Note that the value of R will be higher than the dc resistance because of skin effect.

[5] L. McCoy, W1ICP (SK), "The Monimatch," *QST*, Feb 1957, pp 38-40.

[6] Richard Measures, AG6K, "A *Balanced* Balanced Antenna Tuner," *QST*, Feb 1990, pp 28-32.

Hairpin Tuners for Matching Balanced Antenna Systems

Balanced Transmatch designs for 28 to 450 MHz.

John Stanley, K4ERO



Figure 1 — K4ERO balanced tuner for 60 through 15 meters.

Once more, the advantages of ladder line for HF antennas were well presented in July 2008 *QST.*[1] Before WWII surplus brought us cheap coax, balanced feeders were almost always used for VHF as well. In the January 1942 *QST* reproduction that was included with The 2007 ARRL Handbook, we find that both home-brew and commercial VHF gear all used balanced lines.[2] For a given cost, open wire ladder line, window line or even TV twin lead can give you a lower loss installation than trying to buy large diameter coax in an effort to keep the losses to an acceptable level. This is dramatically demonstrated by comparing losses in various line types.[3] So, we wonder, why do so few present-day operators use ladder line or twin lead on the VHF frequencies? Might one reason be the lack of suitable *antenna tuners* (transmatches) for those bands? If balanced tuners were available, would ladder line be as popular at VHF as it has become at HF?

Balanced Tuners for HF Use

The ARRL Handbook, *The ARRL Antenna Book* and other ham publications have always included designs for balanced tuners.[4,5] Adam Nathanson, N4EKV, has one of many good Web sites showing this type of tuner at **www.n4ekv.com/tuners.asp**. I have used tuners like this for years with good results. Figure 1 shows the one I use at up to 100 W on the HF bands.

As noted in Volume 6 of *The ARRL Antenna Compendium,* I lean toward tuners with a fixed link and tapped coil.[6] The match is found by tuning the capacitor and adjusting the output side to connect to a variable number of turns, keeping the taps equidistant from the coil ends. Other versions use the taps for coarse tune and a variable capacitor in series with the link for finer tuning.

Balanced Tuners for the Higher Frequencies

One of the problems with this type of tuner is that as the frequency goes higher, the number of turns on the coil goes down rather quickly. By the time you get to 28 MHz, there may be only four turns on the coil. This means that the adjustment *steps* available are very limited. You can tap to either two or four turns, or if you are willing to unbalance the tap positions, or can access the opposite side of the coil, you could use one or three turns. In either case, the operation is compromised. Another approach is to connect one tap to the bottom of the coil, instead of to the top, effectively using fractions of a turn rather than whole turns, but this often is not feasible from a mechanical standpoint. In addition the symmetry and thus the balance are affected. If this type of tuner is to be used on 10 meters and higher, we need to rethink the design.

Figure 2(A) is a schematic of the conventional tapped link coupled tuner. Figure 2(B) is a representation of what I call a *hairpin* tuner. The electrical properties are essentially identical, but the physical layout of the hairpin type is optimum for the higher frequencies. By making the main inductor in the shape of a hairpin, or shorted transmission line, instead of a single layer solenoid coil, as is used in the conventional design, the tuner becomes much easier to build and adjust. The use of a short short-circuited transmission line section as an inductor is nothing new. It has been used for VHF/UHF circuits for many years.



Figure 2 — Balanced tuner configurations. At (A) conventional tapped coil based tuner, at (B) the hairpin equivalent.

Building Hairpin Tuners

For some time I have been using a hairpin inductor in a balanced tuner for 6 and 10 meters, and recently I built one for each of the 144, 220 and 432 MHz bands. The approach is the same on each frequency. A section of transmission line was used instead of the coil typically used on lower frequencies.

---

[1] Notes appear on page 36.



Figure 3 — Hairpin tuner for 6 and 10 meters.



Figure 4 — 144 MHz version of a hairpin tuner.

The capacitor was a split stator or butterfly design. The input link is a single turn inductor that overlaps a portion of the main transmission line inductor and the output taps were taken at whatever point of the hairpin that gives the best match.

The advantage of this layout is that moving the taps to any point on the hairpin is the same as tapping on different numbers of turns on a coil, except that with the hairpin, it is very convenient to make the adjustment in as fine a step as may be desired. In all of my designs, the coupling loop is held to the main hairpin by cable ties. This allows some adjustment of the coupling loop, but holds the loop sufficiently snug so that it is not likely to move around accidentally. Use less loop coupling for higher Q with more selectivity and more loop coupling for lowest loss.

Making them Play

The frequency tuning range percentage will depend on the capacitor used. For widest range, select one with a high minimum to maximum capacitance ratio. All of the capacitors I have tried have provided adequate range to cover the desired amateur band. The range can be extended to cover a second band by putting fixed capacitors in parallel with the variable tuning capacitor. For example, the 6 meter version, shown in Figure 3, works for 10 meters with the addition of a parallel 40 pF fixed ceramic capacitor, while the 220 MHz version, shown in Figure 5, works fine on 2 meters with the addition of a 12 pF ceramic. As it is, the 2 meter version just makes it to 222 MHz, so two bands are possible without switching caps. A single tuner could also work on 10 and 6 meters without switching by careful component selection.

Capacitor Options

The most difficult component to find will likely be the split stator capacitor. There are ways of designing your own capacitor and it is made easier because of the relatively small capacitance required at these frequencies. For all of the designs shown here, I took capacitors from my well stocked junk box. You less well equipped folks will have to search at a hamfest or check out the basement of one of the local old timers. Commercial capacitors are available, but the price may shock you. You could also choose to use a single section capacitor instead of the split stator. In that case, the capacitor shaft and frame will be "hot" and must be floated above ground. You will have to tune it via a long insulated shaft. And, of course, the balance will be somewhat compromised. The method does work and a suitable single section capacitor may be easier to find, however . Alternatively you could use a pair of identical capacitors to ground if you adjusted them each to the same setting or worked out a common shaft arrangement. Fussy, but it could work. Target dimensions and component values for the bands in this range are shown in Table 1.

Inductor Choices

The length of the hairpin will depend on the value of your capacitor. The values below represent tuners I have built and should give you a good starting point. Match the hairpin width to the spacing of the capacitor terminals, or bend the ends of the hairpin in or out at the capacitor end in order to make the connections. Spacing does affect the inductance value so keep it close to what you see in the photos.

My inductors are ⅛ inch diameter brass rod, but they could be soft copper tubing or wire in sizes from 12 gauge up to ¼ inch. Brass welding rods from the hardware store could also be used. A smaller diameter means the hairpin should be shortened a bit as the inductance per inch will be higher. The links should be insulated wire, either enameled or PVC coated or, best of all, Teflon insulated. The 6 meter tuner in Figure 3 uses the shield of Teflon coax as the link. My links do not make electrical contact anywhere with the main hairpin. The coax shield and center of the hairpin could both

Table 1
Hairpin Tuner Component Values, Dimensions and Frequency Range

Band	*Capacitor Value (pF/Section)**	*Inductor Length (Inches)***	*Tuning Range (MHz)****
10 Meters	95-170	15	26-34
6 Meters	15-90	15	36-90
2 Meters	3-20	6	110-225
222 MHz	3-10	4	220-330
432 MHz	3-4	1.5	390-440

*Effective capacity is ½ of the value/section.
**All inductors made of ⅛ inch brass rod.
***Range may by reduced or shifted by reactive loads.



Figure 5 — Hairpin tuner for 144/222 MHz enclosed in its box.



Figure 6 — 432 MHz version of a hairpin tuner.

be grounded to a chassis, if desired.

Tuning Up

Tuning consists of setting the taps to an intermediate position and adjusting the capacitor for minimum SWR. If SWR is not as low as desired, move the taps a bit either towards or away from the capacitor and readjust the capacitor. You should be able to find tap settings that allow the SWR to be reduced to 1:1.

Safety Considerations

Note that neither of the tuners described above are shown installed within a chassis of any kind. This is to show the construction more clearly. Also, I must admit that during tests, I got away with this because I used low power and am very careful not to touch the *hot* parts of the circuit. I also have a non-metallic operating desk. The open construction is useful during experiments.

I definitely do not recommend this approach for general use. You will want to put your tuner in a shielded box of some kind, probably with a hinged lid to allow you to move the taps as shown in Figure 5. You should *never* adjust the tap clips with power applied. The tuning shaft should be brought out through the enclosure where an insulated knob should be installed for tuning even though with a split stator capacitor the shaft should be at ground potential. For high power, the use of a suitable enclosure is essential, especially if the tuner is to be installed close to the operating position. This is to prevent RF burns from contact as well as exposure to excess RF levels.

Remember that your body is more susceptible to pick up from VHF fields than is the case at HF. If you put the tuner well away from the operating position in a place that is protected from access by family members or pets, you may be able to use a somewhat more open construction as is sometimes done with conventional home brew tuners. Radiation from an unenclosed tuner of any type can be enough to cause interference with nearby electronics devices and could cause fires if anything flammable comes in contact with the hot parts of the circuit.

These tuners have been tested with 100 W on 10 and 6 meters, 50 W on 2 meters and 20 W on 70 cm, the maximum output of my rig. For higher power, the designs can be scaled, remembering that the bigger it gets, the lower the frequency for the same geometry. Thus, a design similar to that used here for 432 MHz, but three times larger, would probably work fine with a full kW, but on 144 MHz. Since my 20 W, 432 MHz design uses an inductor that is about as short as is practical (see Figure 6), getting up to 1 kW at 432 MHz, might prove difficult with this design. At the least, a different type of capacitor would be required.

I hope that these simple to build and adjust tuners will start a trend towards greater use of balanced feeders on the higher frequencies just as ladder line has become the favorite for many on the lower bands.

Notes

[1] J. Hallas, W1ZR, "Getting on the Air—Your Second HF Antenna," *QST*, Jul 2008, pp 69-70.

[2] B. Goodman, W1JPE, "Receivers for 112-Mc. Emergency Work," *QST*, Jan 1942, pp 18-25, 74-75.

[3] *The ARRL Handbook for Radio Communications*, 2009 Edition, Figure 21.4. Available from your ARRL dealer or the ARRL Bookstore, ARRL order no. 0261 (Hardcover 0292). Telephone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.org/shop**; **pubsales@arrl.org**.

[4] See Note 3, p 21.13.

[5] R. D. Straw, Editor, *The ARRL Antenna Book*, 21st Edition, p 25-3. Available from your ARRL dealer or the ARRL Bookstore, ARRL order no. 9876. Telephone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.org/shop**; **pubsales@arrl.org**.

[6] J. Stanley, K4ERO, "The Filtuner," *ARRL Antenna Compendium, Volume 6*. Available from your ARRL dealer or the ARRL Bookstore, ARRL order no. 7431. Telephone 860-594-0355, or toll-free in the US 888-277-5289; **www.arrl.org/shop**; **pubsales@arrl.org**.

John Stanley, K4ERO, holds an Amateur Extra class license and has been licensed for over 50 years. He has worked as a broadcast engineer most of his life, mainly with religious shortwave stations in many parts of the world. He graduated from MIT in 1962 with a BSEE degree. John is an ARRL Technical Adviser. He and his wife, Ruth, WB4LUA, live in Rising Fawn, Georgia. You can reach John at 524 White Pine Ln, Rising Fawn, GA 30738 or at **jnrstanley@alum.MIT.edu**.

Review Questions

15-1 What are some major challenges involved with building an antenna tuner?

15-2 Under what conditions is a special purpose tuner a viable option?

15-3 Why might you decide not to include 160 meters in your tuner design?

APPENDIX A

Making Sense of Decibels

Joel R. Hallas, W1ZR

Much of the technical data found in *QST* and other ARRL publications is expressed in decibels, generally shown as *dB*. Contrary to the belief of some, this is not done to mystify beginners, but rather is intended to make comparisons easier and avoid the use of very large or small numbers.

So What's this Decibels Business All About?

Decibels are just a way of expressing ratios, often power ratios. If we are looking at the gain of an amplifier stage, the pattern of an antenna or the loss of a transmission line we are generally interested in the ratio of the power out to the power in, or the ratio of the power in front of a beam antenna to that coming from the back. These are some of the places that we will find the results expressed in dB.

Decibels are a logarithmic function. Logarithms are a handy mathematical tool based on exponents. An important feature of logarithms is that multiplication can be performed by adding the logarithmic quantities instead of multiplying them. Similarly, divisions can be accomplished by subtracting in the same manner. This becomes a benefit if you are dealing with multiple stages of amplification and attenuation — as we often are in radios — snatching a minuscule signal from the ether — amplifying and processing it so we can hear it out the loudspeaker. Instead of having to multiply and divide at each stage to keep track of the progress of our signal processing — often with signal levels with many zeros to the right of the decimal point — we can just tally all the dB and have total gain of the system.

So How do We Compute the Decibels?

The *deci* in decibels refers to a factor of $\frac{1}{10}$, as in *deciliters* for $\frac{1}{10}$ of a liter, while the *bel* relates to the idea of a logarithmic ratio, originally used to define sound power.

- To convert a power ratio into decibels, just:

1. Find the base 10 logarithm of the power ratio.
2. Multiply by 10.

For example, if we have an amplifier with a power gain of 275, we find the logarithm of 275 (see below, if you don't do logs in your head) to be 2.44. We multiply by 10 and the result is that a power gain of 275 can be represented as 24.4 dB.

- To convert decibels to a power ratio, we do the opposite:



Figure 1 — The *Windows Scientific Calculator* ready to calculate the effect of a 2 dB cable loss.

1. Divide by 10.
2. Find the base 10 antilog of the result.

Note that the base 10 antilog of a number is just 10 raised to the power of the number. This is also something you probably don't do in your head, so let's see how to easily perform the computations.

Understanding a few characteristics of logs will help avoid problems interpreting results. Note that a gain of 0 dB means that there is no change to the signal — not that the signal has vanished! The other important fact is that a power ratio of less than one (a loss rather than a gain) is represented as a negative number in decibels.

Enter the *Windows Scientific Calculator*

In the *very* old days, engineers and technicians used tables to make accurate logarithmic calculations, and mechanical slide rules if three significant digits was sufficient precision.[1] Starting around 1970, scientific calculators became available. Initially they were expensive typewriter-sized devices that were typically shared within an engineering department. Within a few years pocket-sized units were available for less than $200, and now everyone could make calculations to a precision of nine significant digits, whether warranted by the data accuracy or not. Tables and slide rules were relegated to the pages of history with spark transmitters.

The dawn of the reasonably priced personal computer seemed to push the fancy scientific calculator out of sight only about 10 years later. Unfortunately, for many functions a calculator may be a better choice, and decibel calculations may be one. The calculations may be easily performed on a PC by putting the equations in cells of an Excel spreadsheet, but not everyone can do that without a lot of thought.

If you have a suitable scientific calculator, that should easily make the calculations. Not all have an ANTILOG button, but if not, they will likely have a button that says X^Y, which can be used as above. If you don't have a handheld calculator, you may not know that there is a very capable one included as an "accessory" within the Microsoft *Windows* operating system! Just click START then ALL PROGRAMS then ACCESSORIES. You should find an icon for the *Windows Calculator*. You could open it, but why not drag it onto your desktop first.

On first opening, you may find a four-function grocery store type calculator. Have no fear, just click on VIEW then SCIENTIFIC to get the one you want. It should look about like Figure 1.

Give it a Test Drive

Let's say you have a mismatched coax cable with a loss of 2 dB. You may want to know how many of the 100 W from your transmitter actually reach your antenna. Remember a 2 dB loss is a "gain" of –2 dB! We'll go through the inverse dB calculation of column 2. Using your *Windows Calculator*, either hit 2 on your keyboard, or:

- Click on the 2 on the calculator "keypad," then:
- Click on the +/– key; the display should show – 2, as in Figure 1.
- Click on the / key to select the "divide by" operation. Enter the digits 1 and 0 for the number 10 and hit ENTER or =. Make note of the result (–0.2) or store it in memory (M+).
- Enter the digits 1 and 0 for the number 10.
- Click on X^Y to raise 10 to a power.
- Enter your earlier result, –.2 and hit ENTER.
- The display should show 0.63095734448019324943436013662234 or about 0.63. That is the fraction of your power left after a 2 dB loss. That means your antenna sees 63 W and 37 W is heating your transmission line.

While you are using the *Windows Scientific Calculator* look over its other features. It provides painless conversion between decimal and binary, octal or hex numbers, for example.

Joel R. Hallas, W1ZR, is QST *Technical Editor. He can be reached at* **w1zr@arrl.org**.

---

[1] See, for example, *Standard Mathematical Tables*, CRC Press, any edition. In addition to tables of logarithms and trigonometric functions, it includes many handy formulas from geometry, trigonometry and calculus.

From April 2007 QST © ARRL

Index

A

- Ameritron ATR-30 14–5 ff
- Antenna
  - Analyzers 15–4
  - Balanced 13–7
  - Bobtail curtain 13–5 ff
  - Center-fed Zepp 13–7 ff
  - Dipole (see half-wave dipole)
  - End-fed Zepp 13–8
  - Inverted L 13–5
  - Mobile 13–8
    - HF mobile on land vehicles 13–9
    - HF mobile on other vehicles 13–9
  - Single wire fed 13–4
    - Lengths to avoid 13–4
  - Vertical monopole 13–5
  - Windom 13–6 ff
  - Yagi 13–3
- Antenna tuner
  - Ameritron ATR-30 14–5 ff
  - Balanced 12–2 ff
  - Configuration
    - Balanced 12–1 ff
    - Unbalanced 3–3 ff
  - Controls
    - L-network 3–3
    - Pi-network 3–6
    - T-network 3–6
    - Tuned transformer 3–6 ff
  - External 6–2 ff
  - General purpose, home made 15–7 ff
  - Hot chassis tuner 12–4
  - Impedance range 5–3 ff
  - Johnson Matchbox 14–26 ff
  - Lab testing 14–4
  - LDG AT-1000 14–19 ff
  - LDG RT-11 14–12 ff
  - LDG Z-100 14–12 ff
  - Limitations 3–7
  - Measures' balanced, home made 15–15 ff
  - Metering 3–7
  - MFJ 991 14–12 ff
  - MFJ-974H 14–26 ff
  - MFJ-986 14–5 ff
  - MFJ-994 14–19 ff
  - Name 1–5
  - Palstar AT-Auto 14–19 ff
  - Palstar AT1500 14–5 ff
  - Palstar AT1500BAL 14–26 ff
  - Palstar AT4K 14–26 ff
  - Remote 8–2 ff
  - SGC MAC-200 14–12 ff
  - SGC SG-235 14–19 ff
  - SGC SG-237 14–12 ff
  - Ten Tec 238A 14–5 ff
  - Tuning
    - Automatic tuner 4–2
    - Manual tuner 4–3
  - Vectronics HFT-1500 14–5 ff
- Attenuation 7–3 ff, 7–5 ff, 8–3, 9–3, 11–4
  - Determining 9–3, 9–5

B

- Badger, George W6TC (SK) 15–2 ff
- Balun
  - Bazooka balun 11–6
  - Choke type 11–5
  - Conditions requiring 11–2
  - Ferrite toroid core balun 11–7
  - Half-wave loop balun 11–6
  - Location in system 11–4
  - Transformer type 11–3, 11–6
- Bandwidth 2–3 ff
  - Fractional 2–5
- Bobtail curtain 13–5 ff

C

- Center-fed Zepp 13–7 ff

D

- Delta match 10–2
- Dipole (see half-wave dipole)

E

- End-fed Zepp 13–8

G

- Gamma match 10–2

H

- Half-wave dipole 2–2
  - Fed with coax 10–5, 13–2
  - Height 2–4
  - Length 2–3
  - Operating on odd harmonic frequency 13–2 ff
  - Resonant frequency 2–4
- Hot chassis tuner 12–4

I

- Impedance 1–3
  - Matching 1–3
- Inverted L 13–5

J
Johnson Matchbox .... 14–26 ff

L
Lab testing.. 14–4
LDG AT-1000 .... 14–19 ff
LDG RT-11 .... 14–12 ff
LDG Z-100... 14–12 ff
Limitations.. 3–7
Load
  Balanced 10–2
  Reactive... 3–2 ff
  Reistive 3–2
  Unbalanced 10–2

M
Measures' balanced, home made.................... 15–15 ff
MFJ 991 .... 14–12 ff
MFJ-974H.. 14–26 ff
MFJ-986... 14–5 ff
MFJ-994.. 14–19 ff
Mobile 13–8
  HF mobile on land vehicles 13–9
  HF mobile on other vehicles.......................... 13–9

P
Palstar AT-Auto.. 14–19 ff
Palstar AT1500.. 14–5 ff
Palstar AT1500BAL...................................... 14–26 ff
Palstar AT4K.. 14–26 ff

S
S-meter 8–3
SGC MAC-200 .... 14–12 ff
SGC SG-235 .... 14–19 ff
SGC SG-237 .... 14–12 ff
Single wire fed 13–4
  Lengths to avoid 13–4
Specifications 1–2
  Impedance.. 1–3 ff
SWR (standing wave ratio) .... 2–2, 3–4 ff

T
Ten Tec 238A .... 14–5 ff
Transmission line .... 2–2 ff
  Attenuation .... 7–3 ff, 7–5 ff, 8–3, 9–3, 11–4
    Determining... 9–3, 9–5
  Balanced line .... 10–2 ff
  Characteristic impedance.............. 2–2, 3–4 ff, 7–2
  Construction... 9–4
  Input impedance... 7–6
  Loss (*see* "Attenuation")
  Measuring line current 4–6
  Open wire line... 10–1
  Propagation velocity 7–3
  Twinlead... 10–1
  Unmatched....................................... 7–4, 7–6, 9–4
  Window line.. 10–1
Transmission line for Windows (TLW)................. 15–5

V
Vectronics HFT-1500 .... 14–5 ff
Vertical monopole 13–5

W
W6TC (SK).. 15–2 ff
Windom.. 13–6 ff

Y
Yagi antenna.. 13–3

Notes

Please use this form to give us your comments [illegible] future editions.
or e-mail us at pubsfdbk@arrl.org (publications [illegible] your name, call, e-mail address and the book title, edition and printing in the [illegible] whether or not you are an ARRL member.

Where did you purchase this book? ☐ From ARRL directly [illegible]

Is there a dealer who carries ARRL publications within:

☐ 5 miles ☐ 15 miles ☐ 30 miles of your location? [illegible]

License class:

☐ Novice ☐ Technician ☐ Technician with code ☐ General [illegible]

Name ______________________________ [illegible]

____

Address ______________________________

City, State/Province, ZIP/Postal Code ______________________________

Daytime Phone ( ) ______________________________

If licensed, how long? ______________________________

Other hobbies ______________________________ E-mail ______________________________

____

Occupation ______________________________

For ARRL use only	[illegible]
Edition	1 2 3 4 5 6 7 8 9 10 11 12
Printing	[illegible]

FEEDBACK

Please use this form to give us your comments on this book and what you'd like to see in future editions, or e-mail us at **pubsfdbk@arrl.org** (publications feedback). If you use e-mail, please include your name, call, e-mail address and the book title, edition and printing in the body of your message. Also indicate whether or not you are an ARRL member.

Where did you purchase this book? ☐ From ARRL directly ☐ From an ARRL dealer

Is there a dealer who carries ARRL publications within:

☐ 5 miles ☐ 15 miles ☐ 30 miles of your location? ☐ Not sure.

License class:

☐ Novice ☐ Technician ☐ Technician with code ☐ General ☐ Advanced ☐ Amateur Extra

Name ______________________ ARRL member? ☐ Yes ☐ No

______________________ Call Sign ______________

Address ______________________

City, State/Province, ZIP/Postal Code ______________________

Daytime Phone ( ) ______________________ Age ______________

If licensed, how long? ______________________

Other hobbies ______________________ E-mail ______________

____

Occupation ______________________

For ARRL use only	**GAT**
Edition	1 2 3 4 5 6 7 8 9 10 11 12
Printing	2 3 4 5 6 7 8 9 10 11 12

From ______________________________

____

____

Please affix postage. Post Office will not deliver without postage.

EDITOR, THE ARRL GUIDE TO ANTENNA TUNERS
ARRL—THE NATIONAL ASSOCIATION FOR AMATEUR RADIO
225 MAIN STREET
NEWINGTON CT 06111-1494

please fold and tape



Buy or Build the Best Tuner for Your Station.

Antenna tuners are devices often misunderstood in the Amateur Radio world. While not every station requires an antenna tuner to transmit radio signals, often an incompatibility between the transmitter and the antenna system results in poor performance. An antenna tuner between them is the way to obtain efficient operation.

The ARRL Guide to Antenna Tuners discusses the details of the different configurations and requirements of antenna tuners. It explores the design, construction and applications of the different types available. You'll learn if one is necessary in your station, what type of tuner is needed and where to install it for maximum improvement. This book will give you a better understanding of your antenna system and the way it can be enhanced through the selection and use of the appropriate antenna tuner.

Contents:

- Why Might I Need an Antenna Tuner
- A Look at a Typical Configuration
- So Just What is an Antenna Tuner?
- Tuning an Antenna Tuner
- The Internal Tuner—How Does it Help?
- An External Tuner at the Radio
- Transmission Lines and Loss
- Moving the Tuner to the Back 40
- Transmission Line Choices for Low Loss
- Balanced versus Unbalanced Lines
- So What's a Balun, an Unun, a Choke?
- Balanced Antenna Tuners
- Antennas that Work Well with Tuners
- A Survey of Available Tuners
- Making Your Own Tuner

Joel Hallas has been a radar and telecommunications systems engineer, engineering manager, telecommunications executive and college teacher, and is now Technical Editor of ***QST***, the monthly journal of ARRL, the national association for Amateur Radio. He has earned BS and MS degrees in electrical engineering. Joel is a radio amateur, and holds the license call sign W1ZR.

***ARRL** — devoted entirely to Amateur Radio*

ARRL has books, software, online courses and other resources for licensing, operating and education. Look for these other popular ARRL titles:

- ***The ARRL Antenna Book***
- ***Basic Antennas: Understanding Practical Antennas and Design***
- ***The ARRL Antenna Designer's Notebook***

Published by:
ARRL *The national association for* **AMATEUR RADIO™**
225 Main Street
Newington, CT 06111-1494 USA
www.arrl.org

ISBN 978-0-87259-098-4
52295
9 780872 590984
USA $22.95 ARRL Order No. 0984

$44.95

The ARRL

ANTENNA BOOK

21st Edition

The *ultimate* reference for Amateur Radio antennas, transmission lines and propagation

Complete CD
for THE ARRL
ANTENNA BOOK

INSIDE: Includes the fully searchable book on CD-ROM

The ARRL Antenna Book



All the information you need to design your own complete antenna system.

Since the first edition in September 1939, radio amateurs and professional engineers have turned to **The ARRL Antenna Book** as THE source of current antenna theory and a wealth of practical how-to construction projects. Use this book to discover even the most basic antenna designs— wire and loop antennas, verticals, and Yagis—and for advanced antenna theory and applications. Many of the antennas in this edition benefit directly from advances in sophisticated computer modeling.

This 21st edition has been extensively revised to include information you can use to build highly optimized or specialized antennas. The book includes new content on Near Vertical Incidence Skywave (NVIS) techniques, phased arrays, S-parameters as used in modern vector network analyzers (VNA), Beverage receiving antennas, mobile “screwdriver” antennas, ionospheric area-coverage maps, *and much…much more*.

Fully searchable CD-ROM included!
Bundled with this book is a CD-ROM containing **The ARRL Antenna Book** in its entirety, using the popular Adobe® Reader® software for Microsoft® Windows® and Macintosh® systems. View, search and print from the entire text, including images, photographs, drawings…**everything!**

The CD-ROM contains additional utility programs, including:

- **YW**—Yagi for Windows
- **TLW**—Transmission Line for Windows
- **HFTA**—HF Terrain Assessment for Windows
- **Range-Bearing**— compute range/bearing or latitude/longitude
- **Arrayfeed1**— designing phased-array feed systems
- **EZNEC-ARRL**— antenna modeling for Windows

PLUS propagation forecast tables for more than 170 locations around the world for all portions of the solar cycle!

CONTENTS

Safety First
Antenna Fundamentals
The Effects of Ground
Antenna Modeling and System Planning
Loop Antennas
Low-Frequency Antennas
Multiband Antennas
Multielement Arrays
Broadband Antenna Matching
Log Periodic Arrays
HF Yagi Arrays
Quad Arrays
Long-Wire and Traveling-Wave Antennas
Direction Finding Antennas
Portable Antennas
Mobile and Maritime Antennas
Repeater Antenna Systems
VHF and UHF Antenna Systems
Antenna Systems for Space Communications
Antenna Materials and Accessories
Antenna Products Suppliers
Antenna Supports
Radio Wave Propagation
Transmission Lines
Coupling the Transmitter to the Line
Coupling the Line to the Antenna
Antenna and Transmission-Line Measurements
Smith Chart Calculations

Includes a comprehensive glossary and index

ISBN-13: 978-0-87259-987-1
ISBN-10: 0-87259-987-6

Published by:
ARRL *The national association for AMATEUR RADIO*
225 Main Street, Newington, CT 06111-1494 USA
www.arrl.org

ISBN 0-87259-987-6 Order No. 9876

The ARRL

Antenna Book

21st Edition

Editor
R. Dean Straw, N6BV

Contributing Editors
L. B. Cebik, W4RNL
Dave Hallidy, K2DH
Dick Jansson, WD4FAB
Roy Lewallen, W7EL
Rudy Severns, N6LF
Frank Witt, AI1H

Production
Michelle Bloom, WB1ENT
Sue Fagan, KB1OKW—Cover Art
Jodi Morin, KA1JPA
David Pingree, N1NAS
Kathy Ford

Software Beta Testers
Ahti Aintila, OH2RZ
Alan Bloom, N1AL
L. B. Cebik, W4RNL
Loney Duncan, W0GZV
Chuck Hutchinson, K8CH
Steve London, N2IC
Dan Maguire, AC6LA
Steve Miller, N8SM (SK)
Bob Neece, K0KR,
Danny Richardson, K6MHE
Rudy Severns, N6LF
Jim Tabor, KU5S
Bill Tippett, W4ZV
Don Toman, K2KQ
Pete Smith, N4ZR
Scott Tuthill, K7ZO
Frank Witt, AI1H.

The Covers:

Tower photo at sunset (front and back): Tower and beam at the station of Francisco R.F. Aragao, PT2TD, in Brasilia, Brazil.

Center image: Kurt Andress, K7NV, working on 40-meter Yagi at N6RO in Oakley, CA. Photo by Dean Straw, N6BV.

Upper right image: UHF antenna. Photo credit: ShutterStock.com.

Lower right image: Some of the members of the C5Z contest DXpedition near Banjul, The Gambia. Photo by Henryk Kotowski, SM0JHF.

ARRL The national association for AMATEUR RADIO
225 Main Street, Newington, CT 06111-1494 USA
www.arrl.org/

Copyright © 2007 by

The ARRL, Inc.

Copyright secured under the Pan-American Convention

International Copyright secured

This work is publication No. 15 of the Radio Amateur's Library, published by the ARRL. All rights reserved. No part of this work may be reproduced in any form except by written permission of the publisher. All rights of translation are reserved.

Printed in USA

Quedan reservados todos los derechos

21st Edition
First Printing

ISBN: 0-87259-987-6

We strive to produce books without errors. Sometimes mistakes do occur, however. When we become aware of problems in our books (other than obvious typographical errors that should not cause our readers any problems) we post an Adobe Portable Document Format (PDF) file on ARRLWeb. If you think you have found an error, please check **www.arrl.org/notes** for corrections. If you don't find a correction there, please let us know, either using the Feedback Form in the back of this book or by sending an e-mail to **pubsfdbk@arrl.org**.

Foreword

We are pleased to offer the 21st edition of *The ARRL Antenna Book*. Since the first edition in September 1939, each new *Antenna Book* has provided more and better information about the fascinating subject of radio antennas. We've sold more than a million *Antenna Books* over the years to amateurs and professionals alike, making it one of the most successful books in our extensive lineup of publications.

Fundamentals about antennas rarely change from edition to edition, but modern application of these fundamentals can result in more highly optimized or specialized antennas. For example, many of the antennas in this new edition benefit directly from advances in sophisticated computer modeling.

We usually update at least 20% of the material in a new edition, and this book is no exception. There have been major revisions in the following chapters:

- Chapter 2: Updated information the concept of "gain."
- Chapter 6: Further insights into the importance of low elevation angles for the lower frequencies, plus a whole new section on NVIS (Near Vertical Incidence Skywave) operation.
- Chapter 8: Completely new section on feeding of phased arrays by W7EL.
- Chapter 13: Updates on Beverage receiving antennas.
- Chapter 14: New "tape-measure" portable Yagi for fox hunting.
- Chapter 16: New information on mobile "screwdriver" antennas.
- Chapter 23: Expanded section on ionospheric area-coverage maps.
- Chapter 27: New section on S-parameters, as used in Vector Network Analyzers (VNAs)

We are fortunate to have the expertise of some well-known and highly talented authorities, who either wrote or reviewed a number of chapters for technical accuracy:

- Rudy Severns, N6LF, and Roy Lewallen, W7EL—low-frequency antennas.
- LB Cebik, W4RNL—Modeling antennas.
- Dick Jansson, WD4FAB—satellite antennas.
- Dave Hallidy, K2DH—EME arrays.
- Bob Hunsucker, AB7VP, and Carl Luetzelschwab, K9LA—HF propagation.

In addition, some exceptional software writers have contributed programs and data for the *Antenna Book*.

- Roy Lewallen, the author of *EZNEC*, has created a special *EZNEC ARRL* program, just for the *Antenna Book*. *EZNEC ARRL* uses the multitude of specialized modeling files also included on the CD-ROM. These models were used in almost every chapter in the book.
- W7EL has also supplied *Arrayfeed1.exe*, a program to design feed systems for phased-arrays.
- Dr Peter Guth and the US Naval Academy have again graciously allowed ARRL to include the versatile *MicroDEM* mapping program on the CD-ROM. *MicroDEM* can easily and quickly generate customized terrain files for the *HFTA* terrain-assessment program, as well as map terrain all around the country using free US topographic data files from the Internet.
- Jim Tabor, NU5S, wrote *GeoAlert-ARRL*, a wonderful freeware program to track propagation trends and to keep tabs on the latest Internet propagation bulletins.
- Dean Straw, N6BV, editor of *The ARRL Antenna Book* has updated and upgraded his *YW* (Yagi for Windows), *TLW* (Transmission Line for Windows) and *HFTA* (HF Terrain Assessment) programs from the 20th edition. A large number of statistical elevation-angle files for QTHs all around the world are included as well. N6BV has also written a new *Range-Bearing* program that is included on the CD-ROM.
- Also included on the CD-ROM are DOS-based utility programs by several authors that analyze antenna tuners, design mobile antennas and LPDAs, and that scale Yagis for *YW*.
- Are you planning on going on a DXpedition to somewhere you've never been before? The CD-ROM now includes both Simplified and Detailed propagation prediction tables for more than 150 QTHs all around the world. Even if you don't journey to distant lands, these tables will give you plenty of insight on planning contesting or DXing strategies—They can also help you set up that Saturday afternoon schedule with your uncle Harry in Cleveland!

You now have in one place the information you need to design your own complete antenna system scientifically—the elevation angles to aim for from your part of the world and the effects of your own local terrain.

As usual, in a publishing effort of this magnitude, errors creep into the process, despite our best efforts. We appreciate hearing from you, our readers, about errors or about suggestions on how future editions might be made even more useful to you. A form for mailing your comments is included at the back of the book, or you can e-mail us at: **pubsfdbk@arrl.org**.

David Sumner, K1ZZ
Executive Vice President
Newington, Connecticut
February 2007

Contents

1 Safety First
2 Antenna Fundamentals
3 The Effects of Ground
4 Antenna Modeling & System Planning
5 Loop Antennas
6 Low-Frequency Antennas
7 Multiband Antennas
8 Multielement Arrays
9 Broadband Antenna Matching
10 Log Periodic Arrays
11 HF Yagi Arrays
12 Quad Arrays
13 Long-Wire and Traveling-Wave Antennas
14 Direction Finding Antennas
15 Portable Antennas
16 Mobile and Maritime Antennas

17 Repeater Antenna Systems
18 VHF and UHF Antenna Systems
19 Antenna Systems for Space Communications
20 Antenna Materials and Accessories
21 Antenna Products Suppliers
22 Antenna Supports
23 Radio Wave Propagation
24 Transmission Lines
25 Coupling the Transmitter to the Line
26 Coupling the Line to the Antenna
27 Antenna and Transmission-Line Measurements
28 Smith Chart Calculations
A-1 Appendix
AB-1 Index of Advertisers
931 Index

Schematic Symbols Used in Circuit Diagrams


FIXED
VARIABLE
PHOTO
ADJUSTABLE
TAPPED
THERMISTOR
t°
RESISTORS
FIXED
NON-POLARIZED
SPLIT-STATOR
ELECTROLYTIC
VARIABLE
FEED-THROUGH
CAPACITORS
AIR-CORE
ADJUSTABLE
PHASING
IRON-CORE
OR
FERRITE-BEAD
TAPPED
INDUCTORS
METERS
*
*~ =~ V, mV,
~ A, mA, |m~ A
CONDUCTORS NOT JOINED
CONDUCTORS JOINED
SHIELDED WIRE OR COAXIAL CABLE
TERMINAL
ADDRESS OR DATA BUS
MULTIPLE CONDUCTOR CABLE
WIRING
SPST
SPDT
NORMALLY OPEN
TOGGLE
NORMALLY CLOSED
MULTIPOINT
MOMENTARY
THERMAL
SWITCHES
BATTERIES
SINGLE CELL
MULTI CELL
GROUNDS
CHASSIS
EARTH
A-ANALOG
D-DIGITAL
LED
(DS#)
VOLTAGE VARIABLE CAPACITOR
THYRISTOR (SCR)
BRIDGE RECTIFIER
DIODE/RECTIFIER
T
T
G
TRIAC
(U#)
ZENER
SCHOTTKY
TUNNEL
DIODES
(D#)
AIR CORE
ADJUSTABLE INDUCTANCE
ADJUSTABLE COUPLING
WITH CORE
WITH LINK
TRANSFORMERS
3-PIN CERAMIC RESONATOR
ANTENNA
FUSE
QUARTZ CRYSTAL
HAND KEY
MOT
MOTOR
Z
ASSEMBLY OR MODULE (OTHER THAN IC)
MISCELLANEOUS
PNP
P-CHANNEL
P-CHANNEL
P-CHANNEL
P-CHANNEL
P-CHANNEL
B
C
E
E
B2
B1
G
D
S
G
D
S
G2
G1
D
S
G
D
S
NPN
N-CHANNEL
N-CHANNEL
N-CHANNEL
N-CHANNEL
N-CHANNEL
B
C
E
E
B2
B1
G
D
S
G
D
S
G2
G1
D
S
G
D
S
BIPOLAR
UJT
JUNCTION FET
SINGLE-GATE
DUAL-GATE
SINGLE-GATE
DEPLETION MODE MOSFET
ENHANCEMENT MODE MOSFET
TRANSISTORS
AND
NAND
OR
NOR
XOR
INVERT
SCHMITT
OTHER
LOGIC (U#)
SPST
SPDT
DPDT
THERMAL
RELAYS
GENERAL AMPLIFIER
OTHER
OP AMP
+
-
INTEGRATED CIRCUITS (U#)
COMMON CONNECTIONS
LABEL
PHONE JACK
PHONE PLUG
CONTACTS
MALE
FEMALE
COAXIAL CONNECTORS
FEMALE
MALE
MULTIPLE, MOVABLE
MULTIPLE, FIXED
240 V FEMALE
GROUND
TRIODE
PENTODE
CRT
TUBE ELEMENTS
ANODE
HEATER OR FILAMENT
GRID
GAS FILLED
CATHODE
COLD CATHODE
DEFLECTION PLATES
TUBES
INCANDESCENT
NEON (AC)
LAMPS
FEMALE
MALE
MALE CHASSIS-MOUNT
HOT 120 V
NEUT
HOT 120 V
HOT 120 V
NEUT
GND
GND
GND
CONNECTORS

About the ARRL

The seed for Amateur Radio was planted in the 1890s, when Guglielmo Marconi began his experiments in wireless telegraphy. Soon he was joined by dozens, then hundreds, of others who were enthusiastic about sending and receiving messages through the air—some with a commercial interest, but others solely out of a love for this new communications medium. The United States government began licensing Amateur Radio operators in 1912.

By 1914, there were thousands of Amateur Radio operators—hams—in the United States. Hiram Percy Maxim, a leading Hartford, Connecticut inventor and industrialist, saw the need for an organization to band together this fledgling group of radio experimenters. In May 1914 he founded the American Radio Relay League (ARRL) to meet that need.

Today ARRL, with approximately 150,000 members, is the largest organization of radio amateurs in the United States. The ARRL is a not-for-profit organization that:

- promotes interest in Amateur Radio communications and experimentation
- represents US radio amateurs in legislative matters, and
- maintains fraternalism and a high standard of conduct among Amateur Radio operators.

At ARRL headquarters in the Hartford suburb of Newington, the staff helps serve the needs of members. ARRL is also International Secretariat for the International Amateur Radio Union, which is made up of similar societies in 150 countries around the world.

ARRL publishes the monthly journal *QST*, as well as newsletters and many publications covering all aspects of Amateur Radio. Its headquarters station, W1AW, transmits bulletins of interest to radio amateurs and Morse code practice sessions. The ARRL also coordinates an extensive field organization, which includes volunteers who provide technical information and other support services for radio amateurs as well as communications for public-service activities. In addition, ARRL represents US amateurs with the Federal Communications Commission and other government agencies in the US and abroad.

Membership in ARRL means much more than receiving *QST* each month. In addition to the services already described, ARRL offers membership services on a personal level, such as the ARRL Volunteer Examiner Coordinator Program and a QSL bureau.

Full ARRL membership (available only to licensed radio amateurs) gives you a voice in how the affairs of the organization are governed. ARRL policy is set by a Board of Directors (one from each of 15 Divisions). Each year, one-third of the ARRL Board of Directors stands for election by the full members they represent. The day-to-day operation of ARRL HQ is managed by a Chief Executive Officer.

No matter what aspect of Amateur Radio attracts you, ARRL membership is relevant and important. There would be no Amateur Radio as we know it today were it not for the ARRL. We would be happy to welcome you as a member! (An Amateur Radio license is not required for Associate Membership.) For more information about ARRL and answers to any questions you may have about Amateur Radio, write or call:

ARRL—The national association for Amateur Radio
225 Main Street
Newington CT 06111-1494
Voice: 860-594-0200
Fax: 860-594-0259
E-mail: **hq@arrl.org**
Internet: **www.arrl.org/**

Prospective new amateurs call (toll-free):
800-32-NEW HAM (800-326-3942)
You can also contact us via e-mail at **newham@arrl.org**
or check out *ARRLWeb* at **http://www.arrl.org/**

FEEDBACK

Please use this form to give us your comments on this book and what you'd like to see in future editions, or e-mail us at **pubsfdbk@arrl.org** (publications feedback). If you use e-mail, please include your name, call, e-mail address and the book title, edition and printing in the body of your message. Also indicate whether or not you are an ARRL member.

Where did you purchase this book?
☐ From ARRL directly ☐ From an ARRL dealer

Is there a dealer who carries ARRL publications within:
☐ 5 miles ☐ 15 miles ☐ 30 miles of your location? ☐ Not sure.

License class:
☐ Novice ☐ Technician ☐ Technician with code ☐ General ☐ Advanced ☐ Amateur Extra

---

Name ARRL member? ☐ Yes ☐ No

Call Sign

Daytime Phone ( )

Age

Address

City, State/Province, ZIP/Postal Code

E-mail:

If licensed, how long?

Other hobbies

Occupation

For ARRL use only **ANT BK**

Edition 0 21 22 23 24 25 26

Printing 1 2 3 4 5 6 7 8 9 10 11 12

From ______________________________

____

____

Please affix
postage. Post
Office will not
deliver without
postage.

EDITOR, ARRL ANTENNA BOOK
ARRL—THE NATIONAL ASSOCIATION FOR
AMATEUR RADIO
225 MAIN STREET
NEWINGTON CT 06111-1494

please fold and tape

Chapter 1

Safety First

Safety begins with your attitude. If you make it a habit to plan your work carefully and to consider the safety aspects of a project before you begin the work, you will be much safer than "Careless Carl," who just jumps in, proceeding in a haphazard manner. Learn to have a positive attitude about safety. Think about the dangers involved with a job before you begin the work. Don't be the one to say, "I didn't think it could happen to me."

Having a good attitude about safety isn't enough, however. You must be knowledgeable about common safety guidelines and follow them faithfully. Safety guidelines can't possibly cover all the situations you might face, but if you approach a task with a measure of "common sense," you should be able to work safely.

This chapter offers some safety guidelines and protective measures for you and your Amateur Radio station. You should not consider it to be an all-inclusive discussion of safety practices, though. Safety considerations will affect your choice of materials and assembly procedures when building an antenna. Other chapters of this book will offer further suggestions on safe construction practices. For example, Chapter 22 includes some very important advice on a tower installation.

PUTTING UP SIMPLE WIRE ANTENNAS

No matter what type of antenna you choose to erect, you should remember a few key points about safety. If you are using a slingshot or bow and arrow to get a line over a tree, make sure you keep everyone away from the "downrange" area. Hitting one of your helpers with a rock or fishing sinker is considered not nice, and could end up causing a serious injury.

Make sure the ends of the antenna are high enough to be out of reach of passers-by. Even when you are transmitting with low power there may be enough voltage at the ends of your antenna to give someone nasty "RF burns." If you have a vertical antenna with its base at ground level, build a wooden safety fence around it at least 4 feet away from it. Do not use metal fence, as this will interfere with the proper operation of the antenna. Be especially certain that your antenna is not close to any power wires. That is the only way you can be sure it won't come in contact with them!

Antenna work often requires that one person climb up on a tower, into a tree or onto the roof of a house. Never work alone! Work slowly, thinking out each move before you make it. The person on the ladder, tower, tree or rooftop should wear a safety belt, and keep it securely anchored. It is helpful (and safe!) to tie strings or lightweight ropes to all tools. If your tools are tied on, you'll save time getting them back if you drop them, and you'll greatly reduce the risk of injuring a helper on the ground. (There are more safety tips for climbing and working on towers later in this chapter. Those tips apply to any work that you must do above the ground to install even the simplest antenna.)

Tower Safety

Working on towers and antennas is dangerous, and possibly fatal, if you do not know what you are doing. Your tower and antenna can cause serious property damage and personal injury if any part of the installation should fail. Always use the highest quality materials in your system. Follow the manufacturer's specifications, paying close attention to base pier and guying details. Do not overload the tower. If you have any doubts about your ability to work on your tower and antennas safely, contact another amateur with experience in this area or seek professional assistance.

Chapter 22, Antenna Supports, provides more detailed guidelines for constructing a tower base and putting up a tower. It also explains how to properly attach guy wires and install guy anchors in the ground. These are extremely important parts of a tower installation, and you should not take shortcuts or use second-rate materials. Otherwise the strength and safety of your entire antenna system may be compromised.

Any mechanical job is easier if you have the right tools. Tower work is no exception. In addition to a good assortment of wrenches, screwdrivers and pliers, you will need some specialized tools to work safely and efficiently on a tower. You may already own some of these tools. Others may be purchased or borrowed. Don't start a job until you have assembled all of the necessary tools. Shortcuts or improvised tools can be fatal if you gamble and lose at 70 feet in the air. The following sections describe in detail the tools you will need to work safely on a tower.

CLOTHING

The clothing you wear when working on towers and antennas should be selected for maximum comfort and safety. Wear clothing that will keep you warm, yet allow complete freedom of movement. Long denim pants and a long-sleeve shirt will protect you from scrapes and cuts. (A pull-on shirt, like a sweat shirt with no openings or buttons to snag on tower parts, is best.) Wear work shoes with heavy soles, or better yet, with steel shanks (steel inserts in the soles), to give your feet the support they need to stand on a narrow tower rung.

Gloves are necessary for both the tower climber and all ground-crew members. Good quality leather gloves will protect hands from injury and keep them warm. They also offer protection and a better grip when you are handling rope. In cooler weather, a pair of gloves with light insulation will help keep your hands warm. The insulation should not be so bulky as to inhibit movement, however.

Ground-crew members should have hard hats for protection in case something falls from the tower. It is not uncommon for the tower climber to drop tools and hardware. A wrench dropped from 100 feet will bury itself several inches in soft ground; imagine what it might do to an unprotected skull.

SAFETY BELT AND CLIMBING ACCESSORIES

Any amateur with a tower must own a high-quality safety belt, such as the one shown in **Fig 1**. *Do not attempt* to climb a tower, even a short distance, without a belt. The climbing belt is more than just a safety device for the experienced climber. It is a tool to free up both hands for work. The belt allows the climber to lean back away from the tower to reach bolts or connections. It also provides a solid surface to lean against to exert greater force when hoisting antennas into place.

A climber must trust his life to his safety belt. For this reason, nothing less than a professional quality, commercially made, tested and approved safety belt is acceptable. Check the suppliers' list in Chapter 21, Antenna Product Suppliers, and ads in *QST* for suppliers of climbing belts and accessories. Examine your belt for defects before each use. If the belt or lanyard (tower strap) are cracked, frayed or worn in any way, destroy the damaged piece and replace it with a new one. You should never have to wonder if your belt will hold.



Fig 1—Bill Lowry, W1VV, uses a good quality safety belt, a requirement for working on a tower. The belt should contain large steel loops for the strap snaps. Leather loops at the rear of the belt are handy for holding tools. (*Photo by K1WA*)

Along with your climbing belt, you should seriously consider purchasing some climbing accessories. A canvas bucket is a great help for carrying tools and hardware up the tower. Two buckets, a large one for carrying tools and a smaller one for hardware, make it easier to find things when needed. A few extra snap hooks like those on the ends of your belt lanyard are useful for attaching tool bags and equipment to the tower at convenient spots. These hooks are better than using rope and tying knots because in many cases they can be hooked and unhooked with one hand.

Many hams use climbing belts such as shown in Fig 1. But fully integrated fall-arrest and positioning safety harnesses are preferable. The model ASL-301 in **Fig 2** has a D-ring on the back of the harness to which a safety lanyard is attached. These harnesses are available through Champion Radio Products, Box 572, Woodinville, WA 98072, **www.championradio.com**.

Rope and Pulley

Every amateur who owns a tower should also own a



Fig 2—Fall-arrest safety harness integrated with positioning safety belt for tower climbing. *(Courtesy of Champion Radio Products)*



Fig 3—A good quality rope and pulley are essential for anyone working on towers and antennas. This pulley is encased in wood so the rope cannot jump out of the pulley wheel and jam.

good quality rope at least twice as long as the tower height. The rope is essential for safely erecting towers and installing antennas and cables. For most installations, a good quality $^1/_2$-inch diameter manila hemp rope will do the job, although a thicker rope is stronger and may be easier to handle. Some types of polypropylene rope are acceptable also; check the manufacturer's strength ratings. Nylon rope is not recommended because it tends to stretch and cannot be securely knotted without difficulty.

Check your rope before each use for tearing or chafing. Do not attempt to use damaged rope; if it breaks with a tower section or antenna in mid-air, property damage and personal injury are likely results. If your rope should get wet, let it air dry thoroughly before putting it away.

Another very worthwhile purchase is a pulley like the one shown in **Fig 3**. Use the right size pulley for your rope. Be sure that the pulley you purchase will not jam or bind as the rope passes through it.

THE GIN POLE

A gin pole, like the one shown in **Fig 4**, is a handy device for working with tower sections and masts. This gin pole is designed to clamp onto one leg of Rohn No. 25 or 45 tower. The tubing, which is about 12 feet long,



Fig 4—A gin pole is a mechanical device that can be clamped to a tower leg to aid in the assembly of sections as well as the installation of the mast. The aluminum tubing extends through the clamp and may be slipped into position before the tubing clamp is tightened. A rope should be routed through the tubing and over the pulley mounted at the top.



Fig 5—The assembly of tower sections is made simple when a gin pole is used to lift each one into position. Note that the safety belts of both climbers are fastened below the pole, thereby preventing the strap from slipping over the top section. (*Photo by K1WA*)

has a pulley on one end. The rope is routed through the tubing and over the pulley. When the gin pole is attached to the tower and the tubing extended into place, the rope may be used to haul tower sections or the mast into place. **Fig 5** shows the basic process. A gin pole can be expensive for an individual to buy, especially for a one-time tower installation. Some radio clubs own a gin pole for use by their members. Stores that sell tower sections to amateurs and commercial customers frequently will rent a gin pole to erect the tower. If you attempt to make your own gin pole, use materials heavy enough for the job. Provide a means for securely clamping the pole to the tower. There are many cases on record where homemade gin poles have failed, sending tower sections crashing down amidst the ground crew.

When you use a gin pole, make every effort to keep the load as vertical as possible. Although gin poles are strong, you are asking for trouble if you apply too much lateral force.

INSTALLING ANTENNAS ON THE TOWER

All antenna installations are different in some respects. Therefore, thorough planning is the most important first step in installing any antenna. At the beginning, before anyone climbs the tower, the whole process should be thought through. The procedure should be discussed to be sure each crew member understands what is to be done. Plan how to work out all bugs. Consider what tools and parts must be assembled and what items must be taken up the tower. Extra trips up and down the tower can be avoided by using forethought.

Getting ready to raise a beam requires planning. Done properly, the actual work of getting the antenna into position can be accomplished quite easily with only one person at the top of the tower. The trick is to let the ground crew do all the work and leave the person on the tower free to guide the antenna into position.

Before the antenna can be hoisted into position, the tower and the area around it must be prepared. The ground crew should clear the area around the base while someone climbs the tower to remove any wire antennas or other objects that might get in the way. The first person to climb the tower should also rig the rope and pulley that will be used to raise the antenna. The time to prepare the tower is before the antenna leaves the ground, not after it becomes hopelessly entwined with your 3.5-MHz dipole.

SOME TOWER CLIMBING TIPS

The following tower climbing safety tips were compiled by Tom Willeford, N8ETU. The most important safety factor in any kind of hazardous endeavor is the right attitude. Safety is important and worthy of careful consideration and implementation. The right attitude toward safety is a requirement for tower climbers. Lip service won't do, however; safety must be practiced.

The safe ham's safety attitude is simple: *Don't take any unnecessary chances*. There are no exceptions to this plain and simple rule. It is the first rule of safety and, of course, of climbing. The second rule is equally simple: *Don't be afraid to terminate an activity* (climbing, in this case) at any time if things don't seem to be going well.

Take time to plan your climb; this time is never wasted, and it's the first building block of safety. Talk the climb over with friends who will be helping you. Select the date and alternative dates to do the work. Choose someone to be responsible for all activities on the ground and for all communication with the climbers. Study the structure to be climbed and choose the best route to your objective. Plan emergency ascent and descent paths and methods.

Make a list of emergency phone numbers to keep by your phone, even though they may never be used. Develop a plan for rescuing climbers from the structure, should that become necessary.

Give careful thought to how much time you will need to complete the project. Allow enough time to go up, do the work, and then climb down during daylight hours. Include time for resting during the climb and for completing the work in a quality fashion. Remember that the



Fig 6—If the switch box feeding power to equipment on your tower is equipped with a lock-out hole, use it. With a lock through the hole on the box, the power cannot be accidentally turned back on. (*Photos courtesy of American ED CO®, at left, and Osborn Mfg Corp, at right.*)

temperature changes fast as the sun goes down. Climbing up or down a tower with cold hands and feet is very difficult—and dangerous.

Give careful consideration to the weather, and climb only in good weather. Investigate wind conditions, the temperature, and the weather forecast. The weather can change quickly, so if you're climbing a really tall tower, it may be a good idea to have a weather alert radio handy during the climb. *Never* climb a wet tower.

The person who is going to do the climbing should be the one to disconnect and tag all sources of power to the structure. All switches or circuit breakers should be labeled clearly with DO NOT TOUCH instructions. Use locks on any switches designed to accept them. (See **Fig 6**.) Only the climber should reconnect power sources.

An important part of the climbing plan is to review notes on the present installation and any previous work. It's a good idea to keep a notebook, listing every bolt and nut size on your tower/antenna installation. Then, when you have to go up to make repairs, you'll be able to take the minimum number of tools with you to do the job. If you take too many tools up the tower, there is a much greater chance of dropping something, risking injury to the ground crew and possibly damaging the tool.

It is also a good idea to review the instruction sheets and take them with you. In other words, plan carefully what you are going to do, and what you'll need to do it efficiently and safely.

It's better to use a rope and pulley to hoist tools. Climbing is hard work and there's no sense making it more difficult by carrying a big load of tools. Always rig the pulley and rope so the ground crew raises and lowers tools and equipment.

Climbing Equipment

Equipment is another important safety consideration. By equipment, we don't just mean tools. We mean safety equipment. Safety equipment should be selected and cared for as if your life depends on it—because it does!

The list of safety equipment essential to a safe climb and safe work on the tower should include:

1) A first class safety belt,
2) Safety glasses,
3) Hard hat,
4) Long-sleeved, pull-over shirt with no buttons or openings to snag (long sleeves are especially important for climbing wooden poles),
5) Long pants without cuffs,
6) Firm, comfortable, steel-shank shoes with no-slip soles and well-defined heels, and
7) Gloves that won't restrict finger movement (insulated gloves if you MUST work in cold weather).

Your safety belt should be approved for use on the structure you are climbing. Different structures may require different types of safety hooks or straps. The belt should be light weight, but strength should not be sacrificed to save weight. It should fit you comfortably. All moving parts, such as snap hooks, should work freely. You should inspect safety belts and harnesses carefully and thoroughly before each climb, paying particular attention to stitching, rivets and weight-bearing mechanical parts.



Fig 7—Mark Wilson, K1RO, shows the proper way to attach a safety hook, with the hook opening facing away from the tower. That way the hook can't be accidentally released by pressing it against a tower leg.

Support belt hooks should always be hooked to the D rings in an outward configuration. That is, the opening part of the hook should face away from the tower when engaged in the D rings (see **Fig 7**). Hooks engaged this way are easier to unhook deliberately but won't get squeezed open by a part of the tower or engage and snag a part of the tower while you are climbing. The engagement of these hooks should always be checked visually. A snapping hook makes the same sound whether it's engaged or not. Never check by sound—look to be sure the hook is engaged properly before trusting it.

Remember that the D rings on the safety belt are for support hooks *only*. No tools or lines should be attached to these hooks. Such tools or lines may prevent the proper engagement of support belt hooks, or they may foul the hooks. At best, they could prevent the release of the hooks in an emergency. No one should have to disconnect a support hook to get a tool and then have to reconnect the support hook before beginning to work again. That's foolish.

Equipment you purchase new is best. Homemade belts or home-spliced lines are dangerous. Used belts may have worn or defective stitching, or other faulty components. Be careful of so-called "bargains" that could cost you your life.

Straps, lanyards and lines should be as short as possible. Remember, in general knots reduce the load strength of a line by approximately 50%.

Before actually climbing, check the structure visually. Review the route. Check for obstacles, both natural (like wasp's nests) and man-made. Check the structure supports and add more if necessary. Guy wires can be obstacles to the climb, but it's better to have too many supports than not enough. Check your safety belt, support belts and hooks at the base of the tower. Really test them before you need them. Never leave the ground without a safety belt—even 5 or 10 feet. After all of this, the climb will be a "cake walk" if you are careful.

Climb slowly and surely. Don't overreach or overstep. Patience and watchfulness is rewarded with good hand and foot holds. Take a lesson from rock climbers. Hook on to the tower and rest periodically during the climb. Don't try to rest by wedging an arm or leg in some joint; to rest, hook on. Rests provide an opportunity to review the remainder of the route and to make sure that your safety equipment feels good and is working properly. Rest periods also help you conserve a margin of energy in case of difficulty.

Finally, keep in mind that the most dangerous part of working on a tower occurs when you are actually climbing. Your safety equipment is not hooked up at this time, so be extra careful during the ascent or descent.

You must climb the tower to install or work on an antenna. Nevertheless, any work that can be done on the ground should be done there. If you can do any assembly or make any adjustments on the ground, that's where you should do the work! The less time you have to spend on the tower, the better off you'll be.

When you arrive at the work area, hook on to the tower and review what you have to do. Determine the best position to do the work from, disconnect your safety strap and move to that position. Then reconnect your safety strap at a safe spot, away from joints and other obstacles. If you must move around an obstacle, try to do it while hooked on to the tower. Find a comfortable position and go to work. Don't overreach—move to the work.

Use the right tool for the task. If you don't have it, have the ground crew haul it up. Be patient. Lower tools, don't drop them, when you are finished with them. Dropped tools can bounce and cause injury or damage, or can be broken or lost. It's a good idea to tie a piece of string or light rope to the tools, and to tie the other end to the tower or some other point so if you do drop a tool, it won't fall all the way to the ground. Don't tie tools to the D ring or your safely belt, however!

Beware of situations where an antenna may be off balance. It's hard to obtain the extra leverage needed to handle even a small beam when you are holding it far from the balance point. Leverage can apply to the climber as well as the device being levered. Many slips and skinned knuckles result from such situations. A severely injured hand or finger can be a real problem to a climber.

Before descending, be sure to check all connections and the tightness of all the bolts and nuts that you have worked with. Have the ground crew use the rope and pulley to lower your tools. Lighten your load as much as possible. Remember, you're more tired coming down than going up. While still hooked on, wiggle your toes and move a little to get your senses working again. Check your downward route and begin to descend slowly and even more surely than you went up. Rest is even more important during the descent.

The ground captain is the director of all activities on the ground, and should be the only one to communicate with a person on a tower. Hand-held transceivers can be very helpful for this communication, but no one else should transmit to the workers on the tower. Even minor confusion or misunderstanding about a move to be made could be very dangerous.

"Antenna parties" can be lots of fun, but the joking and fooling around should wait until the job is done and everyone is down safely. Save the celebrating until after the work is completed, even for the ground crew.

These are just a few ideas on tower climbing safety; no list can include everything that you might run into. Check Chapter 22 for additional ideas. *Just remember—you can't be too careful when climbing*. Keep safety in mind while doing antenna work, and help ensure that after you have fallen *for* ham radio, you don't fall *from* ham radio.

THE TOWER SHIELD

A tower can be legally classified as an "attractive nuisance" that could cause injuries. You should take some precautions to ensure that "unauthorized climbers" can't get hurt on your tower. This tower shield was originally described by Baker Springfield, W4HYY, and Richard Ely, WA4VHM, in September 1976 *QST*, and should eliminate the worry.

Generally, the attractive-nuisance doctrine applies to your responsibility to trespassers on your property. (The law is much stricter with regard to your responsibility to an invited guest.) You should expect your tower to attract children, whether they are already technically trespassing



Fig 8—Z-bracket component pieces.


Two 6" Pieces Bound Together
to Make One "Z" Bracket.
"Panel - Bracket" Mounting
Screw Holes in This
Vertical Part.
No Holes Drilled in
Lip Part of "Z" Backet.
Two 8-32 X 1/2" Brass Binding
Screws. These are Two
"Z" Bracket Binding Screws.

Fig 9—Assembly of the Z bracket.


PANEL WITH MOUNTED "Z" BRACKET
Lip or Channel
of "Z" Bracket
Shown Hooked
on Tower Rung
"Panel - Bracket"
Mounting Screws
Two per Bracket
Tower Rung
Outside of Panel
This Side of Panel Towards
Inside of Tower

Fig 10—Installation of the shield on a tower rung.


5 -1/4"
2-3/8"
1-1/2"
1-1/2"
2-5/8"
1/4-20
2 Nuts
3/8"
This Bend Makes
The Hook of The Handle
5"
Panel Holes for Handle Should Be 5"
Center to Center Two Pairs are Used.
Notes:
1. Standard Rodstock 1/4"-20 X 36" was Used.
2. Two Pieces were Cut from Rod Stock.
Each Approximately 10 7/8".
3. Make The Three Bends of The Rod in Vise.
4. Two Nuts 1/4-20 of The Same Threads as
Rods. Jam or Lock Together.This Makes
a Handle Stop.

Fig 11—Removable handle construction.

or whether the tower itself lures them onto your property. A tower is dangerous to children, especially because of their inability to appreciate danger. (What child could resist trying to climb a tower once they see one?) Because of this danger, you have a legal duty to exercise reasonable care to eliminate the danger or otherwise protect children against the perils of the attraction.

The tower shield is composed simply of panels that enclose the tower and make climbing practically impossible. These panels are 5 feet in height and are wide enough to fit snugly between the tower legs and flat against the rungs. A height of 5 feet is sufficient in almost every case. The panels are constructed from 18-gauge galvanized sheet metal obtained and cut to proper dimensions from a local sheet-metal shop. A lighter gauge could probably be used, but the extra physical weight of the heavier gauge is an advantage if no additional means of securing the panels to the tower rungs are used. The three types of metals used for the components of the shield are supposedly rust proof and nonreactive. The panels are galvanized sheet steel, the brackets aluminum, and the screws and nuts are brass. For a triangular tower, the shield consists of three panels, one for each of the three sides, supported by two brackets. Construct these brackets from 6-inch pieces of thin aluminum angle stock. Bolt two of the pieces together to form a Z bracket (see **Figs 8**, **9** and **10**). The Z brackets are bolted together with binding head brass machine screws.

Lay the panels flat for measuring, marking and drilling. First measure from the top of the upper mounting rung on the tower to the top of the bottom rung. (Mounting rungs are selected to position the panel on the tower.) Then mark this distance on the panels. Use the same size brass screws and nuts throughout the shield. Bolt the top vertical portion of each Z bracket to the panel. Drill the mounting-screw holes about 1 inch from the end of the Z



Fig 12—Installed tower shield. Note the holes for using the handles.

brackets so there is an offset clearance between the Z-bracket binding-screw holes and the panel-bracket mounting-screw holes. Drill holes in each panel to match the Z-bracket holes.

The panels are held on the tower by their own weight. They are not easy to grasp because they fit snugly between the tower legs. If you feel a need for added safety against deliberate removal of the panels, this can be accomplished by means of tie wires. Drill a small hole in the panel just above, just below, and in the center of each Z bracket. Run a piece of heavy galvanized wire through the top hole, around the Z bracket, and then back through the hole just below the Z bracket. Twist together the two ends of the wire. One tie wire should be sufficient for each panel, but use two if desired.

The completed panels are rather bulky and difficult to handle. A feature that is useful if the panels have to be removed often for tower climbing or accessibility is a pair of removable handles. The removable handles can be constructed from one threaded rod and eight nuts (see **Fig 11**). Drill two pair of handle holes in the panels a few inches below the top Z bracket and several inches above the bottom Z bracket. For panel placement or removal, you can hook the handles in these panel holes. The hook, on the top of the handle, fits into the top hole of each pair of the handle holes. The handle is optional, but for the effort required it certainly makes removal and replacement much safer and easier.

Fig 12 shows the shield installed on a tower. This relatively simple device could prevent an accident.

Electrical Safety

Although the RF, ac and dc voltages in most amateur stations pose a potentially grave threat to life and limb, common sense and knowledge of safety practices will help you avoid accidents. Building and operating an Amateur Radio station can be, and is for almost all amateurs, a perfectly safe pastime. However, carelessness can lead to severe injury, or even death. The ideas presented here are only guidelines; it would be impossible to cover all safety precautions. Remember, there is no substitute for common sense.

A fire extinguisher is a requirement for the well-equipped amateur station. The fire extinguisher should be of the carbon-dioxide type to be effective in electrical fires. Store it in an easy-to-reach spot and check it at recommended intervals.

Family members should know how to turn the power off in your station. They should also know how to apply artificial respiration. Many community groups offer courses on cardiopulmonary resuscitation (CPR).

AC AND DC SAFETY

The primary wiring for your station should be controlled by one master switch, and other members of your household should know how to kill the power in an emergency. All equipment should be connected to a good ground. All wires carrying power around the station should be of the proper size for the current to be drawn and should be insulated for the voltage level involved. Bare wire, open-chassis construction and exposed connections are an invitation to accidents. Remember that high-current, low-voltage power sources are just as dangerous as high-voltage, low-current sources. Possibly the most-dangerous voltage source in your station is the 120-V primary supply; it is a hazard often overlooked because it is a part of everyday life. Respect even the lowliest power supply in your station.

Whenever possible, kill the power and unplug equipment before working on it. Discharge capacitors with an insulated screwdriver; don't assume the bleeder resistors are 100% reliable. In a power amplifier, always short the tube plate cap to ground just to be sure the supply is discharged. If you must work on live equipment, keep one hand in your pocket. Avoid bodily contact with any grounded object to prevent your body from becoming the return path from a voltage source to ground. Use insulated tools for adjusting or moving any circuitry. Never work alone. Have someone else present; it could save your life in an emergency.

National Electrical Code

The National Electrical Code® is a comprehensive document that details safety requirements for all types of electrical installations. In addition to setting safety standards for house wiring and grounding, the Code also contains a section on Radio and Television Equipment — Article 810. Sections C and D specifically cover Amateur Transmitting and Receiving Stations. Highlights of the section concerning Amateur Radio stations follow. If you are interested in learning more about electrical safety, you may purchase a copy of *The National Electrical Code* or *The National Electrical Code Handbook*, edited by Peter Schram, from the National Fire Protection Association, Batterymarch Park, Quincy, MA 02269.

Antenna installations are covered in some detail in the Code. It specifies minimum conductor sizes for different length wire antennas. For hard-drawn copper wire, the Code specifies #14 wire for open (unsupported) spans less than 150 feet, and #10 for longer spans. Copper-clad steel, bronze or other high-strength conductors may be #14 for spans less than 150 feet and #12 wire for longer runs. Lead-in conductors (for open-wire transmission line) should be at least as large as those specified for antennas.

The Code also says that antenna and lead-in conductors attached to buildings must be firmly mounted at least 3 inches clear of the surface of the building on nonabsorbent insulators. The only exception to this minimum distance is when the lead-in conductors are enclosed in a "permanently and effectively grounded" metallic shield. The exception covers coaxial cable.

According to the Code, lead-in conductors (except those covered by the exception) must enter a building through a rigid, noncombustible, nonabsorbent insulating tube or bushing, through an opening provided for the purpose that provides a clearance of at least 2 inches or through a drilled window pane. All lead-in conductors to transmitting equipment must be arranged so that accidental contact is difficult.

Transmitting stations are required to have a means of draining static charges from the antenna system. An antenna discharge unit (lightning arrester) must be installed on each lead-in conductor (except where the lead-in is protected by a continuous metallic shield that is permanently and effectively grounded, or the antenna is permanently and effectively grounded). An acceptable alternative to lightning arrester installation is a switch that connects the lead-in to ground when the transmitter is not in use.

Grounding conductors are described in detail in the Code. Grounding conductors may be made from copper, aluminum, copper-clad steel, bronze or similar erosion-resistant material. Insulation is not required. The "protective grounding conductor" (main conductor running to the ground rod) must be as large as the antenna lead-in, but not smaller than #10. The "operating grounding conductor" (to bond equipment chassis together) must be at least #14. Grounding conductors must be adequately supported and arranged so they are not easily damaged. They must run in as straight a line as practical between the mast or discharge unit and the ground rod.

The Code also includes some information on safety inside the station. All conductors inside the building must be at least 4 inches away from conductors of any lighting or signaling circuit except when they are separated from other conductors by conduit or a nonconducting material. Transmitters must be enclosed in metal cabinets, and the cabinets must be grounded. All metal handles and controls accessible by the operator must be grounded. Access doors must be fitted with interlocks that will disconnect all potentials above 350 V when the door is opened.

Ground

An effective ground system is necessary for every amateur station. The mission of the ground system is twofold. First, it reduces the possibility of electrical shock if something in a piece of equipment should fail and the chassis or cabinet becomes "hot." If connected properly, three-wire electrical systems ground the chassis, but older amateur equipment may use the ungrounded two-wire system. A ground system to prevent shock hazards is generally referred to as "dc ground."

The second job the ground system must perform is to provide a low-impedance path to ground for any stray RF current inside the station. Stray RF can cause equipment to malfunction and contributes to RFI problems. This low-impedance path is usually called "RF ground." In most stations, dc ground and RF ground are provided by the same system.

The first step in building a ground system is to bond together the chassis of all equipment in your station. Ordinary hookup wire will do for a dc ground, but for a good RF ground you need a low-impedance conductor. Copper strap, sold as "flashing copper," is excellent for this application, but it may be hard to find. Braid from coaxial cable is a popular choice; it is readily available, makes a low-impedance conductor, and is flexible.

Grounding straps can be run from equipment chassis to equipment chassis, but a more convenient approach is illustrated in **Fig 13**. In this installation, a $^1/_2$-inch diameter copper water pipe runs the entire length of the operating bench. A thick braid (from discarded RG-8 cable) runs from each piece of equipment to a clamp on the pipe. Copper water pipe is available at most hardware stores and home centers. Alternatively, a strip of flashing copper may be run along the rear of the operating bench.

After the equipment is bonded to a common ground bus, the ground bus must be wired to a good earth ground. This run should be made with a heavy conductor (braid is a popular choice, again) and should be as short and direct as possible. The earth ground usually takes one of two forms.

In most cases, the best approach is to drive one or more ground rods into the earth at the point where the conductor from the station ground bus leaves the house. The best ground rods to use are those available from an electrical supply house. These rods are 8 to 10 feet long and are made from steel with a heavy copper plating. Do not depend on shorter, thinly plated rods sold by some home electronics suppliers. These rods begin to rust almost immediately after they are driven into the soil, and they become worthless within a short time. Good ground rods, while more expensive initially, offer long-term protection.

If your soil is soft and contains few rocks, an acceptable alternative to "genuine" ground rods is $^1/_2$-inch diameter copper water pipe. A 6- to 8-foot length of this material offers a good ground, but it may bend while being driven into the earth. Some people have recommended that you make a connection to a water line and run water down through the copper pipe so that it forces its own


Low Impedance Conductor, as Short as Possible
Three Wire Grounded Power Outlets Connected to Grounded House Electrical System
Clamp Securely
Ground Bus (1/2" Copper Pipe)
Ground Level
6' to 8'
Hose Clamp
Braid to Equipment
Transceiver
Transmatch
Keyer
Antenna Switch
Ground Rod
Operating Position

Fig 13—An effective station ground bonds the chassis of all equipment together with low-impedance conductors and ties into a good earth ground.

hole in the ground. There may be a problem with this method, however. When the ground dries, it may shrink away from the pipe and not make proper contact with the ground rod. This would provide a rather poor ground.

Once the ground rod is installed, clamp the conductor from the station ground bus to it with a clamp that can be tightened securely and will not rust. Copper-plated clamps made especially for this purpose are available from electrical supply houses, but a stainless-steel hose clamp will work too. Alternatively, drill several holes through the pipe and bolt the conductor in place.

Another popular station ground is the cold water pipe system in the building. To take advantage of this ready-made ground system, run a low-impedance conductor from the station ground bus to a convenient cold water pipe, preferably somewhere near the point where the main water supply enters the house. Avoid hot water pipes; they do not run directly into the earth. The advent of PVC (plastic) plumbing makes it mandatory to inspect the cold water system from your intended ground connection to the main inlet. PVC is an excellent insulator, so any PVC pipe or fittings rule out your cold water system for use as a station ground.

For some installations, especially those located above the first floor, a conventional ground system such as that just described will make a fine dc ground but will not provide the necessary low-impedance path to ground for RF. The length of the conductor between the ground bus and the ultimate ground point becomes a problem. For example, the ground wire may be about $^1/_4$ λ (or an odd multiple of $^1/_4$ λ) long on some amateur band. A $^1/_4$-λ wire acts as an impedance inverter from one end to the other. Since the grounded end is at a very low impedance, the equipment end will be at a high impedance. The likely result is RF hot spots around the station while the transmitter is operating. A ground system like this may be worse than having no ground at all.

An alternative RF ground system is shown in **Fig 14**. Connect a system of $^1/_4$-λ radials to the station ground bus. Install at least one radial for each band used. You should still be sure to make a connection to earth ground for the ac power wiring. Try this system if you have problems with RF in the shack. It may just solve a number of problems for you. Be careful, however, to prevent contact with the ends of the radials, where there is high-voltage RF for powers greater than QRP level.


to Transmitter
SWR Bridge
Coax
Transmatch
to Antenna
Quarter Wave Radials (At Least One For Each Band Used)

Fig 14—Here is an alternative to earth ground if the station is located far from the ground point and RF in the station is a problem. Install at least one $^1/_4$-λ radial for each band used.

Ground Noise

Noise in ground systems can affect sensitive radio equipment. It is usually related to one of three problems:

1) Insufficient ground conductor size,
2) Loose ground connections, or
3) Ground loops.

These matters are treated in precise scientific research equipment and some industrial instruments by paying attention to certain rules. The ground conductor should be at least as large as the largest conductor in the primary power circuit. Ground conductors should provide a solid connection to both ground and to the equipment being grounded. Liberal use of lock washers and star washers is highly recommended. A loose ground connection is a tremendous source of noise, particularly in a sensitive receiving system.

Ground loops should be avoided at all costs. A short discussion of what a ground loop is and how to avoid them may lead you down the proper path. A ground loop is formed when more than one ground current is flowing in a single conductor. This commonly occurs when grounds are "daisy-chained" (series linked). The correct way to ground equipment is to bring all ground conductors out radially from a common point to either a good driven earth ground or to a cold water system.

Ground noise can affect transmitted as well as received signals. With the low audio levels required to drive amateur transmitters, and with the ever-increasing sensitivity of our receivers, correct grounding is critical.

Lightning and EMP Protection

The National Fire Protection Association (NFPA) publishes a booklet called *Lightning Protection Code* (NFPA no. 78-1983) that should be of interest to radio amateurs. For information about obtaining a copy of this booklet, write to the National Fire Protection Association, Batterymarch Park, Quincy, MA 02269. Two paragraphs of particular interest to amateurs are presented below:

"3-26 Antennas. Radio and television masts of metal, located on a protected building, shall be bonded to the lightning protection system with a main size conductor and fittings.

"3-27 Lightning arresters, protectors or antenna discharge units shall be installed on electric and telephone service entrances and on radio and television antenna lead-ins."

The best protection from lightning is to disconnect all antennas from equipment and disconnect the equipment from the power lines. Ground antenna feed lines to safely bleed off static buildup. Eliminate the possible paths for lightning strokes. Rotator cables and other control cables from the antenna location should also be disconnected during severe electrical storms.

In some areas, the probability of lightning surges entering homes via the 120/240-V line may be high. Lightning produces both electrical and magnetic fields that vary with distance. These fields can be coupled into power lines and destroy electronic components in equipment that is miles from where the lightning occurred. Radio equipment can be protected from these surges to some extent by using transient-protective devices.

ELECTROMAGMETIC PULSE AND THE RADIO AMATEUR

The following material is based on a 4-part *QST* article by Dennis Bodson, W4PWF, that appeared in the August through November 1986 issues of *QST*. The series was condensed from the National Communications System report NCS TIB 85-10.

An equipment test program demonstrated that most Amateur Radio installations can be protected from lightning and electromagnetic pulse (EMP) transients with a basic protection scheme. Most of the equipment is not susceptible to damage when all external cabling is removed. You can duplicate this stand-alone configuration simply by unplugging the ac power cord from the outlet, disconnecting the antenna feed line at the rear of the radio, and isolating the radio gear from any other long metal conductors. Often it is not practical to completely disconnect the equipment whenever it is not being used. Also, there is the danger that a lightning strike several miles away could induce a large voltage transient on the power lines or antenna while the radio is in use. You can add two transient-protection devices to the interconnected system, however, that will also closely duplicate the safety of the stand-alone configuration.

The ac power line and antenna feed line are the two important points that should be outfitted with transient protection. This is the minimum basic protection scheme recommended for all Amateur Radio installations. (For fixed installations, consideration should also be given to the rotator connections—see **Fig 15**.) Hand-held radios equipped with a "rubber duck" require no protection at the antenna jack. If a larger antenna is used with the hand-held, however, a protection device should be installed.

General Considerations

Because of the unpredictable energy content of a nearby lightning strike or other large transient, it is possible for a metal-oxide varistor (MOV) to be subjected to an energy surge in excess of its rated capabilities. This may result in the destruction of the MOV and explosive rupture of the package. These fragments can cause damage to nearby components or operators and possibly ignite flammable material. Therefore, the MOV should be physically shielded.

A proper ground system is a key factor in achieving protection from lightning and EMP transients. A low-impedance ground system should be installed to eliminate transient paths through radio equipment and to provide a good physical ground for the transient-suppression devices. A single-point ground system is recommended (**Fig 16**) to help prevent lightning from getting into the shack on the shields of antenna feed-line coaxes. Many hams use a well-grounded radio-entrance panel mounted *outside* the shack to ground their coaxes before they enter the house. **Fig 17** shows an entrance panel at K8CH's home in Michigan. All external conductors going to the radio equipment should enter and exit the station through this panel. Install all transient-suppression devices directly on the panel. Use


Antenna
Legend:
P1–P2 – Plug in AC Power Transient Suppressor
C1–C2 – Coaxial Line RF Transient Suppressor
R1–R2 – Varistor Boxes and Control Cable Can Be Shielded
C2
Antenna Rotator
R2
Rotator Control Cable
Coax (RG–8)
C1
R1
Ground Panel (Bus Bar) #2 Gauge Solid Wire or Solid Strap
Ground
Ground
Ground
Ground
Ground
Ham Shack (System Ground)
AC Power
P2
AC Power
Coax (RG–8)
P1
AC Power
Audio Cable
Coax
Rotator Control Cable
Speaker
Power Supply
Transceiver
Antenna Matching Network
Rotator Remote Control Unit
13.8 V dc
MIC
Antenna Matching Network Control Cable

Fig 15—Transient suppression techniques applied to an Amateur Radio station.

the shortest length(s) possible of #6 solid wire to connect the radio equipment case(s) to the ground bus.

Ac Power-Line Protection

Tests have indicated that household electrical wiring inherently limits the maximum transient current that it will pass to approximately 120 A. Therefore, if possible, the amateur station should be installed away from the house ac entrance panel and breaker box to take advantage of these limiting effects.

Ac power-line protection can be provided with easy-to-install, plug-in transient protectors. Ten such devices were tested for the article series in 1986. The plug-in-strip units are the best overall choice for a typical amateur installation. They provide the protection needed, they're simple to install and can be easily moved to other operating locations with the equipment.

In their tests, NCS found that the model that provided transient paths to ground from the hot and neutral lines (common mode) as well as the transient path between the hot and neutral lines (normal mode) performed best. The best model used three MOVs and a 3-electrode gas-discharge-tube arrester to provide fast operation and large power dissipation capabilities. This unit was tested repeatedly and operated without failure.

The flood of low-cost computers in the 1990s spawned a host of surge protection devices designed to limit transient voltage spikes coming from the ac line and also through the telephone line into a modem connected to a computer. Many of these devices are well-designed and can be relied upon to provide the protection they claim.

You can, however, easily find a variety of really low-cost bargain strips at flea markets and discount hardware stores. A bargain-brand $6 unit may prove to be a poor bargain indeed if it allows a spike to get through to damage your $2000 computer or $4000 transceiver.

You should be careful to find one that carries a sticker indicating that it meets Underwriters Laboratories safety standard UL 1449. This defines the minimum level of clamping voltage beyond which a surge protector will "fire" to protect the device connected to its output. The UL 1149 limit is 330 V ac. Prices for brand-name units from Tripp Lite, APC or Curtis vary from about $30 to $80, depending on how many ac sockets they have and the number of indicator lights and switched/unswitched sockets. A brand-name device is well worth the small additional cost over the bargain-basement units.

A transient suppressor requires a 3-wire outlet; the outlet should be tested to ensure all wires are properly connected. In older houses, an ac ground may have to be installed by a qualified electrician. The ac ground must be available for the plug-in transient suppressor to function properly. The ac ground of the receptacle should be attached to the station ground bus, and the plug-in receptacle should be installed on the ground panel behind the radio equipment.

Emergency Power Generators

Emergency power generators provide two major transient-protection advantages. First, the station is disconnected from the commercial ac power system. This isolates the radio equipment from a major source of damaging transients. Second, tests have shown that the emergency power generator may not be susceptible to EMP transients.

When the radio equipment is plugged directly into the generator outlets, transient protection may not be


Solid Wire
No.6 Gauge
or Larger
Buried 1" Deep
Tower
Grounds
AC Power
Ground
System
Ground
Telephone
Ground
(A)
Transient
Suppressors
Radio
Equipment
Ground Panel
Coaxial Cable
RF
Transient Path
to Ground
AC Power
TELCO
GND
(B)
Buried Ground Wire
Antenna
Ground
System
Ground
AC Power
Ground
Telephone Co
Ground

Fig 16—At A, the proper method of tying all ground points together. The transient path to ground with a single-point ground system and use of transient suppressors is shown at B. You want to keep transients from nearby lightning strikes from getting into the radio room.

needed. If an extension cord or household wiring is used, transient protection should be employed.

An emergency power generator should be wired into the household circuit only by a qualified electrician. When properly connected, a switch is used to disconnect the commercial ac power source from the house lines before the generator is connected to them. This keeps the generator output from feeding back into the commercial power system. If this is not done, death or injury to unsuspecting linemen can result.

Feed-Line Protection

Coaxial cable is recommended for use as the transmission line because it provides a certain amount of transient surge protection for the equipment to which it is attached. The outer conductor shields the center conductor from the transient field. Also, the cable limits the maximum conducted transient voltage on the center by arcing the differential voltage from the center conductor to the grounded cable shield.

By providing a path to ground ahead of the radio equipment, the gear can be protected from the large currents impressed upon the antenna system by lightning and EMP. A single protection device installed at the radio antenna jack will protect the radio, but not the transmission line. To protect the transmission line, another tran-



Fig 17—Radio-entrance panel at K8CH. A flat aluminum plate serves as a common grounding point for all coax cables to prevent transients from nearby lightning strikes from getting into the shack on the feed lines. "Spark-gap" protectors to kill transients on the coax inner conductors are located behind the panel. A spark-gap protector is also used on the two open-wire feeder insulators mounted on the Plexiglas sheet behind the aluminum panel.

sient protector must be installed between the antenna and the transmission line. (See Fig 15).

RF transient protection devices from several manufacturers were tested (see **Table 1**) using RG-8 cable equipped with UHF connectors. All of the devices shown can be installed in a coaxial transmission line. Recall that during the tests the RG-8 cable acted like a suppressor; damaging EMP energy arced from the center conductor to the cable shield when the voltage level approached 5.5 kV.

Low price and a low clamping-voltage rating must be considered in the selection of an RF transient-protection device. The lower cost devices have the higher clamping voltages, however, and the higher-cost devices have the lower clamping voltages. Because of this, medium-priced devices manufactured by Fischer Custom Communications were selected for testing. The Fischer Spikeguard Suppressors ($55 price class) for coaxial lines can be made to order to operate at a specific clamping voltage. The Fischer devices satisfactorily suppressed the damaging transient pulses, passed the transmitter RF output power without interfering with the signal, and operated effectively over a wide frequency range.

Polyphaser Corporation devices are also effective in providing the necessary transient protection. The devices available limited the transmitter RF output power to 100 W or less, however. These units cost approximately $83 each.

RF coaxial protectors should be mounted on the station ground bus bar. If the Fischer device is used, it should be attached to a grounded UHF receptacle that will serve as a hold-down bracket. This creates a conductive path between the outer shield of the protector and the bus bar. The Polyphaser device can be mounted directly to the bus bar with the bracket provided.

Table 1
RF Coaxial-Line Protectors

Manufacturer	*Device*	*Approximate Cost (US Dollars)*	*Measured High-Z Clamping Voltage (Volts)*
Fischer	FCC-250-300-UHF	55	393
Fischer	FCC-250-350-UHF	55	260
Fischer	FCC-250-150-UHF	55	220
Fischer	FCC-250-120-UHF	55	240
Fischer	FCC-450-120-UHF	55	120
Polyphaser	IS-NEMP	83	140
Polyphaser	IS-NEMP-1	83	150
Polyphaser	IS-NEMP-2	83	160

Note: The transmitter output power, frequency of operation, and transmission line SWR must be considered when selecting any of these devices.

Attach the transceiver or antenna matching network to the grounded protector with a short (6 foot or less) piece of coaxial cable. Although the cable provides a ground path to the bus bar from the radio equipment, it is not a satisfactory transient-protection ground path for the transceiver. Another ground should be installed between the transceiver case and the ground bus using solid #6 wire. The coaxial cable shield should be grounded to the antenna tower leg at the tower base. Each tower leg should have an earth ground connection and be connected to the single-point ground system as shown in Fig 16.

Antenna Rotators

Antenna rotators can be protected by plugging the control box into a protected ac power source and adding protection to the control lines to the antenna rotator. When the control lines are in a shielded cable, the shield must be grounded at both ends. MOVs of the proper size should be installed at both ends of the control cable. At the station end, terminate the control cable in a small metal box that is connected to the station ground bus. Attach MOVs from each conductor to ground inside the box. At the antenna end of the control cable, place the MOVs inside the rotator case or in a small metal box that is properly grounded.

For example, the Alliance HD73 antenna rotator uses a 6-conductor unshielded control cable with a maximum control voltage of 24.7 V dc. Select an MOV with a clamping voltage level 10% higher (27 V or more) so the MOV won't clamp the control signal to ground. If the control voltage is ac, be sure to convert the RMS voltage value to peak voltage when considering the clamping voltage level.

Mobile Power Supply Protection

The mobile amateur station environment exposes radio equipment to other transient hazards in addition to those of lightning and EMP. Currents as high as 300 A are switched when starting the engine, and this can produce voltage spikes of over 200 V on the vehicle's electrical system. Lightning and EMP are not likely to impact the vehicle's electrical system as much as they would that of a fixed installation because the automobile chassis is not normally grounded. This would not be the case if the vehicle is inadvertently grounded; for example, when the vehicle is parked against a grounded metal conductor. The mobile radio system has two advantages over a fixed installation: Lightning is almost never a problem, and the vehicle battery is a natural surge suppressor.

Mobile radio equipment should be installed in a way that takes advantage of the protection provided by the battery. See **Fig 18**. To do this, connect the positive power lead of the radio directly to the positive battery post, not to intermediate points in the electrical system such as the fuse box or the auxiliary contacts on the ignition switch. To prevent equipment damage or fire, in-line fuses should be installed in the positive lead where they are attached to the battery post.

An MOV should be installed between the two leads of the equipment power cord. A GE MOV (V36ZA80) is recommended for this application. This MOV provides the lowest measured clamping voltage (170 V) and is low in cost.

Mobile Antenna Installation

Although tests indicate that mobile radios can survive an EMP transient without protection for the antenna system, protection from lightning transients is still required. A coaxial-line transient suppressor should be installed on the vehicle chassis between the antenna and the radio's antenna connector.

A Fischer suppressor can be attached to a UHF receptacle that is mounted on, and grounded to, the vehicle chassis. The Polyphaser protector can be mounted on, and grounded to, the vehicle chassis with its flange. Use a short length of coaxial cable between the radio and the transient suppressor.

Clamping Voltage Calculation

When selecting any EMP-protection device to be used at the antenna port of a radio, several items must be considered. These include transmitter RF power output, the SWR, and the operating frequency. The protection device must allow the outgoing RF signal to pass without clamping. A clamping voltage calculation must be made for each amateur installation.

The RF-power input to a transmission line develops a corresponding voltage that becomes important when a voltage-surge arrester is in the line. SWR is important because of its influence on the voltage level. The maximum voltage developed for a given power input is determined by:

$$V = \sqrt{2 \times P \times Z \times SWR} \qquad \text{(Eq 1)}$$

where

P = peak power in W
Z = impedance of the coaxial cable (Ω)
V = peak voltage across the cable

Eq 1 should be used to determine the peak voltage present across the transmission line. Because the RF transient-protection devices use gas-discharge tubes, the voltage level at which they clamp is not fixed; a safety margin must be added to the calculated peak voltage. This is done



Fig 18—Recommended method of connecting mobile radio equipment to the vehicle battery and antenna.

by multiplying the calculated value by a factor of three. This added safety margin is required to ensure that the transmitter's RF output power will pass through the transient suppressor without causing the device to clamp the RF signal to ground. The final clamping voltage obtained is then high enough to allow normal operation of the transmitter while providing the lowest practical clamping voltage for the suppression device. This ensures the maximum possible protection for the radio system.

Here's how to determine the clamping voltage required. Let's assume the SWR is 1.5:1. The power output of the transceiver is 100 W PEP. RG/8 coaxial cable has an impedance of 52 Ω. Therefore:

P = 100 W
Z = 52 Ω
SWR = 1.5

Substituting these values into Eq 1:

$$V = \sqrt{2 \times 100 \times 52 \times 1.5} = 124.89 \text{ V peak}$$

Note that the voltage, V, is the peak value at the peak of the RF envelope. The final clamping voltage (FCV) is three times this value, or 374.7 V. Therefore, a coaxial-line transient suppressor that clamps at or above 375 V should be used.

The cost of a two-point basic protection scheme is estimated to be $100 for each fixed amateur station. This includes the cost of a good quality plug-in power-line protector ($45) and one Fischer coaxial-line protector ($55).

Inexpensive Transient-Protection Devices

Here are two low-cost protection devices you can assemble. They performed flawlessly in the tests.

The radio antenna connection can be protected by means of another simple device. As shown in **Fig 19**, two spark gaps (Siemens BI-A350) are installed in series at one end of a coaxial-cable T connector. Use the shortest practical lead length (about 1/4 inch) between the two spark gaps. One lead is bent forward and forced between the split sections of the inner coaxial connector until the spark gaps approach the body of the connector. A short length of insulating material (such as Mylar) is placed between the spark gaps and the connector shell. The other spark-gap lead is folded over the insulator, then conductive (metallic) tape is wrapped around the assembly. This construction method proved durable enough to allow many insertions and removals of the device during testing. Estimated cost of this assembly is $9. Similar devices can be built using components from Joslyn, General Electric, General Semiconductor or Siemens.

Summary

Amateurs should be aware of which components in their radio system are most likely to be damaged by EMP. They should also know how to repair the damaged equipment. Amateurs should know how to reestablish communications after an EMP event, taking into consideration its adverse effects on the earth's atmosphere and radio equipment. One of the first things that would be noticed, providing the radio equipment is operative, is a sudden silence in radio transmissions across all frequencies below approximately 100 MHz. This silence would be caused in part by damage to unprotected radio gear from the EMP transient. Transmissions from one direction, the direction of the nuclear blast, would be completely out. RF signal loss by absorption and attenuation by the nuclear fireball are the reasons for this.



Fig 19—Pictorial diagram of an inexpensive, homemade RF coax transient protector.

After an EMP event, the amateur should be prepared to operate CW. CW gives the most signal power under adverse conditions. It also provides a degree of message security from the general public.

Amateurs should develop the capability and flexibility to operate in more than one frequency band. The lower ground-wave frequencies should be useful for long-distance communications immediately after an EMP event. Line-of-sight VHF would be of value for local communications.

What can be done to increase the survivability of an Amateur Radio station? Here are some suggestions:

1) If you have spare equipment, keep it disconnected; use only the primary station gear. The spare equipment would then be available after an EMP event.
2) Keep equipment turned off and antenna and power lines disconnected when the equipment is not in use.
3) Connect only those external conductors necessary for the current mode of operation.
4) Tie all fixed equipment to a single-point earth ground to prevent closed loops through the ground.
5) Obtain schematic diagrams of your equipment and tools for repair of the equipment.
6) Have spare parts on hand for sensitive components of the radio equipment and antenna system.
7) Learn how to repair or replace the sensitive components of the radio equipment.
8) Use nonmetallic guy lines and antenna structural parts where possible.
9) Obtain an emergency power source and operate from

it during periods of increased world political tension. The power source should be completely isolated from the commercial power lines.

10) Equipment power cords should be disconnected when the gear is idle. Or the circuit breaker for the line feeding the equipment should be kept in the OFF position when the station is off the air.
11) Disconnect the antenna lead-in when the station is off the air. Or use a grounding antenna switch and keep it in the GROUND position when the equipment is not in use.
12) Have a spare antenna and transmission line on hand to replace a damaged antenna system.
13) Install EMP surge arresters and filters on all primary conductors attached to the equipment and antenna.
14) Retain tube type equipment and spare components; keep them in good working order.
15) Do not rely on a microprocessor to control the station after an EMP event. Be able to operate without microprocessor control.

The recommendations contained in this section were developed with low cost in mind; they are not intended to cover all possible combinations of equipment and installation methods found in the amateur community. Amateurs should examine their own requirements and use this report as a guideline in providing protection for the equipment.

RF Radiation and Electromagnetic Field Safety

Amateur Radio is basically a safe activity. In recent years, however, there has been considerable discussion and concern about the possible hazards of electromagnetic radiation (EMR), including both RF energy and power-frequency (50-60 Hz) electromagnetic (EM) fields. FCC regulations set limits on the maximum permissible exposure (MPE) allowed from the operation of radio transmitters. These regulations do not take the place of RF-safety practices, however. This section deals with the topic of RF safety.

This section was prepared by members of the ARRL RF Safety Committee and coordinated by Dr Robert E. Gold, WBØKIZ. It summarizes what is now known and offers safety precautions based on the research to date.

All life on Earth has adapted to survive in an environment of weak, natural, low-frequency electromagnetic fields (in addition to the Earth's static geomagnetic field). Natural low-frequency EM fields come from two main sources: the sun, and thunderstorm activity. But in the last 100 years, man-made fields at much higher intensities and with a very different spectral distribution have altered this natural EM background in ways that are not yet fully understood. Researchers continue to look at the effects of RF exposure over a wide range of frequencies and levels.

Both RF and 60-Hz fields are classified as *nonionizing radiation,* because the frequency is too low for there to be enough photon energy to ionize atoms. (*Ionizing radiation*, such as X-rays, gamma rays and even some ultraviolet radiation has enough energy to knock electrons loose from their atoms. When this happens, positive and negative ions are formed.) Still, at sufficiently high power densities, EMR poses certain health hazards. It has been known since the early days of radio that RF energy can cause injuries by heating body tissue. (Anyone who has ever touched an improperly grounded radio chassis or energized antenna and received an *RF burn* will agree that this type of injury can be quite painful.) In extreme cases, RF-induced heating in the eye can result in cataract formation, and can even cause blindness. Excessive RF heating of the reproductive organs can cause sterility. Other health problems also can result from RF heating. These heat-related health hazards are called *thermal effects.* A microwave oven is a positive application of this thermal effect.

There also have been observations of changes in physiological function in the presence of RF energy levels that are too low to cause heating. These functions return to normal when the field is removed. Although research is ongoing, no harmful health consequences have been linked to these changes.

In addition to the ongoing research, much else has been done to address this issue. For example, FCC regulations set limits on exposure from radio transmitters. The Institute of Electrical and Electronics Engineers, the American National Standards Institute and the National Council for Radiation Protection and Measurement, among others, have recommended voluntary guidelines to limit human exposure to RF energy. The ARRL has established the RF Safety Committee, consisting of concerned medical doctors and scientists, serving voluntarily to monitor scientific research in the fields and to recommend safe practices for radio amateurs.

THERMAL EFFECTS OF RF ENERGY

Body tissues that are subjected to *very high* levels of RF energy may suffer serious heat damage. These effects depend on the frequency of the energy, the power density of the RF field that strikes the body and factors such as the polarization of the wave.

At frequencies near the body's natural resonant frequency, RF energy is absorbed more efficiently, and an increase in heating occurs. In adults, this frequency usually is about 35 MHz if the person is grounded, and about 70 MHz if insulated from the ground. Individual body parts may be resonant at different frequencies. The adult head, for example, is resonant around 400 MHz, while a baby's smaller head resonates near 700 MHz. Body size thus determines the frequency at which most RF energy is absorbed. As the frequency is moved farther from resonance, less RF heating generally occurs. *Specific absorption rate (SAR)* is a term that describes the rate at which RF energy is absorbed in tissue.

Maximum permissible exposure (MPE) limits are based on whole-body SAR values, with additional safety factors included as part of the standards and regulations. This helps explain why these safe exposure limits vary with frequency. The MPE limits define the maximum electric and magnetic field strengths or the plane-wave equivalent power densities associated with these fields, that a person may be exposed to without harmful effect—and with an acceptable safety factor. The regulations assume that a person exposed to a specified (safe) MPE level also will experience a safe SAR.

Nevertheless, thermal effects of RF energy should not be a major concern for most radio amateurs, because of the power levels we normally use and the intermittent nature of most amateur transmissions. Amateurs spend more time listening than transmitting, and many amateur transmissions such as CW and SSB use low-duty-cycle modes. (With FM or RTTY, though, the RF is present continuously at its maximum level during each transmission.) In any event, it is rare for radio amateurs to be subjected to RF fields strong enough to produce thermal effects, unless they are close to an energized antenna or un- shielded power amplifier. Specific suggestions for avoiding excessive exposure are offered later in this chapter.

ATHERMAL EFFECTS OF EMR

Research about possible health effects resulting from exposure to the lower level energy fields, the athermal effects, has been of two basic types: epidemiological research and laboratory research.

Scientists conduct laboratory research into biological mechanisms by which EMR may affect animals including humans. Epidemiologists look at the health patterns of large groups of people using statistical methods. These epidemiological studies have been inconclusive. By their basic design, these studies do not demonstrate cause and effect, nor do they postulate mechanisms of disease. Instead, epidemiologists look for associations between an environmental factor and an observed pattern of illness. For example, in the earliest research on malaria, epidemiologists observed the association between populations with high prevalence of the disease and the proximity of mosquito infested swamplands. It was left to the biological and medical scientists to isolate the organism causing malaria in the blood of those with the disease, and identify the same organisms in the mosquito population.

In the case of athermal effects, some studies have identified a weak association between exposure to EMF at home or at work and various malignant conditions including leukemia and brain cancer. A larger number of equally well designed and performed studies, however, have found no association. A risk ratio of between 1.5 and 2.0 has been observed in positive studies (the number of observed cases of malignancy being 1.5 to 2.0 times the "expected" number in the population). Epidemiologists generally regard a risk ratio of 4.0 or greater to be indicative of a strong association between the cause and effect under study. For example, men who smoke one pack of cigarettes per day increase their risk for lung cancer tenfold compared to nonsmokers, and two packs per day increases the risk to more than 25 times the nonsmokers' risk.

Epidemiological research by itself is rarely conclusive, however. Epidemiology only identifies health patterns in groups—it does not ordinarily determine their cause. And there are often confounding factors: Most of us are exposed to many different environmental hazards that may affect our health in various ways. Moreover, not all studies of persons likely to be exposed to high levels of EMR have yielded the same results.

There also has been considerable laboratory research about the biological effects of EMR in recent years. For example, some separate studies have indicated that even fairly low levels of EMR might alter the human body's circadian rhythms, affect the manner in which T lymphocytes function in the immune system and alter the nature of the electrical and chemical signals communicated through the cell membrane and between cells, among other things. Although these studies are intriguing, they do not demonstrate any effect of these low-level fields on the overall organism.

Much of this research has focused on low-frequency magnetic fields, or on RF fields that are keyed, pulsed or modulated at a low audio frequency (often below 100 Hz). Several studies suggested that humans and animals can adapt to the presence of a steady RF carrier more readily than to an intermittent, keyed or modulated energy source.

The results of studies in this area, plus speculations concerning the effect of various types of modulation, were and have remained somewhat controversial. None of the research to date has demonstrated that low-level EMR causes adverse health effects.



Fig 20—1991 RF protection guidelines for body exposure of humans. It is known officially as the "IEEE Standard for Safety Levels with Respect to Human Exposure to Radio Frequency Electromagnetic Fields, 3 kHz to 300 GHz."

Given the fact that there is a great deal of ongoing research to examine the health consequences of exposure to EMF, the American Physical Society (a national group of highly respected scientists) issued a statement in May 1995 based on its review of available data pertaining to the possible connections of cancer to 60-Hz EMF exposure. This report is exhaustive and should be reviewed by anyone with a serious interest in the field. Among its general conclusions were the following:

1. The scientific literature and the reports of reviews by other panels show no consistent, significant link between cancer and power line fields.
2. No plausible biophysical mechanisms for the systematic initiation or promotion of cancer by these extremely weak 60-Hz fields has been identified.
3. While it is impossible to prove that no deleterious health effects occur from exposure to any environmental factor, it is necessary to demonstrate a consistent, significant, and causal relationship before one can conclude that such effects do occur.

In a report dated October 31, 1996, a committee of the National Research Council of the National Academy of Sciences has concluded that no clear, convincing evidence exists to show that residential exposures to electric and magnetic fields (EMFs) are a threat to human health.

A National Cancer Institute epidemiological study of residential exposure to magnetic fields and acute lymphoblastic leukemia in children was published in the *New England Journal of Medicine* in July 1997. The exhaustive, seven-year study concludes that if there is any link at all, it is far too weak to be concerned about.

Readers may want to follow this topic as further studies are reported. Amateurs should be aware that exposure to RF and ELF (60 Hz) electromagnetic fields at all power levels and frequencies has not been fully studied under all circumstances. "Prudent avoidance" of any avoidable EMR is always a good idea. Prudent avoidance doesn't mean that amateurs should be fearful of using their equipment. Most amateur operations are well within the MPE limits. If any risk does exist, it will almost surely fall well down on the list of causes that may be harmful to your health (on the other end of the list from your automobile). It does mean, however, that hams should be aware of the potential for exposure from their stations, and take whatever reasonable steps they can take to minimize their own exposure and the exposure of those around them.

Safe Exposure Levels

How much EM energy is safe? Scientists and regulators have devoted a great deal of effort to deciding upon safe RF-exposure limits. This is a very complex problem, involving difficult public health and economic considerations. The recommended safe levels have been revised downward several times over the years —and not all scientific bodies agree on this question even today. An Institute of Electrical and Electronics Engineers (IEEE) standard for recommended EM exposure limits was published in 1991 (see Bibliography). It replaced a 1982 American National Standards Institute (ANSI) standard. In the new standard, most of the permitted exposure levels were revised downward (made more stringent), to better reflect the current research. The new IEEE stan-

FCC RF-Exposure Regulations

FCC regulations control the amount of RF exposure that can result from your station's operation (§§97.13, 97.503, 1.1307 (b)(c)(d), 1.1310 and 2.1093). The regulations set limits on the maximum permissible exposure (MPE) allowed from operation of transmitters in all radio services. They also require that certain types of stations be evaluated to determine if they are in compliance with the MPEs specified in the rules. The FCC has also required that five questions on RF environmental safety practices be added to Novice, Technician and General license examinations.

These rules went into effect on January 1, 1998 for new stations or stations that file a Form 605 application with the FCC. Other existing stations have until September 1, 2000 to be in compliance with the rules.

The Rules

Maximum Permissible Exposure (MPE)

All radio stations regulated by the FCC must comply with the requirements for MPEs, even QRP stations running only a few watts or less. The MPEs vary with frequency, as shown in **Table A**. MPE limits are specified in maximum electric and magnetic fields for frequencies below 30 MHz, in power density for frequencies above 300 MHz and all three ways for frequencies from 30 to 300 MHz. For compliance purposes, all of these limits must be considered *separately*. If any one is exceeded, the station is not in compliance.

The regulations control human exposure to RF fields, not the strength of RF fields. There is no limit to how strong a field can be as long as no one is being exposed to it, although FCC regulations require that amateurs use the minimum necessary power at all times (§97.311 [a]).

Environments

The FCC has defined two exposure environments — *controlled* and *uncontrolled*. A controlled environment is one in which the people who are being exposed are aware of that exposure and can take steps to minimize that exposure, if appropriate. In an uncontrolled environment, the people being exposed are not normally aware of the exposure. The uncontrolled environment limits are more stringent than the controlled environment limits.

Although the controlled environment is usually intended as an occupational environment, the FCC has determined that it generally applies to amateur operators and members of their immediate households. In most cases, controlled-environment limits can be applied to your home and property to which you can control physical access. The uncontrolled environment is intended for areas that are accessible by the general public, such as your neighbors' properties.

The MPE levels are based on average exposure. An averaging time of 6 minutes is used for controlled exposure; an averaging period of 30 minutes is used for uncontrolled exposure.

Table A—(From §1.1310) Limits for Maximum Permissible Exposure (MPE)

(A) Limits for Occupational/Controlled Exposure

Frequency Range (MHz)	*Electric Field Strength (V/m)*	*Magnetic Field Strength (A/m)*	*Power Density (mW/cm^2)*	*Averaging Time (minutes)*
0.3-3.0	614	1.63	(100)*	6
3.0-30	1842/f	4.89/f	(900/f^2)*	6
30-300	61.4	0.163	1.0	6
300-1500	—	—	f/300	6
1500-100,000	—	—	5	6

f = frequency in MHz

* = Plane-wave equivalent power density (see Note 1).

(B) Limits for General Population/Uncontrolled Exposure

Frequency Range (MHz)	*Electric Field Strength (V/m)*	*Magnetic Field Strength (A/m)*	*Power Density (mW/cm^2)*	*Averaging Time (minutes)*
0.3-1.34	614	1.63	(100)*	30
1.34-30	824/f	2.19/f	(180/f^2)*	30
30-300	27.5	0.073	0.2	30
300-1500	—	—	f/1500	30
1500-100,000	—	—	1.0	30

f = frequency in MHz

* = Plane-wave equivalent power density (see Note 1).

Note 1: This means the equivalent far-field strength that would have the E or H-field component calculated or measured. It does not apply well in the near field of an antenna. The equivalent far-field power density can be found in the near or far field regions from the relationships: $P_d = |E_{total}|^2 / 3770$ mW/cm^2 or from $P_d = |H_{total}|^2 \times 37.7$ mW/cm^2

Station Evaluations

The FCC requires that certain amateur stations be evaluated for compliance with the MPEs. Although an amateur can have someone else do the evaluation, it is not difficult for hams to evaluate their own stations. The ARRL book *RF Exposure and You* contains extensive information about the regulations and a large chapter of tables that show compliance distances for specific antennas and power levels. Generally, hams will use these tables to evaluate their stations. Some of these tables have been included in the FCC's information — *OET Bulletin 65* and its *Supplement B*. If hams choose, however, they can do more extensive calculations, use a computer to model their antenna and exposure, or make actual measurements.

Table B—Power Thresholds for Routine Evaluation of Amateur Radio Stations

Wavelength Band	***Evaluation Required if Power* (watts) Exceeds:***
MF	
160 m	500
HF	
80 m	500
75 m	500
40 m	500
30 m	425
20 m	225
17 m	125
15 m	100
12 m	75
10 m	50
VHF (all bands)	50
UHF	
70 cm	70
33 cm	150
23 cm	200
13 cm	250
SHF (all bands)	250
EHF (all bands)	250
Repeater stations (all bands)	*non-building-mounted antennas*: height above ground level to lowest point of antenna < 10 m *and* power > 500 W ERP *building-mounted antennas*: power > 500 W ERP

*Transmitter power = Peak-envelope power input to antenna. For repeater stations ***only,*** power exclusion based on ERP (effective radiated power).

Categorical Exemptions

Some types of amateur stations do not need to be evaluated, but these stations must still comply with the MPE limits. The station licensee remains responsible for ensuring that the station meets these requirements.

The FCC has exempted these stations from the evaluation requirement because their output power, operating mode and frequency are such that they are presumed to be in compliance with the rules.

Stations using power equal to or less than the levels in **Table B** do not have to be evaluated. For the 100-W HF ham station, for example, an evaluation would be required *only* on 12 and 10 meters.

Hand-held radios and vehicle-mounted mobile radios that operate using a push-to-talk (PTT) button are also categorically exempt from performing the routine evaluation. Repeater stations that use less than 500 W ERP or those with antennas not mounted on buildings, if the antenna is at least 10 meters off the ground, also do not need to be evaluated.

Correcting Problems

Most hams are already in compliance with the MPE requirements. Some amateurs, especially those using indoor antennas or high-power, high-duty-cycle modes such as a RTTY bulletin station and specialized stations for moonbounce operations and the like may need to make adjustments to their station or operation to be in compliance.

The FCC permits amateurs considerable flexibility in complying with these regulations. As an example, hams can adjust their operating frequency, mode or power to comply with the MPE limits. They can also adjust their operating habits or control the direction their antenna is pointing.

More Information

This discussion offers only an overview of this topic; additional information can be found in *RF Exposure and You* and on *ARRLWeb* at **www.arrl.org/news/rfsafety/**. *ARRLWeb* has links to the FCC Web site, with *OET Bulletin 65* and *Supplement B* and links to software that hams can use to evaluate their stations.

dard was adopted by ANSI in 1992.

The IEEE standard recommends frequency-dependent and time-dependent maximum permissible exposure levels. Unlike earlier versions of the standard, the 1991 standard recommends different RF exposure limits in controlled environments (that is, where energy levels can be accurately determined and everyone on the premises is aware of the presence of EM fields) and in uncontrolled environments (where energy levels are not known or where people may not be aware of the presence of EM fields). FCC regulations also include controlled/occupational and uncontrolled/general population exposure environments.

The graph in **Fig 20** depicts the 1991 IEEE standard. It is necessarily a complex graph, because the standards differ not only for controlled and uncontrolled environments but also for electric (E) fields and magnetic (H) fields. Basically, the lowest E-field exposure limits occur at frequencies between 30 and 300 MHz. The lowest H-field exposure levels occur at 100-300 MHz. The ANSI standard sets the maximum E-field limits between 30 and 300 MHz at a power density of 1 mW/cm^2 (61.4 V/m) in controlled environments—but at one-fifth that level (0.2 mW/cm^2 or 27.5 V/m) in uncontrolled environments. The H-field limit drops to 1 mW/cm^2 (0.163 A/m) at 100-300 MHz in controlled environments and 0.2 mW/cm^2 (0.0728 A/m) in uncontrolled environments. Higher power densities are permitted at frequencies below 30 MHz (below 100 MHz for H fields) and above 300 MHz, based on the concept that the body will not be resonant at those frequencies and will therefore absorb less energy.

In general, the 1991 IEEE standard requires averaging the power level over time periods ranging from 6 to

30 minutes for power-density calculations, depending on the frequency and other variables. The ANSI exposure limits for uncontrolled environments are lower than those for controlled environments, but to compensate for that the standard allows exposure levels in those environments to be averaged over much longer time periods (generally 30 minutes). This long averaging time means that an intermittently operating RF source (such as an Amateur Radio transmitter) will show a much lower power density than a continuous-duty station—for a given power level and antenna configuration.

Time averaging is based on the concept that the human body can withstand a greater rate of body heating (and thus, a higher level of RF energy) for a short time than for a longer period. Time averaging may not be appropriate, however, when considering nonthermal effects of RF energy.

The IEEE standard excludes any transmitter with an output below 7 W because such low-power transmitters would not be able to produce significant whole-body heating. (Recent studies show that hand-held transceivers often produce power densities in excess of the IEEE standard within the head.)

There is disagreement within the scientific community about these RF exposure guidelines. The IEEE standard is still intended primarily to deal with thermal effects, not exposure to energy at lower levels. A small but significant number of researchers now believe athermal effects also should be taken into consideration. Several European countries and localities in the United States have adopted stricter standards than the recently updated IEEE standard.

Another national body in the United States, the National Council for Radiation Protection and Measurement (NCRP), also has adopted recommended exposure guidelines. NCRP urges a limit of 0.2 mW/cm^2 for non-occupational exposure in the 30-300 MHz range. The NCRP guideline differs from IEEE in two notable ways: It takes into account the effects of modulation on an RF carrier, and it does not exempt transmitters with outputs below 7 W.

The FCC MPE regulations are based on parts of the 1992 IEEE/ANSI standard and recommendations of the National Council for Radiation Protection and Measurement (NCRP). The MPE limits under the regulations are slightly different than the IEEE/ANSI limits. Note that the MPE levels apply to the FCC rules put into effect for radio amateurs on January 1, 1998. These MPE requirements do not reflect and include all the assumptions and exclusions of the IEEE/ANSI standard.

Cardiac Pacemakers and RF Safety

It is a widely held belief that cardiac pacemakers may be adversely affected in their function by exposure to electromagnetic fields. Amateurs with pacemakers may ask whether their operating might endanger themselves or visitors to their shacks who have a pacemaker. Because of this, and similar concerns regarding other sources of electromagnetic fields, pacemaker manufacturers apply design methods that for the most part shield the pacemaker circuitry from even relatively high EM field strengths.

It is recommended that any amateur who has a pacemaker, or is being considered for one, discuss this matter with his or her physician. The physician will probably put the amateur into contact with the technical representative of the pacemaker manufacturer. These representatives are generally excellent resources, and may have data from laboratory or "in the field" studies with specific model pacemakers.

One study examined the function of a modern (dual chamber) pacemaker in and around an Amateur Radio station. The pacemaker generator has circuits that receive and process electrical signals produced by the heart, and also generate electrical signals that stimulate (pace) the heart. In one series of experiments, the pacemaker was connected to a heart simulator. The system was placed on top of the cabinet of a 1-kW HF linear amplifier during SSB and CW operation. In another test, the system was placed in close proximity to several 1 to 5-W 2-meter hand-held transceivers. The test pacemaker was connected to the heart simulator in a third test, and then placed on the ground 9 meters below and 5 meters in front of a three-element Yagi HF antenna. No interference with pacemaker function was observed in these experiments.

Although the possibility of interference cannot be entirely ruled out by these few observations, these tests represent more severe exposure to EM fields than would ordinarily be encountered by an amateur—with an average amount of common sense. Of course, prudence dictates that amateurs with pacemakers, who use hand-held VHF transceivers, keep the antenna as far as possible from the site of the implanted pacemaker generator. They also should use the lowest transmitter output required for adequate communication. For high power HF transmission, the antenna should be as far as possible from the operating position, and all equipment should be properly grounded.

Low-Frequency Fields

Although the FCC doesn't regulate 60-Hz fields, some recent concern about EMR has focused on low-frequency energy rather than RF. Amateur Radio equipment can be a significant source of low-frequency magnetic fields, although there are many other sources of this kind of energy in the typical home. Magnetic fields can be measured relatively accurately with inexpensive 60-Hz meters that are made by several manufacturers.

Table 2 shows typical magnetic field intensities of Amateur Radio equipment and various household items. Because these fields dissipate rapidly with distance, "prudent avoidance" would mean staying perhaps 12 to 18 inches away from most Amateur Radio equipment (and

24 inches from power supplies with 1-kW RF amplifiers).

Determining RF Power Density

Unfortunately, determining the power density of the RF fields generated by an amateur station is not as simple as measuring low-frequency magnetic fields. Although sophisticated instruments can be used to measure RF power densities quite accurately, they are costly and require frequent recalibration. Most amateurs don't have access to such equipment, and the inexpensive field-

Table 2

Typical 60-Hz Magnetic Fields Near Amateur Radio Equipment and AC-Powered Household Appliances

Values are in milligauss.

Item	*Field*	*Distance*
Electric blanket	30-90	Surface
Microwave oven	10-100	Surface
	1-10	12″
IBM personal computer	5-10	Atop monitor
	0-1	15″ from screen
Electric drill	500-2000	At handle
Hair dryer	200-2000	At handle
HF transceiver	10-100	Atop cabinet
	1-5	15″ from front
1-kW RF amplifier	80-1000	Atop cabinet
	1-25	15″ from front

(Source: measurements made by members of the ARRL RF Safety Committee)

Table 3

Typical RF Field Strengths Near Amateur Radio Antennas

A sampling of values as measured by the Federal Communications Commission and Environmental Protection Agency, 1990

Antenna Type	*Freq (MHz)*	*Power (W)*	*E Field (V/m)*	*Location*
Dipole in attic	14.15	100	7-100	In home
Discone in attic	146.5	250	10-27	In home
Half sloper	21.5	1000	50	1 m from base
Dipole at 7-13 ft	7.14	120	8-150	1-2 m from earth
Vertical	3.8	800	180	0.5 m from base
5-element Yagi at 60 ft	21.2	1000	10-20	In shack
			14	12 m from base
3-element Yagi at 25 ft	28.5	425	8-12	12 m from base
Inverted V at 22-46 ft	7.23	1400	5-27	Below antenna
Vertical on roof	14.11	140	6-9	In house
			35-100	At antenna tuner
Whip on auto roof	146.5	100	22-75	2 m antenna
			15-30	In vehicle
			90	Rear seat
5-element Yagi at 20 ft	50.1	500	37-50	10 m antenna

Table 4

RF Awareness Guidelines

These guidelines were developed by the ARRL RF Safety Committee, based on the FCC/EPA measurements of Table 3 and other data.

- Although antennas on towers (well away from people) pose no exposure problem, make certain that the RF radiation is confined to the antennas' radiating elements themselves. Provide a single, good station ground (earth), and eliminate radiation from transmission lines. Use good coaxial cable or other feed line properly. Avoid serious imbalance in your antenna system and feed line. For high-powered installations, avoid end-fed antennas that come directly into the transmitter area near the operator.
- No person should ever be near any transmitting antenna while it is in use. This is especially true for mobile or ground-mounted vertical antennas. Avoid transmitting with more than 25 W in a VHF mobile installation unless it is possible to first measure the RF fields inside the vehicle. At the 1-kW level, both HF and VHF directional antennas should be at least 35 ft above inhabited areas. Avoid using indoor and attic-mounted antennas if at all possible. If open-wire feeders are used, ensure that it is not possible for people (or animals) to come into accidental contact with the feed line.
- Don't operate high-power amplifiers with the covers removed, especially at VHF/UHF.
- In the UHF/SHF region, never look into the open end of an activated length of waveguide or microwave feed-horn antenna or point it toward anyone. (If you do, you may be exposing your eyes to more than the maximum permissible exposure level of RF radiation.) Never point a high-gain, narrow-bandwidth antenna (a paraboloid, for instance) toward people. Use caution in aiming an EME (moonbounce) array toward the horizon; EME arrays may deliver an effective radiated power of 250,000 W or more.
- With hand-held transceivers, keep the antenna away from your head and use the lowest power possible to maintain communications. Use a separate microphone and hold the rig as far away from you as possible. This will reduce your exposure to the RF energy.
- Don't work on antennas that have RF power applied.
- Don't stand or sit close to a power supply or linear amplifier when the ac power is turned on. Stay at least 24 inches away from power transformers, electrical fans and other sources of high-level 60-Hz magnetic fields.

strength meters that we do have are not suitable for measuring RF power density.

Table 3 shows a sampling of measurements made at Amateur Radio stations by the Federal Communications Commission and the Environmental Protection Agency in 1990. As this table indicates, a good antenna well removed from inhabited areas poses no hazard under any of the IEEE/ANSI guidelines. However, the FCC/EPA survey also indicates that amateurs must be careful about using indoor or attic-mounted antennas, mobile antennas, low directional arrays or any other antenna that is close to inhabited areas, especially when moderate to high power is used.

Ideally, before using any antenna that is in close proximity to an inhabited area, you should measure the RF power density. If that is not feasible, the next best option is make the installation as safe as possible by observing the safety suggestions listed in **Table 4**.

It also is possible, of course, to calculate the probable power density near an antenna using simple equations. Such calculations have many pitfalls. For one, most of the situations where the power density would be high enough to be of concern are in the near field. In the near field, ground interactions and other variables produce power densities that cannot be determined by simple arithmetic. In the far field, conditions become easier to predict with simple calculations.

The boundary between the near field and the far field depends on the wavelength of the transmitted signal and the physical size and configuration of the antenna. The boundary between the near field and the far field of an antenna can be as much as several wavelengths from the antenna.

Computer antenna-modeling programs are another approach you can use. *MININEC* or other codes derived from *NEC* (Numerical Electromagnetics Code) are suitable for estimating RF magnetic and electric fields around amateur antenna systems.

These models have limitations. Ground interactions must be considered in estimating near-field power densities, and the "correct ground" must be modeled. Computer modeling is generally not sophisticated enough to predict "hot spots" in the near field—places where the field intensity may be far higher than would be expected, due to reflections from nearby objects. In addition, "nearby objects" often change or vary with weather or the season, so the model so laboriously crafted may not be representative of the actual situation, by the time it is running on the computer.

Intensely elevated but localized fields often can be detected by professional measuring instruments. These "hot spots" are often found near wiring in the shack, and metal objects such as antenna masts or equipment cabinets. But even with the best instrumentation, these measurements also may be misleading in the near field.

One need not make precise measurements or model the exact antenna system, however, to develop some idea of the relative fields around an antenna. Computer modeling using close approximations of the geometry and power input of the antenna will generally suffice. Those who are familiar with *MININEC* can estimate their power densities by computer modeling, and those who have access to professional power-density meters can make useful measurements.

While our primary concern is ordinarily the intensity of the signal radiated by an antenna, we also should remember that there are other potential energy sources to be considered. You also can be exposed to RF radiation directly from a power amplifier if it is operated without proper shielding. Transmission lines also may radiate a significant amount of energy under some conditions. Poor microwave waveguide joints or improperly assembled connectors are another source of incidental radiation.

Further RF Exposure Suggestions

Potential exposure situations should be taken seriously. Based on the FCC/EPA measurements and other data, the "RF awareness" guidelines of Table 4 were developed by the ARRL RF Safety Committee. A longer version of these guidelines, along with a complete list of references, appeared in a *QST* article by Ivan Shulman, MD, WC2S ("Is Amateur Radio Hazardous to Our Health?" *QST* , Oct 1989, pp 31-34). For more information or background, see the list of RF Safety References in the next section.

In addition, the ARRL has published a book, *RF Exposure and You*, that is helping hams comply with the FCC's RF-exposure regulations. The ARRL also maintains an RF-exposure news page on its Web site. See **www.arrl.org/news/rfsafety**. This site contains reprints of selected *QST* articles on RF exposure and links to the FCC and other useful sites.

Chapter 2

Antenna Fundamentals

Antennas belong to a class of devices called *transducers*. This term is derived from two Latin words, meaning literally "to lead across" or "to transfer." Thus, a transducer is a device that transfers, or converts, energy from one form to another. The purpose of an antenna is to convert radio-frequency electric current to *electromagnetic waves*, which are then *radiated* into space. [For more details on the properties of electromagnetic waves themselves, see Chapter 23, Radio Wave Propagation.]

We cannot directly see or hear, taste or touch electromagnetic waves, so it's not surprising that the process by which they are launched into space from our antennas can be a little mystifying, especially to a newcomer. In everyday life we come across many types of transducers, although we don't always recognize them as such. A comparison with a type of transducer that you can actually see and touch may be useful. You are no doubt familiar with a *loudspeaker*. It converts audio-frequency electric current from the output of your radio or stereo into acoustic pressure waves, also known as *sound waves*. The sound waves are propagated through the air to your ears, where they are converted into what you perceive as sound.

We normally think of a loudspeaker as something that converts electrical energy into sound energy, but we could just as well turn things around and apply sound energy to a loudspeaker, which will then convert it into electrical energy. When used in this manner, the loudspeaker has become a microphone. The loudspeaker/microphone thus exhibits the principle of *reciprocity*, derived from the Latin word meaning to move back and forth.

Now, let's look more closely at that special transducer we call an *antenna*. When fed by a transmitter with RF current (usually through a transmission line), the antenna launches electromagnetic waves, which are propagated through space. This is similar to the way sound waves are propagated through the air by a loudspeaker. In the next town, or perhaps on a distant continent, a similar transducer (that is, a receiving antenna) intercepts some of these electromagnetic waves and converts them into electrical current for a receiver to amplify and detect.

In the same fashion that a loudspeaker can act as a microphone, a radio antenna also follows the principle of reciprocity. In other words, an antenna can transmit as well as receive signals. However, unlike the loudspeaker, an antenna does not require a *medium*, such as air, through which it radiates electromagnetic waves. Electromagnetic waves can be propagated through air, the vacuum of outer space or the near vacuum of the upper ionosphere. This is the miracle of radio—electromagnetic waves can propagate without a physical medium.

Essential Characteristics of Antennas

What other things make an antenna different from an ordinary electronic circuit? In ordinary circuits, the dimensions of coils, capacitors and connections usually are small compared with the wavelength of the frequency in use. Here, we define wavelength as the distance in free space traveled during one complete cycle of a wave. The velocity of a wave in free space is the speed of light, and the wavelength is thus:

$$\lambda_{\text{meters}} = \frac{299.7925 \times 10^6 \text{ meters/sec}}{\text{f hertz}} = \frac{299.7925}{\text{f MHz}} \qquad \text{(Eq 1)}$$

where λ_{meters}, the Greek letter lambda, is the free-space wavelength in meters.

Expressed in feet, Eq 1 becomes:

$$\lambda_{feet} = \frac{983.5712}{f\ MHz} \approx \frac{983.6}{f\ MHz} \qquad \text{(Eq 2)}$$

When circuit dimensions are small compared to λ, most of the electromagnetic energy is confined to the circuit itself, and is used up either performing useful work or is converted into heat. However, when the dimensions of wiring or components become significant compared with the wavelength, some of the energy escapes by radiation in the form of electromagnetic waves.

Antennas come in an enormous, even bewildering, assortment of shapes and sizes. This chapter on fundamentals will deal with the theory of simple forms of antennas, usually in *free space*, away from the influence of ground. Subsequent chapters will concentrate on more exotic or specialized antenna types. Chapter 3 deals with the complicated subject of the effect of ground, including the effect of uneven local terrain. Ground has a profound influence on how an antenna performs in the real world.

No matter what form an antenna takes, simple or complex, its electrical performance can be characterized according to the following important properties:

1. Feed-point Impedance
2. Directivity, Gain and Efficiency
3. Polarization

FEED-POINT IMPEDANCE

The first major characteristic defining an antenna is its *feed-point impedance*. Since we amateurs are free to choose our operating frequencies within assigned bands, we need to consider how the feed-point impedance of a particular antenna varies with frequency, within a particular band, or even in several different bands if we intend to use one antenna on multiple bands.

There are two forms of impedance associated with any antenna: *self impedance* and *mutual impedance*. As you might expect, self impedance is what you measure at the feed-point terminals of an antenna located completely away from the influence of any other conductors.

Mutual, or coupled, impedance is due to the parasitic effect of nearby conductors; that is, conductors located within the antenna's reactive near field. (The subject of fields around an antenna will be discussed in detail later.) This includes the effect of ground, which is a lossy conductor, but a conductor nonetheless. Mutual impedance is defined using Ohm's Law, just like self impedance. However, mutual impedance is the ratio of voltage in one conductor, divided by the current in another (coupled) conductor. Mutually coupled conductors can distort the pattern of a highly directive antenna, as well as change the impedance seen at the feed point.

In this chapter on fundamentals, we won't directly deal with mutual impedance, considering it as a side effect of nearby conductors. Instead, here we'll concentrate on simple antennas in free space, away from ground and any other conductors. Mutual impedance will be considered in detail in Chapter 11, HF Yagi Arrays, where it is essential for proper operation of these beam antennas.

Self Impedance

The current that flows into an antenna's feed point must be supplied at a finite voltage. The self impedance of the antenna is simply equal to the voltage applied to its feed point divided by the current flowing into the feed point. Where the current and voltage are exactly in phase, the impedance is purely resistive, with zero reactive component. For this case the antenna is termed *resonant*. (Amateurs often use the term "resonant" rather loosely, usually meaning "nearly resonant" or "close-to resonant.")

Please recognize that an antenna *need not be resonant* in order to be an effective radiator. There is in fact nothing magic about having a resonant antenna, provided of course that you can devise some efficient means to feed the antenna. Many amateurs use non-resonant (even random-length) antennas fed with open-wire transmission lines and antenna tuners. They radiate signals just as well as those using coaxial cable and resonant antennas, and as a bonus they usually can use these antenna systems on multiple frequency bands. It is important to consider an antenna and its feed line as a *system*, in which all losses should be kept to a minimum. See Chapter 24, Transmission Lines, for details on transmission-line loss as a function of impedance mismatch.

Except at the one frequency where it is truly resonant, the current in an antenna is at a different phase compared to the applied voltage. In other words, the antenna exhibits a feed-point *impedance*, not just a pure resistance. The feed-point impedance is composed of either capacitive or inductive reactance in series with a resistance.

Radiation Resistance

The power supplied to an antenna is dissipated in two ways: radiation of electromagnetic waves, and heat losses in the wire and nearby dielectrics. The radiated power is what we want, the useful part, but it represents a form of "loss" just as much as the power used in heating the wire or nearby dielectrics is a loss. In either case, the dissipated power is equal to I^2R. In the case of heat losses, R is a real resistance. In the case of radiation, however, R is a "virtual" resistance, which, if replaced with an actual resistor of the same value, would dissipate the power actually radiated from the antenna. This resistance is called the *radiation resistance*. The total power in the antenna is therefore equal to $I^2(R_0+R)$, where R_0 is the radiation resistance and R represents the total of all the loss resistances.

In ordinary antennas operated at amateur frequencies, the power lost as heat in the conductor does not exceed a few percent of the total power supplied to the antenna. Expressed in decibels, the loss is less than 0.1 dB. The RF loss resistance of copper wire even as small as #14 is very low compared with the radiation resistance of an antenna that is reasonably clear of surrounding objects and is not too close to the ground. You can therefore assume that the ohmic loss in a reasonably well-located antenna is negligible, and that the total resistance shown by the antenna (the feed-point resistance) is radiation resistance. As a radiator of electromagnetic waves, such an antenna is a highly efficient device.

Impedance of a Center-Fed Dipole

A fundamental type of antenna is the *center-fed half-wave dipole*. Historically, the λ/2 dipole has been the most popular antenna used by amateurs worldwide, largely because it is very simple to construct and because it is an effective performer. It is also a basic building block for many other antenna systems, including beam antennas, such as Yagis.

A center-fed half-wave *dipole* consists of a straight wire, one-half wavelength long as defined in Eq 1, and fed in the center. The term "dipole" derives from Greek words meaning "two poles." See **Fig 1**. A λ/2-long dipole is just one form a dipole can take. Actually, a center-fed dipole can be any length electrically, as long as it is configured in a symmetrical fashion with two equal-length legs. There are also versions of dipoles that are not fed in the center. These are called *off-center-fed dipoles*, sometimes abbreviated as "OCF dipoles."

In free space—with the antenna remote from everything else—the theoretical impedance of a physically half-wave long antenna made of an infinitely thin conductor is 73 + *j* 42.5 Ω. This antenna exhibits both resistance and reactance. The positive sign in the + *j* 42.5-Ω reactive term indicates that the antenna exhibits an inductive reactance at its feed point. The antenna is slightly long electrically, compared to the length necessary for exact resonance, where the reactance is zero.



Fig 1—The center-fed dipole antenna. It is assumed that the source of power is directly at the antenna feed point, with no intervening transmission line. Most commonly in amateur applications, the overall length of the dipole is λ/2, but the antenna can in actuality be any length.

The feed-point impedance of any antenna is affected by the wavelength-to-diameter ratio (λ/dia) of the conductors used. Theoreticians like to specify an "infinitely thin" antenna because it is easier to handle mathematically.

What happens if we keep the physical length of an antenna constant, but change the thickness of the wire used in its construction? Further, what happens if we vary the frequency from well below to well above the half-wave resonance and measure the feed-point impedance? **Fig 2** graphs the impedance of a 100-foot long, center-fed dipole in free space, made with extremely thin wire—in this case, wire that is only 0.001 inches in diameter. There is nothing particularly significant about the choice here of 100 feet. This is simply a numerical example.

We could never actually build such a thin antenna (and neither could we install it in free space), but we can model how this antenna works using a very powerful piece of computer software called *NEC-4.1*. See Chapter 4, Antenna Modeling and System Planning, for details on antenna modeling.

The frequency applied to the antenna in Fig 2 is varied from 1 to 30 MHz. The x-axis has a logarithmic scale because of the wide range of feed-point resistance seen over the frequency range. The y-axis has a linear scale representing the reactive portion of the impedance. Inductive reactance is positive and capacitive reactance is negative on the y-axis. The bold figures centered on the spiraling line show the frequency in MHz.

At 1 MHz, the antenna is very short electrically, with a resistive component of about 2 Ω and a series capaci-



Fig 2—Feed-point impedance versus frequency for a theoretical 100-foot long dipole in free space, fed in the center and made of extremely thin 0.001-inch diameter wire. The y-axis is calibrated in positive (inductive) series reactance up from the zero line, and negative (capacitive) series reactance in the downward direction. The range of reactance goes from –6500 Ω to +6000 Ω. Note that the x-axis is logarithmic because of the wide range of the real, resistive component of the feed-point impedance, from roughly 2 Ω to 10,000 Ω. The numbers placed along the curve show the frequency in MHz.



Fig 3—Feed-point impedance versus frequency for a theoretical 100-foot long dipole in free space, fed in the center and made of thin 0.1-inch (#10) diameter wire. Note that the range of change in reactance is less than that shown in Fig 2, ranging from –2700 Ω to +2300 Ω. At about 5,000 Ω, the maximum resistance is also less than that in Fig 2 for the thinner wire, where it is about 10,000 Ω.



Fig 4—Feed-point impedance versus frequency for a theoretical 100-foot long dipole in free space, fed in the center and made of thick 1.0-inch diameter wire. Once again, the excursion in both reactance and resistance over the frequency range is less with this thick wire dipole than with thinner ones.

tive reactance about –5000 Ω. Close to 5 MHz, the line crosses the zero-reactance line, meaning that the antenna goes through half-wave resonance there. Between 9 and 10 MHz the antenna exhibits a peak inductive reactance of about 6000 Ω. It goes through full-wave resonance (again crossing the zero-reactance line) between 9.5 and 9.6 MHz. At about 10 MHz, the reactance peaks at about –6500 Ω. Around 14 MHz, the line again crosses the zero-reactance line, meaning that the antenna has now gone through 3/2-wave resonance.

Between 19 and 20 MHz, the antenna goes through 4/2-wave resonance, which is twice the full-wave resonance or four times the half-wave frequency. If you allow your mind's eye to trace out the curve for frequencies beyond 30 MHz, it eventually spirals down to a resistive component somewhere between 200 and 3000 Ω. Thus, we have another way of looking at an antenna—as a sort of *transformer*, one that transforms the free-space impedance into the impedance seen at its feed point.

Now look at **Fig 3**, which shows the same kind of spiral curve, but for a thicker-diameter wire, one that is 0.1 inches in diameter. This diameter is close to #10 wire, a practical size we might actually use to build a real dipole. Note that the y-axis scale in Fig 3 is different from that in Fig 2. The range is from ±3000 Ω in Fig 3, while it was ±7000 Ω in Fig 2. The reactance for the thicker antenna ranges from +2300 to –2700 Ω over the whole frequency range from 1 to 30 MHz. Compare this with the range of +5800 to –6400 Ω for the very thin wire in Fig 2.

Fig 4 shows the impedance for a 100-foot long dipole using really thick, 1.0-inch diameter wire. The reactance varies from +1000 to –1500 Ω, indicating once again that a larger diameter antenna exhibits less of an excursion in the reactive component with frequency. Note that at the half-wave resonance just below 5 MHz, the resistive component of the impedance is still about 70 Ω, just about what it is for a much thinner antenna. Unlike the reactance, the half-wave radiation resistance of an antenna doesn't radically change with wire diameter, although the maximum level of resistance at full-wave resonance is lower for thicker antennas.



Fig 5—Feed-point impedance versus frequency for a theoretical 100-foot long dipole in free space, fed in the center and made of very thick 10.0-inch diameter wire. This ratio of length to diameter is about the same as a typical rod type of dipole element commonly used at 432 MHz. The maximum resistance is now about 1,000 Ω and the peak reactance range is from about –625 Ω to +380 Ω. This performance is also found in "cage" dipoles, where a number of paralleled wires are used to simulate a fat conductor.

Fig 5 shows the results for a very thick, 10-inch diameter wire. Here, the excursion in the reactive component is even less: about +400 to –600 Ω. Note that the full-wave resonant frequency is about 8 MHz for this



Fig 6—Expansion of frequency range around half-wave resonant point of three center-fed dipoles of three different thicknesses. The frequency is shown along the curves in MHz. The slope of change in series reactance versus series resistance is steeper for the thinner antennas than for the thick 1.0-inch antenna, indicating that the Q of the thinner antennas is higher.



Fig 7—Another way of looking at the data for a 100-foot, center-fed dipole made of #14 wire in free space. The numbers along the curve represent the fractional wavelength, rather than frequency as shown in Fig 6. Note that this antenna goes through its half-wave resonance about 0.488 λ, rather than exactly at a half-wave physical length.



Fig 8—Effect of antenna diameter on length for half-wavelength resonance, shown as a multiplying factor, K, to be applied to the free-space, half-wavelength.

extremely thick antenna, while thinner antennas have full-wave resonances closer to 9 MHz. Note also that the full-wave resistance for this extremely thick antenna is only about 1,000 Ω, compared to the 10,000 Ω shown in Fig 2. All half-wave resonances shown in Figs 2 through 5 remain close to 5 MHz, regardless of the diameter of the antenna wire. Once again, the extremely thick, 10-inch diameter antenna has a resistive component at half-wave resonance close to 70 Ω. And once again, the change in reactance near this frequency is very much less for the extremely thick antenna than for thinner ones.

Now, we grant you that a 100-foot long antenna made with 10-inch diameter wire sounds a little odd! A length of 100 feet and a diameter of 10 inches represent a ratio of 120:1 in length to diameter. However, this is about the same length-to-diameter ratio as a 432-MHz half-wave dipole using 0.25-inch diameter elements, where the ratio is 109:1. In other words, the ratio of length-to-diameter for the 10-inch diameter, 100-foot long dipole is not that far removed from what might actually be used at UHF.

Another way of highlighting the changes in reactance and resistance is shown in **Fig 6**. This shows an expanded portion of the frequency range around the half-wave resonant frequency, from 4 to 6 MHz. In this region, the shape of each spiral curve is almost a straight line. The slope of the curve for the very thin antenna (0.001-inch diameter) is steeper than that for the thicker antennas (0.1 and 1.0-inch diameters). **Fig 7** illustrates another way of looking at the impedance data above and below the half-wave resonance. This is for a 100-foot dipole made of #14 wire. Instead of showing the frequency for each impedance point, the wavelength is shown, making the graph more universal in application.

Just to show that there are lots of ways of looking at the same data, **Fig 8** graphs the constant "K" used to multiply the free-space half-wavelength as a function of the ratio between the half-wavelength and the conductor diameter. The curve approaches the value of 1.00 for an infinitely thin conductor, in other words an infinitely large ratio of half-wavelength to diameter.

The behavior of antennas with different λ/diameter ratios corresponds to the behavior of ordinary series-resonant circuits having different values of Q. When the Q of a circuit is low, the reactance is small and changes rather slowly as the applied frequency is varied on either side of resonance. If the Q is high, the converse is true. The response curve of the low-Q circuit is *broad*; that of the high-Q circuit *sharp*. So it is with antennas—the impedance of a thick antenna changes slowly over a comparatively wide band of frequencies, while a thin antenna has a faster change in impedance. Antenna Q is defined

$$Q = \frac{f_0 \Delta X}{2 R_0 \Delta f} \qquad \text{(Eq 3)}$$

where f_0 is the center frequency, ΔX is the change in the reactance for a Δf change in frequency, and R_0 is the resistance the f_0. For the "Very Thin," 0.001-inch diameter dipole in Fig 2, a change of frequency from 5.0 to 5.5 MHz yields a reactance change from 86 to 351 Ω, with an R_0 of 95 Ω. The Q is thus 14.6. For the 1.0-inch-diameter "Thick" dipole in Fig 4, $\Delta X = 131\ \Omega$ and R_0 is still 95 Ω, making Q = 7.2 for the thicker antenna, roughly half that of the thinner antenna.

Let's recap. We have described an antenna first as a transducer, then as a sort of transformer to a range of free-space impedances. Now, we just compared the antenna to a series-tuned circuit. Near its half-wave resonant frequency, a center-fed λ/2 dipole exhibits much the same characteristics as a conventional series-resonant circuit. Exactly at resonance, the current at the input terminals is in phase with the applied voltage and the feed-point impedance is purely resistive. If the frequency is below resonance, the phase of the current leads the voltage; that is, the reactance of the antenna is capacitive. When the frequency is above resonance, the opposite occurs; the current lags the applied voltage and the antenna exhibits inductive reactance. Just like a conventional series-tuned circuit, the antenna's reactance and resistance determines its Q.

ANTENNA DIRECTIVITY AND GAIN

The Isotropic Radiator

Before we can fully describe practical antennas, we must first introduce a completely theoretical antenna, the *isotropic radiator*. Envision, if you will, an infinitely small antenna, a point located in outer space, completely removed from anything else around it. Then consider an infinitely small transmitter feeding this infinitely small, point antenna. You now have an isotropic radiator.

The uniquely useful property of this theoretical *point-source* antenna is that it radiates equally well in all directions. That is to say, an isotropic antenna favors no direction at the expense of any other—in other words, it has absolutely no *directivity*. The isotropic radiator is useful as a *measuring stick* for comparison with actual antenna systems.

You will find later that real, practical antennas all exhibit some degree of directivity, which is the property of radiating more strongly in some directions than in others. The radiation from a practical antenna never has the same intensity in all directions and may even have zero radiation in some directions. The fact that a practical antenna displays directivity (while an isotropic radiator does not) is not necessarily a bad thing. The directivity of a real antenna is often carefully tailored to emphasize radiation in particular directions. For example, a receiving antenna that favors certain directions can discriminate against interference or noise coming from other directions, thereby increasing the signal-to-noise ratio for desired signals coming from the favored direction.

Directivity and the Radiation Pattern—a Flashlight Analogy

The directivity of an antenna is directly related to the *pattern* of its radiated field intensity in free space. A graph showing the actual or relative field intensity at a fixed distance, as a function of the direction from the antenna system, is called a *radiation pattern*. Since we can't actually see electromagnetic waves making up the radiation pattern of an antenna, we can consider an analogous situation.

Fig 9 represents a flashlight shining in a totally darkened room. To quantify what our eyes are seeing, we might use a sensitive light meter like those used by photographers, with a scale graduated in units from 0 to 10. We place the meter directly in front of the flashlight and adjust the distance so the meter reads 10, exactly full scale. We also carefully note the distance. Then, always keeping the meter the same distance from the flashlight and keeping it at the same height above the floor, we move the light meter around the flashlight, as indicated by the



Fig 9—The beam from a flashlight illuminates a totally darkened area as shown here. Readings taken with a photographic light meter at the 16 points around the circle may be used to plot the radiation pattern of the flashlight.

arrow, and take light readings at a number of different positions.

After all the readings have been taken and recorded, we plot those values on a sheet of polar graph paper, like that shown in **Fig 10**. The values read on the meter are plotted at an angular position corresponding to that for which each meter reading was taken. Following this, we connect the plotted points with a smooth curve, also shown in Fig 10. When this is finished, we have completed a radiation pattern for the flashlight.

Antenna Pattern Measurements

Antenna radiation patterns can be constructed in a similar manner. Power is fed to the antenna under test, and a field-strength meter indicates the amount of signal. We might wish to rotate the antenna under test, rather than moving the measuring equipment to numerous positions about the antenna. Or we might make use of antenna reciprocity, since the pattern while receiving is the same as that while transmitting. A source antenna fed by a low-power transmitter illuminates the antenna under test, and the signal intercepted by the antenna under test is fed to a receiver and measuring equipment. Additional information on the mechanics of measuring antenna patterns is contained in Chapter 27, Antennas and Transmission-Line Measurements.

Some precautions must be taken to assure that the measurements are accurate and repeatable. In the case of the flashlight, let's assume that the separation between the light source and the light meter is 2 meters, about 6.5 feet. The wavelength of visible light is about one-half micron, where a micron is one-millionth of a meter.

For the flashlight, a separation of 2 meters between source and detector is $2.0/(0.5\times10^{-6}) = 4$ million λ, a very large number of wavelengths. Measurements of practical HF or even VHF antennas are made at much closer distances, in terms of wavelength. For example, at 3.5 MHz a full wavelength is 85.7 meters, or 281.0 feet. To duplicate the flashlight-to-light-meter spacing in wavelengths at 3.5 MHz, we would have to place the field-strength measuring instrument almost on the surface of the Moon, about a quarter-million miles away!

The Fields Around an Antenna

Why should we be concerned with the separation between the source antenna and the field-strength meter, which has its own receiving antenna? One important reason is that if you place a receiving antenna very close to an antenna whose pattern you wish to measure, mutual coupling between the two antennas may actually alter the pattern you are trying to measure.

This sort of mutual coupling can occur in the region very close to the antenna under test. This region is called the *reactive near-field* region. The term "reactive" refers to the fact that the mutual impedance between the transmitting and receiving antennas can be either capacitive or inductive in nature. The reactive near field is sometimes called the "induction field," meaning that the magnetic field usually is predominant over the electric field in this region. The antenna acts as though it were a rather large, lumped-constant inductor or capacitor, storing energy in the reactive near field rather than propagating it into space.



Fig 10—The radiation pattern of the flashlight in Fig 9. The measured values are plotted and connected with a smooth curve.

For simple wire antennas, the reactive near field is considered to be within about a half wavelength from an antenna's radiating center. Later on, in the chapters dealing with Yagi and quad antennas, you will find that mutual coupling between elements can be put to good use to purposely shape the radiated pattern. For making pattern measurements, however, we do not want to be too close to the antenna being measured.

The strength of the reactive near field decreases in a complicated fashion as you increase the distance from the antenna. Beyond the reactive near field, the antenna's radiated field is divided into two other regions: the *radiating near field* and the *radiating far field.* Historically, the terms *Fresnel* and *Fraunhöfer* fields have been used for the radiating near and far fields, but these terms have been largely supplanted by the more descriptive terminology used here. Even inside the reactive near-field



Fig 11—The fields around a radiating antenna. Very close to the antenna, the reactive field dominates. Within this area mutual impedances are observed between antenna and any other antennas used to measure response. Outside of the reactive field, the near radiating field dominates, up to a distance approximately equal to 2L²/λ, where L is the length of the largest dimension of the antenna. Beyond the near/far field boundary lies the far radiating field, where power density varies as the inverse square of radial distance.

region, both radiating and reactive fields coexist, although the reactive field predominates very close to the antenna.

Because the boundary between the fields is rather fuzzy, experts debate where one field begins and another leaves off, but the boundary between the radiating near and far fields is generally accepted as:

$$D \approx \frac{2L^2}{\lambda} \qquad \text{(Eq 4)}$$

where L is the largest dimension of the physical antenna, expressed in the same units of measurement as the wavelength λ. Remember, many specialized antennas do not follow the rule of thumb in Eq 4 exactly. **Fig 11** depicts the three fields in front of a simple wire antenna.

Throughout the rest of this book we will discuss mainly the radiating far-fields, those forming the traveling electromagnetic waves. Far-field radiation is distinguished by the fact that the intensity is inversely proportional to the distance, and that the electric and magnetic components, although perpendicular to each other in the wave front, are in time phase. The total energy is equally divided between the electric and magnetic fields. Beyond several wavelengths from the antenna, these are the only fields we need to consider. For accurate measurement of radiation patterns, we must place our measuring instrumentation at least several wavelengths away from the antenna under test.

Pattern Planes

Patterns obtained above represent the antenna radiation in just one plane. In the example of the flashlight, the plane of measurement was at one height above the floor. Actually, the pattern for any antenna is three dimensional, and therefore cannot be represented in a single-plane drawing. The *solid* radiation pattern of an antenna in free space would be found by measuring the field strength at every point on the surface of an imaginary sphere having the antenna at its center. The information so obtained would then be used to construct a solid figure, where the distance from a fixed point (representing the antenna) to the surface of the figure is proportional to the field strength from the antenna in any given direction. **Fig 12B** shows a three-dimensional wire-grid representation of the radiation pattern of a half-wave dipole.

For amateur work, *relative* values of field strength (rather than absolute) are quite adequate in pattern plotting. In other words, it is not necessary to know how many microvolts per meter a particular antenna will produce at a distance of 1 mile when excited with a specified power level. (This is the kind of specifications that AM broadcast stations must meet to certify their antenna systems to the FCC.)

For whatever data is collected (or calculated from theoretical equations), it is common to normalize the plotted values so the field strength in the direction of maximum radiation coincides with the outer edge of the chart. On a given system of polar coordinate scales, the *shape* of the pattern is not altered by proper normalization, only its size.

E and H-Plane Patterns

The solid 3-D pattern of an antenna in free space cannot adequately be shown with field-strength data on a flat sheet of paper. Cartographers making maps of a round Earth on flat pieces of paper face much the same kind of problem. As we discussed above, cross-sectional or plane diagrams are very useful for this purpose. Two such diagrams, one in the plane containing the straight wire of a dipole and one in the plane perpendicular to the wire, can convey a great deal of information. The pattern in the plane containing the axis of the antenna is called the *E-plane pattern*, and the one in the plane perpendicular to the axis is called the *H-plane pattern*. These designations are used because they represent the planes in which the electric (symbol E), and the magnetic (symbol H) lines of force lie, respectively.

The E lines represent the *polarization* of the antenna. Polarization will be covered in more detail later in this chapter. As an example, the electromagnetic field pictured in Fig 1 of Chapter 23, Radio Wave Propagation, is the field that would be radiated from a vertically polarized antenna; that is, an antenna in which the conductor is mounted perpendicular to the earth.

When a radiation pattern is shown for an antenna mounted over ground rather than in free space, we automatically gain two frames of reference—an *azimuth angle* and an *elevation angle*. The azimuth angle is usually ref-



Fig 12—Directive diagram of a free-space dipole. At A, the pattern in the plane containing the wire axis. The length of each dashed-line arrow represents the relative field strength in that direction, referenced to the direction of maximum radiation, which is at right angles to the wire's axis. The arrows at approximately 45° and 315° are the half-power or –3 dB points. At B, a wire grid representation of the solid pattern for the same antenna. These same patterns apply to any center-fed dipole antenna less than a half wavelength long.

Introduction to the Decibel

The power gain of an antenna system is usually expressed in *decibels*. The decibel is a practical unit for measuring power ratios because it is more closely related to the actual effect produced at a distant receiver than the power ratio itself. One decibel represents a just-detectable change in signal strength, regardless of the actual value of the signal voltage. A 20-decibel (20-dB) increase in signal, for example, represents 20 observable steps in increased signal. The power ratio (100 to 1) corresponding to 20 dB gives an entirely exaggerated idea of the improvement in communication to be expected. The number of decibels corresponding to any power ratio is equal to 10 times the common logarithm of the power ratio, or

$$\mathrm{dB} = 10 \log_{10} \frac{P_1}{P_2}$$

If the voltage ratio is given, the number of decibels is equal to 20 times the common logarithm of the ratio. That is,

$$\mathrm{dB} = 20 \log_{10} \frac{V_1}{V_2}$$

When a *voltage* ratio is used, both voltages must be measured across the same value of impedance. Unless this is done the decibel figure is meaningless, because it is fundamentally a measure of a *power* ratio.

The main reason a decibel is used is that successive power gains expressed in decibels may simply be added together. Thus a gain of 3 dB followed by a gain of 6 dB gives a total gain of 9 dB. In ordinary power ratios, the ratios must be multiplied together to find the total gain.

A *reduction* in power is handled simply by subtracting the requisite number of decibels. Thus, reducing the power to ½ is the same as *subtracting* 3 decibels. For example, a power gain of 4 in one part of a system and a reduction to ½ in another part gives a total power gain of 4 × ½ = 2. In decibels, this is 6 – 3 = 3 dB. A power reduction or *loss* is simply indicated by including a negative sign in front of the appropriate number of decibels.

erenced to the maximum radiation lobe of the antenna, where the azimuth angle is defined at 0°, or it could be referenced to the Earth's True North direction for an antenna oriented in a particular compass direction. The E-plane pattern for an antenna over ground is now called the *azimuth pattern*.

The elevation angle is referenced to the horizon at the Earth's surface, where the elevation angle is 0°. Of course, the Earth is round but because its radius is so large, it can in this context be considered to be flat in the area directly under the antenna. An elevation angle of 90° is straight over the antenna, and a 180° elevation is toward the horizon directly behind the antenna.

Professional antenna engineers often describe an antenna's orientation with respect to the point directly overhead—using the *zenith angle*, rather than the elevation angle. The elevation angle is computed by subtracting the zenith angle from 90°.

Referenced to the horizon of the Earth, the H-plane pattern is now called the *elevation pattern*. Unlike the free-space H-plane pattern, the over-ground elevation pattern is drawn as a half-circle, representing only positive elevations above the Earth's surface. The ground reflects or blocks radiation at negative elevation angles, making below-surface radiation plots unnecessary.

After a little practice, and with the exercise of some imagination, the complete solid pattern can be visualized with fair accuracy from inspection of the two planar diagrams, provided of course that the solid pattern of the antenna is *smooth*, a condition that is true for simple antennas like λ/2 dipoles.

Plane diagrams are plotted on polar coordinate paper, as described earlier. The points on the pattern where the radiation is zero are called *nulls*. The curved section from one null to the next on the plane diagram, or the corresponding section on the solid pattern, is called a *lobe*. The strongest lobe is commonly called the *main lobe*. Fig 12A shows the E-plane pattern for a half-wave dipole. In Fig 12, the dipole is placed in free space. In addition to the labels showing the main lobe and nulls in the pattern, the so-called *half-power* points on the main lobe are shown. These are the points where the power is 3 dB down from the peak value in the main lobe.

Directivity and Gain

Let us now examine directivity more closely. As mentioned previously, all practical antennas, even the simplest types such as dipoles, exhibit directivity. Here's another picture that may help explain the concept of directivity. **Fig 13A** shows a balloon blown into its usual spherical shape. This represents a "reference" isotropic source. Squeezing the balloon in the middle in Fig 13B produces a dipole-like figure-8 pattern whose peak levels at top and bottom are larger than the reference sphere. Compare this with Fig 13C. Next, squeezing the bottom end of the balloon produces a pattern that gives even more "gain" compared to the reference.

Free-space directivity can be expressed quantitatively by comparing the three-dimensional pattern of the antenna under consideration with the perfectly spherical three-dimensional pattern of an isotropic antenna. The field strength (and thus power per unit area, or *power density*) is the same everywhere on the surface of an imaginary sphere having a radius of many wavelengths and having an isotropic antenna at its center. At the surface of the same imaginary sphere around an antenna radiating the same total power, the directive pattern results in greater power density at some points on this sphere and less at others. The ratio of the maximum power density to the average power density taken over the entire sphere (which is the same as from the isotropic antenna under the specified conditions) is the numerical measure of the directivity of the antenna. That is,

$$D=\frac{P}{P_{av}} \qquad \text{(Eq 5)}$$



Fig 13—Demonstrating antenna pattern gain with balloons. Take a balloon, blow it up so that it is roughly circular in shape and then declare that this is a radiation pattern from an isotropic radiator. Next, blow up another balloon to the same size and shape and tell the audience that this will be the "reference" antenna (A). Then, squeeze the first balloon in the middle to form a sort of figure-8 shape and declare that this is a dipole and compare the maximum size to that of the reference "antenna" (B). The dipole can be seen to have some "gain" over the reference isotropic. Next, squeeze the end of the first balloon to come up with a sausage-like shape to demonstrate the sort of pattern a beam antenna creates (C).

where

D = directivity
P = power density at its maximum point on the surface of the sphere
P_{av} = average power density

The *gain* of an antenna is closely related to its directivity. Because directivity is based solely on the *shape* of the directive pattern, it does not take into account any power losses that may occur in an actual antenna system. To determine gain, these losses must be subtracted from the power supplied to the antenna. The loss is normally a constant percentage of the power input, so the antenna gain is

$$G = k\frac{P}{P_{av}} = kD \qquad \text{(Eq 6)}$$

where

G = gain (expressed as a power ratio)
D = directivity
k = efficiency (power radiated divided by power input) of the antenna
P and P_{av} are as above

For many of the antenna systems used by amateurs, the efficiency is quite high (the loss amounts to only a few percent of the total). In such cases the gain is essentially equal to the directivity. The more the directive diagram is compressed—or, in common terminology, the *sharper* the lobes—the greater the power gain of the antenna. This is a natural consequence of the fact that as power is taken away from a larger and larger portion of the sphere surrounding the radiator, it is added to the volume represented by the narrow lobes. Power is therefore concentrated in some directions, at the expense of others. In a general way, the smaller the volume of the solid radiation pattern, compared with the volume of a sphere having the same radius as the length of the largest lobe in the actual pattern, the greater the power gain.

As stated above, the gain of an antenna is related to its directivity, and directivity is related to the shape of the directive pattern. A commonly used index of directivity, and therefore the gain of an antenna, is a measure of the width of the major lobe (or lobes) of the plotted pattern. The width is expressed in degrees at the half-power or –3 dB points, and is often called the *beamwidth*.

This information provides only a general idea of relative gain, rather than an exact measure. This is because an absolute measure involves knowing the power density at every point on the surface of a sphere, while a single diagram shows the pattern shape in only one plane of that sphere. It is customary to examine at least the E-plane and the H-plane patterns before making any comparisons between antennas.

A simple approximation for gain over an isotropic radiator can be used, but only if the sidelobes in the antenna's pattern are small compared to the main lobe and if the resistive losses in the antenna are small. When the radiation pattern is complex, numerical integration is employed to give the actual gain.

$$G \approx \frac{41253}{H_{3dB} \times E_{3dB}} \qquad \text{(Eq 7)}$$

where H_{3dB} and E_{3dB} are the half-power points, in degrees, for the H and E-plane patterns.

Radiation Patterns for Center-Fed Dipoles at Different Frequencies

Earlier, we saw how the feed-point impedance of a fixed-length center-fed dipole in free space varies as the frequency is changed. What happens to the radiation pattern of such an antenna as the frequency is changed?

In general, the greater the length of a center-fed antenna, in terms of wavelength, the larger the number of lobes into which the pattern splits. A feature of all such patterns is the fact that the main lobe—the one that gives the largest field strength at a given distance—always is the one that makes the smallest angle with the antenna wire. Furthermore, this angle becomes smaller as the length of the antenna is increased.

Let's examine how the free-space radiation pattern changes for a 100-foot long wire made of #14 wire as the frequency is varied. (Varying the frequency effectively changes the wavelength for a fixed-length wire.) **Fig 14** shows the E-plane pattern at the $\lambda/2$ resonant frequency of 4.8 MHz. This is a classical dipole pattern, with a gain in free space of 2.14 dBi referenced to an isotropic radiator.

Fig 15 shows the free-space E-plane pattern for the same antenna, but now at the full-wave ($2\lambda/2$) resonant frequency of 9.55 MHz. Note how the pattern has been pinched in at the top and bottom of the figure. In other words, the two main lobes have become sharper at this frequency, making the gain 3.73 dBi, higher than at the $\lambda/2$ frequency.



Fig 14—Free-space E-Plane radiation pattern for a 100-foot dipole at its half-wave resonant frequency of 4.80 MHz. This antenna has 2.14 dBi of gain. The dipole is located on the line from 90° to 270°.

Coordinate Scales for Radiation Patterns

A number of different systems of coordinate scales or *grids* are in use for plotting antenna patterns. Antenna patterns published for amateur audiences are sometimes placed on rectangular grids, but more often they are shown using polar coordinate systems. Polar coordinate systems may be divided generally into three classes: linear, logarithmic and modified logarithmic.

A very important point to remember is that the shape of a pattern (its general appearance) is highly dependent on the grid system used for the plotting. This is exemplified in **Fig A**, where the radiation pattern for a beam antenna is presented using three coordinate systems discussed in the paragraphs that follow.



Linear Coordinate Systems

The polar coordinate system for the flashlight radiation pattern, Fig 10, uses linear coordinates. The concentric circles are equally spaced, and are graduated from 0 to 10. Such a grid may be used to prepare a linear plot of the power contained in the signal. For ease of comparison, the equally spaced concentric circles have been replaced with appropriately placed circles representing the decibel response, referenced to 0 dB at the outer edge of the plot. In these plots the minor lobes are suppressed. Lobes with peaks more than 15 dB or so below the main lobe disappear completely because of their small size. This is a good way to show the pattern of an array having high directivity and small minor lobes.

Logarithmic Coordinate System

Another coordinate system used by antenna manufacturers is the logarithmic grid, where the concentric grid lines are spaced according to the logarithm of the voltage in the signal. If the logarithmically spaced concentric circles are replaced with appropriately placed circles representing the decibel response, the decibel circles are graduated linearly. In that sense, the logarithmic grid might be termed a linear-log grid, one having linear divisions calibrated in decibels.

This grid enhances the appearance of the minor lobes. If the intent is to show the radiation pattern of an array supposedly having an omnidirectional response, this grid enhances that appearance. An antenna having a difference of 8 or 10 dB in pattern response around the compass appears to be closer to omnidirectional on this grid than on any of the others. See Fig A-(B).

ARRL Log Coordinate System

The modified logarithmic grid used by the ARRL has a system of concentric grid lines spaced according to the logarithm of 0.89 times the value of the signal voltage. In this grid, minor lobes that are 30 and 40 dB down from the main lobe are distinguishable. Such lobes are of concern in VHF and UHF work. The spacing between plotted points at 0 dB and –3 dB is significantly greater than the spacing between –20 and –23 dB, which in turn is significantly greater than the spacing between –50 and –53 dB.

For example, the scale distance covered by 0 to –3 dB is about $^{1}/_{10}$ of the radius of the chart. The scale distance for the next 3-dB increment (to –6 dB) is slightly less, 89% of the first, to be exact. The scale distance for the next 3-dB increment (to –9 dB) is again 89% of the second. The scale is constructed so that the progression ends with –100 dB at chart center.

The periodicity of spacing thus corresponds generally to the relative significance of such changes in antenna performance. Antenna pattern plots in this publication are made on the modified-log grid similar to that shown in Fig A-(C).



Fig 15—Free-space E-Plane radiation pattern for a 100-foot dipole at its full-wave resonant frequency of 9.55 MHz. The gain has increased to 3.73 dBi, because the main lobes have been focused and sharpened compared to Fig 13.



Fig 16—Free-space E-Plane radiation pattern for a 100-foot dipole at its 3/2λ resonant frequency of 14.60 MHz. The pattern has broken up into six lobes, and thus the peak gain has dropped to 3.44 dBi.

Fig 16 shows the pattern at the 3λ/2 frequency of 14.6 MHz. More lobes have developed compared to Fig 14. This means that the power has split up into more lobes and consequently the gain decreases a small amount, down to 3.44 dBi. This is still higher than the dipole at its λ/2 frequency, but lower than at its full-wave frequency. **Fig 17** shows the E-plane response at 19.45 MHz, the 4λ/2, or 2λ, resonant frequency. Now the pattern has reformed itself into only four lobes, and the gain has as a consequence risen to 3.96 dBi.

In **Fig 18** the response has become quite complex at the 5λ/2 resonance point of 24.45 MHz, with ten lobes showing. Despite the presence all these lobes, the main lobes now show a gain of 4.78 dBi. Finally, **Fig 19** shows the pattern at the 3λ (6λ/2) resonance at 29.45 MHz. Despite the fact that there are fewer lobes taking up power than at 24.45 MHz, the peak gain is slightly less at 29.45 MHz, at 4.70 dBi.

Fig A—Radiation pattern plots for a high-gain Yagi antenna on three different grid coordinate systems. At A, the pattern on a linear-power dB grid. Notice how details of sidelobe structure are lost with this grid. At B, the same pattern on a grid with constant 5 dB circles. The sidelobe level is exaggerated when this scale is employed. At B, the same pattern on the modified log grid used by ARRL. The side and rearward lobes are clearly visible on this grid. The concentric circles in all three grids are graduated in decibels referenced to 0 dB at the outer edge of the chart. The patterns look quite different, yet they all represent the same antenna response!

The pattern—and hence the gain—of a fixed-length antenna varies considerably as the frequency is changed. Of course, the pattern and gain change in the same fashion if the frequency is kept constant and the length of the wire is varied. In either case, the wavelength is changing. It is also evident that certain lengths reinforce the pattern to provide more peak gain. If an antenna is not rotated in azimuth when the frequency is changed, the peak gain may occur in a different direction than you might like. In other words, the main lobes change direction as the frequency is varied.

POLARIZATION

We've now examined the first two of the three major properties used to characterize antennas: the radiation pattern and the feed-point impedance. The third general property is *polarization*. An antenna's polarization is defined to be that of its electric field, in the direction where the field strength is maximum.

For example, if a λ/2 dipole is mounted horizontally over the Earth, the electric field is strongest perpendicular to its axis (that is, at right angle to the wire) and parallel to the earth. Thus, since the maximum electric field is horizontal, the polarization in this case is also considered to be *horizontal* with respect to the earth. If the dipole is mounted vertically, its polarization will be *vertical*. See **Fig 20**. Note that if an antenna is mounted in free space, there is no frame of reference and hence its



Fig 17—Free-space E-Plane radiation pattern for a 100-foot dipole at twice its full-wave resonant frequency of 19.45 MHz. The pattern has been refocused into four lobes, with a peak gain of 3.96 dBi.



Fig 18—Free-space E-Plane radiation pattern for a 100-foot dipole at its 5/2λ resonant frequency of 24.45 MHz. The pattern has broken down into ten lobes, with a peak gain of 4.78 dBi.

polarization is indeterminate.

Antennas composed of a number of λ/2 elements arranged so that their axes lie in the same or parallel directions have the same polarization as that of any one of the elements. For example, a system composed of a group of horizontal dipoles is horizontally polarized. If both horizontal and vertical elements are used in the same plane and radiate in phase, however, the polarization is the *resultant* of the contributions made by each set of elements to the total electromagnetic field at a given point some distance from the antenna. In such a case the resultant polarization is still *linear,* but is tilted between horizontal and vertical.



Fig 19—Free-space E-Plane radiation pattern for a 100-foot dipole at three times its full-wave resonant frequency of 29.45 MHz. The pattern has returned to six lobes, with a peak gain of 4.70 dBi.



Fig 20—Vertical and horizontal polarization of a dipole above ground. The direction of polarization is the direction of the maximum electric field with respect to the earth.

In directions other than those where the radiation is maximum, the resultant wave even for a simple dipole is a combination of horizontally and vertically polarized components. The radiation off the ends of a horizontal dipole is actually vertically polarized, albeit at a greatly reduced amplitude compared to the broadside horizontally polarized radiation—the sense of polarization changes with compass direction.

Thus it is often helpful to consider the radiation pattern from an antenna in terms of polar coordinates, rather than trying to think in purely linear horizontal or vertical coordinates. See **Fig 21**. The reference axis in a polar system is vertical to the earth under the antenna. The zenith angle is usually referred to as θ (Greek letter theta), and the azimuth angle is referred to as ϕ (Greek letter phi). Instead of zenith angles, most amateurs are more familiar with *elevation angles*, where a zenith angle of 0° is the same as an elevation angle of 90°, straight overhead. Native *NEC* or *MININEC* computer programs use zenith angles rather than elevation angles, although most commercial versions automatically reduce these to elevation angles.



Fig 21—Diagram showing polar representation of a point P lying on an imaginary sphere surround a point-source antenna. The various angles associated with this coordinate system are shown referenced to the x, y and z-axes.

If vertical and horizontal elements in the same plane are fed out of phase (where the beginning of the RF period applied to the feed point of the vertical element is not in time phase with that applied to the horizontal), the resultant polarization is *elliptical*. Circular polarization is a special case of elliptical polarization. The wave front of a circularly polarized signal appears (in passing a fixed observer) to rotate every 90° between vertical and horizontal, making a complete 360° rotation once every period. Field intensities are *equal* at all instantaneous polarizations. Circular polarization is frequently used for space communications, and is discussed further in Chapter 19, Antenna Systems for Space Communications.

Sky-wave transmission usually changes the polarization of traveling waves. (This is discussed in Chapter 23, Radio Wave Propagation.) The polarization of receiving and transmitting antennas in the 3 to 30-MHz range, where almost all communication is by means of sky wave, need not be the same at both ends of a communication circuit (except for distances of a few miles). In this range the choice of polarization for the antenna is usually determined by factors such as the height of available antenna supports, polarization of man-made RF noise from nearby sources, probable energy losses in nearby objects, the likelihood of interfering with neighborhood broadcast or TV reception and general convenience.

Other Antenna Characteristics

Besides the three main characteristics of impedance, pattern (gain) and polarization, there are some other useful properties of antennas.

RECIPROCITY IN RECEIVING AND TRANSMITTING

Many of the properties of a resonant antenna used for reception are the same as its properties in transmission. It has the same directive pattern in both cases, and delivers maximum signal to the receiver when the signal comes from a direction in which the antenna has its best response. The impedance of the antenna is the same, at the same point of measurement, in receiving as in transmitting.

In the receiving case, the antenna is the source of power delivered to the receiver, rather than the load for a source of power (as in transmitting). Maximum possible output from the receiving antenna is obtained when the load to which the antenna is connected is the same as the impedance of the antenna. We say that the antenna is *matched* to its load.

The power gain in receiving is the same as the gain in transmitting, when certain conditions are met. One such condition is that both antennas (usually λ/2-long antennas) must work into load impedances matched to their own impedances, so that maximum power is transferred in both cases. In addition, the comparison antenna should be oriented so it gives maximum response to the signal used in the test. That is, it should have the same polarization as the incoming signal and should be placed so its direction of maximum gain is toward the signal source.

In long-distance transmission and reception via the ionosphere, the relationship between receiving and transmitting, however, may not be exactly reciprocal. This is because the waves do not always follow exactly the same paths at all times and so may show considerable variation in the time between alternations between transmitting and receiving. Also, when more than one ionospheric layer is involved in the wave travel (see Chapter 23, Radio Wave Propagation), it is sometimes possible for reception to be good in one direction and poor in the other, over the same path.

Wave polarization usually shifts in the ionosphere. The tendency is for the arriving wave to be elliptically polarized, regardless of the polarization of the transmitting antenna. Vertically polarized antennas can be expected to show no more difference between transmission and reception than horizontally polarized antennas. On the average, however, an antenna that transmits well in a certain direction also gives favorable reception from the same direction, despite ionospheric variations.

FREQUENCY SCALING

Any antenna design can be scaled in size for use on another frequency or on another amateur band. The dimensions of the antenna may be scaled with Eq 8 below.

$$D = \frac{f1}{f2} \times d \qquad \text{(Eq 8)}$$

where

D = scaled dimension

d = original design dimension

f1 = original design frequency

f2 = scaled frequency (frequency of intended operation)

From this equation, a published antenna design for, say, 14 MHz can be scaled in size and constructed for operation on 18 MHz, or any other desired band. Similarly, an antenna design could be developed experimentally at VHF or UHF and then scaled for operation in one of the HF bands. For example, from Eq 8, an element of 39.0 inches length at 144 MHz would be scaled to 14 MHz as follows: D = 144/14 × 39 = 401.1 inches, or 33.43 feet.

To scale an antenna properly, *all* physical dimensions must be scaled, including element lengths, element spacings, boom diameters and element diameters. Lengths and spacings may be scaled in a straightforward manner as in the above example, but element diameters are often not as conveniently scaled. For example, assume a 14-MHz antenna is modeled at 144 MHz and perfected with $^3/_8$-inch cylindrical elements. For proper scaling to 14 MHz, the elements should be cylindrical, of 144/14 × $^3/_8$ or 3.86 inches diameter. From a realistic standpoint, a 4-inch diameter might be acceptable, but cylindrical elements of 4-inch diameter in lengths of 33 feet or so would be quite unwieldy (and quite expensive, not to mention heavy). Choosing another, more suitable diameter is the only practical answer.

Diameter Scaling

Simply changing the diameter of dipole type elements during the scaling process is not satisfactory without making a corresponding element-length correction. This is because changing the diameter results in a change in the λ/dia ratio from the original design, and this alters the corresponding resonant frequency of the element. The element length must be corrected to compensate for the effect of the different diameter actually used.

To be more precise, however, the purpose of diameter scaling is not to maintain the same resonant frequency for the element, but to maintain the same ratio of self-resistance to self-reactance at the operating frequency—that is, the Q of the scaled element should be the same as that of the original element. This is not always possible to achieve exactly for elements that use several telescoping sections of tubing.

Tapered Elements

Rotatable beam antennas are usually constructed with elements made of metal tubing. The general practice at HF is to taper the elements with lengths of telescoping tubing. The center section has a large diameter, but the ends are relatively small. This reduces not only the weight, but also the cost of materials for the elements. Tapering of HF Yagi elements is discussed in detail in Chapter 11, HF Yagi Arrays.

Length Correction for Tapered Elements

The effect of tapering an element is to alter its electrical length. That is to say, two elements of the same length, one cylindrical and one tapered but with the same average diameter as the cylindrical element, will not be resonant at the same frequency. The tapered element must be made longer than the cylindrical element for the same resonant frequency.

A procedure for calculating the length for tapered elements has been worked out by Dave Leeson, W6NL (ex-W6QHS), from work done by Schelkunoff at Bell Labs and is presented in Leeson's book, *Physical Design of Yagi Antennas*. In the software accompanying this book is a subroutine called EFFLEN.FOR. It is written in Fortran and is used in the *SCALE* program to compute the effective length of a tapered element. The algorithm uses the W6NL-Schelkunoff algorithm and is commented step-by-step to show what is happening. Calculations are made for only one half of an element, assuming the element is symmetrical about the point of boom attachment.

Also, read the documentation SCALE.PDF for the *SCALE* program, which will automatically do the complex mathematics to scale a Yagi design from one frequency to another, or from one taper schedule to another.

The Vertical Monopole

So far in this discussion on Antenna Fundamentals, we have been using the free-space, center-fed dipole as our main example. Another simple form of antenna derived from a dipole is called a *monopole*. The name suggests that this is one half of a dipole, and so it is. The monopole is always used in conjunction with a *ground plane*, which acts as a sort of electrical mirror. See **Fig 22**, where a λ/2 dipole and a λ/4 monopole are compared. The *image antenna* for the monopole is the dotted line beneath the ground plane. The image forms the missing second half of the antenna, transforming a monopole into the functional equivalent of a dipole. From this explanation you can see where the term *image plane* is sometimes used instead of ground plane.

Although we have been focusing throughout this chapter on antennas in free space, practical monopoles are usually mounted vertically with respect to the surface of the ground. As such, they are called *vertical monopoles*, or simply *verticals*. A practical vertical is supplied power by feeding the radiator against a ground system, usually made up of a series of paralleled wires radiating from and laid out in a circular pattern around the base of the antenna. These wires are termed *radials*.

The term *ground plane* is also used to describe a vertical antenna employing a λ/4-long vertical radiator working against a *counterpoise* system, another name for the ground plane that supplies the missing half of the antenna. The counterpoise for a ground-plane antenna usually consists of four λ/4-long radials elevated well above the earth. See **Fig 23**.

Chapter 3, The Effects of Ground, devotes much attention to the requirements for an efficient grounding system for vertical monopole antennas, and Chapter 6, Low-Frequency Antennas, gives more information on ground-plane verticals.



Fig 22—The λ/2 dipole antenna and its λ/4 ground-plane counterpart. The "missing" quarter wavelength is supplied as an image in "perfect" (that is, high-conductivity) ground.

Characteristics of a λ/4 Monopole

The free-space directional characteristics of a λ/4 monopole with its ground plane are very similar to that of a λ/2 antenna in free space. The gain for the λ/4 monopole is slightly less because the H-plane for the λ/2 antenna is compressed compared to the monopole. Like a λ/2 antenna, the λ/4 monopole has an *omnidirectional* radiation pattern in the plane perpendicular to the monopole.

The current in a λ/4 monopole varies practically sinusoidally (as is the case with a λ/2 wire), and is highest at the ground-plane connection. The RF voltage is highest at the open (top) end and minimum at the ground plane. The feed-point resistance close to λ/4 resonance of a vertical monopole over a perfect ground plane is one-half that for a λ/2 dipole at its λ/2 resonance. In this case, a "perfect ground plane" is an infinitely large, lossless conductor.

See **Fig 24**, which shows the feed-point impedance of a vertical antenna made of #14 wire, 50 feet long, located over perfect ground. This is over the whole HF range from 1 to 30 MHz. Again, there is nothing special about the choice of 50 feet for the length of the vertical radiator; it is simply a convenient length for evaluation. **Fig 25** shows an expanded portion of the frequency range above and below the λ/4 resonant point, but now calibrated in terms of wavelength. Note that this particular antenna goes through λ/4 resonance at a length of 0.244 λ, not at exactly 0.25 λ. The exact length for resonance varies with the diameter of the wire used, just as it does for the λ/2 dipole at its λ/2 resonance.

The word *height* is usually used for a vertical monopole antenna whose base is on or near the ground, and in this context, height has the same meaning as *length* when applied to λ/2 dipole antennas. Older texts often refer to heights in electrical degrees, referenced to a free-space wavelength of 360°, but here height is expressed in terms of the free-space wavelength. The range shown in Fig 24 is from 0.132 λ to 0.300 λ, corresponding to a frequency range of 2.0 to 5.9 MHz.



Fig 23—The ground-plane antenna. Power is applied between the base of the vertical radiator and the center of the four ground plane wires.



Fig 24—Feed-point impedance versus frequency for a theoretical 50-foot-high grounded vertical monopole made of #14 wire. The numbers along the curve show the frequency in MHz. This was computed using "perfect" ground. Real ground losses will add to the feed-point impedance shown in an actual antenna system.



Fig 25—Feed-point impedance for the same antennas as in Fig 21, but calibrated in wavelength rather than frequency, over the range from 0.132 to 0.300λ, above and below the quarter-wave resonance.

The reactive portion of the feed-point impedance depends highly on the length/dia ratio of the conductor, as was discussed previously for a horizontal center-fed dipole. The impedance curve in Figs 24 and 25 is based on a #14 conductor having a length/dia ratio of about 800 to 1. As usual, thicker antennas can be expected to show less reactance at a given height, and thinner antennas will show more.

Efficiency of Vertical Monopoles

This topic of the efficiency of vertical monopole systems will be covered in detail in Chapter 3, The Effects of Ground, but it is worth noting at this point that the efficiency of a real vertical antenna over real earth often suffers dramatically compared with that of a λ/2 antenna. Without a fairly elaborate grounding system, the efficiency is not likely to exceed 50%, and it may be much less, particularly at monopole heights below λ/4.

BIBLIOGRAPHY

J. S. Belrose, "Short Antennas for Mobile Operation," *QST*, Sep 1953.

G. H. Brown, "The Phase and Magnitude of Earth Currents Near Radio Transmitting Antennas," *Proc IRE*, Feb 1935.

G. H. Brown, R. F. Lewis and J. Epstein, "Ground Systems as a Factor in Antenna Efficiency," *Proc IRE*, Jun 1937, pp 753-787.

G. H. Brown and O. M. Woodward, Jr., "Experimentally Determined Impedance Characteristics of Cylindrical Antennas," *Proc IRE*, April 1945.

A. Christman, "Elevated Vertical Antenna Systems," *QST*, Aug 1988, pp 35-42.

R. B. Dome, "Increased Radiating Efficiency for Short Antennas," *QST*, Sep 1934, pp 9-12.

A. C. Doty, Jr., J. A. Frey and H. J. Mills, "Characteristics of the Counterpoise and Elevated Ground Screen," Professional Program, Session 9, Southcon '83 (IEEE), Atlanta, GA, Jan 1983.

A. C. Doty, Jr., J. A. Frey and H. J. Mills, "Efficient Ground Systems for Vertical Antennas," *QST*, Feb 1983, pp 20-25.

A. C. Doty, Jr., technical paper presentation, "Capacitive Bottom Loading and Other Aspects of Vertical Antennas," Technical Symposium, Radio Club of America, New York City, Nov 20, 1987.

A. C. Doty, Jr., J. A. Frey and H. J. Mills, "Vertical Antennas: New Design and Construction Data," *The ARRL Antenna Compendium, Volume 2* (Newington: ARRL, 1989), pp 2-9.

R. Fosberg, "Some Notes on Ground Systems for 160 Meters," *QST*, Apr 1965, pp 65-67.

G. Grammer, "More on the Directivity of Horizontal Antennas; Harmonic Operation—Effects of Tilting," *QST*, Mar 1937, pp 38-40, 92, 94, 98.

H. E. Green, "Design Data for Short and Medium Length Yagi-Uda Arrays," *Trans IE Australia*, Vol EE-2, No. 1, Mar 1966.

H. J. Mills, technical paper presentation, "Impedance Transformation Provided by Folded Monopole Antennas," Technical Symposium, Radio Club of America, New York City, Nov 20, 1987.

B. Myers, "The W2PV Four-Element Yagi," *QST*, Oct 1986, pp 15-19.

L. Richard, "Parallel Dipoles of 300-Ohm Ribbon," *QST*, Mar 1957.

J. H. Richmond, "Monopole Antenna on Circular Disc," *IEEE Trans on Antennas and Propagation*, Vol. AP-32, No. 12, Dec 1984.

W. Schulz, "Designing a Vertical Antenna," *QST*, Sep 1978, pp 19- 21.

J. Sevick, “The Ground-Image Vertical Antenna,” *QST*, Jul 1971, pp 16-17, 22.

J. Sevick, “The W2FMI 20-Meter Vertical Beam,” *QST*, Jun 1972, pp 14-18.

J. Sevick, “The W2FMI Ground-Mounted Short Vertical,” *QST*, Mar 1973, pp. 13-18, 41.

J. Sevick, “A High Performance 20-, 40- and 80-Meter Vertical System,” *QST*, Dec 1973.

J. Sevick, “Short Ground-Radial Systems for Short Verticals,” *QST*, Apr 1978, pp 30-33.

J. Sevick, *Transmission Line Transformers*, 3rd ed. (Tucker, GA: Noble Publishing, 1996).

C. E. Smith and E. M. Johnson, “Performance of Short Antennas,” *Proc IRE*, Oct 1947.

J. Stanley, “Optimum Ground Systems for Vertical Antennas,” *QST*, Dec 1976, pp 13-15.

R. E. Stephens, “Admittance Matching the Ground-Plane Antenna to Coaxial Transmission Line,” Technical Correspondence, *QST*, Apr 1973, pp 55-57.

D. Sumner, “Cushcraft 32-19 ‘Boomer’ and 324-QK Stacking Kit,” Product Review, *QST*, Nov 1980, pp 48-49.

W. van B. Roberts, “Input Impedance of a Folded Dipole,” *RCA Review*, Jun 1947.

E. M. Williams, “Radiating Characteristics of Short-Wave Loop Aerials,” *Proc IRE*, Oct 1940.

TEXTBOOKS ON ANTENNAS

C. A. Balanis, *Antenna Theory, Analysis and Design* (New York: Harper & Row, 1982).

D. S. Bond, *Radio Direction Finders*, 1st ed. (New York: McGraw-Hill Book Co).

W. N. Caron, *Antenna Impedance Matching* (Newington: ARRL, 1989).

K. Davies, *Ionospheric Radio Propagation*—National Bureau of Standards Monograph 80 (Washington, DC: U.S. Government Printing Office, Apr 1, 1965).

R. S. Elliott, *Antenna Theory and Design* (Englewood Cliffs, NJ: Prentice Hall, 1981).

A. E. Harper, *Rhombic Antenna Design* (New York: D. Van Nostrand Co, Inc, 1941).

K. Henney, *Principles of Radio* (New York: John Wiley and Sons, 1938), p 462.

H. Jasik, *Antenna Engineering Handbook*, 1st ed. (New York: McGraw-Hill, 1961).

W. C. Johnson, *Transmission Lines and Networks*, 1st ed. (New York: McGraw-Hill Book Co, 1950).

R. C. Johnson and H. Jasik, *Antenna Engineering Handbook*, 2nd ed. (New York: McGraw-Hill, 1984).

R. C. Johnson, *Antenna Engineering Handbook*, 3rd ed. (New York: McGraw-Hill, 1993).

E. C. Jordan and K. G. Balmain, *Electromagnetic Waves and Radiating Systems*, 2nd ed. (Englewood Cliffs, NJ: Prentice-Hall, Inc, 1968).

R. Keen, *Wireless Direction Finding*, 3rd ed. (London: Wireless World).

R. W. P. King, *Theory of Linear Antennas* (Cambridge, MA: Harvard Univ. Press, 1956).

R. W. P. King, H. R. Mimno and A. H. Wing, *Transmission Lines, Antennas and Waveguides* (New York: Dover Publications, Inc, 1965).

King, Mack and Sandler, *Arrays of Cylindrical Dipoles* (London: Cambridge Univ Press, 1968).

M. G. Knitter, Ed., *Loop Antennas—Design and Theory* (Cambridge, WI: National Radio Club, 1983).

M. G. Knitter, Ed., *Beverage and Long Wire Antennas*—Design and Theory (Cambridge, WI: National Radio Club, 1983).

J. D. Kraus, *Electromagnetics* (New York: McGraw-Hill Book Co).

J. D. Kraus, *Antennas*, 2nd ed. (New York: McGraw-Hill Book Co, 1988).

E. A. Laport, *Radio Antenna Engineering* (New York: McGraw-Hill Book Co, 1952).

J. L. Lawson, *Yagi-Antenna Design*, 1st ed. (Newington: ARRL, 1986).

P. H. Lee, *The Amateur Radio Vertical Antenna Handbook*, 2nd ed. (Port Washington, NY: Cowen Publishing Co., 1984).

A. W. Lowe, *Reflector Antennas* (New York: IEEE Press, 1978).

M. W. Maxwell, *Reflections—Transmission Lines and Antennas* (Newington: ARRL, 1990). Out of print.

M. W. Maxwell, *Reflections II—Transmission Lines and Antennas* (Sacramento: Worldradio Books, 2001).

G. M. Miller, *Modern Electronic Communication* (Englewood Cliffs, NJ: Prentice Hall, 1983).

V. A. Misek, *The Beverage Antenna Handbook* (Hudson, NH: V. A. Misek, 1977).

T. Moreno, *Microwave Transmission Design Data* (New York: McGraw-Hill, 1948).

L. A. Moxon, *HF Antennas for All Locations* (Potters Bar, Herts: Radio Society of Great Britain, 1982), pp 109-111.

Ramo and Whinnery, *Fields and Waves in Modern Radio* (New York: John Wiley & Sons).

V. H. Rumsey, *Frequency Independent Antennas* (New York: Academic Press, 1966).

P. N. Saveskie, *Radio Propagation Handbook* (Blue Ridge Summit, PA: Tab Books, Inc, 1980).

S. A. Schelkunoff, *Advanced Antenna Theory* (New York: John Wiley & Sons, Inc, 1952).

S. A. Schelkunoff and H. T. Friis, *Antennas Theory and Practice* (New York: John Wiley & Sons, Inc, 1952).

J. Sevick, *Transmission Line Transformers* (Atlanta: Noble Publishing, 1996).

H. H. Skilling, *Electric Transmission Lines* (New York: McGraw-Hill Book Co, Inc, 1951).

M. Slurzburg and W. Osterheld, *Electrical Essentials of Radio* (New York: McGraw-Hill Book Co, Inc, 1944).

G. Southworth, *Principles and Applications of Waveguide*

Transmission (New York: D. Van Nostrand Co, 1950).

F. E. Terman, *Radio Engineers' Handbook*, 1st ed. (New York, London: McGraw-Hill Book Co, 1943).

F. E. Terman, *Radio Engineering*, 3rd ed. (New York: McGraw-Hill, 1947).

S. Uda and Y. Mushiake, *Yagi-Uda Antenna* (Sendai, Japan: Sasaki Publishing Co, 1954). [Published in English—Ed.]

P. P. Viezbicke, "*Yagi Antenna Design*," NBS Technical Note 688 (U. S. Dept of Commerce/National Bureau of Standards, Boulder, CO), Dec 1976.

G. B. Welch, *Wave Propagation and Antennas* (New York: D. Van Nostrand Co, 1958), pp 180-182.

The GIANT Book of Amateur Radio Antennas (Blue Ridge Summit, PA: Tab Books, 1979), pp 55-85.

IEEE Standard Dictionary of Electrical and Electronics Terms, 3rd ed. (New York: IEEE, 1984).

Radio Broadcast Ground Systems, available from Smith Electronics, Inc, 8200 Snowville Rd, Cleveland, OH 44141.

Radio Communication Handbook, 5th ed. (London: RSGB, 1976).

Radio Direction Finding, published by the Happy Flyer, 1811 Hillman Ave, Belmont, CA 94002

Chapter 3

The Effects of Ground

The ground around and under an antenna is part of the environment in which any actual antenna must operate. Chapter 2, Antenna Fundamentals, dealt mainly with theoretical antennas in free space, completely removed from the influence of the ground. This chapter is devoted to exploring the interactions between antennas and the ground.

The interactions can be analyzed depending on where they occur relative to two areas surrounding the antenna: the *reactive near field* and the *radiating far field*. You will recall that the reactive near field only exists very close to the antenna itself. In this region the antenna acts as though it were a large lumped-constant inductor or capacitor, where energy is stored but very little is actually radiated. The interaction with the ground in this area creates mutual impedances between the antenna and its environment and these interactions not only modify the feed-point impedance of an antenna, but also often increase losses.

In the radiating far field, the presence of ground profoundly influences the radiation pattern of a real antenna. The interaction is different, depending on the antenna's polarization with respect to the ground. For horizontally polarized antennas, the *shape* of the radiated pattern in the elevation plane depends primarily on the antenna's height above ground. For vertically polarized antennas, both the *shape* and the *strength* of the radiated pattern in the elevation plane strongly depend on the nature of the ground itself (its dielectric constant and conductivity at the frequency of operation), as well as on the height of the antenna above ground.

The Effects of Ground in the Reactive Near Field

FEED-POINT IMPEDANCE VERSUS HEIGHT ABOVE GROUND

Waves radiated from the antenna directly downward reflect vertically from the ground and, in passing the antenna on their upward journey, induce a voltage in it. The magnitude and phase of the current resulting from this induced voltage depends on the height of the antenna above the reflecting surface.

The total current in the antenna consists of two components. The amplitude of the first is determined by the power supplied by the transmitter and the free-space feed-point resistance of the antenna. The second component is induced in the antenna by the wave reflected from the ground. This second component of current, while considerably smaller than the first at most useful antenna heights, is by no means insignificant. At some heights, the two components will be in phase, so the total current is larger than is indicated by the free-space feed-point resistance. At other heights, the two components are out of phase, and the total current is the difference between the two components.

Changing the height of the antenna above ground will change the amount of current flow, assuming that the power input to the antenna is constant. A higher current at the same power input means that the effective resistance of the antenna is lower, and vice versa. In other words, the feed-point resistance of the antenna is affected by the height of the antenna above ground because of mutual coupling between the antenna and the ground beneath it.

The electrical characteristics of the ground affect both the amplitude and the phase of reflected signals. For this reason, the electrical characteristics of the ground under the antenna will have some effect on the impedance of that antenna, the reflected wave having been influenced by the ground. Different impedance values may be encountered when an antenna is erected at identical heights but over different types of earth.

Fig 1 shows the way in which the radiation resistance of horizontal and vertical half-wave antennas varies with height above ground (in λ, wavelengths). The height of the vertical half-wave is the distance from the bottom of the antenna to ground. For horizontally polarized half-wave antennas, the differences between the effects of perfect ground and real earth are negligible if the antenna height is greater than 0.2 λ. At lower heights, the feed-point resistance over perfect ground decreases rapidly as the antenna is brought closer to a theoretically perfect ground, but this does not occur so rapidly for actual ground. Over real earth, the resistance actually begins increasing at heights below about 0.08 λ. The reason for the increasing resistance at very low heights is that more and more of the reactive (induction) field of the antenna is absorbed by the lossy ground in close proximity. This results in increased loss that is reflected in the increased value of the feedpoint resistance.



Fig 1—Variation in radiation resistance of vertical and horizontal half-wave antennas at various heights above flat ground. Solid lines are for perfectly conducting ground; the broken line is the radiation resistance of horizontal half-wave antennas at low height over real ground.

For a vertically polarized λ/2-long dipole, differences between the effects of perfect ground and real earth on the feed-point impedance is negligible, as seen in **Fig 1**. The theoretical half-wave antennas on which this chart is based are assumed to have infinitely thin conductors.

GROUND SYSTEMS FOR VERTICAL MONOPOLES

In this section, we'll look at vertical monopoles, which require some sort of ground system in order to make up for the "missing" second half of the antenna and reduce the power lost in the near field. Rudy Severns, N6LF, contributed much of the new material in this chapter.

In Chapter 2, Antenna Fundamentals, and up to this point in this chapter, the discussion about vertical monopoles has mainly been for antennas where *perfect ground* is available. We have also briefly looked at the ground-plane vertical in free space, where the four ground-plane radials form a built-in ground system.

Perfect ground makes a vertical monopole into the functional equivalent of a center-fed dipole, although the feed-point resistance at resonance is half that of the center-fed dipole. But how can we manage to create that elusive perfect ground, or at least a reasonable approximation, for our real vertical antennas?

Simulating a Perfect Ground in the Reactive Near Field

The effect of a perfectly conducting ground (so far as feed-point resistance and losses are concerned) can be simulated under a real antenna by installing a very large metal screen or mesh, such as poultry netting (chicken wire) or hardware cloth, on or near the surface of the ground. The screen (also called a *counterpoise system*, especially if it is elevated off the ground) should extend at least a half wavelength in every direction from the antenna. The feed-point resistance of a quarter-wave long, thin vertical radiator over such a ground screen will approach the theoretical value of 36.6 Ω. Of course on the lower HF bands such a screen is not practical for most amateurs.

Based on the results of a study published in 1937 by Brown, Lewis and Epstein (see Bibliography), a grounding system consisting of 120 wires, each at least λ/2 long, extending radially from the base of the antenna and spaced equally around a circle, is also the practical equivalent of perfectly conducting ground for reactive-field currents. The wires can either be laid directly on the surface of the ground or buried a few inches below.

Another approach to simulating a perfect ground system is to utilize the ground-plane antenna, with its four ground-plane radials elevated well above lossy earth. Heights (between the bottom of the ground-plane and the surface of the ground) greater than λ/8 have proven to yield excellent results. See Chapter 6, Low-Frequency Antennas, for more details on practical ground-plane verticals.

For a vertical antenna, a large ground screen, either made of wire mesh or a multitude of radials, or an elevated system of ground-plane radials will reduce ground losses near the antenna. This is because the screen conductors are solidly bonded to each other and the resistance is much lower than that of the lossy, low-conductivity earth itself. If the ground screen or elevated ground plane were not present, RF currents would be forced to flow through the lossy, low-conductivity earth to return to the base of the radiator. The ground screen or elevated ground plane in effect shield ground-return currents from the lossy earth.

Less-Than-Ideal Ground Systems

Now, what happens when something less than an ideal ground screen is used as the ground plane for a vertical monopole? Typically this will take the form of an on-ground wire radial system. A great deal of mystery and lack of information seems to surround the vertical antenna ground system. In the case of ground-mounted vertical antennas, many general statements such as “the more radials the better” and “lots of short radials are better than a few long ones” have served as rules of thumb, but many questions as to relative performance differences and optimum number for a given length remain unanswered, as is the justification for the rules of thumb. Most of these questions boil down to one: namely, how many radials, and how long, should be used in a given vertical antenna installation?

A ground system with 120 $\lambda/2$ radials is not very practical for many amateur installations, which often must contend with limited space and funding. Unfortunately the ground resistance, R_g, increases rapidly when the number of radials is reduced. To minimize ground loss where a large, optimum ground system is not possible requires that we understand how ground losses occur and how to optimize the design of a ground system that can fit within the space and budget available.

E and H Fields

E and H fields were introduced in Chapter 2, Antenna Fundamentals, to explain some basic concepts concerning antennas. To understand the reasons for ground loss we need to look at the E and H fields in the near field, but we need to have some feeling for what E and H fields are. The following is a brief description of these fields. It is certainly not a rigorous description but should give at least an intuitive feeling for what is happening.

In 1820 Hans Oerstad discovered that a current flowing in a wire would deflect the needle of a nearby compass. We attribute this effect to a *magnetic* or *H-field*, which at any given location is denoted by the bold-faced letter **H**. **H** is a vector, with an amplitude expressed in A/m (Amperes/meter) and a direction. **Fig 2** shows a typical experimental arrangement. The shape of the magnetic field is roughly shown by the distribution of the iron filings. This field distribution is very similar to that for a vertical antenna.

A compass needle (a small magnet itself) will try to align itself parallel to **H.** As the compass is moved around the conductor, the orientation of the needle changes accordingly. The orientation of the needle gives the direction of **H**. If you attempt to turn the needle away from alignment you will discover a torque trying to restore the needle to its original position. The torque is proportional to the strength of the magnetic field at that point. This is called the *field intensity* or amplitude of **H** at that point. If a larger current flows in the conductor going through the piece of paper holding the iron filings, the amplitude of **H** will be larger. Currents flowing in the conductors of an antenna also generate a magnetic field, one component of the near field.

An antenna will also have an *electric* or *E-field*, which can be visualized using a parallel-plate capacitor, as shown in **Fig 3**. If we connect a battery with a potential V_{dc} across the capacitor plates there will be an electric field **E** established between the plates, as indicated by the lines and directional arrows between the plates. The magnitude of vector **E** is expressed in V/m (volts per meter), so for a potential of V volts and a spacing of d meters, E = V/d V/m. The amplitude of **E** will increase with greater voltage and/or a smaller distance (d). In an antenna, there will be ac potential differences between different parts of the antenna and from the antenna to ground. These ac potential differences establish the electric field associated with the antenna.

Conduction And Displacement Currents

If we replace the dc voltage source in Fig 3 with an ac source, a steady ac current will flow in the circuit. In the



Fig 2—The magnetic lines of force that surround a conductor with an electric current flowing in it are shown by iron filings and small compass needles. The needles point in the direction of the magnetic or H-field. The filings give a general view of the field distribution in the plane perpendicular to the conductor.

conductors between the ac source and the capacitor plates, current (I_c) flows, because of the movement of charge, usually electrons. But in the space between the capacitor plates—particularly in a vacuum—there are no charge carriers available to carry a conduction current. Nonetheless, current still flows in the complete circuit, and we attribute this to a *displacement current* (I_d) flowing between the capacitor plates to account for the continuity of current in the circuit. Displacement and conduction currents are two different phenomena but they both represent current, just two different kinds. Some observers prefer to call conduction currents "currents" and displacement currents "imaginary currents." That terminology is OK, but to account for the current flow in a closed circuit with capacitance you have to keep track of both kinds of current, whatever you call them.

In an antenna over ground, the displacement current represents the current flow from the antenna surface through the air into the ground. The currents flowing in the ground are predominantly conduction currents, but there may also be displacement currents.



Fig 3—Example of an electric field, $E=V_{dc}/d$. When the dc source is replaced with an ac source there will be a displacement current (I_d) flowing between the capacitor plates.



Fig 4—When the capacitor dielectric is less than perfect there will be a conduction current (I_c) in addition to the displacement current (I_d). Soil will typically have both resistive and capacitive components. Power loss in the soil is due to the current flowing through the resistive component.

Where the dielectric material between the capacitor plates is not a perfect insulator, both conduction and displacement currents can flow between the capacitor plates. A good example of this would be a soil dielectric, which has both resistive and capacitive characteristics. Soil can be represented in the circuit of **Fig 4**, where there is a resistor with a conduction current I_c in parallel with a capacitor with a displacement current I_d. The two currents add up (vectorially) as the total current I_T.

A Closer Look at Verticals

A vertical antenna has two field components that induce currents in the ground around the antenna. **Fig 5** shows in a general way the electric-field component (E_z, in V/m) and magnetic-field component (H_ϕ, in A/m) in the region near a vertical. Because the soil near the antenna usually has relatively high resistance, both of these field components will induce currents (I_V and I_H) in the ground, resulting in losses. While the worms may enjoy the heated ground, power dissipated in the ground is subtracted from the radiated power, weakening your signal.

As shown in Fig 5, the tangential component of the H-field (H_ϕ) induces horizontal currents (I_H) flowing radially. The normal component (perpendicular to the ground surface) of the E-field (E_z) induces vertically flowing currents (I_v). Actually, things are more complex than this but we don't need to thrash through that to understand conceptually what's going on.

When modeling an antenna we account for the radiated power (P_r) by assuming there is a resistor we call the *radiation resistance* (R_r) through which the antenna base current (I_o) flows. The radiated power is then $P_r = I_o^2R_r$. Similarly, we can account for the power dissipated in the ground (P_g) by adding a loss resistance (R_g) in series with R_r. The ground loss is then $P_g = I_o^2R_g$. Additional losses due to conductors, loading coils, etc can also be simulated



Fig 5—A general view of the fields and ground currents near the base of a vertical antenna. Note that the H-field distribution is equivalent to that shown in Fig 3.

by adding more series loss resistances. Putting aside for the moment these additional losses, the efficiency (η) of a vertical can be expressed as:

$$\eta = \frac{P_r}{P_r + P_g} \qquad \text{(Eq 1)}$$

This can be restated in terms of resistances as:

$$\eta = \frac{R_r}{R_r + R_g} = \frac{1}{1 + \frac{R_g}{R_r}} \qquad \text{(Eq 2)}$$

In essence, efficiency is the ratio of the radiated power to the total input power ($P_T = P_r + P_g$). Another way of saying this is that efficiency depends on the ratio of ground loss resistance (R_g) to radiation resistance (R_r), as Eq 2 shows. The smaller we make R_g the more power will be radiated for a given input power. Reducing R_g is the purpose of the ground system.

A sketch of current flow in the antenna and the surrounding ground (due to H-field), near the base of a vertical, is shown in **Fig 6**. I_z represents the total *zone current* flowing radially through a cylindrical zone at a given radius (r) due to the H field, while I_o is the current at the feed point at the base of the antenna. Technically speaking, the cylinder is infinitely deep, with I_z being the total current integrated over the surface of the cylinder at a given radius.

Fig 7 is a graph of the amplitude of I_z for several antenna heights in wavelengths (h) as we move away from the base of the antenna. Fig 7 shows the zone current that would flow in the ground returning to the base of the antenna, assuming a single ground rod is placed at the feed point for the vertical radiator. The heights indicated are the effective electrical heights. For example, if you use some top loading on the vertical, the effective electrical height will be greater than the physical height.

It is important to recognize that simply adding a top hat to a vertical of a given physical height may reduce ground losses. We can see this from the effect of h on ground current amplitude in Fig 7. Increasing h reduces the ground current. Even something as simple as moving a loading coil from the base up to the center of the antenna may reduce ground losses because it reduces ground current amplitude. But we do have to be careful that the loss introduced by the loading coil does not overcome the reduction in ground loss! Both loading-coil and top-hat schemes also increase the radiation resistance R_r, which further improves efficiency.

The currents in Fig 7 have been adjusted for constant radiated power at the base of the antenna by varying I_o to compensate for the change in R_r as we vary h. To maintain constant radiated power as R_r is falling, you must increase I_o. The base feed-point impedance is a strong function of h. For example, for h = 0.25 λ, R_r will be in the neighborhood of 36 Ω. However, for h = 0.1 λ, R_r will be less than 4 Ω. More information on short antennas can be found in Chapter 16, Mobile and Maritime Antennas.

Fig 7 clearly shows the high currents that flow in the ground near the base of a short antenna due to the antenna's H field. Compared to a 0.25-λ vertical, the 0.1-λ vertical has about three times the base current. As you shorten the antenna further, the zone current increases even more quickly. The ground loss is proportional to the square of the ground current ($P_g = I_g^2 R_g$), so the power loss in the immediate



Fig 6—Representation of the zone current near the base of a vertical antenna. Individual i_z components of current flow into a cylinder of soil, with a radius r centered on the base of the vertical. The total current, I_z, thus represents the net current induced in the soil by the H-field for a given radius. (I_z was labeled I_H in Fig 5.)



Fig 7—Plot of zone current (I_z) in amperes near the base of a vertical as a function of height (h) and radius (r) in wavelengths. The current in the base of the 0.25-λ antenna is assumed to be 1 A and the current for other values of h is adjusted to maintain the same radiated power ($P_r = I_o^2 R_r$ = 37 W) as the radiation resistance (R_r) changes with h.



Fig 8—Total H-field induced ground loss within a circle of radius r around the base of a vertical for different values of h and constant P_r = 37 W. Note how the total loss increases rapidly near the base of the antenna indicating high loss. Beyond r = 0.15 λ, however, the additional loss is much lower and the curves flatten out. Note also how much higher the loss is for shorter antennas.

region of the base is much higher for a short antenna operating with the same input power as for a quarter-wave vertical.

We can calculate the losses induced in the soil by either the E- or H-field intensity. **Fig 8** shows an example of the H-field losses for several different antenna heights, given a constant radiated power of 37 W. Note that the total loss within 0.5 λ of the base for h = 0.25 λ is about 16 W (right side of the graph). This gives η = 37/(37 + 16) = 70%. However, for h = 0.1 λ, the total loss is about 94 W. Taking into consideration only the H-field losses, η = 37/(37 + 94) = 28%. Note that in both cases the majority of the loss is near (< 0.1 λ) the antenna, with the rate of increase of total loss decreasing rapidly as we move farther away from the base, where the lines are almost flat.

Fig 9 is a graph of the E-field intensity around a vertical with 1500 W radiated power, for three values of h. The E-field intensity doesn't depend on the exact type of ground system. (You can see this when you consider that the voltage across a capacitor doesn't depend on the size of the capacitor's plates.) Notice that close to the base, the E-field intensity for the 0.1-λ vertical is almost 100 times that for the 0.25-λ vertical. Because loss is proportional to the square of the voltage, the E-field losses close to the base will be ten thousand times larger in the 0.1-λ vertical! At a 1500-W power level the field intensity near the base of a short vertical is high enough to pose some risk of igniting grass and bushes that grow above any radial system close to the vertical's base. The grass should be kept mowed within 0.1 λ of the base.



Fig 9—Electric field intensity near the base of a vertical for different values of h. P_r is held constant at 1500 W.

Fig 10 shows a computation for the E-field losses, again for a constant radiated power of 37 W and several values of h. For the 0.25-λ vertical, the electric field intensity is quite low and so are the losses associated with it, at only 1.5 W. With any reasonable ground system, the E-field losses for a 0.25-λ vertical will be insignificant.

For shorter or longer verticals, however, the picture is different. This is why we see the very high losses (> 100 W) in Fig 10 for h = 0.1 λ. This loss, when added to the H-field loss, reduces the efficiency of the 0.1-λ vertical to 16% or less without a good ground system. In short antennas the E-field losses cannot be ignored, since they get worse exponentially as the antenna is shortened further.

The presence of a top-loading hat will also increase the E-field intensity in the area below the hat. However, most practical amateur hats will be quite small and the associated E-field loss small. The benefit, however, of reducing I_o because of the addition of the hat—which reduces the field



Fig 10—Total E-field induced ground loss within a circle of radius r around the base of a vertical for different values of h and constant P_r = 37 W. Note how the total loss increases rapidly near the base of the antenna, indicating high loss. Beyond r = 0.05 λ, however, the additional loss is much lower and the curves flatten out. Note again how much higher the loss is for shorter antennas. For h = 0.1 λ the E-field loss is greater than the H-field loss.



Fig 11—Effective ground resistance (R_g) at the base of the vertical as a function of the radius of a ground screen for several different antenna heights. Note how R_g falls as power dissipation in the soil is eliminated by the highly conducting ground screen.

from the vertical part of the antenna—more than compensates for the small additional E-field loss due to the hat.

Verticals taller than 0.25 λ also display increased E-field intensity, but not nearly so severe as short verticals. In verticals both shorter and longer than a 0.25 λ, the critical loss region is within a radius of about 0.05 λ. We can see this in Fig 10, where the power-loss curves for the shorter antennas flatten out by the time we reach a radius of 0.05 λ.

It's not widely known, but while radial wire systems reduce the H-field losses very effectively, Larsen (see Bibliography) has shown that the E-field losses with the same radial system do not fall in the same fashion as H-field losses. For h > 0.15 λ this doesn't matter much because the E-field loss is so low anyway. However, for short antennas it is very helpful to install either a ground screen or a dense radial system within 0.05 λ of the base.

We can take the data in Figs 8 and 10 and calculate the effective value of the ground resistance R_g. **Fig 11** shows the results of such a computation. Fig 11 assumes a perfect ground screen that varies in radius from 0.001 λ to 0.5 λ. As we would expect, when the ground screen is very small the ground losses are high, meaning R_g is high and the efficiency is low. As we increase the radius of the ground screen, forcing current out of the lossy soil and into the very low-loss screen, R_g drops rapidly and the efficiency increases.

Fig 11 demonstrates why it is desirable to have a good ground system out to at least 0.125 λ, and better yet, even farther. The shorter the antenna, the more important the ground system becomes, especially close to the base. In this example the ground system consists of a highly conductive, bonded ground screen, not always practical for amateur installations. A more typical ground system would consist of a number of individual radial wires. This kind of ground will be inferior to a screen but represents a practical compromise. We'll examine this in more detail shortly.

Note that as we reduce h in Fig 11, R_g actually goes down—even though the ground losses are higher. When h is made smaller the radiation resistance declines rapidly (see Chapter 16, Mobile and Maritime Antennas), so that for a given radiated power I_o must increase. If we measure R_g as we reduce h over a given ground system, we would see that the value for R_g goes down as shown in Fig 11. But because I_o^2 is rising more rapidly than R_g is falling, the power lost in the ground increases and efficiency decreases. The point here is that the value of R_g depends on the ground system, soil characteristics *and* the antenna configuration. You cannot assign an arbitrary value to R_g independent of the antenna system.

Wire Radial Systems

Fig 11 shows R_g for a dense, perfectly conducting ground screen, but what we really need to know is the effect of length and number of individual radials on R_g in a wire radial system. We can calculate the current division between a radial system and the soil and use this to determine R_g. A typical graph of the proportion of the zone current flowing in the radial system, as a function of radius and various numbers of radials (N), is shown in **Fig 12**.

The radial currents decrease as we move away from the base, and the lower the number of radials, the more rapidly the radial current decreases. This means that close to the base of the antenna most of the current is in the radial system, but as we move away from the base the current increasingly flows in the lossy ground. When only a few radials are used, the outer ends of the radials contribute little to reducing ground loss.

Why is this? The problem is that I_z does not go immediately to the nearest radial but may flow for some distance in the soil. This is illustrated in a general way in **Fig 13**. As we move away from the base of the antenna, adjacent radials are further apart from each other and the current must flow further in the soil before it reaches one of the radials. When we use more radials, the distance between radials is less and more of the total current will be in the radials and less in the soil. This reduces ground loss.

When we know the current distribution in the ground we can calculate the power loss and R_g. A typical example for h = 0.25 λ is given in **Fig 14**. We can learn a lot about radial system design from Fig 14 and similar graphs. If we use only a few radials, the radial current drops off very rapidly. Most of the current is flowing in the soil.

Such a ground system is by nature inefficient—that is, R_g is large. We can also see that if we have only 16 radials, R_g falls an ohm or two as we lengthen the radials, but is essentially flat by 0.1 λ. There is no point in making them longer because there is little current in the outer portions and R_g is essentially constant beyond 0.1 λ. As we increase the number of radials, we gather more current further out, making longer radials more useful. The result is cumulative—more radials allow longer radials to be effective and both together reduce ground loss. We can see this in Fig 14, where the initial value of R_g drops as N increases and flattens out at longer radial lengths. For 128 radials, for example, lengths of 0.25 λ or more are useful.

The example in Fig 14 uses #12 wire for the radials. Compared to soil, the resistance of the radial wires is very small, especially if many radials are used, and does not greatly affect overall losses no matter how small the wire. The effect of changing wire size is to slowly change the current division between ground and the radial system. Larger wire results in only a small decrease in R_g. In principle, very small wire could be used for radials but from a mechanical point of view, #18 or #20 wire is about as small as is practical. Any smaller wire breaks too easily to be buried, and also breaks easily when left on the ground surface and is walked on or driven over.



Fig 13—An example of current entering the ground between the radials and flowing for some distance before being picked up by a radial.



Fig 12—An example of the portion of the zone current flowing in the radial system as you move away from the base of a 0.25 λ vertical for different numbers of radials (N). Note that when more radials are used, more of the zone current flows in the radials and not in the ground, reducing ground loss. The proportion of current in the radial system falls rapidly when only a few radials are used. This leads to high ground loss because most of the zone current is flowing in the ground rather than in the radials.



Fig 14—An example of the variation of R_g with radial length and number of radials (N) for h = 0.25 λ. When only a few radials are used there is little point in making them longer than 0.1 λ. Increasing N reduces R_g at a given radius and also makes longer radials useful, further reducing R_g. R_g for other values of h behave similarly.

On the other hand, wire larger than #12 is expensive. Thousands of feet of #8 wire may be affordable for broadcast stations but not for most hams. Increasing the wire size from #20 to #10 would result in only a small reduction in R_g. Of course, if you happen to have a few thousand feet of old RG-8 cable lying around (the diameter is comparable to #0000 wire) then that might indeed help to reduce R_g, as W9QQ has shown (see Bibliography). You are still better off, however, using many radials with small wire than a few radials with large wire. Radial wire size is usually a mechanical and financial issue, not an electrical one.

If the example in Fig 14 were changed for different ground characteristics, then the curves would have a similar shape but would be shifted either up or down. For example, poorer ground will result in higher R_g but the usable length for the radials for a given N would increase somewhat. For better-quality ground, with higher conductivity, R_g will be lower but the usable length of the radials for a given N will be shorter.

For short antennas, the initial drop in R_g will be more rapid and the curves flatten out sooner. This implies that somewhat shorter radials are useful with short antennas. However, given the high losses, it is still a very good idea to use lots of radials with short antennas. As in the above example, increasing N also increases the usable length.

As you go up in frequency from 160 meters, R_g generally rises slowly and then stabilizes around 7 MHz, depending on the ground characteristics. This effect is related to the change in skin depth with frequency, which is discussed in a later section of this chapter. There is also a small shift in current division between the radials and ground as the frequency increases.

A Word Of Caution

In the preceding discussion we presented a number of graphs and the CD-ROM accompanying this book contains some spreadsheets containing the equations from which these graphs were derived. From these graphs we extracted a number of observations on how to design radial systems. Basic to each graph is the assumption that we know the ground characteristics: conductivity and permitivity. In the real world, we amateurs very rarely have more than a rough idea of the ground characteristics under our antennas. Even when careful measurements are made, the characteristics will vary through the year with rainfall or the lack thereof.

Soils are always stratified vertically and can vary by factors or two or more horizontally over distances comparable to radial length, so that even good ground measurements are at best an average. In addition, there will frequently be constraints on the size and shape of the ground system. As a result, we use the calculated information and the previous graphs for general guidance and preliminary design, but when actually installing a ground system we try to measure—or at least estimate—R_g as we go along.

When R_g stops falling, or our patience and/or money run out, we stop adding ground radials. We can measure the feed-point resistance with an impedance bridge to estimate of R_g. The impedance seen at the feed point of the antenna is the sum of the loss and the radiation resistance. To determine R_g you have to estimate R_r (from the antenna height) and other losses due to loading or conductors, and then subtract that from the total measured input resistance. The remainder is R_g, and R_g should fall as we add radials. When R_g stops falling we probably have as many radials of a given length as will be useful. Further reduction in R_g would require more, longer radials.

Practical Suggestions For Vertical Ground Systems

At least 16 radials should be used if at all possible. Experimental measurements and calculations show that with this number, the loss resistance decreases the antenna efficiency by 30% to 50% for a 0.25 λ vertical, depending on soil characteristics. In general, a large number of radials (even though some or all of them must be short) is preferable to a few long radials for a vertical antenna mounted on the ground. The conductor size is relatively unimportant as mentioned before: #12 to #22 copper wire is suitable.

Table 1 summarizes these conclusions. John Stanley, K4ERO, first presented this material in December 1976 *QST*. Another source of information on ground-system design is *Radio Broadcast Ground Systems* (see the Bibliography at the end of this chapter). Most of the data presented in Table 1 is taken from that source, or derived from the interpolation of data contained therein.

Table 1 is based on the number of radials. For each configuration, there is a corresponding optimum radial length. Each configuration also includes the amount of wire used, expressed in wavelengths. Using radials considerably longer than suggested for a given N or using a lot more radials than suggested for a given length, while not adverse to performance, does not yield significant improvement either. That would represent a non-optimum use of wire and construction time. Each suggested configuration represents an optimum relationship between length and number for the given amount of total wire used. Table 1 leads to these conclusions:

- If you install only 16 radials (in configuration A), they need not be very long—0.1 λ is sufficient. The total length of wire will be 1.6 λ, which is about 875 feet at 1.8 MHz.
- If you have the wire, the space and the patience to lay down 120 radials (optimal configuration F), they should be 0.4 λ long. This radial system will gain about 3 dB over the 16-radial case and you'll use 48 λ of wire, or about 26,000 feet at 1.8 MHz.
- If you install 36 radials that are 0.15 λ long, you will lose 1.5 dB compared to optimal configuration F. You will use 5.4 λ of wire, or almost 3,000 feet at 1.8 MHz.

The loss figures in Table 1 assume $h = 0.25\ \lambda$. A very rough approximation of loss when using shorter antennas can be obtained by doubling the loss in dB each

Table 1
Optimum Ground-System Configurations

	Configuration Designation					
	A	*B*	*C*	*D*	*E*	*F*
Number of radials	16	24	36	60	90	120
Length of each radial in wavelengths	0.1	0.125	0.15	0.2	0.25	0.4
Spacing of radials in degrees	22.5	15	10	6	4	3
Total length of radial wire installed, in wavelengths	1.6	3	5.4	12	22.5	48
Power loss in dB at low angles with a quarter-wave radiating element	3	2	1.5	1	0.5	0*
Feed-point impedance in ohms with a quarter-wave radiating element	52	46	43	40	37	35

Note: Configuration designations are indicated only for text reference.
*Reference: The loss of this configuration is negligible compared to a perfectly conducting ground.

time the antenna height is halved. For taller antennas the losses decrease, approaching 2 dB for configuration A of Table 1 for a half-wave radiator. Even longer antennas yield correspondingly better performance.

Table 1 is based on average ground conductivity. Variation of the loss values shown can be considerable, especially for configurations using fewer radials. Those building antennas over dry, sandy or rocky ground should expect more loss. On the other hand, higher than average soil conductivity and wet soils would make the compromise configurations (those with the fewest radials) even more attractive.

When antennas are combined into arrays, either parasitic or all-driven types, mutual impedances lower the radiation resistance of the elements. This drastically increases the effects of ground loss because I_0 will be higher for the same power level. For instance, an antenna with a 50-Ω feed-point impedance, of which 10 Ω is ground-loss resistance, will have an efficiency of approximately 83%. An array of two similar antennas in a driven array with similar ground losses may have an efficiency of 70% or less.

Special precautions must be taken in such cases to achieve satisfactory operation. Generally speaking, a wide-spaced broadside array presents little problem because R_r is high, but a close-spaced end-fire array should be avoided because R_r is much lower, unless low-loss radial system configurations are used or other precautions taken. Chapter 8, Multielement Arrays, covers the subject of vertical arrays in great detail.

In cases where directivity is desirable or real-estate limitations dictate, longer, more closely spaced radials can be installed in one direction, and shorter, more widely spaced radials in another. Multiband ground systems can be designed using different optimum configurations for different bands. Usually it is most convenient to start at the lowest frequency with fewer radials and add more short radials for better performance on the higher bands.

There is nothing sacred about the exact details of the configurations in Table 1, and small changes in the number of radials and lengths will not cause serious problems. Thus, a configuration with 32 or 40 radials of 0.14 λ or 0.16 λ will work as well as configuration C shown in the table.

If less than 90 radials are contemplated, there is no need to make them a quarter wavelength long. This differs rather dramatically from the case of a ground-plane antenna, where resonant radials are installed above ground. For a ground-mounted antenna, quarter-wave long radials may not be optimum. Because the radials of a ground-mounted vertical are actually on, if not slightly below the surface, they are coupled by capacitance or conduction to the ground, and thus resonance effects are not important. The basic function of radials is to provide a low-loss return path for ground currents.

Radio Broadcast Ground Systems states, "Experiments show that the ground system consisting of only 15 radial wires need not be more than 0.1 wavelength long, while the system consisting of 113 radials is still effective out to 0.5 wavelength." Many graphs in that publication confirm this statement. This is not to say that these two systems will perform equally well; they most certainly will not. However, if 0.1 λ is as long as the radials can be, there is little point in using more than 15 of them unless the vertical radiator's height is also small.

The antenna designer should:

1. Study the cost of various radial configurations versus the gain of each.
2. Compare alternative means of improving transmitted signal and their cost (more power, etc).
3. Consider increasing the physical antenna height (the electrical length) of the vertical radiator, instead of improving the ground system.
4. Use multi-element arrays for directivity and gain, observing the necessary precautions related to mutual impedances discussed in Chapter 8, Multielement Arrays.

The Effect of Ground in the Far Field

The properties of the ground in the far field of an antenna are very important, especially for a vertically polarized antenna, as discussed above. Even if the ground-radial system for a vertical has been optimized to reduce ground-return losses in the reactive near field to an insignificant level, the electrical properties of the ground may still diminish far-field performance to lower levels than "perfect-ground" analyses might lead you to expect. The key is that *ground reflections* from horizontally and vertically polarized waves behave very differently.

Reflections in General

First, let us consider the case of flat ground. Over flat ground, either horizontally or vertically polarized downgoing waves launched from an antenna into the far field strike the surface and are reflected by a process very similar to that by which light waves are reflected from a mirror. As is the case with light waves, the angle of reflection is the same as the angle of incidence, so a wave striking the surface at an angle of, say, 15° is reflected upward from the surface at 15°.

The reflected waves combine with direct waves (those radiated at angles above the horizon) in various ways. Some of the factors that influence this combining process are the height of the antenna, its length, the electrical characteristics of the ground, and as mentioned above, the polarization of the wave. At some elevation angles above the horizon the direct and reflected waves are exactly in phase—that is, the maximum field strengths of both waves are reached at the same time at the same point in space, and the directions of the fields are the same. In such a case, the resultant field strength for that angle is simply the sum of the direct and reflected fields. (This represents a theoretical increase in field strength of 6 dB over the free-space pattern at these angles.)

At other elevation angles the two waves are completely out of phase—that is, the field intensities are equal at the same instant and the directions are opposite. At such angles, the fields cancel each other. At still other angles, the resultant field will have intermediate values. Thus, the effect of the ground is to increase radiation intensity at some elevation angles and to decrease it at others. When you plot the results as an elevation pattern, you will see *lobes* and *nulls*, as described in Chapter 2, Antenna Fundamentals.

The concept of an *image antenna* is often useful to show the effect of reflection. As **Fig 15** shows, the reflected ray has the same path length (AD equals BD) that it would if it originated at a virtual second antenna with the same characteristics as the real antenna, but situated below the ground just as far as the actual antenna is above it.



Fig 15—At any distant point, P, the field strength will be the vector sum of the direct ray and the reflected ray. The reflected ray travels farther than the direct ray by the distance BC, where the reflected ray is considered to originate at the *image* antenna.

Now, if we look at the antenna and its image over perfect ground from a remote point on the surface of the ground, we will see that the currents in a horizontally polarized antenna and its image are flowing in opposite directions, or in other words, are 180° out of phase. But the currents in a vertically polarized antenna and its image are flowing in the *same* direction—they are *in* phase. This 180° phase difference between the vertically and horizontally polarized reflections off ground is what makes the combinations with direct waves behave so very differently.

FAR-FIELD GROUND REFLECTIONS AND THE VERTICAL ANTENNA

A vertical's azimuthal directivity is omnidirectional. A λ/2 vertical over ideal, perfectly conducting earth has the elevation-plane radiation pattern shown by the solid line in **Fig 16**. Over real earth, however, the pattern looks more like the shaded one in the same diagram. In this case, the low-angle radiation that might be hoped for because of perfect-ground performance is not realized in the real world.

Now look at **Fig 17A**, which compares the computed elevation-angle response for two half-wave dipoles at 14 MHz. One is oriented horizontally over ground at a height of λ/2 and the other is oriented vertically, with its center just over λ/2 high (so that the bottom end of the wire doesn't actually touch the ground). The ground is "average" in dielectric constant (13) and conductivity (0.005 S/m). At a 15° elevation angle, the horizontally polarized dipole has almost 7 dB more gain than its vertical brother. Contrast Fig 17A to the comparison in Fig 17B, where the peak gain of a vertically polarized half-wave dipole over seawater, which is virtually perfect for RF reflections, is quite comparable with the horizontal dipole's response at 15°, and exceeds the horizontally polarized antenna dramatically below 15° elevation.



Fig 16—Vertical-plane radiation pattern for a ground-mounted quarter-wave vertical. The solid line is the pattern for perfect earth. The shaded pattern shows how the response is modified over average earth (k = 13, G = 0.005 S/m) at 14 MHz. ψ is the pseudo-Brewster angle (PBA), in this case 14.8°.

To understand in a qualitative fashion why the desired low-angle radiation from a vertical is not delivered when the ground isn't "perfect," examine **Fig 18A**. Radiation from each antenna segment reaches a point P in space by two paths; one directly from the antenna, path AP, and the other by reflection from the earth, path AGP. (Note that P is so far away that the slight difference in angles is insignificant—for practical purposes the waves are parallel to each other at point P.)

If the earth were a perfectly conducting surface, there would be no phase shift of the vertically polarized wave upon reflection at point G. The two waves would add together with some phase difference because of the different path lengths. This difference in path lengths of the two waves is why the free-space radiation pattern differs from the pattern of the same antenna over ground.

Now consider a point P that is close to the horizon, as in Fig 18B. The path lengths AP and AGP are almost the same, so the magnitudes of the two waves add together, producing a maximum at zero angle of radiation. The arrows on the waves point both ways since the process works similarly for transmitting and receiving.

With real earth, however, the reflected wave from a vertically polarized antenna undergoes a change in both *amplitude* and *phase* in the reflection process. Indeed, at a low-enough elevation angle, the phase of the reflected wave will actually change by 180° and its magnitude will then subtract from that of the direct wave. At a zero takeoff angle, it will be almost equal in amplitude, but 180° out of phase with the direct wave.

Note that this is very similar to what happens with horizontally polarized reflected and direct waves at low elevation angles. Virtually complete cancellation will result in a deep null, inhibiting any radiation or reception at 0°. For real-world soils, the vertical loses the theoretical advantage it has at low elevation angles over a horizontal antenna, as Fig 17A so clearly shows.



Fig 17—At A, comparison of horizontal and vertical λ/2 dipoles over average ground. Average ground has conductivity of 5 mS/m and dielectric constant of 13. Horizontal dipole is λ/2 high; vertical dipole's bottom wire is just above ground. Horizontal antenna is much less affected by far-field ground losses compared with its vertical counterpart. At B, comparison of 20-meter λ/2 vertical dipole whose bottom wire is just above seawater with λ/2-high horizontal dipole over average ground. Seawater is great for verticals!

The degree that a vertical works better than a horizontal antenna at low elevation angles is largely dependent on the characteristics of the ground around the vertical, as we'll next examine.

THE PSEUDO-BREWSTER ANGLE AND THE VERTICAL ANTENNA

Much of the material presented here regarding pseudo-Brewster angle was prepared by Charles J. Michaels, W7XC, and first appeared in July 1987 *QST*, with additional information in *The ARRL Antenna Compendium, Vol 3*. (See the Bibliography at the end of this chapter.)

Most fishermen have noticed that when the sun is low, its light is reflected from the water's surface as glare, obscuring the underwater view. When the sun is high, however, the sunlight penetrates the water and it is possible to see objects below the surface of the water. The angle at which this transition takes place is known as the *Brewster angle*,



Fig 18—The direct wave and the reflected wave combine at point P to form the pattern (P is very far from the antenna). At A the two paths AP and AGP differ appreciably in length, while at B these two path lengths are nearly equal.

named for the Scottish physicist, Sir David Brewster (1781-1868).

A similar situation exists in the case of vertically polarized antennas; the RF energy behaves as the sunlight in the optical system, and the earth under the antenna acts as the water. The *pseudo-Brewster angle* (PBA) is the angle at which the reflected wave is 90° out of phase with respect to the direct wave. "Pseudo" is used here because the RF effect is similar to the optical effect from which the term gets its name. Below this angle, the reflected wave is between 90° and 180° out of phase with the direct wave, so some degree of cancellation takes place. The largest amount of cancellation occurs near 0°, and steadily less cancellation occurs as the PBA is approached from below.

The factors that determine the PBA for a particular location *are not related to the antenna itself, but to the ground around it*. The first of these factors is earth conductivity, G, which is a measure of the ability of the soil to conduct electricity. Conductivity is the inverse of resistance. The second factor is the dielectric constant, k, which is a unitless quantity that corresponds to the capacitive effect of the earth. For both of these quantities, the higher the number, the better is the ground (for vertical antenna purposes). The third factor determining the PBA for a given location is the frequency of operation. The PBA increases with increasing frequency, all other conditions being equal. **Table 2** gives typical values of conductivity and dielectric constant for different types of soil. The map of **Fig 19** shows the approximate conductivity values for different areas in the continental United States.

As the frequency is increased, the role of the dielectric constant in determining the PBA becomes more significant. **Table 3** shows how the PBA varies with changes in ground conductivity, dielectric constant and frequency. The table shows trends in PBA dependency on ground constants and frequency. The constants chosen are not necessarily typical of any geographical area; they are just examples.

At angles below the PBA, the reflected vertically polarized wave subtracts from the direct wave, causing the radiation intensity to fall off rapidly. Similarly, above the PBA, the reflected wave adds to the direct wave, and the radiated pattern approaches the perfect-earth pattern. Fig 16 shows the PBA, usually labeled ψ_B.

When plotting vertical-antenna radiation patterns over real earth, the reflected wave from an antenna segment is multiplied by a factor called the *vertical reflection coefficient,* and the product is then added vectorially to the direct wave to get the resultant. The reflection coefficient consists of an attenuation factor, A, and a phase angle, ϕ, and is usually expressed as $A\angle\phi$. (ϕ is always a negative angle, because the earth acts as a lossy capacitor in this situation.) The following equation can be used to calculate the reflection coefficient for vertically polarized waves, for earth of given conductivity and dielectric constant at any frequency and elevation angle (also called the wave angle in many texts).

Table 2

Conductivities and Dielectric Constants for Common Types of Earth

Surface Type	*Dielectric Constant*	*Conductivity (S/m)*	*Relative Quality*
Fresh water	80	0.001	
Salt water	81	5.0	
Pastoral, low hills, rich soil, typ Dallas, TX, to Lincoln, NE areas	20	0.0303	Very good
Pastoral, low hills, rich soil typ OH and IL	14	0.01	
Flat country, marshy, densely wooded, typ LA near Mississippi River	12	0.0075	
Pastoral, medium hills and forestation, typ MD, PA, NY, (exclusive of mountains and coastline)	13	0.006	
Pastoral, medium hills and forestation, heavy clay soil, typ central VA	13	0.005	Average
Rocky soil, steep hills, typ mountainous	12-14	0.002	Poor
Sandy, dry, flat, coastal	10	0.002	
Cities, industrial areas	5	0.001	Very Poor
Cities, heavy industrial areas, high buildings	3	0.001	Extremely poor

Table 3
Pseudo-Brewster Angle Variation with Frequency, Dielectric Constant, and Conductivity

Frequency (MHz)	*Dielectric Constant*	*Conductivity (S/m)*	*PBA (degrees)*
7	20	0.0303	6.4
	13	0.005	13.3
	13	0.002	15.0
	5	0.001	23.2
	3	0.001	27.8
14	20	0.0303	8.6
	13	0.005	14.8
	13	0.002	15.4
	5	0.001	23.8
	3	0.001	29.5
21	20	0.0303	10.0
	13	0.005	15.2
	13	0.002	15.4
	5	0.001	24.0
	3	0.001	29.8

$$A_{\text{Vert}} \angle \phi = \frac{k' \sin \psi - \sqrt{k' - \cos^2 \psi}}{k' \sin \psi + \sqrt{k' - \cos^2 \psi}} \qquad \text{(Eq 3)}$$

where

$A_{\text{Vert}} \angle \phi$ = vertical reflection coefficient

ψ = elevation angle

$$k' = k - j \left| \frac{1.8 \times 10^4 \times G}{f} \right|$$

k = dielectric constant of earth (k for air = 1)

G = conductivity of earth in S/m

f = frequency in MHz

j = complex operator ($\sqrt{-1}$)

Solving this equation for several points indicates what effect the earth has on vertically polarized signals at a particular location for a given frequency range. **Fig 20** shows the reflection coefficient as a function of elevation angle at 21 MHz over average earth (G = 0.005 S/m, and k = 13).



Numbers on map represent estimated effective ground conductivity in millisiemens per meter

Conductivity of seawater is not shown on map but is assumed to be 500 millisiemens per meter

Estimated Effective
Ground Conductivity
in the United States

Fig 19—Typical average soil conductivities for the continental United States. Numeric values indicate conductivities in millisiemens per meter (mS/m), where 1.0 mS/m = 0.001 S/m.



Fig 20—Reflection coefficient for vertically polarized waves. A and ϕ are magnitude and angle for wave angles ψ. This case is for average earth, (k = 13, G = 0.005 S/m), at 21 MHz.

Note that as the phase curve, ψ, passes through 90°, the attenuation curve (A) passes through a minimum at the same wave angle ψ. This is the PBA. At this angle, the reflected wave is not only at a phase angle of 90° with respect to the direct wave, but is so low in amplitude that it does not aid the direct wave by a significant amount. In the case illustrated in Fig 20 this elevation angle is about 15°.

Variations in PBA with Earth Quality

From Eq 3, it is quite a task to search for either the 90° phase point or the attenuation curve minimum for a wide variety of earth conditions. Instead, the PBA can be calculated directly from the following equation.

$$\psi_B = \arcsin\sqrt{\frac{k-1+\sqrt{(x^2+k^2)^2(k-1)^2+x^2[(x^2+k^2)^2-1]}}{(x^2+k^2)^2-1}}$$

(Eq 4)

where k, G and f are as defined for Eq 3, and

$$x = \frac{1.8\times10^4\times G}{f}$$

Fig 21 shows curves calculated using Eq 4 for several different earth conditions, at frequencies between 1.8 and 30 MHz. As expected, poorer earths yield higher PBAs. Unfortunately, at the higher frequencies (where low-angle radiation is most important for DX work), the PBAs are highest. The PBA is the same for both transmitting and receiving.



Fig 21—Pseudo-Brewster angle (ψ) for various qualities of earth over the 1.8 to 30-MHz frequency range. Note that the frequency scale is logarithmic. The constants used for each curve are given in Table 2.

Relating PBA to Location and Frequency

Table 2 lists the physical descriptions of various kinds of earth with their respective conductivities and dielectric constants, as mentioned earlier. Note that in general, the dielectric constants and conductivities are higher for better earths. This enables the labeling of the earth characteristics as extremely poor, very poor, poor, average, very good, and so on, without the complications that would result from treating the two parameters independently.

Fresh water and salt water are special cases; in spite of high resistivity, the fresh-water PBA is 6.4°, and is nearly independent of frequency below 30 MHz. Salt water, because of its extremely high conductivity, has a PBA that never exceeds 1° in this frequency range. The extremely low conductivity listed for cities (the last case) in Table 2 results more from the clutter of surrounding buildings and other obstructions than any actual earth characteristic. The PBA at any location can be found for a given frequency from the curves in Fig 21.

FLAT-GROUND REFLECTIONS AND HORIZONTALLY POLARIZED WAVES

The situation for horizontal antennas is different from that of verticals. **Fig 22** shows the reflection coefficient for horizontally polarized waves over average earth at 21 MHz. Note that in this case, the phase-angle departure from 0° never gets very large, and the attenuation factor that causes the most loss for high-angle signals approaches unity for low angles. Attenuation increases with progressively poorer earth types.

In calculating the broadside radiation pattern of a horizontal λ/2 dipole, the perfect-earth image current, equal to the true antenna current but 180° out of phase with it) is multiplied by the horizontal reflection coefficient given by Eq 5 below. The product is then added vectorially to the direct wave to get the resultant at that elevation angle. The reflection coefficient for horizontally polarized waves can be calculated using the following equation.

$$A_{\text{Horiz}} \angle \phi = \frac{\sqrt{k' - \cos^2 \psi} - \sin \psi}{\sqrt{k' - \cos^2 \psi} + \sin \psi} \qquad \text{(Eq 5)}$$

where

$A_{\text{Horiz}} \angle \phi$ = horizontal reflection coefficient

ψ = elevation angle

$$k' = k - j \left(\frac{1.8 \times 10^4 \times G}{f} \right)$$

k = dielectric constant of earth
G = conductivity of earth in S/m
f = frequency in MHz
j = complex operator ($\sqrt{-1}$)

For a horizontal antenna near the earth, the resultant pattern is a modification of the free-space pattern of the antenna. **Fig 23** shows how this modification takes place for a horizontal λ/2 antenna over a perfectly conducting flat surface. The patterns at the left show the relative radiation when one views the antenna from the side; those at the right show the radiation pattern looking at the end of the antenna. Changing the height above ground from λ/4 to λ/2 makes a significant difference in the high-angle radiation, moving the main lobe down lower.

Note that for an antenna height of λ/2 (Fig 23, bottom), the out-of-phase reflection from a perfectly conducting surface creates a null in the pattern at the zenith (90° elevation angle). Over real earth, however, a *filling in* of this null occurs because of ground losses that prevent perfect reflection of high-angle radiation.

At a 0° elevation angle, horizontally polarized antennas also demonstrate a null, because out-of-phase reflection cancels the direct wave. As the elevation angle departs from 0°, however, there is a slight filling-in effect so that over other-than-perfect earth, radiation at lower angles is enhanced compared to a vertical. A horizontal antenna will often outperform a vertical for low-angle DX work, particularly over lossy types of earth at the higher frequencies.

Reflection coefficients for vertically and horizontally polarized radiation differ considerably at most angles above ground, as can be seen by comparison of Figs 20 and 22. (Both sets of curves were plotted for the same ground constants and at the same frequency, so they may be compared directly.) This is because, as mentioned earlier, the image of a horizontally polarized antenna is out-of-phase with the antenna itself, and the image of a vertical antenna is in-phase with the actual radiator.

The result is that the phase shifts and reflection magnitudes vary greatly at different angles for horizontal and vertical polarization. The magnitude of the reflection coefficient for vertically polarized waves is greatest (near unity) at very low angles, and the phase angle is close to 180°. As mentioned earlier, this cancels nearly all radiation at very low angles. For the same range of angles, the magnitude of the reflection coefficient for horizontally polarized waves is also near unity, but the phase angle is near 0° for the specific conditions shown in Figs 20 and 22. This causes reinforcement of low-angle horizontally polarized waves. At some relatively high angle, the reflection coefficients for



Fig 22—Reflection coefficient for horizontally polarized waves (magnitude A at angle ϕ), at 21 MHz over average earth (k = 13, G = 0.005 S/m).



Fig 23—Effect of the ground on the radiation from a horizontal half-wave dipole antenna, for heights of one-fourth and one-half wavelength. Broken lines show what the pattern would be if there were no reflection from the ground (free space).

horizontally and vertically polarized waves are equal in magnitude and phase. At this angle (approximately 81° for the example case), the effect of ground reflection on vertically and horizontally polarized signals will be the same.

DEPTH OF RF CURRENT PENETRATION

When considering earth characteristics, questions about depth of RF current penetration often arise. For instance, if a given location consists of a 6-foot layer of soil overlying a highly resistive rock strata, which material dominates? The answer depends on the frequency, the soil and rock dielectric constants, and their respective conductivities. The following equation can be used to calculate the current density at any depth.

$$e^{-pd} = \frac{\text{Current Density at Depth d}}{\text{Current Density at Surface}} \qquad \text{(Eq 6)}$$

where

d = depth of penetration in cm

e = natural logarithm base (2.718)

$$p = \left(\frac{X \times B}{2} \times \left(\sqrt{1 + \frac{G^2 \times 10^{-4}}{B^2}} - 1 \right) \right)^{1/2}$$

$X = 0.008 \times \pi^2 \times f$

$B = 5.56 \times 10^{-7} \times k \times f$

k = dielectric constant of earth

f = frequency in MHz

G = conductivity of earth in S/m

After some manipulation of this equation, it can be used to calculate the depth at which the current density is some fraction of that at the surface. The depth at which the current density is 37% (1/*e*) of that at the surface (often referred to as *skin depth*) is the depth at which the current density would be zero if it were distributed uniformly instead of exponentially. (This 1/*e* factor appears in many physical situations. For instance, a capacitor charges to within 1/*e* of full charge within one RC time constant.) At this depth, since the power loss is proportional to the square of the current, approximately 91% of the total power loss has occurred, as has most of the phase shift, and current flow below this level is negligible.

Fig 24 shows the solutions to Eq 6 over the 1.8 to 30-MHz frequency range for various types of earth. For example, in very good earth, substantial RF currents flow down to about 3.3 feet at 14 MHz. This depth goes to 13 feet in average earth and as far as 40 feet in very poor earth. Thus, if the overlying soil is rich, moist loam, the underlying rock stratum is of little concern. However, if the soil is only average, the underlying rock may constitute a major consideration in determining the PBA and the depth to which the RF current will penetrate.

The depth in fresh water is about 156 feet and is nearly independent of frequency in the amateur bands below 30 MHz. In salt water, the depth is about seven inches at 1.8 MHz and decreases rather steadily to about two inches at 30 MHz. Dissolved minerals in moist earth increase its conductivity.

The depth-of-penetration curves in Fig 24 illustrate a noteworthy phenomenon. While skin effect confines RF current flow close to the surface of a conductor, the earth is so lossy that RF current penetrates to much greater depths than in most other media. The depth of RF current penetration is a function of frequency as well as earth type. Thus, the only cases in which most of the current flows near the surface are with very highly conductive media (such as salt water), and at frequencies above 30 MHz.

DIRECTIVE PATTERNS OVER REAL GROUND

As explained in Chapter 2, Antenna Fundamentals, because antenna radiation patterns are three-dimensional, it is helpful in understanding their operation to use a form of representation showing the elevation-plane directional characteristic for different heights. It is possible to show selected elevation-plane patterns oriented in various directions with respect to the antenna axis. In the case of the horizontal half-wave dipole, a plane running in a direction along the axis and another broadside to the antenna will give a good deal of information.

The effect of reflection from the ground can be expressed as a separate *pattern factor*, given in decibels. For any given elevation angle, adding this factor algebraically to the value for that angle from the free-space pattern for that antenna gives the resultant radiation value at that



Fig 24—Depths at which the current density is 37% (1/*e*) of that at the surface for different qualities of earth over the 1.8- to 30-MHz frequency range. The depth for fresh water, not plotted, is 156 feet and almost independent of frequency below 30 MHz. See text and Table 2 for ground constants.

angle. The limiting conditions are those represented by the direct ray and the reflected ray being exactly in-phase and exactly out-of-phase, when both (assuming there are no ground losses) have equal amplitudes. Thus, the resultant field strength at a distant point may be either 6 dB greater than the free-space pattern (twice the field strength), or zero, in the limiting cases.

Horizontally Polarized Antennas

The way in which pattern factors vary with height for horizontal antennas over flat earth is shown graphically in the plots of **Fig 25**. The solid-line plots are based on perfectly conducting ground, while the shaded plots are based on typical real-earth conditions. These patterns apply to horizontal antennas of any length. While these graphs are, in fact, radiation patterns of horizontal single-wire antennas (dipoles) as viewed from the axis of the wire, it must be remembered that the plots merely represent pattern factors.

Fig 26 shows vertical-plane radiation patterns in the directions off the ends of a horizontal half-wave dipole for various antenna heights. These patterns are scaled so they may be compared directly to those for the appropriate heights in Fig 25. Note that the perfect-earth patterns in Figs 26A and 25B are the same as those in the upper part of Fig 23. Note also that the perfect-earth patterns of Figs 26B and 25D are the same as those in the lower section of Fig 23. The reduction in field strength off the ends of the wire at the lower angles, as compared with the broadside field strength, is quite apparent. It is also clear from Fig 26 that, at some heights, the high-angle radiation off the ends is nearly as great as the broadside radiation, making the antenna essentially an omnidirectional radiator.



A — Antenna 1/8 λ high
B — Antenna 1/4 λ high
C — Antenna 3/8 λ high



D — Antenna 1/2 λ high
E — Antenna 5/8 λ high
F — Antenna 3/4 λ high



G — Antenna 7/8 λ high
H — Antenna 1 λ high
I — Antenna 1–1/4 λ high



J — Antenna 1–1/2 λ high
K — Antenna 1–3/4 λ high
L — Antenna 2 λ high

Fig 25—Reflection factors for horizontal dipole antennas at various heights above flat ground. The solid-line curves are the perfect-earth patterns (broadside to the antenna wire); the shaded curves represent the effects of average earth (k = 13, G = 0.005 S/m) at 14 MHz. Add 7 dB to values shown for absolute gain in dBd referenced to dipole in free space, or 9.15 dB for gain in dBi. For example, peak gain over perfect earth at 5/8 λ height is 7 dBd (or 9.15 dBi) at 25° elevation.

In vertical planes making some intermediate angle between 0° and 90° with the wire axis, the pattern will have a shape intermediate between the broadside and end-on patterns. By visualizing a smooth transition from the end-on pattern to the broadside pattern as the horizontal angle is varied from 0° to 90°, a fairly good mental picture of the actual solid pattern may be formed. An example is shown in **Fig 27**. At A, the elevation-plane pattern of a half-wave dipole at a height of λ/2 is shown through a plane 45° away from the favored direction of the antenna. At B and C, the pattern of the same antenna is shown at heights of 3λ/4 and 1λ (through the same 45° off-axis plane). These patterns are scaled so they may be compared directly with the broadside and end-on patterns for the same antenna (at the appropriate heights) in Figs 25 and 26.

The curves presented in **Fig 28** are useful for determining heights of horizontal antennas that give either maximum or minimum reinforcement at any desired wave angle. For instance, if you want to place an antenna at a height so that it will have a null at 30°, the antenna should be placed where a broken line crosses the 30° line on the horizontal scale. There are two heights (up to 2 λ) that will yield this null angle: 1 λ and 2 λ.

As a second example, you may want to have the ground reflection give maximum reinforcement of the direct ray from a horizontal antenna at a 20° elevation angle. The antenna height should be 0.75 λ. The same height will give a null at 42° and a second lobe at 90°.

Fig 28 is also useful for visualizing the vertical pattern of a horizontal antenna. For example, if an antenna is erected at 1.25 λ, it will have major lobes (solid-line crossings) at 12° and 37°, as well as at 90° (the zenith). The nulls in this pattern (dashed-line crossings) will appear at 24° and 53°.

The Y-axis in Fig 28 plots the wave angle versus the height in wavelength above flat ground on the X-axis. Fig 28 doesn't show the elevation angles required for actual



A—Antenna 1/4 λ high
B—Antenna 1/2 λ high
C—Antenna 3/4 λ high
D—Antenna 1 λ high
E—Antenna 1-1/4 λ high
F—Antenna 1-1/2 λ high

Fig 26—Vertical-plane radiation patterns of horizontal half-wave dipole antennas off the ends of the antenna wire. The solid-line curves are the flat, perfect-earth patterns, and the shaded curves represent the effects of average flat earth (k = 13, G = 0.005 S/m) at 14 MHz. The 0-dB reference in each plot corresponds to the peak of the main lobe in the favored direction of the antenna (the maximum gain). Add 7 dB to values shown for absolute gain in dBd referenced to dipole in free space, or 9.15 dB for gain in dBi.



A—Height 1/2 λ
B—Height 3/4 λ
C—Height 1 λ

Fig 27—Vertical-plane radiation patterns of half-wave horizontal dipole antennas at 45° from the antenna wire over flat ground. The solid-line and shaded curves represent the same conditions as in Figs 25 and 26. These patterns are scaled so they may be compared directly with those of Figs 25 and 26.



Fig 28—Angles at which nulls and maxima (factor = 6 dB) in the ground-reflection factor appear for antenna heights up to two wavelengths over flat ground. The solid lines are maxima, dashed lines nulls, for all horizontal antennas. See text for examples. Values may also be determined from the trigonometric relationship θ = arc sin (A/4h), where θ is the wave angle and h is the antenna height in wavelengths. For the first maximum, A has a value of 1; for the first null A has a value of 2, for the second maximum 3, for the second null 4, and so on.

communications to various target geographic locations of interest. Chapter 23, Radio Wave Propagation, and the CD-ROM in the back of this book give details about the range of angles required for target locations around the world. It is very useful to overlay plots of these angles together with the elevation pattern for horizontally polarized antennas at various heights above flat ground. This will be demonstrated in detail later in this chapter.

Vertically Polarized Antennas

In the case of a vertical λ/2 dipole or a ground-plane antenna, the horizontal directional pattern is simply a circle at any elevation angle (although the actual field strength will vary, at the different elevation angles, with the height above ground). Hence, one vertical pattern is sufficient to give complete information (for a given antenna height) about the antenna in any direction with respect to the wire. A series of such patterns for various heights is given in **Fig 29**. Rotating the plane pattern about the zenith axis of the graph forms the three-dimensional radiation pattern in each case.

The solid-line curves represent the radiation patterns of the λ/2 vertical dipole at different feed-point heights over perfectly conducting ground. The shaded curves in Fig 29 show the patterns produced by the same antennas at the same heights over average ground (G = 0.005 S/m, k = 13) at 14 MHz. The PBA in this case is 14.8°.

In short, far-field losses for vertically polarized antennas are highly dependent on the conductivity and dielectric constant of the earth around the antenna, extending far beyond the ends of any radials used to complete the ground return for the near field. Putting more radials out around the antenna may well decrease ground-return losses in the reactive near field for a vertical monopole, but will not increase radiation at low elevation launch angles in the far field, unless the radials can extend perhaps 100 wavelengths in all directions! Aside from moving to the fabled "salt water swamp on a high hill," there is very little that someone can do to change the character of the ground that affects the far-field pattern of a real vertical. Classical texts



A—Antenna 1/8 λ high

B—Antenna 1/4 λ high

C—Antenna 1/2 λ high



D—Antenna 3/4 λ high

E—Antenna 1 λ high

F—Antenna 1-1/2 λ high

Fig 29—Vertical-plane radiation patterns of a ground-plane antenna above flat ground. The height is that of the ground plane, which consists of four radials in a horizontal plane. Solid lines are perfect-earth patterns; shaded curves show the effects of real earth. The patterns are scaled—that is, they may be directly compared to the solid-line ones for comparison of losses at any wave angle. These patterns were calculated for average ground (k = 13, G = 0.005 S/m) at 14 MHz. The PBA for these conditions is 14.8°. Add 6 dB to values shown for absolute gain in dBd over dipole in free space.

on verticals often show elevation patterns computed over an "infinitely wide, infinitely conducting ground plane." Real ground, with finite conductivity and less than perfect dielectric constant, can severely curtail the low-angle radiation at which verticals are supposed to excel.

While real verticals over real ground are not a surefire method to achieve low-angle radiation, cost versus performance and ease of installation are still attributes that can highly recommend verticals to knowledgeable builders. Practical installations for 160 and 80 meters rarely allow amateurs to put up horizontal antenna high enough to radiate effectively at low elevation angles. After all, a half-wave on 1.8 MHz is 273 feet high, and even at such a lofty height the peak radiation would be at a 30° elevation angle.

The Effects of Irregular Local Terrain in the Far Field

The following material is condensed and updated from an article by R. Dean Straw, N6BV, in July 1995 *QEX* magazine. *HFTA* (HF Terrain Assessment) and supporting data files are included on the CD-ROM at the back of this book. *HFTA* is the latest version of the *YT* program included with earlier editions of *The ARRL Antenna Book.*

Choosing a QTH for DXing

The subject of how to choose a QTH for working DX has fascinated hams since the beginning of amateur operations. No doubt, Marconi probably spent a lot of time wandering around Newfoundland looking for a great radio QTH before making the first transAtlantic transmission. Putting together a high-performance HF station for contesting or DXing has always followed some pretty simple rules. First, you need the perfect QTH, preferably on a rural mountaintop or at least on top of a hill. Even better yet, you need a mountaintop surrounded by seawater! Then, after you have found your dream QTH, you put up the biggest antennas you possibly can, on the highest towers you can afford. Then you work all sorts of DX—sunspots willing, of course.

The only trouble with this straightforward formula for success is that it doesn't always work. Hams fortunate enough to be located on mountain tops with really spectacular drop-offs often find that their highest antennas don't do very well, especially on 15 or 10 meters, but often even on 20 meters. When they compare their signals with nearby locals in the flatlands, they sometimes (but not always) come out on the losing end, especially when sunspot activity is high.

On the other hand, when the sunspots drop into the cellar, the high antennas on the mountaintop are usually the ones crunching the pileups—but again, not always. So, the really ambitious contest aficionados, the guys with lots of resources and infinite enthusiasm, have resorted to putting up antennas at all possible heights, on a multitude of towers.

There is a more scientific way to figure out where and how high to put your antennas to optimize your signal during all parts of the 11-year solar cycle. We advocate a *system approach* to HF station design, in which you need to know the following:

1. The range of elevation angles necessary to get from point A to point B
2. The elevation patterns for various types and configurations of antennas
3. The effect of local terrain on elevation patterns for horizontally polarized antennas.

WHAT IS THE RANGE OF ELEVATION ANGLES NEEDED?

Up until 1994, *The ARRL Antenna Book* contained only a limited amount of information about the elevation angles needed for communication throughout the world. In the 1974 edition, Table 1-1 in the Wave Propagation chapter was captioned: "Measured vertical angles of arrival of signals from England at receiving location in New Jersey."

What the caption didn't say was that Table 1-1 was derived from measurements made during 1934 by Bell Labs. The highest frequency data seemed pretty shaky, considering that 1934 was the low point of Cycle 17. Neither was this data applicable to any other path, other than the one from New Jersey to England. Nonetheless, many amateurs located throughout the US tried to use the sparse information in Table 1-1 as the only rational data they had for determining how high to mount their antennas. (If they lived on hills, they made estimates of the effect of the terrain, assuming that the hill was adequately represented by a long, unbroken slope. More on this later.)

In 1993 ARRL HQ embarked on a major project to tabulate the range of elevation angles from all regions of the US to important DX QTHs around the world. This was accomplished by running many thousands of computations using the *IONCAP* computer program. *IONCAP* has been under development for more than 25 years by various agencies of the US government and is considered the standard of comparison for propagation programs by many agencies, including the Voice of America, Radio Free Europe, and more than 100 foreign governments throughout the world. *IONCAP* is a real pain in the neck to use, but it is the standard of comparison.

The calculations were done for all levels of solar activity, for all months of the year, and for all 24 hours of the day. The results were gathered into some very large databases, from which special custom-written software extracted detailed statistics. The results appeared in summary form in Tables 4 through 13 printed in Chapter 23, Radio Wave Propagation, of the 17th Edition and in more detail on the diskette included with that book. (This book, the 20th Edition, contains even more statistical data, for more areas of the world, on the accompanying CD-ROM.)

Fig 30 shows the full range of elevation angles (represented as vertical bars) for the 20-meter path from New England (centered on Newington, Connecticut) to all of Europe. This is for all openings, in all months, over the entire 11-year solar cycle. The most likely elevation angle occurs at 5° for about 13% of the times when the 20-meter band is open to Europe from New England. From 4° to 6° the band is open a total of about 34% of the times the band is open. There is a secondary peak between 10° to 12°, occurring for a total of about 25% of the times the band is open.

Overlaid on Fig 30 along with the elevation-angle statistics are the elevation-plane responses for three different horizontally polarized Yagi beams, all over flat ground. The first is mounted 140 feet high, 2 λ in terms of wavelength. The second Yagi is mounted 70 feet high (at 1 λ) and the third is 35 feet (0.5 λ). The 140-foot high antenna has a deep null at 15°, but it also has the highest response (13.4 dBi) of the three at the statistical peak elevation angle of 5°. However, at 12°—where the band is open some 9% of the time—the 140-foot high Yagi is down 4 dB compared to the 70-foot antenna.



Fig 30—Graph showing 20-meter percentage of all openings from New England to Europe versus elevation angles, together with overlay of elevation patterns over flat ground for three 20-meter antenna systems. The most statistically likely angle at which the band will be open is 5°, although at any particular hour, day, month and year, the actual angle will likely be different. Note the deep null exhibited by the 140-foot high antenna centered at 14°.

The 70-foot high Yagi arguably covers the overall range best, since it has no disastrous nulls in the 1° to 25° range, where most of the action is occurring on 20 meters. At 5°, however, its response is only 8.8 dBi, 4.6 dB down from the 140-foot high antenna at that angle. The 35-foot antenna peaks above 26° in elevation angle, and is down some 10.4 dB compared to the 140-foot antenna at 5°. Obviously, no single antenna covers the complete range of elevation angles needed.

Note that the highest Yagi has a strong *second lobe* peaking at 22°. Let's say that you could select between two antennas, one at 140 and one at 70 feet, and that the incoming angle for a particular distant station is 22°. You might be fooled into thinking that the incoming angle is around 6°, favoring the first peak of the higher antenna, when in truth the angle is relatively high. The 70-foot antenna's response would be lower at 22° than the higher one, but only because the 140-foot antenna is operating on its second lobe. (What would clinch a determination of the correct incoming angle—6° or 22°—would be the response of the 35-foot high Yagi, which would be close to its peak at 22°, while it would be very far down at 6°.)

Now, we must emphasize that these elevation angles are *statistical entities*— in other words, just because 5° is the "statistically most likely angle" for the 20-meter path from New England to Europe doesn't mean that the band will be open at 11° at any particular hour, on a particular day, in a particular month, in any particular year. In fact, however, experience agrees with the *IONCAP* computations: the 20-meter path to Europe usually opens at a low angle in the New England morning hours, rising to about 11° during the afternoon, when the signals remain strongest throughout the afternoon until the evening in New England.

What would happen if we were to feed all three Yagi at 140, 70 and 35 feet in-phase as a stack? **Fig 31** shows this situation, along with a more highly optimized stack at 120, 80 and 40 feet that better covers the overall range of elevation angles from Connecticut to Europe.

Now see **Fig 32**, which uses the same 120/80/40-foot stack of 20-meter antennas as in Fig 31, but this time from Seattle, Washington, to Europe. For comparison, the response of a single 4-element Yagi at 100 feet over flat ground is also shown in Fig 32. Just because 5º is the statistically most prevalent angle (occurring some 13% of the time) from Seattle to Europe on 20 meters, this doesn't mean that the actual angle *at any particular moment in time* might not be 10º, or even 2º. The statistics for W7 to Europe say that 5º is the most likely angle, but 20-meter signals from Europe arrive at angles ranging from 1º to 18º. Note that this range of angles is quite a bit less than from W1 to Europe, which is much closer geographically to Europe than is the Pacific Northwest coast of the US. If you design an antenna system to cover all possible angles needed to talk to Europe from Seattle (or from Seattle to Europe) on 20 meters, you would need to cover the full range from 1º to 18º equally well.



Fig 31—Graph showing results of stacking antennas at different heights on the same tower to cover a wider range of elevation angles, in this case for the path from Connecticut (W1) to all of Europe on 20 meters. The optimized stack at 120/80/40 feet covers the needed range of elevation angles better than the stack at 140/70/35 feet or the single Yagi at 140 feet.



Fig 33—Graph showing 15-meter percentage of all openings from Chicago to Southern Africa, together with overlay of elevation patterns over flat ground for two 15-meter antenna systems. On this long-distance, low-angle path, higher antennas are again most effective.



Fig 32—Graph showing 20-meter percentage of all openings, this time from Seattle, WA, to Europe, together with an overlay of elevation patterns over flat ground for two 20-meter antenna systems. The statistically most likely angle on this path is 5°, occurring about 13% of the time when the band is actually open. Higher antennas predominate on this low-angle path.

Similarly, if you wish to cover the full range of elevation angles from Chicago to Southern Africa on 15 meters, you would need to cover 1º to 13º, even though the most statistically likely signals arrive at 1º, for 21% of the time when that the band is open for that path. See **Fig 33**.

It is important to recognize that Figs 30 through 33 are for flat ground. When the antennas are mounted over irregular local terrain, things get much more complicated. First, however, we’ll discuss general-purpose antenna modeling programs as they try to model real terrain.

DRAWBACKS OF COMPUTER MODELS FOR ANTENNAS OVER REAL TERRAIN

Modern general-purpose antenna modeling programs such as *NEC* or *MININEC* (or their commercially upgraded equivalents, such as *NEC-Win Plus*, *EZNEC* and *EZNEC ARRL*) can accurately model almost any type of antenna commonly used by radio amateurs. In addition, there are specialized programs specifically designed to model Yagis efficiently, such as *YO* or *YW* (Yagi for Windows, bundled on the CD-ROM with this book) or *YagiMax*. These programs however are all unable to model antennas accurately over anything other than *purely flat ground*.

While both *NEC* and *MININEC* can simulate irregular ground terrain, they do so in a decidedly crude manner, employing step-like concentric rings of height around an antenna. The documentation for *NEC* and *MININEC* both clearly state that diffraction off these steps is not modeled.

Common experience among serious modelers is that the warnings in the manuals are worth heeding.

Although you can analyze and even optimize antenna designs using free-space or flat-earth ground models, it is *diffraction* that makes the real world a very, very complicated place. This should be clarified—diffraction is hard, even tortuous, to analyze properly, but it makes analysis of real world results far more believable than a flat-world reflection model does.

RAY-TRACING OVER UNEVEN LOCAL TERRAIN

The Raytracing Technique

First, let's look at a simple raytracing procedure involving only horizontally polarized reflections, with no diffractions. From a specified height on the tower, an antenna shoots "rays" (just as though they were bullets) in 0.25° increments from +35° above the horizon to –35° below the horizon. Each ray is traced over the foreground terrain to see if it hits the ground at any point on its travels in the direction of interest. If it does hit the ground, the ray is reflected following the classical *law of reflection*. That is, the outgoing angle equals the incoming angle, reflected through the normal to the slope of the surface. Once the rays exit into the ionosphere, the individual contributions are vector-summed to create the overall far-field elevation pattern.

The next step in terrain modeling involves adding *diffractions* as well as reflections. At the Dayton antenna forum in 1994, Jim Breakall, WA3FET, gave a fascinating and tantalizing lecture on the effect of foreground terrain. Later Breakall, Dick Adler, K3CXZ, Joel Young and a group of other researchers published an extremely interesting paper entitled "The Modeling and Measurement of HF Antenna Skywave Radiation Patterns in Irregular Terrain" in July 1994 *IEEE Transactions on Antennas and Propagation*. They described in rather general terms the modifications they made to the *NEC-BSC* program. They showed how the addition of a ray-tracing reflection and diffraction model to the simplistic stair-stepped reflection model in regular *NEC* gave far more realistic results. For validation, they compared actual pattern measurements made on a site in Utah (with an overflying helicopter) to computed patterns made using the modified *NEC* software. However, because the US Navy funded this work the software remained for a long time a military secret.

Thumbnail History of the Uniform Theory of Diffraction

It is instructive to look briefly at the history of how *Geometric Optics* (GO) evolved (and still continues to evolve) into the *Uniform Theory of Diffraction* (UTD). The following is summarized from the historical overview in one book found to be particularly useful and comprehensive on the subject of UTD: *Introduction to the Uniform Geometrical Theory of Diffraction*, by McNamara, Pistorius, and Malherbe.

Many years before the time of Christ, the ancient Greeks studied optics. Euclid is credited with deriving the law of reflection about 300 BC. Other Greeks, such as Ptolemy, were also fascinated with optical phenomena. In the 1600s, a Dutchman named Snell finally figured out the law of refraction, resulting in *Snell's law*. By the early 1800s, the basic world of classical optics was pretty well described from a mathematic point of view, based on the work of a number of individuals.

As its name implies, classical geometric optical theory deals strictly with geometric shapes. Of course, the importance of geometry in optics shouldn't be minimized—after all, we wouldn't have eyeglasses without geometric optics. Mathematical analysis of shapes utilizes a methodology that traces the paths of straight-line *rays* of light. (Note that the paths of rays can also be likened to the straight-line paths of particles.) In classical geometric optics, however, there is no mention of three important quantities: phase, intensity and polarization. Indeed, without phase, intensity or polarization, there is no way to deal properly with the phenomenon of *interference*, or its cousin, *diffraction*. These phenomena require theories that deal with *waves* rather than rays.

Wave theory has also been around for a long time, although not as long as geometry. Workers like Hooke and Grimaldi had recorded their observations of interference and diffraction in the mid 1600s. Huygens had used elements of wave theory in the late 1600s to help explain refraction. By the late 1800s, the work of Lord Rayleigh, Sommerfeld, Fresnel, Maxwell and many others led to the full mathematic characterization of all electromagnetic phenomena, light included.

Unfortunately, ray theory doesn't work for many problems, at least ray theory in the classical optical form. The real world is a lot more jagged, pointy and fuzzy in shape than can be described in a totally rigorous mathematic fashion. Some properties of the real world are most easily explained on the micro level using electrons and protons as conceptual objects, while other macro phenomena (like resonance, for example) are more easily explained in terms of waves. To get a handle on a typical real-world physical situation, a combination of classical ray theory and wave theory was needed.

The breakthrough in the combination of classical geometric optics and wave concepts came from J. B. Keller of Bell Labs in 1953, although he published his work in the early 1960s. In the very simplest of terms, Keller introduced the notion that shooting a ray at a diffraction *wedge* causes wave interference at the tip, with an infinite number of diffracted waves emanating from the diffraction point. Each diffracted wave can be considered to be a point source radiator at the place of generation, the diffraction point. Thereafter, the paths of individual waves can be traced as though they were individual classical optic rays again. What Keller came up with was a reasonable mathematical description of what happens at the tip of the diffraction wedge.

Fig 34 is a picture of a simple diffraction wedge, with an incoming ray launched at an angle of α_r, referenced to the horizon, impinging on it. The diffraction wedge here is considered to be perfectly conducting, and hence impenetrable by the ray. The wedge generates an infinite number of diffracted waves, going in all directions not blocked by the wedge itself. The amplitudes and phases of the diffracted waves are determined by the interaction at the wedge tip, and this in turn is governed by the various angles associated with the wedge. Shown in Fig 34 are the included angle a of the wedge, the angle ϕ' of the incoming ray (referenced to the incoming surface of the wedge), and the observed angle ϕ of one of the outgoing diffracted waves, also referenced to the wedge surface.

The so-called *shadow boundaries* are also shown in Fig 34. The Reflection-Shadow Boundary (RSB) is the angle beyond which no further reflections can take place for a given incoming angle. The Incident-Shadow Boundary (ISB) is that angle beyond which the wedge's face blocks any incident rays from illuminating the observation point.

Keller derived the amplitude and phase terms by comparing the classical Geometric Optics (GO) solution with the exact mathematical solution calculated by Sommerfeld for a particular case where the boundary conditions were well known—an infinitely long, perfectly conducting wedge illuminated by a plane wave. Simply speaking, whatever was left over had to be diffraction terms. Keller combined these diffraction terms with GO terms to yield the total field everywhere.

Keller's new theory became known as the *Geometric Theory of Diffraction* (abbreviated henceforth as GTD). The beauty of GTD was that in the regions where classical GO predicted zero fields, the GTD "filled in the blanks," so to speak. For example, see **Fig 35**, showing the terrain for a hypothetical case, where a 60-foot high 4-element 15-meter Yagi illuminates a wide, perfectly flat piece of ground. A 10-foot high rock has been placed 400 feet away from the tower base in the direction of outgoing rays. **Fig 36** shows the elevation pattern predicted using reflection-only GO techniques. Due to blockage of the direct wave (A) trying to shoot past the 10-foot high rock, and due to blockage of (B) reflections from the flat ground in front of the rock by the rock, there is a *hole* in the smooth elevation pattern.

Now, doesn't it defy common sense to imagine that a single 10-foot high rock will really have such an effect on a 15-meter signal? Keller's GTD took diffraction effects into account to show that waves do indeed sneak past and over the rock to fill in the pattern. The whole GTD scheme is very clever indeed.

However, GTD wasn't perfect. Keller's GTD predicts some big spikes in the pattern, even though the overall shape of the elevation pattern is much closer to reality than a simple GO reflection analysis would indicate. The region right at the RSB and ISB shadow boundaries is where problems are found. The GO terms go to zero at these points because of blockage by the wedge, while Keller's diffraction terms tend to go to infinity at these very spots. In mathematical terms this is referred to as a *caustic problem*. Nevertheless, despite these nasty problems at the ISB and RSB, the GTD provided a remarkably better solution to diffraction problems than did classical GO.

In the early 1970s, a group at Ohio State University under R. G. Kouyoumjian and P. H. Pathak did some pivotal work to resolve this caustic problem, introducing what amounts to a clever *fudge factor* to compensate for the tendency of the diffraction terms at the shadow boundaries to go to infinity. They introduced what is known as a *transition function*, using a form of Fresnel integral. Most importantly, the Ohio State researchers also created several FORTRAN computer programs to compute the amplitude and phase of diffraction components. Now computer hackers could get to work!



Fig 34—Diagram showing diffraction mechanism of ray launched at angle α_r below the horizon at a diffraction wedge, whose included angle is α. Referenced to the incident face (the *o-face* as it is called in UTD terminology), the incoming angle is ϕ' (phi prime). The wedge creates an infinite number of diffracted waves. Shown is one whose angle referenced to the o-face is ϕ, the so-called *observation angle* in UTD terminology.



Fig 35—Hypothetical terrain exhibiting so-called "10-foot rock effect." The terrain is flat from the tower base out to 400 feet, where a 10-foot high rock is placed. Note that this forms a diffraction wedge, but that it also blocks direct waves trying to shoot through it to the flat surface beyond, as shown by Ray A. Ray B reflects off the flat surface before it reaches the 10-foot rock, but it is blocked by the rock from proceeding further. A simple Geometric Optics (GO) analysis of this terrain without taking diffraction into account will result in the elevation response shown in Fig 36.



Fig 36—Elevation response for rays launched at terrain in Fig 35 from a height of 60 feet using a 4-element Yagi. This was computed using a simple Geometrical Optics (GO) reflection-only analysis. Note the ***hole*** in the response between 6° to 10° in elevation. It is not reasonable for a 10-foot high rock to create such a disturbance at 21 MHz!

The program that finally resulted is called *HFTA*, standing for "HF Terrain Assessment." (The DOS version of *HFTA* was known as *YT*, standing for "Yagi Terrain.") As the name suggests, *HFTA* analyzes the effect of local terrain on HF propagation through the ionosphere. It is designed for horizontally polarized Yagis, although it will model the effects of a simple flattop dipole also. The accurate appraisal of the effect of terrain on vertically polarized signals is a far more complex problem than for horizontally polarized waves, and *HFTA* doesn't do verticals.

SIMULATION OF REALITY—SOME SIMPLE EXAMPLES FIRST

We want to focus first on some simple results, to show that the computations do make some sense by presenting some simulations over simple terrains. We've already described the "10-foot rock at 400 feet" situation, and showed where a simple GO reflection analysis is inadequate to the task without taking diffraction effects into account.

Now look at the simple case shown in **Fig 37**, where a very long, continuous downslope from the tower base is shown. Note that the scales used for the X and Y axes are different: the Y-axis changes 300 feet in height (from 800 to 1100 feet), while the X-axis goes from 0 to 3000 feet. This exaggerates the apparent steepness of the downwards slope, which is actually a rather gentle slope, at $\tan^{-1}(1000-850)/(3000-0)=-2.86°$. In other words, the terrain falls 150 feet in height over a range of 3000 feet from the base of the tower.

Fig 38 shows the computed elevation response for this terrain profile, for a 4-element horizontally polarized Yagi on a 60-foot tower. The response is compared to that of an identical Yagi placed 60 feet above flat ground. Compared to the "flatland" antenna, the hilltop antenna has an elevation response shifted over by almost 3° towards the lower elevation angles. In fact, this shift is directly due to the –2.86° slope of the hill. Reflections off the slope are tilted by the slope. In this situation there is a single diffraction at the bottom of the gentle slope at 3000 feet, where the program assumes that the terrain becomes flat.

Look at **Fig 39**, which shows another simple terrain profile, called a "Hill-Valley" scenario. Here, the 60-foot high tower stands on the edge of a gentle hill overlooking a long valley. Once again the slope of the hill is exaggerated by the different X and Y-axes. **Fig 40** shows the computed elevation response at 21.2 MHz for a 4-element Yagi on a 60-foot high tower at the edge of the slope.

Once again, the pattern is overlaid with that of an identical 60-foot-high Yagi over flat ground. Compared to the flatland antenna, the hilltop antenna's response above 9° in elevation is shifted by almost 3° towards the lower elevation angles. Again, this is due to reflections off the downward slope. From 1° to 9°, the hilltop pattern is enhanced even more compared to the flatland antenna, this time by diffraction occurring at the bottom of the hill.

Now let's see what happens when there is a hill ahead in the direction of interest. **Fig 41** depicts such a situation, labeled "Hill-Ahead." Here, at a height of 400 feet above mean sea level, the land is flat in front of the tower, out to a distance 500 feet, where the hill begins. The hill then rises 100 feet over the range 500 to 1000 feet away



Fig 37—A long, gentle downwards-sloping terrain. This terrain has no explicit diffraction points and can be analyzed using simple GO reflection techniques.



Fig 38—Elevation response for terrain shown in Fig 37, using a 4-element 15-meter Yagi, 60-foot high. Note that the shape of the response is essentially shifted towards the left, towards lower elevation angles, by the angle of the sloping ground. For reference, the response for an identical Yagi placed over flat ground is also shown.

from the tower base. After that, the terrain is a plateau, at a constant 500 feet elevation.

Fig 42 shows the computed elevation pattern for a 4-element 21-MHz Yagi 60-feet high on the tower, compared again with an overlay for an identical 60-foot high antenna over flat ground. The hill blocks low-angle waves directly radiated from the antenna from 0° to 2.3°. In addition, waves that would normally be reflected from the ground, and that would normally add in phase from about 2.3° to 12°, are blocked by the hill also. Thus the signal at 8° is down almost 5 dB from the signal over flat ground, all due to the effect of the hill. Diffracted waves start kicking in once the direct wave rises enough above the horizon to illuminate the top edge of the hill. These diffracted waves tend to augment elevation angles above about 12°, which reflected waves can't reach.



Fig 39—"Hill-Valley" terrain, with reflected and diffracted rays.



Fig 40—Elevation response computed by *HFTA* program for single 4-element 15-meter Yagi at 60 feet above "Hill-Valley" terrain shown in Fig 39. Note that the slope has caused the response in general to be shifted towards lower elevation angles. At 5° elevation, the diffraction components add up to increase the gain slightly above the amount a GO-only analysis would indicate.

Is there is any hope for someone in such a lousy QTH for DXing? **Fig 43** shows the elevation response for a truly heroic solution. This involves a stack of four 4element Yagis, mounted at 120, 90, 60 and 30 feet on the tower. Now, the total gain at low angles is just about comparable to that from a single 4-element Yagi mounted over flat ground. Where there's a ham, there is a way!



Fig 41—"Hill-Ahead" terrain, shown with diffracted rays created by illumination of the edge of the plateau at the top of the hill.



Fig 42—Elevation response computed by *HFTA* for "Hill-Ahead" terrain shown in Fig 41. Now the hill blocks direct rays and also precludes possibility of any constructive reflections. Above 10°, diffraction components add up together with direct rays to create the response shown.

At 5° elevation, four diffraction components add up (there are zero reflection components) to achieve the far-field pattern. This seems reasonable, because each of the four antennas is illuminating the diffraction point separately and we know that none of the four antennas can *see over* the hill directly to produce a reflection at a low launch angle.

At an elevation angle of 5°, 15-meter signals arrive from Europe from New England about 13% of the total time when the band is actually open. We can look at this another way. For about two-thirds of the times when the band is open on this path, the incoming angle is between 3° to 12°. For about one-third of the time, signals arrive above 10°, where the "heroic" four-stack is really beginning to come into its own.



Fig 43—Elevation response of "heroic effort" to surmount the difficulties imposed by hill in Fig 41. This effort involves a stack of four 4-element Yagis in a stack starting at 120 feet and spaced at 30-foot increments on the tower. The response is roughly equivalent to a single 4-element Yagi at 60 feet above flat ground, hence the characterization as being a "heroic effort." The elevation-angle statistics from New England to Europe are overlaid on the graph for reference.

A More Complex Terrain

The results for simple terrains look reasonable; let's try a more complicated real-world situation. **Fig 44** shows the terrain from the New Hampshire N6BV/1 QTH towards Japan. The terrain was complex, with 52 different points *HFTA* identifies as diffraction points. **Fig 45** shows a labeled *HFTA* output for three different types of antennas on 20 meters: a stack at 120 and 60 feet, the 120-foot antenna by itself, and then a 120/60-foot stack over flat ground, for reference. The elevation-angle statistics for New England to Japan are overlaid on the graph also, making for a very complicated looking picture—it is a *lot* easier to decipher the lines on the color CRT, by the way than on a black-and-white printer.

Comparison of the same 120/60-foot stacks over irregular terrain and flat ground is useful to show where the terrain itself is affecting the elevation response. The flatland stack has more gain in the region of 3° to 7° than the same stack over the N6BV/1 local terrain towards Japan. On the other hand, the N6BV/1 local terrain boosts signals in the range of 8° to about 12°. This demonstrates the conservation of energy—you may gain a stronger signal at certain elevation angles, but you will lose gain at others. In this case, the N6BV/1 station always felt "weak" towards Japan on 20 meters, because the dominant angles are low.

Examination of the detailed data output from *HFTA* shows that at an elevation angle of 5°, there are 6159



Fig 44—Terrain of N6BV in Windham, NH, towards Japan. *HFTA* identifies 52 different points where diffraction can occur.

diffraction components. There are many, many signals bouncing around off the terrain on their trip to Japan! Note that because of blockage of some parts of the terrain, the 60-foot high Yagi cannot illuminate all the diffraction points, while the higher 120-foot Yagi is able to see these diffraction points.

It is fascinating to reflect on the thought that received signals coming down from the ionosphere to the receiver are having encounters with the terrain, but from the opposite direction. It's not surprising, given these kinds of interactions, that transmitting and receiving might not be totally reciprocal.

The 120/60-foot stack in Fig 45 achieves its peak gain of 17.3 dBi at 11° elevation, where it is about 3 dB stronger than the single Yagi at 120 feet. It maintains this 3-dB advantage over most of the range of incoming signals from Japan. This difference in performance between the stack and each antenna by itself was observed many times on the air. Much of the time when comparisons are being made, however, the small differences in signal are difficult to measure meaningfully, especially when the QSB varies signals by 20 dB or so during a typical QSO. It should be noted that the stack usually exhibited less fading compared to each antenna by itself.

USING *HFTA*

Manually Generating a Terrain Profile

The *HFTA* program uses two distinct algorithms to generate the far-field elevation pattern. The first is a simple reflection-only Geometric Optics (GO) algorithm. The second is the diffraction algorithm using the Uniform Theory of Diffraction (UTD). These algorithms work with a digitized representation of the terrain profile for a single azimuthal direction—for example, towards Japan or towards Europe.



Fig 45—Elevation responses computed by *HFTA* for N6BV/1 terrain shown in Fig 44, for a stack of two 4-element 20-meter Yagis at 120 and 60 feet, together with the response for a single Yagi at 120 feet and a 120/60-foot stack over flat ground for reference. The response due to many diffraction and reflection components is quite complicated!

You can generate a terrain file manually using a topographic map and a ruler or a pair of dividers. The HFTA.PDF file (accessed by clicking on the **Help** button) and on the accompanying CD-ROM gives complete instructions on how to create a terrain file manually (or automatically). The manual process is simple enough in concept. Mark on your US Geological Survey 7.5-minute map the exact location of your tower. You will find 7.5-minute maps available from some local sources, such as large hardware stores, but the main contact point is the U.S. Geological Survey, Denver, CO 80225 or Reston, VA 22092. Call 1-800-MAPS-USA. Ask for the folder describing the topographic maps available for your geographic area. Many countries outside the USA have topographic charts also. Most are calibrated in meters. To use these with *HFTA*, you will have to convert meters to feet by multiplying meters by 3.28 or else inserting a single line at the very beginning of the disk file, saying "meters" for *HFTA* to recognize meters automatically.

Mark off a pencil line from the tower base, in the azimuthal direction of interest, perhaps 45° from New England to Europe, or 335° to Japan. Then measure the distance from the tower base to each height contour crossed by the pencil line. Enter the data at each distance/height into an ASCII computer file, whose filename extension is "PRO," standing for *profile*.

Fig 46 shows a portion of the USGS paper map for the N6BV QTH in Windham, NH, along with lines scribed in several directions towards various parts of Europe and the Far East. Note that the elevation heights of the intermediate contour lines are labeled manually in pencil in order to make sense of things. It is very easy to get confused unless you do this!

The terrain model used by *HFTA* assumes that the terrain is represented by flat *plates* connecting the elevation points in the *.PRO file with straight lines. The model is two dimensional, meaning that range and elevation are the only data for a particular azimuth. In effect, *HFTA* assumes that the width of a terrain plate is wide relative to its length. Obviously, the world is three-dimensional. If your shot in a particular direction involves aiming your Yagi down a canyon with steep walls, then it's pretty likely that your actual elevation pattern will be different than what *HFTA* tells you. The signals must careen horizontally from wall to wall, in addition to being affected by the height changes of the terrain. *HFTA* isn't designed to do canyons.

To get a true 3-D picture of the full effects of terrain, a terrain model would have to show azimuth, along with range and elevation, point-by-point for about two miles in every direction around the base of the tower. After you go through the pain of creating a profile for a single azimuth, you'll appreciate the immensity of the process if you were you try to create a full 360° 3D profile manually.

Terrain Data from the Internet

At one time digitized terrain data commonly available from the Internet didn't have sufficient resolution to be accurate enough for *HFTA*. Nowadays, the complete, accurate set of USGS topographic 7.5-minute maps are available at no cost on the Internet. You can use a program called *MicroDEM*, written by Professor Peter Guth at the US Naval Academy, to quickly and easily produce terrain data files suitable for *HFTA* from topographic data files. Dr Guth and the US Naval Academy have graciously allowed ARRL to include the *MicroDEM* program on the CD-ROM accompanying this book. It should be noted that besides automatically creating terrain profiles for *HFTA*, *MicroDEM* is a full-featured mapping program on its own.

Instructions for using *MicroDEM* are in the Help file for *HFTA* (HFTA.PDF), which you can access from the *HFTA* main window by clicking on the **Help** button. **Fig 47** shows a screen capture of the *MicroDEM* program for the N6BV/1 location in New Hampshire for an azimuth of 45° into Europe. The black/white rendering of the screen capture doesn't do justice to the same information in color. The computed terrain profile is plotted in the window at the right of Fig 47 and the data file is shown in the inset window at the top right.

Using *MicroDEM* and on-line USGS topographic map data, you can also automatically create up to 360 terrain profiles with 1° spacing of azimuths in a few seconds. (Specifying a 1° spacing is really overkill; most operator choose to create 72 profiles with 5° spacing.) On a topographic DEM (digital elevation model) map that covers the geographic



Fig 46—A portion of USGS 7.5 minute topographic map, showing N6BV/1 QTH, together with marks in direction of Europe and Japan from tower base. Note that the elevations contours were marked by hand to help eliminate confusion. This required a magnifying glass and a steady hand!

area of interest, you simply specify the latitude and longitude of a tower's location—found using a GPS receiver—and then ask *MicroDEM* for a **Viewshed**. See the *HFTA* **Help** file for the details.

Compare this automated several-second *MicroDEM* process to creating manual profiles on a paper topographic map—It can take up to an hour of meticulous measurements to manually create a single terrain profile!

Algorithm for Ray-Tracing the Terrain

Once a terrain profile is created, there are a number of mechanisms that *HFTA* takes into account as a ray travels over that terrain:

1. Classical ray reflection, with Fresnel ground coefficients.
2. Direct diffraction, where a diffraction point is illuminated directly by an antenna, with no intervening terrain features blocking the direct illumination.
3. When a diffracted ray is subsequently reflected off the terrain.
4. When a reflected ray encounters a diffraction point and causes another series of diffracted rays to be generated.
5. When a diffracted ray hits another diffraction point, generating another whole series of diffractions.

Certain unusual, bowl-shaped terrain profiles, with sheer vertical faces, can conceivably cause signals to reflect or diffract in a backwards direction, only to be reflected back again in the forward direction by the sheer-walled terrain to the rear. *HFTA* does not accommodate these interactions, mainly because to do so would increase the computation time too much. It only evaluates terrain in the forward direction along one azimuth of interest.

Fig 48 shows a portion of an *HFTA* screen capture in the direction towards Europe from the N6BV/1 location in New Hampshire on 21.2 MHz. It compares the results for a 90/60/30-foot stack of TH7DX tribanders to the same stack over flat land, and to a single antenna at 70 feet over flat ground. The 70-foot single antenna represents a pretty typical station on 15 meters. The terrain produces excellent gain at lower elevation angles compared to the same stack over flat ground. The stack is very close to or superior to the single 70-foot high Yagi at all useful elevation angles. Terrain can indeed exhibit a profound effect on the launch of signals into the ionosphere—for good or for bad.

HFTA's Internal Antenna Model

The operator selects the antenna used inside *HFTA* to be anything from a dipole to an 8-element Yagi. The default assumes a simple cosine-squared mathematic response, equivalent to a 4-element Yagi in free space. *HFTA* traces rays only in the forward direction from the tower along the azimuth of interest. This keeps the algorithms reasonably simple and saves computing time.

HFTA considers each antenna in a stack as a separate *point source*. The simulation begins to fall apart if a traveling wave type of antenna like a rhombic is used, particularly if the terrain changes under the antenna—that is, the ground is not flat under the entire antenna. For a typical Yagi, even a long-boom one, the point-source assumption is reasonable. The internal antenna model also assumes that the Yagi is horizontally polarized. *HFTA* does not do vertically polarized antennas, as discussed previously. The documentation for *HFTA* also cautions the user to work with practical spacings between stacked Yagis—0.5 λ or more



```
      0.0000       129.0667
      0.0300       127.6407
      0.0600       126.2436
      0.0900       124.4495
      0.1200       123.3463
      0.1500       121.3171
      0.1800       119.1279
      0.2100       117.0958
      0.2400       114.3074
      0.2700       112.5209
      0.3000       110.0138
      0.3300       105.5836
      0.3600       102.0239
      0.3900       101.3096
      0.4200       101.2728
```

N 42°50'31.32" W 71°18'40.38" WGS84 z=420.2 ft

Fig 47—A screen-capture of the *MicroDEM* program, showing the topographic map for the same terrain shown in Fig 46, together with the computed terrain profile along an azimuth of 45° on the path towards Europe from the N6BV/1 location in Windham, NH.



Fig 48—The 21-MHz elevation response for a stack of three TH7DX Yagis mounted on a single tower at 90/60/30 feet, at the N6BV/1 QTH for a 45° azimuth towards Europe. The terrain focuses the energy at low elevation angles compared to the same stack over flat ground. This illustrates once again the conservation of energy—Energy squeezed down into low elevation angles is stolen from other, higher, angles.

because *HFTA* doesn't explicitly model mutual coupling between Yagis in a stack.

HFTA compares well with the measurements for the horizontal antennas described earlier by Jim Breakall, WA3FET, using a helicopter in Utah. Breakall's measurements were done with a 15-foot high horizontal dipole.

More Details About *HFTA*

Frequency Coverage

HFTA can be used on frequencies higher than the HF bands, although the graphical resolution is only 0.25°. The patterns above about 100 MHz thus look rather grainy. The UTD is a *high-frequency-asymptotic* solution, so in theory the results become more realistic as the frequency is raised. Keep in mind too that *HFTA* is designed to model launch angles for skywave propagation modes, including E- and F-layer, and even Sporadic-E. Since by definition the ionospheric launch angles include only those above the horizon, direct line-of-sight UHF modes involving negative launch angles are not considered in *HFTA*.

See the HFTA.PDF documentation file for further details on the operation of *HFTA*. This file, as well as sample terrain profiles for some *big-gun* stations, is located on the CD-ROM accompanying this book.

BIBLIOGRAPHY

Source material and more extended discussion of the topics covered in this chapter can be found in the references listed below and in the textbooks listed at the end of Chapter 2, Antenna Fundamentals.

B. Boothe, "The Minooka Special," *QST*, Dec 1974.

Brown, Lewis and Epstein, "Ground Systems as a Factor in Antenna Efficiency," *Proc. IRE* , Jun 1937.

G. Brown, "The Phase And Magnitude Of Earth Currents Near Radio Transmitting Antennas," *Proc. IRE*, Feb 1935, pp 168-182.

R. Collin and F. Zucker, *Antenna Theory*, Chap 23 by J. Wait, Inter-University Electronics Series (New York: McGraw-Hill, 1969), Vol 7, pp 414-424.

T. Hullick, W9QQ, "A Two-Element Vertical Parasitic Array For 75 Meters," *QST*, Dec 1995, pp 38-41.

R. Jones, "A 7-MHz Vertical Parasitic Array," *QST*, Nov 1973.

T. Larsen, "The E-Field and H-Field Losses Around Antennas With a Radial Ground Wire System," *Journal of Research of the National Bureau of Standards*, D. Radio Propagation, Vol 66D, No. 2, Mar-Apr 1962, pp 189-204.

D. A. McNamara, C. W. I. Pistorius, J. A. G. Malherbe, *Introduction to the Geometrical Theory of Diffraction* (Norwood, MA: Artech House, 1994).

C. J. Michaels, "Some Reflections on Vertical Antennas," *QST*, Jul 1987.

C. J. Michaels, "Horizontal Antennas and the Compound Reflection Coefficient," *The ARRL Antenna Compendium, Vol 3* (Newington: ARRL, 1992).

R. Severns, N6LF, "Verticals, Ground Systems and Some History," *QST*, Jul 2000, pp 38-44.

J. Sevick, "The Ground-Image Vertical Antenna," *QST*, Jul 1971.

J. Sevick, "The W2FMI 20-Meter Vertical Beam," *QST*, Jun 1972.

J. Sevick, "The W2FMI Ground-Mounted Short Vertical," *QST*, Mar 1973.

J. Sevick, "A High Performance 20-, 40- and 80-Meter Vertical System," *QST*, Dec 1973.

J. Sevick, "The Constant-Impedance Trap Vertical," *QST*, Mar 1974.

J. Stanley, "Optimum Ground Systems for Vertical Antennas," *QST*, Dec 1976.

F. E. Terman, *Radio Engineers' Handbook*, 1st ed. (New York, London: McGraw-Hill Book Co, 1943).

Radio Broadcast Ground Systems, available from Smith Electronics, Inc, 8200 Snowville Rd, Cleveland, OH 44141.

The last major study that appeared in the Amateur literature on the subject of local terrain as it affects DX appeared in four *QST* "How's DX" columns, by Clarke Greene, K1JX, from October 1980 to January 1981. Greene's work was an update of a landmark Sep 1966 *QST* article entitled "Station Design for DX," by Paul Rockwell, W3AFM. The long-range profiles of several prominent, indeed legendary, stations in Rockwell's article are fascinating: W3CRA, W4KFC and W6AM.

Chapter 4

Antenna Modeling & System Planning

OVERVIEW: ANTENNA ANALYSIS BY COMPUTER

As pointed out in Chapter 3, The Effects of Ground, irregular local terrain can have a profound effect on the launch of HF signals into the ionosphere. A *system approach* is needed to create a scientifically planned station. We pointed out in Chapter 3 that antenna modeling programs do not generally take into account the effects of irregular terrain, and by "irregular" we mean any sort of ground that is not flat. Most modeling programs based on *NEC-2* or *MININEC* do model reflections, but they do not model diffractions.

On the other hand, while a ray-tracing program like *HFTA* (HF Terrain Assessment) does take into account diffraction, it doesn't explicitly factor in the mutual impedance between an antenna and the ground. Instead, *HFTA* makes the basic assumption that the antenna is mounted sufficiently high above ground so that the mutual impedance between an antenna and the ground is minimal.

In this chapter we'll look at modeling the antennas themselves on the PC. We'll evaluate some typical antennas over flat ground and also in free space. Once characterized—or even optimized for certain characteristics—these antennas can then be analyzed over real terrain using *HFTA* and the other tools discussed in Chapter 3.

A Short History of Antenna Modeling

With the proliferation of personal computers since the early 1980s, amateurs and professionals alike have made significant strides in computerized antenna system analysis. It is now possible for the amateur with a relatively inexpensive computer to evaluate even complicated antenna systems. Amateurs can obtain a keener grasp of the operation of antenna systems—a subject that has been a great mystery to many in the past. We might add that modern computing tools allow hams to debunk overblown claims made about certain antennas.

The most commonly encountered programs for antenna analysis are those derived from a program developed at US government laboratories called *NEC*, short for "Numerical Electromagnetics Code." *NEC* uses a so-called *Method of Moments* algorithm. This intriguing name derives from a mathematical convention dealing with how "momentous" the accumulated error becomes when certain simplifying assumptions are made about the current distribution along an antenna wire. If you want to delve into details about the method of moments, John Kraus, W8JK, has an excellent chapter in his book *Antennas*, 2nd edition. See also the article "Programs for Antenna Analysis by the Method of Moments," by Bob Haviland, W4MB, in *The ARRL Antenna Compendium, Vol 4*.

The mathematics behind the method-of-moments algorithm are pretty formidable, but the basic principle is simple. An antenna is broken down into a number of straight-line wire *segments*, and the field resulting from the RF current in each segment is evaluated by itself and also with respect to other mutually coupled segments. Finally, the field from each contributing segment is vector-summed to yield the total field, which can be computed for any elevation or azimuth angle desired. The effects of flat-earth ground reflections, including the effect of ground conductivity and dielectric constant, may be evaluated as well.

In the early 1980s, *MININEC* was written in BASIC for use on personal computers. Because of limitations in memory and speed typical of personal computers of the time, several simplifying assumptions were necessary in *MININEC* and these limited potential accuracy. Perhaps the most significant limitation was that perfect ground was assumed to be directly under the antenna, even though the radiation pattern in the far field did take into account real ground parameters. This meant that antennas modeled closer than approximately 0.2 λ over ground sometimes gave erroneous impedances and inflated gains, especially for horizontal polarization. Despite some limitations, *MININEC* represented a remarkable leap forward in analytical capability. See Roy Lewallen's (W7EL) "*MININEC*—the Other Edge of the Sword" in Feb 1991 *QST* for an excellent treatment on pitfalls when using *MININEC*.

Because source code was made available when *MININEC* was released to the public, a number of programmers produced some very capable commercial versions for the amateur market, many incorporating exciting graphics showing antenna patterns in 2D or 3D. These programs also simplify the creation of models for popular antenna types, and several come with libraries of sample antennas.

By the end of the 1980s, the speed and capabilities

Commercial Implementations of *MININEC* and *NEC-2* Programs

Ever since the source code for *NEC-2* and *MININEC* came into in the public domain, enterprising programmers have been upgrading, extending and improving these programs. There are a number of "freeware" versions available nowadays, and there are also a variety of commercial implementations.

This sidebar deals only with the most popular commercial versions, programs that many hams use. You should keep in mind that whatever program you choose will require an investment in learning time, if not in dollars. Your time is valuable, of course, and so is the ability to swap modeling files you create with other modelers. Other peoples' modeling files, particularly when you are just starting out, are a great way to learn how the "experts" do their modeling. For example, there are archives of *EZNEC/ELNEC* files available on the Internet, since this popular modeling program has been around for a number of years. (*ELNEC* is the DOS-only, *MININEC*-core predecessor of EZNEC.)

The following table summarizes the main features and the pricing as of 2006 for some popular commercial antenna modeling programs. The programs that use the *NEC-4* core require separate licenses from Lawrence Livermore National Laboratories.

Commercial Implementations of *MININEC* and *NEC 2* programs

Name	***EZNEC 4.0 (+ ver.)***	***EZNEC-M Pro***	***EZNEC/4***	***NEC-Win Plus +***	***NEC-Win Pro***	***GNEC***	***Antenna Model***
Manufacturer	Roy Lewallen	Roy Lewallen	Roy Lewallen	Nittany Scientific	Nittany Scientific	Nittany Scientific	Teri Software
Core	*NEC-2*	*NEC-2*	*NEC-4*	*NEC-2*	*NEC-2*	*NEC-2/NEC-4*	*MININEC*
Operating System	Windows 32-bit	Windows 32-bit	Windows 32-bit	Windows 32-bit	Windows 32-bit	Windows 32-bit	Windows 32-bit
Number Segments	500 (1500, + ver.)	20,000	20,000	10,000	10,000	80,000	Limited by memory
NEC-Card Inputs	No	Yes	Yes	Yes	Yes	Yes	No
Other Input	ASCII (NEC, + ver.)	ASCII, NEC	ASCII, NEC	CAD *.DXF	CAD *.DXF	CAD *.DXF	No
Wires by Equation	No	No	No	Yes	Yes	Yes	Yes
Source Setting	By %	By %	By %	By %	By %	By %	By %
Source Type	Current/ Voltage/Split	Current/ Voltage/Split	Current /Voltage/Split	Current/ Voltage/Split	All types	All types	Current/Voltage
R + *j* X Loads	Yes	Yes	Yes	Yes	Yes	Yes	Yes
RLC Loads	Series, Parallel, Trap	Series, Parallel, Trap	Series, Parallel, Trap	Series, Parallel	Series, Parallel	Series, Parallel	Series, Parallel
True Trap Loads	Yes	Yes	Yes	No	No	No	No
Laplace Loads	Yes	Yes	Yes	Yes	Yes	Yes	No
Conductivity Table	Yes *	Yes *	Yes *	Yes	Yes	Yes	Yes
Average Gain Test	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Transmission Lines	Yes	Yes	Yes	Yes	Yes	Yes	No
View Geometry	Excellent	Excellent	Excellent	Good	Good	Good	Very Good
Geometry Checking	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Easy Height Change	Yes	Yes	Yes	No	No	No	No
Polar Plots	ARRL, linear-dB Az/El, Circ. (+ ver.)	ARRL, linear-dB Az/El, Circ.	ARRL, linear-dB Az/El, Circ.	ARRL, linear-dB Az/El Patterns	ARRL, linear-dB Az/El Patterns	ARRL, linear-dB Az/El Patterns	ARRL, Linear -dB Az/El Patterns
Rectangular Plots	SWR	SWR	SWR	SWR, Zin	SWR, Zin, Az/El, Near/Far Plots, Currents	SWR, Zin, Az/El, Near/Far Plots, Currents	Gain, SWR, F/B, F/R, Rin, Xin
Operating Speed	Fast	Fast	Fast	Very Fast	Very Fast	Very Fast	Slow
Smith Chart	Data for Ext. Smith program	Data for Ext. Smith program	Data for Ext. Smithprogram	No	Yes	Yes	Yes
Near/Far Field Tables	Both	Both	Both	Far	Both	Both	Both
Ground Wave Analysis	No	Yes	Yes	No	Yes	Yes	No
Pricing	$89 Web; $99 CD-ROM, $139 (+ ver.)	$450	$600; must have *NEC-4* license	$150	$425	$795	$85

* Wire conductivity is the same for all wires.

Excellent, Very Good, Good ratings done by *Antenna Book* editor.

of personal computers had advanced to the point where PC versions of *NEC* became practical, and several versions are now available to amateurs. The most recent public-domain version is *NEC-2* and this is the computational core that we'll use as an example throughout this chapter.

Like *MININEC*, *NEC-2* is a general-purpose modeling package and it can be difficult to use and relatively slow in operation for certain specialized antenna forms. Thus, custom commercial software has been created for more user-friendly and speedier analysis of specific antenna varieties, mainly Yagi arrays. See Chapter 11, HF Yagi Arrays. Also see the sidebar, "Commercial Implementations of *MININEC* and *NEC-2* Programs."

For this edition of *The ARRL Antenna Book*, Roy Lewallen, W7EL, has graciously provided a special version of his *EZNEC 3.0* program, called *EZNEC-ARRL*. This version works with the specific antenna models also bundled on the CD-ROM. Please note that this ARRL-specific version of *EZNEC* is limited to a maximum of 20 segments (we'll explain segments later) for all models except for the special ones included on this CD-ROM. You can find information on how to purchase the full-fledged version of *EZNEC* in the **Help** section of the *EZNEC-ARRL* program.

The following material on antenna modeling is by necessity a summary, since entire books have been written on this subject. Serious modelers would be well-advised to enroll in the online Antenna Modeling course, part of the ARRL Certification and Continuing Education series. L. B. Cebik, W4RNL created the ARRL Antenna Modeling course and it contains a great deal of information, tips and techniques concerning modeling by computer. See: **http://www.arrl.org/news/stories/2002/02/06/2/** for more information. We also strongly recommend that you read the Help files in *EZNEC-ARRL*. There is a wealth of practical information on the finer points of antenna modeling there.

THE BASICS OF ANTENNA MODELING

This chapter will discuss the following antenna-modeling topics for an *NEC-2*-based modeling software, using *EZNEC-ARRL* as an example:

- Program outputs
- Wire geometry
- Segmentation, warnings and limitations
- Source (feed point) placement
- Environment, including ground types and frequency
- Loads and transmission lines
- Testing the adequacy of a model

PROGRAM OUTPUTS

Instruction manuals for software programs traditionally start out describing in detail the input data needed by the program. They then demonstrate the output data the program can generate. We feel it is instructive, however, to turn things around and start out with a brief overview of the output from a typical antenna-modeling program.

We'll look at the output from public-domain *NEC-2*. Next, we'll look at the output information available from commercial adaptations of *NEC-2*, using *EZNEC-ARRL* provided by W7EL. After this brief overview of the output data, we'll look in detail at the input data needed to make a modeling program work. In the following discussions it will be very instructive if you to bring up *EZNEC-ARRL* on your computer and open the specific modeling files used in each example. [From now on in this chapter we'll refer merely to *EZNEC* rather than *EZNEC 3.0*, the official name or *EZNEC-ARRL*, a specialized subset of *EZNEC 3.0*. Where there are specific differences between *EZNEC 3.0* and the limited-edition *EZNEC-ARRL* we'll identify them.]

Native *NEC-2*

The native *NEC-2* program produces pages and pages of output formatted for a mainframe "line printer." You may be old enough to remember the stacks of green-and-white, tractor-feed, 132-column computer paper that such a line printer produced. Corporate MIS departments stored untold number of boxes of that paper.

Native *NEC-2* was written in the Fortran language, which stands for *Formula Translation*. Programmers used punched cards to enter the program itself and its accompanying input data into huge mainframe computers. To say that the paper output from *NEC-2* is massive, even intimidating, is putting it mildly. There is a strong distinction between "useful information" and "raw data" and the raw output from native *NEC-2* bombards the user with raw data.

Commercial versions that use the *NEC-2* computational core shield the user from the ugliness of raw line-printer output, as well as punched-card input (or disk surrogates for punched cards). Commercial versions like *EZNEC* do produce output numerical tables where this is useful. These tables show parameters such as the source impedance and SWR at a single frequency, or the characteristics of a load or a transmission line. But as the old saying goes, "One picture is worth a thousand words." This is as true for modeling programs as it is for other endeavors dealing with reams of numbers. Thus, most commercial modeling software packages create *graphs* for the user. *EZNEC* produces the following types of graphs:

- Polar (linear-dB or ARRL-style) graphs of the far-field elevation and azimuth responses.
- 3-D wire-frame graph of the total far-field response.
- Graph of the SWR across a frequency band.
- Graphical display of the RF currents on various conductors in a model.
- Rotatable, zoomable 3-D views of the wires used to make a model.
- Output to programs capable of generating Smith charts.

Fig 1A and 1B shows the computed far-field 2-D elevation and azimuth patterns for a 135-foot long horizontal dipole, mounted in a flattop configuration 50 feet above flat ground. These figures were generated using *EZNEC* at 3.75 MHz. Fig 1C shows a 3-D wire-frame picture of the far-field response, but this time at 14.2 MHz. For comparison, **Table 1** shows a short portion of the line-printer output for the azimuth pattern at 3.75 MHz. The actual printout is many pages long. One picture can indeed replace thousands of numbers!

Fig 2 shows the computed SWR curve over the frequency range 3.0 to 4.0 MHz for this dipole, fed with lossless 50-Ω transmission line. *EZNEC* generated this plot using the "SWR" button. Figs 1 and 2 are typical of the kind of graphical outputs that commercial implementations of the *NEC-2* computing core can produce.

Now, let's get into the details of what kind of input data is required to run a typical method-of-moments antenna-modeling program.

PROGRAM INPUTS: WIRE GEOMETRY

Coordinates in an X, Y and Z World

The most difficult part of using a *NEC*-type of modeling program is setting up the antenna's geometry—you must condition yourself to think in three-dimensional, Cartesian coordinates. Each end point of a wire is represented by three numbers: an x, y and z coordinate. These coordinates represent the distance from the origin (x-axis), the width of an antenna (y-axis), and the height (z-axis).

An example should help sort things out. **Fig 3** shows a simple model of a 135-foot center-fed dipole, made of #14 copper wire placed 50 feet above flat ground. The common term for this antenna is *flattop dipole*. For convenience, the ground is located at the *origin* of the coordinate system, at (0, 0, 0) feet, directly under the center of the dipole. **Fig 4** shows the *EZNEC* spreadsheet-like input data for this antenna. (Use model file: **Ch4-Flattop Dipole.EZ**.) *EZNEC* allows you to specify the type of conductor material from its main window, using the **Wire Loss** button to open a new window. We will click on the **Copper** button for this dipole.

Above the origin, at a height of 50 feet on the z-axis, is the dipole's *feed point*, called a *source* in *NEC* terminology. The width of the dipole goes toward the left (that is, in the "negative-y" direction) one-half the overall length of 135 feet, or –67.5 feet. Toward the right, our dipole's other end is at +67.5 feet. The x-axis dimension of our dipole is zero, meaning that the dipole wire is parallel to and directly above the x-axis. The dipole's ends are thus represented by two points, whose coordinates are (0, –67.5, 50) and (0, 67.5, 50) feet. The use of parentheses with a sequential listing of (x, y, z) coordinates is a common practice among antenna modelers to describe a wire end point.

Fig 3B includes some other useful information about this antenna beyond the wire geometry. Fig 3B overlays the wire geometry, the current distribution along the wire and the far-field azimuth response, in this case at an elevation angle of 30°.

Although not shown specifically in Fig 3, the thickness of the antenna is the diameter of the wire, #14 gauge. Note that native *NEC* programs specify the *radius* of the



Fig 1—At A, far-field elevation-plane pattern for a 135-foot-long horizontal dipole, 50 feet above flat ground, at 3.5 MHz. At B, the far-field azimuth-plane pattern at an elevation angle of 30°.



Fig 2—SWR curve for 135-foot flattop dipole over the frequency range 3.0 to 4.0 MHz for a 50-Ω feed line. This antenna is an example and is not optimized for the amateur band.

wire, rather than the diameter, but programs like *EZNEC* use the more intuitive diameter of a wire rather than the radius. *EZNEC* (and other commercial programs) also allows the user to specify the wire as an AWG gauge, such as #14 or #22, for example.

We've represented our simple dipole in Fig 3 using a single, straight wire. In fact, all antenna models created for method-of-moment programs are made of combinations of straight wires. This includes even complex antennas, such as helical antennas or round loops. (The mathematical basis for modeling complex antennas is that they can be simulated using straight-wire *polygons*. A circular loop, for example, can be modeled using an octagon.)

Segmentation and Specifying a Source Segment

We've specified the physical geometry of this simple one-wire dipole. Now several more modeling details surface—you must specify the number of *segments* into which the dipole is divided for the method-of-moment analysis and you must somehow feed the antenna. The *NEC-2* guideline for setting the number of segments is to use at least 10 segments per half-wavelength. This is a general rule of thumb, however, and in many models more dense segmentation is mandatory for good accuracy.

In Fig 3, we've specified that the dipole be divided into 11 segments for operation on the 80-meter band. This follows the rule of thumb above, since the 135-foot dipole is about a half-wavelength long at 3.5 MHz.

Setting the Source Segment

The use of 11 segments, an odd rather than an even number such as 10, places the dipole's feed point (the

Table 1
Portion of line-printer output from *NEC-2* for 135-foot dipole.

```
                                 - - - RADIATION PATTERNS - - -

 - - ANGLES - -     - POWER GAINS -    - - - POLARIZATION - - -      - - - E(THETA) - - -        - - - E(PHI) - - -

Theta    Phi        Vert    Hor   Total  Axial      Tilt    Sense    Magnitude      Phase     Magnitude      Phase
Degrees  Degrees    dB      dB    dB     Ratio      Degrees          Volts          Degrees   Volts          Degrees
60.00     0.00    –999.99   3.14  3.14  0.00000    90.00   LINEAR   0.00000E+00     0.00    6.62073E-01  –66.87
60.00     1.00     –37.87   3.13  3.14  0.00301    89.52   LEFT     5.89772E-03   –86.64    6.61933E-01  –66.87
60.00     2.00     –31.85   3.13  3.13  0.00603    89.04   LEFT     1.17915E-02   –86.64    6.61512E-01  –66.87
60.00     3.00     –28.33   3.12  3.12  0.00904    88.56   LEFT     1.76776E-02   –86.64    6.60812E-01  –66.87
60.00     4.00     –25.84   3.11  3.11  0.01206    88.08   LEFT     2.35520E-02   –86.64    6.59834E-01  –66.87
60.00     5.00     –23.91   3.09  3.10  0.01508    87.59   LEFT     2.94109E-02   –86.64    6.58577E-01  –66.87
60.00     6.00     –22.34   3.07  3.08  0.01810    87.11   LEFT     3.52504E-02   –86.64    6.57045E-01  –66.87
60.00     7.00     –21.01   3.05  3.06  0.02112    86.62   LEFT     4.10669E-02   –86.63    6.55237E-01  –66.87
60.00     8.00     –19.87   3.02  3.04  0.02415    86.14   LEFT     4.68565E-02   –86.63    6.53158E-01  –66.87
60.00     9.00     –18.86   2.99  3.02  0.02718    85.65   LEFT     5.26156E-02   –86.63    6.50808E-01  –66.87
60.00    10.00     –17.96   2.95  2.99  0.03022    85.15   LEFT     5.83405E-02   –86.63    6.48190E-01  –66.87
60.00    11.00     –17.15   2.91  2.96  0.03327    84.66   LEFT     6.40278E-02   –86.63    6.45308E-01  –66.86
60.00    12.00     –16.42   2.87  2.92  0.03631    84.16   LEFT     6.96739E-02   –86.63    6.42165E-01  –66.86
60.00    13.00     –15.75   2.83  2.89  0.03937    83.66   LEFT     7.52755E-02   –86.63    6.38764E-01  –66.86
60.00    14.00     –15.13   2.78  2.85  0.04243    83.16   LEFT     8.08291E-02   –86.63    6.35108E-01  –66.86
60.00    15.00     –14.56   2.72  2.80  0.04550    82.65   LEFT     8.63317E-02   –86.62    6.31203E-01  –66.86
60.00    16.00     –14.03   2.66  2.76  0.04858    82.14   LEFT     9.17800E-02   –86.62    6.27051E-01  –66.86
60.00    17.00     –13.53   2.60  2.71  0.05166    81.62   LEFT     9.71711E-02   –86.62    6.22657E-01  –66.85
60.00    18.00     –13.07   2.54  2.66  0.05475    81.10   LEFT     1.02502E-01   –86.62    6.18027E-01  –66.85
```



Fig 3—At A, simple model for a 135-foot long horizontal dipole, 50 feet above the ground. The dipole is over the y-axis. The wire has been segmented into 11 segments, with the center of segment number 6 as the feed point. The left-hand end of the antenna is -67.5 feet from the center feed point and that the right-hand end is at 67.5 feet from the center. At B, *EZNEC* "View Antenna" drawing, showing geometry of wire and the x, y and z axes. Overlaid on the wire geometry drawing are the current distribution along the wire and the far-field azimuthal response at an elevation angle of 30°.

source in *NEC*-speak, a word choice that can befuddle beginners) right at the antenna's center, at the center of segment number six. In concert with the "EZ" in its name, *EZNEC* makes choosing the source segment easy by allowing the user to specify a percentage along the wire, in this case 50% for center feeding.

At this point you may very well be wondering why no center insulator is shown in the middle of our center-fed dipole. After all, a real dipole would have a center insulator. However, method-of-moment programs assume that a source generator is placed across an infinitely small gap in the antenna wire. While this is convenient from a mathematical point of view, the unstated use of such an infinitely small gap often confuses newcomers to the world of antenna modeling. We'll get into more details, caveats and limitations in source placement later in this chapter. For now, just trust us that the model we've just described with 11 segments, fed at segment 6, will work well over the full amateur band from 3.5 to 4.0 MHz.



☐ Coord Entry Mode ☐ Preserve Connections

Wires

	No.	End 1				End 2				Diameter	Segs
		X (ft)	Y (ft)	Z (ft)	Conn	X (ft)	Y (ft)	Z (ft)	Conn	(in)	
	1	0	-67.5	50		0	67.5	50		#14	83
*											

Fig 4—*EZNEC* "Wires" spreadsheet for simple flattop dipole in Fig 3. The numbers shown are in feet, except for the wire diameter, which *EZNEC* allows you to specify as an AWG gauge, in this case #14. Note that 83 segments have been specified for this antenna for analysis over the range from 3.5 to 29.7 MHz.

Now, let's consider what would happen if we want to use our 135-foot long dipole on all HF amateur bands from 3.5 to 29.7 MHz, rather than just from 3.5 to 4.0 MHz. Instead of feeding such an antenna with coax cable, we would feed it with open-wire line and use an antenna tuner in the shack to create a 50-Ω load for the transmitter. To comply with the segmentation rule above, the number of segments used in the model should vary with frequency—or at least be segmented at or above the minimum recommended level at the highest frequency used. This is because a half wavelength at 29.7 MHz is 16.6 feet, while a half wavelength at 3.5 MHz is 140.6 feet. So the number of segments for proper operation on 29.7 MHz should be 10 × 135/16.6 = 81. We'll be a little more conservative than the minimum requirement and specify 83 segments. **Fig 4** shows the *EZNEC* input spreadsheet for this model. (Use model file: **Ch4-Multiband Dipole.EZ**.)

The penalty for using more segments in a program like *NEC* is that the program slows down roughly as the square of the segments—double the number of segments and the speed drops to a fourth. If we try to use too few segments, we'll introduce inaccuracies, particularly in computing the feed-point impedance. We'll delve into this area of segmentation density in more detail later when we discuss testing the adequacy of a model.

Segment Length-to-Wire-Diameter Ratio

Even if you're willing to live with the slowdown in computing speed for situations involving a large number of wire segments, you should make sure the ratio between the segment length and the diameter of any wire is greater than 1:1. This is to say that the length of each segment is longer than the diameter of the wire. Doing so stays away from internal limitations in the *NEC* program.

For the #14 wire specified in this simple 135-foot long dipole, it's pretty unlikely that you'll bump up against this limitation for any reasonable level of segmentation. After all, #14 wire has a diameter of 0.064 inches and 135 feet is 1620 inches. To keep above a segment length of 0.064 inches, the maximum number of segments is 1620/

0.064 = 25,312. This is a *very* large number of segments and it would take a very long time to compute, assuming that your program can handle that many segments.

Keeping above a 1:1 ratio in segment length to wire diameter can be more challenging at VHF/UHF frequencies, however. This is particularly true for fairly large "wires" made of aluminum tubing. Incidentally, this is another point where newcomers to antenna modeling can be led astray by the terminology. In a *NEC*-type program, all conductors in a model are considered to be *wires*, even if they consist of hollow aluminum or copper tubes. Surface effect keeps the RF current in any conductor confined to the outer surface of that conductor, and thus it doesn't matter whether the conductor is hollow or solid, or even made using a number of stranded wires twisted together.

Let's look at a half-wave dipole at 420 MHz. This would be about 14.1 inches long. If you use $^1/_4$-inch diameter tubing for this dipole, the maximum segment length meeting the 1:1 diameter-to-length ratio requirement is also $^1/_4$ inches long. The maximum number of segments then would be 14.1/0.25 = 56.4, rounded down to 56. From this discussion you should now understand why method-of-moment programs are known for using a "thin-wire approximation." Really fat conductors can get you into trouble, particularly at VHF/UHF.

Some Caveats and Limitations Concerning Geometry

Example: Inverted-V Dipole

Now, let's get a little more complicated and specify another 135-foot-long dipole, but this time configured as an *inverted V*. As shown in **Fig 5**, you must now specify two wires. The two wires join at the top, at (0, 0, 50) feet. (Again, the program doesn't use a center insulator in the model.)

If you are using a native version of *NEC*, you may have to go back to your high-school trigonometry book to figure out how to specify the end points of our "droopy" dipole, with its 120° included angle. Fig 5 shows the details, along with the trigonometric equations needed. *EZNEC* is indeed more "easy" here, since it allows you to tilt the ends of each wire downwards an appropriate number of degrees (in this case –30° at each end of the dipole) to automatically create an inverted-V configuration. **Fig 6A** shows the *EZNEC* spreadsheet describing this inverted-V dipole with a 120° included angle between the two wires.


Z
67.5′ Long
67.5′ Long
(0, 67.5×Sin60°, 50 – 67.5×Cos60°)
120°
(0, –67.5×Sin60°, 50 – 67.5×Cos60°)
Y
X
Sin = Opp/Hyp
Cos = Adj/Hyp

Fig 5—Model for an inverted-V dipole, with an included angle between the two legs of 120°. Sine and cosine functions are used to describe the heights of the end points for the sloping arms of the antenna.



☐ Coord Entry Mode ☐ Preserve Connections

	Wires									
No.	End 1				End 2				Diameter	Segs
	X (ft)	Y (ft)	Z (ft)	Conn	X (ft)	Y (ft)	Z (ft)	Conn	(in)	
1	0	-58.4567	16.25		0	0	50	W2E1	#14	41
2	0	0	50	W1E2	0	58.4567	16.25		#14	41

(A)



(B)

Fig 6—At A, *EZNEC* spreadsheet for inverted-V dipole in Fig 5. Now the ends of the inverted-V dipole are 16.25 feet above ground, instead of 50 feet for the flattop dipole. At B, *EZNEC* "View Antenna" drawing, with overlay of geometry, current distribution and azimuth plot.

See the *EZNEC* **Help** section under "Wire Coordinate Shortcuts" for specific instructions on how to use the "elevation rotate end" shortcut "RE–30" to create the sloping wires easily by rotating the end of the wire down 30°. Now the specification of the source becomes a bit more complicated. The easiest way is to specify two sources, one on each end segment at the junction of the two wires. *EZNEC* does this automatically if you specify a so-called *split-source* feed. Fig 6B shows the two sources as two open circles at the top ends of the two wires making up the inverted-V dipole. What *EZNEC* is doing is creating two sources, each on the closest segments on either side of the junction of the two wires. *EZNEC* sums up the two source impedances to provide a single readout.

Navigating in the View Antenna Window

At this point it's worthwhile to explore some of the ways you can see what the wire geometry looks like using the *EZNEC* **View Ant** button on the main window. Bring up the file **Ch4-Inverted V Dipole.EZ** in *EZNEC*, and click on the **View Ant** button. You will see a small inverted-V dipole raised over the (0, 0, 0) origin on the ground directly under the feed point of the inverted-V dipole. First, "rotate" the dipole by holding down the left-mouse button and moving the mouse. You can orient the picture any way you wish.

Let's take a closer look at the junction of the two wires at the feed point. Click the **Center Ant Image** checkbox toward the bottom of the window to anchor the center of the image at the center of the window, and then move the **Zoom** slider upwards to zoom in on the image. At some point the junction of the two slanted wires will move up off the edge of the window, so you will need to click on the left-hand side of the **Z Move Image** slider to bring the junction back into view. Now you should be able to see a zoomed view of the junction, along with the two open circles that represent the location of the split sources in the middle of the segments adjacent to the wire junction.

Now put the mouse cursor over one of the slanted wires and double click the left-mouse button. *EZNEC* will now identify that wire and show its length, as well as the length of each segment on that wire. Pretty slick, isn't it?

Short, Fat Wires and the Acute-Angle Junction

Another possible complication can arise for wires with short, fat segments, particularly ones that have only a small included angle between them. These wire segments can end up inter-penetrating within each other's volumes, leading to problems in a model. Once you think of each wire segment as a thick cylinder, you can appreciate the difficulty in connecting two wires together at their ends. The two wires always inter-penetrate each other's volume to some extent. **Fig 7** depicts this problem graphically for two short, fat wires joined at their ends at an acute angle. A rule of thumb is to avoid creating junctions where more than $^1/_3$ of the wire volumes inter-penetrate. You can achieve this by using longer segment lengths or thinner wire diameters.



Fig 7—A junction of two short, fat wire segments at an acute angle. This results in inter-penetration of the two wire volumes beyond the middle-1/3 recommended limit.

Some Other Practical Antenna Geometries

A Vertical Half-Wave Dipole

If you turn the 135-foot-long horizontal dipole in Fig 1 on its end you will create a vertical half-wave dipole that is above the origin of the x, y and z axes. See **Fig 8**, where the bottom end of the dipole is placed 8 feet off the ground to keep it away from humans and animals for safety, at (0, 0, 8) feet. The top end is thus at 8 + 135 = 143 feet off the ground at (0, 0, 143). Fig 8 also shows the current distribution and the elevation pattern for this antenna. (Use *EZNEC* model file: **Ch4-Vertical Dipole.EZ**.)



Fig 8—A vertical half-wave dipole, created by turning the dipole in Fig 3 on its end, with a minimum height at the lower end of 8 feet to keep the antenna away from people and animals. The current distribution and the elevation pattern for this antenna are also shown overlaid on the wire geometry.

A Ground-Plane Antenna

The ground-plane model is more complicated than previous ones because a total of five wires are now needed: one for the vertical radiator and four for the radials. **Fig 9** shows the *EZNEC* view for a 20-meter ground plane mounted 15 feet off the ground (perhaps on a garage roof), with the overlay of both the current distribution and the elevation-plane plot. (Use *EZNEC* model file: **Ch4-GP.EZ**.) Note that the source has been placed at the



Fig 9—A vertical ground-plane antenna. The radials and the bottom of the vertical radiator are located 15 feet off the ground in this model. The current distribution along each wire and the far-field elevation-plane pattern are overlaid on the antenna geometry.



Fig 10—*EZNEC* View Antenna for the ground-plane antenna with its four radials tilted downwards by 40° to improve the SWR at the feed point.

bottom segment of the vertical radiator. Once again, the program needs no bottom insulator, since all five wires are connected together at a common point. *EZNEC* reports that this antenna has a resonant feed-point impedance of about 22 Ω, which would show an SWR of 2.3:1 for a 50-Ω coax feed line if no matching system is used, such as a gamma or hairpin match.

Fig 10 shows the same antenna, except that the radials have now been tilted downwards by 35° to facilitate an almost perfect 50-Ω match (SWR = 1.08:1). In addition, the length of the radiator in this model was shortened by 6 inches to re-resonate the antenna. (Use *EZNEC* model file: **Ch4-Modified GP.EZ**.) The trick of tilting the radials downwards for a ground-plane antenna is an old one, and the modeling programs validates what hams have been doing for years.

A 5-Element Horizontal Yagi

This is a little more challenging modeling exercise. Let's use a 5-element design on a 40-foot boom, but rather than using telescoping aluminum tubing for the elements, we'll use #14 wire. The *SCALE* program included with this book on the CD-ROM converted the aluminum-tubing 520-40.YW to a design using #14 copper wire. **Table 2** shows the element lineup for this antenna. (Later in this chapter we'll see what happens when telescoping aluminum tubing is used in a real-world Yagi design.)

Some explanations of what Table 3 means are in order. First, only one half of each element is shown. The *YW* program (Yagi for Windows), also included on the CD-ROM, computes the other half of the Yagi automatically, essentially mirroring the other half on the opposite side of the boom. Having to enter the dimensions for only half of a real-world Yagi element that uses telescoping aluminum tubing is much easier this way.

Second, the placement of the elements along the boom starts at 0.0 inches for the reflector. The distance between adjacent elements defined in this particular file is the spacing between the element itself and the element just before it. For example, the spacing between the driven element and the reflector is 72 inches, and the spacing between the first director and the driven element is also 72 inches. The spacing between the second director and the first director is 139 inches.

Fig 11A shows the wire geometry for this Yagi array when it is mounted 720 inches (60 feet) above flat ground and Fig 11B shows the *EZNEC* Wires spreadsheet that describes the coordinates. (Use *EZNEC* model file: **Ch4-520-40W.EZ**.) You can see that the x-axis coordinates for the elements have been automatically moved by the *SCALE* program so that the center of the boom is located directly above the origin. This makes it easier to evaluate the effects of stacking different monoband Yagis on a rotating mast in a "Christmas Tree" arrangement. A typical Christmas Tree stack might include 20, 15 and 10-meter monobanders on a single rotating mast sticking out of the top of the tower.

Fig 12 shows the computed azimuth pattern for this Yagi at 14.175 MHz, at an elevation angle of 15°, the angle where the peak of the forward lobe occurs at this

Table 2

```
520-40W.YW, using #14 wire from 520-40H.YW
14.000  14.174  14.350 MHz
5 elements,    inches
Spacing           .064
0.000          210.923
72.000         200.941
72.000         199.600
139.000        197.502
191.000        190.536
```



(A)

	Wires									
No.	End 1				End 2				Diameter	Segs
	X (in)	Y (in)	Z (in)	Conn	X (in)	Y (in)	Z (in)	Conn	(in)	
1	-237.188	-210.923	720		-237.188	210.923	720		0.064	13
2	-165.188	-200.941	720		-165.188	200.941	720		0.064	13
3	-93.188	-199.6	720		-93.188	199.6	720		0.064	13
4	45.812	-197.502	720		45.812	197.502	720		0.064	13
5	236.812	-190.536	720		236.812	190.536	720		0.064	13

(B)

Fig 11—At A, geometry for 5-element Yagi on a 40-foot boom, mounted 720 inches (60 feet) above flat ground, with an overlay of current and the azimuth pattern. At B, *EZNEC* Wires spreadsheet for this antenna. This design uses #14 wire for simplicity.



Fig 12—*EZNEC* azimuth-plane pattern at an elevation angle of 15° for #14 wire Yagi described in Fig 11.

height above flat ground. The antenna exhibits excellent gain at 13.1 dBi, as well as a clean pattern behind the main lobe. The worst-case front-to-rear ratio at any point from 90° to 270° in azimuth is better than 23 dB. *EZNEC* says the feed-point impedance is 25 – *j* 23 Ω, just the right impedance suited for a simple hairpin or gamma match.

A Monoband 2-Element Cubical Quad

Unlike a Yagi, with its elements existing only in the x-y plane, a quad type of beam is a three-dimensional sort of antenna. A quad loop has height in the z-axis, as well as width and length in the x-y plane. Each individual loop for a monoband quad consists of four wires, joined together at the corners. **Fig 13** shows the coordinates for a 2-element 15-meter quad, consisting of a reflector and a driven element on a 10-foot boom.

You can see that the axis of symmetry, the x-axis, runs down the center of this model, meaning that the origin of this particular x, y and z-coordinate scheme is in the center of the reflector. The (0, 0, 0) origin is placed this way for convenience in assigning corner coordinates for each element. For actual placement of the antenna at a particular height above real ground, the heights of all z-axis coordinates are changed accordingly. *EZNEC* has a convenient built-in function to change the height of all wires at a single stroke.

Fig 14 shows the input *EZNEC* spreadsheet for this quad in free space, clearly showing the symmetrical nature of the corner coordinates. (Use *EZNEC* model file: **Ch4-Quad.EZ**.) This is a good place to emphasize that you should enter the wire coordinates in a logical



Fig 13—Wire geometry for a 2-element cubical quad, with a reflector and driven element. The x-axis is the axis of symmetry for this free-space model.



Wires

No.	End 1				End 2				Diameter	Segs
	X (ft)	Y (ft)	Z (ft)	Conn	X (ft)	Y (ft)	Z (ft)	Conn	(in)	
1	0	-6.083	-6.083	W4E2	0	6.083	-6.083	W2E1	#12	7
2	0	6.083	-6.083	W1E2	0	6.083	6.083	W3E1	#12	7
3	0	6.083	6.083	W2E2	0	-6.083	6.083	W4E1	#12	7
4	0	-6.083	6.083	W3E2	0	-6.083	-6.083	W1E1	#12	7
5	10	-5.917	-5.917	W8E2	10	5.917	-5.917	W6E1	#12	7
6	10	5.917	-5.917	W5E2	10	5.917	5.917	W7E1	#12	7
7	10	5.917	5.917	W6E2	10	-5.917	5.917	W8E1	#12	7
8	10	-5.917	5.917	W7E2	10	-5.917	-5.917	W5E1	#12	7

Fig 14—*EZNEC* Wires spreadsheet showing the coordinates used for the quad in Fig 13. Note how the x-axis describes the position of an element on the 10-foot boom and also is the axis of symmetry for each element. The values for the z-axis and y-axis vary above and below the axis of symmetry.

sequence. The most obvious example in this particular model is that you should group all the wires associated with a particular element together—for example, the four wires associated with the reflector should be in one place. In Fig 14 you can see that all four wires with an x-coordinate of zero represent the reflector.

It's best to follow a convention in entering wires in a loop structure in a logical fashion. The idea to connect the end point of one wire to the starting point of the next wire. For example, in Fig 13 you can see that the left-hand end of Wire 1 is connected to the bottom of Wire 2, and that the top of Wire 2 connects to the left-hand end of Wire 3. In turn, Wire 3 connects to the top of Wire 4, whose bottom end connects to the right-hand end of Wire 1. The pattern is known as "going around the horn" meaning that the connections proceed smoothly in one direction, in this case in a clockwise direction.

You can see that the entry for the wires making up the elements in the 5-element Yagi in Fig 11B also proceeded in an orderly fashion by starting with the reflector, then the driven element, then director 1, then director 2 and finally director 3. This doesn't mean that you couldn't mix things up, say by specifying the driven element first, followed by director 3, and then the reflector, or whatever. But it's a pretty good bet that doing so in this quasi-random fashion will result in some confusion later on when you revisit a model, or when you let another person see your model.

THE MODELING ENVIRONMENT

The Ground

Above, when considering the 135-foot dipole mounted 50 feet above flat earth, we briefly mentioned the most important environmental item in an antenna model—the ground beneath it. Let's examine some of the options available in the *NEC-2* environment in *EZNEC*:

- Free space
- Perfect ground
- *MININEC* type ground
- "Fast" type ground
- Sommerfeld-Norton ground.

The free space environment option is pretty self-explanatory—the antenna model is placed in free space away from the influence of any type of ground. This option is useful when you wish to optimize certain characteristics of a particular antenna design. For example, you might wish to optimize the front-to-rear ratio of a Yagi over an entire amateur band and this might entail many calculation runs. The free-space ground will run the fastest among all the ground options.

Perfect ground is useful as a reference case, especially for vertically polarized antennas over real ground. Antenna evaluations over perfect ground are shown in most classical antenna textbooks, so it is useful to compare models for simple antennas over perfect ground to those textbook cases.

MININEC type ground is useful when modeling vertical wires, or horizontal wires that are higher than 0.2 λ above ground. A *MININEC* type ground will compute faster than either a "Fast" ground or a Sommerfeld-Norton type of ground because it assumes that the ground under the antenna is perfect, while still taking into account the far-field reflections for ground using user-specified values of ground conductivity and dielectric constant. The fact that the ground under the antenna is perfect allows the *NEC-2* user of a *MININEC* type ground to specify wires that touch (but don't go below) the ground surface, something that only users of the advanced *NEC-4* program can do with the more accurate Sommerfeld-Norton type of ground described below. (*NEC-4* is presently not in the public domain and is strictly restricted and licensed by the US government.) The ability to model grounded wires is useful with vertical antennas. The modeler must be wary of the feed-point source impedances reported for either horizontally or vertically polarized wires because of the perfect-ground assumption inherent in a *MININEC*-type ground.

The "fast" type of ground is a hybrid type of ground that makes certain simplifying assumptions that allow it to be used provided that horizontal wires are higher than about 0.1 λ above ground. With today's fast computers the Sommerfeld-Norton model is preferred.

The Sommerfeld-Norton ground (referred to in *EZNEC* as the "high accuracy" ground) is preferable to the other ground types because it has essentially no practical limitations for wire height. It has the disadvantage that it can run about four times slower than a *MININEC* type of ground, but today's fast computers make that almost a non-issue. Again, *NEC-2*-based programs cannot model wires that penetrate into the ground (although there are work-arounds described below).

As mentioned above, for any type of ground other than perfect ground or free space, the user must specify the conductivity and dielectric constant of the soil. *EZNEC* allows the entry by several user-friendly categories, where σ is conductivity in Siemens/meter and ε is dielectric constant:

- Extremely poor: cities, high buildings (σ = 0.001, ε = 3)
- Very Poor: cities, industrial (σ = 0.001, ε = 5)
- Sandy, dry (σ = 0.002, ε = 10)
- Poor: rocky, mountainous (σ = 0.002, ε = 13)
- Average: pastoral, heavy clay (σ = 0.005, ε = 13)
- Pastoral: medium hills and forestation (σ = 0.006, ε = 13)
- Flat, marshy, densely wooded (σ = 0.0075, ε = 12)
- Pastoral, rich soil, US Midwest (σ = 0.010, ε = 14)
- Very Good: pastoral, rich, central US (σ = 0.0303, ε = 20)
- Fresh water (σ = 0.001, ε = 80)
- Saltwater (σ = 5, ε = 80)

Let's use *EZNEC*'s ability to overlay one or more plots together on one graph to compare the response of the vertical ground plane antenna in Fig 9 for two different types of ground: Saltwater and Poor. Open the **Ch4-GP.EZ** file in *EZNEC*. Click the **Ground Descrip** button and then right-click anywhere in the Media window that opens up. Choose first the "Poor: rocky, mountainous" option button, click **OK** and then **FF Plot**. When the elevation plot appears, click the **File** menu at the top of the main window, and then **Save As**. Choose an appropriate name for the trace, perhaps "Poor Gnd.PF."

Go back and select saltwater as your **Ground Descrip** and follow the same procedure to compute the far-field plot for saltwater ground. Now, add the Poor Gnd.PF trace, by clicking menu selection **File**, **Add Trace**. **Fig 15** shows this comparison, which greatly favors the saltwater environment, particularly at low elevation angles. At 5° the ground plane mounted over saltwater has about a 10 dB advantage compared to its landlocked cousin.

You might be wondering what happens if we move the ground-plane antenna down closer to the ground. The lower limit to how far the radials can approach the lossy earth is 0.001 λ or twice the diameter of the radial wire. A distance of 0.001 λ at 1.8 MHz is about 6 inches, while it is 0.4 inches at 30 MHz. While *NEC-2*-based programs cannot model wires that penetrate the ground, radial systems just above the ground with more than about eight radial wires can provide a work-around to simulate a direct-ground connection.

Modeling Environment: Frequency

It's always a good idea to evaluate an antenna over a *range of frequencies*, rather than simply at a single spot frequency. Trends that become quite apparent on a frequency sweep are frequently lost when looking simply at a single frequency. Native *NEC-2* has built-in frequency sweep capabilities, but once again the commercial programs make the process easier to use and understand. You saw in the SWR curve in Fig 2 the result of one such frequency sweep using *EZNEC*. **Fig 16** shows a frequency sweep of the azimuth response for the 5-element Yagi in Fig 11 across the 20-meter band, using steps of 117 kHz so there are four evaluation frequencies. At 14.0 MHz this Yagi's gain is down a small amount compared to the gain at 14.351 MHz but the rearward pattern is noticeably degraded, dropping to a front-to-back ratio of just under 20 dB.



Fig 15—A comparison of the elevation response for the vertical ground plane in Fig 9 over saltwater and over "poor: rocky, mountainous" soil. Saltwater works wonders for verticals, providing excellent low-angle signals.



Fig 16—Frequency sweep of 5-element Yagi described in Fig 11, showing how the azimuth pattern changes with frequency.

EZNEC can save to a series of output plot files a frequency sweep of elevation (or azimuth) patterns. In essence, this automates the process described above for saving a plot to disk and then overlaying it on another plot. *EZNEC* can save to a text file for later analysis (or perhaps importation into a spreadsheet) the following parameters, chosen by the user:

- Source data
- Load data
- Pattern data
- Current data
- MicroSmith numeric data
- Pattern analysis summary.

Frequency Scaling

EZNEC has a very useful feature that allows you to create new models *scaled* to a new frequency. You invoke the algorithm used to scale a model from one frequency to another by checking the **Rescale** box after you've clicked the **Frequency** button. *EZNEC* will scale all model dimensions (wire length, height and diameter) except for one specific situation—the wire diameter will stay the same at the new frequency if you originally specified wire size by AWG gauge. For example, #14 copper wire for a half-wave 80-meter dipole will stay #14 copper wire for a 20-meter half-wave dipole. If, however, you specified diameter as a floating point number originally, the diameter will be scaled by the ratio of new to old frequency, along with wire length and height.

Start up *EZNEC* and open up the file **Ch4-520-40W.EZ** for the 5-element 20-meter Yagi on a 40-foot boom. Click the **Frequency** box and then check the **Rescale** check box. Now, type in the frequency of 28.4 MHz and click **OK**. You have quickly and easily created a new 5-element 10-meter Yagi, that is mounted 29.9949 feet high, the exact ratio of 28.4 MHz to 14.1739 MHz, the original design frequency on 20 meters. Click the **FF Plot** button to plot the azimuth pattern for this new Yagi. You will see that it closely duplicates the performance of its 20-meter brother. Click **Src Dat** to see that the source impedance is 25.38 – *j* 22.19 Ω, again very close to the source data for the 20-meter version.

REVISITING SOURCE SPECIFICATION

Sensitivity to Source Placement

Earlier, we briefly described how to specify a source on a particular segment using *EZNEC*. The sources for the relatively simple dipole, Yagi and quad models investigated so far have been in the center of an easy-to-visualize wire. The placement for the source on the vertical ground plane was at the bottom of the vertical radiator, an eminently logical place. In the other cases we specified the position of the source at 50% of the distance along a wire, given that the wire being fed had an odd number of segments. Please note that in each case so far, the feed point (source) has been placed at a relatively low-impedance point, where the current changes relatively slowly from segment to segment.

Now we're going to examine some subtler source-placement problems. *NEC-2* is well-known as being very sensitive to source placement. Significant errors can result from a haphazard choice of the source segment and the segments surrounding it.

Let's return to the inverted-V dipole in Fig 5. The first time we evaluated this antenna (**Ch4-Inverted V Dipole.EZ**) we specified a split source in *EZNEC*. This function uses two sources, one on each of the segments immediately adjacent to the junction of the two downward slanting wires.

Another common method to create a source at the junction of two wires that meet at an angle is to separate these two slanted wires by a short distance and bridge that gap with a short straight wire, which is fed at its center. **Fig 17** shows a close-up of this scheme. In Fig 17 the length of the segments surrounding the short middle wire are purposely made equal to the length of the middle wire. The segmentation for the short middle wire is set to one. **Table 3** lists the source impedance and the maximum gain the *EZNEC* computes for three different models:

1. **Ch4-Inverted V Dipole.EZ** (the original model)
2. **Ch4-Inverted V Dipole Triple Segmentation.EZ**
3. **Ch4-Modified Inverted V Dipole.EZ** (as shown in Fig 17, for the middle wire set to be 2 feet long)
4. **Ch4-Mod Inverted V Poor Segmentation.EZ** (where the number of segments on the two slanted wires have been increased to 200)



Fig 17—Model of inverted-V dipole using a short center wire on which the source is placed.

Table 3
135-Foot Inverted-V Dipole at 3.75 MHz

Case	*Segments*	*Source Impedance Ω*	*Max. Gain dBi*
1	82	72.64 + *j* 128.2	4.82
2	246	73.19 + *j* 128.9	4.82
3	67	73.06 + *j* 129.1	4.85
4	401	76.21 + *j* 135.2	4.67

Case 2 shows the effect of tripling the number of segments in Case 1. This is a check on the segmentation, to see that the results are stable at a lower level compared to a higher level of segmentation (which theoretically is better, although slower in computation). We purposely set up Case 4 so that the lengths of the segments on either side of the single-segment middle wire are significantly different (0.33 feet) compared to the 2-foot length of the middle wire.

The feed-point and gain figures for the first three models are close to each other. But you can see that the figures for the fourth model are beginning to diverge from the first three, with about a 5% overall change in the reactance and resistance compared to the average values, and about a 3% change in the maximum gain. This illustrates that it is best to keep the segments surrounding the source equal or at least close to equal in length. We'll soon examine a figure of merit called the *Average Gain* test, but it bears mentioning here that the average gain test is very close for the first three models and begins to diverge for the fourth model.

Things get more interesting if the source is placed at a high-impedance point on an antenna—for example, in the center of a full-wave dipole—the value computed for the source impedance will be high, and things will be quite sensitive to the segment lengths. We'll repeat the computations for the same inverted-V models, but this time at twice the operating frequency, at 7.5 MHz.

Table 4 summarizes the results. The impedance is high, as expected. Note that the resistance term varies quite a bit for all four models, a range of about 23% around the average value. Interestingly, the poorly segmented model's resistance falls in between the other three. The reactive terms are closer for all four models but still cover a range of 4% around the average value. The maximum gain shows the same tendancy to be somewhat lower in the fourth model compared to the first three and thus looks as potentially untrustworthy at 7.5 MHz as it does at 3.75 MHz.

This is, of course, but a small sampling of segmentation schemes, and caution dictates that you shouldn't take these results as being representative of all possibilities. Nevertheless, the lesson to be learned here is that the feed-point (source) impedance can vary significantly at a point where the current is changing rapidly, as it does where a high impedance feed is involved. Another general conclusion that can be drawn from Table 5 is that more segments, particularly if they surround the source segment improperly, is not necessarily better.

Table 4
135-Foot Inverted-V Dipole at 7.5 MHz

Case	*Segments*	*Source Impedance Ω*	*Max. Gain dBi*
1	82	2297 – *j* 2668	5.67
2	246	1822 – *j* 2553	5.66
3	67	1960 – *j* 2583	5.66
4	401	2031 – *j* 2688	5.48

Voltage and Current Sources

Before we leave the topic of sources, you should be aware that programs like *EZNEC* and others have the ability to simulate both voltage sources and current sources. Although native *NEC-2* has several source types, voltage sources are the most commonly used by hams. Native *NEC-2* doesn't have a current source, but a current source is nothing more than a voltage source delivering current through a high impedance. Basic network theory says that every Thevenin voltage source has a Norton current source equivalent. Various commercial implementations of *NEC-2* approach the creation of a current source in slightly different fashions. Some use a high value of inductive reactance as a series impedance, while others use a high value of series resistance.

Why would we want to use a current source instead of a voltage source in a model? The general-purpose answer is that models containing a single source at a single feed point can use a voltage source with no problems. Models that employ multiple sources, usually with different amplitudes and different phase shifts, do best with current sources.

For example, *phased arrays* feed RF currents at different amplitudes and phase shifts into two or more elements. The impedances seen at each element may be very different—some impedances might even have negative values of resistance, indicating that power is flowing out of that element into the feed system due to mutual coupling to other elements. Having the ability to specify the amplitude and phase of the current, rather than a feed voltage, at a feed point in a program like *EZNEC* is a valuable tool.

Next, we examine one more important aspect of building a model, setting up loads. After that, we'll look into two tests for the potential accuracy of a model. These tests can help identify source placement, as well as other problems.

LOADS

Many ham antennas, in particular electrically short ones, employ some sort of *loading* to resonate the system. Sometimes loading takes the form of *capacitance hats*, but these can and should be modeled as wires connected to the top of a vertical radiator. A capacitance hat is not the type of loading we'll explore in this section.

Here, the term *loads* refers to discrete inductances, capacitances and resistances that are placed at some point (or points) in an antenna system to achieve certain effects. One fairly common form of a load is a *loading coil* used to resonate an electrically short antenna. Another form of load often seen in ham antennas is a *trap*. *EZNEC* has a special built-in function to evaluate parallel-resonant traps, even at different frequencies beyond their main parallel resonance.

Just for reference, a more subtle type of load is a *distributed* material load. We encountered just such a load in our first model antenna, the 135-foot long flattop dipole—although we didn't identify it specifically as a load at that time. Instead, it was identified as a "wire loss" associated with copper.

The *NEC-2* core program has the capability of simulating a number of built-in loads, including distributed material and discrete loads. *EZNEC* implements the following discrete loads:

- Series R ± *j* X loads.
- Series R-L-C loads, specified in Ω of resistance, µH of inductance and pF of capacitance.
- Parallel R-L-C loads, specified in Ω of resistance, µH of inductance and pF of capacitance.
- Trap loads, specified in Ω of resistance in series with µH of inductance, shunted by pF of capacitance, at a specific frequency.
- Laplace loads, specified as mathematical Laplace coefficients (sometimes used in older modeling programs and left in *EZNEC* for backwards compatibility).

It is important to recognize that the discrete loads in an antenna modeling program *do not radiate* and they have zero size. The *NEC-2* discrete loads are described by L. B. Cebik in his antenna modeling course as being *mathematical loads*. The fact that *NEC-2* loads do not radiate means that the popular mobile antennas that use helical loading coils wound over a length of fiberglass whip cannot be modeled with *NEC-2*, because such coils do radiate.

Let's say that we want to put a air-wound loading coil with an unloaded Q of 400 at the center of a 40-foot long, 50-foot high, flattop dipole so that it is resonant at 7.1 MHz. The schematic of this antenna is shown in **Fig 18**. Examine the modeling file **Ch4-Loaded Dipole.EZ** to see how a discrete series RL load is used to resonate this short dipole at 7.1 MHz, with a feed-point (source) impedance of 25.3 Ω. This requires a series resistance of 1.854 Ω and an inductive reactance of +741.5 Ω. Note that we again used a single wire to model this antenna, and that we placed the load at a point 50% along the length of the wire.

This load represents a 16.62 µH coil with an unloaded Q of 741.5/1.854 = 400, just what we wanted. Let's assume for now that we use a perfect transformer to transform the 25.3-Ω source impedance to 50 Ω. If we now attempt to run a frequency sweep over the whole 40-meter band from 7.0 to 7.3 MHz, the load reactance and resistance will not change, since we specified fixed values for reactance and resistance. Hence, the source impedance will be correct only at the frequency where the reactance and resistance are specified, since the reactance changes with frequency.



Fig 18—Schematic diagram of a 40-foot long flattop dipole with a loading coil placed at the center. This coil has an unloaded Q of 400 at 7.1 MHz.



Freq 7 MHz
SWR 3.22
Z 24.67 - j 30.92 ohms
Refl Coeff 0.5263 at -59.42 deg.
Source # 1
Z0 25.3 ohms

Fig 19—SWR graph of the loaded 40-foot long flattop dipole shown in Fig 18.

So let's use another load capability and substitute a 16.62 µH coil with a series 1.854-Ω resistance at 7.1 MHz. We'll let *EZNEC* take care of the details of computing both the reactance and the changing series resistance at various frequencies. The degree that both reactance and series loss resistance of the coil change with frequency may be viewed using the **Load Dat** button from the main *EZNEC* window.

Fig 19 shows the computed SWR curve for a 25.3-Ω **Alt SWR Z0** reference resistance. The 2:1 SWR bandwidth is about 120 kHz. As could be expected, the antenna has a rather narrow bandwidth because it is electrically short.

ACCURACY TESTS

There are two tests that can help identify accuracy problems in a model:

- The Convergence test.
- The Average Gain test.

Convergence Test

The idea behind the *Convergence* test is simple: If you increase the segmentation in a particular model and the results changes more than you'd like, then you increase the segmentation until the computations converge to a level that is suitable to you. This process has the potential for being subjective, but simple antenna models do converge quickly. In this section, we'll review several more of the antennas discussed previously to see how they converge.

Let's go back to the simple dipole in Fig 3. The original segmentation was 11 segments, but we'll start with a very low value of segmentation of three, well below the minimum recommended level. **Table 5** shows how the source impedance and gain change with increase in segmentation at 3.75 MHz. For this simple antenna, the gain levels off at 6.50 dBi by the time the segmentation has reached 11 segments. Going to ten times the minimum-recommended level (to 111 segments) results in an increase of only 0.01 dBi in the gain.

Arguably, the impedance has also stabilized by the time we reach a segmentation level of 11 segments, although purists may opt for 23 segments. The tradeoff is a slowdown in computational speed.

Let's see how the 5-element Yagi model converges with changes in segmentation level. **Table 6** shows how the source impedance, gain, 180° front-to-back ratio and worst-case front-to-rear ratio change with segmentation density. By the time the segmentation has reached 11 segments per wire, the impedance and gain have stabilized quite nicely, as has the F/R. The 180° F/B is still increasing with segmentation level until about 25 segments, but a relatively small shift in frequency will change the maximum F/B level greatly. For example, with 11 segments per wire, shifting the frequency to 14.1 MHz—a shift of only 0.5%— will change the maximum 180° F/B from almost 50 dB down to 27 dB. For this reason the F/R is considered a more reliable indicator of the adequacy of the segmentation level than is F/B.

Table 5
135-Foot Flattop Dipole at 3.75 MHz

Segments	*Source Impedance Ω*	*Max. Gain dBi*
3	85.9 + *j* 128.0	6.34
5	86.3 + *j* 128.3	6.45
7	86.8 + *j* 128.8	6.48
11	87.9 + *j* 129.5	6.50
23	88.5 + *j* 130.3	6.51
45	89.0 + *j* 130.8	6.51
101	89.4 + *j* 131.1	6.51

Table 6
5-element Wire Yagi at 14.1739 MHz

Segments	*Source Impedance Ω*	*Max. Gain dBi*	*180° F/B dB*	*F/R dB*
3	28.5 – *j* 30.6	12.79	23.2	22.4
5	26.3 – *j* 25.6	13.02	30.5	23.1
7	25.6 – *j* 24.0	13.07	34.8	23.1
11	25.1 – *j* 22.9	13.09	39.9	23.1
25	24.9 – *j* 22.0	13.10	43.7	23.1
99	24.7 – *j* 21.5	13.10	44.2	23.1

Average Gain Test

The theory behind the *Average Gain* test is a little more involved. Basically, if you remove all intentional losses in a model, and if you place the antenna either in free space or over perfect ground, then all the power fed to the antenna should be radiated by it. Internally, the program runs a full 3-D analysis, adding up the power in all directions and then dividing that sum by the total power fed to the antenna. Since *NEC-2* is very sensitive about source placement, as mentioned before, the Average Gain test is a good indicator that something is wrong with the specification of the source.

Various commercial versions of *NEC-2* handle the Average Gain test in different ways. *EZNEC* requires the operator to turn off all distributed losses in wires or set to zero any discrete resistive losses in loads. Next you set the ground environment to free space (or perfect ground) and request a 3-D pattern plot. *EZNEC* will then report the average gain, which will be 1.000 if the model has no problems. The average gain can be lower or higher than 1.000, but if it falls within the range 0.95 to 1.05 it is usually considered adequate.

As L. B. Cebik, W4RNL, stated in his ARRL Certification and Continuing Education Course on antenna modeling: "Like the convergence test, the average gain test is a necessary but not a sufficient condition of model reliability." Pass both tests, however, and you can be pretty well sure that your model represents reality. Pass only one test, and you have reason to worry about how well your model represents reality.

Once again, open the model file **Ch4-Mod Inverted V Poor Segmentation.EZ** and set **Wire Loss** to zero, **Ground Type** to Free Space and **Plot Type** to 3-Dimensional. Click on the **FF Plot** button. *EZNEC* will report that the Average Gain is 0.955 = –0.2 dB. This is very close to the lower limit of 0.95 considered valid for excellent accuracy. This is a direct result of forcing the segment lengths adjacent to the source segment to be considerably shorter than the source segment's length. The gain reported using this test would be approximately –0.2 dB from what it should be—just what Table 4 alludes to also.

Now, let's revisit the basic model **Ch4-Inverted V Dipole.EZ** and look at Case 2 in Table 4. Case 2 amounts to a Convergence test for the basic inverted-V model. Since the impedance and gain changes were small comparing the basic model to the one using three times the number of segments, the model passed the Convergence test. The Average Gain test for the basic model yields a value of 0.991, well within the limits for good accuracy. This model has thus passed both tests and can be considered accurate.

Running the Average Gain test for the 5-element Yagi (using 11 segments per wire and whose convergence we examined in Table 6) yields a value of 0.996, again well within the bounds indicating a good model. And the simple flattop dipole with 11 segments at 3.75 MHz yields an Average Gain result of 0.997, again indicating a very accurate model.

OTHER POSSIBLE MODEL LIMITATIONS

Programs based on the *NEC-2* core computational code have several well-documented limitations that you should know about. Some limitations have been removed in the restricted-access *NEC-4* core (which is not generally available to users), but other limitations still exist, even in *NEC-4*.

Closely Spaced Wires

If wires are spaced too close to each other, the *NEC-2* core can run into problems. If the segments are not carefully aligned, there also can be problems with accuracy. The worst-case situation is where two wires are so close together that their volumes actually merge into each other. This can happen where wires are thick, parallel to each other and close together. You should keep parallel wires separated by at least several diameters.

For example, #14 wire is 0.064 inches in diameter. The rule then is to keep parallel #14 wires separated by more than 2 × 0.064 = 0.128 inches. And you should run the Convergence test to assure yourself that the solution is indeed converging when you have closely spaced wires, especially if the two wires have different diameters. To model antennas containing closely spaced wires, very often you will need many more segments than usual and you must also carefully ensure that the segments line up with each other.

Things can get a little more tricky when wires cross over or under each other, simply because such crossings are sometimes difficult to visualize. Again, the rule is to keep crossing wires separated by more than two diameters from each other. And if you intend to join two wires together, make sure you do so at the ends of the two wires, using identical end coordinates. When any or all of these rules are violated, the Convergence and Average Gain tests will usually warn you of potential inaccuracies.

Parallel-Wire Transmission Lines and LPDAs

A common example of problems with closely spaced wires is when someone attempts to model a parallel-wire transmission line. *NEC-2*-based programs usually do not work as well in such situations as do *MININEC*-based programs. The problems are compounded if the diameters are different for the two wires simulating a parallel-wire transmission line. In *NEC-2* programs, it is usually better to use the built-in "perfect transmission line" function than to try to model closely spaced parallel wires as a transmission line.

For example, a Log Periodic Dipole Array (LPDA) is composed of a series of elements fed using a transmission line that reverses the phase 180° at each element. In other words, the elements are connected to a transmission line that reverses connections left-to-right at each element. It is cumbersome to do so, but you could model such a transmission line using separate wires in *EZNEC*, but it is a potentially confusing and a definitely painstaking process. Further, the accuracy of the resulting model is usually suspect, as shown by the Average Gain test.

It is far easier to use the **Trans Lines** function from the *EZNEC* main window to accurately model an LPDA. See **Fig 20**, which shows the **Trans Lines** window for the **9302A.EZ** 16-element LPDA. There are 15 transmission lines connecting the 16 elements, placed at the 50% point on each element, with a 200-Ω characteristic impedance and with Reversed connections.

Fat Wires Connected to Skinny Wires

Another inherent limitation in the *NEC-2* computational core shows up when modeling several popular ham-radio antennas: many Yagis and some quads.

Tapered Elements

As mentioned before, many Yagis are built using telescoping aluminum tubing. This technique saves weight and makes for a more flexible and usually stronger element, one that can survive wind and ice loading better than a "monotaper" element design. Many vertical antennas are also constructed using telescoping aluminum tubing.

Unfortunately, native *NEC-2* doesn't model accurately such *tapered elements*, as they are commonly called. There is, however, a sophisticated and accurate work-around for such elements, called the *Leeson corrections*. The Leeson corrections, derived by Dave Leeson, W6NL, from pioneering work by Schelkunoff at Bell Labs, compute the diameter and length of an element that is electrically equivalent to a tapered element. This monotaper element is much easier to use in a pro-



Transmission Lines

No.	End 1 Specified Pos.		End 1 Act	End 2 Specified Pos.		End 2 Act	Length	Z0	VF	Rev/Norm
	Wire #	% From E1	% From E1	Wire #	% From E1	% From E1	(in)	(ohms)		
1	1	50	50	2	50	50	Actual dist	200	1	R
2	2	50	50	3	50	50	Actual dist	200	1	R
3	3	50	50	4	50	50	Actual dist	200	1	R
4	4	50	50	5	50	50	Actual dist	200	1	R
5	5	50	50	6	50	50	Actual dist	200	1	R
6	6	50	50	7	50	50	Actual dist	200	1	R
7	7	50	50	8	50	50	Actual dist	200	1	R
8	8	50	50	9	50	50	Actual dist	200	1	R
9	9	50	50	10	50	50	Actual dist	200	1	R
10	10	50	50	11	50	50	Actual dist	200	1	R
11	11	50	50	12	50	50	Actual dist	200	1	R
12	12	50	50	13	50	50	Actual dist	200	1	R
13	13	50	50	14	50	50	Actual dist	200	1	R
14	14	50	50	15	50	50	Actual dist	200	1	R
15	15	50	50	16	50	50	Actual dist	200	1	R

Fig 20—Transmission-line window for the 9302A.EZ 16-element LPDA. Note that the transmission lines going between elements are "reversed," meaning that they are 180° out-of-phase at each element, a requirement for properly feeding an LPDA.

Table 7

5-element Yagi at 14.1739 MHz with Telescoping Aluminum Elements

	With Leeson Corrections			Without Leeson Corrections		
Freq. MHz	*Source Impedance Ω*	*Gain dBi*	*F/R dB*	*Source Impedance Ω*	*Gain dBi*	*F/R dB*
14.0	23.2 – *j* 26.5	14.82	23.3	22.4 – *j* 12.7	14.92	23.1
14.1	22.7 – *j* 20.5	14.87	22.8	18.6 – *j* 12.5	14.70	21.6
14.2	22.8 – *j* 14.8	14.87	22.7	6.6 – *j* 4.6	14.01	16.2
14.3	22.5 – *j* 11.9	14.76	21.5	1.9 + *j* 10.6	10.61	3.1
14.4	14.5 – *j* 10.5	14.45	19.9	1.6 + *j* 23.7	11.15	–11.4

gram like *NEC-2*. See Chapter 2, Antenna Fundamentals, for more information on the Leeson corrections.

EZNEC and other *NEC-2* programs can automatically invoke the Leeson corrections, providing that some basic conditions are met—and happily, these conditions are true for the telescoping aluminum-tubing elements commonly used as Yagi elements. *EZNEC* gives you the ability to disable or enable Leeson corrections, under the **Option** menu, under **Stepped Diameter Correction**, *EZNEC*'s name for the Leeson corrections. Open the modeling file **520-40H.EZ**, which contains tapered aluminum tubing elements and compare the results using and without using the Leeson corrections.

Table 7 lists the differences over the 20-meter band, with the 5-element Yagi at a height of 70 feet above flat ground. You can see that the non-Leeson corrected figures are very different from the corrected ones. At 14.3 MHz, the pattern for the non-corrected Yagi has degenerated to a F/R of 3.1 db, while at 14.4 MHz, just outside the top of the Amateur band, the pattern for the non-corrected antenna actually has reversed. Even at 14.2 MHz, the non-corrected antenna shows a low source impedance, while the corrected version exhibits smooth variations in gain, F/R and impedance across the whole band, just as the actual antenna exhibits.

Some Quads

Some types of cubical quads are made using a combination of aluminum tubing and wire elements, particularly in Europe where the "Swiss" quad has a wide following. Again, *NEC-2*-based programs don't handle such tubing/wire elements well. It is best to avoid modeling this type of antenna, although there are some ways to attempt to get around the limitations, ways that are beyond the scope of this chapter.

NEAR-FIELD OUTPUTS

FCC regulations set limits on the maximum permissible exposure (MPE) allowed from the operation of radio transmitters. These limits are expressed in terms of the electric (V/m) and magnetic fields (A/m) close to an antenna. *NEC-2*-based programs can compute the electric and magnetic *near fields* and the FCC accepts such computations to demonstrate that an installation meets their regulatory requirements. See Chapter 1, Safety, in this book.

Table 8

E- and H-Field Intensities for 1500 W into 5-Element Yagi at 70 Feet on 14.2 MHz

Height Feet	*H-Field (A/m)*	*E-Field (V/m)*
0	0.04	4.1
10	0.03	13.8
20	0.04	20.6
30	0.06	22.6
40	0.08	25.8
50	0.10	33.8
60	0.12	41.5
70	0.12	44.3

We'll continue to use the 5-element Yagi at 70 feet to demonstrate a near-field computation. Open **Ch4-520-40H.EZ** in *EZNEC* and choose **Setups** and then **Near Field** from the menu at the top of the main window. Let's calculate the E-field and H-field intensity for a power level of 1500 W (chosen using the **Options**, **Power Level** choices from the main menu) in the main beam at a fixed distance, say 50 feet, from the tower base. We'll do this at various heights, using 10-foot increments of height, in order to see the lobe structure of the Yagi at 70 feet height.

Table 8 summarizes the total H- and E-field intensities as a function of height. As you might expect, the fields are strongest directly in line with the antenna at a height of 70 feet. At ground level, the total fields are well within the FCC limits for rf exposure for both fields. In fact, the fields are within the FCC limits if someone were to stand at the tower base, directly under the antenna.

ANTENNA MODELING SUMMARY

This section on antenna modeling is by necessity only a brief introduction to the science of antenna modeling. The subject is partly art as well as science because there are usually several ways of creating a model for a particular antenna or antennas.

Indeed, the presence of other wires surrounding a particular antenna can affect the performance of that antenna. Finally, there are the practical aspects of putting a actual antenna up in the real world. We'll explore this next.

Practical Aspects, Designing Your Antenna System

The most important time spent in putting together an antenna system is the time spent in planning. In Chapter 3, The Effects of Ground, we outlined the steps needed to evaluate how your local terrain can affect HF communications. There we emphasized that you need to compare the patterns resulting from your own terrain to the statistically relevant elevation angles needed for coverage of various geographic areas. (The elevation-angle statistics were developed in Chapter 23, Radio Wave Propagation and are located on the CD-ROM included with this book, as is the terrain-assessment program *HFTA*.)

The implicit assumptions in Chapter 3 are (1) that you know where you want to talk to, and (2) that you'd like the most effective system possible. At the start of such a theoretical analysis, cost is no object. Practical matters, like cost or the desires of your spouse, can come later! After all, you're just checking out all the possibilities. If nothing else, you will use the methodology in Chapter 3 to evaluate any property you are considering buying so that you can build your "dream station."

Next, in the first part of this chapter we described modeling tools used to evaluate different types of antennas. These modeling tools can help you evaluate what type of antenna might be suitable to your own particular style of operating. Do you want a Yagi with a lot of rejection of received signals from the rear? Let's say that terrain analysis shows that you need an antenna at least 50 feet high. Do you really need a steel tower, or would a simple dipole in the trees serve your communication needs just fine? How about a vertical in your backyard? Would that be inconspicuous enough to suit your neighbors and your own family, yet still get you on the air?

In short, using the techniques and tools we've presented in Chapters 3, 23 and here in Chapter 4, you can scientifically plan an antenna *system* that will be best suited for your own particular conditions. Now, however, you have to get practical. Thinking through and planning the installation can save a lot of time, money and frustration. While no one can tell you the exact steps you should take in developing your own master plan, this section, prepared originally by Chuck Hutchinson, K8CH, should help you with some ideas.

WHAT DO YOU REALLY WANT?

Begin planning by spelling out your communications *desires*. What bands are you interested in? Who (or where) do you want to talk to? When do you operate? How much time and money are you willing to spend on an antenna system? What physical limitations affect your master plan?

From the answers to the above questions, begin to formulate *goals*—short, intermediate and long range. Be realistic about those goals. Remember that there are three station effectiveness factors that are under your control. These are: operator skill, equipment in the shack, and the antenna system. There is no substitute for developing operating skills. Some tradeoffs are possible between shack equipment and antennas. For example, a high-power amplifier can compensate for a less than optimum antenna. By contrast, a better antenna has advantages for receiving as well as for transmitting.

Consider your *limitations*. Are there regulatory restrictions on antennas in your community? Are there any deed restrictions or covenants that apply to your property? Do other factors (finances, family considerations, other interests, and so forth) limit the type or height of antennas that you can erect? All of these factors must be investigated because they play a major role determining the type of antennas you erect.

Chances are that you won't be able to immediately do all you desire. Think about how you can budget your resources over a period of time. Your resources are your money, your time available to work, materials you may have on hand, friends that are willing to help, etc. One way to budget is to concentrate your initial efforts on a given band or two. If your major interest is in chasing DX, you might want to start with a very good antenna for the 14-MHz band. A simple multiband antenna could initially serve for other frequencies. Later you can add better antennas for those other bands.

SITE PLANNING

A map of your property or proposed antenna site can be of great help as you begin to consider alternative antennas. You'll need to know the size and location of buildings, trees and other major objects in the area. Be sure to note compass directions on your map. Graph or quadrille paper (or a simple CAD program) can be very useful for this purpose. See **Fig 21** for an example. It's a good idea to make a few photocopies of your *site map* so you can mark on the copies as you work on your plans.

Use your map to plan antenna layouts and locations of any supporting towers or masts. If your plan calls for more than one tower or mast, think about using them as supports for wire antennas. As you work on a layout, be sure to think in three dimensions even though the map shows only two.

Be sensitive to your neighbors. A 70-foot guyed tower in the front yard of a house in a residential neighborhood is not a good idea (and probably won't comply with local ordinances!). You probably will want to locate that tower in the back yard.

ANALYSIS

Use the information earlier in this chapter and in Chapters 3 and 23 to analyze antenna patterns in both



Fig 21—A site map such this one is a useful tool for planning your antenna installation.

horizontal and vertical planes towards geographic areas of interest. If you want to work DX, you'll want antennas that radiate energy at low as well as intermediate angles. An antenna pattern is greatly affected by the presence of ground and by the local topography of the ground. Therefore, be sure to consider what effect ground will have on the antenna pattern at the height you are considering. A 70-foot high antenna is approximately $^{1}/_{2}$, 1, 1$^{1}/_{2}$ and 2 wavelengths (λ) high on 7, 14, 21 and 28 MHz respectively. Those heights are useful for long-distance communications. The same 70-foot height represents only λ/4 at 3.5 MHz, however. Most of the radiated energy from a dipole at that height would be concentrated straight up. This condition is not great for long-distance communication, but can still be useful for some DX work and excellent for short-range communications.

Lower heights can be useful for communications. However, it is generally true that "the higher, the better" as far as communications effectiveness is concerned. This general rule of thumb, of course, should be tempered by an exact analysis of your local terrain. Being located at the top of a steep hill can mean that you can use lower tower heights to achieve good coverage.

There may be cases where it is not possible to install low-frequency dipoles at λ/4 or more above the ground. A vertical antenna with many radials is a good choice for long-distance communications. You may want to install both a dipole and a vertical for the 3.5- or 7-MHz bands. On the 1.8-MHz band, unless extremely tall supports are available, a vertical antenna is likely to be the most useful for DXing. You can then choose the antenna that performs best for a given set of conditions. A low dipole will generally work better for shorter-range communications, while the vertical will generally be the better performer over longer distances.

Consider the azimuthal pattern of fixed antennas. You'll want to orient any fixed antennas to favor the directions of greatest interest to you.

BUILDING THE SYSTEM

When the planning is completed, it is time to begin construction of the antenna system. Chances are that you can divide that construction into a series of *phases* or steps. Say, for example, that you have lots of room and that your long-range plan calls for a pair of towers, one 100-feet high, and the other 70-feet high, to support monoband Yagi antennas. The towers will also support a horizontal 3.5-MHz dipole, for DX work. On your map you've located them so the 80-meter dipole will be broadside to Europe. You decide to build the 70-foot tower with a "triband" beam and 80- and 40-meter inverted-V dipoles to begin the project.

In your master plan you design the guys, anchors and all hardware for the 70-foot tower to support the load of stacked 4-element 10- and 15-meter monobanders Yagis. So you make sure you buy a heavy-duty rotator and the stout mast needed for the monoband antennas later. Thus you avoid having to buy, and then sell, a medium-duty rotator and lighter weight tower equipment later on when you upgrade the station. You could have saved money in the long run by putting up a monoband beam for your favorite band, but you decided that for now it is more important to have a beam on 14, 21 and 28 MHz, so you choose a commercial triband Yagi.

The second step of your plan calls for installing the second tower and stacking a 2-element 40-meter and a 4-element 20-meter monoband Yagi on it. You also plan to replace the tribander on the 70-foot tower with stacked 4-element 10- and 15-meter monoband Yagis. Although this is still a "dream system" you can now apply some of the modeling techniques discussed earlier in this chapter to determine the overall system performance.

Modeling Interactions at Your Dream Station

In this analysis we're going to assume that you have sufficient real estate to separate the 70- and 100-foot towers by 150 feet so that you can easily support an 80-meter dipole between them. We'll also assume that you want the 80-meter dipole to have its maximum response at a heading of 45° into Europe from your location in Newington, Connecticut. The dipole will also have a lobe



Fig 22—Layout for two-tower antenna system, at 70 and 100 feet high and 150 feet apart. The 70-foot tower has a 4-element 10-meter Yagi at 80 feet on a 10-foot rotating mast and a 4-element 15-meter Yagi at 70 feet. An 80-meter dipole goes from the 70-foot tower to the 100-foot tower, which holds a 2-element 40-meter Yagi at 110 feet and a 4-element 20-meter Yagi at 100 feet. In this figure all the rotatable Yagis are facing the direction of Europe and the currents on the 15-meter Yagi are shown. Note the significant amount of current re-radiated by the nearby 80-meter dipole.

facing 225° towards the USA and New Zealand, making it a good antenna for both domestic contacts and DX work.

Let's examine the interactions that occur between the rotatable Yagis for 10, 15, 20 and 40 meters. See **Fig 22**, which purposely exaggerates the magnitude of the currents on the 4-element 15-meter Yagi mounted at 70 feet. Here, both sets of Yagis have been rotated so that they are pointing into Europe. There is a small amount of current radiated onto the 10-meter antenna but virtually no current is radiated onto the 40- and 20-meter Yagis. This is good.

However, significant current is radiated onto, and then re-radiated, by the 80-meter dipole. This undesired current affects the radiation pattern of the 15-meter antenna, as shown in **Fig 23**, which overlays the pattern of the 4-element 15-meter Yagi by itself with that of the Yagi interacting with the other antennas. You can see "ripples" in the azimuthal response of the 15-meter Yagi due to the effects of the 80-meter dipole's re-radiation. The magnitude of the ripples is about 1 dB at worst, so they don't seriously affect the forward pattern (into Europe), but the rearward lobes are degraded somewhat, to just below 20 dB.



Fig 23—An overlay of azimuth patterns. The solid line is the radiation pattern for the 15-meter Yagi all by itself. The dashed line is the pattern for the 15-meter Yagi, as affected by all the other antennas. The dotted line is the pattern for the 15-meter Yagi when it is pointed toward the Caribbean, with the Yagis on the 100-foot tower pointed toward the 70-foot tower. The peak response of the 15-meter Yagi has dropped by about 1.5 dB.



Fig 24—The layout and 15-meter currents when the Yagis on the 100-foot tower are pointed toward the 70-foot tower. The 15-meter Yagi has been rotated to face the direction of the 100-foot tower (toward the Caribbean).

Fig 23 also shows the worst-case situation for the 15-meter Yagi. Here, the 15- and 10-meter stack has been turned clockwise 90°, facing the Caribbean, while the 40- and 20-meter Yagis on the 100-foot tower have been turned counter-clockwise 90° (in the direction of Japan) to face the 70-foot tower holding the 10/15-meter Yagis. You can see the layout and the currents in **Fig 24**. Now the 40- and 20-meter Yagis re-radiate some 15-meter



Fig 25—The radiation patterns for the 10-meter Yagi. The solid line is the 10-meter Yagi by itself. The dashed line is for the same Yagi, with all other antenna interactions. The dotted line shows the worst-case pattern, with the stacked Yagis on the 100-foot tower facing the 70-foot tower and the 10-meter Yagi pointed toward the Caribbean. Again, the peak response of the 10-meter Yagi has dropped about 1.5 dB in the worst-case situation.

energy and reduce the maximum gain by about 1.5 dB. Note that in this direction the 80-meter dipole no longer has 15-meter energy radiated onto it by the 15-meter Yagi.

The shape of the patterns will change depending on whether you specify “current” or “voltage” sources in the models for the other antennas, since this effectively opens up or shorts the feed points at the other antennas so far as 15-meter energy is concerned. In practice, this means that the interaction between antennas will vary somewhat depending on the length of the feed lines going to each antenna and whether each feed line is open-circuited or short-circuited when it is not in use.

You can now see that interactions between various antennas pointing in different directions can be significant in a real-world antenna system. In general, higher-frequency antennas are affected by re-radiation from lower-frequency antennas, rather than the other way around. Thus the presence of a 10- or 15-meter stack does not affect the 20-meter Yagi at all.

Modeling can also help determine the minimum stacking distance required between monoband Yagis on the same rotating mast. In this case, stacking the 10- and 15-meter monobanders 10 feet apart holds down interaction between them so that the pattern and gain of the 10-meter Yagi is not impacted adversely. **Fig 25** demonstrates this in the European direction, where the patterns for the 10-meter beam by itself looks very clean compared to the same Yagi separated by 10 feet from the 15-meter Yagi below it. The worst-case situation is pointing towards the Caribbean, when the 40- and 20-meter stack is facing the 70-foot tower. This drops the 10-meter gain down about 1.5 dB from maximum, indicating significant interaction is occurring.

In this situation you might find it best to place the 70-foot tower in the direction closest to the Caribbean if this direction is very important to you. Doing so will, however, cause the pattern in the direction of the Far East to be affected on 10 and 15 meters. You have the modeling tools necessary to evaluate various configurations to achieve whatever is most important to you.

COMPROMISES

Because of limitations, most amateurs are never able to build their dream antenna system. This means that some compromises must be made. Do not, under any circumstances, compromise the *safety* of an antenna installation. Follow the manufacturer’s recommendations for tower assembly, installation and accessories. Make sure that all hardware is being used within its ratings.

Guyed towers are frequently used by radio amateurs because they cost less than more complicated unguyed or freestanding towers with similar ratings. Guyed towers are fine for those who can climb, or those with a friend who is willing to climb. But you may want to consider an antenna tower that folds over, or one that cranks up (and down). Some towers crank up (and down) and fold over too. See **Fig 26**. That makes for convenient access to antennas for adjustments and maintenance without climbing. Crank-up towers also offer another advantage. They allow antennas to be lowered during periods of no operation, such as for aesthetic reasons or during periods of high winds.

A well-designed monoband Yagi should outperform a multiband Yagi. In a monoband design the best adjustments can be made for gain, front-to-rear ratio (F/R) and matching, *but only for a single band*. In a multiband design, there are always tradeoffs in these properties for the ability to operate on more than one band. Nevertheless, a multiband antenna has many advantages over two or more single band antennas. A multiband antenna requires less heavy-duty hardware, requires only one feed line, takes up less space and it costs less.

Apartment dwellers face much greater limitations in their choice of antennas. For most, the possibility of a tower is only a dream. (One enterprising ham made arrangements to purchase a top-floor condominium from a developer. The arrangements were made before construction began, and the plans were altered to include a roof-top tower installation.) For apartment and condominium dwellers, the situation is still far from hopeless. A later section presents ideas for consideration.



Fig 26—Alternatives to a guyed tower are shown here. At A, the crank-up tower permits working on antennas at reduced height. It also allows antennas to be lowered during periods of no operation. Motor-driven versions are available. The fold-over tower at B and the combination at C permit working on antennas at ground level.

EXAMPLES

You can follow the procedure previously outlined to put together modest or very large antenna systems. What might a ham put together for antennas when he or she wants to try a little of everything, and has a modest budget? Let's suppose that the goals are (1) low cost, (2) no tower, (3) coverage of all HF bands and the repeater portion of one VHF band, and (4) the possibility of working some DX.

After studying the pages of this book, the station owner decides to first put up a 135-foot center-fed antenna. High trees in the back yard will serve as supports to about 50 feet. This antenna will cover all the HF bands by using a balanced feeder and an antenna tuner. It should be good for DX contacts on 10 MHz and above, and will probably work okay for DX contacts on the lower bands. However, her plan calls for a vertical for 3.5 and 7 MHz to enhance the DX possibilities on those bands. For VHF, a chimney-mounted vertical is included.

ANOTHER EXAMPLE

A licensed couple has bigger ambitions. Goals for their station are (1) a good setup for DX on 14, 21 and 28 MHz, (2) moderate cost, (3) one tower, (4) ability to work some DX on 1.8, 3.5 and 7 MHz, and (5) no need to cover the CW portion of the bands.

After considering the options, the couple decides to install a 65-foot guyed tower. A large commercial triband Yagi will be mounted on top of the tower. The center of a trap dipole tuned for the phone portion of the 3.5- and 7-MHz bands will be supported by a wooden yardarm installed at the 60-foot level of the tower, with ends drooping down to form an inverted V. An inverted L for 1.8 MHz starts near ground level and goes up to a similar yardarm on the opposite side of the tower. The horizontal portion of the inverted L runs away from the tower at right angles to the trap dipole. Later, the husband will experiment with sloping antennas for 3.5 MHz. If those experiments are not successful, a $\lambda/4$ vertical will be used on that band.

Apartment Possibilities

A complete and accurate assessment of antenna types, antenna placement and feed-line placement is very important for the apartment dweller. Among the many possibilities for types are balcony antennas, *invisible* ones (made of fine wire), vertical antennas disguised as flag poles or as masts with a TV antenna on top, and indoor antennas.

A number of amateurs have been successful negotiating with the apartment owner or manager for permission to install a short mast on the roof of the building. Coaxial lines and rotator control cables might be routed through conduit troughs or through ductwork. If you live in one of the upper stories of the building, routing the cables over the edge of the roof and in through a window might be the way to go. There is a story about one amateur who owns a triband beam mounted on a 10-foot mast. But even with such a short mast, he is the envy of all his amateur friends because of his superb antenna height. His mast stands on top of a 22-story apartment building.

Usually the challenge is to find ways to install antennas that are unobtrusive. That means searching out antenna locations such as balconies, eaves, nearby trees, etc. For example, a simple but effective balcony antenna is a dangling vertical. Attach a thin wire to the tip of a mobile whip or a length of metal rod or tubing. Then mount the rigid part of the antenna horizontally on the balcony rail, dangling the wire over the edge. The antenna is operated against the balcony railing or other metallic framework. A matching network is usually required at the antenna feed point. Metal in the building will likely give a directivity effect, but this may be of little consequence and perhaps even an advantage. The antenna may be removed and stored when not in use.

Frequently, the task of finding an inconspicuous route for a feed line is more difficult than the antenna installation itself. When Al Francisco, K7NHV, lived in an apartment, he used a tree-mounted vertical antenna. The coax feeder exited his apartment through a window and ran down the wall to the ground. Al buried the section of line that went from under the window to a nearby tree. At the tree, a section of enameled wire was connected to the coax center conductor. He ran the wire up the side of the tree away from foot traffic. A few short radials completed the installation. The antenna worked fine, and was never noticed by the neighbors.

See Chapters 6, Low-Frequency Antennas, and Chapter 15, Portable Antennas, for ideas about low-frequency and portable antennas that might fit into your available space. Your options are limited as much by your imagination and ingenuity as by your pocketbook. Another option for apartment dwellers is to operate away from home. Some hams concentrate on mobile operation as an alternative to a fixed station. It is possible to make a lot of contacts on HF mobile. Some have worked DXCC that way.

Suppose that you like VHF contests. Because of other activities, you are not particularly interested in operating VHF outside the contests. Why not take your equipment and antennas to a hilltop for the contests? Many hams combine a love for camping or hiking with their interest in radio.

Antennas for Limited Space

It is not always practical to erect full-size antennas for the HF bands. Those who live in apartment buildings may be restricted to the use of minuscule radiators because of house rules, or simply because the required space for full-size antennas is unavailable. Other amateurs may desire small antennas for aesthetic reasons, perhaps to keep peace with neighbors who do not share their enthusiasm about high towers and big antennas. There are many reasons why some amateurs prefer to use physically-shortened antennas. This section discusses proven designs and various ways of building and using them effectively. You will find that modeling antennas by computer, even compromised “stealth antennas,” can help you determine the most practical system possible for your particular circumstances—before you go through the effort of stringing up wires.

Few compromise antennas are capable of delivering the performance you can expect from the full-size variety. But the patient and skillful operator can often do as well as some who are equipped with high power and full-size antennas. Someone with a reduced-size antenna may not be able to “bore a hole” in the bands as often and with the commanding dispatch enjoyed by those who are better equipped, but DX can be worked successfully when band conditions are suitable.

INVISIBLE ANTENNAS

We amateurs don’t regard our antennas as eyesores; in fact, we almost always regard them as works of art! But there are occasions when having an outdoor or visible antenna can present problems.

When we are confronted with restrictions—self-imposed or otherwise—we can take advantage of a number of options toward getting on the air and radiating at least a moderately effective signal. In this context, a poor antenna is certainly better than no antenna at all! This section describes a number of techniques that enable us to use indoor antennas or “invisible” antennas outdoors.



Fig 27—The clothesline antenna is more than it appears to be.



Fig 28—The "invisible" end-fed antenna.

Many of these systems will yield good-to-excellent results for local and DX contacts, depending on band conditions at any given time. *The most important consideration is that of not erecting any antenna that can present a hazard (physical or electrical) to humans, animals and buildings. Safety first!*

Clothesline Antenna

Clotheslines are sometimes attached to pulleys (**Fig 27**) so that the user can load the line and retrieve the laundry from a back porch. Laundry lines of this variety are accepted parts of the neighborhood "scenery," and can be used handily as amateur antennas by simply insulating the pulleys from their support points. This calls for the use of a conducting type of clothesline, such as heavy gauge stranded electrical wire with Teflon or vinyl insulation. A high quality, flexible steel cable (stranded) is suitable as a substitute if you don't mind cleaning it before clothing is hung on it.

A jumper wire can be brought from one end of the line to the ham shack when the station is being operated. If a good electrical connection exists between the wire clothesline and the pulley, a permanent connection can be made by connecting the lead-in wire between the pulley and its insulator. An antenna tuner can be used to match the "invisible" random-length wire to the transmitter and receiver.

Invisible Long Wire

A wire antenna is not actually a "long wire" unless it is one wavelength or greater in length. Yet many amateurs refer to (relatively) long physical spans of conductor as *long wires*. For the purpose of this discussion we will assume we have a fairly long span of wire, and refer to it as an *end-fed* wire antenna.

If we use small-diameter enameled wire for our end-fed antenna, chances are that it will be very difficult to see against the sky and neighborhood scenery. The smaller the wire, the more invisible the antenna will be. The limiting factor with small wire is fragility. A good compromise is #24 or #26 magnet wire for spans up to 130 feet; lighter-gauge wire can be used for shorter spans, such as 30 or 60 feet. The major threat to the longevity of fine wire is icing. Also, birds may fly into the wire and break it. Therefore, this style of antenna may require frequent service or replacement.

Fig 28 illustrates how you might install an invisible end-fed wire. It is important that the insulators also be lacking in prominence. Tiny Plexiglas blocks perform this function well. Small-diameter clear plastic medical vials are suitable also. Some amateurs simply use rubber bands for end insulators, but they will deteriorate rapidly from sun and air pollutants. They are entirely adequate for short-term operation with an invisible antenna, however.

Rain Gutter and TV Antennas

A great number of amateurs have taken advantage of standard house fixtures when contriving inconspicuous antennas. A very old technique is the use of the gutter and downspout system on the building. This is shown in **Fig 29**, where a lead wire is routed to the operating room



Fig 29—Rain gutters and TV antenna installations can be used as inconspicuous Amateur Radio antennas.

from one end of the gutter trough. We must assume that the wood to which the gutter is affixed is dry and of good quality to provide reasonable electrical insulation. The rain gutter antenna may perform quite poorly during wet weather or when there is ice and snow on it and the house roof.

All joints between gutter and downspout sections must be bonded electrically with straps of braid or flashing copper to provide good continuity in the system. Poor joints can permit rectification of RF and subsequently cause TVI and other harmonic interference. Also, it is prudent to insert a section of plastic downspout about 8 feet above ground to prevent RF shocks or burns to passersby while the antenna is being used. Improved performance may result if you join the front and back gutters of the house with a jumper wire to increase the area of the antenna.

Fig 29 also shows a TV or FM antenna that can be employed as an invisible amateur antenna. Many of these antennas can be modified easily to accommodate the 144- or 222-MHz bands, thereby permitting the use of the 300-Ω line as a feeder system. Some FM antennas can be used on 6 meters by adding #10 bus wire extensions to the ends of the elements, and adjusting the match for an SWR of 1:1. If 300-Ω line is used it will require a balun or antenna tuner to interface the line with the station equipment.

For operation in the HF bands, the TV or FM antenna feeders can be tied together at the transmitter end of the span and the system treated as a random length wire. If this is done, the 300-Ω line will have to be on TV standoff insulators and spaced well away from phone and power company service entrance lines. Naturally, the TV or FM radio must be disconnected from the system when it is used for amateur work! Similarly, masthead amplifiers and splitters must be removed from the line if the system is to be used for amateur operation. If the system is mostly vertical, a good RF ground system with many radials around the base of the house should be used to improve performance.

A very nice top-loaded vertical can be made from a length of TV mast with a large TV antenna on the top. Radials can be placed on the roof or at ground level with the TV "feed line" acting as part of the vertical. There is an extensive discussion of loaded verticals and radial systems in Chapter 6, Low-Frequency Antennas.

Flagpole Antennas

We can exhibit our patriotism and have an invisible amateur antenna at the same time by disguising our antenna as shown in **Fig 30**. The vertical antenna is a wire that has been placed inside a plastic or fiberglass pole.

The flagpole antenna shown is structured for a single amateur band, and it is assumed that the height of the pole corresponds to a quarter wavelength for the chosen band. The radials and feed line can be buried in the ground as shown. In a practical installation, the sealed end of the coax cable would protrude slightly into the lower end of the plastic pole.



Fig 30—A flagpole antenna.

If a large-diameter fiberglass pole were available, a multiband trap vertical may be concealed inside it. Or you might use a metal pole and bury a water-tight box at its base, containing fixed-tuned matching networks for the bands of interest. The networks could then be selected remotely by means of relays inside the box. A 30-foot flagpole would provide good results in this kind of system, provided it was used in conjunction with a buried radial system.

Still another technique is one that employs a wooden flagpole. A small diameter wire can be stapled to the pole and routed to the coax feeder or matching network. The halyard could by itself constitute the antenna wire if it were made from heavy-duty insulated hookup wire. There are countless variations for this type of antenna, and they are limited only by the imagination of the amateur.

Other Invisible Antennas

Some amateurs have used the metal fence on apartment verandas as antennas, and have had good results on the upper HF bands (14, 21 and 28 MHz). We must presume that the fences were not connected to the steel framework of the building, but rather were insulated by the concrete floor to which they were affixed. These verandah fences have also been used effectively as ground systems (counterpoises) for HF-band vertical antennas put in place temporarily after dark.

One amateur in New York City uses the fire escape on his apartment building as a 7-MHz antenna, and he reports good success working DX stations with it. Another apartment dweller makes use of the aluminum frame on his living room picture window as an antenna for 21 and 28 MHz. He works it against the metal conductors of the baseboard heater in the same room.

Many jokes have been told over the years about *bedspring antennas*. The idea is by no means absurd. Bedsprings and metal end boards have been used to advantage as antennas by many apartment dwellers as 14, 21 and 28 MHz radiators. A counterpoise ground can be routed along the baseboard of the room and used in combination with the bedspring. It is important to remember that any independent (insulated) metal object of reasonable size can serve as an antenna if the transmitter can be matched to it. An amateur in Detroit once used his Shopsmith craft machine (about 5 feet tall) as a 28 MHz antenna. He worked a number of DX stations with it when band conditions were good.

A number of operators have used metal curtain rods and window screens for VHF work, and found them to be acceptable for local communications. Best results with any of these makeshift antennas will be had when the “antennas” are kept well away from house wiring and other conductive objects.

INDOOR ANTENNAS

Without question, the best place for your antenna is outdoors, and as high and in the clear as possible. Some of us, however, for legal, social, neighborhood, family or landlord reasons, are restricted to indoor antennas. Having to settle for an indoor antenna is certainly a handicap for the amateur seeking effective radio communication, but that is not enough reason to abandon all operation in despair.

First, we should be aware of the reasons why indoor antennas do not work well. Principal faults are:

- Low height above ground—the antenna cannot be placed higher than the highest peak of the roof, a point usually low in terms of wavelength at HF
- The antenna must function in a lossy RF environment involving close coupling to electrical wiring, guttering, plumbing and other parasitic conductors, besides dielectric losses in such nonconductors as wood, plaster and masonry
- Sometimes the antenna must be made small in terms of a wavelength
- Usually it cannot be rotated.

These are appreciable handicaps. Nevertheless, global communication with an indoor antenna is still possible, although you must be sure that you are not exposing anyone in your family or nearby neighbors to excessive radiation. See Chapter 1, Safety, in this book.

Some practical points in favor of the indoor antenna include:

- Freedom from weathering effects and damage caused by wind, ice, rain and sunlight (the SWR of an attic antenna, however, can be affected somewhat by a wet or snow-covered roof).
- Indoor antennas can be made from materials that would be altogether impractical outdoors, such as aluminum foil and thread (the antenna need support only its own weight).
- The supporting structure is already in place, eliminating the need for antenna masts.
- The antenna is readily accessible in all weather conditions, simplifying pruning or tuning, which can be accomplished without climbing or tilting over a tower.

Empiricism

A typical house or apartment presents such a complex electromagnetic environment that it is impossible to predict theoretically which location or orientation of the indoor antenna will work best. This is where good old fashioned cut-and-try, use-what-works-best *empiricism* pays off. But to properly determine what really is most suitable requires an understanding of some antenna measuring fundamentals.

Unfortunately, many amateurs do not know how to evaluate performance scientifically or compare one antenna with another. Typically, they will put up one antenna and try it out on the air to see how it “gets out” in comparison with a previous antenna. This is obviously a very poor evaluation method because there is no way to know if the better or worse reports are caused by changing band conditions, different S-meter characteristics or any of several other factors that could influence the reports received.

Many times the difference between two antennas or between two different locations for identical antennas amounts to only a few decibels, a difference that is hard to discern unless instantaneous switching between the two is possible. Those few decibels are not important under strong signal conditions, of course, but when the going gets rough, as is often the case with an indoor antenna, a few dB can make the difference between solid copy and no possibility of real communication.

Very little in the way of test equipment is needed for casual antenna evaluation, other than a communications receiver. You can even do a qualitative comparison by ear, if you can switch antennas instantaneously. Differences of less than 2 dB, however, are still hard to discern. The same is true of S-meters. Signal strength differences of less than a decibel are usually difficult to see. If you want to measure that last fraction of a decibel, you should use a good ac voltmeter at the receiver audio output (with the AGC turned off).

In order to compare two antennas, switching the coaxial transmission line from one to the other is necessary. No elaborate coaxial switch is needed; even a simple double-throw toggle or slide switch will provide more than 40 dB of isolation at HF. See **Fig 31**. Switching by means of manually connecting and disconnecting coaxial lines is not recommended because that takes too long.



Fig 31—When antennas are compared on fading signals, the time delay involved in disconnecting and reconnecting coaxial cables is too long for accurate measurements. A simple slide switch will do well for switching coaxial lines at HF. The four components can be mounted in a tin can or any small metal box. Leads should be short and direct. J1 through J3 are coaxial connectors.

Fading can cause signal-strength changes during the changeover interval.

Whatever difference shows up in the strength of the received signal will be the difference in performance between the two antennas in the direction of that signal. For this test to be valid, both antennas must have nearly the same feed-point impedance, a condition that is reasonably well met if the SWR is below 2:1 on both antennas.

On ionospheric propagated signals (sky wave) there will be constant fading, and for a valid comparison it will be necessary to take an average of the difference between the two antennas. Occasionally, the inferior antenna will deliver a stronger signal to the receiver, but in the long run the law of averages will put the better antenna ahead.

Of course with a ground-wave signal, such as that from a station across town, there will be no fading problems. A ground-wave signal will enable the operator to properly evaluate the antenna under test in the direction of the source. The results will be valid for ionospheric-propagated signals at low elevation angles in that direction. On 28 MHz, all sky-wave signals arrive and leave at low angles. But on the lower bands, particularly 3.5 and 7 MHz, we often use signals propagated at high elevation angles, almost up to the zenith. For these angles a ground-wave test between local stations may not provide a proper evaluation of the antenna, and use of sky wave signals becomes necessary.

Dipoles

At HF the most practical indoor antenna is usually the dipole. Attempts to get more gain with parasitic elements will usually fail because of close proximity to the ground or coupling to house wiring. Beam antenna dimensions determined outdoors will not usually be valid for an attic antenna because the roof structure will cause dielectric loading of the parasitic elements. It is usually more worthwhile to spend time optimizing the location and performance of a dipole than to try to improve results with parasitic elements.

Most attics are not long enough to accommodate half-wave dipoles for 7 MHz and below. If this is the case, some folding of the dipole will be necessary. The final shape of the antenna will depend on the dimensions and configuration of the attic. Remember that the center of the dipole carries the most current and therefore does most of the radiating. This part should be as high and unfolded as possible. Because the dipole ends radiate less energy than the center, their orientation is not as important. They do carry the maximum voltage, nevertheless, so care should be taken to position the ends far enough from other conductors to avoid arcing.

The dipole may end up being L-shaped, Z-shaped, U-shaped or some indescribable corkscrew shape, depending on what space is available, but reasonable performance can often be had even with such a non-straight arrangement. **Fig 32** shows some possible configurations. Multiband operation is possible with the use of open-wire feeders and an antenna tuner.

One alternative not shown here is the aluminum-foil dipole, which was conceived by Rudy Stork, KA5FSB. He suggests mounting the dipole behind wallpaper or in the attic, with portability, ease of construction and adjustment, and economy in design among its desirable features. This antenna should also display reasonably good bandwidth resulting from the large area of its conductor material. If coaxial feed is used, some pruning of an attic antenna to establish minimum SWR at the band center will be required. Tuning the antenna outdoors and then installing it inside is usually not feasible since the behavior of the antenna will not be the same when placed in the attic. Resonance will be affected somewhat if the antenna is bent.

Even if the antenna is placed in a straight line, parasitic conductors and dielectric loading by nearby wood structures can affect the impedance. Trap and loaded dipoles are shorter than the full-sized versions, but are comparable performers. Trap dipoles are discussed in Chapter 7, Multiband Antennas, and loaded dipoles in Chapter 6, Low-Frequency Antennas.

Dipole Orientation

Theoretically a vertical dipole is most effective at low radiation angles, but practical experience shows that the horizontal dipole is usually a better indoor antenna. A high horizontal dipole does exhibit directional effects at low radiation angles, but you will not be likely to see much, if any, directivity with an attic-mounted dipole. Some operators place two dipoles at right angles to each other with provisions at the operating position for switching between the two. Their reasoning is the radiation patterns will inevitably be distorted in an unpredictable manner by nearby parasitic conductors. There will be little coupling between the dipoles if they are oriented a right


(A)
to Antenna Tuner
(B)
to Antenna Tuner
(C)
to Antenna Tuner
(D)
to Antenna Tuner
(E)
in Attic
Capacitance Hat
Single wire
Tuner
to TX
Earth Ground
(F)
in Attic
Single wire
to TX
Earth Ground

Fig 32—Various configurations for small indoor antennas. See text for discussion.

angles to each other as shown in **Figs 33A** and 33B. There will be some coupling with the arrangement shown in Fig 33C, but even this orientation is preferable to a single dipole.

With two antennas mounted 90° apart, you may find that one dipole is consistently better in nearly all directions, in which case you will want to remove the inferior dipole, perhaps placing it someplace else. In this manner the best spots in the house or attic can be determined experimentally.

Parasitic Conductors

Inevitably, any conductor in your house near a quarter wave in length or longer at the operating frequency will be parasitically coupled to your antenna. The word *parasitic* is particularly appropriate in this case because these conductors usually introduce losses and leave less energy for radiation into space. Unlike the parasitic elements in a beam antenna, conductors such as house wiring and plumbing are usually connected to lossy objects such as earth, electrical appliances, masonry or other objects that dissipate energy. Even where this energy is reradiated, it is not likely to be in the right phase in the desired direction; it is, in fact, likely to be a source of RFI.


E1
E1
C1
E1
E1
(A)
E1
C1
E1
E1
C1
E1
(B)
E1
C1
E1
E1
C1
E1
(C)

Fig 33—Ways to orient a pair of perpendicular dipoles. The orientation at A and B will result in no mutual coupling between the two dipoles, but there will be some coupling in the configuration shown at C. End (EI) and center (CI) insulators are shown.

There are, however, some things that can be done about parasitic conductors. The most obvious is to reroute them at right angles to the antenna or close to the ground, or even underground—procedures that are usually not feasible in a finished home. Where these conductors cannot be rerouted, other measures can be taken. Electrical wiring can be broken up with RF chokes to prevent the flow of radio-frequency currents while permitting 60-Hz current (or audio, in the case of telephone wires) to flow unimpeded. A typical RF choke for a power line can be 100 turns of #10 insulated wire close wound on a length of 1-inch diameter plastic pipe. Of course one choke will be needed for each conductor. A three-wire line calls for three chokes. The chokes can be simplified by winding them bifilar or trifilar on a single coil form.

THE RESONANT BREAKER

Obviously, RF chokes cannot be used on conductors such as metal conduit or water pipes. But it is still possible, surprising as it may seem, to obstruct RF currents on such conductors without breaking the metal. The resonant breaker was first described by Fred Brown, W6HPH, in Oct 1979 *QST*.



Fig 34—A "resonant breaker" such as shown here can be used to obstruct radio-frequency currents in a conductor without the need to break the conductor physically. A vernier dial is recommended for use with the variable capacitor because tuning is quite sharp. The 100-pF capacitor is in series with the loop. This resonant breaker tunes from 14 through 29.7 MHz. Larger models may be constructed for the lower frequency bands.

Fig 34 shows a method of accomplishing this. A figure-eight loop is inductively coupled to the parasitic conductor and is resonated to the desired frequency with a variable capacitor. The result is a very high impedance induced in series with the pipe, conduit or wire. This impedance will block the flow of radio-frequency currents. The figure-eight coil can be thought of as two turns of an air-core toroid and since the parasitic conductor threads through the hole of this core, there will be tight coupling between the two. Inasmuch as the figure-eight coil is parallel resonated, transformer action will reflect a high impedance in series with the linear conductor.

Before you bother with a *resonant breaker* of this type, be sure that there is a significant amount of RF current flowing in the parasitic conductor, and that you will therefore benefit from installing one. The relative magnitude of this current can be determined with an RF current probe of the type described in Chapter 27, Antenna and Transmission-Line Measurements. According to the rule of thumb regarding parasitic conductor current, if it measures less than $^1/_{10}$ of that measured near the center of the dipole, the parasitic current is generally not large enough to be of concern.

The current probe is also needed for resonating the breaker after it is installed. Normally, the resonant breaker will be placed on the parasitic conductor near the point of maximum current. When it is tuned through resonance, there will be a sharp dip in RF current, as indicated by the current probe. Of course, the resonant breaker will be effective only on one band. You will need one for each band where there is significant current indicated by the probe.

Power-Handling Capability

So far, our discussion have not considered the full power-handling capability of an indoor antenna. Any tendency to flash over must be determined by running full power or, preferably, somewhat more than the peak power you intend to use in regular operation. The antenna should be carefully checked for arcing or RF heating before you do any operating. Bear in mind that attics are indeed vulnerable to fire hazards. A potential of several hundred volts exists at the ends of a dipole fed by the typical Amateur Radio transmitter. If a power amplifier is used, there could be a few thousand volts at the ends of the dipole. Keep your antenna elements well away from other objects. *Safety first*!

Construction Details and Practical Considerations

Ultimately the success of an antenna project depends on the details of how the antenna is fabricated. A great deal of construction information is given in other chapters of this book. For example the construction of HF Yagis is discussed in Chapter 11, Quad arrays in Chapter 12, VHF antennas in Chapter 18, and in Chapter 20 there is an excellent discussion of antenna materials, particularly wire and tubing for elements. Here is still more helpful antenna construction information.

END EFFECT

If the standard expression $\lambda/2 \approx 491.8/f$ (MHz) is used for the length of a $\lambda/2$ wire antenna, the antenna will resonate at a somewhat lower frequency than is desired. The reason is that in addition to the effect of the conductor diameter and ground effects (Chapter 3, The Effects of Ground) an additional "loading" effect is caused by the insulators used at the ends of the wires to support the antenna. The insulators and the wire loops that tie the insulators to the antenna add a small amount of capacitance to the system. This capacitance helps to tune the antenna to a slightly lower frequency, in much the same way that additional capacitance in any tuned circuit lowers the resonant frequency. In an antenna this is called *end effect*. The current at the ends of the antenna does not quite reach zero because of the end effect, as there is some current flowing into the end capacitance. Note that the computations used to create Figs 2 through 7 in Chapter 2, Antenna Fundamentals, did not take into account any end effect.

End effect increases with frequency and varies slightly with different installations. However, at frequencies up to 30 MHz (the frequency range over which wire antennas are most commonly used), experience shows that the length of a practical $\lambda/2$ antenna, including the effect of diameter and end effect, is on the order of 5% less than the length of a half wave in space. As an average, then, the physical length of a resonant $\lambda/2$ wire antenna can be found from:

$$\lambda = \frac{491.8 \times 0.95}{f\ (\text{MHz})} \approx \frac{468}{f\ (\text{MHz})} \qquad \text{(Eq 1)}$$

Eq 1 is reasonably accurate for finding the physical length of a $\lambda/2$ antenna for a given frequency, but does not apply to antennas longer than a half wave in length. In the practical case, if the antenna length must be adjusted to exact frequency (not all antenna systems require it) the length should be "pruned" to resonance. Note that the use of plastic-insulated wire will typically lower the resonant frequency of a half-wave dipole about 3%.

INSULATORS

Wire antennas must be insulated at the ends. Commercially available insulators are made from ceramic, glass or plastic. Insulators are available from many Amateur Radio dealers. RadioShack and local hardware stores are other possible sources. Acceptable homemade insulators may be fashioned from a variety of material including (but not limited to) acrylic sheet or rod, PVC tubing, wood, fiberglass rod or even stiff plastic from a discarded container. **Fig 35** shows some homemade insulators. Ceramic or glass insulators will usually outlast the wire, so they are highly recommended for a safe, reliable, permanent installation. Other materials may tear under stress or break down in the presence of sunlight. Many types of plastic do not weather well.



Fig 35—Some ideas for homemade antenna insulators.

INSTALLING TRANSMISSION LINES

Many wire antennas require an insulator at the feed point. Although there are many ways to connect the feed line, there are a few things to keep in mind. If you feed your antenna with coaxial cable, you have two choices. You can install an SO-239 connector on the center insu-



Fig 36—Some homemade dipole center insulators. The one in the center includes a built-in SO-239 connector. Others are designed for direct connection to the feed line.


Insulator
Eye
Loop
Not Snug
(A)
Coax Wrapped
Around Insulator
Insulator
Braid
Inner
Conductor
This point should
be sealed to keep
moisture out of coax.
Coax
Coax
Rope to
Support
Insulator
Clamp
(B)

Fig 37—Details of dipole antenna construction. At A, the end insulator connection is shown. At B, the completed antenna is shown. A balun (not shown) is often used at the feed point, since this is a balanced antenna.

lator, as shown by the center example in **Fig 36,** and use a PL-259 on the end of your coax, or you can separate the center conductor from the braid and connect the feed line directly to the antenna wire as shown in the other two examples in Fig 36 and the example in **Fig 37**. Although it costs less to connect direct, the use of connectors offers several advantages. Coaxial cable braid soaks up water like a sponge unless it is very well waterproofed. If you do not adequately seal the antenna end of the feed line, water will find its way into the braid. Water in the feed line will lead to contamination, rendering the coax useless long before its normal lifetime is up. Many hams waterproof the coax, first with vinyl electrical tape, and then using a paint-on material called "PlastiDip," which is sold by RadioShack (part number 910-5166 for the white variety).

It is not uncommon for water to drip from the end of the coax inside the shack after a year or so of service if the antenna connection is not properly waterproofed. Use of a PL-259/SO-239 combination (or connector of your choice) makes the task of waterproofing connections much easier. Another advantage to using the PL-259/SO-239 combination is that feed-line replacement is much easier, should that become necessary.

Whether you use coaxial cable, ladder line, or twin lead to feed your antenna, an often overlooked consideration is the mechanical strength of the connection. Wire antennas and feed lines tend to move a lot in the breeze, and


Plexiglas "T"
Antenna Wire
Antenna Wire
(Loop through holes)
Secure to Plexiglas with
Electrical Tape
450-ohm Ladder Line
To Antenna Tuner

Fig 38—A piece of cut Plexiglas can be used as a center insulator and to support a ladder-line feeder. The Plexiglas acts to reduce the flexing of the wires where they connect to the antenna. Use thick Plexiglas in areas subject to high winds.

unless the feed line is attached securely, the connection will weaken with time. The resulting failure can range from a frustrating intermittent electrical connection to a complete separation of feed line and antenna. Fig 37 and **Fig 38** illustrate different ways of attaching either coax or ladder line to the antenna securely.

When open-wire feed line is used, the conductors of the line should be anchored to the insulator by threading them through the eyes of the insulator two or three times, and twisting the wire back on itself before soldering. A slack tie wire should then be used between the feeder conductor and the antenna, as shown in Fig 38. (The tie wires may be extensions of the line conductors themselves.) When window-type line is suspended from an antenna in a manner such as that shown in Fig 38, the line should be twisted—at several twists per foot—to prevent stress hardening of the wire because of constant flexing in the wind.

When using plastic-insulated open-wire line, the tendency of the line to twist and short out close to the antenna can be counteracted by making the center insulator of the antenna longer than the spacing of the line, as shown in Fig 38. In severe wind areas, it may be necessary to use ¼-inch thick Plexiglas for the center insulator rather than thinner material.

RUNNING THE FEED LINE FROM THE ANTENNA TO THE STATION

Chapter 24, Transmission Lines, contains some general guidelines for installing feed lines. More detailed information is contained in this section. Whenever possible, the transmission line should be lead away from the antenna at a 90° angle to minimize coupling from the antenna to the transmission line. This coupling can cause unequal currents on the transmission line, which will then radiate and it can detune the antenna.

Except for the portion of the line in close proximity to the antenna, coaxial cable requires no particular care in running from the antenna to the station entrance, other than protection from mechanical damage. If the antenna is not supported at the center, the line should be fastened to a post more than head high located under the center of the antenna, allowing enough slack between the post and the antenna to take care of any movement of the antenna in the wind. If the antenna feed point is supported by a tower or mast, the cable can be taped to the mast at intervals or to one leg of the tower.

Coaxial cable rated for direct burial can be buried a few inches in the ground to make the run from the antenna to the station. A deep slit can be cut by pushing a square-end spade full depth into the ground and moving the handle back and forth to widen the slit before removing the spade. After the cable has been pushed into the slit with a piece of 1-inch board 3 or 4 inches wide, the slit can be tamped closed. Many hams run coax cables through PVC pipe buried in the ground deeper than the frost line and slanted downwards slightly so that water will drain, rather than pooling inside the length of the pipe.



Fig 39—A support for open-wire line. The support at the antenna end of the line must be sufficiently rigid to stand the tension of the line.

Solid ribbon or the newer *window* types of line should be kept reasonably well spaced from other conductors running parallel to it for more than a few feet. TV-type standoff insulators with strap clamp mountings can be used for running this type of line down a mast or tower leg. Similar insulators of the screw-in type can be used in supporting the line on wooden poles for a long run.

Open-wire lines with bare conductors require frequent supports to keep the lines from twisting and shorting out, as well as to relieve the mechanical strain. One method of supporting a long horizontal run of heavy open-wire line is shown in **Fig 39**. The line must be anchored securely at a point under the feed point of the antenna. Window-type line can be supported similarly with wire links fastened to the insulators or with black cable ties (ones not affected by UV radiation from the sun).

To keep the line clear of pedestrians and vehicles, it is usually desirable to anchor the feed line at the eaves or rafter line of the station building (see **Fig 40**), and then drop it vertically to the point of entrance. The points of anchorage and entrance should be chosen to permit the vertical drop without crossing windows for aesthetic reasons.

If the station is located in a room on the ground floor, one way of bringing coax transmission line into the house is to go through the outside wall below floor level, feed it through the basement or crawl space and then up to the station through a hole in the floor. When making the entrance hole in the side of the building, suitable measurements should be made in advance to be sure the hole will go through the sill 2 or 3 inches above the foundation line (and between joists if the bore is parallel to the joists). The line should be allowed to sag below the entrance hole level outside the building to allow rain water to drip off.

Open-wire line can be fed in a similar manner, although it will require a separate hole for each conductor. Each hole should be insulated with a length of polystyrene or Lucite tubing. If available, ceramic tubes salvaged from old-fashioned *knob and tube* electrical



Fig 40—Anchoring open-wire line at the station end. The springs are especially desirable if the line is not supported between the antenna and the anchoring point.



Fig 41—An adjustable window lead-in panel made up of two sheets of Lucite or Plexiglas. A feedthrough connector for coax line can be made as shown in Fig 28. Ceramic feedthrough insulators are suitable for open-wire line. (W1RVE)

installations, work very well for this purpose. Drill the holes with a slight downward slant toward the outside of the building to prevent rain seepage. With window ladder line, it will be necessary to remove a few of the spreader insulators, cut the line before passing through the holes (allowing enough length to reach the inside) and splice the remainder on the inside.



Fig 42—Feedthrough connector for coax line. An Amphenol 83-1J (PL-258) connector, the type used to splice sections of coax line together, is soldered into a hole cut in a brass mounting flange. An Amphenol bulkhead adapter 83-1F may be used instead.

If the station is located above ground level, or if there is other objection to the procedure described above, entrance can be made at a window, using the arrangement shown in **Fig 41**. An Amphenol type 83-1F (UG-363) connector can be used as shown in **Fig 42**; ceramic feedthrough insulators can be used for open-wire line. Ribbon line can be run through clearance holes in the panel, and secured by a winding of tape on either side of the panel, or by cutting the retaining rings and insulators from a pair of TV standoff insulators and clamping one on each side of the panel.

LIGHTNING PROTECTION

Two or three types of lightning arresters for coaxial cable are available on the market. If the antenna feed point is at the top of a well-grounded tower, the arrester can be fastened securely to the top of the tower for grounding purposes. A short length of cable, terminated in a coaxial plug, is then run from the antenna feed point to one receptacle of the arrester, while the transmission line is run from the other arrester receptacle to the station. Such arresters may also be placed at the entrance point to the station, if a suitable ground connection is available at that point (or arresters may be placed at both points for added insurance).



Fig 43—A simple lightning arrester for open-wire line made from three standoff or feedthrough insulators and sections of $^1/_8 \times ^1/_2$-inch brass or copper strap. It should be installed in the line at the point where the line enters the station. The heavy ground lead should be as short and as direct as possible. The gap setting should be adjusted to the minimum width that will prohibit arcing when the transmitter is operated.


Line to Ant.
Wire Soldered to Line Conductor
TV Standoff
TV Standoff
Insulation Removed from Ribbon Line
Line to Station

Fig 44—The lightning arrester of Fig 39 may be used with 300-Ω ribbon line in the manner shown here. The TV standoffs support the line an inch or so away from the grounded center member of the arrester

The construction of a homemade arrester for open-wire line is shown in **Fig 43**. This type of arrester can be adapted to ribbon line an inch or so away from the center member of the arrester, as shown in **Fig 44**. Sufficient insulation should be removed from the line where it crosses the arrester to permit soldering the arrester connecting leads.

Lightning Grounds

Lightning-ground connecting leads should be of conductor size equivalent to at least #10 wire. The #8 aluminum wire used for TV-antenna grounds is satisfactory. Copper braid $^3/_4$-inch wide (Belden 8662-10) is also suitable. The conductor should run in a straight line to the grounding point. The ground connection may be made to a water pipe system (if the pipe is not plastic), the grounded metal frame of a building, or to one or more $^5/_8$-inch ground rods driven to a depth of at least 8 feet. More detailed information on lightning protection is contained in Chapter 1, Safety.

A central grounding panel for coax cables coming into the house is highly recommended. See **Fig 45** for a photo of the homemade grounding panel installed by Chuck Hutchinson, K8CH, at his Michigan home. The coax cables screwed into dual-female feed-through UHF connectors. K8CH installed this aluminum panel under the outside grill for a duct that provided combustion air to an unused fireplace. He used ground strap to connect to ground rods located under the panel. See the ARRL book *Simple and Fun Antennas* for more information about ground panels.



Fig 45—K8CH's coax entry panel mounted on exterior wall (later covered by grill that provides combustion to an unused fireplace). The ground braid goes to a ground rod located beneath the panel. (Photo courtesy: *Simple and Fun Antennas for Hams*)

Before a lightning storm approaches, a prudent ham will disconnect all feed lines, rotor lines and control lines inside the shack to prevent damage to sensitive electronics. When lightning is crashing about outside, you certainly don't want that lightning inside your shack!

Chapter 5

Loop Antennas

A loop antenna is a closed-circuit antenna—that is, one in which a conductor is formed into one or more turns so its two ends are close together. Loops can be divided into two general classes, those in which both the total conductor length and the maximum linear dimension of a turn are very small compared with the wavelength, and those in which both the conductor length and the loop dimensions begin to be comparable with the wavelength.

A "small" loop can be considered to be simply a rather large coil, and the current distribution in such a loop is the same as in a coil. That is, the current has the same phase and the same amplitude in every part of the loop. To meet this condition, the total length of conductor in the loop must not exceed about 0.1 λ. Small loops are discussed later in this chapter, and further in Chapter 14, Direction Finding Antennas.

A "large" loop is one in which the current is not the same either in amplitude or phase in every part of the loop. This change in current distribution gives rise to entirely different properties compared with a small loop.

Half-Wave Loops

The smallest size of "large" loop generally used is one having a conductor length of $^{1}/_{2}\ \lambda$. The conductor is usually formed into a square, as shown in **Fig 1**, making each side $^{1}/_{8}\ \lambda$ long. When fed at the center of one side, the current flows in a closed loop as shown in Fig 1A. The current distribution is approximately the same as on a $^{1}/_{2}\ \lambda$ wire, and so is maximum at the center of the side opposite the terminals X-Y, and minimum at the terminals themselves. This current distribution causes the field strength to be maximum in the plane of the loop and in the direction looking from the low-current side to the high-current side. If the side opposite the terminals is opened at the center as shown in Fig 1B (strictly speaking, it is then no longer a loop because it is no longer a closed circuit), the direction of current flow remains unchanged but the maximum current flow occurs at the terminals. This reverses the direction of maximum radiation.

The radiation resistance at a current antinode (which is also the resistance at X-Y in Fig 1B) is on the order of 50 Ω. The impedance at the terminals in Fig 1A is a few thousand ohms. This can be reduced by using two identical loops side by side with a few inches spacing between them and applying power between terminal X on one loop and terminal Y on the other.

Unlike a $^{1}/_{2}\ \lambda$ dipole or a small loop, there is no direction in which the radiation from a loop of the type shown in Fig 1 is zero. There is appreciable radiation in the direction perpendicular to the plane of the loop, as well as to the "rear"—the opposite direction to the arrows shown. The front-to-back (F/B) ratio is approximately 4 to 6 dB. The small size and the shape of the directive pattern result in a loss of about 1 dB when the field strength in the optimum direction from such a



Fig 1—Half-wave loops, consisting of a single turn having a total length of $^{1}/_{2}\ \lambda$.

loop is compared with the field from a $^1/_2$ λ dipole in its optimum direction.

The ratio of the forward radiation to the backward radiation can be increased, and the field strength likewise increased at the same time to give a gain of about 1 dB over a dipole, by using inductive reactances to “load” the sides joining the front and back of the loop. This is shown in **Fig 2**. The reactances, which should have a value of approximately 360 Ω, decrease the current in the sides in which they are inserted and increase it in the side having terminals. This increases the directivity and thus increases the efficiency of the loop as a radiator. Lossy coils can reduce this advantage greatly.

One-Wavelength Loops

Loops in which the conductor length is 1 λ have different characteristics than $^1/_2$-λ loops. Three forms of 1 λ loops are shown in **Fig 3**. At A and B the sides of the squares are equal to $^1/_4$ λ, the difference being in the point at which the terminals are inserted. At C the sides of the triangle are equal to $^1/_3$ λ. The relative direction of current flow is as shown in the drawings. This direction reverses halfway around the perimeter of the loop, as such reversals always occur at the junction of each $^1/_2$-λ section of wire.

The directional characteristics of loops of this type are opposite in sense to those of a small loop. That is, the radiation is maximum perpendicular to the plane of the loop and is minimum in either direction in the plane containing the loop. If the three loops shown in Fig 3 are mounted in a vertical plane with the terminals at the bottom, the radiation is horizontally polarized. When the terminals are moved to the center of one vertical side in Fig 3A, or to a side corner in B, the radiation is vertically polarized. If the terminals are moved to a side corner in C, the polarization will be diagonal, containing both vertical and horizontal components.

In contrast to straight-wire antennas, the electrical length of the circumference of a 1-λ loop is shorter than the actual length. For a loop made of bare #18 wire and operating at a frequency of 14 MHz, where the ratio of conductor length to wire diameter is large, the loop will be close to resonance when

$$\text{Length}_{\text{feet}} = \frac{1032}{f_{\text{MHz}}}$$

The radiation resistance of a resonant 1 λ loop is approximately 120 Ω, under these conditions. Since the loop dimensions are larger than those of a $^1/_2$-λ dipole, the radiation efficiency is high.



Fig 2—Inductive loading in the sides of a $^1/_2$-λ loop to increase the directivity and gain. Maximum radiation or response is in the plane of the loop, in the direction shown by the arrow.



Fig 3—At A and B, loops having sides $^1/_4$ λ long, and at C having sides $^1/_3$ λ long (total conductor length 1 λ). The polarization depends on the orientation of the loop and on the position of the feed point (terminals X-Y) around the perimeter of the loop.

In the direction of maximum radiation (that is, broadside to the plane of the loop, regardless of the point at which it is fed) the 1-λ loop will show a small gain over a $^1/_2$-λ dipole. Theoretically, this gain is about 1 dB, and measurements have confirmed that it is of this order.

The 1-λ loop is more frequently used as an element of a directive antenna array (the quad and delta-loop antennas described in Chapter 12, Quad Arrays) than singly, although there is no reason why it cannot be used alone. In the quad and delta loop, it is nearly always driven so that the polarization is horizontal.

Small Loop Antennas

The electrically small loop antenna has existed in various forms for many years. Probably the most familiar form of this antenna is the ferrite *loopstick* found in portable AM broadcast-band receivers. Amateur applications of the small loop include direction finding, low-noise directional receiving antennas for 1.8 and 3.5 MHz, and small transmitting antennas. Because the design of transmitting and receiving loops requires some different considerations, the two situations are examined separately in this section. This information was written by Domenic M. Mallozzi, N1DM.

The Basic Loop

What is and what is not a small loop antenna? By definition, the loop is considered to be electrically small when its total conductor length is less than 0.1 λ—0.085 is the number used in this section. This size is based on the fact that the current around the perimeter of the loop must be in phase. When the winding conductor is more than about 0.085 λ long, this is no longer true. This constraint results in a very predictable figure-eight radiation pattern, shown in **Fig 4**.

The simplest loop is a 1-turn untuned loop with a load connected to a pair of terminals located in the center of one of the sides, as shown in **Fig 5**. How its pattern is developed is easily pictured if we look at some "snapshots" of the antenna relative to a signal source. **Fig 6** represents a loop from above, and shows the instantaneous radiated voltage wave. Note that points A and B of the loop are receiving the same instantaneous voltage. This means that no current will flow through the loop, because there is no current flow between points of equal potential. A similar analysis of **Fig 7**, with the loop turned 90° from the position represented in Fig 6, shows that this position of the loop provides maximum response. Of course, the voltage derived from the passing wave is small because of the small physical size of the loop. Fig 4 shows the ideal radiation pattern for a small loop.

The voltage across the loop terminals is given by

$$V = \frac{2\,\pi A\ N\ E \cos\theta}{\lambda} \tag{Eq 1}$$

where

V = voltage across the loop terminals
A = area of loop in square meters
N = number of turns in the loop
E = RF field strength in volts per meter
θ = angle between the plane of the loop and the signal source (transmitting station)
λ = wavelength of operation in meters



Fig 4—Calculated small loop antenna radiation pattern.



Fig 5—Simple untuned small loop antenna.



Fig 6—Example of orientation of loop antenna that does not respond to a signal source (null in pattern).



Fig 7—Example of orientation of loop antenna for maximum response.

This equation comes from a term called *effective height*. The effective height refers to the height (length) of a vertical piece of wire above ground that would deliver the same voltage to the receiver. The equation for effective height is

$$h = \frac{2\pi N A}{\lambda} \qquad \text{(Eq 2)}$$

where h is in meters and the other terms are as for Eq 1.

A few minutes with a calculator will show that, with the constraints previously stated, the loop antenna will have a very small effective height. This means it will deliver a relatively small voltage to the receiver, even with a large transmitted signal.

TUNED LOOPS

We can tune the loop by placing a capacitor across the antenna terminals. This causes a larger voltage to appear across the loop terminals because of the Q of the parallel resonant circuit that is formed.

The voltage across the loop terminals is now given by

$$V = \frac{2\pi A N E Q \cos\theta}{\lambda} \qquad \text{(Eq 3)}$$

where Q is the loaded Q of the tuned circuit, and the other terms are as defined above.

Most amateur loops are of the tuned variety. For this reason, all comments that follow are based on tuned-loop antennas, consisting of one or more turns. The tuned-loop antenna has some particular advantages. For example, it puts high selectivity up at the “front” of a receiving system, where it can significantly help factors such as dynamic range. Loaded Q values of 100 or greater are easy to obtain with careful loop construction.

Consider a situation where the inherent selectivity of the loop is helpful. Assume we have a loop with a Q of 100 at 1.805 MHz. We are working a DX station on 1.805 MHz and are suffering strong interference from a local station 10 kHz away. Switching from a dipole to a small loop will reduce the strength of the off-frequency signal by 6 dB (approximately one S unit). This, in effect, increases the dynamic range of the receiver. In fact, if the off-frequency station were further off frequency, the attenuation would be greater.

Another way the loop can help is by using the nulls in its pattern to null out on-frequency (or slightly off-frequency) interference. For example, say we are working a DX station to the north, and just 1 kHz away is another local station engaged in a contact. The local station is to our west. We can simply rotate our loop to put its null to the west, and now the DX station should be readable while the local will be knocked down by 60 or more dB. This obviously is quite a noticeable difference. Loop nulls are very sharp and are generally noticeable only on ground-wave signals (more on this later).

Of course, this method of nulling will be effective only if the interfering station and the station being worked are not in the same direction (or in exact opposite directions) from our location. If the two stations were on the same line from our location, both the station being worked and the undesired station would be nulled out. Luckily the nulls are very sharp, so as long as the stations are at least 10° off axis from each other, the loop null will be usable.

A similar use of the nulling capability is to eliminate local noise interference, such as that from a light dimmer in a neighbor’s house. Just put the null on the offending light dimmer, and the noise should disappear.

Now that we have seen some possible uses of the small loop, let us look at a bit of detail about its design. First, the loop forms an inductor having a very small ratio of winding length to diameter. The equations for finding inductance given in most radio handbooks assume that the inductor coil is longer than its diameter. However, F. W. Grover of the US National Bureau of Standards has provided equations for inductors of common cross-sectional shapes and small length-to-diameter ratios. (See the Bibliography at the end of this chapter.) Grover’s equations are shown in **Table 1**. Their use will yield relatively accurate numbers; results are easily worked out with a scientific calculator or home computer.

The value of a tuning capacitor for a loop is easy to calculate from the standard resonance equations. The only matter to consider before calculating this is the value of distributed capacitance of the loop winding. This capacitance shows up between adjacent turns of the coil because of their slight difference in potential. This causes each turn to appear as a charge plate. As with all other capacitances, the value of the distributed capacitance is based on the physical dimensions of the coil. An exact mathematical analysis of its value is a complex problem. A simple approximation is given by Medhurst (see Bibliography) as:

$$C = HD \qquad \text{(Eq 4)}$$

where

C = distributed capacitance in pF

H = a constant related to the length-to-diameter ratio of the coil (**Table 2** gives H values for length-to-diameter ratios used in loop antenna work.)

D = diameter of the winding in cm

Medhurst's work was with coils of round cross section. For loops of square cross section the distributed capacitance is given by Bramslev (see Bibliography) as

$$C = 60S \qquad \text{(Eq 5)}$$

where

C = the distributed capacitance in pF

S = the length of the side in meters

If you convert the length in this equation to centimeters, you will find Bramslev's equation gives results in the same order of magnitude as Medhurst's equation.

This distributed capacitance appears as if it were a capacitor across the loop terminals. Therefore, when determining the value of the tuning capacitor, the distributed capacitance must be subtracted from the total capacitance required to resonate the loop. The distributed capacitance also determines the highest frequency at which a particular loop can be used, because it is the minimum capacitance obtainable.

Electrostatically Shielded Loops

Over the years, many loop antennas have incorporated an electrostatic shield. This shield generally takes the form of a tube around the winding, made of a conductive but non-magnetic material (such as copper or aluminum). Its purpose is to maintain loop balance with respect to ground, by forcing the capacitance between all portions of the loop and ground to be identical. This is illustrated in **Fig 8**. It is necessary to maintain electrical loop balance to eliminate what is referred to as the *antenna effect*. When the antenna becomes unbalanced it appears to act partially as a small vertical antenna. This vertical pattern gets superimposed on the ideal figure-eight pattern, distorting the pattern and filling in the nulls. The type of pattern that results is shown in **Fig 9**.

Adding the shield has the effect of somewhat reducing the pickup of the loop, but this loss is generally offset by the increase in null depth of the loops. Proper balance of the loop antenna requires that the load on the loop also be balanced. This is usually accomplished by use of a balun transformer or a balanced input preamplifier. One important point regarding the shield is that it cannot form a continuous electrical path around the loop perimeter, or it will appear as a shorted coil turn. Usually the insulated break is located opposite the feed point to maintain symmetry. Another point to be considered is that the shield should be of a much larger diameter than the loop winding, or it will lower the Q of the loop.

Various construction techniques have been used in

Table 1

Inductance Equations for Short Coils (Loop Antennas)

Triangle:

$$L\,(\mu H) = 0.006N^2\,s \left[\ln\left(\frac{1.1547\,sN}{(N+1)\,\ell}\right) + 0.65533 + \frac{0.1348\,(N+1)\,\ell}{sN}\right]$$

Square:

$$L\,(\mu H) = 0.008N^2\,s \left[\ln\left(\frac{1.4142sN}{(N+1)\ell}\right) + 0.37942 + \frac{0.3333(N+1)\ell}{sN}\right]$$

Hexagon:

$$L\,(\mu H) = 0.012N^2\,s \left[\ln\left(\frac{2sN}{(N+1)\ell}\right) + 0.65533 + \frac{0.1348(N+1)\ell}{sN}\right]$$

Octagon:

$$L\,(\mu H) = 0.016N^2 \left[\ln\left(\frac{2.613sN}{(N+1)\ell}\right) + 0.75143 + \frac{0.07153(N+1)\ell}{sN}\right]$$

where

N = number of turns

s = side length in cm

ℓ = coil length in cm

Note: In the case of single-turn coils, the diameter of the conductor should be used for ℓ.

Table 2

Values of the Constant H for Distributed Capacitance

Length to Diameter Ratio	*H*
0.10	0.96
0.15	0.79
0.20	0.78
0.25	0.64
0.30	0.60
0.35	0.57
0.40	0.54
0.50	0.50
1.00	0.46



Fig 8—At A, the loop is unbalanced by capacitance to its surroundings. At B, the use of an electrostatic shield overcomes this effect.



Fig 9—Distortion in loop pattern resulting from antenna effect.

making shielded loops. Genaille located his loop winding inside aluminum conduit, while True constructed an aluminum shield can around his winding. Others have used pieces of Hardline to form a loop, using the outer conductor as a shield. DeMaw used flexible coax with the shield broken at the center of the loop conductor in a multiturn loop for 1.8 MHz. Goldman uses another shielding method for broadcast receiver loops. His shield is in the form of a barrel made of hardware cloth, with the loop in its center. (See Bibliography for above references.) All these methods provide sufficient shielding to maintain the balance. It is possible, as Nelson shows, to construct an unshielded loop with good nulls (60 dB or better) by paying great care to symmetry.

LOOP Q

As previously mentioned, Q is an important consideration in loop performance because it determines both the loop bandwidth and its terminal voltage for a given field strength. The loaded Q of a loop is based on four major factors. These are (1) the intrinsic Q of the loop winding, (2) the effect of the load, (3) the effect of the electrostatic shield, and (4) the Q of the tuning capacitor.

The major factor is the Q of the winding of the loop itself. The ac resistance of the conductor caused by skin effect is the major consideration. The ac resistance for copper conductors may be determined from

$$R = \frac{0.996 \times 10^{-6} \sqrt{f}}{d} \qquad \text{(Eq 6)}$$

where

R = resistance in ohms per foot
f = frequency, Hz
d = conductor diameter, inches

The Q of the inductor is then easily determined by taking the reactance of the inductor and dividing it by the ac resistance. If you are using a multiturn loop and are a perfectionist, you might also want to include the loss from conductor proximity effect. This effect is described in detail later in this chapter, in the section on transmitting loops.

Improvement in Q can be obtained in some cases by the use of Litz wire (short for *Litzendraht*). Litz wire consists of strands of individual insulated wires that are woven into bundles in such a manner that each conductor occupies each location in the bundle with equal frequency. Litz wire results in improved Q over solid or stranded wire of equivalent size, up to about 3 MHz.

Also, the Q of the tuned circuit of the loop antenna is determined by the Q of the capacitors used to resonate it. In the case of air variables or dipped micas this is not usually a problem. But if variable-capacitance diodes are used to remotely tune the loop, pay particular attention to the manufacturer's specification for Q of the diode at the frequency of operation. The tuning diodes can have a significant effect on circuit Q.

Now we consider the effect of load impedance on loop Q. In the case of a directly coupled loop (as in Fig 5), the load is connected directly across the loop terminals, causing it to be treated as a parallel resistance in a parallel-tuned RLC circuit. Obviously, if the load is of a low value, the Q of the loop will be low. A simple way to correct this is to use a transformer to step up the load impedance that appears across the loop terminals. In fact, if we make this transformer a balun, it also allows us to use our unbalanced receivers with the loop and maintain loop symmetry. Another solution is to use what is referred to as an inductively coupled loop, such as DeMaw's four turn electrostatically shielded loop. A one-turn link is connected to the receiver. This turn is wound with the four-turn loop. In effect, this builds the transformer into the antenna.

Another solution to the problem of load impedance on loop Q is to use an active preamplifier with a high impedance balanced input and unbalanced output. This method also has the advantage of amplifying the low-level output voltage of the loop to where it can be used with a receiver of even mediocre sensitivity. In fact, the Q of the loop when used with a balanced preamplifier having high input impedance may be so high as to be unusable in certain applications. An example of this situation would occur where a loop is being used to receive a 5 kHz wide AM signal at a frequency where the bandwidth of the loop is only 1.5 kHz. In this case the detected audio might be very distorted. The solution to this is to put a Q-degrading resistor across the loop terminals.

FERRITE-CORE LOOP ANTENNAS

The ferrite-core loop antenna is a special case of the air-core receiving loops considered up to now. Because of its use in every AM broadcast-band portable radio, the ferrite-core loop is, by quantity, the most popular form of the loop antenna. But broadcast-band reception is far from its only use; it is commonly found in radio-direction-finding equipment and low-frequency-receiving systems (below 500 kHz) for time and frequency standard systems. In recent years, design information on these types of antennas has been a bit sparse in the amateur literature, so the next few paragraphs are devoted to providing some details.

Ferrite-loop antennas are characteristically very small compared to the frequency of use. For example, a 3.5-MHz version may be in the range of 15 to 30 cm long and about 1.25 cm in diameter. Earlier in this chapter, effective height was introduced as a measure of loop sensitivity. The effective height of an air-core loop antenna is given by Eq 2.



Fig 10—At A, an air-core loop has no effect on nearby field lines. B illustrates the effect of a ferrite core on nearby field lines. The field is altered by the reluctance of the ferrite material.

If an air-core loop is placed in a field, in essence it cuts the lines of flux without disturbing them (**Fig 10A**). On the other hand, when a ferrite (magnetic) core is placed in the field, the nearby field lines are redirected into the loop (Fig 10B). This is because the reluctance of the ferrite material is less than that of the surrounding air, so the nearby flux lines tend to flow through the loop rather than passing it by. (Reluctance is the magnetic analogy of resistance, while flux is analogous to current.) The reluctance is inversely proportional to the permeability of the rod core, μ_{rod}. (In some texts the rod permeability is referred to as effective permeability, μ_{eff}). This effect modifies the equation for effective height of a ferrite-core loop to

$$h = \frac{2 \pi N A \mu_{rod}}{\lambda} \quad \text{(Eq 7)}$$

where

h = effective height (length) in meters
N = number of turns in the loop
A = area of loop in square meters
μ_{rod} = permeability of the ferrite rod
λ = wavelength of operation in meters

This obviously is a large increase in "collected" signal. If the rod permeability were 90, this would be the same as making the loop area 90 times larger with the same number of turns. For example, a 1.25-cm diameter ferrite-core loop would have an effective height equal to an air-core loop 22.5 cm in diameter (with the same number of turns).

By now you might have noticed we have been very careful to refer to rod permeability. There is a very important reason for this. The permeability that a rod of ferrite exhibits is a combination of the material permeability or μ, the shape of the rod, and the dimensions of the rod. In ferrite rods, μ is sometimes referred to as initial permeability, μ_i, or toroidal permeability, μ_{tor}. Because most amateur ferrite loops are in the form of rods, we will discuss only this shape.

The reason that μ_{rod} is different from μ is a very complex physics problem that is well beyond the scope of this book. For those interested in the details, books by Polydoroff and by Snelling cover this subject in considerable detail. (See Bibliography.) For our purposes a simple explanation will suffice. The rod is in fact not a perfect director of flux, as is illustrated in **Fig 11**. Note that some lines impinge on the sides of the core and also exit from the sides. These lines therefore would not pass through all the turns of the coil if it were wound from one end of the core to the other. These flux lines are referred to as *leakage flux*, or sometimes as flux leakage.

Leakage flux causes the flux density in the core to be nonuniform along its length. From Fig 11 it can be seen that the flux has a maximum at the geometric center of the length of the core, and decreases as the ends of the core are approached. This causes some noticeable effects. As a short coil is placed at different locations along a long core, its inductance will change. The maximum inductance exists when the coil is centered on the rod. The Q of a short coil on a long rod is greatest at the center. On the other hand, if you require a higher Q than this, it is recommended that you spread the coil turns along the whole length of the core, even though this will result in a lower value of inductance. (The inductance can be increased to the original value by adding turns.) **Fig 12** gives the relationship of rod permeability to material permeability for a variety of values.

The change in μ over the length of the rod results in an adjustment in the term μ_{rod} for its so called "free ends" (those not covered by the winding). This adjustment factor is given by

$$\mu' = \mu_{rod} \sqrt[3]{\frac{a}{b}} \qquad \text{(Eq 8)}$$

where

μ' = the corrected permeability
a = the length of the core
b = the length of the coil

This value of μ' should be used in place of μ_{rod} in Eq 7 to obtain the most accurate value of effective height.

All these variables make the calculation of ferrite loop antenna inductance somewhat less accurate than for the air-core version. The inductance of a ferrite loop is given by

$$L = \frac{4\pi N^2 A \mu_{rod} \times 10^{-4}}{\ell} \qquad \text{(Eq 9)}$$

where

L = inductance in μH
N = number of turns
A = cross-sectional area of the core in square mm
ℓ = magnetic length of core in mm

Experiments indicate that the winding diameter should be as close to that of the rod diameter as practical in order to maximize both inductance value and Q. By using all this information, we may determine the voltage at the loop terminals and its signal-to-noise ratio (SNR). The voltage may be determined from

$$V = \frac{2\pi A N \mu' Q E}{\lambda} \qquad \text{(Eq 10)}$$

where

V = output voltage across the loop terminals
A = loop area in square meters
N = number of turns in the loop winding
μ' = corrected rod permeability
Q = loaded Q of the loop
E = RF field strength in volts per meter
λ = wavelength of operation in meters

Lankford's equation for the sensitivity of the loop for a 10 dB SNR is

$$E = \frac{1.09 \times 10^{-10} \lambda \sqrt{f\ L\ b}}{A N \mu' \sqrt{Q}} \qquad \text{(Eq 11)}$$

where

f = operating frequency in Hz
L = loop inductance in henrys
b = receiver bandwidth in Hz



Fig 11—Example of magnetic field lines near a practical ferrite rod, showing leakage flux.



Fig 12—Rod permeability, μ_{rod}, versus material permeability, μ, for different rod length-to-diameter ratios.

Similarly, Belrose gives the SNR of a tuned loop antenna as

$$\mathrm{SNR} = \frac{66.3\,\mathrm{N\,A}\,\mu_{\mathrm{rod}}\,\mathrm{E}}{\sqrt{\mathrm{b}}}\sqrt{\frac{\mathrm{Qf}}{\mathrm{L}}} \qquad \text{(Eq 12)}$$

From this, if the field strength E, μ_{rod}, b, and A are fixed, then Q or N must increase (or L decrease) to yield a better SNR. Higher sensitivity can also be obtained (especially at frequencies below 500 kHz) by bunching ferrite cores together to increase the loop area over that which would be possible with a single rod. High sensitivity is important because loop antennas are not the most efficient collectors of signals, but they do offer improvement over other receiving antennas in terms of SNR. For this reason, you should attempt to maximize the SNR when using a small loop receiving antenna. In some cases there may be physical constraints that limit how large you can make a ferrite-core loop.

After working through Eq 11 or 12, you might find you still require some increase in antenna system gain to effectively use your loop. In these cases the addition of a low noise preamplifier may be quite valuable even on the lower frequency bands where they are not commonly used. Chapter 14 contains information on such preamplifiers.

The electrostatic shield discussed earlier with reference to air-core loops can be used effectively with ferrite-core loops. (Construction examples are presented in Chapter 14.) As in the air-core loop, a shield will reduce electrical noise and improve loop balance.

PROPAGATION EFFECTS ON NULL DEPTH

After building a balanced loop you may find it does not approach the theoretical performance in the null depth. This problem may result from propagation effects. Tilting the loop away from a vertical plane may improve performance under some propagation conditions, to account for the vertical angle of arrival. Basically, the loop performs as described above only when the signal is arriving perpendicular to the axis of rotation of the loop. At incidence angles other than perpendicular, the position and depth of the nulls deteriorate.

The problem can be even further influenced by the fact that if the loop is situated over less than perfectly conductive ground, the wave front will appear to tilt or bend. (This bending is not always detrimental; in the case of Beverage antennas, sites are chosen to take advantage of this effect.)

Another cause of apparent poor performance in the null depth can be from polarization error. If the polarization of the signal is not completely linear, the nulls will not be sharp. In fact, for circularly polarized signals, the loop might appear to have almost no nulls. Propagation effects are discussed further in Chapter 14.

SITING EFFECTS ON THE LOOP

The location of the loop has an influence on its performance that at times may become quite noticeable. For ideal performance the loop should be located outdoors and clear of any large conductors, such as metallic downspouts and towers. A VLF loop, when mounted this way, will show good sharp nulls spaced 180° apart if the loop is well balanced. This is because the major propagation mode at VLF is by ground wave. At frequencies in the HF region, a significant portion of the signals is propagated by sky wave, and nulls are often only partial.

Most hams locate their loop antennas near their operating position. If you choose to locate a small loop indoors, its performance may show nulls of less than the expected depth, and some skewing of the pattern. For precision direction finding there may be some errors associated with wiring, plumbing, and other metallic construction members in the building. Also, a strong local signal may be reradiated from the surrounding conductors so that it cannot be nulled with any positioning of the loop. There appears to be no known method of curing this type of problem. All this should not discourage you from locating a loop indoors; this information is presented here only to give you an idea of some pitfalls. Many hams have reported excellent results with indoor mounted loops, in spite of some of the problems.

Locating a receiving loop in the field of a transmitting antenna may cause a large voltage to appear at the receiver antenna terminals. This may be sufficient to destroy sensitive RF amplifier transistors or front-end protection diodes. This can be solved by disconnecting your loop from the receiver during transmit periods. This can obviously be done automatically with a relay that opens when the transmitter is activated.

LOOP ANTENNA ARRAYS

Arrays of loop antennas, both in combination with each other and with other antenna types, have been used for many years. The arrays are generally used to cure some “deficiency” in the basic loop for a particular application, such as a 180° ambiguity in the null direction, low sensitivity, and so forth.

A Sensing Element

For direction-finding applications the single loop suffers the problem of having two nulls that are 180° apart. This leads to an ambiguity of 180° when trying to find the direction to a transmitting station from a given location. A sensing element (often called a *sense antenna*) may be added to the loop, causing the overall antenna to have a cardioid pattern and only one null. The sensing element is a small vertical antenna whose height is equal to or greater than the loop effective height. This vertical is physically close to the loop, and when its omnidirectional pattern is adjusted so that its amplitude and phase are equal to one of the loop lobes, the patterns combine to form a cardioid. This antenna can be made quite compact by use of a ferrite loop to form a portable DF antenna for HF direction finding. Chapter 14 contains additional information and construction projects using sensing elements.

Arrays of Loops

A more advanced array that can develop more diverse patterns consists of two or more loops. Their outputs are combined through appropriate phasing lines and combiners to form a phased array. Two loops can also be formed into an array that can be rotated without physically turning the loops themselves. This method was developed by Bellini and Tosi in 1907 and performs this apparently contradictory feat by use of a special transformer called a *goniometer*. The goniometer is described in Chapter 14.

Aperiodic Arrays

The aperiodic loop array is a wide-band antenna. This type of array is useful over at least a decade of frequency, such as 2 to 20 MHz. Unlike most of the loops discussed up to now, the loop elements in an aperiodic array are untuned. Such arrays have been used commercially for many years. One loop used in such an array is shown in **Fig 13**. This loop is quite different from all the loops discussed so far in this chapter because its pattern is not the familiar figure eight. Rather, it is omnidirectional.

The antenna is omnidirectional because it is purposely unbalanced, and also because the isolating resistor causes the antenna to appear as two closely spaced short monopoles. The loop maintains the omnidirectional characteristics over a frequency range of at least four or five to one. These loops, when combined into end-fire or broadside phased arrays, can provide quite impressive performance. A commercially made end-fire array of this type consisting of four loops equally spaced along a 25-meter baseline can provide gains in excess of 5 dBi over a range of 2 to 30 MHz. Over a considerable portion of this frequency range, the array can maintain F/B ratios of 10 dB. Even though the commercial version is very expensive, an amateur version can be constructed using the information provided by Lambert. One interesting feature of this type of array is that, with the proper combination of hybrids and combiners, the antenna can simultaneously feed two receivers with signals from different directions, as shown in **Fig 14**. This antenna may be especially interesting to one wanting a directional receiving array for two or more adjacent amateur bands.

SMALL TRANSMITTING LOOP ANTENNAS

The electrically small transmitting-loop antenna involves some different design considerations compared to receiving loops. Unlike receiving loops, the size limitations of the antenna are not as clearly defined. For most purposes, any transmitting loop whose physical circumference is less than ¼ λ can be considered "small." In most cases, as a consequence of their relatively large size (when compared to a receiving loop), transmitting loops have a nonuniform current distribution along their circumference. This leads to some performance changes from a receiving loop.

The transmitting loop is a parallel-tuned circuit with a large inductor acting as the radiator. As with the receiving



Fig 13—A single wide-band loop antenna used in an aperiodic array.



Fig 14—Block diagram of a four-loop broadside array with dual beams separated by 60° in azimuth.

Table 3
Transmitting Loop Equations

$$X_L = 2\pi f L \text{ ohms}$$

$$Q = \frac{f}{\Delta f} = \frac{X_L}{2\left(R_R + R_L\right)}$$

$$R_R = 3.12 \times 10^4 \left[\frac{NA}{\lambda^2}\right]^2 \text{ ohms}$$

$$V_C = \sqrt{P X_L Q}$$

$$I_L = \sqrt{\frac{PQ}{X_L}}$$

where

X_L = inductive reactance, ohms
f = frequency, Hz
Δf = bandwidth, Hz
R_R = radiation resistance, ohms
R_L = loss resistance, ohms (see text)
N = number of turns
A = area enclosed by loop, square meters
λ = wavelength at operating frequency, meters
V_C = voltage across capacitor
P = power, watts
I_L = resonant circulating current in loop

loop, the calculation of the transmitting-loop inductance may be carried out with the equations in Table 1. Avoid equations for long solenoids found in most texts. Other fundamental equations for transmitting loops are given in **Table 3**.

In the March 1968 *QST*, Lew McCoy, W1ICP, introduced the so-called "Army Loop" to radio amateurs. This was an amateur version of a loop designed for portable use in Southeast Asia by Patterson of the US Army and described in 1967. The Army Loop is diagrammed in **Fig 15A**, showing that this is a parallel tuned circuit fed by a tapped-capacitance impedance-matching network.

The Hart "high-efficiency" loop was introduced in the June 1986 *QST* by Ted Hart, W5QJR. It is shown schematically in Fig 15B and has the series-tuning capacitor separate from the matching network. The Hart matching network is basically a form of gamma match. Other designs have used a smaller loop connected to the transmission line to couple into the larger transmitting loop.

The approximate radiation resistance of a loop in ohms is given by

$$R_R = 3.12 \times 10^4 \left(\frac{NA}{\lambda^2}\right)^2 \qquad \text{(Eq 13)}$$

where

N = number of turns
A = area of loop in square meters
λ = wavelength of operation in meters



Fig 15—At A, a simplified diagram of the Army Loop. At B, the W5QJR loop, which is described in more detail later in this chapter.

The radiation resistance of a small transmitting loop is usually very small. For example, a 1-meter diameter, single-turn circular loop has a radius of 0.5 meters and an enclosed area of $\pi \times 0.5^2 = 0.785$ m^2. Operated at 14.0 MHz, the free-space wavelength is 21.4 meters and this leads to a computed radiation resistance of only $3.12 \times 10^{-4} (0.785/21.4^2)^2 = 0.092\ \Omega$.

Unfortunately the loop also has losses, both ohmic and from skin effect. By using this information, the radiation efficiency of a loop can be calculated from

$$\eta = \frac{R_R}{R_R + R_L} \qquad \text{(Eq 14)}$$

where

η = antenna efficiency, %

R_R = radiation resistance, Ω

R_L = loss resistance, Ω, which includes the loop's conductor loss plus the loss in the series-tuning capacitor.

A simple ratio of R_R versus R_L shows the effects on the efficiency, as can be seen from **Fig 16**. The loss resistance is primarily the ac resistance of the conductor. This can be calculated from Eq 6. A transmitting loop generally requires the use of copper conductors of at least ¾ inch in diameter in order to obtain reasonable efficiency. Tubing is as useful as a solid conductor because high-frequency currents flow only along a very small depth of the surface of the conductor; the center of the conductor has almost no effect on current flow.

Note that the R_L term above also includes the effect of the tuning capacitor's loss. Normally, the unloaded Q of a capacitor can be considered to be so high that any loss in the tuning capacitor can be neglected. For example, a very high-quality tuning capacitor with no mechanical wiping contacts, such as a vacuum-variable or a transmitting butterfly capacitor, might have an unloaded Q of about 5000. This implies a series loss resistance of less than about 0.02 Ω for a capacitive reactance of 100 Ω. This relatively tiny loss resistance can become significant, however, when the radiation resistance of the loop is only on the order of 0.1 Ω! Practical details for curbing capacitor losses are covered later in this chapter.



Fig 16—Effect of ratio of R_R/R_L on loop efficiency.

In the case of multiturn loops there is an additional loss related to a term called *proximity effect*. The proximity effect occurs in cases where the turns are closely spaced (such as being spaced one wire diameter apart). As these current-carrying conductors are brought close to each other, the current density around the circumference of each conductor gets redistributed. The result is that more current per square meter is flowing at the surfaces adjacent to other conductors. This means that the loss is higher than a simple skin-effect analysis would indicate, because the current is bunched so it flows through a smaller cross section of the conductor than if the other turns were not present.

As the efficiency of a loop approaches 90%, the proximity effect is less serious. But unfortunately, the less efficient the loop, the worse the effect. For example, an 8-turn transmitting loop with an efficiency of 10% (calculated by the skin-effect method) actually only has an efficiency of 3% because of the additional losses introduced by the proximity effect. If you are contemplating construction of a multiturn transmitting loop, you might want to consider spreading the conductors apart to reduce this effect. G. S. Smith includes graphs that detail this effect in his 1972 IEEE paper.

The components in a resonated transmitting loop are subject to both high currents and voltages as a result of the large circulating currents found in the high-Q tuned circuit formed by the antenna. This makes it important that any fixed capacitors have a high RF current rating, such as transmitting micas or the Centralab 850 series. Be aware that even a 100-W transmitter can develop currents in the tens of amperes, and voltages across the tuning capacitor in excess of 10,000 V. This consideration also applies to any conductors used to connect the loop to the capacitors. A piece of #14 wire may have more resistance than the rest of the loop conductor!

It is therefore best to use copper strips or the braid from a piece of large coax cable to make any connections. Make the best electrical connection possible, using soldered or welded joints. Using nuts and bolts should be avoided, because at RF these joints generally have high resistance, especially after being subjected to weathering.

An unfortunate consequence of having a small but high-efficiency transmitting loop is high loaded Q, and therefore limited bandwidth. This type of antenna may require retuning for frequency changes as little as 5 kHz. If you are using any wide-band mode such as AM or FM, this might cause fidelity problems and you might wish to sacrifice a little efficiency to obtain the required bandwidth.

A special case of the transmitting loop is that of the ferrite-loaded loop. This is a logical extension of the transmitting loop if we consider the improvement that a ferrite core makes in receiving loops. The use of ferrites in a transmitting loop is still under development. (See the Bibliography reference for DeVore and Bohley.)

PRACTICAL COMPACT TRANSMITTING LOOPS

The ideal small transmitting antenna would have performance equal to a large antenna. A small loop antenna can approach that performance except for a reduction in bandwidth, but that effect can be overcome by retuning. This section is adapted and updated from material written by Robert T. (Ted) Hart, W5QJR.

As pointed out above, small antennas are characterized by low radiation resistance. For a typical small antenna, such as a short dipole, loading coils are often added to achieve resonance. However, the loss inherent in the coils can result in an antenna with low efficiency. If instead of coils a large, low-loss capacitor is added to a low-loss conductor to achieve resonance, and if the antenna conductor is bent to connect the ends to the capacitor, a loop is formed.

Based on this concept, the small loop is capable of relatively high efficiency, compared to its coil-loaded cousin. In addition, the small loop, when mounted vertically, can radiate efficiently over the wide range of elevation angles required on the lower frequency bands. This is because it has both high-angle and low-angle response. See **Fig 17**, which shows the elevation response for a compact transmitting loop only 16.2 inches wide at 14.2 MHz. This loop is vertically polarized and its bottom is 8 feet above average ground, which has a conductivity of 5 mS/m and a dielectric constant of 13. For comparison, Fig 17 also shows the responses of three other reference antennas—the same small loop flipped sideways at a height of 30 feet to produce horizontal radiation, a full-sized ¼-λ ground plane antenna mounted 8 feet above average ground using two tuned radials, and finally a simple ½ λ flattop dipole mounted 30 feet above flat ground. The considerably smaller transmitting loop comes to within 3 dB of the larger ¼-λ vertical at a 10° elevation angle, and it is far stronger for high elevation angles because it does not have the null at high elevation angles that the ground plane has. Of course, this characteristic does make it more susceptible to strong signals received at high elevation angles. Incidentally, just in case you were wondering, adding more radials to the λ/4 ground plane doesn't materially improve its performance when mounted at an 8-foot height on 20 meters.



Fig 17—Elevation-plane plot at 14.2 MHz, showing response of an 8.5-foot circumference octagonal copper loop (width of 16.2 inches), compared to a full-sized λ/4 ground-plane vertical with two elevated λ/4 radials, the same small loop flipped horizontally at a height of 30 feet, and lastly, a λ/2 flattop dipole also at a height of 30 feet. Both the λ/4 ground-plane vertical and the vertically polarized loop are elevated 8 feet above typical ground, with σ = 5 mS/m and ε = 13. The low vertically polarized loop is surprisingly competitive, only down about 2.5 dB compared to the far larger ground plane at low elevation angles. Note that the vertical loop has both high-angle as well as low-angle radiation, and hence would be better at working close-in local stations than the ground-plane vertical, with its deep nulls at higher angles. The simple flattop dipole, however, is better than either vertical because of the poor ground reflection for a vertically polarized compared to a horizontally polarized signal.

The simple horizontal dipole in Fig 17 would be the clear winner in any shootout because its horizontally polarized radiation does not suffer as much attenuation at reflection from ground as does a vertically polarized wave. The case is not quite so clear-cut, however, for the small loop mounted horizontally at 30 feet. While it does have increased gain at medium elevation angles, it may not be worth the effort needed to mount it on a mast, considering the slight loss at low angles compared to its twin mounted vertically only 8 feet above ground.

A physically small antenna like the 16.2-inch-wide vertically polarized loop does put out an impressive signal compared to far larger competing antennas. Though somewhat ungainly, it is a substantially better performer than most mobile whips, for example. The main deficiency in a compact transmitting loop is its narrow bandwidth—it must be accurately tuned to the operating frequency. The use of a remote motor drive allows the loop to be tuned over a wide frequency range.

For example, for fixed-station use, two loops could be constructed to provide continuous frequency coverage from 3.5 to 30 MHz. A loop with an 8.5 foot circumference, 16 inches wide, could cover 10 through 30 MHz and a loop with a 20-foot circumference, 72 inches wide, could cover 3.5 to 10.1 MHz.

Table 4 presents summary data for various size loop antennas for the HF amateur bands. Through computer analysis, the optimum size conductor was determined to be ¾-inch rigid copper water pipe, considering both performance and cost. Performance will be compromised, but only slightly, if ⅝-inch flexible copper tubing is used. This tubing can easily be bent to any desired shape, even a circle. The rigid ¾-inch copper pipe is best used with 45° elbows to make an octagon.

The loop circumference should be between ¼ and ⅛ λ at the operating frequency. It will become self-resonant above ¼ λ, and efficiency drops rapidly below ⅛ λ. In the frequency ranges shown in Table 4, the high fre-

Table 4

Design Data for Loops

Loop Circumference = 8.5' (Width = 32.4"), Vertically Polarized

Frequency, MHz	10.1	14.2	21.2	29.0
Max Gain, dBi	–4.47	–1.42	+1.34	+2.97
Max Elevation Angle	40°	30°	22°	90°
Gain, dBi @10°	–8.40	–4.61	–0.87	+0.40
Total Capacitance, pF	145	70	29	13
Peak Capacitor kV	23	27	30	30

Loop Circumference = 8.5' (Width = 32.4"), Horizontally Polarized, @30'

Frequency, MHz	10.1	14.2	21.2	29.0
Max Gain, dBi	–3.06	+1.71	+5.43	+6.60
Max Elevation Angle	34°	28°	20°	16°
Gain, dBi @10°	–9.25	–3.11	+2.61	+5.34
Total Capacitance, pF	145	70	29	13
Peak Capacitor kV	23	27	30	30

Loop Circumference = 20' (Width = 6'), Vertically Polarized

Frequency, MHz	3.5	4.0	7.2	10.1
Max Gain, dBi	–7.40	–6.07	–1.69	–0.34
Max Elevation Angle	68°	60°	38°	30°
Gain, dBi @10°	–11.46	–10.12	–5.27	–3.33
Capacitance, pF	379	286	85	38
Peak Capacitor kV	22	24	26	30

Loop Circumference = 20' (Width = 6'), Horizontally Polarized, @30'

Frequency, MHz	3.5	4.0	7.2	10.1
Max Gain, dBi	–13.32	–10.60	–0.20	+3.20
Max Elevation Angle	42°	42°	38°	34°
Gain, dBi @10°	–21.62	–18.79	–7.51	–3.22
Capacitance, pF	379	286	85	38
Peak Capacitor kV	22	24	26	30

Loop Circumference = 38' (Width = 11.5'), Vertically Polarized

Frequency, MHz	3.5	4.0	7.2
Max Gain, dBi	–2.93	–2.20	–0.05
Max Elevation Angle	46°	42°	28°
Gain, dBi @10°	–6.48	–5.69	–2.80
Capacitance, pF	165	123	29
Peak Capacitor kV	26	27	33

Notes: These loops are octagonal in shape, constructed with ¾-inch copper water pipe and soldered 45° copper elbows. The gain figures assume a capacitor unloaded Q_C = 5000, typical for vacuum-variable type of tuning capacitor. The bottom of the loop is assumed to be 8 feet high for safety and the ground constants are "typical" at conductivity = 5 mS/m and dielectric constant = 13. Transmitter power is 1500 W. The voltage across the tuning capacitor for lower powers goes down with a multiplier of $\sqrt{\frac{P}{1500}}$. For example, at 100 W using the 38-foot-circumference loop at 7.2 MHz, the peak voltage would be $33\ \text{kV} \times \sqrt{\frac{100}{1500}} = 8.5\ \text{kV}$.

quency is tuned with a minimum capacitance of about 29 pF—including stray capacitance.

The low frequency listed in Table 4 is that where the loop response is down about 10 dB from that of a full-sized elevated ground plane at low elevation angles suitable for DX work. **Fig 18** shows an overlay at 3.5 MHz of the elevation responses for two loops: one with an 8.5-foot circumference and one with a 20-foot circumference, together with the response for a full-sized 80-meter ground plane elevated 8 feet off average ground with 2 tuned radials. The 20-foot circumference loop holds its own well compared to the full-sized ground plane.

Controlling Losses

Contrary to earlier reports, adding quarter-wave ground radials underneath a vertically polarized transmitting loop doesn't materially increase loop efficiency. The size of the conductor used for a transmitting loop, however, does directly affect several interrelated aspects of loop performance.

Data for Table 4 was computed for ¾-inch copper water pipe (nominal OD of 0.9 inch). Note that the efficiency is higher and the Q is lower for loops having a circumference near $^1/_4\ \lambda$. Larger pipe size will reduce the loss resistance, but the Q increases. Therefore the bandwidth decreases, and the voltage across the tuning capacitor increases. The voltage across the tuning capacitor for high-power operation can become very impressive, as shown in Table 4. Rigid ¾-inch copper water pipe is a good electrical compromise and can also help make a small-diameter loop mechanically sturdy.

The equivalent electrical circuit for the loop is a parallel resonant circuit with a very high Q, and therefore a narrow bandwidth. The efficiency is a function of radiation resistance divided by the sum of the radiation plus loss resistances. The radiation resistance is much less than 1 Ω, so it is necessary to minimize the loss resistance, which is largely the skin-effect loss of the conductor, assuming that the tuning capacitor has very low loss. Poor construction techniques must be avoided. All joints in the loop must be brazed or soldered.

However, if the system loss is too low, for example by using even larger diameter tubing, the Q may become excessive and the bandwidth may become too narrow for practical use. These reasons dictate the need for a complete analysis to be performed before proceeding with the construction of a loop.

There is another source of additional loss in a completed loop antenna besides the conductor and capacitor losses. If the loop is mounted near lossy metallic conductors, the large magnetic field produced will induce currents into those conductors and be reflected as losses in the loop. Therefore the loop should be as far from other conductors as possible. If you use the loop inside a building constructed with large amounts of iron or near ferrous materials, you will simply have to live with the loss if the loop cannot otherwise be relocated.

The Tuning Capacitor

Fig 19 demonstrates the selection of loop size versus tuning capacitance for any desired operating frequency range for the HF amateur bands. This is for octagonal-shaped loops using ¾-inch copper water pipe with 45° copper elbows. For example, a capacitor that varies from 5 to 50 pF, used with a loop 10 feet in circumference, tunes from 13 to 27 MHz (represented by the left dark vertical bar). A 25 to 150-pF capacitor with a 13.5-foot loop circumference covers the 7 to 14.4-MHz range, represented by the right vertical bar.

Fig 20 illustrates how the 29-MHz elevation pattern becomes distorted and rather bulbous-looking for the 10-foot circumference loop, although the response at low elevation angles is still better than that of a full-sized ground-plane antenna.



Fig 18—Elevation-plane response of three antennas at 3.5 MHz—a 20-foot circumference octagonal copper loop, a 38-foot circumference copper loop and a full-sized λ/4 ground plane with two elevated radials. The bottom of each antenna is mounted 8 feet above ground for safety. The 38-foot circumference loop (which has a "wingspan" of 11.5 feet) is fairly competitive with the much large ground-plane, being down only about 4 dB at low elevation angles. The 20-foot circumference loop is much more lossy, but with its top only about 14 feet off the ground is very much of a "stealth" antenna.

Air Variable Capacitors

Special care must be taken with the tuning capacitor if an air-variable type is used. The use of a split-stator capacitor eliminates the resistance of wiper contacts, resistance that is inherent in a single-section capacitor. The ends of the loop are connected to the stators, and the rotor forms the variable coupling path between the stators. With this arrangement the value of capacitance is divided by two, but the voltage rating is doubled.



Fig 19—Frequency tuning range of an octagon-shaped loop using $^3/_4$-inch copper water pipe, for various values of tuning capacitance and loop circumference.



Fig 20—Elevation-plane plot for a 16.2-inch wingspan octagonal copper loop at 29 MHz, compared to a λ/4 ground-plane antenna with two resonant elevated radials. The gains at low angles are almost identical, but the loop exhibits more gain at medium and high elevation angles. Again, the bottom of each antenna is located 8 feet above ground for safety.

You must carefully select a variable capacitor for transmitting-loop application—that is, all contacts must be welded, and no mechanical wiping contacts are allowed. For example, if the spacers between plates are not welded to the plates, there will be loss at each joint, and thus degraded loop efficiency. (Earlier transmitting loops exhibited poor efficiency because capacitors with wiping contacts were used.)

There are several suitable types of capacitors for this application. A vacuum variable is an excellent choice, provided one is selected with an adequate voltage rating. Unfortunately, those capacitors are very expensive.

W5QJR used a specially modified air-variable capacitor in his designs. This had up to 340 pF maximum per section, with ¼-inch spacing, resulting in 170 pF when both sections were in series as a butterfly capacitor. Another alternative is to obtain a large air variable, remove the aluminum plates, and replace them with copper or double-sided PC board material to reduce losses. Connect all plates together on the rotor and on the stators. Solder copper straps to the capacitor for soldering to the loop itself.

The spacing between plates in an air-variable capacitor determines the voltage-handling capability, rated at 75,000 V per inch. For other power ratings, multiply the spacing (and voltage) by the square root of the ratio of your power to 1000 W. For example, for 100 W, the ratio would be = 0.316.

Table 5
KD7S Loop-Tuning Capacitor Parts List for Nominal 50-pF Capacitor

Qty	*Description*
2	10-inch length of ¾-inch-ID type M copper water pipe
2	10-inch length of ½-inch-ID type M copper water pipe
1	3-inch length of ½-inch-ID type M copper water pipe
2	½-inch, 90° copper elbows
2	¾-inch, 90° copper elbows
2	10 × 22-inch piece of 0.005-inch-thick Teflon sheet plastic
1	12-inch length of #8-32 threaded brass rod
1	#8-32 brass shoulder nut
2	22 × 5½ × ¼-inch ABS plastic sheet (top and bottom covers)
3	1 × 5½ × ¼-inch ABS plastic sheet (end pieces and center) brace/guide
2	1 × 22 × ¼-inch ABS plastic sheet (side rails)
1	50 to 200-rpm gear-head dc motor
1	DPDT center-off toggle switch (up/down control)
2	SPDT microswitches (limit switches)
50 feet	3-conductor control cable
1	Enclosure for control switch

A Teflon-Insulated Trombone Variable Capacitor

Another type of variable capacitor discussed in the amateur literature for use with a compact transmitting loop is the so-called “trombone” type of capacitor. **Fig 21** shows a practical trombone capacitor created by Bill Jones, KD7S, for Nov 1994 *QST*. This capacitor uses downward pointing extensions of the two ¾-inch OD main conductor copper pipes, with a Teflon-insulated trombone section made of ½-inch ID copper pipe. The trombone telescopes into the main pipes, driven by a lead screw and a 180-rpm gear-head motor. Like the butterfly air variable capacitor, the trombone works without lossy wiper contacts. Jones’ capacitor varied from 12 pF (including strays) to almost 60 pF, making it suitable to tune his 3-foot circumference loop from 14 to 30 MHz at the 100-W level.

KD7S used 5-mil (0.005 inch) thick Teflon sheet as an insulator. Since Teflon is conservatively rated at more than 1 kV per mil of thickness, the voltage breakdown capability of this capacitor is well in excess of 5 kV. The parts list is given in **Table 5**.



Fig 21—A practical trombone capacitor designed by Bill Jones, KD7S, for his compact transmitting loop. This capacitor has a tuning range from 12 to almost 60 pF, and can withstand at least 5 kV peak. The 10-inch ½-inch ID tubes are covered with Teflon-sheet insulation and slide into the ¾-inch ID copper pipes.

A short length of plastic tubing connects the threaded brass rod to the motor. The tubing acts as an insulator and a flexible coupling to smooth out minor shaft-alignment errors. The other end of the rod is threaded into a brass nut soldered to the crossbar holding the $^1/_2$-inch pipes together. Jones used a 12-V motor rated at 180 rpm, but it has sufficient torque to work with as little as 4 V applied. Instead of a sophisticated variable duty-cycle speed control circuit, he used an LM327 adjustable voltage regulator to vary the motor-control voltage from 4 to 12 V. Tuning speeds ranged from 11 seconds per inch at 12 V to 40 seconds per inch at 4 V. The higher speed is necessary to jump from band to band in a reasonable length of time. The lower speed makes it easy to fine-tune the capacitor to any desired frequency within a band.

When building the capacitor, keep in mind that the smaller tubes must telescope in and out of the larger tubes with silky smoothness. Any binding will cause erratic tuning. For the same reason, the #8-32 brass threaded rod must be straight and properly aligned with the brass nut. *Take your time with this part of the project*.

Perhaps the easiest way to form the insulator is to precut a length of Teflon sheet to the proper size. Place a lengthwise strip of double-sided tape on the tube to secure one end of the Teflon sheet. Begin wrapping the Teflon around the tube while keeping it as tight as possible. *Don't allow wrinkles or ridges to form*. Secure the other end with another piece of tape. Once both tubes are covered, ensure they are just short of being a snug fit inside the larger tubes. Confirm that the insulation completely overlaps the open end of the small tubes. If not, the capacitor is certain to arc internally with more than a few watts of power applied to it.

Route the motor wiring inside the antenna pipes to minimize the amount of metal within the field of the antenna. Bring the wires out next to the coaxial connector. A three-wire system allows the use of limit switches to restrict the movement of the trombone section. Be sure to solder together all metal parts of the capacitor. Use a small propane torch, a good quality flux and 50/50 solid solder. Do not use acid-core solder! Clean all parts to be joined with steel wool prior to coating them with flux.

A Cookie-Sheet and Picture-Frame-Glass Variable Capacitor

In Vol 2 of *The ARRL Antenna Compendium* series, Richard Plasencia, WØRPV, described a clever high-voltage variable capacitor he constructed using readily available materials. See **Fig 22**, which shows Plasencia's homebrew high-voltage variable capacitor, along with the coil and other parts used in his homemade antenna coupler. This capacitor could be varied from 16 to 542 pF and tested at a breakdown of 12,000 V.

The capacitor sits on four PVC pillars and consists of two $4^1/_2 \times 4^1/_2$-inch aluminum plates separated by a piece of window glass that is $8^1/_2 \times 5^1/_2$ inches in size. The lower plate is epoxied to the glass. The upper plate is free to move in a wooden track epoxied to the upper surface of the glass. The motor is reversible and moves the upper capacitor plate by rotating a threaded rod in a wing nut pinned to a tab on the capacitor plate. The four pillars are cut from PVC pipe to insulate the capacitor from the chassis and to elevate it into alignment with the motor shaft.

WØRPV used a piece of 0.063-inch thick single-weight glass that exhibited a dielectric constant of 8. He removed the glass from a dime-store picture frame. In time-honored ham fashion, he improvised his wooden tracks for the upper capacitor plate from a single wooden paint stirrer, and for the capacitor plates, he used aluminum cookie sheets.

The wooden track for the upper plate is made by splitting the wooden paint stirrer with a knife into one narrow and one wide strip. The narrow strip is cemented on top and overhangs the movable plate, creating a slotted track. Since the wood is supported by the glass plate, its insulating qualities are of no importance.

The principle of operation is simple. The reversible motor turns a threaded $^1/_4$-inch rod with a pitch of 20 threads to the inch. This rod engages a wing nut attached to the movable capacitor plate. Although WØRPV grounded his capacitor's movable plate with a braid, an insulator similar to that used in the trombone capacitor above should be used to isolate the lead-screw mechanism. Several pieces of braid made from RG-8 coax shield should be used to connect to the ends of the compact transmitting loop conductors to form low-loss connections.

WØRPV used a 90-rpm motor from a surplus vending machine. It moved his variable capacitor plate $4^1/_2$ inches, taking about a minute to travel from one end to the other. Since he wished to eliminate the complexity and dubious reliability of limit switches when used outdoors, he monitored the motor's dc current through two 3 Ω, 2W resistors



Fig 22—The picture-frame-glass variable capacitor design of Richard Plasencia, WØRPV. Two aluminum plates separated by a piece of glass scavenged from a picture frame create a variable capacitor that can withstand 12,000 V, with a variable range from 16 to 542 pF.

placed in series with each lead of the motor and shunted by red LEDs at the control box. When the motor stalled by jamming up against the PVC limit stop or against the inside of the plastic mounting box, the increased motor current caused one or the other of the LEDs to light up.

TYPICAL LOOP CONSTRUCTION

After you select the electrical design for your loop application, you must consider how to mount it and how to feed it. If you wish to cover only the upper HF bands of 20 through 10 meters, you will probably choose a loop that has a circumference of about 8.5 feet. You can make a reasonably sturdy loop using 1-inch diameter PVC pipe and $^5/_8$-inch flexible copper tubing bent into the shape of a circle. Robert Capon, WA3ULH, did this for a QRP-level transmitting loop described in May 1994 *QST*. **Fig 23** shows a picture of his loop, with PVC H-frame stand.



Fig 23—Photo of compact transmitting loop designed by Robert Capon, WA3ULH. This uses a 1-inch PVC H-frame to support the loop made of flexible $^5/_8$-inch copper tubing. The small coupling loop made of RG-8 coax braid couples the loop to the coax feed line. The tuning capacitor and drive motor are at the top of the loop, shown here in the ARRL Laboratory during testing.

This loop design used a 20-inch long coupling loop made of RG-8 coax to magnetically couple into the transmitting loop rather than the gamma-match arrangement used by W5QJR in his loop designs. The coupling loop was fastened to the PVC pipe frame using 2-inch long #8 bolts that also held the main loop to the mast.

A more rugged loop can be constructed using rigid $^3/_4$-inch copper water pipe, as shown in the W5QJR design in **Fig 24**. While a round loop is theoretically a bit more efficient, an octagonal shape is much easier to construct. The values presented in Table 4 are for octagons.

For a given loop circumference, divide the circumference by 8 and cut eight equal-length pieces of $^3/_4$ inch copper water pipe. Join the pieces with 45° elbows to form the octagon. With the loop lying on the ground on scraps of 2 × 4 lumber, braze or solder all joints.

W5QJR made a box from clear plastic to house his air-variable capacitor and drive motor at the top of the loop. The side of the box that mounts to the loop and the capacitor should be at least ¼-inch thick, preferably $^3/_8$-inch. The remainder of the box can be $^1/_8$-inch plastic sheet. He mounted the loop to the plastic using $^1/_4$-inch bolts (two on either side of center) after cutting out a section of pipe 2 inches wide in the center. On the motor side of the capacitor, he cut the pipe and installed a copper T for the motor wiring.

W5QJR's next step was to solder copper straps to the loop ends and to the capacitor stators, then he remounted the loop to the plastic. If you insert wood dowels, the pipe will remain round when you tighten the bolts. Next he installed the motor drive cable through the loop and connected it to the motor. Antenna rotator cable is a good choice for this cable. He completed the plastic box using short pieces of aluminum angle and small sheet-metal screws to join the pieces.

The loop was then ready to raise to the vertical position. Remember, no metal is allowed near the loop. W5QJR made a pole of 2 × 4-inch lumber with 1 × 4-inch boards on either side to form an I section. He held the boards together with $^1/_4$-inch bolts, 2 feet apart and tied rope guys to the top. This made an excellent mast up to 50 feet high. The pole height should be one foot greater than the loop diameter, to allow room for cutting grass or weeds at the bottom of the loop. W5QJR installed a pulley at the top so that his loop could be raised, supported by rope. He supported the bottom of the loop by tying it to the pole and tied guy ropes to the sides of the loop to keep it from rotating in the wind. By moving the anchor points, he could rotate his loop in the azimuth plane.

W5QJR used a gamma-matching arrangement made of flexible $^1/_4$-inch copper tubing to couple the loop to the transmission line. In the center of one leg, he cut the pipe and installed a copper T. Adjacent to the T, he installed a mount for the coax connector. He made the mount from copper strap, which can be obtained by splitting a short piece of pipe and hammering it flat.

While the loop was in the vertical position he cut a piece of $^1/_4$-inch flexible copper tubing the length of one



Fig 24—Octagonal loop construction details. Table 4 gives loop design data for various frequency ranges.

of the straight sides of the loop. He then flattened one end and soldered a piece of flexible wire to the other. He wrapped the tubing with electrical tape for insulation and connected the flexible wire to the coax connector. He then installed the tubing against the inside of the loop, held temporarily in place with tape. He soldered the flat part to the loop, ending up with a form of gamma match, but without reactive components. This simple feed provided better than 1.7:1 SWR over a 2:1 frequency range. For safety, he installed a good ground rod under the loop and connected it to the strap for the coax connector, using large flexible wire.

TUNE-UP PROCEDURE

The resonant frequency of the loop can be readily found by setting the receiver to a desired frequency and rotating the capacitor (by remote control) until signals peak. The peak will be very sharp because of the high Q of the loop.

Turn on the transmitter in the tune mode and adjust either the transmitter frequency or the loop capacitor for maximum signal on a field-strength meter, or for maximum forward signal on an SWR bridge. Adjust the matching network for minimum SWR by bending the matching line. Normally a small hump in the $^1/_4$-inch tubing line, as shown in Fig 24, will give the desired results. For a loop that covers two or more bands, adjust the feed to give equally low SWR at each end of the tubing range. The SWR will be very low in the center of the tuning range but will rise at each end.

If there is metal near the loop, the additional loss will reduce the Q and therefore the impedance of the loop. In those cases it will be necessary to increase the length of the matching line and tap higher up on the loop to obtain a 50-Ω match.

PERFORMANCE COMPARISON

As previously indicated, a compact transmitting loop can provide performance approaching full-size dipoles and verticals. To illustrate one case, a loop 100 feet in circumference would be 30 feet high for 1.8 MHz. However, a good dipole would be 240 feet ($^1/_2$ λ) in length and at least 120 feet high ($^1/_4$ λ). A $^1/_4$-λ vertical would be 120 feet tall with a large number of radials on the ground, each 120 feet in length. The smaller loop could replace both of those antennas with only a moderate degradation in performance and a requirement for a high-voltage variable capacitor.

On the higher frequencies, the same ratios apply, but full-size antennas are less dramatic. However, very few city dwellers can erect good verticals even on 7 MHz with a full-size counterpoise. Even on 14 MHz a loop about 3 feet high can work the world.

Other than trading small size for narrow bandwidth and a high-voltage capacitor, the compact transmitting loop is an excellent antenna and should find use where large antennas are not practical.

The Loop Skywire

Are you looking for a multiband HF antenna that is easy to construct, costs nearly nothing and yet works well? You might want to try this one. The *Loop Skywire* antenna is a full-sized horizontal loop. Early proponents suggested that the antenna could be fed with coaxial cable with little concern for losses, but later analysis proved that this was a bit of wishful thinking—the relatively low values for SWR across multiple bands indicate that cable losses were part and parcel of performance. The best way to feed this versatile antenna is with open-wire ladder line, with an antenna tuner in the shack to present the transmitter with a low value of SWR.

THE DESIGN

The Loop Skywire is shown in **Fig 25**. The antenna has one wavelength of wire in its perimeter at the design or fundamental frequency. If you choose to calculate L_{total} in feet, the following equation should be used:

$$L_{total} = \frac{1005}{f}$$

where f equals the frequency in MHz.

Given any length of wire, the maximum possible area the antenna can enclose is with the wire in the shape of a circle. Since it takes an infinite number of supports to hang a circular loop, the square loop (four supports) is the most practical. Further reducing the area enclosed by the wire loop (fewer supports) brings the antenna closer to the properties of the folded dipole, and both harmonic-impedance and feed-line voltage problems can result. Loop geometries other than a square are thus possible, but remember the two fundamental requirements for the Loop Skywire—its horizontal position and maximum enclosed area.

There is another great advantage to this antenna system. It can be operated as a vertical antenna with top-hat loading on other bands as well. This is accomplished by simply keeping the feed line run from the antenna to the shack as vertical as possible and clear of objects. Both feed-line conductors are then tied together, and the antenna is fed against a good ground.

CONSTRUCTION

Antenna construction is simple. Although the loop can be made for any band or frequency of operation, the following two Loop Skywires are good performers. The 10-MHz band can also be operated on both.



Fig 25—A complete view of the Loop Skywire. The square loop is erected horizontal to the earth.

3.5-MHz Loop Skywire
(3.5-28 MHz loop and 1.8-MHz vertical)
Total loop perimeter: 272 feet
Square side length: 68 feet

7-MHz Loop Skywire
(7-28 MHz loop and 3.5-MHz vertical)
Total loop perimeter: 142 feet
Square side length: 35.5 feet

The actual total length can vary from the above by a few feet, as the length is not at all critical. Do not worry about tuning and pruning the loop to resonance. No signal difference will be detected on the other end when that method is used.

Bare #14 copper wire is used in the loop. **Fig 26** shows the placement of the insulators at the loop corners. Two common methods are used to attach the insulators. Either lock or tie the insulator in place with a loop wire tie, as shown in Fig 26A, or leave the insulator free to "float" or slide along the wire, Fig 26B. Most loop users float at least two insulators. This allows pulling the slack out of the loop once it is in the air, and eliminates the need to have all the supports exactly placed for proper tension in each leg. Floating two opposite corners is recommended.

Fig 27A shows the azimuth-plane performance on 7.2 MHz of a 142-foot long, 7-MHz Loop Skywire, 40 feet high at an elevation angle of 10º, compared to a regular flattop $^1/_2$-λ dipole at a height of 30 feet. The loop comes into its own at higher frequencies. Fig 27B shows the response at 14.2 MHz, compared again to a $^1/_2$–λ 14.2-MHz



Fig 26—Two methods of installing the insulators at the loop corners.



Fig 27—At A, azimuth-plane response of 142-foot long, 7-MHz Loop Skywire, 40 feet in the air at 7.2 MHz, compared with ½-λ dipole 30 feet in the air. At B, response of same Loop Skywire at 14.2 MHz, compared with ½-λ 14.2-MHz dipole 30 feet in the air. Now the loop has some advantage in certain directions. At C, response of the same Loop Skywire at 21.2 MHz compared to a 21.2-MHz dipole at 30 feet. Here, the Loop Skywire has more gain in almost all directions than the simple dipole. All azimuth-plane patterns were made at 10° elevation.

dipole at a height of 30 feet. Now the loop has several lobes that are stronger than the dipole. Fig 27C shows the response at 21.2 MHz, compared to a dipole. Now the loop has superior gain compared to the $^1/_2$-λ dipole at almost any azimuth. In its favored direction on 21.2 MHz, the loop is 8 dB stronger than the dipole.

The feed point can be positioned anywhere along the loop that you wish. However, most users feed the Skywire at a corner. **Fig 28** depicts a method of doing this, using a piece of plexiglass to provide insulation as well as strain relief for the open-wire ladder line. It is advantageous to keep the feed-point mechanicals away from the corner support. Feeding a foot or so from one corner allows the feed line to exit more freely. This method keeps the feed line free from the loop support.



Fig 28—Most users feed the Skywire at a corner. A high-impedance weather-resistant insulator should be used for the feed-point insulator.

Generally a minimum of four supports is required. If trees are used for supports, then at least two of the ropes or guys used to support the insulators should be counterweighted and allowed to move freely. The feedline corner is almost always tied down, however. Very little tension is needed to support the loop (far less than that for a dipole). Thus, counterweights are light. Several such loops have been constructed with bungie cords tied to three of the four insulators. This eliminates the need for counterweighting.

Recommended height for the antenna is 40 feet or more. The higher the better, especially if you wish to use the loop in the vertical mode. However, successful local and DX operation has been reported in several cases with the antenna at 20 feet. **Fig 29** shows the feed arrangement for using the Loop Skywire as a top-loaded vertical fed against ground on the lower bands.

Because the loop is high in the air and has considerable electrical exposure to the elements, proper methods should be employed to eliminate the chance of induced or direct lightning hazard to the shack and operator. Some users simply completely disconnect the antenna from the antenna tuner and rig and shack during periods of possible lightning activity.



Fig 29—The feed arrangement for operating the 7-MHz Loop Skywire as a vertical antenna.

7-MHz Loop

An effective but simple 7MHz antenna that has a theoretical gain of approximately 1 dB over a dipole is a full-wave, closed vertical loop. Such a loop need not be square, as illustrated in **Fig 30A**. It can be trapezoidal, rectangular, circular, or some distorted configuration in between those shapes. For best results, however, you should attempt to make the loop as square as possible. The more rectangular the shape, the greater the cancellation of energy in the system, and the less effective it will be. In the limiting case, the antenna loses its identity as a loop and becomes a folded dipole.

You can feed the loop in the center of one of the vertical sides if you want vertical polarization. For horizontal polarization, you feed either of the horizontal sides at the center. Since optimum directivity occurs at right angles to the plane of the loop (or in more simple terms, broadside to the loop), you should hang the loop to radiate the maximum amount in some favored direction.

Fig 31A shows the azimuthal response at a takeoff angle of 15°, a typical angle for 40-meter DX, for vertical and horizontal feed systems over ground with “average” conductivity and dielectric constant. Fig 31A includes, for reference, the response of a flattop dipole 50 feet high. For DX work on 40 meters, the vertically polarized loop can perform as well as or substantially better than either a horizontally polarized loop or a flattop dipole, particularly in the azimuthal nulls of the dipole.

For the low elevation angles that favor DX work, the optimal feed point is at the center of one of the vertical wires. Feeding the loop at one of the corners at the bottom gives a



Fig 30—At A, details of the rectangular full-wave loop. The dimensions given are for operation at 7.05 MHz. The height above ground was 7 feet in this instance, although improved performance should result if the builder can install the loop higher above ground without sacrificing length on the vertical sides. At B, illustration how a single supporting structure can be used to hold the loop in a diamond-shaped configuration. Feeding the diamond at the lower tip provides radiation in the horizontal plane. Feeding the system at either side will result in vertical polarization of the radiated signal.



Fig 31—At A, azimuthal plane responses for the vertically and horizontally polarized 7-MHz loop, compared to a flattop 50-foot high dipole, all at a takeoff angle of 15° for DX work. The solid line is for feeding the loop horizontally at the bottom; the dashed line is for feeding the loop vertically at a side, and the dotted line is for a simple flattop horizontal dipole at 50 feet in height. For DX work, the vertically polarized loop is an excellent performer.

compromise result for both local and DX work. The actual impedance is roughly the same at each point: bottom horizontal center, corner or vertical side center.

Fig 31B demonstrates how the gain for vertical polarization changes over different type of grounds: saltwater, very poor ground (conductivity = 1 mS/m, dielectric constant = 5) very good (conductivity = 30 mS/m, dielectric constant = 20) and average ground (conductivity = 5 mS/m, dielectric constant = 13). Again, for reference a 50-foot high flattop dipole's elevation response is included. As has been mentioned previously in other chapters, a seaside location is a wonderful environment for verticals!

Just how you erect such a loop will depend on what is available in your backyard. Trees are always handy for supporting loop antennas. A disadvantage to the rectangular loop shown in Fig 30A is that two 34-foot high supports are needed, although in many instances your house may be high enough to serve as one of these supports. If you have a tower higher than about 50 feet, Fig 30B demonstrates how you can use it to support a diamond-shaped loop for 40 meters. The elevation and azimuthal responses are almost the same for either loop configuration, rectangular- or diamond-shaped.

The overall length of the wire used in a loop is determined in feet from the formula 1005/f (MHz). Hence, for operation at 7.125 MHz the overall wire length will be 141 feet. The matching transformer, an electrical $^{1}/_{4}$ λ of 75Ω coax cable, can be computed by dividing 246 by the operating frequency in MHz, then multiplying that number by the velocity factor of the cable being used. Thus, for operation at 7.125 MHz, 246/7.125 MHz = 34.53 feet. If coax with solid polyethylene insulation is used, a velocity factor of 0.66 must be employed. Foam-polyethylene coax has a velocity factor of 0.80. Assuming RG-59 is used, the length of the matching transformer becomes 34.53 (feet) × 0.66 = 22.79 feet, or 22 feet, 9$^{1}/_{2}$ inches.



Fig 32—Elevation-plane response of 7-MHz loop used on 14.2 MHz. This is for a feed point at the center of one of the two vertical wires. The dashed line is the response of a flattop 20-meter dipole at 30 feet in height for comparison.

This same loop antenna in Fig 30A fed vertically may be used on the 14 and 21MHz bands, although its pattern will not be as good as that on its fundamental frequency and you will have to use an open-wire transmission line to feed the loop for multiband use. **Fig 32** shows the response at the peak lobe of the loop, at a 45° angle to the plane of the loop, compared to the peak response for a simple halfwave 20-meter dipole, 30 feet high. The gain from a simple flattop dipole, mounted at 30 feet, will be superior to the loop operated on a harmonic frequency.

A Receiving Loop for 1.8 MHz

You can use a small shielded-loop antenna to improve reception under certain conditions, especially at the lower amateur frequencies. This is particularly true when high levels of man-made noise are prevalent, when the second-harmonic energy from a nearby broadcast station falls in the 1.8MHz band, or when interference exists from some other amateur station in the immediate area. A properly constructed and tuned small loop will exhibit approximately 30 dB of front-to-side response, the minimum response being at right angles to the plane of the loop. Therefore, noise and interference can be reduced significantly or completely nulled out, by rotating the loop so that it is sideways to the interference-causing source.

Generally speaking, small shielded loops are far less responsive to man-made noise than are the larger antennas used for transmitting and receiving. But a trade-off in performance must be accepted when using the loop, for the strength of received signals will be 10 or 15 dB less than when using a full-size resonant antenna. This condition is not a handicap on 1.8 or 3.5 MHz, provided the station receiver has normal sensitivity and overall gain. Because a front-to-side ratio of 30 dB may be expected, a shielded loop can be used to eliminate a variety of receiving problems if made rotatable, as shown in **Fig 33**.

To obtain the sharp bidirectional pattern of a small loop, the overall length of the conductor must not exceed 0.1 λ. The loop of **Fig 34** has a conductor length of 20 feet. At 1.81 MHz, 20 feet is 0.037 λ. With this style of loop, 0.037 λ is about the maximum practical dimension if you want to tune the element to resonance. This limitation results from the distributed capacitance between the shield and inner conductor of the loop. RG-59 was used for the loop element in this example. The capacitance per foot for this cable is 21 pF, resulting in a total distributed



Fig 33—Jean DeMaw, W1CKK, tests the 1.8-MHz shielded loop. Bamboo cross arms are used to support the antenna.



Fig 34—Schematic diagram of the loop antenna. The dimensions are not critical provided overall length of the loop element does not exceed approximately 0.1 λ. Small loops which are one half or less the size of this one will prove useful where limited space is a consideration.

capacitance of 420 pF. An additional 100 pF was needed to resonate the loop at 1.810 MHz.

Therefore, the approximate inductance of the loop is 15 μH. The effect of the capacitance becomes less pronounced at the higher end of the HF spectrum, provided the same percentage of a wavelength is used in computing the conductor length. The ratio between the distributed capacitance and the lumped capacitance used at the feed point becomes greater at resonance. These facts should be contemplated when scaling the loop to those bands above 1.8 MHz.

There will not be a major difference in the construction requirements of the loop if coaxial cables other than RG-59 are used. The line impedance is not significant with respect to the loop element. Various types of coaxial line exhibit different amounts of capacitance per foot, however, thereby requiring more or less capacitance across the feed point to establish resonance.

Shielded loops are not affected noticeably by nearby objects, and therefore they can be installed indoors or out after being tuned to resonance. Moving them from one place to another does not significantly affect the tuning.

You can see in the model shown in Fig 33 that a supporting structure was fashioned from bamboo poles. The X frame is held together at the center with two U bolts. The loop element is taped to the cross-arms to form a square. You could likely use metal cross arms without seriously degrading the antenna performance. Alternatively, wood can be used for the supporting frame.

A Minibox was used at the feed point of the loop to hold the resonating variable capacitor. In this model a 50 to 400-pF compression trimmer was used to establish resonance. You must weatherproof the box for outdoor installations.

Remove the shield braid of the loop coax for one inch directly opposite the feed point. You should treat the exposed areas with a sealing compound once this is done.

In operation this receiving loop has proven very effective for nulling out second-harmonic energy from local broadcast stations. During DX and contest operations on 1.8 MHz it helped prevent receiver overloading from nearby 1.8-MHz stations that share the band. The marked reduction in response to noise has made the loop a valuable station accessory when receiving weak signals. It is not used all of the time, but is available when needed by connecting it to the receiver through an antenna selector switch. Reception of European stations with the loop has been possible from New England at times when other antennas were totally ineffective because of noise.

It was also discovered that the effects of approaching storms (with attendant atmospheric noise) could be nullified considerably by rotating the loop away from the storm front. It should be said that the loop does not exhibit meaningful directivity when receiving sky-wave signals. The directivity characteristics relate primarily to ground-wave signals. This is a bonus feature in disguise, for when nulling out local noise or interference, one is still able to copy sky-wave signals from all compass points!

For receiving applications it is not necessary to match the feed line to the loop, though doing so may enhance the performance somewhat. If no attempt is made to obtain an SWR of 1, the builder can use 50 or 75-Ω coax for a feeder, and no difference in performance will be observed. The Q of this loop is sufficiently low to allow the operator to peak it for resonance at 1.9 MHz and use it across the entire 1.8MHz band. The degradation in performance at 1.8 and 2 MHz will be so slight that it will be difficult to discern.

An Indoor Stealth Loop

Ted Phelps, W8TP, wrote an article in *The ARRL Antenna Compendium, Vol 7* describing his attic-mounted wire loop antenna, fed with an automatic antenna tuner. Here is a shortened version of that article.

If you drive down my street in Whitechapel Village in Newark, DE, trying to find my ham location by looking for my antenna, you wouldn't find it. Even if you pulled up in front of my condo, you wouldn't notice any telltale signs, because my multiband antenna is completely hidden. It's in the attic of my two-bedroom condominium in a small retirement community completed in 1999.

Before the move, I had given considerable thought to what type of antenna I might use, if any. I already knew that permanent outdoor types were out of the question, due to restrictive real estate and condo association rules. So I planned a clause for any sales contract I might sign, specifically mentioning amateur radio and my desire to set up a station in my new living quarters. I decided I would not move where my lifelong hobby would be severely restricted or prohibited.

That meant that to be reasonably sure I could continue enjoying Amateur Radio as before, I would have to install an indoor antenna that could perform as well as a typical outdoor system. What kind? In Ohio, I had tried a horizontally polarized attic dipole made with #14 wire. It didn't work very well—it was just too low to the ground.

I learned about a high-tech method of remote antenna tuning using an antenna coupler which contains a microprocessor. I found this kind of automatic tuner available from two American manufacturers and within a reasonable price range. Although our move was still a few months ahead, I purchased a model SG-230 antenna coupler made by SGC Inc, Bellevue, WA, for use in Delaware.

Fig 35 shows the final dimensions of my hidden loop, which is a single-turn rectangular loop, erected in a north-south vertical plane and made from nearly 78 feet of #6 stranded, aircraft primary wire in a PVC jacket, held taut at the lower corners and supported by a pulley and guy rope at each upper corner. Because it's vertically polarized, it supports low-angle radiation reasonably well. By the way, if you're wondering why I used such a relatively large-gauge wire as #6 for the loop antenna, it was readily available from my son-in-law!

Fig 36 shows my completed condo unit. Note the doghouse dormer on the roof about 12 feet above ground at the attic floor. This is the level of my hidden loop's base leg.

In constructing my system I had to overcome RFI problems on my own premises. Each condo unit has its own electronic security panel on an upper shelf in a closet. As soon as I applied moderate power to my radio and loop, the Fire Alarm sounded and firefighters came to my door! The burglar/intrusion signal was triggered a couple of times, too. Working with a security installation technician, I found that *there was no ground wire connected to my security panel.* "We don't bother with that," said the tech, and then, reacting to my surprise, connected a #14 ground between the security panel and the house water-pipe ground. I then installed a ferrite bead on each lead entering the security panel. I also placed ferrite beads on keyer-paddle leads, GFCI electrical outlets, etc. Those


ANT0158
23 Ft Above Ground
Top = 340.5" (28.375 ft) Long
North Leg = 122"
South Leg = 121"
N
S
Tuner
Base = 350.5" (29.208 ft Long), 12 ft Above Ground

Fig 35—Diagram showing layout of W8TP's indoor hidden loop antenna.

Fig 36—Can you see W8TP's antenna in this photograph? Of course you can't—it's hidden from view inside his attic!



Fig 37—At A, computed elevation pattern at 14.2 MHz for W8TP's hidden loop (solid line), compared to a 20-meter dipole (dashed line) at a height of 23 feet. At B, a comparison of the azimuth patterns at a 20°-elevation angle for W8TP's loop (solid line) and the same 20-meter dipole (dashed line). The loop has a slightly asymmetrical response because it is fed at a corner, but its performance is competitive to an outdoor dipole. In fact, it has superior low-angle performance, typical of a vertically polarized antenna compared to a low horizontal antenna.

measures seem to have eliminated my RFI problems.

When we moved into our condo, I took the obvious precaution of not using a linear amplifier. I took extra care to establish a single-point ground for my station equipment by connecting all equipment grounds to the cover plate of the dedicated metallic outlet box behind the operating position, and thence to a separate ground rod in our front yard. I use a 1-kW RL Drake low-pass filter in the transceiver-antenna feed line.

Is this indoor antenna system safe? I believe so. In the attic it is not at all close to our living space. It is fixed firmly in place and unlike most amateur antennas it is *out of the weather*! I therefore do not use a quick-grounding system for times when a thunderstorm approaches.

Fig 37 shows the computed elevation and azimuth patterns on 20 meters. The tuner is able to hold the SWR down low enough so that my JRC-245 transceiver can operate through its internal antenna tuner.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2.

C. F. W. Anderson, "A Crossed-Loop/Goniometer DF Antenna for 160 Meters," *The ARRL Antenna Compendium, Vol 1* (Newington: ARRL, 1985), pp 127-132.

J. S. Belrose, "Ferromagnetic Loop Aerials," *Wireless Engineer*, Feb 1955, pp 41-46.

J. S. Belrose, "An Update on Compact Transmitting Loops," *QST*, Nov 1993, pp 37-40.

D. S. Bond, *Radio Direction Finders*, 1st ed. (New York: McGraw-Hill Book Co, 1944).

G. Bramslev, "Loop Aerial Reception," *Wireless World*, Nov 1952, pp 469-472.

R. W. Burhans, "Experimental Loop Antennas for 60 kHz to 200 kHz," *Technical Memorandum (NASA) 71*, (Athens, OH: Ohio Univ, Dept of Electrical Engr), Dec 1979.

R. W. Burhans, "Loop Antennas for VLF-LF," *Radio-Electronics*, Jun 1983, pp 83-87.

D. DeMaw, "Beat the Noise with a Scoop Loop," *QST*, Jul 1977, pp 30-34.

M. F. DeMaw, *Ferromagnetic-Core Design and Application Handbook* (Englewood Cliffs, NJ: Prentice-Hall Inc, 1981).

D. DeMaw and L. Aurick, "The Full-Wave Delta Loop at Low Height," *QST*, Oct 1984, pp 24-26.

R. Devore and P. Bohley, "The Electrically Small Magnetically Loaded Multiturn Loop Antenna," *IEEE Trans on Ant and Prop*, Jul 1977, pp 496-505.

T. Dorbuck, "Radio Direction-Finding Techniques," *QST*, Aug 1975, pp 30-36.

R. G. Fenwick, "A Loop Array for 160 Meters," *CQ*, Apr 1986, pp 25-29.

D. Fischer, "The Loop Skywire," *QST*, Nov 1985, pp 20-22. Also "Feedback," *QST*, Dec 1985, p 53.

R. A. Genaille, "V.L.F. Loop Antenna," *Electronics World*, Jan 1963, pp 49-52.

G. Gercke, "Radio Direction/Range Finder," *73*, Dec 1971, pp 29-30.

R. S. Glasgow, *Principles of Radio Engineering* (New York: McGraw-Hill Book Co, Inc, 1936).

S. Goldman, "A Shielded Loop for Low Noise Broadcast Reception," *Electronics*, Oct 1938, pp 20-22.

F. W. Grover, *Inductance Calculation-Working Formulas and Tables* (New York: D. VanNostrand Co, Inc, 1946).

J. V. Hagan, "A Large Aperture Ferrite Core Loop Antenna for Long and Medium Wave Reception," *Loop Antennas Design and Theory*, M.G. Knitter, Ed. (Cambridge, WI: National Radio Club, 1983), pp 37-49.

T. Hart, "Small, High-Efficiency Loop Antennas," *QST*, Jun 1986, pp 33-36.

T. Hart, *Small High Efficiency Antennas Alias The Loop* (Melbourne, FL: W5QJR Antenna Products, 1985)

H. Hawkins, "A Low Budget, Rotatable 17 Meter Loop," *QST*, Nov 1997, p 35.

F. M. Howes and F. M. Wood, "Note on the Bearing Error and Sensitivity of a Loop Antenna in an Abnormally Polarized Field," *Proc IRE*, Apr 1944, pp 231-233.

B. Jones, KD7S, "You Can Build: A Compact Loop Antenna for 30 Through 12 Meters," Nov 1994 *QST*, pp 33-36.

J. A. Lambert, "A Directional Active Loop Receiving Antenna System," *Radio Communication*, Nov 1982, pp 944-949.

D. Lankford, "Loop Antennas, Theory and Practice," *Loop Antennas Design and Theory*, M. G. Knitter, Ed. (Cambridge, WI: National Radio Club, 1983), pp 10-22.

D. Lankford, "Multi-Rod Ferrite Loop Antennas," *Loop Antennas Design and Theory*, M. G. Knitter, Ed. (Cambridge, WI: National Radio Club, 1983), pp 53-56.

G. Levy, "Loop Antennas for Aircraft," *Proc IRE*, Feb 1943, pp 56-66. Also see correction, *Proc IRE*, Jul 1943, p 384.

J. Malone, "Can a 7 foot 40m Antenna Work?" *73*, Mar 1975, pp 33-38.

R. Q. Marris, "An In-Room 80-Meter Transmitting Multiturn Loop Antenna," *QST*, Feb 1996, pp 43-45. Feedback. *QST*, May 1996, p 48.

L. G. McCoy, "The Army Loop in Ham Communications," *QST*, Mar 1968, pp 17, 18, 150, 152. (See also Technical Correspondence, *QST*, May 1968, pp 49-51 and Nov 1968, pp 46-47.)

R. G. Medhurst, "HF Resistance and Self Capacitance of Single Layer Solenoids," *Wireless Engineer*, Feb 1947, pp 35-43, and Mar 1947, pp 80-92.

G. P. Nelson, "The NRC FET Altazimuth Loop Antenna," *N.R.C. Antenna Reference Manual Vol. 1*, 4th ed., R. J. Edmunds, Ed. (Cambridge, WI: National Radio Club, 1982), pp 2-18.

K. H. Patterson, "Down-To-Earth Army Antenna," *Electronics*, Aug 21, 1967, pp 111-114.

R. C. Pettengill, H. T. Garland and J. D. Meindl, "Receiving Antenna Design for Miniature Receivers," *IEEE Trans on Ant and Prop*, Jul 1977, pp 528-530.

T. Phelps, W8TP, "A Hidden Loop Antenna," *The ARRL Antenna Compendium, Vol 7* (Newington: ARRL, 2002), pp 160-162.

R. Z. Plasencia, WØRPV, "Remotely Controlled Antenna Coupler," *The ARRL Antenna Compendium, Vol 2* (Newington: ARRL, 1989), pp 182-186.

W. J. Polydoroff, *High Frequency Magnetic Materials—Their Characteristics and Principal Applications* (New York: John Wiley and Sons, Inc, 1960).

E. Robberson, "QRM? Get Looped," *Radio and Television News*, Aug 1955, pp 52-54, 126.

G. S. Smith, "Radiation Efficiency of Electrically Small Multiturn Loop Antennas," *IEEE Trans on Ant and Prop*, Sep 1972, pp 656-657.

E. C. Snelling, *Soft Ferrites—Properties and Applications* (Cleveland, OH: CRC Press, 1969).

G. Thomas, "The Hot Rod—An Inexpensive Ferrite Booster Antenna," *Loop Antennas Theory and Design*, M. G. Knitter, Ed. (Cambridge, WI: National Radio Club, 1983), pp 57-62.

J. R. True, "Low-Frequency Loop Antennas," *Ham Radio*, Dec 1976, pp 18-24.

E. G. VonWald, "Small-Loop Antennas," *Ham Radio*, May 1972, pp 36-41.

"An FET Loop Amplifier with Coaxial Output," *N.R.C. Antenna Reference Manual, Vol 2*, 1st ed., R. J. Edmunds, Ed. (Cambridge, WI: National Radio Club, Oct 1982), pp 17-20.

Aperiodic Loop Antenna Arrays (Hermes Electronics Ltd, Nov 1973).

Reference Data for Radio Engineers, 6th ed. (Indianapolis: Howard W. Sams & Co, subsidiary of ITT, 1977).



Fig 43—A simple lightning arrester for open-wire line made from three standoff or feedthrough insulators and sections of $^1/_8 \times ^1/_2$-inch brass or copper strap. It should be installed in the line at the point where the line enters the station. The heavy ground lead should be as short and as direct as possible. The gap setting should be adjusted to the minimum width that will prohibit arcing when the transmitter is operated.



Fig 44—The lightning arrester of Fig 39 may be used with 300-Ω ribbon line in the manner shown here. The TV standoffs support the line an inch or so away from the grounded center member of the arrester

The construction of a homemade arrester for open-wire line is shown in **Fig 43**. This type of arrester can be adapted to ribbon line an inch or so away from the center member of the arrester, as shown in **Fig 44**. Sufficient insulation should be removed from the line where it crosses the arrester to permit soldering the arrester connecting leads.

Lightning Grounds

Lightning-ground connecting leads should be of conductor size equivalent to at least #10 wire. The #8 aluminum wire used for TV-antenna grounds is satisfactory. Copper braid $^3/_4$-inch wide (Belden 8662-10) is also suitable. The conductor should run in a straight line to the grounding point. The ground connection may be made to a water pipe system (if the pipe is not plastic), the grounded metal frame of a building, or to one or more $^5/_8$-inch ground rods driven to a depth of at least 8 feet. More detailed information on lightning protection is contained in Chapter 1, Safety.

A central grounding panel for coax cables coming into the house is highly recommended. See **Fig 45** for a photo of the homemade grounding panel installed by Chuck Hutchinson, K8CH, at his Michigan home. The coax cables screwed into dual-female feed-through UHF connectors. K8CH installed this aluminum panel under the outside grill for a duct that provided combustion air to an unused fireplace. He used ground strap to connect to ground rods located under the panel. See the ARRL book *Simple and Fun Antennas* for more information about ground panels.



Fig 45—K8CH's coax entry panel mounted on exterior wall (later covered by grill that provides combustion to an unused fireplace). The ground braid goes to a ground rod located beneath the panel. (Photo courtesy: *Simple and Fun Antennas for Hams*)

Before a lightning storm approaches, a prudent ham will disconnect all feed lines, rotor lines and control lines inside the shack to prevent damage to sensitive electronics. When lightning is crashing about outside, you certainly don't want that lightning inside your shack!

Chapter 6

Low-Frequency Antennas

In theory there is no difference between antennas at 10 MHz and up and those for lower frequencies. In reality however, there are often important differences. It is the size of the antennas, which increases as frequency is decreased, that creates practical limits on what can be realized physically at reasonable cost.

At 7.3 MHz, 1λ = 133 feet and by the time we get to 1.8 MHz, 1 λ = 547 feet. Even a λ/2 dipole is very long on 160 meters. The result is that the average antenna for these bands is quite different from the higher bands, where Yagis and other relatively complex antennas dominate. In addition, vertical antennas can be more useful at low frequencies than they are on 20 meters and above because of the low heights (in wavelengths) usually available for horizontal antennas on the low bands. Much of the effort on the low bands is focused on how to build simple but effective antennas with limited resources. This section is devoted to antennas for use on amateur bands between 1.8 to 7 MHz.

The Importance of Low Angles for Low-Band DXing

In Chapter 3, The Effects of Ground, we emphasized the importance of matching the elevation response of your antennas as closely as possible to the range of elevation angles needed for communication with desired geographic areas. **Fig 1** shows the statistical 40-meter elevation angles needed over the entire 11-year solar cycle to cover the path from Boston, Massachusetts, to all of Europe. These angles range from 1° (at 9.6% of the time when the 40-meter band is open to Europe) to 28° (at 0.3% of the time).

Fig 1 also overlays the elevation pattern response of a 100-foot high flattop dipole on the elevation-angle statistics, illustrating that even at this height the coverage is hardly optimum to cover all the necessary elevation angles. While Fig 1 is dramatic in its own right, the data can be viewed in another way that emphasizes even more the importance of low elevation angles. **Fig 2** plots the the *cumulative distribution function*, the total percentage of time 40 meters is open from Boston to Europe, at or below each elevation angle. For example, Fig 2 says that 40 meters is open to Europe from Boston 50% of the time at an elevation angle of 9° or less. The band is open 90%



HFTA, Copyright ARRL 2002, by N6BV, Ver. 1.26B

Freq. = 7.1 MHz
Max. Gain: 11.1 dBi

FLAT.PRO
100 ft
Fig. of Merit: 8.2

Elev. Statistic File:
W1-MA-EU.PRN

Fig 1—Screen capture from *HFTA* (HF Terrain Assessment) program showing elevation response for 100-foot high dipole over flat ground on 7.1 MHz, with bar-graph overlay of the statistical elevation angles needed over the whole 11-year solar cycle from New England (Boston) to all of Europe. Even a 100-foot high antenna cannot cover all the necessary angles.



Fig 2—Another way of looking at the elevation statistics from Fig 1. This shows the percentage of time the 40-meter band is open, at or below each elevation angle, on the path from Boston to Europe. For example, the band is open 50% of the time at an angle of 9° or lower. It is open 90% of the time at an angle of 19° or lower.



Fig 3—The percentage of time the 40-meter band is open, at or below each elevation angle, for various DX paths from Boston: to Europe, South America, southern Africa, Japan, Oceania and south Asias. The angles are predominantly quite low. For example, on the path from Boston to Japan, 90% of the time when the 40-meter band is open, it is open at elevation angles less than or equal to 10°. Achieving good performance at these low takeoff angles requires very high horizontally polarized antennas, or efficient vertically polarized antennas.



Fig 4—The 40-meter statistics from the West Coast: from San Francisco to the rest of the DX world. Here, 90% of the time the path to Europe is open, it is at takeoff angles less than or equal to 11°. No wonder the hams living on mountain tops do best into Europe from the West Coast.



Fig 5—The situation on 80 meters from Boston to the rest of the DX world. Into Europe, 90% of the time the elevation angle is less than or equal to 20°. Into Japan from Boston, 90% of the time the angle is less than or equal to 12°.

of the time at an elevation angle of 19° or less.

Fig 3 plots the 40-meter elevation-angle data for six major geographic areas around the world from Boston. In general, the overall range of elevation angles for far-distant locations is smaller, and the angles are lower than for closer-in areas. For example, from Boston to southern Asia (India), 50% of the time the takeoff angles are 4° or less. On the path to Japan from Boston, the takeoff angles is less than or equal to 6° about 70% of the time. These are low angles indeed.

Fig 4 shows similar data for the 40-meter band from San Francisco, California, to the rest of the world. The path to southern Africa from the US West Coast is a very long-distance path, open some 65% of the time it is open at angles of 2° or less! The 40-meter path to Japan involves takeoff angles of 10° or less more than 50% of the time. If you are



Fig 6—From San Francisco to the rest of the world on 80 meters: 90% of the time on the path to Japan, the takeoff angle is less than or equal to 17°; 50% of the time the angle is less than or equal to 10°; 25% of the time the angle is less than or equal to 6°. A horizontally polarized antenna would have to be 600 feet above flat ground to be optimum at 6°!

fortunate enough to have a 100-foot high flattop dipole for 40 meters, at a takeoff angle of 10° the response would be down about 3 dB from its peak level at 20°. At an elevation angle of 5° the response would be about 8 dB down from peak. You can see why the California stations located on mountain tops do best on 40 meters for DXing.

Fig 5 shows the same percentage-of-time data for the 80-meter band from Boston to the world. Into Europe from Boston, the 80-meter elevation angle is 13° or less more than 50% of the time. Into Japan from Boston, 90% of the time the band is open is at a takeoff angle of 13° or less. (Note that these elevation statistics are computed for "undisturbed" ionospheric conditions. There are times when the incoming angles are affected by geomagnetic storms, and generally speaking the elevation angles rise under these conditions.)

Fig 6 shows the 80-meter data from San Francisco to the world. Low elevation angles dominate in this graph and high horizontal antennas would be necessary to optimal coverage. In fact, 50% of the time for all paths, the elevation angle is less than 10°.

In the rest of this chapter, we'll often compare horizontally polarized antennas at practical heights with vertically polarized antennas, usually at takeoff angles of 5° or 10°, angles useful for DX work. But first, let us look at situations where *high* takeoff angles are most useful.

Short/Medium-Range Communications

Not all hams are interested in working stations thousands of miles from them. Traffic handlers and rag chewers may, in fact, only be interested in *nearby* communications—perhaps out to 600 miles from their location.

For example, a ham in Boston may want to talk with his brother-in-law in Cleveland, OH, a path that is just over 550 miles away. Or an operator in Buffalo, NY, may be the net control station (NCS) for a regional net involving the states of New York and New Jersey. She needs to cover distances up to about 300 miles away.

Depending on the time of day, the most appropriate ham frequencies needed for nearby communications are the 40 and 80/75-meter bands, with 160 meters also a possibility during the night hours, particularly during low portions of the sunspot cycle. The elevation angles involved in such nearby distances are usually high, even almost directly overhead for distances beyond ground-wave coverage (which may be as short as a few miles on 40 meters). For example, the distance between the Massachusetts cities of Boston and Worchester is about 40 miles. On 40 meters, 40 miles is beyond ground-wave coverage. So you will need sky-wave signals that use the ionosphere to communicate between these two cities, where the elevation angle is 83°—very nearly straight up.

Hams using vertical antennas for communications with nearby stations may well find that their signals will be below the noise level typical on the lower bands, especially if they aren't running maximum legal power. Such relatively short-range paths involve so-called *NVIS*, "Near Vertical Incidence Skywave," a fancy name for HF communication systems covering nearby geographic areas. The US military discusses NVIS out to about 500 miles, encompassing the territory a brigade might cover. Elevation angles needed to cover distances from 0 to 500 miles range from about 40º to 90º. This also covers the circumstances involved in amateur communications, particularly in emergency situations.

The following section is adopted from the article "What's the Deal About NVIS?" that appeared in December 2005 *QST*. This article used an example of a hypothetical earthquake in San Francisco to analyze HF emergency communication requirements.

HAM RADIO RESPONSE IN NATURAL DISASTERS

One of San Francisco's somewhat less endearing nicknames is "the city that waits to die." When the *Big Earthquake* does come, you can be assured that all the cell phones and the land-line telephones will be totally jammed, making calling in or out of the San Francisco Bay Area virtually impossible. The same thing occurred in Manhattan on September 11, 2001. The Internet will also be severely affected throughout northern California because of its trunking via the facilities of the telephone network. Commercial electricity will be out in wide areas because power lines will be down. It's virtually certain that water mains will be out of commission too.

If the repeaters on the hills around the San Francisco Bay Area haven't been damaged by the shaking itself, there will be some ham VHF/UHF voice coverage in the intermediate area, at least until the backup batteries run down. But connecting to the dysfunctional telephone system will be difficult at best through amateur repeaters.

With little or no telephone coverage, an obvious need for ham radio communications to aid disaster relief would be from San Francisco to Sacramento, the state capital. Sacramento is 75 miles northeast of the Bay Area, well outside VHF/UHF coverage, so amateur HF will be required on this radio circuit. On-the-ground communications directly between emergency personnel (including the armed-forces personnel who will be brought into the rescue and rebuilding effort) will often be difficult on VHF/UHF since San Francisco is a hilly place. So HF will probably be needed even for short distance, operator-to-operator or operator-to-communications center work. Throughout the city, portable HF stations will have to be quickly set up and staffed to provide such communications.

Hams used to half jokingly call short range HF communications on 40 and 80 meters "cloud warming." This is an apt description, because the takeoff angles needed to launch HF signals up into the ionosphere and then down again to a nearby station are almost directly upwards. **Table 1** lists the distance and takeoff angles from San Francisco to various cities around the western part of the USA. The distance between San Francisco and Sacramento is about 75 miles, and the optimum takeoff angle is about 78°. Launching such a high-angle signal is best done using horizontally polarized antennas mounted relatively close to the ground.

GEOGRAPHIC COVERAGE FOR NVIS

Figure 7A shows the geographic area coverage around San Francisco for a 100-W, 7.2-MHz station using an inverted V dipole. The center of this antenna is 20 feet above flat

Table 1
Average Elevation Angles for Target Destinations from San Francisco

Location	*Distance Miles*	*Average Elevation Angle, Degrees*
San Jose, CA	43	80
Sacramento, CA	75	78
Fresno, CA	160	63
Reno, NV	185	60
Los Angeles	350	44
San Diego	450	42
Portland, OR	530	30
Denver, CO	950	18
Dallas, TX	1500	8



Fig 8—Layout for two band inverted V dipoles for 40 and 80 meters. The two dipoles are fed together at the center and are laid out at right angles to each other to minimize interaction between them. Each end of both dipoles is kept 8 feet above ground for personnel safety.



(A)

(B)

Fig 7—At A, Predicted 40 meter geographic coverage plot for a 100 W transmitter in December at 0000 UTC (near sunset), for a SSN (Smoothed Sunspot Number) of 20. The antennas used are 20 foot-high inverted V dipoles. At B, 40 meter coverage for same date and time, but for 100 foot-high flattop dipoles. Most of California is well covered with S9 signals in both cases, but there is more susceptibility in the higher dipole case to thunderstorm crashes coming from outside California, for example from Arizona or even Texas. Such noise can interfere with communications inside California.



Fig 9—Elevation plots for different 40 meter antennas above flat ground with average ground characteristics (5 mS/m conductivity and dielectric constant of 13). The 10 foot-high flattop dipole and the 20 foot-high inverted V dipoles both have close to the same characteristics. Note that there is a null in the response of the 100 foot-high flattop dipole at a 42° elevation angle. The gain there is roughly that of a 2 foot-high dipole!


Welcome to Vaisala Lightning Explorer®

Color Key (Minutes from Current Map End Time)

Total Strikes: 60898

Time: 08/10/05 22:00:00 GMT **to** 08/11/05 00:00:00 GMT

Fig 10—The distribution of lightning strikes across the USA for August 10, 2005 from 2200 to 0000 UTC, in the afternoon California time. There are lots of lightning strikes in the US during the summer—60,898 of them in this two-hour period! (*Courtesy Vaisala Lightning Explorer.*)

ground and the ends are 8 feet high. An actual implementation of such an antenna could be as an 80-meter inverted V, fed in parallel with a 40-meter inverted V dipole at a 90° angle. See **Fig 8**. The 8-foot height puts the ends high enough to prevent RF burns to humans (or most animals). The low height of the antenna above ground means that the azimuthal pattern is omnidirectional for high elevation angles.

Fig 7 was generated using the *VOAAREA* program, part of the *VOACAP* propagation-prediction suite, for the month of December. This was for 0000 UTC, close to sundown, for a low period of solar activity (Smoothed Sunspot Number, SSN of 20). The receiving stations were also assumed to be using identical inverted-V dipoles.

You can see that almost the whole state of California is covered with S9 signals, minus only a thin slice of land near the Mexican border in the southeast portion of the state, where the signal drops to S7. Signals from Texas are predicted to be only S5 or less in strength. Signals (or thunderstorm static) coming from, say, Louisiana would be several S units weaker than signals from central Texas.

Now take a look at Fig 7B. Here, the date, time and solar conditions remain the same, but now the antennas are 100-foot high flattop dipoles. California is still blanketed with S9 signals, save for an interesting crescent-shaped slice near Los Angeles, where the signal drops down to S7. Close investigation of this intriguing drop in signal strength reveals that the necessary elevation angle, 44°, from San Francisco to this part of southern California falls in the first null of the 100-foot high antenna's elevation pattern. See **Fig 9**, which shows the elevation patterns for five 40-meter antennas at different heights. In the null at a 44° takeoff angle, the 100-foot high dipole is just about equal to a 2-foot high dipole. We'll discuss 2-foot high dipoles in more detail later.

For most of California, the problem with 100-foot high 40-meter antennas is that interfering signals from Texas, Colorado or Washington State will *also* be S9 in San Francisco. So will static crashes coming from thunderstorms all over the West and much of the Gulf Coast. (Ed Farmer, AA6ZM, joked once that the Army doesn't have any problem with interfering signals—they just call in an airstrike. We hams don't generally have this ability, although we occasionally call in the FCC.) See **Fig 10**, which shows a typical distribution of thunderstorms across the US in the late afternoon, California time, in mid-August. There certainly are a lot of thunderstorms raging around the country in the summer.

The signal-to-noise and signal-to-interference ratios for a 20-foot high inverted V dipole will be superior for medium-



Fig 11—VOACAP calculations for a 350 mile path from San Francisco to Los Angeles, using 10 foot-high flattop dipoles. This plot shows the signal strength in S Units ("S10" = S9+10) for a worst-case month/SSN combination—winter solstice, in December, for a low level of solar activity (SSN = 20). The 40-meter signal drops to a very low level during the night because the MUF drops well below 7.2 MHz. The 80-meter signal drops in the afternoon because of D-layer absorption. For 24-hour communications on this path, the rule of thumb is to select 40 meters during the day and 80 meters during the night.



Fig 12—Signal strengths for the San Francisco to Los Angeles path for a worst-case month/ SSN combination—summer solstice, in June, for a high level of solar activity (SSN = 120). Now 80 meters drops out more dramatically during the daylight hours, due to increased D-layer absorption. At this high level of solar activity, 40 meters remains open 24 hours with reasonable signal levels. However, the NVIS rule-of-thumb still holds: Use 40 meters during the day; 80 meters at night.

range distances, say out to 500 miles from the center, compared to a 100-foot high antenna. The 20-foot high antenna can discriminate against medium-angle thunderstorm noise in the late afternoon coming from the Arizona desert, although it wouldn't help much for thunderstorms in the Sierra Nevada in central Nevada, which are arriving in San Francisco at high angles, along with the desired NVIS signals.

This is the essence of what NVIS means. NVIS exploits the difference in elevation pattern responses of low horizontally polarized antennas compared to higher horizontal antennas, or even verticals. Over the years, many hams have been lead to believe that higher is always better. This is not quite so true for consistent coverage of medium or short distance signals!

If NVIS only involved putting up a low horizontally polarized antenna on 40 meters the story would end here. However, real cloud warming is more complicated. It also involves the intelligent choice of more than just one operating frequency to achieve reliable all day, all-night communications coverage.

Fig 11 shows the signal strength predicted using *VOACAP* for the 350-mile path from San Francisco to Los Angeles for the month of December for a period of low solar activity (SSN of 20). The antennas used in this case are 10-foot high dipoles, just for some variety. These act almost like 20-foot high Inverted V dipoles. December at a low SSN was chosen as a worst-case scenario because the *winter solstice* occurs on December 21. This is the day that has the fewest hours of daylight in the year. (Contrast this with the *summer solstice*, on June 21, which has the most hours of daylight in the year.) Note that the upper signal limit in Fig 11 is "S10"—a fictitious quantity that allows easier graphing.

S10 is equivalent to S9+, or at least S9+10 dB.

The 40-meter curve in Fig 11 shows that the MUF (maximum usable frequency) actually drops below the 7.2 MHz amateur band after sunset. The signal becomes quite weak for about 14 hours during the night, from about 0300 to 1700 UTC. In a period of low solar activity the 40-meter band thus becomes strictly a *daytime band* on this medium-distance path.

The 80-meter curve in Fig 11 shows strong signals after dusk, through the night and up until about an hour after sunrise. After sunrise, 80 meters starts to suffer absorption in the D layer of the ionosphere and hence the signal strength drops. Here, 80 meters is a true *nighttime band*.

Let's see what happens from San Francisco to Los Angeles during a period of high solar activity (SSN of 120) during the summer solstice in June. **Fig 12** shows that 40 meters now stays open all hours of the day due to the greater number of hours of sunlight in June and because the ionosphere becomes more highly ionized by higher solar activity. Meanwhile, 80 meters still remains a nighttime band during these conditions on this path.

Now, let's look at a shorter-distance path—our 75-mile emergency communications path from San Francisco to Sacramento. We'll again use June during the summer solstice, at a high level of solar activity (SSN of 120) because this represents another worst-case scenario. **Fig 13** shows that 40 meters remains open on this path all day, dropping to a lower signal level just before sunrise. At sunrise, the MUF drops close to 7.2 MHz. 80 meters is still mainly a nighttime band to Sacramento, even though it does yield workable signal levels even during the daylight hours. However, 40 meters is better from 1200 to 0400 UTC, so 40 would be still the right daytime band for this path during the day.

CHOOSING THE RIGHT NVIS FREQUENCY

You can see that a pattern is developing here for efficient NVIS short/medium-distance communications out to 500 miles:

- You should pick a frequency on 40 meters during the day.
- You should pick a frequency on 80 meters during the night.
- You should choose an antenna that emphasizes moderate to high elevation angles, from 40° to almost directly overhead at 90°.

"What about 60 meters?" you might ask. The characteristics on 60 meters fall in-between 40 and 80 meters, although it resembles 40 meters more closely. With characteristics close to that of 40, but with only five channels available and a 50-W power limit, the 60-meter band is of low utility for serious NVIS use.

What about 160 meters? For 100-W level radios, even at the worst-case month or during low solar activity, the critical frequency doesn't fall below 3.8 MHz often enough to destroy the ability to communicate, even for short distances. That is a relief, considering that installing a 160-meter half-wave dipole involves a 255-foot wingspan, and it would need to be elevated at least 30 feet in the center. A short loaded vertical such as a 160-meter mobile whip would have poor response at the high elevation angles needed for NVIS. You could probably put a monster 160-meter horizontal dipole up at a permanent location, but hauling such a thing around in the field would not be an easy task.

SOME OTHER OBSERVATIONS ABOUT NVIS—STRATEGY

You could pose the question about whether NVIS is an operating *mode* or whether it is actually an operating *strategy*. We maintain that NVIS is a strategy. It involves choosing both appropriate frequencies and then appropriate antennas for those frequencies. Fig 13 does show that on short-distance



Fig 13—Signal strengths for a 75 mile path—San Francisco to Sacramento. This is for June and SSN = 120. Either band could be used successfully over the full 24-hour period because signal levels are always higher than S6. But the simple NVIS rule-of-thumb still holds: Use 40 meters during the day; 80 meters at night. This simplifies giving instructions to operators unaccustomed to the use of HF.

paths, such as between San Francisco and Sacramento, you could stay on 80 meters all day and night. But if you have to give a single rule-of-thumb to operators who are not very experienced at operating HF, we would tell them to operate on the higher frequency band during the day and on the lower frequency band at night.

SOME OTHER OBSERVATIONS ABOUT NVIS—ANTENNA HEIGHT

Some NVIS aficionados have advocated placing dipoles only a few feet over ground, something akin to saying, "If low is good for NVIS, then lower must be even better." Now we are not claiming that a very low antenna *won't* work in specific instances—for example, covering a small state such as Rhode Island or even just the San Francisco Bay Area.

It certainly is convenient to mount a 40-meter dipole on some 2-foot high red traffic cones! You should be very skeptical, however, about the ability of such antennas to cover all of a large state, such as California or Texas, especially on 80 meters. **Fig 14** shows the computed elevation responses for a number of 80-meter antennas, including a 2-foot-high dipole.

Fig 15B shows the 80 meter geographic coverage plot for 2-foot-high flattop dipoles, compared with the plot in Fig 15A for 20-foot-high inverted V dipoles on both ends of the path. The 2-foot-high dipoles produce about two S-units less signal across all of California than the 20-foot-high inverted V dipoles, at 0300 UTC in December, with an SSN of 20. The reason is that a low dipole will suffer more losses in the ground under it.

The differential between California signals and possible interfering signals from, say, New Mexico, is predicted to be four S-units, the same as it is for the higher inverted V dipole



Fig 14—Elevation response patterns for 80 meter antennas over average soil. The shapes track each other rather well, remaining parallel for heights from 2 to 66 feet over flat ground. The 2 foot dipole is substantially down, about 9 dB, from the 20 foot inverted V dipole at all angles.



(A)

(B)

Fig 15—Geographic coverage plots for December, SSN = 20, 0300 UTC. At A, antennas are 20 foot-high inverted V dipoles over Average soil. At B, antennas are 2-foot-high flattop dipoles over Average soil. The response for the 2-foot-high antennas is down about 2 S Units, 8 to 12 dB for a typical communications receiver.

at 20 feet. Thus there is no real advantage in terms of signal-to-interference ratio or signal-to-noise ratio (for thunderstorm static crashes) for either height. This is because the shape of all the response curves in Fig 14 below 20 feet essentially track each other in parallel.

However, the lower the antenna, the lower the transmitted signal strength. Physics remain physics. And if you are in an emergency situation operating on batteries, you could reduce power from 100 W to 10 W with a 20-foot high inverted-V antenna and still maintain the same signal strength as a 2-foot high dipole at 100W.

LOW NVIS ANTENNAS AND LOCAL POWERLINE NOISE

Some advocates of really low antennas have stated that the received noise is much lower than that received from higher antennas, and this therefore leads to better signal-to-noise ratios (SNR). How much this is true depends on the source of the noise. If the noise comes from distant thunderstorms, then the SNR advantage going to a 2-foot antenna from a 20-foot-high one is insignificant, as Fig 15 indicates.

If noise is from an arcing insulator on a HV power line half a mile away, that noise will arrive at the antenna as a ground-wave signal. We calculate that the 2-foot antenna receives 4.4 dB less noise by groundwave than a 20-foot-high inverted V dipole. However, at an incoming elevation angle of 45º—suitable for a signal going from Los Angeles to San Francisco—the signal would be down 7.1 dB on the low dipole compared to the higher antenna. The net loss in SNR for the 2-foot-high dipole is thus 7.1– 4.4 or 2.7 dB. Close, but no cigar. Summarizing about really low NVIS antennas:

- A 2-foot-high dipole yields weaker signals, but without an SNR advantage compared to its more elevated brethren.
- A 2-foot-high dipole is a lot easier to trip over at night. We would call this a "knee biter" (or maybe an "ankle biter" if you're really tall).
- You (and your dog) can easily get RF burns from an antenna that is only 2 feet off the ground.

This is not a winning strategy to make friends or QSOs, it seems. But still, a really low dipole may serve your short-range communication needs just fine. But remember, that just as "higher is better" isn't universally true for NVIS (or even longer range) applications, "lower is better" isn't a panacea either.

ELEVATION ANGLES FOR MODERATE DISTANCES ON 75/80 METERS

Fig 16 shows the elevation angles statistics for a 75-meter, 550-mile path from Boston to Cleveland, together with overlays of the elevation patterns for several different types of antennas. These elevation statistics cover all parts of the 11-year solar cycle for this path. The responses for the popular G5RV antenna (described later in this chapter) are shown for two different heights above flat ground: 50 and 100 feet. An 80-meter half-wave sloper ("full sloper") and an 80-meter ground-plane antenna are also shown. All antenna patterns are for "average ground" constants of 5 mS/m conductivity and a dielectric constant of 13.



Fig 16—80/75-meter elevation statistics for all portions of the 11-year solar cycle for the path from Cleveland, Ohio, to Boston, Massachusetts, together with the elevation responses for four different multiband antennas. The 100-foot high horizontally polarized G5RV performs well over the entire range of necessary takeoff elevation angles.

At the statistically most significant takeoff angles around 50°, the two horizontally polarized G5RV antennas are about equal. At the second-highest elevation peak near 30°, the 100-foot G5RV has about a 4-dB advantage over its lower counterpart. The full sloper has comparable performance to the 100-foot high G5RV from 1° to about 20° and then gradually rises to its peak at angles higher than 70°. The full sloper is superior to the 50-foot horizontal G5RV at low takeoff elevation angles. The 80-meter ground plane has a deep null directly overhead. At an elevation angle of 70° it is down some 16 dB compared to the 50-foot high horizontal G5RV.

The advantage of antennas suitable for high-angle radiation was vividly demonstrated during a 75-meter QSO one fall evening between N6BV/1 in southern New Hampshire and W1WEF in central Connecticut. This involved a distance of about 100 miles and W1WEF was using his Four Square vertical array. Although W1WEF's signal was S9 on the Four Square, N6BV/1 suggested an experiment. Instead of connecting the so-called "dump power" connector on his Comtek ACB-4 hybrid phasing coupler to a 50-Ω dummy load (the normal configuration), W1WEF switched the dump power to his 100-foot high 80-meter horizontal dipole. W1WEF's signal came up more than 20 dB! The approximately 100-W of power that would otherwise be "wasted" in the dummy load was converted to useful signal.

ELEVATION ANGLES FOR MODERATE DISTANCES ON 40 METERS

Fig 17 shows the situation for the 40-meter band, from Boston to Cleveland, together with the same antennas used for 80 meters in Fig 16. Note that the 100-foot high horizontally



Fig 17—40-meter elevation statistics for the Cleveland to Boston path, together with elevation patterns for four antennas. Here, the 100-foot high horizontally polarized G5RV would have a null in the middle of the range of elevation angles needed for consistent performance on this path. For multiband use on this path to relatively nearby stations, the 50-foot high horizontal antenna would be a better choice than the 100-foot high antenna.

polarized G5RV has about a 16-dB null at an elevation angle of 43°. This doesn't affect things for low elevation angles, but it certainly has a profound effect on signals arriving between about 30° to 60°, especially when compared to the 50-foot high horizontal G5RV. The 40-meter full sloper beats out the high horizontal antenna from about 35° to 50°. And the ground plane is obviously not the antenna of choice for this moderate-range path from Boston to Cleveland, although it is still a good performer on longer-distance paths, with their low takeoff angles.

A 100-foot high multiband dipole is about ⅜-λ high on 75/80 meters. It is an excellent antenna for general-purpose local and DXing operation. But the same dipole used on 40 meters becomes ¾-λ high. At that height, the nulls in its elevation pattern give large holes in coverage for nearby 40-meter contacts. Many operators have found that a 40- to 50-foot high dipole on 40 meters gives them far superior performance for close-in QSOs, when compared to a high dipole, or even a high 2-element 40-meter Yagi.

NVIS SUMMARY

The use of NVIS strategies to cover close-in and intermediate distance communications within about 600 miles involves the intelligent choice of low HF frequencies. As a rule-of-thumb for ham band NVIS, 40 meters is recommended for use during the day; 80 meters during the night.

NVIS involves the choice of antennas suitable for this strategy. Horizontally polarized dual-band 80 and 40-meter flattop dipoles that are mounted higher than about 10 feet high will work adequately for portable operations. Dual-band 80 and 40-meter inverted V dipoles supported 20 feet above the ground at the center can also work well in portable operations.

Single-band 40-meter flattop antennas about 30 feet high and 80-meter flattop antennas about 60 feet high can do a good job for fixed locations.

Horizontal Antennas for the Low Bands

As shown in Chapter 3, The Effects of Ground, and here, radiation angles from horizontal antennas are a very strong function of the height above ground in wavelengths. Typically for DX work heights of λ/2 to 1 λ are considered to be a minimum. As we go down in frequency these heights become harder to realize. For example, a 160-meter dipole at 70 feet is only 0.14 λ high. This antenna will be very effective for local and short distance QSOs but not very good for DX work. Despite this limitation, horizontal antennas are very popular on the lower bands because the low frequencies are often used for short range communications, local nets and rag chewing. Also horizontal antennas do not require extensive ground systems to be efficient.

DIPOLE ANTENNAS

Half-wave dipoles and variations of these can be a very good choice for a low band antenna. A variety of possibilities are shown in **Fig 18**. An untuned or "flat" feed line is a logical choice on any band because the losses are low, but this generally limits the use of the antenna to one band. Where only single-band operation is wanted, the λ/2 antenna fed with open-wire line is one of the most popular systems on the 3.5 and 7-MHz bands.

If the antenna is a single-wire affair, its impedance is in the vicinity of 60 Ω, depending on the height and the ground characteristics. The most common way to feed the antenna is with 50- or 75-Ω coaxial line. Heavy coaxial lines present support problems because they are a concentrated weight at the center of the antenna, tending to pull the center of the antenna down. This can be overcome by using an auxiliary pole to take at least some of the weight of the line. The line should come away from the antenna at right angles, and it can be of any length.

Folded Dipoles

A folded dipole (Fig 18B and C) has an impedance of about 300 Ω, and can be fed directly with any length of 300-Ω line. The folded dipole can be made of ordinary wire spaced by lightweight wooden or plastic spacers, 4 or 6 inches long, or a piece of 300 or 450-Ω twin-lead or ladder line.

A folded dipole can be fed with a 600-Ω open wire line with only a 2:1 SWR, but a nearly perfect match can be ob-


468
f (MHz)
72 Ω Twin—lead
or Coaxial Lines
Any Length
C
(A)
468
f (MHz)
Two #12 or #14 Wires,
Spaced 4 to 6 Inches
300 Ω Twin—Lead
Any Length
C
(B)
468
f (MHz)
300 Ω
Twin -Lead
Weatherproof Seal
300 Ω Twin -Lead
Any Length
C
(C)
468
f (MHz)
Three #12 or #14 Wires,
Spaced 4 to 6 Inches with
Wood or Plastic Spacers
#14 Spaced 5 Inches
or #12 Spaced 6 Inches
C
(D)

Fig 18—Half-wavelength antennas for single band operation. The multiwire types shown in B, C and D offer a better match to the feeder over a somewhat wider range of frequencies but otherwise the performances are identical. The feeder should run away from the antenna at a right angle for as great a distance as possible. In the coupling circuits shown, tuned circuits should resonate to the operating frequency. In the series-tuned circuits of A, B, and C, high L and low C are recommended, and in D the inductance and capacitance should be similar to the output-amplifier tank, with the feeders tapped across at least ½ the coil. The tapped-coil matching circuit shown in Chapter 25 can be substituted in each case.

tained with a three-wire dipole fed with either 450-Ω ladder line or 600-Ω open wire line. One advantage of the two- and three-wire antennas over the single wire is that they offer a better match over a wider band. This is particularly important if full coverage of the 3.5-MHz band is contemplated.

Inverted-V Dipole

The halves of a dipole may be sloped to form an inverted V, as shown in **Fig 19**. This has the advantages of requiring only a single high support and less horizontal space. There will be some difference in performance between a normal horizontal dipole and the inverted V as shown by the radiation patterns in **Fig 20**. There is small loss in peak gain and the pattern is less directional.

Sloping of the wires results in a raising of the resonant frequency and a decrease in feed-point impedance and



Fig 19—The inverted-V dipole. The length and apex angle should be adjusted as described in the text.



Fig 20—At A, elevation and at B, azimuthal radiation patterns comparing a normal 80-meter dipole and an inverted-V dipole. The center of both dipoles is at 65 feet and the ends of the inverted V are at 20 feet. The frequency is 3.750 MHz.

bandwidth. Thus, for the same frequency, the length of the dipole must be increased somewhat. The angle at the apex is not critical, although it should probably be made no smaller than 90°. Because of the lower impedance, a 50-Ω line should be used. For those who are dissatisfied with anything but a perfect match, the usual procedure is to adjust the angle for lowest SWR while keeping the dipole resonant by adjustment of length. Bandwidth may be increased by using multiconductor elements, such as a cage configuration.

PHASED HORIZONTAL ARRAYS

Phased arrays with horizontal elements, which provide some directional gain, can be used to advantage at 7 MHz, if they can be placed at least 40 feet above ground. At 3.5 MHz heights of 70 feet or more are needed for any real advantage.



Fig 21—Directional antennas for 7 MHz. To realize any advantage from these antennas, they should be at least 40 feet high. At A, system is bidirectional. At B, system is unidirectional in a direction depending upon the tuning conditions of the parasitic element. The length of the elements in either antenna should be exactly the same, but any length from 60 to 150 feet can be used. If the length of the antenna at A is between 60 and 80 feet, the antenna will be bidirectional along the same line on both 7 and 14 MHz. The system at B can be made to work on 7 and 14 MHz in the same way, by keeping the length between 60 and 80 feet.

Many of the driven arrays discussed in Chapter 8 and even some of the Yagis discussed in Chapter 11 can be used as fixed directional antennas. If a bidirectional characteristic is desired, the W8JK array, shown in **Fig 21A**, is a good one. If a unidirectional characteristic is required, two elements can be mounted about 20 feet apart and provision included for tuning one of the elements as either a director or reflector, as shown in Fig 21B.

The parasitic element is tuned at the end of its feed line with a series or parallel-tuned circuit (whichever would normally be required to couple power into the line), and the proper tuning condition can be found by using the system for receiving and listening to distant stations along the line to the rear of the antenna. Tuning the feeder to the parasitic element can minimize the received signals from the back of the antenna. This is in effect adjusting the antenna for maximum front-to-back ratio. Maximum front-to-back does not occur at the same point as maximum forward gain but the loss in forward gain is very small. Adjusting the antenna for maximum forward gain (peaking received signals in the forward direction) may increase the forward gain slightly but will almost certainly result in relatively poor front-to-back ratio.

A MODIFIED EXTENDED DOUBLE ZEPP

If the distance between the available supports is greater than λ/2 then a very simple form of a single wire collinear array can be used to achieve significant gain. The *extended double Zepp* antenna has long been used by amateurs and is discussed in Chapter 8, Multielement Arrays. A simple variation of this antenna with substantially improved bandwidth can be very useful on 3.5 and 7.0 MHz. The following material has been taken from an article by Rudy Severns, N6LF, in *The ARRL Antenna Compendium Vol 4*.

The key to improving the characteristics of a standard double-extended Zepp is to modify the current distribution. One of the simplest ways to do this is to insert a reactance(s) in series with the wire. This could either be an inductor(s) or a capacitor(s). In general, a series capacitor will have a higher Q and therefore less loss. With either choice it is desirable to use as few components as possible.

As an initial trial at 7 MHz, only two capacitors, one on each side of the antenna, were used. The value and position of the capacitors was varied to see what would happen. It quickly became clear that the reactance at the feed point could be tuned out by adjusting the capacitor value, making the antenna look essentially like a resistor over the entire band. The value of the feed-point resistance could be varied from less than 150 Ω to over 1500 Ω by changing the location of the capacitors and adjusting their values to resonate the antenna.

A number of interesting combinations were created. The one ultimately selected is shown in **Fig 22**. The antenna is 170 feet in length. Two 9.1 pF capacitors are located 25 feet out each side of the center. The antenna is fed with 450-Ω transmission line and a 9:1 three-core Guanella balun used at the transmitter to convert to 50 Ω. The transmission line can be any convenient length and it operates with a very low SWR.



Fig 22—Schematic for modified N6LF Double Extended Zepp. Overall length is 170 feet, with 9.1 pF capacitors placed 25 feet each side of center.



Fig 23—Azimuth pattern for N6LF Double Extended Zepp (solid line), compared to classic Double Extended Zepp (dashed line). The main lobe for the modified antenna is slightly broader than that of the classic model, and the sidelobes are suppressed better.

That's all there is to it. The radiation pattern, overlaid with that for a standard DEZepp for comparison, is shown in **Fig 23**. The sidelobes are now reduced to below 20 dB. The main lobe is now 43° wide at the 3-dB points, as opposed to 35° for the original DEZepp. The antenna has gain over a dipole for > 50° now and the gain of the main lobe has dropped only 0.2 dB below the original DEZepp.

Experimental Results

The antenna was made from #14 wire and the capacitors were made from 3.5-inch sections of RG-213, shown in **Fig 24A**. Note that great care should be taken to seal out moisture in these capacitors. The voltage across the capacitor for 1.5 kW will be about 2000 V so any corona will quickly destroy the capacitor.

A silicon sealant was used and then both ends covered



Fig 24—Construction details for series capacitor made from RG-213 coaxial cable. At A, the method used by N6LF is illustrated. At B, a suggested method to seal capacitor better against weather is shown, using a section of PVC pipe with end caps.



Fig 25—Measured SWR curve across 40-meter band for N6LF DEZepp.

with coax seal, finally wrapping it with plastic tape. The solder balls indicated on the drawing are to prevent wicking of moisture through the braid and the stranded center conductor. This is a small but important point if long service out in the weather is expected. An even better way to protect the capacitor would be to enclose it in a short piece of PVC pipe with end caps, as shown in Fig 24B.

Note that all RG-8 type cables do not have exactly the same capacitance per foot and there will also be some end effect adding to the capacitance. If possible the capacitor should be trimmed with a capacitance meter. It isn't necessary to be too exact—the effect of varying the capacitance ±10% was checked and the antenna still worked fine.



Fig 26—75/80-meter modified Double Extended Zepp, designed using *NEC Wires*. At A, a schematic is shown for antenna. At B, SWR curve is shown across 75/80-meter band. Solid line shows measured curve for W7ISV antenna, which was pruned to place SWR minimum higher in the band. The dashed curve shows the computed response when SWR minimum is set to 3.8 MHz.

The results proved to be close to those predicted by the computer model. **Fig 25** shows the measured value for SWR across the band. These measurements were made with a Bird directional wattmeter. The worst SWR is 1.35:1 at the low end of the band.

Dick Ives, W7ISV, erected an 80-meter version of the antenna, shown in **Fig 26A**. The series capacitors are 17 pF. Since he isn't interested in CW, Dick adjusted the length for the lowest SWR at the high end of the band, as shown in the SWR curve (Fig 26B). The antenna could have been tuned somewhat lower in frequency and would then provide an SWR < 2:1 over the entire band, as indicated by the dashed line.

This antenna provides wide bandwidth and moderate gain over the entire 75/80-meter band. Not many antennas will give you that with a simple wire structure.

Vertical Antennas

On the low bands quarter-wave high vertical antennas become increasingly attractive, especially for DX work, because they provide a means for lowering the radiation angle. This is especially true where practical heights for horizontally polarized antennas are too low. In addition, verticals can be very simple and unobtrusive structures. For example, it is very easy to disguise a vertical as a flagpole. In fact an actual flagpole may be used as a vertical. Performance of a vertical is determined by several factors:

- Height of the vertical portion of the radiator
- The ground or counterpoise system efficiency, if one is used
- Ground characteristics in the near- and far-field regions
- The efficiency of loading elements and matching networks

THE HALF-WAVE VERTICAL DIPOLE (HVD)

The simplest form of vertical is that of a half-wave vertical dipole, an HVD. This is a horizontal dipole turned 90º so that it is perpendicular to the ground under it. Of course, the top end of such an antenna must be at least a half wave above the ground or else it would be touching the ground. This poses quite a construction challenge if the builder wants a free-standing low-frequency antenna. Hams fortunate enough to have tall trees on their property can suspend wire HVDs from these trees. Similarly, hams with two tall towers can run rope catenaries between them to hold up an HVD.

A vertical half-wave dipole has some operational advantages compared to a more-commonly used vertical configuration—the quarter-wave vertical used with some sort of above-ground counterpoise or an on-ground radial system. See **Fig 27** and 27B, which shows the two configurations discussed here. In each case, the lowest part of each antenna is 8 feet above ground, to prevent passersby from being able to touch any live wire. Each antenna is assumed to be made of #14 wire resonant on 80 meters.



Fig 27—At A, a 80-meter half-wave vertical dipole elevated 8 feet above the ground. The feed line is run perpendicularly away from the dipole. At B, a "ground plane" type of quarter-wave vertical, with four elevated resonant radials. Both antennas are mounted 8 feet above the ground to keep them away from passersby.

Feeding a Half-Wave Vertical Dipole

Fig 28 compares elevation patterns for the two antennas for "average ground." You can see that the half-wave vertical dipole has about 1.5 dB higher peak gain, since it compresses the vertical elevation pattern down somewhat closer to the horizon than does the quarter-wave ground plane. Another advantage to using a half-wave radiator besides higher gain is that less horizontal "real estate" is needed compared to a quarter-wave vertical with its horizontal radials.

The obvious disadvantage to an HVD is that it is taller than a quarter-wave ground plane. This requires a higher support (such as a taller tree) if you make it from wire, or a longer element if you make it from telescoping aluminum tubing.

Another problem is that theory says you must dress the feed line so that it is perpendicular to the half-wave radiator. This means you must support the coax feed line above ground for some distance before bringing the coax down to ground level. A question immediately arises: How far must you go out horizontally with the feed line before going to ground level to eliminate common-mode currents that are radiated onto the coax shield? Such common-mode currents will affect the feed-point impedance as well as the radiation pattern for the antenna system. Quite a bit of distortion in the azimuthal pattern can be created if common-mode currents aren't suppressed, usually by using a common-mode choke, also known as a current balun.



Fig 28—A comparison of the elevation patterns for the two antennas in Fig 27. The peak gain of the HVD is about 1.5 dB higher than that for the quarter-wave ground-plane radiator with radials.



Fig 29—A 20-meter HVD whose bottom is 8 feet above ground. This is fed with a λ/2 of RG-213 coax. This system uses a common-mode choke at the feed point and another λ/4 down the line. The resulting azimuthal radiation pattern is within 0.4 dB of being perfectly circular. The "wingspan" of this antenna system is 27 feet from the radiator to the point where the coax comes to ground level.

Constructing such a common-mode choke is very simple: Three large ferrite beads are slipped over the coax (before the connectors are soldered on or else they won't fit!) and taped in place. The only problem with this scheme is that an additional support (some sort of "skyhook") is required to support the coax horizontally. Let's try to simplify the installation, by slanting the feed-line coax down to ground from the feed point at a fairly steep angle of about 30º from vertical. See **Fig 29**.

Note that the bottom end of the coax in Fig 29 is grounded to a ground rod. This serves several purposes—this serves as a mechanical connection to hold the coax in place and it provides some protection against lightning strikes. Now, as a purely practical matter, just how picky are we being here? What if we skip the second common-mode choke and just use one at the feed point? The computer models predicts that there will be some distortion in the azimuthal pattern—about 1.1 dB worth. Whether this is serious is up to you. However, you may find other problems with common-mode currents on the coax shield—problems such as RF in the shack or variable SWR readings depending on the way coax is routed in the shack. The addition of three extra ferrite beads to suppress the common-mode currents is cheap insurance.

Later in this chapter we'll discuss shortened vertical antennas, ones arranged both as vertical dipoles and as vertical monopoles with radial systems.

MONOPOLE VERTICALS WITH GROUND PLANE RADIALS

For best performance the vertical portion of a ground-plane type of antenna should be λ/4 or more, but this is not an absolute requirement. With proper design, antennas as short as 0.1 λ or even less can be efficient and effective. Antennas shorter than λ/4 will be reactive and some form of loading and perhaps a matching network will be required.

If the radiator is made of wire supported by nonconducting material, the approximate length for λ/4 resonance can be found from:

$$\ell_{\text{feet}} = \frac{234}{f_{\text{MHz}}} \qquad \text{(Eq 1)}$$

For tubing, the length for resonance must be shorter than given by the above equation, as the length-to-diameter ratio is lower than for wire (see Chapter 2, Antenna Fundamentals). For a tower, the resonant length will be shorter still. In any case, after installation the antenna length (height) can be adjusted for resonance at the desired frequency.

The effect of ground characteristics on losses and elevation pattern is discussed in detail in Chapter 3, The Effects of Ground. The most important points made in that discussion are the effect of ground characteristics on the radiation pattern and the means for achieving low ground-loss resistance in a buried ground system. As ground conductivity increases, low-angle radiation improves. This makes a vertical very attractive to those who live in areas with good ground conductivity. If your QTH is on a saltwater beach, then a vertical would be very effective, even when compared to horizontal antennas at great height.

When a buried-radial ground system is used, the efficiency of the antenna will be limited by the loss resistance of the ground system. The ground can be a number of radial wires extending out from the base of the antenna for about λ/4. Driven ground rods, while satisfactory for electrical safety and for lightning protection, are of little value as an RF ground for a vertical antenna, except perhaps in marshy or beach areas. As pointed out in Chapter 3, many long radials are desirable. In general, however, a large number of short radials are preferable to only a few long radials, although the best system would have 60 or more radials longer than λ/4. An elevated system of radials or a ground screen (*counterpoise*) may be used instead of buried radials, and can result in an efficient antenna.

ELEVATED RADIALS AND COUNTERPOISES

Elevated radials, isolated from ground, can be used in place of an extensive buried radial system. Work by Al Christman, K3LC (ex-KB8I), has shown that 4 to 8 elevated radials can provide performance comparable to a 120 λ/4-long buried wires. This is especially important for the low bands, where such a buried ground system is very large and impractical for most amateurs. An elevated ground system is sometimes referred to as a *ground plane* or *counterpoise*. **Fig 30** compares buried and elevated ground systems, showing the difference in current flow in the two systems.

An elevated ground can take several forms. A number of wires arranged with radial symmetry around the base of the antenna is shown in Fig 30B. Four radials are normally



Fig 30—How earth currents affect the losses in a short vertical antenna system. At A, the current through the combination of C_E and R_E may be appreciable if C_E is much greater than C_W, the capacitance of the vertical to the ground wires. This ratio can be improved (up to a point) by using more radials. By raising the entire antenna system off the ground, C_E (which consists of the series combination of C_{E1} and C_{E2}) is decreased while C_W stays the same. The radial system shown at B is sometimes called a *counterpoise*.

used, but as few as two, or as many as eight, can be used. For a given height of vertical, the length of the radials can be adjusted to resonate the antenna. For a λ/4 vertical, the radials are normally λ/4 long.

In the case of a multiband vertical, two or more sets of radials, with different lengths, may be interleaved. The radials associated with each band are adjusted for resonance on their associated band.

A counterpoise is most commonly a system of elevated radials, where the radial wires are interconnected with jumpers, as shown in **Fig 31**. As illustrated in Fig 30, the purpose of the elevated-ground system is to provide a return path for the displacement currents flowing in the vicinity of the antenna. The idea is to minimize the current flowing through the ground itself, which is usually very lossy. By raising the radials above ground most of the current will flow in the radials, which are good conductors. This allows a simple radial system to provide a very efficient ground. However, there is a price to be paid for this.

The ground system now has a direct effect on the feedpoint impedance, introducing reactance as well as resistance, and is relatively narrow band. For a given vertical height, the



Fig 31—Counterpoise, showing the radial wires connected together by cross wires. The length of the perimeter of the individual meshes should be < λ/4 to prevent undesired resonances. Sometimes the center portion of the counterpoise is made from wire mesh.

Table 2

Illustration of the effect of variable vertical height (L_1) on elevated radial length (L2) and R_R.
#12 wire, elevated 5 feet over average ground at 3.525 MHz.

L_1 (λ)	L_1 (feet)	L_2 (feet)	R_R (Ω)
0.225	62.8	94	28.8
0.25	69.8	67	38.4
0.27	75.0	45	51.0
0.3	83.7	24	75.9



Fig 32—The ground-plane antenna. Power is applied between the base of the vertical radiator and the center of the ground plane, as indicated in the drawing. Decoupling from the transmission line and any conductive support structure is highly desirable.

radial length must be adjusted to resonate the antenna. The length of the radials must be readjusted for each band if a multiband vertical is used. As pointed out above, this usually means the installation of a set of radials for each band. To minimize current flowing in the ground, the antenna, ground plane and feed line must be isolated from ground for RF. More on this later.

The height of the vertical does not have to be exactly λ/4. Other lengths may be used and the antenna may be resonated by adjusting the length of the radials. **Table 2** gives a comparison between three different vertical lengths in an antenna using four elevated radials at 3.525 MHz.

An important feature of Table 2 is the dramatic reduction in radial length (L_2) with even a small increase in vertical height (L_1). For example, increasing the height by 5 feet reduces the radial length by 22 feet on 80 meters. On the other hand even a small decrease in L_1 can cause a substantial increase in L_2. This would be very undesirable, since the area required by the radials is already considerable. Notice also that the small increase in height raises R_R to 51 Ω. This trick of increasing the height slightly to reduce the size of the elevated ground system and to increase the input resistance can be very useful. In a following section the use of *top loading* for short antennas will be discussed. Top loading can also be used on a λ/4 vertical to achieve the same effect as increasing the height—the ability to use shorter radials and a better match.

GROUND-PLANE ANTENNAS

The ground-plane antenna is a λ/4 vertical with four radials, as shown in **Fig 32**. The entire antenna is elevated above ground. A practical example of a 7-MHz ground-plane antenna is given in **Fig 33**. As explained earlier, elevating the antenna reduces the ground loss and lowers the radiation angle somewhat. The radials are sloped downward to make the feed-point impedance closer to 50 Ω.

The feed-point impedance of the antenna varies with the height above ground, and to a lesser extent varies with the ground characteristics. **Fig 34** is a graph of feed-point resistance (R_R) for a ground-plane antenna with the radials parallel to the ground. R_R is plotted as a function of height above ground. Notice that the difference between perfect ground and average ground (ε=13 and σ = 0.005 S/m) is small, except when quite close to ground. Near ground R_R is between 36 and 40 Ω. This is a reasonable match for 50-Ω feed line but as the antenna is raised above ground R_R drops to approximately 22 Ω, which is not a very good match. The feed-point resistance can be increased by sloping the radials downward, away from the vertical section.

The effect of sloping the radials is shown in **Fig 35**. The



Fig 33—A ground-plane antenna is effective for DX work on 7 MHz. Although its base can be any height above ground, losses in the ground underneath will be reduced by keeping the bottom of the antenna and the ground plane as high above ground as possible. Feeding the antenna directly with 50-Ω coaxial cable will result in a low SWR. The vertical radiator and the radials are all λ/4 long electrically. Contrary to popular myth, the radials need not necessarily be 5% longer than the radiator. Their physical length will depend on their length-to-diameter ratios, the height over ground and the length of the vertical radiator, as discussed in text.



Fig 34—Radiation resistance of a 4-radial ground-plane antenna as a function of height over ground. Perfect and average ground are shown. Frequency is 3.525 MHz. Radial angle (θ) is 0°.



Fig 35—Radiation resistance and resonant length for a 4-radial ground-plane antenna > 0.3 λ above ground as a function of radial droop angle (θ).



Fig 36—Radiation resistance and resonant length for a 4-radial ground-plane antenna for various heights above average ground for radial droop angle θ = 45°.

graph is for an antenna well above ground (> 0.3 λ). Notice that R_R = 50 Ω when the radials are sloped downward at an angle of 45°, a convenient value. The resonant length of the antenna will vary slightly with the angle. In addition, the resonant length will vary a small amount with height above the ground. It is for these reasons, as well as the effect of conductor diameter, that some adjustment of the radial lengths is usually required. When the ground-plane antenna is used on the higher HF bands and at VHF, the height above ground is usually such that a radial sloping angle of 45° will give a good match to 50-Ω feed line.

The effect of height on R_R with a radial angle of 45° is shown in **Fig 36**. At 7 MHz and lower, it is seldom possible to elevate the antenna a significant portion of a wavelength and the radial angle required to match to 50-Ω line is usually of the order of 10° to 20°. To make the vertical portion of the antenna



Fig 37—The folded monopole antenna. Shown here is a ground plane of four λ/4 radials. The folded element may be operated over an extensive counterpoise system or mounted on the ground and worked against buried radials and the earth. As with the folded dipole antenna, the feed-point impedance depends on the ratios of the radiator conductor sizes and their spacing.



Fig 38—A choke balun with sufficient impedance to isolate the antenna properly can be made by winding coaxial cable around a section of plastic pipe. Suitable dimensions are given in the text.

as long as possible, it may be better to accept a slightly poorer match and keep the radials parallel to ground.

The principles of the folded dipole (Fig 18) can also be applied to the ground-plane antenna, as shown in **Fig 37**. This is the *folded monopole* antenna. The feed-point resistance can be controlled by the number of parallel vertical conductors and the ratios of their diameters.

As mentioned earlier, it is important in most installations to isolate the antenna from the feed line and any conductive supporting structure. This is done to minimize the return current conducted through the ground. A return current on the feed line itself or the support structure can drastically alter the radiation pattern, usually for the worse. For these reasons, a balun (see Chapter 26, Coupling the Line to the Antenna) or other isolation scheme must be used. 1:1 baluns are effective for the higher bands but at 3.5 and 1.8 MHz commercial baluns often have too low a shunt inductance to provide adequate isolation. It is very easy to recognize when the isolation is inadequate. When the antenna is being adjusted while watching an isolated impedance or SWR meter, adjustments may be sensitive to your touching the instrument. After adjustment and after the feed line is attached, the SWR may be drastically different. When the feed line is inadequately isolated, the apparent resonant frequency or the length of the radials required for resonance may also be significantly different from what you expect.

In general, an isolation choke inductance of 50 to 100 µH will be needed for 3.5 and 1.8-MHz ground-plane antennas. One of the easiest ways to make the required isolation choke is to wind a length of coaxial cable into a coil as shown in **Fig 38**. For 1.8 MHz, 30 turns of RG-213 wound on a 14-inch length of 8-inch diameter PVC pipe, will make a very good isolation choke that can handle full legal power continuously. A smaller choke could be wound on 4-inch diameter plastic drain pipe using RG-8X or a Teflon insulated cable. The important point here is to isolate or decouple the antenna from the feed line and support structure.

A full-size ground-plane antenna is often a little impractical for 3.5-MHz and quite impractical for 1.8 MHz, but it can be used at 7 MHz to good advantage, particularly for DX work. Smaller versions can be very useful on 3.5 and 1.8 MHz.

EXAMPLES OF VERTICALS

There are many possible ways to build a vertical antenna—the limits are set by your ingenuity. The primary problem is creating the vertical portion of the antenna with sufficient height. Some of the more common means are:

- A dedicated tower
- Using an existing tower with an HF Yagi on top
- A wire suspended from a tree limb or the side of a building
- A vertical wire supported by a line between two trees or other supports
- A tall pole supporting a conductor
- Flagpoles
- Light standards
- Irrigation pipe
- TV masts

If you have the space and the resources, the most straightforward means is to erect a dedicated tower for a vertical. While this is certainly an effective approach, many amateurs do not have the space or the funds to do this, especially if they already have a tower with an HF antenna on the top. The existing tower can be used as a top-loaded vertical, using shunt feed and a ground radial system. A system like this is shown in **Fig 39B**.

For those who live in an area with tall trees, it may be possible to install a support rope between two trees, or between a tree and an existing tower. (Under no circumstances should you use an active utility pole!) The vertical portion of the antenna can be a wire suspended from the support line to ground, as shown in Fig 39C. If top loading is needed, some or all of the support line can be made part of the antenna.

Your local utility company will periodically have older power poles that they no longer wish to keep in service. These are sometimes available at little or no expense. If you see a power line under reconstruction or repair in your area you might stop and speak with the crew foreman. Sometimes they will have removed older poles they will not use again and will have to haul them back to their shop for disposal. Your offer for local "disposal" may well be accepted. Such a pole can be used in conjunction with a tubing or whip extension such as that shown in Fig 39A. Power poles are not your only option. In some areas of the US, such as the southeast or northwest, tall poles made directly from small conifers are available.

Freestanding (unguyed) flagpoles and roadway illumination standards are available in heights exceeding 100 feet. These are made of fiberglass, aluminum or galvanized steel. All of these are candidates for verticals. Flagpole suppliers are listed under "Flags and Banners" in your Yellow Pages. For lighting standards (lamp posts), you can contact a local electrical hardware distributor. Like a wooden pole, a fiberglass flagpole does not require a base insulator, but metal poles do. Guy wires will be needed.

One option to avoid the use of guys and a base insulator is to mount the pole directly into the ground as originally intended and then use shunt feed. If you want to keep the pole grounded but would like to use elevated radials, you can attach a cage of wires (four to six) at the top as shown in Fig 39D. The cage surrounds the pole and allows the pole (or tower for that matter) to be grounded while allowing elevated radials to be used. The use of a cage of wires surrounding the pole or tower is a very good way to increase the effective diameter. This reduces the Q of the antenna, thereby increasing the bandwidth. It can also reduce the conductor loss, especially if the pole is galvanized steel, which is not a very good RF conductor.

Aluminum irrigation tubing, which comes in diameters of 3 and 4 inches and in lengths of 20 to 40 feet, is widely available in rural areas. One or two lengths of tubing con-



Fig 39—Vertical antennas are effective for 3.5- or 7-MHz work. The λ/4 antenna shown at A is fed directly with 50-Ω coaxial line, and the resulting SWR is usually less than 1.5 to 1, depending on the ground resistance. If a grounded antenna is used as at B, the antenna can be shunt fed with either 50- or 75-Ω coaxial line. The tap for best match and the value of C will have to be found by experiment. The line running up the side of the antenna should be spaced 6 to 12 inches from the antenna. If tall trees are available the antenna can be supported from a line suspended between the trees, as shown in C. If the vertical section is not long enough then the horizontal support section can be made of wire and act as top loading. A pole or even a grounded tower can be used with elevated radials if a cage of four to six wires is provided as shown in D. The cage surrounds the pole which may be wood or a grounded conductor.

nected together can make a very good vertical when guyed with non-conducting line. It is also very lightweight and relatively easy to erect. A variety of TV masts are available which can also be used for verticals.

1.8 TO 3.5-MHz VERTICAL USING AN EXISTING TOWER

A tower can be used as a vertical antenna, provided that a good ground system is available. The shunt-fed tower is at its best on 1.8 MHz, where a full λ/4 vertical antenna is rarely possible. Almost any tower height can be used. If the beam structure provides some top loading, so much the better, but anything can be made to radiate—if it is fed properly. W5RTQ (now K6SE) uses a self-supporting, aluminum, crank-up, tilt-over tower, with a TH6DXX tribander mounted at 70 feet. Measurements showed that the entire structure has about the same properties as a 125-foot vertical. It thus works quite well as an antenna on 1.8 and 3.5 MHz for DX work requiring low-angle radiation.

Preparing the Structure

Usually some work on the tower system must be done before shunt-feeding is tried. If present, metallic guys should be broken up with insulators. They can be made to simulate top loading, if needed, by judicious placement of the first insulators. Don't overdo it; there is no need to "tune the radiator to resonance" in this way since a shunt feed is employed. If the tower is fastened to a house at a point more than about one-fourth of the height of the tower, it may be desirable to insulate the tower from the building. Plexiglas sheet, ¼-inch or more thick, can be bent to any desired shape for this purpose, if it is heated in an oven and bent while hot.

All cables should be taped tightly to the tower, on the inside, and run down to the ground level. It is not necessary to bond shielded cables to the tower electrically, but there should be no exceptions to the down-to-the-ground rule.

A good system of buried radials is very desirable. The ideal would be 120 radials, each 250 feet long, but fewer and shorter ones must often suffice. You can lay them around corners of houses, along fences or sidewalks, wherever they can be put a few inches under the surface, or even on the earth's surface. Aluminum clothesline wire may be used extensively in areas where it will not be subject to corrosion. Neoprene-covered aluminum wire will be better in highly acid soils. Contact with the soil is not important. Deep-driven ground rods and connection to underground copper water pipes may be helpful, if available, especially to provide some protection from lightning.

Installing the Shunt Feed

Principal details of the shunt-fed tower for 1.8 and 3.5 MHz are shown in **Fig 40**. Rigid rod or tubing can be used for the feed portion, but heavy gauge aluminum or copper wire is easier to work with. Flexible stranded #8 copper wire is used at W5RTQ (now K6SE) for the 1.8-MHz feed, because when the tower is cranked down, the feed wire must come down with it. Connection is made at the top, 68 feet, through a 4-foot length of aluminum tubing clamped to the top of the tower, horizontally. The wire is clamped to the tubing at the outer end, and runs down vertically through standoff insulators. These are made by fitting 12-inch lengths of PVC plastic water pipe over 3-foot lengths of aluminum tubing. These are clamped to the tower at 15- to 20-foot intervals, with the bottom clamp about 3 feet above ground. These lengths allow for adjustment of the tower-to-wire spacing over a range of about 12 to 36 inches, for impedance matching.

The gamma-match capacitor for 1.8 MHz is a 250-pF variable with about ⅙-inch plate spacing. This is adequate for power levels up to about 200 W. A large transmitting or a vacuum-variable capacitor should be used for high-power applications.

Tuning Procedure

The 1.8-MHz feed wire should be connected to the top of the structure if it is 75 feet tall or less. Mount the standoff insulators so as to have a spacing of about 24 inches between wire and tower. Pull the wire taut and clamp it in place at the bottom insulator. Leave a little slack below to permit adjustment of the wire spacing, if necessary.

Adjust the series capacitor in the 1.8-MHz line for minimum reflected power, as indicated on an SWR meter connected between the coax and the connector on the capacitor housing. Make this adjustment at a frequency near the middle of your expected operating range. If a high SWR is indicated, try moving the wire closer to the tower. Just the


Connection to Tower
No.8 Copper, Spaced Max. 30" from Tower
80/75–Meter Feed Wire #8 Aluminum, Spaced 15" from Tower
Standoff Insulator
Standoff Insulator
150–pF Variables
250–pF Variable
Coaxial Feed
Buried Radials, Connected to Base of Tower

Fig 40—Principal details of the shunt-fed tower at W5RTQ (now K6SE). The 1.8-MHz feed, left side, connects to the top of the tower through a horizontal arm of 1-inch diameter aluminum tubing. The other arms have standoff insulators at their outer ends, made of 1-foot lengths of plastic water pipe. The connection for 3.5-4 MHz, right, is made similarly, at 28 feet, but two variable capacitors are used to permit adjustment of matching with large changes in frequency.

lower part of the wire need be moved for an indication as to whether reduced spacing is needed. If the SWR drops, move all insulators closer to the tower, and try again.

If the SWR goes up, increase the spacing. There will be a practical range of about 12 to 36 inches. If going down to 12 inches does not give a low SWR, try connecting the top a bit farther down the tower. If wide spacing does not make it, the omega match shown for 3.5-MHz work should be tried. No adjustment of spacing is needed with the latter arrangement, which may be necessary with short towers or installations having little or no top loading.

The two-capacitor arrangement in the omega match is also useful for working in more than one 25-kHz segment of the 1.8-MHz band. Tune up on the highest frequency, say 1990 kHz, using the single capacitor, making the settings of wire spacing and connection point permanent for this frequency. To move to the lower frequency, say 1810 kHz, connect the second capacitor into the circuit and adjust it for the new frequency. Switching the second capacitor in and out then allows changing from one segment to the other, with no more than a slight retuning of the first capacitor.

SIMPLE, EFFECTIVE, ELEVATED GROUND-PLANE ANTENNAS

This section describes a simple and effective means of using a grounded tower, with or without top-mounted antennas, as an elevated ground-plane antenna for 80 and 160 meters. It first appeared in a June 1994 *QST* article by Thomas Russell, N4KG.

From Sloper to Vertical

Recall the quarter-wavelength sloper, also known as the *half sloper*. [The half sloper is covered later in this chapter in more detail.—*Ed.*] It consists of an isolated quarter wavelength of wire, sloping from an elevated feed point on a grounded tower. Best results are usually obtained when the feed point is somewhere below a top-mounted Yagi antenna. You feed a sloper by attaching the center conductor of a coaxial cable to the wire and the braid of the cable to the tower leg. Now, imagine four (or more) slopers, but instead of feeding each individually, connect them together to the center conductor of a single feed line. Voilà! Instant elevated ground plane.

Now, all you need to do is determine how to tune the antenna to resonance. With no antennas on the top of the tower, the tower can be thought of as a fat conductor and should be approximately 4% shorter than a quarter wavelength in free space. Calculate this length and attach four insulated quarter-wavelength radials at this distance from the top of the tower. For 80 meters, a feed point 65 feet below the top of an unloaded tower is called for. The tower guys must be broken up with insulators for all such installations. For 160 meters, 130 feet of tower above the feed point is needed.

What can be done with a typical grounded-tower-and-Yagi installation? A top-mounted Yagi acts as a large capacitance hat, top loading the tower. Fortunately, top loading is the most efficient means of loading a vertical antenna.

The examples in **Table 3** should give us an idea of how much top loading might be expected from typical amateur antennas. The values listed in the *Equivalent Loading* column tell us the approximate vertical height replaced by the antennas listed in a top-loaded vertical antenna. To arrive at the remaining amount of tower needed for resonance, subtract these numbers from the non-loaded tower height needed for resonance. Note that for all but the 10-meter antennas, the equivalent loading equals or exceeds a quarter wavelength on 40 meters. For typical HF Yagis, this method is best used only on 80 and 160 meters.

Construction Examples

Consider this example: A TH7 triband Yagi mounted on a 40-foot tower. The TH7 has approximately the same overall dimensions as a full-sized 3-element 20-meter beam, but has more interlaced elements. Its equivalent loading is estimated to be 40 feet. At 3.6 MHz, 65 feet of tower is needed without loading. Subtracting 40 feet of equivalent loading, the feed point should be 25 feet below the TH7 antenna.

Ten quarter-wavelength (65-foot) radials were run from a nylon rope tied between tower legs at the 15-foot level, to various supports 10 feet high. Nylon cord was tied to the insulated, stranded, #18 wire, without using insulators. The radials are all connected together and to the center of an exact half wavelength (at 3.6 MHz) of RG-213 coax, which will repeat the antenna feed impedance at the other end. **Fig 41** is a drawing of the installation. The author used a Hewlett-Packard low-frequency impedance analyzer to measure the input impedance across the 80-meter band. An exact resonance (zero reactance) was seen at 3.6 MHz, just as predicted. The radiation resistance was found to be 17 Ω. The next question is, how to feed and match the antenna.

One good approach to 80-meter antennas is to tune them to the low end of the band, use a low-loss transmission line, and switch an antenna tuner in line for operation in the higher portions of the band. With a 50-Ω line, the 17-Ω radiation resistance represents a 3:1 SWR, meaning that an antenna tuner should be in-line for all frequencies. For short runs, it

Table 3
Effective Loading of Common Yagi Antennas

Antenna	*Boom Length (feet)*	*S (area, ft^2)*	*Equivalent Loading (feet)*
3L 20	24	768	39
5L 15	26	624	35
4L 15	20	480	31
3L 15	16	384	28
5L 10	24	384	28
4L 10	18	288	24
3L 10	12	192	20
TH7	24	—	40 (estimated)
TH3	14	—	27 (estimated)



Fig 41—At A, an 80-meter top-loaded, reverse-fed elevated ground plane, using a 40-foot tower carrying a TH7 triband Yagi antenna. At B, dimensions of the 3.6-MHz matching network, made from RG-59.



Fig 42—A 160-meter antenna using a 75-foot tower carrying stacked triband Yagis.

would be permissible to use RG-8 or RG-213 directly to the tuner. If you have a plentiful supply of low-loss 75-Ω CATV rigid coax, you can take another approach.

Make a quarter-wave (70 feet × 0.66 velocity factor = 46 feet) 37-Ω matching line by paralleling two pieces of RG-59 and connecting them between the feed point and a run of the rigid coax to the transmitter. The magic of quarter-wave matching transformers is that the input impedance (R_i) and output impedance (R_o) are related by:

$$Z_0^2 = R_i \times R_o \qquad \text{(Eq 2)}$$

For $R_i = 17\ \Omega$ and $Z_0 = 37\ \Omega$, $R_o = 80\ \Omega$, an almost perfect match for the 75-Ω CATV coax. The resulting 1.6:1 SWR at the transmitter is good enough for CW operation without a tuner.

160-Meter Operation

On the 160-meter band, a resonant quarter-wavelength requires 130 feet of tower above the radials. That's a pretty tall order. Subtracting 40 feet of top loading for a 3-element 20-meter or TH7 antenna brings us to a more reasonable 90 feet above the radials. Additional top loading in the form of more antennas will reduce that even more.

Another installation, using stacked TH6s on a 75-foot tower, is shown in **Fig 42**. The radials are 10 feet off the ground.

PHASED VERTICALS

Two or more vertical antennas spaced apart can be operated as a single antenna system to obtain additional gain and a directional pattern. There is an extensive discussion of phased arrays in Chapter 8, Multielement Arrays. Much of the material in Chapter 8 is useful for low-band antennas.

The Half-Square Antenna

The *half-square* antenna is a very simple form of vertical two-element phased array that can be very effective on the low bands. The following section was originally presented in *The ARRL Antenna Compendium Vol 5*, by Rudy Severns, N6LF.

A simple modification to a standard dipole is to add two λ/4 vertical wires, one at each end, as shown in **Fig 43**. This makes a *half-square antenna*. The antenna can be fed at one corner (low-impedance, current fed) or at the lower end of one of the vertical wires (high-impedance, voltage fed).



Fig 43—Typical 80-meter half-square, with λ/4-high vertical legs and a λ/2-long horizontal leg. The antenna may be fed at the bottom or at a corner. When fed at a corner, the feed point is a low-impedance, current-feed. When fed at the bottom of one of the wires against a small ground counterpoise, the feed point is a high-impedance, voltage-feed.

Other feed arrangements are also possible.

The "classical" dimensions for this antenna are λ/2 (131 feet at 3.75 MHz) for the top wire and λ/4 (65.5 feet) for the vertical wires. However, there is nothing sacred about these dimensions! They can vary over a wide range and still obtain nearly the same performance.

This antenna is two λ/4 verticals, spaced λ/2, fed in-phase by the top wire. The current maximums are at the top corners. The theoretical gain over a single vertical is 3.8 dB. An important advantage of this antenna is that it does not require the extensive ground system and feed arrangements that a conventional pair of phased λ/4 verticals would.

Comparison to a Dipole

In the past, one of the things that has turned off potential users of the half-square on 80 and 160 meters is the perceived need for λ/4 vertical sections. This forces the height to be > 65 feet on 80 meters and > 130 feet on 160 meters. That's not really a problem. If you don't have the height there are several things you can do. For example, just fold the ends in, as shown in **Fig 44**. This compromises the performance surprisingly little.

It is helpful to compare the examples given in Figs 43 and 44 to dipoles at the same height. Two heights, 40 and 80 feet, and average, very good and sea water grounds, were used for this comparison. It is also assumed that the lower end of the vertical wires had to be a minimum of 5 feet above ground.

At 40 feet the half-square is really mangled, with only 35-foot long (≈ λ/8) vertical sections. The elevation-plane comparison between this antenna and a dipole of the same height is shown in **Fig 45**. Over average ground the half-square is superior below 32° and at 15° is almost 5 dB better. That is a worthwhile improvement. If you have very good soil conductivity, like parts of the lower Midwest and South, then the half-square will be superior below 38° and at 15° will be nearly 8 dB better. For those fortunate few with saltwater frontal property the advantage at 15° is 11 dB! Notice also that above 35°, the response drops off rapidly. This is great for DX but is not good for local work.



Fig 44—An 80-meter half-square configured for 40-foot high supports. The ends have been bent inward to reresonate the antenna. The performance is compromised surprisingly little.



Fig 45—Comparison of 80-meter elevation response of 40-foot high, horizontally polarized dipole over average ground and a 40-foot high, vertically polarized half-square, over three types of ground: average (conductivity σ = 5 mS/m, dielectric constant ε = 13), very good (σ = 30 mS/m, ε = 20) and salt water (σ = 5000 mS/m, ε = 80). The quality of the ground clearly has a profound effect on the low-angle performance of the half-square. Even over average ground, the half-square outperforms the low dipole below about 32°.



Fig 46—80-meter azimuth patterns for shortened half-square antenna (solid line) shown in Fig 44, compared with flattop dipole (dashed line) at 100 feet height. Average ground is assumed for these cases.

Fig 46 shows the azimuthal-plane pattern for the 80-meter half-square antenna in Fig 44, but this time compared with the response of a flattop horizontal dipole that is 100 feet high. These comparisons are for average ground and are for an elevation angle of 5°. The message here is that the lower your dipole and the better your ground, the more you have to gain by switching from a dipole to a half-square. The half-square antenna looks like a good bet for DXing.

Changing the Shape of the Half Square

Just how flexible is the shape? There are several common distortions of practical importance. Some have very little effect but a few are fatal to the gain. Suppose you have either more height and less width than called for in the standard version or more width and less height, as shown in **Fig 47A**.

The effect on gain from this type of dimensional variation is given in **Table 4**. For a top length (L_T) varying between 110 and 150 feet, where the vertical wire lengths (L_V) readjusted to resonate the antenna, the gain changes only by 0.6 dB. For a 1-dB change the range of L_T is 100 to 155 feet, a pretty wide range.

Another variation results if we vary the length of the horizontal top wire and readjust the vertical wires for resonance, while keeping the top at a constant height. See Fig 47B. **Table 5** shows the effect of this variation on the peak gain. For a range of L_T = 110 to 145 feet, the gain changes only 0.65 dB.

The effect of bending the ends into a V shape, as shown in Fig 47C, is given in **Table 6**. The bottom of the antenna is kept at a height of 5 feet and the top height (H) is either 40 or 60 feet. Even this gross deformation has only a relatively small effect on the gain. Sloping the ends outward as shown in Fig 47D and varying the top length also has only a small effect on the gain. While this is good news because it allows you dimension the antenna to fit different QTHs, not all distortions are so benign.

Table 4

Variation in Gain with Change in Horizontal Length, with Vertical Height Readjusted for Resonance (see Fig 47A)

L_T (feet)	*L_V (feet)*	*Gain (dBi)*
100	85.4	2.65
110	79.5	3.15
120	73.7	3.55
130	67.8	3.75
140	61.8	3.65
150	56	3.05
155	53	2.65

Table 5

Variation in Gain with Change in Horizontal Length, with Vertical Length Readjusted for Resonance, but Horizontal Wire Kept at Constant Height (see Fig 47B)

L_T (feet)	*L_V (feet)*	*Gain (dBi)*
110	78.7	3.15
120	73.9	3.55
130	68	3.75
140	63	3.35
145	60.7	3.05



Fig 47—Varying the horizontal and vertical lengths of a half-square. At A, both the horizontal and vertical legs are varied, while keeping the antenna resonant. At B, the height of the horizontal wire is kept constant, while its length and that of the vertical legs is varied to keep the antenna resonant. At C, the length of the horizontal wire is varied and the legs are bent inwards in the shape of "vees." At D, the ends are sloped outward and the length of the flattop portion is varied. All these symmetrical forms of distortion of the basic half-square shape result in small performance losses. At E, a "halfwave vertical dipole" (HVD) with the feed coax isolated with common-mode choke baluns to keep RF current off the coax shield.

Table 6

Gain for Half-Square Antenna, Where Ends Are Bent Into V-Shape (see Fig 47 C)

Height ⇒	*H=40 feet*	*H=40 feet*	*H=60 feet*	*H=60 feet*
L_T (feet)	*L_e (feet)*	*Gain (dBi)*	*L_e (feet)*	*Gain (dBi)*
40	57.6	3.25	52.0	2.75
60	51.4	3.75	45.4	3.35
80	45.2	3.95	76.4	3.65
100	38.6	3.75	61.4	3.85
120	31.7	3.05	44.4	3.65
140	—	—	23	3.05



Fig 48—An asymmetrical distortion of the half-square antenna, where the bottom of one leg is purposely made 20 feet higher than the other. This type of distortion does affect the pattern!



Fig 49—Elevation pattern for the asymmetrical half-square shown in Fig 48, compared with pattern for a 50-foot high dipole. This is over average ground, with a conductivity of 5 mS/m and a dielectric constant of 13. Note that the zenith-angle null has filled in and the peak gain is lower compared to conventional half-square shown in Fig 43 over the same kind of ground.

Suppose the two ends are not of the same height, as illustrated in **Fig 48**, where one end of the half-square is 20 feet higher than the other. The elevation-plane radiation pattern for this antenna is shown in **Fig 49** compared to a dipole at 50 feet. This type of distortion does affect the pattern. The gain drops somewhat and the zenith null goes away. The nulls off the end of the antenna also go away, so that there is some end-fire radiation. In this example the difference in height is fairly extreme at 20 feet. Small differences of 1 to 5 feet do not affect the pattern seriously.

If the top height is the same at both ends but the length of the vertical wires is not the same, then a similar pattern distortion can occur. The antenna is very tolerant of symmetrical distortions but it is much less accepting of asymmetrical distortion.

What if the length of the wires is such that the antenna is not resonant? Depending on the feed arrangement, that may or may not matter. We will look at that issue later on, in the section on patterns versus frequency. The half-square antenna, like the dipole, is very flexible in its proportions.

Half-Square Feed-Point Impedance

There are many different ways to feed the half-square. Traditionally the antenna has been fed either at the end of one of the vertical sections, against ground, or at one of the upper corners as shown in Fig 43.

For voltage feed at the bottom against ground, the impedance is very high, on the order of several thousand ohms. For current feed at a corner, the impedance is much lower and is usually close to 50 Ω. This is very convenient for direct feed with coax.

The half-square is a relatively high-Q antenna (Q ≈ 17). **Fig 50** shows the SWR variation with frequency for this feed arrangement. An 80-meter dipole is not particularly wideband either, but a dipole will have less extreme variation in SWR than the half-square.

Patterns Versus Frequency

Impedance is not the only issue when defining the bandwidth of an antenna. The effect on the radiation pattern of changing frequency is also a concern. For a voltage-fed half-square, the current distribution changes with frequency. For an antenna resonant near 3.75 MHz, the current distribution is nearly symmetrical. However, above and below resonance the current distribution increasingly becomes asymmetrical. In effect, the open end of the antenna is constrained to be a voltage maximum but the feed point can behave less as a voltage point and more like a current maxima. This allows the current distribution to become asymmetrical.

The effect is to reduce the gain by –0.4 dB at 3.5 MHz and by –0.6 dB at 4 MHz. The depth of the zenith null is reduced from –20 dB to –10 dB. The side nulls are also reduced. Note that this is exactly what happened when the antenna was made physically asymmetrical. Whether the asymmetry is due to current distribution or mechanical arrangements, the antenna pattern will suffer.

When current-feed at a corner is used, the asymmetry introduced by off-resonance operation is much less, since both ends of the antenna are open circuits and constrained to be voltage maximums. The resulting gain reduction is only –0.1 dB. It is interesting that the sensitivity of the pattern to changing frequency depends on the feed scheme used.

Of more concern for corner feed is the effect of the transmission line. The usual instruction is to simply feed



Fig 50—Variation of SWR with frequency for current-fed half-square antenna. The SWR bandwidth is quite narrow.



Fig 51—Typical matching networks used for voltage-feeding a half-square antenna.

the antenna using coax, with the shield connected to vertical wire and the center conductor to the top wire. Since the shield of the coax is a conductor, more or less parallel with the radiator, and is in the immediate field of the antenna, you might expect the pattern to be seriously distorted by this practice. This arrangement seems to have very little effect on the pattern. The greatest effect is when the feed line length was near a multiple of λ/2. Such lengths should be avoided.

Of course, you may use a choke balun at the feed point if you desire. This might reduce the coupling to the feed line even further but it doesn't appear to be worth the trouble. In fact, if you use an antenna tuner in the shack to operate away from resonance with a very high SWR on the transmission line, a balun at the feed point would take a beating.

Voltage-Feed at One End of Antenna: Matching Schemes

Several straightforward means are available for narrow-band matching. However, broadband matching over the full 80-meter band is much more challenging. Voltage feed with a parallel-resonant circuit and a modest local ground, as shown in **Fig 51**, is the traditional matching scheme for this antenna. Matching is achieved by resonating the circuit at the desired frequency and tapping down on the inductor in Fig 51A or using a capacitive divider (Fig 51B). It is also possible to use a λ/4 transmission-line matching scheme, as shown in Fig 51C.

If the matching network shown in Fig 51B is used, typical values for the components would be: L = 15 µH, C1 = 125 pF and C2 = 855 pF. At any single point the SWR can be made very close to 1:1 but the bandwidth for SWR < 2:1 will be very narrow at <100 kHz. Altering the L-C ratio doesn't make very much difference. The half-square antenna has a well-earned reputation for being narrow-band.

Short Vertical Antennas

On the lower frequencies it becomes increasingly difficult to accommodate a full λ/4 vertical height and full-sized λ/4 radials, or even worse, a full-sized half-wave vertical dipole (HVD). In fact, it is not absolutely necessary to make the antenna full size, whether it is an HVD, a grounded monopole antenna or a ground-plane type of monopole antenna. The size of the antenna can be reduced by half or even more and still retain high efficiency and the desired radiation pattern. This requires careful design, however. And if high efficiency is maintained, the operating bandwidth of the shortened antenna will be reduced because the shortened antenna will have a higher Q.

This translates into a more rapid increase of reactance away from resonance. The effect can be mitigated to some extent by using larger-diameter conductors. Even doing this however, bandwidth will be a problem, particularly on the 3.5 to 4-MHz band, which is very wide in proportion to the center frequency.

If we take a vertical monopole with a diameter of 2 inches and a frequency of 3.525 MHz and progressively shorten it from λ/4 in length, the feed-point impedance and efficiency (using an inductor at the base to tune out the capacitive reactance) will vary as shown in **Table 7**. In this example perfect ground and conductor are assumed. Real ground will not make a great difference in the impedance but will introduce ground loss, which will reduce the efficiency further. Conductor loss will also reduce efficiency. In general, higher R_R will result in better efficiency.

The important point of Table 7 is the drastic reduction in radiation resistance R_R as the antenna gets shorter. This combined with the increasing loss resistance of the inductor (R_L) used to tune out the increasing base reactance (X_C) reduces the efficiency.

BASE LOADING A SHORT VERTICAL ANTENNA

The base of the antenna is a convenient point at which to add a loading inductor, but it is usually not the lowest loss point at which an inductor, of a given Q, could be placed. There is an extensive discussion of the optimum location of the loading in a short vertical as a function of ground loss and inductor Q in Chapter 16 for mobile antennas, which by necessity are electrically and physically short. This information should be reviewed before using inductive loading.

On the accompanying CD-ROM is a copy of the program *MOBILE.EXE*. This is an excellent tool for designing short, inductively loaded antennas. In most cases, where top loading (discussed below) is not used, the optimum point is near or a little above the middle of the vertical section. Moving the loading coil from the base to the middle of the vertical antenna can make an important difference, increasing R_R and reducing the inductor loss. For example, in an antenna operating at 3.525 MHz, if we make L_1 = 34.9 feet (0.125 λ) the amount of loading inductor placed at the center is 25.2 µH. This resonates the antenna. In this configuration R_R will increase from 6.8 Ω (base loading) to 13.5 Ω (center loading). This substantially increases the efficiency of the antenna, depending on the ground loss and conductor resistances.

Instead of a lumped inductance being inserted at some point in the antenna, it is also possible to use "continuous loading," where the entire radiator is wound as a small diameter coil. The effect is to distribute the inductive loading all along the radiator. In this version of inductive loading the coil is the radiator. An example of a short vertical using this principle is given later in this chapter.

OTHER WAYS OF LOADING A SHORT ANTENNA FOR RESONANCE

Inductive loading is not the only, or even the best, way to compensate for reduced antenna height. *Capacitive top loading* can also be used as indicated in **Fig 52** to bring a vertical monopole to resonance. **Table 8** gives information on a shortened 3.525-MHz vertical using top loading. The vertical portion (L_1) is made from 2-inch tubing. The top loading is also 2-inch tubing extending across the top like a T. The length of the top loading T (±L_2) is adjusted to resonate the

Table 7

Effect of Shortening a Vertical Radiator Below λ/4 Using Inductive Base Loading.

Frequency is 3.525 MHz and for the Inductor Q_L = 200. Ground and conductor losses are omitted.

Length (feet)	*Length (λ)*	*R_R (Ω)*	*X_C (Ω)*	*R_L (Ω)*	*Efficiency (%)*	*Loss (dB)*
14	0.050	0.96	–761	3.8	20	–7.0
20.9	0.075	2.2	–533	2.7	45	–3.5
27.9	0.100	4.2	–395	2.0	68	–1.7
34.9	0.125	6.8	–298	1.5	82	–0.86
41.9	0.150	10.4	–220	1.1	90	–0.44
48.9	0.175	15.1	–153	0.77	95	–0.22
55.8	0.200	21.4	–92	0.46	98	–0.09
62.8	0.225	29.7	–34	0.17	99	–0.02

Table 8

Effect of Shortening a Vertical Using Top Loading

L_1 (feet)	*L_2 (feet)*	*Length (λ)*	*R_R (Ω)*
14.0	48.8	0.050	4.0
20.9	38.6	0.075	8.5
27.9	30.1	0.100	14.0
34.9	22.8	0.125	19.9
41.9	17.3	0.150	25.5
48.9	11.9	0.175	30.4
55.8	7.0	0.200	33.9
62.8	2.4	0.225	35.7

antenna. Again, the ground and the conductors are assumed to be perfect in Table 8.

For a given vertical height, resonating the antenna with top loading results in much higher radiation resistance R_R—2 to 4 times. In addition, the loss associated with the loading element will be smaller. The result is a more efficient antenna for low heights. A comparison of R_R for both capacitive top loading and inductive base loading is given in **Fig 53**. For heights below 0.15 λ the length of the top-loading elements becomes impractical but there are other, potentially more useful, top-loading schemes.

A multiwire system such as the one shown in **Fig 54** has more capacitance than the single-conductor arrangement, and thus does not need to be as long to resonate at a given frequency. This design does, however, require extra supports for the additional wires. Ideally, an arrangement of this sort should be in the form of a cross, but parallel wires separated by several feet give a considerable increase in capacitance



Fig 52—Horizontal wire used to top load a short vertical.



Fig 53—Comparison of top (capacitive) and base (inductive) loading for short verticals. Sufficient loading is used to resonate the antenna.



Fig 54—Multiple top wires can increase the effective capacitance substantially. This allows the use of shorter top wires to achieve resonance.



Fig 55—A close-up view of the capacitance hat for a 7-MHz vertical antenna. The ½-in. diameter radial arms terminate in a loop of copper wire.



Fig 56—Capacitance of sphere, disc and cylinder as a function of their diameters. The cylinder length is assumed equal to its diameter.

over a single wire.

The top loading can be supplied by a variety of metallic structures large enough to have the necessary self-capacitance. For example, as shown in **Fig 55**, a multi-spoked structure with the ends connected together can be used. One simple way to make a capacitance hat is to take four to six 8-foot fiberglass CB mobile whips, arrange them like spokes in a wagon wheel and connect the ends with a peripheral wire. This arrangement will produce a 16-foot diameter hat that is economical and very durable, even when loaded with ice. Practically any sufficiently large metallic structure can be used for this purpose, but simple geometric forms such as the sphere, cylinder and disc are preferred because of the relative ease with which their capacitance can be calculated.

The capacitance of three geometric forms can be estimated from the curves of **Fig 56** as a function of their size. For the cylinder, the length is specified equal to the diameter. The sphere, disc and cylinder can be constructed from sheet metal, if such construction is feasible, but the capacitance will be practically the same in each if a "skeleton" type of construction with screening or networks of wire or tubing are used.

Finding Capacitance Hat Size

The required size of a capacitance hat may be determined from the following procedure. The information in this section is based on a September 1978 *QST* article by Walter Schulz, K3OQF. The physical length of a shortened antenna can be found from:

$$h_{inches} = \frac{11808}{F_{MHz}} \qquad \text{(Eq 3)}$$

where h = length in inches.

Thus, using an example of 7 MHz and a shortened length of 0.167 λ, h = 11808/7 × 0.167 = 282 inches, equivalent to 23.48 feet.

Consider the vertical radiator as an open-ended transmission line, so the impedance and top loading may be determined. The characteristic impedance of a vertical antenna can be found from

$$Z_0 = 60 \left(\ln\left(\frac{4h}{d}\right) - 1 \right) \qquad \text{(Eq 4)}$$

where

ln = natural logarithm

h = length (height) of vertical radiator in inches (as above)

d = diameter of radiator in inches

The vertical radiator for this example has a diameter of 1 inch. Thus, for this example,

$$Z_0 = 60 \left(\ln\left(\frac{4 \times 281}{1}\right) - 1 \right) = 361\ \Omega$$

The capacitive reactance required for the amount of top loading can be found from

$$Z_0 = 60\ \ln\left(\frac{4 \times 281}{1}\right) - 1 = 361\ \Omega \qquad \text{(Eq 5)}$$

where

X = capacitive reactance, ohms

Z_0 = characteristic impedance of antenna (from Eq 4)

θ = amount of electrical loading, degrees.

This value for a 30° hat is 361/tan 30° = 625 Ω. This capacitive reactance may be converted to capacitance with the following equation,

$$C = \frac{10^6}{2\pi f X_C} \qquad \text{(Eq 6)}$$

where

C = capacitance in pF

f = frequency, MHz

X_C = capacitive reactance, ohms (from above).

For this example, the required C = $10^6/(2\ \pi \times 7 \times 625)$ = 36.4 pF, which may be rounded to 36 pF. A disc capacitor is used in this example. The appropriate diameter for 36 pF of hat capacitance can be found from Fig 56. The disc diameter that yields 36 pF of capacitance is 40 inches.

The skeleton disc shown in Fig 55 is fashioned into a wagonwheel configuration. Six 20-inch lengths of ½-inch OD aluminum tubing are used as spokes. Each is connected to the hub at equidistant intervals. The outer ends of the spokes terminate in a loop made of #14 copper wire. Note that the loop increases the hat capacitance slightly, making a better approximation of a solid disc. The addition of this hat at the top of a 23.4-foot radiator makes it quarter-wave resonant at 7 MHz.

After construction, some slight adjustment in the radiator length or the hat size may be required if resonance at a specific frequency is desired. From Fig 53, the radiation resistance of a 0.167-λ high radiator is seen to be about 13 Ω without top loading. With top loading Rr ≈ 25 Ω or almost double.

THE COMPACT VERTICAL DIPOLE

A variation on the HVD (half-wave vertical dipole) theme is the *compact vertical dipole*, or CVD. The CVD uses capacitance-hat loading on each end of a shortened vertical radiator, as shown in **Fig 57C**. Some call this "top hat" and "bottom hat" loading. Les Moxon, G6XN, called this method of loading a shortened antenna simply "end loading." The vertical wire for his 40-meter CVD is 25 feet high, with 15-foot long horizontal loading wires on each side, top and bottom.

K8CH Compact Vertical Dipole

The top loading wires needn't be perpendicular to the vertical radiator, although that is convenient if you construct the antenna from aluminum tubing. K8CH described a wire 30-meter CVD in the 2006 Edition of *The ARRL Handbook.* This used #14 wire throughout, with sloping top loading wires. It was designed to be suspended from a tree at least



Fig 57—Progression of end-loaded-vertical dipole designs. At A, the HVD (half-wave vertical dipole), with no end loading. At B, an HVD whose bottom half has been replaced with a set of four ground-plane radials, making it into the familiar ground-plane vertical. At C, G6XN-style dipole with end loading of two wires at both top and bottom. At D, end-loaded dipole with four shorter wires at top and bottom. At E, K8CH end-loaded dipole with asymmetric loading wires. The four top wires are slanted down to the ground using extension insulating strings that also hold up the bottom horizontal end-loading wires. See Fig 58.

32 feet high to keep all wires 8 feet or more above humans and animals. The vertical radiating wire is 24 feet long, and the eight top and bottom end-loading wires are all 5 feet 9 inches long. See Fig 57E and **Table 9**, CVD 1.

The top loading wires slant at an angle of 45º down to the ground, using insulating strings that also support the ends of the bottom loading wires, holding them out so that they are horizontal. See **Fig 58**. There is a small loss of gain because of the “umbrella” shape of the top loading wires, and the 2:1 SWR bandwidth is diminished slightly from the horizontal case. This isn’t a problem on a narrow band like 30 meters.

A 40-meter version of this antenna, CVD 6, also uses a 24-foot long vertical radiator, 8 feet high at its bottom. It uses 11.3-foot long radial wires made of #14 wire, again with the top four slanted down at 45º. This CVD has a 2:1



Fig 58—Layout of CVD made using #14 wire suspended from a tree branch.

SWR bandwidth of 250 kHz. It is directly fed with 50-Ω coax with ferrite-core common-mode choke baluns in the middle of the vertical radiator. An additional choke balun is used where the coax reaches ground level in order to knock down common-mode currents that might otherwise radiate onto the coax shield.

You should note the comparison of 40-meter ground-plane vertical antennas in Table 9. GP 1 is for horizontal radials that are 8 feet off the ground, while GP 2 has its radials only 2 feet high. There is some loss in gain because of the proximity of the lossy ground. The 40-meter CVD 1 and CVD 2 cases illustrate the same effect of being close to the lossy ground.

Some of the cases in Table 9 require Center Load coils to bring the antenna to resonance. Where the loading coil inductance is equal to the "Hairpin Coil" inductance, the loading coil also serves as a hairpin matching coil. Where the amount of Hairpin Coil inductance is less than the Load Coil inductance, a match is achieved by tapping the Center Load Coil symmetrically out from the center.

80-Meter CVD

The size of a CVD becomes a real challenge on 80 meters, requiring either very tall support structures or multiple loading methods to keep the vertical radiator to a reasonable length. The CVD 2 design in Table 9 shows a K8CH-style CVD wire antenna whose vertical radiator is 46.5 feet long. It requires a 54.5-foot high tree to keep the bottom end of the vertical radiator 8 feet above ground for safety. Compare this to an HVD that requires a 143-foot support of some sort to keep it 8 feet off the ground at the bottom. The CVD 2 sacrifices some 0.7 dB in gain for this difference in size, and about 75 kHz in 2:1 SWR bandwidth.

The CVD 2 would require retuning when going from

Table 9

Variations on a Vertical Center-Fed Dipole

Name	*Style Fig 57*	*Vertical Length feet*	*Spoke Length feet*	*Min. Ht feet*	*Max. Gain dBi*	*2:1 SWR kHz*	*Hairpin Coil µH*	*Center Load µH*
20 Meters								
GP	B	17.53	16.53	8	0.29	400	—	—
CVD 1	C	13	7.57	8	0.12	625	—	—
CVD 2	D	12	5.1	8	0.00	550	0.68	0.68
CVD 3	E	12.15	5.6	8	–0.01	450	0.5	0.5
30 Meters								
GP	B	24.54	23.14	8	0.04	400	—	—
CVD 1	E	24	5.33	8	–0.2	500	—	—
CVD 2	E	17	7.60	8	–0.36	400	0.82	0.82
40 Meters								
HVD	A	66	—	8	0.13	450	—	—
GP 1	B	35	33	8	–0.12	325	—	—
GP 2	B	34.5	33	2	–0.37	400	—	—
CVD 1	C	25	15	8	–0.42	450	—	—
CVD 2	C	24	15	2	–1.09	400	—	—
CVD 3	D	24	10	8	–0.55	425	—	0.25
CVD 4	D	24	5	8	–0.85	225	—	8.7
CVD 5	D	16	8	8	–1.18	175	0.94	6.8
CVD 6	E	24	11.3	8	–0.59	250	—	—
80 Meters								
HVD	A	135	—	8	0.19	225	—	—
GP	B	65.5	61	8	0.11	200	—	—
CVD 1	C	48.3	30	8	–0.27	200	—	—
CVD 2	E	46.5	21.9	8	–0.50	150	—	—

CW to phone, probably by changing the length of the four bottom horizontal wires equally.

LINEAR LOADING

Another alternative to inductive loading is *linear loading*. This little-understood method of shortening radiators can be applied to almost any antenna configuration—including parasitic arrays. Although commercial antenna manufacturers make use of linear loading in their HF antennas, relatively few hams have used it in their own designs. Linear loading can be used to advantage in many antennas because it introduces relatively little loss, does not degrade directivity patterns, and has low enough Q to allow reasonably good bandwidth. Some examples of linear-loaded antennas are shown in **Fig 59**.



Fig 59—Some examples of linear loading. The small circles indicate the feed points of the antennas.



Fig 60—Wire dipole antennas. The ratio f/f_0 is the measured resonant frequency divided by frequency f_0 of a standard dipole of same length. R is radiation resistance in ohms. At A, standard single-wire dipole. At B, two-wire linear-loaded dipole, similar to folded dipole except that side opposite feed line is open. At C, three-wire linear-loaded dipole.

Since the dimensions and spacing of linear-loading devices vary greatly from one antenna installation to another, the best way to employ this technique is to try a length of conductor 10% to 20% longer than the difference between the shortened antenna and the full-size dimension for the linear-loading device. Then use the "cut-and-try" method, varying both the spacing and length of the loading device to optimize the match. A hairpin at the feed point can be useful in achieving a 1:1 SWR at resonance.

Linear-Loaded Short Wire Antennas

More detail on linear loading is provided in this section, which was originally presented in *The ARRL Antenna Compendium Vol 5* by John Stanford, NN0F. Linear loading can significantly reduce the required length for resonant antennas. For example, it is easy to make a resonant antenna that is as much as 30 to 40% shorter than an ordinary dipole for a given band. The shorter overall lengths come from bending back some of the wire. The increased self-coupling lowers the resonant frequency. These ideas are applicable to short antennas for restricted space or portable use.

Experiments

The results of the measurements are shown in **Fig 60** and are also consistent with values given by Rashed and Tai from an earlier paper. This shows several simple wire antenna configurations, with resonant frequencies and impedance (radiation resistance). The reference dipole has a resonant frequency f_0 and resistance R = 72 Ω. The f/f_0 values give the effective reduced frequency obtained with the linear loading in each case. For example, the two-wire linear-loaded dipole has its resonant frequency lowered to about 0.67 to 0.70 that of the simple reference dipole of the same length.

The three-wire linear-loaded dipole has its frequency reduced to 0.55 to 0.60 of the simple dipole of the same length. As you will see later, these values will vary with conductor diameter and spacing.

The two-wire linear-loaded dipole (Fig 60B) looks almost like a folded dipole but, unlike a folded dipole, it is open in the middle of the side opposite where the feed line is attached. Measurements show that this antenna structure has a resonant frequency lowered to about two-thirds that of the reference dipole, and R equal to about 35 Ω. A three-wire linear-loaded dipole (Fig 60C) has even lower resonant frequency and R about 25 to 30 Ω.

Linear-loaded monopoles (one half of the dipoles in Fig 60) working against a radial ground plane have similar resonant frequencies, but with only half the radiation resistance shown for the dipoles.

A Ladder-Line Linear-Loaded Dipole

Based on these results, NN0F next constructed a linear loaded dipole as in Fig 60B, using 24 feet of 1-inch ladder line (the black, 450-Ω plastic kind widely available) for the dipole length. He hung the system from a tree using nylon fishing line, about 4 feet from the tree at the top, and about 8 feet from the ground on the bottom end. It was slanted at about a 60° angle to the ground. This antenna resonated at 12.8 MHz and had a measured resistance of about 35 Ω. After the resonance measurements, he fed it with 1-inch ladder open-wire line (a total of about 100 feet to the shack).

For brevity, this is called a vertical *LLSD* (linear-loaded short dipole). A tuner resonated the system nicely on 20 and 30 meters. On these bands the performance of the vertical LLSD seemed comparable to his 120-foot long, horizontal center-fed Zepp, 30 feet above ground. In some directions where the horizontal, all-band Zepp has nulls, such as toward Siberia, the vertical LLSD was definitely superior. This system also resonates on 17 and 40 meters. However, from listening to various signals, NN0F had the impression that this length LLSD is not as good on 17 and 40 meters as the horizontal 120-foot antenna.

Using Capacitance End Hats

He also experimented with an even shorter resonant length by trying an LLSD with capacitance end-hats. The hats, as expected, increased the radiation resistance and lowered the resonant frequency. Six-foot long, single-wire hats were used on each end of the previous 24-foot LLSD, as shown in **Fig 61**. The antenna was supported in the same way as the previous vertical dipole, but the bottom-end hat wire was only inches from the grass. This system resonated at 10.6 MHz with a measured resistance of 50 Ω.

If the dipole section were lengthened slightly, by a foot or so, to about 25 feet, it should hit the 10.1-MHz band and be a good match for 50-Ω coax. It would be suitable for a restricted space, shortened 30-meter antenna. Note that this antenna is only about half the length of a conventional 30-meter dipole, needs no tuner, and has no losses due to traps. It does have the loss of the extra wire, but this is essentially negligible.



Fig 61—Two-wire linear-loaded dipole with capacitance end hats. Main dipole length was constructed from 24 feet of "windowed" ladder line. The end-hat elements were stiff wires 6 feet long. The antenna was strung at about a 60° angle from a tree limb using monofilament fishing line. Measured resonant frequency and radiation resistance were 10.6 MHz and 50 Ω.

Any of the linear-loaded dipole antennas can be mounted either horizontally or vertically. The vertical version can be used for longer skip contacts—beyond 600 miles or so—unless you have rather tall supports for horizontal antennas to give a low elevation angle. Using different diameter conductors in linear-loaded antenna configurations yields different results, depending on whether the larger or small diameter conductor is fed. NN0F experimented with a vertical ground-plane antenna using a 10-foot piece of electrical conduit pipe (⅝ inch OD) and #12 copper house wire.

Fig 62 shows the configuration. The radial ground system was buried a couple of inches under the soil and is not shown. Note that this is not a folded monopole, which would have either A or B grounded.

The two conductors were separated by 2 inches, using plastic spreaders held onto the pipe by stainless-steel hose clamps obtained from the local hardware store. Hose clamps intertwined at right angles were also used to clamp the pipe on electric fence stand-off insulators on a short 2×4 post set vertically in the ground.

The two different diameter conductors make the antenna characteristics change, depending on how they are configured. With the antenna bridge connected to the larger diameter conductor (point A in Fig 62), and point B unconnected, the system resonated at 16.8 MHz and had R = 35 Ω. With the bridge at B (the smaller conductor), and point A left unconnected, the resonance lowered to 12.4 MHz and R was found to be about 24 Ω.

The resonant frequency of the system in Fig 62 can be adjusted by changing the overall height, or for increasing the frequency, by reducing the length of the wire. Note that a 3.8-MHz resonant ground plane can be made with height only about half that of the usual 67 feet required, if the smaller conductor is fed (point B in Fig 62). In this case, the pipe would be left unconnected electrically. The lengths given above can be scaled to determine a first-try attempt for your favorite band. Resonant lengths will, however, depend on the conductor diameters and spacing.



Fig 62—Vertical ground-plane antenna with a 10-foot pipe and #12 wire as the linear-loaded element. Resonant frequency and radiation resistance depend on which side (A or B) is fed. The other side (B or A) is *not* grounded. See text for details.

The same ideas hold for a dipole, except that the lengths should be doubled from those of the ground plane in Fig 62. The resistance will be twice that of the ground plane. Say, how about a shortened 40-meter horizontal beam to enhance your signal?!

COMBINED LOADING

As an antenna is shortened further the size of the top loading device will become larger and at some point will be impractical. In this situation inductive loading, usually placed directly between the capacitance "hat" and the top of the antenna, can be added to resonate the antenna. An alternative would be to use linear loading in place of inductive loading. The previous section contained an example of end loading combined with linear loading.

SHORTENING THE RADIALS

Very often the space required by full-length radials is simply not available. Like the vertical portion of the antenna, the radials can also be shortened and loaded in very much the same way. An example of end loaded radials is given in **Fig 63A**. Radials half the usual length can be used with little reduction in efficiency but, as in the case of top loading, the antenna Q will be higher and the bandwidth reduced. As shown in Fig 63B**,** inductive loading can also be used. As long as they are not made too short (down to 0.1λ) loaded radials can be efficient—with careful design.



Fig 63—Radials may be shortened by using either capacitive (A) or inductive (B) loading. In extreme cases both may be used but the operating bandwidth will be limited.

GENERAL RULES

The steps in designing an efficient short vertical antenna system are:

- Make the vertical section as long as possible.
- Make the diameter of the vertical section as large as possible. Tubing or a cage of smaller wires will work well.
- Provide as much top and/or bottom loading as possible.
- If the top/bottom loading is insufficient, resonate the antenna with a high-Q inductor placed between the hat and the top of the antenna.
- For buried-ground systems, use as many radials (> 0.2 λ) as possible. 40 or more is best.
- If an elevated ground plane is used, use 4 to 8 radials, 5 or more feet above ground.
- If shortened radials must be used then capacitive loading is preferable to inductive loading.

EXAMPLES OF SHORT VERTICALS

A 6-Foot-High 7-MHz Vertical Antenna

Figs 64 through 67 give details for building short, effective vertical quarter-wavelength radiators. This information was originally presented by Jerry Sevick, W2FMI.

A short vertical antenna, properly designed and installed, approaches the efficiency of a full-size resonant quarter-wave antenna. Even a 6-foot vertical on 7 MHz can produce an exceptional signal. Theory tells us that this should be possible, but the practical achievement of such a result requires an understanding of the problems of ground losses, loading, and impedance matching.

The key to success with shortened vertical antennas lies in the efficiency of the ground system with which the antenna is used. A system of at least 60 radial wires is rec-



Fig 64—Jerry Sevick, W2FMI, adjusts the 6-foot high, 40-meter vertical.

ommended for best results, although the builder may elect to reduce the number at the expense of some performance. The radials can be tensioned and pinned at the far ends to permit on-the-ground installation, which will enable the amateur to mow the lawn without the wires becoming entangled in the mower blades. Alternatively, the wires can be buried in the ground, where they will not be visible. There is nothing critical about the wire size for the radials. Radials made of 28, 22, or even 16-gauge wire, will provide the same results. The radials should be at least 0.2 λ long (27 feet or greater on 7 MHz).

A top hat is formed as illustrated in **Fig 65**. The diameter is 7 feet, and a continuous length of wire is connected to the spokes around the outer circumference of the wheel. A loading coil consisting of 14 turns of B&W 3029 Miniductor stock (2½-inch dia, 6 TPI, #12 wire) is installed 6 inches below the top hat (see Fig 65). This antenna exhibits a feed-point impedance of 3.5 Ω at 7.21 MHz. For operation above or below this frequency, the number of coil turns must be decreased or increased, respectively. Matching is accomplished by increasing the feed-point impedance to 14 Ω through addition of a 4:1-transformer, then matching 14 Ω to 50 Ω (feeder impedance) by means of a pi network. The 2:1 SWR bandwidth for this antenna is approximately 100 kHz.



Fig 65—Construction details for the top hat. For a diameter of 7 feet, ½-in. aluminum tubing is used. The hose clamp is made of stainless steel and is available at Sears. The rest of the hardware is aluminum.



Fig 66—Standing-wave ratio of the 6-foot vertical using a 7-foot top hat and 14 turns of loading 6 inches below the top hat.

More than 200 contacts with the 6-foot antenna have indicated the efficiency and capability of a short vertical. Invariably at distances greater than 500 or 600 miles, the short vertical yields excellent signals. Similar antennas can be scaled and constructed for bands other than 7 MHz. The 7-foot-diameter-top hat was tried on a 3.5-MHz vertical, with an antenna height of 22 feet. The loading coil had 24 turns and was placed 2 feet below the top hat. On-the-air results duplicated those on 40-meters. The bandwidth was 65 kHz.

Short verticals such as these have the ability to radiate and receive almost as well as a full-size quarter-wave. Trade-offs are in lowered input impedances and bandwidths. However, with a good radial system and a proper design, these trade-offs can be made entirely acceptable.

Short Continuously Loaded Verticals

While there is the option of using lumped inductance to achieve resonance in a short antenna, the antenna can also be helically wound to provide the required inductance. This is shown in **Fig 68**. Shortened quarter-wavelength vertical antennas can be made by forming a helix on a long cylindrical insulator. The diameter of the helix must be small in terms of λ to prevent the antenna from radiating in the axial mode.

Acceptable form diameters for HF-band operation are from 1 inch to 10 inches when the practical aspects of antenna construction are considered. Insulating poles of fiberglass, PVC tubing, treated bamboo or wood, or phenolic are suitable for use in building helically wound radiators. If wood or bamboo is used the builder should treat the material with at least two coats of exterior spar varnish prior to winding the antenna element. The completed structure should be given two more coats of varnish, regardless of the material used for the coil form. Application of the varnish will help weatherproof the antenna and prevent the coil turns from changing position.

No strict rule has been established concerning how short a helically wound vertical can be before a significant drop in performance is experienced. Generally, one should use the greatest amount of length consistent with available space. A guideline might be to maintain an element length of 0.05 wavelength or more for antennas which are electrically a quarter wavelength long. Thus, use 13 feet or more of stock for an 80-meter antenna, 7 feet for 40 meters, and so on.

A quarter-wavelength helically wound vertical can be used in the same manner as a full-size vertical. That is, it can be worked against an above-ground wire radial system (four or more radials), or it can be ground-mounted with



Fig 67—Base of the vertical antenna showing the 60 radial wires. The aluminum disc is 15 inches in diameter and ¼ inches thick. Sixty tapped holes for ¼-20 aluminum hex-head bolts form the outer ring and 20 form the inner ring. The inner bolts were used for performance comparisons with more than 60 radials. The insulator is polystyrene material (phenolic or Plexiglas suitable) with a 1-inch diameter. Also shown is the impedance bridge used for measuring input resistance.



Fig 68—Helically wound ground-plane vertical. Performance from this type of antenna is comparable to that of many full-size λ/4 vertical antennas. The major design trade-off is usable bandwidth. All shortened antennas of this variety are narrow-band devices. At 7 MHz, in the example illustrated here, the bandwidth between the 2:1 SWR points will be on the order of 50 kHz, half that amount on 80 meters, and twice that amount on 20 meters. Therefore, the antenna should be adjusted for operation in the center of the frequency band of interest.

radials buried or lying on the ground. Some operators have reported good results when using antennas of this kind with four helically wound radials cut for resonance at the operating frequency. The latter technique should capture the attention of those persons who must use indoor antennas.

Winding Information

There is no hard-and-fast formula for determining the amount of wire needed to establish resonance in a helical antenna. The relationship between the length of wire needed for resonance and a full quarter wave at the desired frequency depends on several factors. Some of these are wire size, diameter of the turns, and the dielectric properties of the form material, to name a few. Experience has indicated that a section of wire approximately one half wavelength long, wound on an insulating form with a linear pitch (equal spacing between turns) will come close to yielding a resonant quarter wavelength. Therefore, an antenna for use on 160 meters would require approximately 260 feet of wire, spirally wound on the support.

No specific rule exists concerning the size or type of wire one should use in making a helix. Larger wire sizes are, of course, preferable in the interest of minimizing I^2R losses in the system. For power levels up to 1000 W it is wise to use a wire size of #16 or larger. Aluminum clothesline wire is suitable for use in systems where the spacing between turns is greater than the wire diameter. Antennas requiring close-spaced turns can be made from enameled magnet wire or #14 vinyl jacketed, single-conductor house wiring stock. Every effort should be made to keep the turn spacing as large as is practical to maximize efficiency.

A short rod or metal disc should be made for the top or high-impedance end of the vertical. This is a necessary part of the installation to assure reduction in antenna Q. This broadens the bandwidth of the system and helps prevent extremely high amounts of RF voltage from being developed at the top of the radiator. (Some helical antennas act like Tesla coils when used with high-power transmitters, and can actually catch fire at the high-impedance end when a stub or disc is not used.) Since the Q-lowering device exhibits some additional capacitance in the system, it must be in place before the antenna is tuned.

Tuning and Matching

Once the element is wound it should be mounted where it will be used, with the ground system installed. The feed end of the radiator can be connected temporarily to the ground system. Use a dip meter to check the antenna for resonance by coupling the dipper to the last few turns near the ground end of the radiator. Add or remove turns until the vertical is resonant at the desired operating frequency.

It is impossible to predict the absolute value of feed impedance for a helically wound vertical. The value will depend upon the length and diameter of the element, the ground system used with the antenna, and the size of the disc or stub atop the radiator. Generally speaking, the radiation resistance will be very low—approximately 3 to 10 Ω. An L network of the kind shown in Fig 68 can be used to increase the impedance to 50 Ω. The Q_L (loaded Q) of the network inductors is low to provide reasonable bandwidth, consistent with the bandwidth of the antenna. Network values for other operating bands and frequencies can be determined by using the reactance values listed below. The design center for the network is based on a radiation resistance of 5 Ω. If the exact feed impedance is known, the following equations can be used to determine precise component values for the matching network. (See Chapter 25, Coupling the Transmitter to the Line, for additional information on L-network matching.)

XA QRL (Eq 7)

$$X_{C2} = 50\sqrt{\frac{R_L}{50 - R_L}} \qquad \text{(Eq 8)}$$

$$X_{L1} = X_{C1} + \frac{R_L\,50}{X_{C2}} \qquad \text{(Eq 9)}$$

where

X_{C1} = capacitive reactance of C1
X_{C2} = capacitive reactance of C2
X_{L1} = inductive reactance of L1
Q = loaded Q of network
R_L = radiation resistance of antenna

Example: Find the network constants for a helical antenna with a feed impedance of 5 Ω at 7 MHz, Q = 3:

$$X_{C1} = 3 \times 5 = 15$$

$$X_{C2} = \sqrt{\frac{5}{50-5}} = 16.666$$

$$X_{L1} = 15 + \frac{250}{16.666} = 30$$

Therefore, C1 = 1500 pF, C2 = 1350 pF, and L1 = 0.7 µH. The capacitors can be made from parallel or series combinations of transmitting micas. L_1 can be a few turns of large Miniductor stock. At RF power levels of 100 W or less, large compression trimmers can be used at C1 and C2 because the maximum RMS voltage at 100 W (across 50 Ω) will be 50 V. At, say, 800 W there will be approximately 220 V RMS developed across 50 Ω. This suggests the use of small transmitting variables at C1 and C2, possibly connected in parallel with fixed values of capacitance to constitute the required amount of capacitance for the network.

By making some part of the network variable, it will be possible to adjust the circuit for an SWR of 1:1 without knowing precisely what the antenna feed impedance is. Actually, C1 is not required as part of the matching network. It is included here to bring the necessary value for L1 into a practical range.

Fig 68 illustrates the practical form a typical helically wound ground-plane vertical might take. Performance from this type antenna is comparable to that of many full-size quarter-wavelength vertical antennas. The major design trade-off is in usable bandwidth. All shortened antennas of this variety are narrow-band devices. At 7 MHz, in the example illustrated here, the bandwidth between the 2:1 SWR points will be on the order of 50 kHz, half that amount on 80 meters, and twice that amount on 20 meters. Therefore, the antenna should be adjusted for operation in the center of the frequency spread of interest.

SHORTENED DIPOLES

As shown in preceding sections, there are a number of ways to load antennas so they may be reduced in size without severe reductions in effectiveness. Loading is always a compromise; the best method is determined by the amount of space available and the band(s) to be worked.

The simplest way to shorten a dipole is shown in **Fig 69**. If you do not have sufficient length between the supports, simply hang as much of the center of the antenna as possible between the supports and let the ends hang down. The ends can be straight down or may be at an angle as indicated but in either case should be secured so that they do not move in the wind. As long as the center portion between the supports is at least ¼, the radiation pattern will be very nearly the same



Fig 69—When space is limited, the ends may be bent downward as shown at A, or back on the radiator as shown at B. The bent dipole ends may come straight down or be led off at an angle away from the center of the antenna. An inverted V at C can be erected with the ends bent parallel to the ground when the support structure is not high enough.



Fig 70—At A is a dipole antenna lengthened electrically with off-center loading coils. For a fixed dimension A, greater efficiency will be realized with greater distance B, but as B is increased, L must be larger in value to maintain resonance. If the two coils are placed at the ends of the antenna, in theory they must be infinite in size to maintain resonance. At B, capacitive loading of the ends, either through proximity of the antenna to other objects or through the addition of capacitance hats, will reduce the required value of the coils. At C, a fan dipole provides some electrical lengthening as well as broadbanding.

as a full-length dipole.

The resonant length of the wire will be somewhat shorter than a full-length dipole and can best be determined by experimentally adjusting the length of ends, which may be conveniently near ground. Keep in mind that there can be very high potentials at the ends of the wires and for safety the ends should be kept out of reach. Letting the ends hang down as shown is a form of capacitive end loading. While it is efficient, it will also reduce the matching bandwidth—as does any form of loading.

The most serious drawback associated with inductive loading is high loss in the coils themselves. It is important that you use inductors made from reasonably large wire or tubing to minimize this problem. Close winding of turns should also be avoided if possible. A good compromise is to use some off-center inductive loading in combination with capacitive end loading, keeping the inductor losses small and the efficiency as high as possible.

Some examples of off-center coil loading and capacitive-end loading are shown in **Fig 70**. This technique was described by Jerry Hall, K1TD in Sep 1974 *QST*. In the equation below, the diameter D is that of the wire used for the antenna, in inches. The frequency f is expressed in MHz.



Fig 71—Chart for determining approximate inductance values for off-center-loaded dipoles. See Fig 70A. At the intersection of the appropriate curve from the body of the chart for dimension A and proper value for the coil position from the horizontal scale at the bottom of the chart, read the required inductive reactance for resonance from the scale at the left. Dimension A is expressed as percent length of the shortened antenna with respect to the length of a half-wave dipole of the same conductor material. Dimension B is expressed as the percentage of coil distance from the feed point to the end of the antenna. For example, a shortened antenna, which is 50% or half the size of a half-wave dipole (one-quarter wavelength overall) with loading coils positioned midway between the feed point and each end (50% out), would require coils having an inductive reactance of approximately 950 Ω at the operating frequency for antenna resonance.



Fig 72—The WØSVM "Shorty Forty" center-loaded antenna. Dimensions given are for 7.0 MHz. The loading coil is 5 inches long and 2½ inches diameter. It has a total of 30 turns of #12 wire wound at 6 turns per inch (Miniductor 3029 stock).

For the antennas shown, the longer the overall length (dimension A, Fig 70A, in feet) and the farther the loading coils are from the center of the antenna (dimension B, also in feet), the greater the efficiency of the antenna. As dimension B is increased, however, the inductance required to resonate the antenna at the desired frequency increases.

Approximate inductive reactances for single-band resonance (for the antenna in Fig 70A only) may be determined with the aid of **Fig 71** or from Eq 10 below. The final values will depend on the proximity of surrounding objects in individual installations and must be determined experimentally. The use of high-Q low-loss coils is important for maximum efficiency.

A dip meter or SWR indicator is recommended for use during adjustment of the system. Note that the minimum inductance required is for a center-loaded dipole. If the inductive reactance is read from Fig 66 for a dimension B of zero, one coil having approximately twice this reactance can be used near the center of the dipole. **Fig 72** illustrates this idea. This antenna was conceived by Jack Sobel, WØSVM, who dubbed the 7-MHz version the "Shorty Forty."

$$X_L = \frac{10^6}{34\pi f}\left(\frac{\ln\frac{24\left(\frac{234}{f}\right)-B}{D}-1\left(\left(1-\frac{fB}{234}\right)^2-1\right)}{\frac{234}{f}-B}-\frac{\left(\ln\frac{24\left(\frac{A}{2}-B\right)}{D}-1\right)\left(\left(\frac{\frac{fA}{2}-fB}{234}\right)^2-1\right)}{\frac{A}{2}-B}\right) \quad \text{(Eq 10)}$$

Inverted-L Antennas

The antenna shown in **Fig 73** is called an *inverted-L* antenna. It is simple and easy to construct and is a good antenna for the beginner or the experienced 1.8-MHz DXer. Because the overall electrical length is made somewhat greater than λ/4, the feed-point resistance is on the order of 50 Ω, with an inductive reactance. That reactance is canceled by a series capacitor as indicated in the figure. For a vertical section length of 60 feet and a horizontal section length of 115 feet, the input impedance is ≈ 40 + *j* 300 Ω. Longer vertical or horizontal sections would increase the input impedance. The azimuthal radiation pattern is slightly asymmetrical with ≈1 to 2-dB increase in the direction opposite to the horizontal wire. This antenna requires a good buried ground system or elevated radials and will have a 2:1 SWR bandwidth of about 50 kHz.

This antenna is a form of top-loaded vertical, where the top loading is asymmetrical. This results in both vertical and horizontal polarization because the currents in the top wire do not cancel like they would in a symmetrical-T vertical. This is not necessarily a bad thing because it eliminates the zenith null present in a true vertical. This allows for good communication at short ranges as well as for DX.

A yardarm attached to a tower or a tree limb can be used to support the vertical section. As with any vertical, for best results the vertical section should be as long as possible. A good ground system is necessary for good results—the better the ground, the better the results.

If you don't have the space for the inverted L shown in Fig 73 (with its 115-foot horizontal section) and if you don't have a second tall supporting structure to make the top



Fig 73—The 1.8-MHz inverted L. Overall wire length is 165 to 175 feet. The variable capacitor has a capacitance range from 100 to 800 pF, at 3 kV or more. Adjust antenna length and variable capacitor for lowest SWR.



Fig 74—Sketch showing a modified 160-meter inverted L, with a single supporting 60-foot high tower and a 79-foot long slanted top-loading wire. The feed-point impedance is about 12 Ω in this system, requiring a quarter-wave matching transformer made of paralleled 50-Ω coaxes.

wire horizontal, consider sloping the top wire down towards ground. **Fig 74** illustrates such a setup, with a 60-foot high vertical section and a 79-foot sloping wire. As always, you will have to adjust the length of the sloping wire to fine-tune the resonant frequency. For a good ground radial system, the feed-point impedance is about 12 Ω, which may be transformed to 50 Ω with a 25-Ω quarter-wave transformer consisting of two paralleled 50-Ω quarter-wave coaxes. The peak gain will decrease about 1 dB compared to the inverted L shown in Fig 73. **Fig 75** overlays the elevation responses for average ground conditions. The 2:1 SWR bandwidth will be about 30 kHz, narrower than the larger system in Fig 73.

If the ground system suggested for Figs 73 and 74 is not practical, you can use a single elevated radial as shown in **Fig 76**. For the dimensions shown in the figure $Z_i = 50 + j\,498$ Ω, requiring a 175-pF series resonating capacitor. The azimuthal radiation pattern is shown in **Fig 77** compared to



Fig 75—Overlay of the elevation responses for the inverted-L antennas in Fig 73 (solid line) and Fig 74 (dashed line). The gains are very close for these two setups, provided that the ground radial system for the antenna in Fig 74 is extensive enough to keep ground losses low.



Fig 76—A single elevated radial can be used for the inverted-L. This changes the directivity slightly. The series tuning capacitor is approximately 175 pF for this system.



Fig 77—Azimuthal pattern comparison for inverted-L antennas shown in Fig 73 (solid line) and the compromise, single-radial system in Fig 76 (dashed line). This is for a takeoff angle of 10°.



Fig 78—Azimuthal pattern at a takeoff angle of 5° for an 80-meter version of the inverted L (solid line) in Fig 73, compared to the response for a 100-foot high flattop dipole (dashed line).



Fig 79—Details and dimensions for gamma-match feeding a 50-foot tower as a 1.8-MHz vertical antenna. The rotator cable and coaxial feed line for the 14-MHz beam is taped to the tower legs and run into the shack from ground level. No decoupling networks are necessary.

the inverted L in Fig 68. Note that the 1 to 2-dB asymmetry is now in the direction of the horizontal wires, just the opposite of that for a symmetrical ground system. The 2:1 SWR bandwidth is about 40 kHz, assuming that the series capacitor is adjusted at 1.83 MHz for minimum SWR.

Fig 78 shows the azimuthal response at a 5° elevation angle for an 80-meter version of the inverted L in Fig 73. The peak response occurs at an azimuth directly behind the direction in which the horizontal portion of the inverted L points. For comparison, the response for a 100-foot high flattop dipole is also shown. The top wire of this antenna is only 40 feet high and the 2:1 SWR bandwidth is about 150 kHz wide with a good, low-loss ground-radial system.

Fig 78 illustrates that the azimuth response of an inverted L is nearly omnidirectional. This gives such an antenna an advantage in certain directions compared to a flattop dipole, which is constrained by its supporting mounts (such as trees or towers) to favor fixed directions. For example, the flattop dipole in Fig 78 is at its weakest at azimuths of 90° and 270°, where it is down about 12 dB compared to the inverted L. Hams who are fortunate enough to have high rotary dipoles or rotatable low-band Yagis have found them to be very effective antennas indeed.

A DIFFERENT APPROACH

Fig 79 shows the method used by Doug DeMaw, W1FB, to gamma match his self-supporting 50-foot tower operating as an inverted L. A wire cage simulates a gamma rod of the proper diameter. The tuning capacitor is fashioned from telescoping sections of 1½ and 1½-inch aluminum tubing with polyethylene tubing serving as the dielectric. This capacitor is more than adequate for power levels of 100 W. The horizontal wire connected to the top of the tower provides the additional top loading.

Sloper Antennas

Sloping dipoles and λ/2 dipoles can be very useful antennas on the low bands. These antennas can have one end attached to a tower, tree or other structure and the other end near ground level, elevated high enough so that passersby can't contact them, of course. The following section gives a number of examples of these types of antennas.

THE HALF-WAVE SLOPING DIPOLE

If you have a sufficiently high support, you can install a halfwave dipole sloping downwards toward ground to provide vertical as well as horizontal polarization. This antenna is popularly known as a *sloper* or a *halfwave sloper*. The amount of slope from horizontal can vary from 0°, where the dipole is in a flattop configuration, all the way to 90°, where the dipole becomes fully vertical. The latter configuration is sometimes called a *Halfwave Vertical Dipole* (HVD).



Fig 80—At A, the azimuthal responses for a flattop dipole (solid line), a dipole whose end has been tilted down 45° (dashed line), and a HVD (halfwave vertical dipole, dotted line). All these were modeled over average ground, with a conductivity of 5 mS/m and a dielectric constant of 13. Note that the tilted dipole exhibits about 5 dB front-to-back ratio, although its maximum gain is less than either the HVD or flattop dipole. At B, the elevation-plane patterns for the same antennas. Note that the tilted halfwave dipole (dashed line) has more energy at higher elevation angles than either the flattop dipole or HVD.

The question arises when contemplating a vertical halfwave dipole or a halfwave sloping dipole about how to treat the feed line to make sure it doesn't accidentally become part of the radiating system. The ideal situation would be to bring the feed line out perpendicular to the vertical or sloping wire for an infinite distance. Obviously, that isn't very practical because the feed line eventually has to be connected to a transmitter located near the ground. An intensive modeling study on feeding an HVD was done for the book *Simple and Fun Antennas for Hams*. This study indicated that a slant angle down to the ground of as little as 30° from a vertical radiator can work with only minor interaction, provided that common-mode decoupling chokes were employed at the feed point and a quarter-wavelength down the line from the feed point. These common-mode chokes can consist of either discrete ferrite beads placed over the outer jacket of the coaxial line or multiple turns of the coax itself to form a choke.

Fig 80A compares the 40-meter azimuthal patterns at a DX takeoff angle of 5° for three configurations: a flattop dipole, a dipole tilted down 45° and an HVD (halfwave vertical dipole). These are computed for ground with average conductivity and dielectric constant, and for a maximum height of 80 feet in each configuration. The sloping halfwave dipole exhibits about 5 dB of front-to-back ratio, although even at its most favored direction it doesn't quite have the same maximum gain as the HVD or the flattop dipole.

The reason why the maximum gain for the sloper is less than the other two configurations, even while still exhibiting some front-to-back pattern, is shown in Fig 80A, which shows the elevation-plane patterns for the same antennas, each at the azimuth of maximum gain. The halfwave sloper distributes much of its energy higher in elevation than the HVD, lowering the peak-gain potential of the sloper.

You can also see from Fig 80B that the 80-foot high horizontal dipole would perform much better than either the HVD or halfwave sloper for close-in local contacts, which occur at high elevation angles. On the other hand, except for the greater gain exhibited in the flattop dipole's most favored directions, the HVD has more gain than the other antennas at low elevation angles. While the HVD's omnidirectional pattern is a plus for transmitting, it may be a problem for receiving, where local noise may be coming from specific directions (such as power lines) and may also be predominantly vertically polarized. In such cases, a horizontally polarized flattop dipole may be a considerably better receiving antenna than a vertically polarized antenna of any sort. We've already mentioned the fact that a rotary flattop dipole high in the air can be a very effective antenna on the low bands.

THE QUARTER-WAVELENGTH "HALF SLOPER"

Perhaps one of the easiest antennas to install is the λ/4 sloper shown in **Fig 81**. As pointed out above, a sloping λ/2 dipole is known among radio amateurs as a *sloper* or sometimes as a *full sloper*. If only one half of it is used, it becomes a *half sloper*. The performance of the two types of sloping antennas is similar—They exhibit some directivity in the direction of the slope and radiate vertically polarized energy at low angles respective to the horizon. The amount of directivity will range from 3 to 6 dB, depending upon the individual installation, and will be observed in the slope direction.

The main advantage of the half sloper over the full half-wave-long sloping dipole is that its supporting tower needn't be as high. Both the half sloper and the full sloper place the feed point (the point of maximum current) high above lossy ground. But the half-sloper only needs half as much wire to build the antenna for a given amateur band. The disadvantage of the half sloper is that it is sometimes difficult or even impossible to obtain a low SWR when using coaxial-cable feed, especially without a good isolating choke balun. (See the section above on isolating ground-plane antennas.)

Other factors that affect the feed impedance are tower height, height of the attachment point, enclosed angle between the sloper and the tower, and what is mounted atop the tower (HF or VHF beams). Further, the quality of the ground under the tower (ground conductivity, radials, etc) has a marked effect on the antenna performance. The final SWR can vary (after optimization) from 1:1 to as high as 6:1. Generally speaking, the closer the low end of the slope wire is to ground, the more difficult it will be to obtain a good match.

Basic Recommendations for a Half Sloper

The half sloper can be an excellent DX type of antenna. Hams usually install theirs on a metal supporting structure such as a mast or tower. The support needs to be grounded at the lower end, preferably to a buried or on-ground radial system. If a nonconductive support is used, the outside of the coax braid becomes the return circuit and should be grounded at the base of the support. As a starting point you can attach the sloper so the feed point is approximately λ/4 above ground. If the tower is not high enough to permit this, the antenna should be fastened as high on the supporting structure as possible. Start with an enclosed angle of approximately 45°, as indicated in Fig 81. Cut the wire to the length determined from

$$\ell = \frac{260}{f_{MHz}} \qquad \text{(Eq 11)}$$

This will allow sufficient extra length for pruning the wire for the lowest SWR. A metal tower or mast becomes an operating part of the half sloper system. In effect, it and the slope wire function somewhat like an inverted-V dipole antenna. In other words, the tower operates as the missing half of the dipole. Hence its height and the top loading (beams) play a significant role.

Detailed modeling indicates that a sufficiently large



Fig 81—The λ/4 "half slopper" antenna.



Fig 82—Radiation pattern for a typical half sloper (solid line) mounted on a 50-foot high tower with a large 5-element 20-meter beam on the top compared to that for a flattop dipole (dashed line) at 100 feet. At a 5° takeoff angle typical for DX work on 80 meters, the two antennas are pretty comparable in the directions favored by the high dipole. In other directions, the half sloper has an advantage of more than 10 dB.



Fig 83—Comparison of elevation patterns for a full-sized halfwave sloper (solid line) on a 100-foot tower and a half sloper (dashed line) on a 50-foot tower with a 5-element 20-meter Yagi acting as a top counterpoise. The performance is quite comparable for these two systems.



Fig 84—Comparing the azimuthal response of a half sloper (solid line) on a 50-foot tower with a 3-element 20-meter Yagi on top to that of a flattop dipole (dashed line) at 100 feet. The two are again quite comparable at a 5° takeoff angle.

mass of metal (that is, a large, “Plumber’s Delight” Yagi) connected to the top of the tower acts like enough of a “top counterpoise” that the tower may be removed from the model with little change in the essential characteristics of the half-sloper system. Consider an installation using a freestanding 50-foot tower with a large 5-element 20-meter Yagi on top. This Yagi is assumed to have a 40-foot boom oriented 90° to the direction of the slanted 80-meter half-sloper wire. The best SWR that could be reached by changing the length and slant angle for this sloper is 1.67:1, representing a feed-point impedance of 30.1 – j 2.7 Ω. The peak gain at 3.8 MHz is 0.97 dBi at an elevation angle of 70°. **Fig 82** shows the azimuth-plane pattern for this half sloper, compared to a 100-foot high flattop dipole for reference, at an elevation angle of 5°.

Removing the tower from the model resulted in a feed-point impedance of 30.1 – j 1.5 Ω and a peak gain of 1.17 dBi. The tower is obviously not contributing much in this setup, since the mass of the large 20-meter Yagi is acting like an elevated counterpoise all by itself. It’s interesting to rotate the boom of the model Yagi and observe the change in SWR that occurs on the half-sloper antenna. With the boom turned 90°, the SWR falls to 1.38:1. This level of SWR change could be measured with amateur-type instrumentation.

On the other hand, substituting a smaller 3-element 20-meter Yagi with an 18-foot boom in the model does result in significant change in feed-point impedance and gain when the tower is removed from the model, indicating that the “counterpoise effect” of the smaller beam is insufficient by itself. Interestingly enough, the best SWR for the half sloper/tower and the 3-element Yagi (with its boom inline with the half sloper is 1.33:1), changing to 1.27:1 with the boom turned 90°. Such a small change in SWR would be difficult to measure using typical amateur instrumentation.

In any case, the 50-Ω transmission line feeding a half sloper should be taped to the tower leg at frequent intervals to make it secure. The best method is to bring it to earth level, then route it to the operating position along the surface of the ground if it can’t be buried. This will ensure adequate RF decoupling, which will help prevent RF energy from affecting the equipment in the station. Rotator cable and other feed lines on the tower or mast should be treated in a similar manner.

Adjustment of the half sloper is done with an SWR indicator in the 50-Ω transmission line. A compromise can usually be found between the enclosed angle and wire length, providing the lowest SWR attainable in the center of the chosen part of an amateur band. If the SWR “bottoms out” at 2:1 or lower, the system will work fine without using an antenna tuner, provided the transmitter can work into the load. Typical optimum values of SWR for 3.5 or 7-MHz half slopers are between 1.3:1 and 2:1. A 100-kHz bandwidth is normal on 3.5 MHz, with 200 kHz being typical at 7 MHz.

If the lowest SWR possible is greater than 2:1, the attachment point can be raised or lowered to improve the match. Readjustment of the wire length and enclosed angle may be necessary when the feed-point height is changed. If the tower is guyed, the guy wires will need to be insulated from the tower and broken up with additional insulators to prevent resonance.

At this point you may be curious about which antenna is better—a full sloper or a half sloper. The peak gain for each antenna is very nearly identical. **Fig 83** overlays the elevation-plane pattern for the full-sized halfwave sloper on a 100-foot tower and for the half sloper shown in Fig 81 on a 50-foot tower with a 5-element 20-meter Yagi on top. The


Relay Switch Box
45°
130'
92' Tower
Guy Wires
Guy Wires
15'
Tower Ground
Ground Anchor
52 Ω Transmission Line
Ground Anchor

Fig 85—The W1CF half sloper for 160 meters is arranged in this manner. Three monoband antennas atop the tower provide capacitive loading.

full-sized halfwave sloper has more front-to-back ratio, but it is only a few dB more than the half sloper. **Fig 84** compares the azimuthal patterns at a 5° takeoff angle for a 100-foot high flattop dipole and a half-sloper system on a 50-foot tower with a 3-element 20-meter Yagi on top.

Despite the frustration some have experienced trying to achieve a low SWR with some half-sloper installations, many operators have found the half sloper to be an effective and low-cost antenna for DX work.

1.8-MHz ANTENNA SYSTEMS USING TOWERS

The half sloper discussed above for 80 or 40-meter operation will also perform well on 1.8 MHz where vertically polarized radiators can achieve the low takeoff angles needed on Topband. Prominent 1.8-MHz operators who have had success with the half sloper antenna suggest a minimum tower height of 50 feet. Dana Atchley, W1CF (SK), used the configuration sketched in **Fig 85**. He reported that the uninsulated guy wires act as an effective counterpoise for the sloping wire. In **Fig 86** is the feed system used by Doug


Insulator
Aluminum Clamp
λ/4 Radiator
Shield Braid Under Clamp
Seal With Epoxy
Tower Leg
Insulator
Tape
to Station

Fig 86—Feed system used by W1FB for 1.8 MHz half sloper on a 50-foot self-supporting tower.

DeMaw, W1FB (SK), on a 50-foot self-supporting tower. The ground for the W1FB system is provided by buried radials connected to the tower base.

As described previously, a tower can also be used as a true vertical antenna, provided a good ground system is used. The shunt-fed tower is at its best on 1.8 MHz, where a full λ/4 vertical antenna is rarely possible. Almost any tower height can be used. An HF beam at the top provides some top loading.

THE K1WA 7-MHz "SLOPER SYSTEM"

One of the more popular antennas for 3.5 and 7 MHz is the half-wave long sloping dipole described previously. David Pietraszewski, K1WA, made an extensive study of sloping dipoles at different heights with reflectors at the 3-GHz frequency range. From his experiments, he developed the novel 7-MHz antenna system described here. With several sloping dipoles supported by a single mast and a switching network, an antenna with directional characteristics and forward gain can be simply constructed. This 7-MHz system uses several "slopers" equally spaced around a common center support. Each dipole is cut to λ/2 and fed at the center with 50-Ω coax. The length of each feed line is 36 feet.



Fig 88—The basic materials required for the sloper system. The control box appears at the left, and the relay box at the right.

All of the feed lines go to a common point on the support (tower) where the switching takes place. The line length of 36 feet is just over 3λ/8, which provides a useful quality. At 7 MHz, the coax looks inductive to the antenna when the end at the switching box is open circuited. This has the effect of adding inductance at the center of the sloping dipole element, which electrically lengthens the element. The 36-foot length of feed line serves to increase the length of the element about 5%. This makes any unused element appear to be a reflector.

The array is simple and effective. By selecting one of the slopers through a relay box located at the tower, the system becomes a parasitic array that can be electrically rotated. All but the driven element of the array become reflectors.

The physical layout is shown in **Fig 87**, and the basic materials required for the sloper system are shown in **Fig 88**. The height of the support point should be about 70 feet, but can be less and still give reasonable results. The upper portion of the sloper is 5 feet from the tower, suspended by rope. The wire makes an angle of 60° with the ground.



Fig 87—Five sloping dipoles suspended from one support. Directivity and forward gain can be obtained from this simple array. The top view shows how the elements should be spaced around the support.



Fig 89—Inside view of relay box. Four relays provide control over five antennas. See text. The relays pictured here are Potter and Brumfeld type MR11D.

In **Fig 89**, the switch box is shown containing all the necessary relays to select the proper feed line for the desired direction. One feed line is selected at a time and the feed lines of those remaining are opened, **Fig 90**. In this way the array is electrically rotated. These relays are controlled from inside the shack with an appropriate power supply and rotary switch. For safety reasons and simplicity, 12-volt dc relays are used. The control line consists of a five conductor cable, one wire used as a common connection; the others go to the four relays. By using diodes in series with the relays and a dual-polarity power supply, the number of control wires can be reduced, as shown in Fig 90B.

Measurements indicate that this sloper array provides up to 20 dB front-to-back ratio and forward gain of about 4 dB over a single half-wave sloper. **Fig 91** shows the azimuthal pattern (at a 5° takeoff angle) for the K1WA array, compared to a 100-foot high flattop dipole and a full sloper suspended from a 50-foot tower. These patterns were calculated for average ground conditions. Just for fun, look at



Fig 90—Schematic diagram for sloper control system. All relays are 12-volt dc, DPDT, with 8-A contact ratings. At A, the basic layout, excluding control cable and antennas. Note that the braid of the coax is also open-circuited when not in use. Each relay is bypassed with 0.001-µF capacitors. The power supply is a low current type. At B, diodes are used to reduce the number of control wires when using dc relays. See text.



Fig 91—Azimuth pattern for K1WA 40-meter sloper array (solid line), compared to a flattop dipole (dashed line) at 100 feet and a halfwave full sloper on a 50-foot tower (dotted line). The K1WA array has an excellent front-to-back ratio and almost as much gain as the high flattop dipole. These patterns are for average ground.

Fig 92, which shows a comparison between a 100-foot high flattop dipole and a K1WA array placed over saltwater. Now that's a real barnburner at low takeoff angles! Such a seaside system would be very competitive with a rotatable 2-element "shorty-40" type of Yagi.

If one direction is the only concern, the switching system can be eliminated and the reflectors should be cut 5% longer than the resonant frequency. The feature worth noting is the good F/B ratio. By arranging the system properly, a null can be placed in an unwanted direction, thus making it an effective receiving antenna. In the tests conducted with this antenna, the number of reflectors used were as few as one and as many as five. The optimum combination appeared to occur with four reflectors and one driven element. No tests were conducted with more than five reflectors. This same array can be scaled to 3.5 MHz for similar results.



Fig 92—The K1WA 40-meter sloper array over saltwater, compared to a 100-foot high flattop dipole. At A, azimuth patterns. At B, elevation patterns. Now the sloper array really comes into its own!

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below.

D. Atchley, Jr., "Putting the Quarter-Wave Sloper to Work on 160," *QST*, Jul 1979, pp 19-20.

J. Belrose, "Transmission Line Low Profile Antennas," *QST*, Dec 1975, pp 19-25.

L. Braskamp, AA6GL, "*MOBILE*, a Computer Program for Short HF Verticals," *The ARRL Antenna Compendium Vol 4*, pp 92-96.

G. H. Brown, "The Phase and Magnitude of Earth Currents Near Radio Transmitting Antennas," *Proc. IRE*.

G. H. Brown, R. F. Lewis and J. Epstein, "Ground Systems as a Factor in Antenna Efficiency," *Proc. IRE* , Jun 1937, pp 753-787.

P. Carr, N4PC, "A Two Band Half-Square Antenna With Coaxial Feed," *CQ*, Sep 1992, pp 40-45.

P. Carr, N4PC, "A DX Antenna For 40 Meters," *CQ*, Sep 1994, pp 40-43.

A. Christman, KB8I, "Elevated Vertical Antennas for the Low Bands," *The ARRL Antenna Compendium Vol 5*, pp 11-18.

Curry Communications, PO Box 1884, Burbank, CA 91507, a kit manufacturer of lowfer CW transceivers.

D. DeMaw, "Additional Notes on the Half Sloper," *QST*, Jul 1979, p 20.

P. Dodd, *The LF Experimenter's Source Book* (RSGB, 1996).

A. C. Doty, Jr., J. A. Frey and H. J. Mills, "Efficient Ground Systems for Vertical Antennas," *QST*, Feb 1983, pp 9-12.

S. Ford, "*Low*fing on 1750 Meters," *QST*, Oct 1993, pp 67-68.

R. Fosberg, "Some Notes on Ground Systems for 160 Meters," *QST*, Apr 1965, pp 65-67.

J. Hall, "Off-Center-Loaded Dipole Antennas," *QST*, Sep 1974, pp 28-34.

G. Hubbell, "Feeding Grounded Towers as Radiators," *QST*, pp 32-33, 140, 142.

C. Hutchinson and R. D. Straw, *Simple and Fun Antennas for Hams* (Newington, Ct: ARRL, 2002).

P. H. Lee, *The Amateur Radio Vertical Antenna Handbook*, 1st edition (Port Washington, NY: Cowan Publishing Corp., 1974).

C. J. Michaels, "Some Reflections on Vertical Antennas," *QST*, July 1987, pp 15-19; feedback *QST*, Aug 1987, p 39.

Rashed and C. Tai, "A New Class of Wire Antennas," 1982 International Symposium Digest, *Antennas and Propagation*, Vol 2, IEEE.

T. Russell, N4KG, "Simple, Effective, Elevated Ground-Plane Antennas," *QST*, June 1994, pp 45-46

F. J. Schnell, "The Flagpole Deluxe," *QST*, Mar 1978, pp 29-32.

R. Severns, N6LF, "Using the Half-Square Antenna for Low-Band Dxing," *The ARRL Antenna Compendium Vol 5*, pp 35-42.

R. Severns, N6LF, "Broadbanding the Half-Square Antenna For 80-meter Dxing," *The ARRL Antenna Compendium Vol 5*, pp 43-44.

R. Severns, N6LF, "An Improved Double Extended Zepp," *The ARRL Antenna Compendium Vol 4*, pp 78-80.

J. Sevick, "The Ground-Image Vertical Antenna," *QST*, Jul 1971, pp 16-19, 22.

J. Sevick, "The W2FMI Ground-Mounted Short Vertical," *QST*, Mar 1973, pp 13-18, 41.

J. Sevick, "The Constant-Impedance Trap Vertical," *QST* , Mar 1974, pp 29-34.

J. Sevick, "Short Ground-Radial Systems for Short Verticals," *QST*, Apr 1978, pp 30-33.

J. Sevick, W2FMI, *Transmission Line Transformers* (Noble Publishing, Atlanta, 1996).

W. Smith, W6BCX, "Bet My Money On A Bobtail Beam," *CQ*, Mar 1948, pp 21-23, 92.

J. Stanford, NNØF, "Linear-Loaded Short Wire Antennas," *The ARRL Antenna Compendium Vol 5*, pp 105-107.

J. Swank, W8HXR, "The S-Meter Bender," *73*, Jun 1978, pp 170-173.

J. Tyskewicz, "The Heli-Rope Antenna," *QST*, Jun 1971.

B. Vester, K3BC, "The Half-Square Antenna," *QST*, Mar 1974, pp 11-14.

A. D. Watt, *VLF Radio Engineering* (Pergamon Press, 1967) (out of print).

Prediction of Sky-wave Field Strength at Frequencies Between About 150 and 1700 kHz, ITU Doc 3/14, Radiocommunication Study Groups, Feb 1995.

Chapter 7

Multiband Antennas

For operation in a number of bands, such as those between 3.5 and 30 MHz, it would be impractical for most amateurs to put up a separate antenna for each band. But this is not necessary—a dipole, cut for the lowest frequency band to be used, can be operated readily on higher frequencies. To do so, one must be willing to accept the fact that such harmonic-type operation leads to a change in the directional pattern of the antenna, both in the azimuth and the elevation planes (see Chapter 2, Antenna Fundamentals, and Chapter 3, The Effects of Ground).

You can see from discussions in Chapter 6, Low-Frequency Antennas, that you should carefully plan the height at which you install a multiband horizontally polarized antenna. This is one aspect of multiband antennas. Another important thing to consider is that you should be willing to use so-called *tuned feeders*. A center-fed single-wire antenna can be made to accept power and radiate it with high efficiency on any frequency higher than its fundamental resonant frequency and, with a reduction in efficiency and bandwidth, on frequencies as low as one half the fundamental.

In fact, it is not necessary for an antenna to be a full half-wavelength long at the lowest frequency. An antenna can be considerably shorter than ½ λ, even as short as ¼ λ, and still be a very efficient radiator. The use of such short antennas results in stresses, however, on other parts of the system, for example the antenna tuner and the transmission line. This will be discussed in some detail in this chapter.

Methods have been devised for making a single antenna structure operate on a number of bands while still offering a good match to a transmission line, usually of the coaxial type. It should be understood, however, that a multiband antenna is not *necessarily* one that will match a given line on all bands on which you intend to use it. Even a relatively short whip type of antenna can be operated as a multiband antenna with suitable loading for each band. Such loading may be in the form of a coil at the base of the antenna on those frequencies where loading is needed, or it may be incorporated in the tuned feeders running from the transmitter to the base of the antenna.

This chapter describes a number of systems that can be used on two or more bands. Beam antennas, such as Yagis or quads, are treated separately in later chapters.

Simple Wire Antennas

The simplest multiband antenna is a random length of #12 or #14 wire. Power can be fed to the wire on practically any frequency using one or the other of the methods shown in **Fig 1**. If the wire is made either 67 or 135 feet long, it can also be fed through a tuned circuit, as in **Fig 2**. It is advantageous to use an SWR bridge or other indicator in the coax line at the point marked “X.”

If you have installed a 28- or 50-MHz rotary beam, in many cases it may be possible to use the beam’s feed line as an antenna on the lower frequencies. Connecting the two wires of the feeder together at the station end will give a random-length wire that can be conveniently coupled to the transmitter as in Fig 1. The rotary system at the far end will serve only to *end-load* the wire and will not have much other effect.



Fig 1—At A, a random-length wire driven directly from the pi-network output of a transmitter. At B, an L network for use in cases where sufficient loading cannot be obtained with the arrangement at A. C1 should have about the same plate spacing as the final tank capacitor in a vacuum-tube type of transmitter; a maximum capacitance of 100 pF is sufficient if L1 is 20 to 25 µH. A suitable coil would consist of 30 turns of #12 wire, 2½ inches diameter, 6 turns per inch. Bare wire should be used so the tap can be placed as required for loading the transmitter.



Fig 2—If the antenna length is 137 feet, a parallel-tuned coupling circuit can be used on each amateur band from 3.5 through 30 MHz, with the possible exception of the WARC 10-, 18- and 24-MHz bands. C1 should duplicate the final tank tuning capacitor and L1 should have the same dimensions as the final tank inductor on the band being used. If the wire is 67 feet long, series tuning can be used on 3.5 MHz as shown at the left; parallel tuning will be required on 7 MHz and higher frequency bands. C2 and L2 will in general duplicate the final tank tuning capacitor and inductor, the same as with parallel tuning. The L network shown in Fig 1B is also suitable for these antenna lengths.

One disadvantage of all such directly fed systems is that part of the antenna is practically within the station, and there is a good chance that you will have some trouble with RF feedback. RF within the station can often be minimized by choosing a length of wire so that the low feed-point impedance at a current loop occurs at or near the transmitter. This means using a wire length of λ/4 (65 feet at 3.6 MHz, 33 feet at 7.1 MHz), or an odd multiple of λ/4 (¾-λ is 195 feet at 3.6 MHz, 100 feet at 7.1 MHz). Obviously, this can be done for only one band in the case of even harmonically related bands, since the wire length that presents a current loop at the transmitter will present a voltage loop at two (or four) times that frequency.

When you operate with a random-length wire antenna, as in Figs 1 and 2, you should try different types of grounds on the various bands, to see what gives you the best results. In many cases it will be satisfactory to return to the transmitter chassis for the ground, or directly to a convenient metallic water pipe. If neither of these works well (or the metallic water pipe is not available), a length of #12 or #14 wire (approximately λ/4 long) can often be used to good advantage. Connect the wire at the point in the circuit that is shown grounded, and run it out and down the side of the house, or support it a few feet above the ground if the station is on the first floor or in the basement. It should not be connected to actual ground at any point.

END-FED ANTENNAS

When a straight-wire antenna is fed at one end with a two-wire transmission line, the length of the antenna portion becomes critical if radiation from the line is to be held to a minimum. Such an antenna system for multiband operation is the *end-fed Zepp* or *Zepp-fed* antenna shown in **Fig 3**. The antenna length is made λ/2 long at the lowest operating frequency. (This name came about because the first documented use of this sort of antennas was on the *Zeppelin* airships.) The feeder length can be anything that is convenient, but feeder lengths that are multiples of λ/4 generally give trouble with parallel currents and radiation from the feeder portion of the system. The feeder can be an open-wire line of #14 solid



Fig 3—An end-fed Zepp antenna for multiband use.

copper wire spaced 4 or 6 inches with ceramic or plastic spacers. Open-wire TV line (not the type with a solid web of dielectric) is a convenient type to use. This type of line is available in approximately 300- and 450-Ω characteristic impedances.

If you have room for only a 67-foot flat top and yet want to operate in the 3.5-MHz band, the two feeder wires can be tied together at the transmitter end and the entire system treated as a random-length wire fed directly, as in Fig 1. The simplest precaution against parallel currents that could cause feed-line radiation is to use a feeder length that is not a multiple of λ/4. An antenna tuner can be used to provide multiband coverage with an end-fed antenna with any length of open-wire feed line, as shown in Fig 3.

CENTER-FED ANTENNAS

The simplest and most flexible (and also least expensive) all-band antennas are those using open-wire parallel-conductor feeders to the center of the antenna, as in **Fig 4**. Because each half of the flat top is the same length, the feeder currents will be balanced at all frequencies unless, of course, unbalance is introduced by one half of the antenna being closer to ground (or a grounded object) than the other. For best results and to maintain feed-current balance, the feeder should run away at right angles to the antenna, preferably for at least λ/4.

Center feed is not only more desirable than end feed because of inherently better balance, but generally also results in a lower standing wave ratio on the transmission line, provided a parallel-conductor line having a characteristic impedance of 450 to 600 Ω is used. TV-type open-wire line is satisfactory for all but possibly high power installations (over 500 W), where heavier wire and wider spacing is desirable to handle the larger currents and voltages.

The length of the antenna is not critical, nor is the length of the line. As mentioned earlier, the length of the antenna can be considerably less than λ/2 and still be very effective. If the overall length is at least λ/4 at the lowest frequency, a quite usable system will result. The only difficulty that may exist with this type of system is the matter of coupling the antenna-system load to the transmitter. Most modern transmitters are designed to work into a 50-Ω coaxial load. With this type of antenna system a coupling network (an antenna tuner) is required.

Feed-Line Radiation

The preceding sections have pointed out means of reducing or eliminating feed-line radiation. However, it should be emphasized that any radiation from a transmission line is not "lost" energy and is not necessarily harmful. Whether or not feed-line radiation is important depends entirely on the antenna system being used. For example, feed-line radiation is not desirable when a directive array is being used. Such feed-line radiation can distort the desired pattern of such an array, producing responses in unwanted directions. In other words, you want radiation only from the directive array, rather than from the directive array and the feed line. See Chapter 26, Coupling the Line to the Antenna, for a detailed discussion of this topic.



Fig 4—A center-fed antenna system for multiband use.

On the other hand, in the case of a multiband dipole where general coverage is desired, if the feed line happens to radiate, such energy could actually have a desirable effect. Antenna purists may dispute such a premise, but from a practical standpoint where you are not concerned with a directive pattern, much time and labor can be saved by ignoring possible transmission-line radiation.

THE 135-FOOT, 80 TO 10-METER DIPOLE

As mentioned previously, one of the most versatile antennas around is a simple dipole, center-fed with open-wire transmission line and used with an antenna tuner in the shack. A 135-foot long dipole hung horizontally between two trees or towers at a height of 50 feet or higher works very well on 80 through 10 meters. Such an antenna system has significant gain at the higher frequencies.

Flattop or Inverted-V Configuration?

There is no denying that the inverted-V mounting configuration (sometimes called a *drooping dipole*) is very convenient, since it requires only a single support. The flattop configuration, however, where the dipole is mounted horizontally, gives more gain at the higher frequencies. **Fig 5** shows the 80-meter azimuth and elevation patterns for two 135-foot long dipoles. The first is mounted as a flattop at a height of 50 feet over flat ground with a conductivity of 5 mS/m and a dielectric constant of 13, typical for average soil. The second dipole uses the same length of wire, with the center apex at 50 feet and the ends drooped down to be suspended 10 feet off the ground. This height is sufficient so that there is no danger to passersby from RF burns.

At 3.8 MHz, the flattop dipole about 4 dB more peak gain than its drooping cousin. On the other hand, the inverted-V configuration gives a pattern that is more omnidirectional than the flattop dipole, which has nulls off the ends of the wire. Omnidirectional coverage may be more important to net operators, for example, than maximum gain.

Fig 6 shows the azimuth and elevation patterns for the same two antenna configurations, but this time at 14.2 MHz. The flattop dipole has developed four distinct lobes at a 10° elevation angle, an angle typical for 20-meter skywave communication. The peak elevation angle gain of 9.4 dBi occurs at about 17° for a height of 50 feet above flat ground for the flattop dipole. The inverted-V configuration is again nominally more omnidirectional, but the peak gain is down some 6 dB from the flattop.

The situation gets even worse in terms of peak gain at 28.4 MHz for the inverted-V configuration. Here the peak gain is down about 8 dB from that produced by the flattop dipole, which exhibits eight lobes at this frequency with a maximum gain of 10.5 dBi at about 7° elevation. See the comparisons in **Fig 7**.

Whatever configuration you choose to mount the 135-foot dipole, you will want to feed it with some sort of low-loss open-wire transmission line. So-called *window* 450-Ω ladder line is popular for this application. Be sure to twist the line about three or four turns per foot to keep it from twisting excessively in the wind. Make sure also that you provide some mechanical support for the line at the junction with the dipole



Fig 5—Patterns on 80 meters for 135-foot, center-fed dipole erected as a horizontal flattop dipole at 50 feet, compared with the same dipole installed as an inverted V with the apex at 50 feet and the ends at 10 feet. The azimuth pattern is shown at A, where the dipole wire lies in the 90° to 270° plane. At B, the elevation pattern, the dipole wire comes out of the paper at a right angle. On 80 meters, the patterns are not markedly different for either flattop or inverted-V configuration.



Fig 6—Patterns on 20 meters for two 135-foot dipoles. One is mounted horizontally as a flattop and the other as an inverted V with 120° included angle between the legs. The azimuth pattern is shown in A and the elevation pattern is shown in B. The inverted V has about 6 dB less gain at the peak azimuths, but has a more uniform, almost omnidirectional, azimuthal pattern. In the elevation plane, the inverted V has a fat lobe overhead, making it a somewhat better antenna for local communication, but not quite so good for DX contacts at low elevation angles.



Fig 7—Patterns on 10 meters for same antenna configurations as in Figs 7 and 8. Once again, the inverted-V configuration yields a more omnidirectional pattern, but at the expense of almost 8 dB less gain than the flattop configuration at its strongest lobes.

wires. This will prevent flexing of the transmission-line wire, since excessive flexing will result in breakage.

THE G5RV MULTIBAND ANTENNA

A multiband antenna that does not require a lot of space, is simple to construct, and is low in cost is the G5RV. Designed in England by Louis Varney (G5RV) some years ago, it has become quite popular in the US. The G5RV design is shown in **Fig 8**. The antenna may be used from 3.5 through 30 MHz. Although some amateurs claim it may be fed directly with 50-Ω coax on several amateur bands with a low SWR, Varney himself recommended the use of an antenna tuner on bands other than 14 MHz (see Bibliography). In fact, an analysis of the G5RV feed-point impedance shows there is *no* length of balanced line of *any* characteristic impedance that will transform the terminal impedance to the 50 to 75-Ω range on all bands. (Low SWR indication with coax feed and no matching network on bands other than 14 MHz may indicate excessive losses in the coaxial line.)



Fig 8—The G5RV multiband antenna covers 3.5 through 30 MHz. Although many amateurs claim it may be fed directly with 50-Ω coax on several amateur bands, Louis Varney, its originator, recommends the use of a matching network on bands other than 14 MHz.



Fig 9—Azimuth pattern at a 5° takeoff angle for a 102-foot long, 50-foot high G5RV dipole (solid line). For comparison, the response for a 132-foot long, center-fed dipole at 50 feet height (dashed line) and a 33-foot long half wave 20-meter dipole at 50 feet (dotted line) are also shown. The longest antenna exhibits about 0.5 dB more gain than the G5RV, although the response is more omnidirectional for the G5RV—an advantage for a wire antenna that is not usually rotatable.

Fig 9 shows the 20-meter azimuthal pattern for a G5RV at a height of 50 feet over flat ground, at an elevation angle of 5° that is suitable for DX work. For comparison, the response for two other antennas is also shown in Fig 9—a standard half wave 20-meter dipole at 50 feet and a 132-foot long center-fed dipole at 50 feet. The G5RV on 20 meters is, of course, longer than a standard half wave dipole and it exhibits about 2 dB more gain compared to that dipole. With four lobes making it look rather like a four-leaf clover, the azimuth pattern is more omnidirectional than the two-lobed dipole. The 132-foot center-fed dipole is longer than the G5RV and it has about 0.5 dB more gain than the G5RV, also exhibiting four major lobes, along with two strong minor lobes in the plane of the wire. Overall, the azimuthal response for the G5RV is more omnidirectional than the comparison antennas.

The G5RV patterns for other frequencies are similar to those shown for the 135-foot dipole previously for other frequencies. Incidentally, you may be wondering why a 132-foot dipole is shown in Fig 9, rather than the 135-foot dipole described earlier. The 132-foot overall length describes another antenna that we'll discus in the next section on Windom antennas.

The portion of the G5RV antenna shown as horizontal in Fig 8 may also be installed in an inverted-V dipole arrangement, subject to the same loss of peak gain mentioned above for the 135-foot dipole. Or instead, up to ⅙ of the total length of the antenna at each end may be dropped vertically, semi-vertically, or bent at a convenient angle to the main axis of the antenna, to cut down on the requirements for real estate.

THE WINDOM ANTENNA

An antenna that enjoyed popularity in the 1930s and into the 1940s was what we now call the *Windom*. It was known at the time as a "single-feeder Hertz" antenna, after being described in Sep 1929 *QST* by Loren G. Windom, W8GZ (see Bibliography).

The Windom antenna, shown in **Fig 10**, is fed with a single wire, attached approximately 14% off center. In theory, this location provides a match for the single-wire transmission line, which is worked against an earth ground. Because the single-wire feed line is not inherently well balanced and because it is brought to the operating position, "RF in the shack" and a potential radiation hazard may be experienced with this antenna.



Fig 10—The Windom antenna, cut for a fundamental frequency of 3.75 MHz. The single-wire feeder, connected 14% off center, is brought into the station and the system is fed against ground. The antenna is also effective on its harmonics.

Later variations of the off-center fed Windom moved the attachment point slightly to accommodate balanced 300-Ω ribbon line. One relatively recent variation is called the "Carolina Windom," apparently because two of the designers, Edgar Lambert, WA4LVB, and Joe Wright, W4UEB, lived in coastal North Carolina (the third, Jim Wilkie, WY4R, lived



Fig 11—Layout for flattop "Carolina Windom" antenna.



Fig 12—20-meter azimuth patterns for a 132-foot long off-center fed Carolina Windom and a 132-foot long center-fed flattop dipole on 20 meters, both at a height of 50 feet above saltwater. The response for the Carolina Windom is more omnidirectional because the vertically polarized radiation from the 22-foot long vertical RG-8X coax fills in the deep nulls.

in nearby Norfolk, Virginia). One of the interesting parts about the Carolina Windom is that it turns a potential disadvantage—feed line radiation—into a potential advantage.

Fig 11 is a diagram of a flattop Carolina Windom, which uses a 50-foot wire joined with an 83-foot wire at the feedpoint insulator. This resembles the layout shown in Fig 10 for the original W8GZ Windom. The "Vertical Radiator" for the Carolina Windom is a 22-foot piece of RG-8X coax, with a "Line Isolator" (current-type choke balun) at the bottom end and a 4:1 "Matching Unit" at the top. The system takes advantage of the asymmetry of the horizontal wires to induce current onto the braid of the vertical coax section. Note that the matching unit is a voltage-type balun transformer, which purposely does not act like a common-mode current choking balun. You must use an antenna tuner with this system to present a 1:1 SWR to the transmitter on the amateur bands from 80 through 10 meters.

The radiation resulting from current induced onto the 22-foot vertical coax section tends to fill in the deep nulls that would be present if the 132-feet of horizontal wire were symmetrically center fed. Over saltwater, the vertical radiator can give significant gain at the low elevation angles needed for DX work. Indeed, field reports for the Carolina Windom are most impressive for stations located near or on saltwater. Over average soil the advantage of the additional vertically polarized component is not quite so evident. **Fig 12** compares a 50-foot high Carolina Windom on 14 MHz over saltwater to a 50-foot high, 132-foot long, flattop center-fed dipole. The Carolina Windom has a more omnidirectional azimuthal pattern, a desirable characteristic in a 132-foot long wire antenna that is not normally rotated to favor different directions.

Another advantage of the Carolina Windom over a traditional Windom is that the coax feed line hanging below the common-mode current choke does not radiate, meaning that there will be less "RF in the shack." Since the feed line is not always operating at a low SWR on various ham bands, use the minimum length of feed coax possible to hold down losses in the coax.

Fig 13 shows the azimuth responses for a 50-foot long flattop Carolina Windom on 28.4 MHz over saltwater and over average soil. The pattern for a 50-foot high, flattop 20-meter dipole operated on 28.4 MHz is also shown, since this 20-meter dipole can also be used as a multiband antenna, when fed with open-wire transmission line rather than with coax. Again, the Carolina Windom exhibits a more omnidirectional pattern, even if the pattern is somewhat lopsided at the bottom.



Fig 13—10-meter azimuthal responses for a 132-foot long, 50-foot high Carolina Windom over saltwater (solid line) and over average ground (dashed line), compared to that for a 20-meter half-wave dipole at 50 feet (dotted line).

MULTIPLE-DIPOLE ANTENNAS

The antenna system shown in **Fig 14** consists of a group of center-fed dipoles, all connected in parallel at the point where the transmission line joins them. The dipole elements are *stagger-tuned*. That is, they are individually cut to be λ/2 at different frequencies. Chapter 9, Broadband Antenna Matching, discusses stagger tuning of dipole antennas to attain a low SWR across a broad range of frequencies. An extension of the stagger tuning idea is to construct multiwire dipoles cut for different bands.

In theory, the 4-wire antenna of Fig 14 can be used with a coaxial feeder on five bands. The four wires are prepared as parallel-fed dipoles for 3.5, 7, 14, and 28 MHz. The 7-MHz dipole can be operated on its 3rd harmonic for 21-MHz operation to cover a fifth band. However, in practice it has been found difficult to get a good match to coaxial line



Fig 14—Multiband antenna using paralleled dipoles all connected to a common low-impedance transmission line. The half-wave dimensions may be either for the centers of the various bands or selected to fit favorite frequencies in each band. The length of a half wave in feet is 468/frequency in MHz, but because of interaction among the various elements, some pruning for resonance may be needed on each band.

on all bands. The λ/2 resonant length of any one dipole in the presence of the others is not the same as for a dipole by itself due to interaction, and attempts to optimize all four lengths can become a frustrating procedure. The problem is compounded because the optimum tuning changes in a different antenna environment, so what works for one amateur may not work for another. Even so, many amateurs with limited antenna space are willing to accept the mismatch on some bands just so they can operate on those frequencies using a single coax feed line.

Since this antenna system is balanced, it is desirable to use a balanced transmission line to feed it. The most desirable type of line is 75-Ω transmitting twin-lead. However, either 52-Ω or 75-Ω coaxial line can be used. Coax line introduces some unbalance, but this is tolerable on the lower frequencies. An alternative is to use a balun at the feed point, fed with coaxial cable.

The separation between the dipoles for the various frequencies does not seem to be especially critical. One set of wires can be suspended from the next larger set, using insulating spreaders (of the type used for feeder spreaders) to give a separation of a few inches. Users of this antenna often run some of the dipoles at right angles to each other to help reduce interaction. Some operators use inverted-V-mounted dipoles as guy wires for the mast that supports the antenna system.

An interesting method of construction used successfully by Louis Richard, ON4UF, is shown in **Fig 15**. The antenna has four dipoles (for 7, 14, 21 and 28 MHz) constructed from 300-Ω ribbon transmission line. A single length of ribbon makes two dipoles. Thus, two lengths, as shown in the sketch, serve to make dipoles for four bands. Ribbon with copper-clad steel conductors (Amphenol type 14-022) should be used because all of the weight, including that of the feed line, must be supported by the uppermost wire.

Two pieces of ribbon are first cut to a length suitable for the two halves of the longest dipole. Then one of the conductors in each piece is cut to proper length for the next band higher in frequency. The excess wire and insulation is stripped away. A second pair of lengths is prepared in the same manner, except that the lengths are appropriate for the next two higher frequency bands.



Fig 15—Sketch showing how the twin-lead multiple-dipole antenna system is assembled. The excess wire and insulation are stripped away.

A piece of thick polystyrene sheet drilled with holes for anchoring each wire serves as the central insulator. The shorter pair of dipoles is suspended the width of the ribbon below the longer pair by clamps also made of poly sheet. Intermediate spacers are made by sawing slots in pieces of poly sheet so they will fit the ribbon snugly.

The multiple-dipole principle can also be applied to vertical antennas. Parallel or fanned λ/4 elements of wire or tubing can be worked against ground or tuned radials from a common feed point.

OFF-CENTER-FED DIPOLES

Fig 16 shows an off-center-fed or *OCF* dipole. Because it is similar in appearance to the Windom of Fig 12, this antenna is often mistakenly called a "Windom," or sometimes a "coax-fed Windom." The two antennas are not the same, since the Windom is worked against its image in the ground, while one leg is worked against the other in the OCF dipole.

It is not necessary to feed a dipole antenna at its center, although doing so will allow it to be operated with a relatively low feed-point impedance on its fundamental and *odd* harmonics. (For example, a 7-MHz center-fed half-wave dipole can also be used for 21-MHz operation.) By contrast, the OCF dipole of Fig 16, fed ⅓ of its length from one end, may be used on its fundamental and *even* harmonics. Its free-space antenna-terminal impedance at 3.5, 7 and 14 MHz is on the order of 150 to 200 Ω. A 1:4 step-up transformer at the feed point should offer a reasonably good match to 50- or 75-Ω line, although some commercially made OCF dipoles use a 1:6 transformer.

At the 6th harmonic, 21 MHz, the antenna is three wavelengths long and fed at a voltage loop (maximum), instead of a current loop. The feed-point impedance at this frequency



Fig 16—The off-center-fed (OCF) dipole for 3.5, 7 and 14 MHz. A 1:4 or 1:6 step-up current balun is used at the feed point.

is high, a few thousand ohms, so the antenna is unsuitable for use on this band.

Balun Requirements

Because the OCF dipole is not fed at the center of the radiator, the RF impedance paths of the two wires at the feed point are unequal. If the antenna is fed directly with coax (or a balanced line), or if a voltage step-up transformer is used, then voltages of equal magnitude (but opposite polarity) are applied to the wires at the feed point. Because of unequal impedances, the resulting antenna currents flowing in the two wires will not be equal. This also means that antenna current can flow on the feeder—on the *outside* of a coaxial line. (You may recall that this is how the Carolina Windom works, actually inducing current onto a carefully chosen length of coax, choked at its bottom end, so that it acts as a vertical radiator.)

How much current flows on the coax shield depends on the impedance of the RF current path down the outside of the feed line. In general, this is not a desirable situation. To prevent radiation, equal *currents* are required at the feed point, with the same current flowing in and out of the short leg as in and out of the long leg of the radiator. A *current* or *choke* type of balun provides just such operation. (Current baluns are discussed in detail in Chapter 26, Coupling the Line to the Antenna.)

Trap Antennas

By using tuned circuits of appropriate design strategically placed in a dipole, the antenna can be made to show what is essentially fundamental resonance at a number of different frequencies. The general principle is illustrated by **Fig 17**.

Even though a trap-antenna arrangement is a simple one, an explanation of how a trap antenna works can be elusive. For some designs, traps are resonated in our amateur bands, and for others (especially commercially made antennas) the traps are resonant far outside any amateur band.

A trap in an antenna system can perform either of two functions, depending on whether or not it is resonant at the operating frequency. A familiar case is where the trap is parallel-resonant in an amateur band. For the moment, let us assume that dimension A in Fig 17 is 32 feet and that each L/C combination is resonant in the 7-MHz band. Because of its parallel resonance, the trap presents a high impedance at that point in the antenna system. The electrical effect at 7 MHz is that the trap behaves as an insulator. It serves to divorce the outside ends, the B sections, from the antenna. The result is easy to visualize—we have an antenna system that is resonant in the 7-MHz band. Each 33-foot section (labeled A in the drawing) represents λ/4, and the trap behaves as an insulator. We therefore have a full-size 7-MHz antenna.



Fig 17—A trap dipole antenna. This antenna may be fed with 50-Ω coaxial line. Depending on the L/C ratio of the trap elements and the lengths chosen for dimensions A and B, the traps may be resonant either in an amateur band or at a frequency far removed from an amateur band for proper two-band antenna operation.

The second function of a trap, obtained when the frequency of operation is *not* the resonant frequency of the trap, is one of electrical loading. If the operating frequency is below that of trap resonance, the trap behaves as an inductor; if above, as a capacitor. Inductive loading will electrically lengthen the antenna, and capacitive loading will electrically shorten the antenna.

Let's carry our assumption a bit further and try using the antenna we just considered at 3.5 MHz. With the traps resonant in the 7-MHz band, they will behave as inductors when operation takes place at 3.5 MHz, electrically lengthening the antenna. This means that the total length of sections A and B (plus the length of the inductor) may be something less than a physical λ/4 for resonance at 3.5 MHz. Thus, we have a two-band antenna that is shorter than full size on the lower frequency band. But with the electrical loading provided by the traps, the overall electrical length is λ/2. The total antenna length needed for resonance in the 3.5-MHz band will depend on the L/C ratio of the trap elements.

The key to trap operation off resonance is its L/C ratio, the ratio of the value of L to the value of C. At resonance, however, within practical limitations the L/C ratio is immaterial as far as electrical operation goes. For example, in the antenna we've been discussing, it would make no difference for 7-MHz operation whether the inductor were 1 μH and the capacitor were 500 pF (the reactances would be just below 45 Ω at 7.1 MHz), or whether the inductor were 5 μH and the capacitor 100 pF (reactances of approximately 224 Ω at 7.1 MHz). But the choice of these values will make a significant difference in the antenna size for resonance at 3.5 MHz. In the first case, where the L/C ratio is 2000, the necessary length of section B of the antenna for resonance at 3.75 MHz would be approximately 28.25 feet. In the second case, where the L/C ratio is 50,000, this length need be only 24.0 feet, a difference of more than 15%.

The above example concerns a two-band antenna with trap resonance at one of the two frequencies of operation. On each of the two bands, each half of the dipole operates as an electrical λ/4. However, the same band coverage can be obtained with a trap resonant at, say, 5 MHz, a frequency quite removed from either amateur band. With proper selection of the L/C ratio and the dimensions for A and B, the trap will act to shorten the antenna electrically at 7 MHz and lengthen it electrically at 3.5 MHz. Thus, an antenna that is intermediate in physical length between being full size on 3.5 MHz and full size on 7 MHz can cover both bands, even though the trap is not resonant at either frequency. Again, the antenna operates with electrical λ/4 sections. Note that such non-resonant traps have less RF current flowing in the trap components, and hence trap losses are less than for resonant traps.

Additional traps may be added in an antenna section to cover three or more bands. Or a judicious choice of dimensions and the L/C ratio may permit operation on three or more bands with just a pair of identical traps in the dipole.

An important point to remember about traps is this. If the operating frequency is below that of trap resonance, the trap behaves as an inductor; if above, as a capacitor. The above discussion is based on dipoles that operate electrically as λ/2 antennas. This is not a requirement, however. Elements may be operated as electrical 3/2 λ, or even 5/2 λ, and still present a reasonable impedance to a coaxial feeder. In trap antennas covering several HF bands, using electrical lengths that are odd multiples of λ/2 is often done at the higher frequencies.

To further aid in understanding trap operation, let's now choose trap L and C components that each have a reactance of 20 Ω at 7 MHz. Inductive reactance is directly proportional to frequency, and capacitive reactance is inversely proportional. When we shift operation to the 3.5-MHz band, the inductive reactance becomes 10 Ω, and the capacitive reactance becomes 40 Ω. At first thought, it may seem that the trap would become capacitive at 3.5 MHz with a higher capacitive reactance, and that the extra capacitive reactance would make the antenna electrically shorter yet. Fortunately, this is not the case. The inductor and the capacitor are connected in parallel with each other.

$$Z = \frac{-jX_L X_C}{X_L + X_C} \qquad \text{(Eq 1)}$$

where *j* indicates a reactive impedance component, rather than resistive. A positive result indicates inductive reactance, and a negative result indicates capacitive. In this 3.5-MHz case, with 40 Ω of capacitive reactance and 10 Ω of inductive, the equivalent series reactance is 13.3 Ω inductive. This inductive loading lengthens the antenna to an electrical λ/2 overall at 3.5 MHz, assuming the B end sections in Fig 17 are of the proper length.

With the above reactance values providing resonance at 7-MHz, X_L equals X_C, and the theoretical series equivalent is infinity. This provides the insulator effect, divorcing the ends.

At 14 MHz, where $X_L = 40\ \Omega$ and $X_C = 10\ \Omega$, the resultant series equivalent trap reactance is 13.3 Ω capacitive. If the total physical antenna length is slightly longer than 3/2 λ at 14 MHz, this trap reactance at 14 MHz can be used to shorten the antenna to an electrical 3/2 λ. In this way, 3-band operation is obtained for 3.5, 7 and 14 MHz with just one pair of identical traps. The design of such a system is not straightforward, however, for any chosen L/C ratio for a given total length affects the resonant frequency of the antenna on both the 3.5 and 14-MHz bands.

Trap Losses

Since the tuned circuits have some inherent losses, the efficiency of a trap system depends on the unloaded Q values of the tuned circuits. Low-loss (high-Q) coils should be used, and the capacitor losses likewise should be kept as low as possible. With tuned circuits that are good in this respect—comparable with the low-loss components used in transmitter tank circuits, for example—the reduction in efficiency compared with the efficiency of a simple dipole is small, but tuned circuits of low unloaded Q can lose an appreciable portion of the power supplied to the antenna.

The commentary above applies to traps assembled from conventional components. The important function of a trap that is resonant in an amateur band is to provide a high isolating impedance, and this impedance is directly proportional to Q. Unfortunately, high Q restricts the antenna bandwidth, because the traps provide maximum isolation only at trap resonance.

FIVE-BAND W3DZZ TRAP ANTENNA

C. L. Buchanan, W3DZZ, created one of the first trap antennas for the five pre-1979 WARC amateur bands from 3.5 to 30 MHz. Dimensions are given in **Fig 18**. Only one set of traps is used, resonant at 7 MHz to isolate the inner (7-MHz) dipole from the outer sections. This causes the overall system to be resonant in the 3.5-MHz band. On 14, 21 and 28 MHz the antenna works on the capacitive-reactance principle just outlined. With a 75-Ω twin-lead feeder, the SWR with this antenna is under 2:1 throughout the three highest frequency



Fig 18—Five-band (3.5, 7, 14, 21 and 28 MHz) trap dipole for operation with 75-Ω feeder at low SWR (C. L. Buchanan, W3DZZ). The balanced (parallel-conductor) line indicated is desirable, but 75-Ω coax can be substituted with some sacrifice of symmetry in the system. Dimensions given are for resonance (lowest SWR) at 3.75, 7.2, 14.15 and 29.5 MHz. Resonance is very broad on the 21-MHz band, with SWR less than 2:1 throughout the band.

bands, and the SWR is comparable with that obtained with similarly fed simple dipoles on 3.5 and 7 MHz.

Trap Construction

Traps frequently are built with coaxial aluminum tubes (usually with polystyrene tubing in-between them for insulation) for the capacitor, with the coil either self-supporting or wound on a form of larger diameter than the tubular capacitor. The coil is then mounted coaxially with the capacitor to form a unit assembly that can be supported at each end by the antenna wires. In another type of trap devised by William J. Lattin, W4JRW (see Bibliography at the end of this chapter), the coil is supported inside an aluminum tube and the trap capacitor is obtained in the form of capacitance between the coil and the outer tube. This type of trap is inherently weatherproof.

A simpler type of trap, easily assembled from readily available components, is shown in **Fig 19**. A small transmitting-type ceramic "doorknob" capacitor is used, together with a length of commercially available coil material, these being supported by an ordinary antenna strain insulator. The circuit constants and antenna dimensions differ slightly from those of Fig 18, in order to bring the antenna resonance points closer to the centers of the various phone bands. Construction data are given in **Fig 20**. If a 10-turn length of inductor is used, a half turn from each end may be used to slip through the anchor holes in the insulator to act as leads.



Fig 19—Easily constructed trap for wire antennas (A. Greenburg, W2LH). The ceramic insulator is 4¼ inches long (Birnback 688). The clamps are small service connectors available from electrical supply and hardware stores (Burndy KS90 servits).



Fig 20—Layout of multiband antenna using traps constructed as shown in Fig 21. The capacitors are 100 pF each, transmitting type, 5000-volt dc rating (Centralab 850SL-100N). Coils are 9 turns of #12 wire, 2½ inches diameter, 6 turns per inch (B&W 3029) with end turns spread as necessary to resonate the traps to 7.2 MHz. These traps, with the wire dimensions shown, resonate the antenna at approximately the following frequencies on each band: 3.9, 7.25, 14.1, 21.5 and 29.9 MHz (based on measurements by W9YJH).

The components used in these traps are sufficiently weatherproof in themselves so that no additional weatherproofing has been found necessary. However, if it is desired to protect them from the accumulation of snow or ice, a plastic cover can be made by cutting two discs of polystyrene slightly larger in diameter than the coil, drilling at the center to pass the antenna wires, and cementing a plastic cylinder on the edges of the discs. The cylinder can be made by wrapping two turns or so of 0.02-inch poly or Lucite sheet around the discs, if no suitable ready-made tubing is available. Plastic drinking glasses and 2-liter soft-drink plastic bottles are easily adaptable for use as impromptu trap covers.

TWO W8NX MULTIBAND, COAX-TRAP DIPOLES

Over the last 60 or 70 years, amateurs have used many kinds of multiband antennas to cover the traditional HF bands. The availability of the 30, 17 and 12-meter bands has expanded our need for multiband antenna coverage.

Two different antennas are described here. The first covers the traditional 80, 40, 20, 15 and 10-meter bands, and the second covers 80, 40, 17 and 12 meters. Each uses the same type of W8NX trap—connected for different modes of operation—and a pair of short capacitive stubs to enhance coverage. The W8NX coaxial-cable traps have two different modes: a high- and a low-impedance mode. The inner-conductor windings and shield windings of the traps are connected in series for both modes. However, either the low- or high-impedance point can be used as the trap's output terminal. For low-impedance trap operation, only the center conductor turns of the trap windings are used. For high-impedance operation, all turns are used, in the conventional manner for a trap. The short stubs on each antenna are strategically sized and located to permit more flexibility in adjusting thc resonant frequencies of the antenna.

80, 40, 20, 15 and 10-Meter Dipole

Fig 21 shows the configuration of the 80, 40, 20, 15 and 10-meter antenna. The radiating elements are made of #14



Fig 21—A W8NX multiband dipole for 80, 40, 20, 15 and 10 meters. The values shown (123 pF and 4 μH) for the coaxial-cable traps are for parallel resonance at 7.15 MHz. The low-impedance output of each trap is used for this antenna.

stranded copper wire. The element lengths are the wire span lengths in feet. These lengths do not include the lengths of the pigtails at the balun, traps and insulators. The 32.3-foot-long inner 40-meter segments are measured from the eyelet of the input balun to the tension-relief hole in the trap coil form. The 4.9-foot segment length is measured from the tension-relief hole in the trap to the 6-foot stub. The 16.l-foot outer-segment span is measured from the stub to the eyelet of the end insulator.

The coaxial-cable traps are wound on PVC pipe coil forms and use the low-impedance output connection. The stubs are 6-foot lengths of ⅛-inch stiffened aluminum or copper rod hanging perpendicular to the radiating elements. The first inch of their length is bent 90° to permit attachment to the radiating elements by large-diameter copper crimp connectors. Ordinary #14 wire may be used for the stubs, but it has a tendency to curl up and may tangle unless weighed down at the end. You should feed the antenna with 75-Ω coax cable using a good 1:1 balun.

This antenna may be thought of as a modified W3DZZ antenna due to the addition of the capacitive stubs. The length and location of the stub give the antenna designer two extra degrees of freedom to place the resonant frequencies within the amateur bands. This additional flexibility is particularly helpful to bring the 15 and 10-meter resonant frequencies to more desirable locations in these bands. The actual 10-meter resonant frequency of the original W3DZZ antenna is somewhat above 30 MHz, pretty remote from the more desirable low frequency end of 10 meters.

80, 40, 17 and 12-Meter Dipole

Fig 22 shows the configuration of the 80, 40, 17 and 12-meter antenna. Notice that the capacitive stubs are attached immediately outboard after the traps and are 6.5 feet long, ½ foot longer than those used in the other antenna. The traps are the same as those of the other antenna, but are connected for the high-impedance parallel-resonant output mode. Since only four bands are covered by this antenna, it is easier to fine tune it to precisely the desired frequency on all bands. The 12.4-foot tips can he pruned to a particular 17-meter frequency with little effect on the 12-meter frequency. The stub lengths can be pruned to a particular 12-meter frequency with little effect on the 17-meter frequency. Both such pruning adjustments slightly alter the 80-meter resonant frequency. However, the bandwidths of the antennas are so broad on 17 and 12 meters that little need for such pruning exists. The 40-meter frequency is nearly independent of adjustments to the capacitive stubs and outer radiating tip elements. Like the first antennas, this dipole is fed with a 75-Ω balun and feed line.

Fig 23 shows the schematic diagram of the traps. It explains the difference between the low and high-impedance modes of the traps. Notice that the high-impedance terminal is the output configuration used in most conventional trap applications. The low-impedance connection is made across only the inner conductor turns, corresponding to one-half of the total turns of the trap. This mode steps the trap's impedance down to approximately one-fourth of that of the high-impedance level. This is what allows a single trap design to be used for two different multiband antennas.

Fig 24 is a drawing of a cross-section of the coax trap shown through the long axis of the trap. Notice that the traps are conventional coaxial-cable traps, except for the added low-impedance output terminal. The traps are 8¾ close-spaced turns of RG-59 (Belden 8241) on a 2⅜-inch-OD PVC pipe (schedule 40 pipe with a 2-inch ID) coil form. The forms are 4⅛ inches long. Trap resonant frequency is very sensitive to the outer diameter of the coil form, so check it carefully. Unfortunately, not all PVC pipe is made with the same wall thickness. The trap frequencies should be checked with a dip meter and general-coverage receiver and adjusted to within 50 kHz of the 7150 kHz resonant frequency before installation. One inch is left over at each end of the coil forms to allow for the coax feed-through holes and holes for tension-relief attachment of the antenna radiating elements to the traps. Be sure to seal the ends of the trap coax cable with RTV sealant to prevent moisture from entering the coaxial cable.

Also, be sure that you connect the 32.3-foot wire element at the start of the inner conductor winding of the trap. This avoids detuning the antenna by the stray capacitance of the coaxial-cable shield. The trap output terminal (which has the shield stray capacitance) should be at the outboard side of



Fig 23—Schematic for the W8NX coaxial-cable trap. RG-59 is wound on a 2⅜-inch OD PVC pipe.



Fig 22—A W8NX multiband dipole for 80, 40, 17 and 12 meters. For this antenna, the high-impedance output is used on each trap. The resonant frequency of the traps is 7.15 MHz.



Fig 24—Construction details of the W8NX coaxial-cable trap.

the trap. Reversing the input and output terminals of the trap will lower the 40-meter frequency by approximately 50 kHz, but there will be negligible effect on the other bands.

Fig 25 shows a coaxial-cable trap. Further details of the trap installation are shown in **Fig 26**. This drawing applies specifically to the 80, 40, 20, 15 and l0-meter antenna, which uses the low-impedance trap connections. Notice the lengths of the trap pigtails: 3 to 4 inches at each terminal of the trap. If you use a different arrangement, you must modify the span lengths accordingly. All connections can be made using crimp connectors rather than by soldering. Access to the trap's interior is attained more easily with a crimping tool than with a soldering iron.

Performance

The performance of both antennas has been very satisfactory. W8NX uses the 80, 40, 17 and 12-meter version because it covers 17 and 12 meters. (He has a tribander for 20, 15 and 10 meters.) The radiation pattern on 17 meters is that of a $\frac{3}{2}$-wave dipole. On 12 meters, the pattern is that of a $\frac{5}{2}$-wave dipole. At his location in Akron, Ohio, the antenna runs essentially east and west. It is installed as an inverted V, 40 feet high at the center, with a 120° included angle between the legs. Since the stubs are very short, they radiate little power and make only minor contributions to the radiation patterns. In theory, the pattern has four major lobes on 17 meters, with maxima to the northeast, southeast, southwest and northwest. These provide low-angle radiation into Europe, Africa, South Pacific, Japan and Alaska. A narrow pair of minor broadside lobes provides north and south coverage into Central America, South America and the polar regions.

There are four major lobes on 12 meters, giving nearly end-fire radiation and good low-angle east and west coverage. There are also three pairs of very narrow, nearly broadside, minor lobes on 12 meters, down about 6 dB from the major end-fire lobes. On 80 and 40 meters, the antenna has the usual figure-8 patterns of a half-wave-length dipole.

Both antennas function as electrical half-wave dipoles on 80 and 40 meters with a low SWR. They both function as odd-harmonic current-fed dipoles on their other operating frequencies, with higher, but still acceptable, SWR. The presence of the stubs can either raise or lower the input impedance of the antenna from those of the usual third and fifth harmonic dipoles. Again W8NX recommends that 75-Ω,



Fig 25—Other views of a W8NX coax-cable trap.



Fig 26—Additional construction details for the W8NX coaxial-cable trap.

rather than 50-Ω, feed line be used because of the generally higher input impedances at the harmonic operating frequencies of the antennas.

The SWR curves of both antennas were carefully measured using a 75 to 50-Ω transformer from Palomar Engineers inserted at the junction of the 75-Ω coax feed line and a 50-Ω SWR bridge. The transformer is required for accurate SWR measurement if a 50-Ω SWR bridge is used with a 75-Ω line. Most 50-Ω rigs operate satisfactorily with a 75-Ω line, although this requires different tuning and load settings in the final output stage of the rig or antenna tuner. The author uses the 75 to 50-Ω transformer only when making SWR measurements and at low power levels. The transformer is rated for 100 W, and when he runs his 1-kW PEP linear amplifier the transformer is taken out of the line.



Fig 27—Measured SWR curves for an 80, 40, 20, 15 and 10-meter antenna, installed as an inverted-V with 40-ft apex and 120° included angle between legs.



Fig 28—Measured SWR curves for an 80, 40, 17 and 12-meter antenna, installed as an inverted-V with 40-ft apex and 120° included angle between legs.

Fig 27 gives the SWR curves of the 80, 40, 20, 15 and 10-meter antenna. Minimum SWR is nearly 1:1 on 80 meters, 1.5:1 on 40 meters, 1.6:1 on 20 meters, and 1.5:1 on 10 meters. The minimum SWR is slightly below 3:1 on 15 meters. On 15 meters, the stub capacitive reactance combines with the inductive reactance of the outer segment of the antenna to produce a resonant rise that raises the antenna input resistance to about 220 Ω, higher than that of the usual 3/2-wavelength dipole. An antenna tuner may be required on this band to keep a solid-state final output stage happy under these load conditions.

Fig 28 shows the SWR curves of the 80, 40, 17 and 12-meter antenna. Notice the excellent 80-meter performance with a nearly unity minimum SWR in the middle of the band. The performance approaches that of a full-size 80-meter wire dipole. The short stubs and the low-inductance traps shorten the antenna somewhat on 80 meters. Also observe the good 17-meter performance, with the SWR being only a little above 2:1 across the band.

But notice the 12-meter SWR curve of this antenna, which shows 4:1 SWR across the band. The antenna input resistance approaches 300 Ω on this band because the capacitive reactance of the stubs combines with the inductive reactance of the outer antenna segments to give resonant rises in impedance. These are reflected back to the input terminals. These stub-induced resonant impedance rises are similar to those on the other antenna on 15 meters, but are even more pronounced.

Too much concern must not be given to SWR on the feed line. Even if the SWR is as high as 9:1 *no destructively high voltages will exist on the transmission line.* Recall that transmission-line voltages increase as the square root of the SWR in the line. Thus, 1 kW of RF power in 75-Ω line corresponds to 274 V line voltage for a 1:1 SWR. Raising the SWR to 9:1 merely triples the maximum voltage that the line must withstand to 822 V. This voltage is well below the 3700-V rating of RG-11, or the 1700-V rating of RG-59, the two most popular 75-Ω coax lines. Voltage breakdown in the traps is also very unlikely. As will be pointed out later, the operating power levels of these antennas are limited by RF power dissipation in the traps, not trap voltage breakdown or feed-line SWR.

Trap Losses and Power Rating

Table 1 presents the results of trap Q measurements and extrapolation by a two-frequency method to higher frequencies above resonance. W8NX employed an old, but recently calibrated, Boonton Q meter for the measurements. Extrapolation to higher-frequency bands assumes that trap resistance losses rise with skin effect according to the square root of frequency, and that trap dielectric loses rise directly with frequency. Systematic measurement errors are not increased by frequency extrapolation. However, random measurement

Table 1
Trap Q

Frequency (MHz)	*3.8*	*7.15*	*14.18*	*18.1*	*21.3*	*24.9*	*28.6*
High Z out (Ω)	101	124	139	165	73	179	186
Low Z out (Ω)	83	103	125	137	44	149	155

Table 2
Trap Loss Analysis: 80, 40, 20, 15, 10-Meter Antenna

Frequency (MHz)	*3.8*	*7.15*	*14.18*	*21.3*	*28.6*
Radiation Efficiency (%)	96.4	70.8	99.4	99.9	100.0
Trap Losses (dB)	0.16	1.5	0.02	0.01	0.003

Table 3
Trap Loss Analysis: 80, 40, 17, 12-Meter Antenna

Frequency (MHz)	*3.8*	*7.15*	*18.1*	*24.9*
Radiation Efficiency (%)	89.5	90.5	99.3	99.8
Trap Losses (dB)	0.5	0.4	0.03	0.006

errors increase in magnitude with upward frequency extrapolation. Results are believed to be accurate within 4% on 80 and 40 meters, but only within l0 to 15% at 10 meters. Trap Q is shown at both the high- and low-impedance trap terminals. The Q at the low-impedance output terminals is 15 to 20% lower than the Q at the high-impedance output terminals.

W8NX computer-analyzed trap losses for both antennas in free space. Antenna-input resistances at resonance were first calculated, assuming lossless, infinite-Q traps. They were again calculated using the Q values in Table 1. The radiation efficiencies were also converted into equivalent trap losses in decibels. **Table 2** summarizes the trap-loss analysis for the 80, 40, 20, 15 and 10-meter antenna and **Table 3** for the 80, 40,17 and 12-meter antenna.

The loss analysis shows radiation efficiencies of 90% or more for both antennas on all bands except for the 80, 40, 20, 15 and 10-meter antenna when used on 40 meters. Here, the radiation efficiency falls to 70.8%. A 1-kW power level at 90% radiation efficiency corresponds to 50-W dissipation per trap. In W8NX's experience, this is the trap's survival limit for extended key-down operation. SSB power levels of 1 kW PEP would dissipate 25 W or less in each trap. This is well within the dissipation capability of the traps.

When the 80, 40, 20, 15 and 10-meter antenna is operated on 40 meters, the radiation efficiency of 70.8% corresponds to a dissipation of 146 W in each trap when 1 kW is delivered to the antenna. This is sure to burn out the traps—even if sustained for only a short time. Thus, the power should be limited to leas than 300 W when this antenna is operated on 40 meters under prolonged key-down conditions. A 50% CW duty cycle would correspond to a 600-W power limit for normal 40-meter CW operation. Likewise, a 50% duty cycle for 40-meter SSB corresponds to a 600-W PEP power limit for the antenna.

The author knows of no analysis where the burnout wattage rating of traps has been rigorously determined. Operating experience seems to be the best way to determine trap burnout ratings. In his own experience with these antennas, he's had no traps burn out, even though he operated the 80, 40, 20, 15 and 10-meter antenna on the critical 40-meter band using his AL-80A linear amplifier at the 600-W PEP output level. He did not make a continuous, key-down, CW operating test at full power purposely trying to destroy the traps!

Some hams may suggest using a different type of coaxial cable for the traps. The dc resistance of 40.7 Ω per 1000 feet of RG-59 coax seems rather high. However, W8NX has found no coax other than RG-59 that has the necessary inductance-to-capacitance ratio to create the trap characteristic reactance required for the 80, 40, 20, 15 and 10-meter antenna. Conventional traps with wide-spaced, open-air inductors and appropriate fixed-value capacitors could be substituted for the coax traps, but the convenience, weatherproof configuration and ease of fabrication of coaxial-cable traps is hard to beat.

Multiband Vertical Antennas

There are two basic types of vertical antennas; either type can be used in multiband configurations. The first is the ground-mounted vertical and the second, the ground plane. These antennas are described in detail in Chapter 6, Low-Frequency Antennas.

The efficiency of any ground-mounted vertical depends a great deal on near-field earth losses. As pointed out in Chapter 3, The Effects of Ground, these near-field losses can be reduced or eliminated with an adequate radial system. Considerable experimentation has been conducted on this subject by Jerry Sevick, W2FMI, and several important results were obtained. It was determined that a radial system consisting of 40 to 50 radials, 0.2 λ long, would reduce the earth losses to about 2 Ω when a λ/4 radiator was being used. These radials should be on the earth's surface, or if buried, placed not more than an inch or so below ground. Otherwise, the RF current would have to travel through the lossy earth before reaching the radials. In a multiband vertical system, the radials should be 0.2 λ long for the lowest band, that is, 55 feet long for 3.5-MHz operation. Any wire size may be used for the radials. The radials should fan out in a circle, radiating from the base of the antenna. A metal plate, such as a piece of sheet copper, can be used at the center connection.

The other common type of vertical is the ground-plane antenna. Normally, this antenna is mounted above ground with the radials fanning out from the base of the antenna. The vertical portion of the antenna is usually an electrical λ/4, as is each of the radials. In this type of antenna, the system of radials acts somewhat like an RF choke, to prevent RF currents from flowing in the supporting structure, so the number of radials is not as important a factor as it is with a ground- mounted vertical system. From a practical standpoint, the customary number of radials is four or five. In a multiband configuration, λ/4 radials are required for each band of operation with the ground-plane antenna.

This is not so with the ground-mounted vertical antenna, where the ground plane is relied upon to provide an image of the radiating section. Note that even quarter-wave-long radials are greatly detuned by their proximity to ground—radial resonance is not necessary or even possible. In the ground-mounted case, so long as the ground-screen radials are approximately 0.2 λ long at the lowest frequency, the length will be more than adequate for the higher frequency bands.

Short Vertical Antennas

A short vertical antenna can be operated on several bands by loading it at the base, the general arrangement being similar to Figs 1 and 2. That is, for multiband work the vertical can be handled by the same methods that are used for random-length wires.

A vertical antenna should not be longer than about ¾ λ at the highest frequency to be used, however, if low-angle radiation is wanted. If the antenna is to be used on 28 MHz and lower frequencies, therefore, it should not be more than approximately 25 feet high, and the shortest possible ground lead should be used.

Another method of feeding is shown in **Fig 29**. L1 is a loading coil, tapped to resonate the antenna on the desired band. A second tap permits using the coil as a transformer for matching a coax line to the transmitter. C1 is not strictly necessary, but may be helpful on the lower frequencies, 3.5 and 7 MHz, if the antenna is quite short. In that case C1 makes it possible to tune the system to resonance with a coil of reasonable dimensions at L1. C1 may also be useful on other bands as well, if the system cannot be matched to the feed line with a coil alone.

The coil and capacitor should preferably be installed at the base of the antenna, but if this cannot be done a wire can be run from the antenna base to the nearest convenient location for mounting L1 and C1. The extra wire will of course be a part of the antenna, and since it may have to run through unfavorable surroundings it is best to avoid using it if at all possible.

This system is best adjusted with the help of an SWR indicator. Connect the coax line across a few turns of L1 and take trial positions of the shorting tap until the SWR reaches its lowest value. Then vary the line tap similarly; this should bring the SWR down to a low value. Small adjustments of both taps then should reduce the SWR to close to 1:1. If not, try adding C1 and go through the same procedure, varying C1 each time a tap position is changed.



Fig 29—Multiband vertical antenna system using base loading for resonating on 3.5 to 28 MHz. L1 should be wound with bare wire so it can be tapped at every turn, using #12 wire. A convenient size is 2½ inches diameter, 6 turns per inch (such as B&W 3029). Number of turns required depends on antenna and ground lead length, more turns being required as the antenna and ground lead are made shorter. For a 25-foot antenna and a ground lead of the order of 5 feet, L1 should have about 30 turns. The use of C1 is explained in the text. The smallest capacitance that will permit matching the coax cable should be used; a maximum capacitance of 100 to 150 pF will be sufficient in any case.

Trap Verticals

The trap principle described in Fig 17 for center-fed dipoles also can be used for vertical antennas. There are two principal differences. Only one half of the dipole is used, the ground connection taking the place of the missing half, and the feed-point impedance is one half the feed-point impedance of a dipole. Thus it is in the vicinity of 30 Ω (plus the ground-connection resistance), so 52-Ω cable should be used since it is the commonly available type that comes closest to matching.


Left Open (Not Shorted) at Top
RG-8 Cable 30 1/2" Long
2"
2 1/4"
2 Turns 1/8" Copper Tubing-1 Turn Per Inch
27 1/4"
Hose Clamp
7/8" OD Plexiglas Rod
Hose Clamp
94 3/4"
7"
1" PVC Tubing 8" Long
3/4" Plywood
TV-Type U-Bolt
10"
1" Mast
Length Given in Text
Aluminum "L" Bracket
SO – 239

Fig 30—Constructional details of the 21- and 28-MHz dual-band antenna system.

A TRAP VERTICAL FOR 21 AND 28 MHZ

Simple antennas covering the upper HF bands can be quite compact and inexpensive. The two-band vertical ground plane described here is highly effective for long-distance communication when installed in the clear.

Figs 30, **31** and **32** show the important assembly details. The vertical section of the antenna is mounted on a ¾-inch thick piece of plywood board that measures 7 × 10 inches. Several coats of exterior varnish or similar material will help protect the wood from inclement weather. Both the mast and the radiator are mounted on the piece of wood by means of TV U-bolt hardware. The vertical is electrically isolated from the wood with a piece of 1-inch diameter PVC tubing. A piece approximately 8 inches long is required, and it is of the schedule-80 variety. To prepare the tubing, you must slit it along the entire length on one side. A hacksaw will work quite well. The PVC fits rather snugly on the aluminum tubing and



Fig 31—A close-up view of a trap. The coil is 3 inches in diameter. The leads from the coaxial-cable capacitor should be soldered directly to the pigtails of the coil. These connections should be coated with varnish after they have been secured under the hose clamps.


ASTM-D-1785-73

Fig 32—The base assembly of the 21- and 28-MHz vertical. The SO-239 coaxial connector and hood can be seen in the center of the aluminum L bracket. The U bolts are TV-type antenna hardware. The plywood should be coated with varnish or similar material.

will have to be "persuaded" with the aid of a hammer. Mount the mast directly on the wood with no insulation.

Use an SO-239 coaxial connector and four solder lugs on an L-shaped bracket made from a piece of aluminum sheet. Solder a short length of test probe wire, or inner conductor of RG-58 cable, to the inner terminal of the connector. A UG-106 connector hood is then slid over the wire and onto the coaxial connector. Then bolt the hood and connector to the aluminum bracket. Two wood screws are used to secure the aluminum bracket to the plywood, as shown in the drawing and photograph. Solder the free end of the wire coming from the connector to a lug mounted on the bottom of the vertical radiator. Fill any space between the wire and where it passes through the hood with GE silicone sealant or similar material to keep moisture out. The eight radials, four for each band, are soldered to the four lugs on the aluminum bracket. Separate the two sections of the vertical member with a piece of clear acrylic rod. Approximately 8 inches of ⅞-inch OD material is required. You must slit the aluminum tubing lengthwise for several inches so the acrylic rod may be inserted. The two pieces of aluminum tubing are separated by 2¼ inches.

The trap capacitor is made from RG-8 coaxial cable and is 30.5 inches long. RG-8 cable has 29.5 pF of capacitance per foot and RG-58 has 28.5 pF per foot. RG-8 cable is recommended over RG-58 because of its higher breakdown-voltage capability. The braid should be pulled back 2 inches on one end of the cable, and the center conductor soldered to one end of the coil. Solder the braid to the other end of the coil. Compression type hose clamps are placed over the capacitor/coil leads and put in position at the edges of the aluminum tubing. When tightened securely, the clamps serve a two-fold purpose—they keep the trap in contact with the vertical members and prevent the aluminum tubing from slipping off the acrylic rod. The coaxial-cable capacitor runs upward along the top section of the antenna. This is the side of the antenna to which the braid of the capacitor is connected. Place a cork or plastic cap in the very top of the antenna to keep moisture out.

Installation and Operation

The antenna may be mounted in position using a TV-type tripod, chimney, wall or vent mount. Alternatively, a telescoping mast or ordinary steel TV mast may be used, in which case the radials may be used as guys for the structure. The 28-MHz radials are 8 feet 5 inches long, and the 21-MHz radials are 11 feet 7 inches.

Any length of 50-Ω cable may be used to feed the antenna. The SWR at resonance should be on the order of 1.2:1 to 1.5:1 on both bands. The reason the SWR is not 1:1 is that the feed-point resistance is something other than 50 Ω —closer to 35 or 40 Ω.

The Open-Sleeve Antenna

Although only recently adapted for the HF and VHF amateur bands, the open-sleeve antenna has been around since 1946. The antenna was invented by Dr J. T. Bolljahn, of Stanford Research Institute. This section on sleeve antennas was written by Roger A. Cox, WB0DGF.

The basic form of the open-sleeve monopole is shown in **Fig 33**. The open-sleeve monopole consists of a base-fed central monopole with two parallel closely spaced parasitics, one on each side of the central element, and grounded at each base. The lengths of the parasitics are roughly one half that of the central monopole.

Impedance

The operation of the open sleeve can be divided into two modes, an antenna-mode and a transmission-line mode. This is shown in **Fig 34**.

The antenna-mode impedance, Z_A, is determined by the length and diameter of the central monopole. For sleeve lengths less than that of the monopole, this impedance is essentially independent of the sleeve dimensions.

The transmission-line mode impedance, Z_T, is determined by the characteristic impedance, end impedance, and length of the 3- wire transmission line formed by the central monopole and the two sleeve elements. The characteristic impedance, Z_c, can be determined by the element diameters and spacing if all element diameters are equal, and is found from

$$Z_c = 207 \log 1.59 (D/d) \qquad \text{(Eq 2)}$$

where

D = spacing between the center of each sleeve element and the center of the driven element

d = diameter of each element

This is shown graphically in **Fig 35**. However, since the end impedance is usually unknown, there is little need to know the characteristic impedance. The transmission-line mode impedance, Z_T, is usually determined by an educated guess and experimentation.

As an example, let us consider the case where the central monopole is λ/4 at 14 MHz. It would have an antenna mode impedance, Z_A, of approximately 52 Ω, depending upon the ground conductivity and number of radials. If two sleeve elements were added on either side of the central monopole, with each approximately half the height of the monopole and at a distance equal to their height, there would be very little



Fig 33—Diagram of an open-sleeve monopole.



Fig 35—Characteristic impedance of transmission-line mode in an open-sleeve antenna.



Fig 34—Equivalent circuit of an open-sleeve antenna.

effect on the antenna mode impedance, Z_A, at 14 MHz.

Also, Z_T at 14 MHz would be the end impedance transformed through a $\lambda/8$ section of a very high characteristic impedance transmission line. Therefore, Z_T would be on the order of 500-2000 Ω resistive plus a large capacitive reactance component. This high impedance in parallel with 52 Ω would still give a resultant impedance close to 52 Ω.

At a frequency of 28 MHz, however, Z_A is that of an end-fed half-wave antenna, and is on the order of 1000-5000 Ω resistive. Also, Z_T at 28 MHz would be on the order of 1000 to 5000 Ω resistive, since it is the end impedance of the sleeve elements transformed through a quarter-wave section of a very high characteristic impedance 3-wire transmission line. Therefore, the parallel combination of Z_A and Z_T would still be on the order of 500 to 2500 Ω resistive.

If the sleeve elements were brought closer to the central monopole such that the ratio of the spacing to element diameter was less than 10:1, then the characteristic impedance of the 3-wire transmission line would drop to less than 250 Ω. At 28 MHz, Z_A remains essentially unchanged, while Z_T begins to edge closer to 52 Ω as the spacing is reduced. At some particular spacing the characteristic impedance, as determined by the D/d ratio, is just right to transform the end impedance to exactly 52 Ω at some frequency. Also, as the spacing is decreased, the frequency where the impedance is purely resistive gradually increases.

The actual impedance plots of a 14/28-MHz open-sleeve monopole appear in **Figs 36** and **37**. The length of the central monopole is 195.5 inches, and of the sleeve elements 89.5 inches. The element diameters range from 1.25 inches at the bases to 0.875 inch at each tip. The measured impedance of the 14-MHz monopole alone, curve A of Fig 36, is quite high. This is probably because of a very poor ground plane under the antenna. The addition of the sleeve elements raises this impedance slightly, curves B, C and D.

As curves A and B in Fig 37 show, an 8-inch sleeve spacing gives a resonance near 27.8 MHz at 70 Ω, while a 6-inch spacing gives a resonance near 28.5 MHz at 42 Ω. Closer spacings give lower impedances and higher resonances. The optimum spacing for this particular antenna would be somewhere between 6 and 8 inches. Once the spacing is found, the lengths of the sleeve elements can be tweaked slightly for a choice of resonant frequency.

In other frequency combinations such as 10/21, 10/24, 14/21 and 14/24-MHz, spacings in the 6 to 10-inch range work very well with element diameters in the 0.5 to 1.25-inch range.



Fig 36—Impedance of an open-sleeve monopole for the frequency range 13.5-15 MHz. Curve A is for a 14 MHz monopole alone. For curves B, C and D, the respective spacings from the central monopole to the sleeve elements are 8, 6 and 4 inches. See text for other dimensions.



Fig 37—Impedance of the open-sleeve monopole for the range 25-30 MHz. For curves A, B and C the spacings from the central monopole to the sleeve elements are 8, 6 and 4 inches, respectively.

Bandwidth

The open-sleeve antenna, when used as a multiband antenna, does not exhibit broad SWR bandwidths unless, of course, the two bands are very close together. For example, **Fig 38** shows the return loss and SWR of a single 10-MHz vertical antenna. Its 2:1 SWR bandwidth is 1.5 MHz, from 9.8 to 11.3 MHz. Return loss and SWR are related as given by the following equation.

$$\mathrm{SWR} = \frac{1+k}{1-k} \qquad \text{(Eq 3)}$$

where

$$k = 10^{\frac{R_L}{20}}$$

RL = return loss, dB

When sleeve elements are added for a resonance near 22 MHz, the 2:1 SWR bandwidth at 10 MHz is still nearly 1.5 MHz, as shown in **Fig 39**. The total amount of spectrum under 2:1 SWR increases, of course, because of the additional band, but the individual bandwidths of each resonance are virtually unaffected.

The open-sleeve antenna, however, can be used as a broadband structure, if the resonances are close enough to overlap. With the proper choices of resonant frequencies, sleeve and driven element diameters and sleeve spacing, the SWR "hump" between resonances can be reduced to a value less than 3:1. This is shown in **Fig 40**.

Current Distribution

According to H. B. Barkley (see Bibliography at the end of this chapter), the total current flowing into the base of the open-sleeve antenna may be broken down into two components, that contributed by the antenna mode, I_A, and that contributed by the transmission-line mode, I_T. Assuming that the sleeves are approximately half the height of the central monopole, the impedance of the antenna mode, Z_A, is very low at the resonant frequency of the central monopole, and



Fig 38—Return loss and SWR of a 10 MHz vertical antenna. A return loss of 0 dB represents an SWR of infinity. The text contains an equation for converting return loss to an SWR value.



Fig 39—Return loss and SWR of a 10/22 MHz open-sleeve vertical antenna.



Fig 40—SWR response of an open-sleeve dipole and a conventional dipole.



Fig 41—Current distribution in the transmission-line mode. The amplitude of the current induced in each sleeve element equals that of the current in the central element but the phases are opposite, as shown.



Fig 42—Total current distribution with $\lambda = L/2$.

the impedance of the transmission-line mode, Z_T, is very high. This allows almost all of the current to flow in the antenna mode, and I_A is very much greater than I_T. Therefore, the current on the central $\lambda/4$ monopole assumes the standard sinusoidal variation, and the radiation and gain characteristics are much like those of a normal $\lambda/4$ vertical antenna.

However, at the resonant frequency of the sleeves, the impedance of the central monopole is that of an end fed half-wave monopole and is very high. Therefore I_A is small. If proper element diameters and spacings have been used to match the transmission line mode impedance, Z_T, to 52 Ω, then I_T, the transmission line mode current, is high compared to I_A.

This means that very little current flows in the central monopole above the tops of the sleeve elements, and the radiation is mostly from the transmission-line mode current, I_T, in all three elements below the tops of the sleeve elements. The resulting current distribution is shown in **Figs 41** and **42** for this case.

Radiation Pattern and Gain

The current distribution of the open-sleeve antenna where all three elements are nearly equal in length is nearly that of a single monopole antenna. If, at a particular frequency, the elements are approximately $\lambda/4$ long, the current distribution is sinusoidal.

If, for this and other length ratios, the chosen diameters and spacings are such that the two sleeve elements approach an interelement spacing of $\lambda/8$, the azimuthal pattern will show directivity typical of two in-phase vertical radiators, approximately $\lambda/8$ apart. If a bi-directional pattern is needed, then this is one way to achieve it.

Spacings closer than this will produce nearly circular azimuthal radiation patterns. Practical designs in the 10 to 30 MHz range using 0.5 to 1.5-inch diameter elements will produce azimuthal patterns that vary less than ±1 dB.

If the ratio of the length of the central monopole to the length of the sleeves approaches 2:1, then the elevation pattern of the open-sleeve vertical antenna at the resonant frequency of the sleeves becomes slightly compressed. This is because of the in-phase contribution of radiation from the $\lambda/2$ central monopole.

As shown in **Fig 43**, the 10/21-Mhz open-sleeve vertical antenna produces a lower angle of radiation at 21.2 MHz with a corresponding increase in gain of 0.66 dB over that of the 10-MHz vertical alone. At length ratios approaching 3:1, the



Fig 43—Vertical-plane radiation patterns of a 10/21-MHz open-sleeve vertical antenna on a perfect ground plane. At 10.1 MHz the maximum gain is 5.09 dBi, and 5.75 dBi at 21.2 MHz.

antenna mode and transmission-line mode impedance become nearly equal again, and the central monopole again carries a significant portion of the antenna current. The radiation from the top λ/2 combines constructively with the radiation from the λ/4 sleeve elements to produce gains of up to 3 dB more than just a quarter-wave vertical element alone.

Length ratios in excess of 3.2:1 produce higher level sidelobes and less gain on the horizon, except for narrow spots near the even ratios of 4:1, 6:1, 8:1, etc. These are where the central monopole is an even multiple of a half-wave, and the antenna-mode impedance is too high to allow much antenna-mode current.

Up to this point, it has been assumed that only λ/4 resonance could be used on the sleeve elements. The third, fifth, and seventh-order resonances of the sleeve elements and the central monopole element can be used, but their radiation patterns normally consist of high-elevation lobes, and the gain on the horizon is less than that of a λ/4 vertical.

Practical Construction and Evaluation

The open-sleeve antenna lends itself very easily to home construction. For the open-sleeve vertical antenna, only a feed-point insulator and a good supply of aluminum tubing are needed. No special traps or matching networks are required. The open-sleeve vertical can produce up to 3 dB more gain than a conventional λ/4 vertical. Further, there is no reduction in bandwidth, because there are no loading coils.

The open-sleeve design can also be adapted to horizontal dipole and beam antennas for HF, VHF and UHF. A good example of this is Telex/Hy-Gain's Explorer 14 triband beam which utilizes an open sleeve for the 10/15-meter driven element. The open-sleeve antenna is also very easy to model in computer programs such as *NEC* and *MININEC*, because of the open tubular construction and lack of traps or other intricate structures.

In conclusion, the open-sleeve antenna is an antenna experimenters delight. It is not difficult to match or construct, and it makes an ideal broadband or multiband antenna.

The Coupled-Resonator Dipole

A variation of the open-sleeve system above is the coupled-resonator system described by Gary Breed, K9AY, in an article in *The ARRL Antenna Compendium, Vol 5*, entitled “The Coupled-Resonator Principle: A Flexible Method for Multiband Antennas.” The following is condensed from that article.

In 1995, *QST* published two antenna designs that use an interesting technique to get multiband coverage in one antenna. Rudy Severns, N6LF, described a wideband 80 and 75-meter dipole using this technique, and Robert Wilson, AL7KK, showed us how to make a three-band vertical. Both of these antennas achieve multi-frequency operation by placing resonant conductors very close to a driven dipole or vertical—with no physical connection.

The Coupled-Resonator Principle

As we all know, nearby conductors can interact with an antenna. Our dipoles, verticals and beams can be affected by nearby power lines, rain gutters, guy wires and other metallic materials. The antennas designed by Severns and Wilson use this interaction intentionally, to combine the resonances of several conductors at a single feed point. While other names have been used, I call the behavior that makes these antennas work the *coupled-resonator* (C-R) principle.

Take a look at **Fig 44**, which illustrates the general idea. Each figure shows the SWR at the feed point of a dipole, over a range of frequencies. When this dipole is all alone, it will have a very low SWR at its half-wave resonant frequency (Fig 44A). Next, if we take another wire or tubing conductor and start bringing it close to the dipole, we will see a “bump” in the dipole’s SWR at the resonant frequency of this new wire. See Fig 44B. We are beginning to the see the effects of interaction between the two conductors. As we bring this new conductor closer, we reach a point where the SWR “bump” has grown to a very deep dip—a low SWR. We now have a good match at both the original dipole’s resonant frequency and the frequency of the new conductor, as illustrated in Fig 44C.

We can repeat this process for several more conductors at other frequencies to get a dipole with three, four, five, six, or more resonant frequencies. The principle also applies to verticals, so any reference to a dipole can be considered to be valid for a vertical, as well.

We can write a definition of the C-R principle this



Fig 44—At A, the SWR of a dipole over a wide frequency range. At B, a nearby conductor is just close enough to interact with the dipole. At C, when the second conductor is at the optimum spacing, the combination is matched at both frequencies.

way: *Given a dipole (or vertical) at one frequency and an additional conductor resonant at another frequency, there is an optimum distance between them that results in the resonance of the additional conductor being imposed upon the original dipole, resulting in a low SWR at both resonant frequencies.*

Some History

In the late 1940s, the *coaxial sleeve* antenna was developed (**Fig 45A**), covering two frequencies by surrounding a dipole or monopole with a cylindrical tube resonant at the higher of the desired frequencies. In the 1950s, Gonset briefly marketed a two-band antenna based on this design. Other experimenters soon determined that two conductors at the second frequency, placed on either side of the main dipole or monopole, would make a skeleton representation of a cylinder (Fig 45B). This is called the *open-sleeve* antenna. The Hy-Gain Explorer tribander uses this method in its driven element to obtain resonance in the 10-meter band. Later on, a few antenna developers finally figured out that these extra conductors did not need to be added in pairs, and that a single conductor at each frequency could add the extra resonances (Fig 45C). This is the method used by Force 12 in some of their multiband antennas.


Coaxial Sleeve
Main Dipole
(A)
Feed-Point Access Through Hole in Sleeve
Main Dipole
Feed Point
(B)
Two Outer Conductors Make an "Open Sleeve"
Main Dipole
Feed Point
(C)
Single Additional Conductor Adds New Frequency

Fig 45—Evolution of coupled-resonator antennas: At A, the *coaxial-sleeve* dipole; at B, the *open-sleeve* dipole; and at C, a *coupled-resonator* dipole, the most universal configuration.

This is a perfect example of how science works. A specific idea is discovered, with later developments leading to an underlying general principle. The original coaxial-sleeve configuration is the most specific, being limited to two frequencies and requiring a particular construction method. The open-sleeve antenna is an intermediate step, showing that the sleeve idea is not limited to one configuration.

Finally, we have the coupled-resonator concept, which is the general principle, applicable in many different antenna configurations, for many different frequency combinations. Severns' antenna uses it with a folded dipole, and Wilson uses it with a main vertical that is off-center fed. The author K9AY used it with conventional dipoles and quarter-wave verticals. Other designers have used the principle more subtly, like putting the first director in a Yagi very close to the driven element, broadening the SWR bandwidth the same way Severns' design does with a dipole.

In the past, most antennas built with this single-conductor technique have also been called *open-sleeve* (or *multiple-open-sleeve*) antennas, a term taken from the history of their development. However, the term *sleeve* implies that one conductor must surround another. This is not really a physical or electrical description of the antenna's operation, therefore, K9AY suggests using the term *coupled-resonator,* which is the most accurate description of the general principle.

A Little Math

The interaction that makes the C-R principle work is not random. It behaves in a predictable, regular manner. K9AY derived an equation that shows the relationship between the driven element and the additional resonators for ordinary dipoles and verticals:

$$\frac{\log_{10} d}{\log_{10}(D/4)} = 0.54 \qquad \text{(Eq 4)}$$

where

d = distance between conductors, measured in wavelengths at the frequency of the chosen additional resonator

D = the diameter of the conductors, also in wavelengths at the frequency of the additional resonator.

Eq 4 assumes they are both the same diameter and that the feed point impedance at both frequencies is the same as a dipole in free space (72 Ω) or a quarter-wave monopole over perfect ground (36 Ω).

The equation only describes the impedance due to the additional resonator. The main dipole element is always part of the antenna, and it may have a fairly low impedance at the additional frequency. This is the case when the frequencies are close together, or when the main element is operating at its third harmonic. At these frequencies, the spacing distance must be adjusted so that the parallel combination of dipole and resonator results in the desired feed-point impedance.

K9AY worked out two correction factors, one to cover a range of impedances and another for frequencies close together. These can be included in the basic equation, which is rearranged below to solve for the distance between the conductors:

$$d = 10^{0.54\log_{10}(D/4)} \times \frac{Z_0 + 35.5}{109} \times [1 + e^{-[((F_2/F_1)-1.1)\times 11.3)+0.1)]}] \qquad \text{(Eq 5)}$$

where

d and D are the same as above.

Z_0 = the desired feed point impedance at the frequency of the additional resonator (between 20 and 120 Ω). For a vertical, multiply the desired impedance by two to get Z_0. If you want a 50-Ω feed, use 100 Ω for Z_0.

F_1 = the resonant frequency of the main dipole or vertical.

F_2 = the resonant frequency of the additional conductor. The ratio F_2/F_1 is more than 1.1.

e = 2.7183, the base of natural logarithms.

Eq 5 does not directly allow for conductors of unequal diameters, but it can be used as a starting point if you use the diameter of the driven dipole or vertical element for D in the equation.

Characteristics of C-R Antennas

Here's the important stuff—what's different about C-R antennas, what are they good for and what are their drawbacks? The key points are:

- Multiband operation without traps, stubs or tuners



Fig A—Graph of the spacing versus frequency ratio for two Coupled-Resonator elements at 28.4 MHz, for 50-Ω feed-point impedance.

K9AY's Eq 5 above does indeed yield a good "first-cut" value for the spacing between coupled-resonator elements. **Fig A** shows the spacing, in inches, plotted against the ratio of frequencies, for two coupled resonator elements with different diameters, again expressed in inches. This is for an upper frequency of 28.4 MHz. Beyond a frequency ratio of about 1.5:1 (28.4:18.1 MHz), the spacing flattens out to a fixed distance between elements for each element diameter. For example, if $^{1}/_{2}$-inch elements are used at 28.4 and 18.1 MHz, the spacing between the elements is about 3.75 inches.

EZNEC verifies Eq 5's computations. Note that a large number of segments are necessary for each element when they are closely spaced from each other, and the segments on the elements must be closely aligned with each other. Be sure to run the Average Gain test, as well as Segmentation tests. The modeler should also be aware that if mutually coupled resonators are placed along a horizontal boom (as they would be on multiband Yagis using coupled resonators), the higher-frequency elements will act like retrograde directors, producing some gain (or lack of gain, depending on the azimuth being investigated).

For example, in the *EZNEC* file **K9AY C-R 28-21-14 MHz 1 In.EZ**, using 1-inch diameter elements spaced 6 inches apart, if the 28-MHz element is placed 6 inches behind the 14-MHz driven element (with the 21-MHz element placed 6 inches ahead), on 28 MHz the system will have a F/B of 2.6 dB, favoring the rearward direction. On 21 MHz, the system will exhibit a F/B of 1.6 dB, favoring the forward direction. Of course, there are systems where gain and F/B due to the C-R configuration may be put to good use, such as the multiband Yagis mentioned above. However, if the elements are spaced above/below the 14-MHz driven element there is no distortion of the dipole patterns.

- Flexible impedance matching at each frequency
- Independent fine-tuning at each frequency (little interaction)
- Easily modeled using *MININEC* or *NEC*-based programs
- Pruning process same as a simple dipole
- Can accommodate many frequencies (seven or more)
- Virtually lossless coupling (high efficiency)
- Requires a separate wire or tubing conductor at each frequency
- Mechanical assembly requires a number of insulated supports
- Narrower bandwidth than equivalent dipole
- Capacitance requires slight lengthening of conductors

To begin with, the most obvious characteristic is that this principle can be used to add multiple resonant frequencies to an ordinary dipole or vertical, using additional conductors that are not physically connected. This gives us three variable factors: (1) the diameter of the conductor, (2) its length, and (3) its position relative to the main element.

Having the freedom to control these factors gives us the advantage of *flexibility*; we have a wide range of control over the impedance at each added frequency. Another advantage is that the behavior at each frequency is quite *independent*, once the basic design is in place. In other words, making fine-tuning adjustments at one frequency doesn't change the resonance or impedance at the other frequencies. A final advantage is *efficiency.* With conductors close together, and with a resonant target conductor, coupling is very efficient. Traps, stubs, and compensating networks found on other multiband antennas all introduce lossy reactive components.

There are two main disadvantages of C-R antennas. The first is the relative *complexity* of construction. Several conductors are needed, installed with some type of insulating spacers. Other multiband antennas have their complexities as well (such as traps that need to be mounted and tuned), but C-R antennas will usually be bulkier. The larger size generally means greater windload, which is a disadvantage to some hams.

The other significant disadvantage is *narrower bandwidth,* particularly at the highest of the operating frequencies. We can partially overcome this problem with large conductors that are naturally broad in bandwidth, and in some cases we might even use an extra conductor to put two resonances in one band. It is interesting to note that the pattern is opposite that of trapped antennas. The C-R antenna gets narrower at the highest frequencies of operation, while trap antennas generally have narrowest bandwidth at their lowest frequencies.

There are two special situations that should be noted. First, when the antenna has a resonance near the frequency where the driven dipole is 3/2 λ long (3/4 λ for a vertical), the dipole has a fairly low impedance. The spacing of the C-R element needs to be increased to raise its impedance so that the parallel combination of the main element and C-R element equals the desired impedance (usually 50 Ω). There is also significant antenna current in the part of the main dipole extending beyond the C-R section, contributing to the total radiation pattern. As a result, this particular arrangement radiates as three λ/2 sections in phase, and has about 3 dB gain and a narrower directional pattern compared to a dipole (**Fig 46**). This might be an advantage for antennas covering bands with a frequency ratio of about three, such as 3.5 and 10.1 MHz, 7 and 21 MHz, or 144 and 430 MHz.

The other special situation is when we want to add a new frequency very close to the resonant frequency of the main dipole. An antenna for 80 and 75 meters would be an example of this. Again, the driven dipole has a fairly low impedance at the new frequency. Add the fact that coupling is very strong between these similar conductors and we find that a wide spacing is required to make the antenna work. A dipole resonant at 3.5 MHz and another wire resonant at 3.8 MHz will need to be 3 or 4 feet apart, while a 3.5 MHz and 7 MHz combination might only need to be spaced 4 or 5 inches.

Another useful characteristic of C-R antennas is that they are easily and accurately modeled by computer programs based on either *MININEC* or *NEC*, as long as you stay within each program's limitations. For example, Severns points out that *MININEC* does not handle folded dipoles very well, and *NEC* modeling is required. With ease of computer modeling, a precise answer isn't needed for the design equation given above. An approximate solution will provide a starting point that can quickly be adjusted for optimum dimensions.

The added resonators have an effect on the lengths of all conductors, due to the capacitance between the conductors. Capacitance causes antennas to look electrically shorter, so



Fig 46—Radiation pattern for the special case of a C-R antenna with the additional frequency at the third harmonic of the main dipole resonant frequency.

each element needs to be about 1% or 2% longer than a simple dipole at the same frequency. As a rule of thumb, use 477/f (in feet) instead of the usual 468/f when calculating dipole length, and 239/f instead of 234/f for a λ/4 vertical.

A 30/17/12-Meter Dipole

To show how a C-R antenna is designed, let's build a dipole to cover all three WARC bands. We'll use #12 wire, which has a diameter of 0.08 inches, and the main dipole will be cut for the 10.1 MHz band. From the equation above, the spacing between the main dipole and the 18-MHz resonator should be 2.4 inches for 72 Ω, or 1.875 inches for 50 Ω. At 24.9 MHz, the spacing to the resonator for that band should be 2.0 inches for 72 Ω, or 1.62 inches for 50 Ω. Of course, this antenna will be installed over real ground, not in free space, so these spacing distances may not be exact. Plugging these numbers into your favorite antenna-modeling program will let you optimize the dimensions for installation at the height you choose.

For those of you who like to work with real antennas, not computer-generated ones, the predicted spacing is accurate enough to build an antenna with minimum trial-and-error. You should use a nice round number just larger than the calculated spacing for 50 Ω. For this antenna, K9AY decided that the right spacing for the desired height would be 2 inches for the 18 MHz resonator and 1.8 inches for the 24.9 MHz resonator. For simplicity of construction, he just used 2 inches for both, figuring that the worst he would get is a 1.2:1 SWR if the numbers were a little bit off. Like all dipoles, the impedance varies with height above ground, but the 2-inch spacing results in an excellent match on the two additional bands, at heights of more than 25 feet.



Fig 47—Dimensions of a C-R dipole for the 30, 17 and 12-meter bands.

The final dimensions of the dipole for 10.1, 18.068 and 24.89 MHz are shown in **Fig 47**. These are the final pruned lengths for a straight dipole installed at a height of about 40 feet. If you put up the antenna as an inverted V, you will need each wire to be a bit longer. Pruning this type of antenna is just like a dipole—if it's resonant too low in frequency, it's too long and the appropriate wire needs to be shortened. So, you can cut the wires just a little long to start with and easily prune them to resonance.

A final note: if you want to duplicate this antenna design, remember that the 2-inch spacing is just for #12 wire! The required spacing for a C-R antenna is related to the conductor diameter. This same antenna built with #14 wire needs under 1½-inch spacing, while a 1-inch aluminum-tubing version requires about 7-inch spacing.

Summary

The coupled-resonator principle is one more weapon in the antenna designer's arsenal. It's not the perfect method for all multiband antennas, but what the C-R principle offers is an alternative to traps and tuners, in exchange for using more wire or aluminum. Although a C-R antenna requires more complicated construction, its main attraction is in making a multiband antenna that can be built with no compromise in matching or efficiency.

HF Discone Antennas

The material in this section is adapted from an article by Daniel A. Krupp, W8NWF, in *The ARRL Antenna Compendium, Vol 5*. The name *discone* is a contraction of the words disc and cone. Although people often describe a discone by its design-center frequency (for example, a "20-meter discone"), it works very well over a wide frequency range, as much as several octaves. **Fig 48** shows a typical discone, constructed of sheet metal for UHF use. On lower frequencies, the sheet metal may be replaced with closely spaced wires and/or aluminum tubing.

The dimensions of a discone are determined by the lowest frequency of use. The antenna produces a vertically polarized signal at a low-elevation angle and it presents a good match for 50-Ω coax over its operating range. One advantage of the discone is that its maximum current area is near the top of the antenna, where it can radiate away from ground clutter. The cone-like skirt of the discone radiates the signal—radiation from the disc on top is minimal. This is because the currents flowing in the skirt wires essentially all go in the same direction, while the currents in the disc elements oppose each other and cancel out. The discone's omnidirectional characteristics make it ideal for roundtable QSOs or for a Net Control station.

Electrical operation of this antenna is very stable, with no changes due to rain or accumulated ice. It is a self-contained antenna—unlike a traditional ground-mounted vertical radiator, the discone does not rely on a ground-radial system for efficient operation. However, just like any other vertical



Fig 48—Diagram of VHF/UHF discone, using a sheet-metal disc and cone. It is fed directly with 50-Ω coax line. The dimensions L and D, together with the spacing S between the disc and cone, determine the frequency characteristics of the antenna. $L = 246 / f_{MHz}$ for the lowest frequency to be used. Diameter D should be from 0.67 to 0.70 of dimension L. The diameter at the bottom of the cone B is equal to L. The space S between disc and cone can be 2 to 12 inches, with the wider spacing appropriate for larger antennas.

antenna, the quality of the ground in the Fresnel area will affect the discone's far-field pattern.

Both the disc and cone are inherently balanced for wind loading, so torque caused by the wind is minimal. The entire cone and metal mast or tower can be connected directly to ground for lightning protection.

Unlike a trap vertical or a triband beam, discone antennas are not adjusted to resonate at a particular frequency in a ham band or a group of ham bands. Instead, a discone functions as a sort of high-pass filter, efficiently radiating RF all the way from the low-frequency design cutoff to the high-frequency limits imposed by the physical design.

While VHF discones have been available out-of-the-box for many years, HF discones are rare indeed. Some articles have dealt with HF discones, where the number of disc elements and cone wires was minimized to cut costs or to simplify construction. While the minimalist approach is fine if the sought-after results really are obtained, W8NWF believes in building his discones without compromise.

History of the Discone

The July 1949 and July 1950 issues of *CQ* magazine both contained excellent articles on discones. The first article, by Joseph M. Boyer, W6UYH, said that the discone was developed and used by the military during World War II. (See Bibliography.) The exact configuration of the top disc and cone was the brainchild of Armig G. Kandonian. Boyer described three VHF models, plus information on how to build them, radiation patterns, and most importantly, a detailed description of how they work. He referred to the discone as a type of "coaxial taper transformer."

The July 1950 article was by Mack Seybold, W2RYI. He described an 11-MHz version he built on his garage roof. The mast actually fit through the roof to allow lowering the antenna for service. Seybold stated that his 11-MHz discone would load up on 2 meters but that performance was down 10 dB compared to his 100-MHz Birdcage discone. He commented that this was caused by the relatively large spacing between the disc and cone. Actually, the performance degradation he found was caused by the wave angle lifting upward at high frequencies. The cone wires were electrically long, causing them to act like long wire antennas. See **Fig 49**.

W8NWF's First Discone: the A-Frame Discone

The first discone was one designed to cover 20 through 10 meters without requiring an antenna tuner. The cone assembly uses 18-foot long wires, with a 60° included apex angle and a 12-foot diameter disc assembly. See **Fig 50** and **Fig 51**. The whole thing was assembled on the ground, with the feed coax and all guys attached. Then with the aid of some friends, it was pulled up into position.

The author used a 40-foot tall wooden "A-frame" mast, made of three 22-foot-long 2 × 4s. He primed the mast with sealer and then gave it two coats of red barn paint to make it look nice and last a long time. The disc hub was a 12-inch length of 3-inch schedule-40 PVC plumbing pipe. The PVC is very tough, slightly ductile, and easy to drill and cut. PVC is well suited for RF power at the feed point of the antenna.

Three 12-foot by 0.375-inch OD pieces of 6061 aluminum, with 0.058-inch wall thickness, were used for the 12-foot diameter top disc. These were cut in half to make the center portions of the six telescoping spreaders. Four twelve foot by 0.250-inch OD (0.035-inch wall thickness) tubes were cut into 12 pieces, each 40 inches long. This gave extension tips for each end of the six spreaders.

See **Fig 52** for details on the disc hub assembly. W8NWF started by drilling six holes straight through the PVC for the six spreaders, accurately and squarely, starting



Fig49—Computed elevation plot over average ground for W8NWF's small discone at 146 MHz, ten times its design frequency range. The cone wires are acting as long-wire antennas, distorting severely the low-elevation angle response, even though the feed-point impedance is close to 50 Ω.



Fig 50—Photo of W8NWF's original A-frame mounted HF discone.

about two inches down from the top and spaced radially every 30°. Each hole is 0.375 inches below the plane of the previous one. Take great care in drilling—a poor job now will look bad from the ground up for a long time! It's a good idea to make up a paper template beforehand. Tape this to the PVC hub and then drill the holes, which should make for a close fit with the elements. If you goof, start over with a new piece of PVC—it's cheap.

Each six-foot spreader tube was secured exactly in the center to clear a 6-32 threaded brass rod that secured the elements mechanically and electrically. A two-foot long by ¼-inch OD wooden dowel was inserted into the middle of each six-foot length of tubing. The dowel added strength and also prevented crushing the element when the nuts on the threaded rod were tightened.

Insert the 40-inch long extensions four inches into each end of the six-foot spreaders. Mark and drill holes to pin the telescoping tips, plus holes big enough to clear #18 soft-drawn copper wire. This was for the inner circumferential wire for the disc. Drill a single hole for #18 wire about ¼ inch from each extension element tip, through which passes the outer circumferential wire. Finally, insert all 6-foot elements into the PVC hub and line up the holes in the center so the brass rod could be inserted through the middle to secure the elements.


12′ dia. disc — 12 aluminum spreaders connected tip to tip with 18 ga. wire
45 cone wires 18′ long 60° apex angle
Aluminum strap 1″x 1/8″x 55′ 6-1/2″ See text
Six nylon or black Dacron cone guy lines
All stakes 23′ 1-1/2″ from center of mast
40′ mast made of wooden 2x4 s
Mast guy wires 2 sets of 3 with egg insulators

Fig 51—Detailed drawing of the A-frame discone for 14 to 30 MHz. The disc assembly at the top of the A-frame is 12 feet in diameter. There are 45 cone wires, each 18 feet long, making a 60° included angle of the cone. This antenna works very well over the design frequency range.

The next step is to "chisel to fit" the top of my wooden mast to allow the PVC to slide down on it about six or seven inches. For convenience, place the whole mast assembly in a horizontal position on top of two clothesline poles and one stepladder.

Place the disc head assembly over the top of the mast, but don't secure it yet. This allows for rotation while adding the disc spreader extensions. A tip for safety: tie white pieces of cloth to the ends of elements near eye level. Just remember to remove them before raising the antenna.

For a long-lasting installation, use an anti-corrosion compound, such as Penetrox, when assembling the aluminum antenna elements. As the extensions are added, secure them in the innermost of the two holes with a short piece of #18 wire. Then run a wire through the remaining holes looping each element as you go. This gives added support laterally to the elements. Next add a #18 wire to the tips of the extensions in the same fashion. This provides even more


PVC Rain Cap
Brass Nuts, Washers, and Threaded Rod
3/8" OD aluminum disc through the PVC pipe. 2' long wooden dowel inside each one.
Center Lead of Coax
PVC pipe, 3"ID, 12" long
Shielded Braid of Coax
Brass hardware
Loop of 12 ga. stranded wire for connecting cone wires
Cone wires
Top end of 2x4 of 40' wooden mast. Snug fit inside PVC, corners trimmed to fit
50–Ω coax feed line

Fig 52—Details of the top hub for the A-frame discone. The three-inch PVC pipe was drilled to hold the six spreaders making up the top disc. Connections for the shield of the feed coax were made to the disc. The coax center conductor was connected to the cone-wire assembly by means of a loop of #12 stranded wire encircling the outside of the PVC hub.

physical stability as well as making electrical connections.

Next, pin the PVC disk hub to the wooden mast with a ⅜-inch threaded rod. This is also the point where the cone wires are attached, using a loop of #12 stranded copper wire around the PVC. Solder each cone wire to this loop, together with the coax shield braid. Make sure the loop of #12 wire is large enough to make soldering possible without burning the PVC with the soldering iron.

Connect the coax center conductor to the disc assembly by securing it with the same 6-32 threaded rod that ties all the disc elements together. Make sure to use coax-seal compound to keep moisture out of the coax. The coax is then fed down the mast and secured in a few places to provide strain relief and to keep it out of the way of the cone wires.

Use two sets of three guy wires. Break these up with egg insulators, just to be sure there won't be any interaction with the antenna. Use 45 wires of #18 soft-drawn copper wire for the cone, 18 feet long each. Cut them a little long so they can be soldered to the connecting loop.

A difficult task is now at hand—keeping all the cone wires from getting tangled! Solder each of the 45 cone wires to the loop of #12 wire, spacing each wire about ¼ inch from the last one for an even distribution all the way around.

The cone base is 18 feet in diameter to provide a 60° included angle. At the base of the cone, use five 12-foot long aluminum straps, 1 inche wide by ⅛ inch thick, overlapping 8¼ inches and fastened together with aluminum rivets. Drill holes along the strap every 15 inches to secure the cone wires.

Make sure to handle the aluminum strap carefully while fastening the cone wire ends; too sharp of a bend could possibly break it. Fasten six small-diameter nylon lines to the cone-base aluminum strap to stabilize the cone. These cone-guys share the same guy stakes as the mast guy lines.

After cutting the nylon lines, heat the frayed ends of each with a small flame to prevent unraveling. Apply several coats of clear protective spray to the disk head assembly, after checking that all hardware is tight. A rain cap at the top of the PVC disc hub completes construction.

Putting It All Up

You are going to need a lot of help now to raise this antenna. Have the whole process fully thought out before trying to raise it. You should have the spot selected for the base of the mast and some pipes driven into the ground to prevent the mast from slipping sideways as it is being pulled up. The three guy stakes should be in place, 23 feet, 1½ inches from mast center. Of course, the guys should have been cut to the correct length, with some extra. Be sure the coax transmission line will come off the mast where it should. A long length of rope to an upper and lower guy line is used to pull up the whole works.

The author used an old trick of standing an extension ladder vertically near the antenna base with the pull lines looped over the top rung to get a good lift angle. The weight added to the mast from the antenna disc assembly and cone wires is about 26 pounds, most of it from the cone assembly. Use two strong people to pull up the antenna slowly so that the other helpers on the guy wires and cone guy lines have time to move about as required. As the antenna rises to the vertical position, if there are no snafus, the guy lines can be secured. Then tie the six cone lines to stakes.

A Really Big Discone

When an opportunity arose to buy a 64-foot self-supporting TV tower, the author jumped at the chance to implement a full 7 to 30-MHz discone. His new tower had eight sections, each eight feet long. Counting the overlap between sections, the cone wires would come off the tower at about the 61.5-foot mark.

W8NWF took some liberties with the design of this larger discone compared to the first one, which he had done strictly "by the book." The first change was to make the cone wires 70 feet long, even though the formula said they should be 38 feet long. Further, the cone wires would not be connected together at the bottom. With the longer cone wires, he felt that 75 and 80-meter operation might be a possibility.

The second major change was to widen the apex angle out from 60° to about 78°. Modeling said this should produce a flatter SWR over the frequency spectrum and would also give a better guy system for the tower.

The topside disc assembly would be 27 feet in diameter and have 16 radial spreaders, using telescoping aluminum tubing tapering from ⅝ to ½ to ⅜ inches OD. All spreaders were made from 0.058-inch wall thickness 6063-T832 aluminum tubing, available from Texas Towers. A section of 10-inch PVC plumbing pipe would be used as the hub for construction of the disc assembly.

Construction Details for the Large Discone.

While installing the tower, the author had left the top section on the ground. This allowed him to fit the disc head assembly precisely to it. **Fig 53** shows the overall plan for the large discone. The 10-inch diameter PVC hub was designed to slip over the tower top section, but was a little too large. So a set of shims was installed on the three legs at the top of the tower for a just-right fit. Drilling the PVC pipe for the eight ⅝-inch OD elements was started about an inch down from the top. W8NWF purposely staggered the drilled holes in the same fashion as the hub for the smaller antenna. See **Fig 54**.

Again, three-foot sections of ½-inch wooden dowel were used to strengthen the ⅝-inch center portion of each spreader. Instead of using a loop of #12 wire for connecting the cone wires, as had been done on the smaller discone, he drilled 36 holes in the PVC hub. These holes are small enough so



Fig 53—The large W8NWF discone, designed for operation from 7 to 14 MHz, but useable with a tuning network in the shack for 3.8 MHz.



Fig 54—Photo showing details of the hub assembly for the large discone, including the threaded brass rod that connects the radial spreaders together. The 10-inch PVC pipe is drilled to accommodate the radial spreaders. Each spreader is reinforced with a three-foot long wooden dowel inside for crush resistance. Note the row of holes drilled below the lowest spreader. Each of the 36 cone wire passes through one of these holes.



Fig 55—Details of the copper pipe slipped over the feed coax. The coax shield has been folded back over the copper pipe and secured with two stainless-steel hose clamps. The cone wires are also laid against the copper pipe and secured with additional hose clamps.

that the PVC hub would not be weakened appreciably. He drilled the circles of holes for the cone wires about 6 inches below the disc spreaders.

He prepared a three-foot long piece of RG-213 coax, permanently fastened on one end to the antenna, with a female type-N connector at the other end. Type-N fittings were used because of their superior waterproofing abilities. The coax center lead was connected with a terminal lug under a nut on the brass threaded rod securing the disc spreaders. The coax shield braid was folded back over a six-inch long copper pipe and clamped to it with a stainless-steel hose clamp. See **Fig 55** for details.

The plan was that after the top disc assembly had been hoisted up and attached at the top of the tower, individual cone wires would be fed, one at a time, through the small holes drilled in the PVC. They were to be laid against the copper pipe and secured with stainless-steel hose clamps.

The ½ and ⅜-inch OD spreader extension tips were secured in place with two aluminum pop-rivets at each joint. Again, the author used anti-oxidant compound on all spreader junctions. He drilled a hole horizontally near the tip of each ⅜-inch tip all around the perimeter to allow a #8 aluminum wire to circle the entire disc. A small stainless-steel sheet-metal screw was threaded into the end of each element to secure the wire.

In parallel with the aluminum wire, a length of small-diameter black Dacron line was run, securing it in a couple of places between each set of spreaders with UV-resistant plastic tie-wraps. The reason for doing this was to hold the aluminum wire in position and to prevent it from dangling, in case it should break some years in the future. Two coats of clear protective spray were applied for protection.

A truss system helps prevent the disc from sagging due to its own weight. See **Fig 56** for details. This shows the completed disk assembly mounted on the



Fig 56—Photo of the spreader hub assembly, showing the truss ropes above and below the radial spreaders. This is a very rugged assembly!



Fig 57—Photo showing some of the fence posts used to hold individual cone wires to keep them off the ground and out of harm's way. The truck in the background is carting away the A-frame discone for installation at KA8UNO's QTH.

top of the tower. A 3-foot length of 2-inch PVC pipe was used for a truss mast above the disc assembly, notching the bottom of the pipe so that it would form a saddle over the top couple of spreaders. This gave a good foothold. He cut a circle of thin sheet aluminum to fit over the 10-inch PVC to serve as a rain cap. The cap has a hole in the center for the two-inch PVC truss mast to pass through, thereby holding it down tight. The author sprayed a few light coats of paint over the PVC for protection from ultraviolet radiation from the sun.

Sixteen small-diameter black Dacron ropes were connected at the top of the truss support mast, with the other ends fastened to the disc spreaders, halfway out. Another rain cap was added to the top of the two-inch PVC truss mast. Eight lengths of the same small diameter Dacron rope were added halfway out the length of every other spreader. These ropes are meant to be tied back to the tower, to prevent updrafts from blowing the disc assembly upwards. Small egg insulators were used near the spot where the eight bottom trusses were tied to the disc spreaders, just to be sure there would be no RF leakage in rainy weather.

Hoisting the completed disc assembly to the top of the tower can be done easily, with the assistance of at least two others. The trickiest part is to get the disc assembly from its position sitting flat on the ground to the vertical position needed for hoisting it up the tower without damaging it. The disc assembly weighs about 35 pounds. Someone at the top of the tower will receive the disc as it is hoisted up by gin pole, and can mount it on the tower top.

You should prepare three 6-foot long metal braces going over the outside of the PVC to fasten to the tower legs. They really beef things up.

In plastic irrigation pipe buried between the house and tower base, the author ran 100 feet of 9086 low-loss coax to the shack. For cone wires, he was able to obtain some #18 copperclad steel wire, with heavy black insulation that looked a lot like neoprene. The cone system takes a lot of wire: 36 × 70 feet = 2520 feet, plus some extra at each end for termination. You'd be well advised to look around at hamfests to save money.

As each cone wire was connected at the top of the tower, a helper should place the other end at its proper spot below. The lower end of each cone wire is secured to an insulator screwed into a fencepost. See **Fig 57**. There are 36 treated-pine fenceposts, each standing about 5½ feet tall, 45 feet from the tower base to hold the lower end of the cone wires. This makes mowing the grass easier and the cone wires are less likely to be tripped over too.

On the final trip down the tower, the eight Dacron downward-truss lines were tied back to the tower about 6 feet below the disc assembly. The author's tower has three ground rods driven near the base, connected with heavy copper wire to the three tower legs.



Fig 58—Computed patterns showing elevation response of small discone at 28.5 MHz compared to that of the larger discone at 28.5 MHz. The cone wires are clearly too long for efficient operation on 10 meters, producing unwanted high-angle lobes that rob power from the desirable low-elevation angles.

Performance Tests

On the air tests proved to be very satisfying. Loading up on 40 meters was easy—the SWR was 1:1 across the entire band. W8NWF can work all directions very well and receives excellent signal reports from DX stations. When he switches to his long (333 foot) center-fed dipole for comparison, he finds the dipole is much noisier and that received signals are weaker. During the daytime, nearby stations (less than about 300 to 500 miles) can be louder with the dipole, but the discone can work them just fine also.

The author happily reports that this antenna even works well on 75 meters. As you might expect, it doesn't present a 1:1 match. However, the SWR is between 3.5:1 and 5.5:1 across the band. W8NWF uses an antenna tuner to operate the discone on 75. It seems to get out as well on 75 as it does on 40 meters.

The SWR on 30 meters is about 1.1:1. On 20 meters the SWR runs from 1.05:1 at 14.0 MHz to 1.4:1 at 14.3 MHz. The SWR on the 17, 15, 12 and 10-meter bands varies, going up to a high of 3.5:1 on 12 meters.

Radiation Patterns for the Discones

From modeling using *NEC/Wires* by K6STI, W8NWF verified that the low-angle performance for the bigger antenna is worse than that for the smaller discone on the upper frequencies. See **Fig 58** for an elevation-pattern comparison on 10 meters for both antennas, with average ground constants. The azimuth patterns are simply circles. Radiation patterns produced by antenna modeling programs are very helpful to determine what to expect from an antenna.

The smaller discone, which was built by the book, displays good, low-angle lobes on 20 through 10 meters. The frequency range of 14 through 28 MHz is an octave's worth of coverage. It met his expectations in every way by covering this frequency span with low SWR and a low angle of radiation.

The bigger discone, with a modified cone suitable for use on 75 meters, presents a little different story. The low-angle lobe on 40 meters works well, and 75-meter performance also is good, although an antenna tuner is necessary on this band. The 30-meter band has a good low-angle lobe but secondary high-angle lobes are starting to hurt performance. Note that 30 meters is roughly three times the design frequency of the cone. On 20 and 17 meters there still are good low-angle lobes but more and more power is wasted in high-angle lobes.



Fig 59—Computed elevation-response patterns for the larger W8NWF discone for 3.8, 7.2 and 21.2 MHz operation. Again, as in Fig 58, the pattern degrades at 21.2 MHz, although it is still reasonably efficient, if not optimal.

The operation on 15, 12, and 10 meters continues to worsen for the larger discone. The message here is that although a discone may have a decent SWR as high as 10 times the design frequency, its radiation pattern is not necessarily good for low-angle communications. See **Fig 59** for a comparison of elevation patterns for 3.8, 7.2 and 21.2 MHz on the larger discone.

A discone antenna built according to formula will work predictably and without any adjustments. One can modify the antenna's cone length and apex angle without fear of rendering it useless. The broadband feature of the discone makes it attractive to use on the HF bands. The low angle of radiation makes DX a real possibility, and the discone is also much less noisy on receive than a dipole.

Probably the biggest drawback to an HF discone is its bulky size. There is no disguising this antenna! However, if you live in the countryside you should be able to put up a nice one.

Harmonic Radiation from Multiband Antennas

Since a multiband antenna is intentionally designed for operation on a number of different frequencies, any harmonics or spurious frequencies that happen to coincide with one of the antenna resonant frequencies will be radiated with very little, if any, attenuation. Particular care should be exercised, therefore, to prevent such harmonics from reaching the antenna.

Multiband antennas using tuned feeders have a certain inherent amount of built-in protection against such radiation, since it is nearly always necessary to use a tuned coupling circuit (antenna tuner) between the transmitter and the feeder. This adds considerable selectivity to the system and helps to discriminate against frequencies other than the desired one.

Multiple dipoles and trap antennas do not have this feature, since the objective in design is to make the antenna show as nearly as possible the same resistive impedance in all the amateur bands the antenna is intended to cover. It is advisable to conduct tests with other amateur stations to determine whether harmonics of the transmitting frequency can be heard at a distance of, say, a mile or so. If they can, more selectivity should be added to the system since a harmonic that is heard locally, even if weak, may be quite strong at a distance because of propagation conditions.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2, Antenna Fundamentals.

H. B. Barkley, *The Open-Sleeve As A Broadband Antenna*, Technical Report No. 14, U.S. Naval Postgraduate School, Monterey, CA, Jun 1955.

W. M. Bell, "A Trap Collinear Antenna," *QST*, Aug 1963, pp 30-31.

J. S. Belrose, "The HF Discone Antenna," *QST*, Jul 1975, pp 11-14, 56.

J. Belrose and P. Bouliane, "The Off-Center-Fed Dipole Revisited: A Broadband, Multiband Antenna," *QST*, Oct 1990, p 40.

H. J. Berg, "Multiband Operation with Paralleled Dipoles," *QST*, Jul 1956.

E. L. Bock, J. A. Nelson and A. Dorne, "Sleeve Antennas," *Very High Frequency Techniques*, H. J. Reich, ed. (New York: McGraw-Hill, 1947), Chap 5.

J. T. Bolljahn and J. V. N. Granger, "Omnidirectional VHF and UHF Antennas," *Antenna Engineering Handbook* , H. Jasik, ed. (New York: McGraw-Hill, 1961) pp 27-32 through 27-34.

J. M. Boyer, W6UYH, "Discone--40 to 500 Mc Skywire," *CQ*, July 1949, p 11.

G. A. Breed, K9AY, "Multi-Frequency Antenna Technique Uses Closely-Coupled Resonators," *RF Design*, November 1994. US Patent 5,489,914, "Method of Constructing Multiple-Frequency Dipole or Monopole Antenna Elements Using Closely-Coupled Resonators," Gary A. Breed, Feb 6, 1996.

G. H. Brown, "The Phase and Magnitude of Earth Currents Near Radio Transmitting Antennas," *Proc. IRE*, Feb 1935.

G. H. Brown, R. F. Lewis and J. Epstein, "Ground Systems as a Factor in Antenna Efficiency," *Proc. IRE* , Jun 1937, pp 753-787.

C. L. Buchanan, "The Multimatch Antenna System," *QST*, Mar 1955.

R. A. Cox, "The Open-Sleeve Antenna," *CQ*, Aug 1983, pp 13-19.

D. DeMaw, "Lightweight Trap Antennas—Some Thoughts," *QST*, Jun 1983, p 15.

W. C. Gann, "A Center-Fed 'Zepp' for 80 and 40," *QST*, May 1966.

D. Geiser, "An Inexpensive Multiband VHF Antenna," *QST*, Dec 1978, pp 28-29.

A. Greenberg, "Simple Trap Construction for the Multiband Antenna," *QST*, Oct 1956.

G. L. Hall, "Trap Antennas," Technical Correspondence, *QST*, Nov 1981, pp 49-50.

W. Hayward, "Designing Trap Antennas," Technical Correspondence, *QST*, Aug 1976, p 38.

R. H. Johns, "Dual-Frequency Antenna Traps," *QST*, Nov 1983, p 27.

A. G. Kandoian, "Three New Antenna Types and Their Applications," *Proc IEE*, Vol 34, Feb 1946, pp 70W-75W.

R. W. P. King, *Theory of Linear Antennas* (Cambridge, MA: Harvard Univ Press, 1956), pp 407-427.

W. J. Lattin, "Multiband Antennas Using Decoupling Stubs," *QST*, Dec 1960.

W. J. Lattin, "Antenna Traps of Spiral Delay Line," *QST*, Nov 1972, pp 13-15.

M. A. Logan, "Coaxial-Cable Traps," Technical Correspondence, *QST*, Aug 1985, p 43.

J. R. Mathison, "Inexpensive Traps for Wire Antennas," *QST*, Aug 1977, p 18.

L. McCoy, "An Easy-to-Make Coax-Fed Multiband Trap Dipole," *QST*, Dec 1964.

M. Mims, "The Mims Signal Squirter," *QST*, Dec 1939, p 12.

G. E. O'Neil, "Trapping the Mysteries of Trapped Antennas," *Ham Radio*, Oct 1981, pp 10-16.

B. Orr, W6SAI, "Radio FUNdamentals," The Open-Sleeve Dipole, *CQ*, February 1995.

E. W. Pappenfus, "The Conical Monopole Antenna," *QST*, Nov 1966, pp 21-24.

L. Richard, "Parallel Dipoles of 300-Ohm Ribbon," *QST*, Mar 1957.

R. Severns, N6LF, "A Wideband 80-Meter Dipole," *QST*, July 1995.

R. R. Shellenback, "Try the 'TJ'," *QST*, Jun 1982, p 18.

R. R. Shellenback, "The JF Array," *QST*, Nov 1982, p 26.

H. Scholle and R. Steins, “Eine Doppel-Windom Antenna fur Acht Bander,” *cq-DL*, Sep 1983, p 427. (In English: *QST*, Aug 1990, pp 33-34.)

T. H. Schiller, N6BT, President, Force 12, US Patent 5,995,061, “No loss, multi-band, adaptable antenna,” Nov 30, 1999.

M. Seybold, W2RYI, “The Low-Frequency Discone,” *CQ*, July 1950, p 13.

D. P. Shafer, “Four-Band Dipole with Traps,” *QST*, Oct 1958.

R. C. Sommer, “Optimizing Coaxial-Cable Traps,” *QST*, Dec 1984, p 37.

L. Varney, “The G5RV Multiband Antenna . . . Up-to-Date,” *The ARRL Antenna Compendium, Vol 1* (Newington: ARRL, 1985), pp 86.

R. Wilson, AL7KK, “The Offset Multiband Trapless Antenna (OMTA),” *QST*, October 1995.

L. G. Windom, “Notes on Ethereal Antennas,” *QST*, Sep 1929, pp 19-22, 84.

W. I. Orr, W6SAI, editor, “The Low-Frequency Discone,” *RADIO Handbook*, 14th Edition, (Editors and Engineers, 1956), p 369.

Chapter 8

Multielement Arrays

The gain and directivity offered by an array of elements represents a worthwhile improvement both in transmitting and receiving. *Power gain* in an antenna is the same as an equivalent increase in the transmitter power. But unlike increasing the power of your own transmitter, antenna gain works equally well on signals received from the favored direction. In addition, the directivity reduces the strength of signals coming from the directions not favored, and so helps discriminate against interference.

One common method of obtaining gain and directivity is to combine the radiation from a group of $\lambda/2$ dipoles to concentrate it in a desired direction. A few words of explanation may help make it clear how power gain is obtained.

In **Fig 1**, imagine that the four circles, A, B, C and D, represent four dipoles so far separated from each other that the coupling between them is negligible. Also imagine that point P is so far away from the dipoles that the distance from P to each one is exactly the same (obviously P would have to be much farther away than it is shown in this drawing). Under these conditions the fields from all the dipoles will add up at P if all four are fed RF currents in the same phase.

Let us say that a certain current, I, in dipole A will produce a certain value of field strength, E, at the distant point P. The same current in any of the other dipoles will produce the same field at P. Thus, if only dipoles A and B are operating, each with a current I, the field at P will be 2E. With A, B and C operating, the field will be 3E, and with all four operating with the same I, the field will be 4E. Since the power received at P is proportional to the square of the field strength, the relative power received at P is 1, 4, 9 or 16, depending on whether one, two, three or four dipoles are operating.

Now, since all four dipoles are alike and there is no coupling between them, the same power must be put into each in order to cause the current I to flow. For two dipoles the relative power input is 2, for three dipoles it is 3, for four dipoles 4, and so on. The actual gain in each case is the relative received (or output) power divided by the relative input power. Thus we have the results shown in **Table 1**. The power ratio is directly proportional to the number of elements used.

It is well to have clearly in mind the conditions under which this relationship is true:

1) The fields from the separate antenna elements must be in-phase at the receiving point.

2) The elements are identical, with equal currents in all elements.

3) The elements must be separated in such a way that the current induced in one by another is negligible; that is, the radiation resistance of each element must be the same as it would be if the other elements were not there.

Very few antenna arrays meet all these conditions exactly. However, the power gain of a directive array using dipole elements with optimum values of element spacing is approximately proportional to the number of elements.



Fig 1—Fields from separate antennas combine at a distant point, P, to produce a field strength that exceeds the field produced by the same power in a single antenna.

Table 1
Comparison of Dipoles with Negligible Coupling (See Fig 1)

Dipoles	*Relative Output Power*	*Relative Input Power*	*Power Gain*	*Gain in dB*
A only	1	1	1	0
A and B	4	2	2	3
A, B and C	9	3	3	4.8
A, B, C and D	16	4	4	6

Another way to say this is that a gain of approximately 3 dB will be obtained each time the number of elements is doubled, assuming the proper element spacing is maintained. It is possible, though, for an estimate based on this rule to be in error by a ratio factor of two or more (gain error of 3 dB or more), especially if mutual coupling is *not* negligible.

DEFINITIONS

An *element* in a multi-element directive array is usually a λ/2 radiator or a λ/4 vertical element above ground. The length is not always an exact electrical half or quarter wavelength, because in some types of arrays it is desirable that the element show either inductive or capacitive reactance. However, the departure in length from resonance is ordinarily small (not more than 5% in the usual case) and so has no appreciable effect on the radiating properties of the element.

Antenna elements in multi-element arrays of the type considered in this chapter are always either *parallel*, as in **Fig 2A** , or *collinear* (end-to-end), as in Fig 2B. Fig 2C shows an array combining both parallel and collinear elements. The elements can be either horizontal or vertical, depending on whether horizontal or vertical polarization is desired. Except for space communications, there is seldom any reason for mixing polarization, so arrays are customarily constructed with all elements similarly polarized.

A *driven element* is one supplied power from the transmitter, usually through a transmission line. A *parasitic element* is one that obtains power solely through coupling to another element in the array because of its proximity to such an element.

A *driven array* is one in which all the elements are driven elements. A *parasitic array* is one in which one or more of the elements are parasitic elements. At least one element must be a driven element, since you must somehow introduce power into the array.

A *broadside array* is one in which the principal direction of radiation is perpendicular to the axis of the array and to the plane containing the elements, as shown in **Fig 3**. The elements of a broadside array may be collinear, as in Fig 3A, or parallel (two views in Fig 3B).

An *end-fire array* is one in which the principal direction of radiation coincides with the direction of the array axis. This definition is illustrated in **Fig 4**. An end-fire array must consist of parallel elements. They cannot be collinear, as λ/2 elements do not radiate straight off their ends. A Yagi is a familiar form of an end-fire array.

A *bidirectional array* is one that radiates equally well in either direction along the line of maximum radiation. A bidirectional pattern is shown in **Fig 5A**. A *unidirectional array* is one that has only one principal direction of radiation, as the pattern in Fig 5B shows.

The *major lobes* of the directive pattern are those in which the radiation is maximum. Lobes of lesser radiation intensity are called *minor lobes*. The *beamwidth* of a directive antenna is the width, in degrees, of the major lobe between the two directions at which the relative radiated power is equal to one half its value at the peak of the lobe. At these *half-power points* the field intensity is equal to 0.707 times its maximum value, or in other words, is down 3 dB from the maximum. **Fig 6** shows a lobe having a beamwidth of 30°.

Unless specified otherwise, the term *gain* as used in this



Fig 2—At A, parallel and at B, collinear antenna elements. The array shown at C combines both parallel and collinear elements.



Fig 3—Representative broadside arrays. At A, collinear elements, with parallel elements at B.


View from Ends of Elements
Axis of Array
Direction of Max. Radiation
Axis of Array
Direction of Max. Radiation
ANT0299
Side View

Fig 4—An end-fire array. Practical arrays may combine both broadside directivity (Fig 3) and end-fire directivity, including both parallel and collinear elements.

section is the power gain over an isotropic radiator in free space. The gain can also be compared with a $\lambda/2$ dipole of the same orientation and height as the array under discussion and having the same power input. Gain may either be measured experimentally or determined by calculation. Experimental measurement is difficult and often subject to considerable error, for two reasons. First, errors normally occur in measurement because the accuracy of simple RF measuring equipment is relatively poor—even high-quality instruments suffer in accuracy compared with their low-frequency and dc counterparts. And second, the accuracy depends considerably on conditions—the antenna site, including height, terrain characteristics, and surroundings—under which the measurements are made.



Fig 5—At A, typical bidirectional pattern and at B, unidirectional directive pattern. These drawings also illustrate the application of the terms *major* and *minor* to the pattern lobes.



Fig 6—The width of a beam is the angular distance between the directions at which the received or transmitted power is half the maximum power (–3 dB). Each angular division of the pattern grid is 5°.

Calculations are frequently based on the measured or theoretical directive patterns of the antenna (see Chapter 2). The theoretical gain of an array may be determined approximately from:

$$G = 10 \log \frac{41{,}253}{\theta_H \, \theta_V} \qquad \text{(Eq 1)}$$

where

G = decibel gain over a dipole in its favored direction
θ_H = horizontal half-power beamwidth in degrees
θ_V = vertical half-power beamwidth in degrees.

This equation, strictly speaking, applies only to lossless antennas having approximately equal and narrow E- and H-plane beam widths—up to about 20°—and no large minor lobes. The E and H planes are discussed in Chapter 2. The error may be considerable when the formula is applied to simple directive antennas having relatively large beam widths. The error is in the direction of making the calculated gain larger than the actual gain.

Front-to-back ratio (F/B) is the ratio of the power radiated in the favored direction to the power radiated in the opposite direction. See Chapter 11 for a discussion of front-to-back ratio, and its close cousin, *worst-case front-to-rear ratio*.

Phase

The term *phase* has the same meaning when used in connection with the currents flowing in antenna elements as it does in ordinary circuit work. For example, two currents are in-phase when they reach their maximum values, flowing in the same direction, at the same instant. The direction of current flow depends on the way in which power is applied to the element.

This is illustrated in **Fig 7**. Assume that by some means an identical voltage is applied to each of the elements at the ends marked A. Assume also that the coupling between the elements is negligible, and that the instantaneous polarity of the voltage is such that the current is flowing away from the point at which the voltage is applied. The arrows show the assumed current directions. Then the currents in elements 1 and 2 are in-phase, since they are flowing in the same direction in space and are caused by the same voltage. However, the current in element 3 is flowing in the *opposite* direction in space because the voltage is applied to the opposite end of the element. The current in element 3 is therefore 180° out-of-phase with the currents in elements 1 and 2.

The phasing of driven elements depends on the direction of the element, the phase of the applied voltage, and the point at which the voltage is applied. In many systems used by amateurs, the voltages applied to the elements are exactly



Fig 7—This drawing illustrates the phase of currents in antenna elements, represented by the arrows. The currents in elements 1 and 2 are in phase, while that in element 3 is 180° out of phase with 1 and 2.

in or exactly out-of-phase with each other. Also, the axes of the elements are nearly always in the same direction, since parallel or collinear elements are invariably used. The currents in driven elements in such systems therefore are usually either exactly in or exactly out-of-phase with the currents in other elements.

It is possible to use phase differences of less than 180° in driven arrays. One important case is where the current in one set of elements differs by 90° from the current in another set. However, making provision for proper phasing in such systems is considerably more complex than in the case of simple 0° or 180° phasing, as described in a later section of this chapter.

In parasitic arrays the phase of the currents in the parasitic elements depends on the spacing and tuning, as described later.

Ground Effects

The effect of the ground is the same with a directive antenna as it is with a simple dipole antenna. The reflection factors discussed in Chapter 3 may therefore be applied to the vertical pattern of an array, subject to the same modifications mentioned in that chapter. In cases where the array elements are not all at the same height, the reflection factor for the mean height of the array may be used for a close approximation. The mean height is the average of the heights measured from the ground to the centers of the lowest and highest elements.

MUTUAL IMPEDANCE

Consider two $\lambda/2$ elements that are fairly close to each other. Assume that power is applied to only one element, causing current to flow. This creates an electromagnetic field, which induces a voltage in the second element and causes current to flow in it as well. The current flowing in element 2 will in turn induce a voltage in element 1, causing additional current to flow there. The total current in 1 is then the sum (taking phase into account) of the original current and the induced current.

With element 2 present, the amplitude and phase of the resulting current in element 1 will be different than if element 2 were not there. This indicates that the presence of the second element has changed the impedance of the first. This effect is called *mutual coupling*. Mutual coupling results in a *mutual impedance* between the two elements. The mutual impedance has both resistive and reactive components. The actual impedance of an antenna element is the sum of its self-impedance (the impedance with no other antennas present) and its mutual impedances with all other antennas in the vicinity.

The magnitude and nature of the feed-point impedance of the first antenna depends on the amplitude of the current induced in it by the second, and on the phase relationship between the original and induced currents. The amplitude and phase of the induced current depend on the spacing between the antennas and whether or not the second antenna is tuned to resonance.

In the discussion of the several preceding paragraphs, power is applied to only one of the two elements. Do not interpret this to mean that mutual coupling exists only in parasitic arrays! It is important to remember that mutual coupling exists between any two conductors that are located near one another.

Amplitude of Induced Current

The induced current will be largest when the two antennas are close together and are parallel. Under these conditions the voltage induced in the second antenna by the first, and in the first by the second, has its greatest value and causes the largest current flow. The coupling decreases as the parallel antennas are moved farther apart.

The coupling between collinear antennas is comparatively small, and so the mutual impedance between such antennas is likewise small. It is not negligible, however.

Phase Relationships

When the separation between two antennas is an appreciable fraction of a wavelength, a measurable period of time elapses before the field from antenna 1 reaches antenna 2. There is a similar time lapse before the field set up by the current in number 2 gets back to induce a current in number 1. Hence the current induced in antenna 1 by antenna 2 will have a phase relationship with the original current in antenna 1 that depends on the spacing between the two antennas.

The induced current can range all the way from being completely in-phase with the original current to being completely out-of-phase with it. If the currents are in-phase, the total current is larger than the original current and the antenna feed-point impedance is reduced. If the currents are out-of-phase, the total current is smaller and the impedance is increased. At intermediate phase relationships the impedance will be lowered or raised depending on whether the induced current is mostly in or mostly out-of-phase with the original current.

Except in the special cases when the induced current is exactly in or out-of-phase with the original current, the induced current causes the phase of the total current to shift with respect to the applied voltage. Consequently, the presence of a second antenna nearby may cause the impedance of an antenna to be reactive—that is, the antenna will be detuned from resonance—even though its self-impedance is entirely resistive. The amount of detuning depends on the magnitude and phase of the induced current.

Tuning Conditions

A third factor that affects the impedance of antenna 1 when antenna 2 is present is the tuning of number 2. If antenna 2 is not exactly resonant, the current that flows in it as a result of the induced voltage will either lead or lag the phase it would have if the antenna were resonant. This causes an additional phase advance or delay that affects the phase of the current induced back in antenna 1. Such a phase lag has an effect similar to a change in the spacing between self-resonant antennas. However, a change in tuning is not exactly equivalent to a change in spacing because the two methods do not have the same effect on the amplitude of the induced current.

MUTUAL IMPEDANCE AND GAIN

The mutual coupling between antennas is important because it can have a significant effect on the amount of current that will flow for a given amount of power supplied. And it is the amount of *current* flowing that determines the field strength from the antenna. Other things being equal, if the mutual coupling between two antennas is such that the currents are greater for the same total power than would be the case if the two antennas were not coupled, the power gain will be greater than that shown in Table 1.

On the other hand, if the mutual coupling is such as to reduce the current, the gain will be less than if the antennas were not coupled. The term *mutual coupling*, as used in this paragraph, assumes that the mutual impedance between elements is taken into account, along with the added effects of propagation delay because of element spacing and element tuning or phasing.

The calculation of mutual impedance between antennas is a complex problem. Data for two simple but important cases are graphed in Figs 8 and 9. These graphs do not show the mutual impedance, but instead show a more useful quantity—the feed-point resistance measured at the center of an antenna as it is affected by the spacing between two antennas.

As shown by the solid curve in **Fig 8**, the feed-point resistance at the center of either antenna, when the two are self-resonant, parallel, and operated in-phase, decreases as the spacing between them is increased until the spacing is about 0.7 λ. This is a broadside array. The maximum gain is achieved from a pair of such elements when the spacing is in this region, because the current is larger for the same power and the fields from the two arrive in-phase at a distant point placed on a line perpendicular to the line joining the two antennas.



Fig 8—Feed-point resistance measured at the center of one element as a function of the spacing between two parallel ½-λ self-resonant antenna elements. For ground-mounted ¼-λ vertical elements, divide these resistances by two.

The dashed line in Fig 8, representing two antennas operated 180° out-of-phase (end-fire), cannot be interpreted quite so simply. The feed-point resistance decreases with spacing decreasing less than about 0.6 λ in this case. However, for the range of spacings considered, only when the spacing is 0.5 λ do the fields from the two antennas add up exactly in phase at a distant point in the favored direction. At smaller spacings the fields become increasingly out-of-phase, so the total field is less than the simple sum of the two. Smaller spacings thus decrease the gain at the same time that



Fig 9—Feed-point resistance measured at the center of one element as a function of the spacing between the ends of two collinear self-resonant ½-λ antenna elements operated in phase.

the reduction in feed-point resistance is increasing it. For a lossless antenna, the gain goes through a maximum when the spacing is in the region of ⅛ λ.

The feed-point resistance curve for two collinear elements in-phase, **Fig 9**, shows that the feed-point resistance decreases and goes through a broad minimum in the region of 0.4 to 0.6-λ spacing between the adjacent ends of the antennas. As the minimum is not significantly less than the feed-point resistance of an isolated antenna, the gain will not exceed the gain calculated on the basis of uncoupled antennas. That is, the best that two collinear elements will give, even with optimum spacing, is a power gain of about 2 (3 dB). When the separation between the ends is very small—the usual method of operation—the gain is reduced.

GAIN AND ARRAY DIMENSIONS

The gain of an array is principally determined by the dimensions of the array, so long as there are a minimum number of elements. A good example of this is the relationship between boom length, gain and number of elements for an array such as a Yagi. **Fig 10** compares the gain versus boom length for Yagis with different numbers of elements. For given number of elements, notice that the gain increases as the boom length increases, up to a maximum. Beyond this point, longer boom lengths result in less gain for a given number of elements. This observation does not mean that it is always desirable to use only the minimum number of elements. Other considerations of array performance, such as front-to-back ratio, minor lobe amplitudes or operating bandwidth, may make it advantageous to use more than the minimum number of elements for a given array length. A specific example of this is presented in a later section in a comparison between a half-square, a bobtail curtain and a Bruce array.



Fig 10—Yagi gain for 3, 4, 5, 6 and 7-element beams as a function of boom length. (From *Yagi Antenna Design*, J. Lawson, W2PV.)

In a broadside array the gain is a function of both the length and width of the array. The gain can be increased by adding more elements (with additional spacing) or by using longer elements (>λ/2), although the use of longer elements requires proper attention to current phase in the elements. In general, in a broadside array the element spacing that gives maximum gain for a minimum number of elements, is in the range of 0.5 to 0.7 λ. Broadside arrays with elements spaced for maximum gain will frequently have significant side lobes and associated narrowing of the main lobe beamwidth. Side lobes can be reduced by using more than the minimum number of elements, spaced closer than the maximum gain distance.

Additional gain can be obtained by expanding the array into a third dimension. An example of this is the stacking of endfire arrays in a broadside configuration. In the case of stacked short endfire arrays, maximum gain occurs with spacings in the region of 0.5 to 0.7 λ. However, for longer higher-gain end-fire arrays, larger spacing is required to achieve maximum gain. This is important in VHF and UHF arrays, which often use long-boom Yagis.

PARASITIC ARRAYS

The foregoing applies to multi-element arrays of both types, driven and parasitic. However, there are special considerations for driven arrays that do not necessarily apply to parasitic arrays, and vice versa. Such considerations for Yagi and quad parasitic arrays are presented in Chapters 11 and 12. The remainder of this chapter is devoted to driven arrays.

Driven Arrays

Driven arrays in general are either broadside or end-fire, and may consist of collinear elements, parallel elements, or a combination of both. From a practical standpoint, the maximum number of usable elements depends on the frequency and the space available for the antenna. Fairly elaborate arrays, using as many as 16 or even 32 elements, can be installed in a rather small space when the operating frequency is in the VHF range, and more at UHF. At lower frequencies the construction of antennas with a large number of elements is impractical for most amateurs.

Of course the simplest of driven arrays is one with just two elements. If the elements are collinear, they are always fed in-phase. The effects of mutual coupling are not great, as illustrated in Fig 9. Therefore, feeding power to each element in the presence of the other presents no significant problems. This may not be the case when the elements are parallel to each other. However, because the combination of spacing and phasing arrangements for parallel elements is infinite, the number of possible radiation patterns is endless.

This is illustrated in **Fig 11**. When the elements are fed in-phase, a broadside pattern always results. At spacings of less than ⅝ λ with the elements fed 180° out-of-phase, an end-fire pattern always results. With intermediate amounts of phase difference, the results cannot be so simply stated. Patterns evolve that are not symmetrical in all four quadrants.

Because of the effects of mutual coupling between the two driven elements, for a given power input greater or lesser currents will flow in each element with changes in spacing and phasing, as described earlier. This, in turn, affects the gain of the array in a way that cannot be shown merely by plotting the *shapes* of the patterns, as has been done in Fig 11. Therefore, supplemental gain information is also shown in Fig 11, adjacent to the pattern plot for each combination of spacing and phasing. The gain figures shown are referenced to a single element. For example, a pair of elements fed 90° apart at a spacing of λ/4 will have a gain in the direction of maximum radiation of 3.1 dB over a single element.

Current Distribution in Phased Arrays

In the plots of Fig 11, the two elements are assumed to be identical and self-resonant. In addition, currents of equal amplitude are assumed to be flowing at the feed point of each element, a condition that most often will not exist in practice without devoting special consideration to the feeder system. Such considerations are discussed in the next section of this chapter.

Most literature for radio amateurs concerning phased arrays is based on the assumption that if all elements in the array are identical, the *current distribution* in all the elements will be identical. This distribution is presumed to be that of a single, isolated element, or nearly sinusoidal. However, information published in the professional literature as early as the 1940s indicates the existence of dissimilar current distributions among the elements of phased arrays. (See Harrison and King references in the Bibliography.) Lewallen, in July 1990 *QST*, pointed out the causes and effects of dissimilar current distributions.

In essence, even though the two elements in a phased array may be identical and have exactly equal currents of the desired phase flowing *at the feed point*, the amplitude and phase relationships degenerate with departure from the feed point. This happens any time the phase relationship is not 0° or 180°. Thus, the field strengths produced at a distant point by the individual elements may differ. This is because the field from each element is determined by the *distribution* of the current, as well as its magnitude and phase.

The effects are minimal with shortened elements—verticals less than λ/4 or dipoles less than λ/2 long. The effects on radiation patterns begin to show at the above resonant lengths, and become profound with longer elements—λ/2 or longer verticals and 1 λ or longer center-fed elements. These effects are less pronounced with thin elements. The amplitude and phase degeneration takes place because the currents in the array elements are not sinusoidal. Even in two-element arrays with phasing of 0° or 180°, the currents are not sinusoidal, but in these two special cases they do remain identical.

The pattern plots of Fig 11 take element current distributions into account. The visible results of dissimilar distributions are incomplete nulls in some patterns and the development of very small minor lobes in others. For example, the pattern for a phased array with 90° spacing and 90° phasing has traditionally been published in amateur literature as a cardioid with a perfect null in the rear direction. Fig 11, calculated for 7.15-MHz self-resonant dipoles of #12 wire in free space, shows a minor lobe at the rear and only a 33-dB front-to-back ratio.

It is characteristic of broadside arrays that the power gain is proportional to the length of the array but is substantially independent of the number of elements used, provided the optimum element spacing is not exceeded. This means, for example, that a five-element array and a six-element array will have the same gain, provided the elements in both are spaced so the overall array length is the same. Although this principle is seldom used for the purpose of reducing the number of elements because of complications introduced in feeding power to each element in the proper phase, it does illustrate the fact that there is nothing to be gained, in terms of more gain, by increasing the number of elements if the space occupied by the antenna is not increased proportionally.

Generally speaking, the maximum gain in the smallest linear dimensions will result when the antenna combines both broadside and end-fire directivity and uses both parallel and collinear elements. In this way the antenna is spread over a greater volume of space, which has the same effect as extending its length to a much greater extent in one linear direction.



Fig 11—H-plane patterns of two identical parallel driven elements, spaced and phased as indicated (S = spacing, φ = phasing). The elements are aligned with the vertical (0°-180°) axis, and the element nearer the 0° direction (top of page) is of lagging phase at angles other than 0°. The two elements are assumed to be thin and self-resonant, with equal-amplitude currents flowing at the feed point. See text regarding current distributions. The gain figure associated with



each pattern indicates that of the array over a single element. The plots represent the horizontal or azimuth pattern at a 0° elevation angle of two ¼-λ vertical elements over a perfect conductor, or the free-space vertical or elevation pattern of two horizontal ½-λ elements when viewed on end, with one element above the other. (Patterns computed with *ELNEC*—see Bibliography.)

Phased Array Techniques

Phased antenna arrays have become increasingly popular for amateur use, particularly on the lower frequency bands, where they provide one of the few practical methods to obtain substantial gain and directivity. This section on phased-array techniques was written by Roy Lewallen, W7EL.

The operation and limitations of phased arrays, how to design feed systems to make them work properly and how to make necessary tests and adjustments are discussed in the pages that follow. The examples deal primarily with vertical HF arrays, but the principles apply to VHF/UHF arrays and arrays made from other element types as well.

OVERVIEW

Much of this chapter is devoted to techniques for feeding phased arrays. Many people who have a limited acquaintance with phased array techniques believe this is a simple problem, consisting only of connecting array elements through "phasing lines" consisting of transmission lines of the desired electrical lengths. Unfortunately, except for a very few special cases, this approach won't achieve the desired array pattern.

Other proposed universal solutions, such as hybrid couplers or Wilkinson or other power dividers, also usually fail to achieve the necessary phasing. These approaches sometimes produce—often more by accident than design—results good enough to mislead the user into believing that the simple approach is working as planned. Confusion can result when an approach fails to work in different circumstances. This section will explain why the simple solutions don't work as often thought, and how to design feed systems that do consistently produce the desired results.

Very briefly, the reason why the simple phasing-line approach fails is that the delay of current or voltage in a transmission line equals the line's electrical length only if the line is terminated in its characteristic impedance. And in phased arrays, element feed-point impedances are profoundly affected by mutual coupling.

Consequently, even if each element has the correct impedance when isolated, it won't when all elements are excited. Furthermore, transmission lines that are not terminated in their characteristic impedance will transform both the voltage and current magnitude. The net result is that the array elements will have neither the correct magnitudes nor phases of current necessary for proper operation except in a few special cases. This isn't a minor effect of concern only to perfectionists, but often a major one that causes significant pattern distortion and poor or mislocated nulls. The problem is examined in greater depth later.

Power dividers and hybrid couplers also fail to achieve the desired result for different reasons, which will be discussed below, although in one common application hybrid couplers fortuitously provide results that are acceptable to many users. This chapter will show how to design array feed systems that *will* produce predicted element currents and array patterns.

Various *EZNEC* models are provided to illustrate concepts presented in this chapter. They can all be viewed with the *EZNEC-ARRL* software furnished on the CD included with this book. Step-by-step instructions for the examples are given in **Appendix A**.

FUNDAMENTALS OF PHASED ARRAYS

The performance of a phased array is determined by several factors. Most significant among these are the characteristics of a single element, reinforcement or cancellation of the fields from the elements and the effects of mutual coupling. To understand the operation of phased arrays, it is first necessary to understand the operation of a single antenna element.

Of primary importance is the strength of the field produced by the element. The field radiated from a linear (straight) element, such as a dipole or vertical monopole, is proportional to the sum of the elementary currents flowing in each part of the antenna element. For this discussion it is important to understand what determines the current in a single element.

The amount of current flowing at the base of a ground mounted vertical or ground-plane antenna is given by the familiar formula

$$I = \sqrt{\frac{P}{R}} \qquad \text{(Eq 2)}$$

where

P is the power supplied to the antenna
R is the feed-point resistance.

R consists of two parts, the loss resistance and the radiation resistance. The loss resistance, R_L, includes losses in the conductor, in the matching and loading components and dominantly (in the case of ground-mounted verticals) in ground losses. The power "dissipated" in the radiation resistance, R_R, is actually the power that is radiated, so maximizing the power dissipated by the radiation resistance is desirable. However, the power dissipated in the loss resistance truly is lost as heat, so resistive losses should be made as small as possible.

The radiation resistance of an element can be derived from electromagnetic field theory, being a function of antenna length, diameter and geometry. Graphs of radiation resistance versus antenna length are given in Chapter 2. The radiation resistance of a thin resonant $\lambda/4$ ground-mounted vertical is about 36 Ω. A resonant $\lambda/2$ dipole in free space has a radiation resistance of twice this amount, about 73 Ω. Reducing the antenna lengths by one half drops the radiation resistances to approximately 7 and 14 Ω, respectively.

The radiation resistance of a large variety of antennas can easily be determined by using *EZNEC-ARRL*, which is included on the CD in the back of this book. The radiation



Fig 12—Simplified equivalent circuit for a single-element resonant antenna. R_R represents the radiation resistance, and R_L the ohmic losses in the total antenna system.

resistance is simply the feed-point resistance (the resistive part of the feed-point impedance) when all losses have been set to zero.

Radiation Efficiency

To generate a stronger field from a given radiator, it is necessary to increase the power P (the brute-force solution), decrease the loss resistance R_L (by putting in a more elaborate ground system for a vertical, for instance) or to somehow decrease the radiation resistance R_R so more current will flow with a given power input. This can be seen by expanding the formula for base current as

$$I = \sqrt{\frac{P}{R_R + R_L}} \qquad \text{(Eq 3)}$$

Splitting the feed-point resistance into components R_R and R_L easily leads to an understanding of element efficiency. The efficiency of an element is the proportion of the total power that is actually radiated. The roles of R_R and R_L in determining efficiency can be seen by analyzing a simple equivalent circuit, shown in **Fig 12**.

The power dissipated in R_R (the radiated power) equals I^2R_R. The total power supplied to the antenna system is

$$P = I^2 (R_R + R_L) \qquad \text{(Eq 4)}$$

so the efficiency (the fraction of supplied power that is actually radiated) is

$$\text{Eff} = \frac{I^2 R_R}{I^2 (R_R + R_L)} = \frac{R_R}{R_R + R_L} \qquad \text{(Eq 5)}$$

Efficiency is frequently expressed in percent, but expressing it in decibels relative to a 100%-efficient radiator gives a better idea of what to expect in the way of signal strength. The field strength of an element relative to a lossless but otherwise identical element, in dB, is

$$\text{FSG} = 10 \log \frac{R_R}{R_R + R_L} \qquad \text{(Eq 6)}$$

where FSG = field strength gain, dB.

For example, information presented by Sevick in March 1973 *QST* shows that a $\lambda/4$ ground-mounted vertical antenna with four 0.2-λ radials has a feed-point resistance of about 65 Ω (see the Bibliography at the end of this chapter). The efficiency of such a system is 36/65 = 55.4%. It is rather disheartening to think that, of 100 W fed to the antenna, only 55 W is being radiated, with the remainder literally warming up the ground. Yet the signal will be only 10 log (36/65) = –2.57 dB relative to the same vertical with a perfect ground system. In view of this information, trading a small reduction in signal strength for lower cost and greater simplicity may become an attractive consideration.

So far, only the current at the base of a resonant antenna has been discussed, but the field is proportional to the sum of currents in each tiny part of the antenna. The field is a function of not only the magnitude of current flowing at the feed point, but also the distribution of current along the radiator and the length of the radiator. Nothing can be done at the feed point to change the current distribution, so for a given element the field strength is proportional to the feed point current. However, changing the radiator length or loading it at some point other than the feed point will change the current distribution.

More information on shortened or loaded radiators may be found in Chapters 2 and 6 and in the Bibliography references of this chapter. The current distribution is also changed by mutual coupling to other array elements, although for most arrays this has only a minor effect on the pattern. This is discussed later in more detail. A few other important facts follow.

1) If there is no loss, the field from even an infinitesimally short radiator is less than ½ dB weaker than the field from a half-wave dipole or quarter-wave vertical. Without loss, all the supplied power is radiated regardless of the antenna length, so the only factor influencing gain is the slight difference in the patterns of very short and $\lambda/2$ antennas. The small pattern difference arises from different current distributions. A short antenna has a very low radiation resistance, resulting in a heavy current flow over its short length. In the absence of loss, this generates a field strength comparable to that of a longer antenna. Where loss is present—that is, in practical antennas—shorter radiators usually don't do so well, since the low radiation resistance leads to lower efficiency for a given loss resistance. If care is taken, reasonably short antennas can achieve good efficiency.

2) Care has to be taken in calculating the efficiency of folded antennas. (See Chapter 6.) Folding transforms both the radiation resistance and loss resistance by the same factor, so their ratio and therefore the efficiency remains the same. It's easy to show that in a ground-mounted vertical array, folding reduces the current flowing from the feed line to the ground system by a factor of two due to the impedance transformation. However, the folded antenna has an additional connection to ground, which also carries half the original ground current. The result is that the same amount of current flows

into the ground system, whether unfolded or folded, resulting in the same ground system loss. Analyses purporting to show otherwise invariably transform the radiation resistance but neglect to also transform the loss resistance and reach an incorrect conclusion.

3) The current flowing in an element with a given power input can be increased or decreased by mutual coupling to other elements. The effect is equivalent to changing the element radiation resistance. Mutual coupling is sometimes thought of as a minor effect, but often it is not minor!

Field Reinforcement and Cancellation

The mechanism by which phased arrays produce gain, and the role of mutual coupling in determining gain, were covered earlier in this chapter. One important point that can't be emphasized enough is that all antennas must abide by the law of *conservation of energy*. No antenna can radiate more power than supplied to it. The total amount of power it radiates is the amount it's supplied, less the amount lost as heat. This is true of all antennas, from the smallest "rubber ducky" to the most gigantic array.

Gain

Gain is strictly a relative measure, so the term is completely meaningless unless accompanied by a statement of just what it is relative to. One useful measure for phased array gain is *gain relative to a single similar element*. This is the increase in signal strength that would be obtained by replacing a single element by an array made from elements just like it. In some instances, such as investigating what happens to array performance when *all* elements become more lossy, it's useful to state gain relative to a more absolute, although unattainable standard: a lossless element.

And the most universal reference for gain is another unattainable standard, the *isotropic radiator*. This fictional antenna radiates absolutely equally in all directions. It's very useful because the field strength resulting from any power input is readily calculated, so if the gain relative to this standard is known, the field strength is also known for any radiated power. Gain relative to this reference is referred to as dBi, and it's the standard used by most modeling programs including *EZNEC-ARRL*. To find the gain of an array relative to a single element or other reference antenna such as a dipole, model both the array and the single element or other reference antenna in the same environment and subtract their dBi gains. Don't rely on some assumption about the gain of a single element—many people assume values that can be very wrong.

Nulls

Pattern nulls are very often more important to users of phased arrays than gain because of their importance in reducing both man-made and natural interference when receiving. Consequently, a good deal of emphasis is, and should be, placed on achieving good pattern nulls. Unfortunately, good nulls are much more difficult to achieve than gain and they are much more sensitive to array and feed-system imperfections.

As an illustration, consider two elements that each produce a field strength of, say, exactly 1 millivolt per meter (mV/m) at some distance many wavelengths from the array. In the direction in which the fields from the elements are in-phase, a total field of 2 mV/m results. In the direction in which they're out-of-phase, zero field results. The ratio of maximum to minimum field strength of this array is 2/0, or infinity.

Now suppose, instead, that one field is 10% high and the other 10% low—1.1 and 0.9 mV/m, respectively. In the forward direction, the field strength is still 2 mV/m, but in the canceling direction, the field will be 0.2 mV/m. The front-to-back ratio has dropped from infinity to 2/0.2, or 20 dB. (Actually, slightly more power is required to redistribute the field strengths this way, so the forward gain is reduced—but by only a small amount, less than 0.1 dB.) For most arrays, unequal fields from the elements have a minor effect on forward gain, but a major effect on pattern nulls. This is illustrated by ***EZNEC* Example: Nulls** in Appendix A.

Even with perfect current balance, deep nulls aren't assured. **Fig 13** shows the minimum spacing required for total field reinforcement or cancellation. If the element spacing isn't adequate, there may be no direction in which the fields are completely out-of-phase (see curve B of Fig 13). Slight physical and environmental differences between elements will invariably affect null depths, and null depths will also vary with elevation angle.

However, a properly designed and fed array can produce very impressive nulls. The key to producing good nulls, like producing gain, is controlling the strengths and phases of the fields from the elements. Just how to accomplish that is the subject of most of the remainder of this section. But be sure to keep in mind that producing good nulls is generally a much more difficult task than producing approximately the predicted gain.



Fig 13—Minimum element spacing required for total field reinforcement, curve A, or total field cancellation, curve B. Total cancellation results in pattern nulls in one or more directions. Total reinforcement does not necessarily mean there is gain over a single element, as the effects of loss and mutual coupling must also be considered.

Mutual Coupling

Mutual coupling was discussed briefly earlier in this chapter. Because it has an important and profound effect on both the performance and feed system design of phased arrays, it will be covered in greater depth here.

Mutual coupling refers to the effects which the elements in an array have on each other. Mutual coupling can occur intentionally or entirely unintentionally. People with multiple antennas on a small lot (or car top) often discover that a better description of their system is a single antenna with multiple feed points. Current is induced in conductors in various antennas by mutual coupling, causing them to act like parasitic elements, which re-radiate and distort the antenna's pattern. The effects of mutual coupling are present whether or not the elements are driven.

Suppose that two driven elements are many wavelengths from each other. Each has some voltage and current at its feed point. For each element, the ratio of this voltage to current is the element self-impedance. If the elements are brought close to each other, the current in each element will change in magnitude and phase because of coupling with the field from the other element. The field from the first element changes the current in the second. This changes the field from the second, which alters the current in the first, and so forth until an equilibrium condition is reached in which the currents in all elements (hence, their fields) are totally interdependent.

The feed-point impedances of all elements also are changed from their values when far apart, and all are dependent on each other. In a driven array, the changes in feed-point impedances can cause additional changes in element currents, because the operation of many feed systems depends on the element feed-point impedances. Significant mutual coupling occurs at spacings as great as a wavelength or more.

Connecting the elements to a feed system to form a driven array does not eliminate the effects of mutual coupling. In fact, in many driven arrays the mutual coupling has a greater effect on antenna operation than the feed system does. All feed-system designs must account for the impedance changes caused by mutual coupling if the desired current balance and phasing are to be achieved.

Several general statements can be made regarding the effects of mutual coupling on phased-array systems.

1) The resistances and reactances of all elements of an array generally will be substantially different from the values when the elements are isolated (that is, very distant from other elements).

2) If the elements of a two-element array are identical and have equal currents that are in-phase or 180° out-of-phase, the feed-point impedances of the two elements will be equal. But they will be different than for an isolated element. If the two elements are part of a larger array, their impedances can be very different from each other.

3) If the elements of a two-element array have currents that are neither in-phase (0°) nor out-of-phase (180°), their feed-point impedances will not be equal. The difference will be considerable in typical amateur arrays.

4) The feed-point resistances of the elements in a closely spaced, 180° out-of-phase array will be very low, resulting in poor efficiency due to ohmic losses unless care is taken to minimize loss. This is also true for any other closely spaced array with significant predicted gain.

It's essential to realize that this is *not* a minor effect and one that can be overlooked or ignored. See ***EZNEC*** **Example—Mutual Coupling** in Appendix A for an illustration of these phenomena.

Loss Resistance, Mutual Coupling and Antenna Gain

Loss reduces the effects of mutual coupling because the feed-point impedance change resulting from mutual coupling is effectively in series with loss resistance. If the loss is great enough, two important results occur. First, the feed-point impedance becomes independent of the presence of nearby current-carrying elements. This greatly simplifies feed system design—the simple "phasing-line" or hybrid-coupler feed system described below is adequate *provided that all elements are physically identical and the feed point of each element is matched to the* Z_0 *of the feed line and, if used, the hybrid coupler.*

The impedance matching restrictions are necessary to insure that the phasing line or hybrid coupler performs as expected. Identical elements are needed so that equal element currents will result in equal fields from the elements.

In the absence of mutual coupling effects, the maximum gain of an array of identical elements relative to a single (similarly lossy) element is simply 10 log(N), where N is the number of elements—providing that spacing is adequate for the fields to fully reinforce in some direction. If spacing is less, maximum gain will also be less. Of course, the array gain relative to a single *lossless* element will be very low, most likely a sizeable negative number when expressed in dB. So intentionally introducing loss isn't a wise idea for a transmitting array. It is sometimes an advantageous thing to do for a receiving array, however, as explained in the following section.

High-gain close-spaced arrays, such as the W8JK phased array (see *EZNEC-ARRL* example file **ARRL_W8JK.EZ** and accompanying Antenna Notes file), and most parasitic arrays depend heavily on mutual coupling to achieve their gain. Introduction of any loss to these arrays, which reduces the mutual coupling effects, has a profound effect on the gain. Consequently, parasitic or close-spaced driven arrays often produce disappointing results when made from grounded vertical elements unless each has a fairly elaborate (and therefore very low-loss) ground system.

If you place two low-loss elements very close together and feed them in-phase, mutual coupling reduces the array gain to essentially that of a single element, so there's no advantage to this configuration over a single element. However, if you have a single lossy element, for example a short vertical having a relatively poor ground system, you can improve the gain by up to 3 dB by adding a second, close spaced, element and ground system and feeding the two in-phase. Another way to look at this technique is that you're putting two equal ground system resistances in parallel, which effectively cuts the loss in half. The gain you can realize in practice depends on such things as the ground system overlap, but it might be a practical way to improve transmitting array performance in some situations.

FEEDING PHASED ARRAYS

The previous section explains why the fields from the elements must be very close to the ratios required by the array design. Since the field strengths are proportional to the currents in the elements, controlling the fields requires controlling the element currents. Since the desired current ratio is 1:1 for virtually all two-element and for most (but not all) larger amateur arrays, special attention is paid to methods of assuring equal element currents. But we will examine other current ratios also.

The Role of Element Currents

The field from a conductor is proportional to the current flowing on it. So if we're to control the relative strengths and phases of the fields from the elements, we have to control their currents. We usually do this by controlling the currents at the element feed points. But because the field from an element depends on the current everywhere along the element, elements having identical feed-point currents will produce different fields if they have different current distributions—that is, if the way the current varies along the lengths of the elements is different.

A previous section explained that mutual coupling alters the current distribution, so in many arrays the current distributions will be different on the elements and consequently the relationship between the overall fields won't be the same as that between the feed-point currents. Fortunately, this effect is relatively minor in thin, λ/4 monopole or λ/2 dipole elements. The most common arrays are made from elements in this category, so we can generally get very nearly the desired ratio of fields by effecting the same ratio of feed point currents. Exceptions are detailed immediately below.

Feed-point vs Element Current

For most antennas, environmental factors are likely to cause greater performance anomalies than current distribution differences, and both can be corrected with minor feed system adjustments. The difference between field and feed-point current ratios can become very significant, however, if the elements are very fat and/or close to λ/2 (monopole) or 1 λ (dipole) long. In those cases, most of the feed systems described here won't produce the desired field ratios without major adjustment or modification, except in the special cases of 2-element arrays with identical elements having feed point currents in-phase or 180° out-of-phase. In those special cases, the element current distributions are the same for the same reason the feed-point impedances are equal. This is explained later in the feed system sections.

To get an idea of just how large an element must be to disturb the pattern of an array with correct feed-point currents, a two-element cardioid array of quarter wave vertical elements was modeled at 10 MHz. With thin, 0.1-inch diameter elements, the front/back ratio was 35 dB, the very small reverse lobe caused by slightly unequal element current distributions. Increasing the element diameter to 20 inches decreased the front/back ratio to 20 dB. Returning the front/back ratio of the array of 20-inch elements to >35 dB required changing the feed-point current ratio from the nominal value of 1.0 at an angle of 90° to 0.88 at 83°.

The same array was first modeled with 0.1 inch diameter elements, where it has a front/back ratio of 35 dB, then the elements were lengthened. The front/back ratio dropped to 20 dB at an element length of 36 feet, or about 0.37 λ. In that case, adjustment of the feed-point current ratio to about 0.9 at about 83° restored a good front/back ratio.

In the discussion and development which follow, the assumption is made that the fields will be very nearly proportional to the feed-point currents. If the elements are fat or long enough to make this assumption untrue, some adjustment of feed-point current ratio will be necessary to achieve the desired pattern, particularly nulls. Most feed systems can be designed for any current ratio. Modeling will reveal the ratio required for the desired pattern, and then the feed system can be designed accordingly.

COMMON PHASED-ARRAY FEED SYSTEMS

This section will first describe several popular approaches to feeding phased arrays that often don't produce the desired results. It will describe why they don't work as well as hoped. It also briefly discusses systems that could be used, but that often aren't appropriate or optimum for amateur arrays.

This will be followed in the next section by detailed descriptions of array feed systems that *do* produce the predicted element current ratios and array patterns.

The "Phasing-Line" Approach

For an array to produce the desired pattern, the element currents must have the required magnitude and the required phase relationship. As explained above, this can generally be achieved well enough by causing the feed point currents to have that same relationship.

On the surface, this sounds easy—just make sure that the difference in electrical lengths of the feed lines to the elements equals the desired phase angle. Unfortunately, this approach doesn't necessarily achieve the desired result. The first problem is that the phase shift through the line is not equal to its electrical length. The current (or, for that matter, voltage) delay in a transmission line is equal to its electrical length in only a few special cases—cases which don't exist in most amateur arrays! The impedance of an element in an array is frequently very different from the impedance of an isolated element and the impedances of all the elements in an array can be different from each other.

See the ***EZNEC* Example—Mutual Coupling** in Appendix A for a graphic illustration of the effect of mutual coupling on feed-point impedance. Also look at the Four-Square array example in the **Phased Array Design Examples** section. The array in that example has one element with a *negative* feed-point resistance, if ground loss is low. Without mutual coupling, the resistance of that same element would be about 36 Ω plus ground loss.

Because of mutual coupling, the elements seldom provide a matched load for the element feed lines. The effect of mismatch on phase shift can be seen in **Fig 14**. Observe what happens to the phase of the current and voltage on a line terminated by a purely resistive impedance that is lower than the characteristic impedance of the line (Fig 14A). At a point 45° from the load the current has advanced less than 45°, and the voltage more than 45°. At 90° from the load both are advanced 90°. At 135° the current has advanced more and the voltage less than 135°. This apparent slowing down and speeding up of the current and voltage waves is caused by interference between the forward and reflected waves. It occurs on any line that is not terminated with a pure resistance equal to its characteristic impedance. If the load resistance is greater than the characteristic impedance of the line, as shown in Fig 14B, the voltage and current exchange angles. Adding reactance to the load causes additional phase shift. The *only cases in which the current (or voltage) delay is equal to the electrical length of the line are*

1) When the line is flat; that is, terminated in a purely resistive load equal to its characteristic impedance;

2) When the line length is an integral number of half wavelengths;

3) When the line length is an odd number of quarter wavelengths and the load is purely resistive; and

4) When other specific lengths are used for specific load impedances.



Fig 14—Resultant voltages and currents along a mismatched line. At A, R less than Z_0, and at B, R greater than Z_0.

Just how much phase error can be expected if two feed lines are simply hooked up to form an array? There is no simple answer. Some casually designed feed systems might deliver satisfactory results, but most will not. See the ***EZNEC* Example—"Phasing-Line" Feed** in Appendix A for the typical consequences of using this sort of feed system.

A second problem with simply connecting feed lines of different lengths to the elements is that the lines will change the *magnitudes* of the currents. The magnitude of the current (or voltage) out of a line does not equal the magnitude into that line, except in cases 1, 2 and 4 above. The feed systems presented later in this chapter assure currents that are correct in both magnitude and phase.

The elementary phasing-line approach *will* work in three very special but common situations. If the array consists of only two identical elements and those elements are fed in-phase, mutual coupling will modify the element impedances, but both will be modified exactly the same amount. Consequently, if the two elements are fed through equal-length transmission lines, the lines will transform and delay the currents by the same amount and result in equal, in-phase currents at the element feed points.

Similarly, an array of two identical elements fed 180º out-of-phase will have the same feed-point impedances and can be fed with two lines of any length so long as one line is an electrical half wavelength longer than the other. But this can't be extended to any two elements in a larger array, since mutual coupling to the other elements can result in different feed-point impedances. Methods will be described later which do assure a correct current ratio in this situation.

The third application in which the phasing-line approach works is in receiving arrays where the elements are very short in terms of wavelength and/or very lossy. In either of these cases, mutual coupling between elements is much less than an element's self-impedance. This allows the elements to be individually matched to the feed lines, with no significant change taking place when the elements are formed into an array. Under those conditions, the transmission lines can be matched and the lines used as simple delay lines with easily predictable phase shift and with no transformation of current or voltage magnitude other than cable loss. This is discussed in the later section on receiving antennas.

Many arrays *can* be correctly fed with a feed system consisting of only transmission lines, but the technique requires knowledge of the element feed-point impedances in a correctly fed array. Line lengths can then be computed that provide the correct ratio of currents into those particular load impedances. The line lengths generally differ by amount that's considerably different from the element phase angle difference, and appropriate line lengths can't always be found for all arrays. This technique is described more fully in the **"The Simplest Phased Array Feed System—That Works"** section later in the chapter and illustrated in the examples in **Phased Array Design Examples**.

The Wilkinson Divider

The *Wilkinson divider*, sometimes called the *Wilkinson power divider*, was once heavily promoted as a means to distribute power among the elements of a phased array. While it's a very useful device for other purposes, it won't produce the desired current ratios in antenna elements. In most phased arrays, element feed-point resistances are different and therefore require different amounts of power to achieve the desired equal magnitude currents. (See the section on mutual coupling above.) A Wilkinson divider is intended to deliver equal powers, not currents, to multiple loads. And it won't even do that when the load impedances are different.

The Hybrid Coupler

Hybrid couplers are promoted as solving the problem of achieving equal magnitude currents with a 90º phase difference between elements. Unfortunately, they provide equal magnitude, quadrature (90° phased) currents only when the load impedances are equal and correct. And this simply isn't true of arrays with quadrature-fed elements, except for arrays consisting of short and/or lossy elements, usually suitable only for receiving. In those arrays, the hybrid coupler can be useful for the same reasons as the phasing-line approach, discussed in an earlier section.

At the time of this writing, hybrid couplers are being used in a popular commercial product for phasing at least one type of array. Reports are that it works satisfactorily. However, this shouldn't be taken as proof that the hybrid coupler forces equal magnitude 90º phased currents in loads of arbitrary impedances. No passive network, including the hybrid coupler, is capable of doing that. See **The "Magic Bullet"** below for more information.

Large Array Feed Systems

The author once worked on a radar system where the transmit array consisted of over 5,000 separate dipole elements and the receive array over 4,000 pairs of crossed dipoles, all over a metal reflecting plane, which was the sloping side of a 140 foot high building. In such large arrays, each element is in essentially the same environment as every other element except near the array edges, so almost all elements have very nearly the same feed-point impedance. While producing the phase shifts and magnitude tapers is a considerable mathematical challenge, the problem of unequal element feed-point impedances can largely be ignored. Consequently, feed methods for these large arrays are generally not suitable for typical amateur arrays of a few elements.

The Broadcast Approach

Networks can be designed to transform the element base impedances from their values in an excited array to, say, 50 Ω resistive. Then another network can be inserted at the junction of the feed lines to properly divide the power among the elements (not necessarily equally!). And finally, additional networks must be added to correct for the phase shifts and magnitude transformations of the other networks. This general approach is used by the broadcast industry, in installations that are typically adjusted only once for a particular frequency and pattern.

Although this technique can be used to correctly feed any type of array, design is difficult and adjustment is tedious, since all adjustments interact. When the relative currents and phasings are adjusted, the feed-point impedances change, which in turn affect the element currents and phasings, and so on. A further disadvantage of using this method is that switching the array direction is generally impossible. Information on applying this technique to amateur arrays can be found in Paul Lee's book, listed in the Bibliography.

The "Magic Bullet"

For about 15 years prior to this writing, this *Antenna Book* section has contained a specification for a hypothetical passive circuit that would provide equal-magnitude, 90° phased currents into two loads without respect to the load impedances. This would be a circuit to which we could connect any two elements and guarantee that they'd have exactly the correct currents.

Along with the specifcation was a request that any person knowing of such a circuit would contact the author (Roy Lewallen, W7EL) or the book editors. During this time, only a single response was received, in 1996. It was from Kevin Schmidt, W9CF, who has formulated a mathematical proof that such a circuit—in fact, one resulting in any relative phase other than 0º or 180º—*cannot exist* if restricted to reciprocal elements. (That is, it can't exist unless directional components such as ferrite circulators are used.) This means that, in order to design a network to feed elements at any other phase angle other than 0 or 180º, we *must* know the impedance of at least one element, and correct feed system operation depends on that impedance. There's no way around this requirement. At the time of this writing, Schmidt's proof can be found at **fermi.la.asu.edu/w9cf/articles/magic/index.html**.

RECOMMENDED FEED METHODS FOR AMATEUR ARRAYS

The following feed methods are able to produce element feed-point currents having a desired magnitude and phase relationship, resulting in desirable and predictable patterns. Most methods require knowing the feed-point impedance of one or more array elements *when the array element currents are the correct values*. This isn't possible to measure directly, because if the element currents were correct, the feed system would already be working properly and no further design would be necessary.

By far the easiest way to get this information, if possible, is by computer modeling. Modeling programs such as *EZNEC-ARRL* (included on the CD in the back of this book) allow you to construct an ideal array with perfect element currents, then look at the resulting feed-point impedances. Because of its simplicity and versatility, this approach is highly recommended and it's the one used for the array design examples in this chapter.

Some feed systems allow adjustment, so even an approximate result provides an adequate starting point on which to base the feed-system design. There are several other alternatives to computer modeling. One is to first eliminate the effects of coupling of the element to be measured from all other elements, usually by open circuiting the feed points of the other elements. Then the feed-point impedance of the element is measured. Next, the impedance change due to mutual coupling from all other elements has to be calculated, based on the intended currents in the other elements, their lengths and their distances from the element being measured. Mutual impedance (which is not the same as the impedance *change* due to mutual coupling) between each pair of elements must be known for this calculation and it can be determined by measurement, calculation or from a graph.

The latter two methods are possible only for the simplest element types and measurement is very difficult to do accurately because it involves resolving very small differences between two relatively large values. Accuracy of a calculated result will be reduced if any elements are relatively fat (that is, they have a large diameter, because this impacts the current distribution) or they aren't perfectly straight and parallel.

So the only situations where you're likely to get good results from approaches other than modeling are the very easiest ones to model! And modeling allows determination of the feed-point impedances of many antennas that areimpossible to calculate by manual or graphical methods. Therefore, the manual approach isn't discussed or used here. Appendix B, on the CD, contains equations and manual techniques from previous editions of *The ARRL Antenna Book,* for those who are interested. You can also find a great deal of additional information in many of the texts listed in the Bibliography, particularly Jasik and Johnson.

Current Forcing with λ/4 Lines—Elements In-Phase or 180° Out-of-Phase

The feed method introduced here has been used in its simplest form to feed television receiving antennas and other arrays, as presented by Jasik, pages 2-12 and 24-10 or Johnson, on his page 2-14. However, until first presented in *The ARRL Antenna Book*, this feed method was not widely applied to amateur arrays.

The method takes advantage of an interesting property of λ/4 transmission lines. (All references to lengths of lines are electrical length and lines are assumed to have negligible loss.) See **Fig 15**. The magnitude of the *current out* of a λ/4 transmission line is equal to the *input voltage* divided by the characteristic impedance of the line. This is independent of the load impedance. In addition, the phase of the output current lags the phase of the input voltage by 90°, also independent of the load impedance. These properties can be used to advantage in feeding arrays with certain phase angles between elements.


$I_{OUT} = -j\ \frac{V_{IN}}{Z_0}$
$I_{OUT} = -j\ \frac{V_{IN}}{Z_0}$
λ/4, Z_0
λ/4, Z_0
V_{IN}
Any Z
Any Z
ANT0312

Fig 15—A useful property of λ/4 transmission lines; see text. This property is utilized in the "current-forcing" method of feeding an array of coupled elements.

If any number of loads are connected to a common driving point through λ/4 lines of equal impedance, the currents in the loads will be *forced* to be equal and in-phase, regardless of the load impedances. So any number of in-phase elements can be correctly fed using this method, regardless of how their impedances might have been changed by mutual coupling. Arrays that require unequal currents can be fed through λ/4 lines of unequal impedances to achieve other current ratios.

The properties of λ/2 lines also are useful. Since the current out of a λ/2 line equals the input current shifted 180°, regardless of the load impedance, any number of half wavelengths of line may be added to the basic λ/4, and the current and phase forcing property will be preserved. For example, if one element is fed through a λ/4 line and another element is fed from the same point through a 3λ/4 line of the same characteristic impedance, the currents in the two elements will be forced to be equal in magnitude and 180° out-of-phase, regardless of the feed-point impedances of the elements.

If an array of two, and only two, identical elements is fed in-phase or 180° out-of-phase with equal magnitude currents, both elements have the same feed-point impedance. The reason is that each element sees exactly the same thing when looking at the other. In an in-phase array, each sees another element with an identical current; in an out-of-phase array, each sees another element with an equal magnitude current that's 180° out-of-phase, the same distance away in both cases. This isn't true in something like a 90° fed array, where one element sees another with a current leading its current by 90°, while the other sees another element with a lagging current.

With arrays fed in-phase or 180° out-of-phase, feeding the elements through equal lengths of feed line (in-phase) or lengths differing by 180° (out-of-phase) will lead to the correct current magnitude ratio and phase difference, regardless of the line length and regardless of how much the element feed-point impedances depart from the lines' Z_0.

Unless the feed-point impedances equal the line Z_0 or the lines are an integral number of half wavelengths long, the magnitudes of the currents out of the lines will not be equal to the input magnitudes, and the phase will not be shifted an amount equal to the electrical lengths of the lines. But both lines will produce the same transformation and phase shift because their load impedances are equal, resulting in a properly fed array. In practice, however, feed-point impedances of elements frequently are different even in these arrays, because of such things as different ground systems (for ground mounted vertical elements), proximity to buildings or other antennas, or different heights above ground (for horizontal or elevated vertical elements).

In many larger arrays, two or more elements must be fed either in-phase or out-of-phase with equal currents, but coupling to other elements can cause their impedances to change unequally—sometimes extremely so. Using the current-forcing method allows the feed system designer to ignore all these effects, while guaranteeing equal and correctly phased currents in any combination and number of 0° and 180° fed elements.

This method is used to develop feed systems for the Four Square and 4-element rectangular arrays in the **Practical Array Design** section. The front and rear elements of a Four-Square antenna provide a good example of elements having very different feed-point impedances that are forced to have equal out-of-phase currents.

"The Simplest Phased Array Feed System—That Works"

This is the title of an article in *The ARRL Antenna Compendium, Vol 2*, which describes how arrays can be fed with a feed system consisting of only transmission lines. (The article is available for viewing at **eznec.com/Amateur/Articles/Simpfeed.pdf** and is also on the CD included in the back of this book, along with the program *Arrayfeed1*, which solves the equations presented in the article.)

As explained earlier in the Phasing Line section, this method requires knowing what the element feed-point impedances will be in a correctly fed array. Feed-line lengths can then be computed, for most but not all arrays. These lengths will produce the desired current ratio in array elements that do present those feed-point impedances. If you know the load impedances connected to transmission lines whose inputs are connected to a common source, it's simple to calculate the resulting load currents for any transmission line lengths. However, the reverse problem is much more difficult; that is, given the load impedances and desired currents to calculate the required cable lengths.

One way to solve the problem is to choose some feed-line lengths, solve for the currents, examine the answer, adjust the feed-line lengths, and try again until the desired currents are obtained. The author used this iterative approach, using first a programmable calculator and later a computer, for some time before developing a direct way of solving for the transmission-line lengths. The direct solution method is described briefly in the *Compendium* article.

Fig 16 shows the basic so-called "simplest" system applied to a two element array. Although it resembles an elementary phasing-line system as described earlier, the critical difference is that the lengths of Lines 1 and 2 are calculated to provide the correct current relative magnitude transformation and phase shift when terminated with the actual feed-point impedances.



Fig 16—"Simplest" feed system for 2-element array. No matching or phasing network is used here, only transmission lines.

The advantage to using this "simplest" feed system is indeed its simplicity. It's no more complicated than the elementary phasing-line approach but actually works as planned. The disadvantage over some other methods is that there's no convenient adjustment to compensate for environment factors, array imperfections or inaccurately known feed-point impedances.

Also, while unusual, it's possible that no suitable feedline lengths can be found for some arrays, or at least none with practical feed-line characteristic impedances. The difference in electrical feed-line lengths almost never equals the difference in phase angles between element currents. This is because of the different line delays resulting from different feed-point impedances.

Program *Arrayfeed1*, included on the CD included with this book, can do the calculations for any two elements (alone or in a larger array), a Four-Square array or a rectangular array in which two in-phase elements are driven at any current magnitude and phase relative to the other two in-phase elements. These possibilities cover a large number of common arrays.

Arrayfeed1 can also be applied to other types of arrays using the method described in the **Feeding Larger Arrays** section in Appendix B (on the CD). The required knowledge of element feed-point impedances in a correctly fed array can be obtained using *EZNEC-ARRL*, also included on the CD. Examples of the design of a "simplest" feed system for several different arrays using *EZNEC-ARRL* and *Arrayfeed1* can be found in the **Phased Array Design Examples** section.

When a solution is possible for a given choice of line characteristic impedances, a second solution with different lengths is always available. See the comments in the introductory part of the **Phased Arrray Design Examples** section about choosing the solution to use.

An Adjustable L-Network Feed System

Adjustment of the current ratio of any two elements requires varying two independent quantities; for example the magnitude and phase of the current ratio. Two degrees of freedom—adjustments that are at least partially independent—are required. The "simplest" all-transmission line feed system described earlier adjusts the lengths of the two transmission lines to achieve the correct ratio.

But if the antenna characteristics aren't well known—for example, if the ground resistance isn't known even approximately—then the initial "simplest" design won't be optimum and adjustment can be difficult and tedious. The current-forcing method produces correct currents independently of the element characteristics, so it doesn't require adjustment as long as the elements are identical. But it's suitable only for feeding elements in-phase or 180° out-of-phase and a few fixed current-magnitude ratios.

The addition of a simple network as shown in **Fig 17** allows you to easily adjust feeding of element pairs at other relative phase angles and/or magnitude ratios. Any desired current ratio (magnitude and phase) can be obtained with two elements fed with any lengths of wire, equal or unequal, by adding a network.

However, calculations for the general case are complex. The problem becomes much simpler if the transmission lines are restricted to lengths of odd multiples of λ/4, forming a modified "forcing" system that includes an added network. There are at least three additional advantages of this scheme. One is that a λ/4 line is easy to measure, even if the velocity factor isn't known. This is described in the **Practical Aspects of Phased Array Design** section.

Second is that the feed system becomes completely insensitive to the feed-point impedance of one of the two elements. And the third is that the transmission lines of "forcing" systems feeding groups of elements in larger arrays can be used in place of the normal λ/4 lines. This greatly simplifies both the design of feed systems for larger arrays and the feed systems themselves. Note that both lines can be changed to 3λ/4 if necessary to span the physical distance between elements, but *both* lines must be the same 3λ/4 length.



Fig 17— The addition of a simple L-network to Fig 16 allows you to easily adjust feeding of element pairs at other relative phase angles and/or magnitude ratios.

This basic feed method can be used for any pair of elements, or for two groups of elements having forced equal currents. (See **Feeding Four Element and Larger Arrays** below.) Many networks can accomplish the desired function, but a simple L network is adequate for most feed systems. The network can be designed to produce a phase lead or phase lag. The basic two-element L-network feed system is shown in Fig 17. Many variations of this general method can be used, but the equations, program, and method to be discussed here apply only to the feed system shown.

If the phase angle of I_2/I_1 is negative (element 2 is lagging element 1), the L network will usually resemble a low-pass network (X_{ser} is an inductor and X_{sh} is a capacitor). But if the phase angle is positive (element 2 lagging element 1), the L network will resemble a high-pass network (X_{ser} is a capacitor and X_{sh} is an inductor). However, some current ratios and feed-point impedances could result in both components being inductors or both being capacitors.

If it's desired to maintain symmetry in the feed system, X_{ser} can be divided into two components, each being inserted in series with a transmission line conductor. If X_{ser} is an inductor, the new components will each have half the value of the original X_{ser}, as shown in **Fig 18**. If X_{ser} is a capacitor, each of the new components will be twice the original value of X_{ser}.

Because of the current-forcing properties of λ/4 lines, we need to make the ratio of *voltages* at the inputs of the lines equal to the desired ratio of *currents* at the output ends of the lines; that is, at the element feed points. The job of the L network is to provide the desired voltage transformation. If the output-to-input voltage ratio of the network is, say, 2.0 at an angle of –60°, then the ratio of element currents (I_2/I_1)



Fig 18—Symmetrical feed system similar to Fig 17, where feed network is split into two symmetrical parts.

will be 2.0 at an angle of –60°. The voltage transformation of the network is affected by the impedance of element 2, but not by the impedance of element 1. So only the impedance of element 2 must be known to design the feed system.

Equations for designing the L network are given in Appendix B, but the program *Arrayfeed1* is included on the CD to make it unnecessary to solve them. The feed-point impedance of the lagging element or group of elements must be known in order to design the network. This can best be determined by modeling the array with *EZNEC-ARRL*. The impedance can be manually calculated for some simple element and array types by using the equations in Appendix B, but those same types of element and array are simple to model.

Examples of the design of L-network feed systems for several different arrays using *EZNEC-ARRL* and *Arrayfeed1* can be found in the **Phased Array Design Examples** section. A similar application of this feed system and a spreadsheet program for calculation was developed by Robye Lahlum, W1MK, and described in *Low-Band DXing* (see the Bibliography). *Arrayfeed1* can be used for the applications of the feed system described in that book if desired.

Additional Considerations

Feeding 4-Element and Larger Arrays

Both the simplest and L-network feed systems described above can be extended to feeding larger arrays having two groups of elements in which all the elements in a group are in-phase or 180° out-of-phase with each other—basically, any group that can be fed with the current-forcing method. The elements in each group are connected to a common point with λ/4 or 3λ/4 lines to force the currents to be in the correct ratio within the group. Then the "simplest" or L-network feed system can be used to produce the correct phasing between the two groups, just as it does between two individual elements.

Two common arrays that fit this description are the Four Square and the 4-element rectangular array. But more elaborate arrays could be constructed and fed using this method, such as a pair of binomial arrays. (A single binomial array is described in the **Phased Array Design Example** section below.) The *Arrayfeed1* program incorporates additional calculations necessary for designing Four Square and 4-element rectangular arrays. The general procedure for adapting the feed methods to other larger arrays can be found in Appendix B.

What If the Elements Aren't Identical?

Getting the desired pattern requires getting the correct relative magnitude and phase of the *fields* from the elements. If the elements are identical, which we've generally assumed up to this point, then producing currents of the desired magnitude and phase will create the desired fields (neglecting mutual coupling current distribution effects, discussed elsewhere).

But what if the elements aren't identical? Fortunately, the feed systems described here can still be used for any 2-element array and some more complex arrays, provided that the system can be accurately modeled. But a slightly different approach is required than for identical elements.

The first step is to model the array with a current source at the feed point of each element. Next, the magnitudes and phases of the model source currents are varied until the desired pattern is achieved. Then the ratio of feed-point (source) currents is calculated and this value, along with the feed-point impedances reported by the model, are used for the feed system design. The feed system will produce the same ratio of currents as the model, resulting in the same pattern.

In general, this approach won't work with shunt fed towers or gamma-fed elements because of the difficulty of accurately modeling those structures. See **Shunt and Gamma Fed Towers and Elements** for more information.

Shunt and Gamma Fed Towers and Elements

In a shunt, gamma, or similarly fed tower or element, the feed-point current isn't the same as the main current flowing in the element. The ratio between the feed-point current and element current isn't a constant, but depends on a number of factors. The ratio of currents in shunt or gamma fed elements are typically different—often vastly different—from the currents at the feed points. This complicates the design of feed systems for arrays of these elements.

An even more limiting problem is that the feed-point impedances are difficult to determine. The feed-point impedances of one or more elements in a properly fed array must be known in order to design a feed system for anything but

2-element in-phase or 180° out-of-phase arrays.

The only practical way to get this information for a shunt or gamma fed array is by modeling an array having the desired element currents. But Cebik has pointed out ("Two Limitations of NEC-4"—see the Bibliography) that many common antenna analysis programs, including *EZNEC-ARRL*, have difficulty accurately modeling folded dipoles with unequal diameter wires. The same problem applies to shunt and gamma-fed elements when the element diameter is significantly different from the diameter of the shunt or gamma feed wire. Without accurate feed-point impedances, feed systems can't be designed to work without adjustment. It might be possible to get reasonably accurate results from a *MININEC*-based modeling program, but there are a number of issues which must be given great care when using one. (See Lewallen, "*MININEC*—The Other Edge of the Sword," listed in the Bibliography.)

If such a *MININEC* program is available, you would have to model the complete array including feed system, with sources at the normal feed points in the shunt or gamma wires. Next, you would have to adjust the magnitudes and phases of the sources to produce the desired pattern. The reported source impedances and currents would be the ones you would use to design the feed system. It's likely that some adjustment would be necessary, so an adjustable system such as the L-network feed system described later would be best.

Loading, Matching and Other Networks

Adding a component such as a loading inductor in series with an element or element feed point won't change the ratio of element current to feed-point current. As a result, a feed system designed to produce a particular ratio of element currents will still function properly if the elements contain series components. The extra feed-point impedance introduced by the loading component(s) must be considered when designing the feed system, however. Similarly, end or top loading won't alter the relationship between feed-point and element current, provided that the current distribution in the elements is essentially the same. (See **Feed-point vs Element Current** in a previous section.)

However, insertion of any *shunt* component, or a network containing a shunt component, *will* alter the relationship between feed-point and element current because it will divert part of the feed-line current that would otherwise flow into the antenna. As a result, a feed system designed to deliver correct currents at the feed points will produce incorrect element currents and therefore an incorrect pattern. Therefore, any components or networks other than a series loading component should be avoided at any place in the feed system on the antenna side of the point at which the feed system splits to go to the various elements.

There are a few exceptions to this rule. If the feed-point impedances of the elements when in the excited array are equal, then identical networks with or without shunt components can be put at the feed points of the elements and the proper element current ratio maintained—so long as the feed system is designed to deliver the proper feed-point current ratio with the networks in place. Equal element impedances occur in arrays having only two identical elements fed in-phase or 180º out-of-phase, or arrays of any number of elements where the elements are electrically short and/or very lossy.

Baluns in Phased Arrays

For purposes of achieving the correct array pattern, baluns aren't usually required when feeding grounded vertical elements with coaxial cable feed lines. However, a balun might be desirable if current induced onto the outside of the feed line by mutual coupling to the elements is causing RF in the shack. And with arrays of dipole or other elevated elements, baluns can be important to achieve the proper element current ratio, as explained below.

First, however, the general rules for using baluns in phased arrays will be stated. Here, "main feed line" means the feedline going from the transmitter or receiver to the common point where the system splits to feed the various elements. "Phasing-system lines" means any transmission lines between that common point and any element. The rules:

- **Rule 1:** A balun or baluns (more specifically, a current, sometimes called a choke balun) should be used as necessary to suppress unbalanced current on the main feed line. This usually isn't required when feeding grounded elements with coaxial feed line from an unbalanced rig or tuner. Unbalanced current can occur on either coax or parallel-conductor line.

"Baluns: What They Do and How They Do It", listed in the Bibliography, describes conducted-imbalance (common-mode) currents. Imbalance can also be caused by mutual coupling to the array elements. Common-mode currents have at least two undesirable effects on array performance. First, the imbalance current can flow from the main feed line to the phasing system lines, not necessarily splitting in the right proportion to maintain the correct element current ratio. This can affect the array pattern. In practice, however, this effect is likely to be small unless the common-mode current is unusually large. Even a small common-mode current, however, results in main feed-line radiation, and even a small amount of radiation can significantly degrade array pattern nulls. Any type of current balun can be used on the main feed line, at any place along the line, without any effect on the array pattern except to the extent that it reduces common mode current.

- **Rule 2:** No balun or any other component or network should be inserted in any phasing system line that will alter the line length or characteristic impedance. This means that baluns in phasing system lines must be of a type made from the phasing line itself. Options are the W2DU type balun, consisting of ferrite cores placed along the outside of the feed line; an air-core balun made by winding part of the line into an approximately self-resonant or otherwise high-impedance coil; or winding part of the line onto a ferrite core or rod to make a several-turn winding. When coaxial cable is used, the feed system characteristics are dictated by the inside of the cable. Any cores or winding of the outside prevents common-mode current on the outside, but otherwise have no effect on the phasing performance. This rule applies equally to parallel wire line, where the balun affects only common-mode current (equivalent to current on the outside of coax) while the phasing performance depends on differential mode current (equivalent to the current on the inside of coax).

Baluns are important when feeding dipole or other elevated arrays, unless a fully balanced tuner is used. This is because common-mode current represents a diversion of some of the current that should be going to the array elements. The presence of common-mode current means that the element currents are being altered from the desired ratio and therefore the pattern won't as intended. A balun should be placed wherever a path for current exists other than along a parallel-line conductor or on the inside of a coaxial line. Such a path exists, for example, where a coaxial cable connects to a dipole, as shown in Fig 1 of the balun article referenced above. Or a path can exist where a parallel-conductor transmission line connects to an unbalanced tuner or to a coaxial line, as shown in Fig 2 of that article. In both those cases, a path exists for a common-mode current to flow on the outside of the coax cable. A balun creates a high impedance to this current, thereby reducing its magnitude. But remember that all baluns must conform to the rules above.

Fig19 shows recommended balun locations for a coax-fed dipole array using an L-network feed system.



Fig 19—Adding choke baluns to a two-dipole feed system to get rid of common-mode currents radiated onto the coax shields.

Receiving Arrays

While it might not be entirely intuitive, an array designed for a particular gain and pattern for transmitting that considers mutual coupling, element currents, field reinforcement and cancellation, and so forth, will perform exactly the same when receiving. So a receiving array can be designed by approaching the problem as though the array were to be used for transmitting.

However, at HF and below, the system requirements for transmitting and receiving antennas are different, so receiving-only arrays can be designed that aren't suitable for transmitting but are perfectly adequate for receiving in that frequency range. The reason, described in more detail in Chapter 13 of this book, is that at HF and below atmospheric noise is typically much greater than a receiver's internally generated noise. Lowering a receiving antenna's gain and efficiency reduces the signal and atmospheric noise both by the same factor. Because the overall noise is for practical purposes all atmospheric noise, the signal/noise ratio isn't affected by antenna efficiency.

Of course, a point can be reached where the atmospheric noise is so reduced by inefficiency that the receiver itself becomes the dominant source of noise, but this typically doesn't happen until the antenna is extremely inefficient. When transmitting, reduced efficiency lowers the transmitted signal, but it has no effect on the receiving station's noise. So reduced efficiency of a transmitting antenna results in a reduced signal/noise ratio at the receiving end, and consequently should be avoided.

Mutual coupling effects can be minimized by increasing the loss (and therefore reducing the efficiency) of the elements, or by reducing the element sizes to a small fraction of a wavelength. Doing the second without the first isn't usually a good idea because the feed-point impedance tends to change rapidly with frequency for very small elements, making an antenna that works well over only a narrow bandwidth. But increasing loss broadens the bandwidth, even for small elements, as well as reducing mutual coupling effects. So this approach is often taken for designing a receiving-only array. With mutual coupling effects minimized because of loss, feed-system design becomes relatively simple, provided a few simple rules are followed. See **Loss Resistance, Mutual Coupling, and Antenna Gain**, above.

Phased Array Design Examples

This section, also written by Roy Lewallen, W7EL, presents examples of feed-system design for several kinds of array using the design principles given in previous sections. All but the last example array are assumed to be made of λ/4 vertical elements. The last example is for a halfwave-dipole array, which illustrates that exactly the same method can be used for arrays of any shape of elements, including dipole, square (quad) and triangular. Likewise, the methods shown here apply equally well to VHF and UHF arrays. The first example includes more detail than the remaining ones, so you should read it before the others.

General Array Design Considerations

If either the "simplest" feed system (Fig 16) or L-network feed system (Fig 17) is used, the feed-point impedance of one or more elements—*when the array elements all have the correct currents*—must be known. By far the best way to determine this is by modeling. If accurate modeling isn't practical for some reason, an estimation should be made from an approximate model, and you should expect to have to adjust the feed system after building and installing it.

Manual calculation methods for some simple configurations are given in Appendix B (on the CD), but calculation is tedious and, as stated earlier, the configurations for which this method works are the very ones which are easiest to model. *EZNEC-ARRL* (also included on the CD) is used in the following examples to determine feed-point impedance. Space doesn't permit detailed instructions here on creating the models, so they are included in complete form. They should provide a convenient starting point for any variations you might like to try. See the *EZNEC-ARRL* manual (accessed by clicking **Help/Contents** in the main *EZNEC-ARRL* window) for help in using this program.

In the following examples, vertical elements are close to λ/4 high and dipole elements close to λ/2, and their lengths have been adjusted for resonance when all other elements are absent or open circuited. There's actually no need in practice to make the elements self-resonant—it's simply used as a convenient reference point for these examples. You'll also find it interesting to see how much reactance is present at the feed points of the elements when in the arrays, knowing that it's very nearly zero when only one element is present.

In any real grounded vertical array, there is ground loss associated with each element. The amount of loss depends on the length and number of ground radials, and on the type and wetness of the ground under and around the antenna. This resistance becomes part of the feed-point resistance, so it must be included in the model used to determine feed-point impedance. The 90° Fed, 90° Spaced Array example below discusses how this is done. **Fig 20** gives resistance values for typical ground systems, based on measurements by Sevick (July 1971 and March 1973 *QST*). The values of feed system components based on Fig 20 will be reasonably close to correct, even if the ground characteristics are somewhat different than Sevick's.



Fig 20—Approximate ground system loss resistance of a resonant λ/4 ground-mounted vertical element versus the number of radials, based on measurements by Jerry Sevick, W2FMI. Moderate length radials (0.2 to 0.4 λ) were used for the measurements. The exact resistance, especially for only a few radials, will depend on the nature of the soil under the antenna. Add 36 Ω for the approximate feed-point resistance of a thin resonant λ/4 vertical.

Feed systems for the design example arrays to follow are based on the resistance values given below.

Number of Radials	*Loss Resistance, Ω*
4	29
8	18
16	9
Infinite	0

Elevated radial systems also have some ground loss, although it can be considerably less than a system with the same number of buried radials. This loss will be automatically included in the feed-point impedance of a model which includes the elevated radials, so no further estimation is required. Be sure to use Perfect, High-Accuracy ground type when modeling an elevated radial system with *EZNEC-ARRL*. In other *NEC-2* based programs, this might be referred to as Sommerfeld type ground. More information can be found in the *EZNEC-ARRL* manual.

The matter of matching the array for the best SWR on the feed line to the station is not dealt with here, since it's a separate problem from that of the main topic, which is designing feed systems to produce a desired pattern. Some of the simpler arrays provide a match that is close to 50 or 75 Ω, so no further matching is required. However, as shown by program *Arrayfeed1*, many larger arrays present a less favorable impedance for direct connection and will require matching if a low SWR on the main feedline is required. If matching is necessary, the appropriate network should be placed in the single feed line running to the station. Attempts to improve the match by adjustment of the phasing L network, individual element lengths, matching at the element feed points or individual element feeder lengths will usually ruin the current balance of the array. Program *TLW*, included on the CD, can be used for designing an appropriate matching network. Additional information on impedance matching may be found in Chapters 25 and 26 of this book.

Choosing Arrayfeed1 Solutions

When designing a feed system for a two element array, *Arrayfeed1* program allows you to choose the characteristic impedances of the two transmission lines going to the elements, which don't have to be equal, so you have your choice of more than one solution. However, directional array switching is much more difficult if the lines have different impedances, so in general you should use the same characteristic impedances.

For larger arrays, *Arrayfeed1* requires the feed lines to all elements to have the same impedance. In choosing the transmission line impedance values, usually you can simply use convenient impedances. But in general, you should avoid solutions where component reactance (X) values are vastly different (say, more than three times or less than one third as large) as the line characteristic impedances. Such networks will become more critical to adjust, and both the impedance and pattern will change more rapidly with changes in frequency. You can usually avoid this situation by choosing feed-line impedances that are in the same ballpark as the element feed-point impedances. The last example in the Practical Array Design section illustrates this problem and its solution.

When designing a "simplest" feed system, the most broadbanded and least critical system is usually one where the difference in electrical feed-line lengths is closest to the relative element phase angle. Here, "broadbanded" means that the pattern changes less with frequency, not necessarily that the SWR changes less. However, an array that's broadbanded in the pattern sense is usually also relatively broadbanded with respect to SWR.

Arrayfeed1 reports the impedance seen at the main array feed point. While it might be tempting to choose the solution producing the lowest SWR on the main feedline, you'll end up with a less critical and more broadbanded system if you base your choice on the criteria given above, and provide separate impedance matching at the array's main feed point when necessary.

90° Fed, 90° Spaced Vertical Array

This example illustrates the design of both "simplest" and L-network feed systems for a 2-element, 90° spaced and fed vertical array. The first task when using either feed system is to determine the feed-point impedances of the elements when placed in an array having the desired element currents. The "simplest" feed system method requires knowledge of both element impedances, while the L-network system requires you to know only one. Actually, it's equally easy to determine both as it is to find just one, using *EZNEC-ARRL*. (Appendix B contains equations for those interested in manual methods or for more insight as to how the impedances come about.) The first step is to specify the antenna we want. For this example, we'll specify:

- Frequency: 7.15 MHz.
- Two identical, one inch (2.54 cm) diameter, 33 feet (10.06 meter) long elements spaced 90 electrical degrees, with element currents equal in magnitude and 90° apart in-phase.
- 8 buried radial wires, 0.3 λ long, under each element.

A model of this antenna has been created and furnished with *EZNEC-ARRL*. So the next step is to start *EZNEC-ARRL*, click the **Open** button, enter **ARRL_Cardioid_Example** in the text box (or double-click it in the file list) to open example file **ARRL_Cardioid_Example.EZ**.

This *EZNEC* example model uses a *MININEC*-type ground, which is the same as perfect ground when calculating antenna currents and impedances. A real antenna would have some additional resistive loss due to the finite conductivity of the ground system. The only way to model a buried radial ground system with an *NEC-2* based program like *EZNEC* is to create radial wires just above the ground (using the Real, High-Accuracy ground type), because *NEC-2* can't handle buried conductors.

This provides only a moderate approximation of a buried system. Another way to estimate ground-system resistance is to measure the feed-point impedance of a single element, then subtract from that the resistance reported for a model of that element over perfect (or *MININEC*-type) ground. For most uses, however, an adequate approximation can be made by simply referring to the graph of Fig 20. As stated previously, the feed system design depends on the feed-point impedances of the elements, which in turn depend on the ground system resistance. So the ground system resistance must be known, approximately anyway, before designing the feed system. At the end of this example we'll investigate the effect of changes in the ground system or errors in estimating the resistance on the pattern.

For 8 radials, Fig 20 shows the ground system resistance to be about 18 Ω. This is included in the example model as a simple resistive load at the feed point of each element. Click the **Src Dat** button to see the feed-point impedances of the two elements. In this model, Source 1 is at the base of Wire 1 (element 1), and Source 2 is at the base of Wire 2 (element 2). Notice in the **Source Data** display that the Source 1 current has been specified at 1 amp at 0°, and Source 2 is 1 amp at –90°. So the Source 2 element is the lagging element. You should see impedances of 37.53 – *j*19.1 Ω for element 1 and 68.97 + *j*18.5 Ω for element 2. These are the feed-point impedances resulting when the array is ideally fed, with equal magnitude and 90° phased currents. Record these values for use in *Arrayfeed1*.

Click the **FF Plot** button to generate a plot of the azimuth pattern at an elevation angle of 10°. In the 2D Plot Window, open the **File** menu and select **Save Trace As**. Enter **Cardioid_Ideal Feed** in the **File Name** box, then click **Save**. This saves the cardioid pattern plot so you can compare it later to the pattern you get with the transmission line feed system.

Now it's time to design the feed system. Refer to the appropriate subheading below for the design of each of the two kinds of feed systems. Both systems use program *Arrayfeed1* program.

"Simplest" (Transmission Line Only) Feed System

Start *Arrayfeed1*. In the **Array Type** frame, select **Two Element**. In Feed System Type, select **"Simplest."** In the **Inputs** frame, enter the following values:

Frequency MHz = 7.15; Feed-point impedances – Leading Element: R ohms = 37.53, X ohms = –19.1; Lagging Element: R ohms = 68.97, X ohms = 18.5 (these are the element R and X values from *EZNEC-ARRL*). We'll be discussing the array input impedance, so check the **Calc Zin** box near the lower left corner of the main window if it's not already checked.

We're free to choose any transmission-line characteristic impedances we want, so long as we can get cables with those impedances. And the two cables don't have to have the same characteristic impedances. Each choice will lead to a different set of solutions. But sometimes a solution isn't possible, which then requires choosing different line impedances. Let's try 50 Ω for both lines. Enter **50** in both **Z0** boxes.

Finally, enter **1** for the lagging:leading **I Mag**, and **–90** for the **Phase**. Click **Find Solutions**. The result is no solution! So enter **75** into both the line impedance boxes and click **Find Solutions** again. You should now see two sets of results in the **Solutions** frame, electrical lengths of 68.80° and 156.03° for the first solution and 131.69° and 185.00° for the second. (Notice that the difference in length between the two lines isn't 90° for either solution, although the first solution is quite close. It's normal for the feed-line length difference to be different than the phase difference, due to the unequal element feed-point impedances caused by mutual coupling.)

The solution with a line length difference closest to the element phase difference is usually preferable. Also, all else being equal, the solution with shortest lines is better providing that the lines will physically reach the elements. This is because the current magnitude and phase will change less with frequency than for a longer-length solution. However, there might be some cases where the change with frequency luckily compensates for the changing electrical distance between elements, so it's not a bad idea to model both solutions unless you plan on using the antenna over only a narrow frequency range.

In this case, the first solution looks best in all respects. The sum of the two lines in the first solution is about 225 electrical degrees. Assuming the lines have a velocity factor of 0.66, the total length of the lines will be more than 148 physical degrees. Since our two elements are spaced 90 physical degrees apart, the lines will comfortably reach. If they didn't, we could either use the second solution's lengths, use cable with a higher velocity factor or add a half wavelength to both the line lengths in the first solution.

The impedance **Zin** shown by *Arrayfeed1* is the impedance at the input to the feed system, so it's the impedance that will be seen by the main feed line. The second solution provides nearly a perfect match for a 50-Ω transmission line. But the first solution is good for nearly all applications. Also a 50-Ω line connected to the first solution's feed system would have an SWR of only 1.65:1, which wouldn't require any matching under most circumstances. Normal line loss would reduce the SWR even more at the transmitter end of the feed coax.

To find the required physical line lengths, enter the cable velocity factor and make your choice of units in the **Physical Lengths** frame. The design is now complete; all you have to do is cut two lines to the specified lengths and connect one from a common feed point to each element as shown in Fig 16, or the screen capture from *Arrayfeed1* shown in **Fig 21**.

Next, we'll design an L-network feed system for the same array.

L Network Feed System

In *Arrayfeed1*, select **L Network** in the **Feed System Type** frame. The program doesn't need to know the leading element impedance to calculate the L-network values, but it does need it to calculate the array input impedance. If you want to know the impedance, check the **Zin** box at the lower left corner of the main window, otherwise you can uncheck it and the input box for the leading element Z will disappear. The values from the "Simplest" analysis should still be present in the appropriate boxes; if not, refer to the "Simplest" feed system design above and re-enter the values. Again, we'll use 75 Ω for the line impedances, since that gave us a



● Two Element
○ Four Square
○ 4 Element Rectangle

● "Simplest"
○ L Network

Enter Frequency MHz 7.15

Enter feedpoint impedances

Element	R ohms	X ohms
Leading Element	37.53	-19.1
Lagging Element	68.97	18.5

Choose line impedances

Line 1 Z0 75 ohms

Line 2 Z0 75 ohms

Choose lagging:leading I mag, phase

Mag 1 Phase -90 deg

☑ Calc Zin

Electrical Length, Degrees

	1st Soln	2nd Soln
Line 1	68.80	131.69
Line 2	156.03	185.00
Zin	33.94 + j 13.13	50.09 - j 2.11

Velocity Factor .66

Units
○ Meters
○ Millimeters
● Feet
○ Inches
○ Wavelengths

1/4 wavelength 22.698

1/2 wavelength 45.396

3/4 wavelength 68.093

	1st Solution	2nd Solution
Line 1	17.352	33.213
Line 2	39.350	46.656

ANT0992

Fig 21—Screen capture from *Arrayfeed1* program for "Simplest" 2-element phased array shown in Fig 16 and whose feed-point impedances are modeled by *EZNEC-ARRL*.



Array Type
● Two Element
○ Four Square
○ 4 Element Rectangle

Feed System Type
○ "Simplest"
● L Network

Inputs
Enter Frequency MHz 7.15
Enter feedpoint impedances

Element	R ohms	X ohms
Leading Element	37.53	-19.1
Lagging Element	68.97	18.5

Choose line impedances
Line 1 Z0 75 ohms
Line 2 Z0 75 ohms

Choose lagging:leading I mag, phase
Mag 1 Phase -90 deg

Solutions

	X ohms	Value	Comp Type
Xser	81.557	1.815 uH	L
Xsh	-111.452	199.7 pF	C

Zin 31.37 + j 25.94

☑ Calc Zin

Physical Lengths
Velocity Factor .66
Units
○ Meters
○ Millimeters
● Feet
○ Inches
○ Wavelengths
1/4 wavelength 22.698
1/2 wavelength 45.396
3/4 wavelength 68.093

ANT0993

Fig 22—Screen capture from *Arrayfeed1* program for L-network feed system using "current-forcing" properties of λ/4 feed lines.

solution for the "Simplest" feed system. This feed system is more versatile, though, so we could use 50-Ω lines with this feed system if desired.

Click **Find Solution** and see the results in the **Solution** frame. See screen capture in **Fig 22**. With 75-Ω lines, the L network consists of a series inductor of 1.815 µH and a shunt capacitor of 199.7 pF, connected as shown in the diagram in the left part of the program window. To find the physical length of the λ/4 lines, enter the velocity factor and choice of units in the **Physical Lengths** frame.

The main feed-point impedance of 31.37 + *j* 25.94 Ω would result in about a 2.2:1 SWR on a 50-Ω feed line, which would be acceptable for many applications. It could easily be reduced to 1.6:1 by the simple addition of a series capacitor of 25.94 Ω reactance (858 pF) at the main feed point or, of course, reduced to 1:1 with a simple L network or other matching system designed with the *TLW* program.

Pattern Verification and Effect of Loss Resistance—"Simplest" System

EZNEC-ARRL doesn't have the capability to model an L-network, so *EZNEC-ARRL* verification of the pattern and the effect of various modifications can be done only for the "simplest" feed system.

EZNEC model **ARRL_Cardioid_TL_Example.EZ** has been created to model the "simplest" feed system just designed. Open it with *EZNEC-ARRL*. In the View Antenna Display, you can see the transmission lines connecting to the source midway between the antennas. In *EZNEC*, the physical locations of the ends of transmission line models don't have to be the same as the physical locations, so the view isn't a precise representation of what the actual setup would look like. (You can find more about this in **ARRL_Cardioid_TL_Example.txt**, the Antenna Notes file that accompanies example file **ARRL_Cardioid_TL_Example.EZ.**)

Click **FF Plot** to generate a 2D pattern of the antenna. In the 2D Plot Window, open the **File** menu and select **Add Trace**. Select **Cardioid—Ideal Feed** (which you saved earlier) and click **Open**. The added plot overlays perfectly, indicating that the pattern using this feed system is identical to the pattern we got with perfect current sources at each feed point.

To check the feed-point currents, click the **Currents** button. In the resulting table, you can see that **Wire 1 Segment 1** current is 0.56467 A at a phase of –56.73° and **Wire 2 Segment 1** current is 0.56467 A at –146.7°. (If you get the correct phase angles but wrong magnitudes, open the main window **Options** menu, select **Power level**, and make sure the **Absolute V, I sources** box is checked.) The ratio is 1.0000 at an angle of –89.97°, which is within normal error bounds for the desired 1 at –90°.

As a check on *Arrayfeed1*, click the **Src Dat** button to find the impedance seen by the source. This would be the impedance at the main feedline connection in the real array. *EZNEC-ARRL* reports 33.96 + *j*13.11 Ω, very close to the 33.94 + *j*13.13 Ω given by *Arrayfeed1* in Fig 21. Small differences of this order are normal and to be expected. This provides a further check that the *EZNEC-ARRL* model is correctly analyzing the *Arrayfeed1* feed system.

This *EZNEC-ARRL* model uses lossless transmission lines of a fixed physical length rather than a fixed electrical length (number of degrees), so they'll behave like real lines as the frequency is changed. By changing the *EZNEC* frequency and re-running the 2D plot, you can see that the front-to-back ratio degrades at 7.0 and 7.3 MHz. A slight adjustment of one or more line lengths, or a new *Arrayfeed1* solution at a slightly different frequency might produce a better compromise for some uses.

Other things you can try are to evaluate the second *Arrayfeed1* solution, or to try using different line impedances. (Keep the two line impedances equal if you anticipate doing array direction switching.) The effect of varying ground system resistance can also be evaluated by clicking the **Loads** line in the main window and changing the load resistance values. For example, if the ground system resistance were 9 Ω instead of the 18 Ω we have assumed, the front/back ratio would drop from about 32 to about 20 dB. Note that changing the *EZNEC* ground conductivity in this model has no effect on the feed-point current ratio. With a *MININEC* type ground, it's used only for pattern calculation—the ground is assumed perfect during impedance and current calculations, and the only ground system loss resistance in the model is what we've specifically put in as loads.

Not surprisingly, the forward gain is affected very little by changes in frequency or ground system loss. To find the gain relative to a single element, compare the reported dBi gain of **ARRL_Cardioid_Example** with the same model with one of the elements deleted. You'll find it's very close to 3.0 dB. The 90° fed, 90° spaced array is a special case of array where the effects of mutual coupling on the two elements are opposite and cancel, resulting in the same gain as if mutual coupling didn't exist. But mutual coupling most certainly does exist!

The second solution presented a more favorable main feed-point impedance, so it would be tempting to use that one instead of the first solution. Replacing the feed-line lengths with the second solution lengths to model the second solution shows that the front/back ratio deteriorates more at the band edges when the second solution is used. This might be tolerable if restricted frequency use is anticipated. But it does illustrate that the solution with shorter lines is generally more broadbanded and that the choice of solution shouldn't in general be based on the one giving the most favorable impedance.

A Three-Element Binomial Broadside Array

An array of three in-line elements spaced λ/2 apart and fed in-phase gives a pattern that is generally bidirectional. If the element currents are equal, the resulting pattern has a forward gain of 5.7 dB (for lossless elements) compared to a single element, but it has substantial side lobes. If the currents are tapered in a binomial coefficient 1:2:1 ratio (twice the current in the center element as in the two end elements), the gain drops slightly to just under 5.3 dB, the main lobes widen and the side lobes disappear.

The array is shown in **Fig 23**, and an *EZNEC-ARRL* model of the antenna over perfect ground to show the ideal pattern is provided as **ARRL_Binomial_Example.EZ**. To obtain a 1:2:1 current ratio in the elements, each end element is fed through a 3λ/4 line of impedance Z_0. Line lengths of 3λ/4 are chosen because λ/4 lines will not physically reach. The center element is fed from the same point through two parallel 3λ/4 lines of the same characteristic impedance. This is equivalent to feeding it through a line of impedance $Z_0/2$. The currents are thus forced to be in-phase and to have the correct ratio. **ARRL_Binomial_TL_Example.EZ** is an *EZNEC-ARRL* model that shows this feed system with lossless transmission lines. The reader is encouraged to experiment with this model to see the effect of changes in frequency, the addition of loss resistance (as resistive loads at the element feed points) and other alterations on the array pattern and gain. You should also replace the perfect ground with *MININEC* type of ground to show how radiation patterns over real ground differ from the theoretical perfect-ground pattern.



Fig 23—Feed system for the three element 1:2:1 binomial array. All feed lines are ¾ electrical wavelength long and have the same characteristic impedance.

A "Four Square" Array

Several types of feed system are used for feeding this popular array, and most share a common problem—they don't provide the correct element current ratio—although a number of them produce a workable approximation. The feed systems described here are capable of producing exactly the correct current ratio. The only significant variable is the element feed-point impedances, so the quality of the result depends on your ability to model the feed-point impedances of a correctly fed array. As in the examples above, *EZNEC-ARRL* will be used for that purpose and *Arrayfeed1* for the design of the feed system itself.

In this array (see **Fig 24**), four elements are placed in a square with λ/4 sides. (A variation of the Four Square uses wider spacing.) The rear and front elements (1 and 4) are 180° out-of-phase with each other. The side elements (2 and 3) are in phase with each other and 90° delayed from the front ele-



Fig 24—Pattern and layout of the four-element Four-Square array. Gain is referenced to a single similar element; add 5.5 dB to the scale values shown.

ment. The magnitudes of the currents in all four elements are equal. The front and rear elements can be forced to be 180° out-of-phase and to have equal currents by using the current-forcing method described earlier. One element is connected to a line that is either λ/4 or 3λ/4 long, the other to a line that is λ/2 longer, and the two lines to a common point.

Likewise, the two side element currents are forced to be equal by connecting them to a common point via λ/4 or 3λ/4 lines. **Fig 25** shows the basic current-forcing system.

If the pattern is to be electrically rotated, it is necessary to bring lines from all four elements to a common location. If solid-polyethylene dielectric coaxial cable, which has a dielectric constant of 0.66, is used, λ/4 lines won't reach the center of the array. So 3λ/4 lines must be used. Alternatively, you can use λ/4 lines with foam or other dielectric having a velocity factor of more than about 0.71 (plus a little extra margin). These will reach to the center. Whatever your choice, three of the lines must be the same length and the fourth must be λ/2 longer.

In this array, the side elements (2 and 3) have equal impedances, but the rear and front (1 and 4) are different from each other, and both are different from the side elements. We have to know the feed-point impedances of the front, rear and side elements in order to design the "simplest" feed system, but only the side element impedances are needed to design the L-network system. Knowledge of all feed-point impedances is necessary if the array main feedpoint impedance **Zin** is to be calculated. *EZNEC-ARRL* model **4Square_Example.EZ** shows a 40-meter Four Square array with 18 Ω of loss resistance at each element, to approximate an 8-radial per element ground system. (See the cardioid array example above for more information about modeling ground system loss.) Opening the file in *EZNEC-ARRL* and clicking the **Src Dat** button gives the following impedances:

Source 1: 16.4 – *j*15.85 Ω
Sources 2 and 3: 57.47 – *j*19.44 Ω
Source 4: 77.81 + *j*54.8 Ω

It's interesting to note that the resistive part of source 1 is less than the 18 Ω of loss resistance we intentionally added to simulate ground system loss. That means that the element 1 feed-point resistance would be negative if the ground resistance were less than about an ohm and a half. This isn't uncommon in phased arrays and simply means that the element is feeding power *into* the feed system. This power is coming via mutual coupling from the other elements.



Fig 25—"Simplest" feed system for the Four-Square array in Fig 24. Grounds and cable shields have been omitted for clarity.

"Simplest" (Transmission Line Only) Feed System

To design a "simplest" feed system, start *Arrayfeed1*. In the **Array Type** frame, select **4 Square**, and select **"Simplest"** in the **Feed System Type** frame. In the **Inputs** frame, enter the frequency and the impedances from *EZNEC-ARRL*:

Frequency = 7.15 MHz
Leading Element: R = 16.4, X = –15.85
Side elements: R = 57.47, X = –19.44
Lagging Element: R = 77.81, X = 54.8

We'll try using 50 Ω for all lines, so enter **50** into the next three boxes.

Enter **1** for the lagging:leading I magnitude and **–90** for the phase.

Click **Find Solutions**.

The result is shown in the **Solutions** frame, shown in **Fig 26**. As always when any solution exists, there are two to choose from. The one with the shortest lines is generally preferable, so we'll choose it. For this example, we'll use λ/4 lines with velocity factor of 0.82. So enter **0.82** in the **Velocity Factor** box in the **Physical Lengths** frame, and read the physical lengths from the bottom of that frame. The λ/4 lines (marked in the *Arrayfeed1* diagram with an asterisk) are 28.2 feet, line 1 is 7.483 feet and line 2 is 51.668 feet. The "simplest" feed system is shown in Fig 26, and the complete feed system consists of this connected to the array of Fig 25.

EZNEC-ARRL model **ARRL_4Square_TL_Example.EZ** is simulates the array fed with this system. Comparison of the pattern plot to one from ideal-current model **ARRL_4Square_Example.EZ** and examination of



Array Type
○ Two Element
● Four Square
○ 4 Element Rectangle

Feed System Type
● "Simplest"
○ L Network

Lines marked * are all the same length and Z0, and either 1/4 or 3/4 WL long.

☑ Calc Zin

Inputs
Enter Frequency MHz 7.15

Enter feedpoint impedances

Element	R ohms	X ohms
Leading Element	16.4	-15.85
Side Elements	57.47	-19.44
Lagging Element	77.81	54.8

Choose line impedances
Line 1 Z0 50 ohms
Line 2 Z0 50 ohms
Choose Z0 of 1/4 or 3/4 wavelength lines 50 ohms
Middle:leading I mag, phase
Mag 1 Phase -90 deg

Solutions
Electrical Length, Degrees

	1st Soln	2nd Soln
Line 1	23.88	137.92
Line 2	164.90	213.36
Zin	11.24 + j 0.23	36.47 + j 7.88

Physical Lengths
Velocity Factor .82
Units
○ Meters
○ Millimeters
● Feet
○ Inches
○ Wavelengths
1/4 wavelength 28.200
1/2 wavelength 56.401
3/4 wavelength 84.601

	1st Solution	2nd Solution
Line 1	7.483	43.214
Line 2	51.668	66.855

Fig 26—Screen capture from *Arrayfeed1* for "Simplest" feed system for Four Square feed system shown in Fig 25.



Array Type
○ Two Element
● Four Square
○ 4 Element Rectangle

Feed System Type
○ "Simplest"
● L Network

Lines marked * are all the same length and Z0, and either 1/4 or 3/4 WL long. Unmarked lines connected to network are zero length.

☑ Calc Zin

Inputs
Enter Frequency MHz 7.15

Enter feedpoint impedances

Element	R ohms	X ohms
Leading Element	16.4	-15.85
Side Elements	57.47	-19.44
Lagging Element	77.81	54.8

Choose Z0 of 1/4 or 3/4 wavelength lines 50 ohms
Middle:leading I mag, phase
Mag 1 Phase -90 deg

Solutions

	X ohms	Value	Comp Type
Xser	21.75	0.484 uH	L
Xsh	-16.253	1369.6 pF	C

Zin 10.56 + j 3.84

Physical Lengths
Velocity Factor .82
Units
○ Meters
○ Millimeters
● Feet
○ Inches
○ Wavelengths
1/4 wavelength 28.200
1/2 wavelength 56.401
3/4 wavelength 84.601

Fig 27—L-network setup for Four-Square array in Fig 25, fed with λ/4 (or 3λ/4) current-forcing feed system.



Fig 28—Pattern and layout of the four-element rectangular array. Gain is referenced to a single similar element; add 6.8 dB to the scale values shown.

the element currents verify that the feed system is producing the desired pattern and element currents. You can use **ARRL_4Square_Example.EZ** to investigate the effect of frequency change, ground loss and other changes on the array gain and pattern.

L-Network Feed System

To design the L-network feed system, simply change the **Feed System Type** to **L Network** and click **Find Solutions**. The results you should see are a 0.484 µH inductor for the series component X_{ser}, and a 1369.6 pF capacitor for the shunt component X_{sh}. The L-network feed system is shown in **Fig 27**, and the complete feed system consists of this L network connected to the array of Fig 25.

EZNEC-ARRL doesn't have the ability to directly model the L network, so it's unable to model the complete system. However, the system has been modeled using the network capability of *EZNEC v.5* and found to work as designed. Arrays have also been built using this feed system and the element currents measured, with exactly the expected results.

This array is more sensitive to adjustment than the 2-element 90° fed, 90° spaced array. Adjustment procedures and a method of remotely switching the direction of this array are described in the **Practical Aspects of Phased Array Design** section that follows.

A 4-Element Rectangular Array

The 4-element rectangule array shown with its pattern in **Fig 28** has appeared numerous times in amateur publications. However, many of the accompanying feed systems fail to deliver currents in the proper amounts and phases to the various elements. The array can be correctly fed using the principles discussed in this chapter and the design methods that follow.

Elements 1 and 2 can be forced to be in-phase and to have equal currents by feeding them through 3λ/4 lines. (As in the binomial and Four Square array examples, 3λ/4 lines are chosen because λ/4 lines won't physically reach.) The currents in elements 3 and 4 can similarly be forced to be equal and in-phase. **Fig 29** shows the "current-forcing" feed system. Elements 3 and 4 are made to have currents of equal magnitude but of 90° phase difference from elements 1 and 2 by use of either a "simplest" all-transmission line feed system or an L-network feed system. Both will be designed in this example.



Fig 29—"Simplest" feed system for four-element rectangular array, using four equal-length λ/4 (or 3λ/4) cables.

For this array, we have to know the feed-point impedances of two elements (one of each pair) in order to design either type of feed system. *EZNEC-ARRL* model **Rectangular_Example.EZ** shows a 20-meter rectangular array with 18 Ω of loss resistance at each element, again to approximate an 8-radial per element ground system. (See the cardioid array example above for more information about modeling ground system loss.) Open the file in *EZNEC-ARRL* and click the **Src Dat** button to find the following feed-point impedances:

Sources 1 and 2: 21.44 – *j* 21.29 Ω
Sources 3 and 4: 70.81 – *j* 5.232 Ω

"Simplest" (Transmission- Line Only) Feed System

To design a "simplest" feed system, start program *Arrayfeed1*. In the **Array Type** frame, select **4 Element Rectangle**, and select **"Simplest"** in the **Feed System Type** frame. In the **Inputs** frame, enter the frequency and the impedances from *EZNEC-ARRL*:

Frequency = 14.15 MHz
Leading Elements R = 21.44, X = –21.29
Lagging Elements R = 70.81, X = –5.232

We'll use 50 Ω for all lines, so enter **50** into the next three boxes.

Enter **1** for the lagging:leading I magnitude and **–90** for the phase.

Click Find Solutions.

The result is "No Solution"—This combination of line impedances can't be used. Several other combinations also produce this result, but making lines 1 and 2 each 75 Ω and the 3λ/4 lines 50 Ω does produce a solution. Enter **75** into the **Line 1 Z0** and **Line 2 Z0** boxes, and leave **50** in the **Choose Z0 of ¼ or ¾ wavelength lines** box, then click the Find Solutions button. There won't be any problem making lines 1 and 2 reach, so we'll choose the first solution because the lines are shorter. The physical lengths of all the lines are shown in the **Physical Lengths** frame when the velocity factor is entered in the appropriate box. Assuming that we use coax with a velocity factor of 0.66 (and the example frequency of 14.15 MHz), the lengths are:

Line 1: 4.982 feet
Line 2: 20.153 feet
3λ/4 lines (marked with an asterisk in the *Arrayfeed1* diagram): 34.408 feet

The lines are connected following the diagram in the upper left part of the *Arrayfeed1* window. This completes the "simplest" feed system design. *EZNEC-ARRL* model **Rectangular_TL_Example.EZ** simulates an array fed with this system.

Comparison of the pattern plot to one from ideal-current **Rectangular_Example.EZ**, and examination of the element currents verify that the feed system is producing the desired pattern and element currents.

L-Network Feed System

To design the L-network feed system using *Arrayfeed1*, change the **Feed System Type** to **L Network** and click **Find Solutions**. The resulting L-network values are a 0.484 μH inductor for the series component X_{ser} and a 1369.6 pF capacitor for the shunt component X_{sh}.

120° Fed, 60° Spaced Dipole Array

This example shows the design of "simplest" and L network feed systems for a 2-element 20- meter dipole array, rather than a vertical array. No special accommodation is required for the array made from dipoles rather than vertical elements—the same methods can be used regardless of element shape. This example also shows that both the "simplest" and L-network feed systems can readily be applied to elements that use phase angles other than 90°.

Any 2-element array made with identical elements spaced λ/2 or closer and having equal magnitude currents with a relative phase angle of 180° minus the spacing will produce a unidirectional pattern with a good null to the rear. In practice, very close spacings lead to very low feed-point resistances, with consequent losses and very narrowband characteristics. But this 60° spaced array is well within the range of practical realization. File **ARRL_Dipole_Array_Example.EZ** is a model created for this array, with ideal element currents. Open this file in *EZNEC-ARRL* and click **FF Plot** to show the pattern at an elevation angle of 10°. You can save this pattern for later comparison to the pattern with a "simplest" feed system by opening the **File** menu in the **2D Plot** window, selecting **Save Trace As**, entering a name for the trace file and clicking **Save**.

Following the same procedure as in the previous examples, we begin the array design by finding the element feed-point impedances in the ideally fed array using *EZNEC-ARRL* numbers. Having already opened **ARRL_Dipole_Array_Example.EZ**, all that's needed is to click **Src Dat.** The results are:

Leading element (source 1) : 36.16 – *j*46.05 Ω
Lagging element (source 2) : 49.56 + *j*51.47 Ω

"Simplest" (Transmission Line Only) Feed System

Select **Two Element** for the **Array Type** in *Arrayfeed1* and **"Simplest"** for the **Feed System Type**. Enter the frequency of 14.15 MHz and enter the element feed-point impedances from *EZNEC-ARRL* into the appropriate boxes in the **Inputs** frame. For line impedances, the section describing the "simplest" feed system recommends against choosing one which is very different from the element feed-point impedances, but for fun let's try 300 Ω for the two lines and see what happens. Enter **300** in the **Line 1 Z0** and **Line 2 Z0** boxes. Finally, enter the **lagging:leading I mag, phase** of **1** for **Mag** and **–120** for **Phase**.

Click **Find Solutions**. For this example we'll assume that TV type twinlead with a velocity factor of 0.8 is being used. So enter **0.8** for the **Velocity Factor** and read the physical line lengths in the **Physical Lengths** frame. A model of the array using the first solution has been created as **ARRL_Dipole_Array_TL_Example.EZ**. Open this file in *EZNEC-ARRL* and click **FF Tab**. You should see that the plot is virtually identical to the one saved earlier from the ideal-current model. Note the gain and front/back ratio or 8.79 dBi and 31.01 dB respectively reported in the data box below the 2D plot.

Don't subtract 2.15 dB to find the gain relative to a single element! This isn't a free-space model, and the gain of a single dipole over ground is much greater than 2.15 dBi. Instead, delete one of the elements in **ARRL_Dipole_Array_Example.EZ** to find the gain of a single element and subtract that value from the array gain. You can use the undo feature or re-open the file to restore the array.

Now, go back to the model with the "simplest" feed system in *EZNEC-ARRL* and change the Frequency to **14.0** MHz. Click **FF Tab** again. The gain has decreased a little, to 8.54 dBi and the front/back ratio has also decreased, to 21.8 dB. At 14.3 MHz, the gain is slightly higher, 9.04 dBi, but the front/back is again worse, down to 18.64 dB. But this isn't bad overall.

Let's take a look at the second solution. Click the **Trans Lines** line in the main *EZNEC-ARRL* window to open the Transmission Lines Window. Change the length of the first line to **26.856** feet, the second to **28.356** feet, and press the **Enter** key to complete the change. Change the **Frequency** back to **14.15** MHz and click **FF Tab**. You should see exactly the same pattern as for both the first solution and for the ideal current model. But now change the **Frequency** to **14.0** MHz, click FF Tab, and look at the pattern.

What happened? The gain has dropped to 5.95 dBi and the front/back to only 3.1 dB. The array is now nearly bi-directional! It's almost as bad at 14.3 MHz. So we've created a terribly touchy system. The chance of its working correctly even at the design frequency is slim, because there are inevitably some differences between the model and real antenna.

We did have a clue this might happen. As stated in the section describing the "simplest" feed system, the best choices for line Z_0 and for the resulting solution give a difference in electrical line lengths about equal to the desired phase delay of the current. The difference in electrical line lengths for the first solution was about 152°—not as close to the 120° current phase difference as we'd like, but much better than the mere 9.7° difference of the lines for the second solution. While the 300-Ω line Z_0 is quite different from the element feed-point impedances, the first solution result is quite good. If desired, you can try other line impedance values into *Arrayfeed1* and evaluate the results with *EZNEC-ARRL*.

Please see the information about baluns in the **Baluns in Phased Arrays** section. Baluns are placed the same as in Fig 19, which shows the L-network feed system.

L-Network Feed System

To design an L network feed system, change the *Arrayfeed1* **Feed System Type** to **L Network** and click **Find Solutions**. The results aren't good ones to use. The component reactance magnitudes of about 1573 and 2619 Ω are more than five times the 300-Ω Z_0 of the feed lines. As explained in the section describing the L-network feed system, it's undesirable to have such a large ratio of component reactance to line Z_0. Among other problems, the inductor and capacitor values are quite extreme and capacitor stray inductance and inductor capacitance would have a significant impact on performance.

The problem occurs because the feed-line impedance we chose is much larger than the element feed-point impedances, so the $\lambda/4$ lines transform the feed-point impedances to much higher values at the L network and main feed point. This feed system would be extremely critical, narrowbanded and difficult to adjust. We can do better by choosing feed-line impedances that aren't too drastically different than the element feed-point impedances. In this case, 50 or 75 Ω would be a much better choice than 300. Let's try 75.

In *Arrayfeed1*, change the **Line 1 Z0** and **Line 2 Z0** impedances from **300** to **75** and click **Find Solutions**. L-network component reactance magnitudes are now about 98 and 164 Ω, much better than before. This will be a relatively uncritical and broadbanded feed system.

Again, be sure to read the information about baluns in the **Baluns in Phased Arrays** section. Fig 19 shows the completed feed system including baluns.

PRACTICAL ASPECTS OF PHASED ARRAY DESIGN

With almost any type of antenna system, there is much that can be learned from experimenting with, testing and using various array configurations. In this section, Roy Lewallen, W7EL, shares the benefit of years of his experience from actually building, adjusting and using phased arrays. There is much more work to be done in most of the areas covered here, and Roy encourages the reader to build on this work.

Adjusting Phased Array Feed Systems

If a phased array is constructed only to achieve forward gain, adjusting it is seldom worthwhile. This is because the forward gain of most arrays is quite insensitive to either the magnitude or phase of the relative currents flowing in the elements. If, however, good rejection of unwanted signals is desired, adjustment may be required. And achieving very deep nulls will almost surely require some adjustment.

The in-phase and 180° out-of-phase current-forcing method supplies very well-balanced and well-phased currents to elements without adjustment. If the pattern of an array fed using this method is unsatisfactory, it's generally the result of environmental differences—where the elements, even though furnished with correct currents, aren't generating the correct fields. Such an array can be optimized in a single direction, but a more general approach than the current-forcing method must be taken. Some possibilities are described by Paul Lee and Forrest Gehrke (see Bibliography).

Unlike the current-forcing method, the "simplest" and L-network feed systems described earlier in this chapter are dependent on the self and mutual impedance of one or more elements. The required transmission-line lengths or L-network component values can be computed to a high level of precision, but the results are only as good as the knowledge of the relevant feed-point impedances.

While the simplest feed system doesn't readily lend itself to adjustment, the components of an L network can easily be made adjustable or can be experimentally changed in increments. A practical approach is to model the array as accurately as possible, design and build the feed system based on the model results and then adjust the network for the best performance.

Simple arrays such as the two-element 90° fed and spaced array can be adjusted as follows. Place a low-power signal source at a distance from the array (preferably several wavelengths), in the direction a null should be. While listening to the signal on a receiver connected to the array, alternately adjust the two L-network components for the best rejection of the signal.

This has proved to be a very good way to adjust 2-element arrays. However, variable results were obtained when a Four-Square array was adjusted using this technique. The probable reason is that more than one combination of current balance and phasing can produce a null in a given direction but each produces a different overall pattern. So a different method must be used for adjusting more complex arrays. This involves actually measuring the element currents in some way, and adjusting the network until the currents are correct. After adjusting the currents, small adjustments can be made to deepen the null(s) if desired.

Measuring Element Currents

You can measure the element currents two ways. One way is to measure them directly at the element feed points, as shown in **Fig 30**. A dual-channel oscilloscope is required to monitor the currents. This method is the most accurate and it provides a direct indication of the actual relative magnitudes and phases of the element currents. The current probe is shown in **Fig 31**.

Instead of measuring the element currents directly, you could measure them indirectly by measuring the voltages on the feed lines an electrical λ/4 or 3λ/4 distance from the array. The voltages at these points are directly proportional to the element currents. This introduces additional variables that can reduce the accuracy of the result, but the method generally produces adequate performance. The 2-element arrays fed with the L-network system and all the four element arrays presented earlier have λ/4 or 3λ/4 lines from all elements to a common location, making this second measurement method convenient. The voltages can be observed with a dual-channel oscilloscope, or, to adjust for equal-magnitude currents and 90° phasing, you can use the test circuit shown in **Fig 32**.

The test circuit is connected to the feed lines of two elements that are to be adjusted for 90° phasing (such as elements 1 and 2, or 2 and 4 of the Four-Square array of Figs 24 and 25). Adjust the L-network components alternately until both meters read zero. Proper operation of the test circuit can be verified by disconnecting one of the inputs. The *phase* output


Equal Lengths
Current Probe at Base of Element
Current Probe at Base of Element
Z_0
Z_0
Feed Line
Feed Line
R = Z_0
R = Z_0
In
In
Two – Channel Oscilloscope
ANT0325

Fig 30—One method of measuring element currents in a phased array. Details of the current probe are given in Fig 31. Caution: Do not run high power to the antenna system for this measurement, or damage to the test equipment may result.


Current – Carrying Conductor
Coax (Any Type)
Ferrite Core Any Size, Type 72 Ferrite
Do Not Connect to Ground at Antenna
10 Turns
ANT1002

Fig 31—The current probe for use in the test setup of Fig 30. The ferrite core is of type 72 material, and may be any size. The coax line must be terminated at the opposite end with a resistor equal to its characteristic impedance. You should build this probe in a plastic or metal box to provide mechanical ruggedness.



Fig 32—Quadrature test circuit. All diodes are germanium, such as 1N34A, 1N270, or equiv. Hot carrier or silicon diodes can be used at higher power levels. All resistors are ¼ or ½ W, 5% tolerance. Capacitors are ceramic. Alligator clips are convenient for making the input and ground connections to the array.

T1—7 trifilar turns on an Amidon FT-37-43, -75, -77, or equivalent ferrite toroid core.

should remain close to zero. If not, there is an undesirable imbalance in the circuit, which must be corrected. Another means of verification is to first adjust the L network so the tester indicates correct phasing (zero volts at the *phase* output). Then reverse the tester input connections to the elements. The *phase* output should remain close to zero.

Directional Switching of Arrays

One ideal directional-switching method would take the entire feed system, including the lines to the elements and physically rotate it. The smallest possible increment of rotation would depend on the symmetry of the array—the feed system would need to rotate until the array again *looks* the same to it. For example, any 2-element array can be rotated 180° (although that wouldn't accomplish anything if the array is bidirectional to begin with). The 4-element rectangular array of Figs 28 and 29 can also be reversed, and the Four-Square array of Figs 24 and 25 can be switched in 90° increments.

Smaller switching increments can be accomplished only by reconfiguring the feed system, including any network if used, effectively creating a different kind of array. Switching in smaller increments than dictated by symmetry will create a different pattern in some directions than in others, and must be thoughtfully done to maintain equal and properly phased element currents. The methods illustrated here will deal only with switching in increments related to the array symmetry, except for one: a 2-element broadside/end-fire array.

In all arrays, the success of directional switching depends on the elements and ground systems being identical so that equal element currents result in equal fields. It's even more important in arrays fed with any method other than current forcing, because the effectiveness of those methods depends on the element feed-point impedances. Few of us can afford the luxury of having an array many wavelengths away from all other conductors, so an array will nearly always perform somewhat differently in each direction. The array should be adjusted when steered in the direction requiring the most signal rejection in the nulls. Forward gain will, for all practical purposes, be equal in all the switched directions, since gain is much more tolerant of error than are nulls.

Basic Switching Methods

Following is a discussion of basic switching methods, how to power relays through the main feed line and other practical considerations. In diagrams, grounds are frequently omitted to aid clarity, but connections of the ground conductors must be carefully made. In fact, it is recommended that the ground conductors be switched just as the center conductors are, as explained in more detail in **Improving Array Switching Systems** below. In all cases, interconnecting lines must be very short.

A pair of elements spaced $\lambda/2$ apart can readily be switched between broadside and end-fire bidirectional pat-



Fig 33—Two-element broadside/end-fire switching. All lines must have the same characteristic impedance. Grounds and cable shields have been omitted for clarity.



Fig 34—Directional switching for 90°, 90° spaced 2-element array fed with a "simplest" feed system.



Fig 35—Directional switching for 90°, 90° spaced 2-element array fed with an L-network, current-forcing feed system.



Fig 36—Directional switching of a four-element rectangular array. All interconnections must be very short. As usual, grounds and cable shields have been omitted for clarity.

terns, using the current-forcing properties of λ/4 lines. The method is shown in **Fig 33**. The switching device can be a relay powered via a separate cable or by dc sent along the main feed line.

Fig 34 shows directional switching of a 90° fed, 90° spaced array fed with a "simplest" feed system, where L1 and L2 are the required lengths of the two feed lines. **Fig 35** shows how to switch the same array when fed with an L-network, current-forcing system.

The rectangular array of Fig 28 can be switched in a similar manner, as shown in **Fig 36**. To switch a "simplest" fed rectangular array, use the switching circuit of Fig 34, but connect the two equal length lines to points A and B of Fig 29 in place of the two elements shown in Fig 34.

Switching the direction of an array in increments of 90°, when permitted by symmetry, requires at least two relays. A method of 90° switching of the Four-Square array with L-network feed is shown in **Fig 37**.

Powering Relays Through Feed Lines

All of the above switching methods can be implemented without additional wires to the switch box. A single-relay system is shown in **Fig 38A**, and a two-relay system in

Fig 38B. Small 12 or 24-V dc power relays can be used in either system at power levels up to at least a few hundred watts. Do not attempt to change directions while transmitting, however. Blocking capacitors C1 and C2 should be good quality ceramic or transmitting mica units of 0.01 to 0.1 µF. No problems have been encountered using 0.1 µF, 300-V monolithic ceramic units at RF output levels up to 300 W. C2 may be omitted if the antenna system is an open circuit at dc. C3 and C4 should be ceramic, 0.001 µF or larger.

In Fig 38B, capacitors C5 through C8 should be selected with the ratings of their counterparts in Fig 38A, as given above. Electrolytic capacitors across the relay coils, C9 and C10 in Fig 38B, should be large enough to prevent the relays from buzzing, but not so large as to make relay operation too slow. Final values for most relays will be in the range from 10 to 100 µF. They should have a voltage rating of at least double the relay coil voltage. Some relays do not require this capacitor. All diodes are 1N4001 or similar. A rotary switch may be used in place of the two toggle switches in the two-relay system to switch the relays in the desired sequence.

Improving Array-Switching Systems

The extra circuitry involved in switching arrays can degrade array performance by altering the relative currents fed to each element. One common cause is current sharing in common ground conductors, even when connections are kept very short. The author has seen a 30° phase shift in voltage along a 4-inch piece of #12 wire in a 40-meter array feed system.

When the two conductors of a feedline are physically separated from each other, the impedance increases. This is especially true when the main lines are coaxial cables. If currents from two elements share the ground conductor of a split line, a relatively large voltage drop results. Voltage changes λ/4 from the elements translate to current changes at the elements. Although keeping all leads extremely short is sometimes adequate, the best way to reduce current sharing problems is to keep the two conductors of each transmission line as close together as possible, and switch both conductors of each line rather than just a single or "hot" conductor.

An example of a carefully designed switching system is shown in **Fig 39**. It avoids the problem of shared ground conductor currents, as well as another common problem, namely that effective line lengths are often different along different switching paths. Notice how the path from the main feed point travels through a single line to each element with no common ground connections to other lines except at the


λ/4 Lines to
Element 1
Feed Line
L Network
Element 2
λ/2
Element 3
Element 4
K 1
K 2
Both Relays Shown " Out "
El. 4
El. 2
El. 3
El. 1
Pattern Maximum in Direction of Element No.
Relays
K 1 K 2
1 In Out
2 In In
3 Out In
4 Out Out
ANT0331

Fig 37—Directional switching of the four-square array. All interconnections must be very short.


Station
Switch Box
to TX
C1
C2
RF to Antenna System
RFC
RFC
C3
C4
Switch Activates Relay
+ V_DC
(A)
Relay
Station
Switch Box
toTX
C5
C6
RF to Antenna System
RFC
RFC
C7
C8
S1
S2
K1
K2
C10
C9
V_AC
(B)
ANT0332

Fig 38—Remote switching of relays. See text for component information. A one-relay system is shown at A, and a two-relay system at B. In B, S1 activates K1, and S2 activates K2.

main feed point. Notice also that the distance doesn't change as the direction is switched. The λ/4 lines going to the two elements must be shortened by the length ℓ of the lines on the feed side of the relays, so that the total line length from the main feed point to each element is λ/4 (or 3λ/4).

You can see that in either relay position, there's an open ended stub of length ℓ connected at the main feed point and another at the output end of the L network. These will add capacitance at those points. Extra C at the main feed point will alter the overall impedance seen by a transmitter, but won't otherwise have any effect on the array or its performance. The one at the output of the L network will, however, change the transformation and phase shift properties of the network. But it's easy to compensate—the value of the shunt capacitor element is simply reduced by the amount of the C added by the stub. The amount of C for any kind of transmission line can be calculated from:

$$C(\text{pf / ft}) = \frac{1017}{Z_0 \text{VF}}$$

or

$$C(\text{pf / m}) = \frac{3336}{Z_0 \text{VF}}$$



Fig 39—A carefully designed L-network, current-forcing switching system that switches both hot and shield conductors in feed coaxes.

where Z_0 = the characteristic impedance of the line and VF = the velocity factor. This works out to 31 pF/foot or 101 pF/meter for 50-Ω solid polyethylene insulated coax, which has a velocity factor of 0.66.

The general principles illustrated in Fig 39 can be extended to other switching systems. If switching the ground conductors as described above isn't practical, use of a metal box for the switching circuitry is recommended, so that the relatively large surface area of the box can be used for the common ground conductors, minimizing their inductance. Always keep leads extremely short.

Measuring the Electrical Length of Feed Lines

When using the feed methods described earlier the feed lines must be very close to the correct length. For best results, they should be correct within 1% or so. This means that a line that is intended to be, say, λ/4 at 7 MHz, should actually be λ/4 at some frequency within 70 kHz of 7 MHz. A simple but accurate method to determine at what frequency a line is λ/4 or λ/2 is shown in **Fig 40A**. The far end of the line is short circuited with a very short connection. A signal is applied to the input and the frequency is swept until the impedance at the input is a minimum. This is the frequency at which the



Fig 40—At A, the setup for measurement of the electrical length of a transmission line. The receiver may be used in place of the frequency counter to determine the frequency of the signal generator. The signal generator output must be free of harmonics; the half-wave harmonic filter at B may be used outboard if there is any doubt. It must be constructed for the frequency band of operation. Connect the filter between the signal generator and the attenuator pad.

C1, C3—Value to have a capacitive reactance = R_{IN}.
C2—Value to have a capacitive reactance = ½ R_{IN}.
L1, L2—Value to have an inductive reactance = R_{IN}.

line is λ/2. Either the frequency counter or the receiver may be used to determine this frequency. The line is, of course, λ/4 at one half the measured frequency.

The detector can be a simple diode detector or an oscilloscope may be used if available. A 6 to 10 dB attenuator pad is included to prevent the signal generator from looking into a short circuit at the measurement frequency. The signal generator output must be free of harmonics. If there is any doubt, an outboard low-pass filter, such as a half-wave harmonic filter, should be used. The half-wave filter circuit is shown in Fig 40B, and must be constructed for the frequency band of operation.

Another satisfactory method is to use a noise or resistance bridge or antenna analyzer at the input of the line, again looking for a low impedance at the input while the output is short circuited. Simple resistance bridges are described in Chapter 27.

Dip oscillators have been found to be unsatisfactory. The required coupling loop has too great an effect on measurements.

Measuring Element Self and Mutual Impedances

The need for measuring element self and mutual impedances has been made largely unnecessary with the ready availability of modeling software. Few amateurs appreciate the considerable difficulty of making accurate impedance measurements and accurate mutual impedance measurements are very difficult even with professional test equipment and skills. Despite the limitations of computer modeling, results very often are better than measured values because of the multiple factors affecting measurement accuracy.

Those who are interested in measuring self and mutual impedances can find more detailed information about doing so in Appendix B. The information there is from earlier editions of *The ARRL Antenna Book*.

Broadside Arrays

Broadside arrays can be made up of collinear or parallel elements or combinations of the two. This section was contributed by Rudy Severns, N6LF.

COLLINEAR ARRAYS

Collinear arrays are always operated with the elements in-phase. (If alternate elements in such an array are out-of-phase, the system simply becomes a harmonic type of antenna.) A collinear array is a broadside radiator, the direction of maximum radiation being at right angles to the line of the antenna.

POWER GAIN

Because of the nature of the mutual impedance between collinear elements, the feed-point resistance (compared to a single element, which is ≈73 Ω) is increased as shown earlier in this chapter (Fig 9). For this reason the power gain does not increase in direct proportion to the number of elements. The gain with two elements, as the spacing between them is varied, is shown by **Fig 41**. Although the gain is greatest when the end-to-end spacing is in the region of 0.4 to 0.6 λ, the use of spacings of this order is inconvenient constructionally and introduces problems in feeding the two elements. As a result, collinear elements are almost always operated with their ends



Fig 41—Gain of two collinear λ/2 elements as a function of spacing between the adjacent ends.

quite close together—in wire antennas, usually with just a strain insulator between.

With very small spacing between the ends of adjacent elements the theoretical power gain of collinear arrays, assuming the use of #12 copper wire, is approximately as follows over a dipole in free space:

2 collinear elements—1.6 dB
3 collinear elements—3.1 dB
4 collinear elements—3.9 dB

More than four elements are rarely used.

DIRECTIVITY

The directivity of a collinear array, in a plane containing the axis of the array, increases with its length. Small secondary lobes appear in the pattern when more than two elements are used, but the amplitudes of these lobes are low enough so that they are usually not important. In a plane at right angles to the array the directive diagram is a circle, no matter what the number of elements. Collinear operation, therefore, affects only E-plane directivity, the plane containing the antenna.

When a collinear array is mounted with the elements vertical, the antenna radiates equally well in all geographical directions. An array of such *stacked* collinear elements tends to confine the radiation to low vertical angles.

If a collinear array is mounted horizontally, the directive pattern in the vertical plane at right angles to the array is the same as the vertical pattern of a simple λ/2 antenna at the same height (Chapter 3).

TWO-ELEMENT ARRAYS

The simplest and most popular collinear array is one using two elements, as shown in **Fig 42**. This system is commonly known as *two half-waves in phase*. The directive pattern in a plane containing the wire axis is shown in **Fig 43**, which shows superimposed patterns for a dipole and 2, 3 and 4-element collinear arrays. Depending on the conductor size, height, and similar factors, the impedance at the feed point can be expected to be in the range of 4 to 6 kΩ, for wire antennas. If the elements are made of tubing having a low λ/dia (wavelength to diameter) ratio, values as low as 1 kΩ are representative. The system can be fed through an open-wire tuned line with negligible loss for ordinary line lengths, or a matching section may be used if desired.



Fig 42—At A, two-element collinear array (two half-waves in phase). The transmission line shown would operate as a tuned line. A matching section can be substituted and a nonresonant line used if desired, as shown at B, where the matching section is two series capacitors.



Fig 43—Free-space E-plane directive diagram for dipole, 2, 3 and 4-element collinear arrays. The solid line is a 4-element collinear; the dashed line is for a 3-element collinear; the dotted line is for a 2-element collinear and the dashed-dotted line is for a λ/2 dipole.

A number of arrangements for matching the feed line to this antenna are described in Chapter 26. If elements somewhat shorter than λ/2 are used, then additional matching schemes can be employed at the expense of a slight reduction in gain. When the elements are shortened two things happen—the impedance at the feed-point drops and the impedance has inductive reactance that can be tuned out with simple series capacitors, as shown in Fig 42B.

Note that these capacitors must be suitable for the power level. Small *doorknob* capacitors such as those frequently used in power amplifiers, are suitable. By way of an example, if each side of a 40-meter 2-element array is shortened from 67 to 58 feet, the feed-point impedance drops from nearly 6000 Ω to about 1012 Ω with an inductive reactance of 1800 Ω. The reactance can be tuned out by inserting 25 pF capacitors at the feed-point. The 1012 Ω resistance can be transformed to 200 Ω using a λ/4 matching section made of 450-Ω ladder line and then transformed to 50 Ω with a 4:1 balun. Shortening the array as suggested reduces the gain by about 0.5 dB.

Another scheme that preserves the gain is to use a 450-Ω



Fig 44—Layouts for 3- and 4-element collinear arrays. Alternative methods of feeding a 3-element array are shown at A and B. These drawings also show the current distribution on the antenna elements and phasing stubs. A matched transmission line can be substituted for the tuned line by using a suitable matching section.

λ/4 matching section and shorten the antenna only slightly to have a resistance of 4 kΩ. The impedance at the input of the matching section is then near 50 Ω and a simple 1:1 balun can be used. Many other schemes are possible. The free-space E-plane response for a 2-element collinear array is shown in Fig 43, compared with the responses for more elaborate collinear arrays described below.

THREE- AND FOUR-ELEMENT ARRAYS

In a long wire the direction of current flow reverses in each λ/2 section. Consequently, collinear elements cannot simply be connected end to end; there must be some means for making the current flow in the same direction in all elements. When more than two collinear elements are used it is necessary to connect *phasing* stubs between adjacent elements in order to bring the currents in all elements in-phase. In **Fig 44A** the direction of current flow is correct in the two left-hand elements because the shorted λ/4 transmission line (*stub*) is connected between them. This stub may be looked upon simply as the alternate λ/2 section of a long-wire antenna folded back on itself to cancel its radiation. In Fig 44A the part to the right of the transmission line has a total length of three half wavelengths, the center half wave being folded back to form a λ/4 phase-reversing stub. No data are available on the impedance at the feed point in this arrangement, but various considerations indicate that it should be over 1 kΩ.

An alternative method of feeding three collinear elements is shown in Fig 44B. In this case power is applied at the center of the middle element and phase-reversing stubs are used between this element and both of the outer elements. The impedance at the feed point in this case is somewhat over 300 Ω and provides a close match to 300 Ω line. The SWR will be less than 2:1 when 600-Ω line is used. Center feed of this type is somewhat preferable to the arrangement in Fig 44A because the system as a whole is balanced. This assures more uniform power distribution among the elements. In Fig 44A, the right-hand element is likely to receive somewhat less power than the other two because a portion of the input power is radiated by the middle element before it can reach the element located at the extreme right.

A four-element array is shown in Fig 44C. The system is symmetrical when fed between the two center elements as shown. As in the three-element case, no data are available on the impedance at the feed point. However, the SWR with a 600 Ω line should not be much over 2:1.

Fig 43 compares the directive patterns of 2, 3 and 4-element arrays. Collinear arrays can be extended to more than four elements. However, the simple 2-element collinear array is the type most frequently used, as it lends itself well to multi-band operation. More than two collinear elements are seldom used because more gain can be obtained from other types of arrays.

ADJUSTMENT

In any of the collinear systems described, the lengths of the radiating elements in feet can be found from the formula $468/f_{MHz}$. The lengths of the phasing stubs can be found from the equations given in Chapter 26 for the type of line used. If the stub is open-wire line (500 to 600 Ω impedance) you may assume a velocity factor of 0.975 in the formula for a λ/4 line. On-site adjustment is, in general, an unnecessary refinement. If desired, however, the following procedure may be used when the system has more than two elements.

Disconnect all stubs and all elements except those directly connected to the transmission line (in the case of feed such as is shown in Fig 44B leave only the center element connected to the line). Adjust the elements to resonance, using the still-connected element. When the proper length is determined, cut all other elements to the same length. Make the phasing stubs slightly long and use a shorting bar to adjust their length. Connect the elements to the stubs and adjust the stubs to resonance, as indicated by maximum current in the shorting bars or by the SWR on the transmission line. If more than three or four elements are used it is best to add elements two at a time (one at each end of the array), resonating the system each time before a new pair is added.

THE EXTENDED DOUBLE ZEPP

One method to obtain higher gain that goes with wider spacing in a simple system of two collinear elements is to make the elements somewhat longer than λ/2. As shown in **Fig 45**, this increases the spacing between the two in-phase λ/2 sections at the ends of the wires. The section in the center carries a current of opposite phase, but if this section is short the current will be small; it represents only the outer ends of a λ/2 antenna section. Because of the small current and short length, the radiation from the center is small. The optimum length for each element is 0.64 λ. At greater lengths the system tends to act as a long-wire antenna, and the gain decreases.



Fig 45—The extended double Zepp. This system gives somewhat more gain than two λ-sized collinear elements.

This system is known as the *extended double Zepp*. The gain over a λ/2 dipole is approximately 3 dB, as compared with about 1.6 dB for two collinear λ/2 dipoles. The directional pattern in the plane containing the axis of the antenna



Fig 46—E-plane pattern for the extended double Zepp of Fig 45. This is also the horizontal directional pattern when the elements are horizontal. The axis of the elements lies along the 90°-270° line. The free-space array gain is approximately 4.95 dBi.



Fig 47—Resistive and reactive feed-point impedance of a 40-meter extended double Zepp in free space.

is shown in **Fig 46**. As in the case of all other collinear arrays, the free-space pattern in the plane at right angles to the antenna elements is the same as that of a λ/2 antenna—circular.

This antenna is not resonant at the operating frequency so that the feed-point impedance is complex (R ± *j* X). A typical example of the variation of the feed-point impedance over the band for a 40-meter double-extended Zepp is shown in **Fig 47**. This antenna is normally fed with open-wire transmission line to an antenna tuner. Other matching arrangements are, of course, possible. A method for transforming the feed-point impedance to 450 Ω and eliminating the minor lobes is given in Chapter 6.



Fig 48—Typical Sterba array, an 8-element version.

THE STERBA ARRAY

Two collinear arrays can be combined to form the *Sterba array*, often called the *Sterba curtain*. An 8-element example of a Sterba array is shown in **Fig 48**. The four λ/4 elements joined on the ends are equivalent to two λ/2 elements. The two collinear arrays are spaced λ/2 and the λ/4 phasing lines connected together to provide λ/2 phasing lines. This arrangement has the advantage of increasing the gain for a given length and also increasing the E-plane directivity, which is no longer circular. An additional advantage of this array is that the wire forms a closed loop. For installations where icing is a problem a low voltage dc or low frequency (50 or 60 Hz) ac current can be passed through the wire to heat it for deicing. The heating current is isolated from RF by decoupling chokes. This is standard practice in commercial installations.

The number of sections in a Sterba array can be extended as far as desired but more than four or five are rarely used because of the slow increase in gain with extra elements, the narrow H-plane directivity and the appearance of multiple sidelobes. When fed at the point indicated the impedance is about 600 Ω. The antenna can also be fed at the point marked X. The impedance at this point will be about 1 kΩ. The gain of the 8-element array in Fig 48 will be between 7 to 8 dB over a single element.

Parallel Broadside Arrays

To obtain broadside directivity with parallel elements the currents in the elements must all be in-phase. At a distant point lying on a line perpendicular to the axis of the array and also perpendicular to the plane containing the elements, the fields from all elements add up in phase. The situation is like that pictured in Fig 1 in this chapter, where four parallel λ/2 dipoles were fed together a broadside array.

Broadside arrays of this type theoretically can have any number of elements. However, practical limitations of construction and available space usually limit the number of broadside parallel elements.

POWER GAIN

The power gain of a parallel-element broadside array depends on the spacing between elements as well as on the number of elements. The way in which the gain of a two-element array varies with spacing is shown in **Fig 49**. The greatest gain is obtained when the spacing is in the vicinity of 0.67 λ.

The theoretical gains of broadside arrays having more than two elements are approximately as follows:

No. of Parallel Elements	*dB Gain with λ/2 Spacing*	*dB Gain with 3λ/4 Spacing*
3	5.7	7.2
4	7.1	8.5
5	8.1	9.4
6	8.9	10.4



Fig 49—Gain as a function of the spacing between two parallel elements operated in-phase (broadside).

The elements must, of course, all lie in the same plane and all must be fed in-phase.

DIRECTIVITY

The sharpness of the directive pattern depends on spacing between elements and number of elements. Larger element spacing will sharpen the main lobe, for a given number of elements, up to a point as was shown in Fig 41. The two-element array has no minor lobes when the spacing is λ/2, but small minor lobes appear at greater spacings. When three or more elements are used the pattern always has minor lobes.

Other Forms Of Broadside Arrays

For those who have the available room, multi-element arrays based on the broadside concept have something to offer. The antennas are large but of simple design and noncritical dimensions; they are also very economical in terms of gain per unit of cost.

Large arrays can often be fed at several different points. However, the pattern symmetry may be sensitive to the choice of feed point within the array. Non-symmetrical feed points will result in small asymmetries in the pattern but these are not usually of great concern.

Arrays of three and four elements are shown in **Fig 50**. In the 3-element array with λ/2 spacing at A, the array is fed at the center. This is the most desirable point in that it tends to keep the power distribution among the elements uniform. However, the transmission line could alternatively be connected at either point B or C of Fig 50A, with only slight skewing of the radiation pattern.

When the spacing is greater than λ/2, the phasing lines must be 1 λ long and are not transposed between elements. This is shown Fig 50B. With this arrangement, any element spacing up to 1 λ can be used, if the phasing lines can be folded as suggested in the drawing.

The 2-element array at C is fed at the center of the system to make the power distribution among elements as uniform as possible. However, the transmission line could be connected at either point B, C, D or E. In this case the section of phasing line between B and D must be transposed to make the currents flow in the same direction in all elements. The 4-element array at C and the 3-element array at B have approximately the same gain when the element spacing in the array at B is 3λ/4.

An alternative feeding method is shown in Fig 50D. This system can also be applied to the 3-element arrays, and will result in better symmetry in any case. It is necessary only to move the phasing line to the center of each element, making connection to both sides of the line instead of one only.

The free-space pattern for a 4-element array with λ/2 spacing is shown in **Fig 51**. This is also approximately the pattern for a 3-element array with 3λ/4 spacing.

Larger arrays can be designed and constructed by following the phasing principles shown in the drawings. No accurate figures are available for the impedances at the various feed points indicated in Fig 50. You can estimate it to be in the vicinity of 1 kΩ when the feed point is at a junction between the phasing line and a λ/2 element, becoming smaller as the number of elements in the array is increased. When the feed point is midway between end-fed elements as in Fig 50C, the feed-point impedance of a 4-element array is in the vicinity of 200 to 300 Ω, with 600-Ω open-wire phasing lines. The impedance at the feed point with the antenna shown at D should be about 1.5 kΩ.



Fig 50—Methods of feeding 3- and 4-element broadside arrays with parallel elements.



Fig 51—Free-space E-plane pattern of a 4-element broadside array using parallel elements (Fig 50). This corresponds to the horizontal directive pattern at low wave angles for a vertically polarized array over ground. The axis of the elements lies along the 90°-270° line.



Fig 52—Layout for the half-square antenna.



Fig 53—Free-space E-plane directive pattern for the half-square antenna.

NON-UNIFORM ELEMENT CURRENTS

The pattern for a 4-element broadside array shown in Fig 51 has substantial side lobes. This is typical for arrays more than λ/2 wide when equal currents flow in each element. Sidelobe amplitude can be reduced by using non-uniform current distribution among the elements. Many possible current amplitude distributions have been suggested. All of them have reduced current in the outer elements and greater current in the inner elements. This reduces the gain somewhat but can produce a more desirable pattern. One of the common current distributions is called *binomial current grading*. In this scheme the ratio of element currents is set equal to the coefficients of a polynomial. For example:

$$\begin{aligned}
&1\,x+1, \quad \Rightarrow \; 1,1 \\
&(x+1)^2 = 1x^2+2x+1, \quad \Rightarrow \; 1,\,2,\,1 \\
&(x+1)^3 = 1x^3+3x^2+3x+1, \quad \Rightarrow \; 1,\,3,\,3,\,1 \\
&(x+1)^4 = 1x^4+4x^3+6x^2+6x+1, \quad \Rightarrow \; 1,\,4,\,6,\,4,\,1
\end{aligned} \tag{Eq 7}$$

In a 2-element array the currents are equal, in a 3-element array the current in the center element is twice that in the outer elements, and so on.

HALF-SQUARE ANTENNA

On the low-frequency bands (40, 80 and 160 meters) it becomes increasingly difficult to use λ/2 elements because of their size. The half-square antenna is a 2-element broadside array with λ/4-high vertical elements and λ/2 horizontal spacing. See **Fig 52**. The free-space H-plane pattern for this array is shown in **Fig 53**. The antenna gives modest (4.2 dBi) but useful gain and has the advantage of only λ/4 height. Like all vertically polarized antennas, real-world performance depends directly on the characteristics of the ground surrounding it.

The half-square can be fed either at the point indicated or at the bottom end of one of the vertical elements using a voltage-feed scheme, such as that shown in **Fig 54** for the bobtail curtain. The feed-point impedance is in the region of 50 Ω when fed at a corner as shown in Fig 52. A typical SWR plot is shown in **Fig 55**. Chapter 6 has a detailed discussion of the half-square antenna with several variations, together with practical considerations.



Fig 54—The bobtail curtain is an excellent low-angle radiator having broadside bidirectional characteristics. Current distribution is represented by the arrows. Dimensions A and B (in feet, for wire antennas) can be determined from the equations.



Fig 55—Typical SWR plot for a 40-meter half-square antenna fed at one corner. Antenna in free space.



Fig 56—Calculated free-space E-plane directive diagram of the bobtail curtain shown in Fig 54. The array lies along the 90°-270° axis.



Fig 57—Typical SWR plot for an 80-meter bobtail curtain in free space. This is a narrow-band antenna.

BOBTAIL CURTAIN

The antenna system in Fig 54 uses the principles of co-phased verticals to produce a broadside, bidirectional pattern providing approximately 5.1 dB of gain over a single $\lambda/4$ element. The antenna performs as three in-phase, top-fed vertical radiators approximately $\lambda/4$ in height and spaced approximately $\lambda/2$. It is most effective for low-angle signals and makes an excellent long-distance antenna for 1.8, 3.5 or 7 MHz.

The three vertical sections are the actual radiating components, but only the center element is fed directly. The two horizontal parts, A, act as phasing lines and contribute very little to the radiation pattern. Because the current in the center element must be divided between the end sections, the current distribution approaches a binomial 1:2:1 ratio. The radiation pattern is shown in **Fig 56**.

The vertical elements should be as vertical as possible. The height for the horizontal portion should be slightly greater than B, as shown in Fig 54. The tuning network is resonant at the operating frequency. The L/C ratio should be fairly low to provide good loading characteristics. As a starting point, a maximum capacitor value of 75 to 150 pF is recommended, and the inductor value is determined by C and the operating frequency. The network is first tuned to resonance and then the tap point is adjusted for the best match. A slight readjustment of C may be necessary. A link coil consisting of a few turns can also be used to feed the antenna.

A feeling for the matching bandwidth of this antenna can be obtained by looking at a feed point located at the top end of the center element. The impedance at this point will be approximately 32 Ω. An SWR plot (for $Z_0 = 32\ \Omega$) for an 80-meter bobtail curtain at this feed-point is shown in **Fig 57**. However, it is not advisable to actually connect a feed line at this point since it would detune the array and alter the pattern. This antenna is relatively narrow band. When fed at the bottom of the center element as shown in Fig 54, the SWR can be adjusted to be 1:1 at one frequency but the operating bandwidth for SWR < 2:1 may be even narrower than Fig 57 shows. For 80-meters, where operation is often desired in the CW DX window (3.510 MHz) and in the phone DX window (3.790 MHz), it will be necessary to retune the matching network as you change frequency. This can be done by switching a capacitor in or out, manually or remotely with a relay.

While the match bandwidth is quite narrow, the radiation pattern changes more slowly with frequency. **Fig 58** shows the variation in the pattern over the entire band (3.5 to 4.0 MHz). As would be expected, the gain increases with frequency because the antenna is larger in terms of wavelengths. The general shape of the pattern, however, is quite stable.



Fig 58—80-meter bobtail curtain's free-space E-plane pattern variation over the 80-meter band.

THE BRUCE ARRAY

Four variations of the Bruce array are shown in **Fig 59**. The Bruce is simply a wire folded so that the vertical sections carry large in-phase currents, while the horizontal sections carry small currents flowing in opposite directions with respect to the center of a section (indicated by dots). The radiation is vertically polarized. The gain is proportional to the length of the array but is somewhat smaller than you can obtain from a broadside array of λ/2 elements of the same length. This is because the radiating portion of the elements is only λ/4.

The Bruce array has a number of advantages:

1) The array is only λ/4 high. This is especially helpful on 80 and 160 meters, where the height of λ/2 supports becomes impractical for most amateurs.

2) The array is very simple. It is just a single piece of wire folded to form the array.

3) The dimensions of the array are very flexible. Depending on the available distance between supports, any number of elements can be used. The longer the array, the greater the gain.

4) The shape of the array does not have to be exactly 1.05 λ/4 squares. If the available height is short but the array can be made longer, then shorter vertical sections and longer horizontal sections can be used to maintain gain and resonance. Conversely, if more height is available but width is restricted then longer vertical sections can be used with shorter horizontal sections.

5) The array can be fed at other points more convenient for a particular installation.

6) The antenna is relatively low Q, so that the feed-point impedance changes slowly with frequency. This is very helpful on 80 meters, for example, where the antenna can be relatively broadband.

7) The radiation pattern and gain is stable over the width of an amateur band.

Note that the nominal dimensions of the array in Fig 59 call for section lengths = 1.05 λ/4. The need to use slightly longer elements to achieve resonance is common in large wire arrays. A quad loop behaves in the same manner. This is quite different from wire dipoles, which are typically *shortened* by 2-5% to achieve resonance.

Fig 60 shows the variations in gain and pattern for 2 to 5-element 80-meter Bruce arrays. **Table 2** lists the gain over a vertical λ/2 dipole, a 4-radial ground-plane vertical and the size of the array. The gain and impedance parameters listed are for free space. Over real ground the patterns and gain will depend on the height above ground and the ground characteristics. Copper loss using #12 conductors in included.

Worthwhile gain can be obtained from these arrays, especially on 80 and 160 meters, where any gain is hard to come by. The feed-point impedance is for the center of a vertical section. From the patterns in Fig 60 you can see that sidelobes start to appear as the length of the array is increased beyond 3λ/4. This is typical for arrays using equal currents in the elements.

It is interesting to compare the bobtail curtain (Fig 54) with a 4-element Bruce array. **Fig 61** compares the radiation patterns for these two antennas. Even though the Bruce is shorter (3λ/4) than the bobtail (1 λ), it has slightly more


1.05 λ/8
2 – Element
1.05 λ/4
(A)
3 – Element
(B)
4 – Element
(C)
5 – Element
(D)
ANT0352

Fig 59—Various Bruce arrays: 2, 3, 4 and 5-element versions.

Table 2
Bruce array length, impedance and gain as a function of number of elements

Number Elements	*Gain Over λ/2 Vertical Dipole*	*Gain over λ/4 Ground-Plane*	*Array Length Wavelengths*	*Approx. Feed Z, Ω*
2	1.2 dB	1.9 dB	¼	130
3	2.8 dB	3.6 dB	½	200
4	4.3 dB	5.1 dB	¾	250
5	5.3 dB	6.1 dB	1	300

gain. The matching bandwidth is illustrated by the SWR curve in **Fig 62**. The 4-element Bruce has over twice the match bandwidth (200 kHz) than does the bobtail (75 kHz in Fig 57). Part of the gain difference is due to the binomial current distribution—the center element has twice the current as the outer elements in the bobtail. This reduces the gain slightly so that the 4-element Bruce becomes competitive. This is a good example of using more than the minimum number of elements to improve performance or to reduce size. On 160 meters the 4-element Bruce will be 140 feet shorter than the bobtail, a significant reduction. If additional space is available for the bobtail (1 λ) then a 5-element Bruce could



Fig 60—80-meter free-space E-plane directive patterns for the Bruce arrays shown in Fig 59. The 5-element's pattern is a solid line; the 4-element is a dashed line; the 3-element is a dotted line, and the 2-element version is a dashed-dotted line.



Fig 61—Comparison of free space patterns of a 4-element Bruce array (solid line) and a 3-element bobtail curtain (dashed line).



Fig 62—Typical SWR curve for a 4-element 80-meter Bruce array.



Fig 63—Alternate feed arrangements for the Bruce array. At A, the antenna is driven against a ground system and at B, it uses a two-wire counterpoise.

be used, with a small increase in gain but also introducing some sidelobes.

The 2-element Bruce and the half-square antennas are both 2-element arrays. However, since the spacing between radiators is greater in the half-square (λ/2) the gain of the half-square is about 1 dB greater. If space is available, the half-square would be a better choice. If there is not room for a half-square then the Bruce, which is only half as long (λ/4), may be a good alternative. The 3-element Bruce, which has the same length (λ/2) as the half-square, has about 0.6 dB more gain than the half-square and will have a wider match bandwidth.

The Bruce antenna can be fed at many different points and in different ways. In addition to the feed points indicated in Fig 59, you may connect the feed line at the center of any of the vertical sections. In longer Bruce arrays, feeding at one end will result in some current imbalance among the elements but the resulting pattern distortion is small. Actually, the feed-point can be anywhere along a vertical section. One very convenient point is at an outside corner. The feed-point impedance will be higher (about 600 Ω). A good match for 450-Ω ladder-line can usually be found somewhere on the vertical section. It is important to recognize that feeding the antenna at a voltage node (dots in Fig 59) by breaking the wire and inserting an insulator, completely changes the current distribution. This will be discussed in the section on endfire arrays.

A Bruce can be fed unbalanced against ground or against a counterpoise as shown in **Fig 63**. Because it is a vertically polarized antenna, the better the ground system, the better the performance. As few as two elevated radials can be used as shown in Fig 63B, but more radials can also be used to improve the performance, depending on local ground constants. The original development of the Bruce array in the late 1920s used this feed arrangement.

FOUR-ELEMENT BROADSIDE ARRAY

The 4-element array shown in **Fig 64** is commonly known as the *lazy H*. It consists of a set of two collinear elements and a set of two parallel elements, all operated in-phase to give broadside directivity. The gain and directivity will depend on the spacing, as in the case of a simple parallel-element broadside array. The spacing may be chosen between the limits shown on the drawing, but spacings below 3λ/8 are not worthwhile because the gain is small. Estimated gains compared to a single element are:

3λ/8 spacing—4.2 dB
λ/2 spacing—5.8 dB
5λ/8 spacing—6.7 dB
3λ/4 spacing—6.3 dB

Half-wave spacing is generally used. Directive patterns for this spacing are given in **Figs 65** and **66**. With λ/2 spacing between parallel elements, the impedance at the junction of the phasing line and transmission line is resistive and in the vicinity of 100 Ω. With larger or smaller spacing the impedance at this junction will be reactive as well as resistive. Matching stubs are recommended in cases where a non-resonant line is to be used. They may be calculated and adjusted as described in Chapter 26.



Fig 64—Four-element broadside array ("lazy H") using collinear and parallel elements.

The system shown in Fig 64 may be used on two bands having a 2-to-1 frequency relationship. It should be designed for the higher of the two frequencies, using 3λ/4 spacing between parallel elements. It will then operate on the lower frequency as a simple broadside array with 3λ/8 spacing.

An alternative method of feeding is shown in the small diagram in Fig 64. In this case the elements and the phasing line must be adjusted exactly to an electrical half wavelength. The impedance at the feed point will be resistive and on the order of 2 kΩ.

THE BI-SQUARE ANTENNA

A development of the lazy H, known as the *bi-square antenna*, is shown in **Fig 67**. The gain of the bi-square is somewhat less than that of the lazy-H, but this array is attractive because it can be supported from a single pole. It has a circumference of 2 λ at the operating frequency, and is horizontally polarized.

The bi-square antenna consists of two 1 λ radiators, fed 180° out-of-phase at the bottom of the array. The radiation resistance is 300 Ω, so it can be fed with either 300- or 600-Ω line. The free space gain of the antenna is about 5.8 dBi, which is 3.7 dB more than a single dipole element. Gain may be increased by adding a parasitic reflector or director. Two bi-square arrays can be mounted at right angles and switched to provide omnidirectional coverage. In this way, the antenna wires may be used as part of the guying system for the pole.

Although it resembles a loop antenna, the bi-square is not a true loop because the ends opposite the feed point



Fig 65—Free-space directive diagrams of the 4-element antenna shown in Fig 64. At A is the E-plane pattern. The axis of the elements lies along the 90°-270° line. At B is the free-space H-plane pattern, viewed as if one set of elements is above the other from the ends of the elements.

are open. However, identical construction techniques can be used for the two antenna types. Indeed, with a means of remotely closing the connection at the top for lower frequency operation, the antenna can be operated on two harmonically related bands. As an example, an array with 17 feet per side can be operated as a bi-square at 28 MHz and as a full-wave loop at 14 MHz. For two-band operation in this manner, the side length should favor the higher frequency. The length of a closed loop is not as critical.



Fig 66—Vertical pattern of the 4-element broadside antenna of Fig 64, when mounted with the elements horizontal and the lower set λ/4 above flat ground. Stacked arrays of this type give best results when the lowest elements are at least λ/2 high. The gain is reduced and the wave angle raised if the lowest elements are too close to ground.



Fig 67—The bi-square array. It has the appearance of a loop, but is not a true loop because the conductor is open at the top. The length of each side, in feet, is 480/f (MHz).

End-Fire Arrays

The term *end-fire* covers a number of different methods of operation, all having in common the fact that the maximum radiation takes place along the array axis, and that the array consists of a number of parallel elements in one plane. End-fire arrays can be either bidirectional or unidirectional. In the bidirectional type commonly used by amateurs there are only two elements, and these are operated with currents 180° out-of-phase. Even though adjustment tends to be complicated, unidirectional end-fire driven arrays have also seen amateur use, primarily as a pair of phased, ground-mounted λ/4 vertical elements. Extensive discussion of this array is contained in earlier sections of this chapter.

Horizontally polarized unidirectional end-fire arrays see little amateur use except in log-periodic arrays (described in Chapter 10). Instead, horizontally polarized unidirectional arrays usually have parasitic elements (described in Chapter 11) and are called Yagis.

TWO-ELEMENT END-FIRE ARRAY

In a 2-element array with equal currents out-of-phase, the gain varies with the spacing between elements as shown in **Fig 68**. The maximum gain occurs in the neighborhood of 0.1 λ spacing. Below that the gain drops rapidly due to conductor loss resistance.

The feed-point resistance for either element is very low at the spacings giving greatest gain, as shown in Fig 8 earlier in this chapter. The spacings most frequently used are λ/8 and λ/4, at which the resistances of center-fed λ/2 elements are about 9 and 32 Ω, respectively.

The effect of conductor resistance on gain for various spacings is shown in **Fig 69**. Because current along the element is not constant (it is approximately sinusoidal), the resistance shown is the equivalent resistance (R_{eq}) inserted at the center of the element to account for the loss distributed along the element.

The equivalent resistance of a λ/2 element is one half the ac resistance (R_{ac}) of the complete element. R_{ac} is usually >> R_{dc} due to skin effect. For example, a 1.84 MHz dipole using #12 copper wire will have the following R_{eq}:

Wire length = 267 feet
Rdc = 0.00159 [/foot] × 267 [feet] = 0.42
Fr = Rac/Rdc = 10.8
Req =(Rdc/2) × Fr = 2.29



Fig 68—Gain of an end-fire array consisting of two elements fed 180° out-of-phase, as a function of the spacing between elements. Maximum radiation is in the plane of the elements and at right angles to them at spacings up to λ/2, but the direction changes at greater spacings.



Fig 69—Gain over a single element of two out-of-phase elements in free space as a function of spacing for various loss resistances.

For a 3.75 MHz dipole made with #12 wire, Req = 1.59 Ω. In Fig 69, it is clear that end-fire antennas made with #12 or smaller wire will limit the attainable gain because of losses. There is no point in using spacings much less than λ/4 if you use wire elements. If instead you use elements made of aluminum tubing then smaller spacings can be used to increase gain. However, as the spacing is reduced below λ/4 the increase in gain is quite small even with good conductors. Closer spacings give little gain increase but can drastically reduce the operating bandwidth due to the rapidly increasing Q of the array.

Unidirectional End-Fire Arrays

Two parallel elements spaced λ/4 apart and fed equal currents 90° out-of-phase will have a directional pattern in the plane at right angles to the plane of the array. See **Fig 70**. The maximum radiation is in the direction of the element in which the current lags. In the opposite direction the fields from the two elements cancel.

When the currents in the elements are neither in-phase nor 180° out-of-phase, the feed-point resistances of the elements are not equal. This complicates the problem of feeding equal currents to the elements, as discussed in earlier sections.



Fig 70—Representative H-plane pattern for a 2-element end-fire array with 90° spacing and phasing. The elements lie along the vertical axis, with the uppermost element the one of lagging phase. Dissimilar current distributions are taken into account. (Pattern computed with *ELNEC*.)



Fig 71—H-plane pattern for a 3-element end-fire array with binomial current distribution (the current in the center element is twice that in each end element). The elements are spaced λ/4 apart along the 0°-180° axis. The center element lags the lower element by 90°, while the upper element lags the lower element by 180° in phase. Dissimilar current distributions are taken into account. (Pattern computed with *ELNEC*.)

More than two elements can be used in a unidirectional end-fire array. The requirement for unidirectivity is that there must be a progressive phase shift in the element currents equal to the spacing, in electrical degrees, between the elements. The amplitudes of the currents in the various elements also must be properly related. This requires binomial current distribution. In the case of three elements, this requires that the current in the center element be twice that in the two outside elements, for 90° (λ/4) spacing and element current phasing. This antenna has an overall length of λ/2. The directive diagram is shown in **Fig 71**. The pattern is similar to that of Fig 70, but the 3-element binomial array has greater directivity, evidenced by the narrower half-power beamwidth (146° versus 176°). Its gain is 1.0 dB greater.

THE W8JK ARRAY

As pointed out earlier, John Kraus, W8JK, described his bidirectional flat-top W8JK beam antenna in 1940. See **Fig 72**. Two λ/2 elements are spaced λ/8 to λ/4 and driven 180° out-of-phase. The free-space radiation pattern for this antenna, using #12 copper wire, is given in **Fig 73**. The pattern is representative of spacings between λ/8 and λ/4 where the gain varies less than 0.5 dB. The gain over a dipole is about 3.3 dB (5.4 dBi referenced to an isotropic radiator), a worthwhile improvement. The feed-point impedance (including wire resistance) of *each* element is about 11 Ω for λ/8 spacing and 33 Ω for λ/4 spacing. The feed-point impedance at the center connection will depend on the length and Z_0 of the connecting transmission line.

Kraus gave a number of other variations for end-fire arrays, some of which are shown in **Fig 74**. The ones fed at the center (A, C and E) are usually horizontally polarized flat-top beams. The end-fed versions (B, D & F) are usually vertically polarized, where the feed point can be conveniently near ground.

A practical variation of Fig 74B is given in **Fig 75**. In this example, the height is limited to λ/4 so the ends can be bent over as shown, producing a 2-element Bruce array. This reduces the gain somewhat but allows much shorter supports, an important consideration on the low bands. If additional height is available, then you can achieve some additional gain. The upper ends can be bent over to fit the available height. The feed-point impedance will greater than 1 kΩ.



Fig 72—A 2-element W8JK array.



Fig 73—Free-space E-plane pattern for the 2-element W8JK array


Gap
λ/8
λ/8
λ/4
λ/4
Trans. Line
λ/8
λ/8
ANT0368

Fig 75—A 2-element end-fire array with reduced height.


S
(A)
λ/4
λ/4
S
(B)
λ/2
S
(C)
λ/2
λ/2
λ/2
S
(D)
λ/2
λ/2
S
(E)
λ/2
λ/2
S
(F)
λ/2
ANT0367

Fig 74—Six other variations of W8JK “flat-top beam” antennas.

FOUR-ELEMENT END-FIRE AND COLLINEAR ARRAYS

The array shown in **Fig 76** combines collinear in-phase elements with parallel out-of-phase elements to give both broadside and end-fire directivity. It is a *two-section W8JK*. The approximate free-space gain using #12 copper wire is 4.9 dBi with λ/8 spacing and 5.4 dBi with λ/4 spacing. Directive patterns are given in **Figs 77** for free space, and in **Fig 78** for heights of 1 λ and λ/2 above flat ground.

The impedance between elements at the point where the phasing line is connected is of the order of several thousand ohms. The SWR with an unmatched line consequently is quite high, and this system should be constructed with open-wire line (500 or 600 Ω) if the line is to be resonant. With λ/4 element spacing the SWR on a 600 Ω line is estimated to be in the vicinity of 3 or 4:1.



Fig 76—A 4-element array combining collinear broadside elements and parallel end-fire elements, popularly known as a two-section W8JK array.



Fig 77—Free-space E-plane pattern for the antenna shown in Fig 76, with λ/8 spacing. The elements are parallel to the 90°-270° line in this diagram. Less than a 1° change in half-power beamwidth results when the spacing is changed from λ/8 to λ/4.



Fig 78—Elevation-plane pattern for the 4-element antenna of Fig 76 when mounted horizontally at two heights over flat ground. Solid line = 1 λ high; dashed line = λ/2 high.

To use a matched line, you could connect a closed stub 3λ/16 long at the transmission-line junction shown in Fig 76. The transmission line itself can then be tapped on this matching section at the point resulting in the lowest line SWR. This point can be determined by trial.

This type of antenna can be operated on two bands having a frequency ratio of 2 to 1, if a resonant feed line is used. For example, if you design for 28 MHz with λ/4 spacing between elements, you can also operate on 14 MHz as a simple 2-element end-fire array having λ/8 spacing.

Combination Driven Arrays

You can readily combine broadside, end-fire and collinear elements to increase gain and directivity, and this is in fact usually done when more than two elements are used in an array. Combinations of this type give more gain, in a given amount of space, than plain arrays of the types just described. Since the combinations that can be worked out are almost endless, this section describes only a few of the simpler types.

The accurate calculation of the power gain of a multi-element array requires a knowledge of the mutual impedances between all elements, as discussed in earlier sections. For approximate purposes it is sufficient to assume that each set (collinear, broadside, end-fire) will have the gains as given earlier, and then simply add up the gains for the combination. This neglects the effects of cross-coupling between sets of elements. However, the array configurations are such that the mutual impedances from cross-coupling should be relatively small, particularly when the spacings are λ/4 or more, so the estimated gain should be reasonably close to the actual gain. Alternatively, an antenna modeling program, such as *EZNEC*, can give good estimates of all parameters for a real-world antenna, providing that you take care to model all applicable parameters.

FOUR-ELEMENT DRIVEN ARRAYS

The array shown in **Fig 79** combines parallel elements with broadside and end-fire directivity. The smallest array (physically)—3λ/8 spacing between broadside and λ/8 spacing between end-fire elements—has an estimated gain of 6.5 dBi and the largest—3λ/4 and λ/4 spacing, respectively—about 8.4 dBi. Typical directive patterns for a λ/4 × λ/2 array are given in **Figs 80** and **81**.

The impedance at the feed point will not be purely resistive unless the element lengths are correct and the phasing lines are exactly λ/2 long. (This requires somewhat less than λ/2 spacing between broadside elements.) In this case the impedance at the junction is estimated to be over 10 kΩ. With other element spacings the impedance at the junction will be reactive as well as resistive, but in any event the SWR will be quite large. An open-wire line can be used as a resonant line, or a matching section may be used for non-resonant operation.



Fig 79—Four-element array combining both broadside and end-fire elements.



Fig 80—Free-space H-plane pattern of the 4-element antenna shown in Fig 79.



Fig 81—Vertical pattern of the antenna shown in Fig 79 at a mean height of 3λ/4 (lowest elements λ/2 above flat ground) when the antenna is horizontally polarized. For optimum gain and low wave angle the mean height should

EIGHT-ELEMENT DRIVEN ARRAYS

The array shown in **Fig 82** is a combination of collinear and parallel elements in broadside and end-fire directivity. Common practice in a wire antenna is to use λ/2 spacing for the parallel broadside elements and λ/4 spacing for the end-fire elements. This gives a free-space gain of about 9.1 dBi. Directive patterns for an array using these spacings are similar to those of Figs 80 and 81, but are somewhat sharper.

The SWR with this arrangement will be high. Matching stubs are recommended for making the lines non-resonant. Their position and length can be determined as described in Chapter 26.



Fig 82—Eight-element driven array combining collinear and parallel elements for broadside and end-fire directivity.

This system can be used on two bands related in frequency by a 2-to-1 ratio, providing it is designed for the higher of the two, with 3λ/4 spacing between the parallel broadside elements and λ/4 spacing between the end-fire elements. On the lower frequency it will then operate as a 4-element antenna of the type shown in Fig 79, with 3λ/8 broadside spacing and λ/8 end-fire spacing. For two-band operation a resonant transmission line must be used.

PHASING ARROWS IN ARRAY ELEMENTS

In the antenna diagrams of preceding sections, the relative direction of current flow in the various antenna elements and connecting lines was shown by arrows. In laying out any antenna system it is necessary to know that the phasing lines are properly connected; otherwise the antenna may have entirely different characteristics than anticipated. The phasing may be checked either on the basis of current direction or polarity of voltages. There are two rules to remember:

1) In every λ/2 section of wire, starting from an open end, the current directions reverse. In terms of voltage, the polarity reverses at each λ/2 point, starting from an open end.
2) Currents in transmission lines always must flow in opposite directions in adjacent wires. In terms of voltage, polarities always must be opposite.

Examples of the use of current direction and voltage polarity are given at A and B, respectively, in **Fig 83**. The λ/2 points in the system are marked by small circles. When current in one section flows toward a circle, the current in the next section must also flow toward it, and vice versa. In the 4-element antenna shown at A, the current in the upper right-hand element cannot flow toward the transmission line because then the current in the right-hand section of the phasing line would have to flow upward and thus would be flowing in the same direction as the current in the left-hand wire. The phasing line would simply act like two wires in parallel in such a case. Of course, all arrows in the drawing could be reversed, and the net effect would be unchanged.



Fig 83—Methods of checking the phase of currents in elements and phasing lines.

C shows the effect of transposing the phasing line. This transposition reverses the direction of current flow in the lower pair of elements, as compared with A, and thus changes the array from a combination collinear and end-fire arrangement into a collinear-broadside array.

The drawing at D shows what happens when the transmission line is connected at the center of a section of phasing line. Viewed from the main transmission line, the two parts of the phasing line are simply in parallel, so the half wavelength is measured from the antenna element along the upper section of phasing line and thence along the transmission line. The distance from the lower elements is measured in the same way. Obviously, the two sections of phasing line should be the same length. If they are not, the current distribution becomes quite complicated; the element currents are neither in-phase nor 180° out-of-phase, and the elements at opposite ends of the lines do not receive the same current. To change the element current phasing at D into the phasing at A, simply transpose the wires in one section of the phasing line. This reverses the direction of current flow in the antenna elements connected to that section of phasing line.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2.

D. W. Atchley, H. E. Stinehelfer, and J. F. White, “360°-Steerable Vertical Phased Arrays,” *QST*, Apr 1976, pp 27-30.

G. H. Brown, “Directional Antennas,” *Proc. IRE*, Vol 25, No. 1, Jan 1937, pp 78-145.

G. H. Brown, R. F. Lewis and J. Epstein, “Ground Systems as a Factor in Antenna Efficiency,” *Proc. IRE*, Jun 1937, pp 753-787.

G. H. Brown and O. M. Woodward, Jr., “Experimentally Determined Impedance Characteristics of Cylindrical Antennas,” *Proc. IRE*, Apr 1945.

L. B. Cebik, “Two Limitations of NEC-4”, **www.cebik.com/model/fd.html**.

A. Christman, “Feeding Phased Arrays: An Alternate Method,” *Ham Radio*, May 1985, pp 58-59, 61-64.

J. Devoldere, *ON4UN’s Low-Band DXing*, 4th ed. (Newington, CT: ARRL, 2005).

EZNEC is an antenna-modeling computer program for Microsoft Windows. See **eznec.com** for full information.

F. Gehrke, “Vertical Phased Arrays,” in six parts, *Ham Radio*, May-Jul, Oct and Dec 1983, and May 1984.

C. Harrison, Jr, and R. King, “Theory of Coupled Folded Antennas,” *IRE Trans on Antennas and Propagation*, Mar 1960, pp131-135.

W. Hayward and D. DeMaw, *Solid State Design for the Radio Amateur* (Newington, CT: ARRL, 1977).

W. Hayward, *Radio Frequency Design* (Newington, CT: ARRL, 1994).

H. Jasik, *Antenna Engineering Handbook*, 1st ed. (New York: McGraw-Hill, 1961). Later editions are edited by Richard C. Johnson.

R. King and C. Harrison, Jr, "Mutual and Self-Impedance for Coupled Antennas," *Journal of Applied Physics* , Vol 15, Jun 1944, pp 481-495.

R. King, "Self- and Mutual Impedances of Parallel Identical Antennas," *Proc. IRE*, Aug 1952, pp 981-988.

R. W. P. King, *Theory of Linear Antennas* (Cambridge, MA: Harvard Univ Press, 1956), p 275ff.

H. W. Kohler, "Antenna Design for Field-Strength Gain," *Proc. IRE*, Oct 1944, pp 611-616.

J. D. Kraus, "Antenna Arrays with Closely Spaced Elements," *Proc. IRE*, Feb, 1940, pp 76-84.

J. D. Kraus, *Antennas*, 2nd ed. (New York: McGraw-Hill Book Co., 1988).

Johnson, Richard C., *Antenna Engineering Handbook*, 3rd ed. (New York: McGraw-Hill Inc., 1993). This is a later edition of the volume by the same name edited by H. Jasik.

E. A. Laport, *Radio Antenna Engineering* (New York: McGraw-Hill Book Co, 1952).

J. L. Lawson, "Simple Arrays of Vertical Antenna Elements," *QST*, May 1971, pp 22-27.

P. H. Lee, N6PL *The Amateur Radio Vertical Antenna Handbook*, 2nd ed. (Hicksville, NY: CQ Publishing, Inc., 1984).

R. W. Lewallen, "Baluns: What They Do and How They Do It," *The ARRL Antenna Compendium, Vol 1* (Newington: ARRL, 1985). Also available for viewing at **eznec.com/Amateur/Articles/Baluns.pdf**.

R. Lewallen, "The Impact of Current Distribution on Array Patterns," Technical Correspondence, *QST*, Jul 1990, pp 39-40. Also available for viewing at **eznec.com/Amateur/Articles/Current_Dist.pdf**.

R. Lewallen, "*MININEC*—The Other Edge of the Sword", *QST*, Feb 1991, pp 18-22. *ELNEC*, referenced in the article, is no longer available.

M. W. Maxwell, "Some Aspects of the Balun Problem," *QST*, Mar 1983, pp 38-40.

J. Sevick, "The Ground-Image Vertical Antenna," *QST*, Jul 1971, pp 16-19, 22.

J. Sevick, "The W2FMI Ground-Mounted Short Vertical," *QST*, Mar 1973, pp 13-28,41.

E. J. Wilkinson, "An N-Way Hybrid Power Divider," *IRE Transactions on Microwave Theory and Techniques*, Jan, 1960.

Radio Broadcast Ground Systems, available from Smith Electronics, Inc, 8200 Snowville Rd, Cleveland, OH 44141.

Appendix A—*EZNEC-ARRL* Examples

This appendix contains step-by-step procedures using *EZNEC-ARRL* (included on the *Antenna Book* CD) to illustrate various topics discussed in the main chapter. A standard *EZNEC* program type of v. 4.0 or later may also be used. Different versions, program types and calculating engines may give results that are slightly different from those shown in the examples. However, any differences should be insignificantly small.

EZNEC Example—Mutual Coupling

Illustrates the effect of mutual coupling on feed-point impedance. Open the **ARRL_Cardioid.EZ** file, which is mounted over "perfect" ground. Click the **View Ant** button to see a diagram of the antenna, a 2-element array of vertical elements. Click on the **Wires** line in the main window to open the Wires Window. Click the button at the left of the Wire 2 line, and then press the **Delete** key on your keyboard to delete wire #2. After clicking **Ok**, note that one of the verticals has disappeared from the View Antenna display, leaving a single element. Click **Src Dat** and note that the feed-point impedance of this single vertical is about $37 + j\,1\ \Omega$--it's very nearly resonant.

Next, in the Wires Window, open the **Edit** menu at the top and click **Undo delete wire(s)** to restore the second element. Click **Src Dat** again and notice that the feed-point impedance of wire #1 is now about $21 - j\,19\ \Omega$. The feed-point impedance of the second element, which is identical to the first, is about $52 + j\,21\ \Omega$. This difference, and the change from the self-impedance of $37 + j\,1\ \Omega$, is due to mutual coupling. As you see, it's not at all a minor effect.

As an additional exercise, change the magnitude or phase angle of the source at the base of wire #2 (click **Sources** in the main window), and see how this changes the feed-point impedances of both elements. You should be able to confirm each of the four points enumerated in the **MUTUAL COUPLING** section.

EZNEC Example—Nulls

Illustrates the effect of current magnitude on nulls and gain. Again, open the **ARRL_Cardioid.EZ** file. Click the **FF Plot** button to generate the azimuth pattern of an ideal array. Save the plot for future reference as follows: In the plot window, open the **File** menu and select **Save Trace As**. Enter the name **Cardioid** and click **Save**. Now, in the main window click on the **Sources** line to open the Sources Window. Change the magnitude of source 1 from 1 to 1.1, and of source 2 from 1 to 0.9 and press **Enter** on your keyboard so that *EZNEC-ARRL* will accept the last change.

Click **FF Plot** to generate a pattern with the new currents. In the plot window, open the File menu and select **Add**

Trace. Enter the name **Cardioid** and click Open. You should now see the original plot and new plot overlaid. Notice that the null is much less deep with the altered currents, but the forward patterns are nearly identical. By clicking on the names of the traces, **Primary** and **Cardioid**, you can see in turn the gain and front-to-back ratio of each of the traces. The original, **Cardioid**, has a front-to-back ratio of about 32 dB, while Primary, the new plot, has a ratio of about 22.5 dB. The forward gain, however, differs by only 0.02 dB, a completely insignificant amount.

EZNEC Example—"Phasing-Line" Feed

Illustrates the effect of using a "phasing-line" feed. Open the **ARRL_CardTL.EZ** file. This is a model of an array fed with transmission lines whose lengths were designed using the *Arrayfeed1* program to take into account the actual load impedances of elements in a phased array. This model is mounted over "perfect" ground.

Click the **View Ant** button to show the array. Note that the lengths of the lines from the source (circle) to the elements don't represent the actual physical lengths of the lines. In the main window, click on the **Trans Lines** line to open the Transmission Lines window. In it you can see that the lengths of the feed lines, both of which are connected to the same source, are about 81° and 155°, a difference of 74° rather than 90°.

In the main window, click the **Currents** button and take a look at the current shown for segment 1 of wires 1 and 2. These are the currents at the element feed points. The ratio of the magnitude of currents is 4.577/4.561 = 1.003, and the phase difference is –56.3°–(–147.5°) = 91.2°. (A more accurate determination of feed-line lengths with program *Arrayfeed1* gives lengths of 80.61° and 153.70°, resulting in a current ratio of 1.000 at a phase of 90.02°. But the resulting pattern is very nearly the same.) But let's see what happens when we make the lines exactly 90° different in length.

First, click the **FF Plot** button to generate the azimuth pattern of the original model. Save the plot for future reference as follows: In the plot window, open the **File** menu and select **Save Trace As**. Enter the name **CardTL** and click **Save**. Now in the Transmission Lines Window, change the length of line number 1 from 80.56° to 90°. *Important:* In the line 1 Length box, enter **90d** to make the line 90° long. If you omit the **d**, it will become 90 meters long! Similarly, change the length of line 2 to 180° by entering **180d** in the line 2 Length box, then press **Enter** on your keyboard so that *EZNEC* will accept the last change.

Click **FF Plot** to generate a pattern with the new line lengths. In the plot window, open the **File** menu and select **Add Trace**. Enter the name **CardTL** and click **Open**. You should now see the original plot and new plot overlaid together. Notice that the gain of the modified model is about 1 dB greater than the original, but the front-to-back ratio has deteriorated to about 10 dB.

Experiment with different combinations of line lengths that differ by 90°--for example, 45° and 135° (don't forget the '**d**'!), or change the impedance of one or both lines and you'll see that you can get a wide variety of patterns. None, however, are likely to be as close to the ideal cardioid pattern as the original.

Chapter 9

Broadband Antenna Matching

Antenna systems that provide a good impedance match to the transmitter over a wide frequency range have been a topic of interest to hams for many years. Most emphasis has been focused on the 80-meter band since a conventional half-wave dipole will provide better than 2:1 SWR over only about one-third of the 3.5 to 4.0 MHz band. The advantage of a broadband match is obvious—fewer adjustments during tune-up and an antenna tuner may not be required.

This chapter was written by Frank Witt, AI1H, who has written numerous articles in *QST* and in *The ARRL Antenna Compendium* series on this subject. See the Bibliography for details.

The term *broadband antennas* has frequently been used to describe antenna systems that provide a wideband impedance match to the transmitter. This is something of a misnomer, since most antennas are good radiators over a wide range of frequencies and are therefore "broadband antennas" by definition. The problem is getting the energy to the antenna so it can be radiated. Antenna tuners solve this problem in some cases, although losses in transmission lines, baluns and the antenna tuner itself can be excessive. Also worthy of mention is that antenna directional properties are usually frequency dependent. In this chapter, we discuss broadbanding the impedance match to the transmitter only.

GENERAL CONCEPTS

The Objective

Fig 1 shows a simplified system: the transmitter, an SWR meter and the transmitter load impedance. Modern transceivers are designed to operate properly into a 50-Ω load and they will deliver full power into the load impedance, at their rated level of distortion, when the SWR is less than about 1.5:1. Loads beyond this limit may cause the transceiver to protect itself by lowering the output power.

Many transceivers have built-in automatic antenna tuners that permit operation for loads outside the 1.5:1 SWR range, but the matching range is often limited, particularly on the lower-frequency bands. In practice, barefoot operation is simplified if the load SWR is held to less than 2:1.

For high-power amplifiers, it is also best to keep the load SWR to less than about 2:1, since output tuning components are commonly rated to handle such loads. You can see that the primary function of the SWR meter in Fig 1 is to measure the suitability of the load impedance so far as the transmitter is concerned. Henceforth, we will use the term *load SWR* as a description of the transmitter's load.

The SWR meter is actually reading a circuit condition at a single point in the system. In fact, the meter really measures magnitude of the reflection coefficient, but is calibrated in SWR. The relationships between the complex load impedance, Z_L, the magnitude of the reflection coefficient, $|\rho|$, and the load SWR are as follows:

$$|\rho| = \left|\frac{Z_L - 50}{Z_L + 50}\right| \qquad \text{(Eq 1)}$$



Fig 1—Basic antenna system elements at the output of a transmitter.

$$\mathrm{SWR} = \frac{1+|\rho|}{1-|\rho|} \qquad \text{(Eq 2)}$$

where 50 Ω is used as the reference impedance, since the design load impedance for the transmitter is assumed to be 50 Ω.

An important point is that you need not know the output impedance of the transmitter to design a broadband matching network. The issue of the actual value of the output impedance of typical RF power amplifiers is a matter of continuing controversy in amateur circles. Fortunately, this issue is not important for the design of broadband matching networks, since the load SWR is independent of the output impedance of the transmitter. Our objective is to design the matching network so that the load SWR (with a 50-Ω reference resistance) is less than some value, say 2:1, over as wide a band as possible.

Resonant Antennas

The broadband matching techniques described here apply to antennas operating near resonance. Typical resonant antennas include half-wave dipoles, quarter-wave verticals over a ground plane and full-wave loops. To design a broadband matching network, you must know the antenna feed-point impedance near resonance. **Fig 2** shows the antenna-impedance equivalent circuit near resonance. Although the series RLC circuit is an approximation, it is good enough to allow us to design matching networks that significantly increase the band over which a good match to the transmitter is achieved.

Note that the impedance is defined by F_0, the resonant frequency, R_A, the antenna resistance at resonance, and Q_A, the antenna Q. R_A is actually the sum of the radiation resistance and any loss resistance, including conductor losses and losses induced by surrounding objects, such as the ground below the antenna. R_A is frequency dependent, but it is sufficient to assume it is fixed during the matching network design process. Minor adjustments to the matching network will correct for the frequency dependence of R_A.



Fig 2—The equivalent circuit of a resonant antenna. The simple series RLC approximation applies to many resonant antenna types, such as dipoles, monopoles, and loops. R_A, Q_A and F_0 are properties of the entire antenna, as discussed in the text.

The antenna resistance and Q depend on the physical properties of the antenna itself, the properties of ground and the height above ground. Consider as an example an 80-meter horizontal half-wave dipole made from #12 wire located over average ground (dielectric constant = 13 and conductivity = 5 mS/m). **Figs 3** and **4** show how feed-point resistance and Q vary with height. It is clear from these figures that there are wide gyrations in antenna parameters. The better these parameters are known, the more successful we will be at designing the broadband matching network. For horizontal dipoles, Figs 3 and 4 may be used to get a good idea of antenna resistance and Q, so long as the height is scaled in proportion to wavelength. For example, a 160-meter dipole at a height of 100 feet would have about the same resistance and Q as an 80-meter dipole at 50 feet.

For optimum results, the resistance and Q can be



Fig 3—Feed-point resistance (solid line) for 80-meter horizontal dipole at resonance versus height over ground. The free-space value is shown as a dashed line.



Fig 4—Antenna Q for 80-meter horizontal dipole (solid line) versus height. The free-space value is shown as a dashed line.

determined from computer simulation (using a program like *EZNEC,* for example) or measurement (using a low power SWR/Z meter such as the MFJ-259B or the Autek Research VA1 or RF-1). R_A can be computed using SWR measurements at resonance. **Fig 5** shows the typical bowl-shaped SWR curve as a function of frequency for a resonant antenna. S_0 is the SWR at resonance. You must take into account the loss of the feed line if the measurement must be made at the end of a long 50-Ω transmission line. If the line loss is low or if the measurement is made at the antenna terminals, the formulas given below apply.

For $R_A > 50\ \Omega$

$$R_A = S_0 \times 50 \qquad \text{(Eq 3)}$$

For $R_A < 50\ \Omega$

$$R_A = \frac{50}{S_0} \qquad \text{(Eq 4)}$$

There is an ambiguity, since we do not know if R_A is greater than or less than 50 Ω. A simple way of resolving this ambiguity is to take the same SWR measurement at resonance with a 10-Ω non-inductive resistor added in series with the antenna impedance. If the SWR goes up, $R_A > 45\ \Omega$. If the SWR goes down, $R_A < 45\ \Omega$. This will resolve the ambiguity.

Q_A may be determined by measuring the SWR bandwidth. Define BW_2 as the bandwidth over which the resonant antenna SWR is less than 2:1 (in the same units as F_0). See Fig 5.

For $R_A > 50\ \Omega$

$$Q_A = \frac{F_0}{BW_2}\sqrt{2.5 S_0 - S_0^{\,2} - 1} \qquad \text{(Eq 5)}$$

For $R_A < 50\ \Omega$

$$Q_A = \frac{F_0}{BW_2 \times S_0}\sqrt{2.5 S_0 - S_0^{\,2} - 1} \qquad \text{(Eq 6)}$$

Again, you must take into account the loss of the feed line if you make the measurement at the end of a long 50-Ω transmission line.



Fig 5—SWR at the antenna versus frequency in the vicinity of resonance.

For horizontal and inverted-V half-wave dipoles, a very good approximation for the antenna Q when R_A is known is given by:

$$Q_A = \frac{93.9\left[\ln \dfrac{8110}{D\,F_0} - 1\right]}{R_A} \qquad \text{(Eq 7)}$$

where D = the diameter of wire, in inches.

Loss

When you build a resonant antenna with some matching scheme designed to increase the bandwidth, you might overlook the loss introduced by the broadband matching components. Loss in dB is calculated from:

$$\text{Loss} = -10\log\frac{\text{Power radiated by antenna}}{\text{Total power from transmitter}} \qquad \text{(Eq 8)}$$

or, alternatively, define efficiency in % as

$$\text{Efficiency} = \frac{100 \times \text{Power radiated by antenna}}{\text{Total power from transmitter}} \qquad \text{(Eq 9)}$$


3: 1
2: 1
1: 1
SWR
100
50
0
Efficiency (%)
Eff.
SWR
3.5
3.6
3.7
3.8
3.9
4.0
Frequency (MHz)
C
R_A
L
Balun
$L = \dfrac{R_A}{2\pi F_0 Q_A}$
$C = \dfrac{Q_A}{2\pi F_0 R_A}$
F_0 = Dipole Resonant Frequency
R_A = Radiation Resistance
Q_A = Dipole Q

Fig 6—Matching the dipole with a complementary RLC network greatly improves the SWR characteristics, nearly 1:1 across the 3.5-MHz band. However, the relative loss at the band edges is greater than 5 dB.

An extreme degree of bandwidth broadening of an 80-meter dipole is illustrated in **Fig 6**. This approach is not recommended, but it is offered here to make a point. The broadening is accomplished by adding resistive losses. From network theory we obtain the RLC (resistor, inductor, capacitor) matching network shown. The network provides the complement of the antenna impedance. Note that the SWR is virtually 1:1 over the entire band (and beyond), but the efficiency falls off dramatically away from resonance.

The band-edge efficiency of 25 to 30% shown in Fig 6 means that the antenna has about 5 to 6 dB of loss relative to an ideal dipole. At the band edges, 70 to 75% of the power delivered down the transmission line from the transmitter is heating up the matching-network resistor. For a 1-kW output level, the resistor must have a power rating of at least 750 W! Use of an RLC complementary network for broadbanding is not recommended, but it does illustrate how resistance (or losses) in the matching network can significantly increase the apparent antenna SWR bandwidth.

The loss introduced by any broadband matching approach must be taken into consideration. Lossy matching networks will usually provide more match bandwidth improvement than less lossy ones.

SIMPLE BROADBAND MATCHING TECHNIQUES

The Cage Dipole

You can increase the match bandwidth of a single-wire dipole by using a thick radiator, one with a large diameter. The gain and radiation pattern are essentially the same as that of a thin-wire dipole. The radiator does not necessarily have to be solid; open construction such as shown in **Fig 7** may be used.

The theoretical SWR response of an 80-meter cage dipole having a 6-inch diameter is shown in **Fig 8**. BW_2 for this antenna fed with 50-Ω line is 287 kHz, and the Q is approximately 8. Its 2:1-SWR frequency range is 1.79 times broader than a dipole with a Q of 13, typical for thin-wire dipoles.

There are other means of creating a thick radiator, thereby gaining greater match bandwidth. The bow-tie and the fan dipole make use of the same Q-lowering principle as the cage for increased match bandwidth. The broadbanding techniques described below are usually more practical than the unwieldy cage dipole.

Stagger-Tuned Dipoles

A single-wire dipole exhibits a relatively narrow bandwidth in terms of coverage for the 3.5 to 4.0-MHz band. A technique that has been used for years to cover the entire band is to use two dipoles, one cut for the CW portion and one for the phone portion. The dipoles are connected in parallel at the feed point and use a single feeder. This technique is known as *stagger tuning*.

Fig 9 shows the theoretical SWR response of a pair of stagger-tuned dipoles fed with 50-Ω line. No mutual coupling between the wires is assumed, a condition



Fig 8—Theoretical SWR versus frequency response for a cage dipole of length 122 feet 6 inches and a spreader diameter of 6 inches, fed with 50-Ω line. The 2:1-SWR bandwidth frequencies are 3.610 and 3.897 MHz, with a resulting BW_2 of 287 kHz.



Fig 7—Construction of a cage dipole, which has some resemblance to a round birdcage. The spreaders need not be of conductive material, and should be lightweight. Between adjacent conductors, the spacing should be 0.02 λ or less. The number of spreaders and their spacing should be sufficient to maintain a relatively constant separation of the radiator wires.



Fig 9—Theoretical SWR response of two stagger-tuned dipoles. They are connected in parallel at the feed point and fed with 50-Ω line. The dipoles are of wire such as #12 or #14, with total lengths of 119 and 132 feet.

that would exist if the two antennas were mounted at right angles to one another. As Fig 9 shows, the SWR response is less than 1.9:1 across the entire band.

A difficulty with such crossed dipoles is that four supports are required for horizontal antennas. A more common arrangement is to use inverted V dipoles with a single support, at the apex of each element. The radiator wires can also act as guy lines for the supporting mast.

When the dipoles are mounted at something other than a right angle, mutual coupling between them comes into play. This causes interaction between the two elements—tuning of one by length adjustment will affect the tuning of the other. The interaction becomes most critical when the two dipoles are run parallel to each other, suspended by the same supports, and the wires are close together. Finding the optimum length for each dipole for total band coverage can become a tedious and frustrating process.


Extension Above Beam
(UHF Antennas, etc)
21 Ft
6.8 m
Beam
18.5 Ft
5.9 m
46 Ft
14.9 m
Cross - Section View
of Radial Connection,
View from top.
Coax Inside
of Tower
Tower,
Top View
UNUN
50 : 22
80 m Radial
Braid
Insulators
75 m Radial
80 m Radial
Center
Conductor
2 Pairs of Radials, One for
75 m, the Other for 80 m
3.00
2.50
2.00
1.50
1.00
SWR
3.450
3.550
3.650
3.750
3.850
3.950
MHz
(A)
(B)

Fig 10—At A, details of the inverse-fed ground-plane at W4PK. The inset shows the feed-point details. Keep the two sets of radials as close to 90° as possible. Don't try to resonate the antenna by adjusting radial lengths. At B, SWR curve of the inverse-fed ground plane antenna with stagger-tuned radials. The objective is to have a low SWR for both the CW and SSB 80/75-meter DX windows.

Stagger-Tuned Radials

A variation of the use of stagger tuning has been applied by Sam Leslie, W4PK. See his article entitled “Broadbanding the Elevated, Inverse-Fed Ground Plane Antenna” in *The ARRL Antenna Compendium, Vol 6*. An existing tower with a large beam and VHF/UHF antennas on top is used as an 80-meter monopole. See **Fig 10A**. The feed point is part way up the tower, at a point where the metal above it makes up an electrical quarter wavelength. Four elevated quarter-wave radials are used as a ground plane. The radials droop away from the tower. They are joined together at the tower but not connected to the tower. The antenna is fed with 50-Ω coax and an impedance step-down autotransformer (50:22 Ω unun) located at the tower. The shield of the coax is carried through the transformer and connected to the tower. The coax “hot side” is connected to the junction of the radials. A Q-section made from two paralleled RG-59 coax cables ($Z_0 = 75/2 = 37.5\ \Omega$) may be used instead of the autotransformer.

The broadband match is achieved by cutting two opposing radials for one end of the desired match range (75 meters) and cutting the other two for the other end of the range (80 meters). See Fig 10B for the resultant SWR versus frequency characteristic.

FEED-LINE IMPEDANCE MISMATCHING

The simplest broadband matching network is a transformer at the junction of the transmission line and the antenna. See Frank Witt’s article entitled “Match Bandwidth of Resonant Antenna Systems” in October 1991 *QST*. Observe that the impedance of the series RLC resonant antenna model of Fig 2 increases at frequencies away from resonance. The result is that more bandwidth is achieved when SWR at resonance is not exactly 1:1. For example, if the antenna is fed with a low-loss 50-Ω transmission line, the maximum SWR bandwidth is obtained if the effective $R_A = 50/1.25 = 40\ \Omega$. The improvement in BW_2, the 2:1 SWR bandwidth, over a perfect match at resonance is only 6%, however. This condition of $R_A = 40\ \Omega$ can be achieved by installing a transformer at the junction of the feed line and the antenna.

If the line loss is larger, you can gain more benefit in terms of bandwidth by deliberately mismatching at the antenna. If the matched-line loss is 2 dB, the improvement rises to 18%. To achieve this requires an $R_A = 28.2\ \Omega$. Again, the improvement over a perfect match at resonance is modest.

It is interesting to compare the 2:1 SWR bandwidth (at the transmitter end of the line) for the case of a lossless line versus the case of 2-dB matched-line loss. BW_2 for the lossy line case is 1.95 times that of the lossless line case, so substantial match bandwidth improvement occurs, but at the cost of considerable loss. The band edge loss for the lossy-line case is 3 dB!

This example is provided mostly as a reference for comparison with the more desirable broadbanding techniques below. It also explains why some installations with long feed lines show large match bandwidths.

PARALLEL-TUNED CIRCUITS AT THE ANTENNA TERMINALS

As mentioned previously, a resonant antenna has an equivalent circuit that may be represented as a series RLC circuit. We can cancel out some of the antenna reactance away from resonance with a parallel-tuned circuit connected across the antenna terminals. The impedance level of the parallel-tuned circuit must be low enough to be effective and must have the same resonant frequency as the antenna. You can use a parallel-tuned circuit made with lumped LC components or with transmission-line segments. A quarter-wave transmission line with a short at the far end, or a half-wave line with an open at the far end, each behave like a parallel-tuned LC circuit.

The Double Bazooka

The response of the controversial *double bazooka* antenna is shown in **Fig 11**. This antenna actually consists of a dipole with two quarter-wave coaxial resonator stubs connected in series. The stubs are connected across the antenna terminals.

Not much bandwidth enhancement is provided by this resonator connection because the impedance of the matching network is too high. The antenna offers a 2:1-SWR bandwidth frequency range that is only 1.14 times that of a simple dipole with the same feeder. And the bandwidth enhancement is partially due to the “fat” antenna wires composed mostly of the coax shield. No



Fig 11—The double bazooka, sometimes called a coaxial dipole. The antenna is self-resonant at 3.75 MHz. The resonator stubs are 43.23-foot lengths of RG-58A coax.

improvement in antenna gain or pattern over a thin-wire dipole can be expected from this antenna.

The Crossed Double Bazooka

A modified version of the double-bazooka antenna is shown in **Fig 12**. In this case, the impedance of the matching network is reduced to one-fourth of the impedance of the standard double-bazooka network. The lower impedance provides more reactance correction, and hence increases the bandwidth frequency range noticeably, to 1.55 times that of a simple dipole. Notice, however, that the efficiency of the antenna drops to about 80% at the 2:1-SWR points. This amounts to a loss of approximately 1 dB. The broadbanding, in part, is caused by the losses in the coaxial resonator stubs (made of RG-58A coax), which have a remarkably low Q (only 20).

MATCHING NETWORK DESIGN

Optimum Matching

You can improve the match bandwidth by using a transformer or a parallel-tuned circuit at the antenna terminals. A combination of these two techniques can yield a very effective match bandwidth enhancement. Again, you can make the impedance transformation and implement the tuned circuit using lumped-circuit elements (transformers, inductors and capacitors) or with distributed-circuit elements (transmission lines).

In 1950, an article by R. M. Fano presented the theory of broadband matching of arbitrary impedances. This classic work was limited to lossless matching networks. Unfortunately, matching networks realized with transmission lines have enough loss to render the Fano results useful as only a starting point in the design process. A theory of optimum matching with lossy matching networks was presented in an article by Frank Witt entitled "Optimum Lossy Broadband Matching Networks for Resonant Antennas" that appeared in April 1990 *RF Design* and was summarized and extended in "Broadband Matching with the Transmission Line Resonator," in *The ARRL Antenna Compendium Vol 4*.

Using a matching network, the 2:1 SWR bandwidth can be increased by a factor of about 2.5. Instead of the familiar bowl-shaped SWR versus frequency characteristic seen in Fig 5, the addition of the matching network yields the W-shaped characteristic of **Fig 13**. The maximum SWR over the band is S_M. The band edges are F_L and F_H. Thus the bandwidth, BW, and the center frequency, F_0, are

$$BW = F_H - F_L \qquad \text{(Eq 10)}$$

$$F_0 = \sqrt{F_H \times F_L} \qquad \text{(Eq 11)}$$

Fig 14 shows the pertinent equivalent circuit for a typical broadband antenna system. The parallel LC matching network is defined by its resonant frequency, F_0 (which is the same as the resonant frequency of the antenna), its Q and its impedance level. The impedance level is the reactance of either the matching network inductance or capacitance at F_0. The optimum transmitter load resistance,



Fig 12—The crossed double bazooka yields bandwidth improvement by using two quarter-wave resonators, parallel connected, as a matching network. As with the double bazooka, the resonator stubs are 43.23-foot lengths of RG-58A coax.



Fig 13—W-shaped SWR versus frequency characteristic that results when a transformer and parallel LC matching network are used.



Fig 14—Assumed equivalent circuit for the broadband matching system. The antenna and the matching network have the same resonant frequency.

R_G, is achieved using an impedance transformer between the transmitter and the input to the parallel-tuned circuit. Thus for a transmitter whose optimum load resistance is 50 Ω, the required impedance transformer would have an impedance transformation ratio of 50:R_G.

The goal is to keep the SWR over the band as low as possible. There is a best or minimum value of S_M that may be achieved over the entire band. It depends on the desired match bandwidth and the Q's of the antenna and matching network and is given by the following formula:

$$S_{M\,min} = \frac{\sqrt{B_N{}^2 + 1} + \sqrt{B_N{}^2 + 1 + \frac{2Q_A}{Q_N}\left(1 + \frac{Q_A}{2Q_N}\right)}}{2\left(1 + \frac{Q_A}{2Q_N}\right)} \qquad \text{(Eq 12)}$$

where $B_N = \frac{BW}{F_0}$ and

Q_A = antenna Q

Q_N = matching network Q.

The reactance at resonance of the parallel tuned LC matching network is given by:

$$X_{N0} = \frac{R_A}{Q_A}\left[\left(1 + \frac{Q_A}{2Q_N}\right) S_{M\,min}{}^2 - \frac{Q_A}{2Q_N}\right] \qquad \text{(Eq 13)}$$

where R_A = antenna resistance in Ω.

The transmitter load resistance is calculated from:

$$R_G = \frac{S_{M\,min}\, R_A\, Q_N\, X_{N0}}{R_A + Q_N\, X_{N0}} \qquad \text{(Eq 14)}$$

The loss of the matching network is always greatest at the edges of the band. This loss, L_{MNE}, in dB, is given by:

$$L_{MNE} = 10 \log\left[1 + \frac{R_A}{Q_N\, X_{N0}}\left(B_N{}^2 + 1\right)\right] \qquad \text{(Eq 15)}$$

Now you have all the information needed to design an optimal broadband matching network. An 80-meter dipole will serve as an example to illustrate the procedure. The following parameters are assumed:

F_L = 3.5 MHz
F_H = 4.0 MHz
R_A = 57.2 Ω
Q_A = 13
Q_N = 40.65

The values of R_A and Q_A are reasonable values for an 80-meter inverted V with an apex 60 feet above ground. Q_N = 40.65 is the calculated value of the Q of a resonator made from RG-213 or similar cable in the middle of the 80-meter band. The results are:

BW = 0.5 MHz (from Eq 10)
F_0 = 3.742 MHz (from Eq 11)
S_{Mmin} = 1.8 (from Eq 12)
X_{N0} = 15.9 Ω (from Eq 13)
R_G = 94.8 Ω (from Eq 14)
L_{MNE} = 1.32 dB (from Eq 15)

Shown in **Fig 15** is the plot of SWR and matching-network loss versus frequency for this example. The reference resistance for the SWR calculation is R_G or 94.8 Ω. Since the desired load resistance for the transmitter is 50 Ω, we need some means to transform from 94.8 Ω to 50 Ω. The examples given in the rest of this chapter will show a variety of ways of achieving the necessary impedance transformation.

The meaning of X_{N0} = 15.9 Ω is that the inductor and the capacitor in the matching network would each have a reactance of 15.9 Ω at 3.742 MHz. Methods for obtaining a particular value of X_{N0} are shown in the fol-



Fig 15—SWR and matching-network loss for example. Note that S_M is exactly 1.8 and the band-edge loss is exactly 1.32 dB, as calculated.



Fig 16—80-meter dipole example with a 1-λ resonator as the matching network.

lowing examples as well. The particular value of X_{N0} of this example may be obtained with a one-wavelength resonator (open-circuited at the far end) made from RG-213. The system described in this example is shown in **Fig 16**.

The broadband antenna system shown in Fig 16 has a desirable SWR characteristic, but the feed line to the transmitter is not yet present. Fortunately, the same cable segment that makes up the resonator may be used as the feed line. A property of a feed line whose length is a multiple of λ/2 (an even multiple of λ/4) is that its input impedance is a near replica of the impedance at the far end. This is exactly true for lossless lines at the frequencies where the λ/2 condition is true. Fortunately, practical lines have low-enough loss that the property mentioned above is true at the resonant frequency. Off resonance, the desired reactance cancellation we are looking for from the resonant line takes place. The very same design equations apply.

In **Fig 17**, the antenna shown in Fig 16 is moved to the far end of the 1λ resonator. The SWR and loss for this case are shown in **Fig 18**, which should be compared with Fig 15. The SWR is only slightly degraded, but the loss is about the same at the band edges. We have picked up a feed line that is 1λ long (173.5 feet) *and* broadband matching. You can make the SWR curve virtually the same as that of Fig 15 if the transmitter load resistance is increased from 94.8 Ω to 102 Ω. From a practical point of view, this degree of design refinement is unnecessary, but is instructive to know how the SWR characteristic may be controlled. You may apply the same approach when the resonator is an odd multiple of a wavelength, but in that case the transmitter or antenna must be connected λ/4 from the shorted end.



Fig 17—The antenna is at the far end of the 1-λ line. The line does double duty—broadband matching and signal transport.

Chebyshev Matching

Although it is not as efficient from the standpoint of bandwidth improvement and loss, Chebyshev matching is useful for some purposes. This arrangement yields a transmitter load impedance of 50 + *j* 0 Ω at two frequencies in the band. The matching network circuit is the same as the optimum matching case, but the parameters are different. In this case, we assume that the antenna parameters, F_0, R_A and Q_A, the network Q and the maximum SWR over the band are specified. The bandwidth, impedance level and generator resistance are given by:

$$BW = \frac{F_0}{Q_A Q_N} \left\{ \frac{(Q_A + Q_N)\left[(Q_A + 2Q_N)S_M - Q_A\right](S_M - 1)}{S_M} \right\}^{\frac{1}{2}} \quad \text{(Eq 16)}$$

$$X_{N0} = \frac{R_A}{Q_A}\left[S_M + \frac{Q_A}{Q_N}(S_M - 1)\right] \quad \text{(Eq 17)}$$

$$R_G = R_A\left(S_M - \frac{Q_A}{Q_A + Q_N}\right) \quad \text{(Eq 18)}$$

The loss at the band edges is given by Eq 15. The frequencies where the transmitter load is 50 + *j* 0 Ω, F_L and F_H, are given by:

$$F_L = \sqrt{F_0^{\,2} + F_M^{\,2}} - F_M \quad \text{(Eq 19)}$$

where

$$F_M = \frac{F_0}{2Q_A}\left[(S_M - 1)\left(1 + \frac{Q_A}{Q_N}\right)\right]^{\frac{1}{2}} \quad \text{(Eq 20)}$$

$$F_H = \frac{F_0^{\,2}}{F_L} \quad \text{(Eq 21)}$$



Fig 18—SWR and loss for a 1-λ 50-Ω feed line. The antenna system model is the one shown in Fig 17.

LC-MATCHING NETWORKS

Before the theory of optimal matching above was developed, Frank Witt, AI1H, described in his article “Broadband Dipoles—Some New Insights” in October 1986 *QST* the basic principle and some applications of LC matching networks. **Fig 19** shows an LC matching network that is a modified version of one originally proposed by Alan Bloom, N1AL. Note that the basic ingredients are present: the parallel-tuned circuit for reactance cancellation and a transformer.

The network also functions as a voltage balun by connecting the shield of the coaxial feed line to the center tap of the inductor. The capacitor is connected across the entire coil to obtain practical element values. The SWR response and efficiency offered by a network of lumped components is shown in **Fig 20**. The 2:1-SWR bandwidth with 50-Ω line is 460 kHz. The design is a Chebyshev match, where SWR = 1:1 is achieved at two frequencies. For the same configuration, more match bandwidth and less loss could have been realized if the optimal-match theory had been applied.

The efficiency at the band edges for the antenna system shown in Fig 20 is 90% (Loss = 0.5 dB). This low loss is due to the high Q of the LC matching network ($Q_N \approx 200$). The very low-impedance level required (X_{N0} = 12.4 Ω) cannot be easily realized with practical inductor-capacitor values. It is for this reason that the coil is tapped and serves as an autotransformer with multiple taps. The required impedance transformation ratio of 1:2.8 is easily achieved with this arrangement.

80-Meter DXer’s Delight

A version of an antenna system with an LC broadbanding network is dubbed the *80-meter DXer’s Delight*. This antenna has SWR minima near 3.5 and 3.8 MHz. A single antenna permits operation with a transmitter load impedance of about 50 Ω in the DX portions of the band, both CW and phone. The efficiency and SWR characteristic are shown in **Fig 21**.

Fig 22 shows the method of construction. The selection of a capacitor for this application must be made carefully, especially if high power is to be used. For the capacitor described in the caption of Fig 22, the allowable peak power (limited by the breakdown voltage) is 2450 W. However, the allowable average power (limited by the RF current rating of 4 A) is only 88 W! These limits apply at the 1.8:1 SWR points.



Fig 19—A practical LC matching network that provides reactance compensation, impedance transformation and balun action.



Fig 20—Efficient broadband matching with a lumped element LC network. The antenna in this example has a resistance of 72 Ω and a Q of 12. The matching network has an impedance level of 12.4 Ω, and a Q of 200. The feed line is 50-Ω coax, and the matching network provides an impedance step-up ratio of 2.8:1.



Fig 21—The 80-meter DXer’s Delight permits operation with a 50-Ω transmitter load in the DX portions of the band, both CW and phone. This network was designed to provide a broadband match for an inverted V with F_0 = 3.67 MHz, an antenna resistance of 60 Ω and a Q of 13. The matching network has an impedance level of 9 Ω, and a Q of 220. The feed line is 50-Ω coax, and the matching network provides an impedance step-up ratio of 2.0:1.



Fig 22—A method of constructing the LC broadband matching network. Components must be chosen for high Q and must have adequate voltage and current ratings. The network is designed for use at the antenna feed point, and should be housed in a weather-resistant package. The component values are as follows:

C1—400 pF transmitting mica rated at 3000 V, 4 A (RF)

L1—4.7 µH, 8½ turns of B&W coil stock, type 3029 (6 turns per in., 2½-in. dia, #12 wire). The LC circuit is brought to midband resonance by adjusting an end tap on the inductor. The primary and secondary portions of the coil have 1¾ and 2½ turns, respectively.

PROPERTIES OF TRANSMISSION-LINE RESONATORS

One way around the power limitations of LC broadband matching networks is to use a transmission line as the resonator. Transmission line resonators, TLRs, typically have higher power-handling capability because the losses, though higher, are distributed over the length of the line instead of being concentrated in the lumped-LC components. Transmission-line resonators must be multiples of a quarter wavelength. For a parallel-tuned circuit, the odd-multiple λ/4 lines must be shorted at the far end and the even-multiple λ/4 lines must be open circuited.

The length of the matching network resonator is n electrical quarter wavelengths. The impedance level, Q, and line length are given by:

$$X_{N0} = \frac{4 Z_0}{n \pi}$$

or, solving for Z_0,

$$Z_0 = \frac{n \pi X_{N0}}{4} \qquad \text{(Eq 22)}$$

$$Q_N = \frac{2.774\, F_0}{A_0\ V} \qquad \text{(Eq 23)}$$

$$L_N = \frac{245.9\ n\ V}{F_0} \qquad \text{(Eq 24)}$$

where

Z_0 = line characteristic impedance in Ω

A_0 = matched line loss in dB per 100 feet

V = velocity factor, and

L_N = line length in feet.

These equations may be used to find the properties of the transmission line resonator in the systems shown in Figs 16 and 17. The line is RG-213 with the following properties:

Z_0 = 50 Ω

V = 0.66

A_0 = 0.4 dB/100 feet at 4 MHz

We need the matched loss at 3.742 MHz. Since the line loss is approximately proportional to $\sqrt{\text{frequency}}$,

$$A_{0F2} = A_{0F1} \sqrt{\frac{F_2}{F_1}} \qquad \text{(Eq 25)}$$

where A_{0F1} and A_{0F2} are the matched line losses at frequencies F_1 and F_2, respectively. Hence,

A_0 = 0.387 dB/100 feet at 3.742 MHz

Q_N = 40.65 (from Eq 23)

This is the Q of any resonator made from RG-213 for a frequency of 3.742 MHz. It does not matter how many quarter wavelengths (n) make up the cable segment. Earlier we calculated that the required impedance level, X_{N0}, is 15.9 Ω. Therefore, the required impedance level is:

$$Z_0 = \frac{n \pi \times 15.9}{4} = 12.5\, n\, \Omega \qquad \text{(from Eq 22)}$$

This means that you could use a quarter-wavelength segment with a short at the far end if Z_0 = 12.5 Ω, or a half-wavelength segment with a open at the far end if Z_0 = 25 Ω. Our example used an open-circuited full-wavelength resonator (n = 4) with a Z_0 of 50 Ω. This example was crafted to make this happen (so that it fits RG-213 properties), but it illustrates that some juggling is required to obtain the right resonator properties when it is made from a transmission line, since we are stuck with the cable's characteristic impedance.

The TLR Transformer

A way around the limitation created by available characteristic impedance values is to use the *transmission-line resonator transformer*. The basic idea is to make the connection to the TLR at an intermediate point along the line instead of at the end of the line. It is analogous to using taps on a parallel-tuned LC resonant circuit to achieve transformer action (See Fig 19). The nature of the transformer action is seen in **Fig 23**, where the ends of the transformer are designated 1-1 and 2-2. The impedance ratio of the transformer, N_Z, is approximated by



Fig 23—Transformer action in the TLR. The definition of transformer terminals depends on whether the TLR end is open- or short-circuited. θ is the distance between the minimum of the voltage standing wave (at resonance) and the connection point, expressed as an electrical angle. The distance x is that same distance expressed in feet.

$$N_Z = \sin^2 \theta \qquad \text{(Eq 26)}$$

The distance in feet, x, is given by

$$x = \frac{\theta}{90} \times \frac{\lambda}{4} = \frac{\theta}{90} \times \frac{245.9\ V}{F_0} \qquad \text{(Eq 27)}$$

This approach may be used for the connection of the TLR to the transmitter or to the antenna or both. An example will help make the power of the TLR transformer clear. We want to broadband match an 80-meter dipole (where F_0 is 3.742 MHz, R_A is 65 Ω and Q_A is 13). The feed line is RG-213 50-Ω cable, and the total distance between the antenna and transmitter is less than 100 feet.

Since we know that $Z_0 = 50\ \Omega$, we will design a prototype system with a 3/4 λ TLR (n=3). Since n is odd, the TLR must be shorted at one end, and we will place the short at the transmitter end of the line. The intermediate step of using a prototype system will enable us to design a system with the final TLR, but without transformer action. Then we'll calculate the proper connection points along the TLR. **Fig 24** shows the prototype system and the system with built-in transformers.

Note that the prototype antenna is connected to the open end of the TLR. The prototype generator (transmitter) is connected at a multiple of λ/2 from the antenna. Here, at resonance, an approximate replica of the antenna will appear. We will use primed variables to indicate prototype antenna system elements. The prototype antenna differs from the actual antenna in impedance level, so only R_A will change. F_0 and Q_A remain the same.

Starting with the 3/4 λ TLR, we have:

$X_{N0} = 21.2\ \Omega$ (from Eq 22)



Fig 24—An optimized antenna system with a 3/4 λ TLR made from RG-213 coaxial cable. The prototype system at A is a convenient intermediate step in the design process. At B is the configuration with TLR transformers. It has an open stub, L_O, a link, L_L (which serves as the feed line), and a shorted stub, L_S.

The prototype antenna resistance at resonance, R'_A, is calculated by rearranging Eq 13.

$$R'_G = \frac{X_{N0}\, Q_A}{\left(1 + \frac{Q_A}{2Q_N}\right) S_{M\,min}{}^2 - \frac{Q_A}{2\,Q_N}} \qquad \text{(Eq 28)}$$

Earlier we calculated that $Q_N = 40.65$ and $S_{Mmin} = 1.8$. Now we find

$R'_A = 76.3\ \Omega$ (from Eq 28)
$R'_G = 126.4\ \Omega$ (from Eq 14)

The electrical angles (in degrees) and connection locations (in feet) are given by

$$\theta_A = \sin^{-1} \sqrt{\frac{R_A}{R'_A}} \qquad \text{(Eq 29)}$$

$$\theta_G = \sin^{-1} \sqrt{\frac{R_G}{R'_G}} \qquad \text{(Eq 30)}$$

$$X_A = \frac{\theta_A}{90} L_1 \qquad \text{(Eq 31)}$$

$$X_G = \frac{\theta_G}{90} L_1 \qquad \text{(Eq 32)}$$

where

$$L_1 = \frac{\lambda}{4} = \frac{245.9\ V}{F_0}$$

The lengths of the stubs and link of Fig 24 are given by

$L_O = L_1 = x_A$ (Eq 33)

$L_S = x_G$ (Eq 34)

$L_L = 3L_1 - L_O - L_S$ (Eq 35)

Since L_1 = 43.4 feet,

$\theta_A = 67.4°$ (from Eq 29)

$\theta_G = 39.0°$ (from Eq 30)

L_O = 10.9 feet (from Eq 33)

L_S = 18.8 feet (from Eq 34)

L_L = 100.4 feet (from Eq 35)

These dimensions are summarized in Fig 24. If required, additional 50-Ω cable may be added between the transmitter and the junction of the shorted stub and the link. A remarkable aspect of the TLR transformer, as demonstrated in this example, is that it is a transformer with multiple taps distributed over a great distance, in this case over 100 feet.

The calculated SWR and loss of the antenna system with the TLR transformer are shown in **Fig 25A**. We mentioned earlier that the stub calculations are an approximation. Fig 25 bears this out, but the changes necessary to achieve the optimized results are relatively small. By changing the lengths and dipole resonant frequency slightly, the target optimized SWR characteristic of Fig 25B results. See **Table 1** for a summary of the changes required.

To demonstrate the significant improvement in match bandwidth that the TLR transformer provides, the SWR and loss of the same dipole fed with 100.4 feet of RG-213 cable is shown in Fig 25C. The loss added by the two stubs used to obtain match bandwidth enhancement is negligible (0.2 to 0.5 dB).

A TLR transformer may be used by itself to achieve a low-loss narrow-band impedance transformation, functioning like a λ/4 Q-section. It is different in nature from a Q-section, in that it is a true impedance transformer, while a Q section is an *impedance inverter*. The TLR transformer may be designed into the antenna system and is a useful tool when a narrow-band impedance transformation is needed.



Fig 25—The SWR and loss of the TLR transformer antenna system. At A, the results are shown with the calculated line lengths. At B, the improvement after the lengths were optimized is shown in Table 1. At C, for comparison, SWR and loss for the same setup as at A, but with the stubs removed.

Table 1
Calculated and Optimized Parameters Using TLR Transformers

	Calculated	*Optimized*
Dipole resonant frequency (F_0)	3.742 MHz	3.710 MHz
Open stub (L_O)	10.9 feet	13.1 feet
Shorted stub (L_S)	18.8 feet	20.1 feet
Link (L_L)	100.4 feet	101.0 feet



Fig 26—Dipole matching methods. At A, the T match; at B, the gamma match; at C, the coaxial resonator match.



Fig 27—Evolution of the coaxial-resonator-match broadband dipole. At A, a TLR transformer is used to match the feed line to the off-center-fed dipole. The match and dipole are made collinear at B. At C, the balanced transmission-line TLR transformer of A and B is replaced by a coaxial version. Because the shield of the coax can serve as a part of the dipole radiator, the wire adjacent to the coax match may be eliminated, D.



Fig 28—Dimensions for the 80-Meter MHz DX Special, an antenna optimized for the phone and CW DX portions of the 3.5-MHz band. The coax segment lengths total to one quarter-wavelength. The overall length is the same as that of a conventional inverted V dipole.

TRANSMISSION-LINE RESONATORS AS PART OF THE ANTENNA

The Coaxial-Resonator Match

This material is condensed from articles that appeared in April 1989 *QST* and *The ARRL Antenna Compendium, Vol 2*. The coaxial-resonator match, a concept based on the TLR transformer, performs the same function as the T match and the gamma match, that is, matching a transmission line to a resonant dipole. These familiar matching devices as well as the coaxial resonator match are shown in **Fig 26**. The coaxial resonator match has some similarity to the gamma match in that it allows connection of the shield of the coaxial feed line to the center of the dipole, and it feeds the dipole off center. The coaxial resonator match has a further advantage: It can be used to broadband the antenna system while providing an impedance match.

The coaxial resonator match is a resonant transformer made from a quarter-wave long piece of coaxial cable. **Fig 27** shows the evolution of the coaxial-resonator match. Now it becomes clear why coaxial cable is used for the quarter-wave TLR transformer—interaction between the dipole and the matching network is minimized. The effective dipole feed point is located at the crossover, which is an off-center feed point. In effect, the match is physically located "inside" the dipole. Currents flowing on the inside of the shield of the coax are associated with the resonator; currents flowing on the outside of the shield of the coax are the usual dipole currents. Skin effect provides a degree of isolation and allows the coax to perform its dual function. The wire extensions at each end make up the remainder of the dipole, making the overall length equal to one half-wavelength.

A useful feature of an antenna using the coaxial-resonator match is that the entire antenna is at the same dc potential as the feed-line potential, thereby avoiding charge buildup on the antenna. Hence, noise and the potential of lightning damage are reduced.

Fig 28 shows the detailed dimensions of an 80-meter inverted-V dipole using a coaxial-resonator match. This design provides a load SWR better than 1.6:1 from 3.5 to 3.825 MHz and has been named the *80-Meter DX Special*. The coax is an electrical quarter wavelength, has a short at one end, an open at the other end, a strategically placed crossover, and is fed at a tee junction. (The crossover is made by connecting the shield of one coax segment to the center conductor of the adjacent segment and by connecting the remaining center conductor and shield in a similar way.) The antenna is constructed as an inverted-V dipole with a 110° included angle and an apex at 60 feet. The measured SWR versus frequency is shown in **Fig 29**. Also in Fig 29



Fig 29—Measured SWR performance of the 80-Meter DX Special, curve A. Note the substantial broadbanding relative to a conventional uncompensated dipole, curve B.



Fig 30—T and crossover construction. At A, a 2-inch PVC pipe coupling can be used for the T, and at B, a 1-inch coupling for the crossover. These sizes are the nominal inside diameters of the PVC pipe that is normally used with the couplings. The T could be made from standard UHF hardware (an M-358 T and a PL-258 coupler). An alternative construction for the crossover is shown at C, where a direct solder connection is made.

is the SWR characteristic for an uncompensated inverted-V dipole made from the same materials and positioned exactly like the broadband version.

The 80-Meter DX Special is made from RG-213 coaxial cable and #14 AWG wire, and is fed with 50-Ω coax. The coax forming the antenna should be cut so that the stub lengths of Fig 28 are within $^1/_2$ inch of the specified values. PVC plastic-pipe couplings and SO-239 UHF chassis connectors can be used to make the T and crossover connections, as shown in **Fig 30A** and 30B. Alternatively, a standard UHF T connector and coupler can be used for the T, and the crossover may be a soldered connection (Fig 30C). RG-213 is used because of its ready availability, physical strength, power handling capability, and moderate loss.

Cut the wire ends of the dipole about three feet longer than the lengths given in Fig 28. If there is a tilt in the SWR-frequency curve when the antenna is first built, it may be flattened to look like the shape given in Fig 29 by increasing or decreasing the wire length. Each end should be lengthened or shortened by the same amount.

A word of caution: If the coaxial cable chosen is not RG-213 or equivalent, the dimensions will have to be modified. The following cable types have about the same characteristic impedance, loss and velocity factor as RG-213 and could be substituted: RG-8, RG-8A, RG-10, RG-10A and RG-215. If the Q of the dipole is particularly high or the radiation resistance is unusually low because of different ground characteristics, antenna height, surrounding objects and so on, then different segment lengths will be required.

What is the performance of this broadband antenna relative to that of a conventional inverted-V dipole? Aside from the slight loss (about 0.75 dB at band edges, less elsewhere) because of the non-ideal matching network, the broadband version will behave essentially the same as a dipole cut for the frequency of interest. That is, the radiation patterns for the two cases will be virtually the same.

The Snyder Dipole

A commercially manufactured antenna utilizing the principles described in the Matching Network Design section is the Snyder dipole. Patented by Richard D. Snyder in late 1984 (see Bibliography), it immediately received much public attention through an article that Snyder published. Snyder's claimed performance for the antenna is a 2:1 SWR bandwidth of 20% with high efficiency.

The configuration of the Snyder antenna is like that of the crossed-double bazooka of Fig 12, with 25-Ω line used for the cross-connected resonators. In addition, the antenna is fed through a 2:1 balun, and exhibits a W-shaped SWR characteristic like that of Fig 13. The SWR at band center, based on information in the patent document, is 1.7 to 1. There is some controversy in professional circles regarding the claims for the Snyder antenna.

The Improved Crossed-Double Bazooka

The following has been condensed from an article by Reed Fisher, W2CQH, that appeared in *The ARRL Antenna Compendium Volume 2*. The antenna is shown in **Fig 31**. Note that the half-wave flat-top is constructed of sections of RG-58 coaxial cable. These sections of coaxial cable serve as quarter-wave shunt stubs that are essentially connected *in parallel* at the feed point in the crossed double-bazooka fashion. At an electrical quarter


122'
43'
43'
X
Y
Short Circuit
RG – 58
1 : 1 Balun
λ/4 (2:1) Transformer
Approx. 50' of RG – 59
50 – Ohm Feed Point
50 – Ohm Coax to Transceiver, Any Length

Fig 31—Details of the W2CQH broadband-matched 80-meter dipole.



Fig 32—SWR curves for the improved double bazooka. Curve A, the theoretical curve with 50-Ω stubs and a λ/4, 75-Ω matching transformer. Curve B, measured response of the same antenna, built with RG-58 stubs and an RG- 59 transformer. Curve C, measurements from a dipole without broadbanding. Measurements were made at W2CQH with the dipole horizontal at 30 feet.


Center–Fed Half–Wave Dipole
Balun
1 λ, 50 Ω RG–213
Transmission–Line Resonator
A
B
Transmitter
SWR Meter
1/4 λ, 75 Ω RG–11

Fig 33—This simple broadband antenna system resembles a conventional 80-meter dipole except for the λ/4-wavelength 75-Ω segment. The lengths of the Q-section, TLR (including balun) and dipole are 43.3 feet, 170.5 feet, and 122.7 feet, respectively.

wavelength (43 feet) from each side of the feed point X-Y, the center conductor is shorted to the braid of the coaxial cable.

The parallel stubs provide reactance compensation. The necessary impedance transformation at the antenna feed point is provided by the quarter-wave Q-section constructed of a 50-foot section of 75-Ω coaxial cable (RG-59). A W2DU 1:1 current balun is used at the feed point. See **Fig 32** for the SWR versus frequency for this antenna with and without the broadband matching network.

This antenna is essentially that of the crossed double bazooka antenna shown in Fig 12, with the addition of the 75-Ω Q-section. The improvement in match bandwidth is substantial. The antenna at W2CQH is straight and nearly horizontal with an average height of about 30 feet.

TRANSMISSION-LINE RESONATORS AS PART OF THE FEED LINE

A Simple Broadband Dipole for 80 Meters

This system was described in an article in September 1993 *QST*. It has the advantage that the radiator is the same as that of a conventional half-wave wire dipole. Thus the antenna is light weight, easy to support and has small wind and ice loading. The broadband matching network is integrated into the feed line.

The system is shown in **Fig 33**. It is a variation of the example shown in the Matching Network Design section of this chapter as shown in Fig 17. The TLR is a 1λ length of RG-213 50-Ω coax and the impedance transformation is accomplished with a 75-Ω Q-section



Fig 34—Measured SWR versus frequency for the broadband and conventional antenna systems.



Fig 35—Measured SWR for the 80- and 40-meter multiband antenna system.

made of RG-11. The antenna is an inverted-V with a 140° included angle and an apex height of 60 feet. The wire size is #14, but is not critical. The balun is a W2DU 1:1 current type. It easily handles the legal power limit over the entire 80-meter band. The measured SWR is shown in **Fig 34**.

A unique advantage of this antenna is that by paralleling a 40-meter dipole at the feed point and sharing the feed line, operation on both 80 and 40 meters is possible. The reason for this is that the lengths of the Q-section and the TLR are multiples of a half-wavelength on 40 meters. To minimize the interaction, the two dipoles should be spaced from each other away from the feed point. First tune the 80-meter antenna and then the 40-meter one. **Fig 35** shows the result of adding a 40-meter dipole to the system shown in Fig 33. Each 40-meter dipole leg is 34.4 feet long. Note that the SWR on 80 meters changes very little compared to Fig 34. No change was made to the 80-meter dipole or to the transmission line.

80-Meter Dipole with the TLR Transformer

The total length of the feed line in the system just described above in Fig 33 is quite long, about 214 feet. For installations with shorter runs, the TLR transformer concept may be employed to advantage. An example provided in "Optimizing the 80-Meter Dipole" in *The ARRL Antenna Compendium, Vol 4* is shown in **Fig 36**. Here the TLR is $^3/_4$ λ long overall and is made from RG-213 50-Ω cable. The design applies for an 80-meter horizontal dipole, 80 feet above average ground, with an assumed antenna F_0, R_A, and Q_A of 3.72 MHz, 92 Ω and 9, respectively. (See Figs 3 and 4). The lengths must be revised for other dipole parameters.



Fig 36—Broadbanding with the TLR transformer. The dimensions shown apply for an 80-meter horizontal dipole 80 feet above average ground.

For this design, the feed line is 113.1 feet long and the shorted stub at the transmitter end is 21.6 feet long. You can add any length of 50-Ω cable between the transmitter and the junction of the shorted stub and the feed line. The shorted stub gives a dc path to ground for both sides of the dipole, preventing charge buildup and some lightning protection. For multiband operation with an antenna tuner, the stub should be removed.

The general application of the TLR transformer concept has a tap at both the transmitter end and a tap at the antenna end. (See Fig 24.) In this case, the concept was applied only at the transmitter end, since very little impedance transformation was required at the antenna end. The location of the TLR transformer is not obvious. Consider a $^3/_4$ λ TLR with a short at one end, and an open at the other end where the antenna is connected. The generator for no impedance transformation would be located λ/4 (43.6 feet @ 3.72 MHz) from the short. By connecting the transmitter 21.6 feet from the short, the required impedance transformation for a transmitter optimized for 50-Ω loads is achieved.

BIBLIOGRAPHY

Source material and more extended discussion of the topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2.

A. Bloom, "Once More with the 80-Meter Dipole," Technical Correspondence, *QST*, Jun 1985, p 42.

R. E. Fisher, "A Simple, Broadband 80-Meter Dipole Antenna," *The ARRL Antenna Compendium, Vol 2* (Newington, CT: ARRL, 1989), pp 119-123.

R. M. Fano, “Theoretical Limitations on the Broadband Matching of Arbitrary Impedances,” *Journal of the Franklin Inst*, Jan 1950, pp 57-83, and Feb 1950, pp 139-155.

J. Hall, “The Search for a Simple, Broadband 80-Meter Dipole,” *QST*, Apr 1983, pp 22-27.

J. Hall, “Maxcom Antenna Matcher and Dipole Cable Kit,” Product Review, *QST*, Nov 1984, pp 53-54.

R. C. Hansen, “Evaluation of the Snyder Dipole,” *IEEE Trans on Antennas and Prop*, Vol AP-35, No. 2, Feb 1987, pp 207-210.

A. Harbach, “Broadband 80-Meter Antenna,” *QST*, Dec 1980, pp 36-37 (presentation of a cage antenna).

S. Leslie, “Broadbanding the Elevated, Inverse-Fed Ground Plane Antenna,” *The ARRL Antenna Compendium, Vol 6* (Newington, CT: 1999), pp 209-211.

R. D. Snyder, “The Snyder Antenna,” *RF Design*, Sep/Oct 1984, pp 49-51.

R. D. Snyder, “Broadband Antennae Employing Coaxial Transmission Line Sections,” United States Patent no. 4,479,130, issued Oct 23, 1984.

C. Whysall, “The ‘Double Bazooka’ Antenna,” *QST*, Jul 1968, pp 38-39.

F. Witt, “A Simple Broadband Dipole for 80 Meters,” *QST*, Sept 1993, pp 27-30, 76.

F. J. Witt, “Broadband Dipoles—Some New Insights,” *QST*, Oct 1986, pp 27-37.

F. Witt, “Broadband Matching with the Transmission Line Resonator,” *The ARRL Antenna Compendium, Vol 4*, (Newington, CT: 1995), pp 30-37.

F. Witt, “How to Design Off-Center-Fed Multiband Wire Antennas Using that Invisible Transformer in the Sky,” *The ARRL Antenna Compendium, Vol 3,* (Newington, CT: ARRL, 1992), p 74.

F. Witt, “Match Bandwidth of Resonant Antenna Systems,” *QST*, Oct 1991, pp 21-25

F. Witt, “Optimizing the 80-Meter Dipole,” *The ARRL Antenna Compendium, Vol 4* (Newington, CT: 1995), pp 38-48.

F. Witt, “Optimum Lossy Broadband Matching Networks for Resonant Antennas,” *RF Design*, Apr 1990, pp 44-51 and Jul 1990, p 10.

F. Witt, “The Coaxial Resonator Match and the Broadband Dipole,” *QST*, Apr 1989, pp 22-27.

F. Witt, “The Coaxial Resonator Match, *The ARRL Antenna Compendium, Vol 2* (Newington, CT: ARRL, 1989), pp 110-118.

Chapter 10

Log Periodic Arrays

This chapter was contributed by L. B. Cebik, W4RNL. The *Log Periodic Dipole Array* (*LPDA*) is one of a family of frequency-independent antennas. Alone, an LPDA forms a directional antenna with relatively constant characteristics across a wide frequency range. It may also be used with parasitic elements to achieve specific characteristic within a narrow frequency range. Common names for such hybrid arrays are the *log-cell Yagi* or the *Log-Yag*. We shall look at the essential characteristics of both types of arrays in this chapter.

The LPDA is the most popular form of log-periodic systems, which also include zig-zag, planar, trapezoidal, slot, and V forms. The appeal of the LPDA version of the log periodic antenna owes much to its structural similarity to the Yagi-Uda parasitic array. This permits the construction of directional LPDAs that can be rotated—at least within the upper HF and higher frequency ranges. Nevertheless, the LPDA has special structural as well as design considerations that distinguish it from the Yagi. A number of different construction techniques for both wire and tubular elements are illustrated later in this chapter.



Fig 1—The basic components of a log periodic dipole array (LPDA). The forward direction is to the left in this sketch. Many variations of the basic design are possible.

The LPDA in its present form derives from the pioneering work of D. E. Isbell at the University of Illinois in the late 1950s. Although you may design LPDAs for large frequency ranges—for example, from 3 to 30 MHz or a little over 3 octaves—the most common LPDA designs that radio amateurs use are limited to a one-octave range, usually from 14 to 30 MHz. Amateur designs for this range tend to consist of linear elements. However, experimental designs for lower frequencies have used elements shaped like inverted Vs, and some versions use vertically oriented $^1/_4$ λ elements over a ground system.

Fig 1 shows the parts of a typical LPDA. The structure consists of a number of linear elements, the longest of which is approximately $^1/_2$ λ long at the lowest design frequency. The shortest element is usually about $^1/_2$ λ long at a frequency well above the highest operating frequency. The antenna feeder, also informally called the *phase-line*, connects the center points of each element in the series, with a phase reversal or *cross-over* between each element. A stub consisting of a shorted length of parallel feed line is often added at the back of an LPDA.

The arrangement of elements and the method of feed yield an array with relatively constant gain and front-to-back ratio across the designed operating range. In addition, the LPDA exhibits a relatively constant feed-point impedance, simplifying matching to a transmission line.

BASIC DESIGN CONSIDERATIONS

For the amateur designer, the most fundamental facets of the LPDA revolve around three interrelated design variables: α (alpha), τ (tau), and σ (sigma). Any one of the three variables may be defined by reference to the other two.

Fig 2 shows the basic components of an LPDA. The angle α defines the outline of an LPDA and permits every dimension to be treated as a radius or the consequence of a radius (R) of a circle. The most basic structural dimensions are the element lengths (L), the distance (R) of each element from the apex of angle α, and the distance between elements (D). A single design constant, τ, defines all of these relationships in the following manner:



Fig 2—Some fundamental relationships that define an array as an LPDA. See the text for the defining equations.

$$\tau = \frac{R_{n+1}}{R_n} = \frac{D_{n+1}}{D_n} = \frac{L_{n+1}}{L_n} \tag{Eq 1}$$

where element n and n+1 are successive elements in the array working toward the apex of angle α. The value of τ is always less than 1.0, although effective LPDA design requires values as close to 1.0 as may be feasible.

The variable τ defines the relationship between successive element spacings but it does not itself determine the initial spacing between the longest and next longest elements upon which to apply τ successively. The initial spacing also defines the angle α for the array. Hence, we have two ways to determine the value of σ, the relative spacing constant:

$$\sigma = \frac{1 - \tau}{4 \tan \alpha} = \frac{D_n}{2L_n} \tag{Eq 2}$$

where D_n is the distance between any two elements of the array and L_n is the length of the longer of the two elements. From the first of the two methods of determining the value of σ, we may also find a means of determining α when we know both τ and σ.

For any value of τ, we may determine the optimal value of σ:

$$\sigma_{opt} = 0.243\,\tau - 0.051 \tag{Eq 3}$$

The combination of a value for τ and its corresponding optimal value of σ yields the highest performance of which an LPDA is capable. For values of τ from 0.80 through 0.98, the value of optimal σ varies from 0.143 to 0.187, in increments of 0.00243 for each 0.01 change in τ. However, using the optimal value of σ usually yields a total array length that is beyond ham construction or tower/mast support capabilities. Consequently, amateur LPDAs usually employ compromise values of τ and σ that yield lesser but acceptable performance.

For a given frequency range, increasing the value of τ increases both the gain and the number of required elements. Increasing the value of σ increases both the gain and the overall boom length. A τ of 0.96—which approaches the upper maximum recommended value for τ—yields an optimal σ of about 0.18, and the resulting array grows to over 100 feet long for the 14 to 30 MHz range. The maximum free space gain is about 11 dBi, with a front-to-back ratio that approaches 40 dB. Normal amateur practice, however, uses values of τ from about 0.88 to 0.95 and values of σ from about 0.03 to 0.06.

Standard design procedures usually set the length of the rear element for a frequency about 7% lower than the lowest design frequency and use the common dipole formula ($L_{feet} = 468/f_{MHz}$) to determine its length (5% lower than a free-space half wavelength, where $L_{feet} = 493.56/f_{MHz}$). The upper frequency limit of the design is ordinarily set at about 1.3 times the highest design frequency. Since τ and σ set the increment between successive element lengths, the number of elements becomes a function of when the shortest element reaches the dipole length for the adjusted upper frequency.

The adjusted upper frequency limit results from the behavior of LPDAs with respect to the number of active elements. See **Fig 3**, which shows an edge view of a 10-element LPDA for 20 through 10 meters. The vertical lines represent the peak relative current magnitude for each element at the specified frequency. At 14 MHz, virtually every element of the array shows a significant cur-



Fig 3—The relative current magnitude on the elements of an LPDA at the lowest and highest operating frequencies for a given design. Compare the number of "active" elements, that is, those with current levels at least 1/10 of the highest level.

rent magnitude. However, at 28 MHz, only the forward 5 elements carry significant current. Without the extended design range to nearly 40 MHz, the number of elements with significant current levels would be severely reduced, along with upper frequency performance.

The need to extend the design equations below the lowest proposed operating frequency varies with the value of τ. In **Fig 4**, we can compare the current on the rear elements of two LPDAs, both with a σ value of 0.04. The upper design uses a τ of 0.89, while the lower design uses a value of 0.93. The most significant current-bearing element moves forward with increases in τ, reducing (but not wholly eliminating) the need for elements whose lengths are longer than a dipole for the lowest operating frequency.



Fig 4—Patterns of current magnitude at the lowest operating frequency of two different LPDA designs: a 10-element low-τ design and a 16-element higher-τ design.

LPDA Design and Computers

Originally, LPDA design proceeded through a series of design equations intended to yield the complete specifications for an array. More recent techniques available to radio amateurs include basic LPDA design software and antenna modeling software. One good example of LPDA design software is *LPCAD28* by Roger Cox, WB0DGF. A copy of this freeware program is on the CD-ROM that accompanies this volume. The user begins by specifying the lowest and highest frequencies in the design. He then enters either his selected values for τ and σ or his choices for the number of elements and the total length of the array. With this and other input data, the program provides a table of element lengths and spacings, using the adjusted upper and lower frequency limits described earlier.

The program also requests the diameters of the longest and shortest elements in the array, as well as the diameter of average element. From this data, the program calculates a recommended value for the phase-line connecting the elements and the approximate resistive value of the input impedance. Among the additional data that *LPCAD28* makes available is the spacing of conductors to achieve the desired characteristic impedance of the phase-line. These conductors may be round—as we would use for a wire phase-line—or square—as we might use for double-boom construction.

An additional vital output from *LPCAD28* is the conversion of the design into antenna modeling input files of several formats, including versions for *AO* and *NEC4WIN* (both *MININEC*-based programs), and a version in the standard *.NEC format usable by many implementations of *NEC-2* and *NEC-4*, including *NECWin Plus*, *GNEC*, and *EZNEC Pro*. Every proposed LPDA design should be verified and optimized by means of antenna modeling, since basic design calculations rarely provide arrays that require no further work before construction. A one-octave LPDA represents a segment of an arc defined by α that is cut off at both the upper and the lower frequency limits. Moreover, some of the design equations are based upon approximations and do not completely predict LPDA behavior. Despite these limitations, most of the sample LPDA designs shown later in this chapter are based directly upon the fundamental calculations. Therefore, the procedure will be outlined in detail before turning to hybrid log-cell Yagi concepts.

Modeling LPDA designs is most easily done on a version of *NEC*. The transmission line (TL) facility built into *NEC-2* and *NEC-4* alleviates the problem of modeling the phase-line as a set of physical wires, each section of which has a set of constraints in *MININEC* at the right-angle junctions with the elements. Although the *NEC* TL facility does not account for losses in the lines, the losses are ordinarily low enough to neglect.

NEC models do require some careful construction to obtain the most accurate results. Foremost among the cautions is the need for careful segmentation, since each element has a different length. The shortest element should have about 9 or 11 segments, so that it has sufficient segments at the highest modeling frequency for the design. Each element behind the shortest one should have a greater number of segments than the preceding element by the inverse of the value of τ. However, there is a further limitation. Since the transmission line is at the center of each element, *NEC* elements should have an odd number of segments to hold the phase-line centered. Hence, each segmentation value calculated from the inverse of τ must be rounded up to the nearest odd integer.

Initial modeling of LPDAs in *NEC-2* should be done with uniform-diameter elements, with any provision for stepped-diameter element correction turned off. Since these correction factors apply only to elements within about 15% of dipole resonance at the test frequency, models with stepped-diameter elements will correct for only a few elements at any test frequency. The resulting combination of corrected and uncorrected elements will not yield a model with assured reliability.

Once one has achieved a satisfactory model with uniform-diameter elements, the modeling program can be used to calculate stepped-diameter substitutes. Each uniform-diameter element, when extracted from the larger array, will have a resonant frequency. Once this frequency is determined, the stepped-diameter element to be used in final construction can be resonated to the same frequency. Although *NEC-4* handles stepped diameter elements with much greater accuracy than *NEC-2*, the process just described is also applicable to *NEC-4* models for the greatest precision.

LPDA Behavior

Although LPDA behavior is remarkably uniform over a wide frequency range compared to narrow-band designs, such as the Yagi-Uda array, it nevertheless exhibits very significant variations within the design range. **Fig 5** shows several facets of these behaviors. Fig 5 shows the free-space gain for three LPDA designs using 0.5-inch diameter aluminum elements. The designations for each model list the values of τ (0.93, 0.89, and 0.85) and of σ (0.02, 0.04, and 0.06) used to design each array. The resultant array lengths are listed with each designator. The total number of elements varies from 16 for "9302" to 10 for "8904" to 7 for "8504."



Fig 5—The modeled free-space gain of 3 relatively small LPDAs of different design. Note the relationship of the values of τ and of σ for these arrays with quite similar performance across the 14-30 MHz span.

First, the gain is never uniform across the entire frequency span. The gain tapers off at both the low and high ends of the design spectrum. Moreover, the amount of gain undulates across the spectrum, with the number of peaks dependent upon the selected value of τ and the resultant number of elements. The front-to-back ratio tends to follow the gain level. In general, it ranges from less than 10 dB when the free-space gain is below 5 dBi to over 20 dB as the gain approaches 7 dBi. The front-to-back ratio may reach the high 30s when the free-space array gain exceeds 8.5 dBi. Well-designed arrays, especially those with high values of τ and σ, tended to have well-controlled rear patterns that result in only small differences between the 180° front-to-back ratio and the averaged front-to-rear ratio.

Since array gain is a mutual function of both τ and σ, average gain becomes a function of array length for any given frequency range. Although the gain curves in Fig 5 interweave, there is little to choose among them in terms of average gain for the 14 to 18-foot range of array lengths. Well-designed 20- to 10-meter arrays in the 30-foot array length region are capable of about 7 dBi free-space gain, while 40-foot arrays for the same frequency range can achieve about 8 dBi free-space gain.

Exceeding an average gain of 8.5 dBi requires at least a 50-foot array length for this frequency range. Long arrays with high values of τ and σ also tend to show smaller excursions of gain and of front-to-back ratio in the overall curves. In addition, high-τ designs tend to show higher gain at the low frequency end of the design spectrum.

The frequency sweeps shown in Fig 5 are widely spaced at 1 MHz intervals. The evaluation of a specific design for the 14 to 30-MHz range should decrease the interval between check points to no greater than 0.25 MHz in order to detect frequencies at which the array may show a *performance weakness*. Weaknesses are frequency regions in the overall design spectrum at which the array shows unexpectedly lower values of gain and front-to-back ratio. In Fig 5 note the unexpected decrease in gain of model "8904" at 26 MHz. The other designs also have weak points, but they fall between the frequencies sampled.

In large arrays, these regions may be quite small and may occur in more than one frequency region. The weakness results from the harmonic operation of longer elements to the rear of those expected to have high current levels. Consider a 7-element LPDA about 12.25-foot long for 14 to 30 MHz using 0.5-inch aluminum elements. At 28 MHz, the rear elements operate in a harmonic mode, as shown by the high relative current magnitude curves in **Fig 6**. The result is a radical decrease in gain, as shown in the "No Stub" curve of **Fig 7**. The front-to-back ratio also drops as a result of strong radiation from the long



Fig 6—The relative current magnitude on the elements of model "8504" at 28 MHz without and with a stub. Note the harmonic operation of the rear elements before a stub is added to suppress such operation.



Fig 7—A graph of the gain of model "8504" showing the frequency region in which a "weakness" occurs and its absence once a suitable stub is added to the array.

elements to the rear of the array.

Early designs of LPDAs called for terminating transmission-line stubs as standard practice to help eliminate such weak spots in frequency coverage. In contemporary designs, their use tends to be more specific for eliminating or moving frequencies that show gain and front-to-back weakness. (Stubs have the added function of keeping both sides of each element at the same level of static charge or discharge.) The model dubbed "8504" was fitted (by trial and error) with an 18-inch shorted stub of 600-Ω transmission line. As Fig 6B shows, the harmonic operation of the rear elements is attenuated. The "stub" curve of Fig 7 shows the smoothing of the gain curve for the array throughout the upper half of its design spectrum. In some arrays showing multiple weaknesses, a single stub may not eliminate all of them. However, it may move the weaknesses to unused frequency regions. Where full-spectrum operation of an LPDA is necessary, additional stubs located at specific elements may be needed.

Most LPDA designs benefit (with respect to gain and front-to-back ratio) from the use of larger-diameter elements. Elements with an average diameter of at least 0.5-inch are desirable in the 14 to 30 MHz range. However, standard designs usually presume a constant element length-to-diameter ratio. In the case of *LPCAD28*, this ratio is about 125:1, which assumes an even larger diameter. To achieve a relatively constant length-to-diameter ratio in the computer models, you can set the diameter of the shortest element in a given array design and then increase the element diameter by the inverse of τ for each succeeding longer element. This procedure is often likely to result in unreasonably large element diameters for the longest elements, relative to standard amateur construction practices.

Since most amateur designs using aluminum tubing for elements employ stepped-diameter (tapered) elements, roughly uniform element diameters will result unless the LPDA mechanical design tries to lighten the elements at the forward end of the array. This practice may not be advisable, however. Larger elements at the high end of the design spectrum often counteract (at least partially) the natural decrease in high-frequency gain and show improved performance compared to smaller diameter elements.

An alternative construction method for LPDAs uses wire throughout. At every frequency, single-wire elements reduce gain relative to larger-diameter tubular elements. An alternative to tubular elements appears in **Fig 8**. For each element of a tubular design, there is a roughly equivalent 2-wire element that may be substituted. The


Tubular Element
1/2 L Resonant at f (MHz)
1/2 L
Vary until resonant at f (MHz)
2–Wire Element

Fig 8—A substitute for a large-diameter tubular element composed of two wires shorted at both the outer ends and at the center junction with the phase-line.

spacing between the wire is determined by taking one of the modeled tubular elements and finding its resonant frequency. A two-wire element of the same length is then constructed with shorts at the far ends and at the junctions with the phase-line. The separation of the two wires is adjusted until the wire element is resonant at the same frequency as the original tubular element. The required separation will vary with the wire chosen for the element. Models used to develop these substitutes must pay close attention to segmentation rules for *NEC* due to the short length of segments in the end and center shorts, and to the need to keep segment junctions as exactly parallel as possible with close-spaced wires.

Feeding and Constructing the LPDA

Original design procedures for LPDAs used a single, ordinarily fairly high, characteristic impedance for the phase-line (antenna feeder). Over time, designers realized that other values of impedance for the phase line offered both mechanical and performance advantages for LPDA performance. Consequently, for the contemporary designer, phase-line choice and construction techniques are almost inseparable considerations.

High-impedance phase lines (roughly 200 Ω and higher) are amenable to wire construction similar to that used with ordinary parallel-wire transmission lines. They require careful placement relative to a metal boom used to support individual elements (which themselves must be insulated from the support boom). Connections also require care. If the phase-line is given a half-twist between each element, the construction of the line must ensure constant spacing and relative isolation from metal supports to maintain a constant impedance and to prevent shorts.

Along with the standard parallel-wire line, shown in **Fig 9A**, there are a number of possible LPDA structures using booms. The booms serve both to support the elements and to create relatively low-impedance (under 200 Ω) phase-lines. Fig 9B shows the basics of a twin circular tubing boom with the elements cross-supported by insulated rods. Fig 9C shows the use of square tubing with the elements attached directly to each tube by through-bolts. Fig 9D illustrates the use of L-stock, which may be practical at VHF frequencies. Each of these sketches is incomplete, however, since it omits the necessary stress analyses that determine the mechanical feasibility of a structure for a given LPDA project.

The use of square boom material requires some adjustment when calculating the characteristic impedance of the phase-line. For conductors with a circular cross-section,


Wire Phase–Line Plate and Connections
U–Clamp
Tubular Element
Insulated Plate
Tubular Boom
(A)
Tubular Element
T= Tubular Boom
Insulated Separator
U–Clamps
(B)
T
T
Fiberglass Rod
Not to scale
Not all hardware shown
Square–Tube Phase–Line
Insulated Separator
Tubular Element with Threaded Insert
Long Bolt
(C)
Threaded–Rod Element
Insulated Separator
L–Stock Phase–Line
Nuts
(D)

Fig 9—Four (of many) possible construction techniques, shown from the array end. In A, an insulated plate supports and separates the wires of the phase-line, suitable with wire or tubular elements. A dual circular boom phase-line also supports the elements, which are cross-supported for boom stability. Square tubing is used in C, with the elements joined to the boom/phase-line with through-bolts and an insert in each half element. The L-stock shown in D is useful for lighter VHF and UHF arrays.

$$Z_0 = 120 \cosh^{-1} \frac{D}{d} \qquad \text{(Eq 4)}$$

where D is the center-to-center spacing of the conductors and d is the outside diameter of each conductor, both expressed in the same units of measurement. Since we are dealing with closely spaced conductors, relative to their diameters, the use of this version of the equation for calculating the characteristic impedance (Z_0) is recommended. For a square conductor,

$$d \approx 1.18\ w \qquad \text{(Eq 5)}$$

where d is the approximate equivalent diameter of the square tubing and w is the width of the tubing across one side. Thus, for a given spacing, a square tube permits you to achieve a lower characteristic impedance than round conductors. However, square tubing requires special attention to matters of strength, relative to comparable round tubing.

Electrically, the characteristic impedance of the LPDA phase-line tends to influence other performance parameters of the array. Decreasing the phase-line Z_0 also decreases the feed-point impedance of the array. For small designs with few elements, the decrease is not fully matched by a decrease in the excursions of reactance. Consequently, using a low impedance phase-line may make it more difficult to achieve a 2:1 or less SWR for the entire frequency range. However, higher-impedance phase-lines may result in a feed-point impedance that requires the use of an impedance-matching balun.

Decreasing the phase-line Z_0 also tends to increase LPDA gain and front-to-back ratio. There is a price to be paid for this performance improvement—weaknesses at specific frequency regions become much more pronounced with reductions in the phase-line Z_0. For a specific array you must weigh carefully the gains and losses, while employing one or more transmission line stubs to get around performance weaknesses at specific frequencies.

Depending upon the specific values of τ and σ selected for a design, you can sometimes select a phase-line Z_0 that provides either a 50-Ω or a 75-Ω feed-point impedance, holding the SWR under 2:1 for the entire design range of the LPDA. The higher the values of τ and σ for the design, the lower the reactance and resistance excursions around a central value. Designs using optimal values of σ with high values of τ show a very slight capacitive reactance throughout the frequency range. Lower design values obscure this phenomenon due to the wide range of values taken by both resistance and reactance as the frequency is changed.

At the upper end of the frequency range, the source resistance value decreases more rapidly than elsewhere in the design spectrum. In larger arrays, this can be overcome by using a variable Z_0 phase-line for approximately the first 20% of the array length. This technique is, however, difficult to implement with anything other than wire phase-lines. Begin with a line impedance about half of the final value and increase the wire spacing evenly until it reaches its final and fixed spacing. This technique can sometimes produce smoother impedance performance across the entire frequency span and improved high-frequency SWR performance.

Designing an LPDA requires as much attention to designing the phase-line as to element design. It is always useful to run models of the proposed design through several iterations of possible phase-line Z_0 values before freezing the structure for construction.

Special Design Corrections

The curve for the sample 8504 LPDA in Fig 7 revealed several deficiencies in standard LPDA designs. The weakness in the overall curve was corrected by the use of a stub to eliminate or move the frequency at which rearward elements operated in a harmonic mode. In the course of describing the characteristics of the array, we have noted several other means to improve performance. Fattening elements (either uniformly or by increasing their diameter in step with τ) and reducing the characteristic impedance of the phase-line are capable of small improvements in performance. However, they cannot wholly correct the tendency of the array gain and front-to-back ratio to fall off at the upper and lower limits of the LPDA frequency range.

One technique sometimes used to improve performances near the frequency limits is to design the LPDA for upper and lower frequency limits much higher and lower than the frequencies of use. This technique unnecessarily increases the overall size of the array and does not eliminate the downward performance curves. Increasing the values of τ and σ will usually improve perfor-



Fig 10—A before and after sketch of an LPDA, showing the original lengths of the elements and their adjustments from diminishing the value of τ at both ends of the array. See the text for the amount of change applicable to each element.

mance at no greater cost in size than extending the frequency range. Increasing the value of τ is especially effective in improving the low frequency performance of an LPDA.

Working within the overall size limits of a standard design, one may employ a technique of *circularizing* the value of τ for the rear-most and forward-most elements. See **Fig 10**, which is not to-scale relative to overall array length and width. Locate (using an antenna-modeling program) the element with the highest current at the lowest operating frequency, and the element with the highest current at the highest operating frequency. The adjustments to element lengths may begin with these elements or—at most—one element further toward the array center. For the first element (counting from the center) to be modified, reduce the value of τ by about 0.5%. For a rearward element, use the inverse of the adjusted value of τ to calculate the new length of the element relative to the unchanged element just forward of the change. For a forward element, use the new value of τ to calculate the new length of the element relative to the unchanged element immediately to the rear of it.

For succeeding elements outward, calculate new values of τ from the adjusted values, increasing the increment of decrease with each step. Second adjusted elements may use values of τ about 0.75% to 1.0% lower than the values just calculated. Third adjusted elements may use an increment of 1.0% to 1.5% relative to the preceding value.

Not all designs require extensive treatment. As the values of τ and σ increase, fewer elements may require adjustment to obtain the highest possible gain at the frequency limits, and these will always be the most outward elements in the array. A second caution is to check the feed-point impedance of the array after each change to ensure that it remains within design limits.

Fig 11 shows the free-space gain curves from 14 to 30 MHz for a 10-element LPDA with an initial τ of 0.89 and a σ of 0.04. The design uses a 200-Ω phase-line, 0.5-inch aluminum elements, and a 3-inch 600-Ω stub. The lowest curve shows the modeled performance across the design frequency range with only the stub. Performance at the frequency limits is visibly lower than within the peak performance region. The middle curve shows the effects of circularizing τ. Average performance levels have improved noticeably at both ends of the spectrum.

In lieu of, or in addition to, the adjustment of element lengths, you may also add a parasitic director to an LPDA, as shown in **Fig 12**. The director is cut roughly for the highest operating frequency. It may be spaced between 0.1 λ and 0.15 λ from the forward-most element of the LPDA. The exact length and spacing should be determined experimentally (or from models) with two factors in mind. First, the element should not adversely effect the feed-point impedance at the highest operating frequencies. Close spacing of the director has the greatest effect on this impedance. Second, the exact spacing and element length should be set to have the most desired effect on the overall performance curve of the array. The mechanical impact of adding a director is to increase overall array length by the spacing selected for the element.

The upper curve in Fig 11 shows the effect of adding a director to the circularized array already equipped with a stub. The effect of the director is cumulative, increasing the upper range gain still further. Note that the added parasitic director is not just effective at the highest



Fig 11—The modeled free space gain from 14 to 30 MHz of an LPDA with τ of 0.89 and σ of 0.04. Squares: just a stub to eliminate a weakness; Triangles: with a stub and circularized elements, and Circles: with a stub, circularized elements and a parasitic director.



Fig 12—A generalized sketch of an LPDA with the addition of a parasitic director to improve performance at the higher frequencies within the design range.

frequencies within the LPDA design range. It has a perceptible effect almost all the way across the frequency span of the array, although the effect is smallest at the low-frequency end of the range.

The addition of a director can be used to enhance upper frequency performance of an LPDA, as in the illustration, or simply to equalize upper frequency performance with mid-range performance. High-τ designs, with good low-frequency performance, may need only a director to compensate for high-frequency gain decrease. One potential challenge to adding a director to an LPDA is sustaining a high front-to-back ratio at the upper frequency range.

Throughout the discussion of LPDAs, the performance curves of sample designs have been treated at all frequencies alike, seeking maximum performance across the entire design frequency span. Special compensations are also possible for ham-band-only LPDA designs. They include the insertion of parasitic elements within the array as well as outside the initial design boundaries. In addition, stubs may be employed not so much to eliminate weaknesses, but only to move them to frequencies outside the range of amateur interests.

A DESIGN PROCEDURE FOR AN LPDA

The following presents a systematic step-by-step design procedure for an LPDA with any desired bandwidth. The procedure requires some mathematical calculations, but a common calculator with square-root, logarithmic, and trigonometric functions is completely adequate. The notation used in this section may vary slightly from that used earlier in this chapter.

1) Decide on an operating bandwidth B between f_1, lowest frequency and f_n, highest frequency:

$$B = \frac{f_n}{f_1} \qquad \text{(Eq 6)}$$

2) Choose τ and σ to give the desired estimated average gain.

$$0.8 \le \tau \le 0.98 \text{ and } 0.03 \le \sigma \le \sigma_{opt} \qquad \text{(Eq 7)}$$

where σ_{opt} is calculated as noted earlier in this chapter.

3)Determine the value for the cotangent of the apex half-angle α from

$$\cot\alpha = \frac{4\sigma}{1-\tau} \qquad \text{(Eq 8)}$$

Although α is not directly used in the calculations, cot α is used extensively.

4) Determine the bandwidth of the active region B_{ar} from

$$B_{ar} = 1.1 + 7.7\left(1-\tau\right)^2 \cot\alpha \qquad \text{(Eq 9)}$$

5) Determine the structure (array) bandwidth B_s from

$$B_S = B \times B_{ar} \qquad \text{(Eq 10)}$$

6) Determine the boom length L, number of elements N, and longest element length ℓ_1.

$$L_n = \left(1 - \frac{1}{B_S}\right) \cot\alpha \times \frac{\lambda_{max}}{4} \qquad \text{(Eq 11)}$$

$$\lambda_{max} = \frac{984}{f_1} \qquad \text{(Eq 12)}$$

$$N = 1 + \frac{\log B_s}{\log \frac{1}{\tau}} = 1 + \frac{\ln B_S}{\ln \frac{1}{\tau}} \qquad \text{(Eq 13)}$$

$$\lambda_{1ft} = \frac{492}{f_1} \qquad \text{(Eq 14)}$$

Usually the calculated value for N will not be an integral number of elements. If the fractional value is more than about 0.3, increase the value of N to the next higher integer. Increasing the value of N will also increase the actual value of L over that obtained from the sequence of calculations just performed.

Examine L, N and l_1 to determine whether or not the array size is acceptable for your needs. If the array is too large, increase f_1 or decrease σ or τ and repeat steps 2 through 6. Increasing f_1 will decrease all dimensions. Decreasing σ will decrease the boom length. Decreasing τ will decrease both the boom length and the number of elements.

7) Determine the terminating stub Z_t. (Note: For many HF arrays, you may omit the stub, short out the longest element with a 6-inch jumper, or design a stub to overcome a specific performance weakness.) For VHF and UHF arrays calculate the stub length from

$$Z_t = \frac{\lambda_{max}}{8} \qquad \text{(Eq 15)}$$

8) Solve for the remaining element lengths from

$$\ell_n = \tau\,\ell_{n-1} \qquad \text{(Eq 16)}$$

9) Determine the element spacing $d_{1\text{-}2}$ from

$$d_{1-2} = \frac{\left(\ell_1 - \ell_2\right)\cot\alpha}{2} \qquad \text{(Eq 17)}$$

where ℓ_1 and ℓ_2 are the lengths of the rearmost elements, and d_{1-2} is the distance between the elements with the lengths ℓ_1 and ℓ_2. Determine the remaining element-to-element spacings from

$$d_{(n-1)-n} = \tau\, d_{(n-2)-(n-1)} \qquad \text{(Eq 18)}$$

10) Choose R_0, the desired feed-point resistance, to give the lowest SWR for the intended balun ratio and feed-line impedance. R_0, the mean radiation resistance level of the LPDA input impedance, is approximated by:

$$R_0 = \frac{Z_0}{\sqrt{1 + \frac{Z_0}{4\sigma' Z_{AV}}}} \qquad \text{(Eq 19)}$$

where the component terms are defined and/or calculated in the following way.

From the following equations, determine the necessary antenna feeder (phase-line) impedance, Z_0:

$$Z_0 = \frac{{R_0}^2}{8\sigma' Z_{AV}} + R_0 \sqrt{\left(\frac{R_0}{8\sigma' Z_{AV}}\right)^2 + 1} \qquad \text{(Eq 20)}$$

σ' is the mean spacing factor and is given by

$$\sigma' = \frac{\sigma}{\sqrt{\tau}} \qquad \text{(Eq 21)}$$

Z_{AV} is the average characteristic impedance of a dipole and is given by

$$Z_{AV} = 120\left[1n\left(\frac{\ell_n}{diam_n}\right) - 2.25\right] \qquad \text{(Eq 22)}$$

The ratio, $l_n/diam_n$ is the length-to-diameter ratio of the element n.

11) Once Z_0 has been determined, select a combination of conductor size and spacing to achieve that impedance, using the appropriate equation for the shape of the conductors. If an impractical spacing results for the antenna feeder, select a different conductor diameter and repeat step 11. In severe cases it may be necessary to select a different R_0 and repeat steps 10 and 11. Once a satisfactory feeder arrangement is found, the LPDA design is complete.

A number of the LPDA design examples at the end of this chapter make use of this calculation method. However, the resultant design should be subjected to extensive modeling tests to determine whether there are performance deficiencies or weaknesses that require modification of the design before actual construction.



Fig 13—A sketch of a typical monoband log-cell Yagi. The reflector is, in principle, optional. The log-cell may have from 2 to 5 (or more elements). There may be one or more directors.

Log-Cell Yagis

Fig 12 showed an LPDA with an added parasitic director. Technically, this converts the original design into a hybrid Log-Yag. However, the term *Log-Yag* (or more generally the *log-cell Yagi*) is normally reserved for monoband designs that employ two or more elements in a single-band LPDA arrangement, together with (usually) a reflector and one or more directors. The aim is to produce a monoband directive array with superior directional qualities over a wider bandwidth than can be obtained from many Yagi-Uda designs. Log-cells have also been successfully used as wide-band driver sections for multiband Yagi beams.

Fig 13 illustrates the general outline of a typical log-cell Yagi. The driver section consists of a log periodic array designed for the confines of a single amateur band or other narrow range of frequencies. The parasitic reflector is usually spaced about 0.085 λ behind the rear element of the log cell, while the parasitic director is normally placed between 0.13 and 0.15 λ ahead of the log cell.

Early log-cell Yagis tended to be casually designed. Most of these designs have inferior performance compared with present-day computer-optimized Yagis of the same boom length. Some were designed by adding one or more parasitic directors to simple phased pairs of elements. Although good performance is possible, the operating bandwidth of these designs is small, suitable only for the so-called WARC bands. However, when the log-cell is designed as a narrowly spaced monoband log periodic array, the operating bandwidth increases dramatically. Operating bandwidth here refers not just to the SWR bandwidth, but also to the gain and front-to-back bandwidth.

The widest operating bandwidths require log cells of 3 to 4 elements for HF bands like 20 meters, and 4 to 5 elements for bands as wide as 10 meters. (The bandwidth of the 20-meter band is approximately 2.4% of the center frequency, while the bandwidth of the 10-meter band approaches 9.4% of the center frequency.) A practical limit to σ for log cells used within parasitic arrays is about 0.05. Slightly higher gain may be obtained from higher values of σ, but at the cost of a much longer log cell. The limiting figure for σ results in a practical value for τ between 0.94 and 0.95 to achieve a cell with the desired bandwidth characteristics.

An array designed according to these principles has an overall length that varies with the size of the log cell. A typical array with a 4-element log-cell and single parasitic elements fore and aft is a bit over 0.35 λ long, while a 5-element log-cell Yagi will be between 0.4 and 0.45 λ long. Spacing the reflector more widely (for example, up



Fig 14—Overlaid free-space azimuth patterns for virtually identical 5-element log-cell Yagis (with 3-element log-cells), one having the elements V'd forward at 40° from linear (dashed), the other with linear elements (solid).

to 0.25 λ) has little effect on either gain or front-to-back ratio. Wider spacing of the director will also have only a small effect on gain, since the arrangement is already close to the boom-length limit recommended for director-driver-reflector arrays. Further lengthening of the boom should be accompanied by the addition of one or more directors to the array, if additional gain is desired from the design.

Compared to a modern-day Yagi of the same boom length, the log-cell Yagi is considerably heavier and exhibits a higher wind load due to the requirements of the log-cell driver. Yagis with 3- and 4-elements within the boom lengths just given are capable of peak free-space gain values of 8.2 to 8.5 dBi, while sustaining a high front-to-back ratio. Peak front-to-back ratios are typically in the vicinity of 25 dB. However, Yagi gain tends to decrease below the design frequency (and increase above it), while the front-to-back ratio tends to taper off as one moves away from the design frequency. For the largest log-cell sizes, log-cell Yagis of the indicated boom lengths are capable of sustaining at least 8.2 dBi free-space gain over the entire band, with front-to-back ratios of over 30 dB across the operating bandwidth.

The feed-point impedance of a log-cell Yagi is a function of both the cell design and the influence of the parasitic elements. However, for most cell designs and common phase-line designs, you can achieve a very low variation of resistance and reactance across a desired band. In many cases, the feed impedance will form a direct match for the standard 50-Ω coaxial cable used by most amateur installations. (In contrast, the high-gain, high-front-to-back Yagis used for comparison here have feed-point impedances ranging from 20 to 25 Ω.)

A common design technique used in some LPDA and log-cell Yagi designs is to bend the elements forward to form a series of Vs. A forward angle on each side of the array centerline of about 40° relative to a linear element has been popular. In some instances, the mechanical design of the array may dictate this element formation. However, this arrangement has no special benefits and possibly may degrade performance.

Fig 14 shows the free-space azimuth patterns of a single 5-element log-cell Yagi in two versions: with the elements linear and with the elements bent forward 40°. The V-array loses about $^{1}/_{2}$ dB gain, but more significantly, it loses considerable signal rejection from the sides. Similar comparisons can be obtained from pure LPDA designs and from Yagi-Uda designs when using elements in the vicinity of $^{1}/_{2}$ λ. Unless mechanical considerations call for arranging the elements in a V, the technique is not recommended.

Ultimately, the decision to build and use a log-cell Yagi involves balancing the additional weight and wind-load requirements of this design against the improvements in operating bandwidth for all of the major operating parameters, especially with respect to the front-to-back ratio and the feed-point impedance.

Wire Log-Periodic Dipole Arrays for 3.5 or 7 MHz

These wire log-periodic dipole arrays for the lower HF bands are simple in design and easy to build. They are designed to have reasonable gain, be inexpensive and lightweight, and may be assembled with stock items found in large hardware stores. They are also strong—they can withstand a hurricane! These antennas were first described by John J. Uhl, KV5E, in *QST* for August, 1986. **Fig 15** shows one method of installation. You can use the information here as a guide and point of reference for building similar LPDAs.

If space is available, the antennas can be rotated or repositioned in azimuth after they are completed. A 75-foot tower and a clear turning radius of 120 feet around the base of the tower are needed. The task is simplified



Fig 15—Typical lower-HF wire 4-element log periodic dipole array erected on a tower.

if you use only three anchor points, instead of the five shown in Fig 15. Omit the two anchor points on the forward element, and extend the two nylon strings used for element stays all the way to the forward stay line.

DESIGN OF THE LOG-PERIODIC DIPOLE ARRAYS

Design constants for the two arrays are listed in **Tables 1** and **2**. The preceding sections of this chapter contain the design procedure for arriving at the dimensions and other parameters of these arrays. The primary differences between these designs and one-octave upper HF arrays are the narrower frequency ranges and the use of wire, rather than tubing, for the elements. As design examples for the LPDA, you may wish to work through the step-by-step procedure and check your results against the values in Tables 1 and 2. You may also wish to compare these results with the output of an LPDA design software package such as *LPCAD28*.

From the design procedure, the feeder wire spacings for the two arrays are slightly different, 0.58 inch for the 3.5-MHz array and 0.66 inch for the 7-MHz version. As a compromise toward the use of common spacers for both bands, a spacing of 5/8 inch is quite satisfactory. Surprisingly, the feeder spacing is not at all critical here from a matching standpoint, as may be verified from $Z_0 = 276 \log (2S/\mathrm{diam})$ and from Eq 4. Increasing the spacing to as much as 3/4 inch results in an R_0 SWR of less than 1.1:1 on both bands.

Constructing the Arrays

Construction techniques are the same for both the 3.5 and the 7-MHz versions of the array. Once the designs are completed, the next step is to fabricate the fittings; see **Fig 16** for details. Cut the wire elements and feed lines to the proper sizes and mark them for identification. After the wires are cut and placed aside, it will be difficult to remember which is which unless they are marked. When you have finished fabricating the connectors and cutting all of the wires, the antenna can be assembled. Use your ingenuity when building one of these antennas; it isn't necessary to duplicate these LPDAs precisely.

The elements are made of standard #14 stranded cop-

Table 1

Design Parameters for the 3.5-MHz Single-Band LPDA

$f1$ = 3.3 MHz
f_n = 4.1 MHz
B = 1.2424
τ = 0.845
σ = 0.06
Gain = 5.9 dBi = 3.8 dBd
cot α = 1.5484
B_{ar} = 1.3864
B_s = 1.7225
L = 48.42 feet
N = 4.23 elements (decrease to 4)
Zt = 6-inch short jumper
R_0 = 208 Ω
Z_{AV} = 897.8 Ω
σ' = 0.06527
Z_0 = 319.8 Ω
Antenna feeder:
#12 wire spaced 0.58 inches
Balun: 4:1
Feed line: 52-Ω coax

Element lengths:
$\ell1$ = 149.091 feet
$\ell2$ = 125.982 feet
$\ell3$ = 106.455 feet
$\ell4$ = 89.954 feet
Element spacings:
d_{12}=17.891 feet
d_{23} = 15.118 feet
d_{34} = 12.775 feet
Element diameters
All = 0.0641 inches
ℓ/diameter ratios:
ℓ/diam_4 = 16840
ℓ/diam_3 = 19929
ℓ/diam_2 = 23585
ℓ/diam_1 = 27911

Table 2

Design Parameters for the 7-MHz Single-Band LPDA

$f1$ = 6.9 MHz
f_n = 7.5 MHz
B = 1.0870
τ = 0.845
σ = 0.06
Gain = 5.9 dBi = 3.8 dBd
cot α = 1.5484
B_{ar} = 1.3864
B_s = 1.5070
L = 18.57 feet
N = 3.44 elements (increase to 4)
Z_t = 6-inch short jumper
R_0 = 208 Ω
Z_{AV} = 809.3 Ω
σ' = 0.06527
Z_0 = 334.2 Ω
Antenna feeder:
#12 wire spaced 0.66 inches
Balun: 4:1
Feed line: 52-Ω coax

Element lengths:
$\ell1$ = 71.304 feet
$\ell2$ = 60.252 feet
$\ell3$ = 50.913 feet
$\ell4$ = 43.022 feet
Element spacings:
d_{12} = 8.557 feet
d_{23} = 7.230 feet
d_{34} = 6.110 feet
Element diameters:
All = 0.0641 inches
ℓ/diameter ratios:
$\ell4/\mathrm{diam}_4$ = 8054
$\ell3/\mathrm{diam}_3$ = 9531
$\ell2/\mathrm{diam}_2$ = 11280
$\ell1/\mathrm{diam}_1$ = 13349


Forward
Hole Size to Match Rope Used
2"
Depends on Size of Balun
Hole Size to Match Wire Size Used
1/4"
1/4"
5/8"
(A)
to Rear Anchor
Hole Size to Match Rope Used
1/2"
Hole Size to Match Wire Size Used
1/2"
1/4"
1/4"
5/8"
(B)
2"
Hole Size to Match Wire Size Used
3/4"
3/8"
1/4"
1/4"
5/8"
(C)

Fig 16—Pieces for the LPDA that require fabrication. At A is the forward connector, made from 1/2-inch Lexan (polycarbonate). At B is the rear connector, also made from 1/2-inch Lexan. At C is the pattern for the phase-line spacers, made from 1/4-inch Plexiglas. Two spacers are required for the array.

per wire. The two parallel feed lines are made of #12 solid copper-coated steel wire, such as Copperweld. Copperweld will not stretch when placed under tension. The front and rear connectors are cut from 1/2-inch thick Lexan sheeting, and the feed-line spacers from 1/4-inch Plexiglas sheeting.

Study the drawings carefully and be familiar with the way the wire elements are connected to the two feed lines, through the front, rear and spacer connectors. Details are sketched in **Figs 17** and **18**. Connections made in the way shown in the drawings prevent the wire from breaking. All of the rope, string, and connectors must be made of materials that can withstand the effects of tension and weathering. Use nylon rope and strings, the type that yachtsmen use. Fig 15 shows the front stay rope coming down to ground level at a point 120 feet from the base of a 75-foot tower. Space may not be available for this arrangement in all cases. An alternative installation technique is to put a pulley 40 feet up in a tree and run the front stay rope through the pulley and down to ground level at the base of the tree. The front stay rope will have to be tightened with a block and tackle at ground level.

Putting an LPDA together is not difficult if it is assembled in an orderly manner. It is easier to connect the elements to the feeder lines when the feed-line


to Tower
Elements Made From #14 Copper Stranded Wire
$1/2\ \ell_1$
$1/2\ \ell_2$
$1/2\ \ell_3$
$1/2\ \ell_4$
d_{12}
d_{23}
d_{34}
Overall Feed-Line Length
Nylon Strings
Feed Point
60°
Feed Line Made From #12 Copperweld Wire
Mount Balun on Underside of Connector for Balance
Nylon Rope 1/4" or Larger
to Front Stay

Fig 17—The generic layout for the lower HF wire LPDA. Use a 4:1 balun on the forward connector. See Tables 1 and 2 for dimensions.


NOTES :
① Mount Balun on Bottom of front Connector for Balance
② Feed with 50 Ω Coaxial Cable and 4:1 Balun
③ Pay Close Attention to Detail of Element Connection to Feed Lines
to Tower
Rear Connector 1/2" Thick Lexan
Feeders
Elements
Spacers
to Front Stay
Front Connector and Balun Mount 1/2" Thick Lexan

Fig 18—Details of the electrical and mechanical connections of the elements to the phase-line. Knots in the nylon rope stay line are not shown.

assembly is stretched between two points. Use the tower and a block and tackle. Attaching the rear connector to the tower and assembling the LPDA at the base of the tower makes raising the antenna into place a much simpler task. Tie the rear connector securely to the base of the tower and attach the two feeder lines to it. Then thread the two feed-line spacers onto the feed line. The spacers will be loose at this time, but will be positioned properly when the elements are connected. Now connect the front connector to the feed lines. A word of caution: Measure accurately and carefully! Double-check all measurements before you make permanent connections.

Connect the elements to the feeder lines through their respective plastic connectors, beginning with element 1, then element 2, and so on. Keep all of the element wires securely coiled. If they unravel, you will have a tangled mess of kinked wire. Recheck the element-to-feeder connections to ensure proper and secure junctions. (See Figs 17 and 18.) Once you have completed all of the element connections, attach the 4:1 balun to the underside of the front connector. Connect the feeder lines and the coaxial cable to the balun.

You will need a separate piece of rope and a pulley to raise the completed LPDA into position. First secure the eight element ends with nylon string, referring to Figs 15 and 17. The string must be long enough to reach the tie-down points. Connect the front stay rope to the front connector, and the completed LPDA is now ready to be raised into position. While raising the antenna, uncoil the element wires to prevent their getting away and tangling up into a mess. Use care! Raise the rear connector to the proper height and attach it securely to the tower, then pull the front stay rope tight and secure it. Move the elements so they form a 60° angle with the feed lines, in the direction of the front, and space them properly relative to one another. By adjusting the end positions of the elements as you walk back and forth, you will be able to align all the elements properly. Now it is time to hook your rig to the system and make some contacts.

Performance

The reports received from these LPDAs were compared with an inverted-V dipole. All of the antennas are fixed; the LPDAs radiate to the northeast, and the dipole to the northeast and southwest. The apex of the dipole is at 70 feet, and the 40- and 80-meter LPDAs are at 60 and 50 feet, respectively. Basic array gain was apparent from many of the reports received. During pileups, it was possible to break in with a few tries on the LPDAs, yet it was impossible to break in the same pileups using the dipole. The gain of the LPDAs is several dB over the dipole. For additional gain, experimenters may wish to try a parasitic director about $^1/_8\ \lambda$ ahead of the array. Director length and spacing from the forward LPDA element should be field-adjusted for maximum performance while maintaining the impedance match across each of the bands.

Wire LPDA systems offer many possibilities. They are easy to design and to construct: real advantages in countries where commercially built antennas and parts are not available at reasonable cost. The wire needed can be obtained in all parts of the world, and cost of construction is low. If damaged, the LPDAs can be repaired easily with pliers and solder. For those who travel on DXpeditions where space and weight are large considerations, LPDAs are lightweight but sturdy, and they perform well.

5-Band Log Periodic Dipole Array

A rotatable log periodic array designed to cover the frequency range from 13 to 30 MHz is pictured in **Fig 19**. This is a large array having a free-space gain that varies from 6.6 to over 6.9 dBi, depending upon the operating portion of the design spectrum. This antenna system was originally described by Peter D. Rhodes, WA4JVE, in Nov 1973 *QST*. A measured radiation pattern for the array appears in **Fig 20**.

The characteristics of this array are:

1) Half-power beamwidth, 43° (14 MHz)
2) Design parameter $\tau = 0.9$
3) Relative element spacing constant $\sigma = 0.05$
4) Boom length, L = 26 feet
5) Longest element $\lambda 1$ = 37 feet 10 inches. (A tabulation



Fig 19—The 13-30 MHz log periodic dipole array.



Fig 20—Measured radiation pattern of the 13-30 MHz LPDA. The front-to-back ratio is about 14 dB at 14 MHz and increases to 21 dB at 28 MHz.

Table 3
13-30 MHz LPDA Dimensions, feet

Ele. No.	*Length*	$d_{n-1,n}$ *(spacing)*	*Nearest Resonant*
1	37′ 10.2″	—	
2	34′ 0.7″	3′ 9.4″ = d_{12}	14 MHz
3	30′ 7.9″	3′ 4.9″ = d_{23}	
4	27′ 7.1″	3′ 0.8″ = d_{34}	
5	24′ 10.0″	2′ 9.1″ = d_{45}	18 MHz
6	22′ 4.2″	2′ 5.8″ = d_{56}	21 MHz
7	20′ 1.4″	2′ 2.8″ = d_{67}	
8	18′ 1.2″	2′ 0.1″ = d_{78}	24.9 MHz
9	16′ 3.5″	1′ 9.7″ = d_{89}	28 MHz
10	14′ 7.9″	1′ 7.5″ = $d_{9,10}$	
11	13′ 2.4″	1′ 5.6″ = $d_{10,11}$	
12	11′ 10.5″	1′ 3.8″ = $d_{11,12}$	

Table 4
Materials list: 13-30 MHz LPDA

Material Description	*Quantity*
1) Aluminum tubing—0.047″ wall thickness	
1″—12′ or 6′ lengths	126 lineal feet
⅞″—12′ lengths	96 lineal feet
⅞″—6′ or 12′ lengths	66 lineal feet
¾″—8′ lengths	16 lineal feet
2) Stainless-steel hose clamps—2″ max	48 ea
3) Stainless-steel hose clamps—1¼″ max	26 ea
4) TV type U bolts	14 ea
5) U bolts, galv. type	
5/16″ × 1½″	4 ea
¼″ × 1″	2 ea
6) 1″ ID polyethylene water-service pipe 160 lb/in.^{2} test, approx. 1¼″ OD	20 lineal feet
A) 1¼″ × 1¼ × 1/8″ aluminum Angle—6' lengths	30 lineal feet
B) 1″ × ¼″ aluminum bar—6′ lengths	12 lineal feet
7) 1¼″ top rail of chain-link fence	26 lineal feet
8) 1:1 toroid balun	1 ea
9) 6-32 × 1″ stainless steel screws	24 ea
6-32 stainless steel nuts	48 ea
#6 solder lugs	24 ea
10) #12 copper feeder wire	60 lineal feet
11A) 12″ × 8″ × ¼″ aluminum plate	1 ea
B) 6″ × 4″ × ¼″ aluminum plate	1 ea
12A) ¾″ galv. Pipe	3 lineal feet
B) 1″ galv. pipe-mast	5 lineal feet
13) Galv. guy wire	50 lineal feet
14) ¼″ × 2″ turnbuckles	4 ea
15) ¼″ × 1½″ eye bolts	2 ea
16) TV guy clamps and eye bolts	2 ea



12a
11b
15
14
6a
6
2
9
6b
7
4
1
3
16
13
12b
11a
5
14
16
10
8
Coax to Transceiver
(A)
6–32 ×1″ Stainless Steel
Screw Washer And Nut
Plastic Pipe – 1″ ID
Element
(B)
4 To 6
Solder Lug
Element
Solder to Lug
Bend Loops in Wire Where
Wires Cross. A Plastic
Spreader May be Used if
Necessary.
No 12 AWG Copper Wire
Boom
6
9
(C)
1–1/4″ OD Galv. Steel
Top Rail of Chain–link
Fence – 21 Ft. Section
2 Nuts
Wood
Dowel
3/16″ ×1–1/2″ Galv.
Stove Bolts
(D)

Fig 21—Construction diagrams of the 13-30 MHz LPDA. B and C show the method of making electrical connection between the phase-line and each half-element. D shows how the boom sections are joined.

Table 5
Element Material Requirements: 13-30 MHz LPDA

Ele. No.	***1″ Tubing***		***$^7/_8$″ Tubing***		***$^3/_4$″ Tubing***		***$1^1/_4$″ Angle***	***1″ Bar***
	Len.	*Qty*	*Len.*	*Qty*	*Len.*	*Qty*	*Len.*	*Len.*
1	6′	2	6′	2	8′	2	3′	1′
2	6′	2	12′	2	—	—	3′	1′
3	6′	2	12′	2	—	—	3′	1′
4	6′	2	8.5′	2	—	—	3′	1′
5	6′	2	7′	2	—	—	3′	1′
6	6′	2	6′	2	—	—	3′	1′
7	6′	2	5′	2	—	—	2′	1′
8	6′	2	3.5′	2	—	—	2′	1′
9	6′	2	2.5′	2	—	—	2′	1′
10	3′	2	5′	2	—	—	2′	1′
11	3′	2	4′	2	—	—	2′	1′
12	3′	2	4′	2	—	—	2′	1′

of element lengths and spacings appears in **Table 3**.)
6) Total weight, 116 pounds
7) Wind-load area, 10.7 square feet
8) Required input impedance (mean resistance), R_0 = 72 Ω, Z_t = 6-inch jumper #18 wire
9) Average characteristic dipole impedance, Z_{AV}: 337.8 Ω
10) Impedance of the feeder, Z_0: 117.1 Ω
11) Feeder: #12 wire, close spaced
12) With a 1:1 toroid balun at the input terminals and a 72-Ω coax feed line, the maximum SWR is 1.4:1.

The mechanical assembly uses materials readily available from most local hardware stores or aluminum supply houses. The materials needed are given in **Table 4**. In the construction diagram, **Fig 21**, the materials are referenced by their respective material list numbers. The photograph shows the overall construction, and the drawings show the details. **Table 5** gives the required tubing lengths to construct the elements.

Experimenters may wish to improve the performance of the array at both the upper and lower frequency ends of the design spectrum so that it more closely approaches the performance in the middle of the design frequency range. The most apt general technique for raising both the gain and the front-to-back ratio at the frequency extremes would be to circularize τ as described earlier in this chapter. However, other techniques may also be applied.

The Telerana

The Telerana (Spanish for *spider web*) is a rotatable log periodic antenna that is lightweight, easy to construct and relatively inexpensive to build. Designed to cover 12.1 to 30 MHz, it was co-designed by George Smith, W4AEO, and Ansyl Eckols, YV5DLT, and first described by Eckols in *QST* for Jul 1981. Some of the design parameters are as follow.
1) τ = 0.9
2) σ = 0.05
3) Gain = 4.5 to 5.5 dBi (free-space) depending upon frequency
4) Feed arrangement: 400-Ω feeder line with 4:1 balun, fed with 52-Ω coax. The SWR is 1.5:1 or less in all amateur bands.

The array consists of 13 dipole elements, properly spaced and transposed, along an open wire feeder having an impedance of approximately 400 Ω. See **Figs 22** and **23**. The array is fed at the forward (smallest) end with a 4:1 balun and RG-8 cable placed inside the front arm and leading to the transmitter. An alternative feed method is to use open wire or ordinary TV ribbon and a tuner, eliminating the balun.

The frame that supports the array (**Fig 24**) consists of four 15-foot fiberglass vaulting poles slipped over short nipples at the hub, appearing like wheel spokes (**Fig 25**). Instead of being mounted directly into the fiberglass, the hub mounts into short metal tubing sleeves that are inserted into the ends of each arm to prevent crushing and splitting the fiberglass. The necessary holes are drilled to receive the wires and nylon.

A shopping list is provided in **Table 6**. The center hub is made from a $1^1/_4$-inch galvanized four-outlet cross or X and four 8-inch nipples (Fig 25). A 1-inch diameter X may be used alternatively, depending on the diameter of the fiberglass. A hole is drilled in the bottom of the hub to allow the cable to be passed through after welding the hub to the rotator mounting stub.

All four arms of the array must be 15 feet long. They should be strong and springy to maintain the tautness of the array. If vaulting poles are used, try to obtain all of them with identical strength ratings.

The forward spreader should be approximately 14.8 feet long. It can be much lighter than the four main arms, but must be strong enough to keep the lines rigid.


4: 1
Balun Connects
Here
Egg Ins.
Direction
of Gain
Nylon
Nylon
36.726
5.13
5.05
4.92
9.25
30.34′
16.82′
16.56′
16.13′
1.75
40.714
5.74′
Dimensions in
Feet
This Side
Dimensions in
Meters
This Side
1.94
8.89
13
29.16′
6.36′
8.50
12
27.89′
4.48
2.16
32.986
7.08′
14.69′
Strong Nylon
Cord or Rope
Catenary
8.07
11
26.47′
2.40
7.87′
3.97
13.02′
29.687
7.59
10
24.89′
3.38
2.66
8.72′
11.08′
26.785
7.06
9
23.15′
2.76
2.96
9.71′
9.05′
24.071
6.46
8
21.14′
2.05
3.29
10.79′
6.72′
21.656
5.81
7
19.05′
1.25
3.66
12.00′
4.1′
19.467
5.07
6
16.63′
0.40 m
4.06
13.31′
1.31′
17.549
4.52
14.82′
4.26
5
13.97′
0
0
5.02
16.46′
15.763
Egg
Insulator
Egg
Insulator
3.36
4
11.02′
5.58
18.30′
14.193
2.35
3
7.71′
6.20
20.33′
Spacing Distances
from Rear
7122 Element
Wire
12.769
1.24 m
2
4.06′
Feeder Line Insulators
1/2″
Front View
1/4″
1/4″
1/4″
1/4″
3/4″
11.492 MHz
1
Feeder Line
(400 Ω)
0
0
Elements -3,5,7,9,11,13
Top
View
Tie for Elements
Ant.
El.
Nylon
Leader
to Catenary
Egg
Ins.
Feeder Lines
Solder
Use Double Clinch Knot
for Leader to Catenary
Under
Over
Solder
Elements -2,4,6,8,10,12

Fig 22—The overall configuration of the spider web antenna. Nylon monofilament line is used from the ends of the elements to the nylon cords. Use nylon line to tie every point where lines cross. The forward fiberglass feeder lies on the feeder line and is tied to it. Both metric and English measurements are shown, except for the illustration of the feed-line insulator. Use soft-drawn copper or stranded wire for elements 2 through 12. Element 1 should use 7/22 flexible wire or #14 AWG Copperweld.


13.75′ (4.2 m)
6.88′ (2.10 m)
4: 1 Balun
Forward Spreader
16.83′ (5.13 m)
Forward Supports are of Small Diameter Nylon Rope
16.83′ (5.13 m)
21.22′ (6.47 m)
21.22′ (6.47 m)
Forward Arm
Arms & Spreader are Fiberglass Vaulting Poles, Approx. 1 − 1/2″ Dia.
Hub
30.34′ (9.25 m) Across
Left Arm
Right Arm
Egg Insulator
Tiny Egg Insulators are Used at All Points Where Metal Might Cut Nylon
Arms are Approx. 31.5′(9.60 m) When Flat, Before Bowing Up
Egg Insulator
Rear Arm
21.22′ (6.47 m)
21.22′ (6.47 m)
Feeder Line Also Connects to El.1 Thru Egg Insulators
4 Nipples
Pipe "T" or "X"
Pipe Insert
1 − 1/4″ X 6″ Nipple (4)
1 − 1/4″ Pipe Cross
Rear
Front
Alternative Hub, No Welding. All 1 − 1/4″ or 1″
Pipe "X"
Rotor Stub
1 − 1/4″ Rotator Mounting Stub
Use Hose Clamps at Each End of Fiberglass to Prevent Spliting
Drill Hole for RG − 8
Rear Supports are Formed by Antenna Element #1 Plus a Short Lead to Total 6.47 m
30.34′ (9.25 m) Front to Rear & Side to Side
4: 1 Balun
Front
Optional Support Stub
Feeder Line, Front to Rear Small Nylon Rope, Side to Side (Tie Together Where They Cross)
Hub
Rotator Mounting Stub
RG − 8 to Balun
Note: if Supported Stub is Used, Upward Bow Can be Reduced

Fig 23—The frame construction of the spider web antenna. Two different hub arrangements are illustrated.



Fig 24—Although the spider web antenna resembles a rotatable clothes line, it is much larger, as indicated by Figs 22 and 23. However, the antenna can be lifted by hand.



Fig 25—The simple arrangement of the spider web antenna hub. See Fig 23 and the text for details.



Fig 26—The elements, balun, transmission line and main bow of the spider web antenna.

Table 6
Shopping List for the Telerana

1—1$\frac{1}{4}$-inch galvanized, 4-outlet cross or X.
4—8-inch nipples.
4—15-foot long arms. Vaulting poles suggested. These must be strong and all of the same strength (150 lb) or better.
1—Spreader, 14.8 foot long (must not be metal).
1—4:1 balun unless open-wire or TV cable is used.
12—Feed-line insulators made from Plexiglas or fiberglass.
36—Small egg insulators.
328 feet copper wire for elements; flexible 7/22 is suggested.
65.6 feet (20 m) #14 Copperweld wire for interelement feed line.
164 feet (50 m) strong $\frac{1}{8}$-inch dia cord.
1—Roll of nylon monofilament fishing line, 50 lb test or better.
4—Metal tubing inserts go into the ends of the fiberglass arms.
2—Fiberglass fishing-rod blanks.
4—Hose clamps.

If tapered, the spreader should have the same measurements from the center to each end. *Do not use metal for this spreader*.

Building the frame for the array is the first construction step. Once the frame is prepared, then everything else can be built onto it. Begin by assembling the hub and the four arms, letting them lie flat on the ground with the rotator stub inserted in a hole in the ground. The tip-to-tip length should be about 31.5 feet each way. A hose clamp is used at each end of the arms to prevent splitting. Place the metal inserts in the outer ends of the arms, with 1 inch protruding. The mounting holes should have been drilled at this point. If the egg insulators and nylon cords are mounted to these tube inserts, the whole antenna can be disassembled simply by bending up the arms and pulling out the inserts with everything still attached.

Choose the arm to be at the front end. Mount two egg insulators at the front and rear to accommodate the inter-element feeder. These insulators should be as close as possible to the ends.

At each end of the cross-arm on top, install a small pulley and string nylon cord across and back. Tighten the cord until the upward bow reaches 3 feet above the hub. All cords will require retightening after the first few days because of stretching. The cross-arm can be laid on its side while preparing the feeder line. For the front-to-rear bowstring it is important to use a wire that will not stretch, such as #14 Copperweld. This bowstring is actually the inter-element transmission line. See **Fig 26**.

Secure the rear ends of the feeder to the two rear insulators, soldering the wrap. Before securing the fronts, slip the 12 insulators onto the two feed lines. A rope can be used temporarily to form the bow and to aid in mounting the feeder line. The end-to-end length of the feeder

Improving the Telerana

In *The ARRL Antenna Compendium, Vol 4*, Markus Hansen, VE7CA, described how he modified the Telerana to improve the front-to-back ratio on 20 and 15 meters. In addition, he added a trapped 30/40-meter dipole that functions as a top truss system to stabilize the modified Telerana in strong uprising winds that otherwise could turn the antenna into an "inside-out umbrella."

Fig A shows the layout for the modified Telerana, and Table A lists the lengths and spacings for the #14 wire elements. Note that VE7CA used tuning stubs to tweak the 15 and 20-meter reflector wires for best rearward pattern. The construction techniques used by VE7CA are the same as for the original Telerana. Fig B shows a side view of the additional 40/30-meter-dipole truss sytem.


4: 1 Balun
Direction Of Gain
15 m Parasitic Reflector 3.51 m (138 in.)
Insulators at End of LPDA Feed Line
15 m Tuning Stub
Nylon Rope
Nylon Rope
20 m Parasitic Reflector 5.17 m (202 in.)
20 m Tuning Stub

Fig A—Physical layout of modified Telerana with 20 and 15-meter reflectors added (in place of first two elements in original Telerana). Note the tuning stubs for the added reflectors.

Table A

Element Lengths and Spacings, in Inches

Element Number	*½ Element Length (inches)*	*Total Distance (inches)*
R1	202.0	0.0
L1	210.1	102.0
L2	191.2	140.7
R2	138.0	158.3
L3	174.0	175.9
L4	158.3	207.9
L5	144.1	237.0
L6	131.1	261.5
L7	119.3	285.6
L8	108.6	307.6
L9	98.8	327.6
L10	89.9	345.8
L11	82.4	364.5

Note: the reflector lengths do not include the length of the tuning stubs.


1: 1 Balun
Length from Balun to Trap, 7.15 m or 281.5″
Insulator
3/4″ PVC Pipe
Nylon Rope
Insulator
30 m Trap
40 m Extension 1.88 m or 74″
Tie Transmission Line to PVC pipe and Nylon Rope
Fiberglass Pole
Antenna Pole

Fig B—Side view of 30/40-meter addition to the modified Telerana, using ¾-inch PVC pipe as a vertical stabilizer and support for the 30/40-meter trapped dipole.

should be 30.24 feet.

Now lift both bows to their upright position and tie the feeder line and the cross-arm bowstring together where they cross, directly over and approximately 3 feet above the hub.

The next step is to install the number 1 rear element from the rear egg insulators to the right and left cross-arms using other egg insulators to provide the proper element length. Be sure to solder the element halves to the transmission line. Complete this portion of the construction by installing the nylon cord catenaries from the front arm to the cross-arm tips. Use egg insulators where needed to prevent cutting the nylon cords.

When preparing the fiberglass forward spreader, keep in mind that it should be 14.75 feet long before bowing and is approximately 13.75 feet across when bowed. Secure the center of the bowstring to the end of the front arm. Lay the spreader on top of the feed line, then tie the feeder to the spreader with nylon fish line. String the catenary from the spreader tips to the cross-arm tips.

At this point of assembly, prepare antenna elements 2 through 13. There will be two segments for each element. At the outer tip make a small loop and solder the wrap. The loop will be for the nylon leader. Measure the length plus 0.4 inch for wrapping and soldering the element segment to the feeder. Seven-strand #22 antenna wire is suggested for the element wires. Slide the feedline insulators to their proper position and secure them temporarily.

The drawings show the necessary transposition scheme. Each element half of elements 1, 3, 5, 7, 9, 11 and 13 is connected to its own side of the feeder, while elements 2, 4, 6, 8, 10 and 12 cross over to the opposite side of the transmission line.

There are four holes in each of the transmission-line insulators (see Fig 22). The inner holes are for the transmission line, and the outer ones are for the elements. Since the array elements are slanted forward, they should pass through the insulator from front to back, then back over the insulator to the front side and be soldered to the transmission line. The small drawings of Fig 22 show the details of the element transpositions.

Everywhere that lines cross, tie them together with nylon line, including all copper-nylon and nylon-nylon junctions. Careful tying makes the array much more rigid. However, all elements should be mounted loosely before you try to align the whole thing. Tightening any line or element affects all the others. There will be plenty of walking back and forth before the array is aligned properly. Expect the array to be firm but not extremely taut.

The Pounder: A Single-Band 144-MHz LPDA

The 4-element Pounder LPDA pictured in **Fig 27** was developed by Jerry Hall, K1TD, for the 144-148 MHz band. Because it started as an experimental antenna, it utilizes some unusual construction techniques. However, it gives a very good account of itself, exhibiting a theoretical free-space gain of about 7.2 dBi and a front-to-back ratio of 20 dB or better. The Pounder is small and light. It weighs just 1 pound, and hence its name. In addition, as may be seen in **Fig 28**, it can be disassembled and reassembled quickly, making it an excellent antenna for portable use. This array also serves well as a fixed-station antenna, and may be changed easily to either vertical or horizontal polarization.

The antenna feeder consists of two lengths of $^1/_2 \times {}^1/_2 \times {}^1/_{16}$-inch angle aluminum. The use of two facing flat surfaces permits the builder to obtain a lower characteristic impedance than can be obtained from round conductors with the same spacing. The feeder also serves as the boom for the Pounder. In the first experimental model, the array contained only two elements with a spacing of 1 foot, so a boom length of 1 foot was the primary design requirement for the 4-element version. **Table 7** gives the calculated design data for the 4-element array.



Fig 27—The 144 MHz Pounder. The boom extension at the left of the photo is a 40-inch length of slotted PVC tubing, $^7/_8$-inch outer diameter. The tubing may be clamped to the side of a tower or attached to a mast with a small boom-to-mast plate. Rotating the tubing at the clamp will provide for either vertical or horizontal polarization.

Construction

You can see the general construction approach for



Fig 28—One end of each half element is tapped to fasten onto boom-mounted screws. Disassembly of the array consists of merely unscrewing 8 half elements from the boom. The entire disassembled array creates a small bundle only 21 inches long.

Table 7

Design Parameters for the 144-MHz Pounder

f1 = 143 MHz
f_n = 148 MHz
B = 1.0350
τ = 0.92
σ = 0.053
Gain = 7.2 dBi = 5.1 dBd
cot α = 2.6500
B_{ar} = 1.2306
B_s = 1.2736
L = 0.98 feet
N = 3.90 elements (increase to 4)
Zt = none
R_0 = 52 Ω
Z_{AV} = 312.8 Ω
σ' = 0.05526
Z_0 = 75.1 Ω

Element lengths:
$\ell 1$ = 3.441 feet
$\ell 2$ = 3.165 feet
$\ell 3$ = 2.912 feet
$\ell 4$ = 2.679 feet
Element spacings:
d_{12} = 0.365 feet
d_{23} = 0.336 feet
d_{34} = 0.309 feet
Element diameters:
All = 0.25 inches
ℓ/diameter ratios:
$\ell 4/\mathrm{diam}_4$ = 128.6
$\ell 3/\mathrm{diam}_3$ = 139.8
$\ell 2/\mathrm{diam}_2$ = 151.9
$\ell 1/\mathrm{diam}_1$ = 165.1

Antenna feeder: 1/2 × 1/2 × 1/16″ angle aluminum spaced 1/4″
Balun: 1:1 (see text)
Feed line: 52-Ω coax (see text)



Fig 29—A close-up view of the boom, showing an alternative mounting scheme. This photo shows an earlier 2-element array, but the boom construction is the same for 2 or 4 elements. See the text for details.



Fig 30—The feed arrangement, using a right-angle chassis-mounted BNC connector, modified by removing a portion of the flange. A short length of bus wire connects the center pin to the opposite feeder conductor.

the Pounder in the photographs. Drilled and tapped pieces of Plexiglas sheet, 1/4-inch thick, serve as insulating spacers for the angle aluminum feeder. Two spacers are used, one near the front and one near the rear of the array. Four #6-32 × 1/4-inch pan head screws secure each aluminum angle section to the Plexiglas spacers, as shown in **Figs 29** and **30**. Use flat washers with each screw to prevent it from touching the angle stock on the opposite side of the spacer. Be sure the screws are not so long as to short out the feeder! A clearance of about 1/16 inch is sufficient. If you have doubts about the screw lengths, check the assembled boom for a short with your ohmmeter on a Megohm range.

Either of two mounting techniques may be used for the Pounder. As shown in Figs 27 and 28, the rear spacer measures 10 × 2 1/2 inches, with 45º corners to avoid sharp points. This spacer also accommodates a boom extension of PVC tubing, which is attached with two #10-32 × 1-inch screws. This tubing provides for side mounting the Pounder away from a mast or tower.

An alternative support arrangement is shown in Fig 29. Two 1/2 × 3-inch Plexiglas spacers are used at the front and rear of the array. Each spacer has four holes drilled 5/8 inch apart and tapped with #6-32 threads. Two screws enter each spacer from either side to make a tight aluminum-Plexiglas-aluminum sandwich. At the center of the boom, secured with only two screws, is a 2 × 18-inch strip of 1/4-inch Plexiglas. This strip is slotted about 2 inches from each end to accept hose clamps for mounting the Pounder atop a mast. As shown, the strip is attached for vertical polarization. Alternate mounting holes, visible on the now-horizontal lip of the angle stock, provide for horizontal polarization. Although sufficient, this mounting arrangement is not as sturdy as that shown in Fig 27.

The elements are lengths of thick-wall aluminum tubing, 1/4-inch OD. The inside wall conveniently accepts a #10-32 tap. The threads should penetrate the tubing to a depth of at least 1 inch. Eight #10-32 × 1-inch screws are attached to the boom at the proper element spacings and held in place with #10-32 nuts, as shown in Fig 28. For assembly, the elements are then simply screwed into place.

Note that with this construction arrangement, the two halves of any individual element are not precisely collinear; their axes are offset by about 3/4 inch. This offset does not seem to affect performance.

The Feed Arrangement

Use care initially in mounting and cutting the elements to length. To obtain the 180° crossover feed arrangement, the element halves from a single section of the feeder/boom must alternate directions. That is, for half-elements attached to one of the two pieces of angle stock, elements 1 and 3 will point to one side, and elements 2 and 4 to the other. This arrangement may be seen by observing the element-mounting screws in Fig 28. Because of this mounting scheme, the length of tubing for an element "half" is not simply half of the length given in Table 7. After final assembly, halves for elements 2 and 4 will have a slight overlap, while elements 1 and 3 are extended somewhat by the boom thickness. The best procedure is to cut each assembled element to its final length by measuring from tip to tip.

The Pounder may be fed with RG-58 or RG-59 coax and a BNC connector. A modified right-angle chassis-mount BNC connector is attached to one side of the feeder/boom assembly for cable connection, Fig 30. The modification consists of cutting away part of the mounting flange that would otherwise protrude from the boom assembly. This leaves only two mounting-flange holes, but these are sufficient for a secure mount. A short length of small bus wire connects the center pin to the opposite side of the feeder, where it is secured under the mounting-screw nut for the shortest element.

For operation, you may secure the coax to the PVC boom extension or to the mast with electrical tape. You should use a balun, especially if the Pounder is operated with vertical elements. A choke type of balun is satisfactory, formed by taping 6 turns of the coax into a coil of 3 inches diameter, but a bead balun is preferred (see Chapter 26). The balun should be placed at the point where the coax is brought away from the boom. If the mounting arrangement of Fig 29 is used with vertical polarization, a second balun should be located approximately 1/4 wavelength down the coax line from the first. This will place it at about the level of the lower tips of the elements. For long runs of coax to the transmitter, a transition from RG-58 to RG-8 or from RG-59 to RG-9 is suggested, to reduce line losses. Make this transition at some convenient point near the array.

No shorting feeder termination is used with the array described here. The antenna feeder (phase-line) Z_0 of this array is in the neighborhood of 120 Ω, and with a resulting feed-point impedance of about 72 Ω. The theoretical mean SWR with 52 Ω line is 72/52 or 1.4 to 1. Upon array completion, the measured SWR (52-Ω line) was found to be relatively constant across the band, with a value of about 1.7 to 1. The Pounder offers a better match to 72-Ω coax.

Being an all-driven array, the Pounder is more immune to changes in feed-point impedance caused by nearby objects than is a parasitic array. This became obvious during portable use when the array was operated near trees and other objects… the SWR did not change noticeably with antenna rotation toward and away from those objects. Consequently, the Pounder should behave well in a restricted environment, such as an attic. Weighing just one pound, this array indeed does give a good account of itself.

Log Periodic-Yagi Arrays

Several possibilities exist for constructing high-gain arrays that use the log periodic dipole array concept. One technique is to add parasitic elements to the LPDA to increase both the gain and the front-to-back ratio for a specific frequency within the passband of the LPDA. The LPDA-Yagi combination is simple in concept. It utilizes an LPDA group of driven elements, along with parasitic elements at normal Yagi spacings from the active elements of the LPDA.

The LPDA-Yagi combinations are endless. An example of a single-band high-gain design is a 2- or 3-element LPDA for 21.0 to 21.45 MHz with the addition of two or three parasitic directors and one parasitic reflector. The name Log-Yag (log-cell Yagi) array has been coined for these hybrid antennas. The LPDA portion of the array is of the usual design to cover the desired bandwidth, and standard Yagi design procedures are used for the parasitic elements. Information in this section is based on a Dec 1976, *QST* article by P. D. Rhodes, K4EWG, and J. R. Painter, W4BBP, "The Log-Yag Array."

THE LOG-YAG ARRAY

The Log-Yag array, with its added parasitic elements, provides higher gain and greater directivity than would be realized with the LPDA alone. Yagi arrays require a long boom and wide element spacing for wide bandwidth and high gain, because the Q of the Yagi system increases as the number of elements is increased or as the spacing between adjacent elements is decreased. An increase in the Q of the Yagi array means that the total operating bandwidth of the array is decreased, and the gain and front-to-back ratio specified in the design are obtainable only over small portions of the band. [Older Yagi designs did indeed exhibit the limitations mentioned here. But modern, computer-aided design has resulted in wideband Yagis, provided that sufficient elements are used on the boom to allow stagger tuning for wide-band coverage. See Chapter 11.—*Ed.*]

The Log-Yag system overcomes this difficulty by using a multiple driven element cell designed in accordance with the principles of the log periodic dipole array. Since this log cell exhibits both gain and directivity by itself, it is a more effective wide-band radiator than a simple dipole driven element. The front-to-back ratio and gain of the log cell can then be improved with the addition of a parasitic reflector and director.

It is not necessary for the parasitic element spacings to be large with respect to wavelength, since the log cell is the determining factor in the array bandwidth. As well, the element spacings within the log cell may be small with respect to a wavelength without appreciable deterioration of the cell gain. For example, decreasing the relative spacing constant (σ) from 0.1 to 0.05 will decrease the array gain by less than 1 dB.

A Practical Example

The photographs and figures show a Log-Yag array for the 14-MHz amateur band. The array design takes the form of a 4-element log cell, a parasitic reflector spaced at 0.085 λ_{max}, and a parasitic director spaced at 0.15 λ_{max} (where λ_{max} is the longest free-space wavelength within the array passband). Array gain is almost unaffected with reflector spacings from 0.08 λ to 0.25 λ, and the increase in boom length is not justified. The function of the reflector is to improve the front-to-back ratio of the log cell, while the director sharpens the forward lobe and decreases the half-power beamwidth. As the spacing between the parasitic elements and the log cell decreases, the parasitic elements must increase in length.

The log cell is designed to meet upper and lower band limits with $\sigma = 0.05$. The design parameter τ is dependent on the structure bandwidth, B_s. When the log periodic design parameters have been found, the element length and spacings can be determined.

Array layout and construction details can be seen in Figs 31 through 34. Characteristics of the array are given in **Table 8**.

The method of feeding the antenna is identical to that of feeding the log periodic dipole array without the parasitic elements. As shown in **Fig 31**, a balanced feeder is required for each log-cell element, and all adjacent elements are fed with a 180° phase shift by alternating connections. Since the Log-Yag array will be covering a relatively small bandwidth, the radiation resistance of the narrow-band log cell will vary from 80 to 90 Ω (tubing

Table 8
Log-Yag Array Characteristics

1) Frequency range	14 to 14.35 MHz
2) Operating bandwidth	B = 1.025
3) Design parameter	$\tau = 0.946657$
4) Apex half angle	$\alpha = 14.921°$; $\cot \alpha = 3.753$
5) Half-power beamwidth	42° (14 to 14.35 MHz)
6) Bandwidth of structure	Bs = 1.17875
7) Free-space wavelength	λ_{max} = 70.28 feet
8) Log cell boom length	L = 10.0 feet
9) Longest log element	$\ell 1$ = 35.14 feet (a tabulation of element lengths and spacings is given in Table 9)
10) Forward gain (free space)	8.2 dBi
11) Front-to-back ratio	32 dB (theoretical)
12) Front-to-side ratio	45 dB (theoretical)
13) Input impedance	Z_0 = 37 Ω
14) SWR	1.3 to 1 (14 to 14.35 MHz)
15) Total weight	96 pounds
16) Wind-load area	8.5 sq feet
17) Reflector length	36.4 feet at 6.0 foot spacing
18) Director length	32.2 feet at 10.5 foot spacing
19) Total boom length	26.5 feet


Reflector
ℓ1
ℓ2
ℓ3
ℓ4
Director
d1
h1
1: 1
Balun
S
RG – 8
52 Ω
h1
0.15 λ Max.
d34
d32
d21
0.85 λ
Max.

Fig 31—Layout of the Log-Yag array.

Table 9
Log-Yag Array Dimensions

Element	*Length Feet*	*Spacing Feet*
Reflector	36.40	6.00 (Ref. to ℓ1)
ℓ1	35.14	3.51 (d_{12})
ℓ2	33.27	3.32 (d_{23})
ℓ3	31.49	3.14 (d_{34})
ℓ4	29.81	10.57 (ℓ4 to dir.)
Director	32.20	

elements) depending on the operating bandwidth. The addition of parasitic elements lowers the log-cell radiation resistance. Hence, it is recommended that a 1:1 balun be connected at the log-cell input terminals and 50-Ω coaxial cable be used for the feed line.

The measured radiation resistance of the 14-MHz Log-Yag is 37 Ω over the frequency range from 14.0 to 14.35 MHz. It is assumed that tubing elements will be used. However, if a wire array is used, then the radiation resistance R_0 and antenna-feeder input impedance Z_0 must be calculated so that the proper balun and coax may be used. The procedure is outlined in detail in an earlier part of this chapter. However, programs such as *LPCAD28* are also suitable to automate the calculations.

Table 9 has array dimensions. **Tables 10** and **11** contain lists of the materials necessary to build the Log-Yag array.


Reflector
⑭
⑲
⑮
④
⑰
⑬
⑱
⑳
⑩
⑨
⑯
Director
Boom to Mast Detail
①
⑦
⑧
⑪
④
⑥
①
⑥
⑨
Clamp
Over Bar,
Angle & PVC Pipe
⑦
Driven Element to Boom Detail

Fig 32—Assembly details. The numbered components refer to Table 11.

Table 10
Element Material Requirements: Log-Yag Array

	1-in. Tubing		*⅞-in. Tubing*		*¾-in. Tubing*		*1¼-in. Angle*	*1¼-in. Bar*
	Len. Feet	*Qty*	*Len. Feet*	*Qty*	*Len. Feet*	*Qty*	*Len. Feet*	*Len. Feet*
Reflector	12	1	6	2	8	2	None	None
ℓ1	6	2	6	2	8	2	3	1
ℓ2	6	2	6	2	8	2	3	1
ℓ3	6	2	6	2	6	2	3	1
ℓ4	6	2	6	2	6	2	3	1
Director	12	1	6	2	6	2	None	None



Fig 33—The attachment of the elements to the boom.



Fig 34—Looking from the front to the back of the Log-Yag array. A truss provides lateral and vertical support.

Table 11
Materials List, Log-Yag Array

1) Aluminum tubing—0.047 in. wall thickness
   1 in.—12 ft lenths, 24 lin. ft
   1 in.—12 ft or 6 ft lengths, 48 lin. ft
   ⅞ in.—12 ft or 6 ft lengths, 72 lin. ft
   ¾ in.—8 ft lengths, 48 lin. ft
   ¾ in.—6 ft lengths, 36 lin. ft
2) Stainless steel hose clamps—2 in. max, 8 ea
3) Stainless steel hose clamps—1¼ in. max, 24 ea
4) TV-type U bolts—1½ in., 6 ea
5) U bolts, galv. type: 5/16 in. × 1½ in., 6 ea
5A) U bolts, galv. type: ¼ in. × 1 in., 2 ea
6) 1 in. ID water-service polyethylene pipe 160 lb/in.^{2} test, approx. 1⅜ in. OD, 7 lin. ft
7) 1¼ in. × 1¼ in. × ⅛ in. aluminum angle—6 ft lengths, 12 lin. ft
8) 1 in. × ¼ in. × ¼ in. aluminum angle—6 ft lengths, 6 lin. ft
9) 1¼ in. top rail of chain-link fence, 26.5 lin. ft
10) 1:1 toroid balun, 1 ea
11) No. 6-32 × 1 in. stainless steel screws, 8 ea
    No. 6-32 stainless steel nuts, 16 ea
    No. 6 solder lugs, 8 ea
12) #12 copper feed wire, 22 lin. ft
13) 12 in. × 6 in. × ¼ in. aluminum plate, 1 ea
14) 6 in. × 4 in. × ¼ in. aluminum plate, 1 ea
15) ¾ in. galv. pipe, 3 lin. ft
16) 1 in. galv. pipe—mast, 5 lin. ft
17) Galv. guy wire, 50 lin. ft
18) ¼ in. × 2 in. turnbuckles, 4 ea
19) ¼ in. × 1½ in. eye bolts, 2 ea
20) TV guy clamps and eyebolts, 2 ea

BIBLIOGRAPHY

Source material and more extended discussion of the topics covered in this chapter can be found in the references listed below and in the textbooks listed at the end of Chapter 2.

D. Allen, "The Log Periodic Loop Array (LPLA) Antenna," *The ARRL Antenna Compendium, Vol 3,* pp 115-117.

C. A. Balanis, *Antenna Theory, Analysis and Design,* 2nd Ed. (New York: John Wiley & Sons, 1997) Chapter 9.

P. C. Butson and G. T. Thompson, "A Note on the Calculation of the Gain of Log-Periodic Dipole Antennas," *IEEE Trans on Antennas and Propagation*, Vol AP-24, No. 1, Jan 1976, pp 105-106.

R. L. Carrel, "The Design of Log-Periodic Dipole Antennas," *1961 IRE International Convention Record*.

L. B. Cebik, “The Monoband Log-Cell Yagi Revisited,” (4-part series) *National Contest Journal*, Jan-Jul 2000.

L. B. Cebik, “Some Preliminary Notes on Standard Design LPDAs for 3-30 MHz,” (2-part series), *QEX*, Mar-May 2000.

R. H. DuHamel and D. E. Isbell, “Broadband Logarithmically Periodic Antenna Structures,” *1957 IRE National Convention Record*, Part 1.

A. Eckols, “The Telerana: A Broadband 13- to 30-MHz Directional Antenna,” *QST*, Jul 1981, pp 24-27.

J. Fisher, “Development of the W8JF Waveram: A Planar Log-Periodic Quad Array,” *The ARRL Antenna Compendium, Vol 1*, pp 50-54.

M. Hansen, “The Improved Telerana, with Bonus 30/40 meter Coverage,” *The ARRL Antenna Compendium, Vol 4*, pp 112-117.

K. Heitner, “A Wide-Band, Low-Z Antenna—New Thoughts on Small Antennas,” *The ARRL Antenna Compendium, Vol 1*, pp 48-49.

D. E. Isbell, “Log-Periodic Dipole Arrays,” *IRE Transactions on Antennas and Propagation*, Vol. AP-8, No. 3, May 1960.

J. D. Kraus, *Antennas*, 2nd Ed. (New York: McGraw-Hill, 1988), Chapter 15.

R. A. Johnson, ed., *Antenna Engineering Handbook*, 3rd Ed. (New York: McGraw-Hill, 1993), Chapters 14 and 26.

K. Luetzelschwab, “Log Periodic Dipole Array Improvements,” *The ARRL Antenna Compendium, Vol 6*, pp 74-76.

D. A. Mack, “A Second-Generation Spiderweb Antenna,” *The ARRL Antenna Compendium, Vol 1*, pp 55-59.

P. E. Mayes and R. L. Carrel, “Log Periodic Resonant-V Arrays,” *IRE Wescon Convention Record*, Part 1, 1961.

P. E. Mayes, G. A. Deschamps, and W. T. Patton, “Backward Wave Radiation from Periodic Structures and Application to the Design of Frequency Independent Antennas,” *Proc. IRE*.

J. J. Meyer, “A Simple Log-Yag Array for 50 MHz,” *The ARRL Antenna Compendium, Vol 1*, pp 62-63.

C. T. Milner, “Log Periodic Antennas,” *QST*, Nov 1959, pp 11-14.

W. I. Orr and S. D. Cowan, *Beam Antenna Handbook*, pp 251-253.

P. D. Rhodes, “The Log-Periodic Dipole Array,” *QST*, Nov 1973, pp 16-22.

P. D. Rhodes and J. R. Painter, “The Log-Yag Array,” *QST*, Dec 1976, pp 18-21.

P. D. Rhodes, “The Log-Periodic V Array,” *QST*, Oct 1979, pp 40-43.

P. D. Rhodes, “The K4EWG Log Periodic Array,” *The ARRL Antenna Compendium, Vol 3*, pp 118-123

V. H. Rumsey, *Frequency Independent Antennas* (New York: Academic Press, 1966).

F. Scholz, “A 14-30 MHz LPDA for Limited Space,” *The ARRL Antenna Compendium, Vol 2*, pp 96-99

W. L. Stutzman and G. A. Thiele, *Antenna Theory and Design*, 2nd Ed. (New York: John Wiley & Sons, 1998), Chapter 6.

J. J. Uhl, “Construct a Wire Log-Periodic Dipole Array for 80 or 40 Meters,” *QST*, Aug 1976, pp 21-24.

R. F. Zimmer, “Three Experimental Antennas for 15 Meters,” *CQ*, Jan 1983, pp 44-45.

R. F. Zimmer, “Development and Construction of ‘V’ Beam Antennas,” *CQ*, Aug 1983, pp 28-32.

Chapter 11

HF Yagi Arrays

Along with the dipole and the quarter-wave vertical, radio amateurs throughout the world make extensive use of the Yagi array. Hidetsugu Yagi and Shintaro Uda, two Japanese university professors, invented the Yagi in the 1920s. Uda did much of the developmental work, while Yagi introduced the array to the world outside Japan through his writings in English. Although the antenna should properly be called a *Yagi-Uda* array, it is commonly referred to simply as a *Yagi*.

The Yagi is a type of endfire multielement array. At the minimum, it consists of a single driven element and a single parasitic element. These elements are placed parallel to each other, on a supporting boom spacing them apart. This arrangement is known as a 2-element Yagi. The parasitic element is termed a *reflector* when it is placed behind the driven element, opposite to the direction of maximum radiation, and is called a *director* when it is placed ahead of the driven element. See **Fig 1**. In the VHF and UHF spectrum, Yagis employing 30 or more elements are not uncommon, with a single reflector and multiple directors. See Chapter 18, VHF and UHF Antenna Systems, for details on VHF and UHF Yagis. Large HF arrays may employ 10 or more elements, and will be covered in this chapter.

The gain and directional pattern of a Yagi array is determined by the relative amplitudes and phases of the currents induced into all the parasitic elements. Unlike the directly driven multielement arrays considered in Chapter 8, Multielement Arrays, where the designer must compensate for mutual coupling between elements, proper Yagi operation *relies on* mutual coupling. The current in each parasitic element is determined by its spacing from both the driven element and other parasitic elements, and by the tuning of the element itself. Both length and diameter affect element tuning.

For about 50 years amateurs and professionals created Yagi array designs largely by "cut and try" experimental techniques. In the early 1980s, Jim Lawson, W2PV, described in detail for the amateur audience the fundamental mathematics involved in modeling Yagis. His book *Yagi Antenna Design* is highly recommended for serious antenna designers. The advent of powerful microcomputers and sophisticated computer antenna modeling software in the mid 1980s revolutionized the field of Yagi design for the radio amateur. In a matter of minutes, a computer can


Direction of Maximum Radiation
Director
Driven Element
(A)
Direction of Maximum Radiation
Driven Element
Reflector
(B)

Fig 1—Two-element Yagi systems using a single parasitic element. At A the parasitic element acts as a director, and at B as a reflector. The arrows show the direction in which maximum radiation takes place.

try 100,000 or more different combinations of element lengths and spacings to create a Yagi design tailored to meet a particular set of high-performance parameters. To explore this number of combinations experimentally, a human experimenter would take an unimaginable amount of time and dedication, and the process would no doubt suffer from considerable measurement errors. With the computer tools available today, an antenna can be designed, constructed and then put up in the air, with little or no tuning or pruning required.

Yagi Performance Parameters

There are three main parameters used to characterize the performance of a particular Yagi—*forward gain*, *pattern* and *drive impedance/SWR*. Another important consideration is *mechanical strength*. It is very important to recognize that each of the three electrical parameters should be characterized over the frequency band of interest in order to be meaningful. Neither the gain, SWR nor the pattern measured at a single frequency gives very much insight into the overall performance of a particular Yagi.

Poor designs have been known to reverse their directionality over a frequency band, while other designs have excessively narrow SWR bandwidths, or overly "peaky" gain response. Finally, an antenna's ability to survive the wind and ice conditions expected in one's geographical location is an important consideration in any design. Much of this chapter will be devoted to describing detailed Yagi designs that are optimized for a good balance between gain, pattern and SWR over various amateur bands, and that are designed to survive strong winds and icing.

YAGI GAIN

Like any other antenna, the gain of a Yagi must be stated in comparison to some standard of reference. Designers of phased vertical arrays often state gain referenced to a single, isolated vertical element. See the section on "Phased Array Techniques" in Chapter 8, Multielement Arrays.

Many antenna designers prefer to compare gain to that of an *isotropic radiator in free space*. This is a theoretical antenna that radiates equally well in all directions, and by definition, it has a gain of 0 *dBi* (dB isotropic). Many radio amateurs, however, are comfortable using a dipole as a standard reference antenna, mainly because it is *not* a theoretical antenna.

In free space, a dipole does not radiate equally well in all directions—it has a figure-eight azimuth pattern, with deep nulls off the ends of the wire. In its favored directions, a free-space dipole has 2.15 dB gain compared to the isotropic radiator. You may see the term *dBd* in amateur literature, meaning gain referenced to a dipole in free space. Subtract 2.15 dB from gain in dBi to convert to gain in dBd.

Assume for a moment that we take a dipole out of "free space," and place it one wavelength over the ocean, whose saltwater makes an almost perfect ground. At an elevation angle of 15°, where sea water-reflected radiation adds in phase with direct radiation, the dipole has a gain of about 6 dB, compared to its gain when it was in free space, isolated from any reflections. See Chapter 3, The Effects of the Earth.

It is perfectly legitimate to say that this dipole has a gain of 6 dBd, although the term "dBd" (meaning "dB dipole") makes it sound as though the dipole somehow has gain over itself! Always remember that gain expressed in dBd (or dBi) refers to the *counterpart antenna in free space*. The gain of the dipole over saltwater in this example can be rated at either 6 dBd (over a dipole in free space), or as 8.15 dBi (over an isotropic radiator in free space). Each frame of reference is valid, as long as it is used consistently and clearly. In this chapter we will often switch between Yagis in free space and Yagis over ground. To prevent any confusion, gains will be stated in dBi.

Yagi free-space gain ranges from about 5 dBi for a small 2-element design to about 20 dBi for a 31-element long-boom UHF design. The length of the boom is the main factor determining the gain a Yagi can deliver. Gain as a function of boom length will be discussed in detail after the sections below defining antenna response patterns and SWR characteristics.

RESPONSE PATTERNS—FRONT-TO-REAR RATIO

As discussed in Chapter 2, Antenna Fundamentals, for an antenna to have gain, it must concentrate energy radiated in a particular direction, at the expense of energy radiated in other directions. Gain is thus closely related to an antenna's directivity pattern, and also to the losses in the antenna. **Fig 2** shows the *E-plane* (also called *E-field*, for electric field) and *H-plane* (also called *H-field*, for magnetic field) pattern of a 3-element Yagi in free space, compared to a dipole, and an isotropic radiator. These patterns were generated using the computer program *NEC-2*, which is highly regarded by antenna professionals for its accuracy and flexibility.

In free space there is no Earth reference to determine whether the antenna polarization is horizontal or vertical, and so its response patterns are labeled as E-field (electric) or H-field (magnetic). For a Yagi mounted over ground rather than in free space, if the



Fig 2—E-Plane (electric field) and H-Plane (magnetic field) response patterns for 3-element 20-meter Yagi in free space. At A the E-Plane pattern for a typical 3-element Yagi is compared with a dipole and an isotropic radiator. At B the H-Plane patterns are compared for the same antennas. The Yagi has an E-Plane half-power beamwidth of 66°, and an H-Plane half-power beamwidth of about 120°. The Yagi has 7.28 dBi (5.13 dBd) of gain. The front-to-back ratio, which compares the response at 0° and at 180°, is about 35 dB for this Yagi. The front-to-rear ratio, which compares the response at 0° to the largest lobe in the rearward 180° arc behind the antenna, is 24 dB, due to the lobes at 120° and 240°.

E-field is parallel to the earth (that is, the elements are parallel to the earth) then the antenna polarization is horizontal, and its E-field response is then usually referred to as its *azimuth* pattern. Its H-field response is then referred to as its *elevation* pattern.

Fig 2A demonstrates how this 3-element Yagi in free space exhibits 7.28 dBi of gain (referenced to isotropic), and has 5.13 dB gain over a free-space dipole. The gain is in the forward direction on the graph at 0° azimuth, and the forward part of the lobe is called the *main lobe*. For this particular antenna, the angular width of the E-plane main lobe at the half power, or 3 dB points compared to the peak, is about 66°. This performance characteristic is called the antenna's azimuthal *half-power beamwidth*.

Again as seen in Fig 2A, this antenna's response in the reverse direction at 180° azimuth is 34 dB less than in the forward direction. This characteristic is called the antenna's *front-to-back ratio*, and it describes the ability of an antenna to discriminate, for example, against interfering signals coming directly from the rear, when the antenna is being used for reception. In Fig 2A there are two sidelobes, at 120° and at 240° azimuth, which are about 24 dB down from the peak response at 0°. Since interference can come from any direction, not only directly off the back of an antenna, these kinds of sidelobes limit the ability to discriminate against rearward signals. The term *worst-case front-to-rear ratio* is used to describe the worst-case rearward lobe in the 180°-wide sector behind the antenna's main lobe. In this case, the worst-case front-to-rear ratio is 24 dB.

In the rest of this chapter the worst-case front-to-rear ratio will be used as a performance parameter, and will be abbreviated as "F/R." For a dipole or an isotropic radiator, Fig 2A demonstrates that F/R is 0 dB. Fig 2B depicts the H-field response for the same 3-element Yagi in free space, again compared to a dipole and an isotropic radiator in free space. Unlike the E-field pattern, the H-field pattern for a Yagi does not have a null at 90°, directly over the top of the Yagi. For this 3-element design, the H-field half-power beamwidth is approximately 120°.

Fig 3 compares the azimuth and elevation patterns for a horizontally polarized 6-element 14-MHz Yagi, with a 60-foot boom mounted one wavelength over ground, to a dipole at the same height. As with any horizontally polarized antenna, the height above ground is the main factor determining the peaks and nulls in the elevation pattern of each antenna. Fig 3A shows the E-field pattern, which has now been labeled as the Azimuth pattern. This antenna has a half-power azimuthal beamwidth of about 50°, and at an elevation angle of 12° it exhibits a forward gain of 16.02 dBi, including about 5 dB of ground reflection gain over relatively poor ground, with a dielectric constant of 13 and conductivity of 5 mS/m. In free space this Yagi has a gain of 10.97 dBi.

The H-field elevation response of the 6-element Yagi has a half-power beamwidth of about 60° in free space,



Fig 3—Azimuth pattern for 6-element 20-meter Yagi on 60-foot long boom, mounted 60 feet over ground. At A, the azimuth pattern at 12° elevation angle is shown, compared to a dipole at the same height. Peak gain of the Yagi is 16.04 dBi, or just over 8 dB compared to the dipole. At B, the elevation pattern for the same two antennas is shown. Note that the peak elevation pattern of the Yagi is compressed slightly lower compared to the dipole, even though they are both at the same height over ground. This is most noticeable for the Yagi's second lobe, which peaks at about 40°, while the dipole's second lobe peaks at about 48°. This is due to the greater free-space directionality of the Yagi at higher angles.

but as shown in Fig 3B, the first lobe (centered at 12° in elevation) has a half-power beamwidth of only 13° when the antenna is mounted one wavelength over ground. The dipole at the same height has a very slightly larger first-lobe half-power elevation beamwidth of 14°, since its free-space H-field response is omnidirectional.

Note that the free-space H-field directivity of the Yagi suppresses its second lobe over ground (at an elevation angle of about 40°) to 8 dBi, while the dipole's response at its second lobe peak (at about 48°) is at a level of 9 dBi.

The shape of the azimuthal pattern for a Yagi operated over real ground will change slightly as the Yagi is placed closer and closer to earth. Generally, however, the azimuth pattern doesn't depart significantly from the free-space pattern until the antenna is less than 0.5 λ high. This is just over 17 feet high at 28.4 MHz, and just under 35 feet at 14.2 MHz, heights that are not difficult to achieve for most amateurs. Some advanced computer programs can optimize Yagis at the exact installation height.



Fig 4—SWR over the 28.0 to 28.8 MHz portion of the 10-meter band for two different 3-element Yagi designs. One is designed strictly for maximum gain, while the second is optimized for F/R pattern and SWR over the frequency band. A Yagi designed only for maximum gain usually suffers from a very narrow SWR bandwidth.

DRIVE IMPEDANCE AND SWR

The impedance at the driven element in a Yagi is affected not only by the tuning of the driven element itself, but also by the spacing and tuning of nearby parasitic elements, and to a lesser extent by the presence of ground. In some designs that have been tuned solely for maximum gain, the driven-element impedance can fall to very low levels, sometimes less than 5 Ω. This can lead to excessive losses due to conductor resistance, especially at VHF and UHF. In a Yagi that has been optimized solely for gain, conductor losses are usually compounded by large excursions in impedance levels with relatively small changes in frequency. The SWR can thus change dramatically over a band and can create additional losses in the feed cable. **Fig 4** illustrates the SWR over the 28 to 28.8 MHz portion of the 10-meter amateur band for a 5-element Yagi on a 24-foot boom, which has been tuned for maximum forward gain at a spot frequency of 28.4 MHz. Its SWR curve is contrasted to that of a Yagi designed for a good compromise of gain, SWR and F/R.

Even professional antenna designers have difficulty accurately measuring forward gain. On the other hand, SWR can easily be measured by professional and amateur alike. Few manufacturers would probably want to advertise an antenna with the narrow-band SWR curve shown in Fig 4!

Monoband Yagi Performance Optimization

DESIGN GOALS

The previous section discussing driven-element impedance and SWR hinted at possible design trade-offs among gain, pattern and SWR, especially when each parameter is considered over a frequency band rather than at a spot frequency. Trade-offs in Yagi design parameters can be a matter of personal taste and operating style. For example, one operator might exclusively operate the CW portions of the HF bands, while another might only be interested in the Phone portions. Another operator may want a good pattern in order to discriminate against signals coming from a particular direction; someone else may want the most forward gain possible, and may not care about responses in other directions.

Extensive computer modeling of Yagis indicates that the parameter that must be compromised most to achieve wide bandwidths for front-to-rear ratio and SWR is forward gain. However, not much gain must be sacrificed for good F/R and SWR coverage, especially on long-boom Yagis. Although 10 and 7-MHz Yagis are not rare, the HF bands from 14 to 30 MHz are where Yagis are most often found, mainly due to the mechanical difficulties involved with making sturdy antennas for lower frequencies. The highest HF band, 28.0 to 29.7 MHz, represents the largest percentage bandwidth of the upper HF bands, at almost 6%. It is difficult to try to optimize in one design the main performance parameters of gain, worst-case F/R ratio and SWR over this large a band. Many commercial designs thus split up their 10-meter designs into antennas covering one of two bands: 28.0 to 28.8 MHz, and 28.8 to 29.7 MHz. For the amateur bands below 10 meters, optimal designs that cover the entire band are more easily achieved.

DESIGN VARIABLES

There are only a few variables available when one is designing a Yagi to meet certain design goals. The variables are:



(A)

(B)



(C)

Fig 5—Comparisons of three different 3-element 10-meter Yagi designs using 8-foot booms. At A, gain comparisons are shown. The Yagi designed for the best compromise of gain and SWR sacrifices an average of about 0.5 dB compared to the antenna designed for maximum gain. The Yagi designed for optimal F/R, gain and SWR sacrifices an average of 1.0 dB compared to the maximum-gain case, and about 0.4 dB compared to the compromise gain and SWR case. At B, the front-to-rear ratio is shown for the three different designs. The antenna designed for optimal combination of gain, F/R and SWR maintains a F/R higher than 20 dB across the entire frequency range, while the antenna designed strictly for gain has a F/R of 3 dB at the high end of the band. At C, the three antenna designs are compared for SWR bandwidth. At the high end of the band, the antenna designed strictly for gain has a very high SWR.

1. The physical length of the boom
2. The number of elements on the boom
3. The spacing of each element along the boom
4. The tuning of each element
5. The type of matching network used to feed the array.

GAIN AND BOOM LENGTH

As pointed out earlier, the gain of a Yagi is largely a function of the length of the boom. As the boom is made longer, the maximum gain potential rises. For a given boom length, the number of elements populating that boom can be varied, while still maintaining the antenna's gain, provided of course that the elements are tuned properly. In general, putting more elements on a boom gives the designer added flexibility to achieve desired design goals, especially to spread the response out over a frequency band.

Fig 5A is an example illustrating gain versus frequency for three different types of 3-element Yagis on 8-foot booms. The three antennas were designed for the lower end of the 10-meter band, 28.0 to 28.8 MHz, based on the following different design goals:

Antenna 1: Maximum mid-band gain, regardless of F/R or SWR across the band
Antenna 2: SWR less than 2:1 over the frequency band; best compromise gain, with no special consideration for F/R over the band.
Antenna 3: "Optimal" case: F/R greater than 20 dB, SWR less than 2:1 over the frequency band; best compromise gain.

Fig 5B shows the F/R over the frequency band for these three designs, and Fig 5C shows the SWR curves over the frequency band. Antenna 1, the design that strives strictly for maximum gain, has a poor SWR response over the band, as might be expected after the previous section discussing SWR. The SWR is 10:1 at 28.8 MHz and rises to 22:1 at 29 MHz. At 28 MHz, at the low end of the band, the SWR of the maximum-gain design is more than 6:1. Clearly, designing for maximum gain alone produces an unacceptable design in terms of SWR bandwidth. The F/R for Antenna 1 reaches a high point of about 20 dB at the low-frequency end of the band, but falls to only 3 dB at the high-frequency end.

Antenna 2, designed for the best compromise of gain while the SWR across the band is held to less than 2:1, achieves this goal, but at an average gain sacrifice of 0.7 dB compared to the maximum gain case. The F/R for this design is just under 15 dB over the band. This design is fairly typical of many amateur Yagi designs before the advent of computer modeling and optimization programs. SWR can easily be measured, and experimental optimization for forward gain is a fairly straightforward procedure. By contrast, overall pattern optimization is not a trivial thing to achieve experimentally, particularly for antennas with more than four or five elements.

Antenna 3, designed for an optimum combination of F/R, SWR and gain, compromises forward gain an average of 1.0 dB compared to the maximum gain case, and about 0.4 dB compared to the compromise gain/SWR case. It achieves its design objectives of more than 20 dB F/R over the 28.0 to 28.8 MHz portion of the band, with an SWR less than 2:1 over that range.

Fig 6A shows the free-space gain versus frequency for the same three types of designs, but for a bigger 5-element 10-meter Yagi on a 20-foot boom. Fig 6B shows the variation in F/R, and Fig 6C shows the SWR curves versus frequency. Once again, the design that concentrates solely on maximum gain has a poor SWR curve over the band, reaching just over 6:1 toward the high end of the band. The difference in gain between the maximum gain case and the optimum design case has narrowed for this size of boom to an average of under 0.5 dB. This comes about because the designer has access to more variables in a 5-element design than he does in a 3-element design, and he can stagger-tune the various elements to spread the response out over the whole band.

Fig 7A, **B** and **C** show the same three types of designs, but for a 6-element Yagi on a 36-foot boom. The SWR bandwidth of the antenna designed for maximum gain has improved compared to the previous two shorter-boom examples, but the SWR still rises to more than 4:1 at 28.8 MHz, while the F/R ratio is pretty constant over the band, at a mediocre 11 dB average level. While the antenna designed for gain and SWR does hold the SWR below 2:1 over the band, it also has the same mediocre level of F/R performance as does the maximum-gain design.

The optimized 36-foot boom antenna achieves an excellent F/R of more than 22 dB over the whole 28.0 to 28.8 MHz band. Again, the availability of more elements and more space on the 36-foot long boom gives the designer more flexibility in broadbanding the response over the whole band, while sacrificing only 0.3 dB of gain compared to the maximum-gain design.

Fig 8A, **B**, and **C** show the same three types of 10-meter designs, but now for a 60-foot boom, populated with eight elements. With eight elements and a very long boom on which to space them out, the antenna designed solely for maximum gain can achieve a much better SWR response across the band, although the SWR does rise to more than 7:1 at the very high end of the band. The SWR remains less than 2:1 from 28.0 to 28.7 MHz, much better than for shorter-boom, maximum-gain designs. The worst-case F/R ratio is never better than 19 dB, however, and remains around 10 dB over much of the band. The antenna designed for the best compromise gain and SWR loses only about 0.1 dB of gain compared to the maximum-gain design, but does little better in terms of F/R across the band.

Contrasted to these two designs, the antenna optimized for F/R, SWR and gain has an outstanding pattern, exhibiting an F/R of more than 24 dB across the entire





Fig 6—Comparisons of three different designs for 5-element 10-meter Yagis on 20-foot booms. At A, the gain of three different 5-element 10-meter Yagi designs are graphed. The difference in gain between the three antennas narrows because the elements can be stagger-tuned to spread the response out better over the desired frequency band. The average gain reduction for the fully optimized antenna design is about 0.5 dB. At B, the optimal antenna displays better than 22 dB F/R over the band, while the Yagi designed for gain and SWR displays on average 10 dB less F/R throughout the band. At C, the SWR bandwidth is compared for the three Yagis. The antenna designed strictly for forward gain has a poor SWR bandwidth and a high peak SWR of 6:1 at 28.8 MHz.

band, while keeping the SWR below 2:1 from 28.0 to 28.9 MHz. It must sacrifice an average of only 0.4 dB compared to the maximum gain design at the low end of the band, and actually has more gain than the maximum gain and gain/SWR designs at the high-frequency end of the band.

The conclusion drawn from these and many other detailed comparisons is that designing strictly for maximum mid-band gain yields an inferior design when the antenna is examined over an entire frequency band, especially in terms of SWR. Designing a Yagi for both gain and SWR will yield antennas that have mediocre rearward patterns, but that lose relatively little gain compared to the maximum gain case, at least for designs with more than three elements.

However, designing a Yagi for an optimal combination of F/R, SWR and gain results in a loss of gain less than 0.5 dB compared to designs designed only for gain and SWR. **Fig 9** summarizes the forward gain achieved for the three different design types versus boom length, as expressed in wavelength.

Except for the 2-element designs, the Yagis described in the rest of this chapter have the following design goals over a desired frequency band:

1. Front-to-rear ratio over the frequency band of more than 20 dB
2. SWR over the frequency band less than 2:1
3. Maximum gain consistent with points 1 and 2 above

Just for fun, **Fig 10** shows the gain versus boom length for theoretical 20-meter Yagis that have been designed to meet the three design goals above. The 31-element design for 14 MHz would be wondrous to behold. Sadly, it is unlikely that anyone will build one, considering that the boom would be 724 feet long! However, such a design *does* become practical when scaled to 432 MHz. In fact, a K1FO 22-element and a K1FO 31-element Yagi are the prototypes for the theoretical 14-MHz long-boom designs. See Chapter 18, VHF and UHF Antenna Systems.



(A)

(B)

(C)

Fig 7—Comparisons of three different 6-element 10-meter Yagi designs on 36-foot booms. At A, gain is shown over the band. With more elements and a longer boom, the tuning can be staggered even more to make the antenna gain more uniform over the band. This narrows the gain differential between the antenna designed strictly for maximum gain and the antenna designed for an optimal combination of F/R, SWR and gain. The average difference in gain is about 0.2 dB throughout the band. At B, the F/R performance over the band is shown for the three antenna designs. The antenna designed for optimal performance maintains an average of almost 15 dB better F/R over the whole band compared to the other designs. At C, the SWR bandwidth is compared. Again, the antenna designed strictly for maximum gain exhibits a high SWR of 4:1 at 28.8 MHz, and rises to more than 14:1 at 29.0 MHz.

OPTIMUM DESIGNS AND ELEMENT SPACING

Two-Element Yagis

Many hams consider a 2-element Yagi to give “the most bang for the buck” among various Yagi designs, particularly for portable operations such as Field Day. A 2-element Yagi has about 4 dB of gain over a simple dipole (sometimes jokingly called a “one-element Yagi”) and gives a modest F/R of about 10 dB to help with rejection of interference on receive. By comparison, going from a 2-element to a 3-element Yagi increases the boom length by about 50% and adds another element, a 50% increase in the number of elements—for a gain increase of about 1 dB and another 10 dB in F/R.

Element Spacing in Larger Yagis

One of the more interesting results of computer modeling and optimization of high-performance Yagis with four or more elements is that a distinct pattern in the element spacings along the boom shows up consistently. This pattern is relatively independent of boom length, once the boom is longer than about 0.3 λ.

The reflector, driven element and first director of these optimal designs are typically bunched rather closely together, occupying together only about 0.15 to 0.20 λ of the boom. This pattern contrasts sharply with older designs, where the amount of boom taken up by the reflector, driven element and first director was typically more than 0.3 λ. **Fig 11** shows the element spacings for an optimized 6-element, 36-foot boom, 10-meter design, compared to a W2PV 6-element design with constant spacing of 0.15 λ between all elements.

A problem arises with such a bunching of elements toward the reflector end of the boom—the wind loading of the antenna is not equal along the boom. Unless properly compensated, such new-generation Yagis will act like windvanes, punishing, and often breaking, the rotators trying to turn, or hold, them in the wind. One successful solution to windvaning has been to employ “dummy elements” made of PVC piping. These nonconducting elements are placed on the boom close to the last director so



(A)

(B)



(C)

Fig 8—Comparisons of three different 8-element 10-meter Yagi designs using 60-foot booms. At A, gain is shown over the frequency band. With even more freedom to stagger-tune elements and a very long boom on which to place them, the average antenna gain differential over the band is now less than 0.2 dB between the three design cases. At B, an excellent 24 dB F/R for the optimal design is maintained over the whole band, compared to the average of about 12 dB for the other two designs. At C, the SWR differential over the band is narrowed between the three designs, again because there are more variables available to broaden the bandwidth.



Fig 9—Gain versus boom length for three different 10-meter design goals. The goals are: (1) designed for maximum gain across band, (2) designed for a compromise of gain and SWR, and (3) designed for optimal F/R, SWR and gain across 28.0 to 28.8 MHz portion of 10-meter band. The gain difference is less than 0.5 dB for booms longer than approximately 0.5 λ.

the windload is equalized at the mast-to-boom bracket. In addition, it may be necessary to insert a small amount of lead weight at one end of the boom in order to balance the antenna weight.

Despite the relatively close spacing of the reflector, driven element and first director, modern optimal Yagi designs are not overly sensitive to small changes in either element length or spacing. In fact, these antennas can be constructed from design tables without excessive concern about close dimensional tolerances. In the HF range up to 30 MHz, building the antennas to the nearest $^1/_8$-inch results in performance remarkably consistent with the computations, without any “tweaking” or fine-tuning when the Yagi is on the tower.

ELEMENT TUNING

Element tuning (or *self-impedance*) is a complex function of the effective electrical length of each element and the effective diameter of the element. In turn, the effective length and diameter of each element is related to



Fig 10—Theoretical gain versus boom length for 20-meter Yagis designed for optimal combination of F/R, SWR and gain across the entire 14.0 to 14.35 MHz band. The theoretical gain approaches 20 dBi for a gigantic 724-foot boom, populated with 31 elements. Such a design on 20 meters is not too practical, of course, but can readily be achieved on a 24-foot boom on 432 MHz.

the taper schedule (if telescoping aluminum tubing is used, the most common method of construction), the length of each telescoping section, the type and size of mounting bracket used to secure the element to or through the boom, and the size of the Yagi boom itself. See the section entitled "Antenna Frequency Scaling," and "Tapered Elements" in Chapter 2, Antenna Fundamentals, of this book for details about element tuning as a function of tapering and element diameter. Note especially that Yagis constructed using wire elements will perform very differently compared to the same antenna constructed with elements made of telescoping aluminum tubing.

The process by which a modern Yagi is designed usually starts out with the selection of the longest boom possible for a given installation. A suitable number of elements of a given taper schedule are then placed on this boom, and the gain, pattern and SWR are calculated over the entire frequency band of interest to the operator. Once an electrical design is chosen, the designer must then ensure the mechanical integrity of the antenna design. This involves verifying the integrity of the boom and each element in the face of the wind and ice loading expected for a particular location. The section entitled "Construction with Aluminum Tubing" in Chapter 20, Antenna Materials and Accessories, of this book shows details of tapered telescoping aluminum elements for the upper HF bands. In addition, the ARRL book *Physical Design of Yagi Antennas*, by Dave Leeson, W6NL (ex-W6QHS), describes the mechanical design process for all portions of a Yagi antenna very thoroughly, and is highly recommended for serious Yagi builders.



Fig 11—Tapering spacing versus constant element spacing. At A, illustration of how the spacing of the reflector, driven element and first director (over the first 0.19 λ of the boom) of an optimally designed Yagi is bunched together compared to the Yagi at B, which uses constant 0.15 λ spacing between all elements. The optimally designed antenna has more than 22 dB F/R and an SWR less than 1.5:1 over the frequency band 28.0 to 28.8 MHz.

Specific Monoband Yagi Designs

The detailed Yagi design tables that follow are for two taper schedules for HF Yagis covering the 14 through 30-MHz amateur bands. The heavy-duty elements are designed to survive at least 120-mph winds without icing, or 85-mph winds with 1/4-inch radial ice. The medium-duty elements are designed to survive winds greater than 80 mph, or 60-mph winds with 1/4-inch radial ice.

For 10.1 MHz, the elements shown are capable of surviving 105-mph winds, or 93-mph winds with 1/4-inch radial ice. For 7.1 MHz the elements shown can survive 93-mph winds, or 69-mph winds with 1/4-inch radial ice. For these two lower frequency bands, the elements and the booms needed are very large and heavy. Mounting, turning and keeping such antennas in the air is not a trivial task.

Each element is mounted above the boom with a heavy rectangular aluminum plate, by means of U-bolts with saddles, as shown in Fig 35 in Chapter 18, VHF and UHF Antenna Systems for a 6-meter Yagi. This method of element mounting is rugged and stable, and because the element is mounted away from the boom, the amount of element detuning due to the presence of the boom is minimal. The element dimensions given in each table already take into account any element detuning due to the boom-to-element mounting plate. For each element, the length of the tip determines the tuning, since the inner tubes are fixed in diameter and length.

Half Elements

Each design shows the dimensions for *one-half* of each element, mounted on *one side* of the boom. The other half of each element is symmetrical, mounted on the other side of the boom. The use of a tubing sleeve inside the center portion of the element is recommended, so that the element is not crushed by the mounting U-bolts. Unless otherwise noted, each section of tubing is made of 6061-T6 aluminum tubing, with a 0.058-inch wall thickness. This wall thickness ensures that the next standard size of tubing can telescope with it. Each telescoping section is inserted 3 inches into the larger tubing, and is secured by one of the methods shown in Fig 11 in Chapter 20, Antenna Materials and Accessories.

Matching System

Each antenna is designed with a driven-element length appropriate for a hairpin type of matching network. The driven-element's length may require slight readjustment for best match, particularly if a different matching network is used. *Do not change* either the lengths or the telescoping tubing schedule of the parasitic elements—they have been optimized for best performance and will not be affected by tuning of the driven element!



Fig 12—Typical construction techniques for an HF Yagi. This photo shows a hairpin match on a driven element that uses a fiberglass insulator (wrapped in black vinyl tape for protection against UV). Muffler clamps and saddles mount the element to the boom, while U-bolts and saddles mount the element to the boom-to-element plate. The gray PVC sleeves insulate the element from the plate. The feed coax is connected to the two bolts that also connect to the hairpin wire. Note that the hairpin is grounded at its opposite end to dissipate static charges that might otherwise build up.

Fig 12 is a photograph of the driven element for a 2-element 17-meter Yagi built by Chuck Hutchinson, K8CH, for the ARRL book *Simple and Fun Antennas for Hams*. The aluminum tubing on each side of the boom was 1-inch OD, and the two pieces were mechanically joined together with a 3/4-inch OD fiberglass insulator. Chuck wound electrical tape over the insulator to protect the fiberglass from the sun's UV.

Chuck used 3-inch lengths of 1-inch sunlight-resistant PVC conduit, split lengthwise, to make the grey outer insulators for the driven element. The aluminum plates came from DX Engineering, as did the stainless-steel U-bolts and saddle clamps. These saddles ensured that the elements don't rotate on the 2-inch OD boom in the heavy winds in his part of rural Michigan.

You can see the bolts used to pin the center fiberglass insulator to the aluminum tubing, while also providing an electrical connection for the #12 hairpin wire and for the feed-line coax, which uses ferrite beads over the coax's outer vinyl jacket to make a common-mode current-type of balun (not shown in Fig 12). Note that the center of the hairpin is connected to the boom using a grounding lug for some measure of protection from static buildup.

10-METER YAGIS

Fig 13 describes the electrical performance of eight optimized 10-meter Yagis with boom lengths between 6 to 60 feet. The end of each boom includes 3 inches of space for the reflector and last-director (or driven element for the 2-element designs) mounting plates. Fig 13A shows the free-space gain versus frequency for each antenna; 13B shows the front-to-rear ratio, and 13C shows the SWR versus frequency. Each antenna with three or more elements was designed to cover the lower half of the 10-meter band from 28.0 to 28.8 MHz, with SWR less than 2:1 and F/R better than 20 dB over that range.

Fig 13D shows the taper schedule for two types of 10-meter elements. The heavy-duty design can survive 125-mph winds with no icing, and 88-mph winds with $^1/_4$-inch of radial ice. The medium-duty design can handle 96-mph winds with no icing, and 68-mph winds with $^1/_4$-inch of radial ice. The element-to-boom mounting plate for these Yagis is a 0.250-inch thick flat aluminum plate, 4 inches wide by 4 inches long. Each element except for the insulated driven element, is centered on the plate, held by two stainless-steel U-bolts with saddles. Another set



Fig 13—Gain, F/R and SWR performance versus frequency for optimized 10-meter Yagis. At A, gain is shown versus frequency for eight 10-meter Yagis whose booms range from 6 feet to 60 feet long. Except for the 2-element design, these Yagis have been optimized for better than 20 dB F/R and less than 2:1 SWR over the frequency range 28.0 to 28.8 MHz. At B, front-to-rear ratio for these antennas is shown versus frequency, and at C, SWR is shown over the frequency range. At D, the taper schedule is shown for heavy-duty and for medium-duty 10-meter elements. The heavy-duty elements can withstand 125-mph winds without icing, and 88-mph winds with $^1/_4$-inch radial ice. The medium-duty elements can survive 96-mph winds without icing, and 68-mph winds with $^1/_4$-inch radial ice. The wall thickness for each telescoping section of 6061-T6 aluminum tubing is 0.058 inches, and the overlap at each telescoping junction is 3 inches.

Table 1

Optimized 10-Meter Yagi Designs

Two-element 10-meter Yagi, 6 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		210-06H.YW	210-06M.YW
Reflector	0.000"	66.000"	71.500"
Driven Element	66.000"	57.625"	63.000"

Three-element 10-meter Yagi, 8 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		310-08H.YW	310-08M.YW
Reflector	0.000"	66.750"	71.875"
Driven Element	36.000"	57.625"	62.875"
Director 1	54.000"	53.125"	58.500"
Compensator	12" behind Dir. 1	19.000"	18.125"

Four-element 10-meter Yagi, 14 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		410-14H.YW	410-14M.YW
Reflector	0.000"	66.000"	72.000"
Driven Element	36.000"	58.625"	63.875"
Director 1	36.000"	57.000"	62.250"
Director 2	90.000"	47.750"	53.125"
Compensator	12" behind Dir. 2	22.000"	20.500"

Five-element 10-meter Yagi, 24 foot boom

Element	*Spacing, inches*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		510-24H.YW	510-24M.YW
Reflector	0.000"	65.625"	70.750"
Driven Element	36.000"	58.000"	63.250"
Director 1	36.000"	57.125"	62.375"
Director 2	99.000"	55.000"	60.250"
Director 3	111.000"	50.750"	56.125"
Compensator	12" behind Dir. 3	28.750"	26.750"

Six-element 10-meter Yagi, 36 foot boom

Element	*Spacing, inches*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		610-36H.YW	610-36M.YW
Reflector	0.000"	66.500"	71.500"
Driven Element	37.000"	58.500"	64.000"
Director 1	43.000"	57.125"	62.375"
Director 2	98.000"	54.875"	60.125"
Director 3	127.000"	53.875"	59.250"
Director 4	121.000"	49.875"	55.250"
Compensator	12" behind Dir. 4	32.000"	29.750"

Seven-element 10-meter Yagi, 48 foot boom

Element	*Spacing, inches*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		710-48H.YW	710-48M.YW
Reflector	0.000"	65.375"	70.500"
Driven Element	37.000"	59.000"	64.250"
Director 1	37.000"	57.500"	62.750"
Director 2	96.000"	54.875"	60.125"
Director 3	130.000"	52.250"	57.625"
Director 4	154.000"	52.625"	58.000"
Director 5	116.000"	49.875"	55.250"
Compensator	12" behind Dir. 5	35.750"	33.750"

Eight-element 10-meter Yagi, 60 foot boom

Element	*Spacing, inches*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		810-60H.YW	810-60M.YW
Reflector	0.000"	65.000"	70.125"
Driven Element	42.000"	58.000"	63.500"
Director 1	37.000"	57.125"	62.375"
Director 2	87.000"	55.375"	60.625"
Director 3	126.000"	53.250"	58.625"
Director 4	141.000"	51.875"	57.250"
Director 5	157.000"	52.500"	57.875"
Director 6	121.000"	50.125"	55.500"
Compensator	12" behind Dir. 6	59.375"	55.125"

These 10-meter Yagi designs are optimized for > 20 dB F/R, and SWR < 2:1 over frequency range from 28.000 to 28.800 MHz, for heavy-duty elements (125 mph wind survival) and for medium-duty (96 mph wind survival). For coverage from 28.8 to 29.7 MHz, subtract 2.000 inches from end of each element, but leave element spacings the same as shown here. Only element tip dimensions are shown, and all dimensions are inches. See Fig 13D for element telescoping tubing schedule. Torque compensator element is made of 2.5" OD PVC water pipe placed 12 inches behind last director. Dimensions shown for compensators is one-half of total length, centered on boom.

of U-bolts with saddles is used to secure the mounting plate to the boom.

Electrically each mounting plate is equivalent to a cylinder, with an effective diameter of 2.405 inches for the heavy-duty element, and 2.310 inches for the medium-duty element. The equivalent length on each side of the boom is 2 inches. These dimensions are incorporated in the files for the *YW* (Yagi for Windows) computer modeling program on the CD-ROM accompanying this book to simulate the effect of the mounting plate.

The second column in **Table 1** shows the spacing of each element relative to the next element in line on the boom, starting at the reflector, which itself is defined as being at the 0.000-inch reference point on the boom. The boom for antennas less than 30 feet long can be constructed of 2-inch OD tubing with 0.065-inch wall thickness. Designs larger than 30 feet long should use 3-inch OD heavy-wall tubing for the boom. Because each boom has extra space at each end, the reflector is actually placed 3 inches from the end of the boom. For example, in the 310-08H.YW design (3 elements on an 8-foot boom), the driven element is placed 36 inches ahead of the reflector, and the director is placed 54 inches ahead of the driven element.

The next columns give the lengths for the variable tips for the heavy-duty and then the medium-duty elements. In the example above for the 310-08H.YW Yagi, the heavy-duty reflector tip, made out of 1/2-inch OD tubing, sticks out 66.750 inches from the 5/8-inch OD tubing. Note that each telescoping piece of tubing overlaps 3 inches inside the piece into which it fits, so the overall length of 1/8-inch OD tubing is 69.750 inches long for the reflector. The medium-duty reflector tip has 71.875 inches protruding from the 5/8-inch OD tube, and is 74.875 inches long overall. As previously stated, the dimensions are not extremely critical, although measurement accu-



Fig 14—Gain, F/R and SWR performance versus frequency for optimized 12-meter Yagis. At A, gain is shown versus frequency for seven 12-meter Yagis whose booms range from 6 feet to 54 feet long. Except for the 2-element design, these Yagis have been optimized for better than 20 dB F/R and less than 2:1 SWR over the narrow 12-meter band 24.89 to 24.99 MHz. At B, front-to-rear ratio for these antennas is shown versus frequency, and at C, SWR over the frequency range is shown. At D, the taper schedule for heavy-duty and for medium-duty 12-meter elements is shown. The heavy-duty elements can withstand 123-mph winds without icing, and 87-mph winds with 1/4-inch radial ice. The medium-duty elements can survive 85-mph winds without icing, and 61-mph winds with 1/4-inch radial ice. The wall thickness for each telescoping section of 6061-T6 aluminum tubing is 0.058 inches, and the overlap at each telescoping junction is 3 inches.

Table 2

Optimized 12-Meter Yagi Designs

Two-element 12-meter Yagi, 6 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		212-06H.YW	212-06M.YW
Reflector	0.000"	67.500"	72.500"
Driven Element	66.000"	59.500"	65.000"

Three-element 12-meter Yagi, 10 foot boom

Element	*Spacing, inches*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		312-10H.YW	312-10M.YW
Reflector	0.000"	69.000"	73.875"
Driven Element	40.000"	60.250"	65.250"
Director 1	74.000"	54.000"	59.125"
Compensator	12" behind Dir. 1	13.625"	12.000"

Four-element 12-meter Yagi, 15 foot boom

Element	*Spacing, inches*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		412-15H.YW	412-15M.YW
Reflector	0.000"	66.875"	71.875"
Driven Element	46.000"	61.000"	66.000"
Director 1	46.000"	58.625"	63.750"
Director 2	82.000"	50.875"	56.125"
Compensator	12" behind Dir. 2	16.375"	14.500"

Five-element 12-meter Yagi, 20 foot boom

Element	*Spacing, inches*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		512-20H.YW	512-20M.YW
Reflector	0.000"	69.750"	74.625"
Driven Element	46.000"	62.250"	67.000"
Director 1	46.000"	60.500"	65.500"
Director 2	48.000"	55.500"	60.625"
Director 3	94.000"	54.625"	59.750"
Compensator	12" behind Dir. 3	22.125"	19.625"

Six-element 12-meter Yagi, 30 foot boom

Element	*Spacing, inches*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		612-30H.YW	612-30M.YW
Reflector	0.000"	68.125"	73.000"
Driven Element	46.000"	61.750"	66.750"
Director 1	46.000"	60.250"	65.250"
Director 2	73.000"	52.375"	57.625"
Director 3	75.000"	57.625"	62.750"
Director 4	114.000"	53.625"	58.750"
Compensator	12" behind Dir. 4	30.000"	26.250"

Six-element 12-meter Yagi, 40 foot boom

Element	*Spacing, inches*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		612-40H.YW	612-40M.YW
Reflector	0.000"	67.000"	71.875"
Driven Element	46.000"	60.125"	65.500"
Director 1	46.000"	57.375"	62.500"
Director 2	91.000"	57.375"	62.500"
Director 3	157.000"	57.000"	62.125"
Director 4	134.000"	54.375"	59.500"
Compensator	12" behind Dir. 4	36.500"	31.625"

Seven-element 12-meter Yagi, 54 foot boom

Element	*Spacing, inches*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		712-54H.YW	712-54M.YW
Reflector	0.000"	68.000"	73.000"
Driven Element	46.000"	60.500"	65.500"
Director 1	46.000"	56.750"	61.875"
Director 2	75.000"	58.000"	63.125"
Director 3	161.000"	55.625"	60.750"
Director 4	174.000"	56.000"	61.125"
Director 5	140.000"	53.125"	58.375"
Compensator	12" behind Dir. 5	43.125"	37.500"

These 12-meter Yagi designs were optimized for > 20 dB F/R, and SWR < 2:1 over frequency range from 24.890 to 24.990 MHz, for heavy-duty elements (123 mph wind survival) and for medium-duty (85 mph wind survival). Only element tip dimensions are shown, and all dimensions are inches. See Fig 14D for element telescoping tubing schedule. Torque compensator element is made of 2.5" OD PVC water pipe placed 12" behind last director. Dimensions shown for compensators is one-half of total length, centered on boom.



Fig 15—Gain, F/R and SWR performance versus frequency for optimized 15-meter Yagis. At A, gain versus frequency is shown for eight 15-meter Yagis whose booms range from 6 feet to 80 feet long. Except for the 2-element design, these Yagis have been optimized for better than 20 dB F/R and less than 2:1 SWR over the frequency range 21.0 to 21.45 MHz. At B, front-to-rear ratio for these antennas is shown versus frequency, and at C, SWR over the frequency range is shown. At D, the taper schedule for heavy-duty and for medium-duty 15-meter elements is shown. The heavy-duty elements can withstand 124-mph winds without icing, and 90-mph winds with $^{1}/_{4}$-inch radial ice. The medium-duty elements can survive 86-mph winds without icing, and 61-mph winds with $^{1}/_{4}$-inch radial ice. The wall thickness for each telescoping section of 6061-T6 aluminum tubing is 0.058 inches, and the overlap at each telescoping junction is 3 inches.

racy to $^{1}/_{8}$ inch is desirable.

The last row in each variable tip column shows the length of one-half of the "dummy element" torque compensator used to correct for uneven wind loading along the boom. This compensator is made from 2.5 inches OD PVC water pipe mounted to an element-to-boom plate like those used for each element. The compensator is mounted 12 inches behind the last director, the first director in the case of the 3-element 310-08H.YW antenna. Note that the heavy-duty elements require a correspondingly longer torque compensator than do the medium-duty elements.

12-METER YAGIS

Fig 14 describes the electrical performance of seven optimized 12-meter Yagis with boom lengths between 6 to 54 feet. The end of each boom includes 3 inches of space for the reflector and last director (or driven element) mounting plates. The narrow frequency width of the 12-meter band allows the performance to be optimized easily. Fig 14A shows the free-space gain versus frequency for each antenna; 14B shows the front-to-rear ratio, and 14C shows the SWR versus frequency. Each antenna with three or more elements was designed to

Table 3
Optimized 15-Meter Yagi Designs

Two-element 15-meter Yagi, 6 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		215-06H.YW	215-06M.YW
Reflector	0.000"	62.000"	85.000"
Driven Element	66.000"	51.000"	74.000"

Three-element 15-meter Yagi, 12 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		315-12H.YW	315-12M.YW
Reflector	0.000"	62.000"	84.250"
Driven Element	48.000"	51.000"	73.750"
Director 1	92.000"	43.500"	66.750"
Compensator	12" behind Dir. 1	34.750"	37.625"

Four-element 15-meter Yagi, 18 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		415-18H.YW	415-18M.YW
Reflector	0.000"	61.000"	83.500"
Driven Element	56.000"	51.500"	74.500"
Director 1	56.000"	48.000"	71.125"
Director 2	98.000"	36.625"	60.250"
Compensator	12" behind Dir. 2	20.875"	18.625"

Five-element 15-meter Yagi, 24 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		515-24H.YW	515-24M.YW
Reflector	0.000"	62.000"	84.375"
Driven Element	48.000"	52.375"	75.250"
Director 1	48.000"	47.875"	71.000"
Director 2	52.000"	47.000"	70.125"
Director 3	134.000"	41.000"	64.375"
Compensator	12" behind Dir. 3	40.250"	35.125"

Six-element 15-meter Yagi, 36 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		615-36H.YW	615-36M.YW
Reflector	0.000"	61.000"	83.375"
Driven Element	53.000"	52.000"	75.000"
Director 1	56.000"	49.125"	72.125"
Director 2	59.000"	45.125"	68.375"
Director 3	116.000"	47.875"	71.000"
Director 4	142.000"	42.000"	65.375"
Compensator	12" behind Dir. 4	45.500"	39.750"

Seven-element 15-meter Yagi, 48 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		615-48H.YW	615-48M.YW
Reflector	0.000"	62.000"	84.000"
Driven Element	48.000"	52.000"	75.000"
Director 1	48.000"	51.250"	74.125"
Director 2	125.000"	48.000"	71.125"
Director 3	190.000"	45.500"	68.750"
Director 4	161.000"	42.000"	65.375"
Compensator	12" behind Dir. 4	51.500"	45.375"

Seven-element 15-meter Yagi, 60 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		715-60H.YW	715-60M.YW
Reflector	0.000"	59.750"	82.250"
Driven Element	48.000"	52.000"	75.000"
Director 1	48.000"	52.000"	74.875"
Director 2	93.000"	49.500"	72.500"
Director 3	173.000"	44.125"	67.375"
Director 4	197.000"	45.500"	68.750"
Director 5	155.000"	41.750"	65.125"
Compensator	12" behind Dir. 5	58.500"	51.000"

Eight-element 15-meter Yagi, 80 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		815-80H.YW	815-80M.YW
Reflector	0.000"	62.000"	84.000"
Driven Element	56.000"	52.500"	75.500"
Director 1	48.000"	51.500"	74.375"
Director 2	115.000"	48.375"	71.500"
Director 3	164.000"	45.750"	69.000"
Director 4	202.000"	43.125"	66.500"
Director 5	206.000"	44.750"	68.000"
Director 6	163.000"	40.875"	64.250"
Compensator	12" behind Dir. 6	95.000"	83.375"

These 15-meter Yagi designs are optimized for > 20 dB F/R, and SWR < 2:1 over entire frequency range from 21.000 to 21.450 MHz, for heavy-duty elements (124 mph wind survival) and for medium-duty (86 mph wind survival). Only element tip dimensions are shown. See Fig 15D for element telescoping tubing schedule. All dimensions are in inches. Torque compensator element is made of 2.5" OD PVC water pipe placed 12" behind last director, and dimensions shown for compensators is one-half of total length, centered on boom.







Fig 16—Gain, F/R and SWR performance versus frequency for optimized 17-meter Yagis. At A, gain versus frequency is shown for six 17-meter Yagis whose booms range from 6 feet to 60 feet long. Except for the 2-element design, these Yagis have been optimized for better than 20 dB F/R and less than 2:1 SWR over the narrow 17-meter band 18.068 to 18.168 MHz. At B, front-to-rear ratio for these antennas is shown versus frequency, and at C, SWR over the frequency range is shown. At D, the taper schedule for heavy-duty and for medium-duty 10-meter elements is shown. The heavy-duty elements can withstand 123-mph winds without icing, and 89-mph winds with $^1/_4$-inch radial ice. The medium-duty elements can survive 83-mph winds without icing, and 59-mph winds with $^1/_4$-inch radial ice. The wall thickness for each telescoping section of 6061-T6 aluminum tubing is 0.058 inches, and the overlap at each telescoping junction is 3 inches.

cover the narrow 12-meter band from 24.89 to 24.99 MHz, with SWR less than 2:1 and F/R better than 20 dB over that range.

Fig 14D shows the taper schedule for two types of 12-meter elements. The heavy-duty design can survive 123-mph winds with no icing, and 87-mph winds with $^1/_4$ inch of radial ice. The medium-duty design can handle 85-mph winds with no icing, and 61-mph winds with $^1/_4$ inch of radial ice. The element-to-boom mounting plate for these Yagis is a 0.375 inch thick flat aluminum plate, 5 inches wide by 6 inches long.

Electrically, each mounting plate is equivalent to a cylinder, with an effective diameter of 2.945 inches for the heavy-duty element, and 2.857 inches for the medium-duty element. The equivalent length on each side of the boom is 3 inches. As usual, the torque compensator is mounted 12 inches behind the last director.

15-METER YAGIS

Fig 15 describes the electrical performance of eight optimized 15-meter Yagis with boom lengths between 6 feet to a spectacular 80 feet. The end of each boom includes 3 inches of space for the reflector and last-director (or driven element) mounting plates. Fig 15A shows the free-space gain versus frequency for each antenna; 15B shows the worst-case front-to-rear ratio, and 15C shows the SWR versus frequency. Each antenna with three or more elements was designed to cover the full 15-meter band from

Table 4

Optimized 17-meter Yagi Designs

Two-element 17-meter Yagi, 6 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		217-06H.YW	217-06M.YW
Reflector	0.000"	61.000"	89.000"
Driven Element	66.000"	48.000"	76.250"

Three-element 17-meter Yagi, 14 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		317-14H.YW	317-14M.YW
Reflector	0.000"	61.500"	91.500"
Driven Element	65.000"	52.000"	79.500"
Director 1	97.000"	46.000"	73.000"
	12" behind Dir. 1	12.625"	10.750"

Four-element 17-meter Yagi, 20 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		417-20H.YW	417-20M.YW
Reflector	0.000"	61.500"	89.500"
Driven Element	48.000"	54.250"	82.625"
Director 1	48.000"	52.625"	81.125"
Director 2	138.000"	40.500"	69.625"
Compensator	12" behind Dir. 2	42.500"	36.250"

Five-element 17-meter Yagi, 30 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		517-30H.YW	517-30M.YW
Reflector	0.000"	61.875"	89.875"
Driven Element	48.000"	52.250"	80.500"
Director 1	52.000"	49.625"	78.250"
Director 2	93.000"	49.875"	78.500"
Director 3	161.000"	43.500"	72.500"
Compensator	12" behind Dir. 3	54.375"	45.875"

Six-element 17-meter Yagi, 48 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		617-48H.YW	617-48M.YW
Reflector	0.000"	63.000"	90.250"
Driven Element	52.000"	52.500"	80.500"
Director 1	51.000"	45.500"	74.375"
Director 2	87.000"	47.875"	76.625"
Director 3	204.000"	47.000"	75.875"
Director 4	176.000"	42.000"	71.125"
Compensator	12" behind Dir. 4	68.250"	57.500"

Six-element 17-meter Yagi, 60 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		617-60H.YW	617-60M.YW
Reflector	0.000"	61.250"	89.250"
Driven Element	54.000"	54.750"	83.125"
Director 1	54.000"	52.250"	80.750"
Director 2	180.000"	46.000"	74.875"
Director 3	235.000"	44.625"	73.625"
Director 4	191.000"	41.500"	70.625"
Compensator	12" behind Dir. 4	62.875"	53.000"

These 17-m Yagi designs are optimized for > 20 dB F/R, and SWR < 2:1 over entire frequency range from18.068 to 18.168 MHz, for heavy-duty elements (123 mph wind survival) and for medium-duty (83 mph wind survival). Only element tip dimensions are shown. All dimensions are in inches. Torque compensator element is made of 2.5" OD PVC water pipe placed 12" behind last director, and dimensions shown for compensators is one-half of total length, centered on boom.

21.000 to 21.450 MHz, with SWR less than 2:1 and F/R ratio better than 20 dB over that range.

Fig 15D shows the taper schedule for two types of 15-meter elements. The heavy-duty design can survive 124-mph winds with no icing, and 90-mph winds with 1/4 inch of radial ice. The medium-duty design can handle 86-mph winds with no icing, and 61-mph winds with 1/4 inch of radial ice. The element-to-boom mounting plate for these Yagis is a 0.375-inch thick flat aluminum plate, 5 inches wide by 6 inches long.

Electrically, each mounting plate is equivalent to a cylinder, with an effective diameter of 3.0362 inches for





Fig 17—Gain, F/R and SWR performance versus frequency for optimized 20-meter Yagis. At A, gain versus frequency is shown for eight 20-meter Yagis whose booms range from 8 feet to 80 feet long. Except for the 2-element design, these Yagis have been optimized for better than 20 dB F/R and less than 2:1 SWR over the frequency range 14.0 to 14.35 MHz. At B, front-to-rear ratio for these antennas is shown versus frequency, and at C, SWR over the frequency range is shown. At D, the taper schedule for heavy-duty and for medium-duty 20-meter elements is shown. The heavy-duty elements can withstand 122-mph winds without icing, and 89-mph winds with $^1/_4$-inch radial ice. The medium-duty elements can survive 82-mph winds without icing, and 60-mph winds with $^1/_4$-inch radial ice. The wall thickness for each telescoping section of 6061-T6 aluminum tubing is 0.058 inches, and the overlap at each telescoping junction is 3 inches.



the heavy-duty element, and 2.9447 inches for the medium-duty element. The equivalent length on each side of the boom is 3 inches. As usual, the torque compensator is mounted 12 inches behind the last director.

17-METER YAGIS

Fig 16 describes the electrical performance of six optimized 17-meter Yagis with boom lengths between 6 to a heroic 60 feet. As usual, the end of each boom includes 3 inches of space for the reflector and last director (or driven element) mounting plates. Fig 16A shows the free-space gain versus frequency for each an-

Table 5

Optimized 20-Meter Yagi Designs

Two-element 20-meter Yagi, 8 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		220-08H.YW	220-08M.YW
Reflector	0.000"	66.000"	80.000"
Driven Element	90.000"	46.000"	59.000"

Three-element 20-meter Yagi, 16 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		320-16H.YW	320-16M.YW
Reflector	0.000"	69.625"	81.625"
Driven Element	80.000"	51.250"	64.500"
Director 1	106.000"	42.625"	56.375"
Compensator	12" behind Dir. 1	33.375"	38.250"

Four-element 20-meter Yagi, 26 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		420-26H.YW	420-26M.YW
Reflector	0.000"	65.625"	78.000"
Driven Element	72.000"	53.375"	65.375"
Director 1	60.000"	51.750"	63.875"
Director 2	174.000"	38.625"	51.500"
Compensator	12" behind Dir. 2	54.250"	44.250"

Five-element 20-meter Yagi, 34 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		520-34H.YW	520-34M.YW
Reflector	0.000"	68.625"	80.750"
Driven Element	72.000"	52.250"	65.500"
Director 1	71.000"	45.875"	59.375"
Director 2	68.000"	45.875"	59.375"
Director 3	191.000"	37.000"	51.000"
Compensator	12" behind Dir. 3	69.250"	56.250"

Five-element 20-meter Yagi, 40 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		520-40H.YW	520-40M.YW
Reflector	0.000"	68.375"	80.500"
Driven Element	72.000"	53.500"	66.625"
Director 1	72.000"	51.500"	64.625"
Director 2	139.000"	48.375"	61.750"
Director 3	191.000"	38.000"	52.000"
Compensator	12" behind Dir. 3	69.750"	56.750"

Five-element 20-meter Yagi, 48 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		520-48H.YW	520-48M.YW
Reflector	0.000"	66.250"	78.500"
Driven Element	72.000"	53.000"	66.000"
Director 1	88.000"	50.500"	63.750"
Director 2	199.000"	47.375"	60.875"
Director 3	211.000"	39.750"	53.625"
Compensator	12" behind Dir. 3	70.325"	57.325"

Six-element 20-meter Yagi, 60 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		620-60H.YW	620-60M.YW
Reflector	0.000"	67.000"	79.250"
Driven Element	84.000"	51.500"	65.000"
Director 1	91.000"	45.125"	58.750"
Director 2	130.000"	41.375"	55.125"
Director 3	210.000"	46.875"	60.375"
Director 4	199.000"	39.125"	53.000"
Compensator	12" behind Dir. 4	72.875"	59.250"

Six-element 20-meter Yagi, 80 foot boom

Element	*Spacing*	*Heavy-Duty Tip*	*Medium-Duty Tip*
File Name		620-80H.YW	620-80M.YW
Reflector	0.000"	66.125"	78.375"
Driven Element	72.000"	52.375"	65.500"
Director 1	122.000"	49.125"	62.500"
Director 2	229.000"	44.500"	58.125"
Director 3	291.000"	42.625"	56.375"
Director 4	240.000"	38.750"	52.625"
Compensator	12" behind Dir. 4	78.750"	64.125"

These 20-meter Yagi designs are optimized for > 20 dB F/R, and SWR < 2:1 over entire frequency range from 14.000 to 14.350 MHz, for heavy-duty elements (122 mph wind survival) and for medium-duty (82 mph wind survival). Only element tip dimensions are shown. See Fig 17 for element telescoping tubing schedule. All dimensions are in inches. Torque compensator element is made of 2.5" OD PVC water pipe placed 12" behind last director, and dimensions shown for compensators is one-half of total length, centered on boom.







Fig 18—Gain, F/R and SWR performance versus frequency for optimized 30-meter Yagis. At A, gain versus frequency is shown for three 30-meter Yagis whose booms range from 15 feet to 34 feet long, and which have been optimized for better than 10 dB F/R and less than 2:1 SWR over the frequency range 10.1 to 10.15 MHz. At B, front-to-rear ratio for these antennas is shown versus frequency, and at C, SWR over the frequency range is shown. At D, the taper schedule is shown for heavy-duty 30-meter elements, which can withstand 107-mph winds without icing, and 93-mph winds with ¼-inch radial ice. Except for the 2¼-inch and 2-inch sections, which have 0.083 inch thick walls, the wall thickness for the other telescoping sections of 6061-T6 aluminum tubing is 0.058 inches, and the overlap at the 1 inch telescoping junction with the ⅞-inch section is complete. The 2-inch section utilizes two machined aluminum reducers to accommodate the 1-inch tubing.

tenna; 16B shows the worst-case front-to-rear ratio, and 16C shows the SWR versus frequency. Each antenna with three or more elements was designed to cover the narrow 17-meter band from 18.068 to 18.168 MHz, with SWR less than 2:1 and F/R ratio better than 20 dB over that range.

Fig 16D shows the taper schedule for two types of 17-meter elements. The heavy-duty design can survive 123-mph winds with no icing, and 83-mph winds with ¼-inch of radial ice. The medium-duty design can handle 83-mph winds with no icing, and 59-mph winds with ¼ inch of radial ice.

The element-to-boom mounting plate for these Yagis is a 0.375-inch thick flat aluminum plate, 6 inches wide by 8 inches long. Electrically, each mounting plate is equivalent to a cylinder, with an effective diameter of 3.5122 inches for the heavy-duty element, and 3.3299 inches for the medium-duty element. The equivalent length on each side of the boom is 4 inches. As usual, the torque compensator is mounted 12 inches behind the last director.

20-METER YAGIS

Fig 17 describes the electrical performance of eight optimized 20-meter Yagis with boom lengths between 8 to a giant 80 feet. As usual, the end of each boom includes 3 inches of space for the reflector and last director (driven element) mounting plates. Fig 17A shows the free-space gain versus frequency for each antenna; 17B shows the front-to-rear ratio, and 17C shows the SWR versus frequency. Each antenna with three or more ele-



(A) (B)



(C)



(D)

Fig 19—Gain, F/R and SWR performance versus frequency for optimized 40-meter Yagis. At A, gain versus frequency is shown for three 40-meter Yagis whose booms range from 20 feet to 48 feet long, and which have been optimized for better than 10 dB F/R and less than 2:1 SWR over the frequency range 7.0 to 7.2 MHz. At B, front-to-rear ratio for these antennas is shown versus frequency, and at C, SWR over the frequency range is shown. At D, the taper schedule is shown for heavy-duty 40-meter elements, which can withstand 107-mph winds without icing, and 93-mph winds with $^1/_4$-inch radial ice. Except for the $2^1/_4$-inch and 2-inch sections, which have 0.083 inch thick walls, the wall thickness for the other telescoping sections of 6061-T6 aluminum tubing is 0.058 inches, and the overlap at the end telescoping junction is 3 inches. The 2-inch section utilizes two machined aluminum reducers to accommodate the 1-inch tubing.

ments was designed to cover the complete 20-meter band from 14.000 to 14.350 MHz, with SWR less than 2:1 and F/R ratio better than 20 dB over that range.

Fig 17D shows the taper schedule for two types of 20-meter elements. The heavy-duty design can survive 122-mph winds with no icing, and 89-mph winds with $^1/_4$ inch of radial ice. The medium-duty design can handle 82-mph winds with no icing, and 60-mph winds with $^1/_4$ inch of radial ice. The element-to-boom mounting plate for these Yagis is a 0.375-inch thick flat aluminum plate, 6 inches wide by 8 inches long. Electrically, each mounting plate is equivalent to a cylinder, with an effective diameter of 3.7063 inches for the heavy-duty element, and 3.4194 inches for the medium-duty element. The equivalent length on each side of the boom is 4 inches. As usual, the torque compensator is mounted 12 inches behind the last director.

30-METER YAGIS

Fig 18 describes the electrical performance of three

Table 6
Optimized 30-Meter Yagi Designs

Two-element 30-meter Yagi, 15 foot boom

Element	*Spacing*	*Heavy-Duty Tip*
File Name		230-15H.YW
Reflector	0.000"	50.250"
Driven Element	174.000"	14.875"

3-element 30-meter Yagi, 22 foot boom

Element	*Spacing*	*Heavy-Duty Tip*
File Name		330-22H.YW
Reflector	0.000	59.375
Driven Element	135.000	35.000
Director 1	123.000	19.625

Three-element 30-meter Yagi, 34 foot boom

Element	*Spacing*	*Heavy-Duty Tip*
File Name		330-34H.YW
Reflector	0.000"	53.750"
Driven Element	212"	29.000"
Director 1	190"	14.500"

These 30-m Yagi designs are optimized for > 10 dB F/R, and SWR < 2:1 over entire frequency range from 10.100 to 10.150 MHz for heavy-duty elements (105 mph wind survival). Only element tip dimensions are shown. See Fig 18D for element telescoping tubing schedule. All dimensions are in inches. No torque compensator element is required.

Table 7
Optimized 40-Meter Yagi Designs

Two-element 40-meter Yagi, 20 foot boom

Element	*Spacing*	*Heavy-Duty Tip*
File Name		240-20H.YW
Reflector	0.000"	85.000"
Driven Element	234.000"	35.000"

Three-element 40-meter Yagi, 32 foot boom

Element	*Spacing*	*Heavy-Duty Tip*
File Name		340-32H.YW
Reflector	0.000"	90.750"
Driven Element	196.000"	55.875"
Director 1	182.000"	33.875"

Three-element 40-meter Yagi, 48 foot boom

Element	*Spacing*	*Heavy-Duty Tip*
File Name		340-48H.YW
Reflector	0.000"	81.000"
Driven Element	300.000"	45.000"
Director 1	270.000"	21.000"

These 40-m Yagi designs are optimized for > 10 dB F/R, and SWR < 2:1 over low-end of frequency range from 7.000 to 7.200 MHz, for heavy-duty elements (95 mph wind survival). Only element tip dimensions are shown. See Fig 19D for element telescoping tubing schedule. All dimensions are in inches. No wind torque compensator is required.

optimized 30-meter Yagis with boom lengths between 15 to 34 feet. Because of the size and weight of the elements alone for Yagis on this band, only 2-element and 3-element designs are described. The front-to-rear ratio requirement for the 2-element antenna is relaxed to be greater than 10 dB over the band from 10.100 to 10.150 MHz, while that for the 3-element designs is kept at greater than 20 dB over that frequency range.

As usual, the end of each boom includes 3 inches of space for the reflector and last director mounting plates. Fig 18A shows the free-space gain versus frequency for each antenna; 18B shows the worst-case front-to-rear ratio, and 18C shows the SWR versus frequency.

Fig 18D shows the taper schedule for the 30-meter elements. Note that the wall thickness of the first two sections of tubing is 0.083 inches, rather than 0.058 inches. This heavy-duty element design can survive 107-mph winds with no icing, and 93-mph winds with $^{1}/_{4}$ inch of radial ice. The element-to-boom mounting plate for these Yagis is a 0.500-inch thick flat aluminum plate, 6 inches wide by 24 inches long. Electrically, each mounting plate is equivalent to a cylinder, with an effective diameter of 4.684 inches. The equivalent length on each side of the boom is 12 inches. These designs require no torque compensator.

40-METER YAGIS

Fig 19 describes the electrical performance of three optimized 40-meter Yagis with boom lengths between 20 to 48 feet. Like the 30-meter antennas, because of the size and weight of the elements for a 40-meter Yagi, only 2-element and 3-element designs are described. The front-to-rear ratio requirement for the 2-element antenna is relaxed to be greater than 10 dB over the band from 7.000 to 7.300 MHz, while the goal for the 3-element designs is 20 dB over the frequency range of 7.000 to 7.200 MHz. It is exceedingly difficult to hold the F/R greater than 20 dB over the entire 40-meter band without sacrificing excessive gain with a 3-element design.

As usual, the end of each boom includes 3 inches of space for the reflector and last director mounting plates. Fig 19A shows the free-space gain versus frequency for each antenna; 19B shows the front-to- rear ratio, and 19C shows the SWR versus frequency.

Fig 19D shows the taper schedule for the 40-meter elements. Note that the wall thickness of the first two sections of tubing is 0.083 inches, rather than 0.058 inches. This element design can survive 93-mph winds with no icing, and 69-mph winds with $^{1}/_{4}$ inch of radial ice. The element-to-boom mounting plate for these Yagis is a 0.500-inch thick flat aluminum plate, 6 inches wide by 24 inches long. Electrically each mounting plate is equivalent to a cylinder, with an effective diameter of 4.684 inches. The equivalent length on each side of the boom is 12 inches. These designs require no torque compensator.

Modifying Monoband Hy-Gain Yagis

Enterprising amateurs have long used the Telex Communications Hy-Gain “Long John” series of HF monobanders as a source of top-quality aluminum and hardware for customized Yagis. Often-modified older models include the 105BA for 10 meters, the 155BA for 15 meters, and the 204BA and 205BA for 20 meters. Newer Hy-Gain designs, the 105CA, 155CA and 205CA, have been redesigned by computer for better performance.

Hy-Gain antennas have historically had an excellent reputation for superior mechanical design, and Hy-Gain proudly points out that many of their monobanders are still working after more than 30 years. In the older designs the elements were purposely spaced along the boom to achieve good weight balance at the mast-to-boom bracket, with electrical performance as a secondary goal. Thus, the electrical performance was not necessarily optimum, particularly over an entire amateur band. Newer Hy-Gain designs are electrically superior to the older ones, but because of their strong concern for weight-balance are still not optimal by the definitions used in this chapter.



Fig 20—Gain, F/R and SWR over the 28.0 to 28.8 MHz range for original and optimized Yagis using Hy-Gain hardware. Original 105BA design provided excellent weight balance at boom-to-mast bracket, but compromised the electrical performance somewhat because of non-optimum spacing of elements. Optimized design requires wind torque-balancing compensator element, and compensating weight at director end of boom to rebalance weight. The F/R ratio over the frequency range for the optimized design is more than 23 dB. Each element uses the original Hy-Gain taper schedule and element-to-boom clamp, but the length of the tip is changed per Table 8.



Fig 21—Gain, F/R and SWR over the 21.0 to 21.45 MHz band for original and optimized Yagis using Hy-Gain hardware. Original 155BA design provided excellent weight balance at boom-to-mast bracket, but compromised the electrical performance somewhat because of non-optimum spacing of elements. Optimized design requires wind torque-balancing compensator element, and compensating weight at director end of boom to rebalance weight. The F/R ratio over the frequency range for the optimized design is more than 22 dB. Each element uses the original Hy-Gain taper schedule and element-to-boom clamp, but the length of the tip is changed per Table 9.

Table 8

Optimized Hy-Gain 20-Meter Yagi Designs

Optimized 204BA, Four-element 20-meter Yagi, 26 foot boom

Element	*Spacing*	*Element Tip*
File Name		BV204CA.YW
Reflector	0.000"	56.000"
Driven Element	85.000"	52.000"
Director 1	72.000"	61.500"
Director 2	149.000"	50.125"

Optimized 205CA, Five-element 20-meter Yagi, 34 foot boom

Element	*Spacing*	*Element Tip*
File Name		BV205CA.YW
Reflector	0.000"	62.625"
Driven Element	72.000"	53.500"
Director 1	72.000"	63.875"
Director 2	74.000"	61.625"
Director 3	190.000"	55.000"

Table 9

Optimized Hy-Gain 15-Meter Yagi Designs

Optimized 155BA, Five-element 15-meter Yagi, 24 foot boom

Element	*Spacing*	*Element Tip*
File Name		BV155CA.YW
Reflector	0.000"	64.000"
Driven Element	48.000"	65.500"
Director 1	48.000"	63.875"
Director 2	82.750"	61.625"
Director 3	127.250"	55.000"



Fig 22—Gain, F/R and SWR over the 14.0 to 14.35 MHz band for original and optimized Yagis using Hy-Gain hardware. Original 205BA design provided good weight balance at boom-to-mast bracket, but compromised the electrical performance because of non-optimum spacing of elements. Optimized design requires wind torque-balancing compensator element, and compensating weight at director end of boom to rebalance weight. The F/R ratio over the frequency range for the optimized design is more than 23 dB, while the original design never went beyond 17 dB of F/R. Each element uses the original Hy-Gain taper schedule and element-to-boom clamp, but the length of the tip is changed per Table 10.

Table 10

Optimized Hy-Gain 10-Meter Yagi Designs

Optimized 105BA, Five-element 10-meter Yagi, 24 foot boom

Element	*Spacing, inches*	*Element Tip*
File Name		BV105CA.YW
Reflector	0.000"	44.250"
Driven Element	40.000"	53.625"
Director 1	40.000"	52.500"
Director 2	89.500"	50.500"
Director 3	112.250"	44.750"

With the addition of wind torque-compensation dummy elements, and with extra lead weights, where necessary, at the director end of the boom for weight-balance, the electrical performance can be enhanced, using the same proven mechanical parts.

Fig 20 shows the computed gain, F/R ratio and SWR for a 24-foot boom, 10-meter optimized Yagi (modified 105BA) using Hy-Gain hardware. **Fig 21** shows the same for a 26-foot boom 15-meter Yagi (modified 155BA), and **Fig 22** shows the same for a 34-foot boom (modified 205BA) 20-meter Yagi. **Tables 8** through **10** show dimensions for these designs. The original Hy-Gain taper schedule is used for each element. Only the length of the end tip (and the spacing along the boom) is changed for each element.

Multiband Yagis

So far, this chapter has discussed monoband Yagis—that is, Yagis designed for a single Amateur-Radio frequency band. Because hams have operating privileges on more than one band, multiband coverage has always been very desirable.

INTERLACING ELEMENTS

In the late 1940s, some experimenters tried interlacing Yagi elements for different frequencies on a single boom, mainly to cover the 10 and 20-meter bands (at that time the 15-meter band wasn't yet available to hams). The experimenters discovered, to their considerable chagrin, that the mutual interactions between different elements tuned to different frequencies are very difficult to handle.

Adjusting a lower-frequency element usually results in interaction with higher-frequency elements near it. In effect, the lower-frequency element acts like a retrograde reflector, throwing off the effectiveness of the higher-frequency directors nearby. Element lengths and the spacing between elements can be changed to improve performance of the higher-frequency Yagi, but the resulting compromise is rarely equal to that of an optimized monoband Yagi. A reasonable compromise for portable operation may be found in Chapter 15, Portable Antennas, by VE7CA.

TRAPPED MULTIBANDERS

Multiband Yagis using a single boom can also be made using traps. Traps allow an element to have multiple resonances. See Chapter 7, Multiband Antennas, for details on trap designs. Commercial vendors have sold trapped antennas to hams since the 1950s and surveys show that after simple wire dipoles and multiband verticals, trapped triband Yagis are the most popular antennas in the Amateur Radio service.

The originator of the trapped tribander was Chester Buchanan, W3DZZ, in his Mar 1955 *QST* article, "The Multimatch Antenna System." On 10 meters this rather unusual tribander used two reflectors (one dedicated and one with traps) and two directors (one dedicated and one with traps). On 20 and 15 meters three of the five elements were active using traps. The W3DZZ tribander employed 12 traps overall, made with heavy wire and concentric tubular capacitors to hold down losses in the traps. Each trap was individually fine tuned after construction before mounting it on an element.

Another example of a homemade tribander was the 26-foot boom 7-element 20/15/10-meter design described by Bob Myers, W1XT (ex-W1FBY) in Dec 1970 *QST*. The W1FBY tribander used only two sets of traps in the driven element, with dedicated reflectors and directors for each frequency band. Again, the traps were quite robust in this design to minimize trap losses, using $^7/_{16}$-inch aluminum tubing for the coils and short pieces of RG-8 coax as high-voltage tuning capacitors.

Only a relatively few hams actually built tribanders for themselves, mainly because of the mechanical complexity and the close tolerances required for such antennas. The traps themselves must be constructed quite accurately for reproducible results, and they must be carefully weatherproofed for long life in rain, snow, and often polluted or corrosive atmospheres.

Christmas Tree Stacks

Another possible method for achieving multiband coverage using monoband Yagis is to stack them in a "Christmas tree" arrangement. See **Fig 23**. For an installation covering 20, 15 and 10 meters, you could mount on the rotating mast just at the top of the tower the 20-meter monobander. Then perhaps 9 feet above that you would mount the 15-meter monobander, followed by the 10-meter monoband Yagi 7 feet further up on the mast. Another configuration would be to place the 10-meter Yagi in between the lower 20-meter and upper 15-meter Yagis. Whatever the arrangement, the antenna in the middle of such a Christmas-tree always suffers the most interaction from the lowest-frequency Yagi.

Dave Leeson, W6NL (ex-W6QHS), mentions that the 10-meter Yagi in his closely stacked Christmas Tree (15 meters at the top, 10 meters in the middle, and 20 meters at the bottom of the rotating mast) loses "substantial gain" because of serious interaction with the 20-meter antenna. (N6BV and K1VR calculated that the free-space gain in the W6NL stack drops to 5 dBi, compared to about 9 dBi with no surrounding antennas.) Monobanders are *definitely not* universally superior to tribanders in multiband installations. In private conversations, W6NL has indicated that he would not repeat this kind of short Christmas Tree installation again.

Forward Staggering

Some hams have built multiband Yagis on a common boom, using a technique called *forward staggering*. This means that that most (or all) of the higher-frequency elements are placed in front of any lower-frequency elements—in other words, most of the elements are not interlaced. Richard Fenwick, K5RR, described his triband Yagi design in Sep 1996 *QEX* magazine. This uses forward-stagger and open-sleeve design techniques and was optimized using several sophisticated modeling programs.

Fenwick's tribander used a 57-foot, 3-inch OD boom to hold 4 elements on 20 meters, 4 elements on 15 meters and 5 elements on 10 meters. **Fig 24** shows the element placement for the K5RR tribander. Most hams, of course, don't have the real-estate or the large rotator needed to turn such a large, but elegant solution to the interaction problem!



Fig 23—"Christmas Tree" stack of 20/15/10-meter Yagis spaced vertically on a single rotating mast.

Force 12 C3 "Multi-Monoband" Triband Yagi

Antenna manufacturer Force 12 also uses forward-stagger layouts and patented combinations of open- and closed-sleeve drive techniques extensively in their product line of multiband antennas, which they call "multi-monoband Yagis." **Fig 25** shows the layout for the popular Force 12 C3 triband Yagi. The C3 uses no traps, thereby avoiding any losses due to traps. The C3 consists of three 2-element Yagis on an 18-foot boom, using full-sized elements designed to withstand high winds.

The C3 feed system employs open-sleeves, where the 20-meter driver element is fed with coax through a common-mode current balun and parasitically couples to the closely spaced 15-meter driver and the two 10-meter drivers to yield a feed-point impedances close to 50 Ω on all three bands. See the section on open-sleeve dipoles in Chapter 7, Multiband Antennas.

Note the use of the forward-stagger technique in the C3, especially on 10 meters. To reduce interaction with


20 R
20 DE
20 D1
20 D2
15 R
15 DE
15 D1
10 R
10 DE
10 D1a
15 D2
10 D1b
10 D2
207 Half-Length in Inches
194.75
192.3
137.85
128.0
129.1
103.8
180.7
97
97.25
121.35
97.25
88
0
84
216
240
310
420
444
468
492
538
566
552
878
Distance from 20 M Reflector in Inches

Fig 24—Dimensions of K5RR's trapless tribander using "forward stagger" and open-sleeve techniques to manage interaction between elements for different frequencies.


10m Driver 1
10m Dir.
15m Refl
15m Driver
10m Driver 2
20m Refl
20m Driver

Fig 25—Layout of Force 12 C3 multiband Yagi. Note that the 10-meter (driver/director) portion of the antenna is "forward staggered" ahead of the 15-meter (reflector/driver) portion, which in turn is placed ahead of the 20-meter (reflector/driver) portion. The antenna is fed at the 20-meter driver, which couples parasitically to the 15-meter driver and the two 10-meter drivers.

the lower-frequency elements behind it, the 10-meter portion of the C3 is mounted on the boom ahead of all the lower-frequency elements, with the main 10-meter parasitic element (#7) acting as a director. The lower-frequency elements behind the 10-meter section act as retrograde reflectors, gaining some improvement of the gain and pattern compared to a monoband 2-element Yagi. A simplified *EZNEC* model of the C3 is included on the CD-ROM accompanying this book.

On 15 meters, the main parasitic element (#2) is a dedicated reflector, but the other elements ahead on the boom act like retrograde directors to improve the gain and pattern somewhat over a typical 2-element Yagi with a reflector. On 20 meters, the C3 is a 2-element Yagi with a dedicated reflector (#1) at the back end of the boom.

The exact implementation of any Yagi, of course, depends on the way the elements are constructed using telescoping aluminum tubing. The C3 type of design is no exception.

Stacked Yagis

Monoband parasitic arrays are commonly stacked either in broadside or collinear fashion to produce additional directivity and gain. In HF amateur work, the most common broadside stack is a vertical stack of identical Yagis on a single tower. This arrangement is commonly called a *vertical stack*. At VHF and UHF, amateurs often employ collinear stacks, where identical Yagis are stacked side-by-side at the same height. This arrangement is called a *horizontal stack*, and is not usually found at HF, because of the severe mechanical difficulties involved with large, rotatable side-by-side arrays.

Fig 26 illustrates the two different stacking arrangements. In either case, the individual Yagis making up the stack are generally fed in phase. There are times, however, when individual antennas in a stacked array are purposely fed out of phase in order to emphasize a particular elevation pattern. See Chapter 17, Repeater Antenna Systems, for such a case where elevation pattern steering is implemented for a repeater station.

Let's look at the reasons hams stack Yagis:

- For more gain
- For a wider elevation footprint in a target geographical area
- For azimuthal diversity—two or more directions at once
- For less fading
- For less precipitation static

STACKS AND GAIN

Fig 27 compares the elevation responses for three antenna systems of 4-element 15-meter Yagis. The response for the single Yagi at a height of 120 feet peaks at an elevation of about 5°, with a second peak at 17° and a third at 29°. When operated by itself, the 60-foot high Yagi has its first peak at about 11° and its second peak beyond 34°.

The basic principle of a vertically stacked HF array is that it takes energy from higher-angle lobes and concentrates that energy into the main elevation lobe. The main lobe of the 120/60-foot stack peaks about 7° and is about 2 dB stronger than either the 60- or 120-foot antenna by itself. The shape of the left-hand side of the stack's main lobe is determined mainly by the 120-foot antenna's response. The right-hand side of the stack's main lobe is "stretched" rightwards (toward higher angles) mainly by the 60-foot Yagi, while the shape follows the curve of the 120-foot Yagi.

Look at the second and third lobes of the stack, which appear about 18° and 27°. These are about 14 dB down from the stack's peak gain, showing that energy has indeed been extracted from them. By contrast, look at the levels of the second and third lobes for the individual Yagis at 60 and 120 feet. These higher-angle lobes are almost as strong as the first lobes.



Fig 26—Stacking arrangements. At A, two Yagis are stacked vertically (broadside) on the same mast. At B, two Yagis are stacked horizontally (collinear) side-by-side. At HF the vertical stack is more common because of mechanical difficulties involved with large HF antennas stacked side-by-side, whereas at VHF and UHF the horizontal stack is common.

The stack squeezes higher-angle energy into its main elevation lobe, while maintaining the frontal lobe azimuth pattern of a single Yagi. This is the reason why many state-of-the-art contest stations are stacking arrays of relatively short-boom antennas, rather than stacking long-boom, higher-gain Yagis. A long-boom HF Yagi narrows the azimuthal pattern (and the elevation pattern too), making pointing the antenna more critical and making it more difficult to spread a signal over a wide azimuthal area, such as all of Europe and Asiatic Russia at one time.

STACKS AND WIDE ELEVATION FOOTPRINTS

Detailed studies using sophisticated computer models of the ionosphere have revealed that coverage



Fig 27—Comparison of elevation patterns on 15 meters for a stack of 4-element Yagis at 120 and 60 feet and individual Yagis at those two heights. The shape of the stack's response is determined mainly by that of the top antenna.



Fig 28—Comparison of elevation patterns and elevation-angle statistics for individual 10-meter TH7DX tribanders mounted over flat ground aiming from New England to Europe. No single antenna can cover the wide range of angles needed—from 1° to 18°.

of a wide range of elevation angles is necessary to ensure consistent DX or contest coverage on the HF bands. These studies have been conducted over all phases of the 11-year solar cycle, and for numerous transmitting and receiving QTHs throughout the world.

Chapter 23, Radio Wave Propagation, covers these studies in more detail, and the CD-ROM accompanying this book contains a huge number of elevation-angle statistical tables for locations all around the world. The *HFTA* (HF Terrain Assessment) program on the CD-ROM can not only compute antenna elevation patterns over irregular local terrain, but it can compare them directly to the elevation-angle statistics for a particular target geographic area.

A 10-Meter Example

Fig 28 shows the 10-meter elevation-angle statistics for the New England path from Boston, Massachusetts, to all of the continent of Europe. The statistics are overlaid with the computed elevation response for three individual 4-element Yagis, at three heights: 90, 60 and 30 feet above flat ground. In terms of wavelength, these heights are 2.60 λ, 1.73 λ and 0.86 λ high.

You can see that the 90-foot high Yagi covers the lower elevation angles best, but it has a large null in its response centered at about 11°. This null puts a big hole in the coverage for some 22% of all the times the 10-meter band is open to Europe. At those angles where the 90-foot Yagi exhibits a null, the 60-foot Yagi would be effective, and so would the 30-foot Yagi. If that is the only antenna you have, the 90-foot high Yagi would be too high for good coverage of Europe from New England.

The peak statistical elevation angle into Europe is 5°, and this occurs about 11% of all the times the 10-meter band is open to Europe from Boston. At an elevation of 5° the 30-foot high Yagi would be down almost 7 dB compared to the 90-foot high Yagi, but at 11° the 90-foot Yagi would be more than 22 dB down from the 30-foot Yagi. There is no single height at which one Yagi can optimally cover all the necessary elevation angles, especially to a large geographic area such as Europe—although the 60-foot high antenna is arguably the best compromise for a single height. To cover all the possibilities to Europe, however, you need a 10-meter antenna system that can cover equally well the entire range of elevation angles from 1° to 18°.

Fig 29 compares elevation-angle statistics for two 10-meter paths from New England to Europe and to Japan. The elevation angles needed for communications with the Far East are very low. Overlaid on Fig 29 for comparison are the elevation responses over flat ground for three different antenna systems, using identical 4-element Yagis:

- Three Yagis, stacked at 90, 60 and 30 feet
- Two Yagis, stacked at 70 and 40 feet
- One Yagi at 90 feet.

The best coverage of all the necessary angles on 10 meters to Europe is with the stack of three Yagis at 90/60/30 feet. The two-Yagi stack at 70 and 40 feet comes in a close second to Europe, and for elevation angles higher than about 9° the 70/40-foot stack is actually superior to the 90/60/30-foot stack.

Both of the stacks illustrated here give a wider *elevation footprint* than any single antenna, so that all the angles can be covered automatically without having to switch from higher to lower antennas manually. This is perhaps the major benefit of using stacks, but not the only



Fig 29—Combinations of 4-element Yagis over flat ground. The elevation-angle statistics into Japan from New England (Boston) are represented by the black vertical bars, while the grey vertical bars represent the elevation-angle statistics to Europe. The 90/60/30-foot stack has the best *elevation footprint* into Japan, although the 70/40-foot stack performs well also.

one, as we'll see.

To Japan, the necessary range of elevation angles is considerably smaller than that needed to a larger geographic target area like Europe. The 90/60/30-foot stack is still best on the basis of having higher gain at low angles, although the two-Yagi stack at 70 and 40 feet is a good choice too. Note that the single 90-foot high Yagi's performance is very close to the 70/40-foot stack of two Yagis at low angles, but the two-Yagi stack is superior to the single 90-foot antenna for angles higher than about 5° on 10 meters.

A 15-Meter Example

The situation is similar on 15 meters from New England to Europe. On 15 meters, the range of angles needed to fully cover Europe is 1° to 28°. This large range of angles makes covering all the angles even more challenging. Ken Wolff, K1EA, a devoted contest operator and the author of the famous *CT* contest logging program, put it very clearly when he wrote in the bulletin for the Yankee Clipper Contest Club:

"Suppose you have 15-meter Yagis at 120 feet and 60 feet, but can feed only one at a time. A 15-meter beam at 120 feet has its first maximum at roughly 5° and the first minimum at 10°. The Yagi at 60 feet has a maximum at 10° and a minimum at 2°. At daybreak, the band is just opening, signals are arriving at 3° or less and the high Yagi outperforms the low one by 5-10 dB. Late in the morning, western Europeans are arriving at angles of 10° or more, while UA6 is still arriving at 4-5°. Western Europe can be 20-30 dB louder on the low antenna than the high! What to do? Stack em!"



Fig 30—Comparison of elevation patterns for K1EA's illustration about 15-meter Yagis mounted over flat ground, with elevation-angle statistics to Europe added. The stack at 120 and 60 feet yields a better footprint over the range of 3° to 11° at its half-power points, better than either antenna by itself.

Fig 30 illustrates K1EA's scenario, showing the elevation statistics to Europe from Massachusetts and the elevation responses for a 120- and a 60-foot high, 4-element Yagi, both over flat ground, together with the response for both antennas operated as vertical stack. The half-power beamwidth of the stack's main lobe is 6.9°, while that for the 120-foot antenna by itself is 5.5° and that for the 60-foot antenna by itself is 11.1°. The half-power beamwidth numbers by themselves can be deceiving, mainly because the stack starts out with a higher gain. A more meaningful observation is that the stack has equal to or more gain than either of the two individual antennas from 1° to about 10°.

Is such a stack of 15-meter Yagis at 120 and 60 feet optimal for the New England to Europe path? No, it isn't, as we'll explore later, but the stack is clearly better than either antenna by itself for the scenario K1EA outlined above.

A 20-Meter Example

Take a look now at **Fig 31**, which overlays elevation-angle statistics for Europe (gray vertical bars) and Japan (black vertical bars) from Boston on 20 meters, plus the elevation responses for four different sets of antennas mounted over flat ground. Just for emphasis, the highest antenna is a 200-foot high 4-Element Yagi. It is clearly too high for complete coverage of all the needed angles into Europe. A number of New England operators have verified that this is true—a really high Yagi will open the 20-meter band to Europe in the morning and may shut it down in the afternoon, but during the middle of the day the high antenna gets soundly beaten by lower antennas.

To Japan, however, from New England the range of angles needed narrows considerably on 20 meters,



Fig 31—Comparison of elevation patterns for individual 20-meter Yagis over flat ground, compared with the range of elevation angles needed on this band from New England to Europe (gray bars) and to Japan (black bars). For fun, the response of a 200-foot high Yagi is included—this antenna is far too high to cover the needed range of angles to Europe because of its deep nulls at critical angles, like 10°. But the 200 footer is great into Japan!

from 1° to only 11°. For these angles, the 200-foot Yagi is the best antenna to work Japan from New England on 20 meters.

This is true provided that the antenna is aiming out over flat ground. The actual, generally irregular, terrain in various directions can profoundly modify the takeoff angles favored by an antenna system, particularly on steep hills. There will be more discussion on this important topic later on.

SPARE ME THE NULLS!

Now, let's look closely at some other 20-meter antennas in Fig 28, the ones at 120 and 60 feet. At an elevation angle of 8° the difference in elevation response between the 60- and 120-foot high Yagis is just over 3 dB. Can you really notice a change of 3 dB on the air? Signals on the HF bands often rise and fall quickly due to fading, so differences of 2 or 3 dB are difficult to discern. Consequently, the difference between a Yagi at 120 feet and one at 60 feet may be difficult to detect at elevation angles covered well by both antennas. But a *deep null* in the elevation response is very noticeable.

Back in 1990, when editor Dean Straw, N6BV, put up his 120-foot tower in Windham, New Hampshire, his first operational antenna was a 5-element triband Yagi, with 3 elements on 40 and 4 elements on both 20 and 15 meters. Just as the sun was going down on a late August day Straw finished connecting the feed line in the shack. The antenna seemed to be playing like it should, with a good SWR curve and a good pattern when it was rotated. So N6BV/1 called a nearby friend, John Dorr, K1AR, on the telephone and asked him to get on the air to make some signal comparisons on 20 meters into Europe.

Straw was shocked that every European they worked that evening said his signal was several S units weaker than K1AR's. Dorr was using a 4-element 20-meter monobander at 90 feet, which at first glance should have been comparable to Straw's 4-element antenna at 120 feet. But N6BV really shouldn't have been so shocked—in New England, the elevation angles from Europe late in the day on 20 meters are almost always higher than 11°, and that is true for the entire solar cycle.

The N6BV/1 station was located on a small hill, while K1AR was located on flat terrain towards Europe. The elevation response for N6BV/1's 120-foot high Yagi fell right into a deep null at 11°. This was later confirmed many times in the following eight years that the N6BV/1 station was operational. During the early morning opening on 20 meters into Europe, the top antenna was always very close to or equal to the stack of three TH7DX tribanders at 90/60/30 feet on the same tower. But in the afternoon the top antenna was *always* decidedly worse than the stack, so much so that Straw often wondered whether something had gone wrong with the top antenna!

So what's the moral to this short tale? It's simple: *The gain you can achieve, while useful, is not so important as the deep nulls you can avoid by using a stack.*

STACKING DISTANCES BETWEEN YAGIS

So far, we've examined stacks as a means of achieving more gain over an individual Yagi, while also matching the antenna system's response to the range of elevation angles needed for particular propagation paths. Most importantly, we seek to avoid nulls in the elevation response. Earlier we asked whether a 120/60-foot stack was optimal for the path from New England to Europe on 15 meters. Let's examine how the stacking distance between individual antennas affects the performance of a stack.

Fig 32 shows overlays of various combinations of 15-meter Yagis. Just for reference, a plot for a single 60-foot high Yagi is also included. Let's start by looking at the most widely spaced stack in the group: the 120/30-foot stack. Here, the spacing is obviously too large, since the second lobe is actually stronger than the first lobe. In terms of wavelength, the 90-foot spacing between antennas in this stack is 1.94 λ, a large spacing indeed.

There is a great deal of folklore and superstition among amateurs about stacking distances for HF arrays. For years, high-performance stacked Yagi arrays have been used for weak-signal DXing on the VHF and UHF bands. The most extreme example of weak-signal work is EME work (Earth-Moon-Earth, also called *moonbounce*) because of the huge path losses incurred on the way to and from the Moon. The most successful arrays used for



Fig 32—Various stacks towards Europe from New England for 15-meters. The stack at 120 and 30 feet is clearly suboptimal, since the second lobe is higher than the first lobe. The 120/60-foot stack is better in this regard, but is still not as good a performer as the 90/60/30-foot stack. It's debatable whether going to four Yagis in the 120/90/60/30-foot stack is a good idea because it drops below the performance of the 90/60/30-foot stack at about 10° in elevation. The exact distance between practical HF Yagis is not critical to obtain the benefits of stacking. For a stack of tribanders at 90, 60 and 30 feet, the distance in wavelengths between individual antennas is 0.87 λ at 28.5 MHz, 0.65 λ at 21.2 MHz, and 0.43 λ at 14.2 MHz.

moonbounce have low sidelobe levels and very narrow frontal lobes that give huge amounts of gain. The low sidelobes help minimize received noise, since the receive levels for signals that do manage to bounce off the Moon and return to Earth are exceedingly weak.

But HF work is different from moonbounce in that rigorously trying to minimize high-angle lobes is far less crucial at HF, where we've already shown that the main goal is to achieve gain over a wide elevation-plane footprint without any disastrous nulls in the pattern. The gain gradually increases as spacing in terms of wavelength is increased between individual Yagis in a stack, and then decreases slowly once the spacing is greater than about 1.0 λ. The difference in gain between spacings of 0.5 λ to 1.0 λ for a stack of typical HF Yagis amounts to only a fraction of a decibel. Stacking distances on the order of 0.6 λ to 0.75 λ give best gain commensurate with good patterns.

While the stack at 120/60 feet in Fig 32 doesn't have the second-lobe-stronger problem the 120/30-foot stack has, 60 feet between antennas is 1.29 λ, again outside the normal range of HF stack spacings. As a consequence, the 120/60-foot stack doesn't cover the range of elevation angles as well as it could, and is inferior to both the 90/60/30-foot stack and the 120/90/60/30-foot stack. The 120/60-foot two-Yagi stack needs at least one more antenna placed in-between to spread out the elevation-range coverage and to provide more gain.

It could be debated, but the 90/60/30-foot stack seems optimal for coverage of all the angles into Europe from New England on 15 meters. Note that the 30-foot spacing between Yagis is 0.65 λ on 21.2 MHz, right in the middle of the range of typical stack spacings.

Switching Out Yagis in the Stack

Still, the extra gain that is available at low elevation angles from a 120/90/60/30-foot high, four-Yagi stack in Fig 32 is alluring. For those statistically possible, but less likely, occasions when the elevation angle is higher than about 12°, it would be advantageous to switch out the top 120-foot Yagi and operate with only the lower three Yagis in a stack. (This also allows the top antenna to be rotated in another direction, an aspect we'll explore later.) There are even times when the incoming angles are really high and when the top two antennas might be switched out to create a 60/30-foot stack. Later in this chapter we'll explore flexible circuitry for such stack switching.

Stacking Distance and Lobes at HF

Let's look a little more closely at how a stack achieves gain and a wide elevation footprint. **Fig 33** shows a rectangular X-Y graph of the elevation response from 0° to 180° for two 3-element 15-meter Yagis (with 12-foot booms) spaced 30 feet apart (0.65 λ at 21.2 MHz), but mounted at two different heights: 95/65 and 85/55 feet. The rectangular plot gives more resolution than is possible on a polar plot. Note that the heights shown represent typical stacking heights on 15 meters—there's nothing magic about these choices. The free-space H-Plane pattern for the 30-foot spaced stack is also shown for reference.

The worst-case overhead elevation lobe, which ranges from about 60° to 120° in elevation (±30° from straight overhead at 90°), is about 14.7 dB down for the 95/65-foot stack. The overhead lobe peaks broadly at an elevation angle of about 82°. The overhead lobe for the lower 85/55-foot stack occurs at an elevation of about 64°, where it is 19 dB down.

The F/B for both 3-element sets of heights is about 15 dB, well down from the excellent 32 dB F/B for each Yagi by itself. The degradation of F/B is mainly due to mutual coupling to its neighbor in the stack.

The ground-reflection pattern in effect "modulates" the free-space pattern of the individual Yagi, but in a complex and not always intuitive manner. This is quite evident for the 85/55-foot stack at near-overhead angles. In this region things become complicated indeed, because the fourth and fifth lobes due to ground reflections are interacting with the free-space pattern of the stack.

Because the spacing remains constant at 30 feet for



Fig 33—Rectangular plot comparing two 15-meter stacks of 3-element Yagis—each antenna is spaced 30 feet from its partner, but at different heights. The lobes are a complicated function of the antenna height, not the spacing, since that remains constant.



Fig 34—Four spacing scenarios for two 3-element 15-meter Yagis. Things get very complicated. The optimal spacing in terms of stacking gain is 30 feet, which is 0.65 λ. The near-overhead lobes turn out to be ugly looking, but unimportant for skywave propagation.

these pairs of antennas, however, the main determinant for the upper-elevation angle lobes is the distance of the horizontally polarized antennas above the ground, not the spacing between them.

Changing the Stack Spacing

Fig 34 demonstrates just how complicated things get for four different spacing scenarios. Here, the lower Yagi in the stack is moved down in 5-foot increments from the 95/70 feet level, to 95/65, 95/60 and 95/55 feet. The closest spacing, 25 feet in the 95/70-foot stack, yields nominally the "cleanest" pattern in the overhead region from 60° to 120°. The worst-case overhead lobe for the 95/70-foot stack is down 28 dB from peak. The F/B is again about 15 dB.

The worst case overhead lobe for the widest spacing, 40 feet in the 95/55-foot stack, is about 11 dB down from peak. The F/B has increased marginally, but is still only about 16 dB. It is difficult to pinpoint directly whether the spacing or the height above ground is the major determinant for the various lobe amplitudes for the 3-element stack. We'll soon look closely at whether the overhead lobe is important or not for HF work.

Longer Boom Length and Stack Spacing

Fig 35 shows the same type overlay of elevation plots, but this time for two 7-element 15-meter Yagis on gigantic 64-foot booms. These Yagis are also spaced 30 feet apart (0.65 λ at 21.2 MHz), mounted at the same four sets of heights in Fig 34. As you'd expect, the free-space elevation pattern for a stacked pair of 7-element Yagis on 64-foot booms is narrower than that for a stacked pair of 3-element Yagis on 12-foot booms. The intrinsic F/B of the longer Yagi is also better than the F/B of the shorter antenna. As a result, all lobes beyond the main lobe of the stacked 7-element pair are lower for both sets of heights than their 3-element counterparts. The worst-case overhead lobe for the 7-element 95/65-foot pair is about 22 dB down at 76° and the F/B at 172° is greater than 21 dB for all four sets of heights.



Fig 35—Four spacing scenarios for two large 7-element 15-meter Yagis (on 64-foot booms). Again, a 0.65 λ spacing (30 feet) provides the most stacking gain.

Table 11 summarizes the main performance characteristics for four sets of stacked Yagis. The first entry for each boom length is for the Yagi by itself at a height of 95 feet. Stacked configurations are next listed in order of gain. The column labeled "Worst lobe, dB re Peak" is the

Table 11
Example, Spacing Between 15–Meter Yagis

Antenna	*Peak Gain dBi*	*Worst Lobe dB re Peak*	*Worst Lobe Angle,°*	*F/B dB*	*Overhead Lobe dB re Peak*
3–Ele., 12' boom					
By itself 95'	13.2	–0.9	21	28.8	–17.5
95'/65' (Δ 30')	16.08	–4.5	25	14.9	–14.7
95'/60' (Δ 35')	16.01	–6.2	24	15.1	–10.9
95'/70' (Δ 25')	15.81	–3.2	24	14.8	–28
95'/55' (Δ 40')	15.71	–8.7	24	16.4	–11
95'/75' (Δ 20')	15.34	–2.3	23	16.3	–17.2
4–Ele., 18' boom					
By itself 95'	13.92	–1	21	28.3	–20.4
95'/65' (Δ 30')	16.63	–4.5	23	18.5	–17.3
95'/60' (Δ 35')	16.6	–6.2	24	18.2	–13.1
95'/55' (Δ 40')	16.36	–8.7	24	19.8	–13.2
95'/70' (Δ 25')	16.36	–3.3	24	20.4	–31.8
95'/75' (Δ 20')	15.92	–2.5	23	25.9	–19
5–Ele., 23' boom					
By itself 95'	14.26	–1.1	21	27.9	–22.3
95'/65' (Δ 30')	16.86	–4.6	24	20.8	–19
95'/60' (Δ 35')	16.86	–6.3	24	20.7	–14.4
95'/55' (Δ 40')	16.67	–8.8	24	23.5	–14.4
95'/70' (Δ 25')	16.59	–3.4	24	24.9	–34.4
95'/75' (Δ 20')	16.18	–2.6	23	34.3	–20.2
7–Ele., 64' boom					
By itself 95'	17.93	–2.2	21	28.9	–17.1
95'/65' (Δ 30')	19.39	–6.9	24.3	21.4	–21.9
95'/60' (Δ 35')	19.38	–8.6	24	21.4	–16.9
95'/55' (Δ 40')	19.29	–10.9	24	25.0	–18.6
95'/70' (Δ 25')	19.26	–5.5	23	24	–35.3
95'/75' (Δ 20')	19.08	–4.6	23	27	–23.4

amplitude of the second lobe due to ground reflections, and the elevation angle of that second lobe is listed as well.

Besides the 3- and 7-element designs discussed above, we've also added 4- and 5-element designs in Table 11. Over the range of stacking distances between 20 and 40 feet on 15 meters (0.43 λ to 0.86 λ), the peak gain for the 3-element stacks changes less than 0.75 dB, with the 30-foot spacing exhibiting the highest gain. The differences between peak gains versus stacking distance become smaller as the boom length increases. For example, for the 64-foot boom Yagi, the gain varies 19.39 – 19.08 = 0.31 dB for stack spacings from 20 to 40 feet.

In other words, changing the spacing from 20 to 40 feet (0.43 λ to 0.86 λ) doesn't change the gain significantly for boom lengths from 12 to 64 feet (0.26 λ to 1.38 λ). From the point of view of gain, the vertical spacing between individual antennas in an HF stack is not critical.

The worst-case lobes (generally speaking, the second lobe due to ground reflections) are highest for a Yagi operated by itself. After all, a single Yagi doesn't benefit from the redistribution of energy from higher-angle lobes into the main lobe that a stack gives. Thus, the 3-element, 12-foot boom Yagi by itself at 95 feet would have a second lobe at 21° that is only 0.9 dB down from the main lobe, while the stack of two such antennas at a 30-foot (0.65 λ) spacing at 95/65 feet would have a second lobe down 4.5 dB. As the spacing between antennas in a vertical stack increases, the second lobe is suppressed more, up to 8.7 dB at a 40-foot (0.86 λ) spacing.

Since the free-space elevation pattern for a 3-element Yagi is wider than that for a 7-element Yagi, the second lobe due to ground reflection will be somewhat reduced. This is true for all longer-boom antennas operating by themselves over ground. Used in stacks, the second lobe's amplitude will vary depending on spacing between antennas, but they range only about 6 dB.

The front-to-back ratio will also tend to increase with longer boom lengths on a properly designed Yagi. Table 11 shows that the F/B is somewhat better for closer spacings between antennas in a stack, a rather non-intuitive result, considering that the mutual coupling should be greater for closer antennas. For example, the 5-element Yagi stack with a 20-foot spacing has a exceptional F/B of 34.3 dB, compared to a F/B of 21.4 dB with the 30-foot spacing distance that gives nominally the most gain. High values of F/B, however, rarely hold over a wide frequency range because of the very critical phasing relationships necessary to get a deep null, so the difference between 34.3 and 21.4 dB would rarely be noticeable in practice.

The near-overhead lobe structure (between 60º to 120º in elevation) tends also to be lower for smaller stack spacings—for all boom lengths—peaking in this example at a spacing of 25 feet for the boom lengths considered here. Since the peak gain actually occurs with smaller spacing between Yagis in this 7-element stack, even relatively large and messy looking overhead lobes are not subtracting from the stacking gain. In the next section we'll now examine whether this overhead lobe is important or not.

Are Higher-Angle Lobes Important?

We've already shown that the exact spacing between HF Yagis is not critical for stacking gain. Further, the heights (and hence spacing) of the individual Yagis in a stack interact in a complicated fashion to determine higher-angle lobes.

Let's examine the relevance of such higher-angle lobes for stacked HF Yagis, this time in terms of interference reduction on receive. As Chapter 23, Radio Wave Propagation, points out, few DX signals arrive at elevation angles greater than about 30°. In fact, DX signals only propagate at elevation angles in the range from 1° to 30° on all the bands where operators might reasonably expect to stack Yagis—nominally from 7 to 29.7 MHz.

You should remember that the definition of the *critical frequency* for HF propagation is the highest frequency for which a wave launched directly overhead at 90° elevation is reflected back down to Earth, rather than being lost into outer space. The maximum critical frequency for extremely high levels of solar flux is about 15 MHz. In other words, high overhead angles do not propagate signals on the upper HF bands.

However, some domestic signals do arrive at relatively high elevation angles. Let's look at some scenarios where higher angles might be encountered and how the elevation patterns of typical HF stacks affect these signals. Let's examine a situation where a medium-range interfering station is on the same heading as a more distant target station.

We'll examine a typical scenario involving stations in Atlanta, Boston and Paris. The heading from Atlanta to Paris is 49º, the same heading as Atlanta to Boston. In other words, the Atlanta station would have to transmit over (and listen through) a Boston station for communication with Paris. The distance between Atlanta and Boston is about 940 miles, while the distance from Atlanta to Paris is about 4350 miles. Ground wave signals obviously cannot travel either of these distances at 21 MHz (ground wave coverage is less than about 10 miles at this frequency), and so the propagation between Atlanta to Boston and Atlanta to Paris will be entirely by means of the ionosphere.

Let's evaluate the situation on 15 meters in the month of October. We'll assume a smoothed sunspot number (SSN) of 100 and that each station puts 1500 W of power into theoretical isotropic antennas that have +10 dBi of gain at all elevation and azimuth angles. [We use such theoretical isotropic antennas because they make it easier to work in *VOACAP*. We will factor in real-world stacks later.] *VOACAP* predicts that the signal from Boston will be S9 + 8 dB in Atlanta at 1400 UTC, arriving at an elevation angle of 21.3º on a single F_2 hop. This elevation angle is higher than commonly encountered angles for DX signals, but it is still far away from near-overhead angles.

The signal from Paris into Atlanta is predicted to be about S6 for the same theoretical isotropic antennas, at an incoming elevation angle of 6.4º on three F_2 hops. The S6 level validates the rule-of-thumb that each extra hop loses approximately 10 dB of signal strength, assuming that each S unit is about 4 dB, typical for modern receivers.

Now look at **Fig 36**, which shows the response for a stack of 3-element Yagis at 90/60/30 feet over flat ground, along with the response for a similar stack of 7-element Yagis. Again, we'll assume that all three stations are using such 3-element 90/60/30-foot stacks. The stations in Atlanta and Boston point their stacks into Europe and the Parisian station points his stack towards the USA. The gain of the Atlanta array at 6.4º into Paris will be about 16 dBi, or 6 dB more than the isotropic array with its +10 dBi of gain selected for use in *VOACAP*. Similarly, the French station's transmitted signal will enjoy a 6 dB gain advantage over the isotropic array used in the *VOACAP* calculation, and thus the French signal into Atlanta will now be S6 + 12 dB, or about S9.

By comparison, the interfering signal from Boston into Atlanta will be reduced by the rearward pattern of his array, which will launch a signal at 180º – 21.3º = 158.7º in elevation at the single F_2 mode from Boston to Atlanta. From Fig 33, the Boston station's gain at this rearward elevation is going to drop from the isotropic's +10 dBi of gain down to –11 dBi, a drop of 21 dB. The signal into the Atlanta receiver will also be reduced by the pattern of the Atlanta array on receive, which has a gain of about 0 dBi at 21.3º, compared to the isotropic's +10 dBi gain at 6.4º, a net drop of 10 dB.

Thus, the Boston station's signal will drop by about 21 + 10 = 31 dB, bringing the interfering signal from Boston, which would be S9 + 8 dB for isotropic antennas, down to about S3 due to the combined effects of the arrays. This is a very significant reduction in interference. But you will note that the reduction has nothing to



Fig 36—Stacks of three 3-element and 7-element Yagis on 15 meters at 90/60/30 feet heights. The F/B for the 7-element stack is superior to the 3-element stack mainly because the F/B is intrinsically better for the long-boom design.

do with the near-overhead lobes, dealing as it does with the trailing edge of the main lobe and the F/B lobe.

Even Higher Elevation Angles

Now let's evaluate a station that is even closer to Boston, say a station in Philadelphia. The heading from Philadelphia to Paris is 53º and the distance is 3220 miles. On the same day in October as above, *VOACAP* predicts a signal strength of S8 from Paris to Philadelphia, at a 2.7º elevation angle on two F_2 hops. Again, the *VOACAP* computations assume isotropic antennas with +10 dBi gain at all three stations. The gain of the 3-element stacks at both ends of the circuit at 2.7º is also about +10 dBi, so the signal level from Paris to Philadelphia would be S8 with the 3-element stacks.

Now *VOACAP* computes the elevation angle from Philadelphia to Boston as 56.3º, on one F_2 hop launched at an azimuth of 53º, well within the azimuthal beamwidth of the stack. *VOACAP* says the predicted signal strength for isotropic antennas with +10 dBi of gain is less than S1!

What's happening here? Boston and Philadelphia are within the "skip" region on 21 MHz and signals are skipping right over Boston from Philadelphia (and vice versa). Actual signals would be much weaker than they would be with theoretical isotropic antennas because of the actual patterns of the transmitting and receiving stacks. At an elevation angle of 56.3º the receiving stack would have a gain of –10 dBi, while at an elevation of 180º – 56.3º = 123.7º the transmitting stack would be down to –10 dBi as well. The net reduction for the stacks compared to isotropics with +10 dBi gain each would be 40 dB, putting the interfering signal well into the receiver noise.

You can safely say that near-overhead angles don't enter into the picture, simply because signals at intermediate distances are in the ionospheric skip zone and interfering signals are very weak in that zone already.

Even in situations where having a poor front-to-back ratio might be beneficial—because it alerts stations tuning across your signal that you are occupying that frequency—the ionosphere doesn't cooperate for intermediate-distance signals that are in the skip zone. Often two stations may be on the same frequency without either knowing that the other is there.

Ground Wave?

What happens, you might wonder, for ground-wave signals? Let's look at a situation where the interfering station is in the same direction as the desired target, but is only 5 miles away. Unfortunately, his signal is S9 + 50 dB. Even reducing the level by 30 dB, a huge number, is still going to make his signal 20 dB stronger than signals from your desired target location! There is not much you can do about ground-wave signals and fretting about optimizing stack heights to discriminate against local signals is generally futile.

Stacking Distances for Multiband Yagis

By definition, a stack of multiband Yagis (such as a "tribander" covering 20/15/10 meters) has a constant vertical spacing between antennas in terms of feet or meters, but not in terms of wavelength. Tribanders are no different than monobanders in terms of optimal spacing between individual antennas. Again, the difference in gain between spacings of 0.5 λ and 1.0 λ for a stack of triband Yagis amounts to only a fraction of a decibel. Furthermore, the main practical constraint that limits choice of stacking distances between any kind of Yagis, multiband or monoband, is the spacing between guy wire sets on the tower itself.

Summary, Stacking Distances

In short, let us summarize that there is nothing magical about stacking distances for practical HF Yagis—a good rule-of-thumb is a stacking distance of 0.65 λ. This is 23 feet on 10 meters, 30 feet on 15 meters and 45 feet on 20 meters for monoband stacks. Practically speaking, however, you've only got limited places where you can mount antennas on the tower—mainly where guy wires allow you to place them. This is especially applicable if you wish to rotate lower antennas on the tower, where you must clear the guys from up above.

STACKS AND FADING

The following is derived from an article by Fred Hopengarten, K1VR, and Dean Straw, N6BV, in a Feb 1994 *QST* article. Using stacked Hy-Gain TH7DXs or TH6DXXs at their respective stations, they have solicited a number of reports from stations, mainly in Europe, to compare various combinations of antennas in stacks and as single antennas. The peak gain of the stack is usually just a little bit higher than that for the best of the single antennas, which is not surprising. Even a large stack has no more than about 6 dB of gain over a single Yagi at a height favoring the prevailing elevation angle. Fading on the European path can easily be 20 dB or more, so it is very confusing to try to make definitive comparisons. They have noticed over many tests that the stacks are much less susceptible to fading compared to single Yagis. Even within the confines of a typical SSB bandwidth, frequency-selective fading occasionally causes the tonal quality of a voice to change on both receive and transmit, often dramatically becoming fuller on the stacks, and tinnier on the single antennas. This doesn't happen all the time, but is often seen. They have also observed often that the depth of a fade is less, and the period of fading is longer, on the stacks compared to single antennas.

Exactly *why* stacks exhibit less fading is a fascinating subject, for which there exist a number of speculative ideas, but little hard evidence. Some maintain that stacks outperform single antennas because they can afford *space diversity* effects, where by virtue of the difference in physical placement one antenna will randomly pick up signals that another one in another physical location might not hear.

This is difficult to argue with, and equally difficult to prove scientifically. A more plausible explanation about why stacked Yagis exhibit superior fading performance is that their narrower frontal elevation lobes can discriminate against undesired propagation modes. Even when band conditions favor, for example, a very low 3° elevation angle on 10 or 15 meters from New England to Western Europe, there are signals, albeit weaker ones, that arrive at higher elevation angles. These higher-angle signals have traveled longer distances on their journey through the ionosphere, and thus their signal levels and their phase angles are different from the signals traversing the primary propagation mode. When combined with the dominant mode, the net effect is that there is both destructive and constructive fading. If the elevation response of a stacked antenna can discriminate against signals arriving at higher elevation angles, then in theory the fading will be reduced. Suffice it to say: In practice, stacks do reduce fading.

STACKS AND PRECIPITATION STATIC

The top antenna in a stack is often much more affected by rain or snow precipitation static than is the lower antenna. N6BV and K1VR have observed this phenomenon, where signals on the lower antenna by itself are perfectly readable, while S9+ rain static is rendering reception impossible on the higher antenna or on the stack. This means that the ability to select individual antennas in a stack can sometimes be extremely important.

STACKS AND AZIMUTHAL DIVERSITY

Azimuthal diversity is a term coined to describe the situation where one of the antennas in a stack is purposely pointed in a direction different from the main direction of the stack. During most of the time in a DX contest from the East Coast, the lower antennas in a stack are pointed into Europe, while the top antenna is often rotated toward the Caribbean or Japan. In a stack of three identical Yagis, the first-order effect of pointing one antenna in a different direction is that one-third of the transmitter power is diverted from the main target area. This means that the peak gain is reduced by 1.8 dB, not a very large amount considering that signals are often 10 to 20 dB over S9 anyway when the band is open from New England to Europe.

Fig 37 shows the 3D pattern of a pair of 4-element Yagis fed in-phase at 95 and 65 feet, but where the lower antenna has been rotated 180° to fire in the –X direction. The backwards lobe peaks at a higher elevation angle because the antenna doing the radiating in this direction is lower on the tower. The forward lobe peaks at a lower angle because its main radiator is higher.

THE N6BV/1 ANTENNA SYSTEM—BRUTE FORCE FEEDING

The N6BV/1 system in Windham, New Hampshire, was located on the crest of a small hill about 40 miles from Boston, and could be characterized as a good, but not dominant, contesting station. A number of top-10 contest results were achieved from that station in the 1990s before N6BV returned to California.

There was a single 120-foot high Rohn 45 tower, guyed at 30-foot intervals, with a 100-foot horizontal spread from tower base to each guy point so there was sufficient room for rotation of individual Yagis on the tower. Each set of guy wires employed heavy-duty insulators at 57-foot intervals, to avoid resonances in the 80 through 10-meter amateur bands. There were five Yagis on the tower. A heavy-duty 12-foot long steel mast with 0.25-inch walls was at the top of the tower, turned by an Orion 2800 rotator. Two thrust bearings were used above the rotator, one at the top plate of the tower itself, and the other about 2 feet down in the tower on a modified rotator shelf plate. The two thrust bearings allowed the rotator to be removed for service.

At the top of the mast, 130 feet high, was a 5-element, computer-optimized 10-meter Yagi, which was a modified Create design on a 24-foot boom. The element tuning was modified from the stock antenna in order to achieve higher gain and a better pattern over the band. At the top of the tower (120-foot level) was mounted a Create 714X-3 triband Yagi. This was a large tribander, with a 32-foot boom and five elements. Three elements were active on 40 meters, four were active on 20 meters and four were active on 15 meters. The 40-meter elements were loaded with coils, traps and



Fig 37—3D representation of the pattern for two 4-element 15-meter Yagis, with the top antenna at 95 and the bottom at 65 feet, but pointed in the opposite direction.

capacitance hats, and were approximately 46 feet long. A triband 20/15/10-meter Hy-Gain TH7DX tribander was fixed into Europe at the 90-foot level on the tower, just above the third set of guys.

At the 60-foot level on the tower, just above the second set of guys, there was a "swinging-gate" side-mount bracket, made by DX Engineering of Oregon. A Hy-Gain *Tailtwister* rotator turned a TH7DX on this side mount. (Note that both the side mount and the element spacings of the TH7DX itself prevented full rotation around the tower—about 280° of rotation was achieved with this system.) At the 30-foot level, just above the first set of guys, was located the third TH7DX, also fixed on Europe.

All five Yagis were fed with equal lengths of Belden 9913 low-loss coaxial cable, each measured with a noise bridge to ensure equal electrical characteristics. At each feed point a ferrite-bead choke balun (using seven large beads) was placed on the coax. All five coaxial cables went to a relay switch box mounted at the 85-foot level on the tower. **Fig 38** shows the schematic for the switch box, which was fed with 250 feet of 75-Ω, 0.75-inch OD Hardline coaxial cable.

The stock DX Engineering remote switch box was modified by adding relay K6, so that either the 130-foot or the 120-foot rotating antenna could be selected through a second length of 0.75-inch Hardline going to the shack. This created a *Multiplier* antenna, independent of the *Main* antennas. A second band could be monitored in this fashion while calling CQ using the main antennas on another band. Band-pass filters were required at the multiplier receiver to prevent overload from the main transmitter.

The 0.75-inch Hardline had very low losses, even when presented with a significant amount of SWR at the switch-box end. This was important, because unlike K1VR's system, no attempt was made at N6BV to maintain a constant SWR when relays K1 through K5 were switched in or out. This seemingly cavalier attitude came about because of several factors. First, there were many



Fig 38—N6BV/1 switch box system. This uses a modified DX Engineering remote switch box, with relay K6 added to allow selection of either of the two top antennas (5-element 10-meter Yagi or 40/20/15-meter triband 714X-3) as a "multiplier" antenna. There is no special provision for SWR equalization when any or all of the Yagis are connected in parallel as a stack fed by the Main coaxial cable. Each of the five Yagis is fed with equal lengths of flexible Belden 9913 coax, so phasing can be maintained on any band. The Main and "Multiplier" coaxes going to the shack are 0.75" OD 75-Ω Hardline cables.

different combinations of antennas that could be used together in this system. Each relay coil was independently controlled by a toggle switch in the shack. N6BV was unable to devise a matching system that did not become incredibly complex because of the numerous impedance combinations used over all the five bands.

Second, the worst-case additional transmission line loss due to a 4:1 SWR mismatch when four antennas were connected in parallel on 10 meters was only 0.5 dB. It was true that the linear amplifier had to be retuned slightly when combinations of antennas were switched in and out, but this was a small penalty to pay for the reduced complexity of the switching and matching networks. The 90/60/30-foot stack into Europe was used for about 95% of the time during DX contests, so the small amount of amplifier retuning for other antenna combinations was considered only a minor irritation.

WHY TRIBANDERS?

Without a doubt, the most common question K1VR and N6BV have been asked is: "Why did you pick *tribanders* for your stacks?" Triband antennas were chosen with full recognition that they are compromise antennas. Other enterprising amateurs have built stacked tribander arrays. Bob Mitchell, N5RM, is a prominent example, with his so-called *TH28DX* array of four TH7DX tribanders on a 145-foot-high rotating tower. Mitchell employed a rather complex system of relay-selected tuned networks to choose either the upper stacked pair, the lower stacked pair or all four antennas in stack. Others in Texas have also had good results with their tribander stacks. Contester Danny Eskenazi, K7SS, has very successfully used a pair of stacked KT-34XA tribanders for years.

A major reason why tribanders were used is that over the years both authors have had good results using TH6DXX or TH7DX antennas. They are ruggedly built, mechanically and electrically. They are able to withstand New England winters without a whimper, and their 24-foot long booms are long enough to produce significant gain, despite trap-loss compromises. Amateurs speculating about trap losses in tribanders freely bandy about numbers between 0.5 and 2 dB. Both N6BV and K1VR are comfortable with the lower figure, as are the Hy-Gain engineers.

Consider this: If 1500 W of transmitter power is going into an antenna, a loss of 0.5 dB amounts to 163 W. This would create a significant amount of heat in the six traps that are on average in use on a TH6DXX, amounting to 27 W per trap. If the loss were as high as 1 dB, this would be 300 W total, or 50 W per trap. Common sense says that if the overall loss were greater than about 0.5 dB, the traps would act more like big *firecrackers* than resonant circuits! A long-boom tribander like the TH6DXX or TH7DX also has enough space to employ elements dedicated to different bands, so the compromises in element spacing usually found on short-boom 3 or 4-element tribanders can be avoided.

Another factor in the conscious choice of tribanders was first-hand frustration with the serious interaction that can result from stacking monoband antennas closely together on one mast in a Christmas Tree configuration. N6BV's worst experience was with the ambitious 10 through 40-meter Christmas Tree at W6OWQ in the early 1980s. This installation used a Tri-Ex SkyNeedle tubular crankup tower with a rotating 10-foot-long heavy-wall mast. The antenna suffering the greatest degradation was the 5-element 15-meter Yagi, sandwiched 5 feet below the 5-element 10-meter Yagi at the top of the mast, and 5 feet above the full-sized 3-element 40-meter Yagi, which also had five 20-meter elements interlaced on its 50-foot boom.

The front-to-back ratio on 15 meters was at best about 12 dB, down from the 25+ dB measured with the bottom 40/20-meter Yagi removed. No amount of fiddling with element spacing, element tuning or even orientation of the 15-meter boom with respect to the other booms (at 90° or 180°, for example) improved its performance. Further, the 20-meter elements had to be lengthened by almost a foot *on each end of each element* in order to compensate for the effect of the interlaced 40-meter elements. It was a lucky thing that the tower was a motorized crankup, because it went up and down hundreds of times as various experiments were attempted!

Interaction due to close proximity to other antennas in a short Christmas Tree can definitely destroy carefully optimized patterns of individual Yagis. Nowadays, such interaction can be modeled using a computer program such as *EZNEC* or *NEC*. A gain reduction of as much as 2 to 3 dB can easily result due to close vertical spacing of monobanders, compared to the gain of a single monoband antenna mounted in the clear. Curiously enough, at times such a reduction in gain can be found even when the front-to-back ratio is not drastically degraded, or when the front-to-back occasionally is actually *improved*.

If you plan on stacking monoband Yagis—for example, putting only 15-meters Yagis on a single tower, with your other monoband stacks on other towers—do make sure you model the system to see if any interactions occur. You may be quite surprised.

Finally, in the N6BV/1 installation, triband antennas were chosen because the system was meant to be as simple as possible, given a certain desired level of performance, of course. Triband antennas make for less mechanical complexity than do an equivalent number of monobanders. There were five Yagis on the N6BV/1 tower, yielding gain from 40 to 10 meters, as opposed to using 12 or 13 monobanders on the tower.

THE K1VR ARRAY: A MORE ELEGANT APPROACH TO MATCHING

The K1VR stacked array is on a 100-foot high Rohn

25 tower, with sets of guy wires at 30, 60 and 90 feet, made of nonconducting Phillystran. Phillystran is a nonmetallic Kevlar rope covered by black polyethylene to protect against the harmful effects of the sun's ultraviolet rays. A caution about Phillystran: Don't allow tree branches to rub against it. It is designed to work in tension, but unlike steel guy wire, it does not tolerate abrasion well.

Both antennas are Hy-Gain TH6DXX tribanders, with the top one at 97 feet and the bottom one at 61 feet. The lower antenna is rotated by a Telex Ham-M rotator on a homemade swinging-gate side mount, which allows it to be rotated 300° around the tower without hitting any guy wires or having an element swing into the tower. At the 90-foot point on the tower, a 2-element 40-meter Cushcraft Yagi has been mounted on a RingRotor so it can be rotated 360° around the tower.

After several fruitless attempts trying to match the TH6DXX antennas so that either could be used by itself or together in a stack, K1VR settled on using a relay-selected broadband toroidal matching transformer. When both triband antennas are fed together in parallel as a stack, it transforms the resulting 25-Ω impedance to 50 Ω. The transformer is wound on a T-200A powdered-iron core, available from Amidon, Palomar Engineering or Ocean State Electronics. Two lengths of twin RG-59 coax (sometimes called Siamese or WangNet), four turns each, are wound on the core. Two separate RG-59 cables could be used, but the Siamese-twin cable makes the assembly look much more tidy. The shields of the RG-59 cables are connected in series, and the center conductors are connected in parallel. See **Fig 39** for details.


50-Ω Point
1
3
4
2
25-Ω Point
7
8
5
6
50 Ω
1
2
25 Ω
3
4
5
6
7
8
4 turns RG-59A coax on T-200A core
1
5
50 Ω
2
6
7
25 Ω
8
3
4

Fig 39—Diagram for matching transformer for K1VR stacked tribander system. The core is powdered iron-core T-200A, with four turns of two RG-59A or "Siamese" coax cables. Center conductors are connected in parallel and shields are connected in series to yield 0.667:1 turns ratio, close to desired 25-Ω to 50-Ω transformation.

Fig 40 shows the schematic of the K1VR switch box, which is located in the shack. Equal electrical lengths of 50-Ω Hardline are brought from the antennas into the shack and then to the switch box. Inside the box, the relay contacts were soldered directly to the SO-239 chassis connectors to keep the wire lengths down to the absolute minimum. K1VR used a metal box that was larger than


UPPER TH6DXX
LOWER TH6DXX
Equal lengths of 50-Ω Hardline
Flexible Coax
Flexible Coax
Inside Shack
K1
K2
K3
K4
MAIN FEED to TX
25 Ω
50 Ω
T1
4
3
8
7
2
1
6
5
Coaxial Cable Transformer
+24 V
K1
K2
K3
K4
BOTH
UPPER
LOWER
Diodes are 1N4001s.

Fig 40—Relay switch box for K1VR stacked tribander system. Equal lengths of 50-Ω Hardline (with equal lengths of flexible 50-Ω cable at each antenna to allow rotation) go to the switch box in the shack. The SWR on all three bands for Upper, Lower or Both switch positions is very close to constant.

might appear necessary because he wanted to mount the toroidal transformer with plenty of clearance between it and the box walls. The toroid is held in place with a piece of insulation foam board. Before placing the switch box in service, the system was tested using two 50-Ω dummy loads, with equal lengths of cable connected in parallel to yield 25 Ω. The maximum SWR measured was 1.25:1 at 14 MHz, 1.3:1 at 21 MHz and 1.15:1 at 28 MHz, and the core remained cold with 80 W of continuous output power.

One key to the system performance is that K1VR made the electrical lengths of the two hardlines the same (within 1 inch) by using a borrowed TDR (time domain reflectometer). Almost as good as Hardline, K1VR points out, would be to cut exactly the same length of cable from the same 500-foot roll of RG-213. This eliminates manufacturing tolerances between different rolls of cable.

K1VR's experience over the last 10 years has been that at the beginning of the 10 or 15-meter morning opening to Europe the upper antenna is better. Once the band is wide open, both antennas are fed in phase to cast a bigger shadow, or footprint, on Europe. By mid-morning, the lower antenna is better for most Europeans, although he continues to use the stack in case someone is hearing him over a really long distance path throughout Europe. He reports that it is always very pleasant to be called by a 4S7 or HS0 or VU2 when he is working Europeans at a fast clip!

SOME SUGGESTIONS FOR STACKING TRIBANDERS

It is unlikely that many amateurs will try to duplicate exactly K1VR's or N6BV's contest setups. However, many hams already have a tribander on top of a moderately tall tower, typically at a height of about 70 feet. It is not terribly difficult to add another, identical tribander at about the 40-foot level on such a tower. The second tribander can be pointed in a fixed direction of particular interest (such as Europe or Japan), or it can be rotated around the tower on a side mount or a Ring Rotor. If guy wires get in the way of rotation, the antenna can usually be arranged so that it is fixed in a single direction.

Insulate the guy wires at intervals to ensure that they don't shroud the lower antenna electrically. A simple feed system consists of equal-length runs of surplus 0.5-inch 75-Ω Hardline (or more expensive 50-Ω Hardline, if you are really obsessed by SWR) from the shack up the tower to each antenna. Each tribander is connected to its respective Hardline feeder by means of an equal length of flexible coaxial cable, with a ferrite choke balun, so that the antenna can be rotated.

Down in the shack, the two hardlines can simply be switched in and out of parallel to select the upper antenna only, the lower antenna only, or the two antennas as a stack. See **Fig 41**. Any impedance differences can be handled as stated previously, simply by retuning the linear amplifier, or by means of the internal antenna tuner (included in most modern transceivers) when the transceiver is run barefoot. The extra performance experienced in such a system will be far greater than the extra decibel or two that modeling calculates.



Fig 41—Simple feed system for 70/40-foot stack of tribanders. Each tribander is fed with equal lengths of 0.5-inch 75-Ω Hardline cables (with equal lengths of flexible coax at the antenna to allow rotation), and can be selected singly or in parallel at the operator's position in the shack. Again, no special provision is made in this system to equal SWR for any of the combinations.

THE WX0B APPROACH TO STACK MATCHING AND FEEDING

Earlier we mentioned how useful it would be to switch various antennas in or out of a stack, depending on the elevation angles that need to be emphasized at that moment. Jay Terleski, WX0B, of Array Solutions has designed switchable matching systems, called *StackMatches*, for stacks of monoband or multiband Yagis.

The StackMatch uses a 50-Ω to 22.25-Ω broadband transmission-line transformer to match combinations of up to three Yagis in a stack. See **Fig 42** for a schematic of the StackMatch. For selection of any 50-Ω Yagi by itself, no matching transformer is needed and Relay IN routes RF directly to the common bus going to Relay 1, 2 and 3. For selection of two Yagis together the parallel impedance is 50/2 = 25 Ω and Relay IN routes RF to the matching transformer. The SWR is 25/22.25 = 1.1:1. For three Yagis used together, the parallel impedance is 50/3 = 16.67 Ω, and the SWR is 22.25/16.67 = 1.3:1.

The broadband transformer consists of four trifilar turns of #12 enamel-insulated wire wound on a Ferrite Corporation FT-240 2.4-inch OD core made of #61



Fig 42—Schematic of WX0B's StackMatch 2000 switchbox, which uses a broadband transmission line transformer using trifilar #12 enamel-insulated wires. (*Courtesy Array Solutions.*)

material ($\mu = 125$). WX0B uses 10-A relays enclosed in plastic cases to do the RF switching, selected by a control box at the operating position. (10-A relays can theoretically handle $10\ \text{A}^2 \times 50\ \Omega = 5000$ W.) **Fig 43** shows a photo of the transmission-line transformer and StackMaster PCB.

The control/indicator box uses a diode matrix to switch various combinations of antennas in/out of the stack. Three LEDs lined up vertically on the front panel indicate which antennas in a stack are selected.

"BIP/BOP" OPERATION

The contraction "BIP" means "both in-phase," while "BOP" means "both out-of-phase." BIP/BOP refer to stacks containing two Yagis, although the term is commonly used for stacks containing more than two Yagis. In theory, feeding a stack with the antennas out-of-phase will shift the elevation response higher than in-phase feeding.

Fig 44 shows a rectangular plot comparing BIP/BOP operation of two 3-element 15-meter Yagis at heights of $2\ \lambda$ and $1\ \lambda$ (93 and 46 feet) over flat ground. The BOP pattern is the higher-angle lobe and the two lobes cross over about 14°. The maximum amplitude of the BOP stack's gain is about ½ dB less than the BIP pair. For reference, the pattern of a single 46-foot high Yagi is overlaid on the pattern for the stacks.

The most common method for feeding one Yagi 180° out-of-phase is to include an extra electrical half wavelength of feed-line coax going to one of the antennas. This method obviously works on a single frequency band and thus is not applicable to stacks of multiband Yagis, such as tribanders. For such multiband stacks, feeding only the lower antenna(s)—by switching out higher antenna(s) in the stack—is a practical method for achieving better coverage at medium or high elevation angles.



Fig 43—Inside view of StackMatch. (*Photo courtesy Array Solutions.*)



Fig 44—*HFTA* screen shot of "BIP/BOP" operation of two 4-element 15-meter Yagis at 93 and 46 feet above flat ground. The elevation response in BOP (both out-of-phase) operation is shifted higher, peaking at about 21°, compared to the BIP (both in-phase) operation where the peak is at 8°. The dashed line is response of single Yagi at 46 feet.

STACKING DISIMILAR YAGIS

So far we have been discussing vertical stacks of identical Yagis. Less commonly, hams have successfully stacked dissimilar Yagis. For example, consider a case where two 5-element 10-meter Yagis are placed 46 and 25 feet above flat ground, with a 7-element 10-meter Yagi at 68 feet on the same tower. See **Fig 45**, which is a schematic of the layout for this stack. Note that the driven element for the top 7-element Yagi is well behind the vertical plane of the driven elements for the two 5-element Yagis. This offset distance must be compensated for with a phase shift in the drive system for the top Yagi.

Fig 46 shows the elevation-pattern responses for uncompensated (equal-length feed lines) and the compensated (additional 150° of phase shift to top Yagi) stacks. These patterns were computed using *EZNEC ARRL*, which is included with this book. Not only is about 1.7 dB of maximum gain lost, but the peak elevation angle is shifted upwards by 11° from the optimal takeoff angle of 8°—where some 10 dB of gain is also lost. Without compensation, this is a severe distortion of the stack's elevation pattern.

For RG-213 coax, the extra length needed to provide an additional 150° of phase shift = 150°/360° λ = 0.417 λ = 9.53 feet at 28.4 MHz. This was computed using the program *TLW* (Transmission Line for Windows) included on the CD-ROM accompanying this book.



Fig 45—Stacking dissimilar Yagis. In this case a 7-element 10-meter Yagi is stacked over two 5-element Yagis. Note the displacement of the 7-element Yagi's driven element compared to the position of the two 5-element Yagis. This leads to an undesired phase shift for the higher antenna.



Fig 46—Comparison of elevation responses for 7/5/5-element 10-meter stacks, with and without compensation for driven-element offset.

It is not always possible to compensate for dissimilar Yagis in a stack with a simple length of extra coax, so you should be sure to model such combinations to make sure that they work properly. A safe alternative, of course, is to stack only identical Yagis, feeding all of them with equal lengths of coax to ensure in-phase operation.

Real-World Terrain and Stacks

So far, the stacking examples shown have been for flat ground. Things can become a lot more complicated when you deal with real-world irregular terrains! See Chapter 3, The Effects of Ground, for a description of the *HFTA* (High Frequency Terrain Assessment) program that is included with this book.

Fig 47 shows the *HFTA*-computed 20-meter elevation responses towards Europe (at an azimuth of 45°) for three antennas at the N6BV/1 location in Windham, New Hampshire. Overlaid as a bar graph are the elevation-angle statistics for the path to all of Europe from New England (Massachusetts). The stack at 90/60/30 feet clearly covers all the angles needed best at 14 MHz. The N6BV 120-foot Yagi has a severe null in the region from about 7° to about 20°, with the deepest part of that null occurring at about 13° and is roughly comparable to the 90/60/30-foot stack between 2° to 7°.

In practice, the 120-foot Yagi was indeed comparable to the stack during morning openings to Europe on 20 meters, when the elevation angles are typically about 5°. In the New England afternoon, when the elevation angles typically rise to about 11°, the 120-foot Yagi was always distinctly inferior to the stack.

For reference, the response of a single 120-foot high Yagi over flat ground is also shown. Note that the N6BV 120-foot high Yagi has about 3 dB more gain at a 5° takeoff angle than does its flatland counterpart. This additional gain is due to the focusing effects of the local terrain, which had about a 3° downwards slope towards Europe.

Fig 48 shows the *HFTA*-computed 15-meter elevation responses towards Europe for the 90/60/30-foot stack at 90/60/30 feet at N6BV/1, compared to the same 120-foot high Yagi and a 90/60/30-foot stack, but this time over flat ground. Again, the N6BV/1 terrain towards Europe has a significant effect on the gain of the stack compared to that of an identical stack over flat ground. In fact, the peak gain of 20.1 dBi at a 4° elevation angle is close to moon-bounce levels.

OPTIMIZING OVER LOCAL TERRAIN

There are only a small number of possibilities to optimize an installation over local terrain:

- Change the antenna height(s) above ground.
- Stack two (or more) Yagis.
- Change the spacing between stacked Yagis.
- Move the tower back from a cliff (or a hill).
- BIP/BOP (Both In Phase/Both Out of Phase).

The *HFTA* program on the CD-ROM accompanying this book can be used, together with Digital Elevation Model (DEM) topographic data available on the Internet, to evaluate all these options.

SO NEAR, YET SO FAR

It is sometimes very surprising to compare elevation responses for different towers located at various points on the same property, particularly when that prop-



Freq. = 14.2 MHz
Max. Gain: 19.2 dBi

N6BV-45.PRO
90/60/30 ft
Fig. of Merit: 17.2

N6BV-45.PRO
120 ft
Fig. of Merit: 13.4

FLAT.PRO
120 ft
Fig. of Merit: 12

Elev. Statistic File:
W1-MA-EU.PRN

Fig 47—*HFTA* screen shot showing how complicated things become when real-world irregular terrain is analyzed. This is the 20-meter elevation pattern for the N6BV/1 station location in Windham, NH, for the 90/60/30-foot stack of triband TH7DX Yagis and a 4-element Yagi at 120 feet on the same tower. For comparison, the response of a 120-foot Yagi over flat ground is also included.



Freq. = 21.2 MHz
Max. Gain: 20.1 dBi

N6BV-45.PRO
90/60/30 ft
Fig. of Merit: 16.3

N6BV-45.PRO
120 ft
Fig. of Merit: 12.9

FLAT.PRO
90/60/30 ft
Fig. of Merit: 15.4

Elev. Statistic File:
W1-MA-EU.PRN

Fig 48—*HFTA* screen shot showing the 15-meter elevation pattern for the N6BV/1 station location in Windham, NH, for the 90/60/30-foot stack of triband TH7DX Yagis and a 4-element Yagi at 120 feet on the same tower. For comparison, the response of a 120-foot Yagi over flat ground is also included.


Output Graph, HFTA
HFTA, Copyright ARRL 2002, by N6BV, Ver. 1.26B
Gain, dBi
Elevation Statistics, %
Takeoff Angle, Degrees
0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34
Four-Element Yagi, 8.5 dBi Free-Space Gain
Print
Out File
Close

Freq. = 14.2 MHz
Max Gain: 17.2 dBi

K1KI-N-45.PRO
100 ft
Fig. of Merit: 13.5

K1KI-S-45.PRO
100 ft
Fig. of Merit: 12

FLAT.PRO
100 ft
Fig. of Merit: 12.1

Elev. Statistic File:
W1-MA-EU.PRN

Fig 49—*HFTA* screen shot showing the 20-meter elevation pattern for K1KI's North and South towers, with 100-foot high 4-element Yagis pointing into Europe at an azimuth of 45°. The responses are surprisingly different for two towers separated by only 600 feet.


Terrain Plot, HFTA
Terrain Profile
Height, feet ASL
230 240 250 260 270 280 290 300 310 320 330 340 350 360 370 380 390 400 410 420 430 440 450 460
0 2,000 4,000 6,000 8,000 10,000
Distance from Tower Base, Feet
Print
Close

K1KI-N-45.PRO
100 ft

K1KI-S-45.PRO
100 ft

Fig 50—K1KI's terrain profiles for the North and South towers at an azimuth of 45° into Europe.

erty is located in the mountains. **Fig 49** shows the computed elevation responses for three 100-foot high 14-MHz Yagis over three terrains towards Europe: from the North tower at K1KI's location in West Suffield, Connecticut, from the South tower at K1KI, and over flat ground. The elevation response from the South tower follows that over flat ground well, while the response from the North tower is quite a bit stronger at low elevation angles—about 1.5 dB on average, as the Figure of Merit shows from *HFTA*.

Fig 50 shows the reason why this happens—the terrain from the North tower slopes down quickly towards Europe, while the terrain from the South tower goes out almost 900 feet before starting to fall off. These two towers are about 600 feet apart.

Moxon Rectangle Beams

LB Cebik, W4RNL, has written extensively about the *Moxon rectangle*, an antenna invented by Les Moxon, G6XN, derived from a design by VK2ABQ. The Moxon rectangle beam takes less space horizontally than a conventional 2-element Yagi design, yet it offers nearly the same amount of gain and a superior front-to-back ratio. And as an additional benefit, the drive-point impedance is close to 50 Ω, so that it doesn't need a matching section.

For example, rather than a "wingspan" of 17 feet for the reflector in a conventional 2-element 10-meter Yagi, the Moxon rectangle is 13 feet wide, a saving of almost 25%. The Moxon rectangle W4RNL created for *The ARRL Antenna Compendium, Vol 6*, had an SWR less than 2:1 from 28.0 to 29.7 MHz, with a gain over ground of 11 dBi. It had a F/B of 15 dB at 28.0 MHz, more than 20 dB at 28.4 MHz, and 12 dB at 29.7 MHz.

The Moxon rectangle relies on controlling the spacing (hence controlling the coupling) between the ends of the driven element tips and the ends of the reflector tips, which are both bent toward each other. See **Fig 51**, which shows the general outline for W4RNL's 10-meter aluminum Moxon rectangle. The tips of the elements are kept a fixed distance from each other by PVC spacers. The closed rectangular mechanical assembly gives some rigidity to the design, keeping it stable in the wind. W4RNL described other Moxon rectangle designs using wire elements in June 2000 *QST*.


Radius corners
0.875" dia. al.
Feedpoint
0.75" dia. al.
4' 0.875" dia. al.
0.75" dia. al.
1' 8.2"
0.75"
dia. al.
0.75"
dia. al.
0.625" OD CPVC Spacer
0.625" OD CPVC Spacer
6.2"
4' 7.2"
0.75"
dia. al.
0.75"
dia. al.
12' 8.5"
2' 4.8"
0.75" dia. al.
4' 0.875" dia. al.
0.75" dia. al.

Fig 51—General outline of the 10-meter aluminum Moxon rectangle, showing tubing dimensions.

Chapter 12

Quad Arrays

Chapter 11, HF Yagi Arrays, discussed Yagi arrays as systems of approximately half-wave dipole elements that are coupled together mutually. You can also employ other kinds of elements using the same basic principles of analysis. For example, loops of various types may be combined into directive arrays. A popular type of parasitic array using loops is the *quad antenna*, in which loops having a perimeter of about one wavelength are used in much the same way as half-wave dipole elements in the Yagi antenna.

Clarence Moore, W9LZX, created the quad antenna in the early 1940s while he was at the Missionary Radio Station HCJB in Quito, Ecuador. He developed the quad to combat the effects of corona discharge at high altitudes. The problem at HCJB was that their large Yagi was literally destroying itself by melting its own element tips. This occurred due to the huge balls of corona it generated in the thin atmosphere of the high Andes mountains. Moore reasoned correctly that closed loop elements would generate less high voltage—and hence less corona—than would the high impedances at the ends of a half-wave dipole element.

Fig 1 shows the original version of the two-element quad, with a driven element and a parasitic reflector. The square loops may be mounted either with the corners lying on horizontal and vertical lines, as shown at the left, or with two sides horizontal and two vertical (right). The feed points shown for these two cases will result in horizontal polarization, which is commonly used.

Since its inception, there has been controversy whether the quad is a better performer than a Yagi. Chapter 11 showed that the three main electrical performance parameters of a Yagi are gain, response patterns (front-to-rear ratio, F/R) and drive impedance/SWR. Proper analysis of a quad also involves checking all these parameters across the entire frequency range over which you intend to use it. Both a quad and a Yagi are classified as "parasitic, end-fire arrays." Modern antenna modeling by computer shows that monoband Yagis and quads with the same boom lengths and optimized for the same performance parameters have gains within about 1 dB of each other, with the quad slightly ahead of the Yagi.



Fig 1—The basic two-element quad antenna, with driven-element loop and reflector loop. The driven loops are electrically one wavelength in circumference ($^1/_4$ wavelength on a side); the reflectors are slightly longer. Both configurations shown give horizontal polarization. For vertical polarization, the driven element should be fed at one of the side corners in the arrangement at the left, or at the center of a vertical side in the "square" quad at the right.



Fig 2—Comparison of gain, F/R and SWR over the 14.0 to 14.35-MHz range for an optimized three-element quad and an optimized three-element Yagi, both on 26-foot booms. The quad exhibits almost 0.5 dB more gain for the same boom length, but doesn't have as good a rearward pattern over the whole frequency range compared to the Yagi. This is evidenced by the F/R curve. The quad's SWR curve is also not quite as flat as the Yagi. The quad's design emphasizes gain more than the other two parameters.

Fig 2 plots the three parameters of gain, front-to-rear ratio (F/R) and SWR over the 14.0 to 14.35-MHz band for two representative antennas—a monoband three-element quad and a monoband four-element Yagi. Both of these have 26-foot booms and both are optimized for the best compromise of gain, F/R and SWR across the whole band.

While the quad in Fig 2 consistently exhibits about 0.5 dB more gain over the whole band, its F/R pattern toward the rear isn't quite as good as the Yagi's over that span of frequencies. This quad attains a maximum F/R of 25 dB at 14.1 MHz, but it falls to 17 dB at the bottom end of the band and 15 dB at the top. On the other hand, the Yagi's F/R stays consistently above 21 dB across the whole 20-meter band. The quad's SWR rises to just under 3:1 at the top end of the band, but stays below 2:1 from 14.0 to almost 14.3 MHz. The Yagi's SWR remains lower than 1.5:1 over the whole band.

The reason the Yagi in Fig 2 has more consistent responses for gain, F/R and SWR across the whole 20-meter band is that it has an additional parasitic element, giving two additional variables to play with—that is, the length of that additional element and the spacing of that element from the others on the boom.

Yagi advocates point out that it is easier to add extra elements to a Yagi, given the mechanical complexities of adding another element to a quad. Extra parasitic elements give a designer more flexibility to tailor all performance parameters over a wide frequency range. Quad designers have historically opted to optimize strictly for gain and, as stated before, they can achieve as much as 1 dB more gain than a Yagi with the same length boom. But in so doing, a quad designer typically has to settle for front-to-rear patterns that are peaked over more narrow frequency ranges. The 20-meter quad plots in Fig 2 actually represent an even-handed approach, where the gain is compromised slightly to obtain a more consistent pattern and SWR across the whole band.

Fig 3 plots gain, F/R and SWR for two 10-meter monoband designs: a five-element quad and a five-element Yagi, both placed on 26-foot booms. The quad now has the same degrees of freedom as the Yagi, and as a consequence the pattern and SWR are more consistent across the range from 28.0 to 28.8 MHz. The quad's F/R remains above about 18.5 dB from 28.0 to 28.8 MHz. Meanwhile, the Yagi maintains an F/R of greater than 22 dB over the same range, but has almost 0.8 dB less gain compared to the quad at the low end of the band, eventually catching up at the high end of the band. The SWR for the quad is just over 2:1 at the bottom of the band, but remains less than 2:1 up to 28.8 MHz. The SWR on the Yagi remains less than 1.6:1 over the whole band.



Fig 3—Comparison of gain, F/R and SWR over the 28.0 to 28.8-MHz range for an optimized five-element quad and an optimized five-element Yagi, both on 26-foot booms. The gain advantage of the quad is about 0.25 dB at the low end of the band. The F/R is more peaked in frequency for the quad, however, than the Yagi.



Fig 4—Comparison of gain, F/R and SWR over the 21.0 to 21.45-MHz range for an optimized 5-element quad and optimized 5-element Yagi, both on 26-foot booms. The quad enjoys a gain advantage of about 0.5 dB over most of the band. Its rearward pattern is not as good as the Yagi, which remains higher than 24 dB across the whole range, compared to the quad, which remains in the 16-dB average range.

Fig 4 shows the performance parameters for two 15-meter monoband designs: a five-element quad and a five-element Yagi, both on 26-foot booms. The quad is still the leader in gain, but has a less optimal rearward pattern and a somewhat less flat SWR curve than the Yagi. One thing should be noted in Figs 2 through 4. The F/R pattern on the Yagi is largely determined by the response at the 180° point, directly in back of the frontal lobe. This point is usually referred to when discussing the "front-to-back ratio."

The quad on the other hand has what a sailor might term "quartering lobes" (referring to the direction back towards the "quarterdeck" at the stern of a sailing vessel) in the rearward pattern. These quartering lobes are often



Fig 5—Comparing the pattern of the 15-meter quad and Yagi shown in Fig 4. The quad has a slightly narrower frontal beamwidth (it has 0.5 dB more gain than the Yagi), but has higher "rear quartering" sidelobes at about 125° (with a twin sidelobe, not shown, at 235°). These sidelobes limit the worst-case front-to-rear (F/R) to about 17 dB, while the F/B (at 180°, directly at the back of the quad) is more than 24 dB for each antenna.

worse than the response at 180°, directly in back of the main beam. **Fig 5** overlays the free-space E-Field responses of the 15-meter quad and Yagi together. At 21.2 MHz, the quad actually has a front-to-back ratio (F/B) of about 24 dB, excellent in anyone's book. The Yagi at 180° has a F/B of about 25 dB, again excellent.

However, at an azimuth angle of about 125° (and at 235° azimuth on the other side of the main lobe) the quad's "quartering lobe" is down only some 17 dB, setting the worst-case F/R at 17 dB also. As explained in Chapter 11, the reason F/R is more important than just the F/B is that on receive signals can come from any direction, not just from directly behind the main beam.

Table 1 lists the dimensions for the three computer-optimized monoband quads shown in Figs 2, 3 and 4.

Table 1
Dimensions for Optimized Monoband Quads in Figs 2, 3 and 4, on 26-Foot Booms

	14.2 MHz	*21.2 MHz*	*28.4 MHz*
Reflector	73′ 9"	49′ 6"	37′ 3"
R-DE Spacing	17′ 8"	7′	6′ 4"
Driven Element	71′ 8"	47′ 6"	35′ 9"
DE-D1 Spacing	8′ 3"	5′	5′ 6"
Director 1	68′ 7"	46′ 8"	34′ 8"
D1-D2 Spacing	—	6′ 8"	6′ 9"
Director 2	—	46′ 10"	35′ 2"
D2-D3 Spacing	—	7′ 4"	7′ 5"
Director 3	—	45′ 8"	34′ 2"
Feed method	Direct 50 Ω	Direct 50 Ω	Direct 50 Ω

Is a Quad Better at Low Heights than a Yagi?

Another belief held by some quads enthusiasts is that they need not be mounted very high off the ground to give excellent DX performance. Quads are somehow supposed to be greatly superior to a Yagi at the same height above ground. Unfortunately, this is mainly wishful thinking.



Fig 6—A comparison on 10 meters between an optimized five-element quad and an optimized five-element Yagi, both mounted 50 feet high over flat ground and both employing 26-foot booms. There is no appreciable difference in the peak elevation angle for either antenna. In other words, a quad does not have an appreciable elevation-angle advantage over a Yagi mounted at the same boom height. Note that the quad achieves its slightly higher gain by taking energy from higher-angle lobes and concentrating that energy in the main elevation lobe. This is a process that is similar to what happens with stacked Yagis.

Fig 6 compares the same two 10-meter antennas as in Fig 3, but this time with each one mounted on a 50-foot tower over flat ground, rather than in theoretical free space. The quad does indeed have slightly more gain than a Yagi with the same boom length, as it has in free space. This is evidenced by the very slight compression of the quad's main lobe, but is more obvious when you look at the third lobe, which peaks at about 53° elevation. In effect, the quad squeezes some energy out of its second and third lobes and adds that to the first lobe. However, the difference in gain compared to the Yagi is only 0.8 dB for this particular quad design at a 9° elevation angle. And while it's true that every dB counts, you can also be certain that on the air you wouldn't be able to tell the difference between the two antennas. After all, a 10- to 20-dB variation in the level of signals is pretty common because of fading at HF.

Multiband Quads

On the other hand, one of the valid reasons quads have remained popular over the years is that antenna homebrewers can build multiband quads far more easily than they can construct multiband Yagis. In effect, all you have to do with a quad is add more wire to the existing support arms. It's not quite as simple as that, of course, but the idea of ready expandability for other bands is very appealing to experimenters.

Like the Yagi, the quad does suffer from interactions between wires of different frequencies, but the degree of interaction between bands is usually less for a quad. The higher-frequency bands are the ones that often suffer most from any interaction, for both Yagis and quads. For example, the 10- and 15-meter bands are usually the ones affected most by nearby 20-meter wires in a triband quad, while the 20-meter elements are not affected by the 10- or 15-meter elements.

Modern computer modeling software can help you counteract at least some of the interaction by allowing you to do virtual "retuning" of the quad on the computer screen — rather than clinging precariously to your tower fiddling with wires. However, the programs (such as *NEC-2* or *EZNEC*) that can model three-dimensional wire antennas such as quads typically run far more slowly than those designed for monoband Yagis (such as *YW* included with this book). This makes optimizing rather tedious, but you use the same considerations for tradeoffs between gain, pattern (F/R) and SWR over the operating bandwidth as you do with monoband Yagis.

CONSTRUCTING A QUAD

The parasitic element shown in Fig 1 is tuned in much the same way as the parasitic element in a Yagi antenna. That is, the parasitic loop is tuned to a lower frequency than the driven element when the parasitic is to act as a reflector, and to a higher frequency when it is to act as a director. Fig 1 shows the parasitic element with an adjustable tuning stub, a convenient method of tuning since the resonant frequency can be changed simply by changing the position of the shorting bar on the stub. In practice, it has been found that the length around the loop should be approximately 3.5% greater than the self-resonant length if the element is a reflector, and about 3.0% shorter than the self-resonant length if the parasitic element is a director. Approximate formulas for the loop lengths in feet are:

$$\text{Driven Element} = \frac{1008}{f_{\text{MHz}}}$$

$$\text{Reflector} = \frac{1045}{f_{\text{MHz}}}$$

$$\text{Director} = \frac{977}{f_{\text{MHz}}}$$

These are valid for quad antennas intended for operation below 30 MHz and using uninsulated #14 stranded copper wire. At VHF, where the ratio of loop circumference to conductor diameter is usually relatively small, the circumference must be increased in comparison to the wavelength. For example, a one-wavelength loop constructed of $^1/_4$-inch tubing for 144 MHz should have a circumference about 2% greater than in the above equation for the driven element.

Element spacings on the order of 0.14 to 0.2 free-space wavelengths are generally used. You would employ the smaller spacings for antennas with more than two elements, where the structural support for elements with larger spacings tends to become challenging. The feed-point impedances of antennas having element spacings on this order have been found to be in the 40- to 60-Ω range, so the driven element can be fed directly with coaxial cable with only a small mismatch.

For spacings on the order of 0.25 wavelength (physically feasible for two elements, or for several elements at 28 MHz) the impedance more closely approximates the impedance of a driven loop alone—that is, 80 to 100 Ω. The feed methods described in Chapter 26 can be used, just as in the case of the Yagi.

Making It Sturdy

The physical sturdiness of a quad is directly proportional to the quality of the material used and the care with which it is constructed. The size and type of wire selected for use with a quad antenna is important because it will determine the capability of the spreaders to withstand high winds and ice. One of the more common problems confronting the quad owner is that of broken wires. A solid conductor is more apt to break than stranded wire under constant flexing conditions. For this reason, stranded copper wire is recommended. For 14-, 21- or 28-MHz operation, #14 or #12 stranded wire is a good choice. Soldering of the stranded wire at points where flexing is likely to occur should be avoided.

You may connect the wires to the spreader arms in many ways. The simplest method is to drill holes through the fiberglass at the appropriate points on the arms and route the wires through the holes. Soldering a wire loop across the spreader, as shown later, is recommended. However, you should take care to prevent solder from flowing to the corner point where flexing could break it.

While a boom diameter of 2 inches is sufficient for smaller quads using two or even three elements for 14, 21 and 28 MHz, when the boom length reaches 20 feet or longer a 3-inch diameter boom is highly recommended. Wind creates two forces on the boom, vertical and horizontal. The vertical load on the boom can be reduced with a guy-wire truss cable. The horizontal forces on the boom are more difficult to relieve, so 3-inch diameter tubing is desirable.

Generally speaking, three grades of material can be used for quad spreaders. The least expensive material is bamboo. Bamboo, however, is also the weakest material normally used for quad construction. It has a short life, typically only three or four years, and will not withstand a harsh climate very well. Also, bamboo is heavy in contrast to fiberglass, which weighs only about a pound per 13-foot length. Fiberglass is the most popular type of spreader material, and will withstand normal winter climates. One step beyond the conventional fiberglass arm is the pole-vaulting arm. For quads designed to be used on 7 MHz, surplus "rejected" pole-vaulting poles are highly recommended. Their ability to withstand large amounts of bending is very desirable. The cost of these poles is high, and they are difficult to obtain. See Chapter 21 for dealers and manufacturers of spreaders.

Diamond or Square?

The question of how to orient the spreader arms has been raised many times over the years. Should you mount the loops in a diamond or a square configuration? Should one set of spreaders be horizontal to the earth as shown in Fig 1 (right), or should the wire itself be horizontal to the ground (spreaders mounted in the fashion of an X) as shown in Fig 1 (left)? From the electrical point of view, there is not enough difference in performance to worry about.

From the mechanical point of view there is no question which version is better. The diamond quad, with the associated horizontal and vertical spreader arms, is capable of holding an ice load much better than a system where no vertical support exists to hold the wire loops upright. Put another way, the vertical poles of a diamond array, if sufficiently strong, will hold the rest of the system erect. When water droplets are accumulating and forming into ice, it is very reassuring to see water running down the wires to a corner and dripping off, rather than just sitting there on the wires and freezing. The wires of a loop (or several loops, in the case of a multiband antenna) help support the horizontal spreaders under a load of ice. A square quad will droop severely under heavy ice conditions because there is nothing to hold it up straight.

Of course, in climates where icing is not a problem, many amateurs point out that they like the aesthetics of the square configuration. There are thousands of square-configuration quads in temperate areas around the world.

Another consideration will enter into your choice of orientation for a quad. You must mount a diamond quad somewhat higher on the mast or tower than for an equivalent square array, just to keep the bottom spreader away from the tower guys when you rotate the antenna.

Two Multiband Quads

This section describes two multiband quad designs. The first is a large triband 20/15/10-meter quad built on a 26-foot boom made of 3-inch irrigation tubing. This antenna has three elements on 20 meters, four elements on 15 meters, and five elements on 10 meters. **Fig 7** shows a photograph of the five-element triband quad.

The second project is a compact two-element triband quad on an 8-foot boom that covers 20, 17, 15, 12 and 10 meters. We call this a "pentaband" quad since it covers five bands. This antenna uses five concentric wire loops mounted on each of the two sets of spreaders. Either antenna may be constructed in a diamond or square configuration.

While the same basic construction techniques are employed for both multiband quads, the scale of the larger triband antenna makes it a far more ambitious undertaking! The large quad requires a strong tower and a rugged rotator. It also requires a fair amount of real estate in order to raise the quad to the top of the tower without entangling trees or other antennas.

A FIVE-ELEMENT, 26-FOOT BOOM TRIBAND QUAD

Five sets of element spreaders are used to support the three elements used on 14 MHz, four elements on 21 MHz and five elements on 28-MHz. We chose to use four elements on 15 meters in this design (rather than the five we could have been employed on this length of boom) because the difference in optimized performance wasn't great enough to warrant the extra complexity of using five elements. The dimensions are listed in **Table 2**, and are designed for center frequencies of 14.175, 21.2 and 28.4 MHz.

The spacing between elements has been chosen to provide good compromises in performance consistent with boom length and mechanical construction. You can see that the element spacings for 20 meters are quite different from those for the optimized monoband design. This is because the same set of spreaders is used for all



Fig 7—Photo of the three-band, five-element quad antenna.


14 – MHz Director
21 – MHz Second Director
28 – MHz Third Director
21 – MHz
First Director
28 – MHz
Second Director
14 – 21 – MHz
Driven Element
28 – MHz
First Director
28 – MHz
Driven Element
14 – 21 – 28 – MHz
Reflector
Direction of
Maximum
Radiation
C
G
L
K
F
J
E
B
I
A
D
H
7′
7′
6′
6′

Fig 8—Layout for the three-band, five-element quad, not drawn to scale. See Table 2 for dimensions.

three bands on three out of the five elements, and the higher-frequency bands dictate the spacing because they are more critical.

Each of the parasitic loops is closed (ends soldered together) and requires no tuning. **Fig 8** shows the physical layout of the triband quad. **Fig 9** plots the computed free-space gain, front-to-rear ratio and SWR response across the 20-meter band. With only a few degrees of freedom in tuning and spacing of the three elements, it is impossible to spread the response out to cover the entire 20-meter band. The compromise design results in a rearward pattern that varies from a worst-case of just under 10 dB at the high end of the band, to a peak F/R of just under 19 dB at 14.2 MHz, in the phone portion of the band. The F/R is about 11 dB at the low end of the band.

The SWR remains under 3:1 for the entire 20-meter band, rising to 2.8:1 at the high end. The feed system for this triband quad consists of three separate 50-Ω coax

Table 2
Three-Band Five-Element Quad on 26-Foot Boom

	14.15 MHz	*21.2 MHz*	*28.4 MHz*
Reflector	72′ 6"	49′ 4"	36′ 8"
R-DE Spacing	12′	12′	6′
Driven Element	71′	47′ 6"	35′ 4"
DE-D1 Spacing	14′	7′	6′
Director 1	68′ 6"	46′ 8"	34′ 8"
D1-D2 Spacing	—	14′	7′
Director 2	—	46′ 5"	34′ 8"
D2-D3 Spacing	—	—	7′
Director 3	—	—	34′
Feed method	Direct 50 Ω	Direct 50 Ω	Direct 50 Ω



Fig 9—Computed performance of the triband, five-element quad over the 20-meter band. The direct 50-Ω feed system holds the SWR below 2.8: 1 across the whole band. This could be improved with a gamma-match system tuned to 14.1 MHz if the builder really desires a low SWR. The F/R peaks at 14.1 MHz and remains above 10 dB across the whole band.

lines, one per driven element, together with a relay switchbox mounted to the boom so that a single coax can be used back to the operating position. Each feed line uses a ferrite-bead balun to control common-mode currents and preserve the radiation pattern and each coax going to the switchbox is cut to be an electrical three-quarter wavelength on 15 meters. This presents a short at the unused driven elements since modeling indicated that the 15-meter band is adversely affected by the presence of the 20-meter driven element if it is left open-circuited. If you use RG-213 coax, the $^{3}/_{4}$-λ electrical length of each feed line is 23 feet long at 21.2 MHz. This is sufficient physical length to reach each driven element from the switchbox.

Fig 10 shows the free-space response for the 15-meter band. The rearward response is roughly 15 dB across the band. This is a result of the residual interaction between the 20-meter elements on 15 meters, and no further tuning could improve the F/R. Note how flat the SWR curve is. This SWR characteristic is what gives the quad the reputation of being "wideband." A flat SWR curve, however, is not necessarily a good indicator of optimal performance for directional antennas like quads or Yagis, particularly multiband designs where compromises must be made by physical necessity.

Fig 11 shows the characteristics of the 10-meter portion of the two-element triband quad. The response favors the low-phone band, with the F/R falling to about 12 dB at the low end of the frequency range and rising to just about 23 dB at 28.4 MHz. The SWR curve is once again relatively flat across the major portion of the band up to 28.8 MHz.

Construction

The most obvious problem related to quad antennas is the ability to build a structurally sound system. If high winds or heavy ice are a normal part of the environment, special precautions are necessary if the antenna is to survive a winter season. Another stumbling block for would-be quad builders is the installation of a three-dimensional system (assuming a Yagi has only two important dimensions) on top of a tower—especially if the tower needs guy wires for support. With proper planning, however, many of these obstacles can be overcome. For example, a tram system may be used.

Both multiband quad arrays use fiberglass spreaders (see Chapter 21 for suppliers). Bamboo is a suitable substitute (if economy is of great importance). However, the additional weight of the bamboo spreaders over fiberglass is an important consideration. A typical 12-foot bamboo pole weighs about 2 pounds; the fiberglass type weighs less than a pound. By multiplying the difference times 8 for a two-element array, times 12 for a three-element antenna, and so on, it quickly becomes apparent that fiberglass is worth the investment if weight is an important factor. Properly treated, bamboo has a useful life of three or four years, while fiberglass life is probably 10 times longer.

Spreader supports (sometimes called *spiders*) are available from many different manufacturers. If the builder is keeping the cost at a minimum, he should consider building his own. The expense is about half that of a commercially manufactured equivalent and, according to some authorities, the homemade arm supports described below are less likely to rotate on the boom as a result of wind pressure.

A 3-foot length of steel angle stock, 1 inch per side, is used to interconnect the pairs of spreader arms. The steel is drilled at the center to accept a muffler clamp of sufficient size to clamp the assembly to the boom. The fiberglass is clamped to the steel angle stock with auto-



Fig 10—Computed performance of the triband, five-element quad over the 15-meter band. There is some degree of interaction with the 20-meter elements, limiting the worst-case F/R to about 15 dB. The gain and SWR curves are relatively flat across the band.



Fig 11—Computed performance of the triband, five-element quad over the 10-meter band. The F/R is higher than 12 dB across the band from 28.0 to 29.0 MHz, but the SWR rises at the top end of the band beyond 2:1. The free-space gain is higher than 10 dBi across the band.


Fiberglass Arm
Angle Steel
Mounting Holes for Muffler Clamp
Hose Clamps
Fiberglass Arm

Fig 12—Details of one of two assemblies for a spreader frame. The two assemblies are joined back-to-back to form an X with a muffler clamp mounted at the position shown.


Element Loop Wire
Solder
Solder
Wire Element
Nylon line wrapped tightly and covered with electrical tape
Fiberglass Arm

Fig 14—An alternative method of assembling the wire of a quad loop to the spreader arm.


Element Loop Wire
Solder in Place
Wrap Wire
Hole Drilled Through Fiberglass
Fiberglass Arm

Fig 13—A method of assembling a corner of the wire loop of a quad element to the spreader arm.


120 V AC Control
K1B
K2B
K1A
K2A
14 MHz
28 MHz
Input
21 MHz

Fig 15—Suitable circuit for relay switching of bands for the three-band quad. A three-wire control cable is required. K1, K2—any type of relay suitable for RF switching, coaxial type not required (Potter and Brumfeld MR11A acceptable; although this type has double-pole contacts, mechanical arrangements of most single-pole relays make them unacceptable for switching of RF).

motive hose clamps, two per pole. Each quad-loop spreader frame consists of two assemblies of the type shown in **Fig 12**.

Connecting the wires to the fiberglass can be done in a number of different ways. Holes can be drilled at the proper places on the spreader arms and the wires run through them. A separate wrap wire should be included at the entry/exit point to prevent the loop from slipping. Details are presented in **Fig 13**. Some amateurs have experienced cracking of the fiberglass, which might be a result of drilling holes through the material. However, this seems to be the exception rather than the rule. The model described here has no holes in the spreader arms; the wires are attached to each arm with a few layers of



Fig 16—The relay box is mounted on the boom near the center. Each of the spreader-arm fiberglass poles is attached to steel angle stock with hose clamps.

plastic electrical tape and then wrapped approximately 20 times in a crisscross fashion with $^{1}/_{8}$-inch diameter nylon string, followed by more electrical tape for UV protection, as shown in **Fig 14**.

The wire loops are left open at the bottom of each driven element where the feed-line coaxes are attached. All of the parasitic elements are continuous loops of wire; the solder joint is at the base of the diamond.

Although you could run three separate coax cables down to the shack, we suggest that you install a relay box at the center of the boom. A three-wire control system may be used to apply power to the proper relay for changing bands. The circuit diagram of a typical configuration is presented in **Fig 15** and its installation is shown in **Fig 16**.

Every effort must be placed upon proper construction if you want to have freedom from mechanical problems. Hardware must be secure or vibration created by the wind may cause separation of assemblies. Solder joints should be clamped in place to keep them from flexing, which might fracture a connection point.

A TWO-ELEMENT, 8-FOOT BOOM PENTABAND QUAD

This two-element pentaband (20/17/15/12/10-meter) quad uses the same construction techniques as its big brother above. Since only two elements are used, the boom can be less robust for this antenna, at 2 inches diameter rather than 3 inches. Those who like really rugged antennas can still use the 3-inch diameter boom, of course.

Table 3 lists the element dimensions for the pentaband quad. The following plots show the performance for each of the five bands covered. The feed system for the pentaband quad uses five, direct 50-Ω coaxes, one to each driven element. These five coaxes are cut to be $^{3}/_{4}$-λ electrically on 10 meters (17 feet, 2 inches for RG-213 at 28.4 MHz). In this design the 10-meter band is the one most affected by the presence of the other driven elements if they are left unshorted. The $^{3}/_{4}$-λ lines open-circuited at the switchbox are long enough physically to reach all elements from a centrally mounted switchbox. This length assumes that the switchbox open-circuits the unused coaxes. If the switchbox short-circuits unused coaxes (as several commercial switchboxes do), then use $^{1}/_{2}$-λ long lines to feed all five driven elements (11 feet,



Fig 17—Computed performance of the pentaband two-element quad on 20 meters. With the simple direct-feed system, the SWR rises to about 2.3:1 at the low end of the band. A gamma match can bring the SWR down to 1:1 at 14.1 MHz, if desired.

Table 3
Five-Band Two-Element Quad on 8-Foot Boom

	14.2 MHz	*18.1 MHz*	*21 MHz*	*24.9 MHz*	*28.4 MHz*
Reflector	72′ 4"	56′ 4"	48′ 6"	40′ 11$^{1}/_{4}$"	37′ 5$^{1}/_{2}$"
R-DE Spacing	8′	8′	8′	8′	8′
Driven Element	69′ 10$^{1}/_{2}$"	54′ 10$^{1}/_{2}$"	46′ 7"	39′ 10$^{1}/_{2}$"	34′ 6"

5 inches for RG-213 at 28.4 MHz).

The SWR curves do not necessarily go down to 1:1 because of this simple, direct feed system. If anyone is bothered by this, of course they can always implement individual matching systems, such as gamma matches. Most amateurs would agree that such a degree of complexity is not warranted. The worst-case SWR is less than 2.3:1 on each band, even with direct feed on 20 meters. With typical lengths of coaxial feed line from the shack to the switchbox at the antenna, say 100 feet of RG-213, the SWR at the transmitter would be less than 2.0:1 on all bands due to losses in the feed line.

Fig 17 shows the computed responses for the pentaband quad over the 20-meter band. With only two degrees of freedom (spacing and element tuning) there is not much that can be done to spread the response out over the entire 20-meter band. Nonetheless, the performance over the band is still pretty reasonable for an antenna this small. The F/R pattern peaks at 19 dB at 14.1 MHz and falls to about 10 dB at either end of the band. The free-space gain varies from about 7.5 dBi to just above 6 dBi, comparable to a short-boom three-element Yagi. The SWR curve remains below 2.3:1 across the band. If you were to employ a gamma match tuned at 14.1 MHz, you could limit the peak SWR to less than 2.0:1, and this would still occur at 14.0 MHz.



Fig 18—Computed performance of the pentaband two-element quad on 17 meters. There is some interaction with the other elements, but overall the performance is satisfactory on this band.



Fig 19—Computed performance of the pentaband two-element quad on 15 meters. The performance is acceptable across the whole band.



Fig 20—Computed performance of the pentaband two-element quad on 12 meters.



Fig 21—Computed performance of the pentaband two-element quad on 10 meters. The SWR curve is slightly above the target 2:1 at the low end of the band and rises to about 2.2:1 at 28.8 MHz. This unlikely to be a problem, even with rigs with automatic power-reduction due to SWR, since the SWR at the input of a typical coax feed line will be lower than that at the antenna due to losses in the line.

On 17 meters, **Fig 18** shows that the other elements are affecting 18 MHz, even with element-length optimization. Careful examination of the current induced on the other elements shows that the 20-meter driven element is interacting on 18 MHz, deteriorating the pattern and gain slightly. Even still, the performance on 17 meters is reasonable, especially for a five-band quad on an 8-foot boom.

On 15 meters, the interactions seems to have been contained, as **Fig 19** demonstrates. The F/R peaks at 21.1 MHz, at 19 dB and remains better than 12 dB past the top of the band. The SWR curve is low across the whole band.

On 12 meters, the interaction between bands is minor, leading to the good results shown in **Fig 20**. The SWR change across this band is quite flat, which isn't surprising given the narrow bandwidth of the 12-meter band.

On 10 meters, the interaction seems to have been tamed well by computer-tuning of the elements. The F/R remains higher than about 14 dB from 28 to 29 MHz. The SWR remains below 2.2:1 up to about 28.8 MHz, while the gain is relatively flat across the band at more than 7.2 dBi in free space. See **Fig 21**.

Overall, this pentaband quad is physically compact and yet it provides good performance across all five bands. It is competitive with commercial Log Periodic Dipole Array (LPDA) designs and triband Yagi designs that employ longer booms.

BIBLIOGRAPHY

Source material and more extended discussions of the topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2.

P. S. Carter, C. W. Hansell and N. E. Lindenblad, "Development of Directive Transmitting Antennas by R.C.A. Communications," *Proc. IRE*, Oct 1931.

C. Cleveland, "More'n One Way to Switch an Antenna," Technical Correspondence, *QST*, Nov 1986.

D. Cutter, "Simple Switcher," *73*, May 1980.

D. DeMaw, "A Remote Antenna Switcher for HF," *QST*, Jun 1986.

M. G. Knitter, Ed., *Loop Antennas—Design and Theory* (Cambridge, WI: National Radio Club, 1983).

H. Landskov, W7KAR, "Evolution of a Quad Array," *QST*, Mar 1977.

J. Lindsay, "Quads and Yagis," *QST*, May 1968.

F. E. Terman, *Radio Engineering*, 3rd ed. (New York: McGraw-Hill Book Co, 1947).

E. M. Williams, "Radiating Characteristics of Short-Wave Loop Aerials," *Proc. IRE*, Oct 1940.

Chapter 13

Long-Wire and Traveling-Wave Antennas

The power gain and directive characteristics of electrically long wires (that is, wires that are long in terms of wavelength), as described in Chapter 2, make them useful for long-distance transmission and reception on the higher frequencies. Long wires can be combined to form antennas of various shapes that increase the gain and directivity over a single wire. The term *long wire*, as used in this chapter, means any such configuration, not just a straight-wire antenna.

Long Wires Versus Multielement Arrays

In general, the gain obtained with long-wire antennas is not as great, when the space available for the antenna is limited, as you can obtain from the multielement phased arrays in Chapter 8 or from a parasitic array such as a Yagi or quad (Chapters 11 or 12). However, the long-wire antenna has advantages of its own that tend to compensate for this deficiency. The construction of long-wire antennas is simple both electrically and mechanically, and there are no especially critical dimensions or adjustments. The long-wire antenna will work well and give satisfactory gain and directivity over a 2-to-1 frequency range. In addition, it will accept power and radiate well on any frequency for which its overall length is not less than about a half wavelength. Since a wire is not electrically long, even at 28 MHz, unless its physical length is equal to at least a half wavelength on 3.5 MHz, any long-wire can be used on all amateur bands that are useful for long-distance communication.

Between two directive antennas having the same theoretical gain, one a multielement array and the other a long-wire antenna, many amateurs have found that the long-wire antenna seems more effective in reception. One possible explanation is that there is a *diversity effect* with a long-wire antenna because it is spread out over a large distance, rather than being concentrated in a small space, as would be the case with a Yagi, for example. This may raise the average level of received energy for ionospheric-propagated signals. Another factor is that long-wire antennas have directive patterns that can be extremely sharp in the horizontal (azimuthal) plane. This is an advantage that other types of multielement arrays do not have, but it can be a double-edged sword too. We'll discuss this aspect in some detail in this chapter.

General Characteristics of Long-Wire Antennas

Whether the long-wire antenna is a single wire running in one direction or is formed into a V-beam, rhombic, or some other configuration, there are certain general principles that apply and some performance features that are common to all types. The first of these is that the power gain of a long-wire antenna as compared with a half-wave dipole is not considerable until the antenna is really long (its length measured in wavelengths rather than in a specific number of feet). The reason for this is that the fields radiated by elementary lengths of wire along the antenna do not combine, at a distance, in as simple a fashion as the fields from half-wave dipoles used in other types of directive arrays.

There is no point in space, for example, where the distant fields from all points along the wire are exactly in phase (as they are, in the optimum direction, in the case of two or more collinear or broadside dipoles when fed with in-phase currents). Consequently, the field strength at a distance is always less than would be obtained if the same length of wire were cut up into properly phased and separately driven dipoles. As the wire is made longer, the fields combine to form increasingly intense main lobes, but these lobes do not develop appreciably until the wire is several wavelengths long. See **Fig 1**.

The longer the antenna, the sharper the lobes become, and since it is really a hollow cone of radiation about the wire in free space, it becomes sharper in both planes. Also, the greater the length, the smaller the angle with the wire at which the maximum radiation lobes occur. There are four main lobes to the directive patterns of long-wire antennas; each makes the same angle with respect to the wire.

Fig 2A shows the azimuthal radiation pattern of a 1-λ long-wire antenna, compared with a $^1/_2$-λ dipole. Both antennas are mounted at the same height of 1 λ above flat ground (70 feet high at 14 MHz, with a wire length of 70 feet) and both patterns are for an elevation angle of 10°, an angle suitable for long-distance communication on 20 meters. The long-wire in Fig 2A is oriented in the 270° to 90° direction, while the dipole is aligned at right angles so that its characteristic figure-8 pattern goes left-to-right. The 1-λ long-wire has about 0.6 dB more gain than the dipole, with four main lobes as compared to the two lobes from the dipole.

You can see that the two lobes on the left side of Fig 2A are about 1 dB down compared to the two lobes on the right side. This is because the long-wire here is fed at the left-hand end in the computer model. Energy is radiated as a wave travels down the wire and some energy is also lost to ohmic resistance in the wire and the ground. The forward-going wave then reflects from the open-circuit at the right-hand end of the wire and reverses direction, traveling toward the left end, still radiating as it



Fig 1—Theoretical gain of a long-wire antenna, in dBi, as a function of wire length. The angle, with respect to the wire, at which the radiation intensity is maximum also is shown.



(A)

(B)

Fig 2—At A, comparison of azimuthal patterns for a 1-λ long-wire antenna (solid line) and a ½-λ dipole (dashed line) at an elevation angle of 10°. Each antenna is located 1 λ (70 feet) over flat ground at 14 MHz. At B, the elevation-plane patterns at peak azimuth angles for each antenna. The long-wire has about 0.6 dB more gain than the dipole.

travels. An antenna operating in this way has much the same characteristics as a transmission line that is terminated in an open circuit—that is, it has standing waves on it. Unterminated long-wire antennas are often referred to as *standing wave antennas*. As the length of a long-wire antenna is increased, a moderate front-to-back ratio results, about 3 dB for very long antennas.

Fig 2B shows the elevation-plane pattern for the long-wire and for the dipole. In each case the elevation pattern is at the azimuth of maximum gain—at an angle of 38° with respect to the wire-axis for the long-wire and at 90° for the dipole. The peak elevation for the long-wire is very slightly lower than that for the dipole at the same height above ground, but not by much. In other words, the height above ground is the main determining factor for the shape of the main lobe of a long-wire's elevation pattern, as it is for most horizontally polarized antennas.

The shape of the azimuth and elevation patterns in Fig 2 might lead you to believe that the radiation pattern is simple. **Fig 3** is a 3-D representation of the pattern from a 1-λ long-wire that is 1 λ high over flat ground. Besides the main low-angle lobes, there are strong lobes at higher angles. Things get even more complicated when the length of the long-wire increases.

Directivity

Because many points along a long wire are carrying currents in different phases (with different current amplitudes as well), the field pattern at a distance becomes more complex as the wire is made longer. This complexity is manifested in a series of minor lobes, the number of which increases with the wire length. The intensity of radiation from the minor lobes is frequently as great as, and sometimes greater than, the radiation from a half-wave dipole. The energy radiated in the minor lobes is not available to improve the gain in the major lobes, which is another reason why a long-wire antenna must be long to give appreciable gain in the desired directions.

Fig 4 shows an azimuthal-plane comparison between a 3-λ (209 feet long) long-wire and the comparison $^1/_2$-λ dipole. The long-wire now has 8 minor lobes besides the four main lobes. Note that the angle the main lobes make with respect to the axis of the long-wire (also left-to-right in Fig 4) becomes smaller as the length of the long-wire increases. For the 3-λ long-wire, the main lobes occur 28° off the axis of the wire itself.

Other types of simple driven and parasitic arrays do not have minor lobes of any great consequence. For that reason they frequently seem to have much better directivity than long-wire antennas, because their responses in undesired directions are well down from their response in the desired direction. This is the case even if a multielement array and a long-wire antenna have the same peak gain in the favored direction. **Fig 5** compares the same 3-λ long-wire with a 4-element Yagi and a ½-λ dipole, again both at the same height as the long-wire. Note that the Yagi has only a single backlobe, down about 21 dB from its broad main lobe, which has a 3-dB beamwidth of 63°. The 3-dB beamwidth of the long-wire's main lobes (at a 28° angle from the wire axis) is far more narrow, at only 23°.

For amateur work, particularly with directive antennas that cannot be rotated, the minor lobes of a long-wire antenna have some advantages. Although the nulls in the



Fig 3—A 3-D representation of the radiation pattern for the 1-λ long-wire shown in Fig 2. The pattern is obviously rather complex. It gets even more complicated for wires longer than 1 λ.



Fig 4—An azimuthal-plane comparison between a 3-λ (209 feet long) long-wire (solid line) and the comparison ½-λ dipole (dashed line) at 70 feet high (1 λ) at 14 MHz.



Fig 5—A comparison between the 3-λ long-wire (solid line) in Fig 4, a 4-element 20-meter Yagi on a 26-foot boom (dotted line), and a ½-λ dipole (dashed line), again at a height of 70 feet. The main lobes of the long-wire are very narrow compared to the wide frontal lobe of the Yagi. The long-wire exhibits an azimuthal pattern that is more omnidirectional in nature than a Yagi, particularly when the narrow, deep nulls in the long-wire's pattern are filled-in due to irregularities in the terrain under its long span of wire.

computer model in Fig 5 are deeper than 30 dB, they are not so dramatic in actual practice. This is due to irregularities in the terrain that inevitably occur under the span of a long wire. In most directions the long-wire antenna will be as good as a half-wave dipole, and in addition will give high gain in the most favored directions, even though that is over narrow azimuths.

Fig 6A compares the azimuth responses for a 5-λ long-wire (350 feet long at 14 MHz) to the same 4-element Yagi and dipole. The long-wire now exhibits 16 minor lobes in addition to its four main lobes. The peaks of these sidelobes are down about 8 dB from the main lobes and they are stronger than the dipole, making this long-wire antenna effectively omnidirectional. Fig 6B shows the elevation pattern of the 5-λ long-wire at its most effective azimuth compared to a dipole. Again, the shape of the main lobe is mainly determined by the long-wire's height above ground, since the peak angle is only just a bit lower than the peak angle for the dipole. The long-wire's elevation response breaks up into numerous lobes above the main lobes, just as it does in the azimuth plane.

For the really ambitious, **Fig 7** compares the performance for an 8-λ (571 feet) long-wire antenna with a 4-element Yagi and the $^1/_2$-λ dipole. Again, in actual practice, the nulls would tend to be filled in by terrain irregularities, so a very long antenna like this would be a pretty potent performer.

Calculating Length

In this chapter, lengths are discussed in terms of wave-



(A)

(B)

Fig 6—At A, the azimuth responses for a 5-λ long-wire (350 feet long at 14 MHz—solid line) to the same 4-element Yagi (dotted line) and dipole (dashed line) as in Fig 5. At B, the elevation-plane responses for the long-wire (solid line) and the dipole (dashed line) by themselves. Note that the elevation angle giving peak gain for each antenna is just about the same. The long-wire achieves gain by compressing mainly the azimuthal response, squeezing the gain into narrow lobes; not so much by squeezing the elevation pattern for gain.



Fig 7—The azimuthal-plane performance for an 8-λ (571 feet) long-wire antenna (solid line), compared with a 4-element Yagi (dotted line) and a ½-λ dipole (dashed line).

lengths. Throughout the preceding discussion the frequency in the models was held at 14 MHz. Remember that a long-wire that is 4 λ long at 14 MHz is 8 λ long at 28 MHz.

There is nothing very critical about wire lengths in an antenna system that will work over a frequency range including several amateur bands. The antenna characteristics change very slowly with length, except when the wires are short (around one wavelength, for instance). There is no need to try to establish exact resonance at a particular frequency for proper antenna operation.

The formula for determining the lengths for harmonic wires is:

$$\text{Length}\left(\text{feet}\right)=\frac{984\left(\text{N}-0.025\right)}{\text{f}\left(\text{MHz}\right)} \qquad \text{(Eq 1)}$$

where N is the antenna length in wavelengths. In cases where precise resonance is desired for some reason (for obtaining a resistive load for a transmission line at a particular frequency, for example) it is best established by trimming the wire length until the standing-wave ratio on the line is minimum.

Tilted Wires

In theory, it is possible to maximize gain from a long-wire antenna by tilting it to favor a desired elevation takeoff angle. Unfortunately, the effect of real ground under the antenna negates the possible advantages of tilting, just as it does when a Yagi or other type of parasitic array is tilted from horizontal. You would do better keeping a long-wire antenna horizontal, but raising it higher above ground, to achieve more gain at low takeoff angles.



Fig 8—Methods for feeding long single-wire antennas.

Feeding Long Wires

A long-wire antenna is normally fed at the end or at a current loop. Since a current loop changes to a node when the antenna is operated at any even multiple of the frequency for which it is designed, a long-wire antenna will operate as a true long wire on all bands only when it is fed at the end.

A common method of feeding a long-wire is to use a resonant open-wire line. This system will work on all bands down to the one, if any, at which the antenna is only a half wave long. Any convenient line length can be used if you match the transmitter to the line's input impedance using an antenna tuner, as described in Chapter 25.

Two arrangements for using nonresonant lines are given in **Fig 8**. The one at A is useful for one band only since the matching section must be a quarter wave long, approximately, unless a different matching section is used for each band. In B, the λ/4 transformer (Q-section) impedance can be designed to match the antenna to the line, as described in Chapter 26. You can determine the value of radiation resistance using a modern modeling program or you can actually measure the feed-point impedance. Although it will work as designed on only one band, the antenna can be used on other bands by treating the line and matching transformer as a resonant line. In this case, as mentioned earlier, the antenna will not radiate as a true long wire on even multiples of the frequency for which the matching system is designed.

The end-fed arrangement, although the most convenient when tuned feeders are used, suffers the disadvantage that there is likely to be a considerable antenna current on the line. In addition, the antenna reactance changes rapidly with frequency. Consequently, when the wire is several wavelengths long, a relatively small change in frequency—a fraction of the width of a band—may require major changes in the adjustment of the antenna tuner. Also, the line becomes unbalanced at all frequencies between those at which the antenna is resonant. This leads to a considerable amount of radiation from the line. The unbalance can be overcome by using multiple long wires in a V or rhombic shape, as described below.

COMBINATIONS OF LONG WIRES

The directivity and gain of long wires may be increased by using two wires placed in relation to each other such that the fields from both combine to produce the greatest possible field strength at a distant point. The principle is similar to that used in designing the multi-element arrays described in Chapter 8.

Parallel Wires

One possible method of using two (or more) long wires is to place them in parallel, with a spacing of $^1/_2$ λ or so, and feed the two in phase. In the direction of the wires the fields will add in phase. However, the takeoff angle is high directly in the orientation of the wire, and this method will result in rather high-angle radiation even if the wires are several wavelengths long. With a parallel arrangement of this sort the gain should be about 3 dB over a single wire of the same length, at spacings in the vicinity of $^1/_2$ wavelength.

The V-Beam Antenna

Instead of using two long wires parallel to each other, they may be placed in the form of a horizontal V, with the included angle between the wires equal to twice the angle made by the main lobes referenced to the wire axis for a single wire of the same physical length. For example, for a leg length of 5 λ, the angle between the legs of a V should be about 42°, twice the angle of 21° of the main lobe referenced to the long-wire's axis. See Fig 6A.

The plane directive patterns of the individual wires combine along a line in the plane of the antenna and bisecting the V, where the fields from the individual wires reinforce each other. The sidelobes in the azimuthal pattern are suppressed by about 10 dB, so the pattern becomes essentially bidirectional. See **Fig 9**.

The included angle between the legs is not particularly critical. This is fortunate, especially if the same antenna is used on multiple bands, where the electrical length varies directly with frequency. This would normally require different included angles for each band. For multi-band V-antennas, a compromise angle is usually chosen to equalize performance. **Fig 10** shows the azimuthal pattern for a V-beam with 1-λ legs, with an included angle of 75° between the legs, mounted 1 λ above flat ground. This is for a 10° elevation angle. At 14 MHz the antenna has two 70-foot high, 68.5-foot long legs, separated at their far ends by 83.4 feet. For comparison the azimuthal patterns for the same 4-element Yagi and ½-λ dipole used previously for the long-wires are overlaid on the same plot. The V has about 2 dB more gain than the dipole but is down some 4 dB compared to the Yagi, as expected for relatively short legs.

Fig 11 shows the azimuthal pattern for the same antenna in Fig 10, but at 28 MHz and at an elevation angle of 6°. Because the legs are twice as long electrically at 28 MHz, the V-beam has compressed the main lobe into a narrow beam that now has a peak gain equal to the Yagi, but with a 3-dB beamwidth of only 18.8°. Note that you could obtain about 0.7 dB more gain at 14 MHz, with a 1.7-dB degradation of gain at 28 MHz, if you increase the included angle to 90° rather than 75°.

Fig 12 shows the azimuthal pattern for a V-beam with 2-λ legs (137 feet at 14 MHz), with an included angle of 60° between them. As usual, the assumed height is 70 feet, or 1 λ at 14 MHz. The peak gain for the V-beam is just about equal to that of the 4-element Yagi, although the 3-dB



Fig 9—Two long wires and their respective patterns are shown at the left. If these two wires are combined to form a V with an angle that is twice that of the major lobes of the wires and with the wires excited out of phase, the radiation along the bisector of the V adds and the radiation in the other directions tends to cancel.



Fig 10— Azimuthal-plane pattern at 10° elevation angle for a 14-MHz V-beam (solid line) with 1-λ legs (68.5 feet long), using an included angle of 75° between the legs. The V-beam is mounted 1 λ above flat ground, and is compared with a ½-λ dipole (dashed line) and a 4-element 20-meter Yagi on a 26-foot boom (dotted line).



Fig 11—The same V-beam as in Fig 10 at 28 MHz (solid line), at an elevation angle of 6°, compared to a 4-element Yagi (dotted line) and a dipole (dashed line). The V-beam's pattern is very narrow, at 18.8° at the 3-dB points, requiring accurate placement of the supports poles to aim the antenna at the desired geographic target.



Fig 12—Azimuthal pattern for a V-beam (solid line) with 2-λ legs (137 feet at 14 MHz), with an included angle of 60° between them. The height is 70 feet, or 1 λ, over flat ground. For comparison, the response for a 4-element Yagi (dotted line) and a dipole (dashed line) are shown. The 3-dB beamwidth has decreased to 23.0°.

nose beamwidth is narrow, at 23°. This makes setting up the geometry critical if you want to maximize gain into a particular geographic area. While you might be able to get away with using convenient trees to support such an antenna, it's far more likely that you'll have to use carefully located towers to make sure the beam is aimed where you expect it to be pointed.

For example, in order to cover all of Europe from San Francisco, an antenna must cover from about 11° (to Moscow) to about 46° (to Portugal). This is a range of 35° and signals from the V-beam in Fig 12 would be down some 7 dB over this range of angles, assuming the center of the beam is pointed exactly at a heading of 28.5°. The 4-element Yagi on the other hand would cover this range of azimuths more consistently, since its 3-dB beamwidth is 63°.

Fig 13 shows the same V-beam as in Fig 12, but this time at 28 MHz. The peak gain of the main lobe is now about 1 dB stronger than the 4-element Yagi used as a reference, and the main lobe has two nearby sidelobes that tend to broaden out the azimuthal response. At this frequency the V-beam would cover all of Europe better from San Francisco.

Fig 14 shows a V-beam with 3-λ (209 feet at 14 MHz) legs with an included angle of 50° between them. The peak gain is now greater than that of a 4-element Yagi, but the 3-dB beamwidth has been reduced to 17.8°, making aim-



Fig 13—The same 2-λ per leg V-beam (solid line) as in Fig 12, but at 28 MHz and at a 6° takeoff elevation angle. Two sidelobes have appeared flanking the main lobe, making the effective azimuthal pattern wider at this frequency.



Fig 15—The same 209-foot/leg V-beam as Fig 14, but at 28 MHz. Again, the two close-in sidelobes tend to spread out the azimuthal response some at 28 MHz.



Fig 14—A V-beam (solid line) with 3-λ (209 feet at 14 MHz) legs using an included angle of 50° between them, compared to a 4-element Yagi (dotted line) and a dipole (dashed line). The 3-dB beamwidth has now decreased to 17.8°.

ing the antenna even more critical. **Fig 15** shows the same V-beam at 28 MHz. Here again, the main lobe has nearby sidelobes that broaden the effective azimuth to cover a wider area.

Fig 16 shows the elevation-plane response for the same 209-foot leg V-beam at 28 MHz (3-λ at 14 MHz), compared to a dipole at the same height of 70 feet. The higher-gain V-beam suppresses higher-angle lobes, essentially stealing energy from them and concentrating it in the main beam at 6° elevation.

The same antenna can be used at 3.5 and 7 MHz. The gain will not be large, however, because the legs are not very long at these frequencies. **Fig 17** compares the V-beam versus a horizontal ½-λ 40-meter dipole at 70 feet. At low elevation angles there is about 2 dB of advantage on 40 meters. **Fig 18** shows the same type of comparison for 80 meters, where the 80-meter dipole is superior at all angles.

Other V Combinations

A gain increase of about 3 dB can be had by stacking two V-beams one above the other, a half wavelength apart, and feeding them with in-phase currents. This will result in a lowered angle of radiation. The bottom V should be at least a quarter wavelength above the ground, and preferably a half wavelength. This arrangement will narrow the



Fig 16—The elevation-plane of the 209-foot/leg V-beam (solid line) compared to the dipole (dashed line). Again, the elevation angle for peak gain corresponds well to that of the simple dipole at the same height.



Fig 17—Elevation pattern for the same 209-foot-per-leg V-beam (solid line), at 7 MHz, compared to a 40-meter dipole (dashed line) at the same height of 70 feet.

elevation pattern and it will also have a narrow azimuthal pattern.

The V antenna can be made unidirectional by using a second V placed an odd multiple of a quarter wavelength in back of the first and exciting the two with a phase difference of 90º. The system will be unidirectional in the direction of the antenna with the lagging current. However, the V reflector is not normally employed by amateurs at low frequencies because it restricts the use to one band and requires a fairly elaborate supporting structure. Stacked Vs with driven reflectors could, however, be built for the 200- to 500-MHz region without much difficulty.

Feeding the V Beam

The V-beam antenna is most conveniently fed with tuned open-wire feeders with an antenna tuner, since this permits multiband operation. Although the length of the wires in a V-beam is not at all critical, it is important that both wires be the same electrical length. If a single band matching solution is desired, probably the most appropriate matching system is that using a stub or quarter-wave matching section. The adjustment of such a system is described in Chapter 26.



Fig 18—Elevation pattern for the same 209-foot-per-leg V-beam (solid line), at 3.5 MHz, compared to an 80-meter dipole at 70 feet (dashed line).

THE RESONANT RHOMBIC ANTENNA

The diamond-shaped or rhombic antenna shown in **Fig 19** can be looked upon as two acute-angle V-beams placed end-to-end. This arrangement is called a *resonant rhombic*. The leg lengths of the resonant rhombic must be an integral number of half wavelengths to avoid reactance at its feed point.

The resonant rhombic has two advantages over the simple V-beam. For the same total wire length it gives somewhat greater gain than the V-beam. A rhombic with 3 λ on a leg, for example, has about 1 dB gain over a V antenna with 6 wavelengths on a leg. **Fig 20** compares the azimuthal pattern at a 10° elevation for a resonant rhombic with 3 λ legs on 14 MHz, compared to a V-beam with 6 λ legs at the same height of 70 feet. The 3-dB nose beamwidth of the resonant rhombic is only 12.4° wide, but the gain is very high at 16.26 dBi.

The directional pattern of the rhombic is less frequency sensitive than the V when the antenna is used over a wide frequency range. This is because a change in frequency causes the major lobe from one leg to shift in one direction while the lobe from the opposite leg shifts the other way. This automatic compensation keeps the direction the same over a considerable frequency range. The disadvantage of the rhombic as compared with the V-beam is that an additional support is required.

The same factors that govern the design of the V-beam apply in the case of the resonant rhombic. The optimal apex angle A in Fig 19 is the same as that for a V having an equal leg length. The diamond-shaped antenna also can be operated as a terminated antenna, as described later in this chapter, and much of the discus-



Fig 19—The resonant rhombic or diamond-shaped antenna. All legs are the same length, and opposite angles of the diamond are equal. Length ℓ is an integral number of half wavelengths for resonance.



Fig 20—Azimuthal-plane pattern of resonant (unterminated) rhombic (solid line) with 3-λ legs on 14 MHz, at a height of 70 feet above flat ground, compared with a 6-λ per leg V-beam (dashed line) at the same height. Both azimuthal patterns are at a takeoff angle of 10°. The sidelobes for the resonant rhombic are suppressed to a greater degree than those for the V-beam.

sion in that section applies to the resonant rhombic as well.

The resonant rhombic has a bidirectional pattern, with minor lobes in other directions, their number and intensity depending on the leg length. In general, these sidelobes are suppressed better with a resonant rhombic than with a V-beam. When used at frequencies below the VHF region, the rhombic antenna is always mounted with the plane containing the wires horizontal. The polarization in this plane, and also in the perpendicular plane that bisects the rhombic, is horizontal. At 144 MHz and above, the dimensions are such that the antenna can be mounted with the plane containing the wires vertical if vertical polarization is desired.

When the rhombic antenna is to be used on several HF amateur bands, it is advisable to choose the apex angle, A, on the basis of the leg length in wavelengths at 14 MHz. Although the gain on higher frequency bands will not be quite as favorable as if the antenna had been designed for the higher frequencies, the system will still work well at the low angles that are necessary at such frequencies.

The resonant rhombic has lots of gain, but you must not forget that this gain comes from a radiation pattern that is very narrow. This requires careful placement of the supports for the resonant rhombic to cover desired geographic areas. This is definitely not an antenna that allows you to use just any convenient trees as supports!

The resonant rhombic antenna can be fed in the same way as the V-beam. Resonant feeders are necessary if the antenna is to be used in several amateur bands.

TERMINATED LONG-WIRE ANTENNAS

All the antenna systems considered so far in this chapter have been based on operation with standing waves of current and voltage along the wire. Although most hams use antenna designs based on using resonant wires, resonance is by no means a necessary condition for the wire to radiate and intercept electromagnetic waves efficiently, as discussed in Chapter 2. The result of using nonresonant wires is reactance at the feed point, unless the antenna is terminated with a resistive load.

In **Fig 21**, suppose that the wire is parallel with the ground (horizontal) and is terminated by a load Z equal to its characteristic impedance, Z_{ANT}. The wire and its image in the ground create a transmission line. The load Z can represent a receiver matched to the line. The *terminating resistor* R is also equal to the Z_{ANT} of the wire. A wave coming from direction X will strike the wire first at its far end and sweep across the wire at some angle until it reaches the end at which Z is connected. In so doing, it will induce voltages in the antenna, and currents will flow as a result. The current flowing toward Z is the useful output of the antenna, while the current flowing backwards toward R will be absorbed in R. The same thing is true of a wave coming from the direction X'. In such an antenna there are no standing waves, because all received power is absorbed at either end.

The greatest possible power will be delivered to the load Z when the individual currents induced as the wave sweeps across the wire all combine properly on reaching the load. The currents will reach Z in optimum phase when the time required for a current to flow from the far end of the antenna to Z is exactly one-half cycle longer than the time taken by the wave to sweep over the antenna. A half cycle is equivalent to a half wavelength greater than the distance traversed by the wave from the instant it strikes



Fig 21—Layout for a terminated long-wire antenna.



Fig 22—Azimuthal-plane pattern for 5-λ long-wire antenna at 14 MHz and 70 feet above flat ground. The solid line shows the long-wire terminated with 600-Ω to ground, while the dashed line is for the same antenna unterminated. For comparison, the response for a ½-λ dipole is overlaid with the two other patterns. You can see that the terminated long-wire has a good front-to-back pattern, but it loses about 2 dB in forward gain compared to the unterminated long-wire.

the far end of the antenna to the instant that it reaches the near end. This is shown by the small drawing, where AC represents the antenna, BC is a line perpendicular to the wave direction, and AB is the distance traveled by the wave in sweeping past AC. AB must be one-half wavelength shorter than AC. Similarly, AB' must be the same length as AB for a wave arriving from X'.

A wave arriving at the antenna from the opposite direction Y (or Y'), will similarly result in the largest possible current at the far end. However, since the far end is terminated in R, which is equal to Z, all the power delivered to R by the wave arriving from Y will be absorbed in R. The current traveling to Z will produce a signal in Z in proportion to its amplitude. If the antenna length is such that all the individual currents arrive at Z in such phase as to add up to zero, there will be no current through Z. At other lengths the resultant current may reach appreciable values. The lengths that give zero amplitude are those which are odd multiples of $^1/_4$ λ, beginning at $^3/_4$ λ. The response from the Y direction is greatest when the antenna is any even multiple of $^1/_2$ λ long; the higher the multiple, the smaller the response.

Directional Characteristics

Fig 22 compares the azimuthal pattern for a 5-λ long 14-MHz long-wire antenna, 70 feet high over flat ground, when it is terminated and when it is unterminated. The rearward pattern when the wire is terminated with a 600 Ω resistor is reduced about 15 dB, with a reduction in gain in the forward direction of about 2 dB.

For a shorter leg length in a terminated long-wire antenna, the reduction in forward gain is larger—more energy is radiated by a longer wire before the forward wave is absorbed in the terminating resistor. The azimuthal patterns for terminated and unterminated V-beams with 2-λ legs are overlaid for comparison in **Fig 23**. With these relatively short legs the reduction in forward gain is about 3.5 dB due to the terminations, although the front-to-rear ratio approaches 20 dB for the terminated V-beam. Each leg of this terminated V-beam use a 600-Ω non-inductive resistor to ground. Each resistor would have to dissipate about one-quarter of the transmitter power. For average conductor diameters and heights above ground, the Z_{ANT} of the antenna is of the order of 500 to 600 Ω.

THE TERMINATED RHOMBIC ANTENNA

The highest development of the long-wire antenna is the *terminated rhombic*, shown schematically in **Fig 24**. It consists of four conductors joined to form a diamond, or *rhombus*. All sides of the antenna have the same length and the opposite corner angles are equal. The antenna can be considered as being made up of two V antennas placed end to end and terminated by a noninductive resistor to produce a unidirectional pattern. The terminating resistor is connected between the far ends of the two sides, and is made approximately equal to the characteristic impedance of the antenna as a unit. The rhombic may be constructed either horizontally or vertically, but is practically always constructed horizontally at frequencies below 54 MHz,



Fig 23—The azimuthal patterns for a shorter-leg V-beam (2-λ legs) when it is terminated (solid line) and unterminated (dashed line). With shorter legs, the terminated V-beam loses about 3.5 dB in forward gain compared to the unterminated version, while suppressing the rearward lobes as much as 20 dB.



Fig 24—The layout for a terminated rhombic antenna.

since the pole height required is considerably less. Also, horizontal polarization is equally, if not more, satisfactory at these frequencies over most types of soil.

The basic principle of combining lobes of maximum radiation from the four individual wires constituting the rhombus or diamond is the same in either the terminated type or the resonant type described earlier in this chapter.

Tilt Angle

In dealing with the terminated rhombic, it is a matter of custom to talk about the *tilt angle* (ϕ in Fig 24), rather than the angle of maximum radiation with respect to an individual wire. **Fig 25** shows the tilt angle as a function of the antenna leg length. The curve marked "0°" is used for a takeoff elevation angle of 0°; that is, maximum radiation in the plane of the antenna. The other curves show the proper tilt angles to use when aligning the major lobe with a desired takeoff angle. For a 5° takeoff angle, the difference in tilt angle is less than 1° for the range of lengths shown.

The broken curve marked "optimum length" shows the leg length at which maximum gain is obtained at any given takeoff angle. Increasing the leg length beyond the optimum will result in less gain, and for that reason the curves do not extend beyond the optimum length. Note that the optimum length becomes greater as the desired takeoff angle decreases. Leg lengths over 6 λ are not recommended because the directive pattern becomes so sharp that the antenna performance is highly variable with small changes in the angle, both horizontal and vertical, at which an incoming wave reaches the antenna. Since these angles vary to some extent in ionospheric propagation, it does not pay to attempt to try for too great a degree of directivity.

Multiband Design

When a rhombic antenna is to be used over a considerable frequency range, a compromise must be made in the tilt angle. **Fig 26** gives the design dimensions of a suitable compromise for a rhombic that covers the 14 to 30 MHz range well. **Fig 27** shows the azimuth and elevation patterns for this antenna at 14 MHz, at a height of 70 feet over flat ground. The comparison antenna in this case is a 4-element Yagi on a 26-foot boom, also 70 feet above flat ground. The rhombic has about 2.2 dB more gain, but its azimuthal pattern is 17.2° wide at the 3 dB points, and only 26° at the –20 dB points! On the other hand, the Yagi has a 3-dB beamwidth of 63°, making it far easier to aim at a distant geographic location. Fig 27B shows the elevation-plane patterns for the same antennas above. As usual, the peak angle for either horizontally polarized antenna is determined mainly by the height above ground.

The peak gain of a terminated rhombic is less than that of an unterminated resonant rhombic. For the rhombic of Fig 26, the reduction in peak gain is about 1.5 dB. **Fig 28** compares the azimuthal patterns for this rhombic with and without an 800-Ω termination.

Fig 29 shows the azimuth and elevation patterns for the terminated rhombic of Fig 26 when it is operated at 28 MHz. The main lobe becomes very narrow, at 6.9° at the 3-dB points. However, this is partially compensated for by the appearance of two sidelobes each side of the main beam. These tend to spread out the main pattern some. Again, a 4-element Yagi at the same height is used for comparison.



Fig 25—Rhombic-antenna design chart. For any given leg length, the curves show the proper tilt angle to give maximum radiation at the selected takeoff angle. The broken curve marked "optimum length" shows the leg length that gives the maximum possible output at the selected takeoff angle. The optimum length as given by the curves should be multiplied by 0.74 to obtain the leg length for which the takeoff angle and main lobe are aligned.



Fig 26—Rhombic antenna dimensions for a compromise design between 14- and 28-MHz requirements, as discussed in the text. The leg length is 6 λ at 28 MHz, 3 λ at 14 MHz.

Termination

Although the difference in the gain is relatively small with terminated or unterminated rhombics of comparable design, the terminated antenna has the advantage that over a wide frequency range it presents an essentially resistive and constant load to the transmitter. In a sense, the power dissipated in the terminating resistor can be considered power that would have been radiated in the other direction had the resistor not been there. Therefore, the fact that some of the power (about one-third) is used up in heating the resistor does not mean that much actual loss in the desired direction.

The characteristic impedance of an ordinary rhombic antenna, looking into the input end, is in the order of 700 to 800 Ω when properly terminated in a resistance at the far end. The terminating resistance required to bring about the matching condition usually is slightly higher than the input impedance because of the loss of energy through radiation by the time the far end is reached. The correct value usually will be found to be of the order of 800 Ω, and should be determined experimentally if the flattest possible antenna is desired. However, for average work a noninductive resistance of 800 Ω can be used with the assurance that the operation will not be far from optimum.

The terminating resistor must be practically a pure resistance at the operating frequencies; that is, its inductance and capacitance should be negligible. Ordinary wire-wound resistors are not suitable because they have far too much inductance and distributed capacitance. Small carbon resistors have satisfactory electrical characteristics but will not dissipate more than a few watts and so cannot be used, except when the transmitter power does not exceed 10 or 20 watts or when the antenna is to be used for reception only. The special resistors designed either for use as dummy antennas or for terminating rhombic antennas should be used in other cases. To allow a factor of safety, the total rated power dissipation of the resistor or resistors should be equal to half the power output of the transmitter.

To reduce the effects of stray capacitance it is desirable to use several units, say three, in series even when one alone will safely dissipate the power. The two end units should be identical and each should have one fourth to one third the total resistance, with the center unit making up the difference. The units should be installed in a weather-





Fig 27—At left, azimuthal pattern for 3-λ (at 14 MHz) terminated rhombic (solid line) shown in Fig 26, compared with 4-element 20-meter Yagi (dotted line) on a 26-foot boom and a 20-meter dipole (dashed line). All antennas are mounted 70 feet (1 λ) above flat ground. The rearward pattern of the terminated rhombic is good and the forward gain exceeds that of the Yagi, but the frontal lobe is very narrow. Above, elevation-plane pattern of terminated rhombic compared to that of a simple dipole at the same height.



Fig 28—Comparison of azimuthal patterns for terminated (solid line) and unterminated (dashed line) rhombic antennas, using same dimensions as Fig 26 at a frequency of 14 MHz. The gain tradeoff is about 1.5 dB in return for the superior rearward pattern of the terminated antenna.

proof housing at the end of the antenna to protect them and to permit mounting without mechanical strain. The connecting leads should be short so that little extraneous inductance is introduced.

Alternatively, the terminating resistance may be placed at the end of an 800-Ω line connected to the end of the antenna. This will permit placing the resistors and their housing at a point convenient for adjustment rather than at the top of the pole. Resistance wire may be used for this line, so that a portion of the power will be dissipated before it reaches the resistive termination, thus permitting the use of lower wattage lumped resistors.

Multiwire Rhombics

The input impedance of a rhombic antenna constructed as in Fig 26 is not quite constant as the frequency is varied. This is because the varying separation between the wires causes the characteristic impedance of the antenna to vary along its length. The variation in Z_{ANT} can be minimized by a conductor arrangement that increases the capacitance per unit length in proportion to the separation between the wires.

The method of accomplishing this is shown in **Fig 30**. Three conductors are used, joined together at the ends but with increasing separation as the junction between legs is approached. For HF work the spacing between the wires at the center is 3 to 4 feet, which is similar to that used in commercial installations using legs several wavelengths long. Since all three wires should have the same length, the top and bottom wires should be slightly farther from the support than the middle wire. Using three wires in this way reduces the Z_{ANT} of the antenna to approximately 600 Ω, thus providing a better match for practical open-wire line, in addition to smoothing out the impedance variation over the frequency range.

A similar effect (although not quite as favorable) is obtained by using two wires instead of three. The 3-wire system has been found to increase the gain of the





Fig 29—At A, the azimuthal pattern for the same terminated antenna in Fig 26, but now at 28 MHz compared to a 4-element 10-meter Yagi. At B, the elevation-plane pattern comparison for these antennas.



Fig 30—Three-wire rhombic antenna. Use of multiple wires improves the impedance characteristic of a terminated rhombic and increases the gain somewhat.

antenna by about 1 dB over that of a single-conductor version.

Front-to-Back Ratio

It is theoretically possible to obtain an infinite front-to-back ratio with a terminated rhombic antenna, and in practice very large values can be had. However, when the antenna is terminated in its characteristic impedance, the infinite front-to-back ratio can be obtained only at frequencies for which the leg length is an odd multiple of a quarter wavelength. The front-to-back ratio is smallest at frequencies for which the leg length is a multiple of a half wavelength.

When the leg length is not an odd multiple of a quarter wave at the frequency under consideration, the front-to-back ratio can be made very high by decreasing the value of terminating resistance slightly. This permits a small reflection from the far end of the antenna, which cancels out the residual response at the input end. With large antennas, the front-to-back ratio may be made very large over the whole frequency range by experimental adjustment of the terminating resistance. Modification of the terminating resistance can result in a splitting of the back null into two nulls, one on either side of a small lobe in the back direction. Changes in the value of terminating resistance thus permit steering the back null over a small horizontal range so that signals coming from a particular spot not exactly to the rear of the antenna may be minimized.

Methods of Feed

If the broad frequency characteristic of the terminated rhombic antenna is to be utilized fully, the feeder system must be similarly broadbanded. Open-wire transmission line of the same characteristic impedance as that shown at the antenna input terminals (approximately 700 to 800 Ω) may be used. Data for the construction of such lines is given in Chapter 24. While the usual matching stub can be used to provide an impedance transformation to more satisfactory line impedances, this limits the operation of the antenna to a comparatively narrow range of frequencies centering about that for which the stub is adjusted. Probably a more satisfactory arrangement would be to use a coaxial transmission line and a broadband transformer balun at the antenna feed point.

Receiving Wave Antennas

Perhaps the best known type of wave antenna is the *Beverage*. Many 160-meter enthusiasts have used Beverage antennas to enhance the signal-to-noise ratio while attempting to extract weak signals from the often high levels of atmospheric noise and interference on the low bands. Alternative antenna systems have been developed and used over the years, such as loops and long spans of unterminated wire on or slightly above the ground, but the Beverage antenna seems to be the best for 160-meter weak-signal reception. The information in this section was prepared originally by Rus Healy, K2UA (ex-NJ2L).

THE BEVERAGE ANTENNA

A Beverage is simply a directional wire antenna, at least one wavelength long, supported along its length at a fairly low height and terminated at the far end in its characteristic impedance. This antenna is shown in **Fig 31A**. It takes its name from its inventor, Harold Beverage, W2BML.

Many amateurs choose to use a single-wire Beverage because they are easy to install and they work well. The drawback is that Beverages are physically long and they do require that you have the necessary amount of real estate to install them. Sometimes, a neighbor will allow you to put up a temporary Beverage for a particular contest or DXpedition on his land, particularly during the winter months.

Beverage antennas can be useful into the HF range, but they are most effective at lower frequencies, mainly on 160 through 40 meters. The antenna is responsive mostly to low-angle incoming waves that maintain a constant (vertical) polarization. These conditions are nearly always satisfied on 160 meters, and most of the time on 80 meters. As the frequency is increased, however, the polarization and arrival angles are less and less constant and favorable, making Beverages less effective at these frequencies. Many amateurs have, however, reported excellent performance from Beverage antennas at frequencies as high as 14 MHz, especially when rain or snow (precipitation) static prevents good reception on the Yagi or dipole transmitting antennas used on the higher frequencies.

Beverage Theory

The Beverage antenna acts like a long transmission line with one lossy conductor (the earth), and one good conductor (the wire). Beverages have excellent directivity if erected properly, but they are quite inefficient because they are mounted close to the ground. This is in contrast with the terminated long-wire antennas described earlier, which are typically mounted high off the ground. Beverage antennas are not suitable for use as transmitting antennas.

Because the Beverage is a traveling wave, terminated antenna, it has no standing waves resulting from radio signals. As a wave strikes the end of the Beverage from the desired direction, the wave induces voltages along the antenna and continues traveling in space as well. Fig 31B shows part of a wave on the antenna resulting from a desired signal. This diagram also shows the tilt of the wave. The signal induces equal voltages in both directions. The resulting currents are equal and travel in both directions; the component traveling toward the termination end moves *against* the wave and thus builds down to a very low level at the termination end. Any residual signal resulting from this direction of current flow will be absorbed in the termination (if the termination is equal to the antenna impedance). The component of the signal flowing in the other direction, as we will see, becomes a key part of the received signal.

As the wave travels along the wire, the wave in space travels at approximately the same velocity. (There is some phase delay in the wire, as we shall see.) At any given point in time, the wave traveling along in space induces a voltage in the wire in addition to the wave already travel-



Fig 31—At A, a simple one-wire Beverage antenna with a variable termination impedance and a matching 9:1 autotransformer for the receiver impedance. At B, a portion of a wave from the desired direction is shown traveling down the antenna wire. Its tilt angle and effective takeoff angle are also shown. At C, a situation analogous to the action of a Beverage on an incoming wave is shown. See text for discussion.

ing on the wire (voltages already induced by the wave). Because these two waves are nearly in phase, the voltages add and build toward a maximum at the receiver end of the antenna.

This process can be likened to a series of signal generators lined up on the wire, with phase differences corresponding to their respective spacings on the wire (Fig 31C). At the receiver end, a maximum voltage is produced by these voltages adding in phase. For example, the wave component induced at the receiver end of the antenna will be in phase (at the receiver end) with a component of the same wave induced, say, 270° (or any other distance) down the antenna, after it travels to the receiver end.

In practice, there is some phase shift of the wave on the wire with respect to the wave in space. This phase shift results from the velocity factor of the antenna. (As with any transmission line, the signal velocity on the Beverage is somewhat less than in free space.) Velocity of propagation on a Beverage is typically between 85 and 98% of that in free space. As antenna height is increased to a certain optimum height (which is about 10 feet for 160 meters), the velocity factor increases. Beyond this height, only minimal improvement is afforded, as shown in **Fig 32**. These curves are the result of experimental work done in 1922 by RCA, and reported in a *QST* article (November 1922) entitled “The Wave Antenna for 200-Meter Reception,” by H. H. Beverage. The curve for 160 meters was extrapolated from the other curves.

Phase shift (per wavelength) is shown as a function of velocity factor in **Fig 33**, and is given by:

$$\theta = 360\left(\frac{100}{k} - 1\right) \quad \text{(Eq 2)}$$

where k = velocity factor of the antenna in percent.

The signals present on and around a Beverage antenna are shown graphically in A through D of **Fig 34**. These curves show relative voltage levels over a number of periods of the wave in space and their relative effects in terms of the total signal at the receiver end of the antenna.



Fig 32—Signal velocity on a Beverage increases with height above ground, and reaches a practical maximum at about 10 feet. Improvement is minimal above this height. (The velocity of light is 100%.)



Fig 33—This curve shows phase shift (per wavelength) as a function of velocity factor on a Beverage antenna. Once the phase shift for the antenna goes beyond 90°, the gain drops off from its peak value, and any increase in antenna length will decrease gain.



Fig 34—These curves show the voltages that appear in a Beverage antenna over a period of several cycles of the wave. Signal strength (at A) is constant over the length of the antenna during this period, as is voltage induced per unit length in the wire (at B). (The voltage induced in any section of the antenna is the same as the voltage induced in any other section of the same size, over the same period of time.) At C, the voltages induced by an undesired signal from the rearward direction add in phase and build to a maximum at the termination end, where they are dissipated in the termination (if $Z_{term} = Z_0$). The voltages resulting from a desired signal are shown at D. The wave on the wire travels closely with the wave in space, and the voltages resulting add in phase to a maximum at the receiver end of the antenna.

Performance in Other Directions

The performance of a Beverage antenna in directions other than the favored one is quite different than previously discussed. Take, for instance, the case of a signal arriving perpendicular to the wire (90° either side of the favored direction). In this case, the wave induces voltages along the wire that are essentially *in phase*, so that they arrive at the receiver end more or less out of phase, and thus cancel. (This can be likened to a series of signal generators lined up along the antenna as before, but having no progressive phase differences.)

As a result of this cancellation, Beverages exhibit deep nulls off the sides. Some minor sidelobes will exist, as with other long-wire antennas, and will increase in number with the length of the antenna.

In the case of a signal arriving from the rear of the antenna, the behavior of the antenna is very similar to its performance in the favored direction. The major difference is that the signal from the rear adds in phase at the termination end and is absorbed by the termination impedance. **Fig 35** compares the azimuth and elevation patterns for a 2-λ (1062 foot) and a 1-λ (531 foot) Beverage at 1.83 MHz. The wire is mounted 8 feet above flat ground (to keep it above deer antlers and away from humans too) and is terminated with a 500-Ω resistor in each case, although the exact value of the terminating resistance is not very critical. The ground constants assumed in this computer model are conductivity of 5 mS/m and a dielectric constant of 13. Beverage dielectric performance tends to decrease as the ground becomes better. Beverages operated over saltwater do not work as well as they do over poor ground.

For most effective operation, the Beverage should be terminated in an impedance equal to the characteristic impedance Z_{ANT} of the antenna. For maximum signal transfer to the receiver you should also match the receiver's input impedance to the antenna. If the termination impedance is not equal to the characteristic impedance of the antenna, some part of the signal from the rear will be reflected back toward the receiver end of the antenna.

If the termination impedance is merely an open circuit (no terminating resistor), total reflection will result and the antenna will exhibit a bidirectional pattern (still with very deep nulls off the sides). An unterminated Beverage will not have the same response to signals in the rearward direction as it exhibits to signals in the forward direction because of attenuation and reradiation of part of the reflected wave as it travels back toward the receiver end. **Fig 36** compares the response from two 2-λ Beverages, one terminated and the other unterminated. Just like a terminated long-wire transmitting antenna (which is mounted higher off the ground than a Beverage, which is meant only for receiving), the terminated Beverage has a reduced forward lobe compared to its unterminated sibling. The unterminated Beverage exhibits about a 5 dB front-to-back ratio for this length because of the radiation and wire and ground losses that occur before the forward wave gets to the end of the wire.

If the termination is between the extremes (open circuit and perfect termination in Z_{ANT}), the peak direction and intensity of signals off the rear of the Beverage will change. As a result, an adjustable reactive termination can be employed to *steer* the nulls to the rear of the antenna (see **Fig 37**). This can be of great help in eliminating a local interfering signal from a rearward direction (typically 30° to 40° either side of the back direction). Such a scheme doesn't help much for interfering skywave signals because of variations encountered in the ionosphere that constantly shift polarity, amplitude, phase and



Fig 35—At A, azimuthal patterns of a 2-λ (solid line) and a 1-λ (dashed line) Beverage antenna, terminated with 550-Ω resistor at 1.83 MHz, at an elevation angle of 10°. The rearward pattern around 180° is more than 20 dB down from the front lobe for each antenna. At B, the elevation-plane patterns. Note the rejection of very high-angle signals near 90°.



Fig 36—Comparing the azimuthal patterns for a 2-λ Beverage, terminated (solid line) and unterminated (dashed line).

incoming elevation angles.

To determine the appropriate value for a terminating resistor, you need to know the characteristic impedance (surge impedance), Z_{ANT}, of the Beverage. It is interesting to note that Z_{ANT} is not a function of the length, just like a transmission line.

$$Z_{ANT} = 138 \times \log\left(\frac{4h}{d}\right) \qquad \text{(Eq 3)}$$

where

Z_{ANT} = characteristic impedance of the Beverage = terminating resistance needed

h = wire height above ground

d = wire diameter (in the same units as h)

Another aspect of terminating the Beverage is the quality of the RF ground used for the termination. For most types of soil a ground rod is sufficient, since the optimum value for the termination resistance is in the range of 400 to 600 Ω for typical Beverages and the ground-loss resistance is in series with this. Even if the ground-loss resistance at the termination point is as high as 40 or 50 Ω, it still is not an appreciable fraction of the overall terminating resistance. For soil with very poor conductivity, however, (such as sand or rock) you can achieve a better ground termination by laying radial wires on the ground at both the receiver and termination ends. These wires need not be resonant quarter-wave in length, since the ground detunes them anyway. Like the ground counterpoise for a vertical antenna, a number of short radials is better than a few long ones. Some amateurs use chicken-wire ground screens for their ground terminations.

As with many other antennas, improved directivity and gain can be achieved by lengthening the antenna and by arranging several antennas into an array. One item that must be kept in mind is that by virtue of the velocity factor of the antenna, there is some phase shift of the wave on the antenna with respect to the wave in space. Because of this phase shift, although the directivity will continue to sharpen with increased length, there will be some optimum length at which the gain of the antenna will peak. Beyond this



Fig 37—A two-wire Beverage antenna that has provisions for direction switching and null steering in the rear quadrant. Performance improves with height to a point, and is optimum for 1.8-MHz operation at about 10 to 12 feet. Parts identifications are for text reference.

length, the current increments arriving at the receiver end of the antenna will no longer be in phase, and will not add to produce a maximum signal at the receiver end. This optimum length is a function of velocity factor and frequency, and is given by:

$$L = \frac{\lambda}{4\left(\frac{100}{k} - 1\right)} \qquad \text{(Eq 4)}$$

where

L = maximum effective length

λ = signal wavelength in free space (same units as L)

k = velocity factor of the antenna in percent

Because velocity factor increases with height (to a point, as mentioned earlier), optimum length is somewhat longer if the antenna height is increased. The maximum effective length also increases with the number of wires in the antenna system. For example, for a two-wire Beverage like the bidirectional version shown in Fig 37, the maximum effective length is about 20% longer than the single-wire version. A typical length for a single-wire 1.8-MHz Beverage (made of #16 wire and erected 10 feet above ground) is about 1200 feet.

Feed-Point Transformers for Single-Wire Beverages

Matching transformer T1 in Fig 31 is easily constructed. Small toroidal ferrite cores are best for this application, with those of high permeability (μ_i = 125 to 5000) being the easiest to wind (requiring fewest turns) and having the best high-frequency response (because few turns are used). Trifilar-wound autotransformers are most convenient.

Most users are not concerned with a small amount of SWR on the transmission line feeding their Beverages. For example, let us assume that the Z_{ANT} of a particular Beverage is 525 Ω and the terminating resistance is made equal to that value. If a standard 3:1 turns-ratio autotransformer is used at the input end of the antenna, the nominal impedance transformation 50 Ω × 3^2 = 450 Ω. This leads to the terminology often used for this transformer as a *9:1 transformer*, referring to its impedance transformation. The resulting SWR on the feed line going back to the receiver would be 525/450 = 1.27:1, not enough to be concerned about. For a Z_{ANT} of 600 Ω, the SWR is 600/450 = 1.33:1, again not a matter of concern.

Hence, most Beverage users use standard 9:1 (450:50 Ω) autotransformers. You can make a matching transformer suitable for use from 160 to 40 meters using eight trifilar turns of #24 enameled wire wound over a stack of two Amidon FT-50-75 or two MN8-CX cores. See **Fig 38**.

Make your own trifilar cable bundle by placing three 3-foot lengths of the #24 wire side-by-side and twisting them in a hand drill so that there is a uniform twist about one twist-per-inch. This holds the three wires together in a bundle that can be passed through the two stacked cores, rather like threading a needle. Remember that each time you put the bundle through the center of the cores counts as one turn.

After you finish winding, cut the individual wires to leave about $^3/_4$-inch leads, sand off the enamel insulation and tin the wires with a soldering iron. Identify the individual wires with an ohmmeter and then connect them together following Fig 38. Coat the transformer with Q-dope (liquid polystyrene) to finalize the transformer. White glue will work also. See Chapters 25 and 26 and *The ARRL Handbook* for more information on winding toroidal transformers or see Chapter 7 (Special Receiving Antennas) of *ON4UN's Low-Band DXing* book.

The Two-Wire Beverage

The two-wire antenna shown in Fig 37 has the major advantage of having signals from both directions available at the receiver at the flip of a switch between J1 and J2. Also, because there are two wires in the system (equal amounts of signal voltage are induced in both wires), greater signal voltages will be produced.



Fig 38—Constructing the feed-point transformer for a single-wire Beverage. See text for details.

A signal from the left direction in Fig 37 induces equal voltages in both wires, and equal in-phase currents flow as a result. The *reflection transformer* (T3 at the right-hand end of the antenna) then inverts the phase of these signals and reflects them back down the antenna toward the receiver, using the antenna wires as a balanced open-wire transmission line. This signal is then transformed by T1 down to the input impedance of the receiver (50 Ω) at J1.

Signals traveling from right to left also induce equal voltages in each wire, and they travel in phase toward the receiver end, through T1, and into T2. Signals from this direction are available at J2.

T1 and T2 are standard 9:1 wideband transformers capable of operating from 1.8 to at least 10 MHz. Like any two parallel wires making up a transmission line, the two-wire Beverage has a certain characteristic impedance—we'll call it Z_1 here—depending on the spacing between the two wires and the insulation between them. T3 transforms the terminating resistance needed at the end of the line to Z_1. Keep in mind that this terminating resistance is equal to the characteristic impedance Z_{ANT} of the Beverage—that is, the impedance of the parallel wires over their images in the ground below. For example, if Z_1 of the Beverage wire is 300 Ω (that is, you used TV twin-lead for the two Beverage wires), T3 must transform the balanced 300 Ω to the unbalanced 500 Ω Z_{ANT} impedance used to terminate the Beverage.

The design and construction of the reflection transformer used in a two-wire Beverage is more demanding than that for the straightforward matching transformer T1 because the exact value of terminating impedance is more critical for good F/B. See Chapter 7 (Special Receiving Antennas) in *ON4UN's Low-Band DXing* for details on winding the reflection transformers for a two-wire Beverage.

Another convenient feature of the two-wire Beverage is the ability to steer the nulls off either end of the antenna while receiving in the opposite direction. For instance, if the series RLC network shown at J2 is adjusted while the receiver is connected to J1, signals can be received from the left direction while interference coming from the right can be partially or completely nulled. The nulls can be steered over a 60° (or more) area off the right-hand end of the antenna. The same null-steering capability exists in the opposite direction with the receiver connected at J2 and the termination connected at J1.

The two-wire Beverage is typically erected at the same height as a single-wire version. The two wires are at the same height and are spaced uniformly—typically 12 to 18 inches apart for discrete wires. Some amateurs construct two-wire Beverages using "window" ladder-line, twisting the line about three twists per foot for mechanical and electrical stability in the wind.

The characteristic impedance Z_{ANT} of a Beverage made using two discrete wires with air insulation between them depends on the wire size, spacing and height and is given by:

$$Z_{ANT} = \frac{69}{\sqrt{\varepsilon}} \times \log\left[\frac{4h}{d}\sqrt{1+\left(\frac{2h}{S}\right)^2}\right] \qquad \text{(Eq 5)}$$

where

Z_{ANT} = Beverage impedance = desired terminating resistance
S = wire spacing
h = height above ground
d = wire diameter (in same units as S and h)
ε = 2.71828

Beverages in Echelon

The pattern of a Beverage receiving antenna is dependent on the terminating resistance used for a particular antenna, as was demonstrated at the extremes by Fig 36. This compared the patterns for a terminated and an unterminated Beverage. The pattern of even a poorly terminated Beverage can be significantly improved by the addition of a second Beverage. The additional Beverage is installed so that it is operated *in echelon,* a word deriving from the fact that the two wires look like the parallel rungs on a ladder. For a practial 160- and 80-meter setup the second Beverage wire is parallel to the first Beverage, spaced from it by about 5 meters, and also staggered 30 meters ahead. See **Fig 38**.

The forward Beverage is fed with a phase difference of +125° such that the total phase, including that due to the forward staggering, is 180°. This forms the equivalent of an end-fire array fed out-of-phase, but it takes advantage of the natural directivity of each Beverage. **Fig 39** compares the pattern of a single 1-λ 160-meter Beverage that is sloppily terminated with two Beverages fed in echelon. The

Beverages in echelon gives a modest additional gain of almost 2 dB. But where the two Beverages in echelon really shine is how they cleans up the rearward pattern—from an average about 15 dB for the single Beverage to more than 25 dB for the two Beverages.

Even at a spacing of 5 meters, there is very little mutual coupling between the two Beverage wires because of their inherently small radiation resistance when they are mounted low above lossy ground. If you adjust for a low SWR (using proper transformers to match the feed-line coaxes), the phase difference will depend solely on the difference in length of the two coaxes feeding the Beverage wires. **Fig 40** shows a wideband feed system designed by Tom Rauch, W8JI, as a "cross-fire" feed system. The 180° wideband phase-inverting transformer allows the system to work on two bands, say 160 and 80 meters. See Chapter 7, Receiving Antennas, in *ON4UN's Low-Band DXing* book, 4th Edition for transformer details.

Practical Considerations

Even though Beverage antennas have excellent directive patterns if terminated properly, gain never exceeds about –3 dBi in most practical installations. However, the directivity that the Beverage provides results in a much higher signal-to-noise ratio for signals in the desired direction than almost any other real-world antenna used at low frequencies.

A typical situation might be a station located in the US Northeast (W1), trying to receive Topband signals from Europe to the northeast, while thunderstorms behind him in the US Southeast (W4) are creating huge static crashes. Instead of listening to an S7 signal with 10-dB over S9 noise and interference on a vertical, the directivity of a Beverage will typically allow you to copy the same signal at perhaps S5 with only S3 (or lower) noise and interference. This is certainly a worthwhile improvement. However, if you are in the middle of a thunderstorm, or if there is a thunderstorm in the direction from which you are trying to receive a signal, no Beverage is going to help you!

There are a few basic principles that must be kept in mind when erecting Beverage antennas if optimum performance is to be realized.

1) Plan the installation thoroughly, including choosing an antenna length consistent with the optimum length values discussed earlier.
2) Keep the antenna as straight and as nearly level as possible over its entire run. Avoid following the terrain under the antenna too closely—keep the antenna level with the average terrain.
3) Minimize the lengths of vertical downleads at the ends of the antenna. Their effect is detrimental to the directive pattern of the antenna. It is best to slope the antenna wire from ground level to its final height (over a distance of 50 feet or so) at the feed-point end. Similar action should be taken at the termination end. Be sure to seal the transformers against weather.



Fig 39—Layout of two 160-meter 1-λ long Beverages in echelon, spaced 5 meters apart, with 30 meter forward stagger. The upper antenna has a 125° phase shift in its feed system.



Fig 40—Azimuth pattern at 10° takeoff angle for single Beverage (dashed line) and two Beverages in an echelon end-fire array. The rearward pattern is considerably cleaner on the echelon. Thus, two closely spaced, short Beverages can give considerable improvement over a single short Beverage.



Fig 41—Two ways of feeding the two-Beverage echelon array in Fig 39. On the left, a feed system good for one frequency; on the right, a "cross-fire" feed system good for 1.8 and 3.6 MHz. For this system we want a phase shift due to the coax length of +116° at the back Beverage A. The angle ϕ is thus 180°–116° = 64° long on 160 meters. In the system on the right, a 64° length on 160 meters becomes 128° long on 80 meters. So with the phase-inverting transformer the net phase shift becomes 53° on 80 meters, a reasonable compromise. (*Courtesy W8JI and ON4UN.*)

4) Use a noninductive resistor for terminating a single-wire Beverage. If you live in an area where lightning storms are common, use 2-W terminating resistors, which can survive surges due to nearby lightning strikes.
5) Use high-quality insulators for the Beverage wire where it comes into contact with the supports. Plastic insulators designed for electric fences are inexpensive and effective.
6) Keep the Beverage away from parallel conductors such as electric power and telephone lines for a distance of at least 200 feet. Perpendicular conductors, even other Beverages, may be crossed with relatively little interaction, but do not cross any conductors that may pose a safety hazard.
7) Run the coaxial feed line to the Beverage so that it is not directly under the span of the wire. This prevents common-mode currents from appearing on the shield of the coax. It may be necessary to use a ferrite-bead choke on the feed line if you find that the feed line itself picks up signals when it is temporarily disconnected from the Beverage. See Chapter 26 for details on common-mode chokes.
8) If you use elevated radials in your transmitting antenna system, keep your Beverage feed lines well away from them to avoid stray pickup that will ruin the Beverage's directivity.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below.

A. Bailey, S. W. Dean and W. T. Wintringham, "The Receiving System for Long-Wave Transatlantic Radio Telephony," *The Bell System Technical Journal*, Apr 1929.

J. S. Belrose, "Beverage Antennas for Amateur Communications," Technical Correspondence, *QST*, Sep 1981.

H. H. Beverage, "Antennas," *RCA Review*, Jul 1939.

H. H. Beverage and D. DeMaw, "The Classic Beverage Antenna Revisited," *QST* , Jan 1982.

B. Boothe, "Weak-Signal Reception on 160—Some Antenna Notes," *QST*, Jun 1977.

E. Bruce, "Developments in Short-Wave Directive Antennas," *Proc IRE*, Aug 1931.

E. Bruce, A. C. Beck and L. R. Lowry, "Horizontal Rhombic Antennas," *Proc IRE*, Jan 1935.

P. S. Carter, C. W. Hansel and N. E. Lindenblad, "Development of Directive Transmitting Antennas by R.C.A. Communications," *Proc IRE*, Oct 1931.

J. Devoldere, *Low-Band DXing* (Newington: ARRL, 1987).

J. Devoldere, *ON4UN's Low-Band DXing* (Newington: ARRL, 1999). See in particular Chapter 7, "Special Receiving Antennas," for many practical details on Beverage antennas.

A. E. Harper, *Rhombic Antenna Design* (New York: D. Van Nostrand Co, Inc).

E. A. Laport, "Design Data for Horizontal Rhombic Antennas," *RCA Review*, Mar 1952.

G. M. Miller, *Modern Electronic Communication* (Englewood Cliffs, NJ: Prentice Hall, 1983).

V. A. Misek, *The Beverage Antenna Handbook* (Wason Rd., Hudson, NH: W1WCR, 1977).

F. E. Terman, *Radio Engineering*, Second Edition (New York: McGraw-Hill, 1937).

Chapter 14

Direction Finding Antennas

The use of radio for direction-finding purposes (RDF) is almost as old as its application for communications. Radio amateurs have learned RDF techniques and found much satisfaction by participating in hidden-transmitter hunts. Other hams have discovered RDF through an interest in boating or aviation, where radio direction finding is used for navigation and emergency location systems.

In many countries of the world, the hunting of hidden amateur transmitters takes on the atmosphere of a sport, as participants wearing jogging togs or track suits dash toward the area where they believe the transmitter is located. The sport is variously known as *fox hunting*, *bunny hunting*, ARDF (Amateur Radio direction finding) or simply transmitter hunting. In North America, most hunting of hidden transmitters is conducted from automobiles, although hunts on foot are gaining popularity.

There are less pleasant RDF applications as well, such as tracking down noise sources or illegal operators from unidentified stations. Jammers of repeaters, traffic nets and other amateur operations can be located with RDF equipment. Or sometimes a stolen amateur rig will be operated by a person who is not familiar with Amateur Radio, and by being lured into making repeated transmissions, the operator unsuspectingly permits himself to be located with RDF equipment. The ability of certain RDF antennas to reject signals from selected directions has also been used to advantage in reducing noise and interference. Through APRS, radio navigation is becoming a popular application of RDF. The locating of downed aircraft is another, and one in which amateurs often lend their skills. Indeed, there are many useful applications for RDF.

Although sophisticated and complex equipment pushing the state of the art has been developed for use by governments and commercial enterprises, relatively simple equipment can be built at home to offer the Radio Amateur an opportunity to RDF. This chapter deals with antennas suitable for that purpose.

RDF by Triangulation

It is impossible, using amateur techniques, to pinpoint the whereabouts of a transmitter from a single receiving location. With a directional antenna you can determine the direction of a signal source, but not how far away it is. To find the distance, you can then travel in the determined direction until you discover the transmitter location. However, that technique can be time consuming and often does not work very well.

A preferred technique is to take at least one additional direction measurement from a second receiving location. Then use a map of the area and plot the bearing or direction measurements as straight lines from points on the map representing the two locations. The approximate location of the transmitter will be indicated by the point where the two bearing lines cross. Even better results can be obtained by taking direction measurements from three locations and using the mapping technique just described. Because absolutely precise bearing measurements are difficult to obtain in practice, the three lines will almost always cross to form a triangle on the map, rather than at a single point. The transmitter will usually be located inside the area represented by the triangle. Additional information on the technique of triangulation and much more on RDF techniques may be found in recent editions of *The ARRL Handbook*.

DIRECTION FINDING SY\STEMS

Required for any RDF system are a directive antenna and a device for detecting the radio signal. In amateur applications the signal detector is usually a transceiver and for convenience it will usually have a meter to indicate signal strength. Unmodified, commercially available portable or mobile receivers are generally quite satisfactory for signal detectors. At very close ranges a simple diode detector and dc microammeter may suffice for the detector.

On the other hand, antennas used for RDF techniques are not generally the types used for normal two-way communications. Directivity is a prime requirement, and here the word *directivity* takes on a somewhat different meaning than is commonly applied to other amateur antennas. Normally we associate directivity with gain, and we think of the ideal antenna pattern as one having a long, thin main lobe. Such a pattern may be of value for coarse measurements in RDF work, but precise bearing measurements are not possible. There is always a spread of a few (or perhaps many) degrees on the *nose* of the lobe, where a shift of antenna bearing produces no detectable change in signal strength. In RDF measure-ments, it is desirable to correlate an exact bearing or compass direction with the position of the antenna. In order to do this as accurately as possible, an antenna exhibiting a *null* in its pattern is used. A null can be very sharp in directivity, to within a half degree or less.

Loop Antennas

A simple antenna for HF RDF work is a small loop tuned to resonance with a capacitor. Several factors must be considered in the design of an RDF loop. The loop must be small in circumference compared with the wavelength. In a single-turn loop, the conductor should be less than 0.08 λ long. For 28 MHz, this represents a length of less than 34 inches (a diameter of approximately 10 inches). Maximum response from the loop antenna is in the plane of the loop, with nulls exhibited at right angles to that plane.

To obtain the most accurate bearings, the loop must be balanced electrostatically with respect to ground. Otherwise, the loop will exhibit two modes of operation. One is the mode of a true loop, while the other is that of an essentially nondirectional vertical antenna of small dimensions. This second mode is called the *antenna effect*. The voltages introduced by the two modes are seldom in phase and may add or subtract, depending upon the direction from which the wave is coming.

The theoretical true loop pattern is illustrated in **Fig 1A**. When properly balanced, the loop exhibits two nulls that are 180° apart. Thus, a single null reading with a small loop antenna will not indicate the exact direction toward the transmitter—only the line along which the transmitter lies. Ways to overcome this ambiguity are discussed later.

When the antenna effect is appreciable and the loop is tuned to resonance, the loop may exhibit little directivity, as shown in Fig 1B. However, by detuning the loop to shift the phasing, a pattern similar to 1C may be obtained. Although this pattern is not symmetrical, it does exhibit a null. Even so, the null may not be as sharp as that obtained with a loop that is well balanced, and it may not be at exact right angles to the plane of the loop.

By suitable detuning, the unidirectional cardioid pattern of Fig 1D may be approached. This adjustment is sometimes used in RDF work to obtain a unidirectional bearing, although there is no complete null in the pattern. A cardioid pattern can also be obtained with a small loop antenna by adding a *sensing element*. Sensing elements are discussed in a later section of this chapter.

An electrostatic balance can be obtained by shielding the loop, as **Fig 2** shows. The shield is represented by the broken lines in the drawing, and eliminates the antenna effect. The response of a well-constructed shielded loop is quite close to the ideal pattern of Fig 1A.



Fig 1—Small-loop field patterns with varying amounts of antenna effect—the undesired response of the loop acting merely as a mass of metal connected to the receiver antenna terminals. The straight lines show the plane of the loop.



Fig 2—Shielded loop for direction finding. The ends of the shielding turn are not connected, to prevent shielding the loop from magnetic fields. The shield is effective against electric fields.



Fig 3—Small loop consisting of several turns of wire. The total conductor length is very much less than a wavelength. Maximum response is in the plane of the loop.

For the low-frequency amateur bands, single-turn loops of convenient physical size for portability are generally found to be unsatisfactory for RDF work. Therefore, multiturn loops are generally used instead. Such a loop is shown in **Fig 3**. This loop may also be shielded, and if the total conductor length remains below 0.08 λ, the directional pattern is that of Fig 1A. A sensing element may also be used with a multiturn loop.

Loop Circuits and Criteria

No single word describes a direction-finding loop of high performance better than *symmetry*. To obtain an undistorted response pattern from this type of antenna, you must build it in the most symmetrical manner possible. The next key word is *balance*. The better the electrical balance, the deeper the loop null and the sharper the maxima.

The physical size of the loop for 7 MHz and below is not of major consequence. A 4-foot diameter loop will exhibit the same electrical characteristics as one which is only an inch or two in diameter. The smaller the loop, however, the lower its efficiency. This is because its aperture samples a smaller section of the wave front. Thus, if you use loops that are very small in terms of a wavelength, you will need preamplifiers to compensate for the reduced efficiency.

An important point to keep in mind about a small loop antenna oriented in a vertical plane is that it is vertically polarized. It should be fed at the bottom for the best null response. Feeding it at one side, rather than at the bottom, will not alter the polarization and will only degrade performance. To obtain horizontal polarization from a small loop, it must be oriented in a horizontal plane, parallel to the earth. In this position the loop response is essentially omnidirectional.

The earliest loop antennas were of the *frame antenna* variety. These were unshielded antennas built on a wooden frame in a rectangular format. The loop conductor could be a single turn of wire (on the larger units) or several turns if the frame was small. Later, shielded versions of the frame antenna became popular, providing electrostatic shielding—an aid to noise reduction from such sources as precipitation static.

Ferrite Rod Antennas

With advances in technology, magnetic-core loop antennas came into use. Their advantage was reduced size, and this appealed especially to the designers of aircraft and portable radios. Most of these antennas contain ferrite bars or cylinders, which provide high inductance and Q with a relatively small number of coil turns.

Magnetic-core antennas consist essentially of turns of wire around a ferrite rod. They are also known as *loopstick* antennas. Probably the best-known example of this type of antenna is that used in small portable AM broadcast receivers. Because of their reduced-size advantage, ferrite-rod antennas are used almost exclusively for portable work at frequencies below 150 MHz.

As implied in the earlier discussion of shielded loops in this chapter, the true loop antenna responds to the magnetic field of the radio wave, and not to the electrical field. The voltage delivered by the loop is proportional to the amount of magnetic flux passing through the coil, and to the number of turns in the coil. The action is much the same as in the secondary winding of a transformer. For a given size of loop, the output voltage can be increased by increasing the flux density, and this is done with a ferrite core of high permeability. A $^1/_2$-inch diameter, 7-inch rod of Q2 ferrite (m_i = 125) is suitable for a loop core from the broadcast band through 10 MHz. For increased output, the turns may be wound on two rods that are taped together, as shown in **Fig 4**. Loopstick antennas for con-



Fig 4—A ferrite-rod or loopstick antenna. Turns of wire may be wound on a single rod, or to increase the output from the loop, the core may be two rods taped together, as shown here. The type of core material must be selected for the intended frequency range of the loop. To avoid bulky windings, fine wire such as #28 or #30 is often used, with larger wire for the leads.



Fig 5—Field pattern for a ferrite rod antenna. The dark bar represents the rod on which the loop turns are wound.

struction are described later in this chapter.

Maximum response of the loopstick antenna is broadside to the axis of the rod as shown in **Fig 5**, whereas maximum response of the ordinary loop is in a direction at right angles to the plane of the loop. Otherwise, the performances of the ferrite-rod antenna and of the ordinary loop are similar. The loopstick may also be shielded to eliminate the antenna effect, such as with a U-shaped or C-shaped channel of aluminum or other form of *trough*. The length of the shield should equal or slightly exceed the length of the rod.

Sensing Antennas

Because there are two nulls that are 180° apart in the directional pattern of a loop or a loopstick, an ambiguity exists as to which one indicates the true direction of the station being tracked. For example, assume you take a bearing measurement and the result indicates the transmitter is somewhere on a line running approximately east and west from your position. With this single reading, you have no way of knowing for sure if the transmitter is east of you or west of you.

If more than one receiving station takes bearings on a single transmitter, or if a single receiving station takes bearings from more than one position on the transmitter, the ambiguity may be worked out by triangulation, as described earlier. However, it is sometimes desirable to have a pattern with only one null, so there is no question about whether the transmitter in the above example would be east or west from your position.

A loop or loopstick antenna may be made to have a single null if a second antenna element is added. The element is called a *sensing antenna*, because it gives an added sense of direction to the loop pattern. The second element must be omnidirectional, such as a short vertical. When the signals from the loop and the vertical element are combined with a 90° phase shift between the two, a cardioid pattern results. The development of the pattern is shown in **Fig 6A**.



Fig 6—At A, the directivity pattern of a loop antenna with sensing element. At B is a circuit for combining the signals from the two elements. C1 is adjusted for resonance with T1 at the operating frequency.

Fig 6B shows a circuit for adding a sensing antenna to a loop or loopstick. R1 is an internal adjustment and is used to set the level of the signal from the sensing antenna. For the best null in the composite pattern, the signals from the loop and the sensing antenna must be of equal amplitude, so R1 is adjusted experimentally during setup. In practice, the null of the cardioid is not as sharp as that of the loop, so the usual measurement procedure is to first use the loop alone to obtain a precise bearing reading, and then to add the sensing antenna and take another reading to resolve the ambiguity. (The null of the cardioid is 90° away from the nulls of the loop.) For this reason, provisions are usually made for switching the sensing element in an out of operation.

PHASED ARRAYS

Phased arrays are also used in amateur RDF work. Two general classifications of phased arrays are end-fire and broadside configurations. Depending on the spacing and phasing of the elements, end-fire patterns may exhibit a null in one direction along the axis of the elements. At the same time, the response is maximum off the other end of the axis, in the opposite direction from the null. A familiar arrangement is two elements spaced $^1/_4$ λ apart and fed 90° out of phase. The resultant pattern is a *cardioid*, with the null in the direction of the leading element. Other arrangements of spacing and phasing for an end-fire array are also suitable for RDF work. One of the best known is the *Adcock array*, discussed in the next section.

Broadside arrays are inherently bidirectional, which means there are always at least two nulls in the pattern. Ambiguity therefore exists in the true direction of the transmitter, but depending on the application, this may be no handicap. Broadside arrays are seldom used for amateur RDF applications however.

The Adcock Antenna

Loops are adequate in RDF applications where only the ground wave is present. The performance of an RDF system for sky-wave reception can be improved by the use of an Adcock antenna, one of the most popular types of end-fire phased arrays. A basic version is shown in **Fig 7**.

This system was invented by F. Adcock and patented in 1919. The array consists of two vertical elements fed 180° apart, and mounted so the system may be rotated. Element spacing is not critical, and may be in the range from 0.1 to 0.75 λ. The two elements must be of identical lengths, but need not be self-resonant. Elements that are shorter than resonant are commonly used. Because neither the element spacing nor the length is critical in terms of wavelengths, an Adcock array may be operated over more than one amateur band.

The response of the Adcock array to vertically polarized waves is similar to a conventional loop, and the directive pattern is essentially the same. Response of the array to a horizontally polarized wave is considerably different from that of a loop, however. The currents induced in the horizontal members tend to balance out regardless of the orientation of the antenna. This effect has been verified in practice, where good nulls were obtained with an experimental Adcock under sky-wave conditions. The same circumstances produced poor nulls with small loops (both conventional and ferrite-loop models).

Generally speaking, the Adcock antenna has attractive properties for amateur RDF applications. Unfortunately, its portability leaves something to be desired, making it more suitable to fixed or semi-portable applications. While a metal support for the mast and boom could be used, wood, PVC or fiberglass are preferable because they are nonconductors and would therefore cause less pattern distortion.

Since the array is balanced, an antenna tuner is required to match the unbalanced input of a typical receiver. **Fig 8** shows a suitable link-coupled network. C2 and C3 are null-balancing capacitors. A low-power signal source is placed some distance from the Adcock



Fig 7—A simple Adcock antenna.



Fig 8—A suitable coupler for use with the Adcock antenna.



Fig 9—At A, the pattern of the Adcock array with an element spacing of $^1/_2$ wavelength. In these plots the elements are aligned with the horizontal axis. As the element spacing is increased beyond $^3/_4$ wavelength, additional nulls develop off the ends of the array, and at a spacing of 1 wavelength the pattern at B exists. This pattern is unsuitable for RDF work.

antenna and broadside to it. C2 and C3 are then adjusted until the deepest null is obtained. The tuner can be placed below the wiring-harness junction on the boom. Connection can be made by means of a short length of 300-Ω twin-lead.

The radiation pattern of the Adcock is shown in **Fig 9A**. The nulls are in directions broadside to the array, and become sharper with greater element spacings. However, with an element spacing greater than 0.75 λ, the pattern begins to take on additional nulls in the directions off the ends of the array axis. At a spacing of 1 λ the pattern is that of Fig 9B, and the array is unsuitable for RDF applications.

Short vertical monopoles are often used in what is sometimes called the *U-Adcock*, so named because the elements with their feeders take on the shape of the letter U. In this arrangement the elements are worked against the earth as a ground or counterpoise. If the array is used only for reception, earth losses are of no great consequence. Short, elevated vertical dipoles are also used in what is sometimes called the *H-Adcock*.

The Adcock array, with two nulls in its pattern, has the same ambiguity as the loop and the loopstick. Adding a sensing element to the Adcock array has not met with great success. Difficulties arise from mutual coupling between the array elements and the sensing element, among other things. Because Adcock arrays are used primarily for fixed-station applications, the ambiguity presents no serious problem. The fixed station is usually one of a group of stations in an RDF network.

LOOPS VERSUS PHASED ARRAYS

Although loops can be made smaller than suitable phased arrays for the same frequency of operation, the phased arrays are preferred by some for a variety of reasons. In general, sharper nulls can be obtained with phased arrays, but this is also a function of the care used in constructing and feeding the individual antennas, as well as of the size of the phased array in terms of wavelengths. The primary constructional consideration is the shielding and balancing of the feed line against unwanted signal pickup, and the balancing of the antenna for a symmetrical pattern.

Loops are not as useful for skywave RDF work because of random polarization of the received signal. Phased arrays are somewhat less sensitive to propagation effects, probably because they are larger for the same frequency of operation and therefore offer some space diversity. In general, loops and loopsticks are used for mobile and portable operation, while phased arrays are used for fixed-station operation. However, phased arrays are used successfully above 144 MHz for portable and mobile RDF work. Practical examples of both types of antennas are presented later in this chapter.

THE GONIOMETER

Most fixed RDF stations for government and commercial work use antenna arrays of stationary elements, rather than mechanically rotatable arrays. This has been true since the earliest days of radio. The early-day device that permits finding directions without moving the elements is called a *radiogoniometer*, or simply a *goniometer*. Various types of goniometers are still used today in many installations, and offer the amateur some possibilities.

The early style of goniometer is a special form of RF transformer, as shown in **Fig 10**. It consists of two fixed coils mounted at right angles to one another. Inside the fixed coils is a movable coil, not shown in Fig 10 to



Fig 10—An early type of goniometer that is still used today in some RDF applications. This device is a special type of RF transformer that permits a movable coil in the center (not shown here) to be rotated and determine directions even though the elements are stationary.



Fig 11—This diagram illustrates one technique used in electronic beam forming. By delaying the signal from element A by an amount equal to the propagation delay, the two signals may be summed precisely in phase, even though the signal is not in the broadside direction. Because this time delay is identical for all frequencies, the system is not frequency sensitive.

avoid cluttering the diagram. The pairs of connections marked A and B are connected respectively to two elements in an array, and the output to the detector or receiver is taken from the movable coil. As the inner coil is rotated, the coupling to one fixed coil increases while that to the other decreases. Both the amplitude and the phase of the signal coupled into the pickup winding are altered with rotation in a way that corresponds to actually rotating the array itself. Therefore, the rotation of the inner coil can be calibrated in degrees to correspond to bearing angles from the station location.

In the early days of radio, the type of goniometer just described saw frequent use with fixed Adcock arrays. A refinement of that system employed four Adcock elements, two arrays at right angles to each other. With a goniometer arrangement, RDF measurements could be taken in all compass directions, as opposed to none off the ends of a two-element fixed array. However, resolution of the 4-element system was not as good as with a single pair of elements, probably because of mutual coupling among the elements. To overcome this difficulty a few systems of eight elements were installed.

Various other types of goniometers have been developed over the years, such as commutator switching to various elements in the array. A later development is the diode switching of capacitors to provide a commutator effect. As mechanical action has gradually been replaced with electronics to “rotate” stationary elements, the word goniometer is used less frequently these days. However, it still appears in many engineering reference texts. The more complex electronic systems of today are called *beam-forming networks*.

Electronic Antenna Rotation

With an array of many fixed elements, beam rotation can be performed electronically by sampling and combining signals from various individual elements in the array. Contingent upon the total number of elements in the system and their physical arrangement, almost any desired antenna pattern can be formed by summing the sampled signals in appropriate amplitude and phase relationships. Delay networks are used for some of the elements before the summation is performed. In addition, attenuators may be used for some elements to develop patterns such as from an array with binomial current distribution.

One system using these techniques is the *Wullenweber* antenna, employed primarily in government and military installations. The Wullenweber consists of a very large number of elements arranged in a circle, usually outside of (or in front of) a circular reflecting screen. Depending on the installation, the circle may be anywhere from a few hundred feet to more than a quarter of a mile in diameter. Although the Wullenweber is not one that would be constructed by an amateur, some of the techniques it uses may certainly be applied to Amateur Radio.

For the moment, consider just two elements of a Wullenweber antenna, shown as A and B in **Fig 11**. Also shown is the wavefront of a radio signal arriving from a distant transmitter. As drawn, the wavefront strikes element A first, and must travel somewhat farther before it strikes element B. There is a finite time delay before the wavefront reaches element B.

The propagation delay may be measured by delaying the signal received at element A before summing it with that from element B. If the two signals are combined directly, the amplitude of the resultant signal will be maximum when the delay for element A exactly equals the propagation delay. This results in an in-phase condition at the summation point. Or if one of the signals is inverted and the two are summed, a null will exist when the element-A delay equals the propagation delay; the signals will combine in a 180° out-of-phase relationship. Either way, once the time delay is known, it may be converted to distance. Then the direction from which the wave is arriving may be determined by trigonometry.

By altering the delay in small increments, the peak of the antenna lobe (or the null) can be steered in azimuth. This is true without regard to the frequency of the incoming wave. Thus, as long as the delay is less than the period of one RF cycle, the system is not frequency sensitive, other than for the frequency range that may be covered satisfactorily by the array elements themselves. Surface acoustic wave (SAW) devices or lumped-constant networks can be used for delay lines in such systems if the system is used only for receiving. Rolls of coaxial cable of various lengths are used in installations for transmitting. In this case, the lines are considered for the time delay they provide, rather than as simple phasing lines. The difference is that a phasing line is ordinarily designed for a single frequency (or for an amateur band), while a delay line offers essentially the same time delay at all frequencies.

By combining signals from other Wullenweber elements appropriately, the broad beamwidth of the pattern from the two elements can be narrowed, and unwanted sidelobes can be suppressed. Then, by electronically switching the delays and attenuations to the various elements, the beam so formed can be rotated around the compass. The package of electronics designed to do this, including delay lines and electronically switched attenuators, is the beam-forming network. However, the Wullenweber system is not restricted to forming a single beam. With an isolation amplifier provided for each element of the array, several beam-forming networks can be operated independently. Imagine having an antenna system that offers a dipole pattern, a rhombic pattern, and a Yagi beam pattern, all simultaneously and without frequency sensitivity. One or more may be rotating while another is held in a particular direction. The Wullenweber was designed to fulfill this type of requirement.

One feature of the Wullenweber antenna is that it can operate 360° around the compass. In many government installations, there is no need for such coverage, as the areas of interest lie in an azimuth sector. In such cases an in-line array of elements with a backscreen or curtain reflector may be installed broadside to the center of the sector. By using the same techniques as the Wullenweber, the beams formed from this array may be slewed left and right across the sector. The maximum sector width available will depend on the installation, but beyond 70° to 80° the patterns begin to deteriorate to the point that they are unsatisfactory for precise RDF work.

RDF SYSTEM CALIBRATION AND USE

Once an RDF system is initially assembled, it should be calibrated or checked out before actually being put into use. Of primary concern is the balance or symmetry of the antenna pattern. A lop-sided figure-8 pattern with a loop, for example, is undesirable; the nulls are not 180° apart, nor are they at exact right angles to the plane of the loop. If you didn't know this fact in actual RDF work, measurement accuracy would suffer.

Initial checkout can be performed with a low-powered transmitter at a distance of a few hundred feet. It should be within visual range and must be operating into a vertical antenna. (A quarter-wave vertical or a loaded whip is quite suitable.) The site must be reasonably clear of obstructions, especially steel and concrete or brick buildings, large metal objects, nearby power lines, and so on. If the system operates above 30 MHz, you should also avoid trees and large bushes. An open field makes an excellent site.

The procedure is to find the transmitter with the RDF equipment as if its position were not known, and compare the RDF null indication with the visual path to the transmitter. For antennas having more than one null, each null should be checked.

If imbalance is found in the antenna system, there are two options available. One is to correct the imbalance. Toward this end, pay particular attention to the feed line. Using a coaxial feeder for a balanced antenna invites an asymmetrical pattern, unless an effective balun is used. A balun is not necessary if the loop is shielded, but an asymmetrical pattern can result with misplacement of the break in the shield itself. The builder may also find that the presence of a sensing antenna upsets the balance slightly, due to mutual coupling. Experiment with its position with respect to the main antenna to correct the error. You will also note that the position of the null shifts by 90° as the sensing element is switched in and out, and the null is not as deep. This is of little concern, however, as the intent of the sensing antenna is only to resolve ambiguities. The sensing element should be switched out when accuracy is desired.

The second option is to accept the imbalance of the antenna and use some kind of indicator to show the true directions of the nulls. Small pointers, painted marks on the mast, or an optical sighting system might be used. Sometimes the end result of the calibration procedure will be a compromise between these two options, as a perfect electrical balance may be difficult or impossible to attain.

The discussion above is oriented toward calibrating portable RDF systems. The same general suggestions apply if the RDF array is fixed, such as an Adcock. However, it won't be possible to move it to an open field. Instead, the array must be calibrated in its intended operating position through the use of a portable or mobile transmitter. Because of nearby obstructions or reflecting objects, the null in the pattern may not appear to indicate the precise direction of the transmitter. Do not confuse this with imbalance in the RDF array. Check for imbalance by rotating the array 180° and comparing readings.

Once the balance is satisfactory, you should make a table of bearing errors noted in different compass directions. These error values should be applied as corrections when actual measurements are made. The mobile or por-



Fig 12—A multiturn frame antenna is shown at A. L2 is the coupling loop. The drawing at B shows how L2 is connected to a preamplifier.



Fig 13—A wooden frame can be used to contain the wire of the loop shown in Fig 12.

table transmitter should be at a distance of two or three miles for these measurements, and should be in as clear an area as possible during transmissions. The idea is to avoid conduction of the signal along power lines and other overhead wiring from the transmitter to the RDF site. Of course the position of the transmitter must be known accurately for each transmission.

FRAME LOOPS

It was mentioned earlier that the earliest style of receiving loops was the frame antenna. If carefully constructed, such an antenna performs well and can be built at low cost. **Fig 12** illustrates the details of a practical frame type of loop antenna. This antenna was designed by Doug DeMaw, W1FB, and described in *QST* for July 1977. (See the Bibliography at the end of this chapter.) The circuit in Fig 12A is a 5-turn system tuned to resonance by C1. If the layout is symmetrical, good balance should be obtained. L2 helps to achieve this objective by eliminating the need for direct coupling to the feed ter-



Fig 14—An assembled table-top version of the electrostatically shielded loop. RG-58 cable is used in its construction.

minals of L1. If the loop feed were attached in parallel with C1, a common practice, the chance for imbalance would be considerable.

L2 can be situated just inside or slightly outside of L1; a 1-inch separation works nicely. The receiver or preamplifier can be connected to terminals A and B of L2, as shown in Fig 12B. C2 controls the amount of coupling between the loop and the preamplifier. The lighter the coupling, the higher is the loop Q, the narrower is the frequency response, and the greater is the gain requirement from the preamplifier. It should be noted that no attempt is being made to match the extremely low loop impedance to the preamplifier.

A supporting frame for the loop of Fig 12 can be constructed of wood, as shown in **Fig 13**. The dimensions given are for a 1.8-MHz frame antenna. For use on 75 or 40 meters, L1 of Fig 12A will require fewer turns, or the size of the wooden frame should be made somewhat smaller than that of Fig 13.

SHIELDED FRAME LOOPS

If electrostatic shielding is desired, the format shown in **Fig 14** can be adopted. In this example, the loop conductor and the single-turn coupling loop are made from RG-58 coaxial cable. The number of loop turns should be sufficient to resonate with the tuning capacitor at the operating frequency. Antenna resonance can be checked by first connecting C1 (Fig 12A) and setting it at midrange. Then connect a small 3-turn coil to the loop feed terminals, and couple to it with a dip meter. Just remember that the pickup coil will act to lower the frequency slightly from actual resonance.

In the antenna photographed for Fig 14, the 1-turn coupling loop was made of #22 plastic-insulated wire. However, electrostatic noise pickup occurs on such a coupling loop, noise of the same nature that the shield on the main loop prevents. This can be avoided by using RG-58 for the coupling loop. The shield of the coupling loop should be opened for about 1 inch at the top, and each end of the shield grounded to the shield of the main loop.

Larger single-turn frame loops can be fashioned from aluminum-jacketed Hardline, if that style of coax is available. In either case, the shield conductor must be opened at the electrical center of the loop, as shown in **Fig 15** at A and B. The design example is for 1.8-MHz operation.

To realize the best performance from an electrostatically shielded loop antenna, you must operate it near to and directly above an effective ground plane. An automobile roof (metal) qualifies nicely for small shielded loops. For fixed-station use, a chicken-wire ground screen can be placed below the antenna at a distance of 1 to 6 feet.


87.5"
Braid
RG - 58
Remove 1" of Braid
(A)
4 Turns RG - 58
1 Turn RG - 58 (Center Inside L1)
L1
Remove 1" of Braid
13.5"
L2
Split Shield
Center Conductor
Braid
Braid and Center Conductor
1000
to Preamp.
1000 pF
Tape
(B)
Tape coax turns tightly together, side by side. Tape L2 inside L1 between turns 2 and 3
(C)
ANT0549

Fig 15—Components and assembly details of the shielded loop shown in Fig 14.


1.8 -2.0 MHz
L2
C2
1000
to Preamp. and Receiver
L1
C1A
C1B
100
100
(A)
Electrostatic Shield
1.8 -2.0 MHz Open
L2
C2
1000
to Preamp. and Receiver
L1
C1
200
(B)

Fig 16—At A, the diagram of a ferrite loop. C1 is a dual-section air-variable capacitor. The circuit at B shows a rod loop contained in an electrostatic shield channel (see text). A suitable low-noise preamplifier is shown in Fig 19.



Fig 17—The assembly at the top of the picture is a shielded ferrite-rod loop for 160 meters. Two rods have been glued end to end (see text). The other units in the picture are a low-pass filter (lower left), broadband preamplifier (lower center) and a Tektronix step attenuator (lower right). These were part of the test setup used when the antenna was evaluated.

FERRITE-CORE LOOPS

Fig 16 contains a diagram for a rod loop (loopstick antenna). This antenna was also designed by Doug DeMaw, W1FB, and described in *QST* for July 1977. The winding (L1) has the appropriate number of turns to permit resonance with C1 at the operating frequency. L1 should be spread over approximately $^1/_3$ of the core center. Litz wire will yield the best Q, but Formvar magnet wire can be used if desired. A layer of 3M Company glass tape (or Mylar tape) is recommended as a covering for the core before adding the wire. Masking tape can be used if nothing else is available.

L2 functions as a coupling link over the exact center of L1. C1 is a dual-section variable capacitor, although a differential capacitor might be better toward obtaining optimum balance. The loop Q is controlled by means of C2, which is a mica-compression trimmer.

Electrostatic shielding of rod loops can be effected by centering the rod in a U-shaped aluminum, brass or copper channel, extending slightly beyond the ends of the rod loop (1 inch is suitable). The open side (top) of the channel can't be closed, as that would constitute a shorted turn and render the antenna useless. This can be proved by shorting across the center of the channel with a screwdriver blade when the loop is tuned to an incoming signal. The shield-braid gap in the coaxial loop of Fig 15 is maintained for the same reason.

Fig 17 shows the shielded rod loop assembly. This antenna was developed experimentally for 160 meters and uses two 7-inch ferrite rods, glued together end-to-end with epoxy cement. The longer core resulted in improved sensitivity for weak-signal reception. The other items in the photograph were used during the evaluation tests and are not pertinent to this discussion. This loop and the frame loop discussed in the previous section have bidirectional nulls, as shown in Fig 1A.

Obtaining a Cardioid Pattern

Although the bidirectional pattern of loop antennas



Except as indicated, decimal values of capacitance are in microfarads (μF); others are in picofarads (pF); resistances are in ohms; k=1,000, M=1,000,000.

Fig 18—Schematic diagram of a rod-loop antenna with a cardioid response. The sensing antenna, phasing network and a preamplifier are shown also. The secondary of T1 and the primary of T2 are tuned to resonance at the operating frequency of the loop. T-68-2 to T-68-6 Amidon toroid cores are suitable for both transformers. Amidon also sells ferrite rods for this type of antenna.



Except as indicated, decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); resistances are in ohms; k=1,000, M=1,000,000.

Fig 19—Schematic diagram of a two-stage broadband amplifier patterned after a design by Wes Hayward, W7ZOI. T1 and T2 have a 4:1 impedance ratio and are wound on FT-50-61 toroid cores (Amidon) which have a μ_i of 125. They contain 12 turns of #24 enamel wire, bifilar wound. The capacitors are disc ceramic. This amplifier should be built on double-sided circuit board for best stability.

can be used effectively in tracking down signal sources by means of triangulation, an essentially unidirectional loop response will help to reduce the time spent finding the fox. Adding a sensing antenna to the loop is simple to do, and it will provide the desired cardioid response. The theoretical pattern for this combination is shown in Fig 1D.

Fig 18 shows how a sensing element can be added to a loop or loopstick antenna. The link from the loop is connected by coaxial cable to the primary of T1, which is a tuned toroidal transformer with a split secondary winding. C3 is adjusted for peak signal response at the frequency of interest (as is C4), then R1 is adjusted for minimum back response of the loop. It will be necessary to readjust C3 and R1 several times to compensate for the interaction of these controls. The adjustments are repeated until no further null depth can be obtained. Tests at ARRL Headquarters showed that null depths as great as 40 dB could be obtained with the circuit of Fig 18 on 75 meters. A near-field weak-signal source was used during the tests.

The greater the null depth, the lower the signal output from the system, so plan to include a preamplifier with 25 to 40 dB of gain. Q1 shown in Fig 18 will deliver approximately 15 dB of gain. The circuit of **Fig 19** can be used following T2 to obtain an additional 24 dB of gain. In the interest of maintaining a good noise figure, even at 1.8 MHz, Q1 should be a low-noise device. A 2N4416, an MPF102, or a 40673 MOSFET would be satisfactory. The sensing antenna can be mounted 6 to 15 inches from the loop. The vertical whip need not be more than 12 to 20 inches long. Some experimenting may be necessary in order to obtain the best results. Optimization will also change with the operating frequency of the antenna.

A SHIELDED LOOP WITH SENSING ANTENNA FOR 28 MHz

Fig 20 shows the construction and mounting of a simple shielded 10-meter loop. The loop was designed by Loren Norberg, W9PYG, and described in *QST* for April 1954. (See the Bibliography at the end of this chapter.) It is made from an 18-inch length of RG-11 coax (either solid or foam dielectric) secured to an aluminum box of any convenient size, with two coaxial cable hoods (Amphenol 83-1HP). The outer shield must be broken at the exact center. C1 is a 25-pF variable capacitor, and is connected in parallel with a 33-pF fixed mica padder capacitor, C3. C1 must be tuned to the desired frequency while the loop is connected to the receiver in the same way as it will be used for RDF. C2 is a small differential capacitor used to provide electrical symmetry. The lead-in to the receiver is 67 inches of RG-59 (82 inches if the cable has a foamed dielectric).

The loop can be mounted on the roof of the car with a rubber suction cup. The builder might also fabricate some kind of bracket assembly to mount the loop temporarily in the window opening of the automobile, allowing for loop rotation. Reasonably true bearings may be obtained through the windshield when the car is pointed in the direction of the hidden transmitter. More accurate bearings may be obtained with the loop held out the window and the signal coming toward that side of the car.

Sometimes the car broadcast antenna may interfere with accurate bearings. Disconnecting the antenna from the broadcast receiver may eliminate this trouble.

Sensing Antenna

A sensing antenna can be added to Norberg's loop above to determine which of the two directions indicated by the loop is the correct one. Add a phono jack to the top of the aluminum case shown in Fig 20. The insulated center terminal of the jack should be connected to the side of the tuning capacitors that is common to the center conductor of the RG-59 coax feed line. The jack then takes a short vertical antenna rod of the diameter to fit the jack, or a piece of #12 or #14 solid wire may be soldered to the center pin of a phono plug for insertion in the jack. The sensing antenna can be plugged in as needed. Starting with a length of about four times the loop diameter, the length of the sensing antenna should be pruned until the pattern is similar to that of Fig 1D.



Fig 20—Sketch showing the constructional details of the 28-MHz RDF loop. The outer braid of the coax loop is broken at the center of the loop. The gap is covered with waterproof tape, and the entire assembly is given a coat of acrylic spray.

THE SNOOP LOOP—FOR CLOSE-RANGE HF RDF

Picture yourself on a hunt for a hidden 28-MHz transmitter. The night is dark, very dark. After you take off at the start of the hunt, heading in the right direction, the signal gets stronger and stronger. Your excitement increases with each additional S unit on the meter. You follow your loop closely, and it is working perfectly. You're getting out of town and into the countryside. The roads are unfamiliar. Now the null is beginning to swing rather rapidly, showing that you are getting close.

Suddenly the null shifts to give a direction at right angles to the car. With your flashlight you look carefully across the deep ditch beside the road and into the dark field where you know the transmitter is hidden. There are no roads into the field as far as you can see in either direction. You dare not waste miles driving up and down the road looking for an entrance, for each tenth of a mile counts. But what to do?—Your HF transceiver is mounted in your car and requires power from your car battery.

In a brief moment your decision is made. You park



Fig 21—The box containing the detector and amplifier is also the "handle" for the Snoop Loop. The loop is mounted with a coax T as a support, a convenience but not an essential part of the loop assembly. The loop tuning capacitor is screwdriver adjusted. The on-off switch and the meter sensitivity control may be mounted on the bottom.


7-1/2"
Except as indicated, decimal values of capacitance are in microfarads (μF); others are in picofarads (pF); resistances are in ohms; k=1,000, M=1,000,000.
Gap
RG – 8
Zero Adj.
R1
100 k
Q1
C
B
E
D1
1N34A
A
C1
25
B
0.0047
R2
50 k
Sens.
0-1
mA
+
560
–
560
BT1
+
3 V
S1
DS1
S2

Fig 22—The Snoop Loop circuit for 28-MHz operation. The loop is a single turn of RG-8 inner conductor, the outer conductor being used as a shield. Note the gap in the shielding; about a 1-inch section of the outer conductor should be cut out. Refer to Fig 23 for alternative connection at points A and B for other frequencies of operation.

- **BT1—Two penlight cells.**
- **C1—25-pF midget air padder.**
- **D1—Small-signal germanium diode such as 1N34A or equiv.**
- **DS1—Optional 2-cell penlight lamp for meter illumination, such as no. 222.**
- **Q1—PNP transistor such as ECG102 or equiv.**
- **R1—100-kΩ potentiometer, linear taper. May be PC-mount style.**
- **R2—50-kΩ potentiometer, linear taper.**
- **S1—SPST toggle.**
- **S2—Optional momentary push for illuminating meter.**



Fig 23—Input circuit for lower frequency bands. Points A and B are connected to corresponding points in the circuit of Fig 22, substituting for the loop and C1 in that circuit. L1-C1 should resonate within the desired amateur band, but the L/C ratio is not critical. After construction is completed, adjust the position of the tap on L1 for maximum signal strength. Instead of connecting the RDF loop directly to the tap on L1, a length of low impedance line may be used between the loop and the tuned circuit, L1-C1.



Fig 24—Unidirectional 3.5-MHz RDF using ferrite-core loop with sensing antenna. Adjustable components of the circuit are mounted in the aluminum chassis supported by a short length of tubing.

beside the road, take your flashlight, and plunge into the veldt in the direction your loop null clearly indicated. But after taking a few steps, you're up to your armpits in brush and can't see anything forward or backward. You stumble on in hopes of running into the hidden transmitter—you're probably not more than a few hundred feet from it. But away from your car and radio equipment, it's like the proverbial hunt for the needle in the haystack. What you really need is a portable setup for hunting at close range, and you may prefer something that is inexpensive. The Snoop Loop was designed for just these requirements by Claude Maer, Jr, WØIC, and was described in *QST* for February 1957. (See the Bibliography at the end of this chapter.)

The Snoop Loop is pictured in **Fig 21**. The loop itself is made from a length of RG-8 coax, with the shield broken at the top. A coax T connector is used for convenience and ease of mounting. One end of the coax loop is connected to a male plug in the conventional way, but the center conductor of the other end is shorted to the shield so the male connector at that end has no connection to the center prong. This results in an unbalanced circuit, but seems to give good bidirectional null readings, as well as an easily detectable maximum reading when the grounded end of the loop is pointed in the direction of the transmitter. Careful tuning with C1 will improve this maximum reading. Don't forget to remove one inch of shielding from the top of the loop. You won't get much signal unless you do.

The detector and amplifier circuit for the Snoop Loop



Fig 25—Circuit of the 3.5-MHz direction finder loop.

C1—140 pF variable (125-pF ceramic trimmer in parallel with 15-pF ceramic fixed.

L1—Approximately 140 µH adjustable (Miller No. 4512 or equivalent.

R1—1-kΩ carbon potentiometer.

S1—SPST toggle.

Loopstick—Approximately 15 µH (Miller 705-A, with original winding removed and wound with 20 turns of #22 enamel). Link is two turns at center. Winding ends secured with Scotch electrical tape. This type of ferrite rod may also be found in surplus transistor AM radios.

is shown in **Fig 22**. The model photographed does not include the meter, as it was built for use only with high-impedance headphones. The components are housed in an aluminum box. Almost any size box of sufficient size to contain the meter can be used. At very close ranges, reduction of sensitivity with R2 will prevent pegging the meter.

The Snoop Loop is not limited to the 10-meter band or to a built-in loop. **Fig 23** shows an alternative circuit for other bands and for plugging in a separate loop connected by a low-impedance transmission line. Select coil and capacitor combinations that will tune to the desired frequencies. Plug-in coils could be used. It is a good idea to have the RF end of the unit fairly well shielded, to eliminate signal pickup except through the loop. This little unit should certainly help you on those dark nights in the country. (Tip to the hidden-transmitter operator—if you want to foul up some of your pals using these loops, just hide near the antenna of a 50-kW broadcast transmitter!)

A LOOPSTICK FOR 3.5 MHz

Figs 24 through 26 show an RDF loop suitable for the 3.5-MHz band. It uses a construction technique that has had considerable application in low-frequency marine direction finders. The loop is a coil wound on a ferrite rod from a broadcast-antenna loopstick. The loop was designed by John Isaacs, W6PZV, and described in *QST* for June 1958. Because you can make a coil with high Q using a ferrite core, the sensitivity of such a loop is comparable to a conventional loop that is a foot or so in diameter. The output of the vertical-rod sensing antenna, when properly combined with that of the loop, gives the system the cardioid pattern shown in Fig 1D.

To make the loop, remove the original winding on the ferrite core and wind a new coil, as shown in **Fig 25**. Other types of cores than the one specified may be substituted; use the largest coil available and adjust the winding so that the circuit resonates in the 3.5-MHz band within the range of C1. The tuning range of the loop may be checked with a dip meter.

The sensing system consists of a 15-inch whip and an adjustable inductor that resonates the whip as a quarter-wave antenna. It also contains a potentiometer to control the output of the antenna. S1 is used to switch the sensing antenna in and out of the circuit.

The whip, the loopstick, the inductance L1, the capacitor C1, the potentiometer R1, and the switch S1 are all mounted on a 4 × 5 × 3-inch box chassis, as shown in **Fig 26**. The loopstick may be mounted and protected inside a piece of $^1/_2$-inch PVC pipe. A section of $^1/_2$-inch electrical conduit is attached to the bottom of the chassis box and this supports the instrument.

To produce an output having only one null there must a 90° phase difference between the outputs of the loop and sensing antennas, and the signal strength from each must be the same. The phase shift is obtained by tuning the sensing antenna slightly off frequency, using the slug in L1. Since the sensitivity of the whip antenna is greater than that of the loop, its output is reduced by adjusting R1.

Adjustment

To adjust the system, enlist the aid of a friend with a mobile transmitter and find a clear spot where the transmitter and RDF receiver can be separated by several hundred feet. Use as little power as possible at the transmitter. (Make very sure you don't transmit into the loop if you are using a transceiver as a detector.) With the test transmitter operating on the proper frequency, disconnect the sensing antenna with S1, and peak the loopstick using C1, while watching the S meter on the transceiver. Once the loopstick is peaked, no further adjustment of C1 will be necessary. Next, connect the sensing antenna and turn R1 to minimum resistance. Then vary the adjustable slug of L1 until a maximum reading of the S meter is again obtained. It may be necessary to turn the unit a bit during this adjustment to obtain a higher reading than with the loopstick alone. The last turn of the slug is quite critical, and some hand-capacitance effect may be noted.

Now turn the instrument so that one side (not an end) of the loopstick is pointed toward the test transmitter. Turn R1 a complete revolution and if the proper side was chosen a definite null should be observed on the S meter for one particular position of R1. If not, turn the RDF 180° and try again. This time leave R1 at the setting producing



Fig 26—Components of the 3.5-MHz RDF are mounted on the top and sides of a channel-lock type box. In this view R1 is on the left wall at the upper left and C1 is at the lower left. L1, S1 and the output connector are on the right wall. The loopstick and whip mount on the outside.


20″
19″
19″
19″
2″ Squares of Circuit Board Material
Two 18″ Radials for Each Radiator
BNC Female
Circuit Board Material
(A)
(B)

Fig 27—At A is a simple configuration that can produce a cardioid pattern. At B is a convenient way of fabricating a sturdy mount for the radiator using BNC connectors.

the minimum reading. Now adjust L1 very slowly until the S-meter reading is reduced still further. Repeat this several times, first R1, and then L1, until the best minimum is obtained.

Finally, as a check, have the test transmitter move around the RDF and follow it by turning the RDF. If the tuning has been done properly the null will always be broadside to the loopstick. Make a note of the proper side of the RDF for the null, and the job is finished.

A 144-MHZ CARIOID-PATTERN RDF ANTENNA

Although there may be any number of different VHF antennas that can produce a cardioid pattern, a simple design is depicted in **Fig 27**. Two $^1/_4$-wavelength vertical elements are spaced one $^1/_4$-λ apart and are fed 90° out of phase. Each radiator is shown with two radials approximately 5% shorter than the radiators. This array was designed by Pete O'Dell, KB1N, and described in *QST* for March 1981.

Computer modeling showed that slight alterations in the size, spacing and phasing of the elements strongly impact the pattern. The results suggest that this system is a little touchy and that the most significant change comes at the null. Very slight alterations in the dimensions caused the notch to become much more shallow and, hence, less usable for RDF. Early experience in building a working model bore this out.

This means that if you build this antenna, you will find it advantageous to spend a few minutes to tune it carefully for the deepest null. If it is built using the techniques presented here, then this should prove to be a small task, well worth the extra effort. Tuning is accomplished by adjusting the length of the vertical radiators, the spacing between them and, if necessary, the lengths of the phasing harness that connects them. Tune for the deepest null on your S meter when using a signal source such as a moderately strong repeater.

This should be done outside, away from buildings and large metal objects. Initial indoor tuning on this project was tried in the kitchen, which revealed that reflections off the appliances were producing spurious readings. Beware too of distant water towers, radio towers, and large office or apartment buildings. They can reflect the signal and give false indications.

Construction is simple and straightforward. Fig 27B shows a female BNC connector (RadioShack 278-105) that has been mounted on a small piece of PC-board material. The BNC connector is held upside down, and the vertical radiator is soldered to the center solder lug. A 12-inch piece of brass tubing provides a snug fit over the solder lug. A second piece of tubing, slightly smaller in diameter, is telescoped inside the first. The outer tubing is crimped slightly at the top after the inner tubing is installed. This provides positive contact between the two tubes. For 146 MHz the length of the radiators is calculated to be about 19 inches. You should be able to find small brass tubing at a hobby store. If none is available in your area, consider brazing rods. These are often available in hardware sections of discount stores. It will probably be necessary to solder a short piece to the top since these come in 18-inch sections. Also, tuning will not be quite as convenient. Two 18-inch radials are added to each element by soldering them to the board. Two 36-inch pieces of heavy brazing rod were used in this project.

The Phasing Harness

As shown in **Fig 28**, a T connector is used with two different lengths of coaxial line to form the phasing harness. This method of feeding the antenna is superior over



Fig 28—The phasing harness for the phased 144-MHz RDF array. The phasing sections must be measured from the center of the T connector to the point that the vertical radiator emerges from the shielded portion of the upside-down BNC female. Don't forget to take the length of the connectors into account when constructing the harness. If care is taken and coax with solid polyethylene dielectric is used, you should not have to prune the phasing line. With this phasing system, the null will be in a direction that runs along the boom, on the side of the $^1/_4$-wavelength section.



Fig 29—A simple mechanical support for the DF antenna, made of PVC pipe and fittings.

other simple systems to obtain equal currents in the two radiators. Unequal currents tend to reduce the depth of the null in the pattern, all other factors being equal.

The $^1/_2$-wavelength section can be made from either RG-58 or RG-59, because it should act as a 1:1 transformer. With no radials or with two radials perpendicular to the vertical element, it was found that a $^1/_4$-wavelength section made of RG-59 75-Ω coax produced a deeper notch than a $^1/_4$-wavelength section made of RG-58 50-Ω line. However, with the two radials bent downward somewhat, the RG-58 section seemed to outperform the RG-59. Because of minor differences in assembly techniques from one antenna to another, it will probably be worth your time and effort to try both types of coax and determine what works best for your antenna. You may also want to try bending the radials down at slightly different angles for the best null performance.

The most important thing about the coax for the harness is that it be of the highest quality (well-shielded and with a polyethylene dielectric). The reason for avoiding foam dielectric is that the velocity factor can vary from one roll to the next—some say that it varies from one foot to the next. Of course, it can be used if you have test equipment available that will allow you to determine its electrical length. Assuming that you do not want to or cannot go to that trouble, stay with coax having a solid polyethylene dielectric. Avoid coax that is designed for the CB market or do-it-yourself cable-TV market. (A good choice is Belden 8240 for the RG-58 or Belden 8241 for the RG-59.)

Both RG-58 and RG-59 with polyethylene dielectric have a velocity factor of 0.66. Therefore, for 146 MHz a quarter wavelength of transmission line will be 20.2 inches × 0.66 = 13.3 inches. A half-wavelength section will be twice this length or 26.7 inches. One thing you must take into account is that the transmission line is the total length of the cable *and the connectors*. Depending on the type of construction and the type of connectors that you choose, the actual length of the coax by itself will vary somewhat. You will have to determine that for yourself.

Y connectors that mate with RCA phono plugs are widely available and the phono plugs are easy to work with. Avoid the temptation, however, to substitute these for the T and BNC connectors. Phono plugs and a Y connector were tried. The results with that system were not satisfactory. The performance seemed to change from day to day and the notch was never as deep as it should have been. Although they are more difficult to find, BNC T connectors will provide superior performance and are well worth the extra cost. If you must make substitutions, it would be preferable to use UHF connectors (type PL-259).

Fig 29 shows a simple support for the antenna. PVC tubing is used throughout. Additionally, you will need a T fitting, two end caps, and possibly some cement. (By not cementing the PVC fittings together, you will have the option of disassembly for transportation.) Cut the PVC for the dimensions shown, using a saw or a tubing cutter.



Fig 30—At the left, A_T represents the antenna of the hidden transmitter, T. At the right, rapid switching between antennas A_1 and A_2 at the receiver samples the phase at each antenna, creating a pseudo-Doppler effect. An FM detector detects this as phase modulation.



Fig 31—If both receiving antennas are an equal distance (D) from the transmitting antenna, there will be no difference in the phase angles of the signals in the receiving antennas. Therefore, the detector will not detect any phase modulation, and the audio tone will disappear from the output of the detector.

A tubing cutter is preferred because it produces smooth, straight edges without making a mess. Drill a small hole through the PC board near the female BNC of each element assembly. Measure the 20-inch distance horizontally along the boom and mark the two end points. Drill a small hole vertically through the boom at each mark. Use a small nut and bolt to attach each element assembly to the boom.

Tuning

The dimensions given throughout this section are those for approximately 146 MHz. If the signal you will be hunting is above that frequency, then the measurements should be a bit shorter. If you wish to operate below that frequency, then they will need to be somewhat longer. Once you have built the antenna to the rough size, the fun begins. You will need a signal source near the frequency that you will be using for your RDF work. Adjust the length of the radiators and the spacing between them for the deepest null on your S meter. Make changes in increments of $^1/_4$ inch or less. If you must adjust the phasing line, make sure that the $^1/_4$-wavelength section is exactly one-half the length of the half-wavelength section. Keep tuning until you have a satisfactorily deep null on your S meter.

THE DOUBLE-DUCKY DIRECTION FINDER

For direction finding, most amateurs use antennas having pronounced directional effects, either a null or a peak in signal strength. FM receivers are designed to eliminate the effects of amplitude variations, and so they are difficult to use for direction finding without looking at an S meter. Most modern HT transceivers do not have S meters.

This classic "Double-Ducky" direction finder (DDDF) was designed by David Geiser, WA2ANU, and was described in *QST* for July 1981. It works on the principle of switching between two nondirectional antennas, as shown in **Fig 30**. This creates phase modulation on the incoming signal that is heard easily on the FM receiver. When the two antennas are exactly the same distance (phase) from the transmitter, as in **Fig 31**, the tone disappears. (This technique is also known in the RDF literature as *Time-Difference-of-Arrival*, or TDOA, since signals arrive at each antenna at slightly different times, and hence at slightly different phases, from any direction except on a line perpendicular to and halfway in-between the two antennas. Another general term for this kind of two-antenna RDF technique is *interferometer*. *—Ed.*)

In theory the antennas may be very close to each other, but in practice the amount of phase modulation increases directly with the spacing, up to spacings of a half wavelength. While a half-wavelength separation on 2 meters (40 inches) is pretty large for a mobile array, a quarter wavelength gives entirely satisfactory results, and even an eighth wavelength (10 inches) is acceptable.

Think in terms of two antenna elements with fixed spacing. Mount them on a ground plane and rotate that ground plane. The ground plane held above the hiker's head or car roof reduces the needed height of the array and the directional-distorting effects of the searcher's body or other conducting objects.

The DDDF is bidirectional and, as described, its tone null points both toward and away from the signal origin. An L-shaped search path would be needed to resolve the ambiguity. Use the techniques of triangulation described earlier in this chapter.

Specific Design

It is not possible to find a long-life mechanical switch operable at a fairly high audio rate, such as 1000 Hz. Yet we want an audible tone, and the 400- to 1000-Hz range is perhaps most suitable considering audio amplifiers and average hearing. Also, if we wish to use the transmit function of a transceiver, we need a switch that will carry per-


Except as indicated, decimal values of capacitance are in microfarads (μF); others are in picofarads (pF); resistances are in ohms; k=1,000, M=1,000,000.
"Rubber Duckies"
BNC
BNC
D1
D2
RFC 1
RFC 2
RG – 58
1/2 Wave
RG – 58
1/2 Wave
BNC T
D3
XMIT
9 V
S1
OFF
DF
RG – 58
Less Than
8 Ft
330
1/4 W
4.7μF
30 V
RFC 3
BNC
U1
567
4
Drive
1 k
Non –Pol.
560
3
V+
Input
8
Output
560
7
GND
Tone
Decoder
BNC
to Transceiver
6
Timing
Cap.
Timing
Resistor
5
Phono
90° Audio
(Test)
10 k
20 k
Pitch
0.1μF
1 k
Control Unit

Fig 32—Schematic diagram of the DDDF circuit. Construction and layout are not critical. Components inside the broken lines should be housed inside a shielded enclosure. Most of the components are available from RadioShack, except D1, D2, the antennas and RFC1-RFC3. These components are discussed in the text. S1—See text.

haps 10 W without much problem.

A solid-state switch, the PIN diode is used. The intrinsic region of this type of diode is ordinarily bare of current carriers and, with a bit of reverse bias, looks like a low-capacitance open space. A bit of forward bias (20 to 50 mA) will load the intrinsic region with current carriers that are happy to dance back and forth at a 148-MHz rate, looking like a resistance of an ohm or so. In a 10-W circuit, the diodes do not dissipate enough power to damage them.

Because only two antennas are used, the obvious approach is to connect one diode *forward* to one antenna, to connect the other *reverse* to the second antenna and to drive the pair with square-wave audio-frequency ac. **Fig 32** shows the necessary circuitry. RF chokes (Ohmite Z144, J. W. Miller RFC-144 or similar vhf units) are used to let the audio through to bias the diodes while blocking RF. Of course, the reverse bias on one diode is only equal to the forward bias on the other, but in practice this seems sufficient.

A number of PIN diodes were tried in the particular setup built. These were the Hewlett-Packard HP5082-3077, the Alpha LE-5407-4, the KSW KS-3542 and the Microwave Associates M/A-COM 47120. All worked well, but the HP diodes were used because they provided a slightly lower SWR (about 3:1).

A type 567 IC is used as the square-wave generator. The output does have a dc bias that is removed with a nonpolarized coupling capacitor. This minor inconvenience is more than rewarded by the ability of the IC to work well with between 7 and 15 volts (a nominal 9-V minimum is recommended).



Fig 33—Ground-plane layout and detail of parts at the antenna connectors.



Fig 34—Photo of Fox-Hunting DF Twin 'Tenna set up as a horizontally polarized, 3-element Yagi.

The nonpolarized capacitor is also used for dc blocking when the function switch is set to XMIT. D3, a light-emitting diode (LED), is wired in series with the transmit bias to indicate selection of the XMIT mode. In that mode there is a high battery current drain (20 mA or so). S1 should be a center-off locking type toggle switch. An ordinary center-off switch may be used, but beware. If the switch is left on XMIT you will soon have dead batteries.

Cables going from the antenna to the coaxial T connector were cut to an electrical $^1/_2$ wavelength to help the open circuit, represented by the reverse-biased diode, look open at the coaxial T. (The length of the line within the T was included in the calculation.)

The length of the line from the T to the control unit is not particularly critical. If possible, keep the total of the cable length from the T to the control unit to the transceiver under 8 feet, because the capacitance of the cable does shunt the square-wave generator output.

Ground-plane dimensions are not critical. See **Fig 33**. Slightly better results may be obtained with a larger ground plane than shown. Increasing the spacing between the pickup antennas will give the greatest improvement. Every doubling (up to a half wavelength maximum) will cut the width of the null in half. A 1° wide null can be obtained with 20-inch spacing.

DDDF Operation

Switch the control unit to DF and advance the drive potentiometer until a tone is heard on the desired signal. Do not advance the drive high enough to distort or "hash up" the voice. Rotate the antenna for a null in the fundamental tone. Note that a tone an octave higher may appear.

If the incoming signal is quite out of the receiver linear region (10 kHz or so off frequency), the off-null antenna aim may present a fairly symmetrical AF output to one side, **Fig 35A**. It may also show instability at a sharp null position, indicated by the broken line on the display in Fig 35B. Aimed to the other side of a null, it will give a greatly increased AF output, Fig 35C. This is caused by the different parts of the receiver FM detector curve used. The sudden tone change is the tip-off that the antenna null position is being passed.

The user should practice with the DDDF to become acquainted with how it behaves under known situations of signal direction, power and frequency. Even in difficult nulling situations where a lot of second-harmonic AF exists, rotating the antenna through the null position causes a very distinctive tone change. With the same frequencies and amplitudes present, the quality of the tone (timbre) changes. It is as if a note were first played by a violin, and then the same note played by a trumpet. (A good part of this is the change of phase of the fundamental and odd harmonics with respect to the even harmonics.) The listener can recognize differences (passing through the null) that would give an electronic analyzer indigestion.

A FOX-HUNTING DF TWIN 'TENNA

Interferometers give sharp bearings, but they lack sensitivity for distant work. Yagis are sensitive, but they provide relatively broad bearings. This project yields an antenna that blends both on a single boom to cover both ends of the hunt. This is a condensation of a October 1998 *QST* article by R. F. Gillette, W9PE.

A good fox-hunting antenna must meet a number of criteria: (1) small size, (2) gain to detect weak signals and (3) high directivity to pinpoint the fox. Small antennas, however, do not normally yield both gain and direc-


Switches Shown in Yagi Position
Yagi
Interferometer
S1
S3
S2
Four Ferrite Beads on each cable
Equal Lengths
8
5
RF In 1
RF In 2
3
Control 1
1
Control 2
Gnd
Gnd
7
6
MSWA–2–20
Gnd
RF Out
4
2
To Receiver
1 k
1 k
4.7 k
47 k
47 k
4.7 k
2N2222
Q2
10 k
10 k
0.01
Q1
2N2222
0.022
0.022
Q3
2N2222
Q4
2N2222
+
10 μF
15 V
+
9 V
−

Except as indicated, decimal values of capacitance are in microfarads (μF); others are in picofarads (pF); resistances are in ohms; k= 1,000.

Fig 35—Schematic of the Yagi/interferometer antenna system.

Table 1
Yagi Design

Item	*Overall Length* *(Inches)*	*Boom to Element Tip* *(Inches)*
Director length	34.75	17.00
Director to Driven El. spacing	15.75	16.00
Driven El. length	37.75	18.50
Driven El. to Reflector spacing	15.75	16.00
Reflector length	40.75	20.00

*SWR less than 1.3:1 from 144.5 to 148 MHz

tivity. By combining two antennas, all three requirements are satisfied in a way that makes a nice build-it-yourself project.

This antenna uses slide switches to configure it as either a Yagi or a single-channel interferometer. When used as an interferometer, a GaAs RF microcircuit switches the FM receiver between two matched dipoles at an audio frequency. To make the antenna compact W9PE used hinged, telescopic whips as the elements; they collapse and fold parallel to the boom for storage.

The Yagi

The Yagi is a standard three-element design, based on 0.2-λ spacing between the director, the driven element and the reflector. It yields about 7 dBi gain and a front-to-back ratio of over 15 dB. Because a slide switch is used at the center of each element and the elements have small diameters, their resonant lengths are different from typical ones. **Table 1** shows the sizes used and **Fig 34** shows the Yagi.

To make sure that radiation from the coax does not affect the pattern, the author used some ferrite beads as coaxial choke-baluns. This also prevents objects near the coax from affecting signal-strength readings. The Yagi also has a low SWR; with uncalibrated equipment, he measured less than 1.3:1 over most of the 2-meter band.

This Yagi has a lot more gain than a "rubber ducky," but we need more directivity for fox hunting. That's where the interferometer comes in.

An Interferometer

To form the interferometer, the two end elements are converted to dipoles and the center element is disabled. When the three switches in **Fig 35** are thrown to the right, the feed line to the receiver is switched from the center element to the RF switch output, and the end elements are connected via feed lines to the RF switch inputs. With the Yagi's feed point open and the driven element equidistant from both interferometer antennas, the center element should have no effect on the interferometer. Nonetheless, it's easier to collapse the driven-element whips and get them out of the way than to worry about spacing.

Now if both interferometer coax cables are of equal length (between the antennas and switch) and the two antennas are the same distance from the transmitter (broadside to it), the signals from both antennas will be in phase. Switching from one antenna to the other will have no effect on the received signal. If one antenna is a little closer to the transmitter than the other, however, there will be a phase shift when we switch antennas.

When the antenna switch is at an audio rate, say 700 Hz, the repeated phase shifts result in a set of 700 Hz sidebands. At this point, all that was needed was a circuit to switch from one antenna to the other at an audio rate. W9PE chose a low-cost Mini-Circuits MSWA-2-20 GaAs RF switch driven by a simple multivibrator and buffer. The GaAs switch is rated to 2.0 GHz, hence this switching concept can easily be scaled to other ham bands. The PC board should work through the 440 MHz ham band. The author suggests adding a ground plane under the RF portion of the PC board and testing it before using it at a higher frequency.

The RF switch is controlled by a set of equal-amplitude, opposite-phase square waves: 0 V at one control port and –8 to –12 V at the other. (Mini Circuits is unclear about maximum voltages for this device. For safety, don't power it with more than 9 V.—*Ed*.) The opposite controls the other switch position. A 9-V battery was used as the power supply, with the positive terminal grounded. This results in a 0 V control signal to the RF switch when the buffer transistor is off and a Vsat (about 0.2 V less than the –9 V battery: –8.8 V) signal when the buffer transistor is saturated. The multi-vibrator has two outputs, and each drives a buffer resulting in the required equal-and-opposite-phase drive signals.

Table 2
Bill of Materials

Quantity	*Item*
3 ft	$^3/_4$-inch aluminum U channel
6 sets	insulated shoulder washers for elements
1	9 V battery
1	9 V battery connector
1	10 µF, 16 V electrolytic capacitor
1	0.01 µF, 25 V capacitor
2	0.022 µF, 25 V capacitor
2	1 kΩ $^1/_8$ W resistor
2	4.7 kΩ $^1/_8$ W resistor
2	10 kΩ $^1/_8$ W resistor
2	47 kΩ $^1/_8$ W resistor
2	1 kΩ $^1/_8$ W resistor
4	2N2222 transistors
1	Mini-Circuits MSWA-2-20 (Mini-Circuits Labs, 13 Neptune Ave, Brooklyn, NY 11235; tel 718-934-4500, 417-335-5935, fax 718-332-4661; e-mail **sales@minicircuits.com**; URL **www.minicircuits.com**)
3	DPDT slide switch (1$^1/_8$-inch, 29 mm, mounting centers), Stackpole, 3 A, 125 V used
10 ft	50 Ω coax (0.140-inch maximum OD)
1	coaxial connector (receiver dependent)
1	lot, mounting hardware
1	lot, heat-shrink tubing or equal
4	cable ties
1	2 × 3.5-inch single-sided fiberglass PC board
1	1-inch PVC conduit
12	#FB-20 ferrite beads 0.14-inch ID, 0.5-inch long (All Electronics Corp: PO Box 567, Van Nuys, CA 91408-0567; tel 888-826-5432, fax 818-781-2653, e-mail: **allcorp@allcorp.com**; URL **www.allcorp.com/**.)
6	20$^1/_2$-inch telescoping antenna elements (Nebraska Surplus, tel 402-346-4750; e-mail **grinnell@probe.net**)
1	Special resist film (Techniks Inc, PO Box 463, Ringoes, NJ 08551; tel 908-788-8249, fax 908-788-8837; e-mail **techniks@idt.net**; URL **www.techniks.com/**)

Circuit Construction

After he selected the Mini-Circuits RF switch, W9PE realized that its small size would be best handled with a simple PC board. He made the prototype boards with a photocopy transparency technique.

A power on-off switch was not used, as the 9-V bat-



NOTE: Cut a 1/2" wide ring from a PVC union that will slip over the prongs; heat prongs to bend out forming a small detent. With mast in place, (horizontal or vertical) the ring slipped over the prongs will lock the mast.

Fig 36—Boom-drilling and mast-machining details.

tery connector serves the same function. The battery fits tightly in the 3/4-inch U channel. W9PE covered the circuit board with a plastic-lined aluminum cover, but plastic film and some aluminum foil, provide the same function. A cable tie will strap either into the U channel.

Table 2 is a complete bill of materials. You can use any telescoping elements, providing that they extend to over 20 inches and have a mounting stud long enough to accommodate the insulated washers. As an alternate to the stud, they can have ends tapped to receive a screw for the insulated mounting. The author picked up his elements at a hamfest from the vendor listed; they are also available from most electronic parts houses. The Mini-Circuit RF switch is a currently available part.

Antenna Construction

Fig 35 shows the antenna schematic. It shows all three switches in the Yagi position; each would slide to the right for interferometer use. Slide switches work pretty well at 2 meters. Each of the elements is mounted to the boom with insulating washers, and a strip of copper stock connects each element to its slide switch. (You can substitute copper braid, solder wick, coax shield or any short, low resistance, low inductance conductor for the copper stock.) This switching arrangement allows you to switch the reflector and director from being parasitic elements (electrically continuous) to being dipoles (center fed).

Because the elements telescope, you can adjust the interferometer dipoles to exactly equal lengths each time you switch the antenna configuration from Yagi to interferometer. Again, choke baluns block RF on the outside of each element's coax.

Caution: Do not transmit when the RF switch is selected. Transmit only when in the Yagi configuration. RF power will destroy the Mini-Circuits RF switch. To be safe, lock out your transmit function. Most HTs have this capability. When using a mobile radio, disconnect the microphone. It is, however, safe to transmit in the Yagi configuration—which is nice for portable operating.

Fig 36 gives dimensions for drilling a standard 3/4-inch aluminum U channel for the boom and shows how the author cut a 1-inch PVC pipe (plastic conduit) for a mast and a mast locking ring. If PVC conduit is not available in your area, PVC water pipe (and a PVC union for the locking ring) will work. This mast allows mounting the antenna for either vertical or horizontal polarization.

Be sure to test the plastic pipe you use for low RF loss. Do this by heating a sample in a microwave oven. Place a pipe sample and a glass of water in the oven. (The sample is not placed in the glass of water; the water keeps the microwave from operating without a load.) Bring the water to a boil, and then carefully check the sample's temperature. If the sample is not hot, its RF loss is low, and the plastic can be used.

Using the Antenna

When starting a hunt, set up the Yagi antenna by placing all switches in the Yagi position. Swing all of the telescoping elements perpendicular to the boom and set the whip lengths to achieve the proper element lengths, while keeping each element symmetrical about the boom. The cables or boom can be marked with the length data.

While the signal is weak, use the Yagi. It has 7 dBi gain, but its bearing resolution is only about 20°. When the signal gets stronger, use the interferometer. It has less gain, but its bearing resolution is better than 1°. If the fox transmitter begins overloading your receiver, collapse the whips (equally) to reduce the gain and continue triangulating. Near the transmitter, you should triangulate both horizontally (azimuth) and vertically (elevation). The antenna works both ways, and the transmitter may be located above or below you.

Antenna Alternative

As an alternative to the telescoping elements, George Holada, K9GLJ, suggested using fixed-length elements with banana plugs matched to banana jacks on the boom. Three pairs would be used for the Yagi, an extra driven-element pair for the interferometer mode and two short-element pairs to reduce the received signal level if an overload condition occurs. He also suggested a PVC boom allowing the elements to be stored inside the boom.

THE FOUR-WAY MOBILE DF SYSTEM

This innovative, yet simple, RDF antenna system was described in an article by Malcolm C. Mallette, WA9BVS, in November 1995 *QST*. It is derived from the TDOA design shown earlier in this chapter by David T. Geiser, WA2ANU, and by a design by Paul Bohrer, W9DUU. (See Bibliography.)

Direction-finding often involves two different activities: DFing on foot and DFing from a vehicle. Often, you must track the signal using a vehicle, then finish the hunt on foot. Whether on foot or in a vehicle, the primary problem you'll encounter when trying to locate the transmitter is multipath reception. Multipath reception involves receiving the same signal by more than one path, one signal from the true direction of the transmitter and others by reflected paths that may come from widely different directions. VHF and UHF signals bounce off almost any object and hide the true source of a signal. For example, if there's a large metal building north of you, a signal from the south may arrive from the north because the signal bounces off the building and back to you.

Multipath reception effects can be defeated by taking a number of readings from different positions and arriving at an average direction. While moving at road speeds in a vehicle, it's possible to take a number of readings from different positions and average them, and it's also possible to average a number of readings over a distance of travel by electronic means. The true bearing to the transmitter can usually be found by either method.

DFing equipment for use on foot is simpler than systems for use on a vehicle. While afoot, you can turn at will or easily rotate an antenna. Turning a vehicle while going down a street may result in a fender-bender if you're not careful!

The simplest DFing system to use while on foot consists of an S-meter-equipped hand-held receiver and a small, hand-held Yagi with an attenuator in line between the antenna and receiver. The attenuator keeps the S meter from pinning. The direction in which the beam points when the strongest signal is received is the direction of the transmitter. Of course, you'll want to take readings at several locations at least a wavelength apart to obtain an average heading, as multipath reception can still cause false readings in some locations.

Another approach that many hams have taken is the simple WA2ANU DDFF—it is now commonly known simply as the "buzzbox." Various commercial versions of the hand-held buzzbox system are available. Some sys-



Fig 37—Front panel of the Four-Way DFer. At the extreme left of the front panel is the VOLUME control. Immediately to the right is the RCV/OFF/DF center-off toggle switch, with the damping (DMP) control switch nearby. Four LEDs mounted in a diamond pattern indicate signal direction: front (yellow), right (green), back (orange) and left (red). The horizontally mounted zero-center meter indicates left/right signal reception, the vertically mounted meter displays front/back signal reception. A small speaker is mounted on the top cover.



Fig 38—Placement of the four antennas on the author's car roof. The small object to the left of the antennas is the switch board.

tems have been upgraded to indicate whether the signal is arriving from the left or right of your position. The main drawback, however, to the buzzbox is that it's not as sensitive as a simple dipole and not nearly as sensitive as a beam.

In theory, you could take a buzzbox or Yagi/attenuator system in a car, stop periodically, get out and check the direction to the transmitter, then climb back in and drive off. Although this procedure works, it isn't very practical—it takes a long time to find the transmitter.

This design is for a left-right, front-back box (LRFB box) that indicates whether the received signal is to the left or right and whether it is to the front or back of the receiver. The location display consists of four LEDs arranged in a diamond pattern (see the title-page photo). When the top LED is on, the signal is coming from the front. When the top and right LEDs are on, the transmitter is between the front and the right. When only the right LED is on, the signal is directly to the right. When the bottom LED and right LED are on, the transmitter is to the right and to the back. The same pattern occurs around the clock. Therefore, four LEDs indicate eight directions. As most highways and streets have intersections that force a driver to choose moving straight ahead, right or left, the indication is sufficiently precise for practical transmitter hunting.

If the four-LED display is used alone, all parts can be obtained from your local Radio Shack store. Two zero-center 50-µA meters (50-0-50)—M1 and M2—can be used in addition to, or in place of, the LEDs, but RadioShack does not stock such meters. **Fig 37** shows the front panel layout of the LRFB.

The LRFB box uses four mag-mount $^1/_4$-λ antennas placed on the vehicle roof as shown in **Fig 38**. The whips in the mag mounts can be changed to $^1/_4$-λ 440-MHz whips and the antennas placed closer together when switching from 144-MHz to 440-MHz operation.

Circuit Description

See **Fig 39** in the following discussion (pages 26 and 27). U2, a 555 timer, generates a string of square-wave pulses at pin 3. The pulse frequency is determined by the setting of R4. The pulses are fed to the clock input (pin 14) of U3, a 4017 decade counter. On the first pulse, a positive voltage appears at U3, pin 3. On receipt of the second pulse from U2, pin 3 of U3 goes to ground and a positive voltage appears on pin 2. This sequence continues on successive pulses from U2 as pins 3, 2, 4, 7, 10, 1, 5, 6, 9 and 11 go positive in succession.

D1 through D5, and D6 through D10, OR the pulses. The result is that TP3 goes positive on the first pulse from U2, while TP2 is at 0 V. The next pulse of U2 results in TP2 going positive and TP3 going to 0 V. This sequence repeats as the counter goes around to make pin 3 positive again, and recycles.

Antenna Switching

U2 and U3 produce alternating pulses at TP2 and TP3. If we wanted only to alternately turn on and off two antennas, we could use the pulses at TP2 and TP3. The design ensures that the pulses at TP2 are the same length as the pulses at TP3. For the LRFB box, however, we need to switch between the left-right antennas many times, then switch between the front-back antennas many times.

Pin 12 of U3, CARRY OUT, emits a pulse every time U3 counts through its cycle of 10 pulses. The carry pulses from U3 go to U4, pin 14, the clock input of that 4017 counter. As U4 cycles, its output pins pulse; those pulses are, in effect, directed by D11 through D20.

As a result, TP4 is positive during the first 50 pulses from U2 and TP5 is positive during the second 50 pulses of U2. Q1 through Q6 form a quad AND gate. They AND the pulses at TP4 and TP5 with the alternating pulses at TP2 and TP3 so that the result is a pulse at the base of Q9, followed by a pulse at the base of Q10, a pulse at the base of Q9, and so on. The pulses alternate 25 times between Q9 and Q10. Then, as TP4 goes to 0 V, TP5 rises from 0 V to some positive voltage and the alternating pulses appear at the bases of Q7 and Q8. The pulses alternately go to the bases of Q7 and Q8 25 times. Then they alternate between the bases of Q9 and Q10 25 times. This pattern continues as long as the unit is in DF operation.

In **Fig 40**, two leads of a four-conductor-plus-ground cable to the antenna-switch board are connected to points A and B. The same pulses that turn Q7 and Q8 off and on turn on and off the left and right antennas. One of those two antennas is turned on and off in phase with Q7 and the other is turned on and off in phase with Q8. The PHASE switch, S3, determines which antenna is in phase with which transistor. Similarly, the two front/back antennas are turned on and off in phase with Q9 and Q10, and S4 determines which antenna is in phase with which transistor.

The pulses arriving at points A and B turn on and off the diodes connecting the coax of the left and right


CW
VOLUME
R19
25
LS1
8 Ω
T1
8 Ω
1 kΩ
Audio In
R10
1 k
AUDIO IN
C4
1 µF
16 V
R45
1.5 k
R21
100 k
U5
LM741
n.c
n.c.
+9 V
R23
1 M
C6
0.001
R22
100 k
C5
1 µF
16 V
n.c.
Q8
2N2222
R26
1 k
M1
50-0-50
µA
R24
4.7 k
L/R BALANCE
CW
C7 *
100 µF
6.3 V
Z
(to Fig 40)
DAMPING
S2A
Y
(to Fig 40)
C8 *
4700 µF
6.3 V
B
(to Fig 41)
Q7
2N2222
R25
1 k
R46
1 k
+
12 V dc
–
F1
2 A
S1
RCV
OFF
DF
A
(to Fig 41)
C1
0.1 µF
50 V
U1
LM317
Reg
IN
OUT
ADJ
ADJ
CW
R1
5 k
R2
220
C2
10 µF
35 V
+9 V
Q2
2N2222
Q3
2N2222
R16
220
R15
47 k
R9
47 k
R8
100 k
TP3
R3
1 k
U2
LM555
8 VCC
4 RESET
2 TRIG
6 THR
5 CONT
7 DIS
1 GND
OUT 3
n.c.
R5
10 k
TP1
U3
4017
15 CLR
13 CLKEN
14 CLK
+9 V 16 VCC
8 GND
CO 12
Y0 3
Y1 2
Y2 4
Y3 7
Y4 10
Y5 1
Y6 5
Y7 6
Y8 9
Y9 11
C3
0.01
C15
0.1
CW
R4
100 k
CLOCK FREQ.
n.c.
TP2
R6
100 k
D1-D10
1N914

Except as indicated, decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); resistances are in ohms; k=1,000, M=1,000,000.
n.c= not connected
∗See text

Fig 39—Unless otherwise specified, part numbers in parentheses are RadioShack. All fixed-value resistors are $^1/_4$-W, 5%-tolerance units. Equivalent parts can be substituted.

C1, C15—0.1-µF, 50-V (272-1069)
C2—10-µF, 35-V electrolytic capacitor (272-1025)
C3—0.01-µF, 25-V disc-ceramic capacitor (272-131)
C4, C5—1-µF, 16-V electrolytic capacitor (272-1434)
C6—0.001-µF, 25-V disc-ceramic capacitor (272-126)
C7, C9—100-µF, 6.3-V bipolar (nonpolarized) capacitor; Digi-Key P-1102, available from Digi-Key Corp, 701 Brooks Ave S, PO Box 677, Thief River Falls, MN 56701-0677, tel 800-344-4539, 218-681-6674; fax: 218-681-3880; RadioShack stocks 100-µF, 35-V axial (272-1016) and radial-lead (272-1028) electrolytic capacitors.
C8, C10—4700-µF, 6.3-V bipolar capacitor (made of five 1000-µF, 6.3-V bipolar capacitors), Digi-Key P1106. Standard 1000-µF, 35-V radial and axial-lead electrolytic capacitors are available from RadioShack; a 4700-µF, 35-V axial-lead electrolytic capacitor is also available (272-1022). Note that C7, C8, C9 and C10 are non-polarized capacitors because a small reverse voltage can appear across the meter and capacitors when the system is in use. Standard polarized electrolytics have been used in a number of units using this circuit (the same detector circuit used in W9DUU's unit) without any known ill effects, however.
D1-D20—1N914 silicon switching diode (276-1620 or 276-1122)
F1—2-A fuse (270-1007)
LS1—8-W speaker (40-245)


Q10
2N2222
R28
1 k
D
(to Fig 41)
X (to Fig 40)
F/B
BALANCE
R27
4.7 k
M2
50-0-50
μA
C9 *
100 μF
6.3 V
C10 *
4700 μF
6.3 V
CW
S2B
DAMPING
W (to Fig 40)
C
(to Fig 41)
Q9
2N2222
R29
1 k
TP5
U4
74HC4017
15 CLR
13 CLKEN
14 CLK
16 VCC
8 GND
CO 12 n.c.
Y0 3
Y1 2
Y2 4
Y3 7
Y4 10
Y5 1
Y6 5
Y7 6
Y8 9
Y9 11
R62
1 k
+9 V
D11-D15
1N914
TP4
R17
47 k
Q6
2N2222
R11
47 k
R13
47 k
R18
220
+9 V
R7
47 k
Q1
2N2222
D16-D20
1N914
R14
220
Q5
2N2222
Q4
2N2222
R12
220

M1, M2—Zero-center, 50-µA meter; optional—see text
Q1-Q10—MPS2222 or 2N2222 NPN silicon general-purpose transistors (276-2009)
R1, R24, R27—4.7 kΩ (271-281); note: many of the fixed-value resistors can be found in RadioShack resistor assortment packages 271-308 and 271-312.
R2, R12, R14, R16, R18—220 Ω (271-1330)
R3, R25, R26, R28, R29—1 kΩ (271-1321)
R4—100-kΩ trimmer potentiometer (271-284)
R5—10 kΩ (271-1335)
R6, R8, R21, R22—100 kΩ (271-1347)
R7, R9, R11, R13, R15, R17—47 kΩ (271-1342)
R10—1-kΩ trimmer potentiometer (271-280)
R19—25-Ω panel-mount potentiometer (271-265A)
R23—1 MΩ (271-1134)
R45—1.5 kΩ (part of 271-312 assortment)
S1—SPDT, center-off switch (275-325)
S2—DPDT switch (275-626)
T1—8-Ω to 1-kΩ audio-output transformer (273-1380)
U1—LM317T, 1.5-A, three-terminal, adjustable voltage regulator (276-1778)
U2—555 timer (276-1723)
U3, U4—4017 decade counter (276-2417)
U5—LM741 op amp (276-007)
Misc: two 8-pin IC sockets (276-1995); two 16-pin IC sockets (276-1992); experimenter's PC board (276-148) or FAR Circuits PC board set; enclosure; four mag-mount antennas, four-conductor shielded cable; in-line fuse holder (270-1281).


Coax to Left Antenna
Coax to Right Antenna
Phase 1
S3
A
B
to Fig 39
C
D
Phase 2
S4
Phase Switches (in Enclosure)
J1 P1
R51
2 kΩ
R52
2 kΩ
D22
D23
R53
2 kΩ
D24
D25
R54
2 kΩ
R50
2 kΩ
50-Ω Coax to Receiver (Any Length)
Coax to Front Antenna
Coax to Back Antenna

Fig 40—Schematic of the antenna switch board. Part numbers in parentheses are RadioShack. All fixed-value resistors are ¼-W, 5%-tolerance units. Equivalent parts can be substituted.

D22-D25—1N914 silicon switching diode (276-1620 or 276-1122)
J1—Six-pin female Molex connector (274-236 or 274-155)
P1—Six-pin male Molex connector (274-226 or 274-152)
R50-R54—2.2 kΩ (can be found in RadioShack resistor assortment packages 271-308 and 271-312); also available in pack of five (271-1325)
S3, S4—DPDT switch (275-626)


U6
LM339
+9 V
R31
100 k
LED
ADJ
1A
W
(to Fig 39)
4
3
2
5
12
U6A
C12
0.1
R32
10 k
R30
10 k
R33
100 k
LED
ADJ
1B
6
U6B
1
7
C11
0.1
X
(to Fig 39)
R34
470 k
+9 V
R61
470 k
10
U6D
11
13
R35
1 k
Front
DS1
Yellow
8
U6C
9
14
R36
1 k
Back
DS2
Orange
+9 V
B
R60
10 kΩ
+9 V
D21
5.1 V
1 W
U7
LM339
+9 V
R44
100 k
LED
ADJ
2A
Y
(to Fig 39)
4
3
2
5
12
U7A
C13
0.1
R41
10 k
R43
10 k
R42
100 k
LED
ADJ
2B
6
U7B
1
7
C14
0.1
Z
(to Fig 39)
R39
470 k
+9 V
R40
470 k
10
U7D
11
13
R37
1 k
Left
DS3
Red
8
U7C
9
14
R38
1 k
Right
DS4
Green

Fig 41—Schematic of the LED driver circuit. Part numbers in parentheses are RadioShack. All fixed-value resistors are ¼-W, 5%-tolerance units. Equivalent parts can be substituted.

C11-C14—0.1-μF, 25-V disc-ceramic capacitor (272-135)
D21—1N4733, 5.1-V, 1-W Zener diode (276-565)
DS1-DS4—LEDs; one each red (276-066); green (276-022); yellow (276-021); orange (276-012)
R30, R32, R41, R43—10 kΩ (271-1335)
R34, R39, R40, R61—470 kΩ (271-1354)
R35-R38—1 kΩ (271-1321)
R31, R33, R42, R44—100-kΩ trimmer potentiometer (271-284)
U6, U7—LM339 quad comparator (276-1712)
Misc: two 14-pin IC sockets (276-1999)

antennas to the receiver coax. This occurs 25 times, thereby switching the receiver between the left and right antennas 25 times. Similar switching then occurs between the front and the back antennas from pulses arriving at points C and D.

Detector Circuit

The detector circuit (back again in Fig 39) starts with U5, a 741 op amp that amplifies the receiver's audio output. The audio is fed into R24 and R27, two 4.7-kΩ pots. The zero-center, 50-μA meters across R24 and R27 are optional. The meters, as well as the LEDs, indicate front/back and left/right. Such meters can be expensive unless you find surplus meters, and they're not really necessary.

When the left/right antennas are active, one end of R24 is grounded by Q7 and Q8 on each alternate pulse.

If Q7 is conducting, Q8 is not conducting. On each pulse, one of the left/right antennas is turned on and one end of R24 is grounded. On the next pulse, the other left/right antenna is turned on and the other end of R24 is grounded. If there is a phase difference between the signal received by the left antenna and the signal received by the right antenna, a dc voltage is built up across R24. That voltage causes the quad comparator, U7 in **Fig 41** to turn on DS3 (red) or DS4 (green) L/R LEDs. If the optional left/right meter is installed, it deflects to indicate the direction as do the LEDs.

After 25 cycles, the left and right antennas are both turned off and the front and back antennas are cycled on and off 25 times with the same detection process, producing a voltage across R27 if there is a phase difference between the RF received by the front and the back antennas. That voltage across R27 causes quad comparator U6 to turn on DS1 or DS2.

C9 and C10, for the F/B detector, and C7 and C8, for the L/R detector, damp the voltage swings caused by multipath reception. To control damping, S2A and S2B switch the 4700-µF capacitors in or out of the circuit. You want the greatest amount of damping when you drive through an area with a lot of multipath propagation (as from buildings); a lot of damping helps under those circumstances.

Construction

The prototype was built using a pad-per-hole RadioShack board. However, a PC board makes construction a lot faster. Far Circuits offers a printed-circuit project on their Web site: **www.cl.ais.net/farcir**). Except for the optional meters and the nonpolarized capacitors, most parts are available from RadioShack.

First build the power supply so you can power the unit from your car or another 12-V source. Apply 12 V to the DFer and adjust R1 until U1's output is +9 V. (You can use a 9-V battery and omit the power-supply section, but you'd better take along a spare battery when you go DFing.)

Install U2 and its associated parts. Power up and turn on S1. A string of pulses should appear at TP1. If you have a frequency counter, set R4 for a pulse frequency of 2200 Hz at TP1. If you don't have a counter, connect a 0.1-µF capacitor from TP1 to headphones or a small speaker and set R4 for a tone of about 2 kHz. Later, you'll adjust the clock so the unit works with the passband of your receiver.

Turn off S1 and remove the power source. Install U3 and its diodes. Pin 12 of U3 need not be connected yet. Apply power and turn on S1. At TP2 and TP3, you should find alternating 1100-Hz pulses. If you have a dual-trace scope, you can see that the pulses alternate. If you have a single-trace scope, connect TP3 to TP2 and to the scope input and the trace will appear as a solid line as there is a pulse at either TP2 or TP3 at all times. If you don't have a scope, the tone in a speaker or earphones from TP2 or TP3 will sound half as high (about 1 kHz) as the tone at TP1.

Turn off S1. Install U4 and its diodes. Note that pin 12 of U3 is connected to pin 14 of U4. At TP4 and TP5, there should be long pulses—five times longer than the pulses at TP1, and the pulses should alternate between TP4 and TP5. The pulse frequency should be about 44 Hz. Power down and turn off S1. Install the remaining circuit components. When you power up, 25 alternating pulses should appear at A and B, then 25 alternating pulses should appear at C and D. Use a scope to verify that.

If you're not using the optional panel meters, connect a voltmeter across R24 (L/R BALANCE), using the lowest dc-voltage range. Note that neither end of R24 is grounded. With no audio input, adjust R24 until there is no voltage across it. Do the same with R27 (F/B BALANCE). If you use the optional meters, adjust R24 and R27 so there's no current shown on either meter.

Power down and assemble the rest of the circuit. With power applied, but with no audio input, adjust R31, 33, 42 and 44 so that the four LEDs (DS1 through DS4) are off. The objective of the following adjustments is to get the red and green LEDs to turn on with the same voltage amplitude, but opposite polarity, across R24. Move R24's wiper so a low positive voltage appears across R24, as indicated by the voltmeter connected across R24 or movement of the panel-meter needle. Adjust R44 (LED ADJ 1A) and R42 (LED ADJ 1B) so that the green LED (DS4) comes on when the voltage goes positive at one end of



Fig 42—An inside view of one DF unit built into a $2 \times 8 \times 5^3/_4$-inch (HWD) box. Because of the height restriction, the two 4700-µF damping capacitors (C8 and C10) are not mounted on the PC board, but near the rear panel behind the smaller of the two PC boards. One of the 4700-µF damping capacitors is a standard electrolytic, the other is a parallel combination of five 1000-µF, 6.3-V bipolar (nonpolarized) capacitors wrapped in electrical tape.



Fig 43—The rear panel of the DF unit supports the two DPDT PHASE toggle switches. Grommets in the panel holes allow abrasion-free passage of the antenna, dc-power and audio cables. The dc power cord is outfitted with an inline fuse holder and a male Jones plug. A six-pin female Molex connector (five pins are used) feeds the four antennas. The audio-input cable is terminated in a $^1/_8$-inch diameter male plug.

R24, but goes off when R24 is adjusted for 0 V across R24.

Next, adjust R24 for a slight negative-voltage indication and adjust R42 and R44 so that the red LED (DS3) comes on, but extinguishes when the voltage across R24 is 0 V. When you're done, adjusting R24's wiper slightly one way should illuminate the red LED. Both LEDs should be off when there's no voltage across R24; rotating R24's wiper slightly in the opposite direction should turn on the green LED.

Connect the voltmeter across R27 or use the panel meter as an indicator. With no audio input, adjust R27 so that there's no voltage across R27. Adjust R31 (F/B LED ADJ 1A) and R33 (F/B LED 1B) so that a F/B LED (DS1) is on when there is a slight positive voltage across R27 and the other F/B LED (DS2) is on when there is a negative voltage across R27.

Switch Board

Assemble the switch board for the four mag-mount antennas (see Fig 40). You can use half of a RadioShack dual pad-per-hole PC board (RS 276-148) as a platform. Lead length is critical only on this board and in the length of the coax from the switching board to the antennas, so avoid wire-wrap construction here.

Feed Lines

The coax lines from the switch board to each of the four antennas must be of equal length. The coax lengths should be long enough to permit each antenna to be placed slightly less than $^1/_4$ λ from its counterpart, at the lowest frequency of operation. (There's a local belief that $27^1/_2$ inches is the best length. The author used that length and it works, but other lengths might work as well.) An attempt to locate the switch board inside the vehicle and run equal-length 12-foot-long cables to the antennas failed. Keep the switch board on the vehicle's roof.

Use the same type of coax for all lines—that is, don't mix foam and polyethylene dielectric coax on the antenna lines. If the velocity factor of the lines is not equal, a phase shift in the signals will exist even when the transmitter is dead ahead and it will lead you astray.

Solder the coax from the antennas directly to the board—don't use connectors. From the switch board to the receiver, use 50-Ω coax of any type and length. Equip the receiver end of the line with a connector that mates with your receiver's antenna-input jack. Make the four-conductor shielded cable from the main DFer box to the switch board long enough to reach from the LRFB box's operating position to the roof of the car. Construct the antennas so that the whips can be changed easily for use on any frequency in which you're interested.

Mechanical Assembly

Mount the finished PC boards in a metal box of your choice. You can follow the construction method used in the prototype (see **Fig 42** and **Fig 43**), but do ensure that R4 can be adjusted easily with a tuning tool from outside the box. A hole drilled in the box at the right point will suffice. Arrange the LEDs in a diamond pattern on the front panel, with the left LED (red) to the left, the right LED (green) on the right, and the front and back LEDs at the top and the bottom.

Wrap the switch board with tape to waterproof it, or place it in a watertight box. Arrange the mag-mount antennas on top of the vehicle in a diamond shape. The distance between each antenna pair should be less than $^1/_4$ λ at the operating frequency. (In limiting the distance between antennas in a pair—F/B or L/R—to less than $^1/_4$ λ, the author followed W9DUU's example.)

Final Adjustments

It's best to start on 2 meters. Install the 2-meter whips in the antenna bases. Mount the antennas on the top of your vehicle. Identify the left and right antenna bases with L and R, and mark the front and back antenna bases, too.

A good way to find out if the antennas are properly installed is to short either the left or right antenna with a clip lead from the whip to the metal base; the L/R meter will deflect one way and the left or right LED will light. If you short one of the front and back antennas with a clip lead, the front or back LED will come on. If you short one of the L/R antennas and it makes the meter go to the right, it does not necessarily mean you have the PHASE switch in the proper position. That depends on the relative phase determined by the number of audio stages in your receiver, each of which may contribute a shift of 180°.

Connect the coax from the switch board to your FM receiver. It must be an FM receiver; an AM VHF or AM aircraft receiver won't suffice. Connect the audio output of your 2-meter receiver to the LRFB box audio input. If you're using a transceiver, disable its transmit function by removing the mike. You don't want to transmit into the switch board!

Turn on the receiver and place the LRFB box in receive by setting S1 to the RCV position. Center R10. Only one of the antennas will be turned on and the DF operation will be disabled. Back off the squelch and notice that you hear the audio from the speaker of the LRFB box. Switch to an unused simplex channel. Have a friend with an HT stand 20 feet or so in front of the vehicle. With the receiver in the car turned off, turn S1 to DF. The four LEDs should be off. If an LED lights, adjust R24 and R27 for zero voltage. If the LED is still on, readjust R31 and R33, or R42 and R44 as explained earlier. When all four LEDs are off with the antennas connected, no audio from the receiver and no RF input signal, you're ready. Turn on your receiver and have your friend transmit on the 2-meter frequency (simplex) that your receiver is set to. When he transmits, one or more of the LEDs should illuminate. Ignore the front/back LEDs, but check to see if the right or left LED is on. If the right LED is on and your friend is standing to the right of the center of the vehicle front, all is well. Have him walk back and forth in front of the vehicle and notice that when he is to the right, the green LED turns on, and when he's to the left, the red LED glows. If the indications are reversed, that is, if the LRFB box indicates left when your friend is to your right, reverse the position of PHASE switch S3.

When the L/R indicators are working properly, have your friend walk back and forth between a position 20 feet to the front and right of the car and a position 20 feet away to the rear and right of the car. The right LED should stay on, but the front LED should be on when the HT is in front of the antennas, and the back LED should be on when the HT is behind the antennas. If the front/back indications are reversed, reverse the position of PHASE switch S4.

While receiving a signal from your friend's HT, adjust R4 for maximum deflection on any one of the two optional meters, or on a voltmeter (set on the lowest dc voltage range) connected across R24 or R27. Look for the maximum deflection of the meter needle as the meter swings both ways while the signal source moves from back to front or left to right (depending, of course, on which panel meter you're looking at or which resistor—R24 or R27—your voltmeter is across). The audio passband of FM receivers varies, and if you switch from an ICOM IC-27 to an ICOM IC-W2A, for example, you'll have to change U2's master clock frequency. You may encounter receivers that don't require readjusting R4, but such readjustment should be expected. When changing receivers, you may also need to change the position of PHASE switches S3 and S4. This may also be necessary when changing from UHF to VHF, or VHF to UHF on the same receiver, as the number of receiver stages (and, hence, the audio phase) may change from band to band.

Audio Level Adjustments

With meter damping (S2) off, adjust R10 so that you have full deflection of one of the two meters (or your multimeter) with the signal source at a 45° angle from the vehicle (halfway between ahead and right), and a reasonable audio level from the speaker. Turn the rig's volume control all the way up to ensure that the audio circuit doesn't overload. If it overloads, the meters won't deflect. From zero to full blast, the meter should deflect more and more (unless the signal is straight ahead or exactly left or right). If you're using an H-T, maximum deflection of the meter should occur before the volume control is $^3/_4$ of maximum, or before the volume control is at $^1/_2$ of maximum if you're using a mobile rig. If R10 is properly adjusted, turning the volume control to maximum won't cause the meter to fall back toward zero. If increasing the volume causes the meter to deflect less, then R10's setting is too high.

Now have your friend walk around the vehicle with the HT transmitting and notice that the LEDs indicate the signal direction. On 2 meters in a clear field, the indications should be correct 80 or 90% of the time. The erroneous readings that occasionally occur are due to multipath propagation caused by the irregular shape of the vehicle. Slight adjustments in the positions of the L/R and F/B antennas may be necessary to make the zero points fall directly in front of the vehicle (neither left nor right LED on) and at the center of the antennas (neither front nor back LED on).

Try the same procedure on 440 MHz. You may have to flip the PHASE switches when you move to another band, even when using the same receiver. Remember that the total length of the 440-MHz antennas must be $^1/_4$ λ or less, and the antennas must be placed less than $^1/_4$ λ apart. The results on 440 MHz probably won't be as consistent as the results on 2 meters, as there is likely to be a lot more multipath propagation caused by the irregular shape of the vehicle.

Fox Hunting

Before heading out to find the fox, check to be certain the LRFB box is working properly. Tune to the fox's frequency and drive off. Turning on the DAMPING switch stabilizes the indication as you drive along. Follow indications generated as you travel over the road or street. If an indication is constant for 15 or 20 seconds while you're moving down the road, it's probably the true direction to the fox. It's possible to have a reflection from a mountain over a long distance down the road, however. When you can hear the fox with no antenna, it's time to get out of the car, switch to the hand-held system and hunt for the fox on foot.

If you switch to a new receiver, you may have to readjust R4, CLOCK FREQ. That's because both receivers may not have the same audio bandwidth. Author WA9BVS forgot this while chasing a balloon once and the results were comical. When chasing balloons with ham radio transmitters, the readings you get are likely to be confusing when the balloon is at a high angle with respect to the plane of the car top. Use a hand-held Yagi to verify the balloon location. Even with a simple buzzbox, you should be able to find a keyed transmitter.

A TAPE-MEASURE BEAM FOR RDFING

Joe Leggio, WB2HOL, designed this antenna while searching for a beam with a really great front-to-back ratio to use in hidden transmitter hunts. It exhibits a very clean pattern and is perfect for RDF use. You can construct this beam using only simple hand tools, and it has been duplicated many times.

WB2HOL's first design requirement was to be able to get in and out of his car easily when hunting for a hidden transmitter. He accomplished this by using steel "tape-measure" elements, which fold easily when putting the antenna into a car and yet are self supporting. They also hold up well while crashing through the underbrush on a fox hunt.

WB2HOL decided to use three elements to keep the boom from getting too long. He used inexpensive


41-3/8 in.
35-1/2
35-1/8 in.
1/2-inch Schedule 40 PVC Crosses
1-1/2 inch Stainless Steel Hose Clamps
RG-58 Coax
1/2-inch Schedule 40 PVC Pipe
1/2-inch Schedule 40 PVC Tee
Antenna elements are made of 1 inch wide steel tape-measure
Use tape on cut edges for safety
ANT0567
8 in.
12-1/2 in.

Fig 44—Tape-measure beam dimensions.



Fig 45—Photo of driven-element mounted to PVC tee using hose clamps. The hairpin match wires is shown here soldered to the tape-measure elements, along with the RG-58 feed line.



Fig 46—Photo of complete tape-measure beam, ready to hunt foxes!

Schedule-40 PVC pipe, crosses and tees that can be found at any hardware store for the boom and element supports.

He used a simple hairpin match, consisting of a 5-inch length of #14 solid wire bent into the shape of a U, with the two legs about $^{3}/_{4}$ inch apart. This gave in a very good match across the 2-meter band after he tweaked the distance (1-inch on his prototype) between the halves of the driven element for minimum SWR.

You can cut the 1-inch wide tape-measure elements with a pair of shears, chamfering the ends of the elements. Be very careful—the edges are very sharp and will inflict a nasty cut if you are careless. Use some sandpaper to remove the sharp edges and burrs and put some vinyl electrical tape on the ends of the elements to protect yourself from getting cut. Wear safety glasses while cutting the elements. See **Fig 44** for dimensions.

The RG-58 coax feed line is wound into a 8-turn coil along the boom to form a choke balun. The coil is covered with vinyl black tape to secure it to the boom. Make sure you scrape or sand the paint off the tape-measure elements where the feed line is attached. Most tape measures have a very durable paint finish designed to stand up to heavy use. You do not want the paint to insulate your feed-line connection!

If you are careful, you can solder the feed line to the element halves, but take care since the steel tape measure does not solder easily and the PVC supports can be easily melted. Tin the tape-measure elements before mounting them to the PVC cross if you decide to connect the feed line in this fashion.

If you decide not to solder to the tape-measure elements, you can use two other methods to attach the feed line. One method employs ring terminals on the end of the coax. The ring terminals are then secured under self-tapping screws or with 6-32 bolts and nuts into holes drilled in the driven-element halves. However, with this method you cannot fine-tune the antenna by moving the halves of the driven element in and out.

The simplest method is simply to slide the ends of the feed line under the driven element hose clamps and tighten the clamps to hold the ends of the coax. This is low-tech but it works just fine.

WB2HOL used $1^{1}/_{2}$-inch stainless-steel hose clamps to attach each driven-element half to the PVC cross that acts as its support. This allowed him to fine-tune his antenna for lowest SWR simply by loosening the hose clamps and sliding the halves of the driven element in or out to lengthen or shorten the element. He achieved a 1:1 SWR at 146.565 MHz (the local fox-hunt frequency) when the two elements were spaced about 1 inch apart. **Fig 45** shows the hose-clamp method for attaching the driven element to the PVC cross, along with the hairpin wire and feed-line coax.

Some builders have used rubber faucet washers between the tape-measure elements and the PVC-cross fittings on the director and reflector. These allow for the tape to fit the contour of the PVC fitting better and will make the antenna look nicer. It is normal for the reflector and director elements to buckle a bit as they are tightened to the PVC tee and cross if you don't use faucet washers. You can also eliminate the buckling if you use self-tapping screws to attach these elements instead of hose clamps. The beam will not be as rugged, however, as when you use hose clamps.

This beam has been used on fox hunts, on mountain tops, at local public-service events, outdoors, indoors in attics—just about everywhere. The SWR is typically very close to 1:1 once adjusted. Front-to-back performance is exactly as predicted. The null in the rear of the pattern is perfect for transmitter hunts.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2.

W. U. Amphar, “Unidirectional Loops for Transmitter Hunting,” *QST*, Mar 1955.

G. Bonaguide, “HF DF—A Technique for Volunteer Monitoring,” *QST*, Mar 1984.

D. S. Bond, *Radio Direction Finders*, 1st edition (New York: McGraw-Hill Book Co).

R. E. Cowan and T. A. Beery, “Direction Finding with the Interferometer,” *QST*, Nov 1985.

D. DeMaw, “Beat the Noise with a Scoop Loop,” *QST*, Jul 1977.

D. DeMaw, “Maverick Trackdown,” *QST*, Jul 1980.

T. Dorbuck, “Radio Direction-Finding Techniques,” *QST*, Aug 1975.

D. T. Geiser, “Double-Ducky Direction Finder,” *QST*, Jul 1981.

D. T. Geiser, “The Simple Seeker,” *The ARRL Antenna Compendium*, *Vol 3*, p 126.

N. K. Holter, “Radio Foxhunting in Europe,” Parts 1 and 2, *QST*, Aug and Nov 1976.

J. Isaacs, “Transmitter Hunting on 75 Meters,” *QST*, Jun 1958.

H. Jasik, *Antenna Engineering Handbook*, 1st edition (New York: McGraw-Hill, 1961).

R. Keen, *Wireless Direction Finding*, 3rd edition (London: Wireless World).

J. Kraus, *Antennas*, 2nd edition (New York: McGraw-Hill Book Co, 1988).

J. Kraus, *Electromagnetics*, 4th edition (New York: McGraw-Hill Book Co, 1992).

C. M. Maer, Jr., “The Snoop-Loop,” *QST*, Feb 1957.

M. C. Mallette, “The Four-Way DFer,” *QST*, Nov 1995. A set of two PC boards is available from FAR Circuits for the “Four-Way DFer” project. 18N640 Field Ct, Dundee, IL 60118-9269, tel 708-576-3540 (voice and fax). Note: No component pads for C15 exist. Mount C15 between U2 pin 5 and ground on the bottom (foil) side of the board. A PC-board template package is available from the ARRL free of charge. Send your request for the MALLETTE 4-WAY DFER, along with a business size SASE, to the Technical Department Secretary, 225 Main St, Newington, CT 06111-1494.

L. R. Norberg, “Transmitter Hunting with the DF Loop,” *QST*, Apr 1954.

P. O’Dell, “Simple Antenna and S-Meter Modification for 2-Meter FM Direction Finding,” Basic Amateur Radio, *QST*, Mar 1981.

Ramo and Whinnery, *Fields and Waves in Modern Radio* (New York: John Wiley & Sons, 1944).

F. Terman, *Electronic and Radio Engineering* (New York: McGraw-Hill Book Co, 1955).

Radio Direction Finding , published by the Happy Flyer, 1811 Hillman Ave, Belmont, CA 94002.

For more information on direction finding, see *The ARRL Handbook* and *Transmitter Hunting: Radio Direction Finding Simplified*, by Joe Moell, KØOV, and Thomas Curlee, WB6UZZ. These books are available from your local dealer or can be ordered directly from ARRL.

Chapter 15

Portable Antennas

For many amateurs, the words *portable antennas* may conjure visions of antenna assemblies that can be broken down and carried in a backpack, suitcase, golf bag, or what-have-you, for transportation to some out-of-the way place where they will be used. Or the vision could be of larger arrays that can be disassembled and moved by pickup truck to a Field Day site, and then erected quickly on temporary supports. Portable antennas come in a wide variety of sizes and shapes, and can be used on any amateur frequency.

Strictly speaking, the words "portable antenna" really means *transportable antenna*—one that is moved to some (usually temporary) operating position for use. As such, portable antennas are not placed into service when they are being transported. This puts them in a different class from mobile antennas, which are intended to be used while in motion. Of course this does not mean that mobile antennas cannot be used during portable operation. Rather, true portable antennas are designed to be packed up and moved, usually with quick reassembly being one of the design requisites. This chapter describes antennas that are designed for portability. However, many of these antennas can also be used in more permanent installations.

Any of several schemes can be employed to support an antenna during portable operation. For HF antennas made of wire, probably the most common support is a conveniently located tree at the operating site. Temporary, lightweight masts are also used. An aluminum extension ladder, properly guyed, can serve as a mast for Field Day operation. Such supports are discussed in Chapter 22, Antenna Supports.

A SIMPLE TWIN-LEAD ANTENNA FOR HF PORTABLE OPERATION

The typical portable HF antenna is a random-length wire flung over a tree and end-fed through an antenna tuner. Low-power antenna tuners can be made quite compact, but each additional piece of necessary equipment makes portable operation less attractive. The station can be simplified by using resonant impedance-matched antennas for the bands of interest. Perhaps the simplest antenna of this type is the half-wave dipole, center-fed with 50- or 75-Ω coax. Unfortunately, RG-58, RG-59 or RG-8 cable is quite heavy and bulky for backpacking, and the miniature cables such as RG-174 are too lossy.

A practical solution to the coax problem, developed by Jay Rusgrove, W1VD, and Jerry Hall, K1TD, is to use folded dipoles made from lightweight TV twin-lead. The characteristic impedance of this type of dipole is near 300 Ω, but this can easily be transformed to a 50-Ω impedance. The transformation is obtained by placing a lumped capacitive reactance at a strategic distance from the input end of the line. **Fig 1** illustrates the construction method and gives important dimensions for the twin-lead dipole.

A silver-mica capacitor is shown for the reactive element, but an open-end stub of twin-lead can serve as well, provided it is dressed at right angles to the transmission line for some distance. The stub method has the advantage of easy adjustment of the system resonant frequency.

The dimensions and capacitor values for twin-lead dipoles for the HF bands are given in **Table 1**. To pre-



Fig 1—A twin-lead folded dipole makes an excellent portable antenna that is easily matched to 50-Ω equipment. See text and Table 1 for details.

Table 1

Twin-Lead Dipole Dimensions and Capacitor Values

Frequency	*Length A*	*Length C*	C_s	*Stub Length*
3.75 MHz	124' 9½"	13' 0"	289 pF	37' 4"
7.15	65' 5½"	6' 10"	151 pF	19' 7"
10.125	46' 2½"	4' 10"	107 pF	13' 10"
14.175	33' 0"	3' 5½"	76 pF	9' 10½"
18.118	25' 10"	2' 8½"	60 pF	7' 9"
21.225	22' ½"	2' 3½"	51 pF	6' 7"
24.94	18' 9"	1' 11½"	43 pF	5' 7½"
28.5	16' 5"	1' 8½"	38 pF	4' 11"

serve the balance of the feeder, a 1:1 balun must be used at the end of the feed line. In most backpack QRP applications the balance is not critical, and the twin-lead can be connected directly to a coaxial output jack—one lead to the center contact, and one lead to the shell.

Because of the transmission-line effect of the shorted-radiator sections, a folded dipole exhibits a wider bandwidth than a single-conductor type. The antennas described here are not as broad as a standard folded dipole because the impedance-transformation mechanism is frequency selective. However, the bandwidth should be adequate. An antenna cut for 14.175 MHz, for example, will present an SWR of less than 2:1 over the entire 14-MHz band.

ZIP-CORD ANTENNAS

Zip cord is readily available at hardware and department stores, and it's not expensive. The nickname, *zip cord*, refers to that parallel-wire electrical cord with brown or white insulation used for lamps and many small appliances. The conductors are usually #18 stranded copper wire, although larger sizes may also be found. Zip cord is light in weight and easy to work with.

For these reasons, zip cord can be pressed into service as both the transmission line and the radiator section for an emergency dipole antenna system. This information by Jerry Hall, K1TD, appeared in *QST* for March 1979. The radiator section of a zip-cord antenna is obtained simply by "unzipping" or pulling the two conductors apart for the length needed to establish resonance for the operating frequency band. The initial dipole length can be determined from the equation $\ell = 468/f$, where ℓ is the length in feet and f is the frequency in MHz. (It would be necessary to unzip only half the length found from the formula, since each of the two wires becomes half of the dipole.) The insulation left on the wire will have some loading effect, so a bit of length trimming may be needed for exact resonance at the desired frequency.

For installation, you may want to use the electrician's knot shown in **Fig 2** at the dipole feed point. This is a balanced knot that will keep the transmission-line part of the system from unzipping itself under the tension of dipole suspension. This way, if zip cord of sufficient length for both the radiator and the feed line is obtained, a solder-free installation can be made right down to the input end of the line.

(Purists may argue that knots at the feed point will create an impedance mismatch or other complications, but as will become evident in the next section, this is not a major consideration.) Granny knots (or any other variety) can be used at the dipole ends with cotton cord to suspend the system. You end up with a lightweight, low-cost antenna system that can serve for portable or emergency use.

But just how efficient is a zip-cord antenna system? Since it is easy to locate the materials and simple to install, how about using such for a more permanent installation? Upon casual examination, zip cord looks about like 72-Ω balanced feed line. Does it work as well?

Zip Cord as a Transmission Line

To determine the electrical characteristics of zip cord as a radio-frequency transmission line, a 100-foot roll was subjected to tests in the ARRL laboratory with an RF impedance bridge. Zip cord is properly called *parallel power cord*. The variety tested was manufactured for GC Electronics, Rockford, IL, being 18-gauge, brown, plastic-insulated type SPT-1, GC cat. no. 14-118-2G42. Undoubtedly, minor variations in the electrical-characteristics will occur among similar cords from different manufacturers, but the results presented here are probably typical.

The characteristic impedance was determined to be 107 Ω at 10 MHz, dropping in value to 105 Ω at 15 MHz and to a slightly lower value at 29 MHz. The nominal



Fig 2—This electrician's knot, often used inside lamp bases and appliances in lieu of a plastic grip, can also serve to prevent the transmission-line section of a zip-cord antenna from unzipping itself under the tension of dipole suspension. To tie the knot, first use the right-hand conductor to form a loop, passing the wire behind the unseparated zip cord and off to the left. Then pass the left-hand wire of the pair behind the wire extending off to the left, in front of the unseparated pair, and thread it through the loop already formed. Adjust the knot for symmetry while pulling on the two dipole wires.



Fig 3—Attenuation of zip cord in decibels per hundred feet when used as a transmission line at radio frequencies. Measurements were made only at the three frequencies where plot points are shown, but the curve has been extrapolated to cover all high-frequency amateur bands.

value is 105 Ω at HF. The velocity factor of the line was determined to be 69.5%.

Who needs a 105-Ω line, especially to feed a dipole? A dipole in free space exhibits a feed-point resistance of 73 Ω, and at heights above ground of less than $^1/_4$ wavelength the resistance can be even lower. An 80-meter dipole at 35 feet over average soil, for example, will exhibit a feed-point resistance of about 35 Ω. Thus, for a resonant antenna, the SWR in the zip-cord transmission line can be 105/35 or 3:1, and maybe even higher in some installations. Depending on the type of transmitter in use, the rig may not like working into the load presented by the zip-cord antenna system.

But the really bad news is still to come—line loss! **Fig 3** is a plot of line attenuation in decibels per hundred feet of line versus frequency. Chart values are based on the assumption that the line is perfectly matched (sees a 105-Ω load as its terminating impedance).

In a feed line, losses up to about 1 decibel or so can be tolerated, because at the receiver a 1-dB difference in signal strength is just barely detectable. But for losses above about 1 dB, beware. Remember that if the total losses are 3 dB, half of your power will be used just to heat the transmission line. Additional losses over those charted in Fig 3 will occur when standing waves are present. (See Chapter 24, Transmission Lines.) The trouble is, you can't use a 50- or 75-Ω SWR instrument to measure the SWR in zip-cord line accurately.

Based on this information, we can see that a hundred feet or so of zip-cord transmission line on 80 meters might be acceptable, as might 50 feet on 40 meters. But for longer lengths and higher frequencies, the losses become appreciable.

Zip Cord Wire as the Radiator

For years, amateurs have been using ordinary copper house wire as the radiator section of an antenna, erecting it without bothering to strip the plastic insulation. Other than the loading effects of the insulation mentioned earlier, no noticeable change in performance has been noted with the insulation present. And the insulation does offer a measure of protection against the weather. These same statements can be applied to single conductors of zip cord.

The situation in a radiating wire covered with insulation is not quite the same as in two parallel conductors, where there may be a leaky dielectric path between the two conductors. In the parallel line, it is the current leakage that contributes to line losses. This leakage current is set up by the voltage potential that exists on the two adjacent wires. The current flowing through the insulation on a single radiating wire is quite small by comparison, and so as a radiator the efficiency is high.

In short, communications can certainly be established with a zip-cord antenna in a pinch on 160, 80, 40, 30 and perhaps 20 meters. For higher frequencies, especially with long line lengths for the feeder, the efficiency of the system is so low that its value becomes questionable.

A TREE-MOUNTED HF GROUND-PLANE ANTENNA

A tree-mounted, vertically polarized antenna may sound silly. But is it really? Perhaps engineering references do not recommend it, but such an antenna does not cost much, is inconspicuous, and it works. This idea was described by Chuck Hutchinson, K8CH, in *QST* for September 1984.

The antenna itself is simple, as shown in **Fig 4**. A piece of RG-58 cable runs to the feed point of the antenna, and is attached to a porcelain insulator. Two radial wires are soldered to the coax-line braid at this point. Another piece of wire forms the radiator. The top of the radiator section is suspended from a tree limb or other convenient support, and in turn supports the rest of the antenna.

The dimensions for the antenna are given in **Fig 5**. All three wires of the antenna are ¼ wavelength long. This generally limits the usefulness of the antenna for portable operation to 7 MHz and higher bands, as temporary supports higher than 35 or 40 feet are difficult to come by. Satisfactory operation might be had on 3.5 MHz with an inverted-L configuration of the radiator, if you can overcome the accompanying difficulty of erecting the antenna at the operating site.

The tree-mounted vertical idea can also be used for fixed station installations to make an invisible antenna. Shallow trenches can be slit for burying the coax feeder and the radial wires. The radiator itself is difficult to see unless you are standing right next to the tree.



Fig 4—The feed point of the tree-mounted ground-plane antenna. The opposite ends of the two radial wires may be connected to stakes or other convenient points.

A PORTABLE DIPOLE FOR 80 TO 2 METERS

This dipole antenna, described by Robert Johns, W3JIP, in August 1998 *QST*, can be used for any band from 80 through 2 meters. One half of the dipole is an inductively loaded aluminum tube. Its length is adjustable from 4 to 11 feet, depending on how much room is available. The other half is flexible insulated wire that can be spooled out as necessary. The tube is supported by a flagpole bracket attached to a long carpenter's clamp. The clamp mounts the antenna to practically anything: a windowsill, railing, a chair or post. If there is no structure to mount the antenna (a parking lot or the beach), the clamp attaches to two light wooden legs to form a tripod, as shown in **Fig 6**.

The key to mounting flexibility is the large clamp. The key to electrical flexibility is a large adjustable coil that lets you resonate the tube on many bands. The coil is wound with #8 aluminum ground wire from RadioShack. The form is a four-inch ($4^1/_2$-inch OD) styrene drain coupling from the Home Depot or a large plumbing supply store. A movable tap adjusts the inductance to tune the upright tube to the desired band. The wire half of the antenna is always a bit less than λ/4 on each band. Hang it from any convenient support or drape it over bushes to keep it off the ground.



Fig 5—Dimensions and construction of the tree-mounted ground-plane antenna.





Fig 6—At top, the portable antenna in some of the many places it may be mounted around the house, porch and yard. At bottom, the simple ground-mounted legs that make a tripod.

Construction

The 18-inch carpenter's clamp (sometimes called a *bar clamp*, such as Jorgensen's No. 3718) and flagpole bracket that takes a 3/4-inch pole are common hardware items. Insulate the bracket from the clamp jaw with a 1 1/2-inch length of 1-inch PVC pipe (see **Fig 7**). Hammer the PVC over the end clamp jaw to make it take the shape of the jaw. Secure the flagpole bracket to PVC with a large ground clamp (for 1/2 or 1-inch conduit). The ground clamp includes 1/4-inch bolts; enlarge the flagpole bracket holes to accept them. Some flagpole brackets have an integral cleat; the author hammered the cleat ears flat on his.

Mount an SO-239 chassis connector on the flagpole bracket using RadioShack insulated standoffs (276-1381). The standoffs tightly press the center pin of the SO-239 against the bracket surface; no other connection is needed. Other mounting hardware may require a connection from the coax center conductor to the bracket. The spooled wire's inner end wraps around a standoff and connects to a ring terminal under a screw holding the SO-239 flange to the standoff.

The 1 × 2-inch wooden legs for the tripod are each 30 inches long. Bolt them together at one end with a 1 or 1 1/4-inch-long bolt. Countersink the bolt head and nut below the surface of the wood so they don't interfere with the clamp jaws.

Aluminum Element

You can make this element from three lengths of telescoping aluminum tubing (3/4, 5/8 and 1/2 inch, 0.058-inch walls). The author used tubing with thinner walls for less weight and easier handling. A 45-inch-long, 3/4-inch tube fits the flagpole bracket. He chose this length because it and the flagpole bracket make $\lambda/4$ on 6 meters. The two outer tubes are both 5/8 inch, made by cutting a seven-foot aluminum clothesline pole in halves. They are



Fig 7—The flagpole bracket that supports the tubing elements is clamped to the long carpenter's clamp, but insulated from it by a small section of 1-inch PVC pipe. A coax connector is mounted to the bracket and the spool of wire is attached to the coax connector.

joined together with a copper coupling (5/8 inch ID) for 1/2-inch copper pipe. The coupling is bolted to one of the 5/8-inch sections, and a slot is cut in the free half of the coupling. The remaining 5/8-inch tube is inserted there and secured with a hose clamp. See **Fig 8**.

One 5/8-inch tube slides into the 3/4-inch tube to provide a continuously variable element length from about 4 to 7 1/2 feet. This extends from 7 1/2 to 11 feet when the two 5/8-inch sections are joined together.

Loading Coil

The loading coil has 12 turns of bare aluminum wire spaced to fill the 3 1/2-inch length of the drain coupling. Drill 9/64-inch holes at the ends of the coil form to accept the ends of the coil wire. (See **Fig 9**.) To wind the coil, feed four inches of wire through the form, make a sharp bend in the wire and start winding away from the nearby mounting hole. Wind 12 turns on the form, spacing them only approximately. Cut the wire for a 4-inch lead and feed it through the other hole in the form. Tighten the wire as best you can and bend it into another acute angle where it passes into the form. Space the turns about equally, but don't fuss with them. Final spacing will be set after the wire is tightened.

Tighten the coil wire by putting a screwdriver or a needle-nose pliers jaw under one turn, and pry the wire up and away from the surface of the coil form. While this can be done anywhere, it's best to put these kinks on the backside, away from the mounting shaft. Put kinks in every other turn, removing any slack from the coil and holding the turns in place. Should the coil ever loosen, simply retighten it with a screwdriver. If you prefer, glue the coil turns in place with epoxy or coil dope. Use a thin bead of glue that won't interfere with the clip that connects to the coil.

The coil form mounts on a nine-inch-long 3/4-inch PVC pipe. (See Fig 9 and **Fig 10**.) The inside diameter is slightly larger than the 3/4-inch aluminum, but slotting the PVC and tightening it with a hose clamp secures the tube. (Use a wide saw to cut these slots, not a hacksaw.) The coil form mounts to the PVC pipe with #6-32 × 1 1/2-inch bolts. A five-inch long, 3/4-inch aluminum tube permanently attaches to one end of the coil assembly and slides into the flagpole bracket. One end of the coil wire connects to this short tube. Flatten the wire end by hammering it on something hard, then drill a 9/64-inch hole in the flattened end and attach it to the short tube with a #6-32 × 1-inch bolt. Tighten the bolt until the 1/2-inch tube starts to flatten. This will keep pressure on the aluminum-to-aluminum joint.

The aluminum element slides into the opposite end of the coil assembly. The hose clamp there can be tightened until the element just slides in snugly.

A 12-inch clip lead connects the aluminum element to the coil. Bolt the plain wire end to the 3/4-inch tube three inches from its end. Many alligator clips will fit in the space between the turns of the coil (about 3/16 inch), but W3JIP preferred using a solid-copper clip (Mueller TC-1). Cut off most of the jaws, so that only the part close to the hinge grabs the coil. This shorter lever grips very tightly.

Wire and Spool

The lower half of the antenna is insulated wire that is about λ/4 on the band of operation. The wire is pulled from the spool, and the remaining wire forms an inductance that doesn't add much to the antenna length. The Home Depot sells #12 and #14 insulated stranded copper wire in 50 and 100-foot lengths, on plastic spools. (See **Fig 11**.) A 1/2-inch dowel fits into the spool to make a



Fig 8—The joint between two sections of 5/8-inch tubing is made from a 1/2-inch copper pipe coupling, bolted to one section and hose clamped to the other.



Fig 9—Holes to be drilled in the styrene coupling and the 3/4-inch PVC pipe. All holes are 9/64-inch diameter, to provide clearance for #6-32 bolts. The hole 1 1/2 inches from one end holds a bolt that serves as a stop, so that the antenna tube does not slide in too far. Space the holes for coil leads far enough from the mounting holes to clear the 3/4-inch pipe.



Fig 10—Top photo shows the loading coil for the 20, 30, and 40-meter band coverage. The short aluminum tube on the coil slides into the flagpole bracket, and the tubing element slides into the other end of the PVC pipe. The wire and clip connect the element to the coil. Bottom photo shows the coil for operating the antenna on 80 meters. This is placed in the flagpole bracket and the 40-meter aluminum coil plus the tubing element is inserted into it.



Fig 11—The wire spool has a wooden axle/handle and small handle for winding the wire. A bungee cord stretched over the spool and around the axle prevents the wire from unwinding.

Table 2

	Tubing Length (feet)	*Coil Turns*	*Wire Length (feet)*
6 meters	4	0	4
10 meters	7	0	8
	4	1.7	7
12 meters	8	0	8.3
	4	1.8	9
15 meters	10	0	10.3
	8	1.8	10
	4	3.5	10
17 meters	11	0	13
	8	2.2	13
	4	4.2	13
20 meters	11	1	16
	8	4	16
	4	6.2	16
30 meters	11	4	24
	8	7	24
	4	10.5	24
40 meters	11	9	32
	8	12	32

handle and spool axle. Bolts through the dowel on either side of the spool hold it in place. A crank handle is made by putting a one-inch-long bolt through the spool flange.

The author calibrates the wire on the spool with markers and electrical-tape flags. There's a mark (from a permanent marking pen) at each foot, a black flag every five feet and a length-marked colored flag every 10 feet. Simply mark the length for each band, if you like.

Make sure you prevent the wire from unspooling, especially when it's hanging from a window mounting. A heavy rubber band works, but it doesn't last long. A better solution is a loop of light bungee cord, preferably with a knot for grip. The bungee loop runs from the axle/handle around the spool making a half twist on the way, and then passes over the axle end on the other side of the spool. (See Fig 11.)

Operation

Table 2 lists element length, wire length and coil tap point for various bands. When the number of turns shown is zero, the coil is not needed. On all bands except 6 meters, you can simply bypass the coil with the clip lead—the extra length just lowers the frequency a bit. For 6 meters, the coil *must* be removed. The location of the unspooled wire greatly affects the settings, so these numbers are only starting points. The lengths in the table were taken with the wire one to three feet above ground, draped over and through bushes and flowerbeds. The antenna will still work if the wire is lying on the ground, but it will require less unspooled wire to resonate. A balun is not needed, and an SWR analyzer is very helpful while adjusting this antenna.

The SWR is less than 1.5:1 on all bands, and it's usually below 1.2:1. Occasionally, a band shows a higher SWR (still less than 2:1), but that can always be lowered by adjusting the length or location of the lower wire. Never set up the antenna where it could fall and injure someone, or where the unwary could get an RF burn by touching it.

The author's results with this antenna have been excellent, both from home and on vacation. If you haven't yet operated from a seashore location, be prepared for a pleasant surprise! The good ground afforded by the salt water really makes a difference.

80 Meters

It's easy to add this lower frequency band. Fig 10 shows a 35 μH coil for 80 meters. It's constructed and tightened just like the 40-meter coil, but has 20 turns of #12 magnet wire.

To operate on 75/80 meters, insert the new coil into the flagpole bracket and plug the 40-meter coil into it. Tune across the band with the movable tap on the 40-meter coil. This varies antenna resonance from below 3.5 to above 4.0 MHz, with the full 11 feet of tubing extended. If your version doesn't achieve this tuning range, adjust the spacing of the turns on the 80-meter coil.

The 80-meter coil has a five-inch length of $^3/_4$-inch aluminum tube inserted into one end of the $^1/_2$-inch PVC pipe that supports the coil form. One end of the coil is connected to this aluminum tube. The other end is secured under the bolt that holds the coil form to the PVC pipe. A second clip lead connects the base of the 40-meter coil to the outer end of the larger coil. The length of wire on the spool must also be increased to about 64 feet.

2 Meters

A λ/2 dipole for 2 meters can be made with about 15 inches of $^1/_2$-inch aluminum tubing in the flagpole bracket, and 18 inches of wire. The tubing element is shorter than normal for 2 meters because the bracket is also part of the antenna. You can also shorten the 6-meter wire a bit and operate the 6-meter antenna as a 3λ/2 on 2 meters, with a somewhat higher SWR.

Continuous Coverage

With easily changed element lengths and a continuously variable loading coil, you may operate the antenna on any frequency from 6.5 to 60 MHz, if coverage for other services is needed. With taps in the 80-meter coil at 8, 11 and 14 turns, the antenna will also tune from 4 to 7 MHz.

THE HF CABOVER ANTENNA

If you have ever had the pleasure of traveling across the country with an HF mobile in a camper, trailer or motor home you may want to duplicate this antenna for use when you park. This antenna was described in *The ARRL Antenna Compendium, Vol* 5, by Jim Ford, N6JF.

The author's camper has limited spots on which to mount an HF mobile antenna. The back ladder is a convenient place to mount a small mobile whip. However, the efficiency of typical mobile center-loaded antennas, depending on coil Q and other assumptions, is often less than 2% for 80 meters and 10% for 40 meters. (These numbers come from the excellent, easy-to-use *MOBILE* antenna design program by Leon Braskamp, AA6GL, which is on the CD-ROM bundled with this book.)

At some locations, N6JF used an 80-meter dipole, which was very efficient and worked great on all bands when fed with open-wire line and an antenna tuner. However, it took over 40 minutes to set up and about 20 minutes to tear down, working with a sling shot and many tree snags. This is too much time to make a schedule or for an early morning departure, although it's OK if you plan to stay for a while. Even more important, there were often too many trees or other barriers (perhaps some even social) to allow putting up the dipole at a campsite.

When this happened he was stuck with the mobile antenna with poor efficiency. There had to be a better antenna for camper operation. The author decided on a large vertical.

A telescoping aluminum extension pole used for roller painting would make a good bottom section for the loaded vertical. These are available at many local home supply centers. The author's was 1 inch in diameter and 6 feet long, telescoping to almost 12 feet. He disassembled both sections and cross-cut a 1-inch slot in the top of the bottom section with a hacksaw to allow compression clamping with a hose clamp. The tip of the top section was fitted with an aluminum plug that had a 3/8-24 hole tapped in it. This procedure was a simple machine-shop operation. The plug was pounded into the top section and is quite snug. He tapped some set screws through the pole into the plug, however, just to be sure. An insulated, lay-down marine antenna mount fit perfectly into the bottom of the aluminum base and was secured with a bolt that also served as the electrical connection from the capacitor matching box. See **Fig 12** showing the aluminum base plate, the laydown mount and the antenna



Fig 12—Photo of aluminum base plate, showing details of mounting to the camper. The four banana-plug jacks on the bottom are for extra radials, if desired.



Fig 13—Photo showing the back of the camper, with the antenna in the lowered position, parallel to the ladder. The “Outback” standby mobile antenna is shown clamped to the left side of the ladder.



Fig 14—Schematic of tuning capacitor at base plate. C2 is an 800 pF transmitting mica capacitor. C1 is a three-section 365 pF broadcast tuning capacitor. S1 is closed for 80-meter operation.



Fig 15—Close-up photo of 80 and 40-meter coils, with top section and telescoping whip antenna with swivel bracket for tuning the top section for the higher bands. Note quick-disconnect connectors at top and bottom of both coils. The top whip is a Fiberglas CB whip, used on 80 and 40 meters.

mast itself lowered down the back of the camper. **Fig 13** shows the layout of the back of the camper, with the antenna on the right-hand side, laid down for travel.

The variable capacitor in the matching box is a surplus three-section 365-pF broadcast tuning capacitor. Two of three sections are connected in parallel and a switch parallels in the third section, along with an extra 800 pF mica capacitor for use on 80 meters. See the schematic in **Fig 14**.

The capacitor assembly was put in a custom-glued Plexiglas box to keep out the weather and mounted to a piece of plate aluminum, along with an SO-239 connector. The aluminum plate was riveted to the camper shell using a lot of aluminum rivets. Do not use steel. N6JF peeled back about a 4-inch wide section of the side of the camper for this direct aluminum-to-aluminum connection. People who are hesitant to modify their campers like this need to find an alternate low-resistance connection method. His camper was old enough not to be an issue.

For an extra low-resistance connection a $1\frac{1}{2}$-inch aluminum strip was added from the top of the base plate to the camper, as shown in Fig 12 near the 80-meter switch. The tuning knob protrudes from the side of the Plexiglas box. The four bottom holes in the plate are for banana plugs to connect ground radials if extra efficiency is desired. However, the roof of a camper is one of the better places for a mobile antenna, so the author seldom hooks up the radials. When he does use them, the tuning changes only a little.

To keep losses down, N6JF used coils wound with aluminum clothes-line wire on old mobile coil center sections with quick disconnect fittings. See **Fig 15**, which shows both the 80 and 40 meter coils, together with the top portion of the antenna. An article by Robert Johns, W3JIP, in October 1992 *QST* described techniques for building your own loading coils. The coils ended with a little more inductance than calculated and the author had to remove some turns. Both coils are spaced at 4 turns per inch. The 8-inch long 80-meter coil has 18 turns. The 7-inch long 40-meter coil has 8 turns.

The matching network is actually an L-section step-up match, using the net inductive reactance of the antenna plus the center loading coil. The PVC coil construction technique was described in W3JIP’s *QST* article and a follow-up Technical Correspondence piece in October 1992 *QST*. Basically, it consists of drilling an accurate row of slightly undersized holes along a length of $\frac{1}{2}$-inch PVC pipe and then carefully sawing down the center of the row of holes with a hack saw. Then, you trap the coil wires in the grooves between the two sawed halves and tie the two halves together with string. When you are satisfied that everything is proper, you then tighten the string and apply epoxy glue to make it strong and permanent.

One advantage of aluminum clothes line wire is that it is already coiled at the approximate diameter needed when you buy it and it is easy to position on the coil form.

The clothes line wire had a plastic coating, which wasn't removed except at the contact points. Once the epoxy dries, this method of construction does a good job of holding the finished coil together and it is lightweight.

The computed coil Q from the *MOBILE* antenna program is about 800 for the 80-meter coil and about 400 for the 40-meter coil. The author accidentally made the 40-meter coil 7 inches in diameter instead of a higher-Q 6 inch diameter. Even so, the whole antenna system with a 9-foot top section calculates as being 56% efficient on 80 meters and 85% for 40 meters.

The removable top section for 80 and 40 meters is a full-size fiberglass CB whip from RadioShack. The fiberglass whip has about a #16 hole in the center of it. Be sure to sand and paint the whip for protection against UV and to protect yourself against fiberglass spurs in the hands. N6JF tried a full-size stainless steel CB whip to get a slightly higher capacitance to ground because of larger conductor size but discovered it was far too heavy. That experience reinforced his decision that aluminum was a far more practical coil and base section material for this project.

Quick-disconnect connectors found years ago at a hamfest were used for both coil forms and for the top section. Bands higher than 40 meters don't need any loading coils and the antenna length can be telescoped to get a $^1/_4$ wavelength. Ten meters doesn't require any top section. Be sure to use some NOALOX or similar compound to prevent corrosion and poor connections at all aluminum joints. This is especially true for the telescoping sections and the aluminum rivets. The matching capacitor is in the circuit at all times but when the 80-meter switch is off you can set the capacitor at minimum (about 14 pF) and it is effectively out of the circuit, even at 10 meters. The author has not tried this antenna on power levels greater than about 100 W but the weakest link would probably be the matching capacitor. The voltage at the matching capacitor is low, so 200 W should be no problem.

You can achieve a 1:1 SWR match for 80 or 40 meters and a good SWR is obtained without retuning the base matching capacitor for approximately 100 kHz on 80 meters and most of 40 meters. The top section, however, does not have such low Q and needs to be tuned. The 2:1 SWR bandwidth on 80 meters is about 25 kHz and 150 kHz for 40 meters. Tuning is accomplished by using a telescoping FM portable radio antenna connected to the top-section whip with a stainless steel hose clamp. The maximum length of the telescoping section used was 29 inches, and it collapses down to 7 inches. A whip with an elbow was used to adjust the angle of the whip as well. A telescoping whip half the length would still be long enough for the full adjustment of both bands.

Adjustment of the top section is one of the penalties paid to achieve high efficiency for operation on 80 and 40 meters. Substituting an automatic antenna tuner would likely lose efficiency, particularly on 80 meters since the base resistance calculates to about 10 Ω. N6JF has not tried to make the antenna work on 160 meters. The SWR for the higher bands was good enough without any matching network.

As light as the antenna is, it still won't hold up in a moderate wind without some support guys. N6JF used $^3/_4$-inch and $^1/_2$-inch PVC support pipes in a telescoping arrangement for storage, but expanding to give an approximate 45° support at the top of the bottom section from both directions. One end of the telescoping section was connected to the camper roof with a hinge. The other end formed a snap-fit out of a PVC barrel that was cut lengthwise. See **Fig 16** and **Fig 17** for details. Even though it formed a good snap fit, N6JF didn't trust the joint for strong winds so he glued a piece of Velcro to the joint to close up the open end. Be careful, though, because Velcro deteriorates with exposure.

Another hose clamp near the top of the bottom section holds an $^1/_8$-inch line taken up the ladder to pull up the antenna without the need of an assistant. The disadvantage is you have to climb the roof. Use a non-slip floor mat or something similar to spread the load on the roof and to avoid slipping. Once on the roof, however, the coil is at a height for easy adjustment when the telescoping section is in the down position.

An advantage of being able to assemble the whole antenna on the roof is that you don't need a lot of swing-up room and you can clear trees easily. You can put calibration marks on the upper aluminum section for resonant lengths on the higher bands but just raise the top section up all the way for 80 or 40 meters. Mark also the small



Fig 16—Close-up of one of the snap-on support brackets used to brace the antenna. Note the Velcro pieces used to ensure that the antenna doesn't pop out of the bracket in the wind.



Fig 17—Photo showing the two support bracket poles bracing the bottom section of the antenna. The top tuning whip is evident above the homemade loading coil at the top of the bottom section.

coil tuning whip for 80 or 40 meters, although different locations may require slightly different settings due to detuning from nearby metal objects.

The overall length is about 21 feet. The top of the author's camper is about 10 feet high when on the truck, putting the tip at 31 feet. This antenna is definitely designed for use when you are parked at a fixed location. N6JF can put up this antenna in less than 5 minutes and can take it down in half the time. The success of this project has as much to do with knowing how and where you operate as it does paying attention to mechanical and electrical details. The antenna has been a good compromise between efficiency and convenience.

TWO PORTABLE 6-METER ANTENNAS

These antennas were described by Markus Hansen, VE7CA, in *The ARRL Antenna Compendium, Vol 5*. After years of HF operation, he became enthusiastic about VHF/UHF operation when he found a used Yaesu FT-726R VHF/UHF all-mode transceiver at a reasonable price.

But he became really enthused when he got on 6 meters and discovered the joys of driving to high mountain peaks to operate. Not only does an antenna have to be portable for this kind of operation, it must be easily assembled and disassembled, just in case you have to move quickly to a better location.

A Portable Two-Element Six-Meter Quad

VE7CA's primary objective was to construct a two-element quad using material found in any small town. It should not use a complicated matching network. The Gamma matches commonly used on quads do not hold up well when you are setting up and taking down these antennas in the field. The final design adjusted the distance between the driven and the reflector elements so that the intrinsic feed-point impedance was 50 Ω.

Fig 18 shows the dimensions for the boom and the boom-to-mast bracket. The boom is made from a $27^{1}/_{4}$-inch length of 2 × 2. (The actual dimension of 2 × 2 is closer to $1^{3}/_{4}$ by $1^{3}/_{4}$ inches but it is commonly known in lumber yards as a 2 × 2.) Use whatever material is available in your area, but lightweight wood is preferred, so clear cedar or pine is ideal. Drill the four $^{1}/_{2}$-inch holes for the spreaders with a wood bit, two at each end, through one of the faces of the 2 × 2 and the other through the other face. The boom-to-mast bracket is made from $^{1}/_{4}$-inch fir plywood.

The spreaders are $^{1}/_{2}$-inch dowel. The local lumberyard had a good supply of fir dowels but other species of wood are available. The exact material is not important. Maple is stronger but expensive. Fiberglass would be ideal but it is not always available locally. Cut two of the $^{1}/_{2}$-inch dowels to a length of $83^{5}/_{8}$ inches for the driven element spreaders and two to 88 inches for the reflector spreaders. **Fig 19** shows one end of the boom with the two spreaders inserted. The mast was made from two six-foot lengths of $1^{3}/_{4}$-inch fir dowel. Again, use whatever you may have available. Waterproof all wooden parts with at least two coats of exterior varnish.

While you are at the lumberyard or hardware store look for plastic pipe that fits over the end of the $^{1}/_{2}$-inch spreaders. You will need a one-foot length, with some to spare. Cut it into seven equal lengths, approximately one inch long, and one to a length of $1^{1}/_{2}$ inches. Drill a $^{1}/_{16}$-inch hole through the seven equal lengths $^{1}/_{4}$ inch from the ends, and two holes one above the other $^{1}/_{4}$-inch apart on the $1^{1}/_{2}$-inch sleeve. VE7CA used #14 hard-drawn stranded bare copper wire for the elements. Do not use insulated wire unless you are willing to experimentally


27-1/4"
1"
24"
24"
8"
1/4" space
2x2 Cedar or Pine
Drill 1/2" holes with wood bit
Glue and screw 1/4" plywood to boom with 1-1/4"#8 wood screws
1/4" Fir plywood
4"
Drill 4 holes for U bolts

Fig 18—Dimensions for the boom-to-mast bracket for VE7CA's portable two-element 6-meter quad.



Fig 19—Photo of one end of the VE7CA quad with the two spreaders inserted.

determine the element lengths, since the insulation detunes each element slightly.

Cut the reflector element 251 inches long and slip one end of the wire through the holes you drilled in four of the plastic sleeves. Don't attempt to secure the wire to the plastic sleeves at this point. Cross the end of the reflector elements one inch from their respective ends and twist and solder together. The total circumference of the reflector element should be 249 inches when the ends are connected together.

Cut the driven element wire to 241 inches and slip three of the 1-inch sleeves onto the wire. Again, don't secure the wires to the sleeves yet. Then the ends are passed through the two holes in the $1\frac{1}{2}$-inch pipe. Wrap the ends around the pipe and twist them back onto themselves to secure the wire. The coax feed line is attached directly to the two ends at this point. The circumference of the driven-element loop from the points where the coax is attached should be $236\frac{5}{8}$ inches. Solder the coax feed line to the driven element and waterproof the coax with silicone seal. The author used RG-58, as it is lightweight. The length required for a portable installation is typically not very long, maybe 20 feet, so the loss in the small cable is not excessive. Near the feed point, coil the coax into six turns with an inside diameter of two inches. This is an effective method of choking any RF from flowing on the outside of the coax shield.

Begin assembling the quad by pushing the two reflector spreaders, without wires attached, through one end of the boom and the two shorter driven-element spreaders through the holes in the other end of the boom. Center the spreaders and mark the spreaders with a black felt-tip pen next to the boom. Now insert a $1\frac{1}{2}$ #8 wood screw or a threaded L-hook into the boom so that it just touches one of the spreaders. Take the screw or L-hook out and file the end flat, then reinsert it so that it is just snug against the spreaders. The author only used two L-hooks for the two vertical spreaders; the horizontal spreaders are held in the proper position by the tension of the wire loops. If you use an L-hook, you can unscrew it with your hands—you won't have to worry about leaving the screwdriver at home.

You are now ready to assemble the wire loops. Take the reflector loop and place the four plastic caps over the ends of the reflector spreaders. Equalize the wire lengths between the spreader so that the loop is square. Now, secure the plastic sleeve pipes by tightly wrapping wire around the sleeve and the wire element and soldering the wire in place. See **Fig 20**, a photo showing one of the plastic sleeves slipped over one of the spreader ends, with the wire element through the hole and fastened in place. Follow the same procedure with the driven element.

Fig 21 shows the quad's boom, with the plywood boom-to-mast bracket fastened with wood screws and glue. Two U-bolts are used to attach to the mast. When the quad is raised, the shape of the loop is commonly known as a diamond configuration. The mast consists of two six-foot lengths of doweling joined together with a two-foot length of PVC plastic pipe, held together with wood screws.

Make a slot the width of a #8 wood screw about one inch deep from the top of the plastic PVC pipe and then put the top mast into the plastic pipe. Insert a one inch #8 wood screw into the bottom of the slot you cut into the top of the pipe and tighten only enough so that the top mast can be removed without unscrewing it. VE7CA drove a nail into the end of the lower mast and left it exposed an inch or more. This end is placed in the ground and the nail holds the pole in place. A strip of wood approximately 1 × 3 and long enough to cross over the roof rack of the family van is used to hold the center of the antenna mast to the roof rack of the van with small diameter rope. See **Fig 22** for a photo of the quad in action next to the family van.

To disassemble the quad, lay it on its side, slip the plastic sleeves off the ends of the spreaders and roll up



Fig 20—Photo showing one of the plastic sleeves slipped over end of a spreader to provide a mechanical mounting point and support for the wires.



Fig 21—Photo of the two-element quad's boom, with the plywood boom-to-mast bracket secured with wood screws and glue.

Fig 22—Ready for action! VE7CA has set up his quad next to the family van.

the wire loops. Loosen the L-hooks holding the vertical spreaders in place. Push the spreaders out of the boom, loosen the U-bolts and free the mast from the boom.

That is all there is to it. It takes about two minutes to put it up, or take it down. It is quite sturdy and has survived several high-wind storms.

A Three-Element Portable 6-Meter Yagi

The idea to build a Yagi antenna resulted when the author traded the family van for a compact car. He needed something that would fit into the trunk of the car. At close to 7-feet long, the quad spreaders were too long. Computer modeling showed that a three-element Yagi on a five-foot boom also could pick up about 1.5 dB gain over the short-boom two-element quad. A five-foot boom fits into the trunk or across the back seat of the car, but something had to be done about the nine-foot elements!

One day VE7CA noticed a box of portable-radio telescoping antenna elements at the radio parts store. They were 54 inches long when fully extended. He next found a 60-inch length of aluminum tubing that fit over the end of the telescoping elements. There are many different sizes of telescoping antenna elements, with different diameters. This is where you will have to use your scrounging skills! **Fig 23** shows how the tubing is used as a center section to join two telescoping elements together. It also serves to extend the total length of each element, since two telescoping elements themselves are not long enough to resonate on six meters. See **Table 3** for dimensions and element spacings. Each center section is slotted at both ends with a hacksaw, and stainless-steel hose clamps are used to secure the telescoping elements.

Fig 24 shows the center sections of the three elements with their mounting brackets. A square boom was used to obtain a flat surface to work with. **Fig 25** shows how the reflector is attached to the end of the boom with two $1^1/_2$-inch 10-32 bolts and wingnuts. **Fig 26A** provides the dimensions and details for the reflector and director element-to-boom brackets, which are formed from $^1/_{16}$-inch plate aluminum. The driven element is split in the center and is insulated from the boom. Fig 26B shows details for the driven-element bracket. **Fig 27** is a photo



Fig 23—Photo showing a piece of aluminum tubing used as a center section to join the two telescoping tips together.



Fig 24—A view of the center sections of the three Yagi elements with their mounting brackets.



Fig 25—Photo detailing attachment of the reflector to the square-section boom, using two #10 bolts and wingnuts.



Drill all hole sizes to suit available hardware
1-1/4"
2"
Curve aluminum snugly over center element
(A)
Holes for banana sockets
1-5/8"
1"
1-1/2"
Bend snugly over plastic sleeve
2-3/4"
(B)

Fig 26—At A, details for the reflector and director element-to-boom brackets, made of $^1/_{16}$-inch plate aluminum. At B, details for the driven-element bracket. These are screwed to the square boom.

of the driven element with the hairpin matching wire and the banana plugs used to connect the coax to the driven element. You could use a female PL-259 connector if you wish. VE7CA used #14 solid bare copper wire for the hairpin. It is very durable—even after being severely warped in the car trunk, it can be bent back into shape quickly and easily.

The boom is $^3/_4$-inch square aluminum, 65 inches long. The material was found at a local hardware store. To detach the elements, just loosen the wing nuts and remove the elements from the boom. A similar method was used to attach the support mast to the boom.

As with the quad, a choke balun was used, consisting of a coil of 6 turns of coax with an inside diameter of 2 inches. To tune the hairpin match, assemble the Yagi on its mast and extend the elements. Spray switch contact solution on a cloth and wipe any dirt and grease from the elements. Push the elements together and apart a

Table 3

Three-Element Yagi, Element Lengths and Spacing Along the Boom, and Hairpin Dimensions

Element Along Boom	Spacing Section Ele. (inches)	Center Length (inches)	Telescoping (inches)	Total Length (inches)
Reflector	0	$22^3/_4$	$51^1/_2$	$125^3/_4$
Driven	28	$9^3/_4$ *	$48^5/_8$	$58^3/_{16}$
Director	$63^3/_8$	$14^1/_2$	$51^1/_4$	117
Hairpin	#14 wire	4 long	$1^5/_8$ spacing	

* Driven-element uses 2 sections insulated at center



Fig 27—Photo of the driven element, complete with hairpin match and the banana plugs used to connect the coax cable to the driven element.

couple of times so that the contact solution cleans the elements thoroughly. Attach the antenna mast to your vehicle or use whatever method of support you intend to use in the field. Connect an SWR meter and a transmitter to the coax feeding the antenna. VE7CA used two alligator clips soldered together to slide along the two hairpin wires to find the position for the lowest SWR. The dimensions computed by computer were correct! The SWR was below 1.16:1 from 50.05 to 50.2 MHz.

You can take this antenna out of the trunk of the car and assemble it in less than two minutes. One caution: the telescoping elements when fully extended are quite fragile. VE7CA has not broken one as yet, but carrying a spare element just in case would be a good idea.

VE7CA 2-Element Portable HF Triband Yagis

These portable HF wire Yagis were described by Markus Hansen, VE7CA, in November 2001 *QST* and in *The ARRL Antenna Compendium, Vol 7*.

A 20/15/10-Meter Triband 2-Element Yagi

VE7CA wanted a simple 2-element wire Yagi for 20/15/10 meters that could be stored in the ski boot of his car. The basic concept comprises three individual dipole driven elements, one each for 20, 15 and for 10 meters tied to a common feed point, plus three separate reflector elements. The elements are strung between two 2.13-meter (7-foot) long, 2 × 2-inch wood spreaders, each just long enough to fit into the ski boot of his car.

By playing with the reflector-to-driven element spacing and the initial driven-element lengths, VE7CA was able to come up with a feed-point impedance on each band that allowed the use of a single setting for the shorting bar on a hairpin match. The result was a very acceptable match over the lower portions of each band. The layout of the 20/15/10-meter triband wire Yagi is shown in **Fig 28**, with the dimensions provided in **Table 4**.

The dimensions shown in Table 4 are what resulted after tuning for the lowest SWR in the middle of the lower portion of each band. VE7CA set his system up by hanging one end of the antenna from a tree and sloped it downwards at 45º, tying the lower end to a peg in the ground. The height at the feed point was 30 feet.

The feed-point impedance of an antenna is affected by many environmental factors. The presence of a reflector relatively close to the driven element has a major effect, since the impedance at the driven element in a Yagi is affected by the tuning of the driven element itself, by the spacing and length of the reflector element and to a lesser extent the height of the antenna above ground and the character of the soil itself. The real challenge in a multiband Yagi with a single feed line is to obtain a low SWR on all the bands.

The hairpin match is one of the easiest matching systems to make. It is easy to adjust and since wire is the only ingredient, it can be coiled up with the rest of the antenna when the antenna is disassembled. The feed-point impedance of the Yagi with a reflector element spaced 0.1 λ behind the driven element typically produces a resistance around 20 Ω. By shortening the driven element from its resonant length, capacitive reactance is added to the feed-point resistance. This can be cancelled by shunting the feed point with an inductor in the shape of a wire loop resembling a *hairpin*. This causes a step up of the 20-Ω feed-point resistance to 50 Ω.

Table 4
Dimensions for 20/15/10-Meter Tribander

Frequency MHz	*Spacing DE to Refl cm (feet)*	*Driven Element Half Length cm (feet)*	*Reflector Length cm (feet)*	*Hairpin Length cm (inches)*
14.1	213 (6.99)	488 (16.01)	1065 (34.94)	43 (14.9)
21.1	175 (5.74)	335 (10.99)	708 (23.23)	
28.25	125 (4.1)	254 (8.33)	531 (17.42)	

Spacing between hairpin wires is 10 cm (4 inches).


Light Nylon Cord
Insulator
2" × 2" Pine or Cedar
20 m Reflector R1
15 m Reflector R2
3/16" Nylon Rope V Sling
10 m Reflector R3
S1
S2
S3
20 / 30-m Driven Element Total Length / Side D1
Tie Knot Here
15 / 17-m Driven Element Total Length / Side D2
Adjust tension by shortening this side of V so when antenna is raised it is in the horizontal plane
10 / 12-m Driven Element Total Length / Side D3
Insulator
Drill Hole and Thread Rope Through Boom
Insulators
Light Nylon Cord
1/2" PVC Pipe Spreaders
Hairpin Match

Fig 28—Dimensions for VE7CA's 2-element 20/15/10-meter triband Yagi.

The Balun

Fig 29 shows the hairpin match and the common-mode choke balun for the 10/15/20-meter triband wire Yagi. You should let the coax drop straight down from the center insulator and attach it to the center of the hairpin shorting bar. Continue by making a coil using the coax of 8 turns, with a diameter of about 4 inches. This balun will choke off RF flowing along the outside of the coax shield that would otherwise distort the radiation pattern of the antenna. The center of the shorting bar is at a neutral potential, so there is no harm in attaching the coax feed line at that point.

Flattop or Tilted?

If DX is your main interest, then you want to tilt the antenna towards the vertical to emphasize the lower elevation angles. Remember that the radiation pattern is quite dependent on ground conductivity and dielectric constant for a vertically polarized antenna. A location close to saltwater will yield the highest gain and the lowest radiation angle. With very poor soil in the near and far field, the peak radiation angle will be higher and the gain less.

VE7CA has had numerous opportunities to test this out while operating portable at his favorite location. Using two trees as supports he can pull the antenna to horizontal with the feed line about 7 meters above the ground. In this position, with 20 meters open to Europe, he found it difficult to work DX on CW with 3 W of output power. However, when he changed the slope of the antenna so that it is nearly vertical he not only heard more DX stations, but he found it relatively easy to work DX. The sloping antenna always performs much better for working DX than a low horizontal antenna.


Wrap Wire Around Spreader and Antenna Wire on Both Sides
Loop Coax Over Insulator and Seal Against Weather
1/2" PVC Pipe Spreader
9 cm (3.5")
9 cm (3.5")
(10 cm) 4"
L
Hard Drawn Stranded #14 Copper Wire
Attach Coax to Center Shorting Bar with Tie Wrap or String
#14 Solid Copper House Wire
Choke Balun 6 to 8 Turns 4" Diameter

Fig 29—Details of feed point for 20/15/10-meter triband Yagi. The same mechanical support is provided for the balun and feed coax for the 30/17/12-meter tribander.

A 30/17/12-Meter Triband 2-Element Yagi

When the author attempted to add 17 and 12 meter elements to the existing 20/15/10-meter Yagi model he became exasperated. Adding two more driven elements and reflectors brings many more variables into the equation! It became clear that there was serious interaction between the elements. He could not obtain a workable feed-point impedance on all five bands that could be transformed to 50 Ω using a single hairpin match. There was also serious pattern distortion on 12 meters.

Even building a WARC-only triband Yagi for 30/17/12 meters turned out to be a real challenge. VE7CA had difficulty finding a combination that would allow him to use a single matching system to transform the feed-point impedance of the combined driven elements to 50 Ω. He couldn't create a 30/17/12 triband Yagi using the same design principles as his 20/15/10-meter version. The main problem occurred on 12 meters. Not only was the feed-point impedance unmanageable, but the radiation pattern had four lobes, not the single lobe you'd like from a Yagi.

He decided to try the *Modified Coaxial-Sleeve* method, more aptly termed by K9AY the *Coupled-Resonator (C-R)* in his article in *The ARRL Antenna Compendium, Vol 5*. The K9AY method uses a single driven element, with other elements placed in very close proximity (but not physically connected) to the driven element. By starting with the dimensions suggested by K9AY for a triband 30/17/12-meter dipole, VE7CA was able to develop a 2-element Yagi with acceptable feed-point impedances on all three bands using a single hairpin match. Notice that this WARC design uses a 2 × 2-inch wooden boom length that is 230 cm (7.5 feet) long. Of course, the antenna can't fit into a typical ski boot anymore, so VE7CA had to put it on a roof rack for transportation.

The space between the tightly coupled driven elements is only 3.7 cm (1.5 inches), so you need to use more PVC pipe spreaders than in the 20/15/10 design to make sure the driven-element wires stay as close as possible to the desired spacing without physically touching each other. The driven elements lie in the horizontal plane and the hairpin match and feed line hang down vertically from the center of the 30-meter driven element.

The spacing between the 30-meter driven elements and the other two conductors and the size of the wire all played a part in developing this antenna for a single feed line with the common hairpin match. Do not change the wire size from the recommended #14 for the driven elements unless you are willing to spend a considerable amount of time with a *NEC*-based modeling program retweaking the antenna. This is not the case with the 20/15/10 tri-band Yagi, where any convenient sized wire is acceptable.

Using #14 gauge wire allows all the Yagi antennas in this article to be used at the maximum power levels allowed in North America. The only limiting factor is the power handling capability of the feed line. However, even RG-58 should work for the relatively short length from the feed point down to ground level, where you can change to RG-8 or some other higher-power, lower-loss coaxial cable if you wish. **Fig 30** is a detailed drawing of the 30/17/12-meter driven element. The other dimensions for the 30/17/12-meter triband Yagi are shown in **Table 5**.

Assembly

When you are ready to assemble your wire Yagi, start by attaching the longest reflector element and the driven element assembly to the wood end booms. Do this with the wires and the booms on the ground. Next attach the V slings to both of the booms and with ropes attached to the V slings pull the array up off the ground between two supports (perhaps two trees). A height of 1.5 meters (5 feet) above the ground makes it easy to work on the antenna while you add the other reflector elements and adjust the V slings. Pull them tight so that the array is fairly flat. It won't stay horizontal, because the driven elements are heavier than a single reflector element. So you will need to support the 2 × 2-inch spreaders so they are horizontal. Lean the booms on something at a convenient height, such as the rungs of two step ladders. Now add the two other reflector elements, but don't pull them as tight as the longest reflector. Next attach the feed line.

Table 5
Dimensions for 30/17/12-Meter Tribander

Frequency MHz	*Spacing DE to Refl cm (feet)*	*Driven Element Length cm (feet)*	*Reflector Length cm (feet)*	*Hairpin Length cm (inches)*
10.12	230 (7.5)	713 (23.4) Half	1476 (48.4)	24.5 (9.5)
18.11	165 (5.4)	808 (26.5)	822 (27.0)	
24.91	120 (3.9)	570 (18.7)	606 (19.9)	

Spacing between hairpin wires is 10 cm (4 inches). Note that dimensions for 17 and 12-meter driven elements are full lengths, since they are not broken with insulator in the middle, unlike all driven elements for 20/15/10-meter triband design in Table 4.


Spacers (3/8" PVC Pipe)
Spaced 30 cm (1') Apart
(Spacers Continue on the Other Side)
Feedpoint and Hairpin Match
(See Fig 29)
12 M (570 cm / 18.7 ft)
713 cm (23.4 ft)
Per Side
3.7 cm (1.5")
3.7 cm (1.5")
17 M (808 cm / 26.52 ft)
Insulator
Masons line or fishing line - After attaching center 30-meter driven element to end boom, pull these cords real tight to help keep driven element in the horizontal plane

Fig 30—Layout of 30-meter driven element with coupled resonators for 17 and 12 meters.

V Slings

Since the author wanted to be able to raise the 30/17/12-meter triband antenna by himself, he again used only one rope on either end of the array. One end goes over a tree limb and the other end is tied to a stake in the ground or some other nearby support, perhaps a tree trunk. Using only one attachment rope on either end makes it very easy to change beam direction by walking the antenna around the antenna support tree or tower. To accomplish this he used two V slings, one on each end attached to the 2 × 2-inch spreaders.

The secret to keeping the antenna level in the horizontal plane is that the V slings are not equilateral in shape. The combined weight of driven elements, balun and feed line is heavier than the reflectors. If the length of the sides of the V are equal, the array will rotate downwards. The driven elements will end up facing the ground, with the reflectors facing up. Adjust the V slings so that the antenna will stay level in the horizontal plane by shortening the length of the side of the V attached to the driven elements. It is quite easy to adjust in the field, and once you have it adjusted it stays balanced.

Once you raise the antenna to its operating position and in the horizontal plane, you can change direction 180° by pulling on the feed line. As you pull, the whole array will slowly turn over. Stop it from turning by holding onto the feed line once the array has swung over to face the opposite direction.


14 ft
2" × 2" Boom
V Sling
Balun
Reflector
120°
Included
Angle
120°
Included
Angle
Driven Element
Insulators
14 ft
2" × 2" Boom
V Sling
14 ft
2" × 2" Boom
V Sling
Stake
Tie to
Stake
50-Ω Coax
Feed Line
Stake
To change direction move support ropes to different stakes.

Fig 31—Layout for inverted-V 40-meter portable wire Yagi suspended from tower.

SWR Adjustment

Since you may situate your antenna in an entirely different position than VE7CA did, you may need to fine tune your antenna. Begin with the dimensions in Table 5 as a starting point. Make a temporary shorting bar using two alligator clips joined by a piece of wire and attach them at the recommended position. Next raise the antenna to the desired final position. Using an antenna analyzer (or transmitter and SWR meter) plot the SWR over all three bands. Start with the lowest band, 30 meters and adjust the shorting bar up or down to find the lowest SWR point in the portion of the band you plan to operate in. (This procedure also works if you wish to adjust the 20/15/10-meter tribander. Start with the lowest frequency.)

You shouldn't have to move the shorting bar very far from the suggested length. Now that you have determined the right shorting-bar position, adjust the other two driven element lengths for the lowest SWR in the portion of those bands in which you plan to operate. You may have to compromise with the position of the shorting bar to find a satisfactory range where the SWR is acceptable on all three bands. After satisfying himself with the position of the shorting bar, VE7CA replaced the alligator clips simply by folding one side of the parallel hair-pin wire lengths over to the other side and soldering it in the position where the alligator clips had been attached. The author does not recommend changing the reflector element lengths unless you are familiar with antenna modeling programs and are willing to model different spacing or element lengths.

40-Meter Wire Yagis

After his November 2001 *QST* article, VE7CA received several requests for a 40-meter wire Yagi. One ham mentioned that he wanted to be able to pull up a 40-meter Yagi between two towers and to be able to flip it over to change direction. Another wanted a 40-meter Yagi he could pull up on a single tower for the winter DX contests and then put it away during the summer. So VE7CA ran four different 40-meter scenarios in his computer models:

1. A horizontal 2-element wire Yagi at 65 feet.
2. A sloping 2-element wire Yagi, with one end at 65 feet and sloping downward 30° from vertical.
3. A sloping 2-element wire Yagi, with one end at 65 feet and sloping downward 65° from vertical.
4. An inverted-V 2-element wire Yagi with the apex at 65 feet and an included angle between the wires of 120°.

Fig 31 shows the layout for an inverted-V system and **Table 6** lists the element and hairpin lengths. Elevation patterns for the 40 meter antennas are compared in **Fig 32**, with a reference antenna of a single flattop dipole at 65 feet. As they say, a picture is worth a thousand words. If your interest is DX, it is very clear that horizontal and high is a very good rule of thumb for most antennas.

Yes, a $^{1}/_{4}$ wave vertical over salt water or 120 $^{1}/_{4}$-wave radials over good ground will produce very low radiation angles, but such systems are not exactly portable and we don't all live near the ocean. Mind you, if you can manage to locate antenna Number 3 (the most vertically oriented wire Yagi) next to the ocean, you would be very happy.

The point here is that if you have two towers and you're not fortunate enough to be located on a saltwater marsh, you should pull the 40-meter array up as high and as horizontal as you can. If you have only one tower and don't need to change direction often, then try the inverted-V configuration. You can still change the direction by walking each end around the tower.

However, even the sloping 40-meter Yagi with one end at 65 feet up a tower (or tree) and the other end attached with a long rope as far as possible from the tower will still put out a very respectable signal. It is directional, and you can walk it around the tower to change direction or you can

Table 6
40-Meter Wire Yagi Configurations

Configuration	*Driven Element cm (feet)*	*Reflector cm (feet)*	*Hairpin Length cm (feet)*
1. Horizontal	1978 (64.90)	2098 (68.83)	Approx 50 cm
2. –30° Sloper	1978 (64.90)	2113 (69.32)	(22 inches)
3. –65° Sloper	1978 (64.90)	2101 (68.93)	
4. Inverted V	2040 (66.93)	2126 (69.75)	

Spacing between driven element and reflector is 427 cm (14 feet). Spacing between parallel hairpin wires is 10 cm (4 inches). The lengths shown above are the total wire length for each element.



Fig 32—Comparisons of elevation patterns for five 40-meter antennas: a 2-element flattop Yagi at 65 feet; a 2-element inverted-V Yagi at 65 feet; a 2-element Yagi sloped 65° from the vertical plane; a 2-element Yagi sloped 30° from the vertical plane; and a horizontal dipole at 65 feet.



Fig 33 — VE7CA portable 2-element 20/15/10-meter wire Yagi installed at Plimoth Plantation in Plymouth, Massachusetts. (*Photo courtesy K1HTN*).

flip the antenna over and change direction 180° very quickly.

Summary

You don't need a 10-meter (60-foot) high tower, a commercial triband Yagi and a rotator to put out a good signal on the HF bands. Wire Yagis work very well and they can be inexpensive and easy-to-build, using components found at your local hardware store. **Fig 33** is a photograph of a successful portable installation in Massachusetts.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below.

G. Breed, K9AY, "The Coupled-Resonator Principle: A Flexible Method for Multiband Antennas," *The ARRL Antenna Compendium, Vol 5* (Newington: ARRL, 1996), p 109ff.

R. J. Decesari, "A Portable Quad for 2 Meters," *QST*, Oct 1980, and "Portable Quad for 2 Meters, Part 2," Technical Correspondence, *QST*, Jun 1981, p 39ff.

D. DeMaw, "A Traveling Ham's Trap Vertical," *QST*, Oct 1980, p 28ff.

J. Hall, "Zip-Cord Antennas—Do They Work?" *QST*, Mar 1979, p 31ff.

M. Hansen, "A Portable 2-Element Triband Yagi," *QST*, Nov 2001, p 35ff.

M. Hansen, "Some More VE7CA 2-Element Portable Yagis," *The ARRL Antenna Compendium, Vol7* (Newington: ARRL, 2002, p 183ff.

C. L. Hutchinson, "A Tree-Mounted 30-Meter Ground-Plane Antenna," *QST*, Sep 1974, p 16ff.

C. W. Schecter, "A Deluxe RV 5-Band Antenna," *QST*, Oct 1980, p 38.

Chapter 16

Mobile and Maritime Antennas

Mobile antennas are those designed for use while antennas, most amateurs think of a whip mounted on an automobile or other highway vehicle, perhaps on a recreational vehicle (RV) or maybe on an off-road vehicle. While it is true that most mobile antennas are vertical whips, mobile antennas can also be found in other places. For example, antennas mounted aboard a boat or ship are mobile, and are usually called *maritime antennas*. **Fig 1** shows yet another type of mobile antenna—those for use on handheld transceivers. Because they may be used while in motion, even these antennas are mobile by literal definition.

Pictured in Fig 1 is a telescoping full-size quarter-wave antenna for 144 MHz, and beside it a *stubby* antenna for the same band. The stubby is a helically wound radiator, made of stiff copper wire enclosed in a protective covering of rubber-like material. The inductance of the helical windings provides electrical loading for the antenna. For frequencies above 28 MHz, most mobile installations permit the use of a full-size antenna, but sometimes smaller, loaded antennas are used for convenience. The stubby, for example, is convenient for short-range communications, avoiding the problems of a lengthier, cumbersome antenna attached to a handheld radio.



Fig 1—Two mobile antennas—mobile because they may be used while in motion. Shown here are a telescoping $^1/_4$-λ antenna and a "stubby" antenna, both designed for use at 144 MHz. The $^1/_4$-λ antenna is 19 inch long, while the stubby antenna is only $3^1/_2$ inch long. (Both dimensions exclude the length of the BNC connectors. The stubby is a helically wound radiator.

Below 28 MHz, physical size becomes a problem with full-size whips, and some form of electrical loading (as with the stubby) is usually employed. Commonly used loading techniques are to place a coil at the base of the whip (base loading), or at the center of the whip (center loading). These and other techniques are discussed in this chapter.

Few amateurs construct their own antennas for HF mobile and maritime use, since safety reasons dictate very sound mechanical construction. Several construction projects are included, however, in this chapter for those who may wish to build their own mobile antenna. Even if commercially made antennas are installed, most require some adjustment for the particular installation and type of operation desired and the information given here may provide a better understanding of the optimization requirements.

HF-MOBILE FUNDAMENTALS

Fig 2 shows a typical bumper-mounted center-loaded whip suitable for operation in the HF range. Jack Schuster, W1WEF, operates 80 through 2 meters from his car. The antenna could also be mounted on the car body itself (such as a fender), and mounts are available for this purpose. The base spring and tennis ball act as shock absorbers for the bottom of the whip, as the continual flexing while in motion would otherwise weaken the antenna. A short heavy mast section is mounted between the base spring and loading coil. Some models have a mechanism that allows the antenna to be tipped over for adjustment or for fastening to the roof of the car when not in use.

It is also advisable to extend a couple of guy lines from the base of the loading coil to clips or hooks fastened to the roof gutter on the car, or to the trunk and



Fig 2—A typical bumper-mounted HF mobile antenna, as used by W1WEF. Note the nylon guy lines and the tennis ball used as a shock absorber. (*Photo courtesy W1WEF.*)

rear bumper, as W1WEF has done. Nylon fishing line (about 40-pound test) is suitable for this purpose. The guy lines act as safety cords and also reduce the swaying motion of the antenna considerably. The feed line to the transmitter is connected to the bumper and base of the antenna. Good low-resistance connections are important here.

Tune-up of the antenna is usually accomplished by changing the height of the adjustable whip section above the precut loading coil. First, tune the receiver and try to determine where the signals seem to peak up. Once this frequency is found, check the SWR with the transmitter on, and find the frequency where the SWR is lowest. Shortening the adjustable section will increase the resonant frequency, and making it longer will lower the frequency. It is important that the antenna be away from surrounding objects such as overhead wires by ten feet or more, as considerable detuning can occur. Once the setting is found where the SWR is lowest at the center of the desired frequency range, the length of the adjustable section should be recorded.

Propagation conditions and ignition noise are usually the limiting factors for mobile operation on 10 through 28 MHz. Antenna size restrictions affect operation somewhat on 7 MHz and much more on 3.5 and 1.8 MHz. From this standpoint, perhaps the optimum band for HF-mobile operation is 7 MHz. The popularity of the regional mobile nets on 7 MHz is perhaps the best indication of its suitability. For local work, 28 MHz is also useful, as antenna efficiency is high and relatively simple antennas without loading coils are easy to build.

As the frequency of operation is lowered, an antenna of fixed length looks (at its feed point) like a decreasing resistance in series with an increasing capacitive reactance. The capacitive reactance must be tuned out, necessitating the use of an equivalent series inductive reactance or loading coil. The amount of inductance required will be determined by the placement of the coil in the antenna system.

Base loading requires the lowest value of inductance for a fixed-length antenna, and as the coil is placed farther up the whip, the necessary value increases. This is because the capacitance of the shorter antenna section (above the coil) to the car body is now lower (higher capacitive reactance), requiring more inductance to tune the antenna to resonance. The advantage is that the current distribution on the whip is improved, increasing the radiation resistance. The disadvantage is that requirement of a larger coil also means the coil size and losses increase. Center loading has been generally accepted as a good compromise with minimal construction problems. Placing the coil $^2/_3$ the distance up the whip seems to be about the optimum position.

For typical antenna lengths used in mobile work, the difficulty in constructing suitable loading coils increases as the frequency of operation is lowered. Since the required resonating inductance gets larger and the radiation resistance decreases at lower frequencies, most of the power is dissipated in the coil's loss resistance and in other ohmic losses. This is one reason why it is advisable to buy a commercially made loading coil with the highest power rating possible, even if only low-power operation is planned.

Coil losses in the higher-power loading coils are usually less (percentage-wise), with subsequent improvement in radiation efficiency, regardless of the power level used. Of course, the above philosophy also applies to homemade loading coils, and design considerations will be considered in a later section.

Once the antenna is tuned to resonance, the input impedance at the antenna terminals will look like a pure resistance. Neglecting losses, this value drops from nearly 15 Ω at 21 MHz to 0.1 Ω at 1.8 MHz for an 8-foot whip. When coil and other losses are included, the input resistance increases to approximately 20 Ω at 1.8 MHz and 16 Ω at 21 MHz. These values are for relatively high-efficiency systems. From this it can be seen that the radiation efficiency is much poorer at 1.8 MHz than at 21 MHz under typical conditions.

Since most modern gear is designed to operate with a 50-Ω transmission line, a matching network is usually necessary, especially with the high-efficiency antennas previously mentioned. This can take the form of either a broadband transformer, a tapped coil, or an LC matching network. With homemade or modified designs, the tapped-coil arrangement is perhaps the easiest one to build, while the broadband transformer requires no adjustment. As the losses go up, so does the input resistance, and in less efficient systems the matching network may not be needed.

The Equivalent Circuit of a Typical Mobile Antenna

In the previous section, some of the general considerations were discussed, and these will now be taken up in more detail. It is customary in solving problems involving electric and magnetic fields (such as antenna systems) to try to find an equivalent network with which to replace the antenna for analysis reasons. In many cases, the network may be an accurate representation over only a limited frequency range. However, this is often a valuable method in matching the antenna to the transmission line.

Antenna resonance is defined as the frequency at which the input impedance at the antenna terminals is purely resistive. The shortest length at which this occurs for a vertical antenna over a ground plane is when the antenna is an electrical quarter wavelength at the operating frequency; the impedance value for this length (neglecting losses) is about 36 Ω. The idea of resonance can be extended to antennas shorter (or longer) than a quarter wave, and means only that the input impedance is purely resistive. As pointed out previously, when the frequency is lowered, the antenna looks like a series RC circuit, as shown in **Fig 3**. For the average 8-foot whip, the capacitive reactance of C_A may range from about –150 Ω at 21 MHz to as high as –8000 Ω at 1.8 MHz, while the radiation resistance R_R varies from about 15 Ω at 21 MHz to as low as 0.1 Ω at 1.8 MHz.

For an antenna less than 0.1 λ long, the approximate radiation resistance may be determined from the following:

$$R_R = 273 \times (\ell f)^2 \times 10^{-8} \qquad \text{(Eq 1)}$$

where ℓ is the length of the whip in inches, and f is the frequency in megahertz.

Since the resistance is low, considerable current must flow in the circuit if any appreciable power is to be dissipated in the form of radiation in R_R. Yet it is apparent that little current can be made to flow in the circuit as long as the comparatively high series reactance remains.

Antenna Capacitance

Capacitive reactance can be canceled by connecting an equivalent inductive reactance, (coil L_L) in series, as shown in **Fig 4**, thus tuning the system to resonance.

The capacitance of a vertical antenna shorter than a quarter wavelength is given by:

$$C_A = \frac{17\ell}{\left[\left(\ln \frac{24\ell}{D}\right) - 1\right]\left[1 - \left(\frac{f\ell}{234}\right)^2\right]} \qquad \text{(Eq 2)}$$

where

C_A = capacitance of antenna in pF
ℓ = antenna height in feet
D = diameter of radiator in inches
f = operating frequency in MHz

$$\ln \frac{24\ell}{D} = 2.3 \log_{10} \frac{24\ell}{D}$$

Fig 5 shows the approximate capacitance of whip antennas of various average diameters and lengths. For 1.8, 4 and 7 MHz, the loading coil inductance required (when the loading coil is at the base) would be approximately the inductance required to resonate in the desired band (with the whip capacitance taken from the graph). For 10 through 21 MHz, this rough calculation will give more than the required inductance, but it will serve as a



Fig 3—At frequencies below resonance, the whip antenna will show capacitive reactance as well as resistance. R_R is the radiation resistance, and C_A represents the antenna capacitance.



Fig 4—The capacitive reactance at frequencies below the resonant frequency of the whip can be canceled by adding an equivalent inductive reactance in the form of a loading coil in series with the antenna.



Fig 5—Graph showing the approximate capacitance of short vertical antennas for various diameters and lengths. These values should be approximately halved for a center-loaded antenna.

starting point for the final experimental adjustment that must always be made.

LOADING COIL DESIGN

To minimize loading coil loss, the coil should have a high ratio of reactance-to-resistance (that is, a high unloaded Q). A 4-MHz loading coil wound with small wire on a small-diameter solid form of poor quality, and enclosed in a metal protector, may have a Q as low as 50, with a loss resistance of 50 Ω or more. High-Q coils require a large conductor, air-wound construction, large spacing between turns, and the best insulating material available. A diameter not less than half the length of the coil (not always mechanically feasible) and a minimum of metal in the field of the coil are also necessities for optimum efficiency. Such a coil for 4 MHz may show a Q of 300 or more, with a resistance of 12 Ω or less.

The coil could then be placed in series with the feed line at the base of the antenna to tune out the unwanted capacitive reactance, as shown in Fig 4. Such a method is often referred to as *base-loading*, and many practical mobile antenna systems have been built using this scheme.

Over the years, the question has come up as to whether or not more efficient designs are possible compared with simple base loading. While many ideas have been tried with varying degrees of success, only a few have been generally accepted and incorporated into actual systems. These are center loading, continuous loading, and combinations of the latter with more conventional antennas.

Base Loading and Center Loading

If a whip antenna is short compared to a wavelength *and the current is uniform along the length ℓ*, the electric field strength E, at a distance d, away from the antenna is approximately:

$$E = \frac{120 \pi I \ell}{d \lambda} \qquad \text{(Eq 3)}$$

where

I is the antenna current in amperes

λ is the wavelength in the same units as D and ℓ.

A uniform current flowing along the length of the whip is an idealized situation, however, since the current is greatest at the base of the antenna and goes to a minimum at the top. In practice, the field strength will be less than that given by the above equation, because it is a function of the current distribution on the whip.

The reason that the current is not uniform on a whip antenna can be seen from the circuit approximation shown in **Fig 6**. A whip antenna over a ground plane is similar in many respects to a tapered coaxial cable where the center conductor remains the same diameter along its length, but with an increasing diameter outer conductor. The inductance per unit length of such a cable would increase along the line, while the capacitance per unit length would decrease. In Fig 6 the antenna is represented by a series of LC circuits in which C1 is greater than C2, which is greater than C3, and so on. L1 is less than L2, which is less than succeeding inductances. The net result is that most of the antenna current returns to ground near the base of the antenna, and very little near the top.



Fig 6—A circuit approximation of a simple whip over a perfectly conducting ground plane. The shunt capacitance per unit length gets smaller as the height increases, and the series inductance per unit length gets larger. Consequently, most of the antenna current returns to the ground plane near the base of the antenna, giving the current distribution shown at the right.



Fig 7—Improved current distribution resulting from center loading.

Two things can be done to improve this distribution and make the current more uniform. One would be to increase the capacitance of the top of the antenna to ground through the use of top loading or a capacitance hat, as discussed in Chapter 6. Unfortunately, the wind resistance of the hat makes it somewhat unwieldy for mobile use. The other method is to place the loading coil farther up the whip, as shown in **Fig 7**, rather than at the base. If the coil is resonant (or nearly so) with the

Table 1

Approximate Values for 8-ft Mobile Whip

f(MHz)	Loading L µH	R_C(Q50) Ω	R_C(Q300) Ω	R_R Ω	Feed R* Ω	Matching L µH
Base Loading						
1.8	345	77	13	0.1	23	3
3.8	77	37	6.1	0.35	16	1.2
7.2	20	18	3	1.35	15	0.6
10.1	9.5	12	2	2.8	12	0.4
14.2	4.5	7.7	1.3	5.7	12	0.28
18.1	3.0	5.0	1.0	10.0	14	0.28
21.25	1.25	3.4	0.5	14.8	16	0.28
24.9	0.9	2.6	—	20.0	22	0.25
29.0	—	—	—	—	36	0.23
Center Loading						
1.8	700	158	23	0.2	34	3.7
3.8	150	72	12	0.8	22	1.4
7.2	40	36	6	3.0	19	0.7
10.1	20	22	4.2	5.8	18	0.5
14.2	8.6	15	2.5	11.0	19	0.35
18.1	4.4	9.2	1.5	19.0	22	0.31
21.25	2.5	6.6	1.1	27.0	29	0.29

R_C = loading coil resistance; R_R = radiation resistance.
*Assuming loading coil Q = 300, and including estimated ground-loss resistance.

Table 2

Suggested Loading Coil Dimensions

Req'd L(µH)	Turns	Wire Size	Dia. Inches	Length Inches
700	190	22	3	10
345	135	18	3	10
150	100	16	$2\frac{1}{2}$	10
77	75	14	$2\frac{1}{2}$	10
77	29	12	5	$4\frac{1}{4}$
40	28	16	$2\frac{1}{2}$	2
40	34	12	$2\frac{1}{2}$	$4\frac{1}{4}$
20	17	16	$2\frac{1}{2}$	$1\frac{1}{4}$
20	22	12	$2\frac{1}{2}$	$2\frac{3}{4}$
8.6	16	14	2	2
8.6	15	12	$2\frac{1}{2}$	3
4.5	10	14	2	$1\frac{1}{4}$
4.5	12	12	$2\frac{1}{2}$	4
2.5	8	12	2	2
2.5	8	6	$2\frac{3}{8}$	$4\frac{1}{2}$
1.25	6	12	$1\frac{3}{4}$	2
1.25	6	6	$2\frac{3}{8}$	$4\frac{1}{2}$

capacitance to ground of the section above the coil, the current distribution is improved as also shown in Fig 7. The result with both top loading and center loading is that the radiation resistance is increased, offsetting the effect of losses and making matching easier.

Table 1 shows the approximate loading coil inductance for the various amateur bands. Also shown in the table are approximate values of radiation resistance to be expected with an 8-foot whip, and the resistances of loading coils—one group having a Q of 50, the other a Q of 300. A comparison of radiation and coil resistances will show the importance of reducing the coil resistance to a minimum, especially on the three lower frequency bands. **Table 2** shows suggested loading-coil dimensions for the inductance values given in Table 1.

OPTIMUM DESIGN OF SHORT COIL-LOADED HF MOBILE ANTENNAS

Optimum design of short HF mobile antennas results from a careful balance of the appropriate loading coil Q-factor, loading coil position in the antenna, ground loss resistance, and the length-to-diameter ratio of the antenna. The optimum balance of these parameters can be realized only through a thorough understanding of how they interact. This section presents a mathematical approach to designing mobile antennas for maximum radiation efficiency. Bruce Brown, W6TWW, in *The ARRL Antenna Compendium Volume 1*, first presented this approach. (See the Bibliography at the end of this chapter.)

The optimum location for a loading coil in an antenna can be found experimentally, but it requires many hours of designing and constructing models and making measurements to ensure the validity of the design. A faster and more reliable way of determining optimum coil location is through the use of a personal computer. This approach allows the variation of any single variable, while observing the cumulative effects on the system. When plotted graphically, the data reveals that the placement of the loading coil is critical if maximum radiation efficiency

Table 3
Variables used in Eqs 4 through 20

A = area in degree-amperes
a = antenna radius in English or metric units
dB = signal loss in decibels
E = efficiency in percent
f (MHz) = frequency in megahertz
H = height in English or metric units
h = height in electrical degrees
h_1 = height of base section in electrical degrees
h_2 = height of top section in electrical degrees
I = I_{base} = 1 ampere base current
k = 0.0128
k_m = mean characteristic impedance
k_{m1} = mean characteristic impedance of base section
k_{m2} =mean characteristic impedance of top section
L = length or height of the antenna in feet
P_I = power fed to the antenna
P_R = power radiated
Q = coil figure of merit
R_C = coil loss resistance in Ω
R_G = ground loss resistance in Ω
R_R = radiation resistance in Ω
X_L = loading-coil inductive reactance



Fig 8—Relative current distribution on a vertical antenna of height h = 90 electrical degrees.

is to be realized. (See the program *MOBILE.EXE*, which is included on the CD-ROM in the back of this book.)

Radiation Resistance

The determination of radiation efficiency requires the knowledge of resistive power losses and radiation losses. Radiation loss is expressed in terms of radiation resistance. Radiation resistance is defined as the resistance that would dissipate the same amount of power that is radiated by the antenna. The variables used in the equations that follow are defined once in the text, and are summarized in **Table 3**. Radiation resistance of vertical antennas shorter than 45 electrical degrees ($^1/_8$ wavelength) is approximately:

$$R_R = \frac{h^2}{312} \qquad \text{(Eq 4)}$$

where

R_R = radiation resistance in Ω
h = antenna length in electrical degrees.

Antenna height in electrical degrees is expressed by:

$$h = \frac{\ell}{984} \times f\left(\text{MHz}\right) \times 360 \qquad \text{(Eq 5)}$$

where

ℓ = antenna length in feet
f (MHz) = operating frequency in megahertz.

End effect is purposely omitted to ensure that an antenna is electrically long. This is so that resonance at the design frequency can be obtained easily by removing a turn or two from the loading coil.

Eq 4 is valid only for antennas having a sinusoidal current distribution and no reactive loading. However, it can be used as a starting point for deriving an equation that is useful for shortened antennas with other than sinusoidal current distributions.

Refer to **Fig 8**. The current distribution on an antenna 90º long electrically ($^1/_4$ wavelength) varies with the cosine of the length in electrical degrees. The current distribution of the top 30º of the antenna is essentially linear. It is this linearity that allows for derivation of a simpler, more useful equation for radiation resistance.

The radiation resistance of an electrically short base-loaded vertical antenna can be conveniently defined in terms of a geometric figure, a triangle, as shown in **Fig 9**. The radiation resistance is given by:

$$R_R = KA^2 \qquad \text{(Eq 6)}$$

where

K is a constant (to be derived shortly)
A = area of the triangular current distribution in degree-amperes.

Degree-ampere area is expressed by

$$A = \frac{1}{2} h \times I_{base} \qquad \text{(Eq 7)}$$



Fig 9—Relative current distribution on a base-loaded vertical antenna of height H = 30 electrical degrees (linearized). The base loading coil is not shown here.



Fig 10—Relative current distribution on a center-loaded antenna with base and top sections each equal to 15 electrical degrees in length. The cross-hatched area shows the current distribution that would exist in the top 15° of a 90°-high vertical fed with 1 ampere at the base.

By combining Eqs 4 and 6 and solving for K, we get

$$K = \frac{h^2}{312 \times A^2} \qquad \text{(Eq 8)}$$

By substituting the values from Fig 9 into Eq 8 we get

$$K = \frac{30^2}{312 \times \left(0.5 \times 30 \times 1\right)^2} = 0.0128$$

and by substituting the derived value of K into Eq 6 we get

$$R_R = 0.0128 \times A^2 \qquad \text{(Eq 9)}$$

Eq 9 is useful for determining the radiation resistance of coil-loaded vertical antennas less than 30° in length. The derived constant differs slightly from that presented by Laport (see Bibliography), as he used a different equation for radiation resistance Eq 4.

When the loading coil is moved up an antenna (away from the feed point), the current distribution is modified as shown in **Fig 10**. The current varies with the cosine of the height in electrical degrees at any point in the base section. Therefore, the current flowing into the bottom of the loading coil is less than the current flowing at the base of the antenna.

But what about the current in the top section of the antenna? The loading coil acts as the lumped constant that it is, and disregarding losses and coil radiation, maintains the same current flow throughout. As a result, the current at the top of a high-Q coil is essentially the same as that at the bottom of the coil. This is easily verified by installing RF ammeters immediately above and below the loading coil in a test antenna. Thus, the coil "forces" much more current into the top section than would flow in the equivalent section of a full 90° long antenna. This occurs as a result of the extremely high voltage that appears at the top of the loading coil. This higher current flow results in more radiation than would occur from the equivalent section of a quarter-wave antenna. (This is true for conventional coils. However, radiation from long thin coils allows coil current to decrease, as in helically wound antennas.)

The cross-hatched area in Fig 10 shows the current that would flow in the equivalent part of a 90° high antenna, and reveals that the degree-ampere area of the whip section of the short antenna is greatly increased as a result of the modified current distribution. The current flow in the top section decreases almost linearly to zero at the top. This can be seen in Fig 10.

The degree-ampere area of Fig 10 is the sum of the triangular area represented by the current distribution in the top section, and the nearly trapezoidal current distribution in the base section. Radiation from the coil is not included in the degree-ampere area because it is small and difficult to define. Any radiation from the coil can be considered a bonus.

The degree-ampere area is expressed by:

$$A = \frac{1}{2}\left[h_1\left(1+\cos h_1\right) + h_2\left(\cos h_1\right)\right] \qquad \text{(Eq 10)}$$

where

h_1 = electrical length in degrees of the base section

h_2 = electrical height in degrees of the top section.

The degree-ampere area (calculated by substituting Eq 10 into Eq 9) can be used to determine the radiation resistance when the loading coil is at any position other than the base of the antenna. Radiation resistance has been calculated with these equations and plotted against loading coil position at three different frequencies for 8- and 11-foot antennas, **Fig 11**. Eight feet is a typical length for commercial antennas, and 11-foot antennas are about the maximum practical length that can be installed on a vehicle.

In Fig 11, the curves reveal that the radiation resistance rises almost linearly as the loading coil is moved up the antenna. They also show that the radiation resistance rises rapidly as the frequency is increased. If the analysis were stopped at this point, one might conclude that the loading coil should be placed at the top of the antenna. This is not so, and will become apparent shortly.



Fig 11—Radiation resistance plotted as a function of loading coil position.

Required Loading Inductance

Calculation of the loading coil inductance needed to resonate a short antenna can be done easily and accurately by using the antenna transmission-line analog described by Boyer in *Ham Radio*. For a base-loaded antenna, Fig 9, the loading coil reactance required to resonate the antenna is given by

$$X_L = -j\,K_m \cot h \qquad \text{(Eq 11)}$$

where

X_L = inductive reactance required

K_m = mean characteristic impedance (defined in Eq 12).

The $-j$ term indicates that the antenna presents capacitive reactance at the feed point. A loading coil must cancel this reactance.

The mean characteristic impedance of an antenna is expressed by

$$K_m = 60\left[\left(\ln\frac{2H}{a}\right) - 1\right] \qquad \text{(Eq 12)}$$

where

H = physical antenna height (excluding the length of the loading coil)

a = radius of the antenna in the same units as H.

From Eq 12 you can see that decreasing the height-to-diameter ratio of an antenna by increasing the radius results in a decrease in K_m. With reference to Eq 11, a decrease in K_m decreases the inductive reactance required to resonate an antenna. As will be shown later, this will increase radiation efficiency. In mobile applications, we quickly run into wind-loading problems if we attempt to use an antenna that is physically large in diameter.

If the loading coil is moved away from the base of the antenna, the antenna is divided into a base and top section, as depicted in Fig 10. The loading coil reactance required to resonate the antenna when the coil is away from the base is given by

$$X_L = j\,K_{m2}\,(\cot h_2) - j\,K_{m1}\,(\tan h_1) \qquad \text{(Eq 13)}$$

In mobile-antenna design and construction, the top section is usually a whip with a much smaller diameter than the base section. Because of this, it is necessary to compute separate values of K_m for the top and base sections. K_{m1} and K_{m2} are the mean characteristic impedances of the base and top sections, respectively.

Loading coil reactance curves for the 3.8-MHz antennas of Fig 11 have been calculated and plotted in **Fig 12**. These curves show the influence of the loading coil position on the reactance required for resonance. The curves in Fig 12 show that the required reactance decreases with longer antennas. The curves also reveal that the required loading coil reactance grows at an increasingly rapid rate after the coil passes the center of the antenna. Because the highest possible loading coil Q



Fig 12—Loading coil reactance required for resonance, plotted as a function of coil height above the antenna base. The resonant frequency is 3.9 MHz.

factor is needed, and because optimum Q is attained when the loading coil diameter is twice the loading coil length, the coil would grow like a smoke ring above the center of the antenna, and would quickly reach an impractical size. It is for this reason that the highest loading coil position is limited to one foot from the top of the antenna in all computations.

Loading Coil Resistance

Loading coil resistance constitutes one of the losses that consumes power that could otherwise be radiated by the antenna. Heat loss in the loading coil is not of any benefit, so it should be minimized by using the highest possible loading coil Q. Loading coil loss resistance is a function of the coil Q and is given by

$$R_C = \frac{X_L}{Q} \qquad \text{(Eq 14)}$$

where

R_C = loading coil loss resistance in Ω
X_L = loading coil reactance
Q = coil figure of merit

Inspection of Eq 14 reveals that, for a given value of inductive reactance, loss resistance will be lower for higher Q coils. Measurements made with a Q meter show that typical, commercially manufactured coil stock produces a Q between 150 and 160 in the 3.8-MHz band.

Higher Q values can be obtained by using larger diameter coils having a diameter-to-length ratio of two, by using larger diameter wire, by using more spacing between turns, and by using low-loss polystyrene supporting and enclosure materials. In theory, loading coil turns should not be shorted for tuning purposes because shorted turns somewhat degrade Q. Pruning to resonance should be done by removing turns from the coil.

In fairness, it should be pointed out that many practical mobile antennas use large-diameter loading coils with shorted turns to achieve resonance. The popular “Texas Bug Catcher” coils come to mind here. Despite general proscriptions against shorting turns, these systems are often more efficient than antennas with small, relatively low-Q, fixed loading coils.

Radiation Efficiency

The ratio of power radiated to power fed to an antenna determines the radiation efficiency. It is given by:

$$E = \frac{P_R}{P_I} \times 100\% \qquad \text{(Eq 15)}$$

where

E = radiation efficiency in percent
P_R = power radiated
P_I = power fed to the antenna at the feed point.

In a short, coil-loaded mobile antenna, a large portion of the power fed to the antenna is dissipated in ground and coil resistances. A relatively insignificant amount of power is also dissipated in the antenna conductor resistance and in the leakage resistance of the base insulator. Because these last two losses are both very small and difficult to estimate, they are here neglected in calculating radiation efficiency.

Another loss worth noting is matching network loss. Because we are concerned only with power fed to the antenna in the determination of radiation efficiency, matching network loss is not considered in any of the equations. Suffice it to say that matching networks should be designed for minimum loss in order to maximize the transmitter power available at the antenna.

The radiation efficiency equation may be rewritten and expanded as follows:

$$E = \frac{I^2\, R_R \times 100}{I^2\, R_R + I^2\, R_G + \left(I \cos h_1\right)^2\, R_C} \qquad \text{(Eq 16)}$$

where

I = antenna base current in amperes
R_G = ground loss resistance in Ω
R_C = coil loss resistance in Ω.

Each term of Eq 16 represents the power dissipated in its associated resistance. All the current terms cancel, simplifying this equation to

$$E = \frac{R_R \times 100}{R_R + R_G + R_C \left(\cos^2 h_1\right)} \qquad \text{(Eq 17)}$$

For base-loaded antennas the term $\cos^2 h_1$ drops to unity and may be omitted.

Ground Loss

Eq 14 shows that the total resistive losses in the antenna system are:

$$R_T = R_R + R_G + R_c (\cos^2 h_1) \qquad \text{(Eq 18)}$$

where R_T is the total resistive loss. Ground loss resistance can be determined by rearranging Eq 18 as follows:

$$R_G = R_T - R_R - R_C \cos^2 h_1 \qquad \text{(Eq 19)}$$

R_T may be measured in a test antenna installation on a vehicle using an R-X noise bridge or an SWR analyzer. You can then calculate R_R and R_C.

Ground loss is a function of vehicle size, placement of the antenna on the vehicle, and conductivity of the ground over which the vehicle is traveling. Only the first two variables can be feasibly controlled. Larger vehicles provide better ground planes than smaller ones. The vehicle ground plane is only partial, so the result is considerable RF current flow (and ground loss) in the ground around and under the vehicle.

By raising the antenna base as high as possible on the vehicle, ground losses are decreased. This results from a decrease in antenna capacitance to ground, which increases the capacitive reactance to ground. This, in turn, reduces ground currents and ground losses.

This effect has been verified by installing the same antenna at three different locations on two different vehicles, and by determining the ground loss from Eq 19. In the first test, the antenna was mounted 6 inches below the top of a large station wagon, just behind the left rear window. This placed the antenna base 4 feet 2 inches above the ground, and resulted in a measured ground loss resistance of 2.5 Ω. The second test used the same antenna mounted on the left rear fender of a mid-sized sedan, just to the left of the trunk lid. In this test, the measured ground loss resistance was 4 Ω. The third test used the same mid-sized car, but the antenna was mounted on the rear bumper. In this last test, the measured ground loss resistance was 6 Ω.

The same antenna therefore sees three different ground loss resistances as a direct result of the antenna mounting location and size of the vehicle. It is important to note that the measured ground loss increases as the antenna base nears the ground. The importance of minimizing ground losses in mobile antenna installations cannot be overemphasized.

Efficiency Curves

With the equations defined previously, a computer



Fig 13—Radiation efficiency of 8-foot antennas at 3.9 MHz.



Fig 14—Radiation efficiency of 11-foot antennas at 3.9 MHz.



Fig 15—Radiation efficiency of 8-foot antennas at 7.225 MHz.



Fig 16—Radiation efficiency of 11-foot antennas at 7.225 MHz.

was used to calculate the radiation efficiency curves depicted in **Figs 13** through **16**. These curves were calculated for 3.8- and 7-MHz antennas of 8- and 11-foot lengths. Several values of loading coil Q were used, for both 2 and 10 Ω of ground loss resistance. For the calculations, the base section is $^1/_2$-inch diameter electrical EMT, which has an outside diameter of $^{11}/_{16}$ inch. The top section is fiberglass bicycle-whip material covered with Belden braid. These are readily available materials, which can be used by the average amateur to construct an inexpensive but rugged antenna.

Upon inspection, these radiation-efficiency curves reveal some significant information:

1) Higher coil Q produces higher radiation efficiencies,
2) longer antennas produce higher radiation efficiencies,
3) higher frequencies produce higher radiation efficiencies,
4) lower ground loss resistances produce higher radiation efficiencies,
5) higher ground loss resistances force the loading coil above the antenna center to reach a crest in the radiation-efficiency curve, and
6) higher coil Q sharpens the radiation-efficiency curves, resulting in the coil position being more critical for optimum radiation efficiency.

Note that the radiation efficiency curves reach a peak and then begin to decline as the loading coil is raised farther up the antenna. This is because of the rapid increase in loading coil reactance required above the antenna center. Refer to Fig 12. The rapid increase in coil size required for resonance results in the coil loss resistance increasing much more rapidly than the radiation resistance. This results in decreased radiation efficiency, as shown in Fig 11.

A slight reverse curvature exists in the curves between the base-loaded position and the one-foot coil-height position. This is caused by a shift in the curve resulting from insertion of a base section of larger diameter than the whip when the coil is above the base.

The curves in Figs 13 through 16 were calculated with constant (but not equal) diameter base and whip sections. Because of wind loading, it is not desirable to increase the diameter of the whip section. However, the base-section diameter can be increased within reason to further improve radiation efficiency. **Fig 17** was calculated for base-section diameters ranging from $^{11}/_{16}$ inch to 3 inches. The curves reveal that a small increase in radiation efficiency results from larger diameter base sections.

The curves in Figs 13 through 16 show that radiation efficiencies can be quite low in the 3.8-MHz band compared to the 7-MHz band. They are lower yet in the 1.8-MHz band. To gain some perspective on what these low efficiencies mean in terms of signal strength, **Fig 18** was calculated using the following equation:

$$\text{dB} = \log \frac{100}{\text{E}} \qquad \text{(Eq 20)}$$



Fig 17—Radiation efficiency plotted as a function of base section diameter. Frequency = 3.9 MHz, ground loss resistance = 2 Ω, and whip section = $^1/_4$-inch diameter.



Fig 18—Mobile antenna signal loss as a function of radiation efficiency, compared to a quarter-wave vertical antenna over perfect ground.

where

dB = signal loss in decibels
E = efficiency in percent.

The curve in Fig 18 reveals that an antenna having 25% efficiency has a signal loss of 6 dB (approximately one S unit) below a quarter-wave vertical antenna over perfect ground. An antenna efficiency in the neighborhood of 6% will produce a signal strength on the order of two S units or about 12 dB below the same quarter-wave reference vertical. By careful optimization of mobile-antenna design, signal strengths from mobiles can be made fairly competitive with those from fixed stations using comparable power. And don’t forget: Moving your car near saltwater, with its high conductivity, can result in surprisingly strong signals from a mobile station!

Impedance Matching

The input impedance of short, high-Q coil-loaded antennas is quite low. For example, an 8-foot antenna optimized for 3.9 MHz with an unloaded coil Q of 300 and a ground-loss resistance of 2 Ω has a base input impedance of about 13 Ω. This low impedance value causes a standing wave ratio of 4:1 on a 50-Ω coaxial line at resonance. This high SWR is not compatible with the requirements of solid-state transmitters. Also, the bandwidth of shortened vertical antennas is very narrow. This severely limits the capability to maintain transmitter loading over even a small frequency range.

Impedance matching can be accomplished by means of L networks or impedance-matching transformers, but the narrow bandwidth limitation remains. A more elegant solution to the impedance matching and narrow bandwidth problem is to install an automatic tuner at the antenna base. Such a device matches the antenna and coaxial line automatically, and permits operation over a wide frequency range.

The tools are now available to tailor a mobile antenna design to produce maximum radiation efficiency. Mathematical modeling with a personal computer reveals that loading coil Q factor and ground loss resistance greatly influence the optimum loading coil position in a short vertical antenna. It also shows that longer antennas, higher coil Q, and higher operating frequencies produce higher radiation efficiencies.

End effect has not been included in any of the equations to assure that the loading coil will be slightly larger than necessary. Pruning the antenna to resonance should be done by removing coil turns, rather than by shorting turns or shortening the whip section excessively. Shortening the whip reduces radiation efficiency, by both shortening the antenna and moving the optimum coil position. Shorting turns in the loading coil degrades the Q of the coil.

Shortened Dipoles

Mathematical modeling techniques can be applied to shortened dipoles by using zero ground loss resistance and by doubling the computed values of radiation resistance and feed-point impedance. Radiation efficiency, however, does not double. Rather, it remains unchanged, because a second loading coil is required in the other leg of the dipole. The addition of the second coil offsets the gain in efficiency that occurs when the feed-point impedance and radiation resistance are doubled. There is a gain in radiation efficiency over a vertical antenna worked against ground, though, because the dipole configuration allows ground loss resistance to be eliminated from the calculations.

CONTINUOUSLY LOADED ANTENNAS

The design of high-Q air core inductors for RF work is complicated by the number of parameters that must be optimized simultaneously. One of these factors affecting coil Q adversely is radiation from a discrete loading coil. Therefore, the possibility of cutting down other losses while incorporating the coil radiation into that from the rest of the antenna system is an attractive one.

The general approach has been to use a coil made from heavy wire (#14 or larger), with length-to-diameter ratios as high as 21. British experimenters have reported good results with 8-foot overall lengths on the 1.8- and 3.5-MHz bands. The idea of making the entire antenna out of one section of coil has also been tried with some success. This technique is referred to as linear loading. Further information on linear-loaded antennas can be found in Chapter 6.

While going to extremes trying to find a perfect loading arrangement may not improve antenna performance very much, a poor system with lossy coils and high-resistance connections must be avoided if a reasonable signal is to be radiated.

MATCHING TO THE TRANSMITTER

Most modern transmitters require a 50-Ω output load, and because the feed-point impedance of a mobile whip is quite low, a matching network is usually necessary. Although calculations are helpful in the initial design, considerable experimenting is often necessary in final tune-up. This is particularly true for the lower bands, where the antenna is electrically short compared with a quarter-wave whip. The reason is that the loading coil is required to tune out a very large capacitive reactance, and even small changes in component values result in large reactance variations. Since the feed-point resistance is low to begin with, the problem is even more aggravated.

You can transform the low resistance of the whip to a value suitable for a 50-Ω system with an RF transformer or with a shunt-feed arrangement, such as an L network. The latter may only require a shunt coil or shunt capacitor at the base of the whip, since the net series capacitive or inductive reactance of the antenna and its loading coil may be used as part of the network. The following example illustrates the calculations involved.

Assume that a center-loaded whip antenna, 8.5 feet in overall length, is to be used on 7.2 MHz. From Table 1, earlier in this chapter, we see that the feed-point resistance of the antenna will be approximately 19 Ω, and from Fig 5 that the capacitance of the whip, as seen at its base, is approximately 24 pF. Since the antenna is to be center loaded, the capacitance value of the section above the coil will be cut approximately in half, to 12 pF. From this, it may be calculated that a center-loading inductor of 40.7 µH is required to resonate the antenna, that is, to cancel out the capacitive reactance. (This figure agrees with the approximate value of 40 µH shown in Table 1. The resulting feed-point impedance would then be 19 + *j* 0 Ω—a good match, *if* one happens to have a supply of 19-Ω coax.)

Solution: The antenna can be matched to a 52-Ω line such as RG-8 by tuning it either above or below reso-



Fig 19—Admittance diagram of the RLC circuit consisting of the whip capacitance, radiation resistance and loading coil discussed in text. The horizontal axis represents conductance, and the vertical axis susceptance. The point P_0 is the input admittance with no whip loading inductance. Points P1 and P2 are described in the text. The conductance equals the reciprocal of the resistance, if no reactive components are present. For a series RX circuit, the conductance is given by

$$G = \frac{R}{R^2 + X^2}$$

and the susceptance is given by

$$B = \frac{-X}{R^2 + X^2}$$

Consequently, a parallel equivalent GB circuit of the series RX one can be found which makes computations easier. This is because conductances and susceptances add in parallel the same way resistances and reactances add in series.

nance and then canceling out the undesired component with an appropriate shunt element, capacitive or inductive. The way in which the impedance is transformed up can be seen by plotting the admittance of the series RLC circuit made up of the loading coil, antenna capacitance, and feed-point resistance. Such a plot is shown in **Fig 19** for a constant feed-point resistance of 19 Ω. There are two points of interest, P1 and P2, where the input conductance is 19.2 millisiemens, corresponding to 52 Ω. The undesired susceptance is shown as $1/X_P$ and $-1/X_P$, which must be canceled with a shunt element of the opposite sign, but with the same magnitude. The value of the canceling shunt reactance, X_P, may be found from the formula:

$$X_p = \frac{R_f\ Z_0}{\sqrt{R_f\left(Z_0 - R_f\right)}} \qquad \text{(Eq 21)}$$

where X_p is the reactance in Ω, R_f is the feed-point resistance, and Z_0 is the feed-line impedance. For Z_0 = 52 Ω and R_f = 19 Ω, $X_p = \pm 39.5$ Ω. A coil or good quality mica capacitor may be used as the shunt element. With the tune-up procedure described later, the value is not critical, and a fixed-value component may be used.

To arrive at point P1, the value of the center loading-coil inductance would be less than that required for resonance. The feed-point impedance would then appear capacitive, and an inductive shunt matching element would then be required. To arrive at point P2, the center loading coil should be more inductive than required for resonance, and the shunt element would need to be capacitive.

The value of the center loading coil required for the shunt-matched and resonated condition may be determined from the equation:

$$L = \frac{10^6}{4\pi^2 f^2 C} \pm \frac{X_S}{2\pi f} \qquad \text{(Eq 22)}$$

where addition is performed if a capacitive shunt is to be used, or subtraction performed if the shunt is inductive, and where L is in µH, f is the frequency in MHz, C is the capacitance of the antenna section being matched in pF, and

$$X_S = \sqrt{R_f\left(Z_0 - R_f\right)} \qquad \text{(Eq 23)}$$



Fig 20—At A, a whip antenna that is resonated with a center loading coil. At B and C, the value of the loading coil has been altered slightly to make the feed-point impedance appear reactive, and a matching component is added in shunt to cancel the reactance. This provides an impedance transformation to match the Z_0 of the feed line. An equally acceptable procedure, rather than altering the loading coil inductance, is to adjust the length of the top section above the loading coil for the best match, as described in the tune-up section of the text.

For the example given, where Z_0 = 52 Ω, R_f = 19 Ω, f = 7.2 MHz, and C = 12 pF, X_S is found to be 25.0 Ω. The required antenna loading inductance is either 40.2 µH or 41.3 µH, depending on the type of shunt. Various matching possibilities for this example are shown in **Fig 20**. At A, the antenna is shown as tuned to resonance with L_L, a 40.7 µH coil, but with no provisions included for matching the resulting 19-Ω impedance to the 52-Ω line. At B, L_L has been reduced to 40.2 µH to make the antenna appear net capacitive, and L_M, having a reactance of 39.5 Ω, is added in shunt to cancel the capacitive reactance and transform the feed-point impedance to 50 Ω. The arrangement at C is similar to that at B except that L_L has been increased to 41.3 µH, and C_M (a shunt capacitor having a negative reactance of 39.5 Ω) is added, which also results in a 52-Ω nonreactive termination for the feed line.

The values determined for the loading coil in the above example point out an important consideration concerning the matching of short antennas—relatively small changes in values of the loading components will have a greatly magnified effect on the matching requirements. A change of less than 3% in the loading coil inductance value necessitates a completely different matching network! Likewise, calculations show that a 3% change in antenna capacitance will give similar results, and the value of the precautions mentioned earlier becomes clear. The sensitivity of the circuit with regard to frequency variations is also quite critical, and an excursion around practically the entire circle in Fig 19 may represent only 600 kHz, centered around 7.2 MHz, for the above example. This is why tuning up a mobile antenna can be very frustrating unless a systematic procedure is followed.

Tune-Up

Assume that inductive shunt matching is to be used with the antenna in the previous example, Fig 20B, where 39.5 Ω is needed for L_M. This means that at 7.2 MHz, a coil of 0.87 µH will be needed across the whip feed-point terminal to ground. With a 40-µH loading coil in place, the adjustable whip section above the loading coil should be set for minimum height. Signals in the receiver will sound weak and the whip should be lengthened a bit at a time until signals start to peak. Turn the transmitter on and check the SWR at a few frequencies to find where a minimum occurs. If it is below the desired frequency, shorten the whip slightly and check again. It should be moved approximately $^1/_4$ inch at a time until the SWR is minimum at the center of the desired range. If the frequency where the minimum SWR occurs is above the desired frequency, repeat the procedure above, but lengthen the whip only slightly.

If a shunt capacitance is to be used, as in Fig 20C, a value of 560 pF would correspond to the required $-39.5\ \Omega$ of reactance at 7.2 MHz. With a capacitive shunt, start with the whip in its longest position and shorten it until signals peak up.


Capacitance Hat
No. 10 or Larger Wire
Loading Coil
Spring
Mount

Fig 21—A capacitance hat can be used to improve the performance of base- or center-loaded whips. A solid metal disc can be used in place of the skeleton disc shown here.

TOP-LOADING CAPACITANCE

Because the loss resistance varies with the inductance of the loading coil, the resistance can be reduced by removing turns from the coil. This must be compensated by adding capacitance to the portion of the mobile antenna that is *above* the loading coil (**Fig 21**). *Capacitance hats*, as they are called, can consist of a single stiff wire, two wires or more, or a disc made up of several wires like the spokes of a wheel. A solid metal disc could also be used, but is less practical for mobile work. The larger the capacitance hat (physically), the greater is the capacitance. The greater the capacitance, the less is the inductance required for resonance at a given frequency.

Capacitance-hat loading is applicable in either base-loaded or center-loaded systems. Since more inductance is required for center-loaded whips to make them resonant at a given frequency, capacitance hats are particularly useful in improving their efficiency.

TAPPED-COIL MATCHING NETWORK

Some of the drawbacks of the L-network can be eliminated by the use of the tapped-coil arrangement shown in **Fig 22**. Tune-up still remains critical, however, although somewhat more straightforward than for an L-network.


Field-Strength
Meter, Several
Feet Away from
Mobile Ant
Adjustable
Top Section
Set Screw
Loading
Coil
Mobile Trans
L1
Matching
Coil
50 or 75 Ω
Coax Line
L2
1: 1 SWR
SWR
Bridge
Car-Body Ground
Shunt Feed

Fig 22—A mobile antenna using shunt-feed matching. Overall antenna resonance is determined by the combination of L1 and L2. Antenna resonance is set by pruning the turns of L1, or adjusting the top section of the whip, while observing the field-strength meter or SWR indicator. Then adjust the tap on L2 for the lowest SWR.

Coil L2 can be inside the car body, at the base of the antenna, or at the base of the whip. As L2 helps determine the resonance of the antenna, L1 should be tuned to resonance in the desired part of the band with L2 in the circuit. The top section of the whip can be telescoped until a field-strength maximum is found. The tap on L2 is then adjusted for the lowest reflected power. Repeat these two adjustments until no further increase in field strength can be obtained; this point should coincide with the lowest SWR. The number of turns needed for L2 will have to be determined experimentally.

THE "SCREWDRIVER" MOBILE ANTENNA

Imagine QSYing from the bottom of 80 meters to the top of 10 meters, right from the driver's seat. With this antenna you will enjoy a very high Q antenna that has no taps or external adjustments, and that exhibits an SWR under 1.5:1 on all bands. Max Bloodworth, KO4TV, described this antenna in *The ARRL Antenna Compendium, Vol 7*.

The Screwdriver type of antenna was the brainchild of Don Johnson, W6AAQ, who developed it after many years of experimenting with mobile antennas. **Fig 23** is a photo of the completed antenna mounted on KO4TV's truck.



Fig 23—The completed Screwdriver antenna mounted on KO4TV's truck rear bumper. (*Photo courtesy of Gary Pearce, KN4AQ.*)

THE LOADING COIL

The general concept for the Screwdriver is that of a center-loaded antenna with an adjustable loading coil. This is an old idea; however, most previous multi-band antennas required multiple coil taps and an adjustable top whip section, as well as an impedance-matching unit at the base.

The problem of tapping a coil is well known. If you leave one end of the coil open, you have a miniature Tesla Coil, which can cause corona discharge and arcing. If you short the turns, the Q of the loading coil usually drops drastically. The Screwdriver is remarkable in that it does not have any coil taps and yet it can cover a wide range of frequencies with very high Q.

The secret is in the manner of adjusting the coil. It simply slides up or down into a metal tube (the base section), and makes contact with the top of the tube by means of "finger stock," which is made of spring-like Beryllium Copper. The coil is pushed up or down by an ordinary cordless screwdriver; hence the name, Screwdriver. This turns a section of threaded rod and moves the coil form up or down. The section of coil above the finger stock is the active loading coil, and the part of the coil just below the finger stock simply "disappears" into the base tube and is totally out of the circuit. No taps, no loose ends—just a high-Q coil in the middle of two solid metal tubes. Although this antenna is available ready-made from several commercial sources, making one is well within the capabilities of any ham who is relatively handy with ordinary hand tools, and who has access to either a small lathe or a common $1^1/_4$-inch pipe die.



Fig 24—The base tube, with finger stock attached to the top.

CONSTRUCTING YOUR SCREWDRIVER ANTENNA

Construction begins by locating a 2-inch inside-diameter tube, about 3 to 3$^1/_2$ feet long. See **Fig 24**. The author had used such diverse materials as:

- Aluminum irrigation pipe
- Schedule-20 copper tubing
- A stainless-steel hydraulic cylinder
- A section of aluminum from a 6-meter beam that was damaged by a tornado
- And even a brass bedpost salvaged from the local garbage dump.

The brass bedpost looked especially good on his vehicle, which was Burgundy with gold trim. Whatever material you use for the bottom tube, you can either leave it unfinished or painted to your taste.



Fig 25—The coil form, with a threaded insert inserted into the bottom PVC cap inside the coil form.

The other essential item is a cordless screwdriver, minus its batteries and switch. You can often find one at yard sales or flea markets for a dollar or so, usually with dead batteries, since it is often just as cheap to buy another one new as it is to buy new batteries. So long as it will fit snugly inside the base tube, the brand name is immaterial. KO4TV has used Skil, Black & Decker, or even a Wal-Mart $8 special, all with equal success. The most difficult part of the job will be making the coil form and winding the loading coil, but with a little patience you should be able to do this satisfactorily.

Bear in mind that it is *not* a "Heathkit" type project, and it will require some innovation and ingenuity on your part. Next, obtain a 2-foot long piece of 1$^1/_4$-inch PVC pipe (*not* CPVC, which is vulnerable to ultraviolet rays from the sun). With either a lathe or a pipe die, thread approximately 20 inches from one end, at 10 to 12 threads per inch (See **Fig 25**). If you use a pipe die, it helps to loosen the cutters slightly, to make the grooves shallower.

When using a lathe, temporarily insert a piece of 1-inch water pipe inside the coil form to hold it steady in the lathe. The grooves should be just deep enough to comfortably hold the wire in place when it is wound. The choice of coil wire is up to you. The author has used #16 or #18 tinned copper, bare copper, or best yet, 17-gauge aluminum electric fence wire. This is available from any



Fig 26—Photo of the top of the loading coil. (*Photo courtesy of Gary Pearce, KN4AQ.*)

farm supply store at a very reasonable cost. It will take about 65 to 70 feet of wire.

Begin by drilling a $^{1}/_{16}$-inch hole through the PVC pipe at the bottom end of the threaded portion. Slip the end of the wire through this hole and tie a knot in it to serve as a stop. You could also insert a nut and bolt through a loop in the wire. Then carefully wind the coil to within an inch of the end of the threaded portion. The preferred method of winding is to put a stick or pipe through the holes of the wire reel and hold it between your feet and the floor, to provide the necessary tension to allow tight winding.

About an inch below the top of the coil, drill a $^{1}/_{16}$-inch hole and thread about 6 or 8 inches of wire through it. This will be the top connection from the coil to the whip. The bottom of the coil has no electrical connection.

The method of attaching the whip to the top of the coil form is up to you. I usually drill a $^{3}/_{8}$-inch hole through a $1^{1}/_{4}$-inch PVC pipe cap and place a $^{3}/_{8}$ × $1^{1}/_{2}$-inch SAE bolt through the hole, with a matching washer and nut on top. The bolt can be drilled and tapped for mounting the whip, which should be about 5 to 6 feet long. (It will be pruned for resonance later.) See **Fig 26**, a photo showing the top of the coil.

A more elegant way of connecting the whip is to obtain a swivel or quick-disconnect antenna fitting from your nearest truck stop. These are widely available for use with CB antennas and are threaded $^{3}/_{8}$-inch SAE. Do not attach the cap to the coil form until after the coil is inserted in the base tube.

Now that you have a coil form and a base tube, the next step will be to plug the bottom of the PVC coil form with a 1-inch PVC pipe cap, which fits snugly inside the coil form. Drill a hole directly in the center of this cap, and install a $^{1}/_{4}$-20 threaded insert, available at most hardware stores for about 25 or 30 cents. These are commonly used in wooden furniture to provide a thread for attaching bolts to wood. See **Fig 27**.

It is imperative that you install this insert squarely. The best method is to screw a short bolt into it and chuck the bolt in a drill press, placing the pipe cap


ANT0986
Whip
Coil Assembly
Pair of Stop Nuts
1/4 x 20 Threaded Rod
24" Long
Pair of Stop Nuts
Cordless Screwdriver
1-1/2" PVC Pipe
Over Handle
1-1/2" Pipe Cap
Base Mounting Bolt

Fig 27—The coil assembly and cordless screwdriver drive assembly.


ANT0987
Whip
Coil Assembly
Finger
Stock
Base Tube
Screwdriver
Assembly
Two
6-32 x 1/2"
Screws,
Countersunk
Two
6-32 x 1/2"
Screws,
Countersunk
Motor
Control
Wires
Bottom
Cap

Fig 28—The complete antenna assembly.

squarely on the drill press table. Carefully turn the drill chuck by hand until the insert is properly seated.

The Motor

Now prepare the cordless drill by removing the dead batteries and the switch. Install a pair of 1 or 1.5-Ω, 10-W resistors in series with each motor lead. Connect a 0.1 µF 50-V disc ceramic capacitor across the motor leads to suppress motor noise.

Connect a pair of wires, about a foot long, to the other ends of the resistors. These will power the screwdriver from your car's 12-V system. Next, procure a 20-inch long piece of $^1/_4$-20 threaded rod (also called "all-thread"). Insert one end of this into the cordless screwdriver chuck, and drill a $^1/_{16}$-inch or $^3/_{32}$-inch hole through both the chuck and the rod. Secure the rod in place with either a roll or cotter pin, and install a pair of $^1/_4$-inch nuts on the rod near the screwdriver chuck. This will be the lower stop for the coil travel and will be adjusted later.

Thread the rod into the threaded insert at the bottom of the coil form, and install another pair of stop nuts on the top side of the rod. It will be easier to do this before attaching the bottom plug to the coil form. Again, these nuts will be adjusted later for proper coil travel.

Place the bottom plug into the coil form, drill a couple of holes through the form and the plug and tap them for 6-32 flat head bolts. Countersink the form so that the heads will be flush with the outside. Again, see **Fig 27**.

Finger Stock

Now, let's go back to the base tube. You must install a circle of finger-stock strip on the top of the tube to make contact with the coil, as shown in Fig 24. This can either be soldered or riveted, depending on your choice of tube material. Next, insert the coil and screwdriver assembly through the bottom of the tube, making sure that the coil clears the finger stock without deforming or bending it.

The best method I have found for attaching the screwdriver to the bottom tube is to fit a piece of $1^1/_2$-inch PVC pipe, about 8 or 10 inches long, over the handle of the screwdriver and attach it with a couple of flat-head 6-32 bolts. You may have to either grind some material off the handle or wrap it with some duct tape to make a snug fit inside the $1^1/_2$-inch PVC pipe, which should slip snugly into the base tube.

Place a matching $1^1/_2$-inch PVC pipe cap on the bottom of the pipe, and secure it with a couple of 6-32 screws. Drill a $^1/_4$-inch hole through one side of the cap, which will serve to pass the wires from the screwdriver motor. Drill a $^3/_8$-inch hole directly in the center of this cap for the base mount. See **Fig 28**, which is a drawing of the completed antenna assembly.

MOUNTING THE ANTENNA

At this point you must determine exactly how you wish to mount the antenna on your vehicle. You could fasten it to a standard mobile antenna mount, but *do not* use a spring! I prefer to fasten the assembly to a thick metal plate about 6 × 18 inches in size. I mount this to the frame of the car, protruding about 4 or 5 inches from the lower car body, just behind the rear wheel. You could also fasten such a plate to the lower fender sheet metal with large sheet-metal screws. The SO-239 connector is mounted to this plate also. See **Fig 29**.

An upper bracket, made from Plexiglas or similar insulating material, can be mounted from the trunk lip with an L-angle and used to support the top of the lower tube. See **Fig 30**. With a Plexiglas bracket about 4-inches wide, a 2-inch hole can be drilled in it to pass the tube. This will make a snug and rigid fit at the top. Under no circumstances use a metal band around the tube, as this will form a shorted turn and drastically lower the antenna Q.

With a little care, this type of mounting will leave no visible holes in the vehicle, which will likely enhance its trade-in value. If you mount the antenna on a pickup truck, it can be mounted directly on the rear safety bumper with a $1^1/_2$ inch pipe floor flange and matching adaptor on the bottom of the tube.

Electrical Connections

After mounting the base, your next job is to connect the wires from the screwdriver to a DPDT, spring-return center-off switch, mounted in a convenient location in your car. See the schematic in **Fig 31**. Connect the coax from the radio to the base tube, with the center conductor going to the base tube and the shield connected to ground at the base of the antenna.

If you like, you could install a simple base-matching network to give a perfect match on the lower bands. Even with no matching unit, SWR is usually under 2:1 on all



Fig 29—Base-mounting plate for Screw-driver installation on KO4TV's truck. Note the quick-disconnect dc motor con-nections and the SO-239 coax connector.



Fig 30—The support Plexiglas plate. (*Photo courtesy of Gary Pearce, KN4AQ.*)



Fig 31—The DPDT center-off spring-loaded switch used to control the screwdriver motor.



Fig 32—Relay-switched matching capacitors for 40 and 80 meters.



Fig 33—Alternative matching scheme using a single shunt matching coil.

bands. See **Fig 32**. One matching network consists of a couple of trimmer capacitors switched from the bottom of the base tube to ground using a pair of small relays. For 80 meters, approximately 800 pF is required, and for 40 meters about 400 pF. No matching is required for 30 meters or higher.

An alternative matching method is to install a 15-turn coil made from #14 enamel wire, about 1/2 inch diameter, from the base to ground. See **Fig 33**. In either case, adjust the whip length for proper resonance at both ends of the HF spectrum over the range of movement of your coil.

This antenna may have different matching requirements, depending on the vehicle type and mounting location, so you may need to do some experimentation to obtain optimum results. If it doesn't work exactly right at first, be prepared to do a little experimenting.

A COIL COVER

Most builders will want to provide a coil cover, both for protection and appearance. KO4TV's favorite cover is made from a plastic mailing tube, about 24 to 30 inches long and about 1/2 inches in diameter. You can find these at an office supply store. They have a screw-on cap on one end, which can be mounted to the top of the loading coil.



Fig 34—Remote control by the rear-view mirror—tuning by the stripes! (*Photo courtesy of Gary Pearce, KN4AQ.*)

You trim the bottom of the cover to the proper length to allow the coil to be fully retracted into the base tube while still clearing the top bracket. Other builders have used such diverse materials as:

- Several 1-liter soft drink bottles cut off, swaged and glued together
- Sections of Schedule 20 PVC pipe with matching cap
- Empty beef jerky tubes (usually available for the asking at convenience stores)
- Wands from a shop vacuum cleaner, fitted with the cap from an aerosol spray can.

Just let your imagination run wild and you may be surprised at your own ingenuity. Whatever material you do use, paint it to match your vehicle. Just be sure to use non-metallic paint.

TUNING BY THE STRIPES

The author used different colored vinyl tapes to mark the tuning points for the amateur bands along the tuning coil. The lower edge of the supporting Plexiglas middle support acts as a pointer, which he can spot from his rear-view mirror. See **Fig 34**. This may be low-tech tuning method, but it works!

THE PROOF IS IN THE PUDDING

Now, you are ready to enjoy some real mobile communications on all bands, without even stopping the vehicle to QSY. KO4TV's antenna has contacted over 100 DX countries, from as far away as Tasmania and Japan from the East Coast. He enjoys regular contacts with Israel and other stations in the Mid-East, running 100 W or less.

A MOBILE J ANTENNA FOR 144 MHz

The J antenna is a mechanically modified version of the Zepp (Zeppelin) antenna. It consists of a half-wave-length radiator fed by a quarter-wave matching stub. This antenna exhibits an omnidirectional pattern with little high-angle radiation, but does not require the ground plane that $^1/_4$-wave and $^5/_8$-wave antennas do to work properly. The material in this section was prepared by Domenic Mallozzi, N1DM, and Allan White, W1EYI.

Fig 35 shows two common configurations of the J antenna. Fig 35A shows the shorted-stub version that is usually fed with 200- to 600-Ω open-wire line. Some have attempted to feed this antenna directly with coax without a balun, and this usually leads to less than optimum results. Among the problems with such a configuration are a lack of reproducibility and heavy coupling with nearby objects. To eliminate these problems, many



Fig 35—Two configurations of the J antenna.



Fig 36—The mount for the mobile J is made from stainless-steel angle stock and secured to the bumper with stainless-steel hardware. Note the $^1/_2$-inch pipe plug and a PL-259 (with a copper disc soldered in its unthreaded end). These protect the mount and connector threads when the antenna is not in use.



Fig 37—The J antenna, ready for use. Note the bakelite insulator and the method of feed. Tie wraps are used to attach the balun to the mounting block and to hold the coax to the support pipe. Clamps made of flashing copper are used to connect the balun to the J antenna just above the insulating block. The ends of the balun should be weatherproofed.



Fig 38—Details of the insulated mounting block. The material is bakelite.



Fig 39—Measured SWR of the mobile J antenna.

amateurs have used a 4:1 half-wave balun between the feed point and a coaxial feed line. This simple addition results in an antenna that can be easily reproduced and that does not interact so heavily with surrounding objects. The bottom of the stub may be grounded (for mechanical or other reasons) without impairing the performance of the antenna.

The open-stub-fed J antenna shown in Fig 35B can be connected directly to low-impedance coax lines with good results. The lack of a movable balun (which allows some impedance adjustment) may make this antenna a bit more difficult to adjust for minimum SWR, however.

The Length Factor

Dr. John S. Belrose, VE2CV, noted in *The Canadian Amateur* that the diameter of the radiating element is important to two characteristics of the antenna—its bandwidth and its physical length. (See Bibliography at the end of this chapter.) As the element diameter is increased, the usable bandwidth increases, while the physical length of the radiating element decreases with respect to the free-space half-wavelength. The increased diameter makes the end effect more pronounced, and also slows the velocity of propagation on the element. These two effects are related to resonant antenna lengths by a factor, "k." This factor is expressed as a decimal fraction giving the equivalent velocity of propagation on the antenna wire as a function of the ratio of the element diameter to a wavelength. The k factor is discussed at length in Chapter 2.

The length of the radiating element is given by

$$\ell = \frac{5904 \times k}{f} \qquad \text{(Eq 25)}$$

where

ℓ = length in inches
f = frequency in MHz
k = k factor.

The k factor can have a significant effect. For example, if you use a $^5/_8$-inch diameter piece of tubing for the radiator at 144 MHz, the k value is 0.907 (9.3% shorter than a free-space half wavelength).

The J antenna gives excellent results for both mobile and portable work. The mobile described here is similar to an antenna described by W. B. Freely, K6HMS, in April 1977 *QST*. This design uses mechanical components that are easier to obtain. As necessary with all mobile antennas, significant attention has been paid to a strong, reliable, mechanical design. It has survived not only three New England winters, but also two summers of 370-mile weekend commutes. During this time, it has maintained consistent electrical performance with no noticeable deterioration.

The mechanical mount to the bumper is a 2 × 2-inch stainless steel angle iron, 10 inches long. It is secured to the bumper with stainless steel hardware, as shown in **Fig 36**. A stainless steel $^1/_2$-inch pipe coupling is welded to the left side of the bracket, and an SO-239 connector is mounted at the right side of the bracket. The bracket is mounted to the bumper so a vertical pipe inserted in the coupling will allow the hatchback of the vehicle to be opened with the antenna installed, **Fig 37**.

A $^1/_2$-inch galvanized iron pipe supports the antenna so the radiating portion of the J is above the vehicle roof line. This pipe goes into a bakelite insulator block, visible in Fig 37. The insulator block also holds the bottom of the stub. This block was first drilled and then split with a band saw, as shown in **Fig 38**. After splitting, the two portions are weatherproofed with varnish and rejoined with 10-32 stainless hardware. The corners of the insulator are cut to clear the L sections at the shorted end of the stub.

The quarter-wave matching section is made of $^1/_4$-inch type L copper tubing ($^5/_{16}$ inch ID, $^3/_8$ inch OD). The short at the bottom of the stub is made from two copper L-shaped sections and a short length of $^1/_4$-inch tubing. Drill a $^1/_8$-inch hole in the bottom of this piece of tubing to drain any water that may enter or condense in the stub.

A $^5/_{16}$-inch diameter brass rod, $1^1/_2$ to 2 inches long, is partially threaded with a $^5/_{16}$ × 24 thread to accept a Larsen whip connector. This rod is then sweated into one of the legs of the quarter-wave matching section. A 40-inch whip is then inserted into the Larsen connector.

The antenna is fed with 50-Ω coaxial line and a coaxial 4:1 half-wave balun. This balun is described at the end of Chapter 26. As with any VHF antenna, use high-quality coax for the balun. Seal all open cable ends and the rear of the SO-239 connector on the mount with RTV sealant.

Adjustment is not complicated. Set the whip so that its tip is 41 inches above the open end of the stub, and adjust the balun position for lowest SWR. Then adjust the height of the whip for the lowest SWR at the center frequency you desire. **Fig 39** shows the measured SWR of the antenna after adjustments are completed.

THE SUPER-J MARITIME ANTENNA

This 144-MHz vertical antenna doesn't have stringent grounding requirements and can be made from easy to find parts. The material in this section was prepared by Steve Cerwin, WA5FRF, who developed the Super-J for use on his boat.

Antennas for maritime use must overcome difficulties that other kinds of mobile antennas normally do not encounter. For instance, the transom of a boat is the logical place to mount an antenna. But the transoms of many boats are composed mostly of fiberglass, and they ride some distance out of the water—from several inches to a few feet, depending on the size of the vessel. Because the next best thing to a ground plane (the water surface) is more than an appreciable fraction of a wavelength away at 144 MHz, none of the popular gain-producing antenna designs requiring a counterpoise are suitable. Also, since a water surface does a good job of assuming the earth's lowest mean elevation (at least on a calm day), anything that can be done to get the radiating part of the antenna up in the air is helpful.

One answer is the venerable J-pole, with an extra in-phase half-wave section added on top—the Super-J antenna. The two vertical half waves fed in phase give outstanding omnidirectional performance for a portable antenna. Also, the J-pole feed arrangement provides the desired insensitivity to height above ground (or water) plus added overall antenna height. Best of all, a $^1/_4$-wave CB whip provides enough material to build the whole driven element of the antenna, with a few inches to spare. The antenna has enough bandwidth to cover the entire 144-MHz band, and affords a measure of lightning protection by being a grounded design.

Antenna Operation

The antenna is represented schematically in **Fig 40**. The classic J-pole antenna is the lower portion shown between points A and C. The half-wave section between points B and C does most of the radiating. The added half-wave section of the Super-J version is shown between points C and E. The side-by-side quarter-wave elements between points A and B comprise the J feed arrangement.

At first glance, counterproductive currents in the J section between points A and B may seem a waste of element material, but it is through this arrangement that



Fig 40—Schematic representation of the Super-J maritime antenna. The radiating section is two half waves in phase.

the antenna is able to perform well in the absence of a good ground. The two halves of the J feed arrangement, side by side, provide a loading mechanism regardless of whether or not a ground plane is present.

The radiation resistance of any antenna fluctuates as a function of height above ground, but the magnitude of this effect is small compared to the wildly changing impedance encountered when the distance from a ground plane element to its counterpoise is varied. Also, the J section adds $^{1}/_{4}$ wavelength of antenna height, reducing the effect of ground height variations even further. Reducing ground-height sensitivity is particularly useful in maritime operation on those days when the water is rough.

The gain afforded by doubling the aperture of a J-pole with the extra half-wave section can be realized only if the added section is excited in phase with the half-wave element B-C. This is accomplished in the Super-J in a conventional manner, through the use of the quarter-wave phasing stub shown between C and D.

Construction and Adjustment

The completed Super-J is shown in **Fig 41**. Details of the individual parts are given in **Fig 42**. The driven element can be liberated from a quarter-wave CB whip antenna and cut to the dimensions shown. All other metal stock can be obtained from metal supply houses or machine shops. Metal may even be scrounged for little or nothing as scraps or remnants, as were the parts for the antenna shown here.



Fig 41—Andy and the assembled Super-J antenna.

The center insulator and the two J stub spacers are made of $^{1}/_{2}$-inch fiberglass and stainless steel stock, and the end caps are bonded to the insulator sections with epoxy. If you don't have access to a lathe to make the end caps, a simpler one-piece insulator design of wood or fiberglass could be used. However, keep in mind that good electrical connections must be maintained at all joints, and strength is a consideration for the center insulator.

The quarter-wave phasing stub is made of $^{1}/_{8}$-inch stainless steel tubing, **Fig 43**. The line comprising this stub is bent in a semicircular arc to narrow the vertical profile and to keep the weight distribution balanced. This makes for an attractive appearance and keeps the antenna from leaning to one side.

The bottom shorting bar and base mounting plate are made of $^{1}/_{4}$-inch stainless steel plate, shown in **Fig 44**. The J stub is made of $^{3}/_{16}$-inch stainless-steel rod stock. The RF connector may be mounted on the shorting bar as shown, and connected to the adjustable slider with a short section of coaxial cable. RTV sealant should be used at the cable ends to keep out moisture. The all-stainless construction looks nice and weathers well in maritime mobile applications.

The antenna should work well over the whole 144-MHz band if cut to the dimensions shown. The only tuning required is adjustment of the sliding feed point for minimum SWR in the center of the band segment you use most. Setting the slider $2^{13}/_{16}$ inch above the top of the shorting bar gave the best match for this antenna and may be used for a starting point. Four turns of coax made into a coil at the feed point or a ferrite-sleeve balun act as a common-mode choke balun to ensure satisfactory performance.


#7(.201") Drill Through
8-32 Tapped Hole (3 plcs)
1/8" Through Cross Hole Drill After Assembly to Insulator
3/8"
3/16"
3/8"
7/8"
3/8"
1-1/4"
Fiberglass
3/8"
3/8"
3/8" Min.
1"
1/4"
1/4"
1/2"
Center Insulator 1/2" Stock
1-1/8"
1/4-Wave Phasing Stub Folded Around Antenna 1/8" SS Tubing
18"
2-1/2"
2"
1/4" Through (4 plcs)
3/8 X 24 NF Tapped Hole
2-1/2"
2"
Base Mounting Plate 1/4" Stainless Plate
1/4"
1/4"
1/4"
3/8"
Fiberglass
#7 (.201")Through Cross Hole Drill After Assembly to Insulator Piece
8-32 Tapped Hole
Top "J" Stub Spacer Insulator End Caps Identical Assemble with Epoxy
1/4" Min.
3/4"
1/8"
4-40 Tapped for Feed Line Connection
1/2"
3/8"
Fiberglass
8-32 Tapped Hole
1/2"
1-1/4"
End View
Sliding Feeder Insulator
1/2-Wave Top Section 38-3/8"
3/4-Wave Bottom Section 58-3/8"
Driven Element Obtained from 1/4-Wave CB Whip
#7 (.201") Drill Through 2 Holes
1/4"
1/4"
1/4"
1-1/4"
1-3/4"
1/4"
1"
1/4"
8-32 Tapped Holes (4 plcs)
Base Shorting Bar 1/4" Stainless Plate
20-3/8"
"J" Stub 3/16 SS Rod

Fig 42—Details of parts used in the construction of the 144-MHz Super-J. Not to scale.



Fig 43—A close-up look at the 1/4-λ phasing section of the Super-J. The insulator fitting is made of stainless-steel end caps and fiberglass rod.



Fig 44—The bottom shorting bar and base mounting plate assembly.



Fig 45—The Super-J in portable use at a field site.

Performance

Initial tests of the Super-J were performed in portable use and were satisfactory, if not exciting. **Fig 45** shows the Super-J mounted on a wooden mast at a portable site. Simplex communication with a station 40 miles away with a 10-W mobile rig was full quieting both ways. Stations were worked through distant repeaters that were thought inaccessible from this location.

Comparative tests between the Super-J and a commercial 5/8-wave antenna mounted on the car showed the Super-J to give superior performance, even when the Super-J was lowered to the same height as the car roof. The mast shown in Fig 45 was made from two 8-foot lengths of 1 × 2-inch pine. (The two mast sections and the Super-J can be easily transported in most vehicles.)

The Super-J offers a gain of about 6 dB over a quarter-wave whip and around 3 dB over a 5/8-wave antenna. Actual performance, especially under less-than-ideal or variable ground conditions, is substantially better than other vertical antennas operated under the same conditions. The freedom from ground-plane radials proves to be a real benefit in maritime mobile operation, especially for those passengers in the back of the boat with sensitive ribs!

A TOP-LOADED 144-MHz MOBILE ANTENNA

Earlier in this chapter, the merits of various loading schemes for shortened whip antennas were discussed. Quite naturally, one might be considering HF mobile operation for the application of those techniques. But the principles may be applied at any frequency. **Fig 46** shows a 144-MHz antenna that is both top and center loaded. This antenna is suitable for both mobile and portable operation, being intended for use on a handheld transceiver. This antenna was devised by Don Johnson, W6AAQ, and Bruce Brown, W6TWW.



Fig 46—This 144-MHz antenna uses a combination of top and center loading. It offers low construction cost and improved efficiency over continuously loaded rubber-ducky antennas.

A combination of top and center loading offers improved efficiency over continuously loaded antennas such as the "stubby" pictured at the beginning of this chapter. This antenna also offers low construction cost. The only materials needed are a length of stiff wire and a scrap of circuit-board material, in addition to the appropriate connector.

Construction

The entire whip section with above-center loading coil is made of one continuous length of material. An 18-inch length of brazing rod or #14 Copperweld wire is suitable.

In the antenna pictured in Fig 46, the top loading disk was cut from a scrap of circuit-board material, but flashing copper or sheet brass stock could be used instead. Aluminum is not recommended.

The dimensions of the antenna are given in **Fig 47**. First wind the center loading coil. Use a $^1/_2$-inch bolt, wood dowel, or other cylindrical object for a coil form. Begin winding at a point 3 inches from one end of the wire, and wrap the wire tightly around the coil form. Wind $5^1/_2$ turns, with just enough space between turns so they don't touch.

Remove the coil from the form. Next, determine the length necessary to insert the wire into the connector you'll be using. Cut the long end of the wire to this length plus 4 inches, measured from the center of the coil. Solder the wire to the center pin and assemble the connector. A tight-fitting sleeve made of Teflon or Plexiglas rod may be used to support and insulate the antenna wire inside the shell. An alternative is to fill the shell with epoxy cement, and allow the cement to set while the wire is held centered in the shell.

The top loading disk may be circular, cut with a hole saw. A circular disk is not required, however—it may be of any shape. Just remember that with a larger disk, less coil inductance will be required, and vice versa. Drill a hole at the center of the disk for mounting it to the wire. For a more rugged antenna, reinforce the hole with a brass eyelet. Solder the disk in place at the top of the antenna, and construction is completed.



Fig 47—Dimensions for the top-loaded 144-MHz antenna. See text regarding coil length.

Tune-Up

Adjustment consists of spreading the coil turns for the correct amount of inductance. Do this at the center frequency of the range you'll normally be using. Optimum inductance is determined with the aid of a field strength meter at a distance of 10 or 15 feet.

Attach the antenna to a handheld transceiver operating on low power, and take a field-strength reading. With the transmitter turned off, spread the coil turns slightly, and then take another reading. By experiment, spread or compress the coil turns for the maximum field-strength reading. Very little adjustment should be required. There is one precaution, however. You must keep your body, arms, legs, and head in the same relative position for each field-strength measurement. It is suggested that the transceiver be placed on a nonmetal table and operated at arm's length for these checks.

Once the maximum field-strength reading is obtained, adjustments are completed. With this antenna in operation, you'll likely find it possible to access repeaters that are difficult to reach with other shortened antennas. W6AAQ reports that in distant areas his antenna even outperforms a $^5/_8$-λ vertical.

VHF QUARTER-WAVELENGTH VERTICAL

Ideally, a VHF vertical antenna should be installed over a perfectly flat reflector to assure uniform omnidirectional radiation. This suggests that the center of the automobile roof is the best place to mount it for mobile use. Alternatively, the flat portion of the trunk deck can be used, but will result in a directional pattern because of car-body obstruction.

Fig 48 illustrates how a Millen high-voltage connector can be used as a roof mount for a VHF whip. The hole in the roof can be made over the dome light, thus providing accessibility through the upholstery. RG-59 and the $^1/_4$-wave matching section, L (Fig 48C), can be routed between the car roof and the ceiling upholstery and brought into the trunk compartment, or down to the dashboard of the car. Instead of a Millen connector, some operators install an SO-239 coax connector on the roof for mounting the whip. The method is similar to that shown in Fig 48.

It has been established that in general, $^1/_4$-λ vertical antennas for mobile repeater work are not as effective as $^5/_8$-λ verticals are. With a $^5/_8$-λ antenna, more of the transmitted signal is directed at a low wave angle, toward the horizon, offering a gain of about 1 dB over the $^1/_4$-λ vertical. However, in areas where the repeater is located nearby on a very high hill or a mountain top, the $^1/_4$-λ antenna will usually offer more reliable per-



Fig 48—At A and B, an illustration of how a quarter-wavelength vertical antenna can be mounted on a car roof. The whip section should be soldered into the cap portion of the connector and then screwed into the base socket. This arrangement allows for the removal of the antenna when desired. Epoxy cement should be used at the two mounting screws to prevent the entry of moisture through the screw holes. Diagram C is discussed in the text.

formance than a $^5/_8$-λ antenna. This is because there is more power in the lobe of the $^1/_4$-λ vertical at higher angles.

144-MHz 5/8-WAVELENGTH VERTICAL

Perhaps the most popular antenna for 144-MHz FM mobile and fixed-station use is the $^5/_8$-wavelength vertical. As compared to a $^1/_4$-wavelength vertical, it has 1 dB of gain.

This antenna is suitable for mobile or fixed-station use because it is small, omnidirectional, and can be used with radials or a solid-plane ground (such as a car body). If radials are used, they need be only $^1/_4$ wavelength long.

Construction

The antenna shown here is made from low-cost materials. **Fig 49** shows the base coil and aluminum mounting plate. The coil form is a piece of low-loss solid rod, such as Plexiglas or phenolic. The dimensions for this and other parts of the antenna are given in **Fig 50**. A length of brazing rod is used as the whip section.

The whip should be 47 inches long. However, brazing rod comes in standard 36-inch lengths, so if used, it is necessary to solder an 11-inch extension to the top of the whip. A piece of #10 copper wire will suffice. Alternatively, a stainless-steel rod can be purchased to make a 47-inch whip. Shops that sell CB antennas should have such rods for replacement purposes on base-loaded antennas. The limitation one can expect with brazing rod is the relative fragility of the material, especially when the threads are cut for screwing the rod into the base coil form. Excessive stress can cause the rod to break where it enters the form. The problem is compli-



Fig 49—At top, a photograph of the $^5/_8$-λ vertical base section. The matching coil is affixed to an aluminum bracket that screws onto the inner lip of the car trunk. Above, the completed assembly. The coil has been wrapped with vinyl electrical tape to keep out dirt and moisture.


11″
#10 Wire
Solder
36″
6-32 Thread
1″ Long
6-32 Nut
#6 Solder Lug
to Solder Lug
#6 Lock Washer
6-32 Thread
1″ Deep
Plexiglas Form
3/4″ X 3-1/2″
#10 or 12
Wire 10-1/2 Turns
Coil Tap to F.T.
Bushing
to Coax Cable
Ground Coil
10-32 Thread
1″ Deep
Cork or Rubber
Gasket
#10 Lock Washer
on Bottom of Bracket
10-32 X 3/4″ Screw
(Coat with Epoxy Glue
at Assembly Time)
(A)
Whip
52 Ω
Line
to Rig
L1
Small Feedthrough
Bushing
Aluminum
Stock
#6 Solder
Lug (Gnd.)
(C)
#6 Holes
Bolt to Inner Lip
of Trunk
(B)

Fig 50—Structural details for the 2-meter $^{5}/_{8}$-λ antenna are provided at A. The mounting bracket is shown at B and the equivalent circuit is given at C.

cated somewhat in this design because a spring is not used at the antenna mounting point. Builders of this antenna can find all kinds of solutions to the problems just outlined by changing the physical design and using different materials when constructing the antenna. The main purpose of this description is to provide dimensions and tune-up information.

The aluminum mounting bracket must be shaped to fit the car with which it will be used. The bracket can be used to effect a no-holes mount with respect to the exterior portion of the car body. The inner lip of the vehicle trunk (or hood) can be the point where the bracket is attached by means of no. 6 or no. 8 sheet-metal screws. The remainder of the bracket is bent so that when the trunk lid or car hood is raised and lowered, there is no contact between the bracket and the moving part. Details of the mounting unit are given in Fig 50B. A 14-gauge metal (or thicker) is recommended for rigidity.

Wind $10^{1}/_{2}$ turns of #10 or #12 copper wire on the $^{3}/_{4}$-inch diameter coil form. The tap on L1 is placed approximately four turns below the whip end. A secure solder joint is imperative.

Tune-Up

After the antenna has been mounted on the vehicle, connect an SWR indicator in the 50-Ω transmission line. Key the 144-MHz transmitter and experiment with the coil tap placement. If the whip section is 47 inches long, an SWR of 1:1 can be obtained when the tap is at the right location. As an alternative method of adjustment, place the tap at four turns from the top of L1, make the whip 50 inches long, and trim the whip length until an SWR of 1:1 occurs. Keep the antenna well away from other objects during tune-up, as they may detune the antenna and yield false adjustments for a match.

A 5/8-WAVELENGTH 220-MHz MOBILE ANTENNA

The antenna shown in **Figs 51** and **52** was developed to fill the gap between a homemade $^{1}/_{4}$-λ mobile antenna and a commercially made $^{5}/_{8}$-λ model. While antennas can be made by modifying CB models, that presents the problem of cost in acquiring the original antenna. The major cost in this setup is the whip portion. This can be any tempered rod that will spring easily.

Construction

The base insulator portion is made of $^{1}/_{2}$-inch Plexiglas rod. A few minutes' work on a lathe is sufficient to shape and drill the rod. (The innovative builder can use an electric drill and a file for the lathe work.)



Fig 51—The 220-MHz $^5/_8$-λ mobile antenna. The coil turns are spaced over a distance of 1 inch, and the bottom end of the coil is soldered to the coax connector.



Fig 52—Diagram of the 220-MHz mobile antenna.

The bottom $^1/_2$ inch of the rod is turned down to a diameter of $^3/_8$ inch. This portion will now fit into a PL-259 UHF connector. A $^1/_8$-inch diameter hole is drilled through the center of the rod. This hole will hold the wires that make the connections between the center conductor of the connector and the coil tap. The connection between the whip and the top of the coil is also run through this opening. A stud is force-fitted into the top of the Plexiglas rod. This allows for removal of the whip from the insulator.

The coil should be initially wound on a form slightly smaller than the base insulator. When the coil is transferred to the Plexiglas rod, it will keep its shape and will not readily move. After the tap point has been determined, a longitudinal hole is drilled into the center of the rod. A #22 wire can then be inserted through the center of the insulator into the connector. This method is also used to attach the whip to the top of the coil. After the whip has been fully assembled, a coating of epoxy cement is applied. This seals the entire assembly and provides some additional strength. During a full winter's use there was no sign of cracking or other mechanical failure. The adjustment procedure is the same as for the 144-MHz version described previously.

HF Antennas For Sailboats

This material was contributed by Rudy Severns, N6LF. Many of the antenna ideas appearing earlier in this chapter can be applied to sailboats. However, the presence of the mast and the rigging, plus the prevalence of non-conducting fiberglass hulls complicates the issue. There are many possibilities for antennas aboard sailboats. This includes both permanently installed antennas and antennas that can be hoisted for temporary use at anchor:

1. ***Permanent***
   Commercial or home-brew automobile-type verticals
   Backstay verticals and slopers
   Shunt feed of uninsulated rigging

2. ***Temporary***
   Sloping dipoles
   Inverted V's
   Yagis

You should remember some basic facts of life on a sailboat:

1) On most boats the spars, standing rigging and some running rigging will be conductors. Stainless steel wire is usually used for the rigging and aluminum for the spars.
2) Topping lifts, running backstays and jackstays all may be made of conducting materials and may often change position while the boat is underway. This changes the configuration of the rigging and may affect radiation patterns and feed-point impedances.
3) Shipboard antennas will always be close to the mast and rigging, in terms of electrical wavelength. Some antennas may in fact be part of the rigging.
4) The feed-point impedance and radiation pattern can be strongly influenced by the presence of the rigging.
5) Because of the close proximity, the rigging is an integral part of the antenna and should be viewed as such.
6) The behavior of a given antenna will depend on the details of the rigging on a particular vessel. The performance of a given antenna can vary widely on different boats, due to differences in dimensions and arrangement of the rigging.
7) Even though you may be floating on a sea of salt water, grounding still requires careful attention!

ANTENNA MODELING

Because of the strong interaction between the rigging and the antenna, accurate prediction of radiation patterns and a reasonable guess at expected feed-point impedance requires that you model both the antenna and the rigging. Unless you do accurately model the system, considerable cut-and-try may be needed. This can be expensive when it has to be done in 1 × 19 stainless steel wire with $300 swaged insulator fittings!

In fact, when your antenna is going to be part of standing rigging, it's a very good idea to try your designs out at the dock. You could temporarily use Copperweld wire and inexpensive insulators in place of the stainless rigging wire and the expensive insulators. This approach can save a good deal of money and aggravation. A wide variety of modeling programs are available and can be very helpful in designing a new antenna but they have to be used with some caution:

1) The rigging will have many small intersection angles and radically different conductor diameters, this can cause problems for *NEC* and *MININEC* programs.
2) You must usually taper the segment lengths near the junctions. This is done automatically in programs like *ELNEC* and *EZNEC*.
3) It is usually necessary to use one wire size for the mast, spars and rigging. Some improvement in accuracy can be obtained by modeling the mast as a cage of 3 or 4 wires.

The predicted radiation patterns will be quite good but the feed-point impedance predictions should be viewed as preliminary. Some final adjustment will usually be required. Because of the wide variation between boats, even those of the same class, each new installation is unique and should be analyzed separately.



Fig 53—An example of a 20-meter λ/4 whip mounted on the transom. A local ground system must also be provided, as described in the section on grounding.

A SAFETY NOTE

Ungrounded rigging endpoints near deck level can have high RF potentials on them when you transmit. For example, the shrouds on a fiberglass boat connect to chainplates that are bolted to the hull, but are not grounded. These can inflict painful RF burns on the unwary, even while operating at low power! As a general rule all rigging, spars and lifelines near deck level should be grounded. This also makes good sense for lightning protection. For a backstay antenna with its feed point near deck level, a sleeve of heavy wall PVC pipe can be placed over the lower end of the stay as a protective shield.

TRANSOM AND MASTHEAD MOUNTED VERTICALS

A very common antenna for boats is a vertical, either a short mobile antenna or a full λ/4, placed on the transom, as shown in **Fig 53**. Note that in this example the antenna is mounted off to one side—it could also be mounted in the center of the transom. The 20-meter radiation pattern for this antenna as shown in **Fig 54**. Unlike a free standing vertical, this antenna doesn't have an omnidirectional pattern. It is asymmetrical, with a front-to-back ratio of about 13 dB. Further, the angle for maximum gain is offset in the direction the antenna is placed on the transom.

This is a very good example of the profound effect the rigging can have on any antenna used on board a sailboat. Not only is the pattern affected but the feed-point impedance will be reduced from a nominal 36 Ω to 25 to 30 Ω.

The directive gain can be useful—if you point the boat in the right direction! Usually, however, a more uniform omnidirectional pattern is more desirable. It is tempting to suggest putting the vertical at the masthead, perhaps using a 6-foot loaded automobile whip, with the mast and rigging acting as a ground plane. **Fig 55** shows such a system. Unfortunately, this usually doesn't work very well because the overall height of the mast and antenna will very likely be > 5/8 λ. This will result in high-angle lobes, as shown in **Fig 56**. Depending on the mast height, this idea may work reasonably well on 40 or 80 meters, but



Fig 54—Typical radiation pattern for the λ/4 transom mounted whip in Fig 53.



Fig 55—A whip mounted at the masthead. The feed line is fed back down the mast either inside or outside. The base of the mast and the rigging is assumed to be properly grounded.



Fig 56—Typical radiation pattern for a masthead-mounted vertical. The multiple vertical lobes are due to the fact the antenna is higher than λ/2.



Fig 57—An example of a backstay vertical. A local ground point must be established on the transom next to the base of the backstay.

you will still be faced with severe mechanical stress due to magnified motion at the masthead in rough sea. The masthead is usually reserved to VHF antennas, with their own radial ground plane.

THE BACKSTAY VERTICAL

A portion of the backstay can be insulated and used as a vertical as shown in **Fig 57**. The length of the insulated section will be λ/4 on the lowest band of interest. Typically, due to the loading effect of the rest of the rigging, the resonant length of the insulated section will be shorter than the classic 234/f (MHz) relation, although it can in some case actually be longer. Either modeling or trial adjustment can be used to determine the actual length needed. On a typical 35 to 40-foot sailboat, the lowest band for λ/4 resonance will be 40 meters due to the limited length of the backstay. Examples of the radiation patterns on several bands for such an an-



Fig 58—Typical radiation patterns on 40 meters for the backstay vertical in Fig 57.



Fig 59—Typical radiation patterns on 20 meters for the backstay vertical in Fig 57.



Fig 60—Typical radiation patterns on 15 meters for the backstay vertical in Fig 57.

tenna are given in **Figs 58** through **60**.

The pattern is again quite directional due to the presence of the mast and rigging. On 15 meters, where the antenna is approximately $^3/_4$ λ, higher angle lobes appear. On 40 and 15 meters, the feed point is near a current maximum and is in the range of 30 to 50 Ω. On 20 meters, however, the feed point is a very high impedance because the antenna is near λ/2 resonance. One way to get around this problem for multiband use is to make the antenna longer than λ/4 on the lowest band. If the lowest band is 40 meters then on 20 meters the feed-point impedance will be much lower. This antenna is non-resonant on any of the bands but can be conveniently fed with a tuner because the feed-point impedances are within the range of commonly available commercial tuners. Tuners specifically intended for marine applications frequently can accommodate very high input impedances, but they tend to be quite expensive.

The sensitivity of the radiation pattern to small details of the mast and rigging is illustrated in **Fig 61**. This is the same antenna as shown in Fig 57 with the exception that the forestay is assumed to be ungrounded. In this particular example, ungrounding the forestay drastically increases the front-to-back ratio. With slightly different dimensions, however, the pattern could have changed in other ways.

High-quality insulators for rigging wire can be quite expensive and represent a potential weak point—if they fail the mast may come down. It is not absolutely necessary to use two insulators in a backstay vertical. As shown in **Fig 62**, the upper insulator may be omitted. The radiation patterns are shown in **Figs 63** and **64**. In this case



Fig 61—The effect of ungrounding the forestay on the radiation pattern. This is for 40-meter operation.



Fig 62—Feeding the backstay without an insulator at the top. The feed point may be moved along the antenna to find a point with a better match on a particular band or to provide a better range of impedances for the tuner to match. The coaxial feed line is taped to the lower portion of the backstay. Again, a good local ground is needed at the base of the backstay.

the pattern is actually more symmetrical than it was with an upper insulator—but this may not hold true for other rigging dimensions. The feed point does not have to be at the bottom of the backstay. As indicated in Fig 62, the feed point can be moved up into the backstay to achieve a better match or a more desirable feed-point impedance variation with frequency. In that case, the center of the coaxial feed line is connected to the upper section and the shield to the lower section. The cable is then taped to the lower portion of the backstay.

If single-band operation is all you want, even the lower insulator can be omitted by using shunt feed. A gamma match would be quite effective for this purpose, as discussed in Chapter 6 when driving a grounded tower.

A 40-METER BACKSTAY HALF SLOPER

A half-sloper antenna can be incorporated into the backstay, as shown in **Fig 65**. This will behave very much the same as the slopers described in Chapter 6. The advantage of this antenna for a sailboat installation is that you don't need to create a good ground connection at the stern, as you would have to do for a transom-mounted vertical or the backstay vertical just described. This may be more convenient. The mast, shrouds and stays must still be grounded for the half-sloper but the arrangement is somewhat simpler.

TEMPORARY ANTENNAS

Not everyone needs permanent antennas. A variety



Fig 63—Typical 40-meter radiation pattern in Fig 62.



Fig 64—Typical 20-meter radiation pattern in Fig 62.

of temporary antennas can be arranged. A few of these are shown in **Figs 66** through **68**. Of all of these the rigid dipole (Fig 66) will provide the best operation and will have a pattern close to that expected from a freestanding dipole. The other two examples will be strongly affected by their close proximity to the rigging.

GROUNDING SYSTEMS

You may be sitting in the middle of a thousand miles of saltwater. This is great for propagation but you will still have to connect to that ground if you want to use a vertical. There are many possibilities, but the scheme shown in **Fig 69** is representative. First a bonding wire, or better yet a copper strap (it can be very thin!), is connected from bow-to-stern on each side, connecting the forestay, lifeline stanchions, chainplates, bow and stern pulpits and the backstay. Other bonding wires are run from the bow, stern and chainplates on both sides to a common connection at the base of the mast. The fore-and-aft bonding can be attached to the engine and to the keel bolts. The question arises: "What about electrolysis between the keel and propeller if you bond them together?" This has to be dealt with on a case-by-case basis. If your protective zincs are depleting more rapidly after you install a bonding scheme, change it by disconnecting something, the engine-shaft-propeller, for example.

Grounding will vary in every installation and has to be customized to each vessel. However, just as on shore, the better the ground system, the better the performance of the vertical!


Feed Point
Z
40 m Backstay Sloper
40 m, λ/4
Backstay Antenna
(Sloper)
Y
X

Fig 65—A 40-meter half-sloper fed at the masthead.


HOISTED DIPOLE
Pole with Dipole Taped on
Control
Line
Control
Brace
Mast

Fig 66—A dipole can be taped to a wood or bamboo pole and hoisted to the masthead with the main halyard while at anchor. It is possible to make this a multiband dipole.


Z
Sloping Dipole
Y
X
End Can Be Poled

Fig 67—One end of dipole can be attached to the main halyard and pulled up to the masthead. The bottom end of the dipole should be pulled out away from the rigging as much as possible to reduce the impact of the rigging on the impedance.


Inverted V
Z
Feed
Point
Y
X

Fig 68—The flag halyard can be used to hoist the center of an inverted V to the spreaders, or alternatively, the main halyard can be used to hoist the center of the antenna to the masthead. Interaction between the rigging and the antenna will be very pronounced and the length of the antenna will have to be adjusted on a cut-and-try basis.

Antennas for Power Boats

Powerboaters are not usually faced with the problems and opportunities created by the mast and rigging on a sailboat. A powerboat may have a small mast, but usually not on the same scale as a sailboat. Antennas for power boats have much more in common with automotive mobile operation, but with some important exceptions:

1) In an automobile, the body is usually metal and it provides a groundplane or counterpoise for a whip antenna. Most modern powerboats, however, have fiberglass hulls. These are basically insulators, and will not work as counterpoises. (On the other hand, metal-hulled power boats can provide nearly ideal grounding!)
2) A height restriction on automotive mobile whips is imposed by clearance limits on highway overpasses and also by the need to sustain wind speeds of up to 80 miles per hour on the highway.
3) In general, powerboats can have much taller antennas that can be lowered for the occasional low bridge.
4) The motion on a powerboat, especially in rough seas, can be quite severe. This places additional mechanical strain on the antennas.
5) On both powerboats and sailboats, operation in a saltwater marine environment is common. This means that a careful choice of materials must be made for the antennas to prevent corrosion and premature failure.

The problem of a ground plane for vertical antennas can be handled in much the same manner as shown in **Fig 69** for sailboats. Since there will most likely not be a large keel structure to connect to and provide a large surface area, additional copper foil can be added inside the hull to increase the counterpoise area. Because of the small area of the propeller, it may be better not to connect to the engine, but to rely instead on increasing the area of the counterpoise and operate it as a true counterpoise—that is, isolated from ground. Sometimes a number of radial wires are used for a vertical, much like that for a ground-plane antenna. This is not a very good idea unless the "wires" are actually wide copper-foil strips that can lower the Q substantially.

The problem is the high voltage present at the ends of normal ground-plane antenna radials. For a boat these radials are likely to be in close proximity to the cabin, which in turn contains both people and electronic equipment. The high potential at the ends of the radials is both a safety hazard and can result in RF coupling back into the equipment, including ham gear, navigational instruments and entertainment devices. The cook is not likely to be happy if he or she gets an RF burn after touching the galley stove! Decoupling the counterpoise from the transmission line, as discussed in Chapter 6, can be very helpful to keep RF out of other equipment.

One way to avoid many of the problems associated with grounding is to use a rigid dipole antenna. On 20 meters and higher, a rigid dipole made up from aluminum tubing, fiberglass poles or some combination of these, can be effective. As shown in **Fig 70A** the halves of the dipole can be slanted upward like rabbit ears to reduce the wingspan and increase the feed-point impedance for a better match to common coax lines. On the lower bands a pair of mobile whips can be used, as shown in Fig 70B. Home-brew coils could also be used.

For short-range communication, a relatively low dipole over saltwater can be effective. However, if long-range communication is needed, then a well-designed vertical, operating over seawater, will work much better. For these to work, of course, you must solve the ground problems associated with a vertical.



Fig 69—A typical sailboat grounding scheme.



Fig 70—At A, a rigid dipole made from aluminum tubing, fiberglass poles or a combination of these. At B, a pair of mobile whips used as a dipole.

It is not uncommon for large powerboats to have a two or three-element multiband Yagi installed on a short mast. While these can be effective, if they are not mounted high (> λ/2) they may be disappointing for longer-range communication. Over saltwater, vertical polarization is very effective for longer distances. A simpler, but well-designed, vertical system on a boat may outperform a low Yagi.

The combination of a good ground system and one of the high-quality, motor-tuned multiband mobile whips now available commercially can also be very effective.

BIBLIOGRAPHY

Source material and more extended discussions of topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2.

J. S. Belrose, “Short Antennas for Mobile Operation,” *QST*, Sep 1953.

J. S. Belrose, “Vertical J Antenna for 2 meters,” *The Canadian Amateur*, Jul/Aug 1979, pp 23-26.

J. M. Boyer, “Antenna-Transmission Line Analog,” *Ham Radio*, May 1977.

B. F. Brown, “Tennamatic: An Auto-Tuning Mobile Antenna System,” *73*, Jul 1979.

B. F. Brown, “Optimum Design of Short Coil-Loaded High-Frequency Mobile Antennas,” *ARRL Antenna Compendium Volume 1* (Newington: ARRL, 1985), p 108.

W. B. Freely, “A Two-meter J Antenna,” *QST*, Apr 1977, pp 35-36.

E. A. Laport, *Radio Antenna Engineering* (New York: McGraw-Hill Book Co., 1952), p 23.

C. E. Smith and E. M. Johnson, “Performance of Short Antennas,” Proceedings of the IRE, Oct 1947.

F. E. Terman, *Radio Engineering Handbook*, 3rd edition (New York: McGraw-Hill Book Co., 1947), p 74.

Chapter 17

Repeater Antenna Systems

There is an old adage in Amateur Radio that goes, "If your antenna did not fall down last winter, it wasn't big enough." This adage might apply to antennas for MF and HF work, but at VHF things are a bit different, at least as far as antenna size is concerned. VHF antennas are smaller than their HF counterparts, but yet the theory is the same—a dipole is a dipole, and a Yagi is a Yagi, regardless of frequency. A 144-MHz Yagi may pass as a TV antenna, but most neighbors can easily detect a radio hobbyist if a 14-MHz Yagi looms over his property.

Repeater antennas are discussed in this chapter. Because the fundamental operation of these antennas is no different than presented in earlier chapters, there is no need to delve into any exotic theory. Certain considerations must be made and certain precautions must be observed, however, since most repeater operations—amateur and commercial—take place at VHF and UHF.

Basic Concepts

The antenna is a vital part of any repeater installation. Because the function of a repeater is to extend the range of communications between mobile and portable stations, the repeater antenna should be installed in the best possible location to provide the desired coverage. This usually means getting the antenna as high above average terrain as possible. In some instances, a repeater may need to have coverage only in a limited area or direction. When this is the case, antenna installation requirements will be completely different, with certain limits being set on height, gain and power.

Horizontal and Vertical Polarization

Until the upsurge in FM repeater activity in the 1970s, most antennas used in amateur VHF work were horizontally polarized. These days, very few repeater groups use horizontal polarization. (One of the major reasons for using horizontal polarization is to allow separate repeaters to share the same input and/or output frequencies with closer-than-normal geographical spacing.) The vast majority of VHF and UHF repeaters use vertically polarized antennas, and all the antennas discussed in this chapter are of that type.

Transmission Lines

Repeaters provide the first venture into VHF and UHF work for many amateurs. The uninitiated may not be aware that the transmission lines used at VHF become very important because feed-line losses increase with frequency.

The characteristics of feed lines commonly used at VHF are discussed in Chapter 24, Transmission Lines. Although information is provided there for small-diameter RG-58 and RG-59 coaxes, these should not be used except for very short feed lines (25 feet or less). These cables are very lossy at VHF. In addition, the losses can be much higher if fittings and connections are not carefully installed.

The differences in loss between solid-polyethylene dielectric types (RG-8 and RG-11) and those using foam polyethylene are significant at VHF and UHF. If you can afford the line with the least loss, buy it.

If you must bury coaxial cable, check with the cable manufacturer before doing so. Many popular varieties of coaxial cable should not be buried, since the dielectric can become contaminated from moisture and soil chemicals. Some coaxial cables are labeled as non-contaminating. Such a label is the best way to be sure your cable can be buried without damage.

Matching

Losses are lowest in transmission lines that are matched to their characteristic impedances. If there is a mismatch at the end of the line, the losses increase. The *only way* to reduce the SWR on a transmission line is by matching the line *at the antenna*. Changing the length of a transmission line does not reduce the SWR. The SWR is established by the impedance of the line and the impedance of the antenna, so matching must be done at the antenna end of the line.

The importance of matching, so far as feed-line losses are concerned, is sometimes overstressed. But under some conditions, it is necessary to minimize feed-line losses related to SWR if repeater performance is to be consistent. It is important to keep in mind that most VHF/UHF equipment is designed to operate into a 50-Ω load. The output circuitry will not be loaded properly if connected to a mismatched line. This leads to a loss of power, and in some cases, damage to the transmitter.

Repeater Antenna System Design

Choosing a repeater or remote-base antenna system is as close as most amateurs come to designing a commercial-grade antenna system. The term *system* is used because most repeaters utilize not only an antenna and a transmission line, but also include duplexers, cavity filters, circulators or isolators in some configuration. Assembling the proper combination of these items in constructing a reliable system is both an art and a science. In this section prepared by Domenic Mallozzi, N1DM, the functions of each component in a repeater antenna system and their successful integration are discussed. While every possible complication in constructing a repeater cannot be foreseen at the outset, this discussion should serve to steer you along the right lines in solving any problems encountered.

COMPUTING THE COVERAGE AREA FOR A REPEATER

Modern computer programs can show the coverage of a repeater using readily available topographic data from the Internet. In Chapter 3, The Effects of Ground, we described the *MicroDEM* program supplied on the CD-ROM accompanying this book. Dr Peter Guth, the author of *MicroDEM*, built into it the ability to generate terrain profiles that can be used with ARRL's *HFTA* (HF Terrain Assessment) program (also included on the CD-ROM).

MicroDEM has a wide range of capabilities beyond simply making terrain profiles. It can do *LOS* (line of sight) computations, based on visual or radio-horizon considerations. **Fig 1** shows a *MicroDEM* map for the area around Glastonbury, Connecticut. This is somewhat hilly terrain, and as a result the coverage for a repeater placed here on a 30-meter (100-foot) high tower would be somewhat spotty. Fig 1 shows a "Viewshed" on the map, in the form of the white terrain profile strokes in 5° increments around the tower.



Fig 1—*MicroDEM* topographic map, showing the coverage for a repeater placed on a 30-meter high tower in Glastonbury, CT. The white radial lines indicate the coverage in 5° increments of azimuth around the tower. The range circles are 1000 meters apart.


LOS: vert exag 27.8
N 41°41.106' W 72°29.050'
N 41°41.792' W 72°23.289'
meters
260
250
240
230
220
210
200
190
180
170
160
150
0
1
2
3
4
5
6
7
8 km
N 41°41.603' W 72°24.879' z=180.8 m

Fig 2—An "LOS" (line of sight) profile at an azimuth of 80° from the tower in Fig 1. The light-gray portions of the terrain profile are visible from the top of the tower, while the dark portions are blocked by the terrain.

Fig 2 shows the LOS for an azimuth of 80°, from a 30-meter high tower out to a distance of 8000 meters. The light-shaded areas on the profile are those that are illuminated directly by the antenna on the tower, while the dark portions of the profile are those that cannot be seen directly from the tower. This profile assumes that the mobile station is 2 meters high—the height of a 6-foot high person with a handheld radio.

The terrain at an 80° azimuth allows direct radio view from the top of the tower out to about 1.8 km. From here, the downslope prevents direct view until about 2.5 km, where the terrain is briefly visible again from several hundred meters, disappearing from radio view until about 2.8 km, after which it becomes visible until about 3.6 km. Note that other than putting the repeater antenna on a higher tower, there is nothing that can be done to improve repeater coverage over this hilly terrain, although knife-edge diffraction off the hill tops will help fill in coverage gaps.

The Repeater Antenna

The most important part of the system is the antenna itself. As with any antenna, it must radiate and collect RF energy as efficiently as possible. Many repeaters use omnidirectional antennas, but this is not always the best choice. For example, suppose a group wishes to set up a repeater to cover towns A and B and the interconnecting state highway shown in **Fig 3**. The available repeater site is marked on the map. No coverage is required to the west or south, or over the ocean. If an omnidirectional antenna is used in this case, a significant amount of the radiated signal goes in undesired directions. By using an antenna with a cardioid pattern, as shown in Fig 1, the coverage is concentrated in the desired directions. The repeater will be more effective in these locations, and signals from low-power portables and mobiles will be more reliable.

In many cases, antennas with special patterns are more expensive than omnidirectional models. This is an obvious consideration in designing a repeater antenna system. Over terrain where coverage may be difficult in some direction from the repeater site, it may be desirable to skew the antenna pattern in that direction. This can be accomplished by using a phased-vertical array or a com-



Fig 3—There are many situations where equal repeater coverage is not desired in all directions from the "machine." One such situation is shown here, where the repeater is needed to cover only towns A and B and the interconnecting highway. An omnidirectional antenna would provide coverage in undesired directions, such as over the ocean. The broken line shows the radiation pattern of an antenna that is better suited to this circumstance.



Fig 4—The "keyhole" horizontal radiation pattern at A is generated by the combination of phased Yagis and vertical elements shown at B. Such a pattern is useful in overcoming coverage blockages resulting from local terrain features. (*Based on a design by Decibel Products, Inc.*)



Fig 5—Vertical-beam downtilt is another form of radiation-pattern distortion useful for improving repeater coverage. This technique can be employed in situations where the repeater station is at a greater elevation than the desired coverage area, when a high-gain omnidirectional antenna is used. Pattern A shows the normal vertical-plane radiation pattern of a high-gain omnidirectional antenna with respect to the desired coverage area (the town). Pattern B shows the pattern tilted down, and the coverage improvement is evident.

bination of a Yagi and a phased vertical to produce a "keyhole" pattern. See **Fig 4**.

Repeaters are common on 440 MHz and above, and many groups invest in high-gain omnidirectional antennas. A consequence of getting high gain from an omnidirectional antenna is vertical beamwidth reduction. In most cases, these antennas are designed to radiate their peak gain at the horizon, resulting in optimum coverage when the antenna is located at a moderate height over normal terrain. Unfortunately, in cases where the antenna is located at a very high site (overlooking the coverage area) this may not be the most desirable pattern. The vertical pattern of the antenna can be tilted downward, however, to facilitate coverage of the desired area. This is called *vertical-beam downtilt*.

An example of such a situation is shown in **Fig 5**. The repeater site overlooks a town in a valley. A 450-MHz repeater is needed to serve low-power portable and mobile stations. Constraints on the repeater dictate the use of an antenna with a gain of 11 dBi. (An omnidirec-



Fig 6—Vertical-beam downtilt can be facilitated by inserting 52-Ω delay lines in series with the 75-Ω feed lines to the collinear elements of an omnidirectional antenna. The delay lines to each element are progressively longer so the phase shift between elements is uniform. Odd $^1/_4$-λ coaxial transformers are used in the main (75-Ω) feed system to match the dipole impedances to the driving point. Tilting the vertical beam in this way often produces minor lobes in the vertical pattern that do not exist when the elements are fed in phase.

tional antenna with this gain has a vertical beamwidth of approximately 6°.) If the repeater antenna has its peak gain at the horizon, a major portion of the transmitted signal and the best area from which to access the repeater exists *above* the town. By tilting the pattern down 3°, the peak radiation will occur in the town.

Vertical-beam downtilt is generally produced by feeding the elements of a collinear vertical array slightly out of phase with each other. Lee Barrett, K7NM, showed such an array in *Ham Radio* magazine. (See the Bibliography at the end of this chapter.) Barrett gives the geometry and design of a four-pole array with progressive phase delay, and a computer program to model it. The technique is shown in **Fig 6**, with a free-space elevation plot showing downtilting in **Fig 7**.

Commercial antennas are sometimes available (at extra cost) with built-in downtilt characteristics. Before ordering such a commercial antenna, make sure that you really require it—they generally are special-order items and are not returnable.

There are disadvantages to improving coverage by means of vertical-beam downtilt. When compared to a standard collinear array, an antenna using vertical-beam downtilt will have somewhat greater extraneous lobes in the vertical pattern, resulting in reduced gain (usually less than 1 dB). Bandwidth is also slightly reduced. The reduction in gain, when combined with the downtilt characteristic, results in a reduction in total coverage area. These trade-offs, as well as the increased cost of a commercial antenna with downtilt, must be compared to the improvement in total performance in a situation where vertical-beam downtilt is contemplated.



Fig 7—Free-space elevation-plane patterns showing downtilting that results from progressive phase shifts for the feed currents for the dipole in Fig 6.

Top Mounting and Side Mounting

Amateur repeaters often share towers with commercial and public service users. In many of these cases, other antennas are at the top of the tower, so the amateur antenna must be side mounted. A consequence of this arrangement is that the free-space pattern of the repeater antenna is distorted by the tower. This effect is especially noticeable when an omnidirectional antenna is side mounted on a structure.

The effects of supporting structures are most pronounced at close antenna spacings to the tower and with large support dimensions. The result is a measurable increase in gain in one direction and a partial null in the other direction (sometimes 15 dB deep). The shape of the supporting structure also influences pattern distortion. Many antenna manufacturers publish radiation patterns showing the effect of side mounting antennas in their catalogs.

Side mounting is not always a disadvantage. In cases where more (or less) coverage is desired in one direction, the supporting structure can be used to advantage. If pattern distortion is not acceptable, a solution is to mount antennas around the perimeter of the structure and feed them with the proper phasing to synthesize an omnidirectional pattern. Many manufacturers make antennas to accommodate such situations.

The effects of different mounting locations and arrangements can be illustrated with an array of exposed dipoles, **Fig 8**. Such an array is a very versatile antenna because, with simple rearrangement of the elements, it can develop either an omnidirectional pattern or an offset pattern. Drawing A of Fig 8 shows a basic collinear array of four vertical ½-λ elements. The vertical spacing between adjacent elements is 1 λ. All elements are fed in phase. If this array is placed in the clear and supported by a nonconducting mast, the calculated radiation resistance of each dipole element is on the order of 63 Ω. If the feed line is completely decoupled, the resulting azimuth pattern is omnidirectional. The vertical-plane pattern is shown in **Fig 9**.

Fig 8B shows the same array in a side-mounting arrangement, at a spacing of ¼ λ from a conducting mast. In this mounting arrangement, the mast takes on the role of a reflector, producing an F/B on the order of 5.7 dB. The azimuth pattern is shown in **Fig 10**. The vertical pattern is not significantly different from that of Fig 9, except the four small minor lobes (two on either side of the vertical axis) tend to become distorted. They are not as "clean," tending to merge into one minor lobe at some mast heights. This apparently is a function of currents in the supporting mast. The proximity of the mast also alters the feed-point impedance. For elements that are resonant in the configuration of Fig 8A, the calculated impedance in the arrangement of Fig 8B is in the order of 72 + *j* 10 Ω.

If side mounting is the only possibility and an omnidirectional pattern is required, the arrangement of Fig 8C may be used. The calculated azimuth pattern takes on a slight cloverleaf shape, but is within 1.5 dB of being circular. However, gain performance suffers, and the idealized vertical pattern of Fig 9 is not achieved. See **Fig 11**. Spacings other than $^1/_4$-λ from the mast were not investigated.

One very important consideration in side mounting an antenna is mechanical integrity. As with all repeater components, reliability is of great importance. An antenna hanging by the feed line and banging against the tower provides far from optimum performance and reliability. Use a mount that is appropriately secured to the tower and the antenna. Also use good hardware, preferably stainless steel (or bronze). If your local hardware store does not carry stainless steel hardware, try a boating supplier.



Fig 8—Various arrangements of exposed dipole elements. At A is the basic collinear array of four elements. B shows the same elements mounted on the side of a mast, and C shows the elements in a side-mounted arrangement around the mast for omnidirectional coverage. See text and Figs 9 through 11 for radiation-pattern information.



Fig 9—Calculated vertical-plane pattern of the array of Fig 8A, assuming a nonconducting mast support and complete decoupling of the feeder. In azimuth the array is omnidirectional. The calculated gain of the array is 8.6 dBi at 0° elevation; the –3 dB point is at 6.5°.



Fig 10—Calculated azimuth pattern of the side-mounted array of Fig 8B, assuming $^1/_4$-λ spacing from a 4-inch mast. The calculated gain in the favored direction, away from the mast and through the elements, is 10.6 dBi.



Fig 11—Calculated vertical pattern of the array of Fig 8C, assuming $^1/_4$-λ element spacing from a 4-inch mast. The azimuth pattern is circular within 1.5 dB, and the calculated gain is 4.4 dBi.

Be certain that the feed line is properly supported along its length. Long lengths of cable are subject to contraction and expansion with temperature from season to season, so it is important that the cable not be so tight that contraction causes it to stress the connection at the antenna. This can cause the connection to become intermittent (and noisy) or, at worst, an open circuit. This is far from a pleasant situation if the antenna connection is 300 feet up a tower, and it happens to be the middle of the winter!

Effects of Other Conductors

Feed-line proximity and tower-access ladders or cages also have an effect on the radiation patterns of side-mounted antennas. This subject was studied by Connolly and Blevins, and their findings are given in *IEEE Conference Proceedings* (see the Bibliography at the end of this chapter). Those considering mounting antennas on air-conditioning evaporators or maintenance penthouses on commercial buildings should consult this article. It gives considerable information on the effects of these structures on both unidirectional and omnidirectional antennas.

Metallic guy wires also affect antenna radiation patterns. Yang and Willis studied this and reported the results in *IRE Transactions on Vehicular Communications*. As expected, the closer the antenna is to the guy wires, the greater the effect on the radiation patterns. If the antennas are near the point where the guy wires meet the tower, the effect of the guy wires can be minimized by breaking them up with insulators every 0.75 λ for 2.25 λ to 3.0 λ.

ISOLATION REQUIREMENTS IN REPEATER ANTENNA SYSTEMS

Because repeaters generally operate in full *duplex* (the transmitter and receiver operate simultaneously), the antenna system must act as a filter to keep the transmitter from blocking the receiver. The degree to which the transmitter and receiver must be isolated is a complex problem. It is quite dependent on the equipment used and the difference in transmitter and receiver frequencies (offset). Instead of going into great detail, a simplified example can be used for illustration.

Consider the design of a 144-MHz repeater with a 600-kHz offset. The transmitter has an RF output power of 10 watts, and the receiver has a squelch sensitivity of 0.1 µV. This means there must be at least 1.9×10^{-16} watts at the 52-Ω receiver-antenna terminals to detect a signal. If both the transmitter and receiver were on the same frequency, the isolation (attenuation) required between the transmitter and receiver antenna jacks to keep the transmitter from activating the receiver would be

$$\text{Isolation} = 10 \log \frac{10 \text{ watts}}{1.9 \times 10^{-16} \text{ watts}} = 167 \text{ dB}$$

Obviously there is no need for this much attenuation, because the repeater does not transmit and receive on the same frequency.

If the 10-watt transmitter has noise 600 kHz away from the carrier frequency that is 45 dB below the carrier power, that 45 dB can be subtracted from the isolation requirement. Similarly, if the receiver can detect a 0.1 µV on-frequency signal in the presence of a signal 600 kHz away that is 40 dB greater than 0.1 µV, this 40 dB can also be subtracted from the isolation requirement. Therefore, the isolation requirement is

$$167 \text{ dB} - 45 \text{ dB} - 40 \text{ dB} = 82 \text{ dB}$$

Other factors enter into the isolation requirements as well. For example, if the transmitter power is increased by 10 dB (from 10 to 100 watts), this 10 dB must be added to the isolation requirement. Typical requirements for 144- and 440-MHz repeaters are shown in **Fig 12**.

Obtaining the required isolation is the first problem to be considered in constructing a repeater antenna system. There are three common ways to obtain this isolation:

1) Physically separate the receiving and transmitting antennas so the combination of path loss for the spacing and the antenna radiation patterns results in the required isolation.
2) Use a combination of separate antennas and high-Q filters to develop the required isolation. (The high-Q filters serve to reduce the physical distance required between antennas.)
3) Use a combination filter and combiner system to



Fig 12—Typical isolation requirements for repeater transmitters and receivers operating in the 132-174 MHz band (Curve A), and the 400-512 MHz band (Curve B). Required isolation in dB is plotted against frequency separation in MHz. These curves were developed for a 100-W transmitter. For other power levels, the isolation requirements will differ by the change in decibels relative to 100 W. Isolation requirements will vary with receiver sensitivity. (The values plotted were calculated for transmitter-carrier and receiver-noise suppression necessary to prevent more than 1 dB degradation in receiver 12-dB SINAD sensitivity.)

allow the transmitter and receiver to share one antenna. Such a filter and combiner is called a *duplexer*.

Repeaters operating on 28 and 50 MHz generally use separate antennas to obtain the required isolation. This is largely because duplexers in this frequency range are both large and very expensive. It is generally less expensive to buy two antennas and link the sites by a committed phone line or an RF link than to purchase a duplexer. At 144 MHz and higher, duplexers are more commonly used. Duplexers are discussed in greater detail in a later section.

Separate Antennas

Receiver desensing (gain limiting caused by the presence of a strong off-frequency signal) can be reduced, and often eliminated, by separation of the transmitting and receiving antennas. Obtaining the 55 to 90 dB of isolation required for a repeater antenna system requires separate antennas to be spaced a considerable distance apart (in wavelengths).

Fig 13 shows the distances required to obtain specific values of isolation for vertical dipoles having horizontal separation (at A) and vertical separation (at B). The isolation gained by using separate antennas is subtracted from the total isolation requirement of the system. For example, if the transmitter and receiver antennas for a 450-MHz repeater are separated horizontally by 400 feet, the total isolation requirement in the system is reduced by about 64 dB.



Fig 13—At A, the amount of attenuation (isolation) provided by horizontal separation of vertical dipole antennas. At B, isolation afforded by vertical separation of vertical dipoles.

Note from Fig 13B that a vertical separation of only about 25 feet also provides 64 dB of isolation. Vertical separation yields much more isolation than does horizontal separation. Vertical separation is also more practical than horizontal, since only a single support is required.

An explanation of the significant difference between the two graphs is in order. The vertical spacing requirement for 60 dB attenuation (isolation) at 150 MHz is about 43 feet. The horizontal spacing for the same isolation level is on the order of 700 feet. **Fig 14** shows why this difference exists. The radiation patterns of the antennas at A overlap; each antenna has gain in the direction of the other. The path loss between the antennas is given by

$$\text{Path loss (dB)} = 20 \log \frac{4\pi d}{\lambda} \qquad \text{(Eq 1)}$$

where

d = distance between antennas

λ = wavelength, in the same units as d.

The isolation between the antennas in Fig 14A is the path loss less the antenna gains. Conversely, the antennas at B share pattern nulls, so the isolation is the path loss added to the depth of these nulls. This significantly reduces the spacing requirement for vertical sepa-



Fig 14—A relative representation of the isolation advantage afforded by separating antennas horizontally (A) and vertically (B) is shown. A great deal of isolation is provided by vertical separation, but horizontal separation requires two supports and much greater distance to be as effective. Separate-site repeaters (those with transmitter and receiver at different locations) benefit much more from horizontal separation than do single-site installations.

ration. Because the depth of the pattern nulls is not infinite, some spacing is required. Combined horizontal and vertical spacing is much more difficult to quantify because the results are dependent on both radiation patterns and the positions of the antennas relative to each other.

Separate antennas have one major disadvantage: They create disparity in transmitter and receiver coverage. For example, say a 50-MHz repeater is installed over average terrain with the transmitter and repeater separated by 2 miles. If both antennas had perfect omnidirectional coverage, the situation depicted in **Fig 15** would exist. In this case, stations able to hear the repeater may not be able to access it, and vice versa. In practice, the situation can be considerably worse. This is especially true if the patterns of both antennas are not omnidirectional. If this disparity in coverage cannot be tolerated, the solution involves skewing the patterns of the antennas until their coverage areas are essentially the same.

Cavity Resonators

As just discussed, receiver desensing can be reduced by separating the transmitter and receiver antennas. But the amount of transmitted energy that reaches the receiver input must often be decreased even farther. Other nearby transmitters can cause desensing as well. A *cavity resonator* (cavity filter) can be helpful in solving these problems. When properly designed and constructed, this type of resonator has very high Q. A commercially made cavity is shown in **Fig 16**.

A cavity resonator placed in series with a transmission line acts as a band-pass filter. For a resonator to operate in series, it must have input and output coupling loops (or probes). A cavity resonator can also be connected across (in parallel with) a transmission line. The cavity then acts as a band-reject (notch) filter, greatly attenuating energy at the frequency to which it is tuned. Only one coupling loop or probe is required for this method of filtering. This type of cavity could be used in the receiver line to “notch” the transmitter signal. Several cavities can be connected in series or parallel to increase the attenuation in a given configuration. The graphs of **Fig 17** show the attenuation of a single cavity (A) and a pair of cavities (B).

The only situation in which cavity filters would not help is the case where the off-frequency noise of the transmitter was right on the receiver frequency. With cavity resonators, an important point to remember is that addition of a cavity across a transmission line may change the impedance of the system. This change can be compensated by adding tuning stubs along the transmission line.

Duplexers

The material in this section was prepared by Domenic Mallozzi, N1DM. Most amateur repeaters in the 144-, 220- and 440-MHz bands use duplexers to obtain the necessary transmitter to receiver isolation. Duplexers have been commonly used in commercial repeaters for many years. The duplexer consists of two high-Q filters. One filter is used in the feed line from the transmitter to the antenna, and another between the antenna and the receiver. These filters must have low loss at the frequency to which they are tuned while having very high attenuation at the surrounding frequencies. To meet the high attenuation requirements at frequencies within as little as 0.4% of the frequency to which they are tuned, the filters usually take the form of cascaded transmission-line cavity filters. These are either band-pass filters, or band-pass filters with a rejection notch. (The rejection notch is tuned to the center frequency of the other filter.) The number of cascaded filter sections is determined by the frequency separation and the ultimate attenuation requirements.


○ = Transmitter Antenna
+ = Receiver Antenna
/// = Receiver Coverage Area
\\\ = Transmitter Coverage Area
XXX = Mutual Coverage Area

Fig 15—Coverage disparity is a major problem for separate-site repeater antennas. The transmitter and receiver coverage areas overlap, but are not entirely mutually inclusive. Solving this problem requires a great deal of experimentation, as many factors are involved. Among these factors are terrain features and distortion of the antenna radiation patterns from supports.



Fig 16—A coaxial cavity filter of the type used in many amateur and commercial repeater installations. Center-conductor length (and thus resonant frequency) is varied by adjustment of the knob (top).



Fig 17—Frequency response curves for a single cavity (A) and two cavities cascaded (B). These curves are for cavities with coupling loops, each having an insertion loss of 0.5 dB. (The total insertion loss is indicated in the body of each graph.) Selectivity will be greater if lighter coupling (greater insertion loss) can be tolerated.

Duplexers for the amateur bands represent a significant technical challenge, because in most cases amateur repeaters operate with significantly less frequency separation than their commercial counterparts. Information on home construction of duplexers is presented in a later section of this chapter. Many manufacturers market high-quality duplexers for the amateur frequencies.

Duplexers consist of very high-Q cavities whose resonant frequencies are determined by mechanical components, in particular the tuning rod. **Fig 18** shows the cutaway view of a typical duplexer cavity. The rod is usually made of a material that has a limited thermal expansion coefficient (such as Invar). Detuning of the cavity by environmental changes introduces unwanted losses in the antenna system. An article by Arnold in *Mobile Radio Technology* considered the causes of drift in the


Locknut
Connector
Coupling Loops
Tuning Rod
Center Conductor (Fixed Section)
λ/4
Center Conductor (Telescoping Section)

Fig 18—Cutaway view of a typical cavity. Note the relative locations of the coupling loops to each other and to the center conductor of the cavity. A locknut is used to prevent movement of the tuning rod after adjustment.

cavity (see the Bibliography at the end of this chapter). These can be broken into four major categories.

1) Ambient temperature variation (which leads to mechanical variations related to the thermal expansion coefficients of the materials used in the cavity).
2) Humidity (dielectric constant) variation.
3) Localized heating from the power dissipated in the cavity (resulting from its insertion loss).
4) Mechanical variations resulting from other factors (vibration, etc).

In addition, because of the high-Q nature of these cavities, the insertion loss of the duplexer increases when the signal is not at the peak of the filter response. This means, in practical terms, that less power is radiated for a given transmitter output power. Also, the drift in cavities in the receiver line results in increased system noise figure, reducing the sensitivity of the repeater.

As the frequency separation between the receiver and the transmitter decreases, the insertion loss of the duplexer reaches certain practical limits. At 144 MHz, the minimum insertion loss for 600 kHz spacing is 1.5 dB per filter.

Testing and using duplexers requires some special considerations (especially as frequency increases). Because duplexers are very high-Q devices, they are very sensitive to the termination impedances at their ports. A high SWR on any port is a serious problem, because the apparent insertion loss of the duplexer will increase, and the isolation may appear to decrease. Some have found that when duplexers are used at the limits of their isolation capabilities, a small change in antenna SWR is enough to cause receiver desensitization. This occurs most often under ice-loading conditions on antennas with open-wire phasing sections.

The choice of connectors in the duplexer system is important. BNC connectors are good for use below 300 MHz. Above 300 MHz, their use is discouraged because even though many types of BNC connectors work well up to 1 GHz, older style standard BNC connectors are inadequate at UHF and above. Type N connectors should be used above 300 MHz. It is false economy to use marginal quality connectors. Some commercial users have reported deteriorated isolation in commercial UHF repeaters when using such connectors. The location of a bad connector in a system is a complicated and frustrating process. Despite all these considerations, the duplexer is still the best method for obtaining isolation in the 144- to 925 MHz range.

ADVANCED TECHNIQUES

As the number of available antenna sites decreases and the cost of various peripheral items (such as coaxial cable) increases, amateur repeater groups are required to devise advanced techniques if repeaters are to remain effective. Some of the techniques discussed here have been applied in commercial services for many years, but until recently have not been economically justified for amateur use.

One technique worth consideration is the use of *cross-band couplers*. To illustrate a situation where a cross-band coupler would be useful, consider the following example. A repeater group plans to install 144- and 902-MHz repeaters on the same tower. The group intends to erect both antennas on a horizontal cross arm at the 325-foot level. A 325-foot run of $^7/_8$-inch Heliax costs approximately $2000. If both antennas are to be mounted at the top of the tower, the logical approach would require two separate feed lines. A better solution involves the use of a single feed line for both repeaters, along with a cross-band coupler at each end of the line.

The use of the cross-band coupler is shown in **Fig 19**. As the term implies, the coupler allows two signals on different bands to share a common transmission line. Such couplers cost approximately $300 each. In our hypothetical example, this represents a saving of $1400 over the cost of using separate feed lines. But, as with all compromises, there are disadvantages. Cross-band cou-



Fig 19—Block diagram of a system using cross-band couplers to allow the use of a single feed line for two repeaters. If the feeder to the antenna location is long (more than 200 feet or so), cross-band couplers may provide a significant saving over separate feed lines, especially at the higher amateur repeater frequencies. Cross-band couplers cannot be used with two repeaters on the same band.

plers have a loss of about 0.5 dB per unit. Therefore, the pair required represents a loss of 1.0 dB in *each* transmission path. If this loss can be tolerated, the cross-band coupler is a good solution.

Cross-band couplers do not allow two repeaters *on the same band* to share a single antenna and feed line. As repeater sites and tower space become more scarce, it may be desirable to have two repeaters on the same band share the same antenna. The solution to this problem is the use of a *transmitter multicoupler*. The multicoupler is related to the duplexers discussed earlier. It is a cavity filter and combiner that allows multiple transmitters and receivers to share the same antenna. This is a common commercial practice. A block diagram of a multicoupler system is shown in **Fig 20**.



Fig 20—Block diagram of a system using a transmitter multicoupler to allow a single feed line and antenna to be used by two repeaters on one band. The antenna must be designed to operate at all frequencies that the repeaters utilize. More than two repeaters can be operated this way by using a multicoupler with the appropriate number of input ports.

The multicoupler, however, is a very expensive device, and has the disadvantage of even greater loss per transmission path than the standard duplexer. For example, a well-designed duplexer for 600 kHz spacing at 146 MHz has a loss per transmission path of approximately 1.5 dB. A four-channel multicoupler (the requirement for two repeaters) has an insertion loss per transmission path on the order of 2.5 dB or more. Another constraint of such a system is that the antenna must present a good match to the transmission line at all frequencies on which it will be used (both transmitting and receiving). This becomes difficult for the system with two repeaters operating at opposite ends of a band.

If you elect to purchase a commercial base-station antenna that requires you to specify a frequency to which the antenna must be tuned, be sure to indicate to the manufacturer the intended use of the antenna and the frequency extremes. In some cases, the only way the manufacturer can accommodate your request is to provide an antenna with some vertical-beam uptilt at one end of the band and some downtilt at the other end of the band. In the case of antennas with very high gain, this in itself may become a serious problem. Careful analysis of the situation is necessary before assembling such a system.

Diversity Techniques for Repeaters

Mobile flutter, "dead spots" and similar problems are a real problem for the mobile operator. The popularity of hand-held transceivers using low power and mediocre antennas causes similar problems. A solution to these difficulties is the use of some form of *diversity reception*. Diversity reception works because signals do not fade at the same rate when received by antennas at different locations (space diversity) or of different polarizations (polarization diversity).

Repeaters with large transmitter coverage areas often have difficulty "hearing" low power stations in peripheral areas or in dead spots. Space diversity is especially useful in such a situation. Space diversity utilizes separate receivers at different locations that are linked to the repeater. The repeater uses a circuit called a *voter* that determines which receiver has the best signal, and then selects the appropriate receiver from which to feed the repeater transmitter. This technique is helpful in urban areas where shadowing from large buildings and bridges causes problems. Space-diversity receiving, when properly executed, can give excellent results. But with the improvement come some disadvantages: added initial cost, maintenance costs, and the possibility of failure created by the extra equipment required. If installed and maintained carefully, problems are generally minimal.

A second improvement technique is the use of *circularly polarized* repeater antennas. This technique has been used in the FM broadcast field for many years, and has been considered for use in the mobile telephone service as well. Some experiments by amateurs have proved very promising, as discussed by Pasternak and Morris (see the Bibliography at the end of this chapter).

The improvement afforded by circular polarization is primarily a reduction in *mobile flutter*. The flutter on a mobile signal is caused by reflections from large buildings (in urban settings) or other terrain features. These reflections cause measurable polarization shifts, sometimes to the point where a vertically polarized signal at the transmitting site may appear to be primarily horizontally polarized after reflection.

A similar situation results from *multipath propagation*, where one or more reflected signals combine with the direct signal at the repeater, having varying effects on the signal. The multipath signal is subjected to large amplitude and phase variations at a relatively rapid rate.

In both of the situations described here, circular polarization can offer considerable improvement. This is because circularly polarized antennas respond equally to all linearly polarized signals, regardless of the plane of polarization. At this writing, there are no known sources of commercial circularly polarized omnidirectional antennas for the amateur bands. Pasternak and Morris describe a circularly polarized antenna made by modifying two commercial four-pole arrays.

EFFECTIVE ISOTROPIC RADIATED POWER (EIRP)

It is useful to know effective isotropic radiated power (EIRP) in calculating the coverage area of a repeater. The FCC formerly required EIRP to be entered in the log of every amateur repeater station. Although logging EIRP is no longer required, it is still useful to have this information on hand for repeater-coordination purposes and so system performance can be monitored periodically.

Calculation of EIRP is straightforward. The PEP output of the transmitter is simply multiplied by the gains and losses in the transmitting antenna system. (These gains and losses are best added or subtracted in decibels and then converted to a multiplying factor.) The following worksheet and example illustrates the calculations.

Feed-line loss _____ dB
Duplexer loss _____ dB
Isolator loss _____ dB
Cross-band coupler loss _____ dB
Cavity filter loss _____ dB

Total losses (L) _____ dB

G (dB) = antenna gain (dBi) –L

where G = antenna system gain. (If antenna gain is specified in dBd, add 2.14 dB to obtain the gain in dBi.)

$M = 10^{G/10}$

where M = multiplying factor

EIRP (watts) = transmitter output (PEP)×M

Example

A repeater transmitter has a power output of 50 W PEP (50-W FM transmitter). The transmission line has 1.8 dB loss. The duplexer used has a loss of 1.5 dB, and a circulator on the transmitter port has a loss of 0.3 dB. There are no cavity filters or cross-band couplers in the system. Antenna gain is 5.6 dBi.

Feed-line loss	1.8 dB
Duplexer loss	1.5 dB
Isolator loss	0.3 dB
Cross-band coupler loss	0 dB
Cavity filter loss	0 dB
Total losses (L)	3.6 dB

Antenna system gain in dB = G = antenna gain (dBi) –L

G = 5.6 dBi – 3.6 dB = 2 dB

Multiplying factor = $M = 10^{G/10}$

$M = 10^{2/10} = 1.585$

EIRP (watts) = transmitter output (PEP) × M

EIRP = 50 W × 1.585 = 79.25 W

If the antenna system is lossier than this example, G may be *negative*, resulting in a multiplying factor less than one. The result is an EIRP that is less than the transmitter output power. This situation can occur in practice, but for obvious reasons is not desirable.

Assembling a Repeater Antenna System

This section will aid you in planning and assembling your repeater antenna system. The material was prepared by Domenic Mallozzi, N1DM. Consult Chapter 23, Radio Wave Propagation, for information on propagation for the band of your interest.

First, a repeater antenna selection checklist such as this will help you in evaluating the antenna system for your needs.

Gain needed ________ dBi
Pattern required ________ Omnidirectional
________ Offset
________ Cardioidal
________ Bidirectional
________ Special pattern (specify)
____
Mounting ________ Top of tower
________ Side of tower

(Determine effects of tower on pattern. Is the result consistent with the pattern required?)

Is downtilt required? ________ Yes
________ No
Type of RF connector ________ UHF
________ N
________ BNC
________ Other (specify)
Size (length) ________
Weight ________
Maximum cost $_______

Table 1 (see next page) has been compiled to provide general information on commercial components available for repeater and remote-base antenna systems. The various components are listed in a matrix format by manufacturer, for equipment designed to operate in the various amateur bands. See Chapter 21, Antenna Products Suppliers, for further information for these components. Although every effort has been made to make this data complete, the ARRL is not responsible for omissions or errors. The listing of a product in Table 1 does not constitute an endorsement by ARRL. Manufacturers are urged to contact the editors with updating information.

Even though almost any antenna can be used for a repeater, the companies indicated in the *Antennas* column in Table 1 are known to have produced heavy-duty antennas to commercial standards for repeater service. Many of these companies offer their antennas with special features for repeater service (such as vertical-beam downtilt). It is best to obtain catalogs of current products from the manufacturers listed, both for general information and to determine which special options are available on their products.

A 144 MHz Duplexer

Obtaining sufficient isolation between the transmitter and receiver of a repeater can be difficult. Many of the solutions to this problem compromise receiver sensitivity or transmitter power output. Other solutions create an imbalance between receiver and transmitter coverage areas. When a duplexer is used, insertion loss is the compromise. But a small amount of insertion loss is more than offset by the use of one antenna for both the transmitter and receiver. Using one antenna assures equal antenna patterns for both transmitting and receiving, and reduces cost, maintenance and mechanical complexity.

As mentioned earlier in this chapter, duplexers may be built in the home workshop. Bob Shriner, WA0UZO, presented a small, mechanically simple duplexer for low-power applications in April 1979 *QST*. Shriner's design is unique, as the duplexer cavities are constructed of circuit-board material. Low cost and simplicity are the result, but with a trade-off in performance. A silver-plated version of Shriner's design has an insertion loss of approximately 5 dB at 146 MHz. The loss is greater if the copper is not plated, and increases as the inner walls of the cavities tarnish.

This duplexer construction project by John Bilodeau, W1GAN, represents an effective duplexer. The information originally appeared in July 1972 *QST*. It is a time-proven project used by many repeater groups, and can be duplicated relatively easily. Its insertion loss is just 1.5 dB.

Fig 21 will help you visualize the requirements for a duplexer, which can be summed up as follows. The duplexer must attenuate the transmitter carrier to avoid overloading the receiver and thereby reducing its sensitivity. It must also attenuate any noise or spurious frequencies from the transmitter on or near the receiver frequency. In addition, a duplexer must provide a proper impedance match between transmitter, antenna, and receiver.

Table 1

Product Matrix Showing Repeater Equipment and Manufacturer by Frequency Band

	Antennas							*Duplexers*				*Cavity Filters*			
Source	*28*	*50*	*144*	*220*	*450*	*902*	*1296*	*144*	*220*	*450*	*902*	*144*	*220*	*450*	*902*
Austin	S	S	S	S	S	S	S								
Celwave	C	C	C	C	C	C		C	C	C	C	C	C	C	C
Comet															
Cushcraft		C	C	C	C										
Dec Prod		C	C	C	C	C		C	C		C	C		C	
MA/COM												C		C	
RF Parts			C		C	C	C								
Sinclair	C	C	C					C		C		C		C	C
TX/RX								C	C	C		C		C	C
Wacom															

	Isolators/Circulators						*Transmitter Combiners*				*Cross-Band Couplers*			
Source	*28*	*50*	*144*	*220*	*450*	*902*	*144*	*220*	*450*	*902*	*0-174 450-512*	*0-512 800-960*	*59-174 806-960*	*406-512 806-960*
Celwave			C	C	C	C	C	C	C	C		S		
Dec Prod			C		C	C		C	C	C				
Sinclair			C		C	C								
TX/RX			C		C	C	C	C	C	C	C	C	C	C
Wacom			C	C	C	C	C	C	C	C		C		C

Abbreviated names above are for the following manufacturers: Austin Antennas, Celwave RF Inc, Cushcraft Corp, Decibel Products Inc, RF Parts, Sinclair Radio Laboratories Inc, TX/RX Systems Inc and Wacom Inc. A manufacturer's contact list appears in Chapter 21.

Key to codes used:
C = catalog (standard) item
S = special-order item

Note: Coaxial cable is not listed, because most manufacturers sell only to dealers.



Fig 21—Duplexers permit using one antenna for both transmitting and receiving in a repeater system. Section 1 prevents energy at the transmitter frequency from interfering with the receiver, while section 2 attenuates any off-frequency transmitter energy that is at or near the receiver frequency.

As shown in Fig 21, transmitter output on 146.94 MHz going from point C to D should not be attenuated. However, the transmitter energy should be greatly attenuated between points B and A. Duplexer section 2 should attenuate any noise or signals that are on or near the receiver input frequency of 146.34 MHz. For good reception the noise and spurious signal level must be less than –130 dBm (0 dBm = 1 milliwatt into 50 Ω). Typical transmitter noise 600 kHz away from the carrier frequency is 80 dB below the transmitter power output. For 60 watts of output (+48 dBm), the noise level is –32 dBm. The duplexer must make up the difference between –32 dBm and –130 dBm, or 98 dB.

The received signal must go from point B to A with a minimum of attenuation. Section 1 of the duplexer must also provide enough attenuation of the transmitter energy to prevent receiver overload. For an average receiver, the transmitter signal must be less than –30 dBm to meet this requirement. The difference between the transmitter output of +48 dBm and the receiver overload point of –30 dBm, 78 dB, must be made up by duplexer section 1.

THE CIRCUIT

Fig 22 shows the completed 6-cavity duplexer, and **Fig 23** shows the assembly of an individual cavity. A $^1/_4$-λ resonator was selected for this duplexer design. The length of the center conductor is adjusted by turning a



Fig 22—A six-cavity duplexer for use with a 144-MHz repeater. The cavities are fastened to a plywood base for mechanical stability. Short lengths of double-shielded cable are used for connections between individual cavities. An insertion loss of less than 1.5 dB is possible with this design.

threaded rod, which changes the resonant frequency of the cavity. Energy is coupled into and out of the tuned circuit by the coupling loops extending through the top plate.

The cavity functions as a series resonant circuit. When a reactance is connected across a series resonant circuit, an anti-resonant notch is produced, and the resonant frequency is shifted. If a capacitor is added, the notch appears below the resonant frequency. Adding inductance instead of capacitance makes the notch appear above the resonant frequency. The value of the added component determines the spacing between the notch and the resonant frequency of the cavity.

Fig 24 shows the measured band-pass characteristics of the cavity with shunt elements. With the cavity tuned to 146.94 MHz and a shunt capacitor connected from input to output, a 146.34-MHz signal is attenuated


TOP VIEW
BNC Connector
2-1/2" Center to Center
Tunning Rod
Teflon Bushing
Top Plate
Clamping Sleeve
Position of L1 on Three Cavities
Position of C1 on Three Cavities
6 Slots Equally Spaced 5/8" Deep
Cavity Outer Conductor
22-1/2"
Solder
Bottom Plate 4-1/4" X 4-1/4" X 1/8" Thick Brass Plate
OUTER CONDUCTOR
Tunning Shaft 3/8 X 16 Threaded Rod 20" Long
Clamping Sleeve Brass Pipe 3/8" ID X 1-5/8" Long
Locknut
Bud CU3002A Minibox
BNC Connector
7/8"
Teflon Bushing
Top Plate
Coupling Loop
Center Conductor 1-3/8" OD Copper Tubing, 18" Long
Tuning Plunger Bushing
Finger Stock
Solder
Tuning Plunger 1" OD Brass Tubing, 6" Long
SIDE VIEW

Fig 23—The assembly of an individual cavity. A Bud Minibox is mounted on the top plate with three screws. A clamping sleeve made of brass pipe is used to prevent crushing the box when the locknut is tightened on the tuning shaft. Note that the positions of both C1 and L1 are shown, but that three cavities will have C1 installed and three will have L1 in place.



Fig 24—Typical frequency response of a single cavity of the type used in the duplexer. The dotted line represents the passband characteristics of the cavity alone; the solid line for the cavity with a shunt capacitor connected between input and output. An inductance connected in the same manner will cause the rejection notch to be above the frequency to which the cavity is tuned.

by 35 dB. If an inductance is placed across the cavity and the cavity is tuned to 146.34 MHz, the attenuation at 146.94 MHz is 35 dB. Insertion loss in both cases is 0.4 dB. Three cavities with shunt capacitors are tuned to 146.94 MHz and connected together in cascade with short lengths of coaxial cable. The attenuation at 146.34 MHz is more than 100 dB, and insertion loss at 146.94 MHz is 1.5 dB. Response curves for a six-cavity duplexer are given in **Fig 25**.

Construction

The schematic diagram for the duplexer is shown in **Fig 26**. Three parts for the duplexer must be machined; all others can be made with hand tools. A small lathe can be used to machine the brass top plate, the threaded tuning plunger bushing and the Teflon insulator bushing. The dimensions of these parts are given in **Fig 27**.

Type DWV copper tubing is used for the outer conductor of the cavities. The wall thickness is 0.058 inch, with an outside diameter of 4$^1/_8$ inches. You will need a tubing cutter large enough to handle this size (perhaps borrowed or rented). The wheel of the cutter should be tight and sharp. Make slow, careful cuts so the ends will be square. The outer conductor is 22$^1/_2$ inches long.

The inner conductor is made from type M copper tubing having an outside diameter of 1$^3/_8$ inches. A 6-inch length of 1-inch OD brass tubing is used to make the tuning plunger.

The tubing types mentioned above are designations used in the plumbing and steam-fitting industry. Other types may be used in the construction of a duplexer, but you should check the sizes carefully to assure that the parts will fit each other. A greater wall thickness will make the assembly heavier, and the expense will increase accordingly. Soft solder is used throughout the assembly. Unless you have experience with silver solder, do not use it. Eutectic type 157 solder with paste or acid



Fig 25—Frequency response of the six-cavity duplexer. One set of three cavities is tuned to pass 146.34 MHz and notch 146.94 MHz (the receiver leg). The remaining set of three cavities is tuned to pass 146.94 MHz and notch 146.34 MHz. This duplexer provides approximately 100 dB of isolation between the transmitter and receiver when properly tuned.


from Transmitter
C1
7"
C1
7"
C1
26"
to Antenna
L1
7"
L1
7"
L1
9"
to Reciceiver
All Coaxial Cable RG – 55
Coaxial Connectors, Type BNC are Represented by Dot ●
Coupling Loop #16 Tinned Wire
1 – 5/8"
1/2"
1/4"
1 – 1/8"
1 – 1/4"
3/4"
L1 #16 Tinned Wire
2 – 1/2"
1/2"
0.02" Copper Strap Connecting Strap for C1
1"
1/4"

Fig 26—Diagram of the six-cavity duplexer. Coaxial cable lengths between cavities are critical and must be followed closely. Double shielded cable and high quality connectors should be used throughout. The sizes and shapes of the coupling loops, L1, and the straps for connecting C1 should be observed.
C1—1.7-11 pF circuit-board mount, E. F. Johnson 189-5-5 or equiv. Set at $^{3}/_{4}$ closed for initial alignment.


TOP PLATE
Material: 1/4" Brasss Plate
3/8" Dia
"A" Holes Tap 6 – 32 Through
3/8" Dia
3/8" Dia
A
A
A
1 – 1/16"
1/4"
7/16"
7/16"
2 – 5/8"
1/16" Wide X 1/8" Deep Groove
4.125" Dia
4.0005" Dia
1 -3/8" Dia
1 -1/4" Dia
SECTIONAL SIDE VIEW
Use #50 Drill
1/16"
3/8"
1/2"
INSULATOR BUSHING
Material: Teflon or Polyethelene
Tap 3/8 – 16
1/8"
1"
27/32"
1"
PLUNGER BUSHING
Material: 1" Dia Brass Rod

Fig 27—Dimensions for the three parts that require machining. A small metal-working lathe should be used for making these parts.

flux makes very good joints. This type has a slightly higher melting temperature than ordinary tin-lead alloy, but has considerably greater strength.

First solder the inner conductor to the top plate (**Fig 28**). The finger stock can then be soldered inside the lower end of the inner conductor, while temporarily held in place with a plug made of aluminum or stainless steel. While soldering, do not allow the flame from the torch to overheat the finger stock. The plunger bushing is soldered into the tuning plunger and a 20-inch length of threaded rod is soldered into the bushing.

Cut six slots in the top of the outer conductor. They should be $^{5}/_{8}$ inch deep and equally spaced around the tubing. The bottom end of the 4-inch tubing is soldered to the square bottom plate. The bottom plates have holes in the corners so they can be fastened to a plywood base by means of wood screws. Because the center conductor has no support at one end, the cavities must be mounted vertically.

The size and position of the coupling loops are critical. Follow the given dimensions closely. Both loops should be $^{1}/_{8}$ inch away from the center conductor on opposite sides. Connect a solder lug to the ground end of the loop, then fasten the lug to the top plate with a screw. The free end of the loop is insulated by Teflon bushings where it passes through the top plate for connection to the BNC fittings.

Before final assembly of the parts, clean them thoroughly. Soap-filled steel wool pads and hot water work well for this. Be sure the finger stock makes firm contact with the tuning plunger. The top plate should fit snugly in the top of the outer conductor—a large hose clamp tightened around the outer conductor will keep the top plate in place.



Fig 28—Two of the center conductor and top plate assemblies. In the assembly at the left, C1 is visible just below the tuning shaft, mounted by short straps made from sheet copper. The assembly on the right has L1 in place between the BNC connectors. The Miniboxes are fastened to the top plate by a single large nut in these units. Using screws through the Minibox into the top plate, as described in the text, is preferred.

ADJUSTMENT

After the cavities have been checked for band-pass characteristics and insertion loss, install the anti-resonant elements, C1 and L1. (See Fig 24.) It is preferable to use laboratory test equipment when tuning the duplexer. An option is to use a low-power transmitter with an RF probe and an electronic voltmeter. Both methods are shown in **Fig 29**.

With the test equipment connected as shown in Fig 29A, adjust the signal generator frequency to the desired repeater input frequency. Connect a calibrated step attenuator between points X and Y. With no attenuation, adjust the HP-415 for 0 on the 20-dB scale. You can check the calibration of the 415 by switching in different amounts of attenuation and noting the meter reading. You may note a small error at either high or very low signal levels.

Next, remove the step attenuator and replace it with a cavity that has the shunt inductor, L1, in place. Adjust the tuning screw for maximum reading on the 415 meter. Remove the cavity and connect points X and Y. Set the



Fig 29—The duplexer can be tuned by either of the two methods shown here, although the method depicted at A is preferred. The signal generator should be modulated by a 1-kHz tone. If the setup shown at B is used, the transmitter should not be modulated, and should have a minimum of noise and spurious signals. The cavities to be aligned are inserted between X and Y in the setup at A, and between P and Q in B.

signal generator to the repeater output frequency and adjust the 415 for a 0 reading on the 20-dB scale.

Reinsert the cavity between X and Y and adjust the cavity tuning for minimum reading on the 415. The notch should be sharp and have a depth of at least 35 dB. It is important to maintain the minimum reading on the meter while tightening the locknut on the tuning shaft.

To check the insertion loss of the cavity, the output from the signal generator should be reduced, and the calibration of the 415 meter checked on the 50-dB expanded scale. Use a fixed 1-dB attenuator to make certain the error is less than 0.1 dB. Replace the attenuator with the cavity and read the loss. The insertion loss should be 0.5 dB or less. The procedure is the same for tuning all six cavities, except that the frequencies are reversed for those having the shunt capacitor installed.

Adjustment with Minimum Equipment

A transmitter with a minimum of spurious output is required. Most modern transmitters meet this requirement. The voltmeter in use should be capable of reading 0.5 volt (or less), full scale. The RF probe used should be rated to 150 MHz or higher. Sections of RG-58 cable are used as attenuators, as shown in Fig 29B. The loss in these 140-foot lengths is nearly 10 dB, and helps to isolate the transmitter in case of mismatch during tuning.

Set the transmitter to the repeater input frequency and connect P and Q. Obtain a reading between 1 and 3 volts on the voltmeter. Insert a cavity with shunt capacitors in place between P and Q and adjust the cavity tuning for a minimum reading on the voltmeter. (This reading should be between 0.01 and 0.05 volt.) The rejection in dB can be calculated by

$$dB = 20 \log (V1/V2)$$

This should be at least 35 dB. Check the insertion loss by putting the receiver on the repeater output frequency and noting the voltmeter reading with the cavity out of the circuit. A 0.5-dB attenuator can be made from a 7-foot length of RG-58. This 7-foot cable can be used to check the calibration of the detector probe and the voltmeter.

Cavities with shunt inductance can be tuned the same way, but with the frequencies reversed. If two or more cavities are tuned while connected together, transmitter noise can cause the rejection readings to be low. In other words, there will be less attenuation.

Results

The duplexer is conservatively rated at 150 watts input, but if constructed carefully should be able to handle as much as 300 watts. Silver plating the interior surfaces of the cavities is recommended if input power is to be greater than 150 watts. A duplexer of this type with silver-plated cavities has an insertion loss of less than 1 dB, and a rejection of more than 100 dB. Unplated cavities should be disassembled at least every two years, cleaned thoroughly, and then retuned.

Miscellaneous Notes

1) Double shielded cable and high quality connectors are *required* throughout the system.
2) The SWR of the antenna should not exceed 1.2:1 for proper duplexer performance.
3) Good shielding of the transmitter and receiver at the repeater is essential.
4) The antenna should have four or more wavelengths of vertical separation from the repeater.
5) Conductors in the near field of the antenna should be well bonded and grounded to eliminate noise.
6) The feed line should be electrically bonded and mechanically secured to the tower or mast.
7) Feed lines and other antennas in the near field of the repeater antenna should be well bonded and as far from the repeater antenna as possible.
8) Individual cavities can be used to improve the performance of separate antenna or separate site repeaters.
9) Individual cavities can be used to help solve intermodulation problems.

BIBLIOGRAPHY

Source material and more extended discussions of the topics covered in this chapter can be found in the references below.

P. Arnold, “Controlling Cavity Drift in Low-Loss Combiners,” *Mobile Radio Technology*, Apr 1986, pp 36-44.

L. Barrett, “Repeater Antenna Beam Tilting,” *Ham Radio*, May 1983, pp 29-35. (See correction, *Ham Radio*, Jul 1983, p 80.)

W. F. Biggerstaff, “Operation of Close Spaced Antennas in Radio Relay Systems,” *IRE Transactions on Vehicular Communications*, Sep 1959, pp 11-15.

J. J. Bilodeau, “A Homemade Duplexer for 2-Meter Repeaters,” *QST*, Jul 1972, pp 22-26, 47.

W. B. Bryson, “Design of High Isolation Duplexers and a New Antenna for Duplex Systems,” *IEEE Transactions on Vehicular Communications*, Mar 1965, pp 134-140.

K. Connolly and P. Blevins, “A Comparison of Horizontal Patterns of Skeletal and Complete Support Structures,” *IEEE 1986 Vehicular Technology Conference Proceedings*, pp 1-7.

S. Kozono, T. Tsuruhara and M. Sakamoto, “Base Station Polarization Diversity Reception for Mobile Radio,” *IEEE Transactions on Vehicular Technology*, Nov 1984, pp 301-306.

J. Kraus, *Antennas*, 2nd ed. (New York: McGraw-Hill Book Co., 1988).

W. Pasternak and M. Morris, *The Practical Handbook of Amateur Radio FM & Repeaters*, (Blue Ridge Summit, PA: Tab Books Inc., 1980), pp 355-363.

M. W. Scheldorf, “Antenna-To-Mast Coupling in Communications," *IRE Transactions on Vehicular Communications*, Apr 1959, pp 5-12.

R. D. Shriner, "A Low Cost PC Board Duplexer," *QST*, Apr 1979, pp 11-14.

W. V. Tilston, "Simultaneous Transmission and Reception with a Common Antenna," *IRE Transactions on Vehicular Communications*, Aug 1962, pp 56-64.

E. P. Tilton, "A Trap-Filter Duplexer for 2-Meter Repeaters," *QST*, Mar 1970, pp 42-46.

R. Wheeler, "Fred's Advice solves Receiver Desense Problem," *Mobile Radio Technology*, Feb 1986, pp 42-44.

R. Yang and F. Willis, "Effects of Tower and Guys on Performance of Side Mounted Vertical Antennas," *IRE Transactions on Vehicular Communications*, Dec 1960, pp 24-31.

Chapter 18

VHF and UHF Antenna Systems

A good antenna system is one of the most valuable assets available to the VHF/UHF enthusiast. Compared to an antenna of lesser quality, an antenna that is well designed, is built of good quality materials, and is well maintained, will increase transmitting range, enhance reception of weak signals and reduce interference problems. The work itself building antennas is by no means the least attractive part of the job. Even with high-gain antennas, experimentation is greatly simplified at VHF and UHF because the antennas are a physically manageable size. Setting up a home antenna range is within the means of most amateurs, and much can be learned about the nature and adjustment of antennas. No large investment in test equipment is necessary.

The Basics

Selecting the best VHF or UHF antenna for a given installation involves much more than scanning gain figures and prices in a manufacturer's catalog. There is no one "best" VHF or UHF antenna design for all purposes. The first step in choosing an antenna is figuring out what you want it to do.

Gain

At VHF and UHF, it is possible to build Yagi antennas with very high gain—15 to 20 dBi—on a physically manageable boom. Such antennas can be combined in arrays of two, four, six, eight or more antennas. These arrays are attractive for EME, tropospheric scatter or other weak-signal communications modes.

Radiation Patterns

Antenna radiation can be made omnidirectional, bidirectional, practically unidirectional, or anything between these conditions. A VHF net operator may find an omnidirectional system almost a necessity, but it may be a poor choice otherwise. Noise pickup and other interference problems are greater with such omnidirectional antennas, and omnidirectional antennas having some gain are especially bad in these respects. Maximum gain and low radiation angle are usually prime interests of the weak-signal DX aspirant. A clean pattern, with lowest possible pickup and radiation off the sides and back, may be important in high-activity areas, or where the noise level is high.

Frequency Response

The ability to work over an entire VHF band may be important in some types of work. Modern Yagis can achieve performance over a remarkably wide frequency range, providing that the boom length is long enough and enough elements are used to populate the boom. Modern Yagi designs in fact are competitive with directly driven collinear arrays of similar size and complexity. The primary performance parameters of gain, front-to-rear ratio and SWR can be optimized over all the VHF or UHF amateur bands readily, with the exception of the full 6meter band from 50.0 to 54.0 MHz, which is an 8% wide bandwidth. A Yagi can be easily designed to cover any 2.0 MHz portion of the 6-meter band with superb performance.

Height Gain

In general, higher is better in VHF and UHF antenna installations. Raising the antenna over nearby obstructions may make dramatic improvements in coverage. Within reason, greater height is almost always worth its cost, but height gain (see Chapter 23, Radio Wave Propagation) must be balanced against increased transmission-line loss. This loss can be considerable, and it increases with frequency. The best available line may not be very good if the run is long in terms of wavelengths. Line loss considerations (see Chapter 24, Transmission Lines) are important in antenna planning.

Physical Size

A given antenna design for 432 MHz has the same gain as the same design for 144 MHz, but being only one-third as large intercepts only one-ninth as much energy in receiving. In other words, the antenna has less pickup efficiency at 432 MHz. To be equal in communication effectiveness, the 432-MHz array should be at least equal in *size* to the 144-MHz antenna, which requires roughly three times as many elements. With all the extra difficulties involved in using the higher frequencies effectively, it is best to keep antennas as large as possible for these bands.

DESIGN FACTORS

With the objectives sorted out in a general way, decisions on specifics, such as polarization, type of transmission line, matching methods and mechanical design must be made.

Polarization

Whether to position antenna elements vertically or horizontally has been widely debated since early VHF pioneering days. Tests have shown little evidence about which polarization sense is most desirable. On long propagation paths there is no consistent advantage either way. Shorter paths tend to yield higher signal levels with horizontally polarized antennas over some kinds of terrain. Man-made noise, especially ignition interference, also tends to be lower with horizontal antennas. These factors make horizontal polarization somewhat more desirable for weak-signal communications. On the other hand, vertically polarized antennas are much simpler to use in omnidirectional systems and in mobile work.

Vertical polarization was widely used in early VHF work, but horizontal polarization gained favor when directional arrays started to become widely used. The major use of FM and repeaters, particularly in the VHF/UHF bands, has tipped the balance in favor of vertical antennas in mobile and repeater use. Horizontal polarization predominates in other communication on 50 MHz and higher frequencies. An additional loss of 20 dB or more can be expected when cross-polarized antennas are used.

TRANSMISSION LINES

Transmission line principles are covered in detail in Chapter 24, Transmission Lines. Techniques that apply to VHF and UHF operation are dealt with in greater detail here. The principles of carrying RF from one location to another via a feed line are the same for all radio frequencies. As at HF, RF is carried principally via open wire lines and coaxial cables at VHF/UHF. Certain aspects of these lines characterize them as good or bad for use above 50 MHz.

Properly built open-wire line can operate with very low loss in VHF and UHF installations. A total line loss under 2 dB per 100 feet at 432 MHz can easily be obtained. A line made of #12 wire, spaced $^3/_4$ inch or more with Teflon spreaders and run essentially straight from antenna to station, can be better than anything but the most expensive coax. Such line can be home made or purchased at a fraction of the cost of coaxial cables, with comparable loss characteristics. Careful attention must be paid to efficient impedance matching if the benefits of this system are to be realized. A similar system for 144 MHz can easily provide a line loss under 1 dB.

Small coax such as RG-58 or RG-59 should never be used in VHF work if the run is more than a few feet. Lines of $^1/_2$-inch diameter (RG-8 or RG-11) work fairly well at 50 MHz, and are acceptable for 144-MHz runs of 50 feet or less. These lines are somewhat better if they employ foam instead of ordinary PE dielectric material. Aluminum-jacket *hardline* coaxial cables with large inner conductors and foam insulation are well worth their cost, and can sometimes be obtained for free from local Cable TV operators as “end runs”—pieces at the end of a roll. The most common CATV cable is $^1/_2$-inch OD 75-Ω hardline. Matched-line loss for this cable is about 1.0 dB/100 feet at 146 MHz and 2.0 dB/100 feet at 432 MHz. Less commonly available from CATV companies is the $^3/_4$-inch 75Ω hardline, sometimes with a black self-healing hard plastic covering. This line has 0.8 dB of loss per 100 feet at 146 MHz, and 1.6 dB loss per 100 feet at 432 MHz. There will be small additional losses for either line if 75-to-50Ω transformers are used at each end.

Commercial connectors for hardline are expensive but provide reliable connections with full waterproofing. Enterprising amateurs have homebrewed low-cost connectors. If they are properly water proofed, connectors and hardline can last almost indefinitely. Hardline must not be bent too sharply, because it will kink. See Chapter 24, Transmission Lines, for details on hardline connectors.

Beware of any “bargains” in coax for VHF or UHF use. Feed-line loss can be compensated to some extent by increasing transmitter power, but once lost, a weak signal can never be recovered in the receiver. Effects of weather on transmission lines should not be ignored. Well-constructed open-wire line works optimally in nearly any weather, and it stands up well. Twin-lead is almost useless in heavy rain, wet snow or icing. The best grades of coax are completely impervious to weather—they can be run underground, fastened to metal towers without insulation and bent into any convenient position with no adverse effects on performance.

WAVEGUIDES

Above 2 GHz, coaxial cable is a losing proposition for communications work. Fortunately, at this frequency the wavelength is short enough to allow practical, efficient energy transfer by an entirely different means. A *waveguide* is a conducting tube through which energy is transmitted in the form of electromagnetic waves. The tube is not considered as carrying a current in the same sense that the wires of a two-conductor line do, but rather as a *boundary* that confines the waves in the enclosed space. Skin effect prevents any electromagnetic effects from being evident outside the guide. The energy is injected at one end, either through capacitive or inductive coupling or by radiation, and is removed from the other end in a like manner. Waveguide merely confines the energy of the fields, which are propagated through it to the receiving end by means of reflections against its inner walls.

Analysis of waveguide operation is based on the assumption that the guide material is a perfect conductor of electricity. Typical distributions of electric and magnetic fields in a rectangular guide are shown in **Fig 1**. The intensity of the electric field is greatest (as indicated by closer spacing of the lines of force) at the center along the X dimension (Fig 1C), diminishing to zero at the end walls. The fields must diminish in this manner, because the existence of any electric field parallel to the walls at the surface would cause an infinite current to flow in a perfect conductor. Waveguides, of course, cannot carry RF in this fashion.

Modes of Propagation

Fig 1 represents the most basic distribution of the electric and magnetic fields in a waveguide. There are an infinite number of ways in which the fields can arrange themselves in a waveguide (for frequencies above the low cutoff frequency of the guide in use). Each of these field configurations is called a *mode*.

The modes may be separated into two general groups. One group, designated *TM* (transverse magnetic), has the magnetic field entirely transverse to the direction of propagation, but has a component of the electric field in that direction. The other type, designated *TE* (transverse electric) has the electric field entirely transverse, but has a component of magnetic field in the direction of propagation. TM waves are sometimes called *E waves*, and TE waves are sometimes called *H waves*, but the TM and TE designations are preferred.

The mode of propagation is identified by the group letters followed by two subscript numerals. For example, TE_{10}, TM_{11}, etc. The number of possible modes increases with frequency for a given size of guide, and there is only one possible mode (called the *dominant mode*) for the lowest frequency that can be transmitted. The dominant mode is the one generally used in amateur work.

Waveguide Dimensions

In rectangular guide the critical dimension is X in Fig 1. This dimension must be more than $^1/_2\ \lambda$ at the lowest frequency to be transmitted. In practice, the Y dimension usually is made about equal to $^1/_2$ X to avoid the possibility of operation in other than the dominant mode.

Cross-sectional shapes other than a rectangle can be used, the most important being the circular pipe. Much the same considerations apply as in the rectangular case.

Wavelength dimensions for rectangular and circular guides are given in **Table 1**, where X is the width of a rectangular guide and r is the radius of a circular guide. All figures apply to the dominant mode.



Fig 1—Field distribution in a rectangular waveguide. The TE10 mode of propagation is depicted.

Coupling to Waveguides

Energy may be introduced into or extracted from a waveguide or resonator by means of either the electric or magnetic field. The energy transfer frequently is through a coaxial line. Two methods for coupling to coaxial line are shown in **Fig 2**. The probe shown at A is simply a short extension of the inner conductor of the coaxial line, oriented so that it is parallel to the electric lines of force. The loop shown at B is arranged so that it encloses some of the magnetic lines of force. The point at which maximum coupling is obtained depends upon the mode of propagation in the guide or cavity. Coupling is maximum when the coupling device is in the most intense field.

Coupling can be varied by turning the probe or loop through a 90° angle. When the probe is perpendicular to the electric lines the coupling is minimum. Similarly, when the plane of the loop is parallel to the magnetic lines the coupling is minimum.

If a waveguide is left open at one end it will radiate energy. This radiation can be greatly enhanced by flaring the waveguide to form a pyramidal horn antenna. The horn acts as a transition between the confines of the waveguide and free space. To effect the proper impedance transformation the horn must be at least $^1/_2\ \lambda$ on a side. A horn of this dimension (cutoff) has a unidirectional radiation pattern with a null toward the waveguide transition. The gain at the cutoff frequency is 3 dB, increasing 6 dB with each doubling of frequency. Horns are used extensively in microwave work, both as primary radiators and as feed elements for more elaborate focusing systems. Details for constructing 10-GHz horn antennas are given later in this chapter.

Evolution of a Waveguide

Suppose an open-wire line is used to carry RF energy from a generator to a load. If the line has any appreciable length it must be mechanically supported. The line must be well insulated from the supports if high losses are to be avoided. Because high-quality insulators are difficult to construct at microwave frequencies, the logical alternative is to support the transmission line with $^1/_4\ \lambda$ stubs, shorted at the end opposite the feed line. The open end of such a stub presents an infinite impedance to the transmission line, provided the shorted stub is nonreactive. However, the shorting link has a finite length, and therefore some inductance. The effect of this inductance can be removed by making the RF current flow on the surface of a plate rather than a thin wire. If the plate is large enough, it will prevent the magnetic lines of force from encircling the RF current.

An infinite number of these $^1/_4\ \lambda$ stubs may be connected in parallel without affecting the standing waves of voltage and current. The transmission line may be supported from the top as well as the bottom, and when an infinite number of supports are added, they form the walls of a waveguide at its cutoff frequency. **Fig 3** illustrates how a rectangular waveguide evolves from a two-wire parallel transmission line as described. This simplified analysis also shows why the cutoff dimension is $^1/_2\ \lambda$.

While the operation of waveguides is usually described in terms of fields, current does flow on the inside walls, just as on the conductors of a two-wire transmission line. At the waveguide cutoff frequency, the current is concentrated in the center of the walls, and disperses toward the floor and ceiling as the frequency increases.

Table 1
Waveguide Dimensions

	Rectangular	*Circular*
Cutoff wavelength	2X	3.41r
Longest wavelength transmitted with little attenuation	1.6X	3.2r
Shortest wavelength before next mode becomes possible	1.1X	2.8r



Fig 2—Coupling coaxial line to waveguide and resonators.

IMPEDANCE MATCHING

Impedance matching is covered in detail in Chapter 25, Coupling the Transmitter to the Line, and Chapter 26, Coupling the Line to the Antenna. The theory is the same for frequencies above 50 MHz. Practical aspects are similar, but physical size can be a major factor in the choice of methods. Only the matching devices used in practical construction examples later in this chapter are discussed in detail here. This should not rule out consideration of other methods, however, and you should read the relevant portions of both Chapters 25 and 26.

Universal Stub

As its name *universal stub* implies, the double-adjustment stub of **Fig 4A** is useful for many matching purposes. The stub length is varied to resonate the system and the transmission-line attachment point is varied until the transmission line and stub impedances are equal. In practice this involves moving both the sliding short and



Fig 3—At its cutoff frequency a rectangular waveguide can be thought of as a parallel two-conductor transmission line supported from top and bottom by an infinite number of $^1/_4$-λ stubs.

the point of line connection for zero reflected power, as indicated on an SWR bridge connected in the line.

The universal stub allows for tuning out any small reactance present in the driven part of the system. It permits matching the antenna to the line without knowledge of the actual impedances involved. The position of the short yielding the best match gives some indication of the amount of reactance present. With little or no reactive component to be tuned out, the stub must be approximately $^1/_2$ λ from load toward the short.

The stub should be made of stiff bare wire or rod, spaced no more than $^1/_{20}$ λ apart. Preferably it should be mounted rigidly, on insulators. Once the position of the short is determined, the center of the short can be grounded, if desired, and the portion of the stub no longer needed can be removed.

It is not necessary that the stub be connected directly to the driven element. It can be made part of an open-wire line as a device to match coaxial cable to the line. The stub can be connected to the lower end of a delta match or placed at the feed point of a phased array. Examples of these uses are given later.

Delta Match

Probably the most basic impedance matching device is the *delta match*, fanned ends of an open-wire line tapped onto a $^1/_2$ λ antenna at the point of the most-efficient power transfer. This is shown in Fig 4B. Both the side length and the points of connection either side of the center of the element must be adjusted for minimum reflected power on the line, but as with the universal stub, you needn't know the impedances. The delta match makes no provision for tuning out reactance, so the universal stub is often used as a termination for it.



Fig 4—Matching methods commonly used at VHF. The universal stub, A, combines tuning and matching. The adjustable short on the stub and the points of connection of the transmission line are adjusted for minimum reflected power on the line. In the delta match, B and C, the line is fanned out and connected to the dipole at the point of optimum impedance match. Impedances need not be known in A, B or C. The gamma match, D, is for direct connection of coax. C1 tunes out inductance in the arm. A folded dipole of uniform conductor size, E, steps up antenna impedance by a factor of four. Using a larger conductor in the unbroken portion of the folded dipole, F, gives higher orders of impedance transformation.

At one time, the delta match was thought to be inferior for VHF applications because of its tendency to radiate if improperly adjusted. The delta has come back into favor now that accurate methods are available for measuring the effects of matching. It is very handy for phasing multiple-bay arrays with open-wire lines, and its dimensions in this use are not particularly critical. It should be checked out carefully in applications like that of Fig 4C, where no tuning device is used.

Gamma and T Matches

An application of the same principle allowing direct connection of coax is the *gamma match*, Fig 4D. Because the RF voltage at the center of a $^1/_2$ λ dipole is zero, the outer conductor of the coax is connected to the element at this point. This may also be the junction with a metallic or wooden boom. The inner conductor, carrying the RF current, is tapped out on the element at the matching point. Inductance of the arm is tuned out by means of C1, resulting in electrical balance. Both the point of contact with the element and the setting of the capacitor are adjusted for zero reflected power, with a bridge connected in the coaxial line.

The capacitance can be varied until the required value is found, and the variable capacitor replaced with a fixed unit of that value. C1 can be mounted in a waterproof box. The maximum required value should be about 100 pF for 50 MHz and 35 to 50 pF for 144 MHz.

The capacitor and arm can be combined in one coaxial assembly, with the arm connected to the driven element by means of a sliding clamp and the inner end of the arm sliding inside a sleeve connected to the center conductor of the coax. An assembly of this type can be constructed from concentric pieces of tubing, insulated by plastic or heat-shrink sleeving. RF voltage across the capacitor is low when the match is adjusted properly, so with a good dielectric, insulation presents no great problem. The initial adjustment should be made with low power. A clean, permanent high-conductivity bond between arm and element is important, since the RF current is high at this point.

Because it is inherently somewhat unbalanced, the gamma match can sometimes introduce pattern distortion, particularly on long-boom, highly directive Yagi arrays. The *T-match*, essentially two gamma matches in series creating a balanced feed system, has become popular for this reason. A coaxial balun like that shown in **Fig 5** is used from the 200 Ω balanced T-match to the unbalanced 50 Ω coaxial line going to the transmitter. See the K1FO Yagi designs later in this chapter for details on practical use of a T-match.

Folded Dipole

The impedance of a $\frac{1}{2}\lambda$ dipole broken at its center is about 70 Ω. If a single conductor of uniform size is folded to make a $\frac{1}{2}\lambda$ dipole as shown in Fig 4E, the impedance is stepped up four times. Such a folded dipole can be fed directly with 300Ω line with no appreciable mismatch. If a 4:1 balun is used, the antenna can be fed with 75Ω coaxial cable. (See balun information presented below.) Higher step-up impedance transformation can be obtained if the unbroken portion is made larger in cross-section than the fed portion, as shown in Fig 4F.



Fig 5—Conversion from unbalanced coax to a balanced load can be done with a $\frac{1}{2}$-λ, coaxial balun at A. Electrical length of the looped section should be checked with a dip meter, with the ends shorted, as at B. The $\frac{1}{2}$-λ balun gives a 4:1 impedance step-up.

Hairpin Match

The feed-point resistance of most multielement Yagi arrays is less than 50 Ω. If the driven element is split and fed at the center, it may be shortened from its resonant length to add capacitive reactance at the feed point. Then, shunting the feed point with a wire loop resembling a *hairpin* causes a step-up of the feed-point resistance. The hairpin match is used together with a 4:1 coaxial balun in the 50 MHz arrays described later in this chapter. See Chapter 26, Coupling the Line to the Antenna, for details on the hairpin match.

BALUNS AND ANTENNA TUNERS

Conversion from balanced loads to unbalanced lines (or vice versa) can be performed with electrical circuits, or their equivalents made of coaxial cable. A balun made from flexible coax is shown in Fig 5A. The looped portion is an electrical $\frac{1}{2}\lambda$. The physical length depends on the velocity factor of the line used, so it is important to check its resonant frequency as shown in Fig 5B. The two ends are shorted, and the loop at one end is coupled to a dip meter coil. This type of balun gives an impedance step-up of 4:1 (typically 50 to 200 Ω, or 75 to 300 Ω).

Coaxial baluns that yield 1:1 impedance transformations are shown in **Fig 6**. The coaxial sleeve, open at the top and connected to the outer conductor of the line at the lower end (A) is the preferred type. At B, a conductor of approximately the same size as the line is used with the outer conductor to form a $\frac{1}{4}\lambda$ stub. Another piece of coax, using only the outer conductor, will serve this purpose. Both baluns are intended to present an infi-



Fig 6—The balun conversion function, with no impedance transformation, can be accomplished with $\frac{1}{4}$-λ lines, open at the top and connected to the coax outer conductor at the bottom. The coaxial sleeve at A is preferred.

nite impedance to any RF current that might otherwise flow on the outer conductor of the coax.

The functions of the balun and the impedance transformer can be handled by various tuned circuits. Such a device, commonly called an *antenna tuner* or a *Transmatch*, can provide a wide range of impedance transformations. Additional selectivity inherent in the antenna tuner can reduce RFI problems.

THE YAGI AT VHF AND UHF

Without doubt, the Yagi is king of home-station antennas these days. Today's best designs are computer optimized. For years amateurs as well as professionals designed Yagi arrays experimentally. Now we have powerful (and inexpensive) personal computers and sophisticated software for antenna modeling. These have brought us antennas with improved performance, with little or no element pruning required. Chapter 11, HF Yagi Arrays, describes the parameters associated with Yagi-Uda arrays. Except for somewhat tighter dimensional tolerances needed at VHF and UHF, the properties that make a good Yagi at HF also are needed on the higher frequencies. See the end of this chapter for practical Yagi designs.

STACKING YAGIS

Where suitable provision can be made for supporting them, two Yagis mounted one above the other and fed in phase can provide better performance than one long Yagi with the same theoretical or measured gain. The pair occupies a much smaller turning space for the same gain, and their wider elevation coverage can provide excellent results. The wide azimuthal coverage for a vertical stack often results in QSOs that might be missed with a single narrow-beam long-boom Yagi pointed in a different direction. On long ionospheric paths, a stacked pair occasionally may show an *apparent* gain much greater than the measured 2 to 3 dB of stacking gain. (See also the extensive section on stacking Yagis in Chapter 11, HF Yagi Arrays.)

Optimum vertical spacing for Yagis with boom longer than 1 λ or more is about 1 λ (984/50.1 = 19.64 feet), but this may be too much for many builders of 50-MHz antennas to handle. Worthwhile results can be obtained with as little as $^{1}/_{2}$ λ (10 feet), but $^{5}/_{8}$ λ (12 feet) is markedly better. The difference between 12 and 20 feet, however, may not be worth the added structural problems involved in the wider spacing, at least at 50 MHz. The closer spacings give lower measured gain, but the antenna patterns are cleaner in both azimuth and elevation than with 1 λ spacing. Extra gain with wider spacings is usually the objective on 144 MHz and higher-frequency bands, where the structural problems are not as severe.

Yagis can also be stacked in the same plane (collinear elements) for sharper azimuthal directivity. A spacing of $^{5}/_{8}$ λ between the ends of the inner elements yields the maximum gain within the main lobe of the array.

If individual antennas of a stacked array are properly designed, they look like noninductive resistors to the phasing system that connects them. The impedances involved can thus be treated the same as resistances in parallel.

Three sets of stacked dipoles are shown in **Fig 7**. Whether these are merely dipoles or the driven elements of Yagi arrays makes no difference for the purpose of these examples. Two 300 Ω antennas at A are 1 λ apart, resulting in a paralleled feed-point impedance of 150 Ω at the center. (Actually it is slightly less than 150 Ω because of coupling between bays, but this can be neglected for illustrative purposes.) This value remains the same regardless of the impedance of the phasing line. Thus, any convenient line can be used for phasing, as long as the *electrical* length of each line is the same.

The velocity factor of the line must be taken into account as well. As with coax, this is subject to so much variation that it is important to make a resonance check on the actual line used. The method for doing this is shown in Fig 5B. A $^{1}/_{2}$ λ line is resonant both open and shorted, but the shorted condition (both ends) is usually the more convenient test condition.



Fig 7—Three methods of feeding stacked VHF arrays. A and B are for bays having balanced driven elements, where a balanced phasing line is desired. Array C has an all-coaxial matching and phasing system. If the lower section is also $^{3}/_{4}$ λ no transposition of line connections is needed.

The impedance transforming property of a $^1/_4$ λ line section can be used in combination matching and phasing lines, as shown in Fig 7B and C. At B, two bays spaced $^1/_2$ λ apart are phased and matched by a 400-Ω line, acting as a double-Q section, so that a 300-Ω main transmission line is matched to two 300-Ω bays. The two halves of this phasing line could also be $^3/_4$-λ or $^5/_4$-λ long, if such lengths serve a useful mechanical purpose. (An example is the stacking of two Yagis where the desirable spacing is more than $^1/_2$ λ.)

A double-Q section of coaxial line is illustrated in Fig 7C. This is useful for feeding stacked bays that were designed for 50-Ω feed. A spacing of $^5/_8$ λ is useful for small Yagis, and this is the equivalent of a full electrical wavelength of solid-dielectric coax such as RG-11.

If one phasing line is electrically $^1/_4$ λ and $^3/_4$ λ on the other, the connection to one driven element should be reversed with respect to the other to keep the RF currents in the elements in phase—the gamma match is located on opposite sides of the driven elements in Fig 7C. If the number of $^1/_4$ λ lengths is the same on either side of the feed point, the two connections should be in the same position, and not reversed. Practically speaking however, you can ensure proper phasing by using exactly equal lengths of line from the same roll of coax. This ensures that the velocity factor for each line is identical.

One marked advantage of coaxial phasing lines is that they can be wrapped around the vertical support, taped or grounded to it, or arranged in any way that is mechanically convenient. The spacing between bays can be set at the most desirable value, and the phasing lines placed anywhere necessary.

Stacking Yagis for Different Frequencies

In stacking horizontal Yagis one above the other on a single rotating support, certain considerations apply when the bays are for different bands. As a very general rule of thumb, the minimum desirable spacing is half the boom length of the higher frequency Yagi.

For example, assume the stacked two-band array of **Fig 8A** is for 50 and 144 MHz. This vertical arrangement is commonly referred to as a *Christmas tree*, because it resembles one. The 50MHz Yagi has 5elements on a 12-foot boom. It tends to look like "ground" to the 8-element 144 MHz Yagi on a 12-foot boom directly above it. [The exact Yagi designs for the examples used in this section are located on the CD-ROM accompanying this book. They may be evaluated as monoband Yagis using the *YW* (Yagi for Windows) program also supplied on the CD-ROM. In each case the bottom Yagi in the stack (at the top of the tower) is assumed to be 20 feet high.]

SWR Change in a Multi-Frequency Stack

Earlier editions of *The ARRL Antenna Book* stated that the feed-point impedance of the higher-frequency antenna would likely be affected the most by the proxim-





Fig 8—In stacking Yagi arrays one above the other, the minimum spacing between bays (S) should be about half the boom length of the smaller array. Wider spacing is desirable, in which case it should be ½ λ or some multiple thereof, at the frequency of the smaller array. At A, stack of 8-element 2-meter Yagi on a 12-foot boom over a 5-element 6-meter Yagi, also on a 12-foot boom. At B, 5-element 2-meter beam on a 6-foot boom over a 3-element 6-meter beam on a 4-foot boom. At C, a 14-element 70-cm beam on a 9-foot boom, mounted over a 8-element 2-meter beam on a 12-foot boom and a 7-element 6-meter beam on a 22-foot boom.

ity of the lower-frequency Yagi. Modern computer modeling programs reveal that while the feed-point SWR can indeed be affected, by far the greatest degradation is in the forward gain and rearward pattern of the higher-frequency Yagi when the booms are closely spaced. In fact, the SWR curve is usually not affected enough to make it a good diagnostic indicator of interaction between the two Yagis.

Fig 9 shows an overlay of the SWR curves across the 2-meter band for four configurations: an 8-element 2-meter Yagi by itself, and then over a 5-element 6-meter Yagi with spacings between the booms of 1, 2, 4 and 6 feet. The SWR curves are similar—it would be difficult to see any difference between these configurations using typical amateur SWR indicators for anything but the very closest (1-foot) spacing. For example, the SWR curve for the 2-foot spacing case is virtually indistinguishable from that of the Yagi by itself, while the forward gain has dropped more than 0.6 dB because of interactions with the 6-meter Yagi below it.

Gain and Pattern Degradation Due to Stacking

Fig 10 shows four overlaid rectangular plots of the azimuth response from 0° to 180° for the 8-element 2-meter Yagi described above, spaced 1, 2, 4 and 6 feet over a 5-element 6-meter beam. The rectangular presentation gives more detail than a polar plot. The most closely spaced configuration (with 1-foot spacing between the booms) shows the largest degradation in the forward gain, a drop of 1.7 dB. The worst-case front-to-rear ratio for the 6-foot spacing is 29.0 dB, while it is 36.4 dB for the 1-foot spacing—actually better than the F/R for the 8-element 2-meter Yagi by itself. Performance change due to the nearby presence of other Yagis can be enormously complicated (and sometimes is non-intuitive as well).

What happens when a different kind of 6-meter Yagi is mounted below the 8-element 2-meter Yagi? **Fig 11** compares the change in forward gain and the worst-case F/R performance as a function of spacing between the booms for two varieties of 6-meter Yagis: the 5-element design on a 12-foot boom and a 7-element Yagi on a



Fig 10—Plots of the 8-element 2-meter Yagi's azimuth response from 0° to 180° for spacing distances from 1 to 6 feet. The sidelobe at about 60° varies about 6 dB over the range of boom spacings, while the shape of worst-case F/R curve varies considerably due to interactions with the lower 6-meter beam. The gain for the 1-foot spacing is degraded by more than 3 dB compared to the 2-meter antenna by itself.



Fig 9—SWR curves for different boom spacing between 8-element 2-meter Yagi on 12-foot boom, over a 5-element 6-meter Yagi on a 12-foot boom. For spacings greater than 1 foot between the booms, differences between the SWR curves are difficult to discern.



Fig 11—Plot of 8-element 2-meter Yagi's gain and worst-case F/R as a function of distance over two types of 6-meter beams, one on a 12-foot boom and the other on a 22-foot boom. Beyond a spacing of about 5 feet the performance is degraded a minimal amount.

22-foot boom. The spacing of "0 feet" represents the 8-element 2-meter Yagi when it is used alone, with no other antenna nearby. This sets the reference expectations for gain and F/R.

The most severe degradation occurs for the 1-foot spacing, as you might imagine, for both the 12 and 22-foot boom lengths. Over the 5-element 6-meter Yagi, the 2-meter gain doesn't recover to the reference level of the 8-element 2-meter beam by itself until the spacing is greater than 9 feet. However, the gain is within 0.25 dB of the reference level for spacings of 3 feet or more. Interestingly, the F/R is higher than that of the 2-meter antenna by itself for the 1, 2 and 5-foot spacings and for spacings greater than 11 feet. The 2-meter F/R in the presence of the 12-foot 5-element 6-meter Yagi remains above 20 dB for spacings beyond 1 feet.

Overall, the 2-meter beam performs reasonably well for spacings of 3 feet or more over the 5-element 6-meter Yagi. Put another way, the 2-meter beam's performance is degraded only slightly for boom spacings greater than 3 feet. A spacing of 3 feet is less than the old rule of thumb that the minimum spacing between booms be greater than one-half the boomlength of the higher-frequency Yagi, which in this case is 6 feet long.

For the 7-element 6-meter Yagi, the 2-meter gain recovers to the reference level for spacings beyond 7 feet, but the F/R is degraded below the reference level for all spacings shown in Fig 11. If we use a gain reduction criterion of less than 0.25 dB and a 20-dB F/R level as the minimum acceptable level, then the spacing must be 5 feet or more over the larger 6-meter Yagi. Again, this is less than the rule of thumb that the minimum spacing between booms be greater than one-half the boomlength of the higher-frequency Yagi.

Now, let's try a smaller setup of 2- and 6-meter Yagis stacked vertically in a Christmas-tree configuration to see if the rule of thumb for spacing the booms still holds. **Fig 12** shows the performance curves versus boom spacing for a 5-element 2-meter Yagi on a 4-foot boom stacked over a 3-element 6-meter Yagi on a 6-foot boom. Again, the 1-foot spacing produces a substantial gain reduction of about 1.3 dB compared to the reference gain when the 2-meter Yagi is used by itself. Beyond a boom spacing of 3 feet the 2-meter gain drops less than 0.25 dB from the reference level of the 2-meter Yagi by itself and the F/R remains above about 20 dB. In this example, the simple rule of thumb that the minimum spacing between booms be greater than half the boom length (half of 4 feet) of the higher-frequency Yagi does not hold up. However, the same minimum spacing of 3 feet we found for the larger 2-meter Yagi remains true. Three feet spacing is almost 0.5 λ between the booms at the higher frequency.



Fig 12— Plot of gain and worst-case F/R of a 5-element 2-meter Yagi on a 4-foot boom as a function of distance over a 3-element 6-meter beam on a 6-foot boom. Beyond a spacing of about 3 feet the performance is degraded a minimal amount.

Adding a 70-cm Yagi to the Christmas Tree

Let's get more ambitious and set up a larger VHF/UHF Christmas tree, with a 14-element 70-cm Yagi on a 9-foot boom at the top, mounted 5 feet over an 8-element 2-meter Yagi on a 12-foot boom. At the bottom of the stack (at the top of the tower) is either the 5-element 6-meter beam on a 12-foot boom, or a 7-element 6-meter beam on a 22-foot boom. See Fig 8C. As before, we will vary the spacing between the 70-cm Yagi and the 2-meter Yagi below it to assess the interactions that degrade the 70-cm performance.

Fig 13 compares the change in gain and F/R curves as a function of boom spacings between the 70-cm and 2-meter Yagis for the two different 6-meter Yagis (with a fixed distance of 5 feet between the 2-meter and 6-meter Yagis). In this example, the 70-cm Yagi was designed to be an intrinsic 50-Ω feed, where the F/R has been compromised to some extent. Still, the F/R is greater than 20 dB when the 70-cm Yagi is used by itself.

For spacings greater than 4 feet between the 70-cm and 2-meter booms, the 70-cm gain is equal to or even slightly greater than that of the 70-cm antenna by itself. The increase of gain indicates that the elevation pattern of the 70-cm antenna is slightly compressed by the presence of the other Yagis below it. The F/R stays above at 19.5 dB for spacings greater than or equal to 4 feet. This falls just below our desired lower limit of 20 dB, but it is highly doubtful that anyone would notice this 0.5-dB drop in actual operation. A spacing of 4 feet between booms falls under the rule of thumb that the minimum spacing be at least half the boomlength of the higher-frequency Yagi, which in this case is 9 feet.

What should be obvious in this discussion is that you should model the exact configuration you plan to build to avoid unnecessary performance degradation.

Stacking Same-Frequency Yagis

This subject has been examined in some detail in Chapter 11, HF Yagi Arrays. The same basic principles



Fig 13—Performance of a 14-element 70-cm Yagi on a 9-foot boom, mounted a variable distance over an 8-element 2-meter Yagi on a 12-foot boom, which is mounted 5 feet above either a 5-element 6-meter Yagi on a 12-foot boom or a 7-element 6-meter Yagi on a 22-foot boom. Beyond a spacing of about 4 feet, the performance of the 70-cm beam is degraded a minimal amount.


HFTA, Copyright ARRL 2003, by N6BV, Ver. 1.35B

Freq. = 50.1 MHz
Max. Gain: 18.1 dBi
FLAT.PRO
42/30 ft
FLAT.PRO
42*/30 ft

Fig 14—*HFTA* comparison plots of the elevation responses for two 5-element 6-meter Yagis mounted at 42 and 30 feet above flat ground, when they are fed in-phase and out-of-phase. By switching the phasing (adding a half-wavelength of coax to one of the antennas), the elevation angle can be controlled to enhance performance when a Sporadic-E cloud is nearly overhead.

hold at VHF and UHF as they do on HF. That is, the gain increases gradually with increasing spacing between the booms, and then falls off gradually past a certain spacing distance.

At HF, Chapter 11 emphasizes that you should avoid nulls in the antenna's elevation response—so that you can cover all the angles needed for geographic areas of interest. At VHF/UHF, propagation is usually at low elevation angles for most propagation modes, and signals are often extremely weak. Thus, achieving maximum gain is the most common design objective for a VHF/UHF stack. Of secondary importance is the cleanliness of the beam pattern, to discriminate against interference and noise sources.

Six-meter Sporadic-E can sometimes occur at high elevation angles, especially if the E_s cloud is overhead, or nearly overhead. Since Sporadic-E is exactly that, *sporadic*, it's not a good design practice to try to cover a wide range of elevation angles, as you must often do at HF to cover large geographic areas. On 6 meters, you can change to high-angle coverage when necessary. For example, you might switch to a separate Yagi mounted at a low height, or you might provide means to feed stacked antennas out-of-phase. **Fig 14** shows an *HFTA* (HF Terrain Assessment) plot of two 5-element 6-meter Yagis, fed either in-phase or out-of-phase to cover a much wider range of elevation angles than the in-phase stack alone.

Fig 15A shows the change in gain for four 2-meter stacked designs, as a function of the spacing in wavelengths between the booms. The 3-element Yagi is mounted on a 2-foot boom (occupying 0.28 λ of that boom). The 5-element Yagi is on a 4-foot boom (0.51 λ of the boom), while the 8-element Yagi is on a 12-foot boom (1.72 λ of boom). The biggest antenna in the group has 16 elements, on a 27-foot boom (4.0 λ of boom). This range of boom lengths pretty much covers the practical range of antennas used by hams.

The stack of two 3-element Yagis peaks at 3.2 dB of additional gain over a single Yagi for 0.75 λ spacing between the booms. Further increases in spacing see the gain change gradually drop off. Fig 15B shows the worst-case F/R of the four stacks, again as a function of boom length. The F/R of a single 3-element Yagi is just over 24 dB, but in the presence of the second 3-element Yagi in the stack, the F/R of the pair oscillates between 15 to 26 dB, finally remaining consistently over the desired 20-dB level for spacings greater than about 1.7 λ, where the gain has fallen about 0.6 dB from the peak possible gain. A boom spacing of 1.7 λ at 146 MHz is 11.5 feet. Thus you must compromise in choosing the boom spacing between achieving maximum gain and the best pattern.

The increase in gain of the stack of two 5-element Yagis peaks at a spacing of about 1 λ (6.7 feet), where the F/R is an excellent 25 dB. Having more elements on a particular length of boom aids in holding a more consistent F/R in the presence of the second antenna.

The gain increase for the bigger stack of 8-element Yagis peaks at a spacing of about 1.5 λ (10.1 feet), where the F/R is more than 27 dB. The 16-element Yagi's gain



Fig 15—Performance of two different 2-meter Yagis (5-elements on 4-foot boom and 8-elements on 12-foot boom) fed in-phase, as a function of spacing between the booms. Note that the distance is measured in wavelengths.

increase is 2.6 dB for a spacing of about 2.25 λ (15.2 feet), where the F/R remains close to 25 dB. The stacking distance of 15.2 feet for an antenna with a 27-foot long boom may be a real challenge physically, requiring a very sturdy rotating mast to withstand wind pressures without bending.

These examples show that the exact spacing between booms is not overly critical, since the gain varies relatively slowly around the peak. Fig 15A shows that the boom spacing needed to achieve peak gain from a stack increases when higher-gain (longer-boom) individual antennas are used in that stack. It also shows that the increase in maximum gain from stacking decreases for long-boom antennas. Fig 15B shows that beyond boom spacings of about 1 λ, the F/R pattern holds well for Yagi designs with booms longer than about 0.5 λ, which is about 4 feet at 146 MHz.

The plots in Fig 15 are representative of typical modern Yagis. You could simply implement these designs as is, and you'll achieve good results. However, we recommend that you model any specific stack you design, just to make sure. Since the boom spacings are displayed in terms of wavelength, you can extend the results for 2 meters to other bands, provided that you use properly scaled Yagi designs to the other bands too.

You can even tweak the element dimensions and spacings of each Yagi used in a stack to optimize the rearward pattern for a particular stacking distance. This strategy can work out well at VHF/UHF, where stacks are often configured for best gain (and pattern) and are "hard-wired" with fixed lengths of feed lines permanently junctioned together.

This is in contrast to the situation at HF (and even on 6 meters). The HF operator usually wants flexibility to select individual Yagis (or combinations of Yagis) from the stack, to match the array's takeoff angle with ionospheric propagation conditions. See Chapter 11, HF Yagi Arrays. The designer of a flexible HF stack thus usually doesn't try to redo the element lengths and spacings of the Yagis to optimize a particular stack.

Stacking Stacks of Different-Frequency Yagis

The investment in a tower is usually substantial, and most hams want to put as many antennas as possible on a tower, provided that interaction between the antennas can be held to a reasonable level. Really ambitious weak-signal VHF/UHF enthusiasts may want "stacked stacks"—sets of stacked Yagis that cover different bands. For example, a VHF contester might want a stack of two 8-element 2-meter Yagis mounted on the same rotating mast as a stack of two 5-element 6-meter Yagis. Let's assume that the boom length of the 8-element 2-meter Yagis is 12 feet (1.78 λ). We'll assume a boom length of 12 feet (0.61 λ) for the 5-element 6-meter Yagis.

From Fig 15, we find the stacking distance between the 8-element 2-meter beams for peak gain and good pattern is 1.5 λ, or 10 feet, but adequate performance can be had for a boom spacing of 0.75 λ, which is 5 feet on 2 meters.

The boom spacing for two 5-element 6-meter beams is 1 λ for peak stacking gain, but a compromise of 0.625 λ (12 feet) still yields an acceptable gain increase of 2 dB over a single Yagi. The overall height of the rotating mast sticking out of the top of the tower is thus set by the 0.625 λ stacking distance on 6 meters, at 12 feet. In-between the 6-meter Yagis at the bottom and top of the rotating mast we will mount the 2-meter Yagi stack. With only 12 feet available on the mast, the spacing for symmetric placement of the two 2-meter Yagis in-between the 6-meter Yagis dictates a distance of only 4 feet between the 2-meter beams. This is less than optimal.

The performance of the 2-meter stack in this "stack within a stack" is affected by the close spacing, but the interactions are not disastrous. The stacking gain is 1.62 dB more than the gain for a single 8-element 2-meter Yagi and the F/R remains above 20 dB across the 2-meter band.

On 6 meters, the stacking gain for two 5-element 6-meter Yagis spaced 12 feet apart is 2.2 dB more than the gain of a single Yagi, while the F/R pattern remains about 20 dB over the weak-signal portion of the 6-meter band. As described in Chapter 11, HF Yagi Arrays, stacking gives more advantages than merely a gain increase, and 6-meter propagation does require coverage of a range of elevation angles because much of the time ionospheric modes are involved.

Increasing the length of the rotating mast to 18 feet sticking out of the top of the tower will increase performance, particularly on 2 meters. The stacking gain on 6 meters will increase to 2.3 dB while the F/R decreases to 18.5 dB, modest changes both. The 18-foot mast allows the 2-meter Yagis to be spaced 6 feet from each other and 6 feet away from both top and bottom 6-meter antennas. The stacking gain goes to 2.14 dB and the F/R approaches 27 dB in the weak-signal portion of the 2-meter band.

Whether the modest increase in stacking gain is worth the cost and mechanical complexity of stacking two 2-meter Yagis in-between a stack of 6-meter Yagis is a choice left to the operator. Certainly the cost and weight of a rotating mast that is 20 feet long (18 feet out of the top of the tower and 2 feet down inside the tower), a mast that must be sturdy enough to support the antennas in high winds without bending, should give pause to even the most enthusiastic 6-meter weak-signal operator.

QUADS FOR VHF

The quad antenna can be built with inexpensive materials, yet its performance is comparable to other arrays of its size. Adjustment for resonance and impedance matching can be accomplished readily. Quads can be stacked horizontally and vertically to provide high gain, without sharply limiting frequency response. Construction of quad antennas for VHF use is covered later in this chapter.

Stacking Quads

Quads can be mounted side by side or one above the other, or both, in the same general way as other beam antennas. Sets of driven elements can also be mounted in front of a screen reflector. The recommended spacing between adjacent element sides is $^1/_2$ λ. Phasing and feed methods are similar to those employed with other antennas described in this chapter.

Adding Quad Directors

Parasitic elements ahead of the driven element work in a manner similar to those in a Yagi array. Closed loops can be used for directors by making them 5% shorter than the driven element. Spacings are similar to those for conventional Yagis. In an experimental model the reflector was spaced 0.25 λ and the director 0.15 λ. A square array using four 3element bays worked extremely well.

VHF AND UHF QUAGIS

At higher frequencies, especially 420 MHz and above, Yagi arrays using dipole-driven elements can be difficult to feed and match, unless special care is taken to keep the feed-point impedance relatively high by proper element spacing and tuning. The cubical quad described earlier overcomes the feed problems to some extent. When many parasitic elements are used, however, the loops are not nearly as convenient to assemble and tune as are straight cylindrical ones used in conventional Yagis. The *Quagi*, designed and popularized by Wayne Overbeck, N6NB, is an antenna having a full-wave loop driven element and reflector, and Yagi type straight rod directors. Construction details and examples are given in the projects later in this chapter.

COLLINEAR ANTENNAS

The information given earlier in this chapter pertains mainly to parasitic arrays, but the collinear array is worthy of consideration in VHF/UHF operations. This array tends to be tolerant of construction tolerances, making it easy to build and adjust for VHF applications. The use of many collinear driven elements was once popular in very large phased arrays, such as those required in moonbounce (EME) communications, but the advent of computer-optimized Yagis has changed this.

Large Collinear Arrays

Bidirectional curtain arrays of four, six, and eight half waves in phase are shown in **Fig 16**. Usually reflector elements are added, normally at about 0.2 λ behind each driven element, for more gain and a unidirectional pattern. Such parasitic elements are omitted from the sketch in the interest of clarity.

The feed-point impedance of two half waves in phase is high, typically 1000 Ω or more. When they are combined in parallel and parasitic elements are added, the feed impedance is low enough for direct connection to open wire line or twin-lead, connected at the points indicated by black dots. With coaxial line and a balun, it is suggested that the universal stub match, Fig 4A, be used at the feed point. All elements should be mounted at their electrical centers, as indicated by open circles in Fig 16. The framework can be metal or insulating material. The metal supporting structure is entirely behind the plane of the reflector elements. Sheet-metal clamps can be cut from scraps of aluminum for this kind of assembly. Collinear elements of this type should be mounted at their centers (where the RF voltage is zero), rather than at their ends, where the voltage is high and insulation losses and detuning can be harmful.

Collinear arrays of 32, 48, 64 and even 128 elements can give outstanding performance. Any collinear array should be fed at the center of the system, to ensure balanced current distribution. This is very important in large arrays, where sets of six or eight driven elements are treated as "sub arrays," and are fed through a balanced harness. The sections of the harness are resonant lengths, usually of open wire line. The 48-element collinear array for 432 MHz in **Fig 17** illustrates this principle.



Fig 16—Element arrangements for 8-, 12- and 16-element collinear arrays. Elements are ½ λ long and spaced ½ λ. Parasitic reflectors, omitted here for clarity, are 5% longer and 0.2 λ behind the driven elements. Feed points are indicated by black dots. Open circles show recommended support points. The elements can run through wood or metal booms, without insulation, if supported at their centers in this way. Insulators at the element ends (points of high RF voltage) detune and unbalance the system.

A reflecting plane, which may be sheet metal, wire mesh, or even closely spaced elements of tubing or wire, can be used in place of parasitic reflectors. To be effective, the plane reflector must extend on all sides to at least $^1/_4$ λ beyond the area occupied by the driven elements. The plane reflector provides high F/B ratio, a clean pattern, and somewhat more gain than parasitic elements, but large physical size limits it to use above 420 MHz. An interesting space-saving possibility lies in using a single plane reflector with elements for two different bands mounted on opposite sides. Reflector spacing from the driven element is not critical. About 0.2 λ is common.

THE CORNER REFLECTOR

When a single driven element is used, the reflector screen may be bent to form an angle, giving an improvement in the radiation pattern and gain. At 222 and 420 MHz its size assumes practical proportions, and at 902 MHz and higher, practical reflectors can approach ideal dimensions (very large in terms of wavelengths), resulting in more gain and sharper patterns. The corner reflector can be used at 144 MHz, though usually at much less than optimum size. For a given aperture, the corner reflector does not equal a parabola in gain, but it is simple to construct, broadbanded, and offers gains from about 9 to 14 dBi, depending on the angle and size. This section was written by Paul M. Wilson, W4HHK.

The corner angle can be 90, 60 or 45°, but the side length must be increased as the angle is narrowed. For a 90° corner, the driven element spacing can be anything from 0.25 to 0.7 λ, 0.35 to 0.75 λ for 60°, and 0.5 to



Fig 17—Large collinear arrays should be fed as sets of no more than eight driven elements each, interconnected by phasing lines. This 48-element array for 432 MHz (A) is treated as if it were four 12-element collinear antennas. Reflector elements are omitted for clarity. The phasing harness is shown at B. Squares represent insulators.



Fig 18—Radiation resistance of the driven element in a corner reflector array for corner angles of 180° (flat sheet), 90°, 60° and 45° as a function of spacing D, as shown in Fig 19.

0.8 λ for 45°. In each case the gain variation over the range of spacings given is about 1.5 dB. Because the spacing is not very critical to gain, it may be varied for impedance-matching purposes. Closer spacings yield lower feed-point impedances, but a folded dipole radiator could be used to raise this to a more convenient level.

Radiation resistance is shown as a function of spacing in **Fig 18**. The maximum gain obtained with minimum spacing is the primary mode (the one generally used at 144, 222 and 432 MHz to maintain reasonable side lengths). A 90° corner, for example, should have a minimum side length (S, **Fig 19**) equal to twice the dipole spacing, or 1 λ long for 0.5-λ spacing. A side length greater than 2 λ is ideal. Gain with a 60° or 90° corner reflector with 1-λ sides is about 10 dB. A 60° corner with 2-λ sides has about 13 dBi gain, and a 45° corner with 3-λ sides has about 14 dBi gain.

Reflector length (L, Fig 19) should be a minimum of 0.6 λ. Less than that spacing causes radiation to increase to the sides and rear, and decreases gain.

Spacing between reflector rods (G, Fig 19) should not exceed 0.06 λ for best results. A spacing of 0.06 λ results in a rear lobe that is about 6% of the forward lobe



Fig 19—Construction of a corner reflector array. The frame can be wood or metal. Reflector elements are stiff wire or tubing. Dimensions for several bands are given in Table 2. Reflector element spacing, G, is the maximum that should be used for the frequency; closer spacings are optional. The hinge permits folding for portable use.

(down 12 dB). A small mesh screen or solid sheet is preferable at the higher frequencies to obtain maximum efficiency and highest F/B ratio, and to simplify construction. A spacing of 0.06 λ at 1296 MHz, for example, requires mounting reflector rods about every $^1/_2$ inch along the sides. Rods or spines may be used to reduce wind loading. The support used for mounting the reflector rods may be of insulating or conductive material. Rods or mesh weave should be parallel to the radiator.

A suggested arrangement for a corner reflector is shown in Fig 19. The frame may be made of wood or metal, with a hinge at the corner to facilitate portable work or assembly atop a tower. A hinged corner is also useful in experimenting with different angles. **Table 2** gives the principal dimensions for corner reflector arrays for 144 to 2300 MHz. The arrays for 144, 222 and 420 MHz have side lengths of twice to four times the driven element spacing. The 915 MHz corner reflectors use side lengths of three times the element spacing, 1296 MHz corners use side lengths of four times the spacing, and 2304 MHz corners employ side lengths of six times the spacing. Reflector lengths of 2, 3, and 4 wavelengths are used on the 915, 1296 and 2304 MHz reflectors, respectively. A 4 × 6 λ reflector closely approximates a sheet of infinite dimensions.

A corner reflector may be used for several bands, or for UHF television reception, as well as amateur UHF work. For operation on more than one frequency, side length and reflector length should be selected for the lowest frequency, and reflector spacing for the highest frequency. The type of driven element plays a part in determining bandwidth, as does the spacing to the corner. A fat cylindrical element (small λ/dia ratio) or triangular dipole (bow tie) gives more bandwidth than a thin driven element. Wider spacings between driven element and corner give greater bandwidths. A small increase in gain can be obtained for any corner reflector by mounting collinear elements in a reflector of sufficient size, but

Table 2
Dimensions of Corner Reflector Arrays for VHF and UHF

Freq, MHz	*Side Length S, in.*	*Dipole to Vertex D, in.*	*Reflector Length L, in.*	*Reflector Spacing G, in.*	*Corner Angle, Vo*	*Radiation Resistance, Ω*
144*	65	27½	48	7¾	90	70
144	80	40	48	4	90	150
222*	42	18	30	5	90	70
222	52	25	30	3	90	150
222	100	25	30	Screen	60	70
420	27	8¾	16¼	$2^5/_8$	90	70
420	54	13½	16¼	Screen	60	70
915	20	6½	25¾	0.65	90	70
915	51	16¾	25¾	Screen	60	65
915	78	25¾	25¾	Screen	45	70
1296	18	4½	27½	½	90	70
1296	48	11¾	27½	Screen	60	65
1296	72	18¼	27½	Screen	45	70
2304	15½	2½	20½	¼	90	70
2304	40	6¾	20½	Screen	60	65
2304	61	10¼	20½	Screen	45	70

*Side length and number of reflector elements somewhat below optimum—slight reduction in gain.

Notes:

915 MHz
Wavelength is 12.9 in.
Side length S is 3 × D, dipole to vertex distance
Reflector length L is 2.0 λ
Reflector spacing G is 0.05 λ

1296 MHz
Wavelength is 9.11 in.
Side length S is 4 × D, dipole to vertex distance
Reflector length L is 3.0 λ
Reflector spacing G is 0.05 λ

2304 MHz
Wavelength is 5.12 in.
Side length S is 6 × D, dipole to vertex distance
Reflector length L is 4.0 λ
Reflector spacing G is 0.05 λ

the simple feed of a dipole is lost if more than two elements are used.

A dipole radiator is usually employed with a corner reflector. This requires a balun between the coaxial line and the balanced feed-point impedance of the antenna. Baluns are easily constructed of coaxial line on the lower VHF bands, but become more difficult at the higher frequencies. This problem may be overcome by using a ground-plane corner reflector, which can be used for vertical polarization. A ground-plane corner with monopole driven element is shown in **Fig 20**. The corner reflector and a $^1/_4$ λ radiator are mounted on the ground plane, permitting direct connection to a coaxial line if the proper spacing is used. The effective aperture is reduced, but at the higher frequencies, second- or third-mode radiator spacing and larger reflectors can be employed to obtain more gain and offset the loss in effective aperture. A J antenna could be used to maintain the aperture area and provide a match to a coaxial line.

For vertical polarization work, four 90° corner reflectors built back-to-back (with common reflectors) could be used for scanning 360° of horizon with modest gain. Feed-line switching could be used to select the desired sector.

TROUGH REFLECTORS

To reduce the overall dimensions of a large corner reflector the vertex can be cut off and replaced with a plane reflector. Such an arrangement is known as a *trough reflector*. See **Fig 21**. Performance similar to that of the large corner reflector can thereby be had, provided that the dimensions of S and T as shown in Fig 21 do not exceed the limits indicated in the figure. This antenna provides performance very similar to the corner reflector, and presents fewer mechanical problems because the plane center portion is relatively easy to mount on the mast. The sides are considerably shorter, as well.

The gain of both corner reflectors and trough reflectors may be increased by stacking two or more and arranging them to radiate in phase, or alternatively by



Angle *α*	*Value of S for maximum gain*	*Gain*	*Value of T*
90°	1.5 λ	13.5 dB	1λ - 1.25 λ
60°	1.75 λ	15 dB	1.0 λ
45°	2.0 λ	16 dB	1.9 λ

Fig 21—The trough reflector. This is a useful modification of the corner reflector. The vertex has been cut off and replaced by a simple plane section. The tabulated data shows the gain obtainable for greater values of S than those covered in Table 2, assuming that the reflector is of adequate size.


"D" — Distance from Radiator to Vertex
"D"
Sides — Rods, Sheet, or Screen on Sides
"V" — Angle Formed by Sides (90°, 60° or 45°)
"V"
"S"
1/4 λ Radiator
Ground Plane Sheet or Mesh
TOP VIEW
"S"
Sides — Rods, Sheet, or Screen on Sides
1/4 λ Radiator
1/2 L
Ground Plane Sheet or Mesh
FRONT VIEW

Fig 20—A ground-plane corner reflector antenna for vertical polarization, such as FM communications or packet radio. The dimension ½ λ in the front view refers to data in Table 2.

adding further collinear dipoles (fed in phase) within a wider reflector. Not more than two or three radiating units should be used, because the great virtue of the simple feeder arrangement would then be lost.

HORN ANTENNAS FOR THE MICROWAVE BANDS

Horn antennas were briefly introduced in the section on coupling energy into and out of waveguides. For amateur purposes, horns begin to show usable gain with practical dimensions in the 902 MHz band.

It isn’t necessary to feed a horn with waveguide. If only two sides of a pyramidal horn are constructed, the antenna may be fed at the apex with a two-conductor transmission line. The impedance of this arrangement is on the order of 300 to 400 Ω. A 60° two-sided pyramidal horn with 18 inch sides is shown in **Fig 22**. This antenna has a theoretical gain of 15 dBi at 1296 MHz, although the feed system detailed in **Fig 23** probably degrades this value somewhat. A $^1/_4$ λ, 150-Ω matching section made from two parallel lengths of twin-lead connects to a bazooka balun made from RG-58 cable and a brass tube. This matching system was assembled strictly for the purpose of demonstrating the two-sided horn in a 50-Ω system. In a practical installation the horn would be fed with open-wire line and matched to 50 Ω at the station equipment.



Fig 22—An experimental two-sided pyramidal horn constructed in the ARRL laboratory. A pair of muffler clamps allows mounting the antenna on a mast. This model has sheet-aluminum sides, although window screen would work as well. Temporary elements could be made from cardboard covered with aluminum foil. The horizontal spreaders are Plexiglas rod. Oriented as shown here, the antenna radiates horizontally polarized waves.

PARABOLIC ANTENNAS

When an antenna is located at the focus of a parabolic reflector (dish), it is possible to obtain considerable gain. Furthermore, the beamwidth of the radiated energy will be very narrow, provided all the energy from the driven element is directed toward the reflector. This section was written by Paul M. Wilson, W4HHK.

Gain is a function of parabolic reflector diameter, surface accuracy and proper illumination of the reflector by the feed. Gain may be found from

$$G = 10 \log k \left(\frac{\pi D}{\lambda} \right)^2 \qquad \text{(Eq 1)}$$

where

G = gain over an isotropic antenna, dBi (subtract 2.15 dB for gain over a dipole)
k = efficiency factor, usually about 55%
D = dish diameter in feet
λ = wavelength in feet

See **Table 3** for parabolic antenna gain for the bands 420 MHz through 10 GHz and diameters of 2 to 30 feet.

A close approximation of beamwidth may be found from

$$\psi = \frac{70\lambda}{D} \qquad \text{(Eq 2)}$$

where

ψ = beamwidth in degrees at half-power points (3 dB down)
D = dish diameter in feet
λ = wavelength in feet

At 420 MHz and higher, the parabolic dish becomes a practical antenna. A simple, single feed point eliminates phasing harnesses and balun requirements. Gain is dependent on good surface accuracy, which is more difficult to achieve with increasing frequency. Surface



Fig 23—Matching system used to test the horn. Better performance would be realized with open wire line. See text.

Table 3
Gain, Parabolic Antennas*

	Dish Diameter (Feet)						
Frequency	*2*	*4*	*6*	*10*	*15*	*20*	*30*
420 MHz	6.0	12.0	15.5	20.0	23.5	26.0	29.5
902	12.5	18.5	22.0	26.5	30.0	32.5	36.0
1215	15.0	21.0	24.5	29.0	32.5	35.0	38.5
2300	20.5	26.5	30.0	34.5	38.0	40.5	44.0
3300	24.0	30.0	33.5	37.5	41.5	43.5	47.5
5650	28.5	34.5	38.0	42.5	46.0	48.5	52.0
10 GHz	33.5	39.5	43.0	47.5	51.0	53.5	57.0

*Gain over an isotropic antenna (subtract 2.1 dB for gain over a dipole antenna). Reflector efficiency of 55% assumed.



Fig 24—Details of the parabolic curve, $Y^2 = 4SX$. This curve is the locus of points that are equidistant from a fixed point, the focus (F), and a fixed line (AB) that is called the *directrix*. Hence, FP = PC. The focus (F) is located at coordinates S,0.

errors should not exceed $^1/_8$ λ in amateur work. At 430 MHz $^1/_8$ λ is 3.4 inches, but at 10 GHz it is 0.1476 inch! Mesh can be used for the reflector surface to reduce weight and wind loading, but hole size should be less than $^1/_{12}$ λ. At 430 MHz the use of 2-inch hole diameter poultry netting (chicken wire) is acceptable. Fine mesh aluminum screening works well as high as 10 GHz.

A support form may be fashioned to provide the proper parabolic shape by plotting a curve (**Fig 24**) from

$$Y^2 = 4SX$$

as shown in the figure.

Optimum illumination occurs when power at the reflector edge is 10 dB less than that at the center. A circular waveguide feed of correct diameter and length for the frequency and correct beamwidth for the dish focal length to diameter (f/D) ratio provides optimum illumination at 902 MHz and higher. This, however, is impractical at 432 MHz, where a dipole and plane reflector are often used. An f/D ratio between 0.4 and 0.6 is considered ideal for maximum gain and simple feeds.

The focal length of a dish may be found from

$$f = \frac{D^2}{16d} \qquad \text{(Eq 3)}$$

where

f = focal length
D = diameter
d = depth distance from plane at mouth of dish to vertex (see Fig 17)

The units of focal length f are the same as those used to measure the depth and diameter. **Table 4** gives the subtended angle at focus for dish f/D ratios from 0.2 to 1.0. A dish, for example, with a typical f/D of 0.4 requires a 10-dB beamwidth of 130°. A circular waveguide feed with a diameter of approximately 0.7 λ provides nearly optimum illumination, but does not uniformly illuminate the reflector in both the magnetic (TM) and electric (TE) planes. **Fig 25** shows data for plotting radiation patterns from circular guides. The waveguide feed aperture can be modified to change the beamwidth.

One approach used successfully by some experimenters is the use of a disc at a short distance behind the aperture as shown in **Fig 26**. As the distance between the aperture and disc is changed, the TM plane patterns become alternately broader and narrower than with an unmodified aperture. A disc about 2 λ in diameter appears to be as effective as a much larger one. Some experimenters have noted a 1 to 2 dB increase in dish gain with this modified feed. Rectangular waveguide feeds can also be used, but dish illumination is not as uniform as with round guide feeds.

The circular feed can be made of copper, brass, aluminum or even tin in the form of a coffee or juice can, but the latter must be painted on the outside to prevent rust or corrosion. The circular feed must be within a proper size (diameter) range for the frequency being used.

This feed operates in the dominant circular waveguide mode known as the TE_{11} mode. The guide must be large enough to pass the TE_{11} mode with no attenuation, but smaller than the diameter that permits the next higher TM_{01} mode to propagate. To support the desirable TE_{11} mode in circular waveguide, the cutoff frequency, F_C, is given by

$$F_C\,(TE_{11}) = \frac{6917.26}{d\,(\text{inches})} \qquad \text{(Eq 4)}$$

where

F_C = cutoff frequency in MHz for TE_{11} mode
d = waveguide inner diameter

Circular waveguide will support the TM_{01} mode having a cutoff frequency

$$F_C\,(TM_{01}) = \frac{9034.85}{d\,(\text{inches})} \qquad \text{(Eq 5)}$$

The wavelength in a waveguide always exceeds the free-space wavelength and is called guide wavelength, λ_g. It is related to the cutoff frequency and operating frequency by the equation

$$\lambda_g = \frac{11802.85}{\sqrt{f_0^{\,2} - f_C^{\,2}}} \qquad \text{(Eq 6)}$$

where

λ_g = guide wavelength, inches
f_0 = operating frequency, MHz
f_C = TE_{11} waveguide cutoff frequency, MHz

An inside diameter range of about 0.66 to 0.76 l is



Fig 25—This graph can be used in conjunction with Table 4 for selecting the proper diameter waveguide to illuminate a parabolic reflector.

Table 4
f/D Versus Subtended Angle at Focus of a Parabolic Reflector Antenna

f/D	*Subtended Angle (Deg.)*	*f/D*	*Subtended Angle (Deg.)*
0.20	203	0.65	80
0.25	181	0.70	75
0.30	161	0.75	69
0.35	145	0.80	64
0.40	130	0.85	60
0.45	117	0.90	57
0.50	106	0.95	55
0.55	97	1.00	52
0.60	88		

Taken from graph “f/D vs Subtended Angle at Focus,” page 170 of the 1966 *Microwave Engineers’ Handbook and Buyers Guide*. Graph courtesy of K. S. Kelleher, Aero Geo Astro Corp, Alexandria, Virginia

Table 5
Circular Waveguide Dish Feeds

Freq. (MHz)	*Inside Diameter Circular Waveguide Range (in.)*
915	8.52-9.84
1296	6.02-6.94
2304	3.39-3.91
3400	2.29-2.65
5800	1.34-1.55
10,250	0.76-0.88



Fig 26—Details of a circular waveguide feed.

suggested. The lower frequency limit (longer dimension) is dictated by proximity to the cutoff frequency. The higher frequency limit (shorter dimension) is dictated by higher order waves. See **Table 5** for recommended inside diameter dimensions for the 902- to 10,000-MHz amateur bands.

The probe that excites the waveguide and makes the transition from coaxial cable to waveguide is $^1/_4$ λ long and spaced from the closed end of the guide by $^1/_4$ guide wavelength. The length of the feed should be two to three guide wavelengths. The latter is preferred if a second probe is to be mounted for polarization change or for polaplexer work where duplex communication (simultaneous transmission and reception) is possible because of the isolation between two properly located and oriented probes. The second probe for polarization switching or polaplexer work should be spaced $^3/_4$ guide wavelength from the closed end and mounted at right angles to the first probe.

The feed aperture is located at the focal point of the dish and aimed at the center of the reflector. The feed mounts should permit adjustment of the aperture either side of the focal point and should present a minimum of blockage to the reflector. Correct distance to the dish center places the focal point about 1 inch inside the feed aperture. The use of a nonmetallic support minimizes blockage. PVC pipe, fiberglass and Plexiglas are commonly used materials. A simple test by placing a material in a microwave oven reveals if it is satisfactory up to 2450 MHz. PVC pipe has tested satisfactorily and appears to work well at 2300 MHz. A simple, clean looking mount for a 4-foot dish with 18 inches focal length, for example, can be made by mounting a length of 4-inch PVC pipe using a PVC flange at the center of the dish. At 2304 MHz the circular feed is approximately 4 inches ID, making a snug fit with the PVC pipe. Precautions should be taken to keep rain and small birds from entering the feed.

Never look into the open end of a waveguide when power is applied, or stand directly in front of a dish while transmitting. Tests and adjustments in these areas should be done while receiving or at extremely low levels of transmitter power (less than 0.1 watt). The US Government has set a limit of 10 mW/cm^2 averaged over a 6-minute period as the safe maximum. Other authorities believe even lower levels should be used. Destructive thermal heating of body tissue results from excessive exposure. This heating effect is especially dangerous to the eyes. The accepted safe level of 10 mW/cm^2 is reached in the near field of a parabolic antenna if the level at $2D^2/\lambda$ is 0.242 mW/cm^2. The equation for power density at the far-field boundary is

$$\text{Power density} = \frac{137.8\ P}{D^2}\ \text{mW/cm}^2 \qquad \text{(Eq 7)}$$

where

P = average power in kilowatts
D = antenna diameter in feet
λ = wavelength in feet

New commercial dishes are expensive, but surplus ones can often be purchased at low cost. Some amateurs build theirs, while others modify UHF TV dishes or circular metal snow sleds for the amateur bands. **Fig 27** shows a dish using the homemade feed just described.



Fig 27—Coffee-can 2304 MHz feed described in text and Fig 26 mounted on a 4-ft dish.



Fig 29—Detailed look at the hub assembly for the ZL1BJQ dish. Most of the structural members are made from ¾-inch T section.



Fig 28—Aluminum framework for a 23-foot dish under construction by ZL1BJQ.

Photos showing a highly ambitious dish project under construction by ZL1BJQ appear in **Figs 28** and **29**. Practical details for constructing this type of antenna are given in Chapter 19. Dick Knadle, K2RIW, described modern UHF antenna test procedures in February 1976 *QST* (see Bibliography). Also see Chapter 19.

OMNIDIRECTIONAL ANTENNAS FOR VHF AND UHF

Local work with mobile stations requires an antenna with wide coverage capabilities. Most mobile work is on FM, and the polarization used with this mode is generally vertical. Some simple vertical systems are described below. Additional material on antennas of this type is presented in Chapter 16, Mobile and Maritime Antennas.

Ground-plane Antennas for 144, 222 and 440 MHz

For the FM operator living in the primary coverage area of a repeater, the ease of construction and low cost of a $^1/_4$ λ ground-plane antenna make it an ideal choice. Three different types of construction are detailed in Figs 30 through 43; the choice of construction method depends upon the materials at hand and the desired style of antenna mounting.

The 144-MHz model shown in **Fig 30** uses a flat piece of sheet aluminum, to which radials are connected with machine screws. A 45° bend is made in each of the radials. This bend can be made with an ordinary bench vise. An SO239 chassis connector is mounted at the center of the aluminum plate with the threaded part of the connector facing down. The vertical portion of the


19" Long #12 Wire
Soldered to Coaxial
Connector
45°
19"
A
B
SO–239 Coax
Connector
C
D
A,B,C,D – 19" Lengths of 3/16" Aluminum
Rod Bent Down at 45° Angle
Aluminum Sheet –
Dimensions Not Critical
#4 Machine Screws
Star Washer and Nut
(8 Places)
5/8" Hole
for SQ-239
Connector
Bend Down at
45 ° Angle
4"

Fig 30—These drawings illustrate the dimensions for the 144-MHz ground-plane antenna. The radials are bent down at a 45° angle.


12-1/2" Long #12 Wire
Soldered to Coaxial
Connector
45°
SQ-239 Coaxial Connector
A
B
C
D
A,B,C,D – 12-1/2" Lengths,
3/16" Aluminum Rod
#4 Machine Screws,
Star Washer and Nut
(4 Places)
Mounting Tab
Bent Down
at 90° Angle
5/8" Hole
for SQ-239
Connector
Bent Down at
45 ° Angle

Fig 31—Dimensional information for the 222-MHz ground-plane antenna. Lengths for A, B, C and D are the total distances measured from the center of the SO-239 connector. The corners of the aluminum plate are bent down at a 45° angle rather than bending the aluminum rod as in the 144-MHz model. Either method is suitable for these antennas.



Frequency (MHz)	A (Inches)	B (Inches)
146	19-5/16″	18-11/16″
225	12-5/8″	12″
445	6-3/8″	5-3/4″

Fig 32—Simple ground-plane antenna for the 144-, 222- and 440-MHz bands. The vertical element and radials are $^{3}/_{32}$- or $^{1}/_{16}$-in. brass welding rod. Although $^{3}/_{32}$-in. rod is preferred for the 144-MHz antenna, #10 or #12 copper wire can also be used.

antenna is made of #12 copper wire soldered directly to the center pin of the SO-239 connector.

The 222-MHz version, **Fig 31**, uses a slightly different technique for mounting and sloping the radials. In this case the corners of the aluminum plate are bent down at a 45° angle with respect to the remainder of the plate. The four radials are held to the plate with machine screws, lock washers and nuts. A mounting tab is included in the design of this antenna as part of the aluminum base. A compression type of hose clamp could be used to secure the antenna to a mast. As with the 144-MHz version, the vertical portion of the antenna is soldered directly to the SO-239 connector.



Fig 33—A 440-MHz ground-plane constructed using only an SO-239 connector, no. 4-40 hardware and $^{1}/_{16}$-in. brass welding rod.

A very simple method of construction, shown in **Figs 32** and **33**, requires nothing more than an SO-239 connector and some no. 4-40 hardware. A small loop formed at the inside end of each radial is used to attach the radial directly to the mounting holes of the coaxial connector. After the radial is fastened to the SO-239 with no. 4-40 hardware, a large soldering iron or propane torch is used to solder the radial and the mounting hardware to the coaxial connector. The radials are bent to a 45° angle and the vertical portion is soldered to the center pin to complete the antenna. The antenna can be mounted by passing the feed line through a mast of ¾-inch ID plastic or aluminum tubing. A compression hose clamp can be used to secure the PL-259 connector, attached to the feed line, in the end of the mast. Dimensions for the 144-, 222- and 440-MHz bands are given in Fig 32.

If these antennas are to be mounted outside it is wise to apply a small amount of RTV sealant or similar material around the areas of the center pin of the connector to prevent the entry of water into the connector and coax line.

The J-Pole Antenna

The J-Pole is a half-wave antenna that is end-fed at its bottom. Since the radiator is longer than that of a ¼-wave ground-plane antenna, the vertical lobe is compressed down toward the horizon and it has about 1.5 dB of gain compared to the ground-plane configuration. The stub-matching section used to transform the high impedance seen looking into a half-wave to 50 Ω coax is shorted at the bottom, making the antenna look like the letter "J," and giving the antenna its name.

Rigid copper tubing, fittings and assorted hardware can be used to make a really rugged J-pole antenna for 2 meters. When copper tubing is used, the entire assembly can be soldered together, ensuring electrical integrity, and making the whole antenna weatherproof. This


Clamp Assembly Detail
Normal clamp
12
Excess clamp cut off this end.
Flattened clamp
13
14
(B)
#19 hole drilled (2 places)
7
3/4
Part of Item 1 *
56–3/4″ Overall
3
8
1/2
18–3/4″
4
Part of Item 2 *
1/2
3/4
1–1/4″
1/2
1/2
1/2
1/2
6
3/4
9
Part of Item 2 *
5
* See Text
3/4
10
Part of Item 1 *
(A)
3–1/4″ Overall
3/4
11
3/4

Fig 34—At A, exploded assembly diagram of all-copper J-Pole antenna. At B, detail of clamp assemblies. Both clamp assemblies are the same.

Item	***Qty***	***Part or Material Name***
1	**1**	**¾-inch × 10 foot length of rigid copper tubing (enough for 2 antennas, 60 inches per antenna)**
2	**1**	**½-inch × 10 ft length of rigid copper tubing (enough for 6 antennas, 20 inches per antenna)**
3	**2**	**¾-inch copper pipe clamps**
4	**2**	**½-inch copper pipe clamps**
5	**1**	**½-inch copper elbow**
6	**1**	**¾ × ½-inch copper tee**
7	**1**	**¾-inch copper end cap**
8	**1**	**½-inch copper end cap**
9	**1**	**½ × 1¼-inch copper nipple (Make from item 2. See text)**
10	**1**	**¾ × 3 ¼-inch copper nipple (Make from item 1. See text)**
11	**1**	**Your choice of coupling to mast fitting (¾ × 1 inch NPT used at KD8JB)**
12	**6**	**# 8-32 × ½-inch brass machine screws (round, pan, or binder head)**
13	**6**	**# 8 brass flat washers**
14	**6**	**# 8-32 brass hex nuts**

material came from an article by Michael Hood, KD8JB, in *The ARRL Antenna Compendium,Vol. 4*.

No special hardware or machined parts are used in this antenna, nor are insulating materials needed, since the antenna is always at dc ground. Best of all, even if the parts aren't on sale, the antenna can be built for less than $15. If you only build one antenna, you'll have enough tubing left over to make most of a second antenna.

Construction

Copper and brass is used exclusively in this antenna. These metals get along together, so dissimilar metal corrosion is eliminated. Both metals solder well, too. See **Fig 34**. Cut the copper tubing to the lengths indicated. Item 9 is a $1^1/_4$-inch nipple cut from the 20-inch length of $^1/_2$-inch tubing. This leaves $18^3/_4$ inches for the $^1/_4$-matching stub. Item 10 is a $3^1/_4$-inch long nipple cut from the 60-inch length of $^3/_4$-inch tubing. The $^3/_4$-wave element should measure $56^3/_4$-inches long. Remove burrs from the ends of the tubing after cutting, and clean the mating surfaces with sandpaper, steel wool, or emery cloth.

After cleaning, apply a very thin coat of flux to the mating elements and assemble the tubing, elbow, tee, end caps and stubs. Solder the assembled parts with a propane torch and rosin-core solder. Wipe off excess solder with a damp cloth, being careful not to burn yourself. The copper tubing will hold heat for a long time after you've finished soldering. After soldering, set the assembly aside to cool.

Flatten one each of the $^1/_2$-inch and $^3/_4$-inch pipe clamps. Drill a hole in the flattened clamp as shown in Fig 34A. Assemble the clamps and cut off the excess metal from the flattened clamp using the unmodified clamp as a template. Disassemble the clamps.

Assemble the $^1/_2$-inch clamp around the $^1/_4$-wave element and secure with two of the screws, washers, and nuts as shown in Fig 34B. Do the same with the $^3/_4$-inch clamp around the $^3/_4$-wave element. Set the clamps initially to a spot about 4 inches above the bottom of the "J" on their respective elements. Tighten the clamps only finger tight, since you'll need to move them when tuning.

Tuning

The J-Pole can be fed directly from 50-Ω coax through a choke balun (3 turns of the feed coax rolled into a coil about 8 inches in diameter and held together with electrical tape). Before tuning, mount the antenna vertically, about 5 to 10 feet from the ground. A short TV mast on a tripod works well for this purpose. When tuning VHF antennas, keep in mind that they are sensitive to nearby objects—such as your body. Attach the feed line to the clamps on the antenna, and make sure all the nuts and screws are at least finger tight. It really doesn't matter to which element (¾-wave element or stub) you attach the coaxial center lead. The author has done it both ways with no variation in performance. Tune the antenna by moving the two feed-point clamps equal distances a small amount each time until the SWR is minimum at the desired frequency. The SWR will be close to 1:1.

Final Assembly

The final assembly of the antenna will determine its long-term survivability. Perform the following steps with care. After adjusting the clamps for minimum SWR, mark the clamp positions with a pencil and then remove the feed line and clamps. Apply a very thin coating of flux to the inside of the clamp and the corresponding surface of the antenna element where the clamp attaches. Install the clamps and tighten the clamp screws.

Solder the feed line clamps where they are attached to the antenna elements. Now, apply a small amount of solder around the screw heads and nuts where they contact the clamps. Don't get solder on the screw threads! Clean away excess flux with a non-corrosive solvent. After final assembly and erecting/mounting the antenna in the desired location, attach the feed line and secure with the remaining washer and nut. Weather-seal this joint with RTV. Otherwise, you may find yourself repairing the feed line after a couple years.

On-the-Air Performance

Years ago, prior to building the first J-Pole antenna for this station, the author used a standard $^1/_4$-wave ground plane vertical antenna. While he had no problem working various repeaters around town with a $^1/_4$-wave antenna, simplex operation left a lot to be desired. The J-Pole performs just as well as a Ringo Ranger, and significantly better than the $^1/_4$-wave ground-plane vertical.

Practical 6-Meter Yagis

Boom length often proves to be the deciding factor when one selects a Yagi design. **Table 6** shows three 6-meter Yagis designed for convenient boom lengths (6, 12 and 22 feet). The 3-element, 6-foot boom design has 8.0 dBi gain in free space; the 12 foot boom, 5-element version has 10.1 dBi gain, and the 22-foot, 7 element Yagi has a gain of 11.3 dBi. All antennas exhibit better than 22 dB front-to-rear ratio and cover 50 to 51 MHz with better than 1.7:1 SWR.

Half-element lengths and spacings are given in the table. Elements can be mounted to the boom as shown in **Fig 35**. Two muffler clamps hold each aluminum plate to the boom, and two U bolts fasten each element to the plate, which is 0.25 inches thick and 4 × 4 inches square. Stainless steel is the best choice for hardware, however, galvanized hardware can be substituted. Automotive muffler clamps do not work well in this application, because they are not galvanized and quickly rust once exposed to the weather. Please note that the element lengths shown in Table 6 are half the overall element lengths. See page 20-7 to 20-11 in Chapter 20 for practical details of telescoping aluminum elements.



Fig 35—The element to boom clamp. U bolts are used to hold the element to the plate, and 2-in. galvanized muffler clamps hold the plates to the boom.

The driven element is mounted to the boom on a Bakelite or G-10 fiberglass plate of similar dimension to the other mounting plates. A 12-inch piece of Plexiglas rod is inserted into the driven element halves. The Plexiglas allows the use of a single clamp on each side of the element and also seals the center of the elements against moisture. Self-tapping screws are used for electrical connection to the driven element.

Refer to **Fig 36** for driven-element and hairpin match details. A bracket made from a piece of aluminum is used to mount the three SO239 connectors to the driven element plate. A 4:1 transmission-line balun connects the two element halves, transforming the 200 Ω resistance at the hairpin match to 50 Ω at the center connector. Note



Fig 36—This shows how the driven element and feed system are attached to the boom. The phasing line is coiled and taped to the boom. The center of the hairpin loop may be connected to the boom electrically and mechanically if desired.
Phasing-line lengths:
For cable with 0.80 velocity factor – 7 ft, $10^{3}/_{8}$ in.
For cable with 0.66 velocity factor – 6 ft, $5^{3}/_{4}$ in.

Table 6
Optimized 6-Meter Yagi Designs

	Spacing Between Elements inches	*Seg 1 OD* Length inches*	*Seg2 OD* Length inches*	*Midband Gain F/R*
306-06				
OD		0.750	0.625	
Refl.	0	36	23.500	7.9 dBi
D.E.	24	36	16.000	27.2 dB
Dir. 1	66	36	15.500	
506-12				
OD		0.750	0.625	
Refl.	0	36	24.000	10.1 dBi
D.E.	24	36	17.125	24.7 dB
Dir. 1	12	36	19.375	
Dir. 2	44	36	18.250	
Dir. 3	58	36	15.375	
706-22				
OD		0.750	0.625	
Refl.	0	36	25.000	11.3 dBi
D.E.	27	36	17.250	29.9 dB
Dir. 1	16	36	18.500	
Dir. 2	51	36	15.375	
Dir. 3	54	36	15.875	
Dir. 4	53	36	16.500	
Dir. 5	58	36	12.500	

*See pages 20-7 to 20-11 for telescoping aluminum tubing details.

that the electrical length of the balun is λ/2, but the physical length will be shorter due to the velocity factor of the particular coaxial cable used. The hairpin is connected directly across the element halves. The exact center of the hairpin is electrically neutral and should be fastened to the boom. This has the advantage of placing the driven element at dc ground potential.

The hairpin match requires no adjustment as such. However, you may have to change the length of the driven element slightly to obtain the best match in your preferred portion of the band. Changing the driven-element length will not adversely affect antenna performance. *Do not adjust the lengths or spacings of the other elements—they are optimized already*. If you decide to use a gamma match, add 3 inches to each side of the driven element lengths given in the table for all antennas.

High-Performance Yagis for 144, 222 and 432 MHz

This construction information is presented as an introduction to the three high-performance VHF/UHF Yagis that follow. All were designed and built by Steve Powlishen, K1FO. For years the design of long Yagi antennas seemed to be a mystical black art. The problem of simultaneously optimizing 20 or more element spacings and element lengths presented an almost unsolvable set of simultaneous equations. With the unprecedented increase in computer power and widespread availability of antenna analysis software, we are now able to quickly examine many Yagi designs and determine which approaches work and which designs to avoid.

At 144 MHz and above, most operators desire Yagi antennas two or more wavelengths in length. This length (2λ) is where most classical designs start to fall apart in terms of gain per boom length, bandwidth and pattern quality. Extensive computer and antenna range analysis has proven that the best possible design is a Yagi that has both varying element spacings and varying element lengths.

This design approach starts with closely spaced directors. The director spacings gradually increase until a constant spacing of about 0.4 λ is reached. Conversely, the director lengths start out longest with the first director and decrease in length in a decreasing rate of change until they are virtually constant in length. This method of construction results in a wide gain bandwidth. A bandwidth of 7% of the center frequency at the –1 dB forward-gain points is typical for these Yagis even when they are longer than 10 λ. The log-taper design also reduces the rate of change in driven-element impedance vs frequency. This allows the use of simple dipole driven elements while still obtaining acceptable driven-element SWR over a wide frequency range. Another benefit is that the resonant frequency of the Yagi changes very little as the boom length is increased.

The driven-element impedance also changes moderately with boom length. The tapered approach creates a Yagi with a very clean radiation pattern. Typically, first side lobe levels of ~17 dB in the E plane, ~15 dB in the H plane, and all other lobes at ~20 dB or more are possible on designs from 2 λ to more than 14 λ.

The actual rate of change in element lengths is determined by the diameter of the elements (in wavelengths). The spacings can be optimized for an individual boom length or chosen as a best compromise for most boom lengths.

The gain of long Yagis has been the subject of much debate. Recent measurements and computer analysis by both amateurs and professionals indicates that given an optimum design, doubling a Yagi's boom length will result in a maximum theoretical gain increase of about 2.6 dB. In practice, the real gain increase may be less because of escalating resistive losses and the greater possibility of construction error. **Fig 37** shows the maximum possible gain per boom length expressed in decibels, referenced to an isotropic radiator. The actual number of directors does not play an important part in determining the gain vs boom length as long as a reasonable number of directors are used. The use of more directors per boom length will normally give a wider gain bandwidth, however, a point exists where too many directors will adversely affect all performance aspects.

While short antennas (< 1.5 λ) may show increased gain with the use of quad or loop elements, long Yagis (> 2 λ) will not exhibit measurably greater forward gain or pattern integrity with loop-type elements. Similarly, loops used as driven elements and reflectors will not significantly change the properties of a long log-taper Yagi. Multiple-dipole driven-element assemblies will also not result in any significant gain increase per given boom length when compared to single-dipole feeds.

Once a long-Yagi director string is properly tuned, the reflector becomes relatively non critical. Reflector spacings between 0.15 λ and 0.2 λ are preferred. The spacing can be chosen for best pattern and driven element impedance. Multiple-reflector arrangements will not significantly increase the forward gain of a Yagi which has its directors properly optimized for forward gain. Many multiple-reflector schemes such as tri-reflectors and corner reflectors have the disadvantage of lowering the driven element impedance compared to a single optimum-length reflector. The plane or grid reflector, shown in **Fig 38**, may however reduce the intensity of unwanted rear lobes. This can be used to reduce noise pickup on EME or satellite arrays. This type of reflector will usually increase the driven-element impedance compared to a single reflector. This sometimes makes driven-element matching easier. Keep in mind that even for EME, a plane reflector will add considerable wind load and weight for



Fig 37—This chart shows maximum gain per boom length for optimally designed long Yagi antennas.



Fig 38—Front and side views of a plane-reflector antenna.

only a few tenths of a decibel of receive signal-to-noise improvement.

Yagi Construction

Normally, aluminum tubing or rod is used for Yagi elements. Hard-drawn enamel-covered copper wire can also be used on Yagis above 420 MHz. Resistive losses are inversely proportional to the square of the element diameter and the square root of its conductivity.

Element diameters of less than $^3/_{16}$ inch or 4 mm should not be used on any band. The size should be chosen for reasonable strength. Half-inch diameter is suitable for 50 MHz, $^3/_{16}$ to $^3/_8$ inch for 144 MHz and $^3/_{16}$ inch is recommended for the higher bands. Steel, including stainless steel and unprotected brass or copper wire, should not be used for elements.

Boom material may be aluminum tubing, either square or round. High-strength aluminum alloys such as 6061-T6 or 6063-T651 offer the best strength-to-weight advantages. Fiberglass poles have been used (where available as surplus). Wood is a popular low-cost boom material. The wood should be well seasoned and free from knots. Clear pine, spruce and Douglas fir are often used. The wood should be well treated to avoid water absorption and warping.

Elements may be mounted insulated or uninsulated, above or through the boom. Mounting uninsulated elements through a metal boom is the least desirable method unless the elements are welded in place. The Yagi elements will oscillate, even in moderate winds. Over several years this element oscillation will work open the boom holes. This will allow the elements to move in the boom. This will create noise (in your receiver) when the wind blows, as the element contact changes. Eventually the element-to-boom junction will corrode (aluminum oxide is a good insulator). This loss of electrical contact between the boom and element will reduce the boom's effect and change the resonant frequency of the Yagi.

Noninsulated elements mounted above the boom will perform fine as long as a good mechanical connection is made. Insulating blocks mounted above the boom will also work, but they require additional fabrication. One of the most popular construction methods is to mount the elements through the boom using insulating shoulder washers. This method is lightweight and durable. Its main disadvantage is difficult disassembly, making this method of limited use for portable arrays.

If a conductive boom is used, element lengths must be corrected for the mounting method used. The amount of correction is dependent upon the boom diameter in



Fig 39—Yagi element correction vs boom diameter. Curve A is for elements mounted through a round or square conductive boom, with the elements in mechanical contact with the boom. Curve B is for insulated elements mounted through a conductive boom, and for elements mounted on top of a conductive boom (elements make electrical contact with the boom). The patterns were corrected to computer simulations to determine Yagi tuning. The amount of element correction is not affected by element diameter.



Fig 40—Measured E-plane pattern for the 22-element Yagi. Note: This antenna pattern is drawn on a linear dB grid, rather than on the standard ARRL log-periodic grid, to emphasize low sidelobes.

wavelengths. See **Fig 39**. Elements mounted through the boom and not insulated require the greatest correction. Mounting on top of the boom or through the boom on insulated shoulder washers requires about half of the through-the-boom correction. Insulated elements mounted at least one element diameter above the boom require no correction over the free-space length.

The three following antennas have been optimized for typical boom lengths on each band.

A HIGH-PERFORMANCE 432-MHz YAGI

This 22-element, 6.1-λ, 432-MHz Yagi was originally designed for use in a 12-Yagi EME array built by K1FO. A lengthy evaluation and development process preceded its construction. Many designs were considered and then analyzed on the computer. Next, test models were constructed and evaluated on a home-made antenna range. The resulting design is based on WlEJ's computer-optimized spacings.

The attention paid to the design process has been worth the effort. The 22-element Yagi not only has exceptional forward gain (17.9 dBi), but has an unusually clean radiation pattern. The measured E-plane pattern is shown in **Fig 40**. Note that a 1-dB-per-division axis is used to show pattern detail. A complete description of the design process and construction methods appears in December 1987 and January 1988 *QST*.

Table 7
Specifications for 432-MHz Yagi Family

No. of Ele.	*Boom length(λ)*	*Gain (dBi)**	*F/B ratio (dB)*	*DE imped (Ω)*	*Beamwidth E/H (°)*	*Stacking E/H (inches)*
15	3.4	15.67	21	23	30/32	53/49
16	3.8	16.05	19	23	29/31	55/51
17	4.2	16.45	20	27	28/30	56/53
18	4.6	16.8	25	32	27/29	58/55
19	4.9	17.1	25	30	26/28	61/57
20	5.3	17.4	21	24	25.5/27	62/59
21	5.7	17.65	20	22	25/26.5	63/60
22	6.1	17.9	22	25	24/26	65/62
23	6.5	18.15	27	30	23.5/25	67/64
24	6.9	18.35	29	29	23/24	69/66
25	7.3	18.55	23	25	22.5/23.5	71/68
26	7.7	18.8	22	22	22/23	73/70
27	8.1	19.0	22	21	21.5/22.5	75/72
28	8.5	19.20	25	25	21/22	77/75
29	8.9	19.4	25	25	20.5/21.5	79/77
30	9.3	19.55	26	27	20/21	80/78
31	9.7	19.7	24	25	19.6/20.5	81/79
32	10.2	19.8	23	22	19.3/20	2/80
33	10.6	9.9	23	23	19/19.5	83/81
34	11.0	20.05	25	22	18.8/19.2	84/82
35	11.4	20.2	27	25	18.5/19.0	85/83
36	11.8	20.3	27	26	18.3/18.8	86/84
37	12.2	20.4	26	26	18.1/18.6	87/85
38	12.7	20.5	25	25	18.9/18.4	88/86
39	13.1	20.6	25	23	18.7/18.2	89/87
40	13.5	20.8	26	21	17.5/18	90/88

*Gain is approximate real gain based on gain measurements made on six different-length Yagis.

Like other log-taper Yagi designs, this one can easily be adapted to other boom lengths. Versions of this Yagi have been built by many amateurs. Boom lengths ranged between 5.3 λ (20 elements) and 12.2 λ (37 elements).

The size of the original Yagi (169 inches long, 6.1 λ) was chosen so the antenna could be built from small-diameter boom material ($^{7}/_{8}$-inch and 1 inch round 6061-T6 aluminum) and still survive high winds and ice loading. The 22-element Yagi weighs about 3.5 pounds and has a wind load of approximately 0.8 square feet. This allows a high-gain EME array to be built with manageable wind load and weight. This same low wind load and weight lets the tropo operator add a high-performance 432-MHz array to an existing tower without sacrificing antennas on other bands.

Table 7 lists the gain and stacking specifications for the various length Yagis. The basic Yagi dimensions are shown in **Table 8**. These are free-space element lengths for $^{3}/_{16}$-inch-diameter elements. Boom corrections for the element mounting method must be added in. The element-length correction column gives the length that must be added to keep the Yagi's center frequency optimized for use at 432 MHz. This correction is required to use the same spacing pattern over a wide range of boom lengths. Although any length Yagi will work well, this design is at its best when made with 18 elements or more (4.6 λ). Element material of less than $^{3}/_{16}$-inch diameter is not recommended because resistive losses will reduce the gain by about 0.1 dB, and wet-weather performance will be worse.

Quarter-inch-diameter elements could be used if all elements are shortened by 3 mm. The element lengths are intended for use with a slight chamfer (0.5 mm) cut into the element ends. The gain peak of the array is centered at 437 MHz. This allows acceptable wet-weather performance, while reducing the gain at 432 MHz by only 0.05 dB.

The gain bandwidth of the 22-element Yagi is 31 MHz (at the –1 dB points). The SWR of the Yagi is less than l.4: l between 420 and 440 MHz. **Fig 41** is a network analyzer plot of the driven-element SWR vs frequency. These numbers indicate just how wide the frequency response of a log-taper Yagi can be, even with a simple dipole driven element. In fact, at one antenna gain contest, some ATV operators conducted gain vs frequency measurements from 420 to 440 MHz. The 22-element Yagi beat all entrants including those with so-called broadband feeds.

To peak the Yagi for use on 435 MHz (for satellite use), you may want to shorten all the elements by 2 mm. To peak it for use on 438 MHz (for ATV applications), shorten all elements by 4 mm. If you want to use the Yagi

Table 8

Free-Space Dimensions for 432-MHz Yagi Family

*Element correction is the amount to shorten or lengthen all elements when building a Yagi of that length.
Element lengths are for 3/16-inch diameter material.

Ele. No.	*Element Position (mm from reflector)*	*Element Length (mm)*	*Element Correction**
Refl	0	340	
DE	104	334	
D1	146	315	
D2	224	306	
D3	332	299	
D4	466	295	
D5	622	291	
D6	798	289	
D7	990	287	
D8	1196	285	
D9	1414	283	
D10	1642	281	–2
D11	1879	279	–2
D12	2122	278	–2
D13	2373	277	–2
D14	2629	276	–2
D15	2890	275	–1
D16	3154	274	–1
D17	3422	273	–1
D18	3693	272	0
D19	3967	271	0
D20	4242	270	0
D21	4520	269	0
D22	4798	269	0
D23	5079	268	0
D24	5360	268	+1
D25	5642	267	+1
D26	5925	267	+1
D27	6209	266	+1
D28	6494	266	+1
D29	6779	265	+2
D30	7064	265	+2
D31	7350	264	+2
D32	7636	264	+2
D33	7922	263	+2
D34	8209	263	+2
D35	8496	262	+2
D36	8783	262	+2
D37	9070	261	+3
D38	9359	261	+3

on FM between 440 MHz and 450 MHz, shorten all the elements by 10 mm. This will provide 17.6 dBi gain at 440 MHz, and 18.0 dBi gain at 450 MHz. The driven element may have to be adjusted if the element lengths are shortened.

Although this Yagi design is relatively broadband, it is suggested that close attention be paid to copying the design exactly as built. Metric dimensions are used because they are convenient for a Yagi sized for 432 MHz.



Fig 41—SWR performance of the 22-element Yagi in dry weather.



Fig 42—Element-mounting detail. Elements are mounted through the boom using plastic insulators. Stainless steel push-nut retaining rings hold the element in place.

Element holes should be drilled within ±2 mm. Element lengths should be kept within ±0.5 mm. Elements can be accurately constructed if they are first rough cut with a hack saw and then held in a vise and filed to the exact length.

The larger the array, the more attention you should pay to making all Yagis identical. Elements are mounted on shoulder insulators and run through the boom (see **Fig 42**). The element retainers are stainless-steel push nuts. These are made by several companies, including Industrial Retaining Ring Co in Irvington, New Jersey, and AuVeco in Ft Mitchell, Kentucky. Local industrial hardware distributors can usually order them for you. The element insulators



Fig 43—Several views of the driven element and T match.


340 mm
All Elements
3/16″ Diam 6061-T6
Clamp,
0.030″ Alum
3/8″ Wide
62 mm
62 mm
15 mm
38 mm
38 mm
Solder
Lug
T Wire: 122 mm
Length of
No. 12 Wire
1″
T Wire 140 mm Length of No. 12 Wire
Make STRAIGHT PORTION of
T Wire 122 mm Long; Form and
Solder to N-Connector
Note: T Wires are Parallel to Driven Element
Balun: Make from UT-141 Copper-Shielded Coax
5 mm
Dielectric
233 mm
Shield
5 mm
Dielectric
19 mm
Centerline of Driven Element to Rear
Face of N-Connector Bracket
Solder
Centerline of
N Connector
Above Boom
15 mm
Balun
Solder Lug Attached to Bottom Screw
on Connector, Bent 90° and Soldered
to UT-141 Shield
Side View

Fig 44—Details of the driven element and T match for the 22-element Yagi. Lengths are given in millimeters to allow precise duplication of the antenna. See text.


Front Boom Section
7/8″OD × 0.049″ Wall
6061–T6 Tubing
1530 mm (60–1/4″) Long
Center Boom Section
1″OD × 0.058″ Wall
6061–T6 Tubing
Double Up Boom Where Mast Clamp
Mounts. Use 12″ of 7/8″OD × 0.049
6061–T6
Rear Boom Section
7/8′OD × 0.049″ Wall
6061–T6 Tubing
1580 mm (62–5/8″)
Long
Center Mast Clamp
Between D10 and D11
NO. 8–32 Screw
(2 places)
Slot and Use Hose
Clamp (2 places)
412 mm
(55–9/16″)
1415 mm
(55–11/16″)
1475 mm
(58–1/16″)
4302 mm
(169–5/16″)
BOOM LAYOUT

Fig 45—Boom-construction information for the 22-element Yagi Lengths are given in millimeters to allow precise duplication of the antenna. See text.



Fig 46—Boom-construction information for the 33-element Yagi. Lengths are given in millimeters to allow precise duplication of the antenna.

are not critical. Teflon or black polyethylene are probably the best materials. The Yagi in the photographs is made with black Delryn insulators, available from C3i in Washington, DC.

The driven element uses a UG-58A/U connector mounted on a small bracket. The UG58A/U should be the type with the press-in center pin. UG-58s with center pins held in by "C" clips will usually leak water. Some connectors use steel retaining clips, which will rust and leave a conductive stripe across the insulator. The T-match wires are supported by the UT-141 balun. RG-303/U or RG-142/U Tefloninsulated cable could be used if UT-141 cannot be obtained. **Fig 43A** and Fig 42B show details of the driven-element construction. Driven element dimensions are given in **Fig 44**.

Dimensions for the 22-element Yagi are listed in **Table 9**. **Fig 45** details the Yagi's boom layout. Element material can be either 3/16 inch 6061-T6 aluminum rod or hard aluminum welding rod.

A 24-foot-long, 10.6-λ, 33-element Yagi was also built. The construction methods used were the same as the 22-element Yagi. Telescoping round boom sections of 1, 1 1/8, and 1 1/4 inches in diameter were used. A boom support is required to keep boom sag acceptable. At 432 MHz, if boom sag is much more than two or three inches, H-plane pattern distortion will occur. Greater amounts of boom sag will reduce the gain of a Yagi. **Table 10** lists the proper dimensions for the antenna when built with the previously given boom diameters. The boom layout is shown in **Fig 46**, and the driven element is described in **Fig 47**. The 33-element Yagi exhibits the same clean pattern traits as the 22-element Yagi (see **Fig 48**). Measured gain of the 33-element Yagi is 19.9 dBi at 432 MHz. A measured gain sweep of the 33-element Yagi gave a –1 dB gain bandwidth of 14 MHz with the –1 dB points at 424.5 MHz and 438.5 MHz.

A HIGH-PERFORMANCE 144MHZ YAGI

This 144MHz Yagi design uses the latest log-tapered element spacings and lengths. It offers near theoretical gain per boom length, an extremely clean pattern and wide bandwidth. The design is based upon the spacings used in a 4.5-λ 432-MHz computerdeveloped design by W1EJ. It is quite similar to the 432MHz Yagi described elsewhere in this chapter. Refer to that project for additional construction diagrams and photographs.

Mathematical models do not always directly translate into real working examples. Although the computer design provided a good starting point, the author, Steve Powlishen, K1FO, built several test models before the final working Yagi was obtained. This hands-on tuning included changing the element-taper rate in order to obtain the flexibility that allows the Yagi to be built with different boom lengths.

The design is suitable for use from 1.8 λ (10 elements) to 5.1 λ (19 elements). When elements are added to a Yagi, the center frequency, feed impedance and front-to-back ratio will range up and down. A modern tapered design will minimize this effect and allow the builder to select any desired boom length. This Yagi's design capabilities per boom length are listed in **Table 11**.

The gain of any Yagi built around this design will be within 0.1 to 0.2 dB of the maximum theoretical gain at the design frequency of 144.2 MHz. The design is intentionally peaked high in frequency (calculated gain peak is about 144.7 MHz). It has been found that by doing this, the SWR bandwidth and pattern at 144.0 to 144.3 MHz will be better, the Yagi will be less affected by weather and its performance in arrays will be more predictable. This design starts to drop off in performance if built with fewer than 10 elements. At less than 2 λ, more traditional designs perform well.

Table 12 gives free-space element lengths for 1/4 inch-diameter elements. The use of metric notation allows for much easier dimensional changes during the design stage. Once you become familiar with the metric system, you'll probably find that construction is easier without the burden of cumbersome English fractional units. For 3/16 inch-diameter elements, lengthen all parasitic elements by 3 mm. If 3/8 inch diameter elements are used, shorten all of the

Table 9

Dimensions for the 22-Element 432-MHz Yagi

Element Number	*Element Position (mm from reflector)*	*Element Length (mm)*	*Boom Diam (in)*
Refl	30	346	
DE	134	340	
D1	176	321	
D2	254	311	7/8
D3	362	305	
D4	496	301	
D5	652	297	
D6	828	295	
D7	1020	293	
D8	1226	291	
D9	1444	289	
D10	1672	288	
D11	1909	286	
D12	2152	285	1
D13	2403	284	
D14	2659	283	
D15	2920	281	
D16	3184	280	
D17	3452	279	7/8
D18	3723	278	
D19	3997	277	
D20	4272	276	

Table 10

Dimensions for the 33-Element 432-MHz Yagi

Element Number	*Element Position (mm from reflector)*	*Element Length (mm)*	*Boom Diam (in)*
REF	30	348	
DE	134	342	
D1	176	323	
D2	254	313	
D3	362	307	
D4	496	303	1
D5	652	299	
D6	828	297	
D7	1020	295	
D8	1226	293	
D9	1444	291	
D10	1672	290	
D11	1909	288	
D12	2152	287	$1^1/_8$
D13	2403	286	
D14	2659	285	
D15	2920	284	
D16	3184	284	
D17	3452	283	
D18	3723	282	1¼
D19	3997	281	
D20	4272	280	
D21	4550	278	
D22	4828	278	
D23	5109	277	$1^1/_8$
D24	5390	277	
D25	5672	276	
D26	5956	275	
D27	6239	274	
D28	6524	274	1
D29	6809	273	
D30	7094	273	
D31	7380	272	

directors and the reflector by 6 mm. The driven element will have to be adjusted for the individual Yagi if the 12-element design is not adhered to.

For the 12-element Yagi, $^1/_4$-inch diameter elements were selected because smaller-diameter elements become rather flimsy at 2 meters. Other diameter elements can be used as described previously. The 2.5-λ boom was chosen because it has an excellent size and wind load vs gain and pattern trade-off. The size is also convenient; three 6-foot-long pieces of aluminum tubing can be used without any waste. The relatively large-diameter boom sizes ($1^1/_4$ and $1^3/_8$ inches) were chosen, as they provide an extremely rugged Yagi that does not require a boom support. The 12-element 17-foot-long design has a calculated wind survival of close to 120 mph! The absence of a boom support also makes vertical polarization possible.

Longer versions could be made by telescoping smaller-size boom sections into the last section. Some sort of boom support will be required on versions longer than 22 feet. The elements are mounted on shoulder insulators and mounted through the boom. However, elements may


342 mm
9 mm
9 mm
76 mm
76 mm
14 mm
17 mm
40 mm
40 mm
T Wire: 122 mm
Length of
No. 12 Wire
1"
T Wire: 136 mm Length of No. 12 Wire
Make Straight Portion
122 mm Long; Additional Length
Approx 14 mm. Connects to
N-Connector Center Pin
Note: T WIres are not Parallel to Driven Element

Fig 47—Details of the driven element and T match for the 33-element Yagi. Lengths are given in millimeters to allow precise duplication of the antenna.

Table 11
Specifications for the 144-MHz Yagi Family

No. of Ele.	*Boom Length(λ)*	*Gain (dBd)*	*DE Imped (Ω)*	*FB Ratio (dB)*	*Beamwidth E/H (°)*	*Stacking E/H (°)*
10	1.8	11.4	27	17	39/42	10.2/9.5
11	2.2	12.0	38	19	36/40	11.0/10.0
12	2.5	12.5	28	23	34/37	11.7/10.8
13	2.9	13.0	23	20	32/35	12.5/11.4
14	3.2	13.4	27	18	31/33	12.8/12.0
15	3.6	13.8	35	20	30/32	13.2/12.4
16	4.0	14.2	32	24	29/30	13.7/13.2
17	4.4	14.5	25	23	28/29	14.1/13.6
18	4.8	14.8	25	21	27/28.5	14.6/13.9
19	5.2	15.0	30	22	26/27.5	15.2/14.4

Table 12
Free-Space Dimensions for the 144-MHz Yagi Family
Element diameter is ¼ inch

Element No.	*Element Position (mm from reflector)*	*Element Length*
Refl.	0	1038
DE	312	955
D1	447	956
D2	699	932
D3	1050	916
D4	1482	906
D5	1986	897
D6	2553	891
D7	3168	887
D8	3831	883
D9	4527	879
D10	5259	875
D11	6015	870
D12	6786	865
D13	7566	861
D14	8352	857
D15	9144	853
D16	9942	849
D17	10744	845

be mounted, insulated or uninsulated, above or through the boom, as long as appropriate element length corrections are made. Proper tuning can be verified by checking the depth of the nulls between the main lobe and first side lobes. The nulls should be 5 to 10 dB below the first sidelobe level at the primary operating frequency. The boom layout for the 12-element model is shown in **Fig 49**. The actual corrected element dimensions for the 12-element 2.5-λ Yagi are shown in **Table 13**.

The design may also be cut for use at 147 MHz. There is no need to change element spacings. The element lengths should be shortened by 17 mm for best operation between 146 and 148 MHz. Again, the driven element will have to be adjusted as required.

The driven-element size ($^1/_2$-inch diameter) was chosen to allow easy impedance matching. Any reasonably sized driven element could be used, as long as appropriate length and T-match adjustments are made. Different driven-element dimensions are required if you change the boom length. The calculated natural driven-element impedance is given as a guideline. A balanced T-match was chosen because it's easy to adjust for best SWR and provides a balanced radiation pattern. A 4:1 half-wave coaxial balun is used, although impedance-transforming quarter-wave sleeve baluns could also be used. The cal-



Fig 48—E-plane pattern for the 33-element Yagi. This pattern is drawn on a linear dB grid scale, rather than the standard ARRL log-periodic grid, to emphasize low sidelobes.


Rear Boom Section
1-1/4″ OD x 0.049″ wall
6061-T6 round tubing
1829 mm (72″) long
Center Boom Section
1-3/8″ OD x 0.058″ wall
6061-T6 round tubing
1829 mm (72″) long
Front Boom Section
1-1/4″ OD x 0.049″ wall
6061-T6 round tubing
1829 mm (72″) long
No. 8-32 Screw
(2 places)
Slot and use
hose clamp (2 places)
20
mm
Mast
Clamp
1735 mm
(68.3″)
1829 mm
(72″)
1735 mm
(68.3″)
BOOM LAYOUT

Fig 49—Boom layout for the 12-element 144-MHz Yagi. Lengths are given in millimeters to allow precise duplication.


955 mm
83 mm
9.5 mm
No. 8 Screw
Nut and
Lockwasher
Driven Element 0.5" Dia (12.5 mm) × 0.035"
Wall Aluminum Tube
Shorting Strap
Make from
0.032" Aluminum
Attach Balun Ends
to T Bars
T Bars Supported on
3/4" High Delryn Insulators
40 mm
12.5 mm
Flatten Ends of
'T' Tubes
50 mm
381 mm
386 mm
T Bars
3/8" × 0.035"
Aluminum
Tubing
Inches = mm × 0.0394
Driven Element Detail 12—Element 144 MHz Yagi
(A)
Driven Element Side View
Front of
Yagi
22 m
Balun
Balun Shield is Grounded
Material 0.062" Aluminum
Connector Bracket
Balun Center Conductors
Attach to T Bars
3/4" Long × 3/8" Dia
Delryn Insulator
Hole Pattern
for UG—58A/U
No. 19 Hole
(2 places)
32mm
21mm
42mm
64mm
22 mm
44mm
7mm
50mm
64mm
7mm
No. 21 Hole for T Bar
Insulators (2 places)
(B)
Solder Lugs
Balun
Shield
Shield 664 mm
750 mm
Material: RG—142/U or RG—303/U Teflon—Insulated Coaxial Cable
Ant18—50
(C)

Fig 50—Driven-element detail for the 12-element 144-MHz Yagi. Lengths are given in millimeters to allow precise duplication.

Table 13

Dimensions for the 12-Element 2.5-λ Yagi

Element Number	*Element Position (mm from reflector)*	*Element Length (mm)*	*Boom Diam (in)*
Refl.	0	1044	
DE	312	955	
D1	447	962	1 1/4
D2	699	938	
D3	1050	922	
D4	1482	912	
D5	1986	904	
D6	2553	898	1 3/8
D7	3168	894	
D8	3831	889	
D9	4527	885	1 1/4
D10	5259	882	



Fig 51—H- and E-plane pattern for the 12-element 144-MHz Yagi.

culated natural impedance will be useful in determining what impedance transformation will be required at the 200-Ω balanced feed point. Chapter 26, Coupling the Line to the Antenna, contains information on calculating folded-dipole and T-match driven-element parameters. A balanced feed is important for best operation on this antenna. Gamma matches can severely distort the pattern balance. Other useful driven-element arrangements are the Delta match and the folded dipole, if you're willing to sacrifice some flexibility. **Fig 50** details the driven-element dimensions.

A noninsulated driven element was chosen for mounting convenience. An insulated driven element may also be used. A grounded driven element may be less affected by static build-up. On the other hand, an insulated driven element allows the operator to easily check his feed lines for water or other contamination by the use of an ohmmeter from the shack.

Table 14

Free-Space Dimensions for the 222-MHz Yagi Family

Element diameter is $^3/_{16}$-inch.

Element No.	*Element Position (mm from reflector)*	*Element Length (mm)*
Refl.	0	676
DE	204	647
D1	292	623
D2	450	608
D3	668	594
D4	938	597
D5	1251	581
D6	1602	576
D7	1985	573
D8	2395	569
D9	2829	565
D10	3283	562
D11	3755	558
D12	4243	556
D13	4745	554
D14	5259	553
D15	5783	552
D16	6315	551
D17	6853	550
D18	7395	549
D19	7939	548
D20	8483	547

Fig 51 shows computer-predicted E- and H-plane radiation patterns for the 12-element Yagi. The patterns are plotted on a l-dB-per-division linear scale instead of the usual ARRL polar-plot graph. This expanded scale plot is used to show greater pattern detail. The pattern for the 12-element Yagi is so clean that a plot done in the standard ARRL format would be almost featureless, except for the main lobe and first sidelobes.

The excellent performance of the 12-element Yagi is demonstrated by the reception of Moon echoes from several of the larger 144MHz EME stations with only one 12-element Yagi. Four of the 12-element Yagis will make an excellent starter EME array, capable of working many EME QSOs while being relatively small in size. The advanced antenna builder can use the information in Table 11 to design a dream array of virtually any size.

A HIGH-PERFORMANCE 222-MHz YAGI

Modern tapered Yagi designs are easily applied to 222 MHz. This design uses a spacing progression that is in between the 12-element 144-MHz design, and the 22-element 432-MHz design presented elsewhere in this chapter. The result is a design with maximum gain per boom length, a clean, symmetrical radiation pattern, and wide bandwidth. Although it was designed for weak-signal work (tropospheric scatter and EME), the design is

Table 15
Specifications for the 222-MHz Yagi Family

No of Ele.	*Boom Length(λ)*	*Gain (dBd)*	*FB Ratio (dB)*	*DE Imped (Ω)*	*Beamwidth E/H (°)*	*Stacking E/H (feet)*
12	2.4	12.3	22	23	37/39	7.1/6.7
13	2.8	12.8	19	28	33/36	7.8/7.2
14	3.1	13.2	20	34	32/34	8.1/7.6
15	3.5	13.6	24	30	30/33	8.6/7.8
16	3.9	14.0	23	23	29/31	8.9/8.3
17	4.3	14.35	20	24	28/30.5	9.3/8.5
18	4.6	14.7	20	29	27/29	9.6/8.9
19	5.0	15.0	22	33	26/28	9.9/9.3
20	5.4	15.3	24	29	25/27	10.3/9.6
21	5.8	15.55	23	24	24.5/26.5	10.5/9.8
22	6.2	15.8	21	23	24/26	10.7/10.2

suited to all modes of 222-MHz operation, such as packet radio, FM repeater operation and control links.

The spacings were chosen as the best compromise for a 3.9-λ 16-element Yagi. The 3.9-λ design was chosen, like the 12-element 144-MHz design, because it fits perfectly on a boom made from three 6-foot-long aluminum tubing sections. The design is quite extensible, and models from 12 elements (2.4 λ) to 22 elements (6.2 λ) can be built from the dimensions given in **Table 14**. Note that free-space lengths are given. They must be corrected for the element-mounting method. Specifications for various boom lengths are shown in **Table 15**.

Construction

Large-diameter ($1^1/_4$- and $1^3/_8$-inch diameter) boom construction is used, eliminating the need for boom supports. The Yagi can also be used vertically polarized. Three-sixteenths-inch-diameter aluminum elements are used. The exact alloy is not critical; 6061-T6 was used, but hard aluminum welding rod is also suitable. Quarter-inch-diameter elements could also be used if all elements are shortened by 3 mm. Three-eighths-inch-diameter elements would require 10-mm shorter lengths. Elements smaller than $^3/_{16}$ inch-diameter are not recommended. The elements are insulated and run through the boom. Plastic shoulder washers and stainless steel retainers are used to hold the elements in place. The various pieces needed to build the Yagi may be obtained from C3i in Washington, DC. **Fig 52** details the boom layout for the 16-element Yagi. **Table 16** gives the dimensions for the 16-element Yagi as built. The driven element is fed with a T match and a 4:1 balun. See **Fig 53** for construction details. See the 432-MHz Yagi project elsewhere in this chapter for additional photographs and construction diagrams.

The Yagi has a relatively broad gain and SWR curve, as is typical of a tapered design, making it usable over a wide frequency range. The example dimensions are intended for use at 222.0 to 222.5 MHz. The 16-element Yagi is quite usable to more than 223 MHz. The best compromise for covering the entire band is to shorten all parasitic elements by 4 mm. The driven element will have to be adjusted in length for best match. The position of the T-wire shorting straps may also have to be moved.

The aluminum boom provides superior strength, is lightweight, and has a low wind-load cross section. Aluminum is doubly attractive, as it will long outlast wood and fiberglass. Using state-of-the-art designs, it is unlikely that significant performance increases will be achieved in the next few years. Therefore, it's in your best interest to build an antenna that will last many years. If suitable wood or fiberglass poles are readily available, they may be used without any performance degradation, at least when the wood is new and dry. Use the free-space element lengths given in Table 16 for insulated-boom construction.

The pattern of the 16-element Yagi is shown in **Fig 54**. Like the 144-MHz Yagi, a l-dB-per-division plot is used to detail the pattern accurately. This 16-element design makes a good building block for EME or tropo DX arrays. Old-style narrow-band Yagis often perform



Fig 52—Boom layout for the 16-element 222-MHz Yagi. Lengths are given in millimeters to allow precise duplication.

Table 16

Dimensions for 16-Element 3.9-λ 222-MHz Yagi

Element Number	*Element Position (mm from reflector)*	*Element Length (mm)*	*Boom Diam (in)*
Refl.	0	683	
DE	204	664	
D1	292	630	
D2	450	615	
D3	668	601	$1^1/_4$
D4	938	594	
D5	1251	588	
D6	1602	583	
D7	1985	580	
D8	2395	576	
D9	2829	572	$1^3/_8$
D10	3283	569	
D11	3755	565	
D12	4243	563	
D13	4745	561	$1^1/_4$
D14	5259	560	

unpredictably when used in arrays. The theoretical 3.0-dB stacking gain is rarely observed. The 16-element Yagi (and other versions of the design) reliably provides stacking gains of nearly 3 dB. (The spacing dimensions listed in Table 15 show just over 2.9 dB stacking gain.) This has been found to be the best compromise between gain, pattern integrity and array size. Any phasing line losses will subtract from the possible stacking gain. Mechanical misalignment will also degrade the performance of an array.



Fig 54—H- and E-plane patterns for the 16-element 222-MHz Yagi at A. The driven-element T-match dimensions were chosen for the best SWR compromise between wet and dry weather conditions. The SWR vs frequency curve shown at B demonstrates the broad frequency response of the Yagi design.


644 mm
10 mm
252 mm
10 mm
Retainer
Insulating Shoulder Washer
3/16" Diam
21 mm
21 mm
Balun
No. 10 Wire
Mounting Bracket
UG-58A/U
Solder Balun Center Conductor to 'T' Wires (2 Places)
87 mm
490 mm
9 mm
Balun, UT-141 or RG-303/U
Solder Lug (2 Places)
10 mm
5 mm
464 mm (Shield)
5 mm
Driven Element

Fig 53—Driven-element detail for the 16-element 222-MHz Yagi. Lengths are given in millimeters to allow precise duplication.

A 144 MHz 2-Element Quad

The basic 2-element quad array for 144 MHz is shown in **Fig 55**. The supporting frame is 1 × 1-inch wood, of any kind suitable for outdoor use. Elements are #8 aluminum wire. The driven element is 1 λ (83 inches) long, and the reflector five percent longer (87 inches). Dimensions are not critical, as the quad is relatively broad in frequency response.

The driven element is open at the bottom, its ends fastened to a plastic block. The block is mounted at the bottom of the forward vertical support. The top portion of the element runs through the support and is held firmly by a screw running into the wood and then bearing on the aluminum wire. Feed is by means of 50-Ω coax, connected to the driven-element loop.

The reflector is a closed loop, its top and bottom portions running through the rear vertical support. It is held in position with screws at the top and bottom. The loop can be closed by fitting a length of tubing over the element ends, or by hammering them flat and bolting them together as shown in the sketch.

The elements in this model are not adjustable, though this can easily be done by the use of stubs. It would then be desirable to make the loops slightly smaller to compensate for the wire in the adjusting stubs. The driven element stub would be trimmed for length and the point of connection for the coax would be adjustable for best match. The reflector stub can be adjusted for maximum gain or maximum F/B ratio, depending on the builder's requirements.

In the model shown only the spacing is adjusted, and this is not particularly critical. If the wooden supports are made as shown, the spacing between the elements can be adjusted for best match, as indicated by an SWR meter connected in the coaxial line. The spacing has little effect on the gain (from 0.15 to 0.25 λ), so the variation in impedance with spacing can be used for matching. This also permits use of either 50- or 75-Ω coax for the transmission line.



Fig 55—Mechanical details of a 2-element quad for 144 MHz. The driven element, L1, is one wavelength long; reflector L2 is 5% longer. With the transmission line connected as shown here, the resulting radiation is horizontally polarized. Sets of elements of this type can be stacked horizontally and vertically for high gain with broad frequency response. Recommended bay spacing is $^1/_2$ λ between adjacent element sides. The example shown may be fed directly with 50-Ω coax.

A Portable 144 MHz 4-Element Quad

Element spacing for quad antennas found in the literature ranges from 0.14 λ to 0.25 λ. Factors such as the number of elements in the array and the parameters to be optimized (F/B ratio, forward gain, bandwidth, etc), determine the optimum element spacing within this range. The 4-element quad antenna described here was designed for portable use, so a compromise between these factors was chosen. This antenna, pictured in **Fig 56**, was designed and built by Philip D'Agostino, W1KSC.

Based on several experimentally determined correction factors related to the frequency of operation and the wire size, optimum design dimensions were found to be as follows.

$$\text{Reflector length (ft)} = \frac{1046.8}{f_{\text{MHz}}} \qquad \text{(Eq 8)}$$

$$\text{Driven element (ft)} = \frac{985.5}{f_{\text{MHz}}} \qquad \text{(Eq 9)}$$

$$\text{Directors (ft)} = \frac{937.3}{f_{\text{MHz}}} \qquad \text{(Eq 10)}$$

Cutting the loops for 146 MHz provides satisfactory performance across the entire 144MHz band.



Fig 56—The 4-element 144-MHz portable quad, assembled and ready for operation. Sections of clothes closet poles joined with pine strips make up the mast. (*Photo by Adwin Rusczek, W1MPO)*

Materials

The quad was designed for quick and easy assembly and disassembly, as illustrated in **Fig 57**. Wood (clear trim pine) was chosen as the principal building material because of its light weight, low cost, and ready availability. Pine is used for the boom and element supporting arms. Round wood clothes closet poles comprise the mast material. Strips connecting the mast sections are made of heavier pine trim. Elements are made of no. 8 aluminum wire. Plexiglas is used to support the feed point. **Table 17** lists the hardware and other parts needed to duplicate the quad.

Construction

The elements of the quad are assembled first. The mounting holes in the boom should be drilled to accommodate $1\frac{1}{2}$ inch no. 8 hardware. Measure and mark the locations where the holes are to be drilled in the element spreaders, **Fig 58**. Drill the holes in the spreaders just



Fig 57—The complete portable quad, broken down for travel. Visible in the foreground is the driven element. The pine box in the background is a carrying case for equipment and accessories. A hole in the lid accepts the mast, so the box doubles as a base for a short mast during portable operation. *(W1MPO photo*)

Table 17
Parts List for the 144 MHz 4-element Quad

Boom: ¾ × ¾ ×48-in. pine
Driven element support (spreader):
  ½ × ¾ × 21¼ in. pine
Driven element feed point strut: ½ × ¾ × 7½ in. pine
Reflector support (spreader): ½ × ¾ × 22½ in. pine
Director supports (spreaders):
  ½ × ¾ × 20¼ in. pine, 2 req'd
Mast brackets: ¾ × 1½ × 12 in. heavy pine trim, 4 req'd
Boom to mast bracket: ½ × $1\frac{5}{8}$ × 5 in. pine
Element wire: Aluminum ground wire
  (Radio Shack no. 15-035)
Wire clamps: ¼in. electrician's copper or zinc plated steel clamps, 3 req'd
Boom hardware:
  6 no. 8-32 × 1½ in. stainless steel machine screws
  6 no. 8-32 stainless steel wing nuts
  12 no. 8 stainless steel washers
Mast hardware:
  8 hex bolts, ¼-20 × 3½ in.
  8 hex nuts, ¼-20
  16 flat washers
Mast material: $1\frac{5}{16}$ in. × 6 ft wood clothes closet poles, 3 req'd
Feed point support plate: 3½ × 2½ in. Plexiglas sheet
Wood preparation materials:
  Sandpaper, clear polyurethane, wax
Feed line: 52-W RG-8 or RG-58 cable
Feed line terminals: Solder lugs for no. 8 or larger hardware, 2 req'd
Miscellaneous hardware:
  4 small machine screws, nuts, washers; 2 flat-head wood screws

large enough to accept the #8 wire elements. It is important to drill all the holes straight so the elements line up when the antenna is assembled.

Construction of the wire elements is easiest if the directors are made first. A handy jig for bending the elements can be made from a piece of 2 × 3-inch wood cut to the side length of the directors. It is best to start with about 82 inches of wire for each director. The excess can be cut off when the elements are completed. (The total length of each director is 77 inches.) Two bends should initially be made so the directors can be slipped into the spreaders before the remaining corners are bent. See **Fig 59**. Electrician's copper-wire clamps can be used to join the wires after the final bends are made, and they facilitate adjustment of element length. The reflector is made the same way as the directors, but the total length is 86 inches.

The driven element, total length 81 inches, requires special attention, as the feed attachment point needs to be adequately supported. An extra hole is drilled in the driven element spreader to support the feed-point strut, as shown in **Fig 60**. A Plexiglas plate is used at the feed point to support the feed- point hardware and the feed line. The feed-point support strut should be epoxied to the spreader, and a wood screw used for extra mechanical strength.

For vertical polarization, locate the feed point in the center of one side of the driven element, as shown in Fig 60. Although this arrangement places the spreader supports at voltage maxima points on the four loop conductors, D'Agostino reports no adverse effects during operation. However, if the antenna is to be left exposed to the weather, the builder may wish to modify the design to provide support for the loops at current maxima points, such as shown in Fig 60. (The element of Fig 60 should be rotated 90° for horizontal polarization.)

Orient the driven element spreader so that it mounts properly on the boom when the antenna is assembled. Bend the driven element the same way as the reflector and directors, but do not leave any overlap at the feed point. The ends of the wires should be $^3/_4$ inch apart where they mount on the Plexiglas plate. Leave enough excess that small loops can be bent in the wire for attachment to the coaxial feed line with stainless steel hardware.

Drill the boom as shown in **Fig 61**. It is a good idea to use hardware with wing nuts to secure the element spreaders to the boom. After the boom is drilled, clean all the wood parts with denatured alcohol, sand them, and give them two coats of glossy polyurethane. After the polyurethane dries, wax all the wooden parts.

The boom to mast attachment is made next. Square the ends of a 6-foot section of clothes closet pole (a miter box is useful for this). Drill the center holes in both the boom



Fig 59—Illustration showing how the aluminum element wires are bent. The adjustment clamp and its location are also shown.



Fig 58—Dimensions for the pine element spreaders for the 144-MHz 4-element quad.


Wood Screw and Glue (Pre-Drill)
Boom Center Mounting Hole
Plexiglas
Machine Screws Washers, Nuts
1/2" Tinned Leads on Coax
52Ω Coax

Fig 60—Layout of the driven element of the 144-MHz quad. The leads of the coaxial cable should be stripped to ½ in. and solder lugs attached for easy connection and disconnection. See text regarding impedance at loop support points.



Fig 61—Detail of the boom showing hole center locations and boom to mast connection points.



Fig 62—Boom to mast plate for the 144-MHz quad. The screw hole in the center of the plate should be countersunk so the wood screw attaching it to the mast does not interfere with the fit of the boom.



Fig 63—Mast coupling connector details for the portable quad. The plates should be drilled two at a time to ensure the holes line up.



Fig 64—Typical SWR curve for the 144MHz portable quad. The large wire diameter and the quad design provide excellent bandwidth.

attachment piece and one end of the mast section (**Fig 62**). Make certain that the mast hole is smaller than the flat-head screw to be used to ensure a snug fit. Accurately drill the holes for attachment to the boom as shown in Fig 62.

Countersink the hole for the flat-head screw to provide a smooth surface for attachment to the boom. Apply epoxy cement to the surfaces and screw the boom attachment piece securely to the mast section. One 6 foot mast is used for attachment to the other mast sections.

Two additional 6-foot mast sections are prepared next. This brings the total mast height to 18 feet. It is important to square the ends of each pole so the mast stands straight when assembled. Mast-section connectors are made of pine as shown in **Fig 63**. Using $3^1/_2 \times {}^1/_4$-inch hex bolts, washers, and nuts, sections may be attached as needed, for a total height of 6, 12 or 18 feet. Drill the holes in two connectors at a time. This ensures good alignment of the holes. A drill press is ideal for this job, but with care a hand drill can be used if necessary.

Line up two mast sections end to end, being careful that they are perfectly straight. Use the predrilled connectors to maintain pole straightness, and drill through the poles, one at a time. If good alignment is maintained, a straight 18-foot mast section can be made. Label the connectors and poles immediately so they are always assembled in the same order.

When assembling the antenna, install all the elements on the boom before attaching the feed line. Connect the coax to the screw connections on the driven element support plate and run the cable along the strut to the boom. From there, the cable should be routed directly to the mast and down. Assemble the mast sections to the desired height. The antenna provides good performance, and has a reasonable SWR curve over the entire 144 MHz band (**Fig 64**).

Building Quagi Antennas

The Quagi antenna was designed by Wayne Overbeck, N6NB. He first published information on this antenna in 1977 (see Bibliography). There are a few tricks to Quagi building, but nothing very difficult or complicated is involved. In fact, Overbeck mass produced as many as 16 in one day. **Tables 18** and **19** give the dimensions for Quagis for various frequencies up to 446 MHz.

For the designs of Tables 18 and 19, the boom is *wood* or any other nonconductor (such as, fiberglass or Plexiglas). If a metal boom is used, a new design and new element lengths will be required. Many VHF antenna builders go wrong by failing to follow this rule: If the original uses a metal boom, use the same size and shape metal boom when you duplicate it. If it calls for a wood boom, use a nonconductor. Many amateurs dislike wood booms, but in a salt air environment they outlast aluminum (and surely cost less). Varnish the boom for added protection.

The 144-MHz version is usually built on a 14 foot, 1 × 3 inch boom, with the boom tapered to 1 inch at both ends. Clear pine is best because of its light weight, but construction grade Douglas fir works well. At 222 MHz the boom is under 10 feet long, and most builders use 1 × 2 or (preferably) $^{3}/_{4}$ × $1^{1}/_{4}$ inch pine molding stock. At 432 MHz, except for long-boom versions, the boom should be $^{1}/_{2}$ inch thick or less. Most builders use strips of $^{1}/_{2}$-inch exterior plywood for 432 MHz.

The quad elements are supported at the current maxima (the top and bottom, the latter beside the feed point) with Plexiglas or small strips of wood. See **Fig 65**. The quad elements are made of #12 copper wire, commonly used in house wiring. Some builders may elect to use #10 wire on 144 MHz and #14 on 432 MHz, although this changes the resonant frequency slightly. Solder a type N connector (an SO-239 is often used at 144 MHz) at the midpoint of the driven element bottom side, and close the reflector loop.

Table 19
432MHz, 15-Element, Long Boom Quagi Construction Data

Element Lengths, Inches	*Interelement Spacing, Inches*
R—28	R-DE7
DE—$26^{5}/_{8}$	DE-D1—$5^{1}/_{4}$
D1—$11^{3}/_{4}$	D1-D2—11
D21—$^{11}/_{16}$	D2-D3—$5^{7}/_{8}$
D3—$11^{5}/_{8}$	D3-D4—$8^{3}/_{4}$
D4—$11^{9}/_{16}$	D4-D5—$8^{3}/_{4}$
D5—$11^{1}/_{2}$	D5-D6—$8^{3}/_{4}$
D6—$11^{7}/_{16}$	D6-D7—12
D7—$11^{3}/_{8}$	D7-D8—12
D8—$11^{5}/_{16}$	D8-D9—$11^{1}/_{4}$
D9—$11^{5}/_{16}$	D9-D10—$11^{1}/_{2}$
D10—$11^{1}/_{4}$	D10-D11—$9^{3}/_{16}$
D11—$11^{3}/_{16}$	D11-D12—$12^{3}/_{8}$
D12—$11^{1}/_{8}$	D12-D13—1-$^{3}/_{4}$
D13—$11^{1}/_{16}$	

Boom: 1 × 2in. × 12-ft Douglas fir, tapered to $^{5}/_{8}$ in. at both ends.
Driven element: #12 TW copper wire loop in square configuration, fed at bottom center with type N connector and 52-Ω coax.
Reflector: #12 TW copper wire loop, closed at bottom.
Directors: $^{1}/_{8}$ in. rod passing through boom.

Table 18
Dimensions, Eight-Element Quagi

Element			*Frequency*		
Lengths	*144.5 MHz*	*147 MHz*	*222 MHz*	*432 MHz*	*446 MHz*
Reflector[1]	$86^{5}/_{8}$"	85"	$56^{3}/_{8}$"	28"	$27^{1}/_{8}$"
Driven[2]	82"	80"	53½"	$26^{5}/_{8}$"	$25^{7}/_{8}$"
Directors	$35^{15}/_{16}$" to 35" in $^{3}/_{16}$" steps	$35^{5}/_{16}$" to $34^{3}/_{8}$" in $^{3}/_{16}$" steps	$23^{3}/_{8}$" to 23¾" in $^{1}/_{8}$" steps	11¾" to $11^{7}/_{16}$" in $^{1}/_{16}$" steps	$11^{3}/_{8}$" to $11^{1}/_{16}$" in $^{1}/_{16}$" steps
Spacing					
R-DE	21"	20½"	$13^{5}/_{8}$"	7"	6.8"
DE-D1	15¾"	$15^{3}/_{8}$"	10¼"	5¼"	5.1"
D1-D2	33"	32½"	21½"	11"	10.7"
D2-D3	17½"	$17^{1}/_{8}$"	$11^{3}/_{8}$"	5.85"	5.68"
D3-D4	26.1"	$25^{5}/_{8}$"	17"	8.73"	8.46"
D4-D5	26.1"	$25^{5}/_{8}$"	17"	8.73"	8.46"
D5-D6	26.1"	$25^{5}/_{8}$"	17"	8.73"	8.46"
Stacking Distance Between Bays					
	11'	10' 10"	7' 1½"	3'7"	3' $5^{5}/_{8}$"

[1] All #12 TW (electrical) wire, closed loops.
[2] All #12 TW wire loops, fed at bottom.

The directors are mounted through the boom. They can be made of almost any metal rod or wire of about $^1/_8$-inch diameter. Welding rod or aluminum clothesline wire works well if straight. (The designer uses $^1/_8$-inch stainless-steel rod obtained from an aircraft surplus store.)

A TV type U bolt mounts the antenna on a mast. A single machine screw, washers and a nut are used to secure the spreaders to the boom so the antenna can be quickly "flattened" for travel. In permanent installations two screws are recommended.

Construction Reminders

Based on the experiences of Quagi builders, the following hints are offered. First, remember that at 432 MHz even a $^1/_8$-inch measurement error results in performance deterioration. Cut the loops and elements as carefully as possible. No precision tools are needed, but accuracy is necessary. Also make sure to get the elements in the right order. The longest director goes closest to the driven element.

Finally, remember that a balanced antenna is being fed with an unbalanced line. Every balun the designer tried introduced more trouble in terms of losses than the feed imbalance caused. Some builders have tightly coiled several turns of the feed line near the feed point to limit line radiation. In any case, the feed line should be kept at right angles to the antenna. Run it from the driven element directly to the supporting mast and then up or down perpendicularly for best results.



Fig 65—A close-up view of the feed method used on a 432-MHz Quagi. This arrangement produces a low SWR and gain in excess of 13 dBi with a 4-ft 10-in. boom! The same basic arrangement is used on lower frequencies, but wood may be substituted for the Plexiglas spreaders. The boom is ½-in. exterior plywood.

QUAGIS FOR 1296 MHz

The Quagi principle has recently been extended to the 1296-MHz band, where good performance is extremely difficult to obtain from homemade conventional Yagis. **Fig 66** shows the construction and **Table 20** gives the design information for antennas with 10, 15 and 25 elements.

At 1296 MHz, even slight variations in design or building materials can cause substantial changes in performance. The 1296 MHz antennas described here work every time—but only if the same materials are used and the antennas are built *exactly* as described. This is not to discourage experimentation, but if modifications to these 1296-MHz antenna designs are contemplated, consider building one antenna as described here, so a reference is available against which variations can be compared.

The Quagis (and the cubical quad) are built on $^1/_4$-inch thick Plexiglas booms. The driven element and reflector (and also the directors in the case of the cubical quad) are made of insulated #18 AWG solid copper bell wire, available at hardware and electrical supply stores. Other types and sizes of wire work equally well, but the dimensions vary with the wire diameter. Even removing the insulation usually necessitates changing the loop lengths.

Quad loops are approximately square (**Fig 67**), although the shape is relatively uncritical. The element lengths, however, *are* critical. At 1296 MHz, variations





Fig 66—A view of the 10-element version of the 1296-MHz Quagi. It is mounted on a 30-in. Plexiglas boom with a 3 × 3-in. square of Plexiglas to support the driven element and reflector. Note how the driven element is attached to a standard UG-290 BNC connector. The elements are held in place with silicone sealing compound.

of $^{1}/_{16}$ inch alter the performance measurably, and a $^{1}/_{8}$ inch departure can cost several decibels of gain. The loop lengths given are *gross* lengths. Cut the wire to these lengths and then solder the two ends together. There is a $^{1}/_{8}$-inch overlap where the two ends of the reflector (and director) loops are joined, as shown in Fig 67.

The driven element is the most important of all. The #18 wire loop is soldered to a standard UG-290 chassis-mount BNC connector as shown in the photographs. This exact type of connector must be used to ensure uniformity in construction. Any substitution may alter the driven element electrical length. One end of the 9$^{1}/_{4}$ inch driven loop is pushed as far as it can go into the center pin, and is soldered in that position. The loop is then shaped and threaded through small holes drilled in the Plexiglas support. Finally, the other end is fed into one of the four mounting holes on the BNC connector and soldered. In most cases, the best SWR is obtained if the end of the wire just passes through the hole so it is flush with the opposite side of the connector flange.

Table 20
Dimensions, 1296-MHz Quagi Antennas

Note: All lengths are gross lengths. See text and photos for construction technique and recommended overlap at loop junctions. All loops are made of #18 AWG solid-covered copper bell wire. The Yagi type directors are $^{1}/_{16}$-in. brass brazing rod. See text for a discussion of director taper.

Feed: Direct with 52-Ω coaxial cable to UG-290 connector at driven element; run coax symmetrically to mast at rear of antenna.

Boom: 1$^{1}/_{4}$-in. thick Plexiglas, 30 in. long for 10-element quad or Quagi and 48 in. long for 15-element Quagi; 84 in. for 25-element Quagi.

10-Element Quagi for 1296 MHz

Element	*Length, Inches*	*Construction*	*Element*	*Interelement Spacing, In.*
Reflector	9.5625	Loop	R-DE	2.375
Driven	9.25	Loop	DE-D1	2.0
Director 1	3.91	Brass rod	D1-D2	3.67
Director 2	3.88	Brass rod	D2-D3	1.96
Director 3	3.86	Brass rod	D3-D4	2.92
Director 4	3.83	Brass rod	D4-D5	2.92
Director 5	3.80	Brass rod	D5-D6	2.92
Director 6	3.78	Brass rod	D6-D7	4.75
Director 7	3.75	Brass rod	D7-D8	3.94
Director 8	3.72	Brass rod		

15-Element Quagi for 1296 MHz

The first 10 elements are the same lengths as above, but the spacing from D6 to D7 is 4.0 in.; 07 to D8 is also 4.0 in.

Director 9	3.70	D8-D9	3.75
Director 10	3.67	D9-D10	3.83
Director 11	3.64	D10-D11	3.06
Director 12	3.62	D11-D12	4.125
Director 13	3.59	D12-D13	4.58

25-Element Quagi for 1296 MHz

The first 15 elements use the same element lengths and spacings as the 15-element model. The additional directors are evenly spaced at 3.0-in. intervals and taper in length successively by 0.02 in. per element. Thus, D23 is 3.39 in.



Fig 67—These photos show the construction method used for the 1296-MHz quad type parasitic elements. The two ends of the #18 bell wire are brought together with an overlap of $^{1}/_{8}$ in. and soldered.

Loop Yagis for 1296 MHz

Described here are loop Yagis for the 1296-MHz band. The loop Yagi fits into the quad family of antennas, as each element is a closed loop with a length of approximately 1 λ. Several versions are described, so the builder can choose the boom length and frequency coverage desired for the task at hand. Mike Walters, G3JVL, brought the original loop-Yagi design to the amateur community in the 1970s. Since then, many versions have been developed with different loop and boom dimensions. Chip Angle, N6CA, developed the antennas shown here.

Three sets of dimensions are given. Good performance can be expected if the dimensions are carefully followed. Check all dimensions before cutting or drilling anything. The 1296-MHz version is intended for weak-signal operation, while the 1270-MHz version is optimized for FM and mode L satellite work. The 1283-MHz antenna provides acceptable performance from 1280 to 1300 MHz.

These antennas have been built on 6- and 12-foot booms. Results of gain tests at VHF conferences and by individuals around the country show the gain of the 6-foot model to be about 18 dBi, while the 12-foot version provides about 20.5 dBi. Swept measurements indicate that gain is about 2 dB down from maximum gain at ±30 MHz from the design frequency. The SWR, however, deteriorates within a few megahertz on the low side of the design center frequency.

The Boom

The dimensions given here apply only to a ¾-inch OD boom. If a different boom size is used, the dimensions must be scaled accordingly. Many hardware stores


3/4" Boom
2-3/4"
1-1/8"
1-1/8"
5/32"
Boom Center Line
3"
U-Bolt
Mast
(A)
Loops
#6-32 Screws (3 pcs)
Nuts and Lockwashers
Boom End View
1/8" Aluminum Plate
U-Bolt
Cut Off Excess U-Bolt Threads
(B)
Boom
1/2" X 1/2" Aluminum Plate
U-Bolt Plate
(C)
1/4-20 Tap
Lock Washer
1/4-20 Bolt
5/8"Dia Aluminum Rod
5/8" Dia Hole
1/4" Dia Hole
1"X 1" Aluminum Square Tubing
(D)
Mast
Square Tubing
No.1 Reflector
4-1/2"
Boom (3/4"OD, 5/8"ID)
Screws
U-Bolt
Nut
Aluminum Plate
(E)

Fig 68—Loop Yagi boom-to-mast plate details are given at A. At B, the mounting of the antenna to the mast is detailed. A boom support for long antennas is shown at C. The arrangement shown in D and E may be used to rear-mount antennas up to 6 or 7 ft long.


R1
R2
DE
D1
D2
D3
D4
D5
D6
D7
D8
Spacing remains constant for all elements from D6 up

Freq.	Element Spacing (inches)									
1296	3.050	1.180	1.120	0.830	1.780	1.780	1.780	1.780	3.560	3.560
1283	3.090	1.193	1.135	0.841	1.804	1.804	1.804	1.804	3.607	3.607
1270	3.122	1.202	1.146	0.850	1.822	1.822	1.822	1.822	3.644	3.644

Fig 69—Boom drilling dimensions. These dimensions must be carefully followed and the same materials used if performance is to be optimum. Element spacings are the same for all directors after D6—use as many as necessary to fill the boom.


Refl 1 and 2
Aluminum
1/2 De
1/2 De
0.144"Dia Coper
0.144"Dia Coper
0.039"Dia
Dir 1-11
0.063"
Aluminum
Dir 12-17
Aluminum
0.125"Dia
All Alum Elements
Dir 18+
Aluminum
1/8" All Alum
Elements
These Dimensions Apply Only to:
0.250" Element Width
0.0325" Element Thickness
0.750" Diaeter Boom
NOTE: All Dimensions are in Inches

Freq	1270	1283	1296
Refl 1,2	9.929	9.829	9.700
1/2 De	4.752	4.704	4.643
Dir 1-11	8.445	8.359	8.250
Dir 12-17	8.189	8.106	8.000
Dir 18+	7.882	7.802	7.700

Element Lengths (Inches)
(Hole to Hole)

Fig 70—Parasitic elements for the loop Yagi are made from aluminum sheet, the driven element from copper sheet. The dimensions given are for ¼-in. wide by 0.0325-in. thick elements only. Lengths specified are hole to hole distances; the holes are located 1/8 in. from each element end.

carry aluminum tubing in 6- and 8-foot lengths, and that tubing is suitable for a short Yagi. If a 12-foot antenna is planned, find a piece of more rugged boom material, such as 6061-T6 grade aluminum. Do not use anodized tubing. The 12foot antenna must have additional boom support to minimize boom sag. The 6 foot version can be rear mounted. For rear mounting, allow 4½ inches of boom behind the last reflector to eliminate SWR effects from the support.

The antenna is attached to the mast with a gusset plate. This plate mounts at the boom center. See **Fig 68**. Drill the plate mounting holes perpendicular to the element mounting holes (assuming the antenna polarization is to be horizontal).

Elements are mounted to the boom with no. 4-40 machine screws, so a series of no. 33 (0.113inch) holes must be drilled along the center of the boom to accommodate this hardware. **Fig 69** shows the element spacings for different parts of the band. Dimensions should be followed as closely as possible.


No. 4-40 X 1"
Machine Screw
Clean Joints
Before Assembly
3/4"OD Boom
1/16" Wall Thk
Lockwasher and Nut

Fig 71—Element-to-boom mounting details.

Parasitic Elements

The reflectors and directors are cut from 0.032-inch thick aluminum sheet and are ¼ inch wide. **Fig 70** indicates the lengths for the various elements. These lengths apply only to elements cut from the specified material. For best results, the element strips should be cut with a shear. If the edges are left sharp, birds won't sit on the elements.

Drill the mounting holes as shown in Fig 70 after carefully marking their locations. After the holes are drilled, form each strap into a circle. This is easily done by wrapping the element around a round form. (A small juice can works well.)

Mount the loops to the boom with no. 4-40 × 1-inch machine screws, lock washers and nuts. See **Fig 71**. It is best to use only stainless steel or plated-brass hardware. Although the initial cost is higher than for ordinary plated-steel hardware, stainless or brass hardware will not rust and need replacement after a few years. Unless the antenna is painted, the hardware will definitely deteriorate.

Driven Element

The driven element is cut from 0.032-inch copper sheet and is ¼ inch wide. Drill three holes in the strap as detailed in Fig 69. Trim the ends as shown and form the strap into a loop similar to the other elements. This antenna is like a quad; if the loop is fed at the top or bottom, it is horizontally polarized.

Driven element mounting details are shown in **Fig 72**. A mounting fixture is made from a ¼-20 × 1¼ inch brass bolt. File the bolt head to a thickness of ⅛ inch. Bore a 0.144-inch (no. 27 drill) hole lengthwise through the center of the bolt. A piece of 0.141 inch semi-rigid Hardline (UT-141 or equivalent) mounts through this hole and is soldered to the driven loop feed point. The point at which the UT-141 passes through the copper loop and brass mounting fixture should be left unsoldered at this time to allow for matching adjustments when the antenna is completed, although the range of adjustment is not very large.

The UT-141 can be any convenient length. Attach the connector of your choice (preferably type N). Use a short piece of low-loss RG-8 size cable (or ½-inch Hardline) for the run down the boom and mast to the main feed line. For best results, the main feed line should be the lowest loss 50-Ω cable obtainable. Good ⅞-inch Hardline has 1.5 dB of loss per 100 feet and virtually eliminates the need for remote mounting of the transmit converter or amplifier.

Tuning the Driven Element

If the antenna is built carefully to the dimensions given, the SWR should be close to 1:1. Just to be sure, check the SWR if you have access to test equipment. Be sure the signal source is clean, however; wattmeters respond to “dirty” signals and can give erroneous readings. If problems are encountered, recheck all dimensions. If they look good, a minor improvement may be realized by changing the shape of the driven element. Slight bending of reflector 2 may also improve the SWR. When the desired match has been obtained, solder the point where the UT-141 jacket passes through the loop and brass bolt.

Tips for 1296-MHz Antenna Installations

Construction practices that are common on lower frequencies cannot be used on 1296 MHz. This is the most important reason why all who venture to these frequencies are not equally successful. First, when a proven design is used, copy it exactly¾don’t change *anything*. This is especially true for antennas.



Fig 72—Driven-element details. See Fig 70 and the text for additional information.

Use the best feed line you can get. Here are some realistic measurements of common coaxial cables at 1296 MHz (loss per 100 feet).

RG-8, 213, 214: 11 dB
½ in. foam/copper Hardline: 4 dB
⅞ in. foam/copper Hardline: 1.5 dB

Mount the antennas to keep feed line losses to an absolute minimum. Antenna height is less important than keeping the line losses low. *Do not* allow the mast to pass through the elements, as is common on antennas for lower frequencies. Cut all U-bolts to the minimum length needed; ¼ λ at 1296 MHz is only a little over 2 inches. Avoid any unnecessary metal around the antenna.

Trough Reflectors for 432 and 1296 MHz

Dimensions are given in **Fig 73** for 432- and 1296-MHz trough reflectors. The gain to be expected is 16 dBi and 15 dBi, respectively. A very convenient arrangement, especially for portable work, is to use a metal hinge at each angle of the reflector. This permits the reflector to be folded flat for transit. It also permits experiments to be carried out with different apex angles.

A housing is required at the dipole center to prevent the entry of moisture and, in the case of the 432-MHz antenna, to support the dipole elements. The dipole may be moved in and out of the reflector to get either minimum SWR or, if this cannot be measured, maximum gain. If a two-stub tuner or other matching device is used, the dipole may be placed to give optimum gain and the matching device adjusted to give optimum match. In the case of the 1296-MHz antenna, the dipole length can be adjusted by means of the brass screws at the ends of the elements. Locking nuts are essential.

The reflector should be made of sheet aluminum for 1296 MHz, but can be constructed of wire mesh (with twists parallel to the dipole) for 432 MHz. To increase the gain by 3 dB, a pair of these arrays can be stacked so the reflectors are barely separated (to prevent the formation of a slot radiator by the edges). The radiating dipoles must then be fed in phase, and suitable feeding and matching must be arranged. A two-stub tuner can be used for matching either a single- or double-reflector system.


Rod Dia
Ant0721
Tube 1
Tube 2
t
Brass Bushing
Center 1/8"Dia Brass Rod
v
Coax Connector
Bras Discs Solder to Coaxial Line
Teflon Spacers
Locking Screw
Adjustable Location
Dipole and Balun Assembly
4 – 40 Brass Screw at Each End to Adjust Length of Dipole
1/8" Dia Brass Rod
1 – 7/8"
Teflon
2 – 1/8"
Hinge
Dipole Detail 1296 MHz Only
q
r
A
Reflector Width w
p

Dimensions in Inches

Band	A	p	q	r	w	t	u	v	Tube 1 Brass or Copper	Tube 2 Brass or Copper	Gain
432	120	100	50	7 – 1/2	60	6 – 1/2	1/4	12 – 3/4	1 – 1/2" ID 1/16" Wall	5/8" OD 1/16" Wall	16 dBi
1296	45	36	9 – 1/2	2 – 1/2	20	2 – 1/8	1/8	4 – 1/4	3/4" ID	3/8" OD 20 s.w.g.	15 dBi

Fig 73—Practical construction information for trough reflector antennas for 432 and 1296 MHz.

A Horn Antenna for 10 GHz

The horn antenna is the easiest antenna for the beginner on 10 GHz to construct. It can be made out of readily available flat sheet brass. Because it is inherently a broadband structure, minor constructional errors can be tolerated. The one drawback is that horn antennas become physically cumbersome at gains over about 25 dBi, but for most line-of-sight work this much gain is rarely necessary. This antenna was designed by Bob Atkins, KA1GT, and appeared in *QST* for April and May, 1987.

Horn antennas are usually fed by waveguide. When operating in its normal frequency range, waveguide propagation is in the TE_{10} mode. This means that the electric (E) field is across the short dimension of the guide and the magnetic (H) field is across the wide dimension. This is the reason for the E-plane and H-plane terminology shown in **Fig 74**.

There are many varieties of horn antennas. If the waveguide is flared out only in the H-plane, the horn is called an H-plane sectoral horn. Similarly, if the flare is only in the E-plane, an Eplane sectoral horn results. If the flare is in both planes, the antenna is called a pyramidal horn.

For a horn of any given aperture, directivity (gain along the axis) is maximum when the field distribution across the aperture is uniform in magnitude and phase. When the fields are not uniform, side lobes that reduce the directivity of the antenna are formed. To obtain a uniform distribution, the horn should be as long as possible with minimum flare angle. From a practical point of view, however, the horn should be as short as possible, so there is an obvious conflict between performance and convenience.

Fig 75 illustrates this problem. For a given flare angle and a given side length, there is a path-length difference from the apex of the horn to the center of the aperture (L), and from the apex of the horn to the edge of the aperture (L'). This causes a phase difference in the field across the aperture, which in turn causes formation of side lobes, degrading directivity (gain along the axis) of the antenna. If L is large this difference is small, and the field is almost uniform. As L decreases however, the phase difference increases and directivity suffers. An optimum (shortest possible) horn is constructed so that this phase difference is the maximum allowable before side lobes become excessive and axial gain markedly decreases.

The magnitude of this permissible phase difference is different for E-plane and H-plane horns. For the E-plane horn, the field intensity is quite constant across the aperture. For the H-plane horn, the field tapers to zero at the edge. Consequently, the phase difference at the edge of the aperture in the E-plane horn is more critical and should be held to less than 90° ($^1/_4$ λ). In an H-plane horn, the allowable phase difference is 144° (0.4 λ). If the aperture of a pyramidal horn exceeds one wavelength in both planes, the Eplane and Hplane patterns are essentially independent and can be analyzed separately.

The usual direction for orienting the waveguide feed is with the broad face horizontal, giving vertical polarization. If this is the case, the H-plane sectoral horn has a narrow horizontal beamwidth and a very wide vertical beamwidth. This is not a very useful beam pattern for most amateur applications. The E-plane sectoral horn has a narrow vertical beamwidth and a wide horizontal beamwidth. Such a radiation pattern could be useful in a beacon system where wide coverage is desired.

The most useful form of the horn for general applications is the optimum pyramidal horn. In this configuration the two beamwidths are almost the same. The E-plane (vertical) beamwidth is slightly less than the H-plane (horizontal), and also has greater side lobe intensity.



Fig 74—10-GHz antennas are usually fed with waveguide. See text for a discussion of waveguide propagation characteristics.



Fig 75—The path-length (phase) difference between the center and edge of a horn antenna is δ.

Building the Antenna

A 10-GHz pyramidal horn with 18.5 dBi gain is shown in **Fig 76**. The first design parameter is usually the required gain, or the maximum antenna size. These are of course related, and the relationships can be approximated by the following:

L = H-plane length (λ) = $0.0654 \times$ gain (Eq 1)
A = H-plane aperture (λ) = $0.0443 \times$ gain (Eq 2)
B = E-plane aperture (λ) = $0.81\ A$ (Eq 3)

where

gain is expressed as a *ratio*; 20 dBi gain = 100
L, A and B are dimensions shown in **Fig 77.**

From these equations, the dimensions for a 20-dBi gain horn for 10.368 GHz can be determined. One wavelength at 10.368 GHz is 1.138 inches. The length (L) of such a horn is $0.0654 \times 100 = 6.54\ \lambda$. At 10.368 GHz, this is 7.44 inches. The corresponding H-plane aperture (A) is 4.43 λ (5.04 inches), and the E-plane aperture (B), 4.08 inches.

The easiest way to make such a horn is to cut pieces from brass sheet stock and solder them together. Fig 77 shows the dimensions of the triangular pieces for the sides and a square piece for the waveguide flange. (A standard commercial waveguide flange could also be used.) Because the E-plane and H-plane apertures are different, the horn opening is not square. Sheet thickness is unimportant; 0.02 to 0.03 inch works well. Brass sheet is often available from hardware or hobby shops.

Note that the triangular pieces are trimmed at the apex to fit the waveguide aperture (0.9×0.4 inch). This necessitates that the length, from base to apex, of the smaller triangle (side B) is shorter than that of the larger (side A). Note that the length, S, of the two different sides of the horn must be the same if the horn is to fit together! For such a simple looking object, getting the parts to fit together properly requires careful fabrication.

The dimensions of the sides can be calculated with simple geometry, but it is easier to draw out templates on a sheet of cardboard first. The templates can be used to build a mock antenna to make sure everything fits together properly before cutting the sheet brass.

First, mark out the larger triangle (side A) on cardboard. Determine at what point its width is 0.9 inch and draw a line parallel to the base as shown in Fig 77. Measure the length of the side S; this is also the length of the sides of the smaller (side B) pieces.

Mark out the shape of the smaller pieces by first drawing a line of length B and then constructing a second line of length S. One end of line S is an end of line B, and the other is 0.2 inch above a line perpendicular to the center of line B as shown in Fig 76. (This procedure is much more easily followed than described.) These smaller pieces are made slightly oversize (shaded area in Fig 77) so you can construct the horn with solder seams on the outside of the horn during assembly.



Fig 76—This pyramidal horn has 18.5 dBi gain at 10 GHz. Construction details are given in the text.



Fig 77—Dimensions of the brass pieces used to make the 10-GHz horn antenna. Construction requires two of each of the triangular pieces (side A and side B).

Cut out two cardboard pieces for side A and two for side B and tape them together in the shape of the horn. The aperture at the waveguide end should measure 0.9 × 0.4 inch and the aperture at the other end should measure 5.04 × 4.08 inches.

If these dimensions are correct, use the cardboard templates to mark out pieces of brass sheet. The brass sheet should be cut with a bench shear if one is available, because scissors type shears tend to bend the metal. Jig the pieces together and solder them on the *outside* of the seams. It is important to keep both solder and rosin from contaminating the inside of the horn; they can absorb RF and reduce gain at these frequencies.

Assembly is shown in **Fig 78**. When the horn is completed, it can be soldered to a standard waveguide flange, or one cut out of sheet metal as shown in Fig 77. The transition between the flange and the horn must be smooth. This antenna provides an excellent performance-to-cost ratio (about 20 dBi gain for about five dollars in parts).


View Looking into Horn
Side A
Side B
Side B
Side A
Solder Seams on Outside of Horn
Waveguide Feed
Solder Horn to Waveguide Flange

Fig 78—Assembly of the 10-GHz horn antenna.

Periscope Antenna Systems

One problem common to all who use microwaves is that of mounting an antenna at the maximum possible height while trying to minimize feed-line losses. The higher the frequency, the more severe this problem becomes, as feeder losses increase with frequency. Because parabolic dish reflectors are most often used on the higher bands, there is also the difficulty of waterproofing feeds (particularly waveguide feeds). Inaccessibility of the dish is also a problem when changing bands. Unless the tower is climbed every time and the feed changed, there must be a feed for each band mounted on the dish. One way around these problems is to use a periscope antenna system (sometimes called a “flyswatter antenna”).

The material in this section was prepared by Bob Atkins, KA1GT, and appeared in *QST* for January and February 1984. **Fig 79** shows a schematic representation of a periscope antenna system. A plane reflector is mounted at the top of a rotating tower at an angle of 45°. This reflector can be elliptical with a major to minor axis ratio of 1.41, or rectangular. At the base of the tower is mounted a dish or other type of antenna such as a Yagi, pointing straight up. The advantage of such a system is that the feed antenna can be changed and worked on easily. Additionally, with a correct choice of reflector size, dish size, and dish to reflector spacing, feed losses can be made small, increasing the effective system gain. In fact, for some particular system configurations, the gain of the overall system can be greater than that of the feed antenna alone.

Gain of a Periscope System

Fig 80 shows the relationship between the effective gain of the antenna system and the distance between the reflector and feed antenna for an elliptical reflector. At first sight, it is not at all obvious how the antenna system can have a higher gain than the feed alone. The reason lies in the fact that, depending on the feed to reflector spacing, the reflector may be in the near field (Fresnel) region of the antenna, the far field (Fraunhöffer) region, or the transition region between the two.

In the far field region, the gain is proportional to the reflector area and inversely proportional to the distance between the feed and reflector. In the near field region, seemingly strange things can happen, such as decreasing gain with decreasing feed to reflector separation. The reason for this gain decrease is that, although the reflec-



Fig 79—The basic periscope antenna. This design makes it easy to adjust the feed antenna.

tor is intercepting more of the energy radiated by the feed, it does not all contribute in phase at a distant point, and so the gain decreases.

In practice, rectangular reflectors are more common than elliptical. A rectangular reflector with sides equal in length to the major and minor axes of the ellipse will, in fact, normally give a slight gain increase. In the far field region, the gain will be proportional to the area of the reflector. To use Fig 80 with a rectangular reflector, R^2 may be replaced by A / π, where A is the projected area of the reflector. The antenna pattern depends in a complicated way on the system parameters (spacing and size of the elements), but **Table 21** gives an approximation of what to expect. R is the radius of the projected circular area of the elliptical reflector (equal to the minor axis radius), and b is the length of the side of the projected square area of the rectangular reflector (equal to the length of the short side of the rectangle).

For those wishing a rigorous mathematical analysis of this type of antenna system, several references are given in the Bibliography at the end of this chapter.

Mechanical Considerations

There are some problems with the physical construction of a periscope antenna system. Since the antenna gain of a microwave system is high and, hence, its beamwidth narrow, the reflector must be accurately aligned. If the reflector does not produce a beam that is horizontal, the



Fig 80—Gain of a periscope antenna using a plane elliptical reflector (after Jasik—see Bibliography).

Table 21
Radiation Patterns of Periscope Antenna Systems

	Elliptical Reflector	*Rectangular Reflector*
3-dB beamwidth, degrees	60 λ/2R	52 λ/b
6-dB beamwidth, degrees	82 λ/2R	68 λ/b
First minimum, degrees from axis	73 λ/2R	58 λ/b
First maximum, degrees from axis	95 λ/2R	84 λ/b
Second minimum, degrees from axis	130 λ/2R	116 λ/b
Second maximum, degrees from axis	156 λ/2R	142 λ/b
Third minimum, degrees from axis	185 λ/2R	174 λ/b



Fig 81—Commercial periscope antennas, such as this one, are often used for point-to-point communication.

useful gain of the system will be reduced. From the geometry of the system, an angular misalignment of the reflector of X degrees in the vertical plane will result in an angular misalignment of 2X degrees in the vertical alignment of the antenna system pattern. Thus, for a dish pointing straight up (the usual case), the reflector must be at an angle of 45° to the vertical and should not fluctuate from factors such as wind loading.

The reflector itself should be flat to better than $^{1}/_{10}$ λ for the frequency in use. It may be made of mesh, provided that the holes in the mesh are also less than $^{1}/_{10}$ λ in diameter. A second problem is getting the support mast to rotate about a truly vertical axis. If the mast is not vertical, the resulting beam will swing up and down from the horizontal as the system is rotated, and the effective gain at the horizon will fluctuate. Despite these problems, amateurs have used periscope antennas successfully on the bands through 10 GHz. Periscope antennas are used frequently in commercial service, though usually for point-to-point transmission. Such a commercial system is shown in **Fig 81**.

Circular polarization is not often used for terrestrial work, but if it is used with a periscope system there is an important point to remember. The circularity sense changes when the signal is reflected. Thus, for right hand circularity with a periscope antenna system, the feed arrangement on the ground should produce left hand circularity. It should also be mentioned that it is possible (though more difficult for amateurs) to construct a periscope antenna system using a parabolically curved reflector. The antenna system can then be regarded as an offset fed parabola. More gain is available from such a system at the added complexity of constructing a parabolically curved reflector, accurate to $^{1}/_{10}$ λ.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2, Antenna Fundamentals.

B. Atkins, "Periscope Antenna Systems," The New Frontier, *QST*, Jan and Feb 1984.

B. Atkins, "Horn Antennas for 10 GHz," The New Frontier, *QST*, Apr and May 1987.

J. Drexler, "An Experimental Study of a Microwave Periscope," *Proc. IRE*, Correspondence, Vol 42, Jun 1954, p 1022.

D. Evans and G. Jessop, *VHF-UHF Manual*, 3rd ed. (London: RSGB), 1976.

N. Foot, "WA9HUV 12foot Dish for 432 and 1296 MHz," The World Above 50 Mc., *QST*, Jun 1971, pp 98-101, 107.

N. Foot, "Cylindrical Feed Horn for Parabolic Reflectors," *Ham Radio*, May 1976.

G. Gobau, "Single-Conductor Surface-Wave Transmission Lines," *Proc. IRE*, Vol 39, Jun 1951, pp 619-624; also see *Journal of Applied Physics*, Vol 21 (1950), pp 1119-1128.

R. E. Greenquist and A. J. Orlando, "An Analysis of Passive Reflector Antenna Systems," *Proc. IRE*, Vol 42, Jul 1954, pp 1173-1178.

G. A. Hatherell, "Putting the G Line to Work," *QST*, Jun 1974, pp 11-15, 152, 154, 156.

D. L. Hilliard, "A 902MHz Loop Yagi Antenna," *QST*, Nov 1985, pp 30-32.

W. C. Jakes, Jr., "A Theoretical Study of an Antenna-Reflector Problem," *Proc. IRE*, Vol 41, Feb 1953, pp 272-274.

H. Jasik, *Antenna Engineering Handbook*, 1st ed. (New York: McGraw-Hill, 1961).

R. T. Knadle, "UHF Antenna Ratiometry," *QST*, Feb 1976, pp 22-25.

T. Moreno, *Microwave Transmission Design Data* (New York: McGraw- Hill, 1948).

W. Overbeck, "The VHF Quagi," *QST*, Apr 1977, pp 11-14.

W. Overbeck, "The Long-Boom Quagi," *QST*, Feb 1978, pp 20-21.

W. Overbeck, "Reproducible Quagi Antennas for 1296 MHz," *QST*, Aug 1981, pp 11-15.

G. Southworth, *Principles and Applications of Waveguide Transmission* (New York: D. Van Nostrand Co, 1950).

P. P. Viezbicke, "Yagi Antenna Design," *NBS Technical Note 688* (U. S. Dept. of Commerce/National Bureau of Standards, Boulder, CO), Dec 1976.

D. Vilardi, "Easily Constructed Antennas for 1296 MHz," *QST*, Jun 1969.

D. Vilardi, "Simple and Efficient Feed for Parabolic Antennas," *QST*, Mar 1973.

Radio Communication Handbook, 5th ed. (London: RSGB, 1976).

Chapter 19

Antenna Systems for Space Communications

When we consider amateur space communications, we usually think about two basic modes: satellite and earth-moon-earth (EME—also referred to as *moonbounce*). At their essence, both modes communicate using one of the Earth's satellites—our natural satellite (the Moon) or one of a variety of manmade satellites.

There are two main differences between these satellites. The first is one of distance. The Moon is about 250,000 miles from Earth, while man-made satellites can be as far as 36,000 miles away. This 7:1 difference in distance makes a huge difference in the signals that arrive at the satellite, since transmission loss varies as the square of the distance. In other words, the signal arriving at the Moon is 20 dB weaker than that arriving at a geo-synchronous satellite 25,000 miles high, due to distance alone.

The second difference between the Moon and a man-made satellite is that the Moon is a *passive reflector*—and not a very good one at that, since it has a craggy and rather irregular surface, at least when compared to a flat mirror-like surface that would make an ideal reflector. Signals scattered by the Moon's irregular surface are thus weaker than for better reflecting surfaces. By comparison, a man-made satellite is an *active* system, where the satellite receives the signal coming from Earth, amplifies it and then retransmits the signal (usually at a different frequency) using a high-gain antenna. Think of a satellite as an ideal reflector, with gain.

The net result of these differences between a man-made satellite and the Earth's natural satellite is that moonbounce (EME) operation challenges the station builder considerably more than satellite operation, particularly in the area of antennas. Successful EME requires high transmitting power, superb receiver sensitivity and excellent operators capable of pulling weak signals out of the noise. This chapter will first explore antennas suitable for satellite operations and then describe techniques needed for EME work.

Common Ground

There are areas of commonality between satellite and EME antenna requirements, of course. Both require consideration of the effects of polarization and elevation angle, along with the azimuth directions of transmitted and received signals.

On the HF bands, signal polarization is generally of little concern, since the original polarization sense is lost after the signal passes through the ionosphere. At HF, vertical antennas receive sky-wave signals emanating from horizontal antennas, and vice versa. It is not beneficial to provide a means of varying the polarization at HF. With satellite communications, however, because of polarization changes, a signal that would disappear into the noise on one antenna may be S9 on one that is not sensitive to polarization direction. Elevation angle is also important from the standpoint of tracking and avoiding indiscriminate ground reflections that may cause nulls in signal strength.

Antennas for Satellite Work

We have amateur satellites providing links from 2 meters and up, and these provide opportunities to use antennas of many types—from the very simple to some pretty complex ones. This section was written by Dick Jansson, WD4FAB. It covers descriptions of a wide range of satellite antennas and points operators to source material for construction of many of them.

Antennas for LEO Satellites

Antenna design and construction requirements for use with Amateur satellites vary from low-gain antennas for low-earth-orbit (LEO) satellites to higher-gain antennas for the high-altitude elliptical-orbit satellites. You can operate the FM LEO satellites with a basic dual-band VHF/UHF FM transceiver or even a good FM H-T, as some amateurs have managed. Assuming that the transceiver is reasonably sensitive, you can even use a good "rubber duck" antenna. Some amateurs manage to work the FM birds with H-Ts and a multi-element directional antenna such as the popular Arrow Antenna, **Fig 1**. Of course, this means they must aim their antennas at the satellites, even as they cross overhead.



Fig 1—The hand-held "Arrow" gain antenna is popular for LEO FM operations. (*Photo courtesy* The AMSAT Journal, *Sept/Oct 1998.*)

High-quality omnidirectional antennas for LEO service come in quite a number of forms and shapes. M^2 Enterprises has their EB-144 and EB-432 Eggbeater antennas, which have proven to be very useful and do not require any rotators for control. See **Fig 2**. The turnstile-over-reflector antenna has been around for a long time, as shown in **Fig 3**. Other operators have done well using low-gain Yagi antennas, such as those shown in **Fig 4**.



Fig 2—Eggbeater antennas are popular for base station LEO satellite operations. This EB-432 eggbeater antenna for 70 cm is small enough to put in an attic. Antenna gain pattern is helped with the radials placed below the antenna.

For even better performance, at the modest cost of a single, simple TV antenna rotator, check out the fixed-elevation *Texas Potato Masher* antenna by K5OE, **Fig 5.** This antenna provides a dual-band solution for medium-gain directional antennas for LEO satellites. This is a considerable improvement over omnidirectional antennas and does not require an elevation rotator for good performance.

There are still two LEO satellites that work on the 10-meter band, RS-15 and the newly resurrected AO-7. Both have 10-meter downlinks in the range of 29.3 to 29.5 MHz. Low-gain 10-meter antennas, such as dipoles or long-wire antennas, are used to receive these satellites.

Antennas for High-Altitude Satellites

The high-altitude, Phase-3 satellites, such as AO-10 (and the late AO-13), have been around for quite a number of years. The greater distances to the Phase-3 satellites mean that more transmitted power is needed to access them and weaker signals are received on the ground. Successful stations usually require ground-station antennas with significant gain (12 dBi or more), such as a set of high-gain Yagi antennas. See **Fig 6**. Note the use of two Yagi antennas mounted on each boom to provide *circular polarization*, usually referred to as CP.



Fig 3—The Turnstile Over Reflector antenna has served well for LEO satellite service for a number of years.



Fig 5—Jerry Brown, K5OE, uses his Texas Potato Masher antennas to work LEO satellites.



Fig 4—Simple ground plane and Yagi antennas can be used for LEO satellite contacts.



Fig 6—Dick Jansson, WD4FAB, used these 2-meter and 70-cm crossed Yagi's in RHCP for AO-10 and AO-13 operations. The satellite antennas are shown mounted above a 6-meter long-boom Yagi.

CIRCULAR POLARIZATION

Linearly polarized antennas are horizontal or vertical in terms of the antenna's position relative to the surface of the Earth, a reference that loses its meaning in space. The need to use circularly polarized (CP) antennas for space communications is well established. If spacecraft antennas used linear polarization, ground stations would not be able to maintain polarization alignment with the spacecraft because of changing orientations. The ideal antenna for random satellite polarizations is one with a circularly polarized radiation pattern.

There are two commonly used methods for obtaining circular polarization. One is with crossed linear elements such as dipoles or Yagis, as Fig 6 shows. The second popular CP method uses a helical antenna, described below. Other methods also exist, such as with the omnidirectional quadrifilar helix, **Fig 7**.

Polarization *sense* is a critical factor, especially in EME and satellite work. The IEEE standard uses the term "clockwise circular polarization" for a *receding* wave. Amateur technology follows the IEEE standard, calling clockwise polarization for a receding wave as right-hand, or RHCP. Either clockwise or a counter-clockwise (LHCP) sense can be selected by reversing the phasing harness of a crossed-Yagi antenna, see **Fig 8**. The sense of a helical antenna is fixed, determined by its physical construction.



Fig 7—W3KH suggests that quadrifilar antennas can serve well for omnidirectional satellite-station antenna service.



Fig 8—Evolution of the circularly polarized Yagi. The simplest form of crossed Yagi, A, is made to radiate circularly by feeding the two driven elements 90° out of phase. Antenna B has the driven elements fed in phase, but has the elements of one bay mounted $^{1}/_{4}$ λ forward from those of the other. Antenna C offers elliptical (circular) polarization using separate booms. The elements in one set are perpendicular to those of the other and are $^{1}/_{4}$ λ forward from those of the other.

See **Fig 9** for construction details.

In working through a satellite with a circularly polarized antenna, it is often convenient to have the capability of switching polarization sense. This is because the sense of the received signal of some of the LEO satellites reverses when the satellite passes its nearest point to you. If the received signal has right-hand circular polarization as the satellite approaches, it may have left-hand circularity as the satellite recedes. There is a sense reversal in EME work, as well, because of a phase reversal of the signal as it is reflected from the surface of the moon. A signal transmitted with right-hand circularity will be returned to the Earth with left-hand circularity. Similarly, the polarization is reversed as it is reflected from a dish antenna, so that for an overall RHCP performance, the feed antenna for the dish needs to be LHCP.

Crossed Linear Antennas

Dipoles radiate linearly polarized signals, and the polarization direction depends on the orientation of the antenna. It two dipoles are arranged for horizontal and vertical dipoles, and the two outputs are combined with the correct phase difference (90°), a circularly polarized wave results. Because the electric fields are identical in magnitude, the power from the transmitter will be equally divided between the two fields. Another way of looking at this is to consider the power as being divided between the two antennas; hence the gain of each is decreased by 3 dB when taken alone in the plane of its orientation.

A 90° phase shift must exist between the two antennas and the simplest way to obtain this shift is to use two feed lines to a coplanar pair of crossed-Yagi antennas. One feed-line section is $^{1}/_{4}$ λ longer than the other, as shown in Fig 8A. These separate feed lines are then paralleled to a common transmission line to the transmitter or receiver. Therein lies one of the headaches of this system. Assuming negligible coupling between the crossed antennas, the impedance presented to the common transmission line by the parallel combination is one half that of either section alone. (This is not true when there is mutual coupling between the antennas, as in phased arrays.) A practical construction method for implementing a RHCP/LHCP coplanar switched system is shown in **Fig 10**.

Another example of a coplanar crossed-Yagi antenna is shown in **Fig 11**. With this phasing-line method, any mismatch at one antenna will be magnified by the extra $^{1}/_{4}$ λ of transmission line. This upsets the current balance between the two antennas, resulting in a loss of polarization circularity. Another factor to consider is the attenuation of the cables used in the harness, along with the


Detail "A"
Detail "B"
Drill Through and Solder
Boom 1-1/4" TV Masting
5/16" Copper Tubing
Radiator 5/16" Tubing
Gamma Rod 1/4" Tubing
Gamma Capacitor 5/8" Tubing
Gamma Shorting Bar
Phasing Section (See Text)
A
B
R
Ra
D1
D2
D3
D4
D5
D6
D7

Fig 9—Construction details of a co-planar crossed-Yagi antenna.


50-Ω Feeds
λ /4 –75Ω Lines
Relay
100-Ω Tee Junction
100-Ω Tee Junction
λ/4-95 Ω Phasing Line
50 Ω Line

Fig 10—Co-planar crossed Yagi, circularly polarized antenna with switchable polarization phasing harness.

connectors. Good low-loss coaxial line should be used. Type-N or BNC connectors are preferable to the UHF variety.

Another method to obtain circular polarization is to use equal-length feed lines and place one antenna $^1/_4$ λ ahead of the other. This offset pair of Yagi-crossed antennas is shown in Fig 8B. The advantage of equal-length feed lines is that identical load impedances will be presented to the common feeder, as shown in **Fig 12**, which shows a fixed circularity sense feed. To obtain a switchable sense feed with the offset Yagi pair, you can use a connection like that of **Fig 13**, although you must compensate for the extra phase added by the relay and connectors.

Fig 8C diagrams a popular method of mounting two separate off-the-shelf Yagis at right angles to each other. The two Yagis may be physically offset by $^1/_4$ λ and fed in parallel, as shown in Fig 8C, or they may be mounted with no offset and fed 90° out of phase. Neither of these arrangements on two separate booms produces true circular polarization. Instead, *elliptical* polarization results from such a system. **Fig 14** is a photo of this type of mounting of Yagis on two booms for elliptical operation.

Helical Antennas

As mentioned, the second method to create a circularly polarized signal is by means of a helical antenna. The axial-mode helical antenna was introduced by Dr John Kraus, W8JK, in the 1940s. **Fig 15** shows examples of S-band (2400-MHz), V-band (145-MHz), and U-band (435-MHz) helical antennas, all constructed by WD4FAB for satellite service.

This antenna has two characteristics that make it



Fig 11—This VHF crossed Yagi design by KH6IJ (Jan 1973 *QST*) illustrates the co-planar, fixed-circularity Yagi.



Fig 12—Offset crossed-Yagi circularly polarized antenna-phasing harness with fixed polarization.

especially interesting and useful in many applications. First, the helix is circularly polarized. As discussed earlier, circular polarization is simply linear polarization that continually rotates as it travels through space. In the case of a helical antenna, this rotation is about the axis of the antenna. This can be pictured as the second hand of a watch moving at the same rate as the applied frequency, where the position of the second hand can be thought of as the instantaneous polarization of the signal.

The second interesting property of the helical antenna is its predictable pattern, gain and impedance characteristics over a wide frequency range. This is one of the few antennas that has both broad bandwidth and high gain. The benefit of this property is that, when used for narrow-band applications, the helical antenna is very forgiving of mechanical inaccuracies.

Probably the most common amateur use of the helical antenna is in satellite communications, where the spinning of the satellite antenna system (relative to the earth) and the effects of Faraday rotation cause the polarization of the satellite signal to be unpredictable. Using a linearly polarized antenna in this situation results in deep fading, but with the helical antenna (which responds equally to linearly polarized signals), fading is essentially eliminated.

This same characteristic makes helical antennas useful in polarization-diversity systems. The advantages of circular polarization have been demonstrated on VHF voice schedules over non-optical paths, in cases where linearly polarized beams did not perform satisfactorily.

Another use for the helical antenna is the transmission of color ATV signals. Many beam antennas (when adjusted for maximum gain) have far less bandwidth than the required 6 MHz, or have non-uniform gain over this frequency range. The result is significant distortion of the transmitted and received signals, affecting color reproduction and other features. This problem becomes more aggravated over non-optical paths. The helix exhibits maximum gain (within 1 dB) more than 20 MHz anywhere above 420 MHz.

The helical antenna can be used to advantage with multimode rigs, especially above 420 MHz. Not only does the helix give high gain over an entire amateur band, but it also allows operation on FM, SSB and CW without the need for separate vertically and horizontally polarized antennas.

Helical Antenna Basics

The helical antenna is an unusual specimen in the antenna world, in that its physical configuration gives a



Fig 13—Offset crossed-Yagi circularly polarized antenna-phasing harness with switchable polarization.



Fig 14—An example of offset crossed-Yagi circularly polarized antennas with fixed polarization. This example is a pair of M^2 23CM22EZA antennas, for L band (1269 MHz), mounted on an elevation boom. (*WD4FAB photo.*)



Fig 15—At top, a seven-turn LHCP helical antenna for S-band dish feed for AO-40 service. This helical antenna uses a cupped reflector and has a preamplifier mounted directly to the antenna feed point. At bottom, a pair of helical antennas for AO-10 service on 2 meters and 70 cm. The 2-meter helical antenna is not small! (*WD4FAB photos.*)

hint to its electrical performance. A helix looks like a large air-wound coil with one of its ends fed against a ground plane, as shown in **Fig 16**. The ground plane is a screen of 0.8 λ to 1.1 λ diameter (or on a side for a square ground plane). The circumference (C_λ) of the coil form must be between 0.75 λ and 1.33 λ for the antenna to radiate in the axial mode. The coil should have at least three turns to radiate in this mode. The ratio of the spacing between turns (in wavelengths), S_λ to C_λ, should be in the range of 0.2126 to 0.2867. This ratio range results from the requirement that the pitch angle, α, of the helix be between 12° and 16°, where:

$$\alpha = \arctan \frac{S_\lambda}{C_\lambda} \qquad \text{(Eq 1)}$$



Fig 16—The basic helical antenna and design equations.

These constraints result in a single main lobe along the axis of the coil. This is easily visualized from Fig 15A. The winding of the helix comes away from the cupped reflector with a counterclockwise winding direction for a LHCP. (The winding can also be a clockwise—this results in a RHCP polarization sense.)

A helix with a C_λ of 1λ has a wave propagating from one end of the coil (at the ground plane), corresponding to an instantaneous dipole "across" the helix. The electrical rotation of this dipole produces circularly polarized radiation. Because the wave is moving along the helix conductor at nearly the speed of light, the rotation of the electrical dipole is at a very high rate, and true circular polarization results.

The IEEE definition, in simple terms, is that when viewing the antenna from the feed-point end, a clockwise wind results in right-hand circular polarization (RHCP), and a counterclockwise wind results in left-hand circular polarization (LHCP). This is important, because when two stations use helical antennas over a nonreflective path, both must use antennas with the same polarization sense. If antennas of opposite sense are used, a signal loss of at least 20 dB results from the cross polarization alone.

As mentioned previously, circularly polarized antennas can be used in communications with any linearly polarized antenna (horizontal or vertical), because circularly polarized antennas respond equally to all linearly polarized signals. The gain of a helix is 3 dB less than the theoretical gain in this case, because the linearly polarized antenna does not respond to linear signal components that are orthogonally polarized relative to it.

The response of a helix to all polarizations is indicated by a term called *axial ratio*, also known as *circularity*. Axial ratio is the ratio of amplitude of the polarization that gives maximum response to the amplitude of the polarization that gives minimum response. An ideal circularly polarized antenna has an axial ratio of 1.0. A well-designed practical helix exhibits an axial ratio of 1.0 to 1.1. The axial ratio of a helix is:

$$AR = \frac{2n + 1}{2n} \qquad \text{(Eq 2)}$$

where:

AR = axial ratio
n = the number of turns in the helix

Axial ratio can be measured in two ways. The first is to excite the helix and use a linearly polarized antenna with an amplitude detector to measure the axial ratio directly. This is done by rotating the linearly polarized antenna in a plane perpendicular to the axis of the helix and comparing the maximum and minimum amplitude values. The ratio of maximum to minimum is the axial ratio.

The impedance of the helix is easily predicted. The terminal impedance of a helix is unbalanced, and is defined by:

$$Z = 140 \times C_\lambda \qquad \text{(Eq 3)}$$

where Z is the impedance of the helix in ohms.

The gain of a helical antenna is determined by its physical characteristics. Gain can be calculated from:

$$\text{Gain}\left(\text{dBi}\right) = 11.8 + 10 \log\left(C_\lambda^{2}\, nS_\lambda\right) \qquad \text{(Eq 4)}$$

In practice, helical antennas do not deliver the gain in Eq 4 for antennas with turns count greater than about twelve. There will be more discussions in this area when practical antennas are discussed.

The beamwidth of the helical antenna (in degrees) at the half-power points is:

$$BW = \frac{52}{C_\lambda \sqrt{nS_\lambda}} \qquad \text{(Eq 5)}$$

The diameter of the helical antenna conductor should be between 0.006 λ and 0.05 λ, but smaller diameters have been used successfully at 144 MHz. The previously noted diameter of the ground plane (0.8 λ to 1.1 λ) should not be exceeded if you desire a clean radiation pattern. As the ground plane size is increased, the sidelobe levels also increase. Cupped ground planes have been used according to Kraus, as in Fig 15. (The ground plane need not be solid; it can be in the form of a spoked wheel or a frame covered with hardware cloth or screen.)

50-Ω Helix Feed

Joe Cadwallader, K6ZMW, presented this feed method in June 1981 *QST*. Terminate the helix in an N connector mounted on the ground screen at the periphery of the helix. See **Fig 17**. Connect the helix conductor to the N connector as close to the ground screen as possible (**Fig 18**). Then adjust the first quarter turn of the helix to a close spacing from the reflector.

This modification goes a long way toward curing a deficiency of the helix—the 140-Ω nominal feed-point



Fig 17—End view and side view of peripherally fed helix.



Fig 18—Wrong and right ways to attach helix to a type N connector for 50-Ω feed.



Fig 19—End view and side view of peripherally fed helix with metal strip added to improve transformer action.

impedance. The traditional λ/4 matching section has proved difficult to fabricate and maintain. But if the helix is fed at the periphery, the first quarter turn of the helix conductor (leaving the N connector) acts much like a transmission line—a single conductor over a perfectly conducting ground plane. The impedance of such a transmission line is:

$$Z_0 = 138 \log \frac{4h}{d} \qquad \text{(Eq 6)}$$

where:

Z_0 = line impedance in ohms
h = height of the center of the conductor above the ground plane
d = conductor diameter (in the same units as h).

The impedance of the helix is 140 Ω a turn or two away from the feed point. But as the helix conductor swoops down toward the feed connector (and the ground plane), h gets smaller, so the impedance decreases. The 140-Ω nominal impedance of the helix is transformed to a lower value. For any particular conductor diameter, an optimum height can be found that will produce a feed-point impedance equal to 50 Ω. The height should be kept very small, and the diameter should be large. Apply power to the helix and measure the SWR at the operating frequency. Adjust the height for an optimum match.

Typically, the conductor diameter may not be large enough to yield a 50-Ω match at practical (small) values of h. In this case, a strip of thin brass shim stock or flashing copper can be soldered to the first quarter turn of the helix conductor (**Fig 19**). This effectively increases the conductor diameter, which causes the impedance to decrease further yet. The edges of this strip can be slit every $^1/_2$ inch or so, and the strip bent up or down (toward or away from the ground plane) to tune the line for an optimum match.

This approach yields a perfect match to nearly any coax. The usually wide bandwidth of the helix (70% for less than 2:1 SWR) will be reduced slightly (to about 40%) for the same conditions. This reduction is not enough to be of any consequence for most amateur work. The improvements in performance, ease of assembly and adjustment are well worth the effort in making the helix more practical to build and tune.

ANTENNAS FOR AO-40 OPERATIONS

Antennas for successful operations on AO-40 come in many shapes and sizes. AO-40 has provided amateurs the opportunity to broadly experiment with antennas.

Fig 20 shows the satellite antennas at WD4FAB. The Yagi antennas are used for the U- and L-band AO-40 uplinks and the V-band AO-10 downlink, while the S-band dish antenna is for the AO-40 downlink. These satellite antennas are tower mounted at 63 feet (19 meters) to avoid pointing into the many nearby trees and suffering from the resulting “green attenuation.” Of course, satellite antennas do not always need to be mounted high on a tower if dense foliage is not a problem. If satellite antennas are mounted lower down, feed-line length and losses can reduced.

Another benefit, however, to tower mounting of satellite antennas is that they can be used for terrestrial ham communications and contests. The fact that the antennas are set up for CP does not really degrade these other operating activities.

Experience with AO-40 has clearly shown the advan-



Fig 20—Details of WD4FAB's tower cluster of satellite antennas including a home-brew elevation rotator. Top to bottom: M^2 436-CP30, a CP U-band antenna; two M^2 23CM22EZA antennas in a CP array for L band; "FABStar" dish antenna with helix feed for S band; M^2 2M-CP22, a CP V-band antenna (only partially shown.) To left of dish antenna is a NEMA4 equipment box with an internal 40-W L-band amplifier, and also hosts externally mounted preamplifiers. (*WD4FAB photo*)



Fig 21—Domenico, I8CVS, has this cluster of satellite antennas for AO-40. Left to right: array of 4 × 23-element Yagi horizontally polarized for L band; 1.2-meter dish with 3-turn helix feed for S band; 15-turn RHCP helical antenna for U band; 60-cm dish for X band. All microwave preamplifiers and power amplifiers are homebrew and are mounted on this antenna cluster. (*I8CVS photo.*)

tages of using RHCP antennas for both the uplink and downlink communications. The antennas shown in Fig 20 are a single-boom RHCP Yagi antenna for U band, a pair of closely spaced Yagi antennas phased for RHCP for L band (see Fig 14), and a helix-fed dish antenna for S band. The antenna gain requirements for U band can easily be met with the gain of a 30-element crossed Yagi. Antennas of this size have boom lengths of 4 to 4$^1/_2$ wavelengths. The enterprising constructor can build a Yagi antenna from one of several references, however most of us prefer to purchase well-tested antennas from commercial sources as M^2 or Hy-Gain. In the past, KLM (now out of business) had offered a 40-element CP Yagi for U-band satellite service, and many of these are still in satisfactory use today.

U-band uplink requirements for AO-40 have clearly demonstrated the need for gain less than 16 to 17 dBic RHCP, with an RF power of less than 50 W PEP at the antenna (≈ 2,500 W-PEP EIRP with a RHCP antenna) depending upon the *squint angle*. (The squint angle is the angle at which the main axis of the satellite is pointed away from your antenna on the ground. If the squint angle is less than half of the half-power beamwidth, the ground station will be within the spacecraft antenna's nominal beam width.)

A gain of 16 to 17 dBic RHCP can be obtained from a 30-element crossed Yagi, AO-13 type antenna, and is good news, considering that the satellite may be over 60,000 km (37,000 miles) from your station. Success on the U-band uplinks to AO-40 is easier than those for L band at wider squint angles more than 20°. At squint angles less than 10°, U-band uplink operation can even be done with 1-5 W power outputs to a RHCP antenna (≈ 200 W-PEP EIRP with RHCP). These lower levels mean that smaller antennas can be used. In practice, these uplinks will produce downlink signals that are 10 to 15 dB above the noise floor, or S7 signals over an S3 noise floor. The beacon will give a downlink S9 signal for these same conditions.

WD4FAB's experience with the AO-40 L-band uplink has demonstrated that 40 W-PEP delivered to an antenna with a gain of ≈ 19dBic (3,000 W-PEP EIRP with RHCP) is needed for operations at the highest altitudes of AO-40 and with squint angles ≤ 15°. This is the pretty compact L-band antenna arrangement with two 22-element antennas in a RHCP array shown in Fig 14 and 20. Other operators have experience that using a 1.2-meter L-band dish antenna and 40 W of RF power (6,100 W-PEP EIRP with RHCP) can also provide a superb uplink for squint angles even up to 25°. A dish antenna can have a practical gain of about 21 to 22 dBic. These uplinks will provide the user a downlink that is 10 to 18 dB above the transponder noise floor. In more practical terms, this is an S7 to 8 signal over a S3 transponder noise floor, a very comfortable armchair copy.



Fig 22—Wilfred Carey, ZS6JT, constructed this cluster of satellite and EME antennas. Left to right: 2 × 23-element offset feed Yagi for U band; 1.64-meter dish with 2^1/$_4$-turn helix feed for S band; 2 × 11-element coplanar feed Yagi for V band. (*ZS6JT photo.*)

Using the L-band uplink for AO-40, instead of the U-band uplink, allows the use of Yagi antennas that more manageable, since their size for a given gain is only one third of those for U-band. With L band there is a narrower difference between using a dish antenna and a Yagi, since a 21- to 22-dBic dish antenna would be only about 1.2 meters (4 feet) in diameter. However, some of us may not have such "real estate" available on our towers and may seek a lower wind-loading solution offered by Yagis. Long-boom rod-element Yagi, or loop-Yagi antennas are commercially offered by M^2 and DEM, although this band is about the highest for practical Yagis. The example shown in Fig 20 is a pair of rod-element Yagi antennas from M^2 in a CP arrangement with a gain of 18 to 19 dBic.

Other amateurs have successful AO-40 operation with different arrangements. **Fig 21** shows I8CVS's 4 × 23-element linear array for a 1270 MHz, a 1.2-meter solid dish for 2400 MHz, a 15-turn helical antenna for 435 MHz, and a 60-cm dish for 10,451 MHz. This arrangement clearly shows the advantage and accessibility of having a roof-mounted antenna.

Fig 22 shows ZS6JT's setup, with a 1.64-meter home-built mesh dish for 2400 MHz and two home-built crossed Yagi antennas, one for 435 MHz and the other for 145 MHz. Note that in these examples, the antennas permit terrestrial communication as well as satellite service. Two of these stations have also maintained the capability to operate the LEO satellites with U- and V-band antennas.

A number of amateurs have taken advantage of the availability of surplus C-band TVRO dishes, since most users of satellite television have moved up to the more



Fig 23—Robert Suding, WØLMD, modified this 4-foot dish antenna with a patch feed for S band and an Az-El mount. (*WØLMD photo.*)



Fig 24—WØLMD graduated to this 8-foot dish with patch feed for S band for AO-40. On the left is a helical antenna for L band and on the right is a 2 × 9-element offset-feed Yagi for U band. A home-brew Az-El mount is provided. (*WØLMD photo.*)

convenient K band using 0.5-meter dishes. Some examples of these dish conversions for satellite communications are shown in **Fig 23**, a WØLMD 4-foot dish with patch feed and Az-El mount. **Fig 24** shows a WØLMD 8-foot dish with patch feed, Az-El mount, a U-band Yagi, and an L-band helical antenna.

Fig 25 is a WØLMD 10-foot dish with tri-band patch feed and Az-El mount; and **Fig 26** is also a WØLMD



Fig 25—WØLMD increased to this 10-foot dish for AO-40 operations, with a triband patch feed for U, L, and S bands on an Az-El mount. (*WØLMD photo.*)



Fig 26—WØLMD found the ultimate in this 14-foot dish for AO-40, with a triband patch feed and Az-El mount. (*WØLMD photo.*)



Fig 27—Clair E. Cessna, K6LG, has this 10-foot dish with S-band patch feed. This dish uses the original polar-mounting system and offsets the patch feed to compensate for AO-40's deviation from the Clarke belt. (*K6LG photo.*)



Fig 28—K5GNA's "circularized" mesh modification of an MMDS dish antenna with a helix-CP feed and DEP preamp. The dish modification reduces the spillover loss by making the antenna fully circular. (*K5OE photo.*)

14-foot dish with tri-band patch feed and Az-El mounting. Other operators, like K6LG, have been able to use TVRO dishes, **Fig 27**, with multiband patch feeds and still use, within limits, their polar-mounting system, as will be explained later.

Other hams have taken advantage of other surplus dish situations. **Fig 28** shows modified MMDS dishes, by K5GNA, and **Fig 29**, by K5OE, both using helix feeds. **Fig 30** shows a 75-cm high modified PrimeStar offset feed dish, by WD4FAB, using a longer helical feed antenna because of the higher f/D ratio of this dish configuration. This dish provides 5 dB of Sun noise, which is good performance. These efforts have rewarded their users with superb service on AO-40. Many have experimented with different feed and mounting systems. These experiments will be further illustrated.

One very popular spun-aluminum dish antenna seen in use on AO-40 has been the G3RUH-ON6UG 60-cm unit with its S-band patch feed, **Fig 31**. A kit, complete with a CP-patch feed is available from SSB-USA and has a gain of 21 dBic. It provides a 2.5-dB Sun noise signal. Surplus dishes have not been the only source for antennas for AO-40 operations, since some ingenious operators have even turned to the use of cardboard boxes. See **Figs 32** to **35**.



Fig 29—Mesh modification of an MMDS dish antenna by Jerry Brown, K5OE, with a helix-CP feed and DEM preamplifier mounted directly to the helix feed point. (*K5OE photo.*)



Fig 31—G3RUH's 60-cm spun-aluminum dish with CP-patch feed is available as a kit. This antenna has been popular with many AO-40 operators all over the world.



Fig 30—PrimeStar offset-fed dish with WD4FAB's helix-feed antenna. NØNSV was so pleased with the modification that he renamed the dish "FABStar," and made a new label! (*NØNSV photo.*)



Fig 32—A complete satellite station with the tracking laptop, FT-847 transceiver, and both downlink and uplink cardboard-box antennas.

Parabolic Reflector Antennas

The satellite S-band downlinks have become very popular for a variety of reasons:

- Good performance with physically small downlink antennas
- Availability of good-quality downconverters
- Availability of preamps at reasonable prices.

A number of people advocate S-band operation, including Bill McCaa, KØRZ, who led the team that designed and built the AO-13 S-band transponder and James Miller, G3RUH, who operates one of the AO-40 command stations. Ed Krome, K9EK, and James Miller have published a number of articles detailing construction of preamps, downconverters and antennas for S band.

Some access AO-40's S-band downlink using compact S-band helical antennas. See **Fig 36**. With the demise of AO-40's S1 transmitter and its high-gain downlink antenna, enthusiasts have had to employ high-gain parabolic-dish antennas to use AO-40's S2 downlink, with its lower-gain helical antenna.

WØLMD notes that like a bulb in a flashlight, the



Fig 33—The completed high-performance corner-reflector uplink antenna for U band. Note how the box corners hold the reflectors and dipole feed in place. The rear legs set the antenna elevation to 20°—this gives good coverage at the design latitude but will need modification for other stations.



Fig 35—Side view of the downlink pyramidal horn showing the elevation control supports and how the downconverter is attached to the horn. The downconverter is pulled forward by the tape to align the probe wire parallel to the rear surface of the horn.



Fig 34—Front view of the downlink pyramidal horn showing how it is mounted in the support carton. Notice the coax probe at the back of the horn.



Fig 36—WD4FAB's example of a 16-turn S-band helical antenna for AO-40. This is about the maximum length of any practical helix. Note the SSB UEK2000 down-converter mounted behind the reflector of the antenna. (*WD4FAB photo.*)

parabolic reflector or dish antenna must have a feed source looking into the surface of the dish. Some dishes are designed so that the feed source is mounted directly in front of the dish. This is referred to as a *center-fed dish*. Other dishes are designed so that the feed source is off to one side, referred to as an *off-center-fed dish*, or just offset-fed dish, as shown in Fig 30. The offset-fed dish may be considered a side section of a center-fed dish. The center-fed dish experiences some signal degradation due to blockage of the feed system, but this is usually an insignificantly small amount. The offset-fed dish is initially more difficult to aim, since the direction of reception is not the center axis, as it is for center-fed dishes.

The basic design precepts of parabolic-dish antennas are covered in more detail in the EME Antenna section of this chapter. Dish antenna properties specific to satellite operations are covered here. The dish's parabola can be designed so the focus point is closer to the surface of the dish, referred to a *short-focal-length* dish, or further away from the dish's surface, referred to as a *long-focal-length* dish. To determine the exact focal length, measure the diameter of the dish and the depth of the dish.

$$f = \frac{D^2}{16d} \qquad \text{(Eq 7)}$$

The focal length divided by the diameter of the dish gives the *focal ratio*, commonly shown as f/D. Center-fed dishes usually have short-focal ratios in the range of f/D = 0.3 to 0.45. Offset-fed dishes usually have longer focal lengths, with f/D = 0.45 to 0.80. If you attach two small mirrors to the outer front surface of a dish and then point the dish at the Sun, you can easily find the focus point of the dish. Put the reflector of the patch or helix feed just beyond this point of focus.

An alternate method for finding a dish's focal length is suggested by W1GHZ (ex-N1BWT), who provides a computer program called *HDL_ANT*, available at: **www.w1ghz.org/10g/10g_home.htm**. The method literally measures a solid-surface dish by the dimensions of the bowl of water that it will form when properly positioned. (See: **www.qsl.net/n1bwt/chap5.pdf**.) WD4FAB used this method on the dish of Fig 30, carefully leveling the bowl, plugging bolt holes, and filling it with water to measure the data needed by the W1GHZ Web-site calculation.

While many of us enjoy building our own antennas, surplus-market availability of these small dish antennas makes their construction unproductive. Many AO-40 operators have followed the practices of AO-13 operators using a surplus MMDS linear-screen parabolic reflector antenna, Figs 28 and 29. These grid-dish antennas are often called *barbeque dishes*. K5OE and K5GNA have shown how to greatly improve these linearly polarized reflectors by adapting them for the CP service desired for AO-40. Simple methods can be used to *circularize* a linear dish and to further add to its gain using simple methods to increase the dish area and feed efficiency.



Fig 37—Prototype 1.2-meter dish by Rick Fletcher, KG6IAL, using a dual-band (L and S) patch-feed antenna for AO-40. See text. This kit dish is covered with $^1/_4$-inch mesh. (*KG6IAL photo.*)

Another approach is the construction of a kit-type dish antenna, just becoming available in 1.2-meter and 1.8-meter diameters. This ingenious design by KG6IAL is available from his Web site **www.teksharp.com/**. **Fig 37** shows the prototype of the 1.2-meter dish with an f/D of 0.30. The 1.2-meter dish is fed with a dual-band patch feed for L and S bands. The 1.8-meter dish is designed for up to three bands using a tri-band patch feed for the U, L and S bands. This dish will permit U-band operation. A Central States VHF Society measurement on a similar sized dish (by WØLMD) with a patch feed showed a gain of about 17.1 dBic (actual measurement was 12.0 dBd linearly fed). This performance along with a small V-band (145 MHz) Yagi would permit a very modest satellite antenna assembly for all of the VHF/UHF LEO satellites, as well as AO-40.

The ingenuity of the design of the KG6IAL antenna is that it is constructed of robust, $^1/_8$-inch-thick aluminum sheet that is numerically machined for the parabolic shape of the ribs. The backsides of the ribs are stiffened by a bent flange edge. The panel mesh is attached by using small tie-wraps or small aluminum wire through the mesh and holes provided along the parabolic edge. KG6IAL used $^1/_4$-inch mesh in the prototype antenna to reduce wind loading. A single formed conduit post is provided in the kit for mounting the patch-feed assembly. The post extends rearward to permit the attachment of a counterweight, if needed.

AO-40 has also provided some additional challenges to the ham operator. Besides its well-known S-band downlink, AO-40 also has a K-band downlink in the range of

24.05 GHz. This quite low-powered transmitter has provided a substantial challenge to some operators, such as N1JEZ, K5OE, W5LUA, G3WDG and others. N1JEZ documented his work in *QST* while K5OE shows his K-band work on his Web site and in the *Proceedings of the AMSAT Space Symposium*. See **Fig 38**.

Parabolic Dish Antenna Construction

In the USA large numbers of dishes can be obtained either free or at low cost. But in some parts of the world dishes are not so plentiful, so hams make their own. **Fig 39** shows G3RUH's S-band dish antenna. There are three parts to the dish antenna—the parabolic reflector, the boom and the feed. There are as many ways to construct this as there are constructors. You need not slavishly replicate every nuance of the design. The only critical dimensions occur in the feed system. After construction, you will have a 60-cm diameter S-band RHCP dish antenna with a gain of about 20 dBi and a 3-dB beamwidth of 18°. Coupled with the proper downconverter, performance will be more than adequate for S-band downlink.

The parabolic reflector used for the original antenna was intended to be a lampshade. Several of these aluminum reflectors were located in department-store surplus. The dish is 585 mm in diameter and 110 mm deep, corresponding to an f/D ratio of 585/110/16 = 0.33 and a focal length of 0.33 × 585 = 194 mm. The f/D of 0.33 is a bit too concave for a simple feed to give optimal performance but the price was right, and the under-illumination keeps ground noise pickup to a minimum. The reflector already had a 40-mm hole in the center with three 4-mm holes around it in a 25-mm radius circle.

The boom passes through the center of the reflector and is made from 12.7-mm square aluminum tube. The boom must be long enough to mount to the rotator boom on the backside of the dish. The part of the boom extending through to the front of the dish must be long enough



Fig 39—Detail of 60-cm S-band dish antenna with feed.



Fig 38—K5OE found this K-band dish on the Web and has set it up for the AO-40 K-band downlink. (*K5OE photo.*)

to mount the feed at the focus. If you choose to mount the downconverter or a preamp near the feed, some additional length will be necessary. Carefully check the requirements for your particular setup.

A 3-mm thick piece of aluminum, 65 mm in diameter, supports the boom at the center of the reflector. Once the center mounting plate is installed, the center boom is attached using four small angle brackets—two on each side of the reflector. See Fig 39 for details of reflector and boom assembly.

A small helix is used for the S-band antenna feed. The reflector for the helix is made from a 125-mm square piece of 1.6-mm thick aluminum. The center of the reflector has a 13-mm hole to accommodate the square center boom described above. The type-N connector is mounted to the reflector about 21.25 mm from the middle. This distance from the middle is, of course, the radius of a helical antenna for S-band. Mount the N connector with spacers so that the back of the connector is flush with the reflector surface. The helix feed assembly is shown in **Fig 40**.

Copper wire, or tubing, about 3.2 mm in diameter is used to form the helix. Wind four turns around a 40-mm diameter form. The turns are wound counterclockwise. This is because the polarization sense is reversed from RHCP when reflected from the dish surface. The wire helix will spring out slightly when winding is complete.

Once the helix is wound, carefully stretch it so that the turns are spaced 28 mm (±1 mm). Make sure the finished spacing of the turns is nice and even. Cut off the first half turn. Carefully bend the first quarter turn about 10° so it will be parallel to the reflector surface once the helix is attached to the N connector. This quarter turn will form part of the matching section.



All dimensions are in mm.

Fig 40—Details of helix feed for S-band dish antennas. The type-N connector is fixed with three screws and is mounted on a 1.6-mm spacer to bring the PTFE molding flush with the reflector. An easier mounting can be using a smaller TNC connector. Reflectors should be 95 to 100 mm in diameter.

Cut a strip of brass, 0.2 mm thick and 6 mm wide, and match the curvature of the first quarter turn of the helix, using a paper pattern. Be careful to get this pattern and subsequent brass cutting done exactly right. Using a large soldering iron and working on a heatproof surface, solder the brass strip to the first $^1/_4$ turn of the helix. Unless you are experienced at this type of soldering, getting the strip attached just right will require some practice. If it doesn't turn out right, just dismantle, wipe clean and try again.

After tack soldering the end of the helix to the type-N connector, the first $^1/_4$ turn, with its brass strip in place, should be 1.2 mm above the reflector at its start (at the N connector) and 3.0 mm at its end. Be sure to line up the helix so its axis is perpendicular to the reflector. Cut off any extra turns to make the finished helix have $2^1/_4$ turns total. Once you are satisfied, apply a generous amount of solder at the point the helix attaches to the N connector. Remember this is all that supports the helix.

Once the feed assembly is completed, pass the boom through the middle hole and complete the mounting by any suitable method. The middle of the helix should be at the geometric focus of the dish. In the figures shown here, the feed is connected directly to the downconverter and then the downconverter is attached to the boom. You may require a slightly different configuration depending on whether you are attaching a downconverter, preamp or just a cable with connector. Angle brackets may be used to secure the feed to the boom in a manner similar to the boom-to-reflector mounting. Be sure to use some method of waterproofing if needed for your preamp and/or downconverter.

Dish Feeds

W0LMD describes in **www.ultimatecharger.com/** that feeding a dish has two major factors that determine the efficiency. Like a flashlight bulb, the feed source should evenly illuminate the entire dish, and none of the feed energy should spillover outside the dish's reflecting surface. No feed system is perfect in illuminating a dish. Losses affect the gain from either under-illuminating or over-illuminating the dish (spillover losses). Typical dish efficiency is 50%. That's 3 dB of lost gain. A great feed system for one dish can be a real lemon on another. A patch feed system is very wide angle, but a helix feed system is narrow angle.

W0LMD has experimented with helical feeds for low f/D antennas ("deep" dishes) shown in **Fig 41**. A short-focal-ratio center-fed dish requires a wide-angle feed system to fully illuminate the dish, making the CP patch the preferred feed system. When used with an offset-fed dish, a patch-type feed system will result in a considerable spillover, or over-illumination loss, with an increased sensitivity to off-axis QRM, due to the higher f/D of this dish. Offset-fed



Fig 41—WØLMD's dual helix-dish feed for U and S bands. This early experimental feed was found to be wanting and he then turned to patch feeds for dishes. (*WØLMD photo.*)



Fig 42—K5OE's helix feed for his MMDS S-band dish antenna. (*K5OE photo.*)

dishes do much better when fed with a helix antenna.

A helix feed is simplicity personified. Mount a type N connector on a flat reflector plate and solder a couple of turns wire to the inner terminal. Designs are anywhere from 2 to 6 turns. The two-turn helices are used for very short-focal-length dishes in the f/D = 0.3 region, and the 6-turn helices are used with longer-focal-length (f/D ~ 0.6) dishes, typically offset-fed dishes. Since AO-40 is right circular and the dish reflection will reverse the polarity, the helix should be wound left circular, looking forward from the connector. Helix feeds work poorly on the short-focal-length dishes but really perform well on the longer-focal-length offset-fed dishes. K5OE shows us the helix feed for his modified MMDS dish in **Fig 42**. This design employs the cupped reflector of W8JK.

A Helix Feed for an Offset-Dish Antenna

This section describes WD4FAB's surplus PrimeStar offset-fed dish antenna with a 7-turn helical feed antenna, shown in Fig 30. This S-band antenna can receive Sun noise 5 dB above sky noise. (Don't try to receive Sun noise with the antenna looking near the horizon, since terrestrial noise will be greater than 5 dB, at least in a big-city environment.) WD4FAB received the dish from NØNSV, who renamed the finished product the "FABStar."

The dish's reflector is a bit out of the ordinary, with the shape of a horizontal ellipse. It is still a single paraboloid, illuminated with an unusual feed horn. At 2401 MHz (S band) we can choose to under-illuminate the sides of the dish while properly feeding the central section, or over-illuminate the center while properly feeding the sides. WD4FAB chose to under-illuminate. The W1GHZ water-bowl measurements showed this to be a dish with a focal point of 500.6 mm and requiring a feed for an f/D = 0.79. The total illumination angle of the feed is 69.8° in the vertical direction and a feed horn with a 3-dB beamwidth of 40.3°. At 50% efficiency this antenna was calculated to provide a gain of 21.9 dBi. A 7-turn helical feed antenna was estimated to provide the needed characteristics for this dish and is shown in **Fig 43**.

The helix is basically constructed as described for the G3RUH parabolic dish above. A matching section for the first λ/4 turn of the helix is spaced from the reflector at 2 mm at the start and 8 mm at the end of that fractional turn. Modifications of the G3RUH design include the addition of a cup reflector, a design feature used by the originator of the helical antenna, John Kraus, W8JK. For the reflector, a 2-mm thick circular plate is cut for a 94 mm (0.75 λ) diameter with a thin aluminum sheet metal cup, formed with a depth of 47 mm. Employment of the cup enhances the performance of the reflector for a dish feed, as shown by K5OE. (See the K5OE material on the CD-ROM accompanying this book.)

The important information for this 7-turn helical antenna is:

- Boom: 12.7-mm square tube or "C" channel.
- Element: $^1/_8$-inch diameter copper wire or tubing.

Close wind the element on a circular 1.50-inch tube or rod; the finished winding is 40 mm in diameter and spaced to a helical angle of 12.3°, or 28 mm spacing. These dimensions work out for an element circumference of 1.0 λ about the center of the wire.

When WD4FAB tackled this antenna, he felt that the small number of helical element supports used by G3RUH would be inadequate, in view of the real-life bird traffic on the antennas at his QTH. He chose to use PTFE (Teflon) support posts every $^1/_2$ turn. This closer spacing of posts permitted a careful control of the helix-winding diameter and spacing and also made the antenna very



Fig 43—Seven-turn LHCP helix feed for an offset dish, long f/D, antenna, with DEM preamp. (*WD4FAB photo.*)



Fig 45—Rain cover for preamp using a two-liter soft-drink bottle with aluminum foil tape for protection from sun damage. (*WD4FAB photo.*)



Fig 44—Mounting details of seven-turn helix and preamp. (*WD4FAB photo.*)

robust. He set up a fixture on the drill press to uniformly predrill the holes for the element spacers and boom. Attachment of the reflector is through three very small aluminum angle brackets on the element side of the boom.

Mounting of the helix to the dish requires modification of the dish's receiver-mounting boom. **Fig 44** shows these modifications using a machined mount. NM2A constructed one of these antennas and showed that a machine shop is not needed for this construction. He made a "Z" shaped mount from aluminum-angle plate and then used a spacer from a block of acrylic sheet. The key here is to get the dish focal point at the 1.5-turn point of the feed antenna, which is also at about the lip of the reflector cup.

The W1GHZ data for this focal point is 500.6 mm from the bottom edge of the dish and 744.4 mm from the top edge. A two-string measurement of this point can confirm the focal point, as shown by Wade in his writings. When mounting this feed antenna the constructor must be cautious to aim the feed at the beam-center of the dish, and not the geometric center, as the original microwave horn antenna was constructed. Taking the illumination angle information noted above, the helical feed antenna should be aimed 5.5° down from the geometric center of the dish.

As illustrated in Fig 44, a DEM preamp was directly mounted to the feed helix, using a TNC female connector on the helix, chosen for this case, since N connectors are quite large for this antenna. A male chassis connector should be mounted on the preamp so that the preamp can be directly connected to the antenna without any adaptors. This photo also illustrates how the reflector cup walls were riveted to the reflector plate.

Exposed connectors must be protected from rainwater. Commonly materials such as messy Vinyl Mastic Pads (3M 2200) or Hand Moldable Plastic (Coax Seal) are used. Since this is a tight location for such mastic applications, a rain cover was made instead from a 2-liter soft-drink bottle, **Fig 45**. Properly cutting off the top of the bottle allows it to be slid over the helix reflector cup and secured with a large hose clamp. You must provide UV protection for the plastic bottle and that was done with a wrapping of aluminum foil pressure-sensitive adhesive tape.

There are many methods for mounting this dish antenna to your elevation boom. You must give consideration to the placement of the dish to reduce the wind loading and off-balance to the rotator system. In WD4FAB's FABStar installation, the off-balance issue was not a major factor, as the dish was placed near the center of the elevation boom, between the pillow-block bearing supports. Since there is already a sizeable aluminum plate for these bearings, the dish was located to "cover" part of that plate, so as to not add measurably to the existing wind-loading area of the overall assembly.

A mounting bracket provided with the stock dish clamps to the end of a standard 2-inch pipe stanchion (actual measure: 2.38 inches in diameter). This bracket was turned around on the dish and clamped to the leg of a welded-pipe Tee assembly. See **Fig 46**. Pipe-reducing fittings were machined and fitted in the Tee-top bar, which was sawn in half for clamping over the $1^1/_2$ inch pipe used for the elevation boom. Bolts were installed through drilled holes and used to clamp this assembly.

Patch Feeds for Dish Antennas

Patch feeds are almost as simple as helix feeds. A patch is typically an N connector on a flat reflector plate with a tuned flat-metal plate soldered to the inner terminal. Sometimes the flat plate is square; sometimes it is rectangular; sometimes it is round. It could have two feed points, 90° out of phase for circular polarization, as used in the construction of the AO-40 U-band antennas. Some patches are rectangular with clipped corners to create a circular radiation pattern.

On 2401 MHz, the plate is 57 mm square and spaced 3 mm away from the reflector. The point of attachment is about halfway between the center and the edge. A round patch for 2401 MHz is about 66 mm in diameter. These patches work well on the shorter focal length center-fed MMDS and TVRO dishes. G3RUH made a CP patch feed for these short f/D dishes, shown in Fig 31 and **Fig 47**.

Robert, W0LMD, has done a considerable amount of experimenting with patch feeds for his dish antennas. One tri-band feed is shown in **Fig 48**. These are circular patches that have CP properties through the arrangement of the feed point and a small piston-variable capacitor that is offset from the feed point. **Fig 49** shows some of the many patches that Robert has created for his trials.



Fig 46—Welded pipefitting mount bracket for FABStar dish antenna. (*WD4FAB photo.*)

A No-Tune Dual-Band Feed for Mode L/S

Jerry, K5OE, notes that the AO-40 transponder has two uplink receivers active most of the time for CW/SSB activity. Most operators use U band at 435 MHz (70 cm). Also available, however, are two L-band (23-cm) receivers: L1 at 1269 MHz and L2 at 1268 MHz. The reasons for going to L band can be varied, but there is no arguing the benefits in reduced antenna size and AGC suppression. The types of L-band antennas are varied as well. Many use helices. Others use beams and arrays of beams. Still others use dishes, small and large.

K5OE recently acquired an old UHF TV dish measuring 1.2 meters in diameter. He wanted to use it both to receive on S band at 2401 MHz (13cm) and to transmit on the uplink on L band. He covered it with aluminum mesh and built a dual-helix feed for it, but was unhappy with the L-band performance. It seems the concentric helices interacted with each other substantially. Having had good success with patch feeds on S band, he designed, built and installed a dual-patch feed on a 1.5-meter solid dish for Field Day 2002. This arrangement worked superbly on uplink (with 25 W), but was embarrassingly deaf on receive. This second dual-band feed failure led him to experiment for months with different configurations, leading ultimately to the design presented here. The project goals were:

- Good performance on both S-band receive and L-band uplink.
- An easy-to-produce model using common hardware and simple hand tools.

Patches are better than helices as dish feeds. This revelation came to K5OE while doing investigation and



Fig 47—Details of CP-patch feed for short f/D dish antennas by G3RUH and ON6UG.



Fig 48—A triband (U, L and S bands) patch-CP feed for large dish antennas for AO-40 service. (*WØLMD photo.*)



Fig 49—Some of the many experimental CP-patch-feed antennas by WØLMD. (*WØLMD photo.*)



Fig 50—The 1.2-meter dish with dual-band patch feed installed. (*K5OE photo; courtesy of* The AMSAT Journal.)

experimenting with helix antennas. In the middle of this investigative foray, he saw the radiation pattern for the G3RUH patch feed published on James Miller's web site. When he modeled that pattern and input it into the W1GHZ feed pattern program, it produced an amazing 72% efficiency. The best helix he ever modeled has about 60% efficiency. I8CVS recently ran his own antenna range tests of a design similar to the G3RUH patch and produced a similarly impressive pattern.

Then K5OE came across the *truncated corners* square patch design popularized by K3TZ. This AO-40 design here is attributed to 7N1JVW, JF6BCC and JG1IIK. There are references in the literature going back over a decade for this now-common commercial design. The first model K5OE built outperformed his best helix-in-cup design by a full S unit (delta over the noise) on his FT-100 portable setup. Compared to a helix, the patch simply has better illumination efficiency with less spillover from side lobes.

Patch theory is beyond the scope of this article, but can be summarized as building a shape that resonates at the desired frequency, compensated in size by the capacitive inductance between itself and the reflector. A patch can be practically any shape since it basically acts like a parallel-plate transmission line. Current in the patch flows from the feed point to the outer edge(s), where all the radiation occurs. The reputed, but often disputed, circularity of the truncated corner patch is accomplished by effectively designing two antennas into the patch element (of two different diagonal lengths) and feeding them 90° out of phase.

For K5OE's 1.2-meter dish, shown in **Fig 50**, computations predicted 21-dBi gain on L band and almost 27 dBi on S band, with an assumed 50% efficiency:

$$G = 10\log_{10}\left[\eta A\left(\frac{4\pi}{\lambda^2}\right)\right] \qquad \text{(Eq 8)}$$

where

η = efficiency

λ = wavelength in meters.

A = aperture of the dish in meters = $\pi \times r^2$

r = dish radius in meters = diameter/2 in meters = 0.6 meters

At 1269 MHz, λ= 300/1269 = 0.236 meters:

$$G = 10\log_{10}\left[0.50 \times \left(3.14 \times 0.6^2\right) \times \frac{4 \times 3.14}{0.236^2}\right] = 21.1\,\text{dBi}$$

At 2401.5 MHz, $\lambda = 300/2401.5 = 0.125$ meters:

$$G = 10\log_{10}\left[0.50 \times \left(3.14 \times 0.6^2\right) \times \frac{4 \times 3.14}{0.125^2}\right] = 26.6\,\text{dB}^2$$

Where does the feed get mounted? The *focal point* is where the parabolic shape of the dish concentrates the reflected signal. In K5OE's case the antenna was placed flat on the garage floor to measure the depth:

$f = D^2 / 16d$ (Eq 9)

where

D = diameter of the dish in inches
d = depth of the dish in inches
$f = 48^2 / (16 \times 7.25) = 19.8$ inches (50.5 cm)

This is just one example of countless combinations of hardware and patch designs. Inherent in this design, however, are five key design and construction features developed from building and empirical testing of a number of patch feeds.

1. The specified dimensions are critical for no-tune operation. **Fig 51** shows the dimensions necessary to build the dual-feed patch. (K5OE recommends you reproduce this sketch accurately on graph paper. When you cut your patches you can lay them on the paper template for checking.) Repeat: These dimensions are critical. Even a 0.5-mm error will throw your resonance off considerably—patches are not broadband.
2. The reflector must be rigid. Spacing between the driven element (patch) and the reflector affects the resonant frequency. K5OE found 0.025-inch aluminum sheet and 26-gauge copper sheet acceptable for a single S-band patch feed, but too flimsy for an L-band reflector. Use more rigid material or provide additional stiffening for the L-band reflector, as shown in Figs **52**, **53** and **54**.
3. The patches must be electrically isolated from each other. A metallic center support works for a single patch but creates harmonic-coupling problems when patches are stacked for multiband use. The use of nylon machine screws and nuts helps solve the vexing problem of the S-band patch coupling to the L-band patch.
4. The "straight corners" of the truncated corner patch must be kept clear of any nearby metal. This includes the edges of the feed support or cup, if used. See Fig 54.
5. Feeding the patches at 90° to each other minimizes the electromagnetic interaction between the two antenna fields.

One final design issue deals with the first harmonic of the L-band antenna. You must significantly reduce the potentially destructive effect from the 1269-MHz signal's second harmonic. Severe desense of your receive signal could occur and potentially even overload and damage the first active device in your system. Sensitive preamps and downconverters without a pre-RF-amplifier filter will need an external filter. K5OE has used a G3WDG stub filter rated at 100-dB rejection with good success ahead of his preamp. His current setup, however, uses a AIDC-3731AA downconverter with its internal combline filter providing adequate filtering. Using the downconverter directly at the



Fig 51—Dual-band patch feed dimensions, in millimeters. (*K5OE diagram; courtesy of* The AMSAT Journal.)



Fig 52—Assembly of the L band reflector. (*K5OE photo; courtesy of* The AMSAT Journal.)



Fig 53—The support, L-band reflector and patch. (*K5OE photo; courtesy of* The AMSAT Journal.)



Fig 54—The completed dual-band patch feed. (*K5OE photo; courtesy of* The AMSAT Journal.)

feed point has a noise figure (NF) of 1.0 dB, compared to the cumulative NF of 1.6 dB using a filter and a preamp.

Construction of the feed begins with selection of material for both the electrical parts (the antennas) and the mechanical parts (the support structure). The L-band antenna is constructed using a 6 × 6-inch double-sided circuit board for the reflector and a piece of 26-gauge copper sheet for the driven element (patch). A flanged female type-N connector is used for the feed connection. The S-band antenna is constructed of two pieces of 26-gauge copper sheeting and the feed connection is made with a short piece of UT-141 (0.141-inch copper-clad semirigid coax) terminated in a male SMA fitting. Fig 52 illustrates the assembly of the L-band reflector with the nylon-center support bolt, the L-band N-connector, and the S-band semirigid coax terminated onto an SMA-to-N adapter through the circuit board.

The support structure began life as a paint can, measuring 155 mm in diameter. It was cut down to a 15-mm depth. Cut a hole in the middle of the bottom of the can and trim the PC board to fit inside the can bottom. Use stainless-steel $^{3}/_{8}$-inch 4-40 bolts, washers and nuts to secure the PC board to the can bottom. A $1^{1}/_{2}$-inch 6-32 nylon bolt is secured through the center of the PC board with two nylon nuts to provide the 6-mm spacing for the L-band patch. Fig 53 shows the L-band patch in position and ready to be soldered to the N-connector. Note the hole through the L-band patch allowing the S-band UT-141 coax to pass (without making contact).

The remainder of the antenna is then assembled in order: First the L-band patch is secured with two nylon nuts and soldered to the N-connector. Then the S-band reflector is secured with one nylon nut to provide 3-mm spacing, and the UT-141 coax shield is soldered to the S-band reflector. Finally, the S-band patch is secured with a single nylon nut (3-mm spacing) and soldered to the center conductor of the UT-141 coax. To summarize the overall order of assembly: L-band reflector, two nylon nuts, L-band patch, two nylon nuts, S-band reflector, one nylon nut, S-band patch, and one nylon nut.

An electrical check with an ohmmeter of the completed feed should show the two reflectors connected, with the patches isolated from the reflectors and from each other. Fig 54 shows the completed feed. Note how the sides of the support are cut out to avoid proximity to the L-band patch and how the L-band and S-band patches are at 90° to each other. **Fig 55** shows the back of the feed, complete with an angle support for the downconverter. The flanged N-connector is for the L-band coax and the male-N adapter is secured from the other side of the feed with the SMA fitting on the UT-141 coax.

For those who are tempted to tune the patch, K5OE recommends doing it with the feed installed on the antenna—since the dish surface affects the feed-point impedance slightly. The feed-point impedance, and thus the resonant frequency, can be changed quite a bit by adjustment of the spacing of just the straight corners. There is no need to change the spacing at the center or the feed—just a slight up or down bending of the straight corners will change the tuning. Do this carefully: a little bit goes a long way. This patch design is very repeatable and will work adequately (an SWR below 1.5:1) with no adjustments.

The antenna performs to the calculated predictions above. On receive, this antenna is 4 S units better than K5OE's 45-cm dish and 3 S units above his 65-cm dish (both other dishes have similar patch feeds and the same downconverter). It also clearly outperforms his previous dual-helix arrangement on the 1.2-meter dish, but he was unable to do a side-by-side comparison.

On transmit, it does equally well, with a decent signal into the satellite with only 10 W measured at the



Fig 55—Rear of the completed feed. (K5OE photo; courtesy of *The AMSAT Journal.*)



Fig 56—The portable 435-MHz helix assembled and ready for operation. (*W0CY photo.*)

antenna. The L band is noticeably improved over the helix predecessor. At low squint angles K5OE finds the L-band uplink to be about 1 S unit weaker than his U-band uplink. He later added a small plastic hat to extend over the top of the patches to keep the rain and bird droppings off—both detune the patches when built up between the patch and the reflector.

Though simple and effective, this is merely one way to construct a dual feed. Cookie-tin lids also make excellent supports. Tin snips are a good investment and much easier to use than a hacksaw. Use a flat file to remove burrs from the edges of the patches. Use stainless-steel hardware, most notably $^3/_8$-inch 4-40 machine bolts and nuts for the antenna hardware and $^1/_2$-inch 6-32 for the support-structure connections to the support arms ($^1/_2$-inch aluminum tubing). The copper sheet is much easier to solder to than aluminum. Once completed, the feed received a few coats of white enamel paint to protect the copper and to minimize the visual reflections.

This is not the only dual-band antenna on AO-40. There are many varied, innovative designs available, including G6LVB's simple and effective 1.2-meter homebrew stressed *chicken wire* dish with a dual-G3RUH helix feed. G3WDG has a 3-meter dish with L/S-band helices and a K-band (1.3-cm) feed horn, and W0LMD has developed some popular dual- and tri-band "round" patch feeds. (See the Notes and References, as well as the CD-ROM bundled with this book.)

For additional information on constructing antennas, feeds and equipment techniques for use at microwave frequencies, see *The ARRL UHF/Microwave Experimenter's Manual* and *The ARRL UHF/Microwave Projects Manual*. Both of these books have a wealth of information for the experimenter.

PORTABLE HELIX FOR 435 MHZ

Helical antennas for 435 MHz are excellent uplinks for U-band satellite communications. The true circular polarization afforded by the helix minimizes signal *spin fading* that is so predominant in these applications. The antenna shown in **Fig 56** fills the need for an effective portable uplink antenna for OSCAR operation. Speedy assembly and disassembly and light weight are among the benefits of this array. This antenna was designed by Jim McKim, W0CY.

As mentioned previously, the helix is about the most tolerant of any antenna in terms of dimensions. The dimensions given here should be followed as closely as possible, however. Most of the materials specified are available in any well supplied do-it-yourself hardware or building supply store. The materials required to construct the portable helix are listed in **Table 1**.

The portable helix consists of eight turns of $^1/_4$-inch soft-copper tubing spaced around a 1-inch fiberglass tube or maple dowel rod 4 feet, 7 inches long. Surplus aluminum jacket Hardline can be used instead of the copper tubing if necessary. The turns of the helix are supported by 5-inch lengths of $^1/_4$-inch maple dowel mounted through the 1-inch rod in the center of the antenna. **Fig 57A** shows the overall dimensions of the antenna. Each of these support dowels has a V-shaped notch in the end to locate the tubing, as shown in Fig 57B.

The rod in the center of the antenna terminates at the feed-point end in a 4-foot piece of 1-inch ID galva-

Table 1
Parts List for the Portable 435-MHz Helix

Qty	*Item*
1	Type N female chassis mount connector
18 feet	1/4-in. soft copper tubing
4 feet	1-inch ID galvanized steel pipe
1	5 feet × 1-inch fiberglass tube or maple dowel
14	5-inch pieces of 1/4-inch maple dowel (6 feet total)
1	1/8-inch aluminum plate, 10 inches diameter
3	2 × 3/4-inch steel angle brackets
1	30 × 30-inch (round or square) aluminum screen or hardware cloth
8 feet	1/2 × 1/2 × 1/2-inch aluminum channel stock or old TV antenna element stock
3	Small scraps of Teflon or polystyrene rod (spacers for first half turn of helix)
1	1/8 × 5 × 5-inch aluminum plate (boom-to-mast plate)
4	1½-inch U bolts (boom-to-mast mounting)
3 feet	#22 bare copper wire (helix turns to maple spacers)

Assorted hardware for mounting connector, aluminum plate and screen, etc.

nized steel pipe. The pipe serves as a counterweight for the heavier end of the antenna. The 1-inch rod material inside the helix must be nonconductive. Near the point where the nonconductive rod and the steel pipe are joined, a piece of aluminum screen or hardware cloth is used as a reflector screen.

If you have trouble locating the 1/4-inch soft copper tubing, try a refrigeration supply house. The perforated aluminum screening can be cut easily with tin snips. This material is usually supplied in 30 × 30-inch sheets, making this size convenient for a reflector screen. Galvanized 1/4-inch hardware cloth or copper screen could also be used for the screen, but aluminum is easier to work with and is lighter.

A 1/8-inch-thick aluminum sheet is used as the support plate for the helix and the reflector screen. Surplus rack panels provide a good source of this material. **Fig 58** shows the layout of this plate.

Fig 59 shows how aluminum channel stock is used to support the reflector screen. (Aluminum tubing also works well for this. Discarded TV antennas provide plenty of this material if the channel stock is not available.) The screen is mounted on the bottom of the 10-inch aluminum center plate. The center plate, reflector screen and channel stock are connected together with plated hardware or pop rivets. This support structure is very sturdy. Fiberglass tubing is the best choice for the center rod material although maple dowel can be used.

Mount the type-N connector on the bottom of the center plate with appropriate hardware. The center pin should be exposed enough to allow a flattened end of the copper tubing to be soldered to it. Tin the end of the tubing after it is flattened so that no moisture can enter it. If the helix is to be removable from the ground-plane screen, do not solder the copper tubing to the connector. Instead, prepare a small block of brass, drilled and tapped at one side for a 6-32 screw. Drill another hole in the brass block to accept the center pin of the type-N connector, and solder this connection. Now the connection to the copper tubing helix can be made in the field with a 6-32 screw instead of with a soldering iron.



Fig 57—At A, the layout of the portable 435-MHz helix is shown. Spacing between the first 5-inch winding-support dowel and the ground plane is 1/2 inch; all other dowels are spaced 3 inches apart. At B, the detail of notching the winding-support dowels to accept the tubing is shown. As indicated, drill a 1/16-inch hole below the notch for a piece of small wire to hold the tubing in place.


120°
2" X 3/4" Steel Angle Brackets (3 pls) Bolt Through Back Screen and Back Plate. Use 10-32 Plated Screws, Nuts, and Lock Washers.

Fig 58—The ground plane and feed-point support assembly are shown. The circular piece is a 10-inch diameter, 1/8-inch thick piece of aluminum sheet. (A square plate may be used instead.) Three 2 × 3/4-inch angle brackets are bolted through this plate to the backside of the reflector screen to support the screen on the pipe. The type-N female chassis connector is mounted in the plate 4 inches from the 1-inch diameter center hole.

Refer to Fig 57A. Drill the fiberglass or maple rod at the positions indicated to accept the 5-inch lengths of 1/2-inch dowel. (If maple doweling is used, the wood must be weatherproofed as described below before drilling.) Drill a 1/16-inch hole near the notch of each 5-inch dowel to accept a piece of #22 bare copper wire. (The wire is used to keep the copper tubing in place in the notch.) Sand the ends of the 5-inch dowels so the glue will adhere properly, and epoxy them into the main support rod.

Begin winding the tubing in a clockwise direction from the reflector screen end. First drill a hole in the flattened end of the tubing to fit over the center pin of the type-N connector. Solder it to the connector, or put the screw into the brass block described earlier. Carefully proceed to bend the tubing in a circular winding from one support to the next.

See the earlier section entitled “50-Ω Helix Feed” and Figs 19 and 20 to see how the first half-turn of the helix tubing must be positioned close above the reflector assembly. **Fig 59B** shows also an excellent example by K9EK on matching his U-band helical antenna to a 52-Ω feed line. It is important to maintain this spacing, since extra capacitance between the tubing and ground is required for impedance-matching purposes.

Insert a piece of #22 copper wire in the hole in each support as you go. Twist the wire around the tubing and the support dowel. Solder the wire to the tubing and to itself to keep the tubing in the notches. Continue in this way until all eight turns have been wound. After winding the helix, pinch the far end of the tubing together and solder it closed.



Fig 59—At top, the method of reinforcing the reflector screen with aluminum channel stock is shown. In this version of the antenna, the three angle brackets of Fig 58 have been replaced with a surplus aluminum flange assembly. (*W0CY photo.*) At bottom, this helix view shows the details of a 1/4-turn matching transformer, as discussed in the text. (*K9EK photo.*)

Weatherproofing the Wood

A word about preparing the maple doweling is in order. Wood parts must be protected from the weather to ensure long service life. A good way to protect wood is to boil it in paraffin for about half an hour. Any holes to be drilled in the wooden parts should be drilled after the paraffin is applied, since epoxy does not adhere well to wood after it has been coated with paraffin. The small dowels can be boiled in a saucepan. Caution must be exercised here—the wood can be scorched if the paraffin is too hot. Paraffin is sold for canning purposes at most grocery stores. Wood parts can also be protected with three or four coats of spar varnish. Each coat must be allowed to dry fully before another coat is applied.

The fiberglass tube or wood dowel must fit snugly with the steel pipe. The dowel can be sanded or turned down to the appropriate diameter on a lathe. If fiberglass is used, it can be coupled to the pipe with a piece of wood dowel that fits snugly inside the pipe and the tubing. Epoxy the dowel splice into the pipe for a permanent connection.

Drill two holes through the pipe and dowel and bolt them together. The pipe provides a solid mount to the boom of the rotator, as well as most of the weight needed to counterbalance the antenna. More weight can be added to the pipe if the assembly is "front-heavy." (Cut off some of the pipe if the balance is off in the other direction.)

The helix has a nominal impedance of about 105 Ω in this configuration. By varying the spacing of the first half turn of tubing, a good match to 52-Ω coax should be obtainable. When the spacing has been established for the first half turn to provide a good match, add pieces of polystyrene or Teflon rod stock between the tubing and the reflector assembly to maintain the spacing. These can be held in place on the reflector assembly with silicone sealant. Be sure to seal the type-N connector with the same material.

Exposed Antenna Relays and Preamplifiers

For stations using crossed Yagi antennas for CP operation, one feature that has been quite helpful for communicating through most of the LEO satellites, has been the ability to switch polarization from RHCP to LHCP. In some satellite operation this switchable CP ability has been essential. Operation through AO-40 has not shown a great need for such CP agility, since if the satellite is seriously off-pointed the signals are not particularly useable. When AO-40's squint angle is less than 25° the need for LHCP has not been observed. For those using helical antennas or helical-fed dish antennas, we just would not have the choice to switch CP unless an entirely new antenna is added to the cluster for that purpose. Not many of us have the luxury of that kind of space available on our towers.

For stations with switchable-circularity Yagi antennas, experience with exposed circularity switching relays and preamplifiers mounted on antennas have shown that they are prone to failure caused by an elusive mechanism known as *diurnal pumping*. Often these relays are covered with a plastic case, and the seam between the case and PC board is sealed with a silicone sealant. Preamps may also have a gasket seal for the cover, while the connectors can easily leak air. None of these methods create a true hermetic seal and as a result the day/night temperature swings pump air and moisture in and out of the relay or preamp case. Under the right conditions of temperature and moisture content, moisture from the air will condense inside the case when the outside air cools down. Condensed water builds up inside the case, promoting extensive corrosion and unwanted electrical conduction, seriously degrading component performance in a short time.

A solution for those antennas with "sealed" plastic relays, such as the KLM CX series; you can avoid problems by making the modifications shown in **Fig 60**. Relocate the 4:1 balun as shown and place a clear polystyrene plastic refrigerator container over the relay. Notch the container edges for the driven element and the boom so the container will sit down over the relay, sheltering it from the elements. Bond the container in place with a few dabs of RTV adhesive sealant. Position the antenna in an "X" orientation, so neither set of elements is parallel to the ground. The switcher board should now be canted at an angle, and one side of the relay case should be lower than the other. An example for the protective cover for an S-band preamp can be seen in the discussion on feeds for parabolic antennas.



Fig 60—KLM 2M-22C antenna CP switching relay with relocated balun. The protective cover is needed for rain protection, be sure to use a polystyrene kitchen box, see text. (*WD4FAB photo.*)



Fig 61—A NEMA4 box is used to shelter the L-band electronics and power supply. The box flanges are convenient for mounting preamplifiers. The box is shown inverted since it is on a tilt-over tower. (*WD4FAB photo.*)

For both the relay and preamp cases, carefully drill a 3/32-inch hole through the low side of the case to provide the needed vent. The added cover keeps rainwater off the relay and preamp, and the holes will prevent any buildup of condensation inside the relay case. Relays and preamplifiers so treated have remained clean and operational over periods of years without problems.

Another example for the protection of remotely, tower-mounted equipment is shown in Fig 50, illustrating the equipment box and mast-mounted preamplifiers at the top of WD4FAB's tower. The commercial NEMA4-rated equipment box, detailed in **Fig 61** (shown inverted), is used to protect the 23-cm power amplifier and its power supply, as well as a multitude of electrical connections. This steel box is very weather resistant, with an exceptionally good epoxy finish, but it is not sealed and so it will not trap moisture to be condensed with temperature changes. Be sure to use a box with at least a NEMA3 rating for rainwater and dust protection. The NEMA4 rating is just a little better protection than the NEMA3 rating. Using a well-rated equipment box is very well worth the expense of the box. As you can see, the box also provides some pretty good flanges to mount the mast-mounted preamplifiers for three bands. This box is an elegant solution for the simple need of rain shelter for your equipment. See **Fig 62**.

Elevation Control

Satellite antennas need to have elevation control to point up to the sky. This is the "El" part of Az-El control of satellite antennas. Generally, elevation booms for CP satellite antennas need to be non-conducting so that the boom does not affect the radiation pattern of the antenna. In the example shown next, the elevation boom center section is a piece of extra-heavy-wall $1^1/_2$-inch pipe (for greater strength) coupled with a tubular fiberglass-epoxy boom extension on the 70-cm end and a home-brew long extension on the 2-meter end. This uses large PVC pipe reinforced with four braces of Phillystran non-metallic guy cable. (PVC pipe is notoriously flexible, but the Phillystran cables make a quite stiff and strong boom of the PVC pipe.) For smaller installations, a continuous piece of fiberglass-epoxy boom can be placed directly through the elevation rotator.

Elevation boom motion needs to be powered, and one solution by WD4FAB, shown in **Fig 63**, uses a surplus jackscrew drive mechanism. I8CVS has also built his own robust elevation mechanism. See **Fig 64**. Note in each of these applications the methods used to provide bearings for the elevation mechanism. In WD4FAB's case, the elevation axis is a piece of heavy-duty $1^1/_2$-inch pipe,



Fig 62—Protection for tower-mounted equipment need not be elaborate. Be sure to dress the cables as shown so that water drips off the cable jacket before it reaches the enclosure. One hazard for such open-bottom enclosures is that of animals liking the cable insulation as a delicacy. Flying insects also like to build their houses in these enclosures.



Fig 63—WD4FAB's homebrew elevation rotator drive using a surplus-store drive screw mechanism. Note also the large journal bearing supporting the elevation axis pipe shaft. (*WD4FAB photo.*)

($1^{15}/_{16}$-inch OD) and large 2 inch journal bearings are used for the motion. I8CVS uses a very large hinge to allow his motion.

Robust commercial solutions for Az-El rotators have given operators good service over the years. **See Fig 65**. Manufacturers such as Yaesu and M^2 are among these suppliers. One operator, VE5FP, found a solution for his Az-El needs by using two low-cost, lightweight TV rotators. See Fig 65B.



Fig 64—I8CVS's homebrew elevation mechanism using a very large, industrial hinge as the pivot and a jackscrew drive. (*I8CVS photo.*)

CONVERTED C-BAND TVRO DISHES

In working with larger, converted C-band TVRO dishes for AO-40, some operators have used only the polar mount with its jack-screw mechanism. See **Fig 66**. This dish is called *Big Ugly Dish* or just "BUD" by their users. Only using the polar mount mechanism limits the operator in the range of motion, as previously discussed. WØLMD provides for a greater degree of articulation of these dishes through several mechanisms. One of these is a sector-gear elevation drive, shown in **Fig 67**.

For the azimuth motion of our satellite antennas, most use motorized rotator drives, mainly the commercial sources previously mentioned. Most antennas are tower-mounted, allowing the placement of the rotator inside the tower. For the large wind loads of satellite antennas, these commercial rotators become rather expensive.

High loads are also prominent with the use of BUD



Fig 65—At left, Yaesu Az-El antenna-rotator mounting system is shown. Note that antenna loads must be more carefully balanced on this rotator than in the previously shown systems. At right, VE5FP has a solution for his Az-El rotators by bolting two of them together in his "An Inexpensive Az-El Rotator System", *QST*, December 1998.



Fig 66—A TVRO dish-drive system is shown on its polar mount, using a protected drive-screw mechanism. (*W0LMD photo.*)



Fig 67—A modified TVRO dish mount is shown using an Az-El mount and a sector-gear drive for the elevation. (*W0LMD photo.*)



Fig 68—W0LMD constructed a very robust and low-cost Az drive mechanism. (*W0LMD photo.*)

antennas, and W0LMD has again engineered some very robust mechanisms using combinations of motorcycle-chain drives, V-belt drives and gear-head motors, as seen in **Fig 68**. An overall view of one of his BUD antennas is shown in **Fig 69**, showing the Az drive with an El drive that uses a jackscrew mechanism.

Operators through the years have employed many methods for the control of their antenna positions, ranging from true *arm-strong* manual positioning, to manual operation of the powered antenna azimuth and elevation rotators, to fully automated computer control of the rotators. While computer control of the rotators is not essential, life is greatly assisted with their use. For many years, one of the keystone control units for rotators has been the *Kansas City Tracker* (KCT) board installed in your computer. Most satellite-tracking programs can connect to the KCT with ease. One difficulty with the KCT unit is that they are 8-bit digital units, providing positioning precision of 0.35° in elevation and 1.41° in azimuth. For the larger dishes, with their narrow beamwidths, these values of precision are unacceptable. There are other options to replace the KCT unit.

A recent trend for amateur antenna control has been evolving in the form of a standalone controller that translates computer antenna-position information into controller commands with an understanding of antenna-position limits. These boxes, represented by the *EasyTrak* unit, **Fig 70**, from the Tucson Amateur Packet Radio (TAPR) group, have made this capability readily available for many amateurs. This unit is a 10-bit encoder, providing precisions of 0.09° in elevation and 0.35° in azimuth. The computer can also control the operation of your station transceiver through the radio interface provided in *EasyTrak*; you will not need any other radio interface.

Other position readout and control options are available. For many years ham operators have employed synchros, or *selsyns*, for their position readouts. These are



Fig 69—A completed TVRO dish Az-El mounting system is shown, using a jackscrew elevation drive. (*W0LMD photo.*)



Fig 70—The EasyTrak automated antenna rotator and radio controller by TAPR. (*WD4FAB photo.*)

specialized transformers, using principles developed over sixty years ago and employed in such devices as surplus “radio compass” steering systems for aircraft. While the position readout of these devices can be quite precise, in general they only provide a visual position indication, one that is not easily adapted to computer control. I8CVS employs such a system at his station and his elevation synchro can be seen in Fig 64, using a weighted arm on the synchro to provide a constant reference to the Earth’s gravity vector.

The more up-to-date, computer-friendly position readout methods used these days are usually based on precision potentiometers or digital code wheels. **Fig 71** shows such a digital code-wheel system employed by W0LMD. He notes that such systems, while providing a very high precision of angular position, they are not absolute systems and that once calibrated, they must be continually powered so they do not lose their calibration. Precision potentiometers, on the other hand, provide an absolute position reference, but with a precision that is limited to the quality of the potentiometer, typically 0.5% (0.45° in El and 1.80° in Az) to 1.0%. So the choices have their individual limits, unless a lot of money is spent for very precise commercial systems.



Fig 71—W0LMD has experimented with highly precise optical encoders for his antenna position systems. See text. (*W0LMD photo.*)

NOTES AND REFERENCES, SATELLITE ANTENNAS

AO-40 frequencies, “Official Transponder Frequency Bandplan for P-3D”; **www.amsat-dl.org/p3dqrg.html**.

Brown, Gerald R., K5OE, “A Helix Feed for Surplus MMDS, Antennas” *Proceedings of the 2001AMSAT-NA Symposium*, October 2001, pp 89-94, also: **members.aol.com/k5oe**.

Brown, Jerry, K5OE, “A K-Band Receiver for AO-40”, *Proceedings for the AMSAT-NA Space Symposium, 2002*.

Brown, Gerald R., K5OE, “Build This No-Tune Dual-Band Feed for Mode L/S” *The AMSAT Journal*, Vol 26, No 1, Jan/Feb 2003.

Brown, Gerald R., K5OE, “Dual-Band Dish Feeds for 13/23 cm,” *Proceedings of the 2002AMSAT-NA Symposium*, October 2002, pp 123-131.

Brown, Jerry, K5OE, **members.aol.com/k5oe/** MMDS Dishes.

Brown, Gerald R., K5OE, “Patch Feeds,” **members.aol.com/k5oe**.

Brown, Jerry, K5OE, “The Texas Potato Masher: A Medium-Gain Directional Satellite Antenna For

LEOs," *The AMSAT Journal*, Vol 22, No. 1, Jan/Feb 1999.

Jansson, Dick, WD4FAB, *QST*, Sep 2002, "Product Review", "M^2 23CM22EZA 1.2 GHz Antenna", p 59.

Kingery, Mike, KE4AZN, "Setting Up for AO-40 L-Band Uplink," *The AMSAT Journal*, May/Jun 2002, pp 14-16, also: **web.infoave.net/~mkmk518/**.

Koehler, Jim, VE5FP, "An Inexpensive Az-El Rotator System", *QST*, Dec 1998.

Kraus, John D., "The Helical Antenna", Chapter 7, *Antennas*, McGraw-Hill Book Company, 1988.

Kraus, John D., W8JK, "16-12, Patch or Microstrip Antennas," *Antennas*, 1988, pp 745-749.

Krome, Ed, K9EK, "Development of a Portable Mode S Ground Station." *The AMSAT Journal*, Vol 16, No. 6, Nov/Dec 1993, pp 25-28.

Krome, Ed, K9EK, "S band Reception: Building the DEM Converter and Preamp Kits," *The AMSAT Journal*, Vol 16, No. 2, Mar/Apr 1993, pp 4-6.

Krome, Ed., K9EK, *Mode S—The Book*, p 96, 109.

Krome, Ed, K9EK, "Mode S: Plug and Play!" *The AMSAT Journal*, Vol 14, No. 1, Jan 1991, pp 21-23, 25.

Long, Howard, G6LVB, "My Shack Configuration—Spring 2002": **www.g6lvb.com/g6lvb_shack_spring_2002.htm**.

McCaa, William D., K0RZ, "Hints on Using the AMSAT-OSCAR 13 Mode S Transponder," *The AMSAT Journal*, Vol 13, No. 1, Mar 1990, pp 21-22.

MacAllister, Andy, W5ACM, "Field Day 2002," *73 Amateur Radio Today*, Sept. 2002, pp 48-52.

Miller, James, G3RUH, "Mode S — Tomorrow's Downlink?" *The AMSAT Journal*, Vol 15, No. 4, Sep/Oct 1992, pp 14-15.

Miller, James S., G3RUH, "'Patch' Feed For S-Band Dish Antennas"; **www.jrmiller.demon.co.uk/products/patch.html**.

Miller, James, G3RUH, "A 60-cm S-Band Dish Antenna," *The AMSAT Journal*, Vol 16 No. 2, Mar/Apr 1993, pp 7-9.

Miller, James, G3RUH, "Small is Best," *The AMSAT Journal*, Vol 16, No. 4, Jul/Aug 1993, p 12.

Monteiro, Anthony, "Work OSCAR 40 with Cardboard-box Antennas!," *QST*, Mar 2003, pp 57-62.

Orban Microwave, "The Basics of Patch Antennas: **www.orbanmicrowave.com/antenna_application_notes.htm**.

Seguin, Mike, N1JEZ, "OSCAR 40 on 24GHz", *QST*, Dec 2002, pp 55-56.

Seydler, Robert, K5GNA,"Modifications of the AIDC 3731 Downconverters", **members.aol.com/k5gna/AIDC3731modifications.doc**.

Suckling, Charles, G3WDG, "K-Band Results From AO-40": **www.g3wdg.free-online.co.uk/kband.htm**.

Suckling, Charles, G3WDG "Notch Filters for AO-40 Mode L/S": **www.g3wdg.free-online.co.uk.notch.htm**.

Suding, Dr. Robert, W0LMD, "Converting TVRO Dish & Dishes For Amateurs" **www.ultimatecharger.com/dish.html**.

Thiel, David & Smith, Staphani, *Switched Parasitic Antennas for Cellular Communications*, Artech House, 2002, "Chapter 3, Patch Antennas," pp 79-96.

Wade, Paul, N1BWT (W1GHZ), *Online Microwave Antenna Handbook*, "Chapter 4, Parabolic Dish Antennas," **www.w1ghz.cx/antbook/chap4.pdf**, Mar. 98. (See CD-ROM bundled with this book.)

Zibrat,Timothy S, K3TZ, "2.4 GHz Patch Design": **www.qsl.net/k3tz/**.

Antenna Systems for EME Communications

This section was updated by David Hallidy, K2DH. As mentioned earlier, the tremendous path loss incurred over an EME circuit places stringent requirements on Earth-station performance. Low-noise receiving equipment, maximum available power and high-gain antenna arrays are required for successful EME operation. Although it is possible to copy some of the better-equipped stations with a low-gain antenna, it is unlikely that such an antenna can provide reliable two-way communications. Antenna gain of at least 20 dBi is required for reasonable EME success. Generally speaking, more antenna gain yields the most noticeable improvement in station performance, since the increased gain improves both the received and transmitted signals.

VHF/UHF EME ANTENNAS

Several types of antennas for 2 meters and 70 cm are popular among EME enthusiasts. Perhaps the most popular antenna for 144-MHz work is an array of either 4 or 8 long-boom (14 to 15 dBi gain) Yagis. The 4-Yagi array provides approximately 20 dB gain, and an 8-Yagi array gives an approximate 3 dB increase over the 4-antenna array. **Fig 72** shows the computed response at a 30° tilt above the horizon for a stack of four 14-element 2-meter Yagis, each with a boomlength of 3.1 λ (22 feet).

At 432 MHz, EME enthusiasts often use 8 or 16 long-boom Yagis in an array. Such Yagis are commercially available or they can be constructed from readily available materials. Chapter 18, VHF and UHF Antenna Systems, has details on some popular Yagi designs.

The main disadvantage of Yagi arrays is that the polarization plane of the individual Yagis cannot be conveniently changed. One way around this is to use cross-polarized Yagis and a relay switching system to select the desired polarization, as described in the previous section. This represents a considerable increase in system complexity to select the desired polarization. Some amateurs have gone so far as to build complicated mechanical systems to allow constant polarization adjustment of all the Yagis in a large array. **Fig 73** shows the K1FO 70-cm EME 16-Yagi array with full polarization control, described in *The ARRL Antenna Compendium*, *Vol 3*. This 432-MHz EME array uses open-wire phasing lines to minimize feed-line losses. **Fig 74** shows the computed response for this array, which employs rugged but lightweight 14-element Yagis on 3.1 λ (7.1 foot) booms. Feed-line losses are not explicitly accounted for in the *EZNEC Professional* computer model, but are estimated to be less than 0.25 dB.

Polarization shift of EME signals at 144 MHz is fairly rapid, and the added complexity of a relay-controlled cross-polarized antenna system or a mechanical polarization adjustment scheme is probably not worth the effort. At 432 MHz, however, where the polarization shifts at a much slower rate, an adjustable polarization system does offer a definite advantage over a fixed one.

The Yagi antenna system used by Ed Stallman, N5BLZ, is shown in **Fig 75**. His system employs twelve 144-MHz long-boom 17-element Yagi antennas. The monster 48-Yagi 2-meter array of Gerald Williamson, K5GW, is shown in **Fig 76**, and the huge 48-Yagi 70-cm EME array of Frank Potts, NC1I, is shown in **Fig 77**.

Although not as popular as Yagis, Quagi antennas (made from both quad and Yagi elements) are sometimes used for EME work. Slightly more gain per unit boom length is possible as compared to the conventional Yagi, at the expense of some robustness. Additional information on the Quagi is presented in Chapter 18, VHF and UHF Antenna Systems.

The collinear array is an older type of antenna for EME work. A 40-element collinear array has approximately



Fig 73—K1FO's variable polarization 16 × 14-element (3.6-λ boom lengths) 432-MHz EME array shown at 2° elevation and vertical polarization. (See *The ARRL Antenna Compendium, Vol 3*.)



Fig 72—*EZNEC Pro* elevation pattern for four 14-element 2-meter Yagis (3.6-λ boom lengths) at an elevation angle of 30° above the horizon. The computed system gain is 21.5 dBi, suitable for 2-meter EME. This assumes that the phasing system is made of open-wire transmission lines so that feed-line losses can be kept below 0.25 dB.



Fig 74—Computed elevation response for K1FO 16-Yagi 432-MHz array shown in Fig 73. (The *EZNEC Pro* model required 2464 segments!) With assumed phasing harness feed-line losses of 0.25 dB, the overall gain exceeds 27.5 dBi.

the same frontal area as an array of four Yagis, but produces approximately 1 to 2 dB less gain. One attraction to a collinear array is that the depth dimension is considerably less than the long-boom Yagis. An 80-element collinear is marginal for EME communications, providing approximately 19 dB gain. As with Yagi and Quagi antennas, the collinear cannot be adjusted easily for polarity changes. From a construction standpoint, there is little difference in complexity and material costs between the collinear and Yagi arrays.

DISH ANTENNAS FOR EME

On 2 meters the minimum antenna gain for reliable EME communications is about 20 dBi. While a few amateurs have had access to parabolic dishes large enough for EME work at 144 and 222 MHz, at those frequencies an array of four long Yagis is equal in gain to a dish 24 feet in diameter! To achieve truly high-gain performance from a dish on 2 meters would require a reflector diameter of nearly 96 feet (providing 32 dBi gain). Such undertakings are generally beyond amateur means, so there has been little work done with dishes at low frequencies, except for the occasional expedition to one of the large radio telescopes that have accommodated amateur EME work.



Fig 75—The EME array used at N5BLZ consists of twelve long-boom 144-MHz Yagis. The tractor, lower left, really puts this array into perspective! (*Photo courtesy N5BLZ.*)



Fig 76—K5GW's huge 48-Yagi 2-meter EME array. (*Photo courtesy K5GW.*)

Microwave Parabolic Dish Antennas

The major problems associated with parabolic dish antennas are mechanical ones. A dish of about 16 feet in diameter is the minimum size required for successful EME operation on 432 MHz. With wind and ice loading, structures of this size place a real strain on the mounting and positioning system. Extremely rugged mounts are required for large dish antennas, especially when used in windy locations. **Fig 78** shows the impressive 7-meter diameter



Fig 77—NC1I's magnificent 48-Yagi 70-cm EME array. (*Photo courtesy NC1I.*)

dish built by David Wardley, ZL1BJQ.

Several aspects of parabolic dish antennas make the extra mechanical problems worth the trouble, however. For example, the dish antenna is inherently broadband, and may be used on several different amateur bands by simply changing the feed. An antenna that is suitable for 432 MHz work will most likely be usable on several of the higher amateur bands too. Increased gain is available as the frequency of operation is increased.

Another advantage of a dish is the flexibility of the feed system. The polarization of the feed, and therefore the polarization of the antenna, can be changed with little difficulty. It is a relatively easy matter to devise a system to rotate the feed remotely from the shack to change polarization. Because polarization changes can account for as much as 30 dB of signal attenuation, the rotatable feed can make the difference between consistent communications and no communications at all. Further information on Parabolic Antennas can be found in Chapter 18, VHF and UHF Antenna Systems as well as in the section below.

A 12-FOOT STRESSED HOMEBREW PARABOLIC DISH

Very few antennas evoke as much interest among UHF amateurs as the parabolic dish, and for good reason. First, the parabola and its cousins—Cassegrain, hog horn and Gregorian—are probably the ultimate in high-gain antennas. One of the highest-gain antennas in the world (148 dB) is a parabola. This is the 200-inch Mt. Palomar telescope. (The very short wavelength of light rays causes such a high gain to be realizable.)

Second, the efficiency of the parabola does not change as size increases. With Yagis and collinear arrays, the losses in the phasing harness increase as the array size increases. The corresponding component of the parabola is lossless air between the feed horn and the reflecting surface. If there are a few surface errors, the efficiency of the system stays constant regardless of antenna size. This project was presented by Richard Knadle, K2RIW, in August 1972 *QST*.



Fig 78—ZL1BJQ's homemade 7-meter (23-foot) parabolic dish, just prior to adding 1/2-inch wire mesh. (*Photo courtesy ZL1BJQ*.)

Some amateurs reject parabolic antennas because of the belief that they are all heavy, hard-to-construct, have large wind-loading surfaces and require precise surface accuracy. However, with modern construction techniques, a prudent choice of materials and an understanding of accuracy requirements, these disadvantages can be largely overcome. A parabola may be constructed with a 0.6 f/D (focal length/diameter) ratio, producing a rather flat dish, which makes it easy to surface and allows the use of recent advances in high-efficiency feed horns. This results in greater gain for a given dish size over conventional designs.

Such an antenna is shown in **Fig 79**. This parabolic dish is lightweight, portable, easy to build, and can be used for 432 and 1296-MHz mountain topping, as well as on 2304, 3456 and 5760 MHz. Disassembled, it fits into the trunk of a car, and can be assembled in 45 minutes.

The usually heavy structure that supports the surface of most parabolic dish antennas has been replaced in this design by aluminum spokes bent into a near parabolic shape by string. These strings serve the triple function of guying the focal point, bending the spokes and reducing the error at the dish perimeter (as well as at the center) to nearly zero. By contrast, in conventional designs, the dish perimeter (which has a greater surface area than the center) is farthest from the supporting center hub. For these reasons, it often has the greatest error. This error becomes more severe when the wind blows.

Here, each of the spokes is basically a cantilevered beam with end loading. The equations of beam bending



Fig 79—A 12-foot stressed parabolic dish set up for satellite signals near 2280 MHz. A preamplifier is shown taped below the feed horn. The dish was designed by K2RIW, standing at the right. From *QST*, August 1972.

predict a near-perfect parabolic curve for extremely small deflections. Unfortunately the deflections in this dish are not that small and the loading is not perpendicular. For these reasons, mathematical prediction of the resultant curve is quite difficult. A much better solution is to measure the surface error with a template and make the necessary correction by bending each of the spokes to fit. This procedure is discussed later.

The uncorrected surface is accurate enough for 432 and 1296-MHz use. Trophies taken by this parabola in antenna-gain contests were won using a completely natural surface with no error correction. By placing the transmission line inside the central pipe that supports the feed horn, the area of the shadows or blockages on the reflector surface is much smaller than in other feeding and supporting systems, thus increasing gain. For 1296 MHz, a backfire feed horn may be constructed to take full advantage of this feature. At 432 MHz, a dipole and reflector assembly produces 1.5 dB additional gain over a corner-reflector feed system. Because the preamplifier is located right at the horn on 2300 MHz, a conventional feed horn may be used.

Construction

Table 2 is a list of materials required for construction. Care must be exercised when drilling holes in the connecting center plates so assembly problems will not be experienced later. See **Fig 80**. A notch in each plate allows them to be assembled in the same relative positions. The two plates should be clamped together and drilled at the same time. Each of the $18^1/_2$-inch diameter aluminum spokes has two no. 28 holes drilled at the base to accept no. 6-32 machine screws that go through the center plates. The 6-foot long spokes are cut from standard 12-foot lengths of tubing. A fixture built from a block of aluminum assures that the holes are drilled in exactly the same position in each spoke. The front and back center plates constitute an I-beam type of structure that gives the dish center considerable rigidity.



Fig 80—Center plate details. Two center plates are bolted together to hold the spokes in place.

A side view of the complete antenna is shown in **Fig 81**. Aluminum alloy (6061-T6) is used for the spokes, while 2024-T3 aluminum alloy sheet, $^1/_8$ inch thick, is used for the center plates. (Aluminum has approximately three times the strength-to-weight ratio of wood, and aluminum cannot warp or become water logged.) The end of each of the 18 spokes has an eyebolt facing the dish focal point, which serves a dual purpose:

1) To accept the #9 galvanized fence wire that is routed through the screw eyes to define the dish perimeter, and
2) To facilitate rapid assembly by accepting the S hooks which are tied to the end of each of the lengths of 130-pound test Dacron fishing string.

The string bends the spokes into a parabolic curve; the dish may be adapted for many focal lengths by tightening or slackening the strings. Dacron was chosen because it has the same chemical formula as Mylar. This is a low-stretch material that keeps the dish from changing shape. The galvanized perimeter wire has a 5-inch overlap area that is bound together with baling wire after the spokes have been hooked to the strings.

The aluminum window screening is bent over the perimeter wire to hold it in place on the back of the spokes. Originally, there was concern that the surface perturbations (the spokes) in front of the screening might decrease the gain. The total spoke area is so small, however, that

Table 2
Materials List for the 12-Foot Stressed Parabolic Dish

1) Aluminum tubing, 12 ft × $^1/_2$ in. OD × 0.049-in. wall, 6061-T6 alloy, 9 required to make 18 spokes.
2) Octagonal mounting plates 12 × 12 × $^1/_8$ in., 2024-T3 alloy, 2 required.
3) $1^1/_4$ in. ID pipe flange with setscrews.
4) $1^1/_4$ in. × 8 ft TV mast tubing, 2 required.
5) Aluminum window screening, 4 × 50 ft.
6) 130-pound test Dacron trolling line.
7) 38 ft #9 galvanized fence wire (perimeter).
8) Two hose clamps, $1^1/_2$ in.; two U bolts; $^1/_2$ × 14 in. Bakelite rod or dowel; water-pipe grounding clamp; 18 eye bolts; 18 S hooks.


7′ 6-1/4″
12′ 3″
U Bolts
1/2″ X 14″ Bakelite Rod Support
Hose Clamp Over Rubber Sheet to Prevent Slippage
1296 MHz Dual Mode Feed Horn
6′
6′ 6″
7′ 2″
Transmission Line
130 Pound Test Dacron Trolling Line
S Hook
Screw Eye

Fig 81—Side view of the stressed parabolic dish.

this fear proved unfounded.

Placing the aluminum screening in front of the spokes requires the use of 200 pieces of baling wire to hold the screening in place. This would increase the assembly time by at least an hour. For contest and mountaintop operation (when the screening is on the back of the spokes) no fastening technique is required other than bending the screen to overlap the wire perimeter.

The Parabolic Surface

A 4-foot wide roll of aluminum screening 50 feet long is cut into appropriate lengths and laid parallel, with a 3-inch overlap between the top of the unbent spokes and hub assembly. The overlap seams are sewn together on one half of the dish using heavy Dacron thread and a sailmaker's curved needle. Every seam is sewn twice; once on each edge of the overlapped area. The seams on the other half are left open to accommodate the increased overlap that occurs when the spokes are bent into a parabola. The perimeter of the screening is then trimmed. Notches are cut in the 3-inch overlap to accept the screw eyes and S hooks.

The first time the dish is assembled, the screening strips are anchored to the inside surface of the dish and the seams sewn in this position. It is easier to fabricate the surface by placing the screen on the back of the dish frame with the structure inverted. The spokes are sufficiently strong to support the complete weight of the dish when the perimeter is resting on the ground.

The 4-foot wide strips of aluminum screening conform to the compound bend of the parabolic shape very easily. If the seams are placed parallel to the E-field polarization of the feed horn, minimum feedthrough will occur. This feedthrough, even if the seams are placed perpendicular to the E field, is so small that it is negligible. Some constructors may be tempted to cut the screening into pie-shaped sections. This procedure will increase the seam area and construction time considerably. The dish surface appears most pleasing from the front when the screening perimeter is slipped between the spokes and the perimeter wire, and is then folded back over the perimeter wire. In disassembly, the screening is removed in one piece, folded in half, and rolled.

The Horn and Support Structure

The feed horn is supported by $1^{1}/_{4}$-inch aluminum television mast. The Hardline that is inserted into this tubing is connected first to the front of the feed horn, which then slides back into the tubing for support. A setscrew assures that no further movement of the feed horn occurs. During antenna-gain competition the setscrew is omit-



Fig 82—Backfire type 1296-MHz feed horn, linear polarization only. The small can is a Quaker State oil container; the large can is a 50-pound shortening container (obtained from a restaurant, Gold Crisp brand). Brass tubing, $^{1}/_{2}$-inch OD extends from UG-23 connector to dipole. Center conductor and dielectric are obtained from $^{3}/_{8}$-inch Alumafoam coaxial cable. The dipole is made from 3/32-inch copper rod. The septum and 30° section are made from galvanized sheet metal. Styrofoam is used to hold the septum in position. The primary gain is 12.2 dBi.

ted, allowing the $^{1}/_{2}$-inch semirigid CATV transmission line to move in or out while adjusting the focal length for maximum gain. The TV mast is held firmly at the center plates by two setscrews in the pipe flange that is mounted on the rear plate. At 2300 MHz, the dish is focused for best gain by loosening these setscrews on the pipe flange and sliding the dish along the TV mast tubing. (The dish is moved instead of the feed horn.)

The fishing strings are held in place by attaching them to a hose clamp that is permanently connected to the TV tubing. A piece of rubber sheet under the hose clamp prevents slippage and keeps the hose clamp from cutting the fishing string. A second hose clamp is mounted below the first as extra protection against slippage.

The high-efficiency 1296-MHz dual mode feed horn, detailed in **Fig 82**, weighs 5$^{3}/_{4}$ pounds. This weight causes some bending of the mast tubing, but this is corrected by a $^{1}/_{2}$-inch diameter bakelite support, as shown in Fig 81. This support is mounted to a pipe grounding clamp with a no. 8-32 screw inserted in the end of the rod. The bakelite rod and grounding clamp are mounted midway between the hose clamp and the center plates on the mast. A double run of fishing string slipped over the notched upper end of the bakelite rod counteracts bending.

The success of high-efficiency parabolic antennas is primarily determined by feed horn effectiveness. The multiple diameter of this feed horn may seem unusual. This patented dual-mode feed, designed by Dick Turrin, W2IMU, achieves efficiency by launching two different kinds of waveguide modes simultaneously. This causes the dish illumination to be more constant than conventional designs.

Illumination drops off rapidly at the perimeter, reducing spillover. The feed backlobes are reduced by at least 35 dB because the current at the feed perimeter is almost zero; the phase center of the feed system stays constant across the angles of the dish reflector. The larger diameter section is a phase corrector and should not be changed in length. In theory, almost no increase in dish efficiency can be achieved without increasing the feed size in a way that would increase complexity, as well as blockage.

The feed is optimized for a 0.6 f/D dish. The dimensions of the feeds are slightly modified from the original design in order to accommodate the cans. Either feed type can be constructed for other frequencies by changing the scale of all dimensions.

Multiband Use

Many amateurs construct multiband antenna arrays by putting two dishes back to back on the same tower. This is cost inefficient. The parabolic reflector is a completely frequency independent surface, and studies have shown that a 0.6 f/D surface can be steered seven beamwidths by moving the feed horn from side to side before the gain diminishes by 1 dB. Therefore, the best dual-band antenna can be built by mounting separate horns side by side. At worst, the antenna may have to be moved a few degrees (usually less than a beamwidth) when switching between horns, and the unused horn increases the shadow area only slightly. In fact, the same surface can function simultaneously on multiple frequencies, making crossband duplex operation possible with the same dish.

Order of Assembly

1) A single spoke is held upright behind the rear center plate with the screw eye facing forward. Two no. 6-

32 machine screws are pushed through the holes in the rear center plate, through the two holes of the spoke, and into the corresponding holes of the front center plate. Lock washers and nuts are placed on the machine screws and hand tightened.

2) The remaining spokes are placed between the machine screw holes. Make sure that each screw eye faces forward. Machine screws, lock washers and nuts are used to mount all 18 spokes.
3) The no. 6-32 nuts are tightened using a nut driver.
4) The mast tubing is attached to the spoke assembly, positioned properly, and locked down with the setscrews on the pipe flange at the rear center plate. The S hooks of the 18 Dacron strings are attached to the screw eyes of the spokes.
5) The ends of two pieces of fishing string (which go over the bakelite rod support) are tied to a screw eye at the forward center plate.
6) The dish is laid on the ground in an upright position and #9 galvanized wire is threaded through the eyebolts. The overlapping ends are lashed together with baling wire.
7) The dish is placed on the ground in an inverted position with the focus downward. The screening is placed on the back of the dish and the screening perimeter is fastened as previously described.
8) The extension mast tubing (with counterweight) is connected to the center plate with U bolts.
9) The dish is mounted on a support and the transmission line is routed through the tubing and attached to the horn.

Parabola Gain Versus Errors

How accurate must a parabolic surface be? This is a frequently asked question. According to the Rayleigh limit for telescopes, little gain increase is realized by making the mirror accuracy greater than $\pm\,^{1}/_{8}\,\lambda$ peak error. John Ruze of the MIT Lincoln Laboratory, among others, has derived an equation for parabolic antennas and built models to verify it. The tests show that the tolerance loss can be predicted within a fraction of a decibel, and less than 1 dB of gain is sacrificed with a surface error of $\pm^{1}/_{8}\,\lambda$. (A $^{1}/_{8}\,\lambda$ is 3.4 inches at 432 MHz, 1.1 inches at 1296 MHz and 0.64 inch at 2300 MHz.)

Some confusion about requirements of greater than $^{1}/_{8}$-λ accuracy may be the result of technical literature describing highly accurate surfaces. Low sidelobe levels are the primary interest in such designs. Forward gain is a much greater concern than low sidelobe levels in amateur work; therefore, these stringent requirements do not apply.

When a template is held up against a surface, positive and negative (±) peak errors can be measured. The graphs of dish accuracy requirements are frequently plotted in terms of RMS error, which is a mathematically derived function much smaller than ± peak error (typically $^{1}/_{3}$). These small RMS accuracy requirements have discouraged many constructors who confuse them with ± peak errors.

Fig 83 may be used to predict the resultant gain of various dish sizes with typical errors. There are a couple of surprises, as shown in **Fig 84**. As the frequency is increased for a given dish, the gain increases 6 dB per octave until the tolerance errors become significant. Gain deterioration then increases rapidly. Maximum gain is realized at the frequency where the tolerance loss is 4.3 dB. Notice that at 2304 MHz, a 24-foot dish with ±2-inch peak errors has the same gain as a 6-foot dish with ±1-inch peak errors. This is quite startling, when it is realized that a 24-foot dish has 16 times the area of a 6-foot dish. Each time the diameter or frequency is doubled or halved, the gain changes by 6 dB. Each time all the errors are halved, the frequency of maximum gain is doubled. With this information, the gain of other dish sizes with other tolerances can be predicted.

These curves are adequate for predicting gain, assuming a high-efficiency feed horn is used (as described earlier), which realizes 60% aperture efficiency. At frequencies below 1296 MHz where the horn is large and causes considerable blockage, the curves are somewhat optimistic. A properly built dipole and splasher feed will have about 1.5 dB less gain when used with a 0.6 f/D dish than the dual-mode feed system described.

The worst kind of surface distortion is where the surface curve in the radial direction is not parabolic but gradually departs in a smooth manner from a perfect parabola. The decrease in gain can be severe, because a large area is involved. If the surface is checked with a template, and if reasonable construction techniques are employed, deviations are controlled and the curves represent an upper limit to the gain that can be realized.

If a 24-foot dish with ±2-inch peak errors is being used with 432 and 1296-MHz multiple feed horns, the constructor might be discouraged from trying a 2300-MHz feed because there is 15 dB of gain degradation. The dish will still have 29 dBi of gain on 2300 MHz, however, making it worthy of consideration.

The near-field range of this 12-foot stressed dish (actually 12 feet 3 inches) is 703 feet at 2300 MHz. By using the sun as a noise source and observing receiver noise power, it was found that the antenna had two main lobes about 4° apart. The template showed a surface error (insufficient spoke bending at $^{3}/_{4}$ radius), and a correction was made. A recheck showed one main lobe, and the solar noise was almost 3 dB stronger.

Other Surfacing Materials

The choice of surface materials is a compromise between RF reflecting properties and wind loading. Aluminum screening, with its very fine mesh (and weight of 4.3 pounds per 100 square feet) is useful beyond 10 GHz because of its very close spacing. This screening is easy to roll up and is therefore ideal for a portable dish. This close spacing causes the screen to be a 34% filled aperture, bring-



Fig 83—Gain deterioration versus reflector error. By Richard Knadle, K2RIW.

ing the wind force at 60 mph to more than 400 *pounds* on this 12-foot dish. Those considering a permanent installation of this dish should investigate other surfacing materials.

Hexagonal 1-inch poultry netting (chicken wire), which is an 8% filled aperture, is nearly ideal for 432-MHz operation. It weighs 10 pounds per 100 square feet, and exhibits only 81 pounds of force with 60 mph winds. Measurement on a large piece reveals 6 dB of feedthrough at 1296 MHz, however. Therefore, on 1296 MHz, one fourth of the power will feed through the surface material. This will cause a loss of only 1.3 dB of forward gain. Since the low-wind loading material will provide a 30-dBi gain potential, it is still a very good tradeoff.

Poultry netting is very poor material for 2300 MHz and above, because the hole dimensions approach $^1/_2$ λ. As with all surfacing materials, minimum feedthrough occurs when the E-field polarization is parallel to the longest dimension of the surfacing holes.

Hardware cloth with $^1/_2$-inch mesh weighs 20 pounds per 100 square feet and has a wind loading characteristic of 162 pounds with 60 mph winds. The filled aperture is 16%, and this material is useful to 2300 MHz.

A rather interesting material worthy of investigation is $^1/_4$-inch reinforced plastic. It weighs only 4 pounds per 100 square feet. The plastic melts with many universal solvents such as lacquer thinner. If a careful plastic-melting job is done, what remains is the $^1/_4$-inch spaced aluminum wires with a small blob of plastic at each junction to hold the matrix together.

There are some general considerations to be made in selecting surface materials:

1) Joints of screening do not have to make electrical contact. The horizontal wires reflect the horizontal wave. Skew polarizations are merely a combination of horizontal and vertical components which are thus reflected by the corresponding wires of the screening. To a horizontally polarized wave, the spacing and diameter of only the horizontal wires determine the reflection coefficient (see **Fig 85**). Many amateurs have the mistaken impression that screening materials that do not make electrical contact at their junctions are poor reflectors.
2) By measuring wire diameter and spacings between the wires, a calculation of percentage of aperture that is filled can be made. This will be one of the major determining factors of wind pressure when the surfacing material is dry.



Fig 84—Parabolic-antenna gain versus size, frequency and surface errors. All curves assume 60% aperture efficiency and 10-dB power taper. Graph by K2RIW for ham bands, using display technique of J. Ruze, British IEE.



Fig 85—Surfacing material quality.

A Parabolic Template

At and above 2300 MHz (where high surface accuracy is required), a parabolic template should be constructed to measure surface errors. A simple template may be constructed (see **Fig 86**) by taking a 12-foot 3-inch length of 4-foot wide tar paper and drawing a parabolic shape on it with chalk. The points for the parabolic shape are calculated at 6-inch intervals and these points are connected with a smooth curve. For those who wish to use the template with the surface material installed, the template should be cut along the chalk line and stiffened by cardboard or a wood lattice frame. Surface error measurements should take place with all spokes installed and deflected by the fishing lines, as some bending of the center plates does take place. **Fig 87** shows the 12-foot stressed dish built by Franco Marcelo, N2UO.

Variations

All the possibilities of the stressed parabolic antenna have not been explored. For instance, a set of fishing lines or guy wires can be set up behind the dish for error correction, as long as this does not cause permanent bending of the aluminum spokes. This technique also protects the dish against wind loading from the rear. An extended piece of TV mast is an ideal place to hang a counterweight and attach the rear guys. This strengthens the structure considerably.

EME USING SURPLUS TVRO DISH ANTENNAS

Since the 1990s, there has been a significant change



(to Nearest 1/16″)

X	Z	X	Z
0.5′	1/8″	3.5′	5-1/8″
1.0′	7/16″	4.0′	6-11/16″
1.5′	15/16″	4.5′	8-1/2″
2.0′	1-11/16″	5.0′	10-7/16″
2.5′	2-5/8″	5.5′	12-11/16″
3.0′	3-3/4″	6.0′	15-1/16″

Fig 86—Parabolic template for 12-foot, 3-inch dish.



Fig 87—N2UO's homemade 12-foot stressed dish. (*Photo courtesy N2UO.*)

in the systems people use to watch satellite TV broadcasts. Formerly, C-band satellite receivers were used, along with parabolic dish antennas in the 3- to 5-meter diameter range. Now, Ku-band (12-GHz) receivers are the norm, with their associated small (usually 18-inch) dish antennas. This has provided a large body of surplus C-band dishes, which can be used for EME—certainly on the bands at 33 cm and above, and for the larger dishes (5 meters), even at 70 cm. Many times, these dishes and their mounts can be had for the asking, so they truly become an inexpensive way to build a multi-band EME antenna.

This updated article, first presented by David Hallidy, K2DH (ex-KD5RO) in the ARRL *UHF/Microwave Projects Manual*, describes the use of a 3-meter (10-foot) TVRO antenna in such an application. (Also see earlier in this chapter the section describing converted C-Band TVRO Dishes for satellite work.)

Background

Calculations show that a 3-meter dish will have about 30 dBi gain at 1296 MHz. With a state-of-the-art LNA (Low-Noise Amplifier or preamp) at the feed, an efficient feed horn illuminating the dish surface, and 200 W at 1296 MHz, lunar echoes should be easily detected and many stations can be worked. The biggest challenges to such a system are assembling the dish to its mount and steering it to track the Moon. As much as possible, the KISS ("Keep It Simple, Stupid") principle was used to accomplish this task.

In 1987, WA5TNY, KD5RO, KA5JPD, and W7CNK proved that such an EME system could work, even as high as 3.4 and 5.7 GHz, to provide the first EME contacts on those bands. An additional advantage to this (or any) small dish is its ability to be mounted to a trailer and taken out on EME expeditions. It can also be easily disassembled and stored, if necessary.

As can be seen from **Fig 88**, the entire setup is very simple, using a standard amateur tower as the main support for the dish.

Azimuth Drive

In azimuth, direct drive of the main rotating shaft was selected, and a small prop-pitch motor was used. These motors, while not as plentiful as they were some years ago, still turn up with some regularity at flea markets for very little money. The beauty of the prop-pitch motor is that it turns slowly, is reversible, provides very high torque, and requires no braking system (the gear reduction, on the order of 4000:1, provides the necessary braking). Prop-pitch motors are dc motors, and were designed to vary the pitch of propeller blades at start-up, take-off and landing of older large airplanes. Thus, they can be run at different speeds merely by varying the dc voltage to the motor, and can be reversed by reversing the polarity of the dc voltage. By mounting a thrust bearing of the appropriate size at the top of the tower, and mounting the motor directly below it at the end of the rotating shaft that turns the antenna, a simple direct-drive system can be constructed.

The dc power supply and control relays are located in a weatherproof box on the side of the tower, next to the motor. This system requires only 9 V dc at about 5 A to adequately start, turn and stop the prop-pitch motor, and this voltage turns the antenna through 360° of rotation in about $2^1/_2$ minutes. Azimuth position sensing is also a simple task. See **Fig 89**. A linear multi-turn potentiometer is driven by the rotating shaft, using a simple friction drive.

A strip of rubber is attached to the rotating shaft and a wheel is connected to the shaft of the pot. The pot is then mounted so that it presses against the rubber strip, and as the shaft turns so does the pot. If a ten-turn pot is used, and the system is aligned such that the pot is at the center of its rotation when the antenna is pointed approximately south, the pot will not rotate past the end at either extreme of the antenna's rotation (CW/CCW north), and absolute alignment is a simple task of calibrating the change in resistance (change in voltage, when the pot is fed from a constant voltage source) with degrees of rotation (see the discussion on Position Readout for details).

Elevation Drive

The elevation drive is also very simple. Most (nearly all) TVRO setups have a means of moving the dish across the sky to align it with various satellites. To do this, most companies use a device called a *Linear Actuator*. This is a dc motor to which is attached a long lead screw that pulls (or pushes) the outer shell of the actuator in or out to make it longer or shorter. The movable end of the actuator is attached to the dish and the motor end is fixed to the mount. The dish rests on pivots, which allow it to move as the actuator extends/retracts. To convert this type of mount (called a *Polar Mount*) to an Az/El mount is usually very simple.

Fig 90 shows how this can be done. Simply breaking the welds that held the mount in a polar fashion allows the mount to be turned on its side and used to pivot the dish vertically with the linear actuator. Another feature of linear actuators is that they also have some means of feeding their relative position to the satellite receiver. This is usually just a multi-turn potentiometer geared to the lead screw. All we have to do is connect this pot to a readout system, and we can calibrate the lift of the actuator in degrees. We thus have a simple means of rotating the dish and elevating it—but how do we know that it's pointed at the Moon?

Position Readout

Readout of the position of the antenna, in both azimuth and elevation is also a relatively simple task. On the



Fig 88—View of K2DH's (ex-KD5RO) complete TVRO antenna installation. (*K2DH photo.*)



Fig 89—Azimuth rotation systems, showing prop-pitch motor and position sensor.



Fig 90—Elevation system, showing modified TVRO mount.

surplus market there are available Digital Volt Meters (DVMs) using LED or LCD displays that can do this job nicely, and that have more precision than is probably necessary for a dish (or Yagi array) of small size. As mentioned earlier, a multi-turn potentiometer on the elevation-drive mechanism can be used to readout elevation, and the same technique can be used for azimuth readout—a potentiometer coupled to the main rotating shaft that turns the antenna.

When using a pot for readout, the most important thing to know is how many degrees of antenna position change occur (in Az or El) for each turn of the pot. This then can be used to calibrate a voltmeter to read volts directly as degrees—for example, 3.60 V could correspond to 360° azimuth (Clockwise North), and 9.0 V could correspond


115 V ac
IN
2 A
MOTOR ON
115 V
115
V ac
24 V ac
6 A
Prop–pitch
Motor
MOT
Counter–
clockwise
Clockwise
CW
CCW
115 V
115
V ac
24 V ac
2 A
0.001
0.001 µF
1000 µF
0.001 µF
UP
OFF
OFF
DOWN
Elevation
Motor
MOT
7805
+12 V dc
Reg
IN
OUT
GND
0.1 µF
0.1 µF
ZERO
ADJ.
F.S.
ADJ.
Azimuth
Sensor
10 k
10 turn
10 k
50 K
Elevation
Sensor
10 k
10 turn
ZERO
ADJ.
F.S.
ADJ.
10 k
50 K
AZ
EL
0.001
µF
+5 V
DATEL
DM–LX3
Gnd
0.001 µF

Fig 91—Schematic diagram of the dish control system. The Datel DM-LX3 is a digital meter, used to indicate azimuth and elevation angles.

to 90° elevation (straight up).

A resistance bridge circuit is best used in this application, since it is less sensitive to changes in the supply voltage. The only thing to be careful about is that the DVM must have both the positive (high) and negative (low) inputs isolated from ground (assuming the power supply used to power the DVM is grounded). You could also use a pair of small, cheap Digital Multi-Meters (DMMs), which can sometimes be found for under $10. Because they are battery powered, the isolation issue just discussed is eliminated.

Please see **Fig 91** for a complete schematic of the azimuth, elevation and readout electronics for this antenna-drive system. Also note that while this discussion is geared towards the use of a small dish, the same positioning and readout systems could be used in a Yagi array for 2 meters or 70 cm.

Now that we know where the dish is pointed, how do we know where the Moon is? There are several software programs available to the Amateur for tracking celestial bodies such as the Moon, the Sun, certain stars (usable as noise sources), and even Amateur Satellites. Programs by W9IP, VK3UM, F1EHN and others can be obtained very reasonably and these work well to provide highly accurate position information for tracking.

Feeding the Surplus TVRO Dish

An area that needs particular attention when attempting EME with a small dish is an efficient feed system. An efficient feed system can be a real challenge with TVRO dishes, because many are "deep"—that is, their f/D (focal length to Diameter ratio) is small.

The satellite TV industry used deep dishes because they tend to be quieter, picking up less Earth noise due to spillover effects. A deep dish has a short focal length, and therefore, the feed is relatively close to the surface of the dish. To properly illuminate the reflector out to its edges, a feed horn of relatively wide beamwidth must be used. The feeds designed several years ago by Barry Malowanchuk, VE4MA, are intended for use with just such dishes, and have the advantage of being adjustable to optimize their pattern to the dish in use.

The feed that was used with this dish was modeled after VE4MA's 1296-MHz feed, and a version was even scaled for use at 2304 MHz that worked as well as the original. See **Fig 92** and also see the Notes and References section at the end of this chapter. (Also see the earlier section in the satellite portion of this chapter describing patch feeds for small dishes.)



Fig 92—View of feed, showing coffee-can feed horn and hybrid coupler.

SHF EME CHALLENGES

The challenges met when successfully building a station for EME at 900 MHz to 5.7 GHz only become more significant on the SHF bands at 10 GHz and above. Absolute attention to detail is the primary requirement, and this extends to every aspect of the EME antenna system. The dish surface is probably the most difficult problem to solve. As was discussed earlier in this chapter, the shape and accuracy of the reflector contribute directly to the overall gain of the antenna.

But where slight errors in construction can be tolerated at the lower frequencies, the same cannot be said at millimetric wavelengths. Those who have attempted EME on 10 and 24 GHz have discovered that the weight of the dish reflector itself will distort its shape enough to lower the gain to the point where echoes are degraded. Stiffening structures at the back of such dishes are often found necessary. **Fig 93** illustrates the back struts added by Al Ward, W5LUA, to strengthen his dish.

Pointing accuracy is also paramount—a 16-foot dish at 10 GHz has a beamwidth about equal to the diameter of the Moon—0.5°. This means that the echo degradation due to the Moon's movement away from where the dish is pointed is almost immediate, and autotracking systems become more of a necessity than a luxury. At these frequencies, most amateurs actually peak their antennas on



Fig 93—Strengthening struts W5LUA added to the back of his dish to hold down distortion. (*Photo courtesy W5LUA.*)

Moon Noise—the black-body Radiation from the Moon that becomes the dominant source of noise in space.

At these frequencies, the elevation of the Moon above the horizon also plays a role in the ability to communicate, since tropospheric absorption due to water vapor is greatest at low elevation angles (the signal must pass through a greater portion of the troposphere than when the Moon is highly elevated). It is beyond the abilities of most Amateurs to construct their own dishes for these frequencies, so surplus dishes for Ku-band satellite TV (typically 3 meters in diameter) are usually employed, as have high-performance dishes designed for millimetric radar and point-to-point communications at 23 and 38 GHz.

NOTES AND REFERENCES, EME ANTENNAS

W. Allen, "A Mode J Helix," *AMSAT Newsletter*, Jun 1979, pp 30-31.

D. J. Angelakos and D. Kajfez, "Modifications on the Axial-Mode Helical Antenna," *Proc. IEEE*, Apr 1967, pp 558-559.

A. L. Bridges, "Really Zap OSCAR With this Helical Antenna," *73*, in three parts, Jul, Aug and Sep 1975.

K. R. Carver, "The Helicone—A Circularly Polarized Antenna with Low Sidelobe Level," *Proc. IEEE*, Apr 1967, p 559.

M. R. Davidoff, "A Simple 146-MHz Antenna for Oscar Ground Stations," *QST*, Sep 1974, pp 11-13.

M. R. Davidoff, *The Radio Amateur's Satellite Handbook* (Newington: ARRL, 1998-2000).

D. DeMaw, "The Basic Helical Beam," *QST*, Nov 1965, pp 20-25, 170.

D. Evans and G. Jessop, *VHF-UHF Manual, 3rd ed.* (London: RSGB), 1976.

N. Foot, "WA9HUV 12-Foot Dish for 432 and 1296 MHz," The World Above 50 Mc., *QST*, Jun 1971, pp 98-101, 107.

N. Foot, "Cylindrical Feed horn for Parabolic Reflectors," *Ham Radio*, May 1976.

O. J. Glasser and J. D. Kraus, "Measured Impedances of Helical Beam Antennas," *Journal of Applied Physics*, Feb 1948, pp 193-197.

D. Hallidy, "Microwave EME Using A Ten-Foot TVRO Antenna," *The ARRL UHF/Microwave Projects Manual*, 1994 pp 10-9 to 10-13.

G. R. Isely and W. G. Smith, "A Helical Antenna for Space Shuttle Communications," *QST*, Dec 1984, pp 14-18.

H. Jasik, *Antenna Engineering Handbook*, 1st ed. (New York: McGraw-Hill, 1961).

R. T. Knadle, "A Twelve-Foot Stressed Parabolic Dish," *QST*, Aug 1972, pp 16-22.

J. D. Kraus, "Helical Beam Antenna," *Electronics*, Apr 1947, pp 109-111.

J. D. Kraus and J. C. Williamson, "Characteristics of Helical Antennas Radiating in the Axial Mode," *Journal of Applied Physics*, Jan 1948, pp 87-96.

J. D. Kraus, "Helical Beam Antenna for Wide Band Applications," *Proc of the IRE*, Oct 1948, pp 1236-1242.

J. D. Kraus, *Antennas* (New York: McGraw-Hill Book Co., 1950).

J. D. Kraus, "A 50-Ohm Input Impedance for Helical Beam Antenna," *IEEE Transactions on Antennas and Propagation*, Nov 1977, p 913.

J. D. Kraus, *Big Ear* (Powell, OH: Cygnus-Quasar Books, 1976).

T. S. M. MacLean, "Measurements on High-Gain Helical Aerial and on Helicals of Triangular Section," *Proc. of IEE* (London), Jul 1964, pp 1267-1270.

D. M. Mallozzi, "The Tailored Helical," *AMSAT Newsletter*, Mar 1978, pp 8-9.

B. Malowanchuk, "Use of Small TVRO Dishes for EME," *Proceedings of the 21st Conference of The Central States VHF Society*, 1987 pp 68-77.

B. Malowanchuk, "Selection of An Optimum Dish Feed," *Proceedings of the 23rd Conference of The Central States VHF Society*, 1989 pp 35-43.

M. W. Maxwell, *Reflections—Transmission Lines and Antennas* (Newington, CT: ARRL, 1990) [out of print].

T. Moreno, *Microwave Transmission Design Data* (New York: McGraw-Hill, 1948).

K. Nose, "Crossed Yagi Antennas for Circular Polarization," *QST*, Jan 1973, pp 11-12.

K. Nose, "A Simple Az-El Antenna System for Oscar," *QST*, Jun 1973, pp 11-12.

S. Powlishen, K1FO, "432-MHz EME 1990s Style," Parts 1 and 2, *Communications Quarterly*, Oct 1990, pp 29-39; Oct 1991, pp 33-48.

S. Powlishen, K1FO, "Rear-Mount Yagi Arrays for 432-MHz EME: Solving the EME Polarization Problem," *The ARRL Antenna Compendium, Vol 3* (Newington:

ARRL, 1992), pp 79-98.

C. Richards, "The 10 Turn Chopstick Helical (Mk2) for OSCAR 10 432 MHz Uplink," *Radio Communication*, Oct 1984, pp 844-845.

S. Sander and D. K. Cheng, "Phase Center of Helical Beam Antennas," *IRE National Convention Record Part 6*, 1958, pp 152-157.

E. A. Scott and H. E. Banta, "Using the Helical Antenna at 1215 Mc.," *QST*, Jul 1962, pp 14-16.

R. Soifer, W2RS, "More 'QRP' EME on 144 MHz," *QST*, Oct 1990, pp 36-38.

G. Southworth, *Principles and Applications of Waveguide Transmission* (New York: D. Van Nostrand Co., 1950).

B. Sykes, "Circular Polarization and Crossed-Yagi Antennas," Technical Topics, *Radio Communication*, Feb 1985, p 114.

H. E. Taylor and D. Fowler, "A V-H-F Helical Beam Antenna," *CQ*, Apr 1949, pp 13-16.

G. Tillitson, "The Polarization Diplexer—A Polaplexer," *Ham Radio*, Mar 1977.

P. P. Viezbicke, "Yagi Antenna Design," *NBS Technical Note 688* (U. S. Dept. of Commerce/National Bureau of Standards, Boulder, CO), Dec 1976.

D. Vilardi, "Easily Constructed Antennas for 1296 MHz," *QST*, Jun 1969.

D. Vilardi, "Simple and Efficient Feed for Parabolic Antennas," *QST*, Mar 1973.

J. L. Wong and H. E. King, "Broadband Quasi-Tapered Helical Antenna," *IEEE Transactions on Antennas and Propagation*, Jan 1979, pp 72-78.

Chapter 20

Antenna Materials and Accessories

This chapter contains information on materials amateurs use to construct antennas—what types of material to look for in a particular application, tips on working with and using various materials. Chapter 21 contains information on where to purchase these materials.

Basically, antennas for MF, HF, VHF and the lower UHF range consist simply of one or more conductors that radiate (or receive) electromagnetic waves. However, an antenna system must also include some means to support those conductors and maintain their relative positions—the boom for a Yagi antenna and the halyards for a wire dipole, for example. In this chapter we'll look at materials for those applications, too. Structural supports such as towers, masts, poles, etc. are discussed in Chapter 22.

There are two main types of material used for antenna conductors, wire and tubing. Wire antennas are generally simple and therefore easier to construct, although some arrays of wire elements can become rather complex. When tubing is required, aluminum tubing is used most often because of its light weight. Aluminum tubing is discussed in a subsequent section of this chapter.

Wire Antennas

Although wire antennas are relatively simple, they can constitute a potential hazard unless properly constructed. Antennas should never be run under or over public utility (telephone or power) lines. Several amateurs have lost their lives by failing to observe this precaution.

The National Electric Code® of the National Fire Protection Association contains a section on amateur stations in which a number of recommendations are made concerning minimum size of antenna wire and the manner of bringing the transmission line into the station. Chapter 1 contains more information about this code. The code in itself does not have the force of law, but it is frequently made a part of local building regulations, which are enforceable. The provisions of the code may also be written into, or referred to, in fire and liability insurance documents.

The RF resistance of copper wire increases as the size of the wire decreases. However, in most types of antennas that are commonly constructed of wire (even quite small wire), the radiation resistance will be much higher than the RF resistance, and the efficiency of the antenna will still be adequate. Wire sizes as small as #30, or even smaller, have been used quite successfully in the construction of "invisible" antennas in areas where more conventional antennas cannot be erected. In most cases, the selection of wire for an antenna will be based primarily on the physical properties of the wire, since the suspension of wire from elevated supports places a strain on the wire.

WIRE TYPES

Wire having an enamel coating is preferable to bare wire, since the coating resists oxidation and corrosion. Several types of wire having this type of coating are available, depending on the strength needed. "Soft-drawn" or annealed copper wire is easiest to handle; unfortunately, it stretches considerably under stress. Soft-drawn wire should be avoided, except for applications where the wire will be under little or no tension, or where some change in length can be tolerated. (For example, the length of a horizontal antenna fed at the center with open-wire line is not critical, although a change in length may require some readjustment of coupling to the transmitter.)

"Hard-drawn" copper wire or copper-clad steel wire (also known as Copperweld™) is harder to handle, because it has a tendency to spiral when it is unrolled. These types of wire are ideal for applications where significant stretch cannot be tolerated. Care should be exercised in using this wire to make sure that kinks do not develop—the wire will have a far greater tendency to break at a kink. After the coil has been unwound, suspend the wire a few feet above ground for a day or two before using it. The wire should not be recoiled before it is installed.

Several factors influence the choice of wire type and size. Most important to consider are the length of the unsupported span, the amount of sag that can be tolerated, the stability of the supports under wind pressure, and whether or not an unsupported transmission line is to be suspended from the span. **Table 1** shows the wire diam, current-carrying capacity and resistance of various sizes of copper wire. **Table 2** shows the maximum rated working tensions of hard-drawn and copper-clad steel wire of various sizes. These two tables can be used to select the appropriate wire size for an antenna.

Table 1
Copper-Wire Table

Wire Size AWG (B&S)	*Dia in Mils*[1]	*Dia in mm*	*Turns per Linear Inch Enamel*	*Feet per Pound Bare*	*Ohms per 1000 ft 25°C*	*Cont.-duty current*[2] *Single Wire in Open Air*
1	289.3	7.348	—	3.947	0.1264	—
2	257.6	6.544	—	4.977	0.1593	—
3	229.4	5.827	—	6.276	0.2009	—
4	204.3	5.189	—	7.914	0.2533	—
5	181.9	4.621	—	9.980	0.3195	—
6	162.0	4.115	—	12.58	0.4028	—
7	144.3	3.665	—	15.87	0.5080	—
8	128.5	3.264	7.6	20.01	0.6405	73
9	114.4	2.906	8.6	25.23	0.8077	—
10	101.9	2.588	9.6	31.82	1.018	55
11	90.7	2.305	10.7	40.12	1.284	—
12	80.8	2.053	12.0	50.59	1.619	41
13	72.0	1.828	13.5	63.80	2.042	—
14	64.1	1.628	15.0	80.44	2.575	32
15	57.1	1.450	16.8	101.4	3.247	—
16	50.8	1.291	18.9	127.9	4.094	22
17	45.3	1.150	21.2	161.3	5.163	—
18	40.3	1.024	23.6	203.4	6.510	16
19	35.9	0.912	26.4	256.5	8.210	—
20	32.0	0.812	29.4	323.4	10.35	11
21	28.5	0.723	33.1	407.8	13.05	—
22	25.3	0.644	37.0	514.2	16.46	—
23	22.6	0.573	41.3	648.4	20.76	—
24	20.1	0.511	46.3	817.7	26.17	—
25	17.9	0.455	51.7	1031	33.00	—
26	15.9	0.405	58.0	1300	41.62	—
27	14.2	0.361	64.9	1639	52.48	—
28	12.6	0.321	72.7	2067	66.17	—
29	11.3	0.286	81.6	2607	83.44	—
30	10.0	0.255	90.5	3287	105.2	—
31	8.9	0.227	101	4145	132.7	—
32	8.0	0.202	113	5227	167.3	—
33	7.1	0.180	127	6591	211.0	—
34	6.3	0.160	143	8310	266.0	—
35	5.6	0.143	158	10480	335	—
36	5.0	0.127	175	13210	423	—
37	4.5	0.113	198	16660	533	—
38	4.0	0.101	224	21010	673	—
39	3.5	0.090	248	26500	848	—
40	3.1	0.080	282	33410	1070	—

[1] A mil is 0.001 inch.

[2] Max wire temp of 212° F and max ambient temp of 135° F.

Table 2
Stressed Antenna Wire

American Wire Gauge	***Recommended Tension[1] (pounds)***		***Weight (pounds per 1000 feet)***	
	Copper-clad steel[2]	*Hard-drawn copper*	*Copper-clad steel[2]*	*Hard-drawn copper*
4	495	214	115.8	126.0
6	310	130	72.9	79.5
8	195	84	45.5	50.0
10	120	52	28.8	31.4
12	75	32	18.1	19.8
14	50	20	11.4	12.4
16	31	13	7.1	7.8
18	19	8	4.5	4.9
20	12	5	2.8	3.1

[1] Approximately one-tenth the breaking load. Might be increased 50% if end supports are firm and there is no danger of ice loading.

[2] Copperweld,™ 40% copper.

Wire Tension

If the tension on a wire can be adjusted to a known value, the expected sag of the wire (**Fig 1**) may be determined before installation using Table 2 and the nomograph of **Fig 2**. Even though there may be no convenient method to determine the tension in pounds, calculation of the expected sag for practicable working tensions is often desirable. If the calculated sag is greater than allowable it may be reduced by any one or a combination of the following:

1) Providing additional supports, thereby decreasing the span
2) Increasing the tension in the wire if less than recommended
3) Decreasing the size of the wire

Instructions for Using the Nomograph

1) From Table 2, find the weight (pounds/1000 feet) for the particular wire size and material to be used.
2) Draw a line from the value obtained above, plotted on the weight axis, to the desired span (feet) on the span axis, Fig 2. Note in Fig 1 that the span is one half the distance between the supports.
3) Choose an operating tension level (in pounds) consistent with the values presented in Table 2 (preferably less than the recommended wire tension).
4) Draw a line from the tension value chosen (plotted on the tension axis) through the point where the work axis crosses the original line constructed in step 2, and continue this new line to the sag axis.
5) Read the sag in feet on the sag axis.

Example:

Weight = 11 pounds/1000 feet
Span = 210 feet
Tension = 50 pounds
Answer: Sag = 4.7 feet

These calculations do not take into account the weight of a feed line supported by the antenna wire.



Fig 1—The half span and sag of a long-wire antenna.

Wire Splicing

Wire antennas should preferably be made with unbroken lengths of wire. In instances where this is not feasible, wire sections should be spliced as shown in **Fig 3**. The enamel insulation should be removed for a distance of about 6 inches from the end of each section by scraping with a knife or rubbing with sandpaper until the copper underneath is bright. The turns of wire should be brought up tight around the standing part of the wire by twisting with broad-nose pliers.

The crevices formed by the wire should be completely filled with rosin-core solder. An ordinary soldering iron or gun may not provide sufficient heat to melt solder outdoors; a propane torch is desirable. The joint should be heated sufficiently so the solder flows freely into the joint when the source of heat is removed momentarily. After the joint has cooled completely, it should be wiped clean with a cloth, and then sprayed generously with acrylic to prevent corrosion.



Fig 2—Nomograph for determining wire sag. (John Elengo, Jr, K1AFR)



Fig 3—Correct method of splicing antenna wire. Solder should be flowed into the wraps after the connection is completed. After cooling, the joint should be sprayed with acrylic to prevent oxidation and corrosion.

ANTENNA INSULATION

To prevent loss of RF power, the antenna should be well insulated from ground, unless of course it is a shunt-fed system. This is particularly important at the outer end or ends of wire antennas, since these points are always at a comparatively high RF potential. If an antenna is to be installed indoors (in an attic, for instance) the antenna may be suspended directly from the wood rafters without additional insulation, if the wood is permanently dry. Much greater care should be given to the selection of proper insulators when the antenna is located outside where it is exposed to wet weather.

Insulator Leakage

Antenna insulators should be made of material that will not absorb moisture. The best insulators for antenna use are made of glass or glazed porcelain. Depending on the type of material, plastic insulators may be suitable. The length of an insulator relative to its surface area is indicative of its comparative insulating ability. A long thin insulator will have less leakage than a short thick insulator. Some antenna insulators are deeply ribbed to increase the surface leakage path without increasing the physical length of the insulator. Shorter insulators can be used at low-potential points, such as at the center of a dipole. If such an antenna is to be fed with open-wire line and used on several bands, however, the center insulator should be the same as those used at the ends, because high RF potential may exist across the center insulator on some bands.

Insulator Stress

As with the antenna wire, the insulator must have sufficient physical strength to support the stress of the antenna without danger of breakage. Long elastic bands or lengths of nylon fishing line provide long leakage paths and make satisfactory insulators within their limits to resist mechanical strain. They are often used in antennas of the “invisible” type mentioned earlier.

For low-power work with short antennas not subject to appreciable stress, almost any small glass or glazed-porcelain insulator will do. Homemade insulators of Lucite rod or sheet will also be satisfactory. More care is required in the selection of insulators for longer spans and higher transmitter power.

For a given material, the breaking tension of an insulator will be proportional to its cross-sectional area. It should be remembered, however, that the wire hole at the end of the insulator decreases the effective cross-sectional area. For this reason, insulators designed to carry heavy strains are fitted with heavy metal end caps, the eyes being formed in the metal cap, rather than in the insulating material itself. The following stress ratings of antenna insulators are typical:

$^5/_8$ in. square by 4 in. long—400 lb
1 in. diameter by 7 or 12 in. long—800 lb
$1^1/_2$ in. diameter by 8, 12 or 20 in. long, with special metal end caps—5000 lb

These are rated breaking tensions. The actual working tensions should be limited to not more than 25% of the breaking rating.

The antenna wire should be attached to the insulators as shown in **Fig 4**. Care should be taken to avoid sharp angular bends in the wire when it is looped through the insulator eye. The loop should be generous enough in size that it will not bind the end of the insulator tightly. If the length of the antenna is critical, the length should be measured to the outward end of the loop, where it passes through the eye of the insulator. The soldering should be done as described earlier for the wire splice.

Strain Insulators

Strain insulators have their holes at right angles, since they are designed to be connected as shown in **Fig 5**. It can be seen that this arrangement places the insulating material under compression, rather than tension. An insulator connected this way can withstand much greater stress. Furthermore, the wire will not collapse if the insulator breaks, since the two wire loops are inter-locked. Because the wire is wrapped around the insulator, however, the leakage path is reduced drastically, and the capacitance between the wire loops provides an additional leakage path. For this reason, the use of the strain insulator is usually confined to such applications as breaking up resonances in guy wires, where high levels of stress prevail, and where the RF insulation is of less importance. Such insulators might be suitable for use at low-potential points on an antenna, such as at the center of a dipole. These insulators may also be fastened in the conventional manner if the wire will not be under sufficient tension to break out the eyes.

Insulators for Ribbon-Line Antennas

Fig 6A shows the sketch of an insulator designed to be used at the ends of a folded dipole or a multiple dipole made of ribbon line. It should be made approximately as shown, out of Lucite or bakelite material about $^1/_4$ inch thick. The advantage of this arrangement is that the strain of the antenna is shared by the conductors and the plastic webbing of the ribbon, which adds considerable strength. After soldering, the screw should be sprayed with acrylic.

Fig 6B shows a similar arrangement for suspending one dipole from another in a stagger-tuned dipole system. If better insulation is desired, these insulators can be wired to a conventional insulator.

PULLEYS AND HALYARDS

Pulleys and halyards commonly used to raise and lower a wire antenna must also be capable of taking the



Fig 4—When fastening antenna wire to an insulator, do not make the wire loop too snug. After the connection is complete, flow solder into the turns. Then when the joint has cooled completely, spray it with acrylic.



Fig 5—Conventional manner of fastening wire to a strain insulator. This method decreases the leakage path and increases capacitance, as discussed in the text.



Fig 6—At A, an insulator for the ends of folded dipoles, or multiple dipoles made of 300-ohm ribbon. At B, a method of suspending one ribbon dipole from another in a multiband dipole system.

same strain as the antenna wire and insulators. Unfortunately, little specific information on the stress ratings of most pulleys is available. Several types of pulleys are readily available at almost any hardware store. Among these are small galvanized pulleys designed for awnings and several styles and sizes of clothesline pulleys. Heavier and stronger pulleys are those used in marine work. The factors that determine how much stress a pulley will handle include the diameter of the shaft, how securely the shaft is fitted into the sheath and the size and material of the frame.

Another important factor to be considered in the selection of a pulley is its ability to resist corrosion. Galvanized awning pulleys are probably the most susceptible to corrosion. While the frame or sheath usually stands up well, these pulleys usually fail at the shaft. The shaft rusts out, allowing the grooved wheel to break away under tension.

Most good-quality clothesline pulleys are made of alloys which do not corrode readily. Since they are designed to carry at least 50 feet of line loaded with wet clothing in stiff winds, they should be adequate for normal spans of 100 to 150 feet between stable supports. One type of clothesline pulley has a 4-inch diameter plastic wheel with a ¼-inch shaft running in bronze bearings. The sheath is made of cast or forged corrosion-proof alloy. Some look-alike low-cost pulleys of this type have an aluminum shaft with no bearings. For antenna work, these cheap pulleys are of little long-term value.

Table 3
Approximate Safe Working Tension for Various Halyard Materials

Material	*Dia, In.*	*Tension, Lb*
Manila hemp rope	1/4	120
	3/8	270
	1/2	530
	5/8	800
Polypropylene rope	1/4	270
	3/8	530
	1/2	840
Nylon rope	1/4	300
	3/8	660
	1/2	1140
7×11 galvanized sash cord	1/16	30
	1/8	125
	3/16	250
	1/4	450
High-strength stranded galvanized steel guy wire	1/8	400
	3/16	700
	1/4	1200
Rayon-filled plastic clothesline	7/32	60 to 70

Marine pulleys have good weather-resisting qualities, since they are usually made of bronze, but they are comparatively expensive and are not designed to carry heavy loads. For extremely long spans, the wood-sheathed pulleys used in "block and tackle" devices and for sail hoisting should work well.

Halyards

Table 3 shows the recommended maximum tensions for various sizes and types of line and rope suitable for hoisting halyards. Probably the best type for general amateur use for spans up to 150 or 200 feet is ¼-inch nylon rope. Nylon is somewhat more expensive than ordinary rope of the same size, but it weathers much better. Nylon also has a certain amount of elasticity to accommodate gusts of wind, and is particularly recommended for antennas using trees as supports. A disadvantage of new nylon rope is that it stretches by a significant percentage. After an installation with new rope, it will be necessary to repeatedly take up the slack created by stretching. This process will continue over a period of several weeks, at which time most of the stretching will have taken place. Even a year after installation, however, some slack may still arise from stretching.

Most types of synthetic rope are slippery, and some types of knots ordinarily used for rope will not hold well. **Fig 7** shows a knot that should hold well, even in nylon rope or plastic line.

For exceptionally long spans, stranded galvanized steel sash cord makes a suitable support. Cable advertised as "wire rope" usually does not weather well. A boat winch, sold at marinas and at Sears, is a great convenience in antenna hoisting (and usually a necessity with metal halyards).



Fig 7—This is one type of knot that will hold with smooth rope, such as nylon. Shown at A, the knot for splicing two ends. B shows the use of a similar knot in forming a loop, as might be needed for attaching an insulator to a halyard. Knot A is first formed loosely 10 or 12 in. from the end of the rope; then the end is passed through the eye of the insulator and knot A. Knot B is then formed and both knots pulled tight. (Richard Carruthers, K7HDB)

Antennas of Aluminum Tubing

Aluminum is a malleable, ductile metal with a mass density of 2.70 grams per cubic centimeter. The density of aluminum is approximately 35% that of iron and 30% that of copper. Aluminum can be polished to a high brightness, and it will retain this polish in dry air. In the presence of moisture, aluminum forms an oxide coating (Al_2O_3) that protects the metal from further corrosion. Direct contact with certain metals, however (especially ferrous metals such as iron or steel), in an outdoor environment can bring about galvanic corrosion of aluminum and its alloys. Some protective coating should be applied to any point of contact between two dissimilar metals. Much of this information about aluminum and aluminum tubing was prepared by Ralph Shaw, K5CAV.

Aluminum is non-toxic; it is used in cooking utensils and to hold and cover "TV dinners" and other frozen foods, so it is certainly safe to work with. The ease with which it can be drilled or sawed makes it a pleasure to work with. Aluminum products lend themselves to many and varied applications.

Aluminum alloys can be used to build amateur antennas, as well as for towers and supports. Light weight and high conductivity make aluminum ideal for these applications. Alloying lowers the conductivity ratings, but the tensile strength can be increased by alloying aluminum with one or more metals such as manganese, silicon, copper, magnesium or zinc. Cold rolling can be employed to further increase the strength.

A four-digit system is used to identify aluminum alloys, such as 6061. Aluminum alloys starting with a 6 contain di-magnesium silicide (Mg_2Si). The second digit indicates modifications of the original alloy or impurity limits. The last two digits designate different aluminum alloys within the category indicated by the first digit.

In the 6000 series, the 6061 and 6063 alloys are a commonly used for antenna applications. Both types have good resistance to corrosion and medium strength. A further designation like T-6 denotes thermal treatment (heat tempering). More information on the available aluminum alloys can be found in **Table 4**.

SELECTING ALUMINUM TUBING

Table 5 shows the standard sizes of aluminum tubing that are stocked by most aluminum suppliers or distributors in the United States and Canada. Note that all tubing comes in 12-foot lengths (local hardware stores sometimes stock 6- and 8-foot lengths) and larger-diameter sizes may be available in lengths up to 24 feet. Note also that any diameter tubing will fit snugly into the next larger size, if the larger size has a 0.058-inch wall thickness. For example, $^5/_8$-inch tubing has an outside diameter of 0.625 inch. This will fit into $^3/_4$-inch tubing with a 0.058-inch wall, which has an inside diameter of 0.634 inch. A clearance of 0.009 inch is just right for a slip fit or for slotting the tubing and then using hose clamps. Always get the next larger size and specify a 0.058-inch wall to obtain the 0.009-inch clearance.

Table 4
Aluminum Numbers for Amateur Use

	Common Alloy Numbers
Type	*Characteristic*
2024	Good formability, high strength
5052	Excellent surface finish, excellent corrosion resistance, normally not heat treatable for high strength
6061	Good machinability, good weldability
6063	Good machinability, good weldability
7075	Good formability, high strength
	Common Tempers
Type	*Characteristics*
T0	Special soft condition
T3	Hard
T6	Hardest, possibly brittle
TXXX	Three digit tempers—usually specialized high strength heat treatments, similar to T6
	General Uses
Type	*Uses*
2024-T3	Chassis boxes, antennas, anything that will be bent or
7075-T3	Flexed repeatedly
6061-T6	Tubing and pipe; angle channel and bar stock
6063-T832	Tubing and pipe; angle channel and bar stock

A little figuring with Table 5 will give you all the information you need to build a beam, including what the antenna will weigh. The 6061-T6 type of aluminum has a relatively high strength and has good workability. It is highly resistant to corrosion and will bend without taking a "set."

SOURCES FOR ALUMINUM

Aluminum can be purchased new, and suppliers are listed in Chapter 21. But don't overlook the local metal scrap yard. The price varies, but between 35 and 60 cents per pound is typical for scrap aluminum. Some aluminum items to look for include aluminum vaulting poles, tent poles, tubing and fittings from scrapped citizen's band antennas, and aluminum angle stock. The scrap yard may even have a section or two of triangular aluminum tower.

Aluminum vaulting poles are 12 or 14 feet long and range in diameter from $1^1/_2$ to $1^3/_4$ inches. These poles are suitable for the center-element sections of large 14-MHz beams or as booms for smaller antennas. Tent poles range in length from 2½ to 4 feet. The tent poles are

Table 5
Aluminum Tubing Sizes
6061-T6 (61S-T6) Round Aluminum Tube In 12-Foot Lengths

	Wall Thickness			Approximate Weight	
Tubing Diameter	*Inches*	*Stubs Ga.*	*ID, Inches*	*Pounds Per Foot*	*Pounds Per Length*
$^{3}/_{16}$ in.	0.035	(#20)	0.117	0.019	0.228
	0.049	(#18)	0.089	0.025	0.330
$^{1}/_{4}$ in.	0.035	(#20)	0.180	0.027	0.324
	0.049	(#18)	0.152	0.036	0.432
	0.058	(#17)	0.134	0.041	0.492
$^{5}/_{16}$ in.	0.035	(#20)	0.242	0.036	0.432
	0.049	(#18)	0.214	0.047	0.564
	0.058	(#17)	0.196	0.055	0.660
$^{3}/_{8}$ in.	0.035	(#20)	0.305	0.043	0.516
	0.049	(#18)	0.277	0.060	0.720
	0.058	(#17)	0.259	0.068	0.816
	0.065	(#16)	0.245	0.074	0.888
$^{7}/_{16}$ in.	0.035	(#20)	0.367	0.051	0.612
	0.049	(#18)	0.339	0.070	0.840
	0.065	(#16)	0.307	0.089	1.068
$^{1}/_{2}$ in.	0.028	(#22)	0.444	0.049	0.588
	0.035	(#20)	0.430	0.059	0.708
	0.049	(#18)	0.402	0.082	0.984
	0.058	(#17)	0.384	0.095	1.040
	0.065	(#16)	0.370	0.107	1.284
$^{5}/_{8}$ in.	0.028	(#22)	0.569	0.061	0.732
	0.035	(#20)	0.555	0.075	0.900
	0.049	(#18)	0.527	0.106	1.272
	0.058	(#17)	0.509	0.121	1.452
	0.065	(#16)	0.495	0.137	1.644
$^{3}/_{4}$ in.	0.035	(#20)	0.680	0.091	1.092
	0.049	(#18)	0.652	0.125	1.500
	0.058	(#17)	0.634	0.148	1.776
	0.065	(#16)	0.620	0.160	1.920
	0.083	(#14)	0.584	0.204	2.448
$^{7}/_{8}$ in.	0.035	(#20)	0.805	0.108	1.308
	0.049	(#18)	0.777	0.151	1.810
	0.058	(#17)	0.759	0.175	2.100
	0.065	(#16)	0.745	0.199	2.399
1 in.	0.035	(#20)	0.930	0.123	1.476
	0.049	(#18)	0.902	0.170	2.040
	0.058	(#17)	0.884	0.202	2.424
	0.065	(#16)	0.870	0.220	2.640
	0.083	(#14)	0.834	0.281	3.372
$1^{1}/_{8}$ in.	0.035	(#20)	1.055	0.139	1.668
	0.058	(#17)	1.009	0.228	2.736
$1^{1}/_{4}$ in.	0.035	(#20)	1.180	0.155	1.860
	0.049	(#18)	1.152	0.210	2.520
	0.058	(#17)	1.134	0.256	3.072
	0.065	(#16)	1.120	0.284	3.408
	0.083	(#14)	1.084	0.357	4.284
$1^{3}/_{8}$ in.	0.035	(#20)	1.305	0.173	2.076
	0.058	(#17)	1.259	0.282	3.384
$1^{1}/_{2}$ in.	0.035	(#20)	1.430	0.180	2.160
	0.049	(#18)	1.402	0.260	3.120
	0.058	(#17)	1.384	0.309	3.708
	0.065	(#16)	1.370	0.344	4.128
	0.083	(#14)	1.334	0.434	5.208
	*0.125	$^{1}/_{8}$ in.	1.250	0.630	7.416
	*0.250	$^{1}/_{4}$ in.	1.000	1.150	14.832
$1^{5}/_{8}$ in.	0.035	(#20)	1.555	0.206	2.472
	0.058	(#17)	1.509	0.336	4.032
1¾ in.	0.058	(#17)	1.634	0.363	4.356
	0.083	(#14)	1.584	0.510	6.120
$1^{7}/_{8}$ in.	0.058	(#17)	1.759	0.389	4.668
2 in.	0.049	(#18)	1.902	0.350	4.200
	0.065	(#16)	1.870	0.450	5.400
	0.083	(#14)	1.834	0.590	7.080
	*0.125	$^{1}/_{8}$ in.	1.750	0.870	9.960
	*0.250	$^{1}/_{4}$ in.	1.500	1.620	19.920
$2^{1}/_{4}$ in.	0.049	(#18)	2.152	0.398	4.776
	0.065	(#16)	2.120	0.520	6.240
	0.083	(#14)	2.084	0.660	7.920
$2^{1}/_{2}$ in.	0.065	(#16)	2.370	0.587	7.044
	0.083	(#14)	2.334	0.740	8.880
	*0.125	$^{1}/_{8}$ in.	2.250	1.100	12.720
	*0.250	$^{1}/_{4}$ in.	2.000	2.080	25.440
3 in.	0.065	(#16)	2.870	0.710	8.520
	*0.125	$^{1}/_{8}$ in.	2.700	1.330	15.600
	*0.250	¼ in.	2.500	2.540	31.200

*These sizes are extruded. All other sizes are drawn tubes.

usually tapered; they can be split on the larger end and then mated with the smaller end of another pole of the same diameter. A small stainless-steel hose clamp (sometimes also available at scrap yards!) can be used to fasten the poles at this junction. A 14- or 21-MHz element can be constructed from several tent poles in this fashion. If a longer continuous piece of tubing is available, it can be used for the center section to decrease the number of junctions and clamps.

Other aluminum scrap is sometimes available, such as US Army aluminum mast sections designated AB-85/GRA-4 (J&H Smith Mfg). These are 3 foot sections with a $1^{5}/_{8}$ inch diameter. The ends are swaged so they can be assembled one into another. These are ideal for making a portable mast for a 144-MHz beam or for Field Day applications.

CONSTRUCTION WITH ALUMINUM TUBING

Most antennas built for frequencies of 14 MHz and above are made to be rotated. Constructing a rotatable antenna requires materials that are strong, lightweight and easy to obtain. The materials required to build a suitable antenna will vary, depending on many factors. Perhaps the most important factor that determines the type of hardware needed is the weather conditions normally encountered.

High winds usually don't cause as much damage to an antenna as does ice, especially ice along with high winds. Aluminum element and boom sizes should be selected so the various sections of tubing will telescope to provide the necessary total length.

The boom size for a rotatable Yagi or quad should be selected to provide stability to the entire system. The best diameter for the boom depends on several factors; most important are the element weight, number of elements and overall length. Tubing of 1-¼-inch diameter can easily support three-element 28-MHz arrays and perhaps a two-element 21-MHz system. A 2-inch diameter boom will be adequate for larger 28-MHz antennas or for harsh weather conditions, and for antennas up to three elements on 14 MHz or four elements on 21 MHz. It is not recommended that 2-inch diameter booms be made any longer than 24 feet unless additional support is given to reduce both vertical and horizontal bending forces. Suitable rein-forcement for a long 2-inch boom can consist of a truss or a truss and lateral support, as shown in **Fig 8**.

A boom length of 24 feet is about the point where a 3-inch diameter begins to be very worthwhile. This dimension provides a considerable improvement in overall mechanical stability as well as increased clamping surface area for element hardware. Clamping surface area is extremely important if heavy icing is common and rotation of elements around the boom is to be avoided. Pinning an element to the boom with a large bolt helps in this regard. On smaller diameter booms, however, the elements sometimes work loose and tend to elongate the pinning holes in both the element and the boom. After some time the elements shift their positions slightly (sometimes from day to day!) and give a rather ragged appearance to the system, even though this doesn't generally harm the electrical performance.



Fig 8—A long boom needs both vertical and horizontal support. The cross bar mounted above the boom can support a double truss to help keep the antenna in position.

A 3-inch diameter boom with a wall thickness of 0.065 inch is satisfactory for antennas up to about a five-element, 14-MHz array that is spaced on a 40-foot long boom. A truss is recommended for any boom longer than 24 feet.

There is no RF voltage at the center of a parasitic element, so no insulation is required in mounting elements that are centered on the boom (driven elements excepted). This is true whether the boom is metal or a nonconducting material. Metal booms have a small "shortening effect" on elements that run through them. With materials sizes commonly employed, this is not more than one percent of the element length, and may not be noticeable in many applications. It is just perceptible with $^1/_2$-inch tubing booms used on 432 MHz, for example. Design-formula lengths can be used as given, if the matching is adjusted in the frequency range one expects to use. The center frequency of an all-metal array will tend to be 0.5 to 1 percent higher than a similar system built of wooden supporting members.

Element Assembly

While the maximum safe length of an antenna element depends to some extent on its diameter, the only laws that specify the minimum diameter of an element are the laws of nature. That is, the element must be rugged enough to survive whatever weather conditions it will encounter.

Fig 9 shows tapered Yagi element designs that will survive winds in excess of 80 mi/h. With a $^1/_4$-inch thickness of radial ice, these designs will withstand winds up to approximately 60 mi/h. (Ice increases the wind area but does not increase the strength of the element.) More rugged designs are shown in **Fig 10**. With no ice loading, these elements will survive in 120-mi/h winds, and in winds exceeding 85 mi/h with $^1/_4$ inch of radial ice. If you lose an antenna made with elements like these, you'll have plenty of company among your neighbors with commercially made antennas!

Figs 9 and 10 show only half elements. When the element is assembled, the largest size tubing for each element should be double the length shown in the drawing, with its center being the point of attachment to the boom. These designs are somewhat conservative, in that they are self-resonant slightly below the frequency indicated for each design. Telescoping the outside end sections to shorter lengths for resonance will increase the survival wind speeds. Conversely, lengthening the outside end sections will reduce the survival wind speeds. [See Bibliography listing for David Leeson (W6NL, ex-W6QHS) at the end of this chapter.]

Fig 11 shows several methods of fastening antenna element sections together. The slot and hose clamp method shown in Fig 11A is probably the best for joints where adjustments are required. Generally, one adjustable joint per element half is sufficient to tune the antenna. Stainless-steel hose clamps (beware—some "stainless


28 MHz
36″
67″
Approx Length
5/8″
1/2″
OD
96 (68) mi/hr
24.9 MHz
48″
68″
Approx Length
5/8″
1/2″
OD
85 (61) mi/hr
21 MHz
24″
36″
79″
Approx Length
3/4″
5/8″
1/2″
OD
86 (61) mi/hr
18.1 MHz
42″
36″
83″
Approx Length
3/4″
5/8″
1/2″
OD
83 (59) mi/hr
14 MHz
48″
48″
42″
72″
Approx Length
7/8″
3/4″
5/8″
1/2″
OD
82 (60) mi/hr

Fig 9—Half-element designs for Yagi antennas. The other side of the element is identical, and the center section should be a single piece twice as long as the length shown here for the largest diameter section. Use 0.058-in.-wall aluminum tubing throughout. Broken lines indicate double tubing thickness, where one tube is inserted into another. The overlap insertion depth into a tube two sizes larger, where shown, should be at least two inches. Maximum survival wind speeds without ice are shown adjacent to each design; values enclosed in parentheses are survival speeds for ¼ inch of radial ice.


28 MHz
24″
18″
62″
Approx Length
3/4″
5/8″
1/2″
OD
125 (88) mi/hr
24.9 MHz
36″
18″
63″
Approx Length
3/4″
5/8″
1/2″
OD
123 (87) mi/hr
21 MHz
30″
36″
18″
57″
Approx Length
7/8″
3/4″
5/8″
1/2″
OD
124 (90) mi/hr
18.1 MHz
24″
24″
36″
24″
55″
Approx Length
1″
7/8″
3/4″
5/8″
1/2″
OD
123 (89) mi/hr
1–1/8″ OD Tubing Inside
14 MHz
48″
24″
20″
42″
20″
59″
Approx Length
1–1/4″
1″
7/8″
3/4″
5/8″
1/2″
OD
122 (89) mi/hr

Fig 10—A more rugged schedule of taper proportions for Yagi half-elements than Fig 9. See the Fig 9 caption for details. Table 5 gives details of aluminum tubing sizes.



Fig 11—Methods of connecting telescoping tubing sections to build beam elements. See text for a discussion of each method.

Table 6
Hose-Clamp Diameters

	Clamp Diameter (In.)	
Size No.	*Min*	*Max*
06	$^{7}/_{16}$	$^{7}/_{8}$
08	$^{7}/_{16}$	1
10	$^{1}/_{2}$	1$^{1}/_{8}$
12	$^{5}/_{8}$	1$^{1}/_{4}$
16	$^{3}/_{4}$	1$^{1}/_{2}$
20	$^{7}/_{8}$	1$^{3}/_{4}$
24	1$^{1}/_{8}$	2
28	1$^{3}/_{8}$	2$^{1}/_{4}$
32	1$^{5}/_{8}$	2$^{1}/_{2}$
36	1$^{7}/_{8}$	2$^{3}/_{4}$
40	2$^{1}/_{8}$	3
44	2$^{5}/_{16}$	3$^{1}/_{4}$
48	2$^{5}/_{8}$	3$^{1}/_{2}$
52	2$^{7}/_{8}$	3$^{3}/_{4}$
56	3$^{1}/_{8}$	4
64	3$^{1}/_{2}$	4$^{1}/_{2}$
72	4	5
80	4$^{1}/_{2}$	5$^{1}/_{2}$
88	5$^{1}/_{8}$	6
96	5$^{5}/_{8}$	6$^{1}/_{2}$
104	6$^{1}/_{8}$	7

steel” models do not have a stainless screw and will rust) are recommended for longest antenna life. **Table 6** shows available hose-clamp sizes.

Figs 11B, 11C and 11D show possible fastening methods for joints that do not require adjustment. At B, machine screws and nuts hold the elements in place. At C, sheet metal screws are used. At D, rivets secure the tubing. If the antenna is to be assembled permanently, rivets are the best choice. Once in place, they are permanent. They will never work free, regardless of vibration or wind. If aluminum rivets with aluminum mandrels are used, they will never rust. In addition, there is no danger of dissimilar-metal corrosion with aluminum rivets and aluminum antenna elements. If the antenna is to be disassembled and moved periodically, either B or C will work. If machine screws are used, however, take all possible precautions to keep the nuts from vibrating free. Use lock washers, lock nuts and flexible sealant such as silicone bathtub sealant to keep the hardware in place.

Very strong elements can be made by using a double thickness of tubing, made by telescoping one size inside another for the total length. This is usually done at the center of an element where more element strength is desired at at the boom support point, as in the 14-MHz element in Fig 10. Other materials can be used as well, such as wood dowels, fiberglass rods, and so forth.

In each case where a smaller diameter length of tubing is telescoped inside a larger diameter one, it’s a good idea to coat the inside of the joint with Penetrox or a similar substance to ensure a good electrical bond. Antenna elements have a tendency to vibrate when they are mounted on a tower, and one way to dampen the vibrations is by running a piece of clothesline rope through the length of the element. Cap or tape the end of the element to secure the clothesline. If mechanical requirements dictate (a U-bolt going through the center of the element, for instance), the clothesline may be cut into two pieces.

Antennas for 50 MHz need not have elements larger than $^{1}/_{2}$-inch diameter, although up to 1 inch is used occasionally. At 144 and 220 MHz the elements are usually $^{1}/_{8}$ to $^{1}/_{4}$ inch in diameter. For 420 MHz, elements as small as $^{1}/_{16}$ inch diameter work well, if made of stiff rod. Aluminum welding rod of $^{3}/_{32}$ to $^{1}/_{8}$ inch diameter is fine for 420-MHz arrays, and $^{1}/_{8}$ inch or larger is good for the 220-MHz band. Aluminum rod or hard-drawn wire works well at 144 MHz.

Tubing sizes recommended in the paragraph above are usable with most formula dimensions for VHF/UHF antennas. Larger diameters broaden the frequency response; smaller ones sharpen it. Much smaller diameters than those recommended will require longer elements, especially in 50-MHz arrays.

Element Taper and Electrical Length

The builder should be aware of one important aspect of telescoping or tapered elements. When the element diameters are tapered, as shown in Figs 9 and 10, the electrical length is not the same as it would be for a cylindrical element of the same total length. Length corrections for tapered elements are discussed in Chapter 2.

Other Materials for Antenna Construction

Wood is very useful in antenna work. It is available in a great variety of shapes and sizes. Rug poles of wood or bamboo make fine booms. Bamboo is quite satisfactory for spreaders in quad antennas.

Round wood stock (doweling) is found in many hardware stores in sizes suitable for small arrays. Wood is good for the framework of multibay arrays for the higher bands, as it keeps down the amount of metal in the active area of the array. Square or rectangular boom and frame materials can be cut to order in most lumber yards if they are not available from the racks in suitable sizes.

Wood used for antenna construction should be well seasoned and free of knots or damage. Available materials vary, depending on local sources. Your lumber dealer can help you better than anyone else in choosing suitable materials. Joining wood members at right angles can be done with gusset plates, as shown in **Fig 12**. These can be made of thin outdoor-grade plywood or Masonite. Round materials can be handled in ways similar to those used with metal components, with U clamps and with other hardware.

In the early days of Amateur Radio, hardwood was used as insulating material for antennas, such as at the center and ends of dipoles, or for the center insulator of a driven element made of tubing. Wood dowels cut to length were the most common source. To drive out moisture and prevent the subsequent absorption of moisture into the wood, it was treated before use by boiling it in paraffin. Of course today's technology has produced superior materials for insulators in terms of both strength and insulating qualities. However, the technique is worth consideration in an emergency situation or if low cost is a prime requirement. "Baking" the wood in an oven for a short period at 200° F should drive out any moisture. Then treatment as described in the next paragraph should prevent moisture absorption. The use of wood insulators should be avoided at high-voltage points if high power is being used.

All wood used in outdoor installations should be protected from the weather with varnish or paint. A good grade of marine spar varnish or polyurethane varnish will offer protection for years in mild climates, and one or more seasons in harsh climates. Epoxy-based paints also offer good protection.

Plastics

Plastic tubing and rods of various sizes are available from many building-supplies stores. The uses for the available plastic materials are limited only by your imagination. Some amateurs have built beam antennas for VHF using wire elements run inside thin PVC plumbing pipe. The pipe gives the elements a certain amount of physical strength. Other hams have built temporary antennas by wrapping plastic pipe with aluminum foil or other conductive material. Plastic plumbing pipe fittings can also be used to enclose baluns and as the center insulator or end insulators of a dipole, as shown in **Fig 13**. Plastic or Teflon rod can be used as the core of a loading coil for a mobile antenna (**Fig 14**) but the material for this use should be selected carefully. Some plastics become quite warm in the presence of a strong RF field, and the loading-coil core might melt or catch fire!



Fig 12—Wood members can be joined at right angles using gusset plates.



Fig 13—Plastic plumbing parts can be used as antenna center and end insulators.

Fiberglass

Fiberglass poles are the preferred material for spreaders for quad antennas. They are lightweight, they withstand harsh weather well, and their insulating qualities are excellent. One disadvantage of fiberglass poles is that they may be crushed rather easily. Fracturing occurs at the point where the pole is crushed, causing it to lose its strength. A crushed pole is next to worthless. Some amateurs have repaired crushed poles with fiberglass cloth and epoxy, but the original strength is



Fig 14—A mobile-antenna loading coil wound on a polystyrene rod.

nearly impossible to regain.

Fiberglass poles can also be used to construct other types of antennas. Examples are helically wound Yagi elements or verticals, where a wire is wound around the pole.

CONCLUSION

The antenna should be put together with good quality hardware. Stainless steel is best for long life. Rust will quickly attack plated steel hardware, making nuts difficult, if not impossible, to remove. If stainless-steel muffler clamps and hose clamps are not available, the next best thing is to have them plated. If you can't have them plated, at least paint them with a good zinc-chromate primer and a finish coat or two.

Galvanized steel generally has a longer life than plated steel, but this depends on the thickness of the galvanizing coat. Even so, in harsh climates rust will usually develop on galvanized fittings in a few years. For the ultimate in long-term protection, galvanized steel should be further protected with zinc-chromate primer and then paint or enamel before exposing it to the weather.

Good quality hardware is expensive initially, but if you do it right the first time, you won't have to take the antenna down in a few years and replace the hardware. When the time does come to repair or modify the antenna, nothing is more frustrating than fighting rusty hardware at the top of the tower.

Basically any conductive material can be used as the radiating element of an antenna. Almost any insulating material can be used as an antenna insulator. The materials used for antenna construction are limited mainly by physical considerations (required strength and resistance to outdoor exposure) and by the availability of materials. Don't be afraid to experiment with radiating materials and insulators.

BIBLIOGRAPHY

Source Material and more extended discussion of topics covered in this chapter can be found in the reference given below.

J. J. Elengo, Jr., "Predicting Sag in Long Wire Antennas," *QST*, Jan 1966, pp 57-58.

D. B. Leeson, *Physical Design of Yagi Antennas* (Newington, CT: ARRL).

Chapter 21

Antenna Products Suppliers

Antenna Manufacturers Products

Finding parts can be the most difficult aspect of an antenna project. Suppliers of aluminum exist in most major metropolitan areas. They can be found in the Yellow Pages of the phone book. Some careful searching of the Yellow Pages may also reveal sources of other materials and accessories. If you live away from a metropolitan area, try using telephone books for the nearest large metropolitan area; they may be available in the reference section of your local library.

Many dealers and distributors will ship their products by freight or by mail. Tables 1 through 7 list several categories of antenna products and some suppliers of them. Company names have been abbreviated where necessary. Table 8 is an address list arranged alphabetically by company name.

Product lines change often; we recommend that you

Table 1
VHF/UHF/Microwave Antenna Suppliers

Manufacturer	Yagi	Quad	Loop Yagi	Vertical	Mobile	HT	Microwave	Helical	Satellite
Antennaco	✓								
Ant Specialists				✓	✓				
Austin Antenna				✓	✓	✓			
Butternut				✓					
Centurion						✓			
Comet				✓	✓	✓			
Create Design	✓								
Cubex		✓							
Cushcraft	✓		✓	✓	✓				✓
Diamond	✓		✓	✓	✓				
Down East	✓		✓				✓		✓
Eur-AM				✓	✓	✓			
Force 12	✓			✓					
Hustler	✓			✓	✓				
Hy-Gain (MFJ)	✓			✓					✓
Kilo-Tec				✓					
Lakeview				✓	✓	✓			
Larsen				✓	✓				
M^2	✓	✓		✓					
Maldol					✓				
MFJ	✓			✓	✓	✓			
Mosley	✓			✓					
Pro-Am Valor					✓				
RadioShack				✓	✓	✓			
Radio Works					✓				
Sommer	✓								
Spectrum Intl	✓		✓				✓	✓	✓
Tennadyne	LPDA								
Tonna	✓						✓		

request current catalogs from those manufacturers who interest you. In addition, all indications of sales policies and prices for catalogs are given for general information only and are subject to change without notice.

Antenna products for repeaters are listed separately, in Chapter 17.

Table 2
HF Antenna Suppliers

Manufacturer	Yagi	Quad	LPDA	Vertical	Dipole	Mobile	Small Xmtg	Active (RX only)
Alpha Delta				✓	✓	✓		
B & W				✓	✓			
Bilal							✓	
Butternut/Bencher	✓			✓			✓	
Create Design	✓		✓	✓	✓		✓	
Cubex		✓						
Cushcraft	✓		✓	✓	✓			
Flytecraft				✓		✓		
Force 12	✓		✓	✓	✓	✓	✓	
GAP				✓				
Gem Quad		✓						
Grove					✓	✓		✓
High Sierra				✓	✓	✓		
Hustler				✓		✓		
Hy-Gain (MFJ)	✓			✓	✓			
Lakeview/Hamstick						✓		
Lightning Bolt		✓						
M^2	✓				✓			
MFJ	✓	✓	✓	✓	✓	✓	✓	✓
Mosley	✓			✓	✓			
Palomar								✓
Pro-Am Valor						✓		
Roadrunner						✓		
Sommer	✓			✓				
Spi-Ro				✓	✓			
Tennadyne			✓					
Texas Radio					✓	✓		
Radio Works				✓	✓			
Van Gorden				✓	✓			
W1JC					✓		✓	
W9INN					✓			

Table 3
Antenna Parts



Manufacturer	Hardware	Insulators	Traps	Aluminum Tubing	Wire	Transmission Lines
Alexanderson AeroPlane Co				✓		
Barker & Williamson		✓	✓			
Cable X-Perts	✓	✓			✓	✓
Hy-Gain (MFJ)	✓	✓				
Metal & Cable, Inc	✓			✓	✓	
Ocean State Electronics	✓	✓			✓	✓
Spi-Ro		✓	✓		✓	✓
Texas Towers				✓	✓	✓
Radio Works	✓	✓			✓	✓
Van Gorden	✓	✓			✓	✓
The Wireman	✓	✓			✓	✓
W1JC		✓			✓	
W9INN					✓	

Table 4
Suppliers of Quad Antenna Parts

Company	*Material Size*
Cubex Co., Inc.	$1^1/_4$-$^1/_2$ in. × 13 ft; $1^1/_2$ in. × 13 ft cast spiders, boom-to-mast mounts.
Lightning Bolt	Custom-made fiberglass spreaders; any length.
Max-Gain Systems, Inc.	Quad spreaders; fiberglass insulators.

Table 5
Towers, Masts and Accessories

Towers
Aluma
Champion Radio
Create Design
Force 12
Glen Martin Engineering
Heights Tower
Hy-Gain (MFJ)
National Tower
RadioShack (masts only)
Rohn
Rotating Tower Systems
Tashjian Towers Corporation
Texas Tower
Trylon
Universal Manufacturing
US Tower

Climbing and Safety Equipment
Champion Radio Products
ONV
Texas Towers

Rotators
Create Design
Hy-Gain (MFJ)
M^2
RadioShack
The Rotor Doctor
Yaesu

Stacking Frames
(Unless otherwise noted these frames are for use in stacking the manufacturer's own antennas in pairs or in quads. These stacking kits are for VHF or UHF antennas only.)
C3i
Cushcraft
Down East
IIX
Spectrum International

Combiners, Power Dividers and Phasing Harnesses
Byers
C3i
Down East
Spectrum International
Tonna

Table 6
Transmission Lines

Source	Coax	Hardline	Ladder Line
Belden	✓	✓	
Cable X-Perts	✓	✓	✓
International Wire & Cable	✓		
Nemal	✓	✓	
The Radio Works	✓	✓	✓
W1JC			✓
W9INN			✓
The Wireman	✓	✓	✓

Table 7
Transmission Line Instruments and Accessories

Matching Networks
Ameritron
Barker & Williamson
Cubex
ICOM (mobile & fixed)
Kenwood
MFJ
Nye
SGC
Ten-Tec
Texas Radio (mobile only)
Vectronics
XMatch

Ferrite Cores and Rods
Amidon
Palomar
The Wireman

Filters—TVI (Low Pass & High Pass)
K-Com
MFJ

Lightning Arresters
Alpha Delta
Ameritron
Comet
Cushcraft
Hy-Gain (MFJ)
Polyphaser
Radioware
Rohn
The Wireman
Zero Surge Inc

Switches (Manual, Coax)
Alpha Delta
Barker & Williamson
MFJ

Switches (Remote, Coax)
Ameritron
MFJ

SWR and Wattmeters
Autek
Bird
Coaxial Dynamics
MFJ
Nye
Palomar
RF Parts
Texas Radio

Table 8
Suppliers Addresses

We have made every effort to ensure that this list is complete and accurate as of mid 2003. The ARRL takes no responsibility for errors or omissions. Similarly, a listing here does not represent an endorsement of a manufacturer or products by the ARRL. Refer to the product reviews in *QST* for descriptions of particular products that interest you. To the best of our knowledge the suppliers listed are willing to sell products to amateurs by mail unless indicated otherwise. This listing will be updated with each edition of *The Antenna Book* and *The ARRL Handbook* in the TISFIND manufacturer database. Check ads in *QST* and other Amateur Radio publications for any changes to this information. Suppliers who wish to be listed or update their information are urged to contact the editors.

Advanced Composites
1154 S. 300 W.
Salt Lake City, UT 84101
801-467-1204
fax 801-467-4367
e-mail
info@advancedcomposites.com

Advanced Specialties
114 Essex Street
Lodi, NJ 07644
USA
Tel: 800-926-9426
Email: advanspec@aol.com
http://advancedspec.freeyellow.com/

AEA—Div. Tempo Research Corporation
1221 Liberty Way
Vista, CA 92083
760-598-9677
fax 760-598-4898
e-mail tempo@inetworld.com
web www.aea-wireless.com

AFT
132 Boulevard Dauphinot
F-51100 Reims, France
+33 326 070 047
fax +33 326 023 654
e-mail Antennes-ft@wanadoo.fr
web www.f9ft.com

Alexander Aeroplane Co
PO Box 909
Griffin, GA 30224
800-831-2949; 404-229-2329

Alan Broadband Company
(Zap Checker)
93 Arch Street
Redwood City, CA 94062
USA
Tel: 888-369-9627 (orders)
650-369-9627
Fax: 650-369-3788
Email: ABCom@prodigy.net
http://www.alanbroadband.com/

Alpha Delta Communications
PO Box 620
Manchester, KY 40962
606-598-2029
fax 606-598-4413

Aluma Tower Co, Inc
PO Box 2806-AL
Vero Beach, FL 32961-2806
772-567-3423
fax 772-567-3432
e-mail atc-t@alumatower.com
web www.alumatower.com/index.html

Amateur Electronic Supply
5710 W Good Hope Rd
Milwaukee, WI 53223
800-558-0411
web www.aesham.com/

Ameritron Division
116 Willow Road
Starkville, MS 39759
662-323-8211 (Tech)
fax 662-323-6551
e-mail
ameritron@ameritron.com
web www.ameritron.com/ameritron

Amidon Associates, Inc.
1510 E. Edinger Avenue, Unit B
Santa Ana CA 92705
800-898-1883; 714-547-4494
fax 714-547-4433
e-mail sales@amidon-inductive.com
web www.amidon-inductive.com/

Antennaco Inc
102 Armory Road
PO Box 218
Milford, NH 03055-0218
603-673-3153
fax 603-673-4347

Allen Telecom Group
Antenna Specialists Mobile Division
30500 Bruce Industrial Parkway
Cleveland, OH 44139-3996
USA
440-349-8400
fax 440-349-8404
web www.antenna.com/

Array Solutions
350 Gloria Rd
Sunnyvale, Tx 75182
USA
Tel: 972-203-8810
Fax: 972-203-8811
Email: wx0b@arrysolutions.com
http://www.arraysolutions.com

ASA Antenna Sales
PO Box 3461
Myrtle Beach, SC 29578
800-772-2681

Associated Radio Communications
8012 Conser
Overland Park, KS 66204
913-381-5900; 800-497-1457
fax 913-648-3020
e-mail assocrad@tfs.net
web www.associatedradio.com

Austin Amateur Radio Supply
5310 Cammeron Road
Austin, TX 78723
800-423-2604; 512-454-2994
fax 512-454-3069

Austin Antenna, Ltd
10 Main St
Gonic, NH 03839
603-336-6339
fax 603-335-1756

Autek Research
PO Box 7556
Wesley Chapel, FL 33544
813-994-2199
e-mail
Mailbox@autekresearch.com
web www.autekresearch.com/
index.htm

Barker & Williamson Co
603 Cidco Rd
Cocoa, FL 32926
321-639-2545
fax 321-639-2545
e-mail
custsrvc@bwantennas.com
web www.bwantennas.com

Barry Electronics Corp
540 Broadway
New York, NY 10012
212-925-7000
fax 212-925-7001

Belden Wire & Cable
PO Box 1980
Richmond, IN 47374
317-983-5257
fax 317-983-5257
web www.belden.com

Bencher Inc.
831 North Central Avenue
Wood Dale, IL 60191
630-238-1183
fax 630-238-1186
e-mail bencher@bencher.com
web www.bencher.com/

Bilal Company
137 Manchester Dr
Florissant, CO 81816
719-687-0650
web www.isotronantennas.com/

Bird Electronics Corporation
30303 Aurora Rd.
Solon, OH 44139
866-695-4569
e-mail sales@bird-technologies.com
web www.bird-electronic.com/

Brian Beezley, K6STI
3532 Linda Vista Dr
San Marcos, CA 92069
619-599-4962
e-mail k6sti@n2.net

Burghardt Amateur Center, Inc.
710 10th Street SW
PO Box 73
Watertown, SD 57201
800-927-4261
605-886-7314 (Service)
605-886-6914 (Fax-back
product info)
fax 605-886-3444
e-mail burghart@daknet.com
web www.burghardt-amateur.com/

Butternut Electronics Co
See Bencher Inc.

Byers Chassis Kits
5120 Harmony Grove Road
Dover, PA 17315
717-292-4901
(6p-9p EST M-F, 8a-4p Sat)
717-292-4901 (24 hrs)

Cable X-Perts Inc.
225 Larkin Drive Suite #6
Wheeling, IL 60090-7209
800-828-3340 (orders only)
847-520-3003 (Tech. Info.)
fax 847-520-3444
e-mail cxp@cablexperts.com
web www.cablexperts.com/

CAL-AV Labs, Inc.
1802 w. Grant road, Ste. 116
Tucson, AZ 85745
USA
Tel: 520-624-1300
888-815-0400 (orders only)
Fax: 520-624-1311
Email: info@cal-av.com
http://www.cal-av.com/

Cardwell Condenser Corp
80 East Montauk Hwy
Lindenhurst, NY 11757
516-957-7200
fax 516-957-7203
web www.cardwellcondenser.com

C.A.T.S.
Formerly known as: Rotor Doctor
7368 SR 105
Pemberville, OH 43450
419-353-2287
fax 419-354-7746
e-mail mailto:craig@rotor-doc.com
web www.rotordoc.com

C-Comm
6115 15th NW
Seattle, WA 98107
206-784-7337; 800-426-6528
fax 206-784-0541

C3i
1401 K Street NW Suite 900
Washington DC 20005
(800) 224-5137
fax (202) 362-8481
e-mail info@C3iusa.com
web www.c3iusa.com/
corpover.html

Centurion International
PO Box 82846
Lincoln, NE 68501-2846
402-467-4491
fax 800-848-3825

Champion Radio Products
Box 572
Woodinville, WA 98072
425-485-7913
206-890-4188 Cell Phone
fax 360-668-1447
e-mail championradio@aol.com
web www.championradio.com/

Coaxial Dynamics
15210 Industrial Parkway
Cleveland, Ohio 44135-3308
800-262-9425
fax 216-267-3142
e-mail cdi-sales@coaxial.com
web www.coaxial.com/
home_frames.htm

Comet North America Inc.
394 Wards Corner Road
Suite 130
Cincinnati, Ohio, 45140
513-831-5000
fax 513-831-7889
e-mail
info@CometNorthAmerica.com
web www.cometnorthamerica.com/

Comet Antenna
See NCG

Comm-Pute
7946 State Street
Midvale, UT 84047
801-567-9944
fax 801-567-9494
e-mail bobwood@xmission.com
web www.comm-pute.com/

Communication Headquarters Inc.
3832 Oleander Drive
Wilmington, NC 28403
910-791-8885
800-688-0073 (orders)
fax 910-452-3891 (orders)
web www.chq-inc.com/

Communications Data Corp
1051 Main St
St Joseph, MI 49085
269-982-0404
fax 269-982-0433
e-mail mailto:did@gtm.net

Comtelco Industries Inc
501 Mitchell Rd
Glendale Heights, IL 60139
800-634-4622; 708-7790-9894
fax 708-798-9799

Create
4-8 Asano-Cho
Kawasaki-Ku
Kawasaki-City, Japan
044 (333) 6681
fax 044 (333) 6598
e-mail email@cd-corp.com

Cubex Co.
228 Hibiscus St, #9
Jupiter, FL 33458
561-748-2830
fax 561-748-2831
e-mail CubexCo@aol.com
web www.cubex.com/

Cushcraft Corp
48 Perimeter Rd.
Manchester, NH 03108
603-627-7877
e-mail sales@cushcraft.com
web www.cushcraft.com/

Dave's Hobby Shop
600 Main St.
Van Buren, AK 72956
USA
Tel: 479-471-0750
Web www.daveswebshop.com

Davis RF Co
See Radioware (distributor)
PO Box 730
Carlisle, MA 01741
978-371-1356
978-369-1738
800-328-4773 (Orders only)
fax 978-369-3484
e-mail davisrfinc@aol.com
web www.davisRF.com

Diamond Antennas
See RF Parts

Down East Microwave
954 Rt 519
Frenchtown, NJ 08825
908-996-3584
fax 908-996-3702
web downeastmicrowave.com/

Dressler Hochfrequenztechnik
GMBH
Werther Strasse 14-16
W-5190 Stolberg
Germany

DX Engineering
POB 440
Peninsula, Ohio 44264
USA
Fax: 330-657-2168
Email:
dxengineering@dxengineering.com
http://www.dxengineering.com/

EDCO - Electronic Distributors
Company
325 Mill Street
Vienna, VA 22180
703-938-8105
fax 703-938-6911
e-mail web www.elecdist.com/
index.html

EUR-AM Antennas
PO Box 225
Moultonboro, NH 03254-0225
603-476-5113
fax 603-476-5113
e-mail info@eur-am.com
web www.eur-am.com/

EZ Hang, Inc.
8645 Tower Dr.
Code C
Laurel, MD 20723
Tel: 540-286-0176
Fax: 202-260-3797
http://www.ezhang.com

Fluidmotion Incorporated
14135 233rd Place SE
Issaquah, WA 98027
425-456-0200; 800-885-8700
fax 425-391-6031
e-mail sales@steppir.com
web www.steppir.com/

Flytecraft
PO Box 3141
Simi Valley, CA 93093
805-583-8173

Force 12
PO Box 1349
Paso Robles, CA 93447
800-248-1985
805-227-1680 (Tech)
fax 805-227-1684
e-mail
mailto:force12e@lightlink.com
web force12inc.com/

GAP Antenna Products
99 North Willow St
Fellsmere, FL 32948
772-571-9922
Email: contact@gapantenna.com
web www.gapantenna.com

Gem Quad Products Ltd
PO Box 291
Boissevain, MB R0K 0E0
Canada
204-534-6184
fax 204-534-6492
e-mail
mailto:gemquad@escape.ca
web www.escape.ca/~gemquad/

GLA Systems
PO Box 425
Caddo Mills, TX 75135
903-527-4163
800-588-2841
fax 214-381-2895
web www.texasbugcatcher.com/

Grove Enterprises Inc.
PO Box 98
Brasstown, NC 28902
800-438-8155 (orders)
704-837-9200 (BBS)
fax 704-837-2216
e-mail nada@grove.net
web www.grove-ent.com/

Ham Radio Outlet
1702 W. Camelback Rd
Phoenix, AZ 85015
web www.hamradio.com/
800-444-4799 Mid Atlantic
800-444-9476 Mountain
800-444-0047 New England
800-644-4476 Northeast
800-444-7927 Southeast
800-854-6046 West

The Ham Station
220 North Fulton Avenue
PO Box 6522
Evansville, IN 47719-0522
800-729-4373 (orders)
812-422-0231 (Tech)
812-422-0252 (Service)
fax 812-422-4253
e-mail sales@hamstation.com
web www.hamstation.com/

Hamtronics, Inc
65-Q Moul Rd
Hilton, NY 14468
716-392-9430
fax 716-392-9420
web www.hamtronics.com

Hamware.de
Int'l: Klaus Bemmerer
Tel: +49 4371 869145
e-mail service@hamware.de
Web www.hamware.de
US: Dillon RF Systems
Email dillonel@mtaonline.net

Heights Tower Systems
1529 Gulf Beach Hwy
Pensacola, FL 32507
850-455-1210
fax 850-455-4355
e-mail info@heightstowers.com
web www.heightstowers.com/

Hi-Q Antennas
21085 Cielo Vista Way
Wildomar, CA 92595
909-674-4862
fax 909-245-2031
e-mail sales@hiqantennas.com
web www.hiqantennas.com/

High Sierra Antennas
Box 2389
Nevada City, CA 95959
888-273-3415; 530-273-3415
fax 530-273-7561
e-mail heath@hsantennas.com
web www.hsantennas.com

Hustler Antennas
see New-Tronics Antenna Corp.

Hy-Gain (also see MFJ)
308 Industrial Park Road
Starkville, MS 39759
800-647-1800 (Sales)
662-323-9358 (Tech)
fax 662-323-6551
web www.hy-gain.com/

ICOM America, Inc.
2380 116th Ave, NE, Suite S
Bellevue, WA 98004
USA
Tel: 800 872-4266
Fax: 425 454-1509
Web www.icomamerica.com

Industrial Communications
Engineers (ICE)
Array Solutions
350 Gloria Rd.
Sunnyvale, TX 75182
972-203-2008; 800-423-2666
fax 972-203-8811
e-mail wx0b@arraysolutions.com
web www.iceradioproducts.com/

IIX Equipment, Ltd
PO Box 9
Oak Lawn, IL 60454
708-423-0605
fax 708-423-1691
web www.w9iix.com/

International Radio
13620 Tyee Road
Umpqua, OR 97486
541-459-5623 9AM-1PM PDT,
Tues-Sat
fax 541-459-5632
e-mail inrad@rosenet.net
web www.qth.com/inrad/

Kenwood USA Corporation
3975 Johns Creek Court,
Suite 300
Suwanee, GA 30024
USA
Tel: 678 474-4700
Fax: 678 474-4730
Web www.kenwoodusa.com

K0XG Systems
1117 Highland Park Drive
Bettendorf, IA 52722
USA
Tel: 563 355-7451
Email K0XG@ K0XG.com
Web www.k0xg.com

Kilo-Tec
PO Box 10
Oakview, CA 93022
805-646-9645

K-Com
PO Box 82
Randolph OH 44265
330-325-2110
fax 330-325-2525
e-mail k-com@worldnet.att.net
web www.k-comfilters.com/
howtoget.asp

Lakeview Co Inc
3620-9A Whitehall Rd
Anderson, SC 29626
(864) 226-6990
fax (864) 225-4565
web www.hamstick.com

Larsen Electronics, Inc
See Radial/Larsen

LDG Electronics
1445 Parran Road
St Leonard, MD 20685
877-890-3003 Toll-Free Orders
410-586-2177 Tech Support
fax 410-586-8475
e-mail ldg@ldgelectronics.com
web www.ldgelectronics.com

Lentini Communications
21 Garfield St
Newington, CT 06111
860-666-6227
800-666-0908 (outside CT)
fax 860-667-3561
e-mail radio@lentinicomm.com
web www.lentinicomm.com

Roy Lewallen, W7EL
PO Box 6658
Beaverton, OR 97007
503-646-2885
fax 503-671-9046
e-mail w7el@eznec.com
web www.eznec.com

Lightning Bolt Antennas
RD #2, RT 19
Volant, PA 16156
724-530-7396
fax 724-530-6796
e-mail lbaquads@ztrain.com
web
www.lightningboltantennas.com/

M^2 Antenna Systems Inc.
4202 N. Selland
Fresno CA, 93722
559-432-8873
fax 559-432-3059
e-mail wyatt@m2inc.com
web www.m2inc.com/

M/A-COM, Inc
(an AMP Company)
1011 Pawtucket Blvd
PO Box 3295
Lowell, MA 01853-3295
508-442-4500
fax 508-442-4436
e-mail sales@macom.com
web www.amp.com

Maldol USA
4711 NE 50th St
Seattle, WA 98105
Answerfax 206-525-1896
fax 206-524-7826
e-mail transtec@cyberquest.com

Glen Martin Engineering
13620 Old Highway 40
Boonville, MO 65233
660-882-2734; 800-486-1223
fax 660-882-7200
web www.glenmartin.com

The Mast Company
Henry Pollock - K4TMC
P.O. Box 1932
Raleigh, NC 27602
Email: k4tmc@aol.com
http://www.geocities.com/tmastco/

MCM Electronics
650 Congress Park Dr
Centerville, OH 45459-4072
800-543-4330
fax 800-765-6960
web www.i-mcm.com

Memphis Amateur Electronics
1465 Wells Station Rd
Memphis, TN 38108
901-683-9125; 800-238-6168
fax 901-682-7165

Metal and Cable Corp, Inc
9241 Ravenna Road, Unit C-10
PO Box 117
Twinsburg, OH 44087
330-425-8455
fax 330-425-3504
web www.metal-cable.com/

MFJ Enterprises
300 Industrial Park Rd
Starkville, MS 39759
662-323-5869
Email
mfjcustserv@mfjenterprises.com
web www.mfjenterprises.com/

MGS (Max-Gain Systems, Inc.)
221 Greencrest Court
Marietta, GA 30068-3825
770-973-6251 (before 9 PM
eastern)
fax 815) 461-7730
e-mail info@mgs4u.com
web www.mgs4u.com/

Michigan Radio
26014 Groesbeck Hwy
Warren, MI 48089
810-771-4711
800-TRU-HAMM (800-878-4266)
Orders only
810-771-4712 (Service)
fax 810-771-6546
web www.michiganradio.com/

Mirage Communications
116 Willow Road
Starkville, MS 39759
662-323-8287
fax 662-323-6551
web www.mirageamp.com/

James Millen Electronics
PO Box 4215BV
Andover, MA 01810-4215
978-975-2711
fax 978-474-8949
e-mail info@jamesmillenco.com
web www.jamesmillenco.com/
millen/millmain.htm

Mosley Electronics
1325 Style Master Drive
Union, MO 63084
800-325-4016 (Orders)
800-9MOSLEY (966-7539)
314-994-7872 (Technical)
fax 314-994-7873
web www.mosley-electronics.com/

Multi-band Antennas (originally
Spider Antennas)
7131 Ownesmouth Avenue -
Suite 563C
Canoga Park, CA 91303
818-341-5460
web www.spiderantenna.com/

Multi-tech Industries, Inc. (MTI)
(formally Radio Switch)
64 South Main Street
PO Box 159
Marlboro, NJ 07746-0159
800-431-3223; 732-431-0550
732-462-6100
fax 732-409-6695
e-mail multitech@sprynet.com
web www.multi-tech-industries.com

National RF, Inc.
7969 Engineer Road, Suite 102
San Diego, CA 92111
858-565-1319
fax 858-571-5909
web www.nationalrf.com/

National Tower Co
PO Box 15417
Shawnee Mission, KS 66285
800-762-5049; 913-888-8864

NCG Companies—Comet Antenna
1275 North Grove St
Anaheim, CA 92806
714-630-4541; 800-962-2611
fax 714-630-7024
web www.cometantenna.com
web www.natcommgroup.com/

Nemal Electronics Inc.
12240 NE 14th Avenue
North Miami, FL 33161
305-893-3924; 305-849-0900
800-522-2253
fax 305-895-8178
e-mail info@nemal.com
web www.nemal.com/

New-Tronics Antenna Corp. - Hustler
1 Newtronics Place
Mineral Wells, TX 76067-9563
877-994-9499 Sales
940-325-1386 Service
fax 940-328-1409
e-mail sales@new-tronics.com
web www.new-tronics.com/main/index.html

Nittany Scientific
1733 West 12600 South
Suite 420
Riverton, UT 84065
Phone/fax (801) 446-1426
e-mail sales@nittany-scientific.com
web www.nittany-scientific.com/

William M. Nye Co
PO Box 1877
Priest River, ID 83856
208-448-1762
fax 208-448-1832

Ocean State Electronics
PO Box 1458
6 Industrial Dr
Westerly, RI 02891
401-596-3080; 800-866-6626
fax 401-596-3590
web www.oselectronics.com

ONV Safety Belt Co.
Box 404
Ramsey, NJ 07446
800-345-5634; 201-327-2462
fax 201-327-2462

OptiBeam
Thomas Schmenger DF2BO
Rastatter Straße 37
D-75179 Pforzheim
Tel./Fax: (0049) 07231 / 45 31 53
Email: Info@optibeam.de

OptiBeam NorthAmerica
Array Solutions
350 Gloria Rd
Sunnyvale, Tx 75182 USA
Tel: 972-203-8810
Fax: 972-203-8811
Email: wx0b@arrysolutions.com
http://www.arraysolutions.com

Orion now sold by M^2

Outbacker Antenna Sales
330 Cedar Glen Circle
Chattanooga, TN 37412
615-899-3390
fax 615-899-6536

Palomar Engineers
PO Box 462222
Escondido, CA 92046
619-747-3343
fax 619-747-3346
e-mail palomar@compuserve.com
web www.palomar-engineers.com/

Palstar, Inc.
9676 N Looney Rd
P O Box 1136-1482
Piqua, Ohio 45356
USA
Tel: 937-773-6255
Fax: 937-773-8003
Email: Palstar@erinet.com
http://www.palstarinc.com/

Phillystran, Inc
151 Commerce Dr
Montgomeryville, PA 18936
215-368-6611
fax 215-362-7956
web www.phillystran.com/

PolyPhaser Corp
2225 Park Place
PO Box 9000
Minden, NV 89423-9000
702-782-2511
fax 702-782-4476
e-mail info@polyphaser.com
web www.polyphaser.com

Quicksilver Radio Products
30 Tremont St.
Meriden, CT 06450
USA
Tel: 203-440-4468
http://www.qsradio.com

Radiall/Larsen Antenna Technologies
3611 NE 112th Avenue
Vancouver, WA 98682
800-ANTENNA (800-268-3662)
360-944-7551
FAX 360-944-7556
fax 800-525-6749
e-mail info@radialllarsen.com
web www.radialllarsen.com/default.htm

Radio Bookstore (Radioware)
PO Box 209
Rindge, NH 03461-0209
603-899-6957
800-457-7373 (10am-6pm EST)
fax 603-899-6826
e-mail radware@radio-ware.com
web www.radiobooks.com/

Radio Center USA
1242 Howell
N. Kansas City, MO 64116
816-459-8832; 800-821-7323

Radio City
2663 County Rd I
Mounds View, MN 55112
612-786-4475; 800-426-2891
fax 612-786-6513
web www.radioinc.com

Radio Engineers/Technitron (see National RF, Inc.)

Radio Shack
(Contact your local store)

Radio Switch Corp
See Multi-tech Industries

Radio Works
PO Box 6159
Portsmouth, VA 23703
757-484-0140
800-280-8327 (Orders)
fax 757-483-1873
e-mail jim@radioworks.com
web radioworks.com/

Raibeam Antennas, Int'l
5638 West Alice Avenue
Glendale, AZ 85302
800-530-1913 (orders)
602-931-9135
e-mail wa7rai@raibeam.com
web www.raibeam.com/

RF Parts Co
435 South Pacific St
San Marcos, CA 92069
760-744-0700; 800-737-2787
760-744-0750 (Tech)
fax 760-744-1943; 888-744-1943
e-mail rfp@rfparts.com
web www.rfparts.com

RF TEC Manufacturing
256 Commerce Rd, Suite 517
Peachtree, GA 30269
770-251-2235
fax 770-502-9827
web www.rftec.com/

Roadrunner Resonator
1850 Swanson, #A20
Lake Havasu, AZ 86403
520-453-7211

ROHN Industries, Inc.
PO Box 2000
Peoria, IL 61656
309-697-4400
fax 309-697-5612
e-mail mail@rohnnet.com
web www.rohnnet.com/Index.htm

Ross Distributing Co
78 South State St
Preston, ID 83263
208-852-0830
fax 208-852-0833
web www.rossdist.com

Rotating Tower Sytems, Inc.
Box 44
Prosper, TX 75058
214-347-2560

Rotor Doctor
See C.A.T.S.

SGC Inc
13737 SE 26th St
Bellevue, WA 98005
425-746-6310
fax 425-746-6384
e-mail sgc@sgcworld.com
web www.sgcworld.com/

Shoestring Antennas
PO Box 425
Keyport, WA 98345
360-697-5399
fax 360-697-8416
e-mail jacksa@juno.com
web www.qth.com/shoestring/

Sky-Pole Manufacturing, Inc
1922 Placentia Ave
Costa Mesa, CA 92627
949-548-5596
fax 949-548-5598

Sommer Antennas
PO Box 710
Geneva, FL 32732
407-349-9114
fax 407-349-2485
e-mail sommer1@ix.netcom.com
web www.sommerantennas.com

Spectrum International, Inc
PO Box 1084
Concord, MA 01742
508-263-2145
fax 508-263-7008

Spi-Ro Manufacturing, Inc.
P.O. Box 189
Jonesborough, TN 37659
800-728-7594
423-913-1615 Tech Support
fax 423-913-2131
e-mail mailto:contact@spiromfg.com
web www.spiromfg.com/

Surplus Sales of Nebraska
1502 Jones St
Omaha, NE 68102-3112
402-346-4750
800-244-4567 (Orders only)
fax 402-346-2939
e-mail grinnell@surplussales.com
web www.surplussales.com/

Tarheel Antennas
913 Old Honeycutt Rd
Fuquay-Varina, NC 27256
919-552-8788
fax 919-552-4970
e-mail tarheelantennas@aol.com
web www.tarheelantennas.com/

Tashjian Towers Corporation
(used to be Tri-Ex Towers)
2183 S Highland Ave.
Sanger, CA 93657
559-495-0307
559-284-9707 Mobile
fax 559-495-0557
e-mail tashjian@MSN.com
web www.karltashjian.com/

Telex Communications, Inc
Hy-Gain (see MFJ)

Ten-Tec, Inc
1185 Dolly Parton Parkway
Sevierville, TN 37862
865-453-7172
865-428-0364 (Repairs)
fax 865-428-4483
web www.tentec.com/

Tennadyne Corp
PO Box 34202
San Antonio, TX 78265-4202
210-599-9064
fax 210-599-9064
(same as voice)
e-mail tennadyn@satx.net
web www.tennadyne.com/

Teri Software
PO Box 277
Lincoln, TX 78948
979-542-7952
e-mail
support@antennamodel.com
web www.antennamodel.com

Texas Radio Products
5 E Upshaw
Temple, TX 76501
817-771-1188

Texas Towers
1108 Summit Ave, Suite 4
Plano, TX 75074
800-272-3467
972-422-7306 (Tech)
fax 972-881-0776
e-mail sales@texastowers.com
web www.texastowers.com/

T.G.M. Communications
121 Devon Street
Stratford, Ontario, N5A 2Z8
Canada
519-271-5928
e-mail tgmc@sympatico.ca
web www3.sympatico.ca/tgmc/
index.html

TIC General
PO Box 1 - 1110 Airport Rd
Thief River Falls, MN 56701
218-681-1119
fax 218-681-8509

Timewave Technology, Inc.
1025 Selby Ave, Suite 101
St Paul, MN 55104
USA
Tel: 651-489-5080
Email: sales@timewave.com
http://www.timewave.com

Traffie Technology
421 Jones Hill Road
Ashby, MA 01431-1801
888-599-BEAM (888-599-2326)
978-386-7900
fax 978-386-7900 (same as voice)

Trylon Manufacturing Co, Ltd
21 South Field Dr
PO Box 186
Elmira, Ontario
N3B 2Z6 Canada
519-669-5421
fax 519-669-8912
e-mail info@trylon.com
web www.trylon.com/home.asp

Tucker Electronics and Computers
1717 Reserve St.
PO Box 551419
Garland, TX 75355-1419
800-527-4642 (Test equipment
and catalog requests)
214-348-8800 (x332)
fax 214-340-5460
web www.tucker.com/

Unadilla Antenna Manufacturing
PO Box 4215
Andover, MA 01810-4215
978-975-2711
978-475-7831 (Office)
fax 978-474-8949
e-mail info@unadilla.com
web www.unadilla.com/

Universal Manufacturing Co
43900 Groesbeck Hwy
Clinton Township, MI 48036
810-463-2560
fax 810-463-2964

Universal Radio
6830 Americana Parkway
Reynoldsburg, OH 43068-4113
USA
Tel: 800-431-3939 (Orders)
614-866-4267 (Technical Info)
Fax: 614-866-2339
Email: dx@universal-radio.com
http://www.universal-radio.com/

US Tower Corp
1220 Marcin St
Visalia, CA 93291
559-733-2438
fax 559-733-7194
web www.ustower.com

Valor Enterprises
1711 Commerce Drive
PO Box 601
Piqua, OH 45356-0601
513-778-0074; 800-543-2197
fax 513-778-0259
web www.valorantenna.com/

Van Gorden Engineering
PO Box 21305
South Euclid, OH 44121

Van Valzah Co
38 W 111 Horseshoe Dr
Batavia, IL 60515-9730
708-406-9210

Vectronics
300 Industrial Park Road
Starkville, MS 39759
800-363-2922; 662-323-5800
fax 662-323-6551
e-mail jshurden@vectronics.com
web www.vectronics.com

XMatch
Paul Schrader, N4XM
7001 Briscoe Lane
Louisville, KY 40228
web http://n4xm.myiglou.com/

XX Towers
814 Hurricane Hill Road
Mason, NH 03048
603-878-1102
fax 603-878-4200
e-mail kc1xx@kc1xx.mv.com
web www.xxtowers.com/

W1JC—TV Evans
113 Stratton Brook Rd
Simsbury, CT 06070
860-658-5579
web pages.prodigy.com/w1jc

W3FF Antennas
2390 Templeton Dr.
Redding, CA 96002
USA
Tel: 530-226-8446
Email: sales@buddipole.com
http://www.buddipole.com

W7FG Vintage Manuals
3300 Wayside Drive
Bartlesville, OK 74006
USA
Tel: 800-807-6146 (orders)
918-333-3754
Email: w7fg@eigen.net
http://www.w7fg.com/

W9INN Antennas
PO Box 393
Mt Prospect, IL 60056
847-394-3414

Wacom Products
PO Box 21145
Waco, TX 76702
716-549-4700
e-mail sales@txrx.com

WBØW, Inc
PO Box 8547
Saint Joseph, MO 64508
USA
Tel: 816-364-2691
Email: WB0W@WB0W.com

The Wireman Inc.
261 Pittman Road
Landrum, SC 29356-9544
800-727-WIRE (800-727-9473)
Orders only
864-895-4195 Technical
fax 803-895-5811
e-mail N8UG@earthlink.net
web thewireman.com/

Yaesu U.S.A. (Vertex Standard)
10900 Walker St.
Cypress, CA 90630
714-827-7600
e-mail
amateurtech@vxstdusa.com
web www.yaesu.com/amateur/
amateur.html

YagiStress
Kurt Andress, K7NV
2835 Wade Street
Minden, NV 89423
702-267-5290
e-mail K7NV@contesting.com
web yagistress.freeyellow.com/

Zero Surge Inc
944 State Rt 12
Frenchtown, NJ 08825
908-996-7700
fax 908-996-7773
e-mail zerosurge1@aol.com
web www.zerosurge.com/

Chapter 22

Antenna Supports

A prime consideration in the selection of a support for an antenna is that of structural safety. Building regulations in many localities require that a permit be obtained in advance of the erection of certain structures, often including antenna poles or towers. In general, localities having such requirements also have building safety codes that must be observed. Such regulations may govern the method and materials used in construction of, for example, a self-supporting tower. Checking with your local government building department before putting up a tower may save a good deal of difficulty later, because a tower would have to be taken down or modified if not approved by the building inspector on safety grounds.

Municipalities have the right and duty to enforce any reasonable regulations having to do with the safety of life or property. The courts generally have recognized, however, that municipal authority does not extend to aesthetic questions. The fact that someone may object to the mere presence of a pole, tower or other antenna structure because in his opinion it detracts from the beauty of the neighborhood is not grounds for refusing to issue a permit for a safe structure to be erected. Since the introduction of PRB-1 (federal preemption of unnecessarily restrictive antenna ordinances), this principle has been borne out in many courts. Permission for erecting amateur towers is more easily obtained than in the recent past because of this legislation.

Even where local regulations do not exist or are not enforced, the amateur should be careful to select a location and a type of support that contribute as much safety as possible to the installation. If collapse occurs, the chances of personal injury or property damage should be minimized by careful choice of design and erection methods. A single injury can be far more costly than the price of a more rugged support, in terms of both monetary loss and damage to the public respect for amateur radio.

This chapter has been reviewed and rewritten by Kurt Andress, K7NV.

TREES AS ANTENNA SUPPORTS

From the beginning of Amateur Radio, trees have been used widely for supporting wire antennas. Trees cost noth-



Fig 1—A method of counter weighting to minimize antenna movement and avoid its breaking from tree movement in the wind. The antenna may be lowered without climbing the tree by removing the counterweight and tying additional rope at the bottom end of the halyard. Excess rope may be left at the counterweight for this purpose, as the knot at the lower end of the halyard will not pass through the pulley.

ing to use, and often provide a means of supporting a wire antenna at considerable height. As antenna supports, trees are unstable in the presence of wind, except in the case of very large trees used to support antennas well down from the top branches. As a result, tree-supported antennas must be constructed much more sturdily than is necessary with stable supports. Even with rugged construction, it is unlikely that an antenna suspended from a tree, or between trees, will stand up indefinitely. Occasional repair or replacement usually must be expected.

There are two general methods of securing a pulley to a tree. If the tree can be climbed safely to the desired level, a pulley can be attached to the trunk of the tree, as shown in **Fig 1**. To clear the branches of the tree, the antenna end of the halyard can be tied temporarily to the tree at the pulley level. Then the remainder of the halyard is coiled up, and the coil thrown out horizontally from this level, in the direction in which the antenna runs. It may help to have the antenna end of the halyard weighted.

After attaching the antenna to the halyard, the other end is untied from the tree, passed through the pulley, and brought to ground along the tree trunk in as straight a line as possible. The halyard need only be long enough to reach the ground after the antenna has been hauled up. (Additional rope can be tied to the halyard when it becomes necessary to lower the antenna.)

The other method consists of passing a line over the tree from ground level, and using this line to haul a pulley up into the tree and hold it there. Several ingenious methods have been used to accomplish this. The simplest method employs a weighted pilot line, such as fishing line or mason's chalk line. By grasping the line about two feet from the weight, the weight is swung back and forth, pendulum style, and then heaved with an underhand motion in the direction of the treetop.

Several trials may be necessary to determine the optimum size of the weight for the line selected, the distance between the weight and the hand before throwing, and the point in the arc of the swing where the line released. The weight, however, must be sufficiently large to carry the pilot line back to ground after passing over the tree. Flipping the end of the line up and down so as to put a traveling wave on the line often helps to induce the weight to drop down if the weight is marginal. The higher the tree, the lighter the weight and the pilot line must be. A glove should be worn on the throwing hand, because a line running swiftly through the bare hand can cause a severe burn.

If there is a clear line of sight between ground and a particularly desirable crotch in the tree, it may eventually be possible to hit the crotch after a sufficient number of tries. Otherwise, it is best to try to heave the pilot line completely over the tree, as close to the centerline of the tree as possible. If it is necessary to retrieve the line and start over again, the line should be drawn back very slowly; otherwise the swinging weight may wrap the line around a small limb, making retrieval impossible.

Stretching the line out straight on the ground before throwing may help to keep the line from snarling, but it places extra drag on the line, and the line may snag on obstructions overhanging the line when it is thrown. Another method is to make a stationary reel by driving eight nails, arranged in a circle, through a 1-inch board. After winding the line around the circle formed by the nails, the line should reel off readily when the weighted end of the line is thrown. The board should be tilted at approximately right angles to the path of the throw.

Other devices that have been used successfully to pass a pilot line over a tree are a bow and arrow with heavy thread tied to the arrow, and a short casting rod and spinning reel used by fishermen. The Wrist Rocket slingshot made from surgical rubber tubing and a metal frame has proved highly effective as an antenna-launching device. Still another method that has been used where sufficient space is available is flying a kite to sufficient altitude, walking around the tree until the kite string lines up with the center of the tree, and paying out string until the kite falls to the earth. This method can be used to pass a line over a patch of woods between two higher supports, which may be impossible using any other method.

The pilot line can be used to pull successively heavier lines over the tree until one of adequate size to take the strain of the antenna has been reached. This line is then used to haul a pulley up into the tree after the antenna halyard has been threaded through the pulley. The line that holds the pulley must be capable of withstanding considerable chafing where it passes through the crotch, and at points where lower branches may rub against the standing part. For this reason, it may be advisable to use galvanized sash cord or stranded guy wire for raising the pulley.

Larger lines or cables require special attention when they must be spliced to smaller lines. A splice that minimizes the chances of coming undone when coaxed through the tree crotch must be used. One type of splice is shown in **Fig 2**.



Fig 2—In connecting the halyard to the pilot line, a large knot that might snag in the crotch of a tree should be avoided, as shown.



Fig 3—A weighted line thrown over the antenna can be used to pull the antenna to one side of overhanging obstructions, such as tree branches, as the antenna is pulled up. When the obstruction has been cleared, the line can be removed by releasing one end.



Fig 4—The cleat eliminates the need to untie a knot that may be weather hardened.

The crotch in which the line first comes to rest may not be sufficiently strong to stand up under the tension of the antenna. If, however, the line has been passed over (or close to) the center line of the tree, it will usually break through the lighter crotches and come to rest in a stronger one lower in the tree.

Needless to say, any of the suggested methods should be used with due respect to persons or property in the immediate vicinity. A child's sponge-rubber ball (baseball size) makes a safe weight for heaving a heavy thread line or fishing line.

If the antenna wire snags in the lower branches of the tree when the wire is pulled up, or if other trees interfere with raising the antenna, a weighted line thrown over the antenna and slid to the appropriate point is often helpful in pulling the antenna wire to one side to clear the interference as the antenna is being raised. This is shown in **Fig 3**.

Wind Compensation

The movement of an antenna suspended between supports that are not stable in the wind can be reduced by the use of heavy springs, such as screen-door springs under tension, or by a counterweight at the end of one halyard. This is shown in Fig 1. The weight, which may be made up of junkyard metal, window sash weights, or a galvanized pail filled with sand or stone, should be adjusted experimentally for best results under existing conditions. **Fig 4** shows a convenient way of fastening the counterweight to the halyard. It eliminates the necessity for untying a knot in the halyard, which may have hardened under tension and exposure to the weather.

TREES AS SUPPORTS FOR VERTICAL WIRE ANTENNAS

Trees can often be used to support vertical as well as horizontal antennas. If the tree is tall and has overhanging branches, the scheme of **Fig 5** may be used. The top end of the antenna is secured to a halyard passed over the limb, brought back to ground level, and fastened to the trunk of the tree.



Fig 5—Counterweight for a vertical antenna suspended from an overhanging tree branch.

MAST MATERIALS

Where suitable trees are not available, or a more stable support is desired, light-duty guyed masts are suitable for wire antennas of reasonable span length. At one time, most amateur masts were constructed of lumber, but the TV industry has brought out metal masts that are inexpensive and much more durable than wood. However, there are some applications where wood is necessary or desirable.

A Ladder Mast

A temporary antenna support is sometimes needed for an antenna system for antenna testing, site selection, emergency exercises or Field Day. Ordinary aluminum extension ladders are ideal candidates for this service. They are strong, light, extendable, weatherproof and easily transported. Additionally, they are readily available and can be returned to normal use once the project is concluded. A ladder tower will support a lightweight triband beam and rotator.

With patience and ingenuity one person can erect this assembly. One of the biggest problems is holding the base down while "walking" the ladder to a vertical position. The ladder can be guyed with $^1/_4$-inch polypropylene rope. Rope guys are arranged in the standard fashion with three at each level. If help is available, the ladder can be walked up in its retracted position and extended after the antenna and rotator are attached. The lightweight pulley system on most extension ladders is not strong enough to lift the ladder extension. This mechanism must be replaced (or augmented) with a heavy-duty pulley and rope. Make sure when attaching the guy ropes that they do not foul the operation of the sliding upper section of the ladder.

There is one hazard in this system that must be avoided: Do not climb or stand on the ladder when it is being extended—even as much as one rung. Never stand on the ladder and attempt to raise or lower the upper section. Do all the extending and retracting with the heavy-duty rope and pulley!

If the ladder is to be raised by one person, use the following guidelines. First, make sure the rung-latching mechanism operates properly before beginning. The base must be hinged so that it does not slip along the ground during erection. The guy ropes should be tied and positioned in such a way that they serve as safety constraints in the event that control of the assembly is lost. Have available a device (such as another ladder) for supporting the ladder during rest periods. (See **Fig 6**.)



Fig 6—Walking the ladder up to its vertical position. Keith, VE2AQU, supports the mast with a second ladder while Chris, VE2FRJ, checks the ropes. (*Photo by Keith Baker, VE2XL.*)

After the ladder is erect and the lower section guys tied and tightened, raise the upper portion one rung at a time. Do not raise the upper section higher than it is designed to go; safety is far more important than a few extra feet of height.

For a temporary installation, finding suitable guy anchors can be an exercise in creativity. Fence posts, trees, and heavy pipes are all possibilities. If nothing of sufficient strength is available, anchor posts or pipes can be driven into the soil. Sandy soil is the most difficult to work with because it does a very poor job of holding anchors. A discarded car axle can be driven into the ground as an anchor, as its mass and strength are substantial. A chain and car-bumper jack can be used to remove the axle when the operation is done.

Above all else, keep the tower and antenna away from power lines. Make sure that nothing can touch the lines if the assembly falls. Disassemble by reversing the process. Ladder towers are handy for "quickie" antenna supports, but as with any improvisation of support materials, care must be taken to ensure safe construction.

The A-Frame Mast

A light and relatively inexpensive mast is shown in **Fig 7**. In lengths up to 40 feet it is very easy to erect and will stand the pull of ordinary wire antenna systems. The lumber used is 2 × 2-inch straight-grained pine (which many lumber yards know as hemlock) or even fir stock. The uprights can be as long as 22 feet each (for a mast slightly over 40 feet high) and the cross pieces are cut to fit. Four pieces of 2 × 2 lumber, each 22 feet long, provides more than enough. The only other materials required are five $^1/_4$-inch carriage bolts $5^1/_2$ inches long, a few spikes, about 300 feet of stranded or solid galvanized wire for guying, enough glazed porcelain compression ("egg") insulators to break up the guys into sections, and the usual pulley and halyard rope. If the strain insulators are put in every 20 feet, approximately 15 of them will be enough.

After selecting and purchasing the lumber—which should be straight-grained and knot-free—sawhorses or boxes should be set up and the mast assembled as shown in **Fig 8**. At this stage it is wise to give the mast a coat of primer and a coat of outside white latex paint.

After the coat of paint is dry, attach the guys and rig the pulley for the antenna halyard. The pulley anchor should be at the point where the top stays are attached so the backstay will assume the greater part of the load tension. It is better to use wire wrapped around the mast with a small through-bolt to prevent sliding down than to use eyebolts.


3 Top Guys
Ant.
Total Height 40′ Plus
Guy Front and Back Here-No Side Guys Necessary
3′
Carriage Bolts
Three 2 X 2's Each 22′
Drill 1/8″ Hole Through Uprights and Hammer in Spikes
1/4″ Bolt
1/4″ Carriage Bolt
6′ or 7′

Fig 7—The A-frame mast is lightweight and easily constructed and erected.


A
Line Up Level on Three Saw Horses or Boxes
B
Put in Bolts
C
Trim Ends Even and Drill Holes for Bottom Sppreaders
℄
D
Spread Ends, Put in Bolts and Line Up Center of Spreader with Top Section. Then Put in Upper Cross Pieces.

Fig 8—Method of assembling the A-frame mast on sawhorses.

If the mast is to stand on the ground, a couple of stakes should be driven to keep the bottom from slipping. At this point the mast may be "walked up" by a helper. If it is to go on a roof, first stand it up against the side of the building and then hoist it, from the roof, keeping it vertical. The whole assembly is light enough for two men to perform the complete operation—lifting the mast, carrying it to its permanent berth, and fastening the guys with the mast vertical. It is entirely practical to put up such a mast on a flat area of roof that would be too small to erect a regular tower installation, one that had to be raised vertically on the same spot.

TV Mast Material

TV mast is available in 5- and 10-foot lengths, $1^1/_4$ inches diameter, in both steel and aluminum. These sections are crimped at one end to permit sections to be joined together. A form that is usually more convenient is the telescoping mast available from many electronic supply houses. The masts may be obtained with three, four or five 10-foot sections, and come complete with guying rings and a means of locking the sections in place after they have been extended. These masts are inherently more suitable for guyed mast installations than the non-telescoping type because the diameters of the sections increase toward the bottom of the mast. For instance, the top section of a 50-foot mast is $1^1/_4$ inches diameter, and the bottom section is $2^1/_2$ inches diameter.

Guy rings are provided at 10-foot intervals, but guys may not be required at every point. Guying is essential at the top and at least one other place near the center of the mast. If the mast has any tendency to whip in the wind, or to bow under the load of a horizontal wire antenna, additional guys should be added at the appropriate points.

MAST GUYING

Three guy wires in each set are usually adequate for a mast. These should be spaced equally round the mast. The required number of sets of guys depends on the height of the mast, its natural sturdiness (or stiffness), and the required antenna tension. A 30-foot-high mast usually requires two sets of guys, and a 50-foot mast needs at least three sets. One guy of the top set should be anchored to a point directly opposing the force exerted by the wire antenna. The other two guys of the same set should be spaced 120° with respect to the first, as shown in the inset in Fig 7.

Generally, the top guys should be anchored at distances from the base of the mast at least 60% of the mast height. The distance of the guy anchors from the mast determines the guy loads and the vertical load compressing the mast. At a 60% distance, the load on the guy wire opposite the wire antenna is approximately twice the antenna tension. The compression in the mast will be 1.66 times the antenna tension. With the anchors out 80% of the mast height, the guy tension will be 1.6 times larger than the antenna load and the mast compression will be 1.25 times larger.

Whenever possible, the largest available anchor spacing should be used. The additional compression on the mast, due to closer anchor spacing, increases the tendency of the mast to buckle. Buckling occurs when the compression on the unsupported spans between guys become too great for the unsupported length. The section then bows out laterally and will usually fold over, collapsing the mast. Additional sets of guys reduce the tendency for the mast to buckle under the compression by decreasing the unsupported span lengths and stabilizing the mast, keeping it in a straight line.

A natural phenomenon, called *vortex shedding*, can occur when the wind passes over the sections of a guyed mast. For every section size, shape, and length, there is a wind speed that can cause the sections to oscillate mechanically. When all the sections of an antenna support mast are close to the same size and length, it is possible for all of the mast sections to vibrate simultaneously between the guys. To reduce the potential for this, you can place the guys at locations along the mast that will result in different span lengths. This creates different mechanical resonant frequencies for each span, eliminating the possibility of all sections oscillating at the same time.

When determining the guy locations along the mast to treat this problem, you also need to consider the mast buckling requirements. Since the compression in the mast is greatest in the bottom span, and the least in the top span, the guys should be placed to make the bottom span the shortest and the top span the longest. A general guide for determining the different span lengths is to make the unguyed lengths change by 10 to 20%.

Example: For a 30-foot high mast with three guy sets, the equal-guy locations would be every 10 feet. We can make the center span, 10 feet long, and then make the lower span 15% shorter and the top span 15% longer. While this is not an exact technical method to determine the best solution, the approach will create different mechanical resonant frequencies for the spans, with the span lengths approximately adjusted for the varying buckling requirements.

You can eliminate electrical resonance from conductive guy materials that might cause distortion of the antenna radiation pattern by breaking each guy into nonresonant lengths using strain insulators (see **Figs 9** and **10**). This subject is covered in detail later in this chapter.

Guy Material

When used within their safe load ratings, you may use any of the halyard materials listed in Chapter 20 for the mast guys. Nonmetallic materials have the advantage that there is no need to break them up into sections to avoid unwanted resonant interactions. All of these materials are subject to *stretching*, however, which causes mechanical problems in permanent installations. At rated working loads, dry manila rope stretches about 5%, while nylon rope stretches about 20%. Usually, after a period of wind load and wet/dry cycles, the lines will become fairly stable and require less frequent adjustment.



Fig 9—Simple lever for twisting solid guy wires when attaching strain insulators.



Fig 10—Stranded guy wire should be attached to strain insulators by means of standard cable clamps made to fit the size of wire used.

Solid galvanized steel wire is also widely used for guying. This wire has approximately twice the load ratings of similar sizes of copper-clad wire, but it is more susceptible to corrosion. Stranded galvanized wire sold for guying TV masts is also suitable for light-duty applications, but is also susceptible to corrosion. It is prudent to inspect the guys every six months for signs of deterioration or damage.

Guy Anchors

Figs 11 and **12** show two different kinds of guy anchors. In Fig 11, one or more pipes are driven into the ground at right angles to the guy wire. If a single pipe proves to be inadequate, another pipe can be added in tandem, as shown, and connected with a galvanized steel cable. Heavy-gauge galvanized pipe is preferred for corrosion resistance. Steel fence posts may be used in the same manner. Fig 12 shows a *dead-man* type of



Fig 11—Driven guy anchors. One pipe is usually sufficient for a small mast. For added strength, a second pipe may be added, as shown.



Fig 12—Buried *dead-man* guy anchor (see text).

anchor. The buried anchor may consist of one or more pipes 5 or 6 feet long, or scrap automobile parts, such as bumpers or wheels. The anchors should be buried 3 or 4 feet in the ground. The cable connecting the dead-man to the guys should be galvanized wire rope, like EHS guy cable. You should coat the buried part of the cable with roofing tar, and thoroughly dry it prior to burial to enhance resistance to corrosion.

Also available are some heavy auger-type anchors that screw into the earth. These anchors are usually heavier than required for guying a mast, although they may be more convenient to install. You should conduct annual inspections of the anchors by digging several inches below grade around the anchor to inspect for corrosion.

Trees and buildings may also be used as guy anchors if they are located appropriately. Care should be exercised, however, to make sure that the tree is of adequate size and that any fastening to a building can be made sufficiently secure.

Guy Tension

Many troubles encountered in mast guying are a result of pulling the guy wires too tight. Guy-wire tension should never be more than necessary to correct for obvious bowing or movement under wind pressure. Approximately 10% to 15% of the working load is sufficient. In most cases, the tension needed does not require the use of turnbuckles, with the possible exception of the guy opposite a wire antenna. If any great difficulty is experienced in eliminating bowing from the mast, the guy tension should be reduced or additional sets of guys are required. The mast should be checked periodically, especially after large wind events, to ensure the guys and anchors have not stretched or moved, allowing the mast to get away from the required straight alignment.

ERECTING A MAST OR OTHER SUPPORT

Masts less than 30 feet high usually can be simply walked up after blocking the bottom end securely. Blocking must be done so that the base can neither slip along the ground nor upend when the mast is raised. An assistant should be stationed at each guy wire, and may help by pulling the proper guy wire as the mast nears the vertical position. Halyards can be used in the same manner.

As the mast is raised, it may be helpful to follow the underside of the mast with a scissors rest (**Fig 13**), should a pause in the hoisting become necessary. The rest may also be used to assist in the raising if an assistant mans each leg.

As the mast nears the vertical position, those holding the guy wires should be ready to temporarily fasten the guys to prevent the mast from falling. The guys can then be adjusted until the mast is perfectly straight.

For masts over 30 feet long, a *gin pole* of some form may be required, as shown in Fig 13. Several turns of



Fig 13—Pulling on a gin line fastened slightly above the center point of the mast and on the halyards can assist in erecting a tall mast. The tensions should be just enough to keep the mast in as straight a line as possible. The "scissors" may be used to push on the under side and to serve as a rest if a pause in raising becomes necessary.

rope are wound around a point on the mast above center. The ends of the rope are then brought together and passed over a tree limb. The rope should be pulled as the mast is walked up to keep the mast from bending at the center. If a tree is not available, a post, such as a 2 × 4, temporarily erected and guyed, can be used. After the mast has been erected, the assisting rope can be removed by walking one end around the mast (inside the guy wires).

Telephone poles and towers are much sturdier supports. Such supports may require no guying, but they are not often used solely for the support of wire antennas because of their relatively high cost. For antenna heights in excess of 50 feet, however, they are usually a most practical form of support.

Tower And Antenna Selection and Installation

The selection of a tower, its height, and the type of antennas and rotator is probably one of the more complex issues faced by station builders. All aspects of the tower, antenna, and rotator system are interrelated, and you should consider the overall system before making any decisions regarding specific system components.

Perhaps the most important consideration for many amateurs is the effect of the antenna system on the surrounding environment. If plenty of space is available for a tower installation and if there is little chance of causing esthetic distress on the part of family members or the neighbors, the amateur is indeed fortunate. Often, the primary considerations are purely financial. For most, however, the size of the property, the effect of the system on others, local ordinances, and the proximity of power lines and poles influence the selection of the tower/antenna system considerably.

The amateur must consider the practical limitations for installation. Some points for consideration are given below:

1) A tower should not be installed in a position where it could fall onto a neighbor's property.
2) The antenna must be located in such a position that it cannot possibly tangle with power lines, either during normal operation or if the structure should fall.
3) Sufficient yard space must be available to position a guyed tower properly. The guy anchors should be between 60% and 80% of the tower height in distance from the base of the tower on level ground—sloping terrain may require larger areas.
4) Provisions must be made to keep children from climbing the support. (Poultry netting around the tower base will serve this need.)
5) Local ordinances should be checked to determine if any legal restrictions affect the proposed installation.

Other important considerations are (1) the total dollar amount to be invested, (2) the size and weight of the antenna desired, (3) the climate, and (4) the ability of the owner to climb a fixed tower.

Most tower manufacturers provide catalogues or data packages that represent engineered tower configurations. These are provided as a convenience for users to help determine the most suitable tower configurations. The most commonly used design specifications for towers are EIA (Electronic Industries Assoc.) RS-222 and UBC (Uniform Building Code). These specifications define how the tower, antenna, and guy loads are determined and applied to the system, and establish general design criteria for the analysis of the tower. Local authorities often require the review and approval of the installation by a state licensed Professional Engineer (P.E.) to obtain building permits. All local authorities in the United States do not subscribe to the same design standards, so often the manufacturers' general-purpose engineering is not applicable.

One of the first things you need to determine in the tower selection process is the type of specification required by the local authorities, if any. Then, you must determine the *Basic Wind Speed* appropriate for the site. The *Basic Wind Speed* used in most specifications is the average wind speed for one mile of wind passing across the structure. It will be a lower value than the peak readings from an anemometer (wind gauge) installed at the site. For example, a Basic Wind Speed of 70 mph could have a maximum value of 80 mph and a minimum of 60 mph, equally distributed during the passage of the mile of wind. Basic wind speeds can be found in tables or maps contained in the appropriate specifications. Often, the basic wind speed used for the location may be obtained from the local permit authority. Check out the Web site at **www.championradio.com**, which contains EIA basic wind speed tables for every county in the USA. UBC speeds are available at almost every local library.

Antenna manufacturers also provide antenna data to assist in the selection process. Unfortunately, antenna mechanical designs do not always follow the same design standards used for towers. Proper antenna selection often means that you must determine the antenna surface areas yourself to avoid overloading the tower. More discussion about this follows later in this chapter.

It is often very helpful to the novice tower installer to visit other local amateurs who have installed towers. Look over their hardware and ask questions. If possible, have a few local experienced amateurs look over your plans—before you commit yourself. They may be able to offer a great deal of help. If someone in your area is planning to install a tower and antenna system, be sure to offer your assistance. There is no substitute for experience when it comes to tower work, and your experience there may prove invaluable to you later.

THE TOWER

Towers for supporting antennas come in a variety of different types. Each type has its own set of benefits and limitations, or conditions and requirements. Often, you can choose a particular tower type by considering issues other than pure mechanical performance. Understanding how each type of tower functions, and what its respective requirements are, are the first steps in making the best tower selection for your own situation.

Guyed Towers

The most common variety of tower is the *guyed tower* made of identical stacked sections, supported by guy cables attached to ground anchors placed symmetrically around the tower. These towers are the most economical, in terms of feet per dollar investment, and are more efficient for carrying antenna loads than non-guyed towers.

The guys resist the lateral loads on the system created by the wind. Since the guys slope down to the ground, horizontal loads due to the wind result in vertical loads applied to the tower at each tower/guy connection. The tower becomes a compression member, trying to resist the column compression generated by the guy reactions. A tower in compression can buckle, so the distance between guy connections along the tower is important.

Tower Bases for Guyed Towers

Another important phenomenon in a guyed tower is stretching of the guy cables. All guys stretch under load and when the wind blows the elongated guys allow the tower to lean over somewhat. If the tower base is buried in the concrete footing—as is commonly done in amateur installations—the bending stress at the tower base can become a significant factor. Towers that have been installed with tapered pier-pin bases much more freely absorb tower leaning, and they are far less sensitive to guy-elongation problems.

The tapered pier-pin tower installation is not without some drawbacks. These installations often require torque-arm guy brackets or six-guy torque-arm assemblies to control tower rotation due to antenna torque. They also require temporary guys when they are being installed to hold the base steady until the permanent guys are mounted. Some climbers also don't like the flexing when they start to climb these types of towers.

On the positive side, pier-pin base towers have all structural members above the concrete footing, eliminating concerns about hidden corrosion that can occur with buried towers. Most decisions regarding the type of base installation are made according to the preference of the tower builder/maintainer. While either type of base configuration can be successfully used, you would be wise to do the stress calculations (or have a professional engineer do them) to ensure safety, particularly when large antenna loads are contemplated and particularly if guys that can easily stretch are used, such as Phillystran guys.

The configuration shown in **Fig 14A** is taken from an older (1983) Unarco-Rohn catalog. This configuration has the top set of guys placed at the top of the tower with the lower set halfway up the tower. This configuration is best for most amateur installations, which usually have the antennas mounted on a rotatable mast extending



Fig 14—The proper method of installation of a guyed tower. At A, the method recommended for most amateur installations. At B, the method shown in later Rohn catalogs. This places considerable strain on the top section of the tower when large antennas are mounted on the tower.

out the top of the tower—thereby placing the maximum lateral loads when the wind blows at the top of the tower (and the bottom of the rotating mast).

The configuration shown in Fig 14B is from a newer (1998) Rohn catalog. It has 5 feet of unsupported tower extending above the top guy set. The lower guy set is approximately halfway between the top guys and the base. The newer configurations are tailored for commercial users who populate the top region of the tower with fixed arrays and/or dishes. The installation in Fig 14B cannot safely withstand the same amount of horizontal top load as can the configuration shown in Fig 14A, simply because the guys start farther down from the top of the tower.

An overhead view of a guyed tower is given in Fig 14C. Common practice is to use equal angular spacings of 120° between guy wires. If you must deviate from this spacing, the engineering staff of the tower manufacturer or a civil engineer should be contacted for advice.

Amateurs should understand that most catalogs show generic examples of tower configurations that work within the cited design specifications. They are by no means the only solution for any specific tower/antenna configuration. You can usually substantially change the load capability of any given tower by varying the size and number of guys. Station builders are encouraged to utilize the services of professional engineers to get the most out of their guyed towers. Those interested in more generic information about guyed tower behavior can find it at **www.freeyellow.com/members3/yagistress/**.

Unguyed Towers

Another commonly used type of tower is not normally guyed—these are usually referred to as *freestanding* or *self-supporting* towers. Unguyed towers come in three different styles.

One style is comprised of stacked lengths of identical tower sections, just like those used for guyed towers. The only difference is that no guys are used. Manufacturers provide the recommended configurations and allowable loads for this type of installation in their catalogs. Unguyed towers are vastly less capable of supporting antenna loads than their guyed counterparts, but have great utility for light-duty applications—when configured within their capabilities.

The second style utilizes different tower section sizes, varying from large sections at the base and tapering down to smaller sections at the top. This style is more much more efficient for freestanding applications, because the tower is sized for the varying bending loads along the tower length, and is shown in **Fig 15**.



Fig 15—Typical freestanding (unguyed) tower. Arrows indicate the directions of the forces acting upon the structure. See text for discussion.

The third style of unguyed towers is commonly called a *crank-up tower*. It is a freestanding tower with telescoping sections that can be extended or retracted with a winch, cable, and pulley mechanism. This allows the tower to be raised and lowered for maintenance and antenna work. It is usually necessary to retract such towers for moderate to heavy winds. Some consider this a disadvantage because they can't operate their antennas at full height when it is windy. Two different forms of the crank-up style, freestanding tower are shown in **Fig 16**. Fig 16A shows the tubular version; Fig 16B shows the triangular space-frame version.

Some crank-up towers are used with guys and are only retracted for maintenance and antenna work. These towers are specially designed with locking mechanisms between the tower sections to carry the vertical compression created by the guys. *Do not* use guys with normal crank-up towers (those that have no locking devices between sections)! The increased tower compression will be carried by the hoisting cable, which will eventually cause it to fail.

Never climb a crank-up tower unless it is properly nested, with all load removed from the hoisting cable. For general antenna work, this can be accomplished by completely retracting it until the cable becomes loose. When servicing the rotator, the tower must be left partially extended. In this case every tower section must be

Fig 16—Two examples of *crank-up* towers.





Fig 17—Fold-over or tilting base. There are several different kinds of hinged sections permitting different types of installation. Great care should be exercised when raising or lowering a tilting tower.

blocked with heavy timber or thick-wall tubes, installed through the tower bracing, until all sections are resting on the blocks and the hoisting cable becomes slack. Safely installing the blocks in an extended crank-up tower can be challenging. The object is to get all the blocks installed without a climber having to scale the unblocked tower, risking loss of limbs should the hoisting cable fail. An extension ladder, capable of reaching the required block elevations is the safest approach. If the necessary equipment or expertise is not available, the tower can be retracted, antennas removed, and leaned over, with the base tilt-over assembly, before extending it to access the rotator. Failure to properly block the tower before climbing can result in serious injury should the cable slip or break!

All freestanding towers share some unique characteristics. Each must support antenna and tower loads only by virtue of the bending strength of the tower sections and the tower footing connection to earth. Because of the large overturning moment at the tower base, freestanding towers require larger concrete footings than guyed towers. They are usually more expensive for the same load capability compared to guyed towers, simply because they require larger heavier tower sections and a larger footing to get the job done. The telescoping mechanisms in crank-up tower require more maintenance too.

Freestanding towers are quite popular, and are often the best solutions for sites with limited space and ascetic concerns. When cranked down, a telescoping tower can maintain a low-profile system, out of sight of the neighbors and family.

Tilt-Over Towers

Some towers have another convenience feature—a hinged section that permits the owner to fold over all or a portion of the tower. The primary benefit is in allowing antenna work to be done close to ground level, without the necessity of removing the antenna and lowering it for service. **Fig 17** shows a hinged base used with stacked, guyed tower sections. The hinged section can be designed for portions of the tower above the base. These are usually referred to as *guyed tilt-over towers*, where a conventional guyed tower can be tilted over for installing and servicing antennas. Many crank-up towers come with optional tilt-over base fixtures that are equipped with a winch and cable system for tilting the fully nested tower from horizontal to vertical positions.

Misuse of hinged sections during tower erection is a dangerously common practice among radio amateurs. Unfortunately, these episodes can end in accidents. If you do not have a good grasp of the fundamentals of physics, it might be wise to avoid hinged towers or to consult an expert if there are any questions about safely installing and using such a tower. It is often far easier (and safer) to erect a regular guyed tower or self-supporting tower with gin pole and climbing belt than it is to try to walk up an unwieldy hinged tower.

The AB-577 Military Surplus Tower

Another light duty tower has found acceptance among many amateurs. Available from assorted military surplus dealers is the AB-577 system. This was designed to be a portable, rapid deployment antenna support for field communications. It is a guyed mast that goes up somewhat like a crank-up. The system consists of several short sections of aluminum tubing, with special end connections for joining them. These can be erected from the base fixture, which has a crank-up type winch-driven elevator platform. The tubing sections are installed in the base fixture and connected to the section above it with an over-center locking *Marmon*-style clamp. Then, the elevator platform is raised with the winch and the new tube is locked in place, high on the base fixture. Then the elevator is lowered to accept the next section. While the tower is extended, the supporting guys are adjusted via the unique *snubber* assemblies at the anchor connection. One person can erect this system, even in windy conditions, when special care is given to keeping the guys properly adjusted during each extension.



Fig 18—Installation of surplus AB-577 tower with tribander at 45 feet at K7NV. (*Photo by Kurt Andress, K7NV.*)

The standard AB-577 system, with 3 sets of guys, will support a modest triband Yagi at 45 feet. **Fig 18A** shows an installation with a Hy-Gain TH7DX at 45 feet.

TOWER BASES

Tower manufacturers can provide customers with detailed plans for properly constructing tower bases. **Fig 19** is an example of one such plan. This plan calls for a hole that is $3\frac{1}{2} \times 3\frac{1}{2} \times 6$ feet. Steel reinforcement bars are lashed together and placed in the hole. The bars are positioned so that they will be completely embedded in the concrete, yet will not contact any metallic object in the base itself. This is done to minimize the possibility of a direct discharge path for lightning through the base. Should such a lightning discharge occur, the concrete base could be damaged.


30"
30"
2"
21"
21"
21"
2"
Base Assembly
Base Flange
16"
No.4 Re-Bar Hoops (4) -Wired to Verticals
2" X 4" Spacer Tacked to Template
No.6 Re-Bar Verticals (4)
Anchor Bolt Template 3/4" Plywood
Re-Bar Framework
Anchor Bolts 1" - 8 UNC X 36" (WT-352)
Hex Nut 1" - 8 UNC (WT-353)
1/2"
2" X 4" Spacer
2" X 4" Form
Crown
3" - 4"
Concrete
3-1/2' X 3-1/2' x 6' Deep Hole (Normal Soil)
Piers (Dirt, Rocks, Etc.)

Fig 19—Plans for installing concrete base for Wilson ST-77B tower. Although the instructions and dimensions vary from tower to tower, this is representative of the type of concrete base specified by most manufacturers.

Providing suitable paths for the discharge of lightning energy safely for towers is a complex subject. Several companies offer products and guidance. The basic requirements for providing controlled discharge paths for lightning-induced current is to supply a low-impedance grid of conductors from the tower and feed lines to a field of interconnected ground rods around the base of the tower. Generally, the tower, station, and electrical service grounds need to be connected to prevent damaging potential differences from developing between the various components in the system.

A strong wooden form is constructed around the top of the hole. The hole and the wooden form are filled with concrete so that the resultant block will be 4 inches above grade. The anchor bolts are embedded in the concrete, and aligned with the plywood template, before it hardens. The template serves to align the anchor bolts to properly mate with the tower itself. Once the concrete has



Fig 20—Another example of a concrete base (Tri-Ex LM-470).

cured, the tower base is installed on the anchor bolts and the base connection is adjusted to bring the tower into vertical alignment.

For a tower that bolts to a flat base plate mounted to the footing bolts (as shown in Fig 19), you can bolt the first tower section on the base plate to ensure that the base is level and properly aligned. Use temporary guys to hold things exactly vertical while the concrete cures. (The use of such temporary guys also works well when you place the first tower section in the base hole and plumb it vertically before pouring in the concrete.) Manufacturers can provide specific, detailed instructions for the proper mounting procedure. **Fig 20** shows a slightly different design for a tower base.

The one assumption so far is that *normal* soil is predominant in the area in which the tower is to be installed. Normal soil is a mixture of clay, loam, sand and small rocks. More conservative design parameters for the tower base should be adopted (usually, using more concrete) if the soil is sandy, swampy or extremely rocky. If there are any doubts about the soil, the local agricultural extension office can usually provide specific technical information about the soil in a given area. When this information is in hand, contact the engineering department of the tower manufacturer or a civil engineer for specific recommendations with regard to compensating for any special soil characteristics.

TOWER INSTALLATION

The installation of a tower is not difficult when the proper techniques are used. A guyed tower, in particular, is not hard to erect, because each of the individual sections is relatively lightweight and can be handled with only a few helpers and some good quality rope.

The Gin Pole and Tips on Tower Building

An essential piece of hardware for working on towers is a *gin pole*. This section came from the ARRL book *Simple and Fun Antennas for Hams*. The dictionary describes a gin pole as “a device for moving heavy objects.” See **Fig 21**, which shows a drawing of the Rohn “Erection Fixture” EF2545. This gin pole was designed to work with the nominal 10-foot long sections of Rohn 25 or 45 towers.

We’re going to assume in the following discussion that you are installing Rohn 45, which weighs about 70 pounds. This is a lot of weight, and you must refrain from adding to that during installation. That means, for example, that you *do not* attempt to lift a 10-foot section with the guy wires attached! Neither should you attempt to lift the top section with the rotator and rotor shelf installed. The gin pole (and your ground crew) will not appreciate all that strain.

The main working part of the gin pole is the pulley



Fig 21—Drawing of Rohn “Erection Fixture” EF2545, also known commonly as a “gin pole.”

mounted at the top of the 12-foot long heavy-wall aluminum tubing. This pulley has a rope going down to the ground crew through the center of the aluminum tube. At the base of the tower, the pull rope should be run through a *snatch block* attached to the tower just above ground level. This block allows the pull rope to be pulled out horizontally away from the tower base. That helps protect ground crew should a tool be dropped by the people on the tower.

An adjustable, sliding clamp towards the bottom of the aluminum tubing is clamped to the tower using a swinging L-bracket-type clamp with two clamping bolts. These have T-bar handles that can be tightened by hand. In fact, this gin pole can be moved and deployed without any tools. The clamp is positioned on the top of the tower section onto which the next tower section is to be installed. Once clamped to the top of the tower, you would loosen the T-bar handle that tightens the clamp against the sliding aluminum tube and slide the tubing up to its maximum extent.

In practice, the following steps are taken as each 10-foot section of tower is installed, one-by-one. We're assuming here that the gin pole starts out on the ground, with at least one person belted in at the top of the tower. We're also assuming that the pull rope has been threaded through the aluminum tube and the top pulley, with a knot tied to prevent it from falling back down the tube.

1. The clamp holding the aluminum tubing is loosened so that the pulley on the tube can be lowered to where it is just above the bottom clamp. Then the T-bar handle for the tube clamp is tightened.
2. The climber lowers a tag rope for the ground crew to tie to the gin-pole pull rope. (This tag rope has been looped through a temporary pulley clipped to the top of the tower. It is also used to pull up tools and other materials.) The ground crew then pulls the gin pole up to the climber, using the tag line rope. Friction of the rope against the top of the pulley-head assembly will prevent the gin-pole assembly from slipping down. [Note that some climbers prefer to "walk" the gin-pole up the tower rather than having it pulled up from the ground below. They free up their hands for climbing and temporarily holding the gin pole by using their belt lanyard looped around the tower as they climb.]
3. Once the gin-pole head reaches the top of the tower, the climber clamps the gin pole clamp securely to the top of the tower.
4. The T-bar handle for the tube clamp is loosened, and the aluminum tube is extended to its maximum height, as shown in Fig 21. Make sure you have tied the free end of the rope coming through the top pulley temporarily to the top of the tower, or else you'll have to lower the gin pole and go through this step again.
5. The free end of the pulley rope is then dropped to the ground, often using a weight such as a medium Crescent wrench or perhaps a hammer to keep the rope from waving about as it dangles down the tower, tangling with every imaginable thing as it proceeds downwards. It's amazing how even a tiny breeze can make an unweighted rope dance like that.
6. The ground crew then ties the free end of the rope *above* the balance point of the tower. For Rohn 25 or 45 there are eight horizontal cross braces per section. You want the crew to tie the rope to the fifth horizontal brace from the bottom. Please remember that you want the bottoms of the tower sections' legs to be pointed downwards, not flipped over, when the bottom of these legs approach you at the top of the tower section the climber is standing on.
7. Once the bottom of the rising tower section is just above the top of the legs of the bottom tower section, the climber guides the tower down onto the top of the three legs, while calling out to the ground crew instructions about *slowly lowering* the new section down onto the legs. See **Fig 22**, which shows the climber guiding the new section of Rohn HBX tower onto the previous section's legs. This process is considerably easier to accomplish if each section of tower has been put together on the ground to make sure that the legs fit together easily. There's nothing more frustrating that trying to manually force-fit tower sections together at the top of a tower.



Fig 22—Climber is guiding the new section onto the top of the existing one. The gin pole attached to the left leg is bearing the weight, as the climber gives verbal instructions to the ground crew pulling on the gin-pole rope. (*Photo courtesy Mike Hammer, N2VR.*)

It seems that freight companies don't always handle heavy tower sections very gently and legs easily get bent out of alignment. A careful installer numbers tower sections in the order they've been test-fitted together on the ground, marking them with a laundry marker pen. You should also spray a small amount of WD-40 up inside mating tower legs after test-assembling them to help prevent galling and to ease fitting sections together. [Don't do this to excess—WD-40 is slippery and messy when it runs out of the bottom of tower legs.]

Another caution: Make sure before you start installing any tower that the correct ends of the bottom section's legs, "male" rather than "female," are pointed upwards. A prominent amateur (who will go unnamed) had to have Rohn make and send him a special "gender-bender" flange to turn females into males, since he had installed the base upside-down in the concrete base. You don't want to do that.

8. Once the new tower section has been guided down onto the male ends, the six pinning bolts are inserted and tightened with nuts. Note that Rohn uses two different sized bolts, with the larger diameter one on the bottom.
9. If this section of tower is one where guy wires are to be placed, they can be brought up using the gin pole rope and positioned on the tower. The maximum spacing for Rohn 25 is 30 feet between guy-wire sets, and 40 feet for Rohn 45. Thirty feet of unguyed Rohn 25 tower is wobbly, though safe. Many installers prefer to come down off the tower when setting guy-wire tension, since they do not like to be on a wobbly tower when the ground crew is moving around yanking on guy wires. Many also greatly prefer working on Rohn 45 tower, which is substantially more secure feeling and easier to stand on, with its legs 18 inches apart, while Rohn 25 legs are only 12 inches apart.
10. Finally, you reposition the gin pole for the next section of tower. The T-bar at the clamp is loosened, the tube is dropped down to the level of the clamp, and the climber walks the gin pole up to the top of the section just installed and clamps it there, ready to pull up the next tower section.

Tower Safety

One of the most important aspects of any tower installation project is the safety of all persons involved. See Chapter 1 for details on important safety issues. The use of hard hats is highly recommended for all assistants helping from the ground. Helpers should always stand clear of the tower base to prevent being hit by a dropped tool or hardware. Each person working on the tower must use a good climber's safety belt.

When climbing the tower, if more than one person is involved, one should climb into position before the other begins climbing. The same procedure is required for climbing down a tower after the job is completed. The purpose is to have the non-climbing person stand still so as not to drop any tools or objects on the climbing person, or unintentionally obstruct his movements. When two persons are working on top of a tower, only one should change position (unbelt and move) at a time.

For most installations, a good-quality 1/2-inch diameter Manila hemp rope can adequately handle the workload for the hoisting tasks. The rope must be periodically inspected to assure that no tearing or chafing has developed, and if the rope should get wet from rain, it should be hung out to dry at the first opportunity. The knots used for connecting hoisting lines and hardware are critical to executing any safe installation, and special attention should be given to this detail for any work party.

Here is an important point regarding safety—the person who climbs the tower should be in charge of what happens with the ground crew. Not only does the person on the tower have a better overall view of the situation below, but also any confusion on the ground can result in serious injury to the climber.

GUY WIRES

In typical guyed tower installations, guy wires may experience loads in excess of 1000 pounds. Since the guys are the primary means of carrying the horizontal wind loads, great care should be taken in their selection and installation.

Guys come in a variety of materials and constructions. Normally, the tower manufacturer or professional engineer will specify the size and type of cable to be used. The most common type of cable used for tower guying is the EHS (Extra High Strength) galvanized steel cable. The EHS cables are very stiff and are the highest strength

Table 1
Guy Cable Comparisons

Cable	*Nominal Dia. Inches*	*Breaking Strength Lbs*	*Weight Lbs/100'*	*Elongation Inches/100'*	*%Elongation*
3/16" 1 × 7 EHS	0.188	3990	7.3	6.77	0.56%
1/4" 1 × 7 EHS	0.250	6700	12.1	3.81	0.32%
HPTG6700	0.220	6700	3.1	13.20	1.10%
HPTG8000	0.290	8000	3.5	8.90	0.74%
5/16" 1 × 7 EHS	0.313	11200	20.5	2.44	0.20%
HPTG11200	0.320	11200	5.5	5.45	0.45%
3/8" Fiberglass Rod	0.375	13000	9.7	5.43	0.45%

EHS steel cable information is taken from ASTM A 475-89, the industry standard specification for steel wire rope. The HPTG listings are for *Phillystran* aramid cables, and are based on the manufacturers' data sheets. The elongation (stretch) values are for 100 feet of cable with a 3000-pound load.

cables in the wire rope family. Other steel cables are made to be more flexible for running around pulleys. While these are easier to work with when assembling, they are not as strong as the EHS type, and should be avoided for tower guying. Non-conductive guys, such as *Phillystran* or *pultruded* fiberglass rod have become popular for eliminating resonant interaction with antennas.

Do not attempt to use cheaper cables that don't meet or exceed the criteria for those specified for your installation. Using the wrong cable, or failing to install the cable properly can have disastrous results! **Table 1** shows data for several cables commonly used for tower guying. It is important to note that the minimum breaking strength of the various cables are independent of their elongation (stretch) under load.

Guy Cable Installation

Figs 23 and **24** show methods for tensioning and safety wiring guy-wire turnbuckles. **Fig 25** shows the traditional method for fixing the end of a steel guy wire. A thimble is used to prevent the wire from breaking because of a sharp bend at the point of intersection. Conventional wisdom strongly recommends the use of thimbles that are at least one wire size larger than the cable to provide a more gentle wire bend radius. Three cable clamps follow to hold the wire securely. Be sure to follow the note in Fig 25 for which part of the clip bears against the live (loaded) cable. As a final backup measure, the individual strands of the free end are unraveled and wrapped around the guy wire. It is a lot of work, but it is necessary to ensure a safe and permanent connection.

Fig 26 shows the use of a device that replaces the clamps and twisted strands of wire. These devices are known as *dead ends*, *preformed guy grips,* or *Big Grips* and are commonly used on electrical power poles. They are far more convenient to use than are clamps, and are the recommended method for terminating Phillystran and



Fig 23—Proper tension can be placed on the guy wires with the aid of a block-and-tackle system. (*Photo by K1WA*)



Fig 24—A length of guy cable is used to assure that the turnbuckles remain in place after they are tightened. This procedure is an absolute requirement in guyed tower systems. (*Photo by N4QX*)



Fig 25—Traditional method for securing the end of a guy wire.



Fig 26—Alternative method for attaching guy wires using *dead ends.* The dead end on the right is completely assembled (the end of the guy wire extends beyond the grip for illustrative purposes). On the left, one side of the dead end is partially attached to the guy wire. In front, a thimble is used where a sharp bend might cause the guy wire or dead end to break.

fiberglass-rod guys. When using the guy grips, it is imperative that the recommended end sleeves are installed over the free end of the grip to prevent ice and falling hardware from sliding down the guy and unraveling the grip connection to the guy. The guy wires must be cut to the proper length. The dead end of each wire is installed into the object to which the guy wire is being attached (use a thimble, if needed to eliminate sharp cable bends). One side of the dead end is then wrapped around the guy wire. The other side of the dead end follows. Using dead ends saves time and trouble, more than making up for their slightly higher cost.

When using the non-conductive guy materials, it is highly recommended that a 25-foot length of EHS steel cable be used at the bottom for connection to the anchor. This serves a valuable purpose. The steel cable is more resistant to damage from ground activity and brush fires, and it is the preferred material for measuring cable pre-tension with commonly available devices.

Fig 27 shows two different methods for attaching guy wires to towers. At Fig 27A, the guy wire is simply looped around the tower leg and terminated in the usual manner. At Fig 27B, a *guy bracket*, with *torque arms* has been added. Even if the torque arms are not required, it is preferred to use the guy bracket to distribute the load from the tower/guy connection to all three tower legs, instead of just one. The torque bracket is more effective resisting torsional loads on the tower than the simpler installation. Rohn offers another guy attachment bracket, called a *Torque Arm Assembly*, that allows six guys to be connected between the bracket and anchors. This is by far the best method of stabilizing a tower against high torque loads, and is recommended for installations with large antennas.

There are two types of commonly used guy anchors. **Fig 28A** depicts an *earth screw*. These are usually 4 to 6 feet long. The screw blade at the bottom typically measures 6 to 8 inches diameter. Fig 28B illustrates two people installing the anchor. The shaft is tilted so that it will be in line with the mean angle of all the guys connecting to the anchor. Earth screws are suitable for use in normal soil where permitted by local building codes. Information about *screw anchors* is available from the manufacturers of these devices. Information from a supplier specializing in this type of anchor can be found at **www.abchance.com**.

The alternative to earth screws is the concrete block anchor. Fig 28C shows the installation of this type of anchor; it is suitable for any soil condition, with the possible exception of a bed of lava rock or coral. Consult the instructions from the manufacturer, or your tower designer, for the precise anchor configuration.

Turnbuckles and associated hardware are used to attach guy wires to anchors and to provide a convenient method for adjusting tension. **Fig 29A** shows a turnbuckle with a single guy wire attached to the eye of the anchor. Turnbuckles are usually fitted with either two eyes, or one eye and one jaw. The eyes are the oval ends, while the jaws are U-shaped with a bolt through each tip.



Fig 27—Two methods of attaching guy wires to tower. See text for discussion.



Fig 28—Two standard types of guy anchors. The earth screw shown at A is easy to install and widely available, but may not be suitable for use in certain soils. The concrete anchor is more difficult to install properly, but it is suitable for use with a wide variety of soil conditions and will satisfy most building code requirements.


(A)
(C)
(B)
Cable Clamps-Space Cable Clamps 6 Times Cable Dia Apart.(U Bolt Should Bear on Dead End
Serve Free (Dead) End of Guy at Each Connection
Safety Wire
Turnbuckle
Grip End Sleeve Required on All Grips
Performed Grip (Optional Method of Attachment)
Tension Equalizer
Single Anchor Rod
Use Oversize Thimble When Using Preforms
Cable Clamps
(D)

Fig 29—Variety of means available for attaching guy wires and turnbuckles to anchors.

Fig 29B shows two turnbuckles attached to the eye of an anchor. The procedure for installation is to remove the bolt from the jaw, pass the jaw over the eye of the anchor and reinstall the bolt through the jaw, through the eye of the anchor and through the other side of the jaw.

If two or more guy wires are attached to one anchor, *equalizer plates* should be installed (Fig 29C). In addition to providing a convenient point to attach the turnbuckles, the plates pivot slightly to equalize the various guy loads and produce a single load applied to the anchor. Once the installation is complete, a safety wire should be passed through the turnbuckles in a figure-eight fashion to prevent the turnbuckles from turning and getting out of adjustment (Fig 29D).

All guyed towers require the guys to be installed with a certain amount of pre-tension. The tower manufacturer or designer specifies the required pre-tension values, which are usually 10% of the cable breaking strength. Pre-tension is necessary to eliminate looseness in the cable caused by the spiral wire construction and to eliminate excessive dynamic guy and tower motion under wind loading. The recommended method for adjusting the guys is to use a cable tension-measuring device such as the popular *Loos Guy Wire Tensioner*. The guy is gripped with a special clamp, such as the *Klein Cable Grip*, which is connected to the anchor below the eye (or equalizer plate) with a block and tackle arrangement (Fig 23) or a ratcheting come-along. Then the turnbuckle is adjusted to take up the load, the cable grip is released and the final guy tension is adjusted and checked.

When you adjust the guys at each level, you should check the tower for vertical alignment and straightness. This is often done with a transit from two ground points located 90° from each other.

Resonance in Guy Wires

If guy wires are resonant at or near the operating frequency, they can receive and reradiate RF energy. By behaving as parasitic elements, the guy wires may alter and thereby distort the radiation pattern of a nearby antenna. For low frequencies where a dipole or other simple antenna is used, this is generally of little or no consequence. But at the higher frequencies where a unidirectional antenna is installed, it is desirable to avoid pattern distortion if at all possible. The symptoms of re-radiating guy wires are usually a lower front to back ratio and a lower front to side ratio than the antenna is capable of producing. The gain of the antenna and the feed-point impedance will usually not be significantly affected, although sometimes changes in SWR can be noted as the antenna is rotated. (Of course other conductors in the vicinity of the antenna can also produce these same symptoms.)

The amount of re-radiation from a guy wire depends on two factors—its resonant frequency, and the degree of coupling to the antenna. Resonant guy wires near the antenna will have a greater effect on performance than those that are farther away. Therefore, the upper portion of the top level of guy wires should warrant the most attention with horizontally polarized arrays. The lower guy wires are usually closer to horizontal than the top level, but by virtue of their increased distance from the antenna, are not coupled as tightly to the antenna.

To avoid resonance, the guys should be broken up by means of egg or strain insulators. **Fig 30** shows wire lengths that fall within 10% of $^{1}/_{2}$-λ resonance (or a multiple of $^{1}/_{2}$ λ) for all the HF amateur bands. Unfortunately, no single length greater than about 14 feet avoids resonance in all bands. If you operate just a few bands, you can locate greater lengths from Fig 30 that will avoid resonance. For example, if you operate only the 14-, 21- and 24-MHz bands, guy wire lengths of 27 feet or 51 feet would be suitable, along with any length less than 16 feet.



Fig 30—The black bars indicate ungrounded guy wire lengths to avoid for the eight HF amateur bands. This chart is based on resonance within 10% of any frequency in the band. Grounded wires will exhibit resonance at odd multiples of a quarter wavelength. (*By Jerry Hall, K1TD.*)

THE RIGHT TOWER FOR YOUR ANTENNA

Most manufacturers rate their towers in terms of the maximum allowable antenna load that can safely be carried at a specific wind speed. Ensuring that the specific antennas you plan to install meet the tower's design criteria, however, may not always be a straightforward task.

For most towers, the manufacturer assumes that the allowable antenna load is a horizontal force applied at the top of the tower. The allowable load represents a defined amount of exposed antenna area, at a specified wind velocity. Most tower manufacturers rate the load in terms of *Flat Projected Area* (FPA). This is simply the equivalent area of a flat rectangular surface at right angles to the wind. The FPA is not related to the actual shape of the antenna itself, only its rectangular projected area. Some manufacturers provide separate FPAs for antennas made from cylindrical sections and those made from rectangular sections.

In the realm of antenna manufacturers, however, you may encounter another wind load rating called the *Effective Projected Area* (EPA). This attempts to take into account the actual shape of antenna elements. The problem is that there is no agreed-upon standard for the conversion from EPA to load numbers. Different manufacturers may use different conversion factors.

Since most tower manufacturers have provided FPA figures for their towers—allowing us in effect to ignore design-specification details—it would be easiest for us to work only with FPA values for our antennas. This would be fine, if indeed we had good FPA figures for the specific antennas we plan to use! Unfortunately, FPAs are rarely specified for commercially built amateur antennas. Instead, most antenna manufacturers provide effective areas in their specification sheets. You may need to contact the antenna manufacturer directly for the FPA antenna area or for the antenna dimensions so that you can do your own FPA calculations.

Determining Antenna Areas

The method for determining the flat projected area of an antenna is quite simple. We'll use a Yagi antenna as an example. There are two worst-case areas that should be considered here. The first is the FPA of all the elements when the wind blows in the direction along the boom; that is, at right angles to the elements. The second FPA for a Yagi is when the wind is at right angles to the boom. One of these two orientations produces the worst-case exposed antenna area—all other wind angles present lower exposed areas. The idea is to take the highest of the FPAs for these two wind directions and call that the FPA of the antenna structure. See **Fig 31A**.

The element FPA is calculated by multiplying each element's dimension of length by its diameter and then



Fig 31—Description of how loads are developed on a Yagi. At A, Fr is the resultant force from the wind load on a generalized member. Fd is the load acting downwind (drag) that creates the load on the tower. Fc is the lateral component of the wind load. The term A is the flat projected area (FPA), which is the broadside area normal to the wind. The term P is the wind pressure. At B, Ae is the total element area, while Ab is the total boom area. All the loads due to the wind act normal to the antenna sections—the force on element #1 (Fe1) acts along the axis of the boom, for example. At C, a plot of the *effective FPA* as a function of the azimuthal wind direction for a Yagi, ignoring drag coefficients. The Yagi in this example has 9.0 square feet of element FPA and 6.0 square feet of boom FPA. The worst-case FPAs occur with the beam pointed in the wind and with the boom broadside to the wind. To determine the actual tower loading, the actual drag coefficients and wind pressures must be used.

summing the FPAs for all elements. The boom's FPA is computed by multiplying the boom's length by its diameter.

The reason for considering two potential peak-load orientations becomes clear when different frequency antennas are stacked on a mast or tower. Some antennas produce peak loads when the elements are broadside to the wind. This is typical of low-frequency Yagis, where the elements are long lengths of aluminum tubing. On the other hand, the boom can dominate the surface area computations in higher-frequency Yagis.

The fundamentals responsible for the need to examine both potential FPAs for Yagis relates to how wind flows over a structure and develops loads. Called *The Cross-Flow Principle*, this was introduced to the communications industry by Dick Weber, K5IU, in 1993. The principle is based on the fact that the loads created by wind flowing across an antenna member only produce forces that are normal to (or perpendicular to) the major axis of the member. The resultant and component load calculations for this method are shown in Fig 31A.

For a Yagi, this means that wind forces on the elements act in-line with the boom, while forces on the boom act in-line with the elements. Fig 31B shows a force diagram for a typical Yagi. Fig 31C shows the FPA for a Yagi rotated through 90° of azimuth.

Antenna Placement on the Mast/Tower

Another important consideration is where the antenna(s) will be placed on the tower. As mentioned before, most generic tower specifications assume that the entire antenna load is applied at the top of the tower. Most amateur installations have a tubular mast extending above the tower top, turned by a rotator mounted down inside the tower. Multiple Yagi antennas are often placed on the mast above the tower top, and you must make sure that both the tower and the mast can withstand the wind forces on the antennas.

For freestanding towers, you can determine how a proposed antenna configuration compares to the tower manufacturer's rating by using an *Equivalent Moment* method. The method computes the bending moment generated at the base of the tower by wind loads on the tower's rated antenna area located right at the top of the tower and compares that to the case when the antenna is mounted on a mast sticking out of the top of the tower.

The exact value of wind pressure is not important, so long as it is the same for both comparisons. The wind load on the tower itself can be ignored because it is the same in both comparisons and the drag coefficients for the antennas can also be ignored if all calculations are performed using flat projected antenna areas, as we've recommended previously.

Keep in mind that this approach does not calculate *actual* loads and moments relevant to any specific tower design standard, but it does allow equivalent comparisons when the wind pressure is constant and all the antenna areas are of the same type. An example is in order.

Fig 32A shows a generic tower configuration, with a concentrated antenna load at the top of the tower. We'll assume that the tower manufacturer rates this tower at 20 square feet of flat projected antenna area. Fig 32B shows a typical amateur installation with a rotating mast and an antenna mounted 7 feet above the top of the tower. To make the calculations easy, we select a wind pressure



Fig 32—At A, a 70-foot tower rated for 20 square feet of antenna load at the top. At B, the same tower with a 2-inch OD × 20-foot long mast, with an antenna mounted 7 feet above the top of the tower. Both configurations produce the same tower load.

of 1 pound per square foot (1 psf). This makes the tower base moment calculation for Fig 32A:

Antenna load = 20 feet^2 × 1 psf = 20 pounds
Base moment = 70 feet × 20 pounds =
1400 foot-pounds.

This is the target value for the comparison. An equivalent configuration would produce the same base moment. For the configuration in Fig 32B, we assume a tubular 2-inch diameter mast that is 20 feet long, mounted 5 feet down inside the tower. Note that the lattice structure of the tower allows the wind to "see" the whole length of the mast and that we can consider the force distributed along the mast as being a single force concentrated at the mast's center. The flat projected area of the mast by itself, without the antenna, is:

Mast area = 20 feet × 2 inches / 12 inches/foot =
3.33 square feet

The center of the mast is located at a height of 75 feet. Using the same 1-psf-wind load, the base bending moment due to the mast alone is:

Base moment (due to mast) = 3.33 feet^2 × 1 psf ×
75 feet = 249.75 foot-pounds

Including the mast in the configuration reduces the allowable antenna load. The remaining target base moment left for the antenna is found by subtracting the moment due to the mast from the original target value:

New base target moment = 1400 - 249.75 foot-pounds
= 1150.25 foot-pounds.

The antenna in Fig 32B is located at a height of 77 feet. To obtain the allowable antenna area at this elevation we divide the new base target moment by the antenna height, yielding an allowable antenna load of:

1150.25 foot-pounds / 77 feet = 14.94 pounds.

Since we chose a wind load of 1 psf, the allowable antenna FPA has been reduced to 14.94 square feet from 20 square feet. If the projected area of the antenna we are planning to mount in the new configuration is less than or equal to this value, we have satisfied the requirements of the original design. You can use this equivalent-moment method to evaluate different configurations, even ones involving multiple antennas on the mast or situations with additional antennas placed along the tower below the tower top.

For guyed towers, the analyses become much more rigorous to solve. Because the guys and their behaviors are such a significant portion of the tower support mechanism, these designs can become very sensitive to antenna load placements. A general rule of thumb for guyed towers is never to exceed the original tower-top load rating, regardless of distributed loads along its length. Once you redistribute the antenna load placements along a guyed tower, you should do a fresh analysis, just to be sure.

You can run evaluations using the above method for antennas placed on the mast above a guyed tower top. The use of the Equivalent-Moment method for antennas mounted below the top of a guyed tower, however, can become quite suspect, since many generic tower designs have their intermediate guys sized for zero antenna loads lower down the tower. The proper approach in this case is to have a qualified mechanical engineer check the configuration, to see if guy placement and strength is adequate for the additional antennas down the tower.

Mounting the mast and antenna as shown in Fig 32B increases tower loads in the region of the mast. You should investigate these loads to ensure that the tower bracing in that area is sufficient. Now we will consider the problem of bending the rotating mast.

Mast Strength

When you mount antennas on a mast above the tower top, you should examine the bending loads on the mast to ensure that it will be strong enough. This section explains how to perform mast stress calculations for a single sustained wind speed. This procedure does not include height, exposure and gust-response factors found in most tower design standards.

Here are some fundamental formulas and values used to calculate the bending stress in a mast mounted in the top of a tower. The basic formula for wind pressure is:

$$P = .00256\ V^2 \qquad \text{(Eq 1)}$$

where

P is the wind pressure is in pounds per square foot (psf)

V = wind speed in miles per hour (mph)

This assumes an air density for standard temperature and atmospheric pressure at sea level. The wind speed is not the Basic Wind Speed discussed in other sections of this chapter. It is simply a steady state (static) wind velocity.

The formula for calculating the force created by the wind on a structure is:

$$F = P \times A \times C_d \qquad \text{(Eq 2)}$$

where

P = the wind pressure from Eq (1)

A = the flat projected area of the structure (square feet)

C_d = drag coefficient for the shape of the structure's members.

The commonly accepted *drag coefficient* for long cylindrical members like the tubing used for the mast and antenna is 1.20. The coefficient for a flat plate is 2.0.

The formula used to find the *bending stress* in a simple beam like our mast is:

$$\sigma = \frac{M \times c}{I} \qquad \text{(Eq 3)}$$

where

σ = the stress in pounds per square inch (psi)

M = *bending moment* at the base of the mast (inch-pounds)

c = ½ of the mast outside diameter (inches)

I = *moment of inertia* of the mast section (inches^4)

In this equation you must make sure that all values are in the same units. To arrive at the mast stress in pounds per square inch (psi), the other values need to be in inches and pounds also. The equation used to find the moment of inertia for the round tubing mast section is:

$$I = \frac{\pi}{4}(R^4 - r^4) \qquad \text{(Eq 4)}$$

where

I = Moment of Inertia of the section (inches^4)

R = Radius of tube outside diameter (inches)

r = Radius of tube inside diameter (inches)

This value describes the distribution of material about the mast *centroid*, which determines how it behaves under load. The equation used to compute the *bending moment* at the base of the mast (where it is supported by the tower) is:

$$M = (F_M \times L_M) + (F_A \times L_M) \qquad \text{(Eq 5)}$$

where

F_M = wind force from the mast (pounds)

L_M = Distance from tower top to center of mast (inches)

F_A = Wind force from the antenna (pounds)

L_A = Distance from tower top to antenna attachment (inches)

L_M is the distance to the center of the portion of the mast extending above the tower top. Additional antennas can be added to this formula by including their F × L. In the installation shown in Fig 32B, a wind speed of 90 mph, and a mast that is 2 inches OD, with a 0.250-inch wall thickness, the steps for calculating the mast stress are:

1. Calculate the wind pressure for 90 mph, from Eq 1:

$P = .00256\ V^2 = .00256 \times (90)^2 = 20.736$ psf

2. Determine the flat projected area of the mast. The portion of the mast above the tower is 15 feet long and has an outside diameter of 2 inches, which is 2/12 feet.

Mast FPA, A_M = 15 feet × (2 inches / 12 inches/feet) = 2.50 square feet.

3. Calculate the wind load on the mast, from Eq 2:

Mast Force, $F_M = P \times A \times C_d =$ 20.736 psf × 2.50 feet^2 × 1.20 = 62.21 pounds

4. Calculate the wind load on the antenna: From Eq 2

Antenna Force, $F_A = P \times A \times C_d =$ 20.736 psf × 14.94 feet^2 × 1.20 = 371.76 pounds

5. Calculate the mast *Bending Moment*, from Eq 5:

$M = (F_M \times L_M) + (F_A \times L_A)$ = (62.21 pounds × 90 inches) + (371.76 pounds × 84 inches) = 36827 inch-pounds

where L_M = 7.5 feet × 12 inches/foot = 90 inches and L_A = 7.0 feet × 12 inches/foot = 84 inches.

6. Calculate the mast *Moment of Inertia*, from Eq 4:

$$I = \frac{\pi}{4}(R^4 - r^4) = \frac{\pi}{4}(1.0^4 - 0.75^4) = 0.5369 \text{ inches}^4$$

where, for a 2.0-inch OD and 0.250-inch wall thickness tube, R= 1.0 and r = 0.75.

7. Calculate the mast *Bending Stress*, from Eq 3:

$$\sigma = \frac{M \times c}{I} = \frac{36827 \text{ inch-pounds} \times 1.0 \text{ inches}}{0.5369} = 68592 \text{ psi}$$

If the yield strength of the mast material is greater than the calculated bending stress, the mast is considered safe for this configuration and wind speed. If the calculated stress is higher than the mast yield strength, a stronger alloy, or a larger mast, or one with a thicker wall is required.

There are many different materials and manufacturing processes for tubing that may be used for a mast. Yield strengths range from 25,000 psi to nearly 100,000 psi. Knowing the minimum yield strength of the material used for a mast is an important part of determining if it will be safe. Using unknown materials renders efforts from the preceding calculations useless!

When evaluating a mast with multiple antennas attached to it, special care should be given to finding the worst-case condition (wind direction) for the system. What may appear to be the worst load case, by virtue of the combined flat projected antenna areas, may not always be the exposure that creates the largest mast bending moment. Masts with multiple stacked antennas should always be examined to find the exposure that produces the largest mast bending moment. The antenna flat projected areas at 0° and 90° azimuths are particularly useful for this evaluation.

ANTENNA INSTALLATION

All antenna installations are different in some respects. Therefore, thorough planning is the most important first step in installing any antenna. Before anyone climbs the tower, the whole process should be discussed to be sure each crewmember understands what is to be done. And remember that the person on the tower is in charge! Coordinate beforehand what signals and commands are used: "Up" or "Up Slowly" for raising something from the ground; "Down" or "Down Slowly" for the opposite.

"Watch Out!" or 'Watch Out Below!" works for dropped hardware or tools to alert the ground crew below. Remember, once someone is on the tower, no one should be allowed to stand near the base of the tower!

Consider what tools and parts must be assembled and what items must be taken up the tower, and plan alternative actions for possible trouble spots. Extra trips up and down the tower can be avoided by careful planning.

If done properly, the actual work of getting the antenna into position can be executed quite easily with only one person at the top of the tower. The ground crew should do all the heavy work and leave the person on the tower free to guide the antenna into position. Because the ground crew does all the lifting, a large pulley, preferably on a gin pole placed at the top of the tower, is essential. Local radio clubs often have gin poles available for use by their members. Stores that sell tower materials frequently rent gin poles as well.

A gin pole should be placed along the side of the tower so the pulley is no more than 2 feet above the top of the tower (or the point at which the antenna is to be placed). Normally this height is sufficient to allow the antenna to be positioned easily. An important reason that the pulley is placed at this level is that there can be considerable strain on the gin pole when the antenna is pulled away from the tower to maneuver past guy wires.

Sometime the mast to which the antenna will be mounted is used as a place to hang the pulley. You should take care that you don't end up bending the mast by placing the pulley too high on the mast. It may be necessary to back-guy the mast on the opposite side of the tower from which the antenna is raised.

The rope (halyard) through the pulley must be somewhat longer than twice the tower height so that the ground crew can raise the antenna from ground level. The rope should be ½ or ⁵⁄₈ inch diameter for both strength and ease of handling. Smaller diameter rope is less easily manipulated; it has a tendency to jump out of the pulley track and foul pulley operation.

The first person to climb the tower should carry an end of the halyard so that the gin pole can be lifted and secured to the tower. Those climbing the tower must have safety belts. Belts provide safety and convenience; it is simply impossible to work effectively while hanging onto the tower with one hand.

Once positioned, the gin pole and pulley allow parts and tools to be sent up the tower. A useful trick for sending up small items like bolts and pliers is for a ground crew member to slide them through the rope strands where they are held by the rope for the trip to the top of the tower. Items that might be dislodged by contact with the tower should either be taped or tied to the halyard.
Ever present is the hazard of falling tools or hardware. It is foolish to stand near a tower when someone is working above. Ground crew member should wear hard-hats as extra insurance.

Raising the Antenna Alongside the Tower

A technique that can save much effort in raising the antenna is outlined here. First, the halyard is passed through the gin-pole pulley or the pulley mounted to the mast, and the leading end of the rope is returned to the ground crew, where it is tied to the antenna. The assembled antenna should be placed in a clear area of the yard (or the roof) so the boom points toward the tower. The halyard is then passed *under* the front elements of the beam to a position past the midpoint of the antenna, where it is securely tied to the boom (**Fig 33A**).

Note that once the antenna is installed, the tower worker must be able to reach and untie the halyard from the boom; the rope must be tied less than an arm's length along the boom from the mounting point. If necessary, a large loop may be placed around the first element located beyond the midpoint of the boom, with the knot tied near the center of the antenna. The rope may then be untied easily after completion of the installation. The halyard should be tied temporarily to the boom at the front of the antenna by means of a short piece of light rope or twine.

While the antenna is being raised, the ground crew does all the pulling. As soon as the front of the antenna reaches the top of the mast, the person atop the tower unties the light rope and prevents the front of the antenna from falling, as the ground crew continues to lift the antenna (Fig 33B). When the center of the antenna is even with the top of the tower, the tower worker puts one bolt through the mast and the antenna-mounting bracket on the boom. The single bolt acts as a pivot point and the ground crew continues to lift the back of the antenna with the halyard (Fig 33C). After the antenna is horizontal, the tower worker secures the rest of the mounting bolts and unties the halyard. By using this technique, the tower worker performs no heavy lifting.

Avoiding Guy Wires

Although the same basic methods of installing a Yagi apply to any tower, guyed towers pose a special problem. Steps must be taken to avoid snagging the antenna on the guy wires. With proper precautions, however, even large antennas can be pulled to the top of a tower, even if the



Fig 33—Raising a Yagi antenna alongside the tower. At A the Yagi is placed in a clear area, with the boom pointing toward the tower. The halyard is passed under the elements, then is secured to the boom beyond the midpoint. B shows the antenna approaching the top of the mast. The person on the tower guides it after the lifting rope has been untied from the front of the antenna. At C the antenna is pulled into a horizontal position by the ground crew. The tower worker inserts the pivot bolt and secures it. Note: A short piece of rope is tied around the halyard and the boom at the front of the antenna to stabilize the beam as it is being raised. The tower worker removes it when the boom reaches him at the top of the tower.


Gin Pole
Hoist Rope Attached to Boom
Boom
Element
Guy
Hoist Rope
Snatch Block at Tower Base
(A)


Boom Rotated 90° so Elements are Vertical
(B)

Fig 34—Building a Yagi partway down the tower. At A, the boom is lashed temporarily to the tower and elements are added, starting at the bottom. At B, the temporary rope securing the boom to the tower is removed and the boom is rotated 90° so that the elements are vertical. At C, the boom is rotated another 90°, "weaving through" guy wires if necessary, until the elements are parallel with the ground, whereupon the boom is secured to the tower.


Boom Rotated so that Elements are Parallel to Ground
(C)

mast is guyed at several levels.

Sometimes one of the top guys can provide a *track* to support the antenna as it is pulled upward. Insulators in the guys, however, may obstruct the movement of the antenna. A better track made with rope is an alternative. One end of the rope is secured outside the guy anchors. The other end is passed over the top of the tower and back down to an anchor near the first anchor. So arranged, the rope forms a narrow V-track strung outside the guy wires. Once the V-track is secured, the antenna may simply be pulled up, resting on the track.

Another method is to tie a rope to the back of the antenna (but within reach of the center). The ground crews then pull the antenna out away from the guys as the antenna is raised. With this method, some crewmembers are pulling up the antenna to raise it while others are pulling down and out to keep the beam clear of the guys. Obviously, the opposing crews must act in coordination to avoid damaging the antenna. The beam is especially vulnerable when it begins to tip into the horizontal position. If the crew continues to pull out and down against the antenna, the boom can be broken. Another problem with this approach is that the antenna may rotate on the axis of the boom as it is raised. To prevent such rotation, long lengths of twine may be tied to outer elements, one piece on each side of the boom. Ground personnel may then use these *tag lines* to stabilize the antenna. Where this is done, provisions must be made for untying the twine once the antenna is in place.

A third method is to tie the halyard to the center of the antenna. A crewmember, wearing a safety belt, walks the antenna up the tower as the crew on the ground raises it. Because the halyard is tied at the balance point, the tower worker can rotate the elements around the guys. A tag line can be tied to the bottom end of the boom so that a ground worker can help move the antenna around the guys. The tag line must be removed while the antenna is still vertical.

A fourth method is to build the antenna on the tower and then swing it into position. (See also the section below on the PVC Mount.) Building the Yagi on the tower works particularly well for Yagis mounted partway up the tower, as you might do in a stacked array. The technique works best when the vertical spacing between the guys is greater than the length of the Yagi boom.

Fig 34 illustrates the steps involved. A pull rope through a gin-pole or tower-mounted pulley is secured to the boom at the final balance point and the ground crew raises the boom in a vertical position up the tower. A tie rope is used to temporarily secure the upper end of the boom to keep it stable while the boom is being raised. The tower person removes the tie-rope once the boom is raised to the right level and has been temporarily secured to the tower.

The elements are then brought up one at a time and mounted to the boom. It helps if you have a 2- or 3-foot long *spotting mast* temporarily attached to the boom to form a 90° frame of reference. This allows the ground crew to spot from below so that the elements are all lined up in the same plane. After all the elements are mounted and aligned properly, the temporary rope securing the boom to the tower is released, suspending the antenna on the pull rope. The tower person then rotates the boom 90° so that the elements are vertical. Next the elements are rotated 90° into the tower so that they are parallel to the ground. The ground crew then moves the boom up or down using the pull rope to the final point where it is mounted to the tower.

A modification of this technique also works for building a medium-sized Yagi on the top of the tower. This technique will work if the length of the gin pole at maximum safe extension is long enough. See **Fig 35**.

As usual, the gin-pole pull rope is attached to the balance point of the boom and the boom is pulled up the tower in the vertical position, using a rope to temporarily tie the pull rope to the top end of the boom for stability. The boom is temporarily secured to the tower with rope in the vertical position so that the top end is just higher than the top of the tower. In order to clear the gin pole when the elements are mounted and the boom is raised higher to mount the next element, you must tilt the boom slightly so that the element mounted to the top end of the boom will be *behind* the mast. This is very important!

The elements are first mounted to the bottom side of the boom to provide weight down below for stability. Then the top-most element is mounted to the boom. The tower person removes the temporary rope securing the boom to the tower and the ground crew uses the pull rope


Elements Behind Gin Pole
Boom Slanted Slightly on Tower so that Elements are Behind Gin Pole
(B)

Fig 35—Building a Yagi at the top of the tower. The length of the gin pole must be longer than $^1/_2$ the boom so that the boom can be hoisted upwards to the place where it is mounted to the mast. Usually the boom is initially lashed to the tower slanted slightly from vertical so that the top element ends up *behind* the gin pole. The elements are mounted at the bottom end of the boom first to provide stability. Then the element at the top of the boom is mounted and the boom is moved upwards using the gin-pole hoist rope so that the next-to-top element may be mounted, again behind the gin pole. This process is repeated until all elements are mounted (save possibly the middle element if it can be reached easily from the tower once the beam has been mounted to the mast). Then the boom is tilted to the final position, weaving the elements to clear guy wires if necessary.

to move the mast vertically upwards to the point where the next element from the top can be mounted. Once all the elements are mounted and aligned in the same plane (with perhaps the center element closest to the mast-to-boom bracket left on the ground until later), the temporary securing rope is removed. The boom is now swung so that the elements can be maneuvered to clear the top guy wires. Once the elements are horizontal the boom is secured to the mast and the center element is mounted.

Using a Tram

Another method to get a large Yagi to the top of the tower safely is a *tram*. A tram supports the antenna *under* the tram wire, using a pulley riding on the tram wire. The antenna can thus move more freely—without the friction it would have riding on top of a track rope, as described previously. This puts considerably less strain on the tram wire itself and on the mast to which it is tied on the tower. Some installers prefer to use a wire-rope tramline for its reduced sag.

The tram method uses an easily constructed fixture mounted to the boom of the Yagi to stabilize it from rotating away from the desired attitude as the antenna is raised. A guy-wire cable or heavy rope is fixed to the mast about two feet above the point where the antenna will mount to the mast. A come-along is often used at the ground end to tension the tram wire properly. It is often necessary to back-guy the mast to make sure it doesn’t get bent, since the horizontal forces acting on the mast can be considerable in any tram (or track) operation. (Note that the tram technique works well for side-mounted antennas also, where back-guying is not necessary if you are reasonably close to a guy set, as is usually the case.)

Fig 36 is a photograph of a tram fixture built by Kurt Andress, K7NV. This consists of a pulley riding on top of the tramline. This pulley is attached using a caribiner or shackle to two equal-length wires connected to the boom to make an inverted-V shaped *sling*. The two sling wires are secured to the boom using angle irons and muffler clamps so that the antenna is perfectly balanced in the horizontal plane. Balance is very important to make sure the antenna rises properly on the tram without having the boom rotate downward on one end or the other.



Fig 36—Photo of the tram system used by Kurt Andress, K7NV. (*Photo by K7NV.*)

The hoisting rope running through the tower-mounted gin-pole pulley (and used by the ground crew to pull the antenna up to the tower on the tram line) is attached to a 2-foot piece of angle iron. This is attached to the boom with a muffler clamp. Note that the angle iron is rotated slightly from horizontal so that the plane of the elements is tilted upwards—this allows the elements to clear the guy wires as the antenna is raised. (While the antenna is close to the ground, the angle iron is adjusted so that the elements remain horizontal. Once they are clear of the ground, the angle iron is readjusted to align the elements in the proper direction to clear the guy wires on the tower.) The force of the pull rope along the angle iron also stabilizes the antenna from yawing from side-to-side. Note in Fig 36 that the angle iron is mounted just off-center from where the boom-to-mast plate will be attached so that it clears the mast as the antenna nears the top of the tower. **Fig 37** diagrams how the tram and hoisting line are rigged to the mast.

The tower person directs the activity of the ground crew below and guides the antenna to the mast. Once the end of the pull rope reaches the mast, the tower man ties the boom temporarily to the mast so that he can undo the pull rope from the tram-fixture angle iron and retie it around the boom. Then the antenna can be raised to the point where it can be mounted to the mast.

This technique has been employed to raise Yagis with booms as long as 42 feet at the N6RO contest station on towers as high as 130 feet. As with the track, the tram system requires a good deal of open real estate. While it sounds complicated to set up, you can raise some rather large antennas in less than an hour, once you get the hang of the operation.

THE PVRC MOUNT

The methods described above for hoisting antennas are sometimes not satisfactory for really large, heavy arrays. The best way to handle large Yagis is to assemble them on top of the tower. One way to do this easily is by using the *PVRC Mount*. Many members of the Potomac Valley Radio Club have successfully used this method to install large antennas. Simple and ingenious, the idea involves offsetting the boom from the mast to permit the boom to tilt 360° and rotate axially 360°. This permits the entire length of the boom to be brought alongside the tower, allowing the elements to be attached one by one. (It also allows any part of the antenna to be brought alongside the tower for antenna maintenance.)

See **Figs 38** through **42**. The mount itself consists of a short length of pipe of the same diameter as the rotating mast (or greater), a steel plate, eight U bolts and four pinning bolts. The steel plate is the larger, horizontal one shown in Fig 38. Four U bolts attach the plate to the rotating mast, and four attach the horizontal pipe to the plate. The horizontal pipe provides the offset between the antenna boom and the tower. The antenna boom-to-mast plate is mounted at the outer end of the short pipe. Four bolts are used to ensure that the antenna ends up parallel to the ground, two pinning each plate to the short pipe. When the mast plate pinning bolts are removed and the



Fig 37—At A, bird's-eye view of tram system used to bring large Yagi antennas from the ground to the top of the tower. At B, side view of rigging used for tramline and hoisting line, along with the sling and tram fixture used to hold the Yagi on the tramline.

four U bolts loosened, the short pipe and boom plate can be rotated through 360°, allowing either half of the boom to come alongside the tower.

First assemble the antenna on the ground. Carefully mark all critical dimensions, and then remove the antenna elements from the boom. Once the rotator and mast have been installed on the tower, a gin pole is used to bring the mast plate and short pipe to the top of the tower. There, the top crew unpins the horizontal pipe and tilts the antenna boom plate to place it in the vertical plane. The boom is attached to the boom plate at the final balance point of the assembled antenna. It is important that the boom be rotated axially so the bottom side of the boom is closest to the tower. This will allow the boom to be tilted without the elements striking the tower.

During installation it may be necessary to loosen one guy wire temporarily to allow for tilting of the boom. As a safety precaution, a temporary guy should be attached to the same leg of the tower just low enough so the assembled antenna will clear it.

The elements are assembled on the boom, starting with those closest to the center of the boom, working out alternately to the farthest director and reflector. This procedure must be followed. If all the elements are put first on one half of the boom, it will be dangerous (if not impossible) to put on the remaining elements. By start-



Fig 38—The PVRC mount, boom plate, mast and rotator ready to go. The mast and rotator are installed on the tower first.



Fig 39—Close-up of the PVRC mount. The long pipe (horizontal in this photo) is the rotating mast. The U bolts in the vertical plate at the left are ready to accept the antenna boom. The heads of two locking pins (bolts) are visible at the midline of the boom plate. The other two pins help secure the horizontal pipe to the large steel mast plate. (The head of the bolt nearest the camera blends in with the right hand leg of the U bolt behind it.)



Fig 40—Working at the 70-foot level. A gin pole makes pulling up and mounting the boom to the boom plate a safe and easy procedure.

ing at the middle and working outward, the balance point of the partly assembled antenna will never be so far removed from the tower that tilting of the boom becomes impossible.

When the last element is attached, the boom is brought parallel to the ground, the horizontal pipe is pinned to the mast plate, and the mast plate U bolts tightened. At this point, all the antenna elements will be positioned vertically. Next, loosen the U bolts that hold the boom and rotate the boom axially 90°, bringing the elements parallel to the ground. Tighten the boom bolts and double check all the hardware.

Many long-boom Yagis employ a truss to prevent boom sag. With the PVRC mount, the truss must be attached to a pipe that is independent of the rotating mast. A short length of pipe is attached to the boom as close as possible to the balance point. The truss then moves with the boom whenever the boom is tilted or twisted.

A precaution: Unless you have a really strong rotator, you should consider using this mount mainly for assembling the antenna on the tower. The offset between the boom and the mast with this assembly can generate high torque loads on the rotator. Mounting the boom as close as possible to the mast will minimize the torque when the antenna is pointed into the wind.



Fig 41—Mounting the last element prior to positioning the boom in a horizontal plane.



Fig 42—The U bolts securing the short pipe to the mast plate are loosened and the boom is turned to a horizontal position. This puts the elements in a vertical plane. Then the pipe U bolts are tightened and pinning bolts secured. The boom U bolts are then loosened and the boom turned axially 90°.

THE TOWER ALTERNATIVE

A cost saving alternative to the ground-mounted tower is the roof-mounted tripod. Units suitable for small HF or VHF antennas are commercially available. Perhaps the biggest problem with a tripod is determining how to fasten it securely to the roof.

One method of mounting a tripod on a roof is to nail 2 × 6 boards to the undersides of the rafters. Bolts can be extended from the leg mounts through the roof and the 2 × 6s. To avoid exerting too much pressure on the area of the roof between rafters, place another set of 2 × 6s on top of the roof (a mirror image of the ones in the attic). Installation details are shown in **Figs 43** through **46**.

The 2 × 6s are cut 4 inches longer than the outside distance between two rafters. Bolts are cut from a length of ¼-inch-threaded rod. Nails are used to hold the boards in place during installation, and roofing tar is used to seal the area to prevent leaks.

Find a location on the roof that will allow the antenna to turn without obstruction from such things as trees, TV antennas and chimneys. Determine the rafter locations. (Chimneys and vent pipes make good reference points.) Now the tower is set in place atop three 2 × 6s. A plumb line run from the top center of the tower can be used to center it on the peak of the roof. Holes for the mounting bolts can now be drilled through the roof.

Before proceeding, the bottom of the 2 × 6s and the area of the roof under them should be given a coat of roofing tar. Leave about $^1/_8$ inch of clear area around the holes to ensure easy passage of the bolts. Put the tower back in place and insert the bolts and tighten them. Apply tar to the bottom of the legs and the wooden supports, including the bolts. For added security the tripod can be guyed. Guys should be anchored to the frame of the house.

If a rotator is to be mounted above the tripod, pressure will be applied to the bearings. Wind load on the antenna will be translated into a "pinching" of one side of the bearings. Make sure that the rotator is capable of handling this additional stress.

ROTATOR SYSTEMS

There are not that many choices when it comes to antenna rotators for the amateur antenna system. Making the correct decision as to how much capacity the rotator must have is very important to ensure trouble-free operation. Manufacturers generally provide an antenna surface-area rating to help the purchase choose a suitable rotator. The maximum antenna area is linked to the rotator's torque capability.

Some rotator manufacturers provide additional information to help you select the right size of rotator for the antennas you plan to use. Hy-Gain provides an *Effective Moment* value. Yaesu calls theirs a *K-Factor*. Both of these ratings are torque values in foot-pounds. You can compute the effective moment of your antenna by multiplying the antenna turning radius by its weight. So long



Fig 43—This tripod tower supports a rotary beam antenna. In addition to saving yard space, a roof-mounted tower can be more economical than a ground-mounted tower. A ground lead fastened to the lower part of the frame is for lightning protection. The rotator control cable and the coaxial line are dressed along two of the legs. (*Photo courtesy of Jane Wolfert.*)



Fig 44—This cutaway view illustrates how the tripod tower is secured to the roof rafters. The leg to be secured to the crosspiece is placed on the outside of the roof. Another cross member is fastened to the underside of the rafters. Bolts, inserted through the roof and the two cross pieces, hold the inner cross member in place because of pressure applied. The inner crosspiece can be nailed to the rafter for added strength.



Fig 45—Three lengths of 2 × 6 wood mounted on the outside of the roof and reinforced under the roof by three identical lengths provide a durable means for anchoring the tripod. A thick coat of roofing tar guards against weathering and leaks.



Fig 46—The strengthened anchoring for the tripod. Bolts are placed through two 2 × 6s on the underside of the roof and through the 2 × 6 on the top of the roof, as shown in Fig 43.

as the effective moment rating of the rotator is greater than or equal to the antenna value, the rotator can be expected to provide a useful service life.

There are basically four grades of rotators available to the amateur. The lightest-duty rotator is the type typically used to turn TV antennas. Without much difficulty, these rotators will handle a small 3-element tribander array (14, 21 and 28 MHz) or a single 21- or 28-MHz monoband three-element antenna. The important consideration with a TV rotator is that it lacks braking or holding capability. High winds turn the rotator motor via the gear train in a reverse fashion. Broken gears sometimes result.

The next grade up from the TV class of rotator usually includes a braking arrangement, whereby the antenna is held in place when power is not applied to the rotator. Generally speaking, the brake prevents gear damage on windy days. If adequate precautions are taken, this group of rotators is capable of holding and turning stacked monoband arrays, or up to a five-element 14-MHz system. The next step up in rotator strength is more expensive. This class of rotator will turn just about anything the most demanding amateur might want to install.

A description of antenna rotators would not be complete without the mention of the *prop pitch* class. The prop pitch rotator system consists of a surplus aircraft propeller blade pitch motor coupled to an indicator system and a power supply. There are mechanical problems of installation, however, resulting mostly from the size and weight of these motors. It has been said that a prop pitch rotator system, properly installed, is capable of turning a house. Perhaps in the same class as the prop pitch motor (but with somewhat less capability) is the electric motor of the type used for opening garage doors. These have been used successfully in turning large arrays.

Proper installation of the antenna rotator can provide many years of trouble-free service; sloppy installation can cause problems such as a burned out motor, slippage, binding and casting breakage. Most rotators are capable of accepting mast sizes of different diameters, and suitable precautions must be taken to shim an undersized mast to ensure dead-center rotation. It is very desirable to mount the rotator inside and as far below the top of the tower as possible. The mast absorbs the torsion developed by the antenna during high winds, as well as during starting and stopping.

Some amateurs have used a long mast from the top to the base of the tower. Rotator installation and service can be accomplished at ground level. A mast length of 10 feet or more between the rotator and the antenna will add greatly to the longevity of the entire system by allowing the mast to act as a torsion shock absorber. Another benefit of mounting the rotator 10 feet or more below the antenna is that any misalignment among the rotator, mast and the top of the tower is less significant. A tube at the top of the tower (a sleeve bearing) through which the mast protrudes almost completely eliminates any lateral forces on the rotator casing. All the rotator must do is support the downward weight of the antenna system and turn the array.



Fig 47—Rotator loop for UHF Yagi array. The feed coax is bundled with a control cable for the polarization relay. The coax/control-cable loop is taped to the rotating mast and to the top of the tower with vinyl electric tape to allow the array to be rotated.

While the normal weight of the antenna and the mast is usually not more than a couple of hundred pounds, even with a large system, one can ease this strain on the rotator by installing a thrust bearing at the top of the tower. The bearing is then the component that holds the weight of the antenna system, and the rotator need perform only the rotating task.

Don't forget to provide a loop of coax to allow your beam to rotate properly. Make sure you position the rotator loop so that it doesn't snag on anything. **Fig 47** shows a rotator loop for an elliptically polarized UHF Yagi array. Note that the coax loop is taped to the rotating mast above the top of the tower and to the tower itself.

Indicator Alignment

A problem often encountered in amateur installations is that of misalignment between the direction indicator in the rotator control box and the heading of the antenna. With a light duty rotator, this happens frequently when the wind blows the antenna to a different heading. With no brake, the force of the wind can move the gear train and motor of the rotator, while the indicator remains fixed. Such rotator systems have a mechanical stop to prevent continuous rotation during operation, and provision is usually included to realign the indicator against the mechanical stop from inside the shack. During installation, the antenna must be oriented correctly for the mechanical stop position, which is usually north.

In larger rotator systems with an adequate brake, indicator misalignment is caused by mechanical slippage in the antenna boom-to-mast hardware. Many texts suggest that the boom be pinned to the mast with a heavy-duty bolt and the rotator be similarly pinned to the mast. There is a trade-off here. If there is sufficient wind to cause slippage in the couplings without pins, with pins the wind could break a rotator casting. The slippage will act as a clutch release, which may prevent serious damage to the rotator. On the other hand, the amateur might not like to climb the tower and realign the system after each heavy windstorm.

BIBLIOGRAPHY

Source material and more extended discussions of the topics covered in this chapter can be found in the references listed below and in the texts listed at the end of Chapter 2.

L. H. Abraham, "Guys for Guys Who Have To Guy," *QST*, Jun 1955.

K. Baker, "A Ladder Mast," *QST*, Jun 1981, p 24.

W. R. Gary, "Toward Safer Antenna Installations," *QST*, Jan 1980, p 56.

S. F. Hoerner, "Fluid Dynamic Drag," published by author, Bricktown, New Jersey, 1965, pp 1-10.

C. L. Hutchinson, "A Tree-Mounted 30-Meter Ground-Plane Antenna," *QST*, Sep 1984, pp 16-18.

C. L. Hutchinson, R. D. Straw, *Simple and Fun Antennas for Hams* (Newington: ARRL, 2002).

M. P. Keown and L. L. Lamb, "A Simple Technique for Tower-Section Separation," *QST*, Sep 1979, pp 37-38.

P. O'Dell, "The Ups and Downs of Towers," *QST*, Jul 1981, p 35.

S. Phillabaum, "Installation Techniques for Medium and Large Yagis," *QST*, Jun 1979, p 23.

C. J. Richards, "Mechanical Engineering in Radar and Communications" (London: Van Nostrand Reinhold Co., 1969) pp 162-165.

D. Weber "Determination of Yagi Wind Loads Using the Cross-Flow Principle," *Communications Quarterly*, Spring 1993.

A. B. White, "A Delayed Brake Release for the Ham-II," *QST*, Aug 1977, p 14.

B. White, E. White and J. White, "Assembling Big Antennas on Fixed Towers," *QST*, Mar 1982, pp 28-29

L. Wolfert, "The Tower Alternative," *QST*, Nov 1980, p 36.

W. C. Young., "Roark's Formulas for Stress & Strain" (New York: McGraw-Hill Co., 1989), pp 67, 96

Structural Standards for Steel Antenna Towers and Antenna Supporting Structures, TIA/EIA Standard TIA/EIA-222-F, Electronic Industries Association, Mar 1996. May be purchased from Telecommunications Industry Association (TIA), Standards and Technology Department, 2500 Wilson Boulevard, Arlington VA, 22201 or Global Engineering Documents, 15 Inverness Way East, Englewood, CO, 80112-5704, 1-800-854-7179.

Chapter 23

Radio Wave Propagation

Because radio communication is carried on by means of electromagnetic waves traveling through the Earth's atmosphere, it is important to understand the nature of these waves and their behavior in the propagation medium. Most antennas will radiate the power applied to them efficiently, but no antenna can do all things equally well, under all circumstances. Whether you design and build your own antennas, or buy them and have them put up by a professional, you'll need propagation know-how for best results, both during the planning stages and while operating your station.

For station planning, this chapter contains detailed new information on elevation angles from transmitting locations throughout the world to important areas throughout the world. With this information in hand, you can design your own antenna installation for optimum capabilities possible within your budget. See the CD-ROM in back of this book.

The Nature of Radio Waves

You probably have some familiarity with the concept of electric and magnetic fields. A radio wave is a combination of both, with the energy divided equally between them. If the wave could originate at a point source in free space, it would spread out in an ever-growing sphere, with the source at the center. No antenna can be designed to do this, but the theoretical *isotropic antenna* is useful in explaining and measuring the performance of practical antennas we *can* build. It is, in fact, the basis for any discussion or evaluation of antenna performance.

Our theoretical spheres of radiated energy would expand very rapidly at the same speed as the propagation of light, approximately 186,000 miles or 300,000,000 meters per second. These values are close enough for practical purposes, and are used elsewhere in this book. If one wishes to be more precise, light propagates in a vacuum at the speed of 299.7925 meters per microsecond, and slightly slower in air.

The path of a *ray* traced from its source to any point on a spherical surface is considered to be a straight line—a radius of the sphere. An observer on the surface of the sphere would think of it as being flat, just as the Earth seems flat to us. A radio wave far enough from its source to appear flat is called a *plane wave*. From here on, we will be discussing primarily plane waves.

It helps to understand the radiation of electromagnetic energy if we visualize a plane wave as being made up of electric and magnetic forces, as shown in **Fig 1**. The nature of wave propagation is such that the electric and magnetic lines of force are always perpendicular. The plane containing the sets of crossed lines represents the wave front. The direction of travel is always perpendicular to the wave front; *forward* or *backward* is determined by the relative directions of the electric and magnetic forces.

The speed of travel of a wave through anything but a vacuum is always less than 300,000,000 meters per second. How much less depends on the medium. If it is air, the reduction in propagation speed can be ignored in most discussions of propagation at frequencies below 30 MHz. In the VHF range and higher, temperature and moisture content of the medium have increasing effects on the communication range, as will be discussed later. In solid insulating materials the speed is considerably less. In distilled water (a good insulator) the speed is $^1/_9$ that in free space. In good conductors the speed is so low that the opposing fields set up by the wave front occupy practically the same space as the wave itself, and thus cancel it out. This is the reason for "skin effect" in conductors at high frequencies, making metal enclosures good shields for electrical circuits working at radio frequencies.



Fig 1—Representation of the magnetic and electric fields of a vertically polarized plane wave traveling along the ground. The arrows indicate instantaneous directions of the fields for a wave traveling perpendicularly out of the page toward the reader. Reversal of the direction of one set of lines reverses the direction of travel. There is no change in direction when both sets are reversed. Such a dual reversal occurs in fact once each half cycle.

Phase and Wavelength

Because the velocity of wave propagation is so great, we tend to ignore it. Only $^1/_7$ of a second is needed for a radio wave to travel around the world—but in working with antennas the *time* factor is extremely important. The wave concept evolved because an alternating current flowing in a wire (antenna) sets up moving electric and magnetic fields. We can hardly discuss antenna theory or performance at all without involving travel time, consciously or otherwise.

Waves used in radio communication may have frequencies from about 10,000 to several billion Hz. Suppose the frequency is 30 MHz. One cycle, or period, is completed in 1/30,000,000 second. The wave is traveling at 300,000,000 meters per second, so it will move only 10 meters during the time that the current is going through one complete period of alternation. The electromagnetic field 10 meters away from the antenna is caused by the current that was flowing one period earlier in time. The field 20 meters away is caused by the current that was flowing two periods earlier, and so on.

If each period of the current is simply a repetition of the one before it, the currents at corresponding instants in each period will be identical. The fields caused by those currents will also be identical. As the fields move outward from the antenna they become more thinly spread over larger and larger surfaces. Their amplitudes decrease with distance from the antenna but they do not lose their identity with respect to the instant of the period at which they were generated. They are, and they remain, *in phase*. In the example above, at intervals of 10 meters measured outward from the antenna, the phase of the waves at any given instant is identical.

From this information we can define both *wave front* and *wavelength*. Consider the wave front as an imaginary surface. On every part of this surface, the wave is in the same phase. The wavelength is the distance between two wave fronts having the same phase at any given instant. This distance must be measured perpendicular to the wave fronts along the line that represents the direction of travel. The abbreviation for wavelength is the Greek letter lambda, λ, which is used throughout this book.

The wavelength will be in the same length units as the velocity when the frequency is expressed in the same time units as the velocity. For waves traveling in free space (and near enough for waves traveling through air) the wavelength is

$$\lambda_{\text{meters}} = \frac{299.7925}{F(\text{MHz})} \qquad \text{(Eq 1)}$$

There will be few pages in this book where phase, wavelength and frequency do not come into the discussion. It is essential to have a clear understanding of their meaning in order to understand the design, installation, adjustment or use of antennas, matching systems or transmission lines in detail. In essence, *phase* means *time*. When something goes through periodic variations, as an alternating current does, corresponding instants in succeeding periods are *in phase*.

The points A, B and C in **Fig 2** are all in phase. They are corresponding instants in the current flow, at 1-λ intervals. This is a conventional view of a sine-wave alternating current, with time progressing to the right. It also represents a *snapshot* of the intensity of the traveling fields, if distance is substituted for time in the horizontal axis. The distance between A and B or between B and C is one wavelength. The field-intensity distribution follows the sine curve, in both amplitude and polarity, corresponding exactly to the time variations in the current that produced the fields. Remember that this is an *instantaneous* picture—the wave moves outward, much as a wave created by a rock thrown into water does.

Polarization

A wave like that in Fig 1 is said to be *polarized* in the direction of the electric lines of force. The polarization here is vertical, because the electric lines are perpendicular to the surface of the Earth. It is one of the laws of electromagnetics that electric lines touching the surface of a perfect conductor must do so perpendicularly, or else they would have to generate infinite currents in the conductor, an obvious impossibility. Most ground is a rather good conductor at frequencies below about 10 MHz, so waves at these



Fig 2—The instantaneous amplitude of both fields (electric and magnetic) varies sinusoidally with time as shown in this graph. Since the fields travel at constant velocity, the graph also represents the instantaneous distribution of field intensity along the wave path. The distance between two points of equal phase such as A-B and B-C is the length of the wave.

frequencies, traveling close to good ground, are mainly vertically polarized. Over partially conducting ground there may be a forward tilt to the wave front; the tilt in the electric lines of force increases as the energy loss in the ground becomes greater.

Waves traveling in contact with the surface of the Earth, called *surface waves*, are of little practical use in amateur communication. This is because as the frequency is raised, the distance over which they will travel without excessive energy loss becomes smaller and smaller. The surface wave is most useful at low frequencies and through the standard AM broadcast band. The surface wave will be covered later. At high frequencies a wave reaching a receiving antenna has had little contact with the ground, and its polarization is not necessarily vertical.

If the electric lines of force are horizontal, the wave is said to be *horizontally polarized*. Horizontally and vertically polarized waves may be classified generally under *linear polarization*. Linear polarization can be anything between horizontal and vertical. In free space, "horizontal" and "vertical" have no meaning, since the reference of the seemingly horizontal surface of the Earth has been lost.

In many cases the polarization of waves is not fixed, but rotates continually, somewhat at random. When this occurs the wave is said to be *elliptically polarized*. A gradual shift in polarization in a medium is known as *Faraday rotation*. For space communication, circular polarization is commonly used to overcome the effects of Faraday rotation. A circularly polarized wave rotates its polarization through 360° as it travels a distance of one wavelength in the propagation medium. The direction of rotation as viewed from the transmitting antenna defines the direction of circularity—right-hand (clockwise) or left-hand (counterclockwise). Linear and circular polarization may be considered as special cases of elliptical polarization.

Field Intensity

The energy from a propagated wave decreases with distance from the source. This decrease in strength is caused by the spreading of the wave energy over ever-larger spheres as the distance from the source increases.

A measurement of the strength of the wave at a distance from the transmitting antenna is its *field intensity*, which is synonymous with *field strength*. The strength of a wave is measured as the voltage between two points lying on an electric line of force in the plane of the wave front. The standard of measure for field intensity is the voltage developed in a wire that is 1 meter long, expressed as volts per meter. (If the wire were 2 meters long, the voltage developed would be divided by two to determine the field strength in volts per meter.)

The voltage in a wave is usually low, so the measurement is made in millivolts or microvolts per meter. The voltage goes through time variations like those of the current that caused the wave. It is measured like any other ac voltage—in terms of the effective value or, sometimes, the peak value. It is fortunate that in amateur work it is not necessary to measure actual field strength, as the equipment required is elaborate. We need to know only if an adjustment has been beneficial, so relative measurements are satisfactory. These can be made easily with home-built equipment.

Wave Attenuation

In free space, the field intensity of the wave varies inversely with the distance from the source, once you are in the radiating far field of the antenna. If the field strength at 1 mile from the source is 100 millivolts per meter, it will be 50 millivolts per meter at 2 miles, and so on. The relationship between field intensity and power density is similar to that for voltage and power in ordinary circuits. They are related by the impedance of free space, which is approximately 377 Ω. A field intensity of 1 volt per meter is therefore equivalent to a power density of

$$P = \frac{E^2}{Z} = \frac{1\,(\text{volt/m})^2}{377\,\Omega} = 2.65\,\text{mW/m}^2 \qquad \text{(Eq 2)}$$

Because of the relationship between voltage and power, the power density therefore varies with the square root of the field intensity, or inversely with the *square* of the distance. If the power density at 1 mile is 4 mW per square meter, then at a distance of 2 miles it will be 1 mW per square meter.

It is important to remember this so-called *spreading loss* when antenna performance is being considered. Gain can come only from narrowing the radiation pattern of an antenna, which concentrates the radiated energy in the desired direction. There is no "antenna magic" by which the total energy radiated can be increased.

In practice, attenuation of the wave energy may be much greater than the inverse-distance law would indicate. The wave does not travel in a vacuum, and the receiving antenna seldom is situated so there is a clear line of sight.

The Earth is spherical and the waves do not penetrate its surface appreciably, so communication beyond visual distances must be by some means that will bend the waves around the curvature of the Earth. These means involve additional energy losses that increase the path attenuation with distance, above that for the theoretical spreading loss in a vacuum.

Bending of Radio Waves

Radio waves and light waves are both propagated as electromagnetic energy. Their major difference is in wavelength, since radio-reflecting surfaces are usually much smaller in terms of wavelength than those for light. In material of a given electrical conductivity, long waves penetrate deeper than short ones, and so require a thicker mass for good reflection. Thin metal however is a good reflector of even long-wavelength radio waves. With poorer conductors, such as the Earth's crust, long waves may penetrate quite a few feet below the surface.

Reflection occurs at any boundary between materials of differing dielectric constant. Familiar examples with light are reflections from water surfaces and window panes. Both water and glass are transparent for light, but their dielectric constants are very different from that of air. Light waves, being very short, seem to bounce off both surfaces. Radio waves, being much longer, are practically unaffected by glass, but their behavior upon encountering water may vary, depending on the purity of that medium. Distilled water is a good insulator; salt water is a relatively good conductor.

Depending on their wavelength (and thus their frequency), radio waves may be reflected by buildings, trees, vehicles, the ground, water, ionized layers in the upper atmosphere, or at boundaries between air masses having different temperatures and moisture content. Ionospheric and atmospheric conditions are important in practically all communication beyond purely local ranges.

Refraction is the bending of a ray as it passes from one medium to another at an angle. The appearance of bending of a straight stick, where it enters water at an angle, is an example of light refraction known to us all. The degree of bending of radio waves at boundaries between air masses increases with the radio frequency. There is slight atmospheric bending in our HF bands. It becomes noticeable at 28 MHz, more so at 50 MHz, and it is much more of a factor in the higher VHF range and in UHF and microwave propagation.

Diffraction of light over a solid wall prevents total darkness on the far side from the light source. This is caused largely by the spreading of waves around the top of the wall, due to the interference of one part of the beam with another. The dielectric constant of the surface of the obstruction may affect what happens to our radio waves when they encounter terrestrial obstructions—but the radio *shadow area* is never totally dark. See Chapter 3, The Effects of Ground, for more information on diffraction.

The three terms, reflection, refraction and diffraction, were in use long before the radio age began. Radio propagation is nearly always a mix of these phenomena, and it may not be easy to identify or separate them while they are happening when we are on the air. This book tends to rely on the words *bending* and *scattering* in its discussions, with appropriate modifiers as needed. The important thing to remember is that any alteration of the path taken by energy as it is radiated from an antenna is almost certain to affect on-the-air results—which is why this chapter on propagation is included in an antenna book.

GROUND WAVES

As we have already seen, radio waves are affected in many ways by the media through which they travel. This has led to some confusion of terms in earlier literature concerning wave propagation. Waves travel close to the ground in several ways, some of which involve relatively little contact with the ground itself. The term *ground wave* has had several meanings in antenna literature, but it has come to be applied to any wave that stays close to the Earth, reaching the receiving point without leaving the Earth's lower atmosphere. This distinguishes the ground wave from a *sky wave*, which utilizes the ionosphere for propagation between the transmitting and receiving antennas.

The ground wave could be traveling in actual contact with the ground, as in Fig 1, where it is called the *surface wave*. Or it could travel directly between the transmitting and receiving antennas, when they are high enough so they can "see" each other—this is commonly called the *direct wave*. The ground wave also travels between the transmitting and receiving antennas by reflections or diffractions off intervening terrain between them. The ground-influenced wave may interact with the direct wave to create a vector-summed resultant at the receiver antenna.

In the generic term ground wave, we also will include ones that are made to follow the Earth's curvature by bending in the Earth's lower atmosphere, or *troposphere*, usually no more than a few miles above the ground. Often called *tropospheric bending*, this propagation mode is a major factor in amateur communications above 50 MHz.

THE SURFACE WAVE

The surface wave travels in contact with the Earth's surface. It can provide coverage up to about 100 miles in the standard AM broadcast band during the daytime, but attenuation is high. As can be seen from **Fig 3**, the attenuation increases with frequency. The surface wave is of little value in amateur communication, except possibly at 1.8 MHz. Vertically polarized antennas must be used, which tends to limit amateur surface-wave communication to where large vertical systems can be erected.

THE SPACE WAVE

Propagation between two antennas situated within line of sight of each other is shown in **Fig 4**. Energy traveling directly between the antennas is attenuated to about the same degree as in free space. Unless the antennas are very high or



Fig 3—Typical HF ground-wave range as a function of frequency.



Fig 4—The ray traveling directly from the transmitting antenna to the receiving antenna combines with a ray reflected from the ground to form the space wave. For a horizontally polarized signal a reflection as shown here reverses the phase of the ground-reflected ray.

quite close together, an appreciable portion of the energy is reflected from the ground. This reflected wave combines with direct radiation to affect the actual signal received.

In most communication between two stations on the ground, the angle at which the wave strikes the ground will be small. For a horizontally polarized signal, such a reflection reverses the phase of the wave. If the distances traveled by both parts of the wave were the same, the two parts would arrive out of phase, and would therefore cancel each other. The ground-reflected ray in Fig 4 must travel a little further, so the phase difference between the two depends on the lengths of the paths, measured in wavelengths. The wavelength in use is important in determining the useful signal strength in this type of communication.

If the difference in path length is 3 meters, the phase difference with 160-meter waves would be only 360° × 3/160 = 6.8°. This is a negligible difference from the 180° shift caused by the reflection, so the effective signal strength over the path would still be very small because of cancellation of the two waves. But with 6-meter radio waves the phase length would be 360° × 3/6 = 180°. With the additional 180° shift on reflection, the two rays would add. Thus, the space wave is a negligible factor at low frequencies, but it can be increasingly useful as the frequency is raised. It is a dominant factor in local amateur communication at 50 MHz and higher.

Interaction between the direct and reflected waves is the principle cause of *mobile flutter* observed in local VHF communication between fixed and mobile stations. The flutter effect decreases once the stations are separated enough so that the reflected ray becomes inconsequential. The reflected energy can also confuse the results of field-strength measurements during tests on VHF antennas.

As with most propagation explanations, the space-wave picture presented here is simplified, and practical considerations dictate modifications. There is always some energy loss when the wave is reflected from the ground. Further, the phase of the ground-reflected wave is not shifted exactly 180°, so the waves never cancel completely. At UHF, ground-reflection losses can be greatly reduced or eliminated by using highly directive antennas. By confining the antenna pattern to something approaching a flashlight beam, nearly all the energy is in the direct wave. The resulting energy loss is low enough that microwave relays, for example, can operate with moderate power levels over hundreds or even thousands of miles. Thus we see that, while the space wave is inconsequential below about 20 MHz, it can be a prime asset in the VHF realm and higher.

VHF/UHF PROPAGATION BEYOND LINE OF SIGHT

From Fig 4 it appears that use of the space wave depends on direct line of sight between the antennas of the communicating stations. This is not literally true, although that belief was common in the early days of amateur communication on frequencies above 30 MHz. When equipment became available that operated more efficiently and after antenna techniques were improved, it soon became clear that VHF waves were actually being bent or scattered in several ways, permitting reliable communication beyond visual distances between the two stations. This was found true even with low power and simple antennas. The average communication range can be approximated by assuming the waves travel in straight lines, but with the Earth's radius increased by one-third. The distance to the *radio horizon* is then given as

$$D_{miles} = 1.415\sqrt{H_{feet}} \qquad \text{(Eq 3)}$$

or

$$D_{km} = 4.124\sqrt{H_{meters}} \qquad \text{(Eq 4)}$$

where H is the height of the transmitting antenna, as shown in **Fig 5**. The formula assumes that the Earth is smooth out to the horizon, so any obstructions along the path must be taken into consideration. For an elevated receiving antenna the communication distance is equal to D + D1, that is, the sum of the distances to the horizon of both



Fig 5—The distance D to the horizon from an antenna of height H is given by equations in the text. The maximum line-of-sight distance between two elevated antennas is equal to the sum of their distances to the horizon as indicated here.

antennas. Radio horizon distances are given in graphic form in **Fig 6**. Two stations on a flat plain, one with its antenna 60 feet above ground and the other 40 feet, could be up to about 20 miles apart for strong-signal line-of-sight communication (11 + 9 mi). The terrain is almost never completely flat, however, and variations along the way may add to or subtract from the distance for reliable communication. Remember that energy is absorbed, reflected or scattered in many ways in nearly all communication situations. The formula or the chart will be a good guide for estimating the potential radius of coverage for a VHF FM repeater, assuming the users are mobile or portable with simple, omnidirectional antennas. Coverage with optimum home-station equipment, high-gain directional arrays, and SSB or CW is quite a different matter. A much more detailed method for estimating coverage on frequencies above 50 MHz is given later in this chapter.

For maximum use of the ordinary space wave it is important to have the antenna as high as possible above nearby buildings, trees, wires and surrounding terrain. A hill that rises above the rest of the countryside is a good location for an amateur station of any kind, and particularly so for extensive coverage on the frequencies above 50 MHz. The highest point on such an eminence is not necessarily the best location for the antenna. In the example shown in **Fig 7**, the hilltop would be a good site in all directions. But if maximum performance to the right is the objective, a point just below the crest might do better. This would involve a trade-off with reduced coverage in the opposite direction. Conversely, an antenna situated on the left side, lower down the hill, might do well to the left, but almost certainly would be inferior in performance to the right.

Selection of a home site for its radio potential is a complex business, at best. A VHF enthusiast dreams of the highest hill. The DX-minded HF ham may be more attracted by a dry spot near a salt marsh. A wide saltwater horizon, especially from a high cliff, just smells of DX. In shopping for ham radio real estate, a mobile or portable rig for the frequencies you're most interested in can provide useful clues.



Fig 6—Distance to the horizon from an antenna of given height. The solid curve includes the effect of atmospheric retraction. The optical line-of-sight distance is given by the broken curve.



Fig 7—Propagation conditions are generally best when the antenna is located slightly below the top of a hill on the side facing the distant station. Communication is poor when there is a sharp rise immediately in front of the antenna in the direction of communication.

ANTENNA POLARIZATION

If effective communication over long distances were the only consideration, we might be concerned mainly with radiation of energy at the lowest possible angle above the horizon. However, being engaged in a residential avocation often imposes practical restrictions on our antenna projects. As an example, our 1.8 and 3.5-MHz bands are used primarily for short-distance communication because they serve that purpose with antennas that are not difficult or expensive to put up. Out to a few hundred miles, simple wire antennas for these bands do well, even though their radiation is mostly at high angles above the horizon. Vertical systems might be better for long-distance use, but they require extensive ground systems for good performance.

Horizontal antennas that radiate well at low angles are most easily erected for 7 MHz and higher frequencies—horizontal wires and arrays are almost standard practice for work on 7 through 29.7 MHz. Vertical antennas, such as a single omnidirectional antenna of multiband design, are also used in this frequency range. An antenna of this type may be a good solution to the space problem for a city dweller on a small lot, or even for the resident of an apartment building.

High-gain antennas are almost always used at 50 MHz and higher frequencies, and most of them are horizontal. The principal exception is mobile communication with FM through repeaters, discussed in Chapter 17, Repeater Antenna Systems. The height question is answered easily for VHF enthusiasts—the higher the better.

The theoretical and practical effects of height above ground at HF are treated in detail in Chapter 3, The Effects of Ground. Note that it is the height in *wavelengths* that is important—a good reason to think in the metric system, rather than in feet and inches.

In working locally on any amateur frequency band, best results will be obtained with the same polarization at both stations, except on rare occasions when polarization shift is caused by terrain obstructions or reflections from buildings. Where such a shift is observed, mostly above 100 MHz or so, horizontal polarization tends to work better than vertical. This condition is found primarily on short paths, so it is not too important. Polarization shift may occur on long paths where tropospheric bending is a factor, but here the effect tends to be random. Long-distance communication by way of the ionosphere produces random polarization effects, so polarization matching is of little or no importance. This is fortunate for the HF mobile enthusiast, who will find that even his short, inductively loaded whips work very well at all distances other than local.

Because it responds to all plane polarizations equally, circular polarization may pay off on circuits where the arriving polarization is random, but it exacts a 3-dB penalty when used with a single-plane polarization of any kind. Circular systems find greatest use in work with orbiting satellites. It should be remembered that “horizontal” and “vertical” are meaningless terms in space, where the plane-Earth reference is lost.

Polarization Factors Above 50 MHz

In most VHF communication over short distances, the polarization of the space wave tends to remain constant. Polarization discrimination is high, usually in excess of 20 dB, so the same polarization should be used at both ends of the circuit. Horizontal, vertical and circular polarization all have certain advantages above 50 MHz, so there has never been complete standardization on any one of them.

Horizontal systems are popular, in part because they tend to reject man-made noise, much of which is vertically polarized. There is some evidence that vertical polarization shifts to horizontal in hilly terrain, more readily than horizontal shifts to vertical. With large arrays, horizontal systems may be easier to erect, and they tend to give higher signal strengths over irregular terrain, if any difference is observed.

Practically all work with VHF mobiles is now handled with vertical systems. For use in a VHF repeater system, the vertical antenna can be designed to have gain without losing the desired omnidirectional quality. In the mobile station a small vertical whip has obvious aesthetic advantages. Often a telescoping whip used for broadcast reception can be pressed into service for the 144-MHz FM rig. A car-top mount is preferable, but the broadcast whip is a practical compromise. Tests with at least one experimental repeater have shown that horizontal polarization can give a slightly larger service area, but mechanical advantages of vertical systems have made them the almost unanimous choice in VHF FM communication. Except for the repeater field, horizontal is the standard VHF system almost everywhere.

In communication over the Earth-Moon-Earth (EME) route the polarization picture is blurred, as might be expected with such a diverse medium. If the moon were a flat target, we could expect a 180° phase shift from the moon reflection process. But it is not flat. This plus the moon’s *libration* (its slow oscillation, as viewed from the Earth), and the fact that waves must travel both ways through the Earth’s entire atmosphere and magnetic field, provide other variables that confuse the phase and polarization issue. Building a huge array that will track the moon, and give gains in excess of 20 dB, is enough of a task that most EME enthusiasts tend to take their chances with phase and polarization problems. Where rotation of the element plane has been tried it has helped to stabilize signal levels, but it is not widely employed.

PROPAGATION OF VHF WAVES

The wave energy of VHF stations does not simply disappear once it reaches the radio horizon. It is scattered, but it can be heard to some degree for hundreds of miles, well beyond line-of-sight range. Everything on Earth, and in the regions of space up to at least 100 miles, is a potential forward-scattering agent.

Tropospheric scatter is always with us. Its effects are often hidden, masked by more effective propagation modes on the lower frequencies. But beginning in the VHF range, scatter from the lower atmosphere extends the reliable range markedly if we make use of it. Called *troposcatter*, this is what produces that nearly flat portion of the curves that will be described later (in the section where you can compute reliable VHF coverage range). With a decent station, you can consistently make troposcatter contacts out to 300 miles out on the VHF and even UHF bands, especially if you don’t mind weak signals and something less than 99% reliability. As long ago as the early 1950s, VHF enthusiasts found that VHF contests could be won with high power, big antennas and a good ear for signals deep in the noise. They still can.

Ionospheric scatter works much the same as the tropo version, except that the scattering medium is higher up, mainly the E region of the ionosphere but with some help from the D and F layers too. Ionospheric scatter is useful mainly above the MUF, so its useful frequency range depends on geography, time of day, season, and the state of the Sun. With near maximum legal power, good antennas and quiet locations, ionospheric scatter can fill in the skip zone with marginally readable signals scattered from ionized trails of meteors, small areas of random ionization, cosmic dust, satellites and whatever may come into the antenna patterns at 50 to 150 miles or so above the Earth. It's mostly an E-layer business, so it works all E-layer distances. Good antennas and keen ears help.

Transequatorial propagation (TE) was an amateur 50-MHz discovery in the years 1946-1947. Amateurs of all continents observed it almost simultaneously on three separate north-south paths. These amateurs tried to communicate at 50 MHz, even though the predicted MUF was around 40 MHz for the favorable daylight hours. The first success came at night, when the MUF was thought to be even lower. A remarkable research program inaugurated by amateurs in Europe, Cyprus, Zimbabwe and South Africa eventually provided technically sound theories to explain the then-unknown mode.

It has been known for years that the MUF is higher and less seasonally variable on transequatorial circuits, but the full extent of the difference was not learned until amateur work brought it to light. As will be explained in a later section in more detail, the ionosphere over equatorial regions is higher, thicker and more dense than elsewhere. Because of its more constant exposure to solar radiation, the equatorial belt has high nighttime-MUF possibilities. TE can often work marginally at 144 MHz, and even at 432 MHz on occasion. The potential MUF varies with solar activity, but not to the extent that conventional F-layer propagation does. It is a late-in-the-day mode, taking over about when normal F-layer propagation goes out.

The TE range is usually within about 4000 km (2500 miles) either side of the geomagnetic equator. The Earth's magnetic axis is tilted with respect to the geographical axis, so the TE belt appears as a curving band on conventional flat maps of the world. See **Fig 8**. As a result, TE has a different latitude coverage in the Americas from that from Europe to Africa. The TE belt just reaches into the southern continental US. Stations in Puerto Rico, Mexico and even the northern parts of South America encounter the mode more often than those in favorable US areas. It is no accident that TE was discovered as a result of 50-MHz work in Mexico City and Buenos Aires.

Within its optimum regions of the world, the TE mode extends the usefulness of the 50-MHz band far beyond that of conventional F-layer propagation, since the practical TE MUF runs around 1.5 times that of normal F_2. Both its seasonal and diurnal characteristics are extensions of what is considered normal for 50-MHz propagation. In that part of the Americas south of about 20° North latitude, the existence of TE affects the whole character of band usage, especially in years of high solar activity.



Fig 8—Transequatorial spread-F propagation takes place between stations equidistant across the geomagnetic equator. Distances up to 8000 km (5000 miles) are possible on 28 through 432 MHz. Note that the geomagnetic equator is considerably south of the geographic equator in the Western Hemisphere. (*Figure courtesy of The ARRL Handbook*.)

Weather Effects on VHF/UHF Tropospheric Propagation

Changes in the dielectric constant of the medium can affect propagation. Varied weather patterns over most of the Earth's surface can give rise to boundaries between air masses of very different temperature and humidity characteristics. These boundaries can be anything from local anomalies to air-circulation patterns of continental proportions.

Under stable weather conditions, large air masses can retain their characteristics for hours or even days at a time. See **Fig 9**. Stratified warm dry air over cool moist air, flowing slowly across the Great Lakes region to the Atlantic Seaboard, can provide the medium for east-west communication on 144 MHz and higher amateur frequencies over as much as 1200 miles. More common, however, are communication distances of 400 to 600 miles under such conditions.

A similar inversion along the Atlantic Seaboard as a result of a tropical storm air-circulation pattern may bring VHF and UHF openings extending from the Maritime Provinces of Canada to the Carolinas. Propagation across the Gulf of Mexico, sometimes with very high signal levels, enlivens the VHF scene in coastal areas from Florida to Texas. The California coast, from below the San Francisco Bay Area to Mexico, is blessed with a similar propagation aid during the warmer months. Tropical storms moving west, across the Pacific below the Hawaiian Islands, may provide a transpacific long-distance VHF medium. Amateurs first exploited this on 144, 220 and 432 MHz, in 1957. It has been used fairly often in the summer months since, although not yearly.

The examples of long-haul work cited above may occur infrequently, but lesser extensions of the minimum operating range are available almost daily. Under minimum conditions there may be little more than increased signal strength over paths that are workable at any time.

There is a diurnal effect in temperate climates. At sunrise the air aloft is warmed more rapidly than that near the Earth's surface, and as the Sun goes lower late in the day the upper air is kept warm, while the ground cools. In fair, calm weather such sunrise and sunset temperature inversions can improve signal strength over paths beyond line of sight as much as 20 dB over levels prevailing during the hours of high sun. The diurnal inversion may also extend the operating range for a given strength by some 20 to 50%. If you would be happy with a new VHF antenna, try it first around sunrise!

There are other short-range effects of local atmospheric and topographical conditions. Known as *subsidence*, the flow of cool air down into the bottom of a valley, leaving warm air aloft, is a familiar summer-evening pleasure. The daily inshore-offshore wind shift along a seacoast in summer sets up daily inversions that make coastal areas highly favored as VHF sites. Ask any jealous 144-MHz operator who lives more than a few miles inland.

Tropospheric effects can show up at any time, in any season. Late spring and early fall are the most favored periods, although a winter warming trend can produce strong and stable inversions that work VHF magic almost equal to that of the more familiar spring and fall events.



Fig 9—Upper air conditions that produce extended-range communication on the VHF bands. At the top is shown the US Standard Atmosphere temperature curve. The humidity curve (dotted) is what would result if the relative humidity were 70%, from ground level to 12,000 feet elevation. There is only slight refraction under this standard condition. At the bottom is shown a sounding that is typical of marked refraction of VHF waves. Figures in parentheses are the "mixing ratio" —grams of water vapor per kilogram of dry air. Note the sharp break in both curves at about 3500 feet.

Regions where the climate is influenced by large bodies of water enjoy the greatest degree of tropospheric bending. Hot, dry desert areas see little of it, at least in the forms described above.

Tropospheric Ducting

Tropospheric propagation of VHF and UHF waves can influence signal levels at all distances from purely local to something beyond 4000 km (2500 miles). The outer limits are not well known. At the risk of over simplification, we will divide the modes into two classes—extended local and long distance. This concept must be modified depending on the frequency under consideration, but in the VHF range the extended-local effect gives way to a form of propagation much like that of microwaves in a waveguide, called *ducting*. The transition distance is ordinarily somewhere around 200 miles. The difference lies in whether the atmospheric condition producing the bending is localized or continental in scope. Remember, we're concerned here with frequencies in the VHF range, and perhaps up to 500 MHz. At 10 GHz, for example, the scale is much smaller.

In VHF propagation beyond a few hundred miles, more than one weather front is probably involved, but the wave is propagated between the inversion layers and ground, in the main. On long paths over the ocean (two notable examples are California to Hawaii and Ascension Island to Brazil), propagation is likely to be between two atmospheric layers. On such circuits the communicating station antennas must be in the duct, or capable of propagating strongly into it. Here again, we see that the positions and radiation angles of the antennas are important. As with microwaves in a waveguide, the low-frequency limit for the duct is critical. In long-distance ducting it is also very variable. Airborne equipment has shown that duct capability exists well down into the HF region in the stable atmosphere west of Ascension Island. Some contacts between Hawaii and Southern California on 50 MHz are believed to have been by way of tropospheric ducts. Probably all contact over these paths on 144 MHz and higher bands is because of duct propagation.

Amateurs have played a major part in the discovery and eventual explanation of tropospheric propagation. In recent years they have shown that, contrary to beliefs widely held in earlier times, long-distance communication using tropospheric modes is possible to some degree on all amateur frequencies from 50 to at least 10,000 MHz.

RELIABLE VHF COVERAGE

In the preceding sections we discussed means by which amateur bands above 50 MHz may be used intermittently for communication far beyond the visual horizon. In emphasizing distance we should not neglect a prime asset of the VHF band: reliable communication over relatively short distances. The VHF region is far less subject to disruption of local communication than are frequencies below 30 MHz. Since much amateur communication is essentially local in nature, our VHF assignments can carry a great load, and such use of the VHF bands helps solve interference problems on lower frequencies.

Because of age-old ideas, misconceptions about the coverage obtainable in our VHF bands persist. This reflects the thoughts that VHF waves travel only in straight lines, except when the DX modes described above happen to be present. However, let us survey the picture in the light of modern wave-propagation knowledge and see what the bands above 50 MHz are good for on a day-to-day basis, ignoring the anomalies that may result in extensions of normal coverage.

It is possible to predict with fair accuracy how far you should be able to work consistently on any VHF or UHF band, provided a few simple facts are known. The factors affecting operating range can be reduced to graph form, as described in this section. The information was originally published in November 1961 *QST* by D. W. Bray, K2LMG (see the Bibliography at the end of this chapter).

To estimate your station's capabilities, two basic numbers must be determined: station gain and path loss. Station gain is made up of seven factors: receiver sensitivity, transmitted power, receiving antenna gain, receiving antenna height gain, transmitting antenna gain, transmitting antenna height gain and required signal-to-noise ratio. This looks complicated but it really boils down to an easily made evaluation of receiver, transmitter, and antenna performance. The other number, path loss, is readily determined from the nomogram, **Fig 10**. This gives path loss over smooth Earth, for 99% reliability.

For 50 MHz, lay a straightedge from the distance between stations (left side) to the appropriate distance at the right side. For 1296 MHz, use the full scale, right center. For 144, 222 and 432, use the dot in the circle, square or triangle, respectively. Example: At 300 miles the path loss for 144 MHz is 214 dB.

To be meaningful, the losses determined from this nomograph are necessarily greater than simple free-space path losses. As described in an earlier section, communication beyond line-of-sight distances involves propagation modes that increase the path attenuation with distance.

VHF/UHF Station Gain

The largest of the eight factors involved in station design is receiver sensitivity. This is obtainable from **Fig 11**, if you know the approximate receiver noise figure and transmission-line loss. If you can't measure noise figure, assume 3 dB for 50 MHz, 5 for 144 or 222, 8 for 432 and 10 for 1296 MHz, if you know your equipment is working moderately well. These noise figures are well on the conservative side for modern solid-state receivers.

Line loss can be taken from information in Chapter 24 for the line in use, if the antenna system is fed properly. Lay a straightedge between the appropriate points at either side of Fig 11, to find effective receiver sensitivity in decibels below 1 watt (dBW). Use the narrowest bandwidth that is practical for the emission intended, with the receiver you will be using. For CW, an average value for effective work



Fig 10—Nomogram for finding the capabilities of stations on amateur bands from 50 to 1300 MHz. Either the path loss for a given distance or vice versa may be found if one of the two factors is known.

is about 500 Hz. Phone bandwidth can be taken from the receiver instruction manual, but it usually falls between 2.1 to 2.7 kHz.

Antenna gain is next in importance. Gains of amateur antennas are often exaggerated. For well-designed Yagis the gain (over isotropic) run close to 10 times the boom length in wavelengths. (Example: A 24-foot Yagi on 144 MHz is 3.6 wavelengths long; 3.6 x 10 = 36, and 10 $\log_{10}$ 36 = 15.5 dBi in free space.) Add 3 dB for stacking, where used properly. Add 4 dB more for ground reflection gain. This varies in amateur work, but averages out near this figure.

We have one more plus factor—antenna height gain, obtained from **Fig 12**. Note that this is greatest for short distances. The left edge of the horizontal center scale is for 0 to 10 miles, the right edge for 100 to 500 miles. Height gain for 10 to 30 feet is assumed to be zero. For 50 feet the height gain is 4 dB at 10 miles, 3 dB at 50 miles, and 2 dB at 100 miles. At 80 feet the height gains are roughly 8, 6 and 4 dB for these distances. Beyond 100 miles the height gain is nearly uniform for a given height, regardless of distance.

Transmitter power output must be stated in decibels above 1 watt. If you have 500 W output, add 10 log (500/1), or 27 dB, to your station gain. The transmission-line loss must be subtracted from the station gain. So must the required signal-to-noise ratio. The information is based on CW work, so the additional signal needed for other modes must be subtracted. Use a figure of 3 dB for SSB. Fading losses must be accounted for also. It has been shown that for distances beyond 100 miles, the signal will vary plus or minus about 7 dB from the average level, so 7 dB must be subtracted from the station gain for high reliability. For distances under 100 miles, fading diminishes almost linearly with distance. For 50 miles, use –3.5 dB for fading.

What It All Means

Add all the plus and minus factors to get the station gain. Use the final value to find the distance over which you can expect to work reliably from the nomogram, Fig 10. Or work it the other way around: Find the path loss for the distance you want to cover from the nomogram and then figure out what station changes will be needed to overcome it.

The significance of all this becomes more obvious when we see path loss plotted against frequency for the various bands, as in **Fig 13**. At the left this is done for 50% reliability. At the right is the same information for 99% reliability.



Fig 11—Nomogram for finding effective receiver sensitivity.

For near-perfect reliability, a path loss of 195 dB (easily encountered at 50 or 144 MHz) is involved in 100-mile communication. But look at the 50% reliability curve: The same path loss takes us out to well over 250 miles. Few amateurs demand near-perfect reliability. By choosing our times, and by accepting the necessity for some repeats or occasional loss of signal, we can maintain communication out to distances far beyond those usually covered by VHF stations.

Working out a few typical amateur VHF station setups with these curves will show why an understanding of these factors is important to any user of the VHF spectrum. Note that path loss rises very steeply in the first 100 miles or so. This is no news to VHF operators; locals are very strong, but stations 50 or 75 miles away are much weaker. What happens beyond 100 miles is not so well known to many of us.

From the curves of Fig 13, we see that path loss levels off markedly at what is the approximate limit of working range for average VHF stations using wideband modulation modes. Work out the station gain for a 50-W station with an average receiver and antenna, and you'll find that it comes out around 180 dB. This means you'd have about a 100-mile working radius in average terrain, for good but not perfect reliability. Another 10 dB may extend the range to as much as 250 miles. Just changing from AM phone to SSB and CW makes a major improvement in daily coverage on the VHF bands.

A bigger antenna, a higher one if your present beam is not at least 50 feet up, an increase in power to 500 W from 50 W, an improvement in receiver noise figure if it is presently poor—any of these things can make a big improvement in reliable coverage. Achieve all of them, and you will have very likely tripled your sphere of influence, thanks to that hump in the path-loss curves. This goes a long way toward explaining why using a 10-W packaged station with a small antenna, fun though it may be, does not begin to show what the VHF bands are really good for.

Terrain at VHF/UHF

The coverage figures derived from the above procedure are for average terrain. What of stations in mountainous country? Although an open horizon is generally desirable for the VHF station site, mountain country should not be



Fig 12—Nomogram for determining antenna-height gain.



Fig 13—Path loss versus distance for amateur frequencies above 50 MHz. At A are curves for 50% of the time; at B, for 99%. The curves at A are more representative of Amateur Radio requirements.

considered hopeless. Help for the valley dweller often lies in the optical phenomenon known as *knife-edge diffraction*. A flashlight beam pointed at the edge of a partition does not cut off sharply at the partition edge, but is diffracted around it, partially illuminating the shadow area. A similar effect is observed with VHF waves passing over ridges; there is a shadow effect, but not a complete blackout. If the signal is strong where it strikes the mountain range, it will be heard well in the bottom of a valley on the far side. (See Chapter 3, The Effects of Ground, for a more thorough discussion of the theory of diffraction.)

This is familiar to all users of VHF communications equipment who operate in hilly terrain. Where only one ridge lies in the way, signals on the far side may be almost as good as on the near side. Under ideal conditions (a very high and sharp-edged obstruction near the midpoint of a long-enough path so that signals would be weak over average terrain), knife-edge diffraction may yield signals even stronger than would be possible with an open path.

The obstruction must project into the radiation patterns of the antennas used. Often mountains that look formidable to the viewer are not high enough to have an appreciable effect, one way or the other. Since the normal radiation pattern from a VHF array is several degrees above the horizontal, mountains that are less than about three degrees above the horizon, as seen from the antenna, are missed by the radiation from the array. Moving the mountains out of the way would have substantially no effect on VHF signal strength in such cases.

Rolling terrain, where obstructions are not sharp enough to produce knife-edge diffraction, still does not exhibit a complete shadow effect. There is no complete barrier to VHF propagation—only attenuation, which varies widely as the result of many factors. Thus, even valley locations are usable for VHF communication. Good antenna systems, preferably as high as possible, the best available equipment, and above all, the willingness and ability to work with weak signals may make outstanding VHF work possible, even in sites that show little promise by casual inspection.

AURORAL PROPAGATION

The Earth has a *magnetosphere* or magnetic field surrounding it. NASA scientists have described the magnetosphere as a sort of protective "bubble" around the Earth that shields us from the solar wind. Under normal circumstances, there are lots of electrons and protons moving in our magnetosphere, traveling along magnetic lines of force that trap them and keep them in place, neither bombarding the earth nor escaping into outer space.

Sudden bursts of activity on the Sun are sometimes accompanied by the ejection of charged particles, often from so-called Coronal Mass Ejections (CME) because they originate from the Sun's outer coronal region. These charged particles can interact with the magnetosphere, compressing and distorting it. If the orientation of the magnetic field contained in a large blast of solar wind or in a CME is aligned opposite to that of the Earth's magnetic field, the magnetic bubble can partially collapse and the particles normally trapped there can be deposited into the Earth's atmosphere along magnetic lines near the North or South poles. This produces a visible or radio *aurora*. An aurora is visible if the time of entry is after dark.

The visible aurora is, in effect, fluorescence at E-layer height—a curtain of ions capable of refracting radio waves in the frequency range above about 20 MHz. D-region absorption increases on lower frequencies during auroras. The exact frequency ranges depend on many factors: time, season, position with relation to the Earth's auroral regions, and the level of solar activity at the time, to name a few.

The auroral effect on VHF waves is another amateur discovery, this one dating back to the 1930s. The discovery came coincidentally with improved transmitting and receiving techniques then. The returning signal is diffused in frequency by the diversity of the auroral curtain as a refracting (scattering) medium. The result is a modulation of a CW signal, from just a slight burbling sound to what is best described as a "keyed roar." Before SSB took over in VHF work, voice was all but useless for auroral paths. A sideband signal suffers, too, but its narrower bandwidth helps to retain some degree of understandability. Distortion induced by a given set of auroral conditions increases with the frequency in use. 50-MHz signals are much more intelligible than those on 144 MHz on the same path at the same time. On 144 MHz, CW is almost mandatory for effective auroral communication.

The number of auroras that can be expected per year varies with the geomagnetic latitude. Drawn with respect to the Earth's magnetic poles instead of the geographical ones, these latitude lines in the US tilt upward to the northwest. For example, Portland, Oregon, is 2° farther north (geographic latitude) than Portland, Maine. The Maine city's geomagnetic latitude line crosses the Canadian border before it gets as far west as its Oregon namesake. In terms of auroras intense enough to produce VHF propagation results, Portland, Maine, is likely to see about 10 times as many per year. Oregon's auroral prospects are more like those of southern New Jersey or central Pennsylvania.

The antenna requirements for auroral work are mixed. High gain helps, but the area of the aurora yielding the best returns sometimes varies rapidly, so sharp directivity can be a disadvantage. So could a very low radiation angle, or a beam pattern very sharp in the vertical plane. Experience indicates that few amateur antennas are sharp enough in either plane to present a real handicap. The beam heading for maximum signal can change, however, so a bit of scanning in azimuth may turn up some interesting results. A very large array, such as is commonly used for moonbounce (with azimuth-elevation control), should be worthwhile.

The incidence of auroras, their average intensity, and their geographical distribution as to visual sightings and VHF propagation effects all vary to some extent with solar activity. There is some indication that the peak period for auroras lags the sunspot-cycle peak by a year or two. Like sporadic E, an unusual auroral opening can come at any season. There is a marked diurnal swing in the number of auroras. Favored times are late afternoon and early evening, late evening through early morning, and early afternoon, in about that order. Major auroras often start in early afternoon and carry through to early morning the next day.

HF Sky-Wave Propagation

As described earlier, the term *ground wave* is commonly applied to propagation that is confined to the Earth's lower atmosphere. Now we will use the term *sky wave* to describe modes of propagation that use the Earth's ionosphere. First, however, we must examine how the Earth's ionosphere is affected by the Sun.

THE ROLE OF THE SUN

Everything that happens in radio propagation, as with all life on Earth, is the result of radiation from the Sun. The variable nature of radio propagation here on Earth reflects the ever-changing intensity of ultraviolet and X-ray radiation, the primary ionizing agents in solar energy. Every day, solar nuclear reactions are turning hydrogen into helium, releasing an unimaginable blast of energy into space in the process. The total power radiated by the Sun is estimated at 4×10^{23} kW—that is, the number four followed by 23 zeroes. At its surface, the Sun creates about 60 *megawatts* per square meter. That is a very potent transmitter!

The Solar Wind

The Sun is constantly ejecting material from its surface in all directions into space, making up the so-called *solar wind*. Under relatively quiet solar conditions the solar wind blows around 200 miles per second—675,000 miles per hour—taking away about two million tons of solar material each second from the Sun. You needn't worry—the Sun is not going to shrivel up anytime soon. It's big enough that it will take many billions of years before that happens.

A 675,000 mile/hour wind sounds like a pretty stiff breeze, doesn't it? Lucky for us, the density of the material in the solar wind is very small by the time it has been spread out into interplanetary space. Scientists calculate that the density of the particles in the solar wind is less than that of the best vacuum they've ever achieved on Earth. Despite the low density of the material in the solar wind, the effect on the Earth, especially its magnetic field, is very significant.

Before the advent of sophisticated satellite sensors, the Earth's magnetic field was considered to be fairly simple, modeled as if the Earth were a large bar magnet. The axis of this hypothetical bar magnet is oriented about 11° away from the geographic north-south pole. We now know that the solar wind alters the shape of the Earth's magnetic field significantly, compressing it on the side facing the Sun and elongating it on the other side—in the same manner as the tail of a comet is stretched out radially in its orientation from the Sun. In fact, the solar wind is also responsible for the shape of a comet's tail.

Partly because of the very nature of the nuclear reactions going on at the Sun itself, but also because of variations in the speed and direction of the solar wind, the interactions between the Sun and our Earth are incredibly complex. Even scientists who have studied the subject for years do not completely understand everything that happens on the Sun. Later in this chapter, we'll investigate the effects of the solar wind when conditions on the Sun are *not* "quiet." As far as amateur HF skywave propagation is concerned, the results of disturbed conditions on the Sun are not generally beneficial.

Sunspots

The most readily observed characteristic of the Sun, other than its blinding brilliance, is its tendency to have grayish black blemishes, seemingly at random times and at random places, on its fiery surface. (See **Fig 14**.) There are written records of naked-eye sightings of *sunspots* in the Orient back to more than 2000 years ago. As far as is known, the first indication that sunspots were recognized as part of the Sun was the result of observations by Galileo in the early 1600s, not long after he developed one of the first practical telescopes.

Galileo also developed the projection method for observing the Sun safely, but probably not before he had suffered severe eye damage by trying to look at the Sun di-



Fig 14—Much more than sunspots can be seen when the sun is viewed through selective optical filters. This photo was taken through a hydrogen-alpha filter that passes a narrow light segment at 6562 angstroms. The bright patches are active areas around and often between sunspots. Dark irregular lines are filaments of activity having no central core. Faint magnetic field lines are visible around a large sunspot group near the disc center. (*Photo courtesy of Sacramento Peak Observatory, Sunspot, New Mexico*).

rectly. (He was blind in his last years.) His drawings of sunspots, indicating their variable nature and position, are the earliest such record known to have been made. His reward for this brilliant work was immediate condemnation by church authorities of the time, which probably set back progress in learning more about the Sun for generations.

The systematic study of solar activity began about 1750, so a fairly reliable record of sunspot numbers goes back that far. (There are some gaps in the early data.) The record shows clearly that the Sun is always in a state of change. It never looks exactly the same from one day to the next. The most obvious daily change is the movement of visible activity centers (sunspots or groups thereof) across the solar disc, from east to west, at a constant rate. This movement was soon found to be the result of the rotation of the Sun, at a rate of approximately four weeks for a complete round. The average is about 27.5 days, the Sun's *synodic* rotation speed, viewed from the perspective of the Earth, which is also moving around the Sun in the same direction as the Sun's rotation.

Sunspot Numbers

Since the earliest days of systematic observation, our traditional measure of solar activity has been based on a count of sunspots. In these hundreds of years we have learned that the average number of spots goes up and down in cycles very roughly approximating a sine wave. In 1848, a method was introduced for the daily measurement of sunspot numbers. That method, which is still used today, was devised by the Swiss astronomer Johann Rudolph Wolf. The observer counts the total number of spots visible on the face of the Sun and the number of groups into which they are clustered, because neither quantity alone provides a satisfactory measure of sunspot activity. The observer's sunspot number for that day is computed by multiplying the number of groups he sees by 10, and then adding to this value the number of individual spots. Where possible, sunspot data collected prior to 1848 have been converted to this system.

As can readily be understood, results from one observer to another can vary greatly, since measurement depends on the capability of the equipment in use and on the stability of the Earth's atmosphere at the time of observation, as well as on the experience of the observer. A number of observatories around the world cooperate in measuring solar activity. A weighted average of the data is used to determine the *International Sunspot Number* or ISN for each day. (Amateur astronomers can approximate the determination of ISN values by multiplying their values by a correction factor determined empirically.)

A major step forward was made with the development of various methods for observing narrow portions of the Sun's spectrum. Narrowband light filters that can be used with any good telescope perform a visual function very similar to the aural function of a sharp filter added to a communications receiver. This enables the observer to see the actual area of the Sun doing the radiating of the ionizing energy, in addition to the sunspots, which are more a by-product than a cause. The photo of Fig 14 was made through such a filter. Studies of the ionosphere with instrumented probes, and later with satellites, manned and unmanned, have added greatly to our knowledge of the effects of the Sun on radio communication.

Daily sunspot counts are recorded, and monthly and yearly averages determined. The averages are used to see trends and observe patterns. Sunspot records were formerly kept in Zurich, Switzerland, and the values were known as *Zurich Sunspot Numbers*. They were also known as Wolf sunspot numbers. The official international sunspot numbers are now compiled at the Sunspot Index Data Center in Bruxelles, Belgium.

The yearly means (averages) of sunspot numbers from 1700 through 2002 are plotted in **Fig 15**. The cyclic nature of solar activity becomes readily apparent from this graph. The duration of the cycles varies from 9.0 to 12.7 years, but averages approximately 11.1 years, usually referred to as the 11-year solar cycle. The first complete cycle to be observed systematically began in 1755, and is numbered Cycle 1. Solar cycle numbers thereafter are consecutive. Cycle 23 began in October, 1996.

The "Quiet" Sun

For more than 60 years it has been well known that radio propagation phenomena vary with the number and size of sunspots, and also with the position of sunspots on the surface of the Sun. There are daily and seasonal variations in the Earth's ionized layers resulting from changes in the amount of ultraviolet light received from the Sun. The 11-year sunspot cycle affects propagation conditions because there is a direct correlation between sunspot activity and ionization.



Fig 15—Yearly means of smoothed sunspot numbers from data for 1700 through 2002. This plot clearly shows that sunspot activity takes place in cycles of approximately 11 years duration. There is also a longer-term periodicity in this plot, the Gleissberg 88-year cycle. Cycle 1, the first complete cycle to be examined by systematic observation, began in 1755.

Activity on the surface of the Sun is changing continually. In this section we want to describe the activity of the so-called *quiet Sun*, meaning those times when the Sun is not doing anything more spectacular than acting like a "normal" thermonuclear ball of flaming gases. The Sun and its effects on Earthly propagation can be described in *statistical* terms—that's what the 11-year solar cycle does. You may experience vastly different conditions on any particular day compared to what a long-term average would suggest.

An analogy may be in order here. Have you ever gazed into a relatively calm campfire and been surprised when suddenly a flaming ember or a large spark was ejected in your direction? The Sun can also do unexpected and sometimes very dramatic things. Disturbances of propagation conditions here on Earth are caused by disturbed conditions on the Sun. More on this later.

Individual sunspots may vary in size and appearance, or even disappear totally, within a single day. In general, larger active areas persist through several rotations of the Sun. Some active areas have been identified over periods up to about a year. Because of these continual changes in solar activity, there are continual changes in the state of the Earth's ionosphere and resulting changes in propagation conditions. A short-term burst of solar activity may trigger unusual propagation conditions here on Earth lasting for less than an hour.

Smoothed Sunspot Numbers (SSN)

Sunspot data are averaged or smoothed to remove the effects of short-term changes. The sunspot values used most often for correlating propagation conditions are *Smoothed Sunspot Numbers* (SSN), often called 12-month running average values. Data for 13 consecutive months are required to determine a smoothed sunspot number.

Long-time users have found that the upper HF bands are reliably open for propagation only when the average number of sunspots is above certain minimum levels. For example, between mid 1988 to mid 1992 during Cycle 22, the SSN stayed higher than 100. The 10-meter band was open then almost all day, every day, to some part of the world. However, by mid 1996, few if any sunspots showed up on the Sun and the 10-meter band consequently was rarely open. Even 15 meters, normally a workhorse DX band when solar activity is high, was closed most of the time during the low point in Cycle 22. So far as propagation on the upper HF bands is concerned, the higher the sunspot number, the better the conditions.

Each smoothed number is an average of 13 monthly means, centered on the month of concern. The 1st and 13th months are given a weight of 0.5. A monthly mean is simply the sum of the daily ISN values for a calendar month, divided by the number of days in that month. We would commonly call this value a monthly average.

This may all sound very complicated, but an example should clarify the procedure. Suppose we wished to calculate the smoothed sunspot number for June 1986. We would require monthly mean values for six months prior and six months after this month, or from December 1985 through December 1986. The monthly mean ISN values for these months are

Dec	85	17.3
Jan	86	2.5
Feb	86	23.2
Mar	86	15.1
Apr	86	18.5
May	86	13.7
Jun	86	1.1
Jul	86	18.1
Aug	86	7.4
Sep	86	3.8
Oct	86	35.4
Nov	86	15.2
Dec	86	6.8

First we find the sum of the values, but using only one-half the amounts indicated for the first and 13th months in the listing. This value is 166.05. Then we determine the smoothed value by dividing the sum by 12: 166.05/12 = 13.8. (Values beyond the first decimal place are not warranted.) Thus, 13.8 is the smoothed sunspot number for June 1986. From this example, you can see that the smoothed sunspot number for a particular month cannot be determined until six months afterwards.

Generally the plots we see of sunspot numbers are averaged data. As already mentioned, smoothed numbers make it easier to observe trends and see patterns, but sometimes this data can be misleading. The plots tend to imply that solar activity varies smoothly, indicating, for example, that at the onset of a new cycle the activity just gradually increases. But this is definitely not so! On any one day, significant changes in solar activity can take place within hours, causing sudden band openings at frequencies well above the MUF values predicted from smoothed sunspot number curves. The durations of such openings may be brief, or they may recur for several days running, depending on the nature of the solar activity.

Solar Flux

Since the late 1940s an additional method of determining solar activity has been put to use—the measurement of *solar radio flux*. The quiet Sun emits radio energy across a broad frequency spectrum, with a slowly varying intensity. Solar flux is a measure of energy received per unit time, per unit area, per unit frequency interval. These radio fluxes, which originate from atmospheric layers high in the Sun's chromosphere and low in its corona, change gradually from day to day, in response to the activity causing sunspots. Thus, there is a degree of correlation between solar flux values and sunspot numbers.

One solar flux unit equals 10^{-22} joules per second per square meter per hertz. Solar flux values are measured daily at 2800 MHz (10.7 cm) at The Dominion Radio Astrophysical Observatory, Penticton, British Columbia, where daily data have been collected since 1991. (Prior to June 1991, the Algonquin Radio Observatory, Ontario, made the measurements.) Measurements are also made at other observatories around the world, at several frequencies. With some variation, the daily measured flux values increase with increasing frequency of measurement, to at least 15.4 GHz. The daily 2800 MHz Penticton value is sent to Boulder, Colorado, where it is incorporated into WWV propagation bulletins (see later section). Daily solar flux information can be of some value in determining current propagation conditions, as sunspot numbers on a given day do not relate directly to maximum usable frequency. Solar flux values are much more reliable for this purpose, when it is averaged over time, as will be discussed later in the section on computer-prediction programs.

Correlating Sunspot Numbers and Solar Flux Values

Based on historical data, an exact mathematical relationship does not exist to correlate sunspot data and solar flux values. Comparing daily values yields almost no correlation. Comparing monthly mean values (often called monthly averages) produces a degree of correlation, but the spread in data is still significant. This is indicated in **Fig 16**, a scatter diagram plot of monthly mean sunspot numbers versus the monthly means of solar flux values adjusted to one astronomical unit. (This adjustment applies a correction for differences in distance between the Sun and the Earth at different times of the year.)

A closer correlation exists when smoothed (12-month running average) sunspot numbers are compared with smoothed (12-month running average) solar flux values adjusted to one astronomical unit. A scatter diagram for smoothed data appears in **Fig 17**. Note how the plot points establish a better defined pattern in Fig 17. The correlation is still no better than a few percent, for records indicate a given smoothed sunspot number does not always correspond with the same smoothed solar flux value, and vice versa.



Fig 16—Scatter diagram or X-Y plot of monthly mean sunspot numbers and monthly mean 2800MHz solar flux values. Data values are from February 1947 through February 1987. Each "+" mark represents the intersection of data for a given month. If the correlation between sunspot number and flux values were consistent, all the marks would align to form a smooth curve.

Table 1 illustrates some of the inconsistencies that exist in the historical data. Smoothed or 12-month running average values are shown.

Even though there is no precise mathematical relationship between sunspot numbers and solar flux values, it is helpful to have some way to convert from one to the other. The primary reason is that sunspot numbers are valuable as a long-term link with the past, but the great usefulness of solar flux values are their immediacy, and their direct bearing on our field of interest. (Remember, a smoothed sunspot number will not be calculated until six months after the fact.)

The following mathematical approximation has been derived to convert a smoothed sunspot number to a solar flux value.



Fig 17—Scatter diagram of smoothed, or 12-month running averages, sunspot numbers versus 2800MHz solar flux values. The correlation of smoothed values is better than for monthly means, shown in Fig 16.

Table 1

Selected Historical Data Showing Inconsistent Correlation Between Sunspot Number and Solar Flux

Month	*Smoothed Sunspot Number*	*Smoothed Solar Flux Value*
May 1953	17.4	75.6
Sept 1965	17.4	78.5
Jul 1985	17.4	74.7
Jun 1969	106.1	151.4
Jul 1969	105.9	151.4
Dec 1982	94.6	151.4
Aug 1948	141.1	180.5
Oct 1959	141.1	192.3
Apr 1979	141.1	180.4
Aug 1981	141.1	203.3

$$F = 63.75 + 0.728\,S + 0.00089\,S^2 \qquad \text{(Eq 5)}$$

where

F = solar flux number

S = smoothed sunspot number

A graphic representation of this equation is given in **Fig 18**. Use this chart to make conversions graphically, rather than by calculations. With the graph, solar flux and sunspot number conversions can be made either way. The equation has been found to yield errors as great as 10% when historical data was examined. (Look at the August 1981 data in Table 1.) Therefore, conversions should be rounded to the nearest whole number, as additional decimal places are unwarranted. To make conversions from flux to sunspot number, the following approximation may be used.

$$S = 33.52\sqrt{85.12 + F} - 408.99 \qquad \text{(Eq 6)}$$

THE IONOSPHERE

There will be inevitable "gray areas" in our discussion of the Earth's atmosphere and the changes wrought in it by the Sun and by associated changes in the Earth's magnetic field. This is not a story that can be told in neat equations, or values carried out to a satisfying number of decimal places. The story must be told, and understood—with its well-known limitations—if we are to put up good antennas and make them serve us well.

Thus far in this chapter we have been concerned with what might be called our "above-ground living space"—that portion of the total atmosphere wherein we can survive without artificial breathing aids, or up to about 6 km (4 miles). The boundary area is a broad one, but life (and radio propagation) undergo basic changes beyond this zone. Somewhat farther out, but still technically within the Earth's atmosphere, the role of the Sun in the wave-propagation picture is a dominant one.



Fig 18—Chart for conversions between smoothed International Sunspot Numbers and smoothed 2800MHz solar flux. This curve is based on the mathematical approximation given in the text.

This is the *ionosphere*—a region where the air pressure is so low that free electrons and ions can move about for some time without getting close enough to recombine into neutral atoms. A radio wave entering this rarefied atmosphere, a region of relatively many free electrons, is affected in the same way as in entering a medium of different dielectric constant—its direction of travel is altered.

Ultraviolet (UV) radiation from the Sun is the primary cause of ionization in the outer regions of the atmosphere, the ones most important for HF propagation. However, there are other forms of solar radiation as well, including both hard and soft x-rays, gamma rays and extreme ultraviolet (EUV). The radiated energy breaks up, or *photoionizes*, atoms and molecules of atmospheric gases into electrons and positively charged ions. The degree of ionization does not increase uniformly with distance from the Earth's surface. Instead there are relatively dense regions (layers) of ionization, each quite thick and more or less parallel to the Earth's surface, at fairly well-defined intervals outward from about 40 to 300 km (25 to 200 miles). These distinct layers are formed due to complex photochemical reactions of the various types of solar radiation with oxygen, ozone, nitrogen and nitrous oxide in the rarefied upper atmosphere.

Ionization is not constant within each layer, but tapers off gradually on either side of the maximum at the center of the layer. The total ionizing energy from the Sun reaching a given point, at a given time, is never constant, so the height and intensity of the ionization in the various regions will also vary. Thus, the practical effect on long-distance communication is an almost continuous variation in signal level, related to the time of day, the season of the year, the distance between the Earth and the Sun, and both short-term and long-term variations in solar activity. It would seem from all this that only the very wise or the very foolish would attempt to predict radio propagation conditions, but it is now possible to do so with a fair chance of success. It is possible to plan antenna designs, particularly the choosing of antenna heights, to exploit known propagation characteristics.

Ionospheric Layer Characteristics

The lowest known ionized region, called the *D layer* (or the *D region*), lies between 60 and 92 km (37 to 57 miles) above the Earth. In this relatively low and dense part of the atmosphere, atoms broken up into ions by sunlight recombine quickly, so the ionization level is directly related to sunlight. It begins at sunrise, peaks at local noon and disappears at sundown. When electrons in this dense medium are set in motion by a passing wave, collisions between particles are so frequent that a major portion of their energy may be used up as heat, as the electrons and disassociated ions recombine.

The probability of collisions depends on the distance an electron travels under the influence of the wave—in other words, on the wavelength. Thus, our 1.8- and 3.5-MHz bands, having the longest wavelengths, suffer the highest daytime absorption loss as they travel through the D layer, particularly for waves that enter the medium at the lowest angles. At times of high solar activity (peak years of the solar cycle) even waves entering the D layer vertically suffer almost total energy absorption around midday, making these bands almost useless for communication over appreciable distances during the hours of high sun. They "go dead" quickly in the morning, but come alive again the same way in late afternoon. The diurnal (daytime) D-layer effect is less at 7 MHz (though still marked), slight at 14 MHz and inconsequential on higher amateur frequencies.

The D region is ineffective in bending HF waves back to Earth, so its role in long-distance communication by amateurs is largely a negative one. It is the principal reason why our frequencies up through the 7-MHz band are useful mainly for short-distance communication during the high-sun hours.

The lowest portion of the ionosphere useful for long-distance communication by amateurs is the *E layer* (also known as the *E region*) about 100 to 115 km (62 to 71 miles) above the Earth. In the E layer, at intermediate atmospheric density, ionization varies with the Sun angle above the horizon, but solar ultraviolet radiation is not the sole ionizing agent. Solar X-rays and meteors entering this portion of the Earth's atmosphere also play a part. Ionization increases rapidly after sunrise, reaches maximum around noon local time, and drops off quickly after sundown. The minimum is after midnight, local time. As with the D layer, the E layer absorbs wave energy in the lower-frequency amateur bands when the Sun angle is high, around mid-day. The other varied effects of E-region ionization will be discussed later.

Most of our long-distance communication capability stems from the tenuous outer reaches of the Earth's atmosphere known as the *F layer*. At heights above 100 miles, ions and electrons recombine more slowly, so the observable effects of the Sun develop more slowly. Also, the region holds its ability to reflect wave energy back to Earth well into the night. The *maximum usable frequency* (MUF) for F-layer propagation on east-west paths thus peaks just after noon at the midpoint, and the minimum occurs after midnight. We'll examine the subject of MUF in more detail later.

Judging what the F layer is doing is by no means that simple, however. The layer height may be from 160 to more than 500 km (100 to over 310 miles), depending on the season of the year, the latitudes, the time of day and, most capricious of all, what the Sun has been doing in the last few minutes and in perhaps the last three days before the attempt is made. The MUF between Eastern US and Europe, for example, has been anything from 7 to 70 MHz, depending on the conditions mentioned above, plus the point in the long-term solar-activity cycle at which the check is made.

During a summer day the F layer may split into two layers. The lower and weaker *F_1 layer*, about 160 km (100 miles) up, has only a minor role, acting more like the E than the *F_2 layer*. At night the F_1 region disappears and the F_2 region height drops somewhat.

Propagation information tailored to amateur needs is transmitted in all information bulletin periods by the ARRL Headquarters station, W1AW. Finally, solar and geomagnetic field data, transmitted hourly and updated eight times daily, are given in brief bulletins carried by the US Time Standard stations, WWV and WWVH, and also on Internet Web sites. But more on these services later.

Bending in the Ionosphere

The degree of bending of a wave path in an ionized layer depends on the density of the ionization and the length of the wave (inversely related to its frequency). The bending at any given frequency or wavelength will increase with increased ionization density and will bend away from the region of most-intense ionization. For a given ionization density, bending increases with wavelength (that is, it decreases with frequency).

Two extremes are thus possible. If the intensity of the ionization is sufficient and the frequency is low enough, even a wave entering the layer perpendicularly will be reflected back to Earth. Conversely, if the frequency is high enough or the ionization decreases to a low-enough density, a condition is reached where the wave angle is not affected enough by the ionosphere to cause a useful portion of the wave energy to return to the Earth. The frequency at which this occurs is called the vertical-incidence *critical frequency.* Each region in the ionosphere has a critical frequency associated with it, and this critical frequency will change depending on the date, time and state of the 11-year solar cycle.

Fig 19 shows a simplified graph of the electron density (in electrons per cubic meter) versus height in the ionosphere (in km) for a particular set of daytime and nighttime conditions. Free electrons are what return the signals you launch into the ionosphere back down to the Earth at some distance from your transmitter—The more free electrons in the ionosphere, the better propagation will be, particularly at higher frequencies.

Electron-density profiles are extremely complicated and vary greatly from one location to the next, depending on a bewildering variety of factors. Of course, this sheer variability makes it all the more interesting and challenging for hams to work each other on ionospheric HF paths!

The following discussion about sounding the ionosphere provides some background information about the scientific instruments used to decipher the highly intricate mechanisms behind ionospheric HF propagation.

SOUNDING THE IONOSPHERE

For many years scientists have *sounded* the ionosphere to determine its communication potential at various elevation angles and frequencies. The word "sound" stems from



Fig 19—Typical electron densities for nighttime and daytime conditions in the various ionospheric regions.



Fig 20—Very simplified ionogram from a vertical-incidence sounder. The lowest trace is for the E region; the middle for the F_1 and the upper trace for the F_2 region.

an old idea—one that has nothing to do with the audio waves that we can hear as "sounds." Long ago, sailors sounded the depths beneath their boats by dropping weighted ropes, calibrated in fathoms, into the water. In a similar fashion, the instrument used to probe the height of the ionosphere is called an *ionosonde*, or ionospheric sounder. It measures distances to various layers by launching a calibrated electronic signal directly up into the ionosphere.

Radar uses the same techniques as ionospheric sounding to detect targets such as airplanes. An ionosonde sends precisely timed pulses into the ionosphere over a range of MF and HF frequencies. The time of reception of an echo reflected from a region in the ionosphere is compared to the time of transmission. The time difference is multiplied by the speed of light to give the apparent distance that the wave has traveled from the transmitter to the ionosphere and back to the receiver. (It is an *apparent* or *virtual distance* because the speed of a wave slows very slightly in the ionosphere, just as the speed of propagation through any medium other than a vacuum slows down because of that medium.)

Another type of ionosonde sweeps the frequency of transmission, from low to high. This is called an "FM-CW," or more colorfully, a "chirp" sounder. Since a received echo takes time to travel from the transmitter up to the reflection point and then back again to the receiver, the echo will be at a lower frequency than the still-moving frequency of the transmitter. The frequency difference is an indication of the height of the echo's reflection off the various ionospheric layers.

Vertical-Incidence Sounders

Most ionosondes are *vertical-incidence sounders*, bouncing their signals perpendicularly off the various ionized regions above it by launching signals straight up into the ionosphere. The ionosonde frequency is swept upwards until echos from the various ionospheric layers disappear, meaning that the critical frequencies for those layers have been exceeded, causing the waves to disappear into space.

Fig 20 shows a highly simplified ionogram for a typical vertical-incidence sounder. The echos at the lowest height at the left-hand side of the plot show that the E region is about 100 km high. The F_1 region shown in the middle of the plot varies from about 200 to 330 km in this example, and the F_2 region ranges from just under 400 km to almost 600 km in height. You can see that the F_1 and F_2 ionospheric regions take a "U" shape, indicating that the electron density varies throughout the layer. In this example, the peak in electron density is at a virtual height of the F_2 region of about 390 km, the lowest point in the F_2 curve.

Scientists can derive a lot of information from a vertical-incidence ionogram, including the critical frequencies for each region, where raising the frequency any higher causes the signals to disappear into space. In Fig 20, the E-region critical frequency (abbreviated f_oE) is about 4.1 MHz. The F_1-region critical frequency (abbreviated f_oF_1) is 4.8 MHz. The F2-region critical frequency (abbreviated f_oF_2) is this simplified diagram is 6.8 MHz.

The observant reader may well be wondering what the subscripted "o" in the abbreviations f_oE, f_oF_1 and f_oF_2 mean. The abbreviation "o" means "ordinary." When an electromagnetic wave is launched into the ionosphere, the Earth's magnetic field splits the wave into two independent waves—the "ordinary" (o) and the "extraordinary" (x) components. The ordinary wave reaches the same height in the ionosphere whether the Earth's magnetic field is present or not, and hence is called "ordinary." The extraordinary wave, however, is greatly affected by the presence of the Earth's magnetic field, in a very complex fashion.

Fig 21 shows an example of an actual ionogram from the vertical Lowell Digisonde at Millstone Hill in Massa-



Fig 21—Actual vertical-incidence ionogram from the Lowell Digisonde, owned and operated at Millstone Hill in Massachusetts by MIT. The ordinary (o) and extraordinary (x) traces are shown for heights greater than about 300 km. At the upper left are listed the computer-determined ionospheric parameters, such as f_oF_2 of 9.24 MHz and f_oF_1 at 4.66 MHz.



Fig 22—Computer simulation of the f_oF_2 contours for 25 November 1998, for an SSN of 85 and a quiet planetary A_p index of 5. Note the two regions of high f_oF_2 values off the upper and lower west coast of Africa. These are the "equatorial anomalies," regions of high electronic density in the F_2 region that often allow chordal-hop north-south propagation. See also Fig 8. (*PropLab Pro simulation, courtesy of Solar Terrestrial Dispatch.*)

chusetts, owned and operated by the Massachusetts Institute of Technology. This ionogram was made on June 18, 2000, and shows the conditions during a period of very high solar activity. The black-and-white rendition in Fig 21 of the actual color ionogram unfortunately loses some information. However, you can still see that a real ionogram is a lot more complicated looking than the simple simulated one in Fig 20.

The effects of noise and interference from other stations are shown by the many speckled dots appearing in the ionogram. The critical frequencies for various ionospheric layers are listed numerically at the left-hand side of the plot and the signal amplitudes are color-coded by the color bars at the right-hand side of the plot. The x-axis is the frequency, ranging from 1 to 11 MHz.

Compared to the simplified ionogram in Fig 20, Fig 21 shows another trace that appears on the plot from about 5.3 to 9.8 MHz, a trace shifted to the right of the darker ordinary trace. This second trace is the extraordinary (x) wave mentioned above. Since the x and o waves are created by the Earth's magnetic field, the difference in the ordinary and extraordinary traces is about 1/2 the *gyro frequency*, the frequency at which an electron will spiral down a particular magnetic field line. The electron gyro frequency is different at various places around the Earth, being related to the Earth's complicated and changing magnetic field. The extraordinary trace always has a higher critical frequency than the ordinary trace on a vertical-incidence ionogram, and it is considerably weaker than the ordinary trace, especially at frequencies below about 4 MHz because of heavy absorption.

The Big Picture Overhead

There are about 150 vertical-incidence ionosondes around the world. Ionosondes are located on land, even on a number of islands. There are gaps in sounder coverage, however, mainly over large expanses of open ocean. The compilation of all available vertical-incidence data from the worldwide network of ionospheric sounders results in global f_oF_2 maps, such as the map shown in **Fig 22**, a simulation from the highly sophisticated *PropLab Pro* computer program.

This simulation is for 1300 UTC, several hours after East Coast sunrise on Nov 25, 1998, with a high level of solar activity of 85 and a planetary A_p index of 5, indicating calm geomagnetic conditions. The contours of f_oF_2 peak over the ocean off the west coast of Africa at 38 MHz. Over the southern part of Africa, f_oF_2 peaks at 33 MHz.

These two "humps" in f_oF_2 form what is known as the "equatorial anomaly" and are caused by upwelling "fountains" of high electron concentration located in daylight areas about ±20° from the Earth's magnetic dip equator. The equatorial anomaly is important in transequatorial propagation. Those LU stations in Argentina that you can hear on 28 MHz from the US in the late afternoon, even during low portions of the solar cycle when other stations to the south are not coming through, are benefiting from transequatorial propagation, sometimes called "chordal hop" propagation, because signals going through this area remain in the ionosphere without lossy intermediate hops to the ground.

From records of f_oF_2 profiles, the underlying electron densities along a path can be computed. And from the electron density profiles computerized "ray tracing" may be done throughout the ionosphere to determine how a wave propagates from a transmitter to a particular receiver location. *PropLab Pro* can do complex ray tracings that explicitly include the effect of the Earth's magnetic field, even taking into effect ionospheric stormy conditions.

Oblique-Angle Ionospheric Sounding

A more elaborate form of ionospheric sounder is the *oblique ionosonde*. Unlike a vertical-incidence ionospheric sounder, which sends its signals directly overhead, an oblique sounder transmits its pulses obliquely through the ionosphere, recording echos at a receiver located some distance from the transmitter. The transmitter and distant receiver are precisely coordinated in GPS-derived time in modern oblique sounders.

Interpretation of ionograms produced by oblique sounders is considerably more difficult than for vertically incident ones. An oblique ionosonde purposely transmits over a continuous range of elevation angles simultaneously and hence cannot give explicit information about each elevation angle it launches. **Fig 23** shows a typical HF oblique-sounder ionogram for the path from Hawaii to California in March of 1973, during a period of medium-level sunspot activity. The y-axis is calibrated in time delay, in milliseconds. Longer distances involve longer time delays between the start of a transmitted pulse and the reception of the echo. The x-axis in this ionogram is the frequency, just like a vertical-incidence ionogram. Note that the frequency range for this plot extends to 32 MHz, while vertical-incidence ionograms usually don't sweep higher than about 12 MHz.

Six possible modes are shown in this ionogram: $1F_2$, $2F_2$, $3F_2$, $4F_2$ and $5F_2$. These involve multiple modes of propagation (commonly called *hops*) between the ionosphere and reflections from the Earth. For example, at an operating frequency of 14 MHz, there are three modes open during the mid-morning: $2F_2$, $3F_2$ and $4F_2$. We'll discuss multiple hops later in more detail.



Fig 23—HF oblique-sounder ionogram. This is a typical chirpsounder measurement on a 2500-mile path from Hawaii to southern California during midmorning in March at a medium level of solar activity. Six possible modes (hops) are shown. The "FOT" is the frequency of optimum traffic, considered most reliable for this path/time.

The lowest mode, $1F_2$ in Fig 23, employs a single F_2 hop to cover the 3900-km long path from Hawaii to California, but it is only open on 28-MHz. (Note that 3900 km is close to the maximum possible single-hop length for the F_2 region. We'll look at this in more detail later too.) In general, each mode that involves more than a single hop is weaker than a single hop. For example, you can see that the received $5F_2$ echo is weak and broken up because of the accumulation of losses at each ground-level reflection in its five hops, with absorption in the ionosphere all along its complicated path to the receiver.

The trace labeled "FOT" is the *frequency of optimum traffic*, considered the most reliable frequency for communications on this particular circuit and date/time. In this example, the FOT would be near the 21-MHz amateur band.

Another interesting point in Fig 23 is labeled "High Angle Ray." This refers to the Pedersen ray. Before we go into more details about the Pedersen high-angle wave, we need to examine how launch angles affect the way waves are propagated through the ionosphere.

Fig 24 shows a highly simplified situation, with a single ionospheric layer and a smooth Earth. This illustrates several important facts about antenna design for long-distance communication. In Fig 24, Wave #1 is launched at the lowest elevation angle (that is, most nearly horizontal to the horizon). Wave #1 manages to travel from the transmitter to the receiving location at point C in a single hop.

Wave #2 is launched at a higher elevation angle than Wave #1, and penetrates further into the ionospheric layer before it is refracted enough to return to Earth. The ground distance covered from the transmitter to point B is less for



Fig 24—Very simplified smooth-Earth/ionosphere diagram showing how the ground range from transmitter to receiver can vary as the elevation angle is gradually raised. The Pedersen wave, launched at a relatively high angle, has the same ground range as the low-angle wave #1, but is weaker because it travels for a long distance in the ionosphere.

Wave #2 than for lower-angle Wave #1. Wave #3 is launched at a still-higher elevation angle. Like Wave #2 before it, Wave #3 penetrates further into the ionosphere and covers less ground downrange than #2.

Now, we see something very interesting happening for Wave #4, whose launch elevation angle is still higher than #3. Wave #4 penetrates even higher into the ionosphere than #3, reaching the highest level of ionization in our theoretical ionospheric layer, where it is finally refracted sufficiently to bend down to Earth. Wave #4 manages to arrive at the same point B as Wave #2, which was launched at a much lower elevation angle.

In other words, in the sequence from #1 to #3 we have been continually *increasing* the elevation launch angle and the ground range covered from the transmitter to the return of the signal back to Earth has been continually *decreasing*. However, starting with Wave #4, the ground range starts to *increase* with increased elevation angle. A further increase in the elevation angle causes Wave #5 to travel for an even longer distance through the ionosphere, exiting finally at point C, the same ground distance as lowest-angle Wave #1.

Finally, increasing the elevation angle even further results in Wave #6 being lost to outer space because the ionization in the layer is insufficient to bend the wave back to Earth. In other words, Wave #6 has exceeded the *critical angle* for this hypothetical ionospheric layer and this frequency of operation.

Both Waves #4 and #5 in Fig 24 are called “high-angle” or Pedersen waves. Because Wave #5 has traveled a greater distance through the ionosphere, it is always weaker than Wave #1, the one launched at the lowest elevation angle. Pedersen waves are usually not very stable, since small changes in elevation angle can result in large changes in the ground range that these high-angle waves cover.

SKIP DISTANCE

Fig 24 shows that we can communicate with the point on the Earth labeled “A” (where Wave #3 arrives), but not any closer to our transmitter site. When the critical angle is less than 90° (that is, directly overhead) there will always be a region around the transmitting site where an ionospherically propagated signal cannot be heard, or is heard weakly. This area lies between the outer limit of the ground-wave range and the inner edge of energy return from the ionosphere. It is called the *skip zone*, and the distance between the originating site and the beginning of the ionospheric return is called the skip distance. This terminology should not to be confused with ham jargon such as “the skip is in,” referring to the fact that a band is open for sky-wave propagation.

The signal may often be heard to some extent within the skip zone, through various forms of scattering (discussed in detail later), but it will ordinarily be marginal in strength. When the skip distance is short, both ground-wave and sky-wave signals may be received near the transmitter. In such instances the sky wave frequently is stronger than the ground wave, even as close as a few miles from the transmitter. The ionosphere is an efficient communication medium under favorable conditions. Comparatively, the ground wave is not.

If the radio wave leaves the Earth at a radiation angle of zero degrees, just at the horizon, the maximum distance that may be reached under usual ionospheric conditions in the F_2 region is about 4000 km (2500 miles).

MULTI-HOP PROPAGATION

As mentioned previously in the discussion about Fig 24, the Earth itself can act as a reflector for radio waves, resulting a multiple hops. Thus, a radio signal can be reflected from the reception point on the Earth back into the ionosphere, reaching the Earth a second time at a still more-distant point. This effect is illustrated in **Fig 25**, where a single ionospheric layer is depicted, although this time we show both the layer and the Earth beneath it as curved rather than flat. The wave identified as “Critical Angle” travels from the transmitter via the ionosphere to point A, in the center of the drawing, where it is reflected upwards and travels through the ionosphere to point B, at the right. This shows a two-hop signal.

As in the simplified case in Fig 24, the distance at which a ray eventually reaches the Earth depends on the launch elevation angle at which it left the transmitting antenna. You have some control of the launch angle by adjusting the height of the antennas you use, as described in Chapter 3, The Effects of Ground.

The information in Fig 25 is greatly simplified. On actual communication paths the picture is complicated by many factors. One is that the transmitted energy spreads over a considerable area after it leaves the antenna. Even with an antenna array having the sharpest practical beam pattern, there is what might be described as a *cone of radiation* centered on the wave lines (rays) shown in the drawing. The reflection/refraction in the ionosphere is also highly variable, and is the cause of considerable spreading and scattering.



Fig 25—Behavior of waves encountering a simple curved ionospheric layer over a curved Earth. Rays entering the ionized region at angles above the critical angle are not bent enough to be returned to Earth, and are lost to space. Waves entering at angles below the critical angle reach the Earth at increasingly greater distances as the launch angle approaches the horizontal. The maximum distance that may normally be covered in a single hop is 4000 km. Greater distances are covered with multiple hops.

Under some conditions it is possible for as many as four or five signal hops to occur over a radio path, as illustrated by the oblique ionogram in Fig 23. But no more than two or three hops is the norm. In this way, HF communication can be conducted over thousands of miles.

An important point should be recognized with regard to signal hopping. A significant loss of signal occurs with each hop. The D and E layers of the ionosphere absorb energy from signals as they pass through, and the ionosphere tends to scatter the radio energy in various directions, rather than confining it in a tight bundle. The roughness of the Earth's surface also scatters the energy at a reflection point.

Assuming that both waves do reach point B in Fig 25, the low-angle wave will contain more energy at point B. This wave passes through the lower layers just twice, compared to the higher-angle route, which must pass through these layers four times, plus encountering an Earth reflection. Measurements indicate that although there can be great variation in the relative strengths of the two signals—the one-hop signal will generally be from 7 to 10 dB stronger. The nature of the terrain at the mid-path reflection point for the two-hop wave, the angle at which the wave is reflected from the Earth, and the condition of the ionosphere in the vicinity of all the refraction points are the primary factors in determining the signal-strength ratio.

The loss per hop becomes significant at greater distances. It is because of these losses that no more than four or five propagation hops are useful; the received signal becomes too weak to be usable over more hops. Although modes other than signal hopping also account for the propagation of radio waves over thousands of miles, backscatter studies of actual radio propagation have displayed signals with as many as five hops. So the hopping mode is arguably the most prevalent method for long-distance communication.



Fig 26—Modified *VOAAREA* plot for 21.2 MHz from San Francisco to the rest of the US, annotated with signal levels in S units, as well as signal contours in dBW (dB below a watt). Antennas are assumed to be 3-element Yagis at 55 feet above flat ground; the transmitter power is 1500 W; the month is November with SSN = 50, a moderate level of solar activity, at 22 UTC. The most obvious feature is the large "skip zone" centered on the transmitter in San Francisco, extending almost a $^1/_3$ of the distance across the US.

Fig 26 shows another way of looking at propagation—a *geographic area* look. Fig 26 shows 15-meter signal levels across the US as they propagate from a transmitting station in San Francisco. This simulation of propagation conditions is for the month of November, with a medium level of solar activity (SSN = 50) at 22 UTC. Fig 26 was created using the *VOAAREA* software program, part of the *VOACAP* software suite. Transmitter power is assumed to be 1500 W, with 3-element Yagis, 55 feet high, at the transmitter and at each receiving location.

From the transmitter out to about 50 miles, signals are moderate, at about S5 on an S meter. Beyond that coverage area to almost $^1/_3$ of the way across the country (to Colorado), there is a large and distinctive skip zone, where only very weak signals return to Earth (S1 or less). Beyond Colorado, signals rapidly build up to S9+10 dB across the middle of the US, falling to S9 and then to S7 in the vicinity of Chicago, Illinois. Beyond Chicago, the signals drop to S5 in a swath from Michigan and part of Ohio down to Alabama. All along the US East Coast, signals come back strong at S9.

The reason why the signals in Fig 26 drop down to S5 in the Midwest is that the necessary elevation angles to cover this region in a single F2 hop are extremely low even at a moderate level of solar activity. To achieve launch angles as low as 1° requires either very high antenna heights or a high mountaintop location. Beyond the Midwest, out to the US East Coast, two F2 hops are required, with higher elevation angles and hence greater antenna gain for moderate antenna heights.

Non-Hopping Propagation Modes

Present propagation theory holds that for communication distances of many thousands of kilometers, signals do not always hop in relatively short increments from ionosphere-to-Earth-to-ionosphere and so forth along the entire path. Instead, the wave is thought to propagate *inside* the ionosphere throughout some portion of the path length, tending to be *ducted* in the ionized layer.

As was shown in Fig 24, the high-angle Pedersen ray can also penetrate an ionospheric layer farther than lower-angle rays. In the less-densely ionized upper edge of the layer, the amount of refraction is less, nearly equaling the curvature of the layer itself as it encircles the Earth.

Non-hopping theory of long-distance propagation is further supported by studies of travel times for signals that go completely around the world. The time required is significantly less than would be necessary to hop between the Earth and the ionosphere 10 or more times while circling the Earth.

Propagation between two points thousands of kilometers apart may in fact consist of a combination of ducting and hopping. It may involve combinations of refractions from the E layer and the F layer. Despite all the complex factors involved, most long-distance propagation can be seen to follow certain general rules. Thus, much commercial and military point-to-point communication over long distances employs antennas designed to make maximum use of known radiation angles and layer heights, even on paths where multihop propagation is assumed.

In amateur work, however, we usually try for the lowest practical radiation angle, hoping to keep reflection losses to a minimum. Years of amateur experience have shown this to be a decided advantage under all usual conditions.

The geometry of propagation by means of the F_2 layer limits our maximum distance along the Earth's surface to about 4000 km (2500 miles) for a single hop. For higher radiation angles, this same distance may require two or more hops (with higher reflection loss). And fewer hops are better, in most cases. If you have a nearby neighbor who consistently outperforms you on the longer paths, a radiation angle difference in his favor is probably the reason.

MAXIMUM USABLE FREQUENCY

The vertical-incidence critical frequency is the *maximum usable frequency* for local sky-wave high-angle communication. It is also useful in the selection of optimum working frequencies and the determination of the maximum usable frequency for distant points at a given time. The abbreviation "MUF" for maximum usable frequency will be used hereafter.

In geographic middle latitudes, the vertical-incident critical frequency ranges between about 1 and 4 MHz for the E layer, and between 2 and 13 MHz for the F_2 layer. The lowest figures are for nighttime conditions in the lowest years of the solar cycle. The highest are for the daytime hours in the years of high solar activity. These are average figures. Critical frequencies have reached as high as 20 MHz briefly during exceptionally high solar activity in the middle latitudes. As was pointed out earlier in Fig 22, $f_o F_2$ levels approaching 40 MHz are possible at low latitudes.

While vertical-incidence critical frequencies are interesting from a scientific point of view, hams are far more concerned about how we can exploit propagation conditions to communicate, preferably at long distances. The MUF for a 4000-km (2500 miles) distance is about 3.5 times the vertical-incidence critical $f_o F_2$ frequency existing at the path midpoint. For one-hop signals, if a uniform ionosphere is assumed, the MUF decreases with shorter distances along the path. This is true because the higher-frequency waves must be launched at higher elevation angles for shorter ranges, and at these launch angles they are not bent sufficiently to reach the Earth. Thus, a lower frequency (where more bending occurs) must be used.

Precisely speaking, a maximum usable frequency or MUF is defined for communication between two specific points on the Earth's surface, for the conditions existing at the time, including the minimum elevation angle that the station can launch at the frequency in use. (This practical form of MUF is sometimes called the *operational MUF*). At the same time and for the same conditions, the MUF from either of these two points to a third point may be different.

Table 2

Time and Frequency Stations Useful for Propagation Monitoring

Call	*Frequency (MHz)*	*Location*
WWV	2.5, 5, 10, 15, 20	Ft Collins, Colorado
WWVH	Same as WWV but no 20	Kekaha, Kauai, Hawaii
CHU	3.330, 7.335, 14.670	Ottawa, Ontario, Canada
RID	5.004, 10.004, 15.004	Irkutsk, USSR*
RWM	4.996, 9.996, 14.996	Novosibirsk, USSR
VNG	2.5, 5, 8.634, 12.984, 16	Lyndhurst, Australia
BPM	5, 5.43, 9.351, 10, 15	Xiang, China
BSF	15	Taoyuan, Taiwan
JJY	2.5, 5, 8, 10, 15	Tokyo, Japan
LOL	5, 10, 15	Buenos Aires, Argentina

*The call, taken from an international table, may not be the one used during actual transmission. Locations and frequencies appear to be accurate as provided.

Therefore, the MUF cannot be expressed broadly as a single frequency, even for any given location at a particular time. The ionosphere is never uniform, and in fact at a given time and for a fixed distance, the MUF changes significantly with changes in compass direction for almost any point on the Earth. Under usual conditions, the MUF will always be highest in the direction toward the Sun—to the east in the morning, to the south at noon (from northern latitudes), and to the west in the afternoon and evening.

For the strongest signals at the greatest distance, especially where the limited power levels of the Amateur Radio Service are concerned, it is important to work fairly near the MUF. It is at these frequencies where signals suffer the least loss. The MUFs can be estimated with sufficient accuracy by using the prediction charts that appear on the ARRL Web site (**www.arrl.org/qst/propcharts/**) or by using a computer prediction program. The CD-ROM bundled in the back of this book contains detailed and summary tables for more than 175 transmitting locations around the world. (See section on "What HF Bands Are Open—Where and When?" later in this chapter.)

MUFs can also be observed, with the use of a continuous coverage communications receiver. Frequencies up to the MUFs are in round-the-clock use today. When you "run out of signals" while tuning upward in frequency from your favorite ham band, you have a pretty good clue as to which band is going to work well, right then. Of course, it helps to know the direction to the transmitters whose signals you are hearing. Shortwave broadcasters know what frequencies to use, and you can hear them anywhere, if conditions are good. Time-and-frequency stations are also excellent indicators, since they operate around the clock. See **Table 2**. WWV is also a reliable source of propagation data, hourly, as discussed in more detail later in this chapter.

The value of working near the MUF is two-fold. Under undisturbed conditions, the absorption loss decreases proportional to the square of a change in frequency. For example, the absorption loss is four times higher at 14 MHz than it is at 28 MHz. Perhaps more important, the hop distance is considerably greater as the MUF is approached. A transcontinental contact is thus much more likely to be made on a single hop on 28 MHz than on 14 MHz, so the higher frequency will give the stronger signal most of the time. The strong-signal reputation of the 28-MHz band is founded on this fact.

LOWEST USABLE FREQUENCY

There is also a lower limit to the range of frequencies that provide useful communication between two given points by way of the ionosphere. *Lowest usable frequency* is abbreviated LUF. If it were possible to start near the MUF and work gradually lower in frequency, the signal would decrease in strength and eventually would disappear into the ever-present “background noise.” This happens because signal absorption increases proportional to the square of the lowering of the frequency. The frequency nearest the point where reception became unusable would be the LUF. It is not likely that you would want to work at the LUF, although reception could be improved if the station could increase power by a considerable amount, or if larger antennas could be used at both ends of the path.

For example, when solar activity is very high at the peak of a solar cycle, the LUF often rises higher than 14 MHz on the morning Eastern US-to-Europe path on 20 meters. Just before sunrise in the US, the 20-meter band will be first to open to Europe, followed shortly by 15 meters, and then 10 meters as the Sun rises further. By mid-morning, however, when 10 and 15 meters are both wide open, 20 meters will become very marginal to Europe, even when both sides are running maximum legal power levels. By contrast, stations on 10 meters can be worked readily with a transmitter power of only 1 or 2 watts, indicating the wide range between the LUF and the MUF.

Frequently, the *window* between the LUF and the MUF for two fixed points is very narrow, and there may be no amateur frequencies available inside the window. On occasion the LUF may be higher than the MUF between two points. This means that, for the highest possible frequency that will propagate through the ionosphere for that path, the absorption is so great as to make even that frequency unusable. Under these conditions it is impossible to establish amateur sky-wave communication between those two points, no matter what frequency is used. (It would normally be possible, however, to communicate between either point and other points on some frequency under the existing conditions.) Conditions when amateur sky-wave communication is impossible between two fixed points occur commonly for long distances where the total path is in darkness, and for very great distances in the daytime during periods of low solar activity.



Fig 27—Propagation prediction chart for East Coast of US to Europe. This appeared in December 1994 *QST*, where an average 2800-MHz (10.7-cm) solar flux of 83 was assumed for the mid-December to mid-January period. On 10% of these days, the highest frequency propagated was predicted at least as high as the uppermost curve (the Highest Possible Frequency, or HPF, approximately 21 MHz), and for 50% of the days as high as the middle curve, the MUF. The broken lines show the Lowest Usable Frequency (LUF) for a 1500-W CW transmitter.

Fig 27 shows a typical propagation prediction from the ARRLWeb members-only site (**www.arrl.org/qst/propcharts/**, previously from the “How’s DX” column in *QST*). In this instance, the MUF and the LUF lines are blurred together at about 10 UTC, meaning that the statistical likelihood of any amateur frequency being open for that particular path at that particular time was not very good. Later on, after about 11 UTC, the gap between the MUF and LUF increased, indicating that the higher bands would be open on that path.

DISTURBED IONOSPHERIC CONDITIONS

So far, we have discussed the Earth’s ionosphere when conditions at the Sun are undisturbed. There are three general types of major disturbances on the Sun that can affect radio propagation here on the Earth. On the air, you may hear people grousing about *Solar Flares*, *Coronal Holes* or *Sudden Disappearing Filaments*, especially when propagation conditions are not good. Each of these disturbances causes both electromagnetic radiation and ejection of material from the Sun.

Solar Flares

Solar flares are cataclysmic eruptions that suddenly release huge amounts of energy, including sustained, high-energy bursts of radiation from VLF to X-ray frequencies and vast amounts of solar material. Most solar flares occur around the peak of the 11-year solar cycle.

The first Earthly indication of a huge flare is often a visible brightness near a sunspot group, along with increases in UV, X-ray radiation and VHF radio noise. If the geometry between the Sun and Earth is right, intense X-ray radiation takes eight minutes, traveling the 93 million miles to Earth at the speed of light. The sudden increase in X-ray energy can immediately increase RF absorption in the Earth's lowest ionospheric layers, causing a phenomenon known as a *Sudden Ionospheric Disturbance* (SID).

An SID affects all HF communications on the sunlit side of the Earth. Signals in the 2 to 30-MHz range may disappear entirely, and even most background noise may cease in extreme cases. When you experience a big SID, your first inclination may be to look outside to see if your antenna fell down! SIDs may last up to an hour before ionospheric conditions temporarily return to normal.

Between 45 minutes and 2 hours after an SID begins, particles from the mass eruption on the Sun may begin to arrive. These high-energy particles are mainly protons and they can penetrate the ionosphere at the Earth's magnetic poles, where intense ionization can occur, with attendant absorption of HF signals propagating through the polar regions. This is called a *Polar Cap Absorption* (PCA) event and it may last for several days. A PCA results in spectacular auroral displays at high latitudes.

Coronal Holes

As described earlier in the section dealing with auroral propagation at VHF, a second major solar disturbance is a so-called "coronal hole" in the Sun's outer layer (the *corona*). Temperatures in the corona can be more than four million °C over an active sunspot region but more typically are about two million °C. A coronal hole is an area of somewhat lower temperature. Solar-terrestrial scientists have a number of competing theories about how coronal holes are formed.

Matter ejected through this "hole" takes the form of a *plasma*, a highly ionized gas made up of electrons, protons and neutral particles, traveling at speeds up to 1,000 km per second (2 million miles per hour). The plasma becomes part of the solar wind and can affect the Earth's magnetic field, but only if the Sun-Earth geometry is right. A plasma has a very interesting and somewhat bizarre ability. It can lock-in the orientation of the magnetic field where it originates and carry it outwards into space. However, unless the locked-in magnetic field orientation is aligned properly with the Earth's magnetic field, even a large plasma mass may not severely disrupt our magnetosphere, and thence our ionosphere.

Presently, we don't have the ability to predict very long in advance when the Sun might erupt in a disturbance that results in Earthly propagation problems. The SOHO satellite can help determine whether a mass ejection is heading towards Earth, and the ACE satellite about 1 million miles away from Earth can give about an hour's warning whether the imbedded magnetic field in a mass ejection from the Sun might impact the Earth's magnetosphere, causing propagation problems for hams.

Statistically, coronal holes tend to occur most often during the declining phase of the 11-year solar cycle and they can last for a number of solar rotations. This means that a coronal hole can be a "recurring coronal hole," disrupting communications for several days about the same time each month for as long as a year, or even more.

Sudden Disappearing Filaments

A sudden disappearing filament (SDF) is the third major category of solar disturbance that can affect propagation. SDFs take their names from the manner in which they suddenly arch upward from the Sun's surface, spewing huge amounts of matter as plasma out into space in the solar wind. They tend to occur mostly during the rising phase of the 11-year solar cycle.

IONOSPHERIC STORMS

When the conditions are right, a flare, coronal hole or an SDF can launch a plasma cloud into the solar wind, resulting in an *ionospheric storm* here on Earth. Unlike a hurricane or a winter Nor'easter storm in New England, an ionospheric storm is not something we can see with our eyes or feel on our skins. We can't easily measure things occurring in the ionosphere some 200 miles overhead. However, we can see the indirect effects of an ionospheric storm on magnetic instruments located on the Earth's surface, because disturbances in the ionosphere are closely related to the Earth's magnetic field. The term *Geomagnetic Storm* ("Geo" means "Earth" in Greek) is used almost synonymously with ionospheric storm.

During a ionospheric storm, we may experience extraordinary radio noise and interference, especially at HF. You may hear solar radio emissions as increases of noise at VHF. A geomagnetic storm generally adds noise and weakens or disrupts ionospheric propagation for several days. Transpolar signals at 14 MHz or higher may be particularly weak, with a peculiar hollow sound or flutter—even more than normal for transpolar signals.

Depending on the severity of the disturbance to the Earth's geomagnetic field and the consequent disturbance of the ionosphere, propagation may be disrupted completely or it might be at least degraded for a period of time that ranges from a day to three or four days before returning to normal propagation conditions.

What can we do about the solar disturbances and related disturbed ionospheric propagation on Earth? The truth is that we are powerless faced with the truly awesome forces of solar disturbances like flares, coronal holes or sudden disappearing filaments. Perhaps there is some comfort, however, in understanding what has happened to cause our HF bands to be so poor. And as a definite consolation, conditions on the VHF bands are often exceptionally good just when HF propagation is remarkably poor due to solar disturbances. VHF operators enthusiastically look forward to conditions when they can engage in auroral communications—exactly the kind of conditions that have HF operators scratching their heads, wondering where the ionosphere went.

ELEVATION ANGLES FOR HF COMMUNICATION

It was shown in connection with Fig 25 that the distance at which a ray returns to Earth depends on the eleva-



Fig 28—Distance plotted against wave angle (one-hop transmission) for the nominal range of heights for the E and F2 layers, and for the F1 layer.

tion angle at which it left the Earth (also known by other names: takeoff, launch or wave angle). Chapter 3, The Effects of Ground, in this book deals with the effects of local terrain, describing how the elevation angle of a horizontally polarized antenna is determined mainly by its height above the ground.

Although it is not shown specifically in Fig 25, propagation distance also depends on the layer height at the time, as well as the elevation angle. As you can probably imagine, the layer height is a very complex function of the state of the ionosphere and the Earth's geomagnetic field. There is a large difference in the distance covered in a single hop, depending on the height of the E or the F_2 layer. The maximum single-hop distance by the E layer is about 2000 km (1250 miles) or about half the maximum distance via the F_2 layer. Practical communicating distances for single-hop E or F layer work at various wave angles are shown in graphic form in **Fig 28**.

Actual communication experience usually does not fit the simple patterns shown in Fig 25. Propagation by means of the ionosphere is an enormously complicated business (which makes it all the more intriguing and challenging to radio amateurs, of course), even when the Sun is not in a disturbed state. Until the appearance of sophisticated computer models of the ionosphere, there was little definitive information available to guide the radio amateur in the design of his antenna systems for optimal performance over all portions of the 11-year solar cycle. Elevation angle information that had appeared for many years in *The ARRL Antenna Book* was measured for only one transmitting path, during the lowest portion of Solar Cycle 17 in 1934.

The *IONCAP* Computer Propagation Model

Since the 1960s several agencies of the US government have been working on a detailed computer program that models the complex workings of the ionosphere. The program has been dubbed *IONCAP*, short for "Ionospheric Communications Analysis and Prediction Program." *IONCAP* was originally written for a mainframe computer, but later versions have been rewritten to allow them to be run by high-performance personal computers. *IONCAP* incorporates a detailed database covering almost three complete solar cycles. The program allows the operator to specify a wide range of parameters, including detailed antenna models for multiple frequency ranges, noise models tailored to specific local environments (from low-noise rural to noisy residential QTHs), minimum elevation angles suitable for a particular location and antenna system, different months and UTC times, maximum levels of multipath distortion, and finally solar activity levels, to name the most significant of a bewildering array of options.

While *IONCAP* has a well-justified reputation for being very *unfriendly* to use, due to its mainframe, non-interactive background, it is also the one ionospheric model most highly regarded for its accuracy and flexibility, both by amateurs and professionals alike. It is the program used for many years to produce the long-term MUF charts formerly included in the "How's DX" monthly column of *QST* and now available on the Members Only ARRLWeb page.

IONCAP is not well suited for short-term forecasts of propagation conditions based on the latest solar indices received from WWV. It is an excellent tool, however, for long-range, detailed planning of antenna systems and shortwave transmitter installations, such as that for the Voice of America, or for radio amateurs. See the section later in this chapter describing other computer programs that can be used for short-term, interactive propagation predictions.

IONCAP/VOACAP Parameters

The elevation-angle statistical information contained in this section was compiled from thousands of *VOACAP* runs (an improved version of *IONCAP* developed by scientists from VOA, the Voice of America). These runs were done for a number of different transmitting locations throughout the world to important DX locations throughout the world.

Some assumptions were needed for setting *VOACAP* parameters. The transmitting and receiving sites were all assumed to be located on flat ground, with "average" ground conductivity and dielectric constant. Each site was assumed to have a clear shot to the horizon, with a minimum elevation angle less than or equal to 1°. Electrical noise at each

Table 3

Boston, Massachusetts, to All of Europe

Elev	*80 m*	*40 m*	*30 m*	*20 m*	*17 m*	*15 m*	*12 m*	*10 m*
1	4.1	9.6	4.6	1.7	2.1	4.4	5.5	7.2
2	0.8	2.3	7.2	1.4	2.8	2.8	3.7	5.3
3	0.3	0.7	4.3	3.1	2.4	2.2	4.4	7.9
4	0.5	4.1	8.7	11.6	12.2	9.4	8.1	3.9
5	4.6	4.8	7.5	12.7	14.3	13.1	9.2	11.2
6	7.1	8.9	5.5	9.2	9.6	12.2	9.2	7.2
7	8.5	6.9	7.2	4.6	7.9	7.4	10.0	5.9
8	5.1	7.0	5.4	3.2	5.9	7.4	4.8	6.6
9	3.3	5.6	3.2	3.1	2.1	3.9	8.1	9.2
10	1.0	4.0	7.9	6.3	5.1	3.7	11.1	6.6
11	1.9	3.8	9.7	10.2	7.2	5.4	3.7	7.9
12	5.6	3.4	4.8	8.5	6.9	7.4	4.8	6.6
13	11.0	3.0	2.4	4.1	5.9	4.6	3.3	2.6
14	7.6	4.8	2.0	2.7	3.8	3.9	6.3	5.9
15	5.3	7.9	2.0	1.5	2.4	1.7	1.5	2.0
16	2.8	6.4	3.8	2.9	1.5	1.3	2.6	2.6
17	5.0	3.4	4.5	3.1	1.0	1.5	0.0	0.0
18	4.2	2.0	3.1	3.1	2.0	2.2	1.8	1.3
19	5.7	1.4	1.4	2.3	1.3	0.7	0.0	0.0
20	6.6	1.4	1.2	1.8	1.1	1.3	0.7	0.0
21	4.4	1.4	0.5	0.8	0.7	0.7	0.4	0.0
22	2.3	2.4	1.0	1.1	0.6	1.3	0.7	0.0
23	1.3	1.8	0.1	0.3	0.1	0.0	0.0	0.0
24	0.6	1.0	0.5	0.5	0.4	0.7	0.0	0.0
25	0.3	0.8	0.3	0.1	0.4	0.0	0.0	0.0
26	0.0	0.5	0.7	0.2	0.1	0.4	0.0	0.0
27	0.1	0.1	0.1	0.2	0.1	0.2	0.0	0.0
28	0.0	0.3	0.1	0.2	0.0	0.2	0.0	0.0
29	0.1	0.0	0.2	0.0	0.0	0.0	0.0	0.0
30	0.0	0.1	0.0	0.0	0.0	0.0	0.0	0.0
31	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
32	0.0	0.0	0.1	0.0	0.0	0.0	0.0	0.0
33	0.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0
34	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
35	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

Percentage of time a particular frequency band is open on this specific propagation path.



Fig 29—The cumulative distribution function showing the total percentage of time that 40 meters is open, at or below each elevation angle, from Boston to the world. For example, 50% of the time the band is open to Europe from Boston, it is at 10° or less. The angles for DX work are indeed low.

receiving location was also assumed to be very low.

Transmitting and receiving antennas for the 3.5 to 30-MHz frequency range were specified to be isotropic-type antennas, but with +6 dBi gain, representing a good amateur antenna on each frequency band. These theoretical antennas radiate uniformly from the horizon, up to 90° directly overhead. With response patterns like this, these are obviously not real-world antennas. They do, however, allow the computer program to explore all possible modes and elevation angles.

Looking at the Elevation-Angle Statistical Data

Table 3 shows detailed statistical elevation informa-



Fig 30—The cumulative distribution function showing the total percentage of time that 80 meters is open, at or below each elevation angle, from Boston to the world. For example, 50% of the time the band is open to Europe from Boston, it is at 13° or less.



Fig 31—Overlay of signals and elevation angles, together with hop-mode information. This is for one month, October, at one level of solar activity, SSN=70, for the path from Newington, CT, to London, England. The mode of propagation does not closely follow the elevation angle. From 15 to 19 UTC the mode is 3F2 hops, and the elevation angle is approximately 12°. The same elevation angle is required from 23 to 03 UTC, but here the mode is 2F2 hops.

tion for the path from Boston, Massachusetts, near ARRL HQ in Newington, Connecticut, to all of Europe. The data incorporated into Table 3 shows the percentage of time versus elevation angle for all HF bands from 80 meters to 10 meters, over all portions of the 11-year solar cycle. The CD-ROM accompanying this book contains more tables such as this for more than 150 transmitting sites around the world. These tables are used by the *HFTA* program (and earlier *YT* program) and can also be imported into many programs, such as word processors or spreadsheets. Six important areas throughout the world are covered, one per table: all of Europe (from London, England, to Kiev, Ukraine), the Far East (centered on Japan), South America (Paraguay), Oceania (Melbourne, Australia), Southern Africa (Zambia) and South Asia (New Delhi, India).

You may be surprised to see in Table 3 that angles lower than 10° dominate the possible range of incoming angles for this moderate-distance path from New England to Europe. In fact, 1.7% of all the times when the 20-meter band is open to Europe, the takeoff angle is as low as 1°. You should recognize that very few real-world 20-meter antennas achieve much gain at such an extremely low angle—unless they just happen to be mounted about 400 feet high over flat ground or else are located on the top of a tall, steep mountain.

The situation is even more dramatic on 40 and 80 meters. **Fig 29** shows the “cumulative distribution function” of the total percentage of time (derived from Table 3) when 40 meters is open from Boston to the rest of the world, plotted against the elevation angle. For example, into Europe from Boston, 50% of the time when the band is open, it is at 10° or less. Into Japan from Boston, the statistics are even more revealing: 50% of the time when the band is open, the angle is 6° or less, and 90% of the time the angle is 13° or less!

Fig 30 shows the same sort of information for 80 meters from Boston to the world. For 50% of the time from Boston to Europe the elevation angle is 13° or less; at the 90% level the angle is 20° or less. For the path to Japan on 80 meters from Boston, 50% of the time the angle is 8° or less; at the 90% level, the angle is 13° or less. Now, to achieve peak gain on 80 meters at an elevation angle of 8° over flat land, a horizontally polarized antenna must be 500 feet high. You can begin to see why verticals can do very well on long-distance contacts on 80 meters, even when they are mounted over poorly conducting, rocky ground. Clearly, low angles are very important for successful DXing.

The Ionosphere Controls Propagation

You should always remember that it is the *ionosphere* that controls the elevation angles, *not* the transmitting antenna. The elevation response of a particular antenna only determines how strong or weak a signal is, at whatever angle (or angles) the ionosphere is supporting at that particular instant, for that propagation path and for that frequency.

If only one propagation mode is possible at a particular time, and if the elevation angle for that one mode happens to be 5°, then your antenna will have to work satisfactorily at that very low angle or else you won’t be able to communicate. For example, if your low dipole has a gain of –10 dBi at 5°, compared to your friend’s Yagi on a mountain top with +10 dBi gain at 5°, then you will be down 20 dB compared to his signal. It’s not that the elevation angle is somehow *too low*—the real problem here is that you don’t have *enough gain* at that particular angle where the ionosphere is supporting propagation. Many “flatlanders” can vividly recall the times when their mountain-top friends could easily work DX stations, while they couldn't even hear a whisper.

Looking at the Data—Further Cautions

A single propagation mode is quite common at the opening and the closing of daytime bands like 20, 15 or 10 meters, when the elevation angle is often lower (but not always) than when the band is wide open. The lower-frequency bands tend to support multiple propagation modes simultaneously. For example, **Fig 31** plots the signal strength (in dBμV) and the elevation angle for the dominant mode (with the strongest signal) over a 24-hour period from Newington to London in October, for a medium-level SSN = 70. The morning opening at 10 UTC starts out with a two-hop $2F_2$ mode (labeled 2F) at an elevation angle of 6°. By 11 UTC the mode has changed to a three-hop $3F_2$ (labeled 3F) at a 12° elevation angle. The band starts to close down with weaker signals after about 23 UTC. Note that this path actually supports both $2F_2$ and $3F_2$ modes most of the time. Either mode may be stronger than the other, depending on the particular time of day.

It is tempting to think that two-hop signals always occur at lower elevation launch angles, while three-hop signals require higher elevation angles. In reality, the detailed workings of the ionosphere are enormously complicated. From 22 UTC to 03 UTC, the elevation angles are higher than 11° for $2F_2$ hops. During much of the morning and early afternoon in Newington (from 11 to 13 UTC, and from 15 to 19 UTC), the angles are also higher than 11°. However, $3F_2$ hops are involved during these periods of time. The number of hops is not directly related to the elevation angles needed—changing layer heights account for this.



Fig 32—October 20-meter signals and elevation angles for the full range of solar activity, from W1 to England. The elevation angle does not closely follow the level of solar activity. What is important in designing a station capable of covering all levels of solar activity is to have flexibility in antenna elevation pattern response — to cover a wide range of possible angles.

Note that starting around 15 UTC, the mid-morning 20-meter "slump" (down some 10 dB from peak signal level) is caused by higher levels of mainly E-layer absorption when the Sun is high overhead. This condition favors higher elevation angles, since signals launched at lower angles must travel for a longer time through the lossy lower layer.

How does the situation change with different levels of solar activity? **Fig 32** overlays predicted signals and elevation angles for three levels of solar activity in October, again for the Newington-London path. Fig 32 shows the mid-morning slump dramatically when the solar activity is at



Fig 33—10-meter graph of the percentage of all openings versus elevation angles, together with overlay of elevation patterns over flat ground for three 10-meter antenna systems. Stacked antennas have wider "footprints" in elevation angle coverage for this example from New England to Europe.



Fig 34—15-meter graph of the percentage of all openings versus elevation angles, together with overlay of elevation patterns over flat ground for two 15-meter antenna systems. Like 10 meters, 15-meter stacked antennas have wider footprints in elevation angle coverage for this example from New England to Europe.



Fig 35—20-meter graph of the percentage of all openings from New England to Europe versus elevation angles, together with overlay of elevation patterns over flat ground for three 20-meter antenna systems.



Fig 36—40-meter graph of the percentage of all openings from New England to Europe versus elevation angles, together with overlays of elevation patterns over flat ground for a 100-foot high dipole and a large 4-element Yagi at 160 feet. Achieving gain at very low elevation angles requires very high heights above ground.



Fig 37—80-meter graph of the percentage of all openings from New England to Europe versus elevation angles, together with overlay of elevation patterns over flat ground for dipoles at two different heights. The 200-foot-high dipole clearly covers the necessary elevation angles better than does the 100-foot-high dipole, although a Four Square vertical array located over saltwater is even better for all angles needed.

a very high level, represented by SSN = 160. At 15 UTC, the signal level drops 35 dB from peak level, and the elevation angle rises all the way to 24°. By the way, as a percentage of all possible openings, the 24° angle occurs only rarely, 0.5% of the time. It barely shows up as a blip in Table 3. Elevation angles are *not* closely related to the level of solar activity.

IONCAP/VOACAP demonstrates that elevation angles do not follow neat, easily identified patterns, even over a 24-hour period—much less over all portions of the solar cycle. Merely looking at the percentage of all openings versus elevation angle, as shown in Table 3, does not tell the whole story, although it is probably the most statistically valid approach to station design, and possibly the most emotionally satisfying approach too. Neither is the whole story revealed by looking only at a snapshot of elevation angles versus time for one particular month, or for one solar activity level.

What is important to recognize is that the most effective antenna system will be one that can cover the *full range* of elevation angles, over the whole spectrum of solar activity, even if the actual angle in use at any one moment in time may not be easy to determine. For this particular path, from New England to all of Europe, an ideal antenna would have equal response over the full range of angles from 1° to 28°. Unfortunately, real-world antennas have a tough time covering such a wide range of elevation angles equally well.

Antenna Elevation Patterns

Figs 33 through **37** show overlays of the same sort of elevation angle information listed in Table 3, together with the elevation response patterns for typical antennas for the HF amateur bands 80, 40, 20, 15 and 10 meters. For example, Fig 34 shows an overlay for 20 meters, with three different types of 20-meter antennas. These are a 4-element Yagi at 90 feet, a 4-element Yagi at 120 feet and a large stack of four 4-element Yagis located at 120, 90, 60 and 30 feet. Each antenna is assumed to be mounted over flat ground. Placement on a hill with a long slope in the direction of interest would lower the required elevation angle by the amount of the hill's slope. For example, if a 10° launch angle is desired, and the antenna is placed on a hill with a slope of –5°, the antenna itself should be designed for a height that would optimize the response at 15° over flat ground—one wavelength high.

In Fig 35, the large stack of four 20-meter Yagis over flat ground comes closest to being ideal, but even this large array will not work well for that very small percentage of time when the angle needed is higher than about 20°. Some hams might conclude that the tiny percentage of time when the angles are very high doesn't justify an antenna tailored for that response. However, when that new DX country pops up on a band, or when a rare multiplier shows up in a contest, doesn't it always seem that the desired signal only comes in at some angle your antenna doesn't cover well? What do you do then, if your only antenna happens to be a large stack?

The answer to this, perhaps unique, high-angle problem lies in switching to using only the top antenna in the stack. In this example, the second elevation lobe of the 120-foot high antenna would cover the angles from 20° to 30° well, much better than the stack does. Note that the top antenna by itself would not be ideal for all conditions. It is simply too high much of the time when the elevation angles are higher than about 12°. The experience of many amateurs on the US East Coast with high 20-meter antennas bears this out—they find that 60 to 90-foot high antennas are far more consistent performers into Europe.

ONE-WAY PROPAGATION

On occasion a signal may be started on the way back toward the Earth by reflection from the F region, only to come down onto the top of the E region and be reflected back up again. This set of conditions is one possible explanation for the often-reported phenomenon called *one-way skip*. The reverse path may not necessarily have the same multilayer characteristic. The effect is more often a difference in the signal strengths, rather than a complete lack of signal in one direction, and many times there may be local noises that mask signals at one end of the path. It is important to remember these sorts of possibilities when a long-distance test with a new antenna system yields apparently conflicting results. Even many tests, on paths of different lengths and headings, may provide data that are difficult to understand. Communication by way of the ionosphere is not always a source of consistent answers to antenna questions.

Fig 37 shows the 80-meter path from New England to Europe with three different antennas. A really high dipole at a height of 200 feet above flat ground would certainly be an impressive antenna. But it would still be overshadowed dramatically by a Four-Square vertical array, at least at the low elevation angles needed often on this path. This is predicated on the Four Square being located over salt water, which provides a virtually perfect RF ground. At an elevation angle of 7°, the Four Square has 7 dB more gain than the 200-foot high dipole.

SHORT OR LONG PATH?

Propagation between any two points on the Earth's surface is usually by the shortest direct route—the *great-circle path* found by stretching a string tightly between the two points on a globe. If an elastic band going completely around the globe in a straight line is substituted for the string, it will show another great-circle path, going "the long way around." The long path may serve for communication over the desired circuit when conditions are favorable along the longer route. There may be times when communication is possible over the long path but not possible at all over the short path. Especially if there is knowledge of this potential at both ends of the circuit, long-path communication may work very well. Cooperation is almost essential, because both the aiming of directional antennas and the timing of the attempts must be right for any worthwhile result. The *IONCAP/VOACAP* computations in the preceding tables were made for short-path azimuths only.

Sunlight is a required element in long-haul communication via the F layer above about 10 MHz. This fact tends to define long-path timing and antenna aiming. Both are essentially the reverse of the "normal" for a given circuit. We know also that salt-water paths work better than overland ones. This can be significant in long-path work.

We can better understand several aspects of long-path propagation if you become accustomed to thinking of the Earth as a ball. This is easy if you use a globe frequently. A



Fig 38—K5ZI's computer-generated azimuthal-equidistant projection centered on Newington, Connecticut. (See Bibliography for ordering information.) Land masses and information showing long paths to Perth and Tokyo have been added. Notice that the paths in both cases lie almost entirely over water, rather than over land masses.

flat map of the world, of the azimuthal-equidistant projection type, is a useful substitute. The ARRL World Map is one, centered on Wichita, Kansas. A similar world map prepared by K5ZI and centered on Newington, Connecticut, is shown in **Fig 38**. These help to clarify paths involving those areas of the world.

Long-Path Examples

There are numerous long-path routes well known to DX-minded amateurs. Two long paths that work frequently and well when 28 MHz is open from the northeastern US are New England to Perth, Western Australia, and New England to Tokyo. Although they represent different beam headings and distances, they share some favorable conditions. By the long path, Perth is close to halfway around the world; Tokyo is about three-quarters of the way. On 28 MHz, both areas come through in the early daylight hours, Eastern Time, but not necessarily on the same days. Both paths are at their best around the equinoxes. (The sunlight is more uniformly distributed over transequatorial paths at these times.) Probably the factor that most favors both is the nature of the first part of the trip at the US end. To work Perth by way of long path, northeastern US antennas are aimed southeast, out over salt water for thousands of miles—the best low-loss start a signal could have. It is salt water essentially all the way, and the distance, about 13,000 miles, is not too much greater than the "short" path.

The long path to Japan is more toward the south, but still with no major land mass at the early reflection points. It is much longer, however, than that to Western Australia. Japanese signals are more limited in number on the long path than on the short, and signals on the average somewhat weaker, probably because of the greater distance.

On the short path, an amateur in the Perth area is looking at the worst conditions—away from the ocean, and out across the huge land mass of North America, unlikely to provide strong ground reflections. The short paths to both Japan and Western Australia, from most of the eastern half of North America, are hardly favorable. The first hop comes down in various western areas likely to be desert or mountains, or both, and not favored as reflection points.

A word of caution: Don't count on the long-path signals always coming in on the same beam heading. There can be notable differences in the line of propagation via the ionosphere on even relatively short distances. There can be more variations on long path, especially on circuits close to halfway around the world. Remember, for a point exactly halfway around, all directions of the compass represent great-circle paths.

FADING

When all the variable factors in long-distance HF communication are taken in account, it is not surprising that signals vary in strength during almost every contact beyond the local range. In VHF communication we can also encounter some fading at distances greater than just to the visible horizon. These are mainly the result of changes in the temperature and moisture content of the air in the first few thousand feet above the ground.

On paths covered by HF ionospheric modes, the causes of fading are very complex—constantly changing layer height and density, random polarization shift, portions of the signal arriving out of phase, and so on. The energy arriving at the receiving antenna has components that have been acted upon differently by the ionosphere. Often the fading is very different for small changes in frequency. With a signal of a wideband nature, such as high-quality FM, or even double-sideband AM, the sidebands may have different fading rates from each other, or from the carrier. This causes severe distortion, resulting in what is termed *selective fading*. The effects are greatly reduced (but still present to some extent) when single-sideband (SSB) is used. Some immunity from fading during reception (but not to the distortion induced by selective fading) can be had by using two or more receivers on separate antennas, preferably with different polarizations, and combining the receiver outputs in what is known as a *diversity* receiving system.

OTHER PROPAGATION MODES

In propagation literature there is a tendency to treat the various propagation modes as if they were separate and distinct phenomena. This they may be at times, but often there is a shifting from one to another, or a mixture of two or more kinds of propagation affecting communication at one time. In the upper part of the usual frequency range for F-region work, for example, there may be enough tropospheric bending at one end (or both ends) to have an appreciable effect on the usable path length. There is the frequent combination of E and F-region propagation in long-distance work. And in the case of the E region, there are various causes of ionization that have very different effects on communication. Finally, there are weak-signal variations of both tropospheric and ionospheric modes, lumped under the term "scatter." We look at these phenomena separately here, but in practice we have to deal with them in combination, more often than not.

Sporadic E (E_S)

First, note that this is *E-subscript-s,* a usefully descriptive term, wrongly written "Es" so often that it is sometimes called "ease," which is certainly not descriptive. *Sporadic E* is ionization at E-layer height, but of different origin and communication potential from the E layer that affects mainly our lower amateur frequencies.

The formative mechanism for sporadic E is believed to be wind shear. This explains ambient ionization being distributed and compressed into a ledge of high density, without the need for production of extra ionization. Neutral winds of high velocity, flowing in opposite directions at slightly different altitudes, produce shears. In the presence of the Earth's magnetic field, the ions are collected at a particular altitude, forming a thin, overdense layer. Data from rockets entering E_s regions confirm the electron density, wind velocities and height parameters.

The ionization is formed in clouds of high density, lasting only a few hours at a time and distributed randomly. They vary in density and, in the middle latitudes in the Northern Hemisphere, move rapidly from southeast to northwest. Although E_s can develop at any time, it is most prevalent in the Northern Hemisphere between May and August, with a minor season about half as long beginning in December (the summer and winter solstices). The seasons and distribution in the Southern Hemisphere are not so well known. Australia and New Zealand seem to have conditions much like those in the US, but with the length of the seasons reversed, of course. Much of what is known about E_s came as the result of amateur pioneering in the VHF range.

Correlation of E_s openings with observed natural phenomena, including sunspot activity, is not readily apparent, although there is a meteorological tie-in with high-altitude winds. There is also a form of E_s, mainly in the northern part of the north temperate zone, that is associated with auroral phenomena.

At the peak of the long E_s season, most commonly in late June and early July, ionization becomes extremely dense and widespread. This extends the usable range from the more common "single-hop" maximum of about 1400 miles to "double-hop" distances, mostly 1400 to 2500 miles. With 50-MHz techniques and interest improving in recent years, it has been shown that distances considerably beyond 2500 miles can be covered. There is also an E_s "link-up" possibility with other modes, believed to be involved in some 50-MHz work between antipodal points, or even long-path communication beyond 12,500 miles.

When E_s is particularly strong and widespread, even the HF bands can suddenly go *short skip* producing exceptionally strong signals from distances that would normally be in the no-signal "skip zone." Editor N6BV distinctly remembers a spectacular 20-meter E_s opening in September 1994, during the "Hiram Percy Maxim/125" anniversary celebration, when he was living in New Hampshire. Signals on 20 meters were 30 to 40 dB over S9 from all along the Eastern Seaboard, from W2 to W4. One exasperated W3 complained that he had been calling in the huge pileup for 20 minutes. N6BV glanced at the S meter and saw that the W3 was 20 dB over S9, normally a very strong 20-meter SSB signal, but not when almost everybody else was 40 dB over S9!

Such short-skip conditions caused by Sporadic E are more common on 10 meters than they are on 15 or 20 meters. They can result in excellent transAtlantic 10-meter openings during the summer months—when 10 meters is not normally open for F_2 ionospheric propagation.

The MUF for E_s is not known precisely. It was long thought to be around 100 MHz, but in the last 25 years or so there have been thousands of 144-MHz contacts during the summer E_s season. Presumably, the possibility also exists at 222 MHz. The skip distance at 144 MHz does average much longer than at 50 MHz, and the openings are usually brief and extremely variable.



Fig 39—Schematic of a simple backscatter path. Stations A and B are too close to make contact via normal F-layer ionospheric refraction. Signals scattered back from a distant point on the Earth's surface (S), often the ocean, may be accessible to both A and B to create a backscatter circuit. (*Courtesy of The ARRL Handbook.*)

The terms "single" and "double" hop may not be accurate technically, since it is likely that cloud-to-cloud paths are involved. There may also be "no-hop" E_s. At times the very high ionization density produces critical frequencies up to the 50-MHz region, with no skip distance at all. It is often said that the E_s mode is a great equalizer. With the reflecting region practically overhead, even a simple dipole close to the ground may do as well over a few hundred miles as a large stacked antenna array designed for low-angle radiation. It's a great mode for low power and simple antennas on 28 and 50 MHz.

HF Scatter Modes

The term "skip zone" (where no signals are heard) should not be taken too literally. Two stations communicating over a single ionospheric hop can be heard to some degree by other stations at almost any point along the way, unless the two are running low power and using simple antennas. Some of the wave energy is *scattered* in all directions, including back to the starting point and farther.

Backscatter functions like a sort of HF ionospheric radar. **Fig 39** shows a schematic for a simple backscatter path. The signal launched from point A travels through the ionosphere back to earth at Point S, the scattering point. Here, the rough terrain of the land scatters signals in many directions, one of which propagates a weak signal back through the ionosphere to land at point B. Point B would normally be in the no-signal skip zone between A and S. Because backscatter signals arrive from multiple directions, through various paths through the ionosphere, they have a characteristic "hollow" sound, much like you get when you talk into a paper tube with its many internal reflections.

Because backscatter involves mainly scattering from the Earth at the point where the strong ionospherically propagated signal comes down, it is a part of HF over-the-horizon radar techniques. (The infamous 1970s-era "woodpecker" was an over-the-horizon HF radar.) Amateurs using sounding techniques have shown that you can tell to what part of the world a band is usable (single-hop F) by probing the backscatter with a directive antenna and high transmitter power, even when the Earth contact point is open ocean. In fact, that's where the mode is at its best, because ocean waves can be efficient backscatter reflectors.

Backscatter is very useful on 28 MHz, particularly when that band seems dead simply because nobody is active in the right places. The mode keeps the 10-meter band lively in the low years of the solar cycle, thanks to the never-say-die attitude of some users. The mode is also an invaluable tool of 50-MHz DX aspirants, in the high years of the sunspot cycle, for the same reasons. On a high-MUF morning, hundreds of 6-meter beams may zero in on a hot spot somewhere in the Caribbean or South Atlantic, where there is no land, let alone other 6-meter stations—keeping in contact while they wait for the band to open to a place where there is somebody.

Sidescatter is similar to backscatter, except the ground scatter zone is off the direct line between participants. A typical example, often observed during the lowest years of the solar cycle, is communication on 28 MHz between the eastern US (and adjacent areas of Canada) and much of the European continent. Often, this may start as "backscatter chatter" between Europeans whose antennas are turned toward the Azores. Then suddenly the North Americans join the fun, perhaps for only a few minutes, but sometimes much longer, with beams also pointed toward the Azores. Duration of the game can be extended, at times, by careful reorientation of antennas at both ends, as with backscatter. The secret, of course, is to keep hitting the highest-MUF area of the ionosphere and the most favorable ground-reflection points.

The favorable route is usually, but not always, south of the great-circle heading (for stations in the Northern Hemisphere). There can also be sidescatter from the auroral regions. Sidescatter signals are stronger than backscatter signals using the same general area of ground scattering.

Sidescatter signals have been observed frequently on the l4-MHz band, and can take place on any band where there is a large window between the MUF and the LUF. For sidescatter communications to occur, the thing to look for is a common area to which the band is open from both ends of the path (the Azores, in the above example), when there is no direct-path opening. It helps if the common area is in the open ocean, where there is less scattering loss than over land.

GRAY-LINE PROPAGATION

The *gray line*, sometimes called the *twilight zone*, is a band around the Earth between the Sunlit portion and darkness. Astronomers call this the *terminator*. The terminator is a somewhat diffused region because the Earth's atmosphere tends to scatter the light into the darkness. **Fig 40** illustrates the gray line. Notice that on one side of the Earth, the gray line is coming into daylight (sunrise), and on the other side it is coming into darkness (sunset).



Fig 40—The gray line or terminator is a transition region between daylight and darkness. One side of the Earth is coming into sunrise, and the other is just past sunset.

Propagation along the gray line is very efficient, particularly on the lower bands, especially on 80 or 160 meters, so greater distances can be covered than might be expected for the frequency in use. One major reason for this is that the D layer, which absorbs HF signals, disappears rapidly on the sunset side of the gray line, and has not yet built up on the sunrise side.

The gray line runs generally north and south, but varies as much as 23° either side of the north-south line. This variation is caused by the tilt of the Earth's axis relative to its orbital plane around the Sun. The gray line will be exactly north and south at the equinoxes (March 21 and September 21). On the first day of Northern Hemisphere summer, June 21, it is tilted to the maximum of 23° one way, and on December 21, the first day of winter, it is tilted 23° the other way.

To an observer on the Earth, the direction of the terminator is always at right angles to the direction of the Sun at sunrise or sunset. It is important to note that, except at the equinoxes, the gray-line direction will be different at sunrise from that at sunset. This means you can work different areas of the world in the evening than you worked in the morning.

It isn't necessary to be located inside the twilight zone in order to take advantage of gray-line propagation. The effects can be used to advantage before sunrise and after sunset. This is because the Sun "rises" earlier and "sets" later on the ionospheric layers than it does on the Earth below.

What HF Bands Are Open—Where and When?

The CD-ROM included at the back of this book includes summary and detailed propagation predictions for more than 150 transmitting locations around the world. This propagation data was calculated using *CapMAN*, an upgraded variety of the mainframe propagation program *IONCAP*. The predictions were done for default antennas and powers that are representative of a "big-gun" station. Of course, not everyone has a big-gun station in his/her backyard, but this represents what the ultimate possibilities are, statistically speaking. After all, if the bands aren't open for the big guns, they are unlikely to be open for the "little pistols" too.

Let's see how propagation is affected if the smoothed sunspot number is 0 (corresponding to a smoothed solar flux of about 65), which is classified as a "Very Low" level of solar activity. And we'll examine the situation for a sunspot number of 100 (a smoothed solar flux of 150), which is typical of a "Very High" portion of the solar cycle.

Five-Band Summary Predictions

Tables 4 and **5** are Summary tables showing the predicted signal levels (in S units) from Boston, Massachusetts, to the rest of the world for the month of January. The Boston transmitting site is representative of the entire New England area of the USA. The target geographic receiving regions for the major HF bands from 80 through 10 meters are tabulated versus UTC (Universal Coordinated Time) in hours. Table 4 represents a Very Low level of solar activity, while Table 5 is for a Very High level of solar activity.

Each transmitting location is organized by six levels of solar activity over the whole 11-year solar cycle:

- VL (Very Low: SSN between 0 to 20)
- LO (Low: SSN between 20 to 40)
- ME (Medium: SSN between 40 to 60)
- HI (High: SSN between 60 to 100)
- VH (Very High: SSN between 100 to 150)
- UH (Ultra High: SSN greater than 150)

The receiving geographic regions for each frequency band are abbreviated:

Table 4

Printout of summary propagation table for Boston to the rest of the world, for a Very Low level of solar activity in the month of January. The abbreviations for the target geographic areas are: EU = Europe, FE = Far East, SA = South America, AF = Africa, AS = south Asia, OC = Oceania, and NA = North America.

```
Jan., MA (Boston), for SSN = Very Low, Sigs in S-Units. By N6BV, ARRL.
              80 Meters                    40 Meters                    20 Meters                    15 Meters                    10 Meters
UTC  EU  FE  SA  AF  AS  OC  NA   EU  FE  SA  AF  AS  OC  NA   EU  FE  SA  AF  AS  OC  NA   EU  FE  SA  AF  AS  OC  NA   EU  FE  SA  AF  AS  OC  NA    UTC
  0  9   -   9+  9   9   -   9+   9   8   9+  9+  9   2   9+   -   8   9+  7   4   8   9+   -   -   -   -   -   -   1    -   -   -   -   -   -   2      0
  1  9   -   9+  9   9   -   9+   9   6   9+  9+  9+  6   9+   -   4   9   4   2   6   9+   -   -   -   -   -   -   1    -   -   -   -   -   -   2      1
  2  9   -   9+  9+  8   1   9+   9   6   9+  9+  9   8   9+   -   1   8   1   2   3   9+   -   -   -   -   -   -   1    -   -   -   -   -   -   2      2
  3  9   -   9+  9+  8   6   9+   9   6   9+  9+  9   8   9+   -   -   8   2   2   -   9+   -   -   -   -   -   -   1    -   -   -   -   -   -   2      3
  4  9   -   9+  9+  1   8   9+   9   8   9+  9+  9   9   9+   -   1   8   7   2   -   9+   -   -   -   -   -   -   1    -   -   -   -   -   -   2      4
  5  9   -   9+  9+  -   9   9+   9   8   9+  9+  8   9   9+   -   1   9   8   2   -   9    -   -   -   -   -   -   1    -   -   -   -   -   -   2      5
  6  9+  -   9+  9+  -   9   9+   7   8   9+  9+  8   9   9+   -   1   9+  8   -   -   9    -   -   -   -   -   -   1    -   -   -   -   -   -   2      6
  7  9   7   9+  9   -   9   9+   7   8   9+  9   8   9   9+   -   1   9+  1   -   1   8    -   -   -   -   -   -   1    -   -   -   -   -   -   2      7
  8  9   8   9+  9   -   9   9+   8   9   9+  9   8   9+  9+   -   1   9+  -   -   5   9    -   -   -   -   -   -   1    -   -   -   -   -   -   2      8
  9  8   8   9+  7   6   9   9+   8   9   9+  9   9   9+  9+   -   -   9   1   -   7   9    -   -   -   -   -   -   1    -   -   -   -   -   -   2      9
 10  5   8   9+  4   6   9   9+   9   9   9+  9   9   9+  9+   -   3   9   5   -   6   9    -   -   -   -   -   -   1    -   -   -   -   -   -   2     10
 11  3   8   9+  -   5   9   9+   8   9   9+  7   9   9+  9+   5   -   9+  9   5   1*  8    -   -   -   -   -   -   1    -   -   -   -   -   -   2     11
 12  1   8   9   -   4   9   9+   7   9   9+  4   8   9   9+   9   5   9+  9+  9   2*  8    -   -   5   6   -   -   1    -   -   -   -   -   -   2     12
 13  -   6   1   -   -   7   9+   6   8   9+  1   8   9   9+   9+  9   9+  9   9   7   8    4   -   9+  9   7   -   1    -   -   -   -   -   -   1     13
 14  -   -   -   -   -   1   9+   5   7   8   -   8   8   9+   9+  9   9+  9   9   9   9+   7   2*  9+  9   9   -   8    -   -   5   -   -   -   1     14
 15  -   -   -   -   -   -   9+   4   6   5   -   6   7   9+   9+  9   9+  9   9   9   9+   7   5   9+  9   2   2   5    -   -   5   -   -   -   -     15
 16  -   -   -   -   -   -   9+   5   6   4   2   5   4   9+   9+  8   9+  9+  9   9   9+   5   1   9+  8   2*  2   9    -   -   5   -   -   -   1     16
 17  -   -   -   -   -   -   9+   6   5   5   5   6   1   9+   9+  5   9+  9+  3   9   9+   -   -   9+  9   -   3   9+   -   -   5   -   -   -   1     17
 18  1   -   -   -   -   -   9+   8   6   6   7   6   -   9+   9+  6   9+  9+  4   9   9+   -   -   9+  9   -   7   9+   -   -   5   -   -   -   1     18
 19  3   -   -   2   -   -   9+   9   7   8   8   8   -   9+   6   6   9+  9+  6   9   9+   -   -   9+  9   -   9   9+   -   -   2   -   -   -   1     19
 20  5   -   7   5   -   -   9+   9   8   9+  9   8   4   9+   1   7   9+  9+  8   9   9+   -   -   9+  4   -   9   9    -   -   -   -   -   -   1     20
 21  8   3   9   8   6   -   9+   9   8   9+  9+  9   7   9+   -   8   9+  9   8   9   9+   -   -   9+  -   -   9   6    -   -   -   -   -   -   1     21
 22  9   3   9+  9   8   -   9+   9   8   9+  9+  9   5   9+   -   9+  9+  9   8   9   9+   -   -   9   -   -   7   1    -   -   -   -   -   -   1     22
 23  9   2   9+  9   9   -   9+   9   8   9+  9+  9   4   9+   -   9+  9+  9   5   9   9+   -   1   6   -   -   2   3    -   -   -   -   -   -   2     23
     EU  FE  SA  AF  AS  OC  NA   EU  FE  SA  AF  AS  OC  NA   EU  FE  SA  AF  AS  OC  NA   EU  FE  SA  AF  AS  OC  NA   EU  FE  SA  AF  AS  OC  NA
```

Table 5

Printout of summary propagation table for Boston to the rest of the world, for a Very High level of solar activity in the month of January.

```
Jan., MA (Boston), for SSN = Very High, Sigs in S-Units. By N6BV, ARRL.
          80 Meters               40 Meters               20 Meters               15 Meters               10 Meters
UTC  EU FE SA AF AS OC NA   EU FE SA AF AS OC NA   EU FE SA AF AS OC NA   EU FE SA AF AS OC NA   EU FE SA AF AS OC NA   UTC
 0   9+ -  9+ 9+ 8  -  9+   9+ 5  9+ 9+ 9  -  9+   1  9+ 9+ 9+ 9+ 9  9+   -  9  9+ 2  2  9+ 9+   -  1  8  -  -  8  9+     0
 1   9+ -  9+ 9+ 8  -  9+   9+ 4  9+ 9+ 9  2  9+   1  9  9+ 8  9+ 9+ 9+   -  3  9  -  7  9+ 9    -  -  -  -  -  4  2      1
 2   9+ -  9+ 9+ 7  -  9+   9+ 4  9+ 9+ 9  7  9+   1  9  9+ 8  9  9+ 9+   -  -  3  -  -  7  9    -  -  -  -  -  -  2      2
 3   9+ -  9+ 9+ 1  2  9+   9+ 4  9+ 9+ 9  9  9+   -  7  9+ 7  8  9+ 9    -  -  -  -  -  -  -    -  -  -  -  -  -  2      3
 4   9+ -  9+ 9+ -  7  9+   9+ 5  9+ 9+ 8  9  9+   -  5  9+ 9  9  9  9+   -  -  1  -  -  -  -    -  -  -  -  -  -  2      4
 5   9+ -  9+ 9+ -  8  9+   9+ 6  9+ 9+ 7  9  9+   -  5  9+ 9  9  5  9+   -  -  -  -  -  -  -    -  -  -  -  -  -  2      5
 6   9+ -  9+ 9+ -  8  9+   9+ 7  9+ 9+ 7  9  9+   -  8  9+ 8  9  5  9+   -  -  -  -  -  -  -    -  -  -  -  -  -  2      6
 7   9+ -  9+ 9+ -  8  9+   9  8  9+ 9+ 7  9+ 9+   -  9  9+ -  7  9  9+   -  -  1  -  -  -  -    -  -  -  -  -  -  2      7
 8   9  7  9+ 9  -  8  9+   9  8  9+ 9+ 8  9+ 9+   -  9  9+ -  4  9+ 9+   -  -  1  -  -  -  2    -  -  -  -  -  -  2      8
 9   8  7  9+ 7  -  8  9+   9  9  9+ 9  8  9+ 9+   -  6  9+ -  1  9+ 9+   -  -  -  -  -  -  1    -  -  -  -  -  -  2      9
10   5  8  9+ 2  3  8  9+   9  9  9+ 8  8  9  9+   4  -  9+ 9+ 1  5  9    -  -  -  -  -  -  -    -  -  -  -  -  -  2     10
11   1  8  9+ -  4  9  9+   8  9  9+ 5  8  9  9+   9+ 4* 9+ 9+ 7  -  8    -  -  9  9  -  -  -    -  -  -  -  -  -  2     11
12   -  7  8  -  1  9  9+   6  9  9+ 1  8  9  9+   9+ 9  9+ 9  9  1* 9+   9  8* 9+ 9+ 9  5* -    -  2* 9  9  1  1* 2     12
13   -  -  -  -  -  2  9+   4  8  8  -  7  9  9+   9+ 9  9+ 9  9  9+ 9+   9+ 7  9+ 9+ 9+ 3* 9    9  5* 9+ 9+ 9  6* 2     13
14   -  -  -  -  -  -  9+   2  7  4  -  5  8  9+   9+ 9  9+ 8  9  9  9+   9+ 9  9+ 9+ 9+ 9  9+   9  6* 9+ 9+ 9  1* 1     14
15   -  -  -  -  -  -  9    1  5  -  -  4  5  9+   9+ 9  9+ 9  9  9  9+   9+ 9+ 9+ 9+ 9+ 9  9+   9  5  9+ 9+ 6  6  8     15
16   -  -  -  -  -  -  8    3  4  -  -  3  1  9+   9+ 8  9  9  9  9  9+   9+ 9+ 9+ 9+ 9  9+ 9+   9  8  9+ 9+ -  8  9     16
17   -  -  -  -  -  -  8    5  3  -  2  4  -  9+   9+ 8  9+ 9+ 9  9  9+   9+ 9  9+ 9+ 1* 9+ 9+   -  8  9+ 9+ -  8  9+    17
18   -  -  -  -  -  -  9    7  4  2  5  5  -  9+   9+ 9  9+ 9+ 9  9  9+   9+ 9  9+ 9+ 1  9+ 9+   -  7  9+ 9+ -  9+ 9+    18
19   1  -  -  1  -  -  9+   8  5  6  8  7  -  9+   9+ 9  9+ 9+ 9  9  9+   -  9+ 9+ 9+ 2  9  9+   -  6  9+ 9+ -  9+ 9+    19
20   4  -  2  5  -  -  9+   9  6  9  9  8  -  9+   9+ 9  9+ 9+ 9  9  9+   -  8  9+ 9+ 3  9  9+   -  1  9+ 9  -  9  9+    20
21   7  -  8  7  1  -  9+   9+ 7  9+ 9+ 8  1  9+   8  9  9+ 9+ 9  9  9+   -  6  9+ 9+ 3  9  9+   -  -  9+ 5* -  9+ 9+    21
22   9  2  9+ 9  8  -  9+   9+ 7  9+ 9+ 9  4  9+   2  9+ 9+ 9+ 9  9  9+   -  9+ 9+ 9  1  9+ 9+   -  5  9+ 4* -  9  6     22
23   9  -  9+ 9  8  -  9+   9+ 7  9+ 9+ 9  -  9+   1  9+ 9+ 9+ 9  9  9+   -  9+ 9+ 6  -  9  9+   -  7  9+ 2* -  9  2     23
     EU FE SA AF AS OC NA   EU FE SA AF AS OC NA   EU FE SA AF AS OC NA   EU FE SA AF AS OC NA   EU FE SA AF AS OC NA
```

• EU	All of Europe
• FE	The Far East, centered on Japan
• SA	South America, centered on Paraguay
• AF	All of Africa, centered on Zambia
• AS	South Asia, centered on India
• OC	Oceania, centered on Sydney, Australia
• NA	North America, all across the USA

These propagation files show the highest predicted signal strength (in S-units) throughout the generalized receiving area, for a 1500-W transmitter and rather good antennas on both sides of the circuit. The standard antennas are:

- 100-foot high inverted-V dipoles for 80 and 40 meters
- 3-element Yagi at 100 feet for 20 meters
- 4-element Yagi at 60 feet for 15 and 10 meters.

For example, Summary Table 4 shows that in January during a period of Very Low solar activity, 15 meters is open to somewhere in Europe from Boston for only 4 hours, from 13 to 16 UTC, with a peak signal level between S4 and S7. Now look at Table 5, where 15 meters is predicted to be open to Europe during a period of Very High solar activity for 7 hours, from 12 to 18 UTC, with peak signals ranging from S9 to S9+.

Both Tables 4 and 5 represent *snapshots* of predicted signal levels to generalized receiving locations—that is, they are computed for a particular month, from a particular transmitting location, and for a particular level of solar activity. These tables provide summary information that is particularly valuable for someone planning for an operating event such as a DXpedition or a contest.

What happens if you don't have a big-gun station with high antennas or the 1500-W power assumed in the analyses above? You can discount the S-Meter readings to reflect a smaller station:

- Subtract 2 S units for a dipole instead of a Yagi at same height on 20/15/10 meters.
- Subtract 3 S units for a dipole at 50 feet instead of a Yagi at 100 feet on 20 meters.
- Subtract 1 S unit for a dipole at 50 feet rather than a dipole at 100 feet on 40/80 meters.
- Subtract 3 S units for 100 W rather than 1500 W.
- Subtract 6 S units for 5 W (QRP) rather than 1500 W.

For example, Table 4 predicts an S7 signal into Boston from Europe on 15 meters at 14 UTC. If a European station is using a dipole at 50 feet, with 100 W of power, what

20 Meters: Jan., MA (Boston), for SSN = Very High, Sigs in S-Units. By N6BV, ARRL.

UTC -->

Zone	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23
KL7 = 01	9+	9+	9+	7	-	-	-	-	-	-	-	-	-	-	-	3	9+	9+	9+	9+	9+	9+	9+	9+
VO2 = 02	9+	9	9	9	9	9	8	7	5	3	2	1	5	9+	9+	9+	9+	9+	9+	9+	9+	9+	8	9+
W6 = 03	9+	9+	9+	7	7	1	1	5	8	8	3	-	-	1	9	9+	9+	9+	9+	9	9	9+	9+	9+
W0 = 04	9+	9+	9+	8	5	5	5	5	3	2	1	-	-	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+
W3 = 05	4	2	2	2	2	2	2	3	3	3	3	2	1	1	8	9+	9+	9+	9+	9+	9+	9+	9+	9
XE1 = 06	9+	9+	7	9	9+	9+	9+	9+	9+	9+	9	8	9+	9+	9+	9+	9	9	9	9	9+	9+	9+	9+
TI = 07	9+	9+	8	9	9	9	9	9	9	9+	9	9+	9+	9+	9+	9+	9	8	9	9	9+	9+	9+	9+
VP2 = 08	9+	9+	9+	9+	9+	9+	9+	9+	9+	8	9	9+	9+	9+	9+	9+	9	9+	9+	9+	9+	9+	9+	9+
P4 = 09	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9	9	9	9	9+	9+	9+	9+	9+
HC = 10	9+	8	9+	9	9	9	9	9	7	3	1	7	9+	9+	9	5	5	5	7	8	9+	9+	9+	9+
PY1 = 11	9+	9+	9+	9	9	9+	9+	9	8	6	9	9+	8	2	1	-	-	1	4	8	9	9+	9+	9+
CE = 12	9+	9+	9+	9+	9+	9+	9+	9+	9	8	8	9+	9	8	2	1	1	-	1	3	7	9	9+	9+
LU = 13	9+	9+	9+	9+	9+	9+	9+	9+	8	8	8	9+	8	4	2	1	-	-	1	4	8	9	9+	9+
G = 14	-	-	-	-	-	-	-	-	-	-	-	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	8	2	-
I = 15	-	-	-	-	-	-	-	-	-	-	4	9	9	9	9	9	9	9+	9+	9	8	2	-	-
UA3 = 16	1	1	1	-	-	-	-	-	-	-	-	8	9	9+	9+	9+	9	8	5	-	-	-	-	1
UN = 17	1	-	-	8	7	7	7	1	-	-	-	2	9	9	9	6	-	-	2	4	8	9	5	4
UA9 = 18	6	7	6	6	9	9	9	7	4	1	-	-	8	8	6	6	5	6	7	8	9	9	8	7
UA0 = 19	9+	9	9	6	5	5	8	8	8	4	-	-	2	6	8	8	8	7	4	4	7	9	9+	9+
4X = 20	8	6	3	1	-	3	4	-	-	-	1	8	8	8	8	8	9	9	9+	9	9	8	7	7
HZ = 21	9+	9	4	3	8	8	2	-	-	-	1	7	8	9	8	8	9	9	9	9	9	9	9	9
VU = 22	7	5	8	7	6	7	5	-	-	-	-	6	9	9	9	9	3	2	2	2	8	8	9	8
JT = 23	9	9+	9	5	7	8	8	6	3	-	-	2*	8	8	5	6	8	8	8	8	9	7	5	6
VS6 = 24	9	9	9	5	4	5	7	8	6	1	-	1*	5	7	1	1	1	1	4	2	-	-	-	9
JA1 = 25	9	9	8	7	5	5	8	9	9	6	-	1	1	2	7	7	6	2	-	-	7	9	9+	9
HS = 26	9	9	6	4	2	-	-	2	1	-	-	2*	9	9	9	9	8	7	5	4	5	-	1*	1
DU = 27	9	8	7	-	-	-	5	7	7	1	-	-	1*	9	9	7	6	4	5	3	1*	1*	8	9
YB = 28	9	8	1	-	-	-	-	-	-	-	-	4*	8	9	9	9	8	8	9	9	9	9	9+	9+
VK6 = 29	3*	4*	-	-	-	-	-	-	5	3	-	-	-	5	9	9	9	8	9	9	9	9	9	8
VK3 = 30	1*	-	-	-	-	-	1	3	9	9	4	-	-	9+	9	8	2	1	-	-	1	2*	5*	4*
KH6 = 31	9	9+	9+	9+	8	2	2	6	4	-	-	-	-	-	-	-	9	9	8	7	6	4	6	7
KH8 = 32	-	2	9	9	9	5	5	9	9+	9+	5	-	-	9+	9	9	8	5	3	1	-	-	-	-
CN = 33	-	-	-	-	-	-	-	-	-	-	9	9+	9	9	8	9	9	9+	9+	9+	9+	9+	9+	7
SU = 34	9	8	3	3	-	1	4	-	-	-	2	7	8	8	8	8	9	9	9+	9+	9+	9+	8	8
6W = 35	9+	8	-	-	2	7	5	-	-	-	9+	9+	8	5	4	3	7	9	9+	9+	9+	9+	9+	9+
D2 = 36	9+	9+	5	3	9	9	8	-	-	-	3	-	-	-	-	4	4	7	8	9	9+	9+	9+	9+
5Z = 37	9+	9	2	4	8	8	1	-	-	-	2	-	-	3	5	5	7	8	9	9	9+	9+	9+	9+
ZS6 = 38	9+	9+	8	7	8	9	6	-	-	-	-	-	-	-	1*	1	2	6	8	9	9+	9+	9+	9+
FR = 39	9+	8	2	1	4	1	-	-	-	-	-	-	-	2*	3*	1*	1	3	8	9	9+	9+	9+	9+
FJL = 40	9+	9+	7	4	7	8	7	1	-	-	-	1*	8	9	9	9	9	9	9	9	9+	9+	9+	9+
Zone	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23

UTC -->

Expected signal levels using 1500 W and 3-element Yagis at 100 feet at each station.

Fig 41—The 20-meter page from Detailed propagation-prediction for the month of January, during Very High solar conditions, from Boston to 40 CQ Zones throughout the world. There are similar pages for each month/SSN level for 160, 80, 40, 20, 15 and 10 meters. These Detailed tables are very useful for planning DX work.

would this do to the predicted signal level in Boston? You would compute: S7 – 2 S units (for a dipole instead of Yagi) – 3 S units (100 W rather than 1500 W) = an S2 signal in Boston. A QRP station with a 4-element 15-meter Yagi at 60 feet would yield: S7 – 6 S units = an S1 signal in Boston.

More Detailed Predictions

Let's now look at table in **Fig 41**, which is the Detailed 20-meter page for the same conditions in Table 5: January at a Very High level of solar activity from Boston to the world. There are six such pages per month/SSN level, covering 160, 80, 40, 20, 15 and 10 meters.

In a Detailed prediction table, the world is divided into the 40 CQ Zones, with a particular sample location in each zone. For example, Zone 14 in Western Europe is represented by a location in London, England (call sign G), while Zone 25 is represented by a location in Tokyo, Japan (call sign JA1). Note that Zones with large ham populations are highlighted with dark shadowing for easy identification. For example, Zones 3, 4 and 5 cover the USA, while Zones 14, 15 and 16 cover the majority of Europe. Zone 25 covers the big ham population in Japan.

Let's revisit the example above for computing the signal strength for a station in London, but this time on 20 meters. Again, we'll assume that the G station has a dipole at 50 feet and 100 W of transmitter power. At 14 UTC in Zone 14, the table in Fig 40 predicts a very healthy signal for the reference big-gun station, at S9+. This is a signal at least S9 + 10 dB. Here, we're going to round off the plus 10 dB to 2 S units, giving a fictional 11 S units to start. We discount this for the smaller station: S11 – 3 S units (for a dipole at 50 feet instead of a 3-element Yagi at 100 feet) – 3 S units (100 W rather than 1500 W) = S5 signal in Boston. This is a respectable signal and will probably get through, in the absence of stronger signals calling the Boston station at the same time, of course.

Here's another example of how to use the Detailed propagation-prediction tables. Let's say that at 1230 UTC in January you work a VU2 station in New Delhi on 15 meters from Boston, where the local time is 7:30 AM.

You need a 20-meter contact also for the 5-Band DXCC award, so you quickly check the table in Fig 40 for Zone 22 (VU) and find that the predicted signal strength is S9. Your new VU2 friend is willing to jump to 20 meters and so you QSY to make the contact.

But perhaps you are late leaving for work and so you ask your new VU2 friend to make a schedule with you later that evening. Again, you consult the Detailed prediction table for 20 meters and find that signals are predicted to be S8 or stronger from 20 to 23 UTC, dropping to S7 at 00 UTC. You quickly ask your new friend whether he minds waking up at 4:30 AM his time to make a schedule with you at 2300 UTC, because New Delhi is 5½ hours ahead of UTC. You determined this using the program *GeoClock*, which is included with the software on the CD-ROM in the back of this book and which you run in the background on *Windows*. Luckily, he's a very gracious fellow and agrees to meet you on a specific frequency at that time.

The Detailed propagation-prediction tables give you all the information needed to plan your operations to maximize your enjoyment chasing DX. You can use these tables to plan a 48-hour contest next month, or next year—or you can use them to plan a schedule with your ham cousin on the West Coast on Saturday afternoon.

THE PROPAGATION BIG PICTURE

A newcomer to the HF bands could easily be overwhelmed with the sheer amount of data available in the Summary (and particularly the Detailed) prediction tables on the CD-ROM included with this book. So here's a long-term, "big-picture" view of HF propagation that might help answer some common questions. For example, what month really is the best for working DX around the clock? Or what level of solar activity is necessary to provide an opening between your QTH and somewhere in the South Pacific?

Table 6 is a table showing the number of hours in a day during each month when each major HF band is open to the same receiving areas shown in Tables 4 and 5. The listing is for New England, for three levels of solar activity: Very Low, Medium and Very High. The number of hours are separated in Table 6 by slashes. (Versions of Table 6 for other areas around the US are on the CD-ROM that accompanies this book in **Fig6Tab.PDF**.)

Let's examine the conditions for New England to Europe on 15 meters for October. The entry shows "7/11/17," meaning that for a Very Low level of solar activity, 15 meters is open for 7 hours; for a Medium level, it is open for 11 hours and for a Very High level of solar activity it is open for 17 hours a day.

Even for a Very Low level of solar activity, the month with the most hours available per day from Boston to somewhere in Europe is October, with 7 hours, followed by the next largest month of March, with 6 hours. For a Very High level of solar activity, however, the 15-meter band is open to Europe for 18 hours in April, followed by 17 hours availability in September and October. Arguably, the CQ World Wide Contest Committee picked the very best month for higher-frequency propagation when they chose October for the Phone portion of that contest.

You can easily see that even at a Very High level of solar activity, the summer months are not very good to work DX, particularly on east-west paths. For example, the 10-meter band is very rarely open from New England to Europe after the month of April, even when solar activity is at the highest levels possible. Things pick up after September, even for a Medium level of solar activity. Again, October looks like the most fruitful month in terms of the number of hours 10 meters is open to Europe under all levels of solar conditions.

Ten meters is open more regularly on north-south paths, such as from New England to South America or to southern Africa. It is open as much as 10 hours a day during March and October to deep South America, and 7 hours a day in October to Africa—even during the lowest parts of the solar cycle. (Together with the sporadic-E propagation that 10 meters enjoys during the summer, this band can often be a lot of fun even during the sunspot doldrums. You just have to *be operating* on the band, rather than avoiding it because you know the sunspots are "spotty!")

Now, look at the 20-meter band in Table 6. From New England, twenty is open to somewhere in South America for 24 hours a day, no matter the level of solar activity. Note that Table 6 doesn't predict the level of signals available; it just shows that the band is open with a signal strength greater than 0 on the S meter. Look back at Summary Table 4 for the predicted signal strengths in January at a Very Low level of solar activity. There, you can see that the signal strength from New England into deep South America is always S8 or greater for a big gun station. A lot of the time during the night the band sounds dead, simply because everyone is either asleep or operating on a lower frequency.

For the 40-meter band in Table 6, during the month of January the band is open to Europe for 24 hours a day, whatever the level of solar activity is. Look now at Table 4, and you'll see that the predicted level for Very Low solar activity varies from S4 to S9. Local QRM or QRN would probably disrupt communications on 40 meters in Europe for stateside signals weaker than perhaps S3 or S4. Even though you might well be able to hear Europeans from New England during the day, they probably won't hear you because of local conditions, including local S9+ European stations and atmospheric noise from nearby thunderstorms. New England stations with big antennas can often hear Europeans on 40 meters as early as noontime, but must wait until the late afternoon before the Europeans can hear them above their local noise and QRM.

Let's say that you want to boost your country total on 80 meters by concentrating on stations in the South Pacific. The best months would be from November to

Table 6

The number of hours per day when a particular band is open to the target geographic areas in Table 4, as related to the level of solar activity (Very Low, Medium and Very High). This table is customized for Boston to the rest of the world. Some paths are open 24 hours a day, plus or minus QRM and local QRN, no matter what the level of solar activity is. See CD-ROM for other transmitting locations.

```
MA (Boston)
Hours Open to Each Region for Very-Low/Medium/Very-High SSNs

80 Meters:
Month  Europe   Far East  So. Amer.  Africa   So. Asia  Oceania   No. Amer.
Jan   17/17/16   5/ 4/ 3  17/17/16  16/16/15   8/ 7/ 5  11/10/ 9  24/24/24
Feb   17/16/15   3/ 3/ 2  17/16/16  15/15/14   6/ 4/ 4  10/ 9/ 9  24/24/24
Mar   15/15/14   3/ 2/ 1  16/16/15  15/13/13   4/ 4/ 3   9/ 8/ 7  24/24/24
Apr   13/13/12   1/ 0/ 0  16/16/14  13/13/13   3/ 3/ 1   9/ 8/ 7  24/24/24
May   12/11/10   0/ 0/ 0  16/15/14  12/11/10   2/ 1/ 1   7/ 6/ 6  24/24/24
Jun   10/ 9/ 8   0/ 0/ 0  14/14/14  11/10/10   1/ 1/ 0   6/ 5/ 5  24/24/24
Jul   11/11/ 9   0/ 0/ 0  15/14/14  11/11/11   2/ 1/ 1   7/ 6/ 5  24/24/24
Aug   13/11/11   0/ 0/ 0  16/16/14  13/12/11   3/ 2/ 1   7/ 7/ 6  24/24/24
Sep   14/13/11   2/ 1/ 0  17/16/14  13/13/12   4/ 4/ 2   9/ 8/ 8  24/24/24
Oct   15/15/13   3/ 2/ 1  17/17/16  14/14/13   5/ 4/ 4   9/ 9/ 7  24/24/24
Nov   17/17/15   4/ 4/ 2  17/17/16  16/15/14   8/ 7/ 4  11/10/ 9  24/24/24
Dec   19/18/17   7/ 6/ 4  18/18/17  16/16/16  11/ 9/ 7  12/11/11  24/24/24

40 Meters:
Month  Europe   Far East  So. Amer.  Africa   So. Asia  Oceania   No. Amer.
Jan   24/24/24  15/16/15  24/24/21  21/20/19  21/21/19  19/18/15  24/24/24
Feb   24/24/21  13/11/11  24/23/20  20/19/18  19/19/17  16/15/14  24/24/24
Mar   23/22/19  10/ 9/ 7  24/21/18  19/17/17  17/17/13  13/13/13  24/24/24
Apr   21/19/18   8/ 6/ 4  22/20/18  17/16/15  16/11/ 8  13/13/11  24/24/24
May   19/17/17   5/ 4/ 3  22/18/17  17/16/14   9/ 8/ 5  12/11/10  24/24/24
Jun   17/15/13   4/ 2/ 2  22/18/16  16/15/14   7/ 5/ 5  11/10/ 9  24/24/24
Jul   18/16/15   5/ 4/ 2  24/18/17  17/15/14   8/ 7/ 5  12/11/10  24/24/24
Aug   19/17/16   7/ 5/ 4  24/19/18  18/16/15  11/10/ 6  13/12/11  24/24/24
Sep   22/21/17   9/ 8/ 5  23/20/18  18/17/16  14/11/ 7  13/13/12  24/24/24
Oct   24/23/20  12/11/ 8  24/23/19  20/18/17  17/16/14  16/13/13  24/24/24
Nov   24/24/22  14/13/12  24/24/20  21/19/18  21/20/17  17/17/13  24/24/24
Dec   24/24/24  18/19/22  24/24/21  23/21/19  24/23/22  21/19/18  24/24/24
```

February in terms of the number of hours per day when the 80-meter band is open to Oceania. You can see by reading across the line for each month that the level of solar activity is not hugely important on 80 meters to any location. Common experience (backed by the statistical information in Table 6) is that the 80-meter band is open only marginally longer when sunspots are low.

This is true to a greater extent on 40 meters. Thus you may hear the generalization that the low bands tend to be better during periods of low solar activity, while the upper HF bands (above 10 MHz) tend to be better when the sun is more active.

Table 6 can give you a good handle on what months are the most productive for DXing and contesting. It should be no surprise to most veteran operators that the fall and winter months are the best times to work DX.

```
20 Meters:
Month  Europe   Far East  So. Amer.  Africa   So. Asia  Oceania   No. Amer.
Jan   13/16/22  15/22/22  24/24/24  20/21/21  18/20/22  18/23/22  24/24/24
Feb   12/18/23  13/21/24  24/24/24  22/22/24  15/21/24  18/23/24  24/24/24
Mar   15/18/24  17/20/24  24/24/24  22/24/24  18/21/24  16/24/24  24/24/24
Apr   15/20/24  19/22/24  24/24/24  21/24/24  19/22/24  18/24/24  24/24/24
May   19/23/24  22/24/24  24/24/24  23/24/24  23/24/24  21/24/24  24/24/24
Jun   22/24/24  24/24/24  24/24/24  24/24/24  24/24/24  24/24/24  24/24/24
Jul   19/24/24  24/24/24  24/24/24  21/24/24  24/24/24  23/24/24  24/24/24
Aug   15/20/24  20/24/24  24/24/24  20/24/24  20/24/24  19/24/24  24/24/24
Sep   16/19/24  17/21/24  24/24/24  21/24/24  18/21/24  17/24/24  24/24/24
Oct   15/21/24  16/20/24  24/24/24  22/24/24  19/22/24  17/24/24  24/24/24
Nov   14/20/23  14/22/24  24/24/24  20/24/24  17/21/24  19/23/24  24/24/24
Dec   11/17/24  13/22/24  24/24/24  17/23/24  12/22/24  16/24/24  24/24/24

15 Meters:
Month  Europe   Far East  So. Amer.  Africa   So. Asia  Oceania   No. Amer.
Jan    4/ 6/ 7   2/ 9/13  12/15/16   9/13/13   3/ 4/ 7   9/12/13  24/15/16
Feb    4/ 7/12   4/10/14  13/18/23  11/13/16   3/ 7/13   8/13/15  22/16/19
Mar    6/ 9/14   2/13/15  14/21/24  13/17/22   5/11/17  10/14/17  15/16/23
Apr    0/10/18   3/13/18  15/23/24  15/18/24   9/15/19  11/15/21  16/16/24
May    1/13/16   6/10/19  17/20/24  14/18/24  13/17/18  10/16/19  20/19/24
Jun    0/ 2/16   0/ 9/15  16/21/24  14/18/24   5/15/18  10/12/20  24/22/22
Jul    0/ 2/16   0/ 5/18  15/19/24  12/18/24   0/12/18   4/12/20  24/22/21
Aug    0/ 2/14   0/ 8/17  14/18/22  13/16/22   0/12/17   6/10/19  22/19/21
Sep    1/10/17   6/13/17  14/16/24  13/17/22   9/14/17   9/14/17  16/16/22
Oct    7/11/17  10/13/17  12/16/22  12/15/22   7/12/17  12/13/15  18/15/22
Nov    5/ 8/14   8/11/14  12/16/22  11/14/17   3/ 7/16  10/13/15  20/16/21
Dec    3/ 6/ 9   2/10/13  12/15/23   8/13/15   2/ 4/12   9/12/14  24/15/18

10 Meters:
Month  Europe   Far East  So. Amer.  Africa   So. Asia  Oceania   No. Amer.
Jan    0/ 1/ 4   0/ 1/ 8   6/11/13   0/ 7/10   0/ 1/ 3   0/ 3/11  23/24/24
Feb    0/ 2/ 7   0/ 2/10   8/12/14   0/ 9/13   0/ 3/ 5   0/ 7/13  24/24/24
Mar    0/ 0/ 8   0/ 1/10  10/14/20   1/11/14   0/ 0/ 8   0/ 7/13  23/24/24
Apr    0/ 0/ 8   0/ 0/ 8   7/14/21   0/12/17   0/ 0/13   0/ 5/11  18/24/24
May    0/ 0/ 0   0/ 0/ 1   7/12/20   1/10/17   0/ 1/12   0/ 2/11  17/20/22
Jun    0/ 0/ 0   0/ 0/ 0   7/11/18   0/ 3/17   0/ 0/ 0   0/ 0/ 2  21/19/23
Jul    0/ 0/ 0   0/ 0/ 0   2/ 9/19   0/ 2/18   0/ 0/ 7   0/ 0/ 6  16/16/24
Aug    0/ 0/ 0   0/ 0/ 0   2/10/17   0/ 1/16   0/ 0/10   0/ 0/ 8  17/17/24
Sep    0/ 0/ 8   0/ 1/10   7/13/18   0/11/16   0/ 0/10   0/ 2/ 9  19/24/24
Oct    0/ 5/ 9   0/ 2/11  10/12/16   7/12/14   0/ 5/ 9   0/ 8/12  24/24/24
Nov    0/ 4/ 8   0/ 3/11   9/12/15   5/10/13   0/ 3/ 6   4/10/12  24/24/24
Dec    0/ 3/ 6   0/ 1/ 8   8/11/13   1/ 8/12   0/ 1/ 4   2/ 7/12  23/23/24
```

Do-It-Yourself Propagation Prediction

Very reliable methods of determining the MUF for any given radio path have been developed over the last 50 years. As discussed previously, these methods are all based on the smoothed sunspot number (SSN) as the measure of solar activity. It is for this reason that smoothed sunspot numbers hold so much meaning for radio amateurs and others concerned with radio-wave propagation—they are the link to past (and future) propagation conditions.

Early on, the prediction of propagation conditions required tedious work with numerous graphs, along with charts of frequency contours overlaid, or overprinted, on world maps. The basic materials were available from an agency of the US government. Monthly publications provided the frequency-contour data a few months in advance. Only rarely did amateurs try their hand at predicting propagation conditions using these hard-to-use methods.

Today's powerful PCs have given the amateur wonderful tools to make quick-and-easy HF propagation predictions, whether for a contest or a DXpedition. The summary and detailed prediction tables described earlier in this chapter were generated using *CAPMan*, a modernized version of the mainframe *IONCAP* program, on a PC.

While tremendously useful to setting up schedules and for planning strategy for contests, both the Summary and Detailed prediction tables located on the CD-ROM accompanying this book show signal strength. They do not show

Table 7
Features and Attributes of Propagation Prediction Programs

	ASAPS V. 4	*CAPMan*	*VOACAP Windows*	*ACE-HF*	*W6ELProp V. 2.70*	*WinCAP Wizard 2*	*PropLab Pro*
User Friendliness	Good	Good	Good	Excellent	Good	Good	Poor
Operating System	Windows	DOS	Windows	Windows	Windows	Windows	DOS
Uses k or A index	No	Yes	No	No	Yes	Yes	Yes
User library of QTHs	Yes	Yes	Yes	Yes-RX	Yes	Yes	No
Bearings, distances	Yes	Yes	Yes	Yes	Yes	Yes	Yes
MUF calculation	Yes	Yes	Yes	Yes	Yes	Yes	Yes
LUF calculation	Yes	Yes	Yes	Yes	No	Yes	Yes
Wave angle calculation	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Vary minimum wave angle	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Path regions and hops	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Multipath effects	Yes	Yes	Yes	Yes	No	Yes	Yes
Path probability	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Signal strengths	Yes	Yes	Yes	Yes	Yes	Yes	Yes
S/N ratios	Yes	Yes	Yes	Yes	No	Yes	Yes
Long-path calculation	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Antenna selection	Yes	Yes	Yes	Yes	Indirectly	Isotropic	Yes
Vary antenna height	Yes	Yes	Yes	Yes	Indirectly	No	Yes
Vary ground characteristics	Yes	Yes	Yes	Yes	No	No	No
Vary transmit power	Yes	Yes	Yes	Yes	Indirectly	Yes	Yes
Graphic displays	Yes	Yes	Yes	Yes	Yes	Yes	2D/3D
UT-day graphs	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Area Mapping	No	Yes	Yes	Yes	Yes	No	Yes
Documentation	Yes	Yes	On-line	Yes	Yes	Yes	Yes
Price class	$275+	$89	free†	$99	free§	$29.95+	$150††

Price classes are for late 2003 and subject to change.
†Available on the World Wide Web: **elbert.its.bldrdoc.gov/hf.html**
§Available on the World Wide Web at: **www.qsl.net/w6elprop/**
+ Shipping and handling extra.
††Available on the World Wide Web: **www.spacew.com/www/proplab.html**

other information that is also in the underlying databases used to generate them. They don't, for example, show the dominant elevation angles and neither do they show reliability statistics. You may want to run propagation-prediction software yourself to get into the really "nitty-gritty" details.

Modern programs are designed for quick-and-easy predictions of propagation parameters. See **Table 7** for a listing of a number of popular programs. The basic input information required is the smoothed sunspot number (SSN) or smoothed solar flux, the date (month and day), and the latitudes and longitudes at the two ends of the radio path. The latitude and longitude, of course, are used to determine the great-circle radio path. Most commercial programs tailored for ham use allow you to specify locations by the call sign. The date is used to determine the latitude of the Sun, and this, with the sunspot number, is used to determine the properties of the ionosphere at critical points on the path.

Of course, just because a computer program predicts that a band will be open on a particular path, it doesn't follow that the Sun and the ionosphere will always cooperate! A sudden solar flare can result in a major geomagnetic storm, taking out HF communication anywhere from hours to days. There is still art, as well as a lot of science, in predicting propagation. In times of quiet geomagnetic activity, however, the prediction programs are good at forecasting band openings and closings.

Obtaining Sunspot Number/Solar Flux Data

After you have chosen and then set up a computer program for evaluation of a particular path, you will still need the sunspot number or solar flux level for the period in question. A caution must be stated here—for best accuracy and consistency, use the average of solar flux values taken from actual observations, perhaps from WWV/WWVH, over the previous three or four days. Many amateur packet systems archive WWV flux numbers (plus planetary k_p and A_p indices). Solar flux numbers can vary dramatically from day to day, but the Earth's ionosphere is relatively slow to respond to instantaneous changes in solar radiation. This caveat also



Fig 42—Smoothed sunspot number, with predictions, from 1940 to 2040. This was extrapolated based on data from 1840 to 1983. Cycle 22 actually peaked in Nov 1989, at a monthly smoothed sunspot number of 158. Propagation on the higher frequencies throughout the peak of Cycle 22 was good to excellent, since the monthly smoothed sunspot number stayed at 100 or above from July 1988 through May 1992. (*Courtesy of Naval Ocean Systems Center,* San Diego.*)*



Fig 43—Effective Sunspot Number (SSN$_e$) produced by NWRA. Note large drop in effective SSN due to a geomagnetic storm commencing Oct 1, 2002. (*Courtesy of Northwest Research Associates.*)

holds for sunspot numbers derived, using Fig 18, from WWV/WWVH solar flux numbers.

Fig 42 shows a graph produced in the early 1980s of smoothed sunspot numbers for Solar Cycles 17 through 21, with predictions for Cycles 22 through 26. The graph covers a period of 100 years, from 1940 to 2040, and may be used for making long-term or historical calculations. Just remember that the graph shows smoothed numbers. The solar activity at any given time can be significantly lower or significantly higher than the graph indicates. In fact, Cycle 22 peaked at the end of 1989, as predicted, but with a monthly smoothed sunspot level of 158, quite a bit higher than predicted. Cycle 23 peaked in early 2002 at a level of about 115, a considerably higher level than the predicted value.

WWV PROPAGATION DATA

For the most current data on what the Sun is doing, National Institute of Standards and Technology stations WWV and WWVH broadcast information on solar activity at 18 and 45 minutes past each hour, respectively. These propagation bulletins give the solar flux, geomagnetic A-Index, Boulder K-Index, and a brief statement of solar and geomagnetic activity in the past and coming 24-hour periods, in that order. The solar flux and A-Index are changed daily with the 2118 UT bulletin, the rest every three hours—0018, 0318, 0618 UT and so on. On the Web, up-to-date WWV information can be found at: **ftp://ftp.sel.noaa.gov/pub/latest/wwv.txt** or on the NOAA Web page **www.sec.noaa.gov/**.

Some other useful Web sites are: **dx.qsl.net/propagation/**, **www.dxlc.com/solar**, **hfradio.org/propagation.html**. The Solar Terrestrial Dispatch page contains a wealth of propagation-related information: **www.spacew.com/**. You may also access propagation information on your local PacketCluster. Use the command SH/WWV/*n*, where *n* is the number of spots you wish to see (five is the default).

Another excellent method for obtaining an "equivalent sunspot number" (SSN$_e$) is to go to the Space Weather site of Northwest Research Services: **www.nwra-az.com/spawx/ssne24.html**. NWRA compares real-time ionospheric sounder data around the world with predictions using various levels of SSN looking for the best match. They thus "back into" the actual effective sunspot number. **Fig 43** is a typical NWRA graph, which covers the week ending 6 October 2002. Note the sudden decrease in SSN$_e$ after a geomagnetic storm depressed SSN$_e$ by more than 50%.

The A-Index

The WWV/WWVH A-Index is a daily figure for the state of activity of the Earth's magnetic field. It is updated with the 2118/2145 UT bulletin. The A-Index tells you mainly how yesterday was, but it is very revealing when charted regularly, because geomagnetic disturbances nearly always recur at four-week intervals.

The K-Index

The K-Index (new every three hours) reflects Boulder readings of the Earth's geomagnetic field in the hours just preceding the bulletin data changes. It is the nearest thing to current data on radio propagation available. With new data every three hours, K-Index trend is important. Rising is bad news; falling is good, especially related to propagation on paths involving latitudes above 30° north. Because this is a Boulder, Colorado, reading of geomagnetic activity, it may not correlate closely with conditions in other areas.

The K-Index is also a timely clue to aurora possibilities. Values of 4, and rising, warn that conditions associated with



Fig 44—Plot of the estimated planetary k index, K_p, for the last four days. (*Courtesy NOAA/SEC.*)

auroras and degraded HF propagation are present in the Boulder area at the time of the bulletin's preparation. A NOAA Web site that carries up-to-date planetary K_p data is: **www.sel.noaa.gov/ftpmenu/plots/2003_plots/kp.html**. **Fig 44** is a graph from this Web site for four days starting 27 April 2003 to 30 April 2003. This was a period of significant geomagnetic activity, indicated by K_p indices of 5 and 4.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below.

E. V. Appleton and W.R. Piggott, "Ionospheric Absorption Measurements during a Sunspot Cycle," *J. Atmos. Terr. Phys.*, Vol 3, p 141, 1954.

D. Bilitiza, *International Reference Ionosphere (IRI 90)*, National Space Science Data Center, Greenbelt, MD, 1990.

D. Bray, "Method of Determining VHF/HF Station Capabilities," *QST*, Nov 1961.

A. Brekke, "Physics of the Upper Polar Atmosphere," (John Wiley and Sons: New York, 1997).

R. R. Brown, "Demography, DXpeditions and Magneto-Ionic Theory," *The DX Magazine*, Vol. X, No. 2, p 44, Mar/Apr 1998.

R. R. Brown, *The Little Pistol's Guide to HF Communication* (Sacramento: WorldRadio Books, 1996).

R. R. Brown, "Signal Ducting on the 160 Meter Band," *Communications Quarterly*, p 65, Spring 1998.

R. R. Brown, "Unusual Low-Frequency Signal Propagation at Sunrise," *Communications Quarterly*, p 67, Fall 1998.

R. R. Brown,, "Atmospheric Ozone, a Meteorological Factor in Low-Frequency and 160 Meter Propagation," *Communications Quarterly*, Spring 1999.

K. Davies, *Ionospheric Radio* (London: Peter Peregrinus Ltd, 1990). Excellent technical reference.

R. Garcia, S. Solomon, S. Avery, G. C. Reid, "Transport of Nitric Oxide and the D-Region Winter Anomaly," *J. Geophys. Res.*, Vol 92, p 977, 1987.

J. Hall, "Propagation Predictions and Personal Computers," Technical Correspondence, *QST*, Dec 1990, pp 58-59 (description of *IONCAP* as used for ARRL. publications).

E . Harper, *Rhombic Antenna Design* (New York: D. Van Nostrand Co, Inc, 1941).

H. Hertz, *Electric Waves*, translated by D. E. Jones (London: MacMillan, 1893).

R. D. Hunsucker, *Radio Techniques for Probing the Terrestrial Ionosphere* (New York: Springer-Verlag).

R. D. Hunsucker, J. K. Hargreaves, *The High Latitude Ionosphere and Its Effects on Radio Propagation* (Cambridge: Cambridge University Press, 2003).

W. D. Johnston, Computer-calculated and computer-drawn great-circle maps are offered. An 11 × 14-inch map is custom made for your location. Write to K5ZI, PO Box 640, Organ, NM 88052, tele 505-382-7804.

T.L. Killeen, R.M. Johnsson, "Upper Atmospheric Waves, Turbulence, and Winds: Importance for Mesospheric and Thermospheric Studies," **earth.agu.org/revgeophys/killee00/killee00.html**.

J. L. Lynch, "The Maunder Minimum," *QST*, Jul 1976, pp 24-26.

J. C. Maxwell, *A Treatise on Electricity and Magnetism*, Vols I and II (Oxford: Oxford University Press, 1873).

M. W. Maxwell, *Reflections—Transmission Lines and Antennas* (Newington, CT: ARRL, 1990) [out of print].

M. W. Maxwell, *Reflections II—Transmission Lines and Antennas* (Sacramento, CA: 2001).

L. F. McNamara, *The Ionosphere: Communications, Surveillance, and Direction Finding* (Malabar, FL: Krieger Publishing Company, 1991). Another excellent technical reference on propagation.

L. F. McNamara, *Radio Amateur's Guide to the Ionosphere* (Malabar, FL: Krieger Publishing Company, 1994). Excellent, quite-readable text on HF propagation.

A. K. Paul, "Medium Scale Structure of the F Region," *Radio Science*, Volume 24, No. 3, p. 301, 1989.

W. R. Piggott, K. Rawer, "URSI Handbook of Ionogram Interpretation and Reduction," Report UAG-50. World Data Center A for Solar-Terrestrial Physics, Boulder, CO, 1975.

E. Pocock, "Sporadic-E Propagation at VHF: A Review of Progress and Prospects," *QST*, Apr 1988, pp 33-39.

E. Pocock, "Auroral-E Propagation at 144 MHz," *QST*, Dec 1989, pp 28-32.

E. Pocock, "Propagation Forecasting During Solar Cycle 22," *QST*, Jun 1989, pp 18-20.

G. C. Reid, "Ion Chemistry of the D-region," *Advances in Atomic and Molecular Physics*, Vol 12, Academic Press, 1976.

R. B. Rose, “MINIMUF: A Simplified MUF-Prediction Program for Microcomputers,” *QST*, Dec 1982, pp 36-38

M. L. Salby, “Fundamentals of Atmospheric Physics,” (Academic Press: Boulder, CO, 1996).

S. C. Shallon, W6EL: *MINIPROP PLUS*, a commercially prepared program written for Amateur Radio users; 11058 Queensland St, Los Angeles, CA 90034-3029.

R. D. Straw, *All the Right Angles* (New Bedford, PA: LTA, 1993). Out of print.

R. D. Straw, “*ASAPS* and *CAPMAN*: HF Propagation-Prediction Software for the IBM PC,” *QST*, Dec 1994, pp 79-81.

R. D. Straw, “Heavy-Duty HF Propagation-Prediction/Analysis Software,” Part 1: *QST*, Sep 1996, pp 28-32; Part 2: *QST*, Oct 1996, pp 28-30.

Chapter 27

Antenna and Transmission-Line Measurements

The principal quantities measured on transmission lines are line current or voltage, and standing-wave ratio (SWR). You make measurements of current or voltage to determine the power input to the line. SWR measurements are useful in connection with the design of coupling circuits and the adjustment of the match between the antenna and transmission line, as well as in the adjustment of these matching circuits.

For most practical purposes a relative measurement is sufficient. An uncalibrated indicator that shows when the largest possible amount of power is being put into the line is just as useful, in most cases, as an instrument that measures the power accurately. It is seldom necessary to know the actual number of watts going into the line unless the overall efficiency of the system is being investigated. An instrument that shows when the SWR is close to 1:1 is all you need for most impedance-matching adjustments. Accurate measurement of SWR is necessary only in studies of antenna characteristics such as bandwidth, or for the design of some types of matching systems, such as a stub match.

Quantitative measurements of reasonable accuracy demand good design and careful construction in the measuring instruments. They also require intelligent use of the equipment, including a knowledge not only of its limitations but also of stray effects that often lead to false results. Until you know the complete conditions of the measurements, a certain amount of skepticism regarding numerical data resulting from amateur measurements with simple equipment is justified. On the other hand, purely qualitative or relative measurements are easy to make and are reliable for the purposes mentioned above.

LINE CURRENT AND VOLTAGE

A current or voltage indicator that can be used with coaxial line is a useful piece of equipment. It need not be elaborate or expensive. Its principal function is to show when the maximum power is being taken from the transmitter; for any given set of line conditions (length, SWR, etc). This will occur when you adjust the transmitter coupling for maximum current or voltage into the transmission line. Although the final-amplifier plate or collector current meter is frequently used for this purpose, it is not always a reliable indicator. In many cases, particularly with a screen-grid tube in the final stage, minimum loaded plate current does not occur simultaneously with maximum power output.

RF VOLTMETER

You can put together a germanium diode in conjunc-



Fig 1—RF voltmeter for coaxial line.

C1, C2—0.005- or 0.01-µF ceramic.
D1—Germanium diode, 1N34A.
J1, J2—Coaxial fittings, chassis-mounting type.
M1—0-1 milliammeter (more sensitive meter may be used if desired; see text).
R1—6.8 kΩ, composition, 1 W for each 100 W of RF power.
R2—680 Ω, 1/2 or 1 W composition.
R3—10 kΩ, 1/2 W (see text).

tion with a low-range milliammeter and a few resistors to form an RF voltmeter suitable for connecting across the two conductors of a coaxial line, as shown in **Fig 1**. It consists of a voltage divider, R1-R2, having a total resistance about 100 times the Z_0 of the line (so the power consumed will be negligible) with a diode rectifier and milliammeter connected across part of the divider to read relative RF voltage. The purpose of R3 is to make the meter readings directly proportional to the applied voltage, as nearly as possible, by swamping the resistance of D1, since the diode resistance will vary with the amplitude of the current through the diode.

You may construct the voltmeter in a small metal box, indicated by the dashed line in the drawing, and fitted with coax receptacles. R1 and R2 should be carbon-composition resistors. The power rating for R1 should be 1 W for each 100 W of carrier power in the matched line; separate 1- or 2-W resistors should be used to make up the total power rating required, to the total resistance as given. Any type of resistor can be used for R3; the total resistance should be such that about 10 V dc will be developed across it at full scale. For example, a 0-1 milliammeter would require 10 kΩ, a 0-500 microammeter would take 20 kΩ, and so on. For comparative measurements only, R3 may be a variable resistor so the sensitivity can be adjusted for various power levels.

In constructing such a voltmeter, you should exercise care to prevent inductive coupling between R1 and the loop formed by R2, D1 and C1, and between the same loop and the line conductors in the assembly. With the lower end of R1 disconnected from R2 and grounded to the enclosure, but without changing its position with respect to the loop, there should be no meter indication when full power is going through the line.

If more than one resistor is used for R1, the units should be arranged end-to-end with very short leads. R1 and R2 should be kept 1/2 inch or more from metal surfaces parallel to the body of the resistor. If you observe these precautions the voltmeter will give consistent readings at frequencies up to 30 MHz. Stray capacitance and stray coupling limit the accuracy at higher frequencies but do not affect the utility of the instrument for comparative measurements.

Calibration

You may calibrate the meter for RF voltage by comparison with a standard such as an RF ammeter. This requires that the line be well matched so the impedance at the point of measurement is equal to the actual Z_0 of the line. Since in that case $P = I^2Z_0$, the power can be calculated from the current. Then $E = \sqrt{PZ_0}$. By making current and voltage measurements at a number of different power levels, you can obtain enough points to draw a calibration curve for your particular setup.



Fig 2—A convenient method of mounting an RF ammeter for use in a coaxial line. This is a metal-case instrument mounted on a thin bakelite panel. The cutout in the metal clears the edge of the meter by about 1/8 inch.

RF AMMETERS

Although they are not as widely available as they used to be, if you can find one on the surplus market or at a hamfest, an RF ammeter is a good way to gauge output power. You can mount an RF ammeter in any convenient location at the input end of the transmission line, the principal precaution being that the capacitance to ground, chassis, and nearby conductors should be low. A bakelite-case instrument can be mounted on a metal panel without introducing enough shunt capacitance to ground to cause serious error up to 30 MHz. When installing a metal-case instrument on a metal panel, you should mount it on a separate sheet of insulating material so that there is 1/8 inch or more separation between the edge of the case and the metal.

A 2-inch instrument can be mounted in a 2 × 4 × 4-inch metal box, as shown in **Fig 2**. This is a convenient arrangement for use with coaxial line. Installed this way, a good quality RF ammeter will measure current with an accuracy that is entirely adequate for calculating power in the line. As discussed above in connection with calibrating RF voltmeters, the line must be closely matched by its load so the actual impedance is resistive and equal to Z_0. The scales of such instruments are cramped at the low end, however, which limits the range of power that can be measured by a single meter. The useful current range is about 3 to 1, corresponding to a power range of about 9 to 1.

SWR Measurements

On parallel-conductor lines it is possible to measure the standing-wave ratio by moving a current (or voltage) indicator along the line, noting the maximum and minimum values of current (or voltage) and then computing the SWR from these measured values. This cannot be done with coaxial line since it is not possible to make measurements of this type inside the cable. The technique is, in fact, seldom used with open lines because it is not only inconvenient but sometimes impossible to reach all parts of the line conductors. Also, the method is subject to considerable error from antenna currents flowing on the line.

Present-day SWR measurements made by amateurs practically always use some form of *directional coupler* or RF-bridge circuit. The indicator circuits themselves are fundamentally simple, but they require considerable care in construction to ensure accurate measurements. The requirements for indicators used only for the adjustment of impedance-matching circuits, rather than actual SWR measurement, are not so stringent, and you can easily make an instrument for this purpose.

BRIDGE CIRCUITS

Two commonly used bridge circuits are shown in **Fig 3**. The bridges consist essentially of two voltage dividers in parallel, with a voltmeter connected between the junctions of each pair of *arms*, as the individual elements are called. When the equations shown to the right of each circuit are satisfied there is no potential difference between the two junctions, and the voltmeter indicates zero voltage. The bridge is then said to be in *balance*.

Taking Fig 3A as an illustration, if R1 = R2, half the applied voltage, E, will appear across each resistor. Then if $R_S = R_X$, $^1/_2$E will appear across each of these resistors and the voltmeter reading will be zero. Remember that a matched transmission line has essentially a purely resistive input impedance. Suppose that the input terminals of such a line are substituted for R_X. Then if R_S is a resistor equal to the Z_0 of the line, the bridge will be balanced.

If the line is not perfectly matched, its input impedance will not equal Z_0 and hence will not equal R_S, since you chose the latter to be equal to Z_0. There will then be a difference in potential between points X and Y, and the voltmeter will show a reading. Such a bridge therefore can be used to show the presence of standing waves on the line, because the line input impedance will be equal to Z_0 only when there are no standing waves.

Considering the nature of the incident and reflected components of voltage that make up the actual voltage at the input terminals of the line, as discussed in Chapter 24, it should be clear that when $R_S = Z_0$, the bridge is always in balance for the incident component. Thus the voltmeter does not respond to the incident component at any time but reads only the reflected component (assuming that R2 is very small compared with the voltmeter impedance). The incident component can be measured across either R1 or R2, if they are equal resistances. The standing-wave ratio is then



Fig 3—Bridge circuits suitable for SWR measurement. At A, Wheatstone type using resistance arms. At B, capacitance-resistance bridge ("Micromatch"). Conditions for balance are independent of frequency in both types.

$$SWR = \frac{E1+E2}{E1-E2} \qquad \text{(Eq 1)}$$

where E1 is the incident voltage and E2 is the reflected voltage. It is often simpler to normalize the voltages by expressing E2 as a fraction of E1, in which case the formula becomes

$$SWR = \frac{1+k}{1-k} \qquad \text{(Eq 2)}$$

where k = E2/E1.

The operation of the circuit in Fig 3B is essentially the same, although this circuit has arms containing reactance as well as resistance.

It is not necessary that R1 = R2 in Fig 3A; the bridge can be balanced, in theory, with any ratio of these two resistances provided R_S is changed accordingly. In practice, however, the accuracy is highest when the two are equal; this circuit is most commonly used.

A number of types of bridge circuits appear in **Fig 4**, many of which have been used in amateur products or amateur construction projects. All except that at G can have the generator and load at a common potential. At G, the generator and detector are at a common potential. You may interchange the positions of the detector and trans-


R
C1
C2
XMTR
D
Z
R3
R1
R2
XMTR
D
Z
L
R3
R1
R2
C
XMTR
D
Z
L
C
M
R1
R2
XMTR
D
Z
L_P
M
L_S
C1
C2
R
XMTR
D
Z
L_P
M
L_S
C1
C2
R1
R2
XMTR
D
Z
GEN
D
Z
R
GEN
D
Z
Diff. Capacitor
R
ANT0921

De Sauty/Wein (Micromatch)
(A)

Balance $Z=\frac{RC1}{C2}$

Christie/Wheatstone (Antenna – Scope)
(B)

Balance $Z=\frac{R2\ R3}{R1}$

Maxwell (Universal)
(C)

Balance R1 Z=R2 R3=L/C

No Discontinuity: $R2 \rightarrow \infty$, $R3 \rightarrow 0$, R1=Z

Carey – Foster
(Twin – Lamp, Monomatch Mickey – Match)
(D)

Balance M=C R2 Z
L=M(1+R1/R2)

No Discontinuity: $R1 + R2 = Z = \sqrt{L/C}$

Bruene (Collins Radio)
(E)

Balance (Approx.) Z C1 L_S=M R (C1+C2)
($2\pi f L_S >> R$)
(L_P=M Approx)

Max. 1% Error: $2\pi f L_S \geq 7R$

Phase – Compensated
(F)

Balance: Z R1 C1=M=L_P
L_S=R1 R2 (C1+C2)

(G)

(H)

Starr's "Hybrid Coil"

Balance: R=Z
(The Differential Capacitor Can Balance Parallel Reactance.)

Fig 4—Various types of SWR indicator circuits and commonly known names of bridge circuits or devices in that they have been used. Detectors (D) are usually semiconductor diodes with meters, isolated with RF chokes and capacitors. However, the detector may be a radio receiver. In each circuit, Z represents the load being measured. (*This information provided by David Geiser, WA2ANU*)

mitter (or generator) in the bridge, and this may be advantageous in some applications.

The bridges shown at D, E, F and H may have one terminal of the generator, detector and load common. Bridges at A, B, E, F, G and H have constant sensitivity over a wide frequency range. Bridges at B, C, D and H may be designed to show no discontinuity (impedance lump) with a matched line, as shown in the drawing. Discontinuities with A, E and F may be small.

Bridges are usually most sensitive when the detector bridges the midpoint of the generator voltage, as in G or H, or in B when each resistor equals the load impedance. Sensitivity also increases when the currents in each leg are equal.

Resistance Bridge

The basic bridge configuration shown in Fig 3B may be home constructed and is reasonably accurate for SWR measurement. A practical circuit for such a bridge is given in **Fig 5** and a representative layout is shown in **Fig 6**. Properly built, a bridge of this design can be used for measurement of SWRs up to about 15:1 with good accuracy.

You should observe these important construction points:

1) Keep leads in the RF circuit short, to reduce stray inductance.
2) Mount resistors two or three times their body diameter away from metal parts, to reduce stray capacitance.
3) Place the RF components so there is as little inductive and capacitive coupling as possible between the bridge arms.

In the instrument shown in Fig 6, the input and line connectors, J1 and J2, are mounted fairly close together so the standard resistor, R_S, can be supported with short leads directly between the center terminals of the connectors. R2 is mounted at right angles to R_S, and a shield partition is used between these two components and the others.

The two 47-kΩ resistors, R5 and R6 in Fig 5, are voltmeter multipliers for the 0-100 microammeter used as an indicator. This is sufficient resistance to make the voltmeter linear (that is, the meter reading is directly proportional to the RF voltage) and no voltage calibration curve is needed. D1 is the rectifier for the reflected volt-



Fig 5—Resistance bridge for SWR measurement. Capacitors are disc ceramic. Resistors are ½-watt composition except as noted below.
D1, D2—Germanium diode, high back resistance type (1N34A, 1N270, etc).
J1, J2—Coaxial connectors, chassis-mounting type.
M1—0-100 dc microammeter.
R1, R2—47 Ω, ½-W composition (see text).
R3—See text.
R4—50-kΩ volume control.
R_S—Resistance equal to line Z_0 (½ or 1 W composition).
S1—SPDT toggle.



Fig 6—A 2 × 4 × 4-inch aluminum box is used to house this SWR bridge, which uses the circuit of Fig 5. The variable resistor, R4, is mounted on the side. The bridge components are mounted on one side plate of the box and a subchassis formed from a piece of aluminum. The input connector is at the top in this view. R_S is connected directly between the two center posts of the connectors. R2 is visible behind it and perpendicular to it. One terminal of D1 projects through a hole in the chassis so the lead can be connected to J2. R1 is mounted vertically to the left of the chassis in this view, with D2 connected between the junction of R1-R2 and a tie point.

age and D2 is for the incident voltage. Because of manufacturing variations in resistors and diodes, the readings may differ slightly with two multipliers of the same nominal resistance value, so a correction resistor, R3, is included in the circuit. You should select its value so that the meter reading is the same with S1 in either position, when RF is applied to the bridge with the line connection open. In the instrument shown, a value of 1000 Ω was required in series with the multiplier for reflected voltage; in other cases different values probably would be needed and R3 might have to be put in series with the multiplier for the incident voltage. You can determine this by experiment.

The value used for R1 and R2 is not critical, but you should match the two resistors within 1% or 2% if possible. Keep the resistance of R_S as close as possible to the actual Z_0 of the line you use (generally 50 or 75 Ω). Select the resistor by actual measurement with an accurate resistance bridge, if you have one available.

R4 is for adjusting the incident-voltage reading to full scale in the measurement procedure described below. Its use is not essential, but it offers a convenient alternative to exact adjustment of the RF input voltage.

Testing

Measure R1, R2 and R_S with a reliable digital ohmmeter or resistance bridge after completing the wiring. This will ensure that their values have not changed from the heat of soldering. Disconnect one side of the microammeter and leave the input and output terminals of the unit open during such measurements to avoid stray shunt paths through the rectifiers.

Check the two voltmeter circuits as described above, applying enough RF (about 10 V) to the input terminals to give a full-scale reading with the line terminals open. If necessary, try different values for R3 until the reading is the same with S1 in either position.

With J2 open, adjust the RF input voltage and R4 for full-scale reading with S1 in the incident-voltage position. Then switch S1 to the reflected-voltage position. The reading should remain at full scale. Next, short-circuit J2 by touching a screwdriver between the center terminal and the frame of the connector to make a low-inductance short. Switch S1 to the incident-voltage position and readjust R4 for full scale, if necessary. Then throw S1 to the reflected-voltage position, keeping J2 shorted, and the reading should be full scale as before. If the readings differ, R1 and R2 are not the same value, or there is stray coupling between the arms of the bridge. You must read the reflected voltage at full scale with J2 either open or shorted, when the incident voltage is set to full scale in each case, to make accurate SWR measurements.

The circuit should pass these tests at all frequencies at which it is to be used. It is sufficient to test at the lowest and highest frequencies, usually 1.8 or 3.5 and 28 or 50 MHz. If R1 and R2 are poorly matched but the bridge construction is otherwise good, discrepancies in the readings will be substantially the same at all frequencies. A difference in behavior at the low and high ends of the frequency range can be attributed to stray coupling between bridge arms, or stray inductance or capacitance in the arms.

To check the bridge for balance, apply RF and adjust R4 for full scale with J2 open. Then connect a resistor identical with R_S (the resistance should match within 1% or 2%) to the line terminals, using the shortest possible leads. It is convenient to mount the test resistor inside a cable connector (PL-259), a method of mounting that also minimizes lead inductance. When you connect the test resistor the reflected-voltage reading should drop to zero. The incident voltage should be reset to full scale by means of R4, if necessary. The reflected reading should be zero at any frequency in the range to be used. If a good null is obtained at low frequencies but some residual current shows at the high end, the trouble may be the inductance of the test resistor leads, although it may also be caused by stray coupling between the arms of the bridge itself.

If there is a constant low (but not zero) reading at all frequencies the problem is poor matching of the resistance values. Both effects can be present simultaneously. You should make sure you obtain a good null at all frequencies before using your bridge.

Bridge Operation

You must limit the RF power input to a bridge of this type to a few watts at most, because of the power-dissipation ratings of the resistors. If the transmitter has no provision for reducing power output to a very low value—less than 5 W—a simple power-absorber circuit can be made up, as shown in **Fig 7**. Lamp DS1 tends to maintain constant current through the resistor over a fairly



Fig 7—Power-absorber circuit for use with resistance-type SWR bridges when the transmitter has no special provisions for power reduction. For RF powers up to 50 W, DS1 is a 117-V 40-W incandescent lamp and DS2 is not used. For higher powers, use sufficient additional lamp capacity at DS2 to load the transmitter to about normal output; for example, for 250 W output DS2 may consist of two 100-W lamps in parallel. R1 is made from three 1-W 68-Ω resistors connected in parallel. P1 and P2 are cable-mounting coaxial connectors. Leads in the circuit formed by the lamps and R1 should be kept short, but convenient lengths of cable may be used between this assembly and the connectors.

wide power range, so the voltage drop across the resistor also tends to be constant. This voltage is applied to the bridge, and with the constants given is in the right range for resistance-type bridges.

To make a measurement, connect the unknown load to J2 and apply sufficient RF voltage to J1 to give a full-scale incident-voltage reading. Use R4 to set the indicator to exactly full scale. Then throw S1 to the reflected voltage position and note the meter reading. The SWR is then found by using these readings in Eq 1.

For example, if the full-scale calibration of the dc instrument is 100 µA and the reading with S2 in the reflected-voltage position is 40 µA, the SWR is

$$\text{SWR} = \frac{100+40}{100-40} = \frac{140}{60} = 2.33:1$$

Instead of calculating the SWR value, you could use the voltage curve in **Fig 8**. In this example the ratio of reflected to forward voltage is 40/100 = 0.4, and from Fig 8 the SWR value is about 2.3:1.

You may calibrate the meter scale in any arbitrary units, so long as the scale has equal divisions. It is the ratios of the voltages, and not the actual values, that determine the SWR.



Fig 8—Chart for finding voltage standing-wave ratio when the ratio of reflected-to-forward voltage or reflected-to-forward power is known.

AVOIDING ERRORS IN SWR MEASUREMENTS

The principal causes of inaccuracies within the bridge are differences in the resistances of R1 and R2, stray inductance and capacitance in the bridge arms, and stray coupling between arms. If the checkout procedure described above is followed carefully, the bridge in Fig 5 should be amply accurate for practical use. The accuracy is highest for low standing-wave ratios because of the nature of the SWR calculation; at high ratios the divisor in the equation above represents the difference between two nearly equal quantities, so a small error in voltage measurement may mean a considerable difference in the calculated SWR.

The standard resistor R_S must equal the actual Z_0 of the line. The actual Z_0 of a sample of line may differ by a few percent from the nominal figure because of manufacturing variations, but this has to be tolerated. In the 50- to 75-Ω range, the RF resistance of a composition resistor of $^1/_2$- or 1-W rating is essentially identical with its dc resistance.

Common-Mode Currents

As explained in Chapter 26, there are two ways in which unwanted *common-mode* (sometimes called *antenna*) currents can flow on the outside of a coaxial line—currents radiated onto the line because of its spatial relationship to the antenna and currents that result from the direct connection between the coax outer conductor and (usually) one side of the antenna. The radiated current usually will not be troublesome if the bridge and the transmitter (or other source of RF power for operating the bridge) are shielded so that any RF currents flowing on the outside of the line cannot find their way into the bridge. This point can be checked by inserting an additional section of line ($^1/_8$ to $^1/_4$ electrical wavelength preferably) of the same Z_0. The SWR indicated by the bridge should not change except for a slight decrease because of the additional line loss. If there is a marked change, you may need better shielding.

Parallel-type currents caused by the connection to the antenna without using a common-mode choke balun will change the SWR with variations in line length, even though the bridge and transmitter are well-shielded and the shielding is maintained throughout the system by the use of coaxial fittings. Often, merely moving the transmission line around will cause the indicated SWR to change. This is because the outside of the coax becomes part of the antenna system—being connected to the antenna at the feed point. The outside shield of the line thus constitutes a load, along with the desired load represented by the antenna itself. The SWR on the line then is determined by the composite load of the antenna and the outside of the coax. Since changing the line length (or position) changes one component of this composite load, the SWR changes too.

The remedy for such a situation is to use a good balun or to detune the outside of the line by proper choice of length. Note that this is not a *measurement error*, since what the instrument reads is the actual SWR on the line. However, it is an undesirable condition since the line is usually operating at a higher SWR than it should—and would if the parallel-type current on the outside of the coax were eliminated.

Spurious Frequencies

Off-frequency components in the RF voltage applied to the bridge may cause considerable error. The principal components of this type are harmonics and low-frequency subharmonics that may be fed through the final stage of the transmitter driving the bridge. The antenna is almost always a fairly selective circuit, and even though the system may be operating with a very low SWR at the desired frequency, it is almost always mismatched at harmonic and subharmonic frequencies. If such spurious frequencies are applied to the bridge in appreciable amplitude, the SWR indication will be very much in error. In particular, it may not be possible to obtain a null on the bridge with any set of adjustments of the matching circuit. The only remedy is to filter out the unwanted components by increasing the selectivity of the circuits between the transmitter final amplifier and the bridge.



Fig 9—Methods of determining $^1/_4$ and $^1/_2$-λ line lengths. At A, $^1/_4$-λ open-circuited line; at B, $^1/_4$-λ shorted and $^1/_2$-λ open-circuited line.

MEASURING LINE LENGTH

The following material is taken from information in September 1985 *QST* by Charlie Michaels, W7XC (see Bibliography).

There is a popular myth that one may prepare an open quarter-wave line by connecting a loop of wire to one end and trimming the line to resonance (as indicated by a dip meter). This actually yields a line with capacitive reactance equal to the inductive reactance of the loop: a 4-inch wire loop yields a line 82.8º line at 18 MHz; a 2-inch loop yields an 86º line. As the loop size is reduced, line length approaches—but never equals—90º.

To make a quarter-wave open line, parallel connect a coil and capacitor that resonate at the required frequency (see **Fig 9A**). After adjusting the network to resonance, do not make further network adjustments. Open the connection between the coil and capacitor and series connect the line to the pair. Start with a line somewhat longer than required, and trim it until the circuit again resonates at the desired frequency. For a shorted quarter-wave line or an open half-wave line, connect the line in parallel with the coil and capacitor (see Fig 9B).

Another method to accurately measure a coaxial transmission line length uses one of the popular "SWR analyzers," portable hand-held instruments with a tunable low-power signal generator and an SWR bridge. While an SWR analyzer cannot compute the very high values of SWR at the input of a shorted quarter-wave line at the fundamental frequency, most include another readout showing the magnitude of the impedance. This is very handy for finding a low-impedance dip, rather than a high-impedance peak.

At the operating frequency, a shorted quarter-wave line results in a high-impedance open-circuit at the input to that line. At twice the frequency, where the line is now one-half wave long electrically, the instrument shows a low-impedance short-circuit. However, when you are pruning a line to length by cutting off short pieces at the end, it is inconvenient to have to install a short before measuring the response. It is far easier to look for the dip in impedance when a quarter-wave line is terminated in an open circuit.

Again, the strategy is to start with a line physically a little longer than a quarter-wave length. A good rule of thumb is to cut the line 5% longer to take into account the variability in the velocity factor of a typical coax cable. Compute this using:

$$\text{Length (feet)} = 0.25 \times 1.05 \times \text{VF} \times 984/\text{Freq} = \text{VF}/\text{Freq}$$

where

Freq is in MHz

VF is the velocity factor in %.

Plug the coax connector installed at one end of the line into the SWR analyzer and find the frequency for the impedance dip. Prune the line by snipping off short pieces at the end. Once you've pruned the line to the desired frequency, connect the short at the end of the line and recheck for a short circuit at twice the fundamental frequency. Seal the shorted end of the coax and you're done.

REFLECTOMETERS

Low-cost *reflectometers* that do not have a guaranteed wattmeter calibration are not ordinarily reliable for accurate numerical measurement of standing-wave ratio. They are, however, very useful as aids in the adjustment of matching networks, since the objective in such adjustment is to reduce the reflected voltage or power to zero. Relatively inexpensive devices can be used for this, since only good bridge balance is required, not actual calibration of SWR. Bridges of this type are usually frequency-sensitive that is, the meter response increase with increasing frequency for the same applied voltage. When matching and line monitoring, rather than SWR measurement, is the principal use of the device, this is not a serious handicap.

Various simple reflectometers, useful for matching and monitoring, have been described from time to time in *QST* and in *The ARRL Handbook*. Because most of these are frequency sensitive, it is difficult to calibrate them accurately for power measurement, but their low cost and suitability for use at moderate power levels, combined with the ability to show accurately when a matching circuit has been properly adjusted, make them a worthwhile addition to the amateur station.

The Tandem Match—An Accurate Directional Wattmeter

Most SWR meters are not very accurate at low power levels because the detector diodes do not respond to low voltage in a linear fashion. This design uses a compensating circuit to cancel diode nonlinearity. It also provides peak detection for SSB operation and direct SWR readout that does not vary with power level. The following information is condensed from an article by John Grebenkemper, KI6WX, in January 1987 *QST*.

DESIGN PRINCIPLES

Directional wattmeters for Amateur Radio use consist of three basic elements: a directional coupler, a detector and a signal-processing and display circuit. A directional coupler samples forward and reflected-power components on a transmission line. An ideal directional coupler would provide signals proportional to the forward and reflected voltages (independent of frequency), which could then be used to measure forward and reflected power over a wide frequency range. The best contemporary designs work over two decades of frequency.

The detector circuit provides a dc output voltage proportional to the ac input voltage. Most directional wattmeters use a single germanium diode as the detector element. A germanium, rather than silicon, diode is used to minimize diode nonlinearity at low power levels. Diode non-linearity still causes SWR measurement errors unless it is compensated ahead of the display circuit. Most directional wattmeters do not work well at low power levels because of diode nonlinearity.

Table 1
Performance Specifications for the Tandem Match

Power range: 1.5 to 1500 W
Frequency range: 1.8 to 54 MHz
Power accuracy: Better than ± 10% (± 0.4 dB)
SWR accuracy: Better than ± 5%
Minimum SWR: Less than 1.05:1
Power display: Linear, suitable for use with either analog or digital meters
Calibration: Requires only an accurate voltmeter

The signal-processing and display circuits compute and display the SWR. There are a number of ways to perform this function. Meters that display only the forward and reflected power require the operator to compute the SWR manually. Many instruments require that the operator adjust the meter to a reference level while measuring forward power, then switch to measure reflected power on a special scale that indicates SWR. Meters that directly compute the SWR using analog signal-processing circuits have been described by Fayman, Perras,



Fig 10—The Tandem Match uses a pair of meters to display net forward power and true SWR simultaneously.



Fig 11—Block diagram of the Tandem Match.

Leenerts and Bailey (see the Bibliography at the end of this chapter).

The next section takes a brief look at several popular circuits that accomplish the functions above and compares them to the circuits used in the Tandem Match. The design specifications of the Tandem Match are shown in **Table l**, and a block diagram is shown in **Fig 11**.

CIRCUIT DESCRIPTION

A directional coupler consists of an input port, an output port and a coupled port. The device takes a portion of the power flowing from the input port to the output port and directs it to the coupled port, but *none* of the power flowing from the output port to the input port is directed to the coupled port.

There are several terms that define the performance of a directional coupler:

1) *Insertion loss* is the amount of power that is lost as the signal flows from the input port to the output port. Insertion loss should be minimized so the coupler doesn't dissipate a significant amount of the transmitted power.

2) *Coupling factor* is the amount of power (or voltage) that appears at the coupled port relative to the amount of power (or voltage) transferred from the input port to the output port. The "flatness" (with frequency) of the coupling factor determines how accurately the directional wattmeter can determine forward and reflected power over a range of frequencies.

3) *Isolation* is the amount of power (or voltage) that appears at the coupled port relative to the amount of power (or voltage) transferred from the output port to the input port.

4) *Directivity* is the isolation less the coupling factor. Directivity dictates the minimum measurable SWR. A directional coupler with 20 dB of directivity measures a 1:1 SWR as l.22:l, but one with 30 dB measures a 1:1 SWR as 1.07:1.

The directional coupler most commonly used in amateur radio was first described in 1959 by Bruene in *QST* (see Bibliography). The coupling factor was fairly flat (± l dB), and the directivity was about 20 dB for a Bruene coupler measured from 3 to 30 MHz. Both factors limit the accuracy of the Bruene coupler for measuring low values of power and SWR. It is a simple directional coupler, however, and it works well over a wide frequency range if great precision is not required.

The coupler used in the Tandem Match (see **Fig 12**) consists of a pair of toroidal transformers connected in tandem. The configuration was patented by Carl G. Sontheimer and Raymond E. Fredrick (US Patent no. 3,426,298, issued February 4, 1969). It has been described by Perras, Spaulding (see Bibliography) and others. With coupling factors of 20 dB or greater, this coupler is suitable for sampling both forward and reflected power.

The configuration used in the Tandem Match works well over the frequency range of 1.8 to 54 MHz, with a


Transmitter
$I_f - I_r$
$V_f + V_r$
Antenna
1 : N
1 : N
V2
R
R
V1
(A)
+
V
V2
R
$\frac{I_f - I_r}{N}$
$\frac{V_f + V_r}{N}$
R
V1
ANT0927
(B)

Fig 12—Simplified diagram of the Tandem Match directional coupler. At A, a schematic of the two transformers. At B, an equivalent circuit.

nominal coupling factor of 30 dB. Over this range, insertion loss is less than 0.1 dB. The coupling factor is flat to within ± 0.1 dB from 1.8 to 30 MHz, and increases to only ±0.3 dB at 50 MHz. Directivity exceeds 35 dB from 1.8 to 30 MHz and exceeds 26 dB at 50 MHz.

The low-frequency limit of this directional coupler is determined by the inductance of the transformer secondary windings. The inductive reactance should be greater than 150 Ω (three times the line characteristic impedance) to reduce insertion loss. The high-frequency limit of this directional coupler is determined by the length of the transformer windings. When the winding length approaches a significant fraction of a wavelength, coupler performance deteriorates.


1 kΩ
V_O
50 Ω
R1
C1
0.001 μ F
D2
R2
ANT0928

Fig 13—Simplified diagram of the detector circuit used in the Tandem Match. The output voltage, V_O is approximately equal to the input voltage. D1 and D2 must be a matched pair (see text). The op amp should have a low offset voltage (less than 1 mV), a low leakage current (less than 1 nA), and be stable over time and temperature. The resistor and capacitor in the feedback path assure that the op amp will be stable.

The coupler described here may overheat at 1500 W on 160 meters (because of the high circulating current in the secondary of T2). The problem could be corrected by using a larger core or one with greater permeability. A larger core would require longer windings; that option would decrease the high-frequency limit.


0.001 μ F
100 kΩ
2.2 kΩ
LOGARITHM CIRCUIT
(A)
100 kΩ
ANTILOGARITHM CIRCUIT
(B)
ANT0929

Fig 14—Simplified diagrams of the log circuit at A and the antilog circuit at B.


ANT0930
W1
Vs+
V+
0.1
15 k
+2.5 V
0.1
1M
10 µF
25 V
Q2
2N2907
Q1
2N2222
470 k
10 k
Q3
2N2222
FB
9V
9V
FB
U9
LM336
1
3
1
U10
LM336
3
0.1
-2.5 V
W2
W3
Vs-
5.6 k
V-
0.1
1N34A
D6
10 k
0.001
0.001
47 k
2.2 k
TP7
TP8
18 V
1W
D5
1N34A
D7
10 k
0.001
0.001
0.01
+15 V
0.01
J1
FORWARD
D1
1N5711
50 *
100
0.001
0.22
1 M
1 M
470
3
4
U1A
2
11
1
1 k
0.01
D2
1N5711
100 k
1 %
TP1
100 k
1 %
100 k
100 k
1 k
470 k
470
12
U1D
13
14
100 k
1 %
SEE TABLE2 FOR RESISTOR VALUES
0.01
-2.5 V
TP2
CW
-2.5 V
+2.5 V
R1 100 k
FORWARD DETECTOR ZERO
S1A
RANGE
NOTE: CHASSIS AND CIRCUIT GROUNDS SEPARATED
FB
FB
1 mH
FB
FB
CHASSIS
CIRCUIT
J2
REFLECTED
D3
1N5711
50 *
100
0.001
0.1
1 M
1 M
470
5
U1B
6
7
1 k
0.01
D4
1N5711
100 k
1 %
TP4
100 k
1 %
100 k
100 k
1 k
470 k
470
10
U1C
9
8
100 k
1 %
SEE TABLE2 FOR RESISTOR VALUES
TP5
CW
-2.5 V
+2.5 V
R2 100 k
REFLECTED DETECTOR ZERO
S1B
RANGE
Chassis Ground Plane
Circuit Ground Plane

Fig 15—Schematic diagram for the Tandem Match directional wattmeter. Parts identified as RS are from RadioShack. For other parts sources, see Table 3. See Fig 17 for construction of 50-Ω loads at J1 and J2.

D1, D2—Matched pair 1N5711, or equivalent.
D3, D4—Matched pair 1N5711, or equivalent.
D6, D7—1N34A.
D8-D14—1N914.
FB—Ferrite bead, Amidon FB-73-101 or equiv.
J1, J2—SO-239 connector.
J3, J4—Open-circuit jack.
M1, M2—50 µA panel meter, RS 270-1751.
Q1, Q3, Q4—2N2222 or equiv.
Q2—2N2907 or equiv.


ANT0930
0.01
-2.5 V
R3
10 k
FOWARD
GAIN
ADJUST
cw
15 k
CA3146
13
U5
V+
0.01
100 k
U2A
TLC27L4
1N914
D9
0.001
2.2 k
-V
100 k
U2D
1M
U4B
1 k
D14
1N914
0.001
1 M
100 k
M1
OUTPUT
POWER
0-50
TP9
J3
OUTPUT
POWER
-2.5 V
330 k
TP3
R4
10 k
REFLECTED
GAIN
ADJUST
U6
U2B
1N914
D8
U2C
220 µ F
16 V
S2A
OPERATE
TUNE
SWR × 10
S2
MODE
S2B
M2
SWR
0-50
+2.5 V
SWR
GAIN
ADJUST
R5
100 k
200 k
U3A
2.2 k
U7
11 k
U3C
D13
1N914
TP10
100 k 1%
U3B
1N914
D12
TP6
J4
SWR
Q4
2N2222
D10
1N914
D11
1N914
U3D
2.2 k
U4A
TLC27L2
LM334, LM336
2 1 3

Except as indicated, decimal values of capacitance are in microfarads (µ F); others are in picofarads (pF); resistances are in ohms; k= 1,000 , M= 1,000,000

* 4 - 200 Ω , 2%, 1/2 W NONINDUCTIVE RESISTORS MOUNTED ON REAR OF SO-239

R1, R2, R5—100 kΩ, 10-turn, cermet Trimpot.
R3, R4—10 kΩ, 10-turn, cermet Trimpot.
U1-U3—TLC27L4 or TLC27M4 quad op amp (Texas Instruments).
U4—TLC27L2 or TLC27M2 dual op amp.
U5-U7—CA3146 quad transistor array.
U8—LM334 adjustable current source.
U9-U10—LM336 2.5-V reference diode. See text.

Detector Circuits

Most amateur directional wattmeters use a germanium diode detector to minimize the forward voltage drop. Detector voltage drop is still significant, however, and an uncompensated diode detector does not respond to small signals in a linear fashion. Many directional wattmeters compensate for diode nonlinearity by adjusting the meter scale.

The effect of underestimating detected power worsens at low power levels. Under these conditions, the ratio of the forward power to the reflected power is overestimated because the reflected power is always less than the forward power. This results in an instrument that underestimates SWR, particularly as power is reduced. A directional wattmeter can be checked for this effect by measuring SWR at several power levels: the SWR should be independent of power level.

The Tandem Match uses a feedback circuit to compensate for diode nonlinearity. A simplified diagram of the compensated detector is shown in **Fig 13**. When used with the 30-dB directional coupler, the output voltage of this circuit tracks the square root of power over a range from 10 mW to 1.5 kW. The compensated diode detector tracks the peak input voltage down to 30 mV, while an uncompensated germanium-diode detector shows significant errors at peak inputs of 1 V and less. More information about compensated detectors appears in Grebenkemper's *QEX* article, "Calibrating Diode Detectors" (see Bibliography).

The compensation circuit uses the voltage across a feedback diode, D2, to compensate for the voltage drop across the detector diode, D1. (The diodes must be a matched pair.) The average current through D1 is determined by the detector diode load resistor, R1. The peak current through this diode is several times larger than the average current; therefore, the current through D2 must be several times larger than the average current through D1 to compensate adequately for the peal voltage drop across D1. This is accomplished by making the feedback-diode load resistor, R2, several times smaller than R1. The voltage at the output of the compensated detector approximates the peak RF voltage at the input. For Schottky barrier diodes and a 1 MΩ detector-diode load resistor, a 5:1 ratio of R1 to R2 is nearly optimal.

Signal-Processing and Display Circuits

The signal-processing circuitry calculates and displays transmission-line power and SWR. When measuring forward power, most directional wattmeters display the actual forward power present in the transmission line, which is the sum of forward and reflected power if a match exists at the input end of the line. Transmission-line forward power is very close to the net forward power (the actual power delivered to the line) so long as the SWR is low. As the SWR increases, however, forward power becomes an increasingly poor measure of the power delivered to the load. At an SWR of 3:1, a forward power reading of 100 W implies that only 75 W is delivered to the load (the reflected power is 25 W), assuming the transmission-line loss is zero.

The Tandem Match differs from most wattmeters in that *it displays the net forward power, rather than the sum of forward and reflected power.* This is the quantity that must be optimized to result in maximum radiated power (and which concerns the FCC).

The Tandem Match directly computes and displays the transmission-line SWR on a linear scale. As the displayed SWR is not affected by changes in transmitter power, a matching network can be simply adjusted to minimize SWR. Transmatch adjustment requires only a few watts.

The heart of the Tandem Match signal-processing circuit is the analog logarithm and antilogarithm circuitry shown in **Fig 14**. The circuit is based on the fact that collector current in a silicon transistor is proportional to the exponential (antilog) of its base-emitter voltage over a range of collector currents from a few nanoamperes to a few milliamperes when the collector-base voltage is zero (see Gibbons and Horn reference in the Bibliography). Variations of this circuit are used in the squaring circuits to convert voltage to power and in the divider circuit used to compute the SWR. With good op amps, this circuit will work well for input voltages from less than 100 mV to greater than 10 V.

(For the Tandem Match, "good" op amps are quad-packaged, low-power-consumption, unity-gain-stable parts with input bias less than 1 nA and offset voltage less than 5 mV. Op amps that consume more power than those shown may require changes to the power supply.)

CONSTRUCTION

The schematic diagram for the Tandem Match is shown in **Fig 15** (see pages 14 and 15). The circuit is designed to operate from batteries and draw very little power. Much of the circuitry is of high impedance, so take care to isolate it from RF fields. House it in a metal case. Most problems in the prototype were caused by stray RF in the op-amp circuitry.

Directional Coupler

The directional coupler is constructed in its own small ($2^3/_4 \times 2^3/_4 \times 2^1/_4$-inch) aluminum box (see **Fig 16**). Two pairs of S0-239 connectors are mounted on opposite sides of the box. A piece of PC board is run diagonally across the box to improve coupler directivity. The pieces of RG-8X coaxial cable pass through holes in the PC board.

(Note: Some brands of "mini 8" cable have extremely low breakdown voltage ratings and are unsuitable to carry even 100 W when the SWR exceeds 1:1. See the subsequent section, "High-Power Operation," for details of a coupler made with RG-8 cable.)

Begin by constructing T1 and T2, which are identi-



Fig 16—Construction details for the directional coupler.



Fig 17—The parallel load resistors mounted on an SO-239 connector. Four 200-Ω, 2%, $^{1}/_{2}$-W resistors are mounted in parallel to provide a 50-Ω detector load.

cal except for their end connections. Refer to Fig 16. The primary for each transformer is the center conductor of a length of RG-8X coaxial cable. Cut two cable lengths sufficient for mounting as shown in the figure. Strip the cable jacket, braid and dielectric as shown. The cable braid is used as a Faraday shield between the transformer windings, so it is only grounded at one end. *Important—connect the braid only at one end or the directional-coupler circuit will not work properly!* Wind two transformer secondaries, each 31 turns of #24 enameled wire on an Amidon T50-3 or equivalent powdered-iron core.

Slip each core over one of the prepared cable pieces (including both the shield and the outer insulation). Mount and connect the transformers as shown in Fig 16, with the wire running through separate holes in the copper-clad PC board. The directional coupler can be mounted separately from the rest of the circuitry if desired. If so, use two coaxial cables to carry the forward and reflected-power signals from the directional coupler to the detector inputs. Be aware, however that any losses in the cables will affect power readings.



Fig 18—Diode matching test setup.

This directional coupler has not been used at power levels in excess of 100 W. For more information about using the Tandem Match at high power levels, see the section, “High-Power Operation.”

Detector and Signal-Processing Circuits

The detector and signal-processing circuits were constructed on a perforated, copper-clad circuit board. These circuits use two separate grounds—*it is extremely important that the grounds be isolated as shown in the circuit diagram.* Failure to do so may result in faulty circuit operation. Separate grounds prevent RF currents on the cable braid from affecting the op-amp circuitry.

The directional coupler requires good 50-Ω loads. They are constructed on the back of female UHF chassis connectors where the cables from the directional coupler enter the wattmeter housing. Each load consists of four 200-Ω resistors connected from the center conductor of the UHF connector to the four holes on the mounting flange, as shown in **Fig 17**. The detector diode is then run from the center conductor of the connector to the 100-pF and 1000-pF bypass capacitors, which are mounted next to the connector. The response of this load and detector combination measures flat to beyond 500 MHz.

Schottky-barrier diodes (type 1N5711) were used in this design because they were readily available. Any RF-detector diode with a low forward voltage drop (less than 300 mV) and reverse break-down voltage greater than 30 V could be used. (Germanium diodes could be used in this circuit, but performance will suffer. If germanium diodes are used, reduce the resistance values for the detector-diode and feedback-diode load resistors by a factor of 10.)

The detector diodes must be matched. This can be done with dc, using the circuit shown in **Fig 18**. Use a high-impedance voltmeter (10 MΩ or greater). For this project, diodes are matched when their forward voltage drops are equal (within a few millivolts). Diodes from the same batch will probably be sufficiently matched.

Table 2
Range-Switch Resistor Values

Full-Scale Power Level (W)	*Range Resistor (1% Precision) (kΩ)*
1	2.32
2	3.24
3	4.02
5	5.23
10	7.68
15	9.53
20	11.0
25	12.7
30	14.0
50	18.7
100	28.7
150	37.4
200	46.4
250	54 9
300	63.4
500	100.0
1000	237.0
1500	649.0
2000	Open

The rest of the circuit layout is not critical, but keep the lead lengths of the 0.001 and 0.01-pF bypass capacitors short. The capacitors provide additional bypassing for the op-amp circuitry. D6 and D7 form a voltage doubler to detect the presence of a carrier. When the forward power exceeds 1.5 W, Q3 switches on and stays on until about 10 seconds after the carrier drops. (A connection from TP7 to TP9 forces the unit on, even with no carrier present.) The regulated references of +2.5 V and –2.5 V generated by the LM334 and two LM336s are critical. Zener-diode substitutes would significantly degrade performance.

The four op amps in U1 compensate for the nonlinearity of the detector diodes. D1-D2 and D3-D4 are the matched diode pairs discussed above. A RANGE switch selects the meter range. (A six-position switch was used here because it was handy.) The resistor values for the RANGE switch are shown in **Table 2**. Full-scale input power gives an output at U1C or U1D of 7.07 V. The forward and reflected-power detectors are zeroed with R1 and R2.

The forward and reflected-detector voltages are squared by U2, U5 and U6 so that the output voltages are proportional to forward and reflected power. The gain constants are adjusted using R3 and R4 so that an input of 7.07 V to the squaring circuit gives an output of 5 V. The difference between these two voltages is used by U4B to yield an output that is proportional to the power delivered to the transmission line. This voltage is peak detected (by an RC circuit connected to the OPERATE position of the MODE switch) to hold and indicate the maximum power during CW or SSB transmissions. SWR is computed from the forward and reflected voltages by U3, U4 and U7. When no carrier is present, Q4 forces the SWR reading to be zero (that is, when the forward power is less than 2% of the full-scale setting of the RANGE switch). The SWR computation circuit gain is adjusted by R5. The output is peak detected in the OPERATE mode to steady the SWR reading during CW or SSB transmissions.

Transistor arrays (U5, U6 and U7) are used for the log and antilog circuits to guarantee that the transistors will be well matched. Discrete transistors may be used, but accuracy may suffer. A three-position toggle switch selects the three operating modes. In the OPERATE mode, the power and SWR outputs are peak detected and held for a few seconds to allow meter reading during actual transmissions. In the TUNE mode, the meters display instantaneous output power and SWR.

A digital voltmeter is used to obtain more precise readings than are possible with analog meters. The output power range is 0 to 5 V (0 V = 0 W and 5 V = full scale). SWR output varies from 1 V (SWR = 1:1) to 5 V (SWR = 5:1). Voltages above 5 V are unreliable because of voltage limiting in some of the op amp circuits.

Calibration

The directional wattmeter can be calibrated with an accurate voltmeter. All calibration is done with dc voltages. The directional-coupler and detector circuits are inherently accurate if correctly built. To calibrate the wattmeter, use the following procedure:

1) Set the MODE switch to TUNE and the RANGE switch to 100 W or less.
2) Jumper TP7 to TP8. This turns the unit on.
3) Jumper TP1 to TP2. Adjust R1 for 0 V at TP3.
4) Jumper TP4 to TP5. Adjust R2 for 0 V at TP6.
5) Adjust R1 for 7.07 V at TP3.
6) Adjust R3 for 5.00 V at TP9, or a full-scale reading on M1.
7) Adjust R2 for 7.07 V at TP6.
8) Adjust R4 for 0 V at TP9, or a zero reading on M1.
9) Adjust R2 for 4.71 V at TP6.
10) Adjust R5 for 5.00 V at TP10, or a full-scale reading on M2.
11) Set the RANGE switch to its most sensitive scale.
12) Remove the jumpers from TP1 to TP2 and TP4 to TP5.
13) Adjust R1 for 0 V at TP3.
14) Adjust R2 for 0 V at TP6.
15) Remove the jumper from TP7 to TP8.

This completes the calibration procedure. This procedure has been found to equal calibration with expensive laboratory equipment. The directional wattmeter should now be ready for use.

ACCURACY

Performance of the Tandem Match has been compared to other well-known directional couplers and laboratory test equipment, and it equals any amateur directional wattmeter tested. Power measurement accuracy compares well to a Hewlett-Packard HP-436A power meter. The HP meter has a specified measurement error of less than ± 0.05 dB. The Tandem Match tracked the HP436A within +0.5 dB from 10 mW to 100 W, and within ± 0.1 dB from 1 W to 100 W. The unit was not tested above 100 W because a transmitter with a higher power rating was not available.

SWR performance was equally good when compared to the SWR calculated from measurements made with the HP436A and a calibrated directional coupler. The Tandem Match tracked the calculated SWR within ± 5% for SWR values from 1:1 to 5:1. SWR measurements were made at 8 W and 100 W.

OPERATION

Connect the Tandem Match in the 50-Ω line between the transmitter and the antenna matching network (or antenna if no matching network is used). Set the RANGE switch to a range greater than the transmitter output rating and the MODE switch to TUNE. When the transmitter is keyed, the Tandem Match automatically switches on and indicates both power delivered to the antenna and SWR on the transmission line. When no carrier is present, the OUTPUT POWER and SWR meters indicate zero.

The OPERATE mode includes RC circuitry to momentarily hold the peak-power and SWR readings during CW or SSB transmissions. The peak detectors are not ideal, so there could be about 10% variation from the actual power peaks and the SWR reading. The SWR ×10 mode increases the maximum readable SWR to 50:1. This range should be sufficient to cover any SWR value that occurs in amateur use. (A 50-foot open stub of RG-8 yields a measured SWR of only 43:1, or less, at 2.4 MHz because of cable loss. Higher frequencies and longer cables exhibit a lesser maximum SWR.)

It is easy to use the Tandem Match to adjust an antenna matching network: Adjust the transmitter for minimum output power (at least 1.5 W). With the carrier on and the MODE switch set to TUNE or SWR ×10, adjust the matching network for minimum SWR. Once the minimum SWR is obtained, set the transmitter to the proper operating mode and output power. Place the Tandem Match in the OPERATE mode.

DESIGN VARIATIONS

There are several ways in which this design could be enhanced. The most important is to add UHF capability. This would require a new directional-coupler design for the band of interest. (The existing detector circuit should work to at least 500 MHz.)

Those who desire a low-power directional wattmeter can build a directional coupler with a 20-dB coupling factor by decreasing the transformer turns ratio to 10:1. That version should be capable of measuring output power from 1 mW to about 150 W (and it should switch on at about 150 mW).

This change should also increase the maximum operating frequency to about 150 MHz (by virtue of the shorter transformer windings). If you desire 1.8-MHz operation, it may be necessary to change the toroidal core material for sufficient reactance (low insertion loss).

The Tandem Match circuit can accommodate coaxial cable with a characteristic impedance other than 50 Ω. The detector terminating resistors, transformer secondaries and range resistors must change to match the new design impedance.

The detector circuitry can be used (without the directional coupler) to measure low-level RF power in 50-Ω circuits. RF is fed directly to the forward detector (J1, Fig 15), and power is read from the output power meter. The detector is quite linear from 10 µW to 1.5 W.

HIGH-POWER OPERATION

This material was condensed from information by Frank Van Zant, KL7IBA, in July 1989 *QST.* In April 1988, Zack Lau, W1VT, described a directional-coupler circuit (based on the same principle as Grebenkemper's circuit) for a QRP transceiver (see the Bibliography at the end of this chapter). The main advantage of Lau's circuit is a very low parts count.

Grebenkemper used complex log-antilog amplifiers to provide good measurement accuracy. This application gets away from complex circuitry, but retains reasonable measurement accuracy over the 1 to 1500-W range. It also forfeits the SWR-computation feature. Lau's coupler uses ferrite toroids. It works well at low power levels, but the ferrite toroids heat excessively with high power, causing erratic meter readings and the potential for burned parts.

The Revised Design

Powdered-iron toroids are used for the transformers in this version of Lau's basic circuit. The number of turns on the secondaries was increased to compensate for the lower permeability of powdered iron.

Two meters display reflected and forward power (see **Fig 19**). The germanium detector diodes (D1 and D2—1N34) provide fairly accurate meter readings, particularly if the meter is calibrated (using R3, R4 and R5) to place the normal transmitter output at mid scale. If the winding sense of the transformers is reversed, the meters are transposed (the forward-power meter becomes the reflected-power meter, and vice versa).

Construction

Fig 20 shows the physical layout of the coupler. The pickup unit is mounted in a $3^1/_2 \times 3^1/_2 \times$ 4-inch box. The meters, PC-mount potentiometers and HIGH/LOW power


J3
S0-239
TRANSMITTER
T1
J4
S0-239
ANTENNA
T2
D1
1N34
D2
1N34
C1
0.01
μ F
R1
47 or
51 Ω
R2
47 or
51 Ω
C2
0.01
μ F
J1
FORWARD
P1
P2
REFLECTED
J2
R3
25 kΩ
HI-PWR
ADJ
R4
25 kΩ
LOW-PWR
ADJ
R5
5 kΩ
CAL
HIGH
PWR
LOW
PWR
S1
+
FORWARD
μA
M1
0-100
−
+
REFLECTED
μA
M2
0-100
−
ANT0934

Fig 19—Schematic diagram of the high-power directional coupler. D1 and D2 are germanium diodes (1N34 or equiv). R1 and R2 are 47 or 51-Ω, $^1/_2$-W resistors. C1 and C2 have 500-V ratings. The secondary windings of T1 and T2 each consist of 40 turns of #26 to #30 enameled wire on T-68-2 powdered-iron toroid cores. If the coupler is built into an existing antenna tuner, the primary of T1 can be part of the tuner coaxial output line. The remotely located meters (M1 and M2) are connected to the coupler box at J1 and J2 via P1 and P2.

switch are mounted in a separate box or a compartment in an antenna tuner. Parts for this project are available from the suppliers listed in **Table 3**.

The primary windings of Tl and T2 are constructed much as Grebenkemper described, but use RG-8 with its jacket removed so that the core and secondary winding may fit over the cable. The braid is wrapped with fiberglass tape to insulate it from the secondary winding. An excellent alternative to fiberglass tape—with even higher RF voltage-breakdown characteristics—is ordinary plumber's Teflon pipe tape, available at most hardware stores.

The transformer secondaries are wound on T-68-2 powdered-iron toroid cores. They are 40 turns of #26 to #30 enameled wire spread evenly around each core. By using #26 to #30 wire on the cores, the cores slip over the tape-wrapped RG-8 lines. With #26 wire on the toroids, a single layer of tape (slightly more with Teflon tape) over the braid provides an extremely snug fit for the core. Use care when fitting the cores onto the RG-8 assemblies.

After the toroids are mounted on the RG-8 sections,


ANT0935
Tape wrapped
RG-8
Shield braid
(ground only one end)
J4
SO-239
T1
J3
SO-239
Grommets
And
Feedthroughs
Pc-board
Shield
Shield braid
(ground one
End only)
R2
T2
R1
Stand-off
Insulator
Standoff
Insulator
D2
D1
J2
Phono Jack
Tape-wrapped
RG-8
C2
C1
J1
Phono Jack
4"

Fig 20—Directional-coupler construction details. Grommets or feedthrough insulators can be used to route the secondary winding of T1 and T2 through the PC board shield. A $3\,^1/_2 \times 3\,^1/_2 \times 4$-inch box serves as the enclosure.

Table 3
Parts Sources
(Also see Chapter 21)

Components	*Source*
TLC-series and CA3146 ICs	Newark Electronics 4801 N Ravenswood St Chicago, IL 60640 773-784-5100
LM334, LM336, 1% resistors, trimmer potentiometers	Digi-Key Corporation 701 Brooks Ave S PO Box 677 Thief River Falls, MN 56701 800-344-4539
Toroid cores, Fiberglass tape	Amidon Associates 240 & 250 Briggs Ave Costa Mesa, CA 92626 714-850-4660
Meters	Fair Radio Sales PO Box 1105 Lima, OH 45804 419-227-6573
Toroid cores	Palomar Engineers PO Box 462222 Escondido, CA 92046 760-747-3343
0-150/1500-W-scale meters, A&M model no. 255-138, 1N5711 diodes	Surplus Sales of Nebraska 1502 Jones St Omaha, NE 68102 402-346-4750

coat the assembly with General Cement Corp Polystyrene Q Dope, or use a spot or two of RTV sealant to hold the windings in place and fix the transformers on the RG-8 primary windings.

Mount a PC-board shield in the center of the box, between T1 and T2, to minimize coupling between the transformers. Suspend T1 between the SO-239 connectors and T2 between two standoff insulators. The detector circuits (C1, C2, D1, D2, R1 and R2) are mounted inside the coupler box as shown.

Calibration, Tune Up and Operation

The coupler has excellent directivity. Calibrate the meters for various power levels with an RF ammeter and a 50-Ω dummy load. Calculate I^2R for each power level, and mark the meter faces accordingly. Use R3, R4 and R5 to adjust the meter readings within the ranges. Diode nonlinearities are thus taken into account, and Grebenkemper's signal-processing circuits are not needed for relatively accurate power readings. Start the tune-up process using about 10 W, adjust the antenna tuner for minimum reflected power, and increase power while adjusting the tuner to minimize reflected power.

This circuit has been built into several antenna tuners with good success. The instrument works well at 1.5-kW output on 1.8 MHz. It also works well from 3.5 to 30 MHz with 1.2 and 1.5-kW output.

The antenna is easily tuned for a 1:1 SWR using the null indication provided. Amplifier settings for a matched antenna, as indicated with the wattmeter, closely agreed with those for a 50-Ω dummy load. Checks with a Palomar noise bridge and a Heath Antenna Scope also verified these findings. This circuit should handle more than 1.5 kW, as long as the SWR on the feed line through the wattmeter is kept at or near 1:1. (On one occasion high power was applied while the antenna tuner was not coupled to a load. Naturally the SWR was extremely high, and the output transformer secondary winding opened like a fuse. This resulted from the excessively high voltage across the secondary. The damage was easily and quickly repaired.)

An Inexpensive VHF Directional Coupler

Precision in-line metering devices capable of reading forward and reflected power over a wide range of frequencies are very useful in amateur VHF and UHF work, but their rather high cost puts them out of the reach of many VHF enthusiasts. The device shown in Figs 14 through 16 is an inexpensive adaptation of their basic principles. It can be made for the cost of a meter, a few small parts, and bits of copper pipe and fittings that can be found in the plumbing stocks at many hardware stores.

Construction

The sampler consists of a short section of handmade coaxial line, in this instance, of 50 Ω impedance, with a reversible probe coupled to it. A small pickup loop built into the probe is terminated with a resistor at one end and a diode at the other. The resistor matches the impedance of the loop, not the impedance of the line section. Energy picked up by the loop is rectified by the diode, and the resultant current is fed to a meter equipped with a calibration control.

The principal metal parts of the device are a brass plumbing T, a pipe cap, short pieces of $^{3}/_{4}$-inch ID and $^{5}/_{16}$-inch OD copper pipe, and two coaxial fittings. Other available tubing combinations for 50-Ω line may be usable. The ratio of outer conductor ID to inner conductor OD should be 2.4/1. For a sampler to be used with other



Fig 21—Circuit diagram for the line sampler.
C1—500-pF feedthrough capacitor, solder-in type.
C2—1000-pF feedthrough capacitor, threaded type.
D1—Germanium diode 1N34, 1N60, 1N270, 1N295, or similar.
J1, J2—Coaxial connector, type N (UG-58A).
L1—Pickup loop, copper strap 1-inch long × 3/16-inch wide. Bend into "C" shape with flat portion 5/8-inch long.
M1—0-100 µA meter.
R1—Composition resistor, 82 to 100 Ω. See text.
R3—50-kΩ composition control, linear taper.



Fig 22—Major components of the line sampler. The brass T and two end sections are at the upper left in this picture. A completed probe assembly is at the right. The N connectors have their center pins removed. The pins are shown with one inserted in the left end of the inner conductor and the other lying in the right foreground.

impedances of transmission line, see Chapter 24 for suitable ratios of conductor sizes. The photographs and **Fig 21** show construction details.

Soldering of the large parts can be done with a 300-watt iron or a small torch. A neat job can be done if the inside of the T and the outside of the pipe are tinned before assembling. When the pieces are reheated and pushed together, a good mechanical and electrical bond will result. If a torch is used, go easy with the heat, as an overheated and discolored fitting will not accept solder well.

Coaxial connectors with Teflon or other heat-resistant insulation are recommended. Type N, with split-ring retainers for the center conductors, are preferred. Pry the split-ring washers out with a knife point or small screwdriver. Don't lose them, as they'll be needed in the final assembly.

The inner conductor is prepared by making eight radial cuts in one end, using a coping saw with a fine-toothed blade, to a depth of 1/2 inch. The fingers so made are then bent together, forming a tapered end, as shown in **Figs 22** and **23**. Solder the center pin of a coaxial fitting into this, again being careful not to overheat the work.

In preparation for soldering the body of the coax connector to the copper pipe, it is convenient to use a similar fitting clamped into a vise as a holding fixture. Rest the T assembly on top, held in place by its own weight. Use the partially prepared center conductor to assure that the coax connector is concentric with the outer conductor. After being sure that the ends of the pipe are cut exactly perpendicular to the axis, apply heat to the coax fitting, using just enough so a smooth fillet of solder can be formed where the flange and pipe meet.

Before completing the center conductor, check its length. It should clear the inner surface of the connector by the thickness of the split ring on the center pin. File to length; if necessary, slot as with the other end, and solder the center pin in place. The fitting can now be soldered onto the pipe, to complete the 50-Ω line section.

The probe assembly is made from a 1 1/2 inch length of the copper pipe, with a pipe cap on the top to support the upper feedthrough capacitor, C2. The coupling loop is mounted by means of small Teflon standoffs on a copper disc, cut to fit inside the pipe. The disc has four small tabs around the edge for soldering inside the pipe. The diode, D1, is connected between one end of the loop and


Solder Lug
Feedthrough Capacitor
Pipe Cap
1 – 1/2" Length Copper Pipe
R2
500 pF
Locking Screw
Teflon Standoff
3/4" Brass Pipe "T"
1 – 1/4" Length of Copper Pipe, 3/4" ID
R1
D1
Solder
Center Conductor 5/16" OD
Pickup Loop
"Split – Ring" Retainer
Solder
Type "N" Coaxial Connector
ANT0937

Fig 23—Cross-section view of the line sampler. The pickup loop is supported by two Teflon standoff insulators. The probe body is secured in place with one or more locking screws through holes in the brass T.

a 500-pF feedthrough capacitor, C1, soldered into the disc. The terminating resistor, R1, is connected between the other end of the loop and ground, as directly as possible.

When the disc assembly is completed, insert it into the pipe, apply heat to the outside, and solder the tabs in place by melting solder into the assembly at the tabs. The position of the loop with respect to the end of the pipe will determine the sensitivity of a given probe. For power levels up to 200 watts the loop should extend beyond the face of the pipe about $^{5}/_{32}$ inch. For use at higher power levels the loop should protrude only $^{3}/_{32}$ inch. For operation with very low power levels the best probe position can be determined by experiment.

The decoupling resistor, R2, and feedthrough capacitor, C2, can be connected, and the pipe cap put in place. The threaded portion of the capacitor extends through the cap. Put a solder lug over it before tightening its nut in place. Fasten the cap with two small screws that go into threaded holes in the pipe.

Calibration

The sampler is very useful for many jobs even if it is not accurately calibrated, although it is desirable to calibrate it against a wattmeter of known accuracy. A good 50-Ω VHF dummy load is required.

The first step is to adjust the inductance of the loop, or the value of the terminating resistor, for lowest reflected power reading. The loop is the easier to change. Filing it to reduce its width will increase its impedance. Increasing the cross-section of the loop will lower the impedance, and this can be done by coating it with solder. When the reflected power reading is reduced as far as possible, reverse the probe and calibrate for forward power by increasing the transmitter power output in steps and making a graph of the meter readings obtained. Use the calibration control, R3, to set the maximum reading.

Variations

Rather than to use one sampler for monitoring both forward and reflected power by repeatedly reversing the



Fig 24—Two versions of the line sampler. The single unit described in detail here is in the foreground. Two sections in a single assembly provide for monitoring forward and reflected power without probe reversal.

probe, it is better to make two assemblies by mounting two T fittings end-to-end, using one for forward and one for reflected power. The meter can be switched between the probes, or two meters can be used.

The sampler described was calibrated at 146 MHz, as it was intended for repeater use. On higher bands the meter reading will be higher for a given power level, and it will be lower for lower frequency bands. Calibration for two or three adjacent bands can be achieved by making the probe depth adjustable, with stops or marks to aid in resetting for a given band. Of course more probes can be made, with each probe calibrated for a given band, as is done in some of the commercially available units.

Other sizes of pipe and fittings can be used by making use of information given in Chapter 24 to select conductor sizes required for the desired impedances. (Since it is occasionally possible to pick up good bargains in 75-Ω line, a sampler for this impedance might be desirable.)

Type-N fittings were used because of their constant impedance and their ease of assembly. Most have the split-ring retainer, which is simple to use in this application. Some have a crimping method, as do apparently all BNC connectors. If a fitting must be used and cannot be taken apart, drill a hole large enough to clear a soldering-iron tip in the copper-pipe outer conductor. A hole of up to $^{3}/_{8}$-inch diameter will have very little effect on the operation of the sampler.

A Calorimeter For VHF And UHF Power Measurements

A quart of water in a Styrofoam ice bucket, a roll of small coaxial cable and a thermometer are all the necessary ingredients for an accurate RF wattmeter. Its calibration is independent of frequency. The wattmeter works on the calorimeter principle: A given amount of RF energy is equivalent to an amount of heat, which can be determined by measuring the temperature rise of a known quantity of thermally insulated material. This principle is used in many of the more accurate high-power wattmeters. This procedure was developed by James Bowen, WA4ZRP, and was first described in December 1975 *QST*.

The roll of coaxial cable serves as a dummy load to convert the RF power into heat. RG-174 cable was chosen for use as the dummy load in this calorimeter because of its high loss factor, small size, and low cost. It is a standard 50-Ω cable of approximately 0.11 inch diameter. A prepackaged roll marked as 60 feet long, but measured to be 68 feet, was purchased at a local electronics store. A plot of measured RG-174 loss factor as a function of frequency is shown in **Fig 25**.



Fig 25—Loss factor of RG-174 coax used in the calorimeter.

Table 4

Calculated Input SWR for 68 Feet of Unterminated RG-174 Cable

Freq. (MHz)	*SWR*
50	2.08
144	1.35
220	1.20
432	1.06
1296	1.003
2304	1.0003

In use, the end of the cable not connected to the transmitter is left open-circuited. Thus, at 50 MHz, the reflected wave returning to the transmitter (after making a round trip of 136 feet through the cable) is 6.7 dB × 1.36 = 9.11 dB below the forward wave. A reflected wave 9.11 dB down represents an SWR to the transmitter of 2.08:1. While this value seems larger than would be desired, keep in mind that most 50-MHz transmitters can be tuned to match into an SWR of this magnitude efficiently. To assure accurate results, merely tune the transmitter for maximum power into the load before making the measurement. At higher frequencies the cable loss increases so the SWR goes down. **Table 4** presents the calculated input SWR values at several frequencies for 68 feet of RG-174. At 1000 MHz and above, the SWR caused by the cable connector will undoubtedly exceed the very low cable SWR listed for these frequencies.

In operation, the cable is submerged in a quart of water and dissipated heat energy flows from the cable into the water, raising the water temperature. See **Fig 26**. The calibration of the wattmeter is based on the physical fact that one calorie of heat energy will raise one gram of liquid water 1° Celsius. Since one quart of water contains 946.3 grams, the transmitter must deliver 946.3 calories of heat energy to the water to raise its temperature 1° C. One calorie of energy is equivalent to 4.186 joules and a joule is equal to 1 W for 1 second. Thus, the heat capacitance of 1 quart of water expressed in joules is 946.3 × 4.186 = 3961 joules/° C.

The heat capacitance of the cable is small with respect to that of the water, but nevertheless its effect should be included for best accuracy. The heat capacitance of the cable was determined in the manner described below. The 68-foot roll of RG-174 cable was raised to a uniform temperature of 100° C by immersing it in a pan of boiling water for several minutes. A quart of tap water was poured into the Styrofoam ice bucket and its temperature was measured at 28.7° C. the cable was then transferred quickly from the boiling water to the water in the ice bucket. After the water temperature in the ice bucket had ceased to rise, it measured 33.0° C. Since the total heat gained by the quart of water was equal to the total heat lost from the cable, we can write the following equation:

$$(\Delta T_{WATER})(C_{WATER}) = -(\Delta T_{CABLE})(C_{CABLE})$$

where

ΔT_{WATER} = the change in water temperature
C_{WATER} = the water heat capacitance
Δ_{CABLE} = the change in cable temperature
C_{CABLE} = the cable heat capacitance

Substituting and solving:

$$(33.0 - 28.7)(3961) = -\,(33.0 - 100)(C_{CABLE})$$

Thus, the total heat capacitance of the water and cable in the calorimeter is 3961 + 254 = 4215 joules/º C. Since 1º F = 5/9º C, the total heat capacitance can also be expressed as 4215 × 5/9 = 2342 joules/º F.



Fig 26—The calorimeter ready for use. The roll of coaxial cable is immersed in one quart of water in the left-hand compartment of the Styrofoam container. Also shown is the thermometer, which doubles as a stirring rod.

Materials and Construction

The quart of water and cable must be thermally insulated to assure that no heat is gained from or lost to the surroundings. A Styrofoam container is ideal for this purpose since Styrofoam has a very low thermal conductivity and a very low thermal capacitance. A local variety store was the source of a small Styrofoam cold chest with compartments for carrying sandwiches and drink cans. The rectangular compartment for sandwiches was found to be just the right size for holding the quart of water and coax.

The thermometer can be either a Celsius or Fahrenheit type, but try to choose one that has divisions for each degree spaced wide enough so that the temperature can be estimated readily to one-tenth degree. Photographic supply stores carry darkroom thermometers, which are ideal for this purpose. In general, glass bulb thermometers are more accurate than mechanical dial-pointer types.

The RF connector on the end of the cable should be a constant-impedance type. A BNC type connector especially designed for use on 0.11-inch diameter cable was located through surplus channels. If you cannot locate one of these, wrap plastic electrical tape around the cable near its end until the diameter of the tape wrap is the same as that of RG-58. Then connect a standard BNC connector for RG-58 in the normal fashion. Carefully seal the opposite open end of the cable with plastic tape or silicone caulking compound so no water can leak into the cable at this point.

Procedure for Use

Pour 1 quart of water (4 measuring cups) into the Styrofoam container. As long as the water temperature is not very hot or very cold, it is unnecessary to cover the top of the Styrofoam container during measurements. Since the transmitter will eventually heat the water several degrees, water initially a few degrees cooler than air temperature is ideal because the average water temperature will very nearly equal the air temperature and heat transfer to the air will be minimized.

Connect the RG-174 dummy load to the transmitter through the shortest possible length of lower loss cable such as RG-8. Tape the connectors and adapter at the RG-8 to RG-174 joint carefully with plastic tape to prevent water from leaking into the connectors and cable at this point. Roll the RG-174 into a loose coil and submerge it in the water. Do not bind the turns of the coil together in any way, as the water must be able to freely circulate among the coaxial cable turns. All the RG-174 cable must be submerged in the water to ensure sufficient cooling. Also submerge part of the taped connector attached to the RG-174 as an added precaution.

Upon completing the above steps, quickly tune up the transmitter for maximum power output into the load. Cease transmitting and stir the water slowly for a minute or so until its temperature has stabilized. Then measure the water temperature as precisely as possible. After the initial temperature has been determined, begin the test transmission, measuring the total number of seconds of key-down time accurately. Stir the water slowly with the thermometer and continue transmitting until there is a significant rise in the water temperature, say 5° to 10°. The test may be broken up into a series of short periods, as long as you keep track of the total key-down time. When the test is completed, continue to stir the water slowly and monitor its temperature. When the temperature ceases to rise, note the final indication as precisely as possible.



Fig 27—Nomogram for finding transmitter power output for the calorimeter.

To compute the transmitter power output, multiply the calorimeter heat capacitance (4215 for C or 2342 for F) by the difference in initial and final water temperature. Then divide by the total number of seconds of key-down time. The resultant is the transmitter power in watts. A nomogram that can also be used to find transmitter power output is given in **Fig 27**. With a straight line, connect the total number of key-down seconds in the time column to the number of degrees change (F or C) in the temperature rise column, and read off the transmitter power output at the point where the straight line crosses the power-output column.

Power Limitation

The maximum power handling capability of the calorimeter is limited by the following. At very high powers the dielectric material in the coaxial line will melt because of excessive heating or the cable will arc over from excessive voltage. As the transmitter frequency gets higher, the excessive-heating problem is accentuated, as more of the power is dissipated in the first several feet of cable. For instance, at 1296 MHz, approximately 10% of the transmitting power is dissipated in the first foot of cable. Overheating can be prevented when working with high power by using a low duty cycle to reduce the average dissipated power. Use a series of short transmissions, such as two seconds on, ten seconds off. Keep count of the total key-down time for power calculation purposes. If the cable arcs over, use a larger-diameter cable, such as RG-58, in place of the RG-174. The cable should be long enough to assure that the reflected wave will be down 10 dB or more at the input. It may be necessary to use more than one quart of water in order to submerge all the cable conveniently. If so, be sure to calculate the new value of heat capacitance for the larger quantity of water. Also you should measure the new coaxial cable heat capacitance using the method previously described.

A Noise Bridge For 1.8 Through 30 MHz

The noise bridge, sometimes referred to as an antenna (RX) noise bridge, is an instrument for measuring the impedance of an antenna or other electrical circuits. The unit shown here in **Fig 28**, designed for use in the 1.8 through 30-MHz range, provides adequate accuracy for most measurements. Battery operation and small physical size make this unit ideal for remote-location use. Tone modulation is applied to the wide-band noise generator as an aid for obtaining a null indication. A detector, such as the station receiver, is required for operation.

The noise bridge consists of two parts—the noise generator and the bridge circuitry. See **Fig 29**. A 6.8-V


RX NOISE BRIDGE
ON
OFF

Fig 28—Exterior and interior views of the noise bridge. The unit is finished in red enamel. Press-on lettering is used for the calibration marks. Note that the potentiometer must be isolated from ground.


S1
BT1
9 V
+
6.8 k
8
4
7
3
U1
NE555P
6.8 k
D2
D1
1N914
1
2
5
6
0.01
0.1
1800
0.01
D3
6.8 V
1 W
1200
0.01
680
22 k
0.01
10 k
0.01
Q1
2N2222A
Q2
2N2222A
C2
20
S.M.
C1
R1
Reactance Dial
Resistance Dial
B
6
5
4
T1 *
1
3
2
U
R
J1
RCVR
1
6
T1 Detail
S2
Range
X_L
X_C
C4
82
S.M.
C3
47
S.M.
1
6
3
2
5
4
ANT0940

Except as indicated, decimal values of capacitance are in microfarads (μ F); others are in picofarads (pF); resistances are in ohms; k= 1,000 , M= 1,000,000

S. M. = Silver Mica

* Note: Numbers and Letters Shown with T1 are Points Indicated on Foil Side of PC Board.

Fig 29—Schematic diagram of the noise bridge. Use 1/4 W composition resistors. Capacitors are miniature ceramic units unless indicated otherwise. Component designations indicated in the schematic but not called out in the parts list are for text and parts-placement reference only.

BT1—9-V battery, NEDA 1604A or equiv.
C1—15- to 150-pF variable
C2—20-pF mica.
C3—47-pF mica.
C4—82-pF mica.
J1, J2—Coaxial connector.
R1—Linear, 250 Ω, AB type. Use a good grade of resistor.
S1, S2—Toggle, SPST.
T1—Transformer; 3 windings on an Amidon BLN-43-2402 ferrite binocular core. Each winding is three turns of #30 enameled wire. One turn is equal to the wire passing once through both holes in the core. The primary winding starts on one side of the transformer, and the secondary and tertiary windings start on the opposite side.
U1—Timer, NE555 or equiv.

Zener diode serves as the noise source. U1 generates an approximate 50% duty cycle, 1000-Hz square wave signal which is applied to the cathode of the Zener diode. The 1000-Hz modulation appears on the noise signal and provides a useful null detection enhancement effect. The broadband-noise signal is amplified by Q1, Q2 and associated components to a level that produces an approximate S9 signal in the receiver. Slightly more noise is available at the lower end of the frequency range, as no frequency compensation is applied to the amplifier. Roughly 20 mA of current is drawn from the 9-V battery, thus ensuring long battery life—providing the power is switched off after use!



Fig 30—Etching pattern for the noise bridge PC board, at actual size. Black represents copper. This is the pattern for the bottom side of the board. The top side of the board is a complete ground plane with a small amount of copper removed from around the component holes.



Fig 31—Parts-placement guide for the noise bridge as viewed from the component or top side of the board. Mounting holes are located in two corners of the board, as shown.

The bridge portion of the circuit consists of T1, C1, C2 and R1. T1 is a trifilar wound transformer with one of the windings used to couple noise energy into the bridge circuit. The remaining two windings are arranged so that each one is in an arm of the bridge. C1 and R1 complete one arm and the UNKNOWN circuit, along with C2, comprise the remainder of the bridge. The terminal labeled RCVR is for connection to the detector.

The reactance range of a noise bridge is dependent on several factors, including operating frequency, value of the series capacitor (C3 or C3 plus C4 in Fig 29) and the range of the variable capacitor (C1 in Fig 29). The RANGE switch selects reactance measurements weighted toward either capacitance or inductance by placing C4 in parallel with C3. The zero-reactance point occurs when C1 is either nearly fully meshed or fully unmeshed. The RANGE switch nearly doubles the resolution of the reactance readings.

CONSTRUCTION

The noise bridge is contained in a homemade aluminum enclosure that measures $5 \times 2^{3}/_{8} \times 3^{3}/_{4}$ inches. Many of the circuit components are mounted on a circuit board that is fastened to the rear wall of the cabinet. The circuit-board layout is such that the lead lengths to the board from the bridge and coaxial connectors are at a minimum. An etching pattern and a parts-placement guide for the circuit board are shown in **Figs 30** and **31**.

Care must be taken when mounting the potentiometer, R1. For accurate readings the potentiometer must be well insulated from ground. In the unit shown this was accomplished by mounting the control on a piece of plexiglass, which in turn was fastened to the chassis with a piece of aluminum angle stock.

Additionally, a $^{1}/_{4}$-inch control-shaft coupling and a length of phenolic rod were used to further isolate the control from ground where the shaft passes through the front panel. A high-quality potentiometer is required if good measurement results are to be obtained.

There is no such problem when mounting the variable capacitor because the rotor is grounded. Use a high-quality capacitor; do not try to save money on that component. Two RF connectors on the rear panel are connected to a detector (receiver) and to the UNKNOWN circuit. Do not use plastic-insulated phono connectors (they might influence bridge accuracy at higher frequencies). Use miniature coaxial cable (RG-174) between the RCVR connector and circuit board. Attach one end of C3 to the circuit board and the other directly to the UNKNOWN circuit connector.

Bridge Compensation

Stray capacitance and inductance in the bridge circuit can affect impedance readings. If a very accurate bridge is required, use the following steps to counter the effects of stray reactance. Because the physical location



Fig 32—Construction details of the resistive loads used to check and calibrate the noise bridge. Each of the loads is constructed inside a coaxial connector that matches those on the bridge. (Views shown are cross-sections of PL-259 bodies; the sleeves are not shown.) Leads should be kept as short as possible to minimize parasitic inductance. A is a 0-Ω load; B depicts a 50-Ω load; C is a 180-Ω load; D shows a variable-resistance load used to determine the loss in a coaxial cable.

of the board, connectors and controls in the cabinet determine where compensation is needed, there is no provision for the compensation components on the printed circuit board.

Good calibration loads are necessary to check the accuracy of the noise bridge. Four are needed here: a 0-Ω (short-circuit) load, a 50-Ω load, a 180-Ω load, and a variable-resistance load. The short-circuit and fixed-resistance loads are used to check the accuracy of the noise bridge; the variable-resistance load is used when measuring coaxial-cable loss.

Construction details of the loads are shown in **Fig 32**. Each load is constructed inside a connector. When building the loads, keep leads as short as possible to minimize parasitic effects. The resistors must be noninductive (*not* wirewound).

Quarter-watt, carbon-composition resistors should work fine. The potentiometer in the variable-resistance load is a miniature PC-mount unit with a maximum resistance of 100 Ω or less. The potentiometer wiper and one of the end leads are connected to the center pin of the connector; the other lead is connected to ground.

Stray Capacitance

Stray capacitance on the variable-resistor side of the bridge tends to be higher than that on the unknown side. This is so because the parasitic capacitance in the variable resistor, R1, is comparatively high.

The effect of parasitic capacitance is most easily detected using the 180-Ω load. Measure and record the actual resistance of the load, R_L. Connect the load to the UNKNOWN connector, place S2 in the X_L position, tune the receiver to 1.8 MHz, and null the bridge. (See the section, "Finding the Null" for tips.) Use an ohmmeter across R1 to measure its dc resistance. The magnitude of the stray capacitance can be calculated by

$$C_P = C3\left(\sqrt{\frac{R1}{R2}} - 1\right) \qquad \text{(Eq 4)}$$

where

R_L = load resistance (as measured)

R1 = resistance of the variable resistor

C3 = series capacitance.

You can compensate for C_P by placing a variable capacitor, C_C, in the side of the bridge with lesser stray capacitance. If R1 is greater than R_L, stray capacitance is greater on the variable resistor side of the bridge: Place C_C between point U (on the circuit board) and ground. If R1 is less than R_L, stray capacitance is greater on the unknown side: Place C_C between point B and ground. If the required compensating capacitance is only a few picofarads, you can use a gimmick capacitor (made by twisting two short pieces of insulated, solid wire together) for C_C. A gimmick capacitor is adjusted by trimming its length.

Stray Inductance

Parasitic inductance, if present, should be only a few tens of nanohenries. This represents a few ohms of inductive reactance at 30 MHz. The effect is best observed by reading the reactance of the 0-Ω test load at 1.8 and 30 MHz; the indicated reactance should be the same at both frequencies.

If the reactance reading decreases as frequency is increased, parasitic inductance is greater in the known arm, and compensating inductance is needed between point U and C3. If the reactance increases with frequency, the unknown-arm inductance is greater, and compensating inductance should be placed between point B and R1.

Compensate for stray inductance by placing a single-turn coil, made from a 1 to 2-inch length of solid wire, in the appropriate arm of the bridge. Adjust the size of this coil until the reactance reading remains constant from 1.8 to 30 MHz.

Calibration

Good calibration accuracy is necessary for accurate noise-bridge measurements. Calibration of the resistance scale is straightforward. To do this, tune the receiver to a frequency near 10 MHz. Attach the 0-Ω load to the UNKNOWN connector and null the bridge. This is the zero-resistance point; mark it on the front-panel resistance scale. The rest of the resistance range is calibrated by adjusting R1, measuring R1 with an accurate ohmmeter, calculating the increase from the zero point and marking the increase on the front panel.

Most bridges have the reactance scale marked in capacitance because capacitance does not vary with frequency. Unfortunately, that requires calibration curves or non-trivial calculations to arrive at the load reactance. An alternative method is to mark the reactance scale in *ohms* at a reference frequency of 10 MHz. This method calibrates the bridge near the center of its range and displays reactance directly, but it requires a simple calculation to scale the reactance reading for frequencies other than 10 MHz. The scaling equation is:

$$X_{u(f)} = X_{u(10)} \frac{10}{f} \qquad \text{(Eq 5)}$$

where

f = frequency in MHz

$X_{u(10)}$ = reactance of the unknown load at 10 MHz

$X_{u(f)}$ = reactance of the unknown load at f.

A shorted piece of coaxial cable serves as a reactance source. (The reactance of a shorted, low-loss coaxial cable is dependent only on the cable length, the measurement frequency and the cable characteristic impedance.) Radio Shack RG-8M is used here because it is readily available, has relatively low loss and has an almost purely resistive characteristic impedance.

Prepare the calibration cable as follows:

1) Cut a length of coaxial cable that is slightly longer than $^{1}/_{4}$ λ at 10 MHz (about 20 feet for RG-8M). Attach a suitable connector to one end of the cable; leave the other end open-circuited.
2) Connect the 0-Ω load to the noise bridge UNKNOWN connector and set the receiver frequency to 10 MHz. Adjust the noise bridge for a null. Do not adjust the reactance control after the null is found.
3) Connect the calibration cable to the bridge UNKNOWN terminal. Null the bridge by adjusting *only* the variable resistor and the receiver frequency. The receiver frequency should be less than 10 MHz; if it is above 10 MHz, the cable is too short, and you need to prepare a longer one.
4) Gradually cut short lengths from the end of the coaxial cable until you obtain a null at 10 MHz by adjusting only the resistance control. Then connect the cable center and shield conductors at the open end with a short length of braid. Verify that the bridge nulls with zero reactance at 20 MHz.
5) The reactance of the coaxial cable (normalized to 10 MHz) can be calculated from:

$$X_{i(10)} = R_0 \frac{f}{10} \tan\left(2\pi \frac{f}{40}\right) \qquad \text{(Eq 6)}$$

where

$X_{i(10)}$ = cable reactance at 10 MHz

R_0 = characteristic resistance of the coaxial cable (52.5 Ω for Radio Shack RG-8M)

f = frequency in MHz

The results of Eq 6 have less than 5% error for reactances less than 500 Ω, so long as the test-cable loss is less than 0.2 dB. This error becomes significantly less at lower reactances (2% error at 300 Ω for a 0.2-dB-loss cable). The loss in 18 feet of RG-8M is 0.13 dB at 10 MHz. Reactance data for Radio Shack RG-8M is given in **Table 5**.

Table 5

Noise Bridge Calibration Data: Coaxial-Cable Method

This data is for Radio Shack RG-8M cable (R_0 =52.5 Ω) cut to exactly $^{1}/_{4}$ λ at 10 MHz; the reactances and capacitances shown correspond to this frequency.

Reactance				***Capacitance***	
X_i	*f(MHz)*	*X_i*	*f(MHz)*	*C(pF)*	*f(MHz)*
10	3.318	–10	19.376	10	9.798
20	4.484	–20	18.722	20	9.612
30	5.262	–30	18.048	30	9.440
40	5.838	–40	17.368	40	9.280
50	6.286	–50	16.701	50	9.130
60	6.647	–60	16.062	60	8.990
70	6.943	–70	15.471	70	8.859
80	7.191	–80	14.936	80	8.735
90	7.404	–90	14.462	90	8.618
100	7.586	–100	14.044	100	8.508
110	7.747	–110	13.682	110	8.403
120	7.884	–120	13.369	120	8.304
130	8.009	–130	13.097	130	8.209
140	8.119	–140	12.861	140	8.119
150	8.217	–150	12.654		
160	8.306	–160	12.473		
170	8.387	–170	12.313		
180	8.460	–180	12.172		
190	8.527	–190	12.045		
200	8.588	–200	11.932	*C(pF)*	*f(MHz)*
210	8.645	–210	11.831	–10	10.219
220	8.697	–220	11.739	–20	10.459
230	8.746	–230	11.655	–30	10.721
240	8.791	–240	11.579	–40	11.010
250	8.832	–250	11.510	–50	11.328
260	8.872	–260	11.446	–60	11.679
270	8.908	–270	11.387	–70	12.064
280	8.942	–280	11.333	–80	12.484
290	8.975	–290	11.283	–90	12.935
300	9.005	–300	11.236	–100	13.407
350	9.133	–350	11.045	–110	13.887
400	9.232	–400	10.905	–120	14.357
450	9.311	–450	10.798	–130	14.801
500	9.375	–500	10.713	–140	15.211

With the prepared cable and calibration values on hand, proceed to calibrate the reactance scale. Tune the receiver to the appropriate frequency for the desired reactance (given in Table 5, or found using Eq 6). Adjust the resistance and reactance controls to null the bridge. Mark the reactance reading on the front panel. Repeat this process until all desired reactance values have been marked. The resistance values needed to null the bridge during this calibration procedure may be significant (more than 100 Ω) at the higher reactances.

This calibration method is much more accurate than using fixed capacitors across the UNKNOWN connector. Also, you can calibrate a noise bridge in less than an hour using this method.

Finding the Null

In use, a receiver is attached to the RCVR connector and some load of unknown value is connected to the UNKNOWN terminal. The receiver allows us to hear the noise present across the bridge arms at the frequency of the receiver passband. The strength of the noise signal depends on the strength of the noise-bridge battery, the receiver bandwidth/sensitivity and the impedance difference between the known and unknown bridge arms. The noise is stronger and the null more obvious with wide receiver passbands. Set the receiver to the widest bandwidth AM mode available.

The noise-bridge output is heard as a 1000-Hz tone. When the impedances of the known and unknown bridge arms are equal, the voltage across the receiver is minimized; this is a null. In use, the null may be difficult to find because it appears only when both bridge controls approach the values needed to balance the bridge.

To find the null, set C1 to mid-scale, sweep R1 slowly through its range and listen for a reduction in noise (it's also helpful to watch the S meter). If no reduction is heard, set R1 to mid-range and sweep C1. If there is still no reduction, begin at one end of the C1 range and sweep R1. Increment C1 about 10% and sweep R1 with each increment until some noise reduction appears. Once noise reduction begins, adjust C1 and R1 alternately for minimum signal.

MEASURING COAXIAL-CABLE PARAMETERS WITH A NOISE BRIDGE

Coaxial cables have a number of properties that affect the transmission of signals through them. Generally, radio amateurs are concerned with cable attenuation and characteristic impedance. If you plan to use a noise bridge or SWR analyzer to make antenna-impedance measurements, however, you need to accurately determine not just cable impedance and attenuation, but also electrical length. Fortunately, all of these parameters are easy to measure with an accurate noise bridge or SWR analyzer.

Cable Electrical Length

With a noise bridge and a general-coverage receiver, you can easily locate frequencies at which the line in question is a multiple of $^1/_2$ λ, because a shorted $^1/_2$ λ line has a 0-Ω impedance (neglecting line loss). By locating two adjacent null frequencies, you can solve for the length of line in terms of $^1/_2$ λ at one of the frequencies and calculate the line length (overall accuracy is limited by bridge accuracy and line loss, which broadens the nulls). As an interim variable, you can express cable length as the frequency at which a cable is 1 λ long. This length will be represented by f λ. Follow these steps to determine f λ for a coaxial cable.

1) Tune the receiver to the frequency range of interest. Attach the short-circuit load to the noise bridge UNKNOWN connector and null the bridge.
2) Disconnect the far end of the coaxial cable from its load (the antenna) and connect it to the 0-Ω test load. Connect the near end of the cable to the bridge UNKNOWN connector.
3) Adjust the receiver frequency and the noise-bridge resistance control for a null. *Do not change the noise bridge reactance-control setting during this procedure.* Note the frequency at which the null is found; call this frequency f_n. The noise-bridge resistance at the null should be relatively small (less than 20 Ω).
4) Tune the receiver upward in frequency until the next null is found. Adjust the resistance control, if necessary, to improve the null, *but do not adjust the reactance control.* Note the frequency at which this second null is found; this is f_{n+2} .
5) Solve Eq 7 for n and the electrical length of the cable.

$$n = \frac{2f_n}{f_{n+2} - f_n} \qquad \text{(Eq 7)}$$

$$f_\lambda = \frac{4f_n}{n} \qquad \text{(Eq 8)}$$

where

n = cable electrical length in quarter waves, at f_n

f_l = frequency at which the cable is 1λ

ℓ = cable electrical length, in λ

For example, consider a 74-foot length of Columbia 1188 foam-dielectric cable (velocity factor = 0.78) to be used on the 10-meter band. Based on the manufacturer's specification, the cable is 2.796 λ at 29 MHz. Nulls were found at 24.412 (f_n) and 29.353 (f_{n+2}) MHz. Eq 7 yields n = 9.88, which produces 9.883 MHz from Eq 8 and 2.934 l for Eq 9. If the manufacturer's specification is correct, the measured length is off by less than 5%, which is very reasonable. Ideally, n would yield an integer. The difference between n and the closest integer indicates that there is some error.

This procedure also works for lines with an open circuit as the termination (n will be close to an odd number). End effects from the PL-259 increase the effective length of the coaxial cable; however, this decreases the calculated f_λ.

Cable Characteristic Impedance

The characteristic impedance of the coaxial cable is found by measuring its input impedance at two frequencies separated by $^1/_4\ f_\lambda$. This must be done when the cable is terminated in a resistive load.

Characteristic impedance changes slowly as a function of frequency, so this measurement must be done near the frequency of interest. The measurement procedure is as follows.

1) Place the 50-Ω load on the far end of the coaxial cable and connect the near end to the UNKNOWN connector of the noise bridge. (Measurement error is minimized when the load resistance is close to the characteristic impedance of the cable. This is the reason for using the 50-Ω load.)
2) Tune the receiver approximately $^1/_8$ f below the frequency of interest. Adjust the bridge resistance and reactance controls to obtain a null, and note their readings as R_{f1} and X_{f1}. Remember, the reactance reading must be scaled to the measurement frequency.
3) Increase the receiver frequency by exactly $^1/_4\ f\lambda$. Null the bridge again, and note the readings as R_{f2} and X_{f2}.
4) Calculate the characteristic impedance of the coaxial cable using Eqs 10 through 15. A scientific calculator is helpful for this.

$$\ell = \frac{f_0}{f_\lambda} \qquad \text{(Eq 9)}$$

$$R = R_{f1} \times F_{f2} - X_{f1} \times X_{f2} \qquad \text{(Eq 10)}$$

$$X = R_{f1} \times X_{f2} + X_{f1} \times R_{f2} \qquad \text{(Eq 11)}$$

$$Z = \sqrt{R^2 + X^2} \qquad \text{(Eq 12)}$$

$$R_0 = \sqrt{Z}\cos\left[\frac{1}{2}\tan^{-1}\left(\frac{X}{R}\right)\right] \qquad \text{(Eq 13)}$$

$$X_0 = \sqrt{Z}\sin\left[\frac{1}{2}\tan_{-1}\left(\frac{X}{R}\right)\right] \qquad \text{(Eq 14)}$$

$$Z_0 = R_0 + jX_0 \qquad \text{(Eq 15)}$$

Let's continue with the example used earlier for cable length. The measurements are:

f1 = 29.000 – (9.883 / 8) = 27.765 MHz
R_{f1} = 64 Ω
X_{f1} = –22 Ω × (10 / 27.765) = –7.9 Ω
f2 = 27.765 + (9.883/4) = 30.236 MHz
R_{f2} = 50 Ω
X_{f2} = –24 Ω × (10 / 30.236) = –7.9 Ω

When used in Eqs 10 through 15, these data yield:

R = 3137.59
X = –900.60
Z = 3264.28
R_0 = 56.58 Ω
X_0 = –7.96 Ω

Cable Attenuation

Cable loss can be measured once the cable electrical length and characteristic resistance are known. The measurement must be made at a frequency where the cable presents no reactance. Reactance is zero when the cable electrical length is an integer multiple of λ/4. You can easily meet that condition by making the measurement frequency an integer multiple of $^1/_4\ f\lambda$. Loss at other frequencies can be interpolated with reasonable accuracy. This procedure employs a resistor-substitution method that provides much greater accuracy than is achieved by directly reading the resistance from the noise-bridge scale.

1) Determine the approximate frequency at which you want to make the loss measurement by using

$$n = \frac{4f_0}{f_\lambda} \qquad \text{(Eq 16A)}$$

Round n to the nearest integer, then

$$f1 = \frac{n}{4} f_\lambda \qquad \text{(Eq 16B)}$$

2) If n is odd, leave the far end of the cable open; if n is even, connect the 0-Ω load to the far end of the cable. Attach the near end of the cable to the UNKNOWN connector on the noise bridge.
3) Set the noise bridge to zero reactance and the receiver to f1. Fine tune the receiver frequency and the noise-bridge resistance to find the null.
4) Disconnect the cable from the UNKNOWN terminal, and connect the variable-resistance calibration load in its place. Without changing the resistance setting on the bridge, adjust the load resistor and the bridge reactance to obtain a null.
5) Remove the variable-resistance load from the bridge UNKNOWN terminal and measure the load resistance using an ohmmeter that's accurate at low resistance levels. Refer to this resistance as R_i.
6) Calculate the cable loss in decibels using

$$a\ell = 8.69\ \frac{R_i}{R_0} \qquad \text{(Eq 17)}$$

To continue this example, Eq 16A gives n = 11.74, so measure the attenuation at n = 12. From Eq 16B, f1 = 29.649 MHz. The input resistance of the cable measures 12.1 Ω with 0-Ω load on the far end of the cable; this corresponds to a loss of 1.86 dB.

USING A BRIDGE TO MEASURE THE IMPEDANCE OF AN ANTENNA

The impedance at the end of a transmission line can be easily measured using a noise bridge or SWR analyzer. In many cases, however, you really want to measure the impedance of an antenna—that is, the impedance of the load at the far end of the line. There are several ways to handle this.

1) Measurements can be made with the bridge at the antenna. This is usually not practical because the antenna must be in its final position for the measurement to be accurate. Even if it can be done, making such a measurement is certainly not very convenient.
2) Measurements can be made at the source end of a coaxial cable—if the cable length is an exact integer multiple of $^1/_2$ λ. This effectively restricts measurements to a single frequency.
3) Measurements can be made at the source end of a coaxial cable and corrected using a Smith Chart as shown in Chapter 28. This graphic method can result in reasonable estimates of antenna impedance—as long as the SWR is not too high and the cable is not too lossy. However, it doesn't compensate for the complex impedance characteristics of real-world coaxial cables. Also, compensation for cable loss can be tricky to apply. These problems, too, can lead to significant errors.
4) Last, measurements can be corrected using the transmission-line equation. The *TLW* program included on the CD-ROM in the back of this book, can do these complicated computations for you. This is the best method for calculating antenna impedances from measured parameters, but it requires that you measure the feed-line characteristics beforehand—measurements for which you need access to both ends of the feed line.

The procedure for determining antenna impedance is to first measure the electrical length, characteristic impedance, and attenuation of the coaxial cable connected to the antenna. After making these measurements, connect the antenna to the coaxial cable and measure the input impedance of the cable at a number of frequencies. Then use these measurements in the transmission-line equation to determine the actual antenna impedance at each frequency.

Table 6

Impedance Data for Inverted-V Antenna

Freq (MHz)	R_u *(Ω)*	X_u *@ 10 MHz (Ω)*	X_u *(Ω)*	R_L *(Ω)*	X_L *(Ω)*
27.0	44	85	31.5	24	–65
27.2	60	95	34.9	26	–56
27.4	75	85	31.0	30	–51
27.6	90	40	14.5	32	–42
27.8	90	–20	–7.2	35	–34
28.0	75	–58	–20.7	38	–24
28.2	65	–65	–23.0	40	–19
28.4	56	–52	–18.3	44	–12
28.6	50	–40	–14.0	44	–6
28.8	48	–20	–6.9	47	1
29.0	50	0	0.0	52	8
29.2	55	20	6.8	57	15
29.4	64	30	10.2	63	21
29.6	78	20	6.8	75	26
29.8	85	0	0	78	30
30.0	90	–50	–16.7	89	33

Table 6 and **Fig 33** give an example of such a calculation. The antenna used for this example is a 10-meter inverted V about 30 feet above the ground. The arms of the antenna are separated by a 120° angle. Each arm is exactly 8 feet long, and the antenna is made of #14 wire. The feed line is the 74-foot length of Columbia 1188 characterized earlier.

See Fig 33A. From this plot of impedance measurements, it is very difficult to determine anything about the antenna. Resistance and reactance vary substantially over this frequency range, and the antenna appears to be resonant at 27.7, 29.0 and 29.8 MHz.

The plot in Fig 33B shows the true antenna imped-



Fig 33–Impedance plot of an inverted-V antenna cut for 29 MHz. At A, a plot of resistances and reactances, measured using the noise bridge, at the end of a 74-foot length of Columbia 1188 coaxial cable. At B, the actual antenna-impedance plot (found using the transmission-line equation to remove the effects of the transmission line).

ance. This plot has been corrected for the effects of the cable using the transmission-line equation. The true antenna resistance and reactance both increase smoothly with frequency. The antenna is resonant at 28.8 MHz, with a radiation resistance at resonance of 47 Ω. This is normal for an inverted V.

When doing the conversions, be careful not to make measurement errors. Such errors introduce more errors into the corrected data. This problem is most significant when the transmission line is near an odd multiple of a $^1/_4$ λ and the line SWR and/or attenuation is high. Measurement errors are probably present if small changes in the input impedance or transmission-line characteristics appear as large changes in antenna impedance. If this effect is present, it can be minimized by making the measurements with a transmission line that is approximately an integer multiple of $^1/_2$ λ.

A Practical Time-Domain Reflectometer

A time-domain reflectometer (TDR) is a simple but powerful tool used to evaluate transmission lines. When used with an oscilloscope, a TDR displays impedance "bumps" (open and short circuits, kinks and so on) in transmission lines. Commercially produced TDRs cost from hundreds to thousands of dollars each, but you can add the TDR described here to your shack for much less. This material is based on a *QST* article by Tom King, KD5HM (see Bibliography), and supplemented with information from the references.

How a TDR Works

A simple TDR consists of a square-wave generator and an oscilloscope. See **Fig 34**. The generator sends a train of dc pulses down a transmission line, and the oscilloscope lets you observe the incident and reflected waves from the pulses (when the scope is synchronized to the pulses).



Fig 34—The time-domain reflectometer shown here is attached to a small portable oscilloscope.

A little analysis of the scope display tells the nature and location of any impedance changes along the line. The nature of an impedance disturbance is identified by comparing its pattern to those in **Fig 35**. The patterns are based on the fact that the reflected wave from a disturbance is determined by the incident-wave magnitude and the reflection coefficient of the disturbance. (The patterns shown neglect losses; actual patterns may vary somewhat from those shown.)

The location of a disturbance is calculated with a simple proportional method: The round-trip time (to the disturbance) can be read from the oscilloscope screen (graticule). Thus, you need only read the time, multiply it by the velocity of the radio wave (the speed of light adjusted by the velocity factor of the transmission line) and divide by two. The distance to a disturbance is given by:

$$\ell = \frac{983.6 \times \mathrm{VF} \times \mathrm{t}}{2} \qquad \text{(Eq 18)}$$

where

ℓ = line length in feet

VF = velocity factor of the transmission line (from 0 to 1.0)

t = time delay in microseconds (μs).

The Circuit

The time-domain reflectometer circuit in **Fig 36** consists of a CMOS 555 timer configured as an astable multivibrator, followed by an MPS3646 transistor acting as a 15-ns-risetime buffer. The timer provides a 71-kHz square wave. This is applied to the 50-Ω transmission line under test (connected at J2). The oscilloscope is connected to the circuit at J1.

Construction

An etching pattern for the TDR is shown in **Fig 37**. **Fig 38** is the part-placement diagram. The TDR is


(A)
IN
OPEN CIRCUIT
E_{in}
t
IN
SHORT CIRCUIT
E_{in}
t
(B)
IN
R
$R = - Z_o \, ?\frac{\rho +1}{\rho -1}?$
$E_{in} \times \rho$
E_{in}
t
$R > Z_o$
$E_{in} \times \rho$
E_{in}
t
$R < Z_o$
(C)
IN
R
X
E_{in}
t
X_L
E_{in}
t
X_C
(D)
IN
R
X
E_{in}
t
X_L
E_{in}
t
X_C
ANT0945

Fig 35—Characteristic TDR patterns for various loads. The location of the load can be calculated from the transit time, t, which is read from the oscilloscope (see text). R values can be calculated as shown (for purely resistive loads only—$\rho < 0$ when $R < Z_0$; $\rho < 0$ when $R > Z_0$). Values for reactive loads cannot be calculated simply.

designed for a 4 × 3 × 1-inch enclosure (including the batteries). Sl, Jl and J2 are right-angle-mounted components. Two aspects of construction are critical. First use *only* an MPS3646 for Q1. This type was chosen for its good performance in this circuit. If you substitute another transistor, the circuit may not perform properly.

Second, for the TDR to provide accurate measurements, the cable connected to J1 (between the TDR and the oscilloscope) must not introduce impedance mismatches in the circuit. *Do not make this cable from ordinary coaxial cable.* Oscilloscope-probe cable is the best thing to use for this connection.

(It took the author about a week and several phone calls to determine that scope-probe cable isn't "plain old coax." Probe cable has special characteristics that prevent undesired ringing and other problems.)

Mount a binding post at J1 and connect a scope probe to the binding post when testing cables with the TDR. R5 and C2 form a compensation network—much like the networks in oscilloscope probes—to adjust for effects of


ANT0946
S1
Power
+
3 - 9 V
–
R1
1 k
8
4
VCC
Reset
7
Discharge
U1
Timer
TLC555
OUT
3
R3
560
R4
100
Q1
MPS3646
C3
1 μ F
15 V
T
C4
22 μ F
16 V
C5
470 μ F
16 V
R2
10 k
6
Threshold
2
Trigger
GND
1
R5
10 M
J 1
Oscilloscope
C2
7-60
Compensate
C1
0.001
P
J2
Cable Under Test
RL
51
Except as indicated, decimal values of capacitance are in microfarads (μF); others are in picofarads (pF); resistances are in ohms; k= 1,000, M= 1,000,000
P = Polystyrene
T = Tantalum

Fig 36—Schematic diagram of the time-domain reflectometer. All resistors are 1/4-W, 5% tolerance. U1 is a CMOS 555 timer. Circuit current drain is 10 to 25 mA. When building the TDR, observe the construction cautions discussed in the text. C2 is available from Mouser Electronics, part no. ME242-8050. Right-angle BNC connectors for use at J1 and J2 can be obtained from Newark Electronics, part no. 89N1578. S1 can be obtained from All Electronics, part no. NISW-1. An SPST toggle switch can also be used at S1.


TDR
REV A
ANT0947
1.00"

Fig 37—Full-size PC-board etching pattern for the TDR. Black areas represent unetched copper foil.


3 - 9 V
-
+
R1
R4
R2
U1
C3
C4
Q1
C5
C1
+
+
C2
S1
R3
R5
RL
J1
J2
TDR
REV A
ANT0948

Fig 38—Part-placement diagram for the TDR. Parts are mounted on the nonfoil side of the board; the shaded area represents an X-ray view of the copper pattern. Be sure to observe the polarity markings of C3, C4 and C5.

the probe wire.

The TDR is designed to operate from dc between 3 and 9 V. Two C cells (in series—3 V) supply operating voltage in this version. The circuit draws only 10 to 25 mA, so the cells should last a long time (about 200 hours of operation). U1 can function with supply voltages as low as 2.25 to 2.5.

If you want to use the TDR in transmission-line systems with characteristic impedances other than 50 Ω, change the value of R_L to match the system impedance as closely as possible.

Calibrating and Using the TDR

Just about any scope with a bandwidth of at least 10 MHz should work fine with the TDR, but for tests in short-length cables, a 50-MHz scope provides for much more accurate measurements. To calibrate the TDR, terminate CABLE UNDER TEST connector, J2, with a 51-Ω



Fig 39—TDR calibration trace as shown on an oscilloscope. Adjust C2 (See Figs 36 and 38) for maximum deflection and sharpest waveform corners during calibration. See text.



Fig 41—TDR display of the impedance characteristics of the 142-foot Hardline run to the 432-MHz antenna at KD5HM. The scope is set for 0.05 ms per division. See text for discussion.



Fig 40—Open-circuited test cable. The scope is set for 0.01 ms per division. See text for interpretation of the waveform.

resistor. Connect the scope vertical input to J1. Turn on the TDR, and adjust the scope timebase so that one square-wave cycle from the TDR fills as much of the scope display as possible (without uncalibrating the timebase). The waveform should resemble **Fig 39**. Adjust C2 to obtain maximum amplitude and sharpest corners on the observed waveform. That's all there is to the calibration process!

To use the TDR, connect the cable under test to J2, and connect the scope vertical input to J1. If the waveform you observe is different from the one you observed during calibration, there are impedance variations in the load you're testing. See **Fig 40**, showing an unterminated test cable connected to the TDR. The beginning of the cable is shown at point A. (AB represents the TDR output-pulse rise time.)

Segment AC shows the portion of the transmission line that has a 50-Ω impedance. Between points C and D, there is a mismatch in the line. Because the scope trace is higher than the 50-Ω trace, the impedance of this part of the line is higher than 50 Ω—in this case, an open circuit.

To determine the length of this cable, read the length of time over which the 50-Ω trace is displayed. The scope is set for 0.01 µs per division, so the time delay for the 50-Ω section is (0.01 µs × 4.6 divisions) = 0.046 µs. The manufacturer's specified velocity factor (VF) of the cable is 0.8. Eq 1 tells us that the 50-Ω section of the cable is

$$\ell = \frac{983.6 \times 0.8 \times 0.046\,\mu\text{s}}{2} = 18.1\text{ feet}$$

The TDR provides reasonable agreement with the actual cable length—in this case, the cable is really 16.5 feet long. (Variations in TDR-derived calculations and actual cable lengths can occur as a result of cable VFs that can vary considerably from published values. Many cables vary as much as 10% from the specified values.)

A second example is shown in **Fig 41**, where a length of $^3/_4$-inch Hardline is being tested. The line feeds a 432-MHz vertical antenna at the top of a tower. Fig 41 shows that the 50-Ω line section has a delay of (6.6 divisions × 0.05 µs) = 0.33 µs. Because the trace is straight and level at the 50-Ω level, the line is in good shape. The trailing edge at the right-hand end shows where the antenna is connected to the feed line.

To determine the actual length of the line, use the same procedure as before: Using the published VF for the Hardline (0.88) in Eq 1, the line length is

$$\ell = \frac{983.6 \times 0.88 \times 0.33\ \mu\text{s}}{2} = 142.8\ \text{feet}$$

Again, the TDR-derived measurement is in close agreement with the actual cable length (142 feet).

Final Notes

The time-domain reflectometer described here is not frequency specific; its measurements are not made at the frequency at which a system is designed to be used. Because of this, the TDR cannot be used to verify the impedance of an antenna, nor can it be used to measure cable loss at a specific frequency. Just the same, in two years of use, it has never failed to help locate a transmission-line problem. The vast majority of transmission-line problems result from improper cable installation or connector weathering.

Limitations

Certain limitations are characteristic of TDRs because the signal used to test the line differs from the system operating frequency and because an oscilloscope is a broadband device. In the instrument described here, measurements are made with a 71-kHz square wave. That wave contains components at 71 kHz and odd harmonics thereof, with the majority of the energy coming from the lower frequencies. The leading edge of the trace indicates that the response drops quickly above 6 MHz. (The leading edge in Fig 40 is 0.042 µs, corresponding to a period of 0.168 µs and a frequency of 5.95 MHz.) The result is dc pulses of approximately 7 µs duration. The scope display combines the circuit responses to all of those frequencies. Hence, it may be difficult to interpret any disturbance which is narrowband in nature (affecting only a small range of frequencies, and thus a small portion of the total power), or for which the travel time plus pattern duration exceeds 7 µs. The 432-MHz vertical antenna in Fig 41 illustrates a display error resulting from narrow-band response.

The antenna shows as a major impedance disturbance because it is mismatched at the low frequencies that dominate the TDR display, yet it is matched at 432 MHz. For an event that exceeds the observation window, consider a l-µF capacitor across a 50-Ω line. You would see only part of the pattern shown in Fig 35C because the time constant ($1 \times 10^{-6} \times 50 = 50$ ms) is much larger than the 7-µs window.

In addition, TDRs are unsuitable for measurements where there are major impedance changes inside the line section to be tested. Such major changes mask reflections from additional changes farther down the line.

Because of these limitations, TDRs are best suited for spotting faults in dc-continuous systems that maintain a constant impedance from the generator to the load. Happily, most amateur stations would be ideal subjects for TDR analysis, which can conveniently check antenna cables and connectors for short and open-circuit conditions and locate the position of such faults with fair accuracy.

Ground Parameters for Antenna Analysis

This section is taken from an article in *The ARRL Antenna Compendium, Vol 5* by R. P. Haviland, W4MB. In the past, amateurs paid very little attention to the characteristics of the earth (ground) associated with their antennas. There are two reasons for this. First, these characteristics are not easy to measure—even with the best equipment, extreme care is needed. Second, almost all hams have to put up with what they have—there are very few who can afford to move because their location has poor ground conditions! Further, the ground is not a dominant factor in the most popular antennas—a tri-band Yagi at 40 feet or higher, or a 2-meter vertical at roof height, for example.

Even so, there has been a desire and even a need for ground data and for ways to use it. It is very important for vertically polarized antennas. Ground data is useful for antennas mounted at low heights generally, and for such specialized ones as Beverages. The performance of such antennas change a lot as the ground changes.

Importance of Ground Conditions

To see why ground conditions can be important, let us look at some values. For a frequency of 10 MHz, *CCIR Recommendation 368*, gives the distance at which the signal is calculated to drop 10 dB below its free-space level as:

Conductivity (mS/meter)	*Distance for 10 dB Drop (km)*
5000	100
30	15
3	0.3

The high-conductivity condition is for sea-water. Inter-island work in the Caribbean on 40 and 80 meters is easy, whereas 40-meter ground-wave contact is difficult for much of the USA, because of much lower ground conductivity. On the other hand, the Beverage works because of poor ground conductivity.

Fig 42 shows a typical set of expected propagation curves for a range of frequencies. This data is also from *CCIR Recommendation 368* for relatively poor ground, with a dielectric constant of 4 and a conductivity of 3 mS/m (one milliSiemens/meter is 0.001 mho/meter). The same data is available in the *Radio Propagation Handbook*. There are equivalent FCC curves, found in the book *Reference Data for Radio Engineers*, but only the ones near 160 meters are useful. In Florida the author has difficulty hearing stations across town on ground



Fig 42—Variation of field strength with distance. Typical field strengths for several frequencies are shown. This is from CCIR data for fairly poor soil, with dielectric constant of 4 and conductivity of 3 mS/m. The curves for good soil are closer to the free-space line, and those for sea water are much closer to the free-space line.

wave, an indication of the poor soil conditions—reflected sky-wave signals are often stronger.

Securing Ground Data

There are only two basic ways to approach this matter of ground data. One is to use generic ground data typical to the area. The second is to make measurements, which haven't really gotten easier. For most amateurs, the best approach seems to be a combination of these—use some simple measurements, and then use the generic data to make a better estimate. Because of equipment costs and measurement difficulties, none of these will be highly accurate for most hams. But they will be much better than simply taking some condition preset into an analysis program. Having a good set of values to plug into an analysis can help you evaluate the true worth of a new antenna project.

Generic Data

In connection with its licensing procedure for broadcast stations, the FCC has published generic data for the



Estimated
Effective Ground Conductivity
in the United States

Numbers on map represent estimated effective ground conductivity in millisiemens per meter. Conductivity of seawater is not shown on map but is assumed to be 500 millisiemens per meter.

Fig 43—Estimated effective ground conductivity in the United States. FCC map prepared for the Broadcast Service, showing typical conductivity for continental USA. Values are for the band 500 to 1500 KHz. Values are for flat, open spaces and often will not hold for other types of commonly found terrain, such as seashores, river beds, etc.

entire country. This is reproduced in **Fig 43**, a chart showing the "estimated effective ground conductivity in the United States." A range of 30:1 is shown, from 1 to 30 mS/m. An equivalent chart for Canada has been prepared, originally by DOT, now DOC.

Of course, some judgment is needed when trying to use this data for your location. Broadcast stations are likely to be in open areas, so the data should not be assumed to apply to the center city. And a low site near the sea is likely to have better conductivity than the generic chart for, say, the coast of Oregon. Other than such factors, this chart gives a good first value, and a useful cross-check if some other method is used.

Still another FCC-induced data source is the license application of your local broadcast station. This includes calculated and measured coverage data. This may include specific ground data, or comparison of the coverage curves with the CCIR or FCC data to give the estimated ground conductivity. Another set of curves for ground conditions are those prepared by SRI. These give the conductivity and dielectric constant versus frequency for typical terrain conditions. These are reproduced as **Fig 44** and **Fig 45**. By inspecting your own site, you may select the curve most appropriate to your terrain. The curves are based on measurements at a number of sites across the USA, and are averages of the measured values.



Fig 44—Typical terrain conductivities versus frequency for 5 types of soils. This was measured by SRI. Units are mS/m. Conductivity of seawater is usually taken as 5000 mS/m. Conductivity of fresh water depends on the impurities present, and may be very low. To extrapolate conductivity values (for 500 to 1500 KHz) shown in Fig 43 for a particular geographic area to a different frequency, move from the conductivity at the left edge of Fig 44 to the desired frequency. For example, in rocky New Hampshire, with a conductivity of 1 mS/m at BC frequencies, the effective conductivity at 14 MHz would be approximately 4 mS/m.

Figs 46 through 48 are data derived from these measurements. **Fig 46** gives the ground-dissipation factor. Sea water has low loss (a high dissipation factor), while soil in the desert or in the city is very lossy, with a low dissipation factor. **Fig 47** gives the skin depth, the distance for the signal to decease to 63% of its value at the surface. Penetration is low in high-conductivity areas and deep in low-conductivity soil. Finally, **Fig 48** shows the wavelength in the earth. For example, at 10 meters (30 MHz), the wavelength in sea water is less than 0.3 meters. Even in the desert, the wavelength has been reduced to about 6 meters at this frequency. This is one reason why buried antennas have peculiar properties. Lacking other data, it is suggested that the values of Figs 44 and 45 be used in computer antenna modeling programs.

Measuring Ground Conditions

W2FNQ developed a simple technique to measure low-frequency earth conductivity, which has been used by W2FMI. The test setup is drawn in **Fig 49**, and uses a very old technique of 4-terminal resistivity measurements. For probes of $^{9}/_{16}$-inch diameter, spaced 18 inches and pene-trating 12 inches into the earth, the conductivity is:

$$C = 21\ V_1/V_2 \quad \text{mS/m} \qquad \text{(Eq 19)}$$

The voltages are conveniently measured by a digital voltmeter, to an accuracy of about 2%. In soil suitable for farming, the probes can be copper or aluminum. The strength of iron or copperweld may be needed in hard soils. A piece of 2 × 4 or 4 × 4 with guide holes drilled through it will help maintain proper spacing and vertical alignment of the probes. Use care when measuring—there is a shock hazard. An isolating transformer with a 24-V secondary instead of 115 V will reduce the danger.

Ground conditions vary quite widely over even small



Fig 45—Typical terrain relative dielectric constant for the 5 soil types of Fig 44, plus sea water. The dashed curve shows the highest measured values reported, and usually indicates mineralization.



Fig 46—Typical values of dissipation factor. The soil behaves as a leaky dielectric. These curves showing the dimensionless dissipation factor versus frequency for various types of soils and for sea water. The dissipation factor is inversely related to soil conductivity. Among other things, a high dissipation factor indicates that a signal penetrating the soil or water will decrease in strength rapidly with depth.



Fig 47—Typical values of skin depth. The skin depth is the depth at which a signal will have decreased to 1/e of its value at the surface (to about 30%). The effective height above ground is essentially the same as the physical height for sea water, but may be much greater for the desert. For practical antennas, this may increase low-angle radiation, but at the same time will increase ground losses.



Fig 48—Typical values of wavelength in soil. Because of its dielectric constant, the wavelength in soils and water will be shorter than that for a wave traveling in air. This can be important, since in a Method of Moment the accuracy is affected by the number of analysis segments per wavelength. Depending on the program being used, adjust the number of segments for antennas wholly or partly in the earth, for ground rods, and for antennas very close to earth.



Fig 49—Low-frequency conductivity measurement system. A 60-Hz measuring system devised by W2FNQ and used by W2FMI. The basic system is widely used in geophysics. Use care to be certain that the plug connection is correct. A better system would use a lower voltage and an isolation transformer. Measure the value of V_2 with no power applied—there may be stray ground currents present, especially if there is a power station or an electric railway close.

areas. It is best to make a number of measurements around the area of the antenna, and average the measured values.

While this measurement gives only the low-frequency conductivity, it can be used to select curves in Fig 44 to give an estimate of the conductivity for the common ham bands. Assume that the 60 Hz value is valid at 2 MHz, and find the correct value on the left axis. Move parallel to the curves on the figure to develop the estimated curve for other soil conditions.

A small additional refinement is possible. If the dielectric constant from Fig 45 is plotted against the conductivity from Fig 44 for a given frequency, a scatter plot develops, showing a trend to higher dielectric constant as conductivity increases. At 14 MHz, the relation is:

$$k = \sqrt{1000/C} \qquad \text{(Eq 20)}$$

where k is the dielectric constant and C is the measured conductivity. Using these values in *MININEC* or *NEC* calculations should give better estimates than countrywide average values.

Direct Measurement of Ground Properties

For really good values, both the conductivity and dielectric constant should be measured at the operating frequency. One way of doing this is the two-probe technique described in George Hagn's article (see Bibliography). This was the technique used to secure the data for Figs 44 through 48. The principle is sketched in **Fig 50**. In essence, the two probes form a short, open-circuited, two-wire transmission line. As shown by the equations for such lines, the input impedance is a function of the conductivity and dielectric constant of the medium. A single measurement is difficult to calculate, since the end effect of the two probes must be determined, a complex task if they are pointed for easy driving. The calculation is greatly simplified if a set of measurements is made with several sets of probes that vary in length by a fixed ratio, since the measured difference is largely due to the increased two-wire length, with some change due to the change in soil moisture with depth.

The impedance to be measured is high because of the short line length, so impedance bridges are not really suitable. An RF vector impedance meter, such as the HP-4193A, is probably the best instrument to use, with a RF susceptance bridge, such as the GR-821A, next best. With care, a Q-meter can be substituted. Because of the rarity of these instruments among amateurs, this method of measurement is not explored further here.



Fig 50—High-frequency conductivity/dielectric constant measurement system. System for measuring ground conditions at frequencies up to about 100 MHz, devised by SRI and used to obtain the data in Figs 44 through 48. Basically, this is a section of transmission line with soil as the dielectric. Requires measurement of high impedances to good accuracy.

Indirect Measurement

Since the terminal impedance and resonant frequency of an antenna change as the antenna approaches earth, measurement of an antenna at one or more heights permits an analysis of the ground characteristics. The technique is to calculate the antenna drive impedance for an assumed ground condition, and compare this with measured values. If not the same, another set of ground conditions is assumed, and the process is repeated. It is best to have a plan to guide the assumptions.

In connection with his studies of transmission lines, Walt Maxwell, W2DU, made such measurements on 20, 40 and 80 meters. Some of the data was included in his book *Reflections*. The following example is based on his 80-meter data. Data came from his Table 20-1, for a 66-foot, 2-inch dipole of #14 wire at 40 feet above ground. His table gives an antenna impedance of 72.59 + *j* 1.38 Ω at 7.15 MHz.

Table 7 shows calculated antenna impedances for ground conductivities of three different ground conductivities: 10, 1 and 0.1 mS/m, and for dielectric constants of 3, 15 and 80. The nearest value to the measured drive impedance is for a conductivity of 0.1 mS/m and a dielectric constant of 3. Figs 44 and 45 indicate that these are typical of flat desert and city land. The effect on antenna performance is shown in **Fig 51**. The maximum lobe gain for soil typical of a city is over 2 dB lower than that for the high-conductivity, high-dielectric constant value. Note that the maximum lobe occurs for a radiation angle that is directly overhead.

Table 7

Calculated values of drive resistance, in ohms, for an 40 meter dipole at 40 feet elevation versus conductivity and dielectric constant.

Conductivity	*Dielectric Constant*		
(mS/m)	*3*	*15*	*50*
10	89.78 – *j* 12.12	88.53 – *j* 10.69	88.38 – *j* 7.59
1	80.05 – *j* 17.54	83.72 – *j* 10.23	87.33 – *j* 6.98
0.1	76.44 – *j* 15.69	83.18 – *j* 9.85	97.30 – *j* 6.46

The value measured by W2DU was 72.59 – *j* 1.28 Ω, and compares closest to the poor soil condition of dielectric constant of 3 and conductivity of 0.1 mS/m.



Fig 51—Plot showing computed elevation patterns for 40-foot high, 40-meter dipole for two different ground conditions: poor ground, with dielectric constant of 3 and conductivity of 0.1 mS/m, and good ground, with dielectric constant of 50 and conductivity of 10 mS/m. Note that for a low horizontal antenna, high-angle radiation is most affected by poor ground, with low-angle radiation least affected by ground characteristics.

The ground at the W2DU QTH is a suburban Florida lot, covered with low, native vegetation. The ground is very sandy (a fossil sand dune), and is some 60-70 feet above sea-level. Measurements were made near the end of the Florida dry season. The water table is estimated to be 20 to 30 feet below the surface. Thus the calculated and measured values are reasonably consistent.

In principle, a further analysis, using values around 0.1 mS/m conductivity and 3 for dielectric constant, will give a better ground parameter estimate. However, the results should be taken with a grain of salt, because the opportunities for error in the computer modeling must be considered. The antenna should have no sag, and its length and height should be accurate. The measurement must be with accurate equipment, free from strays, such as current on the outer conductor of the coax. The feed-point gap effect must be estimated. Further, the ground itself under the antenna must be flat and have constant characteristics for modeling to be completely accurate.

Finally, the feed-line length and velocity constant of the transmission line must be accurately measured for transfer of the measured values at the feeding end of the transmission line to the antenna itself. Because of all the possibilities for error, most attempts at precision should be based on measured values at two or three frequencies, and preferably at two or three heights. Orienting the antenna to right angles for another set of measurements may be useful. Obviously, this can involve a lot of detailed work.

The author was not been able to find any guidelines for the best height or frequency. The data in the book *Exact Image Method for Impedance Computation of Antennas Above the Ground* suggests that a height of 0.3 λ will give good sensitivity to ground conditions. Very low heights may give confusing results, since several combinations of ground parameters can give nearly the same drive impedance. Both this data and experience suggest that sensitivity to ground for heights above 0.75 λ is small or negligible.

If an overall conclusion about ground characteristics is needed, we can just restate from the first paragraph—it is not greatly important for the most common horizontally polarized antenna installations. But it's worth taking a look when you need to depart from typical situations, or when the performance of a vertically polarized antenna is contemplated. Then the techniques outlined here can be helpful.

A Switchable RF Attenuator

A switchable RF attenuator is helpful for making antenna-gain comparisons or for plotting antenna radiation patterns. You may switch attenuation in or out of the line leading to the receiver to obtain an initial reference reading on a signal strength meter. Some form of attenuator is also helpful for locating hidden transmitters, where the real trick is pinpointing the signal source from within a few hundred feet. At such a close distance, strong signals may overload the front end of the receiver, making it impossible to obtain any indication of a bearing.

The attenuator of **Figs 52** and **53** is designed for low power levels, not exceeding $^{1}/_{4}$ watt. If for some reason the attenuator will be connected to a transceiver, a means of bypassing the unit during transmit periods must be devised. An attenuator of this type is commonly called a *step attenuator*, because any amount of attenuation from 0 dB to the maximum available (81 dB for this particular instrument) may be obtained in steps of 1 dB. As each switch is successively thrown from the OUT to the IN position, the attenuation sections add in cascade to yield the total of the attenuator steps switched in. The maximum attenuation of any single section is limited to 20 dB because leak-through would probably degrade the accuracy of higher values. The tolerance of resistor values also becomes more significant regarding accuracy at higher attenuation values.

A good quality commercially made attenuator will cost upwards from $150, but for less than $25 in parts and a few hours of work, you can build an attenuator at home. It will be suitable for frequencies up to 450 MHz. Double-sided pc board is used for the enclosure. The version of the attenuator shown in Fig 52 has identification lettering etched into the top surface (or front panel) of the unit. This adds a nice touch and is a permanent means of labeling. Of course rub-on transfers or Dymo tape labels could be used as well.

Female BNC single-hole, chassis-mount connectors are used at each end of the enclosure. These connectors



Fig 52—A construction method for a step attenuator. Double-sided circuit-board material, unetched (except for panel identification), is cut to the desired size and soldered in place. Flashing copper may also be used, although it is not as sturdy. Shielding partitions between sections are necessary to reduce signal leakage. Brass nuts soldered at each of the four corners allow machine screws to secure the bottom cover. The practical limit for total attenuation is 80 or 90 dB, as signal leakage around the outside of the attenuator will defeat attempts to obtain much greater amounts.



Fig 53—Schematic diagram of the step attenuator, designed for a nominal impedance of 50 Ω. Resistance values are in ohms. Resistors are $^{1}/_{4}$-watt, carbon-composition types, 5% tolerance. Broken lines indicate walls of circuit-board material. A small hole is drilled through each partition wall to route bus wire. Keep all leads as short as possible. The attenuator is bilateral; that is, the input and output ends may be reversed.

J1, J2—Female BNC connectors, Radio Shack 278-105 or equiv.

S1-S8, incl.—DPDT slide switches, standard size. (Avoid subminiature or toggle switches.) Stackpole S-5022CD03-0 switches are used here.

provide a means of easily connecting and disconnecting the attenuator.

Construction

After all the box parts are cut to size and the necessary holes made, scribe light lines to locate the inner partitions. Carefully tack-solder all partitions in position. A 25-W pencil type of iron should provide sufficient heat. Dress any pc board parts that do not fit squarely. Once everything is in proper position, run a solder bead all the way around the joints. Caution! Do not use excessive amounts of solder, as the switches must later be fit flat inside the sections. Complete the top, sides, ends and partitions. Dress the outside of the box to suit your taste. For instance, you might wish to bevel the box edges. Buff the copper with steel wool, add lettering, and finish off the work with a coat of clear lacquer or polyurethane varnish.

Using a little lacquer thinner, soak the switches to remove the grease that was added during their manufacture. When they dry, spray the inside of the switches lightly with a TV tuner cleaner/lubricant. Use a sharp drill bit (about $^3/_{16}$ inch will do), and countersink the mounting holes on the actuator side of the switch mounting plate. This ensures that the switches will fit flush against the top plate. At one end of each switch, bend the two lugs over and solder them together. Cut off the upper halves of the remaining switch lugs. (A close look at Fig 52 will help clarify these steps.)

Solder the series-arm resistors between the appropriate switch lugs. Keep the lead lengths as short as possible and do not overheat the resistors. Now solder the switches in place to the top section of the enclosure by flowing solder through the mounting holes and onto the circuit-board material. Be certain that you place the switches in their proper positions; correlate the resistor values with the degree of attenuation. Otherwise, you may wind up with the 1-dB step at the wrong end of the box how embarrassing!

Once the switches are installed, thread a piece of #18 bare copper wire through the center lugs of all the switches, passing it through the holes in the partitions. Solder the wire at each switch terminal. Cut the wire between the poles of each individual switch, leaving the wire connecting one switch pole to that of the neighboring one on the other side of the partition, as shown in Fig 52. At each of the two end switch terminals, leave a wire length of approximately $^1/_8$ inch. Install the BNC connectors and solder the wire pieces to the connector center conductors.

Now install the shunt-arm resistors of each section. Use short lead lengths. Do not use excessive amounts of heat when soldering. Solder a no. 4-40 brass nut at each inside corner of the enclosure. Recess the nuts approximately $^1/_{16}$-inch from the bottom edge of the box to allow sufficient room for the bottom panel to fit flush. Secure the bottom panel with four no. 4-40, $^1/_4$-inch machine screws and the project is completed. Remember to use caution, always, when your test setup provides the possibility of transmitting power into the attenuator.

A Portable Field Strength Meter

Few amateur stations, fixed or mobile, are without need of a field-strength meter. An instrument of this type serves many useful purposes during antenna experiments and adjustments. When work is to be done from many wavelengths away, a simple wavemeter lacks the necessary sensitivity. Further, such a device has a serious fault because its linearity leaves much to be desired. The information in this section is based on a January 1973 *QST* article by Lew McCoy, W1ICP.

The field-strength meter described here takes care of these problems. Additionally, it is small, measuring only 4 × 5 × 8 inches. The power supply consists of two 9-volt batteries. Sensitivity can be set for practically any amount desired. However, from a usefulness standpoint, the circuit should not be too sensitive or it will respond to unwanted signals. This unit also has excellent linearity with regard to field strength. (The field strength of a received signal varies inversely with the distance from the source, all other things being equal.) The frequency range includes all amateur bands from 3.5 through



Fig 54—The linear field strength meter. The control at the upper left is for C1 and the one to the right for C2. At the lower left is the band switch, and to its right the sensitivity switch. The zero-set control for M1 is located directly below the meter.



Fig 55—Inside view of the field-strength meter. At the upper right is C1 and to the left, C2. The dark leads from the circuit board to the front panel are the shielded leads described in the text.

148 MHz, with band-switched circuits, thus avoiding the use of plug-in inductors. All in all, it is a quite useful instrument.

The unit is pictured in **Figs 54** and **55**, and the schematic diagram is shown in **Fig 56**. A type 741 op-amp IC is the heart of the unit. The antenna is connected to J1, and a tuned circuit is used ahead of a diode detector. The rectified signal is coupled as dc and amplified in the op amp. Sensitivity of the op amp is controlled by inserting resistors R3 through R6 in the circuit by means of S2.

With the circuit shown, and in its most sensitive setting, M1 will detect a signal from the antenna on the order of 100 µV. Linearity is poor for approximately the first 1/5 of the meter range, but then is almost straight-line from there to full-scale deflection. The reason for the poor linearity at the start of the readings is because of nonlinearity of the diodes at the point of first conduction. However, if gain measurements are being made this is of no real importance, as accurate gain measurements can be made in the linear portion of the readings.



Decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); Resistances are in ohms; k=1,000, M=1,000,000.

Fig 56—Circuit diagram of the linear field strength meter. All resistors are 1/4- or 1/2-W composition types.

C1 — 140 pF variable.
C2 — 15-pF variable
D1, D2 — 1N914 or equiv.
L1 — 34 turns #24 enam. wire wound on an Amidon T-68-2 core, tapped 4 turns from ground end.
L2 — 12 turns #24 enam. wire wound on T-68-2 core.
L3 — 2 turns #24 enam. wire wound at ground end of L2.
L4 — 1 turn #26 enam. wire wound at ground end of L5.
L5 — 12 turns #26 enam. wire wound on T-25-12 core.
L6 — 1 turn #26 enam. wire wound at ground end of L7.
L7 — 1 turn #18 enam. wire wound on T-25-12 core.
M1 — 50 or 100 µA dc.
R2 — 10-kΩ control, linear taper.
S1 — Rotary switch, 3 poles, 5 positions, 3 sections.
S2 — Rotary switch, 1 pole, 4 positions.
S3 — DPST toggle.
U1 — Type 741 op amp. Pin numbers shown are for a 14-pin package.

The 741 op amp requires both a positive and a negative voltage source. This is obtained by connecting two 9-volt batteries in series and grounding the center. One other feature of the instrument is that it can be used remotely by connecting an external meter at J2. This is handy if you want to adjust an antenna and observe the results without having to leave the antenna site.

L1 is the 3.5/7 MHz coil and is tuned by C1. The coil is wound on a toroid form. For 14, 21 or 28 MHz, L2 is switched in parallel with L1 to cover the three bands. L5 and C2 cover approximately 40 to 60 MHz, and L7 and C2 from 130 MHz to approximately 180 MHz. The two VHF coils are also wound on toroid forms.

Construction Notes

The majority of the components may be mounted on an etched circuit board. A shielded lead should be used between pin 4 of the IC and S2. The same is true for the leads from R3 through R6 to the switch. Otherwise, parasitic oscillations may occur in the IC because of its very high gain.

In order for the unit to cover the 144-MHz band, L6 and L7 should be mounted directly across the appropriate terminals of S1, rather than on a circuit board. The extra lead length adds too much stray capacitance to the circuit. It isn't necessary to use toroid forms for the 50- and 144-MHz coils. They were used in the version described here simply because they were available. You may substitute air-wound coils of the appropriate inductance.

Calibration

The field strength meter can be used *as is* for a relative-reading device. A linear indicator scale will serve admirably. However, it will be a much more useful instrument for antenna work if it is calibrated in decibels, enabling the user to check relative gain and front-to-back ratios. If you have access to a calibrated signal generator, connect it to the field-strength meter and use different signal levels fed to the device to make a calibration chart. Convert signal-generator voltage ratios to decibels by using the equation

$$\text{dB} = 20 \log (V1/V2) \qquad \text{(Eq 21)}$$

where

V1/V2 is the ratio of the two voltages

log is the common logarithm (base 10)

Let's assume that M1 is calibrated evenly from 0 to 10. Next, assume we set the signal generator to provide a reading of 1 on M1, and that the generator is feeding a 100-µV signal into the instrument. Now we increase the generator output to 200 µV, giving us a voltage ratio of 2:1. Also let's assume M1 reads 5 with the 200-µV input. From the equation above, we find that the voltage ratio of 2 equals 6.02 dB between 1 and 5 on the meter scale. M1 can be calibrated more accurately between 1 and 5 on its scale by adjusting the generator and figuring the ratio. For example, a ratio of 126 µV to 100 µV is 1.26, corresponding to 2.0 dB. By using this method, all of the settings of S2 can be calibrated. In the instrument shown here, the most sensitive setting of S2 with R3, 1 MΩ, provides a range of approximately 6 dB for M1. Keep in mind that the meter scale for each setting of S1 must be calibrated similarly for each band. The degree of coupling of the tuned circuits for the different bands will vary, so each band must be calibrated separately.

Another method for calibrating the instrument is using a transmitter and measuring its output power with an RF wattmeter. In this case we are dealing with power rather than voltage ratios, so this equation applies:

$$\text{dB} = 10 \log (P1/P2) \qquad \text{(Eq 22)}$$

where P1/P2 is the power ratio.

With most transmitters the power output can be varied, so calibration of the test instrument is rather easy. Attach a pickup antenna to the field-strength meter (a short wire a foot or so long will do) and position the device in the transmitter antenna field. Let's assume we set the transmitter output for 10 W and get a reading on M1. We note the reading and then increase the output to 20 W, a power ratio of 2. Note the reading on M1 and then use Eq 2. A power ratio of 2 is 3.01 dB. By using this method the instrument can be calibrated on all bands and ranges.

With the tuned circuits and coupling links specified in Fig 56, this instrument has an average range on the various bands of 6 dB for the two most sensitive positions of S2, and 15 dB and 30 dB for the next two successive ranges. The 30-dB scale is handy for making front-to-back antenna measurements without having to switch S2.

An RF Current Probe

The RF current probe of **Figs 57** through **59** operates on the magnetic component of the electromagnetic field, rather than the electric field. Since the two fields are precisely related, as discussed in Chapter 23, the relative field strength measurements are completely equivalent. The use of the magnetic field offers certain advantages, however. The instrument may be made more compact for the same sensitivity, but its principal advantage is that it may be used near a conductor to measure the current flow without cutting the conductor.

In the average amateur location there may be substantial currents flowing in guy wires, masts and towers, coaxial-cable braids, gutters and leaders, water and gas pipes, and perhaps even drainage pipes. Current may be flowing in telephone and power lines as well. All of these RF currents may have an influence on antenna patterns or can be of significance in the case of RFI.

The circuit diagram of the current probe appears in Fig 58, and construction is shown in the photo, Fig 59. The winding data given here apply only to a ferrite rod of the particular dimensions and material specified. Almost any microammeter can be used, but it is usually convenient to use a rather sensitive meter and provide a series resistor to swamp out nonlinearity arising from diode conduction characteristics. A control is also used to adjust instrument sensitivity as required during operation. The tuning capacitor may be almost anything that will cover the desired range.



Fig 57—The RF current probe. The sensitivity control is mounted at the top of the instrument, with the tuning and band switches on the lower portion of the front panel. Frequency calibration of the tuning control was not considered necessary for the intended use of this particular instrument, but marks identifying the various amateur bands would be helpful. If the unit is provided with a calibrated dial, it can also be used as an absorption wavemeter.



Fig 58—Schematic diagram of the RF current probe. Resistances are in ohms; k = 1000. Capacitances are in picofarads; fixed capacitors are silver mica. Be sure to ground the rotor of C1, rather than the stator, to avoid hand capacitance. L1, L2 and L3 are each close-wound with #22 enameled wire on a single ferrite rod, 4 inch long and 1/2 inch diameter, with μ = 125 (Amidon R61-50-400). Windings are spaced approximately 1/4 inch apart.

C1—Air variable, 6-140 pF; Hammarlund HF140 or equiv.

D1—Germanium diode; 1N34A, 1N270 or equiv.

L1—1.6-5 MHz; 30 turns, tapped at 3 turns from grounded end.

L2—5-20 MHz; 8 turns, tapped at 2 turns from grounded end.

L3—17-39 MHz; 2 turns, tapped at 1 turn.

M1—Any microammeter may be used. The one pictured is a Micronta meter, RadioShack no. 270-1751.

R1—Linear taper.

RFC1—1 mH; Miller no. 4642 or equiv. Value is not critical.

S1—Ceramic rotary switch, 1 section, 2 poles, 2 to 6 positions; Centralab PA2002 or PA2003 or equiv.



Fig 59—The current probe just before final assembly. Note that all parts except the ferrite rod are mounted on a single half of the 3 × 4 × 5-inch Minibox (Bud CU-2105B or equiv.). Rubber grommets are fitted in holes at the ends of the slot to accept the rod during assembly of the enclosure. Leads in the RF section should be kept as short as possible, although those from the rod windings must necessarily be left somewhat long to facilitate final assembly.

As shown in the photos, the circuit is constructed in a metal box. This enclosure shields the detector circuit from the electric field of the radio wave. A slot must be cut with a hacksaw across the back of the box, and a thin file may be used to smooth the cut. This slot is necessary to prevent the box from acting as a shorted turn.

Using the Probe

In measuring the current in a conductor, the ferrite rod should be kept at right angles to the conductor, and at a constant distance from it. In its upright or vertical position, this instrument is oriented for taking measurements in vertical conductors. It must be laid horizontal to measure current in horizontal conductors.

Numerous uses for the instrument are suggested in an earlier paragraph. In addition, the probe is an ideal instrument for checking the current distribution in antenna elements. It is also useful for measuring RF ground currents in radial systems. A buried radial may be located easily by sweeping the ground. Current division at junctions may be investigated. *Hot spots* usually indicate areas where additional radials would be effective.

Stray currents in conductors not intended to be part of the antenna system may often be eliminated by bonding or by changing the physical lengths involved. Guy wires and other unwanted parasitic elements will often give a tilt to the plane of polarization and can make a marked difference in front-to-back ratios. When the ferrite rod is oriented parallel to the electric field lines, there will be a sharp null reading that may be used to locate the plane of polarization quite accurately. When using the meter, remember that the magnetic field is at right angles to the electric field.

You may also use the current probe as a relative signal strength meter. When making measurements on a vertical antenna, locate the meter at least two wavelengths away, with the rod in a horizontal position. For horizontal antennas, hold the instrument at approximately the same height as the antenna, with the rod vertical.

Antenna Measurements

Of all the measurements made in Amateur Radio systems, perhaps the most difficult and least understood are various measurements of antennas. For example, it is relatively easy to measure the frequency and CW power output of a transmitter, the response of a filter, or the gain of an amplifier. These are all what might be called *bench measurements* because, when performed properly, all the factors that influence the accuracy and success of the measurement are under control. In making antenna measurements, however, the “bench” is probably your backyard. In other words, the environment surrounding the antenna can affect the results of the measurement.

Control of the environment is not at all as simple as it was for the bench measurement, because now the work area may be rather spacious. This section describes antenna measurement techniques that are closely allied to those used in an antenna measuring event or contest. With these procedures you can make measurements successfully and with meaningful results. These techniques should provide a better understanding of the measurement problems, resulting in a more accurate and less difficult task. The information in this section was provided by Dick Turrin, W2IMU, and was originally published in November 1974 *QST*.

SOME BASIC IDEAS

An antenna is simply a transducer or coupler between a suitable feed line and the environment surrounding it. In addition to the efficient transfer of power from feed line to environment, an antenna at VHF or UHF is most frequently required to concentrate the radiated power into a particular region of the environment.

To be consistent while comparing different antennas, you must standardize the environment surrounding the antenna. Ideally, you want to make measurements with the measured antenna so far removed from any objects causing environmental effects that it is literally in outer space—a very impractical situation. The purpose of the measurement techniques is therefore to simulate, under practical conditions, a *controlled environment*. At VHF and UHF, and with practical-size antennas, the environment can be controlled so that successful and accurate measurements can be made in a reasonable amount of space.

The electrical characteristics of an antenna that are most desirable to obtain by direct measurement are: (1) gain (relative to an isotropic source, which by definition has a gain of unity); (2) space-radiation pattern; (3) feed-point impedance (mismatch) and (4) polarization.

Polarization

In general the polarization can be assumed from the geometry of the radiating elements. That is to say, if the antenna consists of a number of linear elements (straight lengths of rod or wire that are resonant and connected to the feed point) the polarization of the electric field will be linear and polarized parallel to the elements. If the elements are not consistently parallel with each other, then the polarization cannot easily be assumed. The following techniques are directed to antennas having polarization that is essentially linear (in one plane), although the method can be extended to include all forms of elliptic (or mixed) polarization.

Feed-Point Mismatch

The feed-point mismatch, although affected to some degree by the immediate environment of the antenna, does not affect the gain or radiation characteristics of an antenna. If the immediate environment of the antenna does not affect the feed-point impedance, then any mismatch intrinsic to the antenna tuning reflects a portion of the incident power back to the source. In a receiving antenna this reflected power is reradiated back into the environment, and can be lost entirely.

In a transmitting antenna, the reflected power travels back down the feed line to the transmitter, where it changes the load impedance presented to that transmitter. The amplifier output controls are customarily altered during the normal tuning procedure to obtain maximum power transfer to the antenna. You can still use a mismatched antenna to its full gain potential, provided the mismatch is not so severe as to cause heating losses in the system, especially the feed line and matching devices. (See also the discussion of additional loss caused by SWR in Chapter 24.)

Similarly, a mismatched receiving antenna may be matched into the receiver front end for maximum power transfer. In any case you should clearly keep in mind that the feed-point mismatch does not affect the radiation characteristics of an antenna. It can only affect the system efficiency when heating losses are considered.

Why then do we include feed-point mismatch as part of the antenna characteristics? The reason is that for efficient system performance, most antennas are resonant transducers and present a reasonable match over a relatively narrow frequency range. It is therefore desirable to design an antenna, whether it be a simple dipole or an array of Yagis, such that the final single feed-point impedance is essentially resistive and matched to the feed line. Furthermore, in order to make accurate, absolute gain measurements, it is vital that the antenna under test accept all the power from a matched-source generator, or that the reflected power caused by the mismatch be measured and a suitable error correction for heating losses be included in the gain calculations. Heating losses may be determined from information contained in Chapter 24.

While on the subject of feed-point impedance, mention should be made of the use of *baluns* in antennas. A balun is simply a device that permits a lossless transition between a balanced system feed line or antenna and an unbalanced feed line or system. If the feed point of an antenna is symmetric, such as with a dipole, and it is desired to feed this antenna with an unbalanced feed line such as coax, you should provide a balun between the line and the feed point. Without the balun, current will be allowed to flow on the outside of the coax. The current on the outside of the feed line will cause radiation, and thus the feed line will become part of the antenna radiation system. In the case of beam antennas, where it is desired to concentrate the radiated energy is a specific direction, this extra radiation from the feed line will be detrimental, causing distortion of the expected antenna pattern. See Chapter 26 for additional details on this problem.

ANTENNA TEST SITE SET-UP AND EVALUATION

Since an antenna is a reciprocal device, measurements of gain and radiation patterns can be made with the test antenna used either as a transmitting or as a receiving antenna. In general and for practical reasons, the test antenna is used in the receiving mode, and the source or transmitting antenna is located at a specified fixed remote site and unattended. In other words the source antenna, energized by a suitable transmitter, is simply required to illuminate or flood the receiving site in a controlled and constant manner.

As mentioned earlier, antenna measurements ideally should be made under free-space conditions. A further restriction is that the illumination from the source antenna be a *plane wave* over the effective aperture (capture area) of the test antenna. A plane wave by definition is one in which the magnitude and phase of the fields are uniform, and in the test-antenna situation, *uniform over the effective area plane of the test antenna*. Since it is the nature of all radiation to expand in a spherical manner at great distance from the source, it would seem to be most desirable to locate the source antenna as far from the test site as possible. However, since for practical reasons the test site and source location will have to be near the earth and not in outer space, the environment must include the effects of the ground surface and other obstacles in the vicinity of both antennas. These effects almost always dictate that the test range (spacing between source and test antennas) be as short as possible consistent with maintaining a nearly error-free plane wave illuminating the test *aperture*.

A nearly error-free plane wave can be specified as one in which the phase and amplitude, from center to edge of the illuminating field over the test aperture, do not deviate by more than about 30° and 1 decibel, respectively. These conditions will result in a gain-measurement error of no more than a few percent less than the true gain. Based on the 30º phase error alone, it can be shown that the minimum range distance is approximately

$$S_{min} = 2\frac{D^2}{\lambda} \qquad \text{(Eq 23)}$$

where D is the largest aperture dimension and λ is the free-space wavelength in the same units as D. The phase error over the aperture D for this condition is $^1/_{16}$ wavelength.

Since aperture size and gain are related by

$$\text{Gain} = \frac{4\pi A_e}{\lambda^2} \qquad \text{(Eq 24)}$$

where A_e is the effective aperture area, the dimension D may be obtained for simple aperture configurations. For a square aperture

$$D_2 = G\frac{\lambda^2}{4\pi} \qquad \text{(Eq 25)}$$

that results in a minimum range distance for a square aperture of

$$S_{min} = G\frac{\lambda}{2\pi} \qquad \text{(Eq 26)}$$

and for a circular aperture of

$$S_{min} = G\frac{2\lambda}{\pi^2} \qquad \text{(Eq 27)}$$

For apertures with a physical area that is not well defined or is much larger in one dimension that in other directions, such as a long thin array for maximum directivity in one plane, it is advisable to use the maximum estimate of D from either the expected gain or physical aperture dimensions.

Up to this point in the range development, only the conditions for minimum range length, S_{min}, have been established, as though the ground surface were not present. This minimum S is therefore a necessary condition even under free-space environment. The presence of the ground further complicates the range selection, not in the determination of S but in the exact location of the source and test antennas above the earth.

It is always advisable to select a range whose intervening terrain is essentially flat, clear of obstructions, and of uniform surface conditions, such as all grass or all pavement. The extent of the range is determined by the illumination of the source antenna, usually a Yagi, whose gain is no greater than the highest gain antenna to be measured. For gain measurements the range consists essentially of the region in the beam of the test antenna. For radiation-pattern measurements, the range is considerably larger and consists of all that area illuminated by the source antenna, especially around and behind the test site. Ideally you should choose a site where the test-antenna location is near the center of a large open area and the source antenna is located near the edge where most of the obstacles (trees, poles, fences, etc.) lie.



Fig 60—On an antenna test range, energy reaching the receiving equipment may arrive after being reflected from the surface of the ground, as well as by the direct path. The two waves may tend to cancel each other, or may reinforce one another, depending on their phase relationship at the receiving point.

The primary effect of the range surface is that some of the energy from the source antenna will be reflected into the test antenna, while other energy will arrive on a direct line-of-sight path. This is illustrated in **Fig 60**. The use of a flat, uniform ground surface assures that there will be essentially a mirror reflection, even though the reflected energy may be slightly weakened (absorbed) by the surface material (ground). In order to perform an analysis you should realize that horizontally polarized waves undergo a 180º phase reversal upon reflection from the earth. The resulting illumination amplitude at any point in the test aperture is the vector sum of the electric fields arriving from the two directions, the direct path and the reflected path.

If a perfect mirror reflection is assumed from the ground (it is nearly that for practical ground conditions at VHF/UHF) and the source antenna is isotropic, radiating equally in all directions, then a simple geometric analysis of the two path lengths will show that at various point in the vertical plane at the test-antenna site the waves will combine in different phase relationships. At some points the arriving waves will be in phase, and at other points they will be 180º out of phase. Since the field amplitudes are nearly equal, the resulting phase change caused by path length difference will produce an ampli-



Fig 61—The vertical profile, or plot of signal strength versus test-antenna height, for a fixed height of the signal source above ground and at a fixed distance. See text for definitions of symbols.

tude variation in the vertical test site direction similar to a standing wave, as shown in **Fig 61**.

The simplified formula relating the location of h2 for maximum and minimum values of the two-path summation in terms of h1 and S is

$$h2 = n\frac{\lambda}{4}\times\frac{S}{h1} \qquad \text{(Eq 28)}$$

with n = 0, 2, 4, . . . for minimums and n = 1, 3, 5, . . . for maximums, and S is much larger than either h1 or h2.

The significance of this simple ground reflection formula is that it permits you to determine the approximate location of the source antenna to achieve a nearly plane-wave amplitude distribution *in the vertical direction* over a particular test *aperture size*. It should be clear from examination of the height formula that as h1 is decreased, the vertical distribution pattern of signal at the test site, h2, expands. Also note that the signal level for h2 equal to zero is always zero on the ground regardless of the height of h1.

The objective in using the height formula then is, given an effective antenna aperture to be illuminated from which a minimum S (range length) is determined and a suitable range site chosen, to find a value for h1 (source antenna height). The required value is such that the *first* maximum of vertical distribution at the test site, h2, is at a practical distance above the ground, and at the same time the signal amplitude over the aperture in the vertical direction does not vary more than about 1 dB. This last condition is not sacred but is closely related to the particular antenna under test.

In practice these formulas are useful only to initialize the range setup. A final check of the vertical distribution at the test site must be made by direct measurement. This measurement should be conducted with a small low-gain but unidirectional probe antenna such as a corner reflector or 2-element Yagi that you move along a vertical line over the intended aperture site. Care should be exercised to minimize the effects of local environment around the probe antenna and that the beam of the probe be directed at the source antenna at all times for maximum signal. A simple dipole is undesirable as a probe antenna because it is susceptible to local environmental effects.

The most practical way to instrument the vertical distribution measurement is to construct some kind of vertical track, preferably of wood, with a sliding carriage or platform that may be used to support and move the probe antenna. It is assumed of course that a stable source transmitter and calibrated receiver or detector are available so variations of the order of $^1/_2$ dB can be clearly distinguished.

Once you conduct these initial range measurements successfully, the range is now ready to accommodate any aperture size less in vertical extent than the largest for which S_{min} and the vertical field distribution were selected. Place the test antenna with the center of its aperture at the height h2 where maximum signal was found. Tilt the test antenna tilted so that its main beam is pointed in the direction of the source antenna. The final tilt is found by observing the receiver output for maximum signal. This last process must be done empirically since the apparent location of the source is somewhere between the actual source and its image, below the ground.

An example will illustrate the procedure. Assume that we wish to measure a 7-foot diameter parabolic reflector antenna at 1296 MHz (λ = 0.75 foot). The minimum range distance, S_{min}, can be readily computed from the formula for a circular aperture.

$$S_{min} = 2\frac{D^2}{\lambda} = 2\times\frac{49}{0.75} = 131 \text{ feet}$$

Now a suitable site is selected based on the qualitative discussion given before.

Next determine the source height, h1. The procedure is to choose a height h1 such that the first minimum above ground (n = 2 in formula) is at least two or three times the aperture size, or about 20 feet.

$$h1 = n\frac{\lambda}{4}\frac{S}{h1} = 2\times\frac{0.75}{4}\times\frac{131}{20} = 2.5 \text{ feet}$$

Place the source antenna at this height and probe the vertical distribution over the 7-foot aperture location, which will be about 10 feet off the ground.

$$h2 = n\frac{\lambda}{4}\frac{S}{h1} = 1\times\frac{0.75}{4}\times\frac{131}{2.5} = 9.8 \text{ feet}$$

Plot the measured profile of vertical signal level versus height. From this plot, empirically determine whether the 7-foot aperture can be fitted in this profile such that the 1-dB variation is not exceeded. If the variation exceeds



Fig 62—Sample plot of a measured vertical profile.

1 dB over the 7-foot aperture, the source antenna should be lowered and h2 raised. Small changes in h1 can quickly alter the distribution at the test site. **Fig 62** illustrates the points of the previous discussion.

The same set-up procedure applies for either horizontal or vertical linear polarization. However, it is advisable to check by direct measurement at the site for each polarization to be sure that the vertical distribution is satisfactory. Distribution probing in the horizontal plane is unnecessary as little or no variation in amplitude should be found, since the reflection geometry is constant. Because of this, antennas with apertures that are long and thin, such as a stacked collinear vertical, should be measured with the long dimension parallel to the ground.

A particularly difficult range problem occurs in measurements of antennas that have depth as well as cross-sectional aperture area. Long end-fire antennas such as long Yagis, rhombics, V-beams, or arrays of these antennas, radiate as *volumetric arrays* and it is therefore even more essential that the illuminating field from the source antenna be reasonably uniform in depth as well as plane wave in cross section. For measuring these types of antennas it is advisable to make several vertical profile measurements that cover the depth of the array. A qualitative check on the integrity of the illumination for long end-fire antennas can be made by moving the array or antenna axially (forward and backward) and noting the change in received signal level. If the signal level varies less than 1 or 2 dB for an axial movement of several wavelengths then the field can be considered satisfactory for most demands on accuracy. Large variations indicate that the illuminating field is badly distorted over the array depth and subsequent measurements are questionable. It is interesting to note in connection with gain measurements that any illuminating field distortion will always result in measurements that are lower than true values.

ABSOLUTE GAIN MEASUREMENT

Having established a suitable range, the measure-



Fig 63—Standard-gain antenna. When accurately constructed for the desired frequency, this antenna will exhibit a gain of 7.7 dB over a dipole radiator, plus or minus 0.25 dB. In this model, constructed for 432 MHz, the elements are $^3/_8$-inch diameter tubing. The phasing and support lines are of $^5/_{16}$-inch diameter tubing or rod.

ment of gain relative to an isotropic (point source) radiator is almost always accomplished by direct comparison with a calibrated standard-gain antenna. That is, the signal level with the test antenna in its optimum location is noted. Then you remove the test antenna and place the standard-gain antenna with its aperture at the center of location where the test antenna was located. Measure the difference in signal level between the standard and the test antennas and add to or subtract from the gain of the standard-gain antenna to obtain the absolute gain of the test antenna. Here, *absolute* means with respect to a point source with a gain of unity, by definition. The reason for using this reference rather than a dipole, for instance, is that it is more useful and convenient for system engineering. We assume that both standard and test antennas have been carefully matched to the appropriate impedance and an accurately calibrated and matched detecting device is being used.

A standard-gain antenna may be any type of unidirectional, preferably planar-aperture, antenna, which has been calibrated either by direct measurement or in special cases by accurate construction according to computed dimensions. A standard-gain antenna has been suggested by Richard F. H. Yang (see Bibliography). Shown in **Fig 63**, it consists of two in-phase dipoles $^1/_2$ λ apart and backed up with a ground plane 1 λ square.

In Yang's original design, the stub at the center is a balun formed by cutting two longitudinal slots of $^1/_8$-inch width, diametrically opposite, on a $^1/_4$-λ section of $^7/_8$-inch rigid 50-Ω coax. An alternative method of feeding is to feed RG-8 or RG-213 coax through slotted $^7/_8$-inch copper tubing. Be sure to leave the outer jacket on the coax to insulate it from the copper-tubing balun section. When constructed accurately to scale for the frequency of interest, this type of standard will have an absolute gain of 9.85 dBi (7.7 dBd gain over a dipole in free space) with an accuracy of ± 0.25 dB.

RADIATION-PATTERN MEASUREMENTS

Of all antenna measurements, the radiation pattern is the most demanding in measurement and the most difficult to interpret. Any antenna radiates to some degree in all directions into the space surrounding it. Therefore, the radiation pattern of an antenna is a three-dimensional representation of the magnitude, phase and polarization. In general, and in practical cases for Amateur Radio communications, the polarization is well defined and only the magnitude of radiation is important.

Furthermore, in many of these cases the radiation in one particular plane is of primary interest, usually the plane corresponding to that of the Earth's surface, regardless of polarization. Because of the nature of the range setup, measurement of radiation pattern can be successfully made only in a plane nearly parallel to the earth's surface. With beam antennas it is advisable and usually sufficient to take two radiation pattern measurements, one in the polarization plane and one at right angles to the plane of polarization. These radiation patterns are referred to in antenna literature as the principal E-plane and H-plane patterns, respectively. *E-plane* means parallel to the electric field that is the polarization plane and *H-plane* means parallel to the magnetic field in free space. The electric field and magnetic field are always perpendicular to each other in a plane wave as it propagates through space.

When the antenna is located over real earth, the terms *Azimuth* and *elevation* planes are commonly used, since the frame of reference is the Earth itself, rather than the electric and magnetic fields in free space. For a horizontally polarized antenna such as a Yagi mounted with its elements parallel to the ground, the azimuth plane is the E-plane and the elevation plane is the H-plane.

The technique to obtain these patterns is simple in procedure but requires more equipment and patience than does making a gain measurement. First, a suitable mount is required that can be rotated in the azimuth plane (horizontal) with some degree of accuracy in terms of azimuth-angle positioning. Second, a signal-level indicator calibrated over at least a 20-dB dynamic range with a readout resolution of at least 2 dB is required. A dynamic range of up to about 40 dB would be desirable but does not add greatly to the measurement significance.

With this much equipment, the procedure is to locate first the area of maximum radiation from the beam antenna by carefully adjusting the azimuth and elevation positioning. These settings are then arbitrarily assigned an azimuth angle of zero degrees and a signal level of zero decibels. Next, without changing the elevation setting (tilt of the rotating axis), the antenna is carefully rotated in azimuth in small steps that permit signal-level readout of 2 or 3 dB per step. These points of signal level corresponding with an azimuth angle are recorded and plotted on polar coordinate paper. A sample of the results is shown on ARRL coordinate paper in **Fig 64**.

On the sample radiation pattern the measured points are marked with an X and a continuous line is drawn in, since the pattern is a continuous curve. Radiation patterns should preferably be plotted on a logarithmic radial scale, rather than a voltage or power scale. The reason is that the log scale approximates the response of the ear to signals in the audio range. Also many receivers have AGC systems that are somewhat logarithmic in response; therefore the log scale is more representative of actual system operation.

Having completed a set of radiation-pattern measurements, one is prompted to ask, "Of what use are they?" The primary answer is as a diagnostic tool to determine if the antenna is functioning as it was intended to. A second answer is to know how the antenna will discriminate against interfering signals from various directions.

Consider now the diagnostic use of the radiation patterns. If the radiation beam is well defined, then there is an approximate formula relating the antenna gain to the



For more information see QST, July 1980, p.26 Copyright 1980, ARRL Inc.

Fig 64—Sample plot of a measured radiation pattern, using techniques described in the text. The plot is on coordinate paper available from ARRL HQ. The form provides space for recording significant data and remarks.

measured half-power beamwidth of the E- and H-plane radiation patterns. The half-power beamwidth is indicated on the polar plot where the radiation level falls to 3 dB below the main beam 0-dB reference on either side. The formula is

$$\text{Gain}\left(\text{dBi}\right) \cong \frac{41{,}253}{\theta_E \phi_H} \qquad \text{(Eq 29)}$$

where θ_E and ϕ_H are the half-power beamwidths in degrees of the E- and H-plane patterns, respectively. This equation assumes a lossless antenna system, where any side-lobes are well suppressed.

To illustrate the use of this equation, assume that we have a Yagi antenna with a boom length of two wavelengths. From known relations (described in Chapter 11) the expected free-space gain of a Yagi with a boom length of 2 λ is about 13 dBi; its gain, G, equals 20. Using the above relationship, the product of $\theta_E \times \phi_H \approx 2062$ square degrees. Since a Yagi produces a nearly symmetric beam shape in cross section, $\theta_E = \phi_H = 45°$. Now if the measured values of θ_E and ϕ_H are much larger than 45°, then the gain will be much lower than the expected 13 dBi.

As another example, suppose that the same antenna (a 2-wavelength-boom Yagi) gives a measured gain of 9 dBi but the radiation pattern half power beamwidths are approximately 45°. This situation indicates that although the radiation patterns seem to be correct, the low gain shows inefficiency somewhere in the antenna, such as lossy materials or poor connections.

Large broadside collinear antennas can be checked for excessive phasing-line losses by comparing the gain computed from the radiation patterns with the direct-measured gain. It seems paradoxical, but it is indeed possible to build a large array with a very narrow beamwidth indicating high gain, but actually having very low gain because of losses in the feed distribution system.

In general, and for most VHF/UHF Amateur Radio communications, gain is the primary attribute of an antenna. However, radiation in other directions than the main beam, called *sidelobe radiation*, should be examined by measurement of radiation patterns for effects such as nonsymmetry on either side of the main beam or excessive magnitude of sidelobes. (Any sidelobe that is less than 10 dB below the main beam reference level of 0 dB should be considered excessive.) These effects are usually attributable to incorrect phasing of the radiating elements or radiation from other parts of the antenna that was not intended, such as the support structure or feed line.

The interpretation of radiation patterns is intimately related to the particular type of antenna under measurement. Reference data should be consulted for the antenna type of interest, to verify that the measured results are in agreement with expected results.

To summarize the use of pattern measurements, if a beam antenna is first checked for gain (the easier measurement to make) and it is as expected, then pattern measurements may be academic. However, if the gain is lower than expected it is advisable to make pattern measurements to help determine the possible causes for low gain.

Regarding radiation pattern measurements, remember that the results measured under proper range facilities will not necessarily be the same as observed for the same antenna at a home-station installation. The reasons may be obvious now in view of the preceding information on the range setup, ground reflections, and the vertical-field distribution profiles. For long paths over rough terrain where many large obstacles may exist, the effects of ground reflection tend to become diffused, although they still can cause unexpected results. For these reasons it is usually unjust to compare VHF/UHF antennas over long paths.

Vector Network Analyzers

The process of building and properly tuning a phased array often involves making a number of different measurements to achieve a desired level of performance, as was pointed out in Chapter 8, Multielement Arrays. This section was written by Rudy Severns, N6LF.

After erecting an array we would like to measure the resonant frequency of each element, the self-impedances of each element and the mutual impedances between the elements. We will also want to know these impedances over the whole operating band to help design a feed network. When building the feed network, we may need to check the values and Qs of the network elements and we will want to determine the electrical lengths of transmission lines.

Final tuning of the array requires that the relative current amplitudes and phases in each element be measured and adjusted, if necessary. We also will want to determine the SWR at the feed point. Doing all of this even moderately well can require quite a bit of equipment, some of which is heavy and requires ac line power. This can be a nuisance in the field, especially if the weather is not cooperating.

Professionals make these measurements by employing a *vector network analyzer* (VNA) or the somewhat simpler, *reflection-transmission test set*. These instruments can make all the necessary measurements quickly and with great accuracy. However, in the past VNAs have been very expensive, out of reach for general amateur use. But thanks to modern digital technology VNAs that work with a laptop computer are now becoming available at prices an amateur might consider. It's even possible to homebrew a VNA[1] with performance that approaches a professional instrument. Considering the cost of even a simple array, investment in a VNA makes sense.

VNAs are based on reflection and transmission measurements. To use a VNA it is very helpful to have a basic understanding of *Scattering Parameters* (S-parameters). Microwave engineers have long used these because they have to work with circuits that are large in terms of wavelength, where measurements of forward and reflected power are easy.

HF arrays are also large in terms of wavelength. The techniques for measuring forward and reverse powers work well even at 160 meters. For example, even though the array elements may be 100 feet apart, you can place your instruments in a central location and run cables out to each element. The effect of the cables from the VNA to the elements can be absorbed in the initial calibration procedure so the measurements read out at the VNA are effectively those at each element. In other words, the measurement reference points can be placed electrically at the base of the element, regardless of the physical location of the instrumentation and the interconnecting cables.

In a completed array with its feed network, the network can be excited by the VNA at the feed point and the relative current amplitudes and phases at each element can be measured over a frequency band. Then, adjustments can be made as needed. When the final values for the current amplitudes and phases are known, these values can be put back into an array model in a program like *EZNEC* to determine the pattern of the array across the whole frequency band.

S-PARAMETERS

In Chapter 24, Transmission Lines, the reflection coefficient rho (ρ) is defined as the ratio of the reflected voltage (V_r) to the incident voltage (V_i):

$$\rho = \frac{V_r}{V_i} \qquad \text{(Eq 30)}$$

If we know the load impedance (Z_L) and the transmission line impedance (Z_0) we can calculate ρ from:

$$\rho = \frac{Z_L - Z_0}{Z_L + Z_0} \qquad \text{(Eq 31)}$$

Keep in mind that ρ is a complex number (a vector), which we represent by either amplitude and phase (|Z|, θ) or by real and imaginary parts (R ± *j* X). The two representations are equivalent. From ρ we can then calculate SWR. That's very handy, but here we want to do something different. If we have an instrument that measures ρ and we know Z_0 then we can determine Z_L from:

$$Z_L = Z_0 \left(\frac{1+\rho}{1-\rho} \right) \qquad \text{(Eq 32)}$$

Measuring ρ is one of the things that VNAs do very well. With a VNA, the measurement can be made at one end of a long transmission line with the load at the other end. The effect of the line can be calibrated out, as mentioned above, so that we are in effect measuring right at the load.



Fig 65—A 2-element array, where h is the element height and S is the spacing between the elements.

This approach can be used directly to measure the impedance and resonant frequency of a single element. By open and short circuiting elements in an array we can determine the mutual as well as self impedances for, and between, all the elements. We can also use this approach to measure component values, inductor Qs, etc.

This is an example of a *one-port* measurement; that is, a load at the end of a transmission line. However, a multi-element array actually behaves as a multi-port network, so to get the most out of a VNA, you need to generalize the above procedure. This is where S-parameters come into play. To illustrate the principles we will use a simple 2-element array like that shown in **Fig 65**.

To design a feed network to drive this array we need to know the input impedance of each element (Z_1 and Z_2) as a function of the drive currents (I_1 and I_2). The input impedances will depend on the self impedance of each element, the coupling between them (the mutual impedance) and the drive currents in each element. To manage this problem we can represent a 2-element array as a two-port network, as shown in **Fig 66**. And we can relate the port voltages, currents and impedances with Eq 33:

$$\begin{aligned} V_1 &= Z_{11}I_1 + Z_{12}I_2 \\ V_2 &= Z_{21}I_1 + Z_{22}I_2 \end{aligned} \qquad \text{(Eq 33)}$$

Normally we know I_1 and I_2 from the design of the array, but we need to determine the resulting element impedances. That's the challenge. Fortunately, an array is a linear network, so $Z_{12} = Z_{21}$, which means we need only determine three variables: the self impedances Z_{11} and Z_{22} and the mutual impedance, Z_{12}.

Once we know Z_{11}, $Z_{12,}$ Z_{22} and are given I_1 and I_2, we can determine the feed-point impedances at each element from:

$$\begin{aligned} Z_1 &= Z_{11} + \left(\frac{I_2}{I_1}\right) Z_{12} \\ Z_2 &= Z_{22} + \left(\frac{I_1}{I_2}\right) Z_{12} \end{aligned} \qquad \text{(Eq 34)}$$

This is the conventional approach. However, there are some problems here. We have to be able to accurately measure either voltages and currents or impedances in multiple elements that may be separated by large fractions of a wavelength. In addition, accurate measurements of current, voltage and impedance become increasingly more difficult as we go up in frequency.



Fig 66—Two-port representation of currents and voltages in the 2-element array in Fig 65.



Fig 67—Test setup to measure a 2-element array using a VNA.

It turns out that we can get the information more easily by measuring incident and reflected voltages at the ports and from those measurements determine the feed-point impedances. A VNA is an instrument for measuring these voltages. It turns out to be easier to measure the ratios of two voltages rather than their absolute values.

The measurement setup using a VNA for a 2-element array is shown in **Fig 67**. VNAs usually have at least two RF connections: the transmit port (T) and the receive port (R). Professional units may have more RF connections. The T output provides an signal from a 50-Ω source and the R port is a detector with a 50-Ω input impedance. Basically we have a transmitter and a receiver. The transmit port uses a directional coupler to provide measurements of the forward and reflected signals at that output. The receive port measures the signal transmitted through the network. Transmission lines usually have Z_0 = 50 Ω and may be of any length required by the size of the array.

Using incident and reflected voltages, the two-port network representation is now changed, as shown in **Fig 68**, where:

V_{1i} = incident voltage at port 1
V_{1r} = reflected voltage at port 1
V_{2i} = incident voltage at port 2
V_{2r} = reflected voltage at port 2

In a manner analogous to Eq 33, we can write an expression in terms of the incident and reflected voltages:

$$\begin{aligned} b_1 &= S_{11}a_1 + S_{12}a_2 \\ b_2 &= S_{21}a_1 + S_{22}a_2 \end{aligned} \qquad \text{(Eq 35)}$$

where:

$$a_1 \frac{V_{1i}}{\sqrt{Z_0}} \qquad b_1 \frac{V_{1r}}{\sqrt{Z_0}}$$
$$a_2 = \frac{V_{2i}}{\sqrt{Z_0}} \qquad b_2 = \frac{V_{2r}}{\sqrt{Z_0}} \qquad \text{(Eq 36)}$$

We see that the a_n and b_n are simply the incident and reflected voltages at the two ports divided by $\sqrt{Z_o}$. Because this is a linear network, $S_{21} = S_{12}$.

What are the S_{ij} quantities? These are called the *S-parameters*, which are defined by:

$$\begin{aligned} S_{11} &\equiv \left.\frac{b_1}{a_1}\right|_{a_2=0} = \left.\frac{V_{1r}}{V_{1i}}\right|_{V_{2i}=0} \\ S_{21} &\equiv \left.\frac{b_2}{a_1}\right|_{a_2=0} = \left.\frac{V_{2r}}{V_{1i}}\right|_{V_{2i}=0} \\ S_{12} &\equiv \left.\frac{b_1}{a_2}\right|_{a_1=0} = \left.\frac{V_{1r}}{V_{2i}}\right|_{V_{1i}=0} \\ S_{22} &\equiv \left.\frac{b_2}{a_2}\right|_{a_1=0} = \left.\frac{V_{2r}}{V_{2i}}\right|_{V_{1i}=0} \end{aligned} \qquad \text{(Eq 37)}$$

Note that the S_{ij} parameters are all ratios of reflected and incident voltages, and they are usually complex numbers. The condition that $a_2 = 0 = V_{2i}$ is the same as saying that port 2 is terminated in a load equal to Z_0 and the network is excited at port 1. This means there is no reflection from the load on port 2, which makes $V_{2i} = 0$. Similarly, if we terminate port 1 with Z_0 and excite port 2, then $V_{1i} = 0 = a_1$.



Fig 68—Two-port network with incident and reflected waves.

If we compare Eq 30 to the first line of Eq 37 we see that $S_{11} = \rho_1$, the reflection coefficient at port 1. We can now restate Eq 32 in terms of S_{11}:

$$Z = Z_0\left(\frac{1+S_{11}}{1-S_{11}}\right) \qquad \text{(Eq 38)}$$

where Z is the impedance looking into port 1 with port 2 terminated in Z_0. In the case where port 2 does not exist—that is, you are measuring a single element (for example, measuring element 1 with element 2 open-circuited) or a component, then Z is simply the self impedance (Z_{11} in Eq 33). Since S_{11} is a standard measurement for VNAs you can calculate Z using Eq 38. In many cases the VNA software will do this calculation for you automatically. You can also measure element 2 with element 1 open and determine Z_{22}.

S_{21} represents the ratio of the signal coming out of port 2 (V_{2r}) to the input signal on port 1 (V_{1i}) and is another standard VNA measurement. S_{21} is a measurement of the signal transmission between the ports through the network, or in the case of an array, the signal transmission due to the coupling between the elements. Again, port 2 is terminated in Z_0.

A full-feature VNA will measure all the S_{ij} parameters at once, but most of the lower-cost units of interest to amateurs are what we call *reflection-transmission test sets*. What this means is that they only measure S_{11} and S_{21}. To obtain S_{22} and S_{12} we have to interchange the test cables at the array elements (see Fig 67) and run the measurements again. Normally the software will accommodate this as a second entry and we end up with the full set of S_{ij} parameters.

If we do run a full set of S_{ij} parameters then we can transform these to Z_{ij} (Eq 33) using the following expressions, assuming that $S_{21} = S_{12}$:

$$\begin{aligned} Z_{11} &= \frac{(1+S_{11})(1-S_{22})+S_{12}^{\,2}}{(1-S_{11})(1-S_{22})-S_{12}^{\,2}} \\ Z_{22} &= \frac{(1-S_{11})(1+S_{22})+S_{12}^{\,2}}{(1-S_{11})(1-S_{22})-S_{12}^{\,2}} \\ Z_{12} &= \frac{(2S_{12})}{(1-S_{11})(1-S_{22})-S_{12}^{\,2}} \end{aligned} \qquad \text{(Eq 39)}$$

The example to this point has been for a 2-element array. The S-parameters can be determined for an array with any number of elements. In an n-port S-parameter measurement, all ports are terminated in Z_0 at the same time. Measurements are made between one set of ports at a time and repeated until all pairs of ports are measured.

ARRAY MEASUREMENT EXAMPLE

A good way to illustrate the use of a VNA for array measurements is to work through an example with a real array. **Fig 69** is a picture of a 2-element 20-meter phased array built by Mark Perrin, N7MQ.

Each element is λ/4 (self resonant at 14.150 MHz) and spaced λ/4 (17 feet 5 inches). In the ideal case, both elements would have the same current amplitude with a 90º phase difference. This gives the cardioid pattern shown in Chapter 8, Multielement Arrays. There are many schemes for correctly feeding such an array. The one used in this example uses two different 75-Ω transmission lines (one λ/4 and the other λ/2, electrically), as described by Roy Lewallen, W7EL.[2,3]

The first task is to resonate the elements individually. With the VNA set to measure S_{11} phase, we will get a graph like that shown in **Fig 70**.

At the λ/4 resonant frequency (f_r) we will see a sharp phase transition as we go from –180° to +180°. This is typical of any series resonant circuit. The length of each element is adjusted until the desired f_r is achieved. This is a very sensitive measurement. You can see the shift in f_r due to the wind blowing, the length of the element changing as it heats up in the sun or any interactions between the feed line and the antenna as you move the feed line around. In fact this is very good point in the process to make sure everything is mechanically stable and free of unexpected couplings. Usually you will find it necessary place choke baluns on each element to reduce stray coupling.



Fig 69—2-element 20-meter phased array (*Photo courtesy N7MQ*).



Fig 70—S_{11} phase plot for an individual element.

The next step is to determine the self (Z_{11} and Z_{22}) and mutual (Z_{12}) impedances from which the actual driving point impedances present when the array is excited can be determined. See Chapter 8, Multielement Arrays. There are two ways to go.

First, we can simply use the VNA as an impedance bridge—ie, make two S_{11} measurements at one element, first with the other element open (Z_{11} or Z_{22}) and then with it shorted (Z_1 or Z_2). We can convert the S_{11} measurements to impedances using Eq 38. The value for Z_{12} can be obtained from Eq 40:

$$\begin{aligned} Z_{12} &= \pm\sqrt{Z_{11}\left(Z_{11}-Z_1\right)} \\ Z_{12} &= \pm\sqrt{Z_{22}\left(Z_{22}-Z_2\right)} \end{aligned} \qquad \text{(Eq 40)}$$

The second approach is to do a full two-port S-parameter measurement (S_{11}, S_{21}, S_{12} and S_{22}) and derive the impedances using Eq 38. Both approaches will work but the second approach has the advantage that the ± ambiguity in Eq 40 is eliminated.

For this example, the impedance values from the measurements at 14.150 MHz, turn out to be:

$$\begin{aligned} Z_{11} &= 51.4 + j\,0.35 \\ Z_{22} &= 50.3 + j\,0.299 \\ Z_{12} &= 15.06 - j\,19.26 \end{aligned} \qquad \text{(Eq 41)}$$

With these values we can now determine the feed-point impedances from:

$$\begin{aligned} Z_1{}' &= Z_{11} + \frac{I_2}{I_1} Z_{12} \\ Z_2{}' &= Z_{22} + \frac{I_1}{I_2} Z_{12} \\ \frac{I_1}{I_2} &= -j \end{aligned} \qquad \text{(Eq 42)}$$

Note that –*j* represents the 90° phase shift between the currents. Substituting the values from Eq 41 into Eq 42:

$$\begin{aligned} Z_1{}' &= 32.09 - j\,14.7 \\ Z_2{}' &= 69.6 + j\,15.32 \end{aligned} \qquad \text{(Eq 43)}$$

With these impedances in hand we can now design the feed network. In this particular example however, we have decided to use the λ/4 and λ/2 cables as described by Lewallen[2,3] and accept the results. So we now proceed to cut and trim the two cables to length.



Fig 71—Current phase and amplitude ratio test setup.

Again, there are two ways to go. First we can determine the frequency at which each cable is λ/4 long. At this point the input impedance of the cable will be equivalent to a series-resonant circuit and we can simply measure the phase of S_{11} as we did earlier for f_r and get a plot like that shown in Fig 70. In this example the λ/4 resonant frequencies of the two cables are 7.075 MHz and 14.150 MHz.

The second approach would be to measure S_{21} for each cable at 14.150 MHz. The phase shift in S_{21} tells you how long the cable is, in degrees, at a given frequency. Because there is a small variation in cable characteristics with frequency (dispersion) this approach is slightly more accurate since it is done at the desired operating frequency. But this is not very large effect at HF.

This brings us down to the final measurements, which are to check that the relative current amplitudes and phases between the two elements are correct. We can then determine the feed-point SWR. The phase and amplitude ratios are made using the S_{12} capability of the VNA and the test setup shown in **Fig 71**.



Fig 72—Measured element current ratio over the 20-meter band.



Fig 73—Measured relative current phase shift over the 20-meter band.

The VNA transmit port is connected to the normal feed point. A current sensor (see Chapter 8, Multielement Arrays, for a discussion of current sensors) is inserted at the base of element 1 and the output of the sensor is returned to the detector or receive port of the VNA. A calibration run is then made to normalize this path. That makes it the reference.

Next, the current sensor is shifted to element 2. The amplitude and phase plots for S_{12} obtained at this point will be the desired relative phase shift and amplitude ratio between the currents in the array when driven at the normal feed point. **Figs 72** and **73** show the behavior of the example array over the 20-meter band. Note that the amplitude ratio has been converted from dB. We can now use these values in a *EZNEC* model of the array to determine the actual radiation pattern.

Obviously the W7EL feed scheme is not perfect, but it has a definite advantage of simplicity. If better performance is desired we can use the values of Z_1' and Z_2' determined earlier to design and fabricate a new feed network and then proceed to evaluate its performance in the same way.

The final measurement is to connect the transmit port of the VNA to the feed point and measure S_{11}. From this we can calculate the SWR:

$$\mathrm{SWR} = \frac{1+|S_{11}|}{1-|S_{11}|} \qquad \text{(Eq 44)}$$

In this example, the return loss, $|S_{11}|$, is about –19 dB over the entire 20-meter band. This corresponds to SWR= 1.25:1.

Notes

[1] Paul Kiciak, N2PK, **http://n2pk.com**.

[2] Roy Lewallen, W7EL, *QST*, Aug 1979, Technical Correspondence, pp 42-43.

[3] Orr and Cowan, *Vertical Antennas*, Radio Amateur Call Book, 1986, pp 148-150.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below.

A. Bailey, “The Antenna Lab, Parts 1 and 2,” *Radio Communication*, Aug and Sep 1983.

L. Blake, *Transmission Lines and Waveguides* (New York: John Wiley & Sons, 1969), pp 244-251.

J. H. Bowen, “A Calorimeter for VHF and UHF Power Measurements, *QST*, Dec 1975, pp 11-13.

W. Bruene, “An Inside Picture of Directional Wattmeters,” *QST*, Apr 1959.

CCIR Recommendation 368, Documents of the CCIR XII Plenary assembly, ITU, Geneva, 1967.

J. Carr, “Find Fault with Your Coax,” *73*, Oct 1984, pp 10-14.

D. DeMaw, “In-Line RF Power Metering,” *QST*, Dec 1969.

D. Fayman, “A Simple Computing SWR Meter,” *QST*, Jul 1973, pp 23-33.

J. Gibbons and H. Horn, “A Circuit With Logarithmic Response Over Nine Decades,” *IEEE Transactions on Circuit Theory*, Vol CT-11, No. 3, Sep 1964, pp 378-384.

J. Grebenkemper, “Calibrating Diode Detectors,” *QEX*, Aug 1990.

J. Grebenkemper, “The Tandem Match—An Accurate Directional Wattmeter,” *QST*, Jan 1987.

J. Grebenkemper, “Improving and Using R-X Noise Bridges,” *QST*, Aug 1989; Feedback, *QST*, Jan 1990, p 27.

G. H. Hagn, SRI, “HF Ground Measurements at the Lawrence Livermore National Laboratory (LLNL) Field Site,” *Applied Computational Electromagnetics Society Journal and Newsletter*, Vol 3, Number 2, Fall 1988.

T. King, “A Practical Time-Domain Reflectometer,” *QST*, May 1989, pp 22-24.

Z. Lau and C. Hutchinson, “Improving the HW-9 Transceiver,” *QST*, Apr 1988, pp 26-29.

V. G. Leenerts, “Automatic VSWR and Power Meter,” *Ham Radio*, May 1980, pp 34-43.

J. Lenk, *Handbook of Oscilloscopes* (Englewood Cliffs, NJ: Prentice-Hall, 1982), pp 288-292.

I. Lindell, E. Alanen, K. Mannerslo, “Exact Image Method for Impedance Computation of Antennas Above the Ground,” *IEEE Trans. On Antennas and Propagation*, AP-33, Sep 1985.

L. McCoy, “A Linear Field-Strength Meter,” *QST*, Jan 1973.

T. McMullen, “The Line Sampler, an RF Power Monitor for VHF and UHF,” *QST*, Apr 1972.

M. Walter Maxwell, W2DU, *Reflections* (Newington: ARRL, 1990), p 20-3. [Out of print.]

C. Michaels, “Determining Line Lengths,” Technical Correspondence, *QST*, Sep 1985, pp 43-44.

H. Perras, “Broadband Power-Tracking VSWR Bridge,” *Ham Radio*, Aug 1979, pp 72-75.

S. Ramo, J. Whinnery and T. Van Duzer, *Fields and Waves in Communication Electronics* (New York: John Wiley & Sons, 1967), Chap 1.

Reference Data for Radio Engineers, 5th edition (Indianapolis: Howard W. Sams, 1968), Chapter 28.

P. N. Saveskie, *Radio Propagation Handbook* (Blue Ridge Summit, PA: TAB Books, 1960).

J. Sevick, “Short Ground-Radial Systems for Short Verticals,” *QST*, Apr 1978, pp 30-33.

J. Sevick, “Measuring Soil Conductivity,” *QST*, Mar 1981, pp 38- 39.

W. Spaulding, “A Broadband Two-Port S-Parameter Test Set,” *Hewlett-Packard Journal*, Nov 1984.

D. Turrin, “Antenna Performance Measurements,” *QST*, Nov 1974, pp 35-41.

F. Van Zant, “High-Power Operation with the Tandem Match Directional Coupler,” Technical Correspondence, *QST*, Jul 1989, pp 42-43.

R. F. H. Yang, “A Proposed Gain Standard for VHF Antennas,” *IEEE Transactions on Antennas and Propagation*, Nov 1966.

Chapter 28

Smith Chart Calculations

The Smith Chart is a sophisticated graphic tool for solving transmission line problems. One of the simpler applications is to determine the feed-point impedance of an antenna, based on an impedance measurement at the input of a random length of transmission line. By using the Smith Chart, the impedance measurement can be made with the antenna in place atop a tower or mast, and there is no need to cut the line to an exact multiple of half wavelengths. The Smith Chart may be used for other purposes, too, such as the design of impedance-matching networks. These matching networks can take on any of several forms, such as L and pi networks, a stub matching system, a series-section match, and more. With a knowledge of the Smith Chart, the amateur can eliminate much "cut and try" work.

Named after its inventor, Phillip H. Smith, the Smith Chart was originally described in *Electronics* for January 1939. Smith Charts may be obtained at most university book stores. Smith Charts are also available from ARRL HQ. (See the caption for Fig 3.)

It is stated in Chapter 24 that the input impedance, or the impedance seen when "looking into" a length of line, is dependent upon the SWR, the length of the line, and the Z_0 of the line. The SWR, in turn, is dependent upon the load which terminates the line. There are complex mathematical relationships which may be used to calculate the various values of impedances, voltages, currents, and SWR values that exist in the operation of a particular transmission line. These equations can be solved with a personal computer and suitable software, or the parameters may be determined with the Smith Chart. Even if a computer is used, a fundamental knowledge of the Smith Chart will promote a better understanding of the problem being solved. And such an understanding might lead to a quicker or simpler solution than otherwise. If the terminating impedance is known, it is a simple matter to determine the input impedance of the line for any length by means of the chart. Conversely, as indicated above, with a given line length and a known (or measured) input impedance, the load impedance may be determined by means of the chart—a convenient method of remotely determining an antenna impedance, for example.

Although its appearance may at first seem somewhat formidable, the Smith Chart is really nothing more than a specialized type of graph. Consider it as having curved, rather than rectangular, coordinate lines. The coordinate system consists simply of two families of circles—the resistance family, and the reactance family. The resistance circles, **Fig 1**, are centered on the resistance axis (the only straight line on the chart), and are tangent to the outer circle at the right of the chart. Each circle is assigned a value of resistance, which is indicated at the point where the circle crosses the resistance axis. All points along any one circle have the same resistance value.

The values assigned to these circles vary from zero at the left of the chart to infinity at the right, and actually represent a *ratio* with respect to the impedance value assigned to the center point of the chart, indicated 1.0. This center point is called prime center. If prime center is assigned a value of 100 Ω, then 200 Ω resistance is represented by the 2.0 circle, 50 Ω by the 0.5 circle, 20 Ω by the 0.2 circle, and so on. If, instead, a value of 50 is assigned to prime center,



Fig 1—Resistance circles of the Smith Chart coordinate system.

the 2.0 circle now represents 100 Ω, the 0.5 circle 25 Ω, and the 0.2 circle 10 Ω. In each case, it may be seen that the value on the chart is determined by dividing the actual resistance by the number assigned to prime center. This process is called normalizing.

Conversely, values from the chart are converted back to actual resistance values by multiplying the chart value times the value assigned to prime center. This feature permits the use of the Smith Chart for any impedance values, and therefore with any type of uniform transmission line, whatever its impedance may be. As mentioned above, specialized versions of the Smith Chart may be obtained with a value of 50 Ω at prime center. These are intended for use with 50-Ω lines.

Now consider the reactance circles, **Fig 2**, which appear as curved lines on the chart because only segments of the complete circles are drawn. These circles are tangent to the resistance axis, which itself is a member of the reactance family (with a radius of infinity). The centers are displaced to the top or bottom on a line tangent to the right of the chart. The large outer circle bounding the coordinate portion of the chart is the reactance axis.

Each reactance circle segment is assigned a value of reactance, indicated near the point where the circle touches the reactance axis. All points along any one segment have the same reactance value. As with the resistance circles, the values assigned to each reactance circle are normalized with respect to the value assigned to prime center. Values to the top of the resistance axis are positive (inductive), and those to the bottom of the resistance axis are negative (capacitive).

When the resistance family and the reactance family of circles are combined, the coordinate system of the Smith Chart results, as shown in **Fig 3**. Complex impedances (R + *j*X) can be plotted on this coordinate system.



Fig 2—Reactance circles (segments) of the Smith Chart coordinate system.

IMPEDANCE PLOTTING

Suppose we have an impedance consisting of 50 Ω resistance and 100 Ω inductive reactance (Z = 50 + *j* 100). If we assign a value of 100 Ω to prime center, we normalize the above impedance by dividing each component of the impedance by 100. The normalized impedance is then 50/100 + *j* (100/100) = 0.5 + *j* 1.0. This impedance is plotted on the Smith Chart at the intersection of the 0.5 resistance circle and the +1.0 reactance circle, as indicated in Fig 3. Calculations may now be made from this plotted value.

Now say that instead of assigning 100 Ω to prime center, we assign a value of 50 Ω. With this assignment, the 50 + *j* 100 Ω impedance is plotted at the intersection of the 50/50 = 1.0 resistance circle, and the 100/50 = 2.0 positive reactance circle. This value, 1 + *j* 2, is also indicated in Fig 3. But now we have *two* points plotted in Fig 3 to represent the same impedance value, 50 + *j* 100 Ω. How can this be?

These examples show that the same impedance may be plotted at different points on the chart, depending upon the value assigned to prime center. But two plotted points cannot represent the same impedance *at the same time*! It is customary when solving transmission-line problems to assign to prime center a value equal to the characteristic impedance, or Z_0, of the line being used. This value should always be recorded at the start of calculations, to avoid possible confusion later. (In using the specialized charts with the value of 50 at prime center, it is, of course, not necessary to normalize impedances when working with 50-Ω line. The resistance and reactance values may be read directly from the chart coordinate system.)

Prime center is a point of special significance. As



Fig 3—The complete coordinate system of the Smith Chart. For simplicity, only a few divisions are shown for the resistance and reactance values. Various types of Smith Chart forms are available from ARRL HQ. At the time of this writing, five $8^1/_2$ × 11 inch Smith Chart forms are available for $2.

just mentioned, is is customary when solving problems to assign the Z_0 value of the line to this point on the chart—50 Ω for a 50-Ω line, for example. What this means is that the center point of the chart now represents 50 +*j* 0 ohms–a pure resistance equal to the characteristic impedance of the line. If this were a load on the line, we recognize from transmission-line theory that it represents a perfect match, with no reflected power and with a 1.0 to 1 SWR. Thus, prime center also represents the 1.0 SWR circle (with a radius of zero). SWR circles are also discussed in a later section.

Short and Open Circuits

On the subject of plotting impedances, two special cases deserve consideration. These are short circuits and open circuits. A true short circuit has zero resistance and zero reactance, or 0 + *j* 0). This impedance is plotted at the left of the chart, at the intersection of the resistance and the reactance axes. By contrast, an open circuit has infinite resistance, and therefore is plotted at the right of the chart, at the intersection of the resistance and reactance axes. These two special cases are sometimes used in matching stubs, described later.

Standing-Wave-Ratio Circles

Members of a third family of circles, which are not printed on the chart but which are added during the process of solving problems, are standing-wave-ratio or SWR circles. See **Fig 4**. This family is centered on prime center, and appears as concentric circles inside the reactance axis. During calculations, one or more of these circles may be added with a drawing compass. Each circle represents a value of SWR, with every point on a given circle representing the same SWR. The SWR value for a given circle may be determined directly from the chart coordinate system, by reading the resistance value where the SWR circle crosses the resistance axis to the right of prime center. (The reading where the circle crosses the resistance axis to the left of prime center indicates the inverse ratio.)

Consider the situation where a load mismatch in a length of line causes a 3-to-1 SWR ratio to exist. If we temporarily disregard line losses, we may state that the SWR remains constant throughout the entire length of this line. This is represented on the Smith Chart by drawing a 3:1 constant SWR circle (a circle with a radius of 3 on the resistance axis), as in **Fig 5**. The design of the chart is such that any impedance encountered *anywhere* along the length of this mismatched line will fall on the SWR circle. The impedances may be read from the coordinate system merely by the progressing around the SWR circle by an amount corresponding to the length of the line involved.

This brings into use the wavelength scales, which appear in Fig 5 near the perimeter of the Smith Chart. These scales are calibrated in terms of portions of an electrical wavelength along a transmission line. Both scales start from 0 at the left of the chart. One scale, running



Fig 4—Smith Chart with SWR circles added.



Fig 5—Example discussed in text.

counterclockwise, starts at the generator or input end of the line and progresses toward the load. The other scale starts at the load and proceeds toward the generator in a clockwise direction. The complete circle around the edge of the chart represents $^1/_2$ λ. Progressing once around the perimeter of these scales corresponds to progressing along a transmission line for $^1/_2$ λ. Because impedances repeat themselves every $^1/_2$ λ along a piece of line, the chart may be used for any length of line by disregarding or subtracting from the line's total length an integral, or whole number, of half wavelengths.

Also shown in Fig 5 is a means of transferring the radius of the SWR circle to the external scales of the chart, by drawing lines tangent to the circle. Another simple way to obtain information from these external scales is to transfer the radius of the SWR circle to the external scale with a drawing compass. Place the point of a drawing compass at the center or 0 line, and inscribe a short arc across the appropriate scale. It will be noted that when this is done in Fig 5, the external STANDING-WAVE VOLTAGE-RATIO scale indicates the SWR to be 3.0 (at A)—our condition for initially drawing the circle on the chart (and the same as the SWR reading on the resistance axis).

SOLVING PROBLEMS WITH THE SMITH CHART

Suppose we have a transmission line with a characteristic impedance of 50 Ω and an electrical length of 0.3 λ. Also, suppose we terminate this line with an impedance having a resistive component of 25 Ω and an inductive reactance of 25 Ω (Z = 25 + *j* 25). What is the input impedance to the line?

The characteristic impedance of the line is 50 Ω, so we begin by assigning this value to prime center. Because the line is not terminated in its characteristic impedance, we know that standing waves will exist on the line, and that, therefore, the input impedance to the line will not be exactly 50 Ω. We proceed as follows. First, normalize the load impedance by dividing both the resistive and reactive components by 50 (Z_0 of the line being used). The normalized impedance in this case is 0.5 + *j* 0.5. This is plotted on the chart at the intersection of the 0.5 resistance and the +0.5 reactance circles, as in **Fig 6**. Then draw a constant SWR circle passing through this point. Transfer the radius of this circle to the external scales with the drawing compass. From the external STANDING-WAVE VOLTAGE-RATIO scale, it may be seen (at A) that the voltage ratio of 2.62 exists for this radius, indicating that our line is operating with an SWR of 2.62 to 1. This figure is converted to decibels in the adjacent scale, where 8.4 dB may be read (at B), indicating that the ratio of the voltage maximum to the voltage minimum along the line is 8.4 dB. (This is mathematically equivalent to 20 times the log of the SWR value.)

Next, with a straightedge, draw a radial line from prime center through the plotted point to intersect the wavelengths scale. At this intersection, point C in Fig 6, read a value from the wavelengths scale. Because we are starting from the load, we use the TOWARD GENERATOR or outermost calibration, and read 0.088 λ.

To obtain the line input impedance, we merely find the point on the SWR circle that is 0.3 λ toward the generator from the plotted load impedance. This is accomplished by adding 0.3 (the length of the line in wavelengths) to the reference or starting point, 0.088; 0.3 + 0.088 = 0.388. Locate 0.388 on the TOWARD GENERATOR scale (at D). Draw a second radial line from this point to prime center. The intersection of the new radial line with the SWR circle represents the normalized line input impedance, in this case 0.6 – *j* 0.66.

To find the unnormalized line impedance, multiply by 50, the value assigned to prime center. The resulting value is 30 – *j* 33, or 30 Ω resistance and 33 Ω capacitive reactance. *This* is the impedance that a transmitter must match if such a system were a combination of antenna



Fig 6—Example discussed in text.

and transmission line. This is also the impedance that would be measured on an impedance bridge if the measurement were taken at the line input.

In addition to the line input impedance and the SWR, the chart reveals several other operating characteristics of the above system of line and load, if a closer look is desired. For example, the voltage reflection coefficient, both magnitude and phase angle, for this particular load is given. The phase angle is read under the radial line drawn through the plot of the load impedance, where the line intersects the ANGLE OF REFLECTION COEFFICIENT scale. This scale is not included in Fig 6, but will be found on the Smith Chart just inside the wavelengths scales. In this example, the reading is 116.6 degrees. This indicates the angle by which the reflected voltage wave leads the incident wave at the load. It will be noted that angles on the bottom half, or capacitive-reactance half, of the chart are negative angles, a "negative" lead indicating that the reflected voltage wave actually lags the incident wave.

The magnitude of the voltage-reflection-coefficient may be read from the external REFLECTION COEFFICIENT VOLTAGE scale, and is seen to be approximately 0.45 (at E) for this example. This means that 45 percent of the incident voltage is reflected. Adjacent to this scale on the POWER calibration, it is noted (at F) that the power reflection coefficient is 0.20, indicating that 20 percent of the incident power is reflected. (The amount of reflected power is proportional to the square of the reflected voltage.)

ADMITTANCE COORDINATES

Quite often it is desirable to convert impedance information to admittance data—conductance and susceptance. Working with admittances greatly simplifies determining the resultant when two complex impedances are connected in parallel, as in stub matching. The conductance values may be added directly, as may be the susceptance values, to arrive at the overall admittance for the parallel combination. This admittance may then be converted back to impedance data, if desired.

On the Smith Chart, the necessary conversion may be made very simply. The equivalent admittance of a plotted impedance value lies diametrically opposite the impedance point on the chart. In other words, an impedance plot and its corresponding admittance plot will lie on a straight line that passes through prime center, and each point will be the same distance from prime center (on the same SWR circle). In the above example, where the normalized line input impedance is 0.6 – *j* 0.66, the equivalent admittance lies at the intersection of the SWR circle and the extension of the straight line passing from point D though prime center. Although not shown in Fig 6, the normalized admittance value may be read as 0.76 + *j* 0.84 if the line starting at D is extended.

In making impedance-admittance conversions, remember that capacitance is considered to be a positive susceptance and inductance a negative susceptance. This corresponds to the scale identification printed on the chart. The admittance in siemens is determined by dividing the normalized values by the Z_0 of the line. For this example the admittance is 0.76/50 + *j* 0.84/50 = 0.0152 + *j* 0.0168 siemen. Of course admittance coordinates may be converted to impedance coordinates just as easily—by locating the point on the Smith Chart that is diametrically opposite that representing the admittance coordinates, on the same SWR circle.

DETERMINING ANTENNA IMPEDANCES

To determine an antenna impedance from the Smith Chart, the procedure is similar to the previous example. The electrical length of the feed line must be known and the impedance value at the input end of the line must be determined through measurement, such as with an impedance-measuring or a good quality noise bridge. In this case, the antenna is connected to the far end of the line and becomes the load for the line. Whether the


WAVELENGTHS TOWARDS GENERATOR
WAVELENGTHS TOWARD LOAD
INDUCTIVE REACTANCE COMPONENT OR CAPACITIVE SUSCEPTANCE
RESISTANCE COMPONENT OR CONDUCTANCE
CAPACITIVE REACTANCE COMPONENT OR INDUCTIVE SUSCEPTANCE
Load (Antenna)
0.62-j0.19
1.4-j0.5
Input
C
B
RADIALLY SCALED PARAMETERS
TOWARD GENERATOR
TOWARD LOAD
STANDING WAVE VOLT RATIO
IN DB
TRANS LOSS 1 DB STEPS
LOSS COEFF
REFLECTION COEFF VOLT
PWR
RETN LOSS IN DB
REFL
CENTER
A

Fig 7—Example discussed in text.

antenna is intended purely for transmission of energy, or purely for reception makes no difference; the antenna is still the terminating or load impedance on the line as far as these measurements are concerned. The input or generator end of the line is that end connected to the device for measurement of the impedance. In this type of problem, the measured impedance is plotted on the chart, and the TOWARD LOAD wavelengths scale is used in conjunction with the electrical line length to determine the actual antenna impedance.

For example, assume we have a measured input impedance to a 50-Ω line of $70 - j\,25$ Ω. The line is 2.35 λ long, and is terminated in an antenna. What is the antenna feed impedance? Normalize the input impedance with respect to 50 Ω, which comes out $1.4 - j\,0.5$, and plot this value on the chart. See **Fig 7**. Draw a constant SWR circle through the point, and transfer the radius to the external scales. The SWR of 1.7 may be read from the VOLTAGE RATIO scale (at A). Now draw a radial line from prime center through this plotted point to the wavelengths scale, and read a reference value (at B). For this case the value is 0.195, on the TOWARD LOAD scale. Remember, we are starting at the generator end of the transmission line.

To locate the load impedance on the SWR circle, add the line length, 2.35 λ, to the reference value from the wavelengths scale; 2.35 + 0.195 = 2.545. Locate the new value on the TOWARD LOAD scale. But because the calibrations extend only from 0 to 0.5, we must first subtract a number of half wavelengths from this value and use only the remaining value. In this situation, the largest integral number of half wavelengths that can be subtracted with a positive result is 5, or 2.5 λ. Thus, 2.545 – 2.5 = 0.045. Locate the 0.045 value on the TOWARD LOAD scale (at C). Draw a radial line from this value to prime center. Now, the coordinates at the intersection of the second radial line and the SWR circle represent the load impedance. To read this value closely, some interpolation between the printed coordinate lines must be made, and the value of $0.62 - j\,0.19$ is read. Multiplying by 50, we get the actual load or antenna impedance as $31 - j\,9.5$ Ω, or 31 Ω resistance with 9.5 Ω capacitive reactance.

Problems may be entered on the chart in yet another manner. Suppose we have a length of 50-Ω line feeding a base-loaded resonant vertical ground-plane antenna which is shorter than $^1/_4$ λ. Further, suppose we have an SWR monitor in the line, and that it indicates an SWR of 1.7 to 1. The line is known to be 0.95 λ long. We want to know both the input and the antenna impedances.

From the information available, we have no impedances to enter into the chart. We may, however, draw a circle representing the 1.7 SWR. We also know, from the definition of resonance, that the antenna presents a purely resistive load to the line, that is, no reactive component. Thus, the antenna impedance must lie on the resistance axis. If we were to draw such an SWR circle and observe the chart with only the circle drawn, we would see two points which satisfy the resonance requirement for the load. These points are $0.59 + j\,0$ and $1.7 + j\,0$. Multiplying by 50, we see that these values represent 29.5 and 85 Ω resistance. This may sound familiar, because, as was discussed in Chapter 24, when a line is terminated in a pure resistance, the SWR in the line equals Z_R/Z_0 or Z_0/Z_R, where Z_R=load resistance and Z_0=line impedance.

If we consider antenna fundamentals described in Chapter 2, we know that the theoretical impedance of a $^1/_4$-λ ground-plane antenna is approximately 36 Ω. We therefore can quite logically discard the 85-Ω impedance figure in favor of the 29.5-Ω value. This is then taken as the load impedance value for the Smith Chart calculations. To find the line input impedance, we subtract 0.5 λ from the line length, 0.95, and find 0.45 λ on the TOWARD GENERATOR scale. (The wavelength-scale starting point in this case is 0.) The line input impedance is found to be $0.63 - j\,0.20$, or $31.5 - j\,10$ Ω.

DETERMINATION OF LINE LENGTH

In the example problems given so far in this chapter, the line length has conveniently been stated in wavelengths. The electrical length of a piece of line depends upon its physical length, the radio frequency under consideration, and the velocity of propagation in the line. If an impedance-measurement bridge is capable of quite reliable readings at high SWR values, the line length may be determined through line input-impedance measurements with short- or open-circuit line terminations. Information on the procedure is given later in this chapter. A more direct method is to measure the physical length of the line and calculate its electrical length from

$$N = \frac{Lf}{984VF} \qquad \text{(Eq 1)}$$

where

N = number of electrical wavelengths in the line
L = line length in feet
f = frequency, MHz
VF = velocity or propagation factor of the line

The velocity factor may be obtained from transmission-line data tables in Chapter 24.


Load
6+j0
Input
0.31-j0.36
RESISTANCE COMPONENT R OR CONDUCTANCE G
INDUCTIVE REACTANCE COMPONENT
OR CAPACITIVE SUSCEPTANCE
CAPACITIVE REACTANCE COMPONENT
OR INDUCTIVE SUSCEPTANCE
WAVELENGTHS TOWARDS GENERATOR
WAVELENGTHS TOWARD LOAD

Fig 8—This spiral is the actual "SWR circle" when line losses are taken into account. It is based on calculations for a 16-ft length of RG-174 coax feeding a resonant 28-MHz 300-Ω antenna (50-Ω coax, velocity factor = 66%, attenuation = 6.2 dB per 100 ft). The SWR at the load is 6:1, while it is 3.6:1 at the line input. When solving problems involving attenuation, two constant SWR circles are drawn instead of a spiral, one for the line input SWR and one for the load SWR.


E
1.2+j0.7
0.65-j0.6
F
K
J
RADIALLY SCALED PARAMETERS
TOWARD GENERATOR
TOWARD LOAD
A
B
C
H
G
I
D
CENTER
TRANS LOSS
STANDING WAVE
REFLECTION

Fig 9—Example of Smith Chart calculations taking line losses into account.

LINE-LOSS CONSIDERATIONS WITH THE SMITH CHART

The example Smith Chart problems presented in the previous section ignored attenuation, or line losses. Quite frequently it is not even necessary to consider losses when making calculations; any difference in readings obtained are often imperceptible on the chart. However, when the line losses become appreciable, such as for high-loss lines, long lines, or at VHF and UHF, loss considerations may become significant in making Smith Chart calculations. This involves only one simple step, in addition to the procedures previously presented.

Because of line losses, as discussed in Chapter 24 the SWR does not remain constant throughout the length of the line. As a result, there is a decrease in SWR as one progresses away from the load. To truly present this situation on the Smith Chart, instead of drawing a constant SWR circle, it would be necessary to draw a spiral inward and clockwise from the load impedance toward the generator, as shown in **Fig 8**. The rate at which the curve spirals toward prime center is related to the attenuation in the line. Rather than drawing spiral curves, a simpler method is used in solving line-loss problems, by means of the external scale TRANSMISSION LOSS 1-DB STEPS. This scale may be seen in **Fig 9**. Because this is only a relative scale, the decibel steps are not numbered.

If we start at the left end of this external scale and proceed in the direction indicated TOWARD GENERATOR, the first dB step is seen to occur at a radius from center corresponding to an SWR of about 9 (at A); the second dB step falls at an SWR of about 4.5 (at B), the third at 3.0 (at C), and so forth, until the

15th dB step falls at an SWR of about 1.05 to 1. This means that a line terminated in a short or open circuit (infinite SWR), and having an attenuation of 15 dB, would exhibit an SWR of only 1.05 at its input. It will be noted that the dB steps near the right end of the scale are very close together, and a line attenuation of 1 or 2 dB in this area will have only slight effect on the SWR. But near the left end of the scale, corresponding to high SWR values, a 1 or 2 dB loss has considerable effect on the SWR.

Using a Second SWR Circle

In solving a problem using line-loss information, it is necessary only to modify the radius of the SWR circle by an amount indicated on the TRANSMISSION-LOSS 1-DB STEPS scale. This is accomplished by drawing a second SWR circle, either smaller or larger than the first, depending on whether you are working toward the load or toward the generator.

For example, assume that we have a 50-Ω line that is 0.282 λ long, with 1-dB inherent attenuation. The line input impedance is measured as 60 + *j* 35 Ω. We desire to know the SWR at the input and at the load, and the load impedance. As before, we normalize the 60 + *j* 35-Ω impedance, plot it on the chart, and draw a constant SWR circle and a radial line through the point. In this case, the normalized impedance is 1.2 + *j* 0.7. From Fig 9, the SWR at the line input is seen to be 1.9 (at D), and the radial line is seen to cross the TOWARD LOAD scale, first subtract 0.500, and locate 0.110 (at F); then draw a radial line from this point to prime center.

To account for line losses, transfer the radius of the SWR circle to the external 1-DB STEPS scale. This radius crosses the external scale at G, the fifth decibel mark from the left. Since the line loss was given as 1 dB, we strike a new radius (at H), one "tick mark" to the left (toward load) on the same scale. (This will be the fourth decibel tick mark from the left of the scale.) Now transfer this new radius back to the main chart, and scribe a new SWR circle of this radius. This new radius represents the SWR at the load, and is read as 2.3 on the external VOLTAGE RATIO scale. At the intersection of the new circle and the load radial line, we read 0.65 – *j* 0.6. This is the normalized load impedance. Multiplying by 50, we obtain the actual load impedance as 32.5 – *j* 30 Ω. The SWR in this problem was seen to increase from 1.9 at the line input to 2.3 (at I) at the load, with the 1-dB line loss taken into consideration.

In the example above, values were chosen to fall conveniently on or very near the "tick marks" on the 1-dB scale. Actually, it is a simple matter to interpolate between these marks when making a radius correction. When this is necessary, the relative distance between marks for each decibel step should be maintained while counting off the proper number of steps.

Adjacent to the 1-DB STEPS scale lies a LOSS COEFFICIENT scale. This scale provides a factor by which the matched-line loss in decibels should be multiplied to account for the increased losses in the line when standing waves are present. These added losses do not affect the SWR or impedance calculations; they are merely the additional dielectric copper losses of the line caused by the fact that the line conducts more average voltage in the presence of standing waves. For the above example, from Fig 9, the loss coefficient at the input end is seen to be 1.21 (at J), and 1.39 (at K) at the load. As a good approximation, the loss coefficient may be averaged over the length of line under consideration; in this case, the average is 1.3. This means that the total losses in the line are 1.3 times the matched loss of the line (1 dB), or 1.3 dB. This is the same result that may be obtained from procedures given in Chapter 24 for this data.

Smith Chart Procedure Summary

To summarize briefly, any calculations made on the Smith Chart are performed in four basic steps, although not necessarily in the order listed.

1) Normalize and plot a line input (or load) impedance, and construct a constant SWR circle.
2) Apply the line length to the wavelengths scales.
3) Determine attenuation or loss, if required, by means of a second SWR circle.
4) Read normalized load (or input) impedance, and convert to impedance in ohms.

The Smith Chart may be used for many types of problems other than those presented as examples here. The transformer action of a length of line—to transform a high impedance (with perhaps high reactance) to a purely resistive impedance of low value—was not mentioned. This is known as "tuning the line," for which the chart is very helpful, eliminating the need for "cut and try" procedures. The chart may also be used to calculate lengths for shorted or open matching stubs in a system, described later in this chapter. In fact, in any application where a transmission line is not perfectly matched, the Smith Chart can be of value.

ATTENUATION AND Z_0 FROM IMPEDANCE MEASUREMENTS

If an impedance bridge is available to make accurate measurements in the presence of very high SWR values, the attenuation, characteristic impedance and velocity factor of any random length of coaxial transmission line can be determined. This section was written by Jerry Hall, K1TD.

Homemade impedance bridges and noise bridges will seldom offer the degree of accuracy required to use this technique, but sometimes laboratory bridges can be found as industrial surplus at a reasonable price. It may also be possible for an amateur to borrow a laboratory type of bridge for the purpose of making some weekend measurements. Making these determinations is not difficult, but the procedure is not commonly known among amateurs. One equation treating complex numbers is used, but the math can be handled with a calculator supporting trig functions. Full details are given in the paragraphs that follow.

For each frequency of interest, two measurements are required to determine the line impedance. Just one measurement is used to determine the line attenuation and velocity factor. As an example, assume we have a 100-foot length of unidentified line with foamed dielectric, and wish to know its characteristics. We make our measurements at 7.15 MHz. The procedure is as follows.

1) Terminate the line in an open circuit. The best "open circuit" is one that minimizes the capacitance between the center conductor and the shield. If the cable has a PL-259 connector, unscrew the shell and slide it back down the coax for a few inches. If the jacket and insulation have been removed from the end, fold the braid back along the outside of the line, away from the center conductor.
2) Measure and record the impedance at the input end of the line. If the bridge measures admittance, convert the measured values to resistance and reactance. Label the values as $R_{oc} + j\,X_{oc}$. For our example, assume we measure 85 + *j*179 Ω. (If the reactance term is capacitive, record it as negative.)
3) Now terminate the line in a short circuit. If a connector exists at the far end of the line, a simple short is a mating connector with a very short piece of heavy wire soldered between the center pin and the body. If the coax has no connector, removing the jacket and center insulation from a half inch or so at the end will allow you to tightly twist the braid around the center conductor. A small clamp or alligator clip around the outer braid at the twist will keep it tight.
4) Again measure and record the impedance at the input end of the line. This time label the values as $R_{sc} \pm j\,X$. Assume the measured value now is $4.8 - j\,11.2$ Ω.

This completes the measurements. Now we reach for the calculator.

As amateurs we normally assume that the characteristic impedance of a line is purely resistive, but it can (and does) have a small capacitive reactance component. Thus, the Z_0 of a line actually consists of $R_0 + j\,X_0$. The basic equation for calculating the characteristic impedance is

$$Z_0 = \sqrt{Z_{oc} \times Z_{sc}} \qquad \text{(Eq 2)}$$

where

$Z_{oc} = R_{oc} + jX_{oc}$

$Z_{sc} = R_{sc} + jX_{sc}$

From Eq 2 the following working equation may be derived.

$$Z_0 = \sqrt{\left(R_{oc}R_{sc} - X_{oc}X_{sc}\right) + j\left(R_{oc}X_{sc} + R_{sc}X_{oc}\right)} \qquad \text{(Eq 3)}$$

The expression under the radical sign in Eq 3 is in the form of R + *j* X. By substituting the values from our example into Eq 3, the R term becomes 85 × 4.8 – 179 × (–11.2) = 2412.8, and the X term becomes 85 × (–11.2) + 4.8 × 179 = –92.8. So far, we have determined that

$$Z_0 = \sqrt{2412.8 - j\,92.8}$$

The quantity under the radical sign is in rectangular form. Extracting the square root of a complex term is handled easily if it is in polar form, a vector value and its angle. The vector value is simply the square root of the sum of the squares, which in this case is

$$\sqrt{2412.8^2 + 92.8^2} = \sqrt{2414.58}$$

The tangent of the vector angle we are seeking is the value of the reactance term divided by the value of the resistance term. For our example this is arctan –92.8/2412.8 = arctan –0.03846. The angle is thus found to be –2.20°. From all of this we have determined that

$$Z_0 = \sqrt{2414.58\,\underline{/-2.20^\circ}}$$

Extracting the square root is now simply a matter of finding



Fig 10—Determining the line loss and velocity factor with the Smith Chart from input measurements taken with open-circuit and short-circuit terminations.

the square root of the vector value, and taking half the angle. (The angle is treated mathematically as an exponent.)

Our result for this example is $Z_0 = 49.1\underline{/-1.1°}$. The small negative angle may be ignored, and we now know that we have coax with a nominal 50-Ω impedance. (Departures of as much as 6 to 8% from the nominal value are not uncommon.) If the negative angle is large, or if the angle is positive, you should recheck your calculations and perhaps even recheck the original measurements. You can get an idea of the validity of the measurements by normalizing the measured values to the calculated impedance and plotting them on a Smith Chart as shown in **Fig 10** for this example. Ideally, the two points should be diametrically opposite, but in practice they will be not quite 180° apart and not quite the same distance from prime center. Careful measurements will yield plotted points that are close to ideal. Significant departures from the ideal indicates sloppy measurements, or perhaps an impedance bridge that is not up to the task.

Determining Line Attenuation

The short circuit measurement may be used to determine the line attenuation. This reading is more reliable than the open circuit measurement because a good short circuit is a short, while a good open circuit is hard to find. (It is impossible to escape some amount of capacitance between conductors with an "open" circuit, and that capacitance presents a path for current to flow at the RF measurement frequency.)

Use the Smith Chart and the 1-DB STEPS external scale to find line attenuation. First normalize the short circuit impedance reading to the calculated Z_0, and plot this point on the chart. See Fig 10. For our example, the normalized impedance is 4.8/49.1 – *j* 11.2 / 49.1 or 0.098 – *j* 0.228. After plotting the point, transfer the radius to the 1-DB STEPS scale. This is shown at A of Fig 10.

Remember from discussions earlier in this chapter that the impedance for plotting a short circuit is 0 + *j* 0, at the left edge of the chart on the resistance axis. On the 1-DB STEPS scale this is also at the left edge. The total attenuation in the line is represented by the number of dB steps from the left edge to the radius mark we have just transferred. For this example it is 0.8 dB. Some estimation may be required in interpolating between the 1-dB step marks.

Determining Velocity Factor

The velocity factor is determined by using the TOWARD GENERATOR wavelength scale of the Smith Chart. With a straightedge, draw a line from prime center through the point representing the short-circuit reading, until it intersects the wavelengths scale. In Fig 10 this point is labeled B. Consider that during our measurement, the short circuit was the load at the end of the line. Imagine a spiral curve progressing from 0 + *j* 0 clockwise and inward to our plotted measurement point. The wavelength scale, at B, indicates this line length is 0.464 λ. By rearranging the terms of Eq 1 given early in this chapter, we arrive at an equation for calculating the velocity factor.

$$VF = \frac{Lf}{984N} \qquad \text{(Eq 4)}$$

where

VF = velocity factor
L = line length, feet
f = frequency, MHz
N = number of electrical wavelengths in the line

Inserting the example values into Eq 4 yields VF = 100 × 7.15/(984 × 0.464) = 1.566, or 156.6%. Of course, this value is an impossible number—the velocity factor in coax cannot be greater than 100%. But remember, the Smith Chart can be used for lengths greater than ½ λ. Therefore, that 0.464 value could rightly be 0.964, 1.464, 1.964, and so on. When using 0.964 λ, Eq 4 yields a velocity factor of 0.753, or 75.3%. Trying successively greater values for the wavelength results in velocity factors of 49.6 and 37.0%. Because the cable we measured had foamed dielectric, 75.3% is the probable velocity factor. This corresponds to an electrical length of 0.964 λ. Therefore, we have determined from the measurements and


ℓ1
ℓ3
0+j2.4
0-j0.41
B
ℓ2
WAVELENGTHS TOWARDS GENERATOR
WAVELENGTHS TOWARD LOAD
INDUCTIVE REACTANCE COMPONENT
OR CAPACITIVE SUSCEPTANCE
RESISTANCE COMPONENT OR CONDUCTANCE
INDUCTIVE SUSCEPTANCE
CAPACITIVE REACTANCE COMPONENT

Fig 11—Smith Chart determination of input impedances for short- and open-circuited line sections, disregarding line losses.

calculations that our unmarked coax has a nominal 50-Ω impedance, an attenuation of 0.8 dB per hundred feet at 7.15 MHz, and a velocity factor of 75.3%.

It is difficult to use this procedure with short lengths of coax, just a few feet. The reason is that the SWR at the line input is too high to permit accurate measurements with most impedance bridges. In the example above, the SWR at the line input is approximately 12:1.

The procedure described above may also be used for determining the characteristics of balanced lines. However, impedance bridges are generally unbalanced devices, and the procedure for measuring a balanced impedance accurately with an unbalanced bridge is complicated.



Fig 12—The method of stub matching a mismatched load on coaxial lines.



Fig 13—Smith Chart method of determining the dimensions for stub matching.

LINES AS CIRCUIT ELEMENTS

Information is presented in Chapter 24 on the use of transmission-line sections as circuit elements. For example, it is possible to substitute transmission lines of the proper length and termination for coils or capacitors in ordinary circuits. While there is seldom a practical need for that application, lines are frequently used in antenna systems in place of lumped components to tune or resonate elements. Probably the most common use of such a line is in the hairpin match, where a short section of stiff open-wire line acts as a lumped inductor.

The equivalent "lumped" value for any "inductor" or "capacitor" may be determined with the aid of the Smith Chart. Line losses may be taken into account if desired, as explained earlier. See **Fig 11**. Remember that the top half of the Smith Chart coordinate system is used for impedances containing inductive reactances, and the bottom half for capacitive reactances. For example, a section of 600-Ω line $^{3}/_{16}$-λ long (0.1875 λ) and short-circuited at the far end is represented by $\ell 1$, drawn around a portion of the perimeter of the chart. The "load" is a short-circuit, $0 + j\,0$ Ω, and the TOWARD GENERATOR wavelengths scale is used for marking off the line length. At A in Fig 11 may be read the normalized impedance as seen looking into the length of line, $0 + j\,2.4$. The reactance is therefore inductive, equal to 600 × 2.4 = 1440 Ω. The same line when open-circuited (termination impedance = ∞, the point at the right of the chart) is represented by $\ell 2$ in Fig 11. At B the normalized line-input impedance may be read as $0 - j\,0.41$; the reactance in this case is capacitive, 600 × 0.41 = 246 Ω. (Line losses are disregarded in these examples.) From Fig 11 it is easy to visualize that if $\ell 1$ were to be extended by $^{1}/_{4}$ λ, the total length represented by $\ell 3$, the line-input impedance would be identical to that obtained in the case represented by $\ell 2$ alone. In the case of $\ell 2$, the line is open-circuited at the far end, but in the case of $\ell 3$ the line is terminated in a short. The added section of line for $\ell 3$ provides the "transformer action" for which the $^{1}/_{4}$-λ line is noted.

The equivalent inductance and capacitance as determined above can be found by substituting these values in the equations relating inductance and capacitance to reactance, or by using the various charts and calculators available. The frequency corresponding to the line length in degrees must be used, of course. In this example, if the frequency is 14 MHz the equivalent inductance and capacitance in the two cases are 16.4 µH and 46.2 pF, respectively. Note that when the line length is 45° (0.125 λ), the reactance in either case is numerically equal to the characteristic impedance of the line. In using the Smith Chart it should be kept in mind that the electrical length of a line section depends on the frequency and velocity of propagation, as well as on the actual physical length.

At lengths of line that are exact multiples of $^1/_4$ λ, such lines have the properties of resonant circuits. At lengths where the input reactance passes through zero at the left of the Smith Chart, the line acts as a series-resonant circuit. At lengths for which the reactances theoretically pass from "positive" to "negative" infinity at the right of the Smith Chart, the line simulates a parallel-resonant circuit.

Designing Stub Matches with the Smith Chart

The design of stub matches is covered in detail in Chapter 26. Equations are presented there to calculate the electrical lengths of the main line and the stub, based on a purely resistive load and on the stub being the same type of line as the main line. The Smith Chart may also be used to determine these lengths, without the requirements that the load be purely resistive and that the line types be identical.

Fig 12 shows the stub matching arrangement in coaxial line. As an example, suppose that the load is an antenna, a close-spaced array fed with a 52-Ω line. Further suppose that the SWR has been measured as 3.1:1. From this information, a constant SWR circle may be drawn on the Smith Chart. Its radius is such that it intersects the right portion of the resistance axis at the SWR value, 3.1, as shown at point B in **Fig 13**.

Since the stub of Fig 12 is connected in parallel with the transmission line, determining the design of the matching arrangement is simplified if Smith Chart values are dealt with as admittances, rather than impedances. (An admittance is simply the reciprocal of the associated impedance. Plotted on the Smith Chart, the two associated points are on the same SWR circle, but diametrically opposite each other.) Using admittances leaves less chance for errors in making calculations, by eliminating the need for making series-equivalent to parallel-equivalent circuit conversions and back, or else for using complicated equations for determining the resultant value of two complex impedances connected in parallel.

A complex impedance, Z, is equal to R + *j* X, as described in Chapter 24. The equivalent admittance, Y, is equal to G – *j* B, where G is the conductive component and B the susceptance. (Inductance is taken as negative susceptance, and capacitance as positive.) Conductance and susceptance values are plotted and handled on the Smith Chart in the same manner as resistance and reactance.

Assuming that the close-spaced array of our example has been resonated at the operating frequency, it will present a purely resistive termination for the load end of the 52-Ω line. From information in Chapter 24, it is known that the impedance of the antenna equals Z_0/SWR = 52/3.1 = 16.8 Ω. (We can logically discard the possibility that the antenna impedance is SWR × Z_0, or 0.06 Ω.) If this 16.8-Ω value were to be plotted as an impedance on the Smith Chart, it would first be normalized (16.8/52 = 0.32) and then plotted as 0.32 + *j* 0. Although not necessary for the solution of this example, this value is plotted at point A in Fig 13. What is necessary is a plot of the admittance for the antenna as a load. This is the reciprocal of the impedance; 1/16.8 Ω equals 0.060 siemen. To plot this point it is first normalized by multiplying the conductance and susceptance values by the Z_0 of the line. Thus, (0.060 + *j* 0) × 52 = 3.1 + *j* 0. This admittance value is shown plotted at point B in Fig 13. It may be seen that points A and B are diametrically opposite each other on the chart. Actually, for the solution of this example, it wasn't necessary to compute the values for either point A or point B as in the above paragraph, for they were both determined from the known SWR value of 3.1. As may be seen in Fig 13, the points are located on the constant SWR circle which was already drawn, at the two places where it intersects the resistance axis. The plotted value for point A, 0.32, is simply the reciprocal of the value for point B, 3.1. However, an understanding of the relationship between impedance and admittance is easier to gain with simple examples such as this.

In stub matching, the stub is to be connected at a point in the line where the conductive component equals the Z_0 of the line. Point B represents the admittance of the load, which is the antenna. Various admittances will be encountered along the line, when moving in a direction indicated by the TOWARD GENERATOR wavelengths scale, but all admittance plots must fall on the constant SWR circle. Moving clockwise around the SWR circle from point B, it is seen that the line input conductance will be 1.0 (normalized Z_0 of the line) at point C, 0.082 λ toward the transmitter from the antenna. Thus, the stub should be connected at this location on the line.

The normalized admittance at point C, the point representing the location of the stub, is 1 – *j* 1.2 siemens, having an inductive susceptance component. A capacitive susceptance having a normalized value of + *j* 1.2 siemens is required across the line at the point of stub connection, to cancel the inductance. This capacitance is to be obtained from the stub section itself; the problem now is to determine its type of termination (open or shorted), and how long the stub should be. This is done by first plotting the susceptance required for cancellation, 0 + *j* 1.2, on the chart (point D in Fig 13). This point represents the input admittance as seen looking into the stub. The "load" or termination for the stub section is found by moving in the TOWARD LOAD direction around the chart, and will appear at the closest point on the resistance/conductance axis, either at the left or the right of the chart. Moving counterclockwise from point D, this is located at E, at the left of the chart, 0.139 λ away. From this we know the required stub length. The "load" at the far end of the stub, as represented on the Smith Chart, has a normalized admittance of 0 + *j* 0 siemen, which is equivalent to an open circuit.

When the stub, having an input admittance of 0 + *j* 1.2 siemens, is connected in parallel with the line at a point 0.082 λ from the load, where the line input admittance is 1.0 – *j* 1.2, the resultant admittance is the sum of the individual admittances. The conductance components are added directly, as are the susceptance components. In this case, 1.0 – *j* 1.2 + *j* 1.2 = 1.0 + *j* 0 siemen. Thus, the line from the point of stub connection to the transmitter will be terminated in a load which offers a perfect match. When determining the physical line lengths for stub matching, it is important to remember that the velocity factor for the type of line in use must be considered.

MATCHING WITH LUMPED CONSTANTS

It was pointed out earlier that the purpose of a matching stub is to cancel the reactive component of line impedance at the point of connection. In other words, the stub is simply a reactance of the proper kind and value shunted across the line. It does not matter what physical shape this reactance takes. It can be a section of transmission line or a "lumped" inductance or capacitance, as desired. In the above example with the Smith Chart solution, a capacitive reactance was required. A capacitor having the same value of reactance can be used just as well. There are cases where, from an installation standpoint, it may be considerably more convenient to connect a capacitor in place of a stub. This is particularly true when open-wire feeders are used. If a variable capacitor is used, it becomes possible to adjust the capacitance to the exact value required.

The proper value of reactance may be determined from Smith Chart information. In the previous example, the required susceptance, normalized, was +*j* 1.2 siemens. This is converted into actual siemens by dividing by the line Z_0; 1.2/52 = 0.023 siemen, capacitance. The required capacitive reactance is the reciprocal of this latter value, 1/0.023 = 43.5 Ω. If the frequency is 14.2 MHz, for instance, 43.5 Ω corresponds to a capacitance of 258 pF. A 325-pF variable capacitor connected across the line 0.082 λ from the antenna terminals would provide ample adjustment range. The RMS voltage across the capacitor is

$$E = \sqrt{P \times Z_0}$$

For 500 W, for example, E = the square root of 500 × 52 = 161 V. The peak voltage is 1.41 times the RMS value, or 227 V.

The Series-Section Transformer

The series-section transformer is described in Chapter 26, and equations are given there for its design. The transformer can be designed graphically with the aid of a Smith Chart. This information is based on a *QST* article by Frank A. Regier, OD5CG. Using the Smith Chart to design a series-section match requires the use of the chart in its less familiar off-center mode. This mode is described in the next two paragraphs.

Fig 14 shows the Smith Chart used in its familiar centered mode, with all impedances normalized to that of the transmission line, in this case 75 Ω, and all constant SWR circles concentric with the normalized value r = 1 at the chart center. An actual impedance is recovered by multiplying a chart reading by the normalizing impedance of 75 Ω. If the actual (unnormalized) impedances represented by a constant SWR circle in Fig 14 are instead divided by a normalizing impedance of 300 Ω, a different picture results. A Smith Chart shows all possible impedances, and so a closed path such as a constant SWR circle in Fig 14 must again be represented by a closed path. In fact, it can be shown that the path remains a circle, but that the constant SWR circles are no longer concentric. **Fig 15** shows the circles that result when the impedances along a mismatched 75-Ω line are normalized by dividing by 300 Ω instead of 75. The constant SWR circles still surround the point corresponding to the characteristic impedance of the line (r = 0.25) but are no longer concentric with it. Note that the normalized impedances read from corresponding points on Figs 14 and 15 are different but that the actual, unnormalized, impedances are exactly the same.

An Example

Now turn to the example shown in **Fig 16**. A complex load of Z_L = 600 + *j* 900 Ω is to be fed with 300-Ω line, and a 75-Ω series section is to be used. These characteristic impedances agree with those used in Fig 15, and thus Fig 15 can be used to find the impedance variation along the 75-Ω series section. In particular, the constant SWR circle which passes through the Fig 15 chart center, SWR = 4 in this case, passes through all the impedances (normalized to 300 Ω) which the 75-Ω series section is able to match to the 300-Ω main line. The length ℓ1 of 300-Ω line has the job of transforming the load impedance to some impedance on this matching circle.

Fig 17 shows the whole process more clearly, with all



Fig 14—Constant SWR circles for SWR = 2, 3, 4 and 5, showing impedance variation along 75-Ω line, normalized to 75 Ω. The actual impedance is obtained by multiplying the chart reading by 75 Ω.



Fig 15—Paths of constant SWR for SWR = 2, 3, 4 and 5, showing impedance variation along 75-Ω line, normalized to 300 Ω. Normalized impedances differ from those in Fig 14, but actual impedances are obtained by multiplying chart readings by 300 Ω and are the same as those corresponding in Fig 14. Paths remain circles but are no longer concentric. One, the matching circle, SWR = 4 in this case, passes through the chart center and is thus the locus of all impedances which can be matched to a 300-Ω line.



Fig 16—Example for solution by Smith Chart. All impedances are normalized to 300 Ω.

impedances normalized to 300 Ω. Here the normalized load impedance $Z_L = 2 + j\,3$ is shown at R, and the matching circle appears centered on the resistance axis and passing through the points r = 1 and r = n^2 = $(75/300)^2 = 0.0625$. A constant SWR circle is drawn from R to an intersection with the matching circle at Q or Q′ and the corresponding length ℓ1 (or ℓ1′) can be read directly from the Smith Chart. The clockwise distance around the matching circle represents the length of the matching line, from either Q′ to P or from Q to P. Because in this example the distance QP is the shorter of the two for the matching section, we choose the length ℓ1 as shown. By using values from the TOWARD GENERATOR scale, this length is found as 0.045 – 0.213, and adding 0.5 to obtain a positive result yields a value of 0.332 λ.

Although the impedance locus from Q to P is shown in Fig 17, the length ℓ2 cannot be determined directly from this chart. This is because the matching circle is not concentric with the chart center, so the wavelength scales do not apply to this circle. This problem is overcome by forming **Fig 18**, which is the same as Fig 17 except that all normalized impedances have been divided by n = 0.25, resulting in a Smith Chart normalized to 75 Ω instead of 300. The matching circle and the chart center are now concentric, and the series-section length ℓ2, the distance between Q and P, can be taken directly from the chart. By again using the TOWARD GENERATOR scale, this length is found as 0.250 – 0.148 = 0.102 λ.

In fact it is not necessary to construct the entire impedance locus shown in Fig 18. It is sufficient to plot Z_Q/n (Z_Q is read from Fig 17) and $Z_p/n = 1/n$, connect them by a circular arc centered on the chart center, and to determine the arc length ℓ2 from the Smith Chart.

Procedure Summary

The steps necessary to design a series-section transformer by means of the Smith Chart can now be listed:

1) Normalize all impedances by dividing by the characteristic impedance of the main line.
2) On a Smith Chart, plot the normalized load impedance Z_L at R and construct the matching circle

so that its center is on the resistance axis and it passes through the points $r = 1$ and $r = n^2$.

3) Construct a constant SWR circle centered on the chart center through point R. This circle should intersect the matching circle at two points. One of these points, normally the one resulting in the shorter clockwise distance along the matching circle to the chart center, is chosen as point Q, and the clockwise distance from R to Q is read from the chart and taken to be $\ell 1$.
4) Read the impedance Z_Q from the chart, calculate Z_Q/n and plot it as point Q on a second Smith Chart. Also plot $r = 1/n$ as point P.
5) On this second chart construct a circular arc, centered on the chart center, clockwise from Q to P. The length of this arc, read from the chart, represents $\ell 2$. The design of the transformer is now complete, and the necessary physical line lengths may be determined.

The Smith Chart construction shows that two design solutions are usually possible, corresponding to the two intersections of the constant SWR circle (for the load) and the matching circle. These two values correspond to positive and negative values of the square-root radical in the equation for a mathematical solution of the problem. It may happen, however, that the load circle misses the matching circle completely, in which case no solution is possible. The cure is to enlarge the matching circle by choosing a series section whose impedance departs more from that of the main line.

A final possibility is that, rather than intersecting the matching circle, the load circle is tangent to it. There is then but one solution—that of the $^1/_4$-λ transformer.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2.

W. N. Caron, *Antenna Impedance Matching* (Newington: ARRL, 1989).

C. MacKeand, “The Smith Chart in BASIC,” *QST*, Nov 1984, pp 28-31.

M. W. Maxwell, *Reflections—Transmission Lines and Antennas* (Newington: ARRL, 1990).

F. A. Regier, Series-Section Transmission-Line Impedance Matching,” *QST*, Jul 1978, pp 14-16.

P. H. Smith, *Electronic Applications of the Smith Chart*, reprint ed. (Malabar, FL: Krieger Pub Co, Inc, 1983).


Q
R
P
Q′
ℓ1
WAVELENGTHS TOWARDS GENERATOR
WAVELENGTHS TOWARD LOAD
INDUCTIVE REACTANCE COMPONENT
OR CAPACITIVE SUSCEPTANCE
CAPACITIVE REACTANCE COMPONENT
OR INDUCTIVE SUSCEPTANCE

Fig 17—Smith Chart representation of the example shown in Fig 16. The impedance locus always takes a clockwise direction from the load to the generator. This path is first along the constant SWR circle from the load at R to an intersection with the matching circle at Q or Q′, and then along the matching circle to the chart center at P. Length ℓ1 can be determined directly from the chart, and in this example is 0.332 λ.


ℓ2
Q
R
P
Q′
WAVELENGTHS TOWARDS GENERATOR
WAVELENGTHS TOWARD LOAD
INDUCTIVE REACTANCE COMPONENT
OR CAPACITIVE SUSCEPTANCE
CAPACITIVE REACTANCE COMPONENT
OR INDUCTIVE SUSCEPTANCE

Fig 18—The same impedance locus as shown in Fig 17 except normalized to 75 Ω instead of 300. The matching circle is now concentric with the chart center, and ℓ2 can be determined directly from the chart, 0.102 λ in this case.

Appendix

This appendix contains a glossary of terms, a list of common abbreviations, length conversion information (feet and inches), metric equivalents and antenna-gain-reference data.

Glossary of Terms

This glossary provides a handy list of terms that are used frequently in Amateur Radio conversation and literature about antennas. With each item is a brief definition of the term. Most terms given here are discussed more thoroughly in the text of this book, and may be located by using the index.

Actual ground—The point within the earth's surface where effective ground conductivity exists. The depth for this point varies with frequency and the condition of the soil.

Antenna—An electrical conductor or array of conductors that radiates signal energy (transmitting) or collects signal energy (receiving).

Antenna tuner—A device containing variable reactances (and perhaps a balun). It is connected between the transmitter and the feed point of an antenna system, and adjusted to "tune" or resonate the system to the operating frequency.

Aperture, effective—An area enclosing an antenna, on which it is convenient to make calculations of field strength and antenna gain. Sometimes referred to as the "capture area."

Apex—The feed-point region of a V type of antenna.

Apex angle—The included angle between the wires of a V, an inverted-V dipole, and similar antennas, or the included angle between the two imaginary lines touching the element tips of a log periodic array.

Balanced line—A symmetrical two-conductor feed line that has uniform voltage and current distribution along its length.

Balun—A device for feeding a balanced load with an unbalanced line, or vice versa. May be a form of choke, or a transformer that provides a specific impedance transformation (including 1:1). Often used in antenna systems to interface a coaxial transmission line to the feed point of a balanced antenna, such as a dipole.

Base loading—A lumped reactance that is inserted at the base (ground end) of a vertical antenna to resonate the antenna.

Bazooka—A transmission-line balancer. It is a quarter-wave conductive sleeve (tubing or flexible shielding) placed at the feed point of a center-fed element and grounded to the shield braid of the coaxial feed line at the end of the sleeve farthest from the feed point. It permits the use of unbalanced feed line with balanced feed antennas.

Beamwidth—Related to directive antennas. The width, in degrees, of the major lobe between the two directions at which the relative radiated power is equal to one half its value at the peak of the lobe (half power = –3 dB).

Beta match—A form of hairpin match. The two conductors straddle the boom of the antenna being matched, and the closed end of the matching-section conductors is strapped to the boom.

Bridge—A circuit with two or more ports that is used in measurements of impedance, resistance or standing waves in an antenna system. When the bridge is adjusted for a balanced condition, the unknown factor can be determined by reading its value on a calibrated scale or meter.

Capacitance hat—A conductor of large surface area that is connected at the high-impedance end of an antenna to effectively increase the electrical length. It is sometimes mounted directly above a loading coil to reduce the required inductance for establishing resonance. It usually takes the form of a series of wheel spokes or a solid circular disc. Sometimes referred to as a "top hat."

Capture area—See aperture.

Center fed—Transmission-line connection at the electrical center of an antenna radiator.

Center loading—A scheme for inserting inductive reactance (coil) at or near the center of an antenna element for the purpose of lowering its resonant frequency. Used with elements that are less than $^{1}/_{4}$ wavelength at the operating frequency.

Coax—See coaxial cable.

Coaxial cable—Any of the coaxial transmission lines that have the outer shield (solid or braided) on the same axis as the inner or center conductor. The insulating material can be air, helium or solid-dielectric compounds.

Collinear array—A linear array of radiating elements (usually dipoles) with their axes arranged in a straight line. Popular at VHF and above.

Conductor—A metal body such as tubing, rod or wire that permits current to travel continuously along its length.

Counterpoise—A wire or group of wires mounted close to ground, but insulated from ground, to form a low-impedance, high-capacitance path to ground. Used at MF and HF to provide an RF ground for an antenna. Also see ground plane.

Current loop—A point of current maxima (antipode) on an antenna.

Current node—A point of current minima on an antenna.

Decibel—A logarithmic power ratio, abbreviated dB. May also represent a voltage or current ratio if the voltages or currents are measured across (or through) identical impedances. Suffixes to the abbreviation indicate references: dBi, isotropic radiator; dBic, isotropic radiator circular; dBm, milliwatt; dBW, watt.

Delta loop—A full-wave loop shaped like a triangle or delta.

Delta match—Center-feed technique used with radiators that are not split at the center. The feed line is fanned near the radiator center and connected to the radiator symmetrically. The fanned area is delta shaped.

Dielectrics—Various insulating materials used in antenna systems, such as found in insulators and transmission lines.

Dipole—An antenna that is split at the exact center for connection to a feed line, usually a half wavelength long. Also called a "doublet."

Direct ray—Transmitted signal energy that arrives at the receiving antenna directly rather than being reflected by any object or medium.

Directivity—The property of an antenna that concentrates the radiated energy to form one or more major lobes.

Director—A conductor placed in front of a driven element to cause directivity. Frequently used singly or in multiples with Yagi or cubical-quad beam antennas.

Doublet—See dipole.

Driven array—An array of antenna elements which are all driven or excited by means of a transmission line, usually to achieve directivity.

Driven element—A radiator element of an antenna system to which the transmission line is connected.

Dummy load—Synonymous with dummy antenna. A nonradiating substitute for an antenna.

E layer—The ionospheric layer nearest earth from which radio signals can be reflected to a distant point, generally a maximum of 2000 km (1250 ml).

E plane—Related to a linearly polarized antenna, the plane containing the electric field vector of the antenna and its direction of maximum radiation. For terrestrial antenna systems, the direction of the E plane is also taken as the polarization of the antenna. The E plane is at right angles to the H plane.

Efficiency—The ratio of useful output power to input power, determined in antenna systems by losses in the system, including in nearby objects.

EIRP—Effective isotropic radiated power. The power radiated by an antenna in its favored direction, taking the gain of the antenna into account as referenced to isotropic.

Elements—The conductive parts of an antenna system that determine the antenna characteristics. For example, the reflector, driven element and directors of a Yagi antenna.

End effect—A condition caused by capacitance at the ends of an antenna element. Insulators and related support wires contribute to this capacitance and lower the resonant frequency of the antenna. The effect increases with conductor diameter and must be considered when cutting an antenna element to length.

End fed—An end-fed antenna is one to which power is applied at one end, rather than at some point between the ends.

F layer—The ionospheric layer that lies above the E layer. Radio waves can be refracted from it to provide communications distances of several thousand miles by means of single- or double-hop skip.

Feed line—See feeders.

Feeders—Transmission lines of assorted types that are used to route RF power from a transmitter to an antenna, or from an antenna to a receiver.

Field strength—The intensity of a radio wave as measured at a point some distance from the antenna. This measurement is usually made in microvolts per meter.

Front to back—The ratio of the radiated power off the front and back of a directive antenna. For example, a dipole would have a ratio of 1, which is equivalent to 0 dB.

Front to rear—Worst-case rearward lobe in the 180°-wide sector behind an antenna's main lobe, in dB.

Front to side—The ratio of radiated power between the major lobe and that 90° off the front of a directive antenna.

Gain—The increase in effective radiated power in the desired direction of the major lobe.

Gamma match—A matching system used with driven antenna elements to effect a match between the transmission line and the feed point of the antenna. It consists of a series capacitor and an arm that is mounted close to the driven element and in parallel with it near the feed point.

Ground plane—A system of conductors placed beneath an elevated antenna to serve as an earth ground. Also see counterpoise.

Ground screen—A wire mesh counterpoise.

Ground wave—Radio waves that travel along the earth's surface.

H plane—Related to a linearly polarized antenna. The plane containing the magnetic field vector of an antenna and its direction of maximum radiation. The H plane is at right angles to the E plane.

HAAT—Height above average terrain. A term used mainly in connection with repeater antennas in determining coverage area.

Hairpin match—A U-shaped conductor that is connected to the two inner ends of a split dipole for the purpose of creating an impedance match to a balanced feeder.

Harmonic antenna—An antenna that will operate on its fundamental frequency and the harmonics of the fundamental frequency for which it is designed. An end-fed half-wave antenna is one example.

Helical—A helically wound antenna, one that consists of a spiral conductor. If it has a very large winding length to diameter ratio it provides broadside radiation. If the length-to-diameter ratio is small, it will operate in the axial mode and radiate off the end opposite the feed point. The polarization will be circular for the axial mode, with left or right circularity, depending on whether the helix is wound clockwise or counterclockwise.

Helical hairpin—“Hairpin” match with a lumped inductor, rather than parallel-conductor line.

Image antenna—The imaginary counterpart of an actual antenna. It is assumed for mathematical purposes to be located below the earth’s surface beneath the antenna, and is considered symmetrical with the antenna above ground.

Impedance—The ohmic value of an antenna feed point, matching section or transmission line. An impedance may contain a reactance as well as a resistance component.

Inverted V—A misnomer, as the antenna being referenced does not have the characteristics of a V antenna. See inverted-V dipole.

Inverted-V dipole—A half-wavelength dipole erected in the form of an upside-down V, with the feed point at the apex. Its radiation pattern is similar to that of a horizontal dipole.

Isotropic—An imaginary or hypothetical point-source antenna that radiates equal power in all directions. It is used as a reference for the directive characteristics of actual antennas.

Lambda—Greek symbol (λ) used to represent a wavelength with reference to electrical dimensions in antenna work.

Line loss—The power lost in a transmission line, usually expressed in decibels.

Line of sight—Transmission path of a wave that travels directly from the transmitting antenna to the receiving antenna.

Litz wire—Stranded wire with individual strands insulated; small wire provides a large surface area for current flow, so losses are reduced for the wire size.

Load—The electrical entity to which power is delivered. The antenna system is a load for the transmitter.

Loading—The process of a transferring power from its source to a load. The effect a load has on a power source.

Lobe—A defined field of energy that radiates from a directive antenna.

Log periodic antenna—A broadband directive antenna that has a structural format causing its impedance and radiation characteristics to repeat periodically as the logarithm of frequency.

Long wire—A wire antenna that is one wavelength or greater in electrical length. When two or more wavelengths long it provides gain and a multilobe radiation pattern. When terminated at one end it becomes essentially unidirectional off that end.

Marconi antenna—A shunt-fed monopole operated against ground or a radial system. In modern jargon, the term refers loosely to any type of vertical antenna.

Matching—The process of effecting an impedance match between two electrical circuits of unlike impedance. One example is matching a transmission line to the feed point of an antenna. Maximum power transfer to the load (antenna system) will occur when a matched condition exists.

Monopole—Literally, one pole, such as a vertical radiator operated against the earth or a counterpoise.

Nichrome wire—An alloy of nickel and chromium; not a good conductor; resistance wire. Used in the heating elements of electrical appliances; also as conductors in transmission lines or circuits where attenuation is desired.

Null—A condition during which an electrical unit is at a minimum. A null in an antenna radiation pattern is a point in the 360-degree pattern where a minima in field intensity is observed. An impedance bridge is said to be “pulled” when it has been brought into balance, with a null in the current flowing through the bridge arm.

Octave—A musical term. As related to RF, frequencies having a 2:1 harmonic relationship.

Open-wire line—A type of transmission line that resembles a ladder, sometimes called “ladder line.” Consists of parallel, symmetrical wires with insulating spacers at regular intervals to maintain the line spacing. The dielectric is principally air, making it a low-loss type of line.

Parabolic reflector—An antenna reflector that is a portion of a parabolic revolution or curve. Used mainly at UHF and higher to obtain high gain and a relatively narrow beamwidth when excited by one of a variety of driven elements placed in the plane of and perpendicular to the axis of the parabola.

Parasitic array—A directive antenna that has a driven element and at least one independent director or reflector, or a combination of both. The directors and reflectors are not connected to the feed line. Except for VHF and UHF arrays with long booms (electrically), more than one reflector is seldom used. A Yagi antenna is one example of a parasitic array.

Phasing lines—Sections of transmission line that are used to ensure the correct phase relationship between the elements of a driven array, or between bays of an array of antennas. Also used to effect impedance transformations while maintaining the desired phase.

Polarization—The sense of the wave radiated by an antenna. This can be horizontal, vertical, elliptical or circular (left or right hand circularity), depending on the design and application. (See H plane.)

Q section—Term used in reference to transmission-line matching transformers and phasing lines.

Quad—A parasitic array using rectangular or diamond shaped full-wave wire loop elements. Often called the "cubical quad." Another version uses delta-shaped elements, and is called a delta loop beam.

Radiation pattern—The radiation characteristics of an antenna as a function of space coordinates. Normally, the pattern is measured in the far-field region and is represented graphically.

Radiation resistance—The ratio of the power radiated by an antenna to the square of the RMS antenna current, referred to a specific point and assuming no losses. The effective resistance at the antenna feed point.

Radiator—A discrete conductor that radiates RF energy in an antenna system.

Random wire—A random length of wire used as an antenna and fed at one end by means of an antenna tuner. Seldom operates as a resonant antenna unless the length happens to be correct.

Reflected ray—A radio wave that is reflected from the earth, ionosphere or a man-made medium, such as a passive reflector.

Reflector—A parasitic antenna element or a metal assembly that is located behind the driven element to enhance forward directivity. Hillsides and large man-made structures such as buildings and towers may act as reflectors.

Refraction—Process by which a radio wave is bent and returned to earth from an ionospheric layer or other medium after striking the medium.

Resonator—In antenna terminology, a loading assembly consisting of a coil and a short radiator section. Used to lower the resonant frequency of an antenna, usually a vertical or a mobile whip.

Rhombic—A rhomboid or diamond-shaped antenna consisting of sides (legs) that are each one or more wavelengths long. The antenna is usually erected parallel to the ground. A rhombic antenna is bidirectional unless terminated by a resistance, which makes it unidirectional. The greater the electrical leg length, the greater the gain, assuming the tilt angle is optimized.

Shunt feed—A method of feeding an antenna driven element with a parallel conductor mounted adjacent to a low-impedance point on the radiator. Frequently used with grounded quarter-wave vertical antennas to provide an impedance match to the feeder. Series feed is used when the base of the vertical is insulated from ground.

Stacking—The process of placing similar directive antennas atop or beside one another, forming a "stacked array." Stacking provides more gain or directivity than a single antenna.

Stub—A section of transmission line used to tune an antenna element to resonance or to aid in obtaining an impedance match.

SWR—Standing-wave ratio on a transmission line in an antenna system. More correctly, VSWR, or voltage standing-wave ratio. The ratio of the forward to reflected voltage on the line, and not a power ratio. A VSWR of 1:1 occurs when all parts of the antenna system are matched correctly to one another.

T match—Method for matching a transmission-line to an unbroken driven element. Attached at the electrical center of the driven element in a T-shaped manner. In effect it is a double gamma match.

Tilt angle—Half the angle included between the wires at the sides of a rhombic antenna.

Top hat—See capacitance hat.

Top loading—Addition of a reactance (usually a capacitance hat) at the end of an antenna element opposite the feed point to increase the electrical length of the radiator.

Transmatch—An antenna tuner.

Trap—Parallel L-C network inserted in an antenna element to provide multiband operation with a single conductor.

Unipole—See monopole.

Velocity factor—The ratio of the velocity of radio wave propagation in a dielectric medium to that in free space. When cutting a transmission line to a specific electrical length, the velocity factor of the particular line must be taken into account.

VSWR—Voltage standing-wave ratio. See SWR.

Wave—A disturbance or variation that is a function of time or space, or both, transferring energy progressively from point to point. A radio wave, for example.

Wave angle—The angle above the horizon of a radio wave as it is launched from or received by an antenna. Also called elevation angle.

Wave front—A surface that is a locus of all the points having the same phase at a given instant in time.

Yagi—A directive, gain type of antenna that utilizes a number of parasitic directors and a reflector. Named after one of the two Japanese inventors (Yagi and Uda).

Zepp antenna—A half-wave wire antenna that operates on its fundamental and harmonics. It is fed at one end by means of open-wire feeders. The name evolved from its popularity as an antenna on Zeppelins. In modern jargon the term refers loosely to any horizontal antenna.

Abbreviations

Abbreviations and acronyms that are commonly used throughout this book are defined in the list below. Periods are not part of an abbreviation unless the abbreviation otherwise forms a common English word. When appropriate, abbreviations as shown are used in either singular or plural construction.

-A-
A—ampere
ac—alternating current
AF—audio frequency
AFSK—audio frequency-shift keying
AGC—automatic gain control
AM—amplitude modulation
ANT—antenna
ARRL—American Radio Relay League
ATV—amateur television
AWG—American wire gauge
az-el—azimuth-elevation

-B-
balun—balanced to unbalanced
BC—broadcast
BCI—broadcast interference
BW—bandwidth

-C-
ccw—counterclockwise
cm—centimeter
coax—coaxial cable
CT—center tap
cw—clockwise
CW—continuous wave

-D-
D—diode
dB—decibel
dBd—decibels referenced to a dipole
dBi—decibels referenced to isotropic
dBic—decibels referenced to isotropic, circular
dBm—decibels referenced to one milliwatt
dBW—decibels referenced to one watt
dc—direct current
deg—degree
DF—direction finding
dia—diameter
DPDT—double pole, double throw
DPST—double pole, single throw
DVM—digital voltmeter
DX—long distance communication

-E-
E—ionospheric layer, electric field
ed.—edition
Ed.—editor
EIRP—effective isotropic radiated power
ELF—extremely low frequency
EMC—electromagnetic compatibility
EME—earth-moon-earth
EMF—electromotive force
ERP—effective radiated power
E_S—ionospheric layer (sporadic E)

-F-
f—frequency
F—ionospheric layer, farad
F/B—front to back (ratio)
F/R—worst-case front to rear (ratio)
FM—frequency modulation
FOT—frequency of optimum transmission
ft—foot or feet (unit of length)
F_1—ionospheric layer
F_2—ionospheric layer

-G-
GDO—grid- or gate-dip oscillator
GHz—gigahertz
GND—ground

-H-
H—magnetic field, henry
HAAT—height above average terrain
HF—high frequency (3-30 MHz)
Hz—hertz (unit of frequency)

-I-
I—current
ID—inside diameter
IEEE—Institute of Electrical and Electronic Engineers
in.—inch
IRE—Institute of Radio Engineers (now IEEE)

-J-
j—vector notation

-K-
kHz—kilohertz
km—kilometer
kW—kilowatt
kW—kilohm

-L-
L—inductance
lb—pound (unit of mass)
LF—low frequency (30-300 kHz)
LHCP—left-hand circular polarization
ln—natural logarithm
log—common logarithm
LP—log periodic
LPDA—log periodic dipole array
LPVA—log periodic V array
LUF—lowest usable frequency

-M-
m—meter (unit of length)
m/s—meters per second
mA—milliampere
max—maximum
MF—medium frequency (0.3-3 MHz)
mH—millihenry
MHz—megahertz
mi—mile
min—minute
mm—millimeter
ms—millisecond
mS—millisiemen
MS—meteor scatter
MUF—maximum usable frequency
mW—milliwatt
MW—megohm

-N-
NC—no connection, normally closed
NiCd—nickel cadmium
NIST—National Institute of Standards and Technology
NO—normally open
no.—number

-O-
OD—outside diameter

-P-
p—page (bibliography reference)
P-P—peak to peak
PC—printed circuit
PEP—peak envelope power
pF—picofarad
pot—potentiometer
pp—pages (bibliography reference)
Proc—Proceedings

-Q-
Q—figure of merit

-R-
R—resistance, resistor
RF—radio frequency
RFC—radio frequency choke
RFI—radio frequency interference
RHCP—right-hand circular polarization
RLC—resistance-inductance-capacitance
r/min—revolutions per minute
RMS—root mean square
r/s—revolutions per second
RSGB—Radio Society of Great Britain
RX—receiver

-S-
s—second
S—siemen
S/NR—signal-to-noise ratio
SASE—self-addressed stamped envelope
SINAD—signal-to-noise and distortion
SPDT—single pole, double throw
SPST—single pole, single throw
SWR—standing wave ratio
sync—synchronous

-T-
tpi—turns per inch
TR—transmit-receive
TVI—television interference
TX—transmitter

-U-
UHF—ultra-high frequency (300-3000 MHz)
US—United States
UTC—Universal Time, Coordinated

-V-
V—volt
VF—velocity factor
VHF—very-high frequency (30-300 MHz)
VLF—very-low frequency (3-30 kHz)
Vol—volume (bibliography reference)
VOM—volt-ohm meter
VSWR—voltage standing-wave ratio
VTVM—vacuum-tube voltmeter

-W-
W—watt
WPM—words per minute
WRC—World Radio Conference
WVDC—working voltage, direct current

-X-
X—reactance
XCVR—transceiver
XFMR—transformer
XMTR—transmitter

-Z-
Z—impedance

-Other symbols and Greek letters-
°—degrees
λ—wavelength
λ/dia—wavelength to diameter (ratio)
μ—permeability
μF—microfarad
μH—microhenry
μV—microvolt
Ω—ohm
ϕ—angles
π—3.14159
θ—angles

Length Conversions

Throughout this book, equations may be found for determining the design length and spacing of antenna elements. For convenience, the equations are written to yield a result in feet. (The answer may be converted to meters simply by multiplying the result by 0.3048.) If the result in feet is not an integral number, however, it is necessary to make a conversion from a decimal fraction of a foot to inches and fractions before the physical distance can be determined with a conventional tape measure. Table 1 may be used for this conversion, showing inches and fractions for increments of 0.01 foot. The table deals with only the fractional portion of a foot. The integral number of feet remains the same.

For example, say a calculation yields a result of 11.63 feet, and we wish to convert this to a length we can find on a tape measure. For the moment, consider only the fractional part of the number, 0.63 foot. In Table 1 1ocate the line with “0.6” appearing in the left column. (This is the 7th line down in the body of the table.) Then while staying on that line, move over to the column headed “0.03.” Note here that the sum of the column and line heads, 0.6 + 0.03, equals the value of 0.63 that we want to convert. In the body of the table for this column and line we read the equivalent fraction for 0.63 foot, $7^{9}/_{16}$ inches. To that value, add the number of whole feet from the value being converted, 11 in this case. The total length equivalent of 11.63 feet is thus 11 feet $7^{9}/_{16}$ inches.

Similarly, Table 2 may be used to make the conversion from inches and fractions to decimal fractions of a foot. This table is convenient for using measured distances in equations. For example, say we wish to convert a length of 19 feet $7^{3}/_{4}$ inches to a decimal fraction. Considering only the fractional part of this value, $7^{3}/_{4}$ inches, locate the decimal value on the line identified as “7-” and in the column headed “$^{3}/_{4}$,” where we read 0.646. This decimal value is equivalent to 7 + $^{3}/_{4}$ = $7^{3}/_{4}$ inches. To this value add the whole number of feet from the value being converted for the final result, 19 in this case. In this way, 19 feet $7^{3}/_{4}$ inches converts to 19 + 0.646 = 19.646 feet.

Table 2
Conversion, Inches and Fractions to Decimal Feet

	Fractional Increments							
	0	*$^{1}/_{8}$*	*$^{1}/_{4}$*	*$^{3}/_{8}$*	*$^{1}/_{2}$*	*$^{5}/_{8}$*	*$^{3}/_{4}$*	*$^{7}/_{8}$*
0-	0.000	0.010	0.021	0.031	0.042	0.052	0.063	0.073
1-	0.083	0.094	0.104	0.115	0.125	0.135	0.146	0.156
2-	0.167	0.177	0.188	0.198	0.208	0.219	0.229	0.240
3-	0.250	0.260	0.271	0.281	0.292	0.302	0.313	0.323
4-	0.333	0.344	0.354	0.365	0.375	0.385	0.396	0.406
5-	0.417	0.427	0.438	0.448	0.458	0.469	0.479	0.490
6-	0.500	0.510	0.521	0.531	0.542	0.552	0.563	0.573
7-	0.583	0.594	0.604	0.615	0.625	0.635	0.646	0.656
8-	0.667	0.677	0.688	0.698	0.708	0.719	0.729	0.740
9-	0.750	0.760	0.771	0.781	0.792	0.802	0.813	0.823
10-	0.833	0.844	0.854	0.865	0.875	0.885	0.896	0.906
11-	0.917	0.927	0.938	0.948	0.958	0.969	0.979	0.990

Table 1
Conversion, Decimal Feet to Inches (Nearest 16th)

					Decimal Increments					
	0.00	*0.01*	*0.02*	*0.03*	*0.04*	*0.05*	*0.06*	*0.07*	*0.08*	*0.09*
0.0	0-0	$0^{1}/_{8}$	$0^{1}/_{4}$	$0^{3}/_{8}$	$0^{1}/_{2}$	$0^{5}/_{8}$	$0^{3}/_{4}$	$0^{13}/_{16}$	$0^{15}/_{16}$	$1^{1}/_{16}$
0.1	$1^{3}/_{16}$	$1^{5}/_{16}$	$1^{7}/_{16}$	$1^{9}/_{16}$	$1^{11}/_{16}$	$1^{13}/_{16}$	$1^{15}/_{16}$	$2^{1}/_{16}$	$2^{3}/_{16}$	$2^{1}/_{4}$
0.2	$2^{3}/_{8}$	$2^{1}/_{2}$	$2^{5}/_{8}$	$2^{3}/_{4}$	$2^{7}/_{8}$	3-0	$3^{1}/_{8}$	$3^{1}/_{4}$	$3^{3}/_{8}$	$3^{1}/_{2}$
0.3	$3^{5}/_{8}$	$3^{3}/_{4}$	$3^{13}/_{16}$	$3^{15}/_{16}$	$4^{1}/_{16}$	$4^{3}/_{16}$	$4^{5}/_{16}$	$4^{7}/_{16}$	$4^{9}/_{16}$	$4^{11}/_{16}$
0.4	$4^{13}/_{16}$	$4^{15}/_{16}$	$5^{1}/_{16}$	$5^{3}/_{16}$	$5^{1}/_{4}$	$5^{3}/_{8}$	$5^{1}/_{2}$	$5^{5}/_{8}$	$5^{3}/_{4}$	$5^{7}/_{8}$
0.5	6-0	$6^{1}/_{8}$	$6^{1}/_{4}$	$6^{3}/_{8}$	$6^{1}/_{2}$	$6^{5}/_{8}$	$6^{3}/_{4}$	$6^{13}/_{16}$	$6^{15}/_{16}$	$7^{1}/_{16}$
0.6	$7^{3}/_{16}$	$7^{5}/_{16}$	$7^{7}/_{16}$	$7^{9}/_{16}$	$7^{11}/_{16}$	$7^{13}/_{16}$	$7^{15}/_{16}$	$8^{1}/_{16}$	$8^{3}/_{16}$	$8^{1}/_{4}$
0.7	$8^{3}/_{8}$	$8^{1}/_{2}$	$8^{5}/_{8}$	$8^{3}/_{4}$	$8^{7}/_{8}$	9-0	$9^{1}/_{8}$	$9^{1}/_{4}$	$9^{3}/_{8}$	$9^{1}/_{2}$
0.8	$9^{5}/_{8}$	$9^{3}/_{4}$	$9^{13}/_{16}$	$9^{15}/_{16}$	$10^{1}/_{16}$	$10^{3}/_{16}$	$10^{5}/_{16}$	$10^{7}/_{16}$	$10^{9}/_{16}$	$10^{11}/_{16}$
0.9	$10^{13}/_{16}$	$10^{15}/_{16}$	$11^{1}/_{16}$	$11^{3}/_{16}$	$11^{1}/_{4}$	$11^{3}/_{8}$	$11^{1}/_{2}$	$11^{5}/_{8}$	$11^{3}/_{4}$	$11^{7}/_{8}$

Metric Equivalents

Throughout this book, distances and dimensions are usually expressed in English units—the mile, the foot, and the inch. Conversions to metric units may be made by using the following equations:

km = mi × 1.609

m = ft (′) × 0.3048

mm = in. (″) × 25.4

An inch is $^1/_{12}$ of a foot. Tables in the previous section provide information for accurately converting inches and fractions to decimal feet, and vice versa, without the need for a calculator.

Gain Reference

Throughout this book, gain is referenced to an isotropic radiator (dBi) or to an isotropic radiator with circular polarization (dBic).

Advertisers Index

Advertising Department Staff
Debra Jahnke, K1DAJ, *Business Services Manager*
Janet Rocco, W1JLR, *Business Services Associate*
Lisa Tardette, KB1MOI, *Business Services Associate*
Diane Szlachetka, KB1OKV, *Advertising Graphic Design*

1-800-243-7768

Direct Line: 860-594-0207 ▪ Fax: 860-594-4285 ▪ e-mail: ads@arrl.org ▪ Web: www.arrl.org/ads

Advanced Specialties AB-18
Array Solutions.. AB-13
Cable X-PERTS, Inc. AB-6
Dave's Hobby Shop AB12
EZ Hang AB-17
Gap Antenna Products, Inc. AB-11
Ham Radio Outlet .... COVER II, COVER III
Hamware.de.. AB-18
High Sierra Antennas AB-7
Hy-Gain AB-4, AB-5
IIX Equipment, Ltd. AB-12
K0XG Systems AB-19
MFJ Enterprises AB-2, AB-3
NCG Company AB-15
Quicksilver Radio Products AB-12
Rohn Products/ Div.of Radian
  Communication Services, Inc. AB-16
TGM Communications.. AB-21
Teri Software AB-19
Texas Towers AB-22
Timewave Technology, Inc. AB-8
Unadilla Antenna Mfg. Co. AB-17
Universal Radio AB-14
W3FF Antennas AB-10
WB0W, Inc. AB-9

If your company provides products or services of interest to our readers,
please contact the ARRL Advertising Department today for information on building your business.

MFJ TUNERS

MFJ *IntelliTuner*™ Automatic Tuners

MFJ
MFJ IntelliTuner™
AUTOMATIC ANTENNA TUNER
MODEL MFJ-993B
ANT C-UP L-UP AUTO POWER
MODE C-DN L-DN TUNE
BYPASS
Dual Power Level 300/150 Watts
MFJ ENTERPRISES, INC. STARKVILLE, MS USA
TRANSMITTER
BALANCED LINE
WIRE
ANTENNA 1
ANTENNA 2
POWER 12VDC 1A
REMOTE PORT
RADIO INTERFACE
GROUND
★ Install Jumper When Using BALANCED LINE Antenna
Do not connect WIRE and ANTENNA 1 at same time!

The MFJ-993B *IntelliTuner*™ lets you tune any antenna *automatically -- ultra fast.*

It's a comprehensive automatic *antenna tuning center* complete with SWR/Wattmeter, antenna switch for two antennas and 4:1 current balun for balanced lines.

MFJ's exclusive *IntelliTuner*™, *Adaptive Search*™ and *Instant Recall*™ algorithms give you *ultra fast* automatic tuning with over 20,000 *VirtualAntenna*™ Memories.

You get a highly efficient L-network, 6-1600 ohm matching at 300 Watts SSB/CW or *extra-wide* 6-3200 Ohm matching at 150 Watts SSB/CW, 1.8-30 MHz coverage, Cross-Needle *and* digital meters, audio SWR meter, *backlit* LCD, remote control port, radio interface, heavy-duty 16 amp/1000V relays.

The MFJ-993B automatically tunes for minimum SWR and remembers your frequency and tuner settings. The next time you operate on that frequency and antenna, these tuner settings are instantly restored and *you're ready to operate in milliseconds!* 10W x2¾ Hx9D". Use 12-15 VDC/1 amp or 110 VAC with **MFJ-1316, $21.95**. Radio interface cables, remote control available. See ***www.mfjenterprises.com***

MFJ-993B
$259.95

600 Watt MFJ Automatic Tuner

MFJ
MFJ Automatic Antenna Tuner

Like MFJ-993B but handles 600 Watts SSB /CW, matches 12-800 Ohms. 10,000 memories. Does not have LCD display, antenna switch, 4:1 current balun, audio SWR meter/feedback. 10Wx2¾Hx9D in.

MFJ-994B
$359.95

***No Matter What*™ Warranty**

Every MFJ tuner is protected by MFJ's famous one year *No Matter What*™ limited warranty. We will repair or replace your MFJ tuner (at our option) for a full year.

More hams use MFJ tuners than all other tuners in the world!

MFJ-9982 *2500 Watt* Tuner

2500 Watt Antenna Tuner
MFJ

MFJ-9982
$699.95

The MFJ-9982 *ContinuousCarrier*™ antenna tuner handles 2500 Watts *continuous carrier* output on all modes and all HF bands into most unbalanced antennas -- even 160 Meters. 6-position antenna switch, 4-core balun, 1.5kW dummy load, true *peak*/average SWR/Wattmeter, 13¾Wx7Hx6¼D".

MFJ-989D *Legal Limit* Tuner

MFJ VERSA TUNER V
MFJ

MFJ-989D
$369.95

New, improved MFJ-989D *legal limit* antenna tuner gives you better efficiency, lower losses and a new *true* peak reading meter. Easily handles *full* 1500 Watts SSB/CW, 1.8-30 MHz, including MARS/WARC bands. Six position antenna switch, dummy load. *New* 500 pF air variable capacitors. *New* improved *AirCore*™ Roller Inductor. *New* high voltage current balun. *New* crank knob. 12⅞Wx6Hx11⅝D".

MFJ-962D *compact* kW Tuner

MFJ VERSA TUNER III
MFJ

MFJ-962D
$279.95

A few more dollars steps you up to a KW tuner for an amp later. Handles 1.5 KW PEP SSB amplifier input power (800W output). Ideal for Ameritron's AL-811H! *AirCore*™ roller inductor, gear-driven turns counter, pk/avg lighted Cross-Needle SWR/Wattmeter, antenna switch, balun, Lexan front, 1.8-30MHz. 10¾Wx4½H x10⅞D in.

MFJ-969 300W *Roller Inductor* Tuner

Superb *AirCore*™ Roller Inductor tuning. Covers *6 Meters* thru 160 Meters! 300 Watts PEP SSB. *Active* true peak reading lighted Cross-Needle SWR Wattmeter, *QRM-Free PreTune*™, antenna switch, dummy load, 4:1 balun, Lexan front panel. 10½Wx3½Hx9½D inches.

MFJ-969
$199.95

MFJ-949E *deluxe* 300 Watt Tuner

MFJ DELUXE VERSA TUNER II

***More** hams use MFJ-949s than any other antenna tuner in the world!*

Handles 300 Watts. Full 1.8 to 30 MHz coverage, custom inductor switch, 1000 Volt tuning capacitors, *full size* peak/average lighted Cross-Needle SWR/ Wattmeter, 8 position antenna switch, dummy load, *QRM-Free PreTune*™, scratch proof Lexan front panel. 10⅝Wx3½Hx7D inches.

MFJ-949E
$169.95

MFJ-948, $139.95. Economy version of MFJ-949E, less dummy load, Lexan front panel.

MFJ-941E *super value* Tuner

MFJ VERSA TUNER II

***The** most for your money!*

Handles 300 Watts PEP, covers 1.8-30 MHz, *lighted* Cross-Needle SWR/ Wattmeter, 8 position antenna switch, 4:1 balun, 1000 volt capacitors, Lexan front panel. Sleek 10½Wx2½Hx7D".

MFJ-941E
$129.95

MFJ-945E HF/6M *mobile* Tuner

MFJ MOBILE TUNER
MFJ

Extends your mobile antenna bandwidth so you don't have to stop, go outside and adjust your antenna. Tiny 8Wx2Hx6D in. *Lighted* Cross-Needle SWR/Wattmeter. Lamp and bypass switches. Covers 1.8-30 MHz *and* 6 Meters. 300 Watts PEP. **MFJ-20, $6.95,** mobile mount.

MFJ-945E
$119.95

MFJ-974HB *Balanced Line* Tuner

MFJ Balanced Line Tuner

The MFJ-974HB *true* fully balanced antenna tuner tunes any balanced lines. Matches 12-2000 Ohms. Covers 1.8-54 MHz *continuously* including all WARC bands. 300 Watts SSB/150 Watts CW. Lighted Cross-Needle SWR/Wattmeter. 7½Wx6Hx8D in.

MFJ-974HB
$199.95

MFJ-976, $499.95. 1500 Watt *fully balanced* antenna tuner. 1-30 MHz.

MFJ-971 *portable/QRP* Tuner

MFJ PORTABLE TUNER

Tunes coax, balanced lines, random wire 1.8-30 MHz. Cross-Needle Meter. SWR, 30/300 or 6 Watt QRP ranges. Matches popular MFJ transceivers. 6Wx6½Hx2½D in.

MFJ-971
$109.95

MFJ-902 *Tiny Travel* Tuner

MFJ Travel Tuner

Tiny 4½Wx2¼Hx3D", full 150 Watts, 80-10 Meters, has tuner bypass switch, for coax/random wire.

MFJ-902
$89.95

MFJ-904H, $139.95. Same but adds Cross-needle SWR/Wattmeter and 4:1 balun for balanced lines. 7¼Wx2¼Hx2¾D in.

MFJ-16010 *random wire* Tuner

Operate all bands anywhere with MFJ's reversible L-network. Turns random wire into powerful transmitting antenna. 1.8-30 MHz. 200 Watts PEP. Tiny 2Wx3Hx4D inches.

MFJ-16010
$59.95

Dealer/Catalog/Manuals

Visit: http://www.mfjenterprises.com
or call toll-free 800-647-1800

• 1 Year *No Matter What*™ warranty • 30 day money back guarantee (less s/h) on orders direct from MFJ

MFJ

MFJ ENTERPRISES, INC.
300 Industrial Pk Rd, Starkville,
MS 39759 **PH:** (662) 323-5869
Tech Help: (662) 323-0549
FAX:(662)323-6551 8-4:30 CST, Mon.-Fri. ***Add shipping.***

Prices and specifications subject to change. (c) *2007 MFJ Enterprises, Inc.*

MFJ-259B *Antenna Analyzer*

The world's most popular antenna analyzer gives you a complete picture of your antenna performance 1.8 to 170 MHz. Super easy-to-use -- makes tuning your antenna quick and easy. Read antenna SWR, complex impedance, return loss, reflection coefficient. Determine velocity factor, coax cable loss in dB, length of coax and distance to a short or open in feet. Read inductance in uH and capacitance in pF at RF frequencies. Large easy-to-read two line LCD screen and side-by-side meters clearly display your information. Built-in frequency counter, Ni-Cad charger circuit, battery saver, low battery warning and smooth reduction drive tuning.

MFJ-259B
$279⁹⁵

MFJ-99B, $88.80. Accessory Package for MFJ-259B. Includes MFJ-29C custom foam-filled carrying case, MFJ-66 dip meter adapters, MFJ-1312D 110VAC adapter and 10-pack high capacity Ni-MH MFJ *SuperCell*™ batteries. ***Save $7!***

1.8-170 MHz *plus* 415-470 MHz *Antenna Analyzer*

All-in-one handheld antenna test lab lets you quickly check/tune HF, VHF, ***UHF*** antennas anywhere. Measures: SWR, Return Loss, Reflection Coefficient, R, X, Z, Phase Angle, Coax cable loss, Coax cable length, Distance to short/open in coax, Inductance, Capacitance, Resonant Frequency, Bandwidth, Q, Velocity Factor, Attenuation, more!

MFJ-269
$379⁹⁵

MFJ *Weather-Proof* Antenna *Feedthrough* Panel

Bring three coax-fed HF/VHF/UHF antennas, balanced line, random wire and ground into your hamshack without drilling through walls . . . ***New!*** MFJ-4602 **$59⁹⁵**

Indoor View

MFJ's Weather-proof *Antenna Feedthrough Panel* mounts in your window sill. Lets you feed three coax-fed antennas, balanced line, random wire and ground without drilling through walls.

Simply place in window sill and close window. One cut customizes it for any window up to 48 inches. Use horizontally or vertically. High-quality pressure-treated wood with excellent 3/4 inch thick insulating properties is painted with heavy coat of white outdoor enamel paint. Edges sealed by weather-stripping. Seals and insulates against all weather conditions. Gives years of trouble-free service. ¾Dx3½Hx48W in.

Inside/outside stainless steel plates bond all coax shields to ground. Stainless steel ground post brings outside ground connection inside. 3 *Teflon*® SO-239 coax connectors, *ceramic* balanced line/randomwire feedthru insulators.

Stainless Steel Bonding Plate



Outdoor View



Current Balun/Center Insulator

MFJ-918
$24⁹⁵

True *1:1 Current Balun/Center Insulator* forces equal antenna currents in dipoles. *Improves all dipoles/doublets!* Reduces coax feedline radiation, field pattern distortion, TVI, RFI, RF hot spots. SO-239. 1.8-30 MHz, 1.5kW. Stainless steel hardware. *Direct* wire connection to antenna. 5x2 inches.

MFJ-915 RF Isolator

MFJ-915
$29⁹⁵

MFJ-915 *RF Isolator* prevents unwanted RF from traveling on the outside of your coax shield into your transceiver. Clears up RFI. Eliminates painful RF "bites" on your rig or microphone. Keeps your transceiver and vehicle displays and settings from locking up. Plugs between coax and transceiver. 5x2 inches. 1.8-30 MHz, 1.5 kW.

MFJ W9INN Balun Box

MFJ-912
$59⁹⁵

Converts unbalanced coax line to balanced ladder transmission line. *Giant* 2-core 4:1 balun wound with *Teflon*® wire. 3¼x2¼x7 inches. Heavy duty ceramic feed-through insulators. 1500 Watts full legal limit. SO-239. Ground post, mounting holes.

Antenna Switches

MFJ-1702C 2 position antenna coax switch. Exclusive lightning arrestor and center pos. ground, lightning arrestor. 2.5 kW PEP, 1 kW CW. Loss below .2 dB. 50 dB isolation @ 450 MHz. 50 Ohms. 3x2x3".

MFJ-1702C
$34⁹⁵

MFJ-1704. Like MFJ-1702C but has 4 positions. 6¼x4¼x1¼ in. 50 load. SWR 1.1: 1 to 30 MHz; 1.5:1, 30-650 MHz. SO-239.

MFJ-1704
$74⁹⁵

All Band G5RV Antennas

160-10 Meters with tuner. 102 foot.1.5 kW. Use as Marconi on 160 Meters with tuner/ground. Ladder line/SO-239.

MFJ-1778
$39⁹⁵

MFJ-1778M, $34.95. *Half-size*, 52 ft. G5RV-Jr. 60-10 Meters with tuner. 1.5 kW.

33 Foot *fiberglass* Mast

MFJ-1910
$79⁹⁵

33 foot super strong fiberglass *telescoping* mast collapses to 3.8 feet, weighs 3.3 lbs. Huge, strong 1¾ inch bottom section. Flexes to resist breaking. Resists UV. Put up *full size* inverted Vee dipole/vertical antenna in minutes and get *full size performance!*

6-Band *Rotatable* mini-Dipole

MFJ-1775
$239⁹⁵

Low-profile mini 14 foot rotatable dipole has tiny 7-foot turning radius. Fits on smallest roof -- perfect for town houses, apartments and condos.

Easily turned by TV rotator.

It's no Wimp! Good *directivity* reduces QRM/noise and lets you *focus* your signal in the direction that you want -- so you can work some *real* DX.

Operate 40, 20, 15, 10, 6, 2 meters. Run *full 1500 Watts* SSB/CW on all HF bands!

Ham radio's most versatile rotatable dipole features automatic band switching. Uses highly efficient end-loading with its *entire length* always radiating.

No lossy traps! Has separate, efficient end-loading *Teflon*™ coils on fiberglass forms and capacitance hats for each HF band. 6/2 Meters are *full-length* dipoles.

Built-to-last -- super strong solid fiberglass center insulator, 6063 T-6 aircraft strength aluminum tubing. Assembles in an afternoon.

MFJ-1775W, $239.95. WARC band version for 12, 17, 30, 60 Meters only.

MFJ Field Strength Meters

Huge 3" meter. Telescoping ground-independent *dipole.* .1-500 MHz. Sensitivity control. Remote sensor, MFJ-802R, $24.95. **MFJ-801, $24.95.** *Monopole* field strength meter, 1¼" meter.

MFJ-802
$44⁹⁵

Clamp-On RF Ammeter

MFJ-854
$109⁹⁵

Clamp-On RF Ammeter snaps over cables up to ½ inch diameter. Measure RF currents in antenna elements, radials, ground wires, coax shield. Five *calibrated* ranges to 3 Amps. 1-30 MHz. 2½Wx5½Hx1½D inches.

Free MFJ Catalog

and Nearest Dealer . . . 800-647-1800

http://www.mfjenterprises.com

• 1 Year *No Matter What*™ warranty • 30 day money back guarantee (less s/h) on orders direct from MFJ

MFJ ENTERPRISES, INC.
300 Industrial Pk Rd, Starkville,
MS 39759 **PH:** (662) 323-5869
Tech Help: (662) 323-0549
FAX:(662)323-6551 8-4:30 CST, Mon.-Fri. ***Add shipping.***

Prices and specifications subject to change. (c) 2007 MFJ Enterprises, Inc.

hy-gain® HF VERTICALS

Self-supporting -- no guys required . . . Remarkable DX performance -- low angle radiation, omnidirectional . . . Handles 1500 Watts . . . Low SWR . . . Automatic band switching . . . Aircraft quality aluminum tubing . . . Stainless steel hardware . . . Recessed SO-239 connector . . . Two year limited Warranty . . .

Free Manuals!



hy-gain(R)
Classics

All hy-gain multi-band vertical antennas are entirely self supporting -- no guys required.

They offer remarkable DX performance with their extremely low angle of radiation and omnidirectional pattern.

All handle 1500 Watts PEP SSB, have low SWR, automatic bandswitching (except AV-18VS) and include a 12-inch heavy duty mast support bracket (except AV-18HT).

Heavy duty, slotted, tapered swaged, aircraft quality aluminum tubing with full circumference compression clamps is used for radiators.

Includes all stainless steel hardware. Recessed SO-239 prevents moisture damage.

Hy-gain verticals go up easily with just hand tools and their cost is surprisingly low.

Two year limited warranty.

AV-18HT, $949.95. (10,12,15,20,40,80 M, 160, 17 Meters optional). 53 ft., 114 lbs.

Standing 53 feet tall, the famous *Hy-Gain HyTower* is the world's best performing vertical! The AV-18HT features automatic band selection achieved through a unique stub-decoupling system which effectively isolates various sections of the antenna so that an electrical 1/4 wavelength (or odd multiple of a 1/4 wavelength) exists on all bands. Approximately 250 kHz bandwidth at 2:1 VSWR on 80 Meters. The addition of a base loading coil (**LC-160Q, $109.95**), provides exceptional 160 Meter performance. **MK-17, $89.95**. Add-on 17 Meter kit. 24 foot tower is all rugged, hot-dip galvanized steel and all hardware is iridited for corrosion resistance. Special tilt-over hinged base for easy raising & lowering.

AV-14AVQ, $169.95. (10,15,20,40 Meters). 18 ft., 9 lbs. The Hy-Gain AV-14AVQ uses the same trap design as the famous Hy-Gain Thunderbird beams. Three separate air dielectric Hy-Q traps with oversize coils give superb stability and 1/4 wave resonance on all bands. Roof mount with Hy-Gain AV-14RMQ kit, $89.95.

AV-12AVQ, $124.95. (10, 15, 20 Meters). 13 ft., 9 lbs. AV-12AVQ also uses Thunderbird beam design air dielectric traps for extremely Hy-Q performance. This is the way to go for inexpensive tri-band performance in limited space. Roof mount with AV-14RMQ kit, $89.95.

AV-18VS, $99.95. (10,12,15,17,20,30,40,80 Meters). 18 ft., 4 lbs. High quality construction and low cost make the AV-18VS an exceptional value. Easily tuned to any band by adjusting feed point at the base loading coil. Roof mount with Hy-Gain AV-14RMQ kit, $89.95.

DX-88, $369.95. (10, 12, 15,17,20,30,40,80 Meters, 160 Meters optional). 25 ft., 18 lbs. All bands are *easily* tuned with the DX-88's *exclusive* adjustable capacitors. 80 and 40 Meters can even be tuned from the ground without having to lower the antenna. Super heavy-duty construction. DX-88 OPTIONS: 160 Meter add-on kit, KIT-160-88, $199.95. Ground Radial System, GRK-88, $99.95. Roof Radial System, RRK-88, $99.95.

DX-77A, $449.95. (10, 12, 15, 17, 20, 30, 40 Meters). 29 ft., 25 lbs.

No ground radials required! Off-center-fed Windom has 55% greater bandwidth than competitive verticals. Heavy-duty tiltable base. Each band independently tunable.

Model #	Price	Bands	Max Power	Height	Weight	Wind Surv.	Rec. Mast
AV-18HT	$949.95	10,15,20,40,80	1500 W PEP	53 feet	114 pounds	75 MPH	------
AV-14AVQ	**$169.95**	**10,15,20,40**	**1500 W PEP**	**18 feet**	**9 pounds**	**80 MPH**	**1.5-1.625"**
AV-12AVQ	$134.95	10/15/20 M	1500 W PEP	13 feet	9 pounds	80 MPH	1.5-1.625"
AV-18VS	**$99.95**	**10 - 80 M**	**1500 W PEP**	**18 feet**	**4 pounds**	**80 MPH**	**1.5-1.625"**
DX-88	$369.95	10 - 40 M	1500 W PEP	25 feet	18 pounds	75 mph no guy	1.5-1.625"
DX-77A	**$449.95**	**10 - 80 M**	**1500 W PEP**	**29 feet**	**25 pounds**	**60 mph no guy**	**1.5-1.625"**

hy-gain®
PATRIOT

Hy-Gain's new PATRIOT HF verticals are the best built, best performing and best priced multiband verticals available today. For exciting DX make full use of your sunspot cycle with the PATRIOT's *low 17 degree angle* signal.



No ground or radials needed

Effective counterpoise replaces radials and ground.

Automatic bandswitching

Single coax cable feed. Each band is individually tunable. Extra wide VSWR bandwidth. End fed with broadband matching unit.

Sleek and low-profile

Low 2.5 sq. ft. wind surface area. Small area required for mounting. Mounts easily on decks, roofs and patios.

Full legal limit

Handles 1500 Watts key down continuous for two minutes.

Built-to-last

High wind survival of 80 mph. Broadband matching unit made from all *Teflon®* insulated wire. Aircraft quality aluminum tubing, stainless steel hardware.

hy-gain® warranty

Two year limited warranty. All replacement parts in stock.

AV-640, $399.95. (6,10,12, 15,17,20,30,40 Meters). 25.5 ft., 17.5 lbs. The AV-640 uses quarter wave stubs on 6, 10, 12 and 17 meters and efficient end loading coil and capacity hats on 15, 20, 30 and 40 meters -- no traps. Resonators are placed in parallel not in series. End loading of the lower HF bands allows efficient operation with a manageable antenna height.

AV-620, $299.95. (6,10,12,15,17,20 Meters). 22.5 ft., 10.5 lbs. The AV-620 covers all bands 6 through 20 Meters with no traps, no coils, no radials yielding an uncompromised signal across all bands.

Free Hy-Gain Catalog
and Nearest Dealer . . . 800-973-6572
Call your dealer for your best price!

hy-gain®

Antennas, Rotators & Towers
308 Industrial Park Road, Starkville, MS 39759 USA
Toll-free Customer Sales Hotline: 800-973-6572
• TECH: 662-323-9538 **• FAX:** 662-323-6551
http://www.hy-gain.com

Prices and specifications subject to change without notice or obligation. (c) Hy-Gain®, 2006.

Antennas *built-to-last . . . Use* hy-gain *parts!*

FAMOUS Heavy Duty *hy-gain* BALUNS

BN-86, $79.95. Broadband 50 Ohm ferrite balun. Useable from 3 to 30 MHz. Recommended for all HF Yagi antennas. It provides improved front-to-back ratio. Comes with clamp to bolt to boom, SO-239 connector.

BN-4000B, $109.95. **B**roadband 50 Ohm Yagi current balun is potted to seal out moisture. Rated at 4000 Watts for increased power handling capabilities. 1 to 54 MHz. SO-239 connector. **BN-4000D, $109.95.** dipoles. **BN-4000N, $119.95.** "N" connector.

hy-gain Center Dipole Insulators

C-1, $29.95. Center Insulator for multiband dipole antenna.

C-1C, $29.95. Similar to C-1, but has SO-239 antenna connector.

E-1, $6.95. 6 inch super high-power, high-voltage *end insulator* for Multi-band doublet antenna. Set of 2.

Arrowpoint Anchor

APA-3, $14.95. Up to 2000 lbs. pull-out resistance to secure antennas, towers. Use one per guy wire. **DR-3, $29.95**. Drive Rod.

Glazed Ceramic Insulator

E-2 **79¢** each

E-26 **$4.56** 6-Pack

Extra-strong -- will not break, arc over or melt even under full legal power. Molded ridges give extra-long path to prevent high-voltage breakdown.

Ground Rod

GR-1 **$6.95**

Durable four foot by 3/8 inch diameter *copper bonded* steel earth ground rod. Sharp point makes it easy to insert into ground. Bleed off static/RFI. Prevent RF hot spots. Use several to form a good RF ground.

hy-gain Rotator

HAM-IV **$559.95**

World's most rugged rotator! Many in use after 25 years. Highly resistant to lightning, static, RFI. Bell design gives total weather protection. 15 sq. ft. wind-load, 5-sec. brake delay, 5000 in-lb steel wedge brake, ring gear handles 100,000 PSI, dual 98 ball bearing race, -30° F operation. Max mast $2\frac{1}{16}$”

hy-gain Aluminum Tubing

6063 T832 round, drawn aluminum tubing sold in 2 styles: ***6' standard*** or ***6' slitted*** *one end, (.083" gaps, 1-2" slit lengths*).

Tubing are sized to allow telescoping into one another from .625 OD to 2 inches OD. Select slitted tubing for telescoping. Use Hy-gain Stainless Steel hose clamps to secure.

OD x Wall-Th x ID	6'stnrd; p/n, price/ea	6'slitd; p/n, price/ea.	Ad'l/ft.
.625"x.035"x.555"	810-0625C-6U, $5.70	810-0625C-6S, $6.90	$1.00
.750"x.058"x.634"	810-0750E-6U, $10.55	810-0750E-6S, $12.66	$1.85
.875"x.058"x.759"	810-0875E-6U, $8.72	810-0875E-6S, $9.92	$1.53
1.000"x.058"x.884"	810-1000E-6U, $11.46	810-1000E-6S, $12.66	$2.01
1.125"x.058"x1.009"	810-1125E-6U, $10.03	810-1125E-6S, $11.23	$1.76
1.250"x.058"x1.134"	810-1250E-6U, $11.57	810-1250E-6S, $12.77	$2.03
1.375"x.058"x1.259"	810-1375E-6U, $13.17	810-1375E-6S, $14.37	$2.31
1.500"x.058"x1.384"	810-1500E-6U, $17.95	810-1500E-6S, $19.16	$3.15
1.625"x.058"x1.509"	810-1625E-6U, $21.32	810-1625E-6S, $22.52	$3.74
1.750"x.058"x1.634"	810-1750G-6U, $27.86	810-1750G-6S, $29.62	$4.88
2.000'x.120"x1.760"	810-2000I-6U, $38.93	810-2000I-6S, $41.03	$6.83

hy-gain Stainless Steel Hose Clamps

Part No.	Price	Description
745-3106S	$1.00	#6 Clamp for .75" OD to .875" OD tubing
745-3110S	$1.00	#10 Clamp for 1" OD to 1.125" OD tubing
745-3116S	$1.25	#16 Clamp for 1.25" OD to 1.50" OD tubing
745-3128S	$2.84	#28 Clamp for 1.75" OD to 2" OD tubing

hy-gain Telescopic *Aluminum Mast*

ATM-65 **$199.95**

ATM-65, $199.95. Pictured left. 11-section *multi-purpose* aluminum telescopic pole can be used as a vertical antenna or as a mast. Great for portable, temporary use and permanent use -- traveling, camping, etc. Includes one size of each slitted tube listed above and ten hose clamps. 65 ft. fully extended, 6 ft. collapsed without clamps. Guying required if mast is extended beyond 30 feet. Top section is .625" OD. Bottom section is 2 inches OD x .120 wall.



810-2000I-6W, $44.95 each. Unique tubing has one end slitted and one end swaged to make it stackable. Slide one end into another tubing for longer poles. Secure with standard host clamp. Strong, 2"OD x .120" wall. Good for base sections of vertical antennas. Standard 6-ft. length, longer sections, to 20 ft. available. Add $6.83 each add'l foot. **6** ft. lengths ship by UPS, longer units must ship UPS *oversize*/truck.

hy-gain Base Mount Assembly Kit



877200, $69.95. *New!* Complete ATM-65 base assembly kit with base mounting plate, insulators, hardware.

hy-gain Custom *Precision* Antenna Hardware



BMC-249, $79.95. ***Boom to Mast Clamp***

Heavy duty $1\frac{1}{4}$" OD thick aluminum die casted boom to mast clamp designed for heavy antennas. Supports 2-inch boom antennas, such as the TH-11DX, Long John Monobanders and other beams with a 2" boom. The BMC-249 allows mast to extend past the top of the clamp. This feature allows stacking of several antennas on one mast. Clamp is adjustable for mast sizes from $1\frac{1}{4}$" to $2\frac{3}{4}$" OD. The tilt-over feature permits easy assembly of the elements and simplifies maintenance of the antenna. 4Wx4Hx$1\frac{1}{4}$" thick. Kit comes complete with stainless steel hardware.

Element Insulators These element insulators are made to fit the element bracket (right). Precision injection molded with black UV resisted ABS plastic.

Part No.	Price	Fits these Element sizes	Insulator Size	Fits Element to boom clamp
465216	$3.42	$\frac{7}{16}$" OD	$\frac{7}{8}$"OD x $2\frac{3}{4}$"	163409
461057	$4.40	$\frac{5}{8}$" OD	$1\frac{1}{4}$" OD x 3"	165919
463767	$4.40	$\frac{7}{8}$" OD	$1\frac{1}{4}$" OD x 3"	165919
465833	$4.80	$1\frac{1}{4}$" OD	$1\frac{1}{2}$" OD x 4"	165920

hy-gain TH-series HF Beam Trap Caps

A. 464723, $.75 ea. Trap caps, for large Hy-gain TH-series traps.

B. 466221, $1.59 ea. Trap caps for Hy-gain TH-3Jr. traps.



Element to Boom Clamps

Made from high tensile strength aluminum alloy. Custom die is used to stamp these clamps. No miss-drilled holes. They fit perfect everytime. Required 2 clamps per element. Element Insulators available (left).

Part#	Price	Boom OD"	Element OD		Description	Insulator
			w/o insulator	w/insulator		
161409	$2.71	2"	$\frac{5}{8}$"	---	$2\frac{1}{2}$x7"x.08 Thick, #12	None
163764	$3.80	2"	$\frac{7}{8}$"	$\frac{7}{16}$"	$2\frac{3}{8}$x$7\frac{1}{8}$"x.08 Thick, #4	465216
165919	$5.32	2"	$1\frac{1}{4}$"	$\frac{5}{8}$", $\frac{7}{8}$"	$3\frac{1}{4}$x$7\frac{1}{4}$"x.125 Thick, #13	463767, 461057
165920	$6.28	2"	$1\frac{1}{2}$"	$1\frac{1}{4}$"	$3\frac{1}{4}$x$9\frac{1}{2}$"x.125 Thick, #14	465833
160055	$1.22	$1\frac{1}{4}$"	$\frac{7}{16}$"	---	$\frac{3}{4}$x5"x.063 Thick, #0	None
161422	$3.63	$1\frac{1}{4}$"	$\frac{5}{8}$"	---	$2\frac{1}{2}$x$6\frac{1}{2}$"x.08 Thick, #11	None
165141	$3.76	$1\frac{1}{4}$"	$\frac{7}{8}$"	$\frac{7}{16}$"	$2\frac{5}{16}$x$6\frac{5}{8}$"x.08 Thick, #12	465216
165138	$5.20	$1\frac{1}{4}$"	$1\frac{1}{4}$"	$\frac{5}{8}$", $\frac{7}{8}$"	$2\frac{3}{4}$x$6\frac{5}{8}$"x.08 Thick, #1	463767, 461057
872223	$6.60	Stainless steel screws, nuts and washers for 1 set of element-to-boom clamp				

hy-gain Vertical Antenna Hardware



A. 463011, $14.00, Base tubing insulator, fits $1\frac{1}{4}$" OD tube. Six $\frac{5}{16}$" mounting holes. Super strong fiberglass filled ABS. Used in Hy-tower to isolate tower legs from ground. Tubing not included.

B. 877130, $28.64, Vertical antenna bracket assembly. Includes bracket (C), base cover insulator (D), support insulator (E) and SO-239. Fits $1\frac{1}{4}$" tubing. Tubing not included.

C. 160043-1, $11.84, Base mount bracket. Custom-tooled $\frac{1}{8}$" thick x 12 inch length aluminum bracket with vertical ridges for super strength. Pre-punched holes for SO-239 or N-connector.

D. 863427, $6.90, Base tubing insulator. Molded pin connects base tubing to SO-239 or N-connector.

E. 463056, $3.12, Base antenna support insulator. Made to fit top support of antenna bracket (C). Hole fits $1\frac{1}{4}$" OD tubing.

F. 460316, $12.96, Tubing coupler/insulator. Used to couple/ insulate 1" tube to $\frac{7}{8}$" tubing. Made of fiberglass filled ABS, 5" long.

hy-Gain Tower Bases

Specially designed for *hy-gain* crank-up towers. Complete with base hinge and foundation welded steel-cage. Specify tower model. *Shipped by truck, call for quote.

Model#	Tower	Price	Weight
TB-37	HG-37SS	$299.95	50 lbs.*
TB-52	HG-52SS	$299.95	80 lbs.*
TB-54	HG-54HD	$299.95	90 lbs.*
TB-70	HG-70HD	$349.95	102 lbs.*

Free *hy-gain* Catalog
and Nearest Dealer . . . 800-973-6572
Call your dealer for your best price!

hy-gain®

Antennas, Rotators & Towers
308 Industrial Park Road, Starkville, MS 39759 USA
Toll-free Customer Sales Hotline: 800-973-6572
• **TECH:** 662-323-9538 • **FAX:** 662-323-6551
http://www.hy-gain.com

Prices and specifications subject to change without notice or obligation. © Hy-Gain®, 2007.

Andrew Cinta® Cable Assemblies

From

CABLE X-PERTS, INC.

Connecting You to the World...

ANDREW® Cinta CNT-600

CABLE X-PERTS, INC
800 - 828 - 3340
www.cablexperts.com

HALF INCH SIZE
SHOWN

Connector: **N, PL259, TNC & 7/16,** Burial: **Yes**, UV Resistant: **Yes**.
Shields: **2** (100% bonded foil +90% TC Braid) **VP 87%,** Attenuation 3.9dB @ 2 GHz at 100ft.
Usage 450 MHz and Higher.

PL259
Connector

PL259 CONNECTORS EACH END

Part #	Footage	Price
600C125	125 ft	$235.95
600C100	100 ft	$205.95
600C75	75 ft	$175.95
600C50	50 ft	$145.95
600C25	25 ft	$115.95
600C3	3 ft	$ 88.95

PL259(UHF) TO "N" MALE CONNECTOR

Part #	Footage	Price
600CN100	100 ft	$187.95

"N" MALE CONNECTORS EACH END

Part #	Footage	Price
600N100	100 ft	$168.95
600N75	75 ft	$139.95
600N50	50 ft	$108.95
600N25	25 ft	$ 77.95
600N15	15 ft	$ 66.49
600N6	6 ft	$ 55.49



Or CREATE YOUR OWN CUSTOM LENGTH ON-LINE.

ANDREW® Cinta CNT-400



RG8U SIZE
SHOWN

Connector: **N, PL259, TNC, SMA, BNC & QMA,** Burial: **Yes**, UV Resistant: **Yes**.
Shields: **2** (100% bonded foil +90% TC Braid) **VP 85%,** Attenuation 6.0dB @ 2 GHz at 100ft.
Usage 450 MHz and Higher.

PL259
Connector

PL259 CONNECTORS EACH END

Part #	Footage	Price
400C100	100 ft	$ 82.49
400C75	75 ft	$ 63.95
400C50	50 ft	$ 45.49
400C25	25 ft	$ 27.49
400C6	6 ft	$ 14.95
400C3	3 ft	$ 11.95

"N" MALE CONNECTORS EACH END

Part #	Footage	Price
400N50	50 ft	$ 54.95
400N6	6 ft	$ 22.95
400N3	3 ft	$ 20.95

N
Connector

Or CREATE YOUR OWN CUSTOM LENGTH ON-LINE.

ANDREW® Cinta CNT-240



RG8X SIZE
SHOWN

Connector: **N, PL259, TNC, SMA, BNC & QMA,** Burial: **Yes**, UV Resistant: **Yes**.
Shields: **2** (100% bonded foil +90% TC Braid) **VP 84%,** Attenuation 3.0dB @ 150 MHz at 100ft.
Usage 1 MHz and Higher.

PL259
Connector

PL259 CONNECTORS EACH END

Part #	Footage	Price
240C6	6 ft	$ 14.75
240C3	3 ft	$ 12.95

Or CREATE YOUR OWN CUSTOM LENGTH ON-LINE.

Prices subject to change without notice or obligation.

What makes us better than the competition?

- Quality products at competitive prices.
- Prompt service and customer attention.
- State-of-the-art cable assembly manufacturing facility.
- Stringent quality control to ensure top-quality finished products.
- A large inventory of raw materials.
- Short lead times on custom cable assemblies.
- Experienced engineering and knowledgeable sales staff.
- Centrally located in the Chicago area.

All assemblies are tested to ensure optimum performance.

Many more cables listed on-line
www.cablexperts.com
or call: 800-828-3340

CABLE X-PERTS, INC.
Connecting You to the World...

www.cq73.com

High Sierra AntennAs

Professional Antennas for the Amateur Since 1993

HF Transceiver Speaker

HF Antenna Tripod Deluxe

HF Antenna
Stake Hole Mount



HF Antenna
Magnet Mount

HF, WX, AM, FM, TV
Solar, Battery, AC
Crank Powered
Radio

Explore *All of HF* with Your Sidekick Antenna

Motor Driven Remotely Tunes 75 to 6 Meters
160 Meters with an 8 Foot Whip & Six Shooter Capacity Hat
1.5:1 or Less Typical SWR
Rated at 200 Watts
Includes 3 Foot Stainless Black Whip & Standard Controller
Can Be Used Just About Anywhere!
No Hazardous Beryllium
Weighs Less Than 3 Pounds
EZ-Tune Controllers Available
See Our Website www.cq73.com for Package Deals

High Sierra AntennAs

530-273-3415 www.cq73.com

See Our New Website with Lots of HF Products

TIMEWAVE
TECHNOLOGY INC.

Introducing the... AntennaSmith™!

AntennaSmith™
TIMEWAVE
POWER
LOAD
TUNE

Patent Pending

TZ-900 *Antenna Impedance Analyzer*

2 Sec Sweeps, Sweep Memories, 1 Hz steps, Manual & Computer Control w/software, USB, low power. Rugged Extruded Aluminum Housing - ***Take it up the tower!***


6
SWR
1.75 @ 7.150.000
1
6.0
8.3
MODE
Swp
GRAPH
SWR
FREQ.
-> Ctr
SWP
SETUP

- **Full Color TFT LCD Graphic Display**
- **Visible in Full Sunlight**
- **0.2 - 55 MHz**
- **SWR**
- **Impedance (Z)**
- **Reactance (r+jx)**
- **Reflection coefficient (ρ, θ)**
- **Smith Chart**

NEW!

Rev. 2
Now Shipping!


x=16
x=50
Smith
6.0
8.3
x=0
r=0
16
50
100
x=-16
x=-50
SWR
2.0:1
7.150.000
MODE
Swp
GRAPH
Smith
FREQ.
-> Ctr
SWP
SETUP

Check Your Antennas and Transmisson Lines
Once you use the TZ-900 -
you'll never want to use any other!

and... our *new* line-up

Data & Rig Control:

- **HamLinkUSB™ Rig Control Plus**
  TTL serial interface with PTT
- **U232™ RS-232-to-USB Adapter**
  Universal Conversion Module
  replaces PCB-mount DB-9 & DB-25
- **PK-232/USB Multimode Data Controller**
  (upgrades available)
- **PK-96/USB TNC**
  (upgrades available)
- **HamLinkBT-Lite™ Bluetooth Rig Control**
  Coming soon for your radio!
- **HamLinkBT™ Bluetooth Wireless Remote Control Head**
  Coming soon for Kenwood, Icom & Yaesu!

Noise & QRM Control:

- **DSP-599zx Audio Signal Processor**
- **ANC-4 Antenna Noise Canceller**

From the Timewave Fountain of Youth - **Upgrades for many of our DSP & PK products. Call Us Now!**

Timewave Technology Inc
1025 Selby Ave., Suite 101
St. Paul, MN 55104 USA

www.timewave.com
sales@timewave.com

651-489-5080
Fax 651-489-5066

HEIL • GAP • DIAMOND • SPI-RO • HUSTLER • MFJ • COMET

• WEST MOUNTAIN RADIO PRODUCTS •ANDREWS •AMERITRON • CUSHCRAFT • VECTRONICS •

• TARHEEL ANTENNAS • TUBRO TUNER • HY-GAIN • LARSEN • ISOTRON • BELDEN • LMR

WB0W, INC.

800-626-0834

816-364-2692 • Fax 816-364-2619
P.O. Box 8547, St. Joseph, MO 64508

WWW.WB0W.COM

E-mail WB0W@WB0W.COM



Ginpole for Rohn 25-55 and round leg towers up to 2" O.D. Shown here with optional base pulley. Also ginpoles for BX type Towers.

Tower Insulators for Rohn 25G
$399.00

BX Tower & Accessories



ROHN/Radian Tower & Accessories

25G/45G/55G $99/199/259

KENDOO Batteries

Nifty! Reference Guides
Free Shipping in Continental U.S.

RF Connectors

TURBO TUNER $239.00
Automatic Motorized Antenna Controller

ARRL Books, Cd's, & Study Guides

25% off if you mention ARRL Antenna Handbook Ad!

WORLD'S SMALLEST MOTORIZED ANTENNA

Model 100
10-80 mtrs.
$349



Model 200
6-80 mtrs.
$369



Model 75
"Stubby"
10-80 mtrs.
$349



Little Tarheel II
6-80 mtrs.
$349

TarheelAntennas

Get the quality that only CNC machined blueprinted components in either aircraft aluminum or stainless steel can offer.

ANTENNA SPECIFICATIONS

Little Tarheel II * 3.5 Mhz-54.0 MHz * 200 watts PEP * 1-1/4" coil 16" base * 32" whip * 1.9 lbs * 48" @ 54.0 MHz * 54" @ 3.5 MHz

Model 75 "Stubby" * 3.7 Mhz - 34.0 MHz * 400 watts PEP * 2" coil 16" base * 6' whip * 5.5 lbs * 7' 6" @ 54 MHz * 8' @ 3.5 MHz

Model 100 * 3.4 Mhz - 30.0 * 1.5 Kw PEP * 2" coil * 3' base * 6' whip 8 lbs * 9' 4" tall @ 30.0 MHz * 12' tall @ 3.5 MHz

Model 200 * 3.4 Mhz - 28.0 MHz * 1.5 Kw PEP * 2" coil * 4' base 6' whip * 10' 4" tall @ 28.0 MHz * 12' tall @ 3.5 MHz

Model 300 * 1.8 Mhz - 30.0 MHz * 400 watts PEP * 2" coil * 3' base 6' whip * 8.5 lbs * 9' 4" tall @ 30.0 MHz * 11' tall @ 1.8 MHz

Model 400 * 1.8 Mhz - 28.0 MHz * 400 watts PEP * 2" coil * 4' base 6' whip * 9 lbs * 10' 4" tall @ 28.0 MHz * 12' tall @ 1.8 MHz

All Prices Subject to Change without Notice

TE SYSTEMS AMPS • LDG • ROHN • BX TOWERS • GINPOLES•

BUDDIPOLE

BUDDIPOLE

www.buddipole.com

The Buddipole™ Portable Dipole fits in your travel bag and assembles in minutes. The Buddipole is more than an antenna, it's a versatile system for launching your signal. Optimized for transmit power and proven for DX work, the Buddipole is the secret weapon used by HF portable operators all over the world.

What is the Buddipole?

- > Multi-band design works 9 bands – 40 meters thru 2 meters with one set of adjustable coils!
- > Rated from QRP to 250 watts PEP
- > Modular Design – create dozens of different antennas with interchangeable parts
- > Rotatatable/Directional
- > Lightweight, rugged components
- > Optional Rotating Arm Kit allows users to instantly change antenna configurations
- > Used by the U.S. Military Special Forces and Emergency Services Groups throughout the world

Antenna Systems starting at $199!

Call or write for free brochure!

2390 Templeton Dr.
Redding, CA 96002

tel: (530) 226 8446
fax: (530) 232 2753
info@buddipole.com

THE PERFECT ANTENNA

For almost 2 decades GAP has stated there is no perfect antenna. No singular antenna can do it all. That is why we designed a family of antennas that utilize the patented (# 5.592.183), GAP Technology, to give you options. Within this family is the antenna or antennas right for you. If deed restrictions or visibility are a problem, take a look at the Eagle DX. If you are looking for a simple general coverage antenna with capture area, consider the Challenger DX. What about a low band antenna with great 40m and 80m performance? Then the Voyager DX is worth your attention. If you seek the most popular multiband antenna, then the Titan DX will end your search.

The GAP Technology eliminates traps, electromechanical devices and coils, which can increase loss and decrease reliability. Simplicity in design, results in a very user friendly assembly process. Slide one tube over another until the big hole lines up with the little and insert a screw. A GAP is pretuned, will handle 1500 watts PEP and provides instantaneous coverage with a VSWR under 2:1 across the entire band.*

CATCH THE WAVE



TITAN DX

10m, 12m, 15m, 17m, 20m, 30m, 40m, & 80m

25' tall 25 lbs

Mounts on 1-1/4" OD mast

No radials required.

***VSWR under 2:1 on 80m 100 KHz**



CHALLENGER DX

2m, 6m, 10m, 12m, 15m, 20m, 40m, & 80m

31.5' tall 21 lbs

Drop in ground mount supplied.

3 counterpoises required 25' long.

***VSWR under 2:1 on 80m 130 KHz**



VOYAGER DX

20m, 40m, 80m, & 160m

45' tall 39 lbs

Supllied with hinged ground mount.

3 counterpoises required 57' long.

***VSWR under 2:1 on 160m 90 KHz**



EAGLE DX

10m, 12m, 15m, 17m, 20m & 40m

21' tall 19 lbs

Mounts on 1-1/4" OD mast

No radials required.

***40m limited to 300 watts**

QUICK TILT

The easy way to raise and lower your antenna, support mast or flagpole. Works with most antennas.

GROUND MOUNT



Accomdates
1 1/4" 2" OD Mast

LADDER MOUNT



STAINLESS STEEL & ALUMINUM CONSTRUCTION

ANTENNA ACCESSORIES FOR ALL

GAP
ANTENNA PRODUCTS

(772) 571-9922
Visit us at:
gapantenna.com

GUY KITS

Insure your antenna or support mast against the elements with a Guy Kit.



STAINLESS STEEL & ALUMINUM CLAMP
3/32" UV Protected Black Double Braided Polyester Rope

Your Powerpole Headquarters
More Powerpole Stuff Than *Anybody*

A huge variety of ready-made cables with Anderson Powerpoles for ICOM (***including the new IC-7000***), Kenwood (***including the TS-480***), Yaesu, Alinco, and most other HF, mobile, and handheld rigs. Power supply cables for almost any source — home, mobile, or portable. Accessories including panel mounts, mounting plates, crimpers, and wire.

See us at Hamfests from Maine to Maryland, or visit our Web Site for all of your Powerpole needs

Of course, we also stock a full selection of our famous PaneRelief™ coax feed-through panels, and TuneRite™ tuning modules for ICOM, Yaesu, and Kenwood.

Quicksilver Radio Products • Meriden, Conn.

www.qsradio.com

IIX EQUIPMENT LTD.

▪ Custom Fabrication ▪ Hot Dip Galvanizing ▪

MM-Series Mobile Mounts

Rotating Standoff

Standoffs and Gin Poles



Climbing Steps

Gin Pole KIts

Cell: 708-337-8172
4421 West 87th Street, Hometown, IL 60456
Email: iix@w9iix.com
708-423-0605 ▪ Fax: 708-423-1691
www.w9iix.com

VISA MasterCard DISCOVER PayPal

Electronic Parts

1000s of Component Parts
– No Minimum Order –

– Shortwave – Ham Gear – Scanners –
– AM/FM Radios – Antennas – Coax –
– Accessories – Books – Computer Cables –

Visa/ MC/AMEX/Discover

Dave's Hobby Shop

600 Main Street, Van Buren, Arkansas
479-471-0750
www.daveswebshop.com

Antennas to Build— Ideas to Experiment With



Vol 1: ARRL's Wire Antenna Classics

Vol 2: *More* Wire Antenna Classics

Hang 'em high or hang 'em low, wires are the best antennas to use to get on the air simply and inexpensively. Experience the satisfaction of building your own wire antennas.

Now you can enjoy a collection of the best antenna articles from ARRL publications. Inside these books, you'll find more than just creative ideas. Each is filled with innovative designs that work!

- Dipoles
- Loops
- Collinears
- Wire Beams
- Vertically Polarized
- Multiband Antennas

and more…

– 2 Volumes! –

Vol 1: ARRL's Wire Antenna Classics
ARRL Order No. 7075

Vol 2: *More* Wire Antenna Classics
ARRL Order No. 7709

Available from ARRL and dealers everywhere!

SHOP DIRECT *or call for a dealer near you.*
ONLINE WWW.ARRL.ORG/SHOP
ORDER TOLL-FREE 888/277-5289 (US)

ARRL ***The national association for AMATEUR RADIO***

225 Main Street
Newington, CT 06111-1494 USA

AB 3/2007

Big Winners from Array Solutions

PowerMaster HF Coupler
SOURCE
LOAD
COUPLER CALIBRATION
ARRAY SOLUTIONS
www.arraysolutions.com
MADE IN U.S.A.
TO DISPLAY
F V 1.00 1127W
POWER MASTER
VSWR
POWER
ALARM
MENU
MODE SELECT

PowerMaster

Watt/VSWR Meter

- Sets the leading edge for all watt/vswr meters to follow
- Unheard of accuracy for the price
- Fast Bright reading meter
- Application software included
- Upgradeable via Internet

$430

AIM 4170
POWER
ON-OFF
RF
ARRAY SOLUTIONS
RUN

AIM 4170

Antenna Analyzer

- Most advanced vector impedance analyzer at a fraction of the cost
- Accurate and easy to use
- Application software included
- Lab instrument quality
- Upgradeable via Internet

$400


OptiBeam 3 element 80 Yagi

OB3-80+

OptiBeam Antennas

German Engineering means High Performance and Reliability

Prosistel Rotators

Strongest Rotators on the Market
Prosistel
PST 71 DC

TERMINATION
1
2
3
4
5
6
7
8
DIRECTION
SW
NW
NE
SE
ON
POWER
OFF
ARRAY SOLUTIONS
K9AY Loop System
PREAMP

AS-AYL-4

NEW 4 Direction K9AY Loop Antenna
Hear What You've Been Missing on the Low Bands

www.arraysolutions.com

Phone 972-203-2008
sales@arraysolutions.com
Fax 972-203-8811

We've got your stuff!

WX0B
ARRAY SOLUTIONS

Quality Radio Equipment Since 1942

AMATEUR TRANSCEIVERS

Universal Radio is your authorized dealer for all major amateur radio equipment lines including: Alinco, Icom, Kenwood and Yaesu.

SHORTWAVE RECEIVERS

Whether your budget is $50, $500 or $5000, Universal can recommend a shortwave receiver to meet your needs. Universal is the *only* North American authorized dealer for *all* major shortwave lines including: Elad, Icom, Yaesu, Japan Radio Company, Ten-Tec, Grundig, etón, Sony, Sangean, Palstar, RFspace and Kaito.

WIDEBAND RECEIVERS

Universal Radio carries a broad selection of wideband and scanner receivers. Alinco, AOR, Icom, Yaesu and Uniden models are offered at competitive prices. Portable and tabletop models are available.

ANTENNAS AND ACCESSORIES

Your antenna is just as important as your radio. Universal carries antennas for every need, space requirement and budget. Please visit our website or request our catalog to learn more about antennas.

BOOKS

Whether your interest is amateur, shortwave or collecting; Universal has the very best selection of radio books and study materials.

■ USED EQUIPMENT

Universal carries an extensive selection of used amateur and shortwave equipment. All items have been tested by our service department and carry a 60 day warranty unless stated otherwise. Request our monthly printed used list or visit our website:

www.universal-radio.com

◆ VISIT OUR WEBSITE

Guaranteed lowest prices on the web? Not always. But we ***do*** guarantee that you will find the Universal website to be the **most** informative.

www.universal-radio.com

◆ VISIT OUR SHOWROOM



Showroom Hours

Mon.-Fri.	10:00 - 5:30
Thursday	10:00 - 7:00
Saturday	10:00 - 3:00

universal
radio inc.

FREE 112 PAGE CATALOG

Our informative print catalog covers everything for the amateur, shortwave and scanner enthusiast. All items are also viewable at:

www.universal-radio.com

Universal Radio, Inc.
6830 Americana Pkwy.
Reynoldsburg, OH 43068
➤ 800 431-3939 Orders
➤ 614 866-4267 Information
➤ 614 866-2339 Fax
➤ dx@universal-radio.com

universal radio inc.

✓ Established in 1942.
✓ We ship worldwide.
✓ Visa, Master and Discover cards.
✓ Used equipment list available.
✓ Returns subject to 15% restocking fee.

The ARRL Antenna Compendium

Volume 7


$24.95
The ARRL
Vol. 7
ANTENNA
COMPENDIUM
Proven, practical antenna designs from the world of Amateur Radio.
ARRL AMATEUR RADIO

Hooray for antennas! This is the seventh in the very popular **ARRL Antenna Compendium** series. Inside, you'll find articles covering a very wide range of antenna-related topics:

- 30, 40, 80 and 160-Meter Antennas
- Measurements and Computations
- Mobile Antennas
- Multiband Antennas
- Practical Tips
- Propagation and Ground Effects
- Quad Antennas
- Special Antennas
- Stealth Antennas
- Tuners and Transmission Lines
- Vertical Antennas
- VHF/UHF Antennas
- Wire Antennas
- Yagi Antennas

And, this volume includes even more articles on low-band antennas and operating, and great designs for operating on the road-from cars, vans or motor homes.

ARRL Order No. 8608
Only $24.95*
*shipping $8 US (ground)/ $13.00 International

SHOP DIRECT *or call for a dealer near you.*
ONLINE WWW.ARRL.ORG/SHOP
ORDER TOLL-FREE 888/277-5289 (US)

ARRL *The national association for* ***AMATEUR RADIO***

AB 3/2007

Life is a JOURNEY. Enjoy the ride!

COMET and Maldol

Base Antennas



CHA-250B VSWR graph

"One person can effortlessly raise the antenna at night when no one can spot it, and take it down before daybreak. This antenna is also a great choice for portable operations, such as quick and easy mini-DXpedition to a campground or a nice tropical island! In short, the Comet CHA-250B is simple to assemble, painless to elevate and is easy on the eyes, while at the same time getting you on 6 meters thru 80 meters without the requirement of an antenna tuner and ground radials. You'll even be able to work some DX while you're at it!" – Dan Dankert N6PEQ

COMET NEW CHA-250B BROADBAND HF/6M GROUND-PLANE ANTENNA

A newly designed broadband vertical with NO GROUND RADIALS. EXTREMELY easy to assemble, requires no tuning or adjustments and VSWRis under 1.5:1 from 3.5-57MHz! • TX: 3.5MHz – 57MHz • RX: 2.0 – 90MHz • VSWR is 1.5:1 or less, continuous • Max Power: 250W SSB/125W FM• Impedance: 50 Ohm • Length: 23' 5" • Weight: 7 lbs. 1 oz. • Conn: SO-239 • Mast Req'd: 1" – 2" dia. • Max wind speed: 67MPH

COMET GP-15 TRI-BAND 52/146/446MHZ BASE REPEATER ANTENNA

Wavelength: 52MHz 5/8 wave • 146MHz 5/8 wave x 2 • 446MHz 5/8 wave x 4 • Max Pwr: 150W • Length: 7'11" • Weight: 3lbs. 1oz. • Conn: Gold-plated SO-239• 2MHz band-width after tuning (6M) • Construction: Single-piece fiberglass

COMET CX-333 TRI-BAND 146/220/446MHZ BASE REPEATER ANTENNA

Wavelength: 146MHz 5/8 wave x 2 • 220MHz 5/8 wave x 3• 446MHz 5/8 wave x 5 • Max Pwr: 120W • Length: 10'2" • Weight: 3lbs. 1oz.• Conn: Gold-plated SO-239 • Construction: Fiberglass, 2 Sections

COMET GP-3 DUAL-BAND 146/446MHZ BASE REPEATER ANTENNA

Wavelength: 146MHz 6/8 wave • 446MHz 5/8 wave x 3 • Max Pwr: 200W • Length: 5'11"• Weight: 2lbs. 9ozs. • Conn: Gold-plated SO-239 • Construction: Single-piece fiberglass

COMET GP-6 DUAL-BAND 146/446MHZ BASE REPEATER ANTENNA

Wavelength: 146MHz 5/8 wave x 2 • 446MHz 5/8 wave x 5 • Max Pwr: 200W • Length: 10'2"• Weight: 3lbs. 8ozs. • Conn: Gold-plated SO-239 • Construction: Fiberglass, 2 Sections

Maldol HVU-8 ULTRA-COMPACT 8 BAND HF/VHF/UHF VERTICAL ANTENNA

80/40/20/15/10/6/2M/70cm Only 1/2 the traditional size and weight of vertical HF antennas, and it includes 2M/70cm! Unique radial system rotates for balcony installations, **the radials can all be rotated to one side.** • Wavelength: HF and 6M: 1/4 wave • 2M: 1/2 wave • 70cm: Two 5/8waves in phase • Impedance: 50 Ohm • Max Power: HF 200W SSB • 6M–70cm: 150W FM• Conn: SO-239 • Height: Only 8'6" • Weight: 5lbs. 7ozs.



COMET GP-9 / GP-9N DUAL-BAND 146/446MHZ BASE REPEATER ANTENNA

BEST SELLER!• Wavelength: 146MHz 5/8 wave x 3 • 446MHz 5/8 wave x 8 • Max Pwr: 200W• Length: 16' 9"" • Weight: 5lbs. 11ozs. • Conn: GP-9 Gold-plated SO-239 • GP-9N Gold-plated N-type female • Construction: Fiberglass, 3 Sections

WI-FI/802.11B/LAN/HSMM
ACCESS POINT ANTENNAS

COMET GP-24 2.4GHZ ACCESS POINT ANTENNA The standard high gain 2.4GHz access point antenna for maximum range/signal strength. • 2400-2500MHz • Length: 5'10" • Weight: 2lbs. 9ozs. • Conn: Gold-plated N-female • Construction: Heavy-duty white fiberglass radome

COMET GP-24-3 The same physical high gain 2.4GHz antenna as the GP-24,but with a 3-degree electrical downtilt to concentrate the signal to the horizon and below

COMET GP-24-S MEDIUM GAIN ACCESS POINT ANTENNA For applications where maximum distance is not as important as a solid signal around and directly below the antenna. • Length:3'9" • Weight: 1lb. 14ozs. • Conn: Gold-plated N-female • Construction: Heavy-duty white fiberglass radome

COMET and Maldol Antennas

For a complete catalog, call or visit your local dealer.
Or contact NCG Company.1275 N. Grove Street, Anaheim, CA 92806
714-630-4541 • 800-962-2611 • FAX 714-630-7024 • www.natcommgroup.com

Alphabet soup got you confused?



There's only one letter you need . . . ***it's the G .***

We're the name you've known and trusted for over 56 years!

Our name stands for . . .

Quality

Integrity

Enduring Strength

Choose the original Rohn G Series.
Because everyone knows "G" comes before all the rest!

ROHN™
Products

6718 W. Plank Road ~ Peoria, IL 61604
Ph. 309-697-4400 ~ Fax 309-697-5612
www.radiancorp.com

Division of Radian Communication Services, Inc.



ARRL's Yagi Antenna Classics

—Yagis, Quads, Loops, and other Beam Antennas

Contents:

- **Monobanders:** Beams for your favorite band
- **Multibanders:** Beams that cover two or more bands
- **HF, VHF and UHF Beams:** From 80 meters to 2304 MHz
- **Computer Modeling:** Optimize your beam's performance
- **Towers, Masts and Guys:** Your beam needs solid support
- **The "WOW" Factor:** Can you believe this?


ARRL's Yagi
Antenna
Classics
Yagis, Quads, Loops and
other Beam Antennas
A collection of
the best articles
from ARRL
publications

ARRL *The national association for* ***AMATEUR RADIO***

SHOP DIRECT *or call for a dealer near you.*
ONLINE WWW.ARRL.ORG/SHOP
ORDER TOLL-FREE 888/277-5289 (US)

ARRL Order No. 8187
Only $17.95*
*shipping $7 US (ground)/ $12.00 International

AB 3/2007

“Being the Original has its advantages.”



UNADILLA

ANTENNA MANUFACTURING COMPANY

VHF - UHF - HF Applications

Special Models for Beams, Dipoles and Line Isolation

Manufacturing Baluns and Accessories for over 40 years

Ham - Commercial - Industrial - Government - Military

PO BOX 4215-BV
ANDOVER, MA 01810
PLANT 978 975 2711

www.unadilla.com

No Antenna No Ham Radio!

Antenna Zoning for the Radio Amateur

by Fred Hopengarten, K1VR


$49.95
ANTENNA ZONING
FOR THE RADIO AMATEUR
Everything you and your attorney need to know to obtain a permit for your antenna-support system
PERMIT TO BUILD
Fred Hopengarten, K1VR

Here’s help navigating the thicket of ordinances and bylaws to obtain a building permit for your antenna system. Don't get caught in the crazy quilt of regulations.

Everything you and your attorney need to know to obtain a permit for your antenna-support system

CD-ROM included containing detailed case law, customizable form letters and other invaluable aids.

Providing your attorney with this information can save many hours—and many dollars!

Antenna Zoning for the Radio Amateur
ARRL Order No. 8217
Only $49.95*
*shipping $10 US (ground)/ $15.00 International

ARRL *The national association for AMATEUR RADIO*

SHOP DIRECT *or call for a dealer near you.*
ONLINE WWW.ARRL.ORG/SHOP
ORDER TOLL-FREE 888/277-5289 (US)

AB 3/2007

Hang your
next wire antenna with the

EZ HANG KIT!



Comes with everything you need:

- The original EZ Hang
- The EZ Winder
- A spare set of Bands and six weights and clips.

EZ HANG

Code AB

2217 Princess Anne St., Suite 105-6
Fredericksburg, VA 22401 ▪ Phone: 540-286-0176

Check Our Website for New Products

www.ezhang.com

High-Performance Remote Automatic Antenna Tuners

Places the Tuner Circuitry at the Antenna Feedpoint for

Maximum Efficiency!



1.8 to 30 MHz Balanced
π-Network Antenna Tuners:

- **AT-502** – 200W SSB/CW
  2 x 85 Memories.................... $699.95
- **AT-515** – 1.5kW SSB/CW
  85 Memories........................ $1,699.95

Desktop Control Unit with LCD; Weather-Protected Remote Tuner Unit (to IP65/66 standards).

www.hamware.de

Int'l: Klaus Bemmerer ■ **service@hamware.de**
Tel: +49 4371 869145
US: Dillon RF Systems ■ **dillonel@mtaonline.net**

Backyard Antennas

Simple techniques for building high performance antennas

- End-fed and Center-fed Antennas
- Rotary Beams
- Loops
- Tuning Units
- VHF/UHF Antennas
- Antenna and Mast Construction
- Transmission Lines
- Estimating and Measuring the Performance of your Antenna



ARRL The national association for AMATEUR RADIO
SHOP DIRECT *or call for a dealer near you.*
ONLINE WWW.ARRL.ORG/SHOP
ORDER TOLL-FREE 888/277-5289 (US)

Backyard Antennas
ARRL Order No. RBYA
Only $34.95*
*shipping $9 US (ground)/ $14.00 International

AB 3/2007

ADVANCED SPECIALTIES INC.

New Jersey's Communications Store

VX-7R
Quadband
Submersible HT

YAESU *Choice of the World's top DX'ers*
ALINCO *AMATEUR RADIO'S VALUE LEADER*

DR-635T
Hi Tech FM Mobile
Dual Band

Authorized Dealer

ALINCO * LARSEN * COMET * MALDOL * MFJ * UNIDEN
LDG * ANLI * RANGER * YAESU * TRAM * PROCOMM * PYRAMID

FT-857D
HF, 6M, 2M, 70 CM

AMATEUR RADIO – SCANNERS – BOOKS
ANTENNAS – MOUNTS – FILTERS
ACCESSORIES & MORE

FT-2800M
65W 2M Mobile

Uniden
BCD-396T
Digital Trunk
Tracking
Scanner

Closed Sunday & Monday
Orders/Quotes 1-800-926-9HAM
(201)-VHF-2067
114 Essex Street, Lodi, NJ 07644

FT-8900R
10M, 6M, 2M,
70 CM FM Mobile

Big Online Catalog at
www.advancedspecialties.net

Simple and Fun Antennas for Hams

Lots and lots of real world, practical antennas you can BUILD YOURSELF!



Contents:

- Your First VHF Antenna
- Your First HF Antenna
- Facts About Transmission Lines
- Antenna Masts and Supports
- HF Verticals
- More Simple and Fun Antennas for VHF and UHF
- More HF Dipoles
- Dual-Band VHF/UHF Antennas
- An HF Vertical That Needs No Radials—Try the HVD
- Yet More HF Dipoles
- More Facts About Feed Lines
- A Potpourri of Antenna Ideas
- VHF Beam Antennas
- Towers
- HF Beam Antennas
- Getting the Most Out of Your Antenna

Simple and Fun Antennas for Hams
ARRL Order No. 8624
Only $22.95*

*shipping $8 US (ground)/ $13.00 International

SHOP DIRECT *or call for a dealer near you.*
ONLINE WWW.ARRL.ORG/SHOP
ORDER TOLL-FREE 888/277-5289 (US)

ARRL The national association for AMATEUR RADIO

AB 3/2007

Vertical Antennas are Everywhere

On cell phones, broadcast towers, portable radios and vehicles. And for good reason! Here are the best articles on vertical antennas from *QST* and ARRL publications.

- Theory and Modeling
- VHF and UHF
- Directional Arrays
- Radials
- Single-Band and Multi-Band HF Vertical Antennas
- Ground Systems
- Portable Antennas
- Phased Vertical Arrays

and more….

The Sky's the Limit!

$12
VERTICAL ANTENNA CLASSICS
The best articles from ARRL publications
VERTICAL
$17.95
More VERTICAL ANTENNA CLASSICS
The best articles from ARRL Publications
ARRL

Vertical Antenna Classics
ARRL Order No. 5218
Only $12*

More Vertical Antenna Classics Second Edition
ARRL Order No. 9795
Only $17.95*

*shipping $7 US (ground)/ $12.00 International

SHOP DIRECT *or call for a dealer near you.*
ONLINE WWW.ARRL.ORG/SHOP
ORDER TOLL-FREE 888/277-5289 (US)

ARRL *The national association for AMATEUR RADIO*

AB 3/2007

KØXG Systems

Antenna Rotation Equipment

Orbital Ring Rotor

Unit shown is the 45/55g Orbital Ring rotor with MonstIR Yagi installed.

Models available for any size tower (including cell towers). For any size boom, or tower boom.

1117 Highland Park Dr., Bettendorf, IA 52722
email: k0xg@k0xg.com
(563) 340-5111

Visit our Web Site at:
www.KØXG.com

A picture is worth a thousand words...



With the

ANTENNA MODEL™

wire antenna analysis program for Windows® you get true 3D far field patterns that are far more informative than conventional 2D patterns or wire-frame pseudo-3D patterns.

Now you can have all the advantages of the MININEC code and Sommerfeld-Norton ground too, down to 0.02 wavelengths above ground. No split load, split source, or equivalent monotaper element approximations are needed. Enjoy superior graphing and 2D far field plot comparison capability.

Describe the antenna to the program in an easy-to-use spreadsheet-style format, and then with one mouse-click the program shows you the antenna pattern, front to back ratio, front to rear ratio, input impedance, efficiency, SWR, and more.

An optional **Symbols** window with formula evaluation capability can do your calculations for you. A **Match Wizard** designs Gamma, T, or Hairpin matches for Yagi antennas. A **Clamp Wizard** calculates the equivalent diameter of Yagi element clamps. **Yagi Optimization** finds Yagi dimensions that satisfy performance objectives you specify. Major antenna properties can be graphed as a function of frequency.

There is **no built-in segment limit**. Your models can be as large and complicated as your system permits.

ANTENNA MODEL is only $90. This includes a Web site download **and** a permanent backup copy on CD-ROM. Visit our Web site for more information about **ANTENNA MODEL**.

Teri Software
P.O. Box 277
Lincoln, TX 78948

www.antennamodel.com
e-mail **sales@antennamodel.com**
phone **979-542-7952**

Fourth Edition

ON4UN's Low-Band DXing

Antennas, Equipment and Techniques for DXcitement on 160, 80 and 40 Meters

$39.95

ON4UN's

Low-Band DXing

Fourth Edition

Antennas, Equipment and Techniques for DXcitement on 160, 80 and 40 Meters

John Devoldere, ON4UN

Now includes the fully-searchable book on CD-ROM!

by John Devoldere, ON4UN

Thoroughly updated with entirely new material on low-band antennas and high-gain transmitting arrays. Includes new insights and new design techniques for receiving antennas and vertical arrays.

"John is one of the most recognizable figures on the DX scene. He has spent more than 1,500 hours rewriting and updating **ON4UN's Low-Band DXing**, known far and wide as the 'low-bander's bible.'"—R. Dean Straw, N6BV, Editor

CD-ROM included! This edition is bundled with the fully searchable and complete book on **CD-ROM** for *Windows*® and Macintosh® systems. (Also contains additional **ON4UN software** and over 2000 quality pictures.)

ARRL Order No. 9140—**$39.95***

*shipping: $9 US (ground)/$14 International

Shipping and Handling charges apply. Sales Tax is required for orders shipped to CA, CT, VA, and Canada.

Prices and product availability are subject to change without notice.

ARRL *The national association for AMATEUR RADIO*

SHOP DIRECT *or call for a dealer near you.*
ORDER TOLL-FREE 888/277-5289 (US)
ONLINE WWW.ARRL.ORG/SHOP

AB 3/2007

Basic Radio

Understanding the
Key Building Blocks



Finally — an introduction to radio FOR EVERYONE! — what it does and how it does it.

Basic Radio reveals the key building blocks of radio: **receivers, transmitters, antennas,** and **propagation.** Includes simple, build-it-yourself projects to turn theory into practice.



Basic Electronics

The foundations taught in this book will prepare you for more advanced concepts in electronics. The text is written in an easy-to-understand style that nontechnical readers will enjoy. You don't have to be an engineer or a math whiz to enjoy the thrill of experimenting with electronics circuits!

Basic Radio
ARRL Order No. 9558
Only $29.95*

Understanding Basic Electronics
ARRL Order No. 3983
Only $29.95*
*shipping $9 US (ground)/ $14.00 International

SHOP DIRECT *or call for a dealer near you.*
ONLINE WWW.ARRL.ORG/SHOP
ORDER TOLL-FREE 888/277-5289 (US)

ARRL *The national association for* ***AMATEUR RADIO***

AB 3/2007

HYBRID-QUAD ANTENNA

MQ-24SR

MINI
HF BEAM



MQ-1 Four-Band Antenna
6,10,15,20 Meters, Two element
MQ-24SR Four-Band Antenna
6,10,15,20 Meters, Enhanced reflector
MQ-34SR Four-Band Antenna
6,10,15,20 Meters, Three element, E/Ref.
MQ-26 Six-Band Antenna
6,10,12,15,17,20 Meters, Two element
MQ-26SR Six-Band Antenna
6,10,12,15,17,20 Meters, Enhanced Refl.
MQ-36SR Six-Band Antenna
6,10,12,15,17,20 Meters,Three element,E/R

T.G.M. Communications

121 Devon St. Stratford,
ON Canada N5A 2Z8
Tel. & Fax (519) 271-5928
www3.sympatico.ca/tgmc

ARRL's VHF/UHF Antenna Classics

Build portable, mobile, and fixed antenna designs

Ground planes, J-poles, mobile antennas, Yagis, and more. Build a better antenna for your hand-held radio. Construct a 2-meter Yagi that will rival similar commercial antennas. Build a dual-band vertical for 146 and 445-MHz. The results will be rewarding! Includes projects gathered from the pages of *QST*.



ARRL Order No. 9078
Only $14.95*
*shipping $7 US (ground)/$12.00 International

ARRL *The national association for* ***AMATEUR RADIO***

SHOP DIRECT *or call for a dealer near you.*
ONLINE WWW.ARRL.ORG/SHOP
ORDER TOLL-FREE 888/277-5289 (US)

AB 3/2007

MORE DEALS THAN YOU CAN SHAKE A STICK AT!

- Great Gear
- Great Deals
- Great Service
- Free UPS S/H!*

*On all radio orders shipped within the contiguous USA.

TEXAS TOWERS
Savings As Big As Texas!

Alfa-Spid, Alpha-Delta • Ameritron • ARRL • Astron • Bencher • Butternut • Cal-Av • Comet • Cushcraft • Daiwa • Diamond • Force 12 • Gap • Glen Martin • Hustler • Hygain • Icom • Kantronics • Kenwood • Lakeview • Larsen • LDG Electronics • M2 • MFJ • Mirage • Palstar • Phillystran • Rohn • Tex-Com • Times Microwave • Unadilla • Universal Tower • US Tower • Van Gorden • Vectronics • Vibroplex • Yaesu

KENWOOD

KENWOOD TS-2000X
Huge Band Coverage, All Mode HF/6m/2m/70cm/23cm, Auto Tuner, CW Memory Keyer, Dual RX, Dual DSP, Built-in 1200/9600 bps TNC, and More!
CALL FOR YOUR BEST PRICE!

butternut



BUTTERNUT HF-5B
Lightweight five band beam, small enough to turn with a TV rotator—perfect for portable or limited space operation or for deed restricted stations.
CALL FOR MORE BUTTERNUT!

M2 KT-34M2
Four element, short boom triband beam is long on performance! Rugged, with all stainless hardware. Broad gain, high F/B, flat match. Balun supplied.
CALL FOR M2 ANTENNAS!

KENWOOD TS-480SAT
Mobile Performance, All Mode HF/6m, Auto Tuner, Separate Front Control Panel, 16-Bit DSP, CTCSS Encode/Decode, More!
CALL FOR YOUR BEST PRICE!

cushcraft



CUSHCRAFT A3S
Three element triband beam with optional 30/40m kit. Compact yet rugged design with all stainless steel hardware. Perfect for limited space application.
CALL FOR MORE CUSHCRAFT!

Yaesu
G-1000DXA

ANTENNA ROTATORS

Hygain, AR-40 ....Call
Hygain, CD-45II ....Call
Hygain, Ham-IV ....Call
Hygain, Ham-V ....Call
Hygain, T2X ....Call
Hygain, T2X Digital.........Call
Hygain, HDR-300A ....Call
M2, OR-2800PDX ....Call
Yaesu, G-450A ....Call
Yaesu G-550....................Call
Yaesu, G-800SA ....Call
Yaesu, G-800DXA............Call
Yaesu, G-1000DXA ....Call
Yaesu, G-2800DXA ....Call
Yaesu G-5500 ....Call
ROTOR CABLE IN STOCK, CALL!

KENWOOD TM-D700A
Mobile 2m/70cm FM XCVR With TNC, Separate Front Control Panel, CTCSS Encode/Decode, 200 Memories, and More!
CALL FOR YOUR BEST PRICE!

hy-gain



HYGAIN TH-3MK4
Three element triband beam designed for broadband performance. Rugged construction and all stainless steel hardware for long term reliability.
CALL FOR MORE HYGAIN!



US TOWER CORPORATION

MA SERIES
Neighbor Friendly Design offers a flag-pole-like appearance, while supporting antenna loads up to 22 square feet. Models range from 40–85 feet in height and come with a hand winch and house bracket. Optional self supporting bases are also available.

TOWER EXPERTS
We Ain't Braggin.' But we've helped so many Hams order US Towers over the years that we've become the US Tower experts. Please call for help selecting the perfect US Tower for your QTH!

Universal

B-18 SERIES
Light Duty Aluminum Self Supporting Towers. Five models range from 30–50 feet in height, and support up to 12 sq. ft. of antenna load.
CALL FOR MORE INFO!

B-26 SERIES
Medium Duty Aluminum Self Supporting Towers. Thirteen models range from 30–90 feet and support up to 34.5 sq. ft. of antenna wind load.
CALL FOR MORE INFO!

B-30 SERIES
Heavy Duty Aluminum Self Supporting Towers. Nineteen models range from 40–100 feet, and support up to 34.5 sq. ft. of antenna wind load.
CALL FOR MORE INFO!

TEXAS TOWERS

TOLL FREE **(800) 272–3467**

1108 Summit Avenue, #4 • Plano, TX 75074
Hours: M-F 9 AM–5 PM Central Time
Email: sales@texastowers.com

MASTERCARD
VISA • DISCOVER

Proudly Serving Ham Operators Since 1978!
Visit Our Website for More Great Deals:
http://www.texastowers.com

INDEX

A

A-frame mast: 22-4, 22-5
A-Index: 23-45
AA6GL: 6-29, 15-8
AA6ZM: 6-5
AAT: 25-9ff
AB-577 military tower: 22-12
Absorber circuit, power: 27-6
Accuracy tests: 4-15ff
Acute-angle junction: 4-8
Adcock
  Antenna: 14-5ff
  Pattern: 14-6
Adcock, F.: 14-5
Adding parasitic director to LPDA: 10-8
Additional loss due to SWR: 24-10ff
Addresses of suppliers: 21-4ff
Adjustable L-network feed system: 8-19ff
Adler, Dick, K3CXZ: 3-24
Admittance: 28-5
AI1H: 26-22
AL7KK: 7-22
Algorithm for ray tracing: 3-31
Aluminum tubing: 4-7
AM broadcast stations: 2-8
American National Standards Institute: 1-19ff
American Physical Society: 1-19
Ammeters, RF: 27-2
Amplitude: 3-2, 3-12, 4-14
  Reflected signals: 3-2
Andress, Kurt, K7NV: 22-1, 22-27
Angle:
  Azimuth: 2-8, 2-15, 19-1
  Critical: 23-24
  Elevation: 2-8, 2-15, 19-1
  Near overhead: 11-37
  Zenith: 2-9, 2-15
Annealed copper wire: 20-1
ANSI RF exposure guidelines: 1-19
Antenna Model: 4-2
Antenna Modeling course: 4-3
Antenna tuner: 2-2, 4-6, 4-23, 7-3, 7-5, 7-7, 26-1ff
Antennas:
  Addresses of suppliers: 21-4ff
  Analysis by computer: 4-1ff
  Antenna terms, definitions of: 8-2ff
  AO-40: 19-9ff
  Apartment antennas: 4-24ff
  Aperture: 27-48
  Base loading: 16-1

Antennas:
  Broadband: 9-1ff
  Building on the tower: 22-25ff
  Capacitance: 16-3
  Center loading: 16-1
  Center-fed: 7-3
  Clothesline: 4-25
  Co-planar crossed Yagi: 19-5
  Coaxial sleeve: 7-23
  Construction details and practical considerations: 4-31
  Continuously loaded: 16-13ff, 6-29
  Crossed linear: 19-4ff
  Directive: 2-2
  Directivity and gain: 2-6
  Effect: 14-2
  Electrical loading: 16-1
  EME: 19-32ff
  End effect: 4-31
  End-fed: 7-2ff
  Essential characteristics: 2-1ff
  Flattop: 7-3
  Folded monopole: 6-19
  Folded, efficiency: 8-11ff
  for repeaters: 17-1ff
  G5RV & antenna tuner: 7-5
  G5RV multiband: 7-5ff
  Ground plane: 2-17, 4-8ff, 6-18ff, 7-16
  Half-sloper: 6-44
  Half-square: 6-24ff
  Height: 2-17
  Helical: 19-3, 19-5ff
  High horizontal: 6-10
  Horizontal: 6-10
  Image: 3-11
  Indoor: 4-27ff
  Installation: 1-1, 22-23ff
  Inverted L: 6-41ff
  Inverted V: 7-3ff
  Invisible: 4-24ff
  Isolation, for repeaters: 17-7ff
  Isotropic: 11-2
  K-factor: 2-5
  LC-matching networks: 9-9ff
  Limited space: 4-24ff
  Long-wire and traveling-wave: 13-1ff
  Losses: 3-2
  Low frequency: 6-1ff
  Magnetic core: 5-6ff
  Manufacturers product list: 21-1

Antennas:
  Matching network: 9-2
  Matching network design: 9-6ff
  Materials and accessories: 20-1ff
  Mobile: 16-1ff
  Mobile & marine: 16-1ff
  Mobile, transient protection: 1-15
  Modeling programs: 4-1ff
  Multi-dipole: 7-7ff
  Multiband: 7-1ff
  Near resonance: 9-2ff
  Off-center-fed dipole: 7-8ff
  Omnidirectional, VHF and UHF: 18-22
  Open-Sleeve: 7-18ff
  Other characteristics: 2-15ff
  Parabolic reflector: 19-14ff
  Pattern measurements: 2-7
  Pattern planes: 2-8
  Polarization: 2-8, 27-48
  Portable 2-element 6-meter quad: 15-11ff
  Portable 3-element portable 6-meter Yagi: 15-13ff
  Practical aspects: 4-19ff
  PVRC mount: 22-27ff
  Q: 9-2, 9-3
  Quad arrays: 12-1ff
  Quadrifilar: 19-4
  Raising alongside the tower: 22-23ff
  Range setup: 27-47ff
  Re-radiation: 4-21
  Receiving: 2-6
  Receiving wave antennas: 13-15ff
  Reciprocity: 2-7
  Repeater systems design: 17-1ff
  Resonant rhombic: 13-9ff
  Rotators: 22-30ff
  Satellite: 19-2ff
  Selection criteria: 18-1
  Separate, for repeaters: 17-8ff
  Short antennas: 6-29ff
  Simple wire: 7-1ff
  Site planning: 4-19ff
  Slopers: 6-44ff
  Space communications: 19-1ff
  Support: 22-1ff
  System: 2-2, 4-19
  System compromises: 4-22
  Terminated rhombic: 13-11ff
  Texas potato masher: 19-2
  Textbooks: 2-19
  Top and side mounting: 17-5ff
  Trap: 7-9ff, 25-2
  Turnstile over reflector: 19-3
  Vertical: 6-15ff
  W3DZZ: 7-10ff
  Windom: 7-6
  with parallel-tuned circuits: 9-6ff
  Zip-cord: 15-2ff
AO-10: 19-2, 19-7
AO-13: 19-2
AO-40: 19-7, 19-10, 19-12, 19-14, 19-24, 19-29
AO-7: 19-2
Aperture, antenna: 27-48
Appendix A: 8-12, 8-56
Appendix B: 8-17, 8-19, 8-37
Arm-strong manual positioning: 19-30
Army loop: 5-10
Array Solutions: 11-42
Arrayfeed1 program: 8-18ff, 8-23ff
Arrays:
  Adjusting feed systems: 8-32ff
  Baluns: 8-21
  Bi-square: 8-48ff
  Bidirectional: 8-2
  Binomial current grading: 8-43
  Bobtail curtain: 8-44ff
  Broadside: 8-2, 8-5, 8-37ff
  Bruce: 8-45ff
  Close-spaced driven: 8-13
  Collinear 2 elements: 8-37ff
  Common phased-array feed systems: 8-14ff
  Current distribution: 8-7
  Design examples: 8-23ff
  Directional switching: 8-33ff
  Driven: 8-2
  Driven combinations: 8-53ff
  End-fire: 8-2, 8-5, 8-50ff
  Feeding, shunt components: 8-21
  Forward gain: 8-26
  Four-Square: 8-18, 8-27
  Four-Square, L-network feed: 8-29
  Four-Square, simplest feed: 8-28ff
  Ground losses: 3-10
  L-network feed system: 8-25ff
  Large, feed systems: 8-16
  Lazy-H: 8-48
  Loss resistance & pattern: 8-26
  Measuring currents: 8-32ff
  Mutual coupling: 8-26
  Other broadside: 8-42ff
  Parallel broadside: 8-41ff
  Parasitic: 8-2, 8-6, 8-13
  Pattern null degradation: 8-21
  Phased: 4-14
  Phased arrays, feeding: 8-13ff
  Phased horizontal: 6-12ff
  Phased, element feed-point impedance: 8-10
  Phased, feeding: 8-10
  Phased, patterns vs spacing: 8-8, 8-9
  Phased, techniques: 8-10ff
  Phasing arrows: 8-55
  Practical aspects: 8-31ff
  Quad: 12-1ff
  Receiving: 8-15, 8-22
  Recommended feed methods: 8-16ff

- Arrays:
  - Shunt- or gamma-fed feeding: 8-20ff
  - Simplest feed system: 8-18ff
  - Sterba: 8-41
  - Unidirectional: 8-2
  - W8JK: 8-51ff
  - 3-element binomial broadside: 8-27
  - 4-element driven: 8-53
  - 4-element rectangular array: 8-29ff
  - 4-element, feeding: 8-20ff
  - 8-element driven: 8-54
  - 120 deg. fed, 60 deg. spaced: 8-30ff
- ARRL log coordinate system: 2-12
- Arrow antenna: 19-2
- ASTM A 475-89: 22-15
- Asymmetrical routing of dipole feed line: 26-19ff
- Atchley, Dana, W1CF: 6-47
- Atkins, Bob, KA1GT: 18-52, 18-54
- Attenuation:
  - From impedance measurements: 27-30, 28-8ff
  - Line, in Smith Chart calculations: 28-6ff
- Attenuator pad, switchable: 27-42ff
- Aurora: 23-36
- Autek Research RF-1, VA1: 9-2
- Automatic tuner: 5-26
- Average gain test: 4-14, 4-16ff
- Az-El: 19-28ff
- Az-el mount: 19-11, 19-12
  - angle: 2-8, 2-15, 4-1, 19-1
  - drive: 19-42
  - pattern: 2-9, 11-3

B

- Backscatter: 23-36
- Balanced electrostatically: 14-2
- Balanced feeder: 4-23
- Balloons demonstration: 2-10
- Baluns: 6-19, 18-6, 26-21ff
  - And off-center-fed dipole: 7-9
  - Arrays: 8-21
  - Choke: 6-19, 6-33, 6-45, 7-7, 7-9, 8-21, 11-42
  - Coax line: 18-6
  - Common-mode choke: 11-11, 16-24, 26-21ff
  - Common-mode current: 11-27
  - Current: 6-15, 7-9
  - Guanella: 6-13
  - Impedance step-up: 18-6
  - Impedance step-up/step-down: 26-27
  - Input of tuner: 25-17
  - Voltage: 7-7
  - W2DU: 8-21
- Bamboo spreaders: 12-4
- Bandwidth: 18-1
- Bar clamp (carpenter's clamp): 15-4
- Barkley, H. B.: 7-20
- Barrett, Lee, K7NM: 17-5
- Base loading: 16-1, 16-4ff
- Base spring: 16-1
- *BASIC*: 4-1
- Basic wind speed: 22-8
- Beamwidth: 2-11, 8-2
  - Definition of: 8-3
  - Versus gain: 8-3, 27-53
- Bedspring antenna: 4-27
- Bell labs: 3-21, 4-17
- Belrose, Dr. John S., VE2CV: 16-22
- Belts, safety: 1-2, 1-5
- Bending of radio waves: 23-3ff, 23-4
- Bending stress: 22-22
- Bent dipoles: 4-28, 6-39
- Beta match: 26-10ff
- Beverage: 13-16
  - Characteristic impedance: 13-19
  - Characteristic impedance, 2-wire: 13-21
  - Cross-fire feed system: 13-22
  - Feed-point transformers: 13-19, 13-20
  - In echelon: 13-21
  - Optimum length: 13-19
  - Practical considerations: 13-22ff
  - Signal-to-noise ratio: 13-22
  - Two-wire: 13-20ff
- Beverage, Harold, W2BML: 13-16
- Bi-square: 8-48ff
- Bidirectional: 8-3
- Big grips: 22-16
- Big ugly dish (BUD): 19-29
- Bilodeau, John, W1GAN: 17-14
- BIP/BOP: 11-43
- Bloodworth, Max, KO4TV: 16-16
- Bloom, Alan, N1AL: 9-9
- BNC connectors: 24-24
- Bobtail curtain: 8-44ff
- Bohrer, Paul, W9DUU: 14-23
- Boom length: 11-2
- Bowl-shaped SWR curve: 9-2
- Boyer, Joseph M., W6UYH: 7-27
- Braskamp, Leon, AA6GL: 15-8
- Breakall, Jim, WA3FET: 3-24, 3-32
- Breed, Gary, K9AY: 7-22
- Brewster angle: 3-12
- Bridge:
  - Circuits: 27-3ff
  - Noise, for HF: 27-25ff
  - Resistance type: 27-3ff
  - Sensitivity: 27-5
- Broadband:
  - Antenna matching: 9-1ff
  - Bifilar transformer: 26-16
  - Matching transformers: 26-16
- Broadcast approach, feeds: 8-16

Broadside arrays: 3-10, 8-37ff, 8-41ff
Brown, Bruce, W6TWW: 16-5, 16-26
Brown, Fred, W6HPH: 4-30
Brown, Jerry, K5OE: 19-3
Brown, Lewis and Epstein: 3-2
Bruce array: 8-45ff
Brute force feeding: 11-38
Buchanan, Chester, W3DZZ: 7-10, 11-26
Building:
  Department: 22-1
  Regulations: 22-1
  Safety codes: 22-1
Bumper-mounted HF mobile antenna: 16-2
Bunny hunting: 14-1
Buried radials: 6-22
Buried-radial ground system: 6-16

C

C-band TVRO dish: 19-11
Cable Ties, black: 4-33
Cage:
  Dipole: 2-4, 9-3ff
  Vertical: 6-21
Calorimeter, for power measurements: 27-22ff
Capacitance:
  Hat: 4-14, 6-23, 16-4, 16-15
  Short verticals: 16-3
Capacitive stubs: 7-12
Capacitive top loading: 6-29ff
Capacitor, coax: 6-13
Capacitors, lines as: 28-10ff
CapMan: 23-38, 23-43
Capon, Robert, WA3ULH: 5-17
Cardboard box antenna: 19-13
Cardiac pacemakers and RF safety: 1-22ff
Cardioid pattern: 14-2, 14-11, 14-15
Carey, Wilfred, ZS6JT: 19-11
Carolina Windom: 7-6ff, 7-9
Cartesian coordinates: 4-4ff
Casual antenna evaluation: 4-27
Cataract formation: 1-17
Caustic problem: 3-25
Cavity:
  Filters: 17-9ff
  Resonators: 17-9ff
Cebik, LB, W4RNL: 4-3, 10-1, 11-46
Center:
  Feed: 7-3
  Insulator: 4-6
  Loading: 16-1, 16-4ff
  Prime (Smith Chart): 28-1
Center-fed dipole: 2-3
Central States VHF Society: 19-15
Cerwin, Steve, WA5FRF: 16-23
Cessna, Clair, K6LG: 19-12
Characteristic impedance (also see Z_0): 24-4, 28-4
Chebyshev matching: 9-9
Chicken-wire screen: 3-2
Chirp sounder: 23-21
Choke balun: 6-19, 6-45, 7-7
Choosing a transmission line: 26-1ff
Christman, Al, K3LC (ex-KB8I): 6-16
Christmas tree: 4-9
Christmas tree stacks: 11-27
Circadian rhythms: 1-18
Circles:
  Resistance (Smith Chart): 28-1
  SWR (Smith Chart): 28-3
Circuits, short and open, as line terminations: 28-3
Circular polarization (CP): 19-2ff, 23-6
Circular waveguide dish feeds: 18-19ff
Circularize: 19-15
Circularizing tau: 10-7, 10-8
Clamps, hose: 20-9
Climber's safety belt: 22-15
Climbing tips: 1-4ff
Closely spaced wires: 4-17
Clothing, towers: 1-2
Cloud warming: 6-4
Co-planar crossed Yagi: 19-5
Coaxial:
  Sleeve antenna: 7-23
  Switch: 4-27
Coaxial cable:
  Braid and water: 4-32
  Direct burial: 4-33
Coaxial-resonator match: 9-13
Code, National Electrical: 1-8, 20-1
Coefficient:
  Horizontal reflection: 3-16ff
  Vertical reflection: 3-13ff
Coffee can 2304-MHz feed: 18-22
Coil, loading: 4-14
Coiled-coax balun: 26-22
Collinear: 8-2
  Arrays: 8-37ff, 18-13ff
  Elements: 8-7
  Extended double Zepp: 8-40ff
  Gain and directivity: 8-37
  Vertical: 17-6
  2 elements: 8-37ff
  3 and 4 elements: 8-39ff
Combinations of long wires: 13-5ff
Combined balun and matching stub: 26-26ff
Commercial implementations, *NEC-2*: 4-2
Common logarithm: 2-9
Common-mode:
  Choke balun: 6-15, 6-33, 26-21ff
  Currents: 8-21, 12-7
  Effects with directional antennas: 26-20ff
  Transmission-line currents: 26-17ff

Compact vertical dipole (CVD): 6-31ff
Comparing antennas on fading signals: 4-27
Comparisons:
  Between top and base loading: 6-29ff
  Quad vs Yagi: 12-1ff
Compass needle: 3-3
Complementary RLC network: 9-3
Conductance: 28-5
Conduction current: 3-3ff
Conductivity: 3-11ff, 3-20, 4-1, 4-11
  Map: 3-14
  Soil: 3-1
Conductivity, soil:
  Measurement of: 27-36ff
Conductors:
  Copper clad steel: 20-3
  Copper wire data table: 20-2
  Fat: 4-7
  Losses: 24-6
  Tension and sag on wires: 20-2ff
  Wire types: 20-1
Cone of radiation: 23-24
Conservation of energy: 3-28, 8-12
Continental US: 3-14
Continuous:
  Loaded antennas: 16-13ff
  Loaded verticals (helical): 6-37ff
  Loading: 6-29
Controlled environments: 1-20ff
Convergence test: 4-15ff
Cookie-can lid: 19-24
Cookie-sheet & picture-frame-glass capacitor: 5-16ff
Coordinate scales, radiation patterns: 2-11
Coordinate shortcuts, *EZNEC:* 4-7
Copper wire, data table: 20-2
Copper-clad steel conductors: 7-8
Copperweld: 20-1
Corner reflector: 18-9ff
  Design table: 18-16
Corona: 6-13, 12-1
Coronal holes: 23-28
Counterpoise: 2-17, 3-2, 6-16ff, 16-38
  Elevated: 6-46
Counterweighting: 22-2
Coupled-resonator:
  Bandwidth: 7-25
  Complexity: 7-25
  Equations: 7-24
  Frequency independence: 7-25
  30/17/12-meter dipole: 7-26
Coupled-resonator dipole: 7-22ff
Couplers:
  Cross band: 17-11
  Directional, VHF: 27-19ff
  Hybrid: 8-16
Coupling:
  Coupling the line to the antenna: 26-1ff
  Coupling the transmitter to the line: 25-1ff
  Loops: 17-16
  Mutual: 4-14, 8-4, 8-13, 11-33
Covenants: 4-19
Coverage, repeaters: 17-2ff
Cox, Roger, WB0DGF: 10-3
CP: 19-2ff
CP patch: 19-17
Crank-up tower: 4-22, 22-10ff
Create 714X-3 triband Yagi: 11-38
Critical:
  Angle: 23-24
  Frequency, vertical incidence: 11-36, 23-20
Cross-fire feed system: 13-22
Cross-flow principle: 22-20
Crossed double bazooka: 9-6, 9-7
Crossed linear antennas: 19-3ff
Cumulative distribution function: 6-1, 23-30, 23-31
Cupped reflector, S-band: 19-7
Current:
  Balun: 6-15, 26-22ff
  Balun model: 26-22
  Common-mode, on lines: 27-7ff
  Conduction: 3-3ff
  Displacement: 3-3ff, 6-17
  Distribution: 8-11, 8-14
  Distribution on open sleeve antennas: 7-20ff
  Feed-point vs element: 8-14
  Induced in conductors: 11-1
  Induced, amplitude and phase: 8-4
  Loop: 7-2, 7-8
  Measurement: 27-1
  Measuring phased arrays: 8-32ff
  Parallel: 27-7
  Parasitic conductor: 4-30
  Probe: 8-33
  RF current penetration: 3-17ff
  RF measurement probes: 27-47ff
  Source: 4-14
  Total: 3-1
  Transmission lines: 24-15
  Zone: 3-5, 3-8
Current forcing: 8-17ff, 8-19, 8-26, 8-28, 8-29
CVD: 6-31ff
  80-meter: 6-33ff

D

D'Agostino, Philip, W1KSC: 18-41
D-layer (region): 23-19ff
D-Ring: 1-5
Daytime band: 6-7
dBd: 11-2

dBi: 8-12, 11-2ff
Dead-man anchor: 22-6ff
Decibel: 2-9
Decouple antenna from feed line: 6-19
Deed restrictions: 4-19
Delay lines: 17-4
Delta match: 18-5, 26-7ff
DeMaw, Doug, W1FB: 6-43, 6-47, 14-9, 14-11
DeMaw, Jean, W1CKK: 5-23
Depth of rf current penetration: 3-17ff
Detuning sleeve balun: 26-25ff
Dielectric constant: 3-1ff, 3-11ff, 3-20, 4-1, 4-11
Dielectric, losses: 24-6
Diffraction: 3-23, 3-24, 3-24ff, 23-4
  Diffraction model: 3-24ff
  Incident-shadow boundary: 3-25
  Reflection-shadow boundary: 3-25
  Shadow boundaries: 3-25
  Wedge: 3-24
Digital elevation model (DEM): 3-30ff
Dipole:
  Arrays, log periodic: 10-1ff
  Bent: 4-28, 6-39
  Cage: 2-4, 9-3ff
  Center-fed: 2-3
  Coupled-resonator: 7-22ff
  Coupled-resonator 30/17/12-meter: 7-26
  Flattop: 4-4
  Folded: 6-10ff
  Folded, matching: 18-6
  G5RV multiband: 7-5ff, 26-1
  Halfwave center-fed: 2-3, 6-10ff
  Horizontal: 6-10ff
  Inverted-V: 4-7, 6-11ff
  Multiwire: 6-11
  Off-center fed (OCF): 2-3, 7-8ff
  Off-center-loaded dipoles: 6-39ff
  Orientation: 4-28
  Paralleled: 7-7ff
  Stagger tuned: 7-7, 9-4, 9-5
  Trap: 7-9ff
  Trap, 3.5 to 28 MHz, 5 bands: 7-10ff
  Trap, 80, 40, 20, 15 and 10-meter: 7-11ff
  Trap, 80, 40, 20, 17 and 12 meters: 7-12ff
  Twin-lead folded: 15-1, 15-2
  Vertical half-wave: 4-8
  W8NX trap: 7-11ff
  135-foot, 80 to 10-meter: 7-3ff
Direct matching to the antenna: 26-3ff
Direct ray: 3-11, 3-12, 3-16, 3-19
Direct wave: 23-4
Direction finding antennas: 14-1ff
Directional coupler: 27-3
  VHF: 27-19ff
Directional switching, arrays: 8-33ff
Directive antenna: 2-2
Directivity: 4-28
  And gain: 2-10
  And radiation pattern: 2-6
  Antenna: 2-6
  RDF: 14-1
Director: 6-13, 11-1ff
  Retrograde: 11-28
Disastrous nulls: 3-22, 11-33
Discone: 7-26
  HF, for construction: 7-26ff
  Patterns: 7-32ff
Dish:
  Barbeque: 19-15
  Center-fed: 19-15
  Circularize: 19-15
  Deep: 19-17
  EME antennas: 19-34ff
  Feeds: 19-17ff
  Focal point: 19-22
  Focal ratio (f/D): 19-15
  Gain vs errors: 19-39
  K-band: 19-16
  Long focal length: 19-15
  MMDS, S-band: 19-18
  Off-center fed: 19-15
  Offset-fed: 19-17
  Parabolic 12-foot stressed: 19-35ff
  Patch feed: 19-20ff
  Patch, no-tune dual-band: 19-20ff
  Patch, round feed: 19-24
  Patch, truncated corners: 19-21
  Short focal length: 19-15
  60-cm S-band: 19-16
Displacement current: 3-3ff, 6-17
Distributed material loads: 4-15
Diurnal pumping: 19-27
Diversity:
  Effect: 13-1
  Receiving system: 23-35
  Space: 11-38
  Techniques, repeaters: 17-12ff
Do-it-yourself propagation prediction: 23-43ff
Dorr, John, K1AR: 11-32
Double bazooka: 9-6
Double-ducky direction finder: 14-18ff
Downtilt, vertical beam: 17-4ff
Drag coefficient: 22-22
Dream station: 4-19, 4-20
Drip (loop): 4-33
Driven arrays: 8-6ff
Driven element impedance: 11-4
Drooping dipole: 7-3
Ducting: 23-25ff
Dummy element: 11-8
Dump power: 6-9

Duplexers: 17-9ff
  Adjustment: 17-19ff
  144 MHz, for construction: 17-14ff

E

E and H fields: 3-3ff
E-field: 3-3
  Ground loss: 3-6, 3-7
  Intensity: 3-6, 4-18
  Losses: 3-6, 3-7
E-layer (region): 23-20
E-plane pattern: 2-8
Earth screw: 22-17
Earth-moon-earth (EME): 19-1
EasyTrak: 19-30,1931
EB-144: 19-2
EB-432: 19-2
Echelon, Beverage antennas: 13-21
Eckols, Ansyl, YV5DLT: 10-17
Effective:
  Electrical height: 3-5
  Ground resistance: 3-7
  Height: 5-3
  Projected area (EPA): 22-20
Effects:
  of ground: 3-1ff
  of ground in far field: 3-11ff
  of irregular terrain in the far field: 3-21ff
  of other conductors: 17-7
Efficiency: 3-5
  Antenna matching network: 9-3
  Antenna traps: 7-10
  Radiation: 8-11ff
  Radiation, short verticals: 16-9ff
EFFLEN.FOR program: 2-16
Eggbeater antenna: 19-2
EIA RS-222: 22-8
8-element driven arrays: 8-54
EIRP: 17-13
Electric field: 2-7
Electrical loading: 16-1
Electrician's knot: 15-2
Electromagnetic:
  Pulse protection: 1-11ff
  Radiation hazards: 1-17ff
  Waves: 2-1
Electron density profiles: 23-20
Electronic:
  Antenna rotation: 14-7
  Beam forming: 14-7
Electrostatic shield: 5-5, 5-8
Elements:
  Assembly: 20-9
  Collinear: 8-2
  Currents: 8-14
Elements:
  Driven: 8-2
  Parallel: 8-2
  Parasitic: 8-2
  Self impedance: 11-9
  Tapered: 4-17ff
  Telescoping aluminum tubing: 11-28
Elengo, John, Jr, K1AFR: 20-3
Elevated:
  Counterpoise: 6-46
  Ground-plane antennas: 6-23ff
  Radials: 6-16, 6-20
Elevation:
  Angle: 2-8, 2-15, 3-12ff, 4-1, 19-1
  Angle statistical data: 6-1, 23-30ff
  Angles for HF communications: 23-28ff
  Another way of looking at: 6-2
  Control: 19-28
  Drive: 19-42
  Footprint: 11-30
  Moderate distances on 40 meters: 6-9ff
  Moderate distances on 75/80 meters: 6-9
  Pattern: 2-10, 11-3, 23-33ff
  Peak statistical: 11-30
  Wide footprint: 11-33
ELF (60 Hz) electromagnetic fields: 1-18
Eliminating common-mode effects—the balun: 26-21ff
Elliptical: 2-15
Elliptical polarization: 19-5, 23-3
ELNEC: 16-31
EME: 11-32
  Dish: 19-34ff
EMP protection: 1-11ff
Empiricism: 4-27
End:
  Effect: 4-31ff, 16-6
  Fed Zepp: 7-2ff
  Load: 7-1
  Loading: 6-31
End-fire:
  Arrays: 3-10
  2-element: 8-50
  Unidirectional: 8-50ff
  3-element: 8-51
  4-element collinear: 8-53
Entrance panel: 1-14
Epidemiological studies: 1-18ff
Equalizer plate: 22-18
Equations:
  Antenna test range setup: 27-49ff
  Broadband matching network efficiency: 9-3
  Broadband matching network loss: 9-3
  Calculating long-wire length: 13-4
  Calorimeter calibration: 27-23
  Capacitance, short verticals: 16-3
  Capacity hat: 6-31

Equations:
  Coaxial cable: 24-21
  Decibels: 27-53
  Depth of RF current penetration: 3-17
  Dipole with end effect: 4-31
  Distance to a disturbance, time domain reflectometry: 27-32ff
  EIRP calculation: 17-13
  Ferrite-rod antenna design: 5-6ff
  Frequency for measuring cable losses: 27-30
  Gain: 27-53
  Gain & beamwidth: 8-3
  Horizontal reflection coefficient: 3-16
  Horn antenna design: 18-53
  Impedance, characteristic, open-sleeve elements: 7-18
  Impedance, characteristic, transmission lines: 27-30
  Isolation requirement, repeater antennas: 17-7ff
  L-network: 25-7
  L-network matching: 6-39
  Length, line, electrical: 27-29, 28-6
  Loading inductance, short verticals: 16-8
  Loop ac resistance: 5-6
  Loop antennas, design: 5-3ff
  Loop antennas, effective height: 5-3
  Loop antennas, voltage: 5-3
  Loop distributed capacitance: 5-5
  Loop inductance: 5-4
  Loop Q: 5-6
  Loop radiation efficiency: 5-11
  Loop radiation resistance: 5-10
  Loop sensitivity: 5-8
  Loopstick antenna design: 5-6ff
  Loss,path: 17-8
  Losses, line: 27-30
  Noise bridge compensation and calibration: 27-27ff
  Off-center loading coils: 6-41
  Open sleeve elements, characteristic impedance: 7-18
  PBA: 3-15
  Pi-network: 25-7
  Quarter-wave matching transformer: 6-24
  Quarter-wave sloper: 6-45
  Quarter-wave vertical: 6-16
  Radiation resistance, short vertical: 16-3, 16-5
  Reflection coefficient: 9-1
  Return loss in dB and SWR: 7-20
  S-parameters: 27-54ff
  Series equivalent of unlike parallel reactances: 7-10
  SWR: 9-1, 27-3
  Transient clamping voltage: 1-15
  Transmission line equation: 24-12
  Transmitting loops, design: 5-10
  Velocity factor, line: 28-10
  Velocity of propagation: 24-3
  Vertical reflection coefficient: 3-14
  Wavelength: 23-2

Equations:
  Z_0, line, from impedance measurements: 28-8ff
  1-l loop circumference: 5-2
Equatorial anomaly: 23-22
Equivalent:
  Circuit, resonant antenna: 9-2
  Loading for Yagis: 6-23ff
  Moment method: 22-20ff
Erecting a mast: 22-7ff
Eskenazi, Danny, K7SS: 11-40
Euclid: 3-24
Evaluate property: 4-19
Extended double Zepp: 8-40ff
  Modified: 6-13ff
Extraordinary wave: 23-21,2322
Extreme ultraviolet (EUV): 23-19
EZNEC: 3-22, 4-2, 7-24, 9-2, 10-3, 11-28, 11-40, 12-4, 16-31
  Example, nulls: 8-56
  Example, phasing-line feed: 8-56ff
  EZNEC M Pro: 4-2, 19-33
  EZNEC-ARRL: 3-22, 8-10, 8-12ff, 8-16ff, 8-23, 11-44
  EZNEC/4: 4-2

F

F-layer (region): 23-20
F/B: 6-13
f/D: 19-15
F/R: 11-35
F1 layer: 23-20
F2 layer: 23-20
FABStar: 19-10
Fading: 4-28, 23-35
  Frequency selective: 11-38
  Spin: 19-24
Fall arrest safety harness: 1-3
Fano, R. M.: 9-6
Far field: 3-1
  Elevation pattern: 3-24
Faraday rotation: 19-6, 23-3
Farmer, Ed, AA6ZM: 6-5
Fat conductors: 4-7
  Connected to skinny wires: 4-17
  Elements: 8-14
FCC: 2-8
  Regulations: 4-18
  RF-exposure regulations: 1-20ff
Federal preemption (PRB-1), antennas: 22-1
Feed line: 24-1ff
  Radiation: 7-7
Feed methods:
  Antenna impedance mismatching: 9-5ff
  Center: 7-3
  Delay lines: 17-4
  Direct: 7-2

- Feed methods:
  - Dish: 19-17ff
  - Dual-helix: 19-18
  - End: 7-2ff, 7-2ff
  - Feeding a multiband non-resonant antenna: 26-2
  - Feeding a multiband resonant antenna: 26-2
  - Feeding a single-band antenna: 26-1ff
  - Helix: 19-17ff
  - Parallel fed dipoles: 7-7ff
  - Patch: 19-17, 19-20ff
  - Patch, no-tune dual-band: 19-20ff
  - Phased arrays: 8-14ff
  - Quagis: 18-47
  - Stacked Yagis: 18-7ff
- Feed point: 4-4
  - Impedance: 2-2, 3-1, 3-5, 4-10
  - Resistance: 9-2
  - vs element current: 8-14
- Feeder (also see Lines): 24-1
- Fenwick, Richard, K5RR: 11-27
- Ferrite rod antennas: 5-6ff, 14-3
- Ferrite-core:
  - Balun: 26-23ff
  - Loops: 14-11ff
- Fiberglass:
  - for antenna construction: 20-12
  - Poles: 20-12ff
  - Spreaders: 12-4
- Field Day: 22-3
- Field intensity: 3-3, 23-3
- Field strength: 8-10, 23-3
  - Measurement of: 27-43ff
  - Meter: 2-7
  - RF power density: 1-20
- Fields: 2-7
  - Reactive near: 2-2
  - Reinforcement & cancellation: 8-12ff
- Figure of merit: 11-46
- Filters, cavity type: 17-9ff
- Finding capacitance hat size: 6-31ff
- Finger stock: 16-16,1619
- Fire extinguisher: 1-8
- Fire hazards: 4-30
- Fire-escape antenna: 4-26
- Fisher, Reed, W2CQH: 9-15
- Flagpole: 6-15
  - Antenna: 4-26
  - Bracket: 15-4
- Flashlight analogy: 2-6
- Flat earth: 3-18
  - Ground models: 3-24
  - Reflections: 3-15ff
- Flat lines: 24-9ff
- Flat projected area (FPA): 22-20
- Flattop dipole: 4-4
- Fletcher, Rick, KG6IAL: 19-15
- Floating point number: 4-13
- Focal point, dish: 19-22
- Focal ratio (f/D): 19-15
- foE: 23-21
- foF1: 23-21
- foF2: 23-21
- Folded dipole: 6-10ff, 26-8
- Folded monopole antenna: 6-19
- Force 12 C3: 11-27ff
- Forcing currents: 8-17ff
- Ford, Jim, N6JF: 15-8
- Formula Translation (Fortran): 2-16, 3-25, 4-3
- Forward stagger: 11-27ff
- FOT: 23-23
- Four Square: 8-18, 8-27
- Four Square switching: 8-35
- Four-element driven arrays: 8-53
- Four-way mobile DF system: 14-24ff
- Four-wire lines: 24-16
- Fox hunting: 14-1
  - DF twin 'tenna: 14-20ff
- Fractional wavelength: 2-5
- Frame antenna: 14-3
- Frame loops: 14-9ff
- Francisco, Al, K7NHV: 4-24
- Fraunhöfer: 2-7
- Free space: 2-2, 2-3, 2-10
- Freely, W. B., K6HMS: 16-23
- Freestanding tower: 4-22
- Frequencies, spurious, and RF measurements: 27-8
- Frequency:
  - Critical: 11-36
  - E-region critical: 23-21
  - F-region critical: 23-21
  - Gyro: 23-22
  - Optimum traffic (FOT): 23-23
  - Range: 4-12
  - Scaling: 2-16, 4-13
  - Spot: 4-12
- Fresh water: 3-17
- Fresnel: 2-7
  - Integral: 3-25
- Front-to-back ratio: 4-10, 4-12, 4-16, 6-13, 6-47, 8-3, 11-3
- Front-to-rear ratio: 4-10, 4-16, 11-35
- Frost line: 4-33
- Full duplex: 17-7
- Full-wave resonant frequency: 2-4, 2-11, 2-13

G

- G-line: 18-2
- G3RUH: 19-13, 19-14, 19-16, 19-18, 19-20, 19-24
- G3VJL: 18-48
- G3WDG: 19-16, 19-22

G5RV:
  Dipole: 7-5ff, 26-11
  Inverted V: 7-6
  Lobes: 7-6
  Losses in coax: 7-5
  Multiband: 7-5ff
G6LVB: 19-24
G6XN: 6-31, 6-32, 11-46
Gain: 2-6, 8-3ff, 8-12, 18-1
  and feed point mismatch: 27-48
  Array dimensions: 8-6
  Average gain test: 4-14
  Long wire antennas: 13-1
  Measurement: 27-51ff
  Pattern degradation due to stacking: 18-9
  Relative to single element: 8-12
  Versus beamwidth: 8-3, 27-53
  Versus front-to-rear ratio, Yagi array: 11-2ff
  Versus height: 18-1
  Versus mutual impedance: 8-5ff
Galvanized steel: 20-13
Gamma match: 9-13, 18-5, 26-9ff
Gamma-match capacitor: 6-22
Geiser, David, WA2ANU: 14-18, 14-24, 14-23
Generators, emergency power: 1-12ff
Gentle slope: 3-26
Geomagnetic storm: 23-28
Geometric optics: 3-24, 3-25
Geometric theory of diffraction (GTD): 3-25
Geometry, wires: 4-4ff
Gilbert, Ed, K2SQ: 26-22
Gillette, R.F., W9PE: 14-20
Gin pole: 1-3ff, 22-7, 22-13, 22-23
G*NEC:* 4-2, 10-3
Going around the horn: 4-11
Gold, Dr Robert E, WB0KIZ: 1-17
Goniometer: 14-6ff
GPS receiver: 3-31
Graphs: 4-3
  Origin: 4-4
  Polar: 4-3
  RF currents: 4-3
  SWR: 4-3
  3D Wire-frame: 4-3
Gray-line propagation: 23-37
Greenburg, A., W2LH: 7-11
Grimaldi: 3-24
Ground: 2-2
  Array losses: 3-10
  Buried radials: 6-22
  Cities: 3-15
  Conductivity: 3-1, 4-1, 4-11
  Dielectric constant: 3-1, 4-1, 4-11
  Effect in far field: 3-11ff
  Effects, multielement arrays: 8-4
  Electrical: 1-8ff
Ground:
  Fresh water: 3-17
  Loops: 1-10
  Loss: 16-9, 16-10ff
  Lossy: 3-2
  Parameters, measuring: 27-36ff
  Perfect: 3-2, 4-2
  Plane: 2-17, 6-16
  Practical suggestions: 3-9
  Reflected ray: 23-5
  Reflection factor: 3-20
  Reflections: 3-11, 3-19, 4-1
  Resistance: 8-24
  Return loss: 3-11
  RF alternative: 1-10
  Salt water: 3-17
  Screen: 3-2, 3-7
  Strap: 1-9
  Water pipe: 7-2
  Wave: 11-37, 23-4ff
  Wave range: 23-5
Ground-plane antennas: 3-2, 4-8ff, 6-18ff, 6-18ff, 7-16
  for 144, 222 and 440 MHz: 18-23ff
Group of dipoles: 8-1
Grover, F. W.: 5-4
Guanella balun: 6-13
Gusset plates: 20-12
Guth, Dr Peter: 3-30, 17-2
Guy wires:
  Anchors: 22-6ff
  Avoiding, during installation: 22-25ff
  Earth screw: 22-17
  EHS: 22-15
  Elongation: 22-9
  Equalizer plate: 22-18
  Guy bracket: 22-17
  Klein cable grip: 22-18
  Loos guy wire tensioner: 22-18
  Material: 22-6ff
  Phillystran: 22-15ff
  Preformed guy grips: 22-16
  Resonance: 22-18ff
  Snubber assemblies: 22-12
  Tension: 22-7
  Thimbles: 22-16
  Torque arm assembly: 22-17, 20-09
  Tower: 4-22
  Track, for raising antennas: 22-25
  Turnbuckles: 22-16
Gyro frequency: 23-22

H

H field: 3-3
  Intensity: 3-6, 4-18
  Losses: 3-7

H-Adcock: 14-6
H-plane pattern: 2-8
Hairpin match: 18-6, 26-11ff
Half elements: 11-11
Half sloper: 6-23ff, 6-44
Half-power points: 2-10, 2-11, 8-2, 8-3, 11-3
Half-square antenna: 6-24ff, 8-44ff
  Changing the shape: 6-26ff
  Feed-point impedance: 6-27
  Patterns with frequency: 6-27ff
  Voltage feed: 6-27ff
Half-wave (full) sloper: 6-44
Half-wave resonance: 2-4, 2-4
Half-wave vertical dipole, feeding: 6-15
Hall, Jerry, K1TD: 6-40, 10-22, 15-1, 15-2, 22-19
Hallidy, David, K2DH: 19-32, 19-43
Halyards: 20-5ff, 22-1
  Safe working tension: 20-6
Hansen, Markus, VE7CA: 10-21, 15-11
Hard hat: 1-2, 1-5, 22-15
Hard-drawn copper wire: 20-1
Hart, Ted, W5QJR: 5-10, 5-12
Hat, capacitance: 4-14
Haviland, Bob, W4MB: 4-1, 27-36
Hazards:
  Electrical shock: 1-8ff
  Health: 1-17ff
  RF awareness guidelines: 1-23
  RF radiation: 1-17ff
HCJB, Missionary radio station: 12-1
HDL_ANT program: 19-15
Healy, Rus, K2UA (ex-NJ2L): 13-16
Heat loss: 2-2
Height: 7-1
  Effective electrical: 3-5
  Gain: 18-1
  Vertical antennas: 2-17
Helical antenna: 19-3, 19-5ff
  Axial ratio: 19-8
  Basics: 19-6ff
  Beamwidth: 19-8
  Broad bandwidth: 19-6
  Diameter: 19-8
  Gain: 19-8
  Impedance: 19-8
  Polarization diversity: 19-6
  S-band: 19-14
  Satellite: 19-6
  50-W feed: 19-8ff
Helically wound:
  Radiator: 16-1
  Verticals: 6-37ff
Helix:
  CP feed: 19-12
  Feed: 19-17ff
  Feed for offset-dish: 19-18ff
Helix:
  For Sailboats: 16-31ff
  Yagi arrays: 11-1ff
HFTA (HF Terrain Assessment):3-26ff, 4-1, 4-19, 6-1, 11-30, 11-44, 11-45, 17-2, 23-31
  and canyons: 3-30
  PDF: 3-30, 3-32
High accuracy ground: 4-11
High:
  Efficiency: 7-1
  Frequency asymptotic solution: 3-32
  Impedance point: 4-14
  Pass T-network: 25-2
  Power ARRL antenna tuner: 25-15ff
  Q circuit: 2-6
Hill-ahead: 3-26
Hill-valley: 3-26
History of antenna modeling: 4-1ff
Homemade dipole center insulators: 4-31
Hooke: 3-24
Hop, extra: 11-36
Hopengarten, Fred, K1VR: 11-37
Hops: 23-23
Horizonal:
  Polarization: 3-1, 3-2
  Polarized antennas: 3-15ff
  Reflection coefficient: 3-16ff
  Yagi model: 4-9
Horn antennas: 18-13ff, 18-18, 18-52ff
  Feed: 19-37ff
  for 10 GHz: 18-52ff
  Pyramidal: 18-52, 19-14
  Sectoral: 18-52
Hose clamps, data table: 20-11
Hutchinson, Chuck, K8CH: 4-19, 11-11, 15-4
Huygens: 3-24
HVD (Halfwave Vertical Dipole): 6-15, 6-32
  Feeding: 6-15
Hybrid coupler: 8-10, 8-16

I

I8CVS: 19-10, 19-21, 19-28, 19-29, 19-31
IEEE standard: 19-3
Igniting grass: 3-6
Image antenna: 2-17, 3-11
Impedance:
  Antenna: 27-48
  Antenna, measuring: 27-30ff, 28-5ff
  Antenna, versus element coupling: 8-5
  Feed-point: 2-2, 3-5, 4-10, 8-13
  Input: 28-1
  Load: 28-1, 28-5ff
  Measurement: 27-30ff
  Mutual: 2-2, 3-10, 4-1, 8-4ff
  Plotting (Smith Chart): 28-2ff

- Impedance:
  - Self: 2-2
  - Source: 4-7
- Importance of low angles for low-band DXing: 6-1ff
- Improved:
  - Crossed-double bazooka: 9-15
  - Current distribution: 16-4
  - Telerana: 10-21
- In phase: 8-1
- Incident power: 24-5
- Indoor stealth loop: 5-26ff
- Induced current: 8-4
- Induced voltage: 3-1
- Induction field: 2-7
- Inductors:
  - Lines as: 28-10ff
- Installation:
  - Antennas: 1-1, 1-3
  - Clotheslines: 4-25ff
- Insulators: 4-31ff
  - Center: 4-6
  - for antennas: 20-3ff
  - for ribbon-line antennas: 20-4, 20-5
  - Polystyrene sheet: 7-8
  - Strain type: 20-4
  - Stress on: 20-4
- Inter-penetration: 4-8
- Interference: 2-6, 3-24
- Interferometer: 14-18
- Interlaced elements: 11-26
- International sunspot number (ISN): 23-16
- Inverse-distance law: 23-3
- Inverse-fed ground plane: 9-5
- Inversion: 23-9
- Inverted-L antennas: 6-41ff
  - Single elevated radial: 6-42
- Inverted-V dipole: 4-7, 6-11ff, 7-3ff
- Invisible long wire: 4-25
- *IONCAP*: 3-21, 23-29, 23-38, 23-43
- Ionization: 23-19
- Ionogram: 23-21
- Ionosonde: 23-21
  - Oblique angle: 23-23
- Ionosphere: 19-1, 23-19ff
  - Backscatter: 23-36ff
  - Bending in the: 23-20ff
  - Controls propagation: 23-31
  - D-layer: 23-19ff
  - Disturbed conditions: 23-27ff
  - E-region: 23-20
  - F-layer: 23-20
  - F-region: 23-20
  - Hop: 23-24
  - Layer characteristics: 23-19ff
  - Scatter: 23-36
  - Sidescatter: 23-37
- Ionosphere:
  - Sounding: 23-20ff
  - Storms: 23-28
  - Transequatorial scatter (TE): 23-22
- Irregular local terrain: 3-21ff, 4-1, 13-3
- Irrigation tubing: 6-20
- Isaacs, John, W6PZV: 14-15
- Isbell, D. E.: 10-1
- Isolate antenna from feed line: 6-19
- Isolation, repeater antennas: 17-7ff
- Isotropic antenna: 8-3, 8-12, 11-2, 23-1
- Ives, Dick, W7ISV: 6-14

J

- J-Pole, 144 MHz antenna: 18-25ff
- Jackscrew drive: 19-28ff
- Jammers of repeaters, finding: 14-1
- Jansson, Dick, WD4FAB: 19-2, 19-3
- JF6BCC: 19-21
- JG1IIK: 19-21
- Johns, Robert, W3JIP: 15-4, 15-9
- Johnson, Don, W6AAQ: 16-16, 16-26
- Jones, Bill, KD7S: 5-15

K

- K-band downlink: 19-15ff
- K-factor: 2-5
- K-Index: 23-45
- K0RZ: 19-14
- K1AFR: 20-3
- K1AR: 11-32
- K1EA: 11-31
- K1FO: 18-28ff, 19-33
- K1FO 144 MHz Yagi, 12 elements: 18-34ff
- K1FO 222 MHz Yagi, 16 elements: 18-38ff
- K1FO 432 MHz Yagi, 22 elements: 18-31ff
- K1KI: 11-46
- K1TD: 6-40, 10-22, 15-1, 15-2, 22-19
- K1VR: 11-27, 11-37, 11-40ff
- K1WA: 6-48
- K2DH: 19-43
- K2RIW: 19-35, 19-40
- K2SQ: 26-22
- K3LC: 6-16
- K3OQF: 6-31
- K3TZ: 19-21
- K4ERO: 3-9
- K4EWG: 10-25
- K5GNA: 19-12, 19-15
- K5GW: 19-33
- K5IU: 22-20
- K5OE: 19-2, 19-3, 19-12, 19-13, 19-15, 19-16, 19-18, 19-20, 19-22
- K5RR: 11-27

- K5ZI: 23-34
- K6HMS: 16-23
- K6LG: 19-12, 19-13
- K6SE: 6-21
- K6STI: 7-33
- K7NHV: 4-24
- K7NM: 17-5
- K7NV: 22-1, 22-27
- K7SS: 11-40
- K8CH: 1-14, 4-19, 6-31, 6-32, 11-11, 15-4
  - CVD, 30 meters: 6-31ff
- K9AY: 7-22, 15-17
- K9EK: 19-26
- KA1GT: 18-52, 18-54
- KA5FSB: 4-28
- KA5JPD: 19-42
- Kandonian, Armig G.: 7-27
- Kansas City Tracker (KCT): 19-30
- KB8I: 6-16
- KD5RO: 19-43
- KD7S: 5-15
- Keller, J. B.: 3-24
- Keyhole pattern: 17-3
- KG6IAL: 19-15
- KH6IJ: 19-6
- Kite: 22-2
- Klein cable grip: 22-18
- Knadle, Dick, K2RIW: 18-22, 19-35, 19-40
- Knife-edge diffraction: 23-13
- Knob and tube: 4-33
- Knots, for halyards: 20-5
- KO4TV: 16-16
- Kouyoumjian, R. G. and Pathak, P. H.: 3-25
- Kraus, John, W8JK: 4-1, 8-51, 19-5, 19-18
- Krome, Ed, K9EK: 19-14
- Krupp, Daniel A., W8NWF: 7-26
- KT-34XA tribander: 11-40

L

- L-network: 25-6ff
  - Adjustable feed system: 8-19ff
  - Feed system: 8-25ff
- L/C ratio: 7-9
- Ladder mast: 22-4
- Ladder-line:
  - Feeder: 4-33ff
  - Linear-loaded dipole: 6-34ff
- Lahlum, Robye, W1MK: 8-20
- Lambda: 2-2
- Lambert, Edgar, WA4LVB: 7-6
- Laplace loads: 4-15
- Lattin, William J., W4JRW: 7-11
- Law of reflection: 3-24
- Lawrence Livermore National Laboratories: 4-2
- Lawson, Jim, W2PV: 11-1
- Lazy-H: 8-48
- LC-matching networks, antenna: 9-9ff
- Lead weight: 11-9
- Leakage flux: 5-7
- Leeson corrections: 4-17
- Leeson, Dave, W6NL (ex-W6QHS): 2-16, 4-17, 11-27, 26-10
- Leggio, Joe, WB2HOL: 14-32
- Length-to-wire-diameter ratio: 4-6
- LEO satellite: 19-2, 19-3, 19-15
- Leslie, Sam, W4PK: 9-5
- Lewallen, Roy, W7EL: 4-2, 4-3, 8-10, 8-16, 8-23, 8-31, 27-57
- LHCP: 19-3, 19-19
- Libration: 23-7
- Light-duty guyed mast: 22-3
- Lightning:
  - Arrester: 1-9ff, 4-34ff
  - Grounds: 4-35
  - Protection: 1-11ff, 4-34ff
- Linear:
  - Coordinate systems: 2-12
  - Loading: 6-34ff
  - Polarization: 23-3
- Line: 18-2
  - as circuit elements: 28-10ff
  - Characteristic impedance: 24-4
  - Common-mode currents on: 27-7ff
  - Coupling to antennas: 26-1ff
  - Flattener: 26-1
  - for repeaters: 17-1
  - G-line: 18-2
  - Impedance transformation with: 28-13ff
  - Isolator: 7-7
  - Length, electrical, determining: 27-7, 27-29, 28-6
  - Loss: 25-1
  - Losses: 24-6ff
  - Matched-line losses: 24-6ff
  - Measurement, coaxial cable parameters: 27-29ff
  - Measurement, electrical length: 27-29
  - of force: 3-3
  - Printer: 4-3, 4-5
  - Radiation from: 7-3
  - Reactance & circuit Q: 25-4
  - Sampler, VHF: 27-19ff
  - Single-wire: 24-26
  - Smith Chart calculations: 28-1ff
  - Transient protection: 1-12
  - Velocity factor, from impedance measurements: 28-10
  - Z_0, from impedance measurements: 28-8ff
- Load: 4-14ff
  - Coil: 3-5, 4-14
  - Coil design: 16-3
  - Coil resistance: 16-9
  - Distributed material: 4-15

Load:
  Laplace: 4-15
  Mathematical: 4-15
  SWR: 9-1
  Up into itself: 25-9
Loading:
  End: 6-31
  Top: 3-5
Lobe: 2-10, 3-11, 7-4
  Higher angle: 11-36
  Low sidelobe: 11-33
  Major: 3-19, 8-3
  Minor: 8-2
  Second: 3-22
  Worst-case: 11-35
Log periodic antennas: 10-1ff
  Log-cell Yagi: 10-1, 10-10ff
Logarithm, common: 2-9
Logarithmic: 2-3
  Coordinate system: 2-12
Long boom, support: 20-9
Long path: 23-34ff
Long-distance communication: 4-20
Long-wire and traveling-wave antennas: 13-1ff
  Calculating length: 13-4
  Combinations: 13-5ff
  Directivity: 13-3ff
  Diversity effect: 13-1
  Feeding: 13-5
  Feeding the V beam: 13-9
  Gain: 13-1
  Gain vs wire length: 13-2
  Other V combinations: 13-8, 13-9
  Parallel wires: 13-6
  Resonant rhombic: 13-9ff
  Terminated: 13-10ff
  Tilted wires: 13-5
  V-beam: 13-6ff
Loop antennas: 5-1ff, 14-2
  and environment: 5-8ff
  and propagation effects: 5-8
  Antenna effect: 5-5
  Aperiodic arrays: 5-9
  Arrays of: 5-9
  Balance: 5-5
  Cookie-sheet variable capacitor: 5-16ff
  Current: 7-2, 7-8
  Design data tables: 5-13
  Distributed capacitance: 5-4
  Electrostatically shielded: 5-5
  Half wave: 5-1
  Horizontal: 5-19ff
  Inductive loading: 5-2
  Large: 5-1
  Loopstick: 5-2
  Losses in: 5-14
Loop antennas:
  One wavelength: 5-1
  Pattern comparisons: 5-12
  Pattern distortion: 5-5
  Pattern nulls: 5-4
  Patterns: 5-3
  Practical transmitting loops: 5-12ff
  Q of: 5-6
  Shielded: 5-5
  Skywire: 5-19ff
  Small: 5-1, 5-2ff
  Small, transmitting: 5-10, 5-10ff
  Stealth: 5-26ff
  Transmitting, construction and tune-up: 5-15
  Trombone variable capacitor: 5-15ff
  Tuned: 5-3ff
  Tuning: 5-3
  Tuning capacitor: 5-14ff
  Typical construction: 5-17ff
  Untuned: 5-2
  Vertical: 5-22
  vs phased arrays: 14-7ff
  Voltage: 7-2, 7-8
  Yagis, for 1296 MHz: 18-48ff
Loopstick: 5-6ff, 14-3
  for 3.5 MHz: 14-14ff
Loos guy wire tensioner: 22-18
Lord Rayleigh: 3-24
LOS (line of sight): 17-2
Loss:
  Additional loss due to SWR: 24-10ff
  and Smith Chart calculations: 28-6ff
  and SWR: 28-6ff
  Antenna broadband matching network: 9-3
  E-field: 3-6
  Earth: 3-2
  Ground: 16-9ff
  Heat: 2-2
  In loop antennas: 5-14
  In trap antennas: 7-10
  Line: 27-30, 28-6ff
  Measuring: 27-30, 28-8ff
  Near-field earth: 7-16
  Path: 17-8
  Radiation from transmission line: 24-1
  Resistance: 3-4ff, 9-2
  Resistive: 2-11, 8-10
  Return (dB), and SWR: 7-20
  Spillover: 19-17ff
  Transmission: 19-1
Loudspeaker: 2-1
Low:
  Earth orbit (LEO): 19-2
  Frequency antennas: 6-1ff
  Frequency fields: 1-17ff
  Impedance point: 4-13

- Low:
  - Power link-coupled antenna tuner: 25-13ff, 25-13ff
  - Q circuit: 2-6
- Lowest usable frequency (LUF): 23-27
- *LPCAD30*: 10-3, 10-5
- LPDAs: 4-17, 10-1ff, 26-2
  - Adding parasitic director: 10-8
  - Alpha: 10-1ff
  - Basic design considerations: 10-1ff
  - Behavior: 10-4
  - Circularizing tau: 10-7, 10-8
  - Design and computers: 10-3ff
  - Design procedure: 10-9ff
  - Equalizing upper-frequency response: 10-8
  - Feeding and constructing: 10-6ff
  - Log-cell Yagis: 10-10ff
  - Optimal sigma: 10-2
  - Performance weakness: 10-4
  - Phase line: 10-1
  - Relative current magnitude: 10-2, 10-5
  - Sigma: 10-1ff
  - Special correction: 10-8
  - Special design considerations: 10-7ff
  - Tau: 10-1ff
  - Wire LPDA for 3.5 or 7 MHz: 10-11ff
  - 5-band LPDA: 10-15ff

M

- Maer, Claude, W0IC: 14-14
- Magic bullet: 8-16
- Magnetic field: 2-7, 3-3
  - Health hazards: 1-18ff
  - 60 Hz, near equipment and appliances: 1-23ff
- Main lobe: 2-10, 11-3
- Mainframe: 4-3
- Major lobes: 3-19, 8-2, 13-3
- Mallete, Malcolm C., WA9BVS: 14-24
- Mallozzi, Domenic, N1DM: 5-2, 16-21, 17-3
- Malowanchuk, Barry, VE4MA: 19-45
- Manufacturers, antenna products: 21-1
- Maps:
  - Site planning: 4-19
  - Soil conductivities for continental USA: 3-14
- Marconi: 3-21
- Maritime antennas: 16-1ff
- Marmon-style clamp: 22-12
- Massachusetts Institute of Technology: 23-22
- Mast (also see Towers):
  - Centroid: 22-22
  - Guying: 22-5
  - Stout: 4-20
  - Strength: 22-22ff
- Masthead: 16-32
- Matched: 2-15
  - Lines: 24-4, 24-5, 26-3ff
  - -line loss: 24-10
- Matching: 17-1ff
  - Circuit: 6-11
  - Deliberate network mismatching: 9-6
  - Delta match: 18-5
  - Double adjustment stub: 18-5
  - Gamma: 9-13
  - Gamma match: 18-5
  - *GAMMA* program: 26-10
  - Hairpin match: 11-11
  - Impedance, short verticals: 16-12ff
  - Matching stubs: 26-12ff
  - Network loss: 9-8
  - of folded dipoles: 18-6
  - Optimum network matching: 9-6ff
  - Series section: 28-13ff
  - Stub match: 28-11ff
  - the line to the transmitter: 25-1ff
  - to the transmitter, short verticals: 16-13ff
  - Unit, Carolina Windom: 7-7
  - Universal stub: 18-5
  - with inductive coupling: 25-3ff
  - with lumped constants: 28-12ff
- Mathematical loads: 4-15
- Maximum:
  - Forward gain: 6-13
  - Line-of-sight distance: 23-6
  - Permissible exposure (MPE): 1-18ff, 4-18
  - Usable frequency (MUF): 23-20, 23-26ff
- Maxwell, James: 3-24
- Maxwell, M. Walter, W2DU: 26-22, 27-40
- McCaa, Bill, K0RZ: 19-14
- McCoy, Lew, W1ICP: 5-10
- McKim, Jim, W0CY: 19-24
- Measurements:
  - and spurious frequencies: 27-8
  - Antenna and transmission lines: 27-1ff
  - Current and voltage: 27-1
  - Current probe, RF: 8-33ff, 27-47ff
  - Feed-line electrical length: 8-36ff
  - Field strength: 27-43ff
  - Gain, antennas: 27-51ff
  - General information, antennas: 27-48ff
  - Impedance, antennas: 27-30ff, 28-5ff
  - Line length, electrical: 8-36ff, 27-8ff, 27-29
  - Noise bridge, for HF: 27-25ff
  - Radiation pattern, antennas: 27-52ff
  - Range testing, antennas: 27-47ff
  - Soil conductivity: 27-36ff
  - SWR: 27-1, 27-3ff
  - SWR, errors: 27-6
  - Transmission line parameters: 27-29ff
  - Wattmeter, calorimeter type: 27-22ff
  - Wattmeter, RF directional in-line: 27-9ff
- Mechanical strength: 4-32
- Medium: 2-1
- Metal fence: 4-26
- Metal-oxide varistor (MOV): 1-11

Method of moments: 4-1
MFJ-259B: 9-2
Michaels, Charles, W7XC: 3-12, 27-8
MicroDEM: 3-30ff, 17-2
Microphone: 2-1
MicroSmith: 4-13
Miller, James, G3RUH: 19-14
Millstone Hill: 23-21
Minimum SWR: 9-7
MININEC: 1-24, 2-15, 3-23, 4-1, 4-2, 7-22, 7-25, 8-21, 8-26, 10-3, 16-31
  Ground: 4-11
Minor lobes: 8-2ff, 8-7, 13-3
Mirror: 3-11
Mismatched lines: 24-5
  Deliberate: 9-6
  Results of: 27-48
Missionary radio station, HCJB: 12-1
Mitchell, Bob, N5RM: 11-40
MMDS dish: 19-12, 19-13, 19-18
Mobile and maritime antennas: 16-1ff
Mobile antennas:
  Base loading: 16-1
  Center loading: 16-1
  Continuously loaded: 16-13ff
  Equivalent circuit: 16-2ff
  Flutter: 23-5
  Mobile J antenna for 144 MHz: 16-21ff
  Optimum design: 16-5ff
  Top-loaded 144-MHz mobile: 16-26, 16-26
  VHF quarter-wavelength vertical: 16-27, 16-27
  5/8-wavelength 220-MHz mobile antenna: 16-28ff
  144-MHz 5/8-wavelength vertical: 16-28ff
Modeling:
  Environment, frequency: 4-12
  Environment, ground: 4-11
  History: 4-1ff
  Interactions: 4-20ff
  Limitations: 4-17ff
  Loads: 4-14ff
  Programs: 3-23, 4-1ff
  Tools: 4-19
Modifying Hy-Gain Yagis: 11-25ff
Moment of inertia: 22-22
  Antennas, stacking of: 18-7ff
  Yagi performance optimization: 11-5ff
  2-element quad model: 4-10
Monopole:
  Vertical: 2-17
  Vertical efficiency: 2-18
Moon: 19-1
Moonbounce: 19-1
Moore, Clarence, W9LZX: 12-1
Mountain tops: 6-3
Moxon rectangle beams: 11-46
Moxon, Les, G6XN: 6-31, 11-46
MUF: 23-20, 23-26ff
Multi:
  Hop propagation: 23-24ff
  Dipole antennas: 7-7ff
  Port network: 27-55
Multiband antennas: 7-1ff
  Ground systems: 3-10
  Harmonic radiation from: 7-34
  Random-length wires: 7-1ff
  Yagis: 11-26ff
Multicouplers, transmitter: 17-12
Multielement arrays: 8-1ff
Multiple quarter-wave sections: 26-7
Multiturn loops: 14-2
Mutual coupling: 4-14, 8-13, 8-56, 11-33
  and loss: 8-22
  Arrays: 8-26
  HFTA: 3-32
Mutual impedance: 2-2, 3-1, 3-10, 4-1
  and gain: 8-5ff

N

Trough reflector: 18-51
NØNSV: 19-18
N1DM: 5-2, 16-21, 17-2
N1JEZ: 19-16
N4KG: 6-23
N5BLZ: 19-33
N5RM: 11-40
N6BV: 3-21, 3-28, 11-27, 11-32, 11-37, 23-36, 25-15
N6BV/1: 6-9, 11-38ff, 11-45
N6JF: 15-8
N6LF: 6-13, 6-24, 7-22, 16-31, 27-54
  Extended Double Zepp: 6-13
N6NB: 18-13, 18-45
N6RO: 22-27
N7MQ: 27-57
National Academy of Sciences: 1-19
National Cancer Institute: 1-19
National Electrical Code: 1-8, 20-1
Natural disasters: 6-3ff
Natural low-frequency EM fields: 1-18
NC1I: 19-33
NCRP: 1-22
Near vertical incidence skywave (NVIS): 6-3ff
Near-field: 2-7, 3-1
  Earth loss: 7-16
Near-overhead angles: 11-37
Nearby communications: 6-3
Nearly resonant: 2-2
NEC: 1-24, 2-15, 3-23, 7-22, 7-25, 7-25, 10-3, 11-40, 12-4, 16-31
  NEC-2: 4-1, 4-3
  NEC-4: 4-2, 4-11, 4-17
  NEC-BSC: 3-24
NEC-4.1: 2-3, 8-21, 10-3
NEC-Win Plus: 3-22, 4-2, 10-3

NEC-Win Pro: 4-2
NEC/Wires: 7-33
Negative feed-point resistance: 8-15
Nelson, R. A., WBØIKN: 26-10
NEMA4: 19-10, 19-27
Newfoundland: 3-21
Nighttime band: 6-7
NM2A: 19-19
NNØF: 6-34
NOALOX: 15-9
Noise bridge, for HF: 27-25ff
Non reciprocal: 3-29
Norton source: 4-14
Nulls: 2-10, 3-11, 3-22, 8-7, 8-12, 11-30, 13-3
  Array: 8-21
  Disastrous: 11-33
  Mislocated: 8-10
NVIS: 6-3ff
  Antenna height: 6-8ff
  Choosing the right frequency: 6-7
  Geographic coverage: 6-4ff
  Low antennas and powerline noise: 6-9
  Strategy: 6-7ff
  Summary: 6-10

O

O'Dell, Pete, KB1N: 14-16
Oblique angle sounding: 23-23
OCF dipoles: 2-3, 7-8ff
  Even harmonics: 7-8
  Odd harmonics: 7-8
OD5CG: 26-5
Oerstad: 3-3
OET Bulletin 65: 1-20
Off-center-loaded dipoles: 6-39ff, 7-8ff
Offset crossed Yagi: 19-7
Ohio State University: 3-25
Ohm's law: 2-2
Omega match: 6-23, 26-11
Omnidirectional: 2-17
ON4UF: 7-8
ON4UN: 13-23
ON4UN's Low-Band DXing: 8-20
ON5UG: 19-13
One:
  Element Yagi: 11-8
  Port measurement: 27-55
  Way propagation: 23-34
  Way skip: 23-34
Open circuit, line termination: 28-3
Open sleeve antennas: 7-18ff, 7-23, 11-28
  Antenna mode: 7-18ff
  Bandwidth: 7-20
  Current distribution on: 7-20ff
  Gain: 7-21ff
  Impedance: 7-18ff
Open sleeve antennas:
  Monopole: 7-18
  Patterns: 7-24
  Practical construction: 7-24
  Transmission-line mode: 7-18ff
Open-wire lines: 2-2, 4-6, 26-1
Operator skill: 4-19
Optimized:
  10-meter Yagis: 11-12ff
  12-meter Yagis: 11-14ff
  15-meter Yagis: 11-17ff
  17-meter Yagis: 11-19ff
  20-meter Yagis: 11-20ff
  30-meter Yagis: 11-22ff
  40-meter Yagis: 11-23ff
Optimizing over local terrain: 11-45
Optimum ground-system configurations: 3-3
Optimum traffic frequency: 23-23
Ordinary wave: 23-21, 23-22
Origin: 4-4
Other antenna characteristics: 2-15ff
Over-illuminating, dish: 19-17ff
Overbeck, Wayne, N6NB: 18-13, 18-45
Overblown claims: 4-1
Overlay plots: 4-12

P

Pad, switchable attenuator: 27-42ff
Painter, J. R., W4BBP: 10-25
Parabolas: 18-18ff
  Dish: 19-15
  EME: 19-34ff
  Feed methods: 18-18ff
  Illuminating: 18-13ff
Paraffin, applying to wood: 20-12
Parallel:
  Equivalent circuit: 24-12
  Conductor lines: 26-1
  Tuned: 7-2
  Tuned circuits, at antenna terminals: 9-6ff
Parallel-wire transmission lines: 4-17
  Arrays: 8-6, 11-1ff
  Conductors: 4-29
  Effects: 2-2
  Element: 6-13, 6-13
Passive reflector, moon: 19-1
Patch:
  CP: 19-17
  Feeds: 19-20ff
  Round feed: 19-24
  S-band: 19-13
  Truncated corners: 19-21
Path loss: 17-8, 23-10,2313
Pattern: 18-1
  Bidirectional: 8-3
  Dipoles at different frequencies: 2-11

Pattern:
  Distortion, arrays: 8-10
  Distortion, dipole: 26-18
  E-plane: 2-8
  Elevation: 2-10
  Factor: 3-17ff
  Ground-reflection: 11-33
  H-plane: 2-8
  Half-power points: 8-3
  Measurement of: 27-52
  Planes: 2-8
  Shape: 2-8
  Unidirectional: 8-3
  Worksheets for: 27-52
PBA: 3-13
  and earth quality: 3-15ff
  and Salt water: 3-15
Pedersen wave: 23-23, 23-24
Penetrox: 7-28
Perfect:
  Conducting ground: 3-18
  Earth: 3-12
  Ground: 3-2, 4-2
  Transmission line: 4-17
Periscope antennas: 18-45ff
  Gain: 18-55
  Patterns: 18-56
Perrin, Mark, N7MQ: 27-57
Phase: 3-2, 3-12
  and wavelength: 23-2
  Definition of: 8-3
  Reflected signals: 3-2
  Relationships: 8-4
  Shift: 4-14
Phased arrays: 4-14, 6-12ff
  Adjusting feed systems: 8-32ff
  Baluns: 8-21
  Bi-square: 8-48ff
  Bidirectional: 8-2
  Binomial current grading: 8-43
  Bobtail curtain: 8-44ff
  Broadside: 8-2, 8-5, 8-37ff
  Bruce: 8-45ff
  Collinear 2 element: 8-37ff
  Common feed systems: 8-14ff
  Current distribution: 8-7
  Design examples: 8-23ff
  Directional switching: 8-33ff
  Driven: 8-2
  Driven combinations: 8-53ff
  Element feed-point impedances: 8-10
  End-fire: 8-2, 8-5, 8-50ff
  Feeding: 8-10, 8-14ff
  Feeding, shunt components: 8-21
  Forward gain: 8-26
  Four Square: 8-18, 8-27
  Four Square, L-network feed: 8-29
Phased arrays:
  Four Square, simplest feed: 8-28ff
  L-network feed system: 8-25ff
  Large, feed systems: 8-16
  Lazy-H: 8-48
  Loss resistance & pattern: 8-26
  Measuring currents: 8-32ff
  Mutual coupling: 8-26
  Other broadside: 8-42ff
  Parallel broadside: 8-41ff
  Pattern null degradation: 8-21
  Phasing arrows: 8-55
  Practical aspects: 8-31ff
  RDF: 14-5ff
  Receiving: 8-15, 8-22
  Recommended feed methods: 8-16ff
  Shunt or gamma-fed feeding: 8-20ff
  Simplest feed system: 8-18ff
  Sterba: 8-41
  Techniques: 8-10ff
  Unidirectional: 8-2
  Verticals: 6-24ff
  W8JK: 8-51ff
  3-element binomial broadside: 8-27
  4-element rectangular array: 8-29ff
  4-element, feeding: 8-20ff
  120 deg. fed, 60 deg. spaced: 8-30ff
Phasing lines: 8-10, 8-14ff
Phelps, Ted, W8TP: 5-26
Phi: 2-15
Photoionizes: 23-19
Physical Design of Yagi Antennas: 2-16
Pi-network: 25-1, 25-7ff
Pietraszewski, David, K1WA: 6-48
PL-259: 4-32
  Assembly: 24-22ff
Plane:
  Diagrams: 2-10
  Wave: 23-1
Plasencia, Richard, WØRPV: 5-16
Plastics, for antenna construction: 20-12
PlastiDip: 4-32
Plot:
  Polar: 11-33
  Rectangular: 11-33
Plumber’s delight: 26-10
Point source, *HFTA:* 3-31
Polar coordinates: 2-10, 2-15
Polarization: 2-8, 2-13, 3-11, 11-2, 19-1, 23-2ff
  Antennas: 17-1, 27-48
  Circular: 19-2ff
  Considerations: 18-2
  Diversity: 17-12
  Elliptical: 2-15, 2-16, 19-5, 23-3
  EME: 19-4
  Horizontal: 2-13
    Over flat ground: 3-15ff
    Polarized: 3-1ff

Polarization:
  Linear: 2-14, 23-3
  Reflection coefficients: 3-16
  Sense: 19-3
  Switching sense: 19-4
  Through ionosphere: 2-16
  Verical: 2-13
    Antennas: 3-20ff
    Polarized: 3-1ff
Pole, gin: 1-3ff
Pole-vault arm spreaders: 12-4, 12-5
Polygons: 4-5
Polyphaser Corp: 1-14
Portable:
  Antennas: 15-1ff
  Dipole for 80 to 2 meters: 15-4ff
  2-element 6-meter quad: 15-11ff
  3-element portable 6-meter Yagi: 15-13ff
Position readout: 19-42
Potts, Frank, NC1I: 19-33
Power:
  Density: 1-22ff, 2-10
  Effective isotropic radiated: 17-13
  Gain: 8-1
  Generators, emergency: 1-12
  Loss, traps: 7-14ff
  Ratio: 2-9
  RF, absorber circuit: 27-6
  Supplies, transient protection: 1-12
Powerboats:
  Antennas: 16-38ff
  Counterpoise: 16-38
Powlishen, Steve, K1FO: 18-28
Practical 6-meter Yagis: 18-27ff
Practical aspects, array design: 8-31ff
PRB-1 (federal preemption): 22-1
Prime center: 28-1, 28-2
Probe, for RF current measurement: 8-33, 27-46ff
Proceedings of the AMSAT Space Symposium: 19-16
Programs:
  AAT: 25-9ff
  GAMMA: 26-10
  HFTA (HF Terrain Assessment): 3-26ff
  HFTA.PDF: 3-29
  LPCAD30: 10-3
  MOBILE: 6-29, 15-8, 15-9, 16-6
  TLW: 24-12, 25-7, 26-13
  WinSmith: 24-12
  YO (Yagi Optimizer): 3-23
  YT (Yagi Terrain analyzer): 3-26
  YW (Yagi for Windows): 3-23
Prop-pitch rotator: 22-32
Propagation:
  Auroral: 23-36, 23-36
  Bending: 23-4
  Beyond line-of-sight, VHF: 23-5ff
  Diffraction: 23-4
  Do-it-yourself prediction: 23-43ff

Propagation:
  Ducting: 23-25ff
  Fading: 23-35
  Geographic area: 23-25
  Gray line: 23-37
  Ground wave: 23-4ff
  Ground-wave range: 23-5
  Long path: 23-34ff
  Maximum line-of-sight distance: 23-6
  Multi-hop: 23-24ff
  One-way: 23-34
  Prediction programs: 23-44
  Radio wave propagation: 23-1ff
  Reflection: 23-4
  Refraction: 23-4
  Scatter modes: 23-36ff
  Sky wave: 23-4, 23-15ff
  Space wave: 23-4ff
  What HF bands are open?: 23-38ff
Proplab Pro program: 23-22
Protection:
  Against electromagnetic pulse: 1-11ff
  Against lightning: 1-11ff
  Circuitry: 25-1
  Coaxial-line: 1-13, 1-13ff
  Transient, devices for: 1-11ff, 1-15
  Transient, for feed lines: 1-13
Proximity effect: 5-11
Pseudo-Brewster angle: 3-12
PTFE: 19-18
Ptolemy: 3-24
Pulley: 1-3, 20-5ff, 22-1
PVC pipe: 4-33, 7-27
PVRC mount: 22-27ff
Pyramidal horn: 19-14

Q

Q factor, antenna traps: 7-10
QTH for DXing: 3-21
Quad antennas: 4-18, 12-1ff
  Arrays: 12-1ff
  at low height: 12-3
  Constructing: 12-4ff
  Diamond or square: 12-5
  Loop Yagis, for 1296 MHz: 18-48ff
  Making it sturdy: 12-4ff
  Monoband 2-element: 4-10
  Multiband: 12-3ff
  Stacking: 18-13
  Swiss: 4-18
  VHF: 18-13
  vs Yagi: 12-1ff, 12-1ff, 12-1ff
  2-element, 8-foot boom pentaband: 12-9ff
  5-element, 26-foot boom triband: 12-5ff
  144 MHz, 2 element: 18-41
  144 MHz, 4 element portable: 18-41ff
Quadrifilar antenna: 19-4

Quagis:
  Construction: 18-46ff
  Design tables: 18-45ff, 18-45ff
  Feed method: 18-47
  VHF and UHF: 18-13
  1296 MHz; 10, 15 or 25 elements: 18-47
Quarter-wave:
  Half-sloper: 6-44
  Transformers: 26-4
Quartering lobes: 12-2
Quiet sun: 23-16ff

R

Radar: 23-21
Radials: 2-17
  Close to ground: 4-12
  Elevated: 6-20
  Quarter-wave, proximity to ground: 7-16
  Resonating the antenna: 6-17
  Wire systems: 3-3, 3-7ff
  Wires: 6-16
Radiated: 2-1
Radiating far field: 2-7, 2-8, 3-1
Radiating near field: 2-7, 2-8
Radiation:
  Efficiency: 8-11ff, 16-2, 16-9
  Feed line & directive array: 7-3
  Harmonic, from multiband antennas: 7-34
  Hazards: 1-17ff
  Nonionizing: 1-17ff
  Pattern: 2-6
  Pattern, coordinate scales: 2-12
  Pattern, dipoles at different frequencies: 2-11
  Pattern, of corner reflector: 18-15
  Resistance: 2-2, 3-2, 8-1, 8-10, 9-2, 16-3, 16-5ff
Radio waves:
  Bending: 23-3ff
  Horizon: 23-5
  Nature of: 23-1ff
  Path loss: 17-8
  Propagation: 23-1ff
Rain seepage: 4-34
Rain-gutter antenna: 4-25
Random length wire: 4-26
Range:
  of elevation angles needed: 3-21ff
  of frequencies: 4-12
  Test site for antenna measurements: 27-47ff
Rauch, Tom, W8JI: 13-22
Ray:
  Reflected: 3-11ff
  Technique: 3-24
  Tracing: 3-24ff, 23-1, 23-22
RDF antennas:
  Adcock: 14-5ff
RDF antennas:
  ARDF (Amateur Radio direction finding): 14-1ff
  by triangulation: 14-1
  Calibration and use: 14-8ff
  Electronic antenna rotation: 14-7
  Ferrite rod: 14-3
  Ferrite-core: 14-11ff
  Four-way mobile DF system: 14-24ff
  Fox-hunting DF twin ’tenna: 14-20ff
  Interferometer: 14-18
  Loop antennas: 14-2
  Loopstick for 3.5 MHz: 14-15ff
  Multiturn loops: 14-2
  Phased arrays: 14-4ff
  Sensing: 14-2
  Shielded frame: 14-10ff
  Shielded loop: 14-2
  Shielded loop with sensing antenna for
    28 MHz: 14-13ff
  Snoop Loop for close-range HF RDF: 14-13ff
  TDOA: 14-18
  Wullenweber: 14-7
  144-MHz cardioid-pattern RDF antenna: 14-16ff
Re-radiation: 4-21
Reactance circles (Smith Chart): 28-2
Reactive:
  Fields: 2-8
  Near field: 2-2, 2-7, 3-1, 3-2
Real-world terrain and stacks: 11-45ff
Rear quartering lobes: 12-2
Receiving antenna: 2-6
  Arrays: 8-15
  Wave antennas: 13-16ff
Reciprocity: 2-1, 2-15
Recommended feed methods: 8-16ff
Recreational vehicles (RV): 16-1
Reduction in propagation speed: 23-2
Reflected:
  Power: 24-5
  Ray: 3-11
  Waves: 3-11ff
Reflection: 23-4
  Coefficient: 9-1, 24-7, 28-4
  Factor: 3-18ff
Reflectometers: 27-9ff
  Time domain: 27-32ff
Reflector: 6-13
  Corner: 18-14ff
  Cupped S-band: 19-7
  Parasitic: 11-1ff
  Retrograde: 11-28
  Trough: 18-17ff, 18-51, 18-51
Refraction: 23-4
Regier, Frank, OD5CG: 26-5
Regulatory restrictions: 4-19
Relative values: 2-8

- Relay:
  - Antenna & preamplifier: 19-27
  - Remote switching: 8-35
- Repeater antennas: 17-1ff
  - Cardioid: 17-3
  - Downtilt, vertical beam: 17-4ff
  - Isolation: 17-7ff
  - Matching: 17-1ff
  - Omnidirectional: 17-3
  - Polarization: 17-1
  - Top and side mounting: 17-5ff
- Repeaters:
  - Coverage: 17-2ff
  - Diversity techniques: 17-12ff
  - Duplexers: 17-9ff, 17-9ff
  - Equipment manufacturers: 17-15
  - Isolation: 17-7ff
  - System assembly: 17-14
  - Transmission lines: 17-1
  - 144 MHz duplexer: 17-14ff
- Resistance:
  - Bridge: 27-3ff
  - Circles (Smith Chart): 28-1, 28-2
  - Effective ground: 3-7
  - Feed point, versus element coupling: 8-5
  - Ground system, arrays: 8-24
  - Loss: 8-10
  - Loss, mutual coupling & gain: 8-13ff
  - Radiation: 2-2, 3-2, 8-10
  - RF loss: 2-3
  - Swamping: 27-2
  - Virtual: 2-2
- Resonance:
  - Full-wave: 2-4
  - Half-wave: 2-4
  - in guy wires: 22-18ff
- Resonant: 2-2
  - Antennas: 9-2ff
  - Breaker: 4-30
  - Rhombic antenna: 13-9ff
- Resonators, cavity type: 17-9
- Return loss (dB), and SWR: 7-20
- Return path: 6-17
- RF:
  - ANSI exposure guidelines: 1-21
  - Athermal effects: 1-18
  - Awareness guidelines: 1-23
  - Chokes: 4-30
  - Current probe: 4-30
  - Decoupling: 6-46
  - Feedback: 7-2
  - Ground, alternative: 1-10
  - in the shack: 7-7
  - Loss resistance: 2-3
  - Rectification: 4-26
  - Safe exposure levels: 1-19
  - Thermal effects: 1-18
- RFI: 4-29
- RHCP: 19-3, 19-10
- Rhodes, Peter D., K4EWG: 10-15, 10-25
- Rhombic: 3-31, 13-1, 13-9ff
  - Front-to-back ratio: 13-15
  - Methods of feed: 13-15
  - Multiwire: 13-14, 13-15
  - Resonant: 13-9ff
  - Terminated: 13-11ff
  - Terminated, multiband design: 13-12
  - Terminated, tilt angle: 13-12
  - Termination: 13-13
- Richard, Louis, ON4UF: 7-8
- RingRotor: 11-41
- Roadway illumination standards: 6-20
- Rohn: 22-9
- Role of the Sun: 23-15ff
- Rope: 1-2ff
- Rotators: 22-30ff
  - Heavy duty: 4-20
  - Transient protection: 1-14ff
- RS-15: 19-2
- Rubber duck: 19-2
- Rusgrove, Jay, W1VD: 15-1
- Russell, Thomas, N4KG: 6-23

S

- S-band dish feed: 19-7
- S-parameters: 27-54ff
- Safety: 1-1ff, 4-22
  - Belts: 1-2, 1-5
  - D-ring: 1-5
  - Electrical: 1-8ff
  - Fall arrest: 1-3
  - Gloves: 1-5
  - Hard hats: 1-2, 1-5
  - Knots: 1-6
  - Passers-by: 1-1
  - RF burns: 1-1
  - RF radiation hazards: 1-17ff
  - Safety belt: 22-15
  - Slingshot: 1-1
  - Structural: 22-1
  - Switch box: 1-4
  - Working on towers: 1-1ff
- Sag, in antenna wires: 20-1, 20-3ff
- Sailboats:
  - Antenna modeling: 16-31ff
  - Flag halyard: 16-37
  - Grounding systems: 16-36ff
  - HF antennas: 16-31ff
  - Patterns, backsay vertical: 16-33
  - Patterns, masthead vertical: 16-33
  - Patterns, transom vertical: 16-32
  - Rigging: 16-31
  - Temporary antennas: 16-35ff

Sailboats:
  Transom and masthead mounted verticals: 16-32ff
  40-meter backstay half sloper: 16-35
Saltwater: 3-17, 3-20, 6-16, 6-50, 7-7
  Swamp on a hill: 3-20
Sampler, line, VHF: 27-19ff
Satellites: 19-1
  Geo-synchronous: 19-1
  High-altitude: 19-2ff
  Phase-3: 19-2ff
SCALE program: 2-16
Scaling:
  Boom diameter: 2-16
  Element diameters: 2-16
  Element lengths: 2-16
  Element spacings: 2-16
  Frequency: 4-13
Scatter modes: 23-36ff
Scattering: 23-4
  Parameters: 27-54ff
Schedule, taper, for antenna elements: 20-9, 20-10
Schelkunoff: 4-17
Schmidt, Kevin, W9CF: 8-16
Schulz, Walter, K3OQF: 6-31
Schuster, Jack, W1WEF: 16-1
Scissors rest: 22-7
Screwdriver:
  Coil cover: 16-20
  Loading coil: 16-16ff
  Mobile antenna: 16-16ff
Seawater: 3-12, 3-17, 3-20, 6-16, 6-50, 7-7
Second lobe: 3-22
Segments: 4-1ff
  Density: 4-6
  Length-to-wire-diameter ratio: 4-6
  Mutually coupled: 4-1
  Source: 4-5ff
Selective fading: 23-35
Self impedance: 2-2, 8-4, 11-9
Selsyn: 19-30
Sensing antennas: 5-8, 14-3ff
Sensitivity, bridge measurements: 27-5
Series:
  Equivalent circuit: 24-12
  Resonant circuit: 2-5, 2-6
  Section transformers: 26-5ff, 28-13ff
Severns, Rudy, N6LF: 6-13, 6-24, 7-22, 16-31, 27-54
Sevick, Jerry, W2FMI: 6-36, 7-16, 8-11
Seybold, Mack, W2RYI: 7-27
Shield, anti-climbing, for towers: 1-6ff
Shielded:
  Frame loops: 14-10ff
  Loop: 14-2
  Loop with sensing antenna for 28 MHz: 14-12
  Parallel lines: 24-23
Shock, electrical, and ground systems: 1-8ff
Short:
  Antennas: 6-29ff
  Circuit, line termination: 28-2
  Fat wires: 4-8
  Path: 23-34
  Range communication: 4-20
Shortened:
  Dipoles: 6-39ff
  Radials: 6-66ff
Shorty forty: 6-41ff
Shriner, Bob, WA0UZO: 17-14
Shunt:
  Components, array feeding: 8-21
  Feed, installing: 6-22
Sidelobes: 2-11, 27-53
  Quartering: 12-2
Sidescatter: 23-36
Signal-to-interference ratio: 6-5
Signal-to-noise ratio: 2-6
Silicone sealant: 6-13
Simple and Fun Antennas for Hams: 11-11
Simple:
  Broadband dipole for 80 meters: 9-16, 9-17
  Broadband matching techniques: 9-3ff
  Twin-lead antenna for HF portable operation: 15-1, 15-2
  Wire antennas: 7-1ff
Simplest feed system: 8-18ff, 8-25
Simulations of reality: 3-26ff
Site map: 4-19
Skeleton disc: 6-31
Skin depth: 3-17
Skin effect: 23-2
Skip:
  Distance: 23-24
  Zone: 23-24
Sky wave: 3-32, 23-4, 23-15ff
Sleeve, open: 11-28
Slide switch: 4-28
Sling: 22-27
Slingshot: 22-2
Slopers:
  Antennas: 6-44ff
  Front-to-back ratio: 6-49
  7-MHz sloper system: 6-48ff
Sloping the radials of a ground plane: 6-18
SMA: 19-23
Smith chart: 4-3, 26-5, 28-1ff
  Designing series-section transformers: 28-13ff
  Designing stub matches: 28-11ff
  Off-center mode: 28-14
  Procedure summary: 28-8
Smith, George, W4AEO: 10-17
Smith, Phillip H.: 28-1
Smoothed sunspot numbers (SSN): 23-17ff
Snell's law: 3-24

Snyder dipole: 9-15
SO-239: 4-31
Sobel, Jack, W0SVM: 6-41
Soft-drawn copper wire: 20-1
Solar:
  Flares: 23-27, 23-28
  Flux: 23-17ff
  Wind: 23-15
Solid radiation pattern: 2-8
Sommerfeld: 3-24, 8-23
Sommerfeld-Norton: 4-11
Sound waves: 2-1
Sounder:
  Chirp: 23-21
  Vertical incidence: 23-21
  Ionospheric: 23-20ff
Source: 4-4
  Current: 4-14, 4-22
  Impedances: 4-7
  Segment: 4-5ff
  Sensitivity to placement: 4-13
  Specification: 4-13
  Split: 4-13
  Voltage: 4-14, 4-22
Space:
  Communications: 19-1ff
  Diversity: 11-38, 17-12
  Wave: 23-4ff
Spare me the nulls: 11-32
Specific absorption rate (SAR): 1-18ff
Specific monoband Yagi design: 11-11ff
Spiders, quad: 12-7
Spillover loss: 19-17ff
Spin fading: 19-24
Spinning reel: 22-2
Splattering: 25-1
Splicing: 20-4, 22-2
Split source: 4-13
Sporadic E: 23-35
Spot frequency: 4-12
Spotting mast: 22-23
Spreading loss: 23-3
Spreadsheet: 4-13
Squint angle: 19-10
SSN: 23-17ff
Stacking: 4-9
  and azimuthal diversity: 11-38
  and fading: 11-37ff
  and gain: 11-29
  and precipitation static: 11-38
  and wide elevation footprint: 11-29ff
  Disimilar Yagis: 11-44
  Distances between Yagis: 11-32ff
  Distances for multiband Yagis: 11-37
  Main antenna: 11-39
  Minimum stacking distance: 4-22
  Monoband antennas: 18-7ff
Stacking:
  Multiplier antenna: 11-39
  Quads: 18-13
  Stacks of stacks: 18-12ff
  VHF/UHF Yagis: 18-7ff
  Yagis: 3-22, 3-27, 11-29ff
  Yagis at different frequencies: 18-8ff
  Yagis at same frequencies: 18-10ff
  10-meter example: 11-30ff
  15-meter example: 11-31
  20-meter example: 11-31ff
Stackmatch: 11-42
Stacks:
  Boom length & spacing: 11-34
  Christmas tree: 11-27
  Distance and Lobes at HF: 11-33ff
  Spacing: 11-34
  Switching out Yagis: 11-33
  Vertical spacing not critical: 11-35
Stagger tuned: 7-7
  Dipoles: 9-4, 9-5
  Radials: 9-5
Stallman, Ed, N5BLZ: 19-33
Standing:
  Wave antennas: 13-2
  Waves: 24-8ff
  Wave ratio (SWR): 24-9
Stanford, John, NN0F: 18-51, 6-34
Stanley, John, K4ERO: 3-9
Statistical entities: 3-22
Statistics, elevation angle: 6-1
Stepped diameter correction: 4-18
Sterba curtain: 8-41
Stork, Rudy, KA5FSB: 4-28
Straw, R. Dean, N6BV: 3-21, 11-37, 25-15
Structural safety: 22-1
Stubby antenna: 16-1
Stubs:
  Capacitive: 7-12
  Filter: 19-22
  Harmonics: 25-3
  Matching: 28-11ff
  on coax lines: 26-14
Subsidence: 23-9
Sudden disappearing filaments: 23-28
Suding, Robert, W0LMD: 19-11
Summer solstice: 6-6
Sun noise: 19-13
Sunspots: 23-15, 23-16
Super-J Maritime Antenna: 16-23ff
Suppliers:
  Addresses: 21-4ff
  HF antennas: 21-2
  Quad parts: 21-3
  Towers: 21-3
Supports:
  Belt hooks: 1-5

Supports:
  for antennas: 22-1ff
  for open-wire line: 4-33ff
  Ladder mast: 22-3
  Trees for verticals: 22-3
  Truss: 22-1ff
Surface acoustic wave (SAW): 14-8
Surface wave: 23-3ff
Surge impedance: 24-4
Susceptance: 28-5
Swinging link: 25-5
SWR: 24-9
  Along a line: 28-6ff
  and line losses: 28-6ff
  and the transmission line: 26-1
  Bowl-shaped curve: 9-2
  Change with common-mode current: 26-18
  Circles (Smith Chart): 28-3
  Load: 9-1
  Measurement: 27-1, 27-3ff
  Measurement, errors: 27-6
  Return loss (dB), and SWR: 7-20
Symmetry, RDF: 14-2ff
Synchros: 19-30
System approach: 4-1

T

T-match: 26-8ff
T-network: 25-8ff
  high pass: 25-2
Tag lines: 22-26
Tandem-Match, in-line directional RF
    wattmeter: 27-9ff
  High-power operation: 27-17ff
Tape measure beam for RDFing: 14-32ff
Taper, in antenna elements: 2-16, 4-17ff, 20-9
  and electrical length: 20-11
Tapered:
  Element, spacing: 11-10
  Lines: 26-6
  Pier-pin base: 22-9
Tapped-coil matching network: 16-15ff
TAPR: 19-30
TDR (Time Domain Reflectometer): 11-42
Teflon: 19-18
Telephone pole: 22-8
Telerana: 10-17ff
Telerana, improving the: 10-21
Telescoping aluminum tubing: 2-16, 4-17ff
Tennis ball shock absorber: 16-1
Tension, on antenna wires: 20-2
Terleski, Jay,: 11-42
Terminated:
  Long-wire antennas: 13-10ff
  Rhombic antenna: 13-11ff
Terminations on lines:
  Short and open circuits: 28-3
Terminator: 23-37
Terrain:
  Data from the Internet: 3-30ff
  Optimizing over local: 11-45
  Profile: 3-29, 17-2
Test site, antenna: 27-47ff
Texas potato masher antenna: 19-2
Textbooks, Chap 2: 2-19
TH6DXX: 11-37, 11-41
TH7DX: 3-31, 11-32, 11-37, 11-39, 11-45
The AMSAT Journal: 19-2, 19-21
The ARRL Antenna Compendium series: 9-1
The ARRL Antenna Compendium, Vol 1: 16-5
The ARRL Antenna Compendium, Vol 2: 8-18, 9-13, 9-15
The ARRL Antenna Compendium, Vol 3: 3-12, 19-33
The ARRL Antenna Compendium, Vol 4: 4-1, 6-13, 9-7, 9-17, 10-21
The ARRL Antenna Compendium, Vol 5: 6-24, 6-34, 7-22, 15-8, 15-11
The ARRL Antenna Compendium, Vol 6: 9-5, 11-46
The ARRL Antenna Compendium, Vol 7: 5-26, 16-16
The ARRL Handbook, 2006 Ed.: 6-31
The ARRL UHF/Microwave Experimenter's
    Manual: 19-24
The ARRL UHF/Microwave Projects
    Manual: 19-24, 19-42
The Pounder: 10-22ff
The Snoop Loop for close-range HF RDF: 14-13ff
Theta: 2-15
Thevenin source: 4-14
Thin-wire approximation: 4-7
Three-dimensional: 4-10
Time and frequency stations: 23-26
Time domain reflectometry: 27-32ff
Time-Difference-of-Arrival (TDOA): 14-18
TLW (Transmission Line for
    Windows: 8-24, 11-44, 25-7
Tolles, H. F., W7ITB: 26-10
Top (elevated) counterpoise: 6-45
Top hat: 3-5
  Construction: 6-37ff
  Multiwire: 6-30
Top loading: 3-5, 3-6, 6-18
Top-loaded 144-MHz mobile antenna: 16-26, 16-26
Top-loading capacitance: 16-14
Topography: 3-29
Torque arm assembly: 22-17,2209
Total current: 3-1
Towers:
  and lightning: 22-12
  Antenna installation: 22-23ff
  Antenna placement: 22-20ff
  Antenna selection and installation: 22-8ff
  Anti-climbing shield: 1-6ff

Towers:
  Bases: 22-9, 22-12ff
  Building antennas on the tower: 22-25ff
  Canvas bucket: 1-2
  Climbing equipment: 1-4ff, 1-5ff
  Climbing tips: 1-4ff
  Clothing: 1-2
  Crank-up: 4-22, 4-23, 22-10ff
  Fold-over: 4-23
  Freestanding: 4-22, 22-10ff
  Ground captain: 1-6
  Guyed: 4-22, 22-8ff
  Hard hats: 1-2
  Installation: 22-13ff
  Installing antennas on: 1-4ff
  Notebook: 1-5
  PVRC mount: 22-27ff
  Raising antennas alongside: 22-23ff
  Rest periods: 1-6
  Rohn: 22-9
  Roof-mounted tripod: 22-30ff
  Rope and pulley: 1-2
  Safety belt: 1-1ff
  Suppliers: 21-3
  Tapered pier-pin base: 22-9
  Tie-strings: 1-6
  Tilt-over: 22-11
  Tram, sling: 22-27
  Tram, using a: 22-27ff
  Unguyed: 22-10ff
  Wet tower: 1-5
  Working on: 1-1ff
Tram, using a: 22-27ff
Transducers: 2-1, 2-6
Transformers: 2-4, 2-6
  Quarter wave: 26-4
  Series section: 28-13ff
Transition function: 3-25
Transmatch: 18-6ff, 25-1
Transmission line: 24-1ff
  Air-insulated coaxial: 24-17ff
  Air-insulated lines: 24-15ff
  as circuit elements: 24-13, 24-14
  Cable capacitance: 24-21
  Characteristic impedance: 24-4
  Characteristics, table: 24-18
  Coaxial cables: 24-19ff
  Coaxial fittings: 24-22ff
  Construction: 24-15ff
  Equation: 24-11
  Flexible lines: 24-17ff
  Half-wavelength line: 24-13
  Highly reactive loads: 24-14
  Impedance transformer: 24-11ff
  Input impedance: 24-11ff
  Installation: 24-22ff
Transmission line:
  Installing: 4-31ff
  Line voltages and currents: 24-11ff
  Losses: 24-6ff, 25-1
  Losses and deterioration: 24-20
  Matched lines: 24-4, 24-5
  Matched-line attenuation, chart: 24-20
  Matched-line losses: 24-6ff
  Mismatched lines: 24-5
  Nonresistive terminations: 24-6
  Open-wire lines: 2-2, 24-2
  Parallel-conductor lines: 24-18ff
  Practical: 24-7ff
  Quarter-wavelength line: 24-13
  Reflection coefficient: 24-7
  Running the feed line: 4-33ff
  Simple lightning arrester: 4-35
  Single-wire: 24-22
  Standing-wave ratio: 24-9
  Support for open-wire line: 4-33ff
  Surge impedance: 24-4
  Terminated: 24-4ff
  Testing: 24-27
  Tuned feeders: 7-1
  Twisted: 4-33
  Two-wire lines: 24-2
  Velocity of propagation: 24-3
  Voltage & current: 24-15
  Voltage and power ratings: 24-21
  Waveguides: 24-2
  Window lead-in panel: 4-34
  Window line: 7-4, 24-17
  Z_0: 24-4
  Zip-cord: 15-2, 15-3
Transmission loss: 19-1
Transmission-line resonators (TLR): 9-10ff
  as part of antenna: 9-13ff
  as part of feed line: 9-16ff
  Transformer: 9-11ff
Transmitter chassis: 7-2
Transom: 16-23
Transom and masthead mounted verticals: 16-32ff
Transponder noise floor: 19-11
Transportable antennas: 15-1
Trap Antennas: 7-9ff, 25-2
  Dipole, 3.5 to 28 MHz, 5 bands: 7-10ff
  Dipole, 80, 40, 17 and 12 meters: 7-12ff
  Dipole, 80, 40, 20, 15 and 10 meters: 7-11ff
  Trapped dipole: 26-2
  Trapped tribanders: 11-26ff
  21 and 28 MHz vertical: 7-17ff
Traps: 4-14
  Coax cable: 7-11ff
  Coax capacitor: 7-17
  Coaxial: 7-11ff, 7-13
  Construction: 7-11, 7-17ff

- Traps:
  - Doorknob capacitor: 7-11
  - Electrical loading: 7-9
  - Fundamentals: 7-9
  - Impedance equation: 7-10
  - L/C ratio: 7-9
  - Losses: 7-10
  - Losses & power rating: 7-14ff
  - Non-resonant: 7-10
  - Parallel resonant: 7-9
  - Power loss: 7-14ff
  - Power rating: 7-14ff
  - PVC pipe: 7-12
  - RTV sealant: 7-12
- Tree-mounted HF ground-plane: 15-3, 15-4
- Trees, as antenna supports: 22-1ff
  - Vertical antennas: 4-24
- Triband Yagi: 4-20, 25-2, 26-2
- Tropospheric:
  - Bending: 23-4
  - Ducting: 23-10ff
  - Propagation of VHF: 23-4, 23-7ff
  - Scatter: 23-35
- Trough reflector: 18-51
- Trough reflectors: 18-17ff, 18-51
  - for 432 and 1296 MHz: 18-51
- True north: 2-9
- Tubing, aluminum: 4-7, 20-6ff
  - Alloy numbers: 20-6
  - Construction with: 20-8ff
  - Data table: 20-7
  - Sources for: 20-7
  - Telescoping: 4-17ff
- Tucson Amateur Packet Radio (TAPR): 19-30
- Tuned feeders: 7-1
- TUNER.SUM: 25-15
- Tuners: 25-1
  - Antenna: 4-6, 7-3, 7-7
  - Balanced: 8-22
  - Circuit balance: 25-6
  - Circuit Q: 25-3
  - Harmonic attenuation: 25-2ff
  - High-power ARRL antenna tuner: 25-15ff
  - L-network: 25-6ff
  - Low-power link-coupled: 25-13ff, 25-13ff
  - Measurement of line input current: 25-6
  - Pi-network: 25-7ff
  - Series and parallel coupling: 25-3, 25-4
  - T-network: 25-8ff
  - Variable coupling: 25-5
  - with inductive coupling: 25-3ff
- Turnstile over reflector antenna: 19-3
- TV antenna: 4-25
- TV mast material: 22-5
- TV-type standoff insulators: 4-33
- TVRO:
  - C-band: 19-11
  - Converted C-band: 19-29ff
  - EME, surplus: 19-41ff
  - Feeding: 19-45
  - Modified elevation mount: 19-44
- Twilight zone: 23-37
- Twin-lead folded dipole: 15-1, 15-2
- Type-N connectors: 24-25

U

- U-Adcock: 14-6
- UBC (Uniform Building Code): 22-8
- UHF Quagis: 18-45ff
- UHF-VHF antenna systems: 18-1ff
- UL 1449: 1-12
- Ultraviolet (UV): 23-19
- Umbrella shape loading: 6-32
- Unbalanced coax feeding a balanced dipole: 26-17ff
- Uncontrolled environments: 1-20ff
- Under-illuminating (dish): 19-17ff
- Underwriters Laboratories: 1-12
- Undisturbed ionospheric conditions: 6-3
- Uneven local terrain: 3-24ff
- Uniform theory of diffraction (UTD): 3-24ff
- Unmatched system: 26-2
- Unterminated long-wire antennas: 13-2
- US Geological Survey: 3-29
- US Naval Academy: 3-30, 17-2
- USGS map: 3-29
- Using capacitive end hats: 6-36
- UT-141 coax: 19-23
- UTD: 3-29
- UV: 11-11
  - Protection: 19-19
  - Radiation: 4-33

V

- V-Beam antenna: 13-1, 13-6ff
  - Feeding: 13-9
  - Other combinations: 13-8, 13-9
- Vacuum-tube amplifiers: 25-1
- Vaisala Lightning Explorer: 6-5
- Variable coupling: 25-5
- Varney, Louis, G5RV: 7-5
- VE2CV: 16-22
- VE4MA: 19-45
- VE7CA: 10-21, 15-11
- VE7CA 2-element portable HF triband Yagis: 15-15ff
- Vector Network Analyzer (VNA): 27-54ff
- Velocity factor:
  - of line, from impedance measurements: 28-8ff
- Velocity of propagation: 24-3

Vertical antennas: 6-15ff
  Buried radials: 6-22
  Buried-radial ground system: 6-16
  Continuously loaded verticals: 6-37ff
  Counterpoises: 6-16ff
  Elevated radials: 6-16ff
  Equivalent loading: 6-23ff
  Examples: 6-20ff
  Examples of short verticals: 6-36ff
  Far-field ground reflections: 3-11ff
  Feed-point impedance and ground system: 6-17ff
  Flagpoles: 6-20
  Folded monopole: 6-19
  Ground conductivity: 3-11
  Ground dielectric constant: 3-11ff
  Ground plane: 6-18ff
  Ground systems for vertical monopoles: 3-2ff
  Half-wave dipole: 4-8
  Half-wave vertical dipole (HVD): 6-15
  Irrigation tubing: 6-20
  Less-than-ideal ground systems: 3-2ff
  Monopoles: 3-2ff
  Multiband: 7-16ff
  Omega match: 6-23
  Reflection coefficient: 3-13ff
  Roadway illumination standards: 6-20
  Short: 7-16ff
  Shortening the radials: 6-36ff
  Shunt-fed: 6-21ff
  Shunt-fed gamma: 6-22
  Sloping the radials of a ground plane: 6-18
  Standoff insulators: 6-22
  Top loading: 6-18
  Trap: 7-17ff, 7-17ff
  Tree mounted: 4-4
  Umbrella shape loading: 6-32
  1.8-3.5 MHz using existing tower: 6-21ff
  6-Foot high 7-MHz antenna: 6-36ff
Vertical incidence critical frequency: 23-26
Vertical incidence sounder: 23-21
Vertical monopole: 2-17
Vertical monopole, efficiency: 2-18
VHF:
  Quads: 18-13, 18-41ff
  Quagis: 18-13, 18-45ff
  Quarter-wavelength vertical: 16-27
VHF/UHF:
  Antenna systems: 18-1ff
  Antenna-height gain, nomograph: 23-13
  Capabilities, nomograph: 23-11
  Effective receiver sensitivity, nomograph: 23-12
  Reliable coverage: 23-10ff
  Station gain: 23-10ff
  Terrain: 23-12
View antenna window (*EZNEC*): 4-8
Viewshed: 3-31, 17-2
Vinyl electrical tape: 4-32
Virtual resistance: 2-2
VNA: 27-54ff
  Array example: 27-56
  Multi-port network: 27-55
VOAAREA: 6-5, 23-25
VOACAP: 6-5, 6-6, 11-36, 23-29, 23-33
  Parameters: 23-29
Voltage:
  Balun: 26-27
  Clamping, protection: 1-15
  Induced: 3-1
  Loop: 7-2, 7-8
  Ratio: 2-9
  Reflection coefficient: 28-4
  RF, measurement: 27-1
  Source: 4-14
  Transmission lines: 24-15
Voltmeter, RF: 27-1
Vortex shedding: 22-6

W

W-shaped SWR curve: 9-7
W0CY: 19-24, 19-26
W0LMD: 19-12, 19-15, 19-18, 19-20, 19-21, 19-24, 19-29, 19-31
W0RPV: 5-16
W0SVM: 6-41
W1AW: 23-20
W1CF: 6-47
W1EYI: 16-21
W1FB: 6-43, 6-47
W1GAN: 17-14
W1GHZ (ex-N1BWT): 19-15, 19-18, 19-19, 19-21
W1ICP: 5-10
W1KSC: 18-41
W1MK: 8-20
W1VD: 15-1
W1WEF: 6-9, 16-1, 16-2
W2BML: 13-16
W2DU: 8-21, 26-22, 27-40
W2DU balun: 26-24
W2FMI: 6-36, 7-16
W2PV: 11-1, 11-8
W3DZZ: 7-10, 7-12
W3JIP: 15-4, 15-9
W3KH: 19-4
W4AEO: 10-17
W4BBP: 10-25
W4HHK: 18-13, 18-14
W4JRW: 7-11
W4MB: 27-36
W4RNL: 10-1, 11-46
W5LUA: 19-16, 19-45
W5QJR: 5-10, 5-12

W5RTQ (now K6SE): 6-21
W6AAQ: 16-28
W6HPH: 4-30
W6NL: 4-17, 11-27, 26-10
W6NL (ex-W6QHS): 2-16
W6OWQ: 11-40
W6TWW: 16-5, 16-28
W6UYH: 7-27
W7CNK: 19-42
W7EL: 8-10, 8-16, 8-23, 8-31, 27-57
W7ITB: 26-10
W7XC: 3-12, 27-8
W8GZ: 7-6
W8JI: 13-23
W8JK: 8-13, 8-51, 19-5, 19-18
W8JK array: 6-13, 8-51ff
W8NWF: 7-26
W8NX: 7-11, 7-13
W8NX trap dipoles: 7-11ff
W8TP: 5-26
W9CF: 8-16
W9DUU: 14-23
W9LZX: 12-1
W9PE: 14-20
WA0UZO: 17-14
WA2ANU: 14-18
WA3FET: 3-24
WA3ULH: 5-17
WA4JVE: 10-15
WA5FRF: 16-23
WA5TNY: 19-42
WA9BVS: 14-24
Walters, Mike, G3JVL: 18-48
Ward, Al, W5LUA: 19-45
Wardley, David, ZL1BJQ: 19-35
Water pipe: 7-2
Wattmeters:
  A directional in-line RF: 27-9ff
  Calorimeter type, for VHF and UHF: 27-22ff
Wave:
  Angle: 3-13ff
  Attenuation: 23-3
  Extraordinary: 23-21, 23-22
  Front: 23-1, 23-2
  Ordinary: 23-21, 23-22
  Theory: 3-24
Waveguides: 18-3ff, 24-2
  Coupling to: 18-4
  Dimensions: 18-3
  Evolution of: 18-3
  Modes of propagation in: 18-3
Wavelength: 2-1
Wavelength-to-diameter ratio: 2-3
WB0DGF: 10-3
WB0IKN: 26-10
WB0KIZ: 1-17
WD4FAB: 1-99, 19-10, 19-2, 19-3, 19-5, 19-14, 19-18, 19-19, 19-27
Weatherproofing, wood: 19-26
Weber, Dick, K5IU: 22-20
White, Allan, W1EYI: 16-21
Why tribanders?: 11-40
Wilkie, Jim, WY4R: 7-6
Wilkinson divider: 8-10, 8-16
Williamson, Gerald, K5GW: 19-33
Wilson, Paul M., W4HHK: 18-14, 18-18
Wilson, Robert, AL7KK: 7-22
Wind compensation: 22-3
Wind loading: 11-8
Windom:
  Antenna: 7-6
  Carolina: 7-6ff
  Carolina, matching unit: 7-7
Windom, Loren G, W8GZ: 7-6
Window 450-Ω ladder line: 7-5ff
Winter solstice: 6-6
Wire: 4-7
  Antenna, splicing: 20-4
  as antenna conductors: 20-1
  Closely spaced: 4-17
  Coordinate shortcuts: 4-7
  Copper clad steel: 20-2
  Copper, data table: 20-2
  Crossing: 4-17
  Fat wires connected to skinny wires: 4-17
  Geometry: 4-4ff
  Grid: 2-8
  Loss: 4-15
  Mesh: 6-17
  Radial systems: 3-7ff
  Random length: 4-26
  Short fat and acute-angle junction: 4-8
  Straight: 4-5
  Stressed, data table: 20-3
  Tension and sag: 20-2ff
  Types of: 20-1
Wire LPDA for 3.5 or 7 MHz: 10-11ff
Wiring, electrical, and safety: 1-8ff
Witt, Frank, AI1H: 9-1, 9-6, 9-9
Wolf, Johann Rudolph: 23-16
Wolff, Ken, K1EA: 11-31
Wood:
  for antenna construction: 20-12
  Weatherproofing: 20-12
Worst-case front-to-rear: 8-3
Worst-case front-to-rear ratio: 11-3
Wright, Joe, W4UEB: 7-6
Wullenweber antenna: 14-7
WWV/WWVH: 23-44
WX0B: 11-42
WX0B Approach to stack matching and feeding: 11-42ff

Y

- Yagi: 2-16, 11-1ff
  - Bandwidth: 11-4ff
  - Co-planar crossed: 19-5
  - Comparisons, 3-element designs: 11-6
  - Comparisons, 5-element designs: 11-6
  - Comparisons, 6-element designs: 11-6, 11-8
  - Comparisons, 8-element designs: 11-6, 11-9
  - Construction with aluminum tubing: 11-10
  - Drive impedance and SWR: 11-4ff
  - Element tuning: 11-9
  - F/R: 11-5
  - F-R ratio: 11-2ff
  - Feeding: 11-5
  - Gain: 11-2ff
  - Gain & pattern degradation due to stacking: 18-9
  - Gain and boom length: 11-6ff, 11-10
  - Gain versus F/R ratio: 11-2ff
  - Horizontal model: 4-9
  - Input impedance: 11-4ff
  - Interlaced elements: 11-26
  - Loop, for 1296 MHz: 18-48ff
  - Mechanical strength: 11-2
  - Modifying Hy-Gain Yagis: 11-25ff, 11-25ff
  - Monoband performance optimization: 11-5ff
  - Multiband: 11-26ff
  - Multiband stack spacing: 11-37
  - Offset crossed: 19-7
  - Optimized 10-meter Yagis: 11-12ff
  - Optimized 12-meter Yagis: 11-14ff
  - Optimized 15-meter Yagis: 11-18ff
  - Optimized 17-meter Yagis: 11-19ff
  - Optimized 20-meter Yagis: 11-20ff
  - Optimized 30-meter Yagis: 11-22ff
  - Optimized 40-meter Yagis: 11-23ff
  - Optimum design parameters: 11-5ff
  - Optimum designs and element spacing: 11-8ff
  - Patterns: 11-2ff, 11-2ff
  - Performance optimization: 11-5ff
  - Performance parameters: 11-2ff
  - Specific designs: 11-12ff
  - Stacked Yagis: 11-29ff
  - Stacking: 18-7ff
  - Stacking different frequencies: 18-8ff
  - Stacking same frequencies: 18-10ff
  - Stacking stacks of different frequencies: 18-12ff
  - Stacking, feed method: 18-7ff
  - Trapped tribanders: 11-26ff
  - Two elements: 11-2ff
  - VHF and UHF: 18-7ff
  - 2-element designs: 11-8
  - 6-meter: 18-27ff
  - 15 m Yagis: 11-17ff
- Yagi vs quad: 12-1ff
- Yagi-Uda: 11-1
- *YagiMax*: 3-23
- Yankee Clipper Contest Club: 11-31
- Yield strength: 22-23
- *YO* (Yagi Optimizer): 3-23
- *YT* (Yagi Terrain analyzer): 3-26, 23-31
- YV5DLT: 10-17
- *YW* (Yagi for Windows): 3-23

Z

- Z_0 of lines: 24-4
  - From impedance measurements: 27-30, 28-8
- Zenith angle: 2-9, 2-15
- Zepp, end-fed: 7-2
- Zepp, extended double: 8-40ff
- Zeppelin: 7-2
- Zinc-chromate primer: 20-13
- Zip-cord antennas: 15-2ff
- ZL1BJQ: 18-22, 19-35
- Zone current: 3-5, 3-8
- ZS6JT: 19-11
- Zurich sunspot numbers: 23-16
- 1-800-MAPS-USA: 3-29
- 1.8 MHz antennas, receiving loop: 5-23ff
- 1.8-3.5 MHz vertical using existing tower: 6-21ff
- 1.8-MHz antennas using towers: 6-47ff
- 1.8-MHz inverted-L: 6-42ff
- 2-element broadside/end-fire switching: 8-34
- 2-element quad: 12-1
- 2-element Yagis: 11-8
- 2-element, 8-foot boom pentaband quad: 12-9ff
- 2M-22C: 19-27
- 2M-CP22: 19-10
- 3-element binomial broadside array: 8-27
- 3.5 MHz antennas, horizontal loop: 5-22ff
- 3.5 to 28 MHz trap dipole, 5 bands: 7-10ff
- 3.5 to 30 MHz small transmitting loops: 5-13ff
- 3D analysis: 4-16
- 4-element arrays, feeding: 8-20ff
- 4-element rectangular array: 8-29ff
- 4-element rectangular switching: 8-34
- 5-band LPDA: 10-15ff
- 5-element, 26-foot boom triband quad: 12-5ff
- 5/8-wavelength 220-MHz mobile antenna: 16-29ff
- 6-Foot high 7-MHz vertical antenna: 6-36ff
- 7 MHz antennas:
  - Horizontal loop: 5-22ff
  - Vertical loop: 5-22
- 7-MHz sloper system: 6-48ff
- 7N1JVW: 19-21
- 10 GHz pyramidal horn: 18-52ff
- 14-14.35 MHz Log-Yag: 10-25ff
- 20/15/10-meter triband 2-element Yagi: 15-15ff
- 21 and 28 MHz trap vertical: 7-17ff
- 23CM22EZA: 19-7
- 30/17/12-meter triband 2-element Yagi: 15-17ff
- 40-meter backstay half sloper: 16-35ff

40-meter wire Yagi: 15-19ff
80, 40, 17 and 12-meter trap dipole: 7-12ff
80, 40, 20, 15 and 10-meter trap dipole: 7-11ff
80-meter dipole with TLR transformer: 9-17
80-meter DX special: 9-13ff
120 deg. fed, 60 deg. spaced array: 8-30ff
135-foot, 80 to 10-meter dipole: 7-3ff
144 MHz antennas:
  Cardioid-pattern RDF antenna: 14-16ff
  Ground-plane: 18-23, 18-23ff
  Quad, 2 elements: 18-41
  Quad, 4 element portable: 18-41ff
  Quagi, 15 elements: 18-45ff
  Yagi, 12 elements: 18-34ff
  5/8-wavelength vertical: 16-28ff
144 MHz duplexer: 17-14ff
222 MHz antennas:
  Ground-plane: 18-23ff
  Quagi, 15 elements: 18-45ff
  Yagi, 16 elements: 18-38ff
432 MHz antennas:
  Ground-plane: 18-23ff
  Quagi, 15 elements: 18-45ff
  Quagi, 8 elements: 18-45ff
  Trough reflector: 18-42
  Yagi, 22 elements: 18-31ff
436-CP30: 19-10
1296 MHz antennas:
  Quagi, 10 elements: 18-46ff
  Quagi, 15 elements: 18-46ff
  Quagi, 25 elements: 18-47ff

Notes

Notes

Notes

Notes

Notes

Notes

Notes

FEEDBACK

Please use this form to give us your comments on this book and what you'd like to see in future editions, or e-mail us at **pubsfdbk@arrl.org** (publications feedback). If you use e-mail, please include your name, call, e-mail address and the book title, edition and printing in the body of your message. Also indicate whether or not you are an ARRL member.

Where did you purchase this book?

☐ From ARRL directly ☐ From an ARRL dealer

Is there a dealer who carries ARRL publications within:

☐ 5 miles ☐ 15 miles ☐ 30 miles of your location? ☐ Not sure.

License class:

☐ Novice ☐ Technician ☐ Technician with code ☐ General ☐ Advanced ☐ Amateur Extra

---

Name ARRL member? ☐ Yes ☐ No

______________________________ Call Sign ______________

Daytime Phone ( ) ______________________ Age ______________

Address ______________________________

City, State/Province, ZIP/Postal Code ______________________ E-mail: ______________

If licensed, how long? ______________________

Other hobbies ______________________

____

Occupation ______________________

For ARRL use only	**ANT BK**
Edition	21 22 23 24 25 26
Printing	1 2 3 4 5 6 7 8 9 10 11 12

From ______________________________

____

____

Please affix postage. Post Office will not deliver without postage.

EDITOR, ARRL ANTENNA BOOK
ARRL—THE NATIONAL ASSOCIATION FOR
AMATEUR RADIO
225 MAIN STREET
NEWINGTON CT 06111-1494

— — — — — — — — — please fold and tape — — — — — — — — —

Introduction to the CD-ROM Edition
The ARRL Antenna Book, 21st Edition

> "In recent years it has been borne home on us most forcibly that there is greater room for increased performance through superior antenna systems than in any other part of the equipment."
>
> —*from the Foreword to the First Edition,*

Much has changed since 1939, including the possible ways of delivering information—this CD-ROM is evidence of that! One thing that hasn't changed is that antennas and antenna systems are still the make-or-break component of any amateur station. We are pleased to bring you this 21st edition of *The ARRL Antenna Book* on CD-ROM. The CD-ROM book contains all of the text, drawings and photos contained in the printed 21st edition. And exclusive to the CD-ROM are over 70,000 pages of propagation tables that can help you determine what HF propagation to expect throughout the world, throughout the year and throughout the sunspot cycle.

Make sure you try out the software included for the PC. Follow the instructions for installation of the software and data files.

Using this CD-ROM

This CD-ROM is viewed using Adobe's *Reader* software. Version 7.0 of the software is included on the CD-ROM. The book and the companion files include hyperlinks. These links will appear in blue or green text. Clicking on the text of a hyperlink will cause *Reader* to display another, related part of the book. (See the *Reade*r Help documentation for information on configuring this feature.)

The version of *Acrobat Reader* used with this CD-ROM includes Acrobat Search capability, which allows rapid full-text search of the entire book. This functions as an instant index for every chapter and word in the book. We strongly recommend that you take a few minutes to view the on-line documentation available from *Acrobat Reader*'s Help menu.

Note: Adobe *Reader* version 6.0 or higher is required to use the search index included on this CD-ROM. Older versions of *Acrobat Reader* will not work with the search index, but are otherwise functional. Again, Adobe *Reader* 7.0 is included on the CD-ROM, if you need to install this version.

Installing Adobe *Acrobat Reader*

You may not have *Acrobat Reader* installed on your computer or you may have an older version installed. Installing Adobe *Acrobat Reader Ver.7* is optional during the main Setup installation, and you can do it later, after installing the *Antenna Book* software too.

To install *Acrobat Reader* for *Windows*:
Select **Run** from the *Windows* **Start** menu.

1. Type or Browse to **d:\AdbeRdr709_en_US.exe** (where d: is the drive letter of your CD-ROM drive; if the CD-ROM is a different drive on your system, use the appropriate letter) and press **Enter**.
2. Follow the instructions that appear on your screen.

To install *Acrobat Reader* for the Macintosh:

1. From the top-level folder of the CD, double click on the file "Adobe_Reader_MAC_708.dmg" to open up the disk image. Then double click the Adobe Reader Installer icon to launch the installer.

AB21 Intro to CD.DOC HE:RDS 3/7/2007 8:14 AM Page 3

USA

W1B	Boston, MA
W2A	Albany, NY
W2N	NYC, NY
W3D	Washington, DC
W4A	Montgomery, AL
W4F	Miami, FL
W4G	Atlanta, GA
W4K	Louisville, KY
W4N	Raleigh, NC
W4T	Memphis, TN
W5A	Little Rock, AR
W5H	Houston, TX
W5L	New Orleans, LA
W5M	Jackson, MS
W5N	Albuquerque, NM
W5O	Oklahoma City, OK
W5T	Dallas, TX
W6L	Los Angeles, CA
W6S	San Francisco, CA
W7A	Phoenix, AZ
W7I	Boise, ID
W7M	Helena, MT
W7N	Las Vegas, NV
W7O	Portland, OR
W7U	Salt Lake City, UT
W7W	Seattle, WA
W7Y	Cheyenne, WY
W8M	Detroit, MI
W8O	Cincinnati, OH
W8W	Charleston, WV
W9C	Chicago, IL
W9I	Indianapolis, IN
W9W	Milwaukee, WI
W0C	Denver, CO
W0D	Bismarck, ND
W0I	Kansas City, MO
W0K	Middle of US, KS
W0M	St. Louis, MO
W0N	Omaha, NE
W0S	Pierre, SD

Other, North America

6Y	Kingston, Jamaica
8P	Bridgetown, Barbados
HP	Panama City, Panama
KL7	Anchorage, Alaska
KP2	Virgin Islands
TI	San Jose, Costa Rica
V3	Belmopan, Belize
VE1	Halifax, Nova Scotia
VE2	Montreal, Quebec
VE3	Toronto, Ontario
VE4	Winnipeg, Manitoba
VE5	Regina, Saskatchewan
VE6	Edmonton, Alberta
VE7	Vancouver, BC
VE8	Yellowknife, NWT
VO1	St. John's, NFL
VP2	Anguilla
VP5	Turks & Caicos
XE1	Mexico City, Mexico

Europe

CT	Lisbon, Portugal
DL	Bonn, Germany
EA	Madrid, Spain
EI	Dublin, Ireland
ER	Kishinev, Moldava
F	Paris, France
G	London, England
I	Rome, Italy
JW	Svalbard
OH	Helsinki, Finland
OK	Prague, Czech Republic
ON	Brussels, Belgium
OZ	Copenhagen, Denmark
SV	Athens, Greece
TF	Reykjavik, Iceland
UA3	Moscow, Russia
UA6	Rostov, Russia
UR	Kiev, Ukraine
YO	Bucharest, Romania
YU	Belgrade, Yugoslavia

South America

CE	Santiago, Chile
CP	La Paz, Bolivia
FY	Cayenne, French Guiana
HC	Quito, Ecuador
HC8	Galapagos Islands
HK	Bogota, Columbia
LU	Buenos Aires, Argentina
OA	Lima, Peru
P4	Aruba
PY1	Rio de Janeiro, Brazil
PY0	Fernando de Noronha
YV	Caracas, Venezuela
YV0	Aves Island
ZP	Asuncion, Paraguay

Asia

1S	Spratly Islands
3W	Ho Chi Minh City, Vietnam
4J	Baku, Azerbaijan
4S	Columbo, Sri Lanka
4X	Jerusalem, Israel
9N	Katmandu, Nepal
A6	Dubai, UAE
AP	Karachi, Pakistan
BY1	Beijing, China
BY4	Shanghai, China
BY0	Lhasa, China
HS	Bangkok, Thailand
HZ	Riyadh, Saudi Arabia
JA1	Tokyo, Japan
JA3	Osaka, Japan
JA8	Sapporo, Japan
JT	Ulan Bator, Mongolia
TA	Ankara, Turkey
UA9	Perm, Russia
UA0	Khabarovsk, Russia
UN	Alma-Ata, Kazakh
VR2	Hong Kong
VU	New Delhi, India
VU7	Andaman Islands
XZ	Rangoon, Myanmar

Oceania

3D2	Fiji Islands
DU	Manila, Philippines
FO	Tahiti
H4	Honiara, Solomon Islands
JD1	Ogasawara Island
KH0	Saipan, Mariana Islands
KH5K	Kingman Reef
KH6	Honolulu, Hawaii
KH8	American Samoa
V7	Kwajalein, Marshall Islands
VK2	Sydney, Australia
VK6	Perth, Australia
VK8	Darwin, Australia
YB	Jakarta, Indonesia
ZL1	Aukland, New Zealand
ZL3	Christchurch, New Zealand

Africa

3B9	Rodrigues
3C	Bata, Equatorial Guinea
3V	Tunis, Tunisia
5N	Lagos, Nigeria
5R	Antananarivo, Madagascar
5U	Niamey, Niger Republic
5Z	Nairobi, Kenya
6W	Dakar, Senegal
7Q	Lolongwe, Malawi
7X	Algiers, Algeria
9J	Lusaka, Zambia
9L	Freetown, Sierra Leone
9X	Kigali, Rwanda
C9	Maputo, Mozambique
CN	Casablanca, Morroco
CT3	Madeira Islands
D2	Luanda, Angola
EA8	Canary Islands
IG9	Lampedusa, Italy
J2	Djibouti
ST	Khartoum, Sudan
SU	Cairo, Egypt
VQ9	Chagos, Diego Garcia
XT	Burkina Faso
ZS1	Capetown, So. Africa
ZS6	Johannesburg, So. Africa

These PDF files contain propagation prediction tables valid from the transmitting site indicated in the filename to seven generalized receiving locations throughout the world in the Summary Tables and for the 40 CQ Zones in the Detailed Tables. The user selects a single transmitting site closest to his/her location. You can access this data by opening *Adobe Acrobat Reader* and selecting **Prop Index.pdf**. Or you can operate from the main table of contents in the left pane of the opening window.

Each transmitting location is organized by five levels of solar activity over the whole 11-year solar cycle:

VL (Very Low: SSN between 0 to 20)
LO (Low: SSN between 20 to 40)
ME (Medium: SSN between 40 to 60)
HI (High: SSN between 60 to 100)
VH (Very High: SSN between 100 to 150)
UH (Ultra High: SSN greater than 150)

The seven generalized locations throughout the world for the Summary Tables are:

EU = Europe (all of Europe)
FE = Far East (centered on Tokyo, Japan)
SA = South America (centered on Asuncion, Paraguay)
AF = Africa (centered on Lusaka, Zambia)
AS = southern Asia (centered on New Delhi, India)
OC = Oceania (centered on Sydney, Australia)
NA = North America (all of USA).

Both types of propagation files show the highest predicted signal strength (in S-units) throughout the generalized receiving area, for a 1500-W transmitter and rather good antennas on both sides of the circuit. The standard antennas are 100-foot high inverted-V dipoles for 80 and 40 meters, a 3-element Yagi at 100 feet for 20 meters, and a 4-element Yagi at 60 feet for 15 and 10 meters. Discount the S-Meter readings in the tables to represent a smaller station:

Subtract 2 S units for a dipole instead of a Yagi
Subtract 3 S units for a dipole at 50 feet instead of a Yagi at 100 feet
Subtract 1 S unit for a dipole at 50 feet rather than a dipole at 100 feet
Subtract 3 S units for 100 W rather than 1500 W.
Subtract 6 S units for 5 W rather than 1500 W.

Shown below is an image of a Summary Table printout from Boston to the rest of the world, for Very High solar activity in January. This table could be used, for example, to help plan which bands to operate when on a DXpedition to some exotic location.

The Detailed Table printout from Boston to the rest of the world on 20 meters for January from Boston during a Very High level of the solar cycle is shown on the following page. It shows the predicted signal strength in each of the 40 CQ Zones around the world. Note that long-path openings are predicted by an asterisk appended to the end of the predicted signal strength.

Also located on the CD-ROM in the \Propagation subdirectory is the **Fig6Tab.pdf** file described in Chapter 3 of the printed book. This set of tables shows the hours open to each of 10 regions throughout the USA for Very-Low/Medium/Very-High levels of SSN.

Enjoy the software. We would appreciate any feedback or bug reports you might have.

73,

R. Dean Straw, N6BV
Editor, *The ARRL Antenna Book*
email: **n6bv@arrl.org**

Sample Summary Propagation-Prediction Table, January from Boston to the World

Jan., MA (Boston), for SSN = Very High, Sigs in S-Units. By N6BV, ARRL.

	80 Meters							40 Meters							20 Meters							15 Meters							10 Meters							
UTC	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	UTC
0	9+	-	9+	9+	8	-	9+	9+	5	9+	9+	9	-	9+	1	9+	9+	9+	9+	9	9+	-	9	9+	2	2	9+	9+	-	1	8	-	-	8	9+	0
1	9+	-	9+	9+	8	-	9+	9+	4	9+	9+	9	2	9+	1	9	9+	8	9+	9+	9+	-	3	9	-	7	9+	9	-	-	-	-	-	4	2	1
2	9+	-	9+	9+	7	-	9+	9+	4	9+	9+	9	7	9+	1	9	9+	8	9	9+	9+	-	-	3	-	-	7	9	-	-	-	-	-	-	2	2
3	9+	-	9+	9+	1	2	9+	9+	4	9+	9+	9	9	9+	-	7	9+	7	8	9+	9	-	-	-	-	-	-	-	-	-	-	-	-	-	2	3
4	9+	-	9+	9+	-	7	9+	9+	5	9+	9+	8	9	9+	-	5	9+	9	9	9	9+	-	-	1	-	-	-	-	-	-	-	-	-	-	2	4
5	9+	-	9+	9+	-	8	9+	9+	6	9+	9+	7	9	9+	-	5	9+	9	9	5	9+	-	-	-	-	-	-	-	-	-	-	-	-	-	2	5
6	9+	-	9+	9+	-	8	9+	9+	7	9+	9+	7	9	9+	-	8	9+	8	9	5	9+	-	-	-	-	-	-	-	-	-	-	-	-	-	2	6
7	9+	-	9+	9+	-	8	9+	9	8	9+	9+	7	9+	9+	-	9	9+	-	7	9	9+	-	-	1	-	-	-	-	-	-	-	-	-	-	2	7
8	9	7	9+	9	-	8	9+	9	8	9+	9+	8	9+	9+	-	9	9+	-	4	9+	9+	-	-	1	-	-	-	2	-	-	-	-	-	-	2	8
9	8	7	9+	7	-	8	9+	9	9	9+	9	8	9+	9+	-	6	9+	-	1	9+	9+	-	-	-	-	-	-	1	-	-	-	-	-	-	2	9
10	5	8	9+	2	3	8	9+	9	9	9+	8	8	9	9+	4	-	9+	9+	1	5	9	-	-	-	-	-	-	-	-	-	-	-	-	-	2	10
11	1	8	9+	-	4	9	9+	8	9	9+	5	8	9	9+	9+	4*	9+	9+	7	-	8	-	-	9	9	-	-	-	-	-	-	-	-	-	2	11
12	-	7	8	-	1	9	9+	6	9	9+	1	8	9	9+	9+	9	9+	9	9	1*	9+	9	8*	9+	9+	9	5*	-	-	2*	9	9	1	1*	2	12
13	-	-	-	-	-	2	9+	4	8	8	-	7	9	9+	9+	9	9+	9	9	9+	9+	9+	7	9+	9+	9+	3*	9	9	5*	9+	9+	9	6*	2	13
14	-	-	-	-	-	-	9+	2	7	4	-	5	8	9+	9+	9	9+	8	9	9	9+	9+	9	9+	9+	9+	9	9+	9	6*	9+	9+	9	1*	1	14
15	-	-	-	-	-	-	9	1	5	-	-	4	5	9+	9+	9	9+	9	9	9	9+	9+	9+	9+	9+	9+	9	9+	9	5	9+	9+	6	6	8	15
16	-	-	-	-	-	-	8	3	4	-	-	3	1	9+	9+	8	9	9	9	9	9+	9+	9+	9+	9+	9	9+	9+	9	8	9+	9+	-	8	9	16
17	-	-	-	-	-	-	8	5	3	-	2	4	-	9+	9+	8	9+	9+	9	9	9+	9+	9	9+	9+	1*	9+	9+	-	8	9+	9+	-	8	9+	17
18	-	-	-	-	-	-	9	7	4	2	5	5	-	9+	9+	9	9+	9+	9	9	9+	9+	9	9+	9+	1	9+	9+	-	7	9+	9+	-	9+	9+	18
19	1	-	-	1	-	-	9+	8	5	6	8	7	-	9+	9+	9	9+	9+	9	9	9+	-	9+	9+	9+	2	9	9+	-	6	9+	9+	-	9+	9+	19
20	4	-	2	5	-	-	9+	9	6	9	9	8	-	9+	9+	9	9+	9+	9	9	9+	-	8	9+	9+	3	9	9+	-	1	9+	9	-	9	9+	20
21	7	-	8	7	1	-	9+	9+	7	9+	9+	8	1	9+	8	9	9+	9+	9	9	9+	-	6	9+	9+	3	9	9+	-	-	9+	5*	-	9+	9+	21
22	9	2	9+	9	8	-	9+	9+	7	9+	9+	9	4	9+	2	9+	9+	9+	9	9	9+	-	9+	9+	9	1	9+	9+	-	5	9+	4*	-	9	6	22
23	9	-	9+	9	8	-	9+	9+	7	9+	9+	9	-	9+	1	9+	9+	9+	9	9	9+	-	9+	9+	6	-	9	9+	-	7	9+	2*	-	9	2	23
	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	

Sample Detailed Propagation Table for 20 Meters, January, Boston to World for Very High SSN

20 Meters: Jan., MA (Boston), for SSN = Very High, Sigs in S-Units. By N6BV, ARRL.

Zone (UTC -->)	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23
KL7 = 01	9+	9+	9+	7	-	-	-	-	-	-	-	-	-	-	-	3	9+	9+	9+	9+	9+	9+	9+	9+
VO2 = 02	9+	9	9	9	9	9	8	7	5	3	2	1	5	9+	9+	9+	9+	9+	9+	9+	9+	9+	8	9+
W6 = 03	9+	9+	9+	7	7	1	1	5	8	8	3	-	-	1	9	9+	9+	9+	9+	9	9	9+	9+	9+
W0 = 04	9+	9+	9+	8	5	5	5	5	3	2	1	-	-	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+
W3 = 05	4	2	2	2	2	2	2	3	3	3	3	2	1	1	8	9+	9+	9+	9+	9+	9+	9+	9+	9
XE1 = 06	9+	9+	7	9	9+	9+	9+	9+	9+	9+	9	8	9+	9+	9+	9+	9	9	9	9	9+	9+	9+	9+
TI = 07	9+	9+	8	9	9	9	9	9	9	9+	9	9+	9+	9+	9+	9+	9	8	9	9	9+	9+	9+	9+
VP2 = 08	9+	9+	9+	9+	9+	9+	9+	9+	9+	8	9	9+	9+	9+	9+	9+	9	9+	9+	9+	9+	9+	9+	9+
P4 = 09	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9	9	9	9	9+	9+	9+	9+	9+
HC = 10	9+	8	9+	9	9	9	9	9	7	3	1	7	9+	9+	9	5	5	5	7	8	9+	9+	9+	9+
PY1 = 11	9+	9+	9+	9	9	9+	9+	9	8	6	9	9+	8	2	1	-	-	1	4	8	9	9+	9+	9+
CE = 12	9+	9+	9+	9+	9+	9+	9+	9+	9	8	8	9+	9	8	2	1	1	-	1	3	7	9	9+	9+
LU = 13	9+	9+	9+	9+	9+	9+	9+	9+	8	8	8	9+	8	4	2	1	-	-	1	4	8	9	9+	9+
G = 14	-	-	-	-	-	-	-	-	-	-	-	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	8	2	-
I = 15	-	-	-	-	-	-	-	-	-	-	4	9	9	9	9	9	9	9+	9+	9	8	2	-	-
UA3 = 16	1	1	1	-	-	-	-	-	-	-	-	8	9	9+	9+	9+	9	8	5	-	-	-	-	1
UN = 17	1	-	-	8	7	7	7	1	-	-	-	2	9	9	9	6	-	-	2	4	8	9	5	4
UA9 = 18	6	7	6	6	9	9	9	7	4	1	-	-	8	8	6	6	5	6	7	8	9	9	8	7
UA0 = 19	9+	9	9	6	5	5	8	8	8	4	-	-	2	6	8	8	8	7	4	4	7	9	9+	9+
4X = 20	8	6	3	1	-	3	4	-	-	-	1	8	8	8	8	8	9	9	9+	9	9	8	7	7
HZ = 21	9+	9	4	3	8	8	2	-	-	-	1	7	8	9	8	8	9	9	9	9	9	9	9	9
VU = 22	7	5	8	7	6	7	5	-	-	-	-	6	9	9	9	9	3	2	2	2	8	8	9	8
JT = 23	9	9+	9	5	7	8	8	6	3	-	-	2*	8	8	5	6	8	8	8	8	9	7	5	6
VS6 = 24	9	9	9	5	4	5	7	8	6	1	-	1*	5	7	1	1	1	1	4	2	-	-	-	9
JA1 = 25	9	9	8	7	5	5	8	9	9	6	-	1	1	2	7	7	6	2	-	-	7	9	9+	9
HS = 26	9	9	6	4	2	-	-	2	1	-	-	2*	9	9	9	9	8	7	5	4	5	-	1*	1
DU = 27	9	8	7	-	-	-	5	7	7	1	-	-	1*	9	9	7	6	4	5	3	1*	1*	8	9
YB = 28	9	8	1	-	-	-	-	-	-	-	-	4*	8	9	9	9	8	8	9	9	9	9	9+	9+
VK6 = 29	3*	4*	-	-	-	-	-	-	5	3	-	-	-	5	9	9	9	8	9	9	9	9	9	8
VK3 = 30	1*	-	-	-	-	-	1	3	9	9	4	-	-	9+	9	8	2	1	-	-	1	2*	5*	4*
KH6 = 31	9	9+	9+	9+	8	2	2	6	4	-	-	-	-	-	-	-	9	9	8	7	6	4	6	7
KH8 = 32	-	2	9	9	9	5	5	9	9+	9+	5	-	-	9+	9	9	8	5	3	1	-	-	-	-
CN = 33	-	-	-	-	-	-	-	-	-	-	9	9+	9	9	8	9	9	9+	9+	9+	9+	9+	9+	7
SU = 34	9	8	3	3	-	1	4	-	-	-	2	7	8	8	8	8	9	9	9+	9+	9+	9+	8	8
6W = 35	9+	8	-	-	2	7	5	-	-	-	9+	9+	8	5	4	3	7	9	9+	9+	9+	9+	9+	9+
D2 = 36	9+	9+	5	3	9	9	8	-	-	-	3	-	-	-	-	4	4	7	8	9	9+	9+	9+	9+
5Z = 37	9+	9	2	4	8	8	1	-	-	-	2	-	-	3	5	5	7	8	9	9	9+	9+	9+	9+
ZS6 = 38	9+	9+	8	7	8	9	6	-	-	-	-	-	-	-	1*	1	2	6	8	9	9+	9+	9+	9+
FR = 39	9+	8	2	1	4	1	-	-	-	-	-	-	-	2*	3*	1*	1	3	8	9	9+	9+	9+	9+
FJL = 40	9+	9+	7	4	7	8	7	1	-	-	-	1*	8	9	9	9	9	9	9	9	9+	9+	9+	9+
Zone (UTC -->)	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23

Expected signal levels using 1500 W and 3-element Yagis at 100 feet at each station.

$14

More Wire Antenna Classics

Volume 2

More of the best articles from ARRL publications



More Wire Antenna Classics Volume 2

More Wire Antenna Classics

Volume 2

Compiled by Chuck Hutchinson, K8CH

Production:
Paul Lappen

Cover Design:
Sue Fagan

Published by:
ARRL *The national association for AMATEUR RADIO*
225 Main Street
Newington, CT 06111-1494

Contents

1 Dipoles

2 Off-Center-Fed Dipoles

3 Multiband Antennas

4 Loop Antennas

5 Collinear Antennas

6 Wire Beams

7 Vertically Polarized

8 Receiving Antennas

9 Miscellanea

CHAPTER ONE

DIPOLES

1-1 **An Inverted V for Field Day**
From June 1968 *QST*

1-4 **E-Z-Up Antenna for 75 and 40**
From October 1961 *QST*

1-6 **A Zip-Cord Special Antenna**
From May 1972 *QST* (Hints & Kinks)

1-7 **Zip-Cord Special Antennas–Do They Work?**
From March 1979 *QST*

1-9 **Piggyback Antenna for the Ten-Meter Band**
From April 1973 *QST* (Hints & Kinks)

1-10 **RFD-1 and RFD-2: Resonant Feed Line Dipoles**
From August 1991 *QST*

1-14 **Off-Center-Loaded Dipole Antennas**
From September 1974 *QST*

1-20 **A Simple Broadband Dipole for 80 Meters**
From September 1993 *QST*

1-25 **Once More With the 80-Meter Broadband Dipole**
From June 1985 *QST* (Technical Correspondence)

1-26 **Fat Dipoles**
From *The ARRL Antenna Compendium, Vol 2*

By Frank Gue, VE3DPC, ex-VE6BH **From *QST*, June 1968**

An 80-Meter Inverted V for Field Day

It's that time of year again when portable operation is a delight. Here is a full-sized low-frequency antenna that you can put up in the field or at home without any help.

A Field Day antenna for 80 meters should be light, portable, inexpensive, capable of easy erection without any special equipment, and it should not contain any fragile parts.

Of course, the antenna must perform adequately.

The popular inverted V suggests itself as an answer to these requirements. It can be constructed so that it guys itself, minimizing the inevitable exasperating tangle of rope and wire, and it requires only one mast. Like all dipoles the inverted V can be fed at the center with low impedance line, and elements for several bands can be connected in parallel at the feed point of the antenna.

The inverted V shown in the photographs and sketches is simple, easily managed (20 minutes to erect, 10 minutes to dismantle), and costs under $15 for all components. Not only is it a convenient antenna for portable operation, but it can serve as a fine permanent antenna for the home station as well. In fact, that's what has happened to the inverted V pictured; it's been in use in the back yard of VE3DPC ever since Field Day, 1967.

Assembly

As shown in Figure 1, the antenna support consists of three 10-foot sections of 1¼-inch TV mast. One end of each of the two lower sections is swaged, permitting all three sections to be force-fitted together. Hooks of music wire were installed in the top section, so that the element wire and feed line could be easily coiled for storage.

The center insulator (Figure 2) is made of maple; however, if this wood cannot be found, birch or fir can be used instead.

Figure 2 shows how the center insulator was drilled and Figure 3 shows how the feed line and antenna element were attached. Dimensions are obviously not critical, and the sketches are intended to show in a general way how the insulator was made, not to give precise detail. Just be careful where you drive the screws!



The inverted V as it looked this past winter in the author's backyard.



Upper portion of the 80-meter inverted V as it appeared at the Field Day site.

Softwood (pine) was picked for the end insulators (Figure 4) because it is adequate for the application and easier to work with than maple. Fragile ceramics should not be used in place of the wood insulators.

The 80-meter element (Figures 3 and 5) is made from small-gauge, Teflon-insulated, stranded Copperweld that was bought at a surplus outfit. This wire is worth looking for; it's tough, durable, light, and easy to handle. If operation on both 80 and 40 is desired, the builder can connect a 40 meter element to points A and B in Figure 3.[1]

The feed line can be 50-ohm coax, 72-ohm coax or 72-ohm Twin-Lead. I chose the latter because it is low cost, lightweight, very flexible, easy to store, and because it lends itself to such outrageous techniques as being tied in knots; however, since most transmitters have coax output, either a balun or an antenna coupler must be used between the feed line and the transmitter to maintain balance.[2] If elements for more than one band are to be used, the antenna coupler is preferred because it will reject harmonics of the transmitting frequency that might fall in the range of one or more of the paralleled antennas.

Raising and Lowering

Transporting the antenna to and from the Field Day site is easy. Tape the three mast sections together, wrap them with cloth to protect the car's finish, and tie the works between one of the door handles and the rear bumper. If the antenna extends past the back of the car, don't forget to tie a red flag on the end of the bundle to alert other drivers.

Upon arrival at the Field Day site, unpack the antenna and join the TV masts together. The three-section support is light enough to be "walked up" by one man, if the wind is under 10 miles per hour; however, prior to the antenna raising, you must put stakes into the ground, determine the


5/32 Music Wire Hooks
for Stowing Wire
Center
Insulator
10' of 1-1/4" O.D. Mast
20' (two 10' Lengths of
1-1/4"O.D. Mast (swaged)

Figure 1—The makings of the inverted-V center support.


7/64" Drill for 72 Ω Twin-lead.
Countersink both ends.
Two no. 8×1" brass round head
wood screws driven part way –
for feed and antenna element
electrical connections.
Approx.
18°
Shaved to a taper for
heavy drive fit into top of
TV mast
Drill and countersink
two holes, diameter
to suit wire used for
antenna.
Take care when drilling
and driving screws that all
components miss each
other.
2" or more*
4" or more*
Center Insulator
MATERIAL: Dry Hardwood dowel,
1-1/4" Dia.
FINISH: Boil in paraffin or apply
thinned exterior paint before
and after assembly
* More if 40-meter elements
are to be accommodated also.
Not to Scale.

Figure 2—An X-ray view of the center insulator.


Knot in 72 Ω
Twin-lead
Solder to Point "B"
Knot in
Antenna
Element
"A"
"B"
To Feed Line
Anchor Point
Solder to
Point "A"
To Antenna Element
Anchor Point
To Antenna
Element
Anchor Point
Center
Insulator
Feed
Top View of
Center Insulator in Installed
Antenna System
15° min
15° min
Antenna
Element
Antenna
Element

Figure 3—Details of how the feed line and element wires should be attached to the center insulator, and a top view of the installed insulator.


Drill to suit antenna
wire and countersink
both ends.
45°
Drill to suit small diameter rope
(polypropylene or similar) and
countersink both ends
Antenna End Insulators
MATERIAL: 1×1 Pine
FINISH: Boil in paraffin
or apply thinned out
door paint
4"

Figure 4—A sketch of one of the wooden end insulators. Two insulators are required for each dipole used.



Figure 5—By using the dimensions and layout shown in the upper right corner of the sketch—so that ground stakes could be installed and proper length guys attached between them and the mast—the author was able to raise his 80-meter inverted V without any help. For other element lengths than shown, one man can easily put up the antenna by using simple geometry to determine the amount of rope required and the locations of the stakes.



A sideview of one of the wooden end insulators.

exact length the guys will be when the antenna is in its operating position, and attach the guys to the stakes (Figure 5).

If help is available, it won't be necessary to install stakes or measure guys prior to putting up the antenna. Have the helpers pay out each half of the antenna element and keep slack out of the wire as the mast goes up. Station the men about 45 degrees off the line of the mast as it lies on the ground, and then, once the mast is up, have the helpers walk around to the final positions shown in Figure 5. The last few degrees of "walking up" is where your control is poorest.

With the rear guy (feed line) in your hand, move quickly and smoothly past top dead center and promptly and firmly apply back tension on the antenna element. Once the feed line is snubbed, you can easily correct the mast for lean by lifting the base and putting it where it suits you. If you are fortunate enough to have three helpers, there is no problem at all. Give the third man the feed line, station him as far away as possible from the mast and antenna element, and have him take up the slack as the mast goes up.

Base support can be little or nothing. The mast, which is now permanently erected in my back yard, rests directly on the grass. It was moved a couple of inches during each mowing operation, and no apparent harm came to the lawn.

Lowering the antenna is brutal but quick. Release the back guy (feed line) and let the whole system fall. If the ground is reasonably flat, this will be OK. But if the ground is very rough, the pipe may take a set as it strikes the ground. Under such conditions, it would be better to use helpers to reverse the erecting procedure.

The antenna has been left up for a period of several months, during which there have been many autumn storms and a severe ice storm. It has shown no signs of distress, and it has performed normally when wet or loaded with ice. The small size of the inverted V's parts has led to little wind and ice loading and is probably the main reason for the antenna's durability.

[1] Although dimensions for an 80-meter inverted V are given in Figure 5, these aren't necessarily the optimum dimensions for every installation: there are too many variables involved. If the antenna is not to be used with a transmatch and open-wire line, it is best to experimentally determine the length of the inverted V. This can be done by starting with an overall length equal to about 525 divided by the frequency in megahertz. The ends of the inverted V should then be trimmed until the SWR is minimum at the operating frequency. A simpler method is described in footnote 2.

[2] An easier arrangement, especially for multiband operation, can be achieved by using a transmatch and either 300-ohm Twin-Lead or 450-ohm Ladder-Line. Only one dipole—about 100 feet long (length not critical)—is all that is necessary to cover all the amateur bands between 3.5 and 30 MHz.

By John C. Allred, W5LST

From *QST*, October 1961

E-Z-UP Antenna for 75 and 40

Full-size dipoles for the 75- and 40-meter bands occupy more space than is conveniently available on the 75 by 113-foot lot at W5LST. The increasing popularity of the "drooping," or inverted-vee, dipole antenna among amateurs led us to investigate it for our somewhat crowded conditions. Based on the electrical design of Glanzer,[1] this system has performed meritoriously at W5LST. Requiring only one support, it was surprisingly easy to erect, gives a satisfactory s.w.r. over the phone bands and, importantly, the cost was less than thirty dollars complete. A plan-view sketch is shown in Figure 1.

The Mast

The mast is a telescoping Channel-master, capable of 50-foot height, but extended only to 35 feet. Extending the upper sections to less than their full lengths gives rigidity to the mast, and has apparently eliminated the need for guys on each section, as recommended by the manufacturer. To date this mast has withstood gusts of 50 miles per hour without a shudder; it is yet to be tested in a real gale, however.

As shown in Figure 2, a 9-foot length of 3-inch pipe is cast in concrete with 6 feet of its length extending above ground. Three pairs of clamps, such as those used on chain-link fence, secure the mast to the upright standard. During erection, these clamps are loosened and all three lie at the base of the standard, so that the mast need only be lifted about 6 inches to be put in place. When the mast is in place, the clamps are raised and tightened.



Figure 1—W5LST's layout for effective 40- and 80-meter antennas on a small lot. The two "drooping" dipoles are fed in parallel with a single coax line. Nylon-line extensions are used to reach convenient anchorages.



Figure 2—The mounting for the antenna mast. The 9-foot pipe is guyed temporarily while the concrete is poured.

Rigging

Except for the antenna conductors, all rigging is of nylon line of 500-pound test. A halyard is reeved through a pulley of suitable size which is wired securely to the top of the mast. The two ends of the halyard are made fast to a harness snap which, in turn, supports the center of the antennas. Provision of this halyard has proved to be a great convenience in permitting inspection of the antenna connections and the adjustment of tension in the wires without the necessity for lowering the mast.

Nylon line has a tendency to ravel at its ends but this problem is easily solved. Most fastenings were made with two halfhitches, followed by sewing the end of the line to itself with thread, as shown in Figure 3A, and doping with one of the quick-drying model-airplane cements.

Some weeks after the initial installation, it became apparent that some additional stabilization of the mast against occasional strong northerly winds would be desirable. Accordingly a nylon line was run from the harness snap at the top of the mast to a convenient anchor in the back yard, which happened to be the top of the children's swing set. Experience seems to show that the antenna wires, together with the additional nylon line, stabilize the mast against aerodynamically-excited vibration, without any appreciable strain on the antennas.

The Antennas

As shown in Figure 3, the two antennas are connected in parallel at the top of the mast. The lower ends are connected to convenient tie points so that the two legs of a given antenna are more or less in a straight line. To our great surprise, very little effect is produced by moving the ends of the an-

---

[1] Glanzer, "The Inverted V-Shaped Dipole," *QST*, August, 1960.



Figure 3—The halyard and feeder arrangement. The coaxial cable is sealed securely with polyethylene tape after the connections are made. The harness snap of A at the end of the hoisting halyard engages the bridle between the two insulators in B.



Figure 4—SWR curves as indicated by a "Monimatch"-type SWR indicator.

tennas either horizontally or vertically. There is apparently negligible electrical interaction between them as indicated by the s.w.r. bridge.

Pruning of the antennas is, as always, desirable. In our case, the optimum lengths of each leg turned out to be 33 feet 9 inches for 40 meters and 59 feet 6 inches for 75 meters. Figure 4 shows the performance of the antennas on 40 and 75 as measured by a Heath s.w.r. bridge. Although the antennas tune sharply, they are usable over the entire phone band in each case, and it would be difficult to imagine a better performer on the lower-frequency bands than this simple antenna system.

From *QST*, May 1972 (Hints & Kinks)

A Zip-Cord Special Antenna

Recently I found myself in need of an 80-meter antenna to help me keep in touch with some of my friends back home while operating portable in Arizona. The antenna and feed line were not readily available, but I remembered that one of my friends had recommended zipcord as a substitute feed line for a dipole, provided low power was used. Going one step further, I felt the entire antenna could be made of this low-priced material. I purchased 80 feet of zip cord at a local hardware store (at 4 cents a foot) and peeled it apart for 60 feet. This gave me the required 120 feet for a dipole, plus a 20-foot feed line which was taped to prevent further splitting. The feeder was fastened to a 2×4 which was used as a center support. The ends were extended as far as possible, then tied with heavy cord to a fence that was in the trailer park where I was staying. This made a slight inverted-V antenna.

To reach the desired frequency of 3935 kHz it was necessary to shorten the antenna somewhat. I did this by folding three feet on each end of the dipole back upon itself. This enabled me to keep skeds with many "7s" at home.

Having met with success on 80-meters I immediately began to eye the 40-meter band for possible use. I then measured out 32 feet from the center and cut the wire there, then tied a knot in the two pieces, leaving a couple of inches of bare wire dangling. Now for forty meters, I merely disconnect the wires and reconnect them for 80 meters.

As the *ARRL Antenna Book* states, a 40-meter dipole will often present a good match at 15-meters, and this one is no exception; I have worked many stations across the country on 15 meters with low power while using this simple antenna.

The *Handbook* or *Antenna Book* has not recommended this type of feed line in many years, though using a twisted pair at one time was usual practice in feeding a doublet. But, when the need is there for a quick and easy antenna, I don't think you can find an easier one as long as you remember to use low-power transmitters (100 watts or less) and trim the wire for a low value of SWR. — *Frank S. Wise, W7QYC*

By Jerry Hall, K1TD **From *QST*, March 1979**

Zip-Cord Antennas—Do They Work?

Basic Amateur Radio: Parallel power cord is readily available and is easy to work with. How efficient is it when used at radio frequencies? Well, that depends.

Zip cord is readily available at hardware and department stores, and it's not expensive. The nickname, zip cord, refers to that parallel-wire electrical cord with brown or white insulation used for lamps and many small appliances. The current price is about 6 cents a foot in hundred-foot rolls in most parts of the U.S. The conductors are usually no. 18 stranded copper wire, although larger sizes may also be found. Zip cord is light in weight and easy to work with.

For these reasons, zip cord is frequently used as both the transmission line and the radiator section for an emergency dipole antenna system. The radiator section is obtained simply by "unzipping" or pulling the two conductors apart for the length needed to establish resonance for the operating frequency band. The initial dipole length can be determined from the equation $\ell = 468/f$, where ℓ is the length in feet and f is the frequency in megahertz. (It would be necessary to unzip only half the length found from the formula, since each of the two wires becomes half of the dipole.) The insulation left on the wire will have some loading effect, so a bit of length trimming may be needed for exact resonance at the desired frequency.

For installation, many amateurs like to use the electrician's knot shown in Figure 1 at the dipole feed point to keep the transmission-line part of the system from unzipping itself under the tension of dipole suspension. This way, if zip cord of sufficient length for both the radiator and the feed line is obtained, a solder-free installation can be made right down to the input end of the line. Granny knots (or any other variety) can be used at the ends with cotton cord to suspend the system. You end up with a lightweight low-cost antenna system that can serve for portable or emergency use.

But just how efficient is a zip-cord antenna system? Since it is easy to locate the materials and simple to install, how about using such for a more permanent installation? Upon casual examination, zip cord looks about like high-quality 72-ohm balanced feed line. Does it work as well? Ask several amateurs these questions and you're likely to get answers ranging all the way from, "Yes, it's a very good antenna system!" to "Don't waste your time and money – it's not worth it!" Myths and hearsay seem to prevail, with little factual data. The intent of this article is to rectify that situation.

Zip Cord as a Transmission Line

In order to determine the electrical characteristics of zip cord as a radiofrequency transmission line, we purchased a 100-foot roll and subjected it to tests in the ARRL laboratory with an rf impedance bridge. Zip cord is properly called parallel power cord. The variety purchased was manufactured for GC Electronics, Rockford, IL, being 18-gauge, brown, plastic-insulated type SPT-1, GC cat. no. 14-118-2G42. Undoubtedly, minor variations in the electrical characteristics will occur among similar cords from different manufacturers, but the results presented here are probably typical.

As the first step, we checked the physical length of the wire. GC generously provided nearly 4 feet over the specified 100-ft length, and the extra length was promptly lopped off.

We wanted to avoid measurement errors that might arise from coiling the wire on the supply spool (inductance between turns) or laying it out on the vinyl-tiled cement-slab floor (capacitance to a large surface), so the second step was to suspend the wire in a long hallway, about a foot or so below the false ceiling. Cotton twine was used for the supporting material. Undaunted by snide comments from fellow staff members about cheating the telephone company out of installation work and facetious suggestions


Dipole Section
See Text Regarding Length
Transmission – Line Section, Any Length
to Transmitter

Figure 1—This electrician's knot, often used inside lamp bases and appliances in lieu of a plastic grip, can also serve to prevent the transmission-line section of a zip-cord antenna from unzipping itself under the tension of dipole suspension. To tie the knot, first use the right-hand conductor to form a loop, passing the wire behind the unseparated zip cord and off to the left. Then pass the left-hand wire of the pair behind the wire extending off to the left, in front of the unseparated pair, and thread it through the loop already formed. Adjust the knot for symmetry while pulling on the two dipole wires.

that we use two paper cups and a string for our intercom, we continued with preparation for the tests.

With a General Radio 1606A rf impedance-measuring bridge, we made measurements at the input end of the line on 10, 15 and 29 MHz, while the far end of the line was terminated first in a short and then in an open circuit. We did notice during measurements that our readings changed somewhat as people walked in the hallway, especially during the 29-MHz tests. After a seemingly endless period of shooing away would-be helpers who disrupted measurements by grabbing the line, hanging objects on it, and so forth, we finally arrived at a set of readings considered to be satisfactory for our purposes. From there, a bit of work with an electronic calculator and a Smith Chart told us what we wanted to know — the electrical characteristics at radio frequencies.

The results? Well, as the saying goes, I have some good news and some bad news.



Figure 2—Attenuation of zip cord in decibels per hundred feet when used as a transmission line at radio frequencies. Measurements were made only at the three frequencies where plot points are shown, but the curve has been extrapolated to cover all high-frequency amateur bands.

First, the Good News

If ever you need a balanced 105-ohm transmission line, then zip cord is the stuff for you! Its characteristic impedance was determined to be 107 ohms at 10 MHz, dropping in value to 105 ohms at 15 MHz and to a slightly lower value at 29 MHz. The nominal value is 105 ohms at hf. The velocity factor of the line was determined to be 69.5 percent.

This reported change in impedance with frequency may raise a few eyebrows, but it is a fact that most lines do not exhibit a constant characteristic impedance across a range of frequencies. However, this writer has not previously encountered any line which was not "flat" between 3 and about 50 MHz. Zip cord may be exceptional from this standpoint, especially considering that the insulating material was not chosen for its qualities at rf.

And Now the Bad News

Who needs a 105-ohm line, especially to feed a dipole? Most of us know that a dipole in free space exhibits a feed-point resistance of 73 ohms, and at heights above ground of less than 1/4 wavelength the resistance is even lower. An 80-meter dipole at 35 feet, for example, will exhibit a feed-point resistance of about 40 ohms. Thus, for a resonant antenna, the SWR in the zip-cord transmission line can be 105/40 or 2.6:1, and maybe even higher in some installations. Depending on the type of transmitter in use, the rig may not like working into the load presented by the zip-cord antenna system.

But the really bad news is still to come–line loss! Figure 2 is a plot of line attenuation in decibels per hundred feet of line versus frequency. Chart values are based on the assumption that the line is perfectly matched (sees a 105-ohm load as its terminating impedance). For lengths other than 100 feet, multiply the figure by the actual length in feet and then divide by 100.

In a feed-line, losses up to about one decibel or so can be tolerated, because at the receiver a 1-dB difference in signal strength is just barely detectable. But for losses above about 1-dB, beware. Remember that if the total losses are 3 dB, half of your power will be used up just to heat the transmission line.[1]

Based on this information, we can see that a hundred feet or so of zip-cord transmission line on 80 meters might be acceptable, as might 50 feet on 40 meters. But for longer lengths and higher frequencies, look out! The losses become appreciable.

What About Zip Cord Wire as the Radiator?

For years, amateurs have been using ordinary copper house wire as the radiator section of an antenna, erecting it without bothering to strip the plastic insulation. Other than the loading effects of the insulation mentioned earlier, no noticeable change in performance has been noted with the insulation present. And the insulation does offer a measure of protection against the weather. These same statements can be applied to single conductors of zip cord.

The situation in a radiating wire covered with insulation is not quite the same as in two parallel conductors, where there may be a leaky dielectric path between the two conductors. In the parallel line, it is this current leakage which contributes to line losses. The current flowing through the insulation on a single radiating wire is quite small by comparison, and so as a radiator the efficiency is high.

Now back to the original question: How efficient *is* a zip-cord antenna system? Well, that *does* depend, on the length of the wire used for the feed-line section and on the frequency. In a pinch on 160, 80, 40 and perhaps 20 meters, communications can certainly be established with this kind of antenna. For higher frequencies, especially with long line lengths for the feeder, you're on your own.

---

[1] Additional losses over those charted in Figure 2 will occur when standing waves are present. See Gibilisco, "What Does Your SWR Cost You?" January 1979 *QST*. Trouble is, you can't use a 50- or 75-ohm SWR instrument to measure the SWR in zip-cord line accucately.

From *QST*, April 1973 (Hints & Kinks)

Piggyback Antenna For The Ten-Meter Band

Most amateurs from Novices on up use dipole antennas for the eighty- and forty-meter bands. In many cases, these two antennas were all the Novice needed since the fifteen-meter band could also be covered with the forty-meter dipole.

However, with the advent of the new ten-meter subband for Novices, a simple and inexpensive method of getting the needed coverage is to use a "piggyback" antenna. It can be easily added to an existing dipole, eliminating the need for additional supports or feed lines. Also, it will have no effect on either an eighty- or forty-meter dipole.

Of course, performance will not be as good as that obtained with a beam, but it should not be sold short either. A KH6 was worked during a recent contest with a power output of 1.8 watts. — *Robert M. May, II, WA4DEG*



Existing Dipole
Center Insulator
Insulator *
Twisted Wire
Soft Copper Wire
1/2 λ
$= \frac{468}{f(MHz)}$
* Should be Long Enough to Prevent Tangling
Existing Feed Line

By James E. Taylor, W2OZH **From *QST*, August 1991**

RFD-1 and RFD-2: Resonant Feed-Line Dipoles

This unique design offers simplicity and general utility. In short, these are "reel" great antennas for the HF bands.

During several decades of operation on the 80-meter band, I have encountered a number of hams who need an antenna system that is efficient, simple to construct, and yet can be deployed easily in difficult locations. The resonant feed-line dipoles described here provide an excellent match to the transceiver without a separate antenna tuner. They are easily transported on plastic cord reels. The basic design is extensible to other bands—all of this without a dangling feed line to contend with!

Consider some realistic situations encountered by fellow hams in their efforts to get on 80 meters:

Scenario 1: You live on a small suburban lot with trees, but there is no way to stretch a straight 120-foot-long dipole with a feed line.

Scenario 2: Your small backyard ends at the edge of a steep decline. A radiator wire could be snaked through the trees, but running a separate feed line is out of the question.

Scenario 3: You live in a high-rise building and could secretly stretch a wire upward or downward, but there is no way to install a feed line.

Scenario 4: You're going on vacation to the mountains and you know that your cottage is nestled among hundred-foot-high pines You can take along a bow and arrow and cord, but then what would you do?

In response to these problems, I began to search for a universal solution under the following ground rules. (1) No separate antenna tuner would be required, (2) the antenna could be deployed with no more difficulty than stringing up a length of coax and (3) the antenna could be easily stored and unwound from a cord reel without a tangle of cable and wire.

Several years ago I used a 10-meter vertical linear coaxial sleeve antenna, as shown in Figure 1. A vertical dipole is constructed from a quarter-wave whip and a quarter wavelength of shielding braid. Its feed line passes through the braid, yielding a simplified geometry. Although this concept could be adapted to 80 meters, who wants to deal with 60 feet of shielding braid? The important lesson I learned was that the RF current has no trouble traveling up the inside of the coax and making a 180° turn to travel back on the outside of the braid!

Because this is true, perhaps we don't need the separate outer braid. Why not just use the outside of the coax itself? If we do this, however, how do we let the RF "know" when it should stop flowing and reflect back toward the center of the radiator, as it did when it came to the end of the added braid in the 10-meter vertical? The current on the outside of the coax shield is called "common-mode" current—there is no counteracting equal and opposite current as there is inside the coax. One design approach utilizes the primary function of a balun transformer: to place in unbalanced reactance in the path of this common-mode current without affecting the desired balanced transmission line currents. The development of this concept is discussed in the Appendix.

The common-mode current on the coax shield is transformed by a quarter-wavelength stub to maximum near the transceiver. It was not surprising to note experimentally that a coil of a few turns placed at the fed end of the dipole decreases the resonant frequency of the system substantially (because of the added inductive reactance). However, an unexpected dividend of this is that, at the resonant frequency, an almost perfect impedance match to the 50-ohm source is realized! Now we have the design for our simplified antenna system! We can increase the resonant frequency by moving the coil along the cable away from the current maximum while retaining the perfect match. And at the same time we can decrease the common-mode current on this part of the line, because of the coil's inductive reactance. For the values chosen, the coil is near self-resonance from the distributed capacitance of the coil windings. The equivalent parallel-resonant circuit serves to increase the reactance at this point in the antenna, which assures a reflection when the RF reaches this virtual end of the dipole. To my knowledge, this configuration and method of resonating is unique and novel, and I refer to it as a T choke.

Constructon, Installation and Adjustment

The simple arrangement of the resonant coaxial linear dipole is shown in Figure 2. The dimensions and test results are for a nominal



Figure 1—A vertical linear coaxial sleeve antenna for 10 meters.

frequency of 3.95 MHz. To dramatize the simplicity of the antenna, I list all required parts in Table 1.

The coaxial cable connector is assembled at the input end of the coax for connecting to the transceiver. The center conductor of the far end of the cable is connected to the antenna wire to form a hook and eye, and is securely soldered. This junction is potted in the center of a short length of PVC pipe to form a robust center insulator assembly. At the outset, 13 turns of cable can be wound on the cord reel at a point approximately 59 feet plus 25 inches from the center of the dipole. The 13 turns can then be taped in place on the reel with duct tape or equivalent. The remaining coax and wire can now be wound on the reel for ease of transporting. To avoid kinks when unwinding, secure the end of the wire and rotate the reel, keeping the wire and coax taut.

Ground losses are a great enemy of an HF antenna, especially at the lower frequencies, so place the dipole for 80 meters as far above the ground as possible! After installation, check the resonant frequency with a noise bridge or an SWR meter. If these construction details are followed, the resonant frequency should be approximately 3.95 MHz. If the resonance indication is indefinite or if the resistance is not close to 50 ohms, adjust the self-resonance of the coil by moving the turns slightly on the reel. This alters the inter-turn capacitance, permitting adjustment of the reflection of RF at the end of the dipole. During this adjustment, remember that the greatest effect is between the input and output turns, where the voltage difference is greatest. If you want to lower the resonant frequency of the antenna, remove the tape and rotate the reel to increase the 25-inch distance, thereby increasing the length of the dipole. This is done in a manner to retain the 13-turn coil—you are winding and unwinding equal lengths of cable. When the desired resonant frequency is attained, you are ready to operate! This is a broadband antenna, and not much adjustment is required.

The 13 turns is mentioned only as a nominal coil size. I have used both 11-turn and 13-turn coils. Self-resonance can be adjusted as mentioned earlier. As the number of turns is increased, the initial 25-inch distance will be decreased. For example, in my test installation a change from 11 turns to 13 turns altered this distance required for resonance from 68 inches to 25 inches. A greater impedance at this point serves to improve the isolation of the dipole from ground.

The RFD-2 for Two-Band Operation

The preceding construction information is for an antenna dedicated to a single amateur band, the RFD-1. With a slightly different configuration, referred to as the RFD-2, the RFD-1 design can be extended to cover the 40-meter band without severing the coaxial cable. Conversion from 80 to 40 meters and back requires only a few minutes. The RFD-2 design allows you to change operation to 40 meters for a few days without permanently altering the 80-meter lengths. In other words, the total dimensions of the 80-meter coaxial feed-line dipole are retained but operation is adapted to 40 meters. Tbis is done simply by winding coaxial cable on reels. This is readily achieved by altering the winding of the coax on the original reel and then adding a second coil near the far end of the dipole. Once the values have been established, this band change is accomplished simply.

The RFD-2, as it has evolved at W2OZH, is shown in Figure 3. Total dimensions are given in Figure 3A. The length of the feed line has been increased from that of the RFD-1 to 143 feet to make allowance for the cable used in the 13-turn coil. This assures an isolating stub which is approximately 1/4 λ on 80 meters, and at the same time permits a stub length that is close to 1/4 λ on 40 meters, thereby achieving the desired high impedance for isolation on both bands. Also, the no. 12 terminating antenna wire has been replaced by a length of coaxial cable—the outer jacket provides insulation so the coax can now be coiled to provide the desired dipole length on 40 meters.

Table 1
RFD-1 Parts List

1–118-foot length RG-8X (minifoam) coaxial cable
1–59-foot length no. 12 stranded or Copperweld wire
1–PL-259 male coaxial cable connector
1–10-inch-diameter cord reel (Doscocil model no. 32500 or equiv.)
1–3-inch length of 1/2-inch OD PVC pipe (for center insulator)
1–Epoxy potting compound (sufficient to fill pipe)

As pointed out earlier, a self-resonant coil is used to assure a high coefficient of reflection at the fed end of the 80-meter dipole. For other bands it is necessary to calculate the approximate number of turns required to approach self-resonance. A suitable winding for 80 meters was determined to be 13 turns on a 6-inch diameter reel, so the numbers for other bands can be obtained by a simple scaling calculation. Details are given in the Appendix. For guidance in adapting the design for the other HF bands, the approximate number of turns for the terminating coils is shown in Table 2.

For wavelengths shorter than 40 meters it may be desirable to use a radiating section longer then 1/2 λ. The length either side of center can be any odd number of quarter wavelengths. For example, on 20 meters the radiator could be 3/2 λ (three



Figure 2—The RFD-1 (resonant feed-line dipole) antenna for 80 meters.


T Choke
Coaxial Cable
Coiled on Cord Reel
13 Turns, 6" Diam
(approx. 22')
RG-8 or Mini-8
Coaxial Cable
(Note That Only the
Shield is Connected)
1/2 λ RG-8 or Mini-8
Coaxial Cable
(approx. 143')
to
Station
1/4 λ (approx. 62')
1/4 λ (approx. 59')
1/4 λ (approx. 59')
Center of Dipole
(potted in Epoxy)
(A)
T Choke
Coaxial Cable
Coiled on Cord Reel
9 Turns, 6" Diam
(approx. 15')
RG-8/U or Mini-8
Coaxial Cable
(Note That Only the
Shield is Connected)
T Choke
Coaxial Cable Coil
9 Turns, 6" Diam
RG-8 or Mini-8
Coaxial Cable
(approx. 143')
to
Station
3/4 λ (approx. 95')
1/4 λ
(approx. 32'-2 1/2")
1/4 λ
(approx. 32'-2 1/2")
Center of Dipole
(potted in Epoxy)
Distance Adjusted
for Resonance
(approx. 14")
(B)

Figure 3—The RFD-2 antenna can be configured for either of two bands. Shown at A is the setup for 80 meters, and at B for 40 meters.

quarter waves either side of center). Depending upon the antenna orientation, the additional radiation lobes may be advantageous. Also, the unused conductor lengths at the ends are less apt to cause trouble because of parasitic excitation from the main radiator.

Arrangement and Construction

From Table 2, for the 40-meter band we need to reduce the resonant coil at the input end of the dipole to nine turns, and we need to move the coil along the coax to a point slightly more than 32 feet, $2^3/_4$ inches from the center. This is half the dipole length calculated for 7.26 MHz with an allowance for tuning adjustment, using the dipole-length approximation equation $L = 468/f_{MHz}$. As with the RFD-1, this coil establishes the desired, high impedance at the fed end of the dipole.

In addition, we need to establish a high impedance at the far end of the dipole because, in this case, the desired end of the 40-meter dipole does not coincide with the end of the conductor. This is because we want to retain the full length of the conductor measured for the 80-meter band, rather than cutting it. The desired high impedance reflecting termination is achieved by use of a second, 9-turn, self-resonant coil of coax.

Table 2
Scaling of RFD-1 to Other Bands

Band	*Frequency*	*Turns*
160 m	1.90	19
80 m	3.95	13
40 m	7.26	9
30 m	10.12	8
20 m	14.29	7
17 m	18.14	6
15 m	21.38	6
12 m	24.96	5
10 m	28.65	5

Figure 3B shows the RFD-2 configuration for 40 meters. A cord reel can be used for the second coil, although any suitable insulating 6-inch diameter form can be used. I wound the coil in two layers using a 1-gallon windshield-washer-fluid bottle. After the windings had been properly adjusted, I taped them in place with duct tape, and slipped the coil off the form so it became self-supporting.

As with the RFD-1, it is desirable to place the antenna as high above ground as possible to reduce ground losses and to belp achieve low-angle radiation, if that is desired. The dipole does not have to be installed in a straight line, and if you can gain appreciably greater height by bending it, this may be a desirable compromise.

After the antenna with its two coils is erected, measure the resonant frequency using a noise bridge or an SWR meter. If the construction details have been followed, the resonant frequency should not be far from the nominal value of 7.26 MHz. The resonance point and the input resistance can be shifted moderately by both changing the 14-inch offset distance and changing the inter-turn spacing of the coils. The greatest effect is produced by changing the spacing between the input and the output turns (that is, between coil turns 1 and 9). This is because the voltage difference, and therefore the change in capacitive influence, is greatest there.

Results

My experience in developing antennas is that the good concepts really "want to work," and this antenna was no exception. Noise-bridge measurements with the RFD-1 indicated an input resistance at resonance of

49 ohms, and from a practical standpoint the SWR is 1:1. An H-field antenna probe was used to evaluate the power radiated at the center of the dipole compared with that at the current loop near the feed-point. The current ratio was 5.5 to 1, which corresponds to a power ratio of 30 to 1, or 15 decibels. This indicates that the coil is very effective in attenuating the common-mode current flowing back toward the feed point.

For the RFD-2 with the 40-meter dimensions shown in Figure 3B, the initial resonance point was within the 40-meter phone band and the SWR was essentially 1:1. Slight adjustment brought the resonant frequency up to the desired value, and the input resistance was very close to 50 ohms. A salient characteristic of the RFD antennas is the ease with which an impedance match is attained. It appears always to be easy to get a reflected power indication of zero. This is probably because the common-mode current on the shield of the coax is indistinguishable from the desired radiating current—in other words, the common mode is used rather than avoided.

Appendix

When the separate outer braid of the antenna shown in Figure 1 is removed, there must be some way to let the RF "know" when it should stop flowing on the shield of the coax and reflect back toward the center of the radiator. A balun box that I made up for another purpose is one approach: 30 turns of bifilar winding on an Amidon T-200-2 iron-powder toroidal core. The turns formula for such a balun transformer is

$$T=\sqrt{\frac{\text{desired}\,L(\mu H)}{A_L}}$$

where

T = no. of turns

A_L = inductance index (microhenries per 100 turns)

From this, the inductive reactance for unbalanced current is

$$X_L=2\pi fL=\frac{2\pi fT^2A_L}{10^4}$$

At a frequency of 4 MHz, this 30-turn coil has an unbalanced reactance of only 270 ohms. We would need about ten of these in series to support the RF field at the end of a dipole antenna!

An alternative method involves placing a toroidal isolation transformer in the coaxial line at the fed end of the linear dipole. I actually wound such a transformer on two stacked T-200-2 cores, to provide a 1-kW power capability. This configuration worked, after a fashion, but the impedance match was less than desired, probably because of excessive capacitance between secondary and primary windings. However, before I took steps to control this, a simpler approach came to mind.

We need to isolate the transceiver from the fed end of the dipole, so why not cut the coaxial feed line to be a quarter wavelength long? (This length is measured in free-space, not in the line.) This serves to tranform the high impedance of the fed end of the dipole to the low impedance at the grounded transceiver. Any unused portion of this approximate 60-foot length of coax can be wound in a coil and used for further isolation and, as it turns out, for tuning the system to resonance.

Scaling for a Second Band

For coverage of a second band, we would like to have the same inductive reactance that we had for the 80-meter coil.

From handbooks, the inductance of a coil of assumed dimensions is

$$L = AN^2$$

where

A = a constant determined by the coil geometry

N = number of turns

Thus, we have for the reactance

$$X_L = 2\pi fL = 2\pi fAN^2$$

For equal reactances we can calculate N_2, the new number of turns, at frequency f_2, from N_1, the known number of turns at frequency f_1, by the equation

$$N_2=N_1\sqrt{\frac{f_1}{f_2}}$$

By Jerry Hall, K1PLP **From *QST*, September 1974**

Off-Center-Loaded Dipole Antennas

In these times when much of our amateur population lives in urban areas, the subject of shortened antennas for the lower frequency amateur bands is a very popular one. Physically short ground-mounted vertical antennas with lumped-constant loading to make them resonant can be quite efficient radiators, if a good radial system has been installed. This has certainly been evidenced in Sevick's series of recent *QST* articles.[1] To many amateurs, however, the "hitch" in constructing such a system is the installation of a *good* radial system. It must be admitted that for the "top" amateur bands, 160 and 80/75 meters, an efficient system of buried radials requires a sizable amount of real estate, even for a physically short radiator. On the average city-size lot, 50 or 75 by 120 to 150 feet, it's almost impossible to install a highly efficient radial system for 80/75 meters, much less for 160 meters, when structures like a house and perhaps a separate garage exist. Or to some amateurs, just the thought of burying hundreds or maybe thousands of feet of wire is enough to turn off any enthusiasm for the project. What's the alternative? A dipole type of antenna with lumped constant loading. At modest heights, 30 or 40 feet, such an antenna will prove to be quite satisfactory if it is physically longer than about 0.2 wavelength. Shorter lengths may also be used, at reduced efficiency. Such an antenna can be fed directly with 50-Ω coaxial line, and it can be operated with no earth ground. (Of course the chassis of the transmitter and/or receiver should be grounded adequately for protection against shock hazard.)

Nearly all of us are familiar with the concept behind the use of inductive loading. A vertical antenna which is shorter than a quarter wave (or a dipole antenna which is shorter than a half wave) will exhibit capacitive reactance at its base (or center) feed point. To cancel such capacitive reactance, a coil having the proper inductive reactance may be connected in series with the base feed point of the vertical. The same result will be obtained through the use of two such coils for a dipole, one coil connected in series with each half. It is not necessary for the inductor to be installed at the feed point, however. In fact, greater radiating efficiency results through improved current distribution if the inductor is located along the radiator some distance away from the low-impedance feed point, *viz*, in the manner of a center-loaded mobile whip antenna. Figure 1 shows this concept extended to a dipole element, with off-center loading. The inductors resonate the antenna to the operating frequency, but do little actual radiating themselves. (This is in contrast to helically wound or continuously loaded elements, where a long thin inductor is the radiator as well as the loading element.)

In the antenna represented by Figure 1, there are many variable factors to be considered when a practical antenna for a given frequency is being constructed. Of primary consideration from an efficiency standpoint is the overall length, shown as dimension A. Another consideration for efficiency is the distance of the coils from center, dimension B. The longer the overall length (A), up to a half wave, and the farther the loading coils are placed from the center (B), the greater is the efficiency of the antenna. However, the greater is distance B (for a fixed overall antenna size), the larger the inductors must be to maintain resonance. Theoretically, if the coils were placed at the outer ends of the dipole, they should be infinite in value to maintain resonance. Capacitive loading of the ends, either through proximity of the antenna to other objects or through the addition of capacitance hats, will reduce this requirement to a more practical value.

What Inductance Values?

As a matter of personal interest, this writer has been doing experimental work for a number of years with off-center-loaded antennas. One big drawback to such experimentation was the ever-present need for a large amount of cut-and-try work to arrive at resonance whenever a new set of dimensions was to be used. Probably the number of pruned-off turns from coil stock from such experiments, if straightened out and soldered end to end, would make up several full-sized half-wave antennas for the 160-meter band. Therefore, most of the writer's work of late in this area has been in going through paperwork exercises, looking for a way whereby at least "ball-park" values of inductance needed for a particular system could be calculated.

The equation contained in the Mobile chapter of *The ARRL Antenna Book* for determining the capacitance of a vertical antenna shorter than a quarter wavelength looked promising in early computations,



Figure 1—A dipole antenna lengthened electrically with off-center loading coils. For a fixed dimension A, greater efficiency will be realized with greater distance B, but as B is increased, L must be larger in value to maintain resonance.

and, indeed, it became the basis for the calculation procedure which finally resulted.

This procedure has been found to produce results much closer than mere "ball-park" values for the necessary inductance – for wire antennas "in the clear" at moderate heights, the final inductance values found by cut-and-try pruning for lowest SWR at the desired frequency have been so close to the value from calculations that a laboratory bridge was necessary to measure the difference. The results are equally good for elements using tubing. Once the needed inductance value is determined by calculations, it is generally found sufficient to obtain coil dimensions from an ARRL L/C/F Calculator (see LaPlaca*) or by equation. Any significant pruning which has been found necessary could always be attributed to objects in proximity to the ends of the antenna.

The complete set of calculations is expressed in the mathematical relationship below as Eq. 1, presented here primarily for mathematics buffs or those having access to electronic computers.

This equation yields the inductance required, in microhenrys, for single-band resonance of a shortened antenna of a particular physical size at a given frequency, for a specific position of the loading coils from the center of the antenna. To spare the reader the task of performing some rather tedious calculations, Figure 2 has been prepared from Eq. 1. The curves of the chart have been normalized, and may be used for any frequency of resonance. The chart is based on a halfwavelength/diameter ratio of the radiator of approximately 24,000. (This corresponds to No. 14 wire on 80 meters or No. 8 wire on 160 meters.) For "thinner" conductors, the required inductance will be somewhat greater than that determined from Figure 2, and less inductance will be required for "thicker" conductors.

The use of the chart is as follows: At the intersection of the appropriate curve from the body for dimension A and the proper value for the coil position from the horizontal scale at the bottom of the chart, read the required inductive reactance for resonance from the scale at the left. Dimensions A and B are shown in Figure 1, and for use with the chart are expressed as percentages. Dimension A is taken as percent length of the shortened antenna with respect to the length of a resonant half-wave dipole of the same conductor material. Dimension B is taken as the percent of coil distance from the feed point to the end of the shortened antenna. For example, resonating an antenna which is 50% or half the size of a half-wave dipole (one-quarter wavelength overall), with loading coils positioned midway between the feed point and each end (50% out), would require loading coils having an inductive reactance of approximately 950 ohms at the operating frequency. If the antenna is hung "in the clear," and if the length/diameter ratio of the conductor is near 24,000, inductance values as determined from the chart will be very close to actual values required. (Eq. 1 above takes the diameter of the radiator into account, and thus may be used for any length/diameter ratio.) For practical purposes, dimension B may be taken as that distance from the center of the feed-point insulator to the inside eye of the loading-coil insulator, and dimension A as the eye-to-eye distance inside the end insulators (which are not drawn in Figure 1).

Proximity of surrounding objects in individual installations may require some pruning of the coils, and the exact amount of final inductance required should be determined experimentally. If the antenna is hung in inverted-V style, with the ends brought near the earth, the required inductance will almost always be somewhat less than that determined from the chart or equation. A grid-dip meter, Macromatcher, (see Hall and Kaufmann*) or SWR indicator may be used, during the final adjustment procedure.



Figure 2—Chart for determining approximate inductance values for off-center-loaded dipoles. At the intersection of the appropriate curve from the body of the chart for dimension A and the proper value for the coil position from the horizontal scale at the bottom of the chart, read the required inductive reactance for resonance from the scale at left. See Figure 1 regarding dimensions A and B.

(Eq. 1):

$$L_{\mu H} = \frac{10^6}{68\pi^2 f^2}\left\{\frac{\left[ln\frac{24\left(\frac{234}{f}-B\right)}{D}-1\right]\left[\left(1-\frac{fB}{234}\right)^2-1\right]}{\frac{234}{f}-B}-\frac{\left[ln\frac{24\left(\frac{A}{2}-B\right)}{D}-1\right]\left[\left(\frac{\frac{fA}{2}-fB}{234}\right)^2-1\right]}{\frac{A}{2}-B}\right\}$$

where

$L_{\mu H}$ = inductance required for resonance

ln = natural log

f = frequency, megahertz

A = overall antenna length, feet

B = distance from center to each loading coil, feet

D = diameter of radiator, inches

Practical Antennas

Although one might erect an inductively loaded antenna that is cut for a single amateur band, it is possible to use the antenna itself for two, three, or more bands of operation, if provision is made to lower the antenna for band changes. A simple rope halyard and pulley arrangement at one of the supports will do the trick. Figure 3A shows a 3-band antenna of this nature, for 160, 80, and 20 meters. If the insulators shown are left open, with nothing bridging them, the antenna is a simple half-wave dipole cut for 14.18 MHz. (The 48.5-foot lengths act merely as support wires, and have negligible effect on operation of the antenna.) If the insulators are bridged with short lengths of antenna wire, the antenna becomes a center-fed 80-meter dipole, resonant at about 3.6 MHz. For 160-m operation the 20-meter insulators may be bridged with loading coils to resonate the antenna at 1.8 MHz, as shown in Figure 3A. Burndy or other manufacturers' "Servit" type of electrical connectors may be used, for ease in making band changes quickly, as shown in Figure 4.

The calculation procedure for determining loading-coil values for the antenna of Figure 3A, using the chart of Figure 2, goes like this. If operation is desired on 1.8 MHz, the length of a full-sized half-wave dipole is found from the relationship $468/f$ to be 260 feet. The 130-foot length of Figure 3A represents 50% of this size, meaning that the dimension-A curve marked "50%" in Figure 2 is to be used. The position of the coils is $16.5/(16.5 + 48.5) \times 100$ or 25% of the distance out from center, dimension B. From the intersection of 25 (horizontal scale at bottom), and the 50% curve, the required inductive reactance is read from the scale at the left of Figure 2 to be 650 ohms. The inductance, L, is $650/2\pi f$ or 57.5 microhenrys, if No. 8 wire is to be used. For smaller diameter wire, the inductance should be somewhat larger. (Calculations from Eq. 1 for No. 12 wire indicate the required inductance is 60.99 µH.)

The radiation resistance of a shortened antenna loaded to resonance is less than that of a full-sized antenna. Further, the shortened antenna is "sharper," meaning that the change in reactance versus frequency is greater. In other words, the shortened antenna acts as a tuned circuit having a higher Q than a full-sized antenna. To check these characteristics, the line input impedances for the antenna of Figure 3A were measured with a laboratory bridge, and the electrical line length at the measurement frequency was then taken into account to determine the impedance at the antenna feed point. The antenna was constructed of No. 12 wire and hung at a height of 50 feet as a "flat-top" radiator.

The solid curve of Figure 3B is a plot of the feed-point impedance versus frequency for this antenna. The plot on Smith Chart coordinates is more meaningful than a simple SWR-vs.-frequency curve because the magnitudes of the resistive and reactive components are shown, as well as the sign of the reactance. (Capacitive reactance is negative, plotted to the left of the vertical center line, and inductive reactance is positive, plotted to the right.) In this presentation, a 50-ohm nonreactive impedance will appear at the exact center of the chart. The SWR in 50-ohm line for a given frequency may be determined by first noting the distance from the center of the chart to the particular impedance plot on the curve, and next measuring this same distance down the vertical center line from chart center (a drawing compass is helpful for this task), and finally dividing 50 into the value read at that point on the center line. For example, the SWR at 1.8 MHz equals 120/50 or 2.4, as indicated by the segment of the 2.4 SWR circle in Figure 3B. It may be seen that resonance (zero reactance) occurs at approximately 1810 kHz, where the resistance is about 22 ohms. The SWR at resonance is 2.33:1, and climbs to 3:1 at 1825 kHz. At 1850 kHz, the SWR is 10:1. Without any matching provisions the antenna is relatively sharp, as mentioned earlier. If one sets the usable bandwidth as the frequency range where the SWR is 3:1 or less, it is approximately 35 kHz, or 1.9% of the resonant frequency. As far as efficiency is concerned, ohmic losses are low, and the antenna is a good performer on 160 meters. Because of its horizontal polarization, it has proved to be most effective at night, and stations several hundred miles away have been worked with S-9 reports received for the 50-watt signal.

For a comparison of impedances, the broken curve of Figure 3B is a plot of measured impedances of a full-size half-wave dipole, 260 feet long overall, hung in place of the shortened antenna. From this curve it may be seen that resonance occurs at 1810 kHz, where the resistance is 59 ohms. The 3:1-SWR bandwidth for the half-wave antenna is in the order of 60 kHz, or 3.3% of the reso-


48.5'
16.5'
16.5'
48.5'
Insulator
61 µH
61 µH
Insulator
50–Ohm Coax
(A)
INDUCTIVE REACTANCE COMPONENT $\left(+\frac{jX}{Z_o}\right)$
OR CAPACITIVE SUSCEPTANCE $\left(+\frac{jB}{Y_o}\right)$
CAPACITIVE REACTANCE COMPONENT $\left(-\frac{jX}{Z_o}\right)$
OR INDUCTIVE SUSCEPTANCE $\left(-\frac{jB}{Y_o}\right)$
RESISTANCE COMPONENT $\left(\frac{R}{Z_o}\right)$ OR CONDUCTANCE $\left(\frac{G}{Y_o}\right)$
1.8
1.825
1.8
1.825
1.85
1.85
SWR = 2.4
(B)

Figure 3—At A, an 80-meter dipole loaded for 160-meter operation. The inductors are 37 turns of coil stock having a 3-inch diameter and 10 turns per inch (B&W 3035). At B, the impedance plot of this antenna installed at a height of 50 feet (solid curve), and the plot of a 160-m half-wave dipole (broken curve).

nant frequency. It is interesting to note on this curve that the SWR at resonance is 1.18:1, and that it is a somewhat lower value, 1.15:1, at a frequency a few kilohertz above resonance. (Measurements were made every 5 kHz across this band, but plot points are shown only for 25-kHz increments to avoid crowding of the data.) This evidence refutes the oft-heard statement that the SWR-vs.-frequency curve is *always* lowest at antenna resonance. Points to remember are that the SWR in a transmission line is completely dependent upon the characteristic-impedance value of the line in use. Using a line of different impedance may shift the position of the SWR curve along the frequency axis in a simple SWR-vs.-frequency plot. This is definitely true in this case — if the 160-meter half-wave dipole were to be fed with 75-ohm line, the lowest SWR would occur at a frequency about 5 kHz *below* antenna resonance, whereas with 50-ohm line the lowest SWR is at a frequency slightly *above* resonance. The reason this happens is that the resistive component of the impedance, which consists of the radiation resistance plus any loss resistance, is not constant with frequency, even over a rather narrow frequency range. It must be acknowledged that the differences here are very slight, however, and for practical purposes the frequency of lowest SWR is (within a few kilohertz) the resonant frequency of the antenna.

Another point concerning the SWR values bears noting. The values as determined from the plots in the manner described above are quite accurate, having been determined by measurements with laboratory equipment. In contrast, measurements with simple SWR indicators usually cannot be relied upon for anywhere near the equivalent accuracy.

For example, the author owns a commercially manufactured SWR indicator of the Monimatch type (see McCoy*) which, under a particular set of conditions, indicates a 2.5:1 SWR in a line where laboratory measuring equipment shows the *true SWR to be 4:1*. A significant difference! Herein lies another reason why impedance plots on Smith Chart coordinates are more meaningful than a simple SWR-vs.-frequency curve — greater accuracy may generally be expected.

A Half-Size 80-Meter Antenna

Figure 5A shows the 3-band concept described earlier as it can be applied to 80, 40, and 20 meters. Its overall length is 66 feet, not a difficult length to use on a small lot. This antenna was constructed for 80-m operation with a design-center frequency of 3.55 MHz, using No. 12 antenna wire and 40-μH loading coils—27 turns of stock having a diameter of 3 inches and a pitch of 10 turns per inch (tpi). Feed-point impedances versus 80-m frequency for the antenna, hung at a height of 50 feet, are shown by the solid curve at B of Figure 5. Actual resonance occurred at 3.54 MHz, where the resistance was about 26 ohms. The bandwidth within which the SWR is 3:1 is



Figure 4—Copper electrical service connectors, sold under one trade name of Servit, provide a simple means of installing the loading coils. The antenna wire and the ends of the coil wires should be tinned to prevent corrosion. In addition, a protective coating of acrylic spray may be used at each connection.


17'
16'
16'
17'
L1
L2
Insulator
Insulator
(A)
50–Ohm Coax
INDUCTIVE REACTANCE COMPONENT $\frac{+jX}{Z_0}$ OR CAPACITIVE SUSCEPTANCE $\frac{+jB}{Y_0}$
CAPACITIVE REACTANCE COMPONENT $\frac{-jX}{Z_0}$ OR INDUCTIVE SUSCEPTANCE $\frac{-jB}{Y_0}$
RESISTANCE COMPONENT $\frac{R}{Z_0}$ OR CONDUCTANCE $\frac{G}{Y_0}$
3.5
3.525
3.55
3.575
3.6
3.5
3.55
3.6
3.65
3.7
(B)

Figure 5—At A, a 40-meter dipole loaded for 80-meter operation. For resonance at 3.55 MHz the coils should be approximately 40 μH (27 turns of stock); 3.75 MHz, 35 μH (24 turns); 3.9 MHz, 31 μH (22 turns); and 4.0 MHz, 29 μH (21 turns). These are circulated inductance values for No. 12 antenna wire. Coil stock referenced above is 3-inch diameter, 10 turns per inch (B&W 3035). At B, the impedance plot of the 3.55-MHz version (solid curve) and of an 80-m half-wave dipole (broken curve).

Table 1

Characteristics of various loading techniques, 66-foot 80-m dipole.

Loading	*Approx. feed-point resistance, resonance*	*SWR at resonance*	*3:1-SWR bandwidth, % of resonant freq.*
40-µH coils only	26 ohms	1.92:1	1.69
36.5-µH coils, 18″ dangling ends	26	1.90:1	1.79
36″ hats outside 32.5-µH coils	23	2.15:1	1.68
30-µH coils, 36″ hats at ends	25	1.98:1	2.05
None (λ/2 dipole)	43.5	1.15	Greater than 3.6

Coil positions for each loaded antenna were 16 feet from antenna center. All antennas were constructed of No. 12 wire and installed at a height of 50 feet.

60 kHz, or 1.69% of the resonant frequency.

Also shown in Figure 5B, by the broken curve, are the feed-point impedances of a half-wave dipole, 132 feet overall length, hung in place of the shortened antenna. Resonance occurs at 3.54 MHz, where the resistance is 43.5 ohms and the SWR is 1.15:1. The broader nature of the half-wave antenna is exhibited by the "tighter" curve which swings closer to the 50-ohm center point of the chart than the shorter, loaded antenna. The SWR at 3.5 MHz is 1.6:1 and remains below 3:1 to 3.67 MHz.

Capacitive and Inductive Loading

One would assume that a combination of capacitive and inductive loading might provide a different feed-point impedance than would inductive loading alone, because of different current distributions in the radiators. To check out this assumption, the antenna of Figure 5A was used as a "test bed" for comparative measurements. Capacitance hats were attached at different points along the 17-foot lengths of wire outside the coils, and the coils were pruned to reresonate the antenna at about the same frequency as before. The impedance measurements were then repeated.

Dangling End Sections:

First, "hats" consisting of 18 inches of No. 12 wire were affixed to the antenna ends and permitted to dangle. This lowered the resonant frequency to 3435 kHz. By calculations, this was approximately the same effect as that of extending the 17-foot portions of the antenna by the same amount as the dangling lengths, so it would seem to make little difference whether short sections of extra length are added inside the supporting insulators or are at the ends, suspended at right angles to the main antenna wire.

The inductors were reduced from 40 to 36.5 µH (25-turn coils replaced the original 27-turn coils), and resonance occurred at about 3575 kHz. At this frequency the resistance was 26 ohms and the SWR 1.90:1. The 3:1-SWR bandwidth, 64 kHz, is 1.79% of the frequency of resonance. The impedance plot for this arrangement is shown as Curve A in Figure 6. The resistance at resonance for this antenna is identical to that with the coils alone, and the bandwidth is only 4 kHz greater, 64 kHz vs. 60. From these results, one would conclude that the main advantage offered by the "danglers" is a small saving of space over a flat-top antenna.

Capacitance Hats Near Loading Coils:

Next the dangling end sections were removed and a pair of capacitance hats was formed, each from two 36-inch lengths of No. 12 solid wire. The two wires for a single hat were attached at their centers to the antenna wire at a point just outside one of the loading coils. The hat wires were then bent radially to form an X at right angles to the antenna wire, like four spokes of a wheel with the main antenna wire at the hub. The diameter of the X-shaped hat was thus 36 inches. The second hat was placed in a like manner just outside the second coil. Burndy connectors were used to affix the hat wires. The resonant frequency of this configuration with the original 40-µH loading coils was found to be 3290 kHz. The effect of adding the hats was about the same as that of extending the 17-foot lengths to 19 feet.

When the inductors were replaced with 23-turn coils (32.5 µH), the antenna resonated at about 3.575 MHz, the resistance being 23 ohms. The SWR at resonance is 2.15:1, and the 3:1-SWR bandwidth for this configuration is 60 kHz, 1.68% of the resonant frequency. The impedance of this arrangement versus frequency is shown by Curve B of Figure 6.

It is surprising to note that, by the standards of most amateurs, the characteristics of this antenna are not as good as those of the same length antenna with loading coils alone. The SWR at resonance for the antenna with combination capacitive and in-



Figure 6—Curve A is the impedance plot of the antenna of Figure 5A with 1.5-foot dangling end sections added and the coil trimmed to restore resonance near the original frequency. Curve B is a plot of the same antenna with X-shaped capacitance hats added at a point just outside the loading coils (dangling sections removed and coils trimmed to reestablish resonance).



Figure 7—Impedance plot of a 66-foot dipole using a combination of off-center inductive loading and capacitive end loading. Of all the shortened configurations tried, this arrangement offered the greatest bandwidth.

ductive loading is higher (2.15 vs. 1.92), and the 3:1-SWR bandwidths are the same, 60 kHz. Perhaps a significant factor here, though, is that the diameter of the capacitance hats used for these measurements was small, only .011 wavelength. Supporting much larger hats presents mechanical problems with wire antennas, however, as even these were a bit flimsy and would require reshaping after gusty weather.

Capacitance Hats at Antenna Ends:

Finally, the X-shaped capacitance hats were moved to the outside ends of the antenna, just inside the end insulators. With the original 40-µH coils, resonance appeared at 3215 kHz. From calculations, it was as if the 17-foot end sections were actually 21 feet long. With 30-µH coils (22 turns) in place, the resonant frequency was 3560 kHz. At this frequency the resistance was 25 ohms and the SWR 1.98:1. The 3:1-SWR bandwidth is 73 kHz, or 2.05% of the resonant frequency. The impedance plot of this antenna is given in Figure 7.

It is interesting to note that the position and shape of the plot for this antenna on Smith Chart coordinates is nearly identical to that for the same length antenna with loading coils only, the solid curve of Figure 5B. For this antenna, however, the plot points for 25-kHz frequency increments appear closer together, which accounts for the increased bandwidth.

Conclusions:

The measured characteristics of these various configurations of loading for the 80-meter antennas are tabulated in Table 1. Remember that the overall "flat-top" length of each antenna arrangement, is 66 feet, and that the loading coils are always positioned 16 feet each side of the center of the antenna, being pruned for resonance at approximately 3550 kHz. For comparison, information for a half-wave dipole is also included.

Of the various arrangements, capacitive end loading decidedly provides the greatest bandwidth, excepting the full-size half-wave antenna, of course. Although there are slight differences in the resistance value at resonance, all are of the same order of magnitude. These values, as well as those for the 160-m antenna discussed earlier, tend to confirm a *broad* rule of thumb that the writer has formulated for this type of antenna: The feed-point impedance value at resonance is roughly proportional to the length of the antenna. That is, a loaded antenna which is half the size of a half-wave dipole will have approximately half the radiation resistance of the full-sized antenna.

Eq. 1 given earlier or the chart of Figure 2 allows one to calculate loading-coil values for antennas with loading coils only. Additional capacitive loading is not taken into account. Calculating the effects of various capacitive loading arrangements appears to be difficult, and work remains to be done in this area.

Multiband Antennas with Loading Coils

All of the foregoing material has been devoted to the loading of an antenna for resonance at a single frequency. Resonated as described, the antenna is electrically a half wave in length. It will, however, operate well on higher frequencies — frequencies at which it is an odd multiple of half waves, in *electrical* length . . . three half waves, five half waves, etc. Because of the lumped loading of the shortened antenna, these higher frequencies will likely not be closely related to odd-order harmonics of the fundamental frequency, as the case would be for a nonloaded radiator. (For example, it is a well-known fact that a 7-MHz half-wave dipole operates well on its third harmonic, 21 MHz.)

A loaded dipole will become an electrical 3/2-λ antenna at some frequency *below* that which is three times the fundamental resonant frequency. Depending upon the overall antenna length, coil value, and coil position, it is possible for an 80-meter loaded dipole to become a 3/2-λ performer on 40 meters. With such an arrangement, one would have a dual-band antenna without requiring the use of traps. The idea can be expanded upon to arrive at a loaded antenna without traps which will operate on more than two bands. This scheme offers considerable constructional simplification as compared with trap arrangements.

The multiband loading-coil concept has been recognized for better than half a century, but little use of the technique has been made by amateurs. Some years ago a very good article on the subject a was published by William Lattin, W4JRW.* That article is recommended reading for anyone interested in more details on the concept. Supplemental information has been published by Buchanan.* Attempts by this writer to calculate antenna sizes and coil values for dual-band antennas have met with some success. From calculations and experiments to date, it appears that with only two loading coils (one each side of center), the antenna must always be greater than a half wave in physical length for the higher of the two frequency bands. In other words: any 80/40 meter arrangement, for example, apparently would need to be longer than 66 feet from tip to tip. However, much work also remains to be done in this area.

References

Buchanan, "An Inexpensive 40- and 80-Meter Antenna," Hints and Kinks, *QST*, September, 1962, p. 62.

Hall and Kaufmann, "The Macromatcher, An RF Impedance Bridge for Coax Lines," *QST*, January, 1972, p. 14. Information also contained in the 50th and subsequent editions of *The Radio Amateur's Handbook*, and the 13th edition of *The ARRL Antenna Book*.

LaPlaca, "Using the ARRL L/C/F Calculator," *QST*, December, 1973, p.26.

Lattin, "Multiband Antennas Using Loading Coils," *QST*, April, 1961, p.43.

McCoy, "Monimatch, Mark II," *QST*, February, 1957, p. 38. Also, "An Etched-Circuit Monimatch For Checking Your Antenna System," *QST*, October, 1969, p.29.

Sevick, "The Ground-Image Vertical Antenna," *QST*, July, 1971, p. 16. Also, "The W2FMI Ground-Mounted Short Vertical," *QST*, March, 1973; "A High Performance 20- 40- and 80-Meter Vertical System," *QST*, December, 1973, p. 30; and "The Constant-Impedance Trap Vertical," *QST*, March, 1974, p.29.

By Frank Witt, AI1H From *QST*, September 1993

A Simple Broadband Dipole for 80 Meters

Turn your existing 80-meter dipole into a broadband antenna by simply modifying the feed line. Multiband operation is an option.

A conventional coax-fed, half-wave dipole doesn't provide a low SWR over the entire 80-meter band—an inconvenience for those of us who like to operate phone and CW on that band. Several approaches to overcoming this limitation, short of an antenna tuner in the station, have been described.[1,2] The antenna system described here is simpler than any of its predecessors and has the following features:

- A 2:1 SWR or better is achieved over all or most of the 80-meter band.
- Antenna length and appearance are the same as those of a conventional half-wave dipole. Consequently, it's lightweight and has small wind and ice loading.
- The antenna configuration permits multiband operation with a single feed line.
- The losses due to broadband matching are acceptable.
- The cost is about the same as a conventional half-wave dipole.

All the SWR data given in this article were measured at the transmitter end of the feed line. The reference impedance is 50 Ω, since most equipment is designed for this impedance. The term *antenna system* as used throughout this article includes not only the radiating wire, but also the feed line, balun (if used), any lightning-protection measures, antenna tuner and so forth.

The dipole antenna itself is not broadband; the system uses a broadband *match*. The key broadbanding element of this antenna system is the *transmission-line resonator*: Part of the transmission line compensates for the reactance presented by the dipole away from its resonant frequency. This part of the line is a multiple of an electrical half wavelength. Another part of the line presents an appropriate source impedance to the transmission-line resonator (TLR).

First I'll describe a version of the broadband antenna system, along with some practical results. Then I'll cover the important matter of antenna-system loss. Following that are some variations to suit specific requirements, and a method for using the antenna for several bands. I'll also compare transmission-line-resonator broadbanding to other broadbanding methods.

The 80-Meter Broadband Antenna System

Figure 1 shows the simple broadband antenna system as used at my station. The antenna proper is a center-fed half-wavelength dipole. The transmission line is segmented into one electrical wavelength of 50-Ω coax and an electrical quarter wavelength of 75-Ω coax. The calculated and actual lengths are shown in Table 1. Lengths were calculated using the formulas given later in this article, using a center frequency (F_0) of 3.75 MHz and VF (velocity factor) of 0.66. The actual lengths resulted after I performed the tuning procedure described later. Manufacturing variations from the published cable velocity factors, and some stretching of the coax, contributed to the differences between actual and measured values. (The actual lengths were measured on untensioned cable.) The antenna is installed as an inverted V with a 140° included angle and an apex height of 60 feet. The wire size is #14, but is not critical.

Table 1
Calculated and Actual Lengths of the Broadband Dipole Antenna at AI1H

	Calculated	*Actual*
1/4-λ Coax	43.3 feet	43.3 feet
1-λ Coax	173.1 feet	170.5 feet*
Dipole	124.5 feet	122.7 feet

*Includes 11 inches for balun.



Figure 1—One form of the simple broadband antenna system. It resembles a conventional dipole except for the 1/4-wavelength, 75-Ω segment. Points A and B are discussed in the text.

This system's SWR (at the transmitter) as a function of frequency is shown in Figure 2. For comparison, the SWR for the same dipole fed with about 5/4 wavelengths (214 feet) of RG-213 coax is also shown. (This is the same total length as the RG-213 and RG-11 segments used in the broadband system.) The broadband system's 2:1 SWR bandwidth is 2.2 times that of the conventional system—and the *only* difference is the feedline configuration!

The radiating properties of the broadband antenna over the 80-meter band are essentially identical to those of a dipole cut for any specific frequency in the band. Also, since the antenna system is designed for a 50-Ω transmitter, the feed-line length may be extended by adding the required length of 50-Ω coax between the transmitter and the quarter-wave segment (point A in Figure 1).

A 1:1 current balun should be installed at the antenna's feed point. I use the balun on general principles. Often, it provides no visible difference in operation, but the balun does minimize feed-line radiation. You can determine whether your antenna needs a balun by measuring the SWR versus frequency with and without a balun installed. If the balun is not needed, the two sets of data will be identical.

Antenna-System Losses

It's important to know the losses in any antenna system. This is especially true for broadband antennas, because loss alone can broadband an antenna system. As the next section shows, the configurations presented in this article do not yield a significant loss penalty. Although other loss contributors exist in antenna systems, we will focus on the primary ones: *feed-line loss* and *mismatch loss*. Other losses, such as ohmic loss in the antenna wire, are the same for both the conventional and broadband systems described here.

Feed-line loss is the easiest to understand. It is unavoidable, and is lowest when the feed line is *flat* (when the line SWR is close to 1:1). At HF, feed-line loss results primarily from ohmic losses in the copper conductors.

Mismatch loss occurs when the impedance seen by the transmitter is not the complex conjugate of the transmitter's impedance (when the line SWR at the transmitter is not 1:1). For a 50-Ω transmitter, the mismatch loss is 0 dB when the load impedance is 50 Ω. When the load impedance is not 50 Ω, the mismatch loss can be made to be 0 dB if a transmitter with a tunable output stage (such as a conventional tube-type linear amplifier) is tuned for a conjugate match. An antenna tuner can also provide this match. In this case, however, the antenna-tuner loss (perhaps as much as 1 dB) replaces the mismatch loss in the total-loss equation. That subject isn't discussed here.

If you don't use an antenna tuner and the transmitter has a fixed-tuned 50-Ω output, loads that present the transmitter with an SWR under 2:1 are highly desirable. The impact of high SWR on mismatch loss will become clear in the next section.

Loss must be kept in perspective. All of the broadband antenna systems described here have a worst-case total loss of less than 3 dB—not enough to notice in many 80-meter QSOs. (If the loss is 3 dB, half of the transmitter's output power is radiated and half is lost elsewhere.) The main effect of loss is stress on system components: that on the transmitter due to the mismatched load, and that on the transmission line due to heating.



Figure 2—Measured SWR versus frequency for the broadband and conventional antenna systems.



Figure 3—Antenna-system configurations for long feed-line runs. The solid lines are SWR; the dotted lines are feed-line loss; and the dashed lines are feed-line loss plus mismatch loss. At A, a conventional system using an RG-213 feed line; at B, the feed line is a 1/4-λ section of RG-11 (75 Ω) followed by 1 λ of RG-213; and at C, a 1/4-λ segment of RG-11 is followed by 1 λ of RG-11 (one 5/4-λ piece of RG-11). The total feed-line length in each case is 216.4 feet.

Variations

The broadband antenna system described above is well-suited for the installation at my station, where the distance between the shack and the antenna is rela-



Figure 4—Antenna systems for high power and shorter feed-line runs. The solid lines show SWR; the dotted lines represent feedline loss; and the dashed lines show feed-line loss plus mismatch loss. At A, the feed line is RG-213; at B, it's a 1/4-λ section of RG-11 followed by two paralleled 1/2-λ lengths of RG-213; at C, a 1/4-λ segment of RG-11 is followed by two paralleled 1/2-λ lengths of RG- 11, and at D, 1/4-λ of RG-11 is followed by 1/2-λ of RG-213. The total feed-line length in each case is 129.8 feet.

tively long (more than 200 feet) and because I use a 1-kW amplifier. Other feed-line combinations are better suited to other installations. Some of these are shown in Figures 3 through 5, along with calculated SWR and loss data. From this information, you can select an appropriate feed-line combination for your needs.

The figures also show the characteristics of conventional dipole antenna systems. If you compare them, you'll see that the transmission-line resonator provides broadbanding without a significant loss penalty. I haven't tried all these combinations, but based on my experience, they should perform as predicted in most situations if the radiator doesn't deviate significantly from the model I used in my calculations: a dipole 125 feet long, 40 feet high, and made of #14 wire. This model is based on data provided by Walt Maxwell, W2DU, in his book, *Reflections*.[3] I chose his data since it is typical of many 80-meter installations.

All of the broadband antenna systems use a 1/4-wave section and either a 1/2- or 1-wavelength section. Figure 3 illustrates a system for long feed-line runs. It uses RG-11 and RG-213 cable and should be considered for all power levels. Figure 3B covers the case shown in Figure 1 and used at my station. The feed line of Figure 3C is a continuous length of RG-11 cable 5/4 wavelengths long. The transmission-line resonator is the 1-wavelength section of the cable nearest the antenna.

This approach would also work with surplus 75-Ω CATV Hardline. A 3/4, 5/4 or 7/4-λ section of 1/2-inch Hardline yields less than 2 dB feed-line loss plus mismatch loss over the entire band, and less than 1 dB total loss over any 300 kHz of the band. This configuration is particularly attractive to contesters and DXers, because even a fairly long line7/4 λ is 372 feet of 1/2-inch CATV Hardline—gives low loss and a very good match over, say, the 3.5- to 3.8-MHz range.



(A)

(B)

Figure 5—Antenna systems for low power and shorter feed-line runs. The solid lines show SWR; the dotted lines represent feedline loss; and the dashed lines show feed-line loss plus mismatch loss. At A, the feed line is RG-58; at B, it's a 1/4-λ section of RG-59 followed by 1/2 λ of RG-58. The total feedline length in each case is 129.8 feet.

Three broadband antenna systems are shown in Figure 4. All of these are candidates for applications requiring shorter feedline lengths. Figures 4B and 4C show the performance realized when coax cables are paralleled to achieve a low equivalent characteristic impedance. Figure 3B, which results from a 1-wavelength RG-213 transmission-line resonator, and Figure 4B, are very similar. The latter system uses the same amount of cable, but it's cut in half and parallel-connected. This will become clear in the sidebar, "How It Works." The configuration in Figure 4D is attractive because of its simplicity.

Lower-power applications without long feed-line runs can use RG-58 and RG-59 coax. Figure 5B shows how excellent broadbanding is achieved with a remarkably simple feed line. Again, no loss penalty results from the broadbanding.

Adjusting the Broadband Antenna System

The antenna system is easy to build and adjust. First calculate the lengths (in feet) of the transmission-line segments:

$$L_{quarter} = \frac{245.9\,VF}{F_0} \qquad \text{(Eq 1)}$$

$$L_{half} = \frac{491.8\,VF}{F_0} \qquad \text{(Eq 2)}$$

$$L_{full} = \frac{983.6\,VF}{F_0} \qquad \text{(Eq 3)}$$

where

$L_{quarter}$=length of quarter-wave segment

L_{half} = length of half-wave segment

L_{full} = length of full-wave segment

VF = velocity factor

F_0 = center frequency in MHz

A good starting point for the dipole wire length (in feet) is:

$$L_{dipole} = \frac{467}{F_0} \qquad \text{(Eq 4)}$$

For the 80-meter application, I suggest using an F_0 of 3.75 MHz. It's a good idea to cut the wires so that the overall length is 4 feet longer than necessary, in case you need to lengthen the wire during tuning. Pass 2 feet of the extra wire through each end insulator and wrap it back around the antenna wire.

To tune the antenna system, you'll change only the dipole and transmission-line-resonator lengths. The best approach is to build the antenna system as I have outlined here and to measure the SWR at the transmitter end of the system. Any tilt or frequency offset in the SWR characteristic can be removed by increasing or decreasing the dipole or transmission-line resonator length. Start by changing the length of the dipole. To improve the SWR at the high end of the band, the dipole must be shortened; to improve the SWR at the low end of the band, the dipole must be lengthened. Progressively add or subtract 6 inches from both legs of the dipole until the SWR curve is symmetrical about the center frequency.

Frequency offset may be required to center the SWR characteristic in the 80-meter band. You can move the entire curve along the frequency axis without causing asymmetry by changing both the dipole and transmission-line resonator lengths using the following equation:

$$L_{New} = L_{Old}\left(\frac{3750 - \Delta F}{3750}\right) \qquad \text{(Eq 5)}$$

ΔF is the required frequency offset in kilohertz. Shortening the dipole and resonator moves the curve center up in frequency, and lengthening them moves the center down. The length of the quarter-wave segment need not be changed, since the SWR characteristic is not very sensitive to its length.

Lightning Protection

Every antenna system should be designed to minimize the likelihood of a lightning strike. One part of this is keeping all parts of the antenna proper at ground potential. The grounding should be done *outside the shack*, by means of a good ground rod.

I recommend that you install a coaxial lightning protector, which bleeds any static charge from the center conductor, at point B of Figure 1. The protector (and therefore the feed-line shield) should be connected to a high-quality ground rod (the kind electricians use) driven 8 feet into the ground.

Conversion of Existing 80-Meter Dipoles

A study of the cases shown in Figures 3B, 4D and 5B suggests that it's possible to easily convert many existing 80-meter half-wave dipole antennas. Because the most popular way to feed an 80-meter dipole is with a 50-Ω coaxial feed line, the conversion to a broadband antenna system is straightforward. First trim the dipole for resonance at about 3.75 MHz. Then cut the 50-Ω feed line at a multiple of an electrical half-wavelength (at 3.75 MHz) from the antenna. Calculate this length using Eq 2 or Eq 3. Add the 75-Ω quarter-wave section, then complete the run to the shack (if necessary) with 50-Ω coax. Then use the tuning procedure described earlier to optimize the system.

Multiband Operation

Most broadband 80-meter antenna systems are usable only on the 80-meter band, because the broadbanding elements do not allow efficient power transfer on other bands. This is not true with the approach described here, since the structure consists only of a center-fed dipole and a transmission line. Moreover, the transmission-line segments are close to multiples of an electrical half-wavelength near 40 meters and other bands. This opens the possibility for paralleling other half-wave dipoles with the 80-meter dipole and sharing the feed line.

To minimize their interaction, the various dipoles should be spaced from each other away from the feed point. Of course, some interaction will occur and you must tune the multiband system to meet your requirements. I recommend first tuning the 80-meter broadband system and then the next-highest-frequency dipole, and so forth. Only the 80-meter antenna will be broadband, but such broadbanding is not required on the other bands. Figure 6 shows the result of adding a 40-meter dipole to the Figure 1 antenna. Each dipole leg is 34.4 feet long. Note that the SWR on 80 meters changes very little compared to Figure 2. No change was made to the 80-meter dipole or the transmission line.

The multiple-dipole approach described above achieves resonance on several bands and eliminates the need for an antenna tuner on those bands. Of course, if you use an antenna tuner, operation on all HF bands should be possible, but this arrangement is usually not as effective as the multiple-resonance antenna system described here because the feed-line loss is much higher.

Comparison with the Coaxial-Resonator Match

How does the simple broadband dipole described here stack up against other approaches for achieving a good match over the entire 80-meter band? The coaxial resonator match broadband dipole[4,5] represents one of the more efficient designs published to date. It achieves broadband matching at the antenna by the integration of 1/4 wavelength of coaxial cable as a part of the antenna.

Since the coaxial-resonator match achieves a good match at the antenna, the SWR on the feed line is low and the feedline loss is about the same as its matched loss. However, the coaxial cable in the match itself increases the system loss. The net result is that the total loss is about the same with the coaxial-resonator match, but the SWR at the transmitter is lower, never exceeding about 1.6:1 between 3.5 and 4 MHz. Once the SWR is less than 2:1, however, a lower SWR has little value unless you're using a transmitter that significantly reduces power at such SWRs.

Note that the approach described in this article uses a thin wire for the antenna. Most other broadbanding approaches use additional wires or radiators made partly from coaxial cable and are vulnerable to damage from wind and ice loading. Their additional weight and complexity are also limitations.

From the above comparison, the simple broadband antenna system has, by its very simplicity, an edge over the coaxial resonator match, at least in applications where the simpler approach is feasible. Because of the limitations of available coaxial cables, the opportunity for a satisfactory design is constrained. On the other hand, the coaxial resonator match has more adjustment parameters, is useful over a much broader range of applications and yields the lowest SWR over the band.



Figure 6—Measured SWR for the 80- and 40-meter multiband antenna system.

How It Works

A fundamental way of achieving a broadband match to a resonant dipole antenna involves a parallel-tuned LC network and an appropriate source resistance. In an *RF Design* article,* I described the method for designing such networks, even with lossy resonators. The top of Figure A shows the equivalent circuits of the antenna and matching network. The bottom of Figure A illustrates the corresponding elements in the antenna system.

The role of the resonator is played by the transmission-line segment nearest the antenna. It must be a multiple of an electrical half-wavelength. The quarter-wavelength "Q"-section, made from 75-Ω coax, transforms the 50-Ω transmitter reactance to 112.5 Ω $(75^2/50=112.5)$. I won't go into the design details here; they're the subject of another article, "Broadband Matching Using the Transmission-Line Resonator," in preparation for *The ARRL Antenna Compendium, Volume 4.*

For the structure of Figure A to yield a broadband match, the characteristic impedance of the transmission-line resonator and the transmitter resistance must be within a range of values. Fortunately, commonly used transmission lines, which are available in 50- and 75-Ω characteristic impedances, work well in this application. The broadband systems of Figures 3 through 5 show the usefulness of this approach.

Figure B makes another significant point. For this application, the network parameters of a one-wavelength transmission-line resonator (top) are similar to those of a half-wavelength resonator (bottom) with half the characteristic impedance of the upper resonator. Parallel-connecting two identical cables is a convenient way of achieving lower characteristic impedances. This explains the similarity of Figures 3B and 4B and the similarity of Figures 3C and 4C.—*AI1H*

*F. Witt, "Optimum Lossy Broadband Matching Networks for Resonant Antennas," *RF Design*, Apr 1990, pp 44-51 and Jul 1990, p 10.



Figure A–Lossy broadband-matching-network equivalent circuit (top), and corresponding simple broadband antenna system elements (bottom).



Figure B–These two transmission-line resonators behave essentially the same in this application. The characteristic impedance of each cable segment is the same, making the characteristic impedance of the lower resonator half that of the upper one.

Summary

The simple broadbanding technique I've described here capitalizes on the common availability of coaxial cables that fit the application. It overcomes the narrow bandwidth limitations of a conventional 80-meter, half-wave dipole without significant disadvantages. Even parallel dipoles for other bands may be fed with the same feed line.

The limitation of available coaxial cable parameters can be overcome by using the transmission-line resonator as a resonant transformer. Applying this technique is described in an upcoming *ARRL Antenna Compendium* article, "Broadband Matching Using the Transmission-Line Resonator."

This work has benefited from the support and encouragement of my wife, Barbara, N1DIS. Also, I must credit Andrew Griffith, W4ULD, for helping to turn my attention to the approach described here. After reading my *QST* article on match bandwidth of resonant antenna systems,[6] Andy noted that antenna systems should be viewed from their match to a 50-Ω transmitter, even if the feed line does not have a 50-Ω characteristic impedance. He showed examples of the narrowing of match bandwidth to make his point. In my response, published with Andy's letter in *QST*,[7] I pointed out that match bandwidth of an antenna system may actually be *increased* by selecting the right cable length and characteristic impedance. As an example, I showed in Figure 3 of that correspondence the large match bandwidth of a dipole fed with a 5/4-wavelength, 75-Ω RG-11 cable. Note that this is the same case shown in Figure 3C of this article. Thank you, Andy!

Notes

[1] G. Hall, ed, *The ARRL Antenna Book*, 16th ed (Newington: ARRL, 1991), pp 9-1 through 9-12.

[2] M.W. Maxwell, *Reflections: Transmission Lines and Antennas* (Newington: ARRL, 1990), pp 18-1 through 18-6.

[3] See Note 2, p 15-19. 1 frequency-scaled Walt's data, which is equivalent to changing the wire length. This antenna has a Q of 13 and a resonant resistance of 65-Ω. I took into account the fact that the antenna's radiation resistance increases with frequency.

[4] F. Witt, "The Coaxial Resonator Match and the Broadband Dipole," *QST*, Apr 1989, pp 22-27.

[5] F. Witt, "The Coaxial Resonator Match," *The ARRL Antenna Compendium, Volume 2* (Newington: ARRL, 1989), pp 110-118.

[6] F. Witt, "Match Bandwidth of Resonant Antenna Systems," *QST*, Oct 1991, pp 21-25.

[7] A. Griffith and F. Witt, "Match Bandwidth Revisited," *QST*, Technical Correspondence, Jun 1992, pp 71-72.

From *QST*, June 1985 (Technical Correspondence)

Once More With the 80-Meter Broadband Dipole

With reference to earlier items by K1TD and W7ZOI in *QST*, it *is* possible to design a simple, adjustment-free matching network that will make an 80-meter dipole have a reasonable SWR across the band.[1,2] When using Hayward's RLC model of the dipole, a simple parallel-tuned circuit across the antenna feed point gives less than 2:1 SWR across all but the bottom 10- to 20-kHz of the band, as shown in Figure 1.

This method *does* require a source impedance of 140 ohms, so a broadband matching transformer will be needed at the input. I see no reason why you couldn't just tap the input down on L1 and use L1 as an autotransformer to accomplish the impedance matching function. In fact, although I have not tried it, it may be possible to include the balanced-to-unbalanced transformation in the same coil, as shown in Figure 2. To tune this network, use a dip meter with no antenna connected. Then install the network on the antenna and adjust the input tap for the best compromise SWR across the band.

By choosing a lower characteristic impedance, you can get much better SWR over a narrower bandwidth (Figure 1). Retune both the antenna and the network to center the response on either the phone or CW portion of the band.

You can get better SWR in both the fullband and narrow-band case by adding a series-tuned circuit to the input (Figure 3). The improvement is marginal, however, and complicates the impedance step-up arrangement, so it is probably not worth the effort. It would be better to take Hayward's suggestion and make the antenna itself inherently more broadband. One method is to "fatten" the elements by using a wire cage arrangement or similar. Of course this would change the values of Zo, L1 and C1.

The original graphs for Figures 1 and 3 were drawn with an HP-87. I would be happy to send a copy of the rogram to anyone who sends me an s.a.s.e.—*Alan Bloom, N1AL*



Figure 2—Proposed method of feeding a balanced antenna with unbalanced line. The shielded conductor of the coax line must be connected at the exact center of the coil, which is an electrically neutral point in the antenna system.



Figure 1—Calculated reflection coefficient and standing-wave ratio vs. frequency for a single-wire dipole and dipoles with lumped constants (C1 and L1) at the feed point.

For the curve where Zo is 140 ohms:
C1 = 2000 pF
L1 = 0.9006 μH

For the curve where Zo is 100 ohms:
C1 = 3500 pF
L1 = 0.5146 μH.



Figure 3—Calculated reflection coefficient and standing-wave ratio vs. frequency for an antenna with shunt and series lumped constants at the feed point (C1-L1 and C2-L2, respectively).

For the curve where Zo equals 120 ohms:
C1–3500 pF
C2–60 pF
L1–0.5146μH
L2–30.0211 μH

For the curve where Zo equals 90 ohms:
C1–7000 pF
C2–60 pF
L1–0.2573 μH
L2–30.0211 μH

---

[1] J. Hall, "The Search for a Simple, Broadband: 80-Meter Dipole," *QST*, April 1983, p. 22.

[2] W. Hayward, "Limitations to Broadband Impedance Matching," Technical Correspondence, *QST*, July 1984, p. 45.

By Robert C. Wilson — From *The ARRL Antenna Compendium, Vol 2*

Fat Dipoles

Antennas without problems make radio communications enjoyable. I design overseas radio stations for a living, so I'd rather not have to fight my own ham station when just relaxing and rag chewing. Fat dipoles do the things I want. They match the coax line well over a wide band, and they launch the signal remarkably well.

Theory

Making a dipole conductor thicker than normal with respect to wavelength will increase the bandwidth and modify the working impedance of the antenna. The trick is to make a dipole "fat" in such a way that it may be easily constructed from cheap materials, be highly efficient and at the same time arrange things so that it will match the transmission line from the lower band edge to the upper band edge.

I started with the assumption that my band of interest would be the 80/75-meter band. From end to end, this requires a 13% bandwidth to the 2:1 SWR points for my broadband-solid-state final. I also assumed that this antenna was going to be at a nominal height of 30 feet or 0.11 wavelength above ground. The calculations indicated that a dipole built of four quarter-wavelength no. 14 wires (0.064 inch) with a spacing of 0.0114 wavelength would produce the necessary results. The correct length would have to be 0.45 wavelength to match a 50-ohm line.

Length = 442.5/f feet
Width = 11.25/f feet
Height = 112.5/f feet
where f = center frequency in MHz

Construction

Very few problems will be encountered in building this simple fat dipole if you follow the drawing (Figure 1). First you will need five good insulators. I prefer egg type


Length
Insulator
5 Each
3' Wood Spacer
4 Each
a
a
a
Balun
1:1
Support Wire
Or Rope
Length As
Required.
No. 14 Awg
Copperweld
50 Ω Coax
to Station
Equipment
Support Wire
Or Rope
Length As
Required.
2 Slots No. 14 Ga.
2 Holes 1/8
3'
1 to 1 1/4
1/2
Paint with Auto
Undercoating
Wood Spacer

Figure 1—The fat dipole with construction details of the spreaders. See Table 1 for the length and spreader dimensions (A).

insulators but there is no critical problem here. One insulator is for the center of the dipole and the others are for the four ends. You will need four 3-foot-long broom sticks or 1-inch wood or plastic rods with good weatherproofing. I painted mine with auto undercoating but outdoor paint or varnish should also work. Copperweld wire is very desirable because it won't stretch and change the tuning of your antenna. This type of wire is available through advertisements in *QST*. The same source may also be able to supply the essential wide-band balun transformer and coax. Either the RG-58 or RG-8 types of coax cable are satisfactory but the latter requires more support because of its greater weight.

Table 1
Dimensions and Bandwidths on Various Bands

Frequency MHz	*Length, ft*	*Spacing (A), ft*	*Bandwidth, MHz*
1.9	233	5.9	0.252
3.75	118	3	0.5
7.15	62	1.6	0.951
14.175	31.2	0.8	1.885
21.225	20.85	0.53	2.823
28.860	15.34	0.39	3.837

Measure your wire carefully and leave enough extra so that the insulators can be attached. The final length will need to be the calculated value, from insulator wire end to insulator wire end. After building the four-wire section, attach dowel rods as shown to act as spreaders. Fasten each rod in place with pieces of wire threaded through the holes and then wrapped around the antenna wire. Wrap these spreader wires tight enough so that the rods will not slip out of place. Snip off projecting wire ends wherever they occur to prevent RF corona power loss. Then, using either wire or rope, make a bridle to hold the ends of the antenna.

Last, solder the balanced end of the balun transformer to the dipole. Each wire from the balun should go to the pair of wires on the same side of the dipole. The solder job should be of the best quality and permanent because it is hard to repair later. The coax needs to be connected to the unbalanced side of the balun. If you use large-diameter coax (3/8 inch) then think about ways to support the weight. Perhaps a piece of nylon rope from the dipole center insulator to the coax will help take the load, but I'll leave the details of the problem up to you. After this final construction step, haul the antenna up in the trees, using care that no twists are allowed.

Operation

For once I had a 75-meter antenna that worked better than predicted. The SWR was 1.6:1 or better from 3.5 to 4.0 MHz. Better yet, reports received were excellent with my old 100-watt solid-state transceiver. Moving up and down the band gave no loading problems from the broadband final. The fat dipole is just what I needed for a good, relaxing rag chew after a hard day with the 500-kW rig at the office.

CHAPTER TWO

OFF-CENTER-FED-DIPOLES

2-1 **The Off-Center-Fed Dipole Revisited: A Broadband, Multiband Antenna**
From August 1990 *QST*

2-9 **Improved Feed for the Off-Center-Fed Dipole**
From May 1996 *QST* (Technical Correspondence)

2-11 **Off-Center-Fed Dipole Comments, Part 2**
From October 1996 *QST* (Technical Correspondence)

2-13 **Off-Center-Fed Dipole Comments, Part 3**
From October 1996 *QST* (Technical Correspondence)

2-14 **Choke the OCFD**
From September 1997 *QST* (Technical Correspondence)

By John Belrose, VE2CV and Peter Bouliane, VE3KLO **From *QST*, August 1990**

The Off-Center-Fed Dipole Revisited: A Broadband, Multiband Antenna

The search for a simple broadband, multiband antenna with acceptable SWR over the entire 80/75meter band continued with the publication of the article by Witt, AI1H, in April 1989 *QST*. This inspired author Belrose, VE2CV, to reopen his files on the "Windom antenna," or, more properly, the off-center-fed dipole. Particularly since the opening of the 10, 18 and 24-MHz bands, this time-honored, somewhat controversial antenna is attracting a revival in interest and usage because of its multiband characteristics. Thus, the off-center-fed dipole deserves an update. Certainly, most North American radio amateurs have not heard about the German version of this antenna.

Even though it is one of the simplest antennas, the drooping dipole (a dipole with drooping ends, popularly referred to as an inverted V) is effective on 80 meters. For good DX performance, the apex of an 80-meter drooping-dipole antenna should be as high as possible above ground (at least 15 meters [50 feet]), because the antenna's vertical radiation angle decreases with height above ground. The arms of an 80-meter drooping dipole should not be too close to the ground (say, greater than 3 m [10 ft]). The input impedance ($R_a \pm jX_a$) of a drooping dipole depends on the operating frequency, the length of the dipole, the angle between its arms, the dipole's height above ground, and–particularly the resistive component–on the conductivity of the earth beneath the antenna. The included angle between the arms of an 80-meter drooping dipole should be about 127°, since, in this configuration, the antenna's pattern is dipole-like, and its input impedance is about 50 Ω for antenna heights typically employed by radio amateurs. The principal disadvantage of such an antenna is that its SWR bandwidth–less than 200 kHz–is too narrow to cover the 80/75-meter band.

The broadband performance of an antenna can be improved through the use of a matching network at the feed point. This network can comprise discrete components (see Hall,[1] Hayward,[2] Bloom,[3] Hately,[4] and Li, et al[5]); or transmission-line stubs (Snyder,[6] Hansen,[7] and Witt,[8]). Authors Li, et al give a microcomputer program for the design of LCR networks for broadband matching.

Another way to improve broadband performance is to use two dipoles fed in parallel: one dimensioned for the middle of the lower half of the band, and the other for the middle of the upper half of the band. The drooping-dipole configuration is ideal for this arrangement, since the ends of the two dipoles can be fanned (for angular separation) in either the vertical or horizontal plane. An alternative is to use an off-center-fed dipole, which, in addition to broadbandedness, has multiband performance characteristics. This article is concerned with such an antenna.

The "Windom Antenna" and Single-Wire Feed

The original Windom antenna (devised in 1928-29), named after Loren Windom, W8GZ, the amateur who wrote a comprehensive article about it,[9] employed single wire feed at a point of 1/6 to somewhat over 1/7 of the antenna length from the center (see Figure 1A). Windom reported on a detailed experimental study by colleagues John Byrne, W8DKZ, Edward Brooke, W2QZ, Jack Ryder, W8DKJ, and Prof W. L. Everitt of the Ohio State University Dept of Electrical Engineering. They found that if ammeters were placed on the antenna, with the single-wire feeder at the position just described, the current distribution on the dipole was sinusoidal and symmetrical, with no discontinuity in the vicinity of the feed point, and no standing wave on the feeder. Clearly, the feeder was terminated in its characteristic impedance.

This article did not discuss pattern, and it was many years before the computational tools for predicting pattern were available. Parfitt and Griffin[10] have recently analyzed the single-wire-fed dipole (the Windom antenna), and their results show, as anticipated, that radiation from the feed wire does



Figure 1—Two versions of the off-center-fed dipole. At A, the original "Windom antenna"–actually a Hertz (1/2 λ) element excited via a single-wire feeder; at B, a dipole off-center-fed via balanced line. The single-wire-fed version dates from the late 1920s; the balanced-line-fed version (sans balun) dates from the 1940s, and the balanced-line-and-balun version appeared in ARRL publications beginning in the late 1950s.

modify the antenna pattern, primarily at low elevation angles with the horizon. The feed line for their modeled antenna was vertical.[11] The pattern was basically dipole-like, with a squint away from the broadside. Current on a wire, whether uniform (a traveling wave) or sinusoidal (a standing wave) leads to radiation, unless the radiation that results from this feedwire current is canceled by an equal amplitude, out-of-phase current on an adjacent parallel wire (as in a balanced transmission line). For the Windom antenna, feeder radiation could be significant, depending on the arrangement and the length of the transmission line.

The Windom antenna was widely used during the 1930s and into the 1940s. For example, in author Belrose's experience, the British Columbia Forest Service were using the single-wire, off-center-fed dipole in the mid-1940s. It was a simple antenna that was easy to tune and match with the π network employed in the output circuit of their transmitter.

The Off-Center-Fed Dipole and Balanced Transmission Line

A later version (1940s) of an off-center fed dipole (*mis*called Windom) employed 300-Ω ribbon feed at a point 1/3 of the antenna length from one end (see Figure 1B). Such an arrangement was the first antenna used by author Belrose for operation on the 80, 40 and 20-meter bands in the 1940s. Scholle, DJ7SH, and Steins, DL1BBC, have more recently modified this antenna, devising a double-dipole version that provides a good match to 50-Ω line on all Amateur Radio bands from 3.5 through 28 MHz.[12] [See the Appendix for translations of this article and that cited in Note 13–*Ed.*] Note that their double-dipole version provides a good impedance match to coax on the 21-MHz band, which the single-dipole 80-meter antenna did not. A double-size version provides 1.8-MHz coverage as well.[13]

Scholle and Steins added a shorter off-center-fed dipole in parallel with the longer element, and employed a 50-Ω feed coaxial cable with a 300- to 50-Ω (6:1) balun located at the feed point. Table 1 summarizes information available on the element lengths for single and double off-center-fed dipoles. Since the dipole must be resonant on harmonic frequencies, its length must be somewhat longer than optimum for the 75-meter band, as noted by Scholle and Steins. It is apparent from their SWR curves that the resonant frequency of their antenna is less than 3.5 MHz.

Table 1

Summary of Element Lengths for Published Off-Center-Fed-Dipole Designs

Figure 1B Version	13.5 m (44.29 ft)	27.94 m (91.67 ft)
cq-DL double-dipole version	13.8 m (45.28 ft) 4.69 m (15.39 ft)	27.7 m (90.88 ft) 9.38 m (30.77 ft)
cq-DL double-sized, double-dipole version	25.88 m (84.91 ft) 4.69 m (15.39 ft)	51.77 m (169.85 ft) 9.38 m (30.77 ft)
Author's double-dipole version, (balanced coaxial-line feed, Figure 4)	23.3 m (76.44 ft) 6.78 m (22.24 ft)	48.2 m (158.13 ft) 13.58 m (44.55 ft)

In the arrangement employed by Scholle and Steins, the longer elements were horizontal and the shorter elements sloped (the included angle between the arms of which was $\Lambda \approx 100°$). The authors' version was a drooping-dipole configuration ($\Lambda \approx 127°$) with the angle between the arms of the two dipoles approximately 45°. This antenna was fed with two 15-meter (50-foot) lengths of RG-62A (foam dielectric) coaxial cable configured as a balanced transmission line.[14]

We fabricated a *single* off-center-fed dipole (dimensionally identical with the longer element of the Scholle and Steins "double dipole") and used it as a Field Day antenna (in 1985) for 75/80 in. The stimulus for this, and for carrying out a detailed study, was a search for a simple all-band antenna conducted for the Canadian National Institute for the Blind.[15] We experimented with 4:1 and 6:1 baluns, primarily because 4:1 baluns are easier to come by (more on baluns later). The antenna was operated in a drooping-dipole configuration ($\Lambda \approx 127°$), with the apex (which, in our case, was the feed point) at about 12 meters (40 feet). (In retrospect, we should have positioned the center of the antenna at apex height, since in this configuration the current maximum on the antenna [for 80-meter operation] would be at maximum height.) Extensive impedance and SWR measurements were made. To facilitate this, we employed a low-loss (foam-dielectric) coaxial feeder consisting of a 32.3-meter (106-foot) length of Belden 8214 (velocity factor, 0.8.) This feeder was 1/2 λ long at 3.5 MHz, 1 λ at 7 MHz, and so on. High-quality commercial baluns (made by Antenna Engineering, Australia[16]) were used between the feed line and the antenna.

Figure 2 shows our SWR measurements for the 80/75-meter band. With the 6:1 balun in line, the 2:1 SWR bandwidth was 3.47 to 3.93 MHz—broadbanded, indeed. The SWR was even lower on 40 and 20 meters, and less than 2:1 for the lower half of the 10-meter band; see Figure 3. Clearly, these bandwidths are not in accord with simple



Figure 2—SWR vs frequency for a single off-center-fed dipole employing different baluns (4:1 and 6:1) at the feed point, compared with a center-fed 1/2-λ dipole. Both antennas were operated in a drooping-dipole configuration.

Center-Fed versus Off-Center-Fed Dipoles

A center-fed dipole is a resonant antenna at its fundamental frequency* (f_0) and at $3f_0$, $5f_0$, $7f_0$ and so on, whereas an off-center-fed dipole is resonant at f_0, $2f_0$, $4f_0$, $8f_0$, and its bandwidth (apparently) is greater. As a low-band, multiband antenna, this off-center-fed dipole has advantages over the center-fed dipole, but a disadvantage (or advantage, depending on the antenna configuration and one's point of view) is that feeder radiation can contribute to the antenna's resultant radiation pattern. The use of a current balun minimizes feeder radiation.—*VE2CV and VE3KLO*

*The frequency at which it is 1/2 λ long.



Figure 3—SWR vs frequency for the off-center-fed dipole of Figure 2 at 40, 20 and 10 meters.

theory.[17] Fifteen-meter data are not shown because this single off-center-fed dipole was not resonant on the 15-meter band.

The 4:1 balun provided somewhat sharper resonances and lower SWR at resonance in the 80/75- and 40-meter bands, but a low SWR was not obtainable in the 20-meter band. The measured impedance at resonance in the 80/75-meter band with this balun was exactly 50 Ω; hence the antenna's effective feed-point impedance was 200 Ω. This explains why the minimum SWR with the 6:1 balun was 1.5:1; the 6:1 balun, however, seems to be a better compromise if operation on other bands is wanted.

As noted, we employed high-quality commercial baluns (from the AEA Model 250 series). Radio amateurs have several alternatives in this connection; these include using a 4:1 balun and 75-Ω coax; or purchasing or winding your own 6:1 balun (see Orr, W6SAI[18]),and using 50-Ω coax.

Aside from impedance matching, however, there are other factors to consider in feeding an off-center-fed dipole and selecting a balun for this service. Next, we address some of these aspects.

Balun and Feeder Considerations

In the autumn of 1989, we decided to have another look at off-center-fed dipoles. Because of the multiple-resonant-frequency response of the double off-center-fed dipole, we decided to explore the potential of this antenna system for broadband frequency coverage. If used with a suitable antenna-system tuning unit (ASTU), a double off-center-fed-dipole system could perhaps be used on any frequency from 1.8 to 30 MHz. Since conventional baluns do not perform satisfactorily into reactive loads, we decided to eliminate the balun, at least insofar as the antenna and its feeder were concerned. We fed our antenna with a balanced 190-Ω transmission line consisting of two 15-meter (50-foot) lengths of RG-62A (foam-dielectric) coaxial cable as shown in Figure 4 and described in the work cited in Note 15. Teflon-dielectric cable would have been preferable because of Teflon's superior insulating characteristics but 95-Ω, Teflon-dielectric coax is unavailable.

We started out with a single dipole element dimensioned to 1/2 λ at 2 MHz. This antenna exhibited an antiresonant response (very high input impedance, measured at the transmitter end of the transmission line) at 7.6 MHz. Next, we installed the shorter dipole and dimensioned it to *minimize* the system's impedance at 7.6 MHz. Figure 5 shows the system's impedance v frequency. Except for a narrow band of frequencies near 6 MHz, the input resistance fell in the range of 20 to 400 Ω; and the input reactance fell in the range +*j*100 to –*j*200 Ω. This double off-center-fed dipole system is rather easily tuned and matched, since its reactance is low.

Figure 6 graphs antenna currents for a transmitter output power of 100 W. The antenna system was tuned using an unbalanced T network, with a ferrite-bead current balun of the type described by Maxwell[19] between the ASTU and the antenna. A balanced T network patterned after that described by Belrose was initially used since this is the type of ASTU that, in principle, should be used to tune and match a balanced antenna system. Unfortunately, however, this tuner employed a standard toroidal-core balun—a *voltage* balun, which applies almost-equal *voltages* to the wires of a balanced feeder. Even though the balun was on the "tuned side" of the ASTU—a practice we recommend—and the ASTU it-


23.3 m (76.44 ft)
6.78 m (22.24 ft)
13.58 m (44.55 ft)
48.2 m (158.13 ft)
2 x RG-62A
15 m (49.2 ft)
I3
I1
I2
Ignd
to Antenna System
Tuning Unit with
Current Balun
Tuner Ground

Figure 4—A double-dipole, off-center-fed antenna with a balanced coaxial-line feeder. The longer dipole is dimensioned to 1/2 λ at 2 MHz; the shorter dipole is dimensioned to minimize the system at 7.6 MHz. See text.



Figure 5—Impedance (input resistance [R in] and input reactance [X in]) vs frequency for the antenna shown in Figure 4.



Figure 6—Transmission-line currents (peak values for 100-W transmitter output power) for the antenna shown in Figure 4, tuned by means of an unbalanced T network and a ferrite-bead-choke (W2DU) current balun.



Figure 7—Transmission-line currents (peak values for 100-W transmitter output power) for the Figure 4 antenna, tuned by VE2CV's balanced tuner, which employed a voltage balun.



Figure 8—At A, a 4:1, ferrite-bead current balun; at B, connections to the balun end of the dual-coax-balanced feed line.

self was balanced, we found that the transmission-line currents (I_1 and I_2 in Figure 4) differed greatly in amplitude at some frequencies. The difference may surprise you; it did us (see Figure 7).

For an antenna that is asymmetrical with respect to its feeder–such as an off-center-fed dipole–a *current* balun must be used, since this type of balun forces almost equal *currents* into each conductor of the balanced line. This is necessary if transmission-line radiation is to be minimized. If these currents are exactly equal, there will be no difference in current flowing in the ground lead (I_{gnd}), which connects the braids of the coax to the tuner ground. Any current on this lead is then due to radiation-coupled current (I_3) induced on the *outside* surface of the coaxial shield. Clearly, we want this current to be small (to minimize radiation from the transmission line), and indeed it *is* small except at frequencies below 3 MHz (see Figure 6). (Our antenna was suspended from a bracket at the 12-meter [40-foot] level on a 21-meter [70-foot] aluminum-lattice mast. In the final analysis, reradiation by this mast should be considered because current may have been induced on the mast surface.)

Off-Center-Fed Dipoles for the Amateur Radio Experimenter

The off-center-fed dipole used by author Belrose in the 1940s was fed with 300-Ω twin lead via a balanced ASTU that was link coupled to a balanced (push-pull) power amplifier. There was no concern about balun losses and what type of balun to use because the system contained no balun. [20]

The authors' double-dipole, off-center-fed antenna employed a balanced coaxial feed line. This antenna was attractive for the authors because it could be used throughout the HF range if fed via a suitable matching network. If you decide to fabricate and try an off-center-fed dipole system, we suggested that you dimension it in accord with the Scholle and Steins versions, which are optimized for the amateur bands. Furthermore, we suggest that you feed such an antenna with a balanced transmission line. We have used dual RG-62A cables to make a balanced 190-Ω line, but one could use paralleled RG-63 (125-Ω) coaxial cable, which would make a balanced transmission line more in accord ($Z_o \approx 250$ Ω) with the traditional 300-Ω-twin-lead feeder. In such a system, the balun, and the ASTU (if required), can be in the shack to allow experimentation in achieving balanced current feed and reducing losses in the balun. Whatever method you use, feed your off-center-fed antenna via a current balun.

A shield-choke current balun can be constructed by slipping ferrite beads (–43 or –73 material) over a length of coaxial cable. (Depending on the beads obtainable and the diameter of the cable you use, you may need to remove the cable's outer jacket and install the beads directly around the



Figure A—Double Windom.



Figure B—SWR curves for the eight-band double Windom. [These curves do not cover all US amateur frequencies because allocations in the FRG differ from those in the US—*Ed.*]

shield.) As described in the work cited at Note 19, Walt Maxwell, W2DU, used 50 beads of no. 73 ferrite (Amidon no. FB-73-2401, Palomar FB-24-73 or equiv) on a piece of Teflon-dielectric cable to make a practical, low-loss, 1.8-to-30-MHz balun about 12 inches long.[21] Such a balun, however, is a 1:1 transformer—not very useful for the present application, where impedance transformation is also required. A 4:1 balun of similar type (see Note 20) can be constructed by using two equal lengths of RG-62 (95-Ω) coaxial cable, each fitted with ferrite beads. The inputs to these two coaxial-cable baluns are connected in parallel, and the outputs in series (see Figure 8). This makes a center-tapped 4:1 balun.

Our antenna feeder has a center tap: the braid of the balanced coaxial transmission line. The braids of the transmission-line cables can be grounded to the center tap of the balun, or to the ASTU (or transceiver) ground. Connecting them to the transceiver ground is the better arrangement because the transmission-line currents are better balanced, and the braid current is less. (For the braid-to-ASTU-ground connection, the braid current is measured in the wire connection to the balun center tap; in the braid-to-transceiver-ground case, the braid current is measured in the connection to the equipment ground.)

Performance

Our single-element Field Day antenna worked well for us; as previously noted, however, we employed it only on 80/75 meters. On this band, it is essentially a 1/2-λ dipole with unconventional feed. At higher frequencies, the pattern develops lobes because the dipole acts as a long-wire antenna. Provided that this directivity coincides with directions of interest, the off-center-fed dipole is a good, simple broadband/multiband antenna.

The authors' 1989 (double-dipole) version, while not designed specifically for Amateur Radio communication, has been used on various amateur bands (during the winter of 1989-90). It works, but how well? We checked into various nets on 75 and 40 meters. On 75, for instance, we checked into the ONTARS (Ontario Amateur Radio Service) net, and the Newfoundland Phone Net (1730 EST), two regions at quite different distances from the Ottawa area. The reports received were comparable with those given to other stations by net control. On the 160-meter band, we found that we could work stations we could hear, provided that they were running comparable power (100 W) and their local noise levels were reasonable. We have not yet determined the antenna's gain and pattern.

Acknowledgment

The authors work at the Communications Research Centre, Shirleys Bay, Ontario. The measurements for the double-dipole off-center-fed dipole system were made at the Laboratory as part of a study of broadband HF wire antennas.

Notes

[1] J. Hall, "The Search for a Simple, Broadband 80-Meter Dipole," *QST*, Apr 1983, pp 22-27.

[2] W. Hayward, "Limitation to Broadband Impedance Matching," Technical Correspondence, *QST*, Jul 1984, pp 45-47.

[3] A. Bloom, "Once More with the 80-Meter Broadband Dipole," Technical Correspondence, *QST*, Jun 1985, p 42.

[4] M. Hately, "Multiband Dipole and Ground Plane Antennas," *Third IEE International Conference on HF Communication Systems and Techniques*, Conf Series Pub 245, pp 102-106,1985. Maurice Hately, GM3HAT, has patented his method of feeding and matching HF dipoles (UK Patent GB 2112579), and he manufactures and markets his "dipoles of delight."

[5] S. Li, J. Rockwell, J. Logan, and D. Tan, *Microcomputer Tools for Communications* (610 Washington St, Dedham, MA 02026: Artech House, 1983), Ch 14: Broadband Matching.

[6] R. Snyder, "The Snyder Antenna," *rf design*, Sep/Oct 1984, pp 49-51.

[7] R. Hansen, "Evaluation of the Snyder Dipole," *IEEE Trans on Antennas and Propagation*, AP-35 (No. 2), pp 207-210, Feb 1987.

[8] F. Witt, "The Coaxial Resonator Match and the Broadband Dipole," *QST*, Apr 1989, pp 22-27.

[9] L. Windom, "Notes on Ethereal Adornments," *QST*, Sep 1929, pp 19-22, 84.

[10] A. Parfitt and D. Griffin, "Analysis of the singlewire-fed dipole antenna," *IEEE AP-S International Symposium, Vol III* (IEEE cat no. CH2654-2/89, Library of Congress no. 89—84327, Jun 1989, pp 1344-1347.

[11] Such an arrangement is an extreme case because the feeder is perpendicular to the

ground—a configuration probably atypical of singlewire feed in Amateur Radio installations, and one that affords practically zero cancellation between feeder and ground currents. At the other extreme, one of the amateur systems described in Windom's "Notes on Ethereal Adornments" (see Note 9) employed a *1200-foot-long* (365.8-m) feed wire that likely more nearly approached parallelism with the ground. Clearly, "modeling a Windom" is a fuzzy procedure.–*Ed.*

[12] H. Scholle and R. Steins, "Eine Doppel-Windom Antenne für Acht Bänder," *cq-DL*, Sep 1983, p 427.

[13] H. Scholle, "Eine Doppel-Windom Antenne für Neun Bänder," *cq-DL*, Jul 1984, pp 332-333.

[14] J. Belrose, "Tuning and Constructing Balanced Lines," Technical Correspondence, *QST*, May 1981, p 43.

[15] J. Swail, VE3KF, and W. Loucks, VE3AR, private communications, Apr 1985.

[16] Antenna Engineering, Australia Pty Ltd, PO Box 191, Croydon, Victoria 3136, Australia.

[17] W. Wrigley, "Impedance Characteristics of Harmonic Antennas," *QST*, Feb 1954, pp 10-14.

[18] W. Orr, Ham Radio Techniques, *ham radio*, Jan 1983, pp 68-69.

[19] M. Maxwell, "Some Aspects of the Balun Problem," *QST*, Mar 1983, pp 38-40.

[20] J. Belrose, "The Balun Saga Continued," *QST*, in preparation.

[21] As a less-costly alternative, 10≈1-inch-long mix-77 beads—with an inner diameter to pass the coax used—*may* serve as a substitute. (The authors do not have experience with beads of this material, however.) Consult your ferrite-bead supplier on the availability of beads of this type.–*Ed.*

APPENDIX

A Double Windom Antenna for Eight or Nine Bands

This work, which originally appeared as two articles in *cq-DL*, was translated from the German by Dr. George Elliott Tucker, WA5NVI.

Part 1: A Double Windom Antenna for Eight Bands

By Hubert Scholle, DJ7SH, and Rolf Steins, DL1BBC

The asymmetrical dipole antenna developed and described by Windom (W8GZ) in 1929 has been used by many amateurs for many years as the FD4. This has also been the case in Germany.

We discovered in an older periodical (*QRV*) the explanation by F. Spillner (DJ2KY) that this antenna, with the addition of a small one-band Windom for 15 m, can be used as a five-band Windom. After the installation of the additional elements, this antenna worked very well for two years at DL1BBC.

With the opening of new bands (10, 18 and 24 MHz), the thought occurred to try out a new extension of the FD4 to eight bands (3.5 to 29.7 MHz).

What worked for 21 MHz must also be possible for 10 MHz.

So we took off the 21-MHz extension to my antenna and hung two elements of 4.69 and 9.38 m (15.39 and 30.77 ft), respectively, on the FD4 and stretched these downwards from insulators as an inverted V (Figure A).



Figure C—A double Windom antenna for nine bands.



Figure D—Top view of the nine-band double Windom. [The elements are positioned to reduce coupling between the antenna's two off-center-fed dipoles.—*Ed.*]

To calculate the length we used the formula:

$$L/2 = 142.5 \div f \qquad \text{(Eq A)}$$

Whatever would work for 30 m should also work on 15 m.

As suspected, it worked.

As a by-product, it turned out in the measurements that this double Windom resonated just as well on 18 MHz and 24 MHz. So our eight-band Windom came into being with really simple means.

Construction

Thanks to our neighbors, we were able to extend the basic antenna (FD4) to its full length.

At DL1BBC it was installed about 6.9 m (22.63 ft) above the ground, rising to about 8 m (26.25 ft) at each support point. At DJ7SH it hung about 5 m (16.4 ft) above the ground and partly ran over a garage roof. Both extension legs were stretched downwards as an inverted V with an angle of about 100°. Changing this angle allows the whole antenna to be easily tuned during final adjustments.

After construction, the first measurements showed that because of the length of the 30-m elements, the 80, 40 and 20-m bands each had a resonance point that was shifted towards the low end of the band. This effect was eliminated by lengthening slightly the 30-m section, so the resonance points fell more in the middle of the bands.

With this adjustment, the resonance



Figure E—SWR curves for the nine-band Double Windom.

point on 30 m shifted slightly towards the end of the band, but this can be tolerated.

With all measurements of the Windom, it was very clear that how the feed line ran played a decisive role.

According to our results, it must be stressed that the feed line must run first vertically downwards from the feed point to the ground and only then to the shack, as otherwise the entire antenna may be detuned. This is especially the case when the height of the antenna is under 10 m (32.8 ft). The 50-ohm-coax feed at DL1BBC was pulled through an old garden hose and then buried under the lawn.

The lower antenna height at DJ7SH had the result that, with the first construction attempt, the precalculated length of the 30-m elements was exactly right. The antenna delivered on all eight bands at the first go.

As can be seen from the SWR charts (Figure B), at DL1BBC the match on 40 m turned out somewhat less favorable. However, this was immediately fixed by changing the antenna height slightly. At DJ7SH, no resonance curve ran above 1.5:1, which was the goal since neither station uses an antenna tuner.

Performance

First contacts were made with both antennas. These showed that the antennas had a good degree of performance for a long wire. Especially the downwards sloping extension elements have a clear advantage over the horizontal basic antenna for DX.

With the first try on 30 m, many contacts were made with the US (East and West coasts), with signal reports between S6 and S7 while running 100 W.

At present, we cannot make a concrete statement about contacts within Europe.

This article makes no scientific claims, but intends to stimulate the long-wire enthusiast, and especially the friends of CW.

Part 2: Adding Another Band

Because the response was unexpectedly great to the publication of the above in *cq-DL*, we went to work again on an extension, as it was worthwhile to add 160 m.

With a half wavelength at 1.835 MHz, we calculated the basic length of the antenna to be 77.65 m (254.75 ft). We tapped the antenna at 25.88 m (84.9 ft) from one end and fed it with 50-ohm coax through a 6:1 balun. The basic antenna of this length was installed horizontally as a reclining L at DL1BBC. The additional elements, with lengths of 4.69 and 9.38 m (15.39 and 30.77 ft), were attached at the balun. This additional Windom for 10 and 21 MHz was again stretched downwards as an inverted V with an angle of about 100°. Here the additional Windom was mounted so that its elements were not extended in the same direction as those of the reclining L, which gave sufficient decoupling (Figures C and D).

For the feed, the Fritzel company made available for testing a new 6:1 balun, series 83, which can also handle high power. The SWR charts (Figure E) were obtained with the wire lengths given in the preceding paragraph. In case builders experience slight resonance shifts, these can be balanced out by lengthening or shortening the additional Windom.

Performance

First contacts were made with the antenna installed at DL1BBC. Here it was once again shown that the antenna has a good degree of performance for a long wire, especially for 1.8 and 3.6 MHz within Europe. The additional Windom again had the degree of performance described in the first part of this article.

The authors welcome questions and exchange of information. (When writing, please include return postage.)

From *QST*, May 1996 (Technical Correspondence)

Improved Feed for the Off-Center-Fed Dipole

By Richard A. Formato, K1POO

Theoretical data suggest that the commonly used feedpoint for the off-center-fed dipole (OCFD) may not be the best. The OCFD is an attractive multiband antenna because it's simple, inexpensive and requires no antenna tuner. Improving its performance simply by moving the feedpoint makes the antenna even more attractive. This note illustrates how the feedpoint influences antenna performance by analyzing computer-modeled SWR data for three different feedpoint locations.

The OCFD (shown schematically in Figure 1), consists of a single wire radiator of length L, fed off center a distance D from one end. The usual implementation uses a "1/3 feed," that is, the RF source is located one-third of the way from the end, so that D ≈ L/3. Why the feedpoint should be located there is not exactly clear. The ninth edition of *The ARRL Antenna Book,*[1] for example, observes that there is not much theoretical justification for this choice. Nevertheless, the 1/3-feed is accepted practice for building an OCFD.

Design details for a 1/3-feed three-band OCFD (80, 40 and 20 meters) appear in the 17th edition of *The ARRL Antenna Book.*[2] A 4:1 current balun at the feedpoint matches this antenna to any length of 50-Ω coax. More recently, Bill Wright, G0FAH, described a four-band, 1/3-feed OCFD (40, 20, 15 and 10 meters) fed with 300-Ω ladder line.[3] Matching 50-Ω coax requires a 4:1 balun on 40, 20 and 10 meters, and a 1:1 balun on 15 meters. Four-band operation, therefore, requires switching baluns. Another minor limitation is that the ladder-line length can be only an odd multiple of the wavelength at 21 MHz because the line is used as an impedance transformer. A simpler approach to achieving four-band operation is to feed the OCFD at a different point along its length.

Table 1

SWR Versus Feedpoint Placement (see Figure 1)

Feedpoint Distance D (m)	*SWR*
40 Meters	
8.65	2.5
6.98	2.1
3.65	2.0
20 Meters	
8.65	2.0
6.98	1.7
3.65	1.7
15 Meters	
8.65	1.2
6.98	21.3
3.65	1.9
10 Meters	
8.65	2.2
6.98	2.2
3.65	2.4

I computer-modeled a 21.03-meter (69-foot) long, 0.2053-cm-diameter (#12 AWG) OCFD in free space. The dimensions are the same as those in the G0FAH design. Free-space results are a good approximation for antennas high enough above the ground (typically a significant fraction of a wavelength). The band-center SWR was computed on 40, 20, 15 and 10 meters at the antenna-input terminals for a feed system impedance of 200 Ω. The theoretical values of input resistance and reactance were used to calculate SWR (the antenna was not assumed to be tuned). Because the feedpoint impedance is 200 Ω, a 4:1 balun is required to feed the antenna with 50-Ω coaxial cable. The results for three different feedpoints appear in Table 1.

For the conventional 1/3-feed (D = 6.98 m), the 40 and 10-meter SWR values are slightly over 2, while the 20-meter SWR is about 1.75. In marked contrast, the 15-meter SWR is off the scale (the actual value > 20). It is this behavior that makes a special feed system necessary on 15 meters, a complication that can be avoided by moving the feedpoint.



Figure 1—The basic off-center-fed dipole (OCFD).

When the OCFD feed is located 8.65 meters from one end, the 40, 20, and 10-meter SWRs are somewhat higher than they are with the 1/3 feed, but the 15-meter SWR is very low (≈ 1.2). Moving the feedpoint 1.67 meters closer to the antenna's center of the antenna results in a much better average SWR. And, more importantly, special matching is not required to achieve SWR ≤ 2.5 at the antenna terminals on all bands. Balun and coaxial cable losses, which are inevitable, reduce the SWR at the coax input to even lower levels. For most installations, it is probably reasonable to expect SWR at the transmitter to be less than 2 on all bands.

With the feedpoint located 3.65 meters from one end, the SWR on 40, 20 and 15 meters is excellent. The 40-meter SWR is only slightly above 2, and the 20 and 15-meter SWRs are below 2. The highest SWR occurs on 10 meters, where it's approximately 2.4. Because the SWR is reduced by feed-system losses, it will be less than 2.4 at the coax input. And, because balun and cable losses increase with frequency, the SWR reduction will be greatest on 10 meters where it is needed most. Feeding the antenna 3.65 meters from one end may well provide the best overall four-band performance.

In a specific implementation, the OCFD, like any antenna, must be tweaked for optimum SWR. This is accomplished by adjusting the feedpoint location. Other antennas, nearby metallic objects, and the earth are typical factors that influence antenna performance. Since these factors are not included in the computer model, they must be dealt with empirically by adjusting the antenna on-site. The data presented here provide a starting point for experimenting with different feedpoints. Depending on the total antenna length L, height above ground, earth electrical parameters, and feed system Z_0, it should be possible to operate a single OCFD on four or more bands without an antenna tuner or special feed arrangement. It's apparent that the OCFD's SWR varies dramatically as the feedpoint is moved, and that the commonly used $^1/_3$-feed is not necessarily the best. Other feedpoints may therefore produce a better antenna.

---

[1] *The ARRL Antenna Book*, 9th Edition (Newington: ARRL, 1960), pp 191 to 192.

[2] R. Dean Straw, N6BV, Editor, *The ARRL Antenna Book*, 17th Edition (Newington: ARRL, 1994), pp 7-20 to 7-21.

[3] Bill Wright, G0FAH, "Four Bands, Off Center," *QST*, Feb 1996, p 65.

Dean Straw, N6BV, Senior Assistant Technical Editor, comments:

I've modeled what Richard describes and find that he's basically correct in his assertions. However, I would add a couple of caveats:

- The SWR across an individual band will vary. For example, the 40-meter SWR will rise above the level he describes at the ends of the band, because it is a rather large band, percentage-wise. This antenna is no different from an ordinary center-fed 40-meter dipole in that sense.
- The azimuth patterns for this OCFD will not be symmetrical, as is the case for any such off-center-fed antenna. This is nothing new, but should still be mentioned, particularly for those hopeful folks who want a "one-thing-to-all-people" antenna.
- The ham who tries this approach on 30, 17 or 24 meters may burn out the 200:50-Ω balun transformer. The SWR is very high indeed on those bands.

From *QST*, October 1996 (Technical Correspondence)

Off-Center-Fed Dipole Comments, Part 2

By Richard A. Formato, K1POO

In an earlier correspondence,[1] I suggested that the conventional "1/3-feed" used for the off-center-fed dipole (OCFD) is not the best choice. This letter provides additional information, and responds to comments made by Dean Straw, N6BV, at the end of that correspondence. Before addressing the comments, it is important to examine in more detail the SWR data which are the basis of my earlier letter. Figure 1 plots computer-modeled free-space SWR for the prototype 21.03-meter long, 0.0253-cm-diameter OCFD. SWR for a 200-Ω feed system impedance was calculated at the antenna-input terminals every 50 kHz for source frequencies from 5 to 30 MHz. Three feed-point locations were modeled, 3.65, 6.98 (1/3 feed), and 8.65 meters from the end of the antenna; the curves are labeled accordingly.

The most important features of the SWR curves are the locations of minima and maxima, and the corresponding SWR. Table 1 lists minimum SWRs and the frequencies of the minima for the three feed points. For reference, the right-hand columns list the corresponding amateur band and its approximate center frequency.

Table 1
SWR Minima

3.65 m		*6.98 m (1/3-feed)*		*8.65 m*			
Freq (MHz)	*SWR*	*Freq (MHz)*	*SWR*	*Freq (MHz)*	*SWR*	*Band (Meters)*	*Fc*
6.95	1.27	7.05	2.03	7.05	2.49	40	7.15
14.15	1.70	14.05	1.62	14.00	1.61	20	14.20
21.20	1.91	—	—	21.15	1.14	15	21.20
28.25	1.18	28.30	1.30	28.25	1.41	10	28.85

The main point of my previous correspondence was that the 3.65 and 8.65-meter feeds *might* permit four-band operation without a matching network, because these feed points each result in *four* SWR minima between 5 and 30 MHz (see Figure 1). By contrast, the 6.98-meter SWR curve has only *three* minima in that range. The 1/3-feed antenna cannot possibly operate on more than three bands without some sort of matching, which is why the GØFAH design[2] requires two baluns and a specific transmission line length for 15 meters.

How feasible four-band operation is depends only on where the minimum SWRs occur relative to the ham bands, and how low the SWR is across the bands. Table 1 shows that the prototype OCFD has SWR minima very close to the 40, 20, 15 and 10-meter bands. With some on-site tweaking,

---

[1] Richard A. Formato, K1POO, "Improved Feed for the Off-Center-Fed Dipole," *QST*, May 1996, page 76.

[2] Bill Wright, GØFAH, "Four Bands, Off Center," *QST*, Feb 1996, page 65.



Figure 1—A plot of computer-modeled free-space SWR for the prototype 21.03-meter long, 0.0253-cm-diameter OCFD. SWR for a 200-Ω feed system impedance was calculated at the antenna-input terminals every 50 kHz for source frequencies from 5 to 30 MHz.



Figure 2—A plot of the prototype OCFD's SWR from 100 kHz below to 100 kHz above the 40-meter band in 5-kHz steps.

it is reasonable to expect that this antenna, fed either 3.65 or 8.65 meters from the end, could provide good SWR across all four amateur bands without a matching network.

The prototype OCFD dimensions were chosen because they correspond to the G0FAH design, thus permitting direct comparison with that antenna, not because they are optimized in any way. In fact, the prototype dimensions are *not* optimum for a four-band OCFD. In free space, the frequencies at which SWR minima occur, and the depth of the minima, are determined by three parameters: radiating-element length and diameter, and feed-point location. Changing any one of these changes both the frequencies of the SWR minima and the minimum SWR values.

Optimizing a four-band, free-space OCFD comes down to determining a set of antenna parameters that produces an acceptably low SWR (typically less than 2) across the 40, 20, 15, and 10-meter bands. Although I have not determined optimum parameter values, the very good predicted performance of the prototype antenna suggests that still better performance is almost certainly achievable. The purpose of my first letter was to encourage experimentation with OCFD designs, which would hopefully advance the state of the art by producing near-optimum designs.

Turning next to the comments at the end of my first correspondence, they are addressed as follows:

SWR Variation Across a Band

In terms of SWR behavior, the OCFD is much different from an ordinary center-fed dipole (CFD). The CFD is intentionally cut (tuned) to place minimum SWR within the band, which is why SWR increases toward the ends of the band (moving away from the minimum). An OCFD may or may not exhibit this behavior, depending on where its SWR minima occur. To illustrate, Figure 2 plots the prototype OCFD's SWR from 100 kHz below to 100 kHz above the 40-meter band in 5-kHz steps. The SWR does *not* increase toward each end of the band. If the SWR minimum is either outside or at one end of the band, as it is in Figure 2, the SWR will increase in one direction (up or down band), but decrease in the other, quite unlike an ordinary CFD. The OCFD's SWR will increase at both band edges *only* when its SWR minimum is inside the band, which generally is not the case.

Azimuth Pattern

The OCFD does indeed have an asymmetrical azimuth pattern, because the radiating element is not symmetrical about the feed point. But feeding the OCFD 8.65 meters from the end provides a *higher* degree of symmetry than the conventional $^1/_3$-feed. Locating the feed 8.65 meters from one end should result in a more symmetrical azimuth pattern than the conventional feed, not less. Of course, feeding the OCFD 3.65 meters from the end increases its asymmetry compared to the $^1/_3$-feed, so that the pattern for this implementation would be expected to be less symmetrical. Even so, pattern asymmetry is not necessarily undesirable. Many operators may want to take advantage of the OCFD's pattern by orienting the antenna to radiate in a preferred direction. This consideration applies to any antenna, even to the single-band CFD, which is an extremely poor radiator in the direction of the antenna axis at low to moderate take-off angles.

Operating the OCFD Out-of-Band

Regardless of where the feed is placed, or how it is implemented, certainly no attempt should be made to operate a 40, 20, 15, 10-meter OCFD on any other band. High SWR conditions may very well result in balun damage.

The data presented here provide additional insight into the advantages of feeding the OCFD at points other than $^1/_3$ of its length from the end. With computer-models for wire antennas widely available, it should be possible to optimize the OCFD in free space and over typical ground so that multiband operation is achievable without a matching network.

From *QST*, October 1996 (Technical Correspondence)

Off-Center-Fed Dipole Comments, Part 3

By Roy O. Hill, Jr, W4PID

QST's May 1996 Technical Correspondence column article "Improved Feed for The Off-Center-Fed Dipole" contained a statement that surprised me: "Why the feed point should be located [1/3 of the way from the end] is not exactly clear. The ninth edition of *The ARRL Antenna Book,* for example, observed that there is not much theoretical justification for this choice." It seems to me that there is plenty of theoretical justification. I am not an electrical engineer, and I am going to keep this simple. I won't say anything about computer simulations, ground effects, reactance, unbalanced feed-line currents, or adding 15-meter coverage; and I will use the *lowest* frequencies on the 80, 40, and 20-meter bands with full awareness that the frequencies actually used will be higher than that.

Thirty or 40 years ago, it was more or less generally accepted that the impedance of a half-wave antenna was about 4 kΩ at the ends, about 72 Ω at the center, and that the impedance along the antenna could be accurately represented by a straight line on semi-log graph paper. Using these premises, I plotted the impedance along a half-wave 3.5-MHz antenna on the graph of Figure 3. Then I added 7.0 MHz and 14.0 MHz plots for the same antenna.

All three lines cross at two points at about the 280-Ω impedance mark. These two points are 1/3 of the way (within 0.1 percentage point as I measure it) from the ends of the antenna. The antenna can be fed with 300-Ω line at either of the triple-crossing points and it will work on all three frequencies. You could miss the exact crossing point (or change the frequency) somewhat and still have an impedance between 150 and 600 Ω, which would present an SWR less than 2[4]—an allowable value for most transmitters. All this was pretty widely known in the 1950s. What happened to it? Was all the old low-tech knowledge thrown out when the modern high-tech stuff came along?



Figure 3—Impedance plot of an OCFD for 3.5, 7 and 14 MHz as a function of distance (in feet) from either end.

Also, the article mentioned that the "1/3-feed" antenna requires no antenna tuner. That is true, of course, for loading the antenna, but back in the days I've been talking about, the ARRL was stressing that you should *not* use a multiband antenna without an antenna tuner because of the danger of harmonic radiation. Do we not worry about harmonic radiation any more?

A little over 30 years ago, using as a guide a graph like the one shown in Figure 3, but using frequencies more like those on which I would be operating, I put up an antenna fed with 300-Ω ribbon 80 feet from one end and 44 feet from the other. I have used this antenna ever since. I do use an antenna tuner with it. The system works fine and causes no RFI or TVI. I used similar antennas for about 12 years before that, at other locations.

I just couldn't pass up that "not much theoretical justification" quoted from an ARRL publication without comment. The 1/3 feed has, not only plenty of theoretical justification, but plenty of practical justification—from use.

---

[4] This is only accurate if the impedance is purely resistive. With reactive impedances, it is entirely possible to have an SWR higher than 2.—*Zack Lau, KH6CP*

From *QST*, September 1997 (Technical Correspondence)

Choke the OCFD

By Dale Gaudier M0AOP/K4DG

After reading with interest Richard (K1POO) Formato's technical correspondence,[3] I would like to share some observations made in the course of modeling, then constructing, an off-center-fed dipole (OCFD) using K1POO's design suggestions.

I first modeled K1POO's designs (overall length of 68 feet 5.5 inches or 21.03 meters) with feed points at 3.65 meters (11 feet 10.5 inches, or 17.4%) and 8.65 meters (28 feet 2 inches, or 41%) from one end using Roy (W7EL) Lewallen's *EZNEC* V1.0. Using K1POO's design criteria (a nominal feed point impedance of 200 Ω) the free-space SWR curves were a good match for those set forth in his correspondence.

Based on the model data, it appeared that the design with a feed point at 3.65 meters (17.4%) from one end gave the best results overall for all four bands (40, 20, 15 and 10 meters).

I then built an antenna based on the 3.65-meter-feed-point model. I constructed the dipole conventionally of #14 AWG stranded copper wire and mounted it approximately 33 feet (10 meters) above ground. A commercial 4:1 balun at the feed point allows matching the 200 Ω antenna feed point to a 50 Ω coax feed line. I used an SWR analyzer attached to the feed line to measure the antenna's resonance and SWR. The results are shown in Table 1.

Table 1
Results without the RF Choke

Band (meters)	Minimum (MHz)	2:1 SWR Range (MHz)
40	~8.5	(SWR >>3)
20	14.17	13.250 - 15.500
15	21.58	20.420 - 22.350
10	29.69	28.550 - 30.480

The SWR minimum and 2:1 SWR range for the 10 meter band were higher than desirable for an antenna whose purpose is to minimize the need for a tuner. However, the real puzzle was the lack of resonance anywhere near the 40 meter band! The SWR minimum around 8.5 MHz was neither pronounced nor deep, and certainly not what was predicted by computer modeling.

I tried pruning the two dipole legs. This only caused the 8.5-MHz SWR minimum to shift somewhat. Pruning did not produce an acceptable (< 2:1 SWR) minimum anywhere in the 40 meter band; it also decreased the 20, 15 and 10-meter band SWR minima.

It occurred to me that the effects I was observing might be due to unequal currents flowing at the feed point (possibly due to the asymmetrical design of the OCFD). I made a simple RF choke by coiling several turns of the RG-8X feed line close to the feed point and balun. After some initial adjustments of the choke diameter and number of turns, I had my 40-meter resonance! (See Table 2.) The coil is 5$^1/_2$ turns of RG-8X with an inside diameter of 9$^1/_2$ inches (24 cm). Note that the 40-meter band minimum and 2:1 SWR range can be raised by removing part of a turn from the RF choke.

Table 2
Results with the RF Choke

Band (meters)	Minimum (MHz)	SWR Minima	2:1 SWR Range (MHz)
40	7.00	1.1	6.850 - 7.220
20	14.10	1.2	13.520 - 14.420
15	21.22	1.1	20.420 - 22.340
10	28.34	1.4	27.460 - 29.050

As is apparent, the OCFD design of K1POO is surprisingly broadband, and with a little adjustment, will cover virtually all of the 40, 20, 15 and 10-meter bands with an SWR of 2:1 or less. However, an RF choke appears to be necessary for this design to work on its fundamental frequency.

---

[3] Richard Formato, K1POO, "Off-Center-Fed Dipole Comments, Part 2," Technical Correspondence, *QST*, Oct 1996, pp 72-73.

CHAPTER THREE

MULTIBAND ANTENNAS

3-1 **A Trap Collinear Antenna**
From August 1963 *QST*

3-3 **Antenna Traps of Spiral Delay Line**
From November 1972 *QST*

3-6 **Build a Space-Efficient Dipole Antenna for 40, 80 and 160 Meters**
From July 1992 *QST*

3-8 **Trap Construction Information for Al (W8NX) Buxton's July 1992 Dipole**
From September 1992 *QST* (Technical Correspondence)

3-9 **Two New Multiband Trap Dipoles**
From August 1994 *QST*

3-13 **A Center-Fed "Zepp" for 80 and 40**
From May 1966 *QST*

3-16 **All-Band Antenna**
From March 1967 *QST* (Technical Correspondence)

3-17 **Multiband Antennas Using Decoupling Stubs**
From December 1960 *QST*

3-20 **"All-Band" Antenna**
From December 1954 *QST* (Hints & Kinks)

3-21 **Three-Band Matching System for a Forty-Meter Doublet**
From January 1975 *QST* (Hints & Kinks)

3-22 **A "Z" Antenna for the 10-160 Meter Bands**
From December 1979 *QST* (Technical Correspondence)

3-23 **Compact Multiband Antenna Without Traps**
From November 1981 *QST*

3-25 **Five Bands, No Tuner**
From June 1995 *QST*

3-26 **The NRY: A Simple, Effective Wire Antenna for 80 through 10 Meters**
From March 1993 *QST*

By Wesley M. Bell, W7QB **From *QST*, August 1963**

A Trap Collinear Antenna

Simple 3-Band Radiator with In-Phase Elements

This antenna covers the 15, 20, and 80-meter bands. On the two higher frequency bands the antenna operates with two extended half waves in phase thereby realizing some gain over the dipole operation of a conventional trap antenna.

As your *ARRL Handbook* tells you, broadside gain over a dipole approximately equivalent to doubling transmitting power may be obtained by using a center-fed antenna about 1¼ wavelengths long (extended double Zepp). Advantage of this is taken in the three-band trap antenna shown in Figure 1. The basic antenna is a dipole for 80 meters. The traps isolate sections of approximately 1¼ wavelengths for 20 and 15 meters. Since the center of a 1¼ wavelength wire is not at a current loop, wire is added in the form of a short open-wire feeder to make the total length about 1½ wavelengths, thereby bringing a current loop at the point where the system is fed by coax line. A balun is used to couple the unbalanced line to the balanced antenna system.

Trap Construction

The coil and capacitor specifications given under Figure 1 should be adequate for transmitters running at 100 watts input or less. For higher power, the inductance and capacitance values should be the same, but coils should be wound with heavier conductor, and capacitors should be of the transmitting type, such as the Centralab 850SL type. I made my own coils by wrapping a 2¼-inch form with waxed paper and winding the turns with double strands of No. 18 wire, unwinding one strand and cementing the remaining turns with strips of model-airplane glue. When the glue was dry, the completed coil was slipped off the form. At least one full extra turn should be wound to allow for pruning.

As shown in Figure 2, the capacitor is placed inside the coil, and the terminals of both capacitor and coil soldered to the heads of brass machine screws. These screws serve to hold the assembly central in a plastic waterproof container as shown in Figure 3. The container is the 1-pint size commonly found filled with chip dip, ice cream, potato salad, oysters and whatnot in grocery stores. The screws are fastened in the top cover and bottom of the container with nuts. The container is suspended from an insulator at the appropriate point in the antenna by short lengths of wire dropped from the insulator to the mounting screws where they are secured by a second set of nuts.

After mounting the traps in the containers, they should be resonated to the designated frequencies by carefully pruning the coils while checking with a grid-dip meter. The strain insulator with its wire wraps must be included, as shown in Figure 3, since the insulator capacitance is in parallel with the trap capacitor. (See *ARRL Handbook*.) As resonance is approached, final adjustment can be made by forming what is left of the last turn into a hairpin, and bend-



Figure 1—Sketch showing the approximate dimensions of the trap collinear. Wire lengths shown on left side are in terms of feet, while the approximate wavelength equivalents (electrical length) are shown on the right side. Frequencies and approximate wire lengths are for the centers of the three bands as a compromise for full-band coverage. It may be desirable to increase frequency for phone-only operation or lower frequency for c.w.-only operation.

C1, C2—25-pf. 6000-volt disk ceramic. See text.

L_1—Approx. 2 μH-4¾ turns No. 18, 2¼-inches diam., ⅜ inch long, or 5 turns No. 18, 2-inch diam., 16 tpi. See text.

L_2—Approx. 5 μH.—8 turns No. 18, 2¼-inch dia., ⅝ inch long, or 9 turns No. 18, 2-inch diam. 16 tpi. See text.

Z_1—1 to 1 balun.



Figure 2—Trap components ready to be mounted in weather-proof container.



Figure 3—The completed 21-MHz trap and its supporting insulator ready for checking with a grid-dip oscillator.

ing or twisting the hairpin to alter its inductive relationship to the main part of the coil.

Antenna Adjustment

Antenna resonance can be checked by shorting the ends of the 7-ft. open-wire line and coupling to a grid-dip meter. Initially, the wire lengths should be made a foot or so longer than the lengths shown in Figure 1. Start out with the 21-MHz sections only, anchoring the outer end of each wire section to one side of a 21-MHz trap insulator and connecting it to one side of the trap. An additional insulator should be attached temporarily between the other side of the trap insulator and the antenna-supporting rope. Then gradually shorten the wire until the grid-dip meter shows the desired resonant frequency.

Then add the second sections and traps and adjust similarly for the desired frequency in the 14-MHz band. The end sections of wire are then added and adjusted to show resonance at he desired frequency in the 3.5-MHz band.

In making the antenna adjustments, do not adjust the traps after they have once been set with the g.d.o.; change only the lengths of the wire sections. Devote plenty of time and patience to the adjustments. The job just can't be done correctly in a few minutes.

I use a center supporting pole, and the balun is enclosed in a weather-proof box mounted at the top of the pole.

Results with this antenna have been good. Using it in " inverted-vee" fashion, with one pole at the center and the ends attached to bushes, fences, clotheslines, or whatever else might be handy, I changed directions by simply walking the ends around to different positions. Without half trying, I worked 44 countries with a DX-60. I'm moving to the country soon where I plan to put up several of these antennas. 1 hope to add reflectors too. (Well, a guy can dream, can't he?)

By William J. Lattin, W4JRW **From *QST*, November 1972**

Antenna Traps of Spiral Delay Line

Most "traps" used in amateur radio multiband antennas are made of lumped inductance and capacitance in parallel. These consist of inductors made of coil stock of No. 12 or No. 14 wire and ceramic capacitors having voltage ratings up to 15,000 volts dc, which are relatively expensive. Vacuum capacitors would be the best, of course, but are also rather expensive.

Another type of trap has a capacitor made of two pieces of aluminum tubing arranged with a small-diameter tube inside a larger tube. Some have polystyrene dielectric, others air dielectric. The *ARRL Handbook* has a very complete description of these types.

Quarter-wave stubs of transmission line can be used for isolating sections of an antenna.[1] Loading coils can be used to modify the harmonic responses of a doublet to the second, third, fifth, seventh, and so on, to obtain a multiband antenna.[2] However, the use of loading coils is quite complicated if more than two bands of frequencies are desired. Traps tuned to the desired resonant frequencies make it much easier to adjust the lengths of the antenna sections, and also to obtain closer spacing between bands than can be obtained with loading coils.

Since quarter-wave sections of transmission line can be used as decoupling stubs for isolation of sections of an antenna, the idea occurred that perhaps quarter-wave sections of spiral delay line (SDL) might be used to make a very simple trap, without lumped capacitance. Spiral delay line is coaxial line with a helical inner conductor.

Construction of SDL Traps

Figure 1 shows the coil which is the helical inner conductor of the spiral delay line, along with the polystyrene tubing and end pieces for the coil, and the aluminum tube. The completed assembly is shown in the title photograph and Figure 2.

For a 28.5-MHz trap, a coil of No. 12 magnet wire was wound on a 1/2-inch rod, 37 turns, close wound. The coil was removed from the 1/2-inch rod and it sprang out to about 3/4-inch OD. The coil was 3 1/4 inches long. Enough wire was used to allow end wires straightened out to be 2 inches long on each end of the coil. Two pieces of 3/4-inch OD polystyrene rod cut 1/2-inch thick were drilled in the center to fit over the No. 12 wire ends and one was slipped over each end of the coil. This coil was placed inside a piece of 1-inch OD × 3/4-inch ID polystyrene tube 4 1/4-inches long, and a piece of 1 1/8-inch OD × 1-inch × 4 1/4-inch long aluminum tube slipped over this. The assembly was held together with No. 6-32 × 5/16-inch screws in holes drilled and tapped just far enough into the polystyrene end pieces to hold the screws in place. The short for this quarter-wave section of spiral delay line was made with a solder lug under one screw with a wire soldered between it and one end of the coil, as shown in the photographs.

The curve in the graph, Figure 3, shows the number of turns of No. 12 wire required for quarter-wave sections of the above construction. A close-wound coil of No. 12 magnet wire has approximately 12 turns per inch. The length of the assembly for a particular frequency can be determined approximately by dividing the number of turns on the coil by 12 to get the length in inches.

The traps were adjusted to frequency through the use of a grid-dip meter (checked on a receiver for accuracy of each frequency). The coil can be changed quite easily to the desired frequency by trimming turns if an extra turn or two is put on for this purpose. The coil can also be wound with spacing between turns and compressed or expanded to get the trap exactly on frequency.

After the assembly is completed and tuned to frequency, the coil can be sealed in the polystyrene tube with polystyrene ce-

Figure 1 — The parts used in the make-up of a W4JRW SDL trap.
H1, H2 — End pieces of 1/2-inch length of 3/4-inch OD Polystyrene rod with center hole for No. 12 wire.
H3 —1-inch OD × 3/4-inch ID polystyrene tube, length one inch greater than that of coil turns of L1
H4 —1 1/8-inch OD × 1-inch ID aluminum tube, length equal to that of H3.
L1— Close-wound coil of No. 12 enam. or magnet wire, 3/4-inch OD to fit inside H3. See Figure 3 and text for turns information.



---

[1] Lattin, "Multiband Antennas Using Decoupling Stubs," *QST*, December, 1960, p. 23.

[2] Lattin, "Multiband Antennas Using Loading Coils," *QST*, April, 1961, p. 43.



Figure 2—Assembly of the SDL traps. See Figure 1 and text for identification of parts not listed below.

A1—Solder lug and short length of wire assembled and soldered to short one end of H4 to one end of L1.

A2, A3—See text. The screw at A2 must not contact the wire of L1.



Figure 3—Resonant frequency of spiral-delay-line trap versus number of turns in coil.

ment or coil dope. An inert gas could be sealed inside quite easily, but there seems to be no particular advantage to this.

Trap Ratings and Performance

The thickness of the polystyrene tube used was 1/8 or 0.125 inch. The average voltage rating for polystyrene is given in various handbooks as 500 volts per mil (.001 inch). This would be 62,500 volts for the thickness of 1/8 inch. The maximum power rating of these traps has not been determined. They have been used with a 2-kW PEP ssb transmitter without any failures from either voltage breakdown or heating. Larger wire, polystyrene tubing, and aluminum tubing can be used, of course, but the curve of Figure 3 will be different. Formulas for characteristics of spiral delay lines can be found in radio handbooks and textbooks in which this type of line is described.

The resonant impedance of the traps was measured and found to be approximately 100,000 ohms. For comparison, a trap made of No. 12 wire and a ceramic capacitor gave about the same resonant impedance. Several lumped-constant 15-meter traps borrowed from triband beams were measured and values from 16,000 to 28,000 ohms were found!

The SDL traps can be used in beam antennas, of course, with suitable mechanical modifications to fit the aluminum tube used in the beam. Spiral delay line can be used for other purposes, such as matching transformers, phasing, and any place where coax line is used but short dimensions are needed. The Zo (characteristic impedance) is a function of wire size, diameter, and spacing of the helical coil, dimensions of the insulator and external aluminum tube. Measurement with an rf bridge indicated a Zo of about 250 ohms for the construction used in these traps.

Figures 4 and 5 give the dimensions of two doublet antennas experimented with here. The antenna of Figure 4 has two 7.2-MHz traps and resonates at 3.9 and 7.2 MHz. The antenna of Figure 5 has eight traps, two each for 10 meters, 15 meters, 20 meters, and 40 meters. Resonances are at 3.9, 7.2, 14.3, 21.3, and 28.6 MHz. The flat-top portions were made of No. 12 solid copper wire. The feeder used was RG-8/U. No balun was used in our experiments. It was found that if a trap was not tuned exactly to frequency, it could still be used by changing the wire lengths in the antenna adjacent to the trap to get the desired antenna resonance. An antenna shortened and using traps is sharper in resonance than a full-length doublet. This is generally very well known, but perhaps bears repetition.

SWR curves are also shown in Figures 4 and 5 for these two antennas. During measurements, the antennas were supported in the center about 30 feet high and were 20 feet high at the ends. Measurements were made at the transmitter with 100 feet of RG-8/U coax between the transmitter and the antenna.

It is advisable to support doublet antennas at the center as well as at the ends, with strain relief at the ends – a simple arrangement of a screw eye, plastic rope, and a sash weight or a brick will do.[3] Since RG-8/U coax is fairly heavy, the center support is helpful to reduce the strain on the antenna. The breaking load of No. 12 copper wire is given in handbooks as 197.5 pounds for soft or annealed wire and 261.6 pounds for medium hard-drawn wire. In a high wind any type of support such as trees, towers, push-up masts, and so on, may move a few inches, putting thousands of pounds of tension on a wire stretched between them. Is there any ham who hasn't broken a wire antenna stretched between two trees when no strain reliefs were used?

One spiral-delay-line trap was tested with a hoist and concrete blocks for weight and didn't break at 200 pounds. As the No. 12 wire used in the antenna was softer than



Figure 4—At A, dimensions for a 2-band spiral-delay-line antenna, resonant at 3.9 and 7.2 MHz (not drawn to scale). At B, the measured SWR values with this antenna.

---

[3] [EDITOR'S NOTE: To reduce wear and eventual breaking of the plastic-rope halyard, a pulley should also be used; large-diameter types sold in hardware stores as clothesline pulleys are economical and quite satisfactory.]



Figure 5—At A, the measured SWR values for a 5-band SDL antenna and at B the dimensions for this antenna.

the No. 12 magnet wires in the SDL traps, it appeared that the antenna wire would probably stretch before the wire in the traps. We have had the antenna up for almost two years, supported by three large trees, with strain reliefs at the ends. The antenna was not damaged at all by an 85-mph wind during a storm which bent the top section of our guyed crank-up tower into an inverted U shape with the triband beam hanging down. We did have one ice storm, but it wasn't severe enough to lift the strain-relief weights at the ends of the antenna.

If one desires, he can make the traps stronger by using two screws 180 degrees apart at each end, or even three screws at 120-degree spacing. Also the ends could be made of copper-weld wire soldered to the inner coil. The materials are not difficult to obtain. Most cities now have plastic supply distributors, and also aluminum tubing suppliers. The magnet wire can be obtained at a motor repair shop or from an electrical supply distributor.

By A. C. Buxton, W8NX **From *QST*, July 1992**

Build a Space-Efficient Dipole Antenna for 40, 80 and 160 Meters

A new trap design, using only RG-58 and PVC pipe, yields better space efficiency than conventional coaxial traps.

These days more than ever before, many hams who want to work the low bands need an effective antenna that fits on a small lot. I'll show you how to build a shortened dipole for 160, 80 and 40 meters using improved coaxial-cable traps that I call Super Traps. The antenna, which covers the three ham bands below 7.3 MHz, is about the same length as a fullsize 80-meter dipole. If you install the antenna as an inverted V with a 90° included angle, the baseline length is 88 feet. The antenna uses traps that are easily constructed, rugged and weatherproof. They use no exposed capacitors or inductors.

You can feed the antenna directly with balanced 75-Ω line or via a 1:1 balun with either 50- or 75-Ω coaxial cable. Feed-line length is not critical. The antenna resonates at 1.865, 3.825 and 7.225 MHz. I installed such an antenna on my lot as an inverted V, with the apex 38 feet high and the ends at about 15 feet.

As part of this project, I developed a BASIC-language computer program[1] for trap design; a listing is available from the ARRL.[2] You can use this program to design these traps for frequencies of your choice, but you don't need a computer to make the antenna described here.

Figure 1 shows the antenna layout. The antenna is made of #14 stranded wire and two pairs of coaxial traps. Construction is conventional in most respects, except for the high inductance-to-capacitance (L/C) ratio that results from the unique trap construction. Two recent *QST* articles give tips on dipole construction and feeding.[3,4]

The traps use two-layer windings of the core (dielectric and center conductor) of RG-58 coaxial cable. Coaxial cable with flexible, rugged stranded-wire center conductors is preferable to that with a more brittle solid-wire center conductor. Figure 2 shows the traps. The 3.8-MHz trap is shown with the weatherproofing cover of electrical tape removed to show the construction details.

Precautions and Trap Specifications

With this trap-winding configuration, there are two thicknesses of core dielectric material between adjacent turns, which doubles the breakdown voltage of the traps. The transformer action of the two windings gives a second doubling of the trap-voltage rating. Thus, the trap voltage rating is 5.6 kV (four times RG-58's 1.4-kV rating). Conventional coaxial-cable traps made of RG-58 have a rating of 2.8 kV.

The 7-MHz traps have 33 µH of inductance and 15 pF of capacitance, and the 3.8-MHz traps have 74 µH of inductance and 24 pF of capacitance. The trap Qs are over 170 at their design frequencies, as measured on a Boonton Q meter.

These traps are suitable for operation at the 1-kW power level. When making the traps, *do not* use RG-8X or any other foam-dielectric cable. Winding such cables on small-diameter forms causes the center conductor to migrate through the dielectric toward the inside, decreasing the breakdown rating and compromising trap performance. The core diameter also differs from that of RG-58.

Construction

Although these traps are similar in many ways to other coaxial-cable traps, the shield winding of the common coax-cable trap has been replaced by an outer winding that fits snugly into the grooves formed by the inner layer. Capacitance is reduced to 7.1 pF per



Figure 1—The shortened dipole resonates in the SSB portions of the 40, 80 and 160-meter bands. The antenna is 124 feet long.



Figure 2—The improved coaxial-cable traps use two layered windings to provide an unusually high inductance-to-capacitance ratio, higher Q, and twice the breakdown voltage of single-layer traps. The 3.8-MHz trap is shown without its protective electrical-tape wrap to show the details of trap construction. This construction method makes for simple, lightweight, rugged and weatherproof traps.

foot, compared to 28.5 pF per foot with conventional coax traps made from RG-58. Trap reactance can be up to four times greater than that provided by conventional coax-cable traps.

The coil forms are cut from PVC pipe available at plumbing-supply stores. The 7-MHz trap form is made from 2-inch-ID pipe with an outer diameter of 2.375 inches. The 3.8-MHz trap form is made from 3-inch pipe with an outer diameter of 3.5 inches. The 7-MHz trap uses a 12.3-turn inner winding and an 11.4-turn outer winding. The 3.8-MHz trap uses a 14.3-turn inner winding and a 13.4-turn outer winding. All turns are closewound. The inner-trap frequency is 7.17 MHz and the outer-trap frequency is 3.85 MHz.

If you are unable to get PVC forms of exactly the same diameters as those called for here, compensate for the effect of form-size differences by taking advantage of the fact that the number of turns varies inversely with the form diameter. Thus, if the form diameter you use is, say, 5% larger than mine, reduce the number of turns by 5%. If necessary, add or remove fractions of a turn at the end of the outer winding. If you have a computer, you can use the BASIC programs[5] to calculate the exact number of turns for other form diameters. Stay as close as you can to the prescribed diameters because too much deviation changes the loading effect of the traps. A small change in trap loading may require a change in the lengths of the tip segments beyond the traps.

Use a #30 (0.128-inch diameter) drill for the feed-through holes in the PVC coil forms. The start and end holes of the 7-MHz traps are spaced 1.44 inches center to center, measured parallel to the trap center line. The holes in the 3.8-MHz traps are 1.66 inches apart. Wind the traps with a single length of coax core. The unspliced lengths are 17.55 feet for the 7-MHz traps and 28.45 feet for the 3.8-MHz traps. These lengths include the trap pigtails and a few inches for fine tuning.

Strip the jacket from the coax. This is easily done using a wood vise with wide jaws to hold the cable while cutting the jacket longitudinally with a sharp knife or razor. The coax outer conductor (braid) is best removed by pushing (not pulling) it off.

Use electrical tape to keep the turns of the inner-layer winding closely spaced during the winding process. This counteracts the tendency of the tension in the outer-layer winding to spread the inner–layer turns. Stick the tape strips directly to the coil form before winding and then tightly loop them over and around the inner layer before winding the outer layer. Use six or more tape strips for each trap.

If possible, check the resonant frequencies of your traps with a dip meter. Try to maintain an accuracy of 50 kHz or better.

For low-noise reception, erect the antenna as close to horizontal as possible. If you let the ends of the antenna droop toward the ground, as I have done with my inverted-V installation, you may have to accept a somewhat higher noise level in the interest of structural simplicity and reduced baseline length. Some feel that the inverted V configuration is better for DXing than a horizontal dipole at the same height. For an inverted V with a 90° included angle (legs that slope downward at 45°), you'll need a minimum apex height of about 55 feet and a baseline length of 88 feet. Get the apex as high as you can and keep the ends at least 10 feet above the ground for safety.

Configuration and Performance Trade-Offs

You seldom get something for nothing. This antenna proves no exception to that rule. As with all trap dipoles, this one has less-than-ideal bandwidth due to the loading effect of the traps. This is the price paid for multiband coverage and physical shortening. This antenna covers 65 kHz of 160 meters, 75 kHz of 80 meters and the entire 40-meter band with SWRs under 2:1. The bandwidth limitations on 160 and 80 meters can be largely offset with an antenna tuner.

It is also important to recognize that the traps are used in low-current portions of the antenna, minimizing I^2R trap losses. A relatively high radiation resistance is therefore also retained.

Good luck with your low-band antennas!

Notes

[1] I wrote the program in GWBASIC 3.2. It uses generic BASIC commands and can be easily converted for use with computers other than IBM PCs and compatibles.

[2] For a copy of the BASIC program, send a business-size SASE to the ARRL Technical Department Secretary, 225 Main St, Newington, CT 06111-1494. Request the July 1992 *QST* BUXTON BASIC PROGRAM listing.

[3] J. Healy, "Antenna Here is a Dipole," *QST*, Jun 1991, pp 23-26.

[4] J. Healy, "Feeding Dipole Antennas," *QST*, Jul 1991, pp 22-24.

[5] See note 2.

From *QST*, September 1992 (Technical Correspondence)

Trap Construction Information for Al (W8NX) Buxton's July 1992 Dipole

Several readers have written asking for clearer instructions on how to build the antenna traps described by A. C. Buxton, W8NX, in his July 1992 *QST* article, "Build a Space-Efficient Dipole Antenna for 40, 80 and 160 Meters." For those of you who didn't write, but aren't sure how to build the traps, here's what you need to know.

The trap-winding technique is deceptively simple. Each trap is simply comprised of one winding atop another, wound in the same direction. First, drill four holes in the form for wire entry and exit, as described in July *QST*. Starting from inside the form, pass the wire through the hole labeled "1" in Figures 1 and 2. Wind a layer of the inner conductor on the form. Then, run the wire end down through a second hole into the form (just below the one labeled "EXIT" in Figure 2) and, inside the form, bring the wire back to a point adjacent to where the first winding started. Bring the wire up through the hole marked "2" and wind another layer on top of the first, in the same direction as the first winding. Pass the wire down through the hole labeled "EXIT" and you're done. The tape you see in the photos, described in the article, helps hold the bottom winding's turns together and the top winding in place as you're assembling the trap.

The wires passing through holes in the form are strain-relieved, but use the two mounting holes you drilled in the form to support the trap, just to be on the safe side.
–Rus Healy, NJ2L


Figure 1—An inside view of a W8NX two-layer trap shows how the windings enter and exit the form. Two holes at each end of the form pass the windings into and out of the form.



Figure 2—An outside view of a partially assembled W8NX trap. The bottom winding starts at hole "1" and reenters the form just below the "EXIT" hole. The wire then comes back through the inside of the form to hole "T," and is used to make a second winding atop the first. It reenters the form at the "EXIT" hole.

By Al Buxton, W8NX **From *QST*, August 1994**

Two New Multiband Trap Dipoles

W8NX details a new coax trap design used in two multiband antennas; one covering 80, 40, 20, 15 and 10 meters, and the other covering 80, 40, 17 and 12 meters.





Over the last 60 or 70 years, amateurs have used many kinds of multiband antennas to cover the traditional HF bands. The availability of the 30, 17 and 12-meter bands has expanded our need for multiband antenna coverage. A fortunate few have the space and resources for multiband antennas like rhombics or long Vs, but many hams have employed inverted-L long wires or parallel dipoles. Old-timers will recall the offcenter-fed *Windom* of the '30s–the first version using a single-wire transmission line, and the later design using two-wire feed line. Over the years, random-length dipoles with open-wire feeders and associated tuners have been used successfully as multiband antennas. The G5RV multiband antenna is a specialized example of this approach.[1]

The *log periodic array* represents a kind of brute-force approach to the goal of achieving coverage of multiple HF ham bands. It seems inefficient because of the large gaps between our relatively narrow amateur HF bands.

Over the last few decades, two factors have affected the development of multiband antennas—the popularity of low-impedance (usually 50-Ω) coaxial feed lines, and the appearance of untuned, 50-Ω solid-state amplifiers. The impedance of an antenna is relatively low only at its fundamental frequency and at odd-order harmonics. Although antenna tuners are often necessary to resonate an antenna system, the quest for expanded multiband coverage with simple antennas continues.

At the end of the 1930s, a different technological approach appeared in the form of resonant traps in antennas. The *Mims Signal Squirter* is the grandfather of modern day tribanders.[2] This article discusses in detail an innovative trap design employed in two multiband dipoles.

One W8NX Trap Design—Two Multiband Dipoles

Two different antennas are described here. The first covers 80, 40, 20, 15 and 10 meters, and the second covers 80, 40, 17 and 12 meters. Each uses the same type of W8NX trap—connected for different modes of operation—and a pair of short capacitive stubs to enhance coverage. The new W8NX coaxial-cable traps have two different modes: a high- and a low-impedance mode. The inner-conductor windings and shield windings of the traps are connected in series in the conventional manner for both modes. However, either the low- or high-impedance point can be used as the trap's output terminal. For low-impedance trap operation, only the center conductor turns of the trap windings are used. For high-impedance operation, all turns are used, in the conventional manner for a trap. The short stubs on each antenna are strategically sized and located to permit more flexibility in adjusting the resonant frequencies of the antenna.

Figure 1 shows the configuration of the 80, 40, 20, 15 and 10-meter antenna. The radiating elements are made of #14 stranded copper wire. The element lengths are the wire span lengths in feet. These lengths do not include the lengths of the pigtails at the balun, traps and insulators. The 32.3-foot-long inner 40-meter segments are measured from the eyelet of the input balun to the tension relief hole in the trap coil form. The 4.9-foot segment length is measured from the tension relief hole in



Figure 1—A W8NX multiband dipole for 80, 40, 20, 15 and 10 meters. The values shown (123 pF and 4 µH) for the coaxial-cable traps are for parallel resonance at 7.15 MHz. The low-impedance output of each trap is used for this antenna.



Figure 2—A W8NX multiband dipole for 80, 40, 17 and 12 meters. For this antenna, the high-impedance output is used on each trap. The resonant frequency of the traps is 7.15 MHz.

the trap to the 6-foot stub. The 16.1-foot outer-segment span is measured from the stub to the eyelet of the end insulator. The coaxial-cable traps are wound on PVC pipe coil forms and use the low-impedance output connection. The stubs are 6-foot lengths of 1/8-inch stiffened aluminum or copper rod hanging perpendicular to the radiating elements. The first inch of their length is bent 90° to permit attachment to the radiating elements by large-diameter copper crimp connectors. Ordinary #14 wire may be used for the stubs, but it has a tendency to curl up and may tangle unless weighed down at the end. I recommend that you feed the antenna with 75-Ω coax cable using a good 1:1 balun.

This antenna may be thought of as a modified W3DZZ antenna[3] (shown for many years in various ARRL publications) with the addition of capacitive stubs. The length and location of the stub give the antenna designer two extra degrees of freedom to place the resonant frequencies within the amateur bands. This additional flexibility is particularly helpful to bring the 15 and 10-meter resonant frequencies to more desirable locations in these bands. The actual 10-meter resonant frequency of the W3DZZ antenna is somewhat above 30 MHz, pretty remote from the more desirable low frequency end of 10 meters.



Figure 3—Schematic for the W8NX coaxial-cable trap. RG-59 is wound on a 2³/₈-inch OD PVC pipe.

Figure 2 shows the configuration of the 80, 40, 17 and 12-meter antenna. Notice that the capacitive stubs are attached immediately outboard after the traps and are 6.5 feet long, 0.5 foot longer than those used in the other antenna. The traps are the same as those of the other antenna, but are connected for the high-impedance output mode. Since only four bands are covered by this antenna, it is easier to fine tune it to precisely the desired frequency on all bands. The 12.4-foot tips can be pruned to a particular 17-meter frequency with little effect on the 12-meter frequency. The stub lengths can be pruned to a particular 12-meter frequency with little effect on the 17-meter frequency. Both such pruning adjustments slightly alter the 80-meter resonant frequency. However, the bandwidths of the antennas are so broad on 17 and 12 meters that little need for such pruning exists. The 40-meter frequency is nearly independent of adjustments to the capacitive stubs and outer radiating tip elements. Like the first antennas, this dipole is fed with a 75-Ω balun and feed line.

Figure 3 shows the schematic diagram of the traps. It explains the difference between the low and high-impedance modes of the traps. Notice that the high-impedance terminal is the output configuration used in most conventional trap applications. The low-impedance connection is made across only the inner conductor turns, corresponding to one-half of the total turns of the trap. This mode steps the trap's impedance down to approximately one-fourth of that of the high-impedance level. This is what allows a single trap design to be used for two different multiband antennas.

Figure 4 is a drawing of a cross-section of the coax trap shown through the long axis of the trap. Notice that the traps are conventional coaxial-cable traps, except for the added low-impedance output terminal. The traps are 8³/₄ close-spaced turns of RG-59 (Belden 8241) on a 2³/₈-inch-OD PVC pipe (schedule 40 pipe with a 2-inch ID) coil form. The forms are 4¹/₈ inches long. Trap resonant frequency is very sensitive to the outer diameter of the coil form, so check it carefully. Unfortunately, not all PVC pipe is made with the same wall thickness. The trap frequencies should be checked with a dip meter and general coverage receiver and adjusted to within 50 kHz of the 7150 kHz resonant frequency before installation. One inch is left over at each end of the coil forms to allow for the coax feed-through holes and holes for tension-relief attachment of the antenna radiating elements to the traps. Be sure to seal the ends of the trap coax cable with RTV sealant to prevent moisture from entering the coaxial cable.

Also, be sure that you connect the 32.3-foot wire element at the start of the inner conductor winding of the trap. This avoids detuning the antenna by the stray capacitance of the coaxial-cable shield. The trap output terminal (which has the shield stray capacitance) should be at the outboard side of the trap. Reversing the input and output terminals of the trap will lower the 40-meter frequency by approximately 50 kHz, but there will be negligible effect on the other bands.

The title-page photos show a coaxial-cable trap. Details of the trap installation are shown in Figure 5. This drawing applies specifically to the 80, 40, 20, 15 and 10-meter antenna, which uses the low-impedance trap connections. Notice the lengths of the trap pigtails: 3 to 4 inches at each terminal of the trap. If you use a different arrangement, you must modify the span lengths accordingly. All connections can be made using crimp connectors rather than by soldering. Access to the trap's interior is attained more easily with a crimping tool than with a soldering iron.

Antenna Patterns

The performance of both antennas has



Figure 4—Construction details of the W8NX coaxial-cable trap.



Figure 5—Additional construction details for the W8NX coaxial-cable trap.

been very satisfactory. I am currently using the 80,40, 17 and 12-meter version because it covers 17 and 12 meters. (I have a tribander for 20, 15 and 10 meters.) The radiation pattern on 17 meters is that of 3/2-wave dipole. On 12 meters, the pattern is that of a 5/2-wave dipole. At my location in Akron, Ohio, the antenna runs essentially east and west. It is installed as an inverted V, 40 feet high at the center, with a 120° included angle between the legs. Since the stubs are very short, they radiate little power and make only minor contributions to the radiation patterns. The pattern has four major lobes on 17 meters, with maxima to the northeast, southeast, southwest, and northwest. These provide low-angle radiation into Europe, Africa, South Pacific, Japan and Alaska. A narrow pair of minor broadside lobes provides north and south coverage into Central America, South America and the polar regions.

There are four major lobes on 12 meters, giving nearly end-fire radiation and good low-angle east and west coverage. There are also three pairs of very narrow, nearly broadside, minor lobes on 12 meters, down about 6 dB from the major end-fire lobes. On 80 and 40 meters, the antenna has the usual figure-8 patterns of a half-wave-length dipole. I have some pattern distortion and input impedance effects from aluminum siding on my house. Nevertheless, DX is easily workable on either of these antennas using a 100-W transceiver, when the high-frequency bands are open.

Both antennas function as electrical half-wave dipoles on 80 and 40 meters with a low SWR. They both function as odd harmonic current-fed dipoles on their other operating frequencies, with higher, but still acceptable, SWR. The presence of the stubs can either raise or lower the input impedance of the antenna from those of the usual third and fifth harmonic dipoles. Again, I recommend that 75-Ω, rather than 50-Ω, feed line be used because of the generally higher input impedances at the harmonic operating frequencies of the antennas.

The SWR curves of both antennas were carefully measured. A 75 to 50-Ω transformer from Palomar Engineers was inserted at the junction of the 75-Ω coax feed line and my 50-Ω SWR bridge. The transformer prevents an impedance discontinuity, with attendant additional undesired line reflections appearing at the 75 to 50-Ω junction. The transformer is required for accurate SWR measurement if a 50-Ω SWR bridge is used with a 75-Ω line. No harm is done to any equipment, however, if the transformer is omitted. Most 50-Ω rigs operate satisfactorily with a 75-Ω line, although this requires different tuning and load settings in the final output stage of the rig or antenna tuner. I use the 75 to 50-Ω transformer only when making SWR measurements and at low power levels. The transformer is rated for 100 W, and when I run my 1-kW PEP linear amplifier the transformer is taken out of the line. (I hope my absent-mindedness doesn't catch up with me some day!)

Figure 6 gives the SWR curves of the 80, 40, 20, 15 and 10-meter antenna. Minimum SWR is nearly 1:1 on 80 meters, 1.5:1 on 40 meters, 1.6:1 on 20 meters, and 1.5:1 on 10 meters. The minimum SWR is slightly below 3:1 on 15 meters. On 15 meters, the stub capacitive reactance combines with the inductive reactance of the outer segment of the antenna to produce a resonant rise that raises the antenna input resistance to about 220 Ω, higher than that of the usual 3/2-wavelength dipole. An antenna tuner may be required on this band to keep a solid-state final output stage happy under these load conditions.

Figure 7 shows the SWR curves of the 80, 40, 17 and 12-meter antenna. Notice the excellent 80-meter performance with a



Figure 6—Measured SWR curves for an 80, 40, 20, 15 and 10-meter antenna, installed as an inverted-v with 40-ft apex and 120° included angle between legs.



Figure 7—Measured SWR curves for an 80, 40, 17 and 12-meter antenna, installed as an inverted-v with 40-ft apex and 120° included angle between legs.

Table 1
Trap Q

Frequency (MHz)	3.8	7.15	14.18	18.1	21.3	24.9	28.6
High Z out (Ω)	101	124	139	165	73	179	186
Low Z out (Ω)	83	103	125	137	44	149	155

Table 2A
Trap Loss Analysis: 80, 40, 20,15, 10-Meter Antenna

Frequency (MHz)	3.8	7.15	14.18	21.3	28.6
Radiation Efficiency (%)	96.4	70.8	99.4	99.9	100.0
Trap losses (dB)	–0.16	–1.5	–0.02	–0.01	–0.003

Table 2B
Trap Loss Analysis: 80, 40, 17, 12-Meter Antenna

Frequency (MHz)	3.8	7.15	18.1	24.9
Radiation Efficiency (%)	89.5	90.5	99.3	99.8
Trap losses (dB)	–0.5	–0.4	–0.03	–0.006

nearly unity minimum SWR in the middle of the band. The performance approaches that of a full-size 80-meter wire dipole. The short stubs and the very low inductance traps shorten the antenna somewhat on 80 meters. Also, observe the good 17-meter performance, with the SWR being only a little above 2:1 across the band.

But notice the 12-meter SWR curve of this antenna, which shows 4:1 SWR across the band. The antenna input resistance approaches 300 Ω on this band because the capacitive reactance of the stubs combines with the inductive reactance of the outer antenna segments to give resonant rises in impedance. These are reflected back to the input terminals. These stub-induced resonant impedance rises are similar to those on the other antenna on 15 meters, but are even more pronounced.

Too much concern must not be given to SWR on the feed line. Even if the SWR is as high as 9:1, *no destructively high voltages will exist on the transmission line.* Recall that transmission-line voltages increase as the square root of the SWR in the line. Thus, 1 kW of RF power in 75-Ω line corresponds to 274 V line voltage for a 1:1 SWR. Raising the SWR to 9:1 merely triples the maximum voltage that the line must withstand to 822 V. This voltage is well below the 3700-V rating of RG- 11, or the 1700-V rating of RG-59, the two most popular 75-Ω coax lines. Voltage breakdown in the traps is also very unlikely. As will be pointed out later, the operating power levels of these antennas are limited by RF power dissipation in the traps, not trap voltage breakdown or feed-line SWR.

Trap Losses and Power Rating

Table 1 presents the results of trap Q measurements and extrapolation by a two-frequency method to higher frequencies above resonance. I employed an old, but recently calibrated, Boonton Q meter for the measurements. Extrapolation to higher frequency bands assumes that trap resistance losses rise with skin effect according to the square root of frequency, and that trap dielectric losses rise directly with frequency. Systematic measurement errors are not increased by frequency extrapolation. However, random measurement errors increase in magnitude with upward frequency extrapolation. Results are believed to be accurate within 4% on 80 and 40 meters, but only within 10 to 15% at 10 meters. Trap Q is shown at both the high- and low-impedance trap terminals. The Q at the low-impedance output terminals is 15 to 20% lower than the Q at the high-impedance output terminals.

I computer-analyzed trap losses for both antennas in free space. Antenna-input resistances at resonance were first calculated, assuming lossless, infinite-Q traps. They were again calculated using the Q values shown in Table 1. The radiation efficiencies were also converted into equivalent trap losses in decibels. Table 2A summarizes the trap loss analysis for the 80, 40, 20, 15 and 10-meter antenna and Table 2B for the 80, 40, 17 and 12-meter antenna.

The loss analysis shows radiation efficiencies of 90% or more for both antennas on all bands except for the 80, 40, 20, 15 and 10-meter antenna when used on 40 meters. Here, the radiation efficiency falls to 70.8%. A 1-kW power level at 90% radiation efficiency corresponds to 50-W dissipation per trap. In my experience, this is the trap's survival limit for extended key-down operation. SSB power levels of 1 kW PEP would dissipate 25 W or less in each trap. This is well within the dissipation capability of the traps.

When the 80, 40, 20, 15 and 10-meter antenna is operated on 40 meters, the radiation efficiency of 70.8% corresponds to a dissipation of 146 W in each trap when 1 kW is delivered to the antenna. This is sure to burn out the traps—even if sustained for only a short time. Thus, the power should be limited to less than 300 W when this antenna is operated on 40 meters under prolonged key-down conditions. A 50% CW duty cycle would correspond to a 600-W power limit for normal 40-meter CW operation. Likewise, a 50% duty cycle for 40-meter SSB corresponds to a 600-W PEP power limit for the antenna.

I know of no analysis where the burnout wattage rating of traps has been rigorously determined. Operating experience seems to be the best way to determine trap burn-out ratings. In my own experience with these antennas, I've had no traps burn out, even though I operated the 80, 40, 20, 15 and 10-meter antenna on the critical 40-meter band using my AL-80A linear amplifier at the 600-W PEP output level. I have, however, made no continuous, keydown, CW operating tests at full power purposely trying to destroy the traps!

Summary

Some hams may suggest using a different type of coaxial cable for the traps. The dc resistance of 40.7 Ω per 1000 feet of RG-59 coax seems rather high. However, I've found no coax other than RG-59 that has the necessary inductance-to-capacitance ratio to create the trap characteristic reactance required for the 80, 40, 20, 15 and 10-meter antenna. Conventional traps with wide-spaced, open-air inductors and appropriate fixed-value capacitors could be substituted for the coax traps, but the convenience, weatherproof configuration and ease of fabrication of coaxial-cable traps is hard to beat.

Notes

[1] L. Varney, "The G5RV Multiband Antenna... Up-to-Date," *The ARRL Antenna Compendium, Vol. 1*, p 86.

[2] M. Mims, "The Mims Signal Squirter," *QST*, Dec 1939, p 12.

[3] "Five Band Antenna," *The ARRL Antenna Book*, 16th Edition, pp 7-10 to 7-11.

By William C. Gann, W4NML **From *QST*, May 1966**

A Center-Fed "Zepp" for 80 and 40

Fast QSY for the Phone-C.W. Operator

The center-fed "Zepp" antenna is reviewed by W4NML, showing how complete coverage of a single band is made easy by using old concepts. Although the author shows how to use the Zepp on 80 and 40, only, the system can be used from 80 through 10 meters by employing an all-band transmatch.

Multiband antennas fed with resonant feeders were very popular in the pre-coax cable days. This article is presented to review a good, but seemingly forgotten system. This antenna should be of interest to traffic and contest operators, and to the casual operator who likes to use both the c.w. and phone portions of the 80- and 40-meter bands.

Our section s.s.b. net meets on 3965 kHz and the c.w. net meets on 3575 kHz. Many schemes were tried to make one antenna usable on both ends of the band so that a low s.w.r. could be maintained while securing efficient operation at the different frequencies. None of the antennas tried would permit an excursion of more than 300 kHz without a serious s.w.r. problem between the transmitter and the line. Getting from 80 to 40 meters with such an antenna was even more perplexing. The writer's dilemma was finally solved by the installation of the old reliable center-fed Zepp antenna.

Choosing the Dimensions

In order to use the antenna on 40, 75, and 80 meters, tuned feeders are required[1]. So that the feeders can be matched to the transmitter, a transmatch is used at the "shack" end of the line. Parallel tuning is used to minimize the complexity of the transmatch. This requires that the transmission line presents a high impedance to the transmatch on both bands.

The charts in the handbooks did not give a set of Zepp antenna dimensions that were suitable for the author's installation. Because of the existing tower, which would permit the antenna to be supported at the 50-foot level, and because the ham shack was adjacent to the tower, the prescribed feeder lengths were not practical. A graph was plotted to show the frequency extremes to which the antenna would be tuned, showing the minimum and maximum impedance points across the bands. It was determined that the combined length of one leg of the feed line and one section of the dipole would be 114 feet.[2] A length of 53 feet was used for the feed line and each leg of the driven element was cut to 61 feet.

To broaden the antenna's response, the driven element's effective area was made larger by paralleling two lengths of No. 12 copper wire as shown in Figures 1 and 2. With this arrangement, the Q of the antenna is lower, permitting the operator to QSY approximately 200 kHz without readjusting the transmatch.

Construction Notes

The driven element and the feed line are made from No. 12 copper wire. The 4-inch wide ceramic spreaders used to hold the feeder wires apart are made by the E. F. Johnson Co. Light-weight poly spacers are used to spread the driven-element wires and are sold as TV "clothespins" by the Telco Co. (Figure 2). All of the spreaders are attached to the No. 12 wire by short pieces of No. 18 copper wire. The distance between the spreaders is 4 feet for both the driven element and the feed line.

Sections of 1 × 4-inch lumber are used to hold the feeders away from the steel tower (Figure 3). Each piece is 24 inches long, notched at one end, and is fastened to the tower with U-bolts. Porcelain telephone-type insulators are attached to the feed-line end of each board, offering low-loss anchor



Figure 1—Layout of the 2-band Zepp antenna. Dimensions for each part of the antenna are shown. Feed point is anchored to one of the wooden support arms (See Figure 3).

---

[1] Center-fed Antennas, *A.R.R.L. Antenna Book*, Chapter 6.

[2] This length is generally 145 feet for operation in the 3.5- to 30-MHz range when the antenna is mounted horizontally (no droop), away from steel towers, and with a singlewire driven element.–*Editor*



Figure 2—Details showing how the driven element spreaders are attached to the No. 12 wire. No. 18 copper wire is wrapped above and below each spreader to hold it in place.



Figure 4—Schematic diagram of the W4NML transmatch.

C_1—100 pf. per section transmitting variable. (Split stator type with 0.175-inch spacing between plates.)

C_2—300-pf. variable capacitor(0.078 spacing or greater).

J_1—SO-239 coax connector.

L_1—56 turns, 3-inch diam., 8 turns per inch coil. S_1 taps are 9 turns from ends of coil for 80 meters, and are 22 turns from ends of coil for 40 meters. S_2 taps are 5 turns from ends of coil for 80 meters and 17 turns from ends of coil for 40 meters. (Air Dux 2408T or Polycoils 1779 usable.)

L_2—8 turns of Air Dux 2408T (center portion of L_1).

S_1, S_2—Ceramic rotary, 2 poles, 2 positions, 2 sections.

points for the transmission line. The uppermost support arm, at the 50-foot level, is used as a mount for the center of the driven element.

The far ends of the antenna are supported by 30-foot TV masts. A pulley and halyard arrangement is used for raising and lowering the ends of the antenna. Because the end supports are not as high as the feed point of the antenna, the dipole has a slight droop, but this does not seem to impair the performance.

The transmission line is brought into the operating position by means of feed-through insulators, mounted on a plywood strip which fits under a partially raised window. Insulated No. 12 house wire is used between the feed-through insulators and the transmatch.

Transmatch

Ideas for the author's tuner (Figure 4) were taken from the excellent transmatch article by McCoy.[3] Band changing is made possible by a large ceramic switch (origin unknown) which was obtained at a hamfest. An identical switch is used for selecting the taps for the feed line (Figure 5). Coil L_1 contains 56 turns of No. 14 wire, is 3 inches in diameter, and has 8 turns-per-inch (Air Dux 2408T). A stationary link, L_2, at the center of L_1, contains 8 turns of No. 14 wire and is a part of the Air Dux coil from which L_1 is made. The link is tuned with a 300-pf. variable capacitor. The author did not have a unit of the correct type, so two 150-pf. capacitors were parallel-connected (mounted under the chassis). Capacitor C_1 is a 100-pf-.per-section variable

---

[3] *QST*, July 1965.



Figure 3—Wooden support arms hold the transmission line away from the tower. Telephone-type insulators are mounted at the end of each board to make the feed line secure.



Figure 5—Top-chassis view of the transmatch. C_2 is mounted under the chassis.

with wide spacing. To give L_1 some rigidity, it is mounted on a plexiglass tube which is supported by the frame of C_1 with stand-off insulators.

Results

While using clip leads, the correct tap points for the feeders were found by operating the transmitter through a Collins wattmeter and tuning C_1 and C_2 for zero reflected power. The transmatch permitted the transmitter to "see" 50 ohms in any part of either band. After establishing the correct tap points for the feed line, permanent connections were made between L_1 and the switches.

Next, the tuner was used with the 30L-1 amplifier at an output level of 700 watts. After a 30-minute QSO, no evidence of coil heating could be detected.

When compared to other antenna systems used by the author, the new skywire showed improved performance. It was believed that some sacrifice in efficiency would result from changing to the new antenna. Happily, it was found that we could have our cake and eat it too! Extended use indicated that the performance was, indeed, better than with previous antennas used.

I wish to thank three friends for their help in making this article possible: K4WWN for his tower climbing and photography work, K4ADK for building the transmatch cabinet, and Roy LeCrone for additional darkroom and photographic assistance.

Although this antenna system is an old standard, it may be the answer to your QSY problems. The cost is nominal and the results are most rewarding.

From *QST*, March 1967 (Technical Correspondence)

All-Band Antenna

With reference to the article on a Center-fed Zepp for 80 and 40 in May 1966 *QST*:

I set out to accomplish several things with an antenna to be installed on a California lot which runs east-west:

1) One pole.
2) No guys.
3) Good for short skip up and down the West Coast on 80, 75 and 40 meters.
4) Throw lobes across populated DX areas on 20 and 15 meters with a fairly low radiation angle.
5) Allow some onmidirectional DX on 40 meters.
6) Keep away from anything with critical antenna length or critical tuning.
7) Minimum cost.

Figure 1 shows the arrangement I ended up with. Results have been exceptional for a simple system of low height.

I use No. 14 wire for the antenna. The feeders are also No. 14. The center is mounted on an unguyed wooden pole about 34 feet high. Each section of the antenna is 65 feet long and the ends are only 14 feet high. Thirty-foot feeders are used with series tuning on 80 and 40 and parallel tuning on 20, 15 and 10 meters. Loading from 3.5 to 30 MHz is excellent and not at all critical in tuning. The fact that the feeders are less than 1/8 wave on 80 allows reactance to be tuned out in the feeder-tuning arrangement on that band. The antenna is a bit long for the high end of 75 meters, but tuning there is good (this length was picked because of the slightly longer physical length required on the upper bands for end effect).

I have the antenna itself running east-west, giving some directivity north-south for QSOs with short skip up and down the west coast on 80 and 40 meters (it was found in an earlier antenna . . . vertical . . . that a vertical was not satisfactory for high-radiation-angle short-skip operation). On 20 and 15 the lobes tend to cut across major population DX areas. The tilt of the wire, which lowers the vertical radiation angle plus apparently some lobe addition, seems to give better results in the desired DX directions on 20 and 15 meters than 33-feet-high half-wave horizontal antennas oriented in the correct directions. Quite a bit of omnidirectional DX has been worked on 40 meters, undoubtedly because of the antenna tilt. DX operation on 15-meter c.w. has been really exceptional. Quite often I hook a DX station through the pileup when local beam stations miss (power output is about 150 watts). Since 10 has opened up I have used the antenna quite a bit on that band with very good results for both North American and DX contacts.

As a result of playing around on 160 meters with the bottom of the feeders connected together and working the antenna as a " T " against ground, I decided to see what happened when it was operated as a top-loaded vertical on 80 and 40 meters. The feeders were tied together and the antenna worked against a ground consisting of two 8-foot rods in water-soaked earth. On 80 this places the maximum-current point directly at the top of the vertical section (1/8 wave long) and on 40 gives the effect of a 1/4-wave vertical with maximum current at the bottom. This arrangement gave much better results than the Zepp where low-angle radiation was required, and less effective results than the Zepp where medium- and high-angle radiation was required. An exception is directly off the ends on 80 meters, where the vertical and Zepp seem to give the same results. The Zepp arrangement is therefore now used for short and medium skip on 80 and 40 and the vertical arrangement for long skip or DX. In receiving, the signal-to-noise ratio decreases greatly with the vertical arrangement (vs horizontal), thus somewhat offsetting the overall advantage of the vertical for DX operation. If this condition is extreme, I use the Zepp for receiving and the vertical for transmitting, for DX operation. It appears that the vertical transmitter and horizontal receiver is by far the best DX arrangement for metropolitan areas, but most likely the vertical for both would be best for rural areas where the QRN is lower. – *Dave Hardacker, W6PIZ*



Figure 1–The W6PIZ all-band antenna. Power is applied through a series- or parallel-tuned link-coupled matching circuit at X-X for operation on 3.5 through 30 MHz (see text). For 2 MHz, and also for certain types of work on 3.5 and 7 MHz, points X-X can be connected together and the antenna worked against ground.

By William J. Lattin, W4JRW **From *QST*, December 1960**

Multiband Antennas Using Decoupling Stubs

Substituting Transmission Line Sections for Lumped-Constant Traps

Since W4JRW obtained a patent on this multi-frequency antenna system nearly ten years ago we can't call it "new," but at least it should be welcome news to those seeking a simple way to get good radiation on several bands, Shorted 1/4-wavelength stubs provide r.f. insulation and also serve as part of the antenna.

Since amateurs usually desire to operate on more than one band, several methods have been devised to use a single antenna on several bands. The earliest arrangements employed various combinations of feeder lengths, antenna lengths, and series or parallel tuning of the coupling circuit. Later on, the use of parallel-tuned "traps" with lumped constants which act as insulators at a particular frequency was invented.[1] A practical arrangement of this system for amateur use was developed[2] and is in rather wide use.

It is well known that the parallel-tuned circuit and quarter-wavelength shorted stub of Figure 1 are very similar electrically. Both configurations show a high impedance across points A and B. However, if a stub is connected to an antenna in this manner it does not act as an insulator but rather as a phase changer. The collinear antenna uses such stubs to operate a series of halfwave sections in phase.

There is a different connection possible for the stub, that is from A to C, which will result in insulator action or decoupling in an antenna.[3] For instance, shorted stubs a quarter wavelength long at 28 MHz can be attached to the ends of a 28 MHz dipole as in Figure 2. The 28 MHz dipole is effectively isolated or decoupled from the balance of the antenna which can be made long enough to resonate at 14, 7 or 3.5 MHz. If another pair of stubs is added for 14 MHz,



Figure 1—A parallel-tuned circuit has a high impedance at its resonant frequency, and so does a ¼-wavelength shorted transmission line.



Figure 2—A two-band antenna for 28 MHz and some lower frequency. The center portion is an ordinary 10-meter dipole. The shorted stubs are ¼ wavelength long at 28 MHz and look like an open circuit at that frequency when connected to the dipole as shown. Extensions on the ends of the stubs can be used to resonate the antenna at any frequency less than half of 28 MHz.



Figure 3—Construction and dimensions of an antenna for 10 and 20 meters using 300-ohm tubular Twin-Lead for both the dipole and stubs. Either a 50- or 75-ohm transmission line can be connected at the center of the dipole.

---

[1] Morgan, "A Multifrequency Tuned Antenna System," *Electronics*, August, 1940.

[2] Buchanan, "The Multimatch Antenna System," *QST*, March, 1955.

[3] Lattin, Patent No. 2,535,298.



Figure 4—Dimensions of stub-decoupled antennas for 10, 20 and 40 meters and 10, 20, 40 and 80 meters made of tubular Twin-Lead. Either antenna can also be used on 15 meters where the 40-meter section is 3/4 wavelength long.



Figure 5—From top to bottom, SWR characteristics of the antennas shown in Figures 3, 4A and 4B. A 50-ohm coaxial transmission line was used, and the measurements were made with a Micromatch.



Figure 6—A stub-decoupled antenna for 40 and 80 meters. In this case wires must be hung from the ends of the 40-meter dipole to resonate the antenna in that band.

there will be isolation at both 28 and 14 MHz, and a 10-20-40-meter or 10-20-80-meter antenna can be made.

The stubs can be made of open-wire line, Twin-Lead, or coax. Their lengths can be found from the formula

$$\text{Length (feet)} = \frac{246 \times \text{Velocity Factor}}{\text{Frequency (MHz)}}$$

The over-all length of an antenna containing decoupling stubs will be somewhat less than the figure given by the usual formula for a half-wavelength dipole — *Length* (feet) = 468/*Frequency* (MHz). For instance, an antenna for 10 and 20 meters must be 29 feet, 10 inches long for resonance at the lower frequency, whereas the formula gives a length of 33 feet.

If open line with a velocity factor of nearly unity is used for the stubs, the over-all length of a two-band antenna would be nearly a full free-space wavelength at the higher frequency and the whole antenna would resonate at something *less* than half that frequency. Very fortunately, the velocity factor of 300-ohm tubular Twin-Lead (0.8) gives such lengths for the stubs that, in most cases, adding the stub makes the antenna resonate at just half the original frequency.

Figure 3 shows how tubular Twin-Lead can be used for the antenna itself as well as the stubs and includes dimensions for 10- and 20-meter operation. The foam-filled type of Twin-Lead is recommended to keep out moisture. Lengths for three- and four-band antennas using the same construction are given in Figure 4. Figure 5 indicates the standing-wave ratios observed across various bands when these antennas were fed with 50-ohm coax.

The antenna of Figure 6 can be used when only 40- and 80-meter operation is desired. Since the 40-meter portion is not made up of stubs it must be longer than the antenna of Figure 4A. However, the isolating stubs must still be 1/4 wavelength long (allowing for velocity factor), and the whole antenna would resonate at a frequency below 3.5 MHz if the stubs were simply added to the ends of the 7-MHz dipole. To get around this, the dipole is shortened until the whole antenna tunes to 80 meters. Then resonance at 40 meters is restored by adding extra lengths of wire at the stub junctions. These wires are short and can just hang down from the antenna as shown.

Any of the antennas which will operate on 40 meters can be used on 15 meters as the 40-meter stubs will be approximately 3/4 wavelength long and will provide decoupling. The result is equivalent to operating a 7-MHz dipole at three times its resonant frequency, and we have found the s.w.r. is usually not lower than 3 to 6 when using 40-meter antennas of any type on 15 meters[4].

The power rating of the antenna will depend on the insulation at the stub junctions. These junctions can be painted with corona dope and covered with vinyl tape. It has been our experience over several years that the insulation will not break down with a kilowatt-input transmitter, 100 percent modulated, except when wet or very damp. In this case, the input should be reduced to

[4] Theoretically, a center-fed antenna working on its third harmonic shouldn't be more than about 50 percent higher in resistance than on the fundamental. One would expect an s.w.r. on the order of 2 to 1 rather than such high figures. – Ed.


Sheet Aluminum Clamps
8'-6" × 1/4" O.D. Alumn.
1/2" Spacing
Standoff Insulators
9' × 1-1/8" O.D. × 0.58" Alumn. (Use 10' tube and slide rest into 1-1/4" tube)
6' × 1-1/4" × 0.058" Alumn.
Insulator
Flange
3 Radials 8-1/2' Long and 3 Radials 16-1/2' Long (May be part of guy wires)
50 Ω Coax
Steel Supporting Pipe
(B)
Same Construction as Top Section
(A)
50 Ω Coax
Dimensions and Construction Same as Above
(C)

Figure 7—Dimensions and suggested construction for coaxial, ground-plane and tubing dipole antennas for 10 and 20 meters. The arrangement in A might be mounted with standoff insulators attached to the 1¼-inch sections near the center of the antenna. The dipole in C could be closed at the center and fed with a gamma or "T"-matching system. Similarly-constructed parasitic elements could be added to make a multiband beam.

perhaps 500 watts unless special precautions have been taken to seal up the junctions at the open ends of the stub. Of course, on the lowest band for which the antenna is designed the stubs do not have voltage across them and will not be subject to breakdown or flashover. The high voltage across the open end of a stub occurs only at the resonant frequency of that stub.

Figure 7 shows the construction of several 10 and 20-meter antennas which have been built and the dimensions required for resonance in these bands. The spacing between the rods forming the shorted stubs is not critical—the same lengths were obtained with 1-inch instead of 1/2-inch spacing. Insulators should be made of low-loss material. Reflectors and directors for a multiband beam could be made up the same way.

From *QST*, December 1954 (Hints & Kinks)

"All-Band" Antenna

Figure 1 is a sketch of an "all-band" antenna system that I have been using with success for some time. The idea is not a new one, having appeared in *QST* at least 10 years ago. However, I feel that there are many newcomers since that time who would be interested in a simple system that can be fed with a single 70-ohm transmission line.

The arrangement consists of dipoles, cut for each band and connected in parallel at the center. Although I have not checked standing-wave ratios, the results seem to indicate that it gets out as well as a bunch of individually-fed doublets. If you haven't tried it, you're in for some surprises.– *R. L. Cope, W8MOK*



Figure 1–Sketch of W8MOK's "all-band" antenna. Egg insulators are used at points "A" through "F."

From *QST*, January 1975 (Hints & Kinks)

Three-Band Matching System for a Forty-Meter Doublet

A common method for energizing a half-wave antenna is to feed it at the center with parallel-conductor TV lead-in, or Twin-Lead as it is usually called, and to use an open stub for matching the 50- to 70-Ω antenna resistance to the 300-Ω impedance of the line. However, this technique, as described in the latest edition of *The ARRL Antenna Book*, generally gives proper matching on only one band.

After a number of trial-and-error calculations on a Smith Chart, along with lots of cut-and-try experimenting, I devised a three-stub matching scheme so that I could operate my 40-meter doublet on 40, 20 and 15 meters. Figure 1 illustrates this method and gives the lengths of the stubs and their positions along the feed line. The dimensions shown are for standard Twin-Lead, with a velocity factor of 0.82. All of the stubs are open at the ends and are made from the same type of line as the feed line. Note that the two lower stubs are connected at the same point on the feed fine.



The length of the longest stub is fairly critical. It should first be cut to 17 feet and then trimmed no more than two inches at a time, until the SWR is minimum in the center or the desired portion of the 20-meter band. The feed fine can then be matched with a 4:1 broad-band balun to a 75-Ω coaxial cable from the transmitter. With my antenna, the described matching system gives an SWR of less than 2.5 to 1 over all of the three bands, with minimum values of 1.3 to 1 on 40 and 15 meters, and 1.7 to 1 on 20 meters. As with any multiband antenna, one must guard against harmonic radiation. – *Frank Stuart, K7UUC*

A "Z" Antenna For the 10-160 Meter Bands

One of my interests in ham radio is designing and constructing antennas for both general amateur use and for the Army MARS system. For the amateur who has limited space, I have designed a "Z" antenna that covers the bands from 10 through 160 meters. It is easily constructed from wire. Spreaders for the transmission line are fabricated from Lucite strips or Plexiglas rods. (Refer to the yellow pages of telephone directories for the names of dealers who handle Plexiglas or the equivalent.) For two no. 14 wires, a 2-inch (51-mm) spacing is adequate.

Although a height of 100 feet (30 meters) is indeed desirable for this antenna, hams who settle for elevations between 30 and 50 feet (9 and 15 meters) will still obtain good results. The angles α between the wire segments will depend on individual situations such as the placement of trees or other supports. Generally, the wider the angle, the better the performance.

W1NH, the New Hampshire SCM, who is really into antennas, says my design is "FB." My evaluation of the antenna is that the "aerial" is great.–*John N. MacInnes III, WB1FPD*



A 10- to 160-meter horizontal Z antenna. Inexpensive no. 14 copper-clad (electric fence) wire may be used. For complete information on open-wire transmission lines, see *The ARRL Antenna Book*, any recent edition.

By Taft Nicholson, W5ANB/AAR6AG   From *QST*, November 1981

Compact Multiband Antenna Without Traps

Looking for an inexpensive, easy-to-build, portable antenna to use with your tube-type transmitter? This first cousin of the G5RV may be the aerial of your dreams.

Do you need an antenna for portable operation? I do! My preference is for making things as simple as possible. I don't like traps and matching units. The antenna shown in Figure 1 has no traps, needs no matching unit for the 10-, 20- and 40-meter bands (when used with vacuum-tube PAs), is lightweight and installs easily. What more could you ask for?

Construction

Construction is simple. Cut two lengths of stranded copper wire (such as Radio Shack 278-1292) to 44 feet, 2 inches each (m = ft × 0.3048). Attach 36 feet, 8 inches of 300-ohm twin lead as shown in Figure 1. Coaxial cable attaches to the other end of the twin lead at the points marked A and B in the diagram. I wound 7 feet, 2 inches of RG-58/U coaxial cable into an rf choke to minimize problems with rf flowing on the outside of the coaxial cable. This length of cable in the choke evolved from an attempt to match the antenna to the transmitter for operation on 15 meters.

Alternatively, you could use open-wire feeders in place of the twin lead. If you choose that method, you will need to make the section 42 feet, 6 inches long. Or you could attach the twin lead or openwire conductors to a matching unit. When using a matching unit, there is no particular merit in the lengths given in the diagram.

SWR

The SWR of the antenna is less than 3:1 on 10, 20 and 40 meters. I have no difficulty loading transmitters with tube-type PAs (e.g., Galaxy V, Swan 350 or Drake T4X). This antenna will work with some transmitters on 15 meters, but tuning is quite critical.

However, 80-meter operation is a problem. I have not been able to obtain full output power with these transmitters on frequencies below 3.750 MHz. The SWR measures between 5:1 and 8:1 for the lower part of the band. I constructed a loading coil to go between the choke and the twin lead (Figure 2). The coil consists of 44 inches of twin lead wound on a 7/8-inch diameter form (my left thumb). Once the coil was wound, I removed it from my thumb and used electrical tape to secure it. For 80-meter operation, attach ends C and D to the choke and ends E and F to the twin lead. Remove the coil for operation on the other bands. Banana plugs and sockets can be used to facilitate the insertion and removal of the coil.


44'2" Insulated and Stranded Copper Wire
44'2"
36'8" Twin Lead (300 Ω)
Run Twin—Lead to a Point Near Transmitter
A
B
Load Here (see text)
7'2" ±2" of RG—58/U Cable Wound into a 3" Dia. Roll and Taped in Three Places
RF Choke
To Transmitter

Figure 1—Diagram of the compact multiband antenna. For 80-meter operation the loading coil is inserted at points A and B. Banana plugs and jacks may be added here to facilitate insertion and removal of the loading coil.

Installation

The antenna should be as high as practical. I've had satisfactory results with the center of the antenna only 25 feet above ground, with the ends tied to fences or other convenient supports. Telescoping TV mast sections make a good support if nothing else is available. The legs of the antenna serve as two of the guy wires. One or two additional guy supports should be added (nonconducting material such as nylon rope is best).

This compact multiband antenna works satisfactorily on all bands from 20 through 80, and 10, meters. It has no traps and requires no matching unit when used with tube-type equipment. I have used it for portable operation in and out of the country. It is easy to pack, carry and erect. Perhaps you might want to try one. I think you'll like it! A brief discussion of the theory of operation follows in the appendix.

[Editor's Note: A description of the G5RV appears in the RSGB *Radio Communications Handbook*. Gray described it in the June issue of *Ham Radio Horizons*. A similar design was depicted in the Collins Radio manuals of the 1930s.]



Figure 2—Loading coil for 3500-3750 kHz operation. Points E and F on the coil are connected to the coaxial cable. Points C and D are connected to the twin lead.

Appendix

This multiband antenna evolves from two connected transmission lines with critical length and ratios of surge impedances. The system is self-resonant at a fundamental frequency and at most of the even harmonics and several of the odd harmonics. The first five are 2nd, 4th, 5th, 7th and 8th.

Consider the transmission lines in Figure 3.

The two lines are of equal length, "ℓ" and different surge impedances, Z_o and Z_s.

Looking into the lines:

$$X_o=\frac{Z_o}{\tan(2\pi\ell/\lambda)} \text{ and } X_s=Z_s\tan(2\pi\ell/\lambda)$$

where

λ = wavelength

X_o = reactance looking into open line

X_s = reactance looking into shorted line

From the theory of resonant circuits, we know if we connect the lines the system will be resonant at all frequencies where $\overline{X}_o=\overline{X}_s$ provided the two reactances are of equal value and opposite signs. The open and shorted line provide this condition except at some harmonics.

Joining the lines as depicted in Figure 4 we find that

$$\frac{Z_o}{\tan(2\pi\ell/\lambda)}=Z_s\tan(2\pi\ell/\lambda)$$

$$\frac{Z_o}{Z_s}=\tan^2(2\pi\ell/\lambda)=\tan^2(360°\ell/\lambda)$$

If the angle $2\pi\ell/\lambda$ is made 60°, then the amplitude of the tangent at 120° or second harmonic will be the same. This will be true for 240° (4th harmonic) and 300° (5th harmonic). Similarly, these harmonic responses will continue at discrete angles above 360°, e.g., 7th, 8th, 10th, 11th, 13th, 14th and so on. The signs of the tangents wash out when squared.

The angle $2\pi\ell/\lambda$ becomes 60° by making $\ell=\lambda/6$ (1/6 of a wavelength) at the fundamental frequency.

$$\frac{Z_o}{Z_s}=\tan^2(360°\times1/6)$$

$$=\tan^2 60°=(1.73)^2=3$$

Therefore $Z_o = 3Z_s$. This equation makes practical the multiband antenna because Z_o can represent the antenna proper and Z_s can represent the resonant feeder.

Z_o for the antenna may be computed from formulas in radio engineering handbooks or textbooks. For a piece of wire above the earth and parallel to it as shown in Figure 5C.

$$\frac{Z_o}{2}=138\log\frac{4h}{d}$$

For no. 12 wire, d = 0.08081 in.

Let h = 20 feet or 240 in.

$$\frac{Z_o}{2}=138\times\log\left(\frac{960}{0.08081}\right)$$



Figure 3—Two identical lengths of transmission line. Looking into the lines, the opposite ends are open and shorted at A and B, respectively.



Figure 4—The two transmission lines from Figure 3 are joined to form one line.

138 log (11879) = 562 ohms

This value is not critical. One can use 300-ohm twin lead or 400-ohm open line with

If the wire size had been no. 18,

$$\frac{Z_o}{2}=605\text{ ohms}$$

If we use no. 12 wire, then we would have 562 ohms on one side and + 562 ohms on the other side.

$$Z_o=\frac{Z}{2}+\frac{Z}{2}=1124\text{ ohms}$$

From the formula $\frac{Z_o}{Z_s}=3$

$$Z_s=\frac{Z_o}{3}=\frac{1124}{3}=374.6\text{ inches}$$

good results. The harmonics will be displaced somewhat, but with variable tuning of the transmitter the system can be brought on frequency.

The above indicates that $Z_o/2$ varies with antenna height, wire size and configuration. The function is logarithmic and a lot can be done to the antenna before Z_o changes very much. The inverted V works well; just use the $Z_o/2$ formula for a horizontal wire and let h be the average height of the inverted V. A formula for surge impedance can be worked out for most any configuration, including a vertical. If the reader is interested in feeding a vertical antenna, he is referred to LaPort,[1] which has the fundamental information for finding surge impedance or characteristic impedance of antennas.

The system could be used for a single-ended antenna fed with a balanced transmission line with a balun at each end. Another possibility for a vertical is the use of a two-wire, grounded, open transmission line, as discussed in LaPort's book.[2] The ground system would be critical.

When experimenting with these multiband lines, it is convenient to have some "stock" numbers to apply to the lines (see Figure 6). One-sixth of a wavelength is one-third of a half wavelength. A convenient length for a half wave on 80 meters is 135 feet. One-third of that is 45 feet or λ/6 for 80 meters. One-sixth of a wavelength on 40 meters is 22-1/2 feet. When you are designing an antenna, these lengths need to be multiplied by the propagation constant of the line. After construction and testing, the dimensions can be pruned for end effect, etc.



Figure 5—At A and B, the open portion of the transmission line evolves into the flat-top portion of the antenna. At C, diagram illustrating the formula for calculating Z_o for the antenna.



Figure 6—Angular position chart useful for determining "stock numbers" to apply to the chart.

When operated as a transmission line, the system as described may have application in end-feeding half-wave antennas, especially two half waves in phase. The system transforms a high impedance to a low impedance as a quarter-wave line will; however, it will do this at several even harmonics, in contrast to the quarter-wave line that is only responsive to odd quarter wavelengths.

The author wishes to thank Walt Maxwell, W2DU, for his detailed analysis of the theory section of this article.

Notes

[1] E. LaPort, *Radio Antenna Engineering* (New York: McGraw-Hill Book Co., 1952).

[2] See note 1.

By Bill Wright, G0FAH **From *QST*, June 1995**

Five Bands, No Tuner

Enjoy some of the advantages of a multiband, ladder-line-fed antenna without an antenna tuner.

Reading "The Doctor is IN" (*QST*, January 1995) reminded me that the search continues for a simple backyard antenna. A wire *dipole* antenna fed at the center with 450-Ω ladder line is a good choice. The ladder line keeps your losses low—even at moderately high SWRs. All you need is an antenna tuner and you're in business. No coils or traps necessary.

But can you do away with the tuner and still keep the ladder line? That would certainly make life simpler. To achieve this, your transceiver needs to "see" an impedance that looks reasonably close to 50 Ω on as many bands as possible. Without an antenna tuner acting as the middleman between the 450-Ω ladder line and your 50-Ω radio, this could be a problem.

Table 1
Calculated SWRs for a 94-foot Dipole Fed with 41 Feet of 450-Ω Ladder Line

Note: Although the antenna is cut for the CW portions of the band, expect similar results at other frequencies.

Frequency	*SWR*
3.56	7.6:1
7.1	2.4:1
14.2	1.5:1
18.1	2:1
24.9	1.5:1
29	2.4:1



Figure 1—The wire dipole antenna is 94 feet in length. If you don't have 94 feet of open space, don't hesitate to droop the ends of the dipole to make it fit. Feed the antenna with 41 feet of 450-Ω ladder line that is connected to a 1:1 balun. From the balun to your radio, use 50-Ω coax.

Can It Be Done?

A few years ago I attempted to design an antenna that would work on several HF bands from 80 to 10 meters. Full details were published in the spring 1992 edition of *SPRAT*, the journal of the G-QRP club.

My inspiration was the venerable G5RV. I took a 94-foot-long dipole and fed it with ladder line (see Figure 1). By cutting the ladder line to a specific length and using a 1:1 balun to make the transition to coaxial cable, I found that I could get close to 50-Ω (and thus achieve reasonably low SWRs) on at least five bands: 40, 20, 17, 12 and 10 meters (see Table 1).

The on-air results were better than I expected. My radio was happy and I didn't need to meddle constantly with an antenna tuner.

Of course, you'll need an antenna tuner to work the bands where the SWR exceeds 3:1.

A simple tuner will do the job, though. Because you're using *unbalanced* coax ahead of the balun, you won't need one of the more expensive tuners designed for *balanced* feed lines.

For best results, put your antenna as high as possible. If the ends must bend downward to accommodate the size of your lot, don't worry. Run the ladder line to your balun and take your coax from there to your radio. Keep the coax portion as short as possible.

Conclusion

By eliminating the antenna tuner completely, you lose the flexibility of loading your ladder-line-fed antenna on virtually any band. In return, however, you gain the convenience of operating on several bands without making tuner adjustments each time you change frequency. Your losses are held to a minimum, which means that most of the power your radio generates is radiated by your antenna. Not a bad compromise! Of course, the results I achieved will vary when used at other locations. Still, it's a simple, fun project in the experimental spirit of Amateur Radio.

By Rick Olsen, N6NR **From *QST*, March 1993**

The NRY: A Simple, Effective Wire Antenna for 80 through 10 Meters

Known as a *broadside collinear curtain array*, this antenna is simple to build, rakes in DX signals and has gain over a dipole on all the bands it covers!

Hams' thoughts ultimately turn to antennas. So it was with me a while ago. I had just moved to the emerald beauty of the Pacific Northwest and began pondering the 160-foot-tall Douglas firs in my backyard. I had considered putting up a crank-up tower, but decided that neighbors, architectural committees and crank-ups don't mix. Then I thought about topping a tree. Nope–I moved here because I love these trees.

I started sniffing around for alternatives. I obtained a copy of fellow ARRL Technical Advisor Roy (W7EL) Lewallen's antenna modeling program, *ELNEC*, along with a copy of *The ARRL Antenna Book*, and began to incubate the seeds of what would become my most enjoyable antenna project since I built a four-element quad back in 1974.

Hanging ropes from big trees is not a new idea.[1,2] 1 began by pacing off the distances between the monsters in my yard so I would know how much space I had to work with and how I could optimally direct my signal to places like Europe, Africa and the Caribbean.

Next came the selection of a configuration. Because the trees are approximately 120 feet apart, my first choice was a multielement collinear array. But a good friend, Terry Conboy, N6RY (in *NRY*, I'm the *NR* and he's the *RY*), suggested stacking a pair of *extended double Zepps*. I filed his suggestion away in my memory for the time being. I started my analysis.

The ARRL Antenna Book, on page 8-32, describes the basic function of the collinear array. In sum, it concentrates energy perpendicular to the wire, hence the term *broadside array*. This antenna's physical layout and pattern are shown in Figure 1. Such an antenna's gain can be increased by varying the end-to-end spacing of the elements.[3]

Chapter 8 goes on to explain three- and four-element arrays. Disappointment set in when I sized a four-element in-line array for 20 meters: It wouldn't fit between the trees! What *would* fit, however, was a "two-over-two." In fact, depending on the vertical separation, this array might even have some gain over the four-element collinear arrangement.[4]

My choice was made. I wanted to maximize performance on 20 meters and take what I could get on the other bands. I chose two 1-λ, center-fed wires vertically spaced 5/8 λ apart. According to *ELNEC*, with the array 100 feet high at the top and modeled



Figure 1—A two-element collinear array (A), also known as *two half-waves in phase*, is merely two half-wave wire elements placed end to end. This antenna has about 1.5 dB gain over a dipole in the same surroundings, and B shows its free-space pattern.



Figure 2—At A, the physical layout of and current distribution on an *extended double Zepp* (EDZ), a special case of the two-element collinear array shown in Figure 1A. This antenna exhibits more gain than the Figure 1A antenna because lengthening the elements to 5/8 λ has the same effect as spacing the element ends of two collinear half-wave elements 0.28 λ apart. (See Note 3.) At B, the antenna's azimuth-plane pattern in free space. This antenna has about 3 dB gain over a dipole in the same surroundings.

over lossy ground, this antenna's gain is approximately 12 dBi.[5] Not bad! The only problem is that this antenna's 20-meter feedpoint impedance is very high.

Reenter N6RY and the extended double Zepp. Take a look at Figure 2A. The extended double Zepp is simply a 1.25-λ, center-fed wire (two end-to-end 5/8-λ elements). There's a hidden message here! Have you found it?

Well, at first, I didn't either. Terry explained to me that the extended double Zepp (EDZ) is essentially two half-wave collinear elements spaced just over 1/4 λ apart. The extended double Zepp's added gain over two half waves in phase comes *not* from the extra 0.28 λ of wire between them, but from the *increased end-to-end spacing of the outermost pair of halfwave elements.* (Radiation from the inner 0.28-λ actually works *against* that from the outer halfwaves, but the gain increase from the new element spacing more than overcomes this disadvantage.) Figures 1B and 2B are similar. The EDZ has broader lobes and useful smaller lobes, both of which are attractive for a fixed array.

Sure enough, it was right in front of me all the time in the *Antenna Book* (page 8-34, fifth paragraph). In fact, the *whole darned array* was right in front of me in Chapter 8! I just needed some help piecing it all together. I modeled this array every way I could imagine, looking for the best possible performance. My wife didn't see me in the evenings for two weeks! Figure 3 shows the final configuration.

Figures 4, 5 and 6 show some of the results of my modeling. I used a design frequency of 14.2 MHz, a height of 100 feet above ground (for the top wire), elements made of #14 copper wire, and ground coefficients typical of the Pacific Northwest. All the elements in this array are fed in phase, as described in a bit.

As the figures show, the antenna's gain and patterns are impressive. On the 80- and 40-meter bands, the antenna has remarkably dipole-like patterns and gains and seems to work at least as well as a dipole in the same height range. On the higher bands, it works *much* better than a dipole. Its predicted gains in my installation are 9, 11 and 14 dBi at 7, 10.1 and 14 MHz, respectively. At 18.1 MHz (Figure 6) and above, the array begins to take on long-wire properties. It has several major lobes in directions closer to the wire axis, which the lower-frequency patterns don't provide.

To help you evaluate the NRY's patterns, Figures 4-6 superimpose the patterns of halfwave dipoles cut for 10.1, 14 and 18.1 MHz, respectively, on the NRY's patterns. These comparisons assume that the dipole is the same height as the NRY's feed point (halfway between the elements, or about 22 feet lower than the top wire), and over the same ground.

You may wonder about this antenna's effectiveness as a function of height. According to the *Antenna Book*, arrays like this have the best gain when the lower element is at least 1/2 λ above the ground (33 feet at 14 MHz). And, of course, as with all horizontally polarized antennas, this array's radiation angle decreases as you raise the antenna, which makes for better DX performance. The bottom line is that for DX work, you don't have to get the array up 100 feet for it to work well—you just need to put it up as high as you can. For closer-in coverage, it will work well at lower heights.

Another advantage of this array is that its feed-point impedances are manageable. To maintain my goal of broadband use, I decided to feed the antenna as shown in Figure 3. This is the "lazy-H" configuration described starting on page 8-37 of *The ARRL Antenna Book*. The attractiveness of this configuration is that it doesn't rely on specific phasing-line lengths to work properly. To the extent made possible by the different mutual impedances between each element and the ground, the phase relationship between elements remains constant regardless of frequency.

Final Dimensions

The antenna's physical dimensions (86 feet, 10 inches long and 43 feet, 5 inches high, not counting insulators) are easy to remember because the height is half the length. Because the antenna is basically 1.25 (5/4) λ long, center-fed and vertically spaced 5/8 λ apart, you can easily scale it to whatever band you like. For instance, to scale it to 10 meters, divide all the dimensions by two (28 MHz/14 MHz = 2).

Construction

Now for the really fun stuff: putting this thing up in the air! Building the antenna is a breeze. It took me all of about an hour to cut and solder the wires and attach the tethers. The harder part was preparing the trees.

If you have a friend like Bernie Olshausen, N6RUX, you have it made. He's a crack shot with a slingshot, similar to that described by Wade Calvert, WA9EZY, in *QST* a couple of years back.[6]

Once Bernie landed the fishing lines over the right tree limbs, the next job was to pull up some lightweight twine (we used seiner twine—the stuff fish nets are made of) with the fishing line. This is important; rope sometimes snags as it goes over limbs, and you don't want to try to pull it over with 6-pound-test fishing line! With the twine, we pulled up some 800-pound-test nylon rope with a pulley on one end, using another piece of nylon rope through the pulley to act as a catenary for the array.

It's important to use a strong, weather-resistant catenary rope to hang the array, because the antenna loses its desirable properties quickly when it takes on the shape of a V. You can expect a 2-dB gain



Figure 3—The broadside collinear curtain array—the NRY—in its final configuration. This antenna is cut for 20 meters, but works well on all the HF ham bands. The array hangs from a catenary rope via three short lengths of twine. The lower end insulators are supported by ropes to those of the top wire, and the center insulators are joined by the phasing line, which is 43 feet, 5 inches of parallel-wire feed line. The feeder to the radio is made of the same type of line connected at the halfway point on the phasing line.



Figure 4—The NRY's 14-MHz azimuth-plane pattern with the bottom wire at 56.5 feet and top wire at 100 feet. For comparison, the shaded part shows the pattern of a half-wavelength, 14-MHz dipole at 78 feet (the same height as the NRY's feed point).



Figure 5—The NRY's 10.1-MHz azimuth-plane pattern with the bottom wire at 56.5 feet and top wire at 100 feet. For comparison, the shaded part shows the pattern of a half-wavelength, 10.1-MHz dipole at 78 feet (the same height as the NRY's feed point).

decrease at 20 meters with a 20° variance from the flat-top configuration. The rope, therefore, must be strong enough to minimize droop and maintain integrity in the sun and wind. We'll get back to the rope in a minute.

For the phasing harness I used low-loss, 300-Ω twinlead. Any parallel-wire feeder should work fine. Don't use coaxial cable in the feed system. It's too heavy, unbalances the array and has very high loss when operated at a high mismatch.[7]

To assemble the feed system, I used porcelain insulators and equal lengths of 300-Ω line. I then cut the #14 antenna wire to the proper length and soldered it to the feed system in a standard dipole configuration.

Next came the tethers. For an antenna almost 87 feet wide and 43 feet tall, you need to provide some means of maintaining the proper element spacings. I used equal lengths of seiner twine (nylon or dacron rope would also work fine) to vertically space the element ends. I also attached plenty of line to the lower end insulators so I could tie them to the appropriate fence posts once the antenna was in the air. See Figure 3.

The catenary rope is the trickiest part. The antenna won't hang right if you don't attach the top three insulators in the right spot. I know—I did it wrong the first time!

I cut a piece of catenary rope 95 to 100 feet long and carefully marked the center. Next, I measured the distances from the center to each end of the array. (The array itself is a handy measuring line.) Then I added about 10 more inches and marked the line. I'll tell you why in a minute.



Figure 6—The NRY's 18.1-MHz azimuth-plane pattern with the bottom wire at 56.5 feet and top wire at 100 feet. For comparison, the shaded part shows the pattern of a half-wavelength, 18.1-MHz dipole at 78 feet (the same height as the NRY's feed point).

Then I cut three pieces of twine, each about 24 inches long. At the center of the catenary rope, I carefully opened the rope weave and passed about 6 inches of twine through it, then let the catenary rope retake its natural shape. Wrapping the twine around the rope several times on either side of the joint relieved the tension placed on the rope introduced by passing the twine through it.[8] I then tied the other end of the twine to the top center insulator so that the spacing between the rope and the insulator is 12 inches.

After doing that, I attached the twine at the end marks on the catenary rope in the same manner. The distance to the end insulators is 18 to 20 inches. This causes the ends to hang off the rope at an angle and provides strain relief.

If you use a braided rope (with a weave you can't open to pass twine through it), one good alternative is to use insulators in the catenary rope (at the points where I attached the twine) as tie points for the array.

Now you're ready to haul the antenna up on the lanyards. Consult your US Navy *Marlinspike Seamanship* manual (just kidding, of course) and join the ends of the catenary to the lanyards that are hopefully by now through the pulleys, up in the trees. Use a strong knot that won't slip.

Before hoisting the array into the sky, *make sure* that the connections to the feed harness at the top and bottom are the same (ie, that the left elements both attach to the same wire in the twinlead). This thing does not work right if the top and bottom are fed 180° out of phase!

Now you're ready to haul it up and connect the feed line to the antenna tuner. Check to make sure that the symmetry and top-to-bottom wire spacings are within reasonable limits, then tie the bottom tethers off so that the bottom wire is as flat as you can make it.

You're Done!

This is quite an effective antenna. I've installed two of them: One is boresighted on the Middle East and works like gangbusters into Europe as well; the other favors the Caribbean and most of the US. In the first three months after putting them up, I worked 105 countries on CW, including some rare ones, with a 100-watt transceiver. I'm surprised at how easily I can bust pile-ups—especially on 30 and 20 meters.

I hope you have an opportunity to try this array on for size. Don't limit yourself to just the backyard, either: It's a great Field Day antenna, to say the least. It also comes in handy for emergency work where you need a gain antenna.

You don't have to be a rocket scientist to design effective antennas! Your old friend *The ARRL Antenna Book*, and other ARRL publications, like Walt (W2DU) Maxwell's *Reflections*, the *Handbook*, the *Antenna Compendium* series and Wilfred Caron's *Antenna Impedance Matching*, are serious reference guides and sources of numerous ideas. It doesn't hurt to have your favorite antenna-modeling software loaded on your PC, either!

Notes

[1] D. Brede, "The Care and Feeding of an Amateur's Favorite Antenna Support—the Tree," *QST*, Sep 1989, pp 26-28, 40.

[2] J. Hall, ed, *The ARRL Antenna Book*, Chapter 22 and pp 4-3 and 15-3.

[3] *The ARRL Antenna Book*, Fig 8-38, p 8-32, illustrates how gain varies with the spacing of the two adjacent element ends.

[4] The *Antenna Book*'s Fig 8-45, p 8-35, suggests that a spacing of 5/8 to 2/3 λ yields good broadside gain. For the four-element array, upwards of 8.5 dBi gain is obtainable.

[5] dBi means decibels relative to an *isotropic radiator* (point source) in free space. It *does not* denote gain relative to a point source above real ground, or a dipole in any surroundings.

[6] W. Calvert, "The EZY-Launcher," *QST*, Jun 1991, pp 34-35.

[7] *The ARRL Antenna Book* shows how coaxial-cable loss varies with matched loss and SWR in Fig 18, p 24-18. (The *Antenna Book* also contains a table of matched loss per 100 feet as functions of frequency and cable type in Fig 26, p 24-18).

[8] If you use braided rope for the catenary, you'll need to use another method to secure the seiner twine to the catenary rope.

CHAPTER FOUR

LOOP ANTENNAS

4-1 **Dual Full-Wave Loop Antennas**
From March 1982 *QST*

4-2 **A Gain Antenna for 28 MHz**
From July 1994 *QST*

4-3 **10-Meter “Lazy Quad”**
From July 1968 *QST* (Technical Correspondence)

4-4 **The Full-Wave Delta Loop at Low Height**
From October 1984 *QST*

4-7 **A Triband 75/40/30-Meter Delta Loop**
From *The ARRL Antenna Compendium Vol 5*

4-9 **A Two-Band Loop for 30 and 40 Meters**
From March 1989 *QST* (Hints & Kinks)

4-10 **Feeding an 80-Meter Delta Loop at 160 Meters**
From April 1990 *QST* (Hints & Kinks)

By John Griggs, W6KW **From *QST*, March 1982**

Dual Full-Wave Loop Antenna

Achieving gain from an antenna at 7 and 3.5 MHz normally requires a rather large piece of real estate, a high tower or both. To obtain significantly improved performance over a dipole at these frequencies, and to do it inside an average city lot, is a goal worth pursuing! With this in mind I decided to replace my inverted-V dipoles on 7 and 3.5 MHz with a dual full-wave loop antenna, one inside the other.

I had noticed the strong signals on 7 MHz from Pat Kearins, W7UI (now a silent key), and from Carl Winter, W6OAW, on 3.9 MHz, and was interested to find that both were using full-wave loops. Both signals would pin my S-meter and my QTH is well over 200 miles from either station. The antenna at W7UI was a loop suspended by a very high supporting structure. This loop resembled a square, with one corner facing up, one facing the ground, and the other two corners pulled outward by guy wires.

My attention was attracted to a horizontal loop antenna used by another ham on 3.9 MHz that produced extremely strong signals. It was a square loop, 65 feet on a side, with each leg parallel to the ground but only 14 feet high. Fed by a tuned line, it functioned well, but it was most effective for relatively short ranges, up to 200 miles or so.

Of more interest to me, however, was the 75-meter rectangular loop used at W6OAW. I learned that this was a dual antenna, i.e., a full-wave rectangular loop for 3.9 MHz suspended about 40 feet above ground, with another full-wave loop for 7 MHz inside the first, in the same plane. The 3.9-MHz loop is a closed circuit, whereas the 7-MHz loop is an open circuit. This permits operation on 10, 15 and 20 meters as well as 40 meters when used with open-wire feed line and a matching network. The outer loop is fed with coaxial cable.

Design Planning

In considering loop antennas for my lot, which is 75 feet wide by 125 feet deep, I found that I could use two 40-foot high pipe masts, 130 feet apart along a diagonal across my lot. I duplicated the W6OAW arrangement, except that I hung the antenna vertically and made both loops closed-circuit designs. I could use them only on the bands for which they were cut, 7.2 MHz and 3.8 MHz. Each is fed with a quarter-wave matching section of RG-59/U, which provides a 50-ohm match for the RG-8/U cables leading in to my operating position.

Construction

See Fig. 1 for construction details and dimensions. Matching the 104-ohm antenna impedance to the 50-ohm line impedance requires a quarter-wave coaxial line having a characteristic impedance of 72 ohms. The formula for a $^1/_4$-wave section is:

$$\frac{246}{f\,(\mathrm{MHz})} = \ell\,(\mathrm{ft}) \qquad \text{(Eq. 1)}$$

This result must be multiplied by the velocity-factor of the coaxial cable, 0.66 for RG-59/U 73-ohm cable. The quarterwave section was determined to be 42.7 feet for 3.8 MHz and 22.6 feet for 7.2 MHz. These connect to RG-8/U cables for a 50-ohm match to the transceiver.

The top section of the 3.8-MHz loop is fed at the center because of the length of the quarter-wave line, but the shorter matching section for the 7.2-MHz loop allows me to feed the bottom portion of that antenna.

The inner loop is supported from the corners of the outer loop by means of nylon rope and suitable insulators. It is best to use lightweight, high-quality insulators and wire no larger than no. 14 to reduce the weight of the array. Pulleys (and rope) will be required at the tops of the 40-foot poles and also at the 18-foot level. The fact that the bottom horizontal section of the antenna narrowly misses the top of my house roof seems to have no deleterious effect on its operation.

Measure the antenna sections carefully, and cut them to length. Pay particular attention to locate the feed point at the exact center of the horizontal wire sections. This provides horizontal polarization. Feeding the loop at the center of either vertical section will provide vertical polarization.

Tuning

If trimming is needed to resonate the antenna to your favorite operating frequency, cut or add equal length pieces at each vertical section. Do not shorten the sides to the point at which the top and bottom sections are less than 0.1 wavelength apart. Careful pruning of the horizontal sections would be required if such a problem develops.

Information given to me by those using this antenna seems to confirm my results. A typical comment is "Boy are you ever loud!" A gain of 1.8 dB over a dipole is claimed for this type of antenna. The principal difference appears to be a lower angle of radiation. While it is possible to work stations off the ends of the antenna, maximum radiation occurs broadside to the element. What I like about the antenna is the ability to hear weak stations. It is outstanding in this regard.


m = Feet (') × .03048
104'
Nylon Rope
52'
12'
Nylon Rope
22'
50 - Ω Coaxial Cable to Station
75 - Ω RG - 59 Coaxial Cable 1/4 λ Transformer

Fig 1—Dimensions for the dual full-wave loop antenna. Input impedance is on the order of 104 ohms. A quarter-wave matching section of RG-59/U is used to provide a match to 50 ohms.

By Brian Beezley, K6STI **From *QST*, July 1994**

A Gain Antenna for 28 MHz

Give your 10-meter signal a boost with this simple antenna.

Although in coming years the 10-meter band won't provide the excitement it did at the peak of sunspot cycle 22, DX openings will still occur, especially during spring and fall. And who knows? With the large number of 10-meter operators and wide availability of inexpensive, single-band radios, the band may be the hangout for local ragchews that it was before the advent of 2-meter FM.

I'd like to present a simple antenna for 10 meters that provides gain over a dipole or inverted V. Similar designs have been published before, but because I never hear them on the air, I think they must not be fully appreciated. The antenna is a resonant, rectangular loop with a particular shape. It provides 2.1 dB gain over a dipole at low radiation angles when mounted well above ground. This represents a power increase of 62%. The antenna is simple to feed–no matching network is necessary. When fed with 50-Ω coax, SWR is close to 1:1 at the design frequency. SWR is less than 2:1 from 28.0 to 28.8 MHz for an antenna resonant at 28.4 MHz.

The antenna is made from #12 wire (see Figure 1). For horizontal polarization at 28.4 MHz, the loop is 73 inches wide and 146 inches high (just larger than 6×12 feet). Feed the antenna at the center of the lower wire. Coil the coax into a few turns near the feedpoint to provide a simple balun. A coil diameter of about a foot will work fine. You can support the antenna on a mast with spreaders made of bamboo, fiberglass, wood, PVC, or other nonconducting material. You can use aluminum tubing both for support and conductors, but you'll have to readjust antenna dimensions for resonance.



Figure 1—Construction details of the 10-meter rectangular loop antenna.

This rectangular loop has two advantages over a resonant square loop. First, a square loop has just 1.1 dB gain over a dipole. This is a power increase of only 29%. Second, the input impedance of a square loop is about 125 Ω. You must use a matching network to feed a square loop with 50-Ω coax. The rectangular loop achieves gain by compressing its radiation pattern in the elevation plane. The azimuth pattern is slightly wider than that of a dipole (it's about the same as that of an inverted V). A broad pattern is an advantage for a general-purpose, fixed antenna. The rectangular loop provides bidirectional gain over a broad azimuth region.

You should mount the loop as high as possible. To provide 1.7 dB gain at low angles over an inverted V, the top wire must be at least 30 feet high. The loop will work at lower heights, but its gain advantage disappears. For example, at 20 feet the loop provides the same gain at low angles as an inverted V.

A small, 3-element Yagi can provide 6 dB gain over a dipole and great rejection of signals to the rear. If you can install a beam and rotor, you'll find it much more effective than a loop. But for a simple, cheap, gain antenna that can be thrown together quickly, the rectangular loop is hard to beat.

Note: I used the AO 6.0 Antenna Optimizer program to automatically optimize the dimensions of a rectangular loop for maximum forward gain and unity SWR. I used NEC/Wires 1.5 to verify the design with the Numerical Electromagnetics Code.

From *QST*, July 1968 (Technical Correspondence)

10-Meter "Lazy Quad"

Among your readers that like to tinker with antennas there may be some that would like to try the antenna shown in Figure 1. The basic idea came from a station using a somewhat similar configuration on 15 meters, and I make no claim of originating the idea. However, I have never heard of anyone using the antenna on 10 meters. Since it is currently nameless, and has features similar to both a Lazy H and a quad, perhaps it should be known as a "Lazy Quad."

The major advantages of the antenna are: (1) extreme simplicity, (2) feasibility of installation on a light unguyed pole, (3) small horizontal space requirements (as compared to a horizontal dipole), (4) low QRN in receiving (as compared to a vertical dipole), (5) ability to withstand high wind loads and (6) broadband operation.

When looking at loop 1 we see a horizontally-polarized full-wave loop radiating broadside, with maximum currents along the top and bottom horizontal wires H_1 and H_2. When looking at loop 2 we see a similar horizontally-polarized loop with maxiinum current on wires H_2 and H_3. When looking at wires H_1 and H_3 we notice two in-phase horizontal wires spaced a half wave, both carrying maximum current. Minimum currents appear on the vertical portions of the loops where the tuning stubs are inserted.



Figure 1—W6PIZ's "Lazy Quad" for 10 meters. The loops are No. 14 wire, with the horizontal sections mounted an 8-foot lengths of 1×2 wood. The adjustable stubs are of the same type wire and are self-supporting since the length is only 6 inches. The antenna at W6PIZ is mounted on an unguyed wooden pole 32 feet high.

I operate mostly on 10-meter c.w. and have the antenna peaked at 28,050 MHz. In my specific case the length of each stub is 6 inches for this frequency. Loading is almost constant from 28 to 30 MHz.

The coax feed line is run straight down the pole (wood) to the ground, and there is little antenna effect on the feeder.

Results have been consistently better than had been obtained with vertical or horizontal dipoles previously installed at the same effective height at the same location. Indications are that it outperforms some beams of the same approximate height, perhaps because of the broad vertical pattern (which allows longer QSOs under critical skip conditions), as compared to the beams.

Perhaps some of your readers might be urged to try this basic idea with a reflector of the same basic configuration as the driven element. It would appear that the Double Lazy Quad would be anything but lazy in operation. — *Dave Hardacker, W6PIZ*

By Doug DeMaw, W1FB and Lee Aurick, W1SE **From *QST*, October 1984**

The Full-Wave Delta Loop at Low Height

You'll be surprised at the results you'll get from a full-wave loop at low heights.

Property size and antenna-support height are ever-present concerns of the urban amateur. Many good antennas are untried because the radio amateur is unable to imagine how a large wire antenna could be squeezed onto a small lot. Certainly, this is typical in the case of full-wave loop antennas. But there is no rule that dictates using a symmetrical loop. It can be distorted rather severely without spoiling the performance. The same philosophy is appropriate with regard to height above ground and the plane in which the antenna is erected. In most instances, a less-than-optimum full-wave loop will outperform a dipole or inverted V antenna that is close to the ground in terms of wavelength. It is possible that such a loop will give comparable or better performance than a vertical antenna that is less than 90 degrees (with respect to ground), or one with a substandard ground screen.

We want to discuss the Practical considerations of loops that can be supported from low supports on small pieces of property. The results we have obtained are noteworthy with respect to all-around "solid" communications within and outside the USA. Perhaps you will be inspired to unroll some wire and try a loop at your QTH.

Some Loop History

Loops were used first as receiving antennas. While single- and multiturn small loops worked well for receiving, they were not satisfactory for transmitting: They were inefficient in terms of gain, and the feed impedance was generally a fraction of an ohm, making them difficult to match. The losses were significant. But, it was possible to use a compact loop (less than 0.5 wavelength) for receiving in place of a fullsize version that could require thousands of feet of conductor. One of us owned a portable broadcast-band receiver in the 1930s. The loop antenna was stored in the lid of the cabinet, and needed to be mounted atop the radio during reception periods! The radio was heavy: it weighed 91 pounds, including the various dry batteries.

Receiving loops continued to be useful for many years in the commercial services, especially for LF and VLF applications. Amateurs also used them (and continue to do so) for improved reception on 160 and 80 meters. The signal-to-noise ratio of receiving loops is markedly better than that of vertical antennas, and they are directional.[1] Many successful 160-meter DXers owe their success to the use of receiving loops with low-noise preamplifiers. Practically, these loops are the next best thing to Beverage antennas.[2]

Loop Characteristics

What are some of the advantages of a closed, full-wave loop? Perhaps number 1 on the list is the lack of need for a ground screen. The matter of effective height above ground is still a consideration, but we need not lay a ground-radial system as would be the case with a vertical antenna. Consideration number 2 is that a full-wave loop (depending on the shape) has some gain over a dipole. Number 3 relates to noise factor. A closed loop is a much "quieter" receiving antenna than are most vertical and some horizontal antennas.

To illustrate this point, the 160-meter antenna at W1FB is a $^{3}/_{8}$-wavelength inverted-L with twenty $^{3}/_{8}$-wave radials. Since this is essentially a vertically polarized antenna, it is noisy (man-made and atmospheric noise). There are times when an S9 signal is unreadable because of the ambient noise being S9 or greater in strength. Upon switching to the 75-meter Delta loop, the same signal will rise above the noise by 1 or 2 S units, while the noise and signal will drop well below S9. For example, the received signal may drop to S6 on the loop, but the noise will decline to S4.

Feed-point selection will permit the choice of vertical or horizontal polarization. Various angles of radiation will result from assorted feed-point selections. The system is rather flexible when we want to maximize close-in or faraway communications (high angle versus low angle). Figure 1 illustrates various configurations that can be used. The arrangement at C is used at W1SE, and the shape at D is being applied



	Polarization	Radiation Angle
A	Horizontal	Moderately High
B	Horizontal	High
C	Horizontal	Moderately High
D	Vertical	Low

Overall Loop Size in feet ≈ $\frac{1005}{1\text{ MHz}}$

Feed Impedance ≈ 100 Ω

Figure 1—Various configurations for a full-wave Delta loop. Radiation angles and polarization are affected by the feed-point placement and location of the apex.

at W1FB. Both antennas are cut for 80-meter operation. The bandwidth at resonance is on par with that of a dipole. A Transmatch is used for matching the system to the transmitter in those parts of the band (75 and 80 meters) where the SWR is too high to deal with.

Our loops are not deployed in a vertical plane, owing to the lack of tower height. A 60-foot tower and 50-foot tree support the W1SE antenna. A single 50-foot tower is used at W1FB. Both loops are tilted away from the supports at roughly 45 degrees (Figure 2). This shows the present W1FB system. The loop is broadside northeast and southwest for maximum radiation in those directions at 80 meters. More on this later.

When these low-to-the-ground experiments began in the summer of 1983, we were joined by Bill Martinek, W8JUY, near Traverse City, Michigan. Bill experimented with various loop configurations so that he and W1FB could make signal comparisons locally and afar. He finally adopted the W1SE format with the apex down (Figure 1C, with the flat top strung between two 50-foot trees). In order to keep the loop completely vertical (not sloping), he chose a triangle that was not equilateral. The upper side of his triangle is substantially longer than the two downward sides. His signal on 75 meters is consistently 10 to 20 dB stronger than with his inverted V. The point of this discussion is that you need not use an equilateral triangle if it will not fit on your property. Erect whatever you can, then give it a try!

Feed Methods

A Q section is used for feeding the W1SE loop. A Q section is a quarter-wavelength line with an impedance that is somewhere between the antenna feed impedance and that of the feed line. Calculation is a simple matter:

$$Z\ (Q\ section) = \sqrt{Z1\ Z2}\ ohms \qquad (Eq.\ 1)$$

where Z1 is the antenna impedance, and Z2 is the feeder impedance in ohms. In this case, assuming approximately 100 ohms for the antenna. feed impedance, we would have $\sqrt{100 \times 50} = 70.7$ ohms for the Q-section impedance. This represents a close match to 52-ohm coaxial cable. The Q-section length (made from RG-59/U) can be determined from L(feet) = 246 V/f(MHz), where V is the velocity factor of the coaxial line for the matching section. (The length should be verified using a dip meter.) For operation at the W1SE-chosen frequency of 3.825 MHz, the calculation calls for a Q section of 42 feet 5 inches (Figure 3).

Open-wire feed is used at W1FB (Fig 6B) to permit multiband operation through 10 meters. Unfortunately, a short run of RG-8/U was needed to bring the feed line to the ham station–under the driveway. The coaxial cable was buried in the ground for this reason. A homemade 4:1 toroidal balun transformer (two stacked T200-2 Amidon



Figure 2—A tilted Delta loop for 80 meters is used at W1FB. The tower height is only 50 feet. Homemade open-wire line is used as the feeder to permit multiband use with vertical polarization and a low radiation angle.



Figure 3—At A is the feed method used at W1SE. A coaxial Q section closely matches the 100-ohm feed impedance to a 52-ohm coaxial line. Illustration B shows the W1FB feed arrangement. Open-wire line, a balun transformer and a short length of RG-8/U cable permit multiband use with a Transmatch. Ideally, the open-wire line would continue all the way to the Transmatch, and the balun transformer would be located at the Transmatch.



Figure 4 — Two methods for using a full-wave loop at half frequency. A switching arrangement could be applied at the feed point to change from a closed, full-wave loop to the first configuration seen here. The method at A performs as a ¼-wavelength radiator, but a ground screen is required. Method B is satisfactory as a ½-wavelength open loop for half-frequency use. It requires opening the loop at the electrical point opposite the feed point. A relay could be used for this purpose.

cores and Teflon-insulated no. 14 wire) was enclosed in a weatherproof box and mounted on one of the support poles for the 450-ohm open-wire line. The RG-8/U was run underground from that location (about 25 feet). Ideally, the openwire line would have been brought into the house, where it would be matched to the station gear with a Transmatch. Fortunately, the SWR at loop resonance is 1.3:1 without the Transmatch in use.

Performance

This is the part of our article that many of you have been waiting to read. Well, the W1FB results have been entirely gratifying. The loop replaced an inverted V with an apex height of 50 feet. This led to a pronounced improvement in all-around communications on 75 and 80 meters out to 500-600 miles. But, the loop proved to be very effective also for DX communications to Europe on 80 meters. The first version was that of Figure 1B. Although the antenna was outstanding for close-in 75- and 80-meter work, it offered dismal DX performance. The configuration at D of Figure 1 seems to offer a good compromise in performance for local and DX work. The theoretical launch angle to the horizon at the loop fundamental frequency is 10 degrees, as reported by VE2CV in a letter to W1FB. This assumes that the loop is erected vertically and at a reasonable height above ground.

Harmonic operation of the loop, as depicted in Figure 1D, is superb. At times it outperforms the trap tribander atop the tower during DX operation to Europe and Africa. The loop shows an average 6-dB signal increase on 20 and 15 meters in the favored direction, owing to the gain and lower radiation angle of the loop. Radiation at the harmonics is in the plane of the loop rather than broadside to it. This makes it ideal for contacts into Africa. It is perhaps the most effective 40-meter DX antenna that has been used at W1FB from northwest lower Michigan. The Transmatch is required on all harmonic frequencies other than 18.111 MHz, where W1FB has been conducting propagation studies with Bill Orr, W6SAI, Prose Walker W4BW, Bob Haviland, W4MB and Stu Cowan, W2LX, under special experimental/research licenses (KM2XQV). The loop has worked very well on 24.9 MHz as well during these tests. At 18.111 MHz, the SWR is 1.4:1.

The operating results at W1SE also indicate that a tilted loop, close to the ground, functions quite well. With loop resonance at 3825 kHz, the 2:1 SWR points occur at 3734 and 3934 kHz, respectively. This 200-kHz bandwidth spectrum can be shifted up or down the band by lengthening or shortening the loop conductor and Q section accordingly. From the W1SE location in Newington, the loop has delivered impressive performance for local and DX work.

A 40-meter Delta loop was constructed for use at W1SE after noting the fine performance of the 80-meter system. It was cut for resonance at 7016 kHz. This model was erected in a completely vertical format, using 143 feet 3 inches of wire. The Q section is 23 feet 2 inches long. The apex (feed point) is 4 feet above ground. The SWR on 40 meters is less than 2:1 across all of the band. The 80- and 40-meter W1SE loops showed resonance slightly apart from the design frequency, perhaps because of the proximity of the antennas to ground. Resonance on 40 meters was checked as 7050 kHz. Both loops are performing better for local and DX contacts than any of the many antenna types tested at W1SE. We would be even more impressed if we could elevate our Delta loops so the lower portions were a half wavelength or greater above ground.

In Conclusion

There is no rule that dictates the shape of a full-wave loop. The triangular format is convenient for mounting the radiator. If the apex is at the top, only one high support structure is needed. You may have one or more tall trees that can be used as supports. Circular, square or rectangular shapes have been used by many amateurs and the results were good. Certainly, a loop is an impressive receiving antenna, in terms of noise reduction. In some urban locations, that may be more important than transmitting a "death-ray" signal! There is something to be said about the age-old expression, "If you can't hear 'em, You can't work 'em."

An 80-meter Delta loop can be used on 160 meters by adopting one of two simple methods (Figure 4). A closed loop does not, however, offer good results when the overall length is a half wavelength. Either of the techniques in Figure 4 will work, but the method at A requires a ground radial system for best results.

Notes

[1] D. DeMaw, "Beat the Noise with a Scoop Loop," *QST*, July 1977, and "Maverick Trackdown," *QST*, July 1979.

[2] H. H. Beverage and D. DeMaw, "The Classic Beverage, Revisited," *QST*, Jan. 1982.

By David J. Crockett, WB4DFW **From *The ARRL Antenna Compendium Volume 5***

A Triband 75/40/30-Meter Delta Loop

WB4DFW wanted to use his Delta Loop on other bands besides 75 meters, so he installed some coaxial traps. He also reveals an effective technique to prevent breakage when support trees sway in the wind.

I've been using horizontally mounted, coax-fed Delta Loop antennas on 75 meters for many years. I've found them to be superior to dipoles—they are generally quieter on reception (perhaps because they are dc-grounded), exhibit broader bandwidth (typically less than 2:1 SWR over more than 200 kHz using a coaxial matching section), and are often more easily adaptable to available tree supports. They also don't fall down very often when installed correctly!

Outside of using an antenna tuner, a 265-foot-long 75-meter loop doesn't lend itself to working other bands–and I don't have a tuner. So while listening to a virtually dead 75-meter phone band one day and wishing I had a way to hit 30 meters for a long-overdue dose of CW, I had a brainstorm. Why not use traps? I'd homebrewed coaxial traps based on Sommer's article[1] several times in the past, and I knew they were easy to make and adjust.

The Traps

A quick examination of the latest incarnation of my 75-meter loop found it to be a reasonably equilateral triangle (a little over 85 feet per leg). I calculated that a 30-meter dipole should be something over 46 feet in total length (465/frequency in MHz). It appeared to be a simple enough matter to station some homebrewed coaxial traps 23 feet on each side of the feedpoint. A little more calculating found that it might even be practical to put in a pair of 40-meter traps as well.

Sommer gives a useful set of nomographs for computing trap dimensions on PVC pipe forms, using either RG-58 or RG-174 coax (the former capable of handling a kW with few problems). I opted for the larger cable. The 30-meter traps each require 46.8 inches of coax on a 1.62-inch OD section of PVC (6.75 turns). The 40-meter versions each use 61 inches of coax on a 2.25-inch OD PVC section (6.0 turns). Both PVC sections can be any convenient length. I used four-inch long pieces.


Close-Up of Supports
Support Rope
Screen Door Spring
Insulator
Strain Limit Loop
Support (see inset)
Approx. 80 ft on both untrapped legs
Support (see inset)
40 M Trap
30 M Trap
Center Insulator
30 M Trap
40 M Trap
Support (see inset)
23 ft
7 ft
5 ft
RG-59/U Quarter-Wave Matching Section for 75 Meters (40.1 ft, including choke coil)
Choke Coil (5 turns approx. 1 ft diameter)
RG-8X (any length) to shack

Figure 1—Overhead view of the Triband 75/40/30-meter Delta Loop, which WB4DFW mounted 40 feet off the ground. The traps were constructed with RG-58 coax. See text for winding details.

I wound the 30-meter traps in less than an hour and inserted them in the loop antenna 23 feet either side of the feedpoint. A quick SWR check found them resonant well below the bottom of the 30-meter band, but spacing the turns slightly apart and securing them with electrical tape raised the resonance easily enough, with the SWR bottoming out at 1.2:1 at 10.125 MHz.

The 40-meter traps went together with similar ease. Placement in the existing antenna was a little more challenging than with the first set of traps. The loading caused by the 30-meter traps made determining the physical location for the 40-meter traps uncertain. Grebenkemper notes that traps in a half-wave antenna tend to "pull" an antenna toward resonance,[2] even if they are not placed at exactly the optimum location. So, I simply took the formula length for 40-meter resonance, generously subtracted the physical length of the coax in each of the 30-meter traps and installed the 40-meter traps accordingly.

The approach was unscientific, but SWR was 1.3:1 at 7.1 MHz on the first try. Dumb luck, I guess, and I opted to make no further adjustments. The final antenna layout is shown in Figure 1, and a close-up photo of a trap is shown in Figure 2.

The Matching Section

The ARRL Handbook notes that the typical impedance of a full-wave loop antenna is on the order of 100 Ω, or about a 2:1 SWR presented to a 50-Ω feed line at resonance. The original WB4DFW 75-meter Delta Loop used a quarter-wavelength coaxial matching section (also described in the *Handbook*) between the feedpoint and the coax going to the shack. The matching section is merely 40.1 feet of RG-59 75-Ω coax [(465/3.85)/2 ×.66, the velocity factor] and transforms the load of the antenna very close to the 50-Ω characteristic impedance of the RG-8X feed line I use.



Figure 2—Close-up photo of one of the 40-meter traps. The ends of the coax cable used in each trap have been sealed against moisture with silicone caulking. See text for construction details.



Figure 3—Photo of one of the support system springs, with rope used to limit total stretch. The rope is twice the length of the unstretched spring.

I also use a five-turn loop of the matching section coax to form an RF choke near the antenna feedpoint to minimize feed-line radiation. The matching section has no perceptible effect on the new 40 and 30-meter antenna SWRs (checked empirically by temporarily removing the section and feeding the antenna directly with the 50-Ω coax), so it has been left in service.

What effect did all this have on my original 75-meter loop? As one might expect, the resonant frequency dropped as a result of the traps' loading effects (nearly 200 kHz). But pruning about 8 feet off the far apex end of the loop brought my normal 1.2:1 resonant SWR back to my regular 3.842-MHz stomping grounds.

Keeping It Up in the Air

Here in South Carolina, pines are a great source of antenna support but their swaying during summertime thundershowers can wreak havoc on long, unprotected wire antennas. Over the years, I've found a simple shock-absorber system using a run-of-the-mill screen-door spring placed between a support rope and each antenna insulator can save a lot of grief. See Figure 3 for a closer look at the details.

A special aspect of my system is the employment of a "strain limit rope" in parallel with each spring. This piece of rope, approximately twice the length of the unstretched spring, keeps swaying pines from overly taxing the spring and gives a nice visual reference for gauging how much tension the antenna is operating under. It also provides a fail-safe for the inevitable corrosion-caused failure of the spring after several years aloft. It makes a fine bird perch, too.

So, How Does It Play?

Performance on all three bands has been most satisfactory. The 2:1 SWR bandwidth of the 30-meter section far exceeds the band edges. Similar 40-meter bandwidth is about 100 kHz (noticeably narrower than dipoles I've used, and I suspect partially attributable to my guesswork on the 40-meter trap placement). The 75-meter bandwidth is now approximately 150 kHz (slightly narrower than before the traps were installed). Signal reports both ways on all three bands are comparable to any other non-directional HF antennas I've used.

Notes and References

[1] Robert C. Sommer, "Optimizing Coaxial Cable Traps," *QST*, Dec 1984, pp 38-42.

[2] John Grebenkemper, "Multiband Trap and Parallel HF Dipoles-A Comparison," *QST*, May 1985, pp 29-30.

A Two-Band Loop for 30 and 40 Meters

After trying to find a way to place a 30-m delta loop inside an existing 40-m loop, I remembered an article in *All About Cubical Quad Antennas*[1] describing a 1½-λ, or "Mini X-Q," loop. The gain of this antenna was said to be about 1 dB more than a 1-λ loop. I installed a large, ceramic SPST knife switch in the center of the delta-loop's bottom leg (see Fig 11). With this switch open, the full-wave, 40-m loop becomes a 1½-λ, 30-m loop! The resonant frequency of this arrangement was 10.5 MHz. By adding 18-inch wires to the loop at both sides of the switch, I obtained resonance at 10.125 MHz.

Since the bottom of the loop is only 12 ft above ground, it's a simple matter to reach the band switch from ground level. (Caution: High RF voltage appears at the switch when the antenna is used for transmitting on 30 m.) Incidentally, the loop also works well on 15 m (SWR under 2:1 across the band) when set for 40 m, and I have used the 30-m configuration successfully on 80 m with the help of an antenna tuner.—*James Brenner, NT4B*


Insulator Block
Supported by
Tree or Pole
Weatherproof
Connection
23′ RG-11
(Solid Dielectric)
47′ Long
Each Side
PL-258 and
Two PL-259s
(Weatherproofed)
RG-8 to
Shack
Ceramic
Knife
Switch
Insulator
Insulator
to Anchor
to Anchor
12′
18″ Tuning Wires to
Resonate Open Loop
at 10.125 MHz
Total Length (in Feet) of Loop (at 40 M) = $\frac{1005}{F\,(MHz)}$ or 141′

Fig 11—Jim Brenner's 30- and 40-meter loop. Note the 18-inch tuning wires used to lower the antenna's 30-m resonance from 10.5 to 10.125 MHz. The antenna is top-fed via a ¼-λ 40-m matching section. See text.

---

[1] W Orr and S. Cowan, *All About Cubical Quad Antennas* (Wilton, CT: Radio Publications, 1970).

From *QST*, April 1990 (Hints & Kinks)

Feeding an 80-Meter Delta Loop at 160 Meters

After reading "The Full-Wave Delta Loop at Low Height,"[1] I found a satisfactory method of feeding an 80-meter loop at 160 meters. See Figure 1. C1 tunes the antenna to act as a $^3/_4$-λ resonator and allows the SWR at the feed point to be no more than 1.1 to 1 across the 160-meter band. —*Roy C. Koeppe, K6XK*


Loop Wire Length: 268 ft (1005 ÷ f[MHz]) for 3.75 MHz
Open - Wire Feed Line (#12 Conductors, 6" c - c, 30' Long)
Unbalanced 50 - Ω Feed Point
C1
150 pF
TUNING

Figure 1—Roy Koeppe enjoys satisfactory 160-meter operation with an 80-meter delta loop by feeding the loop as shown here. On 80 through 10 meters, Roy takes C1 out of the circuit and feeds the loop via its open-wire feed line and a balanced tuner.

---

[1] D. DeMaw and L. Aurick, *QST* (Oct 1984, pp 24-25).

CHAPTER FIVE

COLLINEAR ANTENNAS

5-1 **The Extended Double-Zepp Antenna**
From June 1938 *QST*

5-7 **Try an Extended Double-Zepp Antenna**
From February 1992 *QST* (Hints & Kinks)

5-8 **Notes on Wire-Antenna Construction**
From March 1992 *QST* (Hints & Kinks)

5-10 **Collinear Arrays**
From *The ARRL Antenna Book* 18th edition

By Hugo Romander, W2NB **From *QST*, June 1938**

The Extended Double-Zepp Antenna

Simple Antenna Structures Having Improved Gain and Horizontal Diversity

The questions of antenna directivity and antenna "gain" are becoming increasingly popular in discussions on antenna systems among amateurs, and it would therefore seem proper to preface an article dealing with directive antenna arrays with a warning, or perhaps a reminder, that one cannot have high gain and radiate in all directions at the same time. To most amateurs this is an obvious fact, but it may not be as well known that this principle is almost equally important in the *vertical* plane. Those of us fortunate enough to have available large open spaces in which to hang wires will find long-wire antennas, such as the "V" and the horizontal diamond, the easiest way to obtain high gain, but the radiation from such antennas is restricted in the vertical plane fully as much as in the horizontal plane. The result may well be that in the very direction such an antenna is supposed to work best, a simple horizontal doublet will put in a far better signal at certain distances.

It would seem, therefore, that the most practical antenna for a variety of distances is one with a fairly wide radiation pattern in the vertical plane.[1] The "stacking" of elements or the use of long wires is not recommended for distances under 1000 miles, except for the very short distances normally reached by the ground wave. The most universal high-gain antenna must restrict its radiation in the horizontal plane only and its height above ground must also be considered to obtain the best compromise in the vertical plane. It is the purpose of this article to discuss the merits of a simple antenna array which combines these desirable features.

THE DOUBLET

Let us discuss, first, the simple doublet, since this antenna will serve admirably as our basis of reference or comparison. To be more specific, consider this doublet as suspended horizontally and fed at one end in the time-honored fashion of the Zepp feeder, as in Figure 1A. Ignoring, for the moment, the fact that the open-ended feeder wire will be at somewhat higher potential than the other feeder wire and will therefore radiate, the horizontal radiation pattern about this doublet, if you're lucky, will be about as shown on Figure 2. Of course, it is assumed the antenna is sufficiently remote from power-line wires and house plumbing to be unaffected by such linear conductors, since our problem is complicated enough without having to consider the mutual impedance between our doublet and the neighbor's b.c.l. antenna!

This pattern of the horizontal doublet is, no doubt, familiar to most amateurs. Less familiar, perhaps, is the vertical radiation pattern (in the direction of maximum horizontal radiation) as shown in Figure 3. Here it is assumed that the height of the doublet above ground is one-half wavelength and that the earth has perfect conductivity. Fortunately, even the relatively low-conductivity soil and sand on Long Island reflects a high percentage of the horizontally polarized waves radiated at angles less than 50° to the earth's surface. Such reflected



Figure 1—Basic Antenna Configurations (A) The half-wave Zepp; (B) Double Zepp or "two half-waves in phase"; (C) Extended double-Zepp.

---

[1] Although this viewpoint appears to be opposed to that expressed in the article "Simple Directional Arrays Using Half-Wave Elements," by N. C. Stavrou, in May, 1938 *QST* there is no actual conflict. As the present author points out, the broad vertical characteristic is to be preferred when the antenna is to give optimum results over short as well as long distances; the former article was concerned with long-distance transmissions, where the lowest possible angle gives best results under nearly all conditions. The type of work to be carried on naturally will be a determining factor. In any event, the simpler structures are not likely to be too sharp in either plane for satisfactory general work. —EDITOR



Figure 2—Horizontal pattern (relative field strength) of a doublet half-wave antenna.



Figure 3—Vertical-plane pattern for a horizontal antenna, 1/2-wave above perfect earth in direction of maximum radiation.



Figure 4—Horizontal pattern of a double-Zepp or two half-waves in phase.

waves, combining with the direct radiation from the antenna within the range of vertical angles in which we are most interested, are responsible for a maximum gain of nearly 6 db over the same doublet in "free space"; that is, without the presence of the earth.

This gift of 6 db must not be taken too much for granted, however. Consider the fact that most amateur communications at high frequencies utilize vertical angles ranging from 10 degrees to 50 degrees. That 6 db must, therefore, come from radiations reflected from the earth's surface quite some distance from the doublet, and in the desired direction of transmission. If the ground slopes sharply upward, or houses or wires are in this area, it becomes questionable, indeed, whether any great portion of the available 6 db is realized. This is especially true for the lower angles of radiation, but usually nothing can be done about this situation, so let us see if we can make up for our ground reflection losses by increasing the horizontal directivity.

THE DOUBLE-ZEPP

By the simple expedient of attaching another doublet to the open-ended terminal of the Zepp feeder, as in Figure 1B, and hanging this doublet parallel and coaxial with the original doublet, an appreciable gain may be obtained. The horizontal radiation pattern will be as shown in Figure 4. The gain should measure about 1.9 db, corresponding to a 55 per cent increase in power. This antenna is widely used among amateurs and is popularly known as the "double-Zepp" antenna, or "two half-waves in phase." A fair amount of gain and a reduction in interfering signals from end-wise directions is easily realized, but the gain is rather disappointing, since it would seem one is entitled to 100 per cent gain in power when doubling the number of radiating members.

The reason why only 1.9 db is realized with the double-Zepp is made clear only after a mathematical study of the situation. Briefly, the close proximity of the two doublets causes a mutual coupling between them, and this coupling (mutual impedance) has an adverse effect on the radiation resistance insofar as gain in the broadside direction is concerned. Obviously, the thing to do is to move the doublets further apart, but this complicates the method of feed. A much simpler way of obtaining increased gain was evolved by Mr. A. A. Alford, of Mackay Radio and Telegraph Company, from the principles discussed in Mr. G. H. Brown's article on broadcast antennas in the Proceedings of the I.R.E. for January, 1936. Mr. Alford presented this idea in a paper delivered at an I.R.E. meeting in Washington.

EXTENDED DOUBLE ZEPP

The gain of the double-Zepp may be increased from 1.9 to 3.0 db by the simple expedient of increasing the length of each doublet until its electrical length is 0.64



Figure 5—Horizontal pattern of double 230-degree Zepp

wavelength instead of 0.5 wavelength. In electrical degrees the double-Zepp consists of two 180-degree elements; the *extended* double-Zepp for maximum gain should consist of two 230-degree elements. See Figure 1C. In this way the power gain may be increased from 55 per cent to 100 per cent. The gain decreases rapidly for extensions beyond 230 degrees, and therefore, when operating over a band of frequencies, each of the two elements should not exceed 240 degrees for the highest frequency. The horizontal pattern for the double 230-degree Zepp is shown in Figure 5. The vertical pattern in a plane perpendicular to the antenna will be the same as for the simple doublet.

ANTENNA IMPEDANCE

The impedance of this antenna at the termination of the transmission line is of interest, since it has an important bearing on the standing-wave ratio of current or voltage in the line, and it will be compared with that of the ordinary double-Zepp. The double 180-degree antenna presents an impedance of approximately 4400 ohms of almost pure resistance as a termination for the transmission line. This value will be slightly affected by the size of wire used in the antenna and, to a moderate extent, by the height above ground or the influence of nearby conductors, and so the "free space" value is given for No. 14 wire. With this antenna and a 600-ohm surge-impedance line the ratio of maximum to minimum current along the line will be 4400 divided by 600, or 7.3. Incidentally, the terminating resistance of the simple Zepp-fed doublet is about 12,000 ohms, resulting in a standing wave ratio of 20 on our 600-ohm line. For calculation of the surge impedance of the line the reader is referred to *The Radio Amateur's Handbook*.

The impedance at the center of the double 230-degree antenna is not a pure resistance, and hence its effect upon the transmission line be such that maxima or minima of voltage and current along the line will not be odd multiples of a quarter wave from the antenna, as with the ordinary Zepp or double-Zepp antennas. As might be expected, the current or voltage maxima will be shifted towards the antenna, since the two doublets are longer than normal, and this shift is approximately 0.13 times the wavelength. At any rate, the antenna impedance is such that the equivalent pure resistance at any voltage maximum will be about 6000 ohms; that is, the standing-wave ratio will be 10 on a 600-ohm line.

Knowing the standing-wave ratio, it becomes an easy matter to calculate the input resistance to the transmission line if it was cut, let us say, at any current maximum. Thus, for the simple Zepp-fed doublet, this resistance would be 600 divided by 20, or 30 ohms. For the ordinary double-Zepp antenna this resistance would be 600 divided by 7.3, or 92 ohms. For the double 230 degree antenna this resistance would be 600 divided by 10, or 60 ohms. Those who do not use correcting stubs or other methods to obtain a "flat" line (standing wave ratio of 1), but who cut their transmission lines at the maximum current point after the manner of the "tuned feeder," will find these figures useful in calculating the power output of their transniitters.

FEED LINES

However, the use of flat lines, in amateur circles usually referred to as untuned lines, is becoming increasingly popular as their merits are more generally known, and the figures given are essential in calculating the length and position, for example, of a correcting stub, the latter being one of the simplest devices for reducing the standing-wave ratio to unity. A discussion of the use of the correcting stub may be found on page 307 of the *Handbook* (15th edition) where a table indicates the lengths and positions of the stub for various standing-wave ratios. The shorted stub or "loop" will generally be most practical, and some idea of dimensions may be obtained from the fact that when using the double 230-degree Zepp on 14,200 kHz the stub should be 3.5 feet long; that is, it should be composed of the same kind of wire as is used in the transmission line, this wire being 7 feet long and bent to form a U-shaped rectangle with a width equal to the transmission line. At the frequency mentioned, where each extended doublet is 43 feet long, the correct location for the stub will be about 8 feet from the antenna.

Ordinarily the best place to introduce power into an antenna is at a point symmetrically located with respect to the opposite ends of the system. This will not always be practical, because of space limitations, and hence it may become necessary to feed the extended double-Zepp antenna at one end in true Zepp fashion. Some sacrifice in gain will result, due, for the most part, to unequal distribution of current between the two doublets and to radiation from the feeder because it has an unbalanced load. Physical dimensions of feeder, extended doublets, and phasing stub are shown in Figure 6. Note that the phasing-stub length is shorter than a quarter wavelength, but by an amount not exactly



Figure 6—End-fed double 230-degree Zepp with 600-ohm non-resonant transmission line.

equal to the extension of each doublet beyond a half wavelength. This discrepancy is due to interaction between the doublet wires and the wires of the phasing stub. Again a reference frequency is given to simplify calculation of lengths at other frequencies by inverse proportion. The figures given should be regarded as approximations, and tests made individually to determine dimensions and positions of important elements.

ANTENNA ADJUSTMENTS

One of the most effective methods of adjusting an antenna system is to use the transmitter to excite, at the desired frequency, another antenna stretched out, perhaps temporarily, at least 8 or 10 feet from the ground. This "exciter" antenna should preferably be at least one-half wavelength away from the antenna to be adjusted. If the two are parallel to each other, so much the better. Using the end-fed extended double-Zepp antenna as an example, the first consideration is the length of each doublet, and this brings up the problem of "end-effect." We have approximately solved this by cutting our doublets 5 per cent short of the theoretical length. Actually the end effect, which normally exists only at the ends of the antenna, depends on the wire size and the size of the insulator fitting (if metal caps are used), as well as the frequency. Moreover, the end-effect does not vary quite as rapidly as a direct function of the wavelength, so that if an end-effect of 1 foot is correct at 14,200 kHz, it is more nearly 1.5 feet than 2 feet at 7100 kHz.

The theoretical "uncorrected" length of each half of an extended double-Zepp antenna at 14,200 kHz is 44.3 feet. The end-effect may be no more than 1 foot, but since it is better that the antenna be a little too short than too long, let's make the correction 1.3 feet, so that each half will be exactly 43 feet long. At the center insulator which separates the two halves a "stub" must be connected, if the system is to be end-fed. Now, this stub will, take the form of a transmission line shorted at the end opposite from the antenna, and for the frequency under consideration its shortest length will be about 12 feet. Since it is our intention to make this transmission line somewhat longer than the anticipated proper position of the short in order to permit locating the correct position by sliding the short up or down, and furthermore since 12 feet will ordinarily not bring the probable correct shorting point at a convenient distance from ground, it will be more practical to add any multiple of a half wavelength (34 feet) to the transmission line and do the shorting experiment at a point along the line accessible from the ground.

With all this done and with the Zepp feeder *not* attached to the main antenna (why not use it to feed the exciter antenna?), power may be fed to the exciter antenna and with a sensitive r.f. instrument connected in the short on the "stub," a position of the short may easily be found where maximum current flows. This assumes that the main antenna has been hauled up into its normal operating position. Note this maximum-current position of the short and measure in exact multiples of one-half wavelength from this point towards the antenna, thus arriving at the nearest point to the antenna at which a short may be placed. This will give the shortest possible center stub. Of course, it is not necessary that the center stub be made that short, since very little loss will be incurred if it is left a half-wave or even a wavelength longer–that is, if the wire is not smaller than No. 14. The Zepp feeders may now be attached to either end of the antenna, as it is now ready for operation.

The method of adjusting the center stub just outlined is also useful where it is desired to feed any of the antenna forms discussed above with an untuned transmission line—that is, a transmission line terminated by its surge impedance. Using the example cited in the previous paragraph, let us assume the point of maximum current through the short has been found and, after soldering a piece of wire across the line at this point, the extra length of transmission line is chopped off. The two-wire line from the transmitter may now be tapped in above this shorted end of the stub, and it is only a question of position of the feeder tap from the shorted end to terminate the line properly. See Figure 7. This point will be approximately 3.3 feet from the short for a 600-ohm transmission line. Of course, when all this is done, we will have the same transmission line with correcting stub discussed earlier in this article.

LINE-CURRENT MEASURING DEVICES

The same principle holds true for the double Zepp and for center feeding the simple doublet, the only ambiguous point being that of knowing when the transmission line from the transinitter is connected at the right distance from the closed end of the stub. The transmission line will be properly terminated when there is no appreciable variation in voltage or current along the line, and hence some method must be used which will detect any variation in voltage or current. Simplest of all is the old-fashioned wood-covered lead pencil, for with this device bright arcs may be drawn from either wire and the voltage at any one point judged by comparison with the voltage at another point. This method has the disadvantage of being both crude and liable to error due to the presence of second or higher-order harmonics in the output from the transmitter. A little better is the small neon bulb, but this is also a voltage-operated device and subject to harmonic distortion. Then there is the current-squared galvanometer with a few small turns of wire connected to its terminals, these turns being coupled to either line. This device is quite good if one is careful to use constant coupling to the wire, but its disadvantages are that coupling between the meter and line is both inductive and capacitive, causing the meter to read differently according to how it is held up to the line, and that the meter will also be influenced by harmonics.

The most satisfactory device seems to be a sensitive galvanometer in a miniature tuned circuit coupled to the line. Such a device combines sensitivity with freedom from harmonic distortion, but the effects of capacity are still there to some extent. The tuned circuit should therefore be carried along the line with its position relative to the plane of the two wires maintained constant. See Figure 8. Checking along one of the two wires only is usually sufficient, but if one suspects an unbalance exists, the other line should also be checked. If the antenna system is reasonably symmetrical, unbalanced currents will most likely be due to improper coupling to the transmitter, but that is another story. At any rate, if a cur-



Figure 7—Center-fed double 230-degree Zepp with 600-ohm transmission line.


2" to 3" stiff wire parallel to and maintained at a fixed distance from either feeder
Transmission Line
About 0.5 inch
Plug - In Coil
Galv.

Figure 8—Portable line-current indicator.

rent maximum (voltage minimum) appears at the junction of transmission line and stub, the connection to the stub is too near the shorted end, and if the current is a minimum the opposite, of course, will be true. If the current maximum or minimum (assuming standing waves actually exist) does not occur near the stub, there has been a slip-up somewhere in the procedure, for this will be evidence that the stub itself did not tune the antenna to resonance.

PARASITIC ELEMENTS

The use of spreaders several feet in length to support each end of a "flat-top" antenna composed of two wires is again becoming popular, and for a good reason. Gains of around 5.5. db for a bi-directional array and around 7 db for a unidirectional array are thus made possible. One of the most promising arrangements is that of two double-230-degree antennas supported parallel to each other only 0.2 wavelength apart, as illustrated in Figure 9. Antenna A is excited by the transmitter using the same technique as when exciting a single double-230-degree antenna. Antenna B may be tuned by proper positioning of a short on its stub to become either a director or a reflector. In fact, this stub might be extended by multiples of a half wavelength to enter the operating room where, by means of a single switch the shorting position may be changed from that corresponding to a director to the position corresponding to a reflector, thus reversing the directivity of the antenna system. Information as to the gain of such an antenna system when one antenna is used as a director is not available, but when it is used as a reflector and adjusted to give a *minimum* signal to the rear, the signal forward will be 7 db better than a simple doublet, and the signal backwards will be 7 db less than from a doublet, resulting in a front-to-back ratio of 14 db. Adjustment of the reflector shorting bar should be on the basis of minimum backward signal from the antenna, or minimum signal received from a station in that direction when using the antenna system for reception, since this adjustment can be made more accurately than one resulting in maximum front signal. This will minimize QRM for both transmitting and receiving. The same principles hold true when adjusting the auxiliary antenna for use as a director.

If adjustments of the auxiliary antenna are to be made when transmitting and an ammeter is temporarily inserted in the shorting bar, minimum backwards signal will occur for the reflector when the short is moved slightly further from the antenna than that position corresponding to maximum current through the short. For the director, optimum conditions will be obtained when the short is slightly closer to the antenna than the maximum shorting current position. From this it can be seen that the proper adjustment of the auxiliary antenna is quite critical and certainly very important. Since field strength instruments are not generally available, a receiver fitted with a signal strength indicator of some sort located within a few miles of the antenna and in the desired direction should prove to be the next best thing. Connecting your own receiver to the antenna, with the other fellow transmitting, is perhaps even more practical in search for that minimum-signal adjustment.

The presence of the auxiliary antenna only 0.2 wavelength away from the driven antenna and adjusted properly for maximum forward or backward radiation will obviously affect the radiation resistance and impedance of the driven antenna. As a result, if the auxiliary antenna is left open-circuited and the stub on the driven antenna is adjusted in accordance with the method previously given, this adjustment will not be correct when the auxiliary antenna is, in turn, properly tuned. Moreover, the impedance of the driven antenna will differ slightly according to whether the auxiliary antenna is tuned as a director or as a reflector. If quick change from reflector to director is contemplated, some sort of compromise is indicated in the adjustment of the stub on the driven antenna. From a practical standpoint, however, the adjustment of the auxiliary antenna should be made first, be it reflector or director, with the driven antenna excited by the two-wire transmission line without a correcting stub. This may require temporary adjustment of the transmission-line length, either physically or by means of series coils or condensers, to bring a low-impedance point at the coupling coil to the transmitter in order to load the latter satisfactorily. In fact, if the line length from antenna to transmitter is not more than a wavelength or so, the reduction in line losses resulting from the use of a correcting stub is hardly worth the trouble of installing it. The point is, if a "flat" line is desired, adjustments of the stub at the driven antenna should not be made until after the auxiliary antenna has been tuned to give the desired radiation pattern.



Figure 9—Double 230-degree Zepp with parasitic reflector-director.

LARGER COLINEAR ARRAYS

Now let us suppose our backyard is big enough to hang up more than two doublets end to end. An interesting possibility would be a four-element array of 230-degree elements. But here the principles of the extended double-Zepp must be carefully considered in designing the length of each element and the length of the phasing stub separating them. The actual arrangement will be as shown in Figure 10. Both degrees and dimensional designations are used to indicate the electrical and physical length of each element. The length of the stubs indicated is approximate only and must be adjusted for best results. The lengths of the various antenna elements as shown, however, may be assumed correct. The transmission line can be tapped on to any of the stubs, but connection to the center one will give the greatest gain.



Figure 10—Four-element array with 230-degree elements.

The principle of the design shown for four elements is to provide the same separation in space between each doublet center as is provided between the two doublet centers in the double-230-degree antenna. Each phasing stub will, of course, be considerably shorter than a quarter wavelength, and when adjusting their length to tune the whole antenna to resonance, all three stubs must be made the same length; that is, if one is shortened two inches, the other two must also be shortened by two inches, assuming they were all the same length to start with.

This may prove to be an awkward and tedious method of adjustment, but the procedure may be simplified by adjusting the length of the center stub only as a first approximation. The use of an "exciter" antenna temporarily rigged nearby is assumed. If it is found the center stub must be shorter than the other two stubs by 3 feet, for instance, in order to obtain maximum current through its shorting bar, the other two stubs should be shortened by 1 foot and a new position found for maximum current through the center stub. This new position should correspond closely to equal length for all three stubs. This procedure of tuning the four-element array should be followed even though a stub at the center will not be used, finally, its place being taken by the transmission line itself. Such a connection will result in standing waves along the line and it will have to be "tuned" to permit easy coupling to the transmitter or receiver.

The horizontal pattern of the four-element array just described will have two major lobes at right angles to the antenna and several minor lobes of small amplitude. The gain in actual practice has proved to be greater than anticipated, and probably is more than 7 db. The major lobes will be much narrower than for the double-230-degree antenna, thus requiring more careful "aim" in erecting the array, or provisions for swinging it about. It is assumed this array, as well as the others described, is hung horizontally. It may be hung vertically, of course, but the possible restrictions due to sharp directivity in the vertical plane should then be considered. In general, the horizontally polarized antenna will prove most practical, chiefly because the ground reflection usually encountered with vertically polarized radiations is inferior, and because high masts are not often available.

The adjustment of the antennas described in this article may seem a bit involved as compared with the simple doublet or the double-Zepp antenna, but the extra gain thus made available should make their use worthwhile. For that matter, the double-230-degree antenna need not be tuned at all, its construction being made in accordance with the dimensions given and the transmission line tuned to fit the transmitter. In this respect the simplest of all directive antennas, size and gain also taken into consideration, is the extended double-Zepp.

From *QST*, February 1992 (Hints and Kinks)

Try an Extended Double-Zepp Antenna

Although the extended double Zepp (EDZ) antenna (Figure 1) has been in just every antenna handbook since the year one, hams seldom use it. Its overall length is 1.28 wavelengths (1.28 λ), and it's bidirectional broadside. Fed with open-wire line and a balanced antenna tuner, an EDZ also makes a fine multiband antenna. Let's look at an extended double Zepp for 17 meters. We can calculate the overall length of its two wire elements with the formula

$$\frac{984}{f\,(\text{MHz})} \times 1.28 = \text{length in feet} \qquad \text{(Eq 1)}$$

Using this formula, an 18.15-MHz EDZ works out to be 69.4 feet long. At this frequency, the EDZ exhibits, 3 dBd gain [*AB* page 8-34][1] in a figure-8 pattern with two major and four minor lobes. It still performs usefully, when operated on several bands lower in frequency than 17, however. At 20 meters, a 17-meter EDZ acts as two slightly long half waves in phase, exhibiting between 1.6 and 2 dBd gain [*AB* page 8-32]. At 40 meters, it's a slightly long 1/2-λ dipole [*AB* page 2-16,2-17,3-11 and 3-12]. All of these modes are directional broadside if the EDZ is positioned at least 1/2-λ high at 40 meters [*AB* pages 3-8 and 3-9]. At 15 meters, it exhibits a four-leaved-clover pattern, with minor lobes broadside; at 10 and 12 meters, it's close to two full waves in phase and produces a pattern similar to that at 15 meters. It can even be used as a short 75-meter dipole–not bad for a 70-foot piece of wire.

Scaled for 28.7 MHz–43 feet, 10 inches long—the extended double Zepp gives a 3-dBd-gain, figure-8 pattern at 10 meters and a similar pattern with a bit less gain at 12 meters. It acts as two halfwaves in phase at 15 meters, with about 1.6 dBd gain and a figure-8-pattern. At 17 and 20 meters, it's somewhat long for a half-wave dipole; a tuner can make it work at 40. On all of these bands, assuming that it's at least 1/2 λ high at its lowest band of operation, the 10-meter EDZ is directional broadside.

There's nothing magic about the extended double Zepp. It's a tried-and-true dipole that offers useful gain at its design frequency and good multiband performance. *–Bob Baird, W7CSD*

---

[1] This and the other AB references in this item refer to pages in G. Hall, ed, *The ARRL Antenna Book*, 16th ed (Newington: ARRL, 1991).



Figure 1—Evolution of the extended double Zepp antenna. At A, the classic Zepp—a 1/2-λ wire end-fed via an open-wire feeder operated with one of its two wires unterminated. (Antenna lore tells us that this feed method received its name from its use in zeppelin radio installations.) Commonly, Zepp systems use a feeder length of 1/4 λ (or an odd multiple thereof) to transform the antenna's high feed-point impedance to a low impedance at the feeder terminals. Assuming efficient feed, this system exhibits 0 dBd gain—that is, *no gain* relative to a half-wave dipole cut for the same frequency and erected in the same position.

B shows a double Zepp, also known as *two half waves in phase* or (incorrectly) a center-fed Zepp. This is a form of collinear antenna because each 1/2-λ wire acts as an element, and because both elements lie along one line. It's also a *dipole*—a *full-wave* dipole that exhibits about 1.6 dB gain relative to a half-wave dipole in the same position. As with the Zepp, feeders cut to an odd multiple of 1/4 λ make for least hassle feed with the double Zepp, but a good balanced antenna tuner should be able to handle whatever impedance appears at the feed-line input terminals.

A double Zepp becomes an *extended* double Zepp when you make its wires 0.64 λ long instead of 0.5 λ. Its gain increases, too—to about 3 dB relative to a half-wave dipole in the same position and cut for the same frequency.

The rough feed-point impedances shown here are for wire elements (fatter elements, such as those made of aluminum tubing, will lower these values somewhat) and convey only the resistive portion of the antennas' impedance. For more on the extended double Zepp antenna, see *The ARRL Antenna Book* and J. Reh, "An Extended Double Zepp Antenna for 17 Meters," *QST*, December 1987, pp 25-27.

From *QST*, March 1992 (Hints and Kinks)

Notes on Wire-Antenna Construction

Robert J. Zavrel, W7SX, seconds last month's extended-double-Zepp hint as he reports on how he keeps three EDZs high in trees for world-encompassing coverage (Figure 1) at 80, 40 and 20 meters—*Ed.*

What is a terminal DX hound to do when he suddenly moves to a rural area and has access to the stuff dreams are made of: several 100-foot-plus ponderosa pine trees atop a gentle rise in a reasonably clear area, only 500 feet from his house? The answer: *Wire antenna arrays!* A few months spent confronting the practical problems of installing three extended-double-Zepp antennas in these trees has yielded some solutions that I'd like to share.

Counterweights. Although my pines are wonderful supports for wire antennas, they have a few minor disadvantages. Among these is the fact that they sway in the wind. Because too much tension can snap antenna wires and supporting cords in strong winds, a wire-antenna engineer must compensate for variable tension in a horizontal wire antenna strung between two of these majestic plants. The textbook solution to this problem involves installing pulleys where the wires meet the trees. Ropes attached to the wire-end insulators pass over the pulleys and connect to counterweights hanging near the ground. Installed with antenna-to-counterweight lines of sufficient length, such a system also allows the antenna to be raised and lowered without further climbing.

My system includes three extended double Zepps, each fed with 450-Ω, low-loss TV twinlead. Including its supporting lines, each EDZ spans 165 feet. Counterweighting the ends of these antennas serves two purposes: It keeps tree movement from snapping them, and it keeps their wires reasonably horizontal. But how much weight is required, and what should the weights consist of? Charts exist for computing tension necessary to keep a singlewire span taut, but the presence of a twinlead feeder at the span's center renders such charts useless.

Enter experimentation! I strung the extended double Zepp, minus feed line and plus pulleys, between the two trees at about 15 feet above ground. Next, I weighed the feed line. Then I located an object of simi-

Figure 1—Proving the multiband effectiveness of the extended-double-Zepp antenna, "The W7SX Wire Farm" consists of three center-fed wires supported by three ponderosa pines that form a nearly equilateral triangle atop a small rise. (Total cost for the system, including all hardware, wire, feeders, control lines and $150 fee for the tree climber, approximately $700.) Because the ground slopes to the south at about a 10° angle, this system works best for VK, ZL and long paths into Europe and Asia. To the north, the horizon is essentially level. Table 1 shows how the antennas function on the system's three bands.

You're not a second-class citizen just because your best antenna is a dipole. You can easily set the pattern and gain of center-fed horizontal wire antennas by adjusting their length. Get the wires as high as possible, keeping them away from nearby objects, use a tuner and open-wire line for multiband feed, and have a blast! Surrounding terrain may greatly influence your antenna's DX performance.



Table 1
The W7SX Extended Double Zepp Trio

	Length	*Height*	*Band/Antenna Mode*		
			80	*40*	*20*
Antenna 1	82 ft	98 ft	SD	LD	EDZ
Antenna 2	82 ft	98 ft	SD	LD	EDZ
Antenna 3	164 ft	82 ft	LD	EDZ	LW

SD = short dipole; LD = long dipole; EDZ = extended double Zepp, LW = long wire (dipole legs 1 λ or more in length). Because a dipole longer than $^1/_2$ λ exhibits gain over a half-wave dipole in the same position, these three antennas exhibit gain over a half-wave dipole in all but the SD mode.



Figure 2—Bob Zavrel uses a triangular relay box to switch feeders between antennas mounted in a triangular pattern; a square box in this situation twists feeders, en-couraging antenna sway to break feeder wires. *(W7SX photo)*

lar weight, put it in a plastic bag, tied the bag at the antenna feed point, and experimented with various weights. Two 15-lb weights kept the antenna wire horizontal without overtension.

Next, I needed to construct multiple 15-lb weights at minimum cost—weights that had to be long and narrow to avoid collisions with the supporting trees and other nearby objects. I decided that slumpblock bricks inside a 2 × 4 wood frame would be satisfactory. (Slump blocks are long, narrow and about 12 lbs each; some are just as wide as a standard 2 × 4.) Including bricks, wood and nails, each weight cost me about $1.50, so the price was right—and 2 × 4s can be easily drilled for attaching ropes.



Figure 3—A combination feedthrough insulator/strain relief made of fasteners and two plexiglass plates.

The relay box. A square relay box centered between three antennas twists the antennas' open-wire feeders at the feed points. I solved this problem for a triangular, relay-switched vertical array[1] and my three-EDZ system by building triangular relay boxes (Figure 2). (Use redwood, cedar or cypress and weatherproof the box with sealant.[2]) Plexiglass plates and screws insulate the feeder wires from the box, continue the feeders to the relays and provide strain relief (Fiureg 3).

Results with the system. Using a 600-W amplifier, I often get through pileups first on long path. Short path to Europe is more difficult because the ground slopes slightly upward in that direction. My blissful encounters with nature's gift to the RF enthusiast continue!–*W7SX*

---

[1] See Volume 3 of *The ARRL Antenna Compendium*.

[2] In my work with wire antennas, I discovered a reference on wood that may be of interest to amateurs: *Wood Handbook: Wood as an Engineering Material* (Washington, DC: US Department of Agriculture, rev 1987), 466 pages (for sale by the Superintendent of Documents, US Government Printing Office, Washington, DC 20402). This text describes, among many mechanical and structural considerations, electrical qualities of wood that come into play when wood supports are used in RF fields.

Collinear Arrays

Collinear arrays are always operated with the elements in phase. (If alternate elements in such an array are out of phase, the system simply becomes a harmonic type of antenna.) A collinear array is a broadside radiator, the direction of maximum radiation being at right angles to the line of the antenna.

Power Gain

Because of the nature of the mutual impedance between collinear elements, the feed point resistance is increased as shown earlier in this chapter (Figure 9). For this reason the power gain does not increase in direct proportion to the number of elements. The gain with two elements, as the spacing between them is varied, is shown by Figure 38. Although the gain is greatest when the end-to-end spacing is in the region of 0.4 to 0.6 λ, the use of spacings of this order is inconvenient constructionally and introduces problems in feeding the two elements. As a result, collinear elements are almost always operated with their ends quite close together–in wire antennas, usually with just a strain insulator between.

With very small spacing between the ends of adjacent elements the theoretical power gain of collinear arrays is approximately as follows:

2 collinear elements—1.6 dB
3 collinear elements—3.1 dB
4 collinear elements—4.2 dB

More than four elements are rarely used.

Directivity

The directivity of a collinear array, in a plane containing the axis of the array, increases with its length. Small secondary lobes appear in the pattern when more than two elements are used, but the amplitudes of these lobes are low enough so that they are not important. In a plane at right angles to the array the directive diagram is a circle, no matter what the number of elements. Collinear operation, therefore, affects only E-plane directivity, the plane containing the antenna. At right angles to the wire the pattern is the same as that of the individual 1/2-λ elements of which it is composed.

When a collinear array is mounted with the elements vertical, the antenna radiates equally well in all geographical directions. An array of such "stacked" collinear elements tends to confine the radiation to low vertical angles.

If a collinear array is mounted horizontally, the directive pattern in the vertical plane at right angles to the array is the same as the vertical pattern of a simple $^1/_2$-λ antenna at the same height (Chapter 2).

TWO-ELEMENT ARRAY

The simplest and most popular collinear array is one using two elements, as shown in Figure 39. This system is commonly known as "two half-waves in phase." The manner in which the desired current distribution is obtained is described in Chapter 26. The directive pattern in a plane containing the wire axis is shown in Figure 40.

Depending on the conductor size, height, and similar factors, the impedance at the feed point can be expected to be in the range from about 4 to 6 kΩ, for wire antennas. If the elements are made of tubing having a low λ/dia (wavelength to diameter) ratio, values as low as 1 kΩ are representative. The system can be fed through an open-wire tuned line with negligible loss for ordinary line lengths, or a matching section may be used if desired.

THREE- AND FOUR-ELEMENT ARRAYS

When more than two collinear elements are used it is necessary to connect "phasing" stubs between adjacent elements in order to bring the currents in all elements in phase. It will be recalled from Chapter 2 that in a long wire the direction of current flow reverses in each $^1/_2$-λ section. Consequently, collinear elements cannot simply



Figure 38—Gain of two collinear $^1/_2$-λ elements as a function of spacing between the adjacent ends.



Figure 39—A two-element collinear array (two half-waves in phase). The transmission line shown would operate as a tuned line. A matching section can be substituted and a nonresonant line used if desired.

be connected end to end; there must be some means for making the current now in the same direction in all elements. In Figure 41A the direction of current flow is correct in the two left-hand elements because the transmission line is connected between them. The phasing stub between the second and third elements makes the instantaneous current direction correct in the third element. This stub may be looked upon simply as the alternate $^{1}/_{2}$-λ section of a long-wire antenna folded back on itself to cancel its radiation. In Figure 41A the part to the right of the transmission line has a total length of three half wavelengths, the center half wave being folded back to form a $^{1}/_{4}$ λ phase-reversing stub. No data are available on the impedance at the feed point in this arrangement, but various considerations indicate that it should be over 1 kΩ.

An alternative method of feeding three collinear elements is shown in Figure 41B. In this case power is applied at the center of the middle element and phase-reversing



Figure 40—Free-space E-plane directive diagram for the two-element collinear array of Fig 39. The axis of the elements lies along the 90°-270° line. This is the horizontal pattern at low wave angles when the array is horizontal. The array gain is approximately 1.6 dBd (3.8 dBi).



Figure 41—Three and four-element collinear arrays. Alternative methods of feeding a three-element array are shown at A and B. These drawings also show the current distribution on the antenna elements and phasing stubs. A matched transmission line can be substituted for the tuned line by using a suitable matching section.

stubs are used between this element and both of the outer elements. The impedance at the feed point in this case is somewhat over 300 Ω and provides a close match to 300-Ω line. The SWR will be less than 2 to 1 when 600-Ω line is used. Center feed of this type is somewhat preferable to the arrangement in Figure 41A because the system as a whole is balanced. This assures more uniform power distribution among the elements. In A, the right-hand element is likely to receive somewhat less power than the other two because a portion of the fed power is radiated by the middle element before it can reach the element located at the extreme right.

A four-element array is shown in Figure 41C. The system is symmetrical when fed between the two center elements as shown. As in the three-element case, no data are available on the impedance at the feed point. However, the SWR with a 600-Ω line should not be much over 2 to 1. Figure 42 shows the directive pattern of a four-element array. The sharpness of the three-element pattern is intermediate between Figures 40 and 42, with four small minor lobes at 30° off the array axis.

Collinear arrays can be extended to more than four elements. However, the simple two-element collinear array is the type most used, since it lends itself well to multiband operation. More than two collinear elements are seldom used because more gain can be obtained from other types of arrays.

Adjustment

In any of the collinear systems described the lengths of the radiating elements in feet can be found from the formula $468/f_{MHz}$. The lengths of the phasing stubs can be found from the equations given in Chapter 26 for the type of line used. If the stub is open-wire line (500 to 600 Ω impedance) it is satisfactory to use a velocity factor of 0.975 in the formula for a 1/4-λ line. On-the-ground adjustment is, in general, an unnecessary refinement. If desired, however, the following procedure may be used when the system has more than two elements.

Disconnect all stubs and all elements except those directly connected to the transmission line (in the case of feed such as is shown in Figure 41B leave only the center element connected to the line). Adjust the elements to resonance, using the still-connected element. When the proper length is determined, cut all other elements to the same length. Make the phasing stubs slightly long and use a shorting bar to adjust their length. Connect the elements to the stubs and adjust the stubs to resonance, as indicated by maximum current in the shorting bars or by the SWR on the transmission line. If more than three or four elements are used it is best to add elements two at a time (one at each end of the array), resonating the system each time before a new pair is added.

THE EXTENDED DOUBLE ZEPP

An expedient that may be adopted to



Figure 42—E-plane pattern for a four-element collinear array. The axis of the elements lies along the 90°-270° line. The array gain is approximately 4.2 dBd (6.4 dBi).



Figure 43—The extended double Zepp. This system gives somewhat more gain than two 1/2-λ collinear elements.



Figure 44—E-plane pattern for the extended double Zepp of Fig 43. This is also the horizontal directional pattern when the elements are horizontal. The axis of the elements lies along the 90°-270° line. The array gain is approximately 3 dBd.

obtain the higher gain that goes with wider spacing in a simple system of two collinear elements is to make the elements somewhat longer than $^{1}/_{2}$ λ. As shown in Figure 43, this increases the spacing between the two in-phase $^{1}/_{2}$-λ sections at the ends of the wires The section in the center carries a current of opposite phase but if this section is short the current will be small; it represents only the outer ends of a $^{1}/_{2}$-λ antenna section. Because of the small current and short length, the radiation from the center is small. The optimum length for each element is 0.64 λ. At greater lengths the system tends to act as a long-wire antenna, and the gain decreases.

This system is known as the "extended double Zepp." The gain over a $^{1}/_{2}$-λ dipole is approximately 3 dB, as compared with approximately 1.6 dB for two collinear $^{1}/_{2}$-λ dipoles. The directional pattern in the plane containing the axis of the antenna is shown in Figure 44. As in the case of all other collinear arrays, the free-space pattern in the plane at right angles to the antenna elements is the same as that of a $^{1}/_{2}$-λ antenna—circular.

CHAPTER SIX

WIRE BEAMS

6-1 **The K6NA 80-Meter Wire Beam**
From *The ARRL Antenna Compendium Volume 5*

6-10 **Construct a Wire Log-Periodic Dipole Array for 80 or 40 Meters**
From August 1986 *QST*

6-14 **Input Impedance of LPDA Antennas**
From October 1986 *QST* (Technical Correspondence)

6-15 **The WA1AKR 40- and 75-Meter Slopers**
From August 1980 *QST* (Technical Correspondence)

6-16 **Inexpensive 30-Meter Beam Antenna**
From June 1983 *QST* (Hints & Kinks)

6-17 **Try the "FD Special" Antenna**
From June 1984 *QST*

6-21 **Build a 4X Array for 160 Meters**
From February 1985 *QST*

6-25 **The 'BRD Zapper: A Quick, Cheap and Easy "ZL Special" Antenna**
From June 1990 *QST*

6-27 **Combination Driven Arrays**
From *The ARRL Antenna Book* 18th edition

By Glenn Rattmann, K6NA

From *The ARRL Antenna Compendium Volume 5*

The K6NA 80-Meter Wire Beam

Ever get crunched in a DX pileup on 80/75 meters by K6NA? Lots of folks have! K6NA reveals the secrets behind his two-element "killer" Yagi.

This article describes a practical design for a two-element, horizontal wire Yagi for the 75/80-meter band using just two support towers. Designed with DXing and contesting in mind, this radiator-and-reflector combination features moderate gain and good front-to-back ratio, combined with instant beam reversal and band-segment (mode) switching. It uses tuned feeders and a balanced-output antenna tuner at the operating position for matching at the transmitter. Remote relays at ground level handle reversal and parasitic-tuning requirements, taking advantage of the convenient properties of half-wave transmission lines.

I designed this antenna empirically, before PC-modeling programs were readily available. I've confirmed that it really works, through years of successful 80-meter operation. Later, I verified this with computer modeling. Figure 1 shows the general layout of my system.

Background

At my former location I had two towers, 70 and 100-feet high, fairly close together on a half-acre of property. There was an assortment of quads and Yagis for 10-40 meters,[1] but as is often the case with all-band DXers, the 80-meter antenna was an afterthought. Through the years I experimented with many types, looking for the "silver bullet" antenna for 80 that would finally make this challenging band a pleasure to operate.

Each season numerous magazine articles and endless discussions by experts extolled the virtues of this or that magic 80-meter DX antenna. I even tried some of them: a diamond quad loop, a delta loop (bottom-fed or corner-fed), a pair of parasitic deltas, phased quarter-wave slopers (tilted ground planes), a $\lambda/4$ vertical with lots of radials. I always came back to a basic truth: with the tower heights available, and faced with the reality of rough, rocky, lossy earth, my 95 foot high inverted-V dipole was usually as good as–or better than—any of the "trick" antennas I had spent hundreds of hours building. As a bonus, usually the dipole was quieter on receive.

Even Jim Lawson, W2PV, in an early *QST* article about broadbanding an 80-meter antenna, mentioned almost in passing that his high (110-foot) inverted-V was superior to his four-element phased vertical array, at least on transmit.[2] What I observed about 80-meter DXing in the 1970s was that most attempts using vertically polarized systems to achieve low-angle radiation were not satisfactory. This was due to excessive ground losses (both near-field return-current losses and far-field reflective losses); in addition, verticals were generally noisy on receive.

Neither vertically polarized antennas nor relatively low horizontal antennas were really getting thejob done. I resolved to construct my next station thinking about the 80-meter band from the start."High and horizontal" would be the goal.

Design Criteria

My new station would have two main towers, each 140 feet high. Because I had all-band contesting in mind, there would be numerous other antennas on the towers. I wanted to put a three-element 40-meter beam on top of one tower and a large 20-meter Yagi on the top of the other. Though it likely would be an excellent performer, a rotating beam of some type for 80 meters was ruled out because I did not want to dedicate the top of one tower to it. Also, there was the near-certainty of difficult maintenance problems with such a gigantic antenna. Instead, I settled on a design for a fixed-wire beam. These would be the main criteria for reliable, day-to-day operation:

- Oriented properly for best results in both DX and domestic contests
- Moderate gain, with a wide lobe for good azimuth coverage
- Instant beam reversal with a decent front to-back ratio
- Near-instant band-segment (phone or CW mode) switching, especially for casual, daily DXing
- Easy, low-loss matching anywhere in the band
- Horizontally polarized to minimize both ground-reflection losses and noise on receive
- High enough to produce reasonably low angle radiation
- Reliable and easy to maintain without disrupting other antennas on the towers.

Design Discussion

Some discussion of these interrelated design criteria will aid in understanding the trade-offs and choices I made while planning this antenna. For example, from San Diego the typical short path to Europe on 80 meters *is not* the expected true Great-Circle path of about 25°. Rather, the short path toward Europe is almost always a "bent" or skewed path, where signals pass to the south or southeast of the highly absorptive auroral oval, propagating by means of a scatter mode that uses ionized patches over the central Atlantic Ocean. Consequently, our pseudo short-path heading toward Europe is commonly 50° to 90° in azimuth. Occasionally, European signals on 80 meters arrive in California from the southeasterly direction. Rarely, around the time of the Equinox, they may even arrive by scatter path from straight south, as reported by some rotary beam users in California.



Figure 1—The antenna farm at K6NA, showing the 80-meter wire beam installed on the pair of 140-foot towers, using 35-foot long crossarms made of aluminum tubing and fiberglass. The rearward truss and upper truss wires make each crossarm rigid. For clarity, the tower guy wires are not shown.

I decided to orient the two support towers so that the reversible wire beam, slung between the towers on a pair of horizontal crossarms, would point at 60°/240°. This would provide good coverage across the USA and into Europe (both short and long path), Africa, the Caribbean and South Pacific areas, which together make up about 85% of my annual QSOs on 80 meters.

I could build a simple two-element parasitic design, using $\lambda/2$ elements on a reasonable boomlength of about 35 feet, or $\lambda/8$.[3] Figure 2B shows that such a design has a half-power azimuth beamwidth of about 74° in the azimuth plane. I was willing to accept the slightly lower gain and front-to-back ratio compared to a three-element design (which would be more difficult mechanically), or a two-wire phased array using double-extended Zepp elements. The Zepp would require the towers to be placed about 350 feet apart. Either of these antennas conceivably would provide more gain, but at the price of reduced azimuthal coverage. A reversible, all-driven array has the additional disadvantage that its phasing and matching networks become overly complicated to make it work properly at both ends of the band.

To achieve the twin requirements of easy mode-switching and beam reversal, I decided to construct a symmetrical, two-element Yagi beam. The elements are identical dipoles, self-resonant near 3.675 MHz. This frequency is about 3% to 4% lower than the phone operating area around 3.800 MHz, meaning that each element could be used as a reflector in the phone band with no additional loading. Each dipole is fed with $\lambda/2$ of open-wire line. These lines come together in a relay box at ground level. Power is applied to one or the other driven element, and a short is applied across the base of the remaining feeder to force the remaining element to act as a parasitic reflector.

To operate near 3.5 MHz, the reflector simply is retuned to about 3.4 MHz, using an inductor in place of the direct short in the relay box. Supplying RF to the relay box is accomplished using low-loss, open-wire feeders. A balanced-output tuner in the shack is simply touched up to move between phone and CW subbands, and to accommodate the change in SWR. There is no requirement for an exact match at the line input to the driven element because of the low-loss transmission lines.

With the crossarm supports mounted at 130 ft, the dipoles are about $\lambda/2$ high and thus produce fairly low-angle radiation. A horizontally polarized antenna is less responsive to man-made noise sources, which have a large vertical component. The height allows $\lambda/2$ lines to reach down to the switchbox near ground level. All switching relays are in this weatherproof box, so the system is reliable and easy to maintain. No inaccessible relays or matching networks are up at the elements, where failures might occur.

Construction

No doubt, the 80-meter wire beam can be built and integrated into many existing



Figure 2—Patterns for the K6NA 80-meter wire beam at an average height of 125 feet over flat ground. At A, elevation pattern and at B, azimuth pattern at 15° elevation angle. The K6NA Yagi is well suited for the low elevation angles that predominate from Southern California to DX locations.



Figure 3—Top view of the 80-meter wire beam mounted on the towers, with details of the crossarms and rearward truss system that prevents the tensioned antenna wires from bending the crossarms inward. The tower-guy placement geometry provides several advantages for antenna-farm management! See text.

multi-tower systems. I had the luxury of planning the tower and guy arrangement well in advance of building the antenna. This helped make erection and maintenance simpler. Such planning contributes to convenient erection of other antennas too!

Figure 3 shows the recommended two-tower layout that has served very well for this and other projects. Through symmetry of guy-anchor placement, any forces due to loading by wire antennas or temporary trams are balanced out. Note that each tower has an opposing, backward-facing guy exactly in line with its counterpart and parallel with the centerline of the towers. When the 36-foot crossarm is mounted about 10 feet below the top of the tower and the topmost guy bracket, the ends extend out beyond and above the sloping, upper guys. This arrangement keeps the dipoles in the clear, allowing them to be raised and lowered using ropes and pulleys with minimal guy-wire interference, without having to remove or move the crossarms.

This tower/guy layout also presents two parallel tower faces on which to mount the booms and to correctly orient the wire antenna. Non-parallel tower faces can work, but the mounting brackets would be more complex and some advantages of symmetry would be lost. For safety, significant sideloads should be distributed across *at least two* tower legs. In addition, guys passing through the central area between the towers would complicate the raising and lowering of the wire antennas, so this should be avoided if possible.

Another advantage of the layout in Figure 3 concerns the overall use and maintenance of other antennas in the system. Note that the 140-foot towers are 136 feet apart, and the guy radius (distance from tower to each of its guy anchors) is 105 feet. These facts, together with the generally uncluttered work area between the towers, make



Figure 4—Photo of one of the crossarms (booms) mounted on the tower. The truss system and 80-meter folded dipoles are visible. Note that the truss, dipoles and pull-down ropes provide a stable truss/guy system for each crossarm. The large Yagi at the top of the tower is a full-sized three-element 40-meter beam.



Figure 5—Photo showing mounting method for installing the 80-meter crossarm and associated horizontal back-truss pipe. The horizontal riser prevents the crossarm from collapsing when the side load (antenna tension) is applied. Note how a plate with U-bolts is used to secure the back-truss pipe to one of the tower legs, while the other end is secured with an L-shaped bracket and U-bolts to the mounting plate for the crossarm.

it convenient to run a temporary tram wire anchored at the base of one tower to the top (or anywhere along the length) of the other tower. The tram can be used to raise the 80-meter crossarms themselves, or to move other HF Yagis. If an upper-mast-mounted beam is to be erected, the 80-meter wires first can be lowered easily to the ground. If the tram has to reach only to the area of a side-mounted beam, the wire antenna may stay in place above it. I can detach the 80-meter feeders from the feed-through insulators at the switchbox, and pull them away from the vicinity of the tram wire, if necessary.

Crossarms and Trusses

I made each crossarm (boom) using aluminum and fiberglass. In order to eliminate the possibility of "boom resonance" that might interfere with nearby HF Yagis and to keep the 80-meter wire ends away from metal conductors, only the middle 14 feet of crossarm is made of 2-inch OD, 1/4-inch wall aluminum. This section is stiff and very strong.

The outer extensions are fiberglass tubing, each about 11 feet long, for a total crossarm length of 36 feet. Surplus vaulting poles were used but other types of fiberglass would also be suitable. The fiberglass should be wrapped with high-quality black tape (such as Scotch 33 or 88) to prevent decomposition due to ultraviolet radiation. At the end of each fiberglass pole, I mounted a six-inch sleeve of aluminum tubing, before drilling a clearance hole for the forged eyebolt used to secure the pulley used to hoist each dipole.

Each crossarm is clamped to the tower face using an aluminum plate and muffler clamps. See Figures 4 and Fig 5. Once in place, the crossarm is made rigid by means of a dual truss system. When the dipoles are erected and tension is applied, the crossarms cannot collapse. The top and back truss system and dipole pull-ropes together transfer all the balanced forces to the tower.

Layout of the truss system can be seen in Figures 1, 4 and 5. The horizontal riser behind the tower is the key to the truss system. This rigid support is a six-foot length of 1$^{1}/_{2}$-inch OD, 1/4-inch wall aluminum pipe, extending horizontally about five feet beyond the back leg of the tower. This "sideways riser" is anchored to the crossarm mounting plate with a right-angle bracket, and to the back tower leg by means of U clamps and a flat plate. The back-truss lines connect to eyebolts on the outer end of the riser using turnbuckles and shackles.

The various truss lines and dipole pull-ropes are coiled and individually taped to the crossarm prior to erection. After the crossarm has been raised and installed, the back-truss riser pipe is brought up and clamped into the tower from the back side. Then, the crossarm is first trimmed to horizontal by attaching the top-truss lines to the tower legs and adjusting the turnbuckles until the crossarm looks good, much like a Yagi boom truss is adjusted. Then the backtruss lines are untaped from the crossarm, one at a time, and connected to the far end of the horizontal back-truss pipe. This is an interesting maneuver, which should be accomplished only by an experienced climber/rigger! The turnbuckles are adjusted initially for moderate tension. Properly adjusted, the result is a crossarm that doesn't sag downward or fold inward when antenna tension is applied.

After the truss system has been rigged, the installer untapes one of the coiled-up dipole pull-ropes, which has been prerigged to extend along the arm to the outer crossarm pulley and back again to the vicinity of the tower. By attaching either a weight or tag line to the thimble, the dipole-end of the rope is released to hang vertically from the pulley. The rigger then pays out the coiled rope until a ground man can reach the thimble end to attach the dipole insulator. The pull-ropes ultimately are brought to the tower legs through pulleys and thence brought down to ground level. The angle of the pull-ropes completes what is essentially a four-point guy on each end of the crossarm (antenna tension, back-truss, up-truss, and angled pull-down rope). This configuration presents a stable structure when the dipoles are raised and tension applied.

I must emphasize that all subassemblies should first be fabricated and fitted to the tower at ground level. Make sure that all plates, clamps and hardware mate to the tower, referenced to diagonal braces, welds, or leg bolts. Premark the tower legs up at the target location ahead of time to preclude surprises on the tower!

Construction of the Dipoles

Two-wire folded dipoles were selected to help bring the feedpoint impedance up closer to the characteristic impedance of the feeders and to improve bandwidth. This helps minimize tuner adjustments when moving within a subband, but there is no need to go overboard trying to effect a perfect match at the load.

Each folded dipole is built with #14 stranded, non-stretch copper wire. The two parallel wires are held apart by seven horizontal spreaders located about every 20 feet along the wire length. These spreaders of black Delrin are 1/2-inch diameter rod, 18 inches long (See Figure 6). They are held in position by tie wires, as are the ribbed end insulators. I used an unbroken length (about 260 feet) of wire for each two-wire dipole, making the free ends come together at the center-feed insulator. The free ends of the wires and feeders are tied to the center insulator for strain-relief, and then the loose ends are soldered. This technique prevents breakage, because soldered connections (which are weaker due to wire heating) are not under strain, or flexing. After each dipole is assembled on flat ground, it should be stretched temporarily at low level between the towers in order to check the symmetry and mechanical behavior. When adjustments are complete, the feeder can be soldered to the antenna.


Twist Only
Through–hole in rod, no. 12 tie wire holds the 18" spreader firmly to center of 6" ribbed plastic feed insulator.
Solder Here
Horizontal 18" Delrin Spreader (1/2" Diam.) 7 Places
No. 16 feeder wire twisted to feed insulator for strain relief.
3/32" Black Dacron Bridle
Feeder Wire
Twist Only
Solder Here
Tie Wires
Antenna Wire
No. 14 Tie Wire
6" Ribbed Plastic Insulator
3" Delrin spacer (1/4" Diam.)
No. 18 Tie Wire
260' continuous length of antenna wire, passes through each end insulator (not shown) and terminates at feedpoint shown here.
No. 14 Stranded Antenna Wire
Feedline to Ground Level
To End Insulator (not shown)

Figure 6—Folded-dipole center feedpoint with stabilizing cradle. The cradle encourages stability in the large, two-wire dipoles, preventing twist. See text.

There is little point in making any sort of analyzer measurements at five feet off the ground because the results will be misleading. When the dipole is installed in the clear at a half-wavelength in height, it will perform as predicted. However, just to be sure, I grid-dipped one dipole at its final height through the half-wave line. I had first built the $\lambda/2$ transmission line and had checked for resonance near 3.650 MHz with a grid-dip meter. When the first dipole and its feeder are on frequency, the second dipole and feeder was cloned and the array was erected. The dipoles at K6NA are about 130 feet long.

Feed Line Construction

Each feed line was constructed using old techniques but modern materials. Minimum weight is very important. The lines were made about 130 feet long, using #16, prestretched solid copper wire. Spacers are 1/4-inch Delrin rods, three inches long and spaced every four feet along the feeder. Spacers were notched and drilled, and held in position using #18 copper tie wires through the holes. The result is a very lightweight, low-loss feeder with a characteristic impedance of about 575 Ω.[4] To minimize sag in the dipole, avoid using heavy ceramic spacers.

A good technique for constructing the long, open-wire feeder is to stretch two wires tightly between the towers about four feet above the ground. Space the wires three inches apart in a plane parallel to the earth. Precut all the tie wires and make a simple, four-foot long, interval-measuring rod from a piece of wood or tubing. With all the spacers, tie wires, rod and long-nose pliers in a tool bag, the installer begins at one end, moving easily along the line, installing spacers at the correct intervals. The feeder wires sit in the notched ends, while the tie wires pass through the holes and are twisted in place over the feeder wires. When complete, the suspended line is in a good position for checking resonance with a grid-dip meter, assuming the line is insulated from the towers. The final length of each feeder described here is about 128 feet and each weighs less than three pounds.

Some additional comments about feedpoint construction will be helpful to those planning assembly of such a large, wide-spaced folded dipole and associated feeder. Initially, the dipole was built with upper and lower wires, as depicted in most antenna books. An 18-inch Delrin rod connected the lower feed insulator to the upper wire in order to distribute the weight of the feeder onto both wires and to maintain correct spacing. This worked, but with unforeseen side effects. When the dipole was raised under tension, the result was a half-twist in the parallel wires about halfway back toward the end insulator. This twist was not due to "live" or "kinky" wire! The twist was due to a catenary sort of effect.

The solution to the twist problem is to avoid the upper wire/lower wire configuration, and allow all the spreaders (including the center spreader) to lay over into the horizontal plane. To encourage this, a simple cradle was constructed to distribute the weight of the feeder at the center of the two antenna wires. This forces the wires (and all the other balanced spacers) to form a plane parallel to the earth. Fig 6 shows the centering cradle below the Delrin rod. The feeder passes over the cradle insulator (tie wires take the load) and continues up to the feedpoint. Small Dacron lines tie the cradle insulator to the other end of the rod, keeping the load centered. These large folded dipoles have been well behaved, even in high winds.

Remote Switching

A plywood "doghouse" was constructed under the antenna center, and mounted about four feet above ground for convenience. Fig 7 is a schematic of the switching network housed in the box. Two DPDT relays control the direction of the beam pattern. The main feeder connects through K1 and K2 to one dipole, while the other dipole becomes a phone-band reflector due to the short across K3. In the shack, switch S1 activates K1/K2 for reversal. S2 is a phone/CW selector switch that allows K3 to retune the reflector element to about 3.4 MHz by means of an inductor. Relays are large, ceramic-base open-frame types.

The center-loading inductor for a CW reflector is best chosen experimentally. A coil is connected across K3, S2 is set for CW, and the tuner in the shack is adjusted for a match low in the CW band. From the tuner, a coax cable is routed temporarily back to the switchbox. At the box, the temporary coax feeds a receiver, which is used to monitor signals arriving off the back of the antenna around 3.515 MHz. A variable tap is moved along the coil until the best front-to-back ratio is obtained. After a period of testing, the tap can be soldered. With the dipoles self-resonant around 3.650 MHz, a CW reflector coil of about 17 µH was required. This consisted of a 2-inch OD coil, 2$^{3}/_{4}$-inches long, on which were wound about 25 turns of #16 wire.

Operation and Maintenance

The 80-meter wire beam performs as expected. Typical F/B is 11 to 14 dB on both phone and CW modes. For high-band operators accustomed to quiet bands with low atmospherics, this level of F/B may not seem like much. However, on a consistently noisy band like 80 meters, this kind of rejection on receive is very important. The high wire beam makes it possible to work long-path Europeans (southwest heading, before sunrise in San Diego) on a regular basis in the winter months, due to effective rejection of storm noise over North America. The antenna performance is roughly comparable to that of a nearby, two-element rotary beam (195 feet high) at N6ND—we hear and work many of the same weak stations during DX sessions. In domestic contests, reports from the East Coast are excellent on both modes.

The wire beam has been very reliable for over 10 years. The first version of the antenna used #16 solid-copper wire for the elements, and there was a broken wire or two after perhaps six years. The antenna was rebuilt in 1992 with #14 stranded wire and has been perfect since then. The original dipole pull-ropes of black, 1/4-inch polypropylene lasted about seven years before they were replaced. Black Dacron, readily available from several *QST* advertisers, would be an excellent replacement for the pull-ropes, but it is more expensive than polypropylene. Do not use any color except black, and do not use polyethylene lines for permanent antenna supports.

Antenna Comparisons and Modeling

Recently, I wanted to investigate this 80-meter wire beam using computer modeling. By comparing the predicted performance of this antenna with that of several other common types of 80-meter DX antennas, the relative merits of each can be described briefly. Example antennas were modeled over average earth, with a dielectric constant of 13 and a ground conductivity of 5 mS/m. Gain figures listed are referenced to an isotropic antenna in free space.

Fig 8A shows the elevation pattern of the wire beam 125 feet high over real earth, compared to single horizontal dipoles at heights of 125 and at 70 feet. Peak radiation for the Yagi occurs at 28°. The azimuth pattern shown in Fig 8B is at 15° elevation, because low elevation angles are required for success on most DX paths from Southern California. For example, the W6 short path to Europe supports signals between 8° and 18° elevation, essentially 100% of the time.[5] The Yagi has about 5 dB of gain over the high dipole.

Note that a single high dipole is an excellent DX performer, and likely will beat any sort of beam antenna on a 70 to 80-foot tower. In addition, a high dipole has better rejection of local (high-angle) signals, so it will be a superior DX receiving antenna. Inspection of Figure 8A indicates that the high wire beam probably will outperform a 70-foot high dipole by nearly 10 dB at low elevation angles.

Some people might say: "With 140-foot towers, you should be using quad loops!" Not so fast. Figure 9A shows that with the top of a diamond-like, full-wave loop at 135 feet, the $\lambda/2$ dipole at 125 feet is superior by at least 1 dB at all angles lower than 40°, in spite of the small stacking gain expected from the loop. The expected gain from the bigger loop cannot be realized fully because the upper and lower wires are at drastically different heights (in terms of fractional wavelengths) relative to each other and the earth. This prevents proper phase addition. Further, the average height of the loop is lower, which results in a higher peak angle of radiation. The dipole has better high-angle rejection, too, and should be better on receive. If both antennas were up a couple of wavelengths on 80 meters, the quad loop would beat the


Wooden weatherproof enclosure, 4 ft above ground and directly below dipoles.
L1
S2
To Relay Power Supply
K3
K3A
K3B
Open Wire Feeders to Dipole 1
K2A
K2B
S1B
K2
Open Wire Feeders to Dipole 2
To Relay Power Supply
K1
S1A
K1A
K1B
To Relay Power Supply
S1,S2 – at operator's console
L1 – Inductor value to be selected in field tuning (see text)
Open wire feeders to antenna tuner, any length.
Ceramic feed–through insulators (bulkhead style) bring open–wire lines out on three sides of box.

Figure 7—Schematic of the feed system for the reflector-type, 80-meter wire Yagi. With two identical dipoles tuned at 3.650 MHz, only three relays and one inductor are needed to shift the antenna instantly from the phone to the CW subband, and to switch the beam direction. The relays are open-frame DPDT relays with ceramic insulation. S1 is a DPST switch used to reverse the beam direction by activating K1 and K2. S2 activates K3 to tune the parasitic element as a CW reflector.



Figure 8—Comparison of patterns for K6NA two-element Yagi at 125 feet with two dipoles, at 125 and at 70 feet heights. At A, elevation pattern comparisons and at B, azimuth pattern comparisons.



Figure 9—Comparison of elevation responses for full-wave diamond-shaped loop, K6NA two-element Yagi and a single horizontal dipole. The Yagi and dipole are at a height of 125 feet and the loop's apex is at 135 feet.

dipole...but who has a 550-foot tower?

How about a pair of half-wave slopers (that is, tilted vertical dipoles) tied from the tops of the 140-foot towers one λ/2 apart, and fed in phase for broadside gain? See Figure 10A. All the antenna books show the phased-sloper array to be a 4 dB gain, low-angle monster. The author had this exact antenna up for a few months in 1980. It performed fairly well, but was very responsive to powerline noise. For comparison, a single horizontal dipole was hung between the towers a few feet above the top ends of the slopers. With this single dipole, my local noise level dropped by 8 to 10 dB, and stations in New Zealand reported a consistent transmit advantage over the sloper array. This was a real eye-opener. As seen in Fig 10A, the high wire beam *buries* the phased slopers by 7 dB at the peak angle of 28°, and by 5 dB at 15° elevation!

The famous W8JK is a bi-directional, all-driven wire beam made from two dipoles fed 180° out of phase. At 125 feet in the air, this antenna has excellent rejection of high-angle signals, and is only slightly down from the peak gain of the Yagi configuration. See Figure 11A. It requires no relay box. For DXing, it is inferior to the Yagi because there is no way to reject signals (noise) off the back. Years ago, the author fed the two new folded dipoles as a W8JK for a few months prior to building the switchbox. It performed much like the patterns show, but once the switchbox was available to configure the array as a Yagi with good F/B ratio, the W8JK configuration was abandoned. However, a W8JK antenna 100-feet high in Kansas City would be an outstanding Sweepstakes antenna.

Figure 12 compares the horizontal wire beam to a similar antenna with inverted-V elements with a 90° included angle. The V-style gain is down a bit and the pattern is not as clean. But if you have a single tall tower and install this antenna (only one crossarm is required), you will be in the 95th percentile of effective 80-meter DXing antennas.

In Figure 13 the K6NA Yagi is compared to a quarter-wave vertical mounted over average ground. Since there are less losses due to ground reflection characteristics, horizontal polarization allows the Yagi to outperform substantially the verti-



Figure 10—Patterns for a pair of λ/2 sloping dipoles fed in phase, compared with K6NA two-element Yagi and a single horizontal dipole. The slopers both start at a height of 140 feet and are mounted over average ground, with a dielectric constant of 13 and a conductivity of 5 mS/m. The high horizontal Yagi is a decidedly superior performer. Surprisingly enough, even the simple horizontal dipole is a better performer than the phased-sloper system. This is mainly due to far-field losses experienced by the mainly vertically polarized sloper system.



Figure 11—Comparison of elevation responses for a horizontal W8JK array and the K6NA two-element Yagi, both at height of 125 feet. As might be expected, the unidirectional Yagi has gain over the bidirectional W8JK design.

cal at all angles of interest, even down to 10°. In most locations, the vertical will be noisy on receive. *An extensive local ground screen (or elevated radials) will not make any significant change in the pattern relationship depicted here.* Only by installing the vertical in, say, a saltwater marsh extending perhaps 100 λ would its low-angle performance be improved substantially.[6]

The "Four-Square" has become popular in recent years. Figure 13 also shows the beautiful pattern of this array, along with that of the two-element beam and a single vertical. In a quiet location this vertical system with a switching matrix makes a terrific receiving antenna, allowing full azimuth coverage in four directions. However, the horizontal wire Yagi still has superior gain at all elevation angles of interest—note the 4 dB advantage at 15°—and the Yagi likely will be quieter on receive in all but the most remote locations. The remarks in the paragraph above about attempts to improve the lowangle performance of the λ/4 vertical also apply to the Four-Square array.

Conclusions

Someone once said: "All antennas work... some more so." The sometimes-large differences seen during model comparisons can be misleading, as we know from our day-to-day operating. Propagation, pileup dynamics, and operator skills (one skill is picking a quiet location ...) are important factors that determine 80-meter DXing success. Virtually every antenna discussed in the comparison section of this report is a "good" antenna. The author's first 180 countries on 80 meters were worked with an inverted-V dipole at 70 feet.

If *tall* supports are available, a horizontally polarized, gain antenna will certainly provide a statistical increase in performance over the others. In lieu of really tall



Figure 12—Comparison of the horizontal K6NA wire beam to a similar antenna using inverted-V dipole elements with a 90° included angle. The inverted-V configuration loses gain and directivity compared to the fully horizontal dipole Yagi, but the loss is only about 1 dB. The inverted-V style may be quite practical for those with a single, high tower.



Figure 13—Comparison of K6NA Yagi to both a single ground-mounted λ/4 vertical on average ground (with a dielectric constant of 13 and a conductivity of 5 mS/m), and a "Four Square" phased vertical array. Each vertical is assumed to have 120 radials, an "optimal" ground system. Again, far-field ground losses are detrimental to verticals over poor ground.

towers, a well-installed vertical system can be an excellent antenna, especially in a quiet receiving location. As the computer models show, height above ground is the most significant variable when designing a lowband station using horizontally polarized antennas. [Hills help too!–*Ed.*]

It is hoped that some of the construction techniques for the crossarms, wire antennas, and feed lines described in this report will stimulate others to build even better horizontal arrays. You will enjoy special satisfaction using homemade open-wire lines, and a 40-year old Johnson Matchbox tuner makes a nice addition to your modern shack.

The author would like to thank H. Shepherd, W6US, for his valuable advice regarding wire antennas and open-wire feeder construction; R. Craig, N6ND, for mechanical suggestions; E. Andress, W6KUT, for manuscript review; and N6ND and J. McCook, W6YA, for modeling assistance.

Notes and References

[1] Wayne Overbeck, N6NB, "Quads vs. Yagis Revisited," *Ham Radio*, May 1979, p 12.

[2] James L. Lawson, W2PV, "160/80/75-Meter Broad-Band Inverted-V Antenna," *QST*, Nov 1970, p 17.

[3] James L. Lawson, W2PV, *Yagi Antenna Design*, W. Myers, K1GQ, editor (Newington: ARRL, 1986), p 2-2.

[4] Doug DeMaw, W1FB, editor, *ARRL Electronics Data Book* (Newington: ARRL, 1976), p 82.

[5] Frank Witt, AI1H, "Optimizing the 80-Meter Dipole," *The ARRL Antenna Compendium, Vol 4* (Newington: ARRL, 1995), p 39.

[6] Charles J. Michaels, W7XC, "Some Reflections on Vertical Antennas," *QST*, Jul 1987, p 18.

By John J. Uhl, KV5E From *QST*, August 1986

Construct a Wire Log-Periodic Dipole Array for 80 or 40 Meters

These log-periodic dipole arrays are simple and easy to build. They are also lightweight, strong and inexpensive. The design parameters can be used to construct antennas for the other ham bands.

My desire to work DX and obtain DXCC certification caused me to build my first antenna in the early 1960s. I needed a directional antenna that had reasonable gain, was inexpensive, lightweight and rotatable, and could be assembled with stock items found in large hardware stores. My choice of antennas then was the cubical quad. I had much success DXing with different quads, and I quickly earned DXCC certification. Quads are excellent antennas, but the ones I built lacked the mechanical stability needed in southern Louisiana. I soon learned this when they were ruined by hurricanes.

After my fourth quad was destroyed some years later, I purchased a triband Yagi and forgot about building antennas ... until the day I had a QSO with Ansyl Eckols, YV5DLT. What started as a normal QSO that day in the late 1970s led to a full-fledged experiment with the design, construction, erection and use of log-periodic dipole arrays made of wire. At that time, YV5DLT was using a triband log-periodic dipole array (LPDA) for 20, 15 and 10 meters. What immediately piqued my interest was that his beam was made of wire, and that his signal had outstanding quality and strength.

During the QSO, I asked Ansyl for construction details of his antenna. His response was generous. He mailed me diagrams, schematics and photographs of the LPDA that he had named Telerana. (He subsequently published his design in *QST*.[1]) After reading and studying all of his data, I was convinced that his design had the mechanical stability to withstand hurricanes, and I began plans in my mind to build a copy of Telerana.

I began a search of the literature, reading all of the LPDA articles that I could find.[2-8] By the time I gathered and read several references, three years had passed. Sunspot activity had diminished and band conditions weren't as good. Openings on 10 and 15 meters were few and of short duration, and future conditions would be worse. I did not duplicate the Telerana for these reasons, but decided instead to apply the LPDA theory to the design of wire LPDAs for use on the 160, 80 and 40-meter bands. By making some preliminary calculations I found that an LPDA for 160 meters would be too large to fit my lot size, but LPDAs for 80 and 40 would fit. However, it would not be possible for me to rotate these LPDAs.

LPDAs for 80 and 40 Meters

I placed the same criteria on the LPDAs that I had placed on the quads–that they have reasonable gain, be inexpensive and lightweight, and that they could be assembled with stock items found in large hardware stores. This article is written to detail the design, construction, erection and use of wire LPDAs for the lower frequency bands. Figure 1 shows one method of installation. You can use the information presented here as a guide and point of reference for building similar LPDAs.



Figure 1—Typical 4-element log-periodic dipole array erected on a tower.

If space is available, the antennas can be "rotated" or repositioned in azimuth after they are completed. A 75-ft tower and a clear turning radius of 120 ft around the base of the tower are needed. The task is simplified if only three anchor points are used, instead of the five shown in Figure 1. Omit the two anchor points on the forward element, and extend the two nylon strings used for element stays all the way to the forward stay line.

For the design procedure, refer to *The ARRL Antenna Book*.[9] By using the formulas given there and other data in the text, all of the dimensions can be obtained and the LPDAs will take shape on paper. The design results are summarized in the concluding section of this article. The next step is to fabricate the fittings; see Figure 2 for details. Cut the wire elements and feed lines to the proper sizes and mark them for identification. After the wires are cut and placed aside, it will be difficult to remember which is which unless they are marked. When you have finished fabricating the connectors and cutting all of the wires, the antenna can be assembled. Use your ingenuity when building one of these antennas; it isn't necessary to duplicate my LPDAs exactly.

The elements are made of standard no. 14 stranded copper wire. The two parallel feed lines are made of no. 12 solid copper-coated steel wire, such as Copperweld. This will not stretch when placed under tension. The front and rear connectors are cut from 1/2-in-thick Lexan sheeting, and the feed-line spacers from 1/4-in Plexiglas sheeting.

Study the plans carefully and be familiar with the way the wire elements are connected to the two feed lines, through the front, rear and spacer connectors. Details are sketched in Figure 4. Connections made this way prevent the wire from breaking. All of the rope, string and connectors must be made of materials that can withstand the effects of tension and weathering. Use nylon rope and strings, the type that yachtsmen use. Figure 1 shows the front stay rope coming down to ground level at a point 120 ft from the base of a 75-ft tower. It may not be possible to do this in all cases. In my installation I put a pulley 40 ft up in a tree and ran the front stay rope through the pulley and down to ground level at the base of the tree. The front stay rope will have to be tightened with a block and tackle at ground level.

Putting an LPDA together is not difficult if it is assembled in an orderly manner. It is easier to connect the elements to the feeder lines when the feed-line assembly is stretched between two points. Use the tower and a block and tackle. Attaching the rear connector to the tower and assembling the LPDA at the base of the tower makes raising the antenna into place a much simpler task. Tie the rear connector securely to the base of the tower and attach the two feeder lines to it. Then thread the two feed-line spacers onto the feed line. The spacers will be loose at this time, but will be positioned properly when the elements are connected. Now connect the front connector to the feed lines. A word of caution: Measure accurately and carefully! Double-check all measurements before you make permanent connections.

Connect the elements to the feeder lines through their respective plastic connectors, beginning with element 1, then element 2, and so on. Keep all of the element wires securely coiled. If they unravel, you will have a tangled mess of kinked wire. Check that the element-to-feeder connections have been made properly. (See Figure 4.) Once you have completed all of the element connections, attach the 4:1 balun to the underside of the front connector. Connect the feeder lines and the coaxial cable to the balun.

You will need a separate piece of rope and a pulley to raise the completed LPDA into position. First secure the eight element ends with nylon string, referring to Figures 1 and 3. The string must be long enough to reach the tie-down points. Connect the front stay rope to the front connector, and the completed LPDA is now ready to be raised into position. While raising the antenna, uncoil the element wires to prevent their getting away and balling up into a mess. Use care! Raise the rear connector to the proper height and attach it securely to the tower, then pull the front stay rope tight and secure it. Move the elements so that they form a 60-degree angle with the feed lines, in the direction of the front, and space them properly relative to one another. By adjusting the end positions of the elements as you walk back and forth, you will be able to align all the elements properly. Now it is time to hook your rig to the system and make some QSOs.

Performance

The reports I received using the LPDAs were compared with an inverted-V dipole. All of the antennas are fixed; the LPDAs radiate to the northeast and the dipole to the northeast and southwest. The apex of the


Forward
Hole Size to Match Rope Used
2"
Depends on Size of Balun
Hole Size to Match Wire Size Used
1/4"
5/8"
1/4"
(A)
to Rear Anchor
Hole Size to Match Rope Used
1/2"
Hole Size to Match Wire Size Used
1/2"
1/4"
5/8"
1/4"
(B)
2"
Hole Size to Match Wire Size Used
3/4"
3/8"
1/4"
5/8"
1/4"
(C)

Figure 2—Pieces to be fabricated for the LPDA. At A, the forward connector, made from 1/2-inch Lexan. At B, the rear connector, also made from 1/2-inch Lexan. At C is the pattern for the feed-line spacers, made from 1/4-inch Plexiglas. Two of these spacers are required.


to Tower
Elements Made From #14 Copper Stranded Wire
1/2ℓ1
1/2ℓ2
1/2ℓ3
1/2ℓ4
d12
Overall Feed-Line Length
d23
d34
Nylon Strings
Feed Point
90?
Feed Line Made From #12 Copperweld Wire
Mount Balun on Underside of Connector for Balance
Nylon Rope 1/4" or Larger
to Front Stay

Figure 3—Typical layout for the LPDA. Use a 4:1 balun at the point indicated. See Table 1 for dimensions.

Table 1
Calculated Array Dimensions

Element Length	*Half Length*	*Element Spacing*
80-Meter Array		
ℓ1 = 149.09 ft	1/2 ℓ1 = 74.55 ft	d_{12} = 17.89 ft
ℓ2= 125.98 ft	1/2 ℓ2 = 62.99 ft	d_{23} = 15.12 ft
ℓ3 = 106.45 ft	1/2 ℓ3 = 53.23 ft	d_{34} = 12.77 ft
ℓ4 = 89.95 ft	1/2 ℓ4 = 44.98 ft	
40-Meter Array		
ℓl = 71.30 ft	1/2 ℓl = 35.65 ft	d_{12} = 8.56 ft
ℓ2 = 60.25 ft	1/2 ℓ2 = 30.13 ft	d_{23} = 7.23 ft
ℓ3 = 50.91 ft	1/2 ℓ3 = 25.46 ft	d_{34} = 6.11 ft
ℓ4 = 43.02 ft	1/2 ℓ4 = 21.51 ft	

dipole is at 70 feet, and the 40-and 80-meter LPDAs are at 60 and 50 feet, respectively. The gain of the LPDAs is in the range of 7 to 9 dB over the dipole. This was apparent from some of the reports received: "The quality of the audio on the log is superior to the inverted V." "The signal on the log is much stronger and steadier than the V, about 10 dB." "The LPDA does not fade, but fading conditions are present on the inverted V." During pileups, I was able to break in with a few tries on the LPDAs, yet it was impossible to break in the same pileups using the dipole.

During the CQ WW DX Contest I was able to break into some *big* pileups after a few calls with the LPDAs. Switching to the dipole, I found it impossible to break in after many, many calls. Then, after I switched back to the LPDA, it was easy to break into the same pileup and make the QSO.

Think of the possibilities that these wire LPDA systems offer hams worldwide. They are easy to design and to construct, real advantages in countries where commercially built antennas and parts are not available at reasonable cost. The wire needed can be obtained in all parts of the world, and cost of construction is low! If damaged, the LPDAs can be repaired easily with pliers and solder. For those who travel on DXpeditions where space and weight are large considerations, LPDAs are lightweight but sturdy, and they perform well. They'll even withstand a hurricane!

Calculations for Log-Periodic Dipole Arrays

Design constants and the results of design procedures follow. (Terms are defined at the end of this section.)

τ = 0.845
σ = 0.06
σ_{opt} = 0.152
cot α = 1.548
α = 32.86°
Gain = 7.5 dBi (5.35 dBd). [By sloping the elements forward, the gain may be increased 3 to 5 dB over this figure. *–Ed.*]
σ' = 0.065
B_{ar} = 1.39; see note 10.
R_0 = 70

Fed with 50-ohm coaxial cable and a 4:1 balun

For the 80-meter antenna,
fn = 4.1
f1 = 3.3
B = 1.24
B_S = 1.72
λ_{max} = 298.18 ft
L = 48.42 ft
N = 4.23 (rounded to 4)
ℓ1 = 149.09 ft
R_0 = 70 ohms
h = 62.4
a = 2.667×10^{-3}
h/a = 23400
Z_{av} = 937.26 ohms
Z_0 = 80.72 ohms
d_{12} = 17.89 ft
See Table 1 for calculated array dimensions.

For the 40-meter antenna,
fn = 7.5
fl = 6.9
B = 1.09
B_s = 1.51
λ_{max} = 142.61 ft
L = 18.57 ft
N = 3.44 (rounded to 4)
ℓ1 = 71.30 ft
R_0 = 70 ohms
h = 32.727
a = 2.667×10^{-3}
h/a = 12273
Z_{av} = 859.82 ohms
Z_0 = 81.76 ohms
d_{12} = 8.56 ft
See Table 1 for calculated array dimensions.

Definitions of Terms
B = operating bandwidth = fn/f1
fn = highest frequency, MHz
fl = lowest frequency, MHz
τ = design constant
σ = relative spacing constant


NOTES:
① Mount Balun on Bottom of front Connector for Balance
② Feed with 50 Ω Coaxial Cable and 4:1 Balun
③ Pay Close Attencion to Detail of Element Connection to Feed Lines
to Tower
Rear Connector 1/2" Thick Lexan
Feeders
Elements
Spacers
Front Connector and Balun Mount 1/2" Thick Lexan
to Front Stay

Figure 4—Details of electrical and mechanical connections of the elements to the feed line. Knots in the nylon stay lines are not shown.

σ_{opt} = value of σ for optimum gain
σ' = mean spacing factor
α = apex half-angle
B_{ar} = bandwidth of the active group. See note 10.
B_s = structure (array) bandwidth
L = boom length for N elements
N = number of elements
$\ell 1$ = longest element = 492/f1
λ_{max} = longest free-space wavelength = 984/f1
Z_0 = characteristic impedance of feeder
R_0 = mean radiation resistance level of required input impedance of active region
Z_{av} = average characteristic impedance of a dipole

$$= 120\left(\ln\frac{h}{a}-2.25\right)$$

h = element half length
a = radius of element
ℓ = length of elements
d = spacing between elements

Notes

[1] A. Eckols, "The Telerana—A Broadband 13- to 30-MHz Directional Antenna," *QST*, Jul 1981, pp 24-27.

[2] C. T. Milner, "Log Periodic Antennas," *QST*, Nov 1959, p 11.

[3] D. E. Isbell, "Log-Periodic Dipole Arrays," *IRE Transactions on Antennas and Propagation*, Vol AP-8, No. 3, May 1960, pp 260-267.

[4] P. D. Rhodes, "The Log-Periodic Dipole Array," *QST*, Nov 1973, pp. 19-22.

[5] *The GIANT Book of Amateur Radio Antennas* (Blue Ridge Summit, PA: Tab Books, 1979), pp 55-85.

[6] C. A. Balanis, *Antenna Theory, Analysis and Design* (New York: Harper and Row, 1982), pp 427-439.

[7] G. L. Hall, ed., *The ARRL Antenna Book* (Newington, CT: The American Radio Relay League, Inc, 1982), pp 6-24 to 6-26, 9-12 to 9-14.

[8] D. A. Mack, "A Second-Generation Spiderweb Antenna," *The ARRL Antenna Compendium Vol 1* (Newington, CT: The American Radio Relay League, Inc, 1985), pp 55-59.

[9] See note 7.

[10] See Ref 6, p 435. B_{ar} is found from the following equation:
$B_{ar} = 1.1 + 7.7(1-\tau)^2 \cot\alpha$

From *QST,* October 1986 (Technical Correspondence)

Input Impedance of LPDA Antennas

The log-periodic dipole array (LPDA) has intriguing possibilities, some of which have been explored by Uhl.[1] Unfortunately, some misleading information in *The ARRL Antenna Book* has kept the subject from being more accessible to the amateur.[2] The design procedure called out by *The Antenna Book* and by Rhodes refers to graphs of R_0, the mean antenna input resistance, versus the log-periodic design parameters τ and α.[3] It would appear that R_0 is dependent solely on these parameters; such is not the case. As shown by Eq 2 and 4, R_0 is dependent on τ, σ, Z_{av} and Z_0. This relationship is demonstrated by Carrel.[4] The graphs in question are from the seminal experimental study of the LPDA by Isbell, and are used to demonstrate the effect on R_0 of changing τ and σ; Z_{av} and Z_0 were constant.[5] Since τ and σ are usually chosen to provide the desired antenna geometry and directivity (gain), R_0 should be controlled by either Z_{av} or Z_0. Z_{av} is usually constrained by mechanical considerations, which leaves Z_0 as the easiest parameter to adjust for desired R_0.

The erroneous procedure determines R_0 from a graph. The correct procedure is to calculate the necessary Z_0 based on the *desired* R_0. For most practical LPDA antennas, this results in a Z_0 of less than 100 ohms, if an R_0 of 50 ohms is chosen. Impedances in this range are difficult to achieve with open-wire line, the kind normally used in an LPDA, because thick conductors and/or close spacing are needed. For this reason, it is usual to design for a higher R_0 and use an impedance-transforming balun between 50-ohm coaxial cable and the antenna feed point. This is the method chosen by Uhl. Assuming a 4:1 balun, an antenna-input impedance of 200 ohms is required. Z_0 is then calculated (using Eq 9 and 11 from page 6-25 of *The ARRL Antenna Book*) as follows:

$$Z_0 = \frac{{R_0}^2}{8\sigma' Z_{av}} + R_0 \sqrt{\left(\frac{R_0}{8\sigma' Z_{av}}\right)^2 + 1} \quad \text{(Eq 1)}$$

where

$$\sigma' = \frac{\sigma}{\sqrt{\tau}} \quad \text{(Eq 2)}$$

$$Z_0 = \frac{200^2}{8(0.065)\,(937.26)} +$$

$$200\sqrt{\left(\frac{200}{8(0.065)\,(937.26)}\right)^2 + 1}$$

$$= 298.26 \text{ ohms}$$

The actual impedance of the feed line used by Uhl can be computed from the formula on p 3-16 of *The ARRL Antenna Book*:

$$Z_0 = 276 \log\left(\frac{2S}{d}\right) \quad \text{(Eq 3)}$$

where S is the spacing between conductors, 0.75 inch, and d is the conductor diameter, 0.081 inch for no. 12 AWG wire. Therefore:

$$Z_0 = 276 \log\left(\frac{2(0.75)}{0.081}\right) = 349.86 \text{ ohms}$$

Although this appears to be considerably in error, recasting Eq 1 to solve for R_0 based on the true value of Z_0 gives:

$$R_0 = \frac{Z_0}{\sqrt{1 + \frac{Z_0}{4\sigma' Z_{av}}}} = \frac{349.86}{\sqrt{1 + \frac{349.86}{4(0.065)(937.26)}}}$$

$$= 224.17 \text{ ohms} \quad \text{(Eq 4)}$$

which, when transformed by the 4:1 balun, results in a load impedance of 56.04 ohms; this is close to the design impedance. From this, we can infer that the actual Z_0 used is not critical, although it isn't negligible, either.

The design Z_0 values listed in the Uhl article are incorrect, since they were produced using the erroneous procedure from *The ARRL Antenna Book*. The values should be 298.26 and 308.56 ohms for the 80- and 40-meter antennas, respectively. In addition, R_0 could be made closer to the design value of 200 ohms by using a different feeder spacing to change the feeder impedance. From Eq 2:

$$S = \left(\frac{d}{2}\right)10^{(Z_0/276)} = \left(\frac{0.081}{2}\right)10^{(298.26/276)}$$

$$= 0.488 \text{ inch}$$

Rounding this value to 0.5 inch results in a Z_0 of 301.26 ohms and an R_0 of 201.46 ohms for 80 meters and 196.62 ohms for 40 meters. These translate to load impedance of 50.37 and 49.15 ohms, respectively.—*Jon Bloom, KE3Z*

---

[1] J.J. Uhl, "Construct a Wire Log-Periodic Dipole Array for 80 or 40 Meters," *QST*, Aug 1986, p 21.

[2] G.L. Hall, ed., *The ARRL Antenna Book* (Newington: ARRL, 1982), pp 6-24 to 6-26.

[3] P.D. Rhodes, "The Log-Periodic Dipole Array," *QST*, Nov 1973, pp 16-22.

[4] R.L. Carrel, "The Design of Log-Periodic Dipole Antennas," *1961 IRE International Convention Record, Part 1, Antennas and Propagation*, pp 61-75; also PhD thesis, University of Illinois, Urbana, 1961.

[5] D. E. Isbell, "Log-Periodic Dipole Arrays," *IRE Transactions on Antennas and Propagation*, Vol AP-8, No. 3, May 1960, pp 260-267.

From *QST*, August 1980 (Technical Correspondence)

The WA1AKR 40- and 75-Meter Slopers

Several amateurs have suggested that I submit a description of my sloper antenna system for publication in "Hints and Kinks." Other amateurs may be interested in this adaptation of the 8JK beam. Construction information is shown for both the 75- and 40-meter bands.

As shown in the accompanying diagram, the array has two half-wave sloping elements joined by a 1/8-wave, 300-ohm phasing line. Transposing the phasing line should bring the element currents into phase. I find the antenna is broadbanded. There appears to be no need for a Transmatch.

If one desires to suspend an additional sloper from the tower for a directional change, installation of remote switching at the top of the tower will permit the use of a single transmission line. Otherwise, separate transmission lines will be required.

Ends of the antenna are suspended by ropes with the tops placed roughly 1 foot away from the tower. An angle of 45 degrees between the antenna and ground should be maintained. Do not use an angle greater than 50 degrees. Resonance with the dimensions shown should occur near 3.8 MHz for the 75-meter sloper and 7.150 for the 40-meter antenna.

How well do my antennas work? I have contacted stations "across the pond" while competing with the big boys who sport three and four-element beams. I have also experienced little difficulty in working VKs and ZLs. – *Carl Bissonnette, WA1AKR*



When Carl Bissonnette, WA1AKR, chases DX he uses a sloper like the one illustrated. Carl's arrangement is fashioned after the famous 8JK beam. The feed system resembles that of the ZL Special.

From *QST*, June 1983 (Hints & Kinks)

Inexpensive 30-Meter Beam Antenna

In about two months of operating on the new 30-meter band I have worked all 50 states and over 50 countries. My antenna is simple but effective. It is a rotatable inverted V beam. Figure 1 shows the construction details. The antenna boom is suspended from a tree branch about 50 feet in the air. The antenna can be rotated 360° simply by moving the two ground stakes. All of the materials to build this antenna cost me less than $25.

Eq. 1 gives the driven element length, Eq. 2 gives the director length, and Eq. 3 gives the element spacing that I used.

$$\text{D.E. length} = 476/f_{\text{MHz}} \quad \text{(Eq. 1)}$$

$$\text{Dir. length} = 450/f_{\text{MHz}} \quad \text{(Eq. 2)}$$

$$\text{Spacing} = 120/f_{\text{MHz}} \quad \text{(Eq. 3)}$$

The feed-point impedance is around 30 ohms. I used a matching transformer made by connecting two 1/4-λ sections of RG-59/U coaxial cable in parallel. One end of the transformer connects to the antenna, and the other end goes to 50-ohm cable to the shack. Figure 1B shows how this is wired. Perhaps the easiest method to join the two pieces of 75-ohm cable is to use coaxial T connectors. You should use a balun at the antenna feed point to prevent rf from flowing on the outside of the shield braid.

I also built an antenna of this type for 40 meters, and it works great. I guess the key word is rotatable! —*Jon Ferrara, N9DWR, Chattanooga, Tennessee*


Nylon Rope
12'
1/2" PVC Pipe Boom
Insulator
1:1 Balun
22'
23.5'
1/2" PVC Pipe
90° or Greater
Nylon Rope
12'
Coaxial Cable to Shack
(A)
Coaxial "T" Connectors
1/4 λ RG-59/U
75-Ω Coaxial Cable
1/4-λ Stub 2 Pieces RG-59/U
50-Ω
(B)

Figure 1—Construction details for a 30-meter inverted V beam are given at A. A coaxial-cable impedance-matching transformer is shown at B.

By Roy W. Lewallen, W7EL

From *QST*, June 1984

Try the "FD Special" Antenna

Looking for an antenna that's simple, inexpensive, lightweight and easy to install? Here's one that fits the description.

While the Field Day "juices" were flowing last year, my Field Day partners and I decided to become more competitive without compromising our general philosophy: Use all homemade gear, pack it in to the site, and don't let operating interfere with watching the scenery. Since most of our gear already ran the accepted QRP power limit of 10-W dc input and had been designed to provide high output efficiency, the antenna seemed like the reasonable point of attack (our high quality superheterodyne receivers have not been the limiting item). The constraints dictated that an antenna be lightweight, portable and easy to put up. It should also have substantial gain.

Because of our West Coast location, the front-to-back ratio was not a concern. But having a reasonably wide lobe toward the East was. We desired a low SWR because of the relatively high loss of our RG-58/U and/or RG-174/U feed line. We were interested only in the CW portion of the band, but this antenna works well over all of the band. It seemed that 20 meters would be our main "money-maker," so we designed the antenna for that band. It can be scaled for other bands, too.

The Research

Although a number of antenna types might have done the job, I settled quickly on a horizontal, close-spaced, driven array. Experience has shown that driven arrays are generally more tolerant of imperfect construction and erection than are parasitic arrays. Experience and much measurement have convinced me that horizontal arrays outperform vertical ones in the high-frequency bands, except perhaps from an exceptional location. In addition, we didn't want the nuisance of establishing a decent ground system — which most vertical arrays require.

The theoretical gain and front-to-back ratio of 2-element arrays with 1/8-wavelength spacing between the elements are shown in Figures 1 and 2. Note the lower curve of Figure 1. It shows the effect of losses on the gain (losses don't affect the front-to-back ratio, and change only the scaling of the pattern). Figure 3 shows the patterns of arrays with 135, 160 and 180-degree relative spacing. All are drawn to the same scale. The 1/8-wavelength spaced, 135-degree-fed array is frequently called the "ZL Special."[1] The close-spaced, 180-degree-fed array is known as an "8JK."[2] From 135 to 160 degrees, phasing was chosen because of the combination of relatively high insensitivity to loss, reasonable gain and wide forward lobes. Note that the gain stays about the same in this range, ensuring good performance if the phasing isn't exactly as predicted. Actually, it's much easier to generate and maintain precise 180-degree phasing than the angles I've chosen — particularly over a wide frequency range.

There's one major flaw (usually fatal) in a simple analysis like the one presented here: It assumes that equal-magnitude currents are flowing in the elements. This is not easy to realize, for even in arrays with elements spaced 1/2 wavelength or greater, mutual coupling has a profound effect on element impedances. This changes them dramatically and unequally, as a rule. This



Figure 1—Curves that show gain versus phase angle for two-element arrays with 1/8-wavelength spacing.



Figure 2—Theoretical F/B ratio for a two-element array with 1/8-wavelength spacing.



Figure 3—Dipole array patterns for 135, 160 and 180-degree relative phasing at λ/8 spacing. Curves A, B and C, respectively, represent these conditions. Add 5 dB for dBd. These curves are based on the array being fed with equal currents.



Figure 4—Element current ratio (A) and phase angle (B) as a function of frequency.

impedance change is a function of not only "mutual impedance," but also the relative magnitudes and phases of the currents flowing in the elements. In an array as closely spaced as these, coupling is so intimate that it could be argued that the term "driven array" is a misnomer. For example, the feed-point impedances of the elements in a 1/8-wavelength-spaced array, assuming equal currents can be made to flow, are

Phase Angle Between Currents (Degrees)	*Loading Element (Ohms)*	*Lagging Element (Ohms)*
135	28 – j46	28 + j46
160	13 – j22	13 + j22
180	9 + j0	9 + j0

This shows quite a change from the 74 + j0 ohms value that each element exhibits when it is not coupled to another element. The fact that the resistive parts of the two-element impedances are equal, and the reactances are equal in magnitude, is a peculiarity of the particular element spacing chosen. For other spacings they will be unequal, and the reactances can be different in magnitude, as well as in sign.

This mutual coupling isn't undesirable; in fact, it's essential for obtaining gain in the presence of rather severe pattern cancellation that is common in these closely spaced arrays. The lower impedances cause more element current to flow for a given power input, thereby increasing the fields from the elements. In these arrays, the increased field strength is sufficient to compensate for the fact that the fields from the elements don't add in phase in any direction. They partially or completely cancel instead. But, the lower feed-point impedances make them more sensitive to losses, and the low resistance with relatively high reactance makes them tricky to feed properly.

Why do these different and reactive feed impedances make feeding the arrays so difficult? The first problem is that, with few exceptions, the magnitude of current out of a line not terminated in its characteristic impedance won't be equal to the current into the line. In classic "If you can't fix it, feature it!" fashion, this impedance-transforming property is put to good use in the form of the 1/4-wavelength Q section.[3] The second (and almost always overlooked) difficulty is that, again with only a few exceptions, the phase delay of current in an imperfectly terminated transmission line doesn't equal the electrical length of the line. This effect isn't minor: The phasing of a casually designed array can easily be off by tens of degrees. In one design I investigated, an 80-degree line produced 139 degrees of phase shift.

The Solution

There are a number of approaches toward correct feeding of an array. My choice was to investigate some simple feed systems to see if any would yield results that came close to the desired characteristics. I wrote a computer program that would solve, iteratively, for element-current magnitude and phase angle, plus feed-point impedances for this one type of array, given the array specifics. Several configurations looked promising, and one of the simplest proved adequate. This was an array of two folded dipoles that were self-resonant, spaced 1/8 wavelength apart and connected by a taut piece of 300-ohm TV ribbon with one half twist. The feed impedance was close to 50 ohms resistive. There was some inductive reactance that could be corrected by adding two small-value capacitors at the feed point. The element current ratio was 1.13:1, with element phasing that was 154 degrees. This was not the 124 degrees one might expect from the 56 electrical degrees of line — assuming a velocity factor of 0.8 — minus the 180 degrees caused by the half twist.

It was this array that we used for Field Day, with very good results (see section on performance). However, when the array was reconstructed at the home QTH, a dramatic rise in SWR was noticed when operating the antenna at other than the low end of the band. Computer analysis showed that, above the design frequency, the phase angle increased. This caused a substantial lowering of the element feedpoint impedance, plus narrowing of the forward lobe. The analysis also showed the antenna to be well-behaved *below* the design frequency. Consequently, a similar array was designed (figuratively speaking) for 14.5 MHz. It gave good results over the 20-meter band.



Figure 5—Calculated antenna patterns for the high and low ends of the 20-meter band. Add 5 dB for dBd.

Element phasing varies from 135 degrees at 14.0 MHz to 148 degrees at 14.35 MHz, with current ratios from 1.04 to 1.13:1 (see Figure 4). The gain can be calculated as fairly constant from 4.5 to 4.6 dBd across the band. Again, the array feed-point impedance can be corrected easily to provide a low SWR. The calculated patterns for the antenna at the top and bottom ends of the 20-meter band are shown in Figure 5. These take into account the changes in element phasing, spacing, current magnitude and element self-impedance with frequency.

Construction

The antenna is made from quality 300-ohm TV line to the dimensions given in Figure 6. Sketches of the insulators are provided in Figure 7. They are made from scrap pieces of epoxy-glass PC-board material. This results in ruggedness and minimum weight. The spreaders are readily available 10-foot lengths of "1 inch" ($1^5/_{16}$ in OD)[4] schedule 40 PVC pipe. The capacitors are used only to provide a good match to 50-ohm feed line: They don't otherwise affect the performance of the array. Small 500-V mica or monolithic ceramic units may be used for power levels up to a few hundred watts, since they are at a relatively low-voltage part of the system. Open-ended stubs could probably be substituted for the capacitors, if desired. I recommend that a balun transformer be used with this antenna. Attempts to measure the impedance of one element of this array resulted in a unique experience — the first substantial evidence of the need to use a balun transformer. The antenna-bridge readings varied greatly as the measuring equipment was moved, or as I placed my hand around the feed line. This ceased when I added a balun transformer. The phenomenon is explained by Maxwell in a recent paper.[5] Nearly any style of balun transformer will prevent the unwanted flow of current on the coaxial cable outer conductor. I use a choke type of balun transformer. It consists of 10 turns of small-diameter coaxial cable


32' 1"
Direction of Maximum Radiation
300-Ω TV Twin Lead
8' 5-3/4"
330 pF
330 pF
1:1 Balun
50-Ω Coaxial Feed Line
(A)
Similar to Fig 7 (A) without BNC Connector and 330 pF
Insulators (Fig 7A)
(B)
Insulators (Fig 7B)
Insulators (Fig 7B)
Spreader PVC Pipe
Feed Line
Spreader PVC Pipe

Figure 6—Electrical dimensions for the W7EL array (A). Illustration B shows how the antenna is assembled on spreaders of PVC pipe.


Phasing Line to Other Element
Scrap PC-Board Material
To Balun Transformer Mounted on the Other Side of the Board
Twin-Lead Element
Twin-Lead Element
Slots in PC Board Insulator (6)
BNC Connector to Feed Line from Balun (see Fig 6)
(A)
Nylon Cable Tie
PC Board
Twine to Spreader
300-Ω Line
Slots
(B)

Figure 7—Details for the antenna insulators used in the two-element 20-meter array. The drawing at A shows how the TV ribbon is affixed to the feed-point/phasing-line insulating block. The example at B provides details for the end insulators.



Figure 8—SWR curve obtained at the end of a 45-foot length of RG-58/U coaxial cable.

wound on a ferrite toroid core. The OD is approximately 1¼ inches, and it is mounted at the feedpoint insulator by means of small nylon cable ties.

If you use the array for portable operation, as we did, the 10-foot spreaders are out of the question, at least in their original form. We cut ours in half for "packing in," then used PVC cement to glue them together at the FD site. PVC pipe couplings were used to join the sections. The glue container was enclosed in polyethylene sandwich bags, just in case a leak developed. At the end of our FD exercise, we used the saw blade of K0ED's Swiss army knife to cut the PVC pipes again for easy transport. The spreaders were glued together again for use at the home station. The antenna is held horizontal easily by attaching a piece of twine to the nondirectly driven element insulator. This counteracts the weight of the feed line that is connected to the other element.

Performance

The "FD Special" has been in use at W7EL for some time. Array gain has been compared to that of an inverted V at the same height. The calculated performance values appear correct within the measurement capability. The front-to-back ratio has not been measured. The SWR at the end of 45 feet of RG-58/U feed line is shown in Figure 8. The SWR is important only when a lossy line feeds the array, or when it is driven by an intolerant transmitter (with built-in SWR shut down), which is now the norm.

Perhaps the most revealing performance indication was provided by a person who encountered us several times on 20 meters during Field Day. He was operating for another, very competitive local club. After the exercise he remarked, "The only reason I believe you guys were running an honest 10 W is that I know Wes Hayward (W7ZOI) was there." Indeed, we used 10 W or less input while operating—and 0 W while watching the mountain scenery!

Notes

[1] My apologies to the first person who described or named this antenna. I don't know its history. (See L.A. Moxon, "Two-Element Driven Arrays," *QST*, July 1952, p 28.)

[2] Named after W8JK, Dr. John Kraus, "Antenna Arrays with Closely-Spaced Elements," *Proc. IRE*, Feb. 1940.

[3] G. Hall, ed., *The ARRL Antenna Book* (Newington: ARRL, 1982).

[4] mm = in x 25.4; m = ft x 0.0348.

[5] W. Maxwell, "Some Aspects of the Balun Problem," *QST*, March 1983.

By Riki Kline, 4X4NJ

From *QST*, February 1985

Build a 4X Array for 160 Meters

Low-angle radiation and electrical rotation of directivity are the features of this vertically polarized top-band antenna. If you are interested in 160-meter DX, this system could be your secret weapon.

Is your lament a common one — no room for an effective DX antenna on 160 meters? This complaint is voiced frequently by amateurs who live in urban areas, or who are programmed toward horizontal wire antennas. But, a number of successful top-band operators have adopted the philosophy, "If you can't go out, go up!" It is no secret that a physically short vertical antenna is generally more effective than a horizontal antenna that is close to the ground electrically, at least for DX work.

My 4X array is electrically rotatable. It is compact and is effective as a low-angle radiator. Let's examine how my antenna evolved from some basic designs. I will also cover the practical details of construction and system performance.

The Tilted Ground-Plane Look

The tilted ground plane is almost identical to the usual vertical. The physical format of this antenna resembles a four-conductor ground plane. The major difference is that the radiating elements tilt up toward the supporting structure. The 4X array contains four sloping ground planes. Each of the slope wires is 100 feet long.[1] They are supported at the high end by an 80-foot tower. A four-element, 20-meter Yagi antenna is atop the tower.

Each of the sloping wires is fed separately near ground by means of a tapped-coil matching device (Figure 1) that is returned to radial wires and ground rods. In effect, each radiator is a ground-plane vertical antenna that is slightly less than 0.25 wavelength. The matching inductor provides resonance and effects an impedance match to the coaxial feed line.

I believe that the metal tower and 20-meter antenna may possibly be functioning as a reflector because the Yagi antenna and tower combined with ground wires are resonant slightly below 1.8 MHz.

Two Tilted Ground-Plane Verticals in Phase

I had excellent results with one sloping vertical. Next, I installed a second system in the opposite direction. Switching between the two antennas (north-south sloping radiators) showed considerable front-to-back ratio (a relative reading of 15-20 dB). Subsequently, I connected the two antennas in phase. This gave a bidirectional pattern, east and west. Although I did not gather extensive data on the performance, I observed a 6-dB signal improvement with stations about 700 miles to the



Figure 1—Basic tilted ground-plane vertical. L has 25 turns of heavy conductor (see text); length is $5^1/_2$ inches, and diameter is 3 inches. Radiator is tapped $15^1/_2$ turns above ground.



Figure 2—Two tilted ground-plane antennas that can be fed separately or in phase. The feed method is shown in Figure 1, with the method of Figure 7 used for feeding the antennas in phase.



Figure 3—The 4X array as viewed from above the tower.

east. Some of you may want to explore the possibilities further. Figure 2 shows the details of the two-element phased system.

The 4X Configuration

Two more tilted ground-plane verticals were added, thereby providing east-west sloping radiators (Figure 3). A switching and phasing arrangement was added to my 4X array. It allows me to feed any of the slope wires separately, adjacent pairs in phase, or all four wires in phase. When using adjacent pairs in phase, maximum radiation is along a line that bisects the angle between the two antennas (NE, SE, SW or NW directions). When I feed all four wires in phase I note that the radiation is essentially omnidirectional. All of the unfed radiators are resonated to serve as reflectors. This concept is described in *The ARRL Antenna Book.*^{2} My switching network is shown in Figure 4.

Phasing Networks

Most phasing methods call for long lengths of non-50-ohm coaxial cable.^{3} I found this economically prohibitive. This negative factor inspired the approach I am using.

Each of my radiators is fed by means of 115 feet of RG-213 coaxial cable (formerly RG-8A/U 50-ohm line). The coil at the base of each wire is adjusted for the same resonance and SWR as the remaining three coils. The verticals to be fed in phase have their transmission lines connected in parallel through a suitable network for changing the reflected impedance back to 50 ohms. My networks are shown in Figures 7 and 8.

Tapped-Coil Matching

By using inductance and no intentional parallel capacitance for my matching coils, I am able to obtain greater effective antenna bandwidth because of reduced Q. Stray capacitance and antenna capacitance to the tower and ground are present, however. All electrical connections are soldered. A simple rain cover is used over each coil to protect it from moisture and dirt. The absence of switches, variable capacitors and rotary inductors enables construction of a highly reliable matching system without the need for weatherproof boxes.

This system is relatively easy to tune to obtain nearly identical performance from each antenna branch. This becomes a necessity when using "brute-force" parallel feed in the phased-pair and omnidirectional modes. Otherwise, the power distribution and phasing would be disturbed. This would distort the radiation pattern. Large-diameter, heavy-conductor, air-wound coils are best for this job. Two of my coils are made from silver-plated 1/4-inch-diameter copper tubing. The two remaining coils are made from large, flat conductor material of the kind found in some rotary inductors.

I used a dip meter to adjust the coils for resonance (coaxial cables disconnected). My coaxial cables were tapped initially one


J1
To North Ground Plane
L1
NW
N
NE
W
S1A
E
SE
SW
Omni
S
J2
To East Ground Plane
L2
NW
N
NE
W
S1B
E
SE
SW
Omni
S
L3
J3
To South Ground Plane
NW
N
NE
W
S1C
E
SE
SW
Omni
S
L4
J4
To West Ground Plane
NW
N
NE
W
S1D
E
SE
SW
S
Omni
J5
To Transmitter and Receiver
NW
N
NE
W
S1E
E
SE
SW
Omni
S
C
B1
A1
A2
B2

Figure 4—Switching system for the 4X array. L1 through L4, inclusive, are described in the text. A1, A2 and C are connected to the matching circuit shown in Figure 7. B1, B2 and C are connected to the matching circuit shown in Figure 8. S1 is a heavy-duty ceramic rotary switch, five poles, nine positions. J1-J5, inclusive, are coaxial connectors of the builder's choice.

Direction	SWR vs. Frequency				
	1800 kHz	1825 kHz	1850 kHz	1875 kHz	1900 kHz
N	1.4	1.0	1.2	1.8	2.6
NE	1.5	1.1	1.0	1.1	1.2
E	2.2	1.1	1.1	1.4	1.9
SE	1.2	1.0	1.0	1.0	1.1
S	1.4	1.0	1.1	1.4	2.3
SW	1.5	1.1	1.0	1.0	1.1
W	1.4	1.1	1.0	1.2	1.6
NW	1.2	1.0	1.0	1.0	1.2
Omni	1.4	1.1	1.0	1.0	1.0

Figure 5—Chart that shows SWR versus frequency in kilohertz.



Tabulated Data

Direction	Relative Strength
Forward	0 dB
±45°	−3 dB
±90°	−8 dB
±135°	−14 dB
±180°	−19 dB
Omni	−7 dB

Figure 6—Directivity pattern of the array. The pattern is a composite average of measurements made while receiving 10 different stations. There is no apparent difference between the two directive modes—single radiator or phased pair.

third of the way up from the ground ends of the coils. Final tap placement is made while feeding power to the antenna and observing an SWR meter. Alligator clips make this an easy matter to accomplish. When the SWR bottoms out at the same frequency for all four radiators, remove the alligator clips and solder the coil taps in place. Some interaction between the four antennas will occur, so make certain that all of the taps are where they belong before soldering them.

Reflector Tuning

The radiators not being fed are used as reflectors. This is done by switching small inductors in parallel with the ends of the coaxial feed lines. My inductors contain three or four turns of no. 16 wire wound around the center part of a 3/8-inch-diameter ferrite rod from a built-in AM broadcast receiver antenna. The coils are adjusted to give a resonance that is four percent lower than the resonant frequency of the radiators.

Ground Conditions

The efficiency and performance of the antenna depends on the quality of the ground system. Note 3 provides a good reference for ground systems, and a bibliography. Each of my radiators is worked against a counterpoise that contains two or three 1/4-wavelength wires, bent to fit in the boundaries of my property. In addition, I use a 10-foot rod in the ground. Water pipes



Figure 7—Phased-pair matching network. C is a 1000-pF variable, rated at 1000 V or greater. L is 30 airwound turns of heavy conductor (see text), 7 inches long and 3½ inches in diameter.



Figure 8—Network for omnidirectional use. C and L are the same as for Figure 7.

and all other available underground metal objects are tied to my ground system. You should try to extend your radials in the direction of the preferred radiation.

Insulators

The top ends of the radiators contain high RF voltage. I use 15-inch-long Plexiglas strips as insulators, after having problems with 8-inch-long commercial plastic insulators. Moisture and air pollutants caused these problems. The present insulators need to be cleaned periodically. High-quality glass insulators of the type used aboard ships should be excellent and, with luck, should not require periodic cleaning.

Receiving

The antenna directivity enhances reception by rejecting signals from unwanted directions. I was encouraged when I compared my 4X array to an 800-foot unterminated Beverage antenna that is bidirectional NW and SE. In the past, the Beverage wire showed an 8-10 dB S/N advantage over the tilted north vertical alone. During long-haul QSOs to North America, the 4X array, used in the phased-pair mode, comes within 3 dB of the S/N ratio provided by the Beverage.

In Conclusion

Many European stations tell me my signals are as strong as local ones. On occasion they remark that I have the loudest signal on the band.

It's a pleasure to have a directional array on top band. I simply turn a knob to rotate the pattern — much faster than a motor can rotate a typical beam antenna! The 4X array is compact and can be supported by the existing HF-antenna tower. I hope that some of you will try this antenna, and I look forward to hearing from you about your results.

Notes

[1] m = ft × 0.3048; mm = in × 25.4; km = mi × 1.609.

[2] G. Hall, ed., *The ARRL Antenna Book* (Newington: ARRL, 1984), p. 8-12.

[3] J. Devoldere, *80-Meter DXing* (Greenville, NH: Communications Technology, 1978).

By Rod Newkirk, W9BRD **From *QST*, June 1990**

The 'BRD Zapper: A Quick, Cheap and Easy "ZL Special" Antenna

Here's a multipurpose directional wire antenna that has its origins in Kraus, Windom and Newkirk *(who?–Ed.).*

Working Europe from Chicago with low power on 21 MHz, using an indoor, bent-ends W8JK bidirectional wire beam (Figure 1)[1], is fairly straightforward fun. Voltage feed via a $\lambda/4$ stub, gamma-matched to coax, is hard to beat for spartan simplicity. No worry about balancing element currents, no nit-picking with element lengths. Just make the whole system symmetrical and dip it to your favorite frequency by adjusting the stub-shorting point.[2] The 8JK has a similar pattern and good gain all the way from the fundamental to the second harmonic, so it's really a multiband antenna. You can roll the whole thing up in three minutes when it's not in use.

One problem: The bidirectional characteristics of the 8JK cause my ears to be flattened regularly by undesired signals from the direction opposite Europe. Unless you're in the geographical center of a three-way QSO, the unused lobe of this antenna can be a nuisance. Question: Is it feasible to convert easy 180° bidirectionality to tricky 135° *uni*directionality without resorting to clumsy center-feeding, multi-wire-dipole elements, balanced-gammas, etc?[3]

Yes—because there's a *uni*directional ZL Special lurking in our little 8JK. The principal difference between the W8JK and the ZL Special lies in the phasing: In the 8JK, the elements are fed 180° out of phase; in the ZL Special, they're driven 135° out of phase. Therefore, instead of feeding the antenna near the stub's shorting point, we'll need to feed it $\lambda/16$ from the stub's shorted end. That's where the feed path to one element is $\lambda/8$ (45°) longer or shorter than the other, which, after the stub's 180° phase reversal, produces the 135° phase shift that were looking for between the elements.

You can find the proper feed point on the stub by "sniffing" signals of known origin along *one side* of the stub with the insulated center conductor of some coax hooked to a receiver. (Start looking for this point by measuring $\lambda/16$ up from the bottom of the stub.) It's refreshing to hear Europeans rolling in while most of the murderous rearward signals now barely budge the S meter! Directivity is reversed at the opposite stub point (Figure 2).

So he's in there all right, that ZL Special, but coaxing the wily rascal out for an honest day's work is a challenge. The ZL



Figure 1—W9BRD's W8JK wire beam for 21 MHz, made to fit the dimensions of the townhouse bedroom that it occupies. Its dimensions aren't critical, although the element lengths should be close to $\lambda/2$ (total, each), the stub should be $\lambda/4$ or odd multiples, and the element spacing should be close to $\lambda/8$. At the bottom of the stub, connect both stub wires and the coax braid together, after resonating the system as outlined in Note 2. The 12-inch tap distance and 100-pF variable capacitor constitute a gamma match that brings the stub impedance to 50 Ω.



Figure 2—The antenna of Figure 1 configured for unidirectional operation with 135° element phasing. Resonate the system as described in Note 2 and connect the coupler via a very short wire to one leg of the stub about λ/16 above the stub-shorting point. The coaxial choke is needed to eliminate feed-line radiation, which can ruin the rearward null that this system provides.



Figure 3—Matching-network and coaxial-choke details for the 'BRD Zapper. L consists of 10 turns of no. 16 wire, 1½ in. diameter, air core, space wound. For 100 W or less, broadcast-type variable capacitors are suitable. Adjust the inductor-tap point for lowest SWR. The coaxial choke is made of 30 turns of RG-58 wound on a ferrite rod.

Special has a very sharp null in one direction when the element phasing is right, but unbalancing the stub could cost us that null. Fortunately, when the system is resonant, the 135° tap point has a moderately high resistive impedance, making for easy matching of the antenna to 50-Ω coax via a T network (Figure 3).

Pattern distortion through incidental radiation and pickup must be minimized. Excessive leakage would put us right back at the mercy of those loud signals from the other direction. Therefore, the coupler must be built in the most compact form possible, mounted right at the stub, and isolated to keep the feed line from distorting the pattern. Such isolation is done at W9BRD via a home-brew coaxial choke made of 30 turns of the antenna's RG-58 feed line wound on a ferrite rod just before the matching network.

Because feeder radiation could upset the stub balance—and thus spoil the antenna's rearward null—the single-wire run from the matching network to the antenna had better be no more than an inch or two. Here, I'm borrowing on the single-wire-feed theme by Windom. Any circuitry above the choke will be hot with RF, so a bulky meters-bells-and-whistles matching unit will not do. It's best to use a compact, barebones, dedicated network. Run the stub all the way down from the flat top if possible. Incidentally, the tap point on the stub corresponding to the best rearward null is higher on the stub for element spacings wider than λ/8. System Q is also lower with wider spacings, but gain is maximum at λ/8.

As for the stub itself, TV twin lead is okay indoors, but close-spaced, end-fire elements mean high voltages and currents. If the stub is to be longer than a quarter wavelength (odd multiples only) or outside in the weather, low-loss, open-wire line is a must. You can run the stub of an outdoor version directly into the shack for handy directivity reversal.

Though we've been talking horizontal, this setup should be equally interesting as a vertical. By the way, when the elements are placed horizontally, one above the other, 135° phasing accentuates radiation and reception at high angles. Neat for local traffic nets, Sweepstakes and Field Day!

Notes

[1] Dr John D. Kraus, W8JK, first described this antenna in *QST* in "Directional Antennas with Closely Spaced Elements," *QST*, Jan 1938, pp 21-23, 37. Kraus also discussed this antenna in three articles in *Radio* magazine in 1937 and 1939, and in *Proceedings of the IRE*, Feb 1940.

[2] The easiest way to do this is with a dip meter. Jab a straight pin into each leg of the stub near the bottom, short the pins together and couple the dip meter Into the system by bringing the dip motor close to the shorted pins. Locate resonance using the dip meter and measure the dip-meter frequency on your receiver. Move the pins up or down the stub and repeat the process until the antenna is resonant at or near your frequency of Interest. When you've done this, cut the stub, strip and solder a short in the wires where the pins were located at resonance.

[3] Of course, this antenna can be center fed in either Its bidirectional or unidirectional modes. Such flat tops are described in J. Hall, Ed., *The ARRL Antenna Book*, 15th ed, (Newington: ARRL, 1988), Chapter 8, and J. Devoldere, *LowBand DXing* (Newington: ARRL, 1987), pp 2-101 through 2-102.

Combination Driven Arrays

Broadside, end-fire and collinear elements can readily be combined to increase gain and directivity, and this is in fact usually done when more than two elements are used in an array. Combinations of this type give more gain, in a given amount of space, than plain arrays of the types just described. The combinations that can be worked out are almost endless, but in this section are described only a few of the simpler types.

The accurate calculation of the power gain of a multi-element array requires a knowledge of the mutual impedances between all elements, as discussed in earlier sections. For approximate purposes it is sufficient to assume that each set (collinear, broadside, end-fire) will have the gains as given earlier, and then simply add up the gains for the combination. This neglects the effects of cross-coupling between sets of elements. However, the array configurations are such that the mutual impedances from cross-coupling should be relatively small, particularly when the spacings are 1/4 λ or more, so the estimated gain should be reasonably close to the actual gain.

FOUR-ELEMENT END-FIRE AND COLLINEAR ARRAY

The array shown in Figure 1 combines collinear in-phase elements with parallel out-of-phase elements to give both broadside and end-fire directivity. It is popularly known as a "two-section W8JK" or "two-section flat-top beam." The approximate gain calculated as described above is 6.2 dB with 1/8-λ spacing and 5.7 dB with 1/4-λ spacing. Directive patterns are given in Figures 2 and 3.



Figure 1—A four-element array combining collinear broadside elements and parallel end-fire elements, popularly known as the W8JK array.

The impedance between elements at the point where the phasing line is connected is of the order of several thousand ohms. The SWR with an unmatched line consequently is quite high, and this system should be constructed with open-wire line (500 or 600 Ω) if the line is to be resonant. With 1/4-λ element spacing the SWR on a 600-Ω line is estimated to be in the vicinity of 3 or 4 to 1.

To use a matched line, a closed stub 3/16 λ long can be connected at the transmission-line junction shown in Figure 1, and the transmission line itself can then be tapped on this matching section at the point resulting in the lowest line SWR. This point can be determined by trial.

This type of antenna can be operated on two bands having a frequency ratio of 2 to 1, if a resonant feed line is used. For example, if designed for 28 MHz with 1/4-λ spacing between elements it can be operated on 14 MHz as a simple end-fire array having 1/8-λ spacing.



Figure 3—Vertical pattern for the four-element antenna of Figure 1 when mounted horizontally. Solid curve, height $^1/_2$ λ; broken curve, height 1 λ above a perfect conductor. Figure 2 gives the horizontal pattern.



Figure 2—E-plane pattern for the antenna shown in Figure 1. The elements are parallel to the 90°-270° line in this diagram. Less than a 1° change in half-power beamwidth results when the spacing is changed from $^1/_8$ to $^1/_4$ λ.

FOUR-ELEMENT BROADSIDE ARRAY

The four-element array shown in Figure 4 is commonly known as the "lazy H." It consists of a set of two collinear elements and a set of two parallel elements, all operated in phase to give broadside directivity. The gain and directivity will depend on the spacing, as in the case of a simple parallel-element broadside array. The spacing may be chosen between the limits shown on the drawing, but spacings below 3/8 λ are not worthwhile because the gain is small. Estimated gains are as follows

3/8-λ spacing—4.4 dB
1/2-λ spacing—5.9 dB
5/8-λ spacing—6.7 dB
3/4-λ spacing—6.6 dB

Half-wave spacing is generally used. Directive patterns for this spacing are given in Figures 5 and 6.

With 1/2-λ spacing between parallel elements, the impedance at the junction of the phasing line and transmission line is resistive and is in the vicinity of 100 Ω. With larger or smaller spacing the impedance at this junction will be reactive as well as resistive. Matching stubs are recommended in cases where a nonresonant line is to be used. They may be calculated and adjusted as described in Chapter 26.

The system shown in Figure 3 may be used on two bands having a 2-to-1 frequency relationship. It should be designed for the higher of the two frequencies, using 3/4-λ spacing between parallel elements. It will then operate on the lower frequency as a simple broadside array with 3/8-λ spacing.

An alternative method of feeding is shown in the small diagram in Figure 3. In this case the elements and the phasing line must be adjusted exactly to an electrical half wavelength. The impedance at the feed point will be resistive and of the order of 2 kΩ.



Figure 4—Four-element broadside array ("lazy H") using collinear and parallel elements.



Figure 6—Vertical pattern of the four-element broadside antenna of Figure 3, when mounted with the elements horizontal and the lower set 1/2 λ above a perfect conductor. "Stacked" arrays of this type give best results when the lowest elements are at least 1/2 λ high. The gain is reduced and the wave angle raised if the lowest elements are close to ground.



Figure 5—Free-space directive diagrams of the four-element antenna shown in Figure 4. At A is the E-plane pattern, the horizontal directive pattern at low wave angles when the antenna is mounted with the elements horizontal. The axis of the elements lies along the 90°-270° line. At B is the free-space H-plane pattern, viewed as if one set of elements is above the other from the ends of the elements.

CHAPTER SEVEN

VERTICALLY POLARIZED

7-1 **More on "Half Slopers" and Half-Sloper Variation for 160 Meters**
From December 1979 *QST* (Technical Correspondence)

7-3 **A Two-Band Half-Sloper Antenna**
From June 1980 *QST*

7-7 **The KI6O 160-Meter Linear-Loaded Sloper**
From April 1986 *QST*

7-8 **The Super Sloper**
From December 1995 *QST*

7-12 **The Inverted L Revisited**
From January 1983 *QST*

7-14 **160-Meter Antennas**
From July 1991 *QST* (Technical Correspondence)

7-16 **A Truly Broadband Antenna for 80/75 Meters**
From April 1986 *QST*

7-19 **Improved Broadband Antenna Efficiency**
From August 1987 *QST* (Technical Correspondence)

7-20 **Simple, Effective, Elevated Ground-Plane Antennas**
From June 1994 *QST*

From *QST*, December 1979 (Technical Correspondence)

More on "Half Slopers"

The July 1979 *QST* article on quarter-wave slopers has prompted me to write you on the subject. I have had considerable experience using them on 160 and 80, and I have tried them on 40.

The first one I know who used this type antenna was W3AU. His success with the system on 160 caused him to recommend it to W7RM and me. The original configuration used more than one sloping element fed in parallel against the tower. It resembled a top-loaded vertical with a simulated ground system. All my results have supported the view that this is an omnidirectional, vertically polarized radiating system, even when only one sloping element is used.

All the antennas of this type I have tried have been at my father's station, W6UA, and have been on a single tower. The tower is 82 feet (25 m) high, approximately $1\frac{1}{2}$ feet (0.45 m) in uniform triangular cross section, and has a single set of guys at the 70-foot (21.3-m) level. The guys are broken with insulators at about 20-foot intervals, and the top section of each guy is electrically connected to the tower. The base has whatever insulation the concrete provides and there are 10-, 15- and 20-meter Yagis on top of the tower. (This is an AB105 tower, the same as is used by W3AU and W7RM.)

The first antenna of the type in question was tried on 80 meters. It was attached at the 60-ft level, so that top-loading effects of the guys, as well as the rotaries, were probably effective. The attached wire came off at 30° to vertical and was trimmed for minimum VSWR. The resultant length was within 2 feet of the formula length, and the antenna then had a VSWR less than 1.5 from 3.5 to 4.0 MHz. It worked well on transmit but was extremely noisy on receive. The original wire sloped east, so I put up an identical system, attached to the same tower level, sloping west. Electrical characteristics were nearly identical, and no directivity difference between the two could be detected either on transmit or receive.

This is logical considering how little of the antenna current in the sloping wire has any horizontal component, other antenna systems used on 80 at W6UA have been dipoles, inverted Vs, and a delta loop. The quarter-wave sloper is better than any of the others for transmitting, but it is poor on receiving. I have taken down all but the two slopers. They are used for transmitting and receiving, with frequent use of a 40-meter collinear antenna on receiving weak signals.

I also tried this system on 40, with a wire attached to the tower at 30 feet, coming off at 30°. Perhaps because there was so much tower electrically above the attachment point – at least half a wavelength – this one was much harder to tune. The wire length, which was very critical, was some feet shorter than expected, and the VSWR behavior across the band less benign. Not much time was spent on this particular antenna because it seemed no better than a $\lambda/2$ vertical. Both worked well, but neither was the equal of the collinear types available.

The most recent quarter-wave sloper system I have used has been on 160 meters. My first attempt was a single sloping element from the 75-foot level. This places whatever contribution there is from the top guy sections below the point of attachment. I couldn't get this antenna to match by altering the length of the sloping wire, even while making rather severe adjustments. There did seem to be some promise for the system, so the next season I used two sloping elements of about the "correct" length and fed the arrangement with a matching network at the bottom of the tower, with 300-ohm twin-lead going up the tower (Figure 1). This was the best antenna I have used on 160 at W6UA. Previously I had used an inverted V, a center-fed 80-meter dipole at 90 feet and a $\lambda/2$ inverted L. Since the wires must come off the tower at about 45-50° to vertical, the rationale of using two wires instead of one was to attempt to cancel the horizontal current component. As a matter of curiosity I tried adding a third wire and could find no change in setting of the matching components or in the



Figure 1—Illustration of the arrangement used at W6UM for a 160-meter half sloper.

overall effectiveness. Using some rough estimates of component values required for matching, length of feed line, etc., I calculate the feed impedance of the antenna itself to be approximately 100–j300 ohms.

My estimate of how well this antenna performs must be tempered by the realization that conditions during the past two years have been much worse than the period before. During the 160-meter contests, openings to W1, W2 and W3 have been marginal. I have worked nothing with this antenna I hadn't worked before, but the impression remains that the antenna is better than those used earlier. It has done a consistent job into the Caribbean, SA, Pacific and Japan, as well as across the USA. Receiving remains a problem because of the noise. I have taken down the 160-meter version of this antenna. If I put it up again I will definitely install some auxiliary receiving antennas.

The net result seems to be that this is an effective antenna. Getting a good match directly into coax appears easier if the sloping wire is more nearly vertical and if there is not too much loading above the attachment point. The system should be more efficient, up to a point, as there is more vertical structure above the feed point. There is no compelling reason to insist upon using a resonant configuration. The next attempt I make on 160 might well be with the existing 80-meter system, fed at 60 feet and with 80-meter sloping elements, but using a transmission line and matching network at the bottom of the tower as before.

Given that the antenna does work, the areas I feel need further investigation are better characterization and description of it for different parameters, e.g., measurement of the feed impedance as a function of frequency for different sloper attachment points, lengths, angles and conditions of top loading. I would also like to see the current flow on all of the structure mapped via a probe. If some of the results are forthcoming I hope to see them in an early issue of *QST*. — *Charles Weir Jr., W6UM*

From *QST*, December 1979 (Technical Correspondence)

Half-Sloper Variation For 160 M

I read the July *QST* article by W1CF with great interest. I enjoyed it very much and learned something.

A few days ago I was looking at my 80-meter sloper and it occurred to me that by using a loading coil and some more wire it would work on 160. So I took a 4-inch diameter coil of 10 turns of no. 10 wire out of the junk box, attached the coil to the far end of the half sloper, added about 30 feet of wire and ran the wire to the corner of my garage. The noise bridge indicated it was too short, so I added another 10 feet. Presto! Resonance at 1830 kHz with an SWR of 1.1:1.

I think that by using a larger (higher inductance) loading coil, the added wire could be shortened considerably without seriously affecting the 2-to-1 SWR points on the curve.

I have not made too many contacts on 160 yet, as there is very little activity this early in the season around here. I have had several contacts though, always getting at least as good a report as I have given. *—Philip True, W7AQB.*

By Gary E. Myers, K9CZB **From *QST*, June 1980**

A Two-Band Half-Sloper Antenna

When an off-the-wall empirical design like this works well, suspicion and skepticism are warranted. Maybe you'll agree that this sloper idea is an exception!

The popularity of the half-sloper antenna seems to be increasing, as evidenced by recent articles in *QST*.[1,2,3] This type of antenna has some worthwhile advantages, particularly for the lower frequency operator – low-angle radiation for antennas of modest height, compactness and simplicity of construction. On the minus side, narrow bandwidths and difficulties in resonating the system have been reported.[3]

The antenna system to be described here evolved from a simple-minded attempt to design a two-band half sloper for 80- and 40-meter operation. A trap-type of antenna was selected as the design basis because of previous experience with trap antennas and because the inductive loading of the trap on the lower-frequency band allows a somewhat shorter overall length. The same inductive loading, however, was also expected to increase the antenna Q and thereby further decrease the bandwidth. For this reason I was prepared to experiment.

It is well that I was so prepared because the final form of the antenna bears little resemblance to the initial concept. But most interesting — and exciting — is the impressive bandwidth on 80 meters.

The Design

A diagram of the two-band half-sloper antenna system is shown in Figure 1. It can be seen that there is no obvious quarterwave dimension in the entire system. In fact, the radiator itself is a nonresonant device.

Initial attempts to prune the wires to resonance resulted only in a mound of wire clippings and one frustrated amateur. After many hours of cut-and-try experimentation, accompanied by a growing, gut-level appreciation for what apparently was happening, the magic combination of wire lengths and trap component values was found. Impedances of 40 –*j*80 ohms at 7.2 MHz and 60 –*j*40 ohms at 3.6 MHz were measured with a noise bridge. It was then a simple matter to cancel out these capacitive reactances with an inductor.

For convenience, the inductor was placed in the transmission line, rather than at the feed point – final "tweaking" of the system is more easily performed on the ground than at 40 feet (12.2 m) in the air. A Smith Chart exercise shows that the SWR on the transmission line between the feed point and inductor L is 5:1 at 7.2 MHz and 2:1 at 3.6 MHz. When RG-8/U is used, the additional loss incurred because of these SWRs is less than 0.5 dB at 7.2 MHz and is almost nonexistent at 3.6 MHz.



Figure 1—The two-band half sloper. To shield the transmission line from the antenna field, the line is routed up the inside of the support mast, which is grounded. Inductor L is needed to resonate the system.

Performance

This antenna performs very well. Operation at K9CZB is primarily 80-meter cw, with some 40-meter ssb. Power output is nominally 100 watts. Signal reports on 80 have been uniformly good, with comments such as U R LOUDEST 9 ON BAND AND VY FB SIG, VY STRONG. Voice operation on 40 has also resulted in good signal reports, although the praise has not been so lavish. This is my only 80/40-meter antenna, so direct comparisons were not possible. However, it appears to greatly outperform two previous antennas, a 160-foot end-fed wire and a trap dipole, both strung 30 feet above ground. All in all, it is about what I expected from a half sloper.

This kind of performance is nice, but nothing to write an article about, since that has already been done. The real performance story about this antenna can be summed up in one word: bandwidth. A glance at the SWR curves in Figure 2 will open the eyes of any 80-meter operator. As far as I know, this is unheard-of bandwidth for such a simple and compact antenna. It is a real treat to QSY 400 kHz And see the SWR meter needle barely move. This isn't a low-Q antenna —it's a *no*-Q antenna! The bandwidth on 40 is far less impressive and is, in fact, similar to what has been reported previously for half slopers.

Construction

During experiments with prototypes of this antenna, I noticed some sensitivity to feed-line placement and length. Therefore,



Figure 2—Loading characteristics of the antenna. The SWR curves were determined from a Smith Chart. Impedance values were measured with a noise bridge.

in later versions I ran the feed line up the *inside* of the support mast to shield it from the antenna field. This precaution seems to be effective, for no such sensitivity has been observed since. (I can't help but wonder if this might improve the behavior of any cantankerous half sloper.) If a nonmetallic support is used, or if there is no possibility of placing the feed line inside the support, double-shielded coaxial cable should serve equally well, provided the outer braid is connected to the inner braid at the top of the tower and a ground is connected to the outer braid at the bottom of the tower.

I used standard 10-foot TV mast sections for my support, simply because they were on hand. This results in a very flimsy and flexible mast in a 40-foot length, though. The first 20 feet must be doubled up with long U-bolts if the mast is to be walked up. The price of six sections of TV mast is about the same as a 36-foot telescoping push-up mast, but the latter is much sturdier and far easier to erect. If support materials are not already on hand, the telescoping mast is the better choice. I should mention that I took the trouble to bond all sections of mast together electrically to ensure good conductivity and to guard against TVI from rectification at joints after inevitable corrosion sets in. The base of the mast should be grounded. Effects from the guy wires can largely be avoided by breaking them into nonresonant lengths with strain insulators placed at the mast and every 19 feet thereafter.

The inductance and capacitance values shown in Figure 1 must be used for the trap. Construction techniques for the trap are covered in *The ARRL Antenna Book.*[4] A novel and inexpensive method of trap construction has been described by WB9OQM.[5] I built my trap using the method shown in Figure 3. Traps made in this fashion are much stronger than they appear. I've never had one break, even in high winds that caused property damage. In this antenna, however, the radiator also serves as one of the top guys. For that reason the trap was reinforced. Two 3/16-inch thick pieces of plastic were used with three layers of glass cloth and epoxy sandwiched between them. A rotary wire brush serves well to rough up the inner surfaces of the plastic to ensure good adhesion. However, one may use coarse sandpaper for that purpose. Glass cloth and epoxy are sold as a repair kit in many hardware stores.

Before the antenna wires are connected,



Figure 3—A simple, sturdy trap. The coaxial capacitor should be taped to the antenna wire after installation. It is not necessary to enclose the trap.



Figure 4—SWR curve for 40 meters, showing the effect of tapping L and adjusting feed-line length between L and the transmitter to obtain the best SWR curve. Such adjustments have little effect on 80-meter characteristics.

the trap must be tuned to resonance. A dip meter or noise bridge can be used to measure the resonant frequency. Start with about 30 inches of RG-8/U for the coaxial capacitor. After connecting it to the coil, as shown, 26 or 27 inches of braid will remain. At this point, the resonant frequency should be below 7.0 MHz. Trim the braid at the far end, a little at a time, snipping off the center conductor as you go. Recheck the resonant frequency each time. As 7.2 MHz is approached, continue trimming the braid, but stop cutting the center conductor. To increase the leakage path, the polyethylene dielectric should extend beyond the braid 1/8 to 3/16 inch (3.2 to 4.8 mm) when the trap is resonated at 7.2 MHz. Very close to 24 inches of braid should remain at completion. Tightly tape this end with several layers of plastic electrical tape.

The component values for this trap are exactly the same as those used in the W3DZZ trap dipole,[4] so there are several commercially made traps that may be suitable for this antenna. Traps made for a five-band, two-trap dipole, 108 feet long should have the proper values of capacitance and inductance.

In any antenna system, the radiator feed point impedance repeats itself every half wavelength along the transmission line. Inductor L must be inserted in the transmission line at a half-wave point in order to exactly cancel the capacitive reactance of this antenna system. It is, of course, advantageous to place L as close to the feed point as possible in order to minimize losses. A half wavelength at the lower frequency is as close as you can get without going to the feed point itself. The 90.2-foot length of RG-8/U shown in Figure 1 is an electrical half wavelength at 3.6 MHz for solid polyethylene dielectric coaxial cable *only*. If cable having a velocity factor other than 0.66 (e,g., foam-dielectric coaxial cable) is used, this length will have to be recalculated from the equation

$\ell = 492\ V/3.6$ feet

(Feet × 0.305 = m)

In this equation, V is the velocity factor of the cable to be used. Only RG-8/U or a similar type such as RG-213/U should be employed for this section of the transmission line in order to keep the losses low. If you don't mind a dB or so of loss on 40 meters, RG-58/U is acceptable. The loss on 80 meters will be negligible in any case.

The value of inductor L should be 1.75 µH, but I recommend that a coil having about 3-µH inductance be used to allow some latitude for final tune-up of the system. I mounted 12 turns of a no. 3018 Miniductor (1¼ inch in diameter, 8 turns per inch) in a small Minibox with SO-239 coaxial connectors placed at each end. After tapping the coil for the best SWR curve on 40 meters, the entire assembly was sealed and waterproofed with bathtub caulk.

Tune-up

As seems to be characteristic of half slopers, this antenna can be very touchy to tune up. If the length of transmission line between the radiator and L is not an exact integral multiple of a half wavelength at 3.6 MHz, tune-up can be a real "can of worms." Since the oft-quoted value of 0.66 for the velocity factor of standard RG-8/U is only a nominal value and can vary appreciably from brand to brand (in cheap cable from lot to lot), this length should be determined with a noise bridge.

If a noise bridge is not available, the following procedure may be tried. Cut this section of cable about 6 feet shorter than the calculated length. Prepare a section of RG-58/U, 12 feet long, with solderless connectors on each end. Connect it to both the shortened feed line, using a PL-258 double female connector, and to L. Tap L to obtain the best combination of SWRs at 3.6 and 7.2 MHz. Record the SWR figures and tap position.

Now shorten the RG-58/U by 6 inches and repeat — and repeat — until you are certain you have passed through the point where the SWR values simultaneously bottom out at both frequencies. Prepare a length of RG-58/U (from the same lot) exactly as long as the best experimental length, using permanent coaxial connectors. Seal and waterproof all connections. RG-58/U is recommended for relative ease of pruning. If you don't mind unsoldering a PL-259 each time, RG-8 could be used. However, the additional loss from such a short section of RG-58/U will be infinitesimal at these frequencies.

This procedure is obviously tedious, but it is necessary to obtain good performance on 40 if a noise bridge is not available.[6] In fact, some adjustment of this section of transmission line may be necessary even if a noise bridge is used to measure the electrical length to obtain optimum two-band performance. The exact half wavelength should always be used as a starting point, in any case.

Strangely enough, the above procedures are necessary only to optimize 40-meter performance. My experience has been that merely cutting the half-wavelength section of transmission line to the calculated length, then tapping L to obtain the best SWR at 3.6 MHz, is sufficient to obtain a ratio of 2:1 or less over the entire 80/75-meter band. So tune for 40, and 80 should take care of itself.

Once the antenna system has been resonated, it may pay to experiment with the value of L and the length of transmission line between L and the transmitter. Changing these values will change the shape of the 40-meter SWR curve somewhat. By so experimenting, you may be able to tailor the shape of the 40-meter SWR curve to your operating preference. Don't expect miracles, though, for the range of adjustment seems to be small. Figure 4 illustrates the results of such an effort. These adjustments will have very little effect on 80-meter bandwidth within the range of acceptable SWR on 40 meters.

Further Thoughts

The first prototype was constructed close to my house, and I was therefore concerned that the performance might not be reproducible. The next prototype was erected in a far corner of my yard, over 100 feet from the house and even further from any other structures or conductors. The final version was similarly located. Except for final tune-up parameters, all three behaved almost identically, even though a number of physical changes was made each time. As a final test of the soundness of the design, I built scaled versions for 40/20 and 20/10 meters. They exhibited very similar characteristics, although all parameters of the system seem to become very critical as the design frequency is increased.

The first two 80/40-meter systems were built using a 30-foot mast, yet their behavior was not markedly different from the final version with a 40-foot mast. Since the mast is an electrical part of the system, and since proximity to ground must play some role in the performance of the antenna, other heights, and supports that have beams attached, may yield different results.

The reactance of the trap at 3.6 MHz is 245 ohms. Therefore, there is a possibility of constructing an 80-meter-only version of this antenna by using a 10.8-µH inductor in place of the trap. This has not been tried, however.

Scaling up to 160/80 meters is an attractive possibility. Conceivably, a mast height as low as 50 feet could be used. A starting point would be the doubling of all wire lengths, and using a 16.4-µH coil with a 120-pF capacitor for the trap to preserve the 245-ohms reactance at 1.8 MHz.

There also seems to be a possibility that a slight increase in trap capacitor value, to resonate the tap at 7.1 or 7.15 MHz, might allow better coverage of 40 cw, but probably at the expense of the phone portion of the band. Such a change might have little effect on 80-meter bandwidth, but another round of cut-and-try could prove necessary.

Conclusions

At this point, this is still an experimental design. Further development may eventually allow a cut-to-formula type of construction, but until that happens, be prepared to experiment. The dimensions given in Figure 1 will put you in the ball park and should yield immediate results on 80.

The convenience of Transmatchless operation overall of 80/75, plus a reasonable portion of 40, coupled with an excellent radiated signal, is ample repayment even for many hours of cutting and trying. Once tuned up, this antenna is very well behaved and enjoyable to use. I would like to hear from others who construct antennas based on this design.

Notes

[1] Hopps, "A 75-Meter DX Antenna," *QST*, March 1979, p. 44.

[2] Atchley, "Putting the Quarter-Wave Sloper to Work on 160," *QST*, July 1979, p. 19.

[3] DeMaw, "Additional Notes on the Half Sloper," *QST*, July 1979, p. 20.

[4] *The ARRL Antenna Book*, 13th edition, 1974.

[5] Mathison, "Inexpensive Traps for Wire Antennas," *QST*, February 1977.

[6] [Editor's Note: A third alternative is to use a dip meter to determine an exact half wavelength of line. See Downs, "Measuring Transmission-Line Velocity Factor," *QST*, June 1979.)

By Deane J. Yungling, KI6O **From *QST*, April 1986**

The KI6O 160-Meter Linear-Loaded Sloper

No room for a top-band antenna? Try this one on for size!

After having good success using my linear-loaded, inverted-L antenna over the winter 1984-85 160-meter season, I decided to try linear loading on a different type of 160-meter wire antenna.[1] I have had considerable success with a quarter-wave sloper on 80 meters, but my city-sized lot isn't deep enough to accommodate a full-sized sloper for the 160-meter band. About 120 feet would be required for the sloper to be 10 feet off the ground at the low end; I have about half that distance to work with. Linear loading solved the problem.

This antenna provides an effective bandwidth of about 70 kHz with an SWR of 2:1 or less. At the design frequency of 1.840 MHz, SWR is 1.1:1 with 50-ohm feed line and no matching network or tuner.

Although the individual dimensions are not critical, the sloping wire and the ladder line must resonate at the desired frequency. If the sloping wire is less than 65 feet long, the ladder must be longer, and vice versa, If you use a different length for the sloping wire, you will need to experiment a bit to see how much to add or remove from the ladder length.

Construction

My sloper is hooked onto the tower at about the 55-ft level using a strain insulator (see Figure 1). The coaxial-cable feed fine is securely taped to one tower leg, and the shield is connected to the tower leg with a radiator hose clamp. The tower is grounded at the base with several ground rods. The center conductor of the coaxial cable is soldered to the sloper at the strain insulator and is taped for weather protection where the center conductor and shield separate.

The ladder portion of the antenna is made with the same type of wire as the sloping portion. The ladder spacers are made of 3/8-inch hardwood dowels that have small holes drilled 1 inch from each end to hold the wires. The dowels should be soaked or sprayed with a wood preservative, prior to assembly, for weather protection. Plastic spreaders could also be used, if desired. The wires are firmly tied to the dowels with waxed lacing twine or similar material where the wires pass through the holes. The dowel spacing can be adjusted, with some difficulty, after the dowels are tied.

One end of the ladder is tied to the tower with heavy monofilament fishing line, with the other end tied to a tree or whatever else is handy. The tie-off lines are fanned vertically to keep the ladder from twisting and should be tensioned enough to eliminate any sagging in the ladder. Monofilament fishing fine provides some cushioning if the supporting tree sways or if the wind is strong.

Adjustment

Initially, the ladder should be a few feet longer than shown, to allow for adjustment. The resonant frequency should be checked, and a few inches removed at a time from the tower end of the ladder until the desired frequency is achieved. At this point, the wires should be soldered together and then taped to the end dowel. It appears that there must be an BF beam, or something similar, on the tower for any quarter-wave sloper to work properly. This sloper is no different in this respect. Finally, the antenna, particularly the sloping section, should be kept as far as possible from surrounding guy wires and other objects.

This antenna requires no ground system, balun or matching network over its operational bandwidth. The linear-loaded sloper is simple to construct and easy to adjust, and its performance is superior to my linear-loaded, inverted L.



Figure 1—Construction details for the KI6O 160-meter linear-loaded sloper.

---

[1] D.J. Yungling, "The KI6O Top-Linear-Loaded 160 Meter Inverted 'L' Antenna," *CQ*, Apr 1985, pp 38-39.

By Roger Sparks, W7WKB **From *QST*, December 1995**

The Super Sloper

Dramatically improve the front-to-back of a sloper.

You can imagine my surprise when *ELNEC*[1] revealed that a parasitic element can be combined with a long wire to form a whole family of directional antennas. There on my screen, I was looking at useful combinations not found in that bible of antennas, *The ARRL Antenna Book*. I had been exploring combinations of full-wave parasitic elements with wire arrays. How far off center can I slide a parasitic element, I wondered? "A lot," was the answer coming from *ELNEC* [and confirmed by *EZNEC—Ed.*]. As I offset a closely spaced (0.015 to 0.046 λ) parasitic element by 1/8 to 5/8 λ, a whole family of antennas appeared (see Figure 1).

I call the configuration a Super Sloper because the pattern resembles that of the well-known sloper, but it is greatly enhanced (see Figure 2). Super Slopers provide gain in the direction from the tall to the short pole. The amount of gain depends on antenna length, or more exactly, on the number of half wavelengths in each element.

Like slopers, Super Slopers require two supports, one tall and another shorter. At my station, and in this article, I considered only nonconductive supports. Other builders can explore the possibilities of Super Slopers suspended from metal towers. Super Slopers are very inexpensive to build (if you already have suitable supports). They require only wire and a few feet of PVC pipe.

Unlike slopers, Super Slopers have high feedpoint impedances. A matching network is required when feeding a Super Sloper with a 50-Ω line. The result is a broadband, low-Q antenna (Figure 3). Don't think of this as just one antenna, but rather a whole family of antennas, one for each half wavelength of added length.

Technical Concepts

If you just want to build an antenna, skip ahead to the Practical Antennas discussion. Those with a technical inclination can continue here, and they may even want to take a look at the discussion of long-wire antennas in *The ARRL Antenna Book*.

An antenna is called a long wire if it is one wavelength or longer. The radiation pattern can be described as the surfaces of two opposed cones that are coaxial with the wire and have their apexes meeting at the feed-point. The apex angle becomes smaller and the lobes grow stronger as antenna length increases. An azimuth plot of radiation pattern for single long-wire antennas over ground shows four principal lobes at low radiation angles. There are two principal lobes, *in one direction*, when the antenna is terminated in a matched, resistive load.

Table 1
Spacing and Phase Angle for Various Antenna Lengths

At the spacings listed, the current in the resonant parasitic element is equal to driven-element current ±10%. (Derived from *ELNEC*, under free-space conditions, 0.25-λ offset, at 7.1 MHz.)

Antenna Length (λ)	*Spacing (λ)*	*Phase Angle (degrees)*
0.5	0.046	−156
1.0	0.030	−147
1.5	0.023	−144
2.0	0.018	−142
2.5	0.015	−142
3.0	0.015	−144

Table 2
Impedance and SWR versus Frequency (Figure 5)

Frequency (MHz)	*SWR (200-Ω)*	*Impedance*
14.0	1.54	293 + *j*48
14.1	1.25	248 + *j*13
14.2	1.16	172 + *j*0
14.3	1.75	127 + *j*54
14.4	2.61	107 + *j*113

ELNEC shows that a parasitic element added to a single long-wire antenna creates a *unidirectional* radiation pattern similar to that created by a resistive termination. Energy eliminated from the back goes into useful forward gain. The parasitic element can be tuned as either a director or a reflector.[2]

Experience with Yagis (and many other applications of parasitic elements) led me to believe that all parasitic elements must be nearly a half wavelength long and located within the span of the driven element. That concept is completely *incorrect*. Parasitic elements can be *any* resonant length and offset from the driven element, as long as there is adequate coupling between the elements.

Here's how Super Slopers produce front-to-back ratio (F/B) and gain. The best



Figure 1—Drawing of a Super-Sloper antenna showing nomenclature. This is a 3-λ/2 model. See Figure 7 for construction details.



Figure 2—Azimuth (A) and elevation (B) plots for a 45° sloper, 2-λ/2 (0.25-λ offset, spaced 0.04 λ, low end 0.119 λ above ground) and 6λ/2 (0.25-λ offset, spaced 0.015 λ, low end at 0.066 λ above ground) Super Slopers. The high end of each is λ/2 high.



Figure 4—Patterns of a 3-λ/2 antenna with 0.36-λ offset and spaced 0.04-λ oriented flat at 1/2 λ vs sloping from 1/2 λ to 0.045 λ. A shows the elevation patterns at 0°; B shows the azimuth patterns; C shows elevation plots at azimuth=40°.

F/B results from a 180° phase shift between the currents in the driven and parasitic wires, as seen from a distant location where a pattern null is desired. A phase difference of 180° means that the signals completely cancel each other, if each element delivers equal signal strength. A phase shift of 90° is possible with a 1/4-λ offset, and the remaining 90° phase shift can come from the tuning (length) of the parasitic element. If the fields cancel in one direction, they will reinforce in some other direction, to produce gain.



Figure 3—A plot of impedance and SWR versus frequency for the 2-λ/2 antenna described in Table 6, placed as described in Figure 6. The data source is *NEC/WIRES 1.5* (see Note 3).

By increasing the phase angle of the current in the parasitic element, the angle of maximum cancellation can be moved. This is particularly useful in Super Slopers because the principal lobes of long wires lie at some small angle to the direction of the wire. From Table 1, notice that the current in a resonant parasitic element has about –144° to –156° phasing, which is about right for correct reverse-lobe canceling.

If we want each element to deliver equal signal strengths to a distant location, nearly equal currents must flow in both the driven and parasitic elements: The coupling between elements must be very close. Table 1 suggests the approximate spacings for currents to be equal within ±10%. (The antenna also has gain at closer spacings because gain is affected less by unequal currents than is F/B.)

Designing a Super Sloper

When placed near (and parallel to) the ground, Super Slopers show twin-lobed azimuth patterns with a null, often 10 dB or greater, on the axis of the wire. This center null can be filled by tilting the wire, with the low end in the direction of the null. Figure 4 shows the effects of tilting.

When the antenna is tilted, the end of the parasitic element can become closer to the ground than that of the driven element. When considered as two separate antennas at different heights, the driven and parasitic elements will not have the same patterns. This reduces performance, but locating the parasitic element so that its end height equals that of the driven element can solve the problem. That is, increase the spacing to place the parasitic element end above that of the driven element. Models give this design 1 to 2-dB gain advantage over more closely spaced antennas, but construction is a greater mechanical challenge.

Table 3

Element Spacing versus Phase Angle, Relative Current, Impedance, Gain and Lobe Angle

Derived from *ELNEC* free-space model, 14.2 MHz, 2-λ/2 elements, offset 0.25 λ

Spacing (l)	*Phase Angle (degrees)*	*Relative Current*	*Impedance of Driven Element*	*Gain (dBi)*	*Lobe Angle (degrees)*
0.01	–136	1.62	205 – *j*230	4.98	48
0.02	–141	1.29	128 – *j*138	5.54	48
0.03	–144	1.11	103 – *j*94	5.78	48
0.04	–149	0.97	80 – *j*59	6.1	48

Table 4

Offset versus Phase Angle, Relative Current, Impedance, Gain and Lobe Angle

Derived from *ELNEC*, free-space model, 14.2 MHz, 2-λ/2 elements, spaced 0.02 λ. Notice how little gain changes with different offsets.

Offset (λ)	*Phase Angle (degrees)*	*Relative Current*	*Impedance of Driven Element*	*Gain (dBi)*	*Lobe Angle (degrees)*
0.1	–167	1.08	19 –*j*54	5.7	48
0.15	–157	1.18	48 – *j*101	5.67	48
0.2	–148	1.26	89 – *j*135	5.6	48
0.25	–141	1.29	128 – *j*138	5.57	48
0.3	–139	1.16	134 – *j*111	5.6	48
0.35	–138	0.963	123 – *j*70	5.58	48
0.4	–134	0.71	108 – *j*14	5.4	48
Pattern Reversal Begins					
0.5	–26	0.25	83 + *j*46	3.0	54
0.6	39	1.31	126 – *j*57	5.2	61
0.7	43	1.71	192 – *j*180	4.0	64

The driven element is fed at a current antinode, 1/4 λ from an end. The antennas can be made to exhibit a wide range of feed resistances: 20 to 300 Ω, or more (see Tables 2, 3 and 4). High resistances and wide offsets combine to produce low SWR and useful gain over an unusually great bandwidth (Table 2). I've used 1/4-λ matching lines (using RG-62, a 93-Ω line), 4:1 baluns and ladder lines to successfully match the antenna at high impedances.

You can vary the antenna length (gain increases with length), height, offset, phasing and spacing as needed. These many variables would be difficult to work with if each were a critical adjustment, but fortunately, they are not critical. Tables 1, 3, 4 and 5 show the tolerant design features of these antennas. From these tables, we can observe several trends:

- Current balance greatly affects F/B, with less effect on gain.
- Phase angles change very slowly with antenna length.
- Gain changes very little with changes of current and phasing.
- Gain varies by a little over 1 dB with a spacing increase from 0.01 to 0.04 λ.
- Gain is nearly constant with offsets moving from 0.1 to 0.4 λ.

Good F/B is easy to achieve, even



Figure 5—A radiation pattern over a range from 14.0 to 14.4 MHz. The pattern is that of a 3-λ/2 antenna with 0.36 λ offset, with the ends at ½ λ and 0.045 λ. See Table 2 for the SWR tabulation.



Figure 6—Pattern plots over a frequency range from 7.0 to 7.3 MHz. The antenna is 2-λ/2, with 0.25-λ offset and 0.04-λ spacing. The driven element is 1.02-λ long; the director is 0.98-λ long. See Figure 3 for an SWR curve.

though the antenna is designed for best gain or easy construction. Improved F/B ratios and reverse-oriented patterns are possible from designs optimized at specific frequencies. Computer modeling is the best way to optimize reverse patterns. Figures 5 and 6 show some possible patterns and how the patterns vary with frequency. Table 2 and Figure 3 show predicted SWR.

Practical Antennas

Table 6 describes Super Slopers constructed at my station (refer to Figure I for nomenclature). The principal difference between the two 3-λ/2, 20-meter antennas in Table 6 is the increased offset from 17½ feet to 22 feet. This changes the phasing, resulting in a slightly improved F/B ratio and slightly improved gain. The trade-off is a narrower pattern and a longer antenna.

Table 5
Parasitic Element Length versus Phase Angle, Relative Current, Gain and Lobe Angle

Derived from *ELNEC,* under free-space conditions with 14.2 MHz, 2-λ/2 elements, spaced 0.02 λ apart.

Percent Short (λ)	*Phase Angle (degrees)*	*Relative Current*	*Gain (dBi)*	*Lobe Angle (degrees)*
0	−140	1.30	5.54	48
1	−125	1.47	5.33	49
2	−107	1.53	5.02	51
3	−89	1.43	4.70	52
4	−75	1.23	4.44	53
5	−65	1.05	4.19	53

Table 6
Working Antenna Dimensions

Use a 4:1 step-down transformation to match 50-Ω line.

Antenna Number	*1*	*2*	*3*	*4*	*5*	*6*
Band	40 m	20 m	20 m	20 m	15 m	10m
Length*	2	3	3	2	2	2
Driven (ft)	139.3	106.5	105.6	70	46	34.5
Director (ft)	134.3	104.0	102.2	68	45	32.8
Offset (ft)†‡	34.3	17.5	22	17.5	11.5	8.6
Spacing (ft)	6	1.5	1.5	1.5	1.0	1.0
Feedpoint (ft)‡	34.3	17.5	17.25	17.5	11.5	8.6

*Length expressed as a multiple of λ/2.
†Offset is λ/4, except for antenna 3, where the offset is 0.31 λ.
‡Feedpoint and offset are both measured from the high end of the driven element.


Offset
0.25 to 0.36 λ
∗ Parasitic Director
Length = N × λ/2
Note 1
Note 2
Adjust as Req'd for Desired Element Lengths
Spacing from Table 6
#12 Wire
1/2" to 3/4" PVC Pipe
Feed Line
Note 2
∗ Driven Element
Length = N × λ/2
Note 1
1/2" to 3/4" PVC Pipe
0.25 λ All Versions
Note 1. Spreader length is 2" longer than spacing. Wires are threaded through holes drilled in spreaders.
Note 2. Tension member is 2" longer than 0.60 × spacing. Wires are threaded through holes drilled 1" from each end.
∗ Length must be adjusted for optimum gain or F/B ratio. Begin with lengths given in Table 6.
λ= Wavelength

Figure 7—A method of constructing the long-wire parasitic antenna. Additional center spacers reduce the tendency of the wires to twist in the wind.

A 60-foot mast supported the 3-λ/2 and 2-λ/2 20-meter versions. They were mounted back-to-back and tilted to fill the center null. Another 3-λ/2, 20-meter unit was mounted from a 38-foot mast. The 40-meter version sloped from 60 feet down to 6 feet. All antennas performed as predicted. Additional height at either end definitely increases low-angle radiation, but it reduces high-angle radiation.

Figure 7 shows how I assembled and spread the wires. The departure from straight lines (as depicted in Figure 1) has no practical effect on the antenna. Be sure to place the director over the driven element when erecting the antenna. A director placed at the side will skew the pattern, favoring the side of the director. Keep the Super-Sloper support lines tight to minimize sagging. Severe sagging leads to improper phasing and degraded results. I put a support under my 40-meter Super Sloper at midspan, but I just pull the 20-meter antenna support lines tight. The two elements have a tendency to twist and wrap together in the wind. You can prevent this by using two support ropes at the low end or by using spacers as on transmission lines. Both methods work well. Super Sloper performance suffers from excessive ground losses when the low end is at ground level. I strive for an antenna slope (tilt angle) of 10° to 20° and a minimum height of 6 feet. Higher is better.

A 200-Ω feedpoint impedance is easily transformed to 50 Ω with a 4:1 balun. Ladder line and a tuner are another option. Refer to *The ARRL Antenna Book* for other methods of transforming high feed impedances to values acceptable for modern transceivers. Do not feed the Super Sloper directly with coax unless the coax is part of an impedance-matching section.

Results and Conclusions

I've built and used six Super Slopers very successfully. The F/B is often dramatic. A difference of six S units is not uncommon when switching between two antennas built to favor opposite directions.

This family of antennas has not yet been well researched and studied. Use an antenna modeling program before building designs that are substantially different (eg, longer or made from tubing) from those described in Table 6.

Notes

[1] *ELNEC,* and its successor *EZNEC,* are computer antenna modeling programs available from Roy Lewallen, W7EL. The description files for the antenna plots shown in this article are available as a self-extracting archive file named SUPSLOPE.EXE. This file can be found on the Internet (FTP to OAK.OAKLAND.EDU, directory pub/hamradio/arrl/qst-binaries).

[2] Parasitic elements offset more than 1/2 λ from the driven element, become reflectors.

[3] *NECIWIRES 1.5* is a computer antenna modeling program available from Brian Beezley, K6STI.

By John F. Lindholm, W1XX **From *QST*, January 1983**

The Inverted L Revisited

City dwellers, don't despair. Here is a *good* 160-meter antenna that should fit on your lot!

I'll never know what inspired me to make a few contacts in the ARRL 160Meter Contest. My antenna was made by tying together the open-wire feeders of my 80-meter dipole. The performance was not fantastic, but it was the first step in getting me "hooked" on the "gentlemen's band." Working three dozen European stations from a friend's house got my interest up. My friend has a good 160-meter antenna system – and *lots* of property to fit it on!

Returning to my 60 × 150-foot lot made me feel depressed.[1] I suffered all winter while listening to the others working VKs, ZLs and even JAs at daybreak. What could I do to improve *my* signal?

Many hours the following summer were spent trying to figure out how to cram a 160-meter antenna within the confines of my small lot. Space restrictions dictated that my wire be no longer than a standard 80-meter dipole. I began to consider alternative antennas.

Shunt feeding my 50-foot tower was investigated but dismissed for various reasons. This arrangement would require disconnecting the shunt feed when cranking down the tower, and all guy wires would have to be broken up into nonresonant lengths with insulators. Additionally, my cables would have to be rerouted to ground level. I then considered a full-length dipole originating in a neighbor's yard three houses to the east, crossing my property and finally terminating in the yard two houses to the west! This idea was rejected. The legal negotiation fees would have run into six figures! After much head scratching, I settled on the inverted L, an antenna made popular by the grand master of 160-meters, Stew Perry, W1BB. I credit Stew for coming to my rescue!

The Inverted L

The inverted L was selected because it requires no more space than an 80-meter dipole and I could utilize my 50-foot crank-up tower for attachment. The vertical part is 50 feet long, and the horizontal part measures 130 feet, for an overall length of 180 feet (Figure 1). This makes the antenna approximately 3/8 λ, with the horizontal part providing top-loading. W1BB advises making the vertical section as long as possible (depending on tower height), and that an overall length of 160 to 180 feet works well.

Construction

With a bow and arrow, I successfully attached the far horizontal end of the antenna to the top of a 60-foot fir tree. From there, I ran the wire back to the top of the tower, where I bracketed a 30-inch-long two-by-four with an insulator screwed in the end (Figure 2). No. 14 Copperweld wire is used for the horizontal section, and no. 10 copper wire is used for the vertical section, which is spaced about 2 feet from the tower. These two wires are soldered to-



Figure 1—The W1XX inverted L is arranged in this manner.



Figure 2—Detail of how the antenna is mounted to the top of the tower. TV-mast clamps are used to secure the wooden insulator.



Figure 3—A ground rod at the tower base serves as a physical support for the insulator, and as an rf ground. Radial wires are connected to the rod by means of a ground bus, as described in the text.

gether at the insulator.

A plumb line was used to locate a point on the ground directly below the 90° bend in the "L." At this point, a 10-foot copper-clad ground rod was pounded into the earth, leaving 18 inches sticking out. A two-by-four is clamped to the ground rod by means of TV-mast U bolts. The lower end of the vertical wire is attached to an insulator that is screwed into the top of the wooden block (Figure 3). Next, I stripped some coaxial cable (RG-8/U) of its outer braid and used this to make a ground bus around the antenna base. One side of the open-wire transmission line is soldered to the base of the vertical antenna element, and the other side to the bus, which is attached to the ground rod with a clamp. This bus also serves as a connection point for the radials. So far, less than an afternoon of work had been invested.

Radials — the More the Better

The next day, my objective was to install radial wires, which are necessary because the inverted L is essentially a top-loaded vertical radiator. Previous meditation convinced me that several radials would fit on my lot. I'd *make* them fit! All radials were cut to 1/4 λ (125 feet), using scrap wire. About 300 feet of surplus telephone ground wire provided a good start. Stripping some old coaxial cable with a single-edged razor blade produced two radials from one length of wire (outer and center conductors). My technique for radial installation consisted of creasing the earth with a spade and shoving the wire in; afterwards the turf was pressed back into place with my heel.



Freq. kHz	VSWR
1800	2.4:1
1805	1.9:1
1810	1.55:1
1815	1.24:1
1820	1.0:1
1825	1.15:1
1830	1.5:1
1835	1.9:1
1840	2.75:1
1845	3.1:1
1850	4.2:1

Figure 4—SWR curve for the inverted L, with the Transmatch adjusted for an SWR of 1 at 1820 kHz.

With space a problem, it may be impossible to place all your radials in a straight line; don't worry, because it is not necessary. My installation followed a zigzag path to avoid fixtures like the house and driveway. W1BB advises putting some radials under the horizontal part of the antenna. Unfortunately, the location of my garage prevented this. Initially, only four radials were planted, but more were added later. As with all vertical antennas, the more radials you can put in the ground, the better the performance!

Matching System

Voltage-fed antennas approximately $^1/_2$-λ long, such as the inverted L, will have a fairly high feed-point impedance. They will also exhibit inductive or capacitive reactance, depending on whether the antenna is slightly longer or shorter than $^1/_2$ λ. Since the inverted L does not have a 50-ohm impedance, a matching system is needed. To make tuning adjustments easier, I opted for locating the Transmatch *in* the shack, using open-wire line to the antenna. Being able to adjust the antenna match conveniently is recommended, since the SWR climbs rapidly as you shift frequency. For example, adjusting the Transmatch for a 1:1 SWR at 1820 kHz produces an SWR of 2.4:1 at 1800 kHz (see Figure 4). With the Transmatch located in the shack, you can easily adjust for a 1:1 SWR no matter where you operate in the band. My Transmatch consists of a plug-in, link coupled coil and variable capacitors – all scrounged at flea markets. Any of the configurations found in the *ARRL Antenna Book*[2] should work well.

Performance

Does the antenna work? Having no comparison antenna, my conclusions are subjective. But I've been on the air enough to know when, as they say, "it plays." With only four radials in place, my first night of operation yielded plenty of U.S. contacts, plus a Caribbean DXpedition on the first call. Subsequently, many European stations have been worked from my northeast location with good signal reports. Contest activity has yielded some respectable scores, including many QSOs with the Caribbean, and South and Central America — even Antarctica!

By adjusting my Transmatch, I made limited tests with the L on 75-meter ssb. Comparisons were made to a 75-meter dipole at 50 feet. For signals close in, the L was down by some 3 to 5 dB, but equal or superior to the dipole for signals from eastern Europe. Apparently, the 160-meter inverted L also provides a low angle of radiation on this band too. On bands higher than 75 meters, the radiation angle will be tilted *upwards*, rendering the antenna inefficient for DX work. This phenomenon is explained in *The ARRL Antenna Book*.[3]

Giving up the 160-meter band for lack of sufficient real estate is unwarranted. With the inverted L, you can work Top Band from your urban lot. Installation is a breeze, and the performance is admirable. *Now* what's your excuse for missing out on the excitement of 160 meters?

Notes

[1] m = ft × 0.3048.

[2] *The ARRL Antenna Book*, 14th ed. (Newington: ARRL, Inc., 1982), pp. 4-1 through 4-8.

[3] *Ibid.*, pp. 2-23 through 2-24.

From *QST*, July 1991 (Technical Corespondence)

160-Meter Antennas

A recent QST article[1] described two 160-meter inverted-L antennas. The total length of one of the antennas (the vertical element and the horizontal arm) is approximately 1/4 λ; the other antenna is 1/2 λ long. The current-driven 1/4-λ antenna requires a fairly extensive ground screen to realize good radiation efficiency. On the other hand, the voltage-driven 1/2-λ antenna requires only a ground stake-or no ground at all. Here's some additional information to aid you in selecting between these alternatives.

Because the current distribution of these two antennas is quite different, the radiation characteristics are also different. That explains why some signals are ". . . very loud or very weak," depending on station distance, propagation conditions and which antenna is being used.

In the captions for the figures illustrating the two antennas, it's stated that the support poles could be metal or wood. Because the vertical element of the inverted L runs parallel—and rather close to—the support pole, one may wonder whether, if the pole is metal, this proximity will influence antenna performance.

The three antenna types I'll discuss are illustrated in Figure 1; they are (A) the 1/4-λ inverted L; (B) the 1/2-λ inverted L; and (C) the T antenna. Figures 2 and 3 show the calculated[2] radiation patterns for the two inverted-L antennas, assuming average ground ($\sigma = 3$ mS/m, $\varepsilon = 13$). The support poles are trees (or other wooden supports) 50 feet tall. Note that the horizontal arm of the antenna is close to the ground, in terms of wavelength (0.1 λ), and that, in this case, *ELNEC* overestimates the gain of horizontally polarized antennas at a height of 0.1 λ by about 3 dB.[3]

The reason the patterns are so different is because the vertical antenna element carries a heavy current when the antenna length is 1/4 λ, whereas the vertical antenna element carries only a small current when the antenna length is 1/2 λ. Hence, there is a great difference between the vertically and horizontally polarized components of the radiation field for these two inverted Ls. The former antenna has a monopole-like pattern, whereas the latter antenna has a dipole-like pattern.

The lengths given in Figure 1 are those for resonance at 1.9 MHz. DeMaw's dimensions give wire lengths that are a bit too short for resonance (according to *ELNEC*). (In practice, one would trim the antenna length for resonance.)

If you want to work DX, it is advantageous to deploy an antenna that has a deep overhead null in its radiation pattern. This minimizes high-angle sky-wave signals, noise and interference, and improves the signal-to-noise ratio of distant weak signals. The T antenna exhibits this feature. Figure 1C provides dimensions for a T antenna with a resonant frequency of 1.9 MHz; the radiation patterns are given in Figure 4. This antenna's radiation field is almost entirely vertically polarized.

For these plots, the antenna was in the X-Z plane (Z is the vertical axis and 0° azimuth is in the + X direction). The 0° azimuth for the inverted Ls is the direction that the horizontal arm points (away from the feed). There is a slight azimuthal pattern asymmetry for these antennas because the antenna structure is not symmetrical



Figure 1—Sketches for simple wire antennas for 160 meters (1.9 MHz); A, 1/4-λ inverted L; B, 1/2-λ inverted L; and C, 1/4-λ T antenna.



Figure 2—Radiation patterns for Figure 1A's antenna over average ground. The radiated field is dominantly vertically polarized—a monopole-like pattern. The absence of an overhead null in the vertical-plane pattern (compare Figure 2A with Figure 4A) is due to the horizontally polarized component of the field radiated by current on the antenna's horizontal arm.



Figure 3—Radiation patterns for Figure 1B's antenna over average ground. The radiated field is dominantly horizontally polarized in the plane broadside to the antenna, and vertically polarized in the plane of the antenna—a dipole-like pattern. Hence the almost circular pattern at the high elevation angle, 75° (B), and the broadside directivity at the lower elevation angle, 25° (A).



Figure 4—Radiation patterns for Figure 1C's antenna over average ground. The radiated field is almost entirely vertically polarized. The horizontally polarized component of the field radiated by current on one horizontal arm of the T is canceled by that radiated by the other arm.

with respect to the feed.

The effect of a well-grounded metal support tower was also studied. Surprisingly (to me), the effect is rather small, particularly for the 1/4 λ inverted L and 1/4 λ T antennas. The effect on the impedance of the 1/2-λ inverted L looked at first to be significant, but this is only because a small change in the resonant frequency of the antenna (the metal tower couples reactance into the antenna system and so changes the system's resonant frequency) results in a significant impedance change at frequencies near the anti-resonant frequency. Only a slight retuning of the matching circuit is necessary; the radiation patterns are affected relatively little. A 6½-foot nonconductive rope connecting the top ends of the horizontal arm to the support towers is assumed. For 50-foot support poles, it matters little (for 160-meter antennas) whether the poles are metal or wood.

But this is not the case if the support tower is also the mount for a 20-meter Yagi, because the tower and Yagi are much more nearly resonant than the tower alone. In this case, the tower carries a heavy current (0.8 A compared with the 1-A base current in the 1/4-λ inverted L). Because the phase of the tower current is +145° with respect to the phase of the current on the vertical element of the inverted L, the antenna's vertically polarized field is almost canceled. Also, the inverted L is no longer resonant: In fact, it is far from resonant; its impedance is 1547 –*j*2635 Ω, compared with the inverted L's impedance of 14 Ω with tree support.*–John S. Belrose, VE2CV*

Notes

[1] D. DeMaw, "The 160-Meter Antenna Dilemma," *QST*, Nov 1990, pp 30-32.

[2] *ELNEC* was used for all calculations. This program is available from Roy Lewallen, W7EL.

[3] *ELNEC* is a version of *MININEC*. *MININEC* assumes that the antenna is over a perfect earth for the purpose of calculating the antenna's impedance and the current distribution. The result of this approximation is that for horizontally polarized antennas, *MININEC* overestimates the gain of the antenna by an amount that increases as the height of the dipole decreases below a height of about 0.2 λ. The effect of real ground on the shape of the radiation pattern is correctly predicted, however, since for the calculation of the far-field pattern the program employs Fresnel reflection coefficients for the specified earth type.

By Brian L. Wermager, K0EOU **From *QST*, April 1986**

A Truly Broadband Antenna for 80/75 Meters

Have you been dreaming about an antenna that will do justice to your no-tune, solid-state transceiver by letting you operate across the entire band from 3.5 to 4.0 MHz? Then this may be the antenna for you!

With declining sunspots and poor conditions on the higher HF bands, 80 meters has suddenly become very popular. But, unfortunately, many hams are not able to use this band to its full potential. It offers every kind of ham activity from CW to phone, from nets and ragchewing to great DXing, but many hams are too limited by the frequency range of their antennas to enjoy this band completely.

Antenna-matching networks are one answer, but they spoil the advantage of the no-tune feature of modern transceivers. Matching networks also are often less effective than many hams think; they introduce losses. The losses can be significant at some settings which provide a match. With these things in mind, I decided to try some ideas that might give me a more broadbanded antenna. The prime requirement was that it be fed with common 50-ohm coaxial cable, with no traps, coils or capacitors.

First, I tried a quarter-wave sloper. This antenna worked very well, with a bandwidth of 300 kHz between the 2:1 SWR points. It still, however, limited me from operating CW DX at the bottom of the band and the phone nets at the top of the band. There had to be a better antenna.

Antennas can be broadbanded by using large-diameter elements. With this in mind, I began experimenting with two-wire slopers, attached to a common feed point, but with the wire ends fanned out from each other. (See Figure 1.) This seemed to help, but not as much as I had hoped. It did, however, shorten the length required for the sloper. For those with a short tower, this idea could make an 80 or 160-meter sloper possible when a single-wire sloper would be too long.

The Fickle Finger of Fate Strikes!

While I was trying one of these two-wire antennas at a low height on my tower, the SWR was less than 2:1 from 3.5 to 4.0 MHz! After several attempts to get it to work the same way at the top of the tower, I discovered that these results could be attained only when my old quarter-wave sloper was at the top of the tower *and grounded* to the tower. (See Figure 2.) The two antenna elements were obviously interacting with each other, broadening the bandwidth tremendously. Further pruning of the lengths of both the sloper and the two-wire element resulted in the amazing SWR curves shown in Figure 3.

What's Going On?

I will leave the question of *why* it works to the experts. (See the sidebar to this article.—Ed.) Like a true ham, I subscribe to the old saying, "If it works, leave it up and don't mess with it." My guess, however, is that it is something like one-half of a two-element log periodic seeking its mirror



Figure 1—Arrangement of the original K0EOU experiment. The coaxial cable shield is connected to the tower, with both wires of the two-wire element connected to the center conductor. The wires are spread approximately 8 feet at the ends and are each approximately 52 feet long.

The MININEC Analysis of the KØEOU Three-Element Half Sloper

The Mini-Numerical Electronics Code (MININEC) analyzes thin-wire antennas, solving an integral equation representation of the electric fields using a method-of-moments technique. MININEC solves for the currents, impedance and patterns for antennas composed of wires in arbitrary orientations in free space and over perfectly conducting ground.

The impedance at the feed point calculates to be 79.4 + *j*1859.8 ohms. This assumes a perfect ground beneath the structure and simply a 3-foot extension of the tower above the connection of the upper wire. In practice, the impedance will be affected by both the ground conductivity and the top-loading effect of a beam antenna atop the tower.

A fair amount of current flows in the top section above the upper wire connection point. Top loading will affect the phase of this current, which will be reflected as a change in impedance at the feed point. In other words, the calculated data is not absolute. Use it as an approximation only.

A relatively high current flows at the base of the tower to ground—more than in any other part of the system. This indicates that a good earth connection, and even a radial system, would offer highest efficiency.

The antenna patterns, Figures A, B and C, are also approximations. Polarization is predominantly vertical–at low angles it may be considered to be almost completely vertical. Broadside to the direction of the wires, the polarization becomes horizontal at high radiation angles, ie, above 75 degrees. At 60-degrees elevation, the vertical component is almost 16 dB greater than the horizontal. The vertical component increases significantly at lower elevation angles, being in excess of 30 dB above the horizontal component at a 5-degree elevation. These figures all apply in a direction broadside to the wires. In the direction of the wires, both "front" and "back," the radiation is entirely vertically polarized.–*Gerald L. Hall, K1TD*



Figure A–Antenna azimuth radiation pattern for the KØEOU three-element half sloper antenna. Values are in dBi. Add 6.0 dB to the values shown.

Figure B—Antenna elevation radiation pattern, in the direction of the wires, for the KØEOU antenna. Values are in dBi. Add 6.0 dB to the values shown.

Figure C—Antenna elevation radiation pattern, in a direction broadside to the wires, for the KØEOU antenna. Values are in dBi. Add 6.0 dB to the values shown.

image in the grounded tower. The top element is tuned for the lower portion of the band and the two-wire element for the upper portion. In fact, there is a little SWR "bump" in the middle of the band that seems to give further evidence of this.

How Well Does It Work?

Although I have no way of scientifically plotting the antenna pattern, it does seem to be vertically polarized. Good DX performance from the antenna seems to verify this. Because many contacts have been made in all directions, the antenna probably has a fairly omnidirectional pattern. On-the-air comparisons with a quarter-wave sloper across town show that the antenna performs at least as well as the sloper. It also seems to have a little less noise on receive than the sloper.

Getting One Up for Yourself

If you have a tower over 40 feet high, you should be in business. The element dimensions will vary according to the height of your tower. My friend Kelly Davis, KD7XY, constructed one of these antennas on his 50-foot tower so we could see how the dimensions would change.

Measurements of his antenna are shown in Figure 4.

It is interesting to note that the height of the feed point on the tower does not appear to be critical at all. The angle of the wires in the two-wire element does not seem to be critical either. The sloper element, however, should come down *between* the two wires of the lower element. The sloper angle is about 45 degrees. As you attempt to get the



Figure 2—The antenna as constructed at K0EOU. The tower is 70 feet high. The feed point is as described in Figure 1 and is 15 feet above ground level on the tower. The sloper element is 74 feet long, is connected to the tower at the top end and slopes to a point 11 feet above ground level at the end.



Figure 3—SWR measurements for the antenna at K0EOU. The highest SWR measurement between 3.5 and 4.0 MHz is 1.2:1.

lowest possible SWR from the antenna, remember that the angle of the sloper to the tower and its distance from the ground at the end will have an effect on the bandwidth. Because these antennas can be pruned from the ground, the trial-and-error method is easy. When pruning the antenna, remember that the two elements are cut for different frequencies. Changing the length of the top element changes the performance at the lower part of the band. Changing the lengths of the two-wire elements changes the performance at the top part of the band. Don't give up until your antenna SWR is, at the very most, 1.5:1 from band edge to band edge.

Use good insulators at the ends of each of the three wires. I used nylon fishing line at first, but one foggy, wet night the wire in the top element burned through in three places. It surprised me that there could be such high currents in a part of the antenna not even connected to the feed line, but I should have known better. Remember also that other objects around the antenna, such as other antennas or guy lines, could adversely affect antenna performance. Keep the antenna as much in the clear as possible.

Some Untried Ideas

I hope others will try some modifications to this antenna. For example, there should be no reason why a single wire for the bottom element won't work. My small city lot doesn't give me room to try a single wire, as it would surely need to be longer than the two-wire element. I would also like to see someone try cutting the top element for the high end of the band, and the bottom element for the low end. This could shorten the sloper element for someone with a shorter tower and may even give the antenna some gain in the direction of the two-wire element. It might also be possible to construct an antenna for another band inside of this one (40 meters, for example). The same feed point could be used, but with another sloper element for the second band. Another possibility is to construct the antenna with two dipoles. It is my guess (and only a guess), that it is the merging of the ends of the elements that causes the 50-ohm impedance of the antenna.

Winter gives us the best conditions on the 80/75-meter band. You can be ready to use the whole band with this simple-to-construct and very broadband antenna.



Figure 4—The antenna installation at KD7XY. The tower is 50 feet high. The sloper element is attached at 46 feet, is 78 feet long, and is only 1 foot above ground level at the end. The two-wire element is 53 feet long and is attached to the tower at 13 feet above ground level. Like K0EOU's antenna, it is virtually "flat" across the band; highest measured SWR is 1.4:1.

From *QST*, August 1987 (Technical Corespondence)

Improved Broadband Antenna Efficiency

When Brian Wermager's article. "A Truly Broadband Antenna for 80/75 Meters," arrived at HQ, I wanted to see if the antenna worked as well as claimed before publishing the information in *QST*.[1] I stopped tuning the antenna when the SWR was less than 1.6 across the entire band.

For working DX the antenna seemed to work as well as, or better than, a dipole at 50 feet. Casual contacts were not difficult to make, but in contests, it was a different matter. The results were satisfactory, but could "satisfactory" be changed to "outstanding"?

The key to improving the efficiency of this antenna is found in the sidebar accompanying the article. The MiniNumerical Electronics Code (MININEC) computer analysis done by Gerald Hall, K1TD, shows that: "A relatively high current flows at the base of the tower to ground—more than in any other part of the system. This indicates that a good earth connection, and even a radial system, would offer highest efficiency."



Figure 1–Graph showing SWR vs frequency for the K0EOU 80/75-meter antenna. The lower curve depicts results before adding ground radials; the upper curve was plotted after adding radials and retuning the antenna.

A system of radial wires improves antenna efficiency by cutting ground resistance losses. The decreased resistance in ground losses will also narrow the antenna bandwidth. The question now becomes: Is the narrowing of the bandwidth too much? I decided to investigate that question next.

With help from my brother-in-law, I installed 42 radials around, and bonded to, the tower base. As expected, SWR increased across the entire band. After I retuned the antenna, the SWR was below 2:1 across the entire band (see Figure 1). As for results, DX stations are typically 2 to 6 S units stronger on the K0EOU antenna than on the dipole at 50 feet. Contest QSOs are now a reality. I am not the loudest East Coast station on the band, but I am very pleased with the performance of the broadband antenna. (The dipole has been removed and stored!)—*Chuck Hutchinson, K8CH*

---

[1] B. Wermager. "A Truly Broadband Antenna for 80/75 Meters," *QST*, Apr 1988, pp 23-25.

By Thomas Russell, N4KG From *QST*, June 1994

Simple, Effective, Elevated Ground-Plane Antennas

Here's an easier and better way to use your grounded tower as a vertical antenna on 160 or 80 meters.

This article describes a simple and effective means of using a grounded tower, with or without top-mounted antennas, as an elevated ground-plane antenna for 80 and 160 meters.

Grounded towers have been used as shunt-fed verticals on the low-frequency amateur bands for many years. Generally. they required a gamma- or omega-type matching network and an extensive radial system for efficient operation. Recent computer studies reveal that simple elevated radial systems consisting of only four wires can produce results equivalent to 120 buried radials. Typically, these antennas are modeled as isolated monopoles. Presumably, grounded towers could be used with an appropriate shunt-fed matching network. I've found an even easier method!

From Sloper to Vertical

Recall the quarter-wave length sloper, also known as the half-sloper. It consists of an isolated quarter wavelength of wire, sloping from an elevated feedpoint on a grounded tower. Best results were usually obtained when the feedpoint was somewhere below a top-mounted Yagi antenna. You feed a sloper by attaching the center conductor of a coaxial cable to the wire and the braid of the cable to the tower leg. Now, imagine four (or more) slopers, but instead of feeding each individually, connect them together to the center conductor of a single feed line. *Voila*! Instant elevated ground plane.

Now, all you need to do is determine how to tune the antenna to resonance. With no antennas on the top of the tower, the tower can be thought of as a fat conductor and should be approximately 4% shorter than a quarter wavelength in free space. Calculate this length and attach four insulated quarter-wavelength radials at this distance from the top of the tower. For 80 meters, a feedpoint 65 feet below the top of an unloaded tower is called for, The tower guys must be broken up with insulators for all such installations. For 160 meters, 130 feet of tower above the feedpoint is needed.

That's a lot of tower to dedicate to a single-band antenna, especially for someone with limited real estate. What can be done with a typical grounded-tower-and Yagi installation?

A top-mounted Yagi acts as a large capacitance hat, top loading the tower. Fortunately, top loading is the most efficient means of loading a vertical antenna. The amount of loading can be approximated by using an empirical formula developed by John Devoldere, ON4UN.[1]

Devoldere found that the electrical height of a top-loaded tower can be approximated by:

$$L=0.38F(H+\sqrt{2S-H/500}) \qquad \text{(Eq 1)}$$

where

L is the approximate electrical length in degrees
F is the frequency in MHz
H is the height of the tower under the Yagi in feet
S is the area of the Yugi in square feet

To check Eq 1, consider the case of no antenna on top, where S = 0. Then L = $0.38 \times 3.6 \times 65 = 88.9°$, which is very close to the desired 90° quarter wavelength.

The effective loading of a Yagi is the portion of the equation under the radical. The examples in Table 1 should give us an idea of how much top loading might be expected from typical amateur antennas. The term H/500 is ignored as insignificant compared with 2S.

The values listed in the Equivalent Loading column of Table 1 tell us the approximate vertical height replaced by the antennas listed in a top-loaded vertical antenna. To arrive at the remaining amount of tower needed for resonance, subtract these numbers from the nonloaded tower height needed for resonance. Note that for all but the 10-meter antennas, the equivalent loading equals or exceeds a quarter wavelength on 40 meters. For typical HF Yagis, this method is best used only on 80 and 160 meters.

Table 1
Effective Loading of Common Yagi Antennas

Antenna	*Boom Length (feet)*	*S (area, ft²)*	*Equivalent Loading (feet)*
3L 20	24	768	39
51 15	26	624	35
4L 15	20	480	31
31 15	16	384	28
5L 10	24	384	28
4L 10	18	288	24
3L 10	12	192	20
TH7	24	—	40 (estimated)
TH3	14	—	27 (estimated)

Construction Examples

Consider this example: A TH7 Yagi mounted on a 40-foot tower. The TH7 has approximately the same overall dimensions as a full-sized 3-element 20-meter beam, but has more interlaced elements. I estimate its equivalent loading to be 40 feet. At 3.6 MHz, 65 feet of tower is needed without loading. Subtracting 40 feet of equivalent loading, the feedpoint should be 25 feet below the TH7 antenna.

I ran 10 quarter-wavelength (65-foot) radials from a nylon rope tied between tower legs at the 15-foot level, to various

---

[1] J. Devoldere, *Antennas and Techniques for Low Band DXIng* (Newington: ARRL, 1994).



Figure 1—At A, an 80-meter top-loaded, reverse-fed elevated ground plane, using a 40-foot tower carrying a TH7 triband Yagi antenna. At B, dimensions of the 3.6 MHz matching network, made from RG-59.

supports 10 feet high. I tied nylon cord to the insulated, stranded, 18-gauge wire, without using insulators. The radials are all connected together and to the center of an exact half wavelength (at 3.6 MHz) of RG-213 coax, which will repeat the antenna feed impedance at the other end. Figure 1 is a drawing of the installation. I used a Hewlett-Packard low-frequency impedance analyzer to measure the input impedance across the 80-meter band.

An exact resonance (zero reactance) was seen at 3.6 MHz just as predicted. The radiation resistance was found to be 17 Ω. The next question is how to feed and match the antenna.

My approach to 80-meter antennas is to tune them to the low end of the band, use a low-loss transmission line, and switch an antenna tuner in line for operation in the higher portions of the band. With a 50-Ω line, the 17-Ω radiation resistance represents a 3:1 SWR, meaning that an antenna tuner should be in-line for all frequencies. For short runs, it would be permissible to use RG-8 or RG-213 directly to the tuner. Since I have a plentiful supply of low-loss 75-Ω CATV rigid coax, I took another approach.

I made a quarter-wave (70 feet × 0.66 velocity factor = 46 foot) 37-Ω matching line by paralleling two pieces of RG-59 and connecting them between the feedpoint and a run of the rigid coax to the transmitter. The magic of quarter-wave matching transformers is that the input impedance (R_i) and output impedance (R_o) are related by

$$Z_o^2 = R_i \times R_o \qquad \text{(Eq 2)}$$

For $R_i = 17\ \Omega$ and $Z_o = 37\ \Omega$, $R_o = 80\ \Omega$, an almost perfect match for the 75-Ω CATV coax. The resulting 1.6:1 SWR at the transmitter is good enough for CW operation without a tuner.

The Proof is In the Log

How effective is this antenna? Well, I used to install a 60-foot aluminum tower and 100 radials, 100 feet long in a clear one-acre field every winter, and remove it every spring for mowing. The top-loaded reverse-fed elevated ground-plane antenna has replaced that antenna with no regrets. My only other 80-meter antenna is a dipole at 110 feet broadside to Europe and the South Pacific,

I use the elevated ground plane for South Africa, South America. the Caribbean, parts of the Pacific and Asia, both long and short path. With it I have worked everything I can hear, with 1200 W output, including HL (rare in Alabama); HS; UA9; UA0; UI; UJ; UL; most of the VK9s; XV; ZS1; ZS8MI; ZS9; 3Y5X; 8Q; 9M2; and 9V1. While running 5 W output. I have even worked two JAs with this antenna. which may say more for its effectiveness than anything else.

Will It Work on 160 Meters?

You bet it will, but it takes another tower. For the 160-meter band, a resonant quarter-wavelength requires 130 feet of tower above the radials. That's a pretty tall order. Subtracting 40 feet of top loading for a 3-element 20-meter or TH7 antenna brings us to a more reasonable 90 feet above the radials. Additional top loading in the form of more antennas will reduce that even more.

Recently, a friend moved to the country, and he needed a 160-meter antenna in a hurry for an upcoming contest. He had stacked TH6s on a 75-foot tower. I suggested he try four elevated radials at 10 feet above ground, with a tuner if necessary. He connected four radials about 120 feet long and a piece of RG-58. The SWR measured under 2:1 and he worked everything he heard in the contest. Figure 2 is a drawing of this installation.



Figure 2—A 160-meter antenna using a 75-foot tower carrying stacked triband Yagis.

Another friend had a 120-foot tower with no antennas on it. He ran four elevated radials at 10 foet and obtained an SWR below 1.5:1 with a 50-Ω feed line. During the contest, he even beat out some big guns.

Elevated ground-plane antennas work! This simple, reverse-feed system makes it possible to feed grounded towers easily and efficiently.

References

A. Christman, "Elevated Vertical Antenna Systems," *QST*, Aug 1988, pp 35-42 (Feedback, *QST*, Oct 88, p 44).

A. Christman, "More on Elevated Radials," *QST*, Mar 1993, p 72 (Technical Correspondence).

CHAPTER EIGHT

RECEIVING ANTENNAS

8-1 **Ungrounded Beverage Antennas**
From *The ARRL Antenna Compendium Volume 4*

8-5 **A Receiving Antenna that Rejects Local Noise**
From September 1995 *QST*

8-9 **The K9AY Terminal Loop–A Compact, Directional Receiving Antenna**
From September 1997 *QST*

8-13 **Hum Problems When Switching the K9AY Loops**
From May 1998 *QST* (Technical Correspondence)

Ungrounded Beverage Antennas

So you've heard how Beverages can help you hear better on the lower bands, but you're still not convinced they're worth the bother. K6STI analyzes the Beverage, especially an easy-to-construct "ungrounded" version.

Beverages are amazing receiving antennas. A good Beverage can turn a signal barely audible on your transmit antenna into solid, Q5 copy. A Beverage antenna (named after 1920s inventor H. H. Beverage) is a long, low wire used for receiving. They're most popular on the 160, 80, and 40-meter bands. Although occasionally pressed into service, Beverages are much too lossy for regular use as transmitting antennas.

Conventional Beverages are fed against ground. Although very long wires may develop a few dB of front-to-back ratio, unterminated Beverages are essentially bidirectional. Terminating a Beverage through a resistance to ground at the far end creates a highly unidirectional pattern. Beverages typically are 1 to 15 feet high and 1 to 4 wavelengths long.

Beverages are broadband, traveling-wave antennas. Power traveling toward the feedpoint is absorbed by the receiver, while that traveling in the opposite direction is absorbed by the termination resistance. Standing waves can't develop. Because waves traveling toward the feedpoint accumulate substantially in phase, while those arriving from other directions tend to cancel, the azimuth pattern of a long Beverage is highly directive. Beverages are nonresonant antennas and can be used over a wide frequency range.

A very useful Beverage variation uses two parallel wires, with one grounded at the far end. Waves traveling toward the far end reflect and return to the feedpoint differentially as transmission-line currents. With suitable termination and switching circuitry at the feedpoint, you can receive signals from either direction. A two-wire Beverage thus can replace two single-wire antennas.

For simplicity, I'll consider just single-wire Beverages here.

Eliminating Ground Connections

Beverages normally connect to ground at the feedpoint and far end. See Figure 1A. However, obtaining a good, reliable ground can be difficult. A short ground rod may exhibit thousands of ohms resistance to ground when installed in dry soil or when corroded. Since Beverages require a termination resistance of just several hundred ohms, a poor far-end ground can grossly misterminate an antenna and destroy its pattern. A poor feedpoint ground can reduce signal levels and encourage coax-shield pickup. You can use multiple ground rods, a ground screen, or a ground-radial system to lower ground resistance, but this greatly increases the work required to install a Beverage.

A ground connection isn't essential for Beverage operation. You can place the termination resistance about one-quarter wavelength from the far end of the wire. Since the impedance of a quarter-wave wire is low and resistive, the remainder of the wire just sees the termination resistor in series with a low resistance. Similarly, you can feed a Beverage about one-quarter wavelength from the near end. Both ends of the wire are left unconnected. See Figure 1B.

Ungrounded Beverages are simple to install and have stable properties. Their radiation patterns often are superior to those of their grounded counterparts because they don't suffer unwanted response from vertical wires. (This response can be reduced by lowering wire height. One way to do this is to slant the feed and termination wires over a long distance.)

The only real disadvantage of ungrounded Beverages is that they're frequency-dependent. For example, the low-impedance, quarter-wave wire sections become high-impedance, half-wave sections at twice the design frequency. I'll show you how to multiband an ungrounded Beverage later.

Antenna Modeling

While you can use a *MININEC*-based antenna- analysis program to model Beverage antennas, you'll have to settle for approximate results at best. The *MININEC* algorithm uses perfect-conductivity ground during current calculations. It takes lossy ground into account only later when calculating radiation patterns. Because Beverages are so close to ground, their current distribution is strongly affected by ground characteristics. *NEC*'s Sommerfeld-Norton ground model takes ground dielectric constant and conductivity into account when calculating wire currents. This lets you accurately analyze antennas in close proximity to earth. I used the *NEC/Wires 1.0* program to obtain all results presented here. I modeled antennas over average-quality earth (dielectric constant= 13, conductivity = 5 mS/m).

Wire Height

Figures 2A and 2B shows the azimuth and elevation patterns for a 1000-foot long, 10-foot high, ungrounded Beverage on 160 meters. The antenna uses # 18 wire and a 650-Ω termination resistance. It's fed and terminated 120 feet from each end. The remarkable pattern is better than that of many HF Yagis.



Figure 1—Single-wire Beverage antenna feeding and termination configurations. At A, conventional method is shown using slanted-wire terminations. At B, ungrounded Beverage is shown with matching transformer and terminating resistor inserted λ/4 in from either end of wire. At C, ungrounded Beverage using full span of wire by employing perpendicular "tails" at both ends. The tails function as elevated counterpoise radials at 160 meters.



Figure 2—Azimuth and elevation patterns at 1.83 MHz for 1000-foot long ungrounded Beverage mounted 10 feet off flat ground with average conductivity and dielectric constant. The worst-case rearward lobes are better than 18 dB down compared to peak response. Note that the gain is only –9.52 dBi at 10° elevation, peaking at –6.22 dBi at about 30° elevation. If the transmission line to the receiver is very long, a preamplifier may be needed.

Figure 3 shows the azimuth pattern of a similar Beverage 1 foot above ground. The termination resistance for this antenna is 750 Ω and it's fed and terminated 125 feet from the wire ends. The pattern is even sharper than that of Figure 2. Output is about 1 dB lower.

If you're tempted as I was to just lay a Beverage on the ground, take a close look at Figure 4. This is the Beverage of Figure 3 but just 1 inch off ground (*NEC* provides accurate results for wire heights down to within several wire radii of ground). While still useful, the pattern has degraded considerably. Signal output is quite a bit lower. (Nevertheless, some users report excellent results from on-the-ground Beverages. Don't hesitate to try one if it's your only option.)

In the West you can just lay an ungrounded Beverage in the chaparral a few feet off ground. In the East you can unroll one on top of a foot or two of snow (snow has very low dielectric constant and conductivity and should be transparent to RF at low frequencies). Beverages like these are very easy to install (no support poles or ground rods). You can roll one out just before a contest.

Occasionally a Beverage may have to clear a height-sensitive area. Figure 5 shows what can happen when wire height varies. The first 200 feet of this antenna is 3 feet high (chaparral height). Next, a 50-foot section slopes from 3 to 15 feet. This is followed by a 200-foot span 15 feet high, a 50-foot downslope, and finally the remainder of the wire at 3 feet. This model is similar to a Beverage used by K6TQ which must clear an agricultural area with produce trucks. While the rear part of the pattern is relatively unaffected, the height variation causes a large sidelobe bulge. It doesn't matter much if your Beverage is



Figure 3—Azimuth response for 10° elevation angle at 1.83 MHz for 1000-foot long ungrounded Beverage mounted only 1 foot off flat ground. Compared to the higher antenna in Figure 2, this low Beverage has about 1 dB less gain, but the worst-case backlobes are suppressed even better.



Figure 4—Azimuth response for same antenna as in Figure 3, except that the height is now only 1 inch off ground. The rearward pattern suffers and the gain fails about 5.4 dB compared to the Beverages in Figures 2 and 3.

high or low, but try to keep the height as constant as possible.

Wire Length

Figure 6 shows the azimuth pattern of a 2000-foot ungrounded Beverage. The termination resistance is 550 Ω. The pattern of a very long Beverage like this may be too narrow for complete coverage of a general direction.

Figure 7 shows the pattern of a 500-foot ungrounded Beverage. The termination resistance is 1100 Ω. While much broader than the patterns of longer antennas, it's still quite directive and can provide a substantial receive improvement.

Feeding Ungrounded Beverages

Conventional Beverages usually are fed with an autotransformer having a 3:1 turns ratio. This matches a 450-Ω impedance to 50 Ω. Ungrounded Beverages typically have an input resistance of 500 to 1000 Ω (roughly equal to the termination resistance) and an input reactance of up to 100 Ω. An exact impedance match isn't important; a better match just delivers a higher signal. Although usually not required to improve signal-to-noise ratio, a receive preamplifier can equalize Beverage and transmit-antenna signals for easier direct comparisons.

Both grounded and ungrounded Beverages can be sensitive to unwanted coupling at the feedpoint. If you connect coax through an autotransformer to a Beverage, the outside of the coax shield can become part of the antenna system if it exhibits an impedance similar to or less than whatever connects to it. It's the same thing that can happen with a coax-fed dipole. To prevent this, use a matching transformer with separate primary and secondary windings and



Figure 5—Azimuth response at 1.83 MHz for 1000-foot long, variable height ungrounded Beverage. The sidelobes at 90° and 270° are larger than the antenna in Figure 2, but the pattern and gain are still quite acceptable.

low interwinding capacitance. This will isolate the outside of the coax shield from the antenna. Alternatively, you can use an autotransformer followed by a current-type balun. (Because the feed tail of an ungrounded Beverage is likely to provide a lower-impedance termination than a typical ground rod, these Beverages should be less sensitive to coax-shield pickup.)

Terminating Ungrounded Beverages

Optimal termination resistance depends on wire length, height, diameter, and ground constants. The termination resistance normally just affects the rear part of the pattern. It's easy to find the optimal value by modeling the exact geometry of your antenna with *NEC*. If you use long spans of wire with considerable sag, model the sag using multiple wires.

You can determine optimal termination resistance experimentally using a signal source to the rear of the antenna. Simply adjust the termination resistance for minimum signal.

(Actually, minimum response directly to the rear isn't quite optimal for most designs. This condition usually causes the pattern to degrade slightly over a broad region elsewhere. Nevertheless, adjusting for minimum response is close enough for all but the most fanatical Beverage enthusiast.)

Multibanding Ungrounded Beverages

If you provide a termination resistance one-quarter wavelength from the far end for each band of interest, you can use a Beverage on several bands. At the near end use a separate quarter-wave tail for each band and connect them in parallel at the feedpoint.

Figure 8 and Figure 9 show 160-meter and 80-meter patterns of a 1000-foot-long, 10-foot-high, dualband Beverage. This antenna uses a 700-Ω resistor 63 feet from the far end and a 350-Ω resistor 125 feet out. The two termination resistances provide near-optimum performance on 160. The backlobe of the 80-meter pattern is suboptimal but the sidelobes are still well down. I didn't experiment much with termination-resistance values or positions. I'll bet both can be improved.

Another alternative is to use a single termination resistance with multiple quarter-wave tails. The resistor value will be optimal on just one band since antenna length isn't constant in wavelengths. But the value won't be far off on any band if the



Figure 6—Azimuth response at 1.83 MHz for 2000-foot long ungrounded Beverage mounted 10 feet over flat ground. The gain is almost 5 dB higher than that of Figure 2, and the backlobes are all suppressed in excess of 23 dB. This is a great 160-meter receiving antenna, but must be oriented carefully at desired receiving bearing because of narrow frontal lobe.



Figure 7—Azimuth response at 1.83 MHz for 500-foot long ungrounded Beverage mounted 10 feet over average ground. The gain is almost 7 dB less than Figure 2 at 10° elevation. The side lobes are large, even though the rear lobes are well suppressed.

wire is long. For best performance on all bands, use a separate resistor for each tail.

Perpendicular Tails

The ungrounded Beverages described so far really don't make optimal use of the entire antenna length. Although they contribute power, the near- and far-end quarter-wave tails don't support traveling waves. If space permits you can feed and terminate against a pair of quarterwave wires perpendicular to each end. See Figure 1C. This effectively lengthens the Beverage by one-half wavelength. Essentially the perpendicular tails form two, two-wire, elevated radial systems.

Figures 10A and 10B shows the azimuth and elevation patterns for a 1000-foot-long, 10-foot-high Beverage with perpendicular tails, with the patterns from Figure 2 overlaid for comparison. This antenna uses a 500-Ω termination. The pattern is somewhat narrower than that of Figure 2 and the backlobes are even smaller. The elevation plot shows that overhead response is about 10 dB less with perpendicular tails and that the forward lobe cants at a lower angle.

Since the quarter-wave tails of a 500-foot Beverage comprise half its length, you might expect a more dramatic improvement for perpendicular tails on this antenna. Figure 11 shows the pattern of a 500-foot-long, 10-foot-high Beverage with perpendicular tails. This antenna also uses a 500-Ω termination. Side response is down quite a bit from Figure 7 and forward response is 2 dB greater.

While they provide better performance, designs with perpendicular tails are more complex and occupy additional space. You can make better use of the additional space by phasing two Beverages with in-line tails to obtain a much better azimuth pattern . . . but that's another story.



Figure 8—Dualband Beverage on 1.83 MHz, using a 700-Ω resistor 63 feet from the far end, and a 350-Ω resistor 125 feet out.



Figure 9—Dualband Beverage on 3.5 MHz, using same terminations as in Figure 7. The termination is not optimal for this band, but still yields desirable directivity.



Figure 10—Ungrounded Beverage, 1000 feet long with two λ/4 perpen-dicular termination "tails." Pattern from ungrounded Beverage in Figure 2 is overlaid for comparison. At A, the azimuthal patterns at 10° elevation are shown; at B, the elevation patterns are shown.



Figure 11—Azimuthal pattern for ungrounded Beverage, 500 feet long with two λ/4 perpendicular termination tails.

By Brian Beezley, K6STI

From *QST*, September 1995

A Receiving Antenna that Rejects Local Noise

Simplicity and performance combine to give birth to a compact antenna you'll want to have!

Noise can make a ham's life miserable on any amateur band. As we approach the minimum of the sunspot cycle, many hams are discovering that noise can be particularly frustrating on the low bands. In summer, static crashes caused by thunderstorm lightning can totally mask weak signals on the 160, 80, and 40-meter bands. During other seasons, power-line noise, noise from household appliances, and incidental radiation from home electronic products often limits reception.

A recent *QST* article by Floyd Koontz, WA2WVL,[1] describes a small receiving antenna for the low bands that provides a cardioid directional pattern. This pattern can reduce noise and QRM from the rear. As I marveled at the elegance and simplicity of Floyd's design, I realized that the antenna did have one shortcoming: Because it is vertically polarized, the antenna responds strongly to local noise propagated by ground waves. I wondered whether it was possible to devise a receiving antenna to better reject local noise.

The Ground Wave

Most hams who operate HF are familiar with the sky wave (or space wave) that's responsible for long-distance ionospheric propagation. See Figure 1A. The space wave has two components: The *direct wave* propagates along a straight line from the transmit antenna toward the ionosphere. The *ground-reflected wave* bounces off the earth's surface and heads in the same direction.

The space wave also exists for local propagation, as shown in Figure 1B. The direct wave travels in a straight line between the transmit and receive antennas, while the ground-reflected wave takes a midpoint bounce. But when the antennas are close to ground, the direct and reflected waves nearly cancel, leaving a very small residual space wave. When the antennas are right at the earth's surface, the waves cancel completely. So what makes local communication possible? Answer: A third wave, called the *surface wave*, that exists for antennas close to ground. This wave diminishes in intensity as you increase antenna height. The surface wave exists *only near the surface of the earth*. The combination of the direct wave, the ground-reflected wave, and the surface wave is called the *ground wave*.[2]

Surface-wave intensity varies with frequency and ground conductivity. It's stronger at low frequencies and for highly conductive ground. But the most important property of the surface wave is its polarization sensitivity. The surface wave is much weaker for horizontal fields. For example, on 80 meters the broadside ground-wave response of a short piece of wire is about 34 dB lower when oriented horizontally. The difference is about 42 dB at 160 meters.[3]



Figure 1—At A, the direct and ground-reflected components of the space wave for ionospheric propagation. At B, the space-wave components for local propagation.

The surface wave makes local AM radio broadcasting possible. Because of the poor propagation of horizontally polarized ground-wave signals, AM broadcasters universally use vertical polarization. The same phenomenon causes vertical antennas to pick up much more local noise than horizontal antennas do. Even if a noise source has a stronger horizontal component, by the time the field reaches the receive antenna, the vertical component almost always dominates.

These facts suggest that the first requirement of a receiving antenna with low response to local noise is insensitivity to vertically polarized radiation, the dominant component of the ground wave. Surprisingly, simply avoiding the use of vertical wires isn't enough. An antenna composed only of horizontal wires can still respond to vertical fields.

A Low Dipole

Figure 2 shows the ground-wave response of an 80-meter dipole 10 feet high. An easy-to-install, inconspicuous dipole like this is sometimes used for receiving when the transmit antenna is vertically polarized. The pattern shows the electric field strength 10 meters above ground at a distance of 1000 meters for an input power of 1 kW (the dipole exhibits the same pattern on receive). This geometry might be representative of that for a noisy power pole. Although the pattern may look similar to that of a free-space dipole, I think



Figure 2—Azimuthal plot of the ground-wave response of a 10-foot-high 80-meter dipole. The input power to the antenna is 1 kW. The peak electric field is shown.



Figure 3—Azimuthal plot of the ground-wave response of two parallel dipoles 10 feet apart, 10 feet high and fed out of phase. The input power to the antenna is 1 kW. The peak electric field is shown.

you'll be surprised to know that the wire is oriented broadside to the pattern null. A low dipole actually responds to ground-wave fields best off its ends!

Here's an explanation for this peculiar behavior: The dipole has no response to the vertical component of a broadside ground wave because the electric field is perpendicular to the wire. The antenna responds only to the weak horizontal component. The vertical component also is perpendicular to the mirror image of the antenna formed by the ground-reflected wave. But away from broadside, the dipole, its image, or both, have a nonvanishing projection in the vertical plane. This enables the dipole to respond to the vertical component of a ground wave. In addition, lossy earth causes the surface wave to develop a radial component in the direction of propagation. Away from broadside, the radial component also projects onto the wire and induces current. The vertical and radial components induce maximum current when the surface wave arrives in line with the wire.

When compared to a quarter-wave vertical with four radials elevated 10 feet above ground, the low dipole has a 12.5 dB lower ground-wave response in its most sensitive direction in line with the wire. For sky-wave signals arriving at 20° elevation from their weakest direction (also off the ends), the dipole has 10 dB lower response than the vertical. Therefore, the low dipole has a signal-to-noise ratio advantage of 2.5 dB for signals and noise arriving from their worst-possible directions. In the most favorable directions broadside to the wire, the S/N advantage peaks sharply at 26.1 dB.

Raising the dipole broadens the broadside S/N peak and improves S/N off the ends. For example, for signals arriving at 20° elevation, a dipole at 50 feet has an S/N advantage over the reference vertical of 6.3 dB in line with the wire and 25.6 dB broadside. If you have just a single noise source and you can rotate a high dipole, you should be able to come within a few decibels of the latter figure most of the time. But when multiple noise sources in different directions arise (typical for power-line noise in times of low humidity), rotating the antenna won't help much. The S/N advantage of the high dipole then is likely to be near the worst-case figure.

These numbers illustrate the advantage of horizontal receiving antennas and substantiate the notion long held by amateurs that "verticals are noisy." But you can reduce ground-wave noise much more effectively if you don't rely on a simple horizontal wire.

Canceling Ground-Wave Components

Although a horizontal wire responds only weakly to a broadside ground wave, its response is substantial off the ends. If you could somehow eliminate the end response, you'd be left with the low broadside response and whatever residual response developed at intermediate angles.

Figure 3 shows the ground-wave response of two parallel dipoles 10 feet apart and 10 feet high fed out of phase. The phasing cancels everything arriving off the ends of the wires. The end nulls combine with the low broadside response to create a residual cloverleaf ground-wave pattern. The peak of the cloverleaf is 9.3 dB down from the peak end-response of a single dipole.[4] (Wire losses are ignored here to illustrate the cancellation principle.)

This antenna is just a very-close-spaced W8JK endfire array. Although it makes a good receiving antenna for the low bands, it's pretty large. And there's still considerable ground-wave pickup in the cloverleaf peaks. If the wires somehow could remain parallel for all directions, it might be possible to achieve complete cancellation of the vertical and radial components of the ground wave.

In some sense, the sides of a circular loop are parallel everywhere. Current amplitude and phase vary little in small loops of regular shape. Therefore, the currents in opposite sides of such loops are nearly equal and out of phase. Unlike a W8JK array, a small horizontal loop does not have a null anywhere along the ground. But its ground-wave response is uniformly low in all directions because the antenna responds only to the weak horizontal component. Everything else cancels out (or nearly so).

A small loop usually is defined as one with a total conductor length of less than 0.1 λ. But unless you use large-diameter conductors to minimize RF resistance, loops this small are inefficient. A preamplifier may be needed to overcome receiver noise. You can increase the output of a loop by increasing its size, but the larger you make it, the less constant the current becomes. This reduces groundwave cancellation.

The antenna of Figure 4 overcomes this difficulty by using two feedpoints, each on opposite sides of the loop to force current balance. One of the phasing lines is twisted to maintain proper phase.[5] This loop can be made quite large and still exhibit very low response to ground-wave noise.



Figure 4—Basic diagram of the 80-meter low-noise loop antenna showing detail of the feedpoint arrangement. The antenna measures 25 feet on a side, is 10 feet high, and made of #14 wire. It's fed at opposite corners with phasing lines made of #14 wire spaced 1.5 inches. A small ferrite transformer at the junction of the phasing lines matches the antenna to 50 Ω coaxial feed line and also functions as a balun. The trimmer capacitor (a capacitance of about 40 pF is required) in series with the antenna-side winding resonates the loop at 3.5 MHz.

A Practical Design

The 80-meter loop of Figure 4 has a perimeter of 0.36 λ. It's 25 feet on a side, 10 feet high, and made of #14 wire. It's fed at opposite corners with phasing lines made of #14 wire spaced 1.5 inches. A small ferrite transformer at the junction of the phasing lines matches the antenna to 50 Ω and also functions as a balun. A trimmer capacitor (about 40 pF is needed) in series with the antenna-side winding resonates the loop at 3.5 MHz.

The ground-wave response of this particular loop is shown in Figure 5 and its sky-wave response in Figure 6. For signals arriving at 20°elevation, the worst-case sky-wave response is 20.5 dB below that of the reference vertical. This signal level is quite usable on 80 meters without a preamp. Because the loop reduces ground wave noise at least 45.1dB, S/N improvement is 24.6 dB for the worst-case combination of signal and noise directions. if you use a preamp and adjust for equal signal levels, ground-wave noise will be four S units lower on the loop *no matter what direction it comes from!* For signals arriving at higher angles, S/N enhancement approaches 30 dB.

Both the ground-wave noise pattern and sky-wave signal pattern are very uniform in azimuth. The antenna is essentially omnidirectional with an overhead null, just like a vertical. An overhead null is useful for reducing near-vertical-incidence skywave signals from nearby stations. (The loop rejects their ground-wave signals along with local noise.)

Although the S/N performance of this loop is not particularly sensitive to height, you can increase output level substantially by raising the antenna well above ground. For example, if you raise the loop to 50 feet, the output increases 15.2 dB for signals arriving at 20° elevation. At this height, the output level is only 5.3 dB below that of the reference vertical. You'll never need a preamp with a loop this high. The S/N advantage drops 0.1 dB. At a height of 20 feet, output increases 7.2 dB and S/N drops 0.6 dB.

You can shrink the loop to 10 feet on a side. The S/N advantage increases 0.5 dB, but the signal level drops 6.5 dB. You can raise the signal level 3.4 dB by doubling the loop side lengths to 50 feet, but the S/N advantage then drops 7.9 dB. You can thus trade-off loop size, S/N enhancement, and signal level. If you use smaller wire, output drops. For example, it's 1.7 dB lower for #22 wire.

Although this loop is a narrowband device and must be carefully resonated, the resonance is much broader than that of a typical small loop. You can get away with a single capacitor setting for both 3.5 and 3.8 MHz if you're willing to accept somewhat lower signal levels. The capacitor setting does not affect the patterns or skywave-to-ground-wave ratio—it simply alters output level.

The input resistance at the junction of the phasing lines varies over a wide range with loop size, height, and phasing-line characteristic impedance. The input resistance is about 40 Ω for the loop of Figure 4 at a height of 10 feet. A transformer using a type-77 ferrite core (such as an FT-82-77, FT-114-77 or FB-77-1024) with 9 turns of any size enameled wire on the coax side and 8 wire turns on the antenna side provides a good match to 50-Ω coax.[6] The input resistance drops to about 20 Ω when the loop is raised to 20 feet and to about 15 Ω at 50 feet. Use 13 turns of wire on the coax side for 20 feet and 15 for 50 feet.



Figure 5—Azimuthal plot of the ground-wave component of a 25-foot-square, 80-meter loop at a height of 10 feet. The input power to the antenna is 1 kW. The peak electric field is shown.



Figure 6—The sky-wave responses of the 10-foot-high, 25-foot-square, 80-meter loop. At A, the azimuthal plot; at B, the elevation plot.

Although the optimum transformer turns ratio varies with antenna height, little output is sacrificed if you use a fixed ratio.

For example, output is only 1 dB less than optimal when a loop designed for 10 feet is used at 50 feet. If you're determined to obtain the best possible match, use 16 turns of wire on the coax side and tap the winding for lowest SWR (alternatively, a switch can be used to select any of two or more taps). Use the lowest possible power when measuring SWR. It's easy to puncture the dielectric of a small trimmer capacitor with a momentary blast.

The antenna's resonant frequency shifts when the phasing lines get wet. If you use true open-wire line with plastic spacers, the frequency shift will be less than 100 kHz. But if you use 450-Ω line with segmented polyethylene dielectric, the resonant frequency decreases more than 200 kHz when the line becomes thoroughly damp. Although this won't affect signal-to-noise ratio, output drops in the desired frequency range. You may be tempted to try phasing lines of 300-Ω twinlead routed inside PVC tubing to avoid moisture effects, but line impedances this low work only for smaller loops.

This antenna should be constructed as symmetrically as possible to maximize cancellation of the vertical and radial components of the ground wave. Make the loop perfectly square and accurately align it in the horizontal plane. Cut the phasing lines to the same length. Although these loops perform well near houses, fences, and towers, try to install the antenna as far from other conductors as possible to maximize current balance. Use the shortest possible leads to interconnect the matching components. Although it's probably unnecessary, I like to split the antenna-side transformer winding and put the tuning capacitor in the center to promote equal currents in the phasing-line conductors.

To minimize the number of supports, a loop about 17 feet on a side can be constructed using a 20-meter quad spreader. You can mount the spreader well up on a tower to increase output. Alternatively, you may be able to eliminate supports altogether by stringing a loop in your attic or garage. However, the current balance of indoor loops may be degraded by electrical wiring, plumbing, heating ducts, or other nearby conductors.

On-the-Air Performance

Ed Andress, W6KUT, located in the San Diego suburb of Poway, constructed a loop 21 feet on a side and 10 feet high. Ed's location is subjected to strong, chronic power-line noise. On 80 meters, Ed uses a pair of phased quarter-wave verticals for transmitting. We used the verticals as a reference when evaluating the loop. A 20-dB preamp was available. With the preamp, signals near loop resonance were about equal to those from the verticals.

The loop performed as expected. It

dramatically enhanced the signal-to-noise ratio of most sky-wave signals. Sometimes the verticals did better during a momentary change in propagation; occasionally a particular noise arose that the loop didn't attenuate much. But overall, the loop was far superior. It made little difference on strong signals. It made listening to moderately strong signals much more pleasant. It let us copy weak signals that were buried in the noise and unreadable on the verticals.

During times of no detectable powerline noise, we often noticed a curious effect: The loop still enhanced signal-to-noise ratio by one or two S units, making copy of moderately weak signals more pleasant. On these occasions, we were unable to hear the telltale, raspy buzz of power-line noise (or any other noise signature) when we listened with the transceiver's AM detector. Unless noise happens to arrive at low angles and signals at high, there's no reason for the loop to enhance skywave S/N. We believe that the unidentified noise is local and propagates by the ground wave. We speculate that it may be the sum of hundreds of weak man-made noise sources in the densely populated suburb. (The superposition of a large number of noise sources tends to be characterless even when the individual sources aren't.)

Total Ground-Wave Cancellation

If you stack two of these loops vertically and bring both feed lines into the shack, you can form a deep null on the horizon for all azimuth angles by combining the signals with a fixed amplitude and phase offset. Except for azimuth-response irregularities caused by nearby conductors and small elevation-angle differences due to range, this system will cancel all ground-wave components. This noise canceler was to have been the original subject of this article. However, a single component loop worked so well in practice that I decided total ground-wave cancellation was overkill.

Comparison with Other Antennas

A conventional, single-feedpoint, small loop about two feet on a side—oriented horizontally—yields roughly the same S/N enhancement as the loop of Figure 4. However, output will be down about 46 dB from the reference vertical. You'll need a low-noise preamp with a loop this small unless your receiver has a very low noise figure. Still, even with a preamp, a conventional small loop makes an attractive, low-profile alternative. You must construct a low-output antenna like this carefully to avoid stray pickup. A single capacitor setting won't provide good output levels on both phone and CW.

The WA2WVL cardioid antenna attenuates thunderstorm static and ground-wave noise to the rear. If you're seldom troubled by omnidirectional local noise, it should make a more effective receiving antenna than the loop described in this article. The cardioid also requires fewer supports and less space. As a bonus, it's inherently broadband.

If you have room for a two-wavelength Beverage, it will outperform the WA2WVL cardioid on sky-wave noise and should reduce ground-wave noise arriving more than 45° off boresight by at least 15 dB. If local noise near boresight isn't a problem, a long Beverage can tremendously improve your receiving capability.

The easiest way to improve reception on 80 or 160 meters is to use the most sensitive horizontal antenna available at your antenna switch. Many hams with 80-meter verticals find that switching to a 40-meter dipole or beam improves copy of weak signals even though the antenna is nowhere near resonant on 80 meters. When just a single noise source is active, you should be able to null it by broadsiding a 40-meter rotary.

Scaling the Antenna to Other Frequencies

While I've used the 80-meter band for illustration in this article, it's easy to scale the design to other frequencies. Simply multiply lengths, heights, transformer turns and capacitor values by the number you get when you divide 3.5 by the target frequency in MHz.

That said, I don't recommend this antenna for use above 40 meters. If you're using a vertical antenna on the upper HF bands, do yourself a favor and replace it with the highest horizontally polarized antenna you can manage. Not only will your receive noise decrease, your transmit signal almost certainly will improve due to higher ground-reflection gain.[7] (Exception: If your vertical radiates over saltwater, keep it!) If you're already using a horizontal wire on upper HF, I think your next antenna project should be a rotary beam rather than a receiving loop.

Notes

[1] Floyd Koontz, WA2WVL, "Is this Ewe for You?" *QST*, Feb 1995, pp 31-33.

[2] Frederick Terman, *Radio Engineers' Handbook*, 1st ed (New York: McGraw-Hill, 1943), pp 674-709.

[3] *MININEC*-based antenna-analysis programs do not compute the surface wave, nor can they accurately model antennas close to ground. I used *NEC/Wires 2.0* with its surface-wave and Sommerfeld-Norton ground options for all antenna models in this article. All models assumed average ground characteristics (dielectric constant 13, conductivity 5 mS/m).

[4] A small cloverleaf peak requires very close wire spacing. For example, the peak is down only 5.4 dB for a spacing of 50 feet.

[5] The feed arrangement is like that of an Alford Loop. In fact, the low-noise receiving antenna really is just a variant of the VHF/UHF loop devised by Andrew Alford for a different purpose in 1940. See Terman, pp 814-815.

[6] Don't be tempted to eliminate the transformer and connect 50-Ω coax directly to a loop. The transformer functions as a current balun. It keeps noise current induced on the coax shield from entering the receiver. Just a little pickup by the shield can pollute the low-noise output of a loop.

[7] For example, on 20 meters, a horizontal dipole only 35 feet high has 3 to 6 dB broadside gain over a vertical dipole at low angles over average ground.

By Gary Breed, K9AY **From *QST*, September 1997**

The K9AY Terminated Loop—A Compact, Directional Receiving Antenna

Wish you had enough room for an effective low-band receiving antenna? You do! This four-direction system fits in a 30-foot circle!

Low-band operators are always looking for ways to improve their hearing. As a low-band fan, I was impressed with the EWE antenna developed by Floyd Koontz, WA2WVL.[1,2] Koontz shows us how to build a compact, directional antenna—a design that quickly became very popular. But when I sat down at the computer to figure out the best way to install my own EWEs, a surprising new design emerged from my modeling experiments.

Ladies and Gentlemen...

Allow me to introduce you to the *terminated loop*, a concept that further shrinks the space required for a good receiving antenna *without sacrificing performance*! Figure 1 compares the real estate requirements of my four-direction loop system to that of an equivalent EWE array. The new system is not only smaller, it's easier to install, needing only one support instead of five.

The terminated loop (see Figure 2) is physically and electrically quite simple. It consists of a wire loop of any convenient shape (diamond, delta, etc), hung from a single support and with a ground rod at the bottom. A 9:1 impedance-matching transformer connects from one end of the loop to ground; a terminating resistor connects the other end of the loop to ground. This antenna is directional, favoring signals arriving from the feed point end, rejecting by several S units any signals arriving from the end connected to the terminating resistor, R_{TERM}.

Here's the real news: A very small terminated loop maintains its directional pattern. As the loop's size gets smaller, however, the desired signal strength is also reduced. The antenna described here is small enough to fit into a corner of almost *any* backyard. The loop could be made smaller, but I wanted to collect enough signal energy so that



Figure 1—A comparison of the real estate needed for four EWEs and the K9AY Loop system shows that the loops need only 1/7 the area of the EWEs, yet they provide the same directional patterns.



Figure 2—The basic design of a single loop in an easy-to-construct quasi-delta loop configuration. Exchanging the feed point and termination reverses the pattern. A four-direction system uses two of these loops installed at right angles to one another (as shown in Figure 1) and a relay controlled switching system.



Figure 3—Construction details of a terminated loop, showing the base connections and corner supports of one of the loops. The relay box also houses the 9:1 matching transformer.



Figure 4—A photo of the central connection point at the base of a two-loop system, as installed at K9AY.



Figure 5—Schematic of the relay box located at the base of the system. The relays switch between the two loops, reversing the feed point and termination connections.

even a modest preamp (such as those included in most HF rigs) can be used. More information on the antenna's operation can be found in the sidebars "How Does the Terminated Loop Work?" and "Summary of Characteristics."

To cover all directions, two loops using the same support are oriented at right angles to each other. Each loop provides reception from two directions when the feed point and termination are reversed, for a total of four separate patterns. Here are all the details you need to build the K9AY Loop antenna system, including a relay-controlled pattern-switching system that uses the coaxial feed line to carry the switching system control voltage.

How Does the Terminated Loop Work?

The terminated loop was developed after examining the behavior of the EWE. In theory, the EWE is a *terminated half-loop*. High-frequency directional couplers such as those used in the well-known Bird Thruline wattmeters are constructed similarly, just much smaller.* My analysis determined that a *terminated full loop,* fed and terminated to a single ground point at bottom center, behaves the same way as a half loop.

How does a single loop achieve a directional pattern? By the way it responds to the electric (E) and magnetic (H) field components of the arriving electromagnetic wave. Let's say we have a signal arriving at the loop from one end. As the wave passes, the loop's wire intercepts the E-field like a short vertical antenna, creating a *voltage* at the feed point. As expected from a vertical, the E-field response is omnidirectional.

The magnetic field works differently. The H field is at right angles to the E field and induces a *current* as it passes through the loop. The voltage developed across the terminating resistor by that current is combined with the E-field voltage. If the wave arrives from the feed point end, the voltages add in phase. If the wave arrives from the opposite direction, the voltage is 180° out of phase with (and subtracted from) the E-field voltage. To maximize the front-to-back ratio, the terminating resistor must have a value that balances the voltages created by the two field components so that their sum is close to zero.

The resulting pattern is a cardioid with a single null. With an optimum terminating resistor, the null can reach 40 dB or more in depth—that's more than six S units! The null is not at ground level, but at 20 to 55° elevation, depending on the shape of the loop and local ground conditions. Unless you build a short, wide loop or a tall, skinny loop, the null will be at 30 to 40° elevation, very convenient for reducing QRM from in-country stations.

Ground is an essential part of the antenna—its resistance is part of the circuit. If ground conductivity is known at your location, it can be included in the computer modeling parameters. However, ground conditions can change over a short distance and vary with seasonal changes and moisture content. If you find that the antenna does not perform as modeled, adjustment of the terminating resistor value may be needed, as noted in the article.

Ground does not need to be lossy, as is the case with a Beverage antenna. The loop has directivity even with perfect ground. This means that you can install it over *any* type of ground, including a buried radial system (as long as it's not too close to another structure).—*Gary Breed, K9AY*

**Instruction Book*, Model 43 Wattmeter, Bird Electronic Corp, Solon, OH.

Let's Build It!

First, gather the following materials to construct the loops:

- Two lengths of **wire** about 85 feet each. Although almost any wire size will do, #14 copper is probably the best for a long-lasting installation.
- Ten simple **insulators**—anything from old toothbrush handles to fancy porcelain insulators will do.
- A three or four-foot length of **copper pipe**—the ground rod doesn't need to be driven deeply—a depth of three to four feet is sufficient. Because copper-plated steel rods eventually rust, I prefer to use $^1/_2$ or $^3/_4$-inch-diameter copper water pipe.
- One **support** 25 feet above ground—my antenna hangs from a limb of a Georgia Pine, but anything that gets the top of the loops up about 25 feet will work. The wooden **A** frame support described in *The ARRL Handbook* and *Antenna Book* is an excellent choice. A metal mast can be used, but make it only as long as necessary and insulate it from ground. Large metal objects affect the antenna's performance, so install it in the clear.
- You'll also need some **rope**—nothing fancy, just something strong enough to keep things in place.

Now, grab your tools and head for the backyard. Attach the midpoint of each wire length to an insulator that will be positioned at the top of the loop. The two loops must not touch each other, so leave some room between their insulators. I separated my insulators with about a foot of rope.

Aligned directly under the tops of the loops, drive a ground rod, leaving a foot or so above ground as an attachment point. Using short ropes or wires, connect four insulators a few inches away from this post to receive the lower ends of the loops. Leave a foot of wire for a pigtail after twisting the ends of the loop wires around the insulators. Figure 3 sketches the important installation details, and the photo of Figure 4 shows how my system is installed.

The lower corners of the loops are supported by insulators and ropes tied off to nearby trees, fence posts, or stakes driven into the ground. Pull out the corners with enough tension to maintain the loop shapes. At this point, the major mechanical work is finished and you should have something resembling an eggbeater, as shown in Figure 1.

The Relay Box and Controller

Figure 5 shows the relay circuit used to switch the feed and termination points of the loop wires. House the components in a weatherproof box having external connection points for the four ends of the loops, a coax connector for the feed line and a ground-wire attachment.

K1 is a DPDT relay that switches between the two loops. K2, another DPDT relay, swaps the connections of the terminating resistor and matching transformer, thereby reversing the pattern. Relay power is supplied via the coaxial feed line. C1 keeps the control voltage from reaching the antenna, and C2 provides an RF ground for the transformer.

Most builders will likely choose to orient the loops for northeast/southwest and northwest/southeast directions. The relay box has four switching modes, one for each direction: 1) northeast, when *neither* relay is energized; 2) southeast, when K1 *only* is energized; 3) southwest, when K2 *only* is energized and 4) northwest, when *both* relays are energized. Switching is accomplished using a single power connection through steering diodes D1 and D2. D1 allows K1 to operate when +12 V is applied, while D2 blocks the voltage from reaching K2. When −12 V is applied, K2 operates, but not K1. When 12 V ac is applied, the diodes rectify it to operate *both* relays.

The matching transformer is a 9:1 impedance, 3:1 turns ratio type that should be familiar to many readers. Five trifilar turns of ordinary hookup wire are wound on a $^3/_4$-inch-diameter (0.825 inch) 43 material toroid. The terminating resistor (R_{TERM}) value will be between 390 to 560 Ω, depending on your band preference. With average ground conductivity, a value of 390 Ω provides the optimum F/B at 160 meters, while 560 Ω optimizes the loops for 80 meters. A value of 470 Ω splits the difference for "pretty good" performance on both bands. I chose to optimize the antenna for 160 meter operation, so used a 390 Ω resistor. Use an R_{TERM} power rating of at least 1 W in case some transmitter power ends up being coupled to the loops. I use a 2-W carbon resistor, but two parallel $^1/_2$-W or four $^1/_4$-W units of appropriate ohmic value can also be substituted.

Figure 6 is a diagram of the control box that is located in the shack. One 12 V ac transformer provides the ac relay power and feeds two half-wave rectifiers and filter capacitors to generate ±12 V. One SP4T switch selects the proper voltage to apply to the coax. The RF choke and 0.1 µF capacitor keep the RF and control voltage separated at the shack end.

Once the control unit and relay box are built and operating properly, mount the relay box at the ground rod and connect the four ends of the loops to their proper terminals. A length of 50 Ω coax carries the signal and power between the antenna and the switch box in the shack. I highly recommend keep-



Figure 6—Schematic of the control box located in the shack. The control voltage to operate the relays is delivered via the coaxial line.

Summary of Characteristics

When choosing a specific configuration or location for your K9AY Loop system, consider this list of characteristics:

- Like all antennas, this one can be affected by nearby metallic objects or structures. Do your best to keep the antenna in the clear, away from your tower, house and power lines.
- Noise reduction in this antenna is achieved mainly by the directional pattern, although being grounded offers some reduction of wind, rain and snow static. Compared to the typical omnidirectional vertical or low inverted **V**, the reduction in overall noise and interference can be dramatic.
- The maximum circumference of the loop is a little over $^1/_4$ λ at the highest frequency of operation. If the loop is larger, the E and H-field responses of the antenna can no longer be balanced. Smaller loops (or same-size loops at lower frequencies) retain the directional pattern, which makes this an excellent antenna for AM broadcast reception. Unfortunately, the received signal voltage is proportional to the area enclosed by the loop, so sensitivity decreases rapidly as the antenna becomes smaller. Unless you have a very good preamp, keep the loop sizes near the maximum.
- The T-Loop is not just a low-frequency antenna! It can be used at high frequencies for shortwave listening, or to provide improved reception over an omnidirectional antenna such as a vertical. Just scale the size to the desired frequency using the guidelines presented in the accompanying article.—*Gary Breed, K9AY*



Figure 7—Vertical radiation pattern of the loops along the plane of the loop.



Figure 8—Horizontal radiation pattern of the loops at 30° elevation.

ing the coax on the ground (buried is better) to minimize pickup of noise or energy coupled from your transmit antenna. A receiving preamplifier is almost certainly needed, either your rig's internal preamp or an external preamp.

Evaluation and Adjustment

Next, verify that the antenna is working correctly. Some listening is probably what you'll do first, but fading makes it almost impossible to determine the antenna's actual performance. At best, you will be able to confirm that the antenna has reasonable directivity.

More accurate listening tests can be performed several ways. The best way is to enlist the aid of a nearby ham whose station is very close to being in line with one of the two loops. If such help is not available, the next-best option is to identify a local AM radio station high in the band (1400-1600 kHz) and use that as your test signal. Switch the loops to their various directions. If the test station is directly in line with one loop, you should see a front-to-back (F/B) ratio of about 2 to 3 S units as the antenna is switched toward and away from the station. You won't see a *huge* F/B because the deepest null is up at 30 to 40°.

Local ground conductivity can affect performance. You might not get an optimum pattern at your particular location with the "normal-value" terminating resistor. If you aren't getting the expected performance, substitute a 1 kΩ potentiometer for the terminating resistor and adjust it for best F/B while listening to your test station. Then, measure the pot's resistance and install a fixed-value resistor of the same value.

Antenna Performance

The vertical pattern of the antenna, in line with the loop, is shown in Figure 7. Figure 8 is the azimuth pattern at 30° elevation. Modeling was done using W7EL's *EZNEC* program,[3] which uses *NEC-2* to evaluate the antenna over "real" ground.[4] Listening tests confirm that these modeled patterns are close to the as-built antenna performance. Much of the on-air pattern evaluation was done by listening to AM broadcast stations and to WWV on 2.5 MHz, because the pattern of the antenna changes little over this frequency range. Stations at exactly the right distance and directions have verified the deep null off the back. For example, New York City area radio stations are exactly in line with my northeast/southwest loop, and show 40 dB F/B ratio when the arrival angle is just right!

The front of the pattern is quite broad, with maybe one S unit F/S. The advantage of this antenna is its rearward null, which reduces local noise and distant QRM. I installed my system just 2½ weeks before the 1996 ARRL 160 Meter Contest, so it got a thorough evaluation in a short time. During the contest, changing the pattern direction often made the difference between Q5 copy and a busted contact. For example, pointing southeast to hear Caribbean stations reduced stateside QRM by 2 or 3 S units, enough to easily hear the DX through unruly pileups.

Higher-Performance Ideas

The compact size of the K9AY Loop makes it easy to build more than one for a multielement array. Installing two of them in a broadside/endfire combination is one option, but a really ambitious approach would be to install a four-square! This array would have a substantial F/B over a wide angle, along with a much narrower front lobe than a single loop. The space required for this high-performance array is far less than what is needed for Beverages. If you try this, remember to switch the individual loops to the desired direction as you switch the feed system.

Summary

If you want improved reception on the low bands and don't have a lot of room, the terminated loop is an excellent choice. It is small, easy to build and its directional pattern makes DX much easier to hear.

Notes

[1] Floyd Koontz, WA2WVL, "Is This Ewe for You?" *QST*, Feb 1995, pp 31-33.

[2] Floyd Koontz, WA2WVL, "More EWEs for You," *QST*, Jan 1996, pp 32-34

[3] *EZNEC* 1.0 by Roy Lewallen, W7EL, PO Box 6658, Beaverton, OR 97007; tel: 503-646-2885, fax: 503-671-9046.

[4] The modeling accuracy of antennas with a direct connection to ground is somewhat uncertain, even with the power of *NEC-2*. The high accuracy ground characterization of the Sommerfield method gives answers that vary with the number of segments chosen for each wire. The *MININEC*-type ground model gives more consistent results, but on-air tests show that the deepest null is obtained with a lower value terminating resistor than this model indicates. The plots presented here are the "best fit" between modeled and observed performance.

Photos by the author.

From *QST*, May 1998 (Technical Correspondence)

Hum Problems When Switching the K9AY Loops

By Gary Breed, K9AY

I am pleased to report that many hams have successfully built the receiving antenna described in the September 1997 issue of *QST*.[1] I had some concern that variations in local ground conditions and nearby structures could reduce the antenna's performance, but the performance I obtained seems to be readily duplicated.


Loop 1
SW
NE
Loop 2
NW
SE
Phasing
R TERM
9:1 Transformer
to Rig
K1
0.1 µF
K2
0.1 µF
1
2
GND
to Control Box

Figure 1—A revision of the schematic shown in Figure 5 of the September 1997 *QST* article.

There is one problem that needs to be addressed. When the loops are switched to the northwest direction, an ac voltage is sent down the coax to the relay box. A few hams have reported hum or distortion when the antenna is switched in this direction. Two explanations are possible: a ground loop due to widely separated antenna and station grounds, or modulation of the core of the matching transformer. The presence of hum was not evident in my prototype, but to avoid either cause of the problem, I recommend using a *separate* three-conductor control wire to operate the relays. The power is solely 12 V dc, and no current flows through the transformer. The modifications are shown in the accompanying figures, which can replace Figures 5 and 6 in the original article.

Secondary benefits of this arrangement include the option of using an existing 12 V power supply to provide the operating voltage, and the ability to use an additional conductor to carry power to an antenna-mounted preamplifier.


An External 12 V DC Power Supply can be Connected Here (Negative to Ground)
F1 0.25 A
12 V 300 mA
1N4001
F2 0.5 A
SE
NE
n.c.
NW
SW
ON
120 V AC
120 V
220 µF 25 V
0.1 µF
0.1 µF
1
2
GND
to Relay box
All: 1N4001
n.c. = No Connection

Figure 2—Changes to Figure 6 of the original article.

---

[1] Gary Breed, K9AY, "The K9AY Terminated Loop—A Compact, Directional Receiving Antenna," *QST*, Sep 1997, pp 43-46.

CHAPTER NINE

MISCELLANEA

9-1 **A Skyhook for the '90s**
From May 1997 *QST*

9-4 **Balloon Skyhooks**
From August 1997 *QST* (Technical Correspondence)

9-5 **The Clothesline Antenna**
From July 1998 *QST*

9-8 **A Variable-Frequency Antenna**
From July 1949 *QST*

9-12 **Honey, I Shrunk the Antenna!**
From July 1993 *QST*

By Don Daso, K4ZA **From *QST*, May 1997**

A Skyhook for the '90s

Is your group looking to put up a BIG vertical antenna for Field Day? The crew at N4ZC started their own air corps. Their full-size 160-meter quarter-wavelength vertical is *not* supported by hot air!

PHOTO BY DON DASO, K4ZA

Inspiration, on a grand scale. What if we had one of *these* to play with?

Some History, as Introduction

By 1936, the Zeppelin company was without rival in the design, construction and operation of rigid airships. Flying successfully around the world, providing regular passenger service between Germany and South America, the *Graf Zeppelin* airship was nonetheless unsuited for the hardship of crossing the North Atlantic. The *Hindenburg* was designed and built for this route. This huge airship was one of the largest flying machines the world has ever known. Her crash and destruction at Lakehurst on May 6, 1937, ended the era of passenger transport by airship.[1]

Later, growing up on a farm near Akron, I sometimes saw the Goodyear airships passing silently overhead. Twenty-odd

PHOTO BY SCOTT DOUGLASS, K2SD



Figure 1—K4ZA fastens the antenna and tether to the miniature blimp prior to launch.



Figure 2—Select a flying area free from obstructions so your blimp can fly with the wind in any direction at an angle as low as 45° from the ground. *Do not fly* in areas where there is any chance of the tether or antenna contacting buildings, power lines or trees.

---

[1] The terms concerning lighter-than-air (LTA) craft are often misapplied. *Webster's Ninth Collegiate Dictionary* indicates that *dirigible*, *airship* and *blimp* all denote an LTA with *steering and propulsion* capabilities. Hence, the terms do not strictly apply to the kytoon, which has neither steering nor propulsion systems. Nonetheless, *blimp* is so commonly used by manufacturers, sellers and users to describe the kytoon that we continue that usage here, as well. —*Ed.*

PHOTO BY DON DASO, K4ZA



Figure 3—Here's our miniature version of the real thing—fresh out of the box and ready for inflation.

years after the *Hindenburg* disaster, I began to experiment with balloons myself—originally using surplus weather balloons to support wires, and more recently, with small blimps holding contest antennas. Many hams have considered using balloons or kites for antenna supports. Indeed, they come closer than anything else to that "skyhook" we all jokingly refer to on occasion. Yet, each one has limitations.

The Kytoon

Balloon-supported antennas tend to lose altitude in the wind, however slight. Kites cannot fly without wind. Satisfactory service from either support requires a limited range of wind and weather conditions—something that's not too common. Combining features from each—the balloon and kite—solves several of these limitations. Indeed, the Kytoon is a small, inflatable blimp-shaped balloon with kite-like surfaces that cause it to fly into the wind. An early Kytoon—with a rigid skeleton—is registered with the US Patent Office and enjoyed some success as a skyhook. (See Bibliography for further information.)

Today, the early Kytoon's bladder-and-frame construction has been replaced by completely inflatable balloons, made from 2 to 3-mil polyurethane film (see Figure 1). Brilliant skin colors are common because these miniature blimps are intended for advertising purposes. These small blimps are available from various sources, with prices varying according to size—typically from 10 to 30 feet long and starting at $300. [Beware: Many suppliers specialize in advertising Kytoons and sell them for twice the price of those sold for scientific uses.—*Ed.*]

The plastics used in their construction have been specially formulated for high elasticity, helium retention and paint application. Helium (a safe, inert gas) is available from party suppliers or welding supply companies. One tank will easily support an antenna for the typical contest weekend. If you have some room, but maybe not the resources to put up a full-sized radiator, consider a tethered Kytoon. As a modern antenna support, these miniature blimps are the skyhook of the '90s.

Tethered Flight

Most hams considering these small blimps as antenna supports concentrate on their antennas. This natural inclination can create problems. Most hams have little knowledge or experience with the basic principles of LTA flight, knots and rigging rules, with FAA regulations, with weather and especially with how these all relate to tethered flight. It's a complex process and serious business to lift an antenna aloft with a small balloon or blimp.

These blimps consist of a closed envelope of gas—usually helium—that is lighter than the atmosphere. Gas balloons can only descend by losing lift (that is, by venting gas) or when some force overcomes their lift (retrieval by tether or powered flight). As a gas balloon rises, it will reach an equilibrium altitude, where it will remain until the lift-to-weight ratio changes. These principles—which are mostly associated with larger, cargo-carrying blimps—are important, especially because our balloon will be tethered. As with any tower or antenna project, use common sense and make safety your highest priority!

Because space is three-dimensional, any "skyhook" can turn in the air—rotating in three axes: a longitudinal roll, a lateral yaw and a vertical pitch. The shape of these blimps allows them to "fly" in the wind, countering these motions, and the tether allows the blimp to move easily enough within those three axes. Generally, you will experience something like Figure 2.

A 10 to 12-foot blimp is sufficient for most antennas suitable for low-band use. Most blimp applications will be for 160 meters, because the sheer size of effective antennas for this band makes them difficult (and costly) to erect. A 10 to 12-foot-long blimp of 3 to 4 feet in diameter holds about 70 cubic feet of helium and is capable of lifting two pounds. This is sufficient for an effective $\lambda/4$ wire vertical for 160 meters.

Setup, Antenna and Ground

You'll need a working area on the ground to inflate your blimp. A 20×20-foot area should suffice. It's important to protect the thin skin of the balloon. I usually lay the balloon out on a tarp to prevent any stubs or twigs from poking the plastic skin (see Figure 3). While the plastic seems sturdy and elastic, I'm always careful and treat the balloon gently. I hold the helium tank upright, and I usually lash it securely to a two-wheeled dolly, so I can move it to the field easily. Follow the manufacturer's inflation directions carefully (each will be slightly different).

Inflation temperature is important: If possible, inflate the balloon at the same temperature it will experience in flight. Helium comes out of the tank cold. With rising temperatures, it expands quickly inside the balloon. Sunlight and warm air cause further expansion. (In very hot weather, a balloon loses some of its lifting power, but this is usually not a problem.) Do not overinflate the balloon. Finger pressure will barely dent the surface of a properly inflated polyurethane blimp. Pay special attention while closing the neck of the blimp. With many blimps, you can simply fold the neck back on itself several times and then fasten it in place with heavy rub-

PHOTO BY SCOTT DOUGLASS, K2SD



Figure 4—Vertical antennas are real-estate intensive. K4ZA and KF4HK install radials in the horse pasture at N4ZC's contest station.

PHOTO BY SCOTT DOUGLASS, K2SD

Figure 5—WA4UNZ and K4ZA work inside the large copper ground ring installing the feed system.

ber bands (folding them, if necessary) to provide a tight, leak-free fit. Refills are much easier when rubber bands, rather than knotted rope, seal the balloon.

Use a quality ball-bearing swivel between the end of the tether and the balloon's attachment line. This allows the blimp to easily turn into the wind. Fishing line works well as a tether; so do some kite lines and other synthetic ropes. I've used 100-pound fishing line and 1/8-inch nylon rope.

Stranded wire is a lightweight antenna conductor. Aluminum welding wire is light and strong enough to use. (I use phosphor-bronze wire that was originally intended for use with the "Gibson Girl" rescue unit's kite- or balloon-supported antenna. It comes on a small reel. The irony, weight and low cost appeal to me.) To save time, measure and mark the antenna length before construction begins. I have found no instances where the addition of a tether created a problem, in launch, retrieval or during flight. The antenna has never broken; and our balloon has never broken free. Obviously, it's simple insurance, and you don't want your antenna wire touching power lines or other hazards, which might happen with a runaway blimp.

The original installations at N4ZC were all within a working pasture (see Figure 4). On-ground radials were easier to install than elevated radials, albeit more labor-intensive (easier because they need no supports, labor-intensive because it requires more radials—4 versus 60). A large diameter ring of copper water pipe served as the radial connection point and made soldering easier. The ring also created a work space to stand in during set up and launch (see Figure 5). (Future installations will use a high, central wooden post, with attachment points for the antenna, tether and four elevated radials.) Our installation is over 150 feet from the nearest tower (the 20-meter array). RG-213 runs from the feed point to the base of that tower, where it connects to Hardline running to the shack.

Hints

Always wear gloves when launching and retrieving the blimp. Let the blimp rise slowly; retrieve it slowly. The lift can be terrific, and the antenna wire and tether can easily cut your hands. Always have helpers coil up the antenna and tether on spools as you walk the balloon down. (I recommend reeling in the blimp during daylight hours. It's a tempting target, and we hear gunshots in the woods all the time at N4ZC's somewhat country location. Make certain winds cannot push the blimp into nearby objects, even when it's near the ground.)

FAA regulations for flying tethered balloons—those under five pounds in weight—are clear: No person may operate a kite or balloon in a manner that creates a hazard to persons, property or other aircraft.

Avoid all dangerous situations: operation near airports, in wet or stormy weather, near electric power lines, over public streets or areas congested with people or at extreme heights (which is probably the first thing a ham will think of). Use common sense and play it safe. Using less than the legal limit with a single 1/4 vertical supported by a 10-foot blimp, I've been able to work any station heard on 160 meters.

Sources

Here are names and contact information for two suppliers of these inflatable blimps:

Toy-Tex Novelty Company, 7315 N Linder, Skokie IL 60077.

The Blimp Works, 156 Barnes Airship Dr, Statesville NC 28677.

Annotated Bibliography

There's a wide variety of applicable information and material available, but not much has appeared in Amateur Radio publications. This is new territory, in many ways, that's worthy of further experimentation. I recommend the following books and articles for further reference and study—before buying, building and flying:

R. Carleton Greene, W8PWU, "More On Balloon Supported Antennas," *QST*, Nov 1940, pp 38, 39 and 82. One of the earliest articles on using meteorological balloons as antenna supports, complete with lifting charts.

David T. Ferrier, W1LLX and William G. Baird, W9RCQ, "A New Kind of Skyhook," *QST*, Oct 1946, pp 24-25. The original use, as best I can determine, of the Kytoon as an antenna support. Although focused on emergency or Field Day use, the final line of the article presents this challenge: "Perhaps long-wire vertical antennas can now be exploited with outstanding results."

Stan Gibilisco, W1GV, "Balloons as Antenna Supports," *The ARRL Antenna Compendium*, Volume 2, (Newington: ARRL, 1989). A brief overview of the topic, with good descriptions and several safety tips.

Maxwell Eden, *Kiteworks*, (New York: Sterling Publishing Company, 1989). An excellent book about kites of all kinds—including building and flying them. It's filled with tips and techniques.

Will Hayes, *The Complete Ballooning Book*, (Mountain View, California: World Publications, 1977). Although focused on large hot-air balloons, the history, basics of flight and safety chapters are well worth your time. It also includes the FAA regulations.

John Belrose, VE2CV, "A Kite-Supported 160- (or 80-) Meter Antenna," *QST*, Mar 1981, pp 40-42. A unique application of the Parafoil—a special type of kite. Interesting tips and techniques applicable to blimp-supported antennas.

"160-Contest Results," *QST*, Jun 1976, pp 71-74. Pictures and text from W8LT, the Ohio State University Amateur Radio Club, using an original Kytoon to support a vertical antenna.

From *QST*, August 1997 (Technical Correspondence)

Balloon Skyhooks

By Jack M. Hughes, WB6SOI

I appreciated and enjoyed "A Skyhook for the '90s."[1] The company I work for, TCOM, L.P., has been doing this sort of thing commercially since 1981, but on a much larger scale. Since 1972, TCOM, L.P. has been an authority on and builder of aerostats.[2] We manufacture and market an aerostat system called the Tethered Aerostat Antenna Platform (TAAP).

VLF and LF transmitters and receivers are used by the military and governments worldwide for high-reliability communication of strategic information. A typical antenna system for VLF/LF communication is a complex array of wires suspended on insulated towers that take months to erect and place into operation. A unique scheme for the rapid deployment of a complete VLF/LF (up to 100 kW) communications system uses the TAAP.

An aerostat is employed to elevate an encapsulated vertical antenna/tether to a height approaching one quarter wavelength for the frequency in use. At VLF, this technique enables the system to operate with a high antenna-radiation efficiency unobtainable by other land or sea-based antennas.

The radiated-power efficiency is further enhanced by the installation of a simple groundplane consisting of eight radial wires emanating from beneath the mooring-system trailer. The radial ends are secured by ground rods and copper wire. The entire system—antenna/tether, aerostat, mooring system, transmitter and equipment shelter—is designed to be transportable by land, air or sea and to be rapidly erected at a selected site.

The aerostat is a helium-filled, aerodynamically stable tethered balloon typically 32 meters long. Its antenna/tether is composed of Kevlar with optional fiber optics and two concentric outer sheaths of aluminum braid. The Kevlar construction provides up to five times the strength of a similar-weight steel cable. A fiber-optic core provides for secure communication between the ground and the aerostat, and the double-aluminum sheaths act as the radiating elements—as well as a path for the 400 Hz electrical power to the aerostat.

The aerostat is launched and retrieved at a rate of 200 feet per minute and it does not vent helium. In addition to the helium chamber, it uses an air-filled ballonet system that expands and contracts depending on the outside air pressure to keep the aerostat rigid at all times. It can operate in winds of up to 50 knots and will survive in winds of greater than 70 knots. The system is designed to fly continuously for up to 21 days before replenishing it with helium.

I commend author Don Daso for his creativity and resourcefulness. He seems to have just as much of a thrill as we do in handling LTA vehicles.

---

[1] Don Daso, K4ZA, "A Skyhook for the '90s," *QST*, May 1997, pp 31-33.

[2] Aerostats are essentially helium-filled, aerodynamically shaped balloons that are tethered to ground. They're not cheap—a 15-meter-long Aerostat system costs about $175,000.

By Robert Victor, VA2ERY From QST, July 1998

The Clothesline Antenna

Dry your laundry or work DX. Could this be the first dual-purpose antenna?

Every once in a while, you run across an idea that seems so simple, so obvious, you can't believe it hasn't been done before. Surely (you say to yourself), you're not the first person in the universe to have thought of this…

That's the case with the Clothesline antenna and me. While mulling over a variety of ideas for an antenna suited to my apartment, I started drawing some graphs of sine waves at various frequencies. One thing led to another and I wound up with a terrific solution for my antenna needs—and it was one that I haven't found any references to anywhere. As far as I'm concerned, *I've* invented the Clothesline. Still, I'm not going to be surprised if someone shows me that it's been done before!

But even if this antenna design has been around since hydrogen, it may still be new to you. And even if you have seen something similar to the Clothesline, this design may be worth a second look. For hams in a variety of situations, this could be just what the doctor ordered to cure your DX dilemma.

What It Is ... And Isn't

I will tell you what the Clothesline is, but first I'll tell you what it is not. The Clothesline isn't some dubious trick for loading up an actual clothesline with 12 cubits of RG-213 looped four turns to the foot around your washing machine. This is an antenna, it works all the HF bands, and it gets great results. It doesn't need a tuner because it's dead-on resonant on the 160, 80, 40, 20, 15 and 10 meter bands. A tiny tweak will bring in 12 and 17 meters, too.

It's remarkably easy to build. There are no traps, no stubs, no loading coils, no variable or fixed capacitors, no screws, no clamps, and you don't have to drill anything. This antenna is so simple to put up, it hurts. The Clothesline consists of little more than a piece of wire, a center insulator, some feed line, and a couple of $2 hardware-store fittings.

Too good to be true, you say? What's the catch, you ask?

Well, you *do* have to adjust this antenna for most band changes. But before you get too excited by the word "adjust," I'm not talking about unwrapping yards of black tape to get at a loading coil, or tweaking the bare shaft (whoops, hot side—sorry!) of a 50-year-old fleamarket variable capacitor. No, the Clothesline makes band changes a piece of cake. When you see how easy it is, you're going to chuckle!

The Concept

The easiest way to explain how the Clothesline works is to lead you through the simple reasoning I used to come up with the thing. I started with a drawing like the one in Figure 1. It shows a simple dipole for 80 meters. It's 132 feet long and fed in the middle with coax. Next I drew the graph of the voltage distribution along the antenna (at its fundamental resonant frequency). Note the voltage is at a maximum (with reference to ground) at the antenna ends. That's important for any dipole radiator. The ends of the antenna have to correspond to the high voltage points of the curve.

I already knew that the curve the voltage wave describes is a quarter of a full cycle—a quarter wavelength—on each half of the antenna. And that the distance between the two places where the voltage is highest, or in other words, from one end of the antenna to the other, is 1/4 plus 1/4—a half wavelength. That's why they call it a half-wave dipole.

I also understood why the feed point is in the middle. It's located precisely where the voltage curve is lowest with respect to ground. To me, an antenna is just like a transformer—it transforms the low impedance coming out of the coax up to the impedance needed to couple to the cosmos. Come in low, go out high. So much for the plain dipole.

BEASLEY
K6BJH

THAT LAST PAIR OF LONG JOHNS YOU REELED OUT MOVED MY FEEDPOINT



Figure 1—The voltage distribution along an 80-meter dipole antenna. Note that the voltage is at maximum (with respect to ground) at the ends of the antenna.



Figure 2—Take the 80-meter dipole shown in Figure 6 and overlay the voltage distribution for a 7-MHz signal. Note how the 7-MHz feed point (B) has shifted to the left of the 3.5-MHz feed point (A).

I then dropped a 7-MHz voltage curve over the original 3.5 MHz length (see Figure 2). Because the new frequency is a whole multiple of our original frequency (3.5 MHz × 2 = 7 MHz), there is still a whole number of half wavelengths from one end to the other, so the voltage peaks are still at the ends. This means this same length of wire will resonate at 7 MHz, which means it will radiate perfectly well at this frequency too.

But I noticed right away that something had changed from our earlier situation—the point where the voltage minimum crossed ground was no longer in the middle. There were now two such points, neither of them anywhere near the middle. So the antenna was resonant—the voltage peaks were at the ends—but my original feed point was now useless! Alright, I reasoned. If I shift the feed line to the new minimum I'll have the perfect setup—high voltage at the ends, low voltage at the feed point. Look out DX, here I come!

I thought about how far I'd moved the feed point. Looking at the curve, you can see that from (A) to (B) is a quarter wavelength at the new frequency, right? We doubled the frequency, which means we cut the old wavelength in half. So what used to be a quarter wave at the old frequency—from the middle to one end—will be twice that, or one-half wavelength, at the new frequency. And I wanted to get the feed point over to the new location at point (B), so I move it half that half—a quarter wavelength—over to the new minimum at (B).

I also realized that I'd added a quarter wave to the right half of the antenna, making the right-hand side 1/2 plus 1/4 wavelengths, or a total of 3/4 wavelengths long. Since 3/4 on the right plus 1/4 on the left equals 1, I now had a full-wavelength antenna with some gain compared to a dipole, fed one-quarter wavelength from one end.

I kept going. I doubled the frequency again, and the same thing happened. The voltage peaks would stay at the ends, but I'd see the feed point moving further to the left by one-quarter wavelength at the new frequency for each time I doubled frequency.

I tried it for other multiples—by 3, 5, 6, 7 and so on. Just as I expected, I always wound up with some whole number of half waves, and voltage peaks at the ends. All I ever had to do was to move the feed point to the new quarter-wave point of the antenna. And for that matter, for any band other than 80, I had a choice of feed points. Each higher-band antenna had more than one voltage minimum point in its length, and I could feed at any one!

Now I drew a bunch of these curves like the ones shown in Figure 2 for 80, 40, 20, 15 and 10 meters. I dropped reference lines down from each voltage minimum to show where the feed points would lie along this single piece of wire, depending on the frequency. Because there are multiple feed points for each of the higher bands, I could see that any time I want to change frequency, I would just shift to the closest feed point for the next frequency, and away we go!

But so what? How was I going to make a simple antenna with all these feed points? For that matter, what was simple about an antenna with all these feed points anyway? The answer was, "nothing." What about a *single* feed point that somehow travels or slides along the antenna to anywhere I want it to go? Could I make that happen? I was looking out the window at my 40-meter folded dipole when I came up with the answer.

Other than the fact that it's fed with 300-Ω line rather than coax, the folded dipole is almost identical to the standard dipole. It resonates over the same lengths at the same frequencies, so my marvelous (but yet to be invented) multi-band, sliding feed-point antenna would be just as comfortable with a folded dipole 132 feet long as it would be with a plain dipole. But what about the sliding feed point?


132 ft. for Base Frequency of 80 meters (3.5 MHz). 264 ft. for 160
Midpoint
Plastic Pulley
Insulator
Wire
Plastic Pulley
(A)
(B)
300 Ω Feed Line (any length)
6 : 1 Balun
Coax to Transceiver (any length)

Figure 3—The Clothesline antenna. Just set (A) or (B) to equal a quarter wavelength at your operating frequency. As long as it is a multiple of your base frequency (most HF ham bands are), your antenna is tuned. You can measure out your favorite bands, peak them by observing the SWR, and put color marks or tags on the bottom wire. Roll up to the mark and you're ready to couple to the cosmos!

What would happen with my folded dipole if I just grabbed the feed line and tried to slide it along toward one end? It hit me: If the endpoints were run over pulleys the feed point would effectively slide! It would just run along the bottom of the antenna to anywhere you cared to put it. As far as the electrical nature of the antenna is concerned, absolutely nothing has changed—except the position of the feed point! And there it was—the birth of the multi-band, sliding feed-point antenna, otherwise known as the Clothesline! See Figure 3.

But wait a minute, I thought. It's a clothesline. It can't possibly work. It's too simple!

Yet no amount of poking about on paper could find fault with it. Still very skeptical, I strung up a miniature version (for 10 and 20 meters) running down my hallway. It worked! It loaded like a breeze, with the feed about 8 feet from the end on 10 meters and about 16 feet from the end on 20 meters, just where those graphs said it should. I bought some decent wire, a couple of plastic pulleys, 75 feet of 300-Ω twin lead, and threw one up on the roof to cover 40 through 10 (66 feet is all the horizontal space I have up there). Within a couple of days I had racked up dozens of DX contacts on every band. Most remarkable was the apparent gain on the higher bands. I consistently surprised other stations (and myself) with my signal strength, usually trading equal signal reports and getting lush praise from guys running far greater power and fancier antennas. My 100 W and a Clothesline are reaching the world!

How to Build and Use the Clothesline

Measure out enough wire for twice the lowest frequency. If this happens to be 80 meters, you'll need 2 × 132 feet (plus a bit for trimming). String it up like a clothesline, using nylon or rope leaders to attach the plastic pulleys to their supports. Just make sure that all the wire is used, so that the antenna is full-length. You can use long leaders if you want to hang one end off a distant support. Run each end of the wire through the pulleys top-to-bottom, attach the two ends to a center insulator and hook up your feed line. That's it!

If you're building a version for 80 or 160 meters, you'll want to install a third little pulley to ride along the top run, attached by a short piece of cord to the center insulator, to help keep the top and bottom runs of the antenna roughly parallel. Build it for 40 as the lowest frequency and you won't even need this little extra.

There is a full set of feed points between the middle of the antenna and half-way out to either end, so if you want to keep the feed line short, you can cut it to provide just enough slack to move within this range. Alternatively, because different feed points for the same frequency can affect the gain pattern, you may want the flexibility of having a choice of feed points for each frequency, and decide to leave more line slack. Losses in twin lead are so much lower than in regular coax, you can use all you want (within reason). Do be careful to stand it off from any metal it encounters on the way into the shack.

Inside, the simplest way to match the twin lead to your rig is with a balun. I use a 6:1 balun to get the impedance down to the 50 Ω my radio likes. A 4:1 balun works fine too, though the 6:1 usually presents a better match. Both baluns are sold by a number of *QST* advertisers. Ditto for the 300-Ω twin lead.

Speaking of the shack, if yours is on an upper level at your home, consider setting the Clothesline up with one end near a shack window. You'll be able to reach out, retune (that is, haul in the line), then go back to your rig to check your SWR meter.

If you don't have this luxury, don't sweat it. I calibrated my Clothesline by setting my rig on tune-up power for each band, and going up to the roof of my apartment building to peak the antenna with a field-strength meter. I confirmed each setting by checking the SWR back in the shack. On every band I tuned for, it was well below 1.5:1. As I found each feed-point setting, I marked them with various colored indelible markers for each band. Now when I want to change bands, I just go up to the apartment roof, run the Clothesline out to the right color, and I'm tuned! It takes seconds.

I can imagine other settings where you'd run the Clothesline right outside a window, out to some convenient support. Or vertical, up or down the side of a building, a tree, or a flagpole (tie a flag to it, if you like). If you're camped out in suburbia with difficult, anti-antenna neighbors, a detachable feed line using alligator clips makes it the perfect disguised antenna. Who's going to suspect a clothesline? You could even use it during the day to... wait for it... *dry clothes!* You could even make it out of your standard, garden-variety hardware-store clothesline kit—plastic pulleys, vinyl-covered wire, the works. This makes the Clothesline the only ham antenna kit I know of that you can buy complete (minus the feed line) from your local hardware store. (In a perfect world, your local hardware store would stock twin lead.) Yes, I know I said at the beginning that this wasn't a trick for loading up a real clothesline and I've been true to my word. This is an antenna that happens to *look* like a clothesline.

I mentioned covering 17 and 12 meters. If you cut the original length to resonate just a little up from the bottom of 80, at 3.615 MHz, the fifth harmonic is smack dab on 17 meters. Cut it to 3.55 MHz and harmonic number seven is on 12 meters. In fact, these are such minor variations that you can surely find a convenient center frequency on 80 that'll put you right where you want to be on all bands. Though you don't need it, a tuner (either in or out-board) can get you right down to zero reflected power. Remember, feeding with twin lead or other balanced lines keeps your losses way down, so a little elevated SWR at the band edges is no big deal.

I'm now thinking about some kind of motor drive that'll permit me to tune up from inside the shack. My first reaction to this idea was, if I'm going to get into motor drives and the like, is that any simpler than a beam? I now think the answer is "yes." The drive would be simpler, in that I wouldn't need any position feedback—all I need to do is watch my reflected power meter to know when I've hit resonance. It doesn't need a whole lot of travel because a full range of feed points is available over just a quarter-length of the antenna. As well, few beams are all-band. And since the antenna you can put up is always simpler than the antenna you can't, for those of us in apartment settings where a beam or other, more complex antenna systems are out of the question, a motorized Clothesline might well be worth the effort. I've got a sneaking suspicion that, somewhere out there, there's a cheap, off-the-shelf drive unit with "Clothesline" written all over it!

By Ralph O. Williams, W8AJC **From *QST*, July 1949**

A Variable-Frequency Antenna

One to Ten Meters with a Single Antenna System

Multiband transmitters and band-switching receivers make it easy for us to jump from band to band, but the antenna has not kept pace. Many of us are prevented from operating on several bands by the thoughts of the multiplicity of antennas demanded by the conventional approach to multiband work. Here, to go with the VFO, is the VFA — tunable to resonance from the operating position. It covers 11, 10, 6 and 2, and all the television and f.m. bands in between, with the optimum performance all along the line. Ideas for the lower frequencies are included, too.

It has been the writer's lifelong ambition as a radio amateur to have a universal antenna; one that would not only work on several bands, but also tune within a band, providing optimum operating conditions on any frequency. The memory of endless trips to the rooftop or out to the mast to lower the antenna and cut off or splice on a few inches of wire to hit a special spot in the band is still fresh in mind. The old Zepp was pretty good but it required spaced feeders and tuning at the transmitter end. The half-wave aerial split in the center for a 72-ohm transmission line required no tuning at the station end but necessitated a different antenna for every band. Often the resonant frequency of these antennas varied widely from the values indicated by the formulae because of conditions not always apparent, and under some circumstances it was difficult to get adequate loading over an entire band. As the years passed matching systems were introduced, and they, too, are usually one-band devices. With all their disadvantages the antenna systems were not too bad back in the days of crystal control, but now we have VFO and often operate anywhere within the band. It goes without saying that what we need to go with VFO is a good VFA!

The group, other than amateur, most in need of a VFA, is that vast population trying to receive the various television and f.m. channels on a single antenna. A good half-wave dipole will outperform most of the existing elaborate receiving antennas providing, of course, it is possible to adjust the antenna accurately for each channel.

For years I have been giving thought to ways and means of feeding out and retrieving wire to make an adjustable center-fed half-wave antenna. The increased use of the VFO and the advent of television and f.m. broadcasting have made such an antenna practically a necessity. The folded dipole makes it a possibility, with rigging less complicated than the dial drives on some broadcast receivers! It is the purpose of this discussion to describe a remotely-controlled center-fed antenna capable of continuous adjustment from band to band and within the bands, using an untuned transmission line.

The Folded Dipole as a VFA

The folded dipole lends itself admirably to rigging with cords and pulleys so that the length of the flat top may be varied simply by pulling down on the feeders (see Figure 1). If the spacing between the center pulleys is adjusted so that the characteristic impedance of the two parallel conductors is 300 ohms the feeders will match 300 ohm ribbon regardless of their length and the length of the antenna. In this way, we have a tuned antenna with a flat line for any frequency, accomplished without resorting to sliding contacts at any point in the system. Figure 2 shows a practical hand-operated rigging that will enable the experimenter to make a set-up and observe its characteristics. Antennas of this type may be made large or small but it is suggested



Figure 1—Basic principle of the adjustable folded dipole. Dipole and feeder section are made of one piece of flexible wire. Antenna length is changed by pulling down on the feeder at point X. Spacing of the pulleys at the center is such that the characteristic impedance of the feeder section is 300 ohms. Twin-Lead is connected at points A and B.



Practical working model of the folded-dipole VFA of Figure 3 used at W8AJC. The system is operated by the servo motor at the base of the mast, and is controllable from the operating position.

that the beginner make up small models for 2 and 6 meters, or simply for the f.m. and television bands, to prove the merit of the antenna.

The photograph and Figure 3 show the details of an experimental working model, made long enough to tune to 10 meters, but designed so it could be pulled down to a flat-top length of only a few inches. The tuning was fairly sharp and the results over conventional antennas for the reception of f.m. broadcasting were gratifying. A considerable improvement was noticed even within the 88-108 MHz f.m. band when the receiver was tuned to different stations and the antenna adjusted for maximum response. It was a real thrill to couple the feeders to the 10-meter transmitter and watch the plate milliammeter go up as the antenna came into resonance, and then pass through, and return for maximum; then without changing antennas, to switch on the f.m. broadcast receiver, run the antenna down to about four and a half feet to pick up a Detroit station. It was interesting to observe the effects on the received signal strength as the antenna was shortened from resonance at 10 meters to the proper length for the f.m. band, with the receiver tuned to a station on 98.5 MHz. Reception was possible with the long antenna and became good as the flat top hit fourteen feet (three half waves), falling off to a very sharp null at 121.5 inches (critical), after which it returned to full signal strength at 56.25 inches, approximately a half wave for the received signal. This ability to tune to an extremely critical null might find application in the elimination of an undesired, strong nearby signal under certain receiving conditions.

The uses to which a continuously-variable antenna may be put are limited only by the operator's imagination. Once the mechanical details have been worked out they may be used singly or in multiple, as antennas or reflectors, driven by common or separate servo motors and in various phase relations. Such antennas may be used for transmitting or receiving, or for special applications such as field operations covering a wide band of frequencies, signal-strength measurements, target transmitters for lining up rotary beams, and antenna studies. Their greatest commercial application will no doubt be in the f.m. and television fields where simplified versions, adjustable from the receiver, should find wide acceptance.



Figure 2—Hand-operated version of the variable-frequency antenna mounted on a wooden frame. To minimize mounting space, the feeders are folded back over ratio pulleys, F. The 300-ohm line connects at A and B. With this arrangement the vertical movement of pulley F is equal to the end movement of the antenna pulleys. The supporting fishline or sash cord must be taut.



Figure 3—Diagram of the remotely-controlled antenna shown in the photograph. This system is now in use at W8AJC for 28 MHz and up. It may be reduced to a flat top of a few inches.

Other Types of Adjustable Antennas

Although the folded doublet lends itself most easily to continuous adjustment it might also be desirable to have a variable center-fed half-wave antenna suitable for use with coaxial or other low-impedance feeders. This may be done by the use of pulleys, insulators and wire, but requires a sliding contact at the center where the wind-up drums are located, and unless operated frequently it is subject to all the ills of exposed slip rings. This type of antenna is shown in Figure 4 and although at present, untried at W8AJC, it may prove worth-while on the lower frequencies, filling the long-felt need for a tunable 80-meter antenna that will work on 40 and 20 also!

Folded-Dipole Design

Useful information relative to the design of folded dipoles may be found in the ARRL *Handbook* for 1948, War Department *TM11-466*, RCA's little book *A Practical Analysis of U.H.F.* and in a paper by W. Van B. Roberts appearing in the *RCA Review* for June, 1947, page 289. The article by Roberts, in which he tells of the work done by his group at Princeton during the war under Government contract for the study of the folded dipole, is very helpful in providing the reader with a mechanism for analysis of the antenna. The literature indicates that spacing of the conductors composing the flat top should be close, in the order of 1/100 wavelength. Since our antenna is to have flexible conductors it is desirable to work with a type of wire that has a large diameter for low r.f. resistance, and at the same time has a high degree of flexibility. Such a conductor may be composed of insulated wire with a braided copper shield, the shield acting as the antenna and thus combining large area with good flexibility. The rest of the design is based upon available materials, with emphasis upon methods and mechanical devices for carrying out the function of varying the length of the flat top and handling the feeders. Refinements in both electrical and mechanical aspects will result from continued development.

Construction

When considering the construction of a tunable folded dipole many arrangements using springs or cords and pulleys will come to mind and it is up to the individual to select the method best suited to his particular use. In the beginning I tried a variety of springs, shock cords and weights to hold out the ends of the flexible antenna wire, but each of these methods had its own drawbacks and they all had the disadvantage of having to pull against a spring to shorten the antenna and depend upon the spring to pull it back out again. Metal springs come into resonance at certain frequencies. I tried metal-spring sash supports which would extend about 40 inches but they came into resonance in their extended positions and were not very smooth in operation.

It was finally decided to use cords and pulleys so arranged as to be in mechanical equilibrium and use the servo motor or other means only for the purpose of adjustment. This required less power in the servo and while it calls for more pulleys the result was smoother adjustment. I have found it convenient to support the antenna from the ends by means of insulated pulleys on a wood or other nonconducting structure. If the dipole is to be operated in a horizontal position there is no objection to using a vertical metal support pipe, but horizontal metal rods or pipes should not be used. For long antennas a center support must be provided for the feeder pulleys and the wind-up mechanism. The ends may be supported by poles, trees or buildings.

Servo Motors

The servo motor shown in the photograph is from a surplus Azon bomb tail assembly. It has plenty of power and may be reversed at will. It requires a 4-wire cable to the battery or other d.c. source. The current consumed is small and since the time of operation is also small a few dry cells will provide power for operation over a long period of time. Contained within the unit are two selenium rectifiers placed there to short circuit reverse currents to prevent sparking. They may be removed and inserted in a 30-volt a.c. line to the unit where they will provide sufficient d.c. for its operation. Reversal may be obtained at the station end by means of a double-pole double-throw toggle switch. Many other similar slow-speed servo motors are available on the surplus market, most of them reversible, and varying in size and power requirements. In some cases where d.c. is not available advantage may be taken of the gear train by connecting a universal coupling to the motor end and driving with a reversible universal fan or vacuum-cleaner motor operated from 115 volts a.c.



Figure 4–A suggested arrangement for an adjustable motor-driven dipole suitable for use on the lower amateur bands. Reels D_1 and D_2 reel in the antenna wire, while D_3 plays out braided sash cord. The assembly is made from a Signal Corps reel, Type RL-42-B, fitted with three reels, Type M-235, all available on the surplus market. The antenna reels are fastened to the cord reel by means of stand-off bushings secured to the center insulation. Brushes 1 and 2 connect to a 72-ohm line running to the transmitter. Success of this system depends upon maintenance of good contact at the brushes.

Sources of Materials

Antenna wire should be light, durable, flexible, of large diameter and a good conductor. For ease of adjustment it should pull around a one-inch pulley readily. Superflexible stranded copper wire of large diameter would be quite heavy whereas an insulated stranded wire, if size 20 or so and covered by a braided tinned-copper shield, would be light in weight, adequately flexible and of sufficient diameter. Belden No. 8885 shielded grid wire having an o.d. of 0. 1 inch has been found satisfactory. Too-stiff wire will make the system unwieldy.

Pulleys must be free-running for smooth operation and have as little friction as possible. A number of different kinds of pulleys normally available at hardware stores were tried and all had mechanical imperfections. Usually, though they seemed free-running when tried at the store, they turned out to have prohibitive friction when loaded and in the system. Since the number of pulleys required is fairly large and the accumulated friction may be excessive, ball-bearing pulleys are recommended. The first ones used here were homemade and turned out of fiber and used small ball bearings in the center. The ball bearings had 1/4-inch holes and a 5/8-inch o.d. and were obtained from disassembly of surplus gear trains, bomb sights, computers and other equipment so plentiful on the surplus market. Later I found a source of one-inch aircraft pulleys (AN-210-1A) with ball-bearing centers. Air Associates sells them for $1.25 each but the surplus market offers them at a lower figure. Pulleys may be found in all sorts of surplus aircraft control equipment and sometimes it is cheaper to buy a unit containing several pulleys than to buy them separately. Homemade hardwood pulleys turned out of maple and boiled in paraffin and using 1/4-inch brass axles should be satisfactory. The important thing is to have good low-friction bearings.

Twisted rope will cause the pulleys to turn over and twist and short out the aerial; therefore it is recommended that braided sash cord or clothesline be used. This, when properly fed through the pulleys, will not cause twisting. A nice size that fits available pulleys is a light braided clothesline 1/8-inch in diameter. Of course any flexible insulating line may be used such as dial cable, fishline or upholsterer's twine. Spring loading to prevent slipping because of stretching is advisable in some cases.

Limit Switches: If the antenna is not visible from the operating point Micro-Switches may be so placed that when the end of travel of the antenna is reached the circuit will be opened and the motor will stop, it being possible then to reverse it and run it to the other limit where another switch will furnish protection from overtravel. The switches should not be connected in the common lead to the motor but in the circuit controlling that direction only. (Switches and associated wiring must be placed so as not to interfere with the electrical operation of the antenna.)

Conclusion

The examples shown are but a few of many possible ways of setting up remotely-controlled variable-frequency antenna systems. It is hoped that this article will serve as a basis for further development of adjustable antennae for amateur and commercial use.

By Rod Newkirk, W9BRD **From *QST*, July 1993**

Honey, I Shrunk the Antenna!

Think small! Communicate with multiconductor miniature loop antennas.

Great energy and ingenuity go into efforts to boost the effectiveness of compact transmitting antennas—*compact* meaning configurations with circumferences of $^1/_8$ wavelength or less. By this definition, a 40-meter design could be a square with 4-foot sides. In the following discussion, I depart slightly from the square. I prefer $3^1/_2$ feet high by $4^1/_2$ feet wide, suspended in the vertical plane, for convenience in my antenna's location.

The traditional small-loop approach is to insert capacitance in series with a one-turn loop, tune it to the desired frequency, and then attempt to feed power to it as efficiently as possible–no simple matter. The antenna's Q is astronomical, current and voltage are monstrous, bandwidth is razor sharp, and its radiation resistance is ridiculously low. This lossy situation can be improved by reducing the resistance of the loop material through the use of piping, foil, etc, but the resulting plumbers' nightmares are hardly worth the pains.

A more promising avenue toward practical, simple compact antennas would appear to be in the direction of varied configuration. The goal is to "cool" the system with better power distribution, and at the same time simplify the feed. For example, vast improvement in the key parameters is possible by application of the venerable "folded dipole" technique. This can be done by adding one more turn, tuned identically, connecting the two turns *in series*, and re-resonating the antenna. Now, looking into one of the twin current nodes, the input impedance will have roughly quadrupled. The one-turn loop's skimpy 5 or 6 Ω rises to approximately 25 Ω. Adding yet another such turn doubles this to about 50 Ω–a convenient match to common coax. See Figure 1. As with the folded dipole, more than four turns are unprofitable; diminishing returns raise the input impedance. little faster than ohmic resistance. Note that the tuning capacitances, each about 40 pF, must be kept nearly equal for overall system balance.



Figure 1—The three-turn loop antenna for 40 meters. Each capacitor is about 40 pF to resonate and match the antenna to a 50-Ω feed line.

Increasing Multiturn Loop Efficiency

Lots of hams use small loops in situations where they can't erect a larger antenna. Making contacts with these antennas largely depends on high radiation efficiency. Here are some things you can do to increase efficiency and effectiveness of such antennas:

- Use large-diameter copper wire. Keep the copper surface clean. Tin-plated wire is noticeably worse than copper in this application because of skin effect–most of the RF travels in the tin, which is far lossier than copper at RF.
- Use low-loss capacitors. The key here is minimizing dielectric loss, which is most favorable in vacuum- and air-dielectric capacitors. You can also parallel several capacitors to decrease losses.

Increasing the wire size used in these loops raises the antenna Q, narrowing the bandwidth and increasing the voltages and currents present. For this reason, you may have to use higher-quality capacitors than those used in the experimental versions if you increase the wire size.

Remember that high voltages can exist on a multiturn loop antenna's wires at power levels of a few tens of watts or more. Thus, it's best to keep the antenna well away from other objects.—*Roy Lewallen, W7EL*

Construction techniques, conductor material, insulation and components now become less critical because voltage peaks and current nodes are distributed throughout the system. I use ordinary zip cord, two lengths entwined, giving four available turns.[1] For proper continuity, the four wires on each side of the loop are clearly tagged at alligator-clip connectors, top and bottom centers. For 7 MHz, one turn is left open (at top *and* bottom), but will become useful on the lower bands as discussed later. A more classy construction might feature braided hook-up wire of contrasting colors. Small cardboard spreaders at the clips keep adjacent capacitors separated.

Midget receiver-type capacitors are adequate for CW power output up to 100 watts. One of these should be conveniently variable, preferably a double-gang or splitstator type, for tweaking the system to the desired center frequency as indicated by a 1 : 1 SWR. At 7 MHz, each capacitance is about 40 pF in my antenna, so the old war surplus Hammarlund APC midgets do nicely. Bandwidth can approach that of a normal linear dipole if a slightly higher center frequency SWR is accepted by stagger-tuning.

Excellent 40-meter results indicated that the same loop, dimensions unchanged, could have a shot at 80 meters. At 3.5 MHz, it becomes truly a miniloop, only $^1/_{16}$ wavelength in circumference. Adding the fourth turn (Figure 2) raises the feed impedance at a slightly higher rate than ohmic resistance, so I included it. Armed with a bargain bag

The Ingredient Called *Belief*

Even though my busy family life keeps hamming time rare, the time I spend hamming has to be spent *right*. The idea isn't just to get on the air and contact anyone anywhere—that's too *easy*. The idea is to do something a hair off-the-wall and see if anyone shares the same orbit. So I'm one of those guys who calls CQ QRP for ten minutes at 10149.5 kHz even as game clogs the band's low end—someone who looks for (and *expects*) ragchews on 3560 at noon. And so I naturally was the guy to call a 5-watt, 3 × 2 × 1 CQ at 7138 kHz at around 10 PM one night last fall when the broadcasters had long since muscled straight-thinking NovTechs off to safer terrain. And so I naturally was *of course* immediately answered by W9BRD.

It figures. We've worked on schedule many times before, but he and I—he's the father; I'm the son—have never had to prearrange each new "first contact" after changes of station setup or locale. *Chance* is too facile a word for this, but then I haven't looked too hard for a better word, either. I don't need to; we just do our individual quirky things and click.

This time, we *both* had new setups: I'd just relocated the armful of gear constituting my "shack" to the bedroom and was talking to a low dipole through 100+ feet of mongrel coax; *he* was trying out an indoor, largely below-ground loop antenna—one of the versions shrunken in this article—with just a few tens of watts, tunneling past those steamroller broadcast signals as soundly as any medium-scale ham signal from Chicago.

Enjoying the magic of yet another first contact, I hardly gave his setup a second thought. But you may wonder if such antennas really work. Gooch's Paradox explains it thus: "RF gotta go *somewhere*." Seeking to soothe the linearless, towerless masses who toil with "*only* 100 watts," Newkirk's Tiresome Chant puts it, "Successful MF/HF radio communication may proceed at astoundingly low received-signal strengths." Reduced to generic essentials, it's this: The most important single factor in success with *whatever* you use is overcoming your own disbelief.—*David Newkirk, WJ1Z*



Figure 2—Extending the Fig 1 concept to 80 and 160 meters requires adding another turn to the antenna and increasing the capacitances. See the text for capacitor values.

of small 1-kV ceramic capacitors, I reached 3.6-MHz resonance with a value of 100 pF for each of the four capacitances. One capacitor was then replaced with an old broadcast-style, two-gang 300-300-pF variable for tweaking. I measured the feed impedance, at the center of one of the four turns, at about 18 Ω–well within the range of simple gamma matching. So another junk-box broadcast variable, three 350-pF gangs paralleled, was suspended at the loop's top center. Only about 650 pF was needed for a 1:1 match to coax after a 30-inch gamma lead was dangled to a tap at the center of one side of the feed turn. Then the system was tweakable over the entire 80-meter CW range. The remaining ceramic capacitors get slightly warm at 80 watts, which indicates significant power loss. These capacitors should be replaced with low-loss units for best performance, but I left them alone for my experiments. I easily contacted the East Coast and as far west as Arizona in the following few nights on the air.

My next inclination, as you may surmise, was to try the little gem on 160 meters. A four-foot-square transmitting loop for 1.8 MHz? I wasn't overly optimistic. Years of tinkering at W9BRD had failed to produce a decent indoor compact antenna, even of much larger size, for top-band work. But I dug into my bag of ceramics and gave it a go. The four-turn loop, now only $^1/_{32}$ wavelength in circumference, resonated at about 1.8 MHz with four 350-pF capacitors. One of these was replaced with an old broadcast-type 500-pF variable for tweaking the center frequency between 1.8 and 1.85 MHz. I double- and triple-checked the measured feed impedance—16 Ω. Now I knew it would work. The gamma-match SWR dipped to 1:1 at about 800 pF using the same lead, tap and broadcast capacitor as on 80 meters. Immediate solid 40-watt CW QSOs with WN9W, KC4WWV, WK0B and W4VZB were most gratifying.

Variations and the Higher Bands

If such a $^1/_{16}$-wavelength loop can function at 80 meters, the same should be true at 20 meters. So I wound a 1-foot-square, three-turn model on a cardboard box, hung it on a wooden bulkhead, and resonated it to 14.050 MHz with three 50-pF ceramic capacitors. This time, instead of the usual fudging capacitor, I spaced the turns $1^1/_2$ inches apart. Center-frequency tweaking thus could be done by uniformly edging the turns away from or toward each other. This spacing approach works fine for box-wound loops, but for the lower bands, I prefer closewound zip cord. Input impedance turned out to be about 11 Ω—I should have used a fourth turn—and gamma coupling worked okay, as on 80 and 160. The 1:1 feed-line dip occurred with a 120-pF series capacitor, with a gamma lead of 13 inches. In my installation, this antenna is no low-angle DX radiator, to be sure, but I've received S9 reports during many stateside QSOs. Anyone for a 3-inch-square 2-meter version?



Figure 3—At A, the 30/20-meter loop; at B, the 15/17-meter version, and at C, the 10-meter variant.

Antennas smaller than necessary are interesting stunts that help prove a design. However, for the lowest HF bands I recommend the largest practicable circumference.

For operators limited to indoor installations, floor-to-ceiling height is usually the limiting size factor. Thus, a cooler 7-foot by 9-foot job, requiring much smaller resonating capacitances, should be a natural for 80 and 160.

Incidentally, the configurations described are quite well balanced. Although in my tests the antennas were placed within tweaking distance of the operator, no shack RFI showed up on any band at the 80-watt level. Careful symmetry helps, notwithstanding the dangling gamma lead on 80 and 160. The coax feeder should run down and away from the top-center feed point, equidistant from the vertical sides. A balun or coaxial RF choke might seem applicable, but I found such isolation unnecessary. The directivity pattern for such a loop is the usual figure-8, with most radiation in the plane of the loop. However, there will be sharp nulls perpendicular to the loop's plane, which you should take into account when placing your antenna.

My prime purpose here is to treat loops of 1/8-wavelength circumference or smaller, but you may desire to use the same 3½-foot by 4½ foot dimension on the higher HF bands, as I do. The hook-ups shown in Figure 3 perform well on 30 through 10 meters. Each provides a direct match to 50-Ω coax. True, almost any old piece of wire gets QSOs on 10.1 MHz and above, but a balanced loop radiator is hard to beat for indoor hamming. A few hints and observations:

- At 10. 1 and 14 MHz (Figure 3A), just two turns are sufficient to reach a feed impedance of about 50 Ω. The two approximately 20-pF capacitance values are slightly higher for the 30-meter band.
- For 17 and 15 meters (Figure 3B), the loop must be made electrically smaller by splitting it symmetrically. Two split turns and four equal capacitances then bring a close 50-Ω match. Note that the feed point is moved to the center of one of the four vertical sides. Capacitances are in the 15-pF range.
- On 12 and 10 meters (Figure 3C), one split turn will suffice for a near-50-Ω match, with two capacitors of about 12 pF. Here, splitstator midgets can ease adjustment by minimizing hand capacitance, but it's a fancy junk box that includes them. The old APC midgets, whose rotors have little more mass than their stators, will maintain enough system balance.

Cautions and Conclusions

Like any indoor antenna, the loops I describe here generate substantial electromagnetic fields in operation. Thus, they have considerable potential to generate RFI. For this reason and to prudently avoid placing yourself or others in large RF fields, you should keep all antennas as far from consumer electronic devices and people as possible, and use the least RF power necessary to conduct the desired communications. The current editions of *The ARRL Handbook* and *The ARRL Antenna Book* cover this subject in more detail.[2]

A final comment: For overall results with compact antennas, like almost any skyhook, the higher above ground the better. In my case, radiation and reception strongly favor higher skywave propagation angles. All antenna configurations I describe here were tested and operated in a cellar ham shack, where half of the system is below ground level!

Notes

[1] See the sidebar, "Increasing Multiturn Loop Efficiency," for some ideas on optimizing such an antenna's performance.

[2] See Chapter 9 of the *Handbook* and Chapter 1 of the *Antenna Book*.

$12.00

QRP CLASSICS

The Best QRP Projects from QST
and the ARRL Handbook

CERTIFICATE NO

DATE

AMATEUR RADIO CLUB
INTERNATIONAL INCORPORATED

OPERATING ACHIEVEMENT

Certificate

AWARDS MANAGER

QRP
VXO
7 MHz
C2
Y1
100
TUNING
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000
PA
MPS-U02
RFC 1
22 μH
R13
3.9 k
2N2222
2N4400
Q1
C4
33
R6
22
Q2
C9
0.1
C1
270
R1
5.6 k
R2
22 k
R3
180
C3
0.01
RFC 2
390 μH
R5
1.5 k
RFC 3
22 μH
C7
50
C6
0.1
C5
0.1
R7
3.9 k
Q1, Q3, Q4
C
E
B
(FRONT)
R4
47
D1
D2
D3
1N914
OPR
S1A
SPOT
+ 12 V (XMIT)
KEYING SWITCH
T-R SWITCH
R10
4.7 k
Q4
KEY TO GND
R12
4.7 k
Q3
C15
0.01
R9
10 k
C14
0.1
1 μF
16 V
C17
C16
0.1
R11
1.1 k
2N4036
2N4403
2N2222
2N4400

QRP CLASSICS

The Best QRP Projects from QST and the ARRL Handbook

Published by the
American Radio Relay League
225 Main Street
Newington, CT 06111

Edited by Bob Schetgen, KU7G

Copyright © 1990 by

The American Radio Relay League Inc

Copyright secured under the Pan-American Convention

International Copyright secured

This work is publication No. 123 of the Radio Amateur's Library, published by the League. All rights reserved. No part of this work may be reproduced in any form except by written permission of the publisher. All rights of translation are reserved.

Printed in USA

Quedan reservados todos los derechos

First Edition

$12.00 in USA and Possessions

ISBN: 0-87259-316-9

Foreword

Welcome to the realm of QRP, a place where less RF power is more fun for the operator! In general, QRP operators use equipment that weighs less, takes up less space, costs less and is less dependent on ac power than the typical ham station of 50 W or more. In return, QRP enthusiasts get freedom—freedom to carry a complete station, with accessories and antenna, in a briefcase. A typical QRP station is small enough to take along on vacation in a car full of family, by air or backpacking. Your QRP station can operate from batteries for long periods when the power fails, or indefinitely from unusual power sources such as private hydroelectric, wind or solar power systems.

Freedom is gratifying, but better still is the sense of accomplishment that comes from operating equipment you built yourself. You may best love the feeling when that first CQ from your home-built transmitter is answered—or the way a smile steals onto your face when that 1-kW station gives your 1-W transmitter a 599 report.

These qualities place QRP operation near the heart of Amateur Radio, and as a result QRP operation has always been a popular topic in League publications. In this book, we have assembled a balanced collection of QRP articles from 15 years of League publications for easy reference. While there are a few very simple projects suitable for beginners, you will also find challenging projects and pertinent articles about circuit design, component selection and adaptation. A QRP buffet is before you—enjoy!

David Sumner, K1ZZ
Executive Vice President

Newington, Connecticut
May 1990

CONTENTS:

Chapter 1: Introduction

1 Why QRP?
4 QRP: More Than a State of Mind

Chapter 2: Construction Practices

7 Experimenting for the Beginner
12 Quick and Easy Circuit Boards for the Beginner
15 Stalking Those Fugitive Components
19 Blending Circuit-Board Fabrication Techniques for Success
19 Etch-Resist Pens for Homemade Circuit Boards

Chapter 3: Receivers

20 The Neophyte Receiver
25 A Band-Imaging CW Receiver for 10 and 18 MHz
32 His Eminence—The Receiver
40 CER-Verters
45 Build Your Own MCM ICs
50 A Converter for the 24-MHz WARC Band
53 Another One-MOSFET Converter
55 A Four-Stage 75-Meter SSB Superhet

Chapter 4: Transmitters

59 A VXO-Controlled CW Transmitter for 3.5 to 21 MHz
63 18-MHz Component Values for the Handbook VXO CW Transmitter
64 Simple QRP Gear Versus Good Performance
69 Three Fine Mice—MOuSeFET CW Transmitters
75 Transmitter Design — Emphasis on Anatomy
89 Four Watts, QSK, for 24.9 MHz
93 Some QRP-Transmitter Design Tips
96 A QRP Transmitter for 30m
97 A Two-Transistor Transmitter for 30 Meters
98 A VMOS FET Transmitter for 10-Meter CW
102 A Beginner's Look at Basic Oscillators
108 The Fine Art of Improvisation
111 Tuning-Diode Applications and a VVC-Tuned 40-m VFO
116 A VFO with Bandspread and Bandset
119 Meet the Remarkable but Little Known Vackar VFO!
122 Adjusting the Power Output of JFET VFOs

Chapter 5: Transceivers

123 Putting the Boots to Your HW-8 QRP Transceiver
128 30-Meter Conversion for the HW-8
129 Improving the HW-9 Transceiver
133 HW-9 Tips
134 The MAVTI-40
140 Better Ears for the MAVTI-40 Transceiver
148 A QRP SSB/CW Transceiver for 14 MHz
156 The QRP Three-Bander
162 QRP Transceiver for 50 MHz
170 Audio-Filter Connections for the Ten-Tec Argonaut Transceiver
170 Curing Mechanically Induced Frequency Jumps in the Ten-Tec Argosy 525
171 AGC and RF Gain Controls for the Ten-Tec Argosy

Chapter 6: Antennas

172 Some Practical Antenna Considerations
177 Antennas for Those Who Can't Have Antennas
180 Lightweight Trap Antennas - Some Thoughts
184 A Portable Vertical-Antenna Mount
186 An Extended Double Zepp Antenna for 12 Meters
188 Scaling the Extended Double Zepp
189 An Indoor Dipole Antenna
190 A Short 7-MHz Dipole

Chapter 7: Accessories

191 Active Filters
196 A Simple, High-Performance CW Filter
198 A Passive Audio Filter for SSB
199 Designing and Building Simple Crystal Filters
205 Super SCAF and Son—A Pair of Switched Capacitor Audio Filters
212 The SWR Twins—QRP and QRO
216 A New Face for a Recalibrated Meter
217 A Simple and Accurate QRP Directional Wattmeter
223 Build This QRP Omni Box
228 A Simple Resonant ATU
231 A Balanced QRP Transmatch
233 Variable-Notch Filter for Receivers
234 Simplified Output Metering Protects QRP Transmitters
235 An Accurate, Inexpensive Frequency Marker

Chapter 8: Power Supplies

236 Some Power-Supply Design Basics
240 A 1.25- to 25-V, 2.5 A Regulated Power Supply
244 Alternative Energy—An Overview of Options and Requirements
254 Operate Your Station With Power from the Sun!
258 Free NiCd Cells
258 A Deep-Cycle Battery as an Emergency Power Source
258 A One-Shot Timer for Battery Charging

Chapter 9: Design Hints

259 Power Amplifier Development with Your Transistors
262 On Solid-State PA Matching Networks
263 More on Solid-State PA Matching Networks
264 Broadband and Narrow-Band Amplifiers
269 Electronic Switching and How It Works
274 Reducing AM Detection in Direct-Conversion Receivers
274 Common-Mode Hum in Direct-Conversion Receivers
274 Series-Resonant Circuit Enhances Desired Signal in QRP Rig

Preface

The QRP area of Amateur Radio is rich in experimentation, and the projects in this book cover 15 years of Amateur Radio technology. Feedback and pertinent work from the "Hints and Kinks" or "Technical Correspondence" columns of *QST* are included in this book. Parts availability changes every few months, however, and some parts mentioned may be difficult to acquire. In addition, many circuits use active devices well beyond their design range, and even the simplest circuits may not work with all samples of the listed components. So if a circuit doesn't work on the first try, don't let it discourage you. One joy of QRP is the relatively small investment of funds and time in most projects. You can try many circuit configurations and parts substitutions without breaking your budget.

Don't be frightened at the thought of experimenting with circuits; there are many resources to help. Some of the articles in this collection contain ideas that can be applied to other projects. Doug DeMaw, W1FB's *QRP Notebook* provides a basic foundation in QRP techniques with lists of standard component values and QRP organizations. Look in the *ARRL Handbook* for information about basic radio theory and circuit operation. Ask around, and you may find local hams with QRP construction experience. Your ARRL Section Manager (listed on page 8 of *QST*) can put you in touch with an Assistant Technical Coordinator near you who can help with technical questions and activities.

If you have trouble locating parts for projects, "Stalking Those Fugitive Components," in Chapter 2, should be of some help. Look for local parts suppliers in the yellow pages under "Electronic Equipment & Supplies - Dealers." Start building a library of manufacturers' data books to help you determine equivalent parts.

Finally, the QRP purist knows that the mode is officially limited to operation with less than 5 W (10 W PEP for SSB) of output power. ARRL extends the definition to include transmitters with up to 10 W of dc input power, regardless of transmitter efficiency. Some of the articles in this book significantly exceed either of these limits. Those construction projects that are not strictly QRP are included for educational purposes and for those cases where the operator decides to exceed the strict QRP limitations.

CALL FOR PAPERS

If there is sufficient support among QRP enthusiasts, we at ARRL Headquarters would like to publish a QRP Compendium. For such a book we will need a steady supply of previously unpublished articles. If you wish to contribute or want more information, contact the ARRL Technical Department for an author's guide. Articles should be clearly addressed to the Technical Department for the QRP Compendium.

From February 1990 QST, p 43:

Why QRP?

Low-power operation is more popular than ever before. Why not join in the fun?

By Kenny A. Chaffin, WB0E
2942 South Wabash Circle
Denver, CO 80231

Why would anyone except a masochist want to operate with less than 5 W output? What possible attraction could there be? Perhaps it's for the same reason *anyone* would operate an amateur station in this age of global telephone systems and satellite TV.

Maybe it's for the challenge of doing something a little different. Maybe it's for the thrill. But I can tell you, there's nothing quite like having a QSO with a Japanese, Russian, or rare DX station while running less power than a kid's nightlight!

The QRP Q signal was created to mean "Shall I reduce power?" but has since been adopted by the enthusiasts of low-power operation as their banner. QRP has come to mean 5 W or less output for CW, or 10 W PEP output or less for SSB. Most amateur organizations and contests embrace these as the official QRP limits.

Many of the same amateur activities that take place in the rest of Amateur Radio's domain are alive and well within the QRP community. These activities include constructing home-brew equipment, operating QRP stations, experimenting, DX chasing, and contesting.

You Can Build It

The QRP arena is one of the few places where the average home-brewer still can make a decent showing. In this age of multistage, integrated circuit, super-sophisticated all-mode transceivers, QRP operation stands out as a home-brewer's dream. How many hams can hope to duplicate the operation of the latest HF transceiver on their workbench? Probably none. If, however, we change the rules by restricting the power output, it is certainly possible for nearly anyone with the ability to obtain a ham license to build a 5-W transmitter.

QRP transmitting equipment is simple and physically small. The same can't always be said for the receiver, however. A QRP receiver must do the same job as any other receiver, while usually in a smaller box. It is certainly possible to build an adequate QRP receiver by using minimal circuitry and integrated circuits—but it's not easy to duplicate a top-of-the-line commercial receiver in a matchbox.

If you are interested in home-brewing, but haven't actually done much, I would suggest the QRP transmitters as a good first project. QRP transmitters usually consist of a few transistors, and for HF work, the layout is not particularly critical. Probably the toughest part is finding or building the coils and chokes. Even the coils are not a big deal once you've wound a few. Schematics and kits are readily available. They make it easy to get started. After you've put together a kit or two, it'll be a piece of cake to move on to "bigger and better" projects.

If you do start with a QRP transmitter, you can simplify the circuit even further by opting for crystal control. It may not be as restrictive as you think. A fair amount of QRP operation takes place on dedicated QRP frequencies—making it easy to pick the crystal you need (see Table 2). By adding a trimmer capacitor across the crystal you can "pull" the resonant frequency slightly to the lower side of the crystal frequency (This is, in effect, a simple VXO circuit.) The crystal can be pulled from about 3 kHz on 80 meters to 10 kHz on 15 meters, depending on the crystal type and other factors.

Antennas

Once you have a working transmitter, you'll need a suitable antenna. Which brings us to the question: What kind of antennas do QRP stations use? You may think that following the lead of low-power, simple transmitter and receivers, QRP antennas should be small and simple. This is definitely not the case. A QRP antenna system should be as efficient as possible. Many transmission lines



THE AMERICAN
RADIO RELAY LEAGUE

WAS

RANDY RAND, AA2U

has submitted confirmation of having conducted two-way communication with amateur stations in each of the states constituting the United States of America

#00,000
Award Number

October 26, 1989

Larry E. Price

Communications Manager

ARRL's popular Worked All States award has a QRP endorsement. If you're looking for an interesting stateside challenge, why not break out a flea-powered transmitter and give it a try? To make things easier, we no longer require "QRP" to be indicated on the cards submitted for the award.



The "Modified Cubic Incher" is a typical, easy-to-build 2-W CW rig. It can easily be constructed in an afternoon, and will provide plenty of QRP contacts on 80 or 40 meters. Construction details can be found in *The 1990 ARRL Handbook*, p 30-41.

attentuate the signal considerably before it reaches the antenna. If you have 5 W of RF output and a poor feed line, you could end up with only a couple of watts at the antenna! You should approach your QRP feed line as if it were being used for UHF or satellite work. You want to get as much power to the antenna as possible. Using a lossy feed line at kW power levels is tolerable; at QRP levels, however, the loss of every milliwatt becomes more critical.

The antenna itself is also important. For best results you need the best antenna you can put up—it's as simple as that—a high-gain Yagi if possible, up high and clear. It's just as though you were chasing the farthest DX. My antenna is a vertical, which is probably one of the worst choices. But it's the best I can do considering aesthetics, ordinances, and neighborly relations. Even with my vertical I've worked Japan and many Soviet stations using only 5 W output.

Books and Clubs

A couple of reference books you may want to pick up are, *The Joy of QRP* by Adrian Weiss, W0RSP, and *QRP Notebook* by Doug DeMaw, W1FB. The former is more operations oriented and the latter is almost entirely construction projects. There is also a monthly column on QRP written by Michael Bryce, WB8VGE, that runs in *73*. Another monthly QRP column appears in *World Radio*.

Occasional QRP articles, such as this one, appear in various Amateur Radio magazines. Several QRP clubs are available for those interested (see Table 1). QRP Amateur Radio Club International is one of the biggest, and publishes *QRP Quarterly*. For information about QRP ARCI and a sample copy of *QRP Quarterly*, write to Joe Sullivan, WA1WLU, 267 Sutton Street, North Andover, MA 01845. The Michigan QRP Club encourages low-power operation with its newsletter, *The Five Watter*. And if you're interested in British-style QRPing, you can join the G-QRP club [G-land QRPing is strongly associated with home-brewing QRP gear.]

Operating Skills Required

If you want to hone your operating skills, QRP is for you. With only a few watts of signal to work with, it becomes mandatory to perfect your operating technique if you are

Confessions of an Inveterate Milliwatter

People like to overcome challenges; it's part of our nature. I lack the physical skills to be a mountain climber, so I have instead chosen to challenge the fickle layers of the ionosphere with a transmitter that runs milliwatts. It's my way of riding the knife-edge of what can be done.

Like many hams, I started chasing DX with 100 watts. I was content with this until a friend loaned me an HW-7. The meager 5 W didn't work very well with an indoor apartment antenna, but it gave me quite a thrill to work a few common European countries.

I finally managed to move to the country, where I had enough acreage to grow a better antenna crop. I also built a crystal-controlled transmitter that used a 74S00 logic chip as the oscillator and final amplifier, producing 250 milliwatts. A few local states were quickly put in the log. I smiled every time I told the station I was working that my final was a NAND gate!

A few hundred miles seemed to be the limit until the 1984 CW Sweepstakes weekend. I had never paid much attention to contests, so I was not prepared for the bedlam I found when I turned on my radios that Saturday afternoon. A loud W4 was calling CQ on 40 meters, and with no expectation of actually being heard, I sent my call sign—once. What's this? He's working me! Uh, let's see, I first got my ticket in, uh, '64—that will do. By the time the contest was over, I had worked 24 states with 250 milliwatts. Those big-gun contesters sure have good ears! Three years later, I had them all. My hand was literally shaking as I waiting for the band to improve enough to work a KL7 in the CQ WW contest.

Last year, my milliwatt quest continuing, I modified an HW-8 to run 10 milliwatts output. I had quite an adventure during the '88 CW Sweepstakes, netting 56 QSOs with 31 ARRL sections. The 18-hour operation boiled down to 347,200 points per watt!

The 1989 CW SS gave me state number twenty-nine. A couple of DX contests later, eight DXCC countries were in the log. All contacts were made via an 80-meter dipole fed with open-wire ladder line.



ARRL Lab Engineer Ed Hare, KA1CV, shows off his modified Heath HW-8 QRP transceiver. Ed's micro-power rig puts out slightly less than 10 milliwatts on 80 through 15 meters.

It's a high-tech effort. I use a computer to predict expected signal levels to those elusive western states. By all indications, WAS with 10 milliwatts can be done! If any operators west of the Mississippi want to test their station's weak-signal capabilities, I would appreciate a sked!—*Ed Hare, KA1CV, ARRL Lab Engineer.*

Table 1

QRP Clubs

QRP Amateur Radio Club International c/o Bill Harding, K4AHK 10923 Carters Oak Way Burke, VA 22015	Membership—$10 Newsletter—*QRP Quarterly*
Michigan QRP Club c/o Membership Chairperson 5346 W Frances Rd Clio, MI 48420	Membership—$7 Newsletter—*The Five Watter*
G-QRP c/o George Dobbs, G3RJV 498 Manchester Road Roachdale Lance, England OL11 3HE	Membership—$12 US Newsletter—*Sprat*

Table 2

Internationally Recognized QRP Frequencies (kHz)

CW	*SSB*	*Novice*
1810		
3560	3985	3710
7040 (7030)	7285	7110
10106		
14060	14285	
21060	21385	
24900	24950	
28060	28885	28110
50060	50885	

going to work through that DX pileup. QRP is the radio equivalent of brain over brawn.

But isn't a 1-W signal lost in the shuffle of more powerful stations? It's not as lost as you may think. A 1-W signal is only a little more than three S-units weaker than a 100-W signal. So, if your 100-W signal is S-9, your 1-W signal will be about S-6. And that's plenty of signal!

For QRP operation, you must be able to find DX stations, be aware of when and for how long bands will be open and have a crisp and clear setup on both CW and SSB. You must be able to quickly assimilate a DX operator's technique.

One of the primary skills QRP operation strengthens is patience. With QRP power levels you have to wait for the right moment and make your move. This means you must be alert and listening rather than transmitting. You have to be familiar with the bands, operating procedures of DX stations and other QRP operators. All this takes a bit of patience, practice and listening.

How Do I Do It?

Okay, let's say you just want to operate QRP without building any special equipment. That's easy, just turn the power down on your 100-W transceiver. This requires a power meter or some other method of determining your output power. This adjustment is dependent on your rig, and may be as simple as reducing the RF output control or as complicated as retuning the transmitter for reduced output.

Here's a neat experiment that will introduce you to the realm of QRP operation in a gradual fashion: cut your maximum output in half and operate at that power level for a week or so, then cut it in half again. Continue cutting power until you're down to 5 W. I'm sure you'll be surprised, as I was, at how well you can communicate with reduced power. In many cases, the operator on the other end can't tell the difference. My Heath HW-5400 puts out about 100 W maximum, and now that I work QRP almost exclusively, I really have to have a special reason to crank it up to full power.

Commercial QRP Equipment

If for some reason you can't operate your rig at reduced output, there is commercial QRP equipment available. Heathkit has offered three different QRP transceivers. All operate CW exclusively and cover only that portion of the HF bands. The first was the HW-7. It put out a few watts and had a relatively unstable receiver. The redesigned and improved version turned into the HW-8; there are plenty of these still in use.

The QRP community really took the HW-8 to heart and there are modifications galore available to spruce it up. Most of these have been collected in the *Hotwater Handbook*, available from Michael Bryce (he writes the QRP column for *73*). This handbook has been recently revised and reprinted, and includes mods for both the HW-8 and the latest-generation HW-9.

The culmination of Heath's QRP line is the HW-9. It features a vastly improved receiver and a bit healthier power output—slightly more than 5 W on some bands. The HW-9 also covers the newer WARC HF bands and is the only QRP rig currently on the market. You'll have to find the others at swap meets or through the classifieds. Expect to pay up to $70 for an HW-7, $60-$100 for an HW-8, and $100-$200 for a used HW-9.

The cream of the crop among QRP rigs is Ten-Tec's Argonaut series. The latest version (still long out of production) is the Argonaut 515. It's worth its weight in gold. The previously released 509 is almost as good and the 509's predecessor, the 505, is still hanging in there. These rigs operate both CW and SSB and are usually available at swap fests, through want ads, and from individuals. A 505 goes for $100-$175, a 509 for $125-$200 and a 515 for $200-$300 or more, depending on the market. Most of these rigs are generally available, it's just a matter of whether you can afford, and find, a 515 or an HW-8.

A Few More Advantages

There are a couple of other advantages of QRP operations that aren't so obvious. Because you are operating with a minimal power output, your transmitter will probably last "forever." Your electric bill will be less—especially if you stop using your 2-kW space heater. The other nonobvious advantage is that you won't overload the front end of your neighbor's television. It's a pretty rare occasion when operating with 5 W causes interference.

Contests and Awards

The bonus multipliers and points for QRP contest operation have gotten many hams hooked on QRP. Operating "QRP battery power" for Field Day gives a multiplier of five. You only have to make one contact for every five QRO QSOs.

QRP operation is becoming quite popular for many major contests. The following contests have QRP categories: November Sweepstakes, June and September VHF QSO Parties, January VHF Sweepstakes, and the ARRL International DX Contest, among others.

As far as awards, QRP ARCI offers a thousand-miles-per-watt award, available to anyone presenting evidence of a qualifying QSO. QRP ARCI also offers special QRP awards for WAS, WAC and DXCC. The other QRP clubs also offer versions of these, and other, QRP operating achievement awards.

What's Left

What do you do once you've completed QRP DXCC? How about milliwatting? Milliwatting is operating at less than 1-W output. Once you've perfected your QRP skills and equipment, this is the next challenge. Admittedly, there are few who strive for these ranks, but when it all works—WOW! I've recently seen a circuit for a half-watt crystal-controlled transmitter using a single 2N2222 transistor. I haven't tried it yet, but when I do, I can't wait to hear what the operator on the other end says when I tell him. Of course, at milliwatt levels your antenna and feed line become doubly critical. It seems strange to see a 1-inch-square, single-transistor transmitter connected to ¾-inch hardline! But it's great fun.

So why not give QRP or milliwatt operation a try? You just might get hooked. See you on 7040 kHz—a popular QRP hangout.

From April 1984 QST, p 52:

QRP: More Than a State of Mind

Looking for a new challenge? Try reducing power and adopting a few new operating habits.

By Bradley Wells,* KR7L

Low-power operation, or QRP, has enjoyed a surge in popularity in recent years. Why? Mostly it's the challenge of working stations the "hard way," be it during contests or everyday operation, and the great satisfaction that comes from making contacts that the "big guns" make. Most low-power ops will agree that the motivation for QRP is the same as for chasing DX — but the rewards are inversely proportional to the amount of power used.

In this article, we'll take a look at the exciting world of QRP, discuss some equipment that's available and talk about ways of improving your chances of success with low-power operation. One word of caution to the reader, though: QRP can be habit-forming.

The definition of QRP, recognized by most amateur organizations, is 10-W input, or 5-W measured output. Five watts may not sound like much to those who consider 200 W low power, but the difference is not as great as you may think. Under actual conditions, 5 W will have little effect on your ability to work DX. The difference between QRP and, say, 200 or 2000 W is only 3 or 5 S units. Also, QRP exemplifies the spirit of the Rules — specifically 97.67(b), which states that " . . . amateur stations shall use the minimum amount of transmitter power necessary to carry out the desired communications."

Choosing an Antenna

A major failing of both experienced and novice QRPers is the antenna system. Unfortunately, most hams think low power equates with poor antennas. Many QRP operators seem to delight in using their rig with a 50-foot piece of wire thrown out the nearest window.

The basic rule of QRP antennas is that nothing beats a beam; and nothing beats a beam on a tall tower. Put up the best beam/tower combination you can afford. A good 3-element beam and 40-foot tower will put you on a more-than-equal footing with those running 200 W to a vertical.

A good full-size dipole is the next best choice. On 20, 15 and 10 meters, a high dipole exhibits directivity, so place it broadside to the desired direction of radiation.

Related to the dipole, and almost as easy to construct, is the single-quad loop. This antenna is more directive, has wide bandwidth and can exhibit up to 2-dB gain over a dipole.

The poorest choice for the QRPer is the vertical antenna. The vertical suffers two defects when compared to a dipole. It is highly susceptible to man-made QRN, notably power-line noise. For a vertical to have the same radiation efficiency of a dipole, a good radial system is required. Amateurs lacking space for beams or dipoles might consider the Cushcraft R-3 tuned vertical, which requires no radials and approaches the efficiency of a half-wave dipole.

Do not skimp on the coax. Use the best grade of RG-8 you can afford. We are not interested in power capability, but in achieving the lowest attenuation possible. The ham with an amplifier will not miss a couple of watts heating his coax as much as the QRPer running 5 W will. For portable operation, RG-8X may be used where its light weight and ease of handling offset the increase in attenuation. Make all connections clean and weatherproof. Strive for the highest possible efficiency in both feed line and the antenna.

Operating Tips

One may wonder how a DX station can hear a 5-W signal when megawatts are coming at him. But hear it he does, and more often than not the experienced QRP operator will get through those pileups to snag the rare DX station. To do this, however, the operator requires some knowledge of tactics used by successful stations.

First, and most important, listen before using your key or mic. Is he working stations by call area or at random? Is he picking up tailenders? Is he listening high or low, and how wide is the split? All of these things can only be learned by listening. Spend five, even 10 minutes on your receiver before you begin to transmit.

Second, invest in a memory keyer. You're going to send your call a number of times, and it's much easier to do so by pushing a button instead of wearing out your wrist. Send your call at a slightly slower speed than the DX station is transmitting.

Third, on phone, use standard phonetics. The ham on the other end doesn't have time to figure out cute call signs, and will ignore you. In addition, use some form of speech processing to boost your average power, but don't overdo it. Too much is far worse than too little.

Fourth, time your calls. This is most important for QRP operators. Don't try to be first to hit the keyer or PTT switch. Normally, everyone will send their calls all at once, pause, then try again. When you hear that pause, slip your call in just once. That's all you have time for. Do this correctly, and you may get through on the third or fourth call.

Finally, know when to quit. Everyone has days when the propagation is wrong or Lady Luck is against you. Believe it or not, the world will not end if you fail to work the DX in that pileup.

R$_x$ for Success

With only 5 W, there is no way you're going to blast an opening into a crowded band. You don't have an "afterburner" to kick in under heavy QRM conditions, or the power to make your own propagation. So, you need a change in operating style.

The first habit you will break, and soon forget, is calling "CQ." In fact, "CQ" and "CQ DX" will just about disappear from your vocabulary and keyer. With full legal power, a "CQ" in any direction will get you contacts. QRP will never bring the same results. For those unwilling to change this operating habit, the kiss of death is on their QRP career.

There are several ways to increase your chances of success. First, have a good beam antenna. Second, sign your call with /QRP. This may cause stations to call you out of curiosity. The idea is to let everyone know, up front, why you're not 40 dB over S 9. However, most hams will not answer a weak "CQ" unless your call begins with something like S79, VK0 or T32.

The single-most-effective QRP operating technique is search-and-pounce. Search-and-pounce is simply tuning carefully through each band until you find a station to work. Most of the stations you work will be calling "CQ," or you will nail them as they finish a QSO.

---

*1290 Puget Dr E, Port Orchard, WA 98366

Work the station with a moderate-to-loud signal. Since the sensitivity of most QRP receivers outstrips the effective range of their transmitter, a signal that is very weak may be impossible to work. Propagation is a reciprocal thing, and if the station on the other end is S 1 running a kilowatt, imagine what 5 W will sound like. Actually, there will be no sound at all — you simply will not be heard. This condition is more prevalent on 80 and 40 meters, where antennas and propagation tend to work against the QRPer.

If you become involved in a marginal contact, don't prolong it. The other operator did you a favor by coming back and will not get much enjoyment out of the QSO if you're only 3 3 9 at his end. The place to tell him all about your rig, antenna and the weather is on your QSL card.

A fact of QRP life, and one of its more frustrating aspects, is that you are going to get stomped on occasionally — whether it's deliberate bad manners, carelessness or simply that the station firing up on frequency can't hear you. Sometimes, you can operate through the QRM, but generally it's the end of the QSO.

For those of you who chase DX (and who doesn't?), listening on the local DX repeater is a good way to expand your search-and-pounce technique. If you do spot a bit of DX, work him first, then announce his frequency over the repeater. Do it the other way around and you may find yourself hip-deep in "big gun" stations.

Another prime requirement for being able to work DX (or anyone else) on a consistent basis is at least a working knowledge of propagation. All of the major amateur publications have monthly propagation charts. They use different formats, so different interpretive techniques are applicable to each. All of these charts are prepared several months in advance of publication; you should be able to update their information to make allowance for current conditions. There are two ways to do this. One is to monitor the WWV propagation forecast at 18 minutes after each hour. These recordings provide real-time information to update your monthly charts. A second method is to subscribe to one of the DX bulletins. Printed on a weekly or biweekly basis, all are excellent indicators of relatively current propagation conditions.

The three bands providing the bulk of activity for QRP are 20, 15 and 10 meters. When the 10-meter band is open, there is little difference between 5 and 500 W. It can exhibit rapid shifts in propagation, however, which can be disconcerting to even experienced hams. Twenty meters is the most consistent band, providing openings to some part of the world day and night.


Jim Ford, N6JF, of Costa Mesa, California, went the low-power route, and he's glad he did. Using the BP6 "Hamcation Rig" (April 1983 *QST*) as a guide, Jim built his own QRP rig, which he operates with great success on 10 MHz.

Forty and 80 meters are less consistent producers because of their more-seasonal nature and higher levels of QRN and QRM. Both tend to be winter bands, but can produce results any time of year. The best DX time is 30 minutes before and after local sunrise or sunset. Also, the 30-meter band is excellent for QRPers. Its propagation lies midway between 20 and 40 meters, and only limited-power (250 W) operation is permitted.

Most QRP CW operation is around 40-60 kHz up from the bottom edge of any band. Most phone operation tends to be in the Advanced and Extra Class subbands. Stay out of the Novice segments; beginners have enough problems without the added difficulty of having to copy less than S 9 signals.

The QRP Contester

For many, contesting is just one interesting facet of Amateur Radio. For others, contests *are* Amateur Radio. Noncontesters and contesters alike may view operating a contest with a QRP rig as the ultimate insanity. Actually, the reverse is true. Most of us don't have the megabucks required to put together a top-drawer, big-gun, killer-type contest station. However, most hams can afford a first-class QRP station. Since QRP rigs are relatively inexpensive, you can afford to invest more in antennas — a deciding factor in contesting.

Many contests have a separate single-operator, all-band QRP category. Thus, you need only compete against other QRP operators. However, winning still requires maximum doses of perseverance and a large amount of skill.

Contesting effectively with QRP requires the application of several important techniques. At the beginning of the contest, work the strongest stations. Then, work the progressively weaker stations. In addition, don't waste too much time calling any one station. If he hasn't come back to you by the fourth call, move on. You can work him later when the pileup is reduced. An exception to this would be near the end of the contest when that DX station represents a new multiplier.

Instead of tuning up and down the band, start at the high end and work stations as you go to the low end. When you hit the bottom edge, quickly tune up to the top and start down again. This will maximize your time on all portions of the band. Those proficient with a search-and-pounce technique will have a QSO rate almost equal to most stations calling "CQ." Also, new stations will appear and disappear with great rapidity, so don't worry about working the band dry.

Another rule for the QRPer is to work the MUF (maximum usable frequency). Work the highest frequency that is open in the area you want to cover, based on WWV or other propagation information. Operating at or close to the MUF reduces path loss and maximizes your 5-W signal.

In a DX contest, know the areas that are easiest to work, and concentrate on those at the start of the contest. Work the more difficult areas during the last 24 hours. For example: Generally, Japan, Oceania and Europe can be worked from the West Coast on 20 meters in the morning. For the QRPer, however, it is more productive to work Japan and Oceania Saturday morning and Europe Sunday morning. By the last day, Europeans will have worked out much of the Eastern seaboard and will respond more quickly to a call from the West Coast.

In any contest, but more particularly in a DX contest, establish some type of game plan. Spend some time consulting propagation charts, and write up a time-versus-frequency plan for your own use. Decide which areas you will cover at what times and the best band for each combination. This plan should be used as a guide for each hour of operation. The most productive directions will be based on your experience and an examination of previous contest scores.

Next to your log, the most important record to keep is the dupe sheet. Duplicating contacts means wasted effort, lost points and less-productive operating time. Since, as a QRP station, you will be operating 99% of the time in a search-and-pounce mode, your dupe sheet must be as current as your contest log. There are as many different dupe sheets as there are contests, so use one that fits your needs.

Finally, keep the proper perspective and attitude before, during and after the contest. Above all, don't worry about the big-gun station down the block. You're not competing against him, only against other QRPers.

From September 1981 QST, p 11:

Experimenting for the Beginner

Experimenting is half the fun of Amateur Radio! QRP (low power) gear is great for the newcomer to this fine art. Here's how to get started.

By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250
Luther, MI 49656

What's this? You've never built a piece of amateur equipment? You don't know anything about circuits, so you just operate? Well, if this description fits you, at least half the thrill of being a ham has eluded you! For many of us the greatest excitement in amateur work came from building and using that first transmitter. There's a special feeling connected with telling the other guy or gal, "The rig here is homemade." If you haven't been able to make this statement over the air, perhaps it's time you did!

Most experimenters start out with relatively simple projects, and rightfully so. In the old days some of us tinkerers enjoyed building one-tube transmitters. Often, the name of the game was "power output." That is, we tried to extract more output power from a single oscillator than the tube was designed to deliver. A number of popular transmitters of this type were described in *QST* by F. Sutter.[1] But today it's prudent to use transistors and to operate them within their safe maximum ratings. QRP equipment (generally 5 watts or less of rf output power) can provide many interesting and exciting hours of operation, and it's easy and inexpensive to build. Therefore, QRP is the theme of our article this month on basic radio learning.

How to Experiment

We need not have college degrees in engineering to conduct experiments in nonprofessional electronics work. We can assemble suggested circuits, test them, learn their characteristics, and then make changes and observe the results. Familiarity with fundamental circuits can lead to circuit improvements and innovations, and perhaps later to some original design work. Many of the early-day inventors of electrical and electronic devices and systems followed this approach, which supports the validity of the precept, "Learn by doing."

We amateurs have the advantage of trying our ideas at home rather than at work. So, if the circuit is a flop, no need to contemplate the unemployment line! Furthermore, if the equipment is a transmitter for one of the amateur bands, we are licensed to put it on the air and to give it a true "environmental test," an advantage not enjoyed by many engineers and technicians.

The simplest approach we can take to experimenting is to adopt the breadboarding technique.[2] This allows us to tack a test circuit together quickly and easily. In the process we cut down on expense and eliminate the chore of laying out and etching a circuit board. The final product may not look like a work of art, but it can be used on the air just as effectively as a commercial-looking version of the same circuit.

Bargain-bag assortments of 1/4- and 1/2-watt resistors are a vital part of the experimenter's workshop. Likewise with assortments of disc ceramic capacitors, trimmer capacitors, volume controls and small electrolytic capacitors. Of course, we need a small pencil type of soldering iron (40 watts), some solder and a few feet of light-gauge, insulated hookup wire. Bargain assortments are often available from Radio Shack, Poly Paks and other prominent vendors. The best deals are often available at Amateur Radio flea markets, so we must be on the alert when browsing at hamfests and conventions.

An important item in our workshop is a VOM (volt/ohm/milliampere meter). Even a low-cost imported instrument will suffice if cost is an important consideration. For rf measurements it is wise to have a VOM that can be used with a

---

[1] Footnotes appear at end of article.



EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS; k = 1000

Fig. 1 — Circuit of a one-transistor QRP transmitter. Fixed-value capacitors are disc ceramic, 50 volts or greater. Resistors are 1/4- or 1/2-watt composition, 10% tolerance. C1 described in text. C2 is a 100-pF mica trimmer. L1 is a 6-μH winding of 34 turns of no. 26 enam. wire on an Amidon or Palomar T50-2 toroid core. L2 is 6 turns of no. 26 enam. wire, wound over L1 winding (see text). J1 is a phono jack, and J2 is a 2-circuit phone jack. Y1 is a fundamental surplus or new crystal for the standard 40-meter QRP frequency (7060 kHz).



Fig. 2 — Details for measuring transmitter output power with a dummy load (R1), an rf probe and a VOM (see text).

homemade rf probe.[3] This will permit us to measure rf voltages in oscillators and transmitters when performing initial checkout or debugging. A frequency counter is very useful to the experimenter, and should be acquired if the expense can be justified.

We will need a dc power supply for our workbench, and for most of our experiments we can manage nicely with a 12-volt, 1-ampere regulated supply.[4] If the output voltage can be made variable, so much the better.

Bargain assortments of transistors, ICs and diodes aren't likely to be of much use to us unless we have a way to locate the defective ones: Most "bargains" of this type contain manufacturer's rejects, and 50% or more of the semiconductors in a bag are often open, shorted or leaky. Therefore, we're better off to buy parts of known quality for each of our experiments. This practice will help us to avoid confusion and despair.

The Simplest Transmitter

How uncomplicated can a transmitter be for experimental work? Factually, a one-transistor oscillator qualifies as a transmitter. Many beginners have had exciting results with such a circuit while operating with only 50 milliwatts (0.05 watt!) of power output. For example, the circuit in Fig. 1 was tacked together one lunch hour in the ARRL lab and was connected to a 28-foot (8.5-m) base-loaded vertical antenna with buried radials. On the third CQ an answer came from a W8 in Ohio. A signal report of RST 569 was received for our 50-mW signal on 7060 kHz. A second QSO with a W2 station in New Jersey netted an RST 589 report!

Y1 of Fig. 1 determines the operating frequency. C2 tunes L1 to the approximate frequency of Y1. If it is set for resonance at exactly 7060 kHz in this example, the cw signal may become chirpy. With this type of oscillator it is best to tune the C2/L2 circuit for the best sounding note consistent with reasonable power output. Maximum power will not coincide with the cleanest cw note when connecting an antenna to this type of oscillator unless very light coupling is used (L2) between the tuned circuit and the antenna. The lighter coupling will, in itself, reduce the available power to the antenna.

The circuit of Fig. 1 can be used on 160, 80, 40 or 20 meters by using a fundamental-cut crystal for the desired frequency. C1 is part of the feedback network and will have to be chosen for the crystal we use. This is because some crystals are more active than others. The more sluggish a crystal is, the greater the feedback voltage required to make the circuit oscillate reliably. Values between 15 and 100 pF are typical for use at C1 in this particular circuit. We can experiment with the number of turns in L2 to extract maximum rf power output from the circuit.

Fig. 2 shows how we can use a 47-ohm resistor as a dummy load to measure the output power. An rf probe (mentioned earlier) and VOM are connected across R1 with the key closed. Output power can be calculated from:

$$P = E^2/R$$

where P is in watts, E is in rms volts and R is in ohms. Therefore, if we measured 1.53 volts across R1, we would have an output power of 50 milliwatts (0.05 W). The accuracy of our measurement depends on the purity of the sine wave from the transmitter. A distorted waveform will



EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS; k = 1000

Fig. 3 — Same circuit as Fig. 1 except that an FET is used at Q1.

yield only approximate power-output readings on the VOM. A 51-ohm resistor could be used at R1, but that is a 5% tolerance (gold-band) value, and would cost more than a silver-band (10% tolerance) resistor. So, we can use a 47- or 56-ohm resistor. Either value is close enough to 50 ohms for our purposes. Here again is an example of the joy of *experimenting* versus designing!

We can also use field-effect transistors as oscillators of the kind illustrated in Fig. 1. The version seen in Fig. 3 contains a dual-gate MOSFET. Output power from this circuit will be somewhat lower than that from the bipolar transistor oscillator of Fig. 1, but plenty of QSOs can be had with this simple transmitter. Other dual-gate MOSFETs could be used in place of the 3N211, such as a 40673.

If we decided to use a VFO to control the operating frequency of the transmitter in Fig. 1, we could make the modifications shown in Fig. 4. Y1 and C1 are removed to prevent oscillation at the crystal frequency. A dc-blocking capacitor (C3) is added as shown. The rf voltage (rms) developed from the base of Q1 to ground (with the VFO connected and operating) should be between 1 and 3 volts for best results. This shows just another way we can experiment with simple circuits.

Additional experiments can be conducted with the one-transistor transmitters by trying various types of transistors in the basic circuits of Figs. 1 and 3. One important transistor characteristic is the maximum operating voltage (V_{ce}), which should never be rated less than two times the supply voltage for cw work. This will allow for the voltage swing (peak to peak) during the rf sine-wave cycle at the collector or drain. If the voltage is allowed to rise beyond the specified safe value, the transistor can "go away" instantly! We must be concerned also with the upper frequency rating of the semiconductor. This is usually specified as f_T. A good rule of thumb for obtaining maximum oscillator or amplifier performance is to use a transistor that has an f_T at least five times higher than the chosen operating frequency. Thus, for 7-MHz operation the f_T should be 35 MHz or higher. Most FETs are rated for a maximum upper frequency in terms of gain. Generally, they are good from audio frequencies up to that limit for amateur experiments.

The maximum safe current of a transistor is important to us also. This is specified as I_c (collector current) for bipolar transistors, and as I_d (drain current) for FETs. At no time should we allow the transistor to draw more current than the specified safe value. In fact, it's wise to operate the device somewhat below (25% or more) that maximum value. This will help to prevent failures from excessive heating of the transistor junction.

A good safety rule is to do all initial circuit testing at reduced operating voltage. For a 12-volt circuit we might want to start our testing at 6 or 8 volts until we were certain that there were no wiring errors. If things seem to be working normally, we can increase the supply voltage to 12.

An "Experimenter's Special"

Thus far we've discussed two rather unprofound transmitter circuits. Once we've finished tinkering with them we may want to move ahead to something more spectacular in simple circuitry. Fig. 5 shows the circuit of a two-stage, solid-state QRP transmitter that was designed by Wes Hayward, W7ZOI.[1] Some modifications have been made for this article, but the circuit is essentially as he designed it. This experiment should give us hours, weeks or even months of fun in the workshop and on the air. It delivers slightly more than 1 watt of output to a 50-ohm antenna, and can be made to operate on any band from 160 to 10 meters by using the parts values specified in Table 1. Actually, this is a three-transistor circuit if we count the keying transistor, Q3. But, there are so few parts in the circuit that we can assemble it in short order.

Q1 is a tuned-collector crystal oscillator. Its output energy is fed to the base of Q2, which operates as a Class C amplifier. A pi network (C3, L3 and C4) serves as a harmonic filter (low pass) rather than as an impedance-transformation network, as is more often the case with tube and transistor output amplifiers.

Q3 functions as an electronic switch. When its base resistor is grounded by the cw key it conducts and allows the dc to reach the amplifier stage, Q2. This method helps to reduce the possibility of shorting out the 12-volt supply accidentally, as could happen with the circuits of Fig. 1 and 3 where J1 is in the 12-volt line.

Fundamental crystals are used on 160, 80, 40 and 20 meters. For operation on 15 and 10 meters we will need to use third-overtone crystals at Y1. The oscillator is permitted to run continuously, and keying is applied only to the amplifier, Q2. This prevents chirp on 15 and 10 meters, which would occur if the oscillator stage were keyed.

Feedback capacitor C5 is used only on 160 and 80 meters. All of the component values are the same for 10 and 15 meters. Oscillator trimmer C1 has ample range to provide resonance on both bands.

Construction Thoughts

Experimentation can continue after the transmitter is built and tested — we may want to try our skills at cabinet making, or the unit can be enclosed in a small commercial case, such as one finds at Radio Shack stores. But we can use pieces of double- or single-sided circuit board to fashion a homemade cabinet. We can flow a continuous bead of solder (darned expensive stuff these days!) along the inside seams (corners) of the box to join the side and bottom walls. The lid can be a U-shaped piece of metal (furnace ducting or aluminum). Spray paint or contact paper may be applied to the outer surfaces



Fig. 4 — Method for attaching a VFO to the circuits of Fig. 1 and Fig. 3. Q1 is thus changed from an oscillator to an amplifier.

Table 1

Fig. 5 Circuit Component Values for Various Bands

	C1 (pF)	C2 (pF)	C3 (pF)	C4 (pF)	C5 (pF)	L1	L2	L3	R1	RFC1
160 m	400	1800	1800	1800	360	73 t No. 28 T50-2	8 t	30 t No. 26 T50-2	18 Ω	30 t No. 28 FT-37-61 (50 μH
80 m	400	100	750	750	200	43 t No. 26 T50-2	5 t	21 t No. 22 T50-2	39 Ω	21 t No. 28 FT-37-61 (25 μH
40 m	180	100	470	470	—	35 t No. 26 T50-2	4 t	14 t No. 22 T50-2	39 Ω	30 t No. 28 FT-37-63 (15 μH
20 m	60	33	210	210	—	27 t No. 24 T50-6	3 t	12 t No. 22 T50-6	47 Ω	30 t No. 28 FT-37-63 (15 μH
15/10 m	60	33	105	130	—	17 t No. 24 T50-6	3 t	9 t No. 22 T50-6	47 Ω	30 t No. 28 FT-37-63 (15 μH

Toroid cores are used in L1, L2 and L3. These are powdered-iron cores available from Amidon Associates and Palomar Engineers (T50-2, etc.). RFC1 is wound on a small ferrite core (FT-37-67), and so on), available from same suppliers. The letter "t" signifies the number of wire turns in the winding.


OSC.
AMP.
2N2222
Q1
B
C
E
Y1
4.7 k
C5
10 k
C2
220
C1
L1
L2
R1
2N3553
Q2
*
RFC1
0.1
L3
C3
S.M.
C4
S.M.
50-Ω
ANT.
B
E
C
Q1, Q2, Q3
(BOTTOM)
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k = 1000
Z
Q3
2N4036
DC SWITCH
4.7 k
1 k
0.1
J1
KEY
220
X
Y
C6
470 µF
25 V
+12 V
* USE HEAT SINK
S.M. - SILVER MICA
(POLYSTYRENE ALSO SUITABLE)

Fig. 5 — Circuit of the W7ZOI "Universal QRP Transmitter." It can provide up to 1.5 watts of rf output when using a 12- to 14-volt dc supply. Fixed-value capacitors are disc ceramic unless otherwise indicated. Resitors are 1/4- or 1/2-watt composition, 10% tolerance. Values not given are listed in Table 1. C6 is electrolytic or tantalum. C1 is a mica trimmer. Q2 is a Motorola transistor, but other brands and numbers with equivalent characteristics can be used.


TO ANT
L3
C4
C3
0.1µF
Q2
R1
RFC1
220Ω
L1
L2
*
Q1
4.7KΩ
10KΩ
C5
C2
220Ω
TO Y1
KEY
1KΩ
Z
Y
X
Q3
4.7KΩ
+470µF
+12V
NOTE: JOIN PADS X AND Y FOR 10M. JOIN PADS X AND Z FOR 160M-15M USE
*USED ON SOME BANDS. SEE TABLE 1

Fig. 6 — Parts-placement guide for the circuit of Fig. 5. The shaded areas represent an X-ray view of the etched side of the board.

of the box to impart that professional look some of us prefer. Press-on decals are excellent for labeling the controls, but Dymo tape labels are suitable also, especially if they are the same color as the panel.

The circuit of Fig. 5 can be assembled on a sheet of pc board using the type of point-to-point wiring described in an earlier *QST* article[4] if a "masterpiece" is not essential to our purpose. But, if pc-board construction of the classic style is preferred we can duplicate the pattern shown in Fig. 6 and in the Hints & Kinks section of this issue.[5] If point-to-point breadboard assembly is our choice we must be careful to keep the input and output components of amplifier Q2 (Fig. 5) separated from one another. Straight-line wiring (not bunched up) is preferable to achieve this: Too-close spacing can cause unwanted feedback and amplifier instability. All of the rf leads in the circuit need to be kept as short and direct as possible. This is especially important when installing the bypass and coupling capacitors.

Caution: When applying operating voltage to the circuits in this article, *check the polarity!* There is no more effective way to send our transistors and electrolytic capacitors on a permanent leave of absence than cross-polarizing the dc voltage connections! Once you have the misfortune of becoming a member of "Junction Busters, Amalgamated," you'll never repeat your mistake!

A Word About QRP Operation

The 1-watt transmitter of Fig. 5 will be 20 dB weaker in signal strength than your transceiver that delivers 100 watts of output. So if you would be heard at 30 dB over S9 with your 100 watts, you will be only 10 dB over S9 with the QRP rig. Or assume your bigger rig was being heard S9 by the other operator. When you switched to the QRP transmitter your signal would drop to roughly S5 or S5-1/2, depending on the accuracy of the S meter (assuming 6 dB per S unit). So you could still be heard well enough under quiet band conditions to be copied "Q5."

Patience and tenacity are the better virtues we can adopt when running low power. Find clear frequencies on which to call CQ. Don't expect answers from stations with weak or marginal signals, unless they are also using QRP. Unless you're a super operator, it's unlikely that you'll fare very well in DX pileups.

Good antennas are important in successful QRP work. Many first-time QRPers capitulate after a few days of poor results when using mediocre antennas. Erect the antenna high and in the clear, and use a directional, gain type of antenna (beam) on 20, 15 and 10 meters, if you have one available. A good antenna will help to make up for the deficiency in power when using QRP equipment.

The ARRL would welcome clear photographs and reports of the best DX worked with the circuits of Fig. 1 and Fig. 3. Perhaps if we can get enough input on this subject we can run a page of photos, calls and DX records in an issue of *QST*. We



Fig. 7 — Photograph of the assembled kit version (note 7) of the W7ZOI QRP transmitter, as laid out and built by WA0UZO. The panels are made from pieces of double-sided pc board. The dimensions (HWD) are 7/8 × 2-1/4 × 3 inches (22 × 57 × 76 mm).



Etching pattern for the Universal QRP Transmitter. Black represents copper. The pattern is shown actual size from the foil side of the board.

hope you will soon be able to say, "I've built my first piece of amateur gear, and it works great!"

Notes

[1] F. Sutter, "'The Runt Sixty' and the 'QSL Sixty,'" *QST*, Sept. 1939, p. 50.

[2] The expression "breadboard" has confused some newcomers to Amateur Radio. It originated in the early days of the amateur service when hams built their transmitters on wooden foundations, such as the ends from orange crates. The kitchen breadboard became popular for that purpose, and thereafter any wooden chassis base was called a breadboard.

[3] Details for building a simple diode rf probe can be found in the measurements chapter of the past several editions of *The Radio Amateur's Handbook*.

[4] D. DeMaw and R. Shriner, "A Simple Utility Power Supply," *QST*, Nov. 1979. Parts kits available from supplier in note 7.

[5] W. Hayward and D. DeMaw, *Solid State Design for the Radio Amateur*, (Newington, CT: American Radio Relay League, Inc., 1977), ch. 2, p. 26. This publication is recommended for experimenters because it contains a wealth of basic theory and many practical examples of simple transmitters, receivers and test equipment.

[6] D. DeMaw, "Quick and Easy Circuit Boards for the Beginner," *QST*, Sept. 1979, p. 30.

[7] Etched and drilled circuit boards for the transmitter are available from Circuit Board Specialists.

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.

From September 1979 QST, p 30:

Quick-and-Easy Circuit Boards for the Beginner

Why endure layout agony and the mess of chemicals? Make your own breadboard-style modules quickly. Here's how!

By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250
Luther, MI 49656

If you dread those brown ferric-chloride stains on your clothes, the tedium of etching a circuit board and the puzzlement of laying out a pc-board pattern, this article is for you! There's no rule that suggests a firm need for commercial-quality circuit boards. Sure, the professional stuff looks great with these lines and circles of copper so neatly etched on epoxy or phenolic board material. But, consider the person hours involved in planning a layout, applying the etch-resist tape or lacquer, then etching away the unwanted copper. All of this can become rather futile if the amateur is interested only in testing a circuit on a one-shot basis. A simple breadboard type of assembly will often suffice; time and money will be saved in the process.

But what of the finished product? Sure, nobody really wants an "ugly duckling" to show off at the next club meeting or when hams drop in to visit the shack. However, good looking circuit-board assemblies can be had even when using the non-etch techniques outlined here. An experimental circuit board which has the components neatly in place, "dress-right-dress" fashion, can be a thing of beauty to the beholder's eyes, provided he or she is not an inspector for a government-contract job! Let's examine some ways to make our own non-etched boards.



Fig. 1 — Photograph of the simple breadboard depicted in Fig. 2A. High-ohmage resistors serve as standoff terminals.

The Standoff Technique

The basic foundation for any of the "quickie" boards we shall discuss here is a sheet of copper-clad circuit-board material — the kind we find in proliferation at hamfest flea markets, Radio Shack stores and similar outlets. It need not be clad on both sides, but "double-sided board," as the near misnomer indicates, is suitable also. Our objective in making any circuit board ready for use is to provide a suitable number of electrically isolated conductive islands upon which the various components can be connected by means of solder. At least that is the fundamental principle of *etched* boards. But, alternative methods exist for developing isolated pads or tie points. Regardless of the approach taken to achieve this effect, the name of the game remains the same: Assemble the components close to and above a copper "ground plane." In this type of situation the copper on the board becomes the circuit ground, just as a chassis does when circuit boards aren't employed. The copper plane enables us to make direct ground connections, thereby minimizing the pigtail lengths of the various resistors, capacitors and transistors. Short lead lengths and a quality ground conductor help prevent circuit instability (self-oscillations or parasitics). It is for this reason that many amateur projects call for double-sided pc board: One side is etched and the opposite side is solid copper, except where the various



Fig. 2 — Pictorial view of a circuit board that uses the standoff technique as shown at A. A closeup view of one of the standoff resistors is shown at B. Note how the pigtails are bent. The schematic diagram at C shows the assembled circuit displayed at A.

Fig. 3 — Illustration A shows how isolated pads can be glued to a piece of copper-clad pc board to form a simple breadboard. The equivalent circuit is shown at B. A short wire jumper can be used to join individual pads, as shown just below C3 at A.



components are installed. A small amount of copper is removed around each pc-board hole to prevent short-circuiting the component leads to the ground plane.

The "standoff technique" calls for some more haggling at flea markets. Along with the pc-board material we garner in the swap-and-shop area, we must look for high-ohmage 1/4- or 1/2-watt composition resistors. Values from 220 kΩ to several megohms are suitable. Generally, bags of bargain resistors are abundant. Don't worry if the pigtails are short; this type will be just fine, provided the wire leads are each 1/4 inch (6 mm) long or greater.

The purpose of utilizing high-ohmage resistors is to ensure that they act more like *insulators* than as true resistors. Hence, the higher the resistance the better for our application. As a rule of thumb, the resistor being used as a standoff insulator should have a value that is at least 10 times the circuit impedance or value of resistance used at that circuit point. For example, if a resistor is used as a tie point at the 50-Ω output of a circuit, the resistor should be a 500-Ω type, or greater. In the circuit at Fig. 2C we find that R2 is 5.6 kΩ and R3 is 27 kΩ. We will make the standoff resistor, E4, 10 times greater than the smallest resistor, R2, or 56 kΩ. Any value higher than 56 kΩ will work nicely, too. Our only concern for the value of E3, the +9-volt standoff resistor, is that it is high enough in value to minimize the current drain from our power supply. A value of 220 kΩ would draw only 0.04 mA at 9 volts. This is an insignificant amount, even if a transistor-radio battery served as the power source.

Fig. 2A illustrates pictorially how one might apply the standoff technique to wire the circuit shown at C of Fig. 2. Illustration B demonstrates how the resistor pigtails are bent before the component is soldered to the pc-board material. The base circuitry at Q1 of Fig. 2A is strung out excessively. This was done to reduce clutter in the drawing. In a practical circuit all of the signal leads should be kept as short as possible. E4 would, therefore, be placed much closer to Q1 than the drawing indicates.

R1 and R2 of Fig. 2 actually serve two purposes: They are not only the normal circuit resistances, but function as standoff posts as well. This practice should be followed wherever a capacitor or resistor can be employed in the dual role.

Glue-and-Pad Method

A simple but more time-consuming technique for making circuit boards is illustrated in Fig. 3A. Once again we have chosen a piece of copper-clad pc board as our foundation. The isolated pads consist of small squares of pc-board material, single or double sided. The size of the pads is arbitrary, but the author prefers them to be 1/4 inch (6.3 mm) square. The smaller the pads the more of them can be placed in a given area of the main board. There is no reason the pads can't be rectangular or round. The format will depend on personal choice and the cutting technique available to the amateur.

A power or "armstrong" type of hack saw is perhaps the best tool for cutting the board material into squares. If you have a friend who has access to a model-shop shear, perhaps he will be willing to cut a supply of squares for you during his lunch hour. Phenolic-based pc board will shatter in a shear, but glass-epoxy board with a cloth base will cut evenly when sheared.

Once the squares are prepared they can be affixed to the main board by means of epoxy cement. It can take as long as 24 hours for the glue to set firmly, depending on the brand and grade of cement used.

Noted *QST* author W7ZOI once suggested an alternative method for gluing pads to a pc board. He mentioned hot-melt glue as a faster agent for attaching the pads to the main board. This type of adhesive is available from hardware stores in small packets. It comes in tubular stick form. A thin slice of the hard glue is shaved from the stick by means of a knife. The glue slice is placed between the bottom of the pad and the top surface of the main board. A soldering-iron tip is pressed against the pad, held there until the glue melts and spreads, then removed.

The shortcoming of this approach is that the glue softens each time a component is soldered to a pad. It requires more than casual care when assembling the circuit components. Epoxy glue will not melt during the soldering process. Also, the completed module will remain intact much longer if epoxy cement is used.

A comparison between the practical and schematic circuits for a simple half-wave hamonic filter is provided in Fig. 3. The pictorial version shows how we might mount the parts when using the glue-and-pad technique. There are some unused pads in the foreground.

Saw-Slot Boards

For those who subscribe to the armstrong method discussed earlier, a hack saw can be used to cut through the copper on a section of pc board to form isolated pads. This concept was popularized by the author and W1ICP in a *QST* beginner's series which ran from April through September 1974. An example of this technique is given in Fig. 4. The copper must be cut *completely* away where each dark line is shown. This will prevent short circuits between adjacent pads. A hobby Moto Tool can be employed to cut the grid seen in Fig. 4. If this is done, a straight-edge guide will be necessary if a neat job is desired.

If Etching Is Your "Thing"

A universal pc breadboard can be etched and used many times if one does not mind dabbling with etchant chemicals. A few brown stains here and there on one's garments could fit nicely into our contemporary world of fashion, so maybe the etching technique isn't all that bad!



Fig. 4 — Saw-blade scoring of copper-clad pc board material provides isolated pads in this drawing.

Fig. 5 — Suggested pattern for a universal breadboard that can be etched as shown, not to scale. A +V and a ground bus are provided for easy access along the length of the board. See the "Hints and Kinks" section of this issue for a full-size pattern template.



The pattern shown in Fig. 5 is arbitrary. It suits the author's needs handily for circuit experimentation. The smaller pads are suitable for mounting transistors, diodes and other discrete components. The long conductors along the edges and one side of the breadboard are laid out to function as plus-voltage and ground buses. The +V foil has branches that extend through four groups of pads. The ground conductor has similar branches that pass through alternate groups of pads. This helps to keep lead lengths on the various parts to a minimum.[1]

We can use ordinary masking tape as the etch-resist material. Cover all of the copper surface with a layer of tape. Press the tape firmly against the copper by running a smooth object, such as the side of a lead pencil, back and forth across the tape. Next, draw the pattern on the tape. An X-acto knife can be utilized to remove tape sections where the copper must be etched away. All that remains for board preparation is 15 to 30 minutes of etching in ferric-chloride solution. *Do not allow the etching solution to contact your eyes or skin. If it does, wash it off immediately with clear, cool water.*

To ensure reasonable longevity of this type of breadboard, material with heavy-gauge copper laminate should be used. Glass-epoxy insulation is also recommended. If the copper is too thin, repeated soldering will loosen the copper, and stress on the pads will separate them from the main board.

Some Closing Comments

Needless to say, earlier comments about brown stains on our clothing were offered in a purely jocular vein. Avoid allowing the etching chemicals to splash on your clothing: The stain will be permanent!

There are probably a number of additional methods for fabricating circuit boards quickly and simply. No credit is claimed for originality concerning the procedures described in this article. The purpose of this presentation is to illustrate some of the more common approaches to breadboard fabrication without chemicals. But of greater importance, we've tried to stimulate confidence among those who were heretofore unwilling to engage in home-project work through fear of circuit-board layout and etching. Let's compare brown stains later if we should use ferric chloride. If not, perhaps we can swap high-value resistors or sharpen saw blades together!



Black represents copper; the pattern is shown at actual size. The board is single sided (copper on one side only), shown from the foil side, and is a universal breadboard pattern suggested by DeMaw (see Fig 5).

---

[1] Negatives and circuit boards for the breadboard are available from Circuit Board Specialists.

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.

From October 1987 QST, p 24:

Stalking Those Fugitive Components

Specialty components appear hard to find for those who aren't experienced gleaners. Let's learn where and how to obtain some of these bread-and-butter items.



By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250
Luther, MI 49656

What's this you're saying? You would build more ham gear if only you could obtain the necessary components? I receive dozens of letters to this effect each year. Most of them seem to be from the newer hams who have yet to learn the fine art of foraging for those seemingly elusive parts. Some correspondents are critical because my *QST* articles are not based on using parts that can be purchased at Radio Shack stores. Sure, Radio Shack stocks a lot of things that are useful for building projects, but many of the circuits we amateurs want to build require components that Radio Shack will never carry. A designer is severely restricted if he has to rely on any single supply source. At best, his output will soon be reduced to rinky-dink projects.

What, then, might you do to solve the annoying parts-procurement problem? This subject has been addressed frequently in *QST*, but only in general terms. That is, the authors did not focus on specialty items that many of us need from day to day. This article is aimed at those unique parts that we do not find at the corner parts store. All you need is some ambition and a few postage stamps to equip yourself with the means to get the parts highlighted here.

Some of the suppliers I list in this article have many parts to offer in addition to those discussed here, and numerous other suppliers exist. I concentrate in this article on those dealers from whom I purchase most of my parts and materials. I consider their prices fair and generally below the figures set by new parts distributors that aren't in the surplus business. I have experienced neither poor service nor rip-offs from any of the dealers listed, but neither the ARRL nor I endorse them. As the saying goes, "let the buyer beware."

Locating Component Sources

I watch for some of the smaller display ads in *QST* and other amateur publications, and keep tabs on the classified ads in the various magazines. That is where you'll often see information that can lead to a free catalog of bargain parts. I respond to every ad of that type. Consequently, I have stacks of catalogs. It is a practice I recommend to all of you who enjoy building amateur equipment. There is scarcely a component I can't find for my projects, if I scan the pages of these mail-order catalogs.

Writers (myself included) often recommend ham-radio flea markets as a source of parts for home use. Flea markets are, indeed, wonderful places to look for certain items. But, owing to the infrequency of flea-market events in any given region, procuring parts by that means is a long-range situation at best. I depend on flea markets mainly to stock up on items for future, unplanned projects. For example, if I see a super bargain on 2N2222s, polystyrene capacitors or 2200-µF filter capacitors, I buy them for later use. This practice also enables me to help other hams in the area, should they have a sudden need for something I have in my goodie cache.

Parts and materials never appear magically! We may daydream until doomsday, but that won't yield results. We must also innovate as the demand dictates.

Equipment Cases

Consider the low cost and simplicity, for example, of fashioning a small project case from galvanized furnace-ducting material. Most plumbing and heating shops will give you scraps or pieces from stock, or they may charge you a few cents per pound for the material. A large pair of tin shears can be used to cut the sections of metal to shape, and bending can be done by hand over any right-angle form. The cabinet walls and top can be soldered together, or fastened with no. 6 sheet-metal screws. The completed cabinet can be spray painted with sandable gray primer, sanded and then coated with your favorite color of paint for the finishing touch.

Large cabinets, such as those used for antenna-matching networks, can be fashioned from tempered Masonite®. This material can be painted any color you prefer. The front panel can be made from an aluminum cookie sheet, available at most variety stores. There is no need to contain a Transmatch in a shielded cabinet, since it does not generate TVI. The signal going into the Transmatch should already be clean!

I have mentioned many times the ease and low cost of making small boxes from sections of single- or double-sided PC board. The cost of any of these homemade enclosures is substantially less than that of a commercially made box, and the materials are available locally. These methods permit almost instant construction of an equipment case.

Magnet Wire

Many hams ask me where they can find magnet wire. I must say that the market has, for the most part, dried up with respect to magnet wire. Radio Shack sells small spools of enameled wire, but only in a few popular gauges. Jug Wire Co in New York was my primary source for magnet and bare bus wire, but a recent notice from Jug indicated that they were going out of business.

What can you do to solve this problem? First, check with your local electric-motor repair shops. The operators are often willing to reel off a reasonable number of feet of the wire you need, and at a nominal cost. Here, again, use your initiative.

When I first became a ham, it was common practice for my colleagues and me to acquire old power transformers just for the purpose of removing the magnet wire from the windings. The same was true for old dynamic speakers from junked radios. The speaker field coils contain hundreds of feet of small enameled copper wire! Still another source of magnet wire is the field coils of large, low-resistance dc relays—12- and 28-V units in particular. Generally, the larger the relay and the lower the field-coil resistance, the larger the wire gauge. Look for these relays at flea markets. They can be available for 25 cents or less.

Another excellent source of magnet wire is picture-tube yokes from discarded TV receivers. The vertical- and horizontal deflection coils contain many feet of usable sizes of wire.

Litz Wire

Litz (short for *litzendraht,* which means "stranded wire") wire is desirable for winding small LF, MF and HF slug-tuned coils. It provides a higher Q than plain enameled wire. This is because many strands of enameled wire are used to form a cotton- or silk-covered conductor. The additional surface area afforded by multiple conductors offsets *skin effect*—the tendency for ac to flow at or near the surface of a conductor, resulting in greater ac resistance with rising frequency. I have never seen Litz wire offered in surplus equipment catalogs. I obtain my Litz wire by purchasing old RF chokes and slug-tuned coils that are wound with it. Many WW II power RF chokes contain Litz wire, and you may want to consider this method of garnering some.

Coil Forms and Insulating Material

Blank slug-tuned coil forms are currently too expensive to consider for most amateur projects. There are some surplus bargains, however, and you should watch for them. Stock up on these forms should you see them at flea markets, but be aware of the effects of improper core material on operating frequency. Low-frequency cores will spoil the Q of an HF or VHF slug-tuned coil. The same is true of improper toroid-core material. A relative test of coil Q may be made by winding a coil on an unknown form, then placing a silver-mica or variable capacitor in parallel with the coil to obtain resonance at a desired frequency. Check the tuned circuit with a dip meter. If a good dip can be had with the dipper coil a fair distance from the test coil (say, one inch), the Q is reasonably high. If, however, the dipper must be coupled tightly to the test coil to obtain a dip (usually shallow at best), the Q is probably too low to consider for your circuit. In other words, the farther the dipper coil is from the test coil, consistent with a deep dip reading, the higher the Q of the coil.

Homemade fixed-inductance coils can be wound on plastic tubing and rods at a low cost. Included are power-line RF chokes, antenna traps and antenna-loading coils. First, check the scrap department of your local plastics outlet for odd-lot bargains. Such materials as Teflon®, Delrin, polystyrene, Plexiglas™, PVC, Tenite® and Lexan® are often available in small pieces at attractive prices. You may also obtain a catalog from United States Plastic Corp in Lima, Ohio, a mail-order house that has tubing, rod and sheeting of all types (see listing at the end of this article).

Feed-line spreaders can be made inexpensively from such materials as hair curlers, plastic clothespins, sections of plastic coat hangers and even ballpoint pen bodies. Again, I stress the value of being innovative!

Special Capacitors

I've read many laments about how "impossible" it is for some *QST* readers to locate high-voltage disc-ceramic capacitors, polystyrene capacitors, NP0 capacitors and even silver-mica capacitors. These items are *widely* available from the surplus-parts vendors. I must admit, however, that large transmitting variable capacitors *are* scarce (and extremely expensive). Radiokit seems to be the main outlet for large variable capacitors. When the Cardwell Corp bought the tooling and stock of E. F. Johnson and Hammarlund several years ago, it seemed that a variable capacitor monopoly was taking shape. The James Millen Co was the only other major manufacturer of these parts and, to complicate matters more, Millen went out of business, too. It was a sad day for Amateur Radio! You may still be able to obtain Millen capacitors from Radiokit. Our best hope is to remove large variable capacitors from surplus radio gear, such as WW II command transmitters and BC-191/BC-375E transmitter tuning units. Fair Radio Sales in Lima, Ohio is worth checking for these units and other large WW II electronics equipment. Their catalog will fill many of you older hams with nostalgia!

The Joys of Stripping

Lest someone misunderstand, I refer to radio parts! When Lew McCoy, W1ICP, was the Beginner and Novice editor for *QST*, years ago, he constantly stressed the value of stripping parts from old TV and radio sets for use in ham projects. I'm sure that many of you recall his "transmitters from old TV sets." We at ARRL HQ often wondered why he never made a TV set from *an old transmitter,* but he refused the challenge when it was offered to him! Nonetheless, his advice in those days was sage. Even today we can glean countless excellent small parts from old TV and transistor-radio sets. I saw six table-model TV sets for sale last fall at the Hudsonville, Michigan, ham flea market. The owner was asking 25 cents apiece for the sets! Many PC-mount fixed and slug-tuned coils are found in TV receivers, in addition to a host of resistors and capacitors. Also, you can



salvage many potentiometers and switches, as well as a variety of hardware to add to your stock of nuts and bolts.

Pocket-size transistor radios are loaded with small resistors and capacitors. How many of these little radios have you thrown away when they became defective? Consider the parts you could have salvaged for later use. Discarded AM and FM receivers also contain small variable capacitors that can be used for homemade receivers and QRP transmitters. The IF transformers can be used as is, or can be rewound for other frequencies. Not only can you increase the bulk of your parts larder by stripping TV sets and transistor radios, you will have a nice pastime for those rainy or snowy evenings in winter. Solder wick or solder suckers are invaluable for this job.

Source Listing

Table 1 lists a number of hard-to-find components keyed to the suppliers that stock them. The dealer identification is given at the bottom of the table. I have identified specific components that are offered by these suppliers, but they carry many additional items. Their catalogs are worth adding to your reference library. Remember that quantities and specific values may be limited, depending on the supplier.

Some Final Comments

Although this month we haven't covered theory, applications or a practical project, I feel that parts procurement is an important part of construction. I have addressed those parts that readers seem to have the greatest difficulty locating. Perhaps this article will reduce the number of inquiries I receive!

Unfortunately for us amateurs, some of the suppliers listed specify a minimum order. In such instances, it is sometimes convenient to pool your order with those of other hams in your area. This may require some salesmanship on your part, but it can be done. Good luck in stalking those fugitive components!

ARRL Parts Suppliers List

B,E,J,L,M,W,Y
A&A Engineering
2521 W LaPalma Ave Unit K
Anaheim, CA 92801
714-952-2114
*sase

A,B,C,E,G,H,I,J,K,L,M,N,S,X,Y
All Electronics Corp.
15004 Oxnard Street
Van Nuys, CA 91411
800-826-5432
*free **$10

A,C,E,I,K,L,S,X
Allied Electronics
401 E 8th St
Fort Worth, TX 76102
800-433-5700
**$25

A,B,C,D,E,G,H,I,J,K,L,M,U,X,Y
Alpha Electronic Laboratories
705 Vandiver, Suite A
Columbia, MO 65202-2099
314-874-1514
*free

B
Amidon Associates, Inc.
12033 Otsego St.
N. Hollywood, CA 91607

A,D,F,G,H, Millen components
Antennas Etc./Unadilla
PO Box 4215
Andover, MA 01810-4215
508-475-7831
*sase

A,E,F,G,I,K,L,S,X
Arrow Electronics
25 Hub Dr
Melville, NY 11747-9828
800-932-7769 fax 516-595-0979
**$25

N,O, facsimile equipment
Atlantic Surplus Sales
3730 Nautilus Ave.
Brooklyn, NY 11224
718-372-0349
*$1

I,K,M,T,U
ATV Research, Inc.
13th & Broadway
Dakota City, NE 68731
402-987-3771

Avatar Magnetics
see Ronald C. Williams

A,D,H
Barker & Williamson
10 Canal St.
Bristol, PA 19007
215-788-5581

A,B,E,G,H,I,J,K,L,M,N,U,X,Y
BCD Electro
PO Box 450207
Garland, TX 75045-0207
214-343-1770 fax 214-343-1854
*$1/year

A,B,C,D,E,G,H,I,W,
Circuit boards for ARRL projects, kits
Circuit Board Specialists
PO Box 951
Pueblo, CO 81002-0951
719-542-4525
*free

A,B,C,E,I,K
Circuit Specialists, Inc.
PO Box 3047
Scottsdale, AZ 85271-3047
602-966-0764
*$1 **15 (mail orders)

A,B,D,E,H,I,T,W
Communications Concepts, Inc.
508 Millstone Drive
Xenia, OH 45385
513-426-8600 fax 513-429-3811
*free

L,S,tools
Contact East, Inc.
335 Willow Street
N Andover, MA 01845
508-682-2000
*free

blowers
Cooltronic
1700 Morse Ave
Ventura, CA 93003
805-642-8521
**$50

D,E,I,M,H,X
Peter W. Dahl Co, Inc.
5869 Waycross
El Paso, TX 79924
915-715-2300

F
Davis RF
PO Box 230
Carlisle, MA 01741
508-369-1738
*$1

A,D,E,F,H,I,K,L,N,S,W,X
Dick Smith Electronics
PO Box 468
Greenwood, IN 46142
317-888-7265

A,E,I,J,K,L,X,Y
Digi-Key Corporation
701 Brooks Ave. So.
PO Box 677
Thief River Falls, MN 56701
800-344-4539
*free

C
E-Z CIRCUIT by Bishop Graphics, Inc
20936 Roscoe Blvd.
Canoga Park, CA 91304
818-773-9081
*free **$25

A,C,E,F,I,K,L,N,S,X
Edie Electronics, Inc
2700 Hempstead Tpke
Levittown, NY 11756-1143
516-735-3330

A,C,D,E,F,G,H,I,K,L,S,X,Y
Electro Sonic, Inc.
1100 Gordon Baker Rd.
Willowdale, Ontario Canada M2H 3B3

A,L
Electronic Distributors, Inc
4900 N. Elston Ave
Chicago, IL 60630
312-283-4800

B
Fine Ferrite Laboratories, Inc
PO Box 395
Woodstock, NY 12498
914-679-2497

D,G,H,I,M,N,Q
Fair Radio Sales Co., Inc.
PO Box 1105
1016 E. Eureka St.
Lima, OH 45802
419-227-6573 fax 419-227-1313
*free **$10

W
FAR Circuits
18N640 Field Ct
Dundee, IL 60118
708-426-2431

J (8-pole crystal filters)
Fox-Tango Corp.
747 S Macedo Blvd
Port St Lucie, FL 34983
407-879-6868
*sase

D
Gregory Electronics
249 Route 46
Saddle Brook, NJ 07662
201-489-9000
*free **$25

A,B,I,K,M,N,T
H & R Corporation
A. Herbach & Rademan Co.
401 E. Erie Ave.
Philadelphia, PA 19134
215-426-1708
*free **$15

I,K
Hammond Mfg. Co., Inc.
1690 Walden Ave.
Buffalo, NY 14225

I,K
Hammond Mfg., Ltd.
394 Edinburg Rd., N.
Guelph, Ontario Canada N1H 1E5

Q
Hi-Manuals
PO Box 802
Council Bluffs, IA 51502
*$1 Catalog req'd

A,B,E,H,I,K,L
Hosfelt Electronics
2700 Sunset Blvd
Steubenville, OH 43952
800-524-6464

B,J,L,Q,W (8-pole crystal filters)
Int'l Radio and Computers, Inc.
751 S Macedo Blvd
Port St. Lucie, FL 34983
407-879-6868
*sase

Y
International Crystal Mfg Co,
PO Box 26330
Oklahoma City, OK 73126
405-236-3741

A,D,F,G,H,
Millen Equipment
James Millen Electronics
PO Box 4215BV
Andover, MA 01810
508-975-2711 fax 508-474-8949

Y
JAN Crystals
2341 Crystal Dr.
PO Box 06017
Ft. Myers, FL 33906-6017
800-526-9825
*free

E
K2AW's Silicon Alley
175 Friends Lane
Westbury, NY 11590
516-334-7024
*free **$10

C
Kepro Circuit Systems, Inc.
630 Axminister Dr.
Fenton, MO 63026-2992
800-325-3878 (out of state)
314-343-1630 (MO)
*free **$15

C,E,F,G,I,K,L,X
Lashen Electronics, Inc.
21 Broadway
Denville, NJ 07834
201-627-3783 **$15

A,L, EXAR XR-2208 IC
Marshall Electronics
20 Sterling Dr
Wallingford, CT 06492
203-265-3822
**$25

F (aluminum and stainless tubing and pipe)
Metal and Cable Corp, Inc
PO Box 117
Twinsburg, OH 44087
216-425-8455
**$50

K,L
MFJ Enterprises
PO Box 494
Mississippi State, MS 39762
601-323-5869

A,B,E,H,M
Microwave Components of Michigan
PO Box 1697
Taylor, MI 48180
313-753-4581 (evenings)
*sase

A,B,C,D,E,F,G,H,I,J,K,L,S,U
Milo Associates, Inc.
4169 Millersville Rd.
Indianapolis, IN 46205
317-546-5456 fax 317-547-1729
*free

mixers, signal processing
Mini Circuits Labs
PO Box 350166
Brooklyn, NY 11235-0003
718-934-4500

A,E,F,G,H,I,L,M,X,Y
Modern Radio Laboratories
PO Box 14902-Q
Minneapolis, MN 55414
*$2

F
Moeller Instrument Co.
Ivoryton Industrial Park
Main Street
Ivoryton, CT 06442
203-767-2104 800-243-9310
**$10

F
Motorola Semiconductor Products, Inc
PO Box 20912
Phoenix, AZ 85036

A,B,C,E,F,G,H,I,J,K,L,S,U,X,Y
Mouser Electronics
2401 Hwy 287 N
Mansfield, TX 76063
800-346-6873
*free **$20

E
National Semiconductor Corp
2900 Semiconductor Dr
Santa Clara, CA 95052-8090

A,D,E
Oak Hills Research
4061 N Douglas Rd
Luther, MI 49656
*sase

A,B,C,D,E,F,G,H,I,J,K,L,M,N,S,T,U,W,X,Y
Ocean State Electronics
PO Box 1458
Westerly, RI 02891
800-866-6626 fax 401-596-3590
*free **$5

A,E,F,L
ORA Electronics
9410 Owensmouth Ave
Chatsworth, CA 91311

B
Palomar Engineers
PO Box 455
Escondido, CA 92025
619-747-3343
*free

A,D,X
Pasternack Enterprises
PO Box 16759
Irvine, CA 92713
714-261-1920
*free

T
PC Electronics
2522 S. Paxson Lane
Arcadia, CA 91007
818-447-4565 fax 818-447-0489
*free

B
Philips Components (Ferroxcube)
Mt Marion Rd
Saugerties, NY 12477

A,L
R & D Electronics
1224 Prospect Ave
Cleveland, OH 44116
216-621-1052

A,D,E, Electron tubes and RF power transistors
R.F. Gain, Ltd.
116 South Long Beach Rd.
Rockville Centre, NY 11570
800-348-5580

A,B,C,D,E,F,G,H,I,J,K,L,S,U,W,X,Y,Z
Radiokit (mail)
PO Box 973
Pelham, NH 03076
Telex: 887697
*$1

Radiokit (store)
15 Londonderry Rd, Unit 8
Londonderry, NH 03053
603-437-2722

A,B,D,E,F,H
RF Parts Co.
1320-16 Grand Ave
San Marcos, CA 92069
619-744-0720
*free **$20

D,Y
Sentry Mfg., Co.
Crystal Park
Chickasha, OK 73018
405-224-6780
*free

E
Silicon General, Inc.
11861 Western Ave
Garden Grove, CA 92641

(Mechanical components and metal stock)
Small Parts, Inc.
PO Box 381966
Miami, FL 33238
305-751-0856
*free **$12

A,D,F,J,Y
Spectrum International, Inc.
PO Box 1084
Concord, MA 01742
508-263-2145

A,M,N
Star-Tronics
PO Box 683
McMinnville, OR 97128
503-472-9716
**$4

M,N
Surplus Traders
PO Box 276
Alburg, VT 05440
*$1

K,H
Ten-Tec, Inc.
Highway 411, E.
Sevierville, TN 37862

I
Toroid Corporation of Maryland
6000 Laurel-Bowie Rd.
Bowie, MD 20715-4037
301-464-2100
*free

A,G,O,tubes
Typetronics
PO Box 8873
Ft. Lauderdale, FL 33310
*sase

F
US Plastic Corp
1390 Neubrecht Rd
Lima, OH 45801
800-537-9724

I,Z
Ronald C. Williams W9JVF
(Avatar Magnetics)
1408 W Edgewood Ave
Indianapolis, IN 46217

A,E,F,T,W
Wyman Research, Inc.
Box 95, R.R. 1
Waldron, IN 46182
317-525-6452

Chart Coding

A—New Components
B—Toroids and Ferrites
C—Etched Circuit Board Materials
D—Transmitting and Receiving Materials
E—Solid-State Devices
F—Antenna Hardware
G—Dials and Knobs
H—Variable Capacitors
I—Transformers
J—IF Filters
K—Cabinets and Boxes
L—General Supplier
M—Surplus Parts
N—Surplus Assemblies
O—RTTY Equipment and Parts
P—Surplus FM Gear and Parts
Q—Equipment Manuals
R—Service of Collins Equipment
S—Test Equipment
T—Amateur TV Cameras and Components
U—Microcomputer Peripheral Equipment
V—Towers
W—Ready-made Printed Circuit Boards
X—Wire
Y—Crystals
Z—Climbing and Safety Equipment

*Catalog Price
**Minimum Order

To the best of our knowledge the suppliers shown are willing to sell components to amateurs in small quantities by mail. This listing does not necessarily indicate that these firms have the approval of ARRL.

From September 1988 QST, p 44:

BLENDING CIRCUIT-BOARD FABRICATION TECHNIQUES FOR SUCCESS

☐ In his August 1987 article on homemade circuit boards,[4] Doug DeMaw mentioned the unsuitability of mechanically etched boards for use with ICs or other components with close pin spacings. (Generally, mechanical etching isn't precise enough to make traces suitable for the 0.1-inch pin spacing standard with ICs.) I've been getting around this limitation by making a gridded sub-board for the IC and mounting to the main (mechanically etched) circuit board with the piggyback method described in Doug's article (see Fig 4). Jumper wires connect the IC sub-board pads to the main circuit board; glue holds the IC subassembly in place.—*John Evans, K3SQO, RR1, Box 131, Kingsley, PA 18826*



Fig 4—John Evans gets around the incompatibility of mechanically etched boards and ICs by mounting his ICs on gridded, single-sided sub-boards. (Here, the main board is also gridded for clarity.) The sub-boards are mounted to the main board using the piggyback technique described by Doug DeMaw. See text.

ETCH-RESIST PENS FOR HOMEMADE CIRCUIT BOARDS

☐ Because I've been fabricating circuit boards at home for some time, Doug DeMaw's circuit-board article[4] was of more-than-usual interest to me. In particular, I've been involved in "longhand" PC-board production (a general term for boards produced with resist applied by hand with a brush or marking pen) for quite some time.[5] Most problems with boards made by the longhand method are caused by uneven ink flow from the pen. Marcus referred to this problem in a *CQ* article.[6] This uneven-flow problem can be corrected by opening the pen and adding a solvent that is compatible with the ink. (Usually, the ink vehicle is an alcohol-based solvent.)

The ink in most felt- or fiber-tip pens is stored in a fiber cylinder enclosed in a thin plastic sheath. Add 10 to 15 drops of alcohol or a similar solvent (rubbing alcohol [70% isopropyl], lacquer solvent [denatured ethyl alcohol] and butyl acetate [thinner for model paints] are satisfactory) to the cylinder end that contacts the pen tip. (Stop adding alcohol if it appears that the next drop will cause leakage from the bottom of the cylinder.) Replace the ink cylinder in the pen and allow a few minutes for the rejuvenated ink to migrate into the pen tip. Now, the pen should produce opaque black lines without smearing. If the lines appear to be almost *too* fluid, that's ideal. (By the way, overapplication of alcohol to the ink cylinder can cause leakage through the pen's tip vent hole. Watch out for this so you don't generate profanity when a vent drop hits the board and spoils your work!) Using this method, I've successfully rejuvenated *10-year-old* pens!

The best resist pens I've found for circuit-board work are produced in Germany and sold in art stores under the name Staedtler Lumocolor. Medium (no. 317) and fine (no. 318) points are available. (I recommend the no. 318 pen for most circuit-board work.) These pens contain a high-quality waterproof ink and can be opened by removing the top cap (pliers may be necessary in some cases). Most of these pens can be used for circuit-board fabrication *without* the solvent-addition treatment just described.

For builders who do not have easy access to an art supply store, I recommend the 0.4-mm, extra-fine-point version of Sanford's® Sharpie® marker. This model has a removable top that allows easy access to the ink cylinder. Many supermarkets stock this pen with stationery supplies or laundry products.

Two types of *medium*-point Sharpie pens are available. That labeled PERMANENT MARKER is definitely better for circuit-board work than the no. 3000 "highly water-resistant" model; the permanent marker has the further advantage of easy "openability." (The tip end of the permanent pen is pressed into the barrel assembly portion and held snug with several small rings. If the two parts are simultaneously bent slightly and pulled, the two pieces separate, allowing easy removal of the fiber ink cylinder. Once you've disassembled one of these pens, shave the rings with a file or knife to make subsequent assembly/disassembly cycles easier.) The second-choice (no. 3000) pen is cemented shut; if you must use one of these, I suggest sawing off the top end of the pen to add solvent to the ink cylinder. Reassemble the pen with tape if you do this.

My *ham radio* letter suggests use of a commercial metal-marking lacquer (DYKEM®) as etch resist for the portion of the circuit-board copper intended to remain as a ground plane. If you have trouble locating this product, I recommend thin lacquer, model paint or fingernail polish as a substitute. Be sure the resist you use flows easily so that it can be worked quickly. Also, the resist should be easily removable after etching. (I suggest using acetone as resist-removal solvent.)

Be sure to take proper safety precautions when working with any of the chemicals I've discussed here: Don't breathe their fumes and keep them out of contact with your skin. Further on the subject of chemicals, I add this: As a retired chemist, I cheerfully object to the characterization of home etched-PC-board fabrication as requiring "messy chemicals." *Chemicals* aren't messy, but *the people who use them* may be!—*Robert J. Grabowski, W5TKP, Rte 1, Box 388, Ozark, AR 72949*

---

[4] Doug DeMaw, "Homemade Circuit Boards—Don't Fear Them!" *QST*, Aug 1987, pp 14-16.

[5] Robert J. Grabowski, "longhand printed-circuit layout," comments, *ham radio*, Jun 1979, p 6.

[6] Alan Marcus, "A Printed Circuit Board Primer," *CQ*, Oct 1982, pp 44 and 47.

From February 1988 QST, p 14:

The Neophyte Receiver

Looking for a simple receiver to tune the 80- or 40-meter ham bands? Build the Neophyte!

By John Dillon, WA3RNC
Penntek Electronics
14 Peace Dr
Lewistown, PA 17044



It doesn't take long for prospective hams to discover that there's much more excitement in hearing real signals than listening to "canned" code from a tape or computer program. After all, getting on the air and working with *real* radio is the object of getting an Amateur Radio license! Here is a simple 80- or 40-meter receiver that can bridge the gap between a code-practice machine and your first transceiver by giving you on-the-air listening experience. Dubbed the Neophyte, it's been designed with the needs of the neophyte (beginner) in mind, but will find favor with long-time hams as well.

The Neophyte uses two ICs to receive CW, SSB and AM signals in the 3.5-4.0 or 7.0-7.3 MHz ham bands. It's battery-powered, and most of its circuitry fits on a circuit board just 1-7/8 × 2-5/8 inches in size. The Neophyte's frequency stability allows copy of SSB and CW signals for hours without retuning, and it's sensitive enough to detect signals of less than 0.5 microvolt at its antenna terminals.

How the Receiver Hears

The Neophyte is a *direct-conversion* (D-C) receiver. A D-C receiver converts radio signals directly to audio by mixing the incoming signal with a local oscillator (LO) operating very close in frequency to the incoming signal. The mixing process has this effect: Whenever the LO is tuned so that the frequency difference between it and an incoming radio signal is in the audio range—a few hundred to a few thousand hertz for usable CW, SSB and AM reception—the frequency difference appears at the mixer output as an audio signal. Example: For an incoming Novice CW signal operating at 3737.0 kHz, setting the Neophyte's LO to 3737.6 kHz (a difference of 0.6 kHz, or 600 Hz) will allow you to hear that CW signal as dots and dashes at a 600-Hz pitch. (You could also set the Neophyte's LO to 3736.4 kHz, 600 Hz *below* 3737.0 kHz, to receive the same signal at a 600-Hz pitch.) AM and SSB signals are received by tuning the Neophyte's LO to zero beat—zero frequency difference—with the incoming carrier (or suppressed carrier, in the case of SSB signals). The Neophyte converts the modulation on these signals to audio.

The Neophyte does its D-C job with just two active devices, both of which are ICs. The receiver's *front end*—the RF-handling circuitry from the antenna to the mixer, inclusive—consists of a Signetics NE602N mixer/oscillator IC. The NE602's 8-pin mini-DIP (*mini*ature *d*ual *i*nline *p*ackage) contains bipolar-transistor LO and doubly balanced mixer stages, and a voltage-regulator circuit. The mixer circuitry provides 20 dB of *conversion gain*. This means that the power of an incoming signal is amplified 100 times as the signal is converted to audio by the NE602's mixer and LO.

The other active device in the Neophyte is a National Semiconductor LM386N-1 audio amplifier IC, also contained in an 8-pin mini-DIP. This IC provides 46 dB (power gain, 40,000) of audio amplification to drive headphones or (in a quiet room) a 2¼-inch speaker. Four "C" cells, connected in series to form a 6-V battery, power the Neophyte. Current drain is about 10 mA at low audio-output levels.

Table 1

Neophyte Capacitor Values for 80 and 40 Meters

Band	*C1*	*C7,C8*	*C9*	*C10*	*C11*
80 m	330	1000	470	270	120
40 m	not used	330	120	68	150

All capacitances are in pF (1000 pF = 0.001 µF). C1 is disc ceramic; C7-C11 are NP0, polystyrene or silver mica units.

Fig 1 shows the schematic diagram of the Neophyte. If you'd like to learn the function of each component in the schematic, see the sidebar, "Signal Flow in the Neophyte." You needn't wade through signal flow, however, if you just want to do what we're going to do next: *build* the Neophyte.

Building The Neophyte

Fig 2 shows a rear view of the Neophyte. Most of the receiver's components are contained on the circuit board. Fig 3 shows the etching pattern for the board; parts placement is shown in Fig 4A. The Neophyte's "cabinet" consists of a 4½- × 8¼-inch piece of ¾-inch-thick pine (base) and a 4- × 8½-inch piece of ¼-inch-thick particle board, plywood or similar material (front panel). The base can be stained or painted as desired; alternatively, a metal or plastic cabinet can be used to house the Neophyte, if desired.

Components

Although no exotic electronic parts are required, many of the Neophyte's parts are not available at the corner Radio Shack® store. T1 and T2 are 10.7-MHz IF transformers with a 7:1 turns ratio; they have green-colored cores. Other transformers (with different turns ratios) were tried, but receiver performance suffered. Capacitors C7-C11 should be NP0, polystyrene or silver mica units for good frequency stability. At this point, you should decide what band you'd like your Neophyte to cover. The values of C7-C11 depend on the band you choose (see Table 1). For details on the differences between the 80- and 40-meter versions, study the sidebar, "Building the Neophyte for 40 Meters." In the rest of this discussion, I'll concentrate on the construction, testing and adjustment


10 µF
10 V
C6
C5
0.047
3.5 OR 7 MHz
T1
59.2 pF
141.6 pF
J1A
ANT
GAIN
R1
1k
GND
J1B
C1
330
C4A
C4B
RF PEAK
C2
0.047
C3
10 µF
10 V
VCC
INPUT A
OUTPUT B
U1
NE602N
MIXER/OSC
INPUT B
OUTPUT A
GND
OSC
OSC
C7
C8
C9
R2
100
D1
POWER
S1
ON
(PART OF R1)
BT1
6 V
C19
470 µF
10 V
C20
10 µF
10 V
C16
0.1
C13
0.047
R6
10k
C15
0.047
C14
0.1
R3
1.5k
R4
10k
AMP
U2
LM386N-1
NC
C17
0.1
R5
4.7
100 µF
10 V
C18
J2
8 Ω
PHONES
LS1
8 Ω
(A)
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000
C10
C11
C12
365
TUNING
T2
NC
NC
3.5 OR 7 MHz
TO C9
TO T2
(B)

Fig 1—Schematic of the Neophyte receiver. Ceramic capacitors shown below, but not listed in Table 1, may be monolithic or disc units; fixed resistors are ¼-W, carbon film. Component designators shown in the schematic, but not listed below, identify parts for placement on the PC board (see Fig 4). For 40-meter operation, the oscillator circuit is modified slightly, as shown at B. See text and the sidebar, "Building the Neophyte for 40 Meters." Parts kits are available from Penntek Electronics; see Note 2.

BT1—6 V battery (four "C" cells connected in series).
C1—Ceramic. This capacitor is not used, or is changed in value, for 40-meter operation—see "Building the Neophyte for 40 Meters."
C2, C5, C13, C15—0.047-µF polyester film or ceramic. (0.01 µF also suitable for C2 and C5).
C3, C6, C20—10-µF aluminum electrolytic, 10 to 25 V.
C4—Two-section, polyethylene-dielectric variable; sections 59.2 and 141.6 pF (Mouser 24TR222 or equiv). See text.
C7-11—See Table 1.
C12—365-pF, air-dielectric variable (Mouser 524-A1-227, Circuit Specialists A1-227 or equiv). See text.
C14, C16, C17—0.1-µF polyester film or ceramic.
C18—100-µF aluminum electrolytic, 10-25 V.
C19—470-µF aluminum electrolytic, 10-25 V.
D1—1-A, 50-PIV silicon diode (1N4001 suitable).
J1—Two-position terminal strip (Mouser 534-4188, Radio Shack 274-663 or equiv).
J2—Closed-circuit phone jack, 1/8-inch.
LS1—8-Ω speaker, diam 2¼ inches (Mouser 25SP024 or equiv).
R1—1-kΩ audio-taper potentiometer with SPST switch (Mouser 31VM301 or equiv).
S1—SPST switch mounted on R1.
T1, T2—10.7-MHz IF transformer, 7:1 turns ratio, green core (Mouser 421F123 or equiv). See text.
U1—Signetics NE602N mixer/oscillator IC (Arrow Electronics 9778CA2).
U2—National Semiconductor LM386N-1 audio-amplifier IC.

Signal Flow in the Neophyte

RF energy from the antenna is fed through GAIN control R1 to the untuned, low-impedance primary winding of T1. This control actually is an RF attenuator. It can be adjusted to prevent very strong signals from overloading U1 when band conditions are especially good, or when strong local signals are present. T1's primary couples incoming signals to the tuned circuit consisting of the T1 secondary, padding capacitor C1, and RF PEAK capacitor C4. This tuned circuit provides *preselection*—it emphasizes signals at its resonant frequency and tends to reject others. The preselected RF is injected into pin 1 of the mixer/oscillator IC, U1.

The oscillator section of U1 serves as the receiver LO. Capacitors C7-C12 and the tuned winding of T2 make up the LO tuned circuit. (T2 is used as a tuned circuit in this application and not as a transformer; its untuned winding is not used.) Because the frequency stability of the oscillator determines the stability of the receiver, temperature-stable capacitors (NPO, polystyrene or silver mica types) are used to minimize drift. Energy is applied to U1 at pin 8. Capacitors C5 and C6 *bypass* U1's supply pin for ac: Their purpose is to bring the supply pin to ground potential for RF and AF signals while blocking dc. R2 helps these capacitors do their bypassing job by resisting the flow of RF and AF signals on the power-supply line. C2 and C3 are bypass capacitors, also.

Within the mixer section of U1, the LO and preselected RF signals are mixed to provide balanced audio output. The audio appears at pins 4 and 5 of U1. This signal is fed through a simple low-pass filter (C13, C15 and R3) to the inputs (pins 2 and 3) of U2, the audio power amplifier. The low-pass filter tends to pass lower audio frequencies while rejecting higher ones, hence its name. C14 and C16 are blocking capacitors: They block the flow of dc while allowing ac—in this case, audio—to pass.

R4 and R6 set the bias on the input transistors of U2. C20 sets U2's gain to 46 dB. C17 and R5 suppress unwanted HF oscillation in U2. C18 is the output blocking capacitor: Like C14 and C16, it blocks dc while allowing audio signals to pass—in this case, to headphones or speaker. C19 bypasses U2's dc-supply pin for audio. (Because C5, C6, C19 and R2 also work to reduce unwanted audio coupling between U1 and U2 along the dc supply line, they serve as *decoupling* components in the dc line. Decoupling aids stability in high-gain circuits.)

Energy for the Neophyte is provided by four "C" cells connected in series (6 V). S1 is the receiver POWER switch. Diode D1 allows current to pass in only one direction between the battery holder and the receiver circuitry, preventing damage to the receiver components should the batteries be placed in the holder backwards.

About the NE602 Mixer/Oscillator IC

The Signetics NE602 (SA602 for operation over a wider temperature range) is an IC of interest to builders and designers of low-power communications gear, particularly where low power consumption (as during battery operation) is important. Fig A shows its equivalent circuit. The '602 contains doubly balanced mixer, oscillator and voltage regulator elements. Its oscillator circuitry can operate up to 200 MHz in LC and crystal-controlled (fundamental and overtone) configurations. The '602's mixer typically can handle signals up to 500 MHz. Typical dc current drain is 2.4 mA; minimum supply voltage is 4.5, maximum 8.0.

The NE602's mixer is known as a *Gilbert cell* multiplier. (If you've ever built a circuit using a Motorola MC1496 or one of its equivalents, you've used a mixer based on the Gilbert cell.) The Gilbert cell consists of balanced switching circuitry driven by a differential amplifier; in the NE602, the amplifier inputs serve as the mixer RF inputs.

The NE602's mixer inputs (RF) and outputs (IF) can be single- or double-ended (balanced) according to design requirements. The resistance of these ports is 1.5 kΩ; the mixer input capacitance is approximately 3 pF up to 50 MHz. The mixer noise figure is typically 5.0 dB at 45 MHz; typical conversion gain is 18 dB at this frequency. The typical two-tone, third-order intercept point of the '602 (measured at 45 MHz with 60-kHz spacing), is −15 dBm.



Fig A—The equivalent circuit of the NE602 doubly balanced mixer/oscillator IC.

The Neophyte uses the NE602's on-board oscillator circuitry to achieve good frequency stability at 3.5 and 7 MHz. If the '602's oscillator is unsuitable for a particular application, however, an external LO can be applied to pin 6 of the chip via a dc blocking capacitor. At least 200 mV (P-P) of external-LO drive is required for proper operation of the mixer.—Ed.

This material is based on information in Signetics Corporation's SA/NE602 Product Specification, and in Robert J. Zavrel, "Tomorrow's Receivers: What Will the Next Twenty Years Bring?," *Ham Radio*, Nov 1987, pp 8-9, 11-13 and 15.



Fig 2—The Neophyte's cabinet, battery and front-panel controls dwarf its circuit board (right foreground). From left to right, the front-panel components are J2, LS1, R1, C12 and C4. The tuning capacitor mounts to the front panel by means of flat-head, 1-inch, no. 6-32 screws, and no. 6-32 nuts. The screws serve both as fasteners and mounting standoffs for the tuning capacitor (see Fig 5). The antenna terminals have been colored with felt-tip markers to indicate their function: black for the ground connection, green for the antenna.

of the 80-meter Neophyte.

The TUNING capacitor, C12, is a 365-pF, air-dielectric unit. One section of a two-section capacitor can be used at C12, but you may have some difficulty mounting such a capacitor to the front panel with the technique we'll cover shortly in "Construction." Local hamfests offer an excellent opportunity to find a tuning capacitor, as well as a reduction drive to turn it. These reduction drives are generally found in two diameters, 1½ and 2 inches. You can use either size.[1]

RF PEAK capacitor C4 is a two-section, plastic-dielectric variable. Similar capacitors are commonly used in small, portable radios. The unit specified for C4 in the parts list (see the Fig 1 caption) provides a maximum capacitance of about 200 pF with both sections connected in parallel. Off the shelf, its shaft is only about ¼ inch long—too short to be useful for our purposes. The shaft can be extended by bolting a ¼-inch-diameter round standoff, ½ inch long, to the existing C4 shaft. Use a *metric* (2.5-mm-diameter) screw to match the threads in C4's shaft; the force necessary to turn a non-

[1] Footnotes appear at end of article.



Fig 3—Circuit-board etching pattern for the Neophyte. The pattern is shown full-size from the foil side of the board. Black areas represent unetched copper foil.



Fig 4—Parts-placement guide for the Neophyte (A) and detail of connections to C4 (B). Parts are placed on the nonfoil side of the board; the shaded area represents an X-ray view of the copper pattern. The placement of C11 depends on whether 80- or 40-meter coverage is desired; see text and "Building the Neophyte for 40 Meters."

metric screw into C4 can destroy the capacitor. (By the way, don't be tempted to use one of these inexpensive plastic capacitors for C12, the TUNING capacitor. You would be disappointed with the tuning drift that occurs as the capacitor's dielectric sheets settle each time you tune the receiver.)

In general, it's best not to attempt parts substitutions. By using the specified parts, you stand the best chance of being rewarded with a receiver that works correctly the first time it's turned on. Etched and drilled PC boards, and complete parts kits, are available from Penntek Electronics.[2] The Appendix shows the addresses of parts distributors if you'd rather order direct from them. Note, however, that some of these firms may have minimum order requirements or small-order service charges.

Construction

Building the cabinet and mounting controls and mechanical components is the greater part of contructing the Neophyte, so do this job first! Mounting the TUNING capacitor and reduction drive to the panel is the most time-consuming part of construction. The panel hole for the reduction-drive bushing must be large enough to allow rotation of the bushing and its set screw, but small enough to leave enough material to pass and hold the flat head screws used to mount the TUNING capacitor (see Fig 5). The best way to mark these holes is to make a drilling template by pushing a piece of paper down over the capacitor shaft. The shaft punches through the paper, marking the position of the hole for the reduction-drive bushing. Next, hold the paper against the capacitor frame and use a pencil point to punch holes in the paper corresponding to the mounting-screw holes in the capacitor frame. Instant drilling template! The bushing hole shown in Fig 5, 7/8 inch in diameter, leaves just enough panel material to hold the countersunk holes for the three no. 6-32 capacitor mounting screws. The best technique is to enlarge the bushing hole *last*, widening it only enough to pass the

Building the Neophyte for 40 Meters

The Neophyte receiver can be built for 7.0-7.3 MHz coverage as follows: Omit C1. C7 through C11 take the 40-meter values shown in Table 1. C11 is mounted in parallel with C12 instead of across T2 (see Fig 1B); this is easily done by mounting C11 across the PC-board connections to C12. Before mounting T2 to the circuit board, remove the small, tubular capacitor in the base of the transformer. Do this carefully with a small razor knife.

Forty-meter alignment is similar to that for the 80-meter Neophyte. Adjust T2 for an oscillator tuning range of 7.0-7.3 MHz, with some overtravel at both ends of the range. With the TUNING control set to the center of the band, set the RF PEAK knob to one o'clock. Adjust T1 for maximum signal strength. This completes alignment of the 40-meter Neophyte.

Because of decreased LO-mixer isolation in the NE602 at 7 MHz, adjustment of the RF PEAK control "pulls" the LO slightly in the 40-meter Neophyte. (Pulling is perceptible as a shift of received-signal pitch as RF PEAK is varied.) This isn't much of a problem, because the RF PEAK control needs little adjustment from one end of the 40-meter band to the other. In fact, you can eliminate the RF PEAK control in the 40-meter Neophyte if you do most of your listening in one part of the band. To do this, omit C4, install a 150-pF capacitor at C1 and adjust T1 for maximum signal strength at your favorite spot in the band.

The Neophyte in ARRL Lab Tests

ARRL Lab testing of one sample of the 80-meter Neophyte netted these results: minimum discernible signal (MDS), −118 dBm (decibels relative to a milliwatt) at 3520 kHz and −113 dBm at 3747 kHz; two-tone, third-order dynamic range with 100-kHz tone spacing, 73.5 dB; selectivity, 1 kHz at −3 dB and 7.5 kHz at −20 dB. Blocking dynamic range was not measured. No microphonics were noted.

The frequency coverage of the sample receiver was 3473-4027 kHz. The poorer of the two MDS figures above (−113 dBm) confirms that the Neophyte is capable of detecting signals down to 0.5 microvolts across 50 ohms, as specified by WA3RNC. At 3520 kHz, sensitivity improved to just under 0.3 microvolt.—Ed.



Fig 5—Detail of the mounting holes for the TUNING capacitor, C12. The holes are countersunk to keep the screw heads flush with the panel surface, allowing the reduction drive to be mounted flat to the panel. See text.

reduction-drive bushing and its set screw—*after* the capacitor mounting screw holes have been drilled.

Mounting the Neophyte's TUNING capacitor to the front panel as just described provides good mechanical stability. If you use a capacitor other than the one shown in the parts list for C12, carefully study your mounting options. Make sure that the mounting screws don't penetrate too far into the capacitor and damage the plates. Whatever you use for C12, mount it to the panel rather than the base, if possible.

The specified speaker requires a 2-inch hole (or a field of ¼-inch holes 2 inches in diameter). A small piece of wire screen or grille cloth between panel and speaker can be used to protect the speaker cone. (This is especially important if you mount the speaker behind a single large hole.) The speaker is attached to the panel with clips designed for this purpose (Mouser Electronics 48SC004); hot-melt glue or epoxy cement can be used instead. A 3.5-mm or 1/8-inch headphone jack is used to allow connection of inexpensive transistor radio earphones; if you prefer, you can use a ¼-inch jack here.

Microphonics, Hum, LO Radiation: Low to Absent in the Neophyte

Although the Neophyte is simple, it does not exhibit the drawbacks sometimes associated with D-C receivers. Microphonics—unwanted noises that occur with vibration when electronic parts unexpectedly act like microphones—simply do not exist with this receiver, and I have not heard any hum, even when using an external power supply. LO radiation—sometimes a problem in simple receivers using LOs at *any* frequency—*isn't* a problem with the Neophyte: The measured LO level at the receiver antenna terminals is only 80 microvolts.

The antenna connectors (J1A and J1B in Fig 1) are part of a two-position terminal strip; this is mounted to the receiver base by means of standoffs and screws. Radio Shack push-button speaker terminals would be a good substitute here. The battery holder is a 4-"C"-cell holder from Mouser or Radio Shack.

Solder the components to the circuit board, being careful to observe capacitor polarity and IC orientation. (I recommend that you use IC sockets instead of soldering the ICs directly to the board.) After you've soldered the components to the board, cut off excess wire. Check carefully for solder bridges between circuit-board traces, proper electrolytic capacitor polarity, and correct orientation of D1, U1 and U2. If all looks well, wire the board into the rest of the receiver. As shown in Fig 2, use twisted-pair wiring for connections to C4, J1, J2 and R1. The capacitor specified for C4 has three terminals. Fig 4B shows how to wire these for connection to the circuit board.

When you've completed all connections, mount the board to the cabinet base by means of screws and spacers. Next, we'll align and test the Neophyte.

Checkout and Alignment

Before applying power to the receiver, recheck your wiring once again. Install four "C" cells in the Neophyte's battery holder. (Note: You can use a regulated dc supply in place of the batteries if you wish, but *do not apply more than 8 V to the receiver,* or you'll damage the ICs.) Install a milliammeter or digital multimeter (DMM) in series with the batteries, and turn on the receiver. If the meter indicates less than 15 mA, all's well so far.

Adjust the TUNING capacitor almost to minimum capacitance (plates just short of fully unmeshed). Connect a signal generator to the antenna terminals and inject a 500-µV, 4-MHz signal into the Neophyte.[3] Turn the Neophyte's GAIN control to maximum (fully clockwise if you've wired it correctly) and adjust oscillator coil T2 until you hear the test signal.

Position the RF PEAK knob on C4's shaft so that maximum capacitance (knob fully counterclockwise) is at nine o'clock and minimum capacitance is at three o'clock. Set the RF PEAK capacitor nearly to minimum capacitance (almost fully clockwise; near two o'clock) and adjust T1 for maximum signal strength. Verify that the receiver tunes 3.5-4.0 MHz with a slight overtravel at both ends of the range. Also check that the RF PEAK control tunes through resonance at both ends of the band.

Disconnect the signal generator from the Neophyte and connect a good antenna, such as a dipole, to the receiver. As you tune the Neophyte across the band, adjust the RF PEAK control for best signal strength. (Don't expect outstanding performance with a clip-lead antenna!) If you don't have a dipole, use a long random-wire antenna. (Use of a random-wire antenna also requires a ground connection.) Set the GAIN control no higher than necessary for solid reception; this reduces the likelihood of detector overload. This practice also lengthens battery life because U2 draws more energy from the battery as the receiver output increases. Battery life, longest when headphones are used in place of the speaker, can exceed 300 hours when fresh alkaline cells are used!

Summary

I welcome your comments and questions on the Neophyte—please include an SASE if you expect a reply. Several Neophytes have been built using different construction techniques. All perform flawlessly. The Neophyte usually can hear any signal audible on a typical ham transceiver. Its selectivity is adequate for band scans and casual listening, and it's an excellent project for schools, ham-radio classes, beginners and old-timers. In short, the Neophyte is fun!

APPENDIX

Parts for the Neophyte are available from a combination of these sources, and from Penntek Electronics (see Note 2):

Arrow Electronics
25 Hub Dr
Melville, NY 11747
tel 800-932-7769

Circuit Specialists
PO Box 3047
Scottsdale, AZ 85257
tel 602-966-0764

Mouser Electronics
11433 Woodside Ave
Santee, CA 92071
tel 619-449-2222

Mouser Electronics
2401 Hwy 287 N
Mansfield, TX 76063
tel 817-483-4422

Radiokit
PO Box 973
Pelham, NH 03048
tel 603-635-2235

Notes

[1] Mouser Electronics carries 1½- and 2-inch reduction drives as part nos. 45KN100 and 556-S50, respectively. Radiokit carries a 2-inch drive as part no. S-50. See the Appendix for the addresses of these firms.

[2] Circuit boards and parts kits for the Neophyte receiver are available from Penntek Electronics, 14 Peace Dr, Lewistown, PA 17044, tel 717-248-2507. Prices are as follows: (1) An etched and drilled PC board, $4.50; (2) all PC-board-mounted components, and an etched and drilled PC board, $17.50; (3) a complete Neophyte kit, including drilled wooden panel, wooden base, all hardware and parts, $45; (4) builders who wish to supply their own parts for the Neophyte, but who have trouble finding a small-quantity source for the Signetics NE602N IC, can purchase the NE602N from Penntek Electronics for $3.25 postpaid. Add $3.50 for shipping and handling to all orders for options 1, 2 and 3. Pennsylvania residents, add sales tax to all orders. When ordering options 2 and 3, be sure to specify 80- or 40-meter operation. The ARRL and *QST* in no way warrant this offer.

[3] If you don't have access to a signal generator, you may be able to generate a test signal by feeding a 4-MHz transmitter signal into a dummy load. Connect a short length of wire to the Neophyte's antenna terminal (J1A) and bring the wire near the dummy load. Vary the spacing between the wire and the load—or reduce the transmitter output—until the transmitter signal is just strong enough to use.—Ed.

For updated supplier addresses, see ARRL Parts Supplier List in Chapter 2.

From **1990 ARRL Handbook** *Ch 30, p 1:*

A Band-Imaging CW Receiver for 10 and 18 MHz

Band imaging has long been used in Amateur Radio as a means of making a stable local oscillator (LO) do double duty. Instead of building equipment using only one LO-to-RF relationship for frequency conversion—with, for instance, only the *difference* between the LO and higher-frequency incoming signals giving output at the IF—*two* of several LO-to-RF relationships can be exploited for two-band coverage. A band-imaging receiver appeared in every edition of this *Handbook* from 1953 through 1966, from "A Two-Band Four-Tube Superheterodyne" in 1953 to "The HB-65 Five-Band Receiver" in 1966. Each of these receivers converted the 80- and 40-meter amateur bands to a 1.7-MHz IF by means of a 5.2-5.7-MHz LO. On 80 meters, the conversion relationship in such a receiver is LO − RF = IF; on 40, the relationship is RF − LO = IF. Both bands "tune in the same direction" with this system: The received frequencies of 3.5 and 6.9 MHz correspond to the lower limit of the LO tuning range.

Band imaging can also be used to cover the 80- and 20-meter amateur bands: A 5.0-5.5-MHz LO is used to convert each band to a 9-MHz IF. In such a system, the LO-to-RF relationship on 80 meters is RF + LO = IF; on 20, RF − LO = IF. The drawback to this band-imaging system is that the lower band "tunes backwards": The lower limit of the LO tuning range corresponds to 4.0 MHz on 80 meters and 14.0 MHz on 20. Nonetheless, the 80/20 band-imaging system has also been popular with radio amateurs because of the inherent sideband inversion between the image bands: The BFO-to-IF relationship that affords LSB reception on 80 meters demodulates USB on 20.



Fig. 1 — The band-imaging receiver covers the CW segments of the 10- and 18-MHz amateur bands with good stability, sensitivity and single-signal selectivity. Larger controls are (l-r) TUNING, IF GAIN and AF GAIN. The two smaller controls, separated by the PHONES jack, are BAND and SIDETONE LEVEL. The TUNING scale is drawn on contact paper applied to an aluminum disc.

With this overview of band-imaging techniques in place, we present a band-imaging CW receiver for 10 and 18 MHz (see Fig. 1). Using a 14-MHz LO, it converts the entire 10-MHz amateur band, and the CW portion of the 18-MHz amateur band, to a 4-MHz IF. Both bands tune in the same direction. At 4 MHz, a four-crystal ladder filter provides single-signal selectivity. The design emphasizes good basic receiver performance with an eye toward compactness; hence, features such as a digital frequency display, AGC and active audio filtering have been omitted. Alignment and checkout of the band-imaging receiver requires only (1) a 51-ohm resistor; (2) a receiver capable of CW reception at 14.0-14.2 MHz and 4 MHz ± 1 kHz with an S-meter and frequency display resolution of 1 kHz or greater; and (3) a crystal-controlled marker generator capable of providing 10-kHz markers. The performance measurements given later in this article were obtained from a receiver aligned *by ear* with such test equipment. You need not have access to a radio lab to enjoy similar results. David Newkirk, AK7M, designed and built this project in the ARRL lab.

Circuit Description: RF Amplifiers

A separate 40673 RF amplifier is used for each band. (See Fig. 2). The circuit is electrically identical to that used for the RF amplifiers in "A High-Performance Communications Receiver," presented later in this chapter. Several other circuits in the band-imaging receiver are based on the K5IRK/W7ZOI high-performance design. To simplify alignment of the band-imaging



Fig. 2 — Schematic of the RF amplifiers for the band-imaging receiver. A separate amplifier is used for each band. The low- and band-pass filters may be aligned with the aid of a crystal-controlled marker generator; see text. Capacitors are disc ceramic unless otherwise noted. Capacitors marked with polarity are electrolytic. All resistors are ¼-W, 10% units unless otherwise noted.

C1, C2, C4, C7 — Silver mica, polystyrene or ceramic capacitor; see Table 1 for values.
C3, C5, C6 — Ceramic or mica compression trimmer. Mouser Electronics ceramic trimmer 24AA067 (12-100 pF) used for 100 pF; Mouser 24AA064 (5-45 pF) used for 45 pF.
J1 — Coaxial RF connector.
L1-L4 — Wound on Amidon T-50-6 powdered-iron toroid core or equiv. All inductors use no. 22 enameled wire with one exception: For L2 at 10 MHz, use no. 24 enameled wire. See Table 1 for number of turns.
Q1 — 40673 dual-gate MOSFET.
S1 — 3PDT toggle (Radio Shack 275-661 or equiv).
T1 — Transformer wound with no. 28 enameled wire on Amidon FT-37-43 ferrite toroid core or equiv. Primary (168 µH), 20 turns; secondary (6.7 µH), 4 turns.
Z1 — Ferrite bead on Gate 2 lead of Q1, Amidon FB-43-101 or equiv.

Table 1

Component Values for the Band-Imaging Receiver RF Amplifiers

MHz	*C1*	*L1*	*C2*	*L2*	*C3*	*C4, C7*	*L3, L4*	*C5, C6*
10	300	13	680	29	100	33	17	100
18	180	10	390	22	45	22	10	100

Values listed for capacitors are capacitance in pF. Values listed for inductors are number of turns of wire required.

receiver, the variable coupling capacitor (C15 in Ch. 30, Fig. 12) between the two sections of the output filter is replaced by three 12-pF capacitors in series. Gain of this circuit is 12 to 15 dB, depending on alignment and the characteristics of Q1. Band changing is accomplished by switching RF input, RF output and dc connections between the 10- and 18-MHz amplifier boards via S1, a 3PDT toggle. Input and output (I/O) impedances of each RF amplifier board are 50 ohms.

Mixer, IF Filter and IF Amplifiers

See Fig. 3. The band-imaging receiver uses a Mini-Circuits SBL-1 doubly balanced diode-ring mixer (U1) followed by a strong bipolar-transistor IF amplifier (Q2).[1] This is the circuit used in the K5IRK/W7ZOI receiver, with several modifications. In the band-imaging receiver, the bifilar 4:1 collector transformer in the original design has been replaced with a toroidal monofilar choke, RFC1. The supply end of the 1-kΩ Q2 base bias resistor is now connected directly to the 12-V dc line at the cold end of RFC1. This removes the RF feedback present in the original circuit. Surprisingly, this feedbackless configuration results in better sensitivity *and* two-tone 3rd-order IMD dynamic range than the unmodified circuit affords *at a 4-MHz IF*. The original circuit, intended for use at an IF of 9 MHz, did not provide a comparable performance even when the inductance of its 4:1 collector transformer was scaled for 4 MHz.

The post-mixer amplifier feeds a four-crystal ladder filter via a 6-dB pad. The I/O impedances of the crystal filter are 200 ohms. Because this is a good match for the collector impedance of Q2, the step-down transformer in the original post-mixer amplifier circuit is not required. The 50-ohm 6-dB attenuator of the original circuit has been scaled to 200 ohms. This pad should *not* be replaced with one of lower attenuation: It assures a nonreactive wideband termination for Q2 *and* the crystal filter. Less attenuation here results in reduced IMD dynamic range, as confirmed by lab tests.

The crystal filter was designed using Hayward's technique (see "Simple Cohn Crystal Filters," *QST*, July 1987, pp 24-29). Measured selectivity of the prototype filter was 405 Hz at −6 dB and 1850 Hz at −60 dB, resulting in a −60 dB/−6 dB shape factor of 4.57. Insertion loss was 2 dB, and passband ripple was less than 0.4 dB. As is characteristic of simple ladder crystal filters, the upper passband slope is steeper. Because of this, the BFO must be set on the *upper* side of the filter for best single-signal reception. With the BFO set to provide a 550 Hz beat note for signals at IF center, rejection of the audio image in the prototype receiver was 73 dB. Ultimate attenuation was 90 dB.

No filter adjustment is necessary, but it *is* important that you use the specified crystals if you intend to duplicate the post-mixer-amplifier/pad/filter arrangement shown in Fig. 3. Substitutions at Y1-Y4 will require filter capacitors of other than 300 pF, resulting in I/O impedances of other than 200 ohms. Hayward states that the series-resonant frequencies of the four filter crystals must fall within a spread of no more than 10% of the desired *3-dB* filter bandwidth. We chose to evaluate the performance of the filter in the more popular terms of −60 and −6 dB bandwidths; it follows that 10% spread is too generous where a given *−6 dB* filter bandwidth is the target. Experiments with various new and surplus 4-MHz microprocessor-clock crystals in the ARRL lab showed that the new International Crystal Mfg. (ICM) crystals provided the best

---

[1] Mini-Circuits, PO Box 166, Brooklyn, NY 11235, tel. 212-934-4500.


FROM 18-MHz RF AMP
18 MHz
S1C
TO MIXER
(FIG 3, U1, PIN 1)
C7
100
C6
10 MHz

performance overall. Shape factors (−60 dB/−6 dB) for the clock-crystal filters were rarely less than 5, and sometimes more than 6. I/O impedances were between 300 and 400 ohms. Several times, four crystals within a suitably narrow frequency spread could be found only by grading *10 or more* clock crystals. Custom-ground crystals offer the added advantage of resonating—within tolerance, of course—on the frequency you specify. Their unit price is higher, but they come closest to guaranteeing that your filter will perform as predicted.

Post-filter IF amplification is provided by U2, an MC1350P video amplifier IC. The 200-ohm resistor between pins 4 and 6 of U2, in conjunction with the 0.1 μF bypass capacitor at pin 6, terminates the crystal filter output. Manual gain control is achieved by applying a variable positive voltage to pin 5 of U2 through a 27-kΩ resistor and IF GAIN control R1. Receiver muting is accomplished by means of Q3: Grounding the MUTE terminal (center conductor at J2) applies maximum gain-reduction voltage to U2. The supply voltage (nominally 12) appears across J2 with the receiver unmuted; current through the grounded MUTE line is 5 mA. IF output (Z ≈ 50 ohms) is available at the secondary of T2.

Local Oscillator

The schematic of the band-imaging receiver LO is shown in Fig. 4. An MPF102 JFET, Q4, operates as a Colpitts oscillator. The oscillator signal is amplified by Q5, a 40673 dual-gate MOSFET. Bandspread is achieved by tapping the tuning capacitor, C9, down on LO tank inductor L5. Tuning range of the circuit is approximately 14.060 to 14.153 MHz. Air-dielectric trimmer C10 shifts this range for dial calibration.


+12 V
IF AMPLIFIER
100
0.01
RF INPUT
(FROM FIG 2)
U1 SBL-1
MIXER
1
2
3
4
5
6
7
8
LO INPUT
(FROM FIG 4, T3)
RFC 1
ATTENUATOR −6 dB, 200 Ω
0.1
150/5%
1 k
470
Q2
2N3866
56
5.6
0.1
300 5%
300 5%
300 5%
300 5%
* - USE HEAT SINK
4.000 MHz FILTER
BW = 405 Hz AT −6 dB
Y1
Y2
Y3
Y4
300
5% SM
SM = SILVER MICA
0.1
U2
MC1350P
IF AMP
200 5%
0.1
0.005
27 k
C8
350 IF TUNE
T2
120
TO PRODUCT DETECTOR
(FIG 6, U4, PIN 1)
R1
IF GAIN CW
10 k
4.7 k
1N914
1N914
SWITCH
Q3
2N3906
10 k
0.1
0.01
2.2 k
J2
MUTE
U1 PINOUT, BOTTOM VIEW
BLUE RING AROUND PIN 1
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000

Fig. 3 — Schematic of the mixer, crystal filter and IF amplifier stages of the band-imaging receiver. Capacitors are disc ceramic unless otherwise noted. Capacitors marked with polarity are electrolytic. All resistors are ¼-W, 10% units unless otherwise noted.

C8 — 350-pF compression trimmer (Arco 428 or equiv).
J2 — Phono jack.
Q2 — 2N3866 or 2N5109. Use a small heat sink on this transistor.
Q3 — 2N3906.
H1 — 10-kΩ linear potentiometer.
RFC1 — 95 μH; 15 turns no. 24 enameled wire on Amidon FT-37-43 ferrite toroid core.
T2 — Transformer wound on Amidon T-68-1 powered-iron toroid core, or equiv. Primary (12.9 μH): 36 turns no. 26 enameled wire, center-tapped; secondary (0.9 μH): 3 turns no. 26 enameled wire over center of primary.
U1 — Mini-Circuits SBL-1 doubly balanced diode-ring mixer.
U2 — MC1350P video amplifier IC.
Y1-Y4 — 4.000000-MHz custom-etched crystal, 26°C calibration temperature, grade CS-1 (0.001% tolerance), F-700 holder, series resonant. International Crystal Mfg Co type 433340. See text.


Δ ≈ 14.060 - 14.153 MHz
OSCILLATOR
Q4
MPF102
+7 V
U3
LM317L
OUT
REG
IN
ADJ
+12 V
120 NPO
1N914
G
D
S
22 k
0.1
1 μF 35 V
T
0.1
100
L5 *
27 NPO
C10 17
50
C9 *
TUNING
BAND EDGE ADJ
220 NPO
33 NPO
(A)
240 5%
1.1 k 5%
0.01
T3
≈ 5 dBm
OUTPUT TO MIXER
(FIG 3, U1, PIN 8)
Z = 50 Ω
* - NOT MOUNTED ON CIRCUIT BOARD
RFC 2
27 NPO
100 k
Q5 40673
BUFFER
G2
G1
Z2
D
S
U3 78L07
OUT
REG
IN
GND
(B)
1.1 k AND 240-Ω RESISTORS NOT USED
0.01
47 k
100 k
100
0.01
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000
T = TANTALUM

Fig. 4 — Schematic of the band-imaging receiver LO and buffer circuit. Capacitors are disc ceramic unless otherwise noted. Capacitors marked with polarity are electrolytic. All resistors are ¼-W, 10% units unless otherwise noted. At A, an LM317L adjustable regulator is used at U3. The inset at B shows connections for an 78L07 regulator at U3. For best stability, use only NP0 (C0G) capacitors in the circuitry associated with the gate and source leads of Q4. Space L5 by at least its diameter from other components and the LO shield box. See text and Fig. 8.

C9 — 50-pF air variable (Jackson Bros 4667-50 or equiv).
C10 — 17-pF air trimmer (Johnson 189-506-5 or equiv).
L5 — 1.4 μH: 11 turns no. 22 tinned wire, 24 turns per inch (Barker & Williamson 3038 Miniductor). Tap at 2 or 3 turns from ground end. See text and Figs. 8 and 9B.
Q4 — MPF102 JFET.
Q5 — 40673 dual-gate MOSFET.
RFC2 — 39 μH: Miller 70F395AI, or 24 turns no. 26 enameled wire on Amidon FT-50-61 ferrite toroid core.
T3 — Transformer wound on Amidon FT-37-43 ferrite toroid core or equiv. Primary (50 μH): 11 turns no. 26 enameled wire. Secondary (3.8 μH): 3 turns no. 26 enameled wire.
U3 — Voltage regulator, LM317LH, LM317LZ or (with circuit changes shown at inset B) 78L07.
Z2 — Ferrite bead on Gate 2 lead of Q2, Amidon FB-43-101 or equiv.

Despite the relatively high LO operating frequency, stability is good. Measured drift of the point-to-point-wired prototype oscillator was −530 Hz in the 45-minute period after turn-on, 460 Hz of which occurred in the first ten minutes. Over the next three hours, this oscillator drifted approximately −20 Hz. Stability was even better with the circuit rebuilt on an etched circuit board: Drift for the ten minutes after turn-on was only −256 Hz. *The key to this stability is the use of NP0 (C0G) ceramic units for all fixed capacitors associated with the gate and source of Q4.* Although silver-mica or polystyrene capacitors may be hand-picked for low drift, only NP0 capacitors offer minimum drift "off the shelf." Oscillator stability is further improved by the use of a three-terminal regulator to stabilize Q4's drain supply, and by enclosing LO and buffer in a shield box to slow the effect of changes in ambient air temperature.

BFO, Detector and Audio Stages

The K5IRK/W7ZOI crystal-controlled BFO is used in this receiver with one modification: The secondary of T4 in Fig. 5 carries only RF and no dc. Y5 is an inexpensive 4-MHz microprocessor clock crystal. Every such crystal we tried worked well in this circuit; a custom-ground crystal is unnecessary here.

The detector and AF stages of the band-imaging receiver are shown in Fig. 6. The product detector (U4) is a Mini-Circuits SBL-1 doubly balanced diode-ring mixer. RFC3 and the 0.001-μF capacitor provide RF filtering ahead of the AF preamp, U5, an NE5534 low-noise audio op amp. The parts list for Fig. 6 specifies a "wind-it-yourself" toroidal choke for RFC3; pi-wound chokes tried here were prone to pickup of 60-Hz harmonics.

U6, an LM380N-8, serves as the AF power amplifier. Its output is connected to a front-panel stereo headphone jack, J4, and a rear-panel phono connector, J5. J4 is wired to accept stereo headphones; monaural phones may be used if inserted no farther than the first detent. The 1-kΩ resistor from the output lead to ground serves to charge U6's 470-μF output coupling capacitor at power-up if a head-


BFO
Q6
2N3904
66
C12
100
OUTPUT TUNE
4 MHz
T4
2.2 k
BFO TO PRODUCT DETECTOR
≈ 10 dBm
≈ 50 Ω
(TO FIG 6, U4, PIN 8)
270
Y5
C11
100
FREQ ADJ
0.01
100
+12 V
0.01
4.7 k
1 k
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000

Fig. 5 — Schematic of the band-imaging receiver BFO. Capacitors are disc ceramic unless otherwise noted. Capacitors marked with polarity are electrolytic. All resistors are ¼-W, 10% units unless otherwise noted.

C11, C12 — 100-pF ceramic or mica compression trimmer. Mouser Electronics 24AA067 (12-100 pF) suitable.
Q6 — 2N3904.
T4 — Transformer wound on Amidon T-68-2 powdered-iron toroid core or equiv. Primary (19.8 μH): 59 turns no. 28 enameled wire, tapped at 12 turns. Secondary (0.98 μH): 9 turns no. 28 enameled wire over tap end of primary.


AF AMPLIFIER
IF INPUT
(FROM FIG 3, T2)
U4
SBL-1
PRODUCT DETECTOR
4
3
2
6
5
7
8
BFO INPUT
(FROM FIG 5, T4)
51
6.8 µF
16 V
100 µF
25 V
1 k
51 k
RFC 3
.0001
51 k
0.1
U5
NE5534
3
7
6
2
4
AMP
10 k
1 k
10 µF
25 V
J3
SIDETONE INPUT
≈ 0.4 V P-P
100 µF
16 V
GAIN = 20dB
220
+12 V
1 k
2 µF
25 V
.005
33 k
CW
R2
10 k
0.1
SIDETONE LEVEL
R3
10 k
CW
GAIN = 34 dB
22 µF
16 V
T
U6
LM380N-8
2
3
7
6
5
4
8
0.47
470 µF
35 V
2.7
0.1
1 k
J4
PHONES
4-16 Ω
J5
SPKR
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF), OTHERS ARE IN PICOFARADS (pF), RESISTANCES ARE IN OHMS, k = 1000
T = TANTALUM

Fig. 6 — Schematic of the product detector and audio amplifiers for the band-imaging receiver. Capacitors are disc ceramic unless otherwise noted. Capacitors marked with polarity are electrolytic. All resistors are ¼-W, 10% units unless otherwise noted.

J3, J5 — Phono jack.
J4 — Stereo headphone jack.
R2, R3 — 10-kΩ audio-taper potentiometer.
RFC3 — 1-mH RF choke: 34 turns no. 30 enameled wire on Amidon FT-37-72 ferrite toroid core or equiv.
U4 — Mini-Circuits SBL-1 doubly balanced diode-ring mixer.
U5 — NE5534 low-noise audio op amp.
U6 — LM380N-8 audio power amp.



Fig. 7 — The band-imaging receiver prototype. The LO is in the left foreground; just behind it, the 10- and 18-MHz RF amplifiers. At center, the mixer/filter/IF amplifier module, with the detector/AF amplifier module at far right. The smallest module, upper right, is the BFO. Performance was good even though etched circuit boards were not used.

phone or speaker load has not already been installed at J4 or J5. Without this resistor, the capacitor would charge on connection of the audio transducer, resulting in a loud thump.

As mentioned earlier, no active audio filtering is included in the band-imaging receiver. The higher audio components in detected IF amplifier hiss are reduced by the 0.05-µF capacitor connected between the hot end of the AF GAIN control, R3, and ground.

Sidetone can be injected into the audio chain at J3. Sidetone level is adjusted from the front panel by R2. Setting R2 to minimum shunts the AF GAIN control with a 33-kΩ resistor; this reduces overall audio gain by less than 1 dB. A 400-mV signal at J3 provides more than enough sidetone audio at normal AF GAIN settings.

This receiver requires, but does not include, a regulated dc power supply capable of providing a maximum of 220 mA at 12 V. See Chapter 27, Power Supply Projects, for suitable circuits.

Construction

The receiver was prototyped using point-to-point and "dead bug" modular construction (see Fig. 7). Later, circuit boards were designed and debugged.[1] You may use either method for building your receiver, with good results. The following construction hints are based on the circuit-board version of the receiver, but much of the information here will be of use to builders using either style of construction.

Parts for this receiver are available from a number of sources. Virtually everything can be obtained from RadioKit, Mouser, Radio Shack, DigiKey and Circuit Specialists. See the parts suppliers list at the end of Chapter 35 for addresses and telephone numbers of these suppliers.

See Fig. 8. The receiver is housed in a Hammond 1590F diecast aluminum box (approximately 7¼ × 7¼ × 2½ inches). Threaded standoffs are used to mount all circuit boards except the detector/audio board; spade lugs are used to mount this module vertically. Miniature 50-ohm coaxial cable (RG-174) is used for all RF connections between modules except the LO-mixer line. Here, miniature Teflon® -dielectric cable is used because of Teflon's high melting point (see Fig. 9A). RG-174 is also used to connect J3, SIDETONE INPUT, to the detector/audio board. Connections from this board to the AF GAIN and SIDETONE LEVEL controls are made with stranded hookup wire in three colors. This makes for more compact wiring than miniature coax allows and causes no problems with hum or crosstalk. The IF GAIN control and audio output connections are also made in this way. Dc wiring is stranded hookup wire; binding posts are used to bring dc into the receiver.

We recommend that you build, test and install the band-imaging receiver modules in this order: (1) LO; (2) detector/audio and BFO; (3) mixer/filter/IF amplifier; (4)

---

[1] Circuit-board templates are available from the ARRL Technical Department secretary for $3.00 and a no. 10 s.a.s.e.



Fig. 8 — The band-imaging receiver just fits into a Hammond 1590F diecast aluminum box. In this top view, the LO (in its shield box, shown here with cover removed) dominates the layout. The RF amplifier boards are at top, one above the other. The BFO is to the left of the LO, with the detector/audio amplifier board (edge-on) to the right. At far right, the mixer/filter/IF amplifier board. The two capacitors and resistor beneath the mixer/AF board have since been incorporated into the board design. For a similar view of the band-imaging receiver in full color, see the cover of July 1987 *QST*.



Fig. 9 — The detail drawing at A shows installation of the LO output lead. Miniature Teflon coax is recommended here because its dielectric will not melt during soldering. The shield must be flared and soldered to the *inner* wall of the LO shield box. At B, details of the LO inductor, L5, are shown. Taps are made by pushing in adjacent turns of the coil stock. The untrimmed plastic bars preserve the Q of L5 by holding the Miniductor away from the shield box bottom. Before counting the 11 turns necessary for the coil, unwind enough turns from the uncut Miniductor stock to allow L5 to stand above the shield-box bottom by its diameter. The plastic bars are fragile; they may be impregnated with Duco or similar cement for greater strength. The completed L5 is cemented to the shield-box bottom after the LO tuning range has been set.

RF amplifiers. The LO comes first because its installation entails the majority of the metalwork necessary to build the receiver. The sequence allows you to use completed modules as part of your test equipment for the modules later in the sequence.

The LO shield box is made of double-sided copper-clad circuit board. The 10:1 epicyclic reduction drive is a Jackson Bros 5857. Because the sides of the Hammond diecast aluminum box are not perpendicular to the bottom, special construction techniques are needed to ensure that the TUNING capacitor shaft is perpendicular to the front panel of the box. The following construction sequence resulted in a smooth-tuning, no-backlash LO installation in the ARRL lab version of the band-imaging receiver:

1) Mount the 10:1 reduction drive on the front panel.

2) Build the LO shield box (four sides and bottom), soldering only the side and rear pieces into place on the bottom. The front and rear pieces of the shield box must butt the shield box sides as shown in Fig. 8. *Tape* the front side into place. Drill four mounting holes in the shield box bottom plate.

3) Chisel the molded-in printing from the center of the diecast-box bottom to smooth the box floor. Sanding may also be necessary to achieve this.

4) Locate the C9 (TUNING capacitor) mounting hole in the LO shield box front by pushing the box up against the reduction-drive coupler. Size this hole slightly larger than the capacitor mounting bushing. This allows later adjustment of C9's position. Temporarily mount the capacitor in the front side of the shield box and keep this assembly taped to the rest of the box.

5) Place the LO box in the diecast box so that C9 is inserted into the reduction-drive coupler. By feel, be sure that the capacitor is about 1/16-inch short of full insertion into the coupler sleeve. This allows leeway for later adjustment. Mark the diecast box to pass the LO mounting screws through the holes in the shield-box bottom plate. Drill these holes now.

6a) Remove the taped-on front of the shield box. Build and install the LO/buffer circuit board, including the LO output cable and 12-V dc line, in the partially completed shield box. The output cable consists of a 6-inch piece of miniature Teflon coaxial cable (see Fig. 9A) Fig. 9B shows how to prepare LO inductor L5 from a length of B & W Miniductor.

6b) Temporarily install C9, C10, L5 and the 27-pF NP0 LO-tuned-circuit capacitor to the LO/buffer board by short leads. Terminate the LO output cable with a 51-ohm resistor. Verify operation of the LO/buffer board by applying dc power and tuning in the LO signal on the 14-MHz test receiver. Adjust C9 and C10 as necessary to bring the signal into your receiver's tuning range. You may need to add or remove fixed capacitors in the LO tuned circuit. Don't spend time now on setting the LO tuning range; that comes later.

6c) Once LO performance has been verified, disconnect C9, C10, L5 and the fixed tuned-circuit capacitor from the LO/buffer board. Install the board into the LO shield box.

7) Install C10 flat to the shield box floor by soldering down its rotor tab. Be sure to allow clearance for C9. Bend the C10 stator tab up to clear the box bottom. Connect C10 to the LO/buffer circuit board with tinned no. 18 solid wire. Solder L5 into the circuit; it will be cemented to the box floor later, but do not do this yet.

8) Bolt the LO into the diecast box. Loosely mount C9 in the front side of the LO box. Slide the front LO box side into place, and at the same time, slide the C9 shaft into the reduction-drive coupler to about 1/16 inch short of full insertion. *Do not* tape the LO box front into place as before.

9) Adjust the reduction drive to bring its coupler worm screws to approximately 10 and 2 o'clock. Set C9 to maximum capacitance without disturbing the reduction drive. Now, with C9 loose in its mounting hole, tighten the worm screws in the reduction-drive coupler.

10) Tighten C9 to the front of the LO shield box.

11) Using the reduction drive, turn C9 back and forth through its range several times to settle the LO box front into position. Depending on how tightly the front is held in place by the LO box sides, you may need to push the sides apart slightly to free the front piece. By eye, the front of the LO box should appear parallel to the front of the diecast box. If all looks well,

12) Solder the front side of the LO box into position.

Final tuning-range and anti-backlash adjustments will be made during alignment and testing of the receiver.

The circuit board placement shown in Fig. 8 works well. Although the position of the LO shield box left little choice as to the placement of the rest of the circuit boards, maximum spacing between the BFO and mixer/filter/IF amplifier boards was decided on *beforehand* to keep the BFO signal out of the IF amplifier circuitry.

Alignment

Test equipment necessary for aligning the band-imaging receiver is a 51-ohm resistor, a receiver capable of CW reception at 14.0-14.2 MHz and 4 MHz ±1 kHz with an S-meter and frequency display resolution of 1 kHz or greater, and a crystal-controlled marker generator capable of providing 10-kHz markers. Equip the coaxial input of the test receiver with a short test cable terminated with alligator clips.

Detector/audio amplifier and BFO. The audio amplifiers require no adjustment. Align the BFO as follows: Without connecting the BFO to the detector, connect a 51-ohm resistor across the secondary of T4. Set C11 (FREQ ADJ) and C12 (OUTPUT TUNE) to midrange. Apply 12 V dc to the BFO. Set the test receiver for CW reception at 4000 kHz and attach the shield clip of its test cable to the BFO ground foil. Leave the center-conductor clip unconnected. Next, tune in the BFO on the test receiver. Adjust C12 for maximum received signal as indicated by the test receiver S-meter. Adjust C11 to put the BFO at approximately 4000.5 kHz. This completes alignment of the BFO for now. Remove the 51-ohm resistor from the T4 secondary and connect the BFO to the detector with RG-174 cable.

Mixer, filter and IF amplifier. The IF amplifier requires only one adjustment: With 12 V applied to the mixer/filter/IF amplifier board and later stages, adjust C8, IF TUNE, for maximum noise in the speaker or headphones.

Local oscillator tuning range. Connect the LO output cable to the mixer, and apply 12 V to the LO. Tune C9 to the low end of its range, and set the test receiver to 14.060 MHz. Connect the test cable shield clip to the LO box, but leave the center-conductor clip unconnected. Adjust C10 until you hear the LO in the test receiver. Be sure that the unconnected test-cable lead is far enough from the LO tuned circuit to have no effect on the LO frequency. Set the test receiver to 14.155 MHz. Tune the LO upward in frequency until you hear it in the test receiver. With luck, the TUNING capacitor will be nearly at minimum capacitance. Depending on the exact values of the capacitors in the Q4 gate circuitry, however, your LO may not have enough tuning range, requiring that you search downward for it with the test receiver even with the TUNING capacitor at minimum capacitance. If this is so, move the tap on L5 from 2 to 3 turns above ground and readjust the 14.060-MHz band edge with C10. This will increase the tuning range. (You may need to add capacitance in parallel with the 27-pF LO tuned-circuit capacitor to allow C9 to hit the band edge.) C10's tuning range is much larger than that of the TUNING capacitor, so adjust it carefully. With experimentation, you should be able to achieve a TUNING range of between 90 and 150 kHz. Remember that you'll need to make your final band-edge adjustment *after* installation of the LO box cover; be sure to provide a hole in the cover for this purpose, but leave the cover off for now. After you have set the LO tuning range, cement the base of each L5 pillar to the shield-box bottom with Duco® (or similar) cement.

RF amplifiers. Install the 10-MHz RF amplifier in the receiver, and solder a 51-ohm resistor from the center conductor of J1 to ground. Connect the crystal calibrator, set for 10-kHz markers, to J1. Set the BAND switch to 10 MHz. Tune in a marker near the center of the tuning range and adjust C3 for maximum signal. Tune in the lowest marker in the range; adjust C5 for maximum signal. Tune in the highest marker in the range; adjust C6 for maximum signal. Because the C5 and C6 adjustments interlock somewhat, repeat them several times for good measure. Now, install the 18-MHz RF amplifier board and repeat this procedure at 18 MHz with C3 (at band center), C5 (at the lowest marker) and C6 (at the highest marker). This completes alignment of the RF amplifier boards.

Anti-backlash adjustment. With luck, the TUNING control will turn freely and require the same input torque across the tuning range. Backlash should be imperceptible throughout the range. If backlash is present, try loosening the reduction-drive coupler screws and tightening them again. Backlash in the ARRL lab version of this receiver was done away with by loosening and retightening the tuning capacitor in its mounting hole, *and* by slipping the TUNING capacitor several degrees to one side in the drive coupling sleeve before retightening the coupler worm screws.

Dial calibration. Calibrate the tuning dial *after* the tuning range has been set *and* any backlash has been ironed out. In the model shown in Fig. 1, calibration of the 10- and 18-MHz TUNING scales differs by the width of a dial marking. The left edge of each mark is used during 18-MHz tuning (18 MHz L); the right edge is used during 10-MHz reception (10 MHz R). Calibration of the full TUNING capacitor rotation (360°; 180° for each band) would make this unnecessary, but one band would tune "backward" relative to the other.

Performance

Measured performance of the band-imaging receiver at 10 MHz: Minimum discernible signal (MDS), −140.5 dBm; two-tone 3rd-order IMD dynamic range (20-kHz spacing), 89.5 dB; blocking dynamic range, 134 dB; image rejection, 74 dB. At 18 MHz: MDS, −140.0 dBm; two-tone 3rd-order IMD dynamic range, (20-kHz spacing), 90.0 dB; blocking dynamic range, 131 dB; image rejection, 82 dB. With a signal tuned in on the 10-MHz band, dropping the receiver three inches to the operating table produced *no discernible shift* in the pitch of the received signal. Maximum audio output was 0.66 W into an 8.2-Ω test load. Current drain at 12 V dc was 95.1 mA with no input signal, 220 mA at maximum audio output.

From June 1976 QST, p 27:

His Eminence—the Receiver

Part 1: No piece of amateur equipment holds greater sway over our communications pastime than the station receiver. Herefrom, let there be dynamic range!

By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250
Luther, MI 49656

Are you slave to a receiver which unleashes its fury like a many-headed monster in the presence of strong signals? If your receiver shows a will which is most incorrect for an expensive commercial ham-shack trapping, then you and I are kindred souls! Being a long-term urban dweller amid a barrage of strong local signals, I have had a long-existing need for a receiver with an "uncrunchable" front end. Numerous commercial receivers have been tested at my station, and most provided appallingly dismal performances when W1AW was operating – just two blocks away – and during contests when seldom-heard, nearby stations seemed to pop out of the void to inundate reception. This case for nail biting led to a special-application design which cured my receiver cross modulation, desensitization, and IMD maladies. Some of the design notes offered here should be of interest to amateurs who build station receivers for use in areas of high signal density.

Most of the principles described are well-known ones, but they have been ignored by some designers of imported and U.S.-made receivers. Emphasis seems to be on impressive appearance, high receiver "sensitivity" (whatever is meant by that term), and myriad other features. Along the way somebody forgot the real name of the game . . . *dynamic range*. At least one amateur (W7ZOI) has emphasized the need for careful attention to these matters.[1] Reasonable immunity to front-end collapse is not expensive or difficult to achieve. The results are measured easily in terms of operating convenience and clean reception.

Front-End Features

Although the circuit treated here is for a one-band receiver (1.8 to 2.0 MHz), the design procedures are applicable to any amateur band in the hf spectrum. In my case, I employ "down converters" to cover 80 through 10 meters. They are founded on the same concepts to be discussed here.



The receiver is built in a homemade aluminum cabinet. A two-tone gray and flat-black paint job has been applied. Black Dymo tape labels are used for identifying the controls in the black area, and gray labels are affixed to the gray portion of the front panel. A cut-down Jackson Brothers vernier dial mechanism (two-speed) is used for frequency readout.

Fig. 1 shows the rf amplifier, mixer, and post-mixer amplifier. What may seem like excessive elaboration in design is a matter of personal whim, but the features are useful, nevertheless. For example, the two front-end attenuators aren't essential to good performance, but are useful in making accurate measurements (6, 12 or 18 dB) of signal levels during on-the-air experiments with other stations (antennas, amplifiers and such). Also, FL2, a fixed-tuned 1.8- to 2-MHz band pass filter, need not be included if the operator is willing to re-peak the three-pole tracking filter (FL1) when tuning about in the band. The fixed-tuned filter is my preference when the down converters are in use.

The benefits obtained from a highly selective tunable filter like FL1 are seen when strong signals are elsewhere in (or near) the 160-meter band. The rejection characteristics can be seen in Fig. 2. Insertion loss was set at 5 dB in order to narrow the filter response. Part of the circuit was inspired by Sabin's informative *QST* article, where he employed a three-pole Cohn filter with a 4-dB insertion loss.[2] In this example the high-Q slug-tuned inductors are isolated in aluminum shields, and the three-section variable capacitor which tunes them is enclosed in a shield made from pc-board sections. Bottom coupling is accomplished with small toroidal coils.

Rf amplifier Q1 was added to compensate for the filter loss. It is mismatched intentionally by means of L10 and L11 to restrict the gain to 6 dB maximum. Some additional mismatching is seen at L12, and the mixer is overcoupled to the FET tuned output tank to broaden the response (1.8 to 2 MHz). The design tradeoffs do not impair performance. The common-gate rf stage has good dynamic range and IMD characteristics.

The doubly balanced diode-ring mixer (U1) was chosen for its excellent reputation in handling high signal levels, having superb port-to-port signal isolation, and because of its good IMD performance. The module used in this design is a commercial one which contains two broadband transformers and four hot-carrier diodes with matched characteristics. The amateur can build his own mixer assembly in the interest of reduced expense. At the frequencies involved in this example it should not be difficult to obtain performance equal to that of a commercial mixer.

In discussing this circuit with Hayward (W7ZOI), he suggested that I include a diplexer at the mixer output (L13 and the related .002-μF capacitors). The addition was worthwhile, as it provided an improvement in the noise floor and IMD characteristics of the receiver. The diplexer works in combination with matching network L14, a low-pass L-type circuit. The diplexer is a high-pass network which permits the 56-ohm terminating resistor to be seen by the mixer without degrading the 455-kHz i-f. The low-pass portion of the diplexer helps reject all frequencies above 455 kHz so that the post-mixer

---

[1] Footnotes appear at end of article.


1.8–2.0 MHz FL1 -5dB
ATTENUATORS
-6dB
-12dB
160 M ANT.
HF CONV.
J1
J2
S1A
S2A
S2B
S3A
S3B
S1B
S1C
C1A
C1B
C1C
TO 100-kHz CALIBRATOR
S.M.-SILVER MICA
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS; k=1000, M=1 000 000
1.8–2.0 MHz FL2 -5dB
RF AMP
MIXER
1.8–2.0 MHz
Q1 2N5486
+6dB
U1
SRA-1-1
LO IN 2255–2455 kHz
455 kHz
Q2 MPF102
Q3 MPF102
RFC1 2.7mH
RFC2 10mH
+12V
I-F PREAMP (+25 dB)
TO FL3, FL4

Fig. 1 — Schematic diagram of the receiver front end. Fixed-value capacitors are disk ceramic unless otherwise noted. Resistors are 1/2-W composition. All slug-tuned inductors are contained in individual shield cans which are grounded.

C1 — Three-section variable, 100 pF per section. Model used here obtained as surplus.
J1 — SO-239.
J2 — Phono jack.
L1, L4 — 38 to 68 μH, Q_u of 175 at 1.8 MHz, slug-tuned (J. W. Miller 43A685CBI in Miller S-74 shield can).
L2, L3 — 95 to 187 μH, Q_u of 175 at 1.8 MHz, slug tuned (J. W. Miller 43A154CBI in S-74 shield can).
L5, L6 — 1.45-μH toroid inductor, Q_u of 250 at 1.8 MHz.
15 turns No. 26 enam. wire on Amidon T-50-2 toroid.
L7, L9 — 13-μH slug-tuned inductor (J. W. Miller 9052).
L8 — 380-μH slug-tuned inductor (J. W. Miller 9057).
L10 — 16 turns No. 30 enam. wire over L11 winding.
L11 — 45 turns No. 30 enam. wire on Amidon T-50-2 toroid, 8.5 μH.
L12 — 42-μH slug-tuned inductor, Q_u of 50 at 1.8 MHz. (J. W. Miller 9054).
L13 — 8.7-μH toroidal inductor. 12 turns No. 26 enam. wire on Amidon FT-37-61 ferrite core.
L14 — 120- to 280-μH, slug-tuned inductor (J. W. Miller 9056).
L15 — 1.3- to 3.0-mH, slug-tuned inductor (J. W. Miller 9059).
Q1, Q2, Q3 — Motorola JFET.
RFC1 — 2.7-mH miniature choke (J. W. Miller 70F273AI).
RFC2 — 10-mH miniature choke (J. W. Miller 70F102AI).
S1 — Three-pole, two-position phenolic wafer switch.
S2, S3 — Two-pole, double-throw miniature toggle.
U1 — Mini-Circuits Labs. SRA-1-1 doubly balanced diode mixer (2913 Quentin Rd., Brooklyn, NY 11229).

For updated supplier address, see ARRL Parts Supplier List in Chapter 2.

amplifier receives only the desired information. The high-pass section of the diplexer starts rolling off at 1.2 MHz. A reactance of 66 ohms was chosen to permit use of standard-value capacitors in the low-Q network.

A pair of source-coupled JFETs is used in the post-mixer i-f preamplifier. The 10,000-ohm gate resistor of Q2 sets the transformation ratio of the L network at 200:1 (50Ω to 10 kΩ). An L network is used to couple the preamplifier to a diode-switched pair of Collins mechanical filters which have a characteristic impedance of 2000 ohms. The terminations are built into the filters.

Gain distribution to the mixer is held to near unity in the interest of good IMD performance. The preamplifier gain is approximately 25 dB. The choice was made to compensate for the relatively high insertion loss of the mechanical filters — 10 dB. Without the high gain of Q2 and Q3 there would be a deterioration in noise figure.

Local Oscillator

A low noise floor and good stability are essential traits of the local oscillator in a quality receiver. The requirements are met by the circuit of Fig. 3. Within the capabilities of the ARRL lab measuring procedures, it was determined that VFO noise was at least 90 dB below fundamental output. Furthermore, stability at 25°C ambient temperature was such that no drift could be measured from a cold start to a period three hours later. Mechanical stability is excellent: Several sharp blows to the VFO shield box caused no discernable shift in a cw beat note while the 400-Hz i-f filter was



Fig. 2 — Response curve of the tunable front-end filter, centered on 1.9 MHz.

actuated. VFO amplifier Q14 is designed to provide the recommended +7-dBm mixer injection. Furthermore, the output pi tank of Q14 is of 50 ohms characteristic impedance. Though not of special significance in this application, the measured harmonic output across 50 ohms is −36 dB at the second order, and −47 dB at the third order.

Filter Module

In the interest of minimizing leakage between the filter input and output ports, I elected to use diode switching. The advantage of this method is that only dc switching is required, thereby avoiding the occasion for unwanted rf coupling across the contacts and wafers of a mechanical switch. Type 1N914 diodes are used to select FL3 (400-Hz bandwidth) or FL4 (2.5-kHz bandwidth). Reverse bias is applied to the nonconducting diodes. This lessens the possibility of leakage through the switching diodes. Because the Collins filters have a characteristic impedance of 2000 ohms, the output coupling capacitors from each are 120 pF rather than low-reactance .01-μF units, as used at the filter inputs. Without the smaller value of capacitance the filters would see the low base impedance of Q4, the post-filter i-f amplifier. The result would be one of double termination in this case, leading to a loss in signal level. Additionally, the 120-pF capacitors help to divorce the input capacitance of the amplifier stage. The added capacitance would have to be subtracted from the 350- and 510-pF resonating capacitors at the output ends of the filters.

The apparent overall receiver gain is greatest during cw reception, owing to the selectivity of cw filter, FL3. To keep the S-meter readings constant for a given signal level in the ssb and cw modes, R7 has been included in the filter/amplifier module. In the cw mode, R7 is adjusted to bias Q4 for an S-meter reading equal to that obtained in the ssb mode. Voltage for the biasing is obtained from the diode switching line during cw reception.

Although a 2N2222A is not a low-noise device, the performance characteristics are suitable for this circuit. A slight improvement in noise figure would probably result from the use of an MPF102, 40673, or low-noise bipolar transistor in that part of the circuit.

Performance Notes

The remainder of the receiver circuit will be discussed in Part 2 of this article. However, the reader may want to know just how well *His Eminence* performs, and how the characteristics compare to these of some modern commercial receivers. It seems fitting that the high points be covered in Part 1.

The tuning range of the receiver is 200 kHz. This means that for use with converters the builder will have to satisfy himself with either the cw or the ssb band segment. The alternatives are to increase the local oscillator tuning range to 500 kHz, or use a multiplicity of converters to cover the cw and ssb portions of each band. Because 160 meters is my primary band for DXing and casual QSOs during the winter season, the bandspread feature of 200 kHz was adopted.

Some severe lab tests were undertaken with the completed receiver, aimed at learning how "crunchproof" the front end really was. A quarter-wavelength end-fed wire (inverted L) was matched to the receiver 50-ohm input port. The far end of the antenna was situated 3 feet away from the W1AW end-fed Zepp antenna. A pk-pk voltage of 15 was measured across the 50-ohm receiver input jack by means of a Tektronix model 453 scope while W1AW was operating. Now, that's a lot of rf energy! With that high level of rf voltage present, a 10-μV signal was fed into the receiver and spotted 2 kHz away from the W1AW operating frequency. No evidence of cross modula-



Considerable space remains beneath the chassis for the addition of accessory circuits or a set of down converters. At the upper left are the adjustment screws for the tunable filter, plus the bottom-coupling toroids. At the left center is the fixed-tuned front-end filter. To the right is the rf-amplifier module. A 100-kHz MFJ Enterprises calibrator is seen at the far lower left. Immediately to its right is the mixer/amplifier assembly. The large board at the lower center contains the i-f filters and post-filter amplifier. Most of the amplifier components have been tacked beneath the pc board because of design changes which occurred during development.

Fig. 3 — Circuit diagram of the local oscillator. Capacitors are disk ceramic unless specified differently. Resistors are 1/2-W composition. Entire assembly is enclosed in a shield box made from pc-board sections.

C2 — Double-bearing variable capacitor, 50 pF.
C3 — Miniature 30-pF air variable.
CR1 — High-speed switching diode, silicon type 1N914A.
L18 — 17- to 41-μH slug-tuned inductor, Q_u of 175 (J. W. Miller 43A335CBI in Miller S-74 shield can).
L19 — 10- to 18.7-μH slug-tuned pc-board inductor (J. W. Miller 23A155RPC).
RFC13, RFC14 — Miniature 1-mH rf choke (J. W. Miller 70F103AI).
VR2 — 8.6-V, 1-W Zener diode.





−10 dB
455 kHz
BW=400 Hz
FL3
→5MA
CR2
CR3
.01
120
350
RFC3 10mH
RFC4 10mH
RFC5 10mH
RFC6 10mH
1500
1000
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF) ; OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS ; k=1000, M=1000 000.
+10 dB
POST-FILTER
I-F AMP
Q4
2N2222A
15
T1
455kHz
2200
27k
470
100
TO U2
I-F AMP
+12V
R7
−6.5V
10k
GAIN (CW)
EQUALIZER
S4A
S4B
SSB
CW
TO U2,U3
5600
−10 dB
455 kHz
BW=2.1 kHz
FL4
510
RFC7 10mH
RFC8 10mH
RFC9 10mH
RFC10 10mH
CR4
CR5

Fig. 4 — Schematic diagram of the filter and i-f post-filter amplifier. Capacitors are disk ceramic. Resistors are 1/2-W composition.

CR2-CR5, incl. — High-speed silicon switching diode, 1N914A.
FL3 — Collins mechanical filter F455FD-04.
FL4 — Collins mechanical filter F455FD-25.
RFC3-RFC10, incl. — 10-mH miniature rf choke (J. W. Miller 70F102A1).
R7 — Pc-board control, 10,000 ohms, linear taper.
S4 — Double-pole, double-throw toggle or wafer.
T1 — Miniature 455-kHz i-f transformer (J. W. Miller 2067, 30,000 to 500 ohms).

tion could be observed, and desensitization of the receiver could not be discerned by ear. The spread from 1.8 to 2 MHz was tuned, and no IM products were heard.

Dynamic range tests were performed in accordance with the Hayward paper in *QST* for July, 1975. Noise floor was −135 dBm, IMD was 95 dB, and 1 dB of blocking occurred at some undetermined point greater than 123 dB above the noise floor. The latter measurement is inconclusive because blocking did not become manifest within the output capability of the model-80 generators used in the ARRL lab. The resultant receiver noise figure at 1.8 MHz is 13 dB, which is more than adequate for the high atmospheric noise level on 160 meters.

Table 1 shows measured characteristics for numerous current-model commercial amateur receivers. Brand names can not be listed, but the same test equipment and procedures were used for all checks. It should be kept in mind that the higher the noise-floor figure in −dBm, the better the performance. Similarly, the higher readings for IMD and blocking indicate best performance.

Mute testimony is seen in Table 1. It seems incredible that the three best receivers for IMD and blocking are homemade or modified commercial stock models! It is worth adding that the worst performers are not necessarily the least expensive receivers available. You figure it out, eh? Part 2 of this article will appear in a subsequent issue of *QST.*

Table 1

RECEIVER	*IMD TWO-TONE DYNAMIC RANGE (dB)*	*BLOCKING ABOVE NOISE FLOOR (dB)*	*NOISE FLOOR (−dBm)*
W7ZOI Rcvr. from *QST* March 1974	95.5	123	141
W1CER Rcvr. from *QST* June 1976	95.0	123+	135
Import 1 (modified by ARRL) WA1LNQ	92.5	136	145
Same Rcvr. before modification	79.0	110	136
USA Box 1	88.0	116.5	146
USA Box 2	86.0	116	143
USA Box 3	86.0	112	135
USA Box 4	84.0	112	135
USA Box 5	76.0	114	137
USA Box 5 (modified)	83.6	120	141.5
Import 2	79.5	112	139
USA Box 6	79.5	92	123
Import 3	79.0	110	136
USA Box 7	74.5	100	139
USA Box 8	70.0	97	139
Import 4	59.0	102	141

All receivers tested were equipped with 400-, 500-, or 600-Hz i-f filters. Tests were made on 20 meters. Sig. spacing = 20 kHz.

W1CER rcvr. with W7ZOI 20-meter converter attached			
	88	123+	133

Footnotes

[1] Hayward, "A Competition-Grade CW Receiver," *QST* for March and April, 1974.

[2] Satin, "Solid-State Receivers," *QST* for July, 1970.

From July 1976 QST, p 14:

His Eminence—the Receiver

Part 2: Front end — stay worthy of your vocation with "uncrunchable" distinction! And now the final circuit details.

A receiver i-f system should be capable of providing a specific gain, have an acceptable noise figure, and respond satisfactorily to the applied agc. This almost bromidic judgment is not as trite as it may seem, for some designers use a haphazard approach to this part of a receiving system. Two of the more serious shortcomings in some designs are poor agc (clicky, pumping, or inadequate range) and insufficient i-f gain.

Because of my fringe lassitude and an unwillingness to question past successes, I elected to use a pair of RCA CA3028A ICs in the i-f strip. Somewhat greater i-f gain and agc range are possible with MC1590G ICs: They are the choice of many builders. However, the CA3028As, configured as differential amplifiers, will provide approximately 70 dB of gain per pair when operated at 455 kHz. This gives an agc characteristic from maximum gain to full cutoff which is entirely acceptable for most amateur work.

Top-chassis view of the receiver. The R-C active filter and audio preamplifier are built on the pc board at the upper left. To the right is the BFO module in a shield box. The agc circuit is seen at the lower left, and to its right is the i-f strip in a shield enclosure. The large shield box at the upper center contains the VFO. To its right is the tunable front-end filter. The three-section variable capacitor is inside the rectangular shield box. The audio amplifier module is seen at the lower right. The small board (mounted vertically) at the left center contains the product detector. Homemade end brackets add mechanical stability between the panel and chassis and serve as a support for the receiver top cover.



Fig. 5 shows the i-f amplifiers, product detector, and Varicap-tuned BFO. Transformer coupling is used between U2 and U3, and also between U3 and the product detector. The 6800-ohm resistors used across the primaries of T2 and T3 were chosen to force an impedance transformation which the transformers can't by themselves provide. Available Miller transformers with a 30,000-ohm primary to 500-ohm secondary characteristic are used. U2 and U3 have 10- and 22-ohm series resistors in the signal lines. These were added to discourage vhf parasitic oscillations.

Agc is applied to pin 7 of each IC. Maximum gain occurs at +9 V, and minimum gain results when the agc voltage drops to its low value, +2 V. The agc is rf-derived, with i-f sampling for the agc amplifier being done at pin 6 of U3 through a 100-pF blocking capacitor.

The 1000-ohm decoupling resistors in the 12-V feed to U2 and U3 drop the operating voltage to +9. This aids stability and reduces i-f system noise. The amplifier strip operates with unconditional stability.

Product Detector

A quad of 1N914A diodes is used in the product detector. Hot-carrier diodes may be preferred by some, and they may lead to slightly better performance than the silicon units I chose. A trifilar broadband toroidal transformer, T4, couples the i-f amplifier to the detector


I-F AMP
I-F AMP
PROD DET
TO T1 (FIG. 4)
RFC11 2.5mH
CA 3028A
U2
U3
T2 455 kHz
T3 60:1 455 kHz
T4
CR7
CR6
CR9
CR8
TO AGC AMP (Q10, FIG. 6)
AF OUT (Q7, FIG. 7)
AGC (TO U4 OF FIG. 6)
+12V
+9V TO +2V
7V RMS
BFO
AMPLIFIER
VR1 9.1V 1W
Q5 2N2222A
Q6 2N2222A
455 kHz
L16
L17
RFC12 10 mH
BFO TUNE R1 100k
CR10 MV104
POLY
POLY = POLYSTYRENE
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS; k=1000, M=1000 000

Fig. 5 — Circuit of the i-f amplifier, BFO, and product detector. Capacitors are disk ceramic unless noted differently. Fixed-value resistors are 1/2-W composition. Dashed lines show shield enclosures. The BFO and i-f circuits are installed in separate shield boxes. The R-C active filter and af preamplifier are on a common circuit board, which is not shielded.

CR6-CR9, incl. — High-speed silicon, 1N914A or equiv.
CR10 — Motorola MV-104 Varicap tuning diode.
L16 — Nominal 640-μH slug-tuned inductor (J. W. Miller 9057).
L17 — Nominal 60-μH slug-tuned inductor (J. W. Miller 9054).
R1 — 100,000-ohm linear-taper composition control (panel mount).
RFC11 — 2.5-mH miniature choke (J. W. Miller 70F253A1).
RFC12 — 10-mH miniature choke (J. W. Miller 70F102A1).
T2, T3 — 455-kHz i-f transformer. See text. (J. W. Miller 2067).
T4 — Trifilar broadband transformer. 15 trifilar turns of No. 26 enam. wire on Amidon T-50-61 toroid core.
U2, U3 — RCA IC.
VR1 — 9.1 V, 1 W Zener diode.

For updated supplier address, see ARRL Parts Supplier List in Chapter 2.

at a 50-ohm impedance level. BFO injection is supplied at 0.7 V rms.

BFO Circuit

In the interest of lowering the cost of this project, a Varicap (CR10 of Fig. 5) is used to control the BFO frequency. Had a conventional system been utilized, three expensive crystals would have been needed to handle upper sideband, lower sideband and cw. The voltage-variable capacitor tuning method shown in Fig. 5 is satisfactory if the operator is willing to change the operating frequency of the BFO when changing receive modes. Adjustment is done by means of front-panel control R1. Maximum drift with this circuit was measured as 5 Hz from a cold start to a time three hours later. A Motorola MV-104 tuning diode is used at CR10.

To vary the BFO frequency from 453 to 457 kHz, the diode is subjected to various amounts of back bias, applied by means of R1. Regulated voltage (VR1) is applied to the oscillator and tuning diode.

Q6 functions as a Class A BFO amplifier/buffer. It contains a pi-network output circuit and has a 50-ohm output characteristic. The main purpose of the amplifier stage is to increase the BFO injection power without loading down the oscillator.

AGC Circuit

Fig. 6 shows the agc amplifier, rectifier, dc source follower, and op-amp difference amplifier. An FET is used at Q10 because it exhibits a high input impedance and will not, therefore, load down the primary of T3 in Fig. 5. Q1 is direct coupled to a pnp transistor, Q11. Assuming that Rs and R2 are treated as a single resistance, Rs, the Q10/Q11 gain is determined as: Gain (dB) = 20 log Rc ÷ Rs. Control R2 has been included as part of Rs to permit adjustment of the agc loop gain. Each operator may have a preference in this regard. I have the agc set so it is fully actuated at a signal-input level of 10 μV. Agc action commences at 0.2 μV (1 dB of gain compression).

Agc disabling is effected by removing the operating voltage from Q10 and Q11 by means of S5. Manual i-f gain control is made possible by adjusting R3 of Fig. 6. Agc delay is approximately 1 second. Longer or shorter delay periods can be established by altering the values of the Q14 gate resistor and capacitor. Agc amplifier gain is variable from 6 to 40 dB by adjusting R2. The arrangement at Q14 and U4 was adapted from a design by W7ZOI. Agc action is smooth, and there is no evidence of clicks on the attack during strong-signal periods. At no time has agc "pumping" been observed.

Audio System

A major failing of many receivers is poor-quality audio. For the most part this malady is manifest as cross-over distortion in the af-output amplifier. Moreover, some receivers have marginal audio-power capability for normal room volume when a loudspeaker is used. Some transformerless single-chip audio ICs (0.25- to 2-W class) exhibit a prohibitive distortion characteristic, and this is especially prominent at low signal levels. The unpleasant effect is one of "fuzziness" when listening to low-level signals. Unfortunately, external access to the biasing circuit of such ICs is not typical, owing to the unitized construction of the chips.

Since "sanitary" audio is an important feature of a quality communications receiver, I used a circuit containing discrete devices. The complimentary-symmetry output transistors and the op-amp driver are configured in a manner similar to that used by Jung in his *Op Amp Cookbook* published by Howard Sams. Maximum output capability is 3.5 W into an 8-ohm load. An LM-301A driver was chosen because of its low-noise profile. There has been no aural evidence of distortion at any signal level while using the circuit of Fig. 7. The game played in this situation is one of having considerably more audio power available than is ever needed — a rationale used in hi-fi work.

R-C Active CW Filter

A worthwhile improvement in signal-to-noise ratio can be realized during weak-signal reception by employing an R-C active bandpass filter. A two-pole version (FL5) is shown in Fig. 7. A peak frequency of 800 Hz results from the *R* and *C* values given.

The benefits of FL5 are similar to those described by Hayward in his "Competition-Grade CW Receiver" article, which was referenced earlier. He used a second i-f filter (at the i-f strip output) to reduce wide-band noise in the system. The R-C active filter serves in a similar manner, but performs the signal "laundering" at audio rather than at rf. The technique has one limitation — monotony in listening to a fixed-frequency beat note, which is dictated by the center frequency of the filter. The R-C filter should be designed to have a peak frequency which matches the cw beat-note frequency preferred by the operator. That is, if the BFO is adjusted to provide an 800-Hz cw note, the center frequency of FL5 should also be 800 Hz.

Fig. 6 — Schematic diagram of the agc system. Capacitors are disk ceramic except when polarity is indicated, which signifies electrolytic. Fixed-value resistors are 1/2-W composition. This module is not enclosed in a shield compartment.

CR12, CR13 — High-speed silicon. 1N914A or equiv.
Q10, Q11, Q14 — Motorola transistor.
R2, R4, R5 — Linear-taper composition pc-board mount control.
R3 — 10,000-ohm linear-taper control, panel mounted.
RFC15 — 2.5-mH miniature choke (J. W. Miller 70F253A1).
S5 — Single-pole, single-throw toggle.
U4 — Dual-in-line 8 pin 741 op amp.
M1 — 0- to 1-mA meter.



Experience with FL5 in this receiver has proved in many instances that weak DX signals on 160 meters could be elevated above the noise to a Q5 copy level, while without the filter solid copy was impossible. It should be stressed that high-*Q* capacitors be used from C4 to C7, inclusive, to assure a sharp peak response. Polystyrene capacitors satisfy the requirement. To ensure a well-defined (minimum ripple) center frequency, the capacitors should be matched closely in value (5 percent or less). Resistors of 5-percent tolerance should be employed in the circuit, where indicated in Fig. 7.

Summary Comments

A suitable frequency scheme for some hf-band down converters, plus a circuit for digital frequency display, are given in the receiving chapter of the 1976 *Handbook*. In that example the tunable i-f receiver covers 500 kHz, 1.8 to 2.3 MHz.

The photograph in this article illustrates a modular construction technique. All rf-circuit assemblies are isolated from one another, and from outside energy influences, by means of shield compartments. Signal points are joined (module to module) with RG-174/U subminiature coaxial cable, the shield braids being grounded to the chassis at each end. Feedthrough-type .001-µF capacitors are used at the 12-V entry points of the modules. The foregoing measures help to prevent birdies and unwanted stray rf pickup.

The intent of this paper has been to illustrate some ordinary design principles which can be adopted by those wishing to construct a receiver with wide dynamic range. Some of the ideas offered may inspire modifications to commercial receivers. Because this presentation was not meant as a construction exercise, circuit-board templates are not offered. Most of the pc boards in this prototype have been altered severely during the development pro-


DRIVER
3.5-W AF OUTPUT
AF PREAMP
Q7 2N2222A
TO PROD DET (FIG 5)
AF GAIN R6 10k
U4 LM301A
Q8 2N5880/S7003
Q9 2N5881/S7002
J3 LO-Z PHONES OR 8-OHM SPKR.
CR11 1N914A
+12V
U5A N5558
U5B
C4
C5
C6
C7
.001 POLY.
1.8M
680k
24k 5%
27k
S6A
S6B
ON
OFF
FL5 RC ACTIVE 750-Hz CW FILTER
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k=1000, M=1000 000.
POLY. = POLYSTYRENE

Fig. 7 — Diagram of the audio amplifier and R-C active filter. Capacitors are disk ceramic unless otherwise noted. Polarized capacitors are electrolytic or tantalum. Fixed-value resistors are 1/2-W composition. This circuit is not contained in a shield box. Heat sinks are used with Q8 and Q9.

CR11 — High-speed silicon, 1N914A or equiv.
C4-C7, incl. — See text.
J3 — Phone jack.
R6 — 10,000-ohm audio-taper composition control, panel mounted.
S6 — Double-throw, double-pole toggle.
U4 — National Semiconductor LM-301A IC
U5 — Signetics N5558 dual op-amp IC.

cess, and numerous components have been tacked on here and there. For this reason, artwork has not been developed.

During several months of daily use, there has never been a case of desensitization or IMD noted, despite my nearness to W1AW and neighboring contesters and DXers. *His Eminence* is, indeed, uncrunchable!

From June 1976 QST, p 31:

CER-verters

A family of high-performance hf-band converters for the W1FB (ex-W1CER) 160-meter "His Eminence" receiver.

By Wes Hayward,* W7ZOI

If big signals are taking "pot shots" at your collapsing receiver front end, some design changes are probably needed. Here are some guidelines for amateur and professional designers who are interested in improving receiver dynamic range – a sore point with respect to the performance of many modern-day commercial receivers.

This issue of *QST* contains an article describing some recent receiver efforts at W1CER.[1] That receiver was built to serve two purposes. First, it provided high quality performance on 160 meters. Secondly, and of more significance, it was part of a continuing campaign by W1CER and this writer to develop receivers which meet the classic performance goals of sensitivity, selectivity and stability, while still maintaining a suitable dynamic range.[2,3] As DeMaw pointed out in his two-part article, the amateur can do a much better job than the manufacturer in this regard.

As exciting as the 160-meter band can be, predominant interest is in the hf spectrum. As a result, a group of crystal-controlled converters was needed for the W1CER receiver with an i-f output in the 1.8- to 2-MHz region. Such a family is described here. The primary criterion for their design was to maintain a large dynamic range in a *dual-conversion* system, while still realizing a noise figure that was low enough to be acceptable on the various hf bands.



The information provided to the writer by W1CER was that the minimum discernable signal (MDS), also called the equivalent noise floor of the receiver, was −135 dBm with a 400-Hz bandwidth. Further, the two-tone dynamic range of the receiver was 95 dB.

Information of this type can be related to other more fundamental specifications with a fairly simple set of equations. The noise figure of a receiver is related to the MDS by Eq. 1:

$$\mathrm{MDS(dBm)} = -174\ \mathrm{dBm} + \mathrm{NF(in\ dB)} + 10\log_{10}B_n \qquad \text{(Eq. 1)}$$

where B_n is the noise bandwidth of the receiver. The noise bandwidth is well-approximated by the 3-dB bandwidth when steep-skirted filters are used, which was the case for the W1CER receiver.

Similarly, the two-tone dynamic range of the receiver is related to the input intercept, P_i and the MDS by Eq. 2:

$$\mathrm{DR(indB)} = (2/3)(P_i - \mathrm{MDS}) \qquad \text{(Eq. 2)}$$

where both P_i and MDS are given in dBm. This equation is easily derived from the definition of the intercept concept and the observation that third-order IMD products are proportional to the cube of the strength of the input signals.

A final equation of significance is that which relates the noise factor of two cascaded stages. This relationship, which would apply to a crystal-controlled converter ahead of a receiver, as well as a preamplifier preceding a receiver, is given in Eq. 3:

$$F_{net} = F_1 + \frac{F_2 - 1}{G_1} \qquad \text{(Eq. 3)}$$

In this equation, F_1 and F_2 are noise factors which are algebraic ratios. Noise figure is just the decibel equivalent of this factor. G_1 is the gain of the first stage, again as an algebraic ratio. F_{net} is the noise factor of the combination of a given receiver with a preamplifier or converter with noise factor F_1, and gain, G_1.

From Eqs. 1 and 2, it may be shown that the W1CER receiver had a noise figure of 13 dB and an input intercept of +7.5 dBm. Eq. 3 may be used to infer the overall noise figure when various converter noise figures and gains are considered. The input intercept of a combination will merely be the input intercept of the basic receiver less the gain of the converter. This assumes that the converter is strong enough that minimal IMD occurs within the converter when compared with the following receiver. This implies explicitly that the output intercept of the converter should be much larger than the input intercept of the following receiver.

Converter Designs

After a bit of number "crunching" with the foregoing equations, it was concluded that the converters should have a net gain of about 10 dB and an output intercept of approximately +17 dBm or higher. For work on the bands up through 14 MHz a noise figure of 13 to 16 dB was deemed acceptable. On the higher bands some compromise in

[1] Footnotes appear at end of article.

*7700 S.W. Danielle Ave., Beaverton, OR 97005



Fig. 1 — Block diagram of the CER-verters.

dynamic range would be tolerable in order to achieve lower noise figures. In studying the available circuit combinations it was decided to base the front end of the converters on a diode-ring mixer. The mixer would be preceded by a band-pass preselector filter and followed with a diplexer and a dual-gate MOSFET amplifier at 1.9 MHz. A block diagram of the system is shown in Fig. 1.

The original intention was to construct separate converters for each band, 80 through 10 meters. However, after reviewing the design requirements, this was found to be redundant. Diode-ring mixers are inherently broadband and do not require tuned circuits. Further, the post-mixer amplifier would be identical for all of the bands. Only the front-end preselector networks and local oscillators need be changed between bands. The final configuration chosen was to use a master board which contained the diode-ring mixer and a post-mixer amplifier. A family of boards was then constructed, each containing a suitable local oscillator and the preselector network for the band of interest.

Mixer and Post-Amplifier Board

The circuit for the mixer and the dual-gate MOSFET amplifier is shown in Fig. 2. There are a few departures from the standard in this design. First, a diplexer is used between the mixer and the "post-amp." This network serves a number of purposes. First, the inductor (L1) and capacitor (C1) driving the FET form an *L* network which provides an impedance transformation to the gate of the amplifier. A 2200-ohm resistor at the gate assures a termination, causing the mixer to see 50 ohms in the 1.9-MHz frequency range. The other part of the diplexer (C2, C3 and L2) is a high-pass filter designed for a cutoff frequency of 5 MHz. This filter provides a constant i-f termination for the diode ring at virtually *all* frequencies. This is important if the IMD properties of the diode-ring mixer are to be preserved. Such a mixer will create sum-and-difference frequencies from the LO and rf inputs. The difference frequency is used to drive the W1CER receiver. However, a termination must also be provided for the sum frequency.

Fig. 2 — Schematic diagram of the master mixer and amplifier circuit. Fixed-value capacitors are disk ceramic unless noted otherwise. Resistors are 1/2-W composition. See Tables 1 and 2 for component values not marked. U1 is a Mini-Circuits Lab ML-1 doubly balanced diode mixer.



In order to simplify the band switching, +12 volts dc is supplied through the local oscillator port of the mixer. This is realized with an rf choke and suitable capacitors.

The output of the amplifier was designed for broadband performance. In order to obtain large bandwidth, the output transformer (T1) was wound on a high-permeability ferrite toroid. A powdered-iron core should not be used for this transformer. Indeed, it was found that a ferrite core with a permeability of 125 was not suitable in this position. Much better bandwidth and impedance matching was obtained with the core specified which has a permeability of 2000. The 2200-ohm resistor in the drain circuit ensures that the output impedance presented by the amplifier is close to 50 ohms. This is important in order to keep the input filters of the W1CER receiver terminated properly.

A ferrite bead is used on gate 2 of the amplifier. This may not be necessary in some cases. However, it was included to lessen the possibility of uhf oscillations occurring within the amplifier.[4] A Fairchild FT-0601 or RCA 40673 dual-gate MOSFET can be used at Q1

Front-End Sections

Shown in Fig. 3 is the circuit used as the front end for each of the lower-input bands (3.5-3.7, 7.0-7.2 and 14.0-14.2 MHz). Component values are given in Tables 1 and 2.

The local oscillator for each of the converters uses a bipolar transistor and is designed to provide an output from +10 to +13 dBm. This level of LO injection was found to be near optimum for the diode-ring mixer that was used.

The preselector filters are fairly elaborate. However, the results are well worth the extra expense and effort. Predistorted filter-synthesis methods were used to write a computer program for design of the band-pass filters. The coils were wound prior to filter design. Their unloaded *Q* values were measured with a laboratory *Q* meter, and the results were then inserted into the program in order to arrive at the capacitor values. All band-pass filters were designed for a three-pole Butterworth response.

One problem with multisection filters using capacitors as coupling elements between the resonators is that the stopband attenuation may degrade in the vhf spectrum. This is due to slight amounts of lead inductance in the tuning capacitors, and the fact that the capacitive-intersection coupling method degenerates toward a high-pass filter

Table 1

BAND (MHz)	L3, L4, L8 (TURNS-CORE)	L9 (TURNS-CORE)	L5, L6, L7 L10, L11, L12 (TURNS-CORE)	T2, T3 (TURNS-CORE)
3.5 to 3.7	19, No. 22 T50-2	none	35, No. 24 T68-2	25, No. 24 T50-2, 2-t. link
7.0 to 7.2	15, No. 22 T50-2	none	20, No. 22 T68-6	25, No. 24 T50-2, 2-t. link
14 to 14.2	12, No. 22 T50-6	none	12, No. 22 T68-6	28, No. 24 T50-6, 3-t. link
21 to 21.2	10, No. 22 T50-6	21, No. 22 T50-6	10, No. 22 T50-6	19, No. 24 T50-6, 2-t. link

Coil and transformer data. Toroid cores are Amidon Assoc. powdered-iron type. Y1, Y2, Y3 and Y4 for 3.5 through 21 MHz, respectively, are 5.5, 5.2, 12.2 and 19.2 MHz. (International Crystal Co. type GP, 30-pF load capacitance.)

response away from the passband. In order to suppress these responses, should they occur, a 5-pole low-pass filter is included at the antenna terminal.

Two methods were used for evaluation of the filter designs. First, after initial calculation of the component values, a computer program was used to determine the frequency response of the filters over a wide range. In this analysis, resistors were placed in the circuit to simulate the distortion effects caused by the losses in the cores.[5]

After the filters were built and aligned in the home shop, they were checked with laboratory instrumentation. In this case a Tektronix 7L13 spectrum analyzer and TR-502 tracking generator were used. The measured results around the passband corresponded very well with the computer simulation (which is always encouraging to see). The stop-band attenuation was measured, with one exception, to be over 100 dB for all three filters evaluated. The exception was for the 80-meter filter. At about 70 MHz the attenuation degraded to roughly 95 dB, but returned to the better values at frequencies up through 200 MHz.

One of the reasons a Butterworth response was chosen was that this filter shape is aligned easily with simple test equipment. Alignment is performed by driving the filter with a 50-ohm signal generator and terminating the output in a sensitive 50-ohm detector. The generator is set at the center frequency of the filter and the variable capacitors are adjusted for a maximum response. Experimentally, it was not found necessary to readjust the filters when the swept instrumentation was available.

The converter for the 15-meter band was built using the circuit in Fig. 4. On this band it was felt that a better noise figure might be useful. This was provided by inserting an rf amplifier between the low-pass filter and the bandpass circuit. The low-pass circuit was modified. The input section is a symmetrical pi network with a Q of 1. This is followed by a pi network with a Q of 10 and an impedance transformation from 50 to 2000 ohms. A 3300-ohm resistor is used in the drain circuit to ensure proper termination of the bandpass filter. In the unit built, the drain was attached directly to the hot end of the resonator (L10). However, it would be desirable to reduce the gain somewhat. This would be realized easily by tapping the drain down on the tuned circuit. The terminating resistor should remain across L10.

One problem that the builder may encounter is in obtaining capacitors for the coupling elements between resonator sections of the filter. These values are critical and should not be changed casually. However, the capacitors may be replaced by a more complicated equivalent network. The basis of this equivalent circuit is to replace a desired capacitor with a series combination of two capacitors with a value which is more than twice the original value. A third capacitor is then placed from the junction of the series capacitors to ground. This configuration is shown in Fig. 5 along with the equations for picking the proper values. As an example, consider the 14-MHz filter, where 3.3-pF coupling capacitors are used. This single capacitor could be replaced with three 10-pF capacitors.

Those building the converter for 80 meters may wish to cover also the 75-meter phone band. While the filter shown could probably be realigned for a range about 100 kHz higher, the shape of the filter would no doubt deteriorate if it were moved further. A better approach would be to change the value of the inductors. Proper results should be obtained by reducing the coils from 35 to 32 turns, keeping all capacitor values the same. A 5.8-MHz crystal would be required for tuning the range from 4.0 to 3.8 MHz.

Additional Design Notes

The reader should note that the tuning will be "backwards" for the 80-meter band. This was done for two reasons. First, difficulty was encountered in making the oscillator shown operate properly with the 1.7-MHz crystal that was tried. Of greater significance was the fact that the mixer balance was not especially good at this frequency. As a result, a strong 1.7-MHz signal would have appeared at the input to the post-mixer amplifier. This could have resulted in IMD products. Furthermore, for the 75-meter band the crystal would have been at 2.0 MHz if low-side injection were used. This would have

Fig. 3 — Diagram of the filter and crystal oscillator used on 20, 40 and 80 meters. Numbered fixed-value capacitors are silver micas. Resistors are 1/2-W composition. See Tables 1 and 2 for parts values.


50-OHM ANT.
L3
L4
FILTER
TO DIODE-RING RF PORT
C4
C5
C6
C7
C8
C9
C10
C11
C12
C13
C14
C15
C16
L5
L6
L7
RFC2
100mH
.1
100
T2
L0
OSC
.1
10k
.01
TO DIODE-RING LO PORT
2N2222A
C18
Y1-Y3
4700
C17
1000
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS; k=1000, M=1 000 000

Table 2

BAND (MHz)	C4, C6 C13 (pF)	C5, C20 (pF)	C7 (pF)	C8 (pF)	C9, C12 C15 (pF)	C10 (pF)	C11 (pF)	C13 (pF)	C14 (pF)	C16 (pF)	C17, C31 (pF)	C18, C32 (pF)	C21 (pF)
3.5 to 3.7	790	1580	130	–	90 to 400	12	–	10	–	91	100	400	–
7.0 to 7.2	450	890	43	–	90 to 400	4.7	–	4.7	–	62	100	400	–
14 to 14.2	220	450	33	90	20 to 90	3.3	90	3.3	90	22	47	20 to 90	–
21 to 21.2	150	300, 345	–	51	20 to 90	1.2	51	1.2	51	12	47	20 to 90	20 to 90

Fixed-value and trimmer capacitors. Fixed-value capacitors are silver-mica or similar high-*Q*, stable types. Trimmers are mica compression type. See text for obtaining precise non-standard fixed-capacitance values.

placed a strong signal within the tuning range of the main receiver. If it is desirable that all hf bands tune in the same direction, the builder should pick high-side crystals for all of the bands.

The approach used for the 15-meter converter in order to obtain low-noise performance could also be applied to the 10- and 6-meter bands. The image rejection might be a little poor with such a low i-f in the 6-meter case.

Another revision that many builders may consider would be the construction of a high-performance 80-meter receiver with converters for the higher bands. The converters described would be suitable for this situation. The crystal frequencies would change accordingly. The diplexer between the diode mixer and the "post amp" should be redesigned. This could be done easily by halving the inductance and capacitance values used in the diplexer circuit. The broadband output circuit in the drain of Q1 should work equally well at 3.5 MHz. The 15- and 20-meter band-pass filters were designed with enough bandwidth to cover the total band. This was done in order to keep the insertion losses at a reasonable level. A slightly wider filter would be required for the total 40-meter band.

The converters are built on rather large circuit boards. This was done in order to ensure a reasonable level of stopband rejection in the filters, and to ease construction. Those interested in a more compact format should consider the inclusion of shields between the sections of the input band-pass filter and between the filter circuitry and the corresponding oscillators. It is fun to build miniature equipment when there is a good need for small size. However, for high-performance home-station equipment, where considerable experimentation may be required, a larger format is often desirable.

Because the pc boards shown in the photograph are quite large, the builder will probably elect to lay the circuits out for a more compact format. For this reason there are no pc-board templates and layouts available.

Great care should be taken when the front-end sections are band switched. Shielding between switch wafers should have over 100 dB of isolation. Diode switching is not recommended unless the builder has equipment to evaluate the effects on IMD.

Evaluation and Performance

This project was in some ways quite frustrating, for the W1CER receiver was 3000 miles away. This is the first piece of receiving gear that the writer has built which could not initially be evaluated "by ear." However, a suitable substitute was available for laboratory evaluation. This was a Tektronix 7L5 Spectrum Analyzer. This instrument was extremely convenient to use for this purpose, since it is synthesized with a 250-Hz accuracy, and has resolution down to 10 Hz. The dynamic range is excellent.

The only converter evaluated for IMD was the 14-MHz unit. Two-tone IMD measurements were performed and it was found that the output intercept of the converter was +22 dBm. This is

Fig. 4 — Diagram of the 15-meter front end circuit. Numbered fixed-value capacitors are silver micas. Resistors are 1/2-W composition. See Tables 1 and 2 for other parts values.





Fig. 5 — Method for obtaining filter coupling capacitors of computed values.

more than sufficient for the application, since it greatly exceeds the input intercept of the W1CER receiver, +7.5 dBm.

The gain and MDS were measured for all four converters. To remove the effect of the high noise figure of the 7L5 (19 dB), a low-noise MOSFET preamp was built at 1.9 MHz. This unit had a noise figure under 2 dB, allowing meaningful measurement of converter MDS. The signal generator used was an HP-8640B. On the three lower bands, the resultant noise figure of the converters was 12 dB, plus the loss of the input filters. Similarly, the gain of the converter was 12.5 dB, minus the loss of the input filters. It was found that the gain and noise figures could both be improved by removing the 2200-ohm resistor at the gate of Q1. There was a slight reduction in the output intercept, but not enough to cause problems. However, the low-pass part of the diplexer became much sharper in frequency response. This would make a front panel trimmer control necessary.

The 15-meter converter performed differently. The net gain of this unit was 32.5 dB and the noise figure was about 3 dB. This is actually too much sensitivity to be usable at this frequency. It is highly recommended that the builder move the drain tap on the band-pass filter as outlined.

On the basis of the measured results and the published data for the W1CER receiver, the system results may be calculated. Shown in Table 3 are the predicted system noise figure, MDS for a 400-Hz bandwidth, input intercept and two-tone dynamic range for the converters operating into the DeMaw receiver. Also shown are the measurements that were obtained for image rejection and i-f feedthrough for the four converters.

Table 3

BAND (METERS)	*NFIG. (dB)*	*MDS (dBm)*	*P_i (dBm)*	*DR (dB)*	*IMAGE REJ. (dB)*	*I-F FEEDTHROUGH (dB)*
80	14.8	−133.2	−2.5	87.1	−90	−110
40	16.3	−131.7	−1.0	87.1	−110	−94
20	16.3	−131.7	−1.0	87.1	−95	−112
15	3.1	−145	−25.0	80.0	−100	not measured

It is interesting to note that the dynamic range of the system has decreased from 95 dB on 160 meters to 87 dB on the hf bands. This decrease is to be expected in any multiconversion system. Note also that the dynamic range is constant on the three lower bands. This results because the only variation between bands is in the insertion loss of the preselector filters. This difference is the same as would be obtained by adding attenuation to the front end of the receiver. An attenuator will change both the MDS and the input intercept by the same amount, leaving the two-tone dynamic range as a constant of the system. While front-end attenuators are useful accessories for the receiver, they will not improve the dynamic range as is sometimes implied.

A more careful application of attenuation can, however, result in an improved dynamic range. Consider the effect of switching in the 6-dB input attenuator of the W1CER receiver, *after* the converters. The input intercept of the 160-meter tunable i-f will now increase to +13.5 dBm and the noise figure will become 19 dB. If the net result is evaluated using the earlier equations, the 20-meter MDS will degrade by only 0.7 dB, but the system input intercept will move up to +5 dBm, leaving a net dynamic range of 90.6 dB. This is a dramatic demonstration of the effect of gain distribution upon dynamic range, especially in multiconversion receivers.

References

[1] DeMaw, "His Eminence the Receiver," *QST*, June and July, 1976

[2] Hayward, "A Competition-Grade CW Receiver," *QST*, March and April, 1974.

[3] Hayward, "Defining and Measuring Receiver Dynamic Range," *QST*, July 1975.

[4] Reisert, "Low-Noise 29 MHz Preamplifier for Satellite Reception," *Ham Radio*, Oct., 1975.

[5] Hayward, "Bandpass Filters for Receiver Preselectors," *Ham Radio*, Feb., 1975.

From June 1987 QST, p 30:

Build Your Own MCM ICs



MCMs (mini circuit modules) are fun to lay out and build. With a few IC headers and some patience, you can develop miniature subassemblies that may be used many times.

By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250
Luther, MI 49656

Have you considered building your own ICs? The idea is not as ridiculous as it may seem! We must accept the fact that none of us are equipped to construct classic monolithic ICs, wherein the circuit elements are developed on a common piece of silicon (substrate). But, it is not mandatory that circuits to be integrated are formed in that manner. With a reasonable amount of imagination and time, it is possible to place your favorite small circuit on a tiny blank DIP header. For lack of a better acronym, let's call these assemblies MCMs (for "mini circuit modules").

You may wonder what the purpose of such an exercise might be. First, we are forced to develop a compact circuit layout, owing to the restricted number of IC-header pins available, plus the small rectangular area of the header. I find that the circuits I have placed on IC headers would typically occupy three times the space on an ordinary PC board. In other words, when there is room to spare, I seem to use it! Miniaturization is beneficial when we wish to build compact gear for portable use, especially for QRP applications.

Another advantage realized from MCMs is that they can be used many times in numerous projects. The same circuits, if built on PC boards, would require complete stripping of the components in order to transplant them on a new PC board. The MCMs can simply be removed from IC sockets and plugged into a socket on some other PC board. This technique should appeal especially to the experimenter or the frugal amateur.

Some Common Circuits as MCMs

Fig 1 shows a compound, direct-coupled audio amplifier that has been built on a 16-pin DIP header.[1] This amplifier has the ability of providing 40 dB of gain, depending on the electrical characteristics of the transistors used. Such an amplifier is suitable for driving a pair of headphones, serving as a mic amplifier or for use ahead of an audio power IC, such as an LM386. Fig 1B shows how the parts are assembled on the header. The heavy outline around the circuit of Fig 1A indicates which components are on the header. C3, for example, is external to the MCM.

Doubly Balanced Mixer MCM

Diode-ring DBMs are available as commercial units in DIP IC packages. Mini-Circuits has some nice units that come in sealed metal packages for direct insertion into IC sockets. These modules are expensive when purchased in single-lot quantities. If one buys 10 or more units, the price becomes more equitable, but few of us want a drawer filled with DBMs that may never be used! So, the MCM approach becomes worth considering for most of our amateur needs.

Fig 2A shows the circuit of a DBM. The diodes should be matched as closely as possible to ensure proper circuit balance. Diode matching may be done by means of a VOM. Sort through your 1N914 or similar small-signal silicon switching diodes and select four that have the same forward-resistance reading (typically between 7 and 12 ohms). Hot-carrier diodes are even better for use in a DBM, and most of them from a given brand and type number are fairly well matched.

Z2 of Fig 2A may be used as a mixer, balanced modulator or product detector. No internal changes are needed, but the exterior circuitry will differ somewhat, depending upon the application. T1 and T2 are miniature broadband transformers. I used two small ferrite balun cores for T1 and T2, but tiny 850 μ_i toroid cores allow construction of a more compact MCM.

It is essential to connect the T1 and T2 windings as shown. The black dots indicate the polarity of the windings. Local-oscillator injection for this type of mixer is approximately +7 dBm for best IMD performance. Conversion gain (actually a loss) is on the order of −8 dB for a DBM. At frequencies greater than 40 meters, if the DBM is used as a receiver mixer or direct-conversion (D-C) receiver product detector, it is wise to use an RF amplifier between the antenna and the DBM. If not, the receiver noise figure will be too high for weak-signal reception. In fact, an RF amplifier would be an asset even at 7 MHz.

An ideal DBM would be enclosed in a metal case to minimize stray signal pickup. However, there should be no problems with unwanted pickup of RF energy when using the MCM of Fig 2, provided ordinary PC-board layout is employed. In other words, don't place the DBM close to an unshielded oscillator or antenna lead.

Crystal-Oscillator MCM

A simple crystal oscillator is presented in Fig 3A. You may prefer to exclude the crystal, Y1, from the MCM. This will make the module more universal in application. I included the crystal for the purpose of demonstrating the practicality of having Y1 mounted on the IC header. An HC-18/U

---

[1] IC headers (sometimes called DIP adapter plugs) are available from many surplus electronics parts dealers, including Mouser Electronics, 11433 Woodside Ave, Santee, CA 92071, and ALL Electronics Corp, 905 S Vermont Ave, Box 20406, Los Angeles, CA 90006.

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.



EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000, M = 1 000 000.

Fig 1—Schematic diagram of a two-stage audio amplifier that can provide up to 40 dB of gain. The drawing at B shows the component layout for the audio MCM.



Fig 2—Circuit for a doubly balanced mixer, balanced modulator or product detector. Matched diodes are necessary for best DBM balance. Hot-carrier diodes are recommended for this circuit, but matched 1N914s are suitable. T1 and T2 in my MCM consist of four trifilar turns of no. 30 enameled wire through an Amidon balun core no. BN-43-2402. An FT-23-43 ferrite toroid core may be substituted (smaller) by winding 7 trifilar turns of no. 30 enameled wire on each core.

crystal holder is necessary (small) in order to find room for it on the header. If the crystal will be used outboard from the MCM, you may connect it to pins 1 and 16 (Fig 3B).

The oscillator of Fig 3A is easy to work with. External capacitor C2 is used to control the feedback. It functions in connection with the transistor internal capacitance (C_j) to form a feedback network. C2 should have a capacitive reactance of roughly 200 ohms for most small-signal transistors. This equates to 100 pF for operation at 8 MHz. If you wish to convert this circuit to a VXO, you need only to separate pins 1 and 2 (remove jumper) of the header and place a small inductance (25 µH for 8 MHz) in series with a 75- or 100-pF variable capacitor from pin 1 to ground. Connect the capacitor rotor to ground. This arrangement will provide approximately 6-10 kHz of frequency change.

C3 and L1 are outboard from the MCM. This tuned circuit is resonant at the crystal frequency. L2 is a small link for coupling the circuit to low-impedance loads. For most applications, C3 may be a small trimmer.

Oscillator Buffer/Amplifier MCM

It is seldom necessary to use buffering after a crystal oscillator, since changes in load (reactance changes) seldom cause oscillator pulling. VXOs, on the other hand, may be prone to pulling effects from load changes, and a buffer is useful in that case. VFOs are affected significantly by load changes. Therefore, it is wise to include a buffer or buffer/amplifier after a VFO.

Output coupling from the oscillator should be as light as possible to minimize pulling. Light coupling (C4 of Fig 5A) causes reduced power output from the VFO. As a result of this condition, it is advisable to amplify the VFO output energy to compensate for the power loss. Fig 4A shows a suitable buffer/amplifier circuit that will fit on a 16-pin IC header. Q1 is purely a buffer, and has a gain of 0.9


Z3
2N2222A
Q1
8 MHz
Y1
R1 10 k
R2 27 k
R3 470
B
C
E
CJ
RFC 1 60 μH
C1 0.1
C2 0.1
0,12
9
8 MHz
TUNE
C3 100
L1
L2
SIG OUT
1,2
11
14
3,7,8
R4 22
+12 V
100 pF
C2
XC = 200 Ω
B
E
C
Q1 BOTTOM VIEW
BOTTOM VIEW
Z3
Y1
R1
R2
Q1
R3
RFC 1
C1
1
2
3
4
5
6
7
8
16
15
14
13
12
11
10
9
TOP VIEW
(B)

EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000, M = 1000 000.

Fig 3—Example (A) of a crystal oscillator that can be built on an IC header. The heavy black line indicates the MCM boundary. All other parts are external to the MCM. L1 is a 5.5-μH inductor (33 turns of no. 28 enameled wire on an Amidon T50-2 core). L2 consists of 6 turns of no. 28 wire. The MCM layout is given at B.


+12 V
100
0.1
14
Z4
+12 V
27
0.1
7
TO VFO OUTPUT (C4 OF FIG 5)
16
SF MPF102
Q1
D
G
S
R1 100 k
RFC 1 50 μH
R3 15 k
AMP
C3
0.1
C1
100
B
C
E
Q2 2N2222A
R2 5.6 k
R4 270
C2 0.1
2,15
1,4,5
RFC 2
100
0.1
FL1
fco = 8 MHz
R5 3.3 k
RF OUT (50 Ω)
8
L1
C5
C6
B
Q2
E
C
BOTTOM VIEW
G
S
D
Q1
Z4
R1
G
S
Q1
D
R3
R2
R4
C2
C1
E
B
Q2
C
RFC 1
C3
1
2
3
4
5
6
7
8
16
15
14
13
12
11
10
9
TOP VIEW

EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000, M = 1000 000.

Fig 4—Circuit for a VFO buffer/amplifier. FL1 is a low-pass filter with a cutoff frequency of 8 MHz. C5 is 150 pF, C6 is 330 pF, and L1 is a 2.8-μH inductor. See text for data on RFC2.

typically. This is par for a source follower. It helps to isolate the VFO from Q2 and the circuits that follow Q2. Amplifier Q2 builds up the VFO energy to a level that is suitable for most circuits with which a VFO is used.

External to Z4 of Fig 4A is a pi network that serves as a matching circuit between the collector of Q2 and a 50-ohm load. This network also serves as a harmonic filter. R5 may be added to increase the loaded bandwidth of the pi network. This may be helpful when the VFO covers a fairly wide frequency range.

RFC2 of Fig 4A is chosen to yield a broad frequency-response peak at the VFO operating frequency. You may assume approximately 10 pF of stray parallel circuit capacitance for RFC2. Thus, for 40-meter operation we will require a 50-μH inductor for RFC2. Should Q2 become unstable, place a 1-kilohm resistor in parallel with RFC1. The addition of R5 will also aid stability in stubborn cases.

Colpitts VFO MCM

The VFO of Fig 5A uses electronic tuning. VVC (voltage variable capacitor) diodes are specified for D1 and D2. This eliminates the need to locate expensive and scarce miniature variable capacitors for tuning VFOs. It is proper to state that long-term VFO drift may be increased through the use of tuning diodes, as opposed to air variable capacitors. This is because two additional semiconductor junctions have been introduced to the oscillator circuit: Junction capacitance changes with temperature. Normally, the small degradation in frequency stability is acceptable for amateur work. Tuning is done by means of a panel-mounted potentiometer (R3). Smooth tuning will result if a 10-turn Helipot® and dial are used, or if a standard potentiometer is used with a vernier drive. The values for R2 and R4 are chosen for the frequency coverage desired, and this will depend upon the type of VVC diodes used for D1 and D2: VVC diodes come in many capacitance ranges. I have suggested for this circuit a pair of diodes that will provide a fairly linear capacitance swing of 10 to 30 pF.

Outboard components C5, C6 and L1 are chosen for the VFO operating frequency. NP0 capacitors are recommended for best overall frequency stability. C1, C2 and C3, internal to the MCM, are also NP0 ceramic capacitors: the smaller 50-V types are preferred in the interest of fitting them on the IC header.

Q1 of Fig 5A may be any high-transconductance JFET, such as a 2N4416. A dual-gate MOSFET may be substituted by tying gates 1 and 2 together and treating the device like a JFET.

Place a shield compartment around the VFO MCM site on the main PC board of a receiver or transmitter. This will help prevent stray RF energy from entering the VFO circuit and causing frequency instability. The small shield compartment may be fashioned from PC-board sections or from flashing copper.



EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000 M = 1000 000.

Fig 5—Schematic diagram of a Colpitts VFO for use as an MCM. D1 and D2 are tuning diodes (Motorola MV209 or equivalent). L1 has 26 turns of no. 24 enam wire on an Amidon T50-6 (yellow) toroid core. No. 6 core material offers the best stability. R2 and R4 are chosen for the tuning range desired. R3 is a linear-taper carbon composition control (Allen-Bradley high-reliability type recommended). C6, for best stability, should be an NP0 ceramic trimmer.

MCM Practical Considerations

Miniature equipment is not easy to build, and MCMs certainly fit this description. You will need patience during the assembly procedure, but your skill and speed of construction will increase with practice.

Plug the IC header into an IC socket *before* commencing the MCM assembly. This will prevent the pins of the header from becoming bent or broken. I use an IC socket that has its pins mashed flat against the bottom of the socket. This allows the socket to lie flat on the bench during assembly. A "third hand" type of soldering fixture is useful for keeping the header and IC socket in a fixed position while you work on it. A small bench or drill-press vise may be used as a holding fixture if you don't have a third-hand device.

A magnifying glass is almost mandatory when building MCMs. It will allow you to check frequently for unwanted solder bridges, poor joints and shorting leads on the header. To this end, a pencil soldering iron with a fine tip and low wattage rating (25-30 W) will help to minimize melting the IC-header plastic and the formation of unwanted solder bridges between the header terminals.

The first step in construction is to place all of the jumper wires on the header (as indicated by the pictorial drawings). Try to use light-gauge wire, preferably with insulation. The small wire from multiconductor telephone cable is excellent for this purpose. Bare wire may be used, provided there are no crossover jumpers on the header.

The general assembly procedure calls for installing the components of the MCM in layers. Some stacking will be necessary, depending upon the complexity of the circuit. After the jumper wires are in place, mount the resistors. If you can find some 1/8-W resistors, use them. This will minimize crowding on the header. I used ¼-W resistors for the examples shown photographically in this article, as I have no 1/8-W units in stock.

Next in the assembly comes the capacitors, followed by the transistors and, finally, the largest components. I add the RF chokes, toroidal coils and crystals last.

You may protect the tested, completed MCMs by developing a mold and encapsulating the components and header top side in casting resin. This will eliminate the possibility of replacing defective components later on, but it will keep dirt and moisture from entering the circuits. I use quick-setting epoxy cement for this purpose when I want to seal and anchor the components on some of my IC headers.

It is to your advantage to look for miniature components in the surplus catalogs and at flea markets. Large, old-style parts do not lend themselves well to MCM construction. Fortunately, the present electronics technology provides a substantial fallout of surplus mini components, and these are ideal for building MCMs.

A Marriage of MCMs

Four of the MCMs in this article may be used in concert to provide a simple D-C receiver. Fig 6 contains a block diagram of such an arrangement. The example suggests a circuit for 40-meter use. In this case, Z2 serves as a doubly balanced product detector. The output is at audio frequency



7.0 – 7.2 MHz
C1 140
T1
ANT (50 Ω)
PROD DET
Z2
SEE FIG 2
16
1
10
8
9
1 µF 16 V
2.2 k
0.1
AUDIO AMP
Z1
SEE FIG 1
15
9
1
4
10
3
10 µF 16 V
100
+12 V
INSERT AUDIO FILTER HERE (IF USED)
AF GAIN
R1 10 k
LM386 OR SIMILAR
U1
8-Ω SPEAKER OR PHONES
+12 V
FL1
+7 dBm
L1
330
150
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000, M = 1000 000.
VBFO
7.0 – 7.2 MHz
C5 56 NPO
C6 30
14,16
15
10
11
13
SEE FIG 5
Z5
9
1
2
8
0.1
100 k
100
0.1
R3
5.6 k
100 k MAIN TUNING
+9 V REG
VFO BUFFER/AMP
Z4
SEE FIG 4
16
8
4
5
14
1
2
15
7
RFC 2 50 µH
0.1
27
100
0.1
100
0.1
+12 V

Fig 6—Suggested hookup for using four of the MCMs in this article in a 40-meter D-C receiver. See text for detailed information.

rather than at an IF, as would be the situation if Z2 were used as a mixer. Z1 operates as an audio preamplifier to drive an LM386 audio chip (or equivalent IC). Headphones may be connected to the output of Z1, but only strong signals will produce ample volume without U1 being added. D-C receivers require 80-100 dB of audio gain to permit weak-signal copy.

Z5 of Fig 6 is the VFO MCM, but when used in a D-C receiver it operates as a VBFO (variable beat frequency oscillator). C5 and C6 are used to set the operating range of the oscillator. R3 is the main tuning control for the receiver.

Z4 of Fig 6 amplifies the VBFO energy to an acceptable level for injection at pin 9 of Z2. FL1 provides an impedance match and offers some filtering of the Z4 output energy. A 10-20 dB RF preamplifier would be a welcome addition between the antenna and the input of Z2. This would greatly improve the receiver noise figure, and it should enhance weak-signal reception. A preamp may be built on an IC header to conform to the general format of the receiver.

CW reception will be greatly improved (better selectivity and reduced wide-band noise) by the addition of an LC passive or RC active audio filter at the point marked with an X at pin 9 of Z1. Suitable circuits may be found in the *ARRL Handbook for the Radio Amateur* and *Solid State Design* by the ARRL. Reception of SSB signals will be satisfactory without a filter, but the addition of a low-pass audio filter at X will improve the receiver selectivity for SSB reception.

An extremely compact receiver can be built by using the arrangement shown in Fig 6. With a few more MCMs of your design, it would be a simple matter to develop a small superhet receiver. You will need to build an IF-amplifier MCM and another one for the BFO.

Summary Comments

The intent of this article is to inspire you to try this method of miniaturization. I am told frequently that ham radio is supposed to be fun. Designing and building MCMs has been fun for me, and they offer some practical advantages over conventional PC-board construction. You should be able to develop a bank of MCMs for various applications. This can hasten assembly time for many experimental circuits. MCMs are, of course, excellent units for use in a permanent circuit as well. Who knows, you may be the first ham in your area to create that elusive wrist radio of comic-book fame!

From April 1985 QST, p 42:

A Converter for the 24-MHz WARC Band



Here's your chance to listen to a new band and enjoy an interesting construction project.

By Doug DeMaw,* W1FB

Perhaps you've wondered what is happening on the 24-MHz band but you can't listen to the frequency because your rig doesn't include WARC-band coverage. This converter is easy to assemble and get operating, and it's inexpensive.

Few RF circuits are laid out casually. Knowing how to approach the general design and assembly will be helpful in the years ahead when you build other RF projects.

General Design Objectives

First, ask "What do I want this converter to do?" Obviously, it needs to cover the band of interest — a foregone conclusion. But what of the other, sometimes subtle, considerations? Let's draft the criteria. The converter should:

1) exhibit an overall gain of unity, or slightly better. It should not create signal loss.

2) provide sufficient front-end selectivity to reject unwanted out-of-band signals.

3) be free of spurious responses and parasitic oscillations.

4) have a low noise figure (NF), permitting weak-signal reception.

5) have a dynamic range (ability to cope with strong in-band and out-of-band signals) that is reasonable to ideal.

At this point, you may be asking, "What does all of this really mean?" Well, let's examine the list, item by item.

It is possible to design a converter that exhibits a signal *loss*. This can degrade the signal-to-noise ratio (S/N) of the overall receiving system. A poor S/N ratio places the weak signals in the internal noise of the receiving system. This is similar, in effect, to having a normal signal become buried in atmospheric or man-made noise (QRN). Therefore, the converter must have ample gain and a low-enough NF to override the inherent noise of the receiver with which it is used. This does not mean that the converter must have an RF amplifier for all the amateur bands, but for 20 meters and higher it is wise to include one. Many converters for 40, 80 and 160 meters need only a mixer at the input stage, since atmospheric and man-made noise on those bands is usually greater than is the receiver noise.

Selectivity means that a tuned circuit or circuits with good Q (quality factor) should be used between the antenna and the first converter stage. This helps to discriminate against strong out-of-band signals. Some poor designs contain no tuned circuit ahead of the mixer, and that's an invitation to trouble!

To minimize spurious responses, you should ensure that no stage in a converter, other than the local oscillator (LO), is oscillating. The culprit in some home-constructed converters and receivers is the RF amplifier. Sometimes there is no outward indication of self-oscillation, and yet the unstable stage is generating a signal of its own. These random oscillations appear in the receiver output as unsteady or rough-sounding carriers, or "birdies." Under certain conditions, we may even find a mixer that is self-oscillating. Similarly, an oscillator may generate output on more than the desired frequency — especially if too much feedback is used. Other spurious responses can result from excessive harmonic output from the converter LO.

The transistor selected must be capable of providing an acceptable noise figure for our chosen operating frequency. This can be determined by looking at the manufacturer's data sheets for small-signal transistors that are earmarked for RF amplifier service. Let's be thankful that the NF requirements for 160 through 10 meters are not as stringent as they are at VHF and UHF! You can manage quite nicely with a maximum NF of, say, 5 dB in the HF spectrum. There are many transistors that meet this criterion. The f_T (upper-frequency limit versus gain) of a transistor must be correct, also. If not, the stage will not provide ample gain. I like to use a device that has an f_T of at least 10 times the operating frequency. For example, if I wanted to build a converter for 14 MHz, the RF amplifier transistor f_T would be 140 MHz or greater. Also, the noise figure is determined by the input-matching circuit and the specific biasing of the amplifier. So, you must take many things into account when designing an RF amplifier.

The dynamic range figure indicates the ability of the RF amplifier and mixer to handle large signals without generating IMD (intermodulation distortion), or going into gain compression (lowered gain). The system immunity to this is determined by the type of device used in the RF amplifier and mixer stages. Operating conditions based on dc voltages also play an important role in dynamic range. The approach you must take is anything but casual in this general area. There is a wealth of information on all five items on the list in the League's book, *Solid State Design for the Radio Amateur.*

What about Mixers?

There are so many pros and cons about mixer choice and operation that you could soon be wading in a sea of confusion if we discussed this subject in depth. The bottom line is to use a *strong* mixer; one that won't collapse when strong signals enter it. Diode-ring mixers (four diodes in a quad arrangement) are among the better choices, but they require more LO output power than is needed for a transistor or an IC mixer. Also, diodes operate as passive devices (no operating voltage is required), which results in a signal loss in the mixer. This is known as *conversion loss.* With a diode-ring mixer, the loss can be as great as 8 dB. The RF amplifier ahead of this mixer needs to have a gain of at least 10 dB to ensure a low noise figure. ICs such as the MC1596G and CA3028A offer good performance as

---

*ARRL Contributing Editor, P.O. Box 250, Luther, MI 49656


T2
100K
T1
L1
CIRCUIT BOARD SPECIALISTS
P.O. BOX 969
WARC-CONVERTER

Fig. 1 — The assembled converter. Shielded Amidon Associates L43 and L57 transformer assemblies are used for the tuned circuits.

mixers. They do not require high LO power.

Another mixer requirement is that ample LO injection power or voltage be applied. Too little LO power to a mixer results in reduced gain and degraded dynamic range.

All of you won't grasp these fundamentals instantly. But you should have knowledge of the pertinent terms and a rough notion of what the terms relate to. I suggest further study in the various ARRL textbooks.

A Practical Converter You Can Build

Fig. 1 shows an assembled version of the circuit in Fig. 2. As shown, it is set up for operation in the 24-MHz band. PC boards and complete parts kits for this converter are available.[1]

In an effort to trade high performance for simplicity, I have chosen a design that uses only three transistors. Q1 is a grounded-gate (common gate) JFET RF amplifier. If the gate lead is kept very short when grounding it, the stage should be unconditionally stable. A good RF amplifier should not oscillate when the load is disconnected from J1. The stage gain is on the order of 10-12 dB. The same transistor, if used in a grounded-source hookup (input signal to the gate), can yield up to 20 dB of gain, but will be more difficult to tame.

A 40-meter trap (L1 and C1) help prevent 40-meter signals from riding through the converter: The 40-meter band is used as the tunable IF for this converter. T1 offers reasonable front-end selectivity. The source of Q1 is tapped near the ground end of the main transformer winding to provide an approximate 1:1 match between the 50-ohm antenna and 200-Ω source impedance of Q1. The source impedance of Q1 is determined by

$$Z = \frac{10^6}{g_m} \qquad \text{(Eq. 1)}$$

---

[1]Notes appear at end of article.


TRAP
7050 kHz
ANT.
(50 Ω)
J1
L1
5 μH
C1
100
24.940 MHz
C2
33
T1
0.01
100
RF
AMP
MPF102
Q1
S
D
G
24.940 MHz
15
C3
33
100
100k
L2
MIXER
Q2
3N211/40673
G2
G1
D
S
C4
68
5.6 k
7050 kHz
T2
J2
TO RCVR
(50 Ω)
10 k
100
0.01
C5
18
0.1
100
+12 V
0.01
0.01
100
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS; k = 1000
* - SEE TEXT
OSC.
15 k
Q3
2N2222
C
B
E
* C8
60
FREQ. ADJ.
Y1
17.890 MHz
5.6 k
1k
C7
100
C6
68
17.890 MHz
L3
100
0.01
+12 V
Q2
BOTTOM VIEW
G2
D
G1
S
Q1
G S D
Q3
C B E
BOTTOM VIEW
1 2 3 4 5 6
DOT
L1, L2, L3
T1 AND T2

Fig. 2 — Schematic diagram of the 24-MHz receiving converter. Fixed-value capacitors are disc-ceramic, unless otherwise noted. Resistors are ¼- or ½-W carbon-composition.

C1-C7, incl. — Silver-mica, polystyrene or NP0 ceramic capacitors.
C8 — Optional 60-pF trimmer (see text).
J1, J2 — Phono jack, single-hole mount.
L1 — 5-μH (nom.) coil. Use 26 turns of no. 30 enam. wire on an Amidon Assoc. L43-6 transformer bobbin.
L2 — 0.75 μH (nom.) coil. Use 10 turns of no. 26 enam. wire on an L43-6 transformer bobbin.
L3 — 1.1 μH (nom.) coil. Use 12 turns of no. 26 enam. wire on an L43-6 transformer bobbin.
Q1 — Motorola MPF102 JFET or equiv. VHF type.
Q2 — RCA 40673 dual-gate MOSFET or TI 3N211.
Q3 — 2N2222 or 2N2222A NPN transistor or equiv.
T1 — 0.75-μH (nom.) secondary winding. Use nine turns of no. 26 enam. wire on an Amidon Assoc. L57-6 transformer bobbin. Tap at two turns above the ground end. Primary is a one-turn winding over the secondary.
T2 — 5-μH (nom.) primary. Use 22 turns of no. 26 enam. wire on an Amidon Assoc. L57-6 transformer bobbin. Secondary has three turns of no. 26 enam. wire. See inset drawing for pin locations for L1, L2, L3, T1 and T2.
Y1 — Fundamental crystal in HC-6/U holder, 20-pF load capacitance. International Crystal Mfg. Co. type GP or equiv.
Amidon Associates, 12033 Otsego St., North Hollywood, CA 91607, tel. 213-760-4429.
International Crystal Mfg. Co., Inc., 10 North Lee, Oklahoma City, OK 73102, tel. 405-236-3741.

where g_m is the transconductance in siemens (formerly called mhos) of the transistor used.

Our mixer is a dual-gate MOSFET. This transistor is simple to use and offers average performance as a mixer in terms of dynamic range. A tuned transformer, T2, is used in the mixer output to provide an impedance match between the drain of Q2 and the 50-ohm receiver input. The 5.6-kΩ load resistor across T2 sets the impedance value of the drain circuit, and provides a relatively broad response across 100 kHz of the 40-meter IF. The resistor lowers the tuned-circuit Q.

Q3, a bipolar transistor, is the oscillator. Y1 is a fundamental crystal. The load capacitance for the crystal is approximately 20 pF. C8 is an optional trimmer capacitor that you may add to shift the crystal frequency in order to make the receiver dial match the received frequency. If the crystal is slightly off frequency, C8 may be needed. If the parallel arrangement for C8 is not satisfactory, move C8 so it is between the lower end of Y1 and ground, in series with Y1. The parallel arrangement will lower the Y1 frequency, while the series hookup will raise the Y1 frequency.

The RF injection voltage on the mixer (gate 2) should not exceed 6-V P-P (2.12-V RMS). A scope or an RF probe and voltmeter can be used to check the Q2 injection voltage. If it is too low, increase the value of C7. Similarly, decrease the value of C7 if the injection voltage it too high. A value of 4- to 6-V P-P is best for a dual-gate MOSFET mixer. Injection voltages greater than 6 can destroy the mixer transistor.

Construction Notes

A parts-placement layout, seen from the component side of the board, is given in Fig. 3. A scale etching template is shown in Fig. 4.

If you decide to make your own circuit board, try to follow closely the pattern provided in this article. Double-sided board material is recommended for the circuit, but you may use single-sided material. Make certain that all solder joints are good ones. Component leads should be kept as short as possible.



Fig. 3 — Parts-placement guide for the converter, as seen from the component side of the board. The shaded area represents an X-ray view of the copper pattern.

Tune-up and Operation

The converter is capable of approximately 20 dB of gain when each tuned circuit is peaked for a single frequency on 40 meters. However, it is better to stagger-tune T1, L2 and T2 for 7.010, 7.050 and 7.075 MHz, respectively. Peak each circuit at the specified frequency. This will lower the effective converter gain somewhat while providing a more level gain response across the 100-kHz tuning range.[2] L3 is tuned for maximum output at 17.890 MHz. To ensure rapid starting of Q3, it may be necessary to tune L3 slightly off resonance to the high side of 17.890 MHz.

The 24-MHz amateur band extends from 24.890 to 24.990 MHz. Therefore, you will be listening to 24.890 MHz when your receiver is tuned to 7.0 MHz, and 24.990 MHz will be at 7.1 MHz on your receiver dial.

It is a good idea to enclose any converter in a shielded box. This prevents stray pickup of unwanted signals by the circuit board and various components. This is especially important in order to keep 40-meter signals out of the main station receiver during 24-MHz reception. Also, try to find a 40-meter signal that is leaking through the converter somewhere near 7050 kHz. Then adjust the trap, L1/C1, for minimum strength of the unwanted 40-meter signal.

Good luck, and see you sometime soon on 24.890 MHz!

Notes

[1] Circuit Board Specialists, P.O. Box 969, Pueblo, CO 81002, tel. 303-542-5083.

[2] Excessive converter gain can degrade the dynamic range of the receiver used as the tunable IF.

For updated supplier addresses, see ARRL Parts Supplier List in Chapter 2.



Fig. 4 — Circuit-board etching pattern for the 24-MHz converter. The pattern is shown full-size from the foil side of the board. Black areas represent unetched copper foil. Double-sided PC board is recommended (see text).

From February 1989 QST, p 43:

ANOTHER ONE-MOSFET CONVERTER

Almost fifteen years ago, *QST* published a 10- and 15-meter converter that used a 40673 dual-gate MOSFET as mixer *and* crystal oscillator—a *converter* stage (see Fig 6).[7] Despite the article's report that the circuit oscillated reliably with ten different crystals, I recall having heard that some builders had trouble getting the circuit to work.

A variation on the single-MOSFET converter appears in the December 1987 issue of the Japanese magazine *CQ Ham Radio*. The Japanese configuration differs from McCoy's *QST* circuit in that a parallel tuned circuit (resonant at the crystal frequency) between the MOSFET drain and the output tuned circuit (resonant at the IF) is used to keep the drain impedance high at the crystal frequency. With sufficient separation between the crystal and intermediate frequencies, this drain *trap* should not unduly attenuate the converter's IF output. Fig 7 shows the circuit, along with component values for the working model I built in the ARRL Lab.

The values shown in Fig 7 have not been optimized; the tuned-circuit reactance values, in particular, were pulled out of thin air with the intent of constructing a working model quickly. The first crystal I found in my "junk box" was a 4-MHz microprocessor-clock unit; I chose the converter input and output frequencies (14 and 10 MHz, respectively) because they "work" with a 4-MHz LO.

Yes, it works. Dynamic range? I have no idea. Sensitivity? You've got me, although disconnecting my indoor antenna from the converter made most of the received background (not line) noise disappear (the "low tech" sensitivity test!). Image rejection? Not so hot; but this simple prototype has only one tuned circuit between the antenna and gate 1 of the MOSFET, after all.

How does the *CQ Ham Radio* circuit compare with McCoy's? Well, my Fig 7 prototype doesn't oscillate if the 4-MHz drain trap (L1 and the 82-pF capacitor) is shorted; shorting the drain trap of the *CQ Ham Radio* circuit approximates McCoy's hookup. (I suspect that the impedance of T2's resonant secondary is too low at 4 MHz to allow Q1 to "take off" without the drain trap. At some combinations of intermediate and LO frequencies, this may not be a problem. Crystal characteristics undoubtedly play a part.) The McCoy circuit uses positive bias on gate 2 of the MOSFET, and keeps gate 1 and the source at the same dc potential. The Japanese circuit returns both gates to ground; in conjunction with the voltage drop across the 270-Ω source resistor, this biases both gates negatively relative to the source. Even with positive bias applied to gate 2 of the MOSFET, however, my prototype does not oscillate with its drain trap shorted. Message: The drain trap is important! (*CQ Ham Radio* carried one version of this converter in which the gate-2-to-ground resistor was 10 kΩ instead of 100 kΩ; in that circuit, Y1 was a 41-MHz crystal, and a 5-pF feedback capacitor was connected from gate 2 of Q1 to ground.)


CONVERTER
17.5 OR 24.5 MHz
0.01
Q1
40673
G2
D
10
3.5 MHz
RF INPUT
(21 OR 28 MHz)
G1
S
100 k
150 k
180
IF
OUTPUT
(3.5 MHz)
0.01
560
0.001
100
+12 V
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF), OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000

Fig 6—This one-transistor converter stage (RF amplifier not shown) appeared in March 1974 *QST*. Q1 acts as a Pierce oscillator and mixer. The 10-Ω drain resistor may have been included to suppress VHF parasitic oscillations in Q1.


CONVERTER
Y1 4 MHz
4 MHz
L1
Q1 40673
G2
D
14 MHz
T1
G1
S
82
10 MHz
T2
J1
RF
IN
33
100 k
270
0.01
43
J2
IF
OUT
0.1
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000
+12 V

Fig 7—A one-MOSFET converter based on a *CQ Ham Radio* design. The principal difference between this circuit and that shown in Fig 6 is the drain trap (L1 and the 82-pF capacitor). Solenoidal slug-tuned inductors and transformers were used only because they were hardy; their toroidal equivalents should work as well or better. See text.

J1, J2—coaxial RF connectors.

L1—14.8- to 31-μH slug-tuned coil (Miller 4407) set to approximately 19.3 μH. Reactance: approximately 485 Ω at 4 MHz.

T1—2.7- to 4.2-μH slug-tuned coil (Miller 4307) set to approximately 3.9 μH; primary: three turns of no. 26 enameled wire over cold end of secondary. Reactance of secondary: approximately 344 Ω at 14 MHz.

T2—4.7- to 6.8-μH slug-tuned coil (Miller 4407) set to approximately 5.9 μH; secondary: four turns of enameled wire over cold end of primary. Reactance of secondary: approximately 370 Ω at 10 MHz.

It pays to make L1, or its resonating capacitor, variable. In my prototype, the crystal oscillated on several frequencies at once and generated broadband hash unless the drain trap was tuned just so. But it *was* possible to find an L1 setting at which Q1 oscillated cleanly. In my opinion, this merely means more fun for the experimenter! (I also point out that we're perhaps being a bit unkind to the MOSFET in this circuit: Amplitude limiting—essential in any oscillator that does not destroy its active device[s]—obviously occurs *somewhere* in the circuit, but not by design! [Unlike the cathode-grid diode in a vacuum-tube oscillator, a MOSFET's gate-source insulator can't conduct without instantly destroying the device. Perhaps drain saturation is the amplitude limiter in this case.] McCoy reported that the highest RF voltage measured on gate 1 in his circuit was 4—well within the ratings of the 40673. I did not measure the gate 1 voltage in the *CQ Ham Radio* circuit.)

Might this single-MOSFET converter work with overtone crystals? I dunno; *you* experiment, and tell us about it! How about configuring Q1 as an LC, instead of a crystal, oscillator? Great idea! Let me know your results.

The circuit does what I wanted: It works—it "makes noise"—and it's interesting to fiddle with. Maybe you can find a good use for it. You might even have some fun along the way!

—David Newkirk, AK7M, ARRL Staff

---

[2] L. McCoy, "Improving Your Receiver Performance on 15 and 10 Meters," *QST*, Mar 1974, pp 26-27.

From May 1989 QST, p 25:

A Four-Stage 75-Meter SSB Superhet

Getting "the most for the least" is a typical ham radio objective for those who build circuits. This simple SSB superhet receiver is the product of such an effort.



By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250
Luther, MI 49656

"Must everything you design be for CW operation?" I have been asked this question many times. Perhaps my preference for CW work influenced my thinking when I sat down to design a new piece of gear. The circuit in this article is my "apology" for overlooking the voice operators who like to build homemade receivers. I want to stress that this four-stage receiver does not belong in the high-performance class. However, it is sensitive and stable, and it provides good audio quality.

Design Rationale

One objective when starting this project was to learn how few components could be used to develop a receiver with acceptable performance. A great deal of cutting and pruning took place over a one-month period of breadboard-circuit testing. I wanted to have *some* rejection of the unwanted sideband, but I also wanted to minimize the cost of a crystal filter. A low overall noise figure was also a criterion.

Another goal was to have a surplus of audio gain for even the weakest of SSB signals. Finally, the power consumption for the receiver should be modest enough to permit battery operation during emergency or field use. All of these objectives have been met.

Circuit Highlights

The tuning range of the circuit in Fig 1 is from 3.7 to 4.0 MHz. The FL1 and oscillator constants can be changed to provide coverage of the 80-meter CW band, should you prefer that to the SSB segment of the band. Filter information is presented in *The ARRL Electronics Data Book*.[1] A slight increase in inductance is needed for L5 in order to cover 3.5 to 3.7 MHz.

Although Q1 could be made to work as both a mixer and oscillator, I chose to isolate the oscillator from the mixer. Harmonic currents also inject the mixer when both circuits share a common transistor substrate. This causes all manner of spurious responses, and oscillator pulling may also be a problem. The injection waveform from the gate of Q3 is very clean.

FL1 is a band-pass filter with circuit values taken from the W7ZOI tables in the *Data Book*. Although the values specified in Fig 1 are for 3.8 to 4.0 MHz, the attenuation at 3.7 MHz is minor with the filter peaked at 3.85 MHz. There is some insertion loss through FL1 (about 2 dB). An earlier version of this receiver had a single, high-Q tuned circuit at the mixer input. Receiver sensitivity was better with that arrangement, but it was a nuisance to retune the input circuit when changing frequency. With the single tuned circuit a 0.35-μV signal was 3 dB above the noise floor of the receiver. A 3-dB rise occurs at 0.55 μV with FL1 in place. I should mention also that the single tuned circuit allowed signals from the image side of the mixer (20 meters) to pass through the receiver. The band-pass filter corrected the fault.

Should you want to cover both the 75- and 20-meter bands you can build a 20-meter version of FL1 and band switch the two filters. As with the 75-meter-only version, an IF of 9.0 MHz (Y1) is required. With this arrangement the 20-meter band will tune backwards from the 75-meter band, but upper- and lower-sideband reception will occur, as required, without changing the BFO frequency (Y2). This two-band scheme with a 5-MHz VFO is an old one!

In effect, the circuit in Fig 1 is a fixed-tuned direct-conversion receiver (Q2 and U1) with a tunable converter (Q1 and Q3) ahead of it. There are no IF amplifiers, and hence no AGC. Gain from an IF amplifier is not needed to ensure good performance. The overall receiver gain is approximately 75 dB. This is more than adequate for headphone reception.

Q2 serves as a crystal-controlled BFO and product detector. C14 is chosen to provide a BFO frequency that is roughly 1.3 kHz higher than the IF-filter crystal, Y1. (C12 and C13 lower the marked frequency of Y2.) A 50-pF trimmer can be used at W1/C14. You may want to eliminate C14 and order Y2 for a frequency that is 1.5 kHz higher than that of Y1. I found that I could shift a surplus 9.500-MHz HC-6/U crystal to 9.50013 MHz with C14 in place of W1, as shown. Changing C12 and C13 to 47 pF may help raise the Y2 frequency. I find that plated crystals in HC-6/U holders shift upward better than the small units in HC-18 holders. Crystals in FT-243 holders are not recommended for this application.

R3 is chosen to provide a relatively broad band-pass response for Y1. You may want to experiment with this value if you use crystals other than those listed in Fig 1. Filter ringing was a problem with a 100-kΩ value at R3. It appeared as a howl in the receiver output. C15 and C17 are used to prevent BFO energy from reaching U1. These capacitors also roll off the high-frequency audio response to minimize the effects of high-pitched audio energy.

---

[1] Notes appear at end of article.


Prod Det/BFO
Q2
40673
3N211
Mixer
Q1
40673
3N211
4 V P-P
Y1
9.000 MHz
FL1
3.7 to 4.0 MHz
5 V P-P
C5 10
C6 68
G2
D
G1
S
PEAK
C9
30
C10
100
R3
2.2 k
U1
R4
100 k
J1
50-Ω
ANT
PEAK
C1
50
C2
150
C3
82
C4
50
L3
R11
6.8 k
R1
100 k
R2
560
C8
0.01
L4
C12
100
L1
L2
C7
39
NPO
C11
0.1
C13
100
RFC2
22 μH
10 V P-P
Y2 (LSB)
9.0015 MHz
1N914
Oscillator
C14
22
W1
Q3
MPF102
2N4416
D2
5.0 to 5.3 MHz
C25
100
NPO
R9
180
C28
0.1
C26
270
Poly
D1
9.1 V
0.4 W
C22 30
MAIN
TUNING
C24
100
NPO
C23
25
CAL
L5
R10
220 k
C27
270
Poly
RFC1
220 μH
Except as indicated, decimal values of capacitance are in microfarads (μF); others are in picofarads (pF); resistances are in ohms; k=1000, M=1000 000.
Poly = Polystyrene
NC = No Connection
5.0 MHz osc freq = 4.0 MHz RX freq
5.3 MHz osc freq = 3.7 MHz RX freq

Fig 1—Schematic diagram of the simple SSB receiver. Fixed-value capacitors are disc ceramic unless otherwise noted. Polarized capacitors are tantalum or electrolytic. Fixed-value resistors are ¼-W carbon composition.

C1, C4, C9—Small plastic or ceramic trimmer, 50 or 60 pF. Small mica trimmers can be used also.
C2, C3, C10—Silver mica, polystyrene or NP0 disc.
C22—Miniature 30-pF air variable with shaft. Double-bearing type preferred. Should rotate smoothly.
C25—Ceramic trimmer capacitor. NP0 type preferred.
D1—9.1-V, 400-mW or 1-W Zener.
D2—Silicon high-speed switching diode, type 1N914.
L1—Four turns of no. 25 enam wire over L2 winding.
L2, L3—8.7-μH toroidal inductor; 44 turns of no. 28 enam wire on an Amidon Assoc T-50-6 toroid. Q_u = 170
L4—2.6-μH toroidal inductor; 25 turns of no. 26 enam wire on an Amidon Assoc T-50-6 toroid.
L5—5.0-μH toroidal inductor; 33 turns of no. 22 enam wire on an Amidon Assoc T-68-6 toroid. Add two coatings of polystyrene Q Dope® to winding for rigidity. Polyurethane varnish can be substituted.
Q1, Q2—Any dual-gate VHF MOSFET. RCA 40673 or 3N211 suitable.
R1—Audio-taper carbon-composition control.
RFC1, RFC2—Miniature ferrite-core RF choke (Mouser; see note 4).
Y1, Y2—9.0-MHz (Y1) and HC-6/U 9.0015-MHz (Y2) crystals (30 pF load capacitance). Available from JAN Crystals, 2341 Crystal Dr, PO Box 06017, Fort Myers, FL 33906, tel 800-237-3063. Catalog available.

The measured rejection of the unwanted (upper) sideband at 700 Hz (single tone) was 16 dB with a high-Q HC-6/U crystal at Y1. The closer the BFO frequency is to the IF, the worse the rejection. A two-crystal lattice filter can be substituted for Y1 if better rejection is desired. You may also want to consider a four-crystal ladder filter.[2]

Q3 operates as a Colpitts oscillator. C22 permits coverage from approximately 3.7 to 4.0 MHz. NP0 capacitors help to ensure acceptable long-term stability. NP0 units can be used at C26 and C27 to further improve the stability, although polystyrene capacitors are quite temperature stable.

Preventing Problems

Owing to the high gain of U1, it is necessary to keep the leads going to the IC as short as practicable. C18 should be located as close to pin 6 as possible. R8 and C21 need to be close to pin 5 and C17 should be near pin 3. The gain of U1 can be increased by decreasing the value of R7, but instability lurks nearby when the chip gain is boosted!

The value for RFC2 is critical. Too large an inductance value causes unwanted self-oscillation below 4 MHz. Use no more than 50 μH of inductance at RFC2.

Do not install Q1 and Q2 on the PC board until all of the other parts have been soldered in place. Dual-gate MOSFETs have fragile gate insulation, and static charges can perforate the insulation, thereby shorting the gates to the drain-source junction. Ground the tip of your solder pencil before soldering the FETs to the circuit board, and use minimum sustained heat.

Construction Comments

A PC-board etching pattern is provided in Fig 2. Boards for this project are avail-



Interior photo showing component layout. This circuit was designed with a minimum number of components, but optional modifications allow 20-meter coverage.

ARRL Lab Test Results

Tests of the model built by the author showed these results:

Minimum discernible signal (MDS): −99.0 dBm (decibels relative to a milliwatt) at 3800 kHz

Blocking dynamic range at 3800/3850 kHz: 76.0 dB

Two-tone, third-order dynamic range at 3800/3850 kHz: 59.0 dB

able from FAR Circuits.[3] A parts-placement guide is given in Fig 3. Single-sided PC board is used for this project.

Main-tuning capacitor C22 should be driven with a vernier mechanism to make tuning easy. An imported dial drive is suitable. The number scale can be used for frequency logging. Vernier drives are available by mail.[4] Surplus gear drives are available from dealers that sell WW II surplus.[5]

If C22 is not mounted securely to the receiver chassis or mainframe, cabinet flexing will cause mechanical frequency instability. Locate C22 as close to the Q3 circuit as possible.

Pads are available on the PC board for HC-6/U and HC-18/U crystals. The crystals can be soldered directly to the board, or you may install crystal sockets for Y1 and Y2. PC-board crystal sockets are available from International Crystal Manufacturing Co.[6]

Mount the receiver PC board by means of four metal spacers. This ensures that the ground foil of the board is well grounded to the mainframe. Proper grounding aids circuit stability.

Receiver Alignment

Use a frequency counter (or general-coverage receiver) coupled to RFC1 via a 50-pF capacitor to set 23 for the desired VFO range. The frequency range of the VFO is dependent on the crystal you select for Y1. In any event, it should have a 300-kHz range for coverage from 3.7 to 4.0 MHz. Adjust C22 for maximum capacitance and tweak C23 to obtain a 5.0-MHz reading on the counter.

Attach an antenna or signal generator to the input of FL1. Find a weak signal at approximately 3.85 MHz. Adjust C1 and C4 for maximum signal response. Repeat this step three or four times to overcome interaction between the resonators in FL1. Now, peak C9 for maximum signal level. There are no further adjustments, assuming that Y2 is on the proper frequency. You can check the Y2 frequency by sampling RF energy at the top end of RFC2 with a small-value capacitor.

Concluding Remarks

This receiver can serve as a foundation for further experimenting. For example,



Fig 2—Circuit-board etching pattern for the receiver, shown full-size from the etched side of the board. Black areas represent unetched copper foil.



Fig 3—Parts-placement guide for the receiver. Parts are placed on the nonfoil side of the board; the shaded area represents an X-ray view of the copper pattern. Component outlines are not necessarily representative of the shapes of the actual parts used.

the IF filter can be improved, as discussed earlier. An RC active audio filter can also be added to improve the overall receiver selectivity.

Although this receiver will drive an 8-ohm speaker rather well for loud signals, it falls short of the mark on weaker signals. This can be corrected by inserting a one-stage audio amplifier between Q2 and U1. A 2N3904 or 2N2222 can provide the extra gain needed for speaker operation. If this is done, add a 100-Ω resistor and 22-µF bypass capacitor to the supply lead that feeds Q2. This will decouple the audio circuits and prevent motorboating.

An S meter can be added by sampling the audio signal at the drain of Q2. Amplify the sampled audio with a 741 op amp, then rectify it with a 1N914 diode and filter it. A microammeter can be driven with the rectified audio to produce meter readings.

A class-A broadband RF amplifier can be added between FL1 and Q1 to enhance the receiver sensitivity. Circuits for these optional changes are given in Solid State *Design for the Radio Amateur* (ARRL).[7]

It should be a simple matter to modify this receiver for operating on other amateur bands. Only the VFO and FL1 need to be changed.

Notes

[1] Deleted.

[2] W. Hayward, "Designing and Building Simple Crystal Filters," *QST*, July 1987, p 24.

[3] $6 (including shipping to US addresses) from FAR Circuits, 18N640 Field Ct, Dundee, IL 60118, tel 312-423-2431, evenings.

[4] Mouser Electronics, 2401 Hwy 287 N, Mansfield, TX 76063, tel 817-483-4422. Catalog available.

[5] Fair Radio Sales Co, 1016 E Eureka St, PO Box 1105, Lima, OH 45802, tel 419-223-2196. Catalog available

[6] International Crystal Manufacturing Co, Inc, PO Box 26330, 701 W Sheridan, Oklahoma City, OK 73126-0330, tel 405-236-3741.

[7] Deleted.

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.

From 1990 ARRL Handbook Ch 30, p 43:

A VXO-Controlled CW Transmitter for 3.5 to 21 MHz

The 6-W CW transmitter shown in Figs. 47 to 50 can be built in a few evenings and will provide hours of on-the-air enjoyment. It features a variable-crystal oscillator (VXO) to generate a highly stable, adjustable-frequency signal. With the circuit shown here, frequency spans of 5 kHz or more can be realized. See Table 1. Only a few crystals are necessary for coverage of the popular CW frequencies. This single-band transmitter may be built for any one band from 80 through 15 meters. Since most crystals for frequencies above 25 MHz are overtone types, and this transmitter requires fundamental-type crystals, there is no provision for 10-meter operation.

Circuit Description

The schematic diagram of the transmitter is shown in Fig. 48. Q1 and associated components form a Colpitts variable-frequency crystal oscillator. C1 is used to adjust the frequency of the oscillator, and C2 is used to limit the span of the oscillator. If no limit is provided, the oscillator can operate "on its own" and no longer be under the control of the crystal. This is undesirable. On the 30-, 40- and 80-meter bands, C2 is not necessary and is omitted from the circuit. Supply voltage is fed to the oscillator only during transmit and spot periods. This prevents the oscillator from interfering with received stations operating on the same frequency.

Output energy from the oscillator is routed to Q2, a grounded-base amplifier. This stage provides some gain, but more important, it offers a high degree of isolation between the oscillator and the driver stage. Oscillator pulling and chirp are virtually nonexistent.

The driver stage uses a broadband amplifier that operates class A. This stage is keyed by grounding the base and emitter resistors. C10 is used to shape the keying waveform. Although the keying is rather hard, there is no evidence of clicks.

Two MRF476 transistors are used in parallel for the power amplifier. These transistors were designed for the Citizens Band service and work nicely at HF frequencies. Each transistor is rated for 3 W output. The original transmitter design used MRF472 output transistors, but Motorola no longer manufactures these devices. They are still available from many surplus outlets, however. L2 is used as a dc ground for the bases, making the transistors operate class C.

The low output impedance at the collectors of the output transistors is stepped up to 50 ohms by broadband transformer T3. A five-element Chebyshev low-pass filter is used to assure a clean output signal. This transmitter exceeds current FCC spectral purity specifications (see Fig. 49). D2 is used to clamp the collector voltage waveform to protect the output transistors if the transmitter is operated into an open circuit or high-SWR antenna system. The transmitter is designed to operate into a load that is close to 50 ohms resistive. S1 is used as the transmit/receive switch. One section transfers the antenna to an accompanying receiver or to the output of the transmitter. Another section is used to activate the VXO during transmit and the third section is provided for receiver muting purposes.

D3 and the associated components form an RF output driver for M1. This circuitry

Table 1

Component Values for the VXO-Controlled, 6-Watt Transmitter

Band	*C1 (pF)*	*C2 (pF)*	*C3, C4 (pF)*	*C6 (pF)*	*C17, C18 (pF)*	*L1*	*L3, L5*	*L4*	*VXO Range*
80 M	365	*	220	100	820	47 Turns T50-2	25 Turns T50-2	32 Turns T50-2	3- 5 kHz
40 M	365	*	100	100	470	36 Turns T50-2	17 Turns T50-2	21 Turns T50-2	5- 8 kHz
30 M	150	*	68	50	330	27 Turns T50-2	14 Turns T50-2	16 Turns T50-2	8-10 kHz
20 M	50	10	50	50	240	30 Turns T50-6	14 Turns T50-6	17 Turns T50-6	10-12 kHz
15 M	50	10	33	33	150	23 Turns T50-6	11 Turns T50-6	14 Turns T50-6	12-14 kHz

*Not used



Fig. 47 — The completed 6-W VXO controlled transmitter is housed in a small aluminum enclosure. RG-174 is used for all interconnections carrying RF. This version uses the older MRF472 output transistors, which are mounted flat on the board.

Fig. 48 — Schematic diagram of the VXO-controlled transmitter. All resistors are ¼-watt carbon types unless noted otherwise. All capacitors are mylar or disc ceramic unless otherwise noted. Polarized capacitors are electrolytic or tantalum.

C1, C2, C3, C4, C6, C17 and C18 — See Table 1.
D1 — Zener diode, 9.1 V, 1 W.
D2 — Zener diode, 36 V, 1 W.
J1, J2 — Binding post.
J3 — Key jack.
L1, L3, L4, L5 — See Table 1. Wind with no. 24 or 26 enamel wire.
L2 — 8 turns no. 26 enameled wire on FB73-801 ferrite bead.
M1 — 0-1 mA meter, Calectro DI-91Z or equiv.
Q1, Q2 — NPN transistor, 2N2222A or equiv.
Q3 — NPN transistor, 2N3866 or equiv.
Q4, Q5 — Transistor, MRF476 or equiv. (see text).
R14-R17, incl. — Fixed resistor, 1.8 ohms, ½ W.
R18 — Meter shunt. 13½ inches no. 26 enamel wire wound on a high-value 1-watt resistor.
S1 — Toggle switch, 3PDT.
S2 — Push-button switch, SPST normally open.
S3 — Toggle switch, DPDT.
T1, T2 — Broadband transformer, 10 turns no. 24 enameled wire, bifilar wound on an FT37-43 core.
T3 — Broadband transformer, 10 bifilar turns no. 24 enameled wire on an FT50-43 core.
Y1 — Fundamental crystal for frequency range desired.



EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF) ; OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS ; k = 1 000, M = 1 000 000.

*HEATSINK

is optional as there are no power-output tuning adjustments. M1 is also used to monitor transmitter current consumption.

Construction

The majority of the circuit components are mounted on a double-sided PC board. One side of the board is etched with the circuit pattern, and the other side is left unetched as a ground plane. A small amount of copper is removed from around each hole on the ground-plane side of the board to prevent leads from shorting to it. A test transmitter was built in the ARRL lab using single-sided board and the transmitter seemed to function normally with no instability. No long term testing was performed, however. A parts-layout guide and photo of the finished board appear in Fig. 50.

Affixed to the front panel are the transmit/receive switch, spot switch and the tuning capacitor. The rear apron supports the antenna and mute jacks, key jack and binding posts.

A homemade cabinet measuring 3 × 6 × 8¼ inches was used in the construction of this transmitter. The builder may elect to build a cabinet from sheet aluminum or circuit-board material. The layout is not critical except that the lead from the circuit board to C1 should be kept as short as possible — an inch or two is fine.

A bent aluminum heat sink was attached to the output transistors. Commercial TO-220 heat sinks could also be used. If MRF472 transistors are available, they can be mounted flat on the circuit board and screws passed through the center of the transistors to hold them down. The ground plane will act as a heat sink sufficient for short key-down periods.

The only adjustment needed is that of setting the VXO limit capacitor (C2), and even this adjustment is not needed for the 80-, 40- and 30-meter transmitters. This adjustment can be done with the aid of a receiver. With a fundamental crystal in the circuit, adjust C2 for a maximum frequency spread that approximates the value shown in Table 1. If too much frequency spread is available, increase the amount of capacitance. Make a final check with the receiver by listening to the keyed signal from the transmitter. It should be steady and chirp free.

To provide wider frequency coverage, several crystals may be used. A crystal socket may be mounted on the front panel, or several sockets can be mounted on a separate circuit board and a simple rotary switch used to connect the desired crystal into the circuit. This option is shown in Fig. 48. Any number of crystals may be used, depending on the number of positions on the rotary switch. With crystals spaced 10-kHz apart, the circuit can provide continuous coverage of 50-60 kHz of the 20-meter band.


S2
SPOT
S1C
J2
+12.5V
J3 DC
CURRENT
RX MUTE
J4
C14 +
22µF
25V
0-1mA
S3B
S3A
M1
S1A
C15
0.1
OUTPUT
TX
S1B
ANT.
J5
PA
T3
R19
1K
R20
10k
D3
IN914
0.01
R21
1k
RX
RX
ANT.
J6
Q4
MRF 476
C
B
A
R14
1.8
R15
1.8
C16
0.1
L3
L4
L5
C17
C18
Q5
MRF 476
D2
36V
1W
R16
1.8
R17
1.8
Y1
Y2
Y3
TO CRYSTAL PADS
ON PC BOARD
OPTIONAL CRYSTAL SWITCH



Fig. 49 — Spectral display of the VXO-controlled transmitter. Here the transmitter is operated in the 20-meter band. The second harmonic is down 56 dB relative to the fundamental output. Similar presentations were obtained on each of the other bands. This transmitter complies with the current FCC specifications regarding spectral purity.


C2
L1
Y1
C1
R2
R1
D1
C3
R4
R3
B
Q1
C
E
R5
S1C
T1
C B A
C
Q2
E
C6
C4
R6
D8
R8
C9
C7
R7
C10
R10
R9
+12 V
R11
C11
C12
T2
C B A
Q3
E
KEY
R12
R13
C13
L2
R15
R17
R14
HEAT SINK
R16
B C E
Q4
B C E
Q5
D2
C15
C14
T3
C B A
C16
ANT
L5
L4
L3
C18
C17

(A)



(B)

Fig. 50 — The component-placement diagram for the 6-W transmitter PC board is shown at A. The component side of the board is shown, with an X-ray view of the circuit foil. A full-size etching pattern appears at the back of this book. At B is a photo of the transmitter circuit board built using MRF476 transistors. The devices are mounted upright on the board with a heat sink attached to the metal tabs on the transistors.



Etching pattern for VXO-controlled CW transmitter. Shown full size from the foil side of the board. Black areas represent unetched copper.

From November 1989 **QST**, *p 37:*

18-MHz COMPONENT VALUES FOR THE *HANDBOOK* VXO CW TRANSMITTER

☐ Yes, the *1989 ARRL Handbook*'s 6-watt, VXO-controlled CW transmitter works well at 18 MHz. Here are component values necessary for using the rig on this band; the component designators listed are those shown in Fig 48 of the *Handbook* write-up:

C1—VXO tuning capacitor; 50 pF.

C2—Limits the VXO tuning range to ensure that the crystal, and not L1 and C1, controls the oscillator frequency. I omitted this capacitor in the version I tested; if you try this and your crystal loses control, use 10 pF.

C3, C4—VXO feedback capacitors; 39 pF, silver mica or NP0 ceramic.

C6—Interstage coupling capacitor; 39 pF, silver mica or NP0 ceramic.

C17, C18—Output filter capacitors; 190 pF, silver mica (10 pF in parallel with 180 pF).

L1—VXO inductor; 28 turns of no. 26 enameled wire on a T-37-6 toroidal, powdered-iron core (measured inductance, 2.5 μH). Space the turns on this coil, and those on L3-L5, to allow a 30° gap between the beginning and end of the each winding.

L3, L5—Output filter inductor: 16 turns of no. 24 enameled wire on a T-37-6 core (measured inductance, 0.85 μH).

L4—Output filter inductor; 20 turns of no. 24 enameled wire on a T-37-6 core (measured inductance, 1.28 μH).

Y1—Parallel-resonant fundamental crystal, 20- or 32-pF load capacitance. An 18.07-MHz crystal borrowed from Zack Lau's QRP Three-Bander (see pp 25-30 of October 1989 *QST*) provided a VXO swing of 10.8 kHz with 39 pF at C3 and C4.

Powered with a 12.0-V dc supply, my version of the VXO transmitter draws 1.26 A dc while producing 6.2 W output at 18.09 MHz. Fig 4 shows the transmitter's output spectrum under these conditions.—*David Newkirk, AK7M, ARRL Staff*



Fig 4—Spectral display of the *ARRL Handbook* 6-W VXO transmitter operating at 18.09 MHz. Each horizontal division represents 10 MHz; each vertical division represents 10 dB. The spike at far left (the spectrum analyzer's first-local-oscillator signal) serves as a convenient "0 MHz" reference. This spectrogram was taken with the VXO transmitter producing 6.2 W of RF energy. All harmonics and spurious emissions are at least 57 dB below peak fundamental output. Modified for 18 MHz as described in the text, the 6-W VXO transmitter complies with current FCC specifications for spectral purity.

From January 1985 QST, p 22:



Simple QRP Gear Versus Good Performance

Low-power, minimum-component gear is easy to build, but performance is often below that which can be obtained with careful design. Let's consider some design pitfalls and the practical project offered here.

By Doug DeMaw,* W1FB

I'm sure you've heard a number of chirpy or buzzy signals from homemade QRP transmitters. In fact, you may have unwittingly turned loose a "super blooper" on the airways yourself! I'd be shading the truth if I did not confess to being guilty of a similar misdemeanor once or twice in my amateur career. It seems that the simpler the transmitter the more prone it is to chirp and related ills. Once we understand the causes of inferior performance, preventive steps can be taken in the design period to avoid generating "lid" style signals.[1]

Although we are addressing simple transmitters in this discussion, the general approach to design can be applied to most oscillators and VFOs that are part of a larger circuit, such as a multistage high-power transmitter. Since the oscillator is the heart of a transmitter or receiver, it deserves special care in the design and construction stages.

Profile of an Oscillator

There have been many discussions of what oscillators are and how they function. Certainly, *QST* and the ARRL *Handbook* have carried a wealth of data on this subject over past decades. But for the purpose of quick review, let's look at Fig. 1. The circuit example at A shows a Pierce oscillator that has an untuned output circuit. Feedback to make the circuit oscillate is between the base and collector of Q1. This positive feedback is provided by C1 and C2. The capacitance ratio is adjusted to ensure fast starting of the oscillator when it is turned on or keyed. Remember that an oscillator is actually an amplifier. Part of the power output is routed back to the input circuit to cause oscillation. Therefore, C1 and C2 are chosen to ensure just enough feedback energy to provide reliable oscillation. Typically, a ratio of 4:1 in the feedback capacitors is a good starting value during initial design. In other words, we should attempt to use one fourth the output power as feedback energy.



Fig. 1 — Example of a Pierce solid-state oscillator (A). C1 and C2 control the feedback in the circuits at A and B. A Colpitts oscillator is found at B of this drawing.

We need to remember, also, that this feedback power is taken from the output power available for delivery to the load. It is for this reason that an oscillator is not as efficient (dc input power versus RF output power) as a straight RF amplifier. In the interest of best efficiency, we should use no more feedback power than is required for reliable circuit oscillation. There are other reasons why too much feedback is undesirable. It can cause a chirpy output signal and oscillation at frequencies other than the desired one, and may harm the crystal from the effects of excessive current. The high current can cause the crystal to heat up or even fracture. This danger is more pronounced as the operating frequency is increased (raised) because the higher the crystal frequency the thinner the quartz element in a crystal. An overheated crystal will drift in frequency, just as a VFO will with changes in component temperature. Some amateurs attempt to generate substantial power by using a power oscillator in a one-stage transmitter. The results are often dismal, owing to excessive crystal current and drift.

---

[1] Notes appear at end of article.

*ARRL Contributing Editor, P.O. Box 250, Luther, MI 49656

Further examination of Fig. 1A shows that the emitter of Q1 is at RF ground by virtue of the 0.1-µF emitter bypass capacitor. Fundamental-frequency oscillators (output frequency the same as the crystal frequency) have only two terminals that are "hot" at RF. Attempts to have all three terminals "alive" with RF energy will result in unstable performance, or no oscillation at all. The exception is when the oscillator serves also as a frequency multiplier, as in Fig. 2.

RFC1 of Fig. 1A is selected to be self-resonant well below the desired oscillator frequency. In our circuit, we find a value of 1 mH. We can assume approximately 10 pF of stray circuit capacitance at the output of Q1. Therefore, the self-resonant frequency of RFC1 is on the order of 1.6 MHz — well below 3.5 MHz, the oscillator frequency. Owing to the nature of this circuit, the output circuit of our oscillator is broadband. It would be suitable also for use above 80 meters if the values of the feedback capacitors were changed.

The amount of feedback energy needed is dependent mainly upon how active the particular crystal is, plus the beta of the transistor we happen to connect to our circuit. The beta (gain) of a transistor varies considerably between one transistor and another from the same manufacturer's production run. This is why the data sheets list the beta with a "typical" value. In reality, it can be above or below that value by a fair margin. Because of unknown crystal characteristics and the so-called "beta spread," we need to adjust the feedback for each circuit we build — if optimum performance is desired.

Colpitts Oscillator

Thus far we have considered only the Pierce oscillator. There are countless other types of crystal-oscillator circuits, and each is named after the person who developed it. The Pierce and Colpitts circuits seem to be the most common in amateur circuits, and that is why I have selected them for this discussion. The basic form of Colpitts oscillator is shown in Fig. 1B. In this example, we find that the collector is "cold" in terms of RF energy by means of the 0.1-µF bypass capacitor. The base and emitter terminals of Q1 are hot with regard to RF energy. C1 and C2 comprise the feedback divider. They can be adjusted in value to provide the required amount of feedback power.

RF output is taken from the oscillator emitter circuit. The output voltage is quite low compared to that of the Pierce circuit of Fig. 1A because of the low impedance of the Colpitts oscillator output tap point. Both oscillators require the smallest practical value of output coupling capacitor (C3) to minimize loading of the oscillator, which can cause chirp (when keyed) or no oscillation at all. A typical value for C3 at 80 meters is 50-100 pF. Smaller values are recommended for 7 MHz and higher. The larger the value of C1 in Fig. 1B, the greater the feedback amount. In some circuits, we may eliminate C1 completely. This is because there may be sufficient capacitance within the transistor to serve as C1. This will depend on the transistor type we select for Q1.


OSCILLATOR / DOUBLER
2N3904
Q1
14.2 MHz
2f OUTPUT
27
C1
100
7.1 MHz
f
Y1
5.6 k
10 k
18
L1
1.5 µH
RFC
500 µH
68
220
0.01
0.01
100
+12 V
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k=1000

Fig. 2 — A crystal oscillator may be used as a frequency multiplier, as shown here. The collector circuit is tuned to the desired harmonic of the crystal.

We can conclude from the previous discussion that there are many variables that dictate how we select component values for a given crystal oscillator circuit. Experimentation has long been the motto of amateurs, so this requirement should be a matter of course for most of us who manipulate a soldering iron in the small hours of the morning! The variables that apply to crystal oscillators do, of course, relate to VFO (variable-frequency oscillator) circuits as well. Because of these variations in transistors and crystals, it is not unusual to find that a circuit we duplicate from an amateur journal does not perform as specified — or perhaps not at all! The author may have chosen the proper component values for his or her crystal and transistor, but they may be incorrect for your components.

Oscillators That Change the Frequency

Earlier, we touched upon an oscillator that serves also as a frequency multiplier. We would not want to use such a circuit in a one-transistor QRP transmitter, but we could use it to drive a straight-through amplifier in a low-power transmitter. The reason we should avoid oscillator/multipliers directly into an antenna is because they are quite inefficient, and they would cause subharmonic energy to be radiated. The exception in the case of subharmonic radiation would be when we use well-designed filters in the transmitter output. The filters would have to reject the *oscillator* frequency as well as harmonics of the desired output frequency. This would call for a quality band-pass filter rather than the customary low-pass filter. In other words, we would need to reject frequencies above *and* below the desired output frequency.

An example of an oscillator/multiplier is shown in Fig. 2. The basic circuit is a Colpitts oscillator of the kind we saw in Fig. 1B. The difference is found in the collector circuit. C1 and L1 comprise a tuned collector tank that is adjusted for resonance at twice (2f) the crystal frequency. The collector of Q1 is no longer cold at RF, but has 14.2-MHz RF current present. Output from this circuit will be lower than that from the oscillator of Fig. 1B. This is because the efficiency of any multiplier is lower than that for a straight-through amplifier. Most oscillator/doublers exhibit an efficiency of approximately 33% after being optimized. Were we to triple or quadruple in the collector circuit (which is entirely acceptable), the efficiency would be correspondingly lower. The technique is useful when we are willing to amplify the oscillator/multiplier output by means of straight-through amplifiers. Generally, the CW note will be less prone to chirp if we multiply in the oscillator or in the stage immediately after the oscillator. For the most part, our cost will be minimal when we add an amplifier after a frequency-multiplier stage: Transistors and resistors are quite inexpensive these days!

Aids to Frequency Stability

Voltage regulation is important in an oscillator if the main power supply is not regulated. How can we achieve oscillator regulation simply and at low cost? A Zener diode regulator is the answer. The circuit of Fig. 3 illustrates the simplicity of Zener diode dc regulation. D1 is a 9.1-V, 400-mW regulator. It will hold the oscillator base and collector voltage constant during key-down conditions. R1 is the dropping resistor for the diode. Without this resistor, the diode would draw excessive current and burn up. If the resistor has too much resistance, the diode will not regulate at 9.1 V. Information on selecting the correct value of resistance is presented in the ARRL *Handbook*. We need to recognize that the Zener diode must draw a certain amount of current if it is to provide regulation. This current can range from 10 to


OSCILLATOR
Y1
3.7 MHz
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS; k=1000
2N2222
Q1
R2
22
C1
27
5.6 k
10 k
100
0.1
RFC 1
1 mH
0.1
C2
120
C3
0.001
CLASS-C
PA
2N2222
Q2
TO OUTPUT NETWORK
RFC 2
22 μH
27
R1
220
+ 12 V
KEY LINE
D1
9.1 V
400 mW

Fig. 3 — An example of how a Zener diode (D1) can be used to ensure stable operating voltage (see text).

Table 1
Values of L and C for the One-Stage QRP Transmitter (Fig. 4)

Band	*C1 (pF)*	*C_s (pF)*	*C2 (pF)*	*C3 (pF)*	*C4 (pF)*	*L1 (μH)*
3.5 MHz	1000	330	100	1200	100	4.2, 29 turns no. 26 wire on T50-2 toroid core
7.0 MHz	560	180	100	600	47	2.12, 20 turns no. 26 wire on T50-2 toroid core
10.1 MHz	470	100	100	430	33	1.48, 19 turns no. 26 wire on T50-6 toroid core
14.0 MHz	470	68	100	300	27	1.0, 13 turns no. 26 wire on T50-6 toroid core

Note: C2 is a Mouser no. 24AA034 (page 76) 10-mm-diameter trimmer, 15-100 pF. C3 and C_s should be polystyrene or silver mica. All others are disc ceramic.


EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS; k=1000
C4
Ⓡ
RECEIVE ANT
1N914
D1
D2
OSCILLATOR
BREAK AT "X" TO INSERT FILTER
L1
2N3866
Q1
B
R4
15
C
Cs
C2
100
C3
C5
0.01
Ⓐ
STATION ANT (50 OHMS)
Y1
5.6 k
R1
R2
15 k
E
R7
1k
Ⓧ
JUMPER
RFC 1
560 μH
C1
RFC 2
10 μH
R3
33
C6
0.1
2N4036
Q2
C
B
E
Ⓚ
KEY
R5
2.2 k
C7
1 μF
25 V
0.1
C8
R6
10 k
PNP SWITCH
B
E
C
BOTTOM VIEW
Q1, Q2
⊕
+12 V REGULATED
C9
22 μF
25 V
I(TOTAL) = 60 mA MAX.

Fig. 4 — Schematic diagram of a practical QRP transmitter. Resistors are ¼-W carbon composition. Fixed-value capacitors are disc ceramic. Capacitors with polarity marked are electrolytic or tantalum. C2 is a ceramic trimmer capacitor. See Table 1 for coil and capacitor data for the bands from 80 through 20 meters. Y1 is an International Crystal Mfg. Co. type GP, 20-pF load capacitance. Other fundamental crystals will be suitable (see text).

18 mA in this type of circuit, depending on the value of R1. For portable operation from a battery power supply, therefore, this added current must be taken into account when considering the discharge rate of the battery.

You will notice also that we have added R2 in the circuit of Fig. 3. This 22-ohm resistor is located close to the collector of Q1 to prevent unwanted parasitic oscillations that may occur at VHF. It is not unusual for a high-frequency transistor to self-oscillate in the VHF range when the circuit board is laid out with long copper elements. R2 serves as an inexpensive preventive device. Parasitic oscillation can impair the efficiency of the oscillator, encourage spurious radiation, and cause the CW note to be unclean. R2 may not be necessary in circuits that are laid out carefully.

Our circuit in Fig. 3 is a Pierce oscillator. C1 is a feedback capacitor, and C2-C3 in series provide the remaining part of the feedback divider. The effective value of C2 and C3 in series is 107 pF. These two capacitors function as an impedance-transformation circuit as well. The impedance at the top end of RFC1 is quite high compared to that of the base of Q2. The Q1 collector impedance is stepped down by virtue of the ratio of C2 and C3. The *ARRL Electronics Data Book* contains the equations and examples for using capacitive dividers to transform one impedance to another.

Simple Transmitter Performance

Some builders of homemade QRP transmitters are unmindful of the importance of proper impedance matching and output network design. It is not unusual to find some hams using one- or two-stage QRP rigs with output tank circuits that follow vacuum-tube concepts. That is, a single tuned output circuit is used, without regard for the collector and load impedance. Maximum power transfer can't be had without suitable matching of the impedances. Under some conditions of mismatch, the PA (power amplifier) stage may break into self-oscillation. This can cause spurious radiation, and it may even destroy the PA transmitter.

Take, for example, a tube QRP rig that has 150 plate volts and draws 10 mA when operating at 1.5-W dc input power. The plate impedance is 15,000 ohms. Conversely, a 1.5-W solid-state final amplifier that uses a 12-V collector supply will have a collector impedance on the order of 96 ohms. Attempts to use a tube type of output tuned circuit will be met with dismal results when dealing with a 96-ohm collector impedance! Furthermore, the transistor collector will load the high-impedance tank circuit and destroy the Q. This will permit harmonics to be radiated from the antenna, thereby causing TVI and interference to other services. The transmitting chapter of the ARRL *Handbook* contains detailed data on impedance-matching networks for solid-state transmitters.

A Practical One-Stage QRP Transmitter

An uncomplicated circuit for QRP transmitting from 80 through 20 meters (see Table 1) is shown in schematic form in Fig. 4. Dc power input is 250 mW (¼ W), which is ample for worldwide communications under good band conditions if an effective antenna is used (beam antenna, vertical radiator or dipole high above ground). This transmitter permits full break-in (QSK) without the use of antenna relays. The receiver antenna-input line is simply connected to point R of Fig. 4. When the key is up, the receiver is effectively attached to the station antenna. Upon closure of the key, the antenna line to the receiver is shorted to ground by means of D1 and D2. This transmit-receive (TR) circuit permits instant changeover from transmit to receive.

Q2 is a dc switch that serves as a keying transistor. When the terminals at K of Fig. 4 are shorted by the key or keyer, Q2 saturates and supplies +12 V to Q1, thereby turning on the oscillator. C2 is adjusted for maximum power output (100 mW), consistent with a chirp-free CW note. (The best note should occur at the dip in Q1 collector current — approximately 30 mA of total transmitter current.)

R5, C7 and C8 form a shaping network to soften the trailing edge of the CW waveform. The purpose of R7 is to provide a light load at the output of C5 under all conditions. I observed that the transmitter tended to be unstable before R7 was added, particularly when the SWR was higher than 2:1. The instability was observed while I was adjusting the Transmatch for an all-band antenna. Stability was fine when a low SWR was present while using a dipole fed with 52-ohm coaxial cable.

VXO Operation

The pair of terminals marked with an X in Fig. 4 identify the location of a jumper wire that can be removed to permit variable crystal oscillator (VXO) operation through insertion of a coil and variable capacitor. This modification is shown in Fig. 5. C_{VXO} can be a broadcast-band variable with half of the rotor plates removed; a 100- or 140-pF miniature variable capacitor may be used.

L_{VXO} is a small inductor wound on a toroid core. The greater the inductance, the more you will be able to shift the crystal frequency. Too large an inductance, however, will cause Q1 to function as a VFO rather than as a crystal oscillator. This will cause instability and chirp. Typical frequency swings are 2 kHz at 80 meters, 6 kHz at 40 meters, 9 kHz at 30 meters and 12 kHz at 20 meters. Experimental values for L_{VXO} are 12 μH (20 meters), 15 μH (30 meters), 20 μH (40 meters) and 30 μH (80 meters). Experiment with the number of coil turns until you obtain frequency shifts on the order of those listed.

Table 2
Low-Pass Filter Components

Band (Meters)	*C10, C11 (pF)*	*L2 (μH)*	*Filter Cutoff (MHz)*
20	220	0.5 13 turns no. 24 enam. on Amidon T37-6 toroid	15
30	270	0.72 16 turns no. 24 enam. on T37-6 toroid	11
40	390	1.0 15 turns no. 24 enam. on Amidon T37-2 toroid	8
80	820	2.0 22 turns no. 26 enam. on T37-2 toroid	4



Values for use in building a single-section harmonic filter that can be added at the output of the QRP transmitter. C10 and C11 can be disc-ceramic, silver-mica or polystyrene capacitors.

The recommended crystals for VXO and standard use in this transmitter are plated AT-cut fundamental crystals in HC-6/U holders. A load capacitance of 20 pF is suitable for the crystals. Surplus crystals in FT-243 holders may not offer good activity, and they probably won't do too well for VXO operation.

Construction Notes

Keep the leads of all components as short as possible when soldering them to the PC board. Also, when winding L1, be sure to spread the coil turns around 2/3 of the toroid core. Bunching them too close together will increase the inductance, and spreading them over all of the core will decrease the inductance.

You may wish to add a single pi-section harmonic filter to the transmitter output in the interest of spectral purity. I have used this circuit with and without the filter, and have found the output (without the filter) to be clean enough to prevent TVI or harmonic radiation that could be detected on the air. Table 2 contains a circuit that can be added. The photograph of the transmitter shows the three added components for the filter. I made six holes with a no. 60 drill and soldered the filter in place. If you choose to follow this approach it will be necessary to sever the circuit-board foil between C5 and the antenna output terminal. A Moto Tool® or knife blade will be suitable for cutting the copper. Alternatively, you may mount the parts on a piece of perforated board and glue the subassembly to the main circuit board near the antenna output terminal. Spectral photos of the transmitter output before and after the



Fig. 5 — The jumper across terminals X of Fig. 4 may be removed to add these components. A coil (L_{VXO}) and a tuning capacitor (C_{VXO}) are used to shift the crystal operating frequency (see text).


(A)

(B)

Fig. 6 — Spectral display of the QRP transmitter, without the filter (A) and with the filter (B). Horizontal divisions are each 10 MHz; vertical divisions are each 10 dB. Power output is approximately 0.25 W on 20 meters. At A, all spurious output is at least 34 dB down from peak fundamental output; at B, at least 52 dB down.



Fig. 7 Component side view of the PC board showing placement of the components.

addition of the simple filter are shown in Fig. 6.

The completed assembly can be mounted in a cabinet or box of your choice. A nice homemade box can be fashioned from pieces of double-sided PC board that are soldered together where the sections join. The circuit need not be completely enclosed. Rather, you may prefer to mount the board on short standoff posts on an L-shaped piece of aluminum stock. The vertical part of the L can then serve as a panel for the jacks and VXO tuning capacitor. Adhesive-backed plastic feet can be affixed to the bottom of the L chassis. Your 12-V power supply can be packaged in the same box that contains the transmitter.[2] A parts placement guide is provided in Fig. 7. A scale etching template is given in the Hints and Kinks column.

Adjustment and Use

Attach a 56-ohm resistor at the transmitter output to serve as a dummy load. Apply operating voltage and plug in your key. Hold the key down and tune your receiver to the transmitter frequency. Send some CW and monitor the note. If it is chirpy, adjust C2 until the CW note sounds proper. You can observe the S meter on your receiver while tuning C2 for maximum power output, consistent with a good-sounding CW note.

With an antenna connected (it should have an impedance of 50 ohms), look for a clear frequency and call CQ. It is wise to have two or three crystals available if you do not use VXO control. Don't despair if you don't receive an answer on the first few calls. That can happen even when running QRO (high power)! Eventually you will receive a response to your CQ, and the fun will commence. When answering someone on or near your crystal frequencies, try to respond to loud signals. This will mean that your signal will probably be fairly loud in the other station's receiver, assuming the operator is not running high power.

In Summary

If you haven't had the courage to work with transistors, this article may be the stimulant you've needed. On the other hand, if you've been building simple QRP rigs and have had poor results, the design tips we've discussed may get you headed down the right path.

There are many QRP operators in the world, so why not join them and face the exciting challenge of low-power operation. If you want to use this little transmitter in the field, take along a 12-V motorcycle battery, a lantern battery or 10 size-D cells connected in series. Of course, you will need a battery-operated receiver to use with your transmitter for field work. Numerous circuits for QRP receivers are described in the ARRL book, *Solid State Design for the Radio Amateur.*

Notes

[1] A "lid" is a poor operator, or one with a bad-sounding signal. The term comes from the early days of Amateur Radio and is rumored to have been inspired by a bad CW signal that sounded like the lid on a kettle of boiling water.

[2] Deleted.



Circuit-board etching pattern for the QRP transmitter. The pattern is shown full-size from the foil side of the board. Black areas represent unetched copper foil.

From December 1986 QST, p 19:

Three Fine Mice—MOuSeFET CW Transmitters



Got a hankerin' to build a simple CW transmitter that's a real performer? Take your pick—one or all—for 80, 40 and 30 meters. They're VFO controlled, too!

By Michael J. Masterson, WN2A
7 Hudson Rd
Budd Lake, NJ 07828

The availability of low-cost power MOSFETS (they're not really MOuSeFETs!) creates new possibilities for "homebrew" transmitter design. For several years, I have used various RF bipolar transistors, all priced in the $12 to $16 range, in homebrewed CW transmitters. They performed well, but when I found inexpensive switching MOSFETS priced at $1 to $2, I thought: "Why not give them a try?" The low-cost devices seemed to be a painless (to the pocketbook) way to determine the MOSFET's potential and how to tame it for use at RF. Since I'd lost a few RF bipolar transistors while learning how to use them, I knew certainly that a few MOSFETS would be "cooked" before I found the right circuit. I selected 30 meters as the test band, and eventually built transmitters for 30 and 40 meters.

Technical Approach

From articles I reviewed, it was apparent that the majority of MOSFET transmitter circuits use a 24-V, or greater, drain potential and most use RF-characterized device types. Because RF power MOSFETs are priced too high for this learning effort, my objective was to obtain at least 10 W output from a switching MOSFET operating from a 12-V supply.

Different circuits employing heavy gate swamping, RF feedback, drain loading and even the common-drain configuration were tried.

So, I did a lot of computer modeling, experimentation and article review. Different circuits employing heavy gate swamping, RF feedback, drain loading and even the common-drain configuration were tried. Some of these circuits looked promising—for a while. But, just as a circuit seemed to provide sufficient gain, the device would be destroyed by gate breakdown, not excessive dissipation or thermal runaway. I discovered that some form of gate protection is required, along with capacitive drain loading. Apart from the final amplifier, the remainder of the transmitter uses a proven transistor lineup from a previous design.

Circuit Description

Fig 1 is the schematic diagram of the transmitter. Frequency dependent parts information is given in Tables 1 and 2. The transmitter power chain is straightforward and is divided between two boards. (All transmitters use the same PC boards.) The VFO board contains Q1, an FET VFO, buffer Q2 and the balanced doubler composed of Q3 and Q4. D4 provides power-supply regulation for Q1. The 80-meter transmitter uses a Hartley VFO; it's a simple circuit and keeps the inductance of L1 at a reasonable value. A series-tuned Clapp oscillator with the inductor wound on an air-core ceramic form (for stability) is used in the 30- and 40-meter transmitters. Balanced doubler Q3-Q4 gets its drive from the bifilar winding on T1. The transistor collectors are tapped down on T2 for optimal output. T2 is tuned to the operating frequency, twice the VFO frequency.

The VFO runs continuously. When



Fig 1—Schematic diagram of the MOuSeFET low-power transmitter. The 80-meter VFO is shown in the inset drawing. Refer to the parts list and Tables 1 and 2 for parts values not shown on the diagram. All 0.1-µF capacitors are 25-V X7R or Z5U ceramic types. All resistors are ¼- or ½-W, 10% tolerance acceptable.

C11—47-µF, 16-V electrolytic or tantalum.
C12—Deleted.
D1-D3, incl—1N4148.
D4—8.2-V, 400-mW Zener diode (1N959 or equiv).
D5—13-V, 400-mW Zener diode (1N964 or equiv).
FB—2t no. 28 enameled wire on FB-43-101 ferrite bead.
J1—Amphenol 126-011 jack (or equiv).
J2—Phono jack.
P1—Amphenol 126-010 plug (or equiv) for power cable.
Q1, Q2—MPF102 (see text).
Q3, Q4—2N3904 (see text).
Q5—2N3053 (see text).
Q6—80M, IRF 523; 40 m and 30 m, IRF510.
Q7—2N3906 or 2N2907A.
R1—500-Ω, 1-turn trimmer potentiometer.
RFC1—100-µH RF choke on phenolic form (Miller 4642 or equiv).

spotting, the buffer and doubler stages are keyed. The driver and final amplifier stages are on only during transmit when +12 V is applied at J1-E through an external TR switch. C12 provides some keyed wave-shaping, and R1 is an adjustment for doubler balance. C10 ensures stability at this stage, but it may not always be necessary. Measured VFO-board output is in the order of 60 mW. Improved keyed-wave shaping using a time-delay circuit was devised by Zachary Lau, KH6CP, of the ARRL Lab. That circuit employs a general-purpose PNP transistor, Q7, to moderate the otherwise fast rise time of the keyed wave. This addition also allows one side of the key to be grounded.

Q5, a 2N3053 operating class C, and Q6, an International Rectifier IRF type MOSFET also operating class C, comprise the power-amplifier chain. Q5 delivers about 1 W through an L network to Q6's gate circuit.

A power MOSFET's gate circuit is quite different from a bipolar power amplifier's base circuit. D5 provides two functions: It protects Q6 from excessive gate voltages and acts with C15 to provide a "grid-leak" action. During the negative half-cycle, D5 conducts and charges C15; during the positive half-cycle, C15's charge is added to the RF drive to supply a maximum of 15 V gate potential. Power MOSFETS have a high input resistance, but do require drive during switching. This is because of gate-source and gate-drain (Miller) capacitances. Gate-loading resistor R3, and drain-loading capacitor C7, augment stability as verified on a computer-aided design program. R4 limits the power dissipated in D5.

L4, C8, L5 and C9 form an L-pi output network (a pi-L in reverse). The L section matches the 5-ohm drain impedance of Q6 to a 100-ohm image impedance with a Q_L of 4.35. A pi network with a Q_L of approximately 2 then takes the 100-ohm image impedance down to 50 ohms. This type of network is less critical to tune than a T network for a given amount of harmonic suppression. At a nominal power output of 16 W, the second harmonic is 45 dB down; other harmonics are at least 60 dB down. (This performance was verified in the ARRL Lab.) The power level you obtain may be somewhat greater on 80 meters and less on 30 meters.

Component Notes

Most components used in this project are


PA BOARD
J1-D +12 V
0.1
J1-A KEY
0.1
J1-E +12 V TRANSMIT
0.1
J1-B KEY
L6
FB
0.1
0.1
C11
47 µF 15 V
0.1
L7
2.7k
L2
L3
.01
C15
Q6*
L4
L5
PA OUTPUT
0.1
D5
C6
Q5
R3
2.7k
C7
C8
C9
R4 10
NOTES: J1-A AND J1-B TO KEY
J1-D TO +12 V (ALWAYS)
J1-E TO +12 V (TRANSMIT ONLY)
* HEAT-SINK Q6 (SEE TEXT)
** NOT USED IN 30-M VERSION
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000, M = 1000 000

widely available from radio component stores, hamfests or mail-order distributors. A & A Engineering is a one-stop source for boards and parts for this project.[1] The devices recommended for use at Q1 and Q2 are not difficult to find, and a 2N4416 or 2N3823 may also be used. Q3 and Q4 should be matched for current gain, or at least originate from the same production lot. A match of 50% or better (at I_c = 10 mA) will suffice. A 2N2222A can be used at Q3 and Q4, and candidates for Q5 include the 2N2102 or D42C4; good results were obtained with the D42C4 at 80 meters. I purchased the MOSFET (Q6) from Frank, K2AW, at a hamfest table.[2] Motorola, RCA, GE, GI and other manufacturers make IR equivalents.

The toroidal inductors are available from Amidon or Radiokit.[3,4] All coils are wound with no. 28 enameled wire. After the VFO is built and tested (see tune-up and operation), hold the L1 windings in place with a thin layer of glue. L4 and L5 are wound with two paralleled wires to effectively increase the wire size and reduce copper losses. (These are *not* bifilar windings! You may optionally use a larger wire size instead.) Except where noted, capacitors are X7R or Z5U ceramic types. These are used for bypassing and decoupling functions, but not in tuned circuits. C2 and C3 are specified as NP0 ceramic units for excellent temperature stability. C4 through C10, inclusive, can be polystyrene, silver-mica or NP0 ceramics. Do not use X7R or Z5U ceramic capacitors here—degraded performance can result. Polystyrene capacitors work well in this circuit, and are compact compared to mica or NP0 ceramic types. Use caution when soldering polystyrene capacitors because excessive heat will melt the plastic.

Construction

The transmitter may be housed in any

Table 1

Frequency Dependent Capacitor and Resistor Values

Capacitor Number	*80 M*	*40 M*	*30 M*
C1	25-pF air var	35-pF air var	35-pF air var
C2	450 pF (9 × 50 pF N)	1000 pF P	940 pF (2 × 470 pF P)
C3	50 pF N	470 pF P	600 pF (6 × 100 pF N/P)
C4	200 pF (2 × 100 pF N/P)	100 pF N/P	100 pF N/P
C5	200 pF (2 × 100 pF N/P)	100 pF N/P	50 pF N/P
C6	1000 pF P	470 pF P	330 pF P
C7	3300 pF P	1000 pF P	400 pF (4 × 100 pF N/P)
C8	2700 pF P	1410 pF (3 × 470 pF P)	1000 pF (10 × 100 pF N/P)
C9	1100 pF P	700 pF (7 × 100 pF N/P)	400 pF (4 × 100 pF N/P)
C10	50 pF N/P	50 pF N/P	
C13	Not used	250 pF (5 × 50 pF N)	250 pF (5 × 50 pF N)
C14	Not used	60-pF trimmer	60-pF trimmer

N = NP0 ceramic; P = polystyrene; N/P = NP0 ceramic or polystyrene. Silver-mica capacitors can be substituted for the polystyrene types.

Resistor Number	*80 M*	*40 M*	*30 M*
R2	47	68	68
R3	22	33	33
R4	10	10	10

---

[1] Notes appear at end of article.

sturdy, shielded enclosure. An 8 × 5 × 5-inch (LWD) cabinet provides more than enough room; even a 7 × 5 × 3-inch box, such as the LMB 782, is of ample size. The two circuit boards measure about 2 × 3 inches each, the VFO board being slightly larger than the PA board. A single-sided PC board (or perfboard and flea clips, if desired) is used for the VFO. This board can be installed in a box to shield it from the PA board, but no ill effects were found without the shield. If you elect to shield the VFO, C1 should be installed in the VFO box, and the larger transmitter cabinet used. Short, stiff leads from C1 to the VFO board are important for mechanical stability. Figs 2 through 5, inclusive, show the exterior and interior views of two of the three prototype transmitters. The 80-m transmitter (Figs 2 and 4) was the first unit built. Figs 3 and 5 are views of the 40-m unit.

The power amplifier PC board is double-sided, with one side left unetched. Copper foil or braid is used to provide low-inductance wraparounds to ground. Solder the foil to both sides of the board. Alternately, plated-through holes can be used in place of wraparounds. Solder all other components to this board prior to installing Q6. Cut the leads of Q6 to a length of 0.3 inch, and mount the transistor at the board edge. Insulating hardware for Q6 consists of a kapton or mica insulator, nylon washer and spaghetti sleeving for the metal bolt. Heat-sink grease is thinly applied to both sides of the insulator. (Too much grease impairs heat transfer.) The PA board and Q6 are bolted to the front panel, which acts as a heat sink. The leads of Q6 must not be stressed, so shim the PA board with metal washers if necessary. A small, clip-on heat sink will help Q5 dissipate heat.

Table 2
Frequency Dependent Inductance Values

Inductor Number	*80 M*	*40 M*	*30 M*
L1	14.5 μH 60t on T50-6, tap at 14t	14.1 μH 40t no. 36 enameled wire on 3/8-in-dia ceramic form	7 μH 35t on 3/8-in-dia ceramic form
L2	13t on FT-37-61	9t on FT-37-61	9t on FT-37-61
L3	19t on T50-2 (1.8 μH)	12t on T50-6 (0.5 μH)	9t on T50-6 (0.33 μH)
L4[1]	15t on T50-6 (0.9 μH)	10t on T50-6 (0.43 μH)	8t on T50-6 (0.3 μH)
L5[1]	22t on T50-2 (2.8 μH)	15t on T50-2 (1.2 μH)	13t on T50-6 (0.9 μH)
L6	11t on FT-37-61	10t on FT-37-61	9t on FT-37-61
L7	11t on FT-37-61	9t on FT-37-61	6t on FT-37-61
T1	pri: 18t on FT-50-61 sec: 9 bifilar turns	pri: 16t on FT-50-61 sec: 8 bifilar turns	pri: 12t on FT-50-61 sec: 10 bifilar turns
T2	pri: 40t, tap at 20t[2] sec: 7t on T50-2	pri: 26t, tap at 11t[2] sec: 5t on T50-2	pri: 22t, tap at 10t[2] sec: 4t on T50-2

All inductors wound with no. 28 enameled wire unless otherwise noted.

[1] L4 and L5 are wound with two parallel lengths of no. 28 enameled wire this is done to increase the effective wire size. These are *not* bifilar windings.

[2] Tap measured from Q7 side of primary.

Powdered-iron toroids (T50-6 and T50-2) and ferrite toroids (FT-37-61 and FT-50-61) are available from A & A Engineering, Amidon Associates or Radiokit (see notes 1, 3, 4). Ferroxcube 3/8-in 4C4 and 1/2-in 4C4 ferrite toroids may be substituted.

Tune-Up and Check-Out

With the exceptions of C1 and C14 (if used), there are no other variable capacitors in the transmitters. All tune-up is done by adding or removing turns on the toroidal inductors, and by compressing or expancing the windings. This may take some time and patience, but it results in compact construction without the need for large trimmer capacitors. Start with one or two extra turns on L1, the primary of T2, L3, L4 and L5, and remove turns as required during tune-up.

First, adjust the VFO tuning range by listening to its output with a calibrated receiver or coupling a frequency counter to the VFO output. (If your frequency counter is not sensitive enough, you'll have to use a receiver initially.) Set R1 at midrange and apply +12 V to J1-D, with a key across



Fig 2—An 80-m transmitter was the first unit built. The enclosure was salvaged from a piece of defunct test equipment.



Fig 3—This 40-m unit is constructed in a readily available aluminum box. The 5-pin connector serves as a key and power-input jack.



Fig 4—A close look at this inside view of the 80-m transmitter reveals the VFO is built on perf board. Note the shielded VFO enclosure (cover removed). To the left is the driver/output board. Q6 may be seen in the foreground attached to the heavy front panel.



Fig 5—An inside view of the 40-m unit. PC boards from A & A Engineering were used in this model.

J1-A and J1-B. Adjust L1 for the desired band coverage, as you vary C1. Next, set C1 to mid-band and adjust the primary of T2 (80 meters) or C14 (30 and 40 meters) for maximum output as indicated on a sensitive power meter connected to VFO output. If C14 does not allow you to tune through a maximum output point within its range, adjust the primary of T2 until it does. Using a wave or dip meter, sense around T2, and set R1 for minimum fundamental feedthrough (that is, 1.8 MHz on 80 meters, 3.5 MHz on 40 meters and 5 MHz at 30 meters). You should notice a setting of R1 where the fundamental nulls out. Then, disconnect the power meter and connect the VFO output to the PA input using a short length of coaxial cable.

Next, connect an RF power meter to J2 and apply +12 V to J1-D and J1-E. Keying the transmitter briefly, adjust L3, L4 and L5 for maximum output. Go back and adjust the primary of T2 (80 m) or C14 (30 and 40 meters) to peak the output reading.

. . . you should have 12 to 20 W of RF output

Again, adjust L3, L4 and L5 if necessary to maximize output power. At this point, you should have 12 to 20 W of RF output. (With or without parts substitutions, your results may vary from mine because of construction or other differences. Prior RF-circuit building experience should help you correct any problems.) Finally, adjust R1 for minimum fundamental feedthrough as heard on a receiver. Again, a null should be found. Set the receiver to the transmitter's output frequency and reduce the receiver RF gain. Key the transmitter. The transmitted note should sound clean, with no chirp or clicks. Check the heat dissipation of Q6; if it is too hot to touch, it may not be heat-sinked properly. No stability problems were noted in my units; however, a check-up on a spectrum analyzer would help determine if any excessive spurious signals exist. I performed the tune-up as described here without the use of a spectrum analyzer, but if you have access to one, use it!

No hint of thermal runaway has been noted, and the transmitter sustained no damage with high SWR loads.

On the Air

Operation is simple. Use a Transmatch and a resonant antenna. I recommend that you use a 12-V regulated power supply capable of delivering 2.5 A. In my receiver, provision is made for off-the-air monitoring. During receive, key the VFO to spot your operating frequency. External TR switching should remove the voltage from J1-E during receive. While transmitting, monitor your off-the-air signal instead of using a sidetone. No hint of thermal runaway has been noted, and the transmitter sustained no damage with high SWR loads. With the values of C1 given, frequency coverage is about 100 kHz on 80 m, 60 kHz on 40 m, and all of 30 m.

Summary

The on-the-air performance of these little rigs is quite satisfactory. Using a folded dipole on 30 meters, TK5, IV3, G, F, FG and North America have been worked. Results on 80 m (using a random-length wire antenna) are good from Southeast to Midwest states and Canada. I have been too busy (and having fun) building these rigs to get on 40 m, so it is up to you to find out how one of these MOuSeFET transmitters will perform on that band! Though they're small, they pack quite a bite!

Acknowledgments

I offer my sincere thanks to Herb Englemann, W2VIE, and Mike Kucks, KA2ZAM, of KDI Electronics for use of lab facilities; the use of the KDI Electronics facilities was invaluable to the design effort. My thanks also to my wife, Dawn, for her encouragement during this project.

Notes

[1] A & A Engineering, 2521 W LaPalma Ave, Unit K Anaheim, CA 92801, tel 714-952-2114.

[2] K2AW's "Silicon Alley," 175 Friends La, Westbury, NY 11590.

[3] Amidon Associates, 12033 Otsego St, North Hollywood, CA 91607, tel 213-760-4429.

[4] Radiokit, PO Box 411, Greenville, NH 03048, tel 603-878-1033.

For updated supplier addresses, see ARRL Parts Supplier List in Chapter 2.

From May 1979 QST, p 16:

Transmitter Design — Emphasis on Anatomy

Part 1: Which is best — duplication of a published circuit or an understanding of how the circuit works? This builders course provides some "hows" and "whys" for a 10- to 15-watt, 40- and 20-meter cw transmitter.

By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250
Luther, MI 49656

A heap of burned-out transistors, some unsavory language and a hastily scrawled sign which read, "Help Stamp Out Transistors," greeted me as I walked into a friend's workshop recently. Fred stood there with a deeply furrowed brow and pointed to a wretched-looking, pc-board assembly which had been worked and reworked until it looked like no hope remained for it. Fred is one of those fellows who loves to build amateur gear, but never took the time to change his thinking from vacuum tubes to semiconductors. He could duplicate the circuits in amateur magazines, but couldn't make them "play" when something went amiss. After some casual conversation and a hot cup of coffee, Fred calmed down and we began troubleshooting his problem child. The major faults were instability in the PA stage and low output from the driver. An hour later we had his transmitter percolating nicely, and Fred poked his thumbs proudly into his chest and proclaimed, "Ain't it a beaut?"

It occurred to me as I sensed my friend's anguish that a better understanding of how a solid-state circuit functions would have saved him countless hours and a considerable amount of grace in the eyes of The Almighty. The foul language and extra money spent for transistor replacements could easily have been avoided. My adventures with Fred helped to inspire this course in transmitter anatomy. Knowing why a particular circuit was chosen by the designer, and how it is supposed to function in the composite assembly, should help you avoid the "Freddie syndrome."

Understanding Our Circuit

The circuit for our workshop project was based on numerous requests for a transmitter that would serve as a mate for "The Mini-Miser's Dream Receiver" which appeared in *QST* for September, 1976. A power output in the 10- to 15-watt bracket seemed suitable for most of the QRP applications one might encounter, and ample power would be available for driving an amplifier later on should the builder be motivated toward QRO.

Fig. 1 shows the block diagram of the transmitter. Let's run through it and see what each section does. Starting at the left we find a 7-MHz VFO. It operates straight through on 40 meters. The arrows show that S1A/S1B routes the rf energy directly to the broadband amplifier module during 7-MHz operation. For use on 20 meters, the VFO output is switched to a push-push doubler by means of S1. Output at 14 MHz is applied to the broadband amplifier when the switch is set for



Two versions of the 7- and 14-MHz cw transmitter are shown here. At the left is the W1FB prototype. On the right is a model built by WA0UZO. Both units are small and lightweight.



Fig. 1 — Block diagram of the two-band, solid-state transmitter. The arrow heads indicate the direction of signal or dc voltage flow. Coaxial cable (miniature) should be used between the various modules when completing signal paths. S1 is a five-pole, two-position, wafer switch with phenolic insulation. S2 is a dpdt miniature toggle switch. S3 and S4 are spst miniature toggle switches.

20-meter operation. You will notice that an offset line goes to the VFO. When S2A is in the OPERATE position and the key (J1) is open, relay contacts at K1B place +12 V on the VFO-offset line. This voltage turns on a switching diode in the VFO. The diode switches some additional capacitance into the VFO tuned circuit and moves the operating frequency outside the amateur band. This prevents an unwanted beat note in the receiver tuning range during the receive priod. When the transmitter is keyed the offset voltage is disconnected by means of K1B, and the VFO provides output on the desired operating frequency. It is necessary to disable the offset circuit for spotting (zero beating), so S2A is placed in the SPOT position for that function. Operating voltage must be applied to the push-push doubler during 20-meter spoting, and S2B is used for that purpose. Activating the doubler assures a loud beat note when zero beating another 20-meter signal.

As the signal moves to the right in Fig. 1 it reaches the broadband amplifier. This circuit was chosen because it requires no tuned circuits. Elimination of tuned, narrow-band circuits at the output of each of the three amplifiers in the module makes it possible to avoid complicated band-switching circuits. The broadband amplifier delivers approximately 1 watt of output and requires only 10 mW of rf energy from the VFO or doubler to develop its rated output power. Actually, the broadband amplifier is useful from 1.8 to 30 MHz, even though this transmitter covers only two bands. The amplifier is biased for Class A (linear) operation so that it can be driven easily by the VFO. The linearity is not a necessary feature for cw use, however, but would be ideal if this were an ssb exciter.

To the right of the broadband amplifier is a PA stage. It is driven to a power output of 10 to 15 watts by the 1-watt signal from the previous module. A Motorola MRF449A transistor is used in the PA. It is capable of 30 watts of output, and has a rated gain (typical) of 13 dB at 30 MHz. Our purpose in restricting the output to 15 watts is to minimize the overall current drain of the transmitter to 3 amperes or less. This will assure longer battery life during portable operation, and will simplify the requirements of an ac-operated dc supply (regulated). The actual amount of rf output power will depend upon the characteristics of the last stage in the broadband amplifier and the PA transistor. This results from the slight nonuniformity in transistor manufacture: Some have more gain than others. It is for this reason that an output figure of 10 to 15 watts is given.

At the far upper right of the block diagram are two filters — one for each band. They are selected by means of S1D/S1E. Since the PA is also a broadband amplifier there will be a substantial amount of harmonic current in the output. To keep the unwanted energy suppressed by 40 dB or greater it is necessary to use FL1 and FL2. The filters are low-pass types (T networks). They are pretuned, so no external peaking controls are needed.

Output from the filters is routed through an SWR-sensor circuit (lower right of drawing). A panel meter, M1, serves as a visual indicator for trimming an antenna or adjusting a Transmatch for a low SWR. The latter is essential if proper operation of the PA stage is to be realized. Relay contacts at K1C transfer the antenna from the transmitter to the receiver during standby periods.

At the lower left of Fig. 1 we have a break-in delay module. It has a variable time constant which controls the drop-out time of the changeover relay, K1A. The amount of delay time can be determined by adjustment of a potentiometer on the circuit board. Closure of the key charges the timing capacitor, which in turn actuates a bipolar-transistor dc switch. The switch closes K1A and applies operating voltage to the broadband amplifier. S3



EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS; k = 1000, M = 1 000 000

* MOUNT FROM L1 TO CHASSIS GROUND

** MOUNT ON INSIDE OF CHASSIS ON FEEDTHROUGH CAPACITOR

*** MOUNT FROM CIRCUIT BOARD TO FEEDTHROUGH CAPACITOR

P = POLYSTYRENE S.M. = SILVER MICA

Fig. 2 — Schematic diagram of the VFO. Fixed-value capacitors are disk or chip ceramic unless otherwise indicated. Resistors can be 1/4- or 1/2-W composition. (See June, 1976, *ham radio* for the author's detailed explanation of this VFO circuit.)

C1 — 100 pF, miniature, air variable.
C2 — 50 pF, polystyrene.
C3 — 10 pF, silver mica.
C4 — 27 pF, polystyrene.
D1, D2 — High-speed silicon diode, 1N914 or equiv.
D3 — 9.1-V, 400-mW or greater Zener diode; 1N5293 or equiv.
L1 — Slug-tuned inductor with 6-μH nominal inductance (Miller 42A686CBI in W1FB unit, Miller 23A475RPC in WA0UZO model).
L2 — Slug-tuned, pc-board mount inductor, 3.2-μH nominal inductance (Miller 23A476RPC or 25 turns no. 32 enam. wire close wound on Miller 27A014-6 form).
Q1, Q2 — Vhf JFET, MPF102, 2N5486, 2N4416 or HEP802.
Q3 — 2N2222A or HEP-S3001.
RFC1-4 — Miniature rf choke (Millen J301 or equiv.).

locks the break-in delay circuit into the key-down mode for tune-up purposes. An LED indicator illuminates during transmit periods, and a second LED indicates when the circuit is in the standby (receive) mode. At that time the transfer relay routes 12 volts to the receiver via J3. This control voltage can be used for muting and unmuting the receiver.

Understanding the VFO

The VFO of Fig. 2 has a familiar face, as it has been used in a number of my circuits.[1] It has been such a faithful and predictable performer that it was chosen again. The circuit at Q1 is a Colpitts oscillator, but some of you may prefer to call it a series-tuned Clapp if you date back to the tube era when that type of circuit emerged as one of the more stable varieties of VFO.

Three capacitors (C2, C3 and C4) are used in series with L1 to ground. This method permits a larger amount of inductance to be used at L1 than would be possible in a more commmon, parallel-tuned, VFO tank. The higher inductance is less subject to changes in value from heating than would be the case if high C and low L were used. Three capacitors are used below the coil rather than one so that the circulating rf current will be divided among them. This lowers the heating in any one capacitor and improves stability.

C5 and C6 are feedback capacitors that take part of the oscillator output (source terminal) and route it back to the input (gate). This feedback is what causes the FET to oscillate. RFC2 is used to keep the feedback energy at the source of Q1 while providing a dc return to ground for the FET. Stated simply, it's an isolating choke for the rf.

Another purpose is served by C5 and C6: They add a considerable amount of shunt capacitance from the FET base to ground. This helps to disguise the small changes in FET junction capacitance during operation — a significant contribution to oscillator stability. D2 gets into this act, also. It conducts on the positive swing of the oscillator rf voltage, and that limits the change in FET junction capacitance. (Maximum capacitance change occurs near the peak of the positive half of the sine wave.) In addition to helping stabilize the oscillator, D2 reduces the harmonic output of Q1. This is because nonlinear changes in junction capacitance encourage the generation of harmonic currents. It is necessary to use a high-speed, rf type of diode for this purpose, such as a 1N914 switching kind.

C7, D1 and RFC1 are used in the VFO-offset circuit. When the +12 volts are applied to D1, as discussed earlier, C7 is placed in parallel with the main tuning capacitor, C1. This moves the VFO operating frequency lower so that the signal won't be heard in the receiver during standby. R_5 is used to prevent damage to the diode; it limits the current through the diode junction when the offset voltage is applied through it and RFC1.

The 0.01-μF capacitor and 100-ohm resistor at the drain of Q1 are used to place the drain at ac ground (bypass) and to isolate Q1 from the other transistors in the VFO module. This is called a decoupling network, and it helps prevent unwanted self-oscillation in the remaining VFO-chain stages. Q2 has a similar decoupling network in the drain circuit.

A buffer stage (Q2) is shown in Fig. 2. It functions as an isolation circuit between the oscillator and Q3. It is used as a source follower — the output being taken from the source element of the FET. Because the gate of an FET has a very high impedance (megohms), the transistor does not load the output of Q1. The gate coupling capacitor is small in value (39 pF), and that also reduces the loading effects on Q1. The lighter the loading, the less chance there will be for oscillator "pulling" (chirps) when the transmitter is keyed. Because Q2 is a source follower it will not provide a voltage gain. Actually, a slight loss will occur at Q2. Typically, a voltage gain of 0.9 will be realized when using this type of buffer stage. This means that we lose 10 percent of the rf voltage that is applied to the gate of Q2.

RFC3 is used as a broadly resonant (low-Q) tuned circuit that peaks at 7 MHz with the approximate 5 pF of stray circuit

[1] Notes appear at end of article.

capacitance. Zener diode D3 is used to obtain a 9.1-volt regulated supply for Q1 and Q2. This prevents changes in oscillator frequency when the 12-volt power supply output changes. Regulated voltage is supplied to Q2 so that it maintains relatively constant operating characteristics: Voltage shifts at Q2 could cause slight changes in internal capacitance and resistance, and those variations could cause some pulling of the oscillator.

VFO Output Stage

It will be necessary to have ample drive to the broadband amplifier strip of Fig. 1. VFO buffer Q2 could not provide sufficient excitation to operate the remainder of the transmitter. Therefore, we have added Q3 to build up the VFO output power. This amplifier stage operates in Class A and uses a high-frequency, bipolar transistor — a 2N2222A. A 10-ohm resistor is placed near the collector terminal to discourage vhf parasitic oscillations. At 7 MHz the resistor offers minor resistance to the signal, but at vhf it looks like a high impedance; this prevents parasitics.

A pi network is used as the output tank for Q3. It is a low-pass type of network, which means it will attenuate harmonic energy. A 3300-ohm resistor is used in parallel with L2 to broaden the response. This will assure relatively constant VFO output to provide an even drive across all of the 40- and 20-meter cw bands.

The output capacitance for the pi network is obtained by utilizing the capacitance of the feedthrough terminal (C3) and the 470-pF shunt capacitor. The collector tank is designed to transform the 500-ohm output impedance at Q3 to 50 ohms at the pi-network output. Even though the input impedance of the first stage of the broadband amplifier is on the order of 500 ohms, this mismatch is desirable. The lower the VFO output impedance, the less chance there will be for pulling effects caused by the later stages in a transmitter. The base-bias voltage for Q3 is taken from the 9.1-volt regulated line to further reduce the chance for pulling at Q1.

Assembling the VFO

Double-sided pc board material is used as a shield box for the VFO. Fig. 3 shows the pc-board pattern and includes a parts-placement guide. Ready-made pc boards or parts kits for the entire transmitter are available from a supplier.[2]

The components should be assembled on the etched circuit board before the side walls are soldered together around the VFO board. A pencil type of soldering iron with a fine tip is recommended for this and all other modules of the transmitter. Excessive heat will damage some of the components, and can cause the pc-board pads to come loose from the base material. Therefore, a 25- or 30-watt iron is the largest size that should be employed.



Fig. 3 — Scale layout of the VFO circuit board showing parts placement from the component side of the board.

Alignment

VFO testing can be accomplished by shunting the output to ground with a 560-ohm, 1/2-watt resistor and applying +12 volts where indicated on Fig. 2. Attach a two-foot piece of hookup wire to the output and place the loose end near the antenna terminal of a receiver. Next, set C1 so that the plates are fully meshed. With the receiver adjusted to receive 7.0 MHz, move the slug in L1 until the VFO signal is heard. At this point you can adjust L2 for maximum output at 7.1 MHz. The S meter on the receiver will be helpful when tweaking L2.

The offset circuit can be tested by connecting +12 volts to the offset line. The VFO signal can be expected to shift lower in frequency, as stated earlier. There should be no evidence of chirp when keying the 12-volt supply to the VFO.



A look into the VFO compartment of the WA0UZO model. Coil L1 is mounted on a side wall of the VFO box. Feedthrough capacitors are used as terminals for leads entering and leaving the VFO compartment.

Footnotes

[1] DeMaw, "QRP Shakedown, Caymanian Style!" *QST*, March, 1975.

[2] Negatives, pc boards or complete parts kits for this project can be obtained from Bob Shriner, WA0UZO, Box 969, Pueblo, CO 81002.

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.

From June 1978 QST, p 25:

Transmitter Design— Emphasis on Anatomy

Part 2: A VFO by itself doesn't offer much when it comes to transmitting, so let's proceed with the physical structure of our two-band transmitter. Here is some useful information on the frequency doubler and cw break-in delay circuits.

Perchance you're wondering why our VFO described earlier couldn't be made to operate on 14 MHz as well as on 7 MHz. Well, there's no reason why the L and C components couldn't be modified to provide two-band coverage. In such an example a band switch would be included in the VFO module for the purpose of selecting the 7- or 14-MHz coils and capacitors. The disadvantages of that scheme are at least twofold. Mechanical instability is likely to result from the switch contacts and related leads. Also, the effects of oscillator pulling are more pronounced as the operating frequency is increased. Concerning the latter, it would be a difficult task to prevent chirp during 20-meter cw work if the VFO were operated at 14 MHz.

A more suitable technique at the higher operating frequencies is to employ the oscillator at one or more octaves below the desired excitation frequency, and utilize multiplication to obtain the required output frequency of the VFO chain. Through this process the mechanical instability is diminished greatly, and the frequency-multiplier stage or stages tend to isolate the oscillator from the load more effectively than would be the case with a straight-through buffer or amplifier.

Fig. 4 contains the circuit we will use for multiplication. Rather than follow the VFO chain with a single-ended frequency doubler (one transistor), we have elected to use what has long been known as a *push-push doubler.* Although the bases of the transistors are connected in push-pull by means of broadband transformer T1, the collectors are tied in parallel. In this manner the stage differs from a *push-pull* amplifier, as the latter would have the collectors as well as the bases in push-pull. A push-push amplifier favors *even* harmonics, whereas a push-pull amplifier does its best job with *odd* harmonics. Furthermore, a push-push doubler is practically as efficient as a straight-through amplifier. A single-ended doubler would exhibit a typical maximum efficiency of only 50 percent as opposed to a push-push doubler with a ball-park efficiency of 70 percent. There is no reason why a pair of JFETs couldn't be used at Q4 and Q5 of Fig. 4. If they were, however, the doubler output for this transmitter would be somewhat lower (inadequate) than with the 2N2222As we have employed.

Circuit Description

The VFO in Fig. 2 (Part 1, May *QST*) has a single-ended output terminal, so if we are to supply drive to the doubler of Fig. 4 it will be necessary to use a balun-

Interior views of the W1FB (left) and WA0UZO (right) versions of the transmitter. The push-push doubler/break-in delay module is at the far right in this photograph. The VFO and SWR-sensor modules are at the center of the WA0UZO unit, and the broadband amplifier may be seen at the left of his VFO. The PA stage is mounted on the rear wall (lower right) of each rig. The homemade heat sinks are visible on the back aprons of the enclosures.



type transformer (T1). The energy reaching the bases of Q4 and Q5 must be of opposite phase to assure push-pull drive to the doubler. To accomplish this we have included T1, a trifilar-wound broadband transformer (three wires wound on the core at the same time). The black dots on the schematic diagram, at the top of T1, identify the phase relationship of the windings. It can be seen that one transistor base is fed 180 degrees out of phase with the other, thereby satisfying our need for push-pull drive. Forward bias is supplied to the doubler stage through the junction (C and F) of the two right-hand windings. A 0.01-μF bypass capacitor brings that point in the circuit to rf ground.

For proper operation of a frequency multiplier it is necessary to establish Class C operating conditions. The forward bias on Q4 and Q5 implies Class AB operation, but the output from the main VFO chain overrides the forward bias and drives the doubler into the Class C mode. Bias is applied only to make the doubler easier to drive.

In the interest of optimum doubler performance it is necessary to establish dynamic balance. Most discrete transistors of a given type number exhibit different electrical characteristics. In our application we are concerned mainly with any difference in transistor gain which might exist. Ideally, Q4 and Q5 should perform in an identical manner. A balancing control, R1 in Fig. 4, has been included to enable us to match the operating traits of the two devices. A 47-ohm resistor is used on each side of the control to prevent the emitters from going directly to ground if the control arm is set at either end of its range. R1 is adjusted so that the output waveform (14 MHz) is as pure as possible. If R1 is set incorrectly there will be a substantial amount of the 7-MHz driving energy present at the collectors of Q4 and Q5. The worse the imbalance, the greater the level of the 7-MHz energy.

A tuned circuit (C8 and L3) is used at the doubler output to increase the available rf output voltage. A pure waveform would be attainable if only the 1000-ohm shunting resistor was used, but the doubler output would be quite low because of the dc voltage drop across the resistor. L3 permits the full supply voltage (less the drop across the 33-ohm decoupling resistor) to reach the collectors of Q4 and Q5. Also, the 1000-ohm resistor broadens the tuned-circuit response to provide a nearly constant output level across the VFO tuning range. Fig. 5 provides the pc-board pattern and parts placement guide for the doubler and break-in delay circuits.

Fig. 4 — Schematic diagram of the push-push doubler. Fixed-value capacitors are disk ceramic. Resistors are 1/2-W composition, except for R1 (see below).

C8 — 110-pF mica compression trimmer (Elmenco 406 suitable).

L3 — Toroidal inductor; 17 turns no. 26 enam. wire on a T50-2 powdered-iron toroid core.

R1 — Pc-board-mount carbon control.

T1 — 17 trifilar turns of no. 26 enam. wire on an FT-50-61 ferrite toroid core. Twist wires approximately eight twists per inch before winding on core.



Fig. 5 — Scale layout and parts placement for the doubler/break-in delay board. View is from the component side of the board; 1/8 indicates a 1/8-inch hole.



The Final Touches

Checkout for the doubler is an easy assignment. The VFO module is connected to points A and B of T1. A 56-ohm resistor is attached temporarily between the doubler output (to the right of the 27-pF output coupling capacitor) and ground. The 56-ohm resistor simulates the load presented by the broadband amplifier (to be described later).

A short length of hookup wire is attached to the junction of the 56-ohm resistor and the 27-pF capacitor. The opposite end of the wire is placed near the antenna terminal of a receiver which is tuned to 7 MHz. Next, operating voltage is applied to the VFO chain and doubler. R1 and C8 can now be adjusted by setting them for *minimum* signal response at 7 MHz, as noted on the receiver S meter. If an oscilloscope is available, connect the scope probe to the top of the 56-ohm load resistor and adjust R1 and C8 for the purest waveform obtainable at 14 MHz. There may be some interaction between the adjustments of R1 and C8, so the foregoing steps should be repeated two or three times to ensure premium doubler operation.

A low value of coupling capacitor (27 pF) is used to prevent the approximate 50-ohm input impedance of the broadband amplifier strip from loading C8 and L3 excessively. During 40-meter operation the push-push doubler is bypassed so that the VFO output goes directly to the broadband-amplifier module.

Break-In Delay Circuit

A cw break-in delay circuit is not an essential part of a transmitter, but it does provide an operating convenience which


TO Q11 BASE
PNP SWITCH
RELAY DRIVER
QRP
S3
TUNE
D1
1000
+12V
Q7
Q6
D4
12k
2200
KEY
MOUNT ON KEY JACK
0.1
0.01
560
+ C9 47µF 16V
D7
K1A
D5
D6
R2
DELAY
10k
+12V
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k=1000, M=1000 000.

Fig. 6 -- Schematic diagram of the break-in delay circuit. Disk-ceramic capacitors are used except for C9; it is electrolytic. Fixed-value resistors are 1/2-W composition. D4-D7 inclusive, are 1N914 silicon diodes. K1 is a dpdt 12-volt dc relay. A Potter & Brumfield 24-V dc relay (surplus) was used in the W1FB version of the transmitter. The spring was stretched to lessen the tension, enabling the relay to close satisfactorily at voltages as low as 11. The relay number is KHP17D12. A 12-volt version is available. Q6 is a 2N3906 or HEP715. Q7 is a 2N1711 or HEP736. R2 is a pc-board-mount carbon control.

makes it worth including. Manual switching could be used in place of the delay circuit to control the changeover relay, K1. Similarly, keying could be done by breaking the 12-volt supply to the keyed stages of the transmitter. The main advantage in utilizing a break-in delay system is that the operator has one less switch to manipulate between the transmit and receive modes. In some instances this permits faster mode changing than would be possible if mechanical switching was used.

Fig. 6 shows the break-in delay circuit. A straight key, bug or electronic keyer is connected to the input of Q6. When the circuit is completed, Q6 is effectively biased into conduction. At that time 12 volts appear at the Q6 collector to place a charge in C9. R2 is set for the desired discharge time of C9. The greater the resistance, the longer the period before C9 bleeds to ground. D4 is used in the collector lead of Q6 to serve as a one-way path for the dc voltage — a gate of sorts. This component was added after two transistors were destroyed at Q6 by a voltage peak which originated (after Q6) as the key was closed. D4 permits the +12 volts to flow into the charging network, but prevents positive-voltage transients from flowing back toward Q6.

When C9 is charged sufficiently to provide the forward bias necessary to turn on Q7, current flows through the field winding of K1, causing the relay contacts to close. As the voltage across C9 decays (key open), a point will be reached at which Q7 has insufficent forward bias to provide the collector current needed to keep K1 energized. At that time the relay will open. D7 is placed across the relay field coil to clip voltage spikes caused by the inductive "kick" when the relay field collapses. The spike, if great enough in amplitude, can travel along the 12-volt bus and damage transistors elsewhere in the transmitter. Damage could occur to Q7 as well.

The diodes in the emitter return of Q7 are used to establish approximately 1.4 volts of fixed-value bias for Q7. Depending on the transistor used as the relay driver, the resting current of Q7 may be high enough to keep K1 closed even though C9 has been nearly discharged. D5 and D6 prevent such an event from happening. The LED indicator used in parallel with the key was added by WA0UZO in his model of the transmitter, but it is not essential to the operation of the circuit. It illuminates when the key is closed, thus functioning as a *transmit* indicator (a frill).

The break-in delay module can be tested by merely applying operating voltage and shorting from the key terminal to ground. If all is as it should be, K1 will close. R2 can be set for the delay time desired. If wiring errors have been avoided, and if no defective components were used, the "Freddie syndrome" should have remained dormant so far!

From July 1978 QST, p 23:

Transmitter Design — Emphasis on Anatomy

Part 3: Broadband power amplifiers eliminate the need for complicated band-switching circuits. Some amateurs believe that they are mysterious and hard to build. 'Tain't so!

It's unlikely that Freddie would have been able to design the broadband amplifier we are describing here, but he certainly should have enjoyed success in duplicating it and making it perform correctly. However, had something malfunctioned in his assembled module his chances of locating the anomaly would have been enhanced greatly by an understanding of how a broadband amplifier functions. Let's consider the subject of how one of these critters does its particular "thing."

A broadband amplifier is intended to do precisely the job its name implies — amplify signal energy over a broad slice of the frequency spectrum. In meeting this requirement the amplifier should provide reasonably uniform output power across the band of frequencies it is designed to accommodate. Thus, if the circuit was designed to cover from, say, 3.5 to 14 MHz, and deliver 5 watts of output, there should be 5 watts of output available (no more and no less) at any discrete frequency within that range. In practice it is difficult to obtain that kind of precision, but a variation in power no greater than ±10 percent can be realized in a carefully designed amateur circuit.

Solid-state amplifiers tend to supply increasing amounts of output power as the operating frequency is decreased. That is, a given transistor will exhibit more gain at 1.8 MHz than it will at 7 or 14 MHz. Therefore, in order to obtain a relatively flat frequency response from a solid-state, broadband amplifier it is necessary to use certain compensating elements to "taper" the overall gain downward toward the lower end of the amplifier operating range. The inclusion of feedback networks is the most common approach to this design criterion. The mathematical solutions to feedback design problems are beyond the scope of this article, but in-depth data on the subject are given in the ARRL book, *Solid State Design for the Radio Amateur.*

The required feedback for a broadband amplifier is usually introduced by means of R and C components between the collector and base of the transistor (negative feedback), and through the inclusion of degenerative feedback in the emitter circuit. Concerning the latter, the emitter bias resistor is bypassed for rf at the higher end of the amplifier frequency range (low-value capacitor), but is bypassed less effectively as the operating frequency is lowered. At the lowest end of the amplifier range the emitter may function as if no bypass capacitor was there at all. In ordinary language we are saying that the less effective the bypassing the lower will be the stage gain. This kind of frequency-response shaping can be further enhanced by selecting specific values of coupling capacitance between amplifier stages. That is, a low value of capacitance will be less effective as a coupling device at the low-frequency end of the range than it will at the high-frequency end of the range.

The feedback resistors and capacitors used between the collector and base of a broadband amplifier are chosen with the same design philosophy in mind. In this case the lower the operating frequency the greater the feedback voltage through a given value of base-to-collector resistor: The greater the feedback, the lower the stage gain. In cases where the feedback resistor is so low in value that excessive foward bias would reach the transistor base, a blocking capacitor is added in series with the resistor and forward bias is obtained by means of a separate resistive divider.

Broadband transformers are also used



Closeup view of the broadbard linear amplifier.


AMPLIFIER
AMPLIFIER
DRIVER
2700
2700
INPUT (10mW)
0.66
0.01
3
9
12
2.5
Q8
Q9
0.01
1500
47
180
470
04
10
220
T2 *
270
47
0.01
*** C10 100
0.1
RFC5
0.3
0.7
Q10 **
12
10
D8
0.26
1.8
1.8
0.1
4.7µF 6V
470 1W
RFC6
SWITCH Q11
D9
2200
0.01
0.1
TO KEY AND S3
T3
2.6 ACROSS 5 OHMS
Zo = 5 OHMS (1.4W)
RFC7
0.01
0.1
22µF 16V
+12V
0.1
22µF 16V
* MOUNT ON ETCHED FOIL SIDE
** HEAT SINK
*** SELECT FOR DESIRED GAIN
□ = RMS
○ = DC
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k = 1000, M = 1000 000.

Fig. 7 — Schematic diagram of the broadband linear amplifier. Capacitors are disk ceramic except those with polarity marked, which are electrolytic or tantalum. Resistors are 1/2-W composition unless otherwise noted.

C10 — See text.
D8, D9 — 1-A, 50-PRV silicon (1N4003 suitable).
Q8 — 2N2222A or equivalent.
Q9 — 2N3866 or HEP S3008.
Q10 — 2N2270 or HEP S3001.
Q11 — 2N4037 or HEP S3012.
RFC5-RFC7, incl. — 18 turns of no. 28 enam. wire on FT-37-43 ferrite toroid core.
T2 — Primary has 30 turns of no. 28 enam. wire on a FT-50-43 ferrite toroid core. Secondary has 4 turns of no. 28 enam. wire wound over cold end of primary winding.
T3 — Primary has 16 turns of no. 28 enamel wire looped through a BLN-43-302 ferrite core. Secondary has four turns of no. 28 enam. wire looped through the same core. Primary leads come out of end of core opposite the secondary leads.

in the type of amplifier under discussion. They are designed to operate as untuned rf transformers with a turns ratio chosen to match the output of the amplifier stage to its load (collector of one stage to the base of a succeeding stage, for example). A deliberate mismatch is sometimes introduced by the designer to achieve amplifier stability. Another approach is to shunt one or both of the transformer windings with a resistor. This tends to lower the transformer Q, which in turn discourages self-oscillation. The trade-off is in reduced stage gain.


1/8
1/8
1/8
1/8
KEY
D9
RFC 6
.1
D8
4.7 MF
.1
RFC 5
.1
47
.01
IN
OUT
E
C
10
B
2.2K
Q11
+12
22 MF
.1
T3 SEC
T3 PRI
470
220
2.7K
180
2.7K
.01
C
B
Q10
E
T2 SEC
T2 PRI
C
B
.01
E
Q9
C
B
Q8
1.5K
E
1.8
1.8
10
470
47
270
RFC 7
.01
.1
22 MF
1/8
100 PF
BROADBAND AMP

Fig. 8 — Parts placement guide for the amplifier pc board. The shaded area represents an X-ray view of the etched foil pattern; this view is from the component side of the board. board is used for this module. The foil on the component side is used as a solid groundplane, having only clearance holes for the mounting of the components. The commercially made board shown in the photo also has component identification information etched on this side of the board. All mounting holes on pc board marked with a "1/8" should be drilled through with a 1/8-inch drill bit. The board can then be mounted to the chassis with 6-32 machine screws, spacers and nuts.

Examination of Our Circuit

The broadband amplifier used in our transmitter is shown in Fig. 7. It was inspired by a similar circuit in the Atlas 210X transceiver. With approximately 10 mW of driving power at the input to Q8, the amplifier output at Q10 will be roughly 1.4 watts at 7 and 14 MHz. The input impedance of the composite amplifier is close to 50 ohms.

Feedback is provided at Q8 and Q9 by means of the 2700-ohm resistors connected between the collector and base of each stage. Degenerative feedback for Q8 is obtained by leaving part of the emitter-bias resistance unbypassed (47-ohm resistor). No bypassing is used across the 10-ohm emitter resistor of Q9. The parallel 1.8-ohm resistors in the emitter return of Q10 serve two purposes: They are unbypassed to provide degenerative feedback, and they help to protect the transistor from drawing excessive current (thermal runaway).

T2 is a broadband toroidal-wound transformer. It is loaded on the primary by a 220-ohm resistor. A 10-ohm resistor is in parallel with the secondary winding. These resistors were added to reduce the drive to Q10, and to cure a low-level oscillation which occurred during the checkout period. T3 is also a broadband coupling transformer. It is wound on a ferrite core of the balun type. In the breadboard model of this amplifier an RCA 40082 transistor was used at Q10. Owing to its gain and f_T characteristics, it was somewhat more "lively" than the 2N2270 of Fig. 7. To obtain equal performance it was necessary to bridge the primary of T3 with a 150-ohm resistor. This ensured stability.

All three amplifiers are biased for linear operation (Class AB). This has no special value in a cw or fm transmitter, as Class C amplifiers are adequate for those modes. The primary advantage in using a linear amplifier in our transmitter is to lower the driving-power requirements (the transistors require less excitation voltage) and to lessen the occasion for harmonic generation in the stages (Class C amplifiers are richer in harmonic currents). The forward bias applied to Q10 is developed across D8, which regulates the bias by virtue of its barrier voltage (0.7 volt for a silicon diode). A 470-ohm dropping resistor is used between D8 and the 12-volt supply line to prevent the diode from consuming excessive current.

Decoupling networks are used in the 12-volt line between stages. This aids in preventing feedback (positive) from one stage to another. An excessive amount of feedback will cause self-oscillation of one or more of the stages. At Q8 a 47-ohm resistor and 0.01-µF capacitor comprise the decoupling circuit. RFC5, RFC6 and the two 0.1-µF bypass capacitors are used for this purpose at Q9. RFC7 and the related bypass capacitors are employed at Q10 to decouple the stage from the 12-volt line. High, medium and low values of capacitance are used at Q9 and Q10 to assure adequate decoupling at lf, hf and vhf. (The stages could self-oscillate at any of those frequencies.) Who needs or wants to be haunted by the "Freddie syndrome?"

A pnp bipolar switch (Q11) is shown in Fig. 7. It operates in the same manner as Q6 of Fig. 6. When the key is closed, Q11 conducts and permits +12 volts to reach Q9 and the bias network for Q10. A one-second oscillation occurred in the breadboard version of the transmitter, caused by the decoupling capacitors at Q9 and Q10. This formed a timing circuit which was triggered by a self-oscillation at Q11. The decoupling capacitors at Q9 and Q10 acted as a tuned-collector/tuned-emitter circuit for Q11. The oscillation caused the break-in-delay circuit to cycle at a one-second rate. This resulted in a repetitive cycling of the relay, K1. Insertion of D9 at Q11 cured the problem by providing a one-way gate in the feedback path. A crown type of heat sink is needed at Q10 to prevent damage to the transistor.

Amplifier Testing

Following completion of the assembly procedures given in Fig 8, amplifier testing can be done. Tests can be performed first by connecting the VFO directly to the input of Q8 of Fig. 7 (40 meters). A 5-ohm, 2-watt load resistor should be attached across the secondary of T3. Apply operating voltage and short the keying line to ground. A VTVM and an rf probe can be used to compare the circuit voltages with those of Fig. 7. Approximately 2.6 volts rms will appear across the 5-ohm load resistor if the circuit is working correctly. If the overall amplifier gain is too low, increase the value of C10 experimentally. Although 100 pF was right for the circuits built by W1FB and WA0UZO, variations in transistor gain may require that less feedback be used at Q8. These tests can now be repeated at 20 meters, using the push-push doubler between the VFO and broadband amplifier.



Fig. 9 — Diagram of the half-wave harmonic filter discussed in the text. For 7-MHz use, L_a is 1.1 µH (15 turns no. 25 enam. wire on a T50-2 toroid core). C_a is 470 pF and C_b is 910 pF. For 20-meter operation L_a is 0.55 µH (10 turns no. 26 enam. wire on a T50-2 toroid core). C_a is 240 pF and C_b is 470 pF.

This much of the transmitter can be put on the air if the builder likes true QRP work, but it should *not* be connected to an antenna unless a harmonic filter is placed in the output line from T3. Furthermore, the turns ratio for T3 will need to be changed to provide a match to a 50-ohm filter and antenna. The secondary winding of T3 will require 15 turns rather than four turns if this is done. Fig. 9 gives the details for half-wave filters which can be used at 7 and 14 MHz, respectively.

From August 1978 QST, p 16:

Transmitter Design — Emphasis on Anatomy

Part 4: The final touches are applied to our transmitter by adding a 15-watt amplifier and an SWR indicator. If all goes well, we will become immune to the "Freddie syndrome"!

It is unlikely that the 1.5 watts of output from our broadband amplifier (Fig. 7) would lead to the acquisition of five-band DXCC. But a few more decibels might make such an endeavor a reasonable assignment: The amplifier described in this section will help, as the cw signal should be increased some 10 dB in strength!

The final-amplifier stage is shown in Fig. 10. A 220-ohm feedback resistor is used between the base and collector of Q12. An 1800-pF blocking capacitor has been included to prevent the collector dc voltage from being shorted to ground via T3 of Fig. 7.

This amplifier has an input impedance of approximately 5 ohms at 7 and 14 MHz. The 10-ohm base resistor is used as a preventive measure against instability, but only if needed. To remove some vhf harmonics which appeared at the collector of Q12, it was necessary to include the 330-pF bypass capacitor. At 7 and 14 MHz the capacitor has negligible effect on circuit performance.

As was the case with the stages in our broadband amplifier, decoupling of the 12-volt bus is necessary at Q12. This is accomplished by means of RFC9 and the related bypass capacitors. Once again, bypassing is done for lf, hf and vhf.

Since the amplifier is to operate in the Class C mode, no forward bias is used at the base of Q12. For all practical purposes, Q12 draws no current during key-up conditions. When drive is applied (key closed) the transistor is driven into the cutoff region to establish Class C operation.

The collector load impedance of Q12 is determined in the usual manner, where $Zo = Vcc^2/2Po$. Thus, for a 12-volt collector supply and a power output of 15 watts, we obtain a collector load of 4.8 ohms. T4 is a broadband transformer which is made from six toroid cores (see inset drawing of Fig. 10). It must transform the collector impedance to 50 ohms so that a suitable match and power transfer to the T-network filters can be obtained. A 3:1 turns ratio will suffice despite the slight mismatch (9:1 impedance ratio).

In order to prevent excessive harmonic energy from reaching the antenna it is necessary to include a filter at the output of Q12. FL1 and FL2 are used for this purpose. Each is a T type of low-pass network. Energy above the operating frequency is attenuated by the filters, but energy below the filter cutoff frequency passes without impairment. A spectral analysis of this transmitter indicated that all spurious output energy was at least 40 dB below peak power at the fundamental frequency. Additional attenuation could be realized by cascading two such filters at the PA output. The characteristic impedance of the filters in Fig. 10 is 50 ohms.



Fig 10 — Circuit for the 10- to 15-watt Class C power amplifier. Capacitors are disk or chip ceramic unless otherwise noted. Capacitors with polarity marked are electrolytic or tantalum.

L4 — 9 turns no. 18 enam. wire on a T68-6 toroid core.
L5 — 10 turns no. 18 enam. wire on a T68-6 toroid core.
L6 — 12 turns no. 18 enam. wire on a T68-2 toroid core.
L7 — 13 turns no. 18 enam. wire on a T68-2 toroid core.
Q12 — Motorola MRF449A stud-mount transistor.
RFC8, RFC9 — 8 turns no. 18 enam. wire on an FT-50-43 ferrite toroid core.
T4 — Two rows of three each FT-50-43 toroid cores. Join with epoxy cement as shown in the inset drawing. Primary has one turn of no. 18 wire (U shaped). Secondary uses 3 turns of no. 18 enam. or insulated hookup wire. Primary leads exit from core at end opposite to secondary leads.



Fig. 11 — Parts placement guide for the PA pc board. Parts are mounted on the pattern side of the board; the shaded area in this view represents the copper pattern on the component side, and the other side of the board is unetched copper groundplane. Decimal-value numbers alone represent capacitance in microfarads. Whole-number values with no units represent resistance in ohms.



Fig. 12 — Circuit for the SWR sensor (see text). Fixed-value capacitors are disk ceramic. Fixed-value resistors are 1/2-W composition.
C11, C12 — 5-pF air variable, pc-board mount.
D10, D11 — 1N270 or 1N34A diode.
M1 — Small microampere meter. A 50-, 100- or 200-μA type will be satisfactory.
R3 — 10-kΩ, linear-taper, carbon control, panel mount.
RFC10 — Miniature 1-mH rf choke.
T5 — 50 turns no. 26 enam. wire on T50-2 toroid core. Primary has 2 turns of no. 26 enam. wire over center of secondary winding.

There are no special precautions to follow when assembling the amplifier, other than keeping the component leads as short as possible. Double-sided pc board should be used to minimize the chance for ground loops (feedback): They could cause amplifier instability.

The strip leads of Q12 should not be stressed when they are soldered in place. Allow a *slight* amount of slack for expansion when the transistor is heated during operation. Also, use care when tightening the transistor mounting nut. It should be drawn up just a "smidge" beyond the finger-tight point. A coating of silicone grease (heat-sink compound) should be placed on the transistor stud and metal face near the base of the stud. This will improve the transfer of heat between the heat sink and Q12. The heat sink is a homemade unit which has been bent into a U shape. It is made from a piece of 1/16-inch (1.6-mm) thick aluminum plate, 2-1/2 × 3 inches (64 × 76 mm) in size. Each lip is 1/2 inch (12.7 mm) high. The heat sink is affixed to the rear wall of the transmitter cabinet, and silicone grease is applied to the joining surfaces. The stud of Q12 and two no. 4-40 screws hold the heat sink firmly in place. This mounting method also holds the PA module in place on the inner surface of the rear wall of the cabinet. The pc-board layout is shown in Fig. 11.

SWR Indicator

As a convenience gadget we have included the SWR bridge shown in Fig. 12. It not only enables the operator to adjust the antennas for a low SWR when using a Transmatch, but serves as a relative-power-output indicator when switched to the forward mode. A blow-by-blow circuit description will not be given here, as this design was treated earlier in *QST* ("A QRP Man's RF Power Meter," June, 1973).

Assembly Notes — Composite Transmitter

Double-sided pc-board material is used for the cabinet of the WA0UZO version of the transmitter. Aluminum sheeting was bent into a U shape to form the W1FB prototype. The latter (HWD) is 3-1/4 × 5-3/4 × 6 inches (83 × 146 × 152 mm). The cover is a U-shaped piece of perforated aluminum. Two metal L brackets are affixed on the lower surface of the main chassis to permit the box cover to be secured by means of no. 6 sheet-metal screws. The WA0UZO model of the transmitter is slightly larger than the W1FB version. He allowed room for mounting the modules horizontally. The vertical-mounting format makes it possible to realize greater miniaturization.

Our VFO is contained in a separate compartment. The enclosure is made from pc-board stock with the walls joined by means of solder. A U-shaped aluminum top cover is placed on the VFO assembly to prevent unwanted rf energy, moisture and dirt from entering. The



Rear view of the W1FB version of the transmitter. The heat sink is at the far right. The phone jacks and key jack are grouped at the left.



Fig. 13 — Parts placement guide for the SWR sensor. K = the cathode end of a diode. Fractional markings such as "1/8" signify mounting holes to be drilled with that size bit.

cover is press-fitted over the box walls. In the author's unit the SWR-sensor module is bolted to the VFO top cover.

By this time you should have a pretty good "handle" on how the collection of subassemblies are connected together. The block diagram of Fig. 1 provides the essential information. All of the signal leads should be made of shielded cable if they are more than two inches (51 mm) in length. RG-174/U subminiature coaxial cable is excellent for the purpose.

The main-tuning dial is a vernier mechanism (Calectro or Philmore). A large knob can be used as a substitute for the one which comes with the dial, as the original is a bit small for those who have large fingers. A Kurz-Kasch aluminum knob was used on the prototype model after its depth was reduced on a lathe (courtesy of W1SL).

The front and rear panels of the W1FB unit were sprayed a dark green color. Green Dymo tape labels were used to identify the controls: A reasonably professional appearance results from using labels which are the same color as the panel. Finally, four adhesive-backed plastic feet were affixed to the bottom of the cabinet.

Closing Remarks

The toroid cores used in this project are available from Amidon Associates, G. R. Whitehouse and Palomar Engineers (check *QST* ads). It is suggested that the builder ask these suppliers for their catalogs, as some of the other components for the transmitter may be found in their product lines. It would also be prudent to scan the flea markets for parts.

The power supply for this transmitter should deliver 12 to 13 volts dc (regulated) at 3 amperes. Needless to say, a 12-volt car battery is suitable. A dry-battery pack is not recommended: The life span would be extremely short.

Motorola has included internal protection for their MRF449A transistor (Q12), so damage should not occur during short periods of operation when a mismatch greater than, say, 2:1 exists. This circuit has been tested into a dead short and a full-open load condition (key down) for periods of 30 seconds, and no damage to the PA stage resulted.

This two-band transmitter should provide many years of reliable operation. It is hoped that some useful information was passed along to those who aren't heavily immersed in solid-state design theory. If nothing more, let's hope we have negated the "Freddie syndrome" effectively.

Circuit-board etching patterns for the 7- and 14-MHz cw transmitter (DeMaw, "Transmitter Design—Emphasis on Anatomy," in four parts). Black represents copper. All patterns are shown at actual size from the foil side of the circuit board. See the drawings referenced below for parts-layout information. At A, the VFO circuit board (Fig 3, Part 1). At B, the doubler/break-in delay board (Fig 5, Part 2). At C, the broadband amplifier board (Fig 8, Part 3). At D, the SWR sensor (Fig 13, Part 4).



(A)

(B)

(C)

(D)

Circuit-board etching patterns for the 7- and 14-MHz cw transmitter (continued). Shown here is the power-amplifier circuit board, which appears in Fig 11, Part 4 of the series. This circuit board is double sided, the component-side foil being used only as a groundplane. That pattern is not shown, as it contains only clearance holes for the component leads.



From February 1986 QST*, p 23:*

Four Watts, QSK, for 24.9 MHz

Here's your chance to try the 24.9-MHz WARC band at minimum cost. This transmitter is a fine mate for the 24.9-MHz converter described in April 1985 *QST.*

By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250, Luther, MI 49656

What might we expect from the new 24.9-MHz band? Well, it has similar propagation characteristics to the 10-meter band. It also exhibits some of the traits of the 15-meter band. Unfortunately, it is affected by sun-spot activity in a like manner to the other two bands above and below 24 MHz. Therefore, we are in a period of propagation ebb, owing to diminished sunspots.

Low power and reasonable antennas will do the job on 24.9 MHz as effectively as on 28 MHz. That is, it is not difficult to enjoy worldwide communications with less than 10 watts. With this thought in mind, plus an affinity toward being miserly when building a new rig, I designed the transmitter described here. You may build a duplicate model from scratch, or you have the option of purchasing a complete kit from a vendor.[1]

Circuit Details

The transmitter of Fig 1 features full-break-in operation (QSK). Operation requires only a key or keyer, antenna, a 12- to 14-V, 800-mA (or greater) regulated power supply (or car battery) and you, the operator. There is a terminal to which the receiver antenna line connects (terminal C of Fig 1).

Although crystal control is specified, a VFO can be substituted for Y1. Q1 is operated as a third-overtone oscillator. T1 and T2 are shielded transformers with tuned primary windings. They are arranged to provide an impedance transformation between the collectors and bases of the related transistors. This helps to ensure maximum RF-power transfer. The tuned transformers reject most of the unwanted harmonic energy before it reaches the driver and PA stages. You may substitute toroidal transformers and trimmer capacitors at T1 and T2 if you so desire.

Q3 serves as a broadband, class-A linear amplifier. It is the driver for the MRF475 power amplifier, Q4, which operates class C for maximum efficiency. A 7-section low-pass filter (FL1) is used as the output network to attenuate harmonic energy. The constants for FL1 were taken from *The ARRL Handbook* (see filter tables in the transmitting chapter). The power output from this transmitter is 4 watts into a 50-ohm load with an operating voltage of 12, and key-down current of 800 mA.

TR Switching

Q5 and Q6 of Fig 1 provide dc switching that enables the circuit to be classified as QSK. Q5 is a PNP keying switch that operates Q1 and Q2 for CW use. When the key is closed, Q5 triggers NPN transistor Q6 into the ON state, thereby shorting the receiver-antenna line (C) to ground during the transmit period. This prevents damage to the front end of the receiver or converter used with the transmitter. A similar technique was used by Wes Hayward (W7ZOI) to provide QSK operation: He used two reverse-connected 1N914 diodes as the shorting element during transmit. The measured RMS RF voltage on the receive-antenna line (key down) is approximately 0.4 with a 50-ohm termination. If diodes are used instead of Q6, the RMS voltage will be on the order of 0.7, key down.

C14 and L4 have a reactance of roughly 400 ohms. They serve as a series-tuned circuit to minimize loss of signal to the receiver during the receive period. FL1 serves as a filter ahead of the receiver, since the station antenna is attached to the output of FL1. Some insertion loss is present, but attenuation of the received signals is not significant.

S1 can be added to allow zero beating. It removes operating voltage from Q3, which helps lessen receiver overloading when you want to spot your transmitter signal. D2 is used as a dc gate to prevent the +12 V from reaching Q5, Q6 and the accessory terminal (I). The diode allows current to flow from Q5 to Q1 and Q2 (key down), but blocks the flow of current when S1 is set for the SPOT function.

S2 can be added for tune-up or Transmatch adjustments. If your key or keyer has a HOLD function, you may eliminate S2.

Key-down dc voltages have been noted at various points in the circuit of Fig 1. These have been added to aid in troubleshooting. The measurements were made with a Simpson 260 VOM. A 1-mH

---

[1] Notes appear at end of article.


OVERTONE OSC
AMP
24.9 MHz
T1
T2
R4
10
110
SM
C2
R23
4.7 k
0.75
Q1
2N2222A
24.9 MHz
Y1
R1
56 k
R2
15 k
R3
390
C1
33
C4
0.1
6
2
27
C3
1
R7
1 k
R6
5.6 k
10
R9
10
C8
Q2
2N2222A
R8
100
C5
0.1
C6
0.1
C7
0.001
R10
56
R11
10
R12
1 k
R13
4.7 k
0.1
C9
270
C10
+12 V (KEYED)
(2)
SPOT
OPR
S1A
S1B
+12 V
(B)
8 V
400 mW
D1
SM – SILVER MICA
* – CROWN SINK
** – TO-220 SINK
V – DC VOLTAGE, KEY DOWN
R5
180
1/2 W
D2
DC GATE
C
Q4
B C E
Q1–Q3
Q5,Q6
C
B
E
BOTTOM VIEW
S2
TUNE
KEYING SW
+12 V (KEYED)
KEY
(0)
R22
4.7 k
11
2N4036
Q5
C23
0.1
C22
0.1
R21
10 k
C24
0.1
+12-V ACCESSORY LINE
(1)
+12 V
(3)
C21
0.1
+ C20
100 µF
25 V
PA
MRF 475/2SC2092
Q4
**
T4
PRI
SEC
18
C14
R17
47
C13
100
C16
0.1
C25
0.001
RFC1
R18
10 k
TR SW
0.5
2N2222
Q6
3.9 k
R20
R19
10 k
C19
0.1
+12 V (KEYED)
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k = 1000, M = 1000 000.

Fig 1—Schematic diagram of the 24.9-MHz transmitter. Capacitors are disc ceramic unless otherwise noted. Polarized capacitors are tantalum or electrolytic types. Resistors are ¼- or ½-W carbon composition units. Numbers inside circles indicate key-down dc voltages. Numbered components not appearing below are identified numerically for PC-board layout purposes only.

D1—8-V, 400-mW Zener diode.
D2—50 PRV, 1 A.
L1, L3—0.266-µH inductor. Use 8 turns of no 24 enam wire on an Amidon Assoc T50-6 toroid core.
L2—0.5-µH inductor. Use 13 turns of no 24 enam wire on a T50-6 toroid core.
L4—L4 and C14 have reactances of 400 ohms. L4 is a 2.27-µH inductor. Use 24 turns of 26 enam wire on T50-6 toroid core.
RFC1—Use 6 turns of no 22 enam wire on an Amidon Assoc FT-37-43 ferrite toroid (μ = 900).
T1, T2—Primary inductance is 0.38 µH. Use 6 turns of no 26 enam wire on bobbin of Amidon Assoc L57-6 shielded transformer unit. Secondary has 4 turns of same wire.
T3—Broadband transformer. Primary contains 10 turns of no 24 enam wire on an FT-50-43 ferrite toroid. Use 2 turns of same wire for secondary. Spread secondary over all of primary.
T4—Broadband transformer. Primary has 7 turns of no 24 enam wire on stacked (two) FT-50-43 ferrite toroid cores. Use 10 turns of same wire for secondary.
Y1—Overtone crystal, 30-pF load capacitance, HC-6/U holder. International Crystal Mfg Co type GP, and plastic PC-board mount holder. Choose frequency for favored portion of the band. Do not attempt 12-m operation with a 12.450-MHz fundamental crystal. Substantial fundamental energy will appear in the transmitter output if Q1 is used as an oscillator/doubler.

RF choke was used between the positive lead of the VOM and the test point measured. This prevents unwanted RF energy from reaching the instrument and causing false readings. These voltages may vary slightly in accordance with the beta of the transistors used in your circuit. The RMS output voltage measured from (A) to ground across 50 ohms was 14. This indicates about 4 W of output power: Operating voltage was 12. My RMS measurements were made with a Hewlett-


DRIVER
(1)
Q3
2N3866
*
R15
1 k
T3
0.5
PRI
SEC
R14
5.6
C11
0.1
C12
0.1
R16
10
1/2 W
+12 V
FL1 (f_{co} = 26 MHz)
L1
L2
L3
C15
150
5 M
C16
150
5 M
ANT
50 Ω
(A)
L4
C17
0.1
RCVR
ANT
(C)

Packard VTVM and RF probe that is rated to 900 MHz. However, an ordinary VTVM and homemade RF probe (see *The ARRL Handbook*) will work equally well.

Regulated voltage is ensured for Q1 by the addition of Zener diode D1; it sets the voltage level at +8. The lower oscillator-operating voltage helps to ensure frequency stability of Y1 by limiting the crystal current.

Parasitic suppression is aided by using R4, R9, C10 and C13. These components act as low reactances at VHF, but have little effect on circuit operation at 24.9 MHz.

Checkout and Operation

Our first assignment after completing the assembly is to give the PC board (non-component side) a thorough visual inspection to make certain we have no unsoldered joints or unwanted circuit bridges between unrelated PC-board foils. A magnifying glass is ideal for this step in the checkout. Make certain that all transistors are mounted correctly on the circuit board. Fig 2 indicates the placement of the transistor case tabs when the transistors are viewed from their tops.

Connect your power supply to the rig. Attach a 50-ohm load to (A). Place S1 in the SPOT position and switch S2 to OFF. Tune your receiver to the transmitter frequency. If a signal is heard, adjust T1 and T2 for maximum S-meter deflection. The transformer tuning will be broad, so don't be alarmed if the change in meter reading is small.

Place S1 in the OPR position and close S2 (TUNE). Measure the power output by means of an RF power meter, VTVM and RF probe, or oscilloscope with a 30-MHz or greater bandwidth.

If all systems are "go," key the transmitter and listen to the note in your receiver: The keying should be chirpless. If chirp is heard, adjust T1 for minimum chirp. Should this not resolve the problem, experiment with the value of feedback capacitor C1 until a clean CW note is heard. I tried three available crystals at Y1, and in all instances a good CW note resulted.

I purposely made the CW shaping a bit "hard." I have found this useful when operating at QRP levels. The shaping may be "softened" by changing the value of C23 (Fig 1). Start with a value of 1 μF. This will round off the trailing edge of the wave form. Increasing the capacitance of C24 will also affect the shaping.

Summary Remarks

The Motorola MRF475 may be difficult to locate. Other transistors of the same general specifications may be used at Q4. A 2SC2092 works well as a direct substitute and is available by mail.[2]

A scale template for the double-sided PC board is provided in Fig 3; parts placement is indicated in Fig 2.

There is no reason why this general circuit can't be modified for other amateur bands in the HF spectrum. All that needs to be changed are C1, the collector tuned circuits of Q1 and Q2, the constants of FL1 (see *The ARRL Handbook*), C14 and L4. Of course, Y1 must be chosen for the desired operating frequency.

VFO design data are contained in *The ARRL Handbook* and the ARRL book, *Solid State Design for the Radio Amateur* (out of print). I suggest that the VFO be operated at half frequency (12.45 MHz) to reduce the potential of chirp when the transmitter is keyed. A doubler stage (preferably a push-push doubler) should be used to raise the VFO output frequency to


KEY (D)
+ 12 V (3)
TO RCVR ANT (C)
W = JUMPER
CIRCUIT BOARD SPECIALISTS
TO S1A (2)
ACCESS (1)
S1B (B)
C20
R21
R22
C21
R20
R19
C19
Q5
Q6
E
B
C
C17
L4
C14
L1
W
C23
C22
C24
D2
RFC 1
R18
C15
C25
L2
T4
C16
D1
R5
R10
C11
R14
R13
C18
Y1
R2
R3
C1
C4
C5
C6
C7
R8
R6
R12
C12
R16
C13
Q4
L3
ANT (A)
Q1
Q2
Q3
T1
T2
T3
C3
C9
R7
R9
R4
R1
C2
C8
R11
C10
R15
R17

Fig 2—Parts-placement guide for the 24-MHz transmitter PC board, as viewed from the component side of the board. R23 is mounted below the board on the appropriate solder pads.



Fig 3—Scale template of the transmitter PC board as viewed from the etched side. Board is double sided, with the foil on the component serving as a ground plane. Connect etched ground foils to ground plane conductor at several points by means of component pigtails that pass through the board. Solder pigtails on both sides of the PC board.

the 24-MHz band. VFO output should be approximately 2- to 3-V RMS across a 500-ohm load.

Even during mediocre propagation conditions I have found 24 MHz to be an interesting band. During 1984, I made numerous tests on the band with others while using an experimental license (KM2XQV) granted by the FCC. Many more QSOs were made under my amateur call after the 12-m band became available to us on June 21, 1985. Certainly, under skip conditions you should have a lot of fun with this little 4-watter! I hope to meet you on the new band.

Notes

[1] Chuck Hood, Circuit Board Specialists, PO Box 969, Pueblo, CO 81002, tel 303-542-5083. PC boards or complete kits available.

[2] Deleted.

For updated supplier addresses, see ARRL Parts Supplier List in Chapter 2.

From February 1988 QST, p 30:

Some QRP-Transmitter Design Tips

Full QSK is beneficial during QRP CW work. It is easy to achieve without relays at low power levels.

By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250
Luther, MI 49656

DEAR SIGNAL: BE LOUD BUT CLEAN!
QRP RIG

You may discover that full break-in (QSK) is an advantage for your QRP operating. It provides an opportunity to listen to your operating frequency during key-up periods. This lets you know if QRM is present, or if the other station is transmitting because the operator thought you stood by. (There may be times when your signals fade to such low levels that the person with whom you are communicating thinks you're standing by.) QSK can save wasted words in this situation. Full break-in is also beneficial during QRP Field Day operation. It saves time and can lead to a higher score.

This article is directed at those of you who like to build simple rigs. There is no practical project included, but the circuit in Fig 1 is a practical one. I built and tested the transmitter for the purpose of optimizing the performance, and to ensure that each stage operates as stated in this presentation.

Circuit Features

I will discuss the highlights of the Fig 1 circuit so you can understand how they work. This should help you design QRP transmitters on your own. Understanding the circuit functions is also useful when troubleshooting is necessary.

Refer to Fig 1. A VXO (variable crystal oscillator) is used at Q1 to generate the signal. Unlike most VXOs, this one takes the form of the familiar Pierce oscillator. I find this circuit more suitable for my needs than is the more common Colpitts VXO. The advantages are that no tuned output circuit is required to develop adequate excitation for the subsequent RF stage. Also, C2 (frequency control) will swing the crystal frequency *above and below* the marked value. Most Colpitts VXOs do not allow the crystal to be "rubbered" above the marked frequency. My tests were made with an AT-cut plated crystal in an HC-6 holder (International Crystal Mfg Co no. 433113) with a marked frequency of 7050 kHz. The load capacitance of Y1 is 30 pF. C2 of Fig 1 permits the crystal frequency to be moved from 7045 to 7052 kHz. Greater inductance at RFC1 will allow a wider frequency shift, but at the cost of frequency stability. The 7-kHz swing yields crystal controlled stability, even during wide excursions of ambient temperature. This is important when operating QRP during Field Day or on camping trips; vast temperature changes may occur from day to night. The negative feature of the Fig 1 VXO is that C2 must be insulated from ground. In other words, both the rotor and stator must be above ground. The tuning capacitor can be mounted on a plastic bracket to achieve isolation.

R5 and R13 of Fig 1 are used to lower the Q of RFC1 and RFC2. Too great a Q causes crud to appear at the leading edge of the keyed waveform (spurs). The resistors cure this problem. C1 is a feedback capacitor. The value is chosen to provide chirpless keying and high output from Q1. You may need to experiment with the C1 value. The crystal activity and the gain of your particular Q1 transistor will dictate the optimum value for C1.

RF Power Amplifier

I like to experiment with transistors that are not intended to be used for RF applications. The Motorola MPS-U02 is an example, a device that was designed for audio and switching use. It is frequently used as one half of a complementary symmetry audio amplifier (paired with an MPS-U52). The f_T (upper frequency limit) is 150 MHz, and it can handle up to 800 mA of continuous collector current. The specifications strongly suggest RF power use! The maximum V_{ceo} (collector to emitter voltage, base open) is +40. This allows plenty of leeway for the collector voltage to swing beyond 12 volts in RF or audio service. Typically, the RF collector voltage (sine wave) will rise to twice the power supply value, or 24 volts for a 12-V dc supply during CW operation.

The cost for MPS-U02s is quite low—another advantage. I bought 10 of them as surplus for 39 cents each. They are listed as new devices (88 cents each) in the Circuit Specialists catalog.[1] Numerous other high f_T audio/switching transistors are suitable for RF power amplifier use as well. Pick a device that has an f_T of five or more times the operating frequency. This will ensure ample gain at the desired frequency.

I used simple capacitive coupling between Q1 and Q2. C4 is selected to provide 1.5 watts of output from Q2. In my circuit I needed 33 pF of capacitance. Larger values will increase the transmitter power, but at the risk of exceeding the safe ratings of Q2. The light coupling provided by C4 minimizes oscillator loading. Too great a value at C4 can kill the oscillation of Q1. I chose the 1.5-W output power to cause the Q2 collector impedance to be 48 Ω. This is determined from $Z = V_{cc}^2/2P_O$, where V_{cc} is the collector to emitter dc voltage, and P_O is the power output. This enabled me to use a 50-Ω filter (FL1) without a broadband matching transformer between Q2 and FL1. A heat sink is required on the tab of Q2 to minimize the transistor junction temperature. A 1-inch

---

[1] Circuit Specialists, PO Box 3047, Scottsdale, AZ 85257. Phone 1-800-528-1417 when ordering. Catalog available.

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.


VXO
7 MHz
C2
100
TUNING
Y1
RFC 1
22 µH
R13
3.9 k
2N2222
2N4400
Q1
C1 270
R1
5.6 k
R2
22 k
R3
180
C3
0.01
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000
PA
MPS-U02
C4
33
R6
22
Q2
RFC 2
390 µH
R5
1.5 k
RFC 3
22 µH
C6
0.1
C5
0.1
R4
47
D1
R7
3.9 k
C7 50
C9
0.1
RFC 4
C8
0.1
FL1
7 MHz
L1
1.3 µH
L2
1.3 µH
C10
220
C11
620
C12
300
ANT
50 Ω
P_o = 1.5 W
Δf (C2) = 7 kHz
OPR
S1B
SPOT
L3
10 µH
TO RX
ANT JACK
D2
D3
1N914
TR SWITCH
C13
0.01
Q4
R8
10 k
2N2222
2N4400
Q1, Q3, Q4
C
E
B
Q2
(FRONT)
OPR
S1A
SPOT
KEY TO GND
R12
4.7 k
KEYING SWITCH
Q3
+12 V (XMIT)
R10
4.7 k
C15
0.01
R9
10 k
C14
0.1
1 µF
16 V
C17
C16
0.1
R11
1.1 k
2N4036
2N4403
+12 V
(200 mA)
C18
22 µF
16 V

Fig 1—Schematic diagram of the test transmitter. Fixed-value capacitors are disc ceramic unless otherwise noted. Polarized capacitors are tantalum or electrolytic. Resistors are ½-W carbon composition.

C2—100-pF miniature air variable or 10-100 pF compression trimmer with shaft.
C10, C11, C12—Polystyrene or silver mica.
D1—Rectifier diode, 50 PRV, 1 A.
D2, D3—Small-signal switching diode, 1N914 or equiv.
L1, L2—1.3-µH inductor. Use 18 turns of no. 26 enam wire on an Amidon Assoc T-37-2 toroid.
L3—10-µH inductor. Use 45 turns of no. 28 enam wire on an Amidon Assoc T-50-2 toroid.
RFC1, RFC2, RFC3—Miniature ferrite core RF choke.
RFC4—12 turns of no. 26 enam wire on an Amidon Assoc FT-37-43 ferrite toroid (850 µ).
S1—DPDT toggle or slide switch.
Y1—Fundamental crystal (see text).

square piece of no. 16 gauge aluminum or copper was suitable for my test circuit. A 10-minute key-down period at 1.5 W output caused the transistor and heat sink to be moderately warm to the touch.

Harmonic Filter

The FCC purity of emissions requirement is more liberal at power outputs under 5 W. A five-section low-pass filter (FL1 of Fig 1) is ample to comply with regulations. A seven-element filter would offer greater attenuation of the 2nd and 3rd harmonics, should that be your desire. My filter constants were obtained from the normalized filter tables in the transmitting chapter of *The ARRL Handbook*. I chose an f_{co} (cutoff frequency) of 8 MHz. The ripple factor is 0.01 for FL1. The ripple indicates the relative flatness (lack of amplitude dips and peaks) of the peak portion of the filter response curve.

If FL1 were terminated at each end with a 50-Ω nonreactive (purely resistive) load, C10 and C12 would have the same value. However, we must recognize the transistor output capacitance (20 pF for an MPS-U02), stray circuit capacitance (roughly 10 pF) and the value of the TR sampling capacitor, C7. During key-down periods, C7 is switched in parallel with C10 via D2, D3 and Q4. The approximate total of these capacitances is 80 pF. This value must be deducted from 300 pF (normal C10 and C12 value) if the filter is to perform properly. A 220-pF capacitor is, therefore, appropriate for C10. Additional harmonic reduction results from operating Q2 in the class-A linear mode. D1 provides approximately 0.7 V of forward bias for Q2. The class-A mode reduces the excitation requirement for Q2, which is also a benefit. A similar RF amplifier, operated in class C, would require significantly more RF drive, and the harmonic output would be somewhat higher in amplitude.

TR Circuit

You will note in Fig 1 that a TR (transmit-receive) circuit is included. Q3 is a PNP dc switch that applies operating voltage to Q1 when the key is closed. Key closure shorts the base of Q3 to ground, and this causes it to conduct. During conduction, +12 V is connected to Q1 through the junction of Q3. The keyed +12 V is routed also to NPN switch Q4. This transistor also conducts when the key is closed. At full saturation the Q4 collector-emitter junction closes and this shorts the receive antenna line to ground through Q4. D2 and D3 also accomplish this function, but leave a residual RF voltage of 0.7 V RMS on the receive line. The shunt-diode technique was popularized by Wes Hayward, W7ZOI, in some of his QRP transmitters that featured full QSK. I use the diodes as backup protection, should Q4 fail to operate for some reason.

TR circuit sampling capacitor C7 should have a reactance no less than 400 Ω. Smaller reactance values will rob transmitter output power when the key is closed. Some power is sacrificed with the value shown for C7, but it is minimal. The trade-off associated with this type of TR circuit is a slight signal loss during receive, owing to the small value for C7. Both Hayward and Lewallen (W7EL) reduced this problem by adding L3 in the receive antenna line. L3 has the same reactance as C7. This permits C7 and L3 to form a series-resonant circuit at the operating frequency, which in turn reduces the loss in the receive signal that is fed to the receiver. A slug-tuned coil (variable inductor) at L3 would help to make the series circuit exactly resonant.

I measured the RF voltage from the receive antenna line to ground with a Tektronix 453A scope during key down. It is 200 mV P-P (70.7 mV RMS) across 50 Ω. This potential will not harm any receiver, solid state or tube type.

Additional TR control is possible if you connect an outboard NPN switch to the keyed +12 V (between Q3 and Q4). The



Fig 2—Examples of keyed RF waveforms. The illustration at A shows hard keying with square waveform corners. This waveform causes clicks on the make and break of the key. An acceptable waveform is shown at B. The corners are rounded to remove clicks and the decay time is lengthened somewhat over that shown at A. Soft keying is shown at C. The decay time has been increased over that at A and B. This waveform is not suitable for high speed keying. See the text for additional data.

outboard transistor switch can then be used for receiver muting, or for actuating a small 12-V relay, which may, in turn, serve as a receiver muting control.

The Keyed Waveform

Many homemade QRP transmitters are deficient in harmonic suppression and keyed wave shaping. I have been lax in the latter regard myself. One tends to justify hard keying as being somewhat more effective at the QRP level, and in a sense this is true. However, under no circumstances should the keyed wave cause clicks. The dividing line between acceptable hard keying and clicky keying is rather thin! It is better to stay on the safe side and attempt to obtain a keyed wave that has a 5 ms rise and fall time, which is considered entirely acceptable. This represents a clickless wave that has a fast enough recovery time to permit very high speed keying. Too long a decay time (key up) will limit the useful keying speed we can apply. Fig 2 shows a hard, clicky wave at A. The drawing at B illustrates a wave with rounded corners that does not cause clicks. Fig 2C shows a soft wave with a long tail. This waveform is unsuitable for fast keying.

The waveform from your transmitter can be examined by sampling the transmitter RF output energy across a 50-Ω load. Rapid keying of the transmitter will cause the RF envelope to be displayed on the scope tube.

Waveform shaping is accomplished in Fig 1 by means of C16, C17, R11 and R12. Bypass capacitors in the keyed circuit (such as C5 and C15) also affect the shaping.

The decay time (trailing edge of the waveform) is affected by C16, C17, R11 and the bypass capacitors mentioned above. R12 affects the attack time (leading edge of the waveform). In fact, you may add additional resistance between R12 and the key jack to shape the leading edge of the waveform. Values up to 10 kΩ are suitable. The larger the resistance of R11, the slower the waveform decay time. The R11 value shown allows the base of Q3 to return quickly to +12 V, thereby cutting off the Q3 conduction (key up) quickly. This fact was brought to my attention by Ed Hare, KA1CV, of the ARRL lab staff. The shaping-network values in Fig 1 ensure a keyed waveform that is clickless, but hard enough to give "presence" to the CW note. The frequency-control values for the VXO in Fig 1 prevent the signal from sounding chirpy when the VXO is keyed by Q3.

Final Comments

I added S1 to facilitate frequency spotting without placing the transmitter on the air. S1A closes the key line to turn on Q3. S1B removes operating voltage from Q2 at the same time. This reduces the signal strength of the beat note heard in my receiver. In other words, it is not so strong that it overwhelms my receiver. S1B also prevents the transmitter signal from reaching the antenna during zero beating or spotting.

You may feel that a VXO is not nearly as desirable as a VFO. I confess that 7 kHz of frequency swing is a small amount, but the VXO is stable under most conditions, and this appeals to me during operation afield. It is not a severe handicap to carry two or three crystals when camping. This provides sufficient frequency coverage of the 40-meter band. In fact, you may wish to include a low-capacitance crystal selector switch if you build a VXO rig of this type. But remember that the more stray capacitance you introduce in the crystal circuit, the smaller will be the frequency swing of a given crystal.

My purpose in writing this article is to pass along some design hints that you may not have considered. The points I have covered are among the most frequently asked questions I receive concerning QRP transmitters. The main point I want to make is that you *can* build your own gear, and it takes little additional time or money to develop a circuit that operates cleanly and reliably.

From November 1986 QST, p 43:

A QRP Transmitter for 30 Meters



Q1
C
B
E
Y1
4.7 k
220
68
10 k
C1
L1
L2
39
Q2*
B
C
E
0.1
L3
J1
50-Ω
ANT.
C3
SM
C4
SM
RFC1
0.1
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000
* HEAT SINK
220
0.1
C
Q3
B
E
4.7 k
1 k
J2
KEY
.01
.01
C2
.01
+12 V

Fig 1—A schematic diagram of the QRP transmitter for 30-meter operation. Fixed-value capacitors are disc ceramic. Inductor cores are available from Amidon Associates or Palomar Engineers.[1,2] The enclosure is from Radio Shack® (RS-270-251), and the circuit board is from Circuit Board Specialists.[3] An etching pattern for this circuit appears on p 11.

Y1—Fundamental-mode crystal for the 30-meter band.
Q1—2N2222A or equiv.
Q2—2N3553 or equiv.
Q3—2N4036 or equiv.
C1—150-pF mica trimmer, ARCO no. 424.
C2—470-μF, 25-V electrolytic or tantalum capacitor.
C3, C4—330-pF silver-mica or polystyrene capacitor.
L1—30 turns, AWG no. 24 enameled wire on a T-50-2 core.
L2—3 turns, AWG no. 24 enameled wire over L1.
L3—13 turns, AWG no. 22 enameled wire on a T-50-2 core.
RFC1—30 turns, AWG no. 28 enameled wire on an FT-37-63 core.
J1—SO-239.
J2—Phone jack or phono jack.

[1] Amidon Associates, 12033 Otsego St, North Hollywood, CA 91607, tel 213-760-4429.

[2] Palomar Engineers, PO Box 455, Escondido, CA 92025, tel 619-747-3343.

[3] Circuit Board Specialists, PO Box 969, Pueblo, CO 81002, tel 303-542-5083.

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.

☐ Fig 1 shows an inexpensive transmitter for the 30-meter band. The combination of excellent propagation characteristics and a relatively low QRM level on this band make solid communication routine at QRP levels. The circuit shown was adapted from a W7ZOI design shown in "Experimenting for the Beginner" by Doug DeMaw, W1FB, in the September 1981 issue of *QST*. The transmitter can be put on 30 meters with relative ease.

The only major changes required were to resonate the oscillator output circuit, and filter the amplifier output on the new frequency. This was done by changing the number of turns in L1 and selecting an appropriate range for C1. A new output filter (C3, C4, L3) was designed using the component values shown in the schematic. In addition, the antenna output jack was changed to an SO-239 (to suit my personal preference), and a ground stud was added to the enclosure (see Fig 2). My circuit is built on a printed circuit board as in the original article. The transistors shown differ from the original design only because they were available in my junk box.

The transmitter performance is excellent, and the keying is clean. Output power is exactly 1 watt when using a 12.8-V dc supply (measured with a VTVM and a 50-Ω resistor). Excellent signal reports have been received from stations in New Brunswick, Florida and from as far west as Kansas.—*Frank Pitman, WD4DDS, 12 E Lakeshore Dr, Rome, GA 30161*



Fig 2—An interior view of the QRP transmitter as converted for 30 meters. The heat sink is on Q2.

From February 1984 QST, p 46:

A Two-Transistor Transmitter for 30 Meters



EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS; k = 1000, M = 1000 000.

Fig. 1 — Schematic diagram of a simple 30-m transmitter built by KB4PY. Resistors are ¼-W, carbon-composition types. Capacitors are disc ceramic, except C1.

C1 — 10- to 80-pF mica trimmer.
FB1 — FB43-101 ferrite bead.
L1 — 13 turns no. 22 enameled wire on a T68-6 toroid core (yellow), 0.8 μH.
L2 — 30 turns no. 28 enameled wire on an FT37-63 toroid core, 15 μH.
RFC1 — 100-μH RF choke, such as Miller part no. 4632.
Y1 — Fundamental-type crystal in FT-243 holder for any frequency in the 10-MHz amateur band.

When I decided to become active on the 30-m band, I wanted to build a simple transmitter. I have a Yaesu FT-101E that receives WWV on 10 MHz. Others may have general-coverage receivers, and need only a transmitter. April 1983 *QST* described an elaborate 30-m rig.[1] But even the transmitter section is more than just a "junk box" project.

After testing a variety of other circuits, I finally came up with the one shown at Fig. 1. The circuit is simple and inexpensive. It uses fundamental-type crystals in FT-243 holders, which are easy to obtain from a variety of sources. The transmitter output is almost 1.5 W, and the harmonics are 34 dB down from the fundamental. With a reasonably stocked junk box the total cost for this transmitter should be under $10.

My antenna system is a 150-ft random wire and a Transmatch.[2] A two-position coax switch is used to change between transmit and receive. I leave my receiver active during transmit, and it provides a nice sidetone. Keying either the positive or negative power-supply leads seemed like the easiest method to me. The keying waveform is a bit soft, but I don't believe the slight chirp is objectionable. Others may wish to experiment with alternate keying methods.

I built my rig on a piece of perf board, and mounted the circuit inside of an aluminum box, as shown in Fig. 2. An etching pattern and parts-placement diagram are shown in Fig. 3. Many of the parts are available from RADIOKIT. Circuit Board Specialists also has a PC board and a complete kit of parts available for this project.

I used an oscilloscope and frequency counter to align the circuit. Alternatively, use a calibrated receiver, and tune C1 for maximum output. I hope others have as much fun with this little rig as I have.—*Paul Hoffman, KB4PY, 4502 Indian Hills Rd, Decatur, AL 35601.*



Fig. 2 — Photo showing the construction technique used by KB4PY on his 30-m QRP transmitter. Note the heat sink used on Q2. If you use point-to-point wiring, as shown, it may be necessary to reduce the value of the 130-pF silver-mica capacitor. The author used a value of 82 pF in his original design.



Fig. 3 — A PC-board etching pattern is given at A. Black represents unetched copper, viewed from the foil side of the board. The pattern is shown actual size. B shows a parts placement diagram. Components are placed on the non-foil side of the board; the shaded area represents an X-ray view of the copper pattern.

---

[1] D. DeMaw, "Putting the '8P6 Special Hamcation Rig' on 10 MHz," *QST*, April 1983, pp. 19-21.

[2] m = ft × 0.3048, mm = in × 25.4

From May, 1979 QST, p 27:

A VMOS FET Transmitter for 10-Meter CW

Vertical metal-oxide semiconductor FETs are new on the amateur scene. Here is a practical construction project that makes use of the Siliconix VN88AF.

By Wes Hayward,* W7ZOI

Although QRP cw operation has been the major passion at W7ZOI for many years, 10 meters is a band that has been bypassed. The reason is not clear, for it's hard to find a better frequency during periods of high sunspot activity. The rig described here is a long-overdue remedy for this neglect.

It was decided to try one of the new vertical metal-oxide semiconductor field-effect transistors[1] as a power amplifier, rather than to use a conventional approach to transmitter design. Experiments with earlier VMOS FETs were encouraging. However, the devices were either expensive or completely unavailable. Today, plastic medium-power devices are readily available for less than \$2.

The transistor chosen was the Siliconix VN88AF. With 80-volt drain-to-gate and drain-to-source breakdown voltages and a peak current capability of 3 amperes, the device appeared ideal. The major limitations are the power dissipation of 15 watts and the presence of a protection Zener diode at the gate. The latter turned out to be a major constraint for cw operation. (We'll have more comments about that later.)

Modern operating practices dictate the need for some degree of frequency agility. A 14-MHz VXO was chosen for frequency control. A clean balanced doubler provides the required 28-MHz signal. Low-level stages with an abundance of stabilizing negative feedback increase the power to drive the VMOS final. All indications are that the system should be eminently reproducible.

Circuit Details

The heart of the transmitter, the rf chain, is shown in Fig. 1. Q1 serves as a crystal Colpitts oscillator with the crystal operating on the inductive side of resonance. The crystal normally used in this circuit has a marked frequency of 14,025 kHz. With the components shown, a 25-kHz range is obtained at 14 MHz. (Some experimentation may be required with the number of turns on L1 to obtain the desired range.) As shown, the circuit tunes from 14,025 down to about 14,001 kHz. If the inductor L1 is shorted, the circuit will tune from the marked crystal frequency upward about 10 kHz.

Not all crystals will function well in this

Side view of the 10-meter VMOS FET transmitter. No attempt was made to miniaturize the unit. The final amplifier, Q5, is visible at the lower left. The crystal is immediately to the left of the variable capacitor. The connector at the upper right is for the receiver.



---

*Technical Advisor, ARRL, 7700 S. W. Danielle Ave., Beaverton, OR 97005

[1] Notes appear at end of article.


EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k = 1000, M = 1000 000.
S.M. = SILVER MICA
+12 T
+25V KEYED
OSC.
Q1 2N3904
BUFFER
Q2 2N3906
14 MHz
FREQ. DOUBLER
D2 1N914
D3 1N914
28 MHz
PREDRIVER
Q3 2N5179
Q4 2N3866 DRIVER
+10 dBm
+26 dBm
POWER AMP
+25 T
Q5 VN88AF
+36 dBm
K1B (SEE FIG 2)
RCVR.
ANT.
● = PHASING
S.M. = SILVER MICA
Y1 14.025 MHz
L1 7.2 µH
C1 400
L2 0.87 µH
T1
L3A 0.43 µH
L3B
L3C
C2 65
C3 65
L4
T2
T3
L5 0.24 µH
L6 1.3 µH
L7 0.24 µH
L8 0.3 µH
C4 400
C5 400
6.2 V 400 mW D1

Fig 1. — Rf chain for the VMOS FET transmitter. All resistors are ½-watt composition and capacitors are disk ceramic unless otherwise specified. Tolerances are ± 10 percent. The + 12 T indicates 12 V during transmit periods only (see Fig 2). The Supertex VN5-A is an equivalent part for the VN88AF (Siliconix) VMOS transistor. Siliconix parts are almost impossible to purchase in small quantities, but Hamilton-Avnet outlets seem to have a limited number of the transistors for single-lot purchases.

C1 — 400-pF air variable, Allied 695-4200 or equiv.
C2, C3 — 65-pF trimmer, Allied 782-0404 or equiv.
C4, C5 — 400-pF trimmer, two Allied 782-3765s in parallel or equiv.
D1 — 6.2-V, 400-mW Zener diode, 1N753A or equiv.
D2, D3 — 1N914 or equiv.
L1 — 7.2 µH, 40 turns no. 24 wire on Amidon T-80-6 core.
L2 — 0.87 µH, 17 turns no. 26 wire on Amidon T-37-6 core.
L3A, L4 — 0.43 µH, 12 turns no. 24 wire on Amidon T-37-6 core.
L3B, L3C — 2-turn links over L3A.
L5, L7 — 0.24 µH, 9 turns no. 24 wire on Amidon T-37-6 core.
L8 — 0.3 µH, 10 turns no. 24 wire on Amidon T-37-6 core.
L6 — Rf choke, approx. 1.3 µH, 17 turns no. 24 wire on Amidon T-44-6 core.
T1 — 7 trifilar turns no. 28 wire on FT-37-43 ferrite core.
T2, T3 — 7 bifilar turns no. 28 wire on FT-37-43 ferrite core.
Y1 — See text.

circuit. They should be fundamental-mode units, the usual case at 14 MHz. The best results are obtained with HC-6/U metal-can units, such as those manufactured by JAN Crystals and by International Crystal (type 031300). The most reliable operation occurs when the metal crystal case is grounded; if it is allowed to "float," the frequency will change when a hand moves near the rock, making a front-panel mounted crystal socket impractical. Tuning is very nonlinear, but this presents no problem in this application. The 50-kHz tuning range (after doubling) has been more than sufficient. While a 400-pF variable capacitor is used, a smaller unit will suffice with only a slight reduction in tuning range. The power available from the oscillator is around one milliwatt (0 dBm).

Q2 functions as a buffer amplifier to increase the 14-MHz power to about + 10 dBm, a near-optimum drive level for the diode doubler. The output of this stage has a low-pass filter to ensure a waveform relatively free of harmonics that would degrade the balance of the multiplier and hence reduce the suppression of 14-MHz energy in the output.

Frequency multiplication is obtained with a pair of silicon diodes, D2 and D3. One might question the use of a passive frequency doubler, but careful experiments using laboratory instrumentation have confirmed the wisdom of this choice. Details of this work are presented in chapter 3 of *Solid State Design for the Radio Amateur*.[3] The method is used in several projects in that book.[3]

The doubler is followed by a single tuned circuit at 28 MHz. A pair of two-turn links on the toroidal inductor couple energy into and out of this resonator. The power available from the doubler, after filtering in the resonator, is about 0 dBm.

The 28-MHz energy is applied to a two-stage, keyed amplifier. Negative feedback is used in both stages to ensure broadband stability and to establish the gain levels desired. The resistor values used were chosen from a program written for the writer's programmable calculator. Additional information on feedback amplifiers is presented in chapter 8 of *Solid State Design*. The saturated output of Q4 is nearly 1/2 watt, more than enough to drive the VMOS final amplifier. Both



Fig. 2 — Control circuit for the VMOS FET transmitter.
K1 — 24-V dc spdt relay, Magnecraft W65RPCX-3 or equiv.
D4 — 9-V, 400-mW Zener diode, 1N757A or equiv.

driver stages were keyed, a requirement resulting from signal feedthrough in feedback amplifiers when they are "off," leading to an objectionable backwave.

A single tuned circuit was placed between Q3 and Q4. This improved the suppression of 14-MHz energy which was detected in the output of Q4 when using a 50-ohm termination and a 15-MHz-bandwidth oscilloscope. (Addition of the tuned circuit removed all traces of 20-meter energy from the oscilloscope presentation.) If the resonator is eliminated, the amplifier chain (Q3 and Q4) has a very wide bandwidth and is suitable for general-purpose application throughout the hf spectrum. A small heat sink is recommended for Q4.

The final amplifier is generally straightforward, with only a few subtleties. A low-pass filter is contained at the input. It serves the role of absorbing the input capacitance of the transistor, in this case about 50 pF, and hence aids broadband performance. The input of the amplifier is terminated in a 47-ohm resistor. While this decreases power gain, it does provide a low impedance at the gate, a definite aid to stability.

All presently available VMOS transistors are enhancement-mode devices. That is, with no positive voltage on the gate with respect to the source, there is no drain current. Only when a threshold gate voltage is reached does drain current begin to flow. This is typically +1.2 volts for the VN88AF. Current flow increases dramatically as the gate potential is increased further.

Many available VMOS FETs have an internal Zener diode connected between the gate and the source. This diode protects the FET from damage by static electricity. Only one Zener diode is used, in contrast to dual-gate MOSFETs, which employ back-to-back Zeners. The VN88AF includes a protection diode. If there were no internal protection diode, it would be possible to attach the gate directly to the 47-ohm resistor with no additional circuitry. But as it is, the negative-going portion of the rf voltage would quickly destroy the protection diode, taking the transistor with it! Hence, external protection circuitry is required to save the amplifier from the ill effects of the internal protection diode. The resistor network and 1N914 diode shown with Q5 serve this function, clamping the gate voltage and never allowing it to go below about 1.2 volts.

With no drive applied, Q5 sits on the verge of conduction. When drive is applied, the series 280-pF capacitor will charge, establishing a small positive dc voltage on the gate. As such, the amplifier operates Class A. The key-down drain efficiency is poor, only about 30 percent. For this reason, a husky heat sink is mandatory for Q5. (During testing, one VN88AF was destroyed from excessive dissipation because of an inadequate heat sink.) Overall efficiency is reasonable during typical cw operation, since forward bias disappears once drive is removed. Measurements have not been performed on this circuit when operated in a linear mode. However, the method might hold promise for ssb applications.

The output of the amplifier uses a double pi network. Following the work of Roy Lewallen,[4] such a network was used in anticipation of obtaining Zener-less devices that can be operated Class C or D. For the Class A operation employed in this design, a series-tuned output network would probably present no problems.

The output power is +36 dBm, or about 4 watts. Slightly over 8 watts of output was obtained when a second VN88AF was paralleled with Q5. No circuit changes were required other than retuning of the output network. Operation was attempted at a drain supply potential of 12 volts, but power output and gain suffered severely.

Some experiments that might be of interest were done on 80 meters. An amplifier much like that used at Q5 was built with a similar bias scheme. This amplifier used four paralleled VN88AFs bolted to a large heat sink. Power outputs up to 25 watts were easily obtained but the efficiency was still poor. A similar 3.5-MHz amplifier was then built using a Siliconix VN84GA. This transistor is a real brute with no internal protection Zener diode. It had an output of over 25 watts with an efficiency of 73 percent. The amplifier was then moved to 14 MHz by resonating the 1000-pF gate capacitance. Similar results were obtained there. Unfortunately, this transistor is both expensive and difficult to obtain. Perhaps that situation will improve with time.[1]

The control circuitry for the transmitter is shown in Fig. 2. A 7812 three-terminal voltage regulator powers the low-level stages as well as a crystal-controlled receiving converter included within the same box. Transistor Q6 operates as a switch to apply voltage to the oscillator and buffer when either the spot or the transmit switch is activated. Q7 is a pnp switch controlled by the key to provide the voltage for Q3 and Q4. A 1-μF nonpolar capacitor from base to collector forces Q7 to act as an integrator during transitions. This shapes the keying nicely.

Transistors Q8, Q9 and Q10 form a semibreak-in circuit. When the key is pressed, the antenna relay is activated. It will remain on for a fraction of a second after the key is released. The transmit switch, S2, overrides the semibreak-in circuit for more casual contacts. If desired, Q8, Q9 and Q10 may be omitted. They were installed in this transmitter a few days before the annual November Sweepstakes contest. The antenna relay used was a surplus item from the junk box. There is nothing critical here.

The simplicity of the control circuitry presents one potential problem: The transmitter is on (and generating rf) at the instant the antenna relay changes to the transmit position. However, the low power and the inherent stability of the Class A final amplifier allow "hot switching" with no problems. Control systems for correcting this situation are described in chapter 7 of *Solid State Design for the Radio Amateur.*

Results

The performance of this transmitter has been as good as expected. Investigation with a Tektronix 7L13 spectrum analyzer *after* construction and alignment (using less exotic home-station test equipment) was encouraging. The 14-MHz component is 57 dB below the 28-MHz carrier. The second harmonic is 64 dB down while the fourth and sixth harmonics are just barely detectable. The backwave is over 75 dB down. The output amplifier has performed flawlessly with no sign of the usual instabilities found with bipolar power amplifiers. The VMOS FET power transistor is certainly here to stay!

On-the-air reports are equally encouraging. Keying and general "cleanliness" are comparable to any of the better signals around. While using an inverted-V dipole only eight meters high, the writer worked 41 states and a considerable amount of DX in the first two months of operation. The DX (in all continents) includes many slightly rare prefixes, ranging from LU and CX to HK0 and EA8. Let's just hope that the sunspots hold for several more years!

Notes

[1] Raab, "MOSFET Power Amplifier," *Ham Radio*, November 1978. Also see references cited in that paper, especially those by Oxner.

[2] Hayward and DeMaw, *Solid State Design for the Radio Amateur*, ARRL, 1977, p. 41.

[3] *Ibid.*, pp. 197, 223.

[4] Lewallen, "On Solid-State PA Matching Networks," *QST*, October 1978, p. 34.

From February 1984 QST, *p 35:*



A Beginner's Look at Basic Oscillators

A frequency generator is the heart of any signal source. Simple crystal or LC oscillators have many uses in amateur circuits. Let's learn how they work and where some common problem areas exist.

By Doug DeMaw,* W1FB

"Don't try to dazzle me with exotic circuits! I want to learn the theory of simple circuits first." Those statements are voiced frequently by radio amateurs. Are you one of those frustrated persons?

Perhaps the blind spot that exists with some writers (and I'm one myself) results from the belief that in order for a ham to have passed the license exam, he or she fully understood the answers to the theory questions. This is not a fact, because (unfortunately) many amateurs memorize the suggested answers to the FCC examinations. This makes it difficult to comprehend even the most basic of discussions about electronics.

Something else is awry for those who don't understand the fundamentals of our radio pastime: They can't experience the joys of building and using homemade gear! The purpose of this Beginner's Bench series is to encourage those of you who are less technically inclined to climb the ladder to a level that will enable you to enjoy the technical section of *QST* more fully, and to do some dabbling in your home workshops.

Perhaps the most common circuit in RF (radio frequency) projects is the oscillator. A single oscillator can serve by itself as a transmitter for CW. It may also be used as a frequency generator to be followed by one or more amplifier stages to provide a high-power transmitter. But, oscillators are used also in receivers, frequency standards, signal generators (test equipment) and many other pieces of apparatus for amateur use.

Perhaps you're saying to yourself, "Why hasn't he mentioned frequency synthesizers?" Well, that's not a topic that can be handled properly in a beginner's discussion. The synthesizer is a very exotic item that involves a host of subjects that are beyond the intent of this series. There's no doubt that synthesizers are becoming the way of life with most manufacturers of commercial amateur equipment. But, for the sake of experimenting with useful, simple circuits, we will focus on crystal and LC (coil and capacitor) oscillators. They are by no means obsolete!

What is an oscillator? In electronics, an oscillator is a device that generates an alternating current (ac). *Oscillation* is a variation in the magnitude of electrical current with time. Typically, the output of an oscillator alternates between positive and negative current values centered on zero current.

Everyone has alternating current available from an electrical wall outlet. Why is an oscillator needed to produce ac? The ac from the wall outlet is alternating at 60 Hz (cycles per second). In radio we need oscillators that will produce a wide variety of other frequencies from the audio range (20 to 20,000 Hz) throughout the radio-frequency range (as high as 300 GHz, or 300 billion cycles per second).

To make an oscillator, we must have two things. One is a frequency-determining element. This element is an energy-storage device with a special ability to build up energy in one direction, discharge it, build it up in the opposite direction, and discharge that. A pendulum is an example of a mechanical oscillator that does just that. Another example of a mechanical oscillator is the tuning fork used as a standard by musicians. Both of these mechanical devices store energy and oscillate at a certain frequency. In an electrical oscillator we generally use a quartz crystal or a tuned circuit consisting of a coil and a capacitor as the energy-storage and frequency-determining device.

The second ingredient of an oscillator is the ability to supply carefully timed pulses to keep it oscillating. Recall that a tuning fork oscillates for only a short while after it is banged against something. Similarly, a pendulum eventually winds down as the effects of gravity and friction win out.

Neither the mechanical nor electrical oscillators are perpetual-motion machines. The mechanical devices can be kept going by giving them a kick every now and then in exact timing needed to replace the power lost to gravity and friction. The same idea applies to electrical oscillators — there must be a pulse of electrical power supplied to the frequency-determining element exactly synchronized to the frequency of oscillation. The amount of power supplied must replace power lost to circuit resistance. This replacement power is called feedback. To obtain the extra power needed for feedback, it is necessary to sample some of the oscillating energy from the frequency-determining element, amplify it, and feed it back to the frequency-determining element so that it *aids* the power build-up. So an electrical oscillator needs an active device (such as a transistor or a vacuum tube) to serve as an amplifier to produce the correct feedback to keep the circuit oscillating.

---

*ARRL Contributing Editor, P.O. Box 250, Luther, MI 49656

Crystal Oscillators

A crystal oscillator circuit can be built with a quartz crystal and an amplifier to provide the needed feedback. When the amount of feedback is sufficient, the quartz element in our crystal holder will vibrate at a specified rate (depending on its thickness and the stray capacitances present in our circuit). The crystal is ground to the proper thickness at the time of manufacture, and the resultant frequency is marked on the crystal case. Therefore, if our crystal was marked "3.700 MHz," it would vibrate 3.7 million times a second to provide the desired oscillator frequency. The thinner the quartz crystal, the higher the operating frequency. This limits the practical upper frequency of a fundamental crystal, for if it were too thin the element would become impossible to fabricate or would shatter easily during oscillation. Generally, 20 MHz is the upper limit for quartz crystals that operate on their fundamental modes.

Although a crystal may be marked for a specific operating frequency, this does not mean it will produce that exact frequency when we plug it into an oscillator. The crystal must be ground or etched in accordance with the circuit capacitances that exist in our oscillator. This is specified by the manufacturer as the "load capacitance," the existing circuit capacitance that "loads" the crystal. Normally, the load capacitance of a standard oscillator circuit is somewhere between 10 and 40 pF, with 20 or 30 pF being the most typical value. Some circuits are very difficult to analyze with regard to the effective load capacitance. For this reason amateurs who need to have the crystal work at a precise frequency must tell the crystal supplier the model number of the equipment in which the crystal will be used. If the circuit is homemade, or if the model number is not known, the supplier should be provided with a copy of the oscillator circuit, with all parts values marked plainly on the diagram. We can take advantage of the effects of load capacitance by introducing changes in capacitance intentionally. This enables us to shift the operating frequency of a crystal. More on this subject later.



EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k=1000

SAME LEGEND APPLIES TO FIGURES 2-6

Fig. 1 — Simple example of a Pierce crystal oscillator.

LC (coil/capacitor) frequency elements in an oscillator must also be supplied feedback energy to cause oscillation. The coil and capacitor do not vibrate as is the case with a crystal element. Instead, the combination stores and discharges energy at a specific rate to establish the frequency of oscillation. The LC oscillator is seldom as frequency-stable as a crystal oscillator. Changes in temperature and mechanical vibrations (unwanted) tend to change the inductance and capacitance elements of the LC oscillator in a more dramatic manner than when a crystal is used. This causes an instant (mechanical) or gradual (electrical) change in the operating frequency. The gradual change is referred to as "drift."

The Pierce Oscillator

One of the simplest types we hams can use is the Pierce oscillator (named after a person, as are most oscillator circuits). Very few parts are required, as shown in Fig. 1. It makes no difference whether we use a vacuum tube (triode), bipolar transistor or an FET (field-effect transistor) in the circuit. The operating conditions remain the same except for the dc voltages applied to the circuit: The tube would require filament voltage and a higher dc voltage.

Y1, the quartz crystal, is located in the feedback path (between the drain and gate of Q1) to ensure oscillation. We must be careful to make certain we have neither too little nor too much feedback. Insufficient feedback will prevent oscillation, or sluggish starting of the oscillator when operating power is applied. Too much feedback can cause unwanted "frigglies" (oscillations at other than the crystal frequency) or, as some call the condition, "squegging."



Fig. 2 — A basic Colpitts oscillator using a crystal.

To have control over the amount of feedback in Fig. 1 we have added C1 and C2. C1 is variable (a trimmer capacitor) to permit adjustment of the feedback energy. Once the correct value of capacitance is found for our crystal, by virtue of C1, we may install a fixed-value capacitor. A 100-pF capacitor is suitable for C2 for ham-band use from 1.8 to 21 MHz. C1 can be a 60-pF trimmer. An MPF102 or 2N4416-family FET will be suitable at Q1. RFC1 is an RF choke that is resonant with the stray circuit capacitance (roughly 10 pF in most cases) well below the crystal frequency.

For example, using the ARRL Type A L/C/F slide-rule calculator, we would find that a 150-µH RF choke with 10 pF of stray capacitance would be resonant at the high end of the 75-meter band (4 MHz). If our oscillator were for use in that part of the spectrum we would want to avoid this condition. It would be better to use a 500-µH choke, which would provide resonance at approximately 2.2 MHz. We could remove all doubt by using a 1-mH (millihenry) RF choke, which is 1000 µH.

Output from the oscillator of Fig. 1 is taken from the drain of Q1. In order to help prevent the circuit that follows our oscillator from impairing oscillations (loading the oscillator too heavily), a small value of capacitance is used at C3. It should be the smallest value that is practical for delivering the required power to the next stage of the overall circuit. Usually, this will be between 10 and 100 pF in the 1.8 to 30 MHz range. Too much oscillator loading can prevent oscillation.

Colpitts Oscillator

A popular oscillator is shown in Fig. 2. This is the Colpitts circuit. Although a bipolar transistor is shown at Q1, a tube or FET could be used with equal success. In Fig. 1 we found the source of Q1 at ground potential, respective to dc and RF. In Fig. 2, the collector of Q1 is at RF ground by virtue of the collector bypass capacitor, C4. Hence, the feedback path for the Colpitts circuit we have illustrated is between the emitter and base. Other forms of the Colpitts oscillator are common; this is but one variation.

Once again we have used two capacitors

(C1 and C2) for controlling the feedback. C1 and C2 are for that purpose. I find that in a practical circuit that uses a good, active crystal, the ratio of capacitance for C1 and C2 is on the order of 4:1. The larger value is used at C2. By placing a trimmer at C1 we can adjust the feedback for best performance of the crystal we use at Y1. A value of 100 pF seems to be fine for C2, with C1 being a 60-pF trimmer. The RF-choke rule for Fig. 1 does not apply here, entirely. The self-resonant frequency should be well below the crystal frequency. But, with a 100-pF capacitor in shunt with the choke (RFC1 and C2), the resonant frequency will be rather low compared to what it would be if only 10 pF of stray capacitance were present.

Output is taken via C3, which should again be a small value of capacitance to prevent the succeeding circuitry from loading the oscillator excessively. The 10- to 100-pF range is applicable to this circuit also. Q1 can be any small-signal bipolar transistor that has a fairly high cutoff frequency (f_T). I like to use a transistor that has an f_T of 5 to 10 times, or greater, the crystal frequency. Such devices as the 2N3904 and 2N2222A are fine for frequencies up to 20 MHz — the approximate limit for fundamental-cut crystals.

There are, indeed, many kinds of crystal oscillator circuits, but it would take many articles of this length to show them and describe their basic performance characteristics. The Pierce and Colpitts form the basis for most amateur oscillator circuits.

Overtone Oscillators

How might we obtain crystal-oscillator performance above the frequencies for which fundamental crystals are limited? Well, we adopt what is called the "overtone oscillator." As is true of fundamental types of oscillators, there are countless overtone-oscillator circuits. We will deal with but two of them, mainly to illustrate the principle of operation. A simple triode overtone oscillator is shown in Fig. 3A. Y1 is manufactured as a crystal that operates at an odd multiple of its fundamental frequency. This means that we may use a third- or fifth-overtone crystal in our circuit to obtain output at some frequency above, say, 20 MHz. Let's imagine that we wanted a crystal oscillator for use at 28 MHz. We should order a third-overtone crystal for the exact 10-meter frequency of interest. The manufacturer would again need to know the load capacitance presented by our circuit in order to grind or etch the quartz correctly. The crystal is ground for roughly one third the operating frequency. That is, a 28-MHz crystal would be ground for approximately 9.333 MHz. An overtone crystal does not oscillate at exactly three times the frequency of the quartz element, however, so the manufacturer must know the exact overtone frequency we desire. Likewise with fifth-overtone crystals, and so on.



Fig. 3 — Two common types of crystal overtone oscillator.

The circuit at A of Fig. 3 is rather simple. Sufficient internal coupling exists within Q1 to provide the feedback we need for oscillation. This would not necessarily be true of oscillators operating at the fundamental mode of the crystal. C1 and L1 are tuned to the desired overtone frequency, thereby providing feedback at the required frequency. If all is as it should be, Y1 will oscillate and provide RF output from Q1 at *only* the overtone frequency. Too much feedback will permit the crystal to oscillate at its fundamental frequency. This will cause the oscillator output to contain two frequencies — the fundamental *plus* the overtone. Output can be taken at high impedance by means of C2, or a link can be wound on L1 to provide low-impedance output via L2. The choice will depend on what we couple our oscillator to.

Another kind of overtone oscillator is illustrated at Fig. 3B. At first glance we might conclude that it is a Pierce oscillator. But, it is an overtone type of oscillator, with the crystal inserted between the drain and gate of the FET. C1, used to control the feedback, will have a slight effect on the operating frequency as it is adjusted. C2 and L1 again form a resonant circuit at the overtone frequency.

LC Oscillators

Most LC oscillators are used as VFOs (variable-frequency oscillators). But, we may elect to use them on occasion as single-frequency devices, just as we would with a crystal oscillator. How useful an LC oscillator may be will depend entirely on how frequency-stable we can make it. Although crystal oscillators are more expensive, they do offer the best stability of the two types.



Fig. 4 — Examples of coil-capacitor oscillators (see text).

Acceptable frequency stability is obtained through careful selection of the circuit components, the amount of feedback used, regulation of the operating voltages and providing as nearly a constant temperature environment as possible. Special temperature-compensating capacitors are often used to minimize frequency changes. The coil and capacitor must be mechanically and electrically well built to enhance stability. Similarly, nothing in the immediate vicinity of the LC oscillator must be allowed to move position, for this can change the operating frequency. Changes in oscillator loading, caused by operating-condition variations in succeeding circuit stages, will also shift the frequency. LC types of oscillators are more prone to this malady than are crystal oscillators.

Three types of LC oscillators are shown in Fig. 4. The first example (A) is probably the most common of the three in ham equipment. Since C2 and L1 are in parallel, this is called a parallel-tuned oscillator. C3 and C4 provide the path for our feedback energy. In LC oscillators the value of C3 and C4 are approximately the same. A



Fig. 5 — Details of how C, L or both elements can be added to an oscillator circuit to shift the crystal frequency.

3.5-MHz VFO, for example, might use 1000 pF for each of the feedback capacitors. C5 is once more a small-value coupling capacitor to minimize output loading.

The circuit of Fig. 4B relies upon a tap near the grounded end of L1 to provide feedback for oscillation. The tap is usually located approximately ¼ of the way up the coil from ground. Output can be taken via C3 or by means of a link winding (L2) at the ground end of L1.

A series-tuned Colpitts VFO is illustrated at Fig. 4C. The name applies because C1 and L1 are in series for this circuit. The advantage of this configuration over that of Fig. 4A is of particular interest as we raise the operating frequency. Sometimes we end up with impractical (small) values of inductance for L1 in a parallel-tuned circuit, especially at high operating frequencies: The series-tuned arrangement requires a much larger amount of inductance and a smaller value of capacitance at C1 for a given tuning range. The series-tuned format can often lead to improved frequency stability for reasons that we cannot address here.

Shifting the Crystal Frequency

We discussed earlier the possibility of making small changes in the operating frequency of crystal oscillators. This can be done by adopting the methods depicted in Fig. 5. The smallest frequency change will be experienced when using only a variable capacitor as shown at A in Fig. 5. The higher the crystal frequency the greater the frequency shift as C1 is adjusted. The trimmer can also be placed in parallel with C1. One method raises the frequency while the other lowers it. An inductance can be added in series with a crystal, as shown in Fig. 5B, to shift the frequency of oscillation. Too much inductance at L1 will convert the crystal oscillator to an LC type of circuit, and the benefits of crystal control will be lost. I prefer to use an inductive reactance of approximately 850, maximum. Hence, for a 7.0-MHz crystal the maximum inductance at L1 would be 19.3 μH, derived from

$$L(\mu H) = \frac{X_L}{2\pi f} = \frac{850}{6.28 \times 7} = 19.3 \qquad \text{(Eq. 1)}$$

where X_L is in ohms and f is in MHz.

The greatest amount of frequency pulling or swing will be obtained if we employ the method at C of Fig. 5. Here we have a coil and capacitor in a series arrangement at the bottom end of Y1. A 100-pF variable capacitor can be used along with a coil whose value is derived from Eq. 1. Frequency shifts as great as 10 kHz can be had at 10.1 MHz, with 5 kHz being typical at 7 MHz, and 3 kHz being about the limit at 3.5 MHz. Anything greater than that suggests that L1 has too much inductance for full crystal control. A circuit like the one in Fig. 5C is usually referred to as a VXO (variable crystal oscillator). In some circuits we will find that C1 has been replaced by a varicap diode, or voltage-variable capacitance diode. The frequency change will not be as great as with an air variable capacitor, since the minimum capacitance of a varactor diode will be much higher than that of a mechanical capacitor.

Buffering and Isolation

Throughout our discussion we have mentioned loading at the output of oscillators, plus the frequency shifting caused by load variations. We considered also the effects on oscillation that too much loading might cause. These problems can be reduced or eliminated by adding buffer stages after the oscillator, as shown in Fig. 6. In effect, these additional stages help to isolate the oscillator from the circuits that succeed the frequency-generating chain. Some buffer stages can also provide signal amplification, whereas others might reduce the effective output level of our oscillator. FETs work well as buffer stages, owing to their very high input impedance (usually a megohm or greater). The gate resistor in Fig. 6 determines the input impedance of Q2, since it is lower in ohmic value than the natural gate impedance of Q2. Since we show Q2 as a source-follower stage, the output of the FET will be slightly less than the output of Q1 — approximately 10% lower.

Most VFO circuits have at least two buffer stages, and sometimes three. One or more of the buffers can be designed as amplifiers if we wish. This enables us to extract greater output power than would be possible if we took the output directly from the oscillator. C1 and C2 of Fig. 6 are small in capacitance value. This helps limit loading effects after the oscillator. If you have built a VFO-controlled CW transmitter that is chirpy (frequency shifting when the key is closed), chances are that you did not include sufficient buffering to isolate the VFO.



Fig. 6 — Illustration of how a buffer stage can be used after an oscillator to minimize frequency changes caused by load variations.

A Practical Universal VXO

I lean rather strongly toward the use of VXOs (Fig. 5C) above 7 MHz, especially for portable transmitters and receivers that are apt to be used in an environment of frequent temperature changes. They are stable and reliable. The VXO is nice for use as a VFO when operating VHF equipment. We will not obtain as great a potential frequency swing with our VXOs as can be had with an LC type of VFO, but more than one crystal can be switched into the VXO for wide frequency coverage in some amateur band.

The circuit in Fig. 7 shows the diagram of a VXO I developed for my use at a number of frequencies. C1, C2, C3, FL1 and Y1 can be changed to appropriate values for the frequency of interest. This circuit is set up for use as a 2-meter VFO, and when its output is multiplied eight times to 144 MHz, I can obtain coverage from 144 to approximately 144.250 MHz — about right for the CW and SSB part of the band.

Those of you who like to experiment may want to build this circuit. It can have many uses, depending on the frequency to which it is tailored. For example, we might use a VXO for the local oscillator in a homemade receiver. It could be the heart of a little signal generator for workshop use. We might multiply the output more than eight times for the purpose of using the VXO as a frequency source at 220 or 432 MHz, or as a signal generator for VHF and UHF testing. By lowering the VXO frequency to 20, 30 or 40 meters, it can serve nicely as the frequency-controlling element for a home-built CW transmitter.

Best operation (maximum frequency swing) will be had if we use AT-cut crystals. Preferably, they will be the type that are suspended by tiny wires inside the crystal holder (HC-6/U), and they will be cut for fundamental-mode use. I use International Crystal Mfg. Co. general-purpose types of crystals with a 30-pF load capacitance.


4 V
470
VXO
2N5179
4.5 V
0.6 V
Q1
R3
15
100
0.1
B
C
E
18.00625 MHz
Y1
R1
22 k
L1
C2
27
S.M.
R2
47 k
C3
56
S.M.
RFC 1
100 µH
C1
50
FREQ. ADJUST
1.5 V
3 V
27
S.M.
0.1
1 k
D1
LED
REGULATOR
BUFFER / AMP
T1
4:1
A
B
C
D
2.25 V
2N5179
Q2
11 V
1.25 V
1.3 V
10 k
56 k
R3
100
0.1
5 V
R3
330
+12 V
0.1
D2
5 V
400 mW
REGULATOR
0.1
470
0.1
0.1
100
+
220 µF
16 V
+12 V
(30 mA)
f_co = 19 MHz
FL1
L2
L3
0.4 µH
0.4 µH
C4A
C4B
68
S.M.
100
S.M.
C5
330
S.M.
C6A
C6B
68
S.M.
100
S.M.
1.5 V
OUTPUT
(50 Ω)
*
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF);
OTHERS ARE IN PICOFARADS (pF OR µµF);
RESISTANCES ARE IN OHMS;
k = 1000, M = 1000 000.
* = OUTPUT ≈ 40 mW (+16 dBm)
V = RMS VOLTAGE
V = DC VOLTAGE
● = PHASING
S.M. = SILVER MICA
T1
A
B
C
D
B
E
C
Q1, Q2
BOTTOM

Fig. 7 — Schematic diagram of a universal VXO. Fixed-value capacitors except those in Table 1 are disc ceramic. The polarized capacitor is tantalum or electrolytic. Resistors other than R3 are ¼- or ½-W carbon composition. R3 is a ½-W unit.

C1 — Panel-mounted miniature air variable, 50 or 100 pF (not critical).
C2-C6, incl. — See Table 1.
L1, L2 and L3 — See Table 1.
D1 — 1.5-V regulator. Use an LED or two 1N914 diodes in series.
D2 — 5 V, 400 mW Zener diode.
R2 — Value may be adjusted for purest output waveform from Q1.
T1 — Broadband toroidal 4:1 transformer (see Table 1).
Y1 — AT-cut fundamental crystal in HC-6/U holder, 20- or 30-pF load capacitance suitable (International Crystal Mfg. Co. type GP).

Table 1

Typical L and C Values for Various Operating Frequencies

Crystal (Y1) Range (MHz)	*C2 (pF)*	*C3 (pF)*	*C4, C6 (pF)*	*C5 (pF)*	*L1*	*L2, L3*	*T1*
6.000 to 9.000	68	100	390 (for 40-meter use)	820	17 µH max. 55 ts. of no. 26 wire on a T68-2 toroid core	1 µH. 18 ts. no. 26 wire on a T37-6 toroid core. (40-meter use)	15 bifilar ts. of no. 26 on an FT-37-43 toroid core.
9.000 to 15.000	39	68	287 (for 30-meter use)	560	12 µH max. 49 ts. of no. 28 wire on a T50-2 toroid core	0.72 µH. 15 ts. no. 26 wire on a T37-6 toroid core. (30-meter use)	15 bifilar ts. of no. 26 on an FT-37-61 toroid core.
9.000 to 15.000	39	68	212 (for 20-meter use)	424	12 µH max. Same as above.	0.53 µH. 13 ts. no. 24 wire on a T37-6 toroid core. (20-meter use)	Same as above on FT-37-61 toroid core.
15.000 to 20.000	27	56	168	330	7 µH max. 42 ts. of no. 26 wire on a T50-6 toroid core.	0.42 µH. 12 ts. no. 26 wire on a T37-6 toroid core. (for 18-MHz use)	Same as above on FT-37-61 toroid core.

The capacitors are silver-mica or polystyrene types. All toroid coils should be doped with two coats of coil cement or General Cement Q-Dope® after they are wound. Toroid cores are available by mail from Amidon Associates, 12033 Otsego St., N. Hollywood, CA 91607. Also check *QST* ads for Palomar Engineers and RadioKit. Values for C4, C5, C6, L2 and L3, when FL1 of Fig. 7 is to be used for frequencies other than those listed, can be obtained from the filter tables in *The Radio Amateur's Handbook*, transmitting chapter. Nonstandard capacitor values can be closely approximated by using series or parallel combinations of standard values. The nearest standard values have been listed, where possible.

They are the least expensive and seem to be very "rubbery" in VXO circuits. Irrespective of the brand of crystal used, no two identical crystals will yield the same amount of frequency swing in a VXO. I have never understood exactly why this happens, but I have observed it countless times.

If a coil with very high Q (quality factor) is used at L1 of Fig. 7, it may be necessary to swamp the coil with a resistor (R1) to lower the Q. Values from 10 kΩ to 27 kΩ seem to do the job. The need for R1 will be evident if while we are tuning C1 through its range the VXO will break into oscillation at some other frequency (mode changing) and be erratic in operation.

As an aid to the overall frequency stability of Q1, I decided to regulate not only the collector voltage, but put a separate regulator on the feed for the base bias. D1, a standard LED (light-emitting diode), makes a fine 1.5-V regulator when used as shown. Alternatively, we can use two 1N914 diodes in series at D1.

Q2 functions as a buffer/amplifier. It is a broadband, linear Class A stage. Output from Q2 is filtered by means of FL1, a half-wave harmonic filter. It is designed for a 50-ohm input/output characteristic.

Typical output power is 40 mW, which equates to +16 dBm. This is ample to excite most low-level amplifiers or DBM (doubly balanced mixers) of the diode-quad type. If the DBM calls for −7 dBm of injection, a resistive 50-ohm attenuator can be inserted in the line between FL1 and the mixer. The *ARRL Electronics Data Book* (out of print) contains tables of values for resistive attenuator pads. Circuit boards and complete parts kits for this workshop project are available.[1]

I have included key dc and RMS (root-mean-square) voltages on the schematic diagram. These can be used for troubleshooting the circuit if problems arise. An RF probe and VTVM can be used to check the RMS voltage values, or you can use a scope if it has ample bandwidth to provide accurate P-P (peak-to-peak) voltage readings. Multiply your P-P voltages by 0.3535 to obtain the equivalent RMS voltage. All *dc readings are referenced to circuit* ground.

Although 2N5179 CATV transistors are specified in Fig. 7, other NPN devices of similar characteristics will work satisfactorily. I have used 2N3572s with good results. The common 2N2222A should offer acceptable performance as well. The output power of this circuit can be lowered by increasing the resistance of R3. This can eliminate the need to add outboard attenuator pads for power reduction.

If possible, use a double-bearing variable capacitor at C1 (a bearing at each end of the rotor). Addition of a panel-mounted vernier drive will facilitate dial calibration and provide a better (slower) tuning rate. A frequency counter can be used to develop a dial-calibration chart.



Fig. 8 — Parts-placement guide for the universal VXO, shown from the component side of the PC board.



Fig. 9 — Circuit-board etching pattern for the Universal VXO. The pattern is shown full-size from the foil side of the board. Black areas represent unetched copper foil.

Frequency drift from a cold start to an hour later (at 70° F) was 30 Hz. At 2 meters this would multiply to 240 Hz — an acceptable value. The VXO or any LC VFO should be built in a separate shielded box for best results. This will help to maintain a more constant temperature and will prevent unwanted RF energy from entering the circuit and causing frequency changes that aren't wanted. Table 1 lists some typical values for other operating frequencies. Fig. 8 shows the parts placement for the circuit board. A scale pattern for the PC board can be found in the Hints and Kinks section of this issue of *QST*.

Closing Thoughts

We have barely scratched the veneer in this discussion of oscillators. But, I hope you have acquired a better understanding of how they work and what can be done to improve their performance. I suggest you take soldering iron in hand and tack together some of the one-stage oscillators that are presented in this article. Experiment with them to study the cause and effect of value changes, and so on. There is no substitute for "learning by doing." There is no reason you can't tackle the VXO project of Fig. 7. It can be useful in many applications in your ham shack. Good luck!

[1] Circuit Board Specialists, P.O. Box 969, Pueblo, CO 81002. Catalog of kits available on request.

For updated supplier addresses, see ARRL Parts Supplier List in Chapter 2.

From July 1985 **QST**, *p 22:*

BUT, DAD, I'M MAKING A TUNING CAPACITOR!
81

The Fine Art of Improvisation

Improvising in the ham workshop may lead to new ways for solving electrical and mechanical problems. The net result is often a savings in time and money!

By Doug DeMaw,* W1FB

"I gave up on building ham gear because parts are hard to find and they cost too much." Ever hear that comment? Perhaps you've said it to yourself in silent despair. Actually, parts are not hard to find, and most of them need not be purchased at top price. But, there are *some* items that are very expensive and hard to locate when we attempt to buy them new. It is conceivable that we might have to spend $15 for a tuning capacitor and a vernier drive, when the circuit with which it will be used contains only $3 worth of small parts. Prices of items such as tuning capacitors, drive mechanisms, cabinets, slug-tuned coils and meters (purchased new at nonsurplus prices) can discourage even those builders who have a large Amateur Radio budget. The cost, plus the present-day agonies of being socked with back orders and "out of stock" notifications from mail-order dealers, does tend to make us think parts are hard to obtain.

What alternatives do we have? The ingenuity of a true experimenter must be summoned from within if speedy solutions to these common problems are to be found. In decades past, it was a regularly practiced art among hams to solve design and procurement problems by using materials on hand. Most hams were inveterate experimenters when I became involved in Amateur Radio. It was considered a challenge to come up with new electrical and mechanical ideas, then share them with other amateurs. In those days, it was often a stimulating learning experience to get on the air and talk about circuits and projects. Each of us has the potential to build radio equipment, to find shortcuts to design objectives and to enjoy using something we built ourselves. Let's consider some practical ways to use parts in applications for which they were not designed. Perhaps some of these concepts will solve a design problem for you.

Experimental Tuning Methods

Transmitters and receivers require some type of signal source, and generally this local oscillator (LO) is tunable. The conventional techniques for changing a VFO frequency are by means of a fixed-value inductor and variable capacitor or a fixed-value capacitor and a variable inductor, or by employing a VVC (voltage-variable-capacitor) diode. A quality double-bearing tuning capacitor that rotates smoothly is not only hard to find these days, it can be bulky and very expensive. Much of our miniature homemade equipment would be more practical if a tuning capacitor could be avoided for changing the oscillator frequency.

How might we contrive a simpler, less expensive method for tuning a VFO? I developed an interesting circuit for use in a very compact receiver (Fig. 1) that qualifies as a simple, inexpensive tuning technique. I had some reservations about



Fig. 1—Typical circuit for a VFO that uses a 2N4416 or MPF102 FET. Tuning is by means of R1 in series with C2. C2 sets the frequency spread provided by R1. This arrangement is useful when an air-variable capacitor and vernier drive are not desired. It can lead to a very compact VFO assembly. The tap position on the coil (L1) and the maximum capacitance provided by C2 determine the maximum tuning range available.

---

*ARRL Contributing Editor, P.O. Box 250, Luther, MI 49656



Fig. 2—A variation of the circuit of Fig. 1. In this example, the tuning mechanism is a potentiometer that has been modified to become a small variable inductor (see text).

how it might work, but after breadboarding a test circuit, I was pleasantly surprised with the results. For lack of a better name, I call it "reactance tuning." Fig. 1 shows the details of the test circuit in which I tried the idea. R1, which is a high-quality Allen Bradley (A/B) potentiometer, is located close to C2 and L1 in order to keep the leads from R1 as short and direct as possible.

Why does this system work? Well, as R1 is adjusted, the presence of the capacitance of C2 (a trimmer) is more prominent in the tuned circuit. The series combination of C2 and R1 form a capacitive reactance and resistance that cause a frequency shift as R1 is adjusted. The smaller the value of resistance at R1, the lower the operating frequency, because the capacitance of C2 will be more effective.

What are the bad features? No innovation is necessarily perfect, and this applies to the technique illustrated in Fig. 1. The tuning is nonlinear. That is, the frequency is spread out at the maximum-resistance end of the R1 range, and it is somewhat compressed at the minimum-resistance end. Also, if a poor-quality control is used at R1, you may hear a slight scratching noise as the control is adjusted, while listening to the output of a receiver in which this VFO is used. It should not cause a problem if we use the VFO in a transmitter.

The amount of frequency shift available depends on two things: the position of coil tap X on L1 of Fig. 1, and the setting of the trimmer capacitor, C2. The farther the L1 tap is above ground, the greater the frequency change as R1 is adjusted. Similarly, the greater the capacitance of C2, the larger the frequency change. I had no trouble covering all of the 40-meter band when the coil tap was close to the high end of L1. In a practical application, it is best to limit the frequency change to 25 or 50 kHz. This provides better bandspread when R1 is adjusted. A vernier-drive mechanism can be coupled to R1 if frequency excursions greater than, say, 50 kHz are desired.

I did not observe any degradation in VFO frequency stability when comparing this tuning method with that of variable-capacitor tuning while using the same oscillator module. There is, however, a point in the tuning range of R1 where the loaded Q of the VFO tuned circuit will take a dip. When this happens, the VFO output will drop slightly and the output waveform linearity will change. In most practical applications, you will not be able to detect this effect.

As an alternative to the use of a vernier drive attached to R1, we might consider using a bargain-priced 10-turn, carbon-composition control with a suitable 10-turn counter dial. Wire-wound controls must be avoided because they are inductive.

Another Tuning Trick

I tried another idea that I had in mind for a number of years. The circuit for this one is given in Fig. 2. L2, a modified carbon control, is fashioned by removing the metal cover from a standard-size potentiometer, then removing (carefully) the semicircular carbon element from inside the control. I was able to snap this element loose by prying it up near the tabs of the control. The thin phenolic base material broke easily. I used this element as a pattern and cut out a new element from flashing copper. Brass would work, also. Silver plating would help to ensure minimum corrosion, but it is not necessary to add silver plating if the control will be used regularly.

The new element is glued in place, and the ends of the insert piece are soldered to the two outer lugs of the old control. Be careful to avoid getting epoxy glue on the upper surface of the metal element, or erratic operation will result.

Refer again to Fig. 2. L2 is a small variable inductor we made from the potentiometer. It comprises a part of the overall circuit inductance by virtue of its being in series with L1. As L2 is adjusted, the VFO frequency will change. The higher the operating frequency of the VFO, the greater the frequency change caused by L2. Also, the higher the C-to-L ratio of the VFO, the more effect you will observe when L2 is adjusted. The frequency shift obtained with this method is substantially less than with the circuit of Fig. 1, at least with the circuit values given. A 10-kHz shift was observed.

Incremental band-segment selection can be had with either circuit (Figs. 1 and 2) by adopting the method shown in Fig. 3. S1 is used to add capacitors to the VFO tuned circuit, and R1 or L2 can be used in the manner described previously. Perhaps a miniature DIP switch can be added to operate as S1 when compact equipment is being built. The values of capacitors C3, C4 and C5 will determine the coarse tuning range. Trimmers may be substituted for these fixed-value capacitors, which will enable you to have the tuning ranges overlap.

Simple, Homemade Tuning Capacitor

Large frequency changes are possible if we use a low-capacitance variable capacitor that is connected to the high end of a VFO tuned circuit (junction of C1 and L1 of



Fig. 3—S1, C3, C4 and C5 have been added to the circuit of Fig. 1 to provide coarse frequency increments. R1 tunes the VFO through each of the three ranges.



Fig. 4—Mechanical details for a homemade disc tuning capacitor. A tension spring ensures mechanical stability of the rotor portion of the variable capacitor. Side brackets also help to keep the unit mechanically rigid. The detail at B shows how the stator disc is etched on PC board material.


THIN COPPER OR BRASS (GLUE)
ONE-HALF OF A SOLID BRASS ROD GROUND TO ACCEPT ROD
STATOR CONNECTION
GLUE TUBING TO PLATE
1/4" ROD
SOLDER ROD IN GROOVE
GROUNDED VIA PANEL BUSHING TO CHASSIS
POLYSTYRENE OR ACRYLIC TUBING

Fig. 5—A cylindrical format provides still another tuning device that can be made at home. The rotor unit is semicircular brass or copper to which a ¼-inch-diameter tuning rod has been soldered. The stator section is a piece of plastic tubing to which thin copper or brass sheeting has been glued (see text).

Fig. 1). A simple mechanism is illustrated in Fig. 4. It is one that I developed during my search for simple VFO tuning methods. The drawing at A of Fig. 4 shows a side view of the assembly I constructed. A piece of ¼-in × 20 iron bolt is used as the tuning shaft. The front plate of the tuner is a piece of copper-clad PC board. The hex nut is soldered to the inner surface of this end plate, as shown. A disc of copper or brass serves as the capacitor rotor. It is soldered to the end of the bolt that is opposite the knob. I used a 1-inch-diameter disc, and made certain it was at an exact right angle to the bolt when I soldered the two pieces together. A spring is used between the disc plate and the front-plate bearing nut to prevent wobbling and undue backlash. PC-board braces are soldered (four each) to the front bracket and stator-plate bracket to ensure physical stability.

Drawing B of Fig. 4 shows how I made the stator plate. It is a piece of PC board with an outer border and disc that were provided by etching with ferric-chloride solution. Glass-epoxy circuit board is recommended in the interest of high dielectric quality and physical strength. A piece of thin Teflon® sheet is glued to the surface of the stator disc to prevent short circuiting of the stator and rotor discs. Polyethylene sheeting is suitable if you have no Teflon on hand. The capacitance range I obtained with this unit was 0 to 18 pF with the 1-inch diameter disc plates. The closer the plates are to one another, the greater the capacitance and the faster the tuning rate. The rotor disc is grounded by means of the bolt-to-nut connection and by virtue of the front-end plate being grounded. Those skilled in machine work should be able to improve on this design. The disc-tuning method is by no means a new concept. VHF cavities and amplifiers were tuned by this technique for many years. But, I don't recall seeing it applied to HF circuits in this manner.

Another Capacitor Idea

A cylindrical tuning capacitor can be fashioned as shown in Fig. 5. The rotor is slipped inside the stator tubing. When the metal half-rod of the rotor is immediately adjacent to the metal half-round outer conductor of the stator tube, maximum capacitance will exist. The rotor shaft is rotated by means of a knob or vernier drive to operate this capacitor. The larger the two half-round conductors (circumference and length), the greater the maximum capacitance of the unit. The mechanical aspects of this device can be improved markedly by those of you who are adept at building mechanical gadgets. Certainly, a fine assembly could be turned out by a craftsman. The point being made here is that this is just another method for constructing a homemade variable capacitor. There are many other unique ways to construct home-built tuning capacitors, but we shall not go into a lengthy discussion about them.

Generating Innovative Ideas

I have been asked, "How do you come up with so many unusual gadgets?" I think the best reply I can offer is to say that examination of a conventional component should suggest numerous ways to simplify it at a savings in cost. Some inventors do not generate new ideas. Rather, they pick up some ordinary object, such as a paper clip, then ask themselves, "What can I do to improve this thing?" We might also ask ourselves, "What don't I like about this paper clip?" The next step is to devise a new paper clip that no longer has the design fault. Bingo! A new patent can result! This general philosophy can be applied to making our own radio components from readily available materials. You can try your ideas, and you need not be ashamed if they don't work the first time or even at all.

In Conclusion

When you are working with the circuits of Figs. 1 and 2, it is important that the Q of L1 be as high as you can make it. If the Q is quite low, the addition of R1 or L2 could cause the VFO to cease oscillating at some point in the tuning range. Therefore, I suggest that you use a T68-6 toroid core for frequencies above 4 MHz. The wire size should be as large as can be wound easily on the toroid core. This will reduce the coil resistance and enhance the Q. The same rule applies if you use a slug-tuned inductor: The core should be for use in the upper part of the HF spectrum. High-quality capacitors should be used also. The NP0 units specified are entirely suitable, and will ensure minimum VFO drift. Silver-mica capacitors can be used, but will cause considerably more drift than will the NP0 ceramic units.

Should you develop some noteworthy circuit innovations, please consider sharing them with others through the pages of *QST*. Detailed descriptions can be submitted as articles. Short explanatory narratives may be just right for the Hints and Kinks column.

From September 1987 QST, p 25:

Tuning-Diode Applications and a VVC-Tuned 40-m VFO

Inexpensive voltage-variable capacitance diodes are compact and easy to use in your Amateur Radio circuits. They can replace expensive, hard-to-get air-variable tuning capacitors.

By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250, Luther, MI 49656

Have you looked lately for small air-variable capacitors? Does the high cost and scarcity of tuning capacitors bother you? If you answer "yes" to these questions, I can sympathize with you!

Gone are the days when small air-variables lined the shelves of electronics surplus stores. Gone, too, are the attractive price tags of $1 or less. New capacitors are presently in the $10-$15 class, if you can find them. The once-popular Hammarlund and E. F. Johnson capacitor lines are produced by another firm, and single-lot purchases are a thing of the past. The surplus market has literally dried up for small air-variable capacitors with tuning shafts. There is, however, a bright spot in this seemingly grim situation.

We can look toward voltage-variable capacitance (VVC) diodes as a solution to the mechanical-capacitor shortages, at least for use with low-power oscillators and low-level tuned RF circuits. Tuning diodes are not only inexpensive, they are small. There is a greater opportunity for circuit miniaturization using VVC diodes. The major performance trade-off relates to use of diodes in VFO circuits: The frequency stability may be worse than with air variables, and the minimum capacitance of VVC diodes is substantially greater than is typical of an air-variable capacitor. For most amateur applications, however, these shortcomings are not serious.

VVC Diode Characterization

You have probably heard people refer to tuning diodes as Epicap® or Varicap® diodes. These are trade names that the manufacturers have given to these diodes. A varactor (variable reactor) diode is similar in effect to a tuning diode, but it is earmarked for use as a frequency multiplier (harmonic generator). Ordinary tuning diodes work quite well as varactors, as do many small-signal, high-speed switching diodes, such as the popular 1N914. The base-collector junctions of many transistors may also be used as tuning diodes or varactors.

In simple terms, the junction capacitance of a VVC diode changes when a reverse voltage is applied to the device (positive voltage applied to the diode cathode), and the capacitance varies with the voltage. The diode is placed in parallel with the components of a tuned circuit, and tuning is accomplished by varying the voltage, and thus the capacitance, by means of a potentiometer.

Fig 1 shows the equivalent electrical circuit of a VVC diode. Note that there are components of capacitance, resistance and inductance present. C_c is the stray case capacitance. C_j is the junction capacitance (voltage variable). L_s is the diode series inductance, and R_j is the junction resistance (also voltage variable, but negligible above 100 kHz). Finally, R_s is the series resistance of the diode and its leads. Our practical concern is mainly for the C_j component, at least with regard to HF operation. At VHF, and higher, we must be concerned about parasitic capacitance C_c, and R_c, both of which affect the Q and the upper-frequency limit or cutoff frequency of the diode, F_{co}. The diode cutoff frequency is also affected by L_s.



Fig 1—Electrical equivalent of a VVC diode, showing components of C, L and R (see text).

Types of VVC Diodes

There are three styles of tuning diodes. See Fig 2. The diode at A is the basic single-junction type, with a cathode and an anode. Fig 2B shows a unit that is designed to tune three circuits in an AM broadcast receiver. Three separate VVC diodes are contained in a single case. The tuning diode of Fig 2C features a back-to-back pair of junctions. Single VVC diodes can be connected together as in Fig 2C, if desired.

Diode Q Factor

An important consideration for any resonant circuit is the Q (quality factor). The higher the Q_L (loaded Q), the better the circuit selectivity (sharpness of response). High Q is important to an oscillator because if the Q is too low, the oscillator may not work or it may generate wideband noise. Q is dependent upon,



Fig 2—Three types of VVC diodes. A single diode is shown at A. The triple-diode version at B is for tuning three circuits at the same time, such as an RF amplifier, mixer and oscillator. Back-to-back diodes in one package are shown at C.

among other things, the ac resistance of the circuit: the higher the resistance, the lower the Q.

Tuning diodes are rated for Q. This factor varies with the operating voltage and the operating frequency. The Q for a given VVC diode changes considerably as the reverse voltage is varied. The manufacturers' specification sheets include curves showing Q compared with operating voltage and frequency. Check them before selecting a diode for your application.



Fig 3—Abbreviated capacitance/reverse voltage curve for an MV2109 tuning diode. Note the flat portion of the curve to the left (see text for precautions about reverse voltages from 0.1 to 1.5).

Performance Trade-offs

Tuning diodes are not perfect! They have some shortcomings that we must take into account as we design circuits using them. They can worsen the frequency drift of a VFO when they are used in place of an air-variable capacitor. This is because all semiconductor junctions change capacitance with changes in junction temperature. Transistor junctions undergo the same changes with respect to temperature. The addition of a VVC diode adds to the short- and long-term drift problems.

Another annoyance with VVC diodes is the fairly high minimum capacitance value. An air-variable capacitor with a range of 50 pF might have a minimum capacitance of, say, 8 pF, whereas a VVC with a 50-pF range can have a minimum capacitance of 25 pF. We must design the tuned circuit to accommodate the high minimum capacitance of the diode. In some cases, this calls for a high C, low L tuned circuit.

The change in diode capacitance is quite nonlinear as the reverse voltage is decreased below approximately 2 V. This means that we should design for operation in a reasonably linear portion of the curve. Fig 3 shows a typical VVC diode voltage/capacitance curve. You can see that there is very little capacitance change from 0.1 to 1 V. If we use this portion of the curve, we will find that our tuning control has minor effect until we reach the 1.5-V region. The range from 2 to 8 V provides a more linear capacitance change, and this is the desired part of the curve. If we allow the voltage to drop below 1.5, a large part of the tuning dial range will be wasted on a 1- or 2-kHz frequency change at, for example, 7 MHz, while the overall frequency change may be 100 kHz in the 2-


(A)
MECHANICAL TUNING
L1
C1 100
C2 30 CAL
C3 25 MAIN TUNING
100
100 k
VFO
Q1
MPF102
1N914
(B)
ELECTRONIC TUNING
L1
C1 100
C2 30 CAL
C3 100
D1
100
100 k
100 k
R1 50 k
MAIN TUNING
+V REG
VFO
Q1
MPF102
1N914
(C)
ELECTRONIC TUNING
L1
C1 100
C2 30 CAL
C3 100
D1
2N3904
NC
100
100 k
100 k
R1 50 k
MAIN TUNING
+V REG
VFO
Q1
MPF102
1N914
(D)
ELECTRONIC TUNING
L1
C1 100
C2 30 CAL
MV104
D1
100
100 k
100 k
R1 50 k
MAIN TUNING
+V REG
VFO
Q1
MPF102
1N914

EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000, M = 1000 000.

Fig 4—Simplified examples of electronically tuned oscillators. The circuit at A is tuned by a conventional air-variable capacitor. The circuit at B uses a single VVC diode. The example at C shows how to use a bipolar transistor junction as a tuning diode. The circuit at D is preferred, with respect to obtaining a linear oscillator waveform.


VFO
RF AMP
7.0-7.1 MHz
2.6 μH
L1
C1
100 NPO
C3 100 NPO
C2 30
R3 27k
R2 15k
2N2222A Q1
680 P C4
680 P C5
R4 560
C8 0.1
9.1 V
D2
50 NPO C7
R12 180
R10 5.6k
R8 1k
R9 15
Q3 2N3904
R13 560
R11 220
C13 0.1
C9 0.1
R14 39
L2 7.3 μH
C10 120 P
C11 120 P
C14 0.1
C12 0.1
J1 +12 V
J2 RF OUT
1500 Ω
(3 V P-P)
D1 MV2109
RFC 1 500 μH
TEMP COMP DIODE
R1 270k
Q2 2N3904
NC
1.6-7.5 V
C6 0.1
R15 1k
OFFSET (RECEIVE)
R5 470
R6 10k MAIN TUNING
R7 3.3k
B
E
C
Q2, Q3
Q1 BOTTOM VIEW
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000
NC = NO CONNECTION
P = POLYSTYRENE
NPO = ZERO TEMP COMP

Fig 5—Schematic diagram of a practical VVC-tuned VFO for 40 meters. Unless noted otherwise, fixed-value capacitors are disc ceramic or mylar. Fixed-value resistors are ¼- or ½-W carbon composition, 10% tolerance. Numbered components not listed below are identified for PC-board layout purposes.

C2—30-pF trimmer or ceramic NPO trimmer (preferred).
D1—Motorola MV2109 VVC diode (see notes 1 and 3).
D2—9.1 V, 400 mW Zener diode.
J1, J2—Single hole mount phono jack.
L1—Slug-tuned inductor, 2.6 μH. Use 16 turns of no. 26 enam wire on the bobbin of an Amidon Assoc L-57-6 transformer assembly.
L2—Toroidal inductor, 7.3 μH. Use 38 turns of no. 28 enam wire on an Amidon T-50-2 core.
R6—Linear taper 10-turn carbon composition potentiometer (see text).
RFC1—Miniature 500-μH RF choke.

to 8-V reverse-voltage range as we adjust the tuning potentiometer.

Most Motorola tuning diodes are rated for +30 V, maximum. I did not extend the curve in Fig 3 beyond 8 volts because the example is used mainly for illustrative purposes. The higher the reverse voltage, the lower the capacitance; but most amateur equipment is designed for 12-V operation. Therefore, we are interested primarily with the portion of the diode curve from 1.0 to 10 V. Regulated reverse voltage is necessary when VVC devices are used for the frequency control of oscillators; this aids frequency stability.

Some Circuit Examples

Fig 4 shows four VFO tuning approaches. Fig 4A illustrates, in abbreviated form, a tuned circuit for a VFO. C3 is an air-variable capacitor used for frequency adjustment. C2 is a trimmer capacitor used for oscillator calibration. The same circuit is seen at Fig 4B, but D1 and its related circuitry replaces C3 of Fig 4A. The values of C1 and L1 may need slight alteration to provide the same frequency coverage that is obtained from the oscillator of Fig 4A. This is because the minimum capacitance of D1 is greater than that of C3 of Fig 4A. R1 is a panel-mounted control used to vary the reverse voltage applied to D1. A resistor may be added between the low end of R1 and ground to prevent the diode voltage from dropping below 1 or 2 V. We can thereby avoid the flat part of the curve of Fig 3.

A transistor junction can be used as a VVC diode as shown in Fig 4C. The capacitance change will differ with the particular transistor used. Some experimentation may be useful.

Fig 4D shows a circuit using a Motorola MV104 VVC diode. Notice that the MV104 features two back-to-back diodes in one case. This arrangement is preferred for better oscillator-waveform linearity. Two separate VVCs may be connected together, back-to-back, when we desire to use the method seen at Fig 4D. Similarly, two bipolar transistors (Fig 4C) may be connected back-to-back to permit the arrangement of Fig 4D.

A Practical VVC-Tuned VFO

I chose the circuit of Fig 5 as the local oscillator for a direct-conversion (D-C) receiver I am developing. I want the unit to be small, so I opted for a VVC tuning scheme instead of using a large, expensive air-variable capacitor. I had on hand some surplus Motorola MV2109 Epicap diodes that I purchased from BCD Electro.[1] A capacitance swing of approximately 20 pF is possible in the linear portion of the diode curve. This provides sufficient capacitance change for the circuit of Fig 5, because I am interested in covering only 7.0 to 7.1 MHz. A tuning voltage of 1.6 to 7.5 provides the desired tuning range.

Q2 of Fig 5 is a temperature-compensating device that is connected as a diode. As the ambient temperature changes, so does the resistance of the Q2 diode junction. The small resultant resistance change causes the reverse voltage at D1 to change slightly, thus compensating for changes in the diode junction capacitance that are caused by heat.

R5 and R7 are included to provide the required 1.6 to 7.5 V reverse potential for D1 across R6. You may require different values if the regulated voltage for your oscillator is greater or less than the 9.1 V indicated in Fig 5.

L1 is an adjustable inductor that is wound on the bobbin of an Amidon L-57-6 shielded transformer assembly.[2] The no. 6 (yellow) iron-core material offers good stability in the presence of changing temperatures. No. 2 material (red) has greater permeability (fewer turns needed), but it is less stable than is the no. 6 material. The coil turns are glued in place on the bobbin with a high-quality coil cement, such as General Cement Q-Dope.[8] After L1 is tested and adjusted for the desired frequency range, the coil slug should be locked in place by melting a small piece of beeswax or canning wax onto the end of the coil

---

[1] Notes appear at end of article.



Fig 6—Photographic view of the 40-m VFO in its cabinet with cover removed.

slug. This prevents vibration from moving the slug and changing the oscillator frequency.

C2 is used to set the tuning range of D1. The capacitance of C2 is in series with the capacitance of D1. Therefore, the lower the capacitance of C2, the smaller the frequency spread provided by D1 as R6 is adjusted through its range. In other words, the lower the capacitance at C2, the smaller the effective capacitance change for D1.

NP0 (zero temperature coefficient) ceramic capacitors are used at C1, C3 and C7.[3] Polystyrene capacitors are indicated at C4 and C5, but NP0 units can be used instead. I used polystyrene capacitors because they are quite stable with temperature changes. Also, I did not have a pair of 680-pF NP0 units on hand when I built this VFO. Silver-mica capacitors can be used at C1, C3, C4, C5 and C7 if necessary. You may find that silver-mica units exhibit positive *or* negative drift characteristics, however. Best VFO stability will result if you experiment with these capacitors by trying various units of the same value at each critical circuit point. That is, like-value capacitors of the same brand will often exhibit different drift characteristics with respect to internal heating. For this reason, most homemade highly stable VFOs are practically tailor-made with respect to the final choice of fixed-value capacitors in the oscillator circuit.

D2 of Fig 5 regulates the oscillator operating voltage, and ensures a regulated voltage for the D1 tuning circuit. The regulated voltage also stabilizes the forward bias for amplifier Q3, and helps prevent load changes at the oscillator output that would otherwise be reflected by Q3 if the forward bias were allowed to vary.

Q3 is lightly coupled to the emitter of Q1. This also reduces the loading effect of the amplifier. R9 is included as a parasitic suppressor for Q3. If unwanted VHF oscillations are allowed to develop, they will appear at the output of Q3. VHF parasitic oscillations can cause spurious responses in a receiver or transmitter, or cause TVI.

A broadband pi network is used at the output of Q3. It is designed for a Q_L of 3 to ensure a constant output across the VFO tuning range. The network is designed for a 1:1 transformation ratio. R13 sets the collector impedance of Q3. The VFO output impedance (approx 500 ohms) is suitable for interfacing with a class-A bipolar RF amplifier or the 500-ohm input terminal of a mixer IC, such as a CA3028A.

Peak-to-peak output from the circuit of Fig 5 is 3 V across a 470-ohm resistor. This equates to 1.06 V RMS and an output power of 2.4 mW. Greater output power may be obtained by changing R11 to 100 ohms. This provides 5 V P-P or 1.76 V RMS for an output power of 6.6 mW. If greater output power is needed, you may add an RF power amplifier after Q3. A 2N2222A is a good transistor for this purpose. Suitable RF amplifier circuits are presented in *Solid State Design for the Radio Amateur*.[4]

VFO Offset Circuit

Because of the heating of the D1 junction when operating voltage is first applied, you will notice a short-term frequency change of approximately 300 Hz. The VFO settles down and commences its long term drift after about 30 seconds. Because of this, the VFO should remain operating at all times when it is used with a transmitter. R15 of Fig 5 is shown as part of a frequency-offset circuit. During the receive period you may shift the VFO frequency away from the frequency you are listening to by grounding R15. A mechanical or solid-state switch in your TR circuit may be used for this purpose. The amount of frequency offset is determined by the value of R15. If the VFO is used in a D-C transceiver, you may ignore the offset provision—the VFO will be operating at all times.

Drift and Output Waveform

I measured the VFO drift at room temperature (72 °F) with the cover in place on the VFO cabinet. The initial drift took place in a 30-second spurt. Thereafter, the drift was gradual, and stabilization (±2 Hz) was noted after 10 minutes. The long-term drift was measured as 80 Hz. Do not measure your VFO drift for at least an hour after all soldering on the PC board is completed. The VFO module should be mounted in place and enclosed in a cabinet before measurements commence. Even slight stress on the VFO board will cause frequency changes. Solder a 470- or 560-ohm resistor across J2 before doing your drift checks. Set R6 at midrange before starting the tests.

I examined the output waveform of Q3 with a 50-MHz Tektronix 453A scope. A clean sine wave was observed and the output amplitude remained constant over the 100-kHz tuning range of the VFO. The filtering action of the Q3 pi network aids in laundering the output waveform.

Practical Considerations

Some type of reduction-gear mechanism is desirable for the VFO of Figs 5 and 6. I used a 10-turn potentiometer and counter dial that I bought at a flea market for $3. Various 10-turn controls and dials are currently manufactured, but the cost may be prohibitive. Check the surplus electronics dealers' catalogs for these mechanisms. You may also use an imported reduction gear drive to control the VVC diode tuning control (R6). If you are adept at making plastic or metal pulley wheels, try coupling the R6 tuning shaft to the dial-drive shaft with a rubber O ring and two pulleys. A small wheel driving a large pulley wheel will provide a slow tuning rate for the VFO. Some of the small gear drives with readout dials from WW II surplus transmitters, receivers or tuning units can be adapted easily for use as reduction drives for R6.

A good-quality potentiometer is recommended for use at R5. Select a unit that turns smoothly. Industrial-grade controls of the Allen Bradley type (linear taper) operate smoothly, and they will last a long time.

Fig 6 shows the assembled VFO with the cover removed. The unused space in the



Fig 7—Circuit-board etching pattern for the VVC-tuned 40-m VFO. The pattern is shown full-size from the foil side of the board. Black areas represent unetched copper foil.



Fig 8—Parts-placement guide for the VVC-tuned 40-m VFO. Parts are placed on the nonfoil side of the board; the shaded area represents an X-ray view of the copper pattern.

cabinet will contain the product detector, active filter and audio amplifier for my 40-meter D-C receiver project. I used a Ten-Tec TP-19 cabinet. It measures (HWD) 2 × 4¼ × 4 inches. As supplied, it is a plain-finish aluminum box. I painted the front and rear panels with gray automotive primer. The cover was also painted with primer, followed by a coat of marine blue gloss enamel. Adhesive-backed plastic feet are affixed to the bottom.

Motorola, Inc, manufactures a variety of VVC tuning diodes.[5] Check with them regarding the availability of data sheets for these diodes. My information came from the *Motorola Semiconductor Library*, Vol 3, series A, 1974 edition.

Fig 7 shows a full-size etching template for the VFO. Fig 8 is a parts-placement guide.

In Summary

I have addressed the subject of VVC tuning diodes in simple terms. The nature of these diodes is considerably more complex than this article indicates. However, you should now have sufficient knowledge to permit plenty of experimentation and practical satisfaction. Application notes from the companies that manufacture VVC tuning diodes will give you greater insight into the performance characteristics of these devices. If nothing more, you can save money by using tuning diodes, and your equipment will be much smaller than when using mechanical tuning capacitors.

Notes

[1] Deleted.

[2] Amidon Assoc, Inc, 12033 Otsego St, N Hollywood, CA 91607. Catalog available.

[3] NPO capacitors, silver-mica capacitors and MV2109 VVC diodes (also other VVC diodes) are available from Circuit Specialists, PO Box 3047, Scottsdale, AZ 85257, tel 602-966-0764. Catalog available.

[4] W. Hayward and D. DeMaw, *Solid State Design for the Radio Amateur*, 2nd printing (Newington: ARRL, 1986).

[5] Motorola Semiconductor Products, Inc, Technical Information Center, PO Box 20924, Phoenix, AZ 85036

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.

From January 1989 QST, p 31:

A VFO with Bandspread and Bandset

Eliminate expensive vernier drives and dials with an old technique—bandspread and bandset tuning!

By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250
Luther, MI 49656



Are you old enough to recall those days when we amateurs had receivers that had two readout dials? One was a bandset dial (coarse tuning) and the other was for bandspread (fine tuning). When I compare that method to modern digital-readout techniques, I wonder how we managed to get on frequency; the resolution of the dials was primitive by today's standards! The bandset dial was calibrated in megahertz and the bandspread dial indicated kilohertz. The tuning increments for the bandspread dial were in 5- or 10-kHz steps, depending on the model of the receiver.

We may apply that old technique to modern circuits. Reasonable readout accuracy is possible with the method discussed in this article. The trick is to make both dials read kilohertz, rather than megahertz and kilohertz. The circuit described here is meant to be an inspiration toward a design of your own. It serves as a model for a starting point, with a circuit-board pattern offered if you wish to experiment. My circuit values are for use in a 6.572- to 6.872-MHz VFO. This VFO serves as the local oscillator for a homemade 80-meter CW receiver that uses a 3072-kHz IF and a crystal filter made from low-cost computer crystals. I plan to describe the entire receiver in a subsequent article.

Circuit Features

Please refer to Fig 1, which shows the circuit for my experimental VFO. You will note that I use electronic tuning. D2 and D3 are VVC (voltage variable capacitance) diodes. They are also called varactors or tuning diodes. As the reverse bias (positive voltage) is varied at the diode cathode, there is a significant change in the junction capacitance of the diode. This enables us to change the VFO frequency, as would be the situation if we replaced D2 and D3 with mechanical tuning capacitors. The advantage of using the diodes is that we can use standard carbon-composition controls (R2 and R7 of Fig 1) for tuning the VFO. This provides a compact VFO module, should that be our objective.

D2 functions as the bandset tuning diode, while D3 is used for the bandspread function. Each diode has a trimmer capacitor (C3 and C4) between it and L2. The trimmers are set to control the tuning range of each VVC diode.

All is not "milk and honey" when we use tuning diodes in VFOs. Although the diodes offer some advantages over air-variable capacitors, they are not as frequency stable as mechanical tuning devices. The more semiconductor junctions we add to an oscillator circuit, the greater the opportunity for frequency drift—particularly short-term drift (first five minutes of warm-up). This is because the transistor and diode junctions must come up to operating temperature as current flows through them. This involves both RF and direct currents. The stability of the VFO in Fig 1 is adequate for many amateur needs, such as simple receivers and signal generators. Short-term drift is on the order of 1.5 kHz from a cold start to the period when long-term drift commences. Long-term drift occurs for 15 or 20 minutes, and it amounts to a range of 200-300 Hz. Thereafter, the frequency creeps up and down over a range of 5-10 Hz at room temperature. In other words, the circuit in Fig 1 represents a good VFO, but not a spectacular one. It is on par with what I expected when using two VVC diodes.

Remainder of the VFO Circuit

Q1 of Fig 1 is a 2N4416 JFET. This device surpasses the performance of the generic MPF102 family of transistors. It has a better pinchoff characteristic than does the MPF102 and similar devices. This means that greater output is possible at a given operating voltage, compared to an MPF102. Oscillator feedback is by way of the Q1 source and L1. This link has ¼ the number of turns used on L2, which is pretty standard for a feedback winding. The two coils are wound on an Amidon L-57-6


100 NPO
100 NPO
COARSE RANGE ADJ
FINE RANGE ADJ
100 NPO
2N4416 Q1
D
G
S
CASE
COARSE RANGE ADJ
C1
C2
C15
C3 25
C4 25
C5
R9 150k
D1 1N914
C8 .01
L2
L1
6
1
2
5
D2
D3
R4 100k
R5 100k
0.01 C7
0.01 C6
R1 1.5k
R2 10k
BAND SET
R3 470
10k R7
BAND SPREAD
R6 3.9k
R8 3.9k
100 NPO
2N4400 Q2
R11 33k
R12 12k
C10 0.01
R13 270
FREQ ADJ
C11
R15
100
L3
C12 0.001
TO RX MIXER 5V P-P (100k)
R14 47
C13 0.01
R10 180
9.1 V 400 mW
D4
C14 0.1
+12 V (30 mA)
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000
Q1
D
S
G
CASE
BOTTOM
Q2
C B E
L1, L2
L3
BOTTOM VIEW

Fig 1—Schematic diagram of the VVC-tuned VFO. Fixed-value capacitors are disc ceramic, 50- or 100-V rating. Fixed value resistors are ¼-W carbon composition. NPO notations are for temperature-stable disc capacitors (zero temperature coefficient).

C3, C5—25-pF NPO miniature ceramic trimmer or E. F. Johnson I-9-5 miniature air-variable trimmers.
C15—See text.
D1—Silicon switching diode, type 1N914 or equiv.
D2, D3—Motorola MV2109 tuning diode or equiv, 30-70 pF typical range. Available from All-Electronics Corp, Van Nuys, CA 91408.
D4—9.1-V, 400-mW Zener diode.
L1—4 turns of no. 30 enam or Litz wire over grounded end of L2. Use Amidon Assoc, Inc L-57-6 shielded assembly.
L2—16 turns of no. 30 enam or Litz wire on L-57-6 bobbin. Use Q-Dope to secure windings (see text).
L3—24 turns of no. 30 enam or Litz wire on the form of an Amidon Assoc L-43-2 shielded assembly. Turns must be scramble-wound to fit on form.
R2, R7—10-kΩ linear-taper carbon-composition control (see text).
R15—See text.

transformer assembly. The no. 6 (yellow) powdered-iron core material is best for VFO service. It is more temperature stable than the other core materials.

NPO temperature-stable capacitors (C1, C2, C5 and C9) are used to aid the stability. D1, from the Q1 gate to ground, stabilizes the bias on Q1 and limits the device transconductance on sine wave peaks. This helps to keep the junction capacitance fairly constant—an aid to stability. A further enhancement to stability is provided by Zener diode D4. It regulates the operating voltage for D2, D3, Q1 and the base of Q2.

Buffer-amplifier Q2 is used to boost the RF output of the oscillator chain to 5 V P-P. The output is designed to look into a 100-kΩ load, which may be gate no. 2 of a dual-gate MOSFET mixer. R15 may be added (3.3 kΩ to 10 kΩ) across L3 (dashed lines in Fig 1) to broaden the response of L2. This will reduce the RF output somewhat.

You may use a lower value of capacitance at C9 if you require lower output from Q2. The smaller the C9 value, the greater the overall VFO stability. In a like manner, the lower the C5 value, the better the stability. C5 needs to be of a large enough value to allow Q1 to oscillate. The Q of the oscillator tank and the specific transconductance of Q1 are determining factors when selecting the C5 value in a VFO of this general type. C5 values as low as 5 pF are usable, especially when L2 has a high value of Q (100 or greater).

Circuit Variations

If you desire greater frequency stability than I mentioned earlier, replace D2 and D3 with small air-variable capacitors. You may use a 100-pF unit in place of D2. The bandspread tuning can then be done with a 15- or 20-pF variable. This calls for the deletion of the VVC diode components, R1 through R8, plus C6 and C7, and of course, D2 and D3.

C15 of Fig 1 is shown in dashed lines. You may add a capacitor at this circuit point if you wish to increase the tuning range of the bandset control. Experiment with the C15 value to obtain the range you need.

Construction in General

Use a single-sided PC board for this project. Double-sided board material increases the VFO drift, owing to the formation of unwanted low-stability capacitance between the PC foil and the ground-plane side of the board. Try to use high quality glass-epoxy board material. Phenolic PC boards are not suitable for VFOs.

I enclosed my VFO in a homemade box, as shown in the title photo. The box is made from pieces of PC board that have been soldered together. The cover, removed for the photograph, is a U-shaped piece of aluminum. The cover is affixed to the box by means of two no. 4-40 screws. I soldered two 4-40 × ¼-inch nuts on the inside of the box to accommodate the two screws. I used two surplus Teflon push-in feedthrough terminals to route the +12 V to the circuit, and to bring the RF output from



Fig 2—Circuit-board etching pattern for the VVC VFO. The pattern is shown full-size from the foil side of the board. Black areas represent unetched copper foil.



Fig 3—Parts-placement guide for the VFO, not to scale. Parts are placed on the nonfoil side of the board; the shaded area represents an X-ray view of the copper pattern. In the interest of stability, do not use double-sided board material and a ground plane. Component outlines are not necessarily representative of the shapes of the actual parts used.

the box. Two no. 6 spade bolts secure the VFO box to the mainframe assembly that will later contain the remainder of my 80-meter receiver. The hookup-wire cables for tuning controls R2 and R7 are brought from the VFO box through ¼-inch holes in the box wall. The VFO module measures (HWD) 2 × 2 × 2½ inches.

A scale etching pattern for the VFO PC board is provided in Fig 2. A parts-placement guide is shown in Fig 3.[1]

The dial-calibration plate for my VFO is homemade, visible on edge in the title-page photograph. I drew the circles with a ballpoint pen and compass. I use knobs with large skirts (2 inches OD), bought at a flea market. If you can't locate a pair of large knobs with skirts, you may use standard-size knobs and metal or plastic dial skirts with them. The skirts may be attached to the knobs by means of epoxy cement or small screws.

After I made the dial plate I photocopied it. The copy was used for dial calibration with a pencil. I measured the VFO output with a frequency counter. My VFO is set for 50 kHz of tuning range with the bandset control. The bandspread covers only 10 kHz. Midrange on the bandspread control is marked zero. To the left of zero I calibrated this dial with minus kHz marks. Plus-kHz marks are to the right of zero. After plotting the calibration scales I made marks between the two rings of each dial face, then typed the frequencies alongside the marks. Rubber cement is used to affix the dial plate to the front panel.

Try to obtain commercial-grade controls for R2 and R7 of Fig 1, such as Allen-Bradley units. They will last longer than imported controls, and will be less prone to resistive instability from shock and vibration. Check the surplus catalogs for these controls.

Checkout and Operation

You will need to adjust the slug in L2, along with the settings for C3 and C4. First, determine how much frequency range you want to cover with the bandset control. Adjust C3 and L2 so R2 provides the desired range. Next, adjust C4 to yield 10 kHz of tuning range for R7. This will cause some interaction with the settings of C3 and L2. Repeat those adjustments to obtain the desired tuning range for R2.

Next, terminate C12 with a 100-kΩ resistor. Connect a scope or RF probe from the output side of C12 to ground. Adjust the slug in L3 for maximum RF output voltage.

L1 and L2 should be coated with GC polystyrene Q-Dope after they are wound on the L-57-6 bobbin. Allow at least 48 hours for the coil to dry before you check the stability of your VFO. Q-Dope is available by mail from Small Parts Center.[2] Do not attempt drift tests if you have recently soldered connections on the VFO PC board. Allow an hour after all soldering is completed before you commence your drift run. Keep the module away from desk or bench lamps and enclose the VFO PC board in its box to prevent air currents from reaching the critical components. Terminate the VFO output with a 100-kΩ resistor and attach a frequency counter to the VFO output through a 27- or 33-pF capacitor. Apply the VFO operating voltage and log the initial frequency. Monitor the frequency change until the drift is only 1 or 2 Hz per count. Observe the frequency change until it stabilizes. This will be noted when the frequency shifts up and down by a few hertz in a random manner. Dial calibration (discussed earlier) should be done *after* the short-term drift has occurred. This should take place within five minutes after turn-on.

Closing Comments

I want to stress that this is an "idea" article rather than a project for duplication. The main thought here is that you can capitalize on the old technique of using a bandset and bandspread setup in order to avoid the high cost of vernier mechanisms. Tuning diodes are discussed in the interest of equipment miniaturization and reduced cost.

This VFO is not recommended for use with transmitters unless one or more additional stages of buffering are used. A single buffer-amplifier does not provide the load isolation that is necessary between the VFO and a transmitter. It is adequate, however, for connection to a mixer that presents a relatively constant load impedance.

You should have no difficulty in tailoring this circuit to other frequencies. All that is necessary is to change the inductance of L2 and L3, along with appropriate modifications for the values of C1, C2, C5, C9 and C11. I'm sure you will have fun experimenting with this circuit, and you can learn by doing!

For updated supplier addesses, see ARRL Parts Suppliers List in Chapter 2.

[1] Far Circuits (N9ATW), 18N640 Field Court, Dundee, IL 60118; tel 312-426-2431 evenings.

[2] Small Parts Center, 6818 Moose Drive, Lansing, MI 48911; tel 517-882-6447. Catalog available.

From September 1978 QST, p 15:

Meet the Remarkable but Little-Known Vackar VFO!

Searching for a VFO with Rock of Gibraltar stability? End your band-edge worries with this self-contained unit. For the serious-minded cw operator, the chirp-free operation and undetectable frequency drift make this VFO a natural!

By Floyd E. Carter,* K6BSU

The dedicated cw operator must make severe demands of his station equipment. He knows that an elusive DX station amateur cannot be asked to tolerate a signal which drifts through the passband of his receiver or one which has keying chirp. For the cw man, his fist and the note of his transmitter form his "voice" to distant stations. Modern electronic keyers have made machine-like keying an inexpensive reality. Couple a keyer with a fine-quality VFO, and the DX station operator just cannot refuse to QSO.

In designing this heterodyne VFO, the goal was to produce a keyed oscillator with undetectable chirp or frequency drift. Keying of a conventional VFO invariably produces some instability because the starting and stopping of an oscillator upsets the fine balance of dc and ac conditions within the circuit, and with each key-down transition oscillation equilibrium must be reached. During this transient period, the oscillation frequency generally changes, resulting in chirp. Keying of a subsequent buffer stage following a free-running VFO generally allows a small portion of the VFO output to reach the receiver during key-up conditions if the station is set up for full-break-in cw. VFO shielding only reduces the feedthrough, but this may not be adequate for very sensitive station receivers.

Heterodyne-frequency generation eliminates all these problems because the VFO operates continuously on a non-harmonically related frequency which is converted to the operating frequency in a mixer or balanced modulator. Both the keyed crystal oscillator and the VFO operate far from the receiver frequency. Therefore, even though the VFO is not keyed, no harmonic of the oscillator will reach the receiver. Fig. 1 shows the block diagram of the heterodyne process, with frequency values applicable to this VFO.





The Vackar oscillator VFO enclosed in an attractive, contemporary-styled cabinet. Below is an inside view showing rather high component density. The U3 output amplifier is on a separate board next to the transformer.

Fig. 1 — Simplified block diagram of the heterodyne VFO.



*2029 Crist Dr., Los Altos, CA 94022


+8V
RFC2 1mH
C17 0.01
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k=1000, M=1000 000
R32 120k
C15 500 S.M.
R11 470
R15 1000
C18 0.01
R17 12k
C42 1200 S.M.
Q3 2N3640
Q4 2N3638
R16 470
C14 4.5-25pF
Y1 3000 kHz
C19 51 S.M.
L2
R12 270k
R13 1000
Q6 2N3646
C16 0.022
R10 2200
R9 33k
Q5 2N3646
R14 15k
R18 2700
J1 KEY
OPER.
SPOT
S2A
BAL. MIXER
+8V
C22 0.01
C23 0.01
R19 470
C20 0.01
R20 470
C21 0.01
U1 SG3402
C25 56 S.M.
C24 0.01
R21 50k CARRIER BAL.
R3 100
RFC1 1mH
+8V
C9 0.01
VACKAR VFO 4000-4100 kHz
R2 22k
R4 390
R6 100
Q2 2N3014
*R7 220
C12 0.01
C13 20 S.M.
L1
C4 56 S.M.
Q1 2N3014 2N2222
C10 0.01
C11 1µF 50V
C6 820 S.M.
C1
C2 15 S.M.
C3 45-25
C5 680 S.M.
R1 4700
R5 100
C7 0.001
C8 0.1
R8 1000
S.M.=SILVER MICA

Fig. 2 — Schematic diagram of the heterodyne-oscillator VFO using the Vackar circuit. All resistors are ¼-watt, five-percent tolerance. U1 is a proprietary product manufactured by Silicon General, Inc., 7382 Bolsa Ave., Westminster, CA 92683. The toroid core for L2, Ferroxcube no. 1041T060/4C4, is produced by the Ferroxcube Corp., Mt. Marion Rd., Saugerties, NY 12477. (For the convenience of builders who are unable to locate small toroids the author has available a limited supply.) For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.

A normal mixer or unbalanced modulator output contains four prominent frequency components — the two input frequencies, their sum, and their difference. Either the sum or the difference may be used as an output by selecting the desired frequency in a band-pass filter. The balanced mixer is a more sophisticated refinement of the basic mixer circuit, because the two input frequencies are eliminated in the mixing process so that the output contains only the sum and difference frequencies. Consequently, subsequent filtering is made easier.

The VFO circuit used in the heterodyne VFO was first described by Vackar[1] in 1949. This circuit formed the basis for further research by Clapp, resulting in his classic article published in 1954.[2] The Vackar circuit closely resembles the Clapp circuit except for the method of feedback. The Vackar is series tuned like the Clapp, but the tank circuit as well as the transistor are shunted by unusually low reactances which reduce the effects of the transistor reactances. Further refinements of the Vackar circuit were described in 1968 by Jordan,[3] who provides design criteria for use at any frequency.

Construction

The photographs suggest one possible layout. For ease of modification and experimentation, the prototype was built in separate modular form equipped with connectors. Only a few precautions must be kept in mind when designing a layout. First, as with any VFO, mechanical stability is essential. An aluminum extrusion was used as a base for the oscillator. The tank components were bolted to this extrusion and the remainder of the circuit is contained on a glass-epoxy-board bolted to one lip of the extrusion. Heavy solid wire is used to interconnect the tank circuit components to prevent changes in stray circuit capacitance from shock or vibration. The integrated circuits have much higher bandwidths than required, and are capable of oscillations at vhf.

---

[1] Notes appear at end of article.



C1 — Variable capacitor, approximately 2 pF (1 rotor and 1 stator).
C3, C14 — 4.5-25 pF variable capacitor, CRL no. 825-AZ.
C7, C39 — Fixed capacitor, 0.001 µF, CRL no. CE102.
C8 — Fixed capacitor, 0.1 µF, CRL no. DDA104.
C9, C10, C12, C17, C18, C20-C24, incl., C30, C31, C33, C35, C36, C37 — Fixed capacitor, 0.01 µF, CRL no. CK103.
C16 — Mylar fixed capacitor, 0.022 µF, CDE no. 1S22.
C40 — Fixed capacitor, 1000 µF 25 V dc, CDE no. HWM 1000-25. (Fig. 3)
C41 — Fixed capacitor, 500 µF, 15 V dc, CDE no. HWM 500-15. (Fig. 3)
D1 — Silicon voltage regulator diode, 8.2 V, 400 mW, Texas Instrument no. 1N756A or equiv. (Fig. 3)
J1 — 1/4-inch phone jack, Switchcraft no. 11.
J2 — Chassis rf jack, Switchcraft no. 3505F.
L1 — 19 µH, 31 turns No. 22, enameled copper wire, 7/8 inch long, 1 inch diameter. Ceramic form, National no. XR-50.
L2 — Toroid core, Ferroxcube no. 1041T060/4C4, approximately 50 turns no. 28 enameled copper wire.
L3 — Miller no. 42A000CB1-2, 26 turns no. 24 enameled copper wire.
L4 — Miller no. 40A000CB1-2, primary 26 turns no. 28 enameled copper wire, 3/8 inch long; secondary 12 turns no. 28 enameled copper wire.
Q1 — Npn silicon annular transistor, type 2N918 or equiv.
Q2, Q7 — Npn silicon annular transistor, type 2N3014 or equiv.
Q3 — Pnp silicon low-power transistor, type 2N3640 or equiv.
Q4 — Pnp silicon high-current switching transistor, type 2N3638 or equiv.
Q5, Q6 — Npn silicon low-power transistor, National Semiconductor type 2N3646 or equiv.
Q8 — Npn silicon annular transistor, type 2N697. (Fig. 3)
S1 — Spdt toggle switch, Alco no. MST-105D.
S2 — Dpdt toggle switch, Alco MST-205N.
U1 — Variable gain, wideband amplifier/multiplier, Silicon General no. SG3402.
U2, U3— Linear IC, monolithic rf i-f amplifier, Fairchild no. 703E.
U4 — Silicon miniature diode assembly, Motorola MDA 950-2 or equiv. (Fig. 3)
Y1 — Oscillator crystal, 3000 kHz. Sources listed in *QST* advertisements.

Therefore the bypass capacitors should be mounted close to the IC with short leads. The planetary ball reduction gear couples the tuning capacitor to the tuning knob. This is not an ideal setup for it is not possible to calibrate the dial because the ball drive slips at the end of travel. However, accurate calibration of a VFO is not a great advantage, inasmuch as crystal band-edge markers are required if one is going to operate within striking distance of a pink slip.

Test and Adjustment

The only tuned circuit which is not adjustable is the 3-MHz band-pass filter consisting of L2 and C19. This should be resonated with a grid-dip meter after first overwinding the toroid core and removing turns one at a time until the circuit resonates. This circuit removes harmonics from the crystal oscillator and helps to reduce spurious inputs to the balanced modulator.

With the VFO operating and keyed, the output of U1 should be monitored while adjusting R21, the carrier-balance potentiometer, for a null at both 3 MHz and 4 MHz. The null should occur simultaneously. Next, monitor the output of J2 through a length of coaxial cable terminated in the transmitter. The cable is necessary because the cable capacitance is reflected back into the circuit for L4 and C38 and forms part of the total tuning capacitance. Adjust L3 and L4 for maximum drive to the transmitter. While rapidly keying the crystal oscillator, adjust C14 for the best starting characteristics. Finally, C1 is adjusted to cover the spread of 4.0 to 4.1 MHz. Adjustment is made with C3 and by bending the plates of C1 for the desired delta C for full rotation.

If a spectrum analyzer is available, the optimum tuning may be quickly reached for maximum rejection of unwanted frequency components. The prototype circuit had all unwanted components down by at least 40 dB. With key up, the VFO feedthrough at 4 MHz was down 30 dB. This level is not detectable with the station receiver and tuned circuits in the driven transmitter will reject these components.

With S2 in the SPOT position, power is removed from the output buffer amplifier and the crystal oscillator is keyed. This



Fig. 3 — Power supply for the heterocyne VFO. Miniature diode assembly U4 is Motorola part no. MDA.950-2 or equiv.



The Vackar oscillator circuit is constructed on a heavy extrusion. Large bus wire interconnects tuned circuit components. L1 is wound on a ceramic form and coated with epoxy resin. C1 is a heavy-duty two-bearing capacitor reduced to one rotor and one stator plate.



Crystal oscillator and balanced mixer board. The oscillator is a highly modified International AO1 assembly. The small toroid coil on the oscillator board is L2. The balanced mixer (10-lead IC) is on the main board. U2 and Q6 are at far left. As is typical with developmental circuits, the board shows evidence of modifications.

generates a weak signal which can be monitored in the station receiver for frequency spotting. In the OPERATE position, control is transferred to the keyer. Any commercial keyer with an open-collector, current-sinking output will work with this VFO. If there is doubt in one's mind about this feature of a particular keyer, the schematic diagram of the keyer should be examined, or the manufacturer should be consulted. Of course, a relay output will also work with the VFO

The normal output of the heterodyne VFO is about 20 mW into a load of 75 ohms. The driven transmitter operates straight through on 40 meters for outputs of 7.0-7.1 MHz. Using the driven transmitter as a multiplier, 20-meter output from 14.0-14.2 or 10-meter output from 28.0-28.4 MHz is available. The driven transmitter must also be provided with fixed bias to prevent excessive dissipation in the final amplifier under key-up conditions. For transmitters with cathode or emitter keying, fixed bias should be added to cut off the final amplifier during key-up conditions.

The heterodyne VFO has been in use with a Viking-II transmitter with the station set up for full break-in cw operation. It is the only VFO I have ever used where operation very close to the band edges in the Extra Class portion is possible without constant nervous strain from wondering just where the transmitted frequency will end up after a long QSO.

References

[1]Vackar, "LC Oscillators and Their Frequency Stability," *Tesla Technical Reports* (Czechoslovakia) Dec., 1949.

[2]Clapp, "Frequency Stable LC Oscillators," *Proc. IRE.*, Aug., 1954, pp. 1295-1300.

[3]Jordan, "The Vackar VFO: A Design To Try," *Electronic Engineer*, Feb., 1968.

From April 1989 QST, p 38:

Adjusting the Power Output of JFET VFOs

☐ The output of a JFET VFO is determined largely by the device standing current—the JFET's drain current with dc bias applied and ac feedback removed. In many VFO designs, this is equivalent to I_{DSS}—the zero-gate-voltage drain current. Generally, the relationship between I_{DSS} and oscillator output is simple: The higher the device I_{DSS}, the greater the VFO output.

According to the *Motorola Small-Signal Transistor Data* book, I_{DSS} for the popular MPF102 can fall anywhere within the wide range of 2 to 20 mA. This wide I_{DSS} specification explains why some VFO builders have good luck with the MPF102 and others build MPF102 VFOs that deliver less output than that claimed for the circuit involved. The "premium" 2N4416 has an I_{DSS} range of 5 to 15 mA, making the '4416 generally better than the MPF102 if you want more power output. The best commonly available JFET for lots of VFO output is the 2N5486, which has an I_{DSS} range of 8 to 20 mA.

It's important to keep another rule of thumb in mind: Oscillator frequency stability generally *decreases* as power output increases. If you're willing to sacrifice VFO output for greater frequency stability, the 2N5484 (I_{DSS} of 1 to 5 mA) and 2N5485 (I_{DSS} of 4 to 10 mA) are good choices.

By the way, the resistance of the JFET channel is a good relative indicator of device I_{DSS}. With this in mind, you can grade your JFETs for VFO power output merely by measuring their channel resistance (source to drain) with a DMM. (Caution: The measuring instrument you use must not apply a destructively large current to the device under test.) Generally, the lower the channel resistance of a given device, the more power output it will furnish as a VFO.—*Zack Lau, KH6CP, ARRL Laboratory Engineer*

From April 1979 QST, p 18:

Putting the Boots to Your HW-8 QRP Transceiver

Basic Amateur Radio: A signal increase of 9 dB for your QRP rig can turn marginal QSOs into solid ones! This amplifier provides 80- through 15-meter signal increases with only 1 watt of drive. Add these "boots" to your HW-8 and improve your QRP DX score.

By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250
Luther, MI 49656

An article describing a single-ended plug-in amplifier for the HW-7 series QRP transceiver left much to be desired for some *QST* readers.[1] ARRL hq. was hit with a rash of letters requesting a band-switching style of amplifier which included the 80-meter band along with the 40-, 20- and 15-meter bands. Coverage on 80 meters was inspired by the appearance of Heath's newer QRP box, the HW-8. The additional cost of single-band amplifiers over a band-switching unit was objectionable to some, and rightly so. Moreover, some builders reported problems with amplifier instability when they assembled the "Slippers" unit. The amplifier described here is aimed at HW-8 owners in particular. However, it can be used with any QRP transmitter if the latter has the output attenuated so that a maximum of 1 watt reaches the power amplifier input. It is a simple matter to install an appropriate T or pi type of resistive attenuator at the amplifier input when more driving power than is necessary appears at the output of the QRP transmitter.

This amplifier operates from a 12- to 14-volt dc supply. Maximum current drain is less than 2 amperes. A spectral analysis of the amplifier output indicated that it complies with the FCC requirement that all spurious energy be 40 dB or greater below peak carrier value. The spurious components are −45 dB or better on each of the bands covered by this circuit. A host of in-band spurs were observed at levels well below −40 dB. They are products generated within the HW-8 and do not originate in the amplifier described here.

Circuit Description

A pair of RCA 40977 stud-mount power transistors are shown in the circuit of Fig. 1. These are actually vhf devices and are used primarily because they were on hand at the time this circuit was developed. Later, RCA dropped this part from its line. Transistors with similar characteristics for hf-band operation may be used in place of the 40977, notably the Motorola 2N5642 which is an exact replacement. The specifications for the 40977 are 11 dB gain (approximate) at 118 MHz: Look for a substitute which has similar gain at 21 or 30 MHz. Maximum power dissipation is 25 watts. Power input is 0.5 watt (approximate) for 6 watts minimum output. Collector supply voltage is 12.5 nominal. Continuous collector current rating (maximum) is 5 A. Collector efficiency is 55 percent. The builder should not be afraid to experiment with other types of power transistors, especially if they can be obtained inexpensively as surplus from a reliable dealer.

This circuit operates broadband in the Class C mode. This technique simplifies band switching and lowers the cost. To ensure unconditional amplifier stability it is necessary to use shunt feedback from collector to base (R1, R2, C1, C2, L1 and L2). Broadbanding and stabilization of this type always results in a power trade-off. In a similar circuit which used no feedback, the amplifier output could be as great as 15 watts, safely, even though the 40977s are rated at a nominal output of 6 watts each at 118 MHz. With the feedback networks shown, the output is approximately 12 watts on 80, 40 and 20 meters. Somewhat less output is available on 15 meters, owing to the lower output from the HW-8 on that band.

A pair of 10-ohm resistors and two miniature ferrite beads are connected from the transistor bases to ground. These components are used to discourage low-frequency oscillations. The 4-dB attenuator at the amplifier input reduces the HW-8 drive to a safe level. It is suggested that a switch be added to remove the pad during operation on 21 MHz. This will provide an amplifier output of roughly 8 watts on that band. The power output is on the order of 4 watts with the pad in the line.

Two 220-pF silver-mica capacitors are used in the collector circuit to prevent vhf self-oscillations and to lower the harmonic energy in the vhf range. The reactance of the capacitors is high enough in the hf bands to have minor effect on the amplifier power.

T1 of Fig. 1 is a broadband transformer with a 3:1 turns ratio. The transformer used in this design is homemade and is of the *conventional* variety (not a transmission-line transformer). Detailed information of the construction of this transformer is presented in the *ARRL Electronics Data Book* and in *Solid State Design for the Radio Amateur*. T1 consists of two rows of four Amidon FT-50-43 ferrite toroid cores ($\mu = 950$) through which thin-wall brass tubing is

---

[1] Notes appear at end of article.



EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k=1000, M=1000 000.

Fig. 1 — Schematic diagram of the solid-state four-band amplifier. Resistors are 1/2-watt composition types. Capacitors are disk or chip ceramic except the one with polarity marked, which is electrolytic or tantalum. S.M. is silver mica. Components with numbers which do not appear in the parts list are so identified for text discussion only.

J1, J2 — Panel-mount coaxial connector or phono jack.
L1, L2 — Miniature ferrite bead (950 mu) over lead of 0.01-µF capacitor. Same type of beads used on pigtails of 10-ohm base resistors.
Q1, Q2 — RCA transistor (see text).
S1 — Two-pole, four-position ceramic or phenolic wafer switch (see text).
T1 — Broadband 3:1 transformer (see text).
T2 — Bifilar-wound broadband phase-reversing transformer with 8 bifilar turns of no. 22 enam. wire on two stacked FT-50-43 cores (950 mu). Wires have 8 twists per inch.
T3 — Broadband combiner transformer with 8 bifilar turns of no. 22 enam. wire, 8 twists per inch, on stacked FT-50-43 toroid cores.
RFC1 — Toroidal rf choke, 7 turns no. 22 enam. wire on FT-50-43 toroid core.



Inside the amplifier, with the filter board at right, amplifier board at left. The two power transistors are mounted against the rear panel, which serves as a heat sink.

passed and made common at one end (U-shaped single turn, in effect). Then, three turns of insulated wire are passed through the tubing to form the transformer primary. Pc-board headers are used at each end of the assembly to secure the tubing and provide copper tabs for connection to the main circuit board. The advantage in using this type of transformer is that a more precise secondary center tap can be established than is possible with a simple toroidal broadband transformer. Symmetry of the secondary helps to assure equal driving power to each transistor. Those wishing to experiment with a toroidal type of transformer at T1 can wind 9 turns of no. 28 enameled wire on an FT-50-43 core. A three-turn center-tapped secondary winding can be wound over the nine-turn primary. The tap must be in the *exact* center. The leads to the transistor bases should be laid out symmetrically and have equal lengths.

T2 is a phase-reversal transformer that places the collectors of Q1 and Q2 in push pull. The collector voltage is supplied through T2. A combiner transformer, T3, provides a 28-ohm output impedance from the two 14-ohm collectors. Half-wave harmonic filters (FL1-FL4, inclusive) are band switched at the amplifier output by means of S1. They are designed for a loaded Q of 1. The input impedance is 28 ohms and the output impedance is 50 ohms. Since these are low-pass filters, the cutoff frequency is set slightly above each amateur band to minimize insertion loss. Amidon powdered-iron toroid cores are used for the filter inductors.

Construction Notes

Double-sided pc board is used for the amplifier module, but single-sided board is specified for the filter assembly to reduce stray capacitance. The later could degrade the filters by virtue of detuning effects.

Double-sided board material is used for the amplifier circuit to help eliminate ground loops and subsequently improve stability. The ground returns for the input components which relate to the transistor bases are connected to floating pads on the etched side of the board. Small pieces of wire connect those pads to the ground-plane surface on the opposite side of the board. Conversely, the collector components have their ground connections on the *etched* side of the board. This procedure helps to ensure stability by breaking up rf current loops on the ground elements of the pc board. Fig. 2 shows the pc-board pattern for the amplifier. Fig. 3 contains the layout for the filter board.

The photograph shows the collector-base feedback networks being bridged in mid-air over the tops of Q1 and Q2. The board pattern provides copper pads for these components. Also, the prototype version shown photographically has the transistor strip leads bent down slightly to mate with the related pc pads. This mounting technique is not recommended. Two unfavorable conditions can result from this method: Excessive emitter-lead length introduces unwanted inductance, which in turn causes degenerative feedback. Degeneration lowers the amplifier gain and may encourage instability. Fur-



Fig. 2 — Parts placement guide for the amplifier board. Parts are mounted on the etched side of the double-sided pc board; the shaded area in this view represents the copper pattern. The other side of the board is unetched. Decimal-value numbers alone represent capacitance in microfarads. Whole-number values without units represent resistance in ohms. Note that ferrite beads are slipped over one end of each of the two 10-ohm resistors.

thermore, when the leads are bent up or down to mate with the pc board it is possible for undue stress to be exerted on the transistor body during heat cycling. This can cause physical damage to the transistors. The correct mounting procedure calls for the strip leads to come out from the transistor body at 90 degrees. They lie flat on the pc board pads to which they are soldered.[2]

The amplifier board is mounted against the rear wall of the U-shaped homemade chassis. The case serves as a heat sink. Heat transfer is enhanced by the addition of transistor silicone grease. It is applied to the mating surfaces of the transistors and cabinet. The stud nuts should be tightened only slightly beyond a finger-tight tension level. This will prevent damage to the transistors. Through-wires are added at several points on the amplifier board to join the ground foils on both sides of the board. Each through-wire is soldered to the pc board at both ends.

The Filter Module

Table 1 contains L, C and frequency data for the four filters. For the most part, standard-value silver-mica capacitors are not specified. This requires combining standard values in order to arrive at values which are close to those specified. Mica compression trimmers can be used at the center of each filter (see photograph) if desired. The author's model has the trimmers for final tweaking to obtain maximum output power and waveform purity.

RG-174/U miniature coaxial cable is used for the rf leads. It is important to ground the shield braids at both ends of the cables which connect to the amplifier output, antenna jack (J2) and the two poles of S1. The remainder of the coaxial cables need to have the shields grounded only at the filter-board end. In the model shown, heat-shrink tubing is used at the ungrounded ends of the connecting cables. S1 should be a two-wafer type with at least one inch (25.4 mm) of distance between the wafers. This will ensure proper isolation between the filter inputs and outputs. For ideal conditions, a metal shield could even be installed between the wafer sections and bolted to chassis ground.

Operation

The power supply which Heath provides for the HW-8 will not be suitable for this amplifier. A regulated power supply of 2 amperes or greater is required.

The 40977 transistors are "SWR

Fig. 3 — Parts placement guide for the single-sided filter board showing details for one filter. Parts are mounted on the foil side of the board; the shaded area in this view represents copper.





Table 1

Band	f_{CO} (MHz)	L1 (μH)	L2 (μH)	C1 (pF)	C2 (pF)	C3, C4 (pF)	Toroid Core	Turns	Wire Size
15	23	0.26	035	230	210	138	T68-6	L1-7 TS L2-10 TS	no. 22
20	16	0.38	05	330	300	200	T68-6	L1-10 TS L2-10 TS	no. 22
40	8	0.76	10	663	600	400	T68-2	L1-11 TS L2-13 TS	no. 22
80	5	1.2	16	1000	965	636	T68-2	L1-14 TS L2-17 TS	no. 22

Coil and capacitor information for the half-wave harmonic filters shown in Fig. 1. All capacitors are silver-mica units. Parallel or series combinations can be used as needed to provide the approximate values listed above. An accuracy of ± 10 percent is recommended. *A mica compression trimmer can be used as C3 to provide final adjustment of the filters.

protected," to use the RCA vernacular. This means that anything from a dead short to a full open circuit can be tolerated at the amplifier output for short periods of time without causing device damage. A *maximum* mismatch period of 30 seconds is recommended.

The harmonic filters are designed for a 50-ohm termination. Therefore the antenna should not present an SWR of greater than 1.5:1, or filter performance will be impaired. Also, there will be a loss in output power when the SWR is high. A Transmatch and SWR indicator are recommended for use with any solid-state amplifier, including this one, particularly when the antenna does not present a 50-ohm load.

This amplifier will reach its saturated output-power level at slightly under 1 watt of drive at the bases of Q1 and Q2. Observe the increase in forward power to the antenna, then add no further drive once the point is reached where power output from the amplifier levels off.

Now that you've "put the boots to your HW-8," have fun and go after that DX you were reluctant to call with only 2 watts!

Footnotes

DeMaw, "Slippers for the HW-7," *QST*, Dec. 197 p. 45.

[2] Artigo and Johnson, "Fundamentals of Solid-State Power-Amplifier Design," *QST*, Sept. and Nov. 1972, and *QST*, April 1973 (in three parts).



Circuit-board etching patterns. The front sides of the boards are shown here at actual size, with black representing unetched copper. The upper pattern is for the amplifier section (Fig 2); it is copper clad on both sides, with unetched copper on the "back" side that forms a ground plane. The lower pattern is for the filter board (see Fig 3).

From May 1984 QST, p 44:

30-Meter Conversion For The HW-8

☐ The Heath HW-8 QRP transceiver can be modified easily to operate on 30 meters if you are willing to sacrifice one of the existing bands. I chose to give up the 80-meter band, since I have found it to be the most demanding one, in terms of antenna size, for QRP operation. Thirty meters seems to be an excellent band for QRP operation, and it offers the side benefit of WWV reception, which I use to calibrate my VFO dial.

Complete details of the modification are summarized in Table 1. The only expensive component is the crystal, which costs around $10. The other components can be found in your junk box or purchased from a variety of *QST* advertisers. Five of the original capacitors are reused in other locations.

Remove the control knobs and front panel; then, disconnect the loading capacitor from the front of the chassis. This will make it easier to get at the components to be changed in the crowded area around SW1 (the 80-meter band switch). Remove the indicated components using a vacuum desoldering tool, solder wick or a piece of flattened braid from coaxial cable.

After the new components have been installed, the rig can be aligned according to the instructions in the HW-8 assembly manual. The only problem I encountered was that I had lost the small tuning tool used to adjust L17 in the heterodyne oscillator. I found that the larger tool or even an Allen wrench can be used. Carefully insert the tool through the top slug and tune the bottom slug for maximum output on 30 meters. Then, back the tool out and readjust the top slug (L18) for maximum output on 40 meters.

The transmitter dc power input should be about 3 W. The VFO will cover 10.0 to 10.25 MHz. Dial accuracy seems to be a problem with the HW-8, so it may be difficult to determine the band edges without a frequency counter. This is where WWV can assist you. Just be sure to stay within the legal segments (10.100-10.109 and 10.115-10.150 MHz). If in doubt, don't transmit. —*Wayne Burdick, N6KR, 7904 Caminito Dia #2, San Diego, CA 92122*

Table 1

HW-8 30-Meter Modifications[†]

Part No.	*New Value*	*Description*
Y1	18.895 MHz	Fundamental type, 15-pF load, HC-6/U holder. International Crystal Mfg. Co., P.O. Box 26330, Oklahoma City, OK 73126. Part no. 434112.
L1	1.8 µH	Secondary — 25 turns no. 24 enameled wire on T37-6 core (Amidon Associates, 12033 Otsego St., N. Hollywood, CA 91607). Primary — 2 turns no. 24 wire over C2 end of secondary (use original coil form).
L5	1.8 µH	25 turns no. 24 wire on a T37-6 core.
L13	4.0 µH	Remove 16 turns from original L13.
L22	2.7 µH	23 turns no. 22 wire on a T50-2 core.
L26, L27	3.2 µH	25 turns no. 22 wire on a T50-2 core.
C1	100 pF	Silver mica, 5% tolerance (use original C116).
C15, C96	100 pF	Silver mica, 5% tolerance.
C64	68 pF	Silver mica, 5% tolerance (use original C1)
C77	230 pF	Silver mica, 5% tolerance (use original C64).
C78	150 pF	Silver mica, 5% tolerance (use original C96).
C94	47 pF	Silver mica, 5% tolerance (use original C15).
C97	300 pF	Silver mica, 5% tolerance.
C116	30 pF	Silver mica, 5% tolerance.
C301A	—	Disconnect from L1.
R50	—	Remove.
R56	1 kΩ	½ W, 10% tolerance.

[†] Refer to HW-8 schematic diagram for part locations.

From April 1988 QST, p 26:

Improving the HW-9 Transceiver

If you own an HW-9 or other QRP transceiver, you'll find these ideas will add to your operating enjoyment. So, heat up that soldering iron!

By Chuck Hutchinson, K8CH and Zack Lau, KH6CP
ARRL Technical Department

This article is divided into two parts. In the first part Chuck, K8CH, describes the portable QRP station that he uses for Field Day and vacation operating. The second part describes circuit modifications by Zack, KH6CP. Although the ideas presented concentrate on using and improving the Heath HW-9, they can be adapted to many QRP rigs.

Chuck's QRP Package

I enjoy chasing DX with QRP—most of the time. But Field Day and vacation are two times when QRP operation is particularly appropriate and rewarding. I'm not averse to running 100 watts (or even the legal limit when conditions warrant), but my entire QRP station with transceiver, power supply, antenna, keyer and other accessories is about the same size and weight as my 100-W, full-feature transceiver. That means it's a lot easier for me to take the QRP station to the Field Day site. As for vacation, only the QRP rig will fit into the car along with the rest of the family luggage.

I use two 9-Ah gelled-electrolyte, lead-acid batteries as a portable power supply.[1] These are not lightweights, but they're good for many hours of operation. Exact time before recharging is required depends on duty cycle. In other words, transmitting "eats" the batteries more rapidly than receiving.

While one battery is powering the transceiver, the other can be recharging. My favorite method of recharging the batteries is to use a solar panel—mine is rated at 18 V and 500 mA.[2] It feels good to put those free photons to work—and solar energy is good for bonus points on Field Day! An ac-operated charger was described in June 1987 *QST*.[3] That charger ensures optimum charging of batteries. For best battery life, don't run the batteries flat before recharging. *The ARRL Handbook* explains proper care of lead-acid batteries (Chapter 6 in recent editions).

Portable Antennas

For portable operation, I like to use a dipole suspended by tough, lightweight nylon cord. The dipole in my portable station uses plastic insulators (see Fig 1). The center insulator has an extra hole so that a nylon line can be used to support the



Fig 1—Details of the center insulator (left) and end insulator (right) for the antennas described in the text.

---

[1]Notes appear at end of article.


EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000, M = 1000 000.
U2
78L05
REG
IN
OUT
GND
+7−15 V IN
10 µF / 16 V
C4
GND
C3 0.01
C5 0.1
U1
3044B
16 VDD
1 VSS
KEYER
WT 15
R3 5.6 k
C7 0.22
C8 0.1
TO KEY JACK
DOT
R2 470
2 DOT KEY
R4 1M
3 RDOT
C1 0.01
4 CDOT
5 CDASH
GND
0.01 C2
1M R5
6 RDASH
DASH
R1 470
7 DASH KEY
13 12 11
NC
Q1 2N2222
TO KEY LINE
KEYED OUTPUT 14
R7 4.7 k
CSPEED 10
C6 0.15
A
RCSPEED 9
SPEED R8 500 k
RSPEED 8
R6 91 k
B

Fig 2—Schematic diagram of a keyer based on the Curtis 8044 IC. Capacitors are disc ceramic, except for C4, which is electrolytic. C6 and C7 are NP0 types, although any temperature-stable capacitor of the proper value should work fine.


(A)
1 INCH
TO KEYING LINE
GND
+12 V
GND
DOT
C4
U2
CBE
C3
E
B
C
Q1
R5
R4
C2
C1
R6
U1
R7
R2
R1
C8
R3
C6
C7
GND
TO KEY JACK
DASH
B
R8
A
SPEED CONTROL
(B)

Fig 3—Circuit-board etching pattern (A) and parts-placement guide (B) for the keyer. The pattern is shown full-size from the foil side of the board. Black areas represent unetched copper foil. Parts are placed on the nonfoil side of the board; the shaded area represents an X-ray view of the copper pattern.

center. The end insulators are made so that element lengths can be adjusted easily for changing bands.

For 80-meter operation, I use an end-fed quarter wavelength of wire terminated with a banana plug. The plug fits neatly into the RF connector on the HW-9's rear panel. The far end of the wire is supported by a plastic insulator like those used in the dipole. Because this antenna operates against ground, I carry a couple of clip leads to make a connection to the best ground I can locate. (For instance, I've had good luck grounding to the heating pipes in a motel. The secret is to use what you have available.)

Accessories

At first, I used my son Scott's (N1DSF) Heath µMatic Memory keyer with the HW-9. (I mounted a phono connector to the HW-9's rear panel to provide switched 12 V dc power for the keyer.) Later, I decided to build into the transceiver a keyer based on the Curtis 8044 CMOS IC. The circuit is based on the 8044 spec sheet, and the schematic is shown in Fig 2. Tom Miller, NK1P, prepared the schematic and the PC board shown in Fig 3. I mounted the completed board upside down using a bolt and nut that holds the HW-9's BFO shield in place. I moved the wire from the key jack to the circuit board, and ran a new wire from the circuit board to the key jack. The SPEED control, R8, is added to the front panel, and a jack for the paddle is added to the rear panel.

For portable operation, I wanted to package the station for easy transport. An aluminum briefcase proved to be just what I was looking for. Packing foam, cut with a hacksaw blade, cushions the HW-9. The rest of the station, except the solar panel, goes into the case with the HW-9: the two gel batteries, dipole with feed line, 80-m end-fed antenna, nylon cord, clip leads, keyer paddle, lightweight headphones and an ARRL Minilog.

Conclusion

My portable QRP station is not made for backpacking. It does, however, fill my need for something that goes easily to Field Day or on vacation. The entire station, except for the solar panel, fits into a briefcase. What could be more convenient?—*Chuck, K8CH*

Zack's Circuit Improvements

Although this portion of the article concentrates on improving the Heathkit HW-9 QRP transceiver, these modifications may be of general interest to home-brewers, as they can be adapted to many QRP rigs. These modifications include adding an SWR meter that requires no balancing adjustments, removing audio thumps and clicks, and improving the signal-to-noise ratio of the HW-9's NARROW audio filter.

The new HW-9 SWR meter is a version of the directional coupler used in the Tandem match.[4] The main advantage to the coupler shown in Fig 4 is that no adjustments are required. Anyone who has fiddled with trimmer capacitors trying to get a good null will appreciate this feature. Faraday shielding is not used in this application, as coupler directivity is adequate for the uncompensated diode detectors.

The switching circuit, shown in Fig 5, allows the existing HW-9 meter to be used as an SWR meter on transmit and as an S-meter (it's normal function) on receive. When the voltage at the input of this circuit (Q403 collector) is zero, Q1 turns on and Q2



Fig 4—Schematic diagram of the SWR meter.

D1, D2—Shottky diode HP 2800-2635 (1N34A can be substituted).

T1, T2—Broadband transformer. Primary has 14 turns of no. 26 enam wire on an Amidon FT-23-43 toroid core. Secondary is 1 turn of no. 22 hookup wire.



Fig 5—Schematic diagram of the meter switch circuit. Q403 is a Heathkit part designator.



Fig 6—Schematic diagram of the audio thump suppressor. Q303 is part of the transceiver—see text.



Fig 7—Circuit-board etching pattern (A) and parts-placement guide (B) for the SWR meter. The pattern is shown full-size from the foil side of the board. Black areas represent unetched copper foil. Parts are placed on the nonfoil side of the board; the shaded area represents an X-ray view of the copper pattern.

turns off. This allows the meter to function normally. When the input voltage is raised to 12 volts, as is the case during transmit, Q1 is turned off and Q2 is turned on. Q1 now prevents current from the S-meter circuit from affecting the SWR measuring circuit. When Q2 is turned on, it effectively shorts out the S-meter calibration voltage, as it is not wanted while using the meter to measure SWR.

The audio thump suppressor is used to reduce the audio thumps that result when the HW-9 switches from transmit to receive. The audio line in the original HW-9 sounds like it's being shorted out when the rig switches between transmit and receive because a transistor, Q303, is used to do exactly that! A 12-dB reduction in audio thump can be obtained by using a JFET switch to break the audio line while transmitting. See the schematic in Fig 6. When the gate of the JFET Q3 follows the source, the JFET acts as a resistor with a value of roughly 100 to 300 ohms. When the gate is grounded, the JFET effectively breaks the audio line. A dc bias of roughly $V_{cc}/2$ is needed at the source of the JFET for the circuit to work. This is supplied by the output of U304. C2 is used to reduce the high-frequency response of the switch to help remove the high-frequency audio clicks. R2 is optional. A properly selected value for R2 will provide a degree of audio limiting and further thump reduction beyond the measured 12 dB. It is possible to eliminate the thump entirely by adding additional low-pass or band-pass filtering after the JFET switch. The remaining thump exists only in the wide filter position, as the narrow filter removes it.

The final modification increases the dynamic range of the HW-9 by a few decibels. If the capacitor values in an active filter circuit are too small, a substantial increase in noise results. The new values shown in Table 1 are chosen for a 250-Hz Bessel response centered at 700 Hz. A Bessel response is chosen to eliminate ringing. Measurements in the ARRL lab indicate that the filter shape tends to change at very low signal levels if the capacitor values are too small. In some cases, the band-pass response actually becomes a notch response, although the notch is usually above the desired passband.

Construction

The modifications to the HW-9 involve stuffing two PC boards and changing parts on the TR circuit board. The board shown in Fig 7 contains the directional coupler, and the board shown in Fig 8 contains the audio-thump suppressing circuit and the meter-switching circuit. This allows the coupler to be mounted in the back of the rig next to the antenna jack, while keeping the thump removal circuitry next to the audio section.

It is essential that C346 and C347 be replaced with wire jumpers for the thump removal circuit to work, as they would block the needed dc bias voltage. One of these capacitors can be used as C1 on the modification board, but take care to get the polarity right.

Thanks to Heath's excellent design, it is not necessary to unsolder all the wires to get to the solder side of the TR board. First,



Fig 8—Circuit-board etching pattern (A) and parts-placement guide (B) for the audio thump suppressor and meter switch circuit. The pattern is shown full-size from the foil side of the board. Black areas represent unetched copper foil. Parts are placed on the nonfoil side of the board; the shaded area represents an X-ray view of the copper pattern.

set the BAND switch to 20 meters and remove the BAND-switch shaft. Then, unsolder the blue keying wire and remove the six screws holding the back panel to the chassis. After removing the five nuts securing the TR board, the circuit board can be flipped up, exposing the foil side. While you have the foil side of the TR circuit board exposed, install the NARROW audio filter components listed in Table 1. I used metal film capacitors, but polyester or polystyrene capacitors can also be used, although the latter may be physically a little large. I recommend using 5%-tolerance resistors to prevent the center frequency of the filters from being too far off.

The collector lead of Q303 has to be unsoldered and attached to a hookup wire that goes to the thump suppressor. This "flying mod" is unsightly, but I see little alternative. A 10-kΩ resistor must be soldered between the base of Q303 and ground, or the thump suppressor may not allow any audio through! The resistor prevents quiescent currents from keeping the transistor on when it isn't supposed to be.

I made the switch for choosing forward or reverse power readings by combining it with the existing audio SELECTIVITY switch. First, I bought a standard Switchcraft DPDT slide switch. The plastic slider handle is too short, so I then bent the metal tabs holding the (new and old) switches together to take them apart. I then swapped the plastic slider handles, taking care not to lose the metal slide contacts. This gave me a DPDT switch with a long slider handle. You could mount a separate switch if you like, but I prefer modifications that don't require making holes in the front panel.

I used RG-174 cable on the audio and SWR meter connections to prevent unwanted signal pickup. The rest of the connections are made with standard hookup wire.

Table 1
Component Changes

Part No.	*Old Value*	*New Value*
R352	680 k	16 k
R353	33 k	1.6 k
R354	1.5 M	39 k
R357	680 k	6.8 k
R358	33 k	680
R359	1.5 M	16 k
C339, C341	1000 pF	0.027 µF
C344, C345	1000 pF	0.082 µF

Once you're sure everything is installed correctly, turn on the rig. Hopefully, the audio hiss in the WIDE position will be as loud as before. If not, Q3 may have been installed backwards, or you may have forgotten to replace C347 with a jumper. The hiss should be less in the NARROW position, because the modification is supposed to reduce noise. With the rig hooked up to a dummy load, you should be able to notice much less of an audio thump when using WIDE audio selectivity, and no thump when using NARROW. If a nasty thump is heard, Q303 is not hooked up properly. If you hear just a little bit of thump, you may consider adding R2 to reduce the thump by a few more decibels. Basically, you want as low a value of R2 as possible without turning the audio off all the time. Typical R2 values range from 1.5 to 2.2 M, depending heavily on the FET used.

While transmitting into a dummy load, adjust R6 for the desired meter deflection in the forward position. If the meter deflects the wrong way, a diode is hooked up backwards. A bad Q2 (power MOSFET) will either affect the S-meter calibration or make the bridge read backward with no power output. A properly operating bridge will measure little, if any, reflected power when using a dummy load. Since there is no SWR specification for the MRF-237s, you should be careful not to transmit into a load with an SWR greater than 2.

When all is working well, reassemble your HW-9 and enjoy. I'm sure you'll find your transceiver more pleasant to operate.—*Zack, KH6CP*

Notes

[1] Gelled-electrolyte 9-Ah batteries are available from American Electronics, 173 E Broadway, Greenwood, IN 46142, tel 317-888-7265. Reference Dick Smith part no. S-3321; price, $34.95. American Electronics also sells a charger that operates from 120 V ac. Reference Dick Smith part no. M-9523; price, $9.95. For shipping and handling add $1.50 plus 5% of order. American Electronics has a $20 minimum order.

[2] A solar panel rated for 1 A at 9 V or 500 mA at 18 V is also available from American Electronics. Reference Dick Smith part no. Z-4845; price, $149. See note 1.

[3] Warren Dion, N1BBH, "A New Chip For Charging Gelled-Electrolyte Batteries," *QST*, Jun 1987, pp 26-29.

[4] John Grebenkemper, KA3BLO, "The Tandem Match—An Accurate Directional Wattmeter," *QST*, Jan 1987, pp 13-26.

From October 1988 QST, p 43:

HW-9 Tips

☐ I read the article, "Improving the HW-9 Transceiver,"[4] with great interest. I built an HW-9 about two years ago, and the first thing I added to it was a Curtis keyer chip; the second thing was a 100-kHz crystal calibration oscillator. The keyer and calibration oscillator circuits are contained on a small perf board that's secured to the left rear corner of the rig by means of small metal angle brackets. The calibrator has proved extremely useful in light of the HW-9 reduction drive's tendency to slip.

I'd like to add a couple of suggestions concerning the addition of the keyer circuit. I like to use a straight key from time to time, so I removed the original key jack, enlarged the hole and mounted a four-pin microphone connector in its place (see Fig 2). This provides connections for both a paddle and straight key without adding another jack. I also added a small push-button switch to the rear panel and connected it to the keying line for use as a TUNE switch.

I found the HW-9's keying to be a bit on the heavy side. Although the weighting could have been altered by using a weighting control connected to the Curtis chip, I decided it was better to correct the problem at its source: This is the HW-9's keying line, which has a slow return to + 12 V. I solved this by adding a 1-kΩ resistor from the transmitter keying line to + 12 V. Observation of the rig's output on a scope shows almost perfect weighting. I recommend this simple modification to anyone using an external keyer as well.

I'm already planning my next project: Add the SWR meter, thump suppressor and filter modifications described in the April article. With these additions, this great little rig will be even more of a joy to operate! Now—if I could just find a way to reduce the warm-up drift of the VFO . . . —*Larry V. East, W1HUE/7, POB 51445, Idaho Falls, ID 83405-1445*

---

[3] Deleted

[4] C. Hutchinson and Z. Lau, "Improving the HW-9 Transceiver," *QST*, Apr 1988, pp 26-29.



1μF/16V T
MARKER ✱
S1
+5V
0.01
D
G
S
Q1
MPF102
0.001
1N34A
U1
100 kHz
13
14
1M
11
8
10
2.2
910
12
7
9
CAL
5-60 NPO
0.001
10mH
1N34A
100 kHz XTAL
ON TR BOARD
TO PIN 1 OF SECOND MIXER (U401)
U2
LM340-5
REG
IN
OUT
GND
+12 V
0.1
+5V
10μF/16V
SPEED ✱
500k (LOG TAPER)
CW
100k
0.2/M
9
10
8
7
DASH
NC
11
12
13
14
15
16
8044
6
5
4
3
2
1
1M
0.01
0.01
1M
N34A
+5V
DOT
4-PIN MIC CONNECTOR ✱ (REPLACES KEY JACK)
3
2
1
4
PADDLE
KEY
COMMON
100k
FB
10μF/16V
+5V
4.7k
2N3904
Q2
0.01
TX KEY LINE
1k
+12V
TUNE ✱
S2

EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000 M = 1000 000.

T = TANTALUM

M = MYLAR

✱ MOUNTED ON REAR PANEL OF HW-9

Fig 2—Larry East (W1HUE) added a crystal calibrator, Curtis keyer, TUNE and MARKER switches and keying circuit modifications to his HW 9. A four pin microphone jack provides for straight-key and paddle connections.

From June 1975 QST, p 35:

The Mavti-40

Part I



BY D. K. SIEMER,* K0JYD

> *We have had many requests for a simple transceiver that is within the building capabilities of most beginners. The MAVTI-40 described here is the ideal answer to these requests. As the author points out, this is* not *a one of a kind unit, as several have been built by his students, and they all work.*

THE 7-MHz TRANSCEIVER described in this article is the result of a desire to have a small, portable station for personal use. Also, since many of the students here at the Mankato Area Vocational-Technical Institute are interested in ham radio and are usually short of extra cash, it seemed like a good idea to make an inexpensive station available to them on an "installment" basis. They can build the receiver section first for code practice; then they can build the transmitter later when they get their tickets.

The project makes use of new components rather than surplus ones to make parts procurement easier and to avoid the pitfalls and disappointments often associated with the latter. The components, though new, are not expensive, and the whole unit can be built for $40 or so – key, cabinet, and earphones included. Several of these stations are now in operation and have produced many satisfied-operator reports.

Because economy was a byword, the transceiver was built with a minimum number of components consistent with good design and satisfactory operation. None of the units built have exhibited unusual problems in construction or operation making the station a good candidate for a first homemade project.

The VFO

The VFO is a variation of one used in a number of projects here. Q1, Fig. 1, performs as a Colpitts oscillator and Q2 as a source-follower buffer. To keep parts to a minimum and still have good mechanical stability with high output voltage, a toroid core was used with L1 instead of the usual slug-tuned ceramic one. C5 is a compensating capacitor to reduce oscillator drift.

When checked in an environmental chamber, the output frequency shifted less than 2 kHz with a temperature variation between *50° F* and *100° F*. Below *50° F* the frequency shifted quite rapidly however, typically 100 Hz/°*F* which would be of concern if low-temperature operation is anticipated. Frequency shift between transmit and receive is less than 200 Hz and warm-up drift is less than 150 Hz in the two-minute period immediately after turn-on. After the two-minute period the oscillator drift is so slight as to be unnoticeable.

The tuned-circuit component values were chosen so that the tuning capacitor, C4, will just cover the 150-kHz cw portion of the 40-meter band with a few kHz to spare. C3 is a trimmer capacitor to adjust the oscillator frequency to 7000 kHz with C4 fully meshed. The 5 to 25-pF value given in the parts list would be more satisfactory than the 3 to 12-pF value shown in Fig. 5. C3 is mounted directly on the solder lugs of C4.

The MFC4060A voltage-regulator chip offers superior performance when compared to a Zener diode. Line regulation is typically .03% per volt. Good oscillator supply voltage regulation was an important consideration when designing the unit.

The VFO circuit board was laid out so that a Micronta 2-inch vernier dial could be bolted directly to it. The two hex nuts are on No. 4-40 × 1-inch mounting screws that hold the dial to the front panel. Two 5/8-inch long standoffs hold the board away from the front panel the proper distance for connecting the capacitor shaft to the vernier dial. A small 1/4-inch long bushing, 1/4-inch OD and 3/16-inch ID is used between the capacitor shaft and the vernier drive shaft. The bushing was made by drilling a 3/13-inch hole through a 1/4-inch brass shaft and cutting it to length. It was then slotted along one side to allow the bushing to compress against the shaft of C4 when the dial drive setscrew was tightened against it. To insure mechanical stability, L1 was glued to the pc board by means of silicone rubber adhesive.

The Receiver

The receiver section (Fig. 1) makes use of a MOSFET, Q3, in a straight forward direct-conversion scheme as described in numerous technical articles as well as the ARRL *Handbook*. The unusual component is the resonant af transformer consisting of L5, L6, L7, and C16.

Windings L5 and L6 make up a 2.25:1 step-down impedance matched transformer between the drain of Q3 and the base circuit of af amplifier, Q4. L7 and its associated capacitor C16, a 2.2 µF, 3-volt disk ceramic in this case, provides a transformer resonance to a center frequency of approximately 800 Hz with a bandwidth of 200 Hz. This transformer is wound on a cup-core assembly consisting of two cup-shaped pieces of ferrite material that surround a nylon bobbin.

While the cup-core transformer is not very common in amateur work, it is widely applied in industry where high *Q*, compact, self-shielding inductors are required. The parts needed for this assembly may be obtained from Elna Ferrite Laboratories, whose address is given in this article (see Fig. 1). Be sure to order two of the cup cores and one bobbin as they are not sold as an assembly.

The bandwidth of the transformer can be varied by changing the reactance of L7 and selecting another value of C16. In the first unit built, L7 was 70 turns of No. 30 AWG and C16 was 0.68 µF. These values provided a bandwidth of about 400 Hz centered on 800 Hz. C16 should be a low-loss type with ceramic, mylar, or polystyrene dielectric.

For individuals interested in experimenting with the cup-core transformer, the 3B7-L00-3C19P material used here has an incremental inductance value of A_L of 7580 mH/1000 turns. Different



This shows the inside of the transceiver. Shielded leads are used for all interconnections and to the various terminals on the rear of the enclosure.

---

*c/o V-Tek Inc., PO Box 3104, Mankato, MN 56002


RECEIVER BOARD
VARIABLE FREQUENCY OSCILLATOR BOARD
DRIVER BOARD
POWER AMPLIFIER BOARD
FILTER BOARD
PART OF PC B 3
PC B 1
PC B 2
PC B 3
PC B 4
SIDETONE
J2 OUT
J3 ANT
J1 KEY
F12 TO 14.5 V DC
S1 ON/OFF
S2A
S2B
REC.
TRANS.
S3A
S3B
LOW
HI
7 MHz
800 Hz
U1
Q1 MPF102
Q2 2N3904
Q3 40841
Q4 MPS6514
Q5 MPF102
Q6 40081
Q7 2N4831
Q8 40082
13.6

EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS; k=1000, M=1000 000 S.M.=SILVER MICA

NOTES:
DOTTED LINES INDICATE SEPARATE PRINTED CIRCUIT BOARDS.
ALL VOLTAGE MEASUREMENTS TAKEN WITH Vcc=+13.6 V DC.
□ DENOTES DC VOLTAGE.
○ DENOTES PEAK-TO-PEAK VOLTAGE.

Fig. 1 — Circuit diagram of the MAVTI 40-meter portable. Resistances are in ohms, all resistors are 1/2 watt.

C3 — 5- to 25-pF ceramic.
C4 — 2.7- to 19.6-pF variable (E.F. Johnson 160-110-51 or equiv.).
C5 — 47 pF, N750 ceramic.
C13, C22 — 10- to 180-pF mica compression type (ARCO 463).
C24, C29, C30, C32, C33 — 75- to 480-pF mica compression type (ARCO 466).
J1, J2 — Open-circuit jack.
J3 — Phono jack.
L1 — 18 turns No. 24 enam. wound on Amidon T37-2 toroid core.
L2 — 56-μH molded rf choke.
L3 — 4 turns No. 24 enam. wound over L4.
L4 — 34 turns No. 26 enam. wound on T50-2 toroid core.
L5 — 365 turns No. 32 enam. wound on cup core, see note below.
L6 — 162 turns No. 32 enam. wound over L5.
L7 — 50 turns No. 32 enam. wound over L5 and L6.
L8 — 34 turns No. 26 enam. wound on T50-2 toroid core.
L9 — 3 turns No. 24 enam. wound over L8.
L10 — 7 turns No. 24 enam. wound over L11.
L11 — 22 turns No. 22 enam. wound on T50-2 toroid core.
L12 — 4 turns No. 26 enam. wound over L11.
L13 — 14 turns No. 20 enam. wound on T50-2 toroid core.
L14, L17 — 20 turns No. 24 enam. wound on T37-2 toroid core.
L15, L16 — 65 turns No. 32 enam. wound on T37-2 toroid core.
U1 — MFC4060A.

(Note: L5 is wound on a Ferroxcube 3019P3B, ungapped cup core. See text for winding details. This device is available from Elna Ferrite Laboratories Inc., P.O. Box 395, Woodstock, NY 12498. The T50-2 and T37-2 toroid cores are available from Amidon Assoc., 12033 Otsego St., North Hollywood, CA 91607.)

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.

values of inductance may be calculated using the following equation:

$$\frac{L_1}{(N_1)^2} = \frac{L_2}{(N_2)^2}$$

L_1 = Known A_L.
N_1 = 1000 turns.
L_2 = Inductance (known or unknown).
N_2 = Number of turns (known or unknown).

Where L_1 = 7580 mH and N_1 = 1000 turns. The equation is the same as that used with the Amidon cores used in rf circuitry.

Although it does not have the steep skirt selectivity that a more elaborate passive or active filter may have, the tuned transformer approach yields excellent results for a minimum number of components and cash outlay.

The transformer assembly is held down on the pc board with a No. 4-40 × 1-inch screw and washer through its center mounting hole. Be careful not to apply excessive torque to the screw when assembling the unit because the ferrite material is extremely brittle and may crack.

The detected audio is amplified by Q4 and then applied to 2000-ohm headphones via J2. When constructing the unit, don't forget C20 on J2, it prevents rf from being transferred to the headphone cord and being reradiated into the front end of the receiver. This was a source of spurious oscillations which caused considerable grief when the circuit was being developed. The problem also showed up on a completed unit from which C20 was omitted.

The receiver has a comfortable listening level with three or four microvolts input. Af output is "controlled" by positioning the headset for a comfortable audio level. For strong signals they may be laid on the table and used as a loudspeaker.

The receiver board is quite versatile and can be used as a product-detector/af-preamplifier stage in a superheterodyne circuit by changing L3, L4, and C3 to resonate at the intermediate frequency and replacing the VFO input with a BFO of the proper frequency to produce a beat note. The board requires a Vcc jumper to operate. The jumper location on the board may be observed in Fig. 3.

In Part II of this article, we'll describe the driver and amplifier stages, plus tune-up procedures. Meanwhile, readers interested in constructing the station can begin accumulating the parts shown in Fig. 1 and in the parts list.



Fig. 2 — Parts placement for the receiver board.



Fig. 3 — Full-size template for the receiver board.

From July 1975 QST, p 40:

MAVTI-40

Part II

The Driver Stage

IN PART I of the article, we described the receiver and VFO sections of the 40-meter transceiver. With the information provided in this section, the builder can complete the station.

The driver board is a small transmitter that is an adaptation of the Milligallon by W7ZOI, as described on page 336 of the *Radio Amateurs Handbook*, 1972 edition.

To minimize VFO loading, Q5, a JFET was used as the driver transistor. Q5 drives the base of Q6, an amplifier, via L9 which is a 3-turn link wound over L8. Q6 has a typical output of 700 mW when Vcc is 13.6 volts. The output drops to a little over 500 mW when Vcc is reduced to 12 volts making it a usable transmitter when flashlight or lantern batteries are the only available source of power. Q6 is about 65% efficient in this circuit.

The low-pass filter consisting of C25, C26, and L13 removes most of the harmonic energy present in the output from Q6. It is wired between the antenna terminal and the rest of the circuitry, and is effective on both high- and low-power transmitting as well as the receive mode.

Q7 is a UJT that is used as a sidetone oscillator. Whenever the driver is keyed, Q7 turns on and its output is coupled to the headphone jack via C27. The value given for C27 provides a comfortable level of sidetone, but it may be changed to suit individual preference. C28 and R17 determine the sidetone frequency which is typically 1 kHz. With C22 and C24 peaked at midband, 7075 kHz, the output amplitude is constant from one end of the cw band to the other.

The number of turns for the inductors on the driver board is somewhat critical and should be counted carefully. To make counting and hookup easier, different size wire was used for each of the windings. The wire size is not critical. However, it is best if the turns are spaced equally along the circumference of the core. Be sure that L9 is wound over the middle of L8 and not in the gap between the ends. This can be a cause of low rf output.

Depending on the position of S3, the rf output from the driver board is either coupled to the antenna via the T-R switch, S2, and the low-pass filter, or to the input network opposite the power-amplifier board.

The Power Amplifier

The power-amplifier board was designed using the procedure given by W7ZOI in the May, 1972, issue of *QST*. Excitation from the driver board is coupled to the base of Q8 via the input *T* network consisting of C29, C30, and L14. The base swamping resistor, R19, was selected to provide adequate drive and reasonable efficiency in the amplifier.

Rf chokes L15 and L16 should be glued to the pc board by means of silicone rubber adhesive. The other inductors are wound with heavier wire and are supported adequately by their leads.



Fig. 4. – Full size template for the VFO board.

Q8 is the only transistor in the unit that requires a heat sink. It is shown with the sink removed in Fig. 7 for clarity. The heat sink in the author's unit is a Thermalloy type 1101A with two 1-inch square pieces of aluminum bolted to it. It can be observed in photographs. The sink is conservatively rated and the key must be depressed for a good while before the assembly becomes very warm. Almost any of the finned clip-on sinks that are readily available should work well.

The power amplifier is keyed on by applying rf excitation to the input rather than by keying Vcc. When the first prototype was being built, it was found that trying to key several stages caused chirping, particularly when the current through them exceeded 200 mA. Only by keying the driver was this problem eliminated.

There is no danger of thermal runaway with this arrangement because the base of Q8 is tied to the emitter through L15. Also, the leakage current consumed by Q8 when it is not in use is negligible. It is in the order of a few microamperes.

This shows the inside of the transceiver as viewed from the rear.



As a matter of interest, the transmitter was operationaly checked at 10°*F* increments between −40°*F* and +140°*F*. The output was stable and no amplitude change could be observed. Rf power output is typically 5 watts for 8 watts input.

Construction

The receiver, driver, and power amplifier boards all measure 3-1/2 × 2-1/8 inches and the VFO board is 2-1/8 inches square. Layout of the boards is not critical and most any convenient packaging arrangement may be used. All rf wiring is done with RG-174/U. Extra solder lands for interconnection between the VFO, driver, and receiver boards are provided on the receiver board.

The unit is housed in a homemade aluminum box measuring 2-3/8 inches high by 4 inches wide, and 6-3/4 inches deep including the 5/8-inch front overhang of the top cover. The chassis is finished in Golden Harvest Shadow epoxy appliance enamel and the top cover is painted with a dark brown wrinkle finish. Amidon lettering is protected with a coat of clear acrylic spray. Stick-on rubber furniture bumpers are used as feet to complete the cabinet.

The VFO output was brought out to a jack on the back panel so that a frequency counter could be used for a digital-frequency readout when operating at home. The whole station, including the key, earphones, NiCad battery pack, and a 40-meter dipole can be carried in an ordinary lunch bucket.

Alignment

Alignment of the VFO is accomplished by monitoring its output frequency with a frequency counter or calibrated receiver. Tuning the output frequency to 7.0 MHz by adjusting C3 with C4 while they are fully meshed is also done. The receiver is aligned by tuning in a station near 7.075 MHz and adjusting C13 for maximum headphone volume. For transmitting alignment, a dummy load with an rf detector as shown in Fig. 8 should be used.


U1
R2
R1
C1
C7
R4
R7
R5
Q2
R6
C11
L1
C10
C6
L2
C5
R3
C9
Q1
C8
C3
C4

Fig. 5 — Parts placement for the VFO board.


R14
VFO
R18
Q5
L8
C21
C28
L9
Q7
C22
C27
R17
R16
R15
Q6
L10
C25
L12
C23
L11
L13
C24
C26
ANT.
FULL SCALE
FOIL SIDE
DRIVER BOARD
COMPONENT LAYOUT
Q5
L8
C21
C22
R15
R16
L11
C23
C24
R14
R18
C28
Q7
C27
R17
Q6
C25
L13
C26

Fig. 6 — Full-size template and parts placement for the driver board.


C29
C30
C35
L15
L14
R19
Q8
L16
L17
C31
C34
C32
C33
FULL SCALE FOIL SIDE
INPUT
C30
C29
C35
L14
L15
Vcc
R19
L16
Q8
C31
L17
C34
OUTPUT
C33
C32
POWER AMPLIFIER
COMPONENT LAYOUT

Fig. 7 – Full-size template and parts placement for the power-amplifier board.

Turn the adjusting screws of C22, C24, C29, C30, C32, and C33 to maximum clockwise positions. With the load connected to the antenna terminals, S3 set to low power, and Vcc set at 10 V dc, depress the key and adjust C22 and C24 for maximum output. Then increase Vcc to 12 V dc and repeat the adjustment. The tuning should be smooth and regular. Next set Vcc back to 10 V dc, S3 to high power, and adjust C29, C30, C32 and C33 for maximum output. They interact so you will find it necessary to go back over them a few times until no further increase in output can be obtained. Increase Vcc to 12 V dc and repeat the procedure; the capacitors should require very little retuning and should cause the output to vary smoothly with no sudden variations.

After tune-up, a battery current-drain check should yield the following values with Vcc at 13.6 V dc:

Receive mode	20 mA
Transmit mode (low)	100 mA
Transmit mode (high)	750 mA

The author wishes to thank the staff, faculty, and students at the Mankato Area Vocational-Technical Institute who provided assistance on this project.


1N914
220 2W
220 2W
220 2W
220 2W
470 1W
C1 .01
+
TO DC VTVM
–

Fig. 8 – Dummy load and rf detector.

From October 1985 **QST**, *p 14:*

Better Ears for the MAVTI-40 Transceiver

A transceiver need not be a complicated building project. Try QRP—and instead of tackling a superhet receiver, take the direct approach!



By Paul Kranz, W1CFI
26 Mettacomett Path
Harvard, MA 01451

Although this article concentrates primarily on the redesign of the MAVTI 40 receiver section, there's enough information here to permit you to build a complete 40-meter QRP (low-power) transceiver. PC boards and parts kits are available to make your job even easier.

Direct-conversion (D-C) receivers are easier and less costly to build than their superheterodyne cousins, and assembling a D-C receiver is an educational and rewarding project. Although D-C receivers have some performance shortcomings, the receiver described here eliminates some of them. This receiver will reject AM broadcast interference to the level of inaudibility. It also provides a narrow-bandwidth filter for CW reception and a tunable notch filter. Modifications for improving the stability and wave shaping of the original MAVTI-40 transmitter are provided, as is a TR switch.

A Club Transceiver Project

In 1979, the Hewlett-Packard Amateur Radio Club in Andover, Massachusetts, began a Novice class with five prospective radio amateurs. Since none of them had any equipment, we decided that a simple transceiver construction project might solve this problem as well as offer some experience working with hardware. A search of back issues of Amateur Radio magazines turned up one transceiver design that seemed to offer many advantages over other designs. This transceiver, the MAVTI-40, had originally been designed and constructed as a radio club project, and several had been built.[1] This suggested that the 5-W-output, 40-meter transceiver

[1] Notes appear at end of article.



Fig. 1—Schematic diagram of the bridged differentiator notch filter (see Note 5).



Fig. 2—Frequency response of the notch filter of Fig. 1 with the potentiometer set at each end. →

should be capable of being duplicated easily without the problems associated with many one-of-a-kind designs. Further, a PC-board negative was available from the author, making the construction repeatable and reliable.

Forty meters is a good band for beginners because it has an active Novice segment during daylight and evening hours. Also, the band offers good DX and QRP activity in the General- and higher-class portions of the band, and that encourages license upgrading. One disadvantage of 40-meter operation is the evening-hour AM-broadcast interference.

Five MAVTI-40 transceivers were built using a variety of construction techniques. Although the transceivers performed reasonably well, they all exhibited occasional instability in the transmitter and receiver sections. One of the units has been in use at my station for five years, and has served as a test bed for many experiments and subsequent improvements to the original design. Eventually, the instability problems were solved and the transceiver has provided many enjoyable contacts.

Receiver Improvements

The original receiver was difficult to use at night because it detected AM broadcast stations that resided more than 100 kHz above the usual 7040-kHz QRP operating frequency. This problem became increasingly worse as the sunspot activity declined. Several initial modifications, including the use of different mixers and additional input filtering, were tried without success. An examination of Amateur Radio magazine articles turned up some 40-meter transceiver designs that addressed the AM-detection problem.[2,3] These articles offered the inspiration needed to attempt a redesign of the original receiver.

Mixing Schemes

Measurements made at my location revealed broadband signals of 100-mV P-P at the feedpoint of a dipole antenna. These signals would need to be removed before they reached the mixer. AM broadcast stations at 7.2 MHz produced 8-mV P-P on a 50-ohm load connected to the antenna, while the strongest CW signals measured 50-μV P-P. AM-detection comparisons were made using an HP-3585A spectrum analyzer coupled to the MAVTI-40 MOSFET mixer, a harmonic detector (see Note 2) and doubly balanced mixers. These measurements were made by injecting a 50% amplitude-modulated signal into the mixer RF input while measuring the detected AM signal with the analyzer. The frequency of the AM input signal was chosen to be 100 kHz above the mixer local oscillator (LO) to simulate actual 40-meter operating conditions. The detected AM signal is the actual audio modulation (baseband). The result is expressed as a decibel ratio between this audio signal and the mixer output when the LO is tuned to receive the AM signal. The MAVTI-40 mixer was able to reject this AM signal by only 35 dB. The harmonic detector (with the LO operating at half the RF input frequency) rejected the unwanted AM signal by 60 dB. A doubly balanced diode mixer was the best performer,



Fig. 3—Schematic diagram of the active notch filter; R3 controls the notch frequency. This filter has a gain of 0 dB.



Fig. 4—Frequency response of the tunable active notch filter of Fig. 3.



Fig. 5—Block diagram of the new D-C receiver.


AUDIO AMPLIFIER (40 dB)
LOW-PASS FILTER
BALANCED MIXER
NOTCH
+12 V
L1 *see note
47 mH
*see note
L2
205 mH
C5
0.22
C3
0.1
C4
1 µF
16 V
R1 47
C23
33 µF
16 V
C7
33 µF
16 V
R5
1M
C8
0.0068
C9
0.0068
C10
0.0068
Q1
2N3391A
R2 1k
+6 V
R3
5.6k
C6
33 µF
16 V
R4 5.6k
+6 V
T12
NOTCH FREQ
R6
5k
R7
15C k
T11
T3
T4
D1
D2
D3
D4
1
2
3
4
5
6
7
8
ANT
T9
K1C
T1
T2
C24
15
C1
180
C2
180
GND
T6, T8
T7
FROM TRANSMITTER OUTPUT
6.8 MHz - 7.5 MHz
FILTER
B
E C
2N3904
2N3906
S
D G
2N4392
OUT
IN GND
78M12CG
BASE DIAGRAMS BOTTOM VIEW
B
E C
MPS6515
2N339A
S
D G
2N5485
NOTE: CONNECTION POINTS WITH T NUMBERS IDENTIFY PC-BOARD TERMINALS
+12 V
R21
10 k
KEY
T18
R20
1k
Q6
2N3906
TO T17
XMTR
DRIVER +12 V
T22 FIG 9
R22 10k
1N914
D7
C15
47 µF
16 V
0.5 TO 5-SEC
TR DELAY
R25
100k
R23
100 k
R24 10k
TR SWITCH
+12 V
R16 27k
T4
C13
10
7.0 TO 7.15-MHz VFO FIG 9, T30
T3
Q2
2N3904
Q3
2N3904
R18 39
D5
D6
1N914
C14
0.1
R17
27 k
R19 39
2N3906
Q4
Q5
2N5485
VFO BUFFER

EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k = 1000, M = 1 000 000

*Note: Insulate pot cores from circuit board with nylon washers.

Fig. 6—Schematic diagram of the D-C receiver including the TR switch. Note: Equivalent parts may be substituted. Unless otherwise specified, enameled wire is used for winding inductors.

D1-D4, incl.—HP2800 hot carrier diode or part of U3 (see text).
D5-D10, incl.—1N914 or 1N4148.
D11—1N753, 6-V, 0.4-W Zener diode.
K1—12-V, DPDT (Radio Shack 275-213).
L1—113 turns no. 26 on Amidon pot core PC 2213-77.
L2—237 turns no. 30 on Amidon pot core PC 2213-77.
Q1—2N3391A, MPS6515.
Q2, Q3, Q7-Q9, incl.—2N3904.
Q4, Q6, Q10—2N3906.
Q5—2N5485 FET.
Q11—2N4392.
T1, T2—Primary, 4 turns no. 30 on Amidon

boasting a 73-dB rejection ratio.

Compared to the harmonic detector, the doubly balanced mixer has the additional advantage of being insensitive to the LO waveshape. In fact, this mixer is most efficient when driven by a square wave. The mixer diodes are used as switches and, as such, do not provide mixing by virtue of their nonlinear transfer curves as they do in the harmonic mixer. A disadvantage of the doubly balanced diode mixer is the amount of LO power required, typically 7 dBm.

Noise Figure

Although the atmospheric noise in the 40-meter band is not so low that a low-noise-figure receiver is required, an attempt was made to keep the receiver noise to a reasonable level. Since the noise figure will never be lower than the mixer conversion loss (6 to 8 dB), the remaining amplifiers serve only to make the noise figure worse. Atmospheric noise in a quiet location contained in a 200-Hz bandwidth on 40 meters


FILTER (20 dB)
BAND-PASS FILTER (30dB)
+12 V
U1A
1/2 LF353
8
5
7
6
4
9.09k 1%
R8
19.6 1%
R9
R10 1k 1%
T13
GAIN
R11 10k
T16
T15
TO MONITOR OUTPUT FIG 9, T26
C11 820
R15 1.0 M 1%
24.3 k 1%
R12
C12 0.0022
R13 2.7k
R14 439 k 1%
U1B
1/2 LF353
2
3
1
+6 V
2N4392 Q11
R29 100 k
+6V
K1B
T10
GIMMICK CAP (SEE TEXT)
C16
TO VFO FOR XMTR OFFSET T32, FIG 9
+12 V
1N914
D8
K1A
Q7 2N3904
Q8 2N3904
R26 10k
+12 V
Q9 2N3904
C17 33 µF 16 V
1N914
D9
D10
R28 10
R31 100
T14
PHONES
C18 33 µF 16 V
Q10 2N3906
C25 0.1
R27 1k
AUDIO P.A.
U2 78L12
+15 V UNREG.
T2
IN
REG.
OUT
GND
C19 33 µF 25 V
GND
T1 AND T5
C20 33 µF 16 V
220 µF 16 V
C22
R30 470
C21 0.1
-12 V
D11
6.2 V 400 mW
1N753
+6 V

T25-2 core; secondary 28 turns no. 30.
T3, T4—15 turns no. 30 trifilar wound on Amidon FT-50-43 core or part of U3 (see text).
U1—LF353N dual FET op amp.
U2—78M12CG, 12-V, 500-mA, 3-terminal regulator.
U3—Mini-Circuits SBL-1 doubly balanced diode mixer (see text).



Fig. 7—Input band-pass filter frequency response.



Fig. 8 Band pass characteristics of the D-C receiver (see text).

has been shown to be approximately 0.4-μV RMS.[4] This amount of noise would require a receiver noise figure of 20 dB (10 dB S + N/N) where the receiver noise would be just equal to the atmospheric noise.

Single-Signal Reception

One of the major shortcomings of D-C receivers is their lack of single-signal reception. When a CW station is tuned in, it can be heard equally well when the VFO is tuned above or below the zero-beat frequency. This characteristic has the effect of doubling the number of stations falling in the receiver audio passband, compared to what a superheterodyne receiver would produce. Some solutions to this problem add complexity to the D-C receiver and result in a component count that differs little from that of a superheterodyne receiver. A tunable notch filter can be used to null out an offending signal and goes a long way toward solving the single-signal reception problem.

There are many notch-filter designs described in the literature; however, one design offers notch-frequency adjustment with only one potentiometer.[5] This bridged-differentiator circuit is shown in Fig. 1, and a plot of its response is given in Fig. 2. The main problem with this design is the width of the notch at frequencies above and below the notch frequency. The addition of feedback from an op amp solves this problem and provides a notch depth of 40 dB. The resulting circuit is shown in Fig. 3, and a plot of its response is in Fig. 4. In Fig. 3, R3 adjusts the notch frequency, while R5 is used to adjust the notch width, or Q. R2 maximizes the notch depth at a given frequency. Test results of the circuit show a tunable range of 400 Hz to 2 kHz, and a notch depth of 30 to 40 dB for the component values shown. This notch depth is adequate since deeper, higher-Q notches do not take into account the finite bandwidth of CW so the operator will still be able to hear key-click-like sounds from the offending station.

The best solution to the problems experienced by the MAVTI-40 receiver seemed to be to design a completely new


U1
78L08CP
T33
+12 V
FROM T27
IN
REG
OUT
GND
+8 V
C1
0.1
C2
33 µF
16 V
T22
TO +12 V
T17 ON TR
SWITCH
R17
10 k
Q7
2N4871
Q1
MPF102
R4
22 k
MONITOR
OUTPUT
TO T16,
FIG 6
T26
C27
0.002
C28
0.1
R18
100
T32
C10
15
Q2
2N3904
C7
270
C8
470
C11
0.01
T30
VFO
OUTPUT
TO T4,
FIG 6
L1
C3
5-25
C4
3-20
C5
47
N750
C6
180
R3
100 k
C9
470
L2
56 µH
RFC
R5
27 k
R6
1 k
T31
VFO
TO T23
KEYING
MONITOR
NOTE: CONNECTION POINTS WITH
T NUMBERS IDENTIFY
PC-BOARD TERMINALS
C24
R15
470
C21A
10 µF
16 V
C21
0.01
L8
L9
C22
C23A
22 µF
16 V
C23
0.01
L10
L11
L12
C29
L14
C30
R19
6.8
Q8
40082
C31
180
POWER
VFO
INPUT
FROM T30
T23
Q5
MPF102
R14
100 k
Q6
40081
R16
47
DRIVER
40081
40082
C
E
B
GND
LM340T12
IN
OUT
GND
2N3904
E
C
B
MPF102
D
G
S
2N4871
B1
B2
E
78L08CP
OUT
IN
GND
BASE DIAGRAMS, BOTTOM VIEWS

Fig. 9—Schematic diagram of the VFO and modified MAVTI-40 transmitter. Components are numbered to agree with those of the original MAVTI-40 VFO and transmitter. Therefore, designators Q3 and Q4 are missing. Note: Equivalent parts may be substituted. Unless otherwise specified, enameled wire is used for inductor windings.

C3—5-25 pF trimmer.
C4—3-20 pF air variable (Johnson 160-110-51).
C5—47 pF N750 temp. compensating capacitor.
C22—10-180 pF compression trimmer (ARCO 463).
C24, C29, C30, C32, C33—75-480 pF compression trimmer (ARCO 466).
L1—1.4 µH; 18 turns no. 24 enam. wire on Amidon T37-2 core.
L2—56 µH molded RF choke.
L8—34 turns no. 26 on Amidon T50-2 core.
L9—3 turns no. 24 on L8.
L10—7 turns no. 24 on L11.
L11—22 turns no. 22 on Amidon T50-2 core.
L12—4 turns no. 26 on L11.
L13—14 turns no. 20 on Amidon T50-2 core.
L14, L17—20 turns no. 24 on Amidon T37-2 core.
L16—65 turns no. 32 on Amidon T37-2 core.
Q1, Q5—MPF102, 2N4416 or 2N5486 FET.
Q2—2N3904.
Q6—40081 or MRF 8003 RF power transistor.
Q7—2N4871 unijunction transistor.
Q8—40082 or MRF 8004 RF power transistor.
U1—78L08CP, 8-V, 100-mA, 3-terminal regulator.
U2—LM340T12, 12-V, 1-A regulator.

receiver incorporating these improvements. A doubly balanced diode mixer solves the AM-detection problem and provides good immunity to third-order intermodulation distortion. The active audio filtering offers a 200-Hz bandwidth for CW reception. A tunable notch filter helps reduce interference from adjacent signals and the undesired audio image frequency common to D-C receivers. A block diagram of the new receiver is shown in Fig. 5, and its performance figures are given in Table 1.

Receiver Circuit Description

The receiver schematic diagram is shown in Fig. 6. Signals arriving from the antenna enter the receiver through the TR relay contacts K1C and the input band-pass filter (T1, T2, C1, C2, C24). The filter has a passband ripple of about 3 dB from 6.8 to 7.5 MHz; its frequency response curve is presented in Fig. 7.

A Mini-Circuits Labs SBL-1 doubly balanced diode mixer is used in my receiver.[6] Any doubly balanced diode mixer may be used including a "homebrewed" version.[7] The LO drive is supplied by a buffer amplifier consisting of Q2-Q5. The mixer output is terminated for RF signals by C3 and R1. Audio output from the mixer is filtered and is impedance matched to the input of Q1 by the low-pass filter consisting of L1 and C4. Because of its im-



AMPLIFIER

EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k = 1000, M = 1 000 000

Table 1
Receiver Performance Specifications

Sensitivity (10 dB S + N/N)	0.4 µV (−115 dBm)
Bandwidth (audio IF of 750 Hz)	200 Hz
Gain	90 dB
Noise figure	20 dB
Third-order intercept	+15 dBm
Dynamic range	86 dB
AM detection	−70 dB
Notch depth	40 dB
Notch frequency	400 Hz to 2 kHz

pedance transformation, this filter has a voltage gain of 6 dB, which helps to make up for the mixer conversion loss.

The first receiver amplifier stage, Q1, is designed for low-noise while providing a gain of 40 dB in a 200-Hz bandwidth. This bandwidth is controlled by the Q of L2 and the resistance of R4.

U1A acts as a 20-dB-gain tunable notch filter. The notch frequency is adjusted from 400 Hz to 2 kHz by R6. Notch-filter Q is controlled by R9 and R10, and seems to be adequate for CW. Since the notch depth changes from 30 to 40 dB as the notch frequency is varied, R5 can be selected for best notch depth at your preferred frequency. The value of R5 will vary with the tolerance and matching of C8-C10.

The band-pass filter, U1B, provides a gain of 30 dB at 750 Hz with a bandwidth of 200 Hz. This brings the total receiver gain to 90 dB. Fig. 8 shows the band-pass characteristic of the complete receiver from the mixer output through the band-pass filter. The notch filter has been set to a high frequency in order to remove the notch from the plot.

The output of the band-pass filter is buffered by Q9 and Q10, which provide sufficient power gain to drive a pair of low-impedance headphones, such as those used with a personal stereo radio. Because of the large amount of gain (90 dB) at 750 Hz, it is not possible to use this amplifier to drive a speaker and still maintain stable operation at full gain.

Fig. 6 also shows a TR switch, Q6-Q8. Keyed power for the original MAVTI-40 driver PC board is derived from the collector of Q6. A turn-off delay for the TR relay, K1, is produced by C15 and R23. The delay is adjustable from 0.5 to 5 seconds by adjustment of R23. One pair of K1 contacts (K1C) switches the antenna between the receiver and transmitter. Another contact set (K1B) turns off the receiver mute switch (Q11, R29) during receive periods. These contacts also provide a convenient way to shift the VFO frequency down by 750 Hz during transmission. This is accomplished by grounding a gimmick capacitor (C16) connected between normally open relay contact (K1B) and the VFO tuning capacitor. (The gimmick capacitor is a small-value capacitor made by twisting together two pieces of insulated wire.) The capacitor is trimmed to the correct value by cutting away small portions of the wire while measuring the frequency shift with a frequency counter or another receiver.

Transmitter Improvements

While I was adjusting the mica compression trimmers in the original transmitter section, the RF output across a 50-ohm dummy load jumped suddenly to maximum output. This behavior suggested that the transmitter section was oscillating at or near the VFO frequency. The transmitter instability was solved by making three minor changes to the original circuit.

Fig. 9 shows the schematic diagram of the VFO and modified MAVTI-40 transmitter, including the corrections to the original article. R16 is lowered to 47 ohms. Next, a 270-ohm resistor is added in parallel with L16. Finally, L15 is removed from the base of Q8 since the base resistor, R19 (6.8 ohms), provides adequate stability for this power amplifier. The transmitter section now tunes up smoothly to a 4-W output level, and no instability has been observed. Note that this solution to transmitter instability worked well on my transmitter, and some variation from one transmitter to another may require minor changes.

The keyed transmitter output of the original MAVTI-40 has a square-wave envelope since no attempt was made to shape this waveform. I've added a 10-µF capacitor in parallel with C21 and a 22-µF capacitor in parallel with C23 to provide output waveform rise and fall times of approximately 5 ms. I have received many compliments concerning the clean sounding QRP signal from this transceiver.

Construction

The receiver, VFO and transmitter sections of the transceiver are constructed on three PC boards, which are mounted inside an LMB CO-3 cabinet. The PC boards are double sided with the top side of each board serving as a ground plane; the boards have plated-through holes.[8]

I use an external, unregulated supply (Fig. 10) to power the transceiver. It's probably best not to include the power supply inside the transceiver cabinet since hum pick up could become a problem.[9] Voltage regulation is provided for on the receiver board by a three-terminal regulator. The 6-V supply is derived from the regulated 12-V line by using a 470-ohm resistor in series with a 6.2-V Zener diode (D11).

I fashioned a tuning dial by attaching a clear plastic disc to the mounting plate of a Jackson Brothers 30:1 reduction drive. Calibration marks are made by applying



Fig. 10—Schematic diagram of the unregulated power supply.



Fig. 11—Spectral display of the transmitter output. Vertical divisions are each 10 dB; horizontal divisions are each 5 MHz. Output power is 4 W at 7 MHz. All spurious emissions are at least 32 dB below peak fundamental output power.

dry transfers to a translucent piece of plastic film cemented to the plastic dial plate with rubber cement. Another piece of clear plastic is used for a dial window, and a hair-line indicator was produced by scratching the plastic with a scribe. The window is cemented to the inside of the front panel behind the dial cut-out and in front of the dial plate. Back lighting for the dial is provided by two small, colored lamps.

L1 and L2 are mounted to the PC board using the plastic mounting screws supplied with the pot cores. The gimmick capacitor, C16, is made from two pieces of no. 22 insulated, solid-copper wire twisted together over a length of 1 inch. C16 is connected between the VFO tuning capacitor and terminal T10.

The transmitter-board inductors are wired to the board in two different ways. L8, L9, L10 and L12 have each winding connected to the board at opposite sides of the toroid. All other inductors have their windings connected to the board on the same side of the inductor. The mica compression trimmer capacitors are mounted by soldering a U-shaped piece of no. 22 bare wire to each solder tab on the capacitor. The bus wire is then inserted into the two holes in the PC board. The 12-V regulator uses the PC board mounting stud as its heat sink. A heat sink must be used with Q8.

All boards should be tested (refer to the next section) before they are mounted in the transceiver. The PC boards are interconnected with unshielded wire in all cases except for the antenna-to-TR-switch and TR-switch-to-transmitter connections. RG-174 miniature coaxial cable is used for the latter connections. To avoid the possibility of creating unwanted oscillations, interconnecting wires should not run beneath the receiver board. PC-board terminals are used on my transceiver boards, but the wires can be soldered directly to the PC board. Notes concerning interconnection of the boards appear adjacent to each terminal in the transmitter schematic diagram, Fig. 9.

Initial Tests and Calibration

Because the VFO is needed to drive the receiver and transmitter boards, check it first. You may operate the VFO directly from the unregulated 15-V supply during these tests. See that U1 is supplying 3-V dc output, and that an RF signal output of approximately 4-V P-P is present at T30. For the moment, that's all for the VFO; its calibration will be done later.

With 15-V dc applied to the receiver board, check that U2 provides 12-V-dc output, and approximately 6-V dc is present at T15. Pins 1 and 7 of U1 should be at the same potential as T15. Connect a pair of headphones between T14 and ground. Short T13 and T16 together; white noise should be heard in the phones. Shorting T18 to ground should close K1, and adjusting R23 should vary the release delay from approximately 0.5 to 5 seconds.

Tune up the transmitter as follows. Connect a 5-W dummy load between T21 and



A top, inside view of the author's transceiver. The VFO PC board is at the front left, behind the GAIN and NULL potentiometers. The receiver board is at the rear of the unit. At the front right-hand side of the board is the doubly balanced mixer module. Almost directly behind it, near the rear panel, is the TR relay. The two cylindrical objects at the front center of the board are L1 and L2.



The transceiver viewed from the bottom. In this prototype, the RF output transistor has an elongated heat sink that runs parallel to the right side of the board.

T25. Set all mica compression trimmer capacitors for maximum capacitance (fully closed). Key the transceiver and see that 12-V dc is present at T22. Adjust C22 for maximum RF output across R16. Then adjust C24 for maximum RF voltage across L11. Set C29 and C30 for maximum RF voltage across R19. Last, adjust C32 and C33 for maximum output across the dummy load. Since C29, C30, C32 and C33 adjustments interact, the process will have to be repeated several times. During the final stages of tune-up, the trimmer-capacitor adjustments should provide smooth amplitude variations with no sudden jumps apparent. Monitor the temperature of Q8 closely during transmitter tune-up.

Adjust C3 to have the VFO cover the desired frequency range, and set the dial calibration. C5 provides temperature compensation. No noticeable drift should occur after an initial warm-up period of about 10 minutes.

The VFO offset during transmit is set by trimming the length of the gimmick capacitor, C16. Trim C16 to provide a downward VFO frequency shift of about 750 Hz when the transmitter is keyed.

Operation and Comments

Since the transmit frequency is shifted below the receive frequency, it is necessary to tune the receiver so the VFO frequency is above that of the received station. When the transmitter is keyed, the VFO frequency shifts down by 750 Hz and falls on the zero-beat frequency.

The transceiver has been in use for several months, and the improved receiver performance makes the redesign effort worthwhile. There is absolutely no audible amplitude modulation from the high-power 40-meter broadcast stations. The bandwidth of the receiver is adequate for CW reception, and no audio distortion or ringing is evident. In fact, the audio signal has good tone quality when personal stereo headphones are used with the receiver. The notch filter has proved useful; however, it is not a complete substitute for single-signal reception. When the transceiver is used to work other QRP stations, it is helpful to have a low-noise receiver since the received signals can be just above the 40-meter-band noise during the daylight hours. Get out your soldering iron and try your hand at building the receiver or the entire transceiver. I'm sure you'll be glad you did!

Acknowledgment

I'd like to thank Jim Conrad, N1GW, of Hewlett Packard, for his suggestions concerning the design of the receiver RF section and for his help with AM-detection measurements.

Notes

[1] D. K. Seimer, "The MAVTI-40," *QST*, June and July 1975. Also see Feedback, *QST*, Oct. 1975, p. 71.

[2] J. L. Keith, "40-Meter Transceiver for Low-Power Operation," *Ham Radio*, April 1980.

[3] R. W. Lewallen, "An Optimized QRP Transceiver," *QST*, Aug. 1980.

[4] J. A. Dyer, "High Frequency Receiver Performance," *Ham Radio*, Feb. 1984.

[5] C. Hall, "Tunable RC Notch," *Ham Radio*, Sept. 1975.

[6] Mini-Circuits Labs, P.O. Box 166, Brooklyn, NY 11235, tel. 718 934 4500.

[7] C. Hutchinson, ed., *The 1985 ARRL Handbook for the Radio Amateur* (Newington: ARRL, 1984), p. 12-19.

[8] Circuit boards and parts kits are available from Radiokit, P.O. Box 411, Greenville, NH 03048, tel. 603-878-1033. PC-board templates and parts overlays are available (note: this is a *double-sided* board) from ARRL Hq. for $2 and a business-sized s.a.s.e. Address your correspondence to the Technical Department Secretary and identify your request as MAVTI Updates.

[9] [Editor's Note: See D. DeMaw, "Plug-In Wall Transformers—A Super Bargain," *QST*, June 1985. On page 37, Doug relates one of his experiences with D-C receivers and hum pickup.]

For updated supplier addresses, see ARRL Parts Supplier List in Chapter 2.

From December 1989 QST, p 18:

A QRP SSB/CW Transceiver for 14 MHz

Part 1: Exotic circuitry and hard-to-find components aren't necessary if you want to build excellent performance into a home-brew SSB/CW transceiver: Careful design is the key.

By Wes Hayward, W7ZOI
7700 SW Danielle Ave
Beaverton, OR 97005



It's hard to justify the construction of a complete SSB/CW transceiver in this "modern" era of readily available commercial equipment. The popular, multiband MF/HF transceivers offer excellent performance, often at a reasonable cost. Still, I feel a twinge of guilt when I use them. They offer nothing of the feeling of exploration that I've grown to expect from Amateur Radio.

The rig described here is not a copy of the usual "appliance." I've used the project as a vehicle to investigate alternative circuits and a block diagram that departs from the traditional. The circuit is simple and modular, with flexibility that allows for later changes.

I present this rig in order to encourage other home-brew enthusiasts to give QRP SSB a try. I'll not dwell on the standard circuits that are already covered in *Solid-State Design* or in *The ARRL Handbook.*[1,2] Rather, I'll emphasize only those circuits that depart from the traditional. This is intended to be an idea article rather than a construction piece. There are no circuit boards or patterns available for this rig. All construction was done using "ugly" methods.[3]

System Architecture

The filter method was chosen for this transceiver. While that is generally considered to be "the only choice," phasing methods should not be overlooked for an experimental transceiver.[4] The block diagram is shown in Fig 1.

The traditional filter transceiver shares one or more crystal filters between the receive and transmit modes. I wanted to avoid the compromises and complexities of filter switching, so I decided to use separate filters for each function. The transmit and receive modules can then be used for completely independent operation. This might be especially interesting for use with, for example, a VHF/UHF station for OSCAR communications.

Commercial crystal filters from my junk box were used in this project. They are all 9-MHz circuits that are, fortunately, well matched to each other. A 5-MHz local oscillator drives both the receiver and transmitter mixers. Budget-minded builders may elect to built their own filters.[5,6]

The Receiver

The receiver is very much like the Progressive Receiver that's been in *The ARRL Handbook* for several years.[7] The front end and VFO are presented in Fig 2. I initially used a VFO variable capacitor with a vernier drive mechanism. Problems occurred with the mounting, however. The VFO was rebuilt without a vernier. Instead, two capacitors were used. One (C1, **BANDSET**) tunes the entire band, while the other (C2) is a bandspread control with a total range of only 25 kHz. This scheme seems to be practical for a simple transceiver.

The receiver begins with a doubly tuned preselector and a diode-ring mixer (U1, a Mini-Circuits SBL-1). This is followed by a bipolar transistor (Q3, an NEC99532) in a negative-feedback IF amplifier. A ferrite transformer (T4) matches the IF amplifier to the receiver crystal filter (FL1) as shown in Fig 3. The filter I used is similar to the KVG XF-9B. The less-expensive KVG XF-9A was tried in this application and was found wanting for stop-band attenuation.

The crystal filter drives an MC1350P IF amplifier (U2) and a diode-ring product detector (U3, an SBL-1). I would discourage a builder from departing from a diode-ring detector. An NE602 detector was tried, but suffered from severe in-band intermodulation distortion.

The BFO signal is low-pass filtered before driving the detector. A reduced-voltage sample of the BFO energy is routed to the transmit balanced modulator (to be described in Part 2 of this article). Care was taken to extract the sample from a point away from the detector. (The diode-ring detector clips the BFO waveform; clipped carrier-oscillator drive for the balanced modulator is undesirable.)

The audio amplifier (Q6-Q8 and U4) is standard. However, the audio-derived AGC system departs from the usual. U5A (one section of an LM324) amplifies the audio to a level suitable for

---

[1] Notes appear at end of article.


RX Input
14-MHz LC Band-Pass Filter
RX Mixer U1 SBL-1
9-MHz IF Amp NEC99532
Q3
-6 dB
9-MHz Crystal Filter, Bandwidth 2.4 kHz at -6 dB FL1
9-MHz IF Amp MC1350P
U2
R1 IF GAIN
Product Detector U3 SBL-1
AF Amp 2N3904s
Q6-Q8
R2
AF GAIN
AF Power Amp LM386
U4
AUDIO OUT
Current Limiter 2N3904
Q9
+12 V
Audio-AGC Amp LM324
U5
Detector 1N4152s
D5, D6
VFO Q1 2N4416
5-5.5 MHz
VFO Buffer 3N211
Q2
LC Low-Pass Filter
BFO Amp 2N3904
Q5
BFO Q4 2N3904
Y1 8998.5 kHz
TX VFO Driver 2N3904s
Q17, Q18
+10 dBm
TR Switch
K1
ANTENNA (50 Ω)
CW Carrier Osc 2N3904
Q14
Y2 8998.5 kHz
Carrier Osc Buffer 2N3904
Q15
MIC
TX Audio Amp 2N4416
Q16
741
U6
R3 MIC Gain
Balanced Modulator U7 MC1496P
IF Amp 2N3904
Q11
9-MHz Crystal Filter, Bandwidth 2.4 kHz at -6 dB FL2
IF Amp 2N3904s
Q12, Q13
TX Mixer U8 SBL-1
-3 dB
14-MHz LC Band-Pass Filter
Speech Processor
RF Limiter
Hot-Carrier Diodes
D11
D12
Q26
IF Amp 2N3904
9-MHz Crystal Filter, Bandwidth 2.5 kHz at -6 dB FL3
IF Amp 2N3904s
Q27, Q28
R7 PROCESSOR GAIN
Predriver 2N5179
Q21
+2 dBm
Driver 2N5859
Q22
Power Amp IRF511
Q23
14-MHz LC Low-Pass Filter
1 W
Jumper if Outboard Power Amp is Not Used.
Q29
Power Amp DV2880T
14-MHz LC Low-Pass Filter
10 W
OUTPUT TUNE
Outboard Power Amp

Fig 1—Blcck diagram of the 14-MHz SSB/CW transceiver.



0.005 FT
+12 V
1 k
D2
6.8 V
0.4 W
100
0.1
5–5.5 MHz
VFO
2.2 pF
NP0
L1
250
NP0
2.2
G
D
Case
22 µF
16 V
100 k
T1
J1
P1
D1
1N4152
1 M
Case
S
0.01
0.1
80
C1
BANDSET
Q1
2N4416
Q2
3N211
33
NP0
G2
D
VFO Buffer
G1
S
47
NP0
10 k
33 k
150
33
100
NP0
40
C2
BANDSPREAD
0.1
VFO to
TX Mixer,
Fig 4
B
SBL-1 Pinout,
Bottom View
Pin 1 = Blue
L4
L3
Except as indicated, decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); resistances are in ohms; k=1,000, M=1,000,000.
680
0.001
680
100
+12 V
0.1
L2
INPUT
PEAK 2
INPUT
PEAK 1
10 k
9 MHz to
T4, Fig 3
Receiver Input
From TR Switch
(Fig 5)
T2
100
C3
180
7
100
C4
150
47
200
U1
Mixer
SBL-1
1.5 k
0.1
T3
0.1
36
0.1
IF Amplifier
Q3 NEC
99532
150
150
−6 dB
2.2 k
100
4.7
0.1
250 pF,
total
198 pF,
total

Fig 2—Schematic of the transceiver front end and VFO. Resistors are ¼ W, carbon film; unless otherwise indicated, capacitors are monolithic or disc ceramic. The VFO circuitry is built into a die-cast aluminum box.

C1, C2—Panel-mountable, air-dielectric variable with ¼-inch-diam shaft.

C3, C4—100-pF ceramic- or mica-dielectric trimmer.

J1—Coaxial jack. (The prototype transceiver uses a panel-mount SMB jack here, but a BNC or phono jack is suitable.)

L1—23 turns of no. 22 enam wire on a T-68-6 toroidal, powdered-iron core, with a feedback tap 5 turns from the grounded end of the winding.

L2—11 turns of no. 24 enam wire on a T-44-6 toroidal, powdered-iron core.

L3, L4—25 turns of no. 24 enam wire on a T-37-6 toroidal, powdered-iron core.

T1—Broadband transformer: Primary, 16 turns of no. 26 enam wire on an FT-37-43 toroidal, ferrite core; secondary, 4 turns of no. 26 enam wire wound over the primary.

T2—Narrow-band transformer: Tuned winding, 11 turns of no. 24 enam wire on a T-44-6 toroidal, powdered-iron core; input link, 2 turns of no. 24 enam wire over the tuned winding's grounded end.

T3—Broadband transformer: 10 bifilar turns of no. 28 enam wire on an FT-37-43 toroidal, ferrite core. Observe phasing.

detection by D5. U5D functions as a unity gain inverter to drive a second diode (D6), providing full-wave detection. Each diode operates as a peak detector, providing one sample of the audio level per cycle. Full-wave operation doubles the sampling rate to better approach the Nyquist criterion. The practical result is a simple circuit with better dynamic performance than other audio-derived ones I've tried.

Notes

[1] W. Hayward and D. DeMaw, *Solid-State Design for the Radio Amateur* (Newington: ARRL, 1986).

[2] K. Kleinschmidt, ed, *The 1990 ARRL Handbook*, (Newington: ARRL, 1989).

[3] R. and W. Hayward, "The Ugly Weekender," *QST*, Aug 1981, pp 18-21.

[4] G. Breed, "A New Breed of Receiver," *QST*, Jan 1983, pp 16-23.

[5] W. Hayward, "Designing and Building Simple Crystal Filters," *QST*, Jul 1987, pp 24-29.

[6] W. Hayward, "A Unified Approach to the Design of Crystal Ladder Filters," *QST*, May 1982, pp 21-27; also see Feedback, *QST*, Jul 1987, p 41.

[7] W. Hayward and J. Lawson, "A Progressive Communications Receiver," *QST*, Nov 1981. Also see Feedback, *QST*, Jan 1982, p 47; Apr 1982, p 54; and Oct 1982, p 41. This receiver also appears in the 1982 through 1990 editions of *The ARRL Handbook*.


from 6-dB pad, Fig 2
T4
Receive Filter
FL1 9 MHz, 2.4 kHz BW
0.1
620
0.1
Receive IF Amplifier U2 MC1350P
+12 V
100
0.1
Vcc
INPUTS
OUTPUTS
GND
NC
INPUT
1.6 k
T5
U3 Product Detector SBL-1
+7 dBm
22 µF 16 V
Q6 2N3904
Q7 2N3904
Q8 2N3904
4.7 k
1 k
2.2 k
470
10 k
100
680
5.1 k
0.0022
47
Audio Amplifier
Q9 2N3904 Current Limiter
2.2 k
10
100 µF 16 V
R2 10 k AF GAIN
U4 LM386 AF Power Amplifier
100 µF 25 V
J2 AUDIO OUTPUT
R1 10 k IF GAIN
D3 1N4152
27 k
0.01
A
470
L5
L6
1000
to Balanced Modulator (U7, Fig 4)
430
D4 9.1 V 0.4 W
2N3904 Q4
BFO
510
Y1 8998.5 kHz
* 200
* adjusts BFO Frequency
T6 9 MHz
C5 180
BFO AMP TUNE
Q5 2N3904 BFO Amp
U5A LM324
Vcc
Gnd
AGC Amplifiers
Detectors
D5 1N4152
D6 1N4152
U5D
100 k
FAST
SLOW
OFF
S1 AGC
1.5 M
10 M
1 µF ceramic
AGC Amplifier U5C
D7 1N4152
D8 1N4152
D9 1N4152
2.2 µF 16 V
Q10 2N3904 Muting Switch
+12 V, Transmit

Except as indicated, decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); resistances are in ohms; k=1,000, M=1,000,000.

Fig 3—The transceiver receive filter, IF amplifier and detector circuitry. Resistors are ¼ W, carbon film; unless otherwise indicated, capacitors are monolithic or disc ceramic.

FL1—9-MHz crystal filter, 2.4 kHz wide at −6 dB (KVG XF-9B).

L5, L6—22 turns of no. 26 enam wire on a T-37-6 toroidal, powdered-iron core.

T4—Broadband transformer: Primary, 5 turns of no. 26 enam wire wound over the secondary winding; secondary, 16 turns of no. 26 enam wire on an FT-37-43 toroidal, ferrite core.

T5—Broadband transformer: Primary, 20 turns of no. 26 enam wire on an FT-37-43 toroidal, ferrite core; secondary, 3 turns over the primary.

T6—Narrow-band transformer: Primary, 20 turns of no. 24 enam wire on a T-50-2 toroidal, powdered-iron core.

Y1—8998.5-kHz crystal (KVG XF-901 suitable).

From January 1990 QST, p 28:

A QRP SSB/CW Transceiver for 14 MHz

Part 2: This month, W7ZOI rounds out his description of a 1- or 10-W SSB/CW rig with details on its transmitter, TR switching and optional speech processor.

By Wes Hayward, W7ZOI
7700 SW Danielle Ave
Beaverton, OR 97005



Most of the transceiver's components are contained in ugly-constructed modules, with the exception of the VFO (lower left) and panel-mounted controls and jacks.

SSB generation occurs in the circuit shown in Fig 4. A microphone amplifier (Q16-U6) supplies audio to an MC1496 balanced modulator (U7). One-microfarad capacitors (C6-C8) are used at the output of the audio amplifier and at several positions in the balanced modulator. (Originally, 10- or 22-μF units were used, but these caused the system to respond slowly during TR transitions.)

The modulator output is applied to Q11, a 2N3904 IF amplifier. This stage terminates the transmitter crystal filter and provides a convenient place for CW carrier injection. Another IF amplifier (Q12-Q13) follows the crystal filter. The **TX GAIN** control, R5, is set for an output of −10 dBm from Q13. This level is applied to the transmit mixer, or to the speech processor described later.

Fig 5 shows more of the transmitter. SSB energy at −10 dBm drives the transmit mixer, U8, another diode ring mixer. The 5-MHz VFO signal is amplified to +10 dBm for the mixer by Q17 and Q18. A 3-dB pad terminates the mixer, with the signal continuing to a three-pole, LC, band-pass filter. The first stage in the output-amplifier chain is Q21, a 2N5179 feedback amplifier with an output of +2 dBm. This signal is looped through a coaxial-cable jumper on the transceiver rear panel for use with VHF transverters.

The driver, Q22, a 2N5859, is capable of about +20 dBm output. Transceiver output is obtained from Q23, an IRF511 HEXFET® PA operating at the 1 watt output level. This power level is a little low for use on the air with dipoles, but is too high for many transverter applications.

Louder-Signal Options

Two additional circuits, shown in Fig 6, round out the SSB system. The first, at Fig 6A, is an IF speech processor. The processor is driven with a −10 dBm signal. This signal is clipped with parallel, reverse-connected, hot-carrier diodes (D11 and D12). The intermodulation products generated by the clipping are rejected by an additional crystal filter (FL3). The signal is then amplified back to the original −10 dBm level by Q27 and Q28. This circuit generates about 10 dB of clipping. Reports and measurements made on the clipped signal indicate good quality, a potential problem area with many speech processing systems.

Fig 6B shows a 10-watt-output FET power amplifier. The FET that I used (an M/A-COM DV2880T) is no longer available, but is similar to the Motorola MRF138. Alternatively, one could obtain several watts of output from another IRF511.[8] The TR switching in the transceiver is set up for an outboard PA.

Summary

This was a very enjoyable project, and one that I would recommend for other experimenters. The 20-meter phone band, however, can be a little intimidating for the QRP enthusiast.

A rig like this can probably be built and adjusted by those with only modest test equipment. A 15-MHz oscilloscope served as my test-equipment workhorse during construction of this project. A home-brew spectrum analyzer also served as a very useful tool, but is not required. Fig 7 shows the transceiver's CW output spectrum. The 270-Ω resistor and 0.56 μF capacitor associated with the base of Q20, Fig 6, provide CW rise and fall times of 1 and 1.5 ms, respectively. Careful measurement of signal levels during construction helps to keep the system spectrally clean.

Acknowledgments

The author gratefully acknowledges the photographic assistance of Dee Lynch, KA7NPN, and technical discussions with Jeff Damm, WA7MLH.

Fig 4—The transceiver SSB generator Resistors are ¼ W, carbon film; unless otherwise indicated, capacitors are monolithic or disc ceramic.

C9—60-pF, ceramic-dielectric trimmer.
C10, C11—35-pF, ceramic-dielectric trimmer.
FL2—9-MHz transmit filter, 2.5 kHz wide at −6 dB (KVG XF-9A).
T7—Broadband transformer: Primary, 10 bifilar turns of no. 28 enam wire on FT-37-43 toroidal, ferrite core; secondary, 3 turns of no. 28 enam wire over the primary. Observe phasing.
Y2—8998.5-kHz crystal (KVG XF-901 suitable).

Fig 5—The transmit mixer, driver, final amplifier and associated circuits. Unless otherwise indicated, resistors are ¼ W, carbon film, and capacitors are monolithic or disc ceramic.

C12-C14—60-pF mica- or ceramic-dielectric trimmer.
D13—1-A, 600-PIV diode.
K1—12-V dc relay.
L7-L9—20 turns of no. 24 enam wire on a T-44-6 toroidal, powdered-iron core.
L10—15-μH choke.
L11-L13—14 turns of no. 24 enam wire on a T-50-6 toroidal, powdered-iron core.
T8—Broadband transformer: Primary, 15 turns of no. 28 enam wire on an FT-37-43 ferrite, toroidal core; secondary, 4 turns of no. 28 enam wire over the primary.
T9, T10—Broadband transformer: 10 bifilar turns of no. 28 enam wire on an FT-37-43 ferrite, toroidal core. Observe phasing.

---

[8] W. Hayward and J. Damm, "Stable HEXFET® RF Power Amplifiers," Technical Correspondence, *QST*, Nov 1989, pp 38-39.


Fig 4
Transmit Audio Amplifier
Transmit IF Amplifier
+12 V, SSB
-20 dBm
T7
2.2 k
100
6.8 k
U7
MC1496P
Balanced
Modulator
BIAS
OUTPUT
CARRIER INPUTS
SIGNAL INPUTS
GAIN ADJ
V EE
22 µF 16 V
.01
470
1 k
10 k
0.1
C8 1 µF 16 V
C7 1 µF 16 V
C6 1 µF 16 V
R4 50 k
BALANCE
R3 10 k
MIC GAIN
to B, Fig 3 (300 mV from BFO)
U6 741
100 k
4.7 k
10 µF 16 V
22 k
3.3 k
(CASE)
Q16 2N4416
2.2 k
+12 V
J3 MIC
Carrier Osc Amp
Q15 2N3904
1.5 k
CW Carrier Osc
Q14 2N3904
220
+12 V, CW
Y2 8998.5 kHz
C9 60 CW OSC FREQ
+ 2 V, transmit
47
680
510
C11 35
FILTER OUTPUT TUNING
FL2 9 MHz 2.5-kHz BW
C10 35
FILTER INPUT TUNING
Q11 2N3904
270
Q12 2N3904
Q13 2N3904
R5 500 TX GAIN
C to TX Mixer (Fig 5) or Speech Processor (Fig 6)

Except as indicated, decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); resistances are in ohms; k=1,000.
IC pins not shown are unused
● = phasing


TX Mixer
14 MHz Band Pass Filter
+12 V
100
0.1
T8
51
U8
SBL-1
1
2
3
4
5
6
7
8
-3 dB
18
300
300
200
33
BPF TUNE
C12 60
L7
7
7
L8
BPF TUNE
C13 60
33
7
7
L9
BPF TUNE
C14 60
33
5 MHz from VFO (Fig 2)
10 k
0.1
22 k
Q17 2N3904
Q18 2N3904
10 k
1 k
180
0.1
TX LO Driver
C
9 MHz from TX IF amp (Fig 4) or Speech Processor (Fig 6)
200
T9
47
+12 V, Transmit
0.1
Predriver
2.2 k
Q21 2N5179
CASE
470
100
4.7
0.1
0.1
J6
P6
J7
P7
+2 dBm available here for XVTR
HF/XVTR
S4A
+12 V, keyed
J5
EXTERNAL KEYED DC
XVTR
HF
1 K
22
0.1
D10
6 V
0.5 W
BIAS
R6
2.5 k
0.1
10 k
T10
Driver
1.5 k
Q22 2N5859
470
47
4.7
0.1
0.01
0.01
51Ω
M1 0-300
mA
+12 V
0.6
100 µF 16 V
0.1
0.1
L10
Q23 IRF511
0.1
Power Amplifier
Low -Pass Filter
L11
L12
L13
250
470
470
250
J8
P8
J9
P9
1 W available here for externa power amp
to RX input (Fig 2)
J11
ANTENNA
TR Relay
K1
D13 1N847
S4B
HF
XVTR
J10
EXTERNAL +12 V ON TRANSMIT
+12 V
270
Q20 2N5401
470
Q24 2N5401
470
Q25 2N5401
120 0.5 W
2.2 k
2.2 k
S2
PTT
0.56
nonpolar
+12 V, keyed
1.5 k
J4
KEY
0.01
Q19 2N3904
10 k
10 k
TR and Keying Switches
S3
MODE
SSB
CW
to all "+12 V, transmit" points
to all "+12 V, SSB" points
to all "+12 V, CW" points

Except as indicated, decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); resistances are in ohms; k=1,000.

* Use heat sink.

Fig 5


Speech Processor
+12 V, transmit
100
0.1
510
From TX IF Amp
(C in Fig 4),
−10 dBm
4.7 k
Q26
2N3904
0.1
C15
35
FL3
9 MHz
2.5-kHz BW
C16
35
FILTER
TERMINATE
FILTER
TERMINATE
0.1
T11
100
2.2 k
510
200
0.1
D11
D12
(A)
+12 V, transmit
47
0.1
TX IF Amp
680
10 k
Q27
Q28
2N3904s
0.1
47
0.1
510
4.7 k
560
0.1
680
C, Fig 5
1 k
R7
PROCESSOR
GAIN
100
+25 V
2.2 k
R8
BIAS
10 k
680
300 µF
35 V
0.1
0.1
0.1
L14
10 k
External RF Power Amp
OUTPUT
J13
INPUT
J12
T12
0.01
0.1
T13
L15
L16
220
470
C17
90−480
470
FILTER
TUNING
Q29
DV2880T
18
(B)

Except as indicated, decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); resistances are in ohms; k=1,000.

Fig 6—The optional speech processor (A) and outboard power amplifier (B) circuits. Unless otherwise indicated, resistors are ¼ W, carbon film, and capacitors are monolithic or disc ceramic.

C15, C16—35-pF, ceramic-dielectric trimmer.

C17—90- to 480-pF, mica-dielectric trimmer.

D11, D12—Hot-carrier diode, HP-5082-2672 suitable.

FL3—9-MHz transmit filter, 2.5 kHz wide at −6 dB (KVG XF-9A).

L14—50 turns of no. 26 enam wire on a T-68-2 toroidal, powdered-iron core.

L15, L16—19 turns of no. 20 enam wire on a T-50-6 toroidal, powdered-iron core.

T11—Broadband transformer: Primary, 3 turns of no. 28 enam wire over secondary; secondary, 16 turns of no. 28 enam wire on an FT-37-43 toroidal, ferrite core.

T12—Broadband transformer: 7 bifilar turns of no. 22 enam wire on an FT-50-43 toroidal, ferrite core. Observe phasing.

T13—Broadband transformer: 11 bifilar turns of no. 18 enam wire on an FT-82-61, toroidal, ferrite core. Observe phasing.



Fig 7—The transceiver's output spectrum contains a second-harmonic component 63 dB below its 1-W CW output. The major nonharmonic spurious response is a 2:1 spur near 1.5 MHz ([2 × VFO] − IF); this component is −70 dBc. The spike at far left is the spectrum analyzer's "zero-spur." An external 20-dB pad in the coaxial line provided extra protection for the analyzer, a Tektronix 2756P. The spectrum-analyzer measurements were provided by Stan Griffiths, W7NI. The transceiver complies with current FCC specifications for spectral purity.

From October 1989 QST, p 25:

The QRP Three-Bander

This low-power, direct-conversion CW transceiver covers 18, 21 and 24 MHz, and includes sidetone, spotting and relay-less full break-in—all on one circuit board!

By Zack Lau, KH6CP
ARRL Laboratory Engneer



With this solar cycle's activity nearing its peak, the time for high-band QRP operation is *now*. This low-power CW transceiver is capable of exploiting these conditions. It's easy to use, sensitive enough to receive weak QRP stations, and includes audio limiting to protect your ears from loud local stations. Moving from band to band with this rig is easy: Just change crystals and re-peak its receiver input. Key down, the QRP Three-Bander produces its own sidetone—and RF, too: 1.25 to 4 watts, depending on the band, the dc supply voltage and the particular transistors used in the transmitter. And you can build the QRP Three-Bander *your* way: A complete kit of parts is available, or you can assemble your version using ground-plane construction.[1,2]

Circuit Description

Fig 1 shows the transceiver circuit. U1, an NE602N doubly balanced mixer IC, operates as a direct-conversion (D-C) product detector, converting the incoming signal directly to audio by mixing it with energy from Q2, a bipolar-junction-transistor (BJT) variable crystal oscillator (VXO). Although the NE602 achieves its conversion gain and low noise figure at the expense of dynamic range, it rejects AM-broadcast-band signals well when a capacitor is present across its differential output (pins 4 and 5).

To help prevent hum pickup, the NE602's audio output is amplified by a differential amplifier (U2A, half of an NE5532 low-noise, audio-op-amp IC), which feeds a moderate-gain filter stage (U2B). The final audio-amplifier stage (U3A, half of another NE5532) drives low-impedance stereo headphones at a comfortable level. Q1, a 2N5486 junction-field-effect-transistor (JFET) used as a switch, breaks the connection between U2B and U3A in transmit to keep keying clicks and thumps out of the headphones.

The QRP Three-Bander uses audio amplitude limiting instead of automatic gain control (AGC): Diodes in the filter and final-audio-amplifier stages (D1-D2, and D3-D4, respectively), and R18 (between the final audio amplifier and J2), provide ear and headphone protection by clipping the transceiver's audio output on strong signals.

Transmitter RF is generated by Q3, an MPS918 (or 2N5179) BJT operating as a VXO. Q3's output signal drives a buffer amplifier consisting of two BJTs: Q5, a 2N2222, and Q6, a 2N5109 (or selected 2N2222A). The buffer circuit is based on a design by Lewallen;[3] this version is re-biased for higher power output to make it more suitable for transmitters. The transmitter power amplifier, Q8, is an MRF237 BJT running class C. A seven-element low-pass filter (L1 through L3, and C37 through C40) reduces the harmonic content of the transmitted signal. Because this filter's cutoff frequency is high enough to pass the transceiver's 24-MHz output with little loss and yet is low enough to reduce harmonics of the rig's 18-MHz signal to a legal level, it requires no adjustment for band changes. Fig 2 shows the output spectrum of the Three-Bander's transmitter.

Full-break-in, relay-less TR switching is one of the QRP Three-Bander's finer points. The TR switch is a wide-bandwidth version of the switch used by Lewallen in his Optimized QRP Transceiver.[4] If you model this switch or measure its characteristics, you'll notice lots of passband ripple: The filter (C36, C41, C42, L4, L5 and L6) has steep skirts and three peaks corresponding to the bands covered by the transceiver. Although the calculated safe maximum-power-handling capability of this switch is just 1.4 W at 24.9 MHz, it seems to handle the transceiver output just fine. (A PIN-diode switch with appropriate biasing could handle more power, but PIN diodes are more difficult to find than ordinary switching diodes.)

The Three-Bander's transmitter section uses *differential keying*—a method of time-sequencing the keying of multiple transmitter stages to achieve a desired effect. As implemented in this circuit, differential keying helps eliminate chirp by turning on the transmit oscillator (Q3) before the buffer amplifier (Q5-Q6) comes on. This sequence is reversed at key up: The buffer amplifier turns off before the oscillator stops. Turning the oscillator on before the buffer gives the oscillator time to stabilize before the transmitter puts out RF; keeping the oscillator on after the buffer turns off assures that frequency changes by the turning-off oscillator won't be present in the transmitted signal.

To avoid key clicks—which would make the Three-Bander's signal wider than necessary for effective CW communication—the waveform of the transmitted signal is shaped in the buffer amplifier. Even though the transmitter power amplifier is nonlinear and tends to shorten the rise and fall times of its driving signal, the Three-Bander's transceiver's RF-output waveform is well-shaped, as shown in Fig 3. The open-circuit voltage at the **KEY** jack is positive, and about 0.5 V less than the transceiver's dc supply voltage; 1.3 mA flows in the keying circuit line when the **KEY** jack is shorted.

Getting the Parts

The tough part of building has nothing to do with soldering or making holes in metal: It's finding the parts! Fortunately, all the parts used in this project are sold by a number of suppliers—or you can buy a complete kit of parts from RADIOKIT, as detailed at Note 1.

Parts availability is one thing; parts cost is another. Aside from the crystals, variable capacitors C1 (**RX PEAK**), C22 (**RX FREQ**)

---

[1]Notes appear at end of article.

The QRP Three-Bander: Vital Statistics

The performance of the QRP Three-Bander varies with band, dc supply voltage and the particular active devices used. Two versions of the Three-Bander exhibit a receive sensitivity (minimum discernible signal, or MDS) between −124 and −128 dBm, and 3rd-order-IMD dynamic ranges between 71 and 74 dB. A third Three-Bander exhibits an MDS between −112 and −120 dBm, and a 3rd-order-IMD dynamic range between 67 and 69 dB. Operated at 13.8 V and using an MPS918 at Q3, two QRP Three-Banders produce 2.6 and 4.0 W at 18 MHz, 2.6 and 3.4 W at 21 MHz, and 1.7 and 2.5 W at 24 MHz. A third Three-Bander (with a hand-picked 2N3904 at Q3) produces 3.8 W at 18 MHz, 3.1 W at 21 MHz and 2.4 W at 24 MHz when operating at 13.8 V. Operating the Three-Bander at 13.8 V provides 3 to 70% more transmitter output power than that available with a 13.0-V supply.

Although the Three-Bander's receiver isn't unduly sensitive or crunch-proof, it's adequate for routine amateur communication. I had no difficulty in making 3rd-order-IMD dynamic-range measurements on the Three-Bander's receiver at the ARRL lab's standard 20-kHz spacing.

The frequency swing afforded by the Three-Bander's VXOs varies with the band, stray capacitances and the particular crystals and VXO tuning capacitors used. The crystals I used allowed swings of 8.9 to 16.2 kHz at 18 MHz, 8.4 to 17.6 kHz at 21 MHz, and 14.1 to 23.4 kHz at 24 MHz.—*KH6CP*

and C28 (**TX FREQ**) are probably the most expensive components in this project. You can save money by purchasing these capacitors from a surplus outlet or flea market, although they are still available new. In this application, the voltage rating and physical size of C1, C22 and C28 are relatively unimportant; these capacitors need only cover the necessary capacitance range. C1 must cover the range from 15 to 45 pF. VXO capacitors C22 and C28 should have a maximum capacitance of 10 to 50 pF (10 to 15 pF is optimum) and have a minimum capacitance of just a few picofarads—the lower the minimum capacitance, the better.[5] If you can't find air-dielectric variables at an affordable price, you can replace a given variable capacitor with a switch and several trimmer capacitors, as shown in Fig 1B for C1, **RX PEAK**; the transceiver shown in the title photo uses this arrangement. You may prefer the Fig 1B solution to C1 because flipping a switch is easier than peaking a tuning control; on the other hand, a front-panel peaking control can help you minimize interference from strong shortwave broadcasters, as discussed later in "Using the Radio on the Air." This switch-and-trimmers idea can also be applied to the transceiver VXOs; you can readjust the trimmers if your preset frequencies are occupied.

The crystal frequencies you choose depend somewhat on the particular VXO tuning capacitors you use. A VXO with a maximum tuning capacitance of many tens or even hundreds of picofarads (so much capacitance that the crystal is essentially shorted to ground with the tuning capacitance at maximum) may oscillate as much as 10 kHz below the frequency marked on the crystal. If, however, you use capacitors with maximum capacitances in the range I've specified, your VXOs should oscillate within a few kilohertz of the crystal frequency.

If you want to get your transceiver working on all three of its bands with minimal experimentation, use a 2N5109 at Q6 to ensure adequate drive to the final amplifier at 24 MHz. A *metal-cased* (TO-18) 2N2222A may work if you're willing to try several transistors at Q6 before settling on one. (I was able to use metal-cased 2N2222As in two out of the three QRP Three-Banders I've built.) If you're interested in using your Three-Bander only at 18 and 21 MHz, *any* TO-18 2N2222A will probably work at Q6.

One of home-brewing's benefits is that you can use connectors of your choice. I like to use BNC connectors as antenna jacks on HF gear. Although I don't necessarily agree with others' choices, I've seen UHF, N, and even phono connectors used for antenna connections at MF and HF. This transceiver uses phono jacks for power and keying connections. (Beware of using



Fig 2—Worst-case spectral display of the QRP Three-Bander. Each horizontal division represents 10 MHz; each vertical division represents 10 dB. The spike at far left (the spectrum analyzer's first-local-oscillator signal) serves as a convenient "0 MHz" reference. When this spectrogram was taken, the QRP Three-Bander was producing 4 W (14.08-V dc supply) at 18.07 MHz. All harmonics and spurious emissions are at least 36 dB below peak fundamental output. The QRP Three-Bander complies with current FCC specifications for spectral purity.

Fig 1—*(Appears on following two pages.)* Schematic of the QRP Three-Bander. All resistors are ¼ W, carbon film. The inset, B, shows how to replace C1 with a switch (S2) and three trimmer capacitors (C44-C46); if you use this variation, peak C44 at 24 MHz *before* adjusting C45 and C46 for maximum received-signal strength at 21 and 18 MHz.

C1—50 pF, air dielectric, variable (Millen 21050 7- to 45-pF ceramic trimmers, used in ground-plane version, and switch and trimmers [S2 and C44-C46, Fig 1B] have been used successfully). See text.
C2, C24—0.0056 μF, ceramic.
C3, C8, C10, C19-C21, C23, C27, C29, C32-C35, C43—0.022 μF, ceramic.
C4, C11, C18—1-μF, 16-V tantalum electrolytic.
C5, C6, C15—0.22 μF, metal film.
C7, C9—0.0022 μF, metal film (Bessel AF filtering). Use 0.0027 μF for tighter, Chebyshev filtering.
C12, C13—0.010 μF, metal film (Bessel AF filtering). Use 0.012 μF for tighter, Chebyshev filtering.
C14—0.056 μF, metal film.
C16—0.0015 μF, polypropylene.
C17, C31—4.7-μF, 16-V, tantalum electrolytic.
C22, C28—14 pF, air dielectric, variable. (Millen 21015 capacitors and Johnson 189-series trimmers have been used successfully. Several months of on-air-use caused severe wear in the **RX FREQ** Johnson 189-series capacitor, however; use a tuning, not trimmer, capacitor at **RX FREQ** for longest capacitor life.) See text.
C25—0.015 μF, metal film.
C26, C30—0.082 μF, metal film.
C36, C42—15 pF, silver mica.
C37—100 pF, silver mica.
C38, C39—240 pF, silver mica.
C40—120 pF, silver mica.
C41—220 pF, silver mica.
C44-C46—30-pF plastic trimmer (optional). Used in conjunction with S2, these capacitors replace C1. See text.
D1-D9—1N914 or 1N4148 silicon switching diode.
J1—Phono jack.
J2—1/8-inch stereo phone jack.
J3—BNC jack. See text.
L1, L3—Toroidal inductor, 12 turns of no. 26 enam wire on a T-25-6 powered-iron core (0.46 μH).
L2—Toroidal inductor, 13 turns of no. 26 enam wire on a T-25-6 powdered-iron core (0.52 μH).
L4, L6—Toroidal inductor, 26 turns of no. 24 enam wire on a T-44-2 powdered-iron core (3.8 μH).
L5—Toroidal inductor, 9 turns of no. 24 enam wire on a T-25-6 powdered-iron core (0.26 μH).
Q1—2N5486 JFET. A 2N4416, 2N5485, 2N5484 or MPF102 should also work.
Q2—2N3904 BJT.
Q3—BJT, MPS918 or 2N5179 recommended. A 2N3904 will work, but may exhibit faster keying rise and fall times at 24 MHz than those shown in Fig 3, and the transceiver's RF power output may be suboptimal.
Q4, Q7—2N3906 BJT.
Q5—2N2222 BJT. A 2N3904 will also work.
Q6—2N5109 RF-power BJT. A selected metal-cased (TO-18) 2N2222A will work; some 2N2222As may not have enough gain for optimum power output at 24 MHz. See text.
Q8—Motorola MRF237 RF-power BJT.
R1, R6, R17, R18, R21, R27, R41—100 Ω.
R2, R3, R12—2.2-kΩ (Bessel AF filtering).


Audio Filter
Differential Amp
Detector
R1 100
C4 1 μF 16 V
C7 0.0022
+13.8 V
R6 100
U4 78L05
Reg IN OUT GND
R9 1 k
D1 1N914
D2 1N914
R10 10 k
U1 NE602
VCC OSCILLATOR
INPUT A
OUTPUT A
OUTPUT B
INPUT B
OSCILLATOR
GND
NC
R4 75 k
C10 0.022
1 μF 16 V C11
C12 0.010
U2A NE5532
U2B
T1
to C42
C1 RX PEAK
C2 0.0056
R2 2.2 k
C5 0.22
C3 0.022
R3 2.2 k
C6 0.22
C8 0.022
R5 75 k
C9 0.0022
R7 4.7 k
R8 75 k
C13 0.010
J1 KEY
C23 0.022
C24 0.0056
R19 10 k
SIDETONE LEVEL
R36 47 K
Sidetone Osc
C25 0.015
U3B
R35 47 k
R34 100 k
R33 100 k
D6 1N914
D7 1N914
R25 100 k
R31 10 k
Switch
R26 22 k
C26 0.082
+13.8 V
R32 1 k
C30 0.082
Switch
Q4 2N3906
SPOT S1
Q7 2N3906
C31 4.7 μF 16 V
C32 0.022
C34 0.022
R21 100
+13.8 V
C20 0.022
T2
Q2 2N3904 RX Osc
R22 4.7 k
C21 0.022
R24 47
Y1
R20 1 k
R23 1 k
RX FREQ C22
R27 100
C27 0.022
T4
*Q8 MRF237
R42 47
Power Amp
R40 15 k
T3
R38 4.7 k
R37 47
Q5 2N2222
Buffer Amp
Q6 2N5109
Buffer Amp
R39 470
R41 100
C33 0.022
Q3 MPS918 or 2N5179 TX Osc
R29 4.7 k
C29 0.022
case (2N5179 only)
Y2
R28 270
R30 1 k
TX FREQ C28

Except as indicated, decimal values of capacitance are in microfarads (μF); others are in picofarads (pF); resistances are in ohms; k=1,000, M=1,000,000

*Heat sink required; see text
● = phasing
SM = silver mica

Fig 1



GAIN
R13
NC
100 k
C16
0.0015
Audio Amp
D3
1N914
D4
1N914
Audio Switch
S
D
R12
2.2 k
C15
0.22
4.7 µF
16 V
R18
100
C17
J2
STEREO
PHONES
Q1
2N5486
C14
0.056
R14
10 k
U3A
NE5532
R15
47 k
C18
1 µF
16 V
R17
100
C43
0.022
R16
47 k
D5
1N914
+13.8 V
C19
0.022
C35
0.022
L1
L2
L3
ANT
J3
C37
100 SM
C38
240 SM
C39
240 SM
C40
120 SM
C36
15 SM
D8
1N914
D9
1N914
MRF237
bottom, metal 2N2222
L4
L6
C42
15 SM
to T1, lead 1
top view, NE602 and NE5532
8 7 6 5
1 2 3 4
C41
220 SM
L5
2N3904, 2N3906, MPS918 and plastic 2N2222
2N5486
G S D
78L05
OUT GND IN
2N5179
CASE
to U1, pin 1
C44
24-MHz
RX PEAK
S2
center off = 24 MHz
21 MHz
18 MHz
C46
21-MHz
RX PEAK
C45
18-MHz
RX PEAK
(B)

Use 3.3-kΩ for tighter, Chebyshev filtering.
R4, R5—75 kΩ.
R7, R22, R29, R38—4.7 kΩ.
R8—75 kΩ (Bessel AF filtering). Use 56-kΩ for tighter, Chebyshev filtering.
R9, R20, R23, R30, R32—1 kΩ.
R10, R14, R31—10 kΩ.
R11—1 MΩ.
R13—100-kΩ, audio-taper potentiometer.
R15, R16, R35, R36—47 kΩ.
R19—10-kΩ, audio-taper potentiometer.
R24, R37, R42—47 Ω.
R25, R33, R34—100 kΩ.
R26—22 kΩ.
R28—270 Ω.
R39—470 Ω.
R40—15 kΩ.
HFC1—Toroidal RF choke. Use 6 turns of no. 26 enam wire on an FT-37-43 ferrite toroid (10 µH).
S1—Normally open, momentary pushbutton.
S2—SPDT, center-off toggle (optional). Use only if C1 is replaced with C44, C45 and C46. See text.
T1—Narrow-band transformer, 10.5:1 turns ratio; 21 turns of no. 26 enam wire on a T-30-6 powdered-iron toroid (primary, 1.75 µH). Secondary has 2 turns of no. 24 or 26 enam wire over primary winding.
T2—Broadband transformer, 10:1 turns ratio; 20 turns of no. 26 enam wire on an FT-37-43 ferrite toroid (primary). Tap is 13 turns from the collector. Secondary has 2 turns of no. 24 or 26 enam wire over primary winding.
T3—Broadband transformer, 5:1 turns ratio; 20 turns of no. 26 enam wire on an FT-37-43 ferrite toroid (primary); tap at 13 turns from the collector end. Secondary has 4 turns of no. 24 or 26 enam wire over primary winding.
T4—Broadband transformer, 3:1 turns ratio; 9 turns of no. 26 enam wire on an FT-37-43 ferrite toroid (primary). Secondary has 4 turns of no. 24 or 26 enam wire over primary winding.
U1—NE602 mixer IC.
U2, U3—NE5532 dual low-noise op-amp IC.
U4—78L05 5-V regulator IC.
Y1, Y2—Fundamental crystal, HC-25/U holder, parallel resonance, 20- or 32-pF load capacitance. See text for discussion of frequency choice. Available from International Crystal Mfg Co, 701 W Sheridan, PO Box 26330, Oklahoma City, OK 73126-0330, tel 405-236-3741; JAN Crystals, 2341 Crystal Dr, Ft Myers, FL 33906-6017, tel 800-237-3063; and other sources.

For updated supplier addresses, see ARRL Parts Supplier List in Chapter 2.

The title photo version of the QRP Three-Bander uses the switch-and-capacitors scheme shown at Fig 1B instead of C1, and Johnson air-dielectric trimmers for RX FREQ (C22) and TX FREQ (C28). Acrylic blocks machined to take set screws and the trimmers' 3/16-inch-diameter shafts serve as tuning knobs. The board is 4 × 5-3/8 inches in size.



Fig 3—The QRP Three-Bander's CW-keying waveform at 18.07 MHz. The upper trace is the RF envelope; the lower trace depicts the actual key closure. Each horizontal division represents 5 ms.

phono jacks with batteries—phono plugs can short-circuit all too easily. I use Molex® connectors and fuses with my battery packs for safety.) The presence of identical keying and power-supply connectors isn't a problem with this rig: Nothing blows up if the key and power-supply cables are interchanged.

Construction Details

Decide early on whether you'll build the transceiver over a ground plane or on a PC board. If you decide to build a PC-board version, I highly recommend glass-epoxy (G-10 or FR-4), copper-clad circuit board over cheap phenolic board because of glass-epoxy's generally higher quality—and because glass-epoxy's greater heat tolerance allows the desoldering and replacement of components with minimal damage to the board. (This is especially important if you're new to building; you may need to fix wiring goofs.) I've made the copper pads for the wires between the board and off-board components extra large, just in case you have to do a lot of resoldering. (Small pads tend to lift off the board if subjected to too much soldering heat.) This is a trade-off in the case of the VXO-capacitor wires, though: The narrower the pads for C22 and C28 wires, the wider the VXO tuning range per crystal.

Whether you build your transceiver on a PC board or with ground-plane construction, I recommend that the transceiver circuitry be completely shielded when in use. It's important that there be grounded metal between the VXO capacitors and your fingers. Otherwise, you may experience the magic-wand effect that long-time hams call *hand capacitance.* (The VXO-capacitor stators [immovable plates] are at a high impedance above ground, and nearby objects—including you—can be "seen" by those circuit points unless a grounded shield is interposed. You shouldn't be able to tune your receiver just by bringing your hand close to the tuning knob!) Complete shielding of the transceiver circuitry also helps minimize hum and microphonics in the NE602 detector, especially when the transceiver is used with a poor RF ground.

Wind your inductors and transformers before you start wiring the circuit. Amateur radio-equipment builders commonly count coil turns wrong; this usually results in coils wound with one turn too many. (Hint: With toroids, just passing the wire through the core counts as one turn.)[6,7]

Because this is an RF project, keep component leads short, as shown in the photographs. Long leads can induce excessive noise and hum into the circuit. (If you're *really* unlucky, overlong leads may cause the circuit to oscillate when it should be amplifying.) Transformers T1 through T3 aren't critical with regard to mounting—they can either lie flat or stand upright. (Some builders like to glue toroids down; I skip the glue so the coils can be removed easily if necessary.) I used screws, lock washers and ¼-inch-long metal spacers to mount my transceiver boards in their boxes.

Q8, the transmitter power amplifier, must be heat-sinked. Because the MRF237's case is connected to the transistor emitter (instead of the collector, as is usually the case with metal-cased BJTs), you can heat-sink Q8 merely by soldering its case to the circuit-board ground foil (or to the ground plane, if you're undertaking ground-plane construction.) That's what I did in my Three-Bander. One small solder joint does the job; you needn't solder the entire case perimeter.

I used three-hole-mount phono jacks (two holes for mounting screws and one for the jack barrel) because they don't loosen with use as easily as single-hole mount types do. For the same reason, I took the time to drill the extra holes necessary to seat the anti-rotation tabs on the **GAIN** and **SIDETONE LEVEL** controls because seating the tabs—instead of breaking them off—results in controls that almost never work loose from the panel.[8]

Testing

None of the Three-Bander's circuits need be trimmed or aligned beyond the adjustments possible with its panel controls, so you need only verify that it works. I suggest powering the transceiver with a small supply during testing—a 12- to 15-V regulated power supply capable of producing no more than 0.5 to 1 A is fine. (A supply capable of sourcing 7 or 10 A invites the possibility of serious smoke and component destruction if you make a wiring mistake. Don't use batteries, either: Short-circuited, they can source enough current to melt wires!)

The first test is to determine whether or not the Three-Bander can hear its own transmit oscillator. Set the **GAIN** control to the middle of its rotation. Plug in crystals

On the Air with the QRP Three-Bander

What can you expect of the QRP Three-Bander? In three brief operating periods, I snagged OK3CQR, EA8AB, OK2KFM, KK6H, WB6YBT, AF4S and W9MNU at 18 MHz, and KF5OL and G3FGT at 21 MHz—nine contacts, four countries, four states and three continents. The antenna? Fifty or so feet of wire tossed in a tree and worked against a baseboard-heater "ground."

The QRP Three-Bander's receiver is more than satisfactory, considering its simplicity. There's audio to spare; I didn't have to run the **GAIN** control wide open all the time. The receiver is a bit microphonic, but not annoyingly so. I heard a bit of hum at some settings of the **RX PEAK** control—probably because I used an ac-operated power supply in conjunction with my crummy RF ground. Sometimes, I had to use **RX PEAK** to minimize AM "breakthrough" from strong 17- and 21-MHz broadcasters. All this means is that I'll build my version of the QRP Three-Bander with a front-panel-peakable front end. (I didn't hear one iota of breakthrough from local medium-wave broadcasters, by the way.)

Full break-in is fun with the QRP Three-Bander. Zack Lau has solved several problems at once by incorporating audio limiting into this transceiver: "De-thumping" the rig's TR switching, protecting the operator's ears and headphones from overdrive, and ridding the rig's sidetone of monotony. (In transmit, you hear the sidetone [assuming that you've set its **SIDETONE LEVEL** control to allow this, of course], a tone corresponding to the frequency difference between the receive and transmit VXOs, *and* the products of intermodulation between these signals as they mix in the Three Bander's audio-limiting circuitry. Result: The rig's "sidetone" rarely sounds the same two QSOs in a row!)

The QRP Three-Bander's differential keying is a class act. Listened to with my NRD-525 receiver, the Three-Bander's CW sounds absolutely A1 (pun intended) at 18, 21 and 24 MHz. (No "*Sure* the keying's too hard—but heck, it's QRP" excuses are necessary for *this* low-power rig.) If you must key an oscillator for CW, this is how to do it.

Working all continents will be easy with this rig. Who'll be first to work all *states* with a Three-Bander? It probably won't be me—at least, not unless I build mine soon: Other HQ staffers are lining up for *their* stints with KH6CP's QRP Three-Bander!—*David Newkirk, AK7M*

How About Modifying the QRP Three-Bander?

I'm sure that many of you would like this transceiver to cover different bands—14 or 28 MHz, for instance. The problem is that if I'd taken the time to work out the details of all such permutations before publishing this article, you'd never have *seen* this article! The first step in getting a successful equipment design off the drawing board and into reality is defining the limits of what you want to accomplish—so I decided to design the QRP Three-Bander to cover only the 18, 21 and 24-MHz amateur bands. That said, though, I do have some untested Three-Bander-modification hints for the adventurous.

First of all, most of the QRP Three-Bander's RF circuits are broadbanded enough to cover the HF spectrum without modification. The exceptions are the NE602's tuned input circuit (C1-T1), the transmitter-output low-pass filter (C37-C40, L1-L3), and the TR switch filter (C36, C41, C42, and L4-L6). The variable crystal oscillators should work fine from 3.5 to 28 MHz with fundamental-mode crystals; keep in mind, however, that a VXO's tuning range generally *decreases* as the crystal frequency is lowered.

You may need to add a few more turns to T4's primary winding on the low bands, but T4 is pretty broadband, too.

The TR switch is a bit tricky to design—you can't get the peaks in a high-ripple band-pass filter to fall exactly where you want them merely by poking at a calculator—but you can always use Lewallen's single-band version (see Note 4 of the main text). If you use a rotary switch for the TR circuit, receiver front end and transmitter output filter, getting the QRP Three-Bander to cover five or six bands shouldn't be *too* difficult. . . .—*KH6CP*

at Y1 and Y2, both on the same frequency, and set the **RX PEAK**, **RX FREQ** and **TX FREQ** capacitors so that their plates are half meshed. Press the **SPOT** button and adjust **RX FREQ** to find the transmitter signal. If you're lucky, you now have an expensive code-practice oscillator! If you can't hear anything at all, even after trying the entire range of the **GAIN** control, there's a fault in the receiver audio chain.

If you can meter your power supply's output current, you can confirm that the transmitter works by attaching a 50-Ω dummy load to (a 2-W carbon or metal-oxide resistor) and briefly shorting the **KEY** jack. If the transmitter is working, the transceiver's current drain should increase to 200 or 300 mA with keying. You can also use an oscilloscope, RF wattmeter or RF voltmeter to measure the transmitter output.

Using the Radio on the Air

The ultimate test of a home-brew rig is making contacts. Although D-C receivers are notorious for fooling their operators into transmitting on the wrong frequency, the QRP Three-Bander's independent transmitter and receiver oscillators can help you avoid this problem. Perhaps the easiest way is to let other stations tune you in properly by calling CQ on a clear frequency! The second way to be sure you've spotted your transmitter on the other station's frequency is to adjust **TX FREQ** so that your spotting signal (1) has the same pitch as the incoming signal and (2) "tunes the same way" as the incoming signal. In other words, if, once you've spotted your transmitter, adjusting **RX FREQ** causes your spotting signal to rise in pitch as the incoming station falls in pitch, or vice versa, you've set your transmitter to the wrong frequency and must readjust it to "the other side of zero beat" to put your signal in the other station's receiver.[9] Another approach is to adjust **RX FREQ** for zero beat with the incoming signal, press **SPOT**, and adjust **TX FREQ** to zero beat your transmitter to your receiver *and* the incoming signal. Once you've done this, adjust **RX FREQ** to receive the incoming signal at the pitch you want. This latter approach works well on a busy band: After you've spotted your transmitter, readjust **RX FREQ** to receive the less-interfered-with "side" of the received signal. (Incidentally, you can zero-beat your transmitter to fairly strong incoming stations by pulling out the receive crystal [Y1] and adjusting the spotting signal to zero beat. In this case, the spotting signal acts as the receiver local oscillator. The spotting and incoming signals will have exactly the same pitch when you plug the receive crystal back in.)

Adjust **RX PEAK** for maximum received-signal strength. If no man-made signals are audible, adjust **RX PEAK** for maximum background noise. You can also use this control as an attenuator by mistuning it—a useful feature when strong signals overload the rig's mixer. Usually, detuning **RX PEAK** just enough to reduce the culprit signal below the overload point preserves sufficient desired-signal sensitivity for you to keep operating.

Adjust the **GAIN** control for a comfortable listening level; this control does not affect the sidetone level. For finding stations, I adjust **GAIN** so I can just hear the background noise.

The **SIDETONE LEVEL** control adjusts what its name implies. Although a sidetone is unnecessary with a straight key, it's quite handy—if not essential—with electronic keyers.

The **SPOT** button turns on the QRP Three-Bander's transmit oscillator, allowing you to adjust your transmit frequency without actually transmitting a signal on the air. (Sweeping a signal across a band is considered poor amateur practice—even for antenna testing.)

Summary

The QRP Three-Bander gets you going on three of our hot high bands in style, and with enough power to work the world. Build it, use it—and have fun!

Notes

[1] Kits of parts for the QRP Three-Bander are available from RADIOKIT, PO Box 973, Pelham, NH 03076, tel 603-437-2722, for $99 each, plus $4 each for shipping via the United Parcel Service in the US. (Canadian and overseas orders are welcome; contact RADIOKIT for details.) The kit price includes a PC board, an unpainted Ten-Tec enclosure and all QRP Three-Bander components *except crystals*. The ARRL and *QST* in no way warrant this offer.

A PC-board template and parts overlay for the QRP Three-Bander are available for a business-size SASE from the Technical Department Secretary, ARRL, 225 Main St, Newington, CT 06111.

[2] This technique, also known by the unfortunate pejorative term *ugly construction*, entails supporting circuit components—connected directly to each other by short leads—above a thin copper sheet (ground plane). Despite their appearance, circuits built in this way generally work better than their PC-board-built counterparts because air is a better dielectric than fiberglass or phenolic. Builders well-versed in ground-plane construction can generally build the ground-plane version of a given circuit faster than its circuit-board equivalent.

[3] R. Lewallen, "An Optimized QRP Transceiver," Feedback, *QST*, Nov 1980, p 53.

[4] R. Lewallen, "An Optimized QRP Transceiver," *QST*, Aug 1980, pp 14-19. I highly recommend this article to anyone who wants to build a 40-meter QRP transceiver.

[5] Most of the frequency variation provided by C22 and C28 occurs at the low-capacitance end of their capacitance spans. Thus, achieving the smallest possible minimum capacitance at C22 and C28 is especially important to builders who duplicate this project with ground-plane construction because of the generally lower stray capacitances this construction method affords. Less stray capacitance in the VXO circuit maximizes the VXO tuning capacitor's contribution to capacitance *change* in the circuit.

[6] Fig 70 on page 2-37 of the 1989 *ARRL Handbook* shows several aspects of toroid construction, including how to count toroid turns accurately, and how to wind a toroidal transformer (like T1, T2 and T3 in this project).—*Ed.*

[7] The inductances listed for L1 through L6 are *measured* values. If you attempt to verify these inductances by using well-known toroid-inductance formulas to work backward from the core and turns values given, you'll come up with different inductance values. This is so because simple formulas for calculating the inductance of toroids tend to overestimate the inductance. (Such formulas are easy to spot: They fail to take wire thickness into account, returning the same inductance whether you use wire so thick you can barely wind it, or hairlike wire that's nearly invisible!)

[8] These are important considerations in portable QRP operation because you've usually left the necessary retightening tools at home!

[9] Because the days when radio amateurs routinely tuned for replies over a significant portion of a band are long gone, accurately spotting your transmitter is important. Spotted on "the wrong side of zero beat," but at the same pitch as the incoming signal, your transmitter is twice that pitch away from the incoming signal—for example, *1.4 kHz away* from an incoming signal tuned to produce a 700-Hz pitch.—*Ed.*

From February 1975 QST, p 16:



QRP TRANSCEIVER FOR 50 MHZ

Three watts PEP will do it on 6!

Part 1

BY PETER J. BERTINI,* K1ZJH

The "World Above 50 Mc" has lured an increasing number of amateurs, over more than four decades. One of its major attractions has been the effectiveness of low-power gear, especially the portable variety. But with the advent of single-sideband, some of the fascination with vhf operating has tended to fade, especially on the 50-MHz scene, where 200-watt transceivers and the inevitable 2-kW linears tend to make this band seem little different from lower amateur frequencies. After all, how many stations can operate on 50.110, all at once, and not have a rat-race reminiscent of DX pileups on 20? Fortunately there is a difference — there is plenty of room for everyone in the 50-MHz band, and if we just move up a little in frequency, low power works extremely well. Here's an attractive way to get into the QRP game on 6.

AFTER GOING the high-power route for several years, this author decided that QRO was not his cup of tea, and 6-meter activity fell into a state of desuetude until fairly recently. After reading numerous articles by W1CER and other exponents of the QRP cult, we could see no reason why this philosophy should be applied to the hf bands only, especially when the wide-open spaces in the vhf realm are considered. The 50 MHz band should be ideal for QRP work, on cw or ssb. It offers more opportunities for DX, and a greater variety of propagation media than higher bands, and there is more general use of ssb, a mode well-adapted to QRP techniques, now that solid-state gear is "the way to go."

We set to work, and the result is a small package ideally suited to Field-Day type excursions and local mobiling. It is also a very practical primary or back-up rig for the 50-MHz home station. Its robust 3-watt PEP signal is hardly distinguishable from that of stations running 100 watts or more, when a good antenna system is used — and "neighbor trouble," the bane of so many urban 6-meter operators, is virtually nonexistent.

As can be seen from the first photograph, the transceiver is self-contained except for the power supply. This could have been built-in, but a separate power source is advantageous. It allows use of an ac supply at home, direct connection of a car battery for mobile work, or operation from any of several types of portable batteries, including the 15-volt rechargable units often used with solid-state TV sets.

Eleven separate printed-circuit subassemblies are used, each a basic component of the transceiver circuitry. This allowed individual experimentation and trouble-shooting, and it leaves the way open for changes or additions without complete re-building. Board templates and layouts are *not* available. Construction of such a rig is beyond the capabilities of the novice builder. Experienced constructors interested in duplication, or use of some of the items described, should have little trouble working from the individual schematic diagrams and text.

As will be seen from the block diagram, Fig. 1, the principles involved are not unlike those of crystal-filter ssb transceivers for lower frequencies, but applying these principles is simplified in a one-band design. That "good things come in small packages" is amply proven by the simplification resulting from use of integrated circuit packages wherever possible. They make a marked reduction



Fig. 1 — Block diagram of the K1ZJH 50-MHz transceiver. Each item shown is a separate circuit-board assembly. Numbers in parentheses are the order of their description in the text. Transmitting and receiving functions are given adjacent to the signal-path lines. Items 1 through 6 are described in Part I.

---

* 20 Patten Road, Somers, CT 06071.

in number of parts required, in several key areas. A small crystal filter is the heart of the system, mainly responsible for the excellent performance, both transmitting and receiving. The dual conversion lineup will be discussed in step-by-step order, to avoid confusion, following the numerical order indicated in Fig. 1.

Receiver Front End

Eliminating the rf amplifier stage in a "good" vhf receiver is usually considered a bit unorthodox, and is frequently stereotyped with poor performance and cost cutting. This holdover from vacuum-tube limitations is now something of an "old wives' tale," as the noise figure of a well-designed transistor mixer for 50 MHz can be lower than the external noise encountered in most amateur operation. Especially where simplicity is a factor, eliminating the rf amplifier offers a desirable trade-off between sensitivity and good strong-signal overload capability. It is interesting to note that some of the finest commercial mobile receivers for vhf service do not use rf amplification ahead of the mixer stage. Especially for use with a very low-powered transmitter, the ultimate in low noise figure is certainly not important in a 50-MHz receiver.

Some types of rf gain-control systems introduce nonlinearities in the receiver front end, increasing susceptibility to overloading and cross-talk. This problem is avoided with the use of a miniature 500-ohm control, R1, across the receiver input, which serves as a simple yet effective rf gain control. Though the mixer transistors, Q1 and Q2, are dual-gate MOSFETs with built-in transient-suppression diodes, additional protection is provided with 1N914 diodes, connected in opposite polarity across the receiver input.

The incoming 50-MHz signal passes through three lightly coupled toroidal *LC* circuits in a simple band-pass network, for reasonable rejection of out-of-band signals. The first of two mixers converts the 50-MHz signal to 14 MHz. Injection at 36 MHz is generated by an overtone crystal oscillator, also used in the transmitting section for up-conversion, 14 to 50 MHz. The 14-MHz i-f passes through a simple *LC* network to preserve bandwidth. The signal is then mixed with the 5-MHz VFO output in a second 40673 stage, producing the second i-f, 9 MHz. The injection level at gate 2 of both mixers is 1.5 V pk-pk,



EXCEPT AS INDICATED, DECIMAL VALUES OF
CAPACITANCE ARE IN MICROFARADS (µF) ;
OTHERS ARE IN PICOFARADS (pF OR µµF);
RESISTANCES ARE IN OHMS ;
k = 1000 , M = 1000 000.
# = GATE PROTECTED

NOTE: Enameled wire may be used wherever No. 26 Teflon wire is specified in this project, so long as the builder is careful to avoid abrasion damage during construction.

Top view of the 50-MHz transceiver. Circuit-board assemblies identifiable in this picture are listed by numbers given in Fig. 1. (1) Receiver mixers, upper left corner. (4) Audio amplifier, square assembly, upper right. (6) Calibration oscillator, left center. (8) 36-MHz oscillator, small board, lower center. (10) Transmitting mixers, long narrow assembly, right center. (11) Transmitter amplifiers, far right. The agc and meter amplifier assembly (5) is vertically mounted on the back of the panel, lower left corner, so it is not clearly distinguishable as such. The VFO (7) is in an aluminum enclosure directly under the calibration oscillator, except for its tuning and band-setting capacitors, which are visible at the lower left.



Fig. 2 — Schematic diagram and parts information for the 50-MHz transceiver front end and 9-MHz filter. Parts not described below are numbered for text reference.

C1, C3, C5 — Subminiature air trimmer 1-14 pF.
C2, C4 — Gimmick capacitor, 2 twists No. 26 enameled wire, 1/2-inch long; approx. 0.5 pF.
C6, C7 — Ceramic trimmer, 5-25 pF.
C8, C9 — Ceramic trimmer, 7-45 pF.
FL1 — 9-MHz crystal filter (Spectrum International, Box 87, Topsfield, MA 01983, Type XF9B).
L1 — 1 turn No. 26 enameled wire on 0.37-inch toroid core (Amidon T-37, yellow).
L2 — 13 turns like L1, on same core. See text for 25-kHz coupling method.
L3, L4 — 12 turns on core like L1, L2.
L5 — 36 turns No. 32 Teflon on 0.5-inch toroid core (Amidon T-50, red).
L6 — 55 turns like L5.
L7 — 11 turns at low-Z end of L6.
Q1, Q2 — Gate protected MOSFET (RCA 40673).

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.


EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS; k=1000, M=1000 000
I-F AMP.
FILTER FIG. 2
4
C10 50
9 MHz
L8
L9
150 C11
C12 68
1500
2200
.01
1000
27
U1
CA3028A
.005
.1
100
9
AGC FIG. 4
100
.002
PROD. DET.
1200
820
1000
4700
.05
.1
9 MHz
L10
C13 50
C14 180
C15 50
.002
4700
100
10k
2700
.1
MC1596G OR MC1496G
U2
.05
+13.6 V RCV.
2
FIG. 10
47
.1
.005
2700
1000
.005
8
I-F SAMPLE FIG. 4
11
9-MHz BFO FIG. 7
AUDIO AMP.
100μF 15V
.33
R2 GAIN 10k
.33
100
1M
1.2M
U3
MFC8010
.1
720
100
10μF 15V
100
200
10k
1000
1μF 15V
7
+13.6 V RCV. FIG. 10
51k
5μF 15V
500μF 15V
16-OHM SPKR.

Fig. 3 — Schematic diagram of the 9-MHz i-f amplifier and product detector, and audio-amplifier modules. Parts not described are numbered for text reference.

C10, C13 — Ceramic trimmer, 9-50 pF.
L8, L9 — 17 and 24 turns, resp., No. 26 enameled wire on 0.5-inch toroid core (Amidon T-50-2).
L10 — 24 turns, like L1.
R2 — 10,000-ohm miniature control.
U1 — I-f amplifier IC (RCA CA3028A).
U2 — Product Detector IC (Motorola MC1496G or 1596G).
U3 — Audio amplifier IC (Motorola MFC8010 or HEP C6004).

considered to be optimum for conversion efficiency and mixer linearity. Output from the second mixer is link-coupled, through L6-L7, to match the impedance of the crystal filter.

The 9-MHz Filter

The KVG Model XF9B (See Parts list, Fig. 2) filter was chosen for a variety of reasons. It directly controls the receiver selectivity, and barring nonlinearities in the transmitter power stages, the ultimate bandwidth and carrier suppression of the emitted signal. Obviously this is not an area in which to cut corners with a second-rate filter. Salient features of the 8-pole lattice filter include a bandwidth of 2.4 kHz at 6 dB down, a shape factor of 1.8 at the 60-dB point, and 100 dB of stop-band attenuation, with less than 2 dB of ripple when properly terminated.

The filter does double duty in the transmitter and receiver, so diode switching was used to simplify the circuitry. Care must be exercised to avoid unwanted stray coupling between the two filter ports, as it could degrade filter characteristics. The two 45-pF trimmers, C8 and C9 in Fig. 2, were intended to provide ripple band-pass tuning, for precise adjustment of the filter response. In practice they may be omitted, as it is doubtful that any noticeable improvement is made by their use.

Receiver I-F and Product Detector

In the RECEIVE mode the output of the KVG filter is diode-switched to the input transformer, L8-L9 in Fig. 3. This has a capacitive voltage divider, C11-C12, across its secondary, for optimum impedance match between the filter and the i-f amplifier, a CA3028A differential-amplifier IC, U1. As with other tuned stages, the 9-MHz i-f circuits are toroidal, to lessen undesired interstage coupling and attendant instability. The i-f gain is approximately 25 to 30 dB. The i-f output is sampled through an 8-pF capacitor, to provide energy for the agc amplifier, Fig. 4. The control voltage is fed back to pin 7 of the i-f amplifier IC, to produce about 25 dB of agc dynamic range. The agc voltage varies from less than 2, at minimum gain, to 12, during periods of no agc action and maximum i-f gain. Another capacitive voltage divider, C14 and C15, provides impedance transformation between the i-f output and the product-detector input.

Of all circuits considered for the product detector, the MC1496G IC, U2, proved to be the best candidate. With 12 dB of conversion gain, the 1496 compensates for the relatively low gain of the receiver front end. It has an effective dynamic range of 90 dB, and can handle a wide variation of signal levels, despite limited agc action. BFO injection at 9MHz is generated by a 2N3904 crystal oscillator, Q9 in Part II, in the ssb generator assembly. An injection level of 300 mV pk-pk is needed. Extreme care must be used in laying out

Bottom view of the transceiver, showing the i-f amplifier and product detector (3), left side; the sideband generator (9) assembly at the center; and the 9-MHz filter (2) at the right.



and wiring the transceiver, to be sure that stray BFO energy does not reach the rf of i-f stages. Leakage at 9 MHz can kill the i-f gain through the agc, and if the BFO energy reaches the mixers it is possible for the fourth harmonic to beat with the 36-MHz oscillator.

Audio Amplifier

A single MFC8010 (or HEP C6004) is the entire receiver audio system (lower portion of Fig. 3). It is an economical plastic-case unit designed for consumer electronics use, capable of one watt continuous rms output to a 16-ohm load, with as little as 10 mV input. This much sensitivity is not needed, because of the high output level of the product detector, and it caused some instability as a result of stray coupling on our audio board. The final circuit details shown are for an input sensitivity of 400 mV. The amplifier is capable of driving loads of less than 16 ohms, but with a supply voltage of 15 the device ratings may be exceeded, and operation at high audio levels is best avoided. The stabilization network recommended in the manufacturer's application notes was ineffective in curbing instability occurring with certain loads. Instead, it was found that a 1-μF capacitor from pin 8 to ground would eliminate regenerative tendencies in the amplifier.

A feedback path between the product detector and the audio stages, through the supply wiring, was found when certain high-impedance voltage sources (such as carbon-zinc batteries) were used. This was cured with a 2000-μF electrolytic capacitor from the supply line to ground. The capacitor, shown in the control-circuit diagram, Fig. 10, Part II, also helps to reduce ripple from an ac supply, or from a car alternator

AGC

The agc system is a variation of one designed by W1CER, for use with the CA3028.[1] Original plans were for an agc system using the MFC6040 electronic attenuator. This scheme did not work as well as desired, so the i-f agc arrangement was pressed into service. The CA3028A i-f amplifier, U1, is the only stage controlled, so the agc range is somewhat limited. Performance is not spectacular, but the agc is capable of handling the strong local signals encountered in 50-MHZ operation. Part of the 9-MHz i-f output is fed to a CA3028A cascode agc amplifier, U4 in Fig. 4, producing about 40 dB of gain. Output of this amplifier is detected in a simple voltage doubler, with *RC* time constants selectable at this point for fast or slow agc action, via S1. The dc level from the voltage doubler is stepped up in a two-stage dc amplifier, Q3 and Q4, which supplies both S-meter current and agc voltage to the i-f stage.

25-kHz Calibrator

The calibration oscillator assembly indicated in the block diagram is a recommended built-in accessory for the transceiver. A 100-kHz crystal, Y1 in Fig. 5, is used in a JFET oscillator. Calibration intervals of 100 kHz are of little use in the small tuning range of this transceiver, so two *J-K* flip-flops, U5 and U6, were added, to divide the 100-kHz reference down to 25 kHz. The rich harmonic content of the flip-flops extends well into the 50-MHz range. The calibrator output is brought into the receiver through miniature 50-ohm coax (RG-174/U). Stray coupling between an exposed section of the inner conductor, one inch long, and the input transformer of the receiver, gives adequate calibrator signal in the receiver. Coupling is not critical, and the exposed lead can merely lie adjacent to the input circuit.



Fig. 4 – Schematic diagram of the agc and S-meter amplifier. Parts not described are numbered for text reference.

S1 – 2-pole 3-position toggle switch, center off.

U4 – I-f amplifier IC (RCA CA3028A).



Fig. 5 – Schematic diagram of the 25-kHz crystal calibrator.

C16 – Ceramic trimmer, 7- through 45-pF.

S2 – Spst momentary-on, push-button.

U5, U6 – *J-K* flip-flop (Fairchild μL923).

Y1 – 100-kHz crystal, for 32-pF load (International Crystal Mfg. Co).

---

[1] *The Radio Amateur's Handbook*, 1973 and 1974 Editions, "A Receiving Package for 30 to 144 MHz," Chapter 8.

From March 1975 QST, p 27:



Side view of the K1ZJH 50-MHz transceiver, with cover removed, showing the transmitter rf amplifier stages, not completely seen in the top view, Part I.

QRP Transceiver for 50 MHz

Part II

INSOFAR as practical, description of the K1ZJH 50-MHz transceiver was divided to put receiving assemblies in Part I and transmitting units in Part II. Several board assemblies serve both functions, including the 9-MHz filter in Part I. This concluding portion covers other dual-purpose units of the transceiver, as well as those used for transmitting only. As in Part I, order of appearance is indicated by unit numbers in the block diagram, Fig. 1.

The 5-MHz VFO

The VFO and the 36-MHz crystal oscillator, Fig. 6, determine both the transmitting and receiving frequencies. The VFO design was adapted from one used by W1KLK in a 20-meter ssb transmitter.[2] The Colpitts oscillator uses an RCA 40841 MOSFET, Q5, with gates tied together. A 1N914 stabilizes the gate voltage, reducing harmonic generation by limiting device transconductance on positive voltage peaks. Two medium-gain 2N2222A transistors, Q6 and Q7, in an emitter-follower circuit match the VFO output to 50 ohms. The 5-MHz energy passes through a low-pass filter, to eliminate harmonic output from the buffers. It then goes to the transmitting and receiving mixers through RG-174/U coax.

Oscillator voltage regulation was not found necessary, but can be done with a 9.1-volt Zener diode from the oscillator drain to ground. This diode and the 220-ohm resistor already in the drain lead should not be in physical proximity to frequency-determining circuits of the VFO, as heat dissipation by the resistor and diode might cause oscillator drift. A diode-switched capacitance (C19 and C20 in series) off-sets the VFO during lsb operation, to preserve dial calibration.

The VFO is set to cover 5.08 to 5.19 MHz, giving band coverage of 50.08 to 50.19 MHz. This allows operation in the upper portion of the cw-only band at 50.0 to 50.1, and also cw or ssb in the first 90 kHz of the voice band. Most current use of both modes is in this range. More coverage can be had by using a larger capacitor (more plates) for C18. Note that the ceramic padder, C21, has a negative temperature coefficient. Its "N" value can be selected experimentally, if the N330 specified does not correct oscillator drift adequately. Or, a smaller capacitor of the more common N750 type, used in parallel with an NPO, can be tried, to correct drift in environments different from that in which the author's rig operates.

The VFO dial is an old National Type MCN, with a Jackson Brothers ball-bearing vernier drive in place of the original planetary mechanism. This gave the smooth free feel that is so important in a dial that is to be used for receiver tuning, as well as for VFO control. No peaking or tracking controls are needed, as the limited tuning range of the equipment eliminates tracking problems.

Except for the main tuning capacitor, C18, and its padder, C17, both of which are visible in the top view, lower left corner, the VFO assembly cannot be seen in the photographs. The circuit board and VFO components are in a Minibox-type enclosure, for thermal and electrical isolation. The box is under the 25-kHz oscillator board, left center of the top view. It is important that the mounting of all VFO parts be rigid, and special care should be given to the dial drive and variable capacitor assembly. If necessary, the front panel and chassis can be reinforced with additional thickness of aluminum, in these areas.

36-MHz Heterodyne Oscillator

This oscillator, shown schematically in the lower portion of Fig. 6, also serves both transmitting and receiving functions. A 2N3904 transistor, Q8, is used with a 36-MHz crystal, Y2, in a reliable overtone oscillator circuit, to furnish injection for both transmitting and receiving mixers. In the receiver it heterodynes the signal to the 14-MHz range in the first mixer. Q1, Fig. 2. In transmitting it beats with the 14-MHz output of the second transmitting mixer, Q13, Fig. 8, to produce the 50-MHz signal that is fed to the amplifier stages of Fig. 9.

The oscillator collector voltage is Zener-diode regulated, to maintain frequency stability and rf output level with varying supply voltage. Two lightly coupled tuned circuits are used to reduce harmonic content in the output. The gimmick capacitor C23 is adjusted to provide the minimum coupling needed to develop 1.5 volts pk-pk for the mixers. The second tuned circuit, L13-C24, was added after the 36-MHz oscillator board was made. It is seen in the upper-central portion of the top-view photograph, above the oscillator assembly.

Sideband Generation

The sideband generator, Fig. 7, is the largest and most complex subassembly in the transceiver. It is seen in the middle portion of the bottom-view photograph. Included are a crystal oscillator, Q9, two speech stages, Q10 and Q11, and a balanced modulator, U7. The three crystals, Y3, Y4, and Y5, are available for use with the KVG filter, and their frequencies are selected to provide upper and lower sidebands and cw, while maintaining the dial calibration for all modes.

The balanced modulator is a Motorola MC1596G IC, using information supplied by K7QWR.[3] BFO injection is critical for maximum carrier suppression. There should be 150 mV developed at Pin 8 of U7. This can be adjusted by substituting other values for the 82-pF coupling capacitor, C29. A multiturn Trimpot was used for the carrier balance control, R3, for accurate and stable carrier nulling. Since there is no rf energy at this point, only a dc level, the control can be located away from the balanced-modulator circuitry at any convenient point, with no deleterious effects.

In the cw mode the carrier suppression is purposely unbalanced, to generate a carrier at the MC1496G output, and also a crystal within the filter passband is used. Operation with a-m is possible, though not shown here, by increasing the value of the 1000-ohm resistor, R5, used for carrier insertion. A point will be found where satisfactory a-m is generated, minus one sideband, of course. The two frequency-setting capacitors, C25 and C26, associated with the two sideband BFO crystals, are used in conjunction with R3 in nulling the carrier. All settings interact, and it will be necessary to repeat adjustments several times, for maximum carrier rejection on both upper and

---

[2] *The Radio Amateur's Handbook* "A 20-Meter Sideband Transmitter," 1973 Edition, p. 414.

[3] Hejhall, "Integrated Circuit Balanced Modulator," *Ham Radio* September, 1970.


5.08–5.18 MHz
VFO
Q5
40841*
BUFFER
L11
C21
C17 45
C19 7
C18 35
C20
390 µH
1N914
LSB OFFSET FIG.7
Q6 2N2222A
Q7 2N2222A
560 µH
5.6 µH
5-MHz OUTPUT FIGS. 2, 8
13.6 V CONTINUOUS FIG. 10
* = GATE PROTECTED
CRYSTAL OSC.
36 MHz
Q8 2N3904
Y2
C22 25
C23
L12
L13
C24 45
L14
L15
27 µH
36 MHz OUTPUT
FIG. 2
FIG. 8
13.6 V CONTINUOUS FIG. 10
VR1 9.1 V 1W
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k = 1000, M = 1 000 000

NOTE: Enameled wire may be used wherever No. 26 Teflon wire is specified in this project, so long as the builder is careful to avoid abrasion damage during construction.

Fig. 6 — Schematic diagrams of the VFO and 36-MHz oscillator used in the K1ZJH 50-MHz transceiver. Parts not described are numbered for text reference.

C17, C24 — Ceramic trimmer, 7 to 45 pF.
C18 — Shaft-type miniature variable, 35 pF.
C19 — Ceramic trimmer 1.5 — 7 pF.
C20 — 1-pF silver-mica.
C21 — 100-pF disk ceramic, neg. temp. coef. Select N value for minimum oscillator drift. N330 used.
C22 — Ceramic trimmer, 5 — 25 pF.
C23 — Gimmick capacitor; two 1-inch lengths No. 24 Teflon wire, twisted to give desired mixer-injection level, 1.5 V pk-pk.
L11 — 26 turns No. 26 Teflon wire on 1/2-inch toroid core (Amidon T-50-2, red).
L12, L13 — 12 turns like L11, except Amidon T-50-6, yellow.
L14, L15 — 1 turn each, bifilar-wound at low-Z end of L13.
VR1 — 9.1-volt 1-watt Zener diode.


9001.5 kHz
8998.5 kHz
8999 kHz
Y3
Y4
Y5
C25 25
C26 25
C27 25
1N914
500 µH
OSC.
2N3904 Q9
C28 25
L16
L17
L18
TO PROD. DET. FIG. 3
R5 1000 BAL. MOD.
U7 MC1496G
+13.6 V TR. FIG. 10
+13.6 V TRANS. FIG. 10
9.1 V 1W VR2
LSB
USB
CW
S3
VFO LSB OFFSET FIG. 6
SPEECH AMP.
R3 50k BAL.
C29 45
L19
L20
9-MHz FILTER FIG. 2
Q11 2N2102
SPEECH AMP.
Q10 MPF102
1M GAIN
MIC.

Fig. 7 — Schematic diagram for the sideband generator in the 50-MHz transceiver. Parts not described are numbered for text reference.

C25-C28, incl. — Ceramic trimmer, 5 — 25 pF.
C29 — Ceramic trimmer, 7 — 45 pF.
L16 — 32 turns No. 26 Teflon wire on 1/2-inch toroid core (Amidon T-50-2, red).
L17, L18 — 2 turns each, bifilar-wound at low-Z end of L16.
L19 — 20 turns like L16.
L20 — 9 turns No. 28, on core of L19.
R3 — 50,000-ohm control.
R4 — 1-Megohm audio control.
S3 — Single-pole 3-position wafer switch.
U7 — Balanced modulator IC (Motorola MC1496G).
VR2 — 9.1-volt 1-watt Zener diode.
Y3, Y4, Y5 — Crystals, frequencies as indicated, ordered with FL1 (Spectrum International XF902, XF901, and XF903, respectively).

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.


MIXER
9 MHz
TO FILTER FIG. 2
L21
L22
560
C30 25
.001
100k
Q12 40841*
14 MHz
C31 25
C32
L23
C33 25
.05
270
J1 KEYING
.05
VFO FIG. 6
120
1.5 V pk-pk
* = GATE PROTECTED
100k
1M
C34
L24
C35 25
.05
100
MIXER
Q13 40841*
.001
L25
100k
.05
270
100k
120
820k
50 MHz
C36 25
C37
L26
C38 25
L27
L28
TO FIG. 9
100
.001
RFC1
+13.6 V TR FIG. 10
FIG. 6 36 MHz 1.5 V pk-pk

Fig. 8 — Schematic diagram of the transmitter mixer assembly for the 50-MHz transceiver.

C30, C31, C33, C35, C36, C38 — Ceramic trimmer, 5 – 25 pF.
C32, C34, C37 — Gimmick capacitor; two 1-inch lengths No. 24 Teflon wire, twisted three times; approx 1 pF.
J1 — Closed-circuit jack.
L21 — 10 turns No. 26 Teflon, on 1/2-inch toroid core (Amidon T-50-2, red).
L22 — 30 turns like L21, on same core.
L23 — 27 turns like L21.
L24, L25 — 30 turns, like L21.
L26, L27 — 8 turns, like L21.
L28 — 2 turns on same core as L27.
Q12, Q13 — Gate-protected MOSFET (RCA 40841).
RFC1 — 4 ferrite beads (Amidon 43-101).


CLASS A AMP.
CLASS A AMP.
POWER AMP.
50 MHz
36-MHz TRAP
L29
C39 45
FIG. 8
3300
1000
.01
Q14 2N4427
6800
C46 10µF 10 V
10
470
L30
39µH
C40 180
C41 180
560
Q15 2N4427
1000
100
C47 10µF 10 V
3.3
470
R10 270
C42 180
L31
C43 180
39µH
470
.05
680
Q16 2N3632
100
680
R5 1
R6 1
R7 1
470
RFC2
R11 680
39µH
L32
C44 180
C45 180
RFC3
K1C FIG. 10
E99 FIG. 10
R8
+13.6 V K1B FIG. 10
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF OR µµF); RESISTANCES ARE IN OHMS; k = 1000, M = 1 000 000
R9 4700
VR3 10V 1W
50µF 12V
82 1W

Fig. 9 — Schematic diagram of the transmitter rf amplifier stages.

C39, Ceramic trimmer, 7 — 45 pF.
C40-C45, incl. — Mica trimmer, 9 — 180 pF (Arco-Elmenco 463).
C46, C47 — Small tantalum electrolytic, 10 µF, 10 volts. (Mallory MTP-106M010 P1D).
L29 — 10 turns No. 26 Teflon on 1/2-inch toroid core (Amidon T-50-2, red).
L30 — 5 turns, like L29.
L31 — 6 turns, like L29.
L32 — 9 turns, like L29.
Q14, Q15 — 2N4427 (RCA). 2N3866 also usable for Q15.
Q16 — 2N3632 (surplus). 2N3375 also may be usable.
R5, R6, R7 — 1-ohm 1/2-watt composition resistors in parallel.
R9, R10 — Approximate values; adjust for collector currents of 80 and 100 mA for Q14 and Q15, respectively.
R11 — Approximate value; adjust for idling current of 30 mA for Q16, or best linearity in two-tone text.
RFC2, RFC3 — 4 ferrite beads (Amidon 43-101).
VR3 — 10-volt 1-watt Zener diode.

lower sideband. The trimmer C27, for the cw BFO crystal, is simply set at the point where no further increase in carrier output is obtained.

The output of the balanced modulator goes to the KVG filter, where the unwanted sideband and any trace of carrier are removed. Resistive loading of the KVG ports in the *transmit* mode (resistors across L20 and L21) was done for impedance matching.

Transmitter Mixers

The transmitting converters bring the 9-MHz signal up to 50 MHz in the opposite order of conversion to that of the receiving section. Both mixers, Q12 and Q13, are 40841 MOSFETs. The first up-converts the 9-MHz filter output to a 14-MHz bandpass i-f, by heterodyning it with the 5-MHz VFO output. Three lightly coupled tuned stages follow this mixer, forming a 14-MHz bandpass filter. This is very important, reducing spurious mixing products that would otherwise be compounded in the next mixer, and also eliminating harmonic multiples of the VFO frequency. (The tenth harmonic could be especially troublesome.) The source ground return of the first mixer is keyed for cw operation, via J1 in Fig. 8.

The second transmitter mixer combines the 14-MHz i-f with energy from the 36-MHz heterodyne oscillator, to produce the desired 50-MHz signal. Two lightly coupled 50-MHz LC stages follow the second mixer. These reduce 36-MHz and harmonic feed-through, as well as any undesired mixer products present. As with the 40673 MOSFETs, 1.5 volts pk-pk is the recommended injection level at Gate 2 of the 40841.

Amplifier Chain

Three stages are needed to bring the 50-MHz output up to the 3-watt level. The first two are 2N4427s, biased for Class-A operation. Heat sinks are needed to dissipate the heat generated in



Fig. 10 – Schematic diagram of the power supply and control circuits for the 50-MHz transceiver. Capacitors are electrolytic, values in µF.

CR1-CR4, incl. – 100 PRV, 1 A.
F1, F3 – 1-A fuse.
F2 – 2-A fuse, slow-blow.
J2 – Coaxial jack, SO-239.
K1A, K1B, K1C – Miniature 2-pole, 2-position relay, 120-ohm coil. Vary value of, or eliminate, R12 for other coil resistances.
S4, S5 – Spst toggle.
S6 – PTT switch on microphone.
S7 – Double-pole, 3-position wafer switch.
R13 – 8200 ohms, or value to give 50-vdc full-scale deflection with meter used.
VR4 – 15-volt 1-watt Zener diode.
VR5, VR6 – 18-volt 1-watt Zener diode.

Class-A service. The 2N4427 is designed for uhf service, and it is fairly "hot" at 50 MHz. Much empirical design went into the development of a stable circuit, resulting in quite a few gray hairs for the author. Collector-to-base degenerative feedback is used to reduce the gain of the 2N4427s, and this improved the stability and linearity of both stages. A 2N3632 overlay transistor loafs along in the output amplifier stage. This larger-than-necessary type was used mainly because it is plentiful and low-priced on the surplus market,[4] and it works well at 50 MHz. The final stage runs Class B, producing about 1.5 watts average ssb output.

The base-biasing resistors of the 2N4427 stages, R9 and R10, may have to be altered slightly to obtain the desired collector currents indicated in the parts list. The idling current for the 2N3632 is 30 mA. All base-bias levels are developed from a 10-volt line, Zener-diode regulated to insure a linear operating region for the devices, with varying supply voltages. A two-tone test[5] will indicate proper biasing of the 2N3632 amplifier, and also the maximum average collector current for the stage, before flat-topping occurs. This was 150 mA, on voice peaks, in the author's transceiver. The 2N3632 draws 350 mA in cw operation. The two-tone test will also provide a good indication of spurious oscillations, which sometimes occur only at certain power levels, or with mismatched loads.

Collector current in the 2N3632 is monitored across R8, the value of which is adjusted to give full-scale deflection with 500 mA, with the 5-mA meter used by the author. A suitable shunt can be made by winding fine wire on a low-value resistor experimentally. The meter circuits shown also allow monitoring of the supply voltage and relative-signal strength.

A spectral analysis made at the ARRL Lab showed a very clean output from the transmitter. Only the second and third harmonics of the output frequency, and a 90-MHz spurious signal, were evident, and in all cases these were better than 50 dB down, referenced to the carrier.

Results

A brief summary of on-the-air experience with the transceiver may be of interest. During a recent VHF Party, 11 ARRL Sections were worked from the author's home in North-Central Connecticut. These included all New England except Rhode Island, and Eastern Pennsylvania, Northern New Jersey, Eastern New York, NYC-Long Island, and Delaware. Not bad for three watts! Under normal conditions ssb contacts are made regularly with New York, New Hampshire, and the Boston area, at distances out to 100 miles or more, with little difficulty or fanfare, and out to 200 miles or so when the conditions are good. We've even had some success during auroras, which should help to dispel concern about low power and auroral communication. When the band opens for sporadic-E skip, it is only a matter of finding a clear space to jump into – and there's usually plenty of room above about 50.125 or so. Almost anyone heard well can be worked, with a little perseverance, skill, and old-fashioned luck. Locals are often skeptical of the claimed low-power level, but running this way has been a great boon to neighborhood TV reception.

As is likely to be the case with construction projects, this one has generated ideas for improvements and accessories. A recent addition is a 12volt solid-state amplifier, capable of delivering up to 30 watts. A matching high-current power supply has also been added. A 2-meter transverter has been completed, and is now in use at K1ZJH.

[4] Deleted

[5] *The Radio Amateur's Handbook*, Two-Tone Test scope patterns and generator, pages 401 and 527, 1973 and 1974 Editions.

From November 1986 QST, p 43:

Audio-Filter Connections For The Ten-Tec Argonaut Transceiver

☐ I have a Ten-Tec Argonaut 509 transceiver. After I purchased an outboard audio filter, there were some unexpected interface problems. When a sharply tuned filter is placed in the audio line, the sidetone can be filtered out.[4] Also, my filter supplies only about 1 W of audio, which is plenty for headphones, but not for a noisy room.

Some investigation reveals that the 509 audio is generated and preamplified on the IF board. As a matter of fact, the optional Ten-Tec filter is connected within that stage via pins 4 and 5 (FILTER OUT and FILTER IN, respectively) of the rear-apron accessory jack. (These pins are shorted when no filter is used.) There is a mix up in the nomenclature between the IF-board schematic and the block diagram in my instruction manual: Pin 4 should be connected to the filter output, with pin 5 connected to the filter input.

My outboard filter has a fixed gain of about 1, which is ideal for use in the Argonaut IF stage. If your filter has some gain, the filter amplifier (usually an LM380) can be thought of as an output amplifier that is also capable of higher output power. It will probably work just as well with lower drive levels. Therefore, when placed between pins 4 and 5, most any audio filter should work.[5]

This set up leaves the sidetone and the audio output power much the same as before the filter was connected. In addition, the filter is within the Argonaut AGC loop. I have had no problems with this arrangement.—*Michael Martin, KD4ZF, 227 Neville Cir NE, Palm Bay, FL 32907*

---

[4] [The sidetone frequency of the Argonaut 509 is adjustable, and therefore does not necessarily correspond to the receive offset.—Ed.]

[5] [Editor's Note: If your filter has a gain control, set it for unity gain. The chief hazard here is that the filter will overdrive the 509 audio stages. If there is such a problem, simply build an attenuator to follow the filter. Part values for both T- and pi-network attenuators are given in Chapter 25 of the 1985 and 1986 ARRL *Handbooks*.]

From October 1988 QST, p 40:

Curing Mechanically Induced Frequency Jumps In The Ten-Tec Argosy 525

☐ If you push with a finger on the top of the panel or case of an Argosy 525, the frequency of the rig's permeability-tuned oscillator (PTO) may change by 200 Hz or more, seldom returning to the original frequency. Here's how I eliminated this problem in my '525.

Remove the rig's bottom cover. Careful! The speaker leads are not very long and have no strain relief, so take care not to pull the leads out of the speaker. Check the left front foot screw for excessive length; mine was digging into the plastic portion of the '525's phone jack. Pressure on the ends of the front panel results in pressure on this screw; the resultant panel twist is coupled to the PTO. If this condition is present in your rig, snip off the end of the screw with cutters.

With the '525's cover removed, I discovered that touching the PTO cover or bringing part of the '525's bottom cover near the PTO cover can cause wide frequency changes. This suggests that the PTO shielding is inadequate. To correct this condition:

1) Remove the small bracket on the side of the PTO housing that normally receives one of the mounting screws for the transceiver bottom cover.

2) Loosen the PTO cover by backing the PTO-cover retaining screw out a few turns.

3) Remove the piece of fiber board that insulates the PTO cover from the PTO aluminum housing.

4) Cut a piece of household aluminum foil a little wider than the length of the fiber board and about 10 inches long. Wrap the fiber board with about three thicknesses of foil. Cut a hole in the foil corresponding to the hole in the fiber board to permit access to the PTO alignment coil slug.

5) Slip the foil-wrapped fiber board back into its original position and tighten the PTO-cover retaining screw to clamp the foil to the PTO housing.

6) Reinstall the bottom cover of the '525, omitting the screw that formerly engaged the PTO bracket.

This completes the modification. Note: This procedure shifts the Argosy 525's tuning calibration somewhat, so you may need to reset the tuning dial to restore proper calibration. If you find that the tuning shift is excessive or the dial tracking is off, consider realigning the PTO as described in the '525's manual.—*Charles J. Michaels, W7XC, 13431 N 24th Ave, Phoenix, AZ 85029*

From February 1986 QST, p 51:

AGC and RF-Gain Controls for the Ten-Tec Argosy

☐ I have met many users of the Ten-Tec Argosy transceiver on the air and, while all agree the rig is a fine performer, most wish it had an RF-gain control. Since the Argosy operates QSK and uses only AGC to set the RF gain, the noise between dots and dashes can be quite raucous, as the receiver gain is wide open until the AGC takes control. My outboard RF-gain control requires absolutely no surgery to the rig and is within the ability of nearly anyone; the only disassembly required is removal of the top cover.

The circuit in Fig 1 applies an adjustable voltage to pin 5 of U1 (MC1350), which is the AGC input. It controls RF gain in the same fashion as the AGC and has no effect on normal AGC operation. S-meter readings decrease along with the RF gain. Place the outboard control on any breadboard, box or what have you. Connect the control to the transceiver by passing wires through the centers of the rivets that secure the phono-jack panel to the transceiver rear panel. The ground wire of the new control is connected to the ground wire of the jacks, just inside the '525 rear panel. Obtain +12-V dc in the same manner from the 12-V AUX jack inside the rear panel.

To make the control lead, slip a ferrite bead over the diode lead (cathode), and form the shortest hook with which you can work. Solder the hook to the lead of R29 (10 kΩ), which is centered on the end of U1.

My control works nearly as well without the diode and ferrite bead, but I seemed to get a bit of filter blowby without them. This RF-gain control definitely improves CW operating convenience, especially on a noisy band.—*Ned B. Smith, N0CWW, RR 1, Box 163, Ryan, IA 52320*



Fig 1—Schematic diagram of N0CWW's RF-gain control circuit for the Ten-Tec Argosy 525.

☐ Ten-Tec issued a bulletin, TN2-525, describing how to install an RF-gain control in the Argosy 525. It requires that a small, concentric, dual-10-kΩ potentiometer be installed in the AF-gain position. Such a "pot" I have not, so I added an outboard RF-gain control and found it to be a big help.

Then, inspiration struck: Why not reverse the Ten-Tec design and have a fixed audio gain with variable RF gain? My scheme worked well, and you can have the final version without drilling any holes. Furthermore, you can return to the original layout very easily by plugging the connectors from the original audio potentiometer back into terminal 43.

To perform the modification, proceed as follows: Remove the two connectors from terminal 43 of the IF/AF board and move them aside for future use. Wire a miniature 10-kΩ potentiometer to a four-wire connector that will plug into terminal 43. Adjust the potentiometer for an optimum audio level.

Next, turn your attention to the two connectors that are wired to the original audio-gain potentiometer and hook them up as follows: The adjustable arm of the potentiometer goes through a 1N4148 diode to the common junction of D9 and D10. Connect one end terminal of the potentiometer to ground and the other to +12-V dc.

Set the RF-gain potentiometer to midscale and proceed with the "smoke test." I found the adjustment critical because the full range is only a couple of dial markings. (If the RF-gain control works backwards, reverse its battery and ground connections.) In spite of the RF-gain control, a strong signal still generates unwelcome audio pops, so I added an AGC ON/OFF switch. [An AGC-timing modification for the Argosy series appears in the November 1983 Hints and Kinks column. —Ed.]

The AGC ON/OFF switch was created by breaking the connection between D9 and Q5, and wiring in a switch. Disconnect the ac leads from the switch associated with the new RF-gain control and use that switch as the AGC ON/OFF control. [This leaves the radio without a power switch. When used with a switched supply, such as the Ten-Tec 225, the ac-switch leads may be connected, in which case power to the '525 is controlled by the switch in the power supply. When a battery or unswitched supply is used, place a power switch (15 V, 9 A) in the dc line to the radio, or add a new switch to the '525 in a location of your own choosing.—Ed.]

Full QSK CW operation is a most satisfactory experience using a manual RF-gain control and no AGC. SSB works well with the AGC on.—*Jack L. West, W6VD, 3670 Montclaire St, Sacramento, CA 95821*

From January 1984 QST, p 30:

UH--I'LL NEED $450 FOR THIS WIRE AND INSULATORS.
HI-COST ELECTRONICS INC.

Some Practical Antenna Considerations

City lot or "rancho grande," DX or stateside communication, we need certain types of antennas to match available space and operating preferences.

By Doug DeMaw,* W1FB

I remember the mess I made of things back when I erected my first ham antenna. Nobody told me it wasn't just a matter of erecting a wire of a specific length (130 feet was the magic number I'd picked up for 80 through 10 meters back then). Somehow, I had failed to learn that the end-fed wire had to be matched to the transmitter, and that the height above ground had a lot to do with how far away my signal could be heard. Perhaps some fundamental knowledge can save you the agonies that many of us had to endure at the start of our ham radio careers.

As I look back on that first installation at WN8HHS (Novice), I recollect the nail biting, finger drumming and the staring into space that came as a result of being unable to make my homemade CW transmitter develop output power with that end-fed wire attached to it. My first week on the air netted a handful of contacts on 80 meters — none of which were over paths greater than a few city blocks!

Then, quite by accident, the transmitter showed high PA (power amplifier) plate current at the dip (resonance), and I began to work stations all over the USA. What had changed? Earlier that day, I had added an improved manual TR (transmit-receive) switching arrangement to go from transmit back to receive (actually, it was a knife switch and some added wire in the shack). Could this have helped me? I changed things back to their original state, and sure enough — the transmitter wouldn't load up!

I learned later on that the extra feet of wire (plus the switch) I placed in the antenna line had changed the feed-point impedance of the wire, making it just right for a suitable match between the antenna and the transmitter output amplifier. Had I known about antenna tuners then, the problem would never have existed: I could have matched the wire to the transmitter and receiver for use in any of the high-frequency bands. The purpose of this article is to round off some of the sharp edges on antenna problems that could confound the beginner. The topics are based on oft-repeated questions we've answered at ARRL Hq. over the years.[1]

What Kind of Wire Is Best?

You'd be surprised to know that a great number of hams — new and experienced — are uncertain about which type of wire is best for antenna work. "Will insulated wire be okay?" Another query has been, "Will aluminum or steel wire radiate satisfactorily?" as well as "What wire diameter (gauge) must I use?" Well, the straight dope is that none of these are especially critical when you are dealing with wire types of antennas below VHF. If I were to offer a rule of thumb for these questions, I'd say something like, "Use whatever you can round up quickly and inexpensively." Of course, the strength of the wire should be sufficient to provide longevity and safety.

The Matter of Insulation

I'll always remember the amateurs who asked me if they could use antenna wire covered with plastic insulation. Perhaps it is a reasonable thing to wonder about; after all, insulation is an electrical barrier at dc (direct current) and can be a barrier in some ac (alternating current) circuits. Despite this, I have used all manner of insulated wire in my antenna systems, and most of them have worked quite well. Among the wire types employed were nos. 12 and 14 solid and stranded house wiring with plastic jacketing, ordinary electrical hookup wire, cotton-covered bell wire, pieces of ac line cord and, of course, enameled or Formvar® -insulated copper wire.

The insulation does not impair the radiation properties of the antenna. In fact, I prefer insulated wire, because it virtually prevents unwanted oxidation of the copper or aluminum conductor. In some cases it adds strength to the wire — another benefit.

The classic antenna wire among beginners seems to be the stranded bare copper that can be obtained at many parts stores. This is acceptable wire, but it will turn black or green rather quickly in polluted air, such as we find in industrial areas. It can become brittle and break in only two or three years if the air contains con-

---

*ARRL Contributing Editor, P.O. Box 250, Luther, MI 49655

[1] Notes appear at end of article.



Fig. 1 — Illustration of the skin effect of a conductor for various frequency ranges. The election flow is more effective (greater penetration) as the frequency becomes lower.

siderable salt and/or acids. Frequent replacement can be costly!

If insulated wire other than the enameled type is used to prevent corrosion, be sure to seal the open ends with epoxy cement to prevent migration of pollutants and moisture into the space between the wire and the jacketing material. A marvelous new antenna wire with plastic insulation and rugged conductors was recently made available to amateurs.[2] If you are thinking of a new antenna for many years of use, this product may be of interest to you.

There may be an exception to the statement that insulation does not affect antenna performance. I was told by two experienced amateurs that they had difficulty when fashioning cubical-quad elements from vinyl-insulated house wire. The length formulas for the loop elements were of no use when using that style of wire. I haven't investigated the phenomenon yet, but the cause of the difficulty may be related to a change in the propagation factor of the wire, caused by the insulation, with the one-wavelength dimensions. At VHF and higher, there is a definite difference between the propagation factor (wave velocity) of bare wire and a conductor with thick insulation when dealing with conductors that are long in terms of wavelength.[3] I have never observed velocity problems when using insulated wire in ordinary antennas for frequencies lower than 30 MHz.

Conductor Material

Can we use steel wire in our antennas? What about aluminum? Isn't copper best? Here we have to ask ourselves what is meant by the word best? That word can apply to such matters as *strength, weight, conductivity* and *cost*. If I were to ignore cost and handling convenience, and had to give but one answer, I would specify Copperweld® wire. This is a steel-center wire with an outer layer of copper. The combination provides good conductivity and strength. Most amateurs choose no. 16 gauge as a suitable "happy medium" size. But, no. 18 wire is also quite strong, and it is a trifle easier to work with. (Anyone who has struggled with a coil of spring-like Copperweld will understand what I mean by "easier to work with"! A loose coil can be as cooperative as a snake waiting to strike!)



Fig. 2 — Various end insulators and center blocks made from plastic material. Fabricate your own antenna hardware to save money.

Although iron and steel are not as effective a conductor at radio frequencies as are aluminum or copper, it isn't so poor that we should ignore it. I have erected a number of fine antennas with steel guy wire as the radiator elements. I have also used the inexpensive electric-fence wire that can be purchased from Sears. A quarter-mile roll costs less than $15! Similar wire, at slightly higher cost, is available in aluminum.

The reason we may prefer good conductors to less effective ones is to reduce losses in the system. The greater the resistivity of the conductor, the greater the power loss in heating (I^2R losses). Conductivity is also based in part on the operating frequency. We have a condition that is known as "skin effect" — the ability of the RF current to penetrate the conductor. The effective conducting area of a solid conductor is governed by frequency and skin effect (see Fig. 1). Therefore, the larger the conductor, generally speaking, the better the conductivity as the operating frequency is raised. Also, the smaller the wire diameter for a given frequency, the more restricted the antenna bandwidth, owing to increased Q (quality factor) of the system. In other words, the higher the Q of any resonant circuit, the narrower its bandwidth will be. This applies to tuned circuits, filters and the like.

I have been asked such questions as, "What is the smallest wire diameter I can use with my kilowatt rig?" If we don't consider the fragility of very small wire, we might say that even no. 28 wire can be used. I've used no. 24 and no. 26 enameled wire a number of times in so-called "invisible antennas" that were configured as end-fed random-length wires. I have yet to burn up a small-diameter wire used in that manner. The CW or SSB duty cycle, plus the air cooling of the wire, prevents current from burning up the conductor. Small-diameter wire also works nicely in radial systems (buried or above-ground systems of wires that serve as a ground screen for antennas).

Aluminum wire, such as clothesline or electric fencing, is also satisfactory for antennas. The two problems we may encounter are (1) difficulty making a good electrical joint and (2) crystalization of the wire with stress and time, which causes breakage. The use of aluminum wire generally requires the mating of copper to aluminum somewhere along the way, and this invites the rapid oxidation that is so common when dissimilar metals are joined.

Some hams have been fooled by fate when they erected antennas made from soft-drawn copper. Magnet wire, such as we wind coils from, is a form of soft-drawn copper. Although it is easy to work with, since it is not prone to kinking easily, it does stretch under stress.

The longer the antenna, the more pronounced the effect. If the low SWR point in your system has changed mysteriously, chances are your dipole or other wire antenna has become longer as a result of wire stretch. If this happens, you will have to readjust the system by trimming off the excess wire. Soft-drawn copper wire with vinyl jacketing is less likely to change dimension from weight, wind and icing stress.

Insulators

If you've priced commercial antenna insulators recently, you may have concluded (as I have) that the dies from which they are cast must be made of gold or platinum! I object to paying $2 or $3 for an item that is mass-produced from 25 cents worth of material. So, I make my own insulators when possible. Generally, we should strive to use insulators that are of high dielectric quality, such as ceramic, steatite, Teflon, polyethylene and Plexiglas. Other good materials are fiberglass, glass-epoxy circuit-board material (copper removed), phenolic and other low-loss modern plastics. Many of these materials can be purchased as scrap at industrial-plastic outlets, or at a flea market. Fig. 2 shows some of the insulators we can fashion from insulating stock.

In the early days of Amateur Radio, it was not uncommon to find operators who were using antenna insulators made from pieces of hardwood or dowel rod. The wooden sections were cut to size, drilled, then boiled in canning wax or beeswax until they were thoroughly treated against moisture. Spreaders for open-wire feed line were also made from impregnated wood.

Nylon cord is suitable for use as end insulators for wire antennas. Two or more feet of line should be used to ensure that losses are minimized when the line is wet from rain or dew. At this time, I am using a trap-style inverted-V that has 10 feet of strong nylon cord at each end.[4] The cord serves as a support and insulates the ends of the wire from the ground stakes.

Other items that enterprising hams have used as insulators are plastic clothespins, the bodies of plastic pens, plastic pill bottles, nylon center hubs from photocopy-machine paper rolls, plastic hair curlers, nylon six-pack headers and the solid polystyrene center insulation from RG-8/U coaxial cable. I once saw an antenna that had 8-inch strips of inner tube (discarded after a tire blowout) as end insulators! Since most rubber today contains a lot of impurities (such as lamp-black soot), I doubt that I'd use the material in my antenna system. But, this does point out that a little ingenuity can save us time and money.



Fig. 3 — An example of how a tower and triband Yagi might be used as a top-loaded vertical. The beam antenna provides some of the top loading, and the extender wire completes the job. The shunt arm can be spaced 2 to 3 feet from the tower. An L network or other matching system can be housed in a box and located at the feed point. This method is applicable to any unguyed tower under 120 feet in height. The shorter the tower, the longer the extender wire. If the tower is guyed, insulators should be installed at the tower connection points. Fig. 3B shows the details of a similar antenna — the inverted L.

DX or Local QSOs — Which Antenna?

The first section of this article can be considered a lengthy Hint and Kink. I hope the column editor, Larry, WA3VIL, will forgive me for my transgressions! But now that we have talked about some hardware fundamentals, what about the antenna as a whole?

All amateurs are interested in antennas, even though they may never build a piece of ham gear. There is a mystique about antennas that lures all of us. Fortunately, that is one part of radio that most amateurs will try their hands at, and the experiments can usually be carried out in a short period at a minimum outlay of cash.

But, what do we desire in terms of signal coverage? A good antenna must be designed for the distance we want to cover reliably from day to day. Some DX antennas are of little value for close-in work, and many antennas for local work are poor DX performers. Increased antenna height will enhance our DX capability, whereas the lower antennas are much better for working out to a few hundred miles in the lower portion of the hf (high frequency) spectrum. Then there's the matter of limited space for the city dweller. Many urban hams can't erect a tower, and conclude, therefore, that DX is out of reach. In this discussion, our principal concern is for high- or low-angle radiation from the antenna.

Some Easy Antennas

There is a saying among DX chasers who haunt the 160- and 80-meter bands: "A short vertical antenna and ground system is much better than a full-size horizontal antenna that is less than a half wavelength above ground." I tend to agree with that philosophy, having had the good fortune of confirming 72 countries over a three-year span on 160-meter CW. The antenna was a 50-foot, shunt-fed tower with a mediocre ground-radial system. A triband Yagi sat atop the tower. With the same setup (and 100 W of dc input power to the last stage of my transmitter), I obtained my Worked All States Award on 160 meters. Earlier, I tried inverted Vs and low horizontal end-fed half-wave wires, but they failed miserably in DX work. They were super, however, for contacts out to a few hundred miles. The same vertical antenna was used on 80 meters with outstanding results. I had only 16 buried radials in the city-lot lawn, the longest of which was only 100 feet in length. Some were only 40 feet long. Fig. 3 shows the details of the antenna. For those who don't have a tower, a metal mast can be used in place of the tower. If only a tree is available for a support, you might try the inverted L antenna of Fig. 3B. It should provide similar results to those of the antenna at Fig. 3A.

A ground-mounted 40-meter vertical is easy to erect and is fairly "low key" with regard to being seen by neighbors. We need not use tubing if a tree support is available. A vertical wire can serve as the driven element of the antenna. Even a wire that is sloped less than 45 degrees will have


1/4 λ
DRIVEN ELEMENT (WIRE OR TUBING)
FEED METHOD
50-Ω COAXIAL CABLE
INSULATOR
METAL PLATE
NO. 14 WIRE
45° PITCH
MAST
RADIALS (4 EA.)
EACH RADIAL = 1.05 × 1/4 λ
INSULATOR
GUY

Fig. 4 — Example of a ground-plane vertical. The radial wires are connected to the metal base plate and drooped at a 45-degree angle to provide an impedance match to 50-ohm line. The vertical element can be made of tubing, or a wooden support can be added above the base plate to accommodate a wire element in place of the tubing. If this is done, the wire must be insulated from the wooden mast by means of standoff posts. The radial wires serve as guys for the overall system. Each wire is 5 percent longer than the driven element. This is a good DX antenna for 20, 15 or 10 meters, owing to its low radiation angle.

predominantly vertical, low-angle radiation.

For operation at 20, 15 or 10 meters, it is more practical to erect a ground-plane vertical on a pipe mast or chimney mount. Four above-ground radials are sufficient for good operation. They can be made of wire and used as guy wires (see Fig. 4).

The practical limitation of low-angle vertical antennas is the inherent "dead zone" in signal coverage. Signal levels will be high within the ground-wave contour (usually under 100 miles), then there will be a skip zone where the signal is very weak (a couple of hundred miles or more) until refraction bends it down to earth beyond the dead zone. That is why many hams with vertical antennas have communications difficulties on 160, 80 and 40 meters when trying to work someone relatively close to them. A simple horizontal antenna, close to the ground, is frequently used for close-in QSOs.

A very good high-angle antenna for use on 75 or 40 meters is shown in Fig. 5. I dubbed this antenna the "Lazy Quad" when I wrote it up for *CQ* Magazine in the early 1950s. It is excellent out to, say, 500 miles — especially at those times of the day when the band is changing (near sunset and just after daylight). The ground below the antenna acts as a reflector, and the signal is directed skyward. Generally speaking, a dipole that is low to the ground has the same characteristics, and that is why it is so effective for short-haul contacts. A dipole antenna has little or no directivity


SIGNAL
WIRE
1 λ LOOP
MATCHING TRANSFORMER (75-Ω LINE)
T1
POLE OR TREE
H
LOOP = 1005/f MHz FEET
T1 = 246/f MHz FT. × 0.66
H(FEET) 0.15λ
50 Ω LINE TO STATION
(A)
L1 = 468/f MHz (FEET)
GUY
WIRE
50-Ω LINE TO STATION
H
GROUND WIRE
GUY
L2
H = 0.15λ
L2 = 1.05 × L1
(B)

Fig. 5 — The antenna at A is designed for high-angle (short-range) communications on 75, 80 or 40 meters. The ground below it acts as a reflector; the better the ground conductivity, the better the performance. A coaxial transformer matches the 50-ohm feed line to the antenna. The free-space feed impedance is on the order of 115 ohms. It will be somewhat lower when so close to ground. The actual impedance will depend on the quality of the ground below and near the loop. A counterpoise loop made 5 percent longer than the driven element can be placed 0.15 wavelength below the quad loop if there is doubt about the ground conductivity in the area. A similar system is shown at B. It uses a simple dipole above a counterpoise ground or reflector. It can be used without the counterpoise ground if the earth conductivity is acceptable for skyward directivity.

unless it is a half wavelength or greater above ground. Now, that is pretty high at 160 meters (259 feet) or 80 meters (133 feet at 3.7 MHz). We hams tend to think of antenna height in terms of physical dimensions rather than electrical ones. That's a mistake, for even though 70 or 80 feet seems high, it's very low in terms of wavelength at the lower frequencies. To have an 80-meter dipole 50 feet above ground is about as poor as mounting a 10-meter beam 3 feet above ground. None of us would want to do that! It is for this reason that a short vertical antenna usually outperforms a low horizontal antenna for DXing.

We must recognize in this discussion that an electrically short antenna, vertical or horizontal, is not as efficient as a full-size antenna. There is always a trade-off to accept. Also, vertically polarized antennas are noisier during receive than are horizontal antennas. This is because most man-made noise is vertically polarized.

It would be impractical to attempt to describe the many wire antennas suitable for DX and local operation from a city lot. *The ARRL Antenna Book*, recently revised considerably, contains a wealth of practical information for those who want to build antennas. If you don't have a copy, you should invest in one.

Ground Systems in Brief

Countless amateurs have said, "I can't put up a ground-mounted vertical because I don't have room for buried radials." "Balderdash," I am prone to reply. An imperfect ground system is far better than none at all! It is surprising to observe the loud signals that some stations propagate with inferior ground screens. I remember vividly the whopping signal from W7DOL/6 when I worked 160 meters from Connecticut. He was usually the loudest station on the West Coast, and he told me he was using an 80-foot vertical with no ground radials! I dread to think about the kind of signal he would have sent my way if he had had 120 quarter-wavelength radials deployed!

Those fatalists who won't even experiment may be affected by a case of lethargy. I think experimenting is the better part of Amateur Radio. Try a vertical antenna, even if you can lay down only one or two radials. You could be rewarded with better results than theory dictates. I have always made an effort to tie as many ground wires as possible to my antenna systems. If there is a chain-link fence on your property, tie it into the ground system. Do likewise with the cold-water lines in your home, rods driven into the soil near the base of your vertical and utility-company grounds on your property.

Radial wires need not be buried in the ground. They can be laid on the lawn and staked down with homemade large staples to permit mowing the grass without hardship. If they can't be laid out linearly from the base of the antenna, wrap them around the house, garage and trees. The main idea is to get them in or on the ground — some place.

For those of you who are afraid of disfiguring your lawn by putting radial wires in it, take heart. A lawn-edging tool makes a narrow slit, and the wires need be only a couple of inches below the surface to be out of the way. The slits can be closed by stepping on them. The grass will soon grow over the incisions and no one will ever know that an "operation" took place.

What Have We Learned?

In essence, the intent of this article was to kindle your courage toward building and experimenting with antennas. Numerous cost-saving shortcuts have been presented with the hope that you will have some new tricks in your bag when you tackle that next antenna job. If you're wealthy and want to be top dog in the DX pileups, buy your antenna system. The antennas described here will make no one a "big frog in a little pond," but they'll enable you to enjoy good communications most of the time.

Notes

[1] ARRL members may take advantage of the free TIS (Technical Information Service) at Hq. by writing to the Technical Department. Limit the number of questions with each request, and be sure to include a business-size s.a.s.e. for the reply to your inquiry.

[2] Deleted.

[3] J. Hall, ed., *The ARRL Antenna Book* (Newington: ARRL, 1982).

[4] m = ft × 0.3048; mm = in × 25.4.

From February 1983 QST, p 15:

Antennas for Those Who Can't Have Antennas!

Radio amateurs don't engage in covert activities, but there are times in all of our lives when hidden or "invisible" antennas are necessary if we are to get on the air.

By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250
Luther, MI 49656


CQ, DX.. CQ, DX..
CQ, DX.. W8EEF...
I CAN'T UNDERSTAND HOW NORM GOT HIS WAC, DXCC AND WAS WITHOUT HAVING ANY ANTENNAS —
Hmmm....MAYBE HE USES AN UNDERGROUND ANTENNA!

The unfortunate fact of the matter is that some radio amateurs dwell where antennas are prohibited. In other situations the operator may not want to erect outdoor antennas for fear of neighborhood opinions that he or she is destroying the beauty of the residential area. We amateurs don't regard our antennas as eyesores; in fact, we almost always regard them as works of art! But there are occasions when having an outdoor or visible antenna can present problems, especially for those who live in apartments.

When we are confronted with restrictions, self-imposed or otherwise, we can take advantage of a number of options toward getting on the air and radiating at least a moderately effective signal. In this context, a poor antenna is certainly better than no antenna at all! A number of techniques enable us to use indoor antennas or "invisible" antennas out of doors. Many of these systems will yield good to excellent results for local and DX contacts, depending on band conditions at any given time. *Don't erect any antenna that can present a hazard (physical or electrical) to humans, animals or buildings. Safety first!*

Invisible Antennas

In some areas, clotheslines are attached to pulleys (Fig. 1),so that the user can load the line and retrieve the laundry from a back porch. Laundry lines of this variety are accepted parts of the neighborhood "scenery," and can be used handily as amateur antennas by simply insulating the pulleys from their support points. This calls for the use of a conducting type of clothesline, such as heavy-gauge stranded electrical wire with Teflon or vinyl insulation. A high-quality, flexible steel cable (stranded) is suitable as a substitute if one doesn't mind cleaning it each time clothing is hung on it.

A jumper wire can be brought from one end of the line to the ham shack when the station is being operated. If a good electrical connection exists between the wire clothesline and the pulley, a permanent connection can be made by connecting the lead-in wire between the pulley and its insulator. A Transmatch can be used to match the "invisible" random-length wire to the transmitter and receiver.

Invisible "Long Wire"

In reality, an antenna is not a classic "long wire" unless it is one wavelength (or greater) long. Yet, many amateurs refer to all relatively long spans of conductor as "long wires." For the purpose of this article we will assume we have a fairly long span of wire, and refer to it as an "end-fed wire."

If we use small-diameter enameled wire for our end-fed antenna, chances are that it will be very difficult to see against the sky and neighborhood scenery. The higher the wire gauge, the more "invisible" the antenna will be. The limiting factor with very fine wire is fragility. A good compromise can be realized by using no. 24 or no. 26 magnet wire for spans up to 130 feet (m = ft × 0.3048). Lighter-gauge wire can be used for shorter spans, such as 30 or 60 feet. The major threat to the longevity of fine wire is icing; also, birds may fly into the wire and break it. Therefore, this style of antenna may require frequent service or replacement.

Fig. 2 illustrates how we might install an invisible end-fed wire. It is important that the insulators also be lacking in prominence. Tiny Plexiglas blocks work well, as do small-diameter, clear plastic medical vials. Some amateurs simply use rubber bands for end insulators, but they will deteriorate rapidly from sun and air pollutants. They are entirely adequate for short-term operation with an invisible antenna, however.

The invisibility of the antenna can be carried even further if one is willing to use camouflaging techniques. This can be achieved by spraying the antenna wire with green, tan, brown, black and light blue paint at 1-foot intervals. In some instances, a single layer of gray or medium-blue paint will help to disguise the antenna. The wire must be free of grease and dirt if paint is applied, and the paint should be of "exterior" grade. This camouflaging effect can also be realized by dipping sections of the wire into cans of paint of the appropriate colors, assuming that spray paint is not available or desired.



Fig. 1 — One form of hidden antenna is shown in this drawing: The antenna performs double duty as a radiator and a wash line. Large-diameter insulated wire (flexible) can be used as the line, or a clothesline with a wire center may be employed. The pulleys are insulated from the house and the pole.



Fig. 2 — Light-gauge enamel-covered wire works nicely as a hard-to-see antenna. Although a bird may knock it down from time to time, re-erecting it beats having no antenna at all!

Rain-Gutter or TV Antennas

A great number of amateurs have taken advantage of standard house fixtures when contriving inconspicuous antennas. A very old technique is the use of the gutter and downspout system on the building. This can be seen in Fig. 3: A lead wire is routed to the shack from one end of the gutter trough. We must assume that the wood on which the gutter is affixed is dry and of good quality in order to provide a reasonable insulation factor. The rain-gutter antenna may perform quite poorly during wet weather or when there is ice and snow on it and the house roof.

We need to ensure that all joints between gutter and downspout sections are bonded with straps of braid or flashing copper to provide good continuity in the system. Poor joints can cause rectification and subsequent TVI and other harmonic interference. Also, it is prudent to insert a section of plastic downspout about 8 ft above ground. This will prevent humans from receiving rf shocks or burns while the antenna is being used. Improved performance may result if the front and back gutters of the house are joined by a jumper wire to increase the area of the antenna.

Fig. 3 also shows a TV or fm antenna that can be employed as an invisible amateur antenna. Many of these antennas can be modified easily to accommodate the 144- or 220-MHz bands, thereby permitting the use of the 300-Ω line as a feeder system. Some fm antennas can be used on 6 meters by adding no. 10 bus-wire extensions to the ends of the elements and adjusting them for a VSWR of 1:1. If 300-Ω line is used it will require a balun or Transmatch to interface the line with the station equipment.

For operation in the hf bands we can tie the TV- or fm-antenna feeders together at the transmitter end of the span and treat the overall system as a random-length wire. If this is done, the 300-Ω line will have to be on TV standoff insulators and spaced well away from phone and power company service-entrance lines. The TV or fm radio must of course be disconnected from the system when it is used for amateur work! Similarly, masthead amplifiers and splitters must be removed from the line if the system is to be used for amateur operation.



Fig. 3 — Some amateurs have had success when using the rain gutter as a random-length, end-fed radiator. The lower portion should be insulated from the remainder of the gutter and downspout to prevent rf hazards to animals and people. The TV or fm antenna-lead wire also can be used as a random-length antenna, as shown here.


FLAG
FIBERGLASS POLE OR PVC TUBING (PAINT WHITE)
NO 10 OR 12 WIRE INSIDE POLE
SEAL WITH RTV COMPOUND
50-Ω COAXIAL CABLE TO TRANSMITTER (BURIED)
BURIED RADIAL WIRES

Fig. 4 — One can be patriotic while using a disguised antenna. The flagpole also serves as a vertical antenna in this illustration. Insulation should be used over the lower part of the antenna to prevent shock hazard to people and animals.

Flagpole Antenna

We can exhibit our patriotism and have an invisible amateur antenna at the same time by disguising our radiator as shown in Fig. 4. The vertical antenna is a wire that has been placed inside a plastic or fiberglass pole.

As shown, the flagpole antenna is structured for a single amateur band, and it is assumed that the height of the pole corresponds to a quarter wavelength for the chosen band. The radials and feed line can be buried in the ground as shown. In a practical installation, the sealed end of the coax cable would protrude slightly into the lower end of the plastic pole.

If a large-diameter, fiberglass pole were available, we might be able to conceal a four-band trap vertical inside it. Alternatively, we might use a metal pole and bury at its base a water-tight box that contained fixed-tuned matching networks for the bands of interest. The networks could be selected remotely by means of a stepping relay inside the box. A 30-ft flagpole would provide good results in this kind of system, provided it was used with a buried radial system. At least one commercial antenna (from Delta Corp.) is used in this manner, but with an elaborate, continuously adjustable matching network (and VSWR indicator) that is operated remotely.

Still another technique uses a wooden flagpole. A small-diameter wire can be stapled to the pole and routed underground to the coax feeder or the matching box. The halyard could by itself constitute the antenna wire if it were made from heavy-duty insulated hookup wire. There are countless variations for this type of antenna, and they are limited only by the imagination of the amateur.

Other Invisible Antennas

Some amateurs have used the metal fence on apartment verandas as antennas, and have had good results on the higher hf bands (20, 15 and 10 meters). We must presume that the fences were not connected to the steel framework of the building, but rather were insulated by the concrete floor to which they were affixed. These veranda fences have also been used effectively as ground systems (counterpoises) for hf-band vertical antennas that were put in place temporarily after darkness fell.

One New York City amateur used the fire escape on his apartment building as a 40-meter antenna, and reported high success in working DX stations with it. Another apartment dweller made use of the aluminum frame on his living-room picture window as an antenna for 10 and 15 meters. He worked it against the metal conductors of the baseboard heater in the same room.

There have been many jokes told over the past decades about "bed-spring antennas." The idea is by no means absurd. Bed springs and metal end boards have been used to advantage by many apartment dwellers as 20-, 15- and 10-meter radiators. A counterpoise ground can be routed along the baseboard of the bedroom and used in combination with the bed spring. It is important to remember that any independent (insulated) metal object of reasonable size can serve as an antenna if the transmitter can be matched to it. An amateur in Detroit, Michigan, once used his Shopsmith craft machine (about 5 feet tall) as a 10-meter antenna. He worked a number of DX stations with it when band conditions were good.

A number of operators have used metal curtain rods and window screens for vhf work, and found them to be quite acceptable for local communications. You'll have best results with any of these makeshift antennas when the "antennas" are kept well away from house wiring and other conductive objects.

From June 1983 QST, p 15:

Lightweight Trap Antennas — Some Thoughts

Portable multiband antennas need not be heavy and bulky. Small traps and light-gauge wire can provide a trap dipole that fits in a lunch bag. Try these practical guidelines for your next small antenna.

By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250
Luther, MI 49656

Vacationers, campers, sales people and QRPers take note! You need not carry a large multiband trap dipole afield if your transmitter is in the 150-W-output class, or lower. You can construct your own traps inexpensively with ordinary materials, and they can be made quite small without becoming poor performers. This article describes some easy techniques for fabricating homemade antenna traps. Additional hints are offered for keeping the bulk and weight of portable antennas within reason.



Fig. 1 — Representation of a three-band trap dipole antenna.

A Review of the Trap Concept

A "trap" is exactly what the term implies. It traps an rf signal to prevent it from passing beyond a specific point along an electrical conductor. At some other frequency, however, it no longer acts as a trap, and permits the passage of rf energy.

An antenna trap is designed for a particular operating frequency, and there may be several traps in the overall system — each designed for a specific frequency. Therefore, a 40- through 10-meter trap dipole might contain traps for 10, 15, 20 and 30 meters. On 40 meters, all of the traps are "absorbed" into the system to become part of the overall 40-meter dipole. Owing to the loading effect of the traps, the 40-meter portion of the antenna will be somewhat shorter than a full-size 40-meter dipole with no traps. The antenna bandwidth will be narrower when traps are used. Fig. 1 illustrates the general format for a multiband dipole.

A trap style of antenna is not as efficient as a full-size dipole. This is because there will always be some losses in the traps. But the losses in a well-designed system are usually so low that they are hard to measure by simple means. The losses represent a small tradeoff for the convenience of being able to accommodate many ham bands with one radiator and a single feed line. Yagi antennas contain traps in the parasitic elements (directors and reflectors) as well as in the driven element. Therefore, a multielement antenna of that type may have as many as 12 traps.

Electrical Characteristics

An antenna trap is a parallel-resonant L-C circuit. Therefore, it is similar to the tuned circuit in a transmitter or receiver. A resonator of this kind, if designed correctly, has a moderate Q and a fairly narrow bandwidth. This means that the trap capacitor should have a high Q and the trap coil should contain wire that is reasonably large in cross section. These traits will help to reduce losses.

Fig. 2 shows the equivalent circuit for an antenna trap. Once this network is adjusted to resonance in the desired part of an amateur band, it will not be affected significantly by the attachment of the wires that comprise the antenna. A well-designed and -constructed trap should not change frequency by any great amount when the temperature or humidity around it varies. Therefore, it is important to use a stable capacitor, a rigid coil and some type of sealant.

Mini Trap Using a Toroid Core

In an effort to scale down the size of my antenna traps during a design exercise for a portable antenna, I decided to investigate the worth of small toroid cores upon which to wind the coils. Ferrite cores were ruled out because they aren't as stable as powdered-iron ones. Furthermore, the powdered-iron material has a much greater flux density than an equivalent-size ferrite core, which means that the core will not saturate as easily at moderate rf power levels.

Development work started with Micrometals Corporation T50-6 toroids, which are sold by Amidon Associates, Palomar Engineers and RadioKit (see *QST* advertisements). My first effort resulted in a pair of very small 20-meter traps. A silver-mica capacitor was chosen for the parallel-tuned circuit. Ceramic capacitors were not used because of previous experiences I had with changes in value under temperature extremes; I had better results with dipped silver-mica units.

My rule of thumb for choosing the coil and capacitor values for traps is based on a reactance of approximately 200 ohms, although values up to 300 have also yielded good results. Using 200 ohms as the basis for the design, I calculated the capacitor to be a value that was very close to a standard one — 56 pF for trap resonance at 14.100 MHz. This was obtained from

$$C(\mu F) = \frac{1}{2\pi\, f(MHz)\, X_c} \qquad \text{(Eq. 1)}$$

Hence

$$C = \frac{1}{6.28 \times 14.1 \times 200}$$

$$= 0.0000564\ \mu F\ (56\ pF)$$

Since X_c and X_L are equal at resonance, the coil was calculated by means of Eq. 2:

$$L(\mu H) = \frac{X_L}{2\pi f(MHz)} \qquad \text{(Eq. 2)}$$

Hence

$$L = \frac{200}{6.28 \times 14.1} = 2.25\ \mu H$$

(approximate)

The value of the coil will have to be adjusted slightly after the trap is assembled to allow for capacitor tolerance and stray capacitance, which accounts for the term "approximate" in Eq. 2.

The Amidon toroid tables were consulted to learn the A_L factor of a T50-6 core (1/2-inch-diameter toroid). The value is 40. From this I calculated the number of turns from

$$\text{Turns} = 100\sqrt{L_{\mu H}/A_L} \qquad \text{(Eq. 3)}$$

Hence

$$\text{Turns} = 100\sqrt{2.25/40} = 23.7$$

For practical reasons a 24-turn winding was used: A partial turn is not convenient on a toroid form.

The same procedure was used for the remaining traps in my antenna. This article is not a course in basic math, but the equations can be useful to those who have not previously designed resonant circuits or used toroidal cores.

Toroidal-Trap Adjustment

It's best to use the largest size wire that will fit easily on the toroid core. The stiffness of the heavier magnet wire will help to keep the coil turns in place, thereby minimizing detuning. I used no. 24 enameled wire.

The capacitor leads and coil "pigtails" should be kept as short as possible. Fig. 3 illustrates the layout I used. The leads at each end of the mica capacitor are soldered to the related coil leads before final adjustment is made.

A dip meter can be used to determine the resonant frequency of the trap, as shown in Fig. 4. Although a prominent feature of a toroidal coil is the self-shielding characteristic, which makes it difficult for us to get ample coupling with a dip meter, it is possible to read a dip. I have found that by inserting the dip-meter coil into the area of the winding gap on the tuned circuit (Fig. 4) a dip can be obtained. By approaching the trap from different angles, it should be easy to find a spot where a dip can be read on the meter. Once the dip is found, back off the instrument until the dip is barely discernible (the minimum coupling point). Monitor the dip-meter signal on a calibrated receiver to learn the resonant frequency of the trap.



Fig. 2 — Electrical equivalent of an antenna trap. The ac resistance is not shown. A suitable reactance value for the coil and capacitor is 200 ohms.



Fig. 3 — Physical arrangement for one of the toroidal L-C traps. Put spaghetti tubing over the capacitor leads to prevent them from shorting to the turns on the toroid.



Fig. 4 — Test method for finding the resonant frequency of a trap. Different points around the toroid will yield better dip indications. Experiment with the position of the dipper coil.

Select a part of the related amateur band for trap resonance. I adjust my traps for the center of the frequency spread I am most interested in. For example, I set my 20-meter traps for resonance at 14.025 MHz because I work only cw from 14.000 to 14.050 MHz. For phone-band coverage, I'd pick 14.275 MHz as the trap frequency. A compromise frequency for phone and cw operation would be 14.100 MHz. Owing to the trap Q, coverage of an entire band is not possible without having an SWR of 2:1 or greater at the band-edge extremes. The absolute bandwidth will depend on the trap Q and the Q of the antenna itself.

If the trap is not on the desired frequency, move the turns of the toroid coil farther apart to raise the frequency. Push them closer together to lower the frequency. An alternative method for finding the trap resonance is shown in Fig. 5. The trap being tested is connected to terminals x and y. The coupling is very light in order to prevent the test-circuit capacitance from appearing in parallel with the trap. For this reason the coupling capacitors are only 2 pF. The station transmitter is adjusted for the lowest power output that will provide a reading on M1. The VFO is then swept manually across the band. When the resonant frequency of the trap is located, the meter (M1) will deflect upward sharply, indicating resonance. Adjust the trap for a frequency that is approximately 5% lower than the desired one. This will compensate for the shunt capacitance presented by the 2-pF coupling capacitors.

When the coil turns are set in the correct manner, spread a bead of fast-drying epoxy cement across the turns on the two flat sides of the toroid. This will prevent unwanted position changes that could cause a shift in resonance later on from handling.

Housing the Mini Trap

I learned that a 7/8-inch-OD PVC plumbing coupling, 1-1/4 inches long, would serve nicely as a housing for the toroidal traps.[1] A ridge inside the couplings at the center can be filed out easily to provide clearance for the trap. A rat-tail file does the job quickly. Fig. 6 shows a breakaway view of how the trap is assembled. Slices of dowel rod are used for end plugs. A knot is tied in the antenna wire that enters the trap housing; this prevents strain on the trap coil.

After the antenna wire has been soldered to the trap at each end, add a layer of epoxy glue to the outer perimeter of one of the dowel plugs, then insert it into the PVC coupling until it is flush. Fill the coupling with noncorrosive sealant; I used aquarium cement. Finally, place epoxy glue on the remaining end plug and insert it in the PVC coupling. Allow the trap to set for 48 hours, until the sealant has hardened. Fig. 7 is a photograph of a mini trap, along with a dipole center insulator made from a PVC T-coupling. The coupling is filled with sealant after the wires are soldered to the coaxial feed line. Long plugs are used to close the three open ends of the T connector. A closed nylon loop, made from strong spaghetti tubing, was fed through two small holes at the top of the T-coupling to permit erecting the dipole as an inverted V. A small eye bolt and nut could have been used instead.

There was a minor downward shift in trap resonance after the sealant hardened. Both 20-meter traps shifted roughly 30 kHz lower. No doubt this was caused by increased distributed capacitance across the coil turns with the sealant in place.

[1] Notes appear at end of article.



Fig. 5 — Test fixture suitable for checking trap resonance with the station transmitter. Use the least amount of power necessary for meter deflection.



Fig. 6 — Breakaway view of a toroidal mini trap. The knots in the wire prevent stress on the tuned circuit.

This seemed to have no effect on the trap quality; it had a measured parallel resistance of 25 kΩ before and after encapsulation (using the laboratory RX meter for tests). Generally, anything greater than 10 kΩ is suitable for an antenna trap.

Mini Coaxial-Cable Traps

Two very interesting articles concerning antenna traps appeared in the amateur literature during 1981.[2,3] After reading them a second time, I decided to attempt building some traps along the lines discussed in those articles. Some advantages over the usual coil/capacitor style of trap were described by the authors: (1) The traps were not especially frequency sensitive to changes in temperature and climate; (2) the coaxial trap offers greater effective bandwidth; and (3) parallel resistance is quite high — on the order of 50 kΩ.

The articles under discussion contained practical information about the use of RG-58/U and RG-8/U cable for the trap coils. I wanted a small, lightweight trap, so elected to see what could be done with miniature cable — RG-174/U. A completed mini coaxial trap for 20 meters is shown in Fig. 8.

The principle of operation is covered well by O'Neil (note 2). Since this article deals with the practical aspects of traps, we won't delve into the electrical characteristics of the coaxial trap too deeply. However, a diagram showing how it is hooked up is offered in Fig. 9B. A length of coaxial line is wound on a coil form, and the inner conductor at one end is attached to the outer conductor at the opposite end. The distributed capacitance of the two conductors and the inductance of the coil combine to provide a resonant circuit. An acceptable Q results, and the trap can accommodate considerable rf voltage and current without being damaged. A parallel resistance of 50 kΩ was measured for the 20-meter trap of Fig. 8. The bandwidth at the 10 kΩ points was somewhat greater than with the toroidal trap.

Coaxial-Trap Assembly

I found 5/8-inch-OD PVC plumbing pipe to be an acceptable and low-cost material for the coaxial traps. End plugs made from 1/2-inch wooden dowel fit snugly inside the PVC pipe. The completed trap contains a length of bus wire inside it for connecting the braid and center conductor of the cable together, as discussed earlier. The ends of the bus wire and the related cable ends are routed outside the PVC tubing through small holes, then soldered. Aquarium cement was again used, this time to seal the six small holes drilled in the tubing. Epoxy cement was applied to the sides of the wooden plugs before inserting them into the tubing. A layer of vinyl electrical tape can be wound over the coaxial coil if desired, although this should not be necessary. If weather protection is desired, a coating of exterior polyurethane varnish can be applied to the completed close-wound coil. This will keep the turns affixed in the desired position after final adjustment. Tune-up is carried out in the same manner as prescribed for the toroidal traps, using a dip meter or the test fixture described in Fig. 5.

The length of the coaxial cable used will have to be determined experimentally. My 20-meter coaxial trap contains 15 close-wound turns of RG-174 cable (36 inches, 89 pF) to provide resonance at 14.100 MHz. Final adjustment was done by moving the three outer turns at one end until the desired frequency was noted. The coil form for the 20-meter trap is 2-1/2 inches long. The wooden end plugs are 3/8 inch thick. The inside of this trap is not filled with sealant, but it could be if desired. Avoiding the use of filler will make the traps lighter in weight, thereby permitting the use of lighter-gauge wire for the antenna sections.

Trap Performance

Both styles of trap were subjected to rf power tests to determine whether they could handle the output of a typical 150-W class transceiver. A Bird wattmeter was connected between the trap and the transmitter. A 50-ohm dummy load was attached to the opposite end of the trap. Next, 40- and 80-meter rf energy was applied (in separate tests) gradually while observing the reflected power, which of course was not conducive to providing an SWR of 1:1 with the trap in the line. Neither trap showed signs of heating or breakdown at power levels up to 150 W. A key-down period of five minutes was tried during the tests, using a linear amplifier adjusted for 150-W output. Still no sign of power limitation. The SWR did not change under these conditions. I did not advance the power beyond 150 W, but it's safe to conclude that the coaxial-cable trap could sustain substantially more power without damage. This may not be true of the toroidal trap. I lacked the courage to find out!

Toward a Lightweight Dipole

Having solved the problem of lightweight, small traps I set about the task of reducing the bulk of the remainder of my multiband dipole. I am a dedicated miser, so the cost of materials was an important factor in the selection of wire and end insulators. I recalled a type of wire I had used on a number of DXpeditions: It was strong and light in weight, and the price was right! This wire is available from Radio Shack and similar outlets for use as speaker cable. It has a clear plastic outer covering, contains a no. 22 conductor (two each) and costs less than $5 per 100 feet. Hence, for this price we end up with 200 feet of wire (less than 2.5 cents per foot); the parallel conductors can be pulled apart easily without harming the outer insulation. In addition to the insulation aiding the strength of the wire portions of the antenna, it protects the copper



Fig. 7 — View of a toroidal mini trap, an encapsulated toroid and a PVC T-coupling for use as a center insulator. RG-58/U cable is shown in this example (see text).



Fig. 8 — A completed 20-meter coaxial trap with miniature RG-174/U coaxial cable.



Fig. 9 — At A is a breakaway view of a coaxial trap. The illustration at B shows the electrical connections for a coaxial trap.

wire from corrosion. This can be especially beneficial in areas where salt water and industrial pollutants affect the atmosphere. The Radio Shack number for this wire is 278-1385. I have observed no apparent deterioration of this type of conductor, even though some of my antennas have been aloft for three years.

Although RG-58/U coaxial cable is less offensive in terms of loss per 100 feet than is true of RG-174/U, we may want to trade losses for portability by using '174. Normally, a 50-foot length of feeder cable is adequate for portable work. In an effort to determine exactly what the hf-band losses per 50 feet might be, I tested this cable from 3.5 through 29 MHz. A Bird wattmeter was connected to each end of the 50-foot test cable. One wattmeter was terminated with a 50-ohm dummy load, and the other wattmeter was connected to a transmitter. The loss in decibels was as follows: 3.5 MHz — 1.19; 7.0 MHz — 1.42; 14.0 MHz — 1.67; 21 MHz — 1.93; 29 MHz — 2.0. Therefore, in a worst-case situation (10 meters), a 100-W power input to the cable would result in an antenna feed-point power of 63 W. RG-58/U, on the other hand, would have a 1-dB loss at 29 MHz, which would mean an antenna feed-point power of 79.4 W. This is not too significant when operating in the 50-150 W range, but it can be important when using a QRP rig with only a few watts or milliwatts of output power. I must say in defense of RG-174/U cable that I operated 20-meter cw with 2 W of output power from 8P6EU while using a dipole with 50 feet of RG-174/U feed line, and I worked the world without difficulty. I received many RST 599 signal reports. The tiny feeder cable and the hookup-wire dipole could be rolled up and stuffed in my hip pocket! The end and center insulators for that antenna were also lightweight. I made them from scraps of pc board from which the copper had been removed. The end insulators for the trap dipole discussed in this article were fashioned from inch-long pieces of 5/8-inch-diameter PVC tubing through which holes were drilled to accommodate the dipole wires and nylon guy lines.

Summary Comments

The overall length of any dipole section in a trap type of antenna will be less than if the dipole were cut for a single band without traps. The exception is the first dipole section after the feed point (out to the first set of traps). The following percentages (approximate) were typical in a coaxial-trap dipole I built for use from 40 through 10 meters, compared to the length of a full dipole (100%) for each band: 10 meters — 100%; 15 meters — 92.4%; 20 meters — 88.8%; 40 meters — 83.6%. The shortening becomes more pronounced as the frequency is lowered, owing to the cumulative loading effects of the traps.

These percentages can be applied during initial structuring of the antenna. Starting with the highest band, the dipole sections for each frequency of interest are trimmed or lengthened for the lowest attainable SWR. After the exact dimensions are known, continuous lengths of wire can be used between the traps. This will add strength to the antenna by avoiding breaks in the speaker-wire insulation, if that type of conductor is used. The percentage reductions listed above are not necessarily applicable to antennas that use toroidal or other coil/capacitor traps. The wire diameter and insulation may also affect the final dimensions of the dipole.

For long-term installations, I would suggest the use of some type of sealer (spar varnish or polyurethane) over the wooden end plugs of the traps. All trap holes need to be sealed securely to prevent moisture from building up inside them.

Miniature antenna traps and lightweight trap dipole antennas are practical and inexpensive to build. Try one during your next vacation or business trip.

Notes

[1] mm = in. × 25.4; m = ft × 0.3048.

[2] G. O'Neil, "Trapping the Mysteries of Trapped Antennas," *Ham Radio*, Oct. 1981, p. 10.

[3] R. Johns, "Coaxial Cable Antenna Traps," *QST*, May 1981, p. 15.

From December 1988 QST, p 31:

A Portable Vertical-Antenna Mount

Need a temporary, good-performing antenna? The mounting technique described here makes for quick installation of a multiband vertical with a minimum of fuss!

By Guy Black, W4PSJ
1201 Woodside Dr
Winchester, VA 22601

Field Day contestants, vacationers and tenants sometimes need temporary antennas. On the high-frequency bands, a hunk of wire hung from one or more trees often seems to be the best that can be done. To get such an antenna put up, a weight with a rope tied to it is usually thrown into a tree, and the antenna is then pulled up with the rope. I don't have very good aim and my throwing skills are underwhelming, so the dipoles and end-fed lengths of random wire I've managed to put up as temporary antennas have usually been disappointing performers.

For the last several years, I have used a multiband vertical (a Butternut HF2V) at home with great success, particularly for DXing on the 80, 75 and 40-meter bands. Why not turn such a vertical into a portable antenna? It's essentially pre-tuned, and there's no strain on the throwing arm! Light, uncomplicated and easily transported multiband verticals have many possibilities.


Fig 1—Photograph of the portable vertical-antenna mount. The lower rotator-mast-mount casting is bolted to a steel plate, with a copper disc in between for attachment of radials. One of the bags of garden stone used to hold down the wooden stakes is visible in the upper right corner of the photo.

My antenna came with a 22-inch aluminum ground stake. With care, it is possible to drive this stake into the ground repeatedly and without damage by using a short (one foot or more) section of TV masting, which fits nicely over the base insulator, as a driver. Unfortunately, doing this requires the availability of a small sledgehammer (or a large one, depending on the ground!).

Another approach is to use a *portable base* with the vertical. This takes up a bit more space in the car than just a ground stake, but at least you don't need to carry along a sledgehammer!

Materials

The parts for my portable base are a 1 × 1-foot metal plate (an old rack panel works fine), the lower mast-support casting from a rotator (with its hardware), a 7-inch-diameter disc of copper-clad PC board, five 6-foot-long 1 × 1-inch hardwood stakes from a garden supply store, a 1 × 12-inch strip of thin hobby brass, a chassis-mount SO-239 connector and a 6-inch length of 1-inch ID plastic water pipe. A few nuts, bolts, spade lugs, washers, and 500 feet of no. 14 stranded copper wire round out the materials list.

Construction

Bolt four of the hardwood stakes to the steel plate in a pinwheel configuration, as shown in Fig 1. Drill 10 equally spaced holes (large enough to pass no. 6-32 screws) around the outside edge of the PC-board disc. Then, center the mast support on the PC board, and mark and drill the four mounting holes on the PC board. Mark and drill the four mounting holes on the metal plate.

Thread 10 binding-head machine screws into the PC-board disc from the bottom, and connect the mast support, PC-board disc and metal plate using the mast-support casting hardware. The heads of the machine screws should be between the metal plate and the PC-board disc. There is enough flex in the PC board so that the board won't break when the mast-support hardware is tightened. Slip the section of plastic pipe over the vertical-antenna mount, insert the pipe and antenna mount in the rotator mast support, and tighten the mounting clamps.

The section of plastic water pipe is necessary when using this mounting arrangement with a Butternut vertical, because the minimum diameter the clamps will grasp exceeds the one-inch OD of Butternut's base insulator. Other antennas may not require the plastic pipe section.

Part of the one-inch-wide brass strap is used to connect the ground side of the vertical to the copper disc. The remaining piece of brass is used for mounting the SO-239 connector. (If your vertical already has a coaxial feed-point connector, skip this paragraph.) This brass piece should be about 1 × 2¾ inches, with a 5/8-inch hole near one end, and four no. 32 holes for no. 4-40 mounting hardware around the 5/8-inch hole. This hole is for mounting the SO-239 feed-point connector. Put a 90° bend in the brass piece about ¾ inch from the end opposite the SO-239 mounting hole. Mount the connector using no. 4-40 hardware, and solder the ¾-inch section of the brass strip to the disc of PC-board material so that the SO-239 faces away from the antenna and clears the hardwood stake (see Fig 1). Connect the shortest practical length of no. 14 wire from the SO-239 to the feed-point connection of the vertical.

Assemble the vertical according to the manufacturer's instructions, and install it on the mount. I'm not sure how much wind force the portable vertical antenna system can handle, so when I use it I weight down the stabilizer stakes with bags of garden stone, one of which can be seen in the upper right corner of Fig 1. An easier (and lighter) solution is to guy the antenna with lightweight nylon rope. Bricks (for holding the ends of the radials) and bags of garden stone or sand are widely available, and cheap enough to discard when you're through with them.

The Radials

I use the portable vertical-antenna mount with ten 50-foot radials, each spaced 36° apart on the ground. By using flanged, solderless spade lugs (Waldom DS-1083) it is not necessary to remove the nuts on the machine screws to connect the radials. The outer ends of the radials are held down by bricks. (Bricks aren't needed to hold down the radial wires if rocks or some other suitable weights are available.)

The fifth hardwood stake is used in lining up the radials (it also serves as a spare mounting-plate stabilizer). Paint a mark on each radial wire, 9 feet 5 inches from the machine-screw connection point (nail polish works fine for this). At that distance from the casting, uniformly space the radials 36° apart by laying the spare six-foot stake between the painted marks on adjacent radial wires. This makes for a neat layout with a mimimum of fuss. Installation is easier if the radial wires are coiled up from the brick end (so that the connection lug is on the outside of the coiled radial). Tape or wire ties can be used to keep the coiled radials from getting tangled.

Results

With the Butternut HF2V erected on the portable mount in my back yard, tune-up went smoothly. The antenna has an SWR of less than 2:1 across the 40-meter band, and over the selected 30 kHz of 75 meters. Switching back and forth between the portable vertical and my permanently installed vertical (also an HF2V, but with a larger radial field) I found little difference in received signal strength. I had the same good results working DX on both antennas. A 100-foot-square area is needed for the ground radials if the antenna is put up as described, but the radials can be bent or shortened if necessary.

This antenna is so easy to put up and take down that it can be erected for just a few days' use. For easy transportation, I use the antenna's original 66-inch-long shipping carton to carry the antenna and the stakes, and a two-gallon milk crate for the radials, base plate and hardware. All the components of a handy and effective portable antenna system are in two packages, ready to go, and my throwing arm doesn't even get a workout!

From December 1987 QST, p 25:

An Extended Double Zepp Antenna for 12 Meters

Got a little over 50 feet of horizontal space to spare for a 24-MHz skywire? This simple antenna will beat your half-wave dipole by about 3 dB—and you can phase two of them for even more gain and directivity.

By John J. Reh, K7KGP
510 Mt Defiance Cir SW
Issaquah, WA 98027

According to *The ARRL Antenna Book*, *Zepp*—short for Zeppelin—is a term long applied to just about any resonant antenna end-fed by a two-wire transmission line.[1] A bit further on in the *Antenna Book*, there's a discussion of the extended double Zepp (EDZ) antenna.[2] This interested me because I have always been intrigued by "old-fashioned" wire antennas—and because the old-fashioned extended double Zepp's 3-dB gain over a half-wave dipole would provide performance quite suitable for *modern* times! The EDZ antenna consists of two collinear 0.64-λ elements fed in phase. Fig 1 shows current distribution in an EDZ, and Fig 2 shows the EDZ's horizontal directivity pattern in free space.



Fig 1—The extended double Zepp antenna consists of two 0.64-λ elements fed in phase.



Fig 2—Horizontal directivity pattern for an extended double Zepp antenna in free space. Relative to a half-wave dipole, it exhibits a gain of approximately 3 dB. The antenna elements lie along the 90°-270° line.

The extended double Zepp's theoretical performance looked good to me, so I designed and built an EDZ antenna for the 12-meter band. Fig 3 shows its configuration. I decided to cut mine for 24.950 MHz. Each EDZ element is 25 feet, 3 inches long, and consists of no. 14 stranded copper wire. The antenna elements are center-fed by a short matching section made of a 5-foot, 5-inch length of 450-Ω open-wire line. Connection to 52-Ω coaxial feed line is made by means of a 1:1 balun transformer. My EDZ is strung between two trees, 35 feet above ground.

Matching Section

Perhaps I am "reinventing the wheel," but I have not seen this matching method



Fig 3—The extended double Zepp at K7KGP, cut for 24.950 MHz. The 450-Ω matching section transforms the EDZ's calculated input impedance (142-j555 Ω) to 55 Ω (measured) for connection to 52-Ω coaxial cable by means of a 1:1 balun. The electrical length of the matching section is 52°; the linear dimension shown in the drawing assumes 450-Ω line with a velocity factor of 0.95.

---

[1] Notes appear at end of article.



Fig 4—Comparison of calculated horizontal directivity patterns of one extended double Zepp (dotted line), and two EDZs spaced at 1/8 λ and fed 180° out of phase (solid line). The antenna axes lie along the 0°-180° line, and the antennas are mounted 35 feet above average earth. The phased EDZs exhibit nearly 5 dB gain over a single EDZ. This is 7 to 8 dB gain over a half-wave dipole. Beamwidth of the two-EDZ array is 30°. The antenna axis is the same for the single EDZ and both EDZs in the phased array. The two-EDZ configuration characterized here is an *end-fire* array because maximum radiation occurs along its axis.



Fig 5—Comparison of the calculated vertical directivity patterns of one EDZ (dotted line), and two EDZs spaced at 1/8 λ and fed 180° out of phase (solid line). The antenna axis lies along the 0° line.

elsewhere.[3] The open-wire-line matching section is 52 electrical degrees long (0.145 λ). The matching section transforms the EDZ's input impedance to about 55 ohms, as measured with a noise bridge. The matching-section dimension given in Fig 3 assumes a velocity factor of 0.95 for the 450-Ω line.

Trimming the matching section to size is the only adjustment necessary with the EDZ. Make the transformer a little long to begin with, and shorten it an inch or two at a time to bring the system into resonance. (You can check resonance with a noise bridge or by monitoring the SWR.) Do *not* change the length of the elements—the EDZ's gain and directivity depend on its elements being 0.64 λ long.

Phasing Two EDZs for More Gain and Directivity

Properly phased, two extended double Zepp antennas can give improved gain and directivity over a single EDZ. Fig 4 compares the calculated horizontal directivity patterns of a single EDZ and an array consisting of two EDZs spaced at 1/8 λ and fed 180° out of phase. Fig 5 compares the vertical radiation patterns of the single and phased EDZs.

Fig 6 shows the dimensions of a practical two-EDZ configuration. With proper adjustment, it exhibits an SWR of 1.3:1 across the 24-MHz band. In the array I built, lightweight broom handles serve as spreaders between the element ends; the center spreader is a wooden slat. I used nylon rope to haul the array up between two trees. This antenna system works well, but poor propagation has precluded a thorough tryout so far. The contacts I have had with it have been entirely satisfactory.

The matching method shown in Fig 6 is somewhat clumsy because the combined length of the phasing lines is greater than the spacing between the EDZs. The feed method shown in Fig 7 should be easier to build because the combined length of the phasing lines equals the spacing between



ANTENNA ELEMENTS ARE NO. 14 STRANDED COPPER WIRE
PHASING LINES AND STUB ARE 450-Ω OPEN-WIRE LINE
FEED AT XY (SEE CAPTION)

Fig 6—One method of phasing two EDZs for greater gain and directivity. The array is bidirectional, with maximum radiation occurring along the array axis. The impedance across points X and Y is 50 Ω, balanced; with a 1:1 balun at XY, the array can be fed by means of 52-Ω coaxial cable. The stub, 1.5° long, cancels a capacitive reactance of approximately 13.5 Ω at the feed point. This array works well, but its matching system is clumsy because the combined length of the phasing lines is greater than the spacing of the two EDZs. Fig 7 shows a proposed feed method that takes up less space.

the EDZs. I have not tried this matching method, but I'm confident that my calculated dimensions are close to what will actually be encountered.[4]

Conclusion

If the extended double Zepp has caught your attention, but 12 meters hasn't, you can scale the linear dimensions given here for other bands of interest. Once your EDZ is up and working, I think you'll agree that the performance of the "old-fashioned" extended double Zepp isn't old-fashioned at all!


ARRAY AXIS
25' 3"
25' 3"
PHASING LINES, EACH 2' 5-1/2" LONG
b
a
4' 11"
MATCHING SECTION
1' 2"
CLOSED STUB 5" LONG
1:1 BALUN
x y
52-Ω COAX, ANY LENGTH
TO TX
ANTENNA ELEMENTS ARE NO. 14 STRANDED COPPER WIRE
PHASING LINE, MATCHING SECTION AND STUB ARE 450-Ω OPEN-WIRE LINE

Fig 7—Proposed alternative method of phasing two EDZs. In this arrangement, the length of each phasing line is half the EDZ spacing. Calculated impedance across points a and b is 15-j112 Ω. The matching section—11° in length—transforms this to a calculated impedance of approximately 55-j32 Ω (balanced) across points x and y. The stub, 4° long, cancels the capacitive reactance (32 Ω). A 1:1 balun transformer allows the array to be fed by means of 52-Ω coaxial cable. See text.

Notes

[1] *The ARRL Antenna Book*, J. Hall, ed. (Newington: ARRL, 1984), p 5-4.

[2] *The ARRL Antenna Book*, p 6-8.

[3] K7KGP's matching technique is a "reinvention of the wheel" of which he can be proud. Termed the series section transformer, it appears in *The ARRL Antenna Book* and *The ARRL Handbook*. The series-section material in these books is based on Frank A. Regier, "Series-Section Transmission-Line Impedance Matching," *QST*, Jul 1978, pp 14-16.—Ed.

[4] K7KGP's calculations were confirmed by Rus Healy, NJ2L, of the ARRL HQ Technical staff, using the Smith® Chart and the Mini-Numerical Electronics Code (MININEC) on an IBM® personal computer. Data for the plots in Figs 4 and 5 were also generated by means of MININEC.—Ed.

From December 1988 QST, *p 47:*

Scaling the Extended Double Zepp

☐ You can easily scale the design of an extended double Zepp (EDZ)[5] to work on another band. For example, assume you wanted to build an EDZ for 7.2 MHz, basing the design on the 24.95-MHz antenna presented in my December article. The 24.95-MHz antenna has element lengths of 25 ' 3" and the matching-transformer line length is 5 ' 5". Use the following formula to scale the antenna dimensions to the desired band:

$$L2 = \frac{(f1 \times L1)}{f2} \qquad \text{(Eq 1)}$$

where

L2 = length at the desired frequency

f1 = resonant frequency of the original antenna

L1 = length of interest at the resonant frequency of the original antenna

f2 = resonant frequency of the new antenna

Lengths for L1 and L2 must be expressed in similar units of measurement (feet, meters, etc); this also applies to the units of measurement used for f1 and f2 (kilohertz, megahertz, etc).

Substituting the values for element length

$$L2 = \frac{24.95 \times 25.25}{7.2} = 87'6'' \qquad \text{(Eq 2)}$$

and matching-transformer length

$$L2 = \frac{24.95 \times 5.417}{7.2} = 18'9'' \qquad \text{(Eq 3)}$$

This scaling technique also works for element spacings. Velocity-factor considerations can be ignored because they were included in the initial design.—*John Reh, K7KGP, 510 Mt Defiance Cir SW, Issaquah, WA 98027*

---

[5] J. Reh, "An Extended Double Zepp Antenna for 12 Meters," *QST*, Dec 1987, pp 25-27.

From October 1988 QST, p 42:

An Indoor Dipole Antenna

☐ I live in an apartment. Because of this, I'm limited in the size and type of antenna I can install for use on HF. After trying end-fed random wires, loops, mobile verticals, rain gutters and so on, I designed a multiband dipole antenna that requires no tuning after installation. It's inconspicuous, non-hazardous and efficient. I used the following materials to construct it: one PL-259 connector; 12 feet of "Mini 8" coaxial cable; two nylon cable ties; approximately 45 feet of no. 22 insulated, solid copper wire; six test leads with alligator clips; 26 thumbtacks; and an SWR bridge. The antenna was installed in less than two hours.

After attaching the PL-259 to the coaxial cable, I wound 6 feet of the coax into a tight coil and held this winding together with two nylon cable ties. The result is a shield-choke balun at the point where the antenna elements attach to the cable.[2]

Using the formula $\ell \text{ (feet)} = 234 \div f \text{ (MHz)}$, I calculated the length of wire necessary for each leg of a half-wave dipole at 21.1 MHz. Next, I cut two wires to this length and attached them to the feed line, one to the shield braid and the other to the center conductor. Using my transmitter and SWR meter, I pruned the dipole ends equally until I obtained the lowest possible SWR at 21 MHz. (Caution: Trim the antenna wires only when the transmitter is *off.*)

At this point, the clip leads come into play. To get the antenna up and running on 14 MHz, follow this procedure: (1) Attach a clip lead to the end of the 15-meter dipole; (2) calculate the length of the legs of a 14-MHz dipole; (3) add enough wire to each clip lead/dipole leg to bring the total length of the each 14-MHz dipole leg to the length calculated in step 2; and (4) prune the added wire for minimum SWR at the 14-MHz design frequency with the aid of the transmitter and SWR bridge. Continue this procedure to add additional clip leads and wire segments for 10 and 7 MHz. I used the thumbtacks to secure the wire pieces and test leads to the plasterboard ceiling of my apartment. Fig 6 shows the configuration of the entire antenna in linear form.

In my installation, the actual length of the dipole legs for a given band is about 14% shorter than the calculated length. This is probably due to the proximity of the antenna to the apartment ceiling—and the fact that I had to install the antenna around the perimeter of a square room, almost like a loop!

Careful pruning of the antenna for my favorite band segments paid off: An antenna tuner is unnecessary on all of the antenna's four bands. With the addition of Doug DeMaw's "AC Outlet Strip with Filtering" (December 1986 *QST*, pages 25-27), I eliminated TVI and RFI from my station.

—Larry A. Barry, NV5I, 5903 Danny Kaye #1308, San Antonio, TX 78240

An antenna similar to Larry's has been in use at AK7M for several years. I use alligator clips instead of test leads, and my antenna's wire sections are held away from the plasterboard by nylon cable ties and thumbtacks. I can't complain about its performance: I've worked plenty of DX on 30, 20 and 15 meters running just 20 W output. Moral: All's not lost if you live in an apartment: Just keep plugging away with That Old Ham Spirit!—*AK7M*



Fig 6—Larry Barry's multiband dipole makes crafty use of clip leads and thumbtacks to stuff half-wave dipoles for 15, 20, 30 and 40 meters into cramped apartment space. Changing bands entails only the connection or disconnection of clip leads. This drawing shows a straight dipole; Larry's antenna is bent into a square but works just fine. See text.

---

[2] See Bob Schetgen, "Shield Chokes for Coaxial Cable," *QST*, Mar 1988, p 41.

From April 1989 QST, p 38:

A Short 7-MHz Dipole

☐ Here are dimensions and construction information for a short, inductively loaded dipole for 40 meters. If installed over 50 ft above ground—outdoors or even in an apartment—it can provide plenty of DX.



Fig 2—Stan Grimes suggests using this short, loaded 7-MHz half-way dipole where space is limited. The antenna and loading coils consist of no. 14 insulated wire; see text.

See Fig 2. The antenna and loading coils consist of a total of 60 ft of no. 14 plastic-covered wire. Wind the loading coils first: Each consists of 30 close-wound turns on a 1½-inch-diam plastic form [pill bottles are suitable—*AK7M*]. Use the rest of the wire as shown in Fig 2. (If space prohibits an overall antenna length of 32½ ft, you can let the 6¼-ft end sections dangle for a total length of just over 20 ft. Feed the antenna as close to its center as you can; 50- or 72-ohm coax is suitable. Preferably, the feed line should leave the antenna at a right angle.

This system can handle up to 120 W. Installed as shown in Fig 2, it should exhibit better than a 2:1 SWR from 7050 to 7160 kHz.—*Stan Grimes, W7CQB, 13300 NW 14th Ave #A, Vancouver, WA 98685-1652*

From July 1980 QST, p 17:

Active Filters

Why not build one of these nifty filters or use the design information to customize your own!

By Alan Bloom,* N1AL

One of the triumphs of modern technology is that you can build "tuned circuits" and all kinds of other filters entirely without coils. Those generations of RTTY enthusiasts who grew up depending on the ubiquitous 88-mH toroidal inductors might be shocked to discover that you can replace up to four of these bulky items with a single IC. Besides their size and expense, coil-capacitor filters at audio frequencies are notoriously hard to tune — it's just hard to find variable coils or capacitors big enough to do the job. Many active filters can be tuned with an inexpensive potentiometer.

What *is* an active filter? Well, what is a *filter*? We generally consider a filter to be any circuit designed to attenuate some frequencies more than others. A *high-pass* filter passes high frequencies with little attenuation while providing greater attenuation to the lower frequencies. See Fig. 1A. The *cutoff frequency* of a high-pass filter is the lowest frequency that passes with relatively little attenuation. The region above the cutoff frequency is the *passband*, and the region of high attenuation is the *stopband*. A *low-pass* filter has its passband below the cutoff frequency and its stopband above. A *band-pass* filter has two stopbands — one above and one below the passband, and a *band-stop* filter has a stopband between a pair of passbands. See Fig. 1B.

An *active* filter is simply a filter that uses an active device to improve the attenuation characteristics. That Q-multiplier in your old receiver is an early type of active filter. While most active filters these days use operational amplifiers (op amps),[1] you can make some type of active filter with almost any device that has power gain.

RC Active Filters

It's quite possible to design active filters using coils. We've already mentioned the antediluvian Q-multiplier as one example, and we'll look at a couple of others later. But today, most people try to design inductors *out* of their circuits, at least at audio frequencies. As previously mentioned, coils for audio frequencies are often large and frequently expensive. Although passive LC (inductance-capacitance) filters require no power supply, you have to design them carefully to minimize loss, paying careful attention to input and output impedance matching. Active filters, on the other hand, can easily be designed for almost any desired input and output impedances, and can give considerable gain to boot! RC (resistance-capacitance) active filters are especially useful at low audio frequencies where the large inductances needed for LC filters become impractical.



Fig. 1 — At A, plots of relative output versus frequency for high-pass and low-pass filters; f_c is the cutoff frequency. At B, plots of relative output versus frequency for band-pass and band-stop filters; f_0 is the center frequency. The area between f_1 and f_2 is the passband of the band-pass filter and the stopband of the band-stop filter.



Fig. 2 — A passive RC band-pass filter. Maximum Q obtainable is only 1/2.



Fig. 3 — An active RC band-pass filter. To design a filter using this circuit, make all the frequency-determining resistors and capacitors equal: R1 = R2 = R3 and C1 = C2. Choose a convenient value for C and then $R = \sqrt{2}/(2\pi C f_0)$, where R is in kΩ, C is in μF, and f_0 is in kHz. $Q = f_0/B$, where B is the 3-dB bandwidth in kHz. R4 and R5 determine the Q: $R5/R4 = 3 - (\sqrt{2}/Q)$. The voltage gain is $2Q\sqrt{2} - 1$.

Band-Pass RC Active Filters

You *can* make an RC filter without any active devices. Look at Fig. 2. At high frequencies, most of the signal is shorted out by C1. At low frequencies, most of the signal is blocked by C2. Thus the circuit of Fig. 2 is a band-pass filter. The limitation is that the maximum Q possible with this type of filter is only 1/2.

Those familiar with Q-multipliers or regenerative detectors may recall that one way to increase the Q of a tuned circuit is to introduce a little positive feedback around it. (If you apply too much feedback, the circuit will oscillate.) The same trick works for an RC bandpass filter. See Fig. 3. Here R3 has been added to couple in the signal. You can use a number of different resistor and capacitor values to achieve the desired filter characteristics, but for simplicity we usually make the two capacitor values the same and also let R1 = R2 = R3.

Let's say we want a 1-kHz band-pass filter with a 3-dB bandwidth of 600 Hz. The bandwidth is just the center frequency divided by the Q so we have $B = f_0/Q$ or $Q = f_0/B = 1000/600 = 1.67$. So using the equations from Fig. 3, $R5/R4 = 3 - (\sqrt{2}/1.67) = 2.15$. The actual values of these resistors are not too important — it's the *ratio* of the two that determines

---

*1578 Los Alamos Rd, Santa Rosa, CA 95401

[1] Notes appear at end of article.


10 k
10k
27 k
+9 V
0.05
22 k
INPUT
2
7
1 µF
15 V
6
741
OUTPUT
22 k
0.01
3
4
0.01
22 k
-9 V
(A)
+12 V
OUTPUT
330
1 µF
15V
10 k
3.9 k
2N3904
2N3904
INPUT
1 µF
15V
3.3 k
0.1
330
.01
4.7 k
1.8 k
10 µF
15V
10k
3.3 k
(B)

Fig. 4 — A practical audio filter is shown at A, based on the design in Fig. 3. The Q can be varied by adjusting the 10-kΩ potentiometer. A band-pass filter using discrete transistors is shown at B. R2 in Fig. 3 is the parallel combination of the 4.7-kΩ and 10-kΩ resistors in Fig. 4B (about 3 kΩ).



Fig. 5 — Measured frequency response of the filter of Fig. 4A. The center frequency and bandwidth are not exactly as predicted because of component tolerances.


R2
C1
C2
OUTPUT
INPUT
R1
R3

Fig. 6 — A tunable band-pass filter. After choosing a value for C (C1 = C2), then R2 = 1/πBC), where R2 is in kΩ, C is in µF, and B is the bandwidth in kHz. R1 (kΩ) = R2/2G, where G is the desired numerical voltage gain at resonance.

$$R3\ (k\Omega) = \frac{1}{2\pi C\ [(2f_o{}^2/B) - BG]}$$

where f_o is in kHz. Insert the minimum and maximum values of f_o into the above equation to get the maximum and minimum values for R3.


+9V
2
220 k
0.01
0.01
7
741
6
OUTPUT
1 µF
15 V
INPUT
3
4
0.01
100 k
330
-9V
10 k

Fig. 7 — A practical band-pass filter that tunes from 350 to 2000 Hz.

the Q and gain. Let's choose R4 = 15 kΩ. Then R5 = 2.15 × 15 kΩ = 32 kΩ. (If R5/R4 = 3, the Q is infinite and the circuit becomes an oscillator.) To allow for resistor tolerances you usually use a potentiometer to adjust the gain to get the exact Q you want. See Fig. 4A. With the potentiometer set to the middle of its range, the effective values of R4 and R5 are 15 kΩ and 32 kΩ respectively, as desired. Next, choose a value for R or C. Let's let C = 0.01 µF. (All of the formulas in this article express capacitance in microfarads, resistance in kilohms, and frequency in kilohertz.) Then R = $\sqrt{2}/(2\pi C f_o)$ = 22.5 kΩ or about 22 kΩ. Fig. 5 shows the measured frequency response of the circuit in Fig. 4A. You can raise or lower the Q by adjusting the potentiometer. If you want to tune this



Fig. 8 — Measured frequency response of the circuit of Fig. 7 for three settings of the potentiometer.



Fig. 13 — A 50-kHz band-pass filter. Calculated voltage gain is 200 and the Q is 10, giving a bandwidth of 5 kHz. Since a standard 741 op amp does not work well above 10 kHz, a high-slew-rate version is used. To design for other frequencies, first choose a value for C1, then R2 = GB/(2πC1f_o^2), where GB is the gain-bandwidth product of the op amp (1000 kHz for a 741 or 741S). Choose Q using Q = f_o/B or Q = Gf_o/GB. Then

$$R1 = \frac{R2f_o}{GB}\left(\frac{1}{Q} - \frac{f_o}{GB}\right).$$

The highest possible Q is GB/f_o and the highest possible gain is QGB/f_o.



Fig. 9 — A low-pass active filter. For Q greater than one, a low pass filter has a peak in the frequency response similar to that of a band-pass filter. For relatively narrow bandwidths, Q is approximately f_o/B. R2/R1 = 2 − (1/Q). For a given value of C (C1 = C2), R3 = R4 = 1/(2πf_oC), where R is in kΩ, C is in μF, and f_o is in kHz. The gain at f_o is 3Q − 1.



Fig. 11 — A high-pass filter. For fairly narrow bandwidth (high Q), the Q of a high-pass filter is approximately f_o/B. R2/R1 = 2 − (1/Q). For a given value of C (C1 = C2), R3 = R4 = 1/(2πf_oC), where all quantities are expressed in the same units used in the previous examples. The gain at f_o is 3Q − 1.



Fig. 14 — A band-pass LC active filter. Q = f_o/B. Choose a convenient value for L1, then

$$C1 = \frac{1}{(2\pi f_o)^2 L1}$$

where L1 is in henrys and C1 is in μF. R3 = QX, where X is the inductive or capacitive reactance in kΩ (X = 2πf_oL). The gain is 1 + R2/R1. R2/R1 = R5/R4. R4 includes the losses in L1.



Fig. 10 — Another low-pass filter. Choose C2, then C1 = C2(3Q)^2. R1 = R2 = R3 = 1/(2πf_o $\sqrt{C1C2}$), where R is in kΩ, C is in μF, and f_o is in kHz. The gain is equal to Q.



Fig. 12 — Another high-pass filter. Choose R1, then R2 = R1(3Q)^2. C1 = C2 = C3 = 1/(2πf_o $\sqrt{R1R2}$). The gain is equal to Q.

filter without changing the Q, you would need three ganged potentiometers to replace R1, R2 and R3.

Don't get the idea that all RC active filters must be made with op amps. The design of Fig. 3 works fine using a pair of transistors. Fig. 4B is a practical example. The center frequency is about 700 Hz, and the bandwidth is determined by the setting of the 10-kΩ potentiometer.

The filter of Fig. 6 has the interesting property that you can tune the center frequency without changing the gain by varying a single resistor, R3.[3] In addition, the

Q increases with frequency in such a way that the bandwidth stays constant for all tuning settings — a sort of "poor man's passband tuning!"

To design one of these filters, you first choose the bandwidth (B), gain (G) and the lowest and highest frequencies to be tuned (f_{min}, f_{max}). Let's say you want to tune 350 to 2000 Hz (0.35 kHz to 2 kHz) with a bandwidth of 150 Hz (0.15 kHz) and a gain of one. Again we'll choose 0.01 µF for the capacitor value. From the formulas in Fig. 6, R2 = 1/ (π × 0.15 × 0.01) = 212 kΩ, R1 = 106 kΩ and the minimum and maximum values of R3 turn out to be 300 Ω and 10.7 kΩ. Using the nearest standard resistor values, we get the circuit of Fig. 7. Fig. 8 indicates the measured frequency response for the circuit. If your calculations give you a negative value for R3, then your lower frequency limit is too low or your gain is too high. Choose new values and recalculate.

Low-Pass RC Active Filters

If you need attenuation of *higher* frequencies only (such as adjacent-channel ssb interference), a low-pass filter will fill the bill. Representative designs are given in Figs. 9 and 10.

The circuit of Fig. 9 can be tuned by ganged potentiometers at R3 and R4. The Q can be adjusted by inserting a potentiometer between R1 and R2 as in Fig. 4A.

While it's not as easy to tune, the circuit of Fig. 10 has better stability than that of Fig. 9. For high values of Q, the gain and Q of the latter filter will change markedly for small changes in any of the resistor or capacitor values. If you need only a fixed-frequency filter, the one in Fig. 10 is a better choice.

High-Pass RC Active Filters

In principle, you can convert any RC low-pass filter into a high-pass filter by substituting resistors for all the capacitors and capacitors for all the resistors. The circuits of Figs. 11 and 12 correspond to the low-pass filters in Figs. 9 and 10, respectively. Their characteristics are similar except that they are high-pass in nature. Actually, for high values of Q, the frequency responses of band-pass, low-pass and high-pass filters are pretty much the same close to the peak frequency. It's only when you get well away from the passband that you start to notice differences in attenuation.

Fig. 13 is a band-pass filter that uses the internal frequency compensation of the op amp to replace one of the capacitors in the feedback network. This circuit has very high gain at low frequencies. Even at 50 kHz, the tuned i-f amplifier shown has a gain of about 200, which requires careful attention to circuit layout to



Fig. 15 — A tunable 50-kHz amplifier patterned after the circuit of Fig. 14.



Fig. 16 — A combination phone and cw audio filter.

ensure stability.

LC Active Filters

One of the big advantages of active filters is that you can build high-Q filters without coils. On the other hand, if you *like* coils, you can still use them in active filter designs. In fact, this will sometimes result in a more stable and reliable circuit. Fig. 14 is an example. This band-pass filter circuit increases the effective Q of the coil by means of positive feedback through R5. You can set the Q by adjusting R3. In this circuit, changing the bandwidth does not alter the gain. When properly adjusted, this filter is more stable and easier to use than some RC circuits, especially at high frequencies.

For example, you can build a practical 50-kHz tuned amplifier (Fig. 15) that is less critical to construct than one based on an RC design. My 10-mH coil had a measured Q of only 37 at 50 kHz, but it was easy to obtain bandwidths less than 370 Hz, indicating an effective Q of over 130. To align this filter, disconnect the input and adjust the 5-kΩ potentiometer until the circuit is on the verge of oscillation with the variable capacitor adjusted for the desired center frequency. With the input reconnected, the filter should be unconditionally stable.



Fig. 17 — Frequency response of the phone/cw audio filter. In the phone mode, the frequency response is 250 to 3100 Hz with a measured gain of 0.85. On cw, the gain is about eight, with a 6-dB bandwidth of 300 Hz centered at 920 Hz.

Cascading Active Filters

Cascading passive filters can create problems, in that connecting the output of one filter to the input of another causes the impedances to interact, affecting the frequency response in ways you might not expect. Cascading active filters, however, is easy because the high-impedance input of each op amp doesn't affect the low-impedance output of the preceding stage. The total frequency response is the product of the responses of the individual filters — that is, the total attenuation (in dB) at any frequency is the sum of the attenuations of the individual stages. Cascading filters greatly improves the stop-band attenuation. For example, if one filter has 20-dB attenuation at some frequency, two such filters in cascade will have 40 dB, three filters will have 60 dB, and so on.

Let's Build One

Enough theory; let's build one! Fig. 16 shows a useful circuit consisting of a pair of cascaded filters of the type described in Fig. 10. With the switch in the "phone" position, each section is a 2300-Hz low-pass filter with a Q of about one. R1 and C1 were added to further reduce the high-frequency response. Switching to cw adds extra capacitance, which not only lowers the resonant frequency to about 800 Hz, but also raises the Q to about 3.5. The two 0.02-μF coupling capacitors roll off the frequency response below 300 Hz, which helps to block any hum present on the input. The frequency responses for both modes are plotted in Fig. 17.

The filter may be driven by any audio source having less than about 2-kΩ output impedance and a voltage swing less than about 8 volts pk-pk on phone and 1 volt pk-pk on cw. (The gain is about one on phone and about eight on cw.) The output is sufficient to drive headphones of any impedance, but you should add an amplifier to drive a speaker.[3]

By the way, it's not necessary to use two separate integrated circuits to build this filter. You can buy ICs with two or even four op amps to the package. For example, the Motorola MC1747 and MC4741 are the dual and quad versions of their MC1741 operational amplifier.

I hope this article has given you some idea of what can be done with active filters. In fact, there isn't much gear in the average ham shack where one of these little gizmos *wouldn't* come in handy. Drop one into your next construction project and see!

Notes

[1] Woodward, "A Beginner's Look at Op-Amps," *QST*, April 1980, p. 15 and June 1980, p. 25.

[2] Nicosia, "Adjustable Audio Filter for Cw," *Ham Radio*, August 1970.

[3] Shriner, "A Handy Audio Amplifier," Hints and Kinks, *QST*, December 1979, p. 56.

References

[1] Budak, *Passive and Active Network Analysis and Synthesis*, Houghton Mifflin, 1974.

[2] Lam, *Analog and Digital Filters*, Prentice-Hall, 1979.

From* 1990 ARRL Handbook *Ch 28, p 1:

A Simple, High-Performance CW Filter

By Ed Wetherhold, W3NQN
1426 Catlyn Pl
Annapolis, MD 21407

This inductor-capacitor CW filter uses one stack of the familiar 88-mH inductors and two 44-mH inductors in a five-resonator circuit that gives high performance at low cost. The center frequency is fixed at 750 Hz because most transceivers use this sidetone frequency, but sidetones between 700 and 800 Hz can be received with less than 1 dB attenuation relative to the center frequency. Ed Wetherhold, W3NQN, designed and built the filter presented here. The author can provide parts for this project at nominal cost. Write E. E. Wetherhold, W3NQN, 1426 Catlyn Place, Annapolis, MD 21401 for more information. If you need a design for a different center frequency, the author can provide that as well. Be sure to include a self-addressed, stamped 9½- × 4-inch envelope with your request.

One feature of this filter is a 3-dB bandwidth of 236 Hz. This bandwidth is narrow enough to give good selectivity, and yet broad enough for easy tuning with no ringing. Five high-Q resonator circuits provide good skirt selectivity that is equal to or better than most commercial active filters costing more than $80. In comparison, this CW filter can be built for less than $15. Simple construction, low cost and good performance make this filter an ideal first project for anyone interested in putting together a useful station accessory.

Design

Fig 1 shows the filter schematic diagram and component values. These values were selected for a center frequency of 750 Hz and for a filter impedance level of 230 ohms. The filter sees a 230-ohm source impedance consisting of the 200-ohm source (transformed from 8 ohms), a 22-ohm transformer winding resistance and an 8-ohm inductor resistance. In a similar way, the filter sees a load impedance of 230 ohms. This design was selected so that only one turn needs to be removed from both windings of a standard 44-mH inductor to give the required L2 and L4 values.

Construction

Fig 2 is a pictorial diagram showing the filter wiring. Note the 44-mH lead connection, as well as the connections between the capacitor leads, the 88-mH stack terminals and the 44-mH inductor leads. Fig 3 shows the finished filter installed in an aluminum box. Before beginning construction, obtain one 88-mH five-inductor stack with a mounting clip and two 44-mH inductors, and then follow steps 1 to 5.

1) Remove one turn from each of the two windings of one 44-mH inductor to get 43.5 mH (total turns removed is two). Carefully scrape off the film insulation and connect the start lead (with sleeve) of one



Fig 1—Schematic diagram of 750-Hz CW filter. Use 1% tolerance capacitors for best results.

C1, C5—0.512 µF capacitor.
C2, C4—1.036 µF capacitor.
C3—170.7 nF capacitor.
J1—Phone jack, or jack to match your headphones.
L1, L5—88-mH toroid (part of toroid stack, see text).
L2, L4—43.5 mH toroid (modified 44-mH toroid, see text).
L3—264-mH toroid (part of toroid stack, see text).
P1—Phone plug, or plug to match your receiver.
R1—Zero to 220-ohm, ½-W, 10% resistor (see text).
S1—DPDT switch.
T1, T2—8-ohm to 200-ohm impedance-matching transformer, 0.4-W.



Fig 2—Pictorial diagram showing L2 and L4 lead connection and wiring of inductor stack (L1, L3, L5).



Fig 3—The assembled filter is shown installed in a CR-800 aluminum box. The thru/bypass switch (S1) and input/output transformers (T1, T2) are at the left end of the box.

Table 1

Node-to-Node Resistances for the CW Audio Filter

Nodes *From*	*To*	*Components*	*Resistance (ohms)*
1	GND	T1 hi-Z winding	12
2	GND	L1 and ½ L2	10
3	GND	L2	4
4	GND	½ L2	2
5	GND	L3 and ½ L4	26
6	GND	½ L4	2
7	GND	L4	4
8	GND	L5 and ½ L4	10
9	GND	T2 hi-Z winding	12
2	4	L1	8
5	6	L3	24
6	8	L5	8
2	3	L1 and ½ L2	10
8	7	L5 and ½ L4	10

Notes

1) See Figs 1 and 2 for the filter node locations.

2) Check your wiring using the resistance values in Table 1. If there is a significant difference between your measured values and the table values, you have a wiring error that must be corrected.

3) For accurate measurements, use a digital VOM or an analog VOM (such as a Triplett Model 630) that has a scale center of about 5 ohms on the ×1 ohmmeter range.

winding to the finish lead (no sleeve) of the adjacent winding to make the center tap as shown in Fig 2. Do the same for the second 44-mH inductor.

2) Fasten both of the 43.5-mH inductors to opposite ends of the 88-mH stack using clear silicone-rubber sealant, available from most hardware stores.

3) Position the 43.5-mH inductors so their leads can be easily connected to the rest of the circuit. Solder the capacitor leads to the stack terminals as shown in Fig 2.

4) Obtain a suitable box and make holes for the inductor mounting clip, the DPDT switch, and the phone jack and phone cord. First, install matching transformers T1 and T2 and the inductor stack with capacitors. Fasten the transformers (with leads pointing up) to the bottom of the box with silicone rubber sealant. Secure the stack to the bottom of the box with a 1-3/8-inch component mounting clip and two no. 6-32 × 5/16-inch screws. Instead of the 8 × 3 × 2¾-inch aluminum box shown in Fig 3 (Mouser Stock No. 537-CR-800), a small cardboard box may be used to minimize cost.

5) Complete the wiring of the transformers, the DPDT switch with resistor R1, and the phone jack and phone plug. Then check the correctness of your wiring by measuring and comparing the filter node-to-node resistances with the values listed in Table 1.

Installation

T1 and T2 match the filter to the receiver low-impedance audio output and to an 8-ohm headset or speaker. If your headset is high impedance, T2 may be omitted. In this case, connect a 10%, ½ W resistor from node 9 (C5 output lead) to ground. Choose the resistor value so the parallel combination of the headset and resistor gives the correct filter termination impedance (within 10 percent of 230 ohms).

Performance

The measured 30-dB and 3-dB bandwidths are about 511 and 235 Hz, respectively, and the 30-dB/3-dB shape factor is 2.17. This factor can be used to compare the performance of this filter with others. The measured insertion loss at 750 Hz is less than 3 dB and is typical of passive filters of this type. This small loss is compensated by slightly increasing the receiver audio gain. R1 helps to maintain a constant audio level when the filter is switched out of the circuit. The correct value of R1 for your audio system should be determined by experiment. Start with a short circuit for R1 and then gradually increase the resistance until the audio level appears to be the same with the filter in or out of the circuit.

More than 700 hams have constructed this five-resonator filter (using either the 2-stack or the newer 1-stack arrangement) and many have commented on its excellent performance and lack of hiss and ringing.

References

Wetherhold, "Modern Design of a CW Filter using 88- and 44-mH Surplus Inductors," *QST*, Dec. 1980 and Feedback, *QST*, Jan. 1981, p. 43.

Wetherhold, "High Performance CW Filter," *Ham Radio*, Apr 1981.

Radio Handbook, 23rd edition, W. Orr, ed., Howard W. Sams & Co, 1987 (1-Stack CW Filter), p. 13-4.

From* 1990 ARRL Handbook *Ch 28, p 3:

A Passive Audio Filter for SSB

By Ed Wetherhold, W3NQN
1426 Catlyn Pl
Annapolis, MD 21407

While audio filters are most often used during CW reception, the SSB operator can also benefit from their use. Shown in Figs 4 and 5 is a passive band-pass filter designed by Ed Wetherhold, W3NQN, for phone operation. This filter was described in Dec. 1979 *QST*.

All of the inductors are the surplus 88-mH toroidal type with their windings wired either in series or parallel to get the required 88 or 22 mH of inductance. The series connection is shown in Fig 2. The 0.319-µF capacitors were selected from several 0.33-µF capacitors that were about 3 percent on the low side. The 0.638-µF value was obtained with a single 0.68-µF capacitor that was about 6 percent on the low side. The 1.276-µF values were obtained by paralleling selected 1-µF and 0.33-µF capacitors.

Fig 5 shows the measured and calculated attenuation responses of the filter. The difference between the measured and calculated responses at the low frequency side of the passband is probably caused by the much lower Q of the inductors at these frequencies.

The necessary termination resistance of this filter is 206 ohms. While this is not a standard value, it should not be too difficult for most amateurs to accommodate. If low-impedance headphones are used, a matching transformer can be used to provide the correct termination. A suitable transformer is available from Mouser Electronics (see Chapter 35 parts-suppliers list). The part number is 42TU200, and it is a 200-ohm CT to 8-ohm CT unit.


INPUT
R_T = 206 Ω
22
L2
1.276
C2
1.276
C4
22
L4
OUTPUT
R_T = 206 Ω
C1
0.319
L1
88
L3
44
C3
0.638
C5
0.319
L5
88
CAPACITANCE IN µF, INDUCTANCE IN mH
(A)
TERMINAL BOARD OF INDUCTOR STACK
1276
1276
OUTPUT
SIXTH INDUCTOR MOUNTED ON END OF INDUCTOR STACK
88
22
22
22
22
88
1
2
3
4
5
6
INPUT
319
638
319
(B)

Fig 4—Schematic diagram of the SSB band-pass filter (A). Shown in B is a pictorial wiring diagram of the terminal board on the inductor stack.



Fig 5—Response curves of the SSB band-pass filter.

From July 1987 QST, p 24:

Designing and Building Simple Crystal Filters

A simple and inexpensive crystal filter that performs well makes receiver and transmitter projects much more fun. Build one yourself at a fraction of the cost of a commercial unit.

By Wes Hayward, W7ZOI
7700 SW Danielle Ave
Beaverton, OR 97005

I am encouraged by the large number of radio amateurs who want to build their own rigs. The ready availability of good-quality semiconductors helps in this pursuit. Other components are sometimes harder to find, at least at an affordable price. One example is the crystal filter—the heart of any superheterodyne receiver or transmitter.

Inexpensive crystals are readily available. They should be characterized and matched for frequency prior to use in a typical crystal filter. Methods for building the needed test equipment and performing the measurements have been presented before.[1] These methods are, unfortunately, somewhat complicated for the casual experimenter who may hesitate to construct special test equipment when just one filter is to be built. What experimenters really need is an empirical filter design method, one that lends itself to casual "tweaking." Such a method is described in this article.

The Cohn Filter

In the course of computer studies of both crystal and LC filters, I've noted that a circuit called the "Cohn," or "Min-loss" filter, lends itself to particularly simple designs.[2] This filter configuration derives its name from its originator, and differs from the more familiar Butterworth and Chebyshev circuits. The Butterworth bandpass filter is built for optimum flatness at the filter center. The Chebyshev design allows equal passband ripples, and is designed for the best stopband attenuation (steepest skirt response). The Cohn filter is a compromise: It is optimized to exhibit minimum insertion loss when built with practical resonators, while preserving a good shape factor. The Cohn filter, in LC form, is not new to the radio amateur.[3,4] It is not limited to LC resonators, however. It works great with crystals!

The Cohn filter, crystal or otherwise, is a rather simple circuit. This becomes more apparent when we view the filter using coupled-resonator methods.[5] All normalized coupling coefficients are equal. Moreover, the normalized end-section loaded-Q factor is the reciprocal of the coupling coefficient. The practical simplification becomes apparent if we examine the generalized crystal filter circuit shown in Fig 1. All capacitors in the circuit are of equal value! The shunt capacitors are coupling elements while the series capacitors in the filter end sections are included to properly tune the circuit.

Practical Cohn Crystal Filters

An empirical method that the amateur may use for crystal filter design is described easily in a step-by-step procedure.

1) Obtain a collection of substantially identical crystals. The crystals are first matched in frequency. The same oscillator should be used to measure all crystal frequencies. The error (frequency difference) should be less than 10% of the *desired bandwidth* of the filter. For example, a filter with a 1-kHz bandwidth should use crystals matched to within 100 Hz or better.

2) Pick a capacitance value to be used in the filter. The capacitance (C) value determines the filter bandwidth. Larger C values yield narrower bandwidth and higher insertion loss.

3) Vary the end terminations to obtain a shape that is free of passband ripple while


RTERM
C
Y1
Y2
Y3
Yn
C
C
C
C
C
RTERM
NOTE: ALL CAPACITORS ARE OF EQUAL VALUE,
ALL CRYSTALS HAVE THE SAME
RESONANT FREQUENCY

Fig 1—Generalized crystal filter suitable for empirical construction.



Fig 2—A simple CW filter using three crystals.

[1] Notes appear at end of article.

providing sufficient stopband attenuation.

This empiric procedure is illustrated in the following examples. I've cheated a bit—I used a personal computer to simulate the filter, and generate the data presented, but I've obtained similar results with filters I have built. The experimental results agree well with the computer models. All examples shown are based on a collection of crystals from my junk box. They are inexpensive 3.579-MHz TV color-burst crystals. The average motional inductance for these crystals is 117 mH, with a (rather poor) typical Q of 50,000. The parallel capacitance is about 4 pF.

A Three-Crystal Cohn Filter

A simple and practical filter for a beginner's first CW superheterodyne receiver is shown in Fig 2. Three crystals are used. The capacitors are 200-pF units, a standard value. Experimentation (done here with the computer) shows that a good filter shape is obtained with an end termination of 150 ohms. Fig 3 shows the frequency response of this filter. The −3 dB bandwidth is 403 Hz, and the insertion loss is 3.8 dB. The loss will be lower with better (higher Q) crystals. The impedance match is shown in the figure as a series of dots. This is the return loss normalized to the source impedance—150 ohms for the filter shown.

If different crystals are used, the same bandwidth can still be obtained, within limits. The coupling capacitors and end terminations will then be different, however. Insertion loss will also differ.

Decreasing the value of the capacitors increases the bandwidth. Some practical values are shown in Table 1, again the result of tweaking with the computer. This will provide some guidance in experimentation.

Fig 4 illustrates the effect of altering the terminating resistance. Fig 4A shows the result of 75-ohm terminations, lower than the desired 150-ohm value. The filter shows some passband ripple and a higher insertion loss. The effect of a 300-ohm termination is shown in Fig 4B, where the peak shape becomes more rounded, with degradation of skirt response. While the poorer frequency domain shape is generally less desirable, the filter with the higher termination has a significantly improved group delay; this filter would be preferred for high-speed data applications.

A Six-Crystal Cohn Filter

The three-pole filter mentioned above is practical. It does not, however, offer skirts that are as steep as we would like for many demanding applications. Improved skirt selectivity in a filter is obtained by using more crystals. The computer can be used to generate another table like that shown for the three-crystal filter. Alternatively, the results of Table 1 can be used as a starting point for experimentation. The



Fig 3—Frequency response of the filter of Fig 2. The dots show the input return loss, indicating the quality of the impedance match.



Fig 4—Frequency response of the filter of Fig 2 with changes in the end terminations. Curve A shows response with 150-ohm terminations; curve B shows the response using 300-ohm resistors. See the text for considerations of which is "better."

ARRL Lab Experiments with the Cohn Filter

ARRL Lab staff members were intrigued by the material on Cohn filters presented by Wes Hayward, W7ZOI. We built four CW filters and one SSB filter, following Wes's instructions. Tests confirmed the computer models developed by Wes. This was no surprise!

CW Filters

Four different batches of crystals were used for the CW filters. The crystal sources were identifiable, and the relative quality of each batch was determined. Four filters were constructed (Fig A). With the exception of the crystals used in each filter, the filters were identical. The filter schematic is shown in Fig B. The capacitors are 300-pF, 5%- tolerance silver-mica types. The 500-ohm terminations (variable resistors) at the ends of the filter were used to "trim" the filter for the best shape and response characteristics during testing. An HP-8540 spectrum analyzer was used to generate the filter response curves shown in photos C through G.

The units used in filter no. 1 are TV color-burst crystals (3.579545 MHz). They were purchased originally from Radio Shack (about $1.60 each) for another project. There were only five of these crystals in the batch, so frequency matching (within 50 Hz) was not as close as with some of the other crystal batches.

The crystals used in filter no. 2 were selected from an assortment of ten 4.000-MHz microprocessor units purchased from JAN Crystals.[1] These crystals were frequency matched within 40 Hz. The crystals cost approximately $3 each.

Filter no. 3 uses crystals selected on the basis of frequency matching from a large batch (over 30) of 4.000-MHz microprocessor crystals on hand in the ARRL Lab (matched within 30 Hz). These crystals can be characterized as "grab bag" quality, and similar units are available from various dealers at a cost of less than $1 each.

We bought the crystals used in filter no. 4 from International Crystal Co.[2] They can be characterized as high-quality, moderate-cost units. Their guaranteed frequency tolerance is 0.001% of 4.000000 MHz, matching was within 6 Hz, and cost is approximately $10 each.



Fig A—Four CW crystal filters were built in this configuration. The PC-board mounting surfaces provide a ground plane. Capacitors are soldered directly to the ground plane, and the crystals are connected using the capacitors as standoffs. Phono jacks are used for input and output connectors. The only variables in the construction of the filters are the crystal characteristics and the length of the crystal leads. The SSB filter is not shown.

SSB Filter

A four-crystal, 12-MHz SSB filter was built using 160-pF, 10%-tolerance silver-mica capacitors. An 8:5 transformer is used for impedance matching. The crystals are microprocessor types purchased from Jameco Electronics[3] at a cost of approximately $1 each. Of 12 crystals purchased, only 10 were suitable for filter use. The filter response is shown in photo G.

Test Results

Photos C through F show the response curves of the four CW filters. Photo G shows the response curve for the 12-MHz SSB filter. Insertion loss is quantified only for CW filter no. 4 because series resistors were used to adjust the terminating impedance of filter nos. 1 through 3. These resistors introduce losses. In practice, each filter would be coupled to its associated circuitry through matching transformers, not resistors.

Filter no. 1 exhibits an extremely sharp response, with a bandwidth of approximately 240 Hz at the −3 dB points; it may be too sharp for good CW copy. Changing the 300-pF capacitors in this filter to a lower value will broaden the response.

Filter no. 2 is not quite as sharp as filter no. 1, and exhibits a peak ripple effect. The response asymmetry can be corrected by trimming the filter


C
Y1
Y2
Y3
Y4
C
C
C
C
R
R
NOTE: Y1-Y4 SAME FREQUENCY
R = 500 Ω
TERMINATION RESISTANCE (Ω) = R + 50
C = 300-pF SILVER MICA, 5 %

Fig B—Schematic diagram of the crystal filters. Capacitors are all of equal value. Terminating resistors are variable 500-ohm units. Crystals are all of equal nominal frequency with minor (up to 50-Hz) variation.

---

[1] JAN Crystals, 2400 Crystal Dr, PO Box 06017, Fort Myers, FL 33906-6017, tel 813-936-2397.

[2] International Crystal Manufacturing Co, Inc, PO Box 26330, 701 W Sheridan, Oklahoma City, OK 73126-0330, tel 405-236-3741.

[3] Jameco Electronics, 1355 Shoreway Rd, Belmont, CA 94002, tel 415-592-8097.

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.



Fig C—Spectral photo showing the response of filter no. 1. Horizontal divisions are each 200 Hz; vertical divisions are each 10 dB. Sampling bandwidth is 100 Hz. The center frequency is 3.579 MHz.



Fig D—Spectral photo showing the response of filter no. 2. Horizontal divisions are each 200 Hz; vertical divisions are each 10 dB. Sampling bandwidth is 100 Hz. The center frequency is 4.000 MHz.



Fig E—Spectral photo showing the response of filter no. 3. Horizontal divisions are each 200 Hz; vertical divisions are each 10 dB. Sampling bandwidth is 100 Hz. The center frequency is 4.000 MHz.



Fig F—Spectral photo showing the response of filter no. 4. Horizontal divisions are each 200 Hz; vertical divisions are each 10 dB. Sampling bandwidth is 100 Hz. The center frequency is 4.000 MHz.

with the termination resistors, but insertion loss increases significantly. For CW use, however, this filter is probably more than adequate.

Filter no. 3 shows a bandwidth of approximately 350 Hz at the −3 dB points. It is symmetric and shows low ripple. This is a very good CW filter.

Filter no. 4 is a good example of what can be accomplished with high-quality crystals and proper terminations. This filter is used in a CW receiver designed by Dave Newkirk, AK7M (see cover of this issue). The input and output impedances of this filter are 200 ohms. To match the 50-ohm impedance of the test setup 4:1 transformers were used. Filter insertion loss is 2 dB, with an ultimate rejection of over 90 dB.

The SSB filter shows a −3 dB bandwidth of approximately 2.1 kHz. There is no discernible ripple, and the insertion loss is 4.4 dB.

Conclusions

The empiric approach to designing Cohn filters for CW or SSB use is a viable alternative to purchasing commercial filters. The relatively high component cost for the best filter design tested (CW filter no. 4) still results in an advantage of over 50% when compared to the price of commercial equivalents. All of the filters tested are adequate for most home-brew projects. They are fun to build, and result in appreciable savings.—*Bruce O. Williams, WA6IVC, ARRL Staff*



Fig G—Spectral photo showing the response of the SSB filter. Horizontal divisions are each 1 kHz; vertical divisions are each 10 dB. Sampling bandwidth is 100 Hz. The center frequency is 12.000 MHz.

Table 1
Cohn Three-Crystal Filter

Bandwidth (Hz @ −3 dB)	*C (pF) (k = 1000)*	*R_{end} (Ohms)*
380	200	150
600	130	238
1.0k	70	431
1.8k	30	1.5k
2.5k	17	3.3k

computer was used in the "construction" of a filter with six crystals. The circuit, again a narrow CW filter, is shown in Fig 5. The 200-pF capacitors used in the earlier filter are retained. The frequency response of this six-crystal filter is shown in Fig 6, where the "reference sweep" is the response of the previous three-element filter. The new filter has a −3 dB bandwidth of 354 Hz, but much steeper skirts than the three-element filter.

A Simple SSB Filter

Table 1 shows a number of simple three-pole filter configurations. Bandwidth is increased for a given set of crystals merely by decreasing the capacitance value. The frequency domain response for a three-pole SSB filter with 30-pF capacitors is shown in Fig 7. The "reference sweep" is the response of the earlier three-pole CW filter with 200-pF capacitors. The skirt response of the SSB three-crystal filter is certainly less than spectacular. More crystals will improve this response significantly. This simple three-pole filter is still practical for some applications, however, such as a portable VHF SSB transceiver.

Experimental Methods

The computer-based "experiments" have proved to be useful. There are generally no surprises. I've "built" filters on the computer using more than a dozen crystals. Some of the more practical designs have been transferred to hardware for receiver applications. Many of these designs operate at different frequencies, some using 4.433-MHz European TV color-burst crystals. These crystals are harder to obtain, but their frequency is more compatible with the existing HF ham bands, avoiding the spurious responses that can sometimes occur with a 3.579-MHz IF.

Almost all of my test equipment is built for an input and/or output impedance of 50 ohms. The test equipment is still easily used for filter experiments. Extra resistance is merely added at the filter input and output to bring the level up to that desired. This is illustrated in Fig 8. Ferrite transformers may also be built to transform impedance levels, but they cannot be changed as quickly as resistors.

It is often convenient to experiment with a filter that is contained within a receiver or transmitter. An example is shown in the



Fig 5—Circuit of a Cohn filter using six crystals.



Fig 6—Frequency response of the six-crystal filter. The reference sweep is the response of the three-crystal filter of Fig 2.



Fig 7—Frequency response of a simple three-pole SSB filter. The circuit is that of Fig 2 with all capacitors changed to 30 pF and terminations of 1500 ohms.



← Fig 8—External resistors may be added to an experimental filter to allow use of 50-ohm instrumentation for circuit evaluation.

partial schematic of Fig 9A. Q1 is a dual-gate MOSFET mixer. The drain resistor determines the input loading impedance for the filter. An identical resistor terminates the filter output. An NPN amplifier, Q2, buffers the output—insurance that the following stages will not alter the crystal filter termination. Fig 9B is a modified form of the same filter. Tuned circuits have been inserted to present higher impedances to the transistors, affording more gain. The output amplifier is changed to a JFET. This modified circuit is better suited to higher impedance filters, as might be encountered with an SSB transmitter or receiver. Once the circuit containing the filter is built, filter response may be measured by tuning the receiver through a steady carrier while observing the output of a later stage with an oscilloscope or RF voltmeter.

It's often difficult to build a filter while also building a receiver. If problems occur, it is hard to tell if they are related to the filter or to the rest of the circuitry. Uncertainty is removed if receiver construction begins with a simpler, single-crystal filter. This allows you to get the receiver working before pursuing the better filter. I don't encourage you to retain the single-crystal filter as a final option. The enhanced performance afforded by additional crystals is more than ample justification for the minimal added effort and expense.

Other Crystals

The examples presented have used readily available color-burst crystals. There is nothing special about them. Indeed, they often represent the poorest possible quality for a crystal, and their frequency (3.579 MHz) can cause compatibility problems in many of the ham bands. They are, however, both available and cheap.

Many parts distributors list crystals for microprocessor applications in their catalogs. The only experience I have had with these crystals was with two 4-MHz crystals.[6] The average Q was 150,000, motional inductance was 148 mH and the two crystals differed in frequency by 105 Hz. Further data on other crystal types would be of great use to the amateur community. Anyone out there with data to share? [See the sidebar to this article. Ed.]

Traditional intuition might suggest that narrow-bandwidth filters are more difficult to design and build than those with wider bandwidth. Just the opposite is true; CW filters are easier to build than SSB or AM filters. This is fortunate, for it seems that much of the present home-brew activity is aimed at CW rigs.

Narrow-bandwidth CW filters are easily built with the lower frequency crystals, such

Fig 9—Partial schematics of receivers showing how terminations may be altered to achieve the proper filter shapes.



as those at 3.579 MHz. While an SSB filter can be built at 3.579 MHz, probably higher terminating impedances will be required. The termination value drops with increasing frequency, making wider bandwidth filters more easily realized at higher frequencies. I often build equipment with a 10-MHz IF because crystals with excellent Q are readily available for this frequency. Typical parameters for these crystals are: motional inductance = 20 mH, parallel C = 3 pF and Q = 200,000. These characteristics result in practical CW filters with terminating impedances as low as 50 ohms, and SSB filters with 200- to 500-ohm loads.

You can, of course, order high-quality crystals for any desired frequency. It is then possible to fit a new filter into an existing piece of equipment. Unfortunately, this may not be practical—the cost for a set of crystals can be high when the crystal characteristics must be well specified and closely matched.

Before you attempt any custom filter design and construction, spend some time experimenting with the more readily available, and certainly less expensive crystals I have used. I'm sure you'll enjoy the experience.

Notes

[1] W. Hayward, "A Unified Approach to the Design of Crystal Ladder Filters," *QST*, May 1982, pp 21-27.

[2] S. Cohn, "Dissipation Loss in Multiple Coupled Resonators," *Proceedings* IRE, Aug 1959.

[3] W. Sabin, "The Solid-State Receiver," *QST*, Jul 1970, p 35.

[4] D. DeMaw, "His Eminence—The Receiver," *QST*, Jun and Jul 1976.

[5] A. I. Zverev, *Handbook of Filter Synthesis* (New York: John Wiley and Sons, 1967).

[6] Mouser Electronics, 11511 Woodside Ave, Lakeside, CA 92040, part no. ME332-1040.

From April 1986 QST, p 13:

SuperSCAF and Son— A Pair of Switched-Capacitor Audio Filters

Been looking for an audio filter that's a great performer and is easy to build? Here are two that fill the bill nicely!



(photograph courtesy Gould AMI Semiconductors, copyright 1985)

By Rich Arndt, WB4TLM and Joe Fikes, KB4KVE
179 Wildwood Dr
Sanford, FL 32771
6817 Criner Rd
Huntsville, AL 35802

Nothing is more frustrating than trying to copy a weak signal in heavy QRM except, perhaps, losing it altogether. A good audio filter can be tremendously helpful in separating the weak signals from the strong ones. The two switched-capacitor filters (SCFs) presented here reflect the needs of different users. SuperSCAF is a self-contained audio filter with thumbwheel frequency selection at 100-Hz intervals, a built-in audio power amplifier and an ac-operated power supply. JuniorSCAF is much smaller and simpler. Junior is designed to be added internally to a receiver and use the receiver's audio amplifier and power supply. Both filters feature high performance and simple construction. Experienced builders can assemble either one in a weekend.

The heart of these audio filters is a pair of ICs recently introduced by AMI, the S3528 and S3529. These two ICs can be used together to form an SCF band-pass filter with excellent characteristics. The low-pass and high-pass cutoff frequencies, f_{cl} and f_{ch}, are selected by digital inputs to the ICs at increments of approximately 100 Hz throughout the audio band.

The theory of operation of switched-capacitor filters has been well presented in past issues of *QST* and other amateur and professional electronic journals.[1-4] We will discuss SCF theory only briefly here. Primarily, we will examine the significant features of the S3528 and S3529 and will discuss the construction and use of an audio filter incorporating these devices.

Switched-Capacitor Filters

Whenever an electrical signal is modified in some way (except for pure amplification or attenuation), we say that we have "processed" the signal. Signal processing may be accomplished by continuous or discrete processes. We refer to the continuous process as "analog signal processing" and to the discrete process as "digital signal processing." Examples of analog signal-processing circuits are mixers, detectors, and frequency-selective circuits made from inductors and capacitors. Active filters using op amps, resistors and capacitors also fall into the analog category.

Digital signal processing, on the other hand, relies on a series of "snapshots" or samples of the signal in order to perform a given function. These individual samples are combined and manipulated in a way that yields some desired result. Digital signal processing is used in computerized speech, TV image enhancement and radar. An important part of digital signal processing is digital filtering, which is functionally equivalent to analog filtering. One of several practical digital-filter implementations is the SCF.

The SCF works by storing discrete samples of an analog signal as a charge on a capacitor. This charge is transferred from one capacitor to another down a chain of capacitors forming the filter. The sampling and transfer operations take place at regular intervals under control of a precise frequency source or clock. Filtering is achieved by combining the charges on the different capacitors in specific ratios and by feeding charges back to the prior stages of the capacitor chain. In this way, filters of much higher performance (and complexity) may be synthesized than is practical with analog filters.

The AMI S3528 and S3529

AMI has produced a number of ICs for the telecommunications industry that contain complete SCFs. Two of these circuits, the S3528 and S3529, are of particular interest to the amateur community because of their flexibility and performance. Within the S3528, we find a seventh-order elliptical low-pass filter, a clock generator, a program-

---

[1] Notes appear at end of article.

mable-clock frequency divider and a pair of buffer amplifiers that are helpful in getting the signal into and out of the IC. The S3529 is similar to the S3528 except that it contains a high-pass filter instead of a low-pass filter. Attenuation is designed to be greater than 51 dB at frequencies above 1.3 f_{cl} for the low-pass filter or below $f_{ch}/1.3$ for the high-pass filter, where f_{cl} and f_{ch} are the low- and high-pass filter cutoff frequencies, respectively. (In a band-pass configuration, f_{ch} is less than or equal to f_{cl}.) This frequency response characteristic may be seen in the title photo.

A key feature of the S3528 and S3529 pair is the ability to digitally select f_{cl} and f_{ch}. Any of 64 different cutoff frequencies may be selected by setting a 6-bit control code. This code addresses an on-chip ROM whose output controls the frequency divider. In the S3528, the sampling frequency is obtained by dividing the 3.58-MHz clock to equal 40 f_{cl}. In the S3529, the sampling frequency is 44 f_{ch}.

An especially nice set of cutoff frequencies is available in the voice range below 3900 Hz. With a common 3.58-MHz TV color-burst crystal and binary-coded decimal (BCD) inputs, f_{cl} is about 100 times the BCD code on the S3528, and f_{ch} is about 91 times the BCD code on the S3529. Setting the code of both filters to the same value gives a filter whose upper-frequency cutoff is 100 times the switch setting and whose width is 10% of the pass-band center frequency.

This selection scheme works for all BCD codes between 01 and 39. As you may have observed, there are other digital codes, such as 0B and 2E hexadecimal, which lie outside the BCD code set. What happens if you specify one of these codes? You get more frequencies! Some lie between the 100-Hz intervals; others lie outside the 100- to 3900-Hz range, up to 22 kHz. A complete list of codes and frequencies is given in Table 1. Note that codes 35 and 38 deviate from the 100-Hz pattern.

An interesting bit of insight may be gained into the workings of SCFs by examining the possibility of spurious signals in the filter's output. As it happens, there are a few BCD switch combinations that produce very low-level spurious output signals, or "birdies." A few of these artifacts of the digital-filtering process can be heard, although they are much too weak to interfere with communication.



SuperSCAF is a stand-alone unit that contains a switched-capacitor filter, an audio power amplifier and an ac-operated power supply.

Table 1

S3528 and S3529 Cutoff Frequencies

BCD Code	*High-Pass Cutoff Frequency (f_{ch}) (Hz)*	*Low-Pass Cutoff Frequency (f_{cl}) (Hz)*
00	40	44
01	91	100
02	182	200
03	273	300
04	363	399
05	455	500
06	546	601
07	635	699
08	726	799
09	822	904
10	914	1005
11	1005	1105
12	1099	1209
13	1179	1297
14	1271	1398
15	1355	1491
16	1453	1598
17	1535	1688
18	1627	1790
19	1731	1904
20	1808	1989
21	1892	2081
22	1985	2183
23	2086	2295
24	2198	2418
25	2260	2486
26	2392	2632
27	2465	2711
28	2543	2797
29	2625	2887
30	2712	2983
31	2805	3086
32	2905	3196
33	3013	3314
34	3129	3442
35	5423	5965
36	3254	3579
37	3389	3728
38	5811	6392
39	3537	3891
Additional Hex Codes		
0A	433	476
0B	227	250
0C	904	994
0D	935	1028
0E	957	1053
0F	1043	1147
1A	1334	1467
1B	1402	1542
1C	1565	1721
1D	1768	1945
1E	1849	2034
1F	2034	2237
2A	2136	2350
2B	2325	2557
2C	3697	4067
2D	4067	4474
2E	4519	4971
2F	5085	5593
3A	6779	7457
3B	8135	8949
3C	9039	9943
3D	13559	14915
3E	16270	17897
3F	20338	22372

(courtesy Gould AMI Semiconductors, copyright 1985)

One birdie can be heard when the high-pass switch is set to 00. From Table 1, we see that f_{ch} is 40 Hz. In this case, the S3529 sampling frequency is 1760 Hz. At low-pass switch settings above 16, the tone can be heard. Another can be heard when the high-pass switch is set to 01 and the low-pass switch is set to 39. Here, the sampling frequency of the high-pass filter is 4004 Hz. This is close enough to the low-pass cutoff to get through. Other combinations such as 09/10, 10/11 and 11/12 give rise to weak birdies through the aliasing and quantizing process. An explanation of these signals is beyond the scope of this article.

We were curious about the possibility of the clocks and switched signals causing interference to the station receiver, TVs and so on. Fortunately, we were able to have SuperSCAF tested for emissions at a local facility; it proved to be "clean as a whistle."[1]

Circuit Description

The block diagrams for the two filters are shown in Fig 1. Both Super and Junior use an identical band-pass filter circuit. Junior's passband is set by binary DIP switches on


AUDIO INPUT FROM RECEIVER SPEAKER OR HEADPHONE JACK
S-C AUDIO FILTER
POWER AMPLIFIER
AUDIO OUTPUT TO 4- OR 8-OHM SPEAKER OR HEADPHONE
117-V AC INPUT
AC-TO-DC POWER SUPPLY
SUPERSCAF
(A)
FROM RECEIVER AUDIO PREAMP OUTPUT
S-C AUDIO FILTER
TO HIGH-IMPEDANCE (Z > 1k OHMS) HEADPHONE OR RECEIVER POWER-AMP INPUT
RECEIVER 12-V DC SUPPLY
DC-TO-DC POWER SUPPLY
JUNIOFSCAF
(B)

Fig 1—Block diagrams of SuperSCAF (A) and JuniorSCAF (B).


J1
AUDIO IN FROM RECEIVER
0.47
C10
C9
0.01
R1 47 k
R2 47 k
620 C11
U1
S3529
OSC₀
OSC₁
SIG IN
FB
BUF OUT
BUF IN
FLT OUT
V_DD
V_SS
A_GND
D_GND
Y1
3.58 MHz
R9
10 M
R5
47 k
620
C12
R4
47 k
R3
47 k
R6 47 k
620 C13
U2
S3528
R10 – R15
47 k
R16 – R21
47 k
FILTER SWITCH
OUT
IN
S1
FILTER OUT TO P.A. FIG 3
0.47
C15
620
C14
R8
47 k
R7
47 k
+5 V
−5 V
C5
0.1
C6
0.1
C7
0.1
C8
0.1
S2
0
3
1
5
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000, M = 1000 000
A = ANALOG GROUND
D = DIGITAL GROUND

Fig 2—Schematic diagram of the filter sections for SuperSCAF and JuniorSCAF. This circuit, offering simplicity and ease of construction, is used for both filter units.

J1—Phono jacks.
J3—¼-inch phone jack.
R10-R15, R16-R21—47-kΩ × 7 resistor packs used (one resistor in each pack not connected).
S1—SPDT toggle.
S2—BCD thumbwheel switch (SuperSCAF); C & K 342710640-01904 or equiv. For JuniorSCAF, two 6-position DIP PC-mount switches are used.
U1—AMI S3529 programmable high-pass filter.
U2—AMI S3528 programmable low-pass filter.
Y1—3.58-MHz TV color-burst crystal.

the PC board. SuperSCAF's passband is controlled by thumbwheel switches on the unit's front panel. Super also has its own audio power amplifier and ac-operated power supply. In reading the following circuit descriptions, keep in mind that SuperSCAF is a self-contained unit that accepts low- or high-impedance inputs and delivers 1.5 W of audio output at 8 ohms. Junior, on the other hand, has a high-impedance output circuit. It can drive high-impedance phones directly, but doesn't have the "oomph" to drive a speaker.

Refer to Figs 2-4. The input signal to SuperSCAF is obtained directly from the speaker output or the headphone jack of your receiver. The signal is passed first into the S3529 high-pass filter and then into the S3528 low-pass filter. A pair of switches sets the frequency of each filter. The filters are followed by an audio power amplifier. Switching is provided to bypass the filter if desired.

As with any digital filter, it is necessary to band limit the input signal to prevent aliasing. The combination of receiver IF-stage filters and a bit of high-frequency rolloff in the audio sections of most receivers is sufficient to prevent problems. C11 and R2 are used in conjunction with


+V (UNREG)
C17
0.47
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000, M = 1000 000.
1N4148 D1
1N4148 D2
R26 39
Q1 2N3906
C16 330
R23 47 k
R25 4.7 k
A = ANALOG GROUND
D = DIGITAL GROUND
Q5 TIP29A
+V 1458 (UNREG)
Q2 2N3906
FROM FILTER IN/OUT SWITCH FIG 2
R22 27 k
U3A
D5 1N4148
D6 1N4148
R29 0.56 1W
R30 0.56 1W
C19 0.1
J3 HEADPHONE JACK
R24 12 k
−V (UNREG)
Q3 2N3904
R31 10
Q6 TIP30A
J2 AUDIO OUT TO SPEAKER
R27 4.7 k
Q4 2N3904
1N4148 D3
1N4148 D4
R28 39
U3B
−V (UNREG)
C18 0.47

Fig 3—The SuperSCAF audio-amplifier schematic diagram.

D1-D6, incl—1N4148 silicon diode.
J2—Phono jack.
Q1, Q2—2N3906.
Q3, Q4—2N3904.
Q5—TIP29A.
Q6—TIP30A.
U3—MC1456 dual op amp.


EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS.
DS1
R32 390
POWER INDICATOR
+V (UNREG)
U4
REG IN OUT GND
+5 V
78LC5
POWER SWITCH
F1 1/3 A
S3
T1
SEC 12.5-V AC
PRI 117-VAC
P1
1N4001
D8 1N4001
D9 1N4001
D10 1N4001
C1 1500 μF 25 V
C2 0.1
1500 μF 25 V C3
0.1 C4
U5 79L05
−5 V
−V (UNREG)
A = ANALOG GROUND
D = DIGITAL GROUND

Fig 4—Schematic diagram of the power supply designed for use with the SuperSCAF.

D7-D10, incl—1N4001.
DS1—LED.
S3—SPST toggle
T1—117-V pri; 12.5-V sec, 1A (RS 273-1505 or equiv).
U4—78L05 5-V positive regulator.
U5—79L05 5-V negative regulator.

the input op amp of the S3529 to form a simple analog low-pass filter, just in case. The six frequency-select lines to each IC are pulled to digital ground by 47-kΩ resistors, representing a logic low. The BCD switches then selectively apply +5 V to the lines, depending on the code, to indicate a logic high.

Both ICs share a common 3.58-MHz crystal and 10-MΩ resistor. In addition to economy, this scheme ensures that both filter ICs operate synchronously from the same clock. The output signal of the S3529 is smoothed by the analog low-pass filter made up of R4, C12 and the output buffer. An additional stage of analog filtering is provided by R6, C13 and the input buffer of the S3528.

The low-pass filter functions similarly. Output from the low-pass filter is smoothed by the S3528 output op amp, R8 and C14. The filtered signal is then passed to the power amplifier.

Although monolithic audio amplifier ICs are readily available, a discrete-component power amplifier (Fig 3) was designed for SuperSCAF. (This choice was dictated by the split power supply discussed later.) The power amplifier is basically a voltage amplifier composed of U3 followed by a current amplifier. Q2 and Q3 act as drivers for the output transistors, Q5 and Q6. Q1 and Q4 act as constant-current sources for the driver collector and output transistor base nodes. Short-circuit protection (1A) is provided by the current-limiting action of D5 and D6. The power amplifier will deliver a maximum of 1.5 W to a 4- or 8-ohm load, more than enough for a comfortable listening level. Trying to drive the amplifier beyond 1.5 W output will result in distortion.

A split power supply (Fig 4) is used to simplify the input and output signal-return path and to accommodate the ±5-V supply requirements of the S3528 and S3529. Supply voltages for the S3528 and S3529 are obtained from a pair of low-current complementary regulators. Separate analog and digital grounds are used to prevent digital noise from appearing on the analog ground return. The two ground systems are joined at the power supply.

JuniorSCAF (see Figs 2 and 5) is ideal for QRP work. Since the power amplifier



Fig 5—A dc-to-dc converter for use with JuniorSCAF.
D11-D13, incl—1N4148 silicon diode.
U6—CA3524 regulating pulse width modulator.

EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000, M = 1000 000.



JuniorSCAF is designed to use a host receiver's 12-V dc supply and audio power amplifier.

accounts for most of the operating current, its elimination allows the two complementary 5-V dc power supplies to be derived from a simple dc-to-dc converter operating from a 12-V dc source within the receiver.

Although JuniorSCAF is the simpler of the two filters, to install it in a receiver it is necessary to break the signal path between the receiver's audio preamplifier and power amplifier. The output from the preamp is coupled to Junior's input. Junior's output is connected to the receiver's audio power amplifier input. Also, it's necessary to tap into a well-filtered supply of between +12 to 40-V dc to obtain operating power. Because these details vary widely from receiver to receiver, we can't offer more specific installation instructions. Unless you are comfortable cutting leads and traces inside your equipment (or can find a friend to do it for you), we suggest you build SuperSCAF instead.

Construction

Assembling these filters is straightforward. Although the layout is not critical, it's always best to keep leads as short as possible. If you decide to use perf board instead of the PC board, be aware that the pinout of the S3528 is slightly different from that of the S3529.

An interior view of the SuperSCAF is shown in Fig 6. A metal box is used as an enclosure for the prototype. Metal is preferred to plastic because of its strength and also because it offers a degree of RFI protection. Remember that the filter may be required to work in an area of high RF-signal strength.

The rectangular hole for the BCD switches is cut with a nibbling tool. Drill a pilot hole large enough to accommodate the nibbler in the center of the BCD switch mounting location. Next, the sides of the switch hole are cut by the nibbler. Finally, the edges of the hole are filed until smooth. Although we used several types of BCD switches during the course of the project, the one we like best is made by C & K components (see parts list). This switch is small, but has a smooth feel and clearly legible digit markings. The high- and low-pass switch positions have stops installed that limit the range to between 00 and 39, matching the filter's operating range.

After holes for the other switches, jacks, power cord and LED are drilled, these components are mounted and connected to the circuit board. We like the looks of a small (1/8-inch diam) LED ac-power indicator. A hole for the LED must be drilled for a snug fit. The LED is then held firmly in place by a drop of glue on the back. Color-coded ribbon cable works nicely for attaching the switches and LED to the circuit board.

The circuit board is mounted to the bottom of the case by stand-offs. To dissipate the heat and prevent thermal runaway, the output transistors *must* be mounted to heat sinks. We used the rear of the case as a heat sink (see Fig 6). The output transistors must be insulated from the chassis by mica washers and an insulating screw washer to prevent short-circuiting the supply voltages. Use thermally conducting silicon grease on both sides of the mica washers.

For safety reasons, a 3-wire power cord should be used. Connect the ground conductor (green) to the chassis and connect the neutral conductor (white) directly to the



Fig 6—An interior view of SuperSCAF. Note the mounting of the audio-amplifier output transistors; the rear panel of the enclosure is used as a heat sink. The enclosure used for SuperSCAF is a Radio Shack part (RS 270-272).

primary of the power transformer. Solder the hot (black) wire to the spring contact at the rear of the fuse body. Connect the sleeve terminal of the fuse to the power switch. Be sure that the power connection is wired in this manner. Failure to do so may result in a serious shock hazard.

Performance and Operation

Connect the receiver speaker output to the AUDIO IN jack. Plug the speaker into the AUDIO OUT jack. Use shielded audio cable to reduce the possibility of introducing RFI into the filter.

The SuperSCAF and Junior are a pleasure to use. If you mate them with an older rig and operate CW, you'll be surprised by the sudden quiet in the shack. Under many conditions, noise and QRM simply disappear. We became aware of ac hum in one of our receivers only after SuperSCAF made it go away! The filter even does a respectable job on the woodpecker and "sons of the woodpecker." There is no artificial ringing, only the residual noise within the filter passband.

The effect of the filter on SSB signals is not as dramatic, but certainly noticeable and worthwhile. Simply set the switches to 03/27 and eliminate trash outside that frequency range. When conditions get rough, experiment with a narrower passband. Setting the low side of the passband below 02 is never needed and is an open invitation to aliasing.

The most significant operation difference between SuperSCAF and Junior is the passband switching. If Junior is mounted inside a receiver, it is inconvenient to change the passband during operation. We recommend that Junior be set up for a passband of about 500 Hz for CW and switch settings of 03/24 (300-2400 Hz) for SSB.

An obvious advantage of the thumbwheel switching scheme is direct passband readout. Another is the ability to adjust the upper and lower cutoff points in small steps, hearing the effect as you go. For narrow-band interference such as "tuner-uppers," the interference will often disappear at a particular step. At 24, you hear him, at 23, he's gone. For wideband interference, the effect is not as dramatic.

On CW, RTTY and other narrow-band modes, the filter performance is spectacular (see Fig 7). We both work a lot of CW and have older rigs with SSB crystal filters having passbands that are much too wide for comfortable code reception. With SuperSCAF, we get tremendously improved selectivity.

Your new-found selectivity requires changes in operating habits. If the filter is set so that the passband is narrow, say 07/07 (about 70 Hz wide), the band may seem empty. The problem is that your accustomed tuning rate may be too fast for such a narrow bandwidth. You may tune completely across a station during the time between code elements and never hear the



Fig 7—Spectral plots of the SuperSCAF response made in the ARRL lab. Note the steep filter skirts. For both plots, the center frequency is 1 kHz; vertical divisions are each 10 dB and horizontal divisions are each 200 Hz. At A, the front-panel switches are set to 05/06; at B, 05/09. These settings equate to passband widths of about 200 and 500 Hz, respectively.

signal. The solution is to search the band using a relatively wide passband or with the filter bypassed. When you find a "live one," close the passband around him. We often use a setting of 05/09 for search, and then narrow the passband to 07/07 for the QSO.

Be alert to frequency drift, particularly when you turn things over to the other station. It's very easy for one of you to slip outside a 70-Hz passband. If the other station is not where you expect it, widen the filter passband to re-acquire the signal, then narrow the passband on the new frequency. Also, experiment with disabling the AGC if your receiver allows that. Sometimes a strong signal within the IF passband will grab your AGC and reduce the incoming signal levels to practically nothing. You might not hear the interfering station, but you'll know it's there.

Summary

The possibilities presented by monolithic SCFs are numerous. We have built several variations on the theme presented here, and all have worked well. One unit was powered by a pair of 9-V batteries and used an IC power amplifier instead of the discrete amplifier of Fig 3. Another unit included a tone decoder to supply a digital signal to a computer for receiving Morse code and RTTY. That unit was mounted in the transceiver's companion speaker box.

At the outset, our goal was to design an easily constructed audio filter with excellent performance. We are pleased with the results in every way—we hope you will be, too.

Notes

[1] R. Schellenbach and F. Noble, "Switched-Capacitor Filters—An Emerging Technology for Amateur Radio Use," *QST*, Mar 1984.

[2] R. Olsen, "Digital Signal Processing for the Experimenter," *QST*, Nov 1984.

[3] AMI Telecommunications Design Manual, Gould AMI, 1982 3800 Homestead Rd, Santa Clara, CA 95051.

[4] J. Conner, "Switched-Cap Filters Mate With Microprocessors," *Electronic Products Magazine*, Sep 3, 1984.

[5] We wish to thank Don Fisher, W4PLA, and the NCR Corporation Emission Testing Service, Lake Mary, Florida, for providing the FCC Part 15j Class B test data for the SuperSCAF audio filter.

[6] Gould Semiconductors sells the S3528 and S3529 ICs through a network of distributors. Call Gould at 208-233-4690 for the name of their nearest distributor. New Horizons Electronics Corporation, 6000 New Horizons Blvd, Amityville, NY 11701, 516-226-6000, will sell to individuals (prepaid) with a $25 minimum order. (The chips cost about $7 each at the time of publication.)

Altronics sells kits and completed SuperSCAFs, but not parts. Check the *QST* index of advertisers for their listing, which contains current sales information.—*Ed.*

From July 1986 QST, p 34:

The SWR Twins—QRP and QRO

Part 9: Portable amateur operation often calls for miniature equipment. Here are two tiny SWR indicators—one for QRP and one for high power.

PEAK
REF FWD
SENS
SWR
CAL
OPR
SENS
CAL/SWR
PWR

By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250
Luther, MI 49656

Does the inconvenience of too-large SWR-indicating gear complicate your portable operations? It is not uncommon for us to feel that some of the commercially made SWR bridges and RF-power meters are too big and too costly for occasional use during field day, camping trips, vacations and even DXpeditions. I have seen SWR meters that were larger than an entire QRP station, which presents a rather absurd picture! Because of my need for small accessory equipment, I have built a number of compact Transmatches and SWR meters. The pair we shall consider in this article was built to provide an example of small units that you can build inexpensively for field use. We will also consider some practical ideas for home construction that can be applied to other projects as well. These SWR indicators are not works of art, at least from an aesthetic point of view, but you can easily impart a professional appearance to them if you are skilled in the craft of cabinet and panel design.

Do You Need an SWR Indicator?

SWR meters and RF-power indicators have become a way of life with most of us. But, "way back when," we managed quite well without these sophisticated gadgets. An experienced amateur could tell if the antenna SWR was low by observing the settings of the tune and load controls of the transmitter. That is, the plate tuning and loading controls were at approximately the same settings as when the transmitter was connected to a dummy load of the appropriate impedance, thereby indicating a low SWR. Some of us used RF ammeters in the feed line to indicate maximum RF current, a condition that generally occurred when the feed line was matched to the antenna feed point.

SWR has become a more significant concern today because of the many solid-state transmitters that exist. They must "look" into a low SWR—usually 2:1 or less—in order to develop the rated output power and to protect the final-amplifier transistors from damage. The built-in SWR-protection circuits reduce the transmitter output power as the SWR increases. Therefore, it is helpful to have an SWR indicator between the transmitter and the transmission line. The antenna can then be adjusted by means of its length or matching circuit to obtain a low SWR reading.

SWR indicators are useful also as relative output-power meters. They help us to keep tabs on the antenna system and the transmitter performance. Most SWR instruments can be calibrated to read RF power as well, and we will discuss this principle later in the article.

A QRP SWR/Power Meter

Neither of the instruments in this article is new in concept. The resistive QRP bridge was developed many years ago by the late George Grammer, W1DF. The QRO bridge is a design product of Warren Bruene of Collins Radio. The latter design has become the standard for most amateur SWR and power meters of commercial origin. A number of variations in the basic designs have been introduced, along with some extra convenience features.

Fig 1 shows the circuit for our low-power SWR bridge/RF power meter. R1, R2, R3 and R4 comprise a 50-ohm dummy load. Some of the RF voltage developed across the load is sampled through R5 and supplied to the resistive bridge that consists of R6, R7 and R8. The antenna represents the remaining leg of the bridge. When it reflects a 50-ohm condition, the bridge is balanced and the meter reading falls to zero. D1 rectifies the RF voltage to provide dc for the metering circuit. Additional examples of this general circuit are given in *Solid State Design for the Radio Amateur* (temporarily out of print).

R10 is a panel control that is used to establish the "sensitivity" or meter response versus the power level. R11 is a PC-mounted potentiometer that we can use to calibrate the meter for a full-scale reading of 10 W. Once set, it should need no further adjustment.

Since R1, R2, R3 and R4 have a combined rating of 8 W, we must not permit a sustained RF power amount of more than 4 W to be fed into the instrument, lest the resistors become damaged from excessive heating. Momentary tests with powers up to 10 W will not harm the resistors, provided the key-down period does not exceed 15 seconds. Allow a cool-down period of at least 30 seconds between brief tests with more than 4 W of RF power. Film resistors are used in my model, but 5%, 2-W carbon-composition resistors will work equally well. If you cannot locate them, you may purchase the film resistors by mail.[1]

The power handling capability of this instrument may be increased by using higher-wattage (noninductive!) load resistors or by connecting an external dummy load to replace the built-in one. *Warning:* If you plan to use more than 10 W of RF power, and a larger dummy load, be sure to in-

---

[1] Notes appear at end of article.



Fig 1—Schematic diagram of the QRP SWR bridge. Resistors are carbon-composition types. Capacitors are disc ceramic. Part numbers listed below are Radio Shack designators, except when otherwise noted.

C1, C2—Disc ceramic, RS 272-131.
D1—Small-signal silicon diode, RS 276-1122.
J1, J2—RCA style single-hole-mount phono jack, RS 274-346.
M1—Miniature microammeter, 0-50, 0-100 or 0-200 μA. See note 2.
R1-R4, incl—200-ohm, 2-W noninductive resistor. See note 1.
R5—680-ohm, ½-W resistor, RS 271-021.
R6, R7, R8—51-ohm, ½-W noninductive resistor. Available from All-Electronics Corp, Los Angeles, CA. Radio Shack 47-ohm units (271-009) may be substituted for suitable performance.
R9—1-kΩ, ½-W resistor, RS 271-023.
R10—Panel-mount control, 10-kΩ, linear taper carbon-composition, RS 271-1721. Knob (0.5-inch OD) is RS 274-403.
R11—Trimmer control, PC mount, 10-kΩ RS 271-335.
S1—Two-pole, three-position rotary wafer, RS 275-1386 (three positions not used).
S2—SPDT miniature toggle, RS 275-613.



Fig 2—Meter scale that may be pasted over the original scale of the meter offered in note 3. See text for method of making your own custom scale at ×4.



Fig 3—An interior view of the QRP SWR meter. The PC board is mounted vertically by means of two no. 6 spade bolts. A ¼-inch hole is drilled in the rear panel of the box to provide access to the RF-power calibration control, R11.

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.

crease the value of R5 to prevent excessive RF current from flowing in the bridge circuit. Sample only enough RF energy to provide a full-scale meter indication (R10 set for maximum sensitivity) at about half the power level you anticipate. In other words, if you expect to use 50 W of RF power, select an R5 value that will give a full-scale meter reading at 25 W.

How to Use the QRP Meter

Calibration of this instrument was covered in Aug 1983 *QST*, at which time I described a similar instrument.[2] I will review the operating procedure here, since some of you may not have used this type of bridge for SWR and power measurements.

S1 allows us to bypass the bridge after making SWR or power measurements. The bridge is out of the circuit when S1 is in the OPR position. When we switch to the CAL mode, the bridge has no termination. This enables us to adjust R10 (RF power applied) for a full-scale reading at M1. Next, we move S1 to the SWR position. The meter then indicates the relative reflected power. If the antenna is matched and tuned properly for a 50-ohm condition, the meter will read zero. If not, the antenna system or Transmatch should be adjusted until the meter reads zero. Once this is achieved, set S1 to the OPR mode.

RF-power measurements may be made (after M1 has been calibrated by means of R11) by placing S1 in the CAL position and setting S2 to read PWR. This removes the antenna (J2) from the circuit and permits us to develop RF voltage across R1, R2, R3 and R4. You may feed various power levels from 1 to 10 W into the circuit, then note the meter reading for each power amount. A calibration scale may then be drafted for future reference. The 1-10 numerical scales on the meters of these SWR indicators were drawn by hand at ×4. I used press-on decals for the numbers. I then had the meter scale reduced ×4 at a "quick-print" shop, at a cost of 24 cents each. The new scales were pasted over the original faces of surplus 200-μA S meters.[3] You may use an available meter that has a dc sensitivity of 50 or 100 μA. Fig 2 contains a 0-10 meter scale that you may cut out or photocopy for use on the meters that are available from the source listed in note 3. The cases come off easily, and the meter face can be popped out for modification.

The interior of the QRP bridge is shown in Fig 3. A scale parts-placement guide for the PC board is provided in Fig 4A.

QRO SWR Indicator

This fraternal twin to the QRP bridge will measure SWR and RF power at levels up to 1 kW. The major problem is that the instrument is so tiny and lightweight that the coaxial attachment cables may become the "tail that wagged the dog." This is often a penalty associated with miniature gear. I find that RG-8X 50-ohm cable minimizes the problem: I have experienced frustration when trying to use the heavier, stiffer RG-8 cable.

Fig 5 shows the circuit for the QRO bridge. I used a hybrid diagram in order to clarify the relationship of T1 to the rest of the circuit. T1 is a transformer for sampling RF current in the feed line. The cable that passes through the toroid core serves as a one-turn primary winding for T1. QRP versions of this bridge can be built if we use a two-turn link in place of the straight conductor that passes through the toroid. This will increase the sensitivity.

This bridge (minus the cabinet) is suitable for inclusion in Transmatches. The PC board (Fig 4B) can be installed near the RF-input jack of the Transmatch. The leads that go to S1 are not critical as to length, so S1, R1 and M1 may be panel-mounted in your Transmatch, if desired.

The shield braid of the pass-through coaxial line (T1) is grounded only at one end. This provides a Faraday shield to discourage the flow of harmonic currents into the bridge. C1, C2 and C5 form a capacitive divider for balancing the bridge in a 50-ohm circuit. D1 and D2 provide dc for the metering circuit. Germanium diodes are



R8
TO S1B
C1
R7
R5
R2
R1
D1
TO S1A
TO S2
R9
R8
R4
R3
R11
METER GND
TO C2
TO R10
(A)
TO T1 SEC
BRAID GND
T1 SLOT
CUT OUT
TO J2
TO J1
C2
C1
R3
R2
D2
D1
C4
C3
RFC 1
C5 +
+
TO S1 (REF)
TO C6
TO S1 (FWD)
TO S2 (PEAK)
(B)

Fig 4—Scale parts-placement guide for the QRP meter (A) and the QRO meter (B), as viewed from the component side of the boards.



T1
XMTR (50 Ω)
ANT (50 Ω)
J1
J2
C1 5 BAL
D1
D2
C2 5 BAL
22 1/2 W
22 1/2 W
R2
R3
C3 0.01
RFC 1 1 mH
C5 330 SM
C4 0.01
PEAK
S2
+ C6 10 μF 16 V
FWD
REF
S1
R1 10 k SENS
M1
μA
0-200
SM = SILVER MICA
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000

Fig 5—Hybrid diagram of the QRO SWR bridge. A short length of 50 ohm coaxial cable is passed through the center of toroid T1, as indicated. Fixed-value resistors are ½-W carbon-composition types. Other components are described below. Radio Shack numbers included.

C1, C2—Miniature 1-5 or 1-8 pF air or piston trimmer. See note 4.
C3,C4—Disc ceramic, RS 272-131.
C5—Silver mica or polystyrene, 330 pF. NPO ceramic also suitable. Silver-mica capacitor avail from All-Electronics, no. DMCP-330.
C6—Tantalum or electrolytic, RS 272-1436.
D1, D2—Small-signal germanium diode, RS 276-1123, 1N34A.
J1, J2—Single-hole mount BNC or connector of your choice, RS 278-105.
M1—Miniature microammeter, 0-50, 0-100 or 0-200 μA. See note 2.
R1—Linear-taper, carbon-composition, panel-mount control, 10 kΩ, RS 271-1721.
R2, R3—22-ohm, ½-W carbon composition, RS 271-005.
RFC1—Miniature RF choke, 1 mH. Avail from All-Electronics Corp, no. CC-1000 or from BCD Electro.
S1—Miniature SPDT toggle, RS 275-613.
S2—Miniature SPST toggle, RS 275-612.
T1—60 turns of no. 30 enam wire on an Amidon Assoc T50-2 powdered-iron toroid core. Mount in slot on PC board (see text).

recommended to ensure sufficient dc voltage when small amounts of reflected power are present. Silicon diodes, such as 1N914s, may cease to conduct (0.7 V approx) before the SWR is adjusted for a 1:1 state, thereby causing us to think we have a match when, in fact, we do not. Germanium diodes have a lower barrier voltage (approx 0.4). This isn't a problem with the circuit of Fig 1.

I used RG-8X for the line that passes through T1, mainly because it provides a close fit to the center hole of the toroid core. Or, you may use the smaller RG-58, then affix it in the toroid with silicone cement. The RG-8X has a higher power rating, however.

C6 is included with S2 to provide a leveling effect of the meter reading during SSB operation. It will enable you to get an approximate peak-power reading if you calibrate this instrument to read RF watts.

Meter calibration (watts) can be accomplished if we feed a known amount of power through the bridge (into a 50-ohm noninductive load) and adjust R1 for a full-scale reading at M1. A panel mark is then made for this setting of R1. It will enable us to readjust R1 later on for reading RF power. Once we identify this setting of R1, the meter scale can be plotted at different power levels, as I suggested for calibrating the QRP bridge of Fig 1. An RF probe, VTVM or FETVOM and a 50-ohm load may be used for calculating the transmitter output power by measuring the RF voltage across the 50-ohm load [P(watts) equals $V(RMS)^2/R$(ohms)].

Adjustment of the QRO bridge is done with a 50-ohm dummy load connected to J2 of Fig 5. Apply RF power with S1 in the FWD position. Adjust R1 to provide a full-scale reading at M1. Switch S1 to the REF



Fig 6—Interior view of the QRO SWR bridge. The PC board is attached to the solder terminals of the BNC jacks. The bottom edge of the PC board is soldered to the chassis at the center. Short wires (upper right and left of PC board) ground the board to the rear panel of the box. C1 and C2 are on the etched-foil side of the board to permit easy access during bridge adjustment (nulling).

mode and observe the meter reading. If it is not zero, adjust C2 for a zero reading. Next, reverse the cables at J1 and J2 and interior view of this bridge is provided in Fig 6.

Construction Notes

The cabinets for these units are made from PC-board pieces. The box dimensions (hwd) are 2-1/2 × 2-5/8 × 3 inches. I chose cane-metal aluminum sheeting for the box covers since it was available at the hardware store. This is an advantage for the QRP bridge, since the holes in the cover permit air flow around the load resistors.

My cabinets were formed by soldering together sections of double-sided PC board (front, back and bottom plates). Strips of PC board are used as stabilizing members between the front and rear panels, adjacent to the bottom plate. These strips provide anchor points for the top cover, which is affixed by means of no. 6 sheet-metal screws. I cut the meter holes with a hand-operated nibbling tool.

I discovered by chance that Krylon® grey undercoat spray paint is excellent on panels: It was the only can of paint I had on hand when I built these units, so I used it. Not only does it dry quickly (5 minutes), it provides a tough matte finish that is quite immune to smudging from our fingers. It appears to be an excellent paint for amateur projects. If you prefer a gloss finish, you apply RF power. Set C1 for an M1 reading of zero with S1 set in the FWD position. Repeat this procedure one more time. C1 and C2 may be any small trimmer of quality, such as miniature air variable or glass piston trimmers.[4] The *minimum* capacitance of the trimmer must be 1 pF or less in order to null the bridge. An may spray the grey panels with polyurethane varnish (also available in spray cans).

The front panels of my units look a bit crude because of the black Dymo® tape labels. Grey Dymo tape would provide a much nicer appearance. White press-on decals might be an even better choice for the control labels.

Adhesive-backed plastic feet are affixed to the bottom of the boxes to prevent excessive movement of the bridges and to avoid scratching the surfaces of desks or tables on which they rest. Screw-on feet may be substituted.

Either of the bridges can be made smaller, should that be your pleasure. I allowed substantial wasted space in order to keep the units in a size class that would not be awkward to work with (the "tail that wagged the dog" problem).

I hope you have fun with one or both of these weekend projects. You should enjoy building these bridges, and they will not endanger your project fund significantly!

Notes

[1] Deleted.

[2] D. DeMaw, "A Beginner's Look at RF Power Measurement," *QST*, Aug 1983, p 35.

[3] Most edgewise imported audio or S meters have microampere movements. Meters used in the instruments described here are available from the supplier in note 1.

[4] Piston trimmers suitable for this project are listed in the BCD Electro catalog, PO Box 830119, Richardson, TX 75083-0119.

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.



Fig 7—Circuit-board etching patterns for the QRP (A) and QRO (B) SWR/power meters. The patterns are shown full-size from the foil side of the board. Black areas represent unetched copper foil.

From February 1990 QST, p 35:

A NEW FACE FOR A RECALIBRATED METER

☐ In "A Simple and Accurate QRP Directional Wattmeter," (pp 19-23 and 36, this issue), I described a QRP wattmeter that uses a standard 0-1 milliammeter modified with a custom, nonlinear scale calibrated directly in power and SWR according to the values shown in Table 1. Making new scales for a stock meter is one solution; adding markings to the existing meter scale is another. It's fairly easy to make the new scales readable, and somewhat harder to make them look nice. If you decide to make new scales rather than add marks to the existing scale, you'll want to record the correct places to make the new marks before you obliterate the old scale. One way to do this is as follows.

Refer to Fig 1. Attach the meter face to a large piece of paper. Trace around the face so you can exactly reposition it later. Find the meter pivot point by extending the tick marks at the scale's ends, and verify this point by extending a couple of other points on the scale. Then draw lines from the pivot point through the meter face to an area beyond the face, labeling them appropriately, as shown in Fig 1. Then you can remove, repaint and replace the meter face. The new scale and marks can be hand-drawn; press-on letters and numbers can be used; or the face may be made with a photographic process.

A caution: Anyone who sees my home-built equipment immediately realizes that, although I'm willing to spend a lot of time on functionality and performance, I don't devote much time to beauty! So you'll have to look elsewhere for advice on how to make a meter face good-looking. When finished, the meter face should resemble Fig 2.—*Roy Lewallen, W7EL, 5470 SW 152 Ave, Beaverton, OR 97007.*

Table 1

Meter-Recalibration Data for the QRP Wattmeter

Power	*Meter*	*SWR*	*Meter*
0.0	0.0	1	0.0
0.05	0.224	1.5	0.200
0.1	0.316	2	0.333
0.2	0.447	3	0.500
0.3	0.548	4	0.600
0.4	0.633	5	0.667
0.5	0.707	7	0.750
0.6	0.775	10	0.818
0.7	0.837	∞	1.0
0.8	0.894		
0.9	0.949		
1.0	1.0		

The *Meter* column expresses fractions of full-scale readings on the original meter scale. For example, the new SWR = 3 mark should be placed at the same place as the half-scale (0.5) mark on the original meter face.



Fig 1—One means of recording meter-scale marking points before erasing the original scale. See text.



Fig 2—Example of a finished meter face. This scale is that of the meter used in "A Simple and Accurate QRP Directional Wattmeter".

From February 1990 QST, p 19:

A Simple and Accurate QRP Directional Wattmeter



Make a few small enhancements to the Bruene wattmeter and diode detector, and you have a directional wattmeter that's simple, portable, and accurate from 10 watts down to 5 milliwatts!

By Roy Lewallen, W7EL
5470 SW 152 Ave
Beaverton, OR 97007

A directional wattmeter is a really indispensable tool. Besides using such a meter to measure SWR, you can use one to tune a home-built rig, adjust a Transmatch, measure cable loss, and a host of other things. Because it's portable, a wattmeter is an important tool in the field: With it, you can make sure the rig still works, and spot any problems with the antenna system. If you're operating QRP in Field Day or some other event, a good wattmeter can help you keep your output at five watts as the battery voltage drops.

This wattmeter, designed primarily for portable use, gives accurate readings at power levels from 5 mW to 10 W. Achieving good low-power accuracy is a bit tricky; I developed a simple correction circuit to handle the job. During the editing of this article, I learned that the technique I developed for compensating the diodes in this wattmeter's detector circuit was first discussed by John Grebenkemper, KI6WX, in his January 1987 *QST* article.[1] I encourage reading (or rereading) this excellent article.

If carefully constructed, this wattmeter should function well from below 1 MHz at least into the mid-VHF range. One prototype tested in the ARRL Lab maintains better than ± 7% of full-scale accuracy, on all ranges, up to 432 MHz.

Circuit Description

A basic directional wattmeter has three major parts: directional coupler, detector, and meter circuits. Each block can be optimized for a particular application. Here's a description of each block.

Directional Coupler

Two types of directional couplers are commonly used by amateurs. The venerable Monimatch circuit is simple and useful for SWR measurement, but not readily adaptable as a wattmeter except over a narrow frequency range, because its sensitivity changes with frequency.[2] The Bruene circuit doesn't have this limitation, so is more suitable for our use. It's generally implemented with capacitive dividers for sensing voltage, but I chose to use transformers for this function.[3] This results in a simpler circuit that's adjustment-free. Sensitivity can be traded for insertion loss; the values chosen for this meter result in insignificant insertion loss.

Maintaining a near-50-Ω impedance on the line through the wattmeter eliminates several frequency-dependent effects. A microstripline structure is effective for this application, and is extremely simple to build, so I used that technique in this wattmeter.

Detector

Seemingly, the detector should be the easiest part of the wattmeter to design. Well, it happened again: The simplest part turned out to be the hardest. What's so hard about using a diode detector? If you don't want to know, skip ahead to the Construction section. For the truly adventurous (mathematically, that is), I've included the sidebar, "Ac v Dc: Why the Difference?"



Fig 1—Simple diode detector.

Plain diode detectors, like the one shown in Fig 1, are simple and easy to use—*provided you don't require accurate results at low signal levels.* That's unfortunate, because good low-power accuracy is exactly what this wattmeter is intended to provide. Five milliwatts provides only 145 mV (peak) at the detector, so detector accuracy must be maintained down to this level. Some diodes, such as back diodes and zero-bias Schottky types, are specially designed for detecting very small signals. These, however, aren't as readily available as common silicon, germanium, and medium-barrier silicon Schottky diodes, so I investigated only the latter three types. Naturally, each has its deficiencies.

Common small-signal silicon diodes (eg, 1N914) drop too much forward voltage to be accurate at small signal levels when used with reasonable load-resistance values (up to 100 MΩ or so). Ordinary small-signal Schottky diodes are better, but still have an objectionable drop for use at low signal levels. The good old point-contact germanium diode (1N34 type) is the clear winner in this category. Applying 50 mV (dc) to a germanium diode detector produces about 45 mV at its output with a 1-MΩ load resistance. Increasing the load resistance to 10 MΩ brings the output to within 1 mV of the applied voltage.

So what's the problem? The problem is that *the results are different when you apply an ac signal to the detector!* This difference is clearly shown in Fig 2, which gives the measured output of a germanium-diode detector (like the one shown in Fig 1) with three different input signals of the same peak value. On the log-log scales, the vertical spacing be-

[1] Notes appear at end of article.

Ac v Dc: Why the Difference?

Why does a diode detector produce less output when detecting an ac signal than a dc signal if both signals have the same peak value? Why does a pulsed-dc signal produce a lower output than a steady one? Fortunately, we don't have to look any further than the ideal-diode equation to get the answers to these questions. This equation describes the characteristics of an ideal diode—a diode that is ideal in the sense that it can be described by some fundamental principles, not in that its conduction is perfect in one direction and zero in the other.

The deal-diode equation is:

$$I_d = I_s\left(e^{V_d\frac{q}{kT}} - 1\right) \qquad \text{(Eq 1)}$$

where

I_d = Diode forward current
I_s = Saturation current, about 10^{-14} A for silicon, 2×10^{-7} A for germanium at room temperature
V_d = Diode forward voltage
q = Electron charge, 1.60×10^{-19} coulomb
k = Boltzmann's constant, 1.38×10^{-23} J/K
T – Temperature, K

At room temperature, kT ÷ q is about 25 mV. Note that I_s is strongly related to temperature, doubling with approximately every 10-°C rise in temperature.

Because our discussion primarily concerns small signals, let's see how the ideal diode behaves with small voltages or currents applied. The small-signal I/V characteristics of an ideal germanium diode are shown in Fig A. This is simply a graphical representation of Eq 1 over a limited range. (The graph is also valid for silicon diodes if the current scale is reduced by a factor of about 20 million.) Note that the I/V curve doesn't bend at the origin; it's a straight line. This gives us our first clue about small-signal diode operation: a straight line on an I/V graph represents a constant resistance, so at very small signal levels the diode looks like a resistor, and hardly rectifies at all. (By very small signal levels I mean somewhat less than kT ÷ q [25 mV].) The resistance of the germanium diode is about 125 kΩ in this range (an ideal silicon diode is about 2.5 TΩ (2.5×10^{12} Ω!). At higher forward voltages, the current rapidly rises; at greater reverse voltages, the current increases, then levels out at a value of $-I_s$.

If we apply dc to the circuit of Fig 1, current will flow heavily at first, then taper off as C_L charges. Eventually, the current will simply be $V_o \div R_L$. Substituting $(V_i - V_o)$ for V_d in Eq 1 and rearranging produces an equation relating V_o and V_i:

$$V_o = V_i - \frac{kT}{q}\ln\left(\frac{V_o}{R_L I_s} + 1\right) \qquad \text{(Eq 2)}$$

or V_d and V_o:

$$V_d = \frac{kT}{q}\ln\left(\frac{V_o}{R_L I_s} + 1\right) \qquad \text{(Eq 3)}$$

To get a feel for the voltage drop to expect, look at Eq 3 with V_o = 100 mV, R_L = 1 MΩ, and $I_s = 2 \times 10^{-7}$ A. This results in a diode drop (V_d) of 10.1 mV. In contrast, a silicon diode ($I_s = 10^{-14}$ A) would drop 403 mV (503 mV in for 100 mV out) under the same conditions, but it would have 10.1-mV drop if R_L was made 20 million times larger. As the signal level increases, the drop increases—but not in proportion, so detector accuracy improves. Increasing the load resistance helps also; at 100 mV out and R_L = 10 MΩ, V_d = 1.2 mV.

Now let's see what happens with an ac or pulsed-dc signal. Looking at Figs 2 and B, we can see that when V_i is greater than V_o, the drop is the same as if the input signal were dc. However, for part of the cycle, V_i is less than V_o. During this time the diode is reverse biased and substantial current flows to the left in Fig 1. Generally, C_L is made large enough to make the ripple on V_o very small. We can then consider V_o to be a constant value after an initial charge period of many cycles of the input signal. For any signal,

$$V_o = I_{d(avg)} R_L \qquad \text{(Eq 4)}$$

where $I_{d(avg)}$ is the *average* current flowing through the diode over a cycle of the input signal.

The wattmeter's detector signal is a bipolar sine wave,



Fig A—Current-voltage characteristics of an ideal germanium diode.



Fig B—The same data as that of Fig 2, plotted on linear axes.

but analysis of a unipolar square wave illustrates the principle and is much easier to attack mathematically (I'll discuss the sine-wave case shortly).

Consider a unipolar square wave with a positive value V_p for 50% of the cycle and 0 V for the other 50%. When the input signal is positive,

$$I_{d(h)} = I_s\left(e^{V_{d(h)}\frac{q}{kT}} - 1\right) \qquad \text{(Eq 5)}$$

where

$I_{d(h)}$ = diode current when the input signal is high.

$V_{d(h)} = V_p - V_o$ = forward voltage (diode drop) when the input signal is high.

This follows directly from Eq 1. When the input signal is zero, the diode is reverse biased. Again from Eq 1

$$I_{d(\ell)} = I_s\left(e^{V_{d(\ell)}\frac{q}{kT}} - 1\right) \qquad \text{(Eq 6)}$$

where

$I_{d(\ell)}$ = diode current when the input signal is low. $I_{d(\ell)}$ is negative.

$V_{d(\ell)} = -V_o$ = diode forward voltage when the input signal is low. $V_{d(\ell)}$ also is negative.

Because $I_{d(h)}$ and $I_{d(\ell)}$ each flow during 1/2 of the input cycle, average current is found by

$$I_{d(avg)} = 1/2\,(I_{d(h)} + I_{d(\ell)}) = \frac{V_o}{R_L} \qquad \text{(Eq 7)}$$

Combining Eqs 5, 6, and 7 and solving for $V_{d(h)}$:

$$V_{d(h)} = \frac{kT}{q}\ln\left[2\left(\frac{V_o}{I_s R_L} + 1\right) - e^{-V_o\frac{q}{kT}}\right] \qquad \text{(Eq 8)}$$

$V_{d(h)}$ represents the difference between the peak value (V_p) of the input signal, and the output voltage (V_o). An analysis of the argument of the logarithm shows that it's always greater than the dc case. In fact, when V_o gets much greater than kT ÷ q, $V_{d(h)} = V_{d(dc)} + (kT \div q)\ln(2)$, or about 18 mV at room temperature. This result is independent of R_L, so even if R_L is large to minimize dc drop, the added drop due to applying ac will stay the same (as long as $V_o >> kT \div q$). The added offset is clearly shown in Fig B. Values calculated from Eqs 1 and 8 fall almost exactly on the graphs. A similar analysis for a bipolar square wave results in the same limiting value of 18 mV of excess drop.

Math is fun! But everyone's got a limit, and mine falls within the large gap between analyzing the detector with square-wave and sine-wave inputs. However, some generalizations can be made without having to do a rigorous sine-wave analysis. With a sine wave applied, one would expect diode forward current to flow for only a small part of the input cycle, resulting in a greater drop than with a square wave applied. The sine-wave case was studied with a mathematical computer model, and the results agreed very closely with the measurements presented in Figs 2 and B.—*W7EL*

tween plots is proportional to the fractional (percentage) difference between the outputs. As you can see, a simple germanium detector is accurate for ac signals *only when the peak input signal level is above about 1 V.* A simple correction circuit is the secret to this wattmeter's accuracy. I'll explain it in a moment, but first I'll briefly explain why the detector output is less with an ac than with a dc input.

When the forward or reverse voltage across a diode gets very small (a few millivolts), the reverse and forward currents are approximately equal for a given applied voltage; that is, the diode acts like a resistor. (I measured a typical germanium diode's resistance as about 120 kΩ, a value very much smaller than that of silicon diodes.) If dc is applied to the detector, the detector circuit acts like a voltage divider, with the input voltage dividing between the diode resistance and the load resistance. When ac is applied, however, the current flow during the negative half-cycle removes a substantial part of the charge put on the load capacitor during the positive half-cycle, resulting in a lower detector-output voltage. The effect is waveshape and duty-cycle dependent, but isn't related to the frequency of the input signal.



Fig 2—Dc output voltage of the detector of Fig 1 with three types of input signals.

Silicon diodes exhibit the same properties, but at different levels. Silicon-diode resistance at few-millivolt levels is about a million times larger than that of germanium diodes, but extremely large load resistances (10^{12} Ω or so) would have to be used to bring the forward drop to the germanium-diode level. The much smaller currents flowing through the much larger resistance result in the same net effect. The observed ac/dc difference is explained by the ideal-diode equation (see the sidebar). Dc and unipolar-square-wave measurements were compared to results predicted by the ideal-diode equation with extremely good agreement.

Common 1N34A germanium diodes purchased from Radio Shack® were found to be satisfactory for this detector.

The Meter Circuit

See Fig 3. An op amp is a logical choice to provide a high load impedance for the detector and a low-impedance output. Most op amps, however, have enough input-bias current to produce a significant voltage across a high-value detector-load resistor, ruining the measurement. Fortunately, operational amplifiers that have input-bias currents of only a few picoamperes—more than adequate for this application—are readily available. The CA3160 (and its externally compensated equivalent, the CA3130) has the desirable combination of extremely low input current,


Microstripline
J1
J2
T1
Directional Coupler
T2
T3
R1 51
R2 51
D1
D2
R3 100 k
R4 100 k
Detectors
C1 0.01
C2 0.01
S2 FWD/REV
Except as indicated, decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); resistances are in ohms; k=1,000, M=1,000,000.
● = phasing
IC pins not shown are unused.
Meter Circuits
POWER
S1
9 V
0.01
10 µF 16 V
U1 CA3160
1 k*
SENSITIVITY cw
R6
U2B
0.001*
D3
R5 12 k
U2A LM358
CAL
5.6 k
R7 2 k
M1 0-1 mA
CAL R8 10 k
18 k
1W
10W
51 k
0.01
S3
5.1 k
0.1W
R9 1 k CAL
FULL SCALE SELECT

Fig 3—Schematic diagram of the QRP directional wattmeter. All fixed resistors are ¼-W, 5%-tolerance units. D1-D3 are common 1N34 germanium diodes; they should be matched (as discussed in the referent of Note 1) for best performance. T1-T3 are FT-37-72 ferrite cores with single-turn primaries (one pass through the core—see Fig 5). The primaries of T2 and T3 are comprised of the ungrounded leads of R1 and R2, respectively. Each transformer has a single secondary winding consisting of 10 evenly spaced turns of no. 28 enameled wire. Do not substitute a different core for the FT-37-72. R6 can be any value between 10 kΩ and 100 kΩ. The resistor and capacitor (associated with U1) marked with asterisks may be necessary to eliminate instability in the op amp, although my prototypes don't require them. See text.

input-and output-voltage range down to the negative supply rail and moderately low current consumption. To my knowledge, no other readily available op amp shares this set of features; if you know of one, you may substitute it for the CA3160 used at U1.

The second op-amp input is used by the diode-compensation circuit, so a second stage is required to permit variable gain. The only requirements for the second op amp are moderate current consumption and the ability to handle input and output signals down to the negative supply rail (ground). The LM358 contains two such op amps; one section (U2B) is unused in this application. You could substitute one section of an LM324, another CA3160, or any other op amp having the required characteristics.

The diode-compensation circuit (D3 and R5 in Fig 3) creates an offset that approximately compensates for the drop across the detector diode. If dc was applied to detector D2/R4/C2, and if compensation resistor R5 and detector load resistor R4 were equal, perfect compensation would result (assuming that D2 and D3 were identical). However, the circuit is actually compensating the detector *ac* drop with a *dc* drop, so more current must flow through compensation diode D3. This is accomplished by making R5 smaller than R3 and R4. Although the compensation isn't perfect, it's extremely good, and a remarkable improvement for only two added components. Without the compensation circuit, the wattmeter error was 30-50% for small signals (5-50 mW); with the compensation circuit, measured error is less than 7% over the same range. In addition, the compensation circuit tracks well with temperature; an important consideration for portable use.

In John Grebenkemper's circuit (see Note 1), an additional resistor and capacitor in the feedback network are used to ensure stability in the op amp. I saw no signs of instability in my prototype, but if you experience instability problems, adding these components (marked with asterisks in Fig 3) should help.

Construction

Meter Face

You'll need to make new scales for the meter or, at the very least, add markings to the existing scale. It's fairly easy to make the new scales readable and somewhat harder to make them look nice. If you decide to make new scales rather than add marks to the existing scale, you'll want to record the correct places to make the new marks before you obliterate the old scale. See this month's Hints and Kinks column for one method of relabeling a meter face.

Directional Coupler

This wattmeter works best if there's a constant 50-Ω impedance from the input to the output, but it's not highly critical. There are always impedance bumps at the transitions

Fig 4—Completed detector circuit board.
Not drawn to scale.


Hole for T1
0.1"
1" Min
1/16"
Glass-Epoxy Board
Solid Copper on Bottom of Board
Copper



Top of Board



Bottom of Board

Fig 5—Close-up views of the completed directional coupler. T1's primary is a straight piece of insulated wire spanning the cut in the microstripline. T1's secondary winding is routed through the hole cut for T1. The top view shows the components comprising the directional coupler and detector. To achieve minimum lead lengths, R1-R4 are mounted vertically on the ground plane. Capacitors C1 and C2 are not shown, although they should be mounted directly across R3 and R4, respectively.

between the coax connectors and the microstripline, and a larger bump at the coupler transformer, but these bumps can be made insignificant at HF with a little effort. Only the microstripline and directional coupler are sensitive to layout, and you have considerable latitude with these components if you know the rules.

The microstripline will be the simplest circuit board you've ever made. If you've never made a PC board before, don't worry—you can't go wrong with this one. It consists simply of a single trace on one side of the board and a ground plane on the other. There are at least three ways to fabricate this board: You can stick adhesive copper tape to the non-foil side of a single-sided board, you can etch a double-sided board, or you can cut along the edges of the line with a knife and peel away the unwanted copper.

No matter which method you choose, start with a piece of 1/16-inch-thick, glass-epoxy PC board. The board's length should equal or exceed the distance between wattmeter input and output connectors, and the board should be at least one inch wide (wider is okay). The width of the microstrip, which should be about 0.1 inch, determines the impedance of the line. Impedance doesn't change much as line width changes, and the impedance isn't too critical for this application. So if you don't have a decimal ruler, just make the trace a bit thinner than 1/8 inch—it'll be close enough. After making the board, cut a hole in the center just large enough to accommodate transformer T1. The finished microstripline should look like that shown in Fig 4.

Mount the coupler components using *short* leads. A suggested layout is shown in Fig 5. Then assemble the rest of the wattmeter and mount the completed coupler between the input and output connectors. The connections from the connectors to the microstripline must be very short, particularly the ground connections. If possible, put a solder lug or lugs on the connector-mounting screws and solder the lugs directly to the bottom of the line as shown in Fig 6.

A template package containing a PC-board pattern integrating the wattmeter circuit and directional coupler, parts-placement diagram and other information is available from the ARRL Technical Department Secretary for a no. 10 SAE with return postage for 1 ounce.

Tips

A small center-off toggle switch, wired for **REV-OFF-FWD** operation, is a convenient way to combine S1 and S2. However, small toggle switches are amazing in their ability to turn themselves on at the slightest provocation—like being bumped around in a suitcase or backpack. So if you're going to use this wattmeter for portable operation, use some other kind of switch (a slide switch, for example) for, or in series with, S1.

I've seen quite a few articles implementing the Bruene directional-coupler circuit with a powdered-iron core (eg, T-68-2). The low winding impedance of such a transformer will ruin the accuracy of this circuit, so don't use powdered-iron cores for the transformers in this wattmeter.

Adjustments

All you'll need for adjustment is a high-impedance dc voltmeter. Connect the voltmeter between the wiper of the **SENSITIVITY** control (R6) and ground. Connect a temporary jumper between pins 7 and 3 of U1. Turn R6 fully counterclockwise. Set the **FULL SCALE SELECT** switch S3 to the 10-W position. Turn on **POWER** switch S1. Slowly turn R6 clockwise. As you do, the wattmeter and voltmeter readings should increase. If not, turn the wattmeter off and check your wiring.

Adjust R6 for a voltmeter reading of 6.49 V, then adjust R7 so the wattmeter reads full scale. Adjust R6 for a voltmeter reading of 2.05 V, then switch S3 to the 1-W position. Adjust R8 until the wattmeter indicates full scale. Adjust R6 for a voltmeter reading of 0.649 V, then switch S3 to the 0.1-W position. Adjust R9 for a full scale reading on the wattmeter. Turn the wattmeter off and *remove the temporary jumper between pins 3 and 7 of U1.* This completes the calibration.



Fig 6—Using solder lugs to make a good connection to the ground side of the microstripline.

To obtain maximum reliability, measure R7, R8, and R9 and replace them with fixed resistors of the measured values; readjustment should never be necessary.

If you need to measure SWR at levels very close to 1:1, you may want to tweak the wattmeter to show a zero-reflected-power indication when connected to a reference dummy load. The resistors to adjust are R1 and R2. Theoretically, the correct value for these resistors is 49.5 Ω each. It's not necessary to readjust the wattmeter if you change the values of R1 and R2 slightly.

Use

To measure power, select the appropriate scale and turn S6 fully clockwise. The power flowing in the line is the forward reading minus the reverse reading. To measure SWR, switch S3 to the next more sensitive setting and switch S2 to **FWD**. Adjust R6 for a full-scale meter reading. Flip S2 to **REV** and read the SWR scale. To adjust a Transmatch, put the wattmeter between the transmitter and Transmatch and adjust the Transmatch for zero reflected power.

The directional wattmeter can do anything an SWR meter can do, and many things besides. Because you can measure power anywhere in a system, you can use the wattmeter to find cable and Transmatch losses, measure transmitter power, and lots of other things. You'll be surprised how often you reach for it!

Acknowledgments

Thanks to Dave Deford, KØED, for helping me reduce the mystery of ac versus dc response of a diode detector to the realm of physics, where it belongs.

While editing this article, *QST* Assistant Technical Editor Rus Healy, NJ2L, recognized the detector-diode-compensation method as the one presented by John Grebenkemper (see Note 1). John Grebenkemper subsequently reviewed the article and made several useful suggestions, many of which have been incorporated into this article. One important consequence of John's comments is that they motivated me to model the performance of the detector/compensation combination for sine-wave inputs, during which I discovered an undesirably high sensitivity to diode saturation current, which is closely related to temperature. This resulted in lowering the values of R3, R4 and R5 to

those shown in Fig 3 from the original design values, which were much higher. John's diode measurements showed a greater variation in I_{sat} than I had found, indicating the desirability of matching the diodes as described in his article. John also pointed out the possibility of op-amp offset causing the meter to read slightly upscale with no applied signal. The worst-case error is about 2% of full-scale deflection; less in most cases. If necessary, you can add an offset null consisting of a 100-kΩ potentiometer between pins 1 and 5 of U1, with its wiper grounded.

Notes

[1] J. Grebenkemper, "The Tandem Match—An Accurate Directional Wattmeter," *QST*, Jan 1987, pp 18-26. Also see "Tandem Match Corrections," Technical Correspondence, Jan 1988, p 49.

[2] This circuit was originally discussed in L. McCoy, "The Monimatch," *QST*, Oct 1956, and has been covered in many articles since.

[3] W. B. Bruene, "An Inside Picture of Directional Wattmeters," *QST*, Apr 1959.

From November 1987 QST, p 18:

Build This QRP Omni Box



Man does not live by rig alone! Combine your QRP accessories into one package for field or home use.

By Doug DeMaw, W1FB
PO Box 250
Luther, MI 49656

Do you need to carry a number of small QRP-support gadgets with you during portable operation? If so, you may be interested in how I solved my "bag-of-accessories" problem by building the most needed support units into one cabinet. A secondary advantage of unitizing these circuits is that only one panel meter and one cabinet are required. This represents a saving in dollars—an appealing fringe benefit.

You need not incorporate all of the circuits I chose for my Omni Box. On the other hand, you may prefer to add some accessory circuit that I don't find necessary for my QRP operations: The road to innovation is open to you! Whatever your pleasure, I'm sure you will be impressed with the convenience of having all of the necessary accessory items gathered together in a single housing. This is particularly handy for camping, Field Day, vacations and casual travel. Moreover, the Omni Box can be a convenient gadget for home-station use as well.

Fig 1 shows all of the circuits in my Omni Box. The instrument contains a field-strength meter, dummy load, SWR bridge, frequency standard and continuity tester.

Field-Strength Meter Section

An indication of relative field strength is helpful when checking antenna performance and patterns. This instrument may be used as a tune-up indicator, or as a relative output-power monitor. Still another application is that of a frequency meter to ensure that the transmitter is providing output in the correct amateur band. The circuit may be used also as a RF "sniffer" when troubleshooting a transmitter.

Refer to the field-strength meter circuit in Fig 1. Two operating ranges are provided. When S3 (FREQ) is open (LO), the tuning range of C1 provides coverage of 2.6 to 10.5 MHz, thereby permitting tests on 80, 75, 40 and 30 meters. When L1 is placed in parallel with T3 (HI), the effective circuit inductance is 1.5 μH. This provides coverage from 6.9 to 25.4 MHz for use on 40, 30, 20, 15 and 12 m. See Table 1.

Table 1
Approximate TUNING Dial Settings for the Field Strength Meter

Band	*C1 Setting*
FREQ LO Range	
80 m	12:30 (o'clock)
40 m	2:30 "
30 m	3:00 "
FREQ HI Range	
40 m	10:00 "
30 m	12:30 "
20 m	2:00 "
15 m	2:30 "
12 m	3:00 "

C1 is a miniature broadcast-band radio variable capacitor.[1] You may use any capacitor that provides 365 to 400 pF of maximum capacitance. The minimum capacitance (plates unmeshed) should be 20 pF or less. You may also use the variable capacitor from a transistor AM radio by placing both sections in parallel; this provides approximately 225 pF of maximum capacitance. Using this small a capacitance value will limit the tuning range of the field-strength meter, so fixed-value capacitors must be shunted across C1 to cover the low end of each range. Also, the calibration data in Table 1 will not be applicable.

The secondary winding of T3 provides low-impedance coupling to D1 and D2. The link also prevents excessive loading of the tuned circuit, and helps ensure a workable Q on both ranges (too low a Q will restrict the sensitivity of the instrument).

D1 and D2 function as a voltage doubler. The rectified RF voltage causes current to flow through the indicating meter, M1. Therefore, the greater the field strength, the higher the meter reading. C1 is adjusted for a peak meter reading, and R6 is used as a sensitivity control to keep the meter from being driven offscale. A 24-inch whip antenna connected to J1 should suffice for most field-strength tests.

Dummy-Load Section

A dummy load is important when we need to check transmitter performance or make tuning adjustments. In the dummy-load circuit of Fig 1, I use four 200-ohm, 2-W resistors (R1-R4, incl) in parallel to provide a 50-ohm load. RF voltage across the dummy load is rectified by D3 and filtered by C4. The resulting dc voltage is applied to M1 through S1. R5 isolates the dummy load from the metering circuit and makes the meter response more linear. The meter provides a visual indication of the transmitter output energy.

The meter may be calibrated in watts by applying a known power (say, 5 W) to the load and adjusting R6 (SENS) for a full-scale reading on M1. The power is then reduced in 1-W steps, and the meter reading noted at each step. These readings are logged for future use (see Table 2). I placed

---

[1] Notes appear at end of article.


OSC
WHIP
J1
FS METER
Q1, Q2
C
B
E
S3
LO
HI
RANGE
C1
365
TUNING
L1
1.6 µH
22 µH
T3
C2
0.1
D2
1N34A
D1
1N34A
C3
0.1
DUMMY LOAD
J2
RF IN
R1
R2
R3
R4
200
2 W
R5
10 k
D3
1N914
C4
0.1
Y1
100 kHz
C12
0.001
FREQ STD
C11
50
FREQ SET
R9
470 k
2N3904
Q1
C10
0.001
C13
560
AMP
Q2
2N3904
R11
470 k
R10
5.6 k
C16
0.005
500 µH
T2
D7
1N34A
C17
0.1
SIG OUT
J5
D6
1N34A
R13
47
(A)
R12
1 k
C15
1 µF
16 V
SWR
S1
FS
DL
R14 *
6.8 k
0-200
µA
M1
R6
10 k
SENS
J6
CONTINUITY TEST
J7
C14
0.1
ON
S4
BT1
9 V (4 mA)
BT2
1.5 V
SWR BRIDGE
XMTR
J3
(50 Ω)
NULL
T1
J4
ANT
(50 Ω)
C5
7
C6
7
D4
1N34A
D5
1N34A
C7
0.1
C8
0.1
R7
33
R8
33
REF
S2
FWD
RFC1
500 µH
C9
300
SM
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000
SM = SILVER MICA
* = SEE TEXT
WHIP
J1
6.8 pF
(B)
TO C1, L2, S3

Fig 1—Schematic diagram of the Omni Box circuits. Fixed-value capacitors are miniature chip or disc ceramic types, except for C15, which is electrolytic. Fixed-value resistors are ¼-W carbon composition except for R1-R4, incl, which are 2-W units. Numbered parts that do not appear in the parts list are identified for circuit-board layout convenience.

C1—Miniature 365-pF variable (see Note 1).
C5, C6—Miniature 7-pF piston trimmer or equivalent unit with low minimum capacitance (see text).
C11—50-pF trimmer (Radio Shack 272-1340 or equiv).
J1-J5, incl—Single-hole-mount phono jack.
J6, J7—Pin jack for test leads.
L1—1.6-µH inductor, 18 turns of no. 24 enam wire on an Amidon T-50-6 (yellow) powdered-iron toroid.
M1—Miniature 200-µA dc meter (see text).
R6—Miniature 10-kΩ linear-taper carbon.
RFC1—Miniature 500-µH RF choke (1 mH also suitable).
S1—Single-section, three-position rotary switch.
S2, S3 S4—Miniature SPDT toggle or slide switch.
T1—Broadband transformer. Secondary winding is 30 turns of no. 26 enam wire on an Amidon FT-50A-61 ferrite toroid (125 µi). Primary is a two-turn winding of no. 24 enam wire over secondary winding.
T2—500-µH primary winding. Use 36 turns of no. 26 enam wire on an Amidon FT-50-43 ferrite toroid (850 µi). Secondary winding has 10 turns of no. 26 enam wire.
T3—22 µH primary winding. Use 20 turns of no. 26 enam wire on an Amidon FT-37-61 (125 µi) ferrite toroid. Secondary winding consists of 5 turns of no. 26 enam wire.
Y1—100-kHz fundamental crystal, 30-pF load capacitance. International Crystal Co type GP. See note 3.

marks on the front panel to allow resetting of R6.

Depending on the type of SWR bridge you use in your Omni Box, the dummy load may be a part of the bridge circuit. This will simplify the project.

SWR Bridge

You have some choice in the type of SWR bridge you use.[2] You may prefer to use the resistive-bridge circuit described in the referenced article. The circuit shown here is similar to the toroidal-transformer (QRO) bridge described in that article, but it is more sensitive to make it suitable for power levels from 350 mW to 25 W.

D4 and D5 rectify the forward or reflected voltage (selected by S2) to provide a dc voltage for the meter. Trimmer capacitors C5 and C6 form a voltage divider with C9. These trimmers are used to null the bridge with a 50-ohm load connected to J3 or J4. A coaxial-cable jumper may be connected between J3 or J4 and J2 (dummy load) when nulling the bridge circuit.

To null the bridge, set S2 to FWD, connect the 50-ohm load to J4 and apply trans-

Table 2

Calibration for a 200-µA meter with SENS at Mid-scale

RF Power (W)	*Meter Scale*
5	10
4	9
3	8
2	7
1	5
0.5	3.5
0.25	1.5
0.1	1


500 µH
L1
C2
C3
0.1
470 k
Q1
2N3904
560
SIG OUT
5.6 k
C1
100
CAL
2.2 µF
16 V
+9 V
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000

Fig 2—Suggested circuit for a 100-kHz LC oscillator. C1 is a 100-pF ceramic trimmer. L1 consists of 85 turns of no. 32 enam wire on an Amidon FT-50-61 ferrite toroid core. C2 and C3 are 0.01-µF, high-Q capacitors, such as polystyrene or Mylar® units. C1 is adjusted to zero beat the oscillator output with WWV. A coating of coil cement should be applied to L1.

mitter power to J3. Adjust R6 (SENS) for a full-scale M1 reading. Now, set S2 to REF and adjust C6 for a zero reading on M1. Next, reverse the connections—connect the transmitter to J4 and the dummy load to J3, and set S2 to FWD. While applying transmitter power, adjust C5 for a zero reading on M1. Repeat this process once more to compensate for any interaction of the two trimming capacitors.

The values of R7 and R8 are different than those in the QRO bridge in the referenced article. In addition, T1 has a two-turn link rather than having the antenna line pass through the toroidal core (the equivalent of a one-turn winding). These changes ensure greater SWR meter sensitivity, necessary for QRP use. The circuit shown may be used at power levels up to 25 W without damage to the diodes.

The Meter

A 200-µA instrument is specified for M1. There are a number of low-cost, edge-reading meters of this type available in the surplus market. Most of these are FM tuning meters, but some are calibrated for use in CB transceivers. These meters are easy to take apart for substitution of a new meter scale. A 0-10 scale that will fit most of these meters was published in the article referenced in note 2. A photocopy of this meter scale can be affixed to the faceplate of your surplus meter with rubber cement.

Using a 50- or 100-µA meter at M1 will result in greater sensitivity for the Omni Box functions than the specified 200-µA unit. This increased sensitivity can be particularly beneficial when using the field-strength and SWR-bridge circuits. Most imported meters with a 50- or 100-µA movement are in a conventional format, and are easier to read than the smaller, edge-reading types.

100-kHz Frequency Standard

There may be no more useful accessory than a secondary frequency standard. Many home-brew QRP transmitters—particularly those with VFOs—are prone to frequency changes as the ambient temperature varies. The problem is not limited to homemade gear. I have used several pieces of commercial QRP gear that exhibit frequency-calibration problems. Also, shock or vibration can shift a trimmer capacitor or a slug-tuned-core setting. Out-of-band or out-of-license-class-segment frequency excursions can be avoided by making periodic transmitter dial calibration checks using a properly calibrated receiver. I like to know my operating frequency, so I always carry a secondary frequency standard with me on QRP expeditions.

The frequency-standard circuit in Fig 1 holds its calibration quite well. Q1 is a 100-kHz crystal-controlled oscillator. C10 and C12 are feedback capacitors that ensure circuit oscillation. These capacitors may need to be changed slightly from the values shown, depending on the characteristics of the crystal you use.

Q2 is a broadband amplifier that increases the 100-kHz energy sufficiently to permit D6 and D7 to generate strong harmonics of the crystal frequency. The diodes generate harmonics by distorting (clipping) the signal from Q2. This is particularly important when using the 100-kHz markers above 40 meters: Weak markers may not be discernible in QRN and QRM.

T2 is tuned broadly to resonance by C16. R13 provides a dc return for D6 and D7 and establishes a load for Q2. A 9-V battery supplies operating voltage for the frequency standard. It's easy to forget to turn S4 to OFF when you are not using the standard—I've done it too many times! If the switch is left in the ON position for long periods, BT1 will be depleted. It's wise to carry a spare 9-V battery with you on field trips.

Using a new 100-kHz crystal at Y1 may be costly! I suggest that you scan the surplus equipment catalogs for moderately priced 100-kHz crystals.[3] Alternatively, you may use a 500- or 1000-kHz crystal



Fig 3—Interior view of the assembled Omni Box. The battery holders are affixed to the rear wall of the cabinet. The SWR bridge is at the far right of the PC board. The field-strength meter and dummy load are near the front panel at the left side of the cabinet. Y1 and the 100-kHz oscillator are located below the batteries.



Fig 4—Circuit-board etching pattern for the Omni Box. The pattern is shown full-size from the foil side of the board. Black areas represent unetched copper foil.

with frequency dividers to obtain markers at, say, 25, 50 and 100 kHz. This approach complicates the circuit, however, and increases the current drain on BT1. Fig 2 shows an LC 100-kHz oscillator that may be substituted for Q1 of Fig 1. It will need calibration against WWV more frequently than is necessary with a crystal oscillator. It does, however, present a way to save money.

The frequency standard may be calibrated by connecting a coaxial cable between J5 and a receiver capable of receiving WWV. Tune in WWV and adjust C11 to obtain a zero beat between the output frequency of the standard and WWV. Calibration should be checked at least once a month to ensure that the standard is accurate.

Calibrate your receiver by connecting a coaxial-cable jumper between J5 and the antenna jack of your receiver. If the 100-kHz signal is too strong, you can lower the signal level by substituting a capacitor of lower value for C16 (5 to 27 pF). Tune the receiver to a convenient frequency that is an exact multiple of 100-kHz, and adjust the receiver-tuning trimmer capacitor for zero beat with the standard. Once your receiver is properly calibrated, it may be used to check the calibration of the transmitter frequency dial. A low-level signal from the transmitter, such as that obtained in the SPOT position, is sufficient for calibration, and this signal level can usually be heard without an antenna.

Continuity Tester

Continuity tests are frequently necessary when we are away from our home stations with QRP gear. Situations arise when we need to check a coaxial cable or an antenna for opens or shorts. A simple continuity tester will suffice, and it eliminates the need to carry a VOM.

I added R14 (Fig 1) and two pin jacks (J6 and J7) to the metering circuit of the Omni Box. These components, along with BT2, provide a full-scale reading at M1 when a short is placed across J6 and J7. Resistances of more than 1 ohm can be observed with this tester. No switch is needed for connecting BT2 into the circuit because the line is open until the test probes are placed across a conducting path. R14 is chosen for use with a 200-μA meter. You may need to experiment with the value of R14 if you use a meter with other than a 200-μA movement. S1 may be in any position of its three positions while making continuity tests. The diodes connected to S1 block the flow of dc from BT2 because their cathodes are connected toward the *positive* voltage source.

Construction Notes

Packaging of your Omni Box is a matter of personal choice. I used a Ten-Tec TG-TW-34 utility cabinet for this project. Its dimensions are 3 × 4-1/8 × 4-1/8 inches (HWD). The front and rear panels are eggshell white, and the cover is finished in a brown wood-grain adhesive-backed plastic. The panel labels are press-on decals that were applied after the panel holes were drilled, and before the controls were mounted. Following application of the labels, I sprayed the front and back panels with Krylon® No. 1303 clear acrylic lacquer to protect the labels and give them more contrast. This product is available in office-supply stores.

An interior view of the Omni Box is shown in Fig 3. The PC board is double sided, with the copper on the component side acting as a ground plane. I suspect that single-sided board would work satisfactorily for these circuits. I used double-sided board because the input/output PC traces for the SWR bridge depend upon the ground-plane surface of the board to form 50-ohm strip lines. Elimination of the ground plane may not affect the bridge circuit significantly, because of the short distance between J3 and J4 of Fig 1. The most used controls are on the front panel of the box. S4, the ON/OFF switch for the frequency standard, is mounted on the rear panel. A U-shaped holder is used for the 9-V battery. I attached BT2 to the inner rear-panel wall with a nylon clamp. A single AA-size battery holder for BT2 would allow more convenient replacement of the 1.5-V battery: The circuit wires are soldered to the ends of BT2 in my unit.

R14 is not mounted on the circuit board. Rather, it is soldered between J6 and R6, just behind the front panel. All of the toroidal coils are mounted vertically on the PC board. I coated each of them with a homemade coil dope after they were installed. I also flowed a large drop of cement under each coil to affix them to the PC board.

I made my coil dope by dissolving small pieces of polystyrene tubing in acrylic solvent/cement. This liquid contains methylene chloride. *Warning: Do not breathe the fumes from this chemical, and avoid getting it on your skin.* A good grade of coil dope may also be made by dissolving chips of acrylic tubing or sheeting in this solvent.

A full-scale etching template for the PC board is shown in Fig 4. A parts-placement guide is shown in Fig 5. I used donut pads and PC layout tape to develop the master artwork for the PC board. I then transferred a mirror image of the pattern to a sheet of paper with a plain-paper copier. This sheet became my master artwork for Tec-200 film, from which the etch-resist pattern was ironed onto the blank PC board.[4] After drilling the holes in the board, I plated it with Kepro tin-plating solution.

Odds and Ends

The glass piston trimmers I used for C5 and C6 are set at near maximum capacitance for the desired bridge null. Had I realized this sooner, I would have substituted 6.8-pF silver-mica capacitors for the trimmers. You may want to try this, assuming that the value of C9 is close to 330 pF.

Fig 1B shows a 6.8-pF capacitor in series with the line from J1. This capacitor should



Fig 5—Parts-placement guide for the Omni Box. Parts are placed on the nonfoil side of the board; the shaded area represents an X-ray view of the copper pattern.

be added if you intend to use a longer pick-up antenna for the field-strength meter, or if you connect an RF-sniffer probe to the circuit. This low-value capacitor will help to isolate the tuned circuit from the added capacitance of the probe or longer antenna. Without this change, the field-strength meter's tuned circuit will have a restricted upper-frequency range and reduced Q.

Maximum SWR bridge sensitivity (SENS set fully clockwise) is 350 mW. This is more than ample for most QRP transmitters. The dummy-load metering sensitivity may be increased by changing R5 to a lower value. The meter responds adequately at 100 mW with the value for R5 given in Fig 1.

I used an RF probe and a VTVM to measure transmitter power across a 50-ohm resistive load ($P = E_{rms}^2/R_{ohms}$). I set R6 (SENS) for a full-scale reading at M1 with 5 W of RF power into the dummy load. This resulted in approximately a half-scale (12 o'clock) setting for R6. I then incrementally decreased the transmitter power and noted the readings to provide the data in Table 2. You may calibrate your meter scale for forward power by following this procedure. A scope of adequate bandwidth may be substituted for the probe and VTVM, but the resolution will not be as great as with the VTVM. You will have to convert the peak-to-peak readings of the scope to RMS values. The dummy load in the Omni Box will safely dissipate 4 W of continuous RF power. If you exceed this limit (5 to 8 W), restrict your key-down periods to 30 seconds or less, and allow a short cool-off period between tests.

You can cover the 10-m band with the field-strength meter by removing 2 turns from L1. I did not include coverage to 30 MHz because I don't operate QRP at 10 meters, likewise for 160 meters.

In the interest of miniaturization, I chose small components for most of the circuit. Surplus ceramic chip capacitors are used toward this end. Small switches are used, except for S1, which is the only suitable one I had on hand. R6 is a miniature component also.

I'm sure you will find this Omni Box as handy as I have. Maybe you'll include a QRP Transmatch in your unit to make it a complete do-everything gadget!

Notes

[1] Circuit Specialists Co, PO Box 3047, Scottsdale, AZ 85257. Part No. A1-233.

[2] D. DeMaw, "The SWR Twins—QRP and QRO," *QST*, Jul 1986, p 34.

[3] JAN Crystals, 2400 Crystal Dr, PO Box 06017, Fort Myers, FL 33906-6017, Catalog no. 30, 100-kHz crystal, 0.01% tolerance, HC-13/U case, $6.50 ea.

[4] D. DeMaw, "Homemade Circuit Boards—Don't Fear Them," *QST*, Aug 1987, pp 14-16 and 22.

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.

From September 1988 QST, p 26:

A Simple Resonant ATU

Eliminate roller inductors and tapped coils with this simple HF-band Transmatch. This circuit is suitable for QRP or QRO.

By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250
Luther, MI 49656



Are you weary of looking for expensive roller coils? Do tapped coils in ATUs (antenna tuning units) fail to provide the inductance resolution you need for matching a broad range of impedances? We are kindred souls if your answers to these questions are "yes." The roller-coil problem is even more acute for a QRPer: Tiny roller inductors that fit the small format of QRP gear are not available. The remaining option is a tapped coil and switch.

The circuit I shall discuss in this article is by no means new or original. The manner in which I am using it is, however, a bit uncommon. Fig 1 illustrates the circuit. Unlike other Transmatch circuits, this one is resonant at the operating frequency. Most tuners contain elements of L and C, which are used to cancel inductive or capacitive reactance in an antenna circuit. Circuit resonance is not a criterion. The popular T match that is used in most commercial Transmatches is an example of a nonresonant ATU. A resonant Transmatch offers the advantage of simplicity and harmonic reduction.

A Closer Look at the Circuit

Please refer to Fig 1. The main part of the circuit is L1 and L2, along with C1. Here we have a standard tuned circuit or resonator. L1 is the coupling link into the tuned circuit. As shown, C1 and L2 form a resonant 80-meter circuit. C2 has been added to permit matching the signal source (transmitter) to the load. A matched condition will prevail at some setting of C2. This is a very old trick that has been with us for decades.

There is considerable interaction between C1 and C2, since the greater the capacitance at C2, the less capacitance we need at C1 to maintain tuned-circuit



EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS. k = 1000

SM = SILVER MICA

Fig 1—Schematic diagram of the SWR bridge and Transmatch. Fixed-value capacitors are disc ceramic unless noted otherwise. Fixed-value resistors are carbon composition.

C1—Miniature 100- or 140-pF air variable.
C2—10-100 pF trimmer with shaft (see note 1) or 100-pF air variable.
D1—Silicon high-speed switching diode, type 1N914 or equiv.
J1, J2—Single-hole mount phono jack or S0-239.
L1—6 turns of no. 22 insulated wire over ground end of L2.
L2—28-μH inductor. Use 70 close-wound turns of no. 22 enamel wire on a 7/8 × 2-inch length piece of PVC pipe.
L3—10-μH inductor. Use 30 turns of no. 26 enam wire, closely wound, on a 5/8 × 1-inch piece of PVC pipe.
L4—2.6-μH inductor. 16 turns of no. 20 enam wire, closely wound, on a 5/8 × 1-inch piece of PVC pipe.
L5—0.85-μH inductor. Use 9 turns of no. 20 enam wire on a 5/8 × 1-inch piece of PVC pipe. Space turns to occupy 5/8 inch.
M1—Small edgewise tuning meter, 200 μA. Surplus S meter used here with scale from page 35, July 1986 *QST* glued to meter face.
R1—Linear-taper, 10-kΩ potentiometer, carbon composition.
RFC1—Miniature 750-μH or 1-mH RF choke.
S1, S2, S3—SPST slide switch (see text).
T1—Toroidal transformer. Use 35 turns of no. 26 enam wire on an Amidon FT-50-61 ferrite toroid (μ = 125). Primary has 1 turn of no. 26 enam wire.

resonance. In other words, the C2 capacitance adds to that of C1. For this reason we must adjust C1 and C2 alternately as we tune for minimum SWR, just as with conventional ATUs.

How do we solve the problem of multiband operation? A simple solution is provided by adding L3, L4 and L5. These coils are switched in parallel with L2 by means of S1, S2 and S3. A single-pole, three-position wafer switch can be used in place of the individual switches, although it would limit the flexibility of the circuit. I will discuss this later. As is the situation when we place resistors in parallel, coils that are placed in parallel have a net value that is less than that of the smallest coil in the combination. Therefore, we simply add L3 to the circuit for 40-meter operation, L4 for 20 meters and L5 for 10- and 15-meter operation. The 30-meter band can be covered in the 40-meter range, and 12 meters falls into the 10-15 meter range.

The advantage in placing the smaller coils in parallel with the large one is that the L1/L2 turns ratio remains the same as when only the main coil is being used. L1 can be eliminated by tapping the coil six turns above the grounded end. I chose the link method because it is easier to deal with than a coil tap. I wanted to avoid the potential of shorted turns with small wire.

The main coil has an inductance of 28 µH. The effective circuit inductance is 7.5 µH when L2 and L3 are in parallel. L2 + L4 = 2.4 µH and L2 + L3 = 0.82 µH. If all four coils are placed in parallel the net inductance becomes 0.6 µH. The singular coil inductances are given in the Fig 1 caption.

SWR Indicator

You may eliminate the SWR-sensing circuit in Fig 1 if you have a separate SWR meter to use with this tuner. I included this circuit for my convenience when operating afield with QRP equipment. I did not include the circuitry for reading the forward power. My concern is for obtaining a matched condition between the transmitter and the antenna. Therefore, I need only the reflected-power information. T1 samples the RF current (reflected). D1 rectifies the current and produces a dc voltage that is indicated at M1. The ATU is adjusted for minimum needle deflection at M1. R1 is a sensitivity control that prevents the meter from reading off scale during tuner adjustments. The SWR bridge is designed for QRP operation, as shown. A transmitter power output of 1 watt or greater will provide full-scale deflection at M1.

Construction Data


Fig 2—The ATU subassembly before C1 was replaced with a small air-variable capacitor. Holes are punched in the base plate (PC board material) to accommodate the OD of the coil forms. The coils are cemented into the holes with epoxy glue. A small shelf is soldered to the base plate to allow mounting C1 and C2. A plastic block insulates C2 from ground. Wooden dowel rod is glued to the capacitor shafts to allow the use of knobs with ¼-inch holes. The ends of the dowels are ground down to a true ¼-inch diameter.

Fig 2 shows the first-run constructional detail of the coil subassembly. You will note the presence of two shaft-driven compression trimmers. I later changed C1 of Fig 1 to a small APC style air variable. This was done to eliminate mechanical problems that resulted in very "touchy" adjustment of C1. The trimmers are 10-100 pF units with 1/8-inch OD shafts.[1] I drilled holes in the ends of two ¼-inch wooden dowel rods, then glued the trimmer shafts into the dowel rods with epoxy cement. This allowed the use of standard knobs with ¼-inch holes.

Schedule-40 PVC tubing is used for the coil forms. PVC is not suitable for high-power use, since it will heat and melt in the presence of high RF voltage. PVC is entirely acceptable for power levels under 50 watts. L2 is wound on 3/4-inch PVC pipe, which has an OD of 7/8 inch. The remaining coils are wound on 1/2-inch PVC pipe (5/8 inch OD). All of the coils are mounted on the subassembly base plate by gluing them into holes (5/8 and 7/8 inch diameter) that are cut in the PC-board base plate. Epoxy cement is good for this purpose. The coils are spaced apart 1 inch, center to center. The base plate is made from double-sided PC board (2½ × 3¼ inches). The grounded ends of the coils are soldered to the base plate.

Fig 2 shows a 1½ × 2-inch shelf upon which the trimmer capacitors are mounted by means of metal L brackets. A plastic insulator is bolted to the shelf to allow C2 of Fig 1 to be isolated from ground. The PC-board shelf is soldered to the base plate, and a small triangular PC-board bracket is soldered between the bracket and base plate (at each end of the shelf) to strengthen the shelf. Two no. 6 spade bolts are used to affix the subassembly to the main chassis of the ATU. You may use brass or aluminum for the base plate and shelf if you prefer.

I made my chassis and panel from PC-board material. The sections are soldered at the joints to form the main frame. The assembled unit is shown in Fig 3. The dimensions are (HWD) 3¼ × 5¼ × 3 inches. A 1 × 5-3/8 strip of PC-board is soldered across the back of the chassis to contain J1 and J2 of Fig 1. Two strips (½ × 3 inches) are used at the sides of the main frame to serve as panel braces. I polished the copper on the PC-board material, then coated it with clear lacquer to prevent tarnishing. The panel is sprayed with gray automotive primer paint. I first sanded the panel to provide a rough surface. This helps the paint to adhere better than it would on the smooth surface. Gray Dymo™ tape labels identify the control functions. Four adhesive-backed rubber feet are affixed to the bottom of the chassis.

I used a technique that some call "ugly construction" when I built the SWR circuit. A neater job will result if you assemble the parts on a PC board, although the performance will be the same. I used a multilug terminal strip to contain most of the SWR-bridge parts. Other components have mid-air joints.

I used inexpensive slide switches for S1, S2 and S3 of Fig 1. Miniature toggle switches may be substituted, or you may prefer to use a single rotary switch, as dis-

---

[1] Notes appear at end of article.



Fig 3—Interior view of the assembled ATU. "Ugly construction" (see text) is used for the SWR-bridge circuit, lower right. The subassembly, chassis and panel are made from pieces of single- and double-sided PC board. The seams are soldered to hold the sections together.

cussed earlier. Trimmer C2 may be replaced with a 100- or 140-pF air variable. If this is done, you will need to isolate the stator and rotor from ground. The circuit will function satisfactorily if you use two 100-pF capacitors (C1 and C2).

Circuit Performance

I tested this ATU at power levels from 1 to 15 watts. I used resistive loads from 15 to 1000 ohms, and obtained an SWR of 1:1 in all cases. No arcing occurred at trimmer C2. I later connected the ATU to my 80-meter dipole (coaxial cable feed) and ran it through its paces from 80 through 10 meters. Despite the complex impedance the feed line presented above 3.5 MHz, I was able to obtain an SWR of 1:1 on all bands.

Adjustment is done by setting the coil switches for the proper amateur band. With RF power applied to the circuit, adjust C1 for the lowest SWR attainable. Next, adjust C2 slightly and readjust C1 for minimum indicated SWR. Repeat this process until the SWR is 1:1. *Caution*: Use the greatest amount of capacitance possible at C2, consistent with a 1:1 SWR. Although smaller values of capacitance at C2 will result in an SWR of 1:1, the loss through the ATU increases at such settings. All Transmatches introduce some loss, but it is insignificant (less than 1 dB normally) for the most part.

Some Final Thoughts

Keep all RF leads as short as you can. This will prevent unwanted stray inductance, which can lower the tuned-circuit Q. Long RF leads, such as those marked "RG-174" in Fig 1, should be made from coaxial cable. RG-174 is miniature coaxial line that is suitable for short runs and for power levels up to 40 or 50 watts at the lower amateur frequencies.

There is no reason why the circuit of Fig 1 can't be adapted for high-power use. The coils would need to be made with large-diameter wire, and the coil forms should have good high-voltage, low-loss properties. Lexan™ or fiberglass tubing[2] is good material for the coil forms. Surplus ceramic coil forms are also suitable. C1 and C2 of Fig 1 must have wide plate spacing for high power, since substantial RF voltage is present at the top of L2. S1, S2 and S3 need to be high-quality RF ceramic switches if QRO use is contemplated. Fair Radio Sales in Lima, Ohio sells surplus RF power switches.[3]

You may use toroidal coils for your QRP ATU. This will enable you to make the tuner smaller. For example, L2 would have 35 turns of no. 24 enamel wire on an Amidon FT-82-63 core. L1 would consist of 3 turns of no. 24 wire over L2. For L3 use 24 turns of no. 24 wire on an FT-50-63 toroid. L4 would have 23 turns of no. 24 wire on an Amidon T-50-2 toroid, and L5 would consist of 15 turns of no. 24 wire on a T-50-6 core. There is no reason why you can't design a PC board that can contain the four toroidal coils, plus the SWR bridge. This would result in a low-profile, compact ATU.

I wrote this article in order to share some old ideas that may have been forgotten by some of you. I hope you have found the circuit and construction hints interesting and useful.

Notes

[1] Trimmers with shafts are available from Hosfelt Electronics, 2700 Sunset Blvd, Steubenville, OH 43952. Sales line: 800-524-6464 (catalog available).

[2] Plastic rod, tubing and sheeting (many types of plastic) are available by UPS or truck line from U.S. Plastic Corp, 1390 Neubrecht Rd, Lima, OH 45801. Sales line: 800-537-9724 (catalog available).

[3] Fair Radio Sales, Inc, Box 1105, 1016 E Eureka St, Lima, OH 45802, tel 419-227-6573.

From* 1990 ARRL Handbook *Ch 34, p 19:

A Balanced QRP Transmatch



Fig 39 — This QRP Transmatch for balanced feed lines features a balun at the input of the matching network.



Fig 40 — Schematic diagram of the QRP Balanced Transmatch.

C1—330 pF variable capacitor, 500 V rating.
C2,C3—330 pF silver-mica capacitor, 500 V rating.
C4—600 pF silver-mica capcitor, 500 V rating.
J1—Female chassis-mount BNC connector.
J2—Two ceramic feedthrough insulators.
L1—36t no. 16 tinned wire on an Amidon T-200-6 core.
S1—Ceramic rotary switch, single wafer, 1 pole, 12 position.
S2—Ceramic rotary switch, single wafer, 2 pole, 6 position.
T1—12 trifilar turns on an Amidon FT-114-61 core; primary, no. 16 enam wire; secondary, no. 18 enam wire.

The balanced QRP Transmatch shown in Figs 39 through 41 was designed and built by Zachary Lau, KH6CP, in the ARRL Lab. It is designed for use with balanced feed lines, although random-wire antennas can be fed if one of the antenna terminals is grounded. Unlike most Transmatches designed for use with balanced feed lines, this design features a balun at the input, rather than at the output. As a result, the balun sees impedances close to the design impedances once the Transmatch has been properly adjusted. This results in lower loss and freedom from core saturation at low power levels.

Since it is balanced currents that prevent feed-line radiation, this circuit was designed to balance currents rather than voltages. Some antenna systems use circuits that provide balanced voltages, making it necessary to make the system symmetrical in an effort to balance the currents. By going straight to balanced currents, instead of balanced voltages, it is possible to use a much simpler matching network. In addition, the actual current balance in typical amateur open-wire feed lines should be improved.

Construction

The inductor L1 and the capacitor C1 should be of the highest quality obtainable for best performance. Low-impedance loads will require a good inductor for efficient matching, while high-impedance loads will require a good capacitor.

L1 was wound with tinned copper wire to make it easier to adjust taps. It is necessary to wind the wire with spaces between turns to prevent shorts which may make the inductor lossy; no. 16 wire is heavy enough to stay in position on the toroid. The inductor used had a full-inductance Q of 420 at 7.9 MHz; the Q was 410 after the taps and switch were added. The use of clip lead taps is not recommended as they increase losses, although they may be useful in initially setting up tap positions.

Capacitor C1 should have a value of at least 250 pF, and larger capacitors will work even better, increasing the range of the Transmatch at low frequencies. Suitable capacitors are usually available at hamfests. The value of C2 and C3 should equal C1, and C4 should be twice the value of C1. If the calculated values of C2, C3 and C4 are not available, smaller values may be used.

Capacitor C1 must be insulated from the chassis, so it was mounted using ½-inch Plexiglas® with tapped screw holes. An insulated shaft coupler was used to prevent high voltage from appearing on the knob set screw. The cabinet is a Ten-Tec MW-8 with a model 91-206 matching tilt-up bail. Although it is large for a QRP Transmatch, the cabinet matches the author's QRP rig and allows the controls to be spaced apart for easy use. The logging scale is typewritten paper attached to the cabinet with a Plexiglas sheet.

T1 is a trifilar-wound transformer. Winding details are shown in Fig 40. It is possible to wind this coil with only two windings, eliminating the solder joint. The coil should be duplicated exactly with regard to the number of turns and core material unless the transformer can be tested at the operating frequency. Testing can be done by hooking up two baluns in series and measuring the insertion loss. The matching network will compensate for a poor balun, but efficiency will probably suffer. A toroidal choke balun would be recommended for a higher power version.

Switches S1 and S2 should be ceramic. Phenolic switches are not recommended, although they should work at low power levels on the order of a few watts. The switch positions should never be changed while more than a few watts of RF is applied.

Adjustment

Adjustment of the Transmatch is much easier if the approximate impedance of the load is known. In his article in *The ARRL Antenna Compendium, Volume 1*, "Mr. Smith's 'Other' Chart and Broadband Rigs" Roger Ghormley, W0KK, details how parts values for L networks can be calculated. Alternately, received signals can be peaked up by first adjusting the inductor and then the capacitor. As with any Transmatch, low power should be used in the initial adjustment. The actual power handling capability will depend on the load. The capacitor breakdown voltage is the limiting factor on high-impedance loads; a 2000-ohm load will cause the 500 V capacitors to reach their maximum rating at 62.5 W, while the maximum rating will be reached with 625 watts into a 200-ohm load. The current-handling capability of the wire is the limit on low-impedance loads; a 40-ohm load will cause a 90-W signal to generate 1.5 A through the wire, while 450 watts will generate 1.5 A if the load is 200 ohms. These values are for resistive loads; a reactive load would require higher current and voltage ratings. The unit shown here has worked well in low-power operation (up to 4.5 watts).



Fig. 41 — Interior layout of the QRP Transmatch. The variable capacitor is mounted on a Plexiglas block.

From January 1985 QST, p 39:

Variable-Notch Filter for Receivers


VARIABLE NOTCH FILTER
R1A
250 k
R1B
250 k
10 k
0.0022
1 µF
35 V
INPUT
OUTPUT
0.1
U1D
U1B
U1A
U1C
VCC
GND
15 k
U1 = RC-4136
OR ECG-997
+9-15 V
SUPPLY
EXCEPT AS INDICATED, DECIMAL VALUES OF
CAPACITANCE ARE IN MICROFARADS (µF);
OTHERS ARE IN PICOFARADS (pF OR µµF);
RESISTANCES ARE IN OHMS; k = 1000

Fig. 1 — Schematic diagram of the variable notch filter that K4VIZ installed in his Kenwood TS-530. This same circuit should prove useful for other receivers. R1 is a dual, 250-kΩ, linear-taper potentiometer, such as a Clarostat D53C1-250K-S. U1 is an RC-4136, ECG-997 or equiv. quad op amp.

☐ One night before CW net time, I was tuning around the specified frequency using my Kenwood TS-530. I came across some lid giving his finals a "life test." This prompted me to think about how nice it would be to have a notch filter in the '530 similar to the one in my Ten-Tec Argosy. A variable-notch filter can be quite effective for listening to a signal that is very close to a strong, interfering station.

I checked the manual for my Argosy, and found that Ten-Tec uses a simple circuit that employs a quad op amp IC and a few resistors and capacitors. A dual-section, 250-kΩ, linear-taper potentiometer serves as the tuning control. Based on my study of the Ten-Tec circuit, I decided to use it as a basis for my modification. See Fig. 1. A circuit-board etching pattern is given in Fig. 2, and Fig. 3 is a parts-placement diagram. Notice that all resistors are mounted on end to save space and to allow for a smaller board layout. I mounted my circuit inside the TS-530 and connected it as shown in Fig. 4.

Since I never used the RF gain control on my rig, I replaced it with the notch-filter potentiometer. The Clarostat D53C1-250K-S potentiometer I used is a tight fit in the chassis hole; I had to enlarge the hole slightly to fit the bushing



Fig. 2 — Full-size circuit-board etching pattern for the notch filter, shown from the foil side. Black areas represent unetched copper.


LOW LEVEL INPUT
+ SUPPLY
OUTPUT
1 µF
10 k
U1
0.0022
15 k
R1
SUPPLY GND

Fig. 3 — A parts-placement diagram, shown from the component side of the board. Gray areas show an X-ray view of the copper pattern.

on the new control. The RF gain potentiometer is a 10-kΩ unit that I replaced with a fixed resistor.

I filed a flat on the shaft of the new control so the original Kenwood knob would fit and make the new control look like it belongs. I did not try to relabel the front panel to indicate the function of the new control. That way, I can return the rig to original form, should I ever wish to.

To mount the filter board in my Kenwood TS-530, I replaced a screw found near the edge of the audio board, between plugs 8 and 9, with a longer one. A few washers help space the filter board from the chassis. I obtained power for the filter at test point 6 on the audio board. There is a small, red coaxial cable coming from the top side of the rig and going behind the VFO. This cable carries the audio from the detector to the audio amplifier. Cut this cable and connect it to the input and output pads on the filter board, as shown in Fig. 4.



Fig. 4 — Inside view of the Kenwood TS-530 showing the notch-filter wiring and mounting.

Four small wires connect the filter to the dual potentiometer on the front panel. You will have to remove the screws holding the audio board so you can lift it out of the way while replacing the RF gain control. The front panel will have to be removed to get at the nut that holds this potentiometer in place; that involves removing four screws.

With the control turned fully clockwise, the notch frequency is about 2800 Hz; it is about 300 Hz when fully counterclockwise. Both these frequencies are nearly out of the Kenwood audio system passband. When you don't need the filter, just set it to one end or the other.

I have found this to be a worthwhile project and a handy addition to my rig, especially for CW operation. You should be able to complete the modification in an evening or two. Actually, the task sounds worse than it is! It took more time to type it up than to perform the operation. One word of caution: Wire the new control so that maximum resistance on both potentiometer sections occurs when the shaft is rotated counterclockwise. — *Tom Desaulniers, K4VIZ, POB 1026, Leeds, AL 35094*

From April 1977 QST, p 57:

Simplified Output Metering Protects QRP Transmitters



Protective circuit for QRP transmitters.

After destroying a few transistors while tuning QRP transistors into a mismatched load, I decided I needed some way to indicate proper transmitter adjustment, and then protect the rig while the antenna tuner was adjusted. An adaptation of the simple resistive SWR bridge described in the ARRL *Handbook* provides me with a dummy load, relative power-output indicator and a safe method of tuning the transmitter.

As shown in the schematic diagram, the input divider (R1-R4) has a total resistance of 50 ohms. Four 1/2-watt composition resistors safely dissipate the output of my transmitter when S1 is in the TUNE position. Meter M1 indicates relative power applied to this load. The antenna is connected (through a Transmatch) and the antenna tuner is adjusted for minimum deflection on S1, or lowest SWR. R5 acts as an attenuator and effectively isolates the transmitter from the antenna, preventing possible damage to the output transistor of the rig. When the SWR has been reduced to its minimum, S1 is placed in the OPERATE position. M1 now indicates relative power output into the antenna. CR1 may be any germanium signal diode; C1 is either a ceramic-disc or silver-mica capacitor. S1 should be a ceramic rotary switch (dpdt), although a phenolic rotary switch or a slide switch is adequate for use on the 80-meter band. — *Albert S. Woodhull, N1AW, ex-W1GSJ, POB 843, Amherst, MA 01004*

From June 1985 QST, p 39:

An Accurate, Inexpensive Frequency Marker


U1D
9
8
470 k
U1A
1
2
14
7
U1B
3
4
U1C
5
6
U1E
11
10
100 kHz OUT
5 V
0.01
*
C1
220 k
U1F
13
12
Y1
100 kHz
* - SEE TEXT
220 k
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF) ; OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS ; k = 1000
U1: CD4069

Fig. 3—A schematic for the frequency marker. U1 is a CD4069, or equivalent, CMOS hex inverting buffer. Y1 is a 100-kHz CX-1H crystal from Statek.


1.35"
1.05"
1.30"
1.60"
1"
(25.4 mm)

Fig. 4—Full-size circuit-board etching pattern for the frequency marker, shown from the foil side. Black areas represent unetched copper.


OUTPUT
+ SUPPLY
SUPPLY GND
0.01
U1
1
Y1
470 k
220 k
220 k
C1

Fig. 5—A parts-placement diagram, shown from the component side of the board. Gray areas show an X-ray view of the copper pattern.

☐ A highly accurate series oscillator can be constructed from seven components for about $10. The marker is based on the model CX-1H quartz crystal, which is a tuning-fork resonator manufactured by the Statek Corporation.[1] Statek produces these crystals for use in quartz watches and they have a frequency tolerance of ±0.005% at 25° Celsius. The modules cost about $6 each.

A schematic of the frequency-marker circuit is shown in Fig. 3. It consists of three cascaded inverters and three parallel buffer inverters. The entire circuit can be etched on a 1.6- × 1.3-inch board, as shown in Fig. 4. (Fig. 5 is a parts-placement diagram for the circuit.) I used the components specified by Statek and the marker oscillated at 100.0015 kHz. [Larry Wolfgang, WA3VIL, used a "gimmick" capacitor for C1 in the frequency marker he built in the ARRL lab. The gimmick is two wires of a no. 24 AWG ribbon cable. Start with the wire somewhat longer than 3½ inches, connect the output of the frequency marker to a frequency counter, and trim the gimmick wires until the marker is on frequency.—Ed.] Since the nominal frequency of the crystal is 100.00 kHz, the measured frequency is within the quoted tolerances.

The oscillator provides an ideal frequency check for the Argonaut and other radios that lack an internal frequency marker. Statek manufactures the CX-1H crystals and provides circuit component values for frequencies from 10 to 600 kHz. Thus, most HF receiver calibration can be accomplished with this inexpensive and easy-to-build circuit.
—*Michael C. Schell, KF8CZ, 7647 White Oak Dr, Solon, OH 44139*

---

[1] The CX-1H is available from Statek Corp., 512 N. Main St., Orange, CA 92668, tel. 714-639-7810.

From January 1987 QST, p 27:

Some Power-Supply Design Basics

Part 15: Know your components and how to apply them correctly when designing a ham-shack power supply. Failures can be avoided and performance may be improved by observing some basic rules.

By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250 Luther, MI 49656



Let's think about power supplies in a practical way. I'll leave the exacting design information in the closet for this discussion. Those of you who want to dig deeper may consult the power-supply chapter of *The ARRL Handbook*, or such references as National Semiconductor's *Voltage Regulator Handbook* (1982). The latter publication contains several power-supply design application notes, along with countless equations for obtaining precise performance results.[1]

Rectifier Circuits

What are our choices for rectifier circuits, and what are the advantages and limitations of the various configurations? Fig 1 shows some of the possibilities we might consider. The most basic hookup we may use is shown at A of Fig 1. Here we have a half-wave rectifier with a single diode (D1) and filter capacitor (C1). The circuit simplicity is appealing, but regulation is very poor and the output ripple is high and hard to filter, compared to other circuits. Peak dc voltage across the diode may rise to 2.8 times the transformer secondary voltage (RMS) under no-load conditions with a capacitor filter. Conversely, the average output voltage, without filtering (under load) will be on the order of 0.45 times the T1 secondary voltage. The high no-load peak voltage, when filtered, results from C1 being charged. This stored voltage is then added to the peak voltage from the T1 secondary. These traits make the half-wave power supply suitable for low-current needs, such as bias supplies, but not for high-current applications.

A better scheme is shown at Fig 1B. Here we find the familiar full-wave rectifier. A center-tapped transformer is required, and the total secondary voltage must be twice that for a full-wave bridge circuit (C) for a specified dc-output voltage. The average output voltage from the diodes is 0.9 times half the RMS secondary voltage of T1. The peak output voltage (when using a capacitor-input filter, C1) is 1.4 times the T1 secondary voltage. Compared to the half-wave rectifier, this circuit requires less filtering because the output-pulse frequency is twice that of the half-wave rectifier. Also, each diode (D1 and D2) needs to accommodate only half the current taken by the load. This is because the diodes operate alternately at half cycles of the ac. The diode of circuit A must handle all of the load current.

Fig 1C shows the more common full-wave bridge rectifier. The principal advantage here is that no secondary center tap is required for T1. D1 and D3, in effect, provide the missing center tap. In this example two rectifiers operate on each half of the ac cycle. The average and peak output voltages for this circuit are the same as for the full-wave rectifier at B. The diodes should be rated for at least half the current taken by the load.

There are times when we need a plus and minus output voltage from a power supply. A simple method for obtaining the two equal voltages of opposite polarity is illustrated in Fig 1D. This dual-complementary rectifier requires a center-tapped transformer with twice the RMS secondary voltage of that for the full-wave circuit at C. You may think of this supply as two sections of the full-wave circuit of Fig 1B. The notable difference is that two extra diodes are added (D3 and D4). They are connected for the polarity opposite that of D1 and D2. Peak and average dc output voltage is the same as that for circuits B and C of Fig 1.

---

[1] National Semiconductor Corp, 2900 Semiconductor Dr, Santa Clara, CA 95051.

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.



Fig 1—Conventional circuits for power-supply rectifiers. A discussion of these circuits is contained in the text.

Diode Selection

Earlier we discussed diodes that must handle one half the power-supply load current. That is the *minimum* requirement. We need to consider peak currents when choosing our rectifiers. Using diodes that have marginal ratings for the intended application has caused many an amateur to scratch their head in wonderment after witnessing the failure of brand new replacement diodes in a repaired power supply! Be aware that the RMS current flowing into a capacitor-input filter is *two* to *three* times the dc output current. This is because the current is delivered in short pulses. A good rule of thumb (call it empirical if you wish!) is to use diodes rated at no less than twice the output current taken by the load. This allows ample leeway for the surge current of the power supply and has always provided reliability for me.

We must consider also the PIV (peak inverse voltage) or PRV (peak reverse voltage) of the diode we select. Earlier we learned that the peak voltage for a capacitor-input filter can rise to 2.8 times the RMS value of the transformer secondary winding. Therefore, our diodes should have a PRV rating of approximately three times the peak voltage value. If the transformer secondary RMS voltage is 12, the rectifier diodes should have a rating of 36 volts or greater. When building high-voltage power supplies, such as 2 kV, several 1000-PRV diodes must be connected in series in each leg of the rectifier in order to accommodate the high PRV. Equalizing resistors and capacitors are connected in parallel with each diode (as shown in the *The ARRL Handbook*) to equalize the voltage drop across each diode.

Choosing a Filter Capacitor

Amateurs tend to regard the filter capacitor as a casual matter. Why not simply use what is on hand in the junk box? Perhaps a randomly chosen capacitor value will provide adequate results, assuming output ripple is not a major consideration, and if the capacitor voltage rating happens to be sufficient. But what of optimum performance? Well, there is a simple equation we may apply for low current power supplies when we are in doubt about the best type of capacitor to employ:

$$C_{\mu F} = \frac{I_L}{E_{P\text{-}P}} \times 6 \times 10^3 \qquad \text{(Eq 1)}$$

where I_L is the dc load current and E is the desired P-P output ripple voltage at 120 Hz. The P-P ripple voltage may be measured at the regulator output, under normal current load conditions, with a scope.

Using Eq 1, we determine that a 3000-µF filter capacitor is required for a 1-A load current (12-V output), when the desired output ripple (under load) is 2 V P-P. Keep in mind that the values obtained from Eq 1 are based on the assumption that a regulator follows the filter capacitor: The regulator provides additional electronic filtering. The 3000-µF filter capacitor in the foregoing example should have a minimum rating of 36 V.

How about the Transformer?

A vital consideration when designing a power supply is that of the transformer rating—notably the secondary-current specification. Industrial design calls for some rather complex mathematical gymnastics, but we can follow a practical path when choosing the transformer we need for the job. Let's assume that we are using only the capacitor-input filter scheme, since it is more common and less expensive than the choke-input format. Based on this assumption our transformer secondary-current rating should be approximately 1.2 times the full-load dc current of the supply when using a full-wave, center-tapped rectifier (Fig 1B). Thus, for a 2-A maximum load current the transformer secondary should have a minimum rating of 2.4 A (1.2 times the load current).

If we are using a full-wave bridge rectifier, the T1 secondary current minimum will be 3.6 A for a 2-A load (1.8 times the load current). Some amateurs have tried to use a 2-A transformer for a 2-A load, as an example, only to find that the transformer operated quite warm (even hot!), and the output had substantial ripple under full load. If we take care in selecting our transformers, we will avoid these ailments. Make-do measures and junk-box components are not truly applicable when building a power supply.

Applying Regulators

Modern amateur equipment requires regulated dc operating voltage. The power supplies we have considered thus far are suitable for operating low-current devices or circuits that draw a steady current. When there are changes in load current, it becomes necessary to regulate the output voltage to ensure that the correct and safe operating voltage is present. Furthermore, the power supply should be relatively immune to momentary current overload and short circuiting. Present-day three-terminal regulator ICs offer the foregoing features. Many are capable of shutting themselves down when excessive current flows, which in turn protects the regulator, the attached equipment and the power-supply components.

Four basic considerations exist for selecting a regulator: (1) the maximum required output current; (2) required output voltage; (3) unregulated input voltage; and (4) ambient temperature. When you know the answers to items 1 and 2, you may consult the manufacturer's data sheets and make a device selection. Always choose a regulator that has a power dissipation (P_D) greater than the maximum load current presented by your equipment. Fig 2 shows some simple circuits for three-terminal regulators. The example at A represents a standard fixed-voltage regulator. ICs are available for various standard output voltages at various maximum-current ratings, such as 5 V, 8 V, and so on. They are also available for positive or negative power supplies. Fig 2B shows a typical adjustable regulator of the type that might



Fig 2—Circuits for three-terminal regulator ICs. These circuits are explained in the text.

be used for a bench supply. An adjustable regulator with protective diodes (D1 and D2) is shown at C of Fig 2. The diodes are recommended when the output capacitance (C1) is 25 µF or greater. This may be the situation when the equipment used with the power supply contains a high-value filter capacitor at the voltage-input terminal. The low internal resistance of the capacitor can cause high-amperage spikes when shorted (in excess of 20 A), and this can destroy the regulator IC. D1 protects U1 against input short circuiting (C1), and D2 protects U1 against output shorting (C2). Under the respective shorting conditions, C1 and C2 will discharge through the IC and destroy it.

We frequently need greater output current than a three-terminal regulator can provide. The solution to our problem is found in the circuit of Fig 2D. Q1 is a wrap-around pass transistor which handles the high current that U1 cannot accommodate. Several pass transistors may be used in parallel to increase the current rating of the regulated supply. Design information relating to this subject may be found in the 1987 edition of *The ARRL Handbook*, page 27-23.

At the start of this section we considered four items in selecting a regulator. No. 3 deals with the unregulated input voltage. Most manufacturers rate their regulators for maximum safe input voltage for fixed-voltage regulators that use ground as a reference. The maximum input-output voltage differential is used for adjustable regulators that do not use ground as a reference. This is sometimes specified as "input-output voltage differential." For example, Fig 2A has a "differential" of 7 V between pins 1 and 2 of the regulator, U1. The greater the input voltage, respective to the regulated output voltage, the higher the power dissipation within the regulator. Unnecessary power dissipation inside the IC requires greater heat sinking in order to keep the regulator within safe ratings. An example of wasted power and increased heat is seen when an input voltage of 25-28 is used for a 12-V regulated supply. A better input-voltage value is 18-19 V.

Item 4 relates to the ambient temperature of the regulator IC. This concerns item no. 3 and the size of the heat sink we employ. Thermal considerations represent a rather exact science that includes the junction temperature of the regulator. Another complex factor is the thermal resistance of the bond between the device and the heat sink. In any event, the regulator IC and the heat sink should never be more than comfortably warm to the touch after a period of full-load current flow. When in doubt, choose a heat sink that is larger than your intuition suggests. Be sure to use a *thin* layer of heat-sink compound (available at Radio Shack) between the regulator IC and the heat sink. The mounting screws should be snug but not too tight. Excessive torque may distort the IC and weaken the thermal bond, and it might even cause internal damage to the IC!

We must also be concerned about the operating temperature of the rectifier diodes. When large currents pass through the diodes, it becomes necessary to use heat sinks to keep the diodes cool. Bridge rectifier modules (four diodes encapsulated in a plastic block) lend themselves nicely to heat sinking. This is not true of plastic encased single diodes. Stud-mount, discrete-diodes are more suitable for use with a heat sink. In any event, the rectifier diodes, under full load, should never become hot to the touch.

A Practical Regulated Supply

Let's assemble the suggestions in this article and apply them in a small regulated supply that is aimed especially at the QRP operator. Fig 3 shows the circuit for a 1.5-A, 12-V regulated dc power supply. The component ratings are based on the guidelines given earlier.

Some additonal parts appear in the diagram of Fig 3. They include C1-C4, inclusive, and RFC1. These units have been added to prevent unwanted common-mode hum in direct-conversion receivers. This malady is caused by RF energy from the receiver local oscillator (radiated by the antenna and power-supply leads) reaching the rectifier diodes. The RF energy is then modulated by 120-Hz energy and reradiated. It is picked up by the antenna and heard as a hum in the D-C receiver. C1-C4, inclusive, bypass the rectifier diodes at RF, thereby preventing them from acting as mixers or modulators. In effect, the capacitors provide an RF-current short across each diode.

As a further aid in solving the hum problem, we have included RFC1. It is a toroidal bifilar RF choke that prevents RF energy from entering the power supply via the power-supply leads. This preventive measure was first introduced by Wes Hayward, W7ZOI. I have found it to be effective with such transceivers as the HW-7 and HW-8. The bypass capacitors across the transformer primary winding


C1 0.01
F1
1A
S1
ON
0.005
1kV
0.005
1kV
117 V
AC
T1
18 V
D1
D2
D3
D4
C2
0.01
0.01
C3
C4 0.01
D5
U1 LM340-12
REG
IN
OUT
GND
1
2
3
+
1000 µF
50 V
0.1
0.1
RFC1
+
−
12 V,
1.5 A
REG
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (µF); OTHERS ARE IN PICOFARADS (pF); RESISTANCES ARE IN OHMS; k = 1000, M = 1 000 000.
U1
BOTTOM
VIEW
3
1
2
(CASE)

Fig 3—Schematic diagram of a practical 12-V, 1.5-A regulated dc power supply. Components C1-C4, incl, and RFC1 may be omitted if this circuit is not for use with a direct-conversion receiver (see text). Capacitors are disc ceramic except for the one with polarity marked, which is an electrolytic. All diodes are 3 A, 50 PRV or greater. RFC1 has 15 bifilar (parallel) turns of no. 14 enam wire on an Amidon Assoc FT-114-43 toroid core (1.14-inch-OD core with 850 μ_i). T1 has an 18-V secondary at 3 A or greater. U1 is a National Semiconductor Corp 12-V positive regulator in a TO-3 case. D1-D4, incl, may be a full-wave rectifier block (use heat sink here and on U1); see text.

also aid in keeping RF energy out of the power supply.

I recommend a modular bridge rectifier for D1-D4, inclusive. It should be mounted on a heat sink that is approximately 2 to 3 inches square. A 3-inch-square finned heat sink should be ample for U1.

Some Final Thoughts

We have merely agitated the surface in our basic look at power supplies. A lengthy book is needed to cover the subject properly. But, perhaps this article can provide some of the answers you have needed to fundamental questions about power supplies and the ratings of their component parts.

A number of regulated power supplies are described in detail in the 1987 edition of *The ARRL Handbook*. Additional design data may be found in the publication referenced in note 1.

From September 1989 QST, p 22:



A 1.25- to 25-V, 2.5-A Regulated Power Supply

Let's discuss the practical aspects of a test-bench power supply that's easy to build and get working. Most of the parts are available as surplus.

By Doug DeMaw, W1FB
ARRL Contributing Editor
PO Box 250
Luther, MI 49656

I needed a regulated 24-V power supply for development work with power FETs, but my lab supply could not deliver the current required because it provides a maximum of only 1.5 A. My work called for a current range from 2 to 2.5 A. Although I found a number of surplus fixed-voltage power supplies offered at modest prices, they were not variable-voltage units, and they qualified for the "boat anchor" weight class! I chose a typical amateur solution: build the power supply and make it compact.

This article covers the essentials of a simple power supply that you can duplicate in a few evenings. It can be expanded easily to deliver greater output current. The heart of this power supply is contained on a PC board that is available from FAR Circuits.[1] In fact, most components are available from mail-order houses.

Circuit Details

Fig 1 shows the circuit for my supply. The components marked with a double asterisk are external to the PC board. I recommend that you read the *ARRL Handbook* (1989 or other recent editions) for an explanation of how regulated power supplies operate. See pages 27-12 and 27-13 for a design description of a similar power-supply circuit.

T1 is chosen for the voltage and current you require. You can use a 24-V transformer if you can work with a voltage range of 1.25 to 24. Select a transformer that can deliver 0.5 A or greater current than the maximum direct current you need. Likewise, use rectifier diodes that are rated for substantially more direct current than the supply will deliver. The PIV rating should be at least twice the secondary voltage of T1. U1 is a rectifier module that contains four 6-A, 200-PIV diodes in a full-wave bridge hookup. U1 is mounted on a small heat sink. I used a Thermalloy 6118B that is sold by BCD Electro.[2] The heat sink helps to keep the diodes from overheating when heavy current is flowing.

DS1 is a red LED that serves as the POWER ON indicator. You can replace the LED with a 28-V pilot lamp. If so, eliminate R10. By placing the LED or lamp in this part of the circuit, you will always know if the fuse, T1 and U1 are functional.

R1, R2 and R7 can be wound from no. 28 enamel wire on insulated forms, such as the body of a 10-kΩ, 1-W carbon resistor. You will need an accurate way to measure the wire resistance if you do this. These resistors are available from Mouser Electronics.[3]

U2 is a 1.25 to 30-V, 1.5-A three-terminal positive regulator. This device is also mounted on a small heat sink. I used a Thermalloy no. 6098 that I obtained from All Electronics Corp.[4] You can build your own heat sinks from 16-gauge aluminum or brass. Form U-shaped channels that are approximately 1-1/2 inches square by 5/8 inch high.

Q1 is a PNP (TO-204 case) power transistor. I recommend a Radio Shack® MJ2955 or RCA SK3335 transistor. These have a 150-W rating. The emitter and base pins are bypassed to ground at the pins by means of C7 and C8 in Fig 1. This is a preventive measure against instability, owing to the long leads between Q1 and the PC board. You can parallel two or more pass transistors to increase the output current of the supply. Each pass transistor provides an output-current increase of approximately four times that of U2. The single device at Q1 in Fig 1 ensures an out-



Internal view of the assembled power supply. The chassis and panels are made from single-sided PC board. The circuit board is mounted vertically to conserve space.

[1] Notes appear at end of article.


Pass Trans
**
E
C
B
Q1 *
MJ2955
**
C7
0.1
10
1 W
R3
C8 **
0.1
Bridge
Rect
3.1
5 W
R1
U2
LM317T *
120 V
ac
0.01
1 kV
C1
0.01
1 kV
C2
**
T1
25.2
V
U1
6A *
0.33
1/2 W
D1
R2
2200 µF
50 V
C3
3
IN
Reg
OUT
ADJ
2
1
C4
0.1
D2
R7
0.1
5 W
**
J1
+
1.25–25 V
(2.5 A)
–
J2
**
F1
1.5 A
**
S1
POWER ON
**
2.7 k
1/2 W
** DS1
C5
10 µF
50 V
R5
120
1/2 W
R6
1 k
2 W
C6
47 µF
50 V
5 k
2 W
R4
ADJUST
(Voltage adj)
Q1
TO-204
C
E
B
C
Bottom
View
U2
TO-220
2
1
2
3
Front
View
Except as indicated, decimal values of capacitance are in microfarads (µF); others are in picofarads (pF); resistances are in ohms; k=1,000.
* Heat Sink
** External to PC board
R8
500
1/2 W
R9
50 k
1/2 W
M1 **
mA
0–1
–
+
0–5 A
0–50 V
S2A
**
S2B

Fig 1—Schematic diagram of the 1.25- to 25-V regulated power supply. Capacitors are disc ceramic except for those with polarity marked, which are electrolytic. See text for data concerning heat sinks for Q1, U2 and U3.

D1, D2—1-A, 100-PIV rectifier diode.
DS1—Red LED.
F1—1.5-A, 3AG fuse in chassis-mount holder.
J1, J2—Standard five-way binding post, one red, one black.
M1—Milliammeter, 0-1 mA dc (see Notes 5 and 9).
Q1—PNP power transistor MJ2955 (Radio Shack) or equiv device with a +70-V, 10-A, 150-W rating in a TO-204 case.
R1, R2, R7—5-W wire-wound resistor. See Notes 3 and 4 for source. Or, use 17 inches of no. 28 enam wire, single-layer wound, on a 10-kΩ, 1-W carbon-composition resistor for R1 and R7. For R2, use 36 inches of no. 30 enam wire on a 10-kΩ, 1-W carbon-composition resistor (scramble wound).
R4—Panel-mount, 5-kΩ, 2-W or 5-W potentiometer, carbon or wire wound (see Note 8).
R8, R9—See text.
S1—SPST toggle switch.
S2—DPDT toggle or rotary wafer switch.
T1—25.2-V, 2.75-A power transformer (see text).
U1—6-A, 200 PIV bridge rectifier with heat sink. See text.
U2—LM317T +1.25- to 30-V, 1.5-A TO-220 regulator. Use an LM317HVK (TO-204 case) for dc output voltage greater than 40. See text.

put current of 5 to 6 A if the transistor has a large enough heat sink to remain at a safe operating temperature. If you use additional pass transistors, you will need to replace T1 with a heftier transformer.

Output voltage and current monitoring is done with a 0-1 mA meter (M1). I used a surplus meter I had available, hence the additional scales on the meter face. A suitable 2¼- × 2-inch meter can be purchased from Dick Smith Electronics.[5] The voltage drop across R7 indicates the current being taken by the load. R8 allows M1 to read 0.5 V full scale, which corresponds to 5 A of current through R7. R9 permits the meter to read 50 V full scale. Try to use 1% resistors for R7, R8 and R9 for best meter accuracy. I used two 1-kΩ, ¼-W resistors (5% tolerance) in parallel for R8 and two 100-kΩ, ¼-W resistors in parallel at R9. R7 in my unit is a 3% resistor. The accuracy of the readings is satisfactory for my work.

You can lift J2 above chassis ground if you want to extract negative voltages from the power supply. A third binding post can be added (common to the chassis) for connection to J1 or J2, depending on the desired polarity. If this is done it will be necessary to bring all of the negative circuit leads to a bus that connects to J2, except for C1, C2, C7 and C8.

Construction Notes

The photograph shows the interior of my power supply. I used an old cabinet that a welder friend had made for me some 25 years ago. The chassis and panels are made from single-sided PC-board material (metal side in). The mating surfaces are soldered together. I used gray automotive primer as the undercoating for the cabinet, then sprayed it with clear lacquer. The panel has gray primer for the undercoating and white spray enamel as the finish coat. Clear lacquer was sprayed over the white panel after the decals were added. The cabinet dimensions are (HWD) 6 × 6 × 8 inches.

You can see in the photograph that the PC board is mounted vertically to save space. It is held in place by an L-shaped aluminum bracket. Q1 and its heat sink are attached to the rear outer wall of the chassis assembly. My heat sink is a surplus extruded type, measuring 3½ × 3¾ × 1 inch. I do not recommend a Q1 heat sink that is smaller than 13 square inches by 1 inch thick. Larger heat sinks will provide added Q1 protection. A hefty heat sink is available from Dick Smith Electronics (no. DS-H3471).[6] The photograph shows a thick heat sink with fingers. It was replaced by a heavier, extruded unit of the type just mentioned, owing to excessive Q1 heat during high-current periods. John Meshna Jr, Inc lists a dual TO-3 (TO-204) heat sink (no. SP-58A-28) that is suitable for one or two pass transistors.[7]

You may find that R4 and R6 are difficult to locate. Wire-wound or high-wattage carbon potentiometers are scarce items on the surplus market. I was able to find a 2-W


SEC
AC
T1
PRI
AC
AC
T1
SEC
+
+
−
W'FB 2.5A
POWER
SUPPLY
1 INCH

Fig 2—Circuit-board etching pattern for the power supply. The pattern is shown full size from the foil side of the board. Black areas represent unetched copper.

(5-kΩ) control in the Jameco catalog (no. CMU-5021).[8] It is a chore to locate 2-W carbon resistors. If you can't find the proper unit for R6 of Fig 1, you can parallel two 2.2-kΩ, 1-W resistors.

As mentioned earlier, most of the parts for this project can be purchased by mail. The LM317T, for example, is available from the suppliers listed in Notes 2, 4 and 5. U1 can be purchased from BCD Electro (see Note 2) or from Mouser Electronics (no. 33BR062—see Note 3). C3 can also be obtained from Mouser (no. 20NR905). I purchased T1 from Electronic Surplus, Inc (no. 767B11).[9] If you desire an output voltage greater than 25, you can buy a 32-V, 3.5-A transformer from Fair Radio Sales (no. X5157308).[10] The increased dc voltage (46 V maximum) will require that you replace U2 of Fig 1 with an LM317HVK, which is supplied in a TO-204 case. The use of this IC requires a modification of the PC board in Fig 2.

You can buy a modestly priced 0-1 mA dc meter from Fair Radio Sales, which offers a 3½-inch round unit that has a 0-50 scale (ideal for this project). The cost is $5 at this writing.

Be sure to use a thin layer of heat-sink compound or silicone grease between Q1, U1 and U2 and their respective heat sinks. Affix the three devices firmly (but not excessively tight) to the heat sinks. Too much tension causes stress that can damage the semiconductors.

Use 16- or 18-gauge insulated hookup wire between the T1 secondary and the PC board, and likewise between J1 and the PC board. This will minimize unwanted voltage drops through these wires. Also, use insulating hardware to isolate Q1 and U2 from their heat sinks, unless the sinks are "floated" above chassis ground. Radio Shack has insulating kits (no. 276-1371 for Q1 and 276-1373 for U2).

A scale PC-board etching pattern is shown in Fig 2. A parts-placement guide is provided in Fig 3 (see Note 1).

Summary

Many hams have told me they don't build equipment because "It's impossible to find the parts." Perhaps the references

Fig 3—Parts-placement guide for the circuit board, not to scale. Parts are placed on the nonfoil side of the board; the shaded area represents an X-ray view of the copper pattern. Component outlines are not necessarily representative of the shapes of the actual parts used.


to DS1 cathode
to DS1 anode
R10
+
C3
-
U1
and heat sink
T1 SEC
C1
T1
PRI
T1
to S1, F1
and 120 V ac
T1 SEC
C2
to S2A
to S2B
S2
R9
R7
to J1
to J2
+
-
R2
R1
S1A GND
to S2B
R8
C6
Note: C3 pads available for axial or radial capacitor
C7, C8—on Q1 heat sink (see text)
D1
R6
R3
B
E
C
R5
D2
C5
to R4
C4
U2
and heat sink
to Q1

in this article will make your job easier—and they should also be useful when searching for parts to use in other projects.

The maximum recommended load current versus output voltage for the circuit in Fig 1 is 500 mA (1.5 V), 750 mA (6 V), 1 A (9 V), 1.5 A (12 V), 1.75 A (18 V), 2 A (20 V) and 2.5 A (25 V). These figures are for steady-state load current. For intermittent loads, such as for CW and SSB transmitters, the current maximums can be increased 25 to 30 percent, assuming a typical duty cycle during transmit.

This power supply is certainly suitable for uses other than a test-bench unit. It can be used to operate a low-power VHF transceiver or homemade QRP gear, or as a battery charger. Good luck and have fun!

Notes

[1] FAR Circuits, 18N640 Field Ct, Dundee, IL 60118, tel 312-426-2431, evenings. Price: $0.50 (includes shipping to US addresses).

[2] PO Box 830119, Richardson, TX 75083-0119, tel 214-343-1770 (catalog available).

[3] Mouser Electronics, PO Box 699, Mansfield, TX 76063, tel 800-346-6873 (catalog available).

[4] All Electronics Corp, PO Box 567, Van Nuys, CA 91408, tel 800-826-5432 (catalog available).

[5] Dick Smith Electronics, PO Box 468, Greenwood, IN 46142, tel 317-888-7265 (catalog available).

[6] See Note 5.

[7] 19 Allerton St, Lynn, MA 01904, tel 617-595-2275 (catalog available).

[8] Jameco® Electronics, 1355 Shoreway Rd, Belmont, CA 94002, tel 415-592-8121 (catalog available).

[9] Electronic Surplus, Inc (formerly R&D Electronics), 1224 Prospect Ave, Cleveland, OH 44115, tel 216-621-1052.

[10] Fair Radio Sales Co, PO Box 1105, 1016 Eureka St, Lima, OH 45802, tel 419-227-6573 (catalog available).

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.

From September 1987 QST, p 17:

Alternative Energy—An Overview of Options and Requirements

Part 1: Planning on operating far from the power grid? You *can* have the electrical energy you need when you need it, but it takes a systems approach. Here's a look at how to pull energy from sun, water and wind.

By Michael Miceke, WB6EER
Box 123
San Simeon, CA 93452



Miles from commercial electric energy, Mike Mideke's experimental 1750-meter beacon has chugged along on solar power since 1984. The antenna is an 18-foot vertical. *(photos by WB6EER)*

Radio amateurs have always found many reasons to operate beyond the power lines. Field Day, DXpeditions, mountaintopping for the sheer fun of it, emergency work from disaster sites where power is out, and from wildfires in places where power lines have never run—all of these situations call for portable and more or less independent energy resources. Some amateurs find themselves spending long periods in locations far beyond the reach of commercial energy distribution. Others need to operate repeaters or remote equipment in places where commercial energy is either unavailable or unreliable. Still others find themselves caught up in the challenge of developing their own energy resources although they have perfectly good ac available in their wall sockets.

I suspect that the term "alternative energy" evokes quite a variety of responses and definitions in the minds of *QST* readers, so before moving into the subject proper, I'll discuss my personal definition of the term and where I stand in relation to this exciting field.

In my opinion, energy alternatives are those that provide electrical or other energy in some fashion not directly connected to commercial generation and distribution networks. If you buy a gasoline-powered generator and fuel to operate a Field Day rig, I think it is stretching things a bit to say that you're using alternative energy. If, however, you modify the generator to operate on methane, alcohol or wood, and then proceed to produce the fuel before going on the air, *then* you're on alternative power!

A combination of random circumstances moved me beyond the reach of power and telephone lines in 1969. Somehow, I have never gotten back to "civilization," except as a visitor. An addiction to personal comfort, late night reading and a variety of technical hobbies all combined to motivate my alternative energy efforts, so I now find myself operating on a mixture of solar, hydroelectric and internal-combustion-derived electricity. My commercial energy source is a 2.5-kW Onan power plant attached to a 250-gallon propane tank. The tank is topped off once a year. This generator sees limited duty, operating a washing machine once a week, a 16-mm movie projector on rare occasions, and power tools once in a while, as needed.

The combined solar and hydroelectric operations provide power for lights, amateur and experimental radio stations, soldering irons, an electric typewriter and other apparatus. The economics of our situation dictate a piecemeal approach, with maximum emphasis on scrounging, salvage and modification of available devices. My family and I know we'll find plenty of uses for all the energy we can afford to produce or store. At the same time, however, we organize our activities around whatever energy happens to be available at any given moment. Present solar capacity at the homesite is 90 W peak. Maximum hydroelectric capacity is around 300 W. Full hydroelectric potential is generally available from December through

May, while solar input is best from May through August. Some conservation measures are generally required from September through mid-November.

Are we self-sufficient? By no means! Full energy self-sufficiency is not a realistic concept as applied to alternative energy users. No matter how we generate and store electricity, we are ultimately dependent upon energy-intensive technologies to provide our essential hardware. Nor does alternative energy mean free energy. In most cases, cost per watt-hour (Wh) is substantially higher than commercial power. The exceptions are efficient systems that can operate for a long time (decades) at minimal cost above the initial installation expenses.

The effort necessary to achieve any degree of energy self-sufficiency almost inevitably leads to some realization of how much power a person or family really *needs* in order to live comfortably: generally, quite a bit less than the average user of "cheap" commercial power consumes. Thus, even in the short term, a small quantity of expensive power may be just as satisfactory as a lot of cheap power: Wise use of a scarce resource can be as effective as luxurious use of an abundant resource.

Achieving energy self-sufficiency engenders an awareness of the degree to which the global population is becoming ever more dependent upon the electrical power network. This potent but fragile network is, to a distressing degree, taken for granted by its users. When we build our own power systems, we come to better appreciate both our needs for electrical energy and the awesome scope and complexity of the commercial systems that are a cornerstone of modern civilization.

Milking a Herd of Cars

Many of us have participated in mobile Amateur Radio operation, mainly from vehicles using 12-V electrical systems. Most vehicular electrical systems have sufficient capacity to operate a wide range of solid-state equipment with little or no modification to the power source. Does this mean that the nearest car or truck is an alternative energy source just waiting to be tapped?

Whether we consider vehicles to be a valuable source of alternative energy depends somewhat upon how we look at them. Viewed *as a resource*, motor vehicles are ubiquitous. They have on-board energy production, storage and regulation systems. Viewed purely as an electrical energy source, they are dreadfully *inefficient*. Even so, in certain types of emergencies, motor vehicles may provide the best (or only) short-term source of electricity. Further, the family car can be milked for a fair amount of battery charging, though at some reduction in gas mileage—not a particularly efficient source of energy, but a source nonetheless.

Automotive electrical systems are valuable in alternative energy production for another reason: Their components may be used in *long-term* energy production. Automotive storage batteries (and their relatives) may be the first such components that come to mind, but the list doesn't stop there. In my small hydroelectric installation, I get thousands of hours of service from used alternators purchased cheaply in scrapyards. They don't last forever, but with a typical life of three to four years, the annual cost of one alternator is under $5.

Short- or Long-Term Energy Needs?

If alternative energy signifies independence from the mains, *how long* must that independence be maintained? Will an alternative energy system serve only during emergencies and self-initiated portable/mobile stints, or will it be part of your way of life—perhaps permanently?

With NiCd battery packs and chargers available almost everywhere, much portable Amateur Radio operation can almost be considered an extension of the power lines. Potentially, if not always in fact, portable work goes well beyond this simple view. Portable operation, no matter how casual, requires energy storage and management. Such techniques are basic to nearly all alternative energy systems. Secondly, there are many alternatives as to how we charge those batteries. When there is no electricity in the power line or when there is no power line, how do you keep that hand-held transceiver running? Answer: with energy from an alternative source.

The most rigorous applications of alternative energy techniques involve permanent or semipermanent installations that must, for whatever reason, be energy self-sufficient to some degree. Such installations, be they repeaters or small households, must be dependably supplied with energy despite the fact that there can be no expectation of regular reconnection to the mains. For the remainder of this article, we'll be exploring alternative energy systems that can meet these needs. Energy for the short-term needs of portable, mobile and emergency Amateur Radio operation has received ongoing coverage in *QST* and *The ARRL Handbook*. Portable and mobile ham operation *do* have something in common with long-term alternative energy production, however. See the sidebar, "Milking a Herd of Cars."

Energy Production

Most small-scale alternative energy schemes likely to be undertaken by radio amateurs involve two distinct processes: production and storage. It's easier to talk about storage if we have something to store, so let's look first at means of producing electricity.

Wherever there is an energy gradient, be it mechanical, chemical or thermal, there is the possibility of producing electricity.

Wherever there is an energy gradient, be it mechanical, chemical or thermal, there is the possibility of producing electricity. Wherever there is motion, kinetic energy may be intercepted and put to work, either directly to drive machinery or indirectly to generate electricity. The classic and most readily exploited energy sources are water and wind. Where electricity is the desired product, the linear movement of water or wind is transformed into a rotary movement suitable for driving generators. This transformation of linear to rotary motion is usually accomplished with a fan-like propeller in the case of wind, and any of a variety of turbines and wheels in the case of water.

Wind and waterpower systems offer an interesting analog to electrical theory. We may extract equal amounts of energy from large volumes moving at low velocity or smaller volumes moving at high velocity—very much as 1 W can be developed with 1 V at 1 A or with 1 kV at 1 mA. In practice, water is more easily manipulated in this way, while wind must be taken as it comes. Still, in areas where winds are light, larger wind turbines may be used to generate the same output produced by smaller generators in windier areas.

Waterpower Systems

Available water pressure—usually the result of water running downhill—is the heart of every hydroelectric energy system. Pressure increases in direct proportion to the height of the water column contained in the supply pipe or *penstock*. The height of the water column is defined as the *head*. Pressure at the bottom of the penstock in lb/in^2 will be approximately half the measure of the head in feet. Friction must be considered as well, because some of the energy in moving water is spent in friction between water and piping. This factor depends on pipe length and diameter, as well as the pipe material and its condition.

Hydroelectric systems can be divided into high- and low-head categories. In high-head systems, energy is extracted from a relatively small volume of water moving at high velocity, while large volumes of slow-moving water are employed in low-head operations. Either approach may be used to produce a few watts or many kilowatts of power, and the appropriate choice will depend largely on the nature of the available water supply.

Low-head systems entail construction techniques suitable to routing and controlling large volumes of water. If a head of 15 to 20 feet is available, with flow enough to fill an 8-inch (or larger) pipe, turbines and complete generating systems are available that will produce ample electricity to maintain a household, assuming that energy *needs* versus wants have been carefully assessed. Despite the considerable volume of water they entail, low-head systems can be relatively compact because the water source usually need not be far from the generator. Low-head systems based on wooden waterwheels, such as those found at water-powered mills, can be built from basic materials with a minimum of precision work. Although such wheels can deliver substantial power, they do not turn fast enough to drive generators directly, so their speed must be stepped up mechanically. Because the required step-up is usually too extreme to be accomplished efficiently with belt-and-pulley drives, the usual solution is gearing. Automotive gear trains—even whole transmissions—are a common choice for this gearing.

High-head systems require less water for a given output, so they can be applied in areas where water volume is insufficient for low-head generation. A complete high-head installation may require a lot of territory. Much pipe may be needed. Safe and reliable containment of high-pressure water may dictate the use of expensive construction materials. A variety of small turbines, mostly of the Pelton type, are available for high-head systems. Turbine diameter may be as small as four inches for very small systems, with diameters of eight to twelve inches common in 1- to 2-kW applications.

For optimum efficiency, a turbine must be matched to both the volume and velocity of available water. Nonetheless, turbines can deliver useful power over a wide range of pressure and flow, so if you come into possession of an old unit that isn't exactly right for the available situation, it may still be worth using.



Fig 1—Hydroelectric power, anyone? Here, the author's 9-inch Pelton turbine (bottom), manufactured circa 1890, drives a modified automotive alternator (upper left) to produce 117 V ac. Pressing the button at the upper right of the meter panel provides dc field current for the alternator at system startup.

Hydroelectric systems may be designed to deliver either low-voltage dc or 117 V (and higher) ac, depending upon the power available and your requirements. Even a tiny hydroelectric potential of 2 or 3 A at low voltage can be useful in battery charging service. Because such a charger can work 24 hours a day, its performance can approach that of a photovoltaic (solar-powered) unit having four times the output capacity.

The construction of any hydroelectric system represents a long-term investment. Careful planning is a must. Attention must be given to the development of an adequate water source, disposal of water discharged from the system and a multitude of mechanical and environmental concerns related to the routing of water. Potential impact on erosion and vegetation patterns should be considered carefully. A good hydroelectric installation should deliver its design capacity for many decades while requiring only a relatively low level of maintenance and post-construction expense. Of the available small-scale alternative energy techniques, only hydroelectric systems offer a continuous supply of electricity with no battery storage requirements.

In my own system, I use a nine-inch Pelton wheel (manufactured circa 1890) with a 180-foot head delivered via ¼ mile of 2¼-inch pipe. The pipe is installed in six-foot sections, and I'm sure that friction losses are high in this piping because of turbulence at its many joints. Why the short pipe sections? They were brought to the generating site in the 1930s—packed on mules! In the original installation, the nine-inch turbine was used to operate circular and crosscut saws for cutting firewood. At the same time, a considerably smaller turbine charged batteries. Somewhere along the line, the smaller unit vanished. Since we can now take chain saws to the trees instead of dragging whole trees to the saw, the larger turbine is free for use in electricity production. The Pelton wheel drives a modified automotive alternator through a belt and pulleys (see Fig 1). In my case, the alternator modification is a simple matter of installing wires to bypass the connection of one of its three poles to rectifier diodes so that low-voltage ac is available. This ac is applied to the primary of a 12-to-117-V step-up transformer, providing up to 300 W of ac power for lighting, soldering and small electronic applications. Operating frequency and output voltage in this system depend somewhat on loading—the resulting electricity is definitely *not* a 60-Hz sine wave!—but the energy generated is highly useful nonetheless.

Such a simple system is feasible only because of the limited power available from the turbine. Higher power would call for closer regulation and full utilization of the alternator's three-phase capacity.

At times, I use the waterwheel to charge batteries. To do this, it is necessary only to switch the transformer out of the alternator circuit and connect a battery to the alternator's dc output. In this mode, the alternator functions just as it does in a car except that output is somewhat reduced because of the limited driving power. If I want a trickle charge, I just close the turbine water supply valve until I get the charging current I want!

Wind Power Systems

As with waterpower, the kinetic energy of wind may be tapped by converting its action to a rotary motion suitable for operating generators. Like water, wind can provide large or small amounts of power, depending on need and subject to prevailing conditions. But unlike water supplies, which can be closely regulated for continuous operation, the wind is always somewhat intermittent and highly variable in intensity.

Small-scale wind power generators are generally employed as battery chargers, the stored energy being used directly or after conversion to ac for the operation of 117-V appliances and tools. I have heard that on the coast of Chile, where evening wind is common and fairly constant, extensive use has been made of propeller-driver automotive generators connected directly to low-voltage lamps.

The variable nature of wind and the extremes that will occasionally be encountered at any generation site necessitate mechanical means to prevent self-destruction of generating apparatus during high wind conditions. Such velocity compensation may be accomplished with variable pitch propellers that reduce efficiency as speed rises. Alternatively, tail-vane action may be used to turn the wind turbine off-axis to high winds. Various centrifugally actuated braking devices may be used; these operate aerodynamically or mechanically.

Provision must be made to maintain generation no matter what the wind direction. A tail vane will take care of this. Of course, if the generator is free to rotate as the wind turbine aligns itself with changing wind direction, a slip-ring coupling arrangement must be employed to get electricity out to the load. Voltage regulation is essential in wind systems to prevent overcharging of batteries and damage to low-voltage apparatus.

The preceding comments apply mostly to propeller-driven upright wind turbines common to most windmills. If a wind turbine is built similar to a vertical squirrel-cage fan, only the turbine itself need rotate, because such a turbine responds to winds from any direction. Thus, the generator may be fixed, and no slip rings are required to transmit its output to the load. An added advantage claimed for some squirrel-cage wind turbine designs is that they are self-regulating with respect to speed: Increasing wind velocity increases turbulence around the rotor, effectively limiting its maximum speed.

In the days before rural electrification, many homes on the Great Plains were wind powered. A number of companies produced wind generators and complete power systems. As power lines spread through the countryside, wind power installations were shut down and largely left to deteriorate. During the 1970s, increasing interest in alternative power sources led to the salvage and reconditioning of many such units. Some usable salvage may still be gleaned from such systems, but unless wind equipment has been regularly maintained or carefully stored, extensive restoration is required. Any towers and tower-mounted units that have been neglected for decades are potentially dangerous. Undertake salvage efforts only with the help of properly equipped people experienced in wind-power machinery.

Recently, we've seen significant advances in wind power design; high-efficiency units with long lifetimes are available at a variety of power levels. For the dedicated home builder, much has been published covering wind power at all levels, from the most basic on up. These are too numerous to list here; your library is the best place to begin research. If you possess good workshop skills, study of a cross section of this material should enable you to set about designing and building your own wind power system.

Photovoltaic (Solar) Power Systems

Until recently, practical electrical generation has been either electrochemical (primary cells) or electromechanical (generators). With the development of photovoltaic (PV) technology, we are presented with a third and highly elegant option: the direct conversion of light energy to electricity. Modern PV devices can do this efficiently enough to power a wide range of electrical and electronic devices.

The production of PV materials is an energy-intensive process, but the practical application of PV products is the most straightforward of any alternative energy technique. Aside from switches and relays, PV systems entail no moving parts bigger than electrons and photons. Thus, maintenance requirements are minimal: PV generating panels should be kept reasonably clean because sunlight must be able to reach them, electrical connections must be sound, and batteries must be maintained in good condition.

Electromechanical systems have definite ranges of optimum efficiency. A system designed to serve a maximum load demand may not be "happy" with an average or minimum load. With PV technology, power is available in direct proportion to collector surface area, so system capacity may be easily tailored to specific load requirements by adding or subtracting collectors.

PV collectors are a long-term energy source. Most good-quality solar panels are guaranteed for five to ten years, but the usable lifetime of a panel will ordinarily extend for a considerably longer period, offsetting high initial costs with low maintenance expense and high life expectancy.

At the moment, PV efficiency per unit area appears to be rising faster than cost per unit area. Various long-awaited breakthroughs in manufacturing processes, especially the continuous roll-to-roll production of amorphous silicon alloys, are on the point of bringing the PV industry to a new and highly competitive level. *QST* recently carried a New Product announcement about amorphous silicon panels.[1] Although photovoltaics are an expensive energy source, they are indispensable and cost-effective tools when it comes to powering permanent and semipermanent remote installations such as repeaters, remote bases, beacons and sensors.

For powering isolated households, PV will likely be less cost effective than hydroelectric or wind systems, assuming that those resources are readily available for development. But this is really a complex question. Its answer depends on how much energy you choose to define as "enough," how peak requirements relate to average demand, and so forth.

Modern photovoltaic devices can convert light energy to electricity efficiently enough to power a wide range of electrical and electronic devices.

Often, no single energy source will readily satisfy the full range of load demands, so system combinations become very attractive. For instance, photovoltaic battery-charging capability can work in conjunction with an internal-combustion-engine-powered generator. During peak-

---

[1] Bruce O. Williams, "Sovonics Amorphous Solar Electric Panels," New Products, *QST*, May 1987, p 20.

Used Solar Cells Deserve a Place in the Sun

Several years ago, I constructed a small (12 V at 30 mA) energy panel from small semicircular solar cell scraps. The panel worked, but it was never really weather tight. Moisture entered during every rain and heavy fog. This condensed on the glass surface of the panel, reducing its output until evaporation cleared the problem. One day, the panel took a fall and its glass cover broke. It lay abandoned and exposed to the weather for about two years until my curiosity led me to bring it home and check its cells. To my surprise, most of them performed quite well. Because a few cells were broken, and some soldered joints were in bad shape, I dismantled the panel, thinking that I might be able to salvage enough cells to charge small 6-V batteries. Before I could begin work on this charger, the PV cells, lying in disarray on a table, were accidentally exposed to the discharge of a Tesla coil. Sparks jumped freely between all of them! This looked like the end of my mini-project—but the cells checked out fine under test. Using them, I built the 6-V panel shown in the photo. For more than a year, it has been delivering 30 mA to my 6-V batteries whenever the sun shines.

I don't recommend trying any of these tortures on your solar cells, but my experiences do show that unlike many semiconductor devices, solar cells *can* survive abuse. Because of this, used solar cells should not be overlooked as a source of cheap energy.



This 6- × 8-inch solar panel delivers 30 mA to a 6-V battery under full sun conditions. The cover is acrylic plastic sheet, the back is plywood and the sealant is silicone rubber. These cells still work even after a rather shocking experience.

sun periods, the PV system maintains battery charge to operate lighting and low-voltage dc devices. At such times, the engine-driven system sees occasional use in running high-powered tools and appliances. When PV output falls because of short daylight hours in winter or extended periods of overcast, the engine system automatically tops off the battery charge. If PV capacity is later increased, the engine generator runs less, extending its life and reducing the fuel bill.

In many respects, photovoltaics are a nearly perfect power source, but there are drawbacks. System cost is extremely high if any attempt is made to satisfy the energy requirements of a typical American household with a PV system. Individual solar panels are light and fragile, although fragility stands to be greatly reduced with amorphous silicon PV collectors. They must be exposed in plain sight, creating a risk of theft and vandalism so great as to make PV installations totally impractical in many situations.

Battery storage is an essential adjunct to PV power systems. Many installations will also require the conversion of stored dc to 117 V ac, usually by means of high-efficiency solid-state inverters. Outlays for energy storage and conversion hardware must also include the cost of suitable housing for the components. This calls for careful planning, which should begin with a realistic assessment of system requirements.

Many people look at the high cost of the solar panels and decide to build their own, either from kits or by using "bargain" cells available from many sources. With care, anyone can solder cells together and house them well enough to provide protection from the immediate effects of the weather—but by the time the materials have been obtained and the hours have been invested in construction, the "bargain" may not seem like such a bargain. The real question is how long such collectors will continue to deliver their initial output—or work at all, for that matter. The answer depends to a large degree upon the materials used and the care exercised in building the panels. Users looking for more than a few watts should be prepared to tackle a large, demanding (and expensive) construction job. Otherwise, purchasing guaranteed, ready-made units is more satisfactory. On the other hand, construction of a small PV panel can provide a good introduction to photovoltaic technology while adding a useful energy source to the shack.

The present generation of solar cells (of crystalline structure, as opposed to amorphous cells) is fragile. The cells are subject to outright breakage and to microscopic cracking, which interrupts conductive paths, reducing and eventually destroying cell capacity. Even so, solar cells can survive long use and even *ab*use, so used PV devices may be worth investigating. (See the sidebar, "Used Solar Cells Deserve a Place in the Sun.") As existing solar panels age and deteriorate, they are replaced by newer PV technology. This means that more and more surplus, defective and broken early-generation solar panels are sure to become available. These may well provide a useful source of materials for persons desiring to build their own panels on a low budget. While construction of a large panel means a major construction effort, small units are relatively quick and easy to build—and if the price is right, it isn't necessary that they last forever. Small PV panels may not be as impressive as a huge solar array on a roof, but their modest milliampere outputs add up to milliampere-hours. A few days of sunshine on such a panel will recharge a battery pack for your hand-held transceiver—allowing you to talk with the energy of recycled photons!

From October 1987 QST, p 19:

Alternative Energy—An Overview of Options and Requirements

Part 2: Energy storage is necessary to smooth out natural variations in supply. And what about system safety once your alternative energy plant is up and running?

By Michael Mideke, WB6EER
Box 123
San Simeon, CA 93452

Some alternative energy sources, such as wind and sunshine, are intermittent and variable in nature. Others may be constant, but of a level too low to meet intermittent peak demands. In all such cases, energy use is determined by the vagaries of nature unless some form of energy storage is employed. One way or another, a means of smoothing out the peaks and filling in the valleys of energy production must be provided.

In hydroelectric systems, this storage may amount to no more than the confinement of water in a reservoir until its energy is needed. Then, opening a valve or sluice gate sets the water in motion, and the kinetic energy in the flow may be tapped by a turbine. Reservoirs work well with water, but are impractical—to say the least—when the energy source is wind or sunshine. A way must be found to store the energy from these sources after it has been converted to electricity.



Here's solar-powered 2-meter repeater WB6RHR/R, Red Hills (near Shandon), California. Although this installation is not connected to commercial power in real time, it owes its hardware and maintenance to energy-intensive techniques—as do *all* alternative-energy systems. *(photos by WB5EER)*

Capacitive Storage

Electrical energy can be stored in capacitors. This is a useful approach when the available charging current is small in relation to a momentary high-current demand, as in photoflash systems, or if the powered system requires voltage at relatively little current, as is the case with short-term memory backup in computer circuitry. Advances in capacitor design allow us to store more and more energy in ever smaller packages, but we are still a long way from seeing capacitors that can compete with storage batteries when the application is one of sustained and regulated discharge.

Electrochemical Storage

Storage batteries provide a practical means for storing large amounts of electrical energy, though it is not really accurate to say that *electricity* is stored in such a battery in a manner akin to capacitive storage. Rather, electrochemically stored energy is invested in a chemical reaction that is reversed when the battery is discharged. The reversibility of this storage reaction is what makes the difference between primary and secondary cells: The electrochemical reaction in primary cells is not easily reversible, disallowing recharging; secondary cells may be discharged and recharged many times.

A wide variety of storage batteries has been developed to meet many storage needs. Sizes and storage capacities range from tiny to enormous. Various battery chemistries are used, depending on the intended service. Which battery you use is determined by the application you have in mind. Size, weight, charge and discharge characteristics, expected lifetime in the proposed service—all of these are important considerations in choosing a storage battery. There is some advantage in using the largest batteries that size, weight, cost and acceptable float-charge load allow: Large batteries mean a large reserve capacity for emergencies or unanticipated use. For a given battery chemistry, life expectancy is generally greater for large batteries than for small ones.

Nickel-Cadmium Batteries

Highly portable low-power applications are commonly powered by nickel-cadmium (NiCd) batteries. These batteries produce a nominal 1.2 V per cell and should survive around 500 charge-discharge cycles. Some NiCd cells can safely sustain rapid recharging, providing an extra measure of flexibility in portable and emergency situations. NiCd cells are produced in the cell packages commonly associated with primary cells (AA, D, C and so on) and can be used interchangeably with primary cells to some extent. It's important to bear in mind, however, that the difference between zinc-carbon and NiCd cell voltages at full charge (0.3 V) makes for significant under-voltage when NiCd cells are series connected to take the place of an equal number of zinc-carbon cells. Perhaps one or two more NiCd cells can be added to such a battery to make up the difference. But the voltage match is rarely exact in such cases, and addition of more NiCd cells often means substituting too much battery voltage for too little. Since equipment may be damaged by excessive supply voltages, substituting NiCd cells for zinc-carbon units is trickier than it may seem at first—especially if you've added additional cell holders to a battery and someone unknowingly installs zinc-carbon cells!

Lead-Acid Batteries

When small battery-powered equipment is used in such a way that the battery is subject to frequent deep discharges, NiCd cells may be the preferred choice. Where deep discharges are only occasional and float-charge current is generally available, a gelled electrolyte lead-acid storage battery should prove more economical in the long run. The nominal cell voltage for lead-acid batteries is 2.0 V.

When it is necessary to power remote sites, especially if they are not vehicle-accessible, 12-V gel batteries rated at about 30 Ah are nearly ideal. Weighing 25 to 30 lbs, they can be transported nearly anywhere with relative ease. Because these are sealed batteries with rugged mechanical characteristics, there is little danger of damage regardless of the contortions that may be necessary to get them to their destination. When higher voltage or greater storage capacity is required, simply use more batteries in series or parallel and distribute the hauling job among carriers or over time. This is infinitely superior to struggling with one giant battery.

Higher power applications, such as operating HF transceivers or household lighting and appliances, require larger batteries. Where the powered site is accessible and power requirements are large, the 30 Ah gel battery is no longer a cost-effective building block. Then, the best compromise between economy and service life is the liquid-electrolyte lead-acid battery.

Automotive batteries are often pressed into this service, more because of their ready availability than suitability for the job. The automotive battery employs a lead-calcium plate chemistry that is satisfactory for brief periods of high-current discharge followed by immediate and complete recharging. Such batteries are not suited to deep-discharge applications where they will be repeatedly drained to a 50% discharged state. In fact, a dozen or so such cycles will reduce the battery's capacity to the point where it should probably not be counted on to start a car. By contrast, batteries designed for deep-cycle service should be good for a few hundred charge-discharge cycles.

This does not mean that automotive batteries are unsuitable for all alternative energy applications. Where the average load current is low and some energy is available to keep the battery float-charged to near capacity most of the time, its useful life may considerably exceed its rating for automotive service. Although the life of such a battery *will* be reduced by deep discharging, the battery will deliver something close to its rated capacity for the discharge rate in question. Prompt recharging will restore the battery almost to its initial capacity. The self-discharge rate for healthy automotive batteries is lower than that of equivalently rated deep-cycle batteries, so the float-charge current required to keep an idle battery fully charged will be lower for the automotive battery.

Where regular use of higher-power equipment (perhaps 30 W and up) or conversion of battery power to 117 V ac is contemplated, the most practical and economical battery "building block" appears to be the 6-V, 217-Ah units designed for golf carts and similar applications. These are deep-cycle batteries with a lead-antimony plate chemistry. They weigh approximately 70 lbs each and can be moved around fairly easily. For increased storage capacity, they can be connected in series and parallel. Such deep-cycle batteries should have a service life of nearly 10 years if reasonable care is taken in their application.

Large batteries no longer capable or trustworthy in their original service may still do useful work with smaller or less critical loads.

Battery manufacturers consider a battery's useful life to be over when its storage ability has dropped to 50%-80% of its capacity when new. This does not really hold true where the battery has more capacity than necessary for the job. If normal usage of a battery draws only 10% of its rated capacity, it doesn't make much difference whether the battery is 90% as good as new or only 50%. As long as the battery delivers its rated open circuit voltage (no shorted or dead cells) and maintains acceptable voltage under load through the required duty cycle, it is still usefully "alive" for that application. Of course, as a battery ages, its emergency reserve becomes questionable, and overall efficiency is reduced. Eventually, the battery *will* fail; all batteries have a finite life span. The point here is not that we should buy batteries that are much larger than we need, but that large batteries no longer capable or trustworthy in their original service may still do useful work with smaller or less critical loads. This is especially true of older batteries, which can be used to store surplus energy if it is available to trickle charge them.

More Battery Chemistries, Old and New

Earlier this century, much use was made of the nickel-iron chemistry of the Edison cell, particularly because of its lighter weight and tolerance of abuse as compared with the lead-acid batteries of the day. If you can find salvageable Edison batteries, it's quite possible that they can be made to work for you. See the sidebar, "Edison Batteries," for the story.

Looking to where the present blends into the future, research continues in the quest for increased battery life and capacity. Recently, rechargeable lithium cells have made the scene.[2] The dependability of alternative energy systems rests heavily on energy storage, so each improvement in battery and energy management technology is good news for alternative energy planners—especially as the reliability of new technology goes up and costs come down.

Safety in Alternative Energy Systems

As consumers of commercially produced power, we are protected to a considerable degree from electric shock, explosion, mutilation, poisoning and a host of other potential consequences of living in close proximity to the systems and energies that power our civilization. When we take things into our own hands and build energy systems from the ground up, we must consciously build safety in. It is necessary to evaluate hazards and take measures to minimize them.

Next, we'll survey the basic classes of hazards you may encounter in working with the sort of alternative energy techniques outlined so far. This material should not be a substitute for all warnings and instructions that may come with machinery and substances employed in alternative energy work. Nor should it be a substitute for doing personal safety *research*, in the library and face-to-face with experienced people.

The hazards inherent in the production and storage of electrical energy may be divided into three closely related categories: mechanical, chemical and electrical. Some of these hazards are no different from those encountered by any electricity user. Others are more characteristic of complete power systems. As different as they may seem from each other, mechanical, chemical and electrical hazards *are* closely related: A failure or accident in one category is likely to bring about failures in one or both of the others. Such multiple failures can be nearly instantaneous and the consequences can be catastrophic.

---

[2] Noulan Bowker and Christopher Dollard, "The Magic of MOLI," Jun 1987 *QST*, pp 22-25.

Edison Batteries

First marketed in the early 1900s, the nickel-iron alkaline Edison cell has accumulated a reputation for capacity and indestructibility that is only partially justified. It is *not* the perfect storage cell, but it does have some interesting qualities. Batteries of Edison cells were designed to survive rough mechanical abuse in railroad lighting and vehicle propulsion service. Largely because of the strong, lightweight construction of its steel case and its rugged internal structure, the Edison battery achieved this objective with a better power-to-weight ratio than could be attained readily by the lead-acid batteries of the time.

The construction and chemistry of the nickel-iron cell is such that it can survive abuse that would be fatal to a lead-acid cell. As long as it is not drastically overheated, the Edison cell can be overcharged to the point of vaporizing all of the electrolyte and no great harm will result. Nor will the cell be harmed by being left in a totally discharged condition. I know of used Edison cells that recovered a good percentage of their original capacity upon being filled with distilled water and run through a few charge-discharge cycles—after having been dry and totally neglected for over *40 years.*

Now for the bad news. As compared to lead-acid cells, the Edison cell has a high internal resistance and a high self-discharge rate. Thus, voltage regulation during load variation is poor, and the cell shows a continuous loss of voltage throughout its discharge cycle—from nearly 1.4 V at full charge to 1.0 V at the bottom of the cycle. Hydrogen and oxygen are vented continually, though to varying degrees.

Edison cells employ a potassium hydroxide electrolyte. This is a strong base and must be handled with caution. Acids and acid-contaminated tools should *never* be used in or around Edison batteries—something to keep in mind if your battery "stable" is to include both lead-acid and Edison cells.

A hydrometer is not of much use in determining the state of an Edison cell because the specific gravity of the electrolyte changes little between the charged and discharged states. Cell voltage, charging time and charging current are the best indicators of charge for Edison batteries.

Terminal voltage in the discharged condition for a single Edison cell is considered to be 1 V. New Edison batteries had an expected lifetime of 2000 charge-discharge cycles. Most of these batteries were probably used by railroads for passenger car lighting and trackside signaling, although many saw service in domestic wind power installations. Despite their age, however, Edison batteries may still be found. Many of their cells will undoubtedly be in salvageable condition (see photo).


A battery of six Edison cells as collected on a salvage expedition. Most of the cells are good, but the original wooden rack is in bad shape. These are A-8 cells, originally rated at around 220 Ah each.

If you come across an odd-looking battery like that shown in the photo, don't assume that it is dead and gone. If the steel case of a given cell is intact and the poles are not internally shorted or shorted to the case, it is quite possible that the cell can be revived. Cases of adjacent cells in an Edison battery must be insulated from each other or electrolytic action will eat through them in short order. (In an Edison cell, the steel case is isolated from both poles but common to the electrolyte.) A socket wrench and a good gear puller are essential for disassembly of Edison batteries. Details on the care and feeding of Edison batteries can be found in older electrical engineering handbooks.*

---

*Greatly detailed information on Edison and other secondary cells may be found in George Wood Vinal, *Storage Batteries,* 2nd ed (New York: John Wiley and Sons, 1930).

The sidebar, "Harmless," offers an example of the kind of nasty multiple failure that can happen around an alternative energy installation. Although the chain of events depicted there may seem farfetched, it isn't. When you achieve long periods of accident-free alternative energy production, you *won't* have wasted your time anticipating and guarding against the worst!

Mechanical Hazards

Moving parts, especially gears, vee belts, pulleys, wind turbine propellers and the like, should all be made inaccessible to accidental contact. This is usually accomplished with covers and enclosures. When such moving parts must be exposed, they should be located out of reach. A wind turbine should not be able to touch anyone on the ground or working on its tower.

Towers should be designed and supported to withstand worst-case weather conditions for the area. They should receive regular inspections and maintenance as needed. When in doubt, consult a structural engineer. Towers are attractive nuisances, so they should not be climbable by children or passersby.

Persons developing any energy resource must take a certain responsibility for their safety and that of their neighbors.

Chemical Hazards

All motor fuels and their vapors are flammable and potentially explosive. They must be handled in suitable containers, lines and fittings. Most fuel vapors have distinctive odors, so use your nose! Don't ignore what your sense of smell tells you. Track down and repair leaks. Never store fuels near operating engines or sources of open flame and sparks.

Internal combustion engines produce carbon monoxide gas as an exhaust product. This is a colorless, odorless and lethal substance. Do not breathe exhaust fumes; also, do not risk operating engines in enclosed spaces unless exhaust fumes are properly vented through a gas-tight system. Even with a good exhaust system, it's good

Harmless

An industrious mouse enters the battery compartment of an alternative energy system. Shuffle, sniff. No loose scraps worth taking—just a foot-long piece of bare no. 10 wire carelessly abandoned in the framing of the compartment two years ago. Exiting the compartment, the rodent shoulders the scrap aside, causing it to fall across the terminals of a 12-V storage battery. There is an immediate electrical failure as the wire welds to the battery terminals, shorting the system. The wire reaches red heat in a matter of seconds. As it glows brighter and begins to melt, the wire slumps onto the plastic battery case. The case melts like butter under a hot knife.

At this point, the electrical failure is over: The wire melts through the battery case with a sizzling arc that causes the hydrogen and oxygen within the battery to unite with explosive force. The explosion rips the already damaged battery open, spewing sulfuric acid, acid vapors and hot metal all over the battery compartment.

With luck, the problem ends here, with no fire climbing the walls and no injuries—just a terrible mess to clean up. But don't count on it. A chance encounter with a harmless scrap of wire and a mouse has already blown up your battery. Why should chance stop there?

Such a series of events may seem highly improbable. But trusting to probability implies taking chances—in other words, playing odds. And that's exactly what *not* to do when building safety into an alternative energy system. Dangerous system failures are possible unless care is taken to make them *impossible*. You must build safety in.

insurance to keep a carbon monoxide alarm in the engine room.

Engine exhaust systems can emit burning gases and hot carbon particles, both of which can ignite dry materials in the vicinity of the exhaust outlet. When internal-combustion-engine driven generators are to be used outdoors under dry conditions, use spark arresting mufflers or spark arresters approved by the US Forest Service. Clear a ten-foot radius to bare dirt around the generator and *keep* it clear. Have a shovel and fire extinguisher nearby and in plain sight.

Whether they're acidic or alkaline, battery electrolytes are nasty substances. They can corrode metal, creating both mechanical and electrical problems. They can destroy clothing in short order, and their activity does not stop when they get to the flesh underneath. Soft tissues, such as eyes, are particularly prone to rapid damage from exposure to battery electrolytes, so wear eye protection when working around batteries. Keep some means of flushing away accidental exposures at hand; a garden hose will do. Don't wear your best clothing when working with batteries—some exposure to electrolyte is almost inevitable. The evidence may not appear until that special shirt comes out of the washer looking like cheesecloth!

Avoid panic by having emergency procedures well in mind. Your flesh won't dissolve right off your bones if you *do* get electrolyte on it, so don't go into shock. Just start flushing the affected area immediately. If garments are saturated, get out of them.

Storage batteries (except for completely sealed recombining types) emit hydrogen and oxygen gases, particularly under heavy charging and overcharging. This is a highly flammable, explosive mixture. Although hydrogen is much lighter than air and tends to dissipate rapidly, it cannot do this in confined spaces—such as the space between the electrolyte surface and the filler cap of a battery. Dangerous concentrations of hydrogen can accumulate here. Thus, checking the electrolyte level by match light or "testing" a battery by drawing sparks across its terminals are dangerous techniques and should *never* be used.

Dangerous system failures are possible unless care is taken to make them* impossible. *You must build safety in.

Storage batteries also tend to vent corrosive vapors that can damage delicate electronic equipment. If vented batteries are used indoors, the vents should be extended to the outdoors with plastic tubing. The best practice is to provide storage batteries with their own well-ventilated compartment or room.

Electrical Hazards

Electric shock is to be avoided at all costs. Shock danger from 12-V dc systems is minimal, but as system voltage approaches 32 V, it's possible to get "bitten" and even be electrocuted if conditions are just right (or wrong!). Both storage batteries and solar panels connected in series can add up to shock potential in short order. Remember that the output voltage from solar panels is much higher with no load than it is when a load is connected. Where sinusoidal ac energy is concerned, thinking in terms of RMS voltage can be deceptive, because ac peak voltage works to overcome your skin resistance—and *peak* voltage in a sine wave exceeds RMS by a factor of 1.414.

Current Kills—But It Also Burns

Even small storage batteries can deliver high currents sufficient to bring small conductors to red heat, creating potential for fire and burns. Larger batteries, such as those found in automobiles and alternative energy storage systems, can deliver hundreds of amperes. Such currents can heat and melt large conductors. Rings, bracelets and wristwatches should never be worn by people working with electrical systems for this reason. Electrocution may be the first danger that comes to mind when considering the wearing of metal jewelry, and it should never be ruled out, of course. But stories of fingers amputated and cauterized by a white hot ring welded across a high current source are not fables—it can happen to *you.*

Protect battery terminals from short-circuits. Exercise extreme caution if you must work around batteries with metal tools. Always keep one terminal covered to avoid the possibility of a short circuit.

Modern battery cases melt readily even at soldering temperatures (360-460° Fahrenheit for common solders). These cases also deteriorate rapidly in sunlight,



Fig 2—Voltage across the terminals of a "12-V" solar panel varies considerably with load, and this must be allowed for in the design of a solar energy system. (The graph shows voltage versus current for the 5-W Sovonics panel described in the article called out at Note 1 in Part 1 of this article.)

leading to embrittlement and cracking. Keep them out of the sun and handle them with care.

Fusing and Load Switching

Fuses are essential insurance for electrical safety. Fuses or circuit breakers rated to handle full load current should be placed as closely as possible to the battery. Great care must be taken with insulation and dress of the wiring from battery terminals to fuses. Since high currents at low voltages are involved, low-resistance connections to fuses and breakers must be provided. Further fusing of subsystems as appropriate to their individual current demands can be installed at a convenient location farther from the battery.

In switching and fusing a photovoltaic system, bear in mind that "12-V" solar panels may produce more than 20 V across an open circuit or high-resistance load (see Fig 2). This could have disastrous consequences for equipment should the line from the PV array to the battery open with equipment still connected to the PV array. If at all possible, meters should be used to monitor charging current, load current and battery voltage in an alternative energy system. Then, proper operation of the system can be confirmed at a glance.

Conclusion

If you find yourself inspired to become involved with alternative energy projects, you'll discover a wealth of literature devoted both to specific and general topics in the field. The few references I've listed in the bibliography will help get you started. It's also quite likely that you can share ideas and questions with someone in your own area who is working commercially or privately with some aspect of alternative energy. Such people may well be the most valuable untapped resource you'll find as you work to develop an operational energy system.

Bibliography

General Alternative Energy

Reader's Digest Editors, *Back to Basics: How to Learn & Enjoy Traditional American Skills* (New York: Random House, 1981). Good wind- and waterpower chapters in this general book on the "simple life."

Richard Merril and Tom Gage, *Energy Primer* (revised edition) (Pine Brook, NJ: Delta Books, 1978). Not currently listed in *Books in Print*, but worth a library/used-book store search.

Stewart Brand, ed., *The Next Whole Earth Catalog* (Ellenwood, GA: Alternatives, 1981). Published by Alternatives, PO Box 429, 5263 Bouldercrest Rd, Ellenwood, GA 30049. Includes excellent listings of alternative energy literature and hardware.

Batteries

Warren Dion, "A New Chip for Charging Gelled-Electrolyte Batteries," *QST*, Jun 1987, pp 26-29.

Richard A. Perez, *The Complete Battery Book* (Blue Ridge Summit, PA: TAB Books, 1985).

M. Wilson, ed., *The 1987 ARRL Handbook* (Newington: ARRL, 1986). See especially "Battery Power," pp 6-25 to 6-28, and Chapter 27, "Power Supply Projects," pp 27-28 to 27-36.

Solar Energy

C. Philip Chapman, Paul D. Chapman and Alvin H. Lewison, "Amateur Use of Solar Electric Power," *QST*, Oct 1982, pp 11-14 (Part 1) and Nov 1982, pp 30-34 (Part 2).

Waterpower

Dermot McGuigan, *Harnessing Water Power for Home Energy* (Charlotte, VT: Garden Way Publishing, 1978). Available from Garden Way Publishing, Storey Communications, Inc, Schoolhouse Rd, Pownal, VT 05261.

Kvaerner Hydro Power, Inc, 1978 Commerce Rd, Springfield, OH 45504, manufactures Leffel hydroelectric turbines. See especially their Pamphlet A, "Hints on the Development of Small Water Powers" and Bulletin H-49, "Hydro-Electric Power from a Hoppes Hydro-Electric Unit."

Wind Power

Carl J. Heinen, "Watts from the Wind," *QST*, Jul 1977, pp 15-19.

Park and Schwind, *Wind Power for Farms, Homes and Small Industry* (Springfield, VA: National Technical Information Service, 1978). Available from US Dept of Commerce, National Technical Information Service, 5285 Port Royal Rd, Springfield, VA 22161.

From July 1989 QST, p 31:

Operate Your Station With Power from the Sun!

Here's a report on this *hot* technology, with the information you'll need to design your own solar-powered station.

By Peter Berg, KG6JA
PO Box 4207
Carlsbad, CA 92008

I'm not a dyed-in-the-wool ham radio operator when it comes to RF—I'm more of a tinkerer in electronics. Although I have held a license since 1954, I have, until recently, derived more satisfaction from designing receivers and transmitters—and getting them to work than from operating them on the air.

With the sunspot cycle starting upward again, I finally broke down, put savings in pocket, drove to the ham store and purchased a new dc-operated transceiver. Because I did not have a sufficiently large (20-A) power supply for this radio, and because I was in a hurry to try out the new rig, I borrowed the storage battery from my motor home. This battery has a 55 ampere-hour (Ah) capacity, can be deep discharged, and appeared to be plenty large for this application. It has operated the rig for over a year, without trouble.

I recently read up on developments in alternative energy sources such as wind, motion (water) and sun that supply energy to power an entire household. It occurred to me that the use of solar energy to charge a battery capable of powering my ham station would be an interesting and affordable experiment. Much to my surprise, I found that technology in the manufacture of solar electric cells has moved far enough forward that you don't have to live in space, in Florida or in California to benefit from solar energy! Solar-cell efficiency is such that solar cells can provide sufficient energy to be usable in areas of the country where sunshine is less abundant than in the Sunbelt. In fact, these cells even provide electricity on cloudy days.[1]



Solar panels (lower right) and a tribander decorate the rooftops at KG6JA.

Capturing Energy from the Sun

The electric effects of light on certain materials have been known since long before the invention of the transistor. Materials such as cadmium sulfide and selenium exhibit altered electrical behavior when they are exposed to light. Early in the development of transistors, it was discovered that transistors not encapsulated in lightproof housings were sensitive to light. The reason for this is that photons striking a base-emitter junction cause the movement of electron-hole pairs in the junction—just as injecting a forward base-emitter current does. An increase in collector current is the result. This discovery was later put to good use in the development of the translation of light energy to electromotive force, *photovoltaic conversion*, often called PV called *PV conversion*.

A solar cell is a very simple semiconductor. Solar cells are, in fact, large-area semiconductor diodes. A cross-section of a solar cell is shown in Fig 1. Simply explained, when the photons contained in light rays bombard the barrier of this semiconductor, hole-electron pairs inside this P-N junction are freed, resulting in a forward bias of the junction, just as in phototransistors. This forward-biased junction can deliver current into a load. Because the exposed area of a solar cell can be quite large, the forward current proced can be substantial. It follows that the output current of a photocell is directly proportional to the rate of photon bombardment, and thus to the exposed area of the photocell.

Types of Solar Cells

Originally, solar cells were made by cutting slices of grown silicon-crystal rod and subjecting them to doping and metallization processes. These solar cells are called *monocrystalline* cells because each unit consists of only one crystal plate. The shape of these cells is the same as that of the silicon rod from which they are cut: round. A slice of this material with an area of 2 inches can be made into one photocell, but a slice of this size could also be used to

---

[1] Notes appear at end of article.



Fig 1—Cross section of a PV solar cell.

produce upwards of a thousand transistors! The cost of these early solar cells was way beyond the means of common folk, and could only be justified for use in space research and other highly critical applications.

Techniques for the manufacture of two other types of PV cells have been developed since monocrystalline cells were first produced. The newer cells are *polycrystalline cells* and *amorphous cells*. Polycrystalline cells are typically manufactured as rectangular blocks of seemingly randomly arranged silicon crystals from which the cell plates are cut. These cells can be recognized by their shape and their random pattern and colorful surface. Polycrystalline cells are less expensive to manufacture than monocrystalline cells.

In the mid 1970s, researchers began to experiment with the manufacture of PV cells by depositing a thin film of doped silicon on an economical but stable substrate, such as glass. In 1975, these efforts paid off, and today the result, amorphous cells, are used in the production of calculators, watches, security systems, automatic gate openers, electric fences, wireless freeway telephones, battery chargers in automobiles and recreational vehicles, and, of course, in ham radio. At first, amorphous solar cells were not very efficient and exhibited rapid degradation with time. Most of these problems have since been solved, and reliable amorphous PV panels are available from many manufacturers. These panels come in several forms: mounted on thin glass, framed, and even mounted on flexible substrates, such as steel.

Amorphous cells are relatively inexpensive to manufacture. They do not, however, spell the end of crystalline cells: Crystalline cells still offer the highest efficiency. The best shopping comparison you can make when purchasing PV solar panels is to compare power output per dollar, and then select a vendor who offers a good warranty and good customer service.

Solar-Cell Specifications

Depending on construction, each cell has an open-circuit output, when exposed to the sun, of 0.6 to 0.8 V. (You may have expected this, because each cell is the electrical equivalent of a forward-biased silicon diode.) This output voltage drops somewhat when current is drawn from a solar cell. Fig 2 shows the typical voltage v current relationship of a solar cell. This is called the cell's *load curve*. Open-circuit voltage is approximately 0.7, and output voltage at optimum load is nominally 0.45. Output current is maximum with shorted output terminals. This maximum current is called the short-circuit current, or I_{SC}, and is dependent on the cell type and size. Because a cell's output current remains relatively constant under varying load conditions, it can be considered to be a constant-current source. The point on the load curve where maximum power can be drawn from the cell is indicated in Fig 2.



Fig 2—This load curve for a PV solar cell shows that maximum power delivery from a solar cell occurs at approximately 0.45 V output. I_{SC} is the short-circuit current.

Just like batteries, solar cells may be operated in series to increase output voltage, and/or in parallel to increase output-current capability. Several manufacturers supply arrays or panels with a number of cells in a series-parallel hookup to be used, for example, for battery charging.

Techniques have been developed for the construction of amorphous cells whereby the cells are manufactured in series by cutting metal layers that have been vapor deposited on the amorphous silicon mass. This cutting is done with a laser. Cell width in such panels may be up to several feet, and the output-current capability of these relatively economical panels is excellent.

PV-cell efficiency varies: Monocrystalline cells have efficiencies up to 15%; polycrystalline cells, 10 to 12%; amorphous cells, 6.5 to over 10%, depending on the manufacturing process.[2]

The output power of solar arrays or panels is specified in watts. Typically, the listed wattage is measured at full exposure to sunlight, at a nominal potential of 7 V for a 6-V system, 14 V for a 12-V system, and so on. You can calculate the maximum current that can be expected from a PV panel by dividing the specified output power by the panel voltage.

The cost of solar panels has decreased significantly in recent years. Basically, you can expect to pay anywhere from about $8 to $15 per watt, depending on quantity, size, construction and efficiency of the panel.

Storing Solar Energy

Because the sun doesn't shine 24 hours per day at any location in the US, some means of storing collected energy must be used. Batteries are commonly used for this purpose. Battery capacity is generally expressed in ampere hours (Ah) or milliampere hours (mAh). This rating is simply the product of discharge current and discharge time in hours. For example, a fully charged 500-mAh NiCd battery of good quality can deliver a discharge current of 100 mA for a period of 5 hours, or 200 mA for 2½ hours, before recharging is required.[3] Three types of rechargeable batteries are commonly used:

- Nickel-cadmium (NiCd) batteries: NiCds are mostly used in relatively low-energy applications such as hand-held transceivers, scanners, etc. The development of consumer electronics has contributed to the rapidly increasing availability (and somewhat-less-rapidly decreasing cost) of NiCds. Major advantages of NiCds: They are hermetically sealed, operate in any position and have a good service life (several hundred charge/discharge cycles), if they are properly maintained.
- Gelled-electrolyte lead-acid batteries: These hermetically sealed batteries are available in capacities from below 1 Ah to more than 50 Ah. They are ideal for supplying energy to a ham radio station, but their cost (for capacities above 10 Ah) is rather high. For portable and QRP stations, though, this type of battery is difficult to beat. The cells can be operated in any position, but should be charged in an upright position. If properly maintained (no deep discharges—cell-polarity reversal is possible under these conditions—and they are stored in a fully charged state), gel cells last a long time (500 or so cycles). I operate a small 10-W portable CW station from a 12-V, 6.5-Ah gel battery with good success.
- Other lead-acid batteries: These are available in the standard automotive version, in the marine/RV deep-discharge versions and in the golf-cart variety. Differences: Automotive batteries usually fail following several deep-discharge cycles (because of the thin plate and insulation materials used in their construction), resulting in premature internal short circuits. Golf-cart and marine/RV batteries have thicker plates with more rigid insulation between them, so these batteries can withstand deeper discharges without plate deformation and internal failure. Deep-discharge batteries provide the best value in a ham station. Some of these batteries require attention (the electrolyte level must



Fig 3—Basic solar-panel-to-battery connection. The series diode in the panel's output line keeps the battery from discharging into the panel.

be maintained), and they last longest when kept charged. Because these batteries use a wet electrolyte (water), and most of them are not hermetically sealed, they must be kept upright.

A Typical Application

Here's a practical example of how to calculate power requirements for a PV-powered ham radio station. The first thing to do is define the power demand. Assume that you use a 100-W rig. (We'll also assume that 100 W is the peak power consumption, and occurs only during CW operation and SSB voice peaks when a 13.6-V nominal supply [a fully charged battery] is provided.)

The most reliable way to calculate realistic power requirements is to determine the power used over a longer period of time—say, a week or a month. Because most of us have more or less recurring weekly habits, we'll take one week as the base period. (You can substitute your own numbers to adapt these calculations for your rig, under your operating circumstances.) Assume that the rig is turned on five days of the week for two hours on each of these five days. Of each two-hour period, 1½ hours is spent listening, and transmitting takes the remaining half hour. Assume that the current consumption of the transceiver during receive is 2 A; during the 100-W peaks on transmit, current drawn is 20 A. The owner's manual for your rig should give the maximum dc current drain. The average current consumption during SSB transmitting is only about 4 A. Therefore, we need a battery that can supply a peak current of at least 20 A and an average current of 4 A. Now calculate the total energy consumed in ampere hours over a one-week period:

Receiving: 2 A × 2½ hours/day × 5 days = 25 Ah.
Transmitting: 4 A × ½ hours/day × 5 days = 10 Ah.

The total energy used per week is 25 + 10 = 35 Ah, or per day (average) is 35 ÷ 7 = 5 Ah. If we had a perfect system, all we would need to do is supply 35 Ah per week (5 Ah per day) to the battery. In practice, imperfections in battery construction cause some loss (self discharge), for which the charging system must compensate, as you'll see.

Next, calculate the minimum battery capacity required for this application. The system should be designed so that sufficient energy is available to run the equipment for two consecutive sunless days (this is rather arbitrary—some locations are worse than others in this regard). Because these sunless days could be days on which you want to operate, and because it's not a good idea to discharge a battery to less than 50% of its capacity (for maximum battery life), this battery must have a capacity of at least 2 (days) × 5 (Ah) ÷ 0.5 (for the 50% charge capacity left after 2 days without sunshine) = 20 Ah. If your location is likely to be without sunshine for as much as an entire week, the battery requirement is 7 × 5 ÷ 0.5 = 70 Ah. Add about 10% to this number to compensate for self discharge and other losses. (Typically, this means you'll buy the next larger-size battery than the initial calculations indicated.)

What does it take to keep this battery sufficiently charged? Here again, some rules of thumb help in the calculations.

First, estimate the average number of hours of sunshine per year in your area. This information can be found in an almanac. As a guide, average annual sun exposure is approximately 3200 hours per year in the Sunbelt, less elsewhere (down to about 1920 hours per year in the far northern parts of the US).

Your PV solar panel will most likely be mounted in a fixed position, but should be at an optimum angle with respect to the earth. This varies from about 30° in the summer up to about 60° in the dead of winter. Fixed-mounted solar panels cannot pick up maximum energy from the sun, for obvious reasons. Of course, you could build some kind of solar-tracking mechanism to circumvent this obstacle, but that's beyond the scope of this article (and beyond the ambition of most people I know). If you need to collect more solar energy, it is much easier to simply add another solar panel! In practice, you can only count on panel exposure for about 70% of the total sunlit time, which is anywhere between 1340 and 2240 hours per year (between 26 and 43 hours per week), depending on where you live.

The remaining system planning is easy. Our earlier calculations showed that the solar cells must replenish 35 Ah per week, plus 10% to compensate for losses, or about 38.5 Ah of battery capacity. With solar energy available in the Sunbelt for 43 hours per week, the required charge current is 38.5 Ah ÷ 43 hours of sunshine = 0.9 A. In the northern part of the US, this is 38.5 Ah ÷ 25.3 hours = 1.5 A. Now, find a PV panel that can deliver this current under load.

In the 12-V system described here, the PV panel operates, with a fully charged battery, at about 13.6 V, plus the voltage drop of a series diode. The basic hookup is shown in Fig 3. With a fully loaded panel voltage of 14, a panel rated at 21 W (14 V × 1.5 A) is required in northern climes. In practice, this power can be obtained from good-quality solar panels with a surface area as small as 5 square feet. If you live in the Sunbelt, you need only 12.6 W (14 V × 0.9 A) of PV energy.



Fig 4—Connecting panels in parallel is a good way to increase output current from a solar-panel array. A diode is connected in series with each panel to protect the panels from the battery and from the other panels.

Using this basic method, you can calculate the electrical and mechanical dimensions of almost any solar installation; just substitute your power needs into the equations shown here. The sidebar, "Calculating Solar-Cell and Storage-Battery Needs," conveniently shows the required calculations in tabular form.

Some Practical Hints

PV panels can be wired in series to provide increased output voltage. If the total output of the cell array exceeds 20 V, wire shunt diodes across each PV cell. Similarly, PV panels can be wired in parallel to yield increased output-current capability. In this case, use a series diode for each panel, as shown in Fig 4.

When hooking up PV panels to a storage battery, always use a series diode to prevent discharge of the battery into the panels. A Schottky diode can be used in applications where it is important to maintain the lowest voltage drop (and minimum loss) of charge current.

If you live in an area where battery overcharging may occur, take precautions to prevent battery overcharging and related gas discharge inside the battery. Several manufacturers supply simple charge regulators that serve this purpose by disconnecting the PV panel from the battery when the battery is fully charged. Some of these chargers allow charging to resume when the battery has reached a measurable level of discharge. Note: These values are only valid for lead-acid batteries; an entirely different set of charge criteria exists for NiCds.[4]

Installing Solar Panels

If you plan to permanently install PV

Calculating Solar-Cell and Storage-Battery Needs

Calculation of PV solar-cell and storage-battery requirements is easy using this form. See the text for additional information.

Solar Cell

1) Current drain during receive:† ___________ A
2) Number of hours of receiver operation per week: ___________ h
3) Multiply (1) × (2): ___________ Ah
4) Measure peak current drain during transmit:† ___________ A
5) For SSB, enter 0.2; for CW, 0.5; else, 1.0: ___________
6) Number of hours of transmitter operation per week: ___________ h
7) Multiply (4) × (5) × (6): ___________ Ah
8) Add (3) + (7): ___________ Ah
9) Number of hours of sunshine per week (see text): ___________ h
10) Required solar-panel current [(8) ÷ (9)]: ___________ A

The solar panel you select should have at least as much current capability as shown in line 10.

Storage Battery

11) Maximum number of days of operation without sunlight: ___________
12) Daily power requirement [(8) ÷ 7] : ___________ Ah
13) Stored-energy requirement [(11) × (12)]: ___________ Ah
14) Maximum stored-energy requirement [(13) × 2.2]: ___________ Ah

The battery you select should have a capacity at least as large as the total storage requirement found in (14), or the numerical current capacity of the battery (in Ah) should be at least twice as large as the numerical value found in (4), whichever is larger.

†These values are usually given in the transceiver instruction manual.

panels, consider mounting them at ground level on a simple wooden or metal frame, or mounting them on the roof. Roof mounting is more appropriate if you have a roof that slopes at the correct angle (30 to 60°—see the title photo), and in the right direction (anywhere between a little east of south and southwest is acceptable). The easiest way to mount panels permanently is with a silicone adhesive, such as RTV. First, mount series diodes on the back of each panel. Attach color-coded wires to the panels' negative terminal or wire, and to the cathodes of the diodes. If you're using more than one panel, wire them in parallel so that you only need to run one set of leads from the panels to the battery. Secure the wires and diodes with small strips of tape and apply a blob of silicone adhesive to each diode and solder joint.

If the solar panels are going to be located in an area where they might be subjected to lightning, it is especially important to ground the metal frames of the solar panels. Use separate wire for this ground—*do not* combine the panel-frame ground with one of the power leads!

After you have determined where the panels will be positioned, lay them upside down and squeeze a bead of silicone adhesive onto the back of each panel frame. Turn each panel over, lay it on the roof, and tape it down until the adhesive has dried. If you want to go the extra mile, you can mount the panels on blocks so that air can circulate under the panel. PV solar panels, when cool, have slightly higher output than hot panels.

Methods of securing solar panels to wooden or metal frames vary with frame designs; panels may lay in the frame, or you may elect to use brackets and/or bolts. The advantage of a frame mount (as opposed to a more permanent mounting scheme, such as adhesive), is that you can adjust the angle of the panels with respect to the ground, so that you can align the panels for maximum efficiency.

Notes

[1] I use *provide* rather than *generate* to describe the process by which solar energy is transformed into electrical energy. Of course, the energy is generated by the sun; solar cells convert photon energy into electrical energy, and thus *provide* electricity.

[2] For reference, maximum theoretical PV-energy-transfer efficiency is in the 22 to 25% bracket. The optimum has not been reached, but it is pretty well approached (to within an order of magnitude).

[3] Ampere-hour battery ratings are not absolute: You generally cannot, for instance, use a battery with a rating of 2 Ah to supply 10 A for 0.2 h (2 Ah ÷ 10 A), or even 4 A for ½ h. Materials used in battery construction are not made to withstand the heat generated during such extreme operation.—*Ed.*

[4] I intend to describe a simple charge regulator for lead-acid batteries in a future article. Drop me an SASE for more information about charge regulators.

From November 1987* QST*, p 41:

Free NiCd Cells

☐ Many cities and towns have an electric razor repair shop that replaces NiCd batteries in rechargeable electric razors. The razors I've seen contain two NiCd cells. Often, only one of these cells has failed, but both cells are replaced when repair time comes. I talked a razor repair person out of a box of such rejects and got 40 NiCd cells. Twenty of these charged perfectly on the first try! Brief application of heavy overcharging current to the rest of them netted another dozen usable cells. Free NiCd cells? Check your friendly electric razor repair shop.—*Bob Baird, W7CSD, 3740 Summers Ln, Klamath Falls, OR 97603*

From March 1988* QST*, p 41:

A Deep-Cycle Battery as an Emergency Power Source

☐ After I acquired a size 27, deep-cycle lead-acid battery as an emergency power source for my 2-meter transceiver, hams on the local repeater advised me on how to keep the battery charged. "Connect a variable dc supply in parallel with the battery and set its output voltage to 13.6," they said.

The current capability of my power supply is insufficient for such service. The supply can source the 4.8 A required by the rig during high-power transmit, but is rated at only 3 A for continuous duty. Connecting the supply directly in parallel with the battery *and* the transceiver would, at times, result in current drain exceeding the supply's continuous-duty rating.

Fig 2 shows my solution to this problem. Charging current with this circuit is 1 A or less, and the supply can still power the transceiver. Installation of a jumper across points A and B applies the full battery voltage to the transceiver if this is needed during an extended power failure. —*George Hopkins, KF6GL, 521 S Casterock Ter, Sunnyvale, CA 94087*



Fig 2—KF6GL's power supply/charging circuit. In this application, D1 and D2 are 6-A, 600 PIV diodes (Motorola MR756, ECG5815 or equivalent), R1 is a wirewound unit and BT1 is a size 27, deep-cycle, lead-acid storage battery. The jumper is used only during power failures (see text). The power supply is normally turned on only while the station is attended. In tailoring this circuit to your application, use conservatively rated components.

From June 1988* QST*, p 47:

A One-Shot Timer for Battery Charging

☐ One of the problems associated with rechargeable batteries is that of charging duration. This is particularly evident when the charging period is longer than the interval between "home from work" and "back to work"! In such cases, another member of the family must remember to unplug the charger at the appropriate time. My solution to this problem is a one-shot timer. Here's how to build such a timer for around $10.



Fig 1—Dennis Cripp's modified timer turns itself and its associated battery charger off at the end of the charging period. Modification of the timer consists of moving the hot motor lead from point A to point B, and installation of a 120-V neon lamp, DS1, between hot and neutral on the timer's appliance outlet.

Two parts are required: a 120-V neon lamp assembly and a motor-driven lamp timer capable of a timing interval at least as long as the charging period required by your battery. (Both are available in several forms from Radio Shack®.) The motor in such timers usually actuates a switch that breaks the hot side of the ac line for appliance control. Modify the timer as shown in Fig 1. Open the timer and locate the motor lead connected to the hot side of the ac line (point A in Fig 1). Move this lead to the appliance-socket side of the timer switch, S1 (point B in Fig 1). Next, mount the neon lamp assembly at any convenient place on the timer housing, and connect it between the hot and neutral terminals on the timer's appliance outlet. Reassemble the timer.

Connect your battery charger to the timer. Set the timer's on and off actuators to turn on the charger for the charging time required by your battery. To turn on the timer motor and your battery charger, rotate the timer dial until DS1 lights. When the set time has elapsed, your charger *and* the timer motor switch off. Result: a charged battery that won't be overcharged if forgotten.—*Dennis Cripps, N3FIW, 218 N Dillwyn Rd, Newark, DE 19711*

From May 1976 QST, p 25:

Power Amplifier Development with Your Transisitors

Simple test equipment and methods for making-do with devices on hand, on frequencies you want to use.

By Adrian Weiss, W0RSP
833 Duke St 83
Vermillion, SD 57069

One of the more exciting phases of ham radio today is the use of rf power transistors in transmitter amplifier stages. Solid-state design has obvious weight and power-drain advantages, especially in gear that may be used for mobile or portable operation. Development of balanced-emitter rf power transistors, virtually blowout proof and superior to earlier types in regard to stability, gave great impetus to use of all-solid-state equipment in both the hf and vhf ranges.

For the amateur who wants to do other than make exact copies of described equipment, a problem has been lack of understandable information that will permit him to work out transmitter designs for transistors he may have on hand or be able to pick up at moderate prices. Even when good information is available, it may be for only the vhf range, or the circuits described may not necessarily be the best available for amateur-band use. Unlike vacuum tubes, solid-state devices may exhibit wide variations between individual units of the same type. This is in part the result of applications design for top-quality production runs intended for military or space use, whereas the amateur may have to contend with second- or third-level quality. There is also the matter of the practical unreliability of mathematical calculations used in solid-state amplifier design. Johnson and Artigo have noted that competent engineering can produce "ball-park" errors ranging from -22 to +25 percent between calculated values and those that actually work.[1]

Solid-state 40-meter amplifier, built by the author for use with his QRP rig, was tested and adjusted using the methods he describes.



Assumptions

The objective here is to allow the average amateur to circumvent the above obstacles, by placing emphasis on the actual device on hand through in-circuit measurements made during amplifier development. The method is based on several general assumptions which will hold in most cases. A reader unfamiliar with solid-state amplifier basics is encouraged to study papers by Franson, Hayward, Hejhall, and others.[2]

It is assumed that the base input impedance of the amplifier will be quite low, in the range of 1 to 15 ohms. The input matching network must be able to transform this low impedance to whatever is present at the output of the driver stage. This could be 50 ohms, as in using an amplifier with a separate exciter such as one described by the author in an earlier article,[3] and shown in the photograph, or some higher value if the exciter is to be an integral part of a complete transmitter. A reactive component will be present in the base input impedance, so the interstage matching network must tune the base input circuit to resonance, as well. The amplifier will operate properly only when both conditions are satisfied.

Any balanced-emitter device will have an absolute minimum gain of about 6 dB if operating properly. Efficiency will be 45 to 65 percent. At least 8-dB gain is expected normally. On this basis, the drive required for 10-watts output is 1.25 watts. In practice, the writer has found the 2N5590 can be driven to about 12.5-watts output with 1 watt of drive. In another application the 2N5590 delivered 5.5 watts of clean output with only 220 mW of drive – about 14-dB gain. A word of caution is in order here: Maximum efficiency is obtainable only at the collector voltage specified by the manufacturer. Don't expect high efficiency if a 28-volt device is operated at 12 volts

Practical Circuit Details

Hayward discussed choosing values for the base swamping resistor, collector rf choke, bypass capacitors, and other components of the typical Class-C amplifier. Bearing in mind that these criteria are not official "dogma," the reader is advised to familiarize himself with them. There are several usable circuits, descriptions of which can be found in the references and in the RCA *RF Power Transistor Manual*. The author prefers the input network shown in Fig. 1, because it will yield practical component values in nearly all cases.

[1] This and all subsequent footnotes will appear at the end of this article.



Fig. 1 — Schematic diagram and parts information for the K8EEG 40-meter amplifier. Capacitor values not otherwise marked are in pF. Some parts are numbered for text reference only. All grounds should be made directly to the transistor emitter strip. C1, C2 — Final values given; can be made variable as with C3-C4, for experimental purposes.

C4 — 400-pF miniature trimmer. Small broadcast-type capacitors suitable for low-power applications. See text.

L1 — 9 turns No. 22 enamel, closewound on 1/4-inch dia. slug-tuned form.

L2 — 2.5 turns No. 22 enamel, closewound on Amidon T-50-2 toroid core.

L3 — 13 turns, spaced to occupy entire core of L2.

L4 — 4.5 turns, spaced over 1/3 of core.

In using the toroidal circuit for interstage coupling, make L1 1 to 2 turns for 10- to 40-ohm collector load impedance, and 4 turns for 40 to 80 ohms.

If the amplifier is to be used with a separate exciter, as in this instance, the input network is designed and adjusted to match the low-base input impedance to 50 ohms, the usual output impedance of such an exciter. Where the amplifier is to be part of a transmitter, the collector circuit of the driver can be connected in place of J1. To provide for matching the capacitors C1 and C2 should be made variable in this case. A better way would be to make a toroidal matching transformer similar to L2-L3-L4, using slight alterations for this application given under Fig. 1. In the first case there are two unknowns present: The output capacitance of the driver and the input impedance of the amplifier base. This makes optimum adjustment rather complicated, since the output capacitance of the driver stage varies with its collector load impedance. With the tuned circuits in both stages, the driver can be optimized for 50 ohms and will work equally well when the amplifier is installed.



Fig. 2 — Simple test equipment used in optimizing the solid-state amplifier includes a wavemeter, A, a power-output indicator, B, and a variable impedance bridge, C. Values of L1 and C1 depend on the band being checked. Parts designations are for text reference.

There are additional advantages. The tuned network will provide at least twice the harmonic rejection, and there will be much less loading of the previous stages by the final amplifier. The latter is very important in simple VFO-controlled transmitters, where pulling of the oscillator can result in considerable difference in frequency between the SPOT and OPERATE conditions.

The circuit used for the output network is a matter of personal preference. The double-link tank shown yielded an efficiency in excess of 50 percent at 7 MHz, so it was left in. In a 20-meter application the efficiency was about 40 percent. Conversion to the network described by Hayward (reference 2) brought the efficiency up to 62 percent.

Test Equipment

Three simple instruments, shown schematically in Fig. 2, were used in the development of the amplifier: A roughly calibrated wavemeter capable of tuning to the desired frequency and to its second harmonic, a power-output indicator, and an impedance bridge. The wavemeter, Fig. 2A, was calibrated with the aid of a multiband transmitter.

The power-output meter, Fig. 2B, should be isolated from the transmitter and dummy load by shielding and RFC2. Actual output is obtained from the formula:

$$P_o = \frac{V^2}{2R_1}$$

The meter is used to measure power output from a driver or amplifier stage during developmental work. Remember that it is not frequency sensitive. It will read combined fundamental and harmonic power, hence the need for the wavemeter.

The variable impedance bridge, Fig. 2C, is similar to one described by Hayward (reference 2) except that the diode is connected to the arm of a 1000-ohm variable control, instead of to the junction of two 470-ohm resistors. The control can be calibrated by connecting fixed resistors of known value across the output. Adjust the control for null, and mark down the resistance value used for that setting. When you want a circuit to look like, say, 70 ohms, you set the control to 70 and adjust the circuit for null. Parts placement is not critical, but it is wise to use short lengths of coaxial line in connecting the bridge into the circuit to be tested, and to ground both braids at the same point.



$$X_{L1} = Q_L R_2$$

$$X_{C2} = \frac{R_2 (Q_L{}^2 + 1)}{Q_L} \bullet \frac{1}{\left[1 - \frac{X_{C1}}{Q_L R_1}\right]}$$

$$X_{C1} = R_1 \sqrt{\frac{R_2 (Q_L{}^2 + 1)}{R_1} - 1}$$

Fig. 3 — Basic circuit for use with Tables 1, 2 and 3. Circuit A, for Tables 1 and 2, shows the network for input matching. B is used in matching the amplifier to 50-ohm output. The formulas are for operating conditions other than those assumed in the tables.

If the bridge is to be used only between 50-ohm circuits, coaxial connectors will be suitable, as shown.

Construction and Testing

Armed with the above assumptions and test equipment, we can monitor several aspects of the circuit operation in the process of getting the amplifier to work properly. This is a rough duplication of the procedure followed in the manufacturer's laboratory in determining the performance characteristics of a device for given sets of conditions. These appear later on a data sheet. Our purpose is not quite the same, in that we are not looking for a set of "numbers." Rather, we seek to take into account automatically the actual characteristics of the device *on hand*, in achieving optimum operation for our application.

An experimental amplifier can be bread-boarded or built on a circuit board similar to the one shown. It is recommended that a single parallel-tuned circuit be used for the output side of the amplifier during developmental work on the input matching. It can be replaced when the work is completed. Calculated values for both input networks, and the output network, Fig. 3A and B, respectively, are given below for the hf bands.

Table 1
Input network, R1 = 50Ω, R2 = 5Ω, Q = 5.

	3.5	*7*	*14*	*21*	*28 MHz*
X_{L1} = 25Ω	1.25	0.63	0.29	0.2	0.18 µH
X_{C1} = 31Ω	1400	700	380	260	170 pF
X_{C2} = 64Ω	750	370	180	150	85 pF

Table 2
Input network connected to driver stage collector and load impedance of 70 ohms (1.25 watts at 12 volts dc), R1 = 5Ω, Q = 5.

		3.5	*7*	*14*	*21*	*28 MHz*
X_{L1}	40	1.25	0.63	0.29	0.2	0.18
X_{C2}	21	1700	1100	580	380	260
X_{C1}	64	750	370	180	150	85

Table 3
Output network, final collector impedance 8Ω, (10 watts output at 13.6 volts dc), 50Ω load. (From Motorola AN-267.)

		3.5	*7*	*14*	*21*	*28 MHz*
X_{L1}	40	2.0	0.95	0.49	0.3	0.23
X_{C1}	65	720	350	175	125	90
X_{C2}	89	530	260	140	90	65

The formulas given in Fig. 3 can be used to calculate approximate values, should the driver stage operate at a different power level or load impedance. C1, C2, and L1 should be variable, to allow for initial adjustments. Inexpensive broadcast-receiver capacitors, 365 pF, are ideal for tuning. Where higher capacitance is needed, fixed-value micas can be connected across the variables. A 40-meter amplifier is shown in Fig. 1 with component values arrived at by experiment, as described below.

Apply at least 500 mW of drive to the network through the impedance bridge. The network is adjusted for deepest null, first by C1, where the indication will be broad, then by C2, which gives a deeper null, and finally by L1. This is done with the wavemeter coupled to the final-amplifier tank, and the output meter connected to the tank as an indicating load. No dc voltage is applied to the amplifier thus far, as only the feed-through energy will be monitored at this point. With one watt of drive there should be 5 to 15 mW showing on the output meter, when the latter is tuned to the drive frequency. Remove the impedance bridge and repeak slightly for maximum feed-through indication.

Set the wavemeter to the second harmonic frequency. If the drive is clean and the circuits are properly tuned, there should be little or no output detectable at the harmonic frequency. Recheck tuning for minimum harmonic level, if any shows. Optimum adjustment should give maximum fundamental output and rejection of harmonic output.

Apply collector voltage, with no drive. If the transistor is the balanced-emitter type, full collector voltage may be used. With other types it is well to start with about 70 percent of the maximum. De-couple the wavemeter, in anticipation of the 40-dB increase in power to be expected, and apply drive. Readjust both input and output networks for maximum output and minimum harmonic power. The wavemeter should be coupled to the lead going to the output meter for the latter check, as harmonic currents circulate in the output tank, and coupling to it will give an erroneous reading of harmonic level when the amplifier is running normally. Measure the dc input power and the rf output power and compute the efficiency which should be at least 40 percent. Substitute the double-tuned tank circuit for the simple parallel-tuned one, if the output is low.

If an external exciter is to drive the amplifier, no further adjustment is required, and the amplifier is ready for service. If you intend to connect the input network directly to the driver collector, the impedance bridge is set to the desired collector load impedance Figure (70Ω for 1.25 W at 12 V), and adjustment is made for best match. Each of these steps monitors some aspect of circuit operation, using the actual components available, and gives assurance that optimum results are being obtained.

The amplifier shown in the photograph was adjusted by these methods and was ready for use, in the last hours before Field Day, in about a half hour after it was assembled. Running at reduced power, it gave a good account of itself on 40 meters the following day, using the exciter previously described by the writer.

References

[1] Johnson and Artigo, "Fundamentals of Solid-State Power Amplifier Design," Part III, *QST*, April, 1973.

[2] Franson, "How to Use RF Power Transistors," *Ham Radio*, January, 1970. Hayward, "Increased Power for the Solid-State Amplifier," *QST*, May, 1972. Lowe, "15-Watt Solid-State Linear," *QST*, December, 1971. Hejhall, "Broadband Solid-State Power Amplifiers," *QST*, March, 1972. Schoening, "Transistorized Amplifier for 40 Meters," *73*, August, 1964. White, "Thermal Design of Transistor Circuits," *QST*, April, 1972.

[3] Weiss, "Multiband FET VFO QRPp Transmitter," *Ham Radio*, July, 1972.

From October 1978 QST, p 34:

On Solid-State PA Matching Networks

☐ I would like to pass along some observations I've made which are of interest to builders of solid-state Class C hf transmitters.[1] I have found that the use of such matching networks as the commonly recommended L and T,[2] as well as any other network with an inductor or series LC as the input element,[3] will inevitably result in improper circuit operation. The circuit will exhibit poor collector efficiency, spurious output, or a high transistor failure rate, unless one of these conditions is met: (1) the output transistor is very rugged (in which case it won't fail, but the other conditions will remain); (2) the transistor output capacitance is 100 pF or higher; (3) a Zener diode is connected across the transistor (more about this later); or (4) the network is modified in a manner I will describe.

Let's see what causes the problem. Although there is an optimum resistive impedance for a transistor to "see" (approximately $V_{CC}^2/2P_O$),[4] the transistor does not present this or any other impedance. Rather, it acts much as a simple on-off switch. At the instant the transistor is turned off, current flowing through the rf choke is dumped into the circuit elements. The dominant circuit presented to this current is parallel resonant, with L being the network input inductor and C the transistor output capacitance, C_O. C_O is in parallel with stray circuit capacitance. This circuit "rings" at its resonant frequency, which is not necessarily related to the operating frequency.

Fig. 1 shows the schematic of a typical 40-meter, 2-watt-output amplifier. Fig. 2A is a photo of the oscilloscope waveform at the collector of Q1. The presence of 70-volt, 50-MHz ringing at the collector may be readily seen. I was able to obtain this picture only because the particular transistor was exceptionally rugged — several devices were destroyed in the attempt. Although this condition could be detected with a wavemeter coupled loosely to the collector circuit, it can only be observed with the aid of a wide-bandwidth scope. The instrument used to obtain these photos has a 250-MHz bandwidth.

Fig. 1 — Schematic diagram of the 7-MHz Class C amplifier used to examine the oscillation problem.



A photo of the waveform at the load is shown in Fig. 2B. Distortion may be reduced by filtering, but — assuming the transistor is not destroyed — collector efficiency will be less than optimum. Typical efficiency will be on the order of 40 to 60 percent, rather than the 70 to 80 percent obtained from a well-designed amplifier stage.

An advanced circuit-analysis computer program was used to investigate the circuit of Fig. 1, assuming perfect inductors, capacitors, source, load and a good model of the 2N3866 transistor. The graphical results of this analysis are shown in Fig. 3. Because of the use of perfect components, frequency and amplitude of the simulated waveform vary slightly from the real waveforms shown in Fig. 2. The striking similarity to Fig. 2 and the presence of ringing in the simulation verify that the phenomenon is *not* a spurious oscillation in the usual sense, nor is it due to stray capacitance or inductance or poor circuit layout. *It is inherent in the use of this type of network!*

Fig. 2 — Photos of the actual waveforms obtained with the amplifier. Operation was observed with a high-speed oscilloscope. At A, collector waveform; at B, waveform at the output.



(A)

(B)



Fig. 3 — When the circuit of Fig. 1 was analyzed on a computer, the waveforms shown were predicted. The solid line indicates how the computer expected the waveform at the collector to look. Expected output waveform is shown by the dotted line.

A capacitor connected from the collector to ground or, preferably, from collector to emitter, will solve the problem if it approximately resonates with the input inductor at the operating frequency. The capacitor will reduce collector-voltage swing to less than 30 volts with a 12-volt supply. The effect on the Q of common networks will be negligible and only slight readjustment of the variable capacitor(s) will restore the correct match.

A Zener diode connected across the collector will sometimes solve the problem, but not because of Zener action! A typical 33-volt, 1-watt Zener diode has a capacitance of 200 to 800 pF, depending on the amount of reverse bias. This is generally sufficient to prevent the ring in the first place.

This letter has been necessarily brief but I hope it will enable the reader to take advantage of these matching networks without wondering — as I did for a long time — why sometimes they work and sometimes they don't. — *Roy W. Lewallen, W7EL, 5470 S.W. 152 Ave., Beaverton, OR 97005*

Footnotes

[1] Strictly speaking, the Class C amplifiers used by amateurs may be better described as Class D, as they are typically driven to saturation. In fact, this is the reason for the problem described here. However, such operation does allow high collector efficiency. For a more detailed discussion of this topic, see Sokal and Sokal, "Class E — A New Class of High-Efficiency Tuned Single-Ended Switching Power Amplifiers," *IEEE Journal of Solid-State Circuits*, Vol. SC-10, No. 3, June, 1975.

[2] Hayward and DeMaw, *Solid State Design for the Radio Amateur*, ARRL, 1977, pp. 52-53.

[3] *The Radio Amateur's Handbook*, 54th Edition, 1977, ARRL, p. 161.

[4] Hayward and DeMaw, p. 24.

From January 1980 QST, p 55:

More on Solid-State PA Matching Networks

☐ When I experimented with Class C tuned transistor PAs about a decade ago I noticed the same phenomenon that W7EL reported in October 1978 *QST*. I also had the impression that the matching sections derived from vhf/uhf circuits are insufficient for hf power amplifiers.

The solution I adopted to cure this is somewhat different, however. I also place a capacitor (Cp) from collector to ground, but, as a starting value, the reactance (X_{Cp}) of this capacitor is about the same as the collector load resistance ($X_{Cp} = Vcc^2/2P_o$), giving a loaded Q of 1.

In multiband transmitters, therefore, the collector choke remains the same and is chosen for the requirements of the lowest band in use (typically 80 µH for an 18-volt, 2-watt output PA). The capacitor, Cp, is being switched from band to band together with the other tank-circuit components.

The loaded Q = 1 will stop the "ringing" phenomenon, but will also decrease the efficiency to 50 to 60 percent. On the other hand, the PA becomes very insensitive to mismatch, even at full drive. For better efficiency and slightly reduced mismatch safety the loaded Q may be reduced to about 0.7. In higher power PAs where transistors with high internal capacitances are used, the Q may be reduced even further, depending on the efficiency obtainable.

I purposely place this capacitor (Cp) from collector to ground, not to the emitter. As an additional measure for mismatch protection I recommend a small, unbypassed emitter resistor, which causes a dc drop of about 0.5 volt when the stage is tuned correctly. Placing Cp to the emitter in this case would form a *regenerative* circuit.

When using vhf/uhf transistors for hf PAs I further recommend reducing Vcc to 0.5 $Vceo_{(sus.)}$ or less for fail-safe operation, because the breakdown voltages are lower at dc and lower frequencies than at vhf/uhf.

Another trouble which may show up in tuned Class C transistor PAs is *frequency dividing*. The tank circuit, therefore, must have a configuration without any resonance at one half, one third, etc., of the operating frequency. This is especially important if multisection pi networks are to be used for high harmonic suppression, or if a low-pass L section is to be added for antenna tuning.



Fig. 2 — Details of the parallel-resonant circuit.

Subharmonic resonances may be avoided by incorporating a parallel-resonant circuit (Fig. 2) or a series-resonant circuit (Fig. 3). The components marked * are selected by means of the band switch. I have been using the circuit of Fig. 2 in my portable 5-band QRP transmitter (2N3553 PA) since 1969. It will match all random-length wires as well as coax-fed antennas.

The circuit of Fig. 3 will have somewhat better harmonic suppression, but the antenna must be safety-grounded by means of a separate choke. Therefore, this scheme will be good for coax-fed antennas and may take a rather high SWR, up to 3:1. — *Hans-Joachim Brandt, DJ1ZB, Lohensteinstrasse 7/b, 8000 Munich 60, Federal Republic of Germany*



Fig. 3 — Circuit for the series-resonant condition.

From May 1984 QST, p 26:

Broadband and Narrow-Band Amplifiers


I AM A BROADBAND AMPLIFIER AND I COVER A WIDE FREQUENCY RANGE.
I CAN ONLY COVER A NARROW FREQUENCY RANGE.
N2EST

Narrow-band amplifiers have been around for many years, and most hams know how to design them. But, the broadband RF amplifier did not become popular until the semiconductor world bloomed. This article covers some practical aspects of both types.

By Doug DeMaw,* W1FB

Have you wondered what the difference may be between a narrow-band amplifier and a broadband one? Are all broadband amplifiers linear? Must they be linear? These are natural questions in the minds of most beginners to electronics, so we will try to provide simple answers.

If you work with transistors and RF circuits, it is likely that you will need to know something about how a broadband amplifier is designed, what to expect from it and how to build one for the job you have in mind. For the most part, these amplifiers are less prone to self-oscillation than are tuned, narrow-band styles of amplifier. The fundamental thought to keep in mind however, is that we must always trade some overall gain for increased bandwidth. If we can accept that trade-off, the major barrier will have been abolished.

Narrow-Band versus Broadband

The narrow-band amplifiers we use from day to day in our VFOs, receivers, converters and transmitters are *tuned* to some particular operating frequency. The tuned circuits are usually designed to yield a fairly high loaded Q (Q_L). The greater the circuit Q, the narrower the frequency response of the amplifier. Many applications require high Q and the attendant narrow bandwidth. Examples are VFOs, receiver front ends, transmitter tank circuits and filter circuits that contain an amplifier.

The narrow bandwidth is needed to reject unwanted signals above and below the desired operating frequency, and to prevent spurious energy from leaving the transmitter and reaching the antenna system. When broadband amplifiers are used in some of these more critical circuits, a filter of some kind must be used to obtain the desired spectral purity. By way of simple explanation, a broadband amplifier that has no filtering elements is merely an *untuned* amplifier. It will respond to a broad range of frequencies and, if designed well, should have relatively constant gain across that frequency range. An audio amplifier is but one example of a broadband amplifier.

Another advantage of the narrow-band circuit over the broadband type is that some circuits require minimum noise — as in the case of a receiver oscillator strip — and the high-Q tuned circuits greatly reduce the inherent noise output of the oscillator. High-performance receivers require "quiet" local oscillators in order to minimize "reciprocal mixing" in the mixer stage. Transmitter local oscillators should be similarly clean if we are to avoid broadcasting prohibitive amounts of broadband noise along with the desired signal output. Some commercial early-day solid-state transmitters were very offensive in terms of transmitted wideband noise.

Fig. 1 shows examples of narrow band and broadband amplifiers in some simplified circuits. Illustration A shows a conventional small-signal RF amplifier with tuned circuits at the input and output. This is typical of what we may find at the input of a receiver. The high-Q tuned circuits or resonators restrict the frequency response for a given setting of C1 and C2. For this reason we will call our circuit a narrow-band amplifier.

Although the circuit at 3 of Fig. 1 is an oscillator, it is in reality a form of amplifier. For an oscillator to work as such it must be designed as an amplifier. Some of the output energy is fed back to the input terminal to cause oscillation. Again we have a high-Q tuned circuit (C3, C4 and L1), which restricts the bandwidth of the circuit in accordance with the particular setting of C3. Owing to our use of some of the output power as feedback, this type of amplifier is not as efficient as is the circuit in Fig. 1A.

Fig. 1C contains an example of a broadband amplifier for RF use. It operates linearly because it is biased for class A. T1 is a broadband transformer that can be used to match the amplifier impedance to that of the load by virtue of the transformer turns ratio. Note that T1 is untuned; hence the bandwidth.

A class-A linear broadband amplifier

---

*Contributing Editor, P.O. Box 250, Luther, MI 49656



Fig. 1 — The diagrams at A and B illustrate narrow-band amplifiers. The VFO circuit is still a form of amplifier, since its output power (in part) is fed back to the input for the purpose of causing oscillation. A simple Class-A broadband amplifier without feedback is seen at C. A fed-back Class-A broadband amplifier is shown at D. It uses a combination of shunt and degenerative feedback (see text).

with feedback is shown at D of Fig. 1. Here, we have intentionally introduced feedback by means of resistive divider R1/R2 and C1. Degenerative feedback is provided by means of the unbypassed emitter resistor, R3. This type of amplifier has considerable bandwidth. The shunt feedback stabilizes the current gain of the stage while decreasing the input and output resistance of the amplifier. The emitter degeneration helps stabilize the transistor voltage gain, and it increases the input impedance of the transistor. The increase is approximately proportional to the transistor beta. A specific treatment of feedback applied to broadband amplifiers is contained in *Solid State Design for the Radio Amateur,* available from ARRL.

Amplifiers with feedback are used not only for low-power circuits, but are practically the order of the day for high-power solid-state RF amplifiers. A circuit for a broadband, fed-back linear amplifier is provided in Fig. 2. Since this diagram is purely for illustrative purposes, no component values are assigned.

Assume that the circuit is capable of delivering 100 W of output from 1.8 to 29.9 MHz. Shunt feedback is made possible by the networks that contain R1, R2, R3, R4, C1 and C2. Here, we are applying negative feedback between the collectors and bases. Were we to use positive feedback, as in the case of oscillators, the amplifier would "take off" in a spasm of self-oscillation. *Positive* feedback is of the same phase as the input energy, whereas *negative* feedback is approximately 180 degrees out of phase with the input signal. This relationship is important to remember. An absolute 180-degree phase shift is difficult to realize when working with transistors, owing to some inherent phase shift as the signal current passes through the semiconductor material.

T1 and T2 of Fig. 2 are broadband transformers whose frequency response, if they are designed well, is reasonably flat across the 1.8-30 MHz range. Generally, ferrite core material of 800 to 950 effective permeability (μ_e) is used for high-frequency broadband amplifiers. This is a no. 43 material when ordering from Amidon Associates or Fair-Rite Corp.[1] Palomar Engineers and RadioKit also supply cores of the no. 43 variety. Core permeabilities of 125 and 40 are commonly used for VHF broadband transformers.

Broadband transformers work like this: As the operating frequency is increased, the core material becomes less and less effec-



Fig. 2 — A simple example of a push-pull broadband RF power amplifier. T1 and T2 serve as broadband transformers. Shunt feedback is included to help level the amplifier gain over a wide frequency range. A harmonic filter (FL1) is required at the amplifier output.

---

[1] Notes appear at end of article.

tive in the circuit. At the low-frequency end of our transformer range, the core does its job and increases the inductance of the windings (necessary). At the high end of the transformer performance range, the core becomes essentially "not there" as far as the windings are concerned. This enables us to obtain a substantial bandwidth that would be impossible with coreless transformers. A suitable rule of thumb for transformer design is to make the inductive reactance of the smallest winding approximately four times the load impedance. Hence, if the base of a transistor amplifier exhibited a 10-ohm impedance, the broadband-transformer winding that we connect to the base should have sufficient inductance to have a reactance of 40 ohms or slightly greater. If not, the low impedance of the winding would shunt part of the driving power to ground and could cause an SWR condition.

Let's assume that our amplifier is operating at 7.1 MHz. The base impedance of the transistor with drive applied is 12 ohms. How much winding inductance would we need for the transformer secondary? The standard equation for inductance would be used:

$$L(\mu H) = \frac{X_L}{2\pi f(MHz)} \qquad \text{(Eq. 1)}$$

So, with an X_L of 4 times 12, we would obtain the following answer:

$$L(\mu H) = \frac{48}{6.28 \times 7.1} = 1.07 \qquad \text{(Eq. 2)}$$

The required number of turns can be calculated from

$$\text{Turns} = 100\ \sqrt{L(\mu H)/A_L} \qquad \text{(Eq. 3)}$$

where A_L is the number provided for each type of core by the vendor or manufacturer. Each core, relative to its cross-sectional area and the core material, has a specific A_L factor. The Amidon Associates catalog contains such data, as does a book concerning magnetic cores.[2]

I don't want to mislead you into thinking that broadband amplifier design is a snap. There are many subtleties involved, and considerable study of the pertinent literature is important before launching one's own project from scratch. Motorola Semiconductor Company has a wealth of useful data in its book on power semiconductors, inclusive of application notes on transformer and broadband amplifier design.[3]

But, let's return to Fig. 2 and learn a bit more about what's going on. T2, the output transformer, serves also as an impedance-matching device. The inductances in the transformer windings are based also on a ×4 rule, respective to the collector impedance. This impedance can be calculated closely from $Z = V_{cc}^2/2\,P_o$ ohms. Eq. 1 is then applied. FL1 is a harmonic filter, and is a low-pass type. A switch can be inserted at points X and Y to permit band switching of the low-pass filters. This is standard procedure in commercial equipment. For single-band use, a jumper can be placed across X and Y.



Fig. 3 — Examples of conventional and transmission-line transformers. See text for additional information.

It is important in all broadband amplifiers to minimize the stray capacitive and inductive reactances. These parasitic quantities of L and C have a marked effect on the amplifier performance as the operating frequency is increased. In other words, unwanted capacitive and inductive reactance will limit the upper frequency response of the circuit. An improperly designed broadband transformer will degrade the performance in a like manner.

If we are to minimize the presence of stray reactance, we must use large or very short circuit-board strips. This will reduce the effective inductance of the PC-board foils. These copper strips should also be as direct as possible. Similarly, the connecting leads of resistors and capacitors must be held to a minimum length. Many amplifiers contain chip resistors and capacitors to keep stray inductance and capacitance to a minimum. These components are supplied without leads or "pigtails." They are soldered directly to the PC-board foils. They are practically a requisite at the upper end of the HF range and higher, but they are more costly than are silver-mica or disc-ceramic capacitors.

Conventional or Transmission-Line Transformers?

I'm sure you've heard designers speak of "conventional" and "transmission-line" transformers. The so-called conventional transformer is built along the lines of an audio or power transformer. That is, it has a core and separate windings, as in Fig. 3A. The transmission-line transformer, on the other hand, has bifilar, trifilar or quadrifilar windings that are placed on the core in parallel, or they may be twisted together beforehand. In this case, each winding conductor is the same length. The windings function as short lengths of transmission line, and the impedance is generally 25 ohms. Either style of transformer can be used in a broadband amplifier, or as a matching transformer in other types of circuits, such as antennas.

The conventional transformer is considered less efficient than the other type, but it enables us to obtain nearly any turns ratio we desire. The transmission-line transformer (Fig. 3B) yields only specific integers of transformation, such as 4:1, 9:1, etc. Furthermore, we can find ourselves rather frustrated when trying to hook up a multiwire transmission-line transformer, especially if the same size and color of wire is used for the windings. Many engineers use enameled wire of various colors to avoid this problem. Green, red and brown wire is often used. You can solve the problem by dipping the wires in different colors of paint before using them. I have had good results by spraying the wires with fast-drying paint.

A Handy Broadband Amplifier

Many times we find ourselves in need of a little extra "push" when working with a scope or frequency counter. Perhaps the sampling point in the circuit has insufficient signal voltage to trigger our frequency counter or cause ample deflection on the face of the scope tube. A broadband amplifier is useful at such times to give that weak signal the needed boost.

Our workshop project this month is shown schematically in Fig. 4. It is patterned along the lines of a broadband amplifier designed by Hayward, W7ZOI. His design did not use transformers and there was no high-level stage at the tail end of the amplifier strip, but the feedback networks are similar to his. The particulars of the general design are given in the text of *Solid State Design for the Radio Amateur,* referenced earlier in this article.

CATV transistors are used to ensure good bandwidth (1.2 GHz f_T) and linearity. Each stage is biased for linear Class-A operation. A combination of shunt and degenerative feedback is used throughout the circuit. The input of each amplifier is roughly 50 ohms, and each output is approximately 200 ohms with the values given. Amplifier stability is excellent, even when there is no termination at the input and output ports. Circuit boards and parts kits for this circuit are available.[4]

The bandwidth is flat from 400 kHz to 34 MHz (within 1 dB). I measured the overall gain as 41 dB. The maximum-acceptable output, in terms of distortion, is 0.25 W. The circuit draws 90 mA of current with a supply voltage of +13.

Owing to the linearity and bandwidth of the circuit in Fig. 4, it is ideal as a drop-in


BROADBAND LINEAR AMPLIFIER
EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS; k = 1000
SIG IN
50 Ω
0.1
3.3 k
560
2N5179
Q1
1k
10
100
T1
4:1
68
Q2
180pF
T2
18k
2N5109
Q3
6.2
1/2 W
33
1/2 W
T3
33
1 W
SIG OUT
50 Ω
X
Y
JUMPER
22 μF
25 V
+12 V
* CROWN HEAT SINK
CASE
COLLECTOR
EMITTER
BASE
Q1, Q2 BOTTOM VIEW
Q3

Fig. 4 — A practical circuit for a broadband linear-amplifier strip. This can be used as an instrument amplifier, a low-level RF strip in a transmitter or as part of a receiving-loop preamplifier. Resistors are ¼-W carbon-composition unless otherwise noted. The polarized capacitor is tantalum or electrolytic. All others are chip-style or disc-ceramic with short leads. T1 and T2 contain 15 primary turns of no. 28 enameled wire on an Amidon FT37-43 toroid core. The secondary windings consist of seven turns of no. 28 enameled wire. T3 uses an Amidon FT50-43 toroid core with 12 primary turns of no. 26 enameled wire. The secondary of T3 contains six turns of no. 26 wire.


CIRCUIT BOARD SPECIALISTS PO BOX 969 PUEBLO, CO 81002
BB LINEAR AMP
X
Y
1"
(25.4 mm)

Fig. 5 — Circuit-board etching pattern for the broadband amplifier of Fig. 4. The pattern is shown full size from the foil side of the board. Black areas represent unetched copper foil.


OUT
T3
Q3
0.1 μF
1.8 kΩ
180 Ω
1 kΩ
33 Ω
1 W
1/2 W
6.2
22 μF
25 V
T2
Q2
3.3 kΩ
560 Ω
1 kΩ
180
10 Ω
100 Ω
68 Ω
T1
Q1
IN
+12 Vdc
JUMPER

Fig. 6 — Parts-placement guide for the broadband amplifier of Fig. 4.

unit for an HF-band CW or SSB transmitter. It can be used as the low-level section of such a transmitter. I wish to caution you, however, that it should not be used for QRP operation unless a suitable harmonic filter is placed between the amplifier output and the antenna. A half-wave style of filter should be suitable if you want to try your hand at low-power operation.

Terminals X and Y on the circuit board are available for use as a standby point, or for CW keying. If a keying line is attached at X and Y, be sure to include a shaping network so that your signal won't sound clicky.

This amplifier can be used also as a preamplifier for loop antennas. A step attenuator can be inserted at the output of the amplifier to control the gain. If you choose to use this circuit in such a manner, a low-noise preamplifier should precede Q1 of Fig. 4. I find that a JFET stage is suitable for this purpose. Owing to the small signal that a receiving loop provides, the preamplifier (even at 1.8 MHz) must be a low-noise type. If not, you will enjoy listening to "pop-corn" noise along with the DX signals! Q1 does not have a low enough noise figure for satisfactory weak-signal reception.

Construction

If you choose to make your own PC board for this project, try to keep all stages in a straight line. Keep the PC-board foils short and direct. Minimize the lead length of each capacitor and resistor. Make sure the transistors are seated close to the PC board in order to keep their leads as short



Fig. 7 — The assembled broadband amplifier. Note that in-line layout is used.

as possible. A crown heat sink is needed on Q3, the 2N5109. A coating of silicone grease should be applied to the transistor cap before installing the heat sink. Double-sided PC board is recommended in the interest of stability. Fig. 6 shows the parts placement for the circuit board, as seen from the component side. A scale template of the PC board pattern is provided in Fig. 5. Fig. 7 is a photograph of the assembled amplifier.

Some Final Remarks

I hope you have learned the basics about narrow-band and broadband amplifiers. Certainly, we've only scratched the outer layer of the subject. A thorough treatment would require several *QST* installments. Our purpose this time is to explain the difference between amplifier types, and to provide a project that would enable you to try your hand at broadband amplifier construction and use.

A broadband amplifier can be built for Class A, B or C service, just as narrow-band amplifiers can. The advantage of broadband designs is, in retrospect, to obtain a wide frequency response with relatively flat gain. This helps us to design circuits that do not require band-switching provisions. In other words, it simplifies the design of a multiband transmitter. But, as an instrumentation amplifier, the circuit of Fig. 4 has a great many advantages around the workshop. Good luck with your project.

Notes

[1] Amidon Associates, 12033 Otsego St., N. Hollywood, CA 91607 (catalog available). Fair-Rite Products Corp., 1 Commercial Row, Walkill, NY 12589. See *QST* ads for Palomar and RadioKit.

[2] D. DeMaw, *Ferromagnetic Core Design & Applications Handbook*, no. 0-13-314088-1 (Englewood Cliffs, NJ: Prentice-Hall, Inc.).

[3] *Motorola RF Data Manual*, Motorola Semiconductor Products, Inc., P.O. Box 20912, Phoenix, AZ 85036.

[4] Circuit Board Specialists, P.O. Box 969, Pueblo, CO 81002, tel. 303-542-5083.

For updated supplier addresses, see ARRL Parts Suppliers List in Chapter 2.

From September 1984 QST, p 19:

Electronic Switching and How It Works


I'VE BEEN SWITCHING CIRCUITS FOR YEARS!
TIME TO RETIRE, OLD TIMER. I CAN DO THE JOB BETTER!

Replace those old-fashioned toggle switches with up-to-date diodes and transistors and you'll have simpler, less expensive and less cumbersome circuits.

By Doug DeMaw,* W1FB

What could be more ordinary than a switch? True, they are not very spectacular devices, but few circuits can be made to function without some type of switch — mechanical or electronic. Electronic switching is not new, but the state of the switching art has moved forward in grand style since semiconductors became as common as patent medicines. Furthermore, the cost of a solid-state switching device (diode, IC or transistor) is generally less than that of a comparable mechanical unit, such as a toggle switch.

Substantial levels of ac and dc power can now be switched by means of large diodes, power FETs, Triacs, and the like. Also, relatively high potentials can be accommodated safely by some rather small semiconductor components. At the dawning of our solid-state era, we were able to switch low amounts of signal and dc, and at fairly low voltage levels. It seemed in those days that the technology was not going to offer much promise toward replacing cumbersome manual switches with tiny diodes or transistors, but the trend today is clearly toward semiconductor switches. Amateurs can take advantage of the many options presented by solid-state switches, so let's examine a few basic concepts and see how we can develop practical circuits that use diode and transistor switches. First, in the interests of accuracy, let's look at the shortcomings of electronic switches.

Some Limitations

There is no magic in the electronic-switching art. In other words, we can't achieve everything that mechanical switching offers. But, we can come close to realizing the concept of universal replacement of mechanical switching components. What are the trade-offs? First, high-power RF switching is still a tough assignment with present-day low-cost transistors or diodes. Second on the list of not-so-neat features is that large solid-state switches need heat sinks of substantial size, and they may also call for cooling fans. This results in mass and expense that is not acceptable for amateur projects. High-power switches can become larger and more costly when using semiconductors. Number 3 on my list is the inherent internal resistance of most solid-state switches: It is seldom possible to have a zero resistance through a semiconductor switching device. Although the resistance of such a semiconductor junction in the ON mode may be only a fraction of an ohm, it can be enough to cause a problem. Some semiconductor switches have internal resistances greater than an ohm when activated. This becomes a source of difficulty at high power (heating and voltage drop by virtue of the I^2R rule), and in certain types of switching circuits it means that *complete* switching is not possible. For example, the internal resistance of a power FET is specified as RDS (resistance from drain to source) when it is switched to the ON state. This will vary with the device, and can range from 0.5 ohm to a few ohms, depending on the particular FET chosen. Well-designed mechanical switches, on the other hand, will exhibit a nearly zero-resistance condition between the contacts.

How else might we vilify the solid-state switch? Well, we should mention that input-output isolation is seldom of the magnitude that we can obtain with a suitable mechanical switch. This is caused by the semiconductor internal resistance and capacitance. It is a concern mainly when we wish to use a semiconductor to switch a signal line; for dc applications it is not a matter of importance. Finally, in many circuits that contain electronic switches, we need to actuate them by means of a mechanical switch. However, it is often practical to control dozens of electronic switches simultaneously with a single SPST mechanical switch, and therein lies the advantage!

Some Basics

Fig. 1 illustrates the fundamental principle of mechanical and solid-state switching. Assume we wanted to apply dc to a specific module. Example A shows the mechanical means to do this. Circuit B relies on a bipolar transistor to switch the dc on and off. The dashed lines show that the base of Q1 must be grounded to actuate the circuit. This can be managed by the use of a mechanical switch, or by triggering Q1 with another semiconductor switch elsewhere in the system. The use of a PNP transistor permits application of the + 12 V to the emitter, and also enables us to turn Q1 on by grounding the base through R1. If we used an NPN transistor at Q1, we would need to apply + 12 V at R1 in order to saturate (switch) the transistor. Also, the + 12 V of operating potential would have to be fed to the collector rather than to the emitter, as shown.

By grounding the PNP-transistor base, or through applying + 12 V to R1 of an NPN device, we are providing what is called *forward bias*. This causes the transistor to conduct heavily, which makes it perform the switching function. Too much current, caused by excessive base-emitter voltage, can destroy the transistor. Therefore, a series resistor is used (R1). Too little forward bias, conversely, will prevent the transistor from saturating com-

---

*ARRL Contributing Editor, P.O. Box 250, Luther, MI 49656


SIG. IN
MODULE
SIG. OUT
+12 V
S1
ON
ARROWS INDICATE VOLTAGE PATH
(A)
SIG. IN
MODULE
SIG. OUT
R1
2.2 k
0.01
Q1
PNP SWITCH
10 k
(B)
+12 V

EXCEPT AS INDICATED, DECIMAL VALUES OF CAPACITANCE ARE IN MICROFARADS (μF); OTHERS ARE IN PICOFARADS (pF OR μμF); RESISTANCES ARE IN OHMS; k = 1000

LEGEND ALSO APPLIES TO FIGS. 2-5 AND 7-9.

Fig. 1 — Comparison between a simple mechanical switch and an equivalent solid-state type.


OSC.
Q1
100
+12 V
0.01
Y1
Y2
Y3
CHAN. 2
CHAN. 1
CHAN. 3
S1
100 k
SIG. OUT
560
(A)
OSC.
Q1
100
+12 V
0.01
Y1
Y2
Y3
D1
D2
D3
4.7 k
4.7 k
4.7 k
0.01
0.01
0.01
100 k
SIG. OUT
560
CHAN. 2
CHAN. 1
CHAN. 3
S1
+12 V
(B)
RESISTANCES ARE IN OHMS; k = 1000

Fig. 2 — Diodes may be used in place of a mechanical switch to select oscillator crystals, as shown at B.

pletely. This will result in partial operating voltage reaching the module of Fig. 1B.

A comparison between mechanical and diode switching is offered for your study in Fig. 2. Circuit example A illustrates the old way of selecting crystals in a multifrequency oscillator. This method is acceptable if the switch leads are very short or if the crystals are mounted directly on the switch. It is necessary to always keep RF leads as short as possible to prevent impairment of the performance.

Fig. 2B demonstrates the use of diodes in place of S1 of Fig. 2A. This enables us to locate the selector switch a great distance away from the crystals, and the connecting leads will carry dc rather than RF. The diodes offer a practical convenience, and the same control switch may be used to actuate many solid-state switches elsewhere in the overall equipment when the crystals are selected one by one. The 4.7-kΩ resistors near D1, D2 and D3 limit the current that flows through the diode junctions. They also serve as RF chokes in the switching lines to S1. In this low-power circuit, we can safely use inexpensive 1N914 high-speed switching diodes. They are suitable into the microwave region. When dc is routed to a diode through S1, it becomes forward biased and conducts, thereby completing the circuit between the bottom end of the crystal and ground. Diodes can be used in a similar manner to complete various RF circuit paths. They are often used in *series* with signal lines.


FL1
3.5 MHz
0.1
D1
T1
T2
D2
0.1
SIG. IN
4.7 k
L1
L2
4.7 k
SIG. OUT
+12 V
FL2
7.0 MHz
0.1
0.1
D3
T3
T4
D4
0.1
4.7 k
L3
L4
4.7 k
+12 V
7.0 MHz
0.1
(A)
FL2
FL1
S1
+12 V
0.1
D1
D2
T1
FL1
2.2 k
2.2 k
L1
0.1
2.2 k
(B)
FL2
FL1
S1A
S1B
+12 V

Fig. 3 — Series-diode switching is illustrated here. Example A shows how a pair of band-pass filters could be selected by means of diode switching. A better technique is shown at B (see text).



Fig. 4 — Various semiconductor switches (see text).



Fig. 5 — Practical circuit for an electronic hand key. The etched-foil grid at the left is the keying contact. Transmitter or code-practice oscillator keying occurs when the operator places his or her finger on the copper grid. The resistor is in ohms, and the capacitors are in microfarads.

Examples of series diode switching are given in Fig. 3. The circuit at A shows a typical arrangement in which we might use diodes to select band-pass filters. The input and output ends of each filter are connected to switching diodes to permit electronic insertion or removal of the desired filter. This circuit will function as shown, but it is a simplification of diode switching, for the purpose of making the example less difficult to understand. Each diode has a 4.7-kΩ resistor in series with the related +12-V line to limit the junction current and to function as an RF choke. If the resistors were not used as chokes, the input and output signal to and from the filters would be lost to ground through the +12-V line. Each diode obtains its dc ground return through the tuned-circuit windings (L1, L2, L3 and L4). Small diodes of the 1N914 variety work well in this circuit.

A better way to employ diodes for series switching is shown in Fig. 3B. Here we have two diodes in a back-to-back arrangement. This circuit would be used at each end of FL1 and FL2 of Fig. 3A. The advantage of using two diodes is better isolation of the filters. Forward bias is applied to the diode anodes via S1 when a filter is selected. The unused filter (not shown) is well isolated from the signal line because reverse bias (+12 V applied to the diode cathodes) is switched to the dormant diodes to prevent any conduction caused by RF energy that may be present. When S1 of Fig. 3B is set for FL1 use, D1 and D2 are turned on and the signal path is completed. When S1 is changed for use of FL2, D1 and D2 are reverse biased to turn them off. Additional ground and +12-V lines are also connected to the contacts of FL1 to control the remaining six diodes that would be used for two filters of the type indicated in Fig. 3A. One DPDT switch would be used to control all eight diodes.

Here we see the advantage of solid-state switching, for if a mechanical switch were used, it would require four poles with two positions each. Also, the lead lengths from the filters to the switch sections could be prohibitive, and the input/output isolation of the filters could be poor because of signal leakage across the switch sections. RF chokes can be used in place of the resistors if desired, but there should still be a current-limiting resistor in the dc line to the diodes.

Basic Shunt Switches

Fig. 4 contains a number of examples that show how we may use various semiconductor devices as shunt switches. S1 in each case represents a mechanical switch or CW key that turns on the electronic switch. As we learned earlier, turn-on can be effected also by other electronic switches in the overall circuit. For example, AGC voltage or rectified speech energy could be used to actuate a semiconductor switch, depending on the application for the switch; the possibilities are virtually without limit.

Circuit A of Fig. 4 is an NPN transistor switch. A positive voltage is required at the base of Q1 in order to turn it on. The 10-kΩ resistor from the base to ground is used to minimize transistor leakage current when the switch is in the OFF mode. This circuit might be used to key a driver stage in a solid-state CW transmitter. If so, the collector of Q1 would be hooked to the emitter of the keyed stage. S1 would be the CW key, or the keying line from a keyer.

Fig. 4B shows a similar circuit, but with a power FET switch. Since we have an enhancement-mode FET in our circuit, the transistor requires a forward gate bias to turn the device on and make it switch.

A simple diode switch is shown at C of Fig. 4. To the right is a PNP transistor switch (D). The base must be grounded through the 2.2-kΩ resistor to cause turn-on. A 10-kΩ resistor is connected from base to the +12-V line to help cut off the transistor in the OFF mode. This resistor can be eliminated in the circuits of Fig. 4A, 4D and 4E if two 1N914 diodes are connected in series with the emitter leads. The diode junctions will reverse bias the transistors by approximately 1.4 V. The resistor or biasing diodes are especially important in the circuit of Fig. 4E — a relay driver. Without reverse bias, the relay may remain energized after the transistor is turned off. This is because a small amount of leakage or idling current will remain, and it may



Fig. 6 — The test-model key shown in Fig. 5.

be ample to keep the relay closed once it has been energized. D1 of Fig. 4E is used to clamp voltage spikes that occur when the field coil of K1 collapses at turn-off. Such spikes, if allowed to exist, could follow the +12-V line and damage semiconductor devices elsewhere in the circuit.

An Electronic Straight Key

So that we may understand how two transistors can be arranged to work in concert as dc switches, let's look at Fig. 5. Q1 is made to turn on when we place our finger on the circuit-board foil at the left. The resistance of our skin completes the bias circuit for the base of Q1. This actuates Q1, which in turn fires Q2, the keying transistor. When Q1 switches on, dc voltage appears at the emitter. At this moment, the positive potential also reaches the base of Q2, causing it to switch to the ON state. This closes the keying line to our transmitter.



Fig. 7 — Example of a transistor keying switch (Q3) and two diodes (D1 and D2) used as TR switches for QSK operation.

There is no current-limiting resistor at the base of Q2 because there will not be a prohibitive voltage level coming from Q1. This is because the contact resistance of our fingers is sufficiently high to prevent Q1 from completely saturating. Hence, the output voltage from the Q1 emitter will be low enough for safe operation of Q2. A huskier transistor can be used at Q2 if the key-line current warrants a transistor with a dissipation rating greater than that of the 2N2222. A 2N2102 (or equiv.) would be a good choice.

A photograph of a crude test model of the hand key is presented in Fig. 6. The copper grid is etched as shown, and isolating pads are used to contain the transistors and related parts. A three-circuit key plug is needed to accommodate the +12-V, keying and ground leads. This key will operate satisfactorily from a 9-V transistor-radio battery as well. Three bypass capacitors are used to help keep unwanted RF energy from affecting transistor performance.

Fig. 7 shows the driver and PA stages of a simple QRP CW transmitter. The key from Fig. 5 could be used to operate the dc switch, Q3, of Fig. 7. When our finger is placed on the copper grid of the key, Q3 will turn on. This action will permit the flow of dc to driver Q1, thereby keying our transmitter.

D1 and D2 of Fig. 7, 1N914 small-signal diodes, are used as a TR (transmit-receive) switch. This circuit was introduced by Wes Hayward, W7ZOI, and has been used for QSK (full break-in) in many of his QRP rigs. In this example, the diodes are turned on by RF energy from the collector of Q2 when Q3 is actuated. Some of the RF voltage is sampled by C1 and is routed to the diodes. During transmit, D1 and D2 are shorted to ground, thereby protecting the receiver input circuit. The diode conduction threshold is roughly 0.7 V. As a result, there will be a 0.7-V RF potential appearing at the receiver input circuit. This is not a great enough voltage to cause harm to the receiver. I have applied that amount many times to the input line of my FT101E, FT301D and FT102 transceivers, and no damage resulted. Greater details of this type of TR circuit are given in the League's book, *Solid State Design for the Radio Amateur*.

One of the penalties for using the simple TR circuit of Fig. 7 is a loss in received signal (about 6 dB, from my experience). This is because C1 must be relatively small in value to prevent it from affecting the design of the output network of Q2. I use a capacitive reactance of 400 for C1. Thus, at 7 MHz, we would have a 56-pF capacitor at C1. The signal loss can be corrected by inserting a low-gain RF amplifier between the TR switch and the receiver input line. Fig. 8 shows how this might be done. A grounded-gate JFET, such as an MPF102, would serve nicely at Q5.

A More Elaborate Switching Circuit

An illustrative transmitter circuit is presented in Fig. 9. The arrangement for Q4, Q5 and Q6 is one I developed for personal use with a few QRP rigs up to 3 W in RF output. Q4 is a standard PNP keying switch, as discussed earlier. It not only actuates oscillator Q1, it also triggers dc switch Q5, which in turn activates Q6. When the key is closed, the signal energy to the receiver is shorted to ground by Q5. At the same moment, the series diodes, D2 and D3, are turned off by virtue of transistor switch Q6 being in the OFF state. This prevents signal energy from passing through the diodes to the receiver. When the key is up, Q6 conducts and provides a dc ground return for the diodes, which



Fig. 8 — An improved TR system in which Q4 shorts the RF energy to ground when the key is closed. D1 and D2 are optional. They may be added as safety backup for Q4. Signal loss on receive is common with this simple TR circuit (see text), so an RF amplifier can be added at Q5 to compensate for loss in the TR circuit.


0.1
560
3.3 k
C3
C4
2N3904
Q1
c
d
e
L1
2N2222A
Q2
C6
1k
10
100
0.1
0.1
0.1
0.1
22
T1
R1
33
2N3553
Q3
C5
0.1
L2
L3
ANT.
50 Ω
C7
C8
C9
RFC 3
22 µH
0.1
OPER.
S1B
SPOT
Y1
C1
C2
560
a
b
VXO
TERMINALS
D1
9.1 V
1 W
220
S1A
f
SPOT
2N4036
Q4
2.2 k
KEY
1 µF
6 V
0.1
10k
22 µF
25 V
+13 V
0.1
2.2 k
10k
0.01
2N2222A
Q5
10 k
0.1
2.2 k
2.2 k
D2
D3
0.1
RCVR
INPUT
RFC 2
22 µH
RFC 1
22 µH
Q6
2N2222A
0.01
0.01

Fig. 9 — A somewhat elegant TR switching method that uses a series diode switch and a signal shunting transistor (Q5, D2 and D3). An explanation is given in the text. This is purely an illustrative RF circuit from Q1 through Q3. Therefore, there is no parts list.

enables them to reach the ON state. In effect, the action of Q5, D2 and D3 offer added attenuation and double protection for the receiver during transmit periods. The use of Q5 alone greatly reduces the signal level to the receiver input, as compared to the circuit of Fig. 7. I have measured only a few millivolts peak to peak from the receive line to ground when using a transistor shorting switch in place of TR diodes. There is no parts list for the transmitter of Fig. 9, since it is purely an example of how the switching techniques might be used. If you like QSK operation, you may want to experiment with this circuit.

In Conclusion

The intent of this primer on electronic switching is to stimulate thinking on your part, and to encourage you to work with semiconductor switching circuits. Since ICs contain diodes and transistors, many of them are applicable to circuit switching. A number of logic ICs are designed expressly for switching use and for gating.

Certainly, solid-state switches lend themselves well to use in compact circuits. The overall cost of a switching circuit may be somewhat less than that of a similar circuit containing mechanical switches. Also, by replacing relays with semiconductor switches, we can greatly reduce the current required by the overall circuit in our gear.

PIN diodes are designed especially for switching in RF voltage lines. An excellent example of PIN diode TR usage is given in *The Radio Amateur's Handbook*. See the chapter on keying (in recent editions).

You should have no problems in obtaining suitable switching devices these days. Ham radio flea markets and surplus outlets offer a plethora of diodes and transistors for this job, and the unit prices are often less than 10 cents! Perhaps it's time for you to "switch" to solid state!

From October 1987 QST, p 36:

Reducing AM Detection in Direct-Conversion Receivers

☐ While building equipment for the 40- and 30-meter bands, I discovered that AM detection is a common problem in D-C receivers. I used a singly balanced, four-diode detector followed by 85 dB of audio gain and a conventional RC active filter with additional gain. When the receivers were completed, both would detect any AM signals above about 200 μV in level. This is a problem because there are many such signals in the neighborhood of our 30- and 40-meter bands.

I went to some lengths to decouple and shield each receiver's LO, and to provide RF decoupling between the detector and the audio amplifier. Neither of these changes made any improvement.

Oscilloscope display of the detected AM signal showed an interesting peculiarity: At the receiver input, most signals exhibited symmetrical noise—but the *detected* AM signals showed only *negative-going* noise. This led me to suspect that the detection was actually taking place in the audio amplifier. Further, working with a receiver with no front-end selectivity, I found that sensitivity to AM detection decreased with increasing separation between LO and AM signal frequencies. This strengthened my hunch.

I solved the problem by installing a passive L-network filter, with a bandwidth of several hundred hertz, between the detector and the audio amplifier. I used a design similar to that shown in Fig 12 on p 77 of *Solid State Design for the Radio Amateur* with good results. With the filter installed, the modulation on AM signals of several thousand μV is inaudible with a 10-kHz LO/signal spacing. *—Denton Bramwell, K7OWJ, 3139 Royalton Heights Rd, St Joseph, MI 49085*

From July 1977 QST, p 51:

Common-Mode Hum in Direct-Conversion Receivers

A direct-conversion receiver may be virtually impossible to use with ac-line operated power supplies, owing to excessive hum. Part of this problem is that a direct-conversion receiver obtains most, if not all, of its gain at audio frequencies. Hence, the high audio gain makes the system subject to the smallest ac hum on the power supply. The cure for this problem is just better regulation in the power supply, which is easily realized with an integrated-circuit regulator.

A more subtle form of hum is also common and does not depend upon power-supply regulation. This hum is not present when no antenna is connected to the "dc" receiver. However, when an antenna is attached, a very rough sounding hum-like noise is noted. The amplitude of this response peaks as the antenna trimmer is tuned. There are a number of possible explanations. The most realistic is that local-oscillator energy from the dc receiver is coupled into the power-supply lines. This energy is transferred back through the power supply where it is modulated by the rectifier diodes. The resulting hum-modulated note is now coupled into the ac line. This signal is radiated and picked up by the nearby station antenna. Only the sidebands are detected.



Using a toroid with bifilar winding to reduce hum.

While diagnosis of this problem may be subtle, a solution is deceptively simple and is shown in Fig. 1. A large ferrite toroid is wound with a bifilar winding of reasonably large wire diameter. Ten turns of no. 18 are usually suitable. The core is not critical although it should have a high permeability. An Amidon FT-82-75 is recommended. The effect of this balun-like circuit is to present a high impedance for any rf paths between the receiver and the power supply. Only the dc difference voltage from the power supply is applied to the receiver.

In the writer's station this method was applied with three different direct-conversion receivers. In two of the three cases the receivers were previously useless except with battery power sources. With the toroid, no differences could be detected when switching from a battery pack to a well-regulated ac supply *—Wes Hayward, W7ZOI, 7700 SW Danielle Ave, Beaverton, OR 97005*

From September 1989 QST, p 38:

Series-Resonant Circuit Enhances Desired Signal in QRP Rig

☐ During cut-and-try construction of a QRP CW rig that uses push-push doubling to produce 14-MHz drive from a 7-MHz VFO, I discovered that the stages following the doubler had output everywhere *except* 14 MHz! I solved this problem by installing a series-resonant tuned circuit between the doubler and its buffer stage (Fig 3). I have also successfully used series-resonant circuits between the antenna and output stages of monoband rigs to minimize TVI. (By the way, I first submitted something for Hints and Kinks in *1932*, but *QST* didn't publish that hint. I have since recovered from my feeling of rejection and decided to try again!)*—Bob Kuehn, WØHKF, 1871 Silver Bell Rd, Apt 313, Eagan, MN 55122*



Fig 3—Bob Kuehn added this 14-MHz series-resonant circuit (L1C1) to clean up the output of a push-push doubler in his homemade QRP transmitter. L1 consists of 44 turns of no. 24 enameled wire on a T-68-2 powdered-iron toroidal core. C1 is a small air-dielectric capacitor capable of being set to about 11.5 pF.

When radio amateurs first began using tube transmitters, the race to work the most miles per watt was on. In the '50s, transistors added a new dimension to QRP (low power) operating. And with today's ICs, it's possible to put together a complete station that fits into the corner of a knapsack: backpack into the wilderness, and enjoy worldwide communication!

QRP operating is fun. The equipment is generally simple and easy to build, but often performs like more sophisticated commercial equipment. Imagine the sense of accomplishment you'll get from operating equipment you built yourself. Some QRP Field Day stations operate a full 27 hours on a car battery—it's the perfect equipment for emergency communication when the power fails.

This book is a collection of projects published in ARRL publications over the past 15 years. Find out how to build receivers, transmitters, transceivers and accessories. There's a chapter on portable antennas. Power supplies, and a host of accessories are described. The chapter on design hints covers amplifiers, matching networks, electronic switching and direct-conversion receivers.

Are you looking to add an exciting aspect to your Amateur Radio interests? Come join the fun—give QRP a try!

PUBLISHED BY **THE AMERICAN RADIO RELAY LEAGUE**

Cosmic Fusion

Fusion of the Eight Forces

Mantak Chia

Edited by:

Lee J. Holden Jr.

Copy Editor: Lee Holden, Jr.

Copy Writer: Rene J. Navarro

Editorial Assistance: Colin Campbell

Photographer: Saysunee Yongyod

Computer Graphics: Raruen Keawpadung

Design and Production: Saniem Chaisarn

Illustrations: Udon Jandee

Final Editing: Jean Chilton

Project Manager: W.U. Wei

© *North Star Trust*

First published in 2002 by:

Universal Tao Publications
274/1 Moo 7, Luang Nua,
Doi Saket, Chiang Mai, 50220 Thailand
Tel: (66)(53) 495-596 Fax: 495-853
Email: universaltao@universal-tao.com
Web Site: www.universal-tao.com

ISBN: 974-85391-9-9

Manufactured in Thailand
Second Printing, 2002

All rights reserved. No part of this book may be used or reproduced in any manner whatsoever without the express written permission from the author except for brief quotations embodied in critical articles and reviews.

Contents

Contents iv
About the Author viii
Acknowledgments xii
Words of Caution xiii

Chapter 1
Cosmic Fusion and the Tao 14
The Tao 14
Universal Tao System 16
Healing the Physical Body: Becoming Like a Child to Return to the Original Source 17
Stopping Energy Leakage through Conservation and Recycling... 19
Abdominal Brain 20
Transforming Negative Energy into Virtues: Opening the Heart 21
Managing the Life-Force 22
Cosmic Nutrition 23
Developing the Energy Body: Our Vehicle to Travel in Inner and Outer Space 23
Recycling our Negative Emotions.................................. 25
Forming the Spirit Body: Planting the Seed of Immortality 26
Cultivating the Yang Stage of the Immortal Body: Marrying the Light - Greater Kan and Li 27
Greatest Enlightenment of Kan and Li 28
Sealing of the Five Senses, Congress of the Heaven and Earth and Reunion of Heaven and Man............................ 29

Chapter 2
Taoist Cosmology 30
The Void: Our Original Source 31
Yin and Yang 31
Five Major Forces of the Universe....................................... 32
Eight Forces 34
Return to the Wu Chi.. 35
Returning to the Wu Chi: First Three Steps 36

Chapter 3
Goals of the Fusion Practice 38
Inner Universe reflects the Outer 42
Overview of the Cosmic Fusion:
Universal Tao divides Fusion into Three Parts.................. 43
First Part 43
Second Part 44
Third Part 46

Chapter 4
Energetic Preparations for Meditation Practice 51
Preparing for the Fusion Meditations 51
Prepare the Environment 51
Conserve Energy and Purify your Body with an
Appropriate Diet 52
Loosen, Stretch and Warm Up the Body
before Meditating 52
Wear Loose and Comfortable Clothing 52
Establish a Stable Sitting Position 53

Chapter 5
Beginning Fusion Element Meditation 59
Pakua.. 59
Chanting 60
Formula One: Forming the Pakuas 63
Creating the Front Pakua 64
Practice 65
Activate the Facial Pakua by enhancing it on the Forehead 88
Facial Pakua 89
Start the Practice of the Facial Pakua with the First
Four Symbols first 92
Creating the Back Pakua on the Head 99
Formula Two: Transforming the Negative Emotions
of Each Organ into Pure Life-Force Energy 108
Practice 110

Chapter 6
Compassion Fire
Meditation Practice of the Creation Cycle 116
- One Lasting Energy is the Combination of Compassion Energy and Orgasmic Energy 119
- Practice of Creating the Compasstion Fire and Multi-Orgasm 121
  - Multi-Orgasm Energy Smile to the Sexual Organs 127
  - Practice Compassion though the Act of Forgiveness..... 130
- Oneness with Universe (Oneness with God) 131
  - Fuse Inner Positive Energy with Universal Energy through Turning the Dial 131
  - Forming the Collection Points 131
  - The Concept of Fusion Inner Position Energy with Universal Energy 133
  - Activate the Three Fires 134
- Creation Cycle Foundation Practice 141
  - Begin Cosmic Fusion: Creation Cycle............................ 144
  - Shoot the Pearl Above the Crown 152
- Summary 144

Chapter 7
Opening the Thrusting Channels 155
- Theory of the Thrusting Channels 155
- Procedure for Opening the Thrusting Channels 156
  - Seated Position 157
  - Anal Muscle 158
  - Saliva 159
  - Men & Women Practice: Open Channels Differently...... 161
- Practice of Opening the Thrusting Channels 162
- Additional Exercise for Opening the Thrusting Channels.... 179
- Summary: Opening the Thrusting Channels...................... 181

Chapter 8
Belt Channels 183
- Theory of the Belt Channel 183
- Procedure of Forming the Belt Channel............................. 183
- Practice of Forming the Belt Channel 185
  - Men & Women Practice: Open Channels Differently...... 193
  - Forming a Vehicle 194

Summary: Procedure of Forming the Belt Channel............ 198
Energy Body 202
Spirit Body 204

Chapter 9

Fusion as a Bridge 206
Fusion as a Journey of Self-Transformation 206
Unity of Ying and Yang 208
Turning Inward 209
From Balance through Resonance to Love 210
Enlightenment of the Body and New Physics 211
Return to Cosmology 213
Religious Nature of Taoist Practice 214
Wisdom of Making Friends with the Devil 215
Unity of Light and Dark 217
Life as an Invitation to Learning 219
Smiling as the Key Taoist Practice 220
Unity of Fullness and Emptiness 220
Attachment and Detachment 222
Going with the Flow 223
Secret of Breathing and Relaxation 225
Science of Feeling and the Power of Intuition 226
Thinking with the Heart 227
Feminine Underground Current 229
Restoring the Balance 230
World as a Manifestation and Reflection of the Universe ... 231
Unity of What is Above and Below 234
Healing Wounds 237
Practice of Humor and the Humor of Practice 239
Learning to tend our Garden 240
Raising the Quality of Our Energies 241
Marriage of the Light from Within and from Above 241
Questions and Answers
about the Cosmic Fusion Practice 244

Biobliography...254

About the Author

Mantak Chia

Master Mantak Chia

Master Mantak Chia is the creator of the Universal Tao System and is the director of the Universal Tao Center and Tao Garden Health Resort and Training Center in the beautiful northern countryside of Thailand. Since childhood he has been studying the Taoist approach to life. His mastery of this ancient knowledge, enhanced by his study of other disciplines, has resulted in the development of the Universal Tao System which is now being taught throughout the world.

Mantak Chia was born in Thailand to Chinese parents in 1944. When he was six years old, Buddhist monks taught him how to sit and “still the mind.” While still a grammar school student, he learned traditional Thai boxing. He was then taught Tai Chi Chuan by Master Lu, who soon introduced him to Aikido, Yoga and broader levels of Tai Chi.

Years later, when he was a student in Hong Kong excelling in track and field events, a senior classmate named Cheng Sue-Sue introduced him to his first esoteric teacher and Taoist Master, Master Yi Eng (I Yun). At this point, Master Chia began his studies of the Taoist way of life in earnest. He learned how to circulate energy through the Microcosmic Orbit and, through the practice of Fusion of the Five Elements, how to open the other Six Special Channels. As he studied Inner Alchemy further, he learned the Enlightenment of the Kan and Li, Sealing of the Five Senses, Congress of Heaven and Earth and Reunion of Heaven and Man. It was Master Yi Eng who authorized Master Chia to teach and heal.

When Mantak Chia was in his early twenties he studied with Master Meugi in Singapore, who taught him Kundalini, Taoist Yoga and the Buddha Palm. He was soon able to clear blockages to the flow of energy within his own body. He learned to pass the life force energy through his hands also, so that he could heal Master Meugi’s patients. He then learned Chi Nei Tsang from Dr. Mui Yimwattana in Thailand.

A while later, he studied with Master Cheng Yao-Lun who taught him the Shao-Lin Method of Internal Power. He learned the closely guarded secret of the organs, glands and bone marrow exercise known as Bone Marrow Nei Kung and the exercise known as Strengthening and Renewal of the Tendons. Master Cheng Yao-Lun’s system combined Thai boxing and Kung Fu. Master Chia also studied at this time with Master Pan Yu, whose system combined Taoist, Buddhist and Zen teachings. Master Pan Yu also taught him about the exchange of Yin and Yang power between men and women, and how to develop the Steel Body.

To understand the mechanisms behind healing energy better, Master Chia studied Western anatomy and medical science for two years. While pursuing his studies, he managed the Gestetner Company, a manufacturer of office equipment and became well acquainted with the technology of offset printing and copying machines.

Using his knowledge of Taoism, combined with the other disciplines, Master Chia began teaching the Universal Tao System. He eventually trained other Instructors to communicate this knowledge and he established the Natural Healing Center in Thailand. Five years later, he decided to move to New York, where in 1979, he opened the Universal Tao Center. During his years in America, Master Chia continued his studies in the Wu system of Tai Chi with Edward Yee in New York.

Since then, Master Chia has taught tens of thousands of students throughout the world. He has trained and certified over 2,000 instructors and practitioners from all over the world. Living Tao Centers, Chi Nei Tsang Institutes, Cosmic Healing Forums & Immortal Tao Mountain Sancutaries have opened in many locations in North America, South America, Europe, Asia, Africa and Australia.

In 1994, Master Chia moved back to Thailand, where he had begun construction of Tao Garden and the Universal Tao Training Center fifteen miles outside of Chiang Mai.

Master Chia is a warm, friendly and helpful man who views himself primarily as a teacher. He presents the Universal Tao System in a straightforward and practical manner, while always expanding his knowledge and approach to teaching. He uses a word processor for writing and is totally at ease with the latest computer technology.

Master Chia estimates that it will take thirt-five books to convey the full Universal Tao System. In June, 1990, at a dinner in San Francisco, Master Chia was honored by the International Congress of Chinese Medicine and Qi Gong (Chi Kung), who named him the Qi gong Master of the Year. He is the first recipient of this annual award.

In December, 2000, the Tao Garden Health Resort and Universal Tao Training Center was completed with two Meditation Halls, two open air Simple Chi Kung Pavilions, indoor Tai Chi, Tao Tao Yin and Chi Nei Tsang Hall, Tai Chi Natural Swimming Pool, Pakua Communications Center with a complete Taoist Library, Internal World Class Weight Lifting Hall and complete 8 Court Recreational Facilities.

In February, 2002, the Immortal Tao practices were held at Tao Garden for the first time using Darkness Technology, creating a complete environment for the higher level Taoist practices.

Master Mantak Chia has previously written and published these twenty-two Universal Tao books:

Awaken Healing Energy of the Tao - 1983
Taoist Secrets of Love: Cultivating Male Sexual Energy co-authored with Michael Winn - 1984.
Taoist Ways to Transform Stress into Vitality -1985
Chi Self-Massage: the Tao of Rejuvenation - 1986
Iron Shirt Chi Kung I - 1986
Healing Love Through the Tao: Cultivating Female Sexual Energy - 1986
Bone Marrow Nei Kung - 1989
Fusion of the Five Elements I - 1990
Chi Nei Tsang: Internal Organ Chi Massage - 1990
Awaken Healing Light of the Tao - 1993
The Inner Structure of Tai Chi co-authored with Juan Li - 1996
Multi-Orgasmic Man co-authored with Douglas Abrams 1996 - published by Harper Collins
Tao Yin - 1999
Chi Nei Tsang II - 2000
Multi-Orgasmic Couple co-authored with Douglas Abrams 2000 - published by Harper Collins
Cosmic Healing I - 2001
Cosmic Healing II co-authored with Dirk Oellibrandt - 2001
Door of All Wonders co-authored with Tao Haung - 2001
Sexual Reflexology co-authored with W. U. Wei - 2002
Elixir Chi Kung - 2002
Tan Tien Chi Kung - 2002
Cosmic Fusion - 2002

Many of the books above are available in the following foreign languages:

Arabic, Bulgarian, Czech, Danish, Dutch, English, French, German, Greek, Hebrew, Hungarian, Indonesian, Italian, Japanese, Korean, Lithuanian, Malaysian, Polish, Portuguese, Romanian, Russian, Serbo-Croatian, Slovenian, Spanish, & ***Turkish*** editions are available from the Foreign Publishers listed in the Universal Tao Center Overview in the back of this book.

Acknowledgments

The Universal Tao Publications staff involved in the preparation and production of *Cosmic Fusion: Fusion of the Eight Forces* extend our gratitude to the many generations of Taoist Masters who have passed on their special lineage, in the form of an unbroken oral transmission, over thousands of years. We thank Taoist Master I Yun (Yi Eng) for his openness in transmitting the formulas of Taoist Inner Alchemy.

Thanks to Juan Li for the use of his beautiful and visionary paintings, illustrating Taoist esoteric practices.

We offer our eternal gratitude to our parents and teachers for their many gifts to us. Remembering them brings joy and satisfaction to our continued efforts in presenting the Universal Tao System. For their gifts, we offer our eternal gratitude and love. As always, their contribution has been crucial in presenting the concepts and techniques of the Universal Tao.

We wish to thank the thousands of unknown men and women of the Chinese healing arts who developed many of the methods and ideas presented in this book. We offer our gratitute to Master Lao Kang Wen for sharing his healing techniques.

We wish to thank Lee J. Holden Jr. for his editorial work and writing contributions, as well as his ideas for the cover. We appreciate his research and great labor. We wish to thank Colin Campbell for his editorial contributions on the revised edition of this book, as well as thanking our Senior Instructors, Rene J. Narvarro and Annette Derksen, for their insightful contributions to the revised version. We thank Joost Kuitenbrouwer for his technical editing and clear writing throughout the book.

A special thanks goes to our ***Thai Production Team*** for their cover illustration and book design and layout: Raruen Keawapadung, Computer Graphics; Saysunee Yongyod, Photographer; Udon Jandee, Illustrator; and Saniem Chaisam, Production Designer.

Words of Caution

The practices described in this book have been used successfully for thousands of years by Taoists trained by personal instruction. Readers should not undertake the practice without receiving personal transmission and training from a certified instructor of the Universal Tao, since certain of these practices, if done improperly, may cause injury or result in health problems. This book is intended to supplement individual training by the Universal Tao and to serve as a reference guide for these practices. Anyone who undertakes these practices on the basis of this book alone, does so entirely at his or her own risk.

The meditations, practices and techniques described herein are ***not*** intended to be used as an alternative or substitute for professional medical treatment and care. If any readers are suffering from illnesses based on mental or emotional disorders, an appropriate professional health care practitioner or therapist should be consulted. Such problems should be corrected before you start training.

Neither the Universal Tao nor its staff and instructors can be responsible for the consequences of any practice or misuse of the information contained in this book. If the reader undertakes any exercise without strictly following the instructions, notes and warnings, the responsibility must lie solely with the reader.

This book does not attempt to give any medical diagnosis, treatment, prescription, or remedial recommendation in relation to any human disease, ailment, suffering or physical condition whatsoever.

The Universal Tao is not and cannot be responsible for the consequences of any practice or misuse of the information in this book. If the reader undertakes any exercise without strictly following the instructions, notes, and warnings, the responsibility must lie solely with the reader.

Chapter 1

Cosmic Fusion and the Tao

Cosmic Fusion is the basic Taoist practice of internal alchemy. This is the second book in a three part series. This particular book expands on the concepts and practices introduced in Fusion of the Five Elements. Here in part II, the practice goes to the next level of development.

In the beginning these practices may seem complex and mentally challenging, yet once the formulas are understood and applied, they are quite simple. With practice, the materials become familiar territory that you can traverse easily. Take your time with the formulas. Experiment with what works for you. The formulas are the guidelines to enhance your life. The Cosmic Fusion is a doorway into the vast potential of the self and the Universe. It is a very natural process and the first step into the Taoist alchemical practice.

The Tao 道

The word *Tao* means ***The Way***, the way of nature and the Universe, or the path of a natural reality. It also refers to a way in which we can open our minds to learn more about the world, our spiritual paths and ourselves. Taoism is a practice of body, mind and spirit, not just a philosophy of mind. When we have the true sense of the Tao, of the real knowledge and wisdom, we will be able to make the right decisions in our lives.

Taoism involves many practical disciplines that can restore our lost youth, energy and virtues while awakening our deepest spiritual potentials. Taoists regard these practices as a technology that can help us learn universal truths if we are willing to be receptive.

The ancient masters recognized that these potentials can include the possibility of attaining conscious freedom and existence in the after-death state. Through specific exercises, one can avoid suffering the experience of death by expanding the consciousness beyond the physical body before its demise. This makes it possible to determine one’s future existence before leaving this life.

All spiritual paths ultimately lead to the truth. Taoism is both a philosophy and a technology for seeking and finding the truths of the universe, nature, and humanity. Its focus goes beyond one single path or viewpoint. Taoism is not a religion, as it requires no initiations or ceremonies, but it is the outcome of all religions, departing from dogma at the point of truth. It leaves behind all religious beliefs, just like the clothing of past seasons. The Tao is also the goal of science, but it leaves behind all scientific theories as partial and temporal descriptions of the integral truth. Taoism includes all matters of religion and science, yet its breadth goes far beyond the limits of devotion or intellect.

Taoist teachings are like master keys unlocking all doors. They assist people in their lives, as do all religious teachings. Yet the teachings of the Tao transcend religion while retaining the essence of spirituality. They explain and demonstrate the truths of the Universe directly, rather than on the level of emotions, thoughts or beliefs. For this reason, students of the Tao have little cause for skepticism or endless searching.

Philosophy, science and religions all contain some aspects of truth that reflect the Tao. The teachings of the Tao reflect the center of the ultimate truth (ourselves and the Universe) and help us reach it on our own. We can believe in any religion or spiritual path and still benefit from these teachings, because the Tao serves only to promote universal spiritual independence. There are no ultimate masters or gurus in Taoism because we become our own masters, capable of controlling our own destinies and knowing who we really are as we explore the marvelous powers hidden within the Tao of humanity. All the great gods, immortals, sages, saints and holy men and women are our teachers and advisers.

Taoism, which goes back at least seven to eight thousand years, is closely aligned with modern technology and science. Browsing through a bookstore, you will find that many recent books use the concepts of Taoism to explain relationships expounded by the “new” physics. Today, a lot of the world’s intellectual effort is directed toward external technological development.

Thousands of years ago, the Taoists directed their consciousness inwardly, and developed a science of inner alchemy. Chinese written history has a 4700 year history and the language has not changed significantly over the centuries, so even the oldest documents can be read today. A lot of information was accumulated in each dynasty. The Taoist sages, who learned and perfected methods to prepare and leave the body, recorded all the practical details. These, along with philosophical thought, were collected, filling many volumes which constitute the Tao Canon.

These transformative formulas endure, a gift from the original Taoist sages to all who are willing to put them into practice. The Universal Tao is concerned primarily with the practical approaches perfected by the Taoist sages.

Universal Tao System



The ancient Taoists saw the importance of working on all three levels of our being: the physical body, the Energy Body and the spirit. All three are important in forming a ladder with which we may climb consciously into the spiritual worlds and, just as important, back into the physical world to be creatively active here. This ladder enables Taoists to learn about the inner worlds and to return to the physical with knowledge and increased energy. An Immortal Body, which is developed in the practice of Internal Alchemy, enables one to establish a constant link between life and the after-death (or pre-birth) state.

Ancient Taoist sages believed we were born to be immortal. We become mortal by draining ourselves of Chi through engaging in excessive sexual activity, indulging in negative emotions, and depending on material sources to supply our life-force. The masters recognized that different levels of immortality can be achieved through internal alchemy, and they devised many practices for this purpose. The ability to transcend even death through the transmutation of one’s physicality into the Immortal Spirit Body is the highest goal of Taoism. This level, known as physical immortality, takes the longest to achieve.

Healing the Physical Body: Becoming like a Child to return to the Original Source

Taoist practices teach to conserve the physical energy so that it will no longer scatter and deplete as a result of our worldly interactions. Full spiritual independence requires that we avoid being drained of this energy through the eyes, ears, nose, and mouth or through excessive sex. The novice in the Universal Tao System begins with a wide range of exercises that develop the physical body into an efficient and healthy organism, able to live in the world and yet stay free of the tensions and stresses of daily life. One aspires to return to a childlike state of innocence and vitality, to regain the Original Source that is our birthright. Specific goals of this level are to learn how to heal oneself, how to love oneself, and how to love others.



Fig. 1.1 *Returning to the Original Source.*

The first level of practice is to develop a healthy body, which can take months of diligent training. During this process we learn how to condense and conserve our life-force through the *Microcosmic Orbit* meditation, *Healing Love* practices, *Inner Smile*, *Six Healing Sounds*, and *Iron Shirt Chi Kung*. We learn to gather and refine our life-force into a Chi Ball (energy sphere) so it will not dissipate when we are ready to leave this world. As people grow older, their life-force weakens, often resulting in illness and suffering. Using drugs to combat illness drains so much of the body's life-force that there may not be enough energy left to follow the primordial light (clear light) to the Wu Chi (our original source God) at the moment of death. The basic practices of the Universal Tao ensure that we retain enough of our health and vital energy to make that journey.



Fig. 1.2 *Sit down and start to move the orbit in the fast speed, from 1000 rotations per minute, to 10,000 per minute and up to 30,000 per minute.*

Stopping energy leakage through conservation and recycling.



Fig. 1.3 *Heart Leakage*

The Microcosmic Orbit is the body's major energy pathway. Along this path there are nine openings. If we learn how to seal them when they are not in use, that simple act of conservation will save an immense amount of energy.

The Microcosmic Orbit meditation is the first step toward attaining these goals, as it develops the power of the mind to control, conserve, recycle, transform and direct Chi (the Chinese term for energy, or life-force) through the body's primary acupuncture channels. By learning how to manage our Chi effectively, we gain better control over our lives; by using our energy wisely, we discover that we already have plentiful Chi.

At this stage, one also learns to connect with and draw from the unlimited source of Universal Love, a Cosmic Orgasm formed by the union of the three main sources of Chi accessible to humans: the *Universal (Heavenly) Force*, the *Earth Force* and the *Higher Self (Cosmic) Force*. This process is both energizing and balancing. It prepares one for working with greater amounts of Chi in the higher levels of meditative practice, particularly in developing the Energy Body.

Abdominal Brain

Learning to empty the mind is one of the most important Universal Tao practices. Letting go of judgments, suspicions and the incessant repetitive thought process is a simple way to recharge the body, the brain and the spirit. Science has proven that we have about 60,000 thoughts per day and of those 60,000 thoughts 95% of them are the same thoughts we had yesterday. By activating the abdominal brain, we are able to clear the mind and create space for more creative mental activity.



Fig. 1.4 *Upper and Lower Brains*

The brain spends up to 10 times more energy than the rest of the body. Even when we are not working or thinking consciously, our mind still wanders. In Taoism this incessant thinking is called the “Monkey Mind”. If we can stop the mind and empty the energy from the brain down to the organs, there will be tremendous amount of energy stored in the body. This abundance of energy can later return back to the brain. When the energy returns, our thoughts are much more refined, creative and focused.

The abdominal brain is located in the Lower Tan Tien, the reservoir of energy located about an inch below the navel and three inches inside the body. This is the very center of our being. It is called the abdominal brain because it is a center for wisdom. Science is learning that the same chemical activities that go on in the brain, go on in the abdomen. The difference is that the abdomen is not connected with the senses. The senses tend to pull our energy and awareness outside of ourselves. This leads to the constant analyzing of situations and people. The abdominal brain is a much deeper sense of awareness, where our “gut feelings” originate. When the abdominal brain is activated, we open up to more guidance, deeper intuition and full body awareness.

Transforming Negative Energy into Virtues: Opening the Heart

The Inner Smile and Six Healing Sounds are simple yet powerful practices that teach us how to relax and heal the vital organs and to transform negative emotions back into a rich source of energy. They help open the heart center and connect us with unlimited Universal Love, improving daily interactions and providing a vehicle for the virtues, which derive from the internal organs. Taoists perceive the heart as the seat of love, joy and happiness, which can connect with Universal Love. It is also a cauldron in which the energies of our virtues are combined and strengthened. Through the Inner Smile, you will feel these virtuous energies generated from their respective organs. These virtues are then gathered into the heart to be refined and blended into compassion, the highest of all virtues. This is a most effective way to enhance one's best qualities.


Cosmic/Divine Radiation
Planetary & Extraterrestrial Radiations
Solar Radiations
Etheric & Chakra Energies
Mental & Social Electro – Vibrations
Electro – Vibrations of Human Biology
Electro – Vibrations of Physical Environmental Stimuli
Geophysical Force – Fields & Air Ions

Fig. 1.5 Cosmic/Divine Radiation Fields

Another important beginning practice teaches the student of the Tao how to gain strength through the conservation and recycling of sexual energy (*Healing Love through the Tao*). When collected, sexual energy (*Ching Chi*) becomes an incredible source of power that can be used by the individual or shared with a sexual partner through the Microcosmic Orbit pathway during sexual intercourse. With practice, singles and couples can learn to increase and intensify sexual pleasure. The collected and transformed sexual energy is an important alchemical catalyst to be used in the higher meditations.


Draw all the good virtues into the heart.
Heart Mind
Abdominal Mind

***Fig. 1.6** Conserving, recycling and transforming the energy.*

Once you have an abundance of sexual energy, you can connect to the unlimited Cosmic Orgasm experienced every moment by your Higher Self, which is the most basic energy in every cell of your body.

Managing the Life-Force

In the practices of Iron Shirt Chi Kung and Tai Chi Chi Kung, one learns to align the skeletal structure with gravity to allow a smooth, strong flow of energy. With strong fasciae, tendons, and bone marrow and good mechanical structure, we can manage our life-force more efficiently. The body also gains a sense of being rooted deeply in the earth, so one can tap into the Mother Earth healing force.

Cosmic Nutrition

The Taoist approach to diet is based on determining the body's needs and then fulfilling them according to the five elements of nature, which support the five major organs of the body. This system reveals and strengthens any weak organs by balancing one's food intake to enhance any deficient elements. It does not condemn most foods that people enjoy (including sweets), but instead creates a better program in which these foods can support the body's internal balance rather than disrupt it. Choosing and combining foods in this way can help us avoid the cravings we sometimes fall prey to.

Developing the Energy Body: Our Vehicle to Travel in Inner and Outer Space

The next level of the Universal Tao system consists of the *Fusion of Five Elements, Cosmic Fusion,* and *Fusion of the Psychic Channels*. These practices build and enhance the basic Universal Tao exercises. They use the extra energy saved through the foundation practices, including recycled negative energies, to build a strong Energy Body that will not dissipate. Developing this Energy Body awakens a part of oneself that perceives and acts free of environmental, educational and karmic conditioning. Once the Energy Body is strong, it becomes a vehicle (like the space shuttle) to help the untrained soul and spirit for the long journey home, back to the Wu Chi.



Fig. 1.7 *Fusion is the First Step in achieving Union of our Three Bodies.*

If we do not have a chance to practice awakening or to give birth to the soul and immortal spirit during life, the primordial light will awaken us at the moment of death. Unfortunately, we may be too untrained and inexperienced to follow this light. To prepare for the journey, the Energy Body is a vehicle of great importance. We can train and educate the Energy Body so it can help the untrained soul and spirit recognize and follow the primordial light back to our original source.



Fig. 1.8 *Energy Body blasting off the Spiritual Body and enters outer space.*

When we are ready to give birth to the real soul, the Energy Body will act like a booster rocket to help boost the soul into its higher dimension of the immortal spirit. At the highest level, all three of these bodies merge into one.

Each level of development gives us a chance to go further in the journey back to the Wu Chi. Taoist methods of absorbing stellar energies help rejuvenate the physical body and strengthen the soul and spirit bodies for their inter-dimensional travels.

Recycling our Negative Emotions



Fig. 1.9 *There are Five Major Collection Points of the Emotions reflected on all four sides of the body.*

Our emotional life, filled with constant vicissitudes, drains our vital energy. Through the Fusion meditations, one learns to transform the sick or negative energy that has been locked up in the vital organs. Taoists understand morality and good deeds as the most direct path to self-healing and balance. To be good to others is good for oneself as well. All the good energies we create are stored in the Energy Body like deposits in a bank account. By helping others and giving them love, kindness and gentleness, we receive positive energy in return. When we open our hearts, we are filled with love, joy and happiness.

From Taoist experience, we know that when we leave this world we can go directly to heaven, depending on how much energy we have been able to transform into the Energy Body prior to death. Just like money in the bank, the more we transform our physical being to our spiritual being, the more we have in heaven. The more good we do here, the more positive energy we have up there.

Forming the Spirit Body: Planting the Seed of Immortality – Lesser Kan & Li

The Inner Alchemy meditation of the Lesser Enlightenment of Kan and Li (water and fire, multi-orgasmic sexual energy and compassion) reunites the male and female within each of us. It involves the practice of self-intercourse, which by internal sexual coupling of the energies enables one to give birth to the soul body. The soul body then acts as a "baby sitter" to help nurture the spirit body. The soul is the seed, but it can also be matured into the immortal body if one has not had the chance to raise the spirit body in this life. Practitioners of Taoist Alchemy believe that if we give birth to the spirit body and develop the immortal body in this life, we can overcome the cycle of reincarnation.



Fig. 1.10 *Creating the Energy Body in preparation for the Spiritual Body.*

Once the "baby sitter" or soul body is formed, it is in the Yin stage, or infancy (soul embryo). We need to feed, raise, educate and train the young soul to become fully grown.

Once the soul body is developed, we can give birth to the spirit body. To cultivate the young spirit body until it is fully mature can take 14 to 18 years. We also use the energies of nature (trees, sun, moon and stars); virtually all sensory experiences of a positive nature become nourishment for the growth of the spirit within the physical body.

Many masters who attained this level of the immortal body were able to transform the material into the immaterial and transfer it into the spirit body. At the moment of death, they were able to transfer their consciousness, their energy and the physical elements of their bodies up with them into the spirit body, although even this level is not yet the true immortal body. In this process their physical bodies actually shrank in size; they may have weighed two-thirds of their usual weight after their physical deaths occurred. This meant they had successfully transformed much of their material being into an immaterial state while retaining full consciousness.

Cultivating the Yang Stage of the Immortal Body: Marrying the Light - Greater Kan and Li



Fig. 1.11 *Greater Kan and Li*

To merge with the light of the Tao, we must awaken and nourish the awareness that we are in truth children of the light. Once we have fully grown the spirit body, it will be the same frequency as the light of the Tao and can become one with that light. Other traditions refer to this light by such names as the Holy Spirit or Great Spirit; we also refer to it as the "outer light."

The Greater Kan and Li meditation teaches us how to recognize the inner light of our own spirits and shows us how to merge with or "marry" it to the outer light. Once we connect with and "marry the light," we give birth to the second stage of the true immortal spirit. Taoists refer to this as the Yang body. One continues to transform the physical body energy to feed the immortal spirit so it can mature.

At this stage of practice, we learn to digest increasingly higher-grade energies of the Higher Self and Universal Forces from the sun, moon, planets, stars and galaxies, and from the mind of the Tao itself. An awakening to that which is eternal and enduring occurs through this practice. Cognizant of our true nature as spirits, we experience the ability to leave the physical body and travel in the immortal spirit body, which leads to experience of the inner worlds of spirit. Fear of death is vanquished as we become familiar with life beyond physicality.

Greatest Enlightenment of Kan and Li

At this level one transfers all physical essence into the immortal body. When all the body's material elements are transformed into subtle Chi, what remains is known as the "rainbow body." When a master of this level leaves this world, there is nothing left of the physical body but nails and hair. Death is still necessary to speed up the process.



Fig. 1.12 *Union of Fire and Water*

Sealing of the Five Senses, Congress of Heaven and Earth, Reunion of Heaven and Man

At this level death is transcended entirely. One can simply transform the physical body into the immortal body and leave this world or return to it at will. This is the state of complete physical immortality. It takes from eighty to a few hundred years to complete these practices and transform all the material elements of our body into the immaterial. The final goal of ascending to heaven in broad daylight is reached.

There are records in Chinese history of many thousands of Taoist immortals who reached the level of daylight ascension in the presence of many witnesses. In the Bible, Elijah and Moses also accomplished this feat. In the final stage of this practice, the adept can unite the immortal spirit body, the Energy Body, and the physical body, or separate them at will. It is then that the human being knows full and complete freedom as an immortal, where no world is a boundary.

Chapter 2
Taoist Cosmology

Ancient Taoism is rooted in deep observation of naturally occurring Universal processes and their effects upon human beings. Newtonian physics of the West understands these processes as the mechanics of cause and effect. Taoism understands them as the interactions of a vast sea of energy that is constantly creating and recreating the universe in infinite ways. Most religions and esoteric systems study these processes (the ways of God) through scriptures and practices based upon the immaterial. Taoism studies both the material and immaterial aspects of nature and the Universe in the belief that the immaterial is both the source for the material and a product of it. In other words, physical and non-physical processes are sources for each other.


Ultimate
Stillness
Yang
Super Cluster
Creation
Yin
Super Cluster
Tai Chi
5 Elements
Milky Way Galaxy
Earth Man
100,000 Things

Fig. 2.1 *Taoist Cosmology*

The Void: Our Original Source

Through observing nature and the effects of energy within the human body, the ancient Taoists were able to trace the universal energy back to its point of origin. Upon developing an empirical approach with which to contact this source of observable phenomena, they established the concept of the primordial void as the point of departure for all creation. This void was given the name Wu Chi, which is depicted as an empty circle in traditional Taoist art because it is beyond human description. For energy to begin generating the effects and forms of nature and the universe, something had to stir within the Wu Chi. This first stirring created the division between the material and the immaterial as all the processes of the universe began at this time.

Yin and Yang



Fig. 2.2 *Duality of Yin and Yang*

Taoists refer to the first observable variations of the Universal Force, which emanates from the Wu Chi, as Yin and Yang. These two qualities of this force can be understood as the positive and negative poles of the primordial energy. Yin and Yang are inseparable tendencies of all energy, and it is impossible to have one without the other. Their interactions are the root of all universal action; hence, the polarities of Yin and Yang are an intrinsic factor of all creation.

The theory of Yin and Yang is one of the most simple and sublime symbols of the way nature and the Universe interact. The circle that encompasses the symbol is representative of the Tao, the undifferentiated whole, the Universe, ultimate reality. Yin and Yang are terms that shed light on the process of the Tao. Yin describes the feminine, the contracting, the dark, deep side of nature and Yang describes the masculine, projective, electric, light, surface side of nature. Yin and Yang are not two separate states, but an interwoven aspect of one. Just as day cannot exist without night, or male without female, Yin and Yang are opposite co-existing elements of the same Universal substance. They are an interwoven and continuous processes of decaying and becoming. Yin and Yang describe the process of a changing dynamic picture of reality.

Five Major Forces of the Universe

The Taoists observed that Yin and Yang interactions follow five basic patterns which came to be known as the Five Tendencies or Five Processes of Energy. (Such interactions have been misleadingly translated as Five Elements, thereby confusing the process with the actual physical elements.) In Taoism the physical elements found in nature symbolically express the Five Tendencies of Energy in motion. Thus fire represents energy rising; water represents energy sinking; wood represents energy expanding; metal represents energy solidifying; and earth represents stable or centered energy. Each of the five elemental tendencies of energy are dependent upon the interactions of Yin and Yang emanating from the primordial void.



Fig. 2.3 *Oneness, Duality and the Five Elements*



Pre-composting: Draw negative emotional energy from organs to collection points. Neutralize with the virtuous energy from the organs and heart.

Composting: Draw the neutralized energy to the Pakua. Fuse the neutral energy with love and compassion energies from the heart.

Heart Collection Point: Transform hate, cruelty, impatience into love, joy, happiness.

Lung Collection Point: Transform sadness, grief, depression into courage, righteousness.

Spleen Collection Point: Transform worry, anxiety into fairness, openness.

Kidney Collection Point: Transform fear into gentleness, calmness, silence.

Liver Collection Point: Transform anger, frustration, jealousy into kindness, generosity.

Fig. 2.4 *Transform Excess Negative Energy into Positive Energy*

The Five Elemental Forces are expressions of energy that can be observed in nature and throughout the universe. In space they influence the motions of all stars, planets and cosmic phenomena. In nature they promote interactions between the five elements of fire, water, wood, metal and earth. Within the human body they affect the five major organs of the heart, kidneys, liver, lungs and spleen. Just as western science understands the atoms and subatomic particles to be the fundamental units of all matter, the Five Elemental Forces are understood to be the essence of all processes. The forces that influence the cosmos are identical to those which affect nature and our bodies.

Eight Forces


離
Top
Prospering
S-2
Fire-Li
Yang
Red
Summer
Heart
坤
Stabilizing
5
Earth-Kun
Harmony
Yellow
Indian Summer
Spleen
Left
兌
W-4
Contracting
Lake-Tui
Rain
White
Fall-Metal
Lung
Left
Ovary/Testicle
Heaven
Chien
8
乾
Blue Winter
Kidney
Water-Kan
Yin
N-1
Gathering
Bottom
坎
艮
Right
Ovary/Testicle
Mountain
Ken
6
Right
震
E-3
Generating
Thunder-Chen
Lighting
Green
Spring-Wood
Liver
巽
7
Wind-Sun
Gall Bladder

Fig. 2.5 *Eight Forces and Directions*

The Eight Forces represent a more detailed aspect of the forces of nature and the Universe. They are represented by the symbol of the pakua and the eight trigrams. In Fusion of the Five Elements, the pakua was introduced as a way to direct and gather the Chi into a pearl at the lower abdomen. In Cosmic Fusion, the pakuas are used in greater detail to create a stronger connection with the forces of nature and draw much more energy into the pearl.

Using the pakua in the meditation practice is a way to focus energy. The pakua creates a vortex that enables the practitioner to collect, gather and condense Chi. This vortex of energy is used to not only create a strong connection within ourselves, but a harmonious relationship with all the forces of nature.

Return to the Wu Chi

The Taoists realized that we are connected to the stars through our bodies as the human form is a product of stellar energy and matter. With the basic understanding that man, nature and the universe are expressions of primordial energy (or the Wu Chi), the Taoists devised methods to tap the energy of the five elements. This was done to enhance the processes of the Five Elemental Forces within our bodies, which can promote health, refine our spirits, and eventually reunite us with our source, the Wu Chi. Deep within our subconscious minds are memories and desires for the unity and bliss which preceded the dense vibrations of our gross physical state. So the ultimate purpose of Taoist practice is to return to our original state, the Wu Chi.



Fig. 2.6 *Return to the Oneness (Wu Chi)*

In the advanced disciplines of the Universal Tao students begin to work more consciously with the Five Elemental Forces emanating from the cosmos. Advanced practice involves collecting and absorbing energy from different sources in the universe while traveling in the energy and spirit bodies. Taoists move closer to the original source through the vastness of space in the same way a traveler moves from station to station in a train. Generations of Taoist masters have refined and mapped the simplest and safest approaches to follow. Because it is impossible to realize the Wu-Chi in one step, the journey is divided into several stages.

Returning to the Wu Chi: First Three Steps

1. The first step of stage one is to upgrade and maintain your physical health while stabilizing your financial and social conditions. Your body is a vehicle for processing energy, and the healthier you are, the more energy it will process at a faster rate. Your health and processing capabilities will enhance greatly through the Microcosmic Orbit, Six Healing Sounds, Inner Smile, Healing Love and Iron Shirt Chi Kung practices. Your finances and social interactions should be stable so that you can create space in your life for these disciplines.
2. Next you will learn how to use accumulated energies for traveling beyond this earthly plane to the moon, sun and planets. This is similar to the way a space shuttle uses a booster rocket to push it beyond the earth’s gravitational field. In Taoism the Microcosmic Orbit and Fusion practices create the Energy Body to help boost the immortal body (spiritual body) out of this world. The healthier you are internally, the more power you will be able to generate to leave the confines of the physical body. When you can travel out of this reality and back, you will gain the raw materials necessary to build more powerful energy and spirit bodies for longer and farther journeys.
3. The higher practices involve traveling to and from the stars and constellations particularly the North Star and Big Dipper using the energy and spirit bodies. The North Star is a stable and constant point in the sky. For Taoist practitioners, using the North Star was a way to find direction in the Universe. The North Star is the gate of heaven. In the higher practices, the energy is drawn into the body to create that connection between the physical and the Universal bodies.

The human body is a powerful transformer. The sexual energy is the body's most powerful source of fuel for journeys to the higher planes. This is why the Healing Love practice is so important for spiritual development. The practice of Iron Shirt Chi Kung also helps the physical body absorb cosmic energy through the skin and bones to be transformed and refined into more fuel. Fusion of the Five Elements provides another mode of energy refinement through the transformation of negative energies into positive life-force, which is lighter and healthier for the body. All of these internal methods help one develop the means of traveling beyond this world. Their ultimate purpose (after rejuvenating the body) is to accumulate the raw materials for the construction of a stronger and more powerful vehicle for the return to the Wu Chi.

Many other systems have their own means of returning to the source. Monks, nuns and priests emphasize detachment from the world and non-involvement in worldly affairs. They have no relationships with other people and no sex, which leaves them with abundant sexual energy to be transformed and used for higher spiritual work. Such spiritually inclined people make the best and most use of sexual energy. In general, when normal people accumulate sexual energy to the same degree as monks, nuns or priests, they have no way to control it, and internal imbalances are created until it is released. The Universal Tao practices can give anyone the ability to use this energy to improve the body and spirit.

One should not believe in the Taoist teachings without experiencing the practice and its results first hand. This involves learning about the human body, the Universal forces which affect it, and the inherent desire we all have to return to our source. Taoism offers a clear, direct path to the Wu Chi, whereas many other systems provide only dogma and restrictions that can hinder spiritual growth. The Tao is not an escapist philosophy, however, as there is no need to remove yourself from society or restrict your relationships or sexual love. You can continue to live normally as you accumulate energies that will gradually improve your health while providing raw materials for the highest spiritual growth.

Chapter 3
Goals of the Fusion Practice

The Taoist study of **Inner Alchemy** was introduced in Fusion of the Five Elements. The Taoists developed the Fusion of the Five Elements practice to develop connections between and gain control of the inner and outer Universes.



Fig. 3.1 *Taoist Inner Alchemy*

They understood that virtually everything that exists in the Universe can be broken down into the Five Elements. The Fusion practice begins by understanding the dynamics of the Universe, the planet Earth, and the human body with respect to their relationships to these Five Elements.



Fig. 3.2 *Five Elements, the Planets and the Cosmos*

The knowledge of Inner Alchemy is a necessary step in becoming connected to the outer Universe, from which an unlimited supply of powerful energy is available to be used for an individual's physical and spiritual benefit.

The five basic formulas of Fusion I, II, III can be likened to wiring blueprints for making the subtle energy the vehicle, the spaceship connections that link vital organs, glands and senses so that their respective energies can be fused and balanced in the collection point and the pakua. The formulas lead the student systematically through the process of creating four pakuas and an energy pearl.

Five Element Organ Correspondences

Yin Organs	Liver	Heart	Spleen	Lungs	Kidneys
Yang Organs	Gall Bladder	Small Intestine	Stomach, Pancreas	Large Intestine	Bladder
Openings	Eyes	Tongue	Mouth, Lips	Nose	Ears
Positive Emotions	Kindness Generosity	Love, Joy	Fairness, Openness	Righteousness, Courage	Gentleness
Negative Emotions	Anger Envy Frustration	Hate, Impatience	Worry, Anxiety	Sadness, Depression	Fear, Stress
Transform Pure Organ Energy into a Virgin Child Dressed in	Green	Red	Yellow	White	Blue
Transform Pure Child Energy into an Animal	Green Dragon	Pheasant, Red Bird	Phoenix, Yellow on Red	White Tiger	Blue Deer
Earth Force takes the form of	Green Dragon	Pheasant, Red Bird	Phoenix, Yellow on Red	White Tiger	Black Tortoise
Directions	East	South	Center	West	North
Planets	Jupiter	Mars	Saturn	Venus	Mercury
Universal Energy Force	Generating	Prospering	Stabilizing	Contracting	Gathering

Fig. 3.3 *Five Element Organ Energy Chart*

Energy drawn from the organs and senses into the collection point and transformed negative emotions are fused and condensed into a pearl through the pakuas. When the resulting pearl, with its refined, balanced, neutralized energy is circulated through the Microcosmic Orbit, the body absorbs this enhanced life-force. The pearl is then used to form the Energy Body.

Cosmic Fusion builds on the foundation of internal alchemy laid in Fusion of the Five Elements. The student is encouraged to take this opportunity to review the basic Fusion practice.

Once the negative emotions have been drawn out and transformed, the pearl is moved through the creation cycle, nurturing the virtues. These qualities are cultivated, blended and condensed into the pearl, forming the energy of compassion —the essence of the senses, glands, organs and the mind.


Heart Collection Point
Lung Collection Point
Spleen Collection Point
Lung Collection Point
Kidney Collection Point
Liver Collection Point
Kidney Collection Point

Fig. 3.4 *Front and Back Collection Points*


Heart Collection Point
Liver Collection Point
Lung Collection Point
Lung Collection Point
Kidney Collection Point

Fig. 3.5 *Left and Right Collection Points*

This highly refined pearl can now be used to open and clear four of the eight specific energy channels in the subtle body: the Three Thrusting Channels used for cleansing and protection, and the protective belt route that surrounds the Thrusting Channels.

Inner Universe reflects the Outer

The Fusion practice offers a practical way to strengthen the conscious connection with the outer Universe. During the practice of Fusion, the essence of life-force energy found in the organs, glands and senses is transformed, purified, condensed and combined with the Universal, Cosmic Particles and Earth Forces in order to achieve internal balance. This transformation of quality energy into a harmonious whole can effect positive changes in the human body. Controlling this energy enables each individual to attain balance and harmony of these energies on physical, emotional and spiritual levels. Because the inner Universe is a reflection of the outer one, the balance and harmony attained in the inner Universe enables the individual to attain balance and harmony with the outer Universe. Fusion of the Five Elements, the first in a series of the Taoist practice of Inner Alchemy, focuses on the interaction and fusion of all five elements and their correspondences. To understand this interaction, especially with respect to the organs, glands and senses of the human body, it helps to be aware of one of the Taoist laws of the Universe: *Nothing remains the same; everything changes because the Five Energies of Nature constantly interact and change*. This acknowledgement that change is constant contrasts sharply with the Western framework. Under this assumption, each individual's disposition and health is influenced by the balance within him or her of these five energies, a balance affected by the ever-changing conditions of the Universe.

The outer Universe is comprised of Universal Force, Cosmic Particle Force and Earth Force from which all things emerged and whose three combined forces sustain all existence. The concept of Inner Alchemy is grounded in the Taoist belief that the inner Universe is a reflection of the outer Universe. There are connections that can be made between the inner and outer Universe through which energy, recognized and experienced in the inner Universe as Chi, or life-force, can be greatly increased and enhanced by the immense power of the outer Universe.

Overview of the Cosmic Fusion Universal Tao divides Fusion into Three Parts

Fusion of the Five Elements

First Part

Fusion of the Five Elements makes use of pakuas and energy collection points to balance, connect and draw out negative emotional energies found in the organs. These energies, along with their corresponding glands and senses energies, are then fused and transformed into pure, life-force energy.

The purity of this energy has an adhering and magnetizing quality enabling it to condense into a ball of refined energy which is called the pearl.

The pearl is then used to connect to the Universal, Cosmic Particle and Earth Forces whose energies become part of the pearl. A soul or Energy Body is formed from the pearl, enabling the individual to go beyond connecting with the forces of the universe on a purely physical level. Later the pearl returns to the organs and glands to enhance them and provides a protection to the physical and soul body.

Fig. 3.6 *Forming the Compassion Heart.*

Second Part

Cosmic Fusion focuses on using the pearl to grow or intensify the energy of good virtue. It makes use of the interaction of the elements described as the Creation Cycle of the Five Elements Theory to circulate positive Chi or virtuous energy through the major organs. All the energy gathered during this cycle is combined to form a beautiful pearl of Compassion energy. This pearl is then used to open and cleanse specific channels that pass through the physical body into the Energy Body.


Summer - Fire - Heart
Love, Joy, Happiness
Indian Summer-
Earth - Spleen
Openess,
Fairness
Kindness,
Generosity
Spring -
Wood - Liver
Gentleness,
Stillness
Winter - Water
Kidneys
Courage,
Righteousness
Autumn -
Metal - Lungs

Fig. 3.7 *Creation Cycle in Nature and Human Body*


Fire
Earth
Metal
Water
Wood
S
Love
Fire-Li
Yang
Red
Summer
Fairness
Earth-Kum
Harmony
Yellow
Indian Summer
W
Courage
Lake-Tui
Rain
White
Fall-Metal
Heaven
Blue
Winter
Water-Kua
Yin
Gentleness
N
Mountain
E
Kindness
Thunder-Chen
Lighing
Green
Spring-Wood
Wind

Yin movement Feeds

Fig. 3.8 *Creation Circle*



Fig. 3.9 *Forming the Cosmic Compassion of the Heart*

Third Part

The energy of the positive emotions of all the organs is absorbed into the pearl and then circulated in four of the eight special channels: the Microcosmic Orbit (Governor and Functional Channels), the Thrusting Routes, and the Belt Routes. The Thrusting Routes run through the center of the body, linking the “chakra” centers. The Belt Routes spiral around the body strengthening the aura and providing a form of psychic self-defense.


Crown
Pituitary Gland
(Mideyebrow)
Cranial Pump
(Base of the Skull)
Hsuan Chi (Throat)
Ta Chui (C-7)
Shan Chung (Heart Center)
Gia Pe
Chung Wan (Solar Plexus)
Chi Chung (T-11)
Navel
Ming Men (Door of Life)
Male: Sperm Palace
Female: Ovarian Palace
Heding
Chang-Chang (Coccyx)
Wei Chung
Hui Yin (Perineum)
Yung Chuan
(Sole of the Feet)

***Fig. 3.10** Cosmic Orbit with Ancient Chinese Points*

The three Thrusting Channels, sometimes referred to as Thrusting Routes and the Belt Channels or Belt Routes, opened during Cosmic Fusion, permit a freer flow of energy throughout the body.



Fig. 3.11 *Cosmic Thrusting Channels Women and Men*

The Thrusting Channels are opened first. Their primary function is to cleanse specific energy pathways in the body, thereby opening them up for the energy to flow freely. The Belt Channel surrounds the physical body and the internal Thrusting Channels. Both channels help to build a denser body and provide protection to the body, but they have another function.



Use eyes to help spiral the Belt Channels.









__Fig. 3.12__ Belt Channels and Thrusting Channels

With the additional energy generated during the practice of Cosmic Fusion, you will have enough energy to create a new Energy Body above the physical body. Another important aspect of the Fusion of the Five Elements practice is learning how to temporarily separate the Energy Body and the Physical Body. In life, our three bodies, the Physical Body, Energy Body, and Spirit Body (consciousness) all overlap and are generally inseparable. At death, the physical body is no longer a fit vehicle for holding the material five elements together and Chi and consciousness are forced to leave. To avoid the traumatic disorientation and confusion that can occur at death when the energetic essence and consciousness are involuntarily thrust out of the physical body into unknown territory, we can familiarize ourselves with the “out-of-body realm” by temporarily separating the Energy Body and Spirit Body from the Physical Body, as a “dress rehearsal” for death.

Consciousness always requires some sort of vehicle to manifest. Its gross vehicle is the physical body. Its more subtle vehicle is the Energy Body (sometimes referred to as the “subtle” body). We emphasized earlier that the virtues are the true energetic essence of our organs. Although we may identify ourselves more with our physical body than anything else in the world, it is our energetic essence, not our physical body, that survives after death and has the capacity to be immortal.

The Thrusting Channels and Belt Channels can be extended up into this Energy Body and Spirit Body. In this way they serve as connecting links between the organs and glands of the Physical Body and the transferred consciousness that is the Energy Body. Eventually, the channels serve as conduits through which the Spirit Body is boosted to the Mid-Plane. These advanced practices are called the meditations of Kan and Li.

If the Energy Body is thought of as a booster rocket, then the Spirit Body is the shuttle. Once the Spirit Body is boosted through the open channels into the Mid-Plane, it collects a higher quality of energy. The Spirit Body then returns with the higher quality energy to the Physical Body. In the next effort this energy is used to construct a stronger, more intense Energy Body that can boost the Spirit Body to a higher Mid-Plane level. The cycle continues bringing the Spirit Body to higher and higher levels, while increasing the life-force energy for use by the Physical, Energy and Spirit Bodies.


3. Spirit Body
2. Energy Body
1. Physical Body
The booster rockets separate (the Energy Body completes the lifting of the Spirit Body).
3. Shuttle flies free (Spirit Body).
2. Booster Rockets lift-off with the shuttle (Energy Body).
1. Launching (Physical Body)

Fig. 3.13 *Energy, Physical and Spiritual Bodies*

By regularly turning the awareness inward in the Fusion of the Five Elements practice, we gradually come to know our energetic essences as well as we know our face, our arms and our legs. We learn to distill these essences into a pearl, as a sort of “space capsule” to carry our essential energy and consciousness out of the physical body. With regular practice, Taoists who follow the path of Inner Alchemy learn to move their Energy Body and consciousness in and out of their physical body as easily as one might walk from one room into another.

Chapter 4

Energetic Preparations for Meditation Practice

Meditation practices are enhanced by developing one's sensitivity to subtle energy and by exercising to improve postural alignment, increase flexibility of the spine and deepen relaxation of the physical body. The next sections present a series of suggested exercises to help the student meet these goals.

Chi has many sensations. Some of the most common are tingling, heat, expansion, an electrical sensation (like the feeling of static electricity), pulsation or effervescence. This is not the actual Chi itself, but the signs of increasing Chi in a particular area. Chi itself is more mysterious, subtle beyond definition. For more details in the practices of Spinal Cord Breathing, Rocking the Spine and the Inner Smile to relax the whole body check with the book by Mantak Chia "*Awaken Healing Light*".

Preparing for the Fusion Meditations

Prepare the Environment

Find a quiet place to meditate where there are no distractions. Some places have naturally peaceful Chi: mountains, forests, caves, gardens, monasteries or beautifully designed meditation rooms. Once you have experienced such a place, you can just recall it. Set aside a corner of your room for your practice and recall your connection to the forces of nature.

Keep your meditation place clean and pleasant.

Avoid interruptions. Plan to meditate early in the morning before other people are awake: the body is rested, the air is fresh, and the earth itself is energized.

Late at night is also fine. Select a time that works well for you with your own rhythms and schedule.

If you allow yourself time each day to cleanse your emotional, energetic and physical bodies, you will soon reap the rewards in every area of your life.

Conserve Energy and Purify your Body with an Appropriate Diet

To clear your digestive tract, it helps to reduce the amount you eat, to eat less meat, fish and poultry and to increase the amount of fiber in your diet. Unless you are a vegetarian, it is recommended that you eat about 80 percent grains and vegetables, 10 to 15 percent fish and only 5 percent meat and chicken.

Loosen, Stretch and Warm Up the Body before Meditating

Once you have a quiet place and are ready to meditate, spend time loosening up the body, particularly the spine, before you sit down to practice.

The Universal Tao recommends doing some stretching exercises, Chi Kung and Tai Chi before you begin to meditate. These exercises are both invigorating and relaxing; they relieve muscle tensions, stimulate the blood circulation, get rid of stale air in the lungs and oxygenate the blood. As an alternative, you can take a relaxing stroll outside.

Doing some movement before entering the stillness of meditation can help you shake off the sluggishness that comes from being too sedentary and ease the tensions that might build up during a hectic day. Then when you sit down, you are ready to begin. Use the Simple Chi Kung exercises to loosen your spine and prepare the mind and body for meditation.

Wear Loose and Comfortable Clothing

The clothing you wear for meditation should be loose and comfortable. It is very important that your clothes restrict neither the Chi flow, the blood circulation, the nervous system nor the breath.

It is preferable to wear clothing of natural fibers so your body can breathe. During meditation, all the pores open wider and breathing in energy through them requires looser clothing. When you have learned to breathe through the skin, your body will need to contact more fresh air.

Establish a Stable Sitting Position

The body must be stable for the mind to be stable. It has been said, "An anxious mind cannot exist in a relaxed body." The mind and body are clearly connected and when the body and breath become peaceful, the mind easily follows.

If your posture is firm and balanced, it will be easy for you to relax, and you will already be halfway toward achieving a tranquil and focused mind. But if your posture lacks balance and stability, your muscles will soon tire and become tense, your attention will waver like a candle in the wind.

Consider seven points in preparing a good meditation posture: base, hands, spine, shoulders, chin, eyes and tongue.

1. **Base**: Your base is the foundation of a good meditation posture. To accommodate the movement of internal and external forces generated by the Taoist practices we need to stay grounded and establish a good connection with the earth's energy. The more Chi one moves through the body, the more important grounding becomes to prevent overheating of the organs and other negative side effects.

   The soles of the feet provide an ideal connection to the earth through the Yung Chuan (Bubbling Spring) points. These are specifically designed to absorb the earth's energy and conduct it up into the body. The legs also help filter the raw energy to make it more readily digestible.

   It is best to sit on a straight backed chair to practice the Fusion Meditations. Your weight should be evenly divided over four points: your two feet and the two sitting bones (the tuberosities of the ischium) *(Fig. 4.1)*. Place the feet flat on the floor the same distance apart as the hips. The calves of the legs should be vertical, like pillars. Try to have the knees and hips at the same level, or keep the knees slightly higher.

   The part of the pelvis known as the ischium is structurally designed to hold a tremendous amount of weight. Avoid leaning back and sitting on the coccyx and sacrum instead of the ischium. Honor Mother Nature's design by sitting on the ischium and not on the tailbone, which puts pressure on the sacrum, one of the major pumps in the spine for cerebrospinal fluid, a vital cushion for the nervous system. Check to make sure your weight is evenly distributed over the four points to establish a solid base to support the body during meditation.



Fig. 4.1 *Sitting Bones*

2. **Hands**: Let your hands rest in your lap, clasped together with the right palm over the left palm and the right thumb and forefinger wrapped around the base of the left thumb. You may rest your hands on a pillow placed on your lap *(Fig. 4.2)*. The clasped hand position works especially well to consolidate and balance the energies generated during the meditation.



Fig. 4.2 *Using a small pillow helps release shoulder stress.*

3. **Spine**: The spine should be straight but not stiff and in good vertical alignment with gravity. You can imagine your head being pulled up by a string. As it rises, allow the spine to elongate, increasing the space between vertebrae *(Fig. 4.3)*.


Feel as if a string is lifting your head up.
Pull your chin back slightly.
Sit up straight on your sitting bones.
The feet should firmly touch the floor.

Fig. 4.3 *Correct Sitting Position*

Some people find their backs become tired during long rounds of meditation. Good alignment helps prevent this by taking some of the stress off the muscles and putting it instead on the skeletal structure where it belongs. The skeletal structure is designed to support hundreds of pounds without effort when properly aligned. Practicing Iron Shirt Chi Kung and Tai Chi is very helpful for strengthening the muscles you use in sitting and for learning the body mechanics of good alignment.

The spinal column houses many nerves, and it is also a major part of the Microcosmic Orbit pathway. If the spine feels relaxed, clear and open, the mind will feel more awake and alert too.

4. **Shoulders**: The shoulders should be relaxed and balanced over the hips. The armpits should be slightly open allowing enough space to hold a Ping Pong ball *(Fig. 4.4)*. This permits free circulation of blood and Chi into the arms and keeps the nerves in the arms from being impinged.



Fig. 4.4 *Arms' Position*

5. **Chin**: The chin should be drawn back slightly, with as little strain as possible, so that the ears are over the shoulders. If you strain too much to bring the head back, your muscles will soon tire.
6. **Eyes**: Your eyes should generally be closed or slightly open with the gaze directed downward. Or you can focus on the nose, and from the nose focus into the heart. You can open the eyes for a while if you feel sleepy or distracted *(Fig. 4.5)*.
7. **Tongue**: The tip of the tongue should be touching the upper palate *(Fig. 4.6)*. This connection acts like a switch in that it connects the Tu Mo and Ren Mo, the Governor and Functional Channels. The best point for you to use is the one where you feel the strongest sensation of Chi.



Fig. 4.5 *Turn the mind and eyes inward. Focus into the heart and then down into the navel.*



Fig. 4.6 *Touch the tip of your tongue against the upper palate.*



Fig. 4.7 *Smile to the organs and feel the organs smile back to you.*

Chapter 5
Beginning Fusion Element Meditation

Pakua



Fig. 5.1 *Pakua - Eight Forces*

The pakua is a symbol of the eight forces. In the Fusion of the Five Elements meditation the pakuas are used to gather and collect the energy of the organs and fuse them into a pearl. Here in the Cosmic Fusion meditation, the pakuas are again used to fuse energy into a pearl. Now, instead of just using the energy within the body, we combine the energy of the organs with the energy of the Universe. This is a technique used in the Fusion practice to condense and gather the abundant energy that surrounds us into something that is usable and digestible to the body. Forming the pakuas will be used in all the Fusion formulas.

The first step is to form the pakua at the lower abdomen to connect with and attract the five energies and the eight forces. The goal is to balance and transform the emotional energies of the organs. The next step is to form the facial pakua. The facial pakua gathers and transforms the energy of the senses and the thoughts down to the lower abdomen. The Universal pakua is then created to gather and collect the energy of the Universe into the lower abdomen. All these energies once gathered are condensed into an energy ball, or a pearl of white light. This highly refined ball of energy is then circulated through all the channels as a way to open, heal and revitalize the body, mind and spirit. This is the beginning of the transference of consciousness to a new realm.

Chanting

Chanting has been used in all systems of spirituality to help connect the practitioner to their higher source. In Christianity, chanting and singing is used to connect with God. In Buddhism and Hinduism, chanting is used to clear the space, to open the body and connect themselves with the Buddha or Hindu God or Goddess. The power of chanting and singing can be seen not only in a religious setting, but in all levels of society as well. Singing and listening to music is a very natural way to move energy.

In the Taoist practice, chanting is used to invoke the forces of the Universe. It is not necessarily about harmony. We want to get depth and power to the vibration to open the lower abdomen and create internal power. When you chant try to feel the vibration coming from the Lower Tan Tien.

Chanting in the Pakua is very similar to the sound in the genes when the replicating strands of DNA cross over. The eight sounds are the song of the crossing of the chromosomes like two serpents entwining and then they making love and one becomes two.

The pakua is a symbolic representation of the forces of nature. By chanting the names of these forces, we are able to make a connection with that force. Also, Yin and Yang are chanted as a way to contract and expand energy. The combination of chanting the forces and Yin and Yang helps to bring the power of the Universe to you as a tuning fork.

Chanting greatly increases the power and the coherence of the Pearl. After toning all eight directions, the forces of the Universe are fused into the Pearl. The Yin and Yang (Tai Chi spines) chanting helps to expand and gather, as well as contract and store the force. This will help create the connection between your internal energy and the energy of the Universe.



$12.95 NEW SCIENCE

"Extremely provocative!"
—Harvey Bialy
Research Editor, Biotechnology

The I-Gene Cube, shown in the cover photographs, has been granted a design patent (No. 313,623) by the United States Patent Office.

A startling correlation between ancient knowledge and ultra-modern science is explored in *DNA and the I Ching*. Johnson Fu Yan is from the town in China where Chu Hsi, the Sung Dynasty *I Ching* scholar, lectured and meditated. After receiving his Ph.D. from Kent State University, Dr. Yan did post-doctoral research on computational chemistry of biopolymers at Cornell University. His current interest is, of course, the interpretation of DNA and protein sequences.

ISBN 1-55643-097-3

NORTH ATLANTIC BOOKS
BERKELEY, CALIFORNIA

SCIENCE / SPIRITUALITY $12.50

THE I CHING & THE GENETIC CODE
THE HIDDEN KEY TO LIFE

"Dr. Schönberger's astonishing discovery of the identicality of the genetic code and the numerical structure and polarity principle of the I Ching is not only understandable, but also convincing and scientifically acceptable. . .

"May the ideas advanced in this book, representing the most ancient and modern results of human research, be of service to many in stimulating and deepening their own philosophy."
From the Introduction by
Lama Anagarika Govinda

The Universal claims of both the I Ching, "the book of changes," the compendium of Chinese natural knowledge, and the genetic code, "the book of life," encouraged Dr. Schönberger to establish the hypothesis of a *general system* in nature. He has verified in numerous parallels the congruence of both the I Ching code and the genetic code. The sensational results are detailed for the first time in this book.

Includes Chapters on:

The I Ching as World Formula - The Binary System and the I Ching - Psychological Impediments to an Order of Reality -Surrealism and the I Ching - Chance and Necessity in DNA -The Practice of Prediction in the I Ching plus many others.

The I Ching & the Genetic Code demonstrates the exciting link between science and spirituality!

Aurora Press

***Fig. 5.2** DNA and the I Ching book cover*
and the I Ching and the Genetic Code book cover


Nucleus
DNA
Nuclear pore
RNA
Plasma membrane
Cytoplasm
RNA
Ribosome
Protein

Fig. 5.3 *When the frequency is 8Hz transcription occurs in the nucleus, translation takes place in the cytoplasm.*


Gene
Promoter
Terminator
DNA
Transcribed RNA
RNA polymerase
RNA nucleotides
Codon
Codon
Direction of transcription
Newly synthesized mRNA
Nuclear pore
mRNA
Nuclear envelope
Cytoplasm
Key:
A = Adenine
G = Guanine
T = Thymine
C = Cytosine
= Uracil

Fig. 5.4 *During transcription, the genetic information in DNA is copied to RNA which in the Tao is known as cupping or self-intercourse.*

Formula One: Forming the Pakuas


Pre-Heaven
Left Ovary/Testicle
Heaven Chien
2
Gall Bladder
Wind-Sun
5
W-7 Contracting
Lake-Tui
Rain
White
Fall-Metal
Lung
Prospering
S-3
Fire-Li
Yang
Red
Summer
Top Blue
Winter
Kidney
Water-Kan
Yin
N-4
Gathering
E-6
Thunder-Chen
Lighting
Green
Spring-Wood
Liver
Right
Ovary/Testicle
Mountain
Ken
8
Stabilizing
1
Earth-Kun
Harmony
Yellow
Indian Summer
Spleen
Bottom
Post-Heaven
Yang Pakua
離
Top
Prospering
S-2
Fire-Li
Yang
Red
Summer
Heart
巽
7
Wind-Sun
Gall Bladder
坤
Stabilizing
5
Earth-Kun
Harmony
Yellow
Indian Summer
Spleen
Right
震
E-3
Generating
Thunder-Chen
Lighting
Green
Spring-Wood
Liver
Left
W-4
Contracting
Lake-Tui
Rain
White
Fall-Metal
Lung
兑
Right
Ovary/Testicle
Mountain
Ken
6
艮
Left
Ovary/Testicle
Heaven
Chien
8
乾
Blue Winter
Kidney
Water-Kan
Yin
N-1
Gathering
Bottom
坎
Yin Pakua
Top
Prospering
S-2
Fire-Li
Yang
Red Summer
Heart
7
Wind-Sun
Gall Bladder
Stabilizing
5
Earth-Kun
Harmony
Yellow
Indian Summer
Spleen
Right
E-3
Generating
Thunder-Chen
Lighting
Green
Spring-Wood
Liver
Left
W-4
Contracting
Lake-Tui
Rain
White
Fall-Metal
Lung
Right
Ovary/Testicle
Mountain
Ken
6
Left
Ovary/Testicle
Heaven
Chien
8
Blue Winter
Kidney
Water-Kan
Yin
N-1
Gathering
Bottom

***Fig. 5.5** Pakua - Tai Chi Symbol -*
Three Outside Lines - Eight Connecting Lines

There are two arrangements of the pakuas: the Pre-Heaven and the Post-Heaven. It is said that the Pre-Heaven pakua was discovered by Fu Hsi, a legendary figure of early Taoist history, as the Ho-Tu, inscribed, some say on a horse, others say on a dragon that rose from the river Ho to reveal itself to Fu Hsi. The Post-Heaven pakua was revealed to another legendary king, Yü, the Great, as the Lo-shu. This time it was written on the shell (back) of a tortoise that emerged from the river Lo. The Pre-Heaven pakua shows the unchanging cycle movement of these energies, the natural order of the universe and is the foundation of Fu Hsi's divinational trigrams/hexagrams, of the I Ching. The Post-Heaven pakua shows the opposing interaction and movement of these energies, which are responsible for the changes and creation of all the things in the universe, in nature and in our own lives.

Creating the Front Pakua

Drawing the Pakua on the Abdomen: the Front Pakua

It is important to get familiar with visualizing the pakua. Training the mind to concentrate on a single image is of immeasurable value for spiritual practice. The image of the pakua allows the mind to focus and fuse energy. This first step is essential to the rest of the Fusion practice. One of the best ways to get this image deeply connected in the mind is to draw it on a piece of paper and place it over your abdomen. Or, if you are a little more adventurous draw it directly on the abdomen. When you draw the pakua, use blue for Yin, red for Yang and black for the frame. Sometimes it helps to work with a partner. Draw the pakua over your partner's abdomen, and do the meditation facing one another. This way you can glance at the pakua and know what forces to work with. Be creative. Do whatever works so that you get the image planted firmly in your mind.

The pakua is between the underside of the rib cage and above the pubic bone. When we chant the symbols of the trigrams, you can use your finger to draw them on your own abdomen, or while you look at the pakua on your partner.

There are 3 different major centers for generating the frequency which fuse together to form the main energy center of the body. 1. Tan Tien, the Chi Center can be measure like heat in the infrared. 2. Throat Center. 3. Third Eye Center.



Fig. 5.6 *Pakua in the Abdomen*

Practice

1. Four Signs

Kan: First Sound

a. **Kan** (Yin-Yang-Yin). The power symbol of the Water gathering and yin power, connected with the kidneys, ears and sexual organs. Evoke the energy of the symbol by repeating its sound, **Kan,** several times or until you feel the connection with the energy of Kan, which is spreading down to the sexual organs and the kidneys. The Kan sound should come from the abdomen and the throat.

b. First chant the name of the trigram Kan in a long and deep sound while you picture the symbols and touch your lower abdomen. Your eyes look down to the lower abdominal area.



Fig. 5.7 *Kan (Yin-Yang-Yin)*



Fig. 5.8 *Chant Kan (Ears and Kidney connects to the Kan)*

c. Next, chant the Yin and Yang lines of the symbol one after the other (Yin-Yang-Yin). Start from the inner side, close to the Tai Chi symbol.

d. **Yin Contract**: First expand the mind and the hands and palms to touch the universe, the cosmic. Chant the Yin, Yin, Yin as long as you feel comfortable, and continue moving your palms and draw the cosmic Chi from the universe into the navel, and feel the navel has suction. Feel your hands and the Tan Tien; the throat has the power of sucking the Chi down the Yin line to the navel. Rest. (Fig. 5.9)



Fig. 5.9 *Yin Line — — Yin Contract*

e. **Do the Yang Line**: Be aware of the Tan Tien, throat, crown and the palms close to the navel and slowly chant the long Yang sound and turn the palms out. Gradually move the palms to the left and right sides and feel your palms very long and big touching the cosmic. Rest and feel your palms in touch with the cosmic Chi. (Fig. 5.10)



Fig. 5.10 *Yang Line — Yang Expand*

f. **Do the Yin Line again**: Yin contracts; expand the mind and the hands and palms to touch the sky and the cosmic. Chant the Yin, Yin, Yin as long as you feel comfortable and continue moving your palms and draw the cosmic Chi from the universe into the navel, and feel the navel has suction. Feel your hands and the Tan Tien; the throat has the power; the Chi goes down the Yin line to the navel. Rest for a while. Feel the vibrations inside as you chant the trigram. (Fig. 5.11)



Fig. 5.11 *Yin Yang Yin Trigram* ☵

Rest. Repeat the words “ Kan” at the lower abdominal in your mind and let your eyes look down at the lower abdominal. Then you close your eyes and picture the symbols: Kan (Yin-Yang-Yin), smile and be aware the kidneys, ears and the power of the yin and gathering power. Try to imagine them in your mind’s eye and feel them imprinted on your abdomen and vibrating inside you.

Rest and project the symbol into the universe and feel the symbol in the universe reinforce the Kan in the abdomen.

Note: Doing the chanting together in a group makes it much more powerful.



Fig. 5.12 *Kan in the abdomen*

Li: Second Sound

a. The second sound is **Li** (Yang-Yin-Yang), the power symbol of the Fire, connected with the heart, the prospering power. The eyes look up at the upper abdominal, the Li Kua. The sound comes out from the area between the chest and the throat. Repeat this sound until you feel the vibration of the fire expanding upwards in the chest.
When you chant **Li** you feel the energy going up.
When you say **Li** the eyes look up.



Fig. 5.13 *Li (Yang-Yin-Yang)*



Fig. 5.14 *Chant Li (Tongue and Heart connect to the Li)*

b. Chant the name of the trigrams Li in a long and deep voice while you picture the symbols and touch your lower abdomen and upper abdomen. (Fig. 5.14)

c. Next, chant the Yang and Yin lines of the symbol one after the other (Yang-Yin-Yang). Start from the inner side close to the Tai Chi symbol.

d. **Yang Expand**: Be aware of the Tan Tien, the throat, crown and the palms close to the navel and slowly chant the Yang long sound. Turn the palms out and gradually move the palms to the left and right side. Feel your palms very long and big as they touch the cosmos. Rest and feel your palms touch the cosmic Chi. (Fig. 5.15)



Fig. 5.15 *Yang Line — Yang Expand*

e. **Yin Contract**: Your mind and the hands and palms touch the sky, the cosmos. Chant the Yin, Yin, Yin as long as you feel comfortable, and continue moving your palms up. Draw the cosmic Chi from the universe into the navel, and feel the navel has suction. Feel your hands and the Tan Tien. The throat has the power; draw the Chi into the Yang line to the navel. Rest for a while. (Fig. 5.16)



Fig. 5.16 *Yin Line — — Yin Contract*

f. **Do the Yang again**: Be aware of the Tan Tien, the throat, crown and the palms close to the navel and slowly chant the Yang long sound. Turn the palms out and gradually move the palms to the left and right side. Feel your palms very long and big as they touch the cosmos. Rest and feel your palms touch the cosmic Chi. (Fig. 5.17)



Fig. 5.17 *Yang Line — Yang Contract*

g. **Repeat the word "Li"** in your mind and let your eyes look at your Li Kua. Close your eyes and picture the symbol Li, still moving your eyes up. Smile and be aware of the heart, tongue and the prospering power of fire. Imagine them in your mind's eye; feel them imprinted on your abdomen and vibrating inside you. Rest and project the symbol into the universe and feel the symbol in the universe reinforce the Kan in the lower abdomen.



Fig. 5.18 *Li above the Navel*

Chen: Third Sound

a. The third sound is **Chen** (Yang-Yin-Yin), the power symbol of the Thunder and the Lightning, connected with the liver and the eyes, the wood element and gathering power. This sound evokes the trigram Chen that is placed on the right side (below the liver) and the sound comes out as “djen”. Repeat the sound until you feel a vibration of energy below the liver, at the right side of the pakua. When you chant “Chen” the eyes look to the right side.


Yin
Yin
Yang

Fig. 5.19 *Chen (Yang-Yin-Yin)*


Chen, Chen, Chen
Turn the eyes
to right side.
Left
Lighting Thunder in Forest

Fig. 5.20 *Chant Chen (Eyes and Liver connect to the Chen)*

b. **First chant the name of the trigram Chen** ("Djen") in a long deep throat sound while picturing the symbol and touching the right side of your abdomen. Feel the vibration of the lightning and the thunder. Look at the right side of the body, close your eyes and visualize at the symbol of Yang-Yin-Yin. Smile and be aware of the liver, the eyes and the power of generating, lighting and thunder power.
c. **Yang Expand**: Be aware of Tan Tien, the throat, crown and the palms close to the navel and slowly chant the long Yang sound. Turn the palms out and gradually move the palms to the left and right sides and feel your palms very long and big touching the cosmos. Chant the Yang, Yang, Yang as long as you feel comfortable. Rest for a while. Feel the vibrations inside as you chant the trigram. (Fig. 5.21)



Fig. 5.21 *Yang Line — Yang Expand*

d. **Yin Contract**: Be aware of the Tan Tien, the throat, crown and the palms close to the navel and slowly chant the Yin long sound as the palms touch the universe. Chant the Yin, Yin, Yin as long as you feel comfortable and continue moving your palms back. Draw the cosmic Chi from the universe into the navel and feel the navel has suction. Feel your hands and the Tan Tien; the throat has the power, the Chi goes down the yin line to the navel. Rest for a while. Feel the vibrations inside as you chant the trigram. Rest and feel your palms touch the cosmic Chi. (Fig. 5.22)



Fig. 5.22 *Yin Line* **——** *Yin Contract*

e. **Do the Yin line again**: be aware of the Tan Tien, the throat, crown and the palms move out to touch the universe. Chant the Yin long sound. Chant the Yin, Yin, Yin as long as you feel comfortable and continue moving your palms back and draw the cosmic Chi from the universe into the navel and feel the navel has suction. Feel your hands and the Tan Tien; the throat has the power, the Chi goes down the yin line to the navel. Rest for a while. Feel the vibrations inside as you chant the trigram. (Fig. 5.23)
Rest for awhile and feel the vibrations inside.



Fig. 5.23 *Yin Line —— Yin Contract*

Tui: Fourth Sound

a. The fourth sound is **Tui** (Yang-Yang-Yin), the power symbol of Lake and Rain, connected with the lungs and nose, the metal element and contracting power. This sound evokes the trigram Tui, that is placed on the left side (opposite Chen) and the sound comes out as “tway”. Chen and Tui are throat sounds. Repeat the sound until you feel a vibration of energy at the left side of the pakua.


Yin
Yang
Yang

Fig. 5.24 *Tui (Yang-Yang-Yin)*


Tui, Tui, Tui
Right
Left
Turn the eyes to left side.
Rain and Lake

Fig. 5.25 *Chant Tui (Nose and Lung connect to the Tui)*

b. **Next chant the name of Tui** in a long deep voice while picturing the symbol and touching the left side of your abdomen. Feel the vibration of the rain and the lake. Look at your left side, close your eyes and visualize at the symbol of Yang-Yang-Yin. Smile and be aware of the lungs, nose and the power of contracting rain and lake.

c. Do the Yang Line, **Yang Expand**; be aware of Tan Tien, the throat, crown and palms close to the navel and slowly chant the long Yang sound. Turn the palms out and gradually move the palms to the left and right sides and feel your palms very long and big touching the cosmic. Chant the Yang, Yang, Yang. (Fig. 5.26)

d. Do the Yang line again. **Yang Expand**; be aware of Tan Tien throat, crown and palms close to the navel and slowly chant the long Yang sound. Turn the palms out and gradually move the palms to the left and right sides and feel your palms very long and big touching the cosmos. Chant the Yang, Yang, Yang.



***Fig. 5.26** Yang Line — Yang Expand*

e. **Yin Contract**: Chant the Yin, Yin, Yin as long as you feel comfortable, continue moving your palms and draw the cosmic Chi from the universe into the navel and feel the navel has suction. Feel your hands and the Tan Tien; the throat has the power and the Chi goes down the yin line to the navel. Rest for a while. Feel the vibrations inside as you chant the trigram. Finish. Rest for awhile and feel the vibrations inside. (Fig. 5.27)



Fig. 5.27 *Yin Line — — Yin Contract*

2. Continue the practice with the next four symbols.

The last four trigrams of the pakua are: **Kun** (Yin-Yin-Yin), the Earth power, **Ken** (Yin-Yin-Yang), the Mountain power; **Sun** (Yin-Yang-Yang), the Wind power and **Chien** (Yang-Yang-Yang), the Heaven power.

Go through the same procedure as with the first four symbols to evoke the energy and connect it to the pakua.

a. Do all the 8 symbols together quickly Kan, Li, Chen, Tui, Kun, Ken, Sun, Chien (6 sets).
b. Be aware of the pakua and see it imprinted deep into the abdomen.
c. Be aware of the Tai Chi symbol and start to chant, Tai Chi, Tai Chi, and Tai Chi faster and faster. Feel the Tai Chi symbol moving faster and faster now.

Practice of the Next Four Symbols.

Symbol Kun - Earth

▬ ▬ Yin
▬ ▬ Yin
▬ ▬ Yin

Stabilization power stomach and mouth, spleen and pancreas.

Focus on Kun, Yin-Yin-Yin. Chant Kun and then chant Yin-Yin-Yin repeatedly. You can use the hand to help draw in the energy back to the Pakua. Later on, you do not need to use your fingers. Picture the symbol Kun in front of you and expand it very far away to connect with the centering, stabilizing power. Let the energy with the symbol come to you until it sticks to your forehead. Bring it down to the south/west (upper left corner) in the abdominal Pakua.



Fig. 5.28 *Chant Kun (Earth, Mouth and Spleen connect to the Kun)*



***Fig. 5.29** Yin Line —— Yin Contract*



***Fig. 5.30** Yin Line —— Yin Contract*



***Fig. 5.31** Yin Line —— Yin Contract*

Symbol Ken - Mountain



Yin side of water power and with bladder and sexual organs.

Focus on Ken, Yin-Yin-Yang. Chant first Ken and then Yin-Yin-Yang repeatedly. It is a nose/throat sound. Mark the symbol with your fingers and your eyes/mind on your forehead. Rest and feel the symbol imprinted on your forehead. Expand it far away to make the connection with the stable and strong mountain power. Feel the symbol with the energy come back. Move it to its place in the pakua on your abdomen in the lower right corner.



***Fig. 5.32** Chant Ken (Mountain connects to the back of the skull)*

Symbol of Sun - Wind



Also connects with the gall-bladder and wood power.

Focus on Sun, Yin-Yang-Yang. Chant Sun and then Yin-Yang-Yang repeatedly. Picture the symbol on your abdomen mark it with your fingers at the abdomen first and then just with your eyes and mind. Picture the symbol very far away to connect with the power of the wind until it comes back to you and sticks to your abdomen. When the reinforced symbol sticks to your abdomen, move it down to the upper right corner of your abdominal Pakua.



Fig. 5.33 *Chant Sun (Wind connects to the base of the skull)*

Symbol of Chien - Heaven



Also connects with the yang side of metal power and large intestine.

Focus on Chien, Yang-Yang-Yang. Chant Chien and then Yang-Yang-Yang repeatedly. Mark the lines of the trigram on the abdomen with your fingers and your eyes/mind. Rest and feel the symbol imprinted on the abdomen. Expand it very far away to connect with the power of Heaven. Do it several times until you feel that the symbol is coming back and sticks on your abdomen. Bring this reinforced trigram down to the lower left corner of your abdominal Pakua.



Fig. 5.34 *Chant Chien (Heaven connects to the forehead bone)*

When you finished the last imprinting of these first four symbols, make the Tai Chi symbol, spiraling with the fingers around the navel and saying: **Tai Chi, Tai Chi, Tai Chi**. This is an abdominal sound. Continue to chant it more inwardly, **Tai Chi**, **Tai Chi**, **Tai Chi**, at the same time spiraling with your fingers and eyes. When you finish the chanting, rest. Feel the Kan and the Li, the Chen and the Tui join together, fusing the energy of these forces inside of you.

We now combine the four trigrams.

- First look at your pakua and say the name of the symbol and its Yin-Yang components.
- Chant Kan - Li - Chen - Tui while moving your eyes down-up -right-left. Repeat several times.
- Rest; spiral with your fingers around the navel and continue the spiraling movement of the eyes awhile chanting Tai Chi, Tai Chi, Yin - Yang, Yin - Yang until you feel the Tai Chi symbol spiraling in the middle of the pakua connecting the trigrams together. Feel a big space, a fire burning inside of you.



Fig. 5.35 *Finish the imprinting the four symbols and four trigrams.*

Merging Energy of both Pakuas and establish the Cauldron.

a. Copy the front Pakua to the back Pakua and let the Tai Chi symbol spiral. Be aware of the front Pakua spiraling in one direction and the back Pakua in the reverse direction. You can start the front Pakua spiraling counterclockwise and the back clockwise in reverse. Merge the energy of the front and the back Pakua right in the center of the Tan Tien and form a space there for the cauldron. At this point, leave the spinning energy moving. Feel the both Pakuas still spinning and drawing Cosmic Force from all directions. Rest, and then start spinning the energy.



Fig. 5.36 *Back Pakua*



Fig. 5.37 *Front and Back Pakua*

b. When both pakuas are spiraling, focus on the center and look down while being aware of the front and the back pakuas. Chant Yin-Yang and spiral with your mind's eye in the center. Feel the big space of the front pakua and the back pakua coming into the center, merging together and creating a big space inside you for the cauldron. Feel the cauldron inside you spiraling like a big ball of fire, creating a suction in the middle of the front and the back pakua. Feel that, while you continue to chant the Tai Chi subvocally, the energies of both pakuas are sucked into the center, the cauldron. Feel the fire burning in the cauldron like a candle. Be aware of your center and of the energy there.



Fig. 5.38 *Both Pakuas are spiraling and drawn into the center.*

1. *Creating the Right Pakua*

The right pakua is a copy of the back pakua moved to the right side. Use your finger to point to the right side on the same level with the navel while you picture the symbol of Pakua. Then make the Tai Chi symbol, spiraling from the bottom to the right to the top and to the left. Chant Tai Chi and follow the spiraling with your fingers at the same time. Rest, feel the pakua spiraling and drawing energy.

2. *Creating the Left Pakua*

This pakua is a copy of the front pakua moved to the left side. Use your fingers to point to the left side ao the same level with the navel picture the symbol of the Pakua. When you feel that you are in the rhythm continue in your mind using your mind's eye to move. Chanting the Tai Chi, Tai Chi and spiraling with your hand in the middle of the left pakua. Continue spiraling with your mind/eyes until you feel the energy moving.



Fig. 5.39 *Left and Right Pakua*

3. Merging the Energies of the Four Pakuas together in the Cauldron

Go back to the right pakua, activate it and let it spiral. Go back to the left pakua and reactivate it, spiraling the Tai Chi. Focus on the center as you chant the Tai Chi and be aware of the centers of the front, back, right and left pakuas. Feel that the energies of the pakuas are sucked into the center. Feel the energy become violet light, and your mind, eyes and center spiraling.



Fig. 5.40 *Four Pakuas spiral and are being drawn into the Center of the Cauldron.*

4. Connecting the Organs and Senses with the Abdominal Pakua.

a. Bring your ears and kidneys to the Kan below.
b. Your tongue and heart to the Li on the top.
c. The mideyebrow and the liver to the Chen on your right side.
d. Your lungs and your nose to the Tui on your left side.
e. Your mouth to the Kun on your upper left side.
f. You can also connect the back part of your skull to the Ken.
g. The base of the skull to the Sun
h. The forehead point to the Chien.

Spiral the Tai Chi symbol of this pakua drawing all the energy of the organs and the senses to the center, where all these energies are combined and condensed.



a. *Kan - Ear and Kidneys* ***b.*** *Li - Tongue and Heart*
c. *Chen - Mideyebrow and Liver* ***d.*** *Tui - Lung and Nose on Left Side*



e. *Kun - Mouth and Upper Left Side* ***f.*** *Ken - Back part of the Skull*
g. *Sun - Base of the Skull* ***h.*** *Chien - Forehead Point*
Fig. 5.41 *Connecting the Organs*

Activate the Facial Pakua by enhancing it on the Forehead

The forehead Pakua is the reverse of the abdominal pakua. Use the fingers to point at the position of the Pakua. The Yin and Yang sounds generate from the abdomen but emphasis on the throat, nasal and the third eye. Later on, mark the symbol with your eyes and mind.

When you rest after making the specific sound, feel that the symbol of the trigram is imprinted on the forehead. Send this symbol out into the space in front of you to make the connection with the force of the Universe and let it come back to your body. Bring the reinforced symbol down to the trigram in the pakua in the abdomen and start to work with the next symbol.



Fig. 5.42 *Enhancing Pakua on the Forehead*

Facial Pakua

To practice this stage, we form a pakua on the face. This pakua has its face in front of us (as if the symbol is looking toward you), so that the Chen will be on the left side and the Tui will be on the right side and all the other trigrams will be arranged accordingly. The Tai Chi symbol will be on your the center at the mid-eyebrow and expands up and down to the forehead and the ridge of the nose right where the cavity of the spirit is. All the senses are controlled from this point. When information and energy from outside is coming in to trigger the senses, you will feel it first very strongly in this center and then the senses will connect immediately to the center of the front pakua below.



Fig. 5.43 *Use the Eye Mind Power "I" to help move the Eight Forces.*

Practice to form the Facial Pakua.

1. In order to help you get more Chi from the universe, you can start with the “Opening the Three Tan Tiens to the Six Directions” (See the book “*Cosmic Healing I*” by Mantak Chia). If you have not learned this, you can just start with forming the Pakua.



Fig. 5.44 *Opening the Three Tan Tiens to the Six Directions*

2. Then smile, feel your senses turned inward, feel them connecting to the organs. Your mideyebrow connects to your eye and liver, your tongue connects to the heart, your ears connect to the kidneys, your nose connects to your lungs and your mouth connects to the spleen. Feel all the senses turned inward to the mideyebrow and down to navel, going deep inside you. Your abdomen is like a big ocean, a big space, big like a whole universe.



Fig. 5.45 *Turn all senses inward*

3. Reactivate and reinforce the pakua in your lower abdomen.

   a. Touch your Lower Tan Tien and start chanting Kan-Li-Chen-Tui-Kun-Ken-Sun-Chien touching each of the kuas as you chant them. Continue to chant the kua symbols subvocally in your mind and holding the symbol in front of your eyes. Be aware of the Heart Pakua.



Fig. 5.46 *Touch Lower Tan Tien and chant.*

   b. Spiral the Tai Chi symbol from the bottom to the right and up, chanting it while spiraling with your hand, eyes and mind. Continue to spiral with your mind and eyes only and feel the heart pakua also spiraling. The energy is pulling inward and the Tai Chi symbol is spiraling and changing to violet light.



Fig. 5.47 *Tai Chi symbol spiraling*

Start the Practice of the Facial Pakua with the First Four Symbols.

Symbol of Kan - Water ☵

a. Be aware of the mideyebrow. Use the fingers of either the right or left hand to touch below your nose. Eyes look down to the bridge of the nose. Focus on the Kan, Yin-Yang-Yin. Chant the word Kan repeatedly, vibrating it in the brain, making a throat, nose and third eye sound. Picture the trigram on your face and expand it very far away to the ocean. Feel that the energy of the Kan comes right in front of you, allowing the feeling to expand on bridge of the nose. Be aware of the Kan in your lower abdomen and move the powerful Kan from your face to your lower abdomen where it is supposed to be.


Eyes look down to bridge of the nose.
Kan, Kan, Kan
Yin, Yang, Yin

Fig. 5.48 *Kan on the face below the nose.*

b. **Yin Contract**; First expand the mind and the hands and palms to touch the sky, the cosmos. Chant the Yin, Yin, Yin as long as you feel comfortable, and continue moving your palms. Draw the cosmic Chi in from the universe into the face and feel the mideyebrow has suction. Feel your palms, fingers and the Tan Tien, the mideyebrow has power, the fingers can move in and touch below the nose. The Chi goes to the Yin line in the navel. Rest and Smile, breathing the cosmic Chi. (Fig. 5.52)



Fig. 5.49 *Yin Line — — Yin Contract*

c. **Yang Expand**: Do the Yang line; be aware of the Tan Tien, throat, bridge of the nose, the palms, the fingers and touch the face. Slowly chant the long Yang sound and turn the palms out. Gradually move the palms to the left and right sides and feel your palms very long and big touching the cosmos. Rest and smile, the Chi goes to the Yang line in the navel.



Fig. 5.50 *Yang Line —— Yang Expand*

d. **Yin Line again**, Yin contracts; expand the mind. Repeat as in the first Yin line. Rest for awhile. Feel the vibrations inside.



Fig. 5.51 *Yin Line — — Yin Contract*

The Seven Emotions			
Chinese Word	English Translation	Organ Association	Qi Manifestation
Xi	joy, happiness, excitement, pleasure	Heart	slows down and relaxes the Qi
Nu	anger, irritation	Liver	causes Qi to rise
Si	meditation, contemplation, pensiveness, worry	Spleen	stagnates the Qi
You	anxiety, sorrow, grief	Lungs	obstructs the Qi
Kong	fear, extreme anxiety	Kidneys	causes Qi to descend
Jing	shock (sudden intense fear), fright	Heart then Kidneys	scatters and deranges the Qi
Bei	grief, affliction, sadness	Lungs	disperses and consumes the Qi

Figure 3.7. The Seven Emotions and Their Effects on the Organs

- The lateral aspect (further from the center) of the body is Yang; the medial portion (middle) is Yin.

The aspects are summarized in Figure 3.6.

As Yin and Yang are in a constant state of change, always waxing and waning, two points of reference alone are not enough to aptly classify the many phases and stages of transformation; for example, day (Yang) can be further split into dawn (waxing Yang), midday (peaking Yang), and late afternoon (waning Yang). To fill this descriptive gap, the Chinese developed the theory of the Five Elements.

THE FIVE ELEMENTS

The Five Elements (Wu Xing), also translated as the Five Phases, are Wood, Fire, Earth, Metal, and Water. These Five Elements paint a clear and natural image of the changing cycles of Yin and Yang (see Chapter 23).

Furthermore, each of the Five Elements can also be divided into Yin and Yang, making a total of ten subdivisions. Wood, for example, can be subdivided into Yin Wood and Yang Wood.

The Chinese use this framework of the Five Elements to understand and categorize many different areas of knowledge, from the movements of the Heavens and the land forms of Earth to the workings of human anatomy, physiology, and psychology. Earlier in this chapter, it was noted that our organs and their associated energy channels are divided into Yin and Yang. In addition, each of the organs is also related to one of the Five Elements. The Liver and Gall Bladder relate to the Wood Element; the Heart and Small Intestine to the Fire Element; the Spleen and Stomach to the Earth Element; the Lungs and Large Intestine to the Metal Element; and the Kidneys and Bladder to the Water Element. The organs help to regulate the functional aspects of the Five Elements within the human body as they interact with each other to promote and maintain life.

The Yin organs, in particular, are said to store the Jing of the Five Elements. They share this Essence with their elementally paired Yang organs to assist with the Yang organs' functions. The Yin organs also store the Five Agents (the Five Virtues), and are more readily disrupted by the Seven Emotions (anger, joy, worry, grief, sadness, fear, and shock) than are the Yang organs.

The emotions are said to be the primal force behind energy transformation; however, each individual will have a separate reaction to specific emotional changes, based on his or her dominant elemental pattern. Five internal organ emotions are associated with the energy of the Five Elements:

1. Anger - Liver - Wood
2. Joy - Heart - Fire
3. Worry - Spleen - Earth
4. Grief and Sorrow - Lungs - Metal
5. Fear - Kidneys - Water

In this way, the energies of the Five Elements shape all aspects of a human being: physical, energetic, mental, emotional and spiritual (Figure 3.7).

CONGENITAL CONSTITUTIONS

Most individuals are born with a dominant element, which will determine the individual's physical, energetic, and psycho-emotional constitution. When in Excess, the body's emotions can create an energetic imbalance, which in turn, can cause a destructive physical pattern within the body. An example of this process is excessive anger leading to hypertension.

The previous chapter on energetic embryology described how, from month four to month eight, the different Five Elemental Jings (Essences) enter the fetus from each of the mother's organs. Depending on the relative strength or weakness of the mother's internal organ energies during her pregnancy, the fetus will inherit a greater or lesser degree of elemental Jing from the mother. If the mother's Liver energy is dominant, then the child will have a tendency to develop a Wood constitution; if the Kidney energy is dominant, then the child develops a Water constitution, and so forth.

In addition, traditional Chinese astrology states that the various Heavenly influences at the time of birth influence the relative Five Elemental strengths and weaknesses in the newborn's constitution. Years, months, days, and hours all occur in separate cycles of five, corresponding to the Five Elements. Thus both the astrological influences at birth as well as the prenatal maternal transmission of Jing, Qi, and Shen, determine each person's congenital constitution.

After birth, the congenital Jing is cultivated and sustained through prayer, meditation, physical exercise, and sleep. In medical Qigong theory, the health of the congenital Jing determines the health and balance of the overall constitution; it determines the level of vitality and resistance to disease, as well as the mental and emotional nature of the individual. The congenital Jing, with its unique balance of the Five Elements, becomes the foundation for an individual's Qi and Shen.

The congenital influence is, however, not absolute. Postnatal factors, such as diet, life-style, environmental factors, and internal belief structures, can also influence the constitution, for better or for worse. Thus, patients with congenital deficiencies can still improve their health by prayer, meditation, medical Qigong, adequate sleep, proper diet and exercise, herbs, medicines, stress management, and other therapeutic modalities.

On the negative side, patients with strong inherited constitutions may develop serious constitutional imbalances through intemperate lifestyles such as: excess stress, overwork, excessive sexual activity, and poor eating habits. Therefore, the Qigong doctor must consider both prenatal (congenital) and postnatal (acquired) constitutional factors to understand and differentiate between the patient's innate constitution and his or her current condition.

CLASSIFICATION OF THE FIVE CONSTITUTIONS

Over the centuries, much has been written in Chinese medical literature about the Five Elemental Constitutions. The following interpretation was developed by Dr. Zhou Qianchuan, a Daoist master from Qi Cheng Shan and reputed by some to be the master of *The Yellow Emperor's Classic of Internal Medicine* (a 2500 year old three-volume text that is still one of the pivotal texts of Chinese medicine).

Dr. Zhou perceived that each of the Five Elemental Constitutions has both a characteristic physical appearance and a psycho-emotional profile. Through observing these aspects, the Qigong doctor determines a patient's Five Elemental Constitution, and from this diagnosis, the doctor discovers much about the balance or imbalance of the patient's physical and mental health.

In Traditional Chinese Medicine, somatic-build type and psyche are closely intertwined. Physical aspects, such as coloring, proportion, dominant tissue (muscle, fat, sinew, etc.), tone, movement, posture and holding patterns, as well as general vitality all express the patient's internal energetic and psycho-emotional matrices. The body type reveals to the trained Qigong doctor not only the patient's emotional history but also his or her innate personality and acquired personality characteristics.

Dr. Zhou subdivided each of the Five Elemental Constitutions into three categories: balanced nature, Yin nature, or Yang nature. The ideal is to have a balanced nature, regardless of one's elemental type. Note that the treatment addresses the mental, emotional, and spiritual balance of the five constitutions. Since the mind is so closely tied with Jing and Qi, it is not enough to simply tell patients how to change their personality to restore balance. The Qigong doctor must work with patients on all levels (physical, energetic, mental, emotional, and spiritual) to help them restore balance. Specific healing methods are discussed at length in later chapters. In general, the Qigong doctor selects treatment principles based on the Five Elements' Creative (Figure 3.8) and Controlling (Figure 3.9) Cycles to help restore balance (see Chapter 23).

For instance, a patient with a Yin Earth nature would tend to have weak or Deficient Spleen energy. Therapeutically, the Qigong doctor would choose one of the three following treatments.

1. Direct tonification of the Earth Element,
2. Tonification of the Fire Element in accordance with the principle, "To nourish the child, strengthen the mother"), or
3. Disperse or reduce the Wood Element (Wood, the "grandmother", may be overcontrolling Earth, the "grandson").



Figure 3.8 The Five Elements' Creative Cycle



Figure 3.9. The Five Elements' Controlling Cycle

In the instance of Yang Earth nature, the patient would tend to have Excess Earth. In this case, the Qigong doctor could:

1. Use a method to reduce the Earth Element directly; or,
2. Strengthen the Wood Element (the weak "grandmother" may be unable to restrain an overly strong "grandson" without help).

THE WOOD CONSTITUTION

WOOD OUTER APPEARANCE

Wood constitution types usually have a tall and slender body with a small head and a long face. They also have small, nicely formed hands and feet, broad shoulders, and a straight, flat back (Figure 3.10). By nature, they enjoy spring and summer but dislike autumn and winter. This preference is due to the vulnerability of the Wood constitution and its susceptibility to pathogenic invasion and disease during these time periods. Their dominant features include strong sinews and green-blue facial color. Their note is "jue."

WOOD PERSONALITY

The Wood personality can be divided into three subdivisions.

1. A Balanced Wood nature predisposes individuals to be confident, strong, independent, and intuitive, with a clear understanding of themselves and their goals. They are patient, able to allow things to develop naturally, and express their personality in a relaxed harmonious way. They are kind when communicating with others, creative, free-flowing in self-expression, and display merciful and unselfish traits when dealing with the needs of others.
2. A Yin Wood nature predisposes individuals to feel externally insecure, and to be always cautious. They have a tendency to worry and have a weak sense of their own abilities and potential. They are unassertive and are unsure of their identities and life purpose. They also have difficulty expressing their egos and have weak boundaries. They are timid, lack confidence, and display considerable doubt.

   Treatment for Yin Wood nature individuals involves establishing a sense of inner strength and security by teaching them self-trust and building self-esteem. These individuals need to strengthen their boundaries to avoid the intrusion and domination of others. They need to trust in their intuition, develop a greater degree of confidence, enhance their personal power, and find a stronger sense of spiritual growth.
3. A Yang Wood nature predisposes individuals to manifest their internal insecurity through acting irritable and impatient. Such individuals are intolerant, rude, stubborn, and selfish, and tend to expand their egos without consideration for others. They are domineering, angry, aggressive, and generally known as



Figure 3.10. The Wood Constitution in Males and Females

overachievers; however, they are easily frustrated and depressed. Their self-esteem is elevated by acquiring higher political (influential) positions or bullying others.

Treatment for Yang Wood nature individuals should focus on cultivating a discipline of inner peace, following the Dao, to harmonize with life. In situations of conflict, they need to learn to relax, slow down, and act out of stillness. They need to surrender to a higher will, relying on their spiritual intuition and inner direction. They also need to learn to respect others.

THE FIRE CONSTITUTION

FIRE OUTER APPEARANCE

Fire constitution types usually have broad paravertebral muscles and well-proportioned shoulders, upper back, and thighs. They have small pointed heads, pointed chins, small hands, and feet, and curly, or no hair, on top of their head (Figure 3.11). By nature, they enjoy spring and summer but dislike autumn and winter. This preference is due to the vulnerability of the Fire constitution and its susceptibility to pathogenic invasion and disease during these time periods. Their dominant features include a strong circulatory system and a red facial color. Their note is "zhi."

FIRE PERSONALITY

The Fire personality can be divided into three subdivisions.

1. A Balanced Fire nature predisposes individuals to be trusting, open-minded, complacent, social, unconcerned about wealth, and fond of beauty. They love themselves and others, and are very expressive of their affection. They are calm, peaceful, happy, lively, spontaneous, funny, and fun to be with.
2. A Yin Fire nature predisposes individuals to be solemn and depressed. They tend to lack interest in life, and have a tendency to become isolated, feeling unloved and unlovable.

Treatment for Yin-Fire nature individuals requires teaching them how to store and conserve their energy, to use moderation in what



Figure 3.11. The Fire Constitution in Males and Females

they do, and to avoid extremes. They also need to engage in activities that create personal enjoyment, to find simple pleasures that awaken their affection, and to learn how to express their feelings, wants, and needs.

3. A Yang Fire nature predisposes individuals to be arrogant, ignorant, and troublesome. They are restless, excitable, and talk excessively. They always exaggerate and are overenthusiastic. They are socially and sexually overactive and seek every opportunity to assert themselves. They are foolish and display careless behavior. They are overconfident, slightly lazy, irresponsible, and less than truthful. They can be manic, get exhausted, then burnout and become suicidal (e.g., bipolar disorder).

   Treatment for Yang-Fire nature individuals requires teaching them to learn how to stop, slow down, and look for their contentment from within. They should balance their feelings of love with contemplation and wisdom, avoid over-enthusiasm, and allow their inner spirit to radiate through in a more sober way.

THE EARTH CONSTITUTION

EARTH OUTER APPEARANCE

Earth constitution types usually have a somewhat large body, large head, large belly, strong thighs, round face, and wide jaw (Figure 3.12). They are categorized as having excessive flesh, with upper and lower limbs mutually well-proportioned. By nature, they enjoy autumn and winter but dislike spring and summer. This preference is due to the vulnerability of the Earth constitution and its susceptibility to pathogenic invasion and disease during these time periods. Their dominant features include strong muscles and yellow facial color. Their note is "gong."

EARTH PERSONALITY

The Earth personality can be divided into three subdivisions.

1. A Balanced Earth nature predisposes individuals to lead quiet, stable, and peaceful lives, unconcerned about fame or wealth. They are always at ease, calm, generous, forgiving, sincere, and unambitious. They usu-



Figure 3.12. The Earth Constitution in Males and Females

ally have open minds and rarely live in fear, or make excessive demands. They have analytical minds and are logical and practical; they use sound reasoning to convince others of their opinions. They are quite adaptable to changing situations, and rarely use coercion to achieve power. They are kind and gentle with an earnest and well-mannered attitude. They are pleasant, sweet, sympathetic and caring, and are able to maintain boundaries.

2. A Yin Earth nature predisposes individuals to worry endlessly, becoming suspicious and self-centered. They think too much, with not enough follow-through action. Because they feel empty inside, they find it difficult to be nurturing to themselves and others.

   Treatment for Yin Earth nature individuals requires teaching them to learn how to let go of their inner feelings of worry and defensiveness. These individuals need to examine their assumptions, connect with their physical bodies, come out of their shells, and begin to live in the real world. They need to replace their negative thought patterns with positive affirmations, and realistically look at their true potential and abilities for powerful actions.

3. A Yang Earth nature predisposes individuals to cling to others; they are co-dependent, pushy, and possessive. Such individuals try to dominate in a passive-aggressive way while limiting the independence of others.

   Treatment for Yang Earth nature individuals consist of teaching them to develop their inner strength to control the fear, insecurity, and feelings of inner emptiness that make them want to hold on to others. They need to create and establish love as a source of security from within themselves. They need not depend on, or build their lives exclusively on, the praise or presence of others. They must learn to become emotionally independent.

THE METAL CONSTITUTION

METAL OUTER APPEARANCE

Metal constitution types usually have a triangular face with broad, square shoulders, a strong voice, and a strong, muscular build (Figure 3.13). By nature, they enjoy autumn and winter but dislike spring and summer. This preference is due to the vulnerability of the Metal constitution and its susceptibility to pathogenic invasion and disease during these time periods. Their dominant features include strong Lungs and white facial color. Their note is "shang."

METAL PERSONALITY

The Metal personality can be divided into three subdivisions.

1. A Balanced Metal nature predisposes individuals to process their grief, letting go of their past emotional baggage. They believe that they cannot be in the present without cleaning up and being released from their past. They are able to gain knowledge and wisdom by gathering and releasing their emotional bonds while learning and growing from each emotional attachment. They participate in life and form new bonds without fear of loss. They are also generous, just, and bright.

2. A Yin Metal nature predisposes individuals to have a difficult time creating lasting bonds because they are fearful of establishing new relationships due to past losses and emotional trauma. They avoid joining in with others and withdraw from active participation. Living in past remorse, they grieve over lost opportunities. They are also haughty and coldhearted. They are jealous, cunning, sneaky, and furtive. They become angry when they do not have things that others possess. Because they are covetous, they only obtain happiness by possessing certain objects.

   Treatment for Yin Metal nature individuals requires teaching them how to strengthen their physical body, as well as the energy of their Heart, Spleen, and Lower Dantian. They also need to strengthen their abilities to form close emotional bonds with people, reduce their fears of rejection and abandonment, and gain the strength and courage to let go of their past hurts. They need to come out from inside of themselves emotionally and experience the warmth and compassion of life.

3. A Yang Metal nature predisposes individuals



Figure 3.13. The Metal Constitution in Males and Females

to suppress their emotions and hold on to their grief. They are generally considered whiners and complainers, talking to others about their complaints in order to unload their grief. They use new relationships as an emotional bandage to avoid the unprocessed grief of their past relationships. They are also meticulous, independent, and strong-willed.

Treatment for Yang Metal nature individuals requires teaching them how to let go of the need to control and suppress their emotional feelings, and how to genuinely grieve over past wounds. They need to face the truth and be honest about their feelings, instead of selfishly using people and new relationships to cover up their grief. They also need to learn to be sympathetic with the pain and sorrows of others, and put their feelings of grief into perspective.

THE WATER CONSTITUTION

WATER OUTER APPEARANCE

Water constitution types usually have a big round face, head and body (Figure 3.14). They have a long upper back, and unbalanced or uneven physical features. They, by nature, enjoy autumn and winter but dislike spring and summer. This preference is due to the vulnerability of the Water constitution and its susceptibility to pathogenic invasion and disease during these time periods. Their dominant features include their digestive system and black or dark facial color. Their note is "yu."

WATER PERSONALITY

The Water personality can be divided into three subdivisions.

1. A Balanced Water nature predisposes individuals to be skilled negotiators, that are not discouraged by difficulty, and do not take foolish risks. They are sympathetic and loyal to their employer and friends. They have a clear perspective and are sensitive and intuitive. They are powerful, tender, and soft. They have a firm will and know their boundaries and limitations. They are known for their inner strength and strong faith in themselves.

2. A Yin Water nature predisposes individuals to lack spiritual, emotional, mental, and physical energy. They give up on life and surrender the control of their own destinies. They lack the determination to achieve their goals, do everything halfheartedly, and become easily discouraged by difficult challenges.

   Treatment for Yin Water nature individuals requires teaching them how to conserve and strengthen their energy by not attempting to do what's beyond their capacity. They should complete their projects, however, once they have started them, and not procrastinate or leave tasks unfinished. They need to find the strength to overcome their fear of failure by learning to take action through the completion of their goals.
3. A Yang Water nature predisposes individuals to be ambitious overachievers and to live under great stress. They lack consideration for others, and can be reckless and foolhardy. They can also be greedy, ruthless, and cold-blooded. Seemingly modest, they are actually insidious and sinister, concealing their true emotions by suppressing their fears. Because they fear loss of control, their safety lies in dominating others. They only perform duties that are self-serving and blame others for their problems.

   Treatment for Yang Water nature individuals requires that they learn how to act from inner stillness and gain strength and courage from their inner true self. They also need to emotionally and physically slow down, and to balance their activities with rest. They need to learn to gain consideration for themselves and others, as well as to open up their heart and begin to love.

COMBINED CONSTITUTIONS

In ancient China, The Yellow Emperor's physician Shao Shi taught that the Five Elemental constitutions consist of Five Elemental forms, which can be further divided into five additional shapes depending on the strength or development of the individual's Jing, Qi, and Blood. After establishing the patient's physique (Wood, Fire, Earth,



Figure 3.14. The Water Constitution in Males and Females

Metal, or Water), the patient is then classified in terms of five separate colors, and differentiated according to the five prenatal (Heavenly) notes. This system recognizes 25 constitutional types.

The Five Elemental Constitutions are therefore, guidelines for the Qigong doctor to evaluate the patient. These guidelines are not fixed, as the doctor is most likely to encounter combinations of two or more of these elements within one person.

When two constitutions combine in an individual, the combination may be congenital or acquired. The Qigong doctor must evaluate the patient, differentiating between his or her congenital and acquired tissue formations.

A woman who has large hips (Water) and small chest and shoulders (Wood), for example, probably inherited this structure from her parents. This woman's physical structure and personality would then be considered a combination of both Water and Wood (depending on which internal organ characteristic dominates).

A female patient who swims, on the other hand, may be congenitally Wood but may have developed a dominant Metal upper physique through years of physical training. If, through intense physical activity, someone acquires a Metal physique, he or she may also acquire a Metal personality, depending again on his or her psychological format, which is rooted within the internal organs.

The external physical structure serves as a visual guide to the interaction and balance of the internal organs.

PERSONALITY CONSTITUTIONS OF THE EIGHT EXTRAORDINARY VESSELS

Another system of identifying personality traits is practised by observing the four personality constitutions of the patient's Eight Extraordinary Vessels.

Through observation and inspection of the patient's personality and overall energetic and emotional demeanor, the Qigong doctor can further determine which organ and organ system, is Deficient or has an Excess condition and set up a treatment plan.

To begin, the Qigong doctor will first observe the patient's dominant Yin or Yang emotional characteristics and determine which of the Eight Extraordinary Vessels are governing his or her present state of feelings. These personality traits may appear in different combinations, or oscillate from one type of characteristic to another, due to the crossover of acquired and congenital organ energy. This crossover can change with the patient's age (maturation) or situation (environment).

THE PATHOLOGICAL PERSONALITY TYPE OF THE GOVERNING AND YANG HEEL VESSELS

The Governing and Yang Heel Extraordinary Vessels are located on the back and lateral sides of the body and affect the Bladder, Stomach, and Gall Bladder Channels. To "open" and increase the flow of energy within these channels, the Qigong doctor stimulates the patient's SI-3 and Bl-62 points simultaneously (see Chapter 8).

The pathological personality types of the Governing and Yang Heel Vessels are divided into Yin and Yang emotional characteristics. These characteristics are as follows.

1. Patients with Deficient Qi in the Governing and Yang Heel Vessels tend to be weak-willed and spineless. They tend to be overly submissive, and easily give up their personal power. They lack determination, courage, clarity, and inner strength, and have no control over their lives. They participate as little as possible in life for fear of failure.
2. Patients with Excess Qi in the Governing and Yang Heel Vessels tend to be tense, overpressured, stiff, rigid, inflexible, stubborn, and awkward. They are narrow-minded and overcontrolling. Fearful of letting go, they overcompensate and attempt to restrict reality.

THE PATHOLOGICAL PERSONALITY TYPE OF THE CONCEPTION AND YIN HEEL VESSELS

The Conception and Yin Heel Extraordinary Vessels are located on the front and inside of the body. They affect the Lung and Kidney Channels, which in turn affect the Kidneys, Lungs, and Heart organs. To open these channels, the Qigong doctor stimulates the patient's Lu-7 and Kd-6 points simultaneously. These character diagnoses are as follows.

Symbol of Li - Fire ☲

a. Focus on the Li Yang-Yin-Yang trigram. Repeat it several times using your fingers on your mideyebrow. Eyes look up to the forehead and picture a flame burning and chant Li, Li, Li repeatedly. Then chant the Yang-Yin-Yang. Picture the trigram right on your face and expand it very far away. See a fire burning, expanding warmth. Let the energy stay on your forehead as a bright red light. Bring it down to the Li in the Pakua in your abdomen and feel a burning sensation in that area.

b. **Yang Expand:** Do as before.

c. **Yin Contract:** Do as before.

d. **Yang Expand:** Do as before.





Eyes look up
to the forehead.

Fig. 5.52 *Li on Forehead*

Symbol of Chen - Thunder ☳

a. Focus on Chen, Yang, Yin, Yin. Chant this symbol as a throat and nose sound repeatedly and then chant Yang-Yin-Yin. The eyes look to the left temple bone. Picture the symbol in front of you, expand it very far away to the power of the lightning and thunder. Let the energy come to you, feel the tingling on your left temple bone and move this energy sensation down to the left side of the abdominal pakua. Be aware of Kan, Li, Chen. Visualize them very clearly.

b. **Yang Expand:** Do as before.

c. **Yin Contract:** Do as before.

d. **Yin Contract:** Do as before.

1. Patients with Deficient Qi in the Conception and Yin Heel Vessels tend to be weak and depressed. They live in the past, lack interest in life, have no ambition, and also lack interest in sex. It is hard for them to form new relationships because they fear forming emotional bonds due to past losses, failures, and emotional traumas. They constantly daydream and live in their own world of past memories.
2. Patients with Excess Qi in the in the Conception and Yin Heel Vessels tend to participate in life, but hold on to, and suppress, their grief. They fail to let go of emotional attachments and fear being alone. The female patients usually develop Qi stagnations resulting in breast cysts, tumors, and cancer, as well as uterine fibroids and cancer.

THE PATHOLOGICAL PERSONALITY TYPE OF THE BELT AND YANG LINKING VESSELS

The Belt and Yang Linking Extraordinary Vessels are located around the waist and on the outside of the body. They affect the Gall Bladder and Triple Burner Channels, which in turn, affect the Kidneys, Liver, and Gall Bladder organs. To open these channels, the Qigong doctor stimulates the patient's GB-41 and TB-5 points simultaneously. These character diagnoses are as follows.

1. Patients with Deficient Qi in the Belt and Yang Linking Vessels are considered weak, indecisive, and unproductive. They fear criticism and are touchy, snappy, irritable, and hypersensitive. They have low self-esteem and also lack interest in sex.
2. Patients with Excess Qi in the in the Belt and Yang Linking Vessels are aggressive, angry, resentful, bitter, and vindictive. They are also opinionated, inflexible, intolerant, domineering, selfish, and frustrated, with a sex life based on anger or rage.

THE PATHOLOGICAL PERSONALITY TYPE OF THE THRUSTING AND YIN LINKING VESSELS

The Thrusting and Yin Linking Extraordinary Vessels are located within the center of the body (internally) and on the medial and anterior aspect of the body (externally). They affect the Kidney and Stomach Channels, which in turn, affect the Kidneys, Spleen, and Heart organs. To open these channels, the Qigong doctor stimulates the patient's Sp-4 and Pc-6 points simultaneously. These character diagnoses are as follows.

1. Patients with Deficient Thrusting and Yin Linking Vessels are physically and emotionally weak. They quickly become exhausted and depressed. They easily have their feelings hurt and take a long time to recover from emotional upsets. Their internal world of emotional existence is made up of fear, anxiety, worry, and tension. They do not connect well with the outside world or gain much pleasure from life or relationships.
2. Patients with an Excess in the Thrusting and Yin Linking Vessels tend to participate in life, but have difficulty expressing their affections and communicating their needs in relationships. They are inclined to have stagnant Qi and Blood in their chests, epigastrium, or uterus areas due to fear, anxiety, worry, and sorrow. In their personal relationships, they fear loss of control and cannot make a commitment or a deep emotional connection with others. They also fear surrendering and letting go in their love and sexual relationships.

THE YAO IMAGE AND PHYSICAL ANATOMY

Sometimes because of surgery, congenital deformity, or traumas, it is not possible, nor is it recommended, to directly treat certain areas of the patient's body. The Qigong doctor must then choose an indirect method of treatment to ensure better results. One such method available to the doctor utilizes the understanding of the Yao image and the patient's physical anatomy. In order to better comprehend the complexity of this diagnostic and treatment modality, the Qigong doctor must first understand the energetic origin of the Yao images.

All matter is composed of different proportions of Yin and Yang energy. Within the Void (infinite space or Wuji) both Yin and Yang energy gather or disperse to balance the forces of nature. This interaction causes the Yin and Yang energies



Figure 3.15. This diagram shows a hexagram, composed of an upper and lower trigram. In this particular example, the upper trigram is all Yin lines (symbolized by broken lines), the lower all Yang (symbolized by solid lines).

to develop and transform themselves into four phases of energetic powers or stages: Great Yin, Small Yin, Great Yang, and Small Yang. These four phases can be explained as follows.

1. Great Yin (Tai Yin), is affiliated with midnight and the new-moon phase. Modern physicists associate the Great Yin with a weak nuclear force.
2. Small Yin (Shao Yin), is affiliated with the sunset and the waning-moon phase. Modern physicists associate the Lesser Yin with a heavy force, and gravity.
3. Great Yang (Tai Yang), is affiliated with high noon and the full-moon phase. Modern physicists associate the Strong Yang with a strong nuclear force.
4. Small Yang (Shao Yang), is affiliated with the sunrise and the waxing-moon phase. Modern physicists associate the Lesser Yang with a light force and electromagnetism.

These four solar and lunar energetic phases transform themselves into the energies of the eight foundational trigrams. These trigrams further combine to form sixty-four hexagrams, and manifest as the ancient binary system known as the Yi Jing (I Ching). The formation and pattern of these energetic powers or stages vary according to the composition of Yin and Yang, and can be expressed through the energetic symbols of the Yao.

A Yao is a line that represents either Yin or Yang energy. The lines fall into two categories:

- The negative Yao is symbolized by broken lines (Yin energy).
- The positive Yao is symbolized by solid lines (Yang energy).

When these lines are stacked in combinations of three, they form what are known as trigrams (a group of three Yao lines). When pairs of trigrams are joined, hexagrams (six lines) are formed. The lines are arranged from bottom to top, with the first Yao being on the bottom (Figure 3.15).

The Yao trigrams and their relationship to the body's physical and energetic structure can be utilized by the Qigong doctor for diagnosis and treatment. The doctor applies the Yao image as a template and arranges its pattern alongside the physical form of the patient's body. This arrangement of Yao images is designed by the doctor to assist him or her in recognizing the physical and energetic imbalances within the patient's body. This type of physical Yao image diagnosis has been used in China for centuries.

Knowing that each different region of the human body corresponds to one of the six Yaos in the hexagram, as well as a different aspect of Qi, the ancient masters explained the energetic Yao and physical body interaction as follows.

1. The two lowest Yaos align with the feet and legs and correspond to the body's interaction with the Earth's energy.
   a. The 1st Yao extends from the patient's feet, ankles, and shins, to the knees.
   b. The 2nd Yao extends from the knees to the upper thighs.
2. The middle two Yaos align with the lower and upper abdominal regions, and correspond to the body's interaction with human energy, or "Man's energy" (emotional responses).
   a. The 3rd Yao extends from the perineum to the navel.
   b. The 4th Yao extends from the navel to the xiphoid process in the diaphragm.
3. The upper two Yaos align with the upper chest, neck and head, and correspond to the body's interaction with Heaven's energy.
   a. The 5th Yao extends from the xiphoid process of the diaphragm to the top of the manubrium, at the base of the throat.



- The top or 6th Yao is from the neck to the top of the head. (Heaven)
- The 5th Yao is from the diaphragm to the neck. (Heaven)
- The 4th Yao is from the navel to the diaphragm. (Man)
- The 3rd Yao is the lower perineum to the navel. (Man)
- The 2nd Yao is from the knee to the top of the thigh. (Earth)
- The bottom or 1st Yao is from the foot to the knee. (Earth)
- The Categorization of the arms are as follows: From the fingers to the elbow represents the Bottom or 1st Yao; From the elbows to the base of the shoulder represents the 2nd Yao; From the base to the top of the shoulder represents the 3nd Yao.

Figure 3.16. Yao Image and the Human Body

b. The 6th Yao extends from the manubrium, at the base of the throat, to the top of the head.

The doctor further divides the patient's body into six upper and lower Yaos, to determine the dominant energetic and emotional patterns (where the patient's Qi is gathering, collecting, and stagnating). Through observation and study, the Qigong doctor is able to determine the energetic association the patient has with the natural environment. This diagnosis is achieved by observing the body's relationship to the three energetic Yao divisions of Heaven, Earth, and Man (Figure 3.16). When observing the body, for example, if the upper Yao is out of harmony with the patient's middle and lower Yaos, the patient's energetic balance may be compromised, and he or she may experience a spiritual disconnection with his or her body. This can result in either a Yang condition (heaviness, restlessness) due to an Excess spiritual "Heaven" state, or a Yin condition (tired, dizziness) due to a Deficient spiritual "Heaven" state.

In addition to diagnosing the hexagram for the body's Yin and Yang relationship to Heaven, Earth, and Man, the ancient Chinese Qigong masters also studied two other hexagrams for clinical evaluation. These hexagrams were known as the Upper and Lower Hexagrams.

UPPER AND LOWER HEXAGRAMS

In the Ming Dynasty (1368-1644), Tang Rongchuan stated in his book *Detailed Explanations of Application of the Book of Changes to Medicine,* "In the clinical environment, the body may be divided into two different sets of hexagram constructions [the upper and the lower hexagram partition] for the purpose of making a diagnosis, detecting Qi, and for performing Qigong therapeutic treatments." This relationship of Yao positioning is suitable to both the channel system and the nervous system.

Physical disorders located within these hexagrams are generally expressed as symptoms manifesting in the extremities. If stagnant Qi or other abnormal conditions occur in any particular part of the body, an imbalance of both Internal and External Qi may be detected in either that specific area of the body or its corresponding area.

The ancient Qigong masters used the body's hexagrams to explain the etiology, pathology, clinical manifestations, and treatment principles of disease.

The body's upper torso, arms, neck, and head are divided into what is known as the upper hexagram partitions, while the body's lower limbs and torso are divided into the lower hexagram partitions. The six Yao of the upper and lower hexagram partitions interlock at the chest and abdomen. By using these sets of hexagrams, the Qigong doctor has a template or guiding pattern with which to understand the patient's body.

The Upper Hexagram Construction

The Upper Hexagrams range from the base of the lower perineum to the top of the patient's head. These six Yaos are organized as follows.

1. The 1st or bottom Yao encompasses the pubic symphysis to the navel. Reproductive, digestive, and urinary tract diseases are ascribed to this area.
2. The 2nd Yao encompasses the navel to the xiphoid process. Malfunctions in digestion, elimination and the transportation of nutrients are assigned to this area, as well as diseases of the Kidneys, adrenal glands, Liver, Spleen and pancreas.
3. The 3rd Yao encompasses the xiphoid process to the supraclavicular notches. Respiratory and circulatory diseases are ascribed to this area.
4. The 4th Yao encompasses the supraclavicular notch to the tip of the nose. Teeth, jaw, and thyroid diseases are ascribed to this area.
5. The 5th Yao encompasses the tip of the nose to the eyebrow. Sinus problems and headaches, as well as ear, nose, and eye diseases are manifest in this area.
6. The 6th or top Yao encompasses the eyebrows to the top of the head. Several types of headaches, brain tumors, and upper cranial dysfunctions are ascribed to this area.

The Lower Hexagram Construction

The Lower Hexagrams range from the bottom of the patient's feet to the base of the patient's throat. These six Yaos are organized as follows:

1. The 1st or bottom Yao encompasses the bottom of each foot to the ankle. Foot, toe and ankle dysfunctions are ascribed to this area.
2. The 2nd Yao encompasses the ankles to the knees. Shinsplints and calf and ankle dysfunctions are ascribed to this area.
3. The 3rd Yao encompasses the knees to the pubic symphysis. Thigh, knee, and quadriceps dysfunctions are ascribed to this area.
4. The 4th Yao encompasses the pubic symphysis to the navel. Reproductive, digestive, and urinary tract diseases are ascribed to this area.
5. The 5th Yao encompasses the navel to the xiphoid process. Digestion, elimination, and the transportation of nutrients, as well as diseases of the Kidneys, adrenal glands, Liver, Spleen and pancreas are ascribed to this area.
6. The 6th or top Yao encompasses the xiphoid process to the supraclavicular notches at the base of the throat. Respiratory and circulatory diseases are ascribed to this area.



The diagram at left depicts the correspondence of the yaos of the body to the yaos of the hands and feet.

6 The second joint of the toes or fingers pertains to the top Yao and the energy of Heaven.

5 The first joint of the toes or fingers pertains to the 5th Yao and the energy of Heaven.

4 The area below the first joint of the toes or fingers pertains to the 4th Yao and the energy of Man.

3 The ball of the foot or upper palm pertains to the 3rd Yao and the energy of Man.

2 The instep on the midpalm with the thumb pertains to the 2nd Yao and the energy of Earth.

1 The heel or lower palm pertains to the bottom Yao and the energy of Earth.

Figure 3.17. The Therapeutic Use of the Yaos and the Upper and Lower Hexagrams

THERAPEUTIC USE OF THE YAOS

The entire body can be treated by focusing on one small area. When Excess, Deficient, or stagnant Qi occurs in one part of the body, the imbalance of Internal and External Qi is detectable in that area or its corresponding region on one of the body's extremities. This ancient Chinese modality of treatment is popularly called reflexology in the West.

The Yao images can be superimposed onto the patient's body, and the patient diagnosed according to the energetic symptoms expressed through either the patient's extremities (the hands, forearms and arms; or the feet, shins, and thighs), or the six divisions located on the patient's torso and head. A Yao hexagram can additionally be visualized on specific locations of the patient's body such as the face, nose, ears, hand or foot for diagnosis. The base of the palm's heel, for example, corresponds to the lower abdominal area and reproductive organs, which relate to the 1st, or lower, Yao in the hexagram of the hands. These six Yao areas of the hand provide a basis for diagnosis, for treatment of certain diseases, and even for perception and prediction of certain future diseases (Figure 3.17).

As an example of how the Qigong doctor can use the six Yaos of the body for emitting Qi therapy, consider the following situation: An elderly patient with a problem in his prostate area visits the Qigong doctor. The prostate is located in the lower abdominal area, which is located in the 1st Yao of the upper hexagram. Since the six Yao positions can be transferred to the hands, feet, etc., the doctor knows that this particular Yao is congruent to the 1st Yao of the foot. Therefore, as an energetic entry point into the patient's prostate area, the doctor may focus his or her attention on a specific area on the foot.

Dividing the foot into six Yaos, the doctor knows that the 1st Yao of the foot is the heel area. In order to treat the prostate gland, the doctor will



6 The fruit or flower of the herb pertains to the top Yao and the energy of Heaven.

5 The leaf of the herb pertains to the 5th Yao and the energy of Heaven.

4 The branch of the herb pertains to the 4th Yao and the energy of Man.

3 The upper stem of the herb pertains to the 3rd Yao and the energy of Man.

2 The stalk of the herb pertains to the 2nd Yao and the energy of Earth.

1 The root of the herb pertains to the bottom Yao and the energy of Earth.

Figure 3.18. The Yao Image Applied to Plants

focus his or her treatment on the patient's heel and ankle area. Alternatively, the doctor could also have chosen the 1st Yao area of the hand, which is considered the 1st Yao position of the arm. The 1st Yao of the hand corresponds to the prostate and urogenital area.

HERBS AND THE YAOS

Affirming the ancient Chinese belief that the energy of Heaven, Earth, and Man combine as "one," and exist in the same world of energetic dynamics, herbs are also structured and prescribed in accordance with the six Yao hexagram concept. With plants, the following correspondences apply (Figure 3.18):

1. The roots correspond to the bottom or 1st Yao.
2. The stalk corresponds to the 2nd Yao.
3. The upper stem corresponds to the 3rd Yao.
4. The branches correspond to the 4th Yao.
5. The leaves correspond to the 5th Yao.
6. The flowers and fruit of the plant correspond to the top or 6th Yao.

When plants are utilized as a medicine, the part of the plant corresponding to the number and position of the Yao may manifest its energetic properties, affecting the ascending, descending, floating, or sinking action of the patient's Qi. The achyranthes root (Niu Xi), for example, corresponds to the bottom Yao, and leads healing Qi downward, to heal the patient's knees and joints; whereas the chrysanthemum flower (Ju Hua) corresponds to the top Yao, and leads healing Qi up into the patient's head and eyes.

IDENTIFYING INTROVERTED AND EXTROVERTED STRUCTURES

Qi flows through the matrix of the connective tissue and adapts to the postural and structural demands of the body by changing the density and direction of the body's connective tissues and inner fasciae. A postural habit will create an imprint or tissue memory in the supporting connective tissue, as well as an energetic memory in the supporting field of Qi. These imprints result in introverted as well as extroverted postural structures.

Each introverted (Yin) and extroverted (Yang) postural structure has a predictable impact on the


Head held off-center
6th yao
Shoulders sunken and forward
5th yao
Wide back
Narrow chest
4th yao
Pelvis tilted back
3rd yao
Genitals retracted
2nd yao
Thighs bowed
bottom yao

Figure 3.19. The Introverted Structure


6th yao
Head held level
Shoulders Extended back
5th yao
Narrow back
Wide chest
4th yao
Pelvis tilted forward
3rd yao
Genitals extended
2nd yao
Thighs turned inward
bottom yao

Figure 3.20. The Extroverted Structure

myofascial webbing, as well as a natural emotional response. Emotions respond to changes in breathing patterns and vice versa. Both the prevalent breathing pattern and the patient's general mood affect the body's posture and eventually the body's structure. All chronic stress creates postural imprinting or tissue memory, and a corresponding energetic memory in the supporting field of Qi.

INTROVERTED STRUCTURE

When observing the introverted type of structure, the doctor will notice that the back (Yang) area of the patient is expanded, and the muscle structure is usually well-developed. The front of the body (Yin), especially around the chest and Heart area, is retracted, resulting in a narrow chest. The patient's head is generally held off-center, shoulders are sunken and forward, and the pelvis is tilted back, with the genitals retracted (anterior tilt). This condition is commonly referred to as "extended Yang" and "retracted Yin" of the upper torso (Figure 3.19).

EXTROVERTED STRUCTURE

When observing the extroverted type of structure, the doctor will notice that the back (Yang) area of the patient is retracted, while the front of the body (Yin) is expanded and overly exposed. The head is usually held vertically, the shoulders are extended back (military posture), the chest is wide, and the pelvis is tilted forward, with genitals extended (posterior tilt). This condition is commonly referred to as "extended Yin" and "retracted Yang" of the upper back (Figure 3.20).

COMBINED STRUCTURAL FORMATIONS

As with the Five Elemental Constitutions, the introverted and extroverted structures are guidelines for the Qigong doctor to evaluate the patient. These guidelines are not fixed, as the doctor is most likely to encounter combinations of both introverted and extroverted structures within one person.

When two structures combine in an individual, the combination may be due to a congenital or acquired formation. The Qigong doctor must evaluate and assess the patient, differentiating between his or her congenital and acquired tissue formations.

CONGENITAL AND ACQUIRED CELLULAR PATTERNS

The Qigong doctor evaluates the physical condition according to the congenital or acquired patterns manifested within the patient's tissues. The doctor may ask questions to determine if the condition was acquired through exposure to environmental pathogens, diet, trauma, occupation, or inherited. This information aids the Qigong doctor in understanding and assisting the patient in reprogramming any congenital or acquired cellular patterns, as well as internal disease functions.

1. Congenital Cellular Patterns and disease predispositions are locked within the patient's congenital Jing and can be released like a biological time bomb. This is a similar concept to the Western medical concept of genetic congenital disease. The goal of the Qigong doctor is to alter (if possible) the Toxic Qi patterns and help the patient's body recognize that the formation of the disease is a mistake. In order to reprogram these patterns, the Qigong doctor often assists the patient in using guided meditations that employ vivid imagination, colorful visualizations, and positive affirmations. These images are used to encapsulate the disease and return it to the divine light. While in the presence of the divine light, the Toxic Qi (Xie Qi) will be energetically transformed and recycled back to the patient as healing energy. Patients with a direct family history of cancer, for example, can benefit from this type of medical Qigong imagery.
2. Acquired Cellular Patterns and disease functions arise from either external exposure to pathogens, or the suppression of extreme emotions. The goal of the Qigong doctor is to first assist the patient in discovering the origin of the disease. The next step is to teach the patient to alter the toxic patterns and help the patient's body recognize that the development of the disease is a mistake. In order to reprogram these patterns, the Qigong doctor will assist the patient in learning meditations that employ healing mental imagery, colorful visualizations, and positive affirmation. The patient must encapsulate the disease and return it to the divine light, to be energetically transformed and recycled. A patient who has been experiencing severe headaches, for example, could benefit from this kind of treatment given that most headaches are stress related.

SUMMARY

Through the observation of the patient's physical and structural development, a clear understanding can be obtained as to the strength and weakness of the patient's internal organs and immune system.

The four patterns of physical development and structural formation (The Five Elemental Constitutions, The Yao Hexagram Formations, The Yin or Yang Structures, and The Congenital and Acquired Cellular Patterns) are determined as follows.

1. The doctor first begins to diagnose the patient's physical body according to the Five Elemental Constitutions and the dominant element. This helps the doctor to understand the dominant condition of the patient's internal organs.
2. The doctor further divides the patient's body into six upper and lower Yaos, to determine the dominant energetic and emotional patterns (where the patient's Qi is gathering, collecting, and stagnating).
3. Next, the doctor evaluates the patient's external structure according to his or her body's Yin and Yang characteristics, to understand whether the patient has a dominant introverted or extroverted physique.
4. Finally, the Qigong doctor determines whether the patient's condition is congenital, acquired, or a combination of both. This information helps the doctor to understand the innate cellular patterns that dominate the patient's physique.

CHAPTER 4
THE FIVE ENERGIES OF THE HUMAN BODY

The study of various forms of energy and their transformations from one form to another have led to one of the greatest generalizations in physics -- the Law of Conservation of Energy, which states, "Energy cannot be created or destroyed. It may be transformed from one form into another, but the total amount of energy never changes."

Physics defines four types of energy: mechanical, electromagnetic, chemical, and thermal. All four types of energy are related to and convert from one another. Electricity, for example, can be converted into sound, light, mechanical energy and into heat. Sound, light, mechanical energy and heat can all be reconverted into electricity.

Western Science is still for the most part, founded on the principles of Newtonion Physics, that views energy as an impersonal and inanimate force. The Traditional Chinese view of energy is much more akin to the theories of Quantum Physics. Both Chinese energetic theories and Quantum Physics hypothesize that energy cannot be studied without taking into account the mind's influence over it. Furthermore, energetic behavior cannot be studied independently of matter.

From a medical Qigong perspective, the entire human body is suffused with energy, which converts within the human organism. Light energy, for example, is absorbed, stored and converted into the various energies of the body, the same way that plants convert absorbed and stored light into chemical energy.

The human body possesses five energies which resonate within the very core of one's being. Sound, light, magnetic fields, heat, and electricity envelop and permeate our very existence; these energies sustain, govern, control, and determine our psychology as well as our physiology. In Medical Qigong therapy, these energies are considered the spiritual reality that governs the physical reality. These energies are observed in both diagnosis and treatment of illness. Research in China confirms the fact that the body emits sound, light, magnetic energy, electricity, and heat.

SOUND ENERGY RESONANCES

When the body experiences any type of sound, the cell tissues respond to the tone frequency and have either a negative or positive automatic response. The human body both receives and generates sound energy. These subtle sounds resonate from three distinct physical energetic actions. The following subtle sounds are natural tones that resonate as a result of three physical actions.

1. Breathing creates respiratory sound resonances that follow the breath in and out of the lungs mouth, and nose.

2. Muscle movements create somatic and visceral sound resonances that include the clicking sound of the joints, beating of the Heart, gurgling of the Stomach and intestines, etc.

3. Qi activities can produce energetic sound resonances (i.e., when Liver Yang, Liver Fire, or Liver Wind rise, a high-pitched tone is heard in the ears. When the Kidney Yin is Deficient, this sound is like rushing wind, etc.).

SOUND THERAPY THROUGH EMITTED QI

As sound waves vibrate through the body, crystalline structures within the tissues transform the vibration into pulsed currents. These currents are then conducted to the various corresponding organs and glands, depending on the frequency and amplitude of the incoming wave signal. This tissue transformation (due to wave vibrations) automatically changes the function and flow of energy in the body. Thus sound vibrations have a profound effect on both human psychology and physiology. Sound or tone resonances, have been



Fig. 5.53 *Chen on Forehead*



Eyes look to left temple bone

Symbol of Tui - Lake ☱

a. Focus on Tui, Yang, Yang, Yin. Chant Tui repeatedly with a nose sound that is vibrating in the nose. Then chant Yang-Yang-Yin; eyes look to the right temple bone. Picture the symbol on your right temple bone and expand it very far away to the power of the lake, rain and metal element. It is a condensing power. Move it down to the right of the abdominal pakua.

Combine the four symbols together with the Tai Chi symbol. Feel the Tai Chi symbol spiraling inside your head and feel the center of your abdomen nice and warm like a fire burning inside you.

b. **Yang Expand:** Do as before.

c. **Yang Expand:** Do as before.

d. **Yin Contract:** Do as before.



Eyes look to right temple bone.



Fig. 5.54 *Tui on Forehead*

used for centuries as an effective healing tool and are currently used as an adjunct to modern Qigong Medicine.

For centuries in China, patients have used healing sound therapy to resonate certain parts of the body, stimulating the flow of Blood and Qi to and from specific internal organs to cure disease. These healing sounds specifically relate to the Five Agents and the Five Elemental aspects of the patient's internal organs (see Chapter 2). According to the Five Elements' Cycle, each of the Five Elements has a note:

- Gong - C = Earth
- Shang - D = Metal
- Jue - E = Wood
- Zhi - G = Fire
- Yu - A = Water

The Qigong doctor can project resonant sound vibrations by first focusing on all three Dantians at the center of the Taiji Pole. This focused concentration is used first to vibrate the doctor's specific internal organs and then to treat the patient. The Qigong doctor can use vibrating sound therapy by:

1. Audibly speaking the healing sounds to fill the Qigong doctor's energetic field with healing sound vibration. This energetic field of sound is then projected onto his or her patient. Audible sound resonation is considered a Jing to Qi level energy projection, and is generally used when the patient is armored and not energy sensitive.
2. Inaudibly speaking the healing sounds and projecting these mental vibrations into the patient. In this case, the Qigong doctor will begin by internally focusing his or her mind on the healing sound. As this internal sound fills the Qigong doctor's energetic field, it is then emitted into the patient's body. To increase the intensity of energy sound projection, the doctor needs only to increase the mind's intention and the pressure of his or her exhalation. Inaudible sound resonation is considered a Qi to Shen level energy projection, and is generally used when the patient is energy sensitive.
3. Both the doctor and patient simultaneously resonate the sound to enhance the synchronization of both their energy fields. As the Qigong doctor resonates his or her own internal organs, both the doctor and patient can modulate the sound and energy patterns as needed.

THREE MODALITIES OF SOUND THERAPY

The resonant sounds produced by Qigong doctors are effective because the patients' energetic matrix is sensitive to the sound resonances. The modulated, yet unpredictable, nature of sound pulsation affects the vibrational structures which shape and maintain the patient's physical structure. Once the patient's vibrational structures have been disturbed, their body must immediately begin its reconstructive process, thereby creating new energetic patterns to restructure and heal the tissues.

There are three modalities used for sound therapy:

1. Characteristic Sound Therapy refers to the sound from musical instruments (flute, guitar, piano, drum, etc.) and their effect on the subconscious mind. This type of musical energy creates an emotional, physical, and spiritual release of energy within the listener.
2. Extraordinary Sound Therapy refers to the vocal resonances used in silent chanting, prayer and singing. Such techniques include the Daoist six-word healing sound method, Zhuang Zi's breath listening method, Lao Zi's sound-voice method, etc. This type of therapy uses the patients' energy to produce the sound and inner vision to direct the vibration within the body. It is also practised in conjunction with breathing techniques that are guided by the Yuan Shen (the intuitive consciousness of the spirit). All of these techniques are combined to achieve physiological and psychological healing.
3. Infrasonic Sound Therapy refers to the low frequency sound waves emitted from the hands of Qigong doctors. These chaotic, low frequency sound waves, inaudible to the human ears, are naturally produced by the hands

of experienced Qigong doctors when emitting Qi. This infrasonic sound resonance affects the central nervous system, changing the body's neurophysiological functions. Extensive research performed by Richard H. Lee of China Healthways Institute in Los Angeles, California, as well as research performed by the Beijing College of Traditional Chinese Medicine, and the Department of Natural Science in Beijing China, confirms that all humans have a very high degree of acoustic activity in the subsonic range below 20 Hertz (infrasonic). This subsonic activity is similar to the alpha rhythm of an EEG (see Appendix #2).

Qigong doctors may combine the characteristic, extraordinary, and infrasonic sound therapies into one treatment modality to facilitate a deeper and more thorough transformation within their patients. The choice of sound prescriptions vary according to each patient's cultural upbringing, religious beliefs, emotional temperament, and comprehension of energetic healing modalities.

Sound therapy can be prescribed to relieve a patient's feelings of uneasiness or extreme depression. Music, for example, has always been acknowledged as a powerful medium for emotional enhancement. Sounds and tones stimulate the cerebral centers creating a wide range of results from enhancement of memory retention, to facilitating certain emotions, and creative inspirations.

Music therapy specifically created for the harmonizing the Five Elements within the Yin and Yang organs is also used in conjunction with Feng Shui training to regulate any imbalances of the body and mind stemming from the changes of seasons. During autumn, for example, when dryness is prevalent and there is a transition from warm to cool, music can help to stabilize the body's response to these external conditions.

WESTERN SOUND THERAPY

Sound therapy is actively being used in Western medicine. The following are examples of current clinical modalities:

- music therapy for postoperative healing,
- ultrasound therapy for sore muscles and back injuries, and
- shock-wave lithotripsy therapy for kidney stones and calcified gallstones.

LIGHT ENERGY

All matter produces, radiates, transports, or transmits light, and therefore has properties of color vibration. Matter and light are fundamentally inseparable. Matter can be considered a condensation of photons. Its transformation can be viewed as a result of light interacting with atoms and molecules. All life on Earth, whether plant, animal, or human, is dependent upon light and its miraculous qualities for existence.

All living cells emit units of light called "biophotons." Biophoton emissions radiate from the internal organs, as well as the body's surface tissues, to create the body's auric field.

This interaction of light on the body's tissues and within the body's internal organs has a profound healing effect, especially when activated by the Qi emission from a Qigong doctor. When muscles or nerves are activated through medical Qigong therapy and / or exercises, the intensity of the biophoton emission increases. Studies performed on the healing potential of light and color therapies demonstrate that it is clinically effective. Like sound resonances, light therapy is also being researched further as an adjunct to modern clinical medicine.

The body both absorbs and projects light energy. The divine light that enters at the time of conception continues to reside in our Taiji Pole throughout our lives. This light responds and reacts to the doctor's emitted therapeutic light energy. Emitted light and color resonance are absorbed into the patient's body, causing the energies of Heaven and Earth to fuse inside the tissues; this facilitates the healing process.

In Traditional Chinese Medicine, the early diagrams illustrating the body's internal organs, channels, routes of Body Fluids, and arteries were called Charts of the Hall of Light. These detailed maps of Qi and Blood flow illustrated the energetic organs, as well as the body's Jing and Shen (which are rooted in the Blood). The Shen flows inside of the body, transforming into light and radiating from inside of the tissues outward. The



Figure 4.1. Light resonates within the body's Taiji Pole. From the body's Yang Governing Vessel flows a sea of electropositive energy. From the body's Yin Conception Vessel flows a sea of electronegative energy.

light radiating from the physical body spontaneously interacts with the mental, emotional, and spiritual light energy released from other beings.

Light energy can also be accumulated in the storage chambers of the Three Dantians. The Upper Dantian, is called the "peak of Yang energy," and is considered electropositive; it is the doorway to the chamber of Heavenly or divine light. The Lower Dantian, is called the "peak of Yin energy," and is considered electronegative, and the direct root to the Earth.

In time, with Qigong training, the postnatal Heat circulating up the Governing (Yang) and down the Conception (Yin) Vessels can awaken the Prenatal Qi stored in the brain, causing it to unite with the body's nervous system. This is considered a full integration of Yin and Yang energy and manifests as a shimmering white light glowing in the center of the Upper Dantian.

White light is stored in and released from the Upper Dantian, where the spiritual energy is stored. Once white light energy manifests, it should be drawn down the Taiji Pole into the center of the Lower Dantian. By using inner vision to focus the eyes on the center core of the body, the Qigong doctor can concentrate on the white light energy vibration and fuse this energy into one column of light, stemming from the Upper to the Lower Dantian. When the Microcosmic Orbit is completed (i.e., when the Governing and Conception Vessels are energetically fused), the first center column of light can be accessed via the body's five Center Thrusting Channels into the Taiji pole. This column of light runs through the center of the body, connecting all Three Dantians together (Figure 4.1). Accumulated Qi is stored as a golden glowing ball in the Lower Dantian.

COLOR VIBRATIONAL PROJECTIONS

Qigong doctors project light of different colors by first drawing the divine light energy into their Taiji Pole, then focusing on the light energy and releasing it either through the arms and out the hands into the patients, or through a visualization of divine light traveling from the Yin Tang (Third Eye) area into the patients.

When Qigong doctors connect with the divine healing white light energy, they absorb massive quantities of this energy into their Taiji Pole. This white light energy prisms into six color projections of light and energy vibration. As the white light energy transforms into multicolored beams of light, the colors can be either absorbed to strengthen the internal organs, or projected out for Qi emission.

The Qigong doctors use inner vision techniques to connect with the correct color for energy projection. One such technique used by doctors allows the color to naturally develop by mentally focusing both eyes to the back of the head. The color that is observed in the back of the mind is projected into their patients' body. This visualization technique is only performed after connecting with the patients' energetic field.

LIGHT THERAPY THROUGH EMITTED QI

The human body produces light which is visible to both clairvoyants and Qigong doctors (Figure 4.2). In China, doctors of TCM have discovered that light therapy is effective in treating certain diseases because of the light field's ability to penetrate the tissues, and interact with the patients' energetic fields.

Extending the image of the color is an important part of the Qigong doctor's ability to treat


Frequency (in hertz)
Type of Radiation
Examples of Sources
Wavelength (in meters)
Ionizing
Nonionizing
10^{23}
10^{22}
10^{21}
10^{20}
10^{19}
10^{18}
10^{17}
10^{16}
10^{15}
10^{14}
10^{13}
10^{12}
10^{11}
10^{10}
10^{9} (GHz)
10^{8}
10^{7}
10^{6} (MHz)
10^{5}
10^{4}
10^{3} (KHz)
10^{2}
10^{1} (Hz)
Heavenly rays
Sun
Gamma rays
X-rays
Ultraviolet radiation
Visible light
Infrared radiation
EHF
SHF
UHF
VHF
HF
MF
LF
Microwaves
Radio waves
Short wave
Med. wave
Long wave
Extremely low frequency (ELF)
Nuclear material, diagnositc and thearapeutic X-ray equipment
Welding equipment, mercury-vapor lamps, black lingt (UV) devices, flourescent and incandescent lights
White light devices
Arc processes, lasers, hot furnaces, molten metals/glass, alarm systems, motion detectors
Cellular phones, microwave ovens, radar, medical diathermy equipment, ultrasound, smoke detectors, MRI
Communications equipment, CB radios, AM/FM transmitters
Power-generating equipment, 60 Hz appliances like stoves, hair dryers, etc.
10^{-15}
10^{-14}
10^{-13}
10^{-12}
10^{-11}
10^{-10}
10^{-9}
10^{-8}
10^{-7}
The visible spectrum
10^{-6}
10^{-5}
10^{-4}
10^{-3}
10^{-2}
10^{-1}
1
10
10^{2}
10^{3}
10^{4}
10^{5}
10^{6}
10^{7}
red
orange
yellow
green
blue
violet

Figure 4.2. Light Spectrum Chart

and heal patients. To treat patients with emitted light therapy, the Qigong doctor first focuses his or her intention on visualizing a certain color and cultivating the energetic vibrations of this color. By visualizing a certain color, the Qigong doctor is activating the light energy within his or her own body. The doctor then focuses on projecting the healthy color light energy into the organs, channels, and organ systems of his or her patients.

Energy color therapy is divided into eight healing colors, ranging from low frequency (red) to high frequency (violet) and white. These energetic projections are associated with the color ranges emanating from the body's Taiji Pole, and range from a dark to a lighter color band.

When projecting color vibrations, it is important to note that there are four levels, or intensities, of color gradations within each color (Figure 4.3). In the soft color range, there are two levels: a light and a medium-light color used for gentler, less potent projections (usually for healing and cleansing wounds). Medium-light color projections are especially effective for treating young children and the elderly. In the intense range, there are two levels of intensities: a bright and a very bright color range, both of which are used for full-force projection (for destroying cells and pathogenic factors or stabilizing a Deficient organ or organ area). The bright color is used to begin with, later on the very bright color can be used as the patient's strength increases.



Figure 4.3. The Four Levels of Color Light Projection

Research has demonstrated that the use of color in Qigong treatments can effectively change a patient's pulse beat, body rhythms and depth of breathing. Advanced Qigong doctors modulate and switch energetic color projections during treatment. To avoid overstimulating the patient's tissues, the doctor starts with a lighter shade of color projection then increase the color's intensity until the proper color is obtained.

Medical Qigong uses the following eight colors for color projection: red, orange, yellow, blue, indigo, violet and white. Based on a modern study of the prismatic division of light energy, color projection is categorized as follows.

1. The ruby red color simultaneously heats and activates the body. Red improves blood circulation and stimulates the Small Intestine, Heart, Triple Burners, Pericardium, and Fire Qi of the body. The color red can be used to repair tissues or increase cellular growth, as well as to vitalize tissues, Blood, and the skeletal system. It is used for treating paralysis, broken bones, and internal and external wounds.
2. The color orange expels pathogenic factors and disintegrates Blood clots. It is also used in treating cysts. Orange can also be used to stimulate the Spleen and Stomach.
   (Contraindications: The doctor must avoid projecting orange color Qi into the brain, eyes, or Heart of the patient. The color orange is extremely potent and may cause damage.)
3. The lemon yellow color stimulates the nerves, reconstructs cells, and heals wounds. Yellow or orange yellow can stimulate the Stomach, Spleen, pancreas, digestive system, nervous system, and the Earth Qi of the body. Yellow is also used in the treatment of skin rashes and topical problems.
4. The emerald green color detoxifies and disperses pathogenic Qi. Green can stimulate the Liver, Gall Bladder, and the Wood Qi of the body. Green is used in combination with other colors; for example, shades of green are combined with shades of orange for treating tumors. Green color vibration is not as powerful as orange and may be used on elderly

patients to establish a more gentle healing session.

5. The flame blue color cools the body and is beneficial in soothing and calming a patient's anxiety. Blue can be used to stimulate the Bladder, Kidneys, the reproductive system, skeletal system, and the Water Qi of the body. The color blue is also excellent for relieving inflammation and fever and can be used as a mild anesthetic.
6. The indigo or dark blue color has a deep penetrating property and is used for knitting bones and creating "energetic casts" (used for enveloping wounds and specific internal organs). The color indigo can also be used to stimulate the Bladder, Kidneys, skeletal system, reproductive system, and the Water Qi of the body.
7. The reddish-blue color of violet is known for its purifying force, which facilitates the rapid healing of difficult infections, e.g., pneumonia.
8. White energy extension indicates a fusion of all colors. White energy is the most neutral and can be used when one is not sure which other color is appropriate. White is useful for calming the mind and placing a protective field around an organ or around the body. White stimulates the Large Intestine, Lungs, the respiratory system, and the Metal Qi of the body.

USING HEALING COLOR IMAGERY

Specific color meditations can be prescribed to assist patients in their healing. The patients are encouraged to visualize specific organ colors while the Qigong doctor projects that same color into their body and energetic fields (Wood-Liver-Green, Fire-Heart-Red, Earth-Spleen-Yellow, Metal-Lungs-White, and Water-Dark Blue/Indigo-Kidneys). This treatment technique is successful for tonifying, regulating, or purging all the body's major organs and is often combined with healing sounds.

When using healing color imagery, the patients are encouraged to first visualize the diseased organ as being dull, dark, and impure in color. In cases of Liver Heat, patients might imagine a dull, turbid brownish-green, tinged with red. For a Heart imbalance, the red color may be first imagined as a dull, weak or darkish red, tinged with brownish-red or purplish-red (like the color of stagnant Blood). Patients begin the meditation by concentrating on exhaling the toxic, pathological colors. As the patients inhale, they imagine a pure, vibrant ruby-red color flowing into their body from the Heavens or Earth, energizing, cleansing, and replacing the toxic energetic color of the diseased Heart.

Note: The image of the vibrant ruby-red color is prohibited in cases of Excess Heart Fire.

EXPOSURE TO EXTERNAL COLOR FIELDS

In this type of color therapy, patients are required to sit and meditate in rooms painted in the specific color relating to their condition. A healthy color is chosen in accordance with either the Five Elements' Creative Cycle or a Controlling Cycle, depending upon the nature of the patient's disease and which particular Yin organ (or organs) are involved. One example is using the Five Elements' Creative Cycle to tonify a patient's Deficient organ. The theory of the creative cycle is to stimulate and energize the "mother" in order to strengthen its proceeding "child" organ. For a Liver imbalance, for example, the patient can be placed in a blue room for tonifying the Kidneys (the Liver's "mother" organ). The Kidney color indigo (the mother) is used to nourish the Liver organ (the child). For a Liver Excess, the Qigong doctor would use the Five Elements' Controlling Cycle and place the patient in a white room, allowing the Lungs (the grandmother) white Metal color to control the Liver Wood (the child) organ.

Also specific colors can be worn by the patient, or the patient can surround him or herself with certain natural colors to initiate healing (e.g., emerald green for Liver conditions).

FOOD AND COLOR

Another treatment method requires the presentation of food (diet) as a form of color and light therapy. In this treatment the doctor makes sure that the Five Elemental colors are present within the patient's food. Each color will start a resonance within the patient's organs (i.e., Green-Liver, Red-Heart, Yellow-Spleen, White-Lungs, and Dark Blue / Indigo-Kidneys).

When eating the food the patient focuses his or her intention on ingesting the color, light, and energy of the food being eaten.

USING DISTANCE AND RANGE

When using color projection, an important factor is the doctor's ability to maintain focused intention. If the doctor becomes distracted or looses visual concentration, the color resonance being emitted becomes degraded, and the projected color transforms back into non-differentiated white-light energy. Since it is the vibratory rate of the specific color that promotes healing, a strong connection between the doctor and patient is vital in distance color therapy projection.

WESTERN LIGHT THERAPY

Light therapy is currently being used in Western medicine through the following modalities:

- Laser-light therapy surgery,
- Full-spectrum light therapy for SAD (seasonal affective disorder),
- Color-light therapy for eye problems and various other illnesses, and
- UV-light therapy for "blue babies" with hyperbilirubinemia.

MAGNETIC ENERGY

Magnetism can influence energetic flows of energy current within the body. It is difficult to separate the energetic properties of magnetism (Yin) and electricity (Yang), as they are almost two aspects of the same energetic field. The movement of electrical currents generate magnetic fields. By establishing different magnetic polarities, the Qigong doctor can influence the electrical flow in the body.

The body's cells carry electromagnetic fields that both attract and repel each other, resulting in a magnetic pull between the body's tissues, organs, and extremities, as well as the body's electromagnetic interaction with the Earth. Clinical research in China demonstrates that the iron in the hemoglobin of the Blood is attracted to the magnetic pull of the body's tissues, as well as the magnetic pull of the Earth.

The Earth, like the body, has both a Yin (magnetic) field and a Yang (electrical) charge. These energetic fields are interdependent. The magnetic

Figure 4.4. The Earth is enveloped with electromagnetic currents, affecting both weather and vegetation.



Figure 4.5. The body is enveloped with electromagnetic currents, affecting both internal and external organ functions.

field is caused by the movement of charged particles and spans the circumference of the Earth creating a strong electrical field (Figure 4.4).

Some modern researchers believe that the physical body's channel system (see Chapter 6) charges its field of magnetic flux through movement. It is further believed that the channel system creates an electrical field that attracts electrons into the body's Taiji Pole.

Richard Lee of the China Healthways Institute found that the Yin magnetic substances stored within the body's water molecules align with the electrically conducting structure of the body's channels (see Appendix 2). When the body's magnetic energy field is low, these channels become weakened and the conductivity is lowered. This magnetic energy can be replenished either from ingesting and transforming food, air and water, or gathered directly from the Earth's magnetic field.

The body's magnetic field conforms to the Earth's magnetic field through the energetic exchange within the body's electromagnetic fields (Figure 4.5). The body maintains this electromagnetic connection through the energetic resonance of the Taiji Pole. Within the structure of the body's Taiji Pole are located two major conductive poles of energy. These two conductive poles are located at the opposite ends of the Taiji Pole, positioned at the top of the head and the base of the perineum. The purpose of these energetic poles is to absorb Qi from universal and environmental fields, connecting and integrating the energy into the body's Three Dantians (see Chapter 5).

The electromagnetic lines in the body's force field begin from the at top of the head (traditionally considered the south pole) where the Heaven Qi flows into the body, and end at the at the base of the perineum (traditionally considered the north pole) where the Earth Qi flows into the body (Figure 4.6). Each of these two magnetic poles (the Lower and Upper Dantian) have a different energy influx. The energy originates and converts in the Lower Dantian and eventually flows to the Upper Dantian. The bottom pole, located in the Lower Dantian, converts Jing (Essence) into Qi (Energy) and increases the body's overall life-force energy. The upper pole, located in the Upper Dantian, converts Shen (Spirit) into perceptual insight and spiritual light.



Figure 4.6. Magnetic field around a spiral coil



Figure 4.7. Flux lines around current-carrying conductor

There are several ways in which the Qigong doctor can manipulate the electromagnetic field which surrounds the body. The doctor can directly absorb Heaven and Earth energy from the bottom of his or her feet, top of the head, and through both palms (called Absorbing Qi from the Five Gates). The doctor can also, through creative visualization, gather and loop the different types of environmental energy around his or her body, increasing the thickness and power of the electromagnetic field (the energetic boundary that surrounds the doctor's body). This looping action is similar to wrapping a magnet with wire to increase its magnetic field potential (Figure 4.7). Stronger lines of magnetic force will be produced around the body, thus creating a stronger "energy bubble" (Figure 4.8).

The direction of electromagnetic wrapping should be done in accordance with the natural flow of the surrounding environmental fields. Each individual should remain sensitive as to which technique works better for them, as there are individual variations used in accordance to the doctor's intention and belief.

MAGNETIC THERAPY THROUGH EMITTED QI

Qigong doctors are trained to manipulate their patient's electromagnetic field by extending emitted energy into the patient's tissues. This stimulation of the body's magnetic field is extremely effective for regulating the flow of channel energy, as well as stimulating the activity of the nervous system.

Magnetic therapy is also used as a companion to acupuncture therapy. Acupuncturists use magnetic patches, placing them on various channel points on the patient's body, to induce energy flow and tissue stimulation.



Figure 4.8. Qigong doctors can create a strong energetic field by absorbing Qi into their Lower Dantian. This energy extends into the Earth (like an anchor), and the Wei Qi field surrounding the doctor's body automatically increases and expands.

The negative north magnetic field pole of the magnet is placed in contact with the patient's skin in treating conditions due to Excess Heat and stagnation. The negative north pole is found to have a cooling and calming effect on tissues. Herbal teas used for purgation, dispersing, anti-inflammatory or sedative properties can be augmented by placing the tea on the north pole of a magnetized surface for a minimum of an hour before drinking.

The positive south magnetic field pole of the magnet is placed in contact with the patient's skin in treating Deficiencies, Cold and blockages. The positive south pole is said to have a stimulating and warming effect on tissues. Herbal teas used for warming and tonification can be augmented by placing the tea on the south pole of a magnetized surface for a minimum of an hour before drinking.

WESTERN MAGNETIC THERAPY

In 1990, Dr. Arthur Trappier submitted a paper on "Evaluating Perspectives on the Exposure Risks from Magnetic Fields" to the *Journal of the National Medical Association*. In his article, Dr. Trappier explained that exposing cancer cells to a negative magnetic field discourages the growth of the cancer, while exposing cancer cells to a positive magnetic field encourages their growth. Magnetic therapy is currently being used in Western medicine through the following clinical modalities:

- Permanent magnet therapy for localized pain and inflammation relief,
- Super-magnet therapy for stimulation of the thymus for immune enhancement in cancer patients, and
- Pulsed magnetic therapy for the treatment of arthritic joints.

GENERATED HEAT

Electricity passing through any substance will produce heat. The amount of heat that will be generated depends upon the resistance of the substance and the density of the current's flow. Heat is generated at the electron level by the friction created through molecular motion. By increasing the motion of the molecules, more heat is generated. Molecules in living organisms are in constant motion, increasing or decreasing their rate of acceleration according to the environmental temperature. In order for heat to have any effect on the body, enough Qi has to be transferred to increase the movement of the molecules.

The heat within the body causes increased electron movement, resulting in more heat being generated on a cellular level. Heat is also caused by cellular metabolism. The body's metabolism produces 75% of the energy being created in the form of heat. Cellular activity is increased through electrical, magnetic, heat, sound, and light stimulation.

From a Medical Qigong perspective, Heat in the body is generated from the accumulation of Three Fires which emanate from specific locations within the body. Within the body's chest cavity is the Heart Fire, located within the abdominal cavity is the Kidney Fire, and all through the body flows the Bladder Fire. When the Heart Fire first awakes, the Kidney Fire responds to it, and when the Kidneys Fire moves the Bladder Fire follows it.

When these Three Fires follow their normal course of energetic movement, they issue and lead the body's life-force energy, creating and sustaining life. The Three Fires are responsible for regulating the Yin and Yang energy of the body by fusing the Five Elemental energies (stored within the body's Wood, Fire, Earth, Metal, and Water organs) with the energy of the Three Dantians. As the Shen from the Heart Fire is drawn into the Lower Dantian, the Bladder Fire fuses with the Kidney Fire, creating the body's True Fire. This action causes the body's Jing to create Qi in the Lower Dantian and then transform Qi into Shen in the Middle Dantian. Once this fusion is obtained, the mind, breath and body connections all become regulated.

The Three Fires also represent the regions of vital Heat responsible for the circulation of energy that sustains the Eternal Soul. Accessing the energy of the three Fires is used for cultivation and spiritual liberation, and is brought about through Qigong practice, prayer and meditation.

1. The Heart Fire, also called the Commanding or Emperor's Fire, is located in the center of the chest. The Heart Fire is responsible for transforming the body's energy into Shen.
2. The Kidney Fire or Mingmen Fire, is located in the back of the body, just below the last floating rib. Qigong masters in ancient times regarded the Mingmen Fire as the motivating force of the body and paid special attention to its training during Qigong exercises. A Deficiency of the Mingmen Fire may lead to decreased sex-drive, hypogonadism and impotency. Conversely, if the Mingmen Fire is in Excess, increased sex-drive or sexual obsession and hypergonadism will occur.

   Dr. Zhao Xianke, an expert on medicine during the Ming Dynasty period, states that "the Mingmen Fire dominates all Twelve Primary Channels. Without it the Kidneys would be weak, the Spleen and Stomach could not digest food, the Liver and Gall Bladder would not give any energy to think or plan, the urine and feces would not be moved, and the Heart would malfunction causing dizziness and endangering life."
3. The Bladder Fire, also called the Common People's Fire, is located in the lower abdominal area by the perineum and is responsible for evaporating water.

The Three Fires are not the Triple Burners, as the purpose of the Triple Burners is to regulate the major internal organs and is a completely different energy system. The physical locations of the Three Fires however, coincides with the locations of the Triple Burners.

HEAT THERAPY THROUGH EMITTED QI

Stimulating the body's tissues through Heat therapy is extremely effective for treating Deficient and Cold syndromes. In China, Qigong doctors use the extension of Heat through their emitted field of electromagnetic energy to stimulate their patients' tissues. This therapy helps to regulate the flow of the patients' channel energy, and tonifies the Blood and Qi.

Kun ☷ ☷

Imprint Kun on your forehead. Start chanting Kun-Kun-Kun, and then use the fingers and palms to help activate the cosmic force Yin-Yin-Yin, Yin-Yin-Yin, marking the lines with your fingers on your forehead. Project the symbol into the universe as you breathe through your forehead. Picture the symbol breathing in violet/blue and when it connects to your forehead bring it down to its place in the lower pakua.

a. **Yin Contract**, Do as before.
b. **Yin Contract**, Do as before.
c. **Yin Contract,** Do as before.



Eyes look up to the Upper right

Fig. 5.55 *Kun*

Ken ☶

Imprint Ken on your lower left cheek bone. Start by the eyes looking down to the lower left cheek bone, chanting Ken-Ken-Ken, and then Yin-Yin-Yang, Yin-Yin-Yang, Yin-Yin-Yang, marking the lines with your fingers on your forehead. Project the symbol into the universe as you breathe through your forehead. Picture the symbol with its violet/blue and bright red colours in front of you and when it connects to your forehead bring it down to its place in the lower pakua.

a. **Yin Contract:** Do as before.
b. **Yin Contract:** Do as before.
c. **Yang Expand:** Do as before.



Eyes look down to the Lower left cheek bone.

Fig. 5.56 *Ken*

Heat therapy is also used in the form of moxibustation as a companion to acupuncture therapy. Acupuncturists will use moxa sticks and/or cones, lighting and placing them on or over various channel points of the patients' body. This is practiced to induce Qi flow and tissue stimulation.

WESTERN HEAT THERAPY

Radiant and conductive heat therapy are currently being used in Western medicine for vasodilation and pain relief. These heat therapies can further be broken down and categorized into dry-heat therapy and moist heat therapy.

Dry-heat therapies include the following:

- Dry packs
- Hot-water bottles
- Heliotherapy-sun therapy
- Ultraviolet-heat therapy
- Infrared-heat therapy
- Diathermy therapy

Moist-heat therapies (hydrocolators) include the following:

- Hot bath packs
- Hot wet packs
- Hot foot baths
- Fomentations
- Poultices
- Vapor and paraffin baths

ELECTRICITY

A flow of electrons is called a current. Just as a current produces a magnetic field, a magnetic field, when it moves in relation to a conductor, induces an electrical current. In Medical Qigong therapy, the body's channels are also considered electrical circuits, and the points existing within each channel can be considered booster amplifiers (or step-up transformers) that maintain the current's strength. According to Dr. Robert O. Becker, research scientist and author of the book *Cross Currents,* acupuncture needles have the capacity to act as antennae, drawing charged particles (ions) from the atmosphere into the body. The acupuncture needle delivers a low-level electrical stimulation to the channel points and can be used to charge up, or decrease the energetic potential of these "step-up transformers," affecting the current along the channel.

The human body is an excellent conductor of electricity and contains both alternating and direct electrical currents. The alternating current is responsible for the transformation of the body's magnetic field into the body's electrical field. The direct current is responsible for the body's positive Yang and negative Yin flow of electrical charges.

The friction produced by rubbing the feet on a carpet creates a charge that is stored within the body until touching another conductor (metal, another person, etc.) to release the charge. This normal and common occurrence demonstrates the storage, conductance, and discharging of electrons from the body. Any time electrons travel, heat, or thermal radiation is produced.

According to Swedish Physician and medical research scientist Dr. Bjorn Nordenstrom, the biological circuits of the body are driven by the accumulated charges, which, unlike a battery, oscillate between positive and negative. The body's system of channels and blood vessels act as insulated cables, while the blood plasma acts as the conductor. In the permeable tissue, the fluid between the cells conducts ions. A key component of the body's electrical circuit is the natural electrodes in the capillary walls, known as the lipid bilayers of the electron transport chain.

A myriad of electrical forces work within the body. Every human thought and action is accompanied by the conduction of electrical signals along the fibers of the nervous system. In fact, life would not exist at all without a constant flow of ions across the membranes of cells.

The electromagnetic energy in the body's cells is continuously being generated through the biochemical transformation of food, and air, and is circulated by the electromagnetic fields being generated within the tissues. Perineural cells, or nerve sheaths, carry the direct current of the body's electricity. These cells are responsible for motivating the body to heal, regenerate, and repair itself. Healing is always affected by a change within the body's electromagnetic field. The rate and efficiency of healing is based on the strength and polarity of the body's field of energy. This electricity is one of the primary energy sources responsible for maintaining life itself.

Dr. Becker's research demonstrates that bones are "piezoelectric": when stressed, mechanical energy is converted into electrical energy that produces an increased electrical current. Dr. Becker discovered that running a minute electrical current through a fractured bone will stimulate the reproduction of the cells, creating a healing current similar to the body's natural healing mechanism.

According to Richard Lee of China Healthways Institute, electrostatic waves are observed in the body through EEGs (electro-encephalograms) and EMGs (electro-myograms). Different types of therapies affect the EEGs (sound therapy, meditation therapy, self-regulation Qigong therapy, light therapy, etc.). By controlling their thoughts, Qigong doctors can affect the current in their body and thus affect the EEG measurements. These thought patterns will in turn influence the Qigong doctors' electrical field. Experiments show that EEG measurements in test subjects receiving energy from healers tend to synchronize. Qigong doctors, when treating patients, can produce voltages as high as 190 volts, 100,000 times greater than regular EEG voltages.

The body's natural ability to gather, store, and move Qi increases the body's abilities to gather, store, and move electrical charges. The gathering of these electrical charges can cause a gradual electric buildup within the tissues and internal organs, developing into an Excess Qi condition within the body. Excess Qi conditions often manifest mood swings and are responsible for the energetic circuit overloads that occur spontaneously within the body. Excess Qi manifests as a sudden "explosion" or "release" of emotions such as rage, fear, grief, worry, fright, anxiety, and joy. An excess electromagnetic charge, internally combined with the Qi from a patient's on-going emotions can be drawn into an organ's tissue area and absorbed by the internal organ that is in the most elevated state of energy conversion. This energetic reaction can cause the already overcharged internal organ to spontaneously release emotions. Sometimes the release is physiological, e.g., sudden sweating, blushing, twitching or jerking, yawning, stretching, sighing, burping, passing gas, etc. These can all be ways that the organ seeks to regain hemostasis.

ELECTRICAL THERAPY THROUGH EMITTED QI

The idea that an electric current can stimulate bodily repair, alert defence mechanisms, and control the growth and function of cells is not a new concept in Western medicine. In fact, the use of bio-electromagnetism dates back at least 200 years. Electrotherapy is found to be very useful in relieving pain by signaling the brain to activate and alter the body's neurochemicals. The insertion of electrically stimulating needles into a patient's body, for example, causes a release of endorphins, and is used for pain management.

Medical Qigong, acupuncture, and Chinese massage likewise, stimulate the peripheral and cutaneous nerves that carry sensory information, via the spinal cord, to the brain. This stimulation of the cutaneous nerves activates the brain's opiates (endorphins - endogenously generated morphine) and facilitates the closure of the body's pain relay gates, killing pain, and is the basis for anesthesia. Because medical Qigong therapy also has an analgesic affect on the body's cutaneous tissues, it is being increasingly used in hospitals for pre- and postoperative procedures.

WESTERN ELECTROTHERAPY

Electrotherapy is currently being used in Western medicine through the following modalities:

- Giga-TENS therapy for stimulation of healing,
- TENS therapy for pain relief,
- CES-cranial electro-stimulation therapy-for depression and substance abuse, etc., and
- Micro-stimulation therapy for micro-current stimulation below the threshold of awareness, to stimulate nonspecific healing, the reduction of inflammation and the harmonization of tissue polarity.

CHAPTER 5
THE THREE DANTIANS AND THE TAIJI POLE

THE THREE DANTIANS

According to Chinese energetic physiology, humans have three important energy centers, located in the center core of the body, that store collected energy in much the same way as a battery does. These three centers are called the Three Dantians (Figure 5.1). The word Dan literally translates to mean "cinnabar," while the word tian means "field." In terms of Medical Qigong tian is referred to as a field of energy. Together, the characters for Dantian literally translates as "cinnabar field" or "field of elixir."



Figure 5.1. The Anatomical Locations of the Three Dantians and Center Core (Taiji Pole)

Cinnabar is mercury sulfide, a bright red or vermillion mineral, which is the principal ore of mercury. Cinnabar was an important mineral in ancient China, the source material needed to manufacture vermillion ink, which could be used only by the emperors. Cinnabar was -- and is today -- also used in Chinese medicine to sedate the Heart and calm the Shen, but always in small doses for short periods due to its highly toxic nature.

Cinnabar was also a vital elixir in Daoist alchemy, as it was discovered to be very balanced in its Yin and Yang properties. Daoist alchemy, like Western alchemy, was practiced in two ways: outer alchemy (Wai Dan) and inner alchemy (Nei Dan). Outer alchemy was the ancestor of modern chemistry. Outer alchemists set up laboratories and experimented with many substances from mineral, animal, and plant sources with the goal of discovering how to turn base metals into gold. Secretly, they were also seeking to discover an elixir, or drug, that would confer immortality or, at the least, greater longevity. Along the way they made many important discoveries, such as gunpowder, medicines, and many other substances vital to the world today.

Inner alchemy was concerned with purifying human nature and transforming the spirit into its most pure and radiant potential without the use of outer agents. Instead, they used Qigong and meditation to circulate and gather the "inner elixirs" of sexual energy, Qi, and consciousness at various locations within the body. The Three Dantians, or "elixir fields," in addition to storing energy, act like an alchemist's crucible, or cauldrons in the role of gathering and transforming vital substances, energies, and various elements of awareness. The ingredients of the inner elixir are Jing, Qi, and Shen. The inner alchemists kept their work secret by using mineral code words such as "gold," "lead," and "cinnabar" to describe the movement and transformation of energetic and spiritual substances within the body.

The goal of the inner alchemists is immortality, a complete transformation of Jing, Qi, and Shen. Jing, Qi, and Shen are collectively called the Three Treasures and are the three fundamental energies necessary for human life. To accomplish this transformation, alchemists first gather and transform Jing into Qi in the Lower Dantian. They then gather and transform Qi into Shen in the Middle Dantian. Next, they transform Shen into Wuji (the absolute openness of infinite space) in the Upper Dantian. Finally, they merge Wuji into Dao (divine energy). The Three Dantians serve as the inner crucibles for these transformations.

These transformations can be compared to the changes of water (the consistencies and not the temperature), which when heated, can change from solid ice, to a liquid, and then to vapor.

The Three Treasures (Jing, Qi, and Shen) are also connected with the Three Outer Forces or Powers known as Heaven, Earth, and Man. Jing (reproductive essence) is the most substantial and therefore the most Yin of the three, and it is closely linked with Earth Qi. In Medical Qigong practice and Daoist inner alchemy, the Earth energy is gathered in the Lower Dantian and is associated with heat. Qi is a mixture of Yin and Yang and is closely connected with the atmospheric energy, which is a blend of Heaven and Earth Qi and gathered into the Middle Dantian, (which is associated with vibration). Shen (Spirit) is the most insubstantial and, therefore, the most Yang of the three; it corresponds with Heaven Qi, and is gathered in the Upper Dantian which is associated with light.

The Three Dantians are connected to each other through the Taiji Pole. The Taiji Pole acts as a passageway for communication between the Three Dantians, and as a highway for the movement of the various life-force energies. The Eternal Soul is drawn into the body at the moment of conception through the Taiji Pole, and departs through it at death. The Taiji Pole also serves as a transport for the body's Hun.

Regardless of whether or not a modern Qigong practitioner is concerned with spiritual transformation, from a Medical Qigong standpoint the Three Dantians are still vital centers for the cultivation of energy. They are important areas for diagnosis and self-healing, as well as for projecting Qi to patients.

The following is an exploration of the Three Dantians and their individual relationships to the Three Treasures of Jing, Qi, and Shen.

THE LOWER FIELD OF ELIXIR

The Lower Dantian is the Dantian most familiar to martial artists and Zen meditators. It is regarded as the center of physical strength and the source of stamina. Called the "Hara" in Japanese, it is located in the lower abdomen, in the center of the triangle formed by drawing a line between the navel, Mingmen (lower back), and perineum. These three points form a pyramid facing downward. This configuration allows the Lower Dantian to gather the energy from the Earth.

The Lower Dantian is the major storage area for the various types of Kidney energies. The Kidney energies are, in turn, closely linked with our prenatal energies and provide the foundation for all other types of Jing, Qi, Yin, and Yang energies in the body.

The Lower Dantian is connected to the first level of Wei Qi (Protective Qi) circulating outside the body, extending from the body's tissues to about one inch. As the Lower Dantian fills with Qi, the Wei Qi field naturally becomes thicker.

THE LOWER DANTIAN AND JING

The Lower Dantian collects Earth energy and represents the body's physical energy of Jing. The Earth energy that is transformed in the Lower Dantian is a dense, full energy with a thick quality to its texture. In our analogy with the transformations of water, the energy in the Lower Dantian is dense, like ice.

The Lower Dantian is closely linked to the Jing Gong (Essence Palace) located in the perineum, which serves as a reservoir of Jing. Our Prenatal Essence (Yuan Jing), determines our constitutional strengths and vitality, and is stored in the Lower Dantian. It interacts with the Kidney energies to form Kidney Jing. The Kidney energies are all closely intertwined: Kidney Jing, Kidney Qi, Kidney Yin, Kidney Yang, and Kidney Fire. The Mingmen Fire, also called Kidney Yang, helps transform the Jing into steam (Kidney Qi).

Kidney Jing circulates throughout the body via the Eight Extraordinary Vessels, in particular, the Governing, Conception, and Thrusting Vessels, all of which originate in the Lower Dantian.

Kidney Jing controls the reproductive energies and life cycles in the body. Some of the ancient alchemical texts describe the Lower Dantian in women as being located in the Bao or uterus, and it is related to the function of Jing in a woman's body. In men, the reproductive essence is located in the Jing Gong (Essence Palace) or prostate and seminal vesicles. In some Chinese medical, Daoist, and Qigong literature, the term Kidneys is used as a synonym for the testes and ovaries.

The location of the Jing Gong is affected by the different anatomical locations of the male and female reproductive organs. In men, this area is located in the center of the body, at the level of the superior border of the pubic bone, posterior to the Qugu CV-2 (Crooked Bone) point. The Jing Gong area in women is located higher, centered in the uterus, about an inch above the superior border of the pubic bone, posterior to the Zhongji CV-3 (Utmost Center) point.

This difference in location, in turn, affects the storage of Jing (i.e., the testicles in the male cause the transformation of energy to occur lower in the body than in females, due to the higher position of the woman's ovaries).

Jing is the most physical, material form of Qi within the body (corresponding to Yin and Earth energy). The Lower Dantian is the place where Qi of the Earth is drawn into the body and transformed by heat.

The Lower Dantian acts as a reservoir for heat and energy and is associated with the Kidneys. The Kidneys control the Water element in the body. Jing is said to be like the water in the cauldron. Through focused concentration and meditation, the Jing (Essence) in the Lower Dantian is refined and transformed to produce Qi (Energy). When heat is generated as a result of the Heart and Mingmen Fire mixing with the Kidney Water, the alchemical transformation of Jing in the Lower Dantian area transforms Jing into the steam of Qi (the character for Qi is composed of steam rising from a cooking pot). This alchemical transformation is known as "changing Jing into Qi," and takes place within the Lower Dantian.

THE LOWER DANTIAN AND QI

The Lower Dantian is often called The Sea of Qi. It is the place where Qi is housed, the body's Mingmen Fire is aroused, the Kidney Yin and Yang Qi is gathered, and the Yuan Qi is stored. Also called Source Qi, the Yuan Qi is the foundation of all the other types of Qi in the body. The Yuan Qi is closely linked with the Prenatal Essence (Yuan Jing). Together, the Yuan Qi and Yuan Jing determine our overall health, vitality, stamina, and life span.

The Yuan Qi is the force behind the activity of all of the organs and energies in the body. It is closely related to the Mingmen and works to provide body heat. The body's Yuan Qi is the catalytic agent for transforming the food we eat and the air we breath into Postnatal Qi. It also facilitates the production of Blood.

Yuan Qi is housed in the Lower Dantian, and it also flows out to the internal organs and channels through the Triple Burners. Yuan Qi is said to enter the Twelve Primary Channels (the body's twelve major energy pathways) through the Yuan points (sometimes called Source points) in acupuncture theory.

Of the Three Dantians, the Lower Dantian is closest to the Earth, is the most Yin, and has the strongest ability for gathering Earth Qi. In Medical Qigong, once students have learned to conserve and circulate their own Qi, they can increase it by connecting to the unlimited reservoirs of Qi in the natural environment. Earth energy is the first form of external Qi with which the Qigong practitioner connects. This energetic connection to the Earth is important for several reasons.

1. First, Qigong practitioners need the Yin grounding power of the Earth Qi to counterbalance the gathered active Yang energy from Qigong exercises. Without grounding in Earth Qi, many Qigong practitioners develop Qi deviations in the form of Excess Heat.
2. Second, each person's supply of Qi is limited. When Qigong doctors extend their Qi to heal others, they deplete their personal supply of Qi unless they are able to simultaneously replenish their supply from outside sources.

Even people who do not practice Medical Qigong draw Earth Qi into their Lower Dantians. By practicing Qigong and using conscious intent, the amount of Earth Qi drawn into the body is vastly increased.

THE LOWER DANTIAN AND SHEN

The Lower Dantian itself is considered a center of consciousness. The consciousness of the Lower Dantian is more kinesthetic or physical given its Yin nature and close proximity to the Earth.

The body's Jing is connected with the Po (Seven Corporeal Souls). The Po control our survival instinct and the subconscious physical reflexes associated with survival. For this reason, Oriental martial artists spend many hours cultivating their lower elixir field to have the integration of Jing, Qi, and Shen needed for the split-second clarity of focus demanded in life-and-death struggles.

THE LOWER DANTIAN AND KINETIC COMMUNICATION

Not only is the Lower Dantian the center of physical strength and the source of stamina, but it is also considered the "house" of physical (kinetic) communication, awareness and feelings. The level of awareness referred to as "the intuition of the physical body," or kinetic communication, is stimulated by the subconscious. The subconscious mind picks up many signals from the environment that are not processed by the logical mind. These signals can motivate spontaneous body movements and responses and are sometimes referred to as gut feelings.

Kinetic means "characterized by movement." It is usually felt as a movement in the body or of the body. It is in this kinetic state of awareness that allows Qigong doctors to naturally feel the patient's internal resonant vibrations within their own body. When the doctors' body suddenly feels hot or cold, starts shaking or trembling, this may indicate that their subconscious mind is trying to communicate the location and condition of the diseased area within the patient's tissues.

Most of the time, the feelings experienced in the Lower Dantian are very subtle, but Qigong doctors, with a heightened degree of awareness of their own body, are able to pick up subtle variations of energetic shifts within themselves and others. When doctors collect energy in the Lower Dantian, an increased awareness and sensitivity naturally occurs. Cultivating this ability simply requires practice in paying attention to the physical body. A high level of awareness of the physical body, the surrounding environment, and the relationship between the two is required to maximize kinetic communication. When awareness is increased, perceptual feeling and kinetic body movements happen naturally. These are subtle senses that allow Qigong doctors to feel, smell, or hear energetic phenomena as they are released from the diseased tissues of patients.

According to research conducted by Dr. Michael Gershon, a professor of anatomy and cell biology at Columbia Presbyterian Medical Center in New York, the Lower Dantian sends and receives impulses, records experiences, and responds to emotions. Its nerve cells are bathed in and influenced by the same neurotransmitters as the brain. The Lower Dantian's "brain," known as the enteric (intestinal) nervous system, mirrors the body's central nervous system and is a network of 100 million neurons (more then the spinal cord contains), neurotransmitters, and proteins that can act independently of the body's brain, and can send messages, learn, remember, and produce feelings.

Dr. Gershon explains that active within the neural system of the lower abdominal area are major neurotransmitters like serotonin, dopamine, glutamate, norepinephrine, nitric oxide, enkephalins (one type of natural opiate), and benzodiazepines (psychoactive chemicals that relieve anxiety). The lower abdomen also has two dozen small brain proteins called neuropeptides. Dr. Gershon's research results provide modern scientific verification of what Eastern wisdom has taught for millennia -- that centers of consciousness exist at places in the body besides the brain and that the abdomen is one of the body's major centers of awareness.

ANATOMICAL LOCATION OF THE LOWER DANTIAN

The Lower Dantian is centered below the umbilicus, inside the lower abdomen, forming a downward pointing triangle. It occupies the first three lower Chakra gates. Chakras are small energy centers that originate from the Taiji Pole and have one or more gates.

1. The lowest point of the Lower Dantian extends to the Huiyin CV-1 (Meeting of Yin) point at the perineum. The name refers to the area on the body responsible for gathering and absorbing the Earth energy. This area is responsible for gathering the Yin energy into the body and Lower Dantian area via the three Yin leg channels (Liver, Spleen, and Kidney). This area is sometimes known as the Lower Gate of the Taiji Pole, or the Bottom Gate of the Lower Chakra.
2. The front area of the Lower Dantian is located posterior to the Shenque CV-8 (Spirit's Palace) point at the navel. The name refers to the place where the mother's Qi and Shen enter the embryo during fetal development. This area is sometimes known as the Front Dantian, or the Front Gate of the Second Chakra.
3. The back area of the Lower Dantian is located at the Mingmen GV-4 (Gate of Life) point on the lower back, anterior to the second lumbar vertebra. The Mingmen occupies the place between both Kidneys. It is the root of Yuan Qi, and therefore determines life and death. The Mingmen provides the body's True Fire; it supplies the heat for the Triple Burners, and is responsible for stabilizing the Kidneys and Lower Dantian area. This area is sometimes known as the Back Dantian, or the Back Gate of the Second Chakra.
4. Medical Qigong schools in China differ in their belief as to where the center of the Lower Dantian is located. Some schools teach that the center of the Lower Dantian is affected by the different anatomical locations of the male and female reproductive organs. In these particular schools, the students are taught that in men, the center of the Lower Dantian is located posterior to the Guanyuan CV-4 (Gate of Original Qi) point. The center of the Dantian area in a women is said to be located internally higher, and posterior to the Qihai CV-6 (Sea of Qi) point. This area is sometimes called the Middle of the Dantian, referring to its position between the navel and Mingmen areas.

THE NINE CHAMBERS OF THE LOWER DANTIAN

The human body is viewed as a microcosmic replica of the power of Heaven. Just as Heaven is said to be divided into nine different levels, each containing various palaces, our bodies also are said to contain a large variety of palaces and chambers. The nine stars of the Big Dipper are said to correspond to the Nine Chambers of each of the Three Dantians.

The functional aspects of the body's psyche were described by ancient Qigong masters as "spirits" that lived within the nine chambers of the Lower Dantian. These "spirits" linked the body's energetic channels and vital internal organs into an organic harmony of life-force energy. Qigong masters believed that as each Dantian became energized, it would initiate specific reactions within the body's energetic system, causing certain energetic / spiritual awareness to manifest within the practitioner's psyche.

Each of the nine chambers is several inches in diameter and is numbered in accordance to its en-


Liver
Stomach
Large Intestine
Small Intestine
Pubic Symphasis
Urinary Bladder
Vagina
Uterus
Huiyin
Rectum
Aorta
Spleen
Kidney
Mingmen
Overies
1
2
3
4
5
6
7
8
9

Figure 5.2A. The Nine Chambers of the Lower Dantian are shown here in the female body. Each number encompasses the entire chamber.


Liver
Stomach
Large Intestine
Small Intestine
Urinary Bladder
Pubic Symphasis
Penis
Testes
Prostate Gland
Huiyin
Rectum
Aorta
Spleen
Kidneys
Mingmen
1
2
3
4
5
6
7
8
9

Figure 5.2B. The Nine Chambers of the Lower Dantian are shown here in the male body. Each number encompasses the entire chamber.

ergetic stimulation (Figure 5.2 A-B). This vertical abdominal set of Lower Dantian chambers relates to many cavities of the body's internal viscera. The Nine Chambers of the Lower Dantian are named as follows.

1. The Palace of Jade (Jade Stem or Jade Cave)
2. The Official Health Monitor (Kidneys)
3. The Minister of the Orchard Terrace
4. The Chamber of Moving Pearls
5. The Minister of House Cleaning (Large Intestine)
6. The Palace of Mystical Spirits (Small Intestine)
7. The Chamber of Mysterious Elixir
8. The Spirit of the Jade Court (Bladder)
9. The Spirit of the Yellow Court (Spleen)

ENERGETIC FOCUS OF TRAINING THE LOWER DANTIAN

All Qigong training begins with the focus on the Lower Dantian. In the beginning stages of Medical Qigong training, the doctor will encourage students to focus their mind and breath on the Lower Dantian. The purpose of this training is to gather the body's Yuan Qi into the Lower Dantian (called "returning to the source"), to strengthen the foundational root for the body's energy.

It is dangerous for Medical Qigong students to bypass the discipline of Lower Dantian cultivation training to progress more quickly to the more advanced intuitive and psychic training of the Upper Dantian. Such an approach to training may lead to Qi deviations (see Chapter 18) and cause emotional instability.

THE MIDDLE FIELD OF ELIXIR

The Heart is the primary organ related to the Middle Dantian; the second organ is the Lungs. In Medical Qigong, the thymus gland is also of primary importance to the Middle Dantian.

In children, the thymus gland is quite large. As the child matures into adulthood, the thymus gland shrinks in size. Until recently, Western biologists thought that the thymus gland became vestigial and inactive in adults. Beginning in the 1980's, however, with the advent of the AIDS epidemic and the increase in cancer cases, intensive new research was launched into the immune system. As a result, scientists discovered that the thymus gland plays a major role in educating and maturing the white blood cells to become immunocompetent. This thymus function continues throughout one's life.

The Middle Dantian collects Qi and represents the body's energetic reservoir for mental and emotional vibrations and energy. The energy of man that is transformed in the Middle Dantian has a fluid quality—like water.

A refining process also takes place in the Middle Dantian, transforming the fluid energy into more steam-like energy that is then transferred to the Upper Dantian. The Middle Dantian transforms Qi into Shen by bringing the transformed Qi into the Heart Fire. This alchemical process is commonly called "changing Qi into Shen" and refers to kinetic energy transforming into spiritual consciousness.

The Middle Dantian is connected to the second level of Wei Qi, circulating about one-and-a-half feet outside the body. As the Middle Dantian fills with Qi, the colors of the student's middle field of Wei Qi change, becoming even more pronounced. The reason for this change is that the Middle Dantian is connected to the Five Agents, which in turn govern the Five Yin Organs and organ emotions. As the students begin to experience various stresses and emotional releases their aura (resonating from the internal organs, throughout the second energetic field) changes its colors.

THE MIDDLE DANTIAN AND JING

The Heart is related to the Fire element. The Heart derives its Yang Fire from the Kidneys. Modern research in Chinese medicine equates the function of the adrenal glands to the traditional function of Kidney Yang. In Western physiology, the adrenal glands help to regulate the pace of the heart.

To keep the Heart Fire in balance, the Heart also needs Yin. Heart Yin is derived from Kidney Yin (Jing is one aspect of Kidney Yin).

In traditional Chinese physiology, the Heart is said to govern the Blood. Not only is the Heart responsible for the circulation of Blood, but in the Chinese view, the transformation of Gu Qi into Blood takes place in the Heart. Food Qi (energy derived from the consumption and transformation of food matter) is a form of postnatal Jing, derived from the Spleen and Stomach. Blood is composed of Nutritive Qi (Ying Qi), Jing and Fluids (see Chapter 22). The Kidneys also send prenatal Kidney Jing to the Heart to make Blood. Therefore, Jing - particularly postnatal Jing - is vital to the Heart's function of governing Blood.

THE MIDDLE DANTIAN AND QI

Similar to the Lower Dantian, the Middle Dantian is also considered to be a Sea of Qi. The Qi of the Middle Dantian is called Zong Qi. Zong Qi is translated as Ancestral Qi, Gathering Qi, Genetic Qi, or Essential Qi. In English translation, it is sometimes confused with the Original Qi (Yuan Qi), but they are not the same. The Zong Qi is a form of postnatal Qi, whereas the Yuan Qi is housed in the

Sun ☴

Imprint Sun on your upper left eyebrow. Start with the eyes looking up to the upper left eyebrow, chanting Sun-Sun-Sun, and then Yin-Yang-Yang, Yin-Yang-Yang, Yin-Yang-Yang, marking it with your fingers on your forehead. Project the symbol into the universe as you breathe through your forehead. Picture the symbol with its violet/blue and bright red colors in front of you and when it connects to your forehead bring it down to its place in the lower pakua.

a. **Yin Contract:** Do as before.
b. **Yang Expand:** Do as before.
c. **Yang Expand:** Do as before.



Eyes look up to the upper left eyebrow.

Fig. 5.57 *Sun*

Chien ☰

Imprint Chien on your lower right cheek bone. Start with the eyes looking down to the lower right cheek bone, chanting Chien-Chien-Chien, and then Yang-Yang-Yang, Yang-Yang-Yang, marking it with your fingers on your forehead. Project the symbol into the universe as you breathe through your forehead. Picture the symbol with its bright red colors and when it connects to your forehead, bring it down to its place in the pakua in your lower abdomen.

a. **Yang Expand:** Do as before.
b. **Yang Expand:** Do as before.
c. **Yang Expand:** Do as before.



Eyes look down to the lower right cheek bone

Fig. 5.58 *Chien*

Note: Any time that you feel the energy shooting into your forehead, right where the senses' control is located, bring both the senses' energy and the energy from the universe down to your abdomen.

Lower Dantian and is a form of prenatal Qi. Zong Qi and the Yuan Qi assist each other to maintain the healthy function of the Heart and Lungs.

The Zong Qi nourishes both the Heart and Lungs, controls the speech and the strength of the voice, and interacts with the Kidneys to aid in respiration. According to Traditional Chinese Medicine, the Kidneys assist the Lungs in holding and stabilizing the breath when inhaling.

Qi and Blood are closely related. In Chinese medicine, it is often said, "Qi is the master of Blood; Blood is the mother of Qi." Qi gives the Heart and blood vessels the strength to circulate Blood and gives life to the Blood. Blood, on the other hand, houses and carries Qi to all the cells in the body. When one loses Blood, one also loses Qi. Therefore, one should consider Qi and Blood to be inseparable.

Qi is also inseparable from the mind and spirit. According to the teachings of ancient Tibetan Qigong masters, the channels are, metaphorically speaking, the road, the Qi is the horse, and the mind is the rider. Through refining the Qi, the mind and spirit are refined and purified. The Middle Dantian is the main focal point for this refinement of Qi into spirit.

THE MIDDLE DANTIAN AND SHEN

Classically, the Chinese locate the Mind in the Heart. In Chinese, the word for "mind" (Xin) is also the Chinese word for Heart. In Medical Qigong, a distinction is made between the Acquired Mind (Ren Xin) and the Original Mind (Yuan Xin).

The Middle Dantian is said to house the Shen and control all of the other functions of Shen that are attributed to the other Yin organs. Thus the Heart is often referred to as the Heavenly Emperor.

Throughout the world, people relate the heart to emotions and feelings. Emotions and feelings are one important aspect of the spirit. Any type of emotion will have an effect on the Shen.

The negative emotions are sometimes called "the five thieves" because even though negative emotions are necessary for life, chronic states of negative emotions drain the Qi.

The human mind easily falls under the influence of the Po (the Seven Corporeal Soul), that are concerned with survival. When the Po dominate the Heart, their overexaggerated self-concern gives rise to a chronic state of fear, sadness, worry, anger, and defensive arrogance.

The redeeming virtue of the Heart is a sense of propriety and discriminating awareness. The Hun (the Three Ethereal Souls) control the smooth flow of Qi throughout the body and are nourished by the Five Virtues of kindness, order, trust, integrity, and wisdom. These Five Virtues give peace and clarity to the Heart and allow the higher qualities of the Yuan Shen to overrule the Po.

An important relationship regarding the Middle Dantian and Shen is found in the Heart's role of governing the Blood. The ancient classics state that the Shen also resides in the Blood and pervades the body through Blood circulation. This relationship between Blood and Shen is one reason why anemic patients are often restless and suffer from insomnia. Through nourishing the Heart Blood, many forms of spiritual unrest can be treated.

According to Dr. Candace Pert's information on neurotransmitters (stated in *Psychoneuro Immunology*), the brain and white blood cells both contain the same neurotransmitters and biochemical constitutes that are prerequisite for consciousness awareness to exist. These same neurotransmitters and biochemical constitutes which are linked to consciousness are synthesized and created by the white blood cells. This similarity indicates that not only do the brain and abdomen have their own consciousness and nervous system but so does the Blood. This similarity also implies that consciousness is possible anywhere in the body, substantiating the ancient Chinese understanding that consciousness is pervasive throughout the body via the Shen, which resides in the Blood.

THE MIDDLE DANTIAN AND EMPATHIC COMMUNICATION

The Middle Dantian is also considered the "house" of emotional (empathic) communication, awareness, and feelings. Emotional communication is analogous to the feelings of empathy felt within the Heart. Empathy is the means by which the Qigong doctor will most frequently get in touch with the emotional components of the patient's energetic blocks and imbalances.

Empathic communication is felt as an emotion and originates in the Heart and Middle Dantian area. When Qigong doctors focus on the Middle Dantian area, a line of communication is created with their higher self. We are all born with this ability, but as we grow older, we tend to override this type of emotional communication with our logical mind. These impressions slowly atrophy, eventually causing us to lose this natural empathic ability of communication. We disconnect from this higher perception due to the negative and double messages received from our parents and from society. The way to reconnect with the intuitive self is to look inward and become one with our true self, which is connected to the divine.

ANATOMICAL LOCATION OF THE MIDDLE DANTIAN

The Middle Dantian is shaped like a tetrahedron (four points): one area points toward the Upper Dantian and the Heavens, one area points toward the Lower Dantian and the Earth, one area points toward the front, and one area points to the back .

1. The front lower point of the Middle Dantian is located at the Zhongwan CV-12 (Middle Stomach Cavity) point on the midline of the abdomen, just below the sternum. This area is the master point of the Middle Burner and is sometimes known as the Front Gate of the Third Chakra.

   This emotional storage area is also called the Yellow Court because it reflects the emotions stored from the Heart, (the Heart was sometimes referred to as Suspended Gold in ancient China).

   The back lower point of the Middle Dantian is located on the Jinzhong GV-6 (Middle of the Spine) point. The name refers to the point's location. This area is sometimes known as the Back Gate of the Third Chakra.
2. The front center point of the Middle Dantian is located at the Shanzhong CV-17 (Central Altar) point, on the middle of the sternum at the level of the fourth intercostal space. The name refers to the "place of worship" where the Shen resides. This area is sometimes known as the Front Gate of the Fourth Chakra.

   The back center point is located two inches up from the shoulder blades, at the Shendao GV-11 (Spirit Path) point located at the hollow between the fifth and sixth thoracic vertebrae. The name refers to the easy accessibility into the patient's Shen residence (within the Heart) through this particular area on the back. This area is sometimes known as the Back Gate of the Fourth Chakra.
3. The upper front point of the Middle Dantian is located at the Tiantu CV-22 (Heaven's Chimney) point, at the throat. The name refers to the visceral cavity area at the base of the throat responsible for "pooling" escaped Heaven Qi from the Lungs. This area is sometimes known as the Front Gate of the Fifth Chakra.

   The upper back point is located on the Dazhui GV-14 (Big Vertebra) point on the back. The name refers to the point's location below the seventh cervical vertebra and above the first thoracic vertebra. This area is sometimes known as the Back Gate of the Fifth Chakra.
4. The center of this Middle Dantian area is located in the right atrium of the heart, centered between the SA (sinoatrial) and the AV (atrioventricular) nodes. The center of the Heart is considered the seat of all emotions.

THE NINE CHAMBERS OF THE MIDDLE DANTIAN

The Middle Dantian regulates the body's Heart—Mind connection. The Heart-Mind connection includes both the all pervasive consciousness of the entire body and the Shen. It distributes the flow of Yuan Qi into the Yin and Yang aspects of the body's mental and emotional functions. These functions within the psyche are controlled by the interaction of the body's Wu Jing-Shen or Five Essence Spirits (Hun, Po, Zhi, Yi, and Shen). The energy of the Middle Dantian is also



Figure 5.3. The Nine Chambers of the Middle Dantian are identical for men and women. Each number encompasses the entire chamber.

associated with the Spleen and Stomach energies. The vertical thoracic set of nine chambers (Figure 5.3), located within the Middle Dantian, originate around the auricles and ventricles of the heart (especially the pericardial and pleural cavities). The Nine Chambers of the Middle Dantian are named as follows.

1. The Chamber of Mysterious Elixir
2. The Lower Court of the Heart
3. The Chamber of the Ultimate
4. The Chamber of Splendor
5. The Heaven's Cover
6. The Twelve Storied Chamber
7. The Chamber of Government
8. The Purple Chamber
9. The Heaven's Chimney

ENERGETIC FOCUS OF TRAINING THE MIDDLE DANTIAN

In Medical Qigong training the doctors encourage their students to focus their mind and breath on the Middle Dantian to regulate the Heart. Techniques are used for treating Deficient conditions by drawing Qi into the Heart and Middle Dantian area, then regulating the body's energetic fields. For treating Excess conditions, the students are encouraged to lead and purge the Excess Qi from the Heart and Middle Dantian area through the body's extremities. The purpose of this training is to release the toxic Excess Qi gathered in the patient's Heart and Yellow Court areas. These areas of Excess tend to cause disease.

THE UPPER FIELD OF ELIXIR

The Upper Dantian is the collector of Heaven Qi and represents the spiritual aspect of man and his connection to the divine. The Heaven energy that is transformed in the Upper Dantian is of a thinner more ethereal quality—like vapor.

The Upper Dantian is connected to the third level of Wei Qi, circulating several feet outside the body. As the Upper Dantian fills with Qi, the spiritual intuition and psychic perception of the individual increases.

In Chinese physiology, the brain controls memory, concentration, sight, hearing, touch, and smell. These senses stay in close communication with the Heart and Shen.

THE UPPER DANTIAN AND JING

The Jing and Qi form the material foundation for the Shen. In Chinese, the term Jing-Shen means mind or consciousness. Jing-Shen may also mean vigor, vitality, or drive. In China both Western and Chinese doctors use the term Jing-Shen Bing to refer to all types of mental illness. The term Shen is rarely used by itself in a medical context without the concept being connected to the close relationship between the power of the mind and spirit.

The term Wu Jing Shen is used in Medical Qigong to describe the body's Five Essence Spirits (Hun, Po, Zhi, Yi and Shen). These five spirits combine the energetic essence of the Five Yin Organs in order to create the body's innate spiritual consciousness.

The Jing itself is considered the basis for, and ruler of Marrow (a substance derived from the Kidneys that nourishes the brain, spinal cord and forms bone marrow). The brain, is one of the six Extraordinary Organs and is called The Sea of Marrow, and is considered to be a form of Marrow. The six Extraordinary Organs are hollow Yang organs that store Yin Jing. Deficiency of Jing may lead to poor concentration, poor memory, dizziness, and absentmindedness. Deficiency of Prenatal Jing is related to mental retardation and attention deficit disorder (ADD) in children.

In some styles of Qigong, the Jing is intentionally conserved and its energy is drawn upwards from the Lower Dantian through the spine to nourish the brain. Such nourishment benefits the mind and spiritual consciousness.

THE UPPER DANTIAN AND QI

The head is the most Yang part of the body since it is the closest part of the body to Heaven. The Qi that operates in the Upper Dantian is, therefore, Yang in nature. The Spleen and Kidneys send the Clear Yang Qi (pure, light, and insubstantial) upwards to the brain to facilitate mental clarity and activity.

The Upper Dantian is also the place where we connect with the Yang Qi of Heaven. Qigong practitioners consciously absorb Heavenly Qi through the upper doorway, Baihui GV-20. The Heaven Qi is composed of the Qi from the celestial bodies: the sun, moon, planets, and stars.

The Upper Dantian is located in the center of the brain, in an area that encompasses the pineal, pituitary, thalamus, and hypothalamus glands. The pineal gland and hypothalamus have been shown to be extremely sensitive to the influence of light. In his book, *The Body Electric,* Dr. Robert Becker cites experiments with bees and several species of birds that indicated that these animals navigate by the light of the sun. Birds have disproportionately large pineal glands. He also discovered that birds seem to have a backup system of navigation based upon a sensitivity to the electromagnetic fields of the earth.

There are three forms of Qi to which the brain responds and interacts: light, electricity, and magnetism. These particular forms of energy stimulate the pineal, pituitary, thalamus, and hypothalamus glands, affecting and influencing the emotional responses.

THE UPPER DANTIAN AND SHEN

We have already discussed the relationship of the Jing and the Shen with the Upper Dantian. Of particular interest to the alchemists is the opening of the center of the Upper Dantian, called the Crystal Room, where psychic perceptions and intuitive knowing take place. Higher communications, a sense of great bliss, and perceptions that transcend the seeming bonds of time and space are associated with the Upper Dantian. These experiences are particularly valuable to Qigong doctors, who use these heightened perceptions to diagnose illness. Their efficacy is well documented in the works of such authors as C. Norman Shealy and Caroline Myss, who use the term "medical intuitive" to describe this paranormal ability.

The Upper Dantian is also the place where the Eternal Soul connects with the Wuji, and with the Dao. The awareness associated with this union is beyond description, as its unity supersedes the differentiation inherent in conceptual thought.

Although the Upper Dantian is responsible for intuitive and psychic perceptions, the combined energetic properties of all three Dantians establishes the foundation for all psychic perceptions. The steam-like quality of the energy with the Upper Dantian fuses within the light now existing in this center. As this energy disperses, it travels out into the Wuji, returning back to the divine. This interaction is also responsible for what the Chinese call "receiving the message," which describes the ability of connecting with the patients' subtle energy field to acquire the hidden knowledge stored within the patients' tissues.

While in a state of tranquillity and inner peace, the Qigong doctors' Upper Dantian will also intuitively process information from the environment and universe. This intuitive knowledge provides Qigong doctors with a greater ability to explore both their own consciousness and the patients'. The ancients called this ability "knowing without knowing."

THE UPPER DANTIAN AND INTUITIVE COMMUNICATION

As the Shen is developed and the Upper Dantian is opened, spiritual communications may reveal themselves in a flash of an image or a vision in the mind's eye. These images and visions are sometimes very abstract and short lived. Interpreting images takes practice because the images streaming from the Yuan Shen cannot be interpreted easily by the logical mind.

The Qigong doctors must be able to distinguish between true and false messages reflected through their visions. True visions are received from the divine connection to the Dao or Wuji; false visions reflect the messages from the subconscious. The ability to accurately separate these visions is an another example of "knowing without knowing."

Although communication from within usually makes itself felt as a strong impulse, Qigong doctors must learn to keep the logical mind from interfering by practicing spiritual meditations. These meditations involve the forging of links in the chain of communication with the higher self. They should be practiced again and again until this connection becomes a natural, recurring phenomenon. The more one practices at stilling the logical mind and circumventing the ego, the easier it will be to get a clear communication from the higher self. When the higher self initiates a communication, it does not demand or impose itself, and if ignored it will usually stop sending signals.

Five Elements must be in place before the communication lines become fully open and operational:

1. Purity in intention,
2. No hidden agendas,
3. Surrender to the divine will,
4. Complete trust and faith in success (believe and expect), and
5. A quiet and receptive stillness of mind.

The lines of communication with the higher self are severed by the logical mind through doubt, fear, and disbelief. Strong faith is required to open this line of communication. Faith requires no logical proof; if proof is needed, then doubts interfere and breed failure. The logical mind cannot know absolute faith and, therefore, faith must come from deep within one's true self. Any form of cynicism will lead to the death of spiritual growth, for it strikes at the root of faith itself.

Faith is not something that can be forced. Even after practicing Medical Qigong for many years, Qigong doctors may still have to battle their own questions. However, through successful practice, the seed of faith is established, allowing it to grow and blossom. The opposite of faith is doubt combined with fear. Suppression and denial of fear builds and armors the ego, which leads to further pain. If the fears are accepted and acknowledged, they can be overcome by faith.

ANATOMICAL LOCATION OF THE UPPER DANTIAN

The Upper Dantian is located in the head, approximately three inches posterior to the Yintang point (between the eyebrows). It is shaped like a pyramid, facing upward to gather the energy from Heaven. This pyramidal reservoir houses light.

1. The front point of the Upper Dantian is the Yintang (Hall of Impression) point. The name refers to the ancient tradition of placing a red mark or "seal" over the Bright Hall, or Entrance of the Spirit, this point represents wisdom and enlightenment. This area is sometimes known as the Front Gate of the Sixth Chakra, or the Third Eye point.


Cerebral Veins
Corpus Callosum
Tian Men
Yin Tang
Front Sinus
Hypothalamus
Pituitary
Mamillary Body
GV-20
Falx Cerebri
Third Ventricle
Thalamus
Epithalamus (Pineal)
GV-16
Cerebellum
Occipital Sinus
Pons
Medulla
Spinal Cord
①
②
③
④
⑤
⑥
⑦
⑧
⑨

Figure 5.4. The Nine Chambers of the Upper Dantian are portrayed in this drawing. Each number encompasses the entire chamber.

2. The back point of the Upper Dantian is located below the external occipital protuberance, on the Fengfu GV-16 (Wind Palace) point. This area is also connected with and surrounded on both sides by the Bl-10 (Heavenly Pillar) point. The energy field connected to this point may be likened to an antennae receiving messages; it allows Qigong doctors to regulate their state of consciousness. The Governing Vessel 16 point is also a Sea of Marrow point, which is used to affect the flow of Qi and Blood to the brain, and a Window of Heaven Point (one of eleven points used for treating Shen disturbances), as well as one of the thirteen points identified by the famous Daoist physician Sun Simiao as a Ghost Point (points used for treating spirit possession). It has been my personal observation that students with a more prominent occipital protuberance tend to see auras more easily and receive psychic intuition faster. This area is sometimes known as the Back Gate of the Sixth Chakra.
3. The highest point of the Upper Dantian is lo-

cated on the vertex of the crown, on the Baihui GV-20 (One Hundred Meetings) point. The name refers to the ancient tradition that one receives divine messages and spiritual intuition from this point into the Upper Dantian's Chamber of Mysterious Elixir, located within the third ventricle of the brain. This area is sometimes known as the Upper Gate of the Taiji Pole or the Upper Gate of the Seventh Chakra.

It is also said in Traditional Chinese Medicine that all of the body's major channels send a connecting vessel to the Baihui so that at death the Qi can leave the body through this upper doorway and ascend to the Heavenly realms.

4. The center of the Upper Dantian is located in the pineal gland. It is the area where the Shen transcends and merges with the Wuji and then progresses on to the Dao. The Upper Dantian is also considered the house of spiritual (intuitive) communication, awareness, and feelings.

THE NINE CHAMBERS OF THE UPPER DANTIAN

The horizontal cephalic set of nine chambers, located within the Upper Dantian (Figure 5.4) is based on the different ventricles of the brain. The Nine Chambers of the Upper Dantian are named as follows.

1. The Chamber of Mysterious Elixir (Mystical Medicine)
2. The Palace of Jade Emperor
3. The Palace of Moving Pearls
4. The Chamber of Splendor
5. The Hall of the Upper Dantian (Medicine Field)
6. The Chamber of the Ultimate Truth
7. The Cover of Heaven (Palace of the Heavenly Court)
8. The Chamber of Government
9. The Entrance of the Spirit (Bright Hall)

ENERGETIC FOCUS OF THE UPPER DANTIAN

In Medical Qigong training, the Upper Dantian pertains to gathering spiritual intuition and light to advance the doctor's intuitive and psychic ability (see Six Transportations of Shen, Chapter 13).

The Qigong doctor may also absorb universal and environmental Qi into the Upper Dantian through the Yin Tang (Third Eye region) and the Tian Men areas (located in the center of the forehead), and emit healing Qi to patients through either one or both of these points. The Shen can both exit and enter the body from the area in the Upper Dantian by way of the Baihui, Yin Tang, and Tian Men (Heavenly Gate) areas.



Figure 5.5. Qi Dispersion From the Center Taiji Pole Through the Dantians into the Body

THE FUNCTIONAL ASPECTS OF THE THREE DANTIANS

The three energy reservoirs of the Dantians are linked externally through the Governing and Conception Vessels and internally through the Thrusting Vessels and the Taiji Pole.

The center of each Dantian is penetrated by and attached to the Taiji Pole, which exits from the Baihui at the top of the head to the Huiyin point at the perineum. Each of the Dantians corresponds to anatomical locations that are centers for magnetic and electrical vibration and charge. The body's intensity of vibration and charge is dependent on the mental intention, the posture, and the respiration.

Qi moves into the body's Dantians through the body's Taiji Pole. The energy is then absorbed into the body's major organs and surrounding tissues as it flows out of the Dantians and into the body's internal and external channels and collaterals.

Each Dantian acts like a reservoir, collecting energy and redistributing it into all of the internal organs. This energy projects through the surface of the body into the Wei Qi field. The same energy also projects inward flowing through the energy channels, along the nervous system and endocrine glands, and then through the Blood, to nourish the body (Figure 5.5).

You can visualize this energy transformation as follows: Qi flows into the body like rainwater flowing into a lake (the body absorbing and collecting Qi into the Dantians). The rainwater is then absorbed into the surrounding soil, foliage, and root systems (skin, tissues, and cells) before it gathers, collects, and pools into deep artesian wells (the Dantians). Pressure begins to build up as these artesian wells fill with the rainwater, and eventually overflow, pouring into smaller pools (the organs) before combining with the rushing action of underground streams (the channels).

Another popular analogy is to consider the Dantians as batteries, the body's Taiji Pole as a magnetic bar connecting the batteries together, the channels as the wires, and the Wei Qi fields as the electromagnetic fields manifesting from the energy contained within the structure.

Mental and emotional awareness of a specific tissue area can be heightened through increasing the flow of energy to that location. When energy fills the tissues, a cellular release of energy causes the tissues to either store or release emotions, depending on the body's overall Excess or Deficient Qi.

If an increase of Qi is focused into the Lower Dantian, the result is a more powerful and stable feeling in the body. When an increased amount of Qi is focused into the Middle Dantian, the result



Figure 5.6. The Three Dantians and Their Relationship to the Three External Wei Qi Fields

is a heightened feeling of emotional perception and awareness. If an increase of Qi is focused into the Upper Dantian, a heightened spiritual awareness and sense of connection to the divine occurs. The greater these energies flow, the healthier the individual becomes, and the stronger his or her energetic fields become (Figure 5.6).

THE DANTIAN'S YIN AND YANG ENERGETIC CHAMBERS

Each of the Three Dantians can be divided into Yin and Yang energetic chambers. The Yang chambers relate to each Dantian's upper chambers and the spiritual aspects of the Hun. The Yin chambers relate to each Dantian's lower chambers and the carnal aspects of the Po. The chambers and their energetic potential are described as follows.

THE LOWER DANTIAN

1. The Yang Energetic Chamber of the Lower Dantian relates physically to the upper quadrant of the abdomen, located within the small intestine in men and the uterus in women. When influenced by the Hun, quiescence and serenity are enhanced.
2. The Yin Energetic Chamber of the Lower Dantian relates physically to the lower quadrant of the abdomen, which includes the reproductive organs and the Bladder, urethra, and anus. This chamber is responsible for reproduction and sexuality. When influenced by the body's Po, raw physical power and sexual vitality are aroused.

THE MIDDLE DANTIAN

1. The Yang Energetic Chamber of the Middle Dantian relates physically to the upper quadrant of the Heart, which includes the left and right atrium, the upper portions of the left and right ventricles, and the atrioventricular node. This chamber is responsible for spiritual attitudes and virtues related to the influence of the body's Hun. The Hun are responsible for:
   - gathering and transmitting divine inspirations and spiritual insights,
   - giving and receiving unconditional love, and
   - motivating spiritual growth through prayer, devotion, and commitment.
2. The Yin Energetic Chamber of the Middle Dantian relates physically to the lower quadrant of the Heart, which includes the left and right ventricles. This chamber is responsible for sensual passions, conquests, and conditional love. It deals with actions which are often based on hidden agendas. These emotions are related to the influence of the body's Po. The influence of both the Po and the Yin Energetic Chamber of the Upper Dantian activates, energizes and enhances:
   - biological drives (for food and self preservation,
   - sexuality, lust and desire, and
   - sensuality.

THE UPPER DANTIAN

1. The Yang Energetic Chamber of the Upper Dantian relates physically to the upper quadrant of the brain, often referred to as the third ventricle or higher brain centers. When stimulated, the higher brain centers manifest spiritual intuition and divine insight, related to the influence of the Hun. Such insight is responsible for spiritual growth and maturation. Insights eventually lead to the emergence of extrasensory perceptions (ESP), e.g., clairvoyance, clairaudience, telepathy, psychokinesis, and spiritual enlightenment.
2. The Yin Energetic Chamber of the Upper Dantian relates physically to the lower quadrant of the brain, often referred to as the "reptilian" brain. When stimulated, the reptilian brain activates the thalamus, hypothalamus, cerebellum, and cortex, which awaken the body's intuition, as well as animalistic and primordial instincts of survival. When the Yin Energetic Chamber dominates, the sensory, animalistic nature of the Po emerges full force. This phenomenon sometimes occurs when coma patients begin to recover. As energy begins to fill the lower chambers of the Three Dantians, their initial reactions are basic and carnal in nature, i.e., to either engage in sexual activity or strike out in violence. As the Qi begins to fill the upper chambers of the Three Dantians, the energy balances in the patient's

Taiji Pole and the patients' impulses return to normal.

THE DOCTOR'S PROJECTED AURA FIELDS

In China, Qigong doctors are tested and categorized according to the predominant color of their Qi emissions. The healing color will depend upon which of the three Dantians is dominant (corresponding to either the Lower Dantian, Middle Dantian, or Upper Dantian), and the energetic strength and potential of the individual being tested. The emitted color is observed in the visible-light spectrum projected from the Qigong doctor's hands.

YELLOW EMITTED COLOR

Individuals who have just begun their training will emit a yellow glow around their external energy field. The Qi will naturally overflow from the Lower Dantian area and the color yellow will dominate the aura. This is actually a normal aura color observed from most beginning Qigong doctors, indicating that the energy field is still too weak to treat serious diseases.

RED EMITTED COLOR

Qigong doctors who have mastered their body and mind will emit a red radiant glow around their external energy field. The Qi will also overflow from the Lower Dantian area, and the color red will dominate the aura. This is actually a normal range of aura color observed from the many Qigong doctors who have just graduated from Medical Qigong colleges, indicating that the energy field is at the intermediate stage.

PURPLE EMITTED COLOR

Qigong doctors who have evolved to the next level of mastering the emotions will emit a purple radiant glow around their energy field. These doctors' Qi will naturally overflow from the Middle Dantian area, and the color purple will dominate the aura. This aura color is observed in strong and advanced Qigong doctors.

BLUE EMITTED COLOR

Qigong doctors who have further refined their energy will emit a blue radiant glow around their energy field. These doctors' Qi will also overflow from the Middle Dantian area, and the color blue will dominate the aura. This aura color is observed in very advance Qigong doctors, and is developed only after many years of clinical practice and personal spiritual transformations.

WHITE EMITTED COLOR

The Qigong doctors who have mastered their spiritual life, as well as surrendered their body, mind, emotions, and spirit to a divine or higher calling will emit a white radiant glow around their energy field. These doctors' Qi will naturally overflow from the Upper Dantian area, and the color of the aura is considered the strongest and most powerful.

CLEAR-OPALESCENT EMITTED COLOR

The divine energy is emitted through a clear-opalescent color. This Qi emission is different then the white radiant glow, and is a sign of divine intervention and healing. These times of divine intervention can occur in any stage of the doctor's energetic development, and are a testimony to the healing virtue of the divine.

Although every Qigong doctor uses a combination of all Three Dantians when projecting Qi into patients, the color of the aura surrounding the doctor's body reflects which Dantian's reservoir is predominantly used. Through time, patience, and much practice, the Qigong doctor will be able to transform from a yellow to red, purple, blue, and finally to white-light healer.

THE TAIJI POLE

The Taiji Pole can be observed as a vertical column (or pole) of brilliant white light, full of vibration and energetic pulsation. This energetic channel flows from the Baihui point at the top of the head, through the center core of the body, connecting the Three Dantians. The Taiji Pole roots its energy at the base of the perineum at the Huiyin area.

In Chinese energetic embryology, as the father's sperm enters the mother's egg, it creates the upper or Heavenly vortex point of the Taiji Pole. At this stage of energetic development, the Heavenly vortex creates and connects the Three

4. Form the pakua on your face to turn the senses inward.

   Chant Kan-Li-Chen-Tui-Kun-Ken-Sun-Chien and mark the place of the specific kua with your fingers.

   a. Kan is on your bridge of the nose.
   b. Li at the top of your forehead.
   c. In this pakua Chen is on (inside) your left ear.
   d. Tui is on (inside) your right ear.
   e. Kun in your brain above the right eye.
   f. Ken inside your cheek bone on the left side.
   g. Sun in your brain above the left eye.
   h. Chien inside your cheek bone on the right side above.

   Repeat the chanting in your mind and let your eyes move to the place of each kua. Feel the power of the symbols attracting your senses in to the mideyebrow. Chant and spiral the Tai Chi symbol with your finger and then only with your mind. Let the Tai Chi spin fast and faster. Keep on chanting the Tai Chi symbol until the energies are pulled to the center of the pakua. You should feel that all the energy is flowing to the center of the face pakua and connecting to center of the brain, the crystal room, and keep on spiraling and be aware of the Lower Tan Tien, Tai Chi, and also the spiraling of the facial pakua itself. Feel a very strong center in your forehead and bring it down to the center of the lower pakua.



Draw all senses into the center of the mideyebrow.

Fig. 5.59 *Pakua on your face to turn the senses inward*

Dantians together, rooting the column of white light energy into the Kidneys and Mingmen area. As the fetus continues to grow and develop, the Taiji Pole slowly descends, shifting its energetic root to the base of the perineum. After birth, the Taiji Pole can be observed as a vertical column of brilliant white light, surrounded by a veil of golden spiraling light.

HEAVEN, EARTH, AND MAN RELATIONSHIPS

The Taiji Pole of the body is comparable to the central axis of the Earth, which is known as the Taiji Pole of the Earth. At the end of the Earth's Taiji Pole are the North and South Poles, which are compared to the body's Baihui at the top of the head and Huiyin at the base of the perineum. The Earth's Taiji Pole (or central axis) aligns to the North Star.

The North Star is seen as the Taiji Pole of Heaven and is sometimes called the Pole Star or Taiji. It is sometimes said that the original Chinese character for Taiji means Yin and Yang. While the original meaning of the Chinese character for Yin is the shady side of the mountain, and Yang depicts the sunny side of the mountain, the mountain's peak is considered a Taiji, where both Yin and Yang meet (or the center of Yin and Yang).

The center Taiji is also called the Still Point, because although all of the changes of Yin and Yang occur in the Heavens within the course of a day, and all of the stars seem to make a 360 degree rotation (as the Earth rotates) the Pole Star remains stationary as Heaven's Still Point. In a similar manner, the body has the Taiji Pole as the "still point of man." A great stillness is experienced when a Qigong practitioner gathers Qi into the Taiji Pole.

INTERNAL ENERGY INTERACTIONS

Extending from the body's Taiji Pole are the Three Dantians, Five Jing-Shen, and the Eight Extraordinary Vessels. These vital energetic systems feed all the major organs and the body's Twelve Primary Channels. As the Three Dantians absorb energy from the body's Taiji Pole, they also extend, or "feed," and energize the body's Yin and Yang organs, Twelve Primary Channels, and Eight Extraordinary Vessels. Each individual Dantian is connected to the body's Taiji Pole and is responsible for creating its own alchemical transition in the process of converting Jing into Qi, Qi into Shen, Shen into Wuji, and Wuji back to the Dao (see Chapter 13).

In my clinical experience, the closer I work to the patient's Taiji Pole the more powerful the energies become. Accessing the patient's Taiji Pole, Three Dantians, and Eight Extraordinary Vessels for whole body tonification and regulation is faster and less draining on my energetic reservoirs then emitting Qi into the patient's Twelve Primary Channels to accomplish the same type of treatment.

THE FIVE THRUSTING CHANNELS

Five internal Thrusting Channels connect to and transverse the body's center Taiji Pole. These five internal channels begin at the perineum and spiral up through the center of the body's core, flowing into the upper crown of the head. They connect the Baihui area at the top of the head to the Huiyin area at the bottom of the perineum. These five internal channels absorb the Five Elemental energies of Heaven and Earth (Wood, Fire, Metal, Earth, and Water) into the body.

The Taiji Pole is responsible for absorbing the energy from Heaven and Earth and distributing the collected Qi into the body's major internal organs. Similar to the Earth's central axis, the Taiji Pole is divided into two main energetic polarities: The Five Portals of the Heavenly Yang Gate, located at the top of the head, and the Five Portals of the Earthly Gate, located at the perineum (Figure 5.7).

When the body's internal and external energetic wave patterns become synchronized through prayer or meditation, a rhythmic pulsation occurs within the Taiji Pole. This pulse begins deep within the center core of the body and vibrates outward towards infinite space connecting the Wuji with the Dao.

SPIRITUAL MANIFESTATIONS

When doctors penetrate the outside veil surrounding the center core of a patient's Taiji Pole and extend their intention into the light's center, they experience the sensation of falling into space



Top of Head

Figure 5.7. The Five Portals of the Heavenly Yang Gate are portrayed here as seen looking down at the top of the head. The Universal Energy is absorbed into the Taiji Pole through the Five Portals of the Heavenly Yang Gates, located at the center of the Baihui (One Hundred Meetings) and Sishencong (Four Spirits Hearing) areas, at the top of the head.



The Five Portals of the Earthly Yin Gate as seen from the perineum. The environmental energy is absorbed into the Taiji Pole through the Five Portals of the Earthly Yin Gates, located at the center of the anal sphincter, between the Huiyin (Meeting of Yin) and the Changqiang (Long Strength) areas, at the base of the perineum.

or shooting through space. This sensation is followed by seeing flashing colors and moving shapes, as the surrounding core dissolves into infinite space itself. As the Qigong doctors continue to extend their intention to reach this area, time and space feels as if they stretch into eternity. This experience is considered the true connection with the Wuji returning back to the Dao. The potential for this experience exists within everyone and can be accessed through deep prayer and meditation. It is quite a normal phenomenon within deep spiritual practices and is sometimes known as accessing the river of God.

ENERGETICALLY OPENING THE TAIJI POLE

When we are born, we are connected to great spiritual wisdom and power through our center core. During the maturation process, this connection slowly fades away, yielding to masks and defense mechanisms, that seek to shield us from our pain and self-hatred (shame). In childhood, every time we repressed the flow of painful feelings connected to an event, we froze that particular event in both energy and time, and locked it within our muscles. Since the external Wei Qi is composed of energy consciousness, a block of frozen psychic energy is formed within the Wei Qi at the moment we inhibit the pain. By walling off our wounds, we also wall off our connection to our deeper core self (Figure 5.8). We pretend not to feel the pain anymore, we block off the memory of the event. Thus, we prevent a natural resolution to the pain and the trauma of the event. Through denying our true feelings we disconnect from our core self and put on masks. We smile when angry, for example, or pretend indifference to our hurts. Since creative inspiration comes from our core, we lose our creative ability. When we stop the negative experiences of anger, pain, or fear, we also stop the positive healing of the physical, mental, and emotional aspects of the experience.

During Medical Qigong treatments, patients regress layer by layer through the pain and fear associated with the blocked energy that gives rise to the disease. Even though the memories may be very strong and frightening, as the emotions



Figure 5.8. The True Self is Contained Within the Core Self

release, the pain decreases with the dispersal of the original trauma.

I have found in my clinical practice that most of the patients' pain comes not from the original trauma but from the unconscious belief system established to protect them from the original trauma. In other words, more pain and illness is created in our bodies by avoiding working through the original trauma (through our habitual defense and avoidance patterns) than was present in the original trauma. It requires enormous amounts of energy to suppress feelings, and each time we do so, we create further injuries to ourselves.

SPIRITUAL AWAKENING

When patients become aware of their spiritual connection to the divine, it is called an "awakening." This change can be observed through the spiritual transitions experienced within the patients' center core through their Taiji Pole. When the center Taiji Pole (which connects all three Dantians) begins to awaken, certain physical, emotional, and energetic reactions may occur within the patients' body. These transformations occur because the tissues of the energetic fascia (that connect to the major organs of the body) are enveloped within the energetic structure and webbing of the Taiji Pole.

THE TWELVE GATES OF THE CHAKRA SYSTEM

Although the body's major internal energy centers are contained within the interacting network of the Three Dantians, the Three Dantians also connect to the body's major energy doors (located on the Governing and Conception Vessels), known as the Twelve Gates of the Chakras. These Chakra gates are superficial, on the surface of the skin, and are not as deep as the Chakra Cores and Three Dantians which are all connected to the Taiji Pole (Figure 5.9).

The word Chakra is Sanskrit for "wheel." The Chakras look like small, colored disks, usually about the size of a silver dollar. Energetically the Chakra gates look like funnels or vortices of Qi. Qigong doctors and sages have for centuries described their perceptions of these gates as resembling energetic wheels or vortexes within the subtle energy body. Each funnel extends and expands its energetic vortex out into the body's Wei Qi field. As energy travels up and down the Taiji Pole it creates an energetic pulse. This energetic pulse resonates out from the body through the Twelve Chakra Gates, and can be felt several feet from the body. The bottom Chakra is located at the perineum and only has one gate, as does the top Chakra located at the top of the head; the second, third, forth, fifth, and sixth Chakras have two gates each, one on the front of the body and the other on the back of the body. These Chakra Gates serve the following different energetic functions:

1. The top or Crown Chakra gate is responsible for absorbing Heavenly Qi and light into the body, as well as energizing the center core's Taiji Pole.
2. The front Chakra gates are responsible for the patient's feelings and emotional activity. They are related to the patient's Shen and the Heart Fire energy. They are connected to the Conception Vessel.
3. The back Chakra gates are responsible for the patient's willpower and determination. They are related to the patient's Zhi and the Kidney Water energy. They are connected to the Governing Vessel.



Figure 5.9. The body's Twelve Chakras Gates extend from the Taiji Pole and expand outward into the three external Wei Qi fields.

4. The center of the Chakras are actually deep inside the body's center core, located within the middle of the Taiji Pole.
5. The bottom or Base Chakra gate is responsible for absorbing Earthly Qi and heat into the body, as well as energizing the Taiji Pole. Generally, when treating a patient, the Qigong

doctor extends energy into the patient's back Chakra gates to stabilize the emotions and to access control over the patient's will and determination. The doctor can, for example, connect with the Heart Chakra back gate, located on the patient's Shendao, GV-11 point, to access the emotions stored within the tissues of the Heart. The front Chakra gates are used to remove Excess emotions from the patient's tissues. Although the treatment approach differs, the Three Dantians system and Twelve Chakra Gate system, mutually support each other, both in the location of the energy centers, and in their physical manifestations of energetic function.

The Yin and Yang polarity of the Chakra gates are opposite in men and women (Figure 5.10). The Twelve Chakra Gates serve as subtle energy distributors, that help absorb and distribute environmental Qi to the patient's organs, tissues, and major nerve plexus areas closest to each gate. Each Chakra gate is connected to its own potential of psychic perception, interfaces with the body's nervous system, and is associated with a different endocrine gland. Any energy extended from the Qigong doctor towards a patient's Chakra gate will affect the patient's physical body. As the patient begins to energetically open the Chakra gates, the external energetic Chakra wheels begin to spin in half-circle rotations, opening and closing with the core's energetic pulse. The energetic action is similar to the centripetal (closing) and centrifugal (opening) action of the body's energetic channels.

Each opening of a Chakra gate may result in a spontaneous emotional release. Some of these releases can involve painful memories that have been dislodged from the energetic filter (or veil) that envelops the Chakra gates. This energetic filter prevents external emotional traumas from entering into the body's center core.

A Chakra gate can become stuck open, closed, or may also tilt out of alignment with the Taiji Pole, causing Qi Deviations that may result in a distorted or obstructed flow of energy. This obstruction may cause physical, as well as psychological, stress or trauma. The release of these emotional

Polarity		
Chakra	**Men**	**Women**
7th	+ Yang	– Yin
6th	– Yin	+ Yang
5th	+ Yang	– Yin
4th	– Yin	+ Yang
3rd	+ Yang	– Yin
2nd	– Yin	+ Yang
1st	+ Yang	– Yin

Figure 5.10. The energetic Yin and Yang polarity of the Chakra Gates are opposite in men and women. The Chakra Gates of a man start from a Yang (+) energetic field (at the Lower Chakra Gate) and change to Yin (-) at the second Chakra Gate, alternating from Yang to Yin up the body, ending at Yang in the Upper Chakra Gate. Women display the opposite energetic polarity in each Chakra Gate.


Crown Chakra Area
Pituitary
Pineal
6th Chakra Area
Cerebral Cortex
Carotid Plexus
Thyroid Parathyroid
5th Chakra Area
Pharyngeal Plexus
Lungs
Pulmonary & Cardiac Plexus
Thymus
4th Chakra Area
Heart
Adrenals
3rd Chakra Area
Solar Plexus
Pancreas
Spleen
Liver
Kidneys
2nd Chakra Area
Sacral Plexus
Ovaries
Testes
1st Chakra Area
Coccygeal Plexus
Testes or Adrenals
(varies depending on the energy system)

Figure 5.11. The body's Chakra system is connected by the Taiji Pole and extends outward into the body's nerve plexus, affecting the glandular system and both anterior and posterior external energetic fields.

traumas can be overwhelming and painful if the patient has not prepared for, or does not understand the nature of, these transitional energetic malfunctions. These manifestations usually occur when the patient's system has been energized and the body is actively seeking to release and get rid of toxic emotions from certain areas. Qigong doctors should be aware of these strong emotional reactions to assist their patients in facing and working through their fears and pain as the Qi Deviations along the Taiji Pole are corrected. Sometimes these experiences unwind at a rapid rate, stimulating the patient's central and anterior nervous system; this can release a flood of mental and emotional images and sensations, that are sometimes accompanied by shaking, thrashing, and other unusual movements of the body (Figure 5.11).

THE BOTTOM CHAKRA GATE

The bottom or first Chakra gate is sometimes called the Meeting of Yin (referring to the Earth energy), and is located near the perineum, in front of the anal sphincter on the Huiyin CV-1 point. This energy center controls the reproductive system and the urogenital organs and intersects with the Bladder and Kidney Channels. It is associated with survival instincts (the "fight or flight" response), security, tribal power (group acceptance), and the "grounding" or "rooting" of the body.

The first Chakra is associated with the Lower Dantian. Its energetic elemental nature relates to Earth, and its color is red. It connects to the Taiji Pole at the base of the perineum and exits at the top, or Crown Chakra.

The bottom Chakra is associated with the kinesthetic, tactile, and proprioceptive senses. It supplies energy to the spinal column, adrenal glands (in some systems), testicles/ovaries, and Kidneys. This Chakra gate is also connected to both the Conception and Governing Vessels.

The bottom Chakra gate will immediately open in any emergency situation, or when there is danger, to release stored information to ensure survival. Energetic malfunctions caused by stored emotional trauma in this Chakra can cause a massive amount of fear for one's life to be released. The retention of massive amounts of fear, or the sudden energetic release of panic, can cause the following symptoms: lower back pain, sciatica, constipation, hemorrhoids, rectal tumors and cancer, knee problems, and varicose veins.

THE SECOND CHAKRA GATES

The second Chakra core can be accessed through two energetic gates. The front gate is sometimes called the Spirit's Palace Gate and is located at the navel around the Shenque CV-8 point. The back gate is sometimes called the Gate of Life and is located on the lower back at the Mingmen GV-4 point.

This second energetic area is considered the "gateway of the Lower Dantian." Its energetic elemental nature relates to Water, and its color is orange. It is the energy center through which other people's emotions are perceived (kinesthetic perception), allowing one to be sensitive to other people and to sense dangerous situations.

The second Chakra is the energy center for sexuality, sensuality, the hunger for power, and financial issues. It supplies the sexual organs (ovaries and testicles) and the immune system with energy.

When the second Chakra gate opens the patient feels the release of sexual desires, waves of orgasm, and sexual fantasy. Because this area is also associated with the desire for power, sometimes the desire to destroy is released. Energetic malfunctions caused by stored emotional trauma in this Chakra can cause lower back problems, frigidity or impotence. Second Chakra dysfunction can also cause Kidney, uterine, Bladder, and urinary problems.

THE THIRD CHAKRA GATES

The third Chakra core can be accessed through two energetic gates. The front gate is sometimes called the Solar Plexus Center, in this system of Chakra diagnosis it is located between the navel and the xiphoid process (at the level of the pancreas), at the Zhongwan CV-12 (Middle Stomach Cavity) point. The back gate is called the Middle of the Spine and is located on the middle of the back at the Jizhong GV-6 point.

The third Chakra area is associated with the Middle Dantian and is known as the Yellow Court in Medical Qigong therapy. Its energetic elemental nature relates to Fire, and its color is yellow. It is the body's distribution point for psychic energies (gut instinct and intuition), personal power, and self-image. It is the area where the body's Qi transforms into Shen. It is also a storage chamber for severe emotional pain and anger.

This area supplies energy to the Liver, Gall Bladder, Stomach, Spleen, pancreas, adrenal glands, and nervous system. The third Chakra is the center for personal power-storing issues of responsibility, self-esteem, personal honor, and fear of rejection.

When the third charka's energy gates open, feelings of power and waves of anger, rage, fear, greed, jealousy, judgment, and criticism can be released. Energetic malfunctions caused by stored emotional trauma in this Chakra area can cause ulcers, hypoglycemia and diabetes, as well as Liver and / or adrenal problems.

THE FOURTH CHAKRA GATES

The fourth Chakra core can be accessed through two energetic gates. The front gate is sometimes called the Heart Center and is located at the center of the breastbone, at the Shangzhong CV-17 point. The back gate is sometimes called the Spirit Path and is located on the Shendao GV-11 point on the back, between the scapula.

The fourth Chakra area is associated with the Middle Dantian. Its energetic elemental nature relates to Wind, and its color is green. This energy center is associated with love, compassion, empathy, clairsentience, and intuition. This area supplies energy to the Heart, Lungs, circulatory system, thymus gland, vagus nerve, diaphragm, and upper back.

When this energy center opens, it can be physically painful (the patient may experience feelings of a weight on the chest, heart attack sensations, or the release of tears) as the patient becomes aware of being attached to the personal ego. The feelings associated with the fourth Chakra have to do with our internal world, while feelings associated with the third Chakra have to do with the external world. Energetic malfunctions can cause Heart and Lung diseases.

THE FIFTH CHAKRA GATES

The fifth Chakra core can be accessed through two energetic gates. The front gate is sometimes called the Throat Center and is located just above the hollow of the throat, at the Tiantu CV-22 point. The back gate is sometimes called the Big Vertebra and is located on the back, at the base of the neck on the Dazhui GV-14 point.

This energy center is associated with sound vibration, personal and divine will, and communication. The fifth Chakra area is associated with the Middle Dantian. Its energetic elemental nature relates to sound, and its color is bright blue. It is the center for psychic clairaudience, and the power source for the Qigong doctor's "inner voice" guidance. This area supplies energy to the throat, thyroid and parathyroid glands, neck vertebrae, mouth, Lungs, and alimentary canal (the digestive tube from the mouth to the anus).

When the fifth Chakra energetic center opens, a compulsive urge to sing and chant arises. This area is also where Heat from the Liver Fire sometimes becomes entangled with Phlegm (a viscid substance that is a product and a cause of disease) from the Lungs, forming what is known as "plum pit Qi" (an energetic knot within the throat). Energetic malfunctions caused by stored emotional trauma in this Chakra area can cause stiff neck, sore throat, throat "plum pit Qi" symptom, thyroid problems and swollen glands. The patient sometimes experiences a release of unexpressed grief and anger, resulting in the physical reactions of excessive swallowing, coughing, or laryngitis.

THE SIXTH CHAKRA GATES

The sixth Chakra core can be accessed through two energetic gates. The front gate is sometimes called the Third-Eye Center and is located at the middle of the forehead at the Yintang or Hall of Impression point. The back gate is located on the back of the head, between GV-16 (Wind Palace) and GV-17 (Brain's Door), at the external occipital protuberance.

The sixth Chakra area is the center for psychic intuition, clairvoyant seeing (inner vision), and energy projection. The sixth Chakra area is associated with the Upper Dantian. Its energetic elemental nature relates to light, and its color is indigo (deep violet blue). This area of the body is responsible for enabling the Qigong doctor to see auras, Chakras, and other energetic images. This center is also responsible for mental telepathy, allowing the doctor to sometimes know the patient's thoughts and feelings. This area of the body supplies energy to the pituitary gland, lower brain, ears, nose, eyes, and nervous system.

When the sixth Chakra energy center opens, energetic malfunctions can result in headaches, eye strain, pain around the eyes, distorted or blurred vision, and sometimes blindness. Inaccurate interpretations of events, projections of personal fears and other emotions and motivations onto others may sometimes occur. Reoccurring nightmares and misguided fantasies may also be incurred.


(Noon)
Wu
Descent of Yin
(Purification Phase)
Wei
Si
Ch'en
Shen
(Sunrise)
Mao
You
(Sunset)
Yin
Xu
Ch'ou
Hai
Ascent of Yang
(Cleansing Phase)
Zi
(Midnight)

Figure 5.12. This figure shows the Twelve Earthly Branch Relation to the Twelve Chakra Gates. The Governing and Conception Vessels flowing through the middle of the back and front of the body correspond to the ecliptic path of the sun along the Twelve Chakra Gates, and are related to the Twelve Earthly Branches.

THE UPPER CHAKRA GATE

The upper or top Chakra gate is sometimes called the Crown Center and is located on top of the head at the Baihui GV-20 point. This energy center is associated with higher knowledge, understanding, pure intuition, and ecstasy. The upper Chakra area is associated with the Upper Dantian. Its energetic elemental nature relates to infinite space (Wuji), and its color is violet. This area supplies energy to the pineal gland and upper brain.

When the upper Chakra energetic center opens, it is like a golden flower opening, accompanied by a dazzling bright light and a strong, powerful connection with the divine. Energetic malfunctions result in confusion, apathy, alienation, boredom, depression, and a state of incomprehension.

TAKING PRECAUTIONS

When any of the energetic reactions to opening the Chakra gates take place, it is important for the student or patient to realize that these are only transitional stages and are normal phenomena which occur as a sign of energetic and spiritual transformations. The student or patient should take certain precautions, however, like being under the care of a qualified Qigong doctor when beginning any type of energy training.

It is also important not to allow patients to experience these emotional transitions alone. Because these energy transitions, malfunctions, and deviations are new to the Western mode of thinking, they can easily be misdiagnosed by doctors unfamiliar with energetic medicine. Patients should be encouraged to find or establish a support group consisting of advanced practitioners of energetic meditation. Having a support group of experienced practitioners allows these emotional and spiritual transitions to occur in a safe environment, where other experienced practitioners can monitor the patient's feelings, if and when, unfamiliar emotions start to emerge.

THE TWELVE EARTHLY BRANCHES AND THE TWELVE CHAKRA GATES

The body is viewed as a small and complete universe unto itself. The internal organs are influenced by the celestial movements of the sun, moon, planets, and stars. The Governing and Conception Vessels, where the Twelve Chakra Gates are located, are also affected by the Heavenly cycles.

In ancient China, the day was divided into twelve separate time divisions. Each time division corresponds to two hours of the day and was named after one of the Twelve Earthly Branches. These twelve time divisions were further organized into months and seasons (see Chapter 11). The ancient Qigong doctors discovered that the body's Qi and Blood mirror the Earth's seasonal ebb and flow, rising and falling like the lunar tides.

Each of the time periods corresponding to the Twelve Earthly Branches is regarded as having a specific influence on each of the Twelve Gates of the body's Chakra system. The rhythmic variations of the waxing and waning of Qi and Blood is associated to the waxing and waning of Yin and Yang energy, as well as the circulation of Qi following the Microcosmic Orbit (Fire) cycle.

Each of the Twelve Chakra Gates relates to one of the Twelve Earthly Branches following the Microcosmic Orbit (Fire) cycle (see Chapter 41). These Twelve Chakras Gates extend their energy from the patient's Taiji Pole outward, along the center of the body, through the anterior and posterior fields of Qi. Beginning at the bottom Chakra gate (the "Zi" Branch, representing midnight), the energy follows the Fire Cycle of the Microcosmic Orbit, traveling up the Governing Vessel, following the "ascent of Yang." After the Yang Qi reaches its peak, the Yin begins to grow. Starting at the upper Chakra gate (the Wu Branch, representing noon time), the energy travels down the Conception Vessel, following the "descent of Yin" (Figure 5.12).

Creating the Back Pakua on the Head

Duplicate trigrams, pakua and the Tai Chi symbol to the back and spiral clockwise while chanting the Tai Chi, Tai Chi. The mind and the eyes are spiraling as well, going faster and faster. When you spiral as fast as possible, you will feel that the energy is drawing into the back Pakua.



Fig. 5.60 *Pakua on the Head*

Be aware of the front and back Pakuas and spiral them. Spiral in the center faster and faster drawing the front and back into the center.



Fig. 5.61 *Front and Back Pakuas spiraling.*

CHAPTER 6
THE TWELVE PRIMARY CHANNELS AND ORGANS

INTRODUCTION

According to Traditional Chinese Medicine, a system of channels exists that integrates all the body's separate parts and functions into a unified organism. The understanding of these channels and their energetic function and interactions provides the Qigong doctor with the basis for understanding the relationships among the various physiological, pathological, diagnostic, and therapeutic relationships in Traditional Chinese Medicine.

The study of Chinese medicine rests on, and is inspired by, the circulation of Qi, as many diseases follow a predictable course of development. The pathology in an internal organ will often manifest itself in certain external or systemic symptoms; therefore, understanding the circulation of Qi flow allows the doctor to control each organ's energetic function. By stimulating specific sites on the body's surface, diseases in both the superficial tissues and internal organs can be treated.

A doctor of Medical Qigong uses various techniques that facilitate the opening of the major energetic connectors of the body's internal organs. These connectors, called channels and vessels, are responsible for connecting the flow of Qi within the whole body to transfer Qi both internally and externally.

The channels are also known as meridians or Jing-luo. The Chinese character for this type of Jing means "to move through," while the translation of the character luo means "a net" (the body's inner fascia). Along these channels are major trunks and lesser branches that connect internally with the vital organs and externally with the major channels, limbs, sensory organs, and orifices.

The smaller branches are known as collaterals. The tiny areas along these channels and collaterals where the Qi pools are called points. These points are the spots where the patient's spirit and energy enter and leave the body. When stimulated, these channel points (sometimes also called "acupuncture points"), cause an energetic response from within the internal organs and channels, resulting in internal Qi flowing from organ to channel, from channel to channel, or from point to point along the same channel.

The channels unite the body as one unit. Channel theory is interrelated with organ theory. Traditionally, the internal organs have never been regarded as simply independent anatomical entities. Rather, Traditional Chinese Medicine focuses on the functional and pathological interrelationships between the channel network and the organs. The internal organs and their systems are sometimes known as "orbs" or "spheres of influence."

Qi travels throughout the physical body along the channels and collaterals much as water flows through rivers and streams. An ancient Chinese medical text explains this concept as follows: "Heaven is covered with the constellations, Earth with the waterways, and man with channels." Qigong doctors of ancient China paid much more attention to the Body Fluids and energies circulating through the body than to the physical anatomical structures. The ancient Chinese considered the Body's Fluids and energies much more fundamental.

The channels serve as the link between the energies, such as Jing, Qi, Shen, and the ingredients, such as Blood and Body Fluids, that feed and enliven the tissues. The human body's main energetic rivers are the Twelve Primary Channels and Eight Extraordinary Vessels (see Chapter 7).

CLASSIFICATION OF CHANNELS

The channels are classified into four main categories: Jing, Luo, Muscle Tendon, and Skin Zones.

1. The Jing Channels are the Primary Channels. These channels include the Eight Extraordinary Vessels, the Twelve Primary Channels, and the Twelve Divergent Channels.
2. The Luo Channels are the Collaterals. These collaterals include the Fifteen Major Collaterals, the Minute Collaterals, and the Superficial Collaterals.
3. The Muscle/Tendon Channels consist of twelve channels that serve as external connections to the major channels, flowing through the body's muscles, tendons, and ligaments.
4. The Cutaneous Regions are skin zone areas where the channels surface on the external tissues.

JING CHANNELS

The Jing Channels are the major trunks of the circulatory tree. They generally flow vertically through the body through relatively deep tissues. They also transverse the limbs peripherally and penetrate the body cavities to connect with the internal organs (Figure 6.1). They are the body's main interior and exterior rivers of Qi.

1. The Eight Extraordinary Vessels connect with, and regulate, the Qi and Blood of the Twelve Primary Channels by either absorbing any energetic "runoff" in times of channel Excess, or by replenishing energy in times of Deficiency.
2. The Twelve Primary Channels are bilateral and symmetrical. They can be identified in three specific ways: (1) according to the corresponding Yin or Yang organ to which they are connected, (2) by the arms or legs in which the channels originate or end, and (3) according to the six divisions of Yin or Yang Qi to which the channels relate (i.e., Tai Yang, Yang Ming, Shao Yang, Tai Yin, Shao Yin, and Jue Yin).

   The Yin channels run along the medial and anterior aspects of the body. They are associated with the solid Yin organs and connect with the hollow Yang organs. The Yin channels include the Kidneys, Spleen, and Liver Channels that flow from the feet to the torso, a well as the Heart, Pericardium, and Lung Channels that flow from the torso to the hands.

   The Yang channels run along the lateral aspect of the body. They belong to the hollow Yang organs and connect with the solid Yin organs. The Yang channels include the Small Intestine, Triple Burners, and Large Intestine Channels that flow from the hands to the head, as well as the Bladder Gall Bladder and Stomach Channels that flow from the head to the feet. The interaction between the internal/external, Yin/Yang relationship of the organs and channels results in an alchemical transference between energy and matter.
3. The Twelve Divergent Channels branch off the Twelve Primary Channels. They are mainly distributed on the chest, abdomen, and head. The Divergent channels have the energetic functions of connecting internally and externally related channels, strengthening the connection of the Twelve Primary Channels to their related organs, and serving as extensions of the Twelve Primary Channels.

LUO OR COLLATERALS

The Twelve Primary Channels are connected by collaterals, which are small, interlinking streams. These collaterals are the connecting branches of the energetic circulatory system. They generally flow superficially, in horizontal and vertical energetic directions. They are the body's secondary streams of Qi that form an intricate network that traverses the body's surface and interconnects the main rivers, connective tissues, and cutaneous regions (Skin Zones).

1. The Fifteen Major Collaterals (Luo) transfer Qi and Blood from the Twelve Primary Channels to all parts of the body and link the body's interior with its exterior, connecting the body's internal and superficial channels, as well as the Governing and Conception Vessels and the Great Luo of the Spleen (see Chapter 7).


Divine Energy
(Descent of the Soul)
Yang Heavenly Energy
(Universal Energy: Sun, Moon, Stars)
Yin Earthly Energy
(Environmental Energy: Earth, Wind, Water)
Mother's Substance
(Egg: Essence, Energy, Spirit)
Father's Substance
(Sperm: Essence, Energy, Spirit)
The four energies combine and attract the Soul. The center of the energies becomes the Taiji Pole.
Upper Dantian
(Field of Light)
Middle Dantian
(Field of Vibration)
Lower Dantian
(Field of Heat)
3 Dantians
(3 Fields of Energetic Elixir)
9 Channels
(In each Dantian—Taiji Pole is center chamber)
9 Stars
(Taiji Pole + 8 Extraordinary Vessels)
Taiji Pole
(Center Core of Light)
Qi overflows when in excess
Qi moves to strengthen
10 Heavenly Stems
(10 Energetic Pools)
5 Yin Organs
Liver
Heart
Spleen
Lungs
Kidneys
5 Yang Organs
Gall Bladder
Small Intestine
Stomach
Large Intestine
Bladder
Qi overflows when in excess
Qi moves to strengthen
Qi overflows when in excess
Qi moves to strengthen
8 Extraordinary Vessels
(8 Energetic Reservoirs)
Qi moves to strengthen
Qi overflows when in excess
12 Earthly Branches
(12 Primary Channels or 12 Energetic Rivers)
6 Arm Channels
3 Yin Channels
Lungs
Pericardium
Heart
3 Yang Channels
Large Intestine
Triple Burners
Small Intestine
6 Leg Channels
3 Yin Channels
Spleen
Liver
Kidneys
3 Yang Channels
Stomach
Gall Bladder
Bladder
Conception
Thrusting
Yin Linking
Yin Heel
4 Yin Vessels
Governing
Belt
Yang Linking
Yang Heel
4 Yang Vessels
12 Earthly Branches branch into and flow alongside
12 Earthly Branches flow under skin zones and are absorbed into muscles and tendons
12 Earthly Branches come to the skin surface
Provide connections between the 12 Earthly Branches
12 Divergent Channels
(12 Secondary Rivers)
12 Muscle/Tendon Channels
12 Skin Zones
(12 Dermal Segmentations)
15 Collaterals
(15 Connecting Streams)

Figure 6.1. Channel and Organ Energy Flow



Figure 6.2. The Human Body's Energetic Matrix

2. The Minute Collaterals are smaller branches of the Fifteen Major Collaterals. They are countless in number.
3. The Superficial Collaterals are smaller branches of the Minute Collaterals. They are also countless in number.

MUSCLE TENDON CHANNELS

The Twelve Muscle/Tendon Channels are the external connections of the major channels. They generally flow superficially, traversing the body's surface and serve to join the main rivers, connective tissues, and Cutaneous Regions. The Twelve Muscle/Tendon Channels are also regions of the body where the Qi and Blood of the Twelve Primary Channels nourish the muscles, tendons, and ligaments.

CUTANEOUS REGIONS

The Twelve Cutaneous Regions (also called Twelve Skin Zones) are areas of the body where the Blood and Qi of the Twelve Primary Channels surface and connect to the body's skin tissues. These cutaneous regions have a continuous and direct contact with the external environment.

The body resonates in a continuous interplay of Yin and Yang harmony, balancing the channels' and organs' energy flows. The channels help create the body's external Yin and Yang polarities and create the energetic matrices around which the body's energetic fields can flow. Together these energetic matrices establish the foundation of the body's energetic tissues (Figure 6.2).

THE CHANNELS' RELATIONSHIP TO QI AND BLOOD

The channels transport Qi and Blood to nourish, moisten, and vitalize the whole body. Healthy bodily function depends on the balanced circulation of Qi and Blood. Qi is Yang and provides the energy or force necessary for the body's functional activity (i.e., movement and transportation, warming, containing, transforming, and defending). Blood is Yin and is the source of the body's moistening, nourishment, and lubrication.

The Blood, Qi, and heat circulate through the Twelve Primary Channels every two-hours, ebbing and peaking in energetic flow. The maximum peak of a channel's Qi, or "high-tide," occurs at the time of day when the Qi in that channel is at its fullest. The minimum period of a channel's Qi, or "low tide," occurs twelve hours from the peak time (Figure 6.3).



Figure 6.3. The Body's High and Low Energetic Tides

The connective tissues of the body's fasciae transmit a variety of biological energies. Think of the inner fascia as lubricated linings that cover the muscles and internal organs, allowing the tissues to slide and move easily. Within the lining of the superficial fasciae, the channels are webbed; this webbed network conducts energy in the form of electron, proton, and ion transmission, and is influenced by light and sound.

According to Traditional Chinese Medicine theory, each of the Twelve Primary Channels has its own individual resources of Qi and Blood; however, the energetic quality varies in accordance with the amount of Blood and Qi available in each organ and its particular channels. From a traditional Chinese medical perspective, the Spleen plays two important roles in regard to Qi and Blood. First, it converts food into Gu Qi which, when further refined by the Liver and Kidneys, becomes Ying (Nutritive) Qi; and second, it manages the Blood by keeping it in the channels. Ying Qi secretes Body Fluids that enter into the blood vessels and are transformed into Blood by the Heart. The Heart both creates and governs the Blood; whereas, the Liver stores it and spreads Qi throughout the body. Blood is considered to be a denser, more material form of Qi. Qi and Blood

Organs & Channels	Qi	Blood
Liver	less	more
Lungs	more	less
Large Intestine	balanced	balanced
Stomach	balanced	balanced
Spleen	more	less
Heart	more	less
Small Intestine	less	more
Bladder	less	more
Kidney	more	less
Pericardium	less	more
Triple Burners	more	less
Gall Bladder	more	less

Figure 6.4. The Body's Organ and Channel Relationship to the Proportions of Qi to Blood

are interdependent: Qi moves the Blood, but the Blood nourishes Qi; both flow together.

The chart in Figure 6.4 shows each of the Twelve Primary Channels and the proportion of Qi and Blood each channel carries.

FUNCTION OF THE CHANNELS

The channels are responsible for responding to any malfunction in the body. They can also, however, be disseminators of energetic dysfunction and disease. Disease passes in to the internal organs, or from one organ to another, via the channels. Exogenous diseases progress from the body's skin pores to the tiny collaterals, then to primary channels, and finally, to the internal organs. The channels are affected by disease in a predictable fashion.

1. Diseases and symptoms manifest along the channel pathway.
2. Points along the channels become tender, painful, tight, or flaccid.
3. When in a deficient state, the electrical resistance and heat tolerance diminish on the skin at the diseased point(s).
4. The body's sensory organs (sight, smell, taste, hearing and touch) are affected through channel relationship.

From a traditional Chinese medical perspective, the functions and flow of the channels and collaterals, as well as the internal organs' health can be affected by Medical Qigong, acupuncture, Chinese massage, and herbal medicine. Each system of Traditional Chinese Medicine disperses Excess, moves stagnation, stimulates and nourishing the Qi to tonify Deficiency, and stimulates the Wei Qi to fight External pathogens via the channels. In fact, each time the body's channels and collaterals are trained or regulated, they become thicker with Qi.

INTERNAL AND EXTERNAL CHANNEL FLOW

As the Qi of an internal channel flows into or out from its "primary organ," it generates a current that is similar to a river rushing back into the sea. The moment that energy flowing through the internal channel permeates the primary organ, an energetic connection and reaction is immediately created in the organ tissues. When the Qi of an internal channel flows into its "associated organ," however, the energetic reaction is quite different. Instead of immediately permeating the organ, the channel's energy "spirally wraps" the organ's tissues through the internal fascia that envelops the associated organ. The associated organ tissues then absorb the energy from the surrounding fascia. This difference in energetic penetration and absorption rate is an important factor when working with the body's internal energetic channels. When Qigong doctors extend their energy into a patient's channels, they must be aware that the absorption rate will be immediately felt in the channels pertaining organ, and will have a gradual effect on the organ's associated organ.

Channel Name	Yin or Yang	Associated Organ	Element	Blood Heat Cycle	Qi Blood Cycle	Abbre-viation
Gall Bladder	Yang	Liver	Wood	11 p.m.– 1 a.m.	more Qi less Blood	G.B.
Liver	Yin	Gall Bladder	Wood	1 a.m.– 3 a.m.	less Qi more Blood	Liv.
Lungs	Yin	Large Intestine	Metal	3 a.m.– 5 a.m.	more Qi less Blood	Lu.
Large Intestine	Yang	Lung	Metal	5 a.m.– 7 a.m.	balanced Qi and Blood	L.I.
Stomach	Yang	Spleen	Earth	7 a.m.– 9 a.m.	balanced Qi and Blood	St.
Spleen	Yin	Stomach	Earth	9 a.m.– 11 a.m.	more Qi less Blood	Sp.
Heart	Yin	Small Intestine	Fire	11 a.m.– 1 pm.	more Qi less Blood	H.
Small Intestine	Yang	Heart	Fire	1 p.m.– 3 p.m.	less Qi more Blood	S.I.
Bladder	Yang	Kidney	Water	3 p.m.– 5 p.m.	less Qi more Blood	Bl.
Kidney	Yin	Bladder	Water	5 p.m.– 7 p.m.	more Qi less Blood	K. or Kid.
Pericardium	Yin	Triple Burner	Fire	7 p.m.– 9 p.m.	less Qi more Blood	P.
Triple Burner	Yang	Pericardium	Fire	9 p.m.– 11 p.m.	more Qi less Blood	T.B.

Figure 6.5. The Twelve Primary Channels are divided into Yin and Yang. The Yin channels are connected to the solid organs, and the Yang channels are connected to the hollow organs.

ORGAN AND CHANNEL FUNDAMENTALS

The purpose for energetic anatomy and physiology is to understand the fundamental actions of each organ and each channel's unique energetic characteristics. This understanding includes the learning of differential diagnosis to categorize the various symptoms into meaningful patterns of disharmony. This ability to categorize the various symptoms will enable the doctor to analyze and recognize specific pathologies indigenous to specific organs and channel energies (Figure 6.5).

In Chinese medical science, the study of energetic physiology is called Zhang Xiang Xue Shou, which literally translates as "the theory of the phenomena of internal organs." Here, the word "phenomena" means visible external manifestations. The organ's physical structure is of little consequence; whereas, its function in the body is of primary importance. While Western anatomy and physiology are primarily concerned with the physical body in its most concrete form (investigating the structures of the major body systems and organs), energetic anatomy and physiology focuses mainly on the underlying energy that enlivens and sustains the physical form.

In Chinese medical science, the body's internal organs are responsible for creating and distributing Qi, Blood and Body Fluids. Traditional Chinese Medicine divides Body Fluids into two distinct categories: Jin, which are the body's clear, light fluids, and Ye, which are the body's thick and heavy liquids.

1. The Jin Body Fluids are the Yang Fluids of the Upper Burner that move with Wei Qi. They are fast, light, and clear fluids, such as: sweat, tears, saliva, and mucus. The Lungs control the Jin.
2. The Ye Body Fluids are the Yin Liquids of the Middle and Lower Burners that move with Ying Qi. These are slow, heavy, and thick liquids. These liquids include those that moisten the joints, spine, brain, and Bone Marrow and lubricate the eyes, ears, nose, and mouth. The Spleen and Kidneys control the Ye.

This internal action of creating and distributing Qi, Blood and Body Fluids is manifested throughout the body's tissues through the Blood's Heat Cycle, which actively follows a peak (high-tide) and ebb (low-tide) energetic time period. Each organ and channel has either a Yin or Yang characteristic and is grouped and paired according to its Five Element nature.

This chapter focuses on the Twelve Primary Channels and their relationship to the organs. Most Traditional Chinese Medical texts begin the sequence of these channels with the Lung Channels. In this text, however, due to the energetic waxing and waning of the Yin and Yang Yao Cycles, and the Twelve Pi Hexagrams (see Chapter 11), I will start with the Gall Bladder Channels. The Twelve Primary Channels are described as follows: Gall Bladder, Liver, Lung, Large Intestine, Stomach, Spleen, Heart, Small Intestine, Bladder, Kidney, Pericardium, and Triple Burner.

THE GALL BLADDER CHANNELS

The Gall Bladder Channels are Yang channels. The external branches flow from the head to the feet on both sides of the body (Figure 6.6). The internal branches of the Gall Bladder Channels flow from the head to the Gall Bladder. The internal and external branches of these two rivers originate from the outer canthus of each eye. The external branches zigzag around the side of the head, flowing down the sides of the torso. The internal branches leave the outer canthus of the eye and descend the neck, entering the supraclavicular fossa, where they meet the main channels at the St-12 and Pc-1 points, and pass through the diaphragm, spirally wrapping the Liver, and permeating the Gall Bladder. From there they encircle the genitals and enter deeply into the body to emerge at the sacrum.

The external rivers continue to descend the lateral aspects of the torso and legs, ending at the lateral sides of the tips of the fourth toes.

THE GALL BLADDER ORGAN

The Gall Bladder's associated organ is the Liver; its element is Wood. The Gall Bladder's function of storing and excreting bile depends on the Liver's function of maintaining a smooth flow of Qi throughout the body.

The Gall Bladder also helps the Liver control the sinews, tendons, and ligaments. The Liver provides Blood to the sinews, while the Gall Bladder provides Qi to the sinews in order to ensure proper movement and agility.

PSYCHO-EMOTIONAL ASPECTS

The Gall Bladder is responsible for making decisions and judgments, as well as providing courage and initiative. This organ is sometimes called The Court of Justice or The General's Advisor. Although the Kidneys control drive and vitality, the Gall Bladder provides the capacity to turn this drive and vitality into decisive action.

The Gall Bladder has an influence on the quality and length of sleep. If the Gall Bladder is Deficient, the patient will often wake up suddenly, very early in the morning, and be unable to fall asleep again.

Patient's who are timid, indecisive, and easily discouraged by slight adversity, are said to have a weak Gall Bladder; conversely, decisive and determined patients are said to have a strong Gall Bladder.

GALL BLADDER'S ENERGY FLOW

The Gall Bladder Channels are often used to drain off the energy from an overheated or Excess Liver condition. Energetically, the Gall Bladder Channels store more Qi than Blood, acting more on energetic and nervous functions than on physical substances and Blood functions. At the


GB-17
GB-16
GB-18
GB-15
GB-14
GB-8
GB-4
GB-1
GB-3
GB-19
GB-20
B-10
GB-9
GB-2
GB-21
GB-22
GB-23
GB-24
St-12
GB-25
GB-26
Pc-1
GB-27
GB-28
GB-29
GB-30
Lv-13
GB-31
GB-32
St-30
GB-33
GB-34
GB-35
GB-36
GB-37
GB-38
GB-39
GB-41
GB-42
GB-40
GB-43
GB-44

Flowing down from the head, the internal channels of the Gall Bladder pass through St-12 and Pc-1 then spiral wrap the Liver organ. From there, they circle the inside lining of the ribs (on the side of the body) then descend to the St-30 points.

Figure 6.6. The Internal and External Qi Flow of the Gall Bladder (GB) Channels

Duplicate the front Pakua to the left side and let the Tai Chi symbol spin.

Duplicate the back Pakua to the right side of the head and let the Tai Chi symbol spin. Become aware of the center of the brain, the crystal room and let it spin faster and faster, drawing the energy of the left and right Pakuas into the center.



Fig. 5.62 *Energy of the left and right Pakua into the center of the Brain.*

Be aware the front, back, left and right Pakuas and let them spin. Put more attention on the center of the brain and let the center spin faster and faster, drawing all the energy into the center.


Center of the Brain Tai Chi Spiraling

Fig. 5.63 *Draw all the energy into the Center.*

high-tide time period (11 p.m. to 1 a.m.) Qi and Blood abound in the Gall Bladder, and so the Gall Bladder organ and channels can more easily be dispersed and purged. During low-tide (11 a.m. to 1 p.m.) they can be easily tonified. The Gall Bladder Channels' energy acts on the skin, muscles, and nerves found along their pathways.

WESTERN MEDICAL PERSPECTIVE

The gall bladder stores then releases bile through the cystic duct into the common bile duct that flow into the small intestine to aid in the digestion of fats.

PATHOLOGICAL MANIFESTATIONS

The main symptoms of the Gall Bladder Channel diseases are:

- pain in the right-and left-upper quadrants of the abdomen,
- disorders of the head, which include the eyes, ears, and face, and
- disorders of the external sides of the legs along the channels' pathways.

THE LIVER CHANNELS

The Liver Channels are Yin channels that flow externally from the feet to the torso (Figure 6.7). These two rivers originate externally from the inside of the big toes and flow upward on the inside the legs, to circle the groin. From there they continue to ascend externally to the lateral aspects of the thorax, where they enter internally and permeate the Liver. They then connect to and spirally wrap the Gall Bladder. From there, they flow to the Lungs, ascend internally into the thorax, and connect with the eyes, cheeks, and inner surface of the lips. They emerge from the forehead and connect with the Governing Vessel at the Baihui GV-20 point (Figure 6.8).

THE LIVER ORGAN

The Liver is responsible for the "free and easy wandering" of Qi in the body, i.e., the Liver makes the Qi flow smoothly in and around the body. The Liver governs the Belt and Thrusting Vessels, as well as the body's Qi flow and circulation. The smooth flow of Qi ensures normal mental and emotional activity, as well as normal secretion of bile. Impairment of this Liver function leads to a "binding depression of Liver Qi," associated with impatience, hasty decisions impulsive actions, and a hot temper.

The Liver's associated organ is the Gall Bladder; its element is Wood. The Liver energy opens externally at the eyes and manifests externally through the fingernails and toenails. The Liver stores the Blood, and serves as a reservoir of Blood to regulate the circulation of Blood volume. In women it assists the uterus and regulates the menses. The Liver regulates the function and control of the muscles, tendons, and ligaments and is the source of the body's physical strength. It also stores the emotion of anger.

PSYCHO-EMOTIONAL ASPECTS

The Liver is responsible for planning and creativity, as well as instantaneous solutions or sudden insights; it is therefore considered The General in Charge of Strategy. The Liver houses the body's Hun and governs fright.

Its positive psycho-emotional attributes are kindness, benevolence, compassion, and generosity; its negative attributes are anger, irritability, frustration, resentment, jealousy, rage, and depression.

The Liver is also called the "root of resistance to fatigue." Whenever the Liver is not functioning properly (stagnate or excessively Hot due to suppressed emotions) the patient can experience fatigue as well as physical weakness.

THE LIVER'S ENERGY FLOW

The Liver Channels move the Qi to the whole body, storing and distributing the Blood. The Liver Channels contain more Blood than Qi, thus they affect physical substances more than they affect energetic functions. At the high-tide time period (1 a.m. to 3 a.m.), Qi and Blood abound in the Liver, and so the Liver organ and channels can more easily be dispersed and purged.; whereas, during low tide (1 p.m. to 3 p.m.), they can be easily tonified. The Liver Channel's energy acts on the skin, muscles, and nerves found along their pathways.

WESTERN MEDICAL PERSPECTIVE

The liver stores vitamins A, B-12, D, E, and K, and regulates blood volume. It is one of the main


GV-20
Lv-14
Lv-14
Lv-13
Lv-13
CV-12
Lv-12
Lv-12
Lv-11
Lv-11
Lv-10
Lv-10
Lv-9
Lv-8
Lv-7
Lv-6
Lv-5
Lv-4
Lv-3
Lv-2
Lv-1

Figure 6.7. The Internal and External Qi Flow of the Liver (Lv) Channels


GV-20
Lu-1
St-12
CV-12

Figure 6.8. Side View of the Liver Channel's Internal Flow of Energy

sources of the body's heat. The liver manufactures cholesterol and functions in lipid metabolism and controls bile secretion.

PATHOLOGICAL MANIFESTATIONS

Diseases of the Liver Channels cause swelling and a distended sensation of the hypochondrium. The Liver Channels also correspond to diseases of the lower abdomen and genital organs.

Since the Liver supplies the tendons with nutrients to develop physical strength, Liver impairment causes numbness, tremors, or spasms of the muscles, and sluggishness in joint movements.

The Liver and Kidneys are mutually dependant upon each other. The Liver stores the Blood that nourishes the Kidney Jing; whereas the Kidneys store Jing that helps produce the Blood. Deficient Kidneys may lead to Blood Deficiency, and Deficient Liver Blood may cause weakness of the Kidney Jing due to lack of nourishment from the Blood. The hair on top of the head is also nourished by the Blood. When the hair turns grey, it is often alleged to be caused by insufficient Blood stored in the Liver, as well as a Kidney Jing weakness.

THE LUNG CHANNELS

The Lung Channels are Yin channels and flow externally from the torso to the hands. The main river originates internally from the Middle Burner, in the middle of the chest, and descends downward, connecting with and spirally wrapping the Large Intestine. From there, it ascends along the upper surface of the Stomach passage and through the diaphragm, where it branches and permeates both Lungs (Figure 6.9).

From the Lungs, the rivers of Qi merge and ascend into the pit of the throat, where they separate again into two channels that transverse below the clavicle. These two main channels then surface externally to descend down the arms, and end on the outer side of each thumb. A small stream of energy branches off each wrist at the Lu-7 point and runs directly to the radial side of the tip of the index finger, where it connects with a branch of the Large Intestine Channels.

THE LUNG ORGAN

Since the Lungs are the uppermost organs, they are compared to canopies that shelter and protect all other internal organs. The Lungs' associated organ is the Large Intestine; its element is Metal. The Lung Qi opens externally at the nose and manifests itself through the voice (i.e., when the Lung Qi is in Excess the voice is too loud; when Deficient the voice is too soft). The Lungs govern the body's Qi and respiration. They regulate the metabolism of Water passages (sweat and Body Fluids), the opening and closing of the pores, the skin and the hair's texture.

The Lungs also control the circulation of Qi in both vessels and channels, as well as the dispersing or spreading of the body's Wei Qi (protective energy). They control the descending and holding functions of the body's Qi and Body Fluids.

All blood vessels lead to the Lungs, i.e., all Blood within the body must pass through the Lungs.

PSYCHO-EMOTIONAL ASPECTS

It is said that the Lungs are "the priest" or The Minister of Heaven and are responsible for establishing the foundation of Qi for the entire body (see Chapter 12). The Lungs house the body's Seven Corporeal Souls (Po) and are responsible for self-protection and self-preservation.

The Lungs positive psycho-emotional attributes are righteousness, dignity, integrity, and high self-esteem; their negative attributes are disappointment, sadness, grief, despair, anxiety, shame, and sorrow.

THE LUNGS' ENERGY FLOW

Functionally, the Lung Channels' energy acts on the Lungs, bronchi, throat, and larynx. If the Lung Qi is combined with Liver Qi and becomes stagnate in the throat area, a condition known as a "plum pit," or knot in the throat, develops. The Lung Channels store more Qi than Blood, thus they have a greater affect on energetic and nervous functions than on physical substances and Blood functions. At the high-tide time period (3 a.m. to 5 a.m.), Qi and Blood abound in the Lung organs and channels. They can therefore be more


Lu-1
Lu-2
Lu-1
Lu-2
Lu-3
Lu-4
Lu-3
Lu-4
Lu-5
Lu-5
Lu-6
Lu-6
Lu-7
Lu-8
Lu-9
Lu-10
Lu-11
Lu-7
Lu-8
Lu-9
Lu-10
Lu-11

Figure 6.9. The Internal and External Qi Flow of the Lung (Lu) Channels

easily be dispersed and purged at this time period; whereas during low-tide (3 p.m. to 5 p.m.), they can more readily be tonified. The Lung Channels' energy acts on the skin, muscles, and nerves found along their pathways.

WESTERN MEDICAL PERSPECTIVE

The action of inhaling air introduces oxygen into the lungs; exhaling expels carbon dioxide from the lungs. The heart pumps blood into the lungs. Blood passing through the lungs receives oxygen, and is then delivered back into the heart, where it is circulated throughout the body via the circulatory system.

PATHOLOGICAL MANIFESTATIONS

The Lung Channels' dysfunctions can result in chest and Lung diseases, as well as diseases on the radial side of the upper arm and palmar area of the hand.

The Lungs keep the pathway of air unobstructed and disseminate vital Qi throughout the body. If these functions are impeded, obstructions of the nose, coughing, dyspnea, and fullness of the chest may occur.

The Lungs cleanse the inhaled air and keep the Qi flowing downward. If these functions are impeded, coughing, asthma, oliguria (diminished amount of urine formation), and edema may occur.

Since the Lungs have their external orifice at the nose, stuffy nose, nasal discharge, and impairment of smell are common symptoms when the Lungs are being attacked by a pathogenic invasion of Wind and Cold.

THE LARGE INTESTINE CHANNELS

The Large Intestine Channels are Yang channels and flow externally from the hands to the head. These two rivers originate externally from the tips of the index fingers, ascend up the arms, and cross the shoulders, where they connect with the 7th cervical vertebra and then split into two branches. One set of branches (one branch from the left Lung and its corresponding branch from the right Lung) descends internally and spirally wraps the Lungs before moving through to permeate the Large Intestine. The other set continues ascending externally through the neck and cheek to the gums of the lower teeth. It curves around the upper lip and flows to the opposite side of the nose, where it connects with the Stomach Channels (Figure 6.10).

THE LARGE INTESTINE ORGAN

The Large Intestine's associated organ is the Lungs; its element is Metal. The main function of the Large Intestine is to receive food essence from the Small Intestine. The Large Intestine organ is said to govern humor (any fluid or semifluid substance in the body). It absorbs fluid that was separated by the Small Intestine and controls the transformation and transportation of solid waste in the body. The Large Intestine also controls the throat, teeth, and the drainage of the nose.

PSYCHO-EMOTIONAL ASPECTS

The Large Intestine relationship to the Lungs makes it equally affected by the emotions of sadness, grief, and worry. An energetic imbalance in the Large Intestine can result in physical weakness and provoke emotional introversion, accompanied by feelings of depression, irritability, discouragement, distress and apathy.

Strong emotions of fear or panic can produce an energetic-stool reflex reaction in the Large Intestine resulting in a spontaneous defecation.

THE LARGE INTESTINE'S ENERGY FLOW

The Large Intestine Channels have equally abundant amounts of Qi and Blood, acting equally on the body's energetic and nervous functions, as well as on physical substances and Blood functions. At the high-tide time period (5 a.m. to 7 a.m.), Qi and Blood abound in the Large Intestine organ and channels and can therefore be more easily dispersed or purged at this period; whereas during low-tide (5 p.m. to 7 p.m.), they can be more readily tonified. The Large Intestine Channels' energy acts on the skin, muscles, and nerves found along their pathways.

WESTERN MEDICAL PERSPECTIVE

The large intestine, sometimes called the "colon," is divided into four quadrants; the ascending, transverse, descending, and sigmoid or pelvic colon. The function of the large intestine is to reabsorb the fluid from the contents of indigest-


LI-20
LI-19
LI-18
LI-17
St-12
LI-16
LI-15
LI-14
LI-13
LI-12
LI-11
LI-10
LI-9
LI-8
LI-7
LI-6
LI-5
LI-4
LI-3
LI-2
LI-1

Figure 6.10. The Internal and External Qi Flow of the Large Intestine (LI) Channels

ible food residues moving through the intestines and to eliminate them from the body in the form of semisolid feces.

Whatever digestion takes place in the large intestine results from bacterial action. The fermentative bacteria (found in the middle part of the large intestine) and putrefying bacteria (found in the lower part of the large intestine) may produce toxic products, such as indole and skatol; however, if absorbed into the body, such bacterial decompositions undergo detoxification in the liver. In intestinal obstructions these bacterial decompositions are absorbed and eliminated in the urine in the form of indican.

PATHOLOGICAL MANIFESTATIONS

Dysfunctions in the Large Intestine Channels can result in diseases of the lower part of the face (including the nose, oral cavity, and teeth), throat, and front part of the neck, as well as disease of the back and radial sides of the upper extremities.

Tonification of the Large Intestine can be used to eradicate eye pain, toothache, earache, and to prevent hemorrhages, as well as to greatly reduce excessive menstrual bleeding.

Because of its relationship to the Lungs, the Large Intestine can be purged to treat coughing and asthma caused from Excessive Heat in the Lungs; whereas replenishing the vital Qi of the Lungs can cure constipation in debilitated patients.

The Large Intestines' energetic functional patterns generally relate to disturbances in bowel movements. Disturbances of the Large Intestine's energetic function usually gives rise to one of the two following complications:

1. Excess Conditions of the Large Intestines can result in symptoms of: Heat, Heat obstruction, Damp Heat, or Cold invading the Large Intestine.
2. Deficient Conditions of the Large Intestines can lead to an invasion of Cold or Dryness, and in severe cases of Deficiency, to the Collapse of the Large Intestine.

THE STOMACH CHANNELS

The Stomach Channels are Yang channels, and flow externally from the head to the feet (Figure 6.11). These two rivers originate externally from the lateral sides of the nose (LI-20), ascending upward to the base of the eye and bridge of the nose, where they meet the Bladder Channels. They then descend under the eyes, down the face, winding along the angle of the mandible, then ascend in front of the ears, following the anterior hairline till they reach the forehead. From the St-5 point, the primary branches on each side descend the neck and torso. Externally, these branches continue down the torso and legs and end at the lateral tips of the second toes. A second set of branches separate from the St-12 points and internally permeate the Stomach before spiral wrapping the Spleen and joining the primary channel branches at the St-30 points.

THE STOMACH ORGAN

The Stomach organ's associated organ is the Spleen; its element is Earth. The Stomach is considered the origin of the Body's Fluids. Its main function is to accept and decompose food. It separates the "clean" (pure) and "turbid" (impure) parts of ingested food and transfers the clean, energetically usable portion upwards to the Spleen, while sending the turbid unusable portion downward to the Small Intestine, to be further processed. Both the Stomach and the Spleen are considered the roots of Postnatal Qi and are often called The Ministers of Food Storage.

PSYCHO-EMOTIONAL ASPECTS

The Stomach influences the mental state; an Excess condition can agitate the mind and cause mental symptoms such as: mania or hypomania, confusion, severe anxiety, and hyperactivity.

THE STOMACH'S ENERGY FLOW

The Stomach Channels have equally abundant amounts of Qi and Blood, acting equally on the body's energetic and nervous functions, as well as on physical substances and Blood functions. At the high-tide time period (7 a.m. to 9 a.m.), Qi and Blood abound in the Stomach organ and channels, and can therefore be more easily dispersed or purged at this period; whereas during low-tide (7 p.m. to 9 p.m.), they can be more readily tonified. The Stomach Channels' energy acts on the skin, muscles, and nerves found along their pathways.


St-9
St-10
St-11
St-12
St-13
St-15
St-17
St-18
St-19
St-25
St-30
St-31
St-32
St-33
St-34
St-40
St-35
St-36
St-37
St-38
St-39
St-41
St-42
St-43
St-44
St-45
St-9
St-10
St-11
St-12
St-13
St-15
St-17
St-18
St-19
St-25
St-30
St-31
St-32
St-33
St-34
St-40
St-8
St-7
St-6
St-5
St-4
St-1
St-2
St-3
St-12
St-30

A second set of branches separate from the St-12 points and internally permeate the Stomach before spiral wrapping the Spleen and joining the primary channel branches at the St-30 points.

Figure 6.11. The Internal and External Qi Flow of the Stomach (St) Channels

WESTERN MEDICAL PERSPECTIVE

The stomach secretes gastric juice for food digestion. The proteins are converted into peptones; the stomach then regulates the passage of food to the other digestive organs.

PATHOLOGICAL MANIFESTATIONS

Diseases of the Stomach Channels include diseases of the face (nose, oral cavity, and teeth), throat, front of the neck, the abdomen, the frontal part of the legs and gastrointestinal area. Stomach disease can also induce certain psychiatric diseases.

Diseases of the Stomach organ are primarily caused by improper diet. To determine the root of the disease, the following five areas are considered:

1. The patient's Five Elemental Constitution and present state of health,
2. The type and energetic quality of the foods ingested (Hot or Cold), and whether the food is in season or out of season,
3. The scheduling of meals (This not only includes eating meals at regular times, but also eating a balanced meal, not too fast, and not too late at night),
4. The Yin/Yang balance of the types of food digested (This includes balancing the foods Five Tastes and Five Colors), and
5. The emotional factors surrounding meal time. This includes having the proper mental attitude (being relaxed and calm) and avoiding emotional distress (such as feeling rushed, upset, and so on).

The Stomach easily suffers from Excess patterns (e.g., Fire or Phlegm Fire), which in turn agitate the Shen. When the Shen is disturbed, it can cause manic symptoms such as: inappropriate laughter, pressured speech, unconscious talking, laughing, or singing, violent or otherwise inappropriate behavior (e.g., taking off one's clothes in public). In milder cases, symptoms may include mental confusion, severe anxiety, hypomania (a milder form of mania), and hyperactivity.

Since the Stomach has the function of sending the preliminarily digested food downward, an impairment of this function often causes vomiting.

THE SPLEEN CHANNELS

The Spleen Channels are Yin channels and flow externally from the feet to the torso (Figure 6.12). These two rivers originate externally from the medial tips of the big toes, ascend upwards along the inner thighs, then enter the abdomen (connecting to the CV-3 and CV-4 points) and further up the upper torso (connecting to the CV-12 point). The external Spleen Channels meet at the CV-12 point, enter the body, where the left channel flows into the Spleen, and then spirally wraps the Stomach organ. An internal branch ascends from the CV-12 point into the Heart. At the CV-12 point both left and right main channels meet and separate again to ascend through the diaphragm, up the torso and throat, alongside the esophagus, to reconnect at the base of the tongue. From the Sp-20 points external branches descend along the lateral aspects of the torso and terminate on the mid-axillary line in the seventh intercostal space.

THE SPLEEN ORGAN

The Spleen's associated organ is the Stomach; its element is Earth. In Traditional Chinese Medicine, the pancreas (a gland that produces insulin and is connected to the Spleen) is considered part of the Spleen/Stomach function. The Spleen organ is responsible for transforming food received from the Stomach into Gu Qi. The Gu Qi is then sent to the Liver and Kidneys to be "cooked" and further refined. The Spleen's main function is to govern or oversee this transportation and transformation of Gu Qi. It also controls the Blood by keeping it in the blood vessels, and governs the muscles, flesh, and limbs. The Spleen organ's energy opens externally at the mouth, controlling taste, and connects externally by the lips. The Spleen is sometimes called The Minister of Grains, because it is responsible for distributing what the Stomach has stored. Energetically, the Spleen controls the body's central cavity, and maintains the internal organs in their places.

PSYCHO-EMOTIONAL ASPECTS

The Spleen houses the body's thoughts and intentions (Yi), and is responsible for analytical thinking, memory, cognition, intelligence, and ideas. The Spleen is responsible for directing


Sp-20
Sp-20
Sp-19
Sp-19
Sp-18
Sp-18
Sp-17
Sp-17
Sp-21
Sp-21
Sp-16
Sp-16
CV-12
Sp-15
Sp-15
Sp-14
Sp-14
CV-4
Sp-13
Sp-13
Sp-12
Sp-12
CV-3
Sp-11
Sp-11
Sp-10
Sp-9
Sp-8
Sp-7
Sp-6
Sp-5
Sp-4
Sp-3
Sp-2
Sp-1
CV-12

The external Spleen Channels meet at the CV-12 point, enter the body, where the left channel flows into the Spleen, and then spirally wraps the Stomach organ. An internal branch ascends from the CV-12 point into the Heart. At the CV-12 point both left and right main channels meet and separate again to ascend through the diaphragm, up the torso and throat to reconnect at the base of the tongue.

Figure 6.12. The Internal and External Qi Flow of the Spleen (Sp) Channels

Connecting the Senses with the Sense Control of the Facial, Heart and the Abdominal Pakuas.

Repeat the facial pakua again: Kan-Li-Chen-Tui-Kun-Ken-Sun-Chien. This time, when you spiral the Tai Chi symbol as you chant Tai Chi, add the motion of the Yin coming in and the Yang going out. Your mouth is open projecting the sound of Yang into space. Your fingers are pointing out into space as well. With the sound of Yin your fingers are pointing in towards your forehead, which facilitates the inward movement of the energy. Picture a Tai Chi spiraling inside your brain, right behind your forehead. Point, spiral with your fingers saying Yin-Yang, Yin-Yang, Yin-Yang, and then Tai Chi, Tai Chi, Tai Chi. Continue saying it in your mind and feel the pakua deep inside your head (about 2-3 cm behind your forehead). All the senses are drawn together inside the center of the facial pakua (the senses' control point) and their energy is brought down to the Tai Chi of the lower abdominal pakua.



Sense Control at Mideyebrow

Crystal Room

Fig. 5.64 *Let the center of the brain, the heart and abdomen pakuas and all Tai Chis spiral together.*

memories to the Kidneys for short-term storage. The Kidneys will later transfer these memories to the Heart for long-term memory storage (see Chapter 12).

The Spleen's positive psycho-emotional attributes are trust, honesty, openness, acceptance, equanimity, balance, and impartiality; its negative attributes are worry, excessive thinking, pensiveness, obsessiveness, remorse, regret, obsessions, and self-doubt.

THE SPLEEN'S ENERGY FLOW

The Spleen Channels store more Qi and less Blood, acting more on energetic and nervous functions than on physical substance and Blood functions. At the high-tide time period (9 a.m. to 11 a.m.), Qi and Blood abound in the Spleen organ and channels, and can therefore be more easily dispersed and / or purged at this period; whereas during low-tide (9 p.m. to 11 p.m.), they can be more readily tonified. The Spleen Channels' energy acts on the skin, muscles, and nerves found along their pathway.

WESTERN MEDICAL PERSPECTIVE

The spleen is responsible for blood formation, filtration, and storage. In the embryo, all types of blood cells are formed by the spleen, but in the adult, only lymphocytes and monocytes are formed.

PATHOLOGICAL MANIFESTATIONS

The main diseases of the Spleen Channels include gastrointestinal dysfunctions (disturbances of digestion and absorption of food), and diseases of the tongue and throat. Spleen disorders also affect the inner side of the lower extremities along the Spleen's Channels.

Since the Spleen has the function of sending food essence upwards (to the Lungs), if this function is impeded, diarrhea or prolapse of the viscera may occur.

The Spleen also has the function of keeping the Blood flowing in the blood vessels; impairment usually leads to chronic hemorrhagic diseases.

The Spleen has the function of nourishing the flesh (muscles). A person with a healthy Spleen will usually have a healthy figure and a toned body; a diseased Spleen makes the patient lose muscle definition.

The Spleen nourishes the limbs. Strength of the limbs depends upon the nourishment guaranteed by the normal functioning of the Spleen. A diseased Spleen usually causes weakness of the limbs.

THE HEART CHANNELS

The Heart Channels are Yin Channels and flow externally from the torso to the hand (Figure 6.13). Three rivers originate internally from the Heart on each side of the body. The first bilateral set ascends and connects to the tissues connecting the eyeball. The second set descends, first to permeate the Pericardium, then descends further to connect with and spirally wrap the Small Intestine. The third set flows up into the Lungs, emerges externally at the armpits, then descends the medial aspect of the arms and ends on the inside of the little fingers.

THE HEART ORGAN

The main function of the Heart organ consists of controlling the Blood and vessels, regulating the Blood flow, perspiration, and housing the Shen. The Heart organ's energy opens externally at the tongue and is expressed through the complexion.

PSYCHO-EMOTIONAL ASPECTS

The Heart's associated organ is the Small Intestine; its element is Fire. Long-term memory, thinking, emotions, intimacy, cognition, intelligence, and ideas are all dominated by the function of the Heart. The Heart is sometimes called The Emperor, or "supreme controller of all Yin and Yang organs" (see Chapter 12). The Heart houses the body's Spirit (Shen). The Heart dominates sleep; if the Heart is strong the patient will fall asleep easily and sleep soundly. If the Heart is weak, the patient's mind will "float," resulting in an inability to fall asleep, disturbed sleep, or excessive dreaming.

The Heart's positive psycho-emotional attributes are love, joy, peace, contentment, propriety, insight, wisdom, orderliness, forgiveness, and courtesy. Its negative attributes are hate, guilt,



The first points of the Heart (Ht-1) are located in the armpits.

Ht-1
Ht-1
Ht-2
Ht-2
Ht-3
Ht-3
Ht-4
Ht-5
Ht-6
Ht-7
Ht-4
Ht-5
Ht-6
Ht-7
Ht-8
Ht-8
Ht-9
Ht-9

Figure 6.13. The Internal and External Qi Flow of the Heart (Ht) Channels

shock, nervousness, excitement, longing, and craving.

THE HEART'S ENERGY FLOW

The Heart Channels store more Qi than Blood; that is to say, its dominant action affects the energy. This energetic action controls the morale, the spirit of enterprise, and provides the energy required for respiration. At the high-tide time period (11 a.m. to 1 p.m.), Qi and Blood abound in the Heart organ and channels, and can therefore be more easily dispersed or purged at this period; whereas during low-tide (11 p.m. to 1 a.m.), they can be more readily tonified. The Heart Channel's energy acts on the skin, muscles, and nerves found along their pathways.

WESTERN MEDICAL PERSPECTIVE

The heart provides the propulsive force for circulating the blood throughout the vascular system. The blood circulation distributes the nutrients and oxygen needed for cell and tissue survival. The heart's propulsion also aids in the removal of wastes and other substances through the interconnecting blood vessels.

PATHOLOGICAL MANIFESTATIONS

The main diseases of the Heart Channels include diseases that exert pressure on the brain, eyes, or pharyngeal wall, as well as diseases of the Heart itself, and the lateral side of the chest. The Heart also relates to diseases of the ulnar palmar side of the arm.

The Heart is in charge of mental activities, including consciousness and thinking. Dysfunctions of the Heart can lead to insomnia, impairment of consciousness, amnesia, and psychosis.

The Heart and Kidneys have a mutual energetic relationship of supporting and checking each other. The Heart controls the body's Fire, while the Kidneys control the body's Water. Normally, the Fire of the Heart is sent down to warm the Kidneys, and the Water of the Kidneys is sent up to irrigate the Heart. If this balanced relationship breaks down (especially when the Kidney Water is insufficient to check the Heart Fire), a series of Fire symptoms of the Heart, such as hypertension, hyperactivity, palpitations, and insomnia may result.

Since the Heart has its external opening in the tongue, the condition of the Heart is reflected in the tongue:

1. A dark purple tongue indicates Blood Stasis of the Heart.
2. A pale tongue reveals Deficient Blood of the Heart.
3. An ulcer on the tongue reveals Excess Fire of the Heart.

THE SMALL INTESTINE CHANNELS

The Small Intestine Channels are Yang channels and flow externally from the hands to the head. These two rivers originate externally from the lateral tips of the little fingers (ulnar side) then ascend the arms to the shoulders, where they divide into two sets of branches. One set of branches descends the supraclavicular fossa internally, spiral wrapping the Heart, then continues down the esophagus, diaphragm, and Stomach, before permeating the Small Intestine (Figure 6.14).

The other set of branches ascends externally up the sides of the neck, then divides again into two more sets of branches at the cheek; one set will end at the ears, the other at the lateral sides of the nose and inner canthus of the eyes.

THE SMALL INTESTINE ORGAN

The Small Intestine temporarily stores partially digested food, absorbing the essential substances of the undigested food and a portion of the liquid content. It later transfers the residue (with a considerable amount of liquid) to the Large Intestine, and that is why it is said that the Small Intestine "governs liquid."

The Small Intestine is sometimes called "The Official in Charge of Separating the Pure from the Impure, because it separates the "clean" (reusable) food essence (Gu Qi) from the "dirty, turbid" food essence. The clean Gu Qi is transported throughout the body to nourish the tissues. The turbid is transported to the Large Intestine and Bladder organs to be further processed.

The Small Intestine's associated organ is the Heart; its element is Fire.

PSYCHO-EMOTIONAL ASPECTS

The Small Intestine influences the patient's


SI-19
SI-18
SI-17
SI-16
SI-15
SI-12
SI-14
SI-13
SI-10
SI-11
SI-9
SI-8 is located on the opposite side of the elbow.
SI-8
SI-7
SI-6
SI-5
SI-4
SI-3
SI-2
SI-1

Figure 6.14. The Internal and External Qi Flow of the Small Intestine (SI) Channels

mental clarity, judgement, and powers of discernment. The ability to distinguish relevant issues with clarity before making a decision is attributed to the Small Intestine.

THE SMALL INTESTINE'S ENERGY FLOW

The Small Intestine Channels store more Blood than Qi, and act more on the physical substances and Blood functions than on energy. At the high-tide time period (1 p.m. to 3 p.m.), Qi and Blood abound in the Small Intestine organ and channels, and can therefore be more easily dispersed and purged at this period; whereas during low-tide (1 a.m. to 3 a.m.), they can be more readily tonified. The Small Intestine Channels' energy act on the skin, muscles, and nerves found along their pathway.

WESTERN MEDICAL PERSPECTIVE

The small intestine's function is to receive the food mass from the stomach through the pylorus, the bile from the liver and gall bladder, and the pancreatic juices for digestion and absorption. The small intestine then passes what it doesn't absorb into the large intestine.

PATHOLOGICAL MANIFESTATIONS

Diseases of the Small Intestine Channels include diseases of the face, ear, cheek, lower jaw, the neck, and throat, as well as the dorsal ulnar side of the upper extremities.

In TCM, food and herbs are divided into Yin (Cold) or Yang (Hot) properties. The Small Intestine is easily affected by the type and temperature of food eaten. An excess consumption of "cold" and raw foods, for example, can create a Cold condition within the Small Intestines, while an excess consumption of "hot" foods can create a Hot condition.

Disturbances of the Small Intestine's energetic function usually gives rise to one of the following complications:

1. Excess Conditions of the Small Intestines can result in symptoms of: Full Heat, Qi pain, Knotted Qi, and the infestation of worms in the Small Intestine.
2. Deficient Conditions of the Small Intestines can manifest as: Deficient and Cold Small Intestine.

Pathologic Heart Heat may be transmitted to the Small Intestine, resulting in urodynia (painful urination) and hematuria (blood in the urine). Herbal prescriptions used to dispel Heat from the Heart are also effective in treating these urinary symptoms, which are alleged to be caused by dysfunctions of the Small Intestine.

THE BLADDER CHANNELS

The Bladder Channels are Yang channels and flow externally from the head to the feet. Two rivers originate externally from the inner canthus of the eyes, ascend upward over the head to join the Governing Vessel at the GV-20 point, where they divide into two additional branches that flow into each temple, and into the brain. From there, they then divide into two sets of branches (at the Bl-10 point), which descend the back, and internally connect to and spiral wrap the Kidneys, before they descend to permeate the Bladder. They continue externally down the thigh, the popliteal fossa at the back of the knee, calf, and foot, and end on the lateral sides of the tips of the little toes (Figure 6.15).

THE BLADDER ORGAN

The function of the Bladder is to remove water by Qi transformation. The Bladder receives the "impure" parts of the fluids separated by the Small Intestine and temporarily stores and transforms these fluids into urine, to discharge it when the Bladder is full. The Bladder and the Small Intestine work together to remove Body Fluids from the Lower Burner.

The Bladder Channels activate the Yang aspect of the Kidney's function and are sometimes called The Water District Officials or "the controllers of the storage of waste water." The Bladder's associated organ is the Kidney; its element is Water.

PSYCHO-EMOTIONAL ASPECTS

An imbalance in the Bladder can cause such psychological symptoms as habitual fear, lack of decision making capability and a diminished moral character. If the imbalance becomes chronic, it results in such emotional responses as jealousy, suspicion, and a holding on to long-standing grudges.


Bl-7
Bl-8
Bl-8
Bl-9
Bl-9
Bl-10
Bl-10
Bl-11
Bl-11
Bl-41
Bl-41
Bl-46
Bl-46
Bl-17
Bl-17
Bl-47
Bl-47
Bl-51
Bl-52
Bl-51
Bl-52
Bl-24
Bl-24
Bl-31
Bl-53
Bl-53
Bl-54
Bl-54
Bl-35
Bl-36
Bl-36
Bl-37
Bl-37
Bl-38
Bl-39
Bl-38
Bl-39
Bl-40
Bl-55
Bl-55
Bl-56
Bl-56
Bl-58
Bl-57
Bl-58
Bl-59
Bl-59
Bl-62
Bl-63
Bl-65
Bl-67
Bl-66
Bl-60
Bl-61
Bl-64
Bl-62
Bl-63
Bl-65
Bl-67
Bl-66


Bl-6
Bl-5
Bl-4
Bl-6
Bl-5
Bl-4
Bl-3
Bl-2
Bl-1
Bl-3
Bl-2
Bl-1



The internal flow of the Bladder Channels rushes into the lower back and lumbar area, passing through the renal arteries, to spiral wrap the Kidneys. From the Kidneys, the energy flows downward, following into the ureter, to permeate the Bladder.

Figure 6.15. The Internal and External Qi Flow of the Bladder (Bl) Channels

THE BLADDER'S ENERGY FLOW

The Bladder Channels regulate the functions of the Kidneys. The Bladder Channels store more Blood than Qi, acting more on the physical substances and the Blood functions than on the energy. At the high-tide time period (3 p.m. to 5 p.m.), Qi and Blood abound in the Bladder organ and channels, and can therefore be more easily dispersed and purged at this period; whereas during low-tide (3 a.m. to 5 a.m.), they can be more readily tonified. The Bladder Channels' energy acts on the skin, muscles, and nerves found along their pathway.

WESTERN MEDICAL PERSPECTIVE

The bladder is a reservoir for the urine received from the kidneys; it discharges urine from the body through the urethra.

PATHOLOGICAL MANIFESTATIONS

The main diseases of the Bladder Channels include:

- Diseases of the top of the head,
- Brain disorders,
- Disorders of the neck and back, especially the lumbar and sacral regions,
- Disorders of the back of the legs and thighs, and
- Disorders of the lateral side of the feet.

Diseases of the Bladder Organ manifest in changes in urine and urination; these changes will reflect a Deficient or Excess condition of the Bladder.

1. Deficient Conditions are attributed to Deficient Kidney Qi which affects the Bladder's ability to transform Qi. This dysfunction causes frequent urination, dribbling, or enuresis (involuntary discharge of urine).
2. Excess Conditions are attributed to Damp Heat in the Bladder, resulting in symptoms such as:
   - heat and pain during urination,
   - the short release of murky or reddish urine,
   - frequent difficulty in urination,
   - pus, or Blood in the urine, and
   - Bladder stones which cause a urinary block and painful distention of the lower abdomen.

The most common pathological factor in the diseases of the Bladder organ is due to the accumulation of Dampness (e.g., Damp Heat or Damp Cold). Other pathological conditions include: emotional fears, anxieties and insecurities, excessive sex, and Deficient and Cold Bladder.

THE KIDNEY CHANNELS

The Kidney Channels are Yin channels and flow externally from the feet to the torso (Figure 6.16). These two rivers originate externally from underneath the little toes, circling the inside of the heels, ascending through the medial aspect of the legs, where they merge and enter into the coccyx and lower lumbar vertebrae. Dividing again, one branch permeates the Kidneys, while the other branch continues ascending into the cerebral cortex. From the Kidney organs, two additional sets of channels internally emerge. One set descends and spiral wraps the Bladder. The other set ascends into the Liver, diaphragm, and Lungs, then spiral wraps the Heart and travels up the throat, stopping at the root of the tongue (Figure 6.17).

THE KIDNEY ORGANS

The Kidneys store Jing substances, produce Marrow, and control the development of the bones. They also control respiration, reproduction, growth and development, and govern the Body Fluids. The Kidney Jing is the biological basis for the woman's menstrual blood. The Kidneys are the root of the Yin and Yang Qi of all the body's organs. The Kidneys energetically open externally through the ears and are sometimes called The Minister of Ingenuity and Vitality, or "the controller of water" (see Chapter 12).

The Kidney organs' associated organ is the Bladder and it's element is Water. Kidney Yin Qi flows to the Liver, Heart, and Lungs. It is responsible for the body's fluid-like essences and rules the birth, growth, maturation, and reproduction cycle. Kidney Yang Qi flows to the Spleen, Liver, Heart, and Lungs. It supports the Yang of all the body's organs via the Mingmen.

PSYCHO-EMOTIONAL ASPECTS

The Marrow produced from the Kidney Jing flows into the brain. The thinking ability is strengthened when Qi and Blood in the cerebral



From the Kd-16 points, the Qi follows the Belt Vessel and enters into and permeates the Kidneys. From the Kidneys, the Qi descends into the ureters, where it spirally wraps the Bladder.

The internal flow of the Kidney Qi passes the GV-1 point, moving up and down the spine, and exiting the body at the Kd-11 points. From Kd-11, the energy ascends superficially up to the Kd-16 points.

Figure 6.16. The Internal Flow of the Kidney Qi


Kd-27
Kd-27
Kd-24
Kd-24
Kd-23
Kd-23
Kd-22
Kd-22
Kd-21
Kd-21
Kd-17
Kd-17
Kd-16
Kd-16
Kd-11
Kd-11
Kd-10
Kd-9
Kd-8
Kd-7
Kd-3
Kd-1
Kd-2
Kd-4
Kd-6
Kd-5

Figure 6.17. The Internal and External Qi Flow of the Kidney (Kd) Channels

cortex are abundant. With the increase of thinking activity, a circle of light develops within the body's Taiji Pole. The individual's innate intelligence (Yuan Shen) is represented by the intensity of light. The degree of accumulated spiritual energy is reflected by the number of light circles developed within the Taiji Pole. These circles of light can be best observed when first waking. By placing slight pressure on the external eye lids the inner light of the Taiji Pole is projected onto the optic nerves, reflecting an image of the circle of light. If the circle of light is complete, it reflects a strong, healthy condition. If the circle of light is dark within its center (similar to a doughnut), this reflects a Deficient condition. If the circle of light is broken or interrupted, it reflects an extreme Deficiency (Figure 6.18).

The "memory zone," as well as the "thought center" are also located in the cerebral cortex and will not develop until the Kidney Channels travel through the spine, along with the Liver Channels, to reach the cortex. When the Qi of these two channels is abundant, the memory function is keen.

The Kidneys house the body's will power (Zhi). They control short-term memory and store data. The Kidneys provide the capacity and drive for strength, skill, and hard work. A patient with strong Kidneys can work hard and purposefully for long periods of time. Consequently, when the Kidneys are in a state of disharmony, the patient can sometimes be driven to a state of excessive-compulsive working habits (a workaholic). A patient with weak Kidneys will lack strength and endurance.

The Kidney's positive psycho-emotional attributes are wisdom, rationality, clear perception, gentleness, and self-understanding. The negative attributes are fear, loneliness, insecurity, and shock (which attacks the Heart first then descends into the Kidneys to become fear).

THE KIDNEYS' ENERGETIC FLOW

The Kidney Channels store more Qi than Blood, acting more on energetic and nervous functions than on physical substances and Blood functions. At the high-tide time period (5 p.m. to 7 p.m.), Qi and Blood abound in the Kidney organ and channels, and can therefore be more easily dispersed and purged at this period; whereas during low-tide (5 a.m. to 7 am.), they can be more readily tonified. The Kidney Channels' energy acts on the skin, muscles, and nerves found along their pathways.



Figure 6.18. The individual's Yuan Shen is represented by the intensity of the light, and the degree of accumulated spiritual energy is reflected by the number of light circles developed within the Taiji Pole.

WESTERN MEDICAL PERSPECTIVE

The function of the kidneys is to regulate water and electrolytes and to process the body's urine.

PATHOLOGICAL MANIFESTATIONS

Kidney Channel diseases cause general deterioration of the entire body, weakness in the lower extremities, lumbar pain, and hot sensations deep inside the feet.

The Kidneys open through the urogenital orifices and the anus. The energetic condition of the Kidneys can be, partially reflected by the condition of the patient's urination and defecation; in males, this includes the ejaculation process.

Since the Kidneys are responsible for concentration and memory retention, poor concentration and loss of memory are common symptoms of Kidney hypofunction.

THE PERICARDIUM CHANNELS

The Pericardium Channels are Yin channels and flow externally from the torso to the hands. These two rivers originate internally from the center of the chest, flowing out of the Pericardium. They descend through the center of the body, spi-

Blending all the Energy of the Organs and Senses together in the Cauldron

Look down to your center in the Tan Tien and focus on the pakua on the back and on the right and the left pakua. When you focus on them, they will just start spiraling on their own. Look down into your center, into the cauldron and start spiraling the Tai Chi symbol in the center of your cauldron while chanting Tai-Chi, Tai-Chi, Tai-Chi. Rest. Continue to spiral with only your mind and feel that the energy of your senses and organs is coming right down to your center, where all the energy blends into one central energy. Rest. Spiral the energy in your abdomen. Smile to this energy and feel very calm and peaceful.



Fig. 5.65 *Draw all the sense into the center of the Pakua and Tai Chi.*


Pc-1
Pc-1
Pc-2
Pc-2
Pc-3
Pc-3
Pc-4
Pc-4
Pc-5
Pc-5
Pc-6
Pc-6
Pc-7
Pc-7
Pc-8
Pc-8
Pc-9
Pc-9

Figure 6.19. The Internal and External Qi Flow of the Pericardium (Pc) Channels

ral wrapping the Upper, Middle, and Lower Burners. Two rivers surface and branch externally by the nipples to proceed down the center of each arm, ending at the tips of the middle fingers. A second branch arises from the center of each palm at the Pc-8 point and flows into the ring fingers to connect with the Triple Burner Channels (Figure 6.19).

PERICARDIUM ORGAN

The Pericardium is associated with the Triple Burners; its element is Fire. The Pericardium is not considered an independent organ, as much as a protective covering for the Heart, that protects the Heart from pathogenic factors. The Pericardium activates, energizes and controls the Yin channel's distribution of the Kidney Yang Qi to the Yin organs. Along with the Heart, it governs the Blood, and houses the Shen. The Pericardium is considered the Prime Minister, or the official who protects the heart.

PSYCHO-EMOTIONAL ASPECTS

The Pericardium has a powerful influence on the patient's mental and emotional states. Its goal is to "create feelings of joy and/or pleasure for the emperor (Heart)."

THE PERICARDIUM'S ENERGY FLOW

The Pericardium Channels have an affect on the body's circulation of Blood. They are considered the "mother of Yin" and are connected to the Mingmen. The Pericardium Channels store more Blood than Qi, acting more on the physical substance and Blood functions than on the energy. At the high-tide time period (7 p.m. to 9 p.m.), Qi and Blood abound in the Pericardium organ and channels and can therefore be more easily dispersed and purged at this period; whereas during low-tide (7 a.m. to 9 a.m.), they can be more readily tonified. The Pericardium Channel's energy acts on the skin, muscles, and nerves found along their pathways.

WESTERN MEDICAL PERSPECTIVE

The function of the pericardium is to provide a protective covering for the heart. It contains a thin serous fluid that allows the heart to work in a relatively friction-free environment.

PATHOLOGICAL MANIFESTATIONS

The main diseases of the Pericardium Channels include diseases of the Heart, front of the chest, major blood vessels, and diseases on the midline to upper palmar side of the upper extremities. Mental abnormalities may also manifest.

THE TRIPLE BURNER CHANNELS

The Triple Burner Channels are Yang channels that flow externally from the hands to the head. These two rivers originate externally from the tips of the ring fingers and ascend along the lateral aspect of the arms, over the shoulders to the clavicles, then branch internally and spiral wrap the Pericardium. They circle the diaphragm and permeate the Upper, Middle, and Lower Burners. A set of branches originate internally from the chest CV-17 point at the Heart, or center of the Middle Dantian. Flowing upwards, these branches emerge from the supraclavicular fossa at the St-12 points to ascend up the neck, head, and then circle the ears. Another set of branches flows downward to the cheek, terminating in the infraorbital region; the other set ends above the ears, by the outer canthus of the eyes.

THE TRIPLE BURNERS ORGAN

The Triple Burners' associated organ is the Pericardium; its element is Fire. The Triple Burners are not regarded as an independent organ, but are assigned to specific energy areas, and are a part of the function of the Yin and Yang organs. The function of the Triple Burners' energy is to produce Heat, and to regulate the body's temperature. This Heat is increased through such meditative disciplines as the Microcosmic Orbit (which connects the Governing and Conception Vessels), and the Macrocosmic Orbit (which connects all Twelve Primary Channels with the Governing and Conception Vessels). The main function of the Triple Burners (Figure 6.20) is to regulate the general ingestion and digestion of food and fluids throughout the body.

The Triple Burners are known as The Official of Balance and Harmony, because they govern Water metabolism, control the production of Wei


TB-21
TB-22
TB-23
TB-20
TB-19
TB-18
TB-17
TB-16
TB-15
TB-14
TB-13
TB-12
TB-11
TB-10
TB-9
TB-8
TB-6
TB-7
TB-5
TB-4
TB-3
TB-2
TB-1
St-12
CV-17

The internal flow of the Triple Burner Channels moves from St-12 down to CV-17, where it disperses into the chest and envelops the Pericardium. From the Pericardium, as the energy flows down through the diaphragm, it circulates through the chest and permeates the Triple Burners (a continuing branch flows upward to the St-12 points).

Figure 6.20. The Internal and External Qi Flow of the Triple Burners (TB) Channel

Qi, and transport Yuan Qi from the Kidneys to all the other organs of the body. This name refers to the Triple Burners' role in regulating metabolic functions, as well as their production of Qi, Blood, Body Fluids, and waste.

The Triple Burners' energy is composed of Zong Qi (Essential Qi). The Zong Qi assists the Heart in circulating the Blood and the Lungs in respiration. The Zong Qi also assists in conveying the Ying Qi (Nourishing Qi) to nourish the Blood, organs, and tissues of the body, as well as strengthens the Wei Qi (Protective Qi) that protects the external body (see Chapter 14).

1. The Upper Burner

   The Upper Burner is formed from the Fire created from the combined energies of the Heart, Pericardium, and both Lungs. The Upper Burner's energy is housed from the area of the head, throat, and upper chest, to the diaphragm. The Upper Burner is responsible for respiratory and cardiac functions. It moves the body's finer energy, circulating and distributing nutrients and Qi throughout the body like a "mist."

2. The Middle Burner

   The Middle Burner is formed from the Fire created from the combined energies of the Stomach, Spleen, pancreas, and Gall Bladder. The Middle Burner's energy is housed from the upper abdomen (the diaphragm) and the umbilicus.

   The Middle Burner is responsible for digestion, fermentation, and transformation of food and drink into nutrients for distribution. In the Middle Burner area, the Small Intestine connects downward to the Bladder. The Small Intestine transforms waste, that is then sent down to the Large Intestine, and also distills the body's fluids, sending them down to the Bladder.

   The Ying Qi (Nourishing Qi) of the Middle Burner receives its nourishment from the Stomach and Spleen. The Spleen extracts Gu Qi from the food "prepared" by the Stomach, churning the food essence into "foam." The Spleen refines this energetic foam and sends the processed Gu Qi to the Lungs. The Lungs further refine the Gu Qi, sending the impure part to the Kidneys (for additional refinement of the Gu Qi). The Kidneys return the Clean Qi to the Lungs and send the turbid part to the Bladder to be expelled from the body. The Qi from the air mixes with the Gu Qi in the Lungs to produce Zong Qi. The Lungs circulate the refined Gu Qi in the form of vapor or mist which is housed in the Upper Burner. The Heart then produces Blood from this vapor.

3. The Lower Burner

   The Lower Burner is formed from the Fire created from the combined energies of the Liver, Kidneys, Bladder, Intestines, and genitalia. The Lower Burner's energy is housed in the area which starts just below the umbilicus and extends to the lower perineum.

   The Lower Burner is responsible for the reproductive functions and for the filtering and elimination of waste products (Figure 6.21). It moves the body's coarser energy, acting as a "channel for water."

The Triple Burners contribute to the process of the three stages of transformation and ais in the distribution of Ying and Wei Qi throughout the body as follows:

- After the Gu Qi (food energy) has been separated into Clean and Turbid Qi, the Upper Burner releases the body's clean Wei Qi, directing it to the Lungs;
- the Middle Burner releases the body's clean Ying Qi, directing it to all of the body's organs and tissues; and
- the Lower Burner releases the body's Body Fluids, directing the turbid part to the Bladder.

PSYCHO-EMOTIONAL ASPECTS

The Triple Burners are considered the Ambassadors or "intermediaries" for the body's Yuan Qi. On a psychological level, they can be used to move Qi and lift depression derived from stagnation of Liver Qi.

When the Triple Burners, which regulate the consciousness, are full, the consciousness becomes stable and the Mind's intent is benevolent and kindhearted. The Triple Burners are also linked


Dispersing
Pure
Body Fluids To Skin & Muscles
Body Liquids To Whole Body
3rd Dantian
Upper Burner
Lungs
Ascending Steam To Moisten Lungs
Pure
Spleen Transports Pure Upwards
Descending Fluids & Qi
2nd Dantian
Spleen Stomach
Middle Burner
Stomach Transports Impure Downwards
Left Kidney
Kidneys
Right Kidney
1st Dantian
Small Intestine
Pure
Lower Burner
Ming Men Fire
Impure
Large Intestine
Re-Absorbed
Bladder
Pure
Impure
Impure
Feces
Urine

Figure 6.21. The Metabolic Functions of the Triple Burners are divided into three parts or functions: the Upper Burner, Middle Burner, and Lower Burner. These different functions of the Triple Burners control the movement of various types of Qi in the three stages of energy production:

Receiving—The Upper Burner, also known as mist, includes the organs from the diaphragm upwards (the Pericardium, head, throat, Lungs, and Heart). The Upper Burner assists the Spleen in directing the body's clean fluids upwards and helps the Lungs in dispersing and scattering the fluids to the skin and muscles.

Rotting and Ripening—The Middle Burner, also known as the muddy pool, and includes the area between the diaphragm and umbilicus (Stomach, Spleen, and Gall Bladder). The Middle Burner assists the Stomach in the transformation and transportation of Fluids and Liquids and in directing the impure part downwards.

Excreting—The Lower Burner, also known as the drainage ditch, includes the organs below the umbilicus (Liver, Kidneys, Intestines, and Bladder). The Lower Burner assists the Small Intestine, the Blood, and the Kidneys in transforming and transporting liquids and wastes.

with the Heart and Pericardium and are affected by the emotion of joy.

When the energy of the Heart is strong and pure (without guilt), and the desires and thoughts of an individual are at peace, then the energy of the body's sexual essence (Jing) will spread into the Triple Burners, and the Blood will flourish within the individual's vessels. If the "fire of desire" is allowed to Heat and combine with the energy of the Triple Burners, the energy of the individual's sexual essence will overflow, mixing itself with the energy of the Mingmen and will leave the body via the reproductive organs and tissues. This leads to Jing and Qi depletion.

THE TRIPLE BURNERS' ENERGY FLOW

The Triple Burner Channels store more Qi than Blood, and act more on the energetic and nervous functions of the body than on physical substance and Blood functions. At the high-tide time period (9 p.m. to 11 p.m.), Qi and Blood abound in the Triple Burner Channels, and can therefore be more easily dispersed and purged at this period; whereas during low-tide (9 a.m. to 11 a.m.), they can be more readily tonified. The Triple Burner Channels' energy acts on the skin, muscles, and nerves found along their pathways.

WESTERN MEDICAL PERSPECTIVE

Western medicine recognizes no translation of, or reference to the Triple Burners.

PATHOLOGICAL MANIFESTATIONS

The main diseases along the Triple Burner Channels involve the face, ear, cheek, larynx, and neck. Diseases of the Triple Burner Channels also include disorders of the back of the upper extremities from the midline to the upper arm and forearm.

When diagnosing problems due to dysfunctions of the Triple Burners, the Qigong doctor considers the following.

1. A blockage of the Wei Qi located within the Upper Burner causes an impairment of the Lungs' dispersing function. This can result in the invasion of the Lungs by External Evils (e.g., Wind and Heat, etc.), that penetrate the Pericardium (which corresponds to the initial stage of externally contracted Heat diseases).
2. A blockage of the Ying Qi located within the Middle Burner causes an impairment of the Spleen's transporting function. This can result in gastrointestinal Heat stagnation, and cause Spleen and Stomach Damp Heat (which corresponds to the second stage of externally contracted Heat diseases).
3. A blockage of the Body Fluids located within the Lower Burner causes an impairment of the Bladder's transformation function. This results in the deep penetration of Toxic Evils, weakening the body's Kidney Yin. This in turn can cause Deficient Liver Blood, and Wind stirring due to Empty Yin (this corresponds to the advance stages of externally contracted Heat diseases).

UNDERSTANDING CHANNEL PATHOLOGY

Channel pathology is the oldest of all the modes of pathological pattern classification, dating back to the Spiritual Axis from the *Yellow Emperor's Classics on Internal Medicine*. In understanding a channel's pathology, the Qigong doctor takes into consideration several aspects of the patient's energy flow (i.e., the channels are viewed as exterior, whereas the organs are viewed as interior). Channel pathology is often related to organ disturbances, but it can also be distinct from organ pathology (Figure 6.22).

The disease of one channel may cause disease in other channels and organs. Likewise, tonification of one channel may cause a tonification of other channels and organs.

THE FOUR CAUSES OF CHANNEL PATHOLOGY

1. The Invasion of External Pathogens such as Cold, Wind, Heat, and Damp leads to channel pathology. The exogenous pathogenic factors often settle in the joints, causing Bi Syndrome (painful obstruction). Channel pathology is quite closely related to joint pathology. In Traditional Chinese Medicine, joints are important to the circulation of Qi and Blood. Qi and Blood gather and concentrate in the joints. Qi enters and exits the channels at the joints. The Five Source Points, also called Shu Points (see Chapter 8), are usually located on

of near the joints. It is at these points that the External pathogenic influences may enter the body and settle in the joints. These External pathogenic influences upset the Yin and Yang balance and block the flow of Qi and Blood, causing pain and swelling. The body's joints are also affected by Deficient Qi and Blood, causing local weakness and pain from lack of movement.

2. Physical strain or the overuse of certain joints can cause local stagnation that creates pain and weakness.
3. Injuries, trauma, and strain can cause local stagnation resulting in stiffness, bruising, and pain.
4. Internal organ disharmonies may also affect the channels.

DIFFERENTIATION BY CHANNEL FULL/EXCESS AND EMPTY/DEFICIENT

When a channel is too full, its pattern characteristics are that of intense pain, stiffness, contractions, and cramps. A red color along the flow of the channel indicates Heat; a bluish color along the flow of the channel indicates Cold.

When a channel is Empty, its pattern characteristics are that of a dull ache, weakness in the muscles, numbness, and muscle atrophy along the channel.

DIFFERENTIATION OF CHANNEL PATTERNS BY SPECIFIC CHANNELS

This clinical overview of the body's channels was originally expressed through the knowledge found in the Spiritual Axis (for more in-depth dissertation please see *The Foundations of Chinese Medicine* by Giovanni Maciocia).

1. The diseases of the Gall Bladder Channels may cause: Alternating chills and fever, headache, acute onset of deafness, pain in the hip and the sides of the body, pain along the lateral sides of the legs, and pain and distention of the breasts.
2. The diseases of the Liver Channels may cause: Headache, pain and swelling of the eyes, and cramps in the legs.
3. The diseases of the Lung Channels may cause: Fever, aversion to cold, stiffness in the chest, pain in the shoulders, clavicle, and arms.
4. The diseases of the Large Intestine Channels may cause: Sore throat, toothache, nosebleed, runny nose, swollen and painful gums, swollen eyes, and pain along the channels.
5. The diseases of the Stomach Channels may cause: Pain in the eyes, nosebleed, neck swelling, facial paralysis, cold legs and feet, and pain along the channels.
6. The diseases of the Spleen Channels may cause: Vaginal discharge, weakness of the leg muscles, and a cold feeling along the channels.
7. The diseases of the Heart Channels may cause: Pain in the eyes, pain along the scapula, and pain along the inner side of the arms.
8. The diseases of the Small Intestine Channels may cause: Pain and stiffness in the neck, and pain along the lateral side of the scapula, elbow, and arms.
9. The diseases of the Bladder Channels may cause: Fever and aversion to cold, headache, stiff neck, pain in the lower back, pain in the eyes, pain in the backside of the leg along the channels.
10. The diseases of the Kidney Channels may cause: Lower back pain and pain in the sole of the feet.
11. The diseases of the Pericardium Channels may cause: Stiff neck, contraction of the elbow and hand, and pain along the course of the channels.
12. The diseases of the Triple Burner Channels may cause: Alternating chills with fever, acute onset of deafness, pain and discharge from the ear, pain at the top of the shoulders, pain in the elbow, and pain along the course of the channels.

SUMMARY OF TWELVE PRIMARY CHANNEL PATHOLOGY

The clinical significance of studying the Twelve Primary Channels is evident through the observation of certain pathological manifestations that indicate specific patterns peculiar to that channel and its internal organ. The quality, quantity and proportions of Qi and Blood circulation

Twelve Primary Channels	**Pathologies**
Bladder	• Diseases of the top of the head, brain, neck, back, lumbar and sacral region • Diseases of the back of the leg and thigh and the external side of the foot
Gall Bladder	• Pain in upper right- and left-quadrants of abdomen • Diseases of the head, face, eye, ear • Diseases of the external sides of the lower extremities
Heart	• Diseases that exert pressure on the brain, eyes, or pharyngeal wall • Diseases of the Heart and lateral side of the chest • Diseases of the ulnar palmar side of the upper extremities • Insomnia, impairment of consciousness, amnesia, and psychosis
Kidneys	• Diseases that cause general deterioration of the entire body • Weakness in the lower extremities and lumbar pain • Hot sensations deep inside the feet
Large Intestine	• Diseases of the lower part of the face, nose, oral cavity, teeth, throat, and front part of the neck • Diseases of the back and radial side of the upper extremities
Liver	• Swelling and a distended sensation of the hypochondrium • Diseases of the lower abdomen and genital organs
Lungs	• Chest and Lung diseases • Diseases on the radial side of the upper arm and palmar area of the hand
Pericardium	• Diseases of the Heart, front of the chest, major blood vessels • Diseases of the midline to upper palmar side of the upper extremities • Mental abnormalities
Small Intestine	• Diseases of the face, ear, cheek, lower jaw, neck, and throat • Diseases of the back ulnar side of the upper extremities
Spleen	• Diseases of the tongue and throat • Gastrointestinal diseases (disturbances of digestion and absorption of food) • Diseases of the inner side of the lower extremities
Stomach	• Diseases of the face, nose, oral cavity, teeth, throat, and front of the neck • Diseases of the abdomen, the frontal part of the lower extremities and gastrointestinal area • Certain psychiatric diseases
Triple Burners	• Diseases of the face, ear, cheek, larynx, and neck • Diseases of the back of the upper extremities from the midline of the torso to the upper arm and forearm

Figure 6.22. Pathologies of the Twelve Primary Channels

through each of the Twelve Primary Channels has a vital impact on all the body's organ systems. These Qi and Blood flow concepts define the reciprocal relationships existing between the body's internal organs, channels, and energetic points situated throughout the body.

Figure 6.22 describes some of the most common Twelve Primary Channel pathologies, and their clinical manifestations along the "root and branches" of these channels.

The term "root and branch," is used to describe the difference between the medial and lateral, upper and lower orientations of the channels and their points of origin. They are also used to describe the progression of a disease, as well as the priorities and sequence of the Qigong doctor's treatment.

Specifically, the word "branch" is used to describe the channels' flow of Qi and Blood and the progression and direction of a disease. The word "root" is used to described the channels' internal organ, or the origin of a disease.

CHAPTER 7
THE EIGHT EXTRAORDINARY VESSELS AND COLLATERALS

THE EIGHT EXTRAORDINARY VESSELS

Extending from the body's Taiji Pole are the Three Dantians, Five Jing Shen, and the Eight Extraordinary Vessels. These energy systems feed all the vital organs and the body's Twelve Primary Channels. The Eight Extraordinary Vessels are so called because of they differ in energetic function from the Twelve Primary Channels. These eight vessels have an extraordinary ability to regulate the deeper energetic reservoirs of the body. They are the first vessels (or channels) to form in the developing fetus, and are sometimes called the Eight Ancestral Channels, Eight Prenatal Channels, Eight Preheaven Channels, or Eight Psychic Channels.

These vessels represent the merging of the mother's and father's energy, and the linking of the body's prenatal and postnatal energies. They functionally connect to the Twelve Primary Channels and circulate the Jing Qi (Essence Energy) throughout the body.

The energetic expansion and contraction of the Eight Extraordinary Vessels affects the creation and development of the baby's tissues up until the time of birth. In energetic embryology, the three-dimensional space of the impregnated egg is viewed as an object that can be described by eight different surfaces along four axes. Each of the Eight Extraordinary Vessels corresponds with one of these directions:

- anterior/posterior—Governing and Conception Vessels
- superior/inferior—Yin and Yang Linking Vessels
- right/left—Yin and Yang Heel Vessels
- interior/exterior—Thrusting and Belt Vessels

THE FUNCTION OF THE EIGHT EXTRAORDINARY VESSELS

The Eight Extraordinary Vessels have neither a direct connection nor an internal/external relationship with the internal organs. Similar to the Three Dantians' function of distributing the body's energy, these Eight Extraordinary Vessels are also reservoirs that regulate the distribution and circulation of Jing and Qi inside the body. They are the foundation of the body's energy, bridging the Yuan Qi (Original Prenatal Energy) with the body's postnatal energy.

The Eight Extraordinary Vessels serve as reservoirs of Qi. When these reservoirs become full, the energy overflows into the center channel or Taiji Pole. This stimulation of the Taiji Pole expands consciousness and increases perceptual intuition.

The Eight Extraordinary Vessels have five main functions: They serve as reservoirs of Qi, store and circulate Jing Qi, circulate the Wei Qi, regulate the body's life cycles, and integrate the six primary Yang organs with the Six Extraordinary Organs and with the Kidneys.

1. They Serve as Reservoirs of Qi. If the Qi flow of the Twelve Primary Channels becomes Excessive, they overflow into the Eight Extraordinary Vessels, which act as Qi reservoirs, receiving the Excess Qi for storage and distribution, while at the same time regulating the energy flow. If the Qi flow of the Twelve Primary Channels becomes Deficient, they can draw from the reservoirs of energy stored within the Eight Extraordinary Vessels which again regulate the body's energy flow, bringing it back into balance.
2. They Store and Circulate Jing Qi. The Eight Extraordinary Vessels draw their energy from the Kidneys and are responsible for storing and circulating the body's Jing Qi throughout the tissues, particularly to the skin and hair and to the Six Extraordinary (Curious) Organs, also known as the Six Ancestral Or-

Expanding the Pakua in the Universe.

The power of the symbol is the power of the throat, the power of the word. The forces of the universe are Yin and Yang forces and the kua is a very ancient symbol of power. When you project the pakua out, using the pakua breathing, you connect to the Yin and the Yang power in the universe. When you breathe to the kua out there in space and connect to it, you will feel it connect to the kua in your abdomen as well.



Fig. 5.66 *Pakua in the Universe*



Fig. 5.67 *Feel the Pakua Breathing and Pulsating.*

gans. The Six Extraordinary Organs are the Brain, Bone, Marrow, Blood, and Gall Bladder (also included is the Uterus in women).

3. They circulate the Wei Qi (Protective Energy) to protect the body against invasion by External pathogens. The Governing, Conception, and Thrusting Vessels are primarily responsible for circulating the body's Wei Qi over the thorax, abdomen, and back.

   The Eight Extraordinary Vessels provide the link between the Kidneys Jing and the Wei Qi. Although the Wei Qi is circulated by the Lungs, its root is in the Kidneys. This illustrates how the Kidneys play an important role in supporting the Lungs function of circulating the body's Wei Qi. The Kidneys function on the Wei Qi field and therefore the immune system can become vulnerability to pathogenic factors, as well as in causing allergic diseases, e.g., asthma. It also demonstrates why the Kidneys are always at the root of latent Heat syndromes (chronic fatigue), caused by Kidney Deficiency.
4. The Eight Extraordinary Vessels regulate the body's Life Cycles. In the first chapter of *the Yellow Emperor's Classic of Internal Medicine*, the life changes in women (every seven years) and men (every eight years) are governed by the Conception and Thrusting Vessels. These life cycles are related to the body's Jing and the Eight Extraordinary Vessels' role in moving and circulating the body's Jing (see Chapter 13).
5. They Integrate the Six Extraordinary (Curious) Organs with the Six Primary Yang Organs and the Kidneys. The Eight Extraordinary Vessels provide the link between the body's brain, uterus, blood vessels, Gall Bladder, Marrow and bones, and the body's internal energy flow.
   a. The Brain is Regulated by the Governing Vessel and the Yin and Yang Heel Vessels.
   b. The Uterus is regulated by the Thrusting and Conception Vessels.
   c. The Blood Vessels are regulated by the Thrusting Vessels.
   d. The Gall Bladder is regulated by the Belt Vessel.
   e. The Marrow is regulated by the Thrusting Vessels.
   f. The Bones are regulated by the Thrusting and Conception Vessels.
6. They Integrate the Four Seas. The *Magic Pivot (Ling Shu, Hai Lun)* states, "People have Four Seas... the Sea of Marrow, the Sea of Blood, the Sea of Qi, and the Sea of Grain and Water." The Eight Extraordinary Vessels provide the link between the body's Four Seas and the body's internal energy flow.
   a. The Sea of Marrow is the brain, and it is related to the Governing Yin and Yang Heel Vessels. The Sea of Marrow points are located on the Governing Vessel GV-16 and GV-20. When the Sea of Marrow is Deficient, there will be headaches and dizziness.
   b. The Sea of Qi is located in the chest of the center, and is regulated by the Conception Vessel CV-17. Some Medical Qigong schools maintain that there are two reservoirs of Qi: the Middle Dantian, being the Sea of Postnatal Qi, and the Lower Dantian, being the Sea of Prenatal Qi (which is regulated by the Qihai CV-6 point). When the Sea of Qi is in Excess, there is a feeling of fullness in the chest, dyspnea (urgent breathing), and a red complexion. When the Sea of Qi is Deficient, there is weak energy and insufficient speech.
   c. The Sea of Nourishment (also known as the Sea of Grain and Water) is the Stomach, and it is regulated by the Thrusting Vessels, which are accessed by the St-30 points. When the Sea of Water and Grain is in Excess, there is a feeling of fullness in the abdomen. When the Sea of Water and Grain is Deficient, there is a feeling of hunger with an inability to eat.
   d. The Sea of Blood (also known as the Sea of the Twelve Primary Channels) is related to the Thrusting Vessels, the Liver, and Xuehai Sp-10 points. The points can

also be accessed through Bl-11, St-37, and St-39. When the Sea of Blood is in Excess, the body feels big; When the Sea of Blood is Deficient, the body feels small.

THE EIGHT EXTRAORDINARY VESSELS AND MEDICAL QIGONG THERAPY

The energetic pathways, functions and use of the Eight Extraordinary Vessels and points in Medical Qigong are often quite different than those taught in acupuncture colleges, even though they may sometimes bear the same names.

Most acupuncturists, with the exception of some Japanese researchers, often pay little attention to the Eight Extraordinary Vessels in diagnosis and treatment. One Medical Qigong doctor from China has claimed that a study done in China showed that the Eight Extraordinary Vessel treatments were far more effective than those of the Traditional Chinese medical protocols. The results, however, were not released because officials did not want to disturb the TCM institutional operations. The reason Medical Qigong makes use of the Eight Extraordinary Vessels, is that they are much easier to access through Qi emission and Medical Qigong self-regulation prescriptions than through acupuncture therapy.

The Eight Extraordinary Vessels have been of special importance to Medical Qigong practitioners for thousands of years, and are viewed as the foundation of the body's energy, the bridge between the Yuan Qi (Prenatal Qi) and the Postnatal Qi. These Eight Extraordinary Vessels affect the body on the deepest level of our basic constitutional energy. In Medical Qigong regulation exercises, the focus on opening the flow of energy through the Eight Extraordinary Vessels is a prerequisite for opening the energy flow in the Twelve Primary Channels. The major purpose of opening the Eight Extraordinary Vessels is to provide a container for storing the Three Forces: Heaven Force (absorbing universal energy), Earth Force (absorbing environmental energy), and Man's Force: Jing, Qi and Shen (Essence, Energy and Spirit).

It is essential for the Qigong doctors to open their Eight Extraordinary Vessels to attain mastery of their energetic body. The Microcosmic Orbit is introduced for purgation, fusion, tonification, and regulation of the Governing and Conception Vessels in the first stages of training. This exercise restores a healthy flow of energy throughout all of the channels and vessels creating a healthy and balanced body.

Through the refinement of their energy, Qigong doctors receive more Qi, and the quality of their Blood changes, i.e., its energetic potential changes to contain more Qi and less Blood. At this advanced state of transformation, Qigong doctors rechannel the flow of energy through their body's Three Dantians, including the "mystical pass" (located within the Upper Dantian chambers of the brain). When the flow of energy is directed to stimulate the Mystical Pass, the Qigong doctors acquire greater awareness and control over their own bodies (physical, mental, emotional, energetic and spiritual), and are then able to enhance their perception and communication with all the other energetic planes of the world (mineral, plant, animal, and human), and with the Dao (or divine).

CLINICAL USE OF THE EIGHT EXTRAORDINARY VESSELS

The Eight Extraordinary Vessels form and establish the foundational energetic pattern for the developing fetus's tissues, as well as the adult's entire body. The clinical use of the Eight Extraordinary Vessels can be divided into several different approaches of energy manipulation to change the energetic patterns within the patient's tissues.

One approach divides the Eight Extraordinary Vessels into four pairs of Yin and Yang vessels. Each of the vessels is grouped according to the same polarity, two pairs of Yin and two pairs of Yang. When paired this way, each set of the Yin and Yang Extraordinary Vessels has a common range of energetic action in terms of the patient's body area.

1. The Conception and Yin Heel Vessels affect the energetic flow to the patient's abdomen, chest, Lungs, throat, and face.
2. The Governing and Yang Heel Vessels affect the energetic flow to the back of the patient's legs, as well as the back, spine, neck, head, eyes, and brain.

3. The Thrusting and Yin Linking Vessels affect the energetic flow to the inner aspect of the patient's legs, as well as the abdomen, Stomach, chest, and Heart.
4. The Belt and Yang Linking Vessels affect the energetic flow to the outer aspect of the patient's legs, as well as the sides of the body, shoulders, and sides of the neck.

ENERGETIC FUNCTIONS OF THE EIGHT EXTRAORDINARY VESSELS

The Eight Extraordinary Vessels can also be categorized is according to their energetic functions.

1. The Conception, Governing and Thrusting Vessels are considered the source of all the other Extraordinary Vessels These three vessels affect the patient's energy at a deep constitutional level. They originate directly from the Kidneys and are connected to the body's Jing.
2. The Yin and Yang Heel Vessels are complementary in that they both flow from the legs (controlling the state of the muscles of the legs) into the eyes (controlling the muscles that open and close the eyes).
3. The Yin and Yang Linking Vessels complement each other by linking the body's Yin and Yang Channels.
4. The Belt Vessel is the only horizontal vessel in the body, encircling the main channels. Its energetic influence is in its ability to affect the circulation of energy in the body, especially within the legs.

Each of the Eight Extraordinary Vessels is also connected to one of the Eight Trigrams (or Eight Natural Manifestations), and can be energetically regulated through the use of the Magic Square. For further treatment and clinical protocol see Chapter 31 regarding the Eight Extraordinary Vessel and the Magic Square.

THE GOVERNING AND CONCEPTION VESSELS

The Governing and Conception Vessels are the main rivers of the body's Yin and Yang energies. They are polar aspects of the body, perfectly complementary, like midnight and midday. They are responsible for the formation of the holoblastic cleavage and the first cellar division of the fertilized ovum in embryological development (see Chapter 2).

In China, Dr. Li Shi Zhen was the first to believe that the Governing and Conception Vessels are two branches of the same source, an inseparable Yin-and-Yang, front-and-back duality. These vessels connect the uterus with the Kidneys, Heart, and Brain.

They originate externally at Huiyin CV-1 point, ascend the front and back of the torso, and form a small circle when the tip of the tongue touches the upper palate in the mouth and the anal sphincter is squeezed. Not only does this action complete the balance of Fire (Heart) and Water (Kidneys) energy, it also increases the body's protective Wei Qi.

Regulating the Conception and Governing Vessels is a priority in Medical Qigong practice. Along these vessels, the Qigong practitioner draws the Yang Fire and Yin Essence up and down his or her body, fusing the Water and Fire energies together. This fusion facilitates a Yin and Yang balance throughout the body.

The Governing and Conception Vessels each have two energy flows on the anterior and posterior vertical midline of the body. Each vessel's pathway is complete, being composed of an ascending energetic flow and a descending energetic flow. The duality of these two medial lines joins at the extremities (the head and perineum), forming one complete circle of energetic current (Figure 7.1).

Both vessels are superimposed on each other, with the energy of the Governing Vessel being predominant up the back and inferior down the front (behind the Conception Vessel); the energy of the Conception Vessel is predominant up the front and inferior down the back (behind the Governing Vessel).

The energetic flow of the Conception Vessel corresponds to Yin, negative polarity, the female aspect, and responds to bass tones; while the energetic flow of the Governing Vessel corresponds to Yang, positive polarity, the male aspect, and responds to treble tones.


The Top of the Head
(Baihui Point)
Descending Qi flow of the Governing Vessel
Descending Qi flow of the Consеption Vessel
Front of Body
Back of Body
Ascending Qi flow of the Conception Vessel
Ascending Qi flow of the Governing Vessel
The Base of the Perineum
(Huiyin Point)

Figure 7.1. The Energetic Flow of the Conception and Governing Vessels

It is important to understand the energetic potential of these two currents flowing in both an ascending and descending direction on the posterior and anterior vertical midline in the body. The energetic movement of these two currents explains why there are two opposite directions of focused concentration used in energy cultivation meditations. One direction follows the Microcosmic Fire cycle along the Governing Vessel (up the spine and down the chest) to stimulate the emotional regulation of the acquired mind (Zhi Shen); the other direction follows the Microcosmic Water cycle along the Conception Vessel (up the chest and down the spine) to stimulate spiritual intuition and activate the perceptions of the Yuan Shen.

THE GOVERNING VESSEL OR DU VESSEL

The word Du translates as "governing," and refers to a general, someone who controls and is in charge. During the development of the embryo, the Governing Vessel is responsible for the development and formation of the medulla oblongata and cerebrum. The Governing Vessel controls all the Yang Channels in the body, and is called the Sea of Yang Channels. It is responsible for nourishing the brain and spinal cord and for consolidating the Yuan Qi in the Kidneys.

The Governing Vessel originates in the Lower Dantian in both men and women. It is composed of many energetic branches, emerging externally at the perineum. The primary branch ascends externally on the midline of the back, over the head and ends in the frenulum of the upper lip. As the Qi flows up the Governing Vessel one branch enters the interior of the spinal column and enters the Kidneys. Another set of branches enters the brain at the Fengfu GV-16 point and ascends internally to the vertex at the Baihui GV-20 point.

From the lower perineum, another set of branches encircles the anus and envelops the external genitals, ascends past the navel, Heart, and throat to circle the mouth. After circling the mouth, it further ascends to the eyes, emerging just below the middle of the eyes. From the inside of the eyes (at the Jingming Bl-1 point), a set of branches follows the Bladder Channels along the forehead, converging at the vertex of the Baihui GV-20 point and enters the brain. From the brain, the Vessel emerges at the Fengfu GV-16 point, and divides into two additional branches which descend the



Figure 7.2. The Governing Vessel (Side View)

back, passing through the Fengmen Bl-12 points along the sides of the spine and enter into the Kidneys (Figure 7.2).

The Governing Vessel tonifies the Kidney Yang and strengthens the spine and back. When the Governing Vessel is excessive, the back becomes stiff; when it is depleted, the head becomes heavy, unstable, and shaky (Figure 7.3).

CLINICAL MANIFESTATIONS

The functions and clinical uses of the patient's Governing Vessel are as follows.

1. To strengthen and control all the Yang Channels of the patient's body (particularly in relation to the Kidney Yang and the brain);
2. To tonify the Kidney Yang and strengthen the patient's spine and back (especially in cases of chronic lower back pain due to Kidney Deficiency);
3. To purge External Wind from the patient's body when symptoms are present, such as runny nose, head ache, fever, and stiff neck;
4. To purge Internal Wind from the patient's body when symptoms are present, such as dizziness, tremors, convulsions, epilepsy, or the condition of Wind Stroke;
5. To strengthen and nourish the patient's brain and Marrow, and for treating such symptoms as poor memory, dizziness, and tinnitus; and
6. To treat depression, due to the Governing Vessel's connection to the body's Jing (Kidneys, lack of willpower), Qi (Heart), and Shen (Brain).

Note: In men, the Governing Vessel is generally treated by itself, and in women, its treatment is combined with treating the Conception Vessel.

PATHOLOGICAL MANIFESTATIONS

1. Symptoms of Excess include diseases of the head (apoplexy, aphasia, epilepsy, headaches, tetanus, etc.), the back, neck, and Kidneys (pain and stiffness in the spinal column), spastic muscle movement of the extremities, night sweating, and Jing Shen disorders (hyperexcitability, hallucinations, etc.).
2. Symptoms of Deficiency result in shaking of the head along with a feeling of heaviness, instability, and an inability to concentrate. The patient lacks physical and mental stamina, displays weakness in character, and may also experience hemorrhoids, sterility, and impotence.


GV-21
GV-20
GV-19
GV-18
GV-17
GV-16
GV-15
GV-14
GV-13
Fengmen
Bl-12
GV-12
GV-11
GV-10
GV-9
GV-8
GV-7
GV-6
GV-5
GV-4
GV-3
GV-2
GV-1
Fengmen
Bl-12
GV-28
GV-22
GV-23
GV-24
Bl-1
GV-25
GV-26
GV-27

Figure 7.3. The Governing Vessel (GV)

THE CONCEPTION VESSEL OR REN VESSEL

The word Ren translates as Conception, and refers to pregnancy, responsibility, or obligation. It can also mean "to accept." The Conception Vessel governs all the Yin Channels of the body and is called the Sea of Yin Channels. It nourishes the Yuan Qi of all Five Yin Organs. The Conception Vessel originates from the Lower Dantian, and specifically in the uterus in females (Figure 7.4).

Functionally, the upper third of the Conception Vessel, on the sternum, controls respiratory functions; the middle third, on the epigastrium, controls digestive functions; and the lower third, on the abdomen, controls the urogenital functions (Figure 7.5).

In women the Conception Vessel is primarily responsible for nourishing the uterus and the genital system and determines the seven-year life cycles. It links the Yin energy with all aspects of conception and reproduction. The Conception Vessel, along with the Thrusting Vessels, have an important relationship with obstetric diseases related to the development of the fetus, delivery, and menstruation.

CLINICAL MANIFESTATIONS

The functions and clinical uses of the patient's Conception Vessel are as follows.

1. To strengthen and nourish the Yin energy of the patient's body (especially in women after menopause) and harmonize the Lungs and Kidneys;
2. To regulate the energy of the reproductive system, tonifying the Blood and Yin, and to reduce the effects of Heart Empty-Heat symptoms developed from Kidney Yin Deficiency after menopause (i.e., night sweating, hot flashes, anxiety, mental irritability, insomnia and dizziness, etc.);
3. To promote Blood supply to the uterus and regulate menstrual disorders (i.e., dysmenorrhoea, menorrhagia, amenorrhoea, and metrorrhagia);
4. To move the Qi in the patient's Lower Burner and treat abdominal lumps, as well as myomas, fibroids, and carcinoma in the woman's uterus, and hernia in men; and
5. To stimulate the energetic interaction of the Lungs Channels descending Qi function, and the Kidneys' function of receiving and holding the Lung Qi, which can, when malfunctioning, result in asthma.



Figure 7.4. The Conception Vessel (Side View)

PATHOLOGICAL MANIFESTATIONS

1. Symptoms of Excess include diseases of the reproductive and gastrointestinal systems (hemorrhoids, diarrhea, decreased urination, etc.). In the male, problems in the Conception


St-1
CV-24
CV-23
CV-22
CV-21
CV-20
CV-19
CV-18
CV-17
CV-16
CV-15
CV-14
CV-13
CV-12
CV-11
CV-10
CV-9
CV-8
CV-7
CV-6
CV-5
CV-4
CV-3
CV-2
CV-1

After emerging externally at the Huiyin (CV-1) point in the perineum, the main branch of the Conception Vessel ascends through the midline of the front of the torso, flowing to the mouth. After encircling the mouth it branches to connect with the Yinjiao (GV-28) points, and both branches ascend to the Chengqi (St-1) points beneath the eyes.

The internal branch of the Conception Vessel originates from the pelvic cavity and ascends the body along the spine, ending at the mouth.

Figure 7.5. The Conception Vessel (CV)

Vessel produce sterility. In the female, the Conception Vessel can cause menstruation problems such as leukorrhea and dysmenorrhea. Other female problems include breast pain, paralysis after delivery, emaciation, and sterility. Other problems of the female reproductive system include the external genitalia and vulva, vagina, and cervix disorders.

2. Symptoms of Deficiency include abdominal pains (hernia), pruritus, and a heavy feeling in the hips, lower ribs, and lumbar area.

THE THRUSTING VESSELS AND THE BELT VESSELS

The Thrusting and Belt Vessels balance the external tissues and internal organ energies, controlling an Excess or Deficient condition by regulating the upper and lower, as well as left and right, energetic quadrants.

The Belt Vessel is responsible for the second cellular division of the fertilized ovum in embryological development (see Chapter 2).

THE THRUSTING VESSELS OR CHONG VESSELS

The word Chong translates as "a street" and expresses the idea of passing or penetrating through something. This passing through action refers to its function as the vital pathway for alchemical transformation, used to produce energetic change (Jing to Qi, Qi to Shen and vise versa). The Thrusting Vessels, also called the Penetrating Channel, and are regarded as the Sea of Blood and the Sea of the Twelve Regulating Channels. They regulate both the Qi and Blood of all Twelve Primary Channels and extend to the anterior, posterior, upper, and lower parts of the body. During the development of the embryo, the Thrusting Vessels are responsible for the development of the adrenal glands and the cortex.

The Thrusting Vessels originate in the Lower Dantian. The Qi of the Thrusting Vessels travel to the head and face to flow into the Chong and penetrate the lower limbs, irrigating the body's Yin (Figure 7.6). According to some Chinese doctors, all energetic points that have Chong in their names relate to the Thrusting Vessels (i.e., Qichong St-30, Taichong St-42, and Shaochong Ht-9).

Along with the Conception Vessel, the Thrusting Vessels are responsible for regulating the changes in life cycles that occur every eight years in men, and every seven years in women. Abnormalities of the Thrusting Vessels during the beginning of pregnancy result in the mother's body aborting the fetus. Abnormalities of the Thrusting Vessels during the end of pregnancy result in an inability to expel the placenta.

The Thrusting Vessels control the woman's menstruation in all aspects, influencing the supply and amount of Blood in the uterus, and nourishing the woman's Jing. They also flow along the Kidney Channels and are related to the muscles of the abdomen and the penis (and are responsible for tightening the abdominal muscles).

THE ENERGETIC PATHWAY OF THE THRUSTING VESSELS

The classical description of the Thrusting Vessels' energy flow begins inside the uterus in women (the corresponding lower abdominal area in men), continuing down to the perineum. From the perineum, one branch ascends inside the spinal column, while four other branches flow externally.

Two external energetic rivers ascend up the front of the body alongside the Kidney Channels and enter into the chest. They then ascend through the throat, encircling the lips, and end at the corner of the eyes. When the Thrusting Vessels are full and overflowing (through meditation), they radiate a sparkling white-light energy, which can be observed to extend from the upper chest to the eyes.

From the perineum, two other external energetic rivers descend down the inner aspect of the thighs (one on each leg), along the Spleen Channels. They divide again at the medial malleolus. One set of branches flows into the big toes, a second set of branches terminates at the bottom of each foot.

CLINICAL MANIFESTATIONS

The functions and clinical uses of the patient's Thrusting Vessels are as follows.

1. To strengthen, nourish, and regulate weak


Kd-21
Kd-20
Kd-19
Kd-18
Kd-17
Kd-16
Kd-15
CV-7
Kd-14
Kd-13
Kd-12
St-30
Kd-11
Kd-21
Kd-20
Kd-19
Kd-18
Kd-17
Kd-16
Kd-15
Kd-14
Kd-13
Kd-12
St-30
CV-1

Figure 7.6. The Thrusting Vessels

1. Start chanting Kan-Li-Chen-Tui-Kun-Ken-Sun-Chien touching each of the kuas as you chant them. Continue to do this with only your mind, saying the name of the kua and holding the symbol in front of your eyes. Then spiral the Tai Chi symbol from the bottom to the right and up, chanting it and spiraling with your hand, eyes and mind. Continue to spiral with your mind and eyes only. Feel that the energy is drawn inward and the Tai Chi symbol is spiraling and changing to violet light.
2. Activate the facial pakua. Chant each of the symbols and point to them on your face; Kan-Li-Chen-Tui-Kun-Ken-Sun-Chien. Do it several times and make then the Tai Chi symbol on your forehead: Tai Chi, Tai Chi, Tai Chi, spiraling with your fingers over the third eye area. Feel the energy drawn into the center of the forehead, drawing the senses inwardly to the senses control and connecting down to the lower pakua. On their way down they collect the energy from the organs as well.



Fig. 5.68 *Four Head Pakuas*

3. Chant now Yin-Yang, Yin-Yang, Yin-Yang. Contract with Yin and expand from the forehead out with Yang. Use your fingers to point the direction of the energy, in and out.
4. Rest. Smile, feel the Tai Chi very deep inside you spiraling and chant Tai Chi, Tai Chi, Tai Chi, Tai Chi. Feel the facial pakua go into your head.

constitutions with digestive symptoms (e.g., abdominal distension, poor appetite, and poor assimilation of food);

2. To move the Blood of the Heart to relieve symptoms of pain and stiffness of the chest (the Thrusting Vessels control all the Blood in the connecting channels);
3. To purge Qi and Blood stagnation in the abdomen and chest;
4. To treat feelings of anxiety (within the chest) caused by Rebellious Qi; One of the Thrusting Vessels' most important pathologies is Rebellious Qi (Qi that moves in the wrong direction, going upwards instead of downwards). Feelings of anxiety that arise in the patient's abdomen and ascend to their chest are especially indicative of this malfunction;
5. To treat gynecological problems (hot flashes), when the Qi of the Thrusting Vessels rises upwards, and causes the patient's hands and feet to get cold, the face to get hot, and a feeling of fullness in the chest. The treatment is to regulate the Thrusting Vessels and subdue the Rebellious Qi in the Chong Vessel. If there are accompanying emotional problems and Liver Qi stagnation, then also treat the patient's Lv-3 points; and
6. To treat Rebellious Qi caused by the energy of the Thrusting Vessels rebelling upwards; the symptoms are oppressive feelings in the chest, as well as dizziness, nausea, and vomiting.

PATHOLOGICAL MANIFESTATIONS

The main diseases associated with the patient's External Thrusting Vessels include diseases of the Heart, fullness in the chest and abdomen, gastritis, abdominal pain, and convulsive diseases. If a woman's Thrusting Vessels are Deficient or Empty she may develop such conditions as amenorrhoea, scanty periods, or late periods. If there is stagnant Qi and / or Blood in the Thrusting Vessels, she may experience dysmenorrhoea. Abnormalities of the Thrusting Vessels also result in the mother aborting the fetus.

The Thrusting Vessels work with the Qi of the Kidney Channels to control the brain's physiological functions. If the energy from the Thrusting Vessels to the cortex becomes Deficient, this can inhibit the development of the brain.

THE BELT VESSEL OR DAI VESSEL

The word Dai translates as a "belt" or "girdle," and refers to the action of supporting something. The Belt Vessel is the only horizontal vessel in the body. Beginning at the Mingmen, this vessel encircles the waist like a belt, dipping down into the lower abdominal region anteriorly and running across the lumbar region posteriorly. It connects with the Gall Bladder's -26, -27, and -28 points and crosses the Conception Vessel at CV-4. Many sources say that it connects with the Liver -13 (at the free ends of each 12th rib). It binds, joins, and controls all the channels of the body, exerting an influence on the energetic circulation of the body's Governing and Conception Vessels (Figure 7.7).

Medical Qigong schools teach that the Belt Vessel circle wraps the entire body, like a enveloping cocoon, flowing from the feet to the head. The waist is considered the "hub" of the energetic wheel, and the access points of the Belt Vessels center channel (which circles the waist) is used to control the entire vessel. As the energy of the body increases (through Qi cultivation), the Qi within the entire Belt Vessel increases, circle wrapping the tissues from feet to head, increasing the body's Wei Qi fields (Figure 7.8).

In addition, the Belt Vessel keeps both the Yin and Yang Channels under control, connecting all of the leg Yin and Yang channels as they traverse the body's trunk. As a result, the Belt Vessel assists in regulating the circulation of Qi in those channels, especially from the waist down.

The Belt Vessel has an important influence on the body's physiology by encircling the leg channels, influencing the circulation of energy to and from the legs, as well as influencing the energetic actions of the genitals, waist, and hips. This vessel not only restrains the flow of the body's Liver and Gall Bladder Qi, but also harmonizes the ascending and descending flows of energy from the Kidneys and Spleen through its connection with the Kidney Divergent Channel.



Figure 7.7. The Center of the Belt Vessel



Figure 7.8. The Belt Vessel winds up the body like an energetic coil.

CLINICAL MANIFESTATIONS

The functions and clinical uses of the patient's Belt Vessel are as follows.

1. To treat impaired circulation of Qi in the leg channels resulting in such symptoms as cold legs and feet, or tense leg muscles (gastrocnemius and tibiales). This condition is due to Liver Blood not moistening the sinews of the legs;
2. To treat impaired circulation of Qi and Blood that cause numbness, weakness, atrophy, or motor impairment of the leg muscles, due to a Deficiency of energy in the Stomach and Spleen Channels;
3. To tonify and harmonize the circulation of

Liver and Gall Bladder Qi due to Excess patterns of Liver energy;

4. To disperse Damp Heat in the genitals that has resulted in symptoms such as difficulty or burning during urination;
5. To treat hip pain caused by Deficient Liver Blood (leading to sinew and joint malnourishment and Excess of Liver Yang; and
6. To regulate the lower abdomen due to a Belt Vessel imbalance, causing symptoms such as a sagging waist or bloated abdomen.

PATHOLOGICAL MANIFESTATIONS

1. Symptoms of Excess include pain in the back (lumbar region), and sides of the lower abdomen, as well as weakness in the shoulders, upper extremities, and lower limbs. Symptoms may also include weakness in the opposite sides of the body (e.g., eye, breast, ovary, etc.), and a feeling of heaviness in the body and abdomen (as if carrying 5,000 coins) due to exposure to Dampness.
2. Symptoms of Deficiency have physical sensations similar to that of "sitting in cold water" up to the waist. This description generally refers to pain, weakness, and a cold, heavy sensation in the patient's lumbar and sacral regions. Other symptoms include umbilical, abdominal and lumbar pain, as well as a feeling that something like a stick is pressing against the groin. There can also be abdominal fullness and distention. In women, there may be an abnormal white vaginal discharge, and a prolapse of the uterus.

THE YIN AND YANG HEEL VESSELS OR QIAO VESSELS

The word Qiao translates as "the heel" or "to stand on the toes," and refers to the action of kicking one's foot as high as possible. The Yin and Yang Heel Vessels flow along the medial and lateral aspects of the lower legs and torso, connecting at the inner canthus (by the eyes). They link the channel energy of the body's Yin and Yang Channels and regulate the movement of all four limbs. They also control the amount of energy being used by all the other channels in the body. Once these vessels are full, they relax the tissues, enabling the limbs to become more dexterous.

The Yin and Yang Heel Vessels are sometimes called Bridge Channels, because they act like a bridge linking the stored Qi in the body with the areas in need of Qi. When any channel uses more than its share of energy, other channels become Deficient. Thus the Heel Vessels seek to ensure that energy is always distributed in a balanced way.

The Yin Heel Vessels are an offshoot of the Kidney Channels at the front of the body, while the Yang Heel Vessels are an offshoot of the Bladder Channels at the back of the body. Together, the Yin and Yang Heel Vessels can be used to treat structural imbalances and to harmonize the right and left sides of the body.

Because the Heel Vessels cause the motor nerves to develop during the formative stages of the embryo, the Chinese believe the Yang Heel Vessels cause little boys to be more physically active (running, jumping, etc.), while the Yin Heel Vessels cause little girls to be less actively inclined.

THE YIN HEEL VESSELS

The Yin Heel Vessels control the Yin of the left and right sides of the body. The Yin Heel Vessels influences the male and female reproductive system, as well as the lower abdomen in women.

When Yang energy is slowed down in the Heel Vessels, the Yin energy moves more rapidly. The Excess Yin causes the following problems: sleepiness, the inability to keep the eyes open while trying to stay awake, hypotension, choking, painful urination, stomach rumbling, vomiting, diarrhea, difficult bowel movements, and unconsciousness. Excess Yin in women also causes a difficult labor. Also, when the Yin Heel Vessels are in Excess, the inner leg muscles are tight, while the outer leg muscles are loose. Weakness in the Yin Heel Vessels can cause the feet and ankles to invert, whereas an Excess condition can cause the feet to turn outwards.

The Yin Heel Vessels begin at the superficial part of the ankles, just below the medial malleolus of the tibial bones at the Kd-2 points. They continue up the front of the body, ending at the inner



Figure 7.9. The Yin Heel Vessels

corners of the eyes, where they join the Yang Heel Vessels (Figure 7.9).

CLINICAL MANIFESTATIONS

The functions and clinical uses of the patient's Yin Heel Vessels are:

1. To treat symptoms of Excess conditions in the Lower Burner in women (e.g., abdominal distension, difficult delivery, or the retention of the placenta, abdominal masses, lumps, and fibroids);
2. To structurally balance the left and right sides of the body;
3. To treat disturbances of sleep (e.g., insomnia or somnolence); and
4. To treat certain cases of atrophy (e.g., when the muscles of the inner aspect of the leg are loose and the outer leg muscles are tight).

PATHOLOGICAL MANIFESTATIONS

1. Symptoms of Excess of the Yin Heel Vessels include: lower abdominal pain, vomiting, difficult bowel movements, and spasms on the medial side of the legs. The Yin Heel Vessels also control diseases of the eyes (watery eyes, heavy sensations of the eyelids or an inability to open the eyes), migraines, congestive headaches, and hypersomnia. Abnormalities of the Yin Heel Vessels cause pregnant women to have difficult labor.
2. Symptoms of Deficiency include: Aggravations of symptoms during the evening time, nocturnal headaches, insomnia, cramps, or convulsions.

THE YANG HEEL VESSELS

The Yang Heel Vessels control the Yang of the left and right sides of the body. Abnormalities of the Yang Heel Vessels in newborns cause vomiting of milk.

When Yin energy is slowed down in the Heel Vessels, the Yang energy moves more rapidly. The Excess Yang causes the following problems: insomnia, difficulty in closing the eyes, painful eyes, hypertension, stiff back and waist (inability to bend down), thigh tumors, bad colds, spontaneous sweating, headaches, paralysis of the arms and legs, deafness, epilepsy, nose bleeding, swelling of the body, pain in the joints, and head sweating. Excess Yang can also cause the vomiting of milk in infants.

Weakness in the Yang Heel Vessels can cause foot and ankle eversion, while Excess can cause foot inversion. Also, when the Yang Heel Vessel is in Excess, the inner leg muscles are loose and the outer leg muscles are tight.

The Yang Heel Vessels begin on the outer side of the ankles below the lateral malleolus, at the Bl-62 points. From there, they continue to ascend the outside of the thigh and the back to end just below the eyes at the Bl-1 points, where they communicate with the Yin Heel Vessels near the eyes (Figure 7.10).

CLINICAL MANIFESTATIONS

The functions and clinical uses of the patient's Yang Heel Vessel are:

1. To treat acute Excess conditions of the lower back (e.g., aches due to spasm or invasion of Cold) and pain along the Bladder Channels of the legs;
2. To subdue Internal or External Wind from the head (e.g., facial paralysis, severe dizziness, and aphasia); and
3. To purge Wind-Heat and Wind-Cold manifesting in symptoms, such as sneezing, head ache, runny nose, and stiff neck.

PATHOLOGICAL MANIFESTATIONS

1. Symptoms of Excess include: Stiffness of the back and waist, lumbar pain, spasms on the outer side of the legs, tumors of the thighs, nocturnal epileptic seizures, and insomnia or restless sleep. The Yang Heel Vessels are also involved with diseases of the eyes such as dry and itchy eyes.
2. Symptoms of Deficiency include: Fatigue, lassitude and weakness during the day, and aggravations of symptoms from stress during the day. These symptoms improve as the night progresses.

According to some Traditional Chinese Medical Classics, if epilepsy occurs during the daytime, Qigong and moxa are given on the Yang Heel Vessels; however, if epilepsy occurs at night, Qigong and moxa are given on the Yin Heel Vessels.



Figure 7.10. Side View of the Left Yang Heel Vessel

THE YIN AND YANG LINKING VESSELS OR WEI VESSELS

The word Wei translates as "to link" or "bind" and refers to a rope that is tied around something, pulling it down and securing it. The Linking Vessels are sometimes called the Regulator Channels. The Linking Vessels are divided into Yin and Yang energetic pathways.

Both Yin and Yang Linking Vessels start at the lower legs and flow upwards to the head, along the medial and lateral aspects of the lower legs and torso. When the Linking Vessels reach the neck and back of the head, they join the Conception and Governing Vessels. Secondary Vessels, called the Yu (surplus) Vessels, branch away from the energetic flow of the major Vessel, connecting the energetic flow of each Yin and Yang Linking Vessel to the hands.

Instead of serving as streams transporting Qi and Blood, these two vessels act as lakes that store Qi and Blood that overflows from other vessels. Together, these four vessels regulate the circulation of Qi and Blood for the whole body, store the overflowing Qi and Blood, and release the Qi and Blood into the channels in the event of insufficiencies.

THE YIN LINKING VESSEL

The Yin Linking Vessels lie on the medial axis of the body. They help maintain the connection to all the Yin Channels. They begin at the Kd-9 points at the inner side of the lower legs and ascend up the sides of the abdomen and chest. They move toward the front of the body, along the sides of the chest to the tips of the nipples. At the Ruzhong (St-17) Breast Center points they split into two sets of branches. One set of branches connects with the Conception Vessel at the neck. The other set of branches becomes the Yin Yu Vessels, and extends from the chest, over the shoulders and down the inside of the arms following the route of the Pericardium Channels. Just above both wrist folds on each arm, each branch energetically pools at the Neiguan (Pc-6) Inner Pass points, before it flows into the palms. The Pc-6 points are therefore considered the Master Points for the Yin Linking Vessels (Figure 7.11).



Figure 7.11. The Yin Linking Vessels

The Yin Linking Vessels are responsible for moving the Yin energy and regulating the Blood and inner parts of the body. They connect with all the body's Primary Yin Channels: Liver, Heart, Spleen, Lung, Kidney, and Pericardium. When the Yin energy is slowed down in the Linking Vessels, the Yang energy moves more rapidly. Therefore, if the Yin Linking Vessels become unbalanced, the Excess Yang condition can cause the patient to suffer from Heart pain.

CLINICAL MANIFESTATIONS

The functions and clinical uses of the patient's Yin Linking Vessels are:

1. To tonify the Heart (for symptoms of pain, stiffness, tightness and oppression in the chest, as well as mental depression, anxiety, apprehension, and nightmares);
2. To treat Deficient Yin and Blood conditions, especially if accompanied by psychological conditions, such as mental restlessness, anxiety, and insomnia; and
3. To treat headaches located in the back of the neck due to Blood Deficiency.

PATHOLOGICAL MANIFESTATIONS

1. Symptoms of Excess include diseases of the Heart such as hypertension, delirium, nightmares, etc., as well as, cardialgia (tightness and oppression in the chest), difficulty in swallowing, convulsive diseases, contracted feeling in the Lungs, and dyspnea. Diseases of the Yin Linking Vessels also include prolapse of the rectum and diarrhea.
2. Symptoms of Deficiency include timidity or fear, apprehension, nervous laughter, mental depression, hypotension, and weak respiration.

THE YANG LINKING VESSELS

The Yang Linking Vessels lie on the lateral aspects of the body. They serve to maintain and communicate with all the Yang Channels in the exterior portion of the lateral aspects of the body. They begin at the external part of the ankles, just below the lateral malleolus at Bl-63 points, ascend the sides of each leg, up each side of the back of the body, through the shoulder areas to the Naoshu (SI-10) Scapula's Hollow points. The SI-10 points



Figure 7.12. Side View of the Left Yang Linking Vessel

are the intersecting points of the Yang Linking and Yang Heel Vessels located on the Small Intestine Channels. From the SI-10 points, both Yang Linking Vessels split into two sets of branches. One set of branches flows up the sides of the neck and head connecting with the GB-20 points (at the lower occipital part of the head), where it communicates with the Governing Vessel. The other set of branches becomes the Yang Yu Vessels. The Yang Yu Vessels extend from the shoulders, down the back sides of the arms, following the route of the Triple Burner Channels. Just above both wrists on the outside of each arm, each of the branches pools at the Weiguan (TB-5) Outer Pass points, before flowing into the back of the hands. The TB-5 points are therefore considered the Master Points for the Yang Linking Vessels (Figure 7.12).

The Yang Linking Vessels are responsible for moving the Yang energy and controlling the Protective Qi, regulating the Wei Qi's resistance to external infections, and regulating the external parts of the body. They connect with all of the body's Primary Yang Channels: Gall Bladder, Small Intestine, Stomach, Large Intestine, Bladder, and Triple Burners. When the Yang energy is slowed down in the Linking Vessels, the Yin energy moves more rapidly; therefore, if the Yang Linking Vessels become unbalanced, the Excess Yin condition may cause the patient to catch colds and fevers more easily.

CLINICAL MANIFESTATIONS

The functions and clinical uses of the patient's Yang Linking Vessels are:

1. To treat ear problems due to the rising of Liver Fire, resulting in conditions such as tinnitus and deafness;
2. To treat ear diseases due to a Gall Bladder disharmony;
3. To treat hypochondriac pain;
4. To treat sciatic pain in the lateral aspects of the legs (along the Gall Bladder Channels);
5. To treat intermittent fevers that alternate between chills and fever.

PATHOLOGICAL MANIFESTATIONS

1. Symptoms of Excess include: Alternating chills and fever; pain on the lateral sides of the neck, trunk and legs, as well as pain in the head. Symptoms also include pains and skin problems during weather changes, sensitivity to changes in climate (aching muscles, skin rashes, etc.), swelling, pain and fever in the joints, diarrhea and night sweats.
2. Symptoms of Deficiency include: Coldness and lack of body heat, loss of energy, and physical strength. Symptoms also include cold knees, stiffness, and fatigue (especially during cold or rainy weather).

SUMMARY OF EIGHT EXTRAORDINARY VESSEL PATHOLOGY

The Eight Extraordinary Vessels link all of the Yin and Yang Channels in the body and regulate the flow of energy in these channels to maintain a state of energetic balance. The clinical significance of the Eight Extraordinary Vessels is manifested through certain pathological indications that are particular to the vessels' intersection with their specific Primary Channel(s). Their symptomatology is therefore not distinct from, but rather a composite of, the pathological symptoms associated with their joining Primary Channel(s).

Figure 7.13 describes some of the Eight Extraordinary Vessels pathologies and the clinical manifestations indicated along their root (beginning) and ending branches.

The Eight Extraordinary Vessels' energetic pathways used in certain esoteric Qigong meditations are somewhat different from the ones seen in Traditional Chinese Medical texts and acupuncture charts. The reason for this uniqueness is because their purposes are different.

The goal of Chinese acupuncture is to restore sick people to health. The energetic points being treated by an acupuncturist must be along the superficial channels, so that they can be activated by acupuncture needles.

Medical Qigong exercises and meditations aim to maximizing health, and to take the individual beyond mere physical health to spiritual enlightenment. In Medical Qigong training the channels and points can be deep within the body, since the energy is guided by the mind or by postures and movements, rather than by needles.

Eight Extraordinary Vessels	**Pathologies**
Belt	• Pain in the back, lumbar region, and sides of the navel • Weakness in the lower limbs
Conception	• Diseases of the reproductive and gastrointestinal systems (hemorrhoids, diarrhea, decreased urination, etc.) • In the male, sterility • In the female, the menstruation problems such as leukorrhea and dysmenorrhea; also breast pain, paralysis after delivery, emaciation, and sterility; all reproductive system problems, including internal and external genitalia (vulva, vagina, and cervix)
Governing	• Diseases of the head (apoplexy, aphasia, epilepsy, headaches, tetanus, etc.), back, neck, and Kidneys • Stiffness in the spinal column, spastic muscle movements of the extremities, night sweating, and circulatory disturbances around the anus
Thrusting	• In women, amenorrhoea, scanty periods or late periods, dysmenorrhoea, spontaneous abortion, inability to expel the placenta, menopause problems • Diseases of the Heart, fullness in the chest and abdomen, gastritis, abdominal pain, convulsive diseases • Brain dysfunction of physiological origin
Yang Heel	• In newborns, vomiting of milk • Stiffness of the back and waist, lumbar pain, spasms on the outer side of the legs, and tumors of the thighs • Diseases of the eyes
Yang Linking	• Diseases from Cold— fevers resulting in a sensitivity to changes in climate; cold knees; stiffness and fatigue; swelling, pain, and fever in the joints and extremities; and night sweating
Yin Heel	• Lower abdominal pain, vomiting, difficult bowel movements, and spasms on the medial side of the legs • Diseases of the eyes • Difficult labor in women
Yin Linking	• Diseases of the Heart (cardialgia), tightness of the chest, difficulty in swallowing, convulsive diseases • Diseases also include prolapse of the rectum and diarrhea

Figure 7.13. Pathologies of the Eight Extraordinary Vessels

THE FIFTEEN MAJOR COLLATERALS (CONNECTING VESSELS)

The Fifteen Collaterals are also known as the Fifteen Luo. Luo is translated to mean a net or web, and in Traditional Chinese Medicine it refers to the Connecting Vessels. These vessels are the major "passage ways" for the circulation of the body's channel energy, emerging out of the Luo (pathway) points on the Twelve Primary Channels, plus the Governing and Conception Vessels. The Luo points are located below the elbows and knees and provide an additional energetic barrier to keep Evil Winds from affecting the Primary Channels, being somewhat deeper then the Muscle/Tendon Channels. The Collaterals are the streams of energy that connect the paired Primary Channel rivers.

The Fifteen Collaterals are superficial and much thinner in formation than the Primary Channels running through the interior aspect of the body. The collaterals distribute Qi and Blood to those areas not directly traversed by other channels. Flowing out of each Primary Channel's Luo point are two Luo vessels, which are counted as one:

1. The Transverse Luo Vessels connect to the Source Points on the Yin and Yang coupled Primary Channels. They act as a safety valve to maintain balance between Yin and Yang channels by diverting Excess energy from one channel to tonify Deficiencies in the Orb (internal organ and energetic field) of their paired Primary Channel. When a channel is Deficient (Empty) and its paired channel is in Excess (Full), for example, the tonification of the Luo point on the Deficient channel is enough to replenish it, while normalizing the channel previously in Excess.
2. Longitudinal Luo Vessels flow out of the Luo points, but do not connect with the coupled Primary Channels. The Luo Vessels usually flow proximally toward the channel's organ.

The Luo vessels' main function is to transfer Qi and Blood from the Primary Channels to all parts of the body to nourish the tendons, the bones, the skin, and the five sense organs (nose, eyes, ears, lips, and tongue). The Luo vessels also link the body's interior with its exterior, connecting the internal and superficial channels (Figures 7.14 through 7.19).

The Fifteen Major Collaterals have smaller branches, known as the Minute and Superficial Collaterals, extending from them. The Superficial Collaterals are sub-branches similar to capillaries serving to transport Qi and Blood to the surface of the body. Both Minute and Superficial Collaterals, which can be seen beneath the surface as blood vessels, are called Blood Luo Vessels.

PATHOLOGY

The pathology of the Fifteen Major Collaterals are categorized in terms of Excess and Deficient syndromes.

1. Excessive Conditions of the collaterals are due to exogenous invasion if (1) the organ associated with the Luo is in Excess or (2) the body's Wei Qi is weak. Evil Winds enter the body through Jing Well or Wind points, and start moving up the channel. The Longitudinal Luo Vessels provide a route for the diversion of Evil Winds. The Longitudinal Luo Vessels have more Wei Qi then the Primary Channels and can better fight pathogens. Sometimes with a Wind Cold invasion, a blue color is visible along the path of the Longitudinal Luo Vessel. If the invasion is due to Wind Heat, there may be a red color along the vessel.
2. Deficient Conditions of the collaterals are due to: (1) the organ associated with the Luo being Deficient or (2) the patient's Qi is Deficient due to exogenous factors.

POINT LOCATION OF THE FIFTEEN MAJOR COLLATERALS

1. The Foot Taiyin-Spleen 4 Point is located on the Spleen Channel of each foot, on the medial side, just posterior to the base of the first metatarsal bone. This Lou's energy flows downward to connect with the Stomach Channel on each foot. A second branch flows upward along the medial aspect of the inner thigh, passing the abdomen and connecting with the Stomach and Small Intestines (Figure 7.14).

5. Become aware of the Kan symbol. Picture the Kan symbol and project it out down all the way to the galaxy. Chant Kan, Kan, Kan. Chant and picture the Yin-Yang-Yin lines and feel that the power is going out all the way to outer space.

   Start then with the Yin-Yang breathing. Inhale, Yin contracting with bright violet light, exhale, Yang expanding with bright red light. Inhale, contracting, exhale, expanding. Feel the kua of the facial pakua and the abdominal pakua breathing and at the same time, feel the kua in the universe breathing. Picture the Yin-Yang-Yin very clear in your mind as well as very far away in space. Exhale, hold your breath and feel the symbol breathing. Inhale, breathe without breathing and feel the connection with the kua out there. Keep on breathing in this way until suddenly the kua out there comes to you and enforces the Kan in your abdomen.
6. Repeat the same procedure for Li, sending it out, up into the universe, for Chen sending it out into the space on your right side, Tui to the space on your left side, Kun to the space upper left, Ken to the lower left side, Sun to the upper right side of the universe and Chien to the lower left side of the universe.
7. Now picture all the kuas together and repeat their names very slowly: Kan-Li-Chen-Tui-Kun-Ken-Sun-Chien. Rest. Feel the universal pakua covering you. Feel this pakua breathing and pulsating together with your pakua in the abdomen and on your face, drawing the energy back into the lower pakua, into your center. Sit back and smile to the pakua inside you and to the pakua in the universe. Rest, concentrate and condense all the energies in the cauldron.



Fig. 5.69 *Feel all the Pakua and Universal Pakua breathing and pulsating. Feel a big Pakua cover you, breathing and pulsating.*


Major Collaterals
YANG CHANNEL
YIN CHANNEL
CONNECTING LINE
Lv-5
Kd-4
Sp-4
St-40
Bl-58
GB-37

Figure 7.14. The figure at left shows the three Luo points of the Yin Collaterals of the left foot located on the Primary Channels of the Kidneys, Spleen, and Liver. The figure on the right shows the three Luo points of the Yang Collaterals of the left foot located on the Primary Channels of the Stomach, Bladder, and Gall Bladder.

   a. Symptoms of Excess include sharp intestinal pain, vomiting, and diarrhea.
   b. Symptoms of Deficiency include abdominal swelling.
2. The Foot Shaoyin-Kidney 4 Point is located on the Kidney Channel of each foot, just posterior to the medial malleolus. The Lou's energetic flow runs downward, crossing the heel, and connects with the Bladder Channel on each foot. A second branch flows upward along the medial aspect of the inner thigh, following the Kidney Channel. It passes the abdomen and connects with the pericardium of the Heart then flows laterally to connect with the lumbar vertebrae (Figure 7.14).
   a. Symptoms of Excess include enuresis, emotional irritability, and depression.
   b. Symptoms of Deficiency include lower back pain.
3. The Foot Jueyin-Liver 5 Point is located on the Liver Channel of each foot, on the medial side, several inches above the medial malleolus. The Lou's energetic flow connects with the Gall Bladder Channel on each foot and flows upward along the medial aspect of the inner thigh. It connects with the genitals and terminates at the penis in males, and the clitoris in women (Figure 7.14).
   a. Symptoms of Excess include swelling of the testicles.
   b. Symptoms of Deficiency include itching in the pubic region.
4. The Foot Taiyang-Bladder 58 Point is located on the Bladder Channel of each foot, on the lateral side, several inches above the external malleolus. The Lou's energy flows downward to connect with the Kidney Channel on each foot (Figure 7.14).
   a. Symptoms of Excess include nasal congestion, headache, and back pain.
   b. Symptoms of Deficiency include clear mucus nasal discharge and nosebleed.
5. The Foot Shaoyang-Gall Bladder 37 Point is located on the Gall Bladder Channel of each foot, on the lateral side, several inches above the external malleolus. The Lou's energy flows downward to connect with the Liver Channel on each foot, then continues downward to disperse over the dorsum on each foot (Figure 7.14).
   a. Symptoms of Excess include fainting.
   b. Symptoms of Deficiency include weak and flaccid muscles of the feet.
6. The Foot Yangming-Stomach 40 Point is located on the Stomach Channel of each foot, on the lateral side, several inches above the external malleolus. The Lou's energy flows downward to connect with the Spleen Channel on each foot. A second branch flows along the lateral aspect of the tibia, upward to the top of the head where it divides, with one branch converging with the other Yang Channels on the neck and head, and the other branch connecting with the throat (Figure 7.14).
   a. Symptoms of Excess include epilepsy and insanity.
   b. Symptoms of Deficiency include pharyngitis, sudden aphasia, and flaccid or atrophied muscles in the legs or feet.
7. The Hand Taiyang-Small Intestine 7 Point is located on the Small Intestine Channel of each hand, on the dorsal side, several inches above the wrist, on the ulnar side. The Lou's energy flows upward past the elbow and connects with the Large Intestine 15 point (Figure 7.15).
   a. Symptoms of Excess include fever, headaches, and blurred vision.
   b. Symptoms of Deficiency include atrophy of the muscles in the elbow and arm, and a looseness in the joints.
8. The Hand Yangming-Large Intestine 6 Point is located on the Large Intestine Channel of each hand, several inches above the dorsal side of the wrist on the radial side. The Lou's energy flows upward on each arm to the jaw and pours into the area of the teeth. Another branch ascends into each ear, connecting with the Thrusting Vessels which supply energy to the head (Figure 7.15).
   a. Symptoms of Excess include deafness and toothache.

   b. Symptoms of Deficiency include a sensation of coldness in the teeth, as well as fullness and congestion in the chest.
9. The Hand Shaoyang-Triple Burner 5 Point is located on the Triple Burner Channel of each hand, located just above the dorsal transverse crease of the wrist. The Lou's energy flows upward past the arm and over the shoulder, dispersing into the chest and connecting with the Pericardium Channel (Figure 7.15).
   a. Symptoms of Excess include muscle spasms of the elbow.
   b. Symptoms of Deficiency include flaccid muscles in the arm and elbow joint.
10. The Hand Taiyin-Lung 7 Point is located on the Lung Channel of each hand and arises from the cleft of the tendons and bones on the radial side of the wrist, where it flows down into the palm, spreading through the thenar eminence (Figure 7.15).
    a. Symptoms of Excess include hot palms or wrists.
    b. Symptoms of Deficiency include enuresis and shortness of breath.
11. The Hand Shaoyin-Heart 5 Point is located on the Heart Channel of each hand, just above the transverse crease of the wrist. The Lou ascends along the Heart Channel and enters the Heart then continues up the chest into the head, flowing into the root of the tongue, then ascends to connect with each eye (Figure 7.16).
    a. Symptoms of Excess include fullness and pressure in the chest.
    b. Symptoms of Deficiency include aphasia.
12. The Hand Jueyin-Pericardium 6 Point is located on the Pericardium Channel of each hand, just a few inches above the medial transverse crease of the wrist, between the two tendons. The Lou's energy flow follows the Pericardium Channel, connecting with the Heart (Figure 7.16).
    a. Symptoms of Excess include chest pain.
    b. Symptoms of Deficiency include irritability.
13. The Governing Vessel 1 Point is located on the



Figure 7.15. The three Yang Collaterals and their Luo points located on the hand and on the Primary Channels of the Large Intestine (LI), Triple Burners (TB), and Small Intestine (SI).



Figure 7.16. The three Yin Collaterals and their Luo points located on the hand and on the Primary Channels of the Heart, Pericardium, and Lungs.



Figure 7.17. The main collateral and Luo point of the Governing Vessel is located on the Governing Vessel (GV) 1 point.



Figure 7.18. The main collateral and Luo point of the Conception Vessel is located on the Conception Vessel (CV) 15 point.



Figure 7.19. The major collateral and Luo point of the Spleen is located on the Spleen (Sp) 21 point.

base of the Governing Vessel, at the perineum. The Lou's energy flows upward along both sides of the spine to the nape of the neck, spreading to the top of the head. It continues flowing into the scalp regions on both sides of the head and connects with the Bladder Channel and merges with the spine (Figure 7.17).

   a. Symptoms of Excess include stiffness along the spine.
   b. Symptoms of Deficiency include dizziness or heaviness in the head.

14. The Conception Vessel 15 Point is located on the Conception Vessel of the chest, just below the xiphoid process. The Lou's energy flows downward, pouring over the abdomen (Figure 7.18).
    a. Symptoms of Excess include pain on the surface skin of the abdomen.
    b. Symptoms of Deficiency include itching on the surface skin of the abdomen.
15. The Major Luo of the Spleen 21 Point is located on the Spleen Channel of the chest, just below the auxiliary fold of each arm. The Lou's energy flow spreads through the chest and hypochondriac region, gathering the Blood like a net (Figure 7.19).
    a. Symptoms of Excess include general aches and pains throughout the entire body.
    b. Symptoms of Deficiency include weakness in the muscles of the limbs and joints.

THE TWELVE DIVERGENT CHANNELS

The Twelve Divergent Channels comprise an important part of the body's channel system. These channels are branches off the Twelve Primary Channels and share the energetic function of circulating Qi throughout the body. The energetic field of the Twelve Divergent Channels forms an enormous web of complex interconnections within the body's Twelve Primary Channels.

Because the area over which the energy of the Twelve Divergent Channels is distributed is quite extensive, they are considered a separate component of the channel system. They are secondary streams that parallel the primary rivers, yet each has its own functional characteristics and clinical application independent of the Primary Channels. The Twelve Divergent Channels run deeper in the body, supplementing the areas along the pathways that the Primary Channels do not reach. They have no points of their own, although there are intersection points where they cross the major channels (Figures 7.20 through 7.25).

One of the primary functions of the Twelve Divergent Channels is to integrate all parts of the body with the Twelve Primary Channels. There are areas in the body which are not traversed by the pathways of the Twelve Primary Channels, as well as internal organs that are otherwise unconnected, or only remotely connected, by the Primary Channels. These areas are more securely linked by the energetic flow of the Twelve Divergent Channels, which strengthen the bonds between the Twelve Primary Channels and the physical areas that are connected to, or adjoining, their pathways.

Another primary function of the Twelve Divergent Channels is to facilitate the connection between pairs of Yin and Yang Primary Channels and Organs. Therefore, all primary Yin and Yang organs are connected by the Divergent Channels. Both Yin and Yang Divergent Channels ultimately connect with the body's Yang Primary Channels.

1. The Yang Divergent Channels complete a cycle of leaving the primary channels (e.g., Primary Gall Bladder Channel) and entering their associated organs (e.g., The Gall Bladder Organ) before they resurface on the neck and reconnect with their original channels (e.g., The Primary Gall Bladder Channel).
2. The Yin Divergent Channels leave their primary channels (e.g., Primary Liver Channel), then join their associated Yang Divergent Channels (e.g., The Divergent Gall Bladder Channel), which then join with the Yang Primary Channels (e.g., The Primary Gall Bladder Channel).

Similarly, within the body's cavities, most of the Twelve Divergent Channels first join with their pertaining Yin or Yang organ and then connect with the associated organ (belonging to the associated channel) in the Yin / Yang pair. Through this interaction, the connection between paired Yin and Yang organs and channels is strengthened.

An understanding of the relationship between the paired Yin and Yang interactions is important to the Qigong doctor, as sometimes a disease affecting a Yang channel can be treated by selecting certain areas on its associated Yin channel, and vice versa. The same theory holds true for diseases of the internal organs.

The Twelve Divergent Channels are paired into six confluences according to their internal and external relationship.

1. Bladder Divergent Channel (Foot Tai Yang) and Kidney Divergent Channel (Foot Shao Yin)
2. Stomach Divergent Channel (Foot Yang Ming) and Spleen Divergent Channel (Foot Tai Yin)
3. Gall Bladder Divergent Channel (Foot Shao Yang) and Liver Divergent Channel (Foot Jue Yin)
4. Small Intestine Divergent Channel (Hand Tai Yang) and Heart Divergent Channel (Hand Shao Yin)
5. Large Intestine Divergent Channel (Hand Yang Ming) and Lung Divergent Channel (Hand Tai Yin)
6. Triple Burners Divergent Channel (Hand Shao Yang) and Pericardium Divergent Channel (Hand Jue Yin)


Divergent Channels
Yang Channels
Yin Channels
Connecting Line
Gall Bladder Divergent Channel
Liver Divergent Channel

Figure 7.20. The Divergent Channels of the Gall Bladder and Liver


Large Intestine
Divergent
Channel
Lung
Divergent
Channel

Figure 7.21. The Divergent Channels of the Lungs and Large Intestine


Spleen Divergent Channel
Stomach Divergent Channel

Figure 7.22. The Divergent Channels of the Stomach and Spleen


Kidney Divergent Channel
Bladder Divergent Channel

Figure 7.23. The Divergent Channels of the Bladder and Kidneys


Small Intestine
Divergent
Channel
Heart Divergent
Channel

Figure 7.24. The Divergent Channels of the Heart and Small Intestines


Triple Burners Divergent Channel
Pericardium Divergent Channel

Figure 7.25. The Divergent Channels of the Pericardium and Triple Burners

Formula Two: Transforming the Negative Emotions of Each Organ into Pure Life-Force Energy

Taoists reason that the negative emotions can be transformed to become our life-force and position energy. Therefore to expel or suppress unwanted, negative emotions is to expel or suppress life-force. Rather than suppressing them, you gain more by composting, recycling or transfering the negative into positive energy and experiencing these emotions. This means you permit them to emerge, observing and accepting them, but do not let them run wild or trigger other negative emotions. Instead transform them not only into useful life-force energy, but also into another, higher consciousness that is your spiritual energy.



a.*Pile all the garbage together, just like mixing all the emotions together.*

b.*Separate the garbage, just like separating emotions & transfer them.*



c.*Recycle and compost.*

d.*Recycling the garbage into compost and growing flowers and vegetables.*

e.*Eating the food grown from the compost.*

Fig. 5.70 *Transforming the Negative Emotions*

THE TWELVE MUSCLE/TENDON CHANNELS

The Twelve Muscle / Tendon Channels are the muscle and soft tissue regions of the body where the Qi and Blood of the Primary Channels nourish the skin, muscles, and tendons. They are very superficial in relationship to the Primary Channels and form a capillary network that travels in the depressions and planes between muscles and tendons. The Twelve Muscle / Tendon Channels, subsequently spread over the whole of the epidermis, through its close connection with the cutaneous tissues.

Originating in the extremities, these channels ascend to the head and torso. Physiologically, they do not enter into the internal organs but coordinate the movement of the bones and limbs. The Twelve Muscle / Tendon Channels are connected to the inner fascia of the body's muscles, tendons, and ligaments, as well as other connective tissues. They are affiliated with the channels and collaterals (Luo) systems on the exterior of the body, and serve as mediators between any energetic reactions (trauma, stress, etc.) that vibrate from the body's exterior surface to the deep internal organs.

These channels are found along the four extremities on the surface of the body, as well as along the head, neck, back, chest, and abdomen. The name of each Muscle / Tendon Channel comes from the Twelve Primary Channels whose external energy flow they follow. They also receive Blood and Qi nourishment for their functional activity from and through the Twelve Primary Channels. There are points of connection, as well as intersecting points along these channels (Figure 7.26 through 7.37).

Treatment at these conjunctive points consistently responds successfully to stimulation; therefore, the Qigong doctor can effectively apply Jing Point Therapy to specific areas and points along the Muscle / Tendon Channels.

These channels are responsible for extending and flexing the muscles, tendons, ligaments and joints; their pathology is reflected in symptoms of impaired movement (i.e., pulled, twisted, strained, cramped or atrophied muscles, spasms, etc.).

In Traditional Chinese Medicine the muscles and tendons are described in characteristics of Yin (flexion, contraction, internal rotation, etc.) and Yang (extension, expansion, external rotation, etc.) which balance each other. When the Yin and Yang action of the muscles and tendons fail to balance and regulate each other, Muscle Channel Dysfunction results; for example, when exposed to cold, the muscles / tendons become tense and over-contract; when exposed to heat, muscles / tendons become loose and overextend.

The pathology of the Muscle / Tendon Channels also reflects the symptoms of corresponding groups of muscles and other connective tissues. The connective tissues are divided into three groups: the large, the small, and the membranous connective tissue.

Therapeutically, a local Muscle / Tendon Channel symptom can be treated by stimulating an area located next to the origin of the pain; for example, if the area is Yang (lateral) and overactive, then the Yin (medial) will be underactive and vice versa. Treatment is directed towards restoring the balance between the Yin and Yang Muscle / Tendon Channels.

Being superficial, the Twelve Muscle / Tendon Channels contain Wei Qi; thus, they provide the body's third line of defence against any unfavorable exogenous influence (the first being the body's Wei Qi field, and second being the Wei Qi stored within the skin). Only after overcoming the resistance of the body's Muscle / Tendon Wei Qi can the Evil Exogenous pathogens travel down the length of the channel to penetrate the corresponding Primary Channel at the Jing-Well point. Jing-Well points are points of energetic union, connecting Primary Channel points together with the points where the Muscle / Tendon Channel have their origin.


Baihui point
(GV-20)
levator labii
superioris
temporalis
masseter
sternocleidomastoid
pectoralis
major
serratus
anterior
external
oblique
gluteus
maximus
tensor
fascia lata
tibialis
anterior
extensor
digitorum
longus

Figure 7.26. The Muscle Region of the Gall Bladder Channel: High Tide is 11p.m.–1 a.m. Pathological symptoms include strained muscles from the fourth toe to the knee upon lateral rotation, with an inability to bend the knee; muscle spasms or stiffness within the popliteal fossa; strained muscles of the sacrum, pelvis, and lower ribs; pain in the hypochondria, chest, and clavicle region; and an inability to turn the eyes to the left or right.


rectus
abdominis
pectineus
vastus
medialis
soleus

Figure 7.27. The Muscle Region of the Liver Channel: High Tide is 1 a.m.–3 a.m. Pathological symptoms include strained muscles of the big toe; pain in the anterior internal malleolus of the ankle; pain at the medial aspect of the knee and thigh; and dysfunction of the reproductive organs, i.e., impotence.


subclavius
anterior deltoid
biceps brachii
brachio radialis
abductor pollicis brevis

Figure 7.28. The Muscle Region of the Lung Channel: High Tide is 3 a.m.–5 a.m. Pathological symptoms include strained muscles of the thumb; stiff, strained or muscle spasms, and/or pain along the course of the Lung Channel. In more serious cases, there will be muscle spasms over the rib area and spitting of blood.


temporalis
platysma
masseter
middle/anterior deltoid
trapezius
brachialis/ biceps brachii
extensor digitorum

Figure 7.29. The Muscle Region of the Large Intestine Channel: High Tide is 5 a.m.–7 a.m. Pathological symptoms include strained muscles of the index finger; stiffness, strained, or muscle spasms along the course of the Large Intestine Channel, resulting in frozen shoulder; and an inability to rotate the neck from side to side.


orbicularis oculi
levator labii superioris
masseter
orbicularis oris
platysma
pectoralis major
rectus abdominis
external obliques
latissimus dorsi
adductor longus
vastus lateralis
vastus medialis
tibialis anterior
extensor digitorum longus

Figure 7.30. The Muscle Region of the Stomach Channel: High Tide is 7 a.m.–9 a.m. Pathological symptoms include strained muscles of the big toe; spasms or hardening of the muscles in the foot; knotted or twisted muscles in the lower leg and thigh; swelling in the anterior pelvis region; hernia; spasms of the abdominal muscles; spasms or stiffness of neck and cheek muscles; and eye spasms.


rectus abdominis
oblique muscles
sartorius
soleus
flexor digitorum longus
extensor hallucis longgus

Figure 7.31. The Muscle Region of the Spleen Channel: High Tide is 9 a.m.–11 a.m. Pathological symptoms include strained muscles of the big toe; pain in the internal malleolus of the ankle upon rotation; pain along the medial aspect of the knee and adductor muscles of the thigh; groin strain; and pain due to strained upper abdominal muscles and mid-thoracic vertebrae.


pectoralis major
long head of the triceps brachii
brachialis tendon
abductor digit minimi
flexor digitorum superficialis


temporalis
upper trapeziusr
masseter
infraspinatus
middle deltoid
triceps
extensor carpi ulnaris

Figure 7.32. The Muscle Region of the Heart Channel: High Tide is 11 a.m.–1 p.m. Pathological symptoms include strained muscles of the little finger; stiff or strained muscles with spasm and/or pain along the course of the Heart Channel, including internal cramping within the diaphragm and upper abdominal area.

Figure 7.33. The Muscle Region of the Small Intestine Channel: High Tide is 1 p.m.–3 p.m. Pathological symptoms include strained muscles of the little finger; pain along the medial and posterior aspects of the elbow; pain in the posterior aspect of the axilla, neck, and scapula region; tinnitus related to ear ache; and poor vision.


frontalis
levator anguli oris/superioris
platysma
sternocleidomastoid
pectoralis major
serratus anterior
infraspinatus
occipitofrontalis
latissimus dorsi
erector spinae (longissimus, spinalis, iliocostalis)
gluteal muscles
semitendinosus
biceps femoris
popliteal fossa
peroneus longus
both heads of gastrocnemius
extensor tendons

Figure 7.34. The Muscle Region of the Bladder Channel: High Tide is 3 p.m.–5 p.m. Pathological symptoms include strained muscles of the big toe; swelling and pain in the heels; stiffness or spasms along the spine and back area; frozen shoulder; stiffness or spasms in the axillary and clavicle regions.


gracilis
gastrocnemius
flexor digitorum brevis
flexor digiti minimi brevis

Figure 7.35. The Muscle Region of the Kidney Channel: High Tide is 5 p.m.–7 p.m. Pathological symptoms include strained muscles on the bottom of the foot; spasms or stiffness along the Kidney Channel, resulting in an inability to bend forward (Yang disorder) or backward (Yin disorder), with difficulty in flexing or extending the head.

In the Taoist cosmology, the emotions originate from the vital organs, which correspond to the Five Phases of energy. They are also the reservoir of spiritual energy. By transforming the negative emotions in the organs, you are nourishing the spirit of that organ. Fear originates in and is stored in the kidneys, anger and frustration originate in and are stored in the liver, impatience, hastiness and hatred originate in and are stored in the heart, sadness and depression originate in and are stored in the lungs and worrying originates in and is stored in the spleen.

In the Tao, the main idea is to find a balance between the positive and the negative emotions. The negative emotions are like weeds, they are always there, and one could never totally get rid of them. The other point is that the soil needs them as fertilizers and they also help hold the soil in place. But at the same time the danger is that they will take over the garden if we don't control them. We need to cultivate the plants we want (our good virtues) to prevent the weeds from taking over the garden. It is the same with the negative emotions; they should only be kept in balance with the positive ones and one shouldn't waste time trying to get rid of them altogether. The work should be done on the positive emotions, constantly cultivating and nurturing them in order to grow the good virtues and to keep the right balance with the negative emotions. Negative emotions breed negative emotions and positive emotions breed positive emotions.

Fig. 5.71 *Yin and Yang balance negative and positive emotions but they do not get rid of them.*

We work in this formula with the counteracting or controlling cycle and we use collection points to gather and neutralize the negative emotions of each organ. We then blend the emotional energies together in the pakua, transforming them into pure life-force.



Fig. 5.72 *Keep on cultivating the positive emotions. Do not let the weeds out grow the vegetables.*


biceps brachialis
flexor carpi radialis
palmaris longus
flexor digitorum superficialis tendons


masseter
platysma
middle deltoid
brachialis
extensor digitorum

Figure 7.36. The Muscle Region of the Pericardium Channel: High Tide is 7 p.m.–9 p.m. Pathological symptoms include strained muscles of the middle finger; stiff or strained muscles, or spasms and/or pain along the course of the Pericardium's Channel; and chest pain and spasms.

Figure 7.37. The Muscle Region of the Triple Burner Channel: High Tide is 9 p.m.–11 p.m. Pathological symptoms include strained muscles of the ring finger; stiff or strained muscles, or spasms and/or pain along the course of the Triple Burners' Channel.

THE TWELVE SKIN ZONES

Based on the Twelve Primary Channels, their collaterals, and the body's Muscle / Tendon Channels, the surface tissue is divided into Twelve Skin Zones. These Skin Zones are the surface contact areas for the body's channel and collateral systems. These twelve regions (sometimes called the Twelve Cutaneous Channels) are located in the superficial layers of the skin and have continuous and direct contact with the external environment. They are, therefore, the most sensitive to climactic changes and must adapt to protect the body from External pathogenic factors.

Both the Qi and the Blood at the Twelve Skin Zones rely on the collaterals for their nourishment. The Twelve Skin Zones circulate Wei Qi, which in addition to its defensive function, is also in charge of opening and closing the pores. The skin relies primarily upon the strength of the Wei Qi for resistance to the invasion of External pathogenic influences, as these harmful influences must first penetrate the skin before they can affect the body's internal tissues and organs. Since the Lungs rule the skin, weak Lung Qi can allow pathogens to penetrate the skin and affect the Lungs.

Pathological symptoms associated with the Twelve Primary and connecting Channels manifest along the surface of the Twelve Skin Zones, before progressing deeper into the body's connective tissue. The early stages of disease are called Exterior conditions; if the exterior Wei Qi is strong enough, pathogens will be stopped at the external level. The order of pathogenic progression is as follows.

1. The Body's Wei Qi is the body's first line of defense. A healthy body will project a strong, protective, external energetic field, which will maintain a capable defensive boundary. If the patient becomes weak, tired, or stressed, however, External pathogens may advance onto the patient's skin and begin attacking his or her health.
2. The Skin is the body's second line of defence. If the body's Wei Qi is not strong enough to resist an External attack and the skin is not capable of warding off the pathogens, then the pathogens will attack the skin, causing the sweat pores to open, thus allowing the pathogens to advance towards the patient's collaterals.
3. The Collaterals are the third line of defense. If the body's collaterals are unable to redirect or purge the advancing pathogens, the pathogens will then advance into the patient's channels.
4. The Channels are the last line of defense before the advancing External pathogens invade the patient's internal organs. If the body's channels are unable to redirect or purge the pathogens, and the pathogens are allowed to continue their progression, they will advance further into the body's internal organs.
5. The Internal Organs are affected once the pathogens have breached all the outer defences and disease can now begin to establish its residence.

Pathologies associated with the Primary Channels manifest diagnostically through the body's skin, channels, and points. The observation of pimples, moles, discoloration, and changes in electro-conductivity are all valuable signs of pathogens, or obstructions, invading the skin.

A disease of external origin that first lodges within the patient's skin can be treated by the Qigong doctor. The doctor stimulates the Wei Qi in the affected skin zone through external Qi projection before it progresses further into the body's connective tissue. An alternate treatment would be to apply herbal ointments and/or moxa therapy.

THE CONNECTIVE TISSUE OF THE TWELVE SKIN ZONES

The connective tissue always responds to the outside stimulation of the Twelve Skin Zones. The body's connective tissue is just below the skin, and is regarded as one of the largest, most extensive tissue organs in the body. Its function is to support, connect, contain, and transmit. It is a continuous network of structure that binds tissues into their organ shape. It also supplies the internal organ's life support with vessels and ducts, and securely fastens each organ within the body


Small Intestine, Bladder
Lungs, Spleen
Large Intestine, Stomach
Kidney, Heart
Triple Burner, Gall Bladder
Pericardium, Liver

Figure 7.38. The Body's Twelve Skin Zones, Based on the External Flow of Qi from the Twelve Primary Channels and Their Collaterals

cavity. This connective tissue surrounds and anchors the vessels within the muscles, bones, and organ tissue. Its fluid nature supports the entire body structurally by hydrostatic pressure. Any stimulation on one of the body's Twelve Skin Zones will directly affect the body's connective tissue, and will stimulate the corresponding internal organ associated with that particular zone.

The superficial fascia (the connective tissue just under the skin) divides into a top and bottom layer. The top layer is the fatty layer, which constitutes the main fatty tissue of the outer surface of the body and fascia. This fatty layer acts as an insulator, helping to maintain a constant body temperature. It is metabolically active, functionally storing fat as fuel, releasing it in response to nerve and hormonal stimuli. It corresponds to the greasy layer where the Wei Qi circulates throughout the body's tissues. The deeper layer of the superficial fascia envelopes the nerves, veins, arteries, lymph vessels, and nodes.

From a Traditional Chinese Medical perspective, the Qi circulating within the body's inner fascial connective tissue can be stimulated through the external energy stimulation of the Twelve Skin Zones. Heat and movement help maintain the body's connective tissue's base fluids, facilitating movement and the conduction of energy. Any obstruction occurring on the body's surface tissues can result in the binding or thickening of the connective tissue, thus creating adhesions. This obstruction slows the metabolic process and compromises the body's immunity (Figure 7.38).

If the integrity of the connective tissue is compromised, the body's immune system declines. Compartments of connective tissue influence the spread of toxins, diseases, infections, and tumors. The fibrous walls, as well as chemicals in the fluid of the connective tissue, prevent the spread of pathogens from one area of the body to another.

CLINICAL DIAGNOSIS AND THE TWELVE SKIN ZONES

Clinically, the diagnosis and treatment techniques relating to the use of the Twelve Skin Zones is quite extensive. In diagnosis, the skin's surface area along these zones is examined for evidence of discoloration or tissue obstruction. Changes in skin color and tissue formations are observed and categorized as follows.

1. A darkish hue reflects obstruction of Qi and Blood.
2. A bluish-purple color indicates local pain.
3. Change in color from yellow to red shows evidence of Heat.
4. A white or pallid skin tone signifies Deficiency or Cold.
5. Boils, pimples (especially on the back), hives, and eczema, as well as hard lumps or nodules beneath the surface of the skin, indicate diseases associated with the Twelve Primary Channels (manifesting through the Twelve Skin Zones).

A palpable lump can develop from a variety of sources, including congealed or stagnant Blood. There are generally eight types of lumps observed in the clinical environment:

1. The Shrimp Lump, is shaped in the form of a shrimp.
2. The Turtle Lump, is named for its shape and multiple lump formations.
3. The Blue Lump, derives its color from the superficial blood vessels on which it forms.
4. The Single Lump, is diagnosed as opposed to multiple lump formations.
5. The Dry Lump, indicates an obstruction.
6. The Blood Lump, relates to congealed Blood.
7. The Abdominal Lump, is named for its physical location.
8. The Yellow Lump, is named because of the yellow pallor in the specific region of the lump.

PALPATING THE PATIENT'S SKIN

Before palpating and diagnosing the skin, the Qigong doctor first scans the patient's body to feel the temperature, moisture, and texture of the patient's tissues.

1. The doctor scans and palpates the patient to diagnose the condition according to the temperature:
    a. If the skin feels hot to the touch it often indicates a presence of a Damp-Heat condition.

   b. When first touching the patient with light pressure if the skin feels immediately hot, and as the pressure is maintained the feeling of heat increases, this indicates an invasion of Exterior Wind-Heat (with a pathogenic factor still on the exterior surface).
   c. If the skin over a blood vessel feels hot on medium pressure, it indicates Interior Heat in the Middle Burner or Heart area.
   d. If the skin feels hot on deep, heavy pressure, it indicates an Empty-Heat condition from a Yin Deficiency.
   e. If the skin feels cold to the touch, it often indicates a Cold condition. This condition is often manifested in the lower back and lower abdominal region, indicating a Deficiency of the Kidney Yang.
2. The doctor scans and palpates the patient to diagnose the condition according to the amount of moisture:
   a. A moist feeling of the skin may indicate an invasion of the Exterior by Wind-Cold or Wind-Heat.
   b. If the skin feels moist due to spontaneous sweating, it indicates a Deficiency of the Lungs' Qi (in the absence of exterior symptoms).
3. The doctor scans and palpates the patient to diagnose the condition according to the texture:
   a. If the skin is scaly and dry, it indicates an exhaustion of the Body's Fluids.
   b. If the skin feels dry, it indicates either a Yin condition of the Lungs or a Blood Deficiency.
   c. If the skin is swollen and an indentation is left visible after pressing, it indicates Edema (called Water Swelling).
   d. If the skin is swollen and no indentation is left visible after pressing, it indicates a retention of Dampness (called Qi swelling).

CHANNEL AND COLLATERAL THERAPY

Because the Yin and Yang organs' Qi flows within the body's internal and external surfaces, all the internal and external channels and collaterals, five tissues (tendons, blood vessels, muscles, skin, and bones), and five sense organs (eyes, ears, nose, mouth, and tongue), together create an energetic network. Through practicing sitting meditations, patients as well as Qigong practitioners become aware of the circulation of Qi along the body's channels and collaterals. The awareness of what the Qi feels like enables the meditators to feel the flow and function of each channel, as well as the Blood and heat cycle in each Skin Zone. This makes it possible to control the Qi circulation through intention and imagination.

Balancing the Conception and Governing Vessels is of the utmost importance in the practice of any Qigong regulation. Along these two Vessels the Qigong practitioner draws the Yang Fire and Yin essences up and down the body, thus fusing the Water and Fire energies. This fusion is utilized by the doctor in every Qigong treatment, and is responsible for balancing the patient's Yin and Yang energy. This balance is created through the discipline of the Microcosmic Orbit meditation, which connects the Governing and Conception Vessels.

The students' awareness of Qi flowing through the body usually develops in three distinct stages:

1. First, they begin to feel the energy flow along the surface channels of the body, especially within the areas of the extremities. Usually at this stage, the students will feel heat and tingling sensations within the body's surface muscles.
2. Next, they begin to feel the energy flow deeper within their tissues, especially along the tendons, deeper muscles, and visceral organs. Usually at this stage, they begin to feel mild electric shocks and vibrations within their muscles, bones, and visceral organs.
3. In the final stage, they feel the Earth and Heaven energy penetrate through their body's

outside channels and inner organs, connecting into their Taiji Pole, and then turning outward again. Usually at this stage, they will feel their entire energized body vibrate. This vibration may be triggered through either universal or environmental changes, as the Medical Qigong practitioner becomes hypersensitive to any form of external energetic disturbance.

CONTROLLING QI EXTENSION THROUGH THE CHANNELS

The Qigong doctor must first be able to control his or her own energy circulation, causing it to flow in or out, expand or contract at will, before beginning to extend energy for the treatment of any patient. This energetic control is gained through specific imagination and visualization techniques. The fundamental theory for these techniques is "The imagination leads the Mind, the Mind leads the Qi." The doctor must be able to utilize energy from the natural environment (trees, waterfalls, ocean, desert, etc.) in order to replenish and facilitate his or her own energy.

By drawing in Heavenly Qi and combining it with his or her body's connection to Earthly Qi, the doctor may mobilize and activate the Qi of the patient. This combining method establishes an energetic healing field of Qi, which responds to the Qigong doctor's own Qi circulation, as well as to that of the natural environment, which includes the patient. This ability must be achieved in order to activate the patient's Qi and then regulate it by purging the Excess Qi, replenishing the Deficient Qi, dredging the channel Qi, and guiding the Qi back to its origin.

CHAPTER 8
THE BODY'S ENERGETIC POINTS

INTRODUCTION TO ENERGETIC POINTS

The Chinese word for point is Xue or Xue Wei, meaning "cavity place, cave, den, hole, or hollow." Although the Chinese word Xue is usually translated into English as "point" or "acupoint," it is valuable for the English-speaking student to understand the word's different connotations. Points are almost always located in hollows or depressions, which are physically palpable and found in over 1,000 locations all over the body. Many, but not all, are located along the channels and vessels. Sometimes when touching a point, it feels as if your fingertip has found the entrance of a small cave or opening hidden by the skin covering it.

The word Xue also implies a den or lair: thus, it is not only a cave but a home for some type of powerful life form. In the human body, our living Qi gathers and pools within these protected hollows (Figure 8.1). For this reason, some writers have preferred to translate Xue as "vital hollow," rather than "point." Because of its popular acceptance, I have chosen to use the term "point" throughout this book.

THE FOUR WAYS POINTS ARE FORMED

Generally, points are formed in four ways. The first type of point occurs when two muscles, tendons, or ligaments intersect or overlap in a way that creates a small depression at the area of convergence. To form the depression, the two muscles either come together, separate, overlap, or run parallel to each other. Usually the channels lie under a protective layer of muscle, but at the aforementioned junctures, the channels may be exposed, and thus closer to the surface.

The second type of point occurs when a nerve is exposed in an area without much muscle tissue to cover and protect it. Because the nerve is exposed, such points are especially sensitive, and may cause a sharp pain or an electric shock sensation when stimulated.



Figure 8.1. The energetic points are considered the body's small energetic pools.

The third type of point lies under a protective superficial layer of muscle. It can however, still be stimulated due to its natural sensitivity and because the overlying layer of muscle is thin.

The fourth type of point lies in depressions on the surfaces of the bones and cartilage. These depressions may take the form of grooves, pits, hollows, indentations, fissures, or crevices.

SCIENTIFIC RESEARCH OF ACUPOINTS

In the early 1970's, shortly after President Nixon's historic visit to China, Dr. Robert O. Becker, M.D., a Syracuse University orthopedist, received a grant from the National Institutes of Health to research how acupuncture works. Dr. Becker reasoned that the channels were electrical conductors (independent of the nervous system yet communicating with it) that carried an injury message to the brain, which responded by sending back the appropriate level of direct current (DC) to stimulate healing in the troubled area."

Becker also suggested in his book *The Body Electric,* that "any current grows weaker with distance, due to resistance along the transmission cable. The smaller the amperage and voltage, the faster the current dies out. Electrical engineers solve this problem by building booster amplifiers every so often along a power line to get the signal back up to strength. For currents measured in nanoamperes and microvolts (such as those generated in the human body), the amplifiers would have to be no more than a few inches apart—just like the acupuncture points."

Dr. Becker and his assistant, Maria Reichmanis, a young biophysicist, designed special equipment to measure and map the electrical conductivity along the channels. They found the predicted electrical characteristics along the channels and at half the points. These same points showed up on all the people tested. They suggested that the other traditional points may simply be weaker, or of a different kind, than the ones that their instruments detected.

Each point that they found was electrically positive compared to its surrounding tissue, and each point had an electrical field surrounding it with its own characteristic shape.

Later research (see appendices) in China, France, and the United States has shown not only that these points and channels have electrical properties but that they also emit and absorb light and sound, both of which are vital to healthy biological functions.

THE FOUR CATEGORIES OF ENERGETIC POINTS

Points are divided into four categories (Figure 8.2) and are described as follows.

1. Channel points are the Primary points that are distributed along the Twelve Primary Channels and the Conception and Governing Vessels. There are 365 channel points.
2. Extra points are not regarded as having a specific origin in the fourteen main channels, although they are named and are in definite locations. These points are also called "miscellaneous points."
3. New points are a fairly large group of points discovered since the Communist "Liberation" of 1949, in many cases through electric point detection. These points generally have no energetic description, but do have indications. Combined with the Extra points, there are more than 700.
4. Ahshi Points are tender or painful spots near a diseased or injured area and can be anywhere, on or off of traditional points and channels. They function like trigger points, as they are points of tension or pain. Ahshi points are not given specific names or definite locations as they are mostly used for pain syndromes.


Four Categories of Energy Points
Channel Points
Extra Points
New Points
Ahshi Points or " Trigger" Points

Figure 8.2. The Four Categories of Energetic Points

THE TWO GATES OF ENERGETIC POINTS

Another way of categorizing the points is into the two general types commonly used by the Qigong doctor.

1. The Outer Qi Gates are points through which the patient's Shen and Qi enter and leave the body. The Qigong doctor or patient may gather healing Qi from the outer environment through these gates. In terms of pathology, these points are especially vulnerable to the Six External Pathogens, i.e., Cold, Hot, Wind, Damp, Dry, and Fire invasion (see Chapter 21), which may enter the body through these gates. These same pathogens may also be ex-

pelled through these gates. For this reason, many of these outer Qi gates have the word Feng (Wind) in their names, such as Fengchi GB-20 (Wind Pool).

2. The Inner Qi Gates are points through which the Qi of the Yin and Yang organs and channels is transported back and forth internally and externally, deeply and superficially. These points are more involved with the movement of Qi within the body and are less involved in the exchange with the outer environment. In this way, the Inner Qi Gates enable the Qi to communicate between the different parts of the body.

These two types of points (or gates) are specific areas where the Qigong doctors concentrate their intention and focus their energy extension. Point locations have a greater amount of accumulated Qi, and are used for dispersing or tonifying the body's organ energy, to promote the correct balanced circulation of Qi and Blood.

THE THREE FUNCTIONS OF ENERGETIC POINTS

The points can be used for three clinical functions: to manipulate Qi and Blood, for diagnosis, and to serve as pathways for the elimination of disease.

1. Qi and Blood can be manipulated to purge Excess conditions, tonify Deficient conditions, or for regulation.
    a. To disperse Excess conditions, the Qigong doctor emits Qi over a specific point (or points) and begins to purge, or disperse, the energy in the area (to purge is to remove toxins directly from the organ, whereas to disperse is to lead the toxins out through the channels). The goal of this treatment is to move any Excess, particularly stagnant Qi and Blood. If only Qi is stuck, the pain will move and feel dull. If only Blood is stuck, the pain will not move and will be sharp. This distinction, however, is more important in Chinese herbology than it is for medical Qigong, acupuncture, or massage because, as stated in the classics, "Qi is the commander of Blood"; therefore, moving the Qi in the latter therapies will also move stagnant Blood.
    b. To tonify a Deficient condition, the Qigong doctor emits Qi over a specific point or points, and begins to tonify or strengthen the patient's Qi, Blood, Yin, Yang, or specific organs and tissues. The Qigong doctor uses varying techniques according to the patient's needs (e.g., in order to prevent feeling discomfort, the doctor will tonify weak patients slowly).
    c. To regulate, the Qigong doctor emits Qi over a specific point or points, and allows the body's natural homeostasis to take over and restore healthy function. This type of treatment is also used when a patient has a combined Excess/Deficiency syndrome (such as stagnant Qi in the chest due to a Qi Deficiency in the Lungs and Kidneys).

The healing potential of point stimulation can be accomplished through various modalities, such as Energy Projection, Energetic Point Therapy, Jing Point Therapy or Invisible Needle Therapy.

2. Diagnosis through point palpation and inspection is an important diagnostic tool in all the branches of Chinese medicine. If a point hurts when touched with light pressure, is hard or swollen, or is purple, black and blue, or red, this indicates an Excess condition. If the point hurts on deep pressure or is soft to the touch, lacks resilience, or is sallow in color, it indicates an underlying Deficiency.

The skin over points often feels sticky, in contrast to the slippery or smooth quality of the skin surrounding the point. When passing the fingers over a point, the doctor generally feels the energetic pulse of the channel. When touched, the point energetically responds like an echo, vibrating along the channel into the organ and then back again to the

Practice:

1. Preparation

When you begin, first do Formula Two and then continue with this practice.

a. Sit properly on a chair and feel yourself aligned with the forces.
b. Do the crane and turtle neck and the spinal cord breathing
c. Smile down and generate the qualities of loving energy from the heart. Breathe down radiance to the heart making it feel soft in the heart.
d. Be aware of the Tan Tien Chi and the front pakua, the pakua on your face, and the universal pakua. Feel them all breathing together. Feel all your senses and mind turned inwards to the cauldron. Turning the senses inward initiates the training process of inner observation. In developing the ability to focus inward – to smell, listen, taste, see and hear the organs and their activities – and to observe your negative emotions without predetermined judgments, you have the opportunity to develop your true nature.



Fig. 5.73 *Feel joy and happiness.*
a. *Inhale to the heart and smile to the heart.*
b. *Exhale to the heart, smile to heart and make the heart feel soft.*



Figure 8.3. Weak or Deficient tissue will naturally pull and absorbe Qi into the surrounding areas.



Figure 8.4. Strong, Excess, or Armored tissue will naturally repel Qi from the surrounding areas.

doctor's finger. The doctor can use this energetic response for diagnostic evaluation by sending a pulse along the flow of the channel or against it (into the organ itself). Once sufficient stimulation is applied to the point, its organ or region is "reminded" of its normal function. In this way, diagnosis and treatment are accomplished simultaneously.

Once the location and energy flow of the channel to be treated is diagnosed, the doctor must take into consideration that each patient will react differently in accordance with the severity of symptoms, as well as the individual's constitutional type. Before beginning treatment, the doctor should extend Qi between the energetic point's boundary (the space separating the Wei and Ying energy levels), until the soreness or distention is felt on the tips of the doctor's fingers or palms (which act like a barometer). This form of diagnosis determines the condition of the channel and the area needing treatment. Although the feelings and sensations will vary with each patient, energetic truths remain constant. For example:

a. Weak or Deficient areas will feel like an empty hole or deep well. Deficient Blood or Qi will actually pull the energy into the area and will feel something like a subtle vacuum suction. If the area that the doctor is treating attacks his or her Qi and begins to absorb it, the doctor should tonify that area immediately. Think of this reaction as a dry house plant starving for water. The minute the water touches its soil, the plant immediately absorbs it into its roots (Figure 8.3).

b. Strong or Excess areas will repel the doctor's Qi. If the diseased area repels the doctor's Qi, he or she must immediately dredge the Excess. First, the doctor should focus on the region surrounding the Excess to drain the Excess energy away from the damaged points, then dredge the Excess energy away from the original trauma area. This technique is excellent for damaged or sprained joints. The doctor should focus on the patient's breathing when dredging. As the patient inhales, the doctor exhales and vice-versa. As the patient exhales, he or she releases pathogenic factors; by inhaling when the patient exhales, the doctor facilitates this process, and prevents depletion of his or her own Qi (Figure 8.4).

3. Disease transmission may occur due to the External invasion of pathogenic Qi into the body through the points. Some points are particularly vulnerable to exogenous invasions, especially Wind invasion. Wind-susceptible points usually have the word Feng in their names.

POINT NAMES

Traditionally, each point has a name, which either describes its location, its energetic function, or both. In addition, modern acupuncture texts have assigned a name and number for each point, according to its channel and its order along the natural course of the channel.

Sometimes a point may have several different traditional names, varying according to whether they are being used by medical Qigong doctors, acupuncturists, martial artists, or religious practitioners; for example, GV-1 is called Changqiang (Long Strength) in Traditional Chinese Medicine, and Weilu (Tail Gate) in medical Qigong and Daoist inner alchemy.

The history of point naming and the different terminologies used can be traced back to the different Buddhist and Daoist temples in ancient China. Each religious sect had its own specific names given to certain points, in accordance with the temple's spiritual and energetic needs. Giving the points different names was a form of secret code, used to keep the system pure and to prevent the knowledge from falling into the hands of the uninitiated or unscrupulous.

Sometimes the same name may refer to different points or areas on the body; for example, Yuzhen (Jade Pillow), located in the occipital region on the posterior base of the skull, is the name commonly used for Bl-9 in Traditional Chinese Medicine. However, in medical Qigong and Daoist inner alchemy, Yuzhen instead refers to an entire area the size of one's fist placed between the bilateral Bl-9 points.

CLASSIFICATION OF ENERGETIC POINTS

The points are further classified according to their energetic potential. This classification will assist the doctor of Traditional Chinese Medicine in choosing the right point or points to treat. The following is a list of energetic point classifications.

THE FIVE ANTIQUE SHU POINTS

Like the internal organs and channels, some points have a more powerful influence on the body then others. Each point has an action on the quantity of energy of an organ. Along each of the Twelve Primary Channels lie five specific points below the elbow or the knee called Antique Shu points (also called Transporting points and Command points). These points belong to the oldest classification of points, and are described in water images, comparing each section of the channel to the course water takes as it emerges from the ground and makes its way to the ocean. They are identified as follows: Jing (Well), Ying (Spring), Shu (Stream), Jing (River), and He (Sea). These five points are situated along the flow of energy from the extremities to the torso (running from the fingers to the elbows and from the toes to the knees), occupying the same progressive location along the patient's channels (Well, Spring, Stream, River, and Sea).

Centrifugal and Centripetal Energy Flow

All of the body's channel points energetically progress in two opposite currents according to the direction and flow of the channel's energy. These two energy currents are described as follows.

1. The Channel's Outward Centrifugal Flow of Qi passes from the organ, through the channel, to the point, and is expressed or intensified through the patient's exhalation. The outward centrifugal flow of energy is manifested in channel points and in areas of the body where there are conditions of Excess.
2. The Channel's Inward Centripetal Flow of Qi passes from the point, through the channel, to the organ. The inward centripetal flow of energy is manifested in channel points and areas of the body where there are conditions of Deficiency.

Through stimulation, channel points fulfill a double function. Centrifugally, they inform the doctor of impending internal disorders by discharging Excess energy. Centripetally, they transmit the energetic action placed on them, absorbing energy to supply the body's internal insufficiencies.

Yin and Yang Channels and the Five Elements

Each of the Five Antique Shu points also corresponds to the Five Elements, in the progression of the Creative Cycle. Each Yin channel begins

Points	Yin Channel Elements (Ethereal Soul—Hun)	Yang Channel Elements (Corporeal Soul—Po)
Jing-Well Points	Wood	Metal
Ying-Spring Points	Fire	Water
Shu-Stream Points	Earth	Wood
Jing-River Points	Metal	Fire
He-Sea Points	Water	Earth

Figure 8.5. The Five Antique Shu Points and their Correspondence to the Five Elements

with the Hun progression through the Five Elements, starting with Wood, then Fire, Earth, Metal, and Water. Each Yang channel begins with the Po progression through the Five Elements, starting with Metal, then Water, Wood, Fire, and Earth (Figure 8.5).

Similar to the eyes relationship to Wood (Hun) and Metal (Po), the beginning points on the Twelve Primary Channels also have a relationship to either a Wood (Ethereal Soul) or Po (Corporeal Soul) connection. Hence, in meditation exercises, when specific finger tip points are connected, the blending of the Hun and Po energies are established. The practice of connecting specific finger tip points is sometimes referred to as the connection (or fusion) of the body's Ethereal and Corporeal Soul.

The Five Antique Shu points energetically flow from superficial to deep and are susceptible to external pathogens and climatic changes. The distal points on the feet tend to be more powerful than those on the hands. After the manipulation of the patient's distal points, the local channel points are used according to their feeling of tenderness. The Five Transporting points are explained as follows.

1. Jing-Well points are the first points along the extremities of the channels and are located at the tips of the fingers and toes. These points are where the energy of the channel pools and is at its most superficial and thinnest.

   These points are where the energy of the channels leaves the body moving centrifugally outward. At the end of the fingertips and toes, the channel's energetic polarity changes from Yin to Yang or vice versa. Due to this shift in polarity, the energy at the channel's extremities tends to be unstable, and therefore more easily influenced.

   Due to their outward movement of energy, the Well points can be used by the Qigong doctor to eliminate the patient's pathogenic factors quickly, especially when the Yin organs are affected. The Well points will also have a strong effect on the patient's mental state, quickly changing the patient's mood. These points are generally used for acute disorders, expelling exogenous pathogens, and mental disorders. They are used as "revival" points for loss of consciousness from fainting and heat stroke, convulsions, a feeling of fullness below the Heart, and local neuropathy (tingling, numbness, burning pain). In mental disorders, they are commonly used for irritability, mental restlessness, anxiety, hysteria, mania, and insomnia.

2. Ying-Spring points are the second points along the channels and, in all cases, are located in the second position of the channels' energetic progression up the arms or legs, and are located next to the Well points. These points are where the channel's energetic flow quickens its progression of Qi into the body.

At the location of the Spring points, the Qi in the channels is very dynamic and powerful. Slipping and gliding like the swirling movement of cascading water, the energy in these points can change quickly. The Spring points are generally used to eliminate Internal and External pathogenic factors (especially Heat) from the patient's body. They are also used when a disease effects a color change in the patient's complexion.

In the Yin channels, this point is always a Fire Element. Purging the Spring point in the Yin channels reduces Heat and clears Fire. In the Yang channels, the Spring point is always the Water Element point. The doctor can reduce Heat in the patient's Yang channel by tonifying this Water point.

3. Shu-Stream points are the third points along the channels and are located in the third position in the channels' energetic progression up the arms or legs, next to the Spring point (except for the Gall Bladder's Channel where it is the fourth point). These points are where the channel's energy rapidly pours through and slightly deepens its flow into the body.

   At these points, the external pathogenic factors penetrate deep into the channels and can be "transported" into the body's interior. These points are used to clear Wind and Dampness from the patient's channels or when a disease manifests intermittently.

4. Jing-River points are the fourth of the Five Transporting points; they are, however, not always located on the fourth point along the channel. The points are, however, always located between the wrist and elbow on the arms and between the ankle and knee on the legs. These points are where the channels broaden, and the energy flow continues to increase.

   At these points, the energy current flows wider, deeper, and more irregularly, like a large river, directing the invasion of external pathogenic factors towards the body's tendons, joints, and bones. These points are generally used when there is stagnation of Qi and Blood in the patient's channels, as well as for coughing, asthma, dyspnea, sore throat, and upper respiratory diseases.

5. He-Sea points are the fifth points of the Five Transporting points and, in all cases, are located at the elbows and knees. These points are where the energy of the channels is vast and plunges deep into the body.

   The Qi at the He-Sea points moves centripetally inward, flowing much slower, joining, collecting, and fusing with the general circulation of the body's energy (like a mighty river flowing into the sea). The He-Sea points are generally used for all Stomach and Intestinal diseases and for Internal disorders of the organs.

THE FIVE ELEMENTAL POINTS

Each of the Five Elemental points correspond to the Five Antique Shu points. The Five Elemental points are aligned in the progression of the Creative Cycle. Each Yin Channel begins with the Three Ethereal Souls (Hun) progression through the Five Elements, starting with Wood, then Fire, Earth, Metal, and Water. Each Yang channel begins with the Seven Corporeal Souls (Po) progression through the Five Elements, starting with Metal, then Water, Wood, Fire, and Earth.

THE SIXTEEN XI CLEFT (ACCUMULATION) POINTS

These points are used for purging acute conditions of Excess in the channels and organs. There is one point on each of the Twelve Primary Channels, plus one point on the Yin and Yang Heel Vessels, and one point on the Yin and Yang Linking Vessels. The Yin Channel Accumulation points are Lu-6, Pc-4, Ht-6, Sp-8, Lv-6, Kd-5, Yin Heel Kd-8, and Yin Linking Kd-9. The Yang Channel Accumulation points are LI-7, TB-7, SI-6, St-34, GB-36, Bl-63, Yang Heel Bl-59, and Yang Linking GB-35.

THE TWELVE FRONT MU (ALARM, COLLECTING) POINTS

The energy of the organs collect at these points; therefore, they can be used for both diagnosis and treatment. These points are palpated for diagnosis and may feel tender to the patient, either spontaneously or upon pressure. If they respond to light pressure or feel tight or swollen, the patient has an Excess condition; if the points respond to deep pressure or feel hollow or deflated the patient has a Deficient condition. The Twelve Front Alarm points are: Lungs Lu-1, Pericardium CV-17, Liver Lv-14, Spleen Lv-13, Gall Bladder GB-24, Kidneys GB-25, Heart CV-14, Stomach CV-12, Large Intestine St-25, Triple Burners CV-5, Small Intestine CV-4, and Bladder CV-3.

THE EIGHTEEN BACK SHU (ASSOCIATED, TRANSPORTING) POINTS

These points are all located on the Bladder Channel and are used for both diagnosis and treatment. These points transport Qi very effectively and directly to the internal organs. They can be used for treating the corresponding sense organs. The Eighteen Back Transporting points are: Lungs Bl-13, Pericardium Bl-14, Heart Bl-15, Governing Vessel Bl-16, Diaphragm Bl-17, Liver Bl-18, Gall Bladder Bl-19, Spleen Bl-20, Stomach Bl-21, Triple Burners Bl-22, Kidneys Bl-23, Sea of Qi Bl-24, Large Intestine Bl-25, Gate to the Yuan Qi (Guan Yuan) Bl-26, Small Intestine Bl-27, Bladder Bl-28, Sacrum Bl-29, and Anus Bl-30.

THE FIFTEEN LUO (CONNECTING) POINTS

One of these points is located on each of the Twelve Primary Channels, as well as the Governing and Conception Vessels and the Great Luo point of the Spleen. These points are used to treat channel pathology. The Fifteen Collateral points are divided into Yin and Yang channel points. Yin Channel points include: Lu-7, Pc-6, Ht-5, Sp-4, Lv-5, Kd-4, CV-15, and the Great Luo Channel Sp-21. The Yang Channel points include LI-6, TB-5, SI-7, St-40, GB-37, Bl-58, and GV-1.

THE TWELVE ENTRY POINTS

These points are where the energy from a Primary Channel enters its coupled channel in the Horary Cycle. The entry point is the first point on each channel in all cases, except for the Large Intestine's Channel in which it is LI-4.

THE TWELVE EXIT POINTS

These points are where the Qi leaves the Primary Channel to flow into its coupled channel in the Horary Cycle. The Yin Channel Exit points include: Lu-7, Pc-8, Ht-9, Sp-21, Lv-14, and Kd-



Figure 8.6. Locations of the Body's Master and Couple Points

Channel	Open with Master Point	Complete with Couple Point
Governing	Hand (SI-3)	Foot (Bl-62)
Conception	Hand (Lu-7)	Foot (Kd-6)
Thrusting	Foot (Sp-4)	Hand (Pc-6)
Belt	Hand (TB-5)	Foot (GB-41)
Yin Linking	Hand (Pc-6)	Foot (Sp-4)
Yang Linking	Foot (GB-41)	Hand (TB-5)
Yin Heel	Foot (Kd-6)	Hand (Lu-7)
Yang Heel	Foot (Bl-62)	Hand (SI-3)

Figure 8.7. The Vessels with their Associated Master Points and Couple Points

22. The Yang Channel Exit points include: LI-20, TB-23, SI-19, St-42, GB-41, and Bl-67.

THE EIGHT INFLUENTIAL POINTS

These points have specific effects on their respective organs, substances, and tissues. They affect the body's Qi, Blood, sinews, blood vessels, bones, and Marrow, as well as the Yin and Yang organs. The Eight Influential points are as follows: Yin Organs Lv-13, Yang Organs CV-12, Qi CV-17, Blood Bl-17, sinews GB-34, blood vessels Lu-9, Bones Bl-11, and Marrow GB-39.

THE EIGHT CONFLUENT POINTS

These eight points communicate with the Eight Extraordinary Vessels. The Confluent points are divided into Master and Coupled points. The Master point is the primary point chosen for treatment, its Coupled point is the connecting or secondary point used to open the specific Vessel. Each of the Eight Extraordinary Vessels has both a Master and Coupled Confluent point on the upper or lower limbs.

All of the Eight Extraordinary Vessels can be treated in various combinations according to their specific Master and Coupled point locations (Figure 8.6). If, for example, the Qigong doctor causes Qi to flow from the patient's Master point on the hand (SI-3) to its Coupled point (Bl-62) on the foot, the Governing Vessel will open. To complete the treatment, the doctor must first remove stimulation from the Coupled point then disconnect from the Master point (Figure 8.7).

The Eight Confluent points are as follows: Governing Vessel SI-3, Conception Vessel Lu-7, Belt Vessel GB-41, Thrusting Vessels Sp-4, Yang Heel Vessel Bl-62, Yin Heel Vessel Kd-6, Yang Linking Vessel TB-5, and Yin Linking Vessel Pc-6.

THE TWELVE YUAN-SOURCE POINTS

Each of the Twelve Primary Channels has a Yuan-Source point, where the body's Original Qi surfaces and pools. On the Yin Channels, the Yuan-Source points are always the Shu-Stream points. On the Yang Channels, however, the Yuan-Source points are separate points located between the Shu-Stream and the Jing-River points. These points are usually the fourth point from the distal end of the channel, except in the case of the Gall Bladder Channel, where the Yuan-Source point is the fifth point.

The Yuan Qi originates and resides in the Lower Dantian area and is dispersed to the Yin and Yang organs and then to the limbs by the Triple Burners.

The Yuan-Source points can be used clinically in diagnosis for the Yin organs. The Qigong doctor examines the points by both palpation and visual diagnosis.

The Yuan-Source points are the primary points on the Yin channel for tonifying and regulating their respective Yin organs. On the Yang Channels, the Yuan-Source points are quite different in terms of their importance and energetics. These points generally have a negligible tonifying effect on their related Yang organs and comparatively little Qi regulating effect. Their main functions are to expel various pathogenic factors, and to treat disorders along their channel pathways. The Twelve Yuan points are as follows: Gall Bladder GB-40, Liver Lv-3, Lungs Lu-9, Large Intestine LI-4, Stomach St-42, Spleen Sp-3, Heart Ht-7, Small Intestine SI-4, Bladder Bl-64, Pericardium Pc-7, and Triple Burners TB-4.

THE POINTS OF THE FOUR SEAS

The human body has four seas: the Sea of Qi, Sea of Blood, Sea of Marrow, and the Sea of Nourishment (literally Water and Grain). To access these seas, the Qigong doctor stimulates the following points:

1. The Sea of Qi points include: Bl-10, St-9, CV-17, GV-14 and GV-15. When the Sea of Qi is in Excess, symptoms include fullness in the chest, flushed complexion, and dyspnea. When the Sea of Qi is Deficient, symptoms include fatigue or low energy and an inability to speak.
2. The Sea of Blood points include: Bl-11, St-37, and St-39. When the Sea of Blood is in Excess, symptoms include anxiety, uneasiness, and unrest, and the entire body feels big. When the Sea of Blood is Deficient, symptoms include the body feeling too small for no apparent reason.
3. The Sea of Marrow points include: GV-15, GV-

16, GV-17, and GV-20. When the Sea of Marrow is in Excess, symptoms include sensations relating to that of Excess energy (lightness, feelings of strength and vitality). When the Sea of Marrow is Deficient, symptoms include fatigue, vertigo, dizziness, tinnitus, pain in the lower legs, impaired vision, and a desire to sleep.

4. The Sea of Nourishment points include: St-30 and St-36. When the Sea of Nourishment is in Excess, the abdomen feels distended. When the Sea of Nourishment is Deficient, symptoms include hunger with an inability to eat.

UPPER (UNITING) HE-SEA POINTS

There are three points on the upper arm that have a powerful effect on the Yang organs. The affected organs and their points include the Stomach LI-10, Large Intestine LI-9, and the Small Intestine LI-8.

LOWER (UNITING) HE-SEA POINTS

Each of the Yang organs has a uniting He-Sea point on the leg, which can be used to treat Yang organ problems. The three Yang channels of the feet also correspond to the three Yang channels of the hands. The Lower Six Lower He-Sea points are as follows: Stomach St-36, Large Intestine St-37, Small Intestine St-39, Triple Burners Bl-39, Bladder Bl-40, and Gall Bladder GB-34.

THE ELEVEN GHOST POINTS

In ancient times, these eleven points were traditionally used for spirit possession and have a specific effect on the mind's psychological functions. In traditional Chinese medical clinics today, these points are commonly used to treat emotional disorders. The Eleven Ghost points are as follows: GV-26, Lu-11, Sp-1, Pc-7, Bl-62, GV-16, St-6, CV-24, Pc-8, GV-23, and LI-11.

THE TEN WINDOW OF THE SKY POINTS

These ten points also have a specific effects on the mind's psychological functions and are also commonly used to treat emotional disorders. The Ten Window of the Sky points are as follows: Lu-3, LI-18, TB-16, Bl-10, St-9, CV-22, GV-16, SI-16, SI-17, and Pc-1.

SUMMARY OF POINTS

Understanding the origin and function of the body's energetic points, as well as the Qi flow along the energetic channels, allows the Qigong doctor to emit energy through these energetic cavities to easily access the tissues and internal organs of the patients body. It is through this understanding that the doctor can also lead and purge the Toxic or pathogenic Qi (which has become stagnant or detrimentally active within the patient's body) away from the diseased organs, through the channels and out the body.

The following graph (Figure 8.8) is a basic categorization of the body's points and their descriptions.

Category	Points	Description
Five Antique Shu Points	Jing-Well, Ying-Spring, Shu-Stream, Jing-River, He-Sea	Transporting and Command Points
Sixteen Xi Cleft Points	Yin: Lu-6, Pc-4: Ht-6, Sp-8, Lv-6, Kd-5, Yin Heel Kd-8, and Yin Linking Kd-9 Yang: LI-7, TB-7, SI-6, St-34, GB-36, Bl-63, Yang Heel Bl-59 and Yang Linking GB-35	Accumulation Points
Twelve Front Mu Points	Lungs Lu-1, Pericardium CV-17, Liver Lv-14, Spleen Lv-13, Gall Bladder GB-24, Kidneys GB-25, Heart CV-14, Stomach CV-12, Large Intestine St-25, Triple Burners CV-5, Small Intestine CV-4, and Bladder CV-3	Alarm, Collecting Points
Eighteen Back Shu Points	Lungs Bl-13, Pericardium Bl-14, Heart Bl-15, Governing Vessel Bl-16, Diaphragm Bl-17, Liver Bl-18, Gall Bladder Bl-19, Spleen Bl-20, Stomach Bl-21, Triple Burners Bl-22, Kidney Bl-23, Sea of Qi Bl-24, Large Intestine Bl-25, Gate to the Original Qi (Guan Yuan) Bl-26, Small Intestine Bl-27, Bladder Bl-28, Sacrum Bl-29 and Anus Bl.30	Associated, Transporting Points
Fifteen Luo Points	Yin: Lu-7, Pc-6, Ht-5, Sp-4, Lv-5, Kd-4, CV-15, the Great Luo Channel Sp-21 Yang: LI-6, TB-5, SI-7, St-40, GB-37, Bl-58 and GV-1	Connecting Points
Twelve Entry Points	The first point on each channel except for the Large Intestine Channel in which it is LI.4	Qi enters Channel
Twelve Exit Points	Yin: Lu-7, P-8, Ht-9, Sp-21, Lv-14 and Kd-22 Yang: LI-20, TB-23, SI-19, St-42, GB-41 and Bl-67	Qi exits Channel
Eight Influential Points	Yin Organs Lv-13, Yang Organs CV-12, Qi CV-17, Blood Bl-17, Sinews GB-34, Blood Vessels Lu-9, Bones Bl-11 and Marrow GB-39	Influence Internal Organ Function
Eight Confluent Points	Governing Vessel SI-3, Conception Vessel Lu-7, Belt Vessel GB-41, Thrusting Vessels Sp-4, Yang Heel Vessels Bl-62, Yin Heel Vessels Kd-6, Yang Linking Vessels TB-5 and Yin Linking Vessels Pc-6	Master and Couple Points
Twelve Yuan-Source Points	Gall Bladder GB-40, Liver Lv-3, Lungs Lu-9, Large Intestine LI-4, Stomach St-42, Spleen- Sp-3, Heart Ht-7, Small Intestine SI-4, Bladder Bl-64, Pericardium Pc-7, and Triple Burners TB-4	Source of Original Qi Points
Four Seas Points	Sea of Qi Points: Bl-10, St-9, CV-17, GV-14 and 15 Sea of Blood Points: Bl-11, St-37 and 39 Sea of Marrow Points: GV-15, 16, 17, and 20 Sea of Nourishment Points: St-30 and 36	Give Access to the Four Seas
Upper He-Sea Points	Stomach LI-10, Large Intestine LI-9 and the Small Intestine LI-8	Affect the Yang Organs
Lower He-Sea Points	Stomach St-36, Large Intestine St-37, Small Intestine St-39, Triple Burners Bl-39, Bladder Bl-40, and Gall Bladder GB-34	Affect the Yang Organs
Eleven Ghost Points	Governing Vessel 26, Lungs 11, Spleen 1, Pericardium 7, Bladder 62, Governing Vessel 16, Stomach 6, Conception Vessel 24, Pericardium 8, Governing Vessel 23, and Large Intestine 11	Affect the Mind, Emotion, and Spirit
Ten Windows of the Sky Points	Lung 3, Large Intestine 18, Triple Burners 16, Bladder 10, Stomach 9, Conception Vessel 22, Governing Vessel 16, Small Intestine 16, Small Intestine 17, and Pericardium 1	Affect the Mind, Emotion, and Spirit

Figure 8.8. Point Graph

CHAPTER 9
THE EXTRAORDINARY YANG ORGANS

Besides the six Yin organs (Liver, Heart, Pericardium, Spleen, Lungs, and Kidneys) and six Yang organs (Gall Bladder, Small Intestine, Triple Burners, Stomach, Large Intestine, and Bladder), the body has six Extraordinary Yang organs, also called the "curious organs." These Extraordinary organs function like Yin organs (storing Yin Essence, i.e., Blood, Marrow, or Kidney Essence) but look like Yang organs (they are hollow). These six curious organs include the Uterus, Brain, Marrow, Bones, Blood Vessels, and Gall Bladder. The body's Eight Extraordinary Vessels integrate the Extraordinary Yang organs with the main six Yang organs and the Kidneys.

THE UTERUS

In Chinese medicine, the uterus encompasses the fallopian tubes and the ovaries and has the function of regulating menstruation, conception, and pregnancy (Figure 9.1). The uterus connects to the Kidneys (which provide the uterus with Jing), the Conception Vessel (which provides the uterus with Qi and nourishes the fetus), and the Thrusting Channel (which provides the uterus with Blood). Only when the Jing of the Kidneys is sufficient can the menstrual period occur regularly, the woman become pregnant, and fetal growth become possible. The Qi and Blood of the Twelve Primary Channels pass into the uterus through the Thrusting and Conception Vessels, affecting the amount of menstrual flow and its cycle.

The three Yin organs of the Heart, Liver, and Spleen also energetically connect to the uterus through their relationships with the Blood. The Heart governs the Blood. The Liver stores the Blood and regulates the volume of circulating Blood, which is responsible for normal menstruation. The Spleen controls the Blood.



Figure 9.1. The Female Reproductive Organs, including the Uterus, Fallopian Tubes, and Ovaries

2. Real Practice

A. Bring your attention to your kidneys.

Listen to the kidneys, observe your kidneys. Be aware of any fear in the kidneys. Accept your fear; smile to the heart and let the love radiate to the kidneys. Be aware of the Kan, the water power. Chant the Kan and connect your kidneys with this energy. Let love activate the gentleness, calmness and stillness, the essence of this power, a blue light. Wrap the gentleness, calmness around your fear, balancing it and transforming your fear.

Form with your mind a collection point at your perineum and let any fear that is still in the kidneys go down to the collection point. Balance these emotions here also with the positive feeling of gentleness and calmness.



a. **b.**

Fig. 5.74
a. *Fear - Gentleness*
b. *Fear into Gentleness and Calmness*


right and left lateral ventricles (phantom view)
cerebrum
fourth ventricle
third ventricle
cerebellum
cerebrum
thalamus
epithalamus (pineal)
midbrain
hypothalamus
pituitary
pons
cerebellum
medulla oblongata

Figure 9.2. The Human Brain

THE BRAIN

The Brain is considered the house of the Yuan Shen, and the seat of mental function. It is believed that the senses and control of the body's physical movements are related to the Brain. The Brain is functionally related to the Kidneys and controls memory, concentration, hearing, touch, sight, and smell. The Brain is also called the Sea of Marrow, extending from the top of the head to the GV-16 Wind Palace point, just below the external occipital protuberance. The Kidney Essence produces Marrow, which fills the spinal cord and Brain. The Brain also depends on the Heart's Blood for its nourishment. Because the Kidneys store the Jing and the Heart governs the Blood, the Brain depends on the balanced state of the Heart and Kidneys for vitality. The Brain is considered a transformation chamber of both Prenatal and Postnatal Essence (Jing) and Energy (Qi). The Brain is regulated by the Governing Vessel, as well as the Yin and Yang Heel Vessels.

This viewpoint is quite different from the Western approach, which views the brain's anatomy as consisting of five regions (Figure 9.2), including:

1. The cerebral hemispheres or cerebrum (the neocortex (neopallium),
2. The thalamus, hypothalamus, and epithalamus (pineal),
3. The midbrain/mesencephalon (the colliculi and cerebral peduncles),
4. The pons and cerebellum, and
5. The medullae oblongata.

In Western medicine, the oldest part of the Brain (situated at the top of the Brain stem) is often called the "reptilian Brain" because its anatomical formation is similar to that found in lizards, alligators, and turtles. Surrounding it is the mammalian Brain, which is called the limbic system. The third part of the Brain is called the neocortex, which wraps itself around the limbic system. All three parts of the Brain (reptilian, mammalian, and neocortex) are viewed as biologically distinct, both in their chemistry and in their structure. The older formations of the Brain are responsible for the autonomic nervous system, whereas the neocortex is responsible for thinking and voluntary movement.

In Chinese energetic medicine, each selective set of the human brain cells absorbs and records sets of vibrations. The Brain receives these vibrations through the skin, eyes, ears, nose, and mouth, and records them in its cells. The mind interprets these incoming vibrations as images, sounds, smells, and sensations, and organizes these into memories. The extent to which the mind interprets the incoming data depends upon the level of consciousness and awareness of the individual at the time of the recording. When a Qigong doctor, attunes his or her vibrations to the patient's energetic field and emits Qi, the brain cells responsible for storing the vibrations are stimulated. When these vibrations are stimulated through the energy projected by a Qigong doctor, the patient's tissues respond and reproduce an energetic pattern similar to the original one used to record the patient's physical, mental, emotional, energetic and spiritual experiences. This energetic tissue reaction occurs only because the patient's cells are held directly to their same consistent vibrational patterning.

One set of selective brain cells receives, records, and maintains the vibrations of the thoughts, actions, movements, and pictures that other forms project. These vibrations can also be reproduced and projected, being received by the Qigong doctor as images from within his or her own mind through inner-vision. The Qigong doctor can arrange his or her cells' energetic pattern in such a way as to reproduce the words and motions of these forms or objects, even the thoughts of those that sent them. Through these cells, the Qigong doctor can assist his or her patient, as well as him or herself, in controlling their thoughts, as it is through these cells that accidents and disease are brought into existence; for example, someone either observes or imagines a specific thing happening. The corresponding vibration is fixed in the cells, sent out to be imprinted on the corresponding cells of anothers' Brain, then projected back until the incident is so fixed that the occurrence actually happens (self-fulfilling prophecy).

Another set of selective brain cells receives, records, and maintains the vibrations of the thoughts and activities of the divine. The divine energy vibration pervades every substance and is always sending out divine knowledge and true wisdom. Stored within the body are the cells that receive and project the vibrations of the divine Mind. If the doctor separates him or herself from the divine in thought, he or she will also separate from the divine in manifestation.

THE GALL BLADDER

The Gall Bladder stores the bile, which is considered a "pure" fluid. The function of the Gall Bladder is to aid digestion, as well as drain off Excess Heat from the Liver (Figure 9.3). The Gall Bladder is regulated by the energy of the Belt Vessel.

THE MARROW

In Chinese medicine the term Marrow (Sui) is different from bone marrow as defined in Western medicine. The Marrow is the substance which is the common matrix of bones, bone marrow, the spinal cord and the Brain. The Marrow is rooted in the Jing and is connected to the Lower Dantian through the Governing Vessel. It is regulated by the energy of the body's Thrusting Vessels.

The Kidney Jing is the origin of the Marrow. The Marrow functions to form the bone marrow, as well as nourish the Brain and spinal cord. When the Mingmen warms and nourishes the body, the Marrow becomes full (which sustains the body's vertical posture and gives strength to both the Brain and the bones). When the Marrow is full, thinking is clear. Too much thinking leads to Excess Fire, which burns the Brain, causing dizziness, blurred vision, and tinnitus.

Both red and white blood cells are produced in the Marrow of the bones. The red blood cells (which circulate oxygen and eliminate carbon dioxide) are produced within the body's long bones (humerus, femur, tibia, etc.). The white blood cells (vital to the body's immune system) are produced within the body's flat bones (skull, sternum, scapulae, pelvis, etc.) The type of blood cells that are produced depends on the type of Marrow that predominates.



Figure 9.3. The Gall Bladder

When all of the Postnatal energy acquired from the combination of physical (diet, food, and drink), mental/emotional (thoughts and emotions), and spiritual (prayer, meditation, and sex) cultivations is circulated through the Microcosmic Orbit (Fire Cycle), the Prenatal Qi stored in the bone marrow and Brain become stimulated, awaking the spiritual consciousness. This combination and circulation of physical, mental, emotional, and spiritual energy is why the brain marrow is considered to be constructed from the finest and most subtle essences, manifesting the original and hidden power of the Kidneys.

THE BONES

The bones are related to the Kidney's Jing. The bones support the body's structure, strength, and mobility, as well as store the bone marrow (Figure 9.4). The bones are extremely porous and are always "breathing," they are regulated by the energy of both the body's Conception and Thrusting Vessels. The pores of the bones allow Qi and Blood to be absorbed and released, the same way a sponge absorbs and releases water.

There is a natural union between the energetic function of the Marrow and the bones. The Marrow, held within the bones, assures the power and


temporal
frontal
parietal
maxilla
occipital
mandible
scapula
clavicle
cervical
hyoid
manubrium
humerus
sternum
thoracic
xiphoid process
lumbar
radius
ilium
ulna
ischium
sacrum
femur
coccyx
patella
tibia
fibula
talis
calcaneus

Figure 9.4. The human skeleton consists of 200 bones.


external carotid
internal carotid
vertebral
subclavian
common carotid
axillary
aortic arch
brachial
heart
thoracic aorta
abdominal aorta
radial
ulnar
iliac
femoral
popliteal
anterior tibial
posterior tibial

Figure 9.5. The blood-vascular system of the human body consists of the heart and blood vessels.

smooth suppleness of the bones. The bones, in return, prevent the dissipation of the essential richness of the Marrow.

The bones are the only solid crystalline substance in the body capable of generating piezoelectric charges. These electromagnetic charges generate fields of energy that receive and send impulses to the blood cells, tissues, organs, and channels. The Brain, nervous system, Heart, and lower abdomen also generate electromagnetic fields that resonate with the bones, as well as other crystalline-like structures. The crystalline structures of the bones amplify, radiate, and transmit energy, as well as bio-information, to the rest of the body. The rhythmic oscillation of bone-generated electromagnetic fields is released through the transmission of the bones acting as tuning forks. These living tuning forks vibrate the Qi throughout the body's entire physical structure, extending outward into the body's external Wei Qi fields.

THE BLOOD VESSELS

In Chinese medicine, the concept of Blood is different in characteristic and function from that of Western medicine. Blood originates from the transformation of food and drink by the Spleen, which then transfers the refined food energy to be further enhanced by the Heart Qi, Lung Qi, and the Qi of the air.

Qi and Blood flow together, with Qi being the active force that makes the Blood circulate and keeps it within the blood vessels (Figure 9.5). Both Qi and Blood flow within the channels and blood vessels, continuously circulating throughout the body to nourish, maintain, and moisten the tissues. Qi is an energetic form and is considered a Yang substance, while Blood is a liquid form of energy and is considered a Yin substance.

The blood vessels contain Blood and are indirectly related to the Kidneys, because the Kidney Essence (Jing) produces Marrow, which contributes to the production of Blood. The function of the blood vessels is to transport Qi and Blood throughout the body for nutrition and regeneration. The blood vessels are regulated by the energy of the body's Thrusting Vessels, and the Blood is contained in the blood vessels by the Spleen.

SECTION II

THE THREE OUTER FORCES: HEAVEN, EARTH & MAN

CHAPTER 10

INTRODUCTION TO THE THREE OUTER FORCES

THE NATURAL POWER OF THE THREE OUTER FORCES

The Three Outer Forces (Powers) of Heaven, Earth, and Man represent the sum total of all natural forces and energetic factors, which affect the human body on all levels of existence (physical, mental, emotional, energetic, and spiritual). In ancient times, the relationship between the waxing and waning of Heavenly (universal) and Earthly (environmental) energy, as well as the corresponding shifts, changes, and adjustments occurring within the human body, provided the Chinese sages with the theory of the Three Outer Forces. These ancient Chinese masters discovered that the human body's internal network of systems is directly affected by the influences and variations of energetic cycles of the sun, moon, and stars. We now know that these natural influences also affect atmospheric pressures, causing high and low temperatures, which in turn, affect the body's tissues. Recently, Ukrainian physicists found that human DNA vibrates at the same frequency as solar energy.

The Heaven and Earth Powers are responsible for the energetic field changes that cause adjustments and shifts within man's Jing, Qi and Shen (known as the Three Treasures), stored within the internal organs and tissues. Together the combination of Heavenly and Earthly influences affect the functional status of the body's internal organs and the distribution of Qi and Blood throughout the body.

Each of the body's cells, tissues, organs, and organ systems emanates its own specific electromagnetic energy field. This energetic field pulsates at its own particular frequency, regulating the body's internal energy currents and radiating an energetic field that extends outside the body. The body's energetic field (Wei Qi) interacts with and is influenced by the larger energetic fields surrounding it (i.e., power lines, crowds of people, geological formations in the Earth, and the cosmic fields of the solar system).

THE THREE OUTER FORCE'S NINE TREASURES

Each of the Three Outer Forces manifest through a secondary triad of Treasures. These Three Treasures complete the energetic matrix that encompasses the Outer Forces unified energetic field.

1. The Three Treasures of the Heavenly Power are the energy fields of the sun, moon, and stars;
2. The Three Treasures of the Earthly Power represent the energy of the Earth (soil and rock), wind, and water;
3. The Three Treasures of Man are contained within man's Essence (Jing), Energy (Qi), and Spirit (Shen).

These three intricate networks exchange their energetic influence and affect the functional status, as well as the distribution of the body's Qi and Blood.

THE THREE OUTER FORCES AND CHINESE ALCHEMY

Each of the Three Outer Forces and their Three Treasures also constitute the basis of Chinese internal alchemy, whereby Jing (Essence) is transformed into Qi (Energy), Qi is transformed into Shen (Spirit), and Shen is transformed into Wuji (infinite space), and then released back to the Dao (or divine).

The Powers of Heaven and Earth are not only interlinked, but also exist as a microcosm or "small universe" within man's physical body. The human body is an active interaction of two basic elements

B. Bring your attention to your heart.

Connect the tongue with your heart, speak with your heart (the spirit of your heart). Observe your heart. Be aware of any impatience, hastiness, cruelty, hatred, arrogance in your heart. Accept these feelings. Be aware of the Li, the fire power. Chant the Li and connect your heart with this power, a red light. Feel the warmth, love, happiness and inner joy, the essence of this power. Help transform the hatred into love. Wrap the love, the warmth and inner joy around your impatience, arrogance, balancing them with and transforming your impatience, hastiness, arrogance.

Form with your mind a collection point near the heart center and spiral all the negative energies that are still in the heart to this collection point. Chant the Li again and balance the emotions in the collection point.



a. **b.**

Fig. 5.75 a. *Impatience, Hastiness and Hatred*
b. *Love, Joy and Happiness*

of Yin and Yang polarity. Yang energy ascends and is expressed through expansive, active, hard, and aggressive energetic movements. Yin energy descends and is expressed through contractive, passive, soft, and yielding movements. All matter, from the smallest molecular particles to enormous planets and stars, is composed of energy and bound into various patterns of vibration. These matter formations are held in place by electromagnetic and nuclear forces interconnected by the power of Yin and Yang polarity, and are expressed through the Three Outer Forces. The seasonal cycles are an example of Yin Earthly movements, while the solar and lunar cycles are expressions of Yang Heavenly energy.

The creation and manifestation of matter is composed and regulated by what are known as the Five Elemental patterns. In traditional Chinese understanding, it is believed that perfect health and longevity depend largely on man's ability to harmonize with the transitions and five seasonal changes of Heaven and Earth, in accordance with the Five Elemental patterns. In the winter, for example, there is less sunlight, and the temperature can be very cold (Yin), and the Kidneys (Water Element) can easily be overworked; therefore, man should endeavor to lighten his work load and rest more in winter, conserving his Qi to avoid energy depletion.

The principles of Chinese cosmology, Yin and Yang Theory, Five Elements Theory, the *Book of Changes (Yi-Jing),* and Traditional Chinese Medicine are all incorporated into the study of Medical Qigong. This culmination of knowledge reveals the basic structures of energetic dynamics relating to the universal and environmental energy gathered from the Heavens and Earth, and their relationship with man.

HEAVENLY QI

The first of the Three Outer Forces is known as the Universal Force, Original Force, or Heavenly Energy. This force manifests as the energy of the entire Cosmos. Each life born into human form is not only developed and structured but is also influenced by its own unique group of stars within the Heavenly realm. This particular group of stars (including the sun, moon, planets, and constellations), controls or influences the persons life-force energy (Figure 10.1).

Heaven is the realm that predetermines the energetic cycles of birth and death, as well as the seasons and times of planting, fertility, and harvest. It is the source of the Yuan Shen and the Virtue of Dao, as it manifests through universal awareness (divine inspiration, enlightenment and spiritual communion), and free will. Heaven is the residence of spiritual deities and the Jade Emperor (or Divine Creator), and it manifests its prenatal power in man's life through the mysterious forces of fate, destiny, karma, and reincarnation.

According to the ancient Chinese, we exist in a three-dimensional world that exists within the relative parameters of time and space. Heaven represents time, which is symbolized by the circle. Because time moves in circles, hours and days are defined by the circular rotation of the Earth on its axis; months are defined by the circling of the moon around the Earth, and years are defined by the Earth's orbit around the sun.

PHILOSOPHICAL CORRELATION

Man is constantly absorbing energy from the sun, moon, planets, and constellations. In order to explore the patterns of Heavenly energy in detail, the ancient masters developed the science of Chinese astrology, which includes the study of Twelve Animals and Five Elements, as well as the interactions of the Twenty Eight Constellations, Twelve Earthly Branches, Ten Heavenly Stems, Five Planets, and Lunar and Solar Energy Cycles.

The ancient sciences of astrology and divination evolved as a means to analyze, interpret, and predict how the various forces of Heaven influence and guide man's life on Earth. The study of Chinese astrology involves four elements of comprehension: the study of the Signs, the study of the Five Elements, the study of Yin and Yang, and the study of the Sixty-Year Cycle.

1. The Study of the Signs involves the twelve animals of the Chinese zodiac (meaning circus of animals) that encircle the Earth and are divided into twelve equal parts, called "signs." Each sign of the zodiac has certain



Figure 10.1. The Three Outer Forces of Heaven Consists of the Energy Released from the Sun, Moon and Stars.

characteristics that are determined by a particular planet and constellations. The signs affect the character of a person born under them. Each person is given three animal characteristics: one according to the year, the second according to the month, and the third according to the hour of his or her birth. You might, for example, be a Snake according to the year of your birth, a Boar according to the month, and a Dragon according to the hour. The animal governing your birth year represents your external self (the part you show others) and is said to exert a profound influence over your life. The month animal (known as the lunar animal) represents the emotional and psychological aspects of man's relationships. The hour animal represents the inner self (the part hidden from the rest of the world). The combination of the three determines the uniqueness of each individual.

2. The Study of the Five Elements is the next division involved in the study of signs. Each of the twelve animal signs is further differentiated into one of the Five Elements (Wood, Fire, Earth, Metal, and Water). The year of birth determines the element of the sign. Each element rules for a two-year cycle (e.g., January 27, 1952-February 13, 1953 was the year of the Dragon under the element of Water; February 14, 1953-February 2, 1954, was the year of the Snake under the element of Water. The next Water cycle of Dragon and Snake will be in 2012, based on the sixty-year cycle). These Five Elements display an energetic force that affects the formation of the internal organs in the growing fetus, as well as influences the physical, mental, emotional, energetic, and spiritual changes after the child is born.
3. The Study of Yin and Yang is the third division of the study of signs. Each of the twelve animal signs is also governed by a Yin (passive) or Yang (active) direction. The Yin and Yang cycles alternate each year, with Yang being the even years, and Yin the odd years.
4. The Study of the Sixty-Year Cycle is the final division of the study of signs. The yearly correspondence of the twelve animals of the Chinese zodiac also relates to the Twelve Earthly Branches, and is based on a sixty-year cycle. Every sixty years, the sun, moon, Earth, and the North (Pole) Star are in alignment, and a new sixty-year cycle begins. A sixty-year cycle also completes the rotation of the twelve animals through each of the Five Elements. The Chinese consider sixty years a "century" in terms of the human life cycle.

PHYSICAL CORRELATION

Heavenly Qi relates to the congenital strength and formation of the body's internal organs, as determined by the Universal Energetic Fields (which include the energy emitted from the sun, moon, planets, and Twenty-Eight Constellations).

HEAVEN'S ENERGETIC GRID

Similar to the grid system imprinted on the body's energetic field, there exists a massive interconnected Heavenly grid extending throughout the entire universe. This Heavenly grid connects the sun, moon, stars, planets, and constellations throughout our universe, and extends to other solar systems outside our celestial sphere. There are pockets of Heavenly energy (like energetic points), as well as subtle frequency pathways (similar to energetic channels), that follow a progression of universal order.

EARTHLY QI

The second of the Three Outer Forces is known as the Environmental Force, Acquired Force, or Earthly Qi. This force manifests as the energy of the entire planet. Each life born into human form is not only developed and structured but also influenced by its own unique environment within the Earthly realm. The Qi of the individual's particular geographic location includes the energy of the plants, soil, water, animals, and all natural formations responsible for controlling or influencing the person's life-force energy.

The Chinese believed that the Earth is the realm that predetermines the abundance of harvest, as well as the temperance of man's physical stamina. Both harvest and man's physical stamina is determined through the cyclic changes of the five seasons and their relationship to the Five Phases (birth, maturation, peak, decay, and death). The Earth is the source of the natural forces and rhythms of nature, as well as the basic elements and energies that compose the material world of soil and water, mountains and valleys, oceans and rivers, plants and animals. The Earth is the foundational base of the Five Elements through the cyclic transformations of nature, which in turn, shape the human body's physiological form and govern the biological functions of the tissues.

The ancient Chinese viewed the Earth as the center, and as the ground on which we stand looking outward toward the four directions. Just as Heaven defines our movement through life in terms of time, Earth defines the space in which we live, providing the energetic field for our unfolding, within the boundaries of time.

In Chinese symbology, the Earth is symbolized by the image of the square, whose walls face the four cardinal directions. This concept of the energetic interaction of Heaven (symbolized by the circle) and Earth's (symbolized by the square) was so fundamental to ancient Chinese thought that they even designed the coinage of the imperial realm to reflect this interconnection (a round coin with a square center).

PHILOSOPHICAL CORRELATION

Earthly Qi relates to the study of Feng Shui (Harmony of Wind and Water). Feng Shui is divided into two prominent schools of study, the Form School and the Compass School.

1. The Form School is the original school of Feng Shui, originating in Southwest China. This school focuses primarily on developing environmental harmony, by observing the shape and form of the terrain in conjunction with the Five Elemental animals.
2. The Compass School is the second school of Feng Shui. It focuses primarily on developing universal and environmental harmony through the directional orientation of the compass, in relationship to the Ten Heavenly Stems, Twelve Earthly Branches, Twenty-Four Solar Compass Directions, and Twenty-Eight Constellations, as well as the Magic Square and the Bagua (Eight Trigrams).

PHYSICAL CORRELATION

Earthly Qi relates to the "acquired" strength (muscular and skeletal development after birth), as well as the formation of the body's internal organs. Tissue development is determined by the environmental energetic fields (which include the energy emitted from the Earth, Water, and Wind/weather). The Earth energy also expresses its power in man's life through the basic instincts for survival and the primal drives for sex and reproduction.

EARTH'S ENERGETIC GRID.

Similar to the Heavenly energetic grid system imprinted in the cosmos, there exists a massive interconnected Earthly grid extending throughout the entire planet. This Earthly grid connects the planet's eight energetic directions into one energetic field. There are pockets of Earthly energy (like energetic points), as well as subtle frequency pathways (similar to energetic channels), that follow a progression of environmental order. One example of the Earth's axial grid system in Western folklore is the "Ley lines," which are energetic pathways that connect energy vortices or places of power on the planet. This understanding of an Earthly energetic grid system is also reflected in American Indian and South American traditional understanding.

MAN'S QI

The third of the Three Outer Forces is known as the Human Force, or Man's Energy. This force manifests as the energy of the entire body (Figure 10.2). Each life born into human form is not only developed and structured, but also influenced by the individual's adaptations to his or her own physical, mental, emotional, energetic, and spiritual energies.

It is believed that within man, the realm of the Dao or divine conscious spirit exists, wherein both the energies of Heaven and Earth coexist in harmonious balance. Man is formed from the cosmic particles of exploded stars that have descended onto the Earth. These particles are absorbed into the soil, water, and foliage, creating sustenance for human life. This constant internal connection, absorption, and regeneration of vibrating energy from Heaven and Earth is the reason that human life is considered to be the highest physical manifestation of the divine energetic field (see Chapter 1).

PHILOSOPHICAL CORRELATION

Man's Qi relates to the study of the Yi-Jing (I-Ching), or Book of Changes. The Yi-Jing is composed of two sections: the Book of Oracles and the Book of Commentaries.

1. The Book of Oracles is the original text by King Wen and the Duke of Zhou. This book is based on the formation of eight trigrams and their various energetic attributes. These eight trigrams combine to form the sixty-four hexagrams of the Yi-Jing, which were later used for divination.
2. The Book of Commentaries is based on the commentaries of Confucius and his followers, and is also called the Ten Wings. The commentaries are called "wings" because each



Figure 10.2. The Three Outer Forces of Man's Energy is composed of the Energetic Fields Released from Jing, Qi, and Shen.

wing helps the reader to soar higher in comprehension of the original text.

PHYSICAL CORRELATION

Man's Qi relates to the waxing and waning of man's physical, mental, emotional, energetic, and spiritual biorhythmic cycles.

A Qigong doctor must become proficient at understanding, respecting, and adopting these laws of natural variations between nature and man. Through this understanding the doctor can attain a deeper comprehension of the principles and application of Medical Qigong Dao Yin training (mind concentration methods, respiration regulation, and postural manipulation).

MAN'S ENERGETIC GRID

Similar to the Energetic grid system of Heaven and Earth, the human body is imprinted with a massive interconnected grid that extends throughout the body's tissues into the environment. The body's energetic grid is responsible for transforming energy frequencies from cell to cell, tissue to tissue, and from the body's internal energetic field to its external energetic field. These are known in Traditional Chinese Medicine as the 'Jing Luo' channels and collaterals (or the meridian system). The body's energetic grids are also responsible for maintaining the production, growth, and development of energy and tissue formation, and are influenced through intention, thought, and emotion.

CHAPTER 11
THE THREE TREASURES OF HEAVEN: SUN, MOON, AND STARS

DEFINING HEAVEN QI

The Outer Force (Power) of Heaven's Three Treasures (the Sun, Moon, and Stars) manifests as electromagnetic radiation from the sun, reflected light and energy from the moon, starlight energy, and the gravitational forces and interactions of the above mentioned heavenly bodies. The Outer Force of Heaven's Three Treasures also include the twenty-eight constellations, five major planets, and their energetic and gravitational forces.

Heaven Qi is the energy emitted from the universe outside of the realms of Earth and man. The sun and moon, first five planets (Jupiter, Venus, Saturn, Mars, and Mercury), North Star, Big Dipper, and the twenty-eight constellations are the most easily observed natural Heavenly energies, which have a direct connection to life on Earth. The diagram below (Figure 11.1) shows the Five Elements relationship between the universal treasures of Heaven, the environment of Earth and Man's internal organs.

The sun and moon are the primary Heavenly manifestations of Yin and Yang energy. The sun is Yang and is considered the Spirit Soul (Hun) of the sky. The moon is Yin and considered the Corporeal Soul (Po) of the Earth. This interaction of Heavenly Yin and Yang energy affects and governs the Earthly Yin and Yang energy, as well as the Qi within the human body. The sun and moon each have their own cyclic rhythms and energies, changing their relative degrees of Yin to Yang at different times of the day, month, and year.

To cleanse, purify, and strengthen the body, Qigong doctors absorb the essence of the Heavenly Qi by guiding the star's energy into certain areas of the body. The energy of the stars may also be used to reinforce the circulation of Wei Qi for

Organ	Element	Time of Day	Direction	Planet	Associated Animal
Liver	Wood	Early Dawn	East	Jupiter	Green Dragon
Heart	Fire	Midday	South	Mars	Red Phoenix
Spleen	Earth	Midafternoon	Center	Saturn	Yellow Phoenix
Lungs	Metal	Late Dusk	West	Venus	White Tiger
Kidneys	Water	Night	North	Mercury	Indigo Tortoise

Figure 11.1. Natural Heavenly Transformations

added protection against external pathogenic invasion.

INFLUENCES OF HEAVENLY QI ON THE HUMAN BODY

The body's physical fluctuations work in harmony with the cycles of the sun, moon, and nature. The science that deals with the study of these biological clocks is known as chronobiology. The levels of corticosterone and plasma adrenocorticotropic hormone (ACTH), for example, follow a cyclical pattern during the course of a day. Generally, the body's emotional and menstruation cycle in women follow the changing patterns of the moon (i.e., approximately every 28 days). Additionally, approximately every 23 days, the male body releases stored toxins, changing the smell of the sweat in accordance with the body's physical biological cycle. The smooth functioning of natural biological rhythms can at times be disrupted. The "jet lag" phenomenon, for example, is due to the interruption of circadian rhythms in the body.

There are daily, weekly, monthly, and annual solar and lunar cycles to which the human body responds. Other human physical, emotional, and mental cycles are strongly influenced by the types of life-style chosen, and other environmental factors involved. The body's circadian rhythms influence not only the immune system, but also the Yin and Yang energies of the internal organs. The activities of the cells, glands, Kidneys, Liver, and nervous system are coordinated with one another and with the day-night rhythm of the environment. Hunger, excretion, and body temperature are influenced by the body's ability to respond to the micropulsations of the subtle energy fields within the internal organs and tissues, as well as the body's biological clocks.

In China, clinical scientist Liu Bing, from Beijing Medical University, notes in his research that the human body undergoes rhythmic variations within a 24-hour time period. These physical changes include temperature, oxygen consumption, blood pressure, pulse rate, content of hemoglobin, blood sugar, blood amino acids, blood adrenocortical hormone, hepatic glycogen, metabolic rate of fat absorption, and pace of cell metabolism. The natural clockwork of the body can also be altered by food, drink, drugs, and abnormal sleeping patterns.

BODY RHYTHMS AND ENERGETIC PATTERNS

The prenatal and postnatal energetic patterns of the body are also determined by the time and place of conception. The time and place of conception establishes the patient's spiritual energy and ancestral traits (food preferences, manner of dress, preferences of art, spiritual beliefs, and so on). The time and place of birth also determine the patient's energetic biorhythms (physical, emotional, and intellectual cycles).

PRENATAL ANCESTRAL TRAITS

The time and location of conception determine the nature of the ancestral spiritual influence on the patient. As the divine infuses the fetus's soul, the energy of the Eternal Soul combines with the environmental spiritual influences of the geographic location (e.g., the Orient, Europe, North America, etc.). This infusion of geographic spiritual energy creates within the patient a predisposition towards specific ancestral traits and cultural attractions.

At conception and throughout pregnancy, the mother absorbs the natural environmental energy through respiration (breathing through the mouth, nose, and pores), ingesting food (grown in the soil), and visual/auditory ingestion (observing and experiencing the cultural environment). The energetic history of each cultural environment exists within the memories stored in the natural energetic fields contained within that environment. Therefore, someone conceived within a particular geographic location in the Orient may find him or herself, unconsciously drawn to the social and cultural influences of that particular Asian population. This subconscious attraction is considered a natural phenomenon due to the geographic influences of the country's spiritual/ancestral power, causing an effect, indirectly, on the individual.



The Physical Cycle is 23 days long. The first 11 1/2 days are the positive side of the cycle. One experiences a feeling of good physical strength and endurance. The second 11 1/2 days are the negative side of the cycle, marked by having less endurance and a tendency towards fatigue.



The Emotional Cycle is 28 days long. The first 14 days are the positive side of the cycle. One feels optimistic, cheerful, and cooperative. For the second 14 days, a negative stage of the cycle results in tendencies to be moody, irritable, and pessimistic.



The Intellectual Cycle is 33 days long. The first 16 1/2 days are the positive side of the cycle. One has greater success in learning new material and pursuing creative, intellectual activities. The next 16 1/2 days are the negative side of the cycle; one is encouraged to review old material rather than attempting to learn new concepts.

Figure 11.2. The physical, emotional, and intellectual cycles begin on the day of birth.

1. The natural environment of the location at conception exerts a strong influence, such as a preference, or attraction to similar geological formations throughout the individual's life. People conceived by the ocean, for example, may find within themselves an unconscious need to live by the ocean. Likewise, people conceived in the mountains, valleys, tropics, deserts, etc. may find an energetically calm feeling of peace envelop them when visiting such places.
2. The time of conception also exerts a strong influence. The energetic formation, as well as strength or weakness, of the fetus's internal organs is also determined by the positions of the sun, moon, and stars. These Heavenly energies begin their effect on the fetus at the time of conception and continue influencing the fetus's formation throughout the entire pregnancy.

BIRTH-POSTNATAL ENERGETIC PATTERNS

The time and location of birth determines the biorhythmic patterns of each individual. These biorhythms are developed according to the influence of the Heavenly energy (position of the sun, moon, and stars), as well as the Earthly energy (i.e., geographic location, e.g., mountains, valleys, by the ocean, etc.). This infusion of the Earth's geographic energy and Heaven's constellation energy creates within the individual a predisposition towards specific psychological traits.

1. The location of birth strongly influences the individual's desire to seek out and/or surround him or herself with the familiar environment.
2. The Time of Birth may also have an unconscious influence on his or her living patterns, as certain individuals born at night naturally become "night people," while others born in the morning function better during the morning hours.

The body's biorhythms, which react to universal and environmental energetic vibrations, are divided into three distinct cycles and energy flows (Figure 11.2). Each rhythm is cyclical, waxing and waning, creating and contributing to times of physical, emotional, and intellectual triumph, as well as times of reflection and withdrawn behavior. These three cycles begin at the moment of birth and continue with absolute regularity until death. The conditions of the cycle are divided into positive (the first half) and negative (the second half) attributes.

The body's biorhythms are but one example of the effects that Heavenly energy has on the physical, emotional, and intellectual cycles of mankind. By understanding the cycles of the sun, moon, and stars and their energetic potential, the Qigong doctor can utilize the universal energy of Heaven to regulate and balance the patient's Qi. The biological rhythms influence the time at which many illnesses occur or worsen, as well as how fast a medication takes effect and how long the effect lasts. Therefore, Medical Qigong therapy, as well as herbal therapy are prescribed at specific times to enhance their effect on the patient's body.

CYCLES OF THE SUN

The Earth's rotation around the sun causes seasonal changes and instigates cyclic metabolic patterns in the human body. The body's entire metabolic function is influenced by its ability to respond to the seasonal micropulsations of these subtle energetic fields.

The Chinese use both a solar and a lunar calendar. The Heavenly cycle of the moon has 12 lunar month divisions, which correspond to man's 12 internal organs and channels: Lungs, Large Intestine, Stomach, Spleen, Heart, Small Intestine, Bladder, Kidneys, Pericardium, Triple Burners, Gall Bladder and Liver. The Heavenly cycle of the sun has 12 periods of the day, which correspond to man's 12 sections of the body. These 12 internal cycles are sometimes called the 12 Blood / Heat Cycles because they affect the Qi, Blood and temperature within the Twelve Skin Zones (see Chapter 7).

The Earth's rotation and the rhythm of the five seasons (the usual four plus late summer) influence the body's internal organs and channels, affecting their energetic activity. In each of the five seasons, a specific pair of internal organs reaches an energetic peak.

1. In the summer, the Heart and Small Intestine are at their energetic peak.
2. In the late summer, the Spleen and Stomach reach their energetic peak.
3. In the autumn, the Lungs and Large Intestines reach their energetic peak.
4. In the winter, the Kidneys and Bladder reach their energetic peak.
5. In the spring, the Liver and Gall Bladder reach their energetic peak.

THE TWELVE PI HEXAGRAMS

The Twelve Pi Hexagrams symbolize the seasonal changes, which cause the waxing and waning of Yin and Yang energy. The trigrams and hexagrams are used to illustrate the movement of energy in Man (see Chapter 5) as well as Heaven. The Twelve Pi Hexagrams were also used to study and comprehend the interactive energetic fields of man and nature that govern growth and development. The interactive energetic fields engender the creation of energy channels and influence the circulation and transformations of Qi, which in turn, create and maintain the body's internal organs. The ancients believed that the human physique reflects the structure of the universe, and that prenatal Heaven and Earth energy fuse with postnatal Heaven and Earth energy at birth (see Chapter 2). The trigrams reflect the twelve hours of the day, the daily fluctuations of Yin and Yang energy, and the Qi of the Five Elements (Figure 11.3).

The Twelve Pi Hexagrams represent "the laws of hardness and softness," domination and yielding of Yin and Yang, the relationship between the seasons, time of day, major organs, channels, and the transformation and circulation of Qi.

THE YANG YAO CYCLES

When studying the Twelve Pi Hexagrams, it is important to examine the first six (from Fu — 11 p.m. to Qian — 11 a.m.), that represent the gradual increasing of the energetic potential of the Yang Yao (see Chapter 5) and the gradual decreasing of the Yin Qi. The Yang Qi rises and expands during this time period; it is the best time for training techniques that emit external Qi and for treat-


Yin Waxing & Yang Waning
9am–11am
Qian
Spleen
7am–9am
Guai
Stomach
11am–1pm
Gou
Heart
Si
Dazhuang
5am–7am
Chen
May
Wu
Dun
1pm–3pm
L.Intestine
Apr.
⑤
⑥
⑦
June
S.Intestine
Mao
Mar.
④
⑧
July
Wei
3am–5am
Lungs
Yin
Feb.
③
⑨
Aug.
Shen
Bladder
3pm–5pm
Tai
Pi
Jan.
②
⑩
Sept.
Chou
You
①
⑫
⑪
Liver
Dec.
Nov.
Oct.
Kidneys
1am–3am
Zi
Xu
5pm–7pm
Hai
Lin
Guan
G.Bladder
Pericardium
Triple Burners
Fu
Bo
11pm–1am
Kun
7pm–9pm
9pm–11pm
Yang Waxing & Yin Waning
Yang Line
Yin Line
6
Yang
Periods
Fu ①
Lin ②
Tai ③
Dazhuang ④
Guai ⑤
Qian ⑥ Full Yang
6
Yin
Periods
Gou ⑦
Dun ⑧
Pi ⑨
Guan ⑩
Bo ⑪
Kun ⑫ Whole Yin

Figure 11.3. The circular figure depicts the Heavenly cycle of the sun and the Twelve Pi Hexagrams. Solid lines in the trigrams and hexagrams represent Yang, and broken lines represent Yin. The hexagrams on the left depict the Yang Yao Cycle (from Fu to Qian), with the gradual increase in Yang and decrease in Yin, so that the last hexagram, Qian, is full Yang. The hexagrams on the right depict the Yin Yao Cycle (from Guo to Kun), with the gradual increase in Yin and decrease of Yang, so that the last hexagram, Kun, is full Yin.

C. Spiral, blend and transform the energy of the heart and the kidneys at the front pakua.

Spiral and breathe the energies out of the kidney and heart collection points to the front pakua. Blend and spiral them together in the front pakua. (The pure energy trapped in these negative feelings will be freed and released to the center of the pakua). Chant Tai Chi, Tai Chi, Tai Chi. Yin-Yang, Yin-Yang, Yin-Yang. Spiral these energies until they become a bright, golden energy. This energy radiates love and gentleness from the center of the pakua and your being.



Fig. 5.76 *Spiral, blend and transform the energy of the heart and the kidneys.*

ing patients who suffer from insufficiency of Yang Qi. This time period is called the "time of the living breath," and represents the beginning of energetic harvesting. When training in the morning time, the practitioner should progress from still, relaxed, quiescent Qigong meditations to active forms of dynamic Qigong movement.

THE YIN YAO CYCLES

The last six hexagrams (from Gou — 11 a.m. to Kun — 11 p.m.) indicate a gradual increasing of the energetic potential of the Yin Yao and the gradual decreasing of the Yang Qi. This time period is called the "time of the dead breath," and represents the beginning of energetic planting. The Yin Qi increases and expands in this time period; it is the best time for patients suffering from an insufficiency of Yin Qi to train, nurture, and restore the Kidneys' Yin Essence, which in turn will facilitate the preservation of Yang Qi. When training in the afternoon, the practitioner should progress from active forms of dynamic Qigong movement to gradually slower, relaxed, quiescent Qigong meditations.

When prescribing Medical Qigong for patients, the time for practice should be selected in accordance with the philosophy of Yin and Yang theory, the Five Elemental theory, the circadian rhythms of Qi and Blood circulation, as well as the severity of the illness.

USING THE YANG AND YIN YAO CYCLES

Each of the broken lines represents a Yin Yao and can be used to symbolize an inhalation, while a straight line represents a Yang Yao and symbolizes an exhalation. A hexagram consisting of three bottom Yang Yaos and three top Yin Yaos, for example, represents a balanced respirational pattern. When the Qigong doctor writes out a prescription for the patient, the doctor can adjust the patient's respiration in accordance with the Yao hexagrams, taking into consideration each Yao line as representing an inhalation or exhalation. The basic theory of Yin and Yang Yao cycles is also used to determine the time and direction for Qigong practice, as well as the methods of respiration and mind concentration required to establish proper Yin and Yang balance.



Figure 11.4. The Four Principle Time Periods

When practicing Medical Qigong at the hour of the Fu Hexagram, for example, the Yao indicates there is more Yin than Yang, so the practitioner should regulate his or her body with the intent to nourish the Yang through longer inhalation (Yin) and shorter exhalation (Yang).

At the stage of the Gou Hexagram, the Yao indicates there is more Yang and less Yin so the Qigong practitioner should perform regulation through shorter inhalations (Yin) and longer exhalations (Yang).

THE FOUR PRINCIPAL TIME PERIODS OF QIGONG PRACTICE

Practicing Medical Qigong during the "four principal time periods" (Zi, Mao, Wu, and You) facilitates the vigorous growth of internal energy in harmony with the changes of energy in nature (see Figure 11.4). To nourish energy, practice during the sunrise and / or sunset (Mao and You) periods. To stabilize energy, practice during the periods of midnight and / or high noon (Zi and Wu).

Due to the differences between individual constitutions (Excess or Deficient Yang or Yin), the selection of the proper time for practice and the number of Yin or Yang respirations varies between patients. The following is a brief discussion and explanation of the four principal time periods.

1. Zi Time Period corresponds to the Fu Hexagram, and has one Yang and five Yin lines or Yaos. The Zi time period is at midnight (11 p.m. – 1 a.m.). It is related to the beginning of the Yang cycle and is perfect for gathering energy to store the Yuan Qi (Prenatal Qi). The Yuan Qi is the root of life, formed through the divine combination of the primordial Yin and Yang; it is stored primarily in the Kidneys' Water energy. The Zi period of time corresponds to the Fu Hexagram. During this time the Earth energy and the Kidney's Yang Qi are in full harmony, continuously combining and accumulating energy. Practice during this period of time results in twice the effect with half the effort.
2. Mao Time Period corresponds to the Dazhuang Hexagram, and has four Yang and two Yin lines or Yaos. The Mao time period is at sunrise (5 a.m. – 7 a.m.). As the sun rises, warming the air, and natural Yang progresses. At this time of the day, the Yang Qi of the body is in full bloom. Practice during this period of time aids the vigorous growth of Yang.
3. Wu Time Period corresponds to the Gou Hexagram, and has one Yin and five Yang lines or Yaos. The Wu time period is at high noon (11 a.m. – 1 p.m.), and is regarded as the Heart's Fire. At high noon, the Heart Channel (considered the Supreme Yang) will naturally manifest the energetic peak of Yang energy. Because the first line is a Yin Yao, however, the Yang energy Yaos tend to wane rather than grow. Therefore, practicing during this period helps the growth of Yin energy and suppresses the hyperactivity of Yang energy.
4. You Time Period corresponds to the Guan Hexagram, and has four Yin and two Yang lines or Yaos. The You time period is at sunset (5 p.m. – 7 p.m.). At this time, the energy of the environment turns from clear and radiant to dark. Qigong practice at this time nurtures the increase of the primordial Yin energy and the conservation and nourishment of Yang energy.

THE FOUR SEASONAL PEAK TRANSITIONS

Another theory maintained by Qigong doctors is that the sun's light during the day represents Yang, and the energy from the moon's light at night represents Yin. The observation that light coincides with heat and that darkness coincides with cool, led to the division of the year into four seasonal peak transitions (which also correspond to the four principal time periods of the day) (see Figure 11.5).

At the time of the equinoxes and solstices, the sun passes through transitional regions: The Palace of Eternal Frost in the North is entered in the winter; The Golden Gate in the East is entered in the spring; The Palace of Universal Yang in the South is entered in the summer; and The Gate of the Moon in the West is entered in the autumn. The four seasonal peak transitions in the northern hemisphere are described as follows.

1. The Palace of Eternal Frost at the Winter Solstice (December 22–25) indicates the time period when the sun is furthest south from the equator. This is a time of maximum Yin or darkness in the northern hemisphere, with the shortest days and longest time of cold and darkness. This energetic transition corresponds to "midnight" within the four principal time periods.
2. The Golden Gate at the Spring Equinox (March 21) indicates the time period when the sun's center crosses the Heavenly equator, creating an energetic balance between the days and nights. Although light and darkness and Yin and Yang energies are in balance, this seasonal time period is a transitional harmony, as Yang energy is growing. The weather is also moderate. This energetic transition corresponds to the "sunrise" within the four principal time periods.
3. The Palace of Universal Yang at the Summer Solstice (June 21–23) indicates the time period when the sun is furthest north from the equator, a time of maximum Yang or brightness, with the longest days and times of light and warmth. This energetic transition corresponds to "noon" within the four principal time periods.


5th Moon
4th Moon
6th Moon
3rd Moon
7th Moon
Summer Solstice
2nd Moon
Spring Equinox
③
②
④
①
Autumn Equinox
8th Moon
1st Moon
Winter Solstice
9th Moon
12th Moon
10th Moon
11th Moon

Figure 11.5. Four Season Peak Transitions

4. The Gate of the Moon at the Autumn Equinox (September 22) indicates the time period when the sun's center crosses the Heavenly equator, creating an energetic balance between the days and nights. Although light and darkness and Yin and Yang energies are in balance, this seasonal time period is in transitional harmony, as Yin energy is growing. The weather is also moderate. This energetic transition corresponds to the "sunset" within the four principal time periods.

The energy of these four principal time periods enters the practitioner's Taiji Pole during meditation and regulates the "auspicious powers" located within the five regions of space inside and outside of the doctor's body:

- Front—energy of the Heart
- Back—energy of the Kidneys
- Right—energy of the Lungs
- Left—energy of the Liver
- Center—energy of the Spleen

THE SIX PRINCIPAL SEASONS OF TRANSITION

In Traditional Chinese Medicine, the year is divided into six primary periods of seasonal transitions (wind, heat, damp, fire, dry, and cold). Each season represents the ruling Qi, or expected weather, dominant in that particular season (Figure 11.6).

These six periods delineate the differences between and transitional transformations of Heaven energies (through the Ten Heavenly Stems) and Earthly energies (through the Twelve Earthly Branches). In terms of weather, the first half of the year is governed by the Qi of Heaven, while the second half of the year is administered by the Qi of Earth. The Ten Heavenly Stems are the ten energies of Heaven that rule the changes of the Five Elemental Seasonal Transitions, and are represented in the human body as the Yin and Yang aspect of the Five Elements (represented as the ten major internal organs). The Twelve Earthly Branches are the twelve energies of the Earth that determine the six Qi factors of the seasonal transitions (represented in the body as the Twelve Primary Channels). In accordance with the Creative Cycle of the Five Elemental Seasonal Transitions: summer creates late summer, late summer engenders autumn, autumn gives rise to winter, and winter gives birth to spring.

THE DAILY QI, BLOOD, AND HEAT CYCLE

These four principal time periods and seasonal peak transitions affect the body's Blood, Heat, and Qi Cycles. The daily cycle of Heat, Blood, and Qi flow along the body's Twelve Primary Channels, organs, and tissues, according to the two hour Yin and Yang time table are:

- Gall Bladder (GB) - 11 p.m. to 1 a.m. - (Yang)
- Liver (Lv) - 1 a.m. to 3 a.m. - (Yin)
- Lungs (Lu) - 3 a.m. to 5 a.m. - (Yin)
- Large Intestine (LI) - 5 a.m. to 7 a.m. - (Yang)
- Stomach (St)- 7 a.m. to 9 a.m. - (Yang)
- Spleen (Sp) - 9 a.m. to 11 a.m. - (Yin)
- Heart (Ht) - 11 a.m. to 1 p.m. - (Yin)
- Small Intestine (SI) - 1 p.m. to 3 p.m. - (Yang)

Season	Date
1. Spring Begins	Feb. 5
Rainwater	Feb. 20
Insects	March 7
Spring Equinox	March 22
2. Clear and Bright	April 6
Grain Rains	April 21
Summer Begins	May 6
Grain Filling	June 7
3. Grain Full	June 22
Summer Solstice	June 22
Slight Heat	July 8
Great Heat	July 24
4. Autumn Begins	Aug. 8
Limit of heat	Aug. 24
White Dew	Sept. 8
Autumn Equinox	Sept. 24
5. Cold Dew	Oct. 9
Frost Descent	Oct. 24
Winter Begins	Nov. 8
Slight Snow	Nov. 23
6. Great Snow	Dec. 7
Winter Solstice	Dec. 22
Slight Cold	Jan. 6
Great Cold	Jan. 21

Figure 11.6. Six Principal Seasons of Heaven and Earth Energy Transition (1-6), and the Twenty Four Diagram Chart

- Bladder (Bl) - 3 p.m. to 5 p.m. - (Yang)
- Kidneys (Kd)- 5 p.m. to 7 p.m. - (Yin)
- Triple Burners (TB) - 7 p.m. to 9 p.m. - (Yin)
- Pericardium (Pc) 9 p.m. to 11 p.m. - (Yang)

The body's active high and low heat, Blood, and Qi time periods, reflect its relationship with the Twelve Primary Channels. For instance, every morning during the time period of 3–5 a.m., the strongest energy streams down along the Lung Channels, making the Lungs quickly responsive to treatment.



Figure 11.7. Gathering the Sun's Essence Meditation. Step one, stand and face the sun.

GATHERING THE SUN'S ESSENCE MEDITATION

The ancient Qigong masters used this meditation to absorb the essence of the sun. By gathering pure Yang energy to tonify the body's Deficiencies, as well as to consolidate the Zheng Qi (Gathering energy), they were able to eliminate pathogenic factors and prevent premature aging. This particular exercise is considered part of the foundational base from which the ancient Qigong doctors replenished any depleted life-force energy.

The gathering the Sun's Essence Meditation must only be practised on a clear day, when the sun is not obstructed. Avoid practising this meditation in times of fog, smog, thick clouds, and solar eclipses, as cultivation during these times will cause the unnatural cultivation of Turbid Qi.



Figure 11.8. Step two, imagine embracing the sun.

1. While outside on a bright sunny day, face the sun, and assume a Wuji standing posture, hands by your sides, with the feet slightly wider then shoulder-width apart; stand in a relaxed and tranquil state, breath evenly and naturally, and rid your mind of any stray thoughts (Figure 11.7).
2. If the sun is rising above the horizon, slightly close your eyes; you should still be able to see soft, gentle, reddish sunlight. If the sun has already risen, close your eyes and use your inner vision to visualize the sun.
3. Inhale through the nose and imagine filling your mouth with energy from the sunlight's essence. Still facing the sun, with your eyes half open, "infuse," or absorb into the eyes, the energy from the horizon. Blend the energy



Figure 11.9. Step three, imagine embracing the sun and gently placing it in front of your Lower Dantian.

absorbed from your eyes into your Upper Dantian. Close your eyes and imagine blending the sun's golden light energy with the Qi you inhaled through your nose. Hold your breath and focus the mind, mixing both energies; swallow the energies slowly while exhaling, and send the energy down to the Lower Dantian. Repeat this process for several minutes.

4. Stretch your hands towards the sun and imagine embracing it (Figure 11.8). Point your index fingers toward the center of the sun, and imagine pulling the sun down in front of your Lower Dantian. Keep it positioned there for several minutes (Figure 11.9).
5. Imagine the sun gently rolling and turning itself in front of your lower abdomen (Figure 11.10–11). Keep your elbows at your sides and gently shift, or sway from side to side, imagine that it is the sun's movement that causes both your arms and body to move. Using this image keeps the sun in an energetic power position.
6. Place both hands around the sun as if embracing it (Figure 11.12). Next, imagine the sun slowly moving into your navel. Allow both hands to follow the sun into the navel, ending with your left palm on top of your right palm (opposite for women) (Figure 11.13). With one deep breath inhale and absorb the sun's energy into the Lower Dantian while imagining the sun (beneath the navel) transforming into a luminous ball of golden energy. With each inhalation, this golden ball shines brightly; with each exhalation, the sun's rays extend, spreading throughout the entire body.
7. To end, relax the mind and imagine Heavenly Qi melting down the body, pouring through the front, back and center of the body like warm oil, into the Earth. This ending exercise (sometimes called Pulling Down The Heavens), allows the Qi to sink into the Lower Dantian, and the body, mind, and spirit to come into a state of peaceful rest and tranquillity.


Figure 11.10. Step four, imagine the sun gently rolling and turning itself in front of the Lower Dantian.


Figure 11.11. The energy of the sun moves the entire body rather than the arms.


Figure 11.12. Step five, embrace the sun and absorb it into the navel and then into the Lower Dantian.


Figure 11.13. Each breath transforms the sun's energy into luminous golden Qi.

CYCLES OF THE MOON

The ancient Qigong masters believed that the sun has a Yang nature, emitting enormous amounts of hot, thermal energy, whereas the moon has a Yin nature and emits a much cooler type of energy, by reflecting the light of the sun. The energy of the moon is used to replenish the body's Yin Qi, and follows a comprehensive cycle every 28 days (Figure 11.14). Following the cycle of the moon, the energy of the body completes a full rotation, flowing along the Governing Vessel to the top of the head, and down the Conception Vessel to the base of the perineum. When the moon is full, the body's Blood and Qi reach a crest, filling the Baihui point on the top of the head. At the new moon, the body's Blood and Qi gather at the Huiyin point, in the perineum.

Since the lunar cycle at its extreme (full moon and new moon) activates the top and bottom points of the Taiji Pole, these are said to be the most productive times to perform Taiji Pole Qi practice.

The appearance of the moon during the first half of the lunar month symbolizes the waxing of Yang and waning of Yin Qi. As Yang grows and Yin declines, regulation of breathing at this period of time should be aimed at absorption of the Moon's Essence. The second half of the lunar month symbolizes the waxing of Yin and waning of Yang Qi. As Yin grows and Yang declines, regulation of breathing at this period of time should be aimed at replenishing Yang to help the Yin nourish the Yin Jing-Essence (Figure 11.15-20).

As the moon increases the amount of light it reflects, the body's Qi and Blood become more nourished; when the moon is full, the Qi and Blood become substantial. As the moon begins to decrease the amount of light it reflects, the muscles start to lose their energetic substance. This decrease in energy causes the body's Eight Extraordinary Vessels and Twelve Primary Channels to empty themselves to support the muscles that are slowly becoming Deficient. Qi and Blood are influenced by the gravitational pull of the sun and moon, just as the tides of the sea are influenced. Therefore the ancient Qigong masters described the energetic tonifying and purging principles of Qigong regulation in these specific terms: when treating a patient, perform no tonifying when the moon is full, or when the Blood and Qi are sufficient. Perform no purging when the moon is dark, or when the Blood and Qi are Deficient. This observation explains the effect of the "full-moon phenomenon" on patients who are hypersensitive to energy and become restless when the moon's Qi is "full Yang in Yin."

The waxing and waning of the sun and moon affect the adjustment time for Medical Qigong practice and the methods of breathing regulation. In order to facilitate the intake of Heavenly Es-



Figure 11.14. The waxing and waning cycles of the moon correspond to the moon's orbit around the Earth.



Figure 11.15. From the 1st to the 5th night of a lunar month, more Yang absorption and Yin nourishment can be obtained by performing breathing regulations while facing the west. The crescent surface of the Moon is reflecting less sunlight.



Figure 11.16. From the 6th to the 10th night of a lunar month, more Yang absorption and Yin nourishment can be obtained by performing breathing regulations while facing the south. The surface of the moon is turning from a crescent to half-full Yang, and its surface is reflecting more sunlight.



Figure 11.17. From the 11th to the 15th night of a lunar month, equal amounts of Yang absorption and Yin nourishment can be obtained by performing breathing regulations while facing the direction of the moon, as both Yang and Yin energies are plentiful at this time. At this point, the moon is full with its surface reflecting the most sunlight (called "Full Yang in Yin").



Figure 11.18. From the 16th to the 20th night of a lunar month, the Yin grows and Yang declines. Regulation of breathing at this period of time should be aimed at replenishing Yang to help the Yin nourish the Yin Essence, while facing the west. At this time, the crescent surface of the moon is reflecting less sunlight. The reflected sunlight on the moon's surface decreases as Yang wanes and Yin waxes.



Figure 11.19. From the 21st to the 25th night of a lunar month, Yin continues to grow and Yang declines. Regulation of breathing at this period of time should be aimed at replenishing Yang to help the Yin nourish the Yin Essence, while facing the south. At this time, the crescent surface of the moon's shape is turning to half-full Yin, and its surface is reflecting less sunlight. The reflected sunlight on the moon's surface continues to decrease as Yang wanes and Yin waxes.



Figure 11.20. From the 26th to the 30th night of a lunar month, no absorption of Yang is possible when the moon appears in the east at nightfall and its surface is dark, leading to the period of "Pure Yin." Breath regulation should be performed facing east.

sence to nourish the body, the ancient Qigong masters used a system wherein each month is divided into 6 separate sections (a total of 5 days was assigned to each section).

PRENATAL EIGHT TRIGRAMS AND THE MOON

The symbols on the Prenatal Eight Trigrams represent the appearance of the moon, while the Ten Heavenly Stems represent the positions of the moon. Each trigram embraces one or two of the Ten Heavenly Stems. The following chart of Prenatal Trigrams, Ten Heavenly Stems, moon and tide regulation, as well as the principles of purgation and tonification of Qi and Blood is a reference for Qigong doctors for clinical treatments (Figure 11.21).

In this chart, the Yang energy of the Earth gradually increases from the 11th to the 15th. Influenced by this action, the spring tide occurs on the 15th when the moon is full, inducing both the Qi and Blood to become extremely active. This is a good time for Qigong patients who suffer from energy Deficiencies to replenish their Qi. However, if the patient's energy is abundant, he or she should not try to replenish at this time, or an Excess condition of Qi will occur.

CHOOSING THE PROPER DIRECTION FOR TRAINING QI

Since ancient times, Qigong doctors have placed great emphasis on facing certain directions when cultivating energy. Observing that energy training and practicing should be adapted to nature, each routine is selected according to the season, month, and time of day, as well as the physical conditions of the practitioner. The four directions, as well as the sun (solar cycle), moon (lunar cycle), and stars (four sets of seven constellations, each one grouped in the N, S, E, or W), have a direct influence on the human body.

One example of directional training is in setting up treatment schedules according to the energy emitted from the Heavens. It is generally advised when conducting energetic regulations that:

- Patients with Yang Deficiencies should face east or south, to develop Yang Qi;
- Patients with Yin Deficiencies should face west or north, to help develop the Yin Qi;
- Patients with a Kidney Deficiency should face the north;
- Patients with a Liver Deficiency should face east;
- Patients with a Heart Deficiency should face south;
- Patients with a Lung Deficiency should face west;
- Patients with a Spleen Deficiency should focus their attention on the center, i.e., the Earth.

Generally, when first beginning Qigong exercises and meditations, practitioners are taught to face the south or southeast. When practicing specific cultivation exercises, however (such as Gathering the Sun's Essence), the practitioners are taught to face the direction of the sun. In the evening time, unless practicing specific cultivation exercises (such as Gathering the Moon's Cream), it is best to have the patient face the corresponding direction for the Deficient organ. These cultivation methods train the Yang energy to fuse with the Zhen Qi (True Qi), as well as with the Heavenly Qi and Environmental Qi. The timing and methods of training are based on the increase and decrease of Yin and Yang energy.

It is important to note that although these training methods are effective, the most experienced Qigong doctors often choose the place and direction according to their own intuition. To select the appropriate direction, the doctors start by facing south (sitting or standing). As they begin to feel the body filling with Qi, they may feel that they are being pulled towards a specific direction, and that they cannot stand or sit comfortably without facing that direction. The doctors feel more rooted and stable by following their intuition. Through understanding the proper directions, concentration, breath regulation, and assuming the appropriate postures, Qigong doctors are able to help regulate and increase their patients' energetic activities, while avoiding many Qi deviations (see Chapter 18).

Heavenly Stems	Date	Appearance of the Moon	Prenatal Trigrams	Position of Moon you face ○	Cause & Reason	Tide	Qi & Blood	Regulation
Geng ䷡	1st	Waxing Crescent	Zhen ☳	West 	Moon between Sun & Earth	Spring Tide Max. Amplitude when Sun/Moon Pull Together	Turning Excessive	No Tonifying
Ding ䷫	8th	First Quarter	Dui ☱	South 	Moon is 90° East of Sun	Neap Tide Min. Amplitude Sun/Moon work against each other	Deficient	No Purging
Jia ䷗	15th	Full	Qian ☰	East 	Moon opposite Sun, Earth in between to East	Spring Tide Max. Amplitude Sun/Moon pull together	Excessive	No Tonifying
Xin ䷊	16th	Last Quarter	Xun ☴	West 	Moon opposite Sun, Earth in between to West	Medium Tide	Turning Deficient	No Purging
Bing ䷁	23rd	Waning Crescent	Gen ☶	South 	Moon is 90° West of Sun	Neap Tide Min. Amplitude Sun/Moon work against each other	Deficient	No Purging
Yi ䷒	30th	New	Kun ☷	East 	Moon between Sun & Earth	Medium Tide	Deficient	No Purging

Figure 11.21. Medical Qigong Doctor's Chart for Clinical Reference

D. Bring your attention to your liver.

Connect the eyes with the liver and observe your liver. Be aware of any anger, frustration, aggressiveness, guilt in the liver. Accept this feeling. Be aware of the Chen. Chant the Chen and connect your liver with the power of the thunder and the wood, a green light. Feel the kindness, the essence of the wood power. Wrap this feeling of kindness around your anger, balancing them together and transforming your anger. Feel that you can forgive. Forgiveness is one of the most important practices of the Taoist system.

Form with your mind a collection on the left side of the pakua, on the nipple line, and spiral all the negative energies that are still in the liver to this collection point. Chant the Chen again, connect with the wood power and balance the emotions in the collection point.



***Fig. 5.77 a.** Anger and Frustration in the Liver*
***b.** Love from heart and gentleness from kidneys help*
tranfrom the anger and frustration into kindness.

GATHERING MOON'S CREAM QIGONG MEDITATION

Qigong doctors use this particular exercise in conjunction with the Gathering the Sun's Essence meditation for replenishing depleted energy. The vital essence of moon is called the Cream or "cool light" and is used to nourish the Kidneys and strengthen the Jing, Marrow, and brain, while contributing to longevity. It is practiced only nine days a month, three days before, during, and after the full moon, which are the brightest nights of the month. It is prohibited during new moon transitions because there is too little vital essence of the moon to gather.

Gathering the Moon Cream meditation must only be practiced on clear nights, when the moon is not obstructed. Avoid practicing this meditation in times of fog, smog, thick clouds, and lunar eclipses, as cultivation during these times will cause the unnatural cultivation of Turbid Qi

1. Stand outside in the fresh air, while facing the moon. Stand in a relaxed and tranquil state, breath evenly, and rid your mind of any stray thoughts (Figure 11.22).
2. Lower your eyelids until you only faintly see the moonlight. Inhale through the nose and imagine softly "sipping" one mouthful of the moon cream. At the same time, with your eyes half open, visualize "inhaling" the energy of the moon cream with your eyes into your Upper Dantian. Close your eyes and imagine mixing the moon cream with the energy you inhaled through your nose. Slightly hold your breath and concentrate on feeling the moon cream's silvery energetic essence. Swallow this essence slowly, sending it down to the Lower Dantian.
3. Stretch your hands towards the moon (Figure 11.23). Imagine embracing the moon and pulling it out of the sky, placing it just above your Upper Dantian, at your Baihui point (on top of your head). Hold this image for several minutes (Figure 11.24).
4. Next, imagine a second moon forming out of the first moon, and bring it downward with both hands until level with, and in front of, the Middle Dantian (Shanzhong CV-17 point) at the center of the chest. Hold this image for several minutes (Figure 11.25).
5. Finally, imagine a third moon forming out of the second moon, and bring it down to the level of the Lower Dantian, suspended in front of the lower abdomen. Hold this image for several minutes (Figure 11.26).
6. Continue to imagine all three moons suspended (two in front, and one above your body) and inhale, raising both of your arms over your head. Imagine pressing the first moon into your head through the Baihui point, filling the Upper Dantian with the moon cream's silvery white light. As both hands press the moon into the head, allow the left hand to remain on top of the right hand (opposite for women). As you exhale, visualize the light of the moon filling the entire cavity of the Upper Dantian (Figure 11.27).
7. Next, bring both hands to the front of your body. Inhale and press the second moon into your chest through the Middle Dantian, imagining the moon cream's silvery white light filling the chest. As you exhale, visualize the light of the moon filling the entire cavity of the Middle Dantian (Figure 11.28).
8. Finally, bring both hands in front of your lower abdomen. Inhale and press the third moon into your Lower Dantian, imagining the moon's silvery white light filling the abdomen. As you exhale, visualize the light of the moon filling the entire cavity of the Lower Dantian (Figure 11.29).
9. Allow both hands to rest by your sides then slowly raise your left hand (opposite for women) and tap the top of your Baihui point softly nine times. As you tap, imagine that all three moons fuse into a brilliant white-light energy throughout your Taiji Pole, connecting all three Dantians together (Figure 11.30).
10. Relax and perform Pulling Down The Heavens, letting your body, mind and spirit sink into tranquility.



Figure 11.22. Stand facing the moon.



Figure 11.23. Stretch your hands to embrace the moon.



Figure 11.24. Suspend the moon above your Upper Dantian.



Figure 11.25. Suspend a second moon in front of your Middle Dantian.



Figure 11.26. Suspend a third moon in front of your Lower Dantian.



Figure 11.27. Absorb the first moon into your Upper Dantian.



Figure 11.28. Absorb the second moon into your Middle Dantian.



Figure 11.29. Absorb the third moon into your Lower Dantian.



Figure 11.30. Tap lightly until all three moons flow into your Taiji Pole.

CYCLES OF THE STARS

The most influential Heavenly Treasures, other than the sun and moon, are the stars composed of the Big Dipper, Polaris, and the five planets, existing within the twenty-eight constellations.

The North Star is believed to be the unchanging area of Heaven, from which the Heavenly order began (often called the Axis of the Vault of Heaven), and so it was named The Divine Center of the Earth and Sun Cycles. It is also believed that from this star the entire universe expands outward. By placing the North Star in the center of a circle of the Heavens, the circle can be divided into four directions, each containing seven constellations that have a different color energy and sound frequency.

In ancient China, the seven constellations were divided into four sections or directions (north, south, east, and west). In the region of the north was believed to exist the energy of the Tortoise-Snake, in the south was the Red Phoenix, in the east was the Green Dragon, and in the west was the White Tiger. Each of these regions was further divided into twenty-eight constellations or posts (xiu).

According to traditional Chinese belief, the moon travels twenty-eight days from west to east, resting at each post as it circles the Earth. In other words, the twenty-eight days are further divided into twenty-eight regions which are courier stations or travelling houses for the moon.

It was further believed that the Pole Star axis stemming from the North Star traveled downward from the center of Heaven, connecting with the Earth's center core (through the north and south poles). The north pole was regarded as the peak (or Baihui) of the Earth, and was believed to be comprised of seven stars (making it a fifth constellation). The energies of each of the four animals and their seven constellations moved around the Earth's central Pole creating the Five Elemental changes in weather (see Chapter 11). If the weather changes progressed in their expected order, they were considered normal; however, if the weather transition occurred either earlier or later than expected, the result was considered an environmental Evil Qi.

Therefore, the ancient Chinese believed that one could predict the changes of weather by studying the interrelationships between the Five Elements and the cycles of the sun, moon, Polaris, the Five Planets, and the twenty-eight constellations.

THE ENERGY OF THE BIG DIPPER

As the Earth orbits the sun, the angle at which the Big Dipper can be viewed changes on a daily, monthly, and yearly basis (Figure 11.31). These changing angles correspond to the different cycles of the moon as they are arranged in the Twelve Earthly Branches and repeat themselves after completing an orbit (360° rotation of twelve moon cycles). These twelve lunar cycles determine the twelve seasonal periods (Figure 11.32). The beginning part of each month marks the beginning of the seasonal periods of the Twelve Earthly Branches and the beginning of the energy cycle of that month. When the Big Dipper points in the direction of the "lunar month," facing the direction of the Big Dipper will invigorate the practitioner's energy. The Big Dipper is related to the energetic transformations of germinating, beginning, and growing.

There are three kinds of practice centered around the Big Dipper:

1. The first consists of invoking its power for protection;
2. The second consists of ascending into it and pacing its rotation;
3. The third involves gathering the star's essence or star cream into the body.

In ancient times, the Big Dipper was considered the bridge between the energies of the sun and the moon, and the source of "10,000 things." The sun and moon are considered a bipolar energy field, whereas the Big Dipper is considered unipolar.

The sun corresponds to the Heart and Fire energy, which is related to the front area of the body. The moon corresponds to the Kidneys and Water energy, which is related to the back area of the body. The Big Dipper corresponds to the Spleen, which is related to the Taiji Pole.


Winter
North
Spring
East
North
Star
Fall
West
Summer
South

Figure 11.31. The handle of the Big Dipper can be used to determine the season: (1) in winter, the handle points to the northern horizon, (2) in spring, the handle points to the eastern horizon, (3) in summer, the handle points to the southern horizon, and (4) in fall, the handle points to the western horizon. The North Star is positioned in the center of the diagram.


5th Lunar Month
June
Wu
South
Heart
4th Lunar Month
May
Si
Spleen
6th Lunar Month
July
Wei
Small
Intestine
3rd Lunar Month
April
Chen
Stomach
7th Lunar Month
August
Shen
Bladder
North
Star
March
Mao
2nd Lunar Month
East
Large
Intestine
West
Kidneys
You
September
8th Lunar Month
Lungs
Vin
February
1st Lunar Month
Chinese New Year
Pericardium
Xu
October
9th Lunar Month
Triple Burners
Liver
Chou
January
12th Lunar Month
Gall Bladder
North
Zi
December
11th Lunar Month
Hai
November
10th Lunar Month

Figure 11.32. The beginning of the seasonal periods of the Twelve Earthly Branches and the twelve moon cycles is determined by the angle of the Big Dipper.



Figure 11.33. The Big Dipper is considered a reservoir of heavenly energy, collecting Qi from all of the other stars and constellations as it moves through the sky.

THE STARS OF THE BIG DIPPER

The Big Dipper represents the foundational base for the Gate of Access in Chinese mysticism, which is considered the spiritual passageway between life and death. Through this gate the individual may obtain knowledge and insight concerning past, present and future events.

The energy from the stars of the Big Dipper is used to balance the body's Five Agents (stored within the body's Five Yin Organs) and can be arranged internally to enhance internal perception of time and space (Figure 11.33).

One example used in ancient China for invoking the powerful protection of the Big Dipper energy is for the Qigong doctor to cover himself - or herself - with the stars of the Big Dipper by visualizing the stars descending and arranging themselves in a specific order around the doctor's body The stars can be arranged in four ways:

- above the doctor's head,
- in front of or behind the doctor's body,
- placed within the doctor's Three Dantians, or
- placed with the bowl of the Dipper in the Lower Dantian and the handle along the spine.

The doctor imagines placing the stars of the Big Dipper into the center of his or her body. The star's energetic function is to govern the front, back, right, and left of the body, thus regulating the doctor's Yin and Yang energy. The star's energetic function can also be used for absorbing energy from the four seasons into the doctor's body.

The stars of the Big Dipper are also considered responsible for opening the Seven Orifices of the embryo's body and for giving the embryo life. These stars also correspond to the Nine Chambers in the Three Dantians. Usually, meditations dealing with gathering energy from the sun and moon are followed by meditations involving the Big Dipper to further stimulate and energize the body's energetic fields.

THE FIRST FIVE PLANETS

The five planets (Saturn, Jupiter, Mars, Venus, and Mercury) are responsible for the internal Yin organ energy formation within the body during fetal development. These planets are the focus of several Qigong meditations because of their connection to color resonations within each internal Yin organ.

1. Of the first five planets in our solar system, Saturn is coupled with Earth and is considered the central force of planetary energy. It takes twenty-eight years for Saturn to make a complete revolution around the sun. Each year, when Saturn enters into another constellation, it is called "Saturn holding authority over that constellation for one year."

   Saturn's position in the sky relates to the Taiji Pole. The planet Saturn represents the Stomach and Spleen (Earth Element) and emits a golden-yellow light energy.
2. Jupiter represents the easterly direction and the Liver (Wood Element), it emits a green light energy; its position relates to the left side of the Taiji Pole.
3. Mars represents the southerly direction and the Heart (Fire Element). It emits a red light energy and relates to the front side of the Taiji Pole.
4. Venus represents the westerly direction and the Lungs (Metal Element). It emits a white light energy and relates to the right side of the Taiji Pole.
5. Mercury represents the northerly direction and the Kidneys (Water Element). It emits a dark blue/indigo light energy and relates to the back side of the Taiji Pole.

GATHERING ENERGY FROM THE FIVE PLANETS

To absorb energy from the five planets, start by quieting your mind while standing in a Wuji posture and facing the direction of the Big Dipper. Visualize yourself absorbing the energetic essence and color of each planet, one by one, into your body, filling each organ's entire Orb (the organs complete system, channels and tissues). Imagine filling the body with each planet's Heavenly energy from the top of your head, through the center Thrusting Channels.

Begin with the energy of Saturn, imagine it flowing into and filling your body through the Taiji Pole. Next, imagine the energy of Mars flowing into your front Center Thrusting Channel. Now imagine the energy of Mercury filling your body through the back Center Thrusting Channel, Venus's energy filling the body by descending into the right Center Thrusting Channel, and Jupiter's energy filling the body by flowing into the left Center Thrusting Channel. Gather the energy from their corresponding Orbs and lead the Qi downward into the Lower Dantian. After collecting and storing the Heavenly Qi, end the meditation with the Fire Cycle of the Microcosmic Orbit meditation.

THE TWENTY-EIGHT CONSTELLATIONS

Since the year 2000 B.C., the ancient Chinese Qigong Masters observed and used the movements and energy of the twenty-eight constellations, the sun and moon, and the first five planets with the Chinese zodiac, to forecast auspicious times for matters of state and war, and to predict weather and natural disasters. Each of these energetic systems has its own cyclic pattern as well as a direct and indirect influence on human life.

The Chinese practised gathering energy from the Heavenly stars, believing that the study of astrology, like alchemy, united the body's inner world with that of the outer. According to ancient divination practices, the celestial bodies exert forces and exhibit personalities that influence people and events on Earth. A person's character and destiny throughout life is based upon the positions of the planets and constellations at the exact time and place of birth. These influences can be determined by mapping the positions of the twenty-eight constellations in the sky at various times.

So important was this belief, that in ancient China, the Emperor was considered the high priest of the Heavens and frequently made sacrifices to the stars to maintain harmony with the universe. The four corners of the Emperor's palace represented the cardinal points in space (the equinoxes and solstices), and he and his family would move from one corner to another as the seasons changed.

GATHERING ENERGY FROM THE CONSTELLATIONS

At night time, when the moon is not suitable for absorbing Qi (new moon), the Qigong doctor can absorb the energy of the twenty-eight constellations into his or her body.

The energy of all five planets and twenty-eight constellations can be drawn into the body's internal organs and tissues through the five energetic Thrusting Channels which envelop and support the body's Taiji Pole. These Channels flow through the center of the doctor's body, connecting the top of the head to the perineum.

Externally, the twenty-eight day constellation cycle can be arranged externally on the body's Governing and Conception Vessels. The "ecliptic" path of the sun follows the Fire Cycle of the Microcosmic Orbit, which correlates to the individual's emotional/mental and physical health.

There are several meditations used in order to absorb the energy of the five planets and twenty-eight constellations into the doctor's body; one of which is known as The Heavenly Five Yin Organ Meditation.

HEAVENLY FIVE YIN ORGAN MEDITATION (TIAN WU ZANG)

This meditation is very popular in China. It focuses on fusing the energy from the five planets and the constellations into the body through the Five Thrusting Channels that surround the core center of the body's Taiji Pole. These Five Thrusting Channels should not to be confused with the TCM perspective of the Five Thrusting Vessels (as seen in Figure 11.34). Each of these Five Thrusting Channels relates to a specific organ energy and element (Figure 11.35).

When practicing this meditation and gathering the energy from the stars, it is important to first absorb the energy into the Five Thrusting Channels, then spiral the energy in a clockwise downward and counterclockwise upward direction through the body's Taiji Pole. This spiralling action allows the energy to balance itself and stabilizes the body's internal organs (Figure 11.36).

In order to perform the Heavenly Five Yin Organ Meditation and gather the Qi of the twenty-eight constellations, assume a Wuji posture, with your arms suspended by your sides. Face the direction of the North Star and Big Dipper (Figure 11.37). This exercise is performed for thirty-six breaths in each direction.



Figure 11.34. The Thrusting Vessels

1. To begin, imagine golden energy pouring out of the Big Dipper and flowing into the center of the Baihui area, at the top of your head. As you inhale, this golden energy fills the center core of your body, and flows into the extremities. As you exhale, this golden energy gathers into your Spleen.
2. Next, imagine drawing in a red energetic mist from the seven constellations in front of your body. This red mist flows into your body from the front side of the Baihui area, filling your entire body as you inhale. As you exhale, the energy coalesces into your Heart.
3. Now focus your attention on the back of your body. Inhale and imagine drawing in the dark blue energy from the seven constellations behind you into the back side of the Baihui area, filling your entire body as you inhale. This energy gathers into and fills the Kidneys as you exhale.
4. Next, focus on the right side of your body and imagine drawing in white energy from the


Spleen
Fire
Wood
Metal
Water
Top of Head
Fire
Spleen
Metal
Wood
Water

Figure 11.35. Each of the Center Thrusting Channels relates to a specific organ energy and element. Each channel has its own entry point that is positioned either on the top of the head, or on the base of the perineum.


Heart
Shen
Front
Liver
Hun
Left
Side
Spleen
Yi
Right
Side
Lungs
Po
Back
Kidneys
Zhi

Figure 11.36. The body's Yuan Spirit is stored within the body's Five Yin Organs. The placement of the Five Energetic Houses is maintained throughout many Medical Qigong meditations and is used to tonify, strengthen, extend, and project the body's Shen.


FIRE
The Southern 7 Constellations
The Red Phoenix — 64 Stars
WOOD
The Eastern 7 Constellations
The Green Dragon — 32 Stars
The North Star
METAL
The Western 7 Constellations
The White Tiger — 51 Stars
WATER
The Northern 7 Constellations
The Black Turtle — 35 Stars

Figure 11.37. The energy of the Twenty-Eight Constellation Stars is absorbed into the body through the same structural pattern as the placement of the Five Energetic Houses of the body's Shen.

seven constellations to your right into the right side of the Baihui area, filling your entire body as you inhale. This energy gathers and fills the Lungs as you exhale.

5. Finally, focus your attention on the left side of your body and imagine drawing in green energy from the seven constellations on your left into the left side of the Baihui area, filling your entire body as you inhale. This energy gathers and fills the Liver as you exhale.

EARTHLY BRANCHES, HEAVENLY STEMS, AND NINE PALACES

There are many relationships between the macrocosm and the microcosm of man, through the Twelve Earthly Branches, the Ten Heavenly Stems, and the Nine Palaces outlined in the Chinese Classics on Internal Medicine. The Twelve Earthly Branches are Earth energies and are represented in Man as the Twelve Primary Channels. The Ten Heavenly Stems relate to the energies of Heaven and are represented in man as the Yin and Yang aspects of the Five Element organs of Wood, Fire, Earth, Metal, and Water (as seen in Figure 11.38). The Nine Palaces are related to the Eight Extraordinary Vessels (corresponding with the Eight Postheaven Trigrams) in addition to the body's energetic Taiji Pole.

The Twelve Earthly Branches, Ten Heavenly Stems, and the Nine Palaces are interwoven into almost all aspects of Chinese culture, arts and medicine. In Chinese divination, as well as Chinese medicine, the temporal cycles of the Earthly Branches and Heavenly Stems form the foundation for these practices. They can be used to explain the physiology, pathology, diagnosis, and treatment of each clinical case. For each year, month, day, and hour there is a Stem and Branch association. By studying the Stem and Branch association, the Qigong doctor can identify patterns (i.e., determine the cycles and diagnose the patterns of the patient's disharmony) and design treatment protocols, depending on the time of year and the time of day.

The yearly cycles of the Stems and Branches are based on a sixty-year cycle, when the sun, moon, Earth, and North Star are aligned (Figure 11.39). The last sixty-year cycle began in 1984. The exact origin of the Ten Heavenly Stems and Twelve Earthly Branches is not known. They were used, however, to mark the hours, days, years, and planetary cycles as early as 1500 to 2000 B.C. Some historians attribute their origin to the legendary emperor Huang-Di (as early as 2600 B.C.). Each cycle was regarded by the Chinese as being a "century" in the life span of the average man. Those who lived past the age of sixty were regarded as living a "second life." During this second life, the person would experience similar occurrences as in the "first life," but would be able to apply the wisdom and maturity gained from his or her first life. The individual can then further his or her spiritual growth and use the knowledge to benefit society as a whole.



Figure 11.38. The Five Element Chart and Its Relationship to the Ten Celestial Stems

The twelve animals of the Chinese zodiac correlate with the Twelve Earthly Branches and are arranged as follows.

- Zi branch corresponds to the Rat
- Chou to the Ox
- Yin to the Tiger
- Mao to the Rabbit



Figure 11.39. The beginning of the sixty-year cycle is based on the alignment of the sun, moon, earth, and North Star.

- Chen to the Dragon
- Si to the Snake
- Wu to the Horse
- Wei to the Sheep
- Shen to the Monkey
- You to the Rooster
- Xu to the Dog
- Hai to the Boar

The first year of the sixty-year cycle is associated with the first Branch and the first Stem. The first Branch, "Zi," corresponds with the Rat; the first Stem, Chia, corresponds with the element Wood. Thus, the first year of the sixty-year cycle is the year of the Wood Rat in Chinese astrology.

The second year of the cycle represents the second Branch and second Stem, and so on. When you reach the 11th Branch, there are no more Stems and, thus, the 11th year of the cycle represents the eleventh Branch and the first Stem. The cycle continues in this manner until it has transitioned through six cycles of Stems and five cycles of Branches and returns to the first Branch and first Stem paired together.

Figure 11.40 shows these yearly cycles; for example, 1997 was the year of the Fire/Ox, so the year 1998 is the year of the Earth/Tiger.

The Ten Heavenly Stems represent Yang, and the higher form of Heaven's vitality (Figure 11.41). The Twelve Earthly Branches represent Yin and the lower form of Earth's vitality (Figure 11.42). Together they manifest the transformation of all natural events expressed through the growing, thriving, declining, and dying of all living things.

1. Each lunar year the Earthly Branch time divisions are divided into 12 separate month divisions.
2. Each day is divided into 12 two-hour Earthly Branch time divisions during a 24-hour cycle.

SUMMARY

In comprehending the energetic potential of the Three Treasures of Heaven, the Qigong doctor evaluates the patient's condition and treats the disease according to the patient's energetic rhythm and flow, which is blended with the Heavenly and Earthly energies. The treatment also includes prescribing homework (the Medical Qigong prescriptions needed to support and maintain the doctor's treatments).

Although mankind is terrestrial, there can be no separation from the influence of the celestial. For mankind is born on Earth in physical form, created through the integration of both celestial (Heavenly) and terrestrial (Earthly) energies. According to statements recorded in the *Canon of Internal Medicine*, ancient doctors had already rec-

E. Bring your attention to your lungs.

Connect your nose with your lungs and observe your lungs. Be aware of any sadness, depression in the lungs. Accept these feelings. Be aware of the Tui. Chant the Tui and connect your lungs with the power of the rain and the metal power, a white light. Feel the courage and the righteousness, the essence of the metal power. Wrap this courage around your sadness, balancing it with and transforming your sadness.

Form with your mind a collection point on the right side of the pakua on the nipple line and spiral all the negative emotions that are still in the lungs to this collection point. Chant the Tui again, connect with the metal power and balance the sadness with the courage here again.

F. Spiral, blend and transform the energy of the liver and the lungs at the front pakua .

Spiral and breathe the negative emotional energies from the liver and lungs collection points to the front pakua. Spiral and blend them at the front pakua. Chant Tai Chi, Tai Chi, Tai Chi, Yin-Yang, Yin-Yang, Yin-Yang. Use the power of pakua to balance and neutralize the sadness and anger. Feel that the pure energy that is trapped in these negative feelings will be freed and released to the center of the pakua. Continue to spiral the liver's and lungs' energies until they become a bright, golden energy that radiates kindness and courage from the center of the pakua and of your being.



Fig. 5.78 *Spiral, blend and transform the energy of the liver and the lungs.*


Yearly Correspondences of Stems and Branches
Dog
Boar
Rat
Ox
Tiger
Rabbit
Dragon
Snake
Horse
Sheep
Monkey
Rooster
Dog
Boar
Rat
Ox *
Tiger
Rabbit
Dragon
Snake
Horse
Sheep
Monkey
Rooster
Dog
Boar
Rat
Ox
Tiger
Rabbit
Dragon
Snake
Horse
Sheep
Monkey
Rooster
Dog
Boar
Rat
Ox
Tiger
Rabbit
Dragon
Snake
Horse
Sheep
Monkey
Rooster
Dog
Boar
Rat
Ox
Tiger
Rabbit
Dragon
Snake
Horse
Sheep
Monkey
Rooster
Water
Wood
Fire
Earth
Metal
Water
Wood
Fire
Earth
Metal
Water
Wood
Fire
Earth
Metal
Water
Wood
Fire
Earth
Metal
Water
Wood
Fire
Earth
Metal
Water
Wood
Fire
Earth
Metal

Figure 11.40. The asterisk (*) shows the year 1997, which was the year of Fire/Ox. Each year, one of the twelve animals of the Chinese zodiac flourishes and brings its energy into action. Every two years, a new Element (Fire, Wood, Water, Earth, Metal) dominates in the cycle of creation. The chart moves clockwise, so 1998 was the year of Earth/Tiger.

Character	Name	Number	Animal	Month	Time	Branch	Channel	Image	Element
子	Zi	1	Rat	Nov. 22– Dec. 21	11-1 am	**Little Yang**	Gall Bladder	Reproduction of Life	**Water**
丑	Ch'ou	2	Ox	Dec. 22– Jan. 20	1-3 am	**Decreasing Yin**	Liver	Initial Growth	**Earth**
寅	Yin	3	Tiger	Jan. 21– Feb. 19	3-5 am	**Great Yang**	Lungs	Breaking Ground	**Wood**
卯	Mao	4	Rabbit	Feb. 20– Mar. 20	5-7 am	**Bright Yin**	Large Intestine	Thick Vegetation	**Wood**
辰	Ch'en	5	Dragon	Mar. 21– Apr. 19	7-9 am	**Bright Yang**	Stomach	Full Awakening	**Earth**
巳	Si	6	Snake	Apr. 20– May 20	9-11 am	**Great Yin**	Spleen	Preparation for Ripening	**Fire**
午	Wu	7	Horse	May 21– June 21	11-1 pm	**Little Yang**	Heart	Peak of Growth	**Fire**
未	Wei	8	Sheep	June 22– July 21	1-3 pm	**Great Yin**	Small Intestine	Taste of Full Ripeness	**Earth**
申	Shen	9	Monkey	July 22– Aug. 21	3-5 pm	**Great Yang**	Bladder	Time of Harvest	**Metal**
酉	You	10	Rooster	Aug. 22– Sept. 22	5-7 pm	**Little Yin**	Kidneys	Resting after Harvest	**Metal**
戌	Xu	11	Dog	Sept. 23– Oct. 22	7-9 pm	**Decreasing Yang**	Pericardium	Moving Inward	**Earth**
亥	Hai	12	Boar	Oct. 23– Nov. 21	9-11 pm	**Little Yin**	Triple Burners	Seed Awaiting Growth	**Water**

Figure 11.41. Environmental Energetic Interactions of the Twelve Earthly Branches

ognized the close relationship between the body's Qi and Blood and the influences of the natural environment. In ancient China, the Twelve Earthly Branches represented time units, each of them corresponding to a two-hour period. They are primarily used to represent the 12 months in the Lunar Calendar.

The Ten Heavenly Stems are made up of the Five Elements, each of which is divided into pairs of corresponding Yin and Yang, resulting in a ten-step system of numerology. Using the Ten Heavenly Stems allows the Qigong doctor to determine the ebb and flow of the Qi of Heaven and its corresponding relationship to the Qi of Man.

Both the Ten Heavenly Branches and Twelve Earthly Stems represent the characteristics of growing, thriving, declining, and dying of all living things in the universe, as well as the development and transformation of all natural phenomena.

The energy of the Ten Heavenly Stems can be observed within five energetic movements (front, back, right, left, and center), as well as within the elemental energy of the body's major internal organs.

Character	Name	Number	Element	Yin-Yang	Organ	Planet	Image
甲	Jia	1	Wood	Yang	G.B.	Jupiter	Sprouting Growth
乙	Yi	2	Wood	Yin	Liver		Early Growth
丙	Bing	3	Fire	Yang	S.I.	Mars	Expansive Growth
丁	Ding	4	Fire	Yin	Heart		New Life Fully Grown
戊	Wu	5	Earth	Yang	Stomach	Saturn	Prosperous Development
己	Ji	6	Earth	Yin	Spleen		Maturation
庚	Geng	7	Metal	Yang	L.I.	Venus	Retreating Inward
辛	Xin	8	Metal	Yin	Lungs		Hibernation
壬	Ren	9	Water	Yang	Bladder	Mercury	Inward Nourishment
癸	Kui	10	Water	Yin	Kidneys		Gathering New Life Energy

Figure 11.42. The Ten Celestial Stems and their Universal Energetic Interactions

CHAPTER 12

THE THREE TREASURES OF EARTH: EARTH, WATER, AND WIND

INTRODUCTION TO THE THREE TREASURES OF EARTH

The Outer Force (Power) of Earth's Three Treasures consists of the Yin and Yang interaction of energy and light, emitted, absorbed, and reflected back from the land, water, and wind. The Three Earthly Treasures are brought about by the waxing and waning of the five Yin and Yang climatic transformations (the five seasonal growth cycles), which in turn are caused by the sun, moon, and stars. Each seasonal change brings a life transforming gift that affects the mind, body, emotions, and spirit (Figure 12.1). The wind (weather) reflects the various conditions and transformations of energy in the sky, and is viewed as an Earthly manifestation of Heaven's moods.

1. Earth Qi consists of the Yin and Yang interactions of energy and light, manifesting as hot and cold energy originating from the Earth's surface.
2. Water Qi consists of the Yin and Yang interactions of energy and light, manifesting as hot and cold energy originating from the vast oceans, lakes, and rivers of the world.
3. Wind Qi consists of the Yin and Yang interactions of energy and light, manifesting as hot and cold air circulation created from the interaction of the sun's heat on the surface of the planet. This interaction includes all cloud and barometric pressure formations (e.g., tornadoes, hurricanes, lightning storms, etc.).

UNDERSTANDING HEAT AND LIGHT INTERACTIONS

Heat and light are manifested both externally on and from the Earth's surface, and internally within the Earth.

1. Externally, the greater the intensity of the sun's light absorbed into the surface of the Earth, the more heat is manifested from the Earth's surface. Cloudy days diminish the

Natural Earthly Transformations					
Organs	**Element**	**Season**	**Elemental Factor**	**Temperature**	**Transition**
Liver	Wood	Spring	Wind	60– 70° F	Germination
Heart	Fire	Summer	Heat	above 90 F	Growth
Spleen	Earth	Late Summer	Damp	75– 90° F	Transformation
Lungs	Metal	Autumn	Dry	60– 70° F	Gathering
Kidneys	Water	Winter	Cold	below 60° F	Storage

Figure 12.1. The Natural Earthly Transitions

sun's thermal interaction and tend to bring coolness.

2. Internally, heat and light, as well as other natural forces, are contained within the Earth itself. The sun's intense energetic fields draw the heat and light from within Earth, which are then reflected back to the Earth by the atmosphere.

The Earth's air extends only a comparatively short distance out from the Earth's surface, and the effects of the heat rays decrease as you leave the Earth's surface and ascend toward the outer regions of the atmosphere. As the air becomes less dense, there is less reflection. The higher you ascend, the cooler the air becomes. When you have reached the limit of air, you have reached the limit of the Earth's heat.

The heat and light form a protective energetic field around the Earth's surface similar to the body's Wei Qi field. Once you have reached the limit of heat and light, you reach what is called the Great Cold. This cold is considered far more solid than steel, and it presses down upon the Earth's energetic field and atmosphere with an almost irresistible force, holding them together.

UNDERSTANDING THE EARTH'S YIN AND YANG INTERACTIONS

Between Heaven and Earth there is an on-going interaction of Yin and Yang energy exchange. When the Earth Qi is in balance, plants grow and animals thrive. Power, in the form of energetic fields, is created by the integration of Yin and Yang. This power directly and indirectly affects the body's electromagnetic field, as well as the regulation and formation of the body's tissues. Visualize the Earth's energy as Qi resonating and emitting from the Earth itself. This energy includes the electromagnetic fields, subterranean radiations, and thermoluminescence (light and heat emitting from the center of the Earth).

The closer the Qigong doctor bonds physically, mentally, emotionally, and spiritually with the Earth and nature, the easier it is to tap into the Earth's energy and vibration. The development of Earth Qi in the body and the body's connection to the energy of the Earth are mutually supportive. The first step in internal cultivation involves focusing the mind on the Lower Dantian (with the aid of breathing techniques) to enhance the mind-body connection; this interactive connection develops a relationship with the Earth Qi.

GATHERING ENERGY FROM THE EARTH'S ENERGETIC FIELDS

The ability to gather energy from nature and the environment is extremely important to the Qigong doctor. The energy of the Earth stays within the structural components of the planet, flowing like mighty rivers of Qi. It is absorbed into the terrain and vegetation, as well as the water that we drink. Environmental Qi is specific to each geographic area. It is the energy that has been collected from the structural components of the Earth itself (i.e., soil, fields, deserts, plants, trees, forests, mountains, streams, rivers, lakes and oceans, etc.). The energetic potential of the Earth's Qi changes from Yang to Yin energy with the rising and setting of the sun, and therefore directly affects the environmental energy.

Although food and water are excellent sources for gathering energy, the Qigong doctor cannot continually ingest food, or drink herbal teas while treating patients, without overtaxing his or her digestive system. It is, therefore, important for the doctor to find an alternative source of energy, to replenish his or her system once it becomes depleted. By studying the waxing and waning of the Earth's Yin and Yang energies the doctor can optimize the absorption of Yin and Yang energy.

TECHNIQUES FOR CULTIVATING EARTH QI

Generally, several meditations are used to cultivate and absorb energy from the Earth by utilizing the energy of trees, bushes, flowers, lakes, etc. The primary objective of these meditations is to first cleanse the body of pathogenic factors, then cultivate and absorb the environmental Qi to replenish the body's energetic field. Practitioners and patients should visualize themselves immersed in a focused environmental field of energy, filled with its vibration, color, and light. They should allow this energized field to envelop their entire body.

CLEANSING THE BODY

One of the most popular cleansing techniques used in the Xi Yuan Hospital's Qigong Clinics begins from a lying, sitting, or standing posture (usually in a Wuji posture) while in front of a natural object, such as a tree.

To cleanse the body's energy, extend both hands towards the tree, as if to embrace it (it does not matter if the tree is actually being touched). Upon inhalation, begin to guide the energy from the tree into your torso through the Laogong (Pc-8) points at the center of your palms, and the Baihui (GV-20) point at the top of your head. Absorb this energy deep into your body. Once you feel that the body is fully saturated with Qi, exhale through the mouth and guide the Turbid Qi down the legs and out of the body through the Yongquan (Kd-1) points at the bottom of the feet. Continue to guide the Turbid Qi down through the Earth into the root system of the tree. Then inhale through the nose, as you absorb the purified energy from the upper part of the tree leading it down your body through the top of your head. Continue this process until you feel totally cleansed. Remember to synchronize breathing in through your nose as you focus on absorbing the Earth Qi, and to exhale through the mouth, as you focus on dispersing and releasing the Turbid Qi.

For tonification, extend your Qi and intention deep into the root system of the tree and imagine absorbing its natural energy through the Baihui point at the top of your head (Figure 12.2).

GATHERING QI FROM TREES, BUSHES, AND FLOWERS

Earth Qi and environmental energy saturate all types of foliage, allowing the Qigong doctor to select, gather, and absorb Qi from many botanical sources. Throughout history, the Chinese have used trees, bushes, and flowers for healing and medicine. Trees and plants absorb air, light, energy, water, and minerals. When Heavenly Qi is combined together with the environmental energy of the tree or plant, the result is a powerful invigorating energy source.

In China, I noted that every Medical Qigong clinic I visited had its own garden. Each garden was full of healthy trees, bushes, and beautiful flowers from which the patients could draw energy. The patients could choose from different plants and bushes, each type of foliage having its own unique strengths and benefits. Any combination of healthy plant energies can be absorbed by the patients to improve their health.



Figure 12.2. A Qigong doctor can extend Qi and intention deep into the root system of the tree and absorb its natural energy through the Baihui point at the top of the doctor's head.

The best time for absorbing energy from trees, bushes, and flowers is between the hours of sunrise (Mao: 5 - 7 am.) and noon (Wu: 11 a.m. – 1 p.m.).

It is important to note that, within the differing regions of a specific country, each type of tree and plant will have either minor or major variances regarding its energetic potential. This difference in energetic potential is due to the diverse environmental influences affecting each plant. We in the West, for example, have many different varieties of plants and trees similar to those in Asia, however, because of the energetic continental differences, the quality and quantity of Qi in each plant or herb can vary. This energetic difference is brought about by the various Qi fields produced by each region's altitude, the mineral content of the soil and water, and the amount of exposure to the energy of the sun. Even herbs of the same name, but grown in different countries, can have different affects on the body's energetic system, slightly altering their clinical potential (e.g., American Ginseng is sweet, slightly bitter and cold, and enters the body affecting the Heart, Lung and Kidney Channels; Siberian Ginseng is sweet, slightly bitter and slightly warm, and enters the body affecting the Lung and Spleen Channels).

GATHERING ENERGY FROM TREES

Trees are tremendously powerful plants and are commonly used by both doctors and patients to absorb and transform the negative pathogenic Qi into clean, healthy, life-giving energy. Pine trees tend to be one of the most powerful, as they radiate a great deal of Qi. Once an individual has connected with a tree, the primary goal is to:

1. remove stagnation from the channels,
2. tonify the internal organs,
3. stabilize and replenish any depleted energy within the body,
4. nourish the Blood, and
5. strengthen the nervous system.

The following is a brief description of various trees, their Yin or Yang potential, and their energetic affect on the body's internal organ system:

- Apple - slightly Yin - St and Sp
- Bamboo - Yin - Ht, Lu, GB, and St
- Birch - Yin - St
- Cassia (Cinnamon) - Yang - Sp, Kd, and Bl
- Cherry - Yang - Lv, Lu, Kd, and St
- Chestnut - Yang - Sp, St, and Kd
- Cranapple - neutral - Lv, Lu, and Ht
- Elm - neutral - St, SI, and LI
- Fig - neutral - Lu, LI, and Sp
- Ginkgo - neutral - Lu, Kd, and Ht
- Hawthorn - slightly Yang - Sp, St, Lu, and LI
- Magnolia - Yang - Lu, St, GB, LI, and Sp
- Maple - neutral - Sp, Kd, and LI
- Mulberry - Yin - Lu, LI, Sp, and Kd
- Oak - slightly Yang - LI, Sp, Kd, and Ht
- Pine - Yang - Ht, Lu, LI, and Kd
- Willow - Yin - Ht and Sp

GATHERING ENERGY FROM BUSHES

Bushes are an extremely effective source for gathering and ingesting different forms of healing energy. Similarly to trees, each bush has its own energetic properties and causes a specific reaction in the body's energetic field. Bushes, however, are not as powerful an energy source as trees for gathering massive quantities of Qi.

GATHERING ENERGY FROM FLOWERS

Flowers are unique in their effect on stimulating the nervous system. Different colors, shapes, and sizes can affect the emotions, causing the individual's spirit to open. Each color can be absorbed into the body in order to facilitate the stimulation of internal organ energy. The gift of flowers has had a long history in soothing emotional pain and bringing relief to patients.

CULTIVATION AND REGULATION TECHNIQUES

Techniques used in the Qigong clinics for cultivation, absorption and regulation of energy generally begin by having the patient face a tree, bush, flower, etc. Although the hands and body postures are similar to the last meditation, the mind's intention is quite different. In this meditation the patient absorbs Qi from the tree, by inhaling it through his left palm, to draw the energy into his body. The energy is guided down the patient's chest, into his or her Lower Dantian. From there the patient circulates this gathered energy through his or her Microcosmic Orbit. As the patient exhales, the Qi exits the right palm into the tree, and begins the cycle again. This meditation is practiced to replenish the body's energetic field.

Patients should be monitored regularly to prevent Qi deviations, which may occur while absorbing Qi through their pores. For best results, choose a quiet, safe, and healthy environment. Select trees, bushes, and flowers with a stable root, or thick trunks. The color is also very important, as the leaves and flowers should be bright, full, and healthy.

Because the body's internal energy matches that of the external environment, it is important to avoid selecting any area which is unpleasant or unhealthy. Avoid any tree, bush, or flower that is sick, dying, has lost its color, or has just been pruned. Using trees, bushes, or flowers for cleansing the body, as well as to absorb energy, is forbidden at night, because their oxygen production diminishes after the sun has set.

PRECAUTIONS

It is important not to meditate in front of any tree, bush, or flower that has parasites, or has been poisoned or polluted, since such vegetation will induce an impure energetic resonation within the Qigong doctor's body.

GATHERING QI FROM MOUNTAINS, VALLEYS, AND DESERTS

The mountains, valleys, and deserts absorb and release light, energy, and heat from the sun. These energies are absorbed and released from the structures of the land quicker than from the oceans, lakes, and streams. Environmental energy is also gathered and stored by the geological formations and local ecology. The ancient Chinese Qigong masters viewed the Earth as a living entity, with rivers and pockets of energy similar to that of the human body. Certain altitudes, densities of colors, and structural formations can affect the Earth's energetic potential.

GATHERING ENERGY FROM MOUNTAINS

Mountains are extremely powerful conduits of energy. They act as peak areas, or collection points for energy. The higher the mountain, the more the air is charged with electromagnetic potential. In ancient times, for prayer and meditation, Taoist and Buddhist temples, shrines, and caves were constructed on energetic pockets high within the mountains of China. In fact, all high, mountains that are far from human civilization are regarded as superior places for energetic cultivation, due to the clarity of light and extraordinarily potent energies which include a very high negative ion count in the air.

GATHERING ENERGY FROM VALLEYS

The Earth's valleys act as channels for Earth energy, collecting and carrying energy throughout the natural terrain. Systems of valleys extend through the plains, hills, and mountains, and generally flow towards the ocean. By standing at the "floor" of the valley (surrounded by its walls), energy can be easily absorbed into the body for cultivation.

GATHERING ENERGY FROM DESERTS

The deserts are considered seas of dry heat energy. They are excellent environments for meditations when used to gather Qi into the body, especially for combating diseases pertaining to Wind, Cold, and Damp invasion (which give rise to many diseases).

CULTIVATION TECHNIQUES

Generally there are several meditations used to cultivate and absorb energy from mountains, valleys, and deserts. The primary objective of these meditations is either to cleanse the body of pathogenic factors, or to cultivate and absorb Qi. When cultivating energy from mountains, valleys, or deserts, practitioners should visualize themselves immersed in the Earth's field of energy, filled with vibration, color, and light. The practitioners should allow this energized field of Earth Qi to envelop them completely.

For best results, select mountains, valleys, and deserts with a stable foundation. The color is also very important, as the Earth, soil, rocks, and surrounding area should be clean.

Also, there are certain locations on the planet known as "power spots" which can produce remarkably powerful effects in the body's energetic fields.

Patients should be monitored regularly in order to prevent Qi deviations, which may occur while absorbing Qi through their pores.

PRECAUTIONS

Because the body's internal energy matches that of the external environment, it is important not to meditate in front of any mountain, valley, or desert area that has eroded, is dying, has lost its color, or is polluted. Also prohibited are areas where there is ongoing seismic, or volcanic activity, as such areas will induce unstable resonation within the Qigong doctor's body.

GATHERING QI FROM OCEANS, LAKES, AND STREAMS

The oceans, lakes, and streams retain and release the sun's light, energy, and heat slowly and are, therefore, important in energy cultivation. The body instantly absorbs the light, energy, and resonant vibrations stored within water. Energized water (sometimes in the form of herbal teas) is often used by Qigong doctors in clinics throughout China. This energetically transformed water provides the patient's body with the basic components necessary for restoration and regeneration, and is considered the "elixir of life" by many Qigong doctors.

GATHERING ENERGY FROM OCEANS

The energy from the ocean has a strong cleansing and purifying effect on the body's Qi. Meditating by the ocean is used extensively for dispersing negative emotions and regulating the body's internal organs. The active rhythm and sound of the waves allows the patient to harmonize his or her internal energetic rhythms with that of the tide, thus quieting the nervous system.

GATHERING ENERGY FROM LAKES

The energy from a lake has a strong calming affect on the body's energetic field. The quiescent solitude of a lake can be used to sedate active emotions, balance any Excess or Deficiency, and calm the body's Shen.

GATHERING ENERGY FROM STREAMS

The energy of a stream can be used to replenish and restore depleted Qi, sedate active emotions, balance any Excess or Deficiency, and also to calm the body's Shen.

CULTIVATION TECHNIQUES

Generally there are several meditations used to cultivate and absorb energy from oceans, lakes, and streams. The primary objective of these meditations is to either cleanse the body of pathogenic factors, or cultivate and absorb Qi to replenish the body's energetic field. When cultivating energy from oceans, lakes, or rivers, patients should visualize themselves immersed in a pool of water, filled with energy, color, and light. The patient should allow this energized water to absorb, cleanse, and invigorate the entire body.

Patients should be monitored regularly to prevent Qi deviations, which may occur while they are absorbing Qi through their pores. For best results, select oceans, lakes, and streams with a calm, stable current. The color is also very important, it should be clear and clean. The water and the surrounding areas should also be clean.

PRECAUTIONS

Because the body's internal energy matches that of the external environment, it is important to avoid selecting any oceans, lakes, or streams that are turbulent, have become dull in color, polluted, or stagnant.

GATHERING QI FROM THE SIX DIRECTIONS

Absorbing Qi from the six directions (Heaven, Earth, and the Four Winds), focuses on gathering environmental energy into the center core of the body (Taiji Pole) from: Heaven, Earth, and the four directions: South corresponds to the front of the body, North to the back of the body, West to the right of the body, and East to the left of the body. The Taiji Pole is considered the central axis, with two directions, above and below. This is a tonification exercise that is used for gathering and absorbing the Earth's environmental Qi, to energize a weakened or Deficient condition.

CULTIVATION TECHNIQUES

There are several meditations used to cultivate and absorb energy from the four directions of the horizon, with the fifth and sixth directions being at the top and bottom of the Taiji Pole. The primary objective of these meditations is to first cleanse the body of pathogenic factors, then to cultivate and absorb environmental Qi. Each direction of energy (N, S, E, W, Heaven, and Earth) has its own unique field of power and vibration, and is assigned a specific color. Each vibration and color stimulates the energy field of one of the five major Yin organs through the body's Heaven and Earth connection (i.e., the Taiji Pole).

When cultivating energy from the horizon, practitioners should face the direction of the south and visualize themselves surrounded in an energetic mist. This mist contains six different colors and light vibrations. From the four directions (N, S, .E, and W) emanate the corresponding following four colors: ruby red, brilliant white, indigo and emerald green. Each of these colors are associated with a particular Yin organ: ruby red with the Heart, brilliant white with the Lungs, indigo with the Kidneys, and emerald green with the Liver. From the Earth itself arises a golden yellow mist; this color is associated with the Spleen. From Heaven descends a silvery white mist entering the body at the top of the head; this color is associated with the Taiji Pole. These six different colored mists permeate and envelop the body with their healing light vibrations.

To perform this meditation, stand in a Wuji posture as you visualize:

1. A silvery white mist descending from the center of the Heavens to penetrate and envelop your Taiji Pole. This silvery white mist enters your body through the top of the head at the Baihui (GV-20) point, and flows into and fills up the Taiji Pole, saturating and absorbing into your center core.
2. A golden yellow mist, ascending from the center of the Earth, entering the body through the bottom of your feet at Yongquan (Kd-1) points. This golden yellow mist saturates your Spleen as it penetrates and envelops your center core;
3. A ruby red mist, flowing from the horizon in front of you enters your Heart, as it saturates and envelops the front of your body.
4. An indigo or dark blue mist flowing from the horizon behind you enters your Kidneys, as it saturates and envelops your back.
5. A brilliant white mist flowing from the horizon on your right side enters your Lungs, as it saturates and envelops the right side of your body.
6. An emerald green mist flowing from the horizon on your left side enters your Liver, as it saturates and envelops the left side of your body.

Patients should be monitored regularly to prevent Qi deviations which may occur while the patient is absorbing Qi through his or her pores. For best results while absorbing environmental Qi, the color of the energy should be clean, clear and bright.

PRECAUTIONS

Because the body's internal energy matches that of the external environment, it is important to avoid selecting any areas that are windy, turbulent, polluted, or stagnant. Also avoid cultivating energy in storms, during hurricanes, sweltering heat, or blistering cold. Avoid any type of extreme weather condition.

ADDITIONAL TECHNIQUES FOR TRAINING EARTH QI

The following exercises at one time were secretly practiced throughout China, as a means for Medical Qigong doctors and Qigong masters to practice advanced methods of environmental energy manipulation. The purpose of these Qigong exercises is to allow the doctors the chance to practice connecting and infusing their energetic field with the environmental energetic field.

PULLING CLOUDS OUT OF THE SKY

This exercise requires the Qigong doctors to first root and immerse themselves with the vibrational resonance of the Earth (this can be accomplished by practicing the One through Ten Meditation, described in Chapter 26). Next, the doctors extend an energetic line from the Earth into the sky, connecting to and enveloping a specific cloud. Through focused intention, the doctors imagine sucking the cloud out of the sky and down into the Earth, rooting its energetic form into the Earth's energetic field. As the cloud's energy is absorbed into the Earth, it dissolves from the sky.

Once the doctors have rooted the cloud into the Earth's energetic field, they have two choices: either to release the cloud back into the sky by attaching its energetic form onto an already existing cloud, or to allow the cloud to disperse into the energy of the surrounding environmental field.

DIVIDING A CLOUD IN HALF

After connecting and rooting into the Earth's energetic field, the Qigong doctors extend their intention into the sky, connecting with a particular cloud formation. Next, the doctors condense their upward intention, and like a laser beam, be-

G. Bring your attention to your spleen.

Connect your mouth with your spleen and observe your spleen. Be aware of any worry or other emotions you do not like in your spleen. Be aware of the Kun. Chant the Kun and connect your spleen with the earth power, a yellow light. Feel the openness, balance and centeredness of this power, the essence of the earth power. Wrap this around your worries, balancing with and transforming your worries.

Spiral your worries that are still in the lungs to the center of the front pakua, the collection point of the spleen. Chant the Kun again and then Tai Chi, Tai Chi, Tai Chi. Yin-Yang, Yin-Yang, Yin-Yang. Spiral, balance, blend and transform it with the energy that is already there into a bright, golden energy.


a **b**

Fig. 5.79 a. *Draw attention to your spleen.*
b. *Balance, Openness and Fairness*

H. Spiral all remaining negative energy to the front pakua.

Return to the organs and the collection points, and spiral and breathe to draw out any remaining negative energy. Blend and neutralize it with the energy in the front pakua. See all the organs glowing with light.

gin dividing and separating the cloud into two halves. After the cloud has been divided into two separate formations, the doctors can either continue to further divide and dissect the cloud or reconnect its structure.

THE EARTHLY TREASURE OF FOOD

The Earth's natural energetic forms and transformations affect the flow of the body's life-force energy. Food and water are examples of a natural form of Earth Qi, and are viewed as Earthly Treasures. Although the air we breath is representative of Heaven Qi, due to the influence of environmental energetic fields, it is also viewed as an Earthly Treasure. The objective of self-cultivation work is to continually purify the energy within the Microcosm of Man, and increase the awareness of the pure energy within the Macrocosm of the universe.

Because of its connection to the Earth's Yin and Yang energy fields, the body's life-force energy can be replenished through the consumption of food and herbs. Both food and herbs have Yin or Yang properties which, when consumed, help the body in moving, tonifying, purging or regulating the life-force energy.

UNDERSTANDING THE YIN OR YANG ASPECT OF FOOD

When trying to determine whether a food is more Yin or Yang, several characteristics should be evaluated. Yin foods take less time to grow, are more watery or wet, and are colder, and sweeter. Yang foods take more time to grow, are drier, hotter, and less sweet. The more Yin the food, the more expanded it will become (e.g., a pumpkin); the more Yang the food, the more contracted or dense it will become (e.g., a turnip).

Diet directly influences the body's ability to generate Qi. The body's ability to effectively digest food plays a big part in how efficiently the body utilizes the nutrients it receives.

UNDERSTANDING THE YIN OR YANG ASPECT OF HERBS

Food is a powerful healing tool. Medicinal herbs are considered "special foods," and are divided into Yin and Yang aspects throughout China. They are prescribed to be taken in soups (tang), teas, or as additives to other dishes; for example, Chinese Qigong doctors, as well as many martial arts masters, frequently drink herbal teas to help regulate their body's energies during seasonal changes. The herbal teas are consumed according to the following sequence.

1. The summer is considered the season of maximum Yang; green herbal tea is drunk in order to cool down the body and regulate the internal organ systems.
2. The autumn is the season when Yin and Yang energies balance; however, the Yin energy is increasing, so flower tea is drunk to help stabilize the body's Yin and Yang balance.
3. The winter is considered the season of maximum Yin; black or red tea is drunk to warm the body and regulate the internal organ systems.
4. The springtime is the season when Yin and Yang energies balance; however, the Yang energy is increasing, so flower tea is drunk to help stabilize the body's Yin and Yang balance.

Teas are frequently prescribed for their particular healing properties. Each herb has a specific nature. Herbs that are considered Hot or Warm are used to treat Cold conditions, and herbs that are considered Cold or Cool are used to treat Hot conditions. Herbs are also categorized according to their flavor (sour, bitter, sweet, pungent, or salty) and are used to affect the body's internal organ energy. Herbs help the Qi ascend or descend in order to purge or tonify an internal organ or channel. Herbs are also used in moving the Blood. Specific herbs are also chosen for prescription, based on the Differential Diagnosis according to the Eight Energetic Principles (see chapter 21), the Five Elements (see chapter 23), and the Six Stages (see chapter 24) theories .

Generally, because all herbs have medical uses and contraindications, they are collected and divided into three categories: superior herbs - which consist of tonics, common herbs - which are slightly toxic, and inferior herbs - which are toxic. To gather herbs, the doctor must have an extensive knowledge of the environment (season, place, time, etc.), and the specific herb (roots, bark, leaves, flowers, fruits, etc.) The doctor must also possess the harvesting skill required for gathering the herb. Once the herbs have been gathered, the doctor must then begin the procedure of processing them. The process work is important as some herbs are poisonous and need to be detoxified, while others have their properties enhanced through the extracting process.

ENERGY, FOOD, AND DIET

Many generations have asked the same question, "Is food medicine or medicine food?" An old Chinese proverb states, "To tonify with food is better than with medicine, but to tonify with Qi is better than food." Several decades of nutritional, epidemiological, and clinical studies point to a powerful link between disease and dietary habits.

For centuries, Chinese healers have studied food, discovering the properties of specific foods and the secrets of using them to achieve health and longevity. Chinese nutrition focuses on the energetic properties of food and their qualitative actions on the body as a whole, as well as their influences on the various internal organs and channels. Unless the patient eats correctly, Qigong, acupuncture, Chinese massage, and even herbal therapy will not be as effective, or long standing. In the Tang Dynasty, the great physician Sun Simiao wrote the medical classic *One Thousand Ounces Of Gold*, which described the dietary treatments of several diseases, including night blindness and goiter.

What we eat can either aggravate or enhance the healing of a particular condition. When Gu Qi (food energy) is being generated, strong surges of energy from the Spleen and Stomach (in the Middle Dantian) cause the body to generate more Yang Qi. As the body's Yin aspect weakens, its energetic nature becomes dryer and wanes; the Yang is no longer held in check and an overexuberant Yang begins to generate Heat, which produces, and sometimes releases, emotions.

Emotions begin with, and stem from, the energetic properties of Postnatal Qi. When ministering to patients, the doctor should ensure a healthy physical and social environment (e.g., clean air and a loving support system), as well as monitor the quality and quantity of food consumption. Hostile surroundings interfere with the proper digestion of food and cause toxic Qi. Food, air, and water become the fuel that generates energy in the body. When life-force energy becomes impure from poor diet, Heat accumulates in the organs, creating Excess Yang, or Excess Fire Qi.

One essential skill for harvesting the Earth's Treasures is controlling the intake of food and diet. It is important that a patient not eat foods that are excessively Cold, Hot, spicy, or greasy. If food is ingested while the food is too Yin (Cold) or out of harmony with the seasons, an external pathogenic factor can be created. When a Cold or Yin factor is created (a condition where Cold and Excess Yin consumes the Kidneys Yang, preventing the body's Yang Heat from warming the body), the Qi becomes sluggish, thus blocking the channels or collaterals. These blockages cause pain and damage to the Stomach and intestines and affect the Heart and Lungs.

If food is ingested while the food is too Yang (Hot) or out of harmony with the seasons, a Yang factor is created, causing internal energy to be released, which damages both the Blood and Qi. Because of its turbid nature, food that is too greasy may damage the Stomach Qi, causing boils and pyogenic infections, along with ulcerous skin diseases. Excessive eating may cause too much Gu Qi to develop, generating an excessive amount of power. This Excess power produces an upward reaction of Stomach Qi, which is detrimental to both the Spleen and Stomach, causing the breath to become obstructed (mother/Spleen affecting child/Lungs), and the psychic centers (Shen within the Heart) to become blocked. Many postnatal illnesses result from eating the wrong kinds of food in the wrong season, not eating enough of the right kind of food, overeating, or all of the above.

Balancing the diet in accordance with the cycles of nature and the principles of Yin and Yang

Balancing the Diet					
	Liver	**Heart**	**Spleen**	**Lungs**	**Kidneys**
Excess	Sour	Bitter	Sweet	Pungent	Salty
Controlled By	Pungent	Salty	Sour	Bitter	Sweet
Counteracts	Sweet	Pungent	Salty	Sour	Bitter

Figure 12.3. The Five Flavors and their Controlling and Counteracting Cycles

should be an integral part of the daily practice. In some situations, the body can compensate for an improper or unbalanced diet. To counteract this imbalance, however, the body will expend a great quantity of energy. Eating similar foods all the time results in the accumulation of toxins from those foods and can cause mildly allergic reactions. A balance of the different food groups is the key to dietary success.

USING THE FIVE FLAVORS OF FOOD

The energetic properties of the Five Flavors of food (sour, bitter, sweet, pungent, or salty) can be used to balance and control the energy of each organ. Any excess or deficiency of one flavor affects not only the organ to which it corresponds, but all the other organs as well (Figure 12.3). In the clinics in China, the theory of the Five Flavors or tastes is combined with the theory of the Five Elements to describe the interaction of the different "flavors" on the body's internal organs and energetic systems (Figure 12.4). The Five Flavors and their affect on the body are described in the following sections.

SOUR TASTE, ELEMENT WOOD

Some examples of Sour foods include: lemons, pickles, liver, vinegar, wheat, salad oils, and sour cream. Sour foods affect the Liver, eyes, and tendons. They are also excellent for stimulating the energy of the Liver and Gall Bladder.

1. Sour foods are astringent (causes shrinking), and can be prescribed to achieve the following treatment goals:
    - to prevent or reverse the abnormal leakage of Qi and Fluids,
    - to counteract diarrhea and excessive perspiration by slowing the movement of fluids,
    - to drain the Liver of Excess Qi, thereby indirectly strengthening the Lungs, and
    - to correct an irregular, slow heartbeat.
2. An excess of sour foods can cause the following dysfunctions:
    - injures the muscles,
    - hardening and wrinkling of the skin, and
    - stiffness spreading along the tendons that are controlled by the Liver. As the Liver controls the tendons, patients with Liver trouble should also eat less sour food.

BITTER TASTE, ELEMENT FIRE

Some examples of Bitter foods include: coffee, black and green teas, asparagus, celery, turnips, leeks, cabbage, broccoli, and cauliflower. Bitter foods affect the Heart, tongue, and Blood. They are also excellent for stimulating the energy of the Heart and Small Intestine.

1. Bitter foods are used for draining and drying, and can be prescribed to achieve the following treatment goals:
    - to stimulate the energy of the Heart, control the Heart Fire,
    - to reducing fever and Excess body Heat,
    - to stimulate digestion,

Five Elemental Cycle					
Element	Fire	Metal	Wood	Earth	Water
Season	Summer	Autumn	Spring	Late Summer	Winter
Organ	Heart	Lungs	Liver	Spleen/ Pancreas	Kidneys
Bowel	Small Intestine	Large Intestine	Gall Bladder	Stomach	Urinary Bladder
Superficial Organ	Blood Vessels	Skin	Nerves	Muscles	Bones
Release Point (Sense Organ)	Tongue	Nose	Eyes	Mouth	Ears
Taste	Bitter	Pungent	Sour	Sweet	Salty

Figure 12.4. The Five Flavors in Relationship to the Body's Internal Organs, Seasons, and Elements

- to drain Excess Spleen Qi, and
- to remove obstructions in the upper respiratory tract.

2. An excess of Bitter foods can cause the following dysfunctions:
   - dryness and congestion of the Spleen and Stomach; and
   - hyperactivity of the Heart Fire, and the consumption of Kidney Yin fluids.

SWEET TASTE, ELEMENT EARTH

Some examples of Sweet foods include: honey, sugar cane, orange juice, pecans, snow peas, corn, milk, and sweet potatoes. Sweet foods affect the Spleen, mouth, and muscles. They are also excellent for stimulating the energy of the Spleen, Stomach, and pancreas.

1. Sweet foods are used for tonifying, regulating and sometimes moistening, and can be prescribed to achieve the following treatment goals:
   - to stimulate the digestive Fire,
   - to tonify the Spleen, Stomach and pancreas, and
   - to drain the Heart of Excess Qi.
2. An excess of sweet foods can cause the following dysfunctions:
   - an imbalance in the Kidneys,
   - an aching in the bones,
   - hair loss from the head,
   - muscle dysfunctions, and
   - injury to the Spleen and Stomach. The Sweet flavor spreads through the muscles, so patients with diseases of Spleen, Stomach, or muscles (diabetes, hypoglycemia, systemic candida, fibriomyalgia, chronic fatigue, etc.) should limit their intake of Sweet foods.

PUNGENT TASTE, ELEMENT METAL

Some examples of Pungent foods include: garlic, onions, ginger, black and white pepper, mustard, and chilies. Pungent foods affect the Lungs, nose, skin, and body hair. They are also excellent for the stimulating the energy of the

Lungs and Large Intestine. Because the Lungs control the Qi, the Lungs are very quick in absorbing the energy of Pungent foods.

1. Pungent foods are used for dispersing and moving, and can be prescribed to achieve the following treatment goals:
   - to induce perspiration,
   - to improve circulation of Qi and Blood,
   - to stimulate the digestion,
   - to activate the Lung energy and promote the Lung's function,
   - to expand the Lung Qi,
   - to drain the Lungs of Excess Qi, and
   - to increase Fluids and saliva secretions.
2. An excess of Pungent foods can cause the following dysfunctions:
   - great loss of Lung energy and damage to the Lung organs,
   - knots in the muscles, and
   - withering or decay of the fingernails and toenails.

SALTY TASTE, ELEMENT WATER

Some examples of Salty foods include: shellfish, cheese, soy sauce, salt, ham/pork, and margarine. Salty foods affect the Kidneys, ears, and bones. They are also excellent for stimulating the Kidney Qi and Bladder Qi.

1. Salty foods are used for purging and softening, and can be prescribed to achieve the following treatment goals:
   - to soften hard nodules such as cysts,
   - to purge inflamed lymph glands, and
   - to soften knotted muscles.
2. An excess of Salty foods can cause the following dysfunctions:
   - cause damage to the Kidneys and Bladder,
   - cause the Blood to coagulate or clot,
   - cause Blood diseases,
   - harden the pulse, and
   - cause changes in the complexion.

GUIDELINES FOR THE FIVE ELEMENTAL TASTES

During each season, the five separate extremes in flavors serve as a catalyst to draw Qi into the Deficient organ. Overexposure to the seasonal elements (Cold, Wind, Damp, etc.) is responsible for external pathogenic factors that invade the body and affect the body's Jing, Qi, and Shen. The development of disease is due to an imbalance in the struggle between the body's health preserving Qi and the pathogenic influences. If the pathogenic factors are excessive, they can obstruct the body's normal physiological function, creating illness. If, however, the body's Qi is strong, the pathogenic factors will have a difficult time causing any energetic imbalances.



Figure 12.5. The quality of the body's pulse is constantly changing according to the rhythm of the five seasons.

Traditional Chinese Medicine divides the effects of these tastes into five seasons, each with its own unique function and flow of energy affecting the human body. One example of the effects of nature's rhythms on man is that the pulse quality in the viscera constantly changes in accordance with the five seasons (Figure 12.5). The Liver pulse is relatively strong in spring, compared to the other organs; in the summer the Heart is stronger, in the late summer - the Spleen, in the autumn - the Lungs, and in winter - the Kidneys.

Basic guidelines are developed for eating in accordance with the flow of the Five-Element cycle. These guidelines will help train the body to recognize what foods it needs. The food types and tastes are divided into five categories, which relate to the five seasons of the year, the Five Elements, and the Yin and Yang organs (Figure 12.6).

To achieve overall balance, food and energy must be equally balanced. If the Liver is weak, for example, eating Sour food will help correct it and Salty food will also help. This prescription is based on the Five Element theory, which focuses primarily on two cycles—the Generating Cycle and the Controlling Cycle (Figure 12.7).

OVERVIEW OF THE FIVE ELEMENTAL TASTES

The overall understanding of the Five Elemental tastes empowers the Qigong doctor to accurately assist in prescribing better eating habits for his or her patients. By understanding the seasonal eating patterns (i.e., in the winter eating root food, which is grown under the ground, and in the summer eating food that is grown via branches and flowers) the doctor can observe whether the patient is further compounding his or her disease condition through improper diet.

SUMMARY

In comprehending the energetic potential of the Three Treasures of Earth, the Qigong doctor will be able to evaluate the patient's eating and living conditions and their affect on the patient's disease. This also includes prescribing the Medical Qigong exercises, meditations, diets, and eating habits needed in order to support and maintain the doctor's treatments.

Through monitoring the patient's connection to their environment and eating patterns, the Qigong doctor is able to understand the Earthly influence on the patient's physical, mental, emotional, and spiritual being.



Figure 12.6. The Five Elements' Interaction of the Five Flavors

In the Creative or Generating Cycle—		
Salty Kidney (Water)	generates	(Wood) Sour Liver
Sour Liver (Wood)	generates	(Fire) Bitter Heart
Bitter Heart (Fire)	generates	(Earth) Sweet Spleen
Sweet Spleen (Earth)	generates	(Metal) Pungent Lung
Pungent Lung (Metal)	generates	(Water) Salty Kidney

In the Controlling Cycle—		
Salty Kidney (Water)	controls	(Fire) Bitter Heart
Bitter Heart (Fire)	controls	(Metal) Pungent Lungs
Pungent Lungs (Metal)	controls	(Wood) Sour Liver
Sour Liver (Wood)	controls	(Earth) Sweet Spleen
Sweet Spleen (Earth)	controls	(Water) Salty Kidneys

Figure 12.7. The Creative (or Generating) and Controlling Cycles of the Five Flavors

CHAPTER 13

THE THREE TREASURES OF MAN: JING, QI, AND SHEN

The Outer Force (Power) of the Three Treasures of Man are expressed through Jing (Essence), Qi (Energy), and Shen (Spirit). The human body is made up of vibrational frequencies that interact to create energetic fields and substances, or energetic materials ranging in structure from less dense to more dense (Figure 13.1). In order of increasing density, these energetic materials manifest as Spirit (Shen), Energy (Qi), Essence (Jing), Blood (Xue), Body Fluids (Ye/Jin), Marrow (Sui), and Bone (Gu). Of these energetic substances, Essence (Jing), Energy (Qi), and Spirit (Shen) are regarded as the most important. These three materials perform the most important functions in the human body, and are known as the Three Treasures of Man or San Bao.

The energy of the human body, or Man's Qi, is created from and through different interacting rates of vibration and energy fields that combine to form the body's cells, tissues, and organs, creating a living organism. In Chinese philosophy, the Three Treasures of Man also represent the interaction of Heaven and Earth within the human body.

Man is composed of these combined Heaven and Earth energies:

1. The Jing is the body's tangible essence, composed of a morphogenic field of energy that creates and sustains the body's physical form. It is the lower vibrational frequency of the human energy matrix. During the healing process, the patient's Jing directs the proper cells to multiply so that the body can heal rapidly and completely.
2. The Qi is the life-force energy that maintains the body's Jing. It is the electromagnetic body of the channel system and distributes vitality to the body through energetic transference. It

Natural Human Transformations

Yin Organ	Yang Organ	Sense Organ	Taste	Color	Body Smell	Sound	Tissue	Positive Emotion	Negative Emotion
Liver	Gall Bladder	Eyes	Sour	Green	Rancid or goatish	Shout	Nerves & tendons	Kindness, benevolence	Anger
Heart	Small Intestine	Tongue	Bitter	Red	Scorched or burned	Laugh	Blood vessels	Love, joy, respect	Elation, arrogance, impatience
Spleen	Stomach	Mouth	Sweet	Yellow	Sweet, fragrant	Sing	Muscles & fascia	Fairness, openness	Worry, anxiety
Lungs	Large Intestine	Nose	Pungent	White	Tidepool, fishy	Weep	Skin & hair	Righteous, courageous	Sadness, grief
Kidneys	Bladder	Ears	Salty	Blue	Putrid, rotten	Groan	Bones	Gentleness, wisdom	Fear

Figure 13.1. This diagram shows the natural transformations of man's internal organs, energy, and matter, as well as their natural manifestations.

is the middle vibrational frequency of the human energy matrix. The vibrational field of Qi sustains and contains the thoughts and emotions, and interacts between the vibrational fields of Jing and Shen.

3. The Shen is the spirit and psyche which maintains the body's Qi. It is the higher vibrational frequency of the human energy matrix. It is also the energetic field which sustains the vibration of the Mind (the process of awareness and consciousness located throughout the body, not limited to the brain), interfacing between the Mind and Qi.

These three substances resonate at different frequencies and are mutually dependent upon each other for maintenance and survival. Low frequencies are attributed to the resonance of Jing, medium frequencies to the resonance of Qi, and high frequencies to the resonance of Shen. Metaphorically speaking, Jing can be compared to a dense, solid material such as ice, Qi to a flowing material such as water, and Shen to a vapor.

In Chinese medicine, the Qigong doctor uses the Three Treasures of Man for assessing and diagnosing the patient. Observing the state and interaction of the patient's Jing, Qi, and Shen allows the doctor to determine the patient's prognosis and chances for successful treatment. The doctor can assess the Jing, Qi, and Shen by:

1. Observing the general vitality of the patient's Jing through pulse reading and tongue diagnosis,
2. Noting the general vitality of the patient's Qi through observation of the Wei Qi field, and
3. Observing the general vitality of the patient's Shen by the quality of glitter in the patient's eyes.

Within this model, Jing, Qi, and Shen are viewed as layers of energetic fields between the body and the Mind. Jing is the innermost energetic layer, the blueprint which holds the physical body to the desired form. Shen is the outer energetic layer of the body through which the Mind experiences and directs the activity of the body. Qi is the intermediate energetic layer, the medium which allows the Jing and Shen (the energetic fields of the body and spirit) to communicate.



Figure 13.2. The Three Treasures of Man

PRENATAL AND POSTNATAL JING, QI, AND SHEN TRANSFORMATIONS

Jing is the body's foundational substance, responsible for nourishing the tissues. Qi emerges out of Jing circulating through the tissues. It promotes the body's metabolism. Shen governs the body. The body contains both prenatal and postnatal versions of Jing, Qi and Shen.

1. Prenatal Jing (Yuan Jing) is the body's innate and true Original Essence, which determines the constitutional makeup, strength, and vitality. It is not the reproductive Essence (sperm and ovary essence), which is considered Postnatal Jing.
2. Prenatal Qi (Yuan Qi) is the body's Original Energy, extending into the Wuji (infinite space or Void). It is the motivative energetic force linking the Prenatal Jing with the Prenatal Shen. It is not inhaled air (oxygen), which is considered Postnatal Qi.
3. Prenatal Shen (Yuan Shen) is the Original Spirit, that is able to perceive and intuit truth and knowledge (knowing without knowing). It is not cognitive thinking or consciousness, which is considered Postnatal Shen.

Through meditation, the body's alchemical processes of internal energy transmutations can be cultivated. Jing can be used to create or increase Qi; likewise, Qi can be used to create or expand the Shen. This creative cycle also works in reverse order by transforming Shen to Qi, and Qi to Jing (Figure 13.2).


Prenatal Transition
Dao - Divine
Wuji - Infinate Space
The Formless Void
Yuan Shen - Original Spirit
Perceptive and Intuitive Knowledge
Yuan Qi - Original Energy
Extends into the Wuji
Yuan Jing - Original Essence
Determines Constitutional Form,
Strength and Vitality
Postnatal Transition
Dao - Divine
Wuji - Infinate Space
The Formless Void
Shen - Acquired Spirit from
Cognative Thinking
Qi - Acquired Energy from
Food, Air and Water
Jing - Reproductive Essence

Figure 13.3. The Prenatal and Postnatal Alchemical Transitions of Jing, Qi, and Shen

PRENATAL TRANSFORMATIONS

The following transformations describe the origin and creation process of the Three Treasures within the body of the fetus (Figure 13.3). Through comprehending these transformations, the Qigong doctor can teach individuals how to cultivate their Jing. The body's prenatal energies, which support the body's postnatal Jing, are sustained by prayer, meditation, and sleep. This quiescence state is necessary for the body to reenergize its Prenatal Qi.

1. Divine Energy (Dao) transforms into infinite space (Wuji). At this beginning stage, the spirit of the God envelops infinite space, including the energetic fields of the Heavenly universe and the environmental Earthly fields.
2. Infinite space (Wuji) transforms into Spirit (Yuan Shen). At this transition, the spirit of God descends to permeate, unite, and dwell within the Original Spirit (Yuan Shen) of the forming fetus.
3. Spirit (Yuan Shen) transforms into Energy (Yuan Qi). At this stage of transition, the Original Spirit of the fetus transforms into Original Energy (Yuan Qi).
4. Energy (Yuan Qi) Transforms into Essence (Yuan Jing). At this final stage, the Original Energy of the fetus is transformed into Original Essence (Yuan Jing).

POSTNATAL TRANSFORMATIONS

The following transformations describe the origin and creation process of the Three Treasures within the body after birth. Through comprehending these transformations, the Qigong doctor is able to achieve a harmonious balance between the three energies through Postnatal Jing cultivation. The body's postnatal energies are supported and sustained first of all through food, drink, and air.

1. Essence (Jing) Transforms into Energy (Qi). At this beginning stage, the body's Jing is Heated within the Lower Dantian to create Qi. This transition is similar to ice melting into water.
2. Energy (Qi) Transforms into Spirit (Shen). At this transition the body's Qi is steamed within the Middle Dantian, to be transformed into Shen. This transition is similar to water transforming into vapor.
3. Spirit (Shen) Transforms into infinite space (Wuji). At this stage, the body's Shen fuses with the resonant light of the Upper Dantian

I. Be aware of the back, left and right pakuas.

When you have time, you can chant the kuas to enforce the power of the pakuas. Let the Tai Chi in all four pakuas spiral, drawing in, blending and transforming the energies. Continue spiraling and with the spiraling and the breath you draw, suck in the energy to the cauldron, the big empty space in the Tan Tien. Now spiral the energy in the cauldron, chanting subvocally Tai Chi, Yin-Yang, condensing the energy into a bright golden energy ball, a pearl. Bring the pearl to the perineum and circulate it in the Microcosmic Orbit. As the pearl moves through the Microcosmic Orbit, feel that it attracts and absorbs the Universal (at the crown), the Cosmic Particle (at the mideye) and the Earth (at the perineum) Force.

Bring the pearl back into the cauldron. Center yourself in the cauldron and feel your senses and mind drawn inward towards the energy in the cauldron. Feel nice, calm and peaceful inside. When you have time, sit for a while and let this energy and feeling grow inside you.



Fig. 5.80 *Let all the Organ Energy flow down to the Pakua and feel Chi grow inside you.*

and is transformed and released into the Heavenly and Earthly fields of energetic space. This transition is similar to vapor diffusing into space.

4. Infinite Space (Wuji) Reunites with the Divine (Dao). At this final stage, the Shen is reunited with the divine.

The Shen directs the increased amount and flow of Qi during the transformation process of Jing into Qi and Qi into Shen through conscious intention. Through this soft focused intention an alchemical cycle of transformation is created whereby Jing, Qi, and Shen can then be gathered, refined, and trained.

TRANSFORMATIONAL ATTAINMENT MODALITIES

Each of these prenatal and postnatal transformations include training exercises and meditations that are either developed in low, medium, or high attainment approaches. The low attainment approach is known as the physical attainment approach; the medium attainment approach is known as the mental attainment approach; and the high attainment approach is known as the spiritual attainment approach. Qigong regulation encompasses all three attainment modalities in order to facilitate the ultimate in energetic transformation. The three attainment approaches for increasing to maximum capacity the body's energy are described as follows.

1. The Physical Attainment Approach concentrates on the development and cultivation of the body's energy by focusing on Dynamic (energetic movement) and Quiescent (stillness) Qigong meditations to fully realize one's energetic potential.
2. The Mental Attainment Approach concentrates on increasing mental power by focusing on symbolic drawings, reciting prayers, or mantras to manifest fully one's mental potential.
3. The Spiritual Attainment Approach concentrates on the development and cultivation of the body's Original Spirit (Yuan Shen) by focusing on Shengong meditations (meditations that focus on spiritual cultivation) to harvest one's spiritual potential.

JING: ESSENCE OF LIFE

Jing refers to the indispensable bioenergetic substance of all living things (i.e., the energetic matrix of the body's cells, tissues, etc.). In Medical Qigong therapy, Jing is considered the most Yin form of Qi. Jing, as a pure Essence of living matter, is more dense than Qi but more refined than Blood or Fluids. When Jing is cultivated and allowed to arise naturally within the body, the outer surface of the body's tissues becomes harmonized and glows. Deep within the tissues, the Jing pools like a deep spring. The greater the degree of harmony between the individual's physical, mental, energetic, emotional, and spiritual fields, the more Jing is transformed into Qi.

THE YIN AND YANG ASPECTS OF JING

Jing can be divided into the functional aspects of Yin and Yang properties. The Yin aspect of Jing provides the material basis for growth, development and reproduction, and is the substratum for the formation of the materials associated with the Marrow and Blood. The Yang aspect of Jing activates transformations, growth, development and reproduction, and is associated with the Yuan Qi, Blood and Body Fluids (Figure 13.4).

As a subtle energy, Jing has a tendency towards downward movement, flowing like water, it fills the Lower Dantian, adrenals, Kidneys, and urogenital organs. Essence originates from two sources and can be divided into Prenatal and Postnatal Jing.

PRENATAL JING

Prenatal Jing is also called Original Essence (Yuan Jing). It is inherited from the Jing of both parents and is considered the root of life. It is created upon conception through the blending of both parents' sexual energies and substances. Prenatal Jing constitutes the original substance of the body, and serves as the material base for growth, development, and reproduction. With the help of the Qi and Blood acquired from the mother, the Jing is responsible for the nourishment and development of the embryo's and fetus's brain, bones, muscles, tendons, skin, and hair. The Pre-


Prenatal Jing
(from both parents)
Yang aspect of Jing
Activates transformation, growth, development and reproduction.
Yuan Qi
(Original Qi)
Jing
(Essence)
Brain
Postnatal Jing
(from food and drink)
Yin aspect of Jing
Provides the material basis for growth, development and reproduction.
Marrow
Bone Marrow
Blood

Figure 13.4. The Formation of Jing

natal Jing determines each person's basic constitution, strength, and vitality.

POSTNATAL JING

Postnatal Jing is also called the Acquired Essence. It is the Essence of the body's main organs, derived from air and Gu Qi (produced from food and drink by the transformation process of the Spleen and Stomach) which is transported through the channels and vessels to nourish the body's Yin organs, and to irrigate the Yang organs. Postnatal Jing is the material basis for the functional activities of the body's internal organs and metabolism. It is transported (through the function of the Lungs) to all the Yin and Yang organs where it becomes reproductive Yin and Yang Jing. The Kidneys are responsible for storing any surplus Jing to be distributed when needed.

THE INTERACTION OF PRENATAL AND POSTNATAL JING

The Prenatal and Postnatal Jing are interdependent and contribute equally to the growth and development of each other. Postnatal Jing is continually being used by the body and replenished with food and drink. Only with the nourishment of the Postnatal (Acquired) Jing can the Prenatal (Congenital) Jing be enriched and function optimally. Without the function of the Prenatal Jing, the Postnatal Jing cannot be transformed into Qi.

Postnatal Jing is continually being used and replenished through the Spleen's production of Gu Qi from food and drink. This is why so much emphasis is placed on the first postnatal alchemical transition of changing Jing into Qi. Through Medical Qigong exercises, the body is able to stimulate, nourish, and preserve its Jing.

Both Prenatal and Postnatal Jing are related to the Kidneys, which generate bone growth as well as nourish the brain, memory development, and body stamina. The *Yellow Emperor's Classic of Internal Medicine* states that women are on a seven year developmental cycle, while men are on an eight year cycle. Problems with the body's Jing result in developmental problems (i.e. improper maturation, sexual dysfunction, infertility, and premature aging).

The Kidney Jing is responsible for extending the life-force energy up the Governing Vessel into the brain. The Kidney Jing also transforms into Marrow and is responsible for the production of bone marrow, which fills up the spinal cord and brain. When the Jing becomes exhausted, the memory begins to fail and the spirit becomes fatigued. It is important to remember that all types of Jing do not exist as separate substances, but support, interact with, and transform into one another.

The Kidney Jing also works in conjunction with the Qi to establish the body's state of mind and emotional health, which together determine the development of the Five Elemental Constitutions.

QI: VITAL LIFE-FORCE ENERGY

Qi is the energetic substance from which the entire universe was created. Through the interaction and transformation of Yin and Yang Qi, the various substances of form and matter are produced. This vital life-force energy comprises both material and functional aspects of the body.

Qi is the medium between matter (Jing) and Spirit (Shen). Chinese medicine describes many different kinds of Qi. Qi can assume an infinite number of forms according to its state of condensation or dispersion. When Qi condenses, matter is created, and when Qi disperses, energy is created. Although Qi in the body can assume different forms, that have different functions, it is essentially all one energy. The patient's Jing, for example, may be ready to receive a new energetic pattern for accelerated healing, and the Shen may be ready to send this required pattern. But, if the body's Qi is weak or turbulent, it will not transmit this information from the Shen to the patient's Jing, thus delaying or impeding the healing process.

The body's Qi can be classified into two primary forms of energy: Prenatal and Postnatal Qi.

PRENATAL QI

Prenatal Qi (or Xian Tian Zhi Qi, which translates as, "before the baby sees the sky energy") is also called Yuan Qi, or Original Qi. This is the energy that the baby inherits from his or her parents during conception. It is stored in the sexual glands and adrenal cortex, and it is essential for the growth and development of the fetus.

It is Jing in the form of energy, that is cultivated through Qigong practice. Yuan Qi is the innate or inborn energy that is the original force which maintains normal growth and development, and promotes the functional activities of the internal organs. Its role is to bring into existence the vital mechanisms of the human body according to their genetic pattern, conforming them to the models transmitted by each person's lineage.

Prenatal Qi contains elements of all of one's predecessors and gives rise to the Prenatal Jing, and is seen as a means of transmitting the Deoxyribonucleic Acid (DNA) code. Prenatal Qi relies on nourishment from Postnatal Jing. Through Prenatal Qi, each individual is energetically connected with everything in existence. Prenatal Qi also relies on Postnatal Qi for nourishment.

Methods of training Qi and regulating it include counting respirations as the Mind focuses on rooting the Qi into the Lower Dantian, Mingmen, or Kidneys' area.

There are three types of prenatal energy regulations used for circulating and harmonizing the body's internal energy or Dantian Qi:

1. The first type of Qi regulation focuses on moving energy through the body's main channels and torso. This is the most common type of Prenatal Qi circulation, directing the energy to flow along the course of the body's Conception and Governing Vessels, i.e., the "small" Heavenly cycles (Microcosmic Orbits). This type of Qigong exercise is commonly referred to as an Inner Cultivation and Regulation method.
2. The second type of Qi regulation focuses on moving energy through the body's channels and extremities. In this type of Qi circulation, the body's Prenatal Qi is directed to flow only along specific channels (i.e., being led from one channel out from the torso into an extremities and then back into the body through another channel). This type of energetic balancing is commonly seen in the "large" Heavenly cycles (Macrocosmic Orbits) and bone marrow regulation.
3. The third type of Qi regulation focuses on

moving the energy of Heaven (Universal Qi), Earth (Environment Qi) and Man (Qi of the physical body) through the channels. In this type of circulation, these three types of energy are integrated or merged into one energy and then regulated. Upon inhalation, the individual imagines Prenatal Qi circulating from Heaven through the body's channels into the Earth. Then upon exhalation, the energy is imagined flowing from the Earth, through the channels, back into Heaven.

POSTNATAL QI

Postnatal Qi (or Hou Tian Zhi Qi, which translates as, "after the baby sees the sky energy") is also called acquired or Post-Heaven Qi. This is the energy that the baby derives from air, food, and drink after it has been born. Postnatal Qi relies on Prenatal Qi for development.

Prenatal and Postnatal Qi form the foundation for the body's vital energy. In Traditional Chinese Medicine it is believed that the parents' health and their state of Jing, Qi, and Shen at the time of conception determines the general health of the child. If the parents are sick, or their health has is compromised by drinking, smoking, or drug use, the baby's health will suffer. If the parents are old, or have suffered an emotional shock during the pregnancy, this too will negatively impact the baby's health.

Methods of training Postnatal Qi include deep, tranquil abdominal respiration. This method trains the respiratory system to improve both the respiratory and digestive systems, enhancing both the Lung and Spleen Qi.

EIGHTEEN CLASSIFICATIONS OF QI

The distribution and function of life-force energy can be further divided and classified according to the source and function of the Qi. Below is a description of eighteen transitions of Qi and their energetic effects on the body.

1. Prenatal Qi (Yuan Qi), is often referred to as Original Qi, and includes the Original Yin and Original Yang energies of the body. Yuan Qi has its root in-between the Kidneys and Mingmen area, it is distributed throughout the entire body via the Triple Burners.
2. Postnatal Qi, is an external energy derived from the consumption of food and drink (from the Earth), and air (from the Heavens), and is a term used to describe the Qi which is cultivated after one is born.
3. Heavenly Qi (Tian Qi), is energy that has been developed from the energies of the sun, moon and stars. Tian Qi is absorbed into the Lung Qi as Air Qi (oxygen) through respiration.
4. Earthly Qi (Di Qi), is energy that has been developed from the energies of the soil, water and wind. Di Qi is absorbed into the Stomach and Spleen where it is converted into Gu Qi (food energy); Di Qi is also directly absorbed through the pores from the environment.
5. Food Qi (Gu Qi), is the first stage of energy transformation derived from food and drink. It is also called Qi of the Water and Grain in the digestive system. After food essence is cooked in the Stomach, the Spleen transforms it into Gu Qi. At the first stage of development Gu Qi is a coarse, unusable form of food essence. The Spleen divides the energy it derives from the food essence into Pure (Clear) Yang Qi and Impure (Turbid) Yin Qi. The Clear Yang essence of Gu Qi is transported by the Center Qi (Zhong Qi) via the Middle Burner, sending it upwards into the chest, first to the Lungs where it combines with Heavenly (Tian) Qi to form Gathering (Zong) Qi, then to the Heart where it combines with the Yuan Qi (from the Kidneys) to create the Blood. The Turbid Yin essence of Gu Qi is transported downwards through the gastrointestinal tract to be expelled as waste.
6. Clear Yang Qi (Qing Qi), is the clean, pure energetic essence of Gu Qi, transported by the Spleen, via the Middle Burner, up towards the Upper Burners, and chest area. While in the chest, it is combined with Gathering (Zong) and Yuan Qi to form True Qi.
7. Turbid Yin Qi (Zhou Qi), is the clouded, impure energetic essence of Gu Qi, transported by the Spleen, via the Middle Burner, down

towards the Lower Burner, Small Intestine, and Bladder organs, to be further refined. It is a more coarse, unrefined, polluted energy.

8. Center Qi (Zhong Qi), is the energy generated from the Middle Burner, derived from the Spleen and Stomach. Its primary function is to transport the Gu Qi into the chest, to be blended with the Heart and Lungs' Qi.
9. Gathering Qi (Zong Qi), is also called Respiratory Qi. Gathering Qi is considered the "essence of life," manifested through the conversion of the purest and most potent forms of the body's Jing (particularly sexual fluids, hormones, and neurochemicals). It is essential for the formation of the fetus and is the initial motivating power of life. It promotes vitality and increases stamina; it also enhances the immune system, promotes mental clarity and prolongs life. Gathering Qi combines the Heavenly Qi (inhaled by the Lungs) and the Gu Qi (derived by the Stomach and Spleen), and accumulates these energies within the chest in order to assist the Heart in circulation the Blood, and the Lungs in respiration. It controls the speech and strength of the voice, as well as the Blood circulation to the extremities. Gathering Qi gathers in the chest and is controlled by the Middle Dantian.
10. True Qi (Zhen Qi), is also called Anti-pathogenic Qi. It originates in the Lungs and is the last stage of refinement and transformation of Qi. Gathering Qi and Yuan Qi combine their substances to form the True Qi in the chest area. True Qi fills and nourishes the body as it is further broken down into Nourishing (Ying) and Protective (Wei) Qi. True Qi is the energy that circulates inside and outside of the body, in the channels and collaterals, nourishing the Yin and Yang organs. It is called True Qi because it is the most refined and pure, and is in harmony with the environment. It is opposed by Evil Qi (Xie Qi), also called Toxic Qi, which is disharmonious and thus untrue to the body's essential nature.
11. Nourishing Qi (Ying Qi), is another form assumed by the True Qi and is the Yin aspect of the Channel Qi. Ying Qi has two major functions: to nourish the Blood, organs and tissues, and to link the mind and intention to the body. It flows within the blood vessels, as well as the channels, and is the fuel of the body's metabolism. Its potency depends upon the quality of food and water consumed, the purity of air breathed, and the efficiency of the body's digestive, respiratory, and circulatory systems. Since it is Yin, it is considered the more refined form of True Qi, as it flows in the body's inner layers and internal organs. Being directed by thoughts, it is thereby closely related to the emotions.
12. Protective Qi (Wei Qi), is a second form of True Qi and is the Yang aspect of the channel Qi. It protects the Blood, organs, and tissues from invasion of external pathogenic factors such as: harsh weather conditions, microorganisms, and harmful emotional influences. It also protects the individual from evil spiritual forces. It is the coarser Yang aspect which flows through the outer layers of the body's skin. Its texture is slippery in nature and cannot enter into the channels. It therefore circulates under the skin and in between the muscles. The Wei Qi vaporizes in between membranes, and diffuses over the chest and abdominal area to form a kind of energetic armor. It also warms, moistens, and contributes to the nourishment of the skin and muscles. The Wei Qi also helps regulate the perspiration by opening and closing the pores.

Wei Qi has its root in the Lower Burner (Kidneys), is nourished in the Middle Burner (Stomach/Spleen), and spreads from the Upper Burner (Lungs) to the outside of the body. Wei Qi is said to be located at the superficial level of the body during the day, in the muscles, skin, hair, etc. At night it sinks to a deeper level to circulate through the viscera. If the Wei Qi is obstructed in some manner from moving inward, insomnia may result. Also, Wei Qi becomes thick and extends outside its normal realm during Medical Qigong practice and may, therefore, take longer to move inward at night, causing some practitioners to experience difficulty falling asleep after evening Qigong practice.

13. Channel Qi (Jing-Luo Qi), is also called Meridian Qi. This energy flows throughout the body's deep internal and superficial channels, as well as through the collaterals and blood vessels like rivers and streams.
14. Organ Qi (Zang and Fu Qi), is the energy of the physiological activity of the body's internal organs and manifests as a major aspect of its physiological function. Individual pools of Qi are formed within the pairs of Yang-Fu (hollow) bowels and Yin-Zang (Solid) viscera. The Yang organs are responsible for transforming food and drink to produce Qi and Blood. The Yin organs are responsible for storing vital substances. Each organ can be additionally divided into pairs of Yin and Yang energetic aspects.

    Each of the body's organs has its own energy, which is governed by, and corresponds to, one of the Five Elemental energies. These Five Elemental energies respond to the external energetic fields drawn from the universal and environmental energetic fields. The internal processes of thinking and feeling, as well as the physiological process such as metabolism and hormonal production influence the Organ Qi.
15. Evil Qi (Xie Qi), is also called Pathogenic Qi, and Toxic Qi. This usually refers to any harmful external pathogenic factor (especially the Six Climatic factors). However, it also refers to the evil spirits and stuffed toxic emotions, which affect the individual's physical, energetic, and emotional balance.
16. Righteous Qi (Zheng Qi), is the defensive aspect of the True Qi, which protects the body from Evil Qi. This is not actually another type of energy, but a term used to indicate the True Qi's function of protecting the body from invasion by external pathogenic factors. The occurrence and development of disease is directly related to either the hyperactivity or hypoactivity of the Righteous Qi.
17. Spiritual Qi (Ling Qi), is the supernatural energy associated with the most highly refined energy in the human body manifesting through the Eternal Soul. This type of energy enhances spiritual awareness and constitutes the foundation for advanced levels of spiritual conditioning, and the attainment of an enhanced energetic body, and enlightened states of mind and spirit.
18. Divine Qi (Shangdi Qi), is also called Holy Energy or God's Healing Light. It is the supernatural energy associated with the Divine (Dao). The divine energy is the true source of spiritual awareness and constitutes the foundation for advanced levels of spiritual healing, as well as attaining enlightenment.

THE SIX FUNCTIONS OF QI

A Qigong doctor will primarily focus on a patient's combination of Original Qi (Yuan), Gathering Qi (Zong), Nourishing Qi (Ying), and Protective Qi (Wei) when treating or prescribing homework. Initially, Qi has six main functions in regulating the body. Although these functions may seem to overlap, their individual responsibilities are distinct.

1. Qi transforms substances into energy (one example of its transforming nature is changing food into energy).
2. Qi transports the substances it creates.
3. Qi holds and contains energy, Blood and organs, etc., within the energetic and visceral structures.
4. Qi protects against both external and internal pathogenic factors.
5. Qi raises and elevates things (for example, Blood, associated Fluids, and the body's temperature).
6. Qi keeps the body warm (for example, strong Qi will warm the body, while weak Qi makes the body cold).

The normal physiological activity of Qi in the body is a constant harmonious movement, similar to the ebb and flow of a tide. When the body's Qi is in constant motion, it moves in eight primary Yin and Yang directions: ascending and descending, gathering and dispersing, expanding


Sun, Moon, Stars
Environmental Qi
Soil, Water, Wind
Heaven Qi
Tian Qi
Earth Qi
Di Qi
Intestinal Tract
Bladder
Skin,
Muscles,
Tears,
Sweat,
Saliva,
Mucus
Center Qi
Zhong Qi
Stomach
Food
Drink
Triple
Burners
Body Fluids
Jin
Lungs
Food Qi
Gu Qi
Spleen
Turbid Yin Qi
Zhou Qi
Body Liquids
Ye
Gathering Qi
Zong Qi
Clear Yang Qi
Qing Qi
Nourishing Qi
Ying Qi
Joints,
Lubricate
Sensory
Organs
Heart
True Qi
Zhen Qi
Channel Qi,
Blood Vessels,
All Organs
Kidneys
Blood
Xue
Bone
Marrow
Marrow
Sea of Sui
Jing
Original Qi
Yuan Qi
Protective Qi
Wei Qi
Muscles,
Skin,
Outside,
Channels
Brain
Spinal Cord
Prenatal Jing
Yuan Jing
Postnatal Jing
Righteous Qi
Zheng Qi
Protects
against
Evil Qi
Heaven Qi
Tian Qi
Kidney Yin
Mother's Ovum
Jing, Qi, Shen
Yuan Jing
Father's Sperm
Jing, Qi, Shen
Kidney Yang
Moistens &
Nourishes
all Organs
Earth Qi
Di Qi
Mingmen
Warms and
Activates all Organs

Figure 13.5. The Body's Intricate Interactions of Qi, Blending and Flowing through Internal Reservoirs of Pooled Energy.

and contracting, and entering and leaving. If however, there develops a Qi obstruction, or a Deficiency of Qi, the Qi will deviate from its natural course, and may cause Rebellious Qi, disharmony and disease.

Qigong doctors carefully examine the energetic ebb and flow of Qi to comprehend the complexity of the energetic hologram in which we exist as a living energy. As the human body absorbs, stores, utilizes, and releases energy, its natural function of transforming energy promotes health and allows us to live in harmony with the natural environment. However, once an internal organ or organ system develops a Rebellious, Excess, Deficient, or stagnant condition within the body's energetic flow, disease develops. By understanding the energetic pattern and function of each energetic organ and organ system, the Qigong doctor can diagnose the disease by retracing the energetic dysfunction to the root cause. The following graph denotes the function and flow of the body's life-force energy patterns (Figure 13.5).

QI AND ENERGETIC MEDICINE

The utilization of the Three Regulations (posture, respiration and mental Dao Yin concentrations) enable Qigong doctors not only to disperse any Toxic Qi acquired from patients, but also to regulate their own channels, through gathering energy, and increasing their own energetic fields. Through the proper use of the Mind (whole body consciousness and awareness), the doctor can simultaneously influence the energy flows within the patient's body, as well as his or her own Wei Qi fields.

As the doctor begins to focus on specific goals (i.e., dispersing Toxic Qi from a particular organ, tissue area, or channel), the patient may experience a surge and release of strong emotions and memories that had been stored in that area. The patient's energy field then shifts and moves throughout the body according to the specific emotion(s) elicited and released. This energy field is closely related to the thinking activities of the brain. As the Mind begins to release certain specific memories, the field of energy shifts and moves through the body in accordance with the specific emotions that are activated and released. During treatment, the shape, flow, rhythm, nature, and thickness of this energetic field can be perceived by the doctor who has become highly sensitive to perception of energy through "inner-vision" (see Chapter 25).

By training in the Three Dao Yin Regulations (see Chapter 14), internal energy can be guided to surge not only in the natural direction of flow within the channels, but also against it. Internal energy can also be guided along several channels at the same time, in any given direction or to specific areas of the body. By directing Qi against the flow of a channel, the doctor arrives at the source of the river (or energy). This technique is sometimes used by the Qigong doctor to collect or tonify the Qi within the patient's internal organs. This technique for storing and collecting energy is called "following the river to reach the sea." An example of this technique would be extending Qi from the patient's St-36 points, up the Stomach Channels to root, strengthen and stabilize a Deficient or Rebellious condition within the Stomach organ itself. Conversely, by directing Qi with the flow of the stream, one can disperse energy (purgation) and pull Qi out of an area leading it away from the source (e.g., pulling Liver-Stomach Heat down and out the Stomach Channel to cool an overheated Stomach).

QI AND THE BODY'S ENERGETIC STRUCTURE

Similar to the biomechanics of the respiratory, circulatory, and digestive systems, the body's energetic system has its own organization and established rules of action for regulating organ and tissue functions. The adaptability of Qi to the outside environment enables the body to absorb not only healthy energy, but also to expel Toxic Qi.

The nature of Qi is to endlessly gather and disperse, expand and contract, to flow inward and outward, to rise and fall, as it circulates. When a Qigong doctor begins to treat a patient's channels or points, he or she stimulates and activates the patient's Qi, which may arouse muscle movement and sensations which can last for quite some time.

If the frequency and nature of the doctor's Qi is similar to that of the patient's, both energetic resonance and synchronization will synergize, allowing the patient's Qi activities to be regulated and balanced at a rapid rate.

Because people vary in sensitivity to energy, some patients can be treated with Medical Qigong therapy immediately. Sensitive patients are usually taught Medical Qigong exercises allowing them to ingest energy from trees, plants, and other things of the natural world. Patients with low sensitivity may have difficulty in perceiving energy and often dissociate from their body during treatment. These patients should be given Shengong meditations to restore conscious awareness of the toxic emotions trapped within the body, thereby reestablishing a harmonious relationship with the Mind (see Chapter 32). The patient's insensitivity to the doctor's energy extension is an indication that the patient's spirit has gone out of the body in order to avoid feeling the emotions which arise from Medical Qigong therapy.

A patient insensitive to energy projection can still be in touch with basic surface feelings (i.e., hot, cold, tired, etc.); however, the deeper emotions are hidden, or energetically walled off through denial. The better the relationship between the patient and the doctor, the greater the patient's trust and surrender to the doctor's energy.

When observing the patient's Qi and energetic structure, the doctor is able to perceive and enter the patient's five energetic fields. These fields form the matrix of the patient's energetic structure, which constitute a blueprint for the body's physical structure. These energy fields have their own biological components and degree of fluidity.

These five energetic fields form the body's Sea of Energy. The term Sea of Energy (Qi), in this context, refers to the description used to explain the internal and external currents of life-force energy which surround, permeate, and function within the physical body. These energetic fields are described as follows.

1. The External Fields of Wei Qi (Protective Energy),
2. The Internal Current of Ying Qi (Nourishing Energy),
3. The Internal Sea of Blood (Xue Hai),
4. The Internal Sea of Marrow (Sui Hai), and
5. The Center Core of Light (Taiji Pole).

Within these five energetic fields, the protective and nourishing energetic fields of Wei and Ying Qi expand and contract, move and adjust their energetic flow according to the body's respiration patterns. The Sea of Blood resonates within the pulse rhythm established by the heartbeat. The Sea of Marrow undulates from the rhythm established within the body's micropulsation of the sacrum and cranium bones' flexion and extension. The energetic pattern of the Taiji Pole vibrates at the same frequency as divine light (the Dao).

THE THREE EXTERNAL FIELDS OF PROTECTIVE ENERGY (WEI QI)

There are three external energy fields that create the body's Wei Qi field. The Wei Qi field's energy flows from around the regions of the body's external muscles, skin surface, channels, collaterals and channel points, and extends several feet out from the body's tissues. All energetic forms of the physical body, including the internal organs, blood vessels, nervous systems, etc., can be accessed and treated through the three extended fields of Wei Qi.

These three fields are distinguishable from each other by gradations of density, vibrational rate, light, and temperature. All three energy fields communicate with each other, interacting so as to form the body's subtle energetic boundaries.

Enveloped within these energetic boundaries are the body's external "energetic grids," spanning the body's energetic structure like a giant web. These energetic grids are the body's external energetic field patterns, etched through the three fields of Wei Qi like a three dimensional webbed hologram (similar to a three dimensional blueprint).

It is important to note, that any disease within the body's internal structure is also imprinted in this external energetic grid. Disharmony of the body's tissues often appears first in the Wei Qi fields, before manifesting within the body. If the energetic grid is not transformed (through emitted light, sound, and resonant vibration), the disease cannot alter its destructive course, because it follows the patterns dictated within the grid. Thus, for example, a tumor surgically removed often quickly reappears. Trauma, be it physical, mental, emotional, or spiritual, as well as drug and alcohol abuse, distorts, damages, and destroys the delicate energetic web which constitutes the body's external energetic grids, making the patient more susceptible to external environmental influences.

The external energetic grids function to protect the body from external pathogenic factors, as well as to receive and transmit environmental energy. Thus, for example, a person can receive, absorb, and digest other people's emotions. The five senses are constantly receiving on outside environmental influences, which directly and indirectly affect the body's major organs. This constant influx of data, changes the body's emotional patterns, and forces individuals to adjust their emotional perspective frequently.

Researchers conducting tests in San Antonio, Texas, for example, determined that when subjects are being stared at, galvanic skin responses are considerably increased. These increases occurred even though the subjects were not consciously aware of being observed. The research determined that the body has its own expansive field of subtle awareness, which reacts even when the individual is not consciously aware of the body's energetic extension.

By reconnecting the spirit and emotions with the mind and body, the Qigong doctor is able to perceive the subtle Messages that the patient is unconsciously conveying (see Chapter 25).

THE THREE ENERGETIC BARRIERS

The Wei Qi fields are experienced at three different levels. These levels are differentiated by energetic barriers, which protect the body's boundary system. These barriers not only protect and contain the body, they help establish the individual's sense of reality, and sense of self. The third energetic field or "outer spiritual barrier" is depicted in the illustration as the outside speckled field of energy, and affects the second energetic field or "middle emotional/mental barrier." The second field of Wei Qi is depicted in the illustration as the middle white field of energy, which in turn influences the first energetic field or "physical barrier," seen as the black field of energy in the illustration (Figure 13.6).



Figure 13.6. The Three External Fields of Wei Qi

These three Wei Qi barriers are always interesting for the doctor to feel, because they change so much from patient to patient, and sometimes from moment to moment. Some patients have very strong energetic fields, they are very palpable and full. Emotions strongly affect this type of energy field. The Wei Qi field of a patient who is armoring out of fear, reticence, or self-protectiveness, can actually repel the doctor's hand back, if their field and intention is strong enough. This repelling reaction is helpful because it lets the doctor know how to pace the treatment, and encourage the patient to let go of the armoring. This allows the patient to consciously focus on relaxing and sensing the areas in the body that he or she was trying to protect.

The energetic boundaries, act as gateways to the next level of energetic field energy. To perceive

Chapter 6

Compassion Fire Meditation Practice of the Creation Cycle

Practice compassion through the act of forgiveness. To forgive is to let go. Always meet conflict with compassion.

The higher practice of inner alchemy is the transformation of the heart energy into love, the liver energy into kindness and generosity, the lung energy into courage, the kidney energy into gentleness and the spleen energy into openess and fairness. Combine all these energies into compassion. Compassion becomes non physical energy which we can carry with us when we leave the world. It is the love and joy we feel within.



Fig. 6.1 *Compassion Fire originates from the Heart.*

the patient's three fields of Wei Qi, the patient's energetic boundaries must be gently palpated. These boundaries are more easily sensed due to a thickening of energy which serves as a barrier to external pathogenic factors. Sometimes the doctor may have to move back into the patient's third or "outer" energetic field, and telepathically let the patient know that he or she will not be violated, and is safe. The doctor waits until the patient exhales (thereby expelling some tension) before entering and palpating the outer Wei Qi field. Once a release in the energetic field is felt, the doctor moves forward into the next energetic field. Because this same process occurs at all three levels, the Qigong doctor responds accordingly, waiting for the exhalation that allows them to proceed deeper into the next level of the patient's Wei Qi.

THE FIRST EXTERNAL FIELD OF WEI QI

The first external field of energy is confined to about one to two inches outside the physical body, and composed of lower etheric matter. It is related to the Lower Dantian and manifests as a holographic energy template for the physical body. It provides the spatial guidance for morphological development during the creation and formational stages of the embryo, as well as the morphological energetic patterns that assist in the repair of damaged tissues. Its energetic boundary is responsible for armoring the body against invasion of external pathogenic factors. This physical energy body is connected to the somatic tissues and cells, thus any physical-energetic interaction stimulates the body's external channels and points. This first layer is very dense and most Qigong doctors get the impression of physically contacting the patient several inches before actually touching the patient's material body. Its resonant vibrational pattern is very broad and slower than the other Wei Qi fields.

THE SECOND EXTERNAL FIELD OF WEI QI

This energy flows through the regions of the internal organs and tissues. It extends about a foot or more outside the body's tissues, and is composed of astral matter. It is related to the Middle Dantian and the emotional energy body. It contains a form of disembodied consciousness that can astral travel, and at times leave the physical body, as in near death experiences. This second layer of Wei Qi interfaces with the limbic system of the brain (the neurobiological seat of emotions) and is also linked with the sympathetic and autonomic nervous system. The second Wei Qi field's energetic boundary is responsible for protecting the body from negative emotions, destructive feelings and criticism from others. It is automatically activated when the patient is placed in a position where a lack of trust exists, or there is unwanted physical touch. The emotional energy body is connected to the visceral organs. Its main function is to receive, interpret, and verify an individual's emotions, feelings, desires, impulses, and thought patterns. It is through this energetic field that the patient's aura is typically observed as colors and light patterns. The second layer is more subtle then the first layer. When physically palpating, the sensations are similar to a magnetic attraction and repulsion. Its resonant vibrational pattern is faster than that of the first layer.

THE THIRD EXTERNAL FIELD OF WEI QI

This field extends a few feet to several hundred yards depending upon the spiritual evolution of the individual, and is composed of ketheric matter or substance. It is related to the Upper Dantian and the spiritual energy body. It is associated with intuition, inspiration, creativity, and visionary insights. Its energetic boundary is responsible for establishing security by informing the body of impending encounters, conflicts, or environmental transitions. This spiritual energy body is connected to the body's Taiji Pole, and is a container for karmic-related illnesses within the physical body. The Taiji Pole is known as the "root with many branches," as it is a repository of the soul's ancestral memories and experiences. Its function is to receive the subtle energy of the finest and fastest vibrations. It senses and interprets the data received from its environmental awareness and universal connection to the divine. The third layer is most subtle in physical sensations and requires delicate, intuitive contact. Usually the first impression when palpating this energetic field, is one of contact without a material component (like wind). It is sometimes cold, sometimes warm but always "breezy." Its resonant vibrational patterns are the highest and fastest of all the Wei Qi layers.

INTERNAL CURRENT OF NOURISHING ENERGY (YING QI)

The Ying Qi level of internal energy flows within the underlying tissues of the body and sweeps through the torso like a fast wind, expanding and falling with each respiration (Figure 13.7). The Lungs act as a great energy pump; each breath is like a gust of air flowing in and out, in a cycle of expansion and contraction through the entire body. Ying Qi swirls like a breeze; its function is to nourish the Blood, organs and, tissues. It flows within the blood vessels, as well as the channels and links the mind and intention to the body. It is responsible for the organization, construction, completion, and reconstruction of the vitality of the individual. It is integrated with the breath, and extends outward to the body's physical boundaries (skin and body hair).

The internal current of Ying Qi is most palpable when the doctor is gently touching the patient's surface tissue with his or her finger tips, and it feels almost like electromagnetic energy. Feeling the wind of Ying Qi can be likened to falling into "space" after passing through the denser outer field of Wei Qi. The action of Ying Qi, in most cases, is free flowing and connected with the breath. When listening to certain patients, the Qigong doctor may feel the Ying Qi flowing through the patient's channels, wrapping itself around the whole body like a vapor. It feels light, thin, and fairly cool compared to the next River of Blood level.

To access the "current of Ying Qi," the Qigong doctors begin by suspending their hands above the patient's first level of Wei Qi. They imagine dipping their hands into water as they allow their hands to slowly make contact with the patient's body. Once contact is made, the doctors extend their intention under the patient's skin. The doctors should match the patient's respiration and stay connected to the body until they feel the patient relax. Matching their respiration almost always slows the patient's respiratory rate, moving the patient into an altered state of consciousness. Sometimes at this point, age regression can be sensed, as the patient's body memory is triggered.



Figure 13.7. The internal current of Ying Qi flows from the Lungs and center of the chest through the entire body like a mighty wind.

SEA OF BLOOD (XUE HAI)

The Sea of Blood and its pathways constitute the body's internal network for circulating and maintaining the individual's life-force, under the direction of the Wu Jing Shen (the five separate fields that encompass the psycho-spiritual energetic transformations of the Five Yin Organs). The

Sea of Blood's energy flows through the blood arteries, vessels, capillaries, and the tissues of the major organs (Figure 13.8). By extending further into the body, the Qigong doctor perceives the patient's Sea of Blood; it feels like a warm watery pool in the center of the Heart, and flows through the entire body. The transition from Ying Qi to Xue Qi (Blood Qi) is easy to detect.

The energetic sensation of Blood is more substantial than the Wei or Ying Qi. The Blood being a liquid, is a denser form of Qi, and flows through the vessels, organs, and channels propelled by the Ying Qi. It is thick (this thickness varies from person to person), warm and somewhat "slick." The Heart's energy itself feels warm, substantial, and very alive.

As doctors gently touches the patient's surface tissue with his or her fingertips, the doctor extends intention deep into the patient's Heart. Upon contacting the Xue Qi, the doctor immediately becomes connected to the heartbeat of the patient. In some cases, the pulsing will connect and merge with the doctor's own heartbeat. Once the doctors encapsulates the patient's Heart, the strong emotions emanating from patients will usually subside. These feelings may be replaced by sporadic spurts of emotions such as relief, peace, or comfort, which sometimes invite the doctor further into the patient. On the other hand, some patients may react with feelings of fear, intense emotional pain, or even panic causing the doctor's hand to "bounce" away.

If the doctor's energy is "bounced back," he or she should immediately disperse the energetic charge into the Earth for ground purposes. The doctor should then either move to a more superficial energy level within the patient's body, or extend Qi into the patient's thorax or extremities. This technique allows the patient to relax after experiencing a Heart energy discharge. Since the pulse is simply another form of energy, circulating, expanding, and contracting with each heartbeat, the doctor should be able to ride the pulse out into the patient's extremities and viscera by listening to the Heart. This is similar to the listening ability of a master acupuncturist who, when reading a patient's pulse, extends his or her energy and intention through the patient's channels and into the organ of the Heart to diagnose the strengths and weakness of its congenital formation and current condition.



Figure 13.8. The Sea of Blood flows from the Heart through the body like a dense form of Qi.

SEA OF MARROW (SUI HAI)

This energy flows through the central core of the spine into the brain and enters the center core of the bones. In Traditional Chinese Medicine, the Marrow is not the same thing as bone marrow, but the stage prior to becoming bone marrow. Marrow is the pre-substantial Jing that forms the matrix for bone marrow, the spinal cord, and the brain (Figure 13.9). This flow of Sea of Sui energy is much slower than that of the River of Blood. It flows from the Kidneys' Jing, into the center of the spine, brain, and bone marrow. It has sometimes been called the "cranio-sacral rhythm" in Western medical terminology, and can be accessed from anywhere in the body. The Marrow energy generally feels cool and slick or slippery, with a texture like soft silicone gel. Once contact is made with the Sea Of Sui, it is very easy to utilize this pathway and travel throughout the patient's body. Its rhythm is slow yet manifests as a strong energetic pulse.

As the doctor gently touches the patient's surface tissue by dipping in with fingertips, into the Sea of Marrow, he or she can project intention into the center of the patient's spinal column. This connects the doctor with the rhythmic pulse of the Sea of Marrow. It is from this pulse that the doctor can determine the strength of the patient's Original Essence (Yuan Jing), Energy (Qi), and Spirit (Shen).

THE CENTER CORE OF LIGHT (THE TAIJI POLE)

This energy flows through the very center core of the body, uniting the three reservoirs of life-force energy (the Upper, Middle, and Lower Dantians). The fifth and final level of energy feels like a still, quiet place deep inside of the center core of the body's Taiji Pole structure. In China, Qigong doctors describe it as a holy place that almost defies description. It is observed as a vertical column or pole, of brilliant white light, full of pulsating vibrations. This energetic pole is surrounded by a vale of gold spiralling light which travels from the perineum to the top of the head.

When both the body's internal and external energetic wave patterns become synchronized through prayer or meditation, a resonate pulsation occurs within the Taiji Pole. This pulse begins deep within the center core of the body and resonates outward towards space. The Qigong doctors may also feel a powerful stream of energy leaving the body from the top of the head, connecting the Taiji Pole with the energy of the divine. The center core is a very reverent and special place, as it contains the essence of the patient's Eternal Soul, devoid of all ego, masks, or defense mechanisms (the patient's True Self).



Figure 13.9. The Sea of Marrow flows from the kidneys through the spinal cord, brain, and bone marrow.

If the doctor penetrates the outside veil surrounding the patient's Taiji Pole, and extends his or her intention into the light's center, the doctor experiences the sensation of falling into space, or stretching out into eternity. Sometimes the sensation of shooting through space is followed by flashing colors and moving shapes, as the surrounding core dissolves into the Void (Wuji) itself. This same sensation and experience can also be personally accessed through deep prayer and meditation, and is quite a normal phenomena within deep spiritual practices (Figure 13.10).

SHEN: THE SPIRIT OF LIFE

The Chinese character ideogram for Shen is formed to symbolize "that which drops from the sky," and "that which passes through the body." In Medical Qigong therapy, Shen is considered the subtle energy of the spirit, associated with the Heart. It is associated with the spiritual energy and has a radiant nature.

When energized, Shen flows upward like fire, extending through the body's Eight Extraordinary Vessels creating a healthy nervous system. When Shen is gathered in the Upper Dantian, it can be projected as light and energy through the eyes, and the Yin Tang (Third Eye) point. According to Traditional Chinese Medicine, all illness has spiritual roots. The Shen (Spirit) is regarded as an integral part of the diagnosis and treatment process. An old Chinese saying states, "When the Shen is abundant there will be cheerfulness, when it is insufficient there will only be dullness and sorrow."

Shen is developed from Jing and Qi. According to Medical Qigong theory, when the patient's Shen is strong the individual is able to lead energy to an injured area and speed up the healing process. This strong Shen energizes the Qi, enabling it to increase cellular production. When Shen is scattered, the functions of the human body are weak from fatigue, the Shen becomes unsettled, and the mind restless. When the Shen and Qi combine together they form a solid connection of light and vibrational energy. This union is utilized to infuse energy and transfer thought through intention. This can be achieved by either conscious or unconscious intent by the doctor.

SHENGONG SCHOOLS OF MEDITATIONS AND TRAINING

The Shengong (Spirit Skill) meditations emphasize the transformations of consciousness, as well as the development of perceptual insight and the birth of wisdom. From an ancient Chinese energetic perspective, the three primordial qualities of true wisdom, or divine universal consciousness are:



Figure 13.10. The body's center core Taiji Pole spreads from the base of the perineum to the top of the head.

1. The experience of emptiness within the Wuji (the Void), corresponds to the manifestation of the primal virtue of Wisdom.
2. The light manifested from the Shen's luminosity, corresponds to the primal virtue of Love.
3. The life-force energy inherent in all things, corresponds to the primal virtue of Power.

In China, there are three major schools of Shengong training. These spiritual schools of Qigong are described as follows.

- The Daoist School focuses on strengthening the body and mind equally with an emphasis on contemplating nature. Religious Daoism has its roots in Siberian Shamanism.
- The Buddhist School focuses on tempering the mind while giving little thought to the body.
- The Confucianist School focuses on regulating the mind to reach a state of quiet rest and peace through sincerity and the cultivation of moral character.

PRENATAL AND POSTNATAL SHEN

The body's Shen is the Supreme Yang aspect of the psycho-emotional components, the Heavenly Emperor or "master controller." It can be divided and classified into two primary forms through which the Spirit manifests: the Prenatal Spirit (Yuan Shen) and the Postnatal Spirit (Zhi Shen).

1. Yuan Shen is the body's spiritual element derived from Prenatal Jing (Yuan Jing) and Prenatal Qi (Yuan Qi). This aspect of the body's Shen is considered to be the intuitive Mind of the Dao. It is unborn and undying. It shines brightly and clearly. The Yuan Shen transcends conceptual thinking (which is the Postnatal aspect of the mind). It is immortal, unconditioned, primordial, and constitutes the mind's Yang nature.

   The Yuan Shen is produced and developed by the blending of both the male and female elements at conception (Body Fluids, Jing, Qi and Shen), and develops further with the nourishment from food and water. The Yuan Shen dominates all of the body's vital activities (heartbeat, digestion, motor function, etc.) and is also responsible for all intuitive and perceptive insight. The Prenatal Shen constitutes the true spiritual aspect of the Mind.

   By returning to a state of inner quiet and peace, through prayer, meditation, and adequate sleep, the Yuan Shen and the body's health are restored and maintained.
2. Postnatal Spirit (Zhi Shen) is the spiritual element derived from Postnatal Jing and Postnatal Qi. This aspect of the body's Shen is considered to be the conditioned mind or "will," also known as the discriminating, or acquired mind, and constitutes the mind's Yin nature.

   The Postnatal Shen is produced and developed by mental stimulation through contact with the environment after birth. The Postnatal Shen dominates all mental activity and is responsible for thinking and learned behavior. The Postnatal Shen constitutes the true analytical aspect of the mind.

   Prenatal and Postnatal Shen usually interact intermittently with each other in maintaining the body's health. Continual exhaustion of the Postnatal Shen impairs and suppresses the Prenatal Shen. Excessive studying or sleep depravation, for example, can lead individuals to mistake the projection of their deepest fears and desires for genuine intuitive perceptions.

THE FIVE SPIRITUAL ASPECTS AND YIN ORGAN COMPONENTS OF SHEN

Prenatal Shen affects the spiritual disposition which presides over man at the moment of conception. Closely tied to the Yuan Shen are five important, although seldom discussed outside of China, energies or "spiritual entities" called the Five Agents (see Chapter 2). The function of the Five Agents establishes the foundation for the psychological aspect of the Five Element theory used in clinical diagnosis throughout China today.

Each of these Five Agents is connected to, or said to "reside in" one of the Five Yin Organs. The Three Hun reside in the Liver and embody the virtue of Kindness, the Shen resides in the Heart and embodies the virtue of Order, the Yi resides in the Spleen and embodies the virtue of Trust, the Seven Po reside in the Lungs and embody the virtue of Integrity, and the Zhi resides in the Kidneys and embodies the virtue of Wisdom (Figure 13.11). Whereas each of the Five Agents embodies a virtue, each of the Five Yin Organs embodies the energetic qualities of one of the primordial elements. The Liver embodies the element of Wood, the Heart embodies the element of Fire, the Spleen embodies the element of Earth, the Lungs embody the element of Metal, and the Kidneys embody the element of Water.

Each of these Five Agent energies are connected to the five separate yet functionally interactive Yin organs, and thus create complex, multidimensional energy fields (Figure 13.12). These energy fields encompass emotional, mental, and spiritual shifts, as well as energetic transformations. The fluctuations depend upon which of the Five Agents is dominating from moment to moment. The psycho-spiritual attributes engendered are sometimes known as the Wu Jing Shen (Five Essence Spirits). As the universal energy flows through the Taiji Pole, these Five Agents are continuously being energized. The cultivation of the five virtues of these Five Agents nourishes the Eternal Soul.

The Qigong doctor needs to comprehend these multidimensional interactions to trace the complex spiritual, mental, emotional, and physical manifestations of Excess or Deficient conditions to the source or "root." Although Jing and Qi form the physical basis for the Shen, the Five Elemental Yin organs form the components for the Shen and the Five Essence Spirits. The energy of the Five Agents continually circulates through the patient's body, and are described below.

THE LIVER STORES THE ESSENCE SPIRIT "HUN"

The Liver stores the Three Ethereal Souls, also called the Hun. The Hun or Three Ethereal Souls are rooted in the Liver Yin (which includes the Liver Blood). The Liver organ is responsible for the free and easy flow of Qi throughout the body.

The Hun are typically characterized as the Yang, brighter, Heavenly souls. It is through the influence of the Hun that the five virtues of the Five Agents manifest. The Hun leave the body, ascending back to Heaven at the time of death. The ideogram for the Three Hun has two parts. One part is the character for Earthly spirits-Gui (Ghost), represented by a head suspended above a vaporous form of a body, with an appendage (symbolizing the whirlwind that accompanies the movements of the Earthly spirits). The other part of the character is the image for clouds that are seen as vapor rising from the Earth and gathering in the Heavens. The Hun move within the body as freely as clouds, following the Yi (Will) of the "Heavenly breath, within the celestial vault" (following the will of the Eternal Soul stored within the Heart, and originating in the Taiji Pole).



Figure 13.11. The Five Agents and Yin Organs

From the ideogram we also get a distinct picture of the spirit rising to the Heavens. The Eternal Soul is different from the spirit in the context of classical Chinese theology, in that the soul is seen as the more personal of the two, whereas spirits are seen as more universal temperaments or as archetypes. The ancient medical classics say that there are Three Ethereal Souls (Hun) and Seven Corporeal Souls (Po) that symbolize different attributes of the human being. The Hun's spiritual energy is said to be able to leave the body and then return, thus indicating a relationship with out of body travel into the spirit world.

The Hun and Po are expressions of the body's "true spirit." When disorder exists (physical, mental, emotional, or spiritual), the Hun may sometimes fly away (like startled birds in a yard), and the Po will either stir about thoughtlessly, in the absence of effective control, or become animalistic in nature and attack.


Yuan Shen
Prenatal Shen
from both parents
(dominates all of the body's activities and is responsible for all intuitive and preceptive insights)
Zhi Shen
Postnatal Shen
from the interaction of Jing and Qi
(conditioned or acquired mind, dominates all mental activity and is responsible for thinking)
Shen (Heart) Order
The Five Agents
Yi (Spleen) Trust
Zhi (Kidneys) Wisdom
Hun (Liver) Kindness
Po (Lungs) Integrity

Figure 13.12. Formation of Shen

FUNCTIONS OF THE HUN

1. The Hun control sleep and dreaming. They reside in the eyes during the day and lodge in the Liver at night. When residing in the eyes, they see; when they lodge in the Liver, they dream. Dreams are the roaming of the Three Ethereal Souls. It is the nature the Hun to wander, and it happens easily. At night the Hun must be anchored or rooted in the Liver, so the Liver Blood and Liver Yin must be strong. If they are not, the Hun wanders, and the person dreams too much or has unpleasant dreams. Patients who suffer from severe Deficiency of Yin, may experience a floating sensation just before falling asleep. This condition is due to the Hun not being rooted in the patients' Yin.

   Dreams are an example of the information gathered during the Hun's traveling. The ancient Chinese Qigong masters understood that the body's Hun can traverse the Nine Levels of Heaven or Nine Levels of Earth instantaneously (see Chapter 2).

   The Hun store the sum total of past experiences. The expressions of the Three Ethereal Spirits are manifested through images, symbols and ideas from the divine and Wuji. These images, symbols and ideas emerge into the patient's mind, affecting his or her spiritual life. Without this interaction, the patient's mental and spiritual life would be deficient in images, ideas, and dreams.

   The Hun also controls dreams and daydreaming, as well as the ideals, aims, and direction in life. The absence of these objectives and goals results in feelings of depression. If the body's Liver Yin is depleted, the Hun are deprived of their residence, resulting in such conditions as: fear, excessive day dreaming, insomnia, and a lack of sense of direction or purpose in life (one of the main features of depression).

   Traditionally, sleepwalking is believed to be a function of the Hun. In sleepwalking, the body's Shen is not active and functioning, however the Hun are moving the individual. This is why when treating a patient for sleepwalking, the doctor will emit Qi into the patient's Hunmen Bl-47 (The Door of the Ethereal Soul). In modern research, however, some Qigong doctors have begun to theorize that the Po may take an active role in sleep walking, especially when the sleep state is related to incoherent trauma (patients who thrash about, hurt people, or destroy things when sleeping).

When using hypnosis or "creative visualization" in psychotherapy (the therapist may suggest a specific image or scene for the patient), the therapist is trying to bypass the patient's acquired mind and bring psychic material from the Hun, to avoid the judging aspect of the Postnatal Shen.

With regard to sleep and herbal medicine, if the patient does not sleep well because the Hun are wandering, the Qigong doctor can prescribe sour and astringing herbs (i.e., Bai Shao, Mu Li, Suanzao Ren) which will encourage the Hun back into the body.

2. The Hun assist the Shen in mental activities. This relationship is very important, as the energy of the Shen and the Hun must continually be coordinated. The Shen is related to rational thinking and inspiration. The Hun gives the Shen a sense of direction, projecting outwards, relating to other people. The Shen needs to direct the Hun, to "gather the Hun." The Hun give the Shen its movement and direction, encouraging the Shen to relate with people, to socialize and bond. The Hun, however, also need to be gathered and restrained by the Shen. Otherwise if the Shen is weak and does not control the Hun, then the Hun move about too much and have lots of ideas, but never accomplish anything, leading to frustration.

It is important that the Shen allow the Hun to move in and out of the body, but in so doing must give the Hun direction and purpose. The Hun inspire and give us dreams. That is why the words "movement," "coming and going," and "swimming" are often used in connection with the Hun. In fact, many doctors say that the Hun are the coming and going of the body's Shen. In mediumistic trances, when the spirit of one person enters another's body, it is the Hun that come in; the host's Shen is disabled at that time.

Because knowledge is dependent on the awareness of the Three Ethereal Souls, the Hun are therefore considered the collectors of information. The Hun however, do not interpret, rationalize or analyze the knowledge, they just pass the information on to the Shen, which is responsible for rational thinking, intuition, and inspiration. The Shen helps distinguish between the useful and non-relevant information.

There is an interesting correlation with the Hun controlling sleep and dreaming, and the Hun being rooted in the Liver Blood and Yin. The Hun's moving in and out of the Liver governs the free flow of Liver Qi and vice-versa; the free flow of Liver Qi is a manifestation of the swimming energy of the Hun, moving in and out of the tissues.

3. The Hun maintain balance in one's emotional life, under the leadership of the Shen.

Everyone experiences emotions in life; that is normal. The Hun are responsible for keeping a balance, so that the emotions do not become excessive and thus become the cause of disease. The Hun have a regulatory function, closely related to the balance between Liver Blood (Yin), and Liver Qi (Yang). The Hun's function here is the mental equivalent of the Liver's emotional regulating and harmonizing function.

Due to its acquired nature, the Postnatal Shen discriminates, while the Hun does not. The relationship between the Shen and the Hun is very similar to concepts of consciousness and unconsciousness in Jungian terms. The Hun are a repository of images and archetypes, connecting the (personal) subconscious mind and the collective unconscious. If the Hun are unsettled, then the Shen (consciousness) is cut off, confused, isolated, aimless, sterile, and without dreams. The movement of ideas within the body has to be controlled or it gets out of hand, resulting in madness. This madness occurs to the degree that the Shen doesn't control the Hun anymore, and the patient receives an uncontrolled amount of emotional, mental, and spiritual input. All the energies and symbols coming through the Hun have to be integrated and assimilated. Otherwise there can be serious mental illness and possibly psychosis (except in young children who are continually full of ideas and have active imaginations). In a child, the Hun are very active and the Shen is not as restraining, so there is a continual flow of energies streaming from the unconscious world of symbols, without the result of insanity.

4. The Hun are responsible for the eyes. When the Hun wander in through the eyes, the eyes can see. The Hun give us vision, both mentally and spiritually.
5. The Hun influence a person's courage. If the Hun are not strong, the person is timid and fearful. If the Hun are strong, the person is fearless, can face up to the difficulties in life and dares to take action. A patient with weak Hun will have difficulty gathering information, making decisions, will lack courage, and become easily discouraged and apathetic.
6. The Hun control planning with the aid of the Shen and the sense of direction. The mental and spiritual confusion about one's role in life, what to do, what goals to set, can be compared to the aimless wandering of the Hun. This is a strong feature of major depression. If the Liver is strong and the Hun are strong and rooted, the person has a strong sense of direction.
7. The Hun control Spirit Travel. By housing the Shen for "spirit travel" (the spirit journeying outside of the physical body), it is possible for the Qigong doctor to consciously direct the Hun's travelling. This is different than Astral Travel, which is the Eternal Soul journeying outside of the physical body, connected to the Middle Dantian by a silver "cord of life." The Three Ethereal Souls, accompanied by the individual's consciousness, act as one unit which is sometimes referred to as the Spirit-Soul. The Spirit-Soul allows the doctor to know the exact location of the "spirit routes" travelled, as well as which path and direction it takes when it leaves the body. Otherwise, when the Hun wonder, the doctor "Shens out" and has no recollection of where he or she has been in the spiritual realms.


Liver (Hun)
Dreams and Unconscious Information
Spleen (Yi)
Thoughts and Ideas
Heart (Shen)
Mental, Emotional Activity and Intellectual Consciousness

Figure 13.13. Two Ways to Feed the Shen

THE HEART STORES THE ESSENCE SPIRIT "SHEN"

The Heart stores the Shen and is responsible for mental and emotional activity, intelligent consciousness, long term memory, and sleep. It is responsible for organizing mental concepts and activities, and has the capacity to judge.

The Shen is divided into two kinds of energies, Prenatal Shen and Postnatal Shen.

The Prenatal Yuan Shen is associated with the congenital spiritual energy that descends from Heaven. It is the universal divine spirit that is implanted in each person, uniting man to the spiritual realm (that which exists beyond the physical and mental reality). It has been compared to the "Christ within us," or "higher self." This is the energy Qigong doctors attempt to become filled with during sitting meditation practice and prayer.

The Postnatal or Acquired Shen is associated with the wisdom of the five senses and the acquired knowledge of the individual's experiences.

There are two ways to "feed" the Shen. One way is through dreams or unconscious information coming from the Hun of the Liver; the other way is through thoughts and ideas from the Yi of the Spleen (Figure 13.13). A person who has a well-developed, strong, and abundant Shen comprehends things immediately and is able to apply what he or she has learned.

The Hun give the Shen movement allowing the



***Fig. 6.2** Through Compassion Fire,*
we transmit Positive Energy to Our Surroundings.


Summer - Fire - Heart
Love, Joy, Happiness
Indian Summer
- Earth - Spleen
Openess,
Fairness
Autumn -
Metal - Lungs
Courage,
Righteousness
Winter - Water -
Kidneys
Gentleness,Stillness
Spring -
Wood - Liver
Kindness,
Generosity

***Fig. 6.3** Creation Cycle in Nature*

mind the capacity of self insight and introspection, as well as the ability to project outwards from the body and envelop, as well as relate to, other people.

THE SPLEEN STORES THE ESSENCE SPIRIT "YI"

The Chinese term Yi, is typically translated as mind, thought, opinion, idea, sentiment, inclination, intention, intellect, scholar mind, analytical thinking, and memorization in scholastic learning. Because the Spleen stores the Yi, it is responsible for the transformation and transportation of all thoughts and ideas on an intellectual level, through study, concentration, and memorization. This is different from the Hun's creativity. It is the interaction between the Yi of the Spleen and the Shen of the Heart that allows man to place how he thinks, speaks, and acts into sounds, thoughts, and actions.

Concerning memory, there is a lot of overlap between the functions of the Spleen (responsible for memory in terms of concentration and studying), the Kidneys (responsible for storing things on a day to day basis), and the Heart (responsible for storing past events).

The Postnatal Qi and Blood form the physiological basis for the intellect. A person with well-developed Yi has total recall of events experienced in their personal past, and is able to memorize things easily. A patient with an Excess of Yi will be obsessed with the past, while a patient with Deficient Yi will be absentminded, suffer memory loss, be inattentive, and have problems in maintaining concentration and mental focus. Although all physical pain is registered by the Po, and all psychological pain is registered by the Hun, only the memory of the pain is registered by the Yi (Figure 13.14). Therefore, a Deficient Yi condition can often lead to the phenomenon of transference and countertransference. Transference involves the incorrect attribution of certain emotions and intentions onto another person (usually onto the doctor by a patient). Countertransference involves the same type of projection of one's feelings, colored by one's own expectations in response. In countertransference, the doctor or therapist is doing the projecting.



Figure 13.14. Three Ways the Body Registers Pain

Yi also has the meaning of divine purpose when applied to the Yuan Shen energy. Whenever the physical energy is purified by self-cultivation and through connecting to the divine, the intention of the Shen and the divine purpose become one and the same. It is said when the Yi is conserved, it will help build the Zhi (or willpower). The Yi is filled with information from the past along with current knowledge and sensations.

THE LUNGS STORE THE ESSENCE SPIRIT "PO"

The Lungs store the Seven Corporeal Souls (Po), which are physical in nature and are attached to the body's Jing and Qi. The word Po is defined as vigor, animation, or life. There are two parts to the Po ideogram; one is the character for Gui, the spirits of the Earth, and the other represents the color white. Thus, the Po are linked with a descending movement of energy and with the Jing. The Seven Corporeal Souls are also said "to come and go, enter and exit," in association with the body's Essences.

In Medical Qigong therapy, the body's Eternal Soul is seen as being strongly influenced by two main divisions of internal spiritual energies, the Hun and the Po. The Hun are the Three Ethereal Souls and represent the positively charged aspects of the Eternal Soul, while the Po are the Seven Corporeal Souls and are considered the physical, negative, Yin, heavy, and Earthly aspects of the Eternal Soul. The Po are the counterpart of the Hun and can be described by its following six manifestations.

1. The Po are the somatic expressions of the Eternal Soul, related to the reflexive nervous system and limbic system (the "reptilian brain"). They manifest through the body's sensations of feeling, hearing, and seeing. They have an impulsive tendency towards action and correspond to the deep animal instincts within the Mind (personal subconscious) and cells (our reflexes are a Po reaction). The Po also provide us with the animal strength and resources necessary to mobilize the body and perform incredible feats of power. The "animal within" is driven by the Po. They are the manifestation of the body's Jing in the sphere of sensations and feelings. Just as the Three Hun provide the individual with the energetic movement for the Shen, the Po provides the individual with the energetic movement of the body's Jing.
2. The Po are responsible for all physiological processes in childhood. In the beginning of life, the Po are responsible for the sensations of pain and itching. The Po serve as the intermediary between the Jing and the body's other vital substances. At conception the interaction of the body's Jing not only forms the embryo, but also establishes the Po within the body. Although the Po are stored in the Lungs, they stay attached to the body until death, there upon returning their energy back to the Earth within a few days.
3. The Po are related to weeping and crying. The interconnection between the Po and Lungs is very important from an emotional point of view. When the Po's movement in the Lungs is constricted, grief and sadness are suppressed in the chest through shallow breathing.

   In the morning time, when waking, if the patient feels dull and depressed, it is a sign that his or her Shen is clinging to the body, i.e., the patient's Shen is clinging to the excessive energy of the Po.
4. The Po are closely linked to breathing. Because the Po reside in the Lungs, all meditation systems, breathing exercises, and forms of breath control are methods used to regulate the Po, calm the Shen, and access the higher Hun states. Breathing is the pulsation of the Po. Each emotional change the body experiences is related to a shift in the body's respiration rhythm. Because breath control relies on the Lungs which influence the sympathetic and parasympathetic nervous systems, the quality of Qi and its circulation are dependent upon the method, speed, and quality of the breath. To support the greatest longevity possible, it is important to breathe with a long, slow, and even quality to the breath. The breath (air from Heaven) interacting with the Po in the Lungs, plays a significant role in the Heaven-Man-Earth concept for balancing the emotions.

   The Lungs' virtues are righteousness and courage. These virtues give a person the drive and strength to do the "right thing" when the need arises. These virtues manifest and promote good health when a correct energetic and balanced alignment with the Po is achieved (between the Lungs breathing pattern and the Po).
5. The Po are connected to sexuality on the sensation level. All instinctive sexual reactions and passions come under the authority of the Po. In human life, the Po are linked to the basic instincts and perceptions of the body. The Po provide the fundamental biological energy, and are the source of biological needs and impulses. They are driven by basic instincts and urges, and their sole concern is the immediate gratification of biological needs and impulses (emotional and physical survival, reproductive urges, etc.). Most self destructive behavior, such as an attraction to unhealthy and dangerous life-styles, is due to the Po.
6. Because of the Corporeal Souls' relationship with the Lungs and Large Intestine, the anus is considered the "Po Men" or "the door of the Po." It acts as a doorway for the elimination of the waste products for the Five Yin Organs, through draining off impure liquids and waste.

THE KIDNEYS STORE THE ESSENCE SPIRIT "ZHI"

The Chinese term Zhi (translated as "will") is the prenatal spiritual entity associated with the Kidneys, and is not the personal will of the ego that is driven by our desires. The term Zhi has two meanings. It means memory, but it also means willpower. Both are primary features of the Zhi. The word Zhi can also be used to mean the Mind (whole body consciousness and awareness). In connection with the five mental aspects of the Mind, the Three Ethereal Souls, Seven Corporeal Souls, the Shen, the "intellect," and the "willpower" are sometimes referred to as the Five Zhi.

MEMORY

Memory is defined as the ability to remember information when studying or learning a particular subject or pattern. The Kidneys keep a determined focus on our goals, not forgetting where we are going and what we are working to achieve; they maintain a vital mindfulness. The Kidneys relate to short term memory, whereas, the Heart governs the body's long term memory (Figure 13.15). This is why elderly patients, whose Kidneys are declining, often cannot remember what day or year it is, but can remember events long past.

WILLPOWER

This is the most important aspect of the Zhi, because it is responsible for supplying the mental drive, willpower, determination, and single minded pursuit of goals and aspirations. It enables the realization of ambitions by providing the focussed energy necessary to carry ideas to fruition. A powerful Zhi creates the magnetism and charisma necessary to manifest and materialize our dreams.

Even though a person has acquired all the information available via the Hun, Po, and Yi, without the Zhi there can be no action. Although the Hun give us the goal (thinks of something), the Zhi is needed to accomplish it (decides and acts on it). A person with well-developed Zhi demonstrates perseverance, determination, and a tenacity to complete personal goals. Patients with Deficient Zhi become indecisive and fearful. Patients with Excess Zhi have a blind obedience to authority, or tend to be fanatics.



Figure 13.15. Three Ways the Body Stores Memory

The goal of the Qigong doctor is to reach such a level of attainment that his or her personal will merges with Heaven's will (Tian Zhi) becoming one and the same. Tian Zhi is considered the movement of the divine expressed in man as his personal virtue (De).

A man's virtue is defined as his spiritual righteousness, the authenticity of his heart and actions. It is through the acquisition of virtue that man finds and possesses his true nature. If man's virtue is initiated into the "mysterious" (embracing Heaven's will), his intuitive evolution will give way to limitless perception.

Tian Zhi is a divine inner prompting that guides us on our spiritual quest, if we are open to its message. Tian Zhi is what we can call the divine will and carries within it man's purpose in life.

THE FIVE YIN ORGAN CULTIVATION OF SHEN

The Shen indicates the vitality level, and the state of physical, mental, emotional, energetic, and spiritual being. A flourishing vitality is a manifestation of the Jing, Qi, and Blood inherent within the Five Yin Organs. These five components of the Shen are expressed through psychological manifestations (Figure 13.16). They form the bases of the patient's emotional characteristics. Each of the emotional components of the Five Yin Organs contribute to the patient's spiritual manifestation; adding or detracting from the natural harmony of the patient's spiritual nature.

The activity of conscious thinking, insight, and intelligence are the foundational aspects of the body's Shen, activated by the patient's Heart (wherein the Shen resides). The Heart is also responsible for the long term memory of the body's sensory memories (the perceptions, feelings and sensations related to hearing, seeing, smelling, tasting, and touching) and sleep. These sensory activities carry over from the other internal organs, due to their relationship with the Five Yin Organs. Emotional disturbances that affect the Heart can cause energetic changes in the patient's body, influencing health, toward recovery from diseases or illness by impeding or facilitating bodily functions (see Healing the Patient's Emotional Pain, Chapter 31).

When cultivating the Shen, it is important for the Qigong doctor to keep in mind that the spirit is indivisible from matter, and that an individual's emotional and spiritual well-being and development depend upon the healthy functions of the internal organs. When the Shen leaves the body (through shock, trauma, stress, depression, guilt, shame etc.), the Qigong doctor can observe a diminishment of glow in the patient's complexion, lack of luster in the eyes, along with changes in the respiration rate and state of mind.

Once the patient's Shen is disturbed, the Qi is affected. This in turn leads to the body's Jing becoming weakened. Patients with this condition are generally taught Medical Qigong exercises and prescriptions to not only tonify and strengthen their body's internal organs to improve their immune system, but also to improve the overall condition of their emotional/spiritual state. Even a low vitality of spirit can cause emotional disturbances that can scatter or stagnate the body's Qi.



Figure 13.16. The body's Shen is physically housed in the Five Yin Organs. Each Yin organ houses a particular psycho-spiritual and energetic aspect of the human being. For example: The pulse is stored in the Heart, which is the residence of the Shen (Spirit), and placed in the front of the body, the Blood is stored in the Liver, which is the residence of the Hun (Three Ethereal Souls), and placed on the left side of the body, the Jing is stored in the Kidneys, which is the residence of the Zhi (Willpower), and placed on the back, and the Qi is stored in the Lungs, which is the residence of the Po (Seven Corporeal Souls) and placed on the right side of the body.

The Yi (Intention) resides in the Spleen and is placed in the center of the body, governing the Qi of the four aspects of spiritual manifestation, distributing them along the body's Taiji Pole. When Jing and Blood combine Shen is born. The Hun follow the Blood along in all its movements. The Po follow the Jing along in all its movements. The state of Qi and Blood of each organ can influence the Mind and the Spirit, any alteration of the Mind or Spirit affects one or more of the internal organs.

Advanced cultivation methods utilize the energy of the Five Yin Organs, flowing to and from the body's Taiji Pole. It is from the Thrusting Channels along side the Taiji Pole that the energy of the Shen is dispersed into the body's Yin and Yang Organs and then into the extremities (Figure 13.17 - 13.18).

SHENGONG CULTIVATION METHODS

The key to enhancing the Qigong doctor's development of energy, is through learning how to control the vast amount of Qi within the body, without compulsively "Shening out" (allowing the spirit to leave because the body feels uncomfortable). To avoid disconnecting from the body, the Qigong doctor practices several specific training methods of Shengong cultivation. When focusing on Shengong cultivation and regulation, there are four traditional disciplines the doctor must adhere to: Nourishing and Strengthening the Shen, Housing the Shen, Combining the Shen with Respiration, and Combining the Shen with Qi (Figure 13.19).

NOURISH AND STRENGTHEN THE SHEN

The Qi is able to nourish and strengthen the Shen through proper Qigong regulation. This is brought about through a form of coherent light meditation, that focuses the doctor's Shen on a small circle of light (generally about the size of a marble or pearl). The doctor's focus of concentration can extend either externally onto a specific point outside the body, or internally on a specific point inside the body (e.g., the Upper Dantian). Through this focused "coherent light" (light with wave patterns that are all in step or in phase), it is possible to build the Shen's strength and refine its power. Through focused intention on a specific area, the Qi and Shen condenses together forming a more powerful type of energetic projection.

HOUSING THE SHEN

By disciplining (i.e., quieting) both the emotions and thoughts the Shen becomes relaxed and tranquil, and remains in its residence (the Heart). The Shen must not be allowed to become attracted to outside emotional disturbances. The goal is to allow the Shen to be energized but not excited.



Figure 13.17. The Five Thrusting Channels as seen from the top of the head. Located within the Five Thrusting Channels are the "Five Portals of the Heavenly Gate." These gates include four entry points which surround the Baihui (One Hundred Meetings) point. These four points are known as the Sishencong or "Four Spirit Hearings" and are the access points for the upper spiritual matrix surrounding the body's Taiji Pole, and connect the Five Thrusting Channels of the upper gates with the Five portals of the Earthly Gates.



Figure 13.18. The Five Thrusting Channels as seen from the perineum. Located on base of the Five Thrusting Channels are the "Five Portals of the Earthly Gate." The Fire point is at the location of the Huiyin point on the Conception Vessel (CV-1), the Water point is at the location of the Changqiang point on the Governing Vessel (GV-1), the Wood and Metal points are located just below the ischial tuberosity, lateral to the anal sphincter. These points are known as the access points for the lower spiritual matrix surrounding the body's Taiji Pole.

COMBINING THE SHEN WITH THE RESPIRATION

Once the Shen has been nourished, strengthened, and housed, it is then connected with the doctor's breath. Once the Shen is combined with the respiration, maximum healing results can be obtained by releasing Healing Sounds and Qi projection simultaneously.

COMBINING THE SHEN WITH THE QI

The final stage is for the doctor to be able to direct the Shen in coordination with the life-force energy being emitted into the patient. Since Shen projects as light and Qi projects as vapor, this combination of Spirit and Energy projection is very powerful, especially when combined with healing colors and sounds.


HOUSING THE SHEN #2
NOURISH AND STRENGTHEN THE SHEN #1
Shen
COMBINING THE SHEN WITH RESPIRATION #3
COMBINING THE SHEN WITH QI #4

Figure 13.19. Four Ways to Cultivate the Shen

THE SIX TRANSPORTATION'S OF SHEN

The psychic abilities developed in Medical Qigong training result from a well-developed intuitive faculty, brought about through Shengong meditations. Through these meditations the Yuan Shen can transcend the space-time continuum, as both space and time are multidirectional and interconnected.

Shengong meditations cause altered states of consciousness that differ substantially in subjective and objective observation from the general norms for that individual. As the Qigong doctor dissolves his or her Shen into the Wuji, the subconscious will be able to see forward and backward in time, unhampered by distance.

The conscious mind acts as a filter, seeking to analyze every perception, and attempts to identify and categorize each perception. Once the conscious mind is engaged, the flow of perception usually stops because the perceptions arising from the subconscious are usually vague (often with multiple messages). Qigong doctors must train themselves to first root (ground / stabilize) the acquired mind, in order for their perceptions to come through in a pure form, void of thoughts and judgments.

The ancient Qigong masters explained the ability to access the manifestations of Shen as follows: "by rooting the acquired mind (Zhi Shen), the Heart (Yuan Shen) opens up to 10,000 voices (Wuji)." Meaning that, when the "chattering mind" is anchored into the Earth through focused intention, the Heart is able to perceive the spiritual realm (the 10,000 voices), or be aware of its connectedness to the multidirectional space-time continuum.

Extraordinary abilities that develop from the cultivated spiritual consciousness include: telepathy, clairvoyance, clairaudience, precognition, time travel into the past, levitation, and teleportation.

The Qigong doctor experiences different psychological adjustments when opening to the deep spiritual transitions of Shengong meditations. The adjustments the doctor will experience include:

1. Time distortion,
2. Deep mystical states of perception and intuition,
3. Deeper and more powerful levels of self healing,
4. A more spontaneous reaction to movement and sound, and
5. Difficulty communicating verbally.

CULTIVATING THE SPIRITUAL CONSCIOUSNESS TO OBTAIN THE SIX TRANSPORTATION'S OF SHEN

In Shengong meditations, it is through the use of imagery and creative visualization that the doctor's altered states are developed, and a connection is forged with the Yuan Shen and Eternal Soul.

After the doctor's Shen has entered into a quiescent state, his or her altered state of spiritual conscious can be initiated through choosing one of the following five images.

1. The doctor is instructed to go inward into the center of the Taiji Pole to connect with his or her Yuan Shen and Eternal Soul.
2. The doctor is instructed to go into an imaginary temple or sacred place located within the astral plane to connect with his or her Yuan Shen and Eternal Soul.
3. The doctor is instructed to float upwards into the Heavens to connect with the eternal source of his or her Yuan Shen and Eternal Soul.
4. The doctor is instructed to ascend out of the body (after reliving the death of a past life experience) and receive the knowledge learned from that experience collected from by the Yuan Shen and Eternal Soul.
5. The doctor is instructed to allow the Yuan Shen to directly connect with the Eternal Soul and transmit information.

The Higher Self and Eternal Soul are usually considered as the same thing, and are often regarded as the "Master Within." In Jungian psychology, the collective unconscious (Wuji) is accessed through the subconscious mind (Shen) in the form of dreams or directly through "visions." The personal subconscious (Shen) has several elements:

- the anima, which is the wise man (influenced by the Hun)-for males, or
- the animus, which is the wise woman (influenced by the Hun)-for females, plus
- the shadow, which is the individual's dark side (influenced by the Po).

Once the Qigong doctor has cultivated the Shen into a high level of effective energy (absorbing and projecting energy from the universal, as well as the immediate environment), the result is a gradual unveiling of six supernatural diagnostic powers known as the Six Transportations of Shen.

These six metaphysical abilities not only enable the Qigong doctor to accurately evaluate a patient's state, but also to predict the probable future progressions of the patient's life as well as of his or her disease. The Six Transportations of Shen are: Observing the Present, Comprehending the Past and Observing the Future, Knowing a Person's Thoughts, Perceiving a Person's Destiny, Hearing the Sounds of the Universe, and Examining the Universe (Figure 13.20).

OBSERVING THE PRESENT

The Qigong doctor must first quiet the Zhi Shen's (acquired mind) analytical chattering by housing its energy within the Five Yin Organs. As the Mind becomes rooted, the doctor's breathing slows and the Lung Qi harmonizes with the Heart Qi. Once the Seven Po are quieted in their residence and the Zhi Shen is rooted, the Yuan Shen's messages can come through clearly without interference. The Yuan Shen is always connected to the Wuji where all knowledge is stored. The Yuan Shen is always at the "center of time" where it can gather and absorb the patient's past and present experiences, emotional reactions and thought patterns. It is from the Qigong doctor's intention and focus to be at the "center of time" that he or she can observe the present state of "now."

Observing the past is the ability to analyze and accurately discern the actual state of present situations (the here and now). By keeping away from conscious intervention, the Yuan Shen is free to truly listen and perceive as an "observer." The doctor's ego is not engaged and his or her mind's subconscious observer receives and reviews the patient without bias.

This enables the doctor to thoroughly analyze and comprehend events and situations clearly and unambiguously. It is through this state of perception that the Qigong doctor can accurately discern the true emotional problems which disturb his or her patient's energetic balance.

COMPREHENDING THE PAST AND OBSERVING THE FUTURE

Comprehending the past and observing the future is the ability to analyze and understand the thought patterns of the patient, the reasons these patterns take place, and to accurately predict the outcome of future events based upon those pat-


The Six Transportations of Shen
Observing the Present
Comprehending the Past and Observing the Future
Knowing a Person's Thoughts
Perceiving a Person's Destiny
Hearing the Sounds of the Universe
Examining the Universe

Figure 13.20. The Six Transportations of Shen

terns. By observing the patient from the active state of being in the "present," the Qigong doctor is free to travel within the infinite space (Wuji) enveloped within the patient's tissues. The doctor's Yuan Shen has no need to astral travel to obtain this information. The doctor's energetic connection to the patient's energy body gives him or her direct access to the personal information needed. It is from this internal space that the Qigong doctor can begin to access the memories existing within the patient's body (stored within the cells of the tissues).

At the subatomic level, the body and its cells contain a great deal more energetic space than matter. The doctor can directly access the internal Wuji enveloped within the patient's tissues and cells to retrieve the patient's past memories and emotions. Through tracing the patient's emotional, mental and spiritual development a greater understanding of the patient's present condition is achieved. After the doctor's Yuan Shen has gathered this information, it can be further analyzed by the doctor's Zhi Shen, and organized to accurately determine the cause and effects on the patient's present state.

Through understanding past patterns of thought and emotional reactions, the doctor can then predict future patterns of change and transition. These predictions are quite accurate, since people are prone to repeat programmed patterns indefinitely, unless there is an internal spiritual transition that frees them from this subconscious patterning.

Knowing a Person's Thoughts

This is the ability to sense the thoughts, judgments, fears, and emotions of another person, knowing their innermost fears and subconscious thoughts. The subconscious mind of the doctor communicates with the subconscious mind of the patient. This is a nonverbal, telepathic communication. It is therefore important for the doctor to monitor his or her thoughts and feelings, as they are automatically being projected into the subconscious mind of the patient. After the treatment is over the doctor may discuss with the patient any important information received that would be helpful to the patient.

Perceiving a Person's Destiny

This is the ability to predict future events and upcoming transitions in an individual's life based on the doctor's understanding of the patient's past energetic patterns. Through the Yuan Shen's ability to perceive the past and present, the doctor is able to understand the patient's mind, thoughts, acquired characteristics and personality. Above all, however, the doctor is able to perceive the individual's true nature that exists behind all of the patient's external masks. The doctor's Zhi Shen (postnatal mind) is then able to analyze and categorize the individual's patterns. Through deductive thinking, the doctor is able then to perceive the probable outcome and development of these repetitive patterns. This enables the doctor to help the patient to identify the patterns that require restructuring and give added encouragement and advice, when needed.

This spiritual counsel or guidance is extremely important for healing transitions since old patterns established in the three energy matrixes (Jing, Qi, and Shen) must be changed together to achieve a more permanent healing. Otherwise, the illness is likely to reappear. The spiritual matrix sets the foundation for the energetic matrix, which in turn sets the foundation for the physical matrix.

HEARING THE SOUNDS OF THE UNIVERSE

This is the ability to hear sounds, music, and voices not audible to the normal hearing. This is not to be confused with schizophrenia -- a mental illness that causes a person to hear voices; the difference is that the schizophrenic cannot think clearly, the mind is very confused and unordered.

The ability to hear the sounds of the universe is also the ability to be aware of, and receive, divine inspiration or messages (clairaudience). These abilities allow the doctor to affect the lives of those they know or soon will know. The doctor's own inner-voice can guide, instruct, teach, and lead the doctor to ever higher states of enlightenment.

Through inner hearing, the Qigong doctor is able to listen to, as well as understand, the resonant sounds generated by life-force energy and spiritual entities. This enables the doctor to tap into an unlimited source of divine knowledge and wisdom, which in turn allows the doctor to be present for the patient's highest good.

EXAMINING THE UNIVERSE

This is the ability to actually perceive current objects, events, or people that may not be discerned through the normal senses. It is the ability to perceive both time and space on a spiritual dimension (clairvoyance), to understand and acknowledge one's part, and to accept one's divine calling in life. It is also the ability to understand how one's spiritual calling affects both the cosmos and mankind. Through inner-vision the Qigong doctor is able to see inner-visions of divine enlightenment, observe and exchange information with celestial beings, and find holy places for spiritual sanctuary.

The metaphysical abilities of the Six Transportations of Shen are spiritual manifestations from the Eternal Soul. Once the Qigong doctor regulates his or her spiritual life, these abilities become a natural course of experience, giving way to the development of eight supernatural powers. A chart describing the interaction of the body's Eternal Soul with the energetic functions of the Three Dantians and Five Yin Organs' Wu Jing Shen (Five Essence Spirits) is depicted in Figure 13.21.

THE EIGHT SUPERNATURAL POWERS

Once an individual has obtained the Six Transportations of Shen, his or her psychic abilities develope into eight supernatural powers. These powers can be utilized in the individual's personal spiritual practice. Through these eight supernatural powers the doctor's Yuan Shen can allow him or her the ability to transcend all physical boundaries and invoke certain spiritual manifestations. The eight supernatural powers are described as follows.

1. The ability to make the one's physical body light.
2. The ability to make the one's physical body heavy.
3. The ability to reduce one's energetic body to the size of an energetic particle. This allows an individual the ability to astral travel into the subtle energetic and spiritual realms of existence.
4. The ability to expand one's energetic body to an infinite size. This allows an individual the ability to connect to, through, or envelop objects, as well as energetically protect people, places and things.
5. The ability to call into existence and attain one's specific needs or desires. Due to the individual's strong connection to the divine,


Chamber of Light (Upper Dantian) Tai Yi (Great Divinity
Astral Travel
Resides in the Upper Dantian
Tai Guan -Hun (Eminent Light)
Yu Jing - Hun (Hidden Essence)
Taiji Pole
Heat
Vibration
Light
Vibration
Heat
Intuitive Communication
Cord Attached to the Astral Soul
Resides in the Middle Dantian
Shang Ling - Hun (Pleasant Soul) Five Agents
Leaves Body through Dreams
Liver
Hun
Kidneys
Zhi
Spleen
Yi
Lungs
Po
Heart
Shen
Wu Jing Shen
Five Yin Organs
Chamber of Vibration (Middle Dantian) Si Ming (Administrator of Destiny)
Cord Attached to Soul
Empathic Communication
Eternal Soul Rooted Behind the Heart
Core Self (Eternal Soul) True Self
Taiji Pole
Heat
Vibration
Light
Vibration
Heat
Kinetic Communication
Six Transportations of Shen
Intuitive Wisdom of the Eternal Soul
Prenatal Spirit (Yuan Shen)
Postnatal Spirit (Zhi Shen)
Soul Extensions (Personality Characteristics)
Eight Supernatural Powers
Acquired Wisdom of the Five Senses
Chamber of Heat (Lower Dantian) Xia Tao Kang (Below Healthy Peach)
Resides in the Lower Dantian
Bottom of Feet (Kd-1)

Figure 13.21. The Body's Intricate Interactions of the Eternal Soul

Creating compassion energy begins with the creation cycle.

Activate the heart first. It is the fire and the place where the virtue energy can be combined into compassion energy. Go to the kidneys and bring the energy to the collection sphere. Continue with the liver, the heart again, the spleen, the lungs and bring the energy to the respective collection points.



Fig. 6.4 *Creation Cycle*

In the human body the arousal state creates a new chemistry and a new vibration. This 'special' vibration is measured at a frequency of 8Hz/Sec. 'As in the macrocosm, so it is in the microcosm'; hence if we make love, then all cells and the DNA actually make love as well.

The DNA cross over, like two serpents intertwining in an erotic embrace. They make love and they give birth. Any of the cells that do not 'reproduce' will eventually die.



Fig. 6.5 *When we feel love and arousal energy,
the DNA crosses over and makes love.*

The two vital states are arousal, leading to orgasm and compassion are inextricably linked to love. When this 'love-vibration' reaches the pineal gland, a new hormone is produced. This in turn creates whole body conductivity. If the vibration is above or below the 8Hz/Sec. frequency, this process does not occur. Only when you feel the waves of orgasmic vibration and unconditional love for the self and others can the process be activated.

he or she may manifest through faith that which is desired.

6. The ability to experience and enjoy one's desires fulfilled.
7. The ability to gain authority over one's situations. First and foremost, the individual will obtain the spiritual authority over a specific situation, then the authority over the emotional, mental and physical realms follow.
8. The power to attract and control things. This allows an individual the ability to engender help and security (in the form of outside council, finances, and spiritual and emotional support) in order to exercise power over specific situations.

SOUL PROJECTION, SPIRIT PROJECTION AND ENERGY PROJECTION

The phenomena of Soul Projection, Spirit Projection and Energy Projection is known and accepted as a natural part of existence in almost every culture in the world. The holy men and women, shamans, and energy healers of many primitive societies were required to prove their powers by exercising these spiritual and energetic abilities.

Tibetan Buddhism (influenced by the energetic practices of Indian cosmology) contains elaborate doctrines about Soul Projection (also known as Astral Projection), Energy Projection, the Astral Body, and also describe the feats individuals can perform while out of their physical bodies. Some of these doctrines are quite similar to the traditional Daoist teachings which are evident in advanced Daoist Shengong training.

All Chinese systems used for inducing Shen and Qi projections use visualization, concentration, willpower and the individual's innate skill. The three types of external projections are: Soul Projection, Spirit Projection, and Energy Projection.

- Soul Projection occurs when the body's Eternal Soul is externally projected out of the body, while still attached to the Middle Dantian through a Silver Cord;
- Spirit Projection occurs when the body's Shen is externally projected outside of the body as an energetic vehicle of light;
- Energy Projection occurs when the body's Qi is externally projected out of the body like an energetic vapor (Figure 13.22).

In Soul Projection, Spirit Projection and Energy Projection, the effects of time are not acknowledged outside of the physical realm. Within the Astral Plane, time is omnipresent, there is no past or future, only the individual's perception of it.

The body has an established relationship to both the physical and spiritual world. The physical world of the living is considered a Yang state of existence, while the supernatural-spiritual world is in a Yin state of existence (see Chapter 19). As the Qigong doctor's Shen reaches a high state of sensitivity, he or she can transcend the ordinary senses and normal conscious perceptions. These abilities enable the doctor to observe, communicate and even travel within the "higher" and "lower" spiritual Yin world. There are nine energetic levels of Heaven (i.e., the higher astral planes), and nine energetic levels within the Earthly spiritual realm (or lower astral plane).

It is important to note that the term "higher" and "lower" astral realm has nothing to do with the actual space, but with the energetic and spiritual vibrational levels. The higher and lower astral planes overlap and exist within the same space as the physical plane. This blending between the higher planes, lower planes and the physical plane creates energetic dimensions (or places) where the separation between these worlds is thin. In these energetic dimensions, lower beings can reach and attach onto an individual -- even though the individual is not directly within the astral regions.

The energetic frequency of each astral being determines the spiritual level wherein it exists. Beings of higher frequency, for example, vibrate at a faster rate and reside in the higher, less dense astral dimensions; whereas beings of lower energetic frequency can only dwell in the dense lower astral levels.

Negative feelings (e.g., worry, fear, anger, etc.) produce a lower vibrational rate that can not only keep an individual's spiritual vibration at a lower level, but can also attract lower level astral beings to that individual.

Soul Projection	The Eternal Soul is projected out of the body, attached to the Middle Dantian through a Silver Cord.
Spirit Projection	The Shen is projected outside of the body as an energetic vehicle of light.
Energy Projection	The Qi is projected out of the body like an energetic vapor.

Figure 13.22. Soul Projection, Spirit Projection and Energy Projection

SOUL PROJECTION

Soul Projection is the skill of sending the body's Eternal Soul (at will) to other places, times and dimensions (or worlds) in order to retrieve knowledge and experiences that assist the individual in his or her spiritual evolution. It is a nonphysical world in which time and space have no meaning or influence. The astral dimensions form a parallel universe that exists both within and outside ourselves.

The Eternal Soul is a fluid energetic form that can disengage from the physical body and travel about as a disembodied apparition taking the human consciousness along with it. It can pass through walls, travel to higher dimensional worlds, and encounter nonhuman creatures and mystical masters. Many Qigong masters use Soul Projection to seek spiritual knowledge, travel through time to view the past, explore other spiritual dimensions, engage in astral sex, or view the "infinite knowledge" (i.e., Messages) contained within the Wuji.

When the Eternal Soul begins to leave its energetic chamber, the brain wave patterns slow to a theta pulse. The body may feel paralyzed, and begin to vibrate as if an electrical current were passing through it.

There is also an odd roaring sound heard in the ears before the Eternal Soul separates from the body's tissues, or sometimes buzzing noises, musical notes, humming sounds, or chattering voices can be heard. When leaving the physical body, sometimes a swaying sensation can be felt as the astral body separates from its physical shell. The astral body can either spin out or float out of the physical body. When traveling in the astral body individuals may observe streaks of light flashing behind them as they travel.

As the Eternal Soul travels, a silver energetic cord is attached from either the top of the head (at the Baihui area) or at the Lower Dantian (at the umbilical area). This energetic cord is the media through which an individual retains his or her awareness of the physical self while projecting. This energetic cord is constructed of subconscious spiritual energy and maintains the individual's protective perceptual awareness of his or her physical body. It is believed by some that if this cord is severed the individual will die.

When the Eternal Soul (in its astral form) approaches someone, there is a feeling of electricity and coolness that is general felt. While in its phantom form, the Eternal Soul can display telekinetic powers (e.g., knocking on walls or tables, closing a half open door, etc.).

Warnings and Contraindication

Do not practice Soul Projection just before, or during, thunderstorms as the electromagnetic buildup in the atmosphere can hamper your ability to leave or return to the body. Also avoid approaching any kind of power-line during Soul Projection, there is a risk of getting caught by the power-line and becoming "stuck" (like a fly in a spider web).

1. A Body of Light	This energetic form resembles an energetic duplicate of the individual's physical self. It involves creating a near exact energy body duplicate of oneself (often with improvements, e.g., no wheelchair, or the elimination of other physical challenges).
2. An Animal Form	This energetic form resembles that of an animal (known as Shape Shifting). It is an ancient Daoist Shamanistic skill used to transcend the astral plane, and to take on the consciousness and energetic behavior, skills and perceptions of the animals the shamans assumed.
3. A Ghost or Saint	This energetic form resembles that of a Ghost or Saint (also known as an Invocation). It involves energetically taking on the image, form, and personality characteristics of a departed individual or spiritual deity.
4. The Immortal Observer	This energetic form resembles that of an All Seeing Eye (also known as The Astral Eye). It involves creating an energetic ball of light in the Upper Dantian at the Yin Tang (Third Eye) area. The large eye surrounded by a sphere of light is released from the Yin Tang area to gather psychic impressions via a long energetic cord attached to the Upper Dantian. As the eye returns, its energetic form is absorbed back into the individual's Upper Dantian. These gathered images are then analyzed and the information is assimilated before the energy is dispersed into the individual's Lower Dantian (and then down the legs and into the Earth).
5. The Element Body	This energetic form usually resembles that of different elements of nature, such as wind (as vaporous mist), Water, Earth (the terrain) or Fire. The ancient Daoist would use these elemental forms of nature as a disguise in order to obtain information or spy on hostile intruders.

Figure 13.23. Types of Spirit Bodies Used in Spirit Projection

Do not practice Soul Projection while recovering from an acute sickness (the drain on your energetic reserves can make you more susceptible to further illness).

SPIRIT PROJECTION

Spirit Projection is the skill of sending the body's Shen (at will) to other places, times and dimensions (or worlds) to retrieve knowledge and experiences to assist the individual in his or her spiritual evolution.

Spirit Projection (also known as mind projection, remote viewing, mind travel or traveling clairvoyance) can entail a combination of "genuine" observation with an extrasensory perceptional ability to gather information. When individuals perform traveling clairvoyance in the form of Spirit Projection, they can send their consciousness anywhere in the world. Awareness is not physical in nature, it is experiential, totally nonmaterial and cannot be limited to, or fully contained within the body.

Spirit Projection is practised through the creation of an energetic vehicle for the spirit body, such as a body of light, an energetic form of an animal, or a ball of light. An energetic shape is formed through the imagination and intention. The individual then transfers the energetic consciousness from his or her physical body into the energetic vehicle. This energetic form can resemble various patterns shapes and sizes to serve the individual's purpose (Figure 13.23).

As the individual thinks about a person or place, his or her body will be pulled to that object like a magnet, followed by a flood of images. The spirit body can fly over various terrains as it travels (e.g., oceans of water, deserts, mountains, forests, etc.). Once the spirit body arrives at its destination, the individual is able to feel and experience the area's environmental Qi (e.g., the humidity, wind, cold, heat, light, darkness, etc.).

After traveling in the spirit body the individual must reabsorb the energetic body back into his or her physical body to retain a clearer memory of the experiences.

Warnings and Contraindication

Do not perform too many Spirit Projections within a relative short time span. Excessive Spirit Projection has a tendency to weaken the Kidneys and drains the body's Wu Jing Shen.

While traveling, be careful of what your intentions are, as like begets like. Any negative projection, emotion or evil intention brought into the astral plane will quickly rebound back to the individual, or may attract negative entities that feed off of these lower vibrations.

ENCOUNTERING ASTRAL BEINGS

Within the subtle realm of the spiritual world, the existence of spiritual entities and ghosts are divided into Yin and Yang. While traveling in the astral realm, an individual can encounter either type of spiritual entity.

1. The Yang Beings native to the higher astral realm vibrate at a faster energetic rate, and are associated with more advanced, highly evolved beings, such as angels, guides, beings of the light, and enlightened masters.
2. The Yin Beings native to the lower astral realm vibrate at a slower energetic rate, and are associated with lower, less evolved beings, such as devils, demons, spirits of darkness, evil spirits, and other similar negative spiritual manifestations.

In all truth, the astral body cannot be hurt the same way that the physical body can. The astral body can, however, carry back to the physical body mental, emotional, and spiritual scars, or hitchhiking negative astral beings, all of which can negatively affect the physical body.

All actions and reactions on the astral plane, whether productive or destructive, are a product of the individual's belief system (you bring about each condition according to your faith).

ENERGY PROJECTION

Another type of life-force energy that the body can project outside its physical structure is Qi. Qi Projection is emitted outside the body like a fine vaporous mist, enveloping and sensing everything that it touches. Similar to Soul Projection and Spirit Projection, Qi Projection is directed according to the individual's intention, imagination, will, and faith. Distance therapy, pertaining to Qi emission, can be observed as energy leaving the doctor's hand like heat waves emanating towards an external object. Within this emitted life-force energy is contained the doctor's Shen (Spirit), as well as the energetically encoded "Messages" that the doctor sends to his or her patient. This constitutes the energetic foundation for Medical Qigong therapy.

SECTION III

DAO YIN TRAINING

CHAPTER 14

INTRODUCTION TO DAO YIN TRAINING

Qigong developed into a systematic healing art for health preservation during the "Warring States" period in Chinese history (476–221 B.C.). Records from that time contain documentation of symptoms, treatments, and specific points of attention given within the body and energy channels, by doctors practicing Medical Qigong, as well as details of the effects of these Qigong exercises.

The Huang Di Nei Jing (*The Yellow Emperor's Classic of Internal Medicine*) states, "to treat diseases it is important to use both Dao Yin and An Qiao." These are two names given to Medical Qigong therapy in ancient times.

"Dao" refers to physical movements, which are guided by the strength of the mind to stimulate the body's Qi and bring about a state of relaxation. "Yin" refers to the fact that with the aid of physical movements the body's Qi can reach the extremities (feet, fingers, and head). Dao and Yin together mean to lead and guide the energy through both motion and quiescence. This therapy includes mental, respiratory, and postural exercises.

"An" has two meanings, "massage" and the "up and down movement of the wrists." "Qiao" means "to lift up." An Qiao refers to the methods of the postural Dao Yin exercises. The basic hand and body methods of postural Dao Yin training are as follows:

- Kai (Opening)
- Fen (Separating)
- He (Closing)
- Tui (Pushing)
- Rou (Rubbing)
- Xuan (Rotating)
- An (Pressing)

These are the foundational movements a Qigong doctor will use in order to purge, disperse, gather, tonify, emit and guide Qi. The training of energy is achieved and implemented primarily through a combination of dynamic (active) and static (quiescent) exercises and meditations. Although Medical Qigong schools are diverse and complex in their form and content, they can all be divided into two main branches of energetic cultivation: Static Qigong and Dynamic Qigong (Figure 14.1).


Static Qigong Training
1.Dispersing into the Wuji
2.Breath Regulation
3.Mind Concentration
4.Imagination and Observation
5.Static Relaxation Qigong
6.Inner Nourishing and Strengthening Qigong
Dynamic Qigong Training
1.Guiding and Inducing
2.Massage
3.Tapping and Striking
4.Self-inducing
5.Hard Qigong

Figure 14.1. Two Main Branches of Energetic Cultivation: Static Qigong and Dynamic Qigong

STATIC QIGONG TRAINING

This training involves bringing about and keeping a quiescent state of mind and breath. In fixed postures (lying, sitting, or standing) the practitioners can train to accumulate substantial Qi in their Lower Dantian, while circulating it through their bodies. Static Qigong training is further divided into six different schools of practice: Dispersing into the Wuji, Breath Regulation, Mind Concentration, Imagination and Observation, Static Relaxation Qigong, and Inner Nourishing and Strengthening Qigong.

1. Dispersing into the Wuji requires the practitioner to dissolve his or her energy into infinite space, or the Void, without focusing or directing their attention on any object from the external environment.
2. Breath Regulation requires moving Qi internally or externally while inhaling, exhaling, or swallowing the breath, etc.
3. Mind Concentration requires concentrating the mind on one fixed internal or external point.
4. Imagination and Observation require disciplining the imagination with vivid, colorful visualizations.
5. Static Relaxation Qigong requires the relaxation of both body and mind, keeping them in a constant state of quiescence.
6. Inner Nourishing and Strengthening Qigong require the use of multiple Static Qigong modalities (for example; Breath Regulation combined with Imagination and Observation).

DYNAMIC QIGONG TRAINING

This involves training the body, mind and Qi simultaneously, to promote the functional activities of Qi and to enhance its free flow throughout the body's channels. These exercises often require standing or walking, and affect muscular tension, weight distribution, Blood and Qi circulation, as well as the functional activities of the major organs. These exercises are differentiated by various kinds of body movements and can be divided into five different schools of training: Guiding and Inducing, Massage, Tapping and Striking, Self-inducing, and Hard Qigong.

1. Guiding and Inducing requires physical movements such as dancing, mimicking animal movements, and gymnastics.
2. Massage focuses on both the manipulation of specific points and channels, as well as on the knowledge of muscles, tendons, and bone structure.
3. Tapping and Striking focus on using patting, slapping, tapping, and striking techniques with the fingers, palm, fist, wooden stick, or material in a cloth bag.
4. Self-inducing training encompasses small to large physically strenuous Qigong movements.
5. Hard Qigong focuses on martial arts training in Iron Palm Training, Iron Body Training, etc.

The incorrect employment of dynamic or static principles of Qigong exercises and meditations can cause energetic deviations which are capable of either hindering, or harming, the individual's health. There are two purposes for Medical Qigong development: To Protect and Strengthen the Body's Health, and To Treat Diseases.

1. To protect and strengthen the body's health: Medical Qigong exercises are prescribed in accordance with the individual's physical constitution, state of health, emotional constitution, climate, and different seasons.
2. To treat diseases: Medical Qigong exercises are prescribed in accordance with the individual's symptoms, pathological condition, and degree of severity, complications, and the constitution of the patient.

PRINCIPLES OF YIN AND YANG IN DAO YIN TRAINING

Both static and dynamic Qigong methods supplement each other when combined equally. No matter which static or dynamic method is practiced, one of the four principles of Yin and Yang will always be adhered to: Quiescence in Motion, Action within Motion, Motion in Quiescence, and Stillness within Quiescence.

1. Quiescence in Motion is referred to as a Yin within Yang technique, and requires being quiet, calm, and still on the inside while being active on the outside.



Figure 14.2. Dao Yin Chart

2. Action within Motion is referred to as a Yang within Yang technique, and requires being active both on the inside and on the outside.
3. Motion in Quiescence is referred to as a Yang within Yin technique, and requires being active on the inside while being quiet, calm, and still on the outside.
4. Stillness within Quiescence is referred to as a Yin within Yin technique, and requires being quiet, calm, and still both on the inside and on the outside.

THREE FOUNDATIONAL METHODS OF DAO YIN TRAINING

The diverse methods of practicing Medical Qigong exercises fall within three categories of Dao Yin training: Posture Dao Yin training, Respiratory Dao Yin training, and Mental Dao Yin training.

1. Posture Dao Yin consists of posture training for Medical Qigong therapy. It is divided into six specific types of training: walking, standing, sitting, kneeling, lying, and massaging.
2. Respiratory Dao Yin consists of breathing exercises for Qigong training, and therapy that includes various techniques of inhaling, exhaling, aspirating, blowing, and holding the breath.
3. Mental Dao Yin training requires that the thoughts be concentrated on one object, placing the cerebral cortex into a special inhibitory state. In various Medical Qigong circles in China this method is commonly referred to as "the internal keeping of the mental state."

The Dao Yins are taught in a postnatal energetic progression of Jing (posture) to Qi (respiration), to Shen (mind and emotion). In this way, the body regulates and supports the production of energy, which in turn regulates and supports the production of Spirit (Figure 14.2).

Despite the fact that many postures and movements may vary according to the specific styles of each Medical Qigong school, the primary benefit of each exercise will:

- improve and strengthen the patient's metabolism,
- smooth the Qi of the channels and collaterals,
- strengthen the body and mind,
- emotionally detoxify the internal viscera, and
- facilitate the increased flow of Righteous Qi (the Qi that fights the pathogenic invasion of Evil Qi) within the body.



Some practices just want to open the heart by temporarily letting us feel love and kindness. The heart is drained through all kinds of giving and donations.

Worldly desire and many businesses work on activating the sexual desire and then draining it out.

Fig. 6.6 *When the Heart is temporarily open and Sexual Desires activate, these forces will drain us out.*

One Lasting Energy is the Combination of Compassion Energy and Orgasmic Energy

Heart Energy

1. Heart energy is immaterial. When activated it will change into love, but love does not last long.
2. When all the good virtue energy from all the organs combines together into one energy, it becomes compassion energy; it will stay in you longer, but will still disperse.

Sexual Energy

1. Sexual energy when activated from material into immaterial is powerful, but will not last.
2. When the sexual energy is aroused and changes into orgasmic energy, it can charge all the organs, glands, senses and combines into one energy; this energy will stay longer but still will disperse. Orgasmic energy combined with compassion creates one long lasting energy.

CHAPTER 15
POSTURAL DAO YIN TRAINING

The goal of Postural Dao Yin training is to promote the regulation and circulation of Qi. Part of this training involves learning the techniques to guide the internal energy to flow using the movements and changes in the electromagnetic fields of the hands and body.

Success in Medical Qigong training is directly related to the correctness of the body's alignment. Correct posture regulates the Heart, and results in a calm mind; with a relaxed mind it is easy to lead the flow of Qi downward, to affect the Blood circulation and pulse. When the body is incorrectly aligned, it disturbs the smooth flow of Qi; energy then becomes obstructed or deviates, resulting in a restless Mind (both the thinking mind and the whole body consciousness).

The proper sequence of relaxation and energy circulation within the body is as follows:

1. the muscles are first to relax,
2. followed by the tendons and ligaments,
3. next, the nerves relax, and
4. finally the bones.

Once the muscles, tendons, and ligaments relax, the Qi can circulate freely through the channels and collaterals. The skin and muscles are generally the first level of awareness cultivation. The sensations of Qi and Blood circulation are usually experienced by the practitioner as heat, tingling, fullness, and expansion. The Chinese call these sensations the Eight Energetic Touches, which are known as the first of three transformations of energy (also known as the Subtle Wonders, see Chapter 29).

The next level of awareness involves the deeper flows of Qi within the nerves; this feels like an electric vibration, or an energetic current traveling through the body. Sometimes, due to an energetic surge released from within the body's organ system or channels, an electric shock is felt through the extremities or through the entire body.

The final level of Qi circulation awareness involves the Qi circulation within the bones and the Marrow. In the beginning stages it sometimes feels cold and arthritic in the joints (especially within the extremities). These sensations will later develop into a vibrational resonance which is felt deep within the bones.

The main point of Postural Dao Yin is to seek a state of physical and energetic balance. Postural Dao Yin is also divided into two distinct methods of treatment: Static Posture and Dynamic Posture training.

STATIC POSTURE DAO YIN TRAINING

This method includes quiet movement while in the position of lying, sitting, standing, or walking, and is used to accumulate and strengthen the practitioner's internal Qi. Before performing the static posture forms for Medical Qigong therapy, it is important to note that static posture training is divided into three basic modalities: Choosing the Proper Beginning Posture, the Inhaling and Exhaling Methods, and Opening and Closing the Lower Dantian.

1. The purpose of the choosing the proper beginning posture is to calm the Heart and relax the mind, and focus on a specific goal for training the body's life-force energy.
2. When the energy begins to flow freely, the practitioner focuses his or her attention on each inhalation and exhalation for the specific goal of tonification, purgation or regulating the life-force energy.
3. The purpose of the "opening and closing" of the Lower Dantian ending postures is to bring the body's energy back down into the Lower Dantian and to root the Qi. Rooting the Qi in the Lower Dantian after Qigong practice

avoids creating Excess conditions within the body's internal organs.

CHOOSING THE PROPER POSTURE

Medical Qigong meditations and prescriptions are not limited to sitting practice alone. Each of the different lying, sitting, standing, and walking postures has its own specific form of meditation.

The lying, sitting, and standing postures create the foundational base for Static Posture Dao Yin training. Each static posture can induce the body's energy to descend quickly into the Lower Dantian. The selection of the appropriate technique and body position is determined by each practitioner's body type (structural formation) and the condition of the individual's physical health. The length of time that a practitioner focuses on the Medical Qigong prescription is also determined by the individual's specific disease as shown in the following examples.

- Patients with digestive problems, gastroptosis, or prolapse of the internal organs should begin their training while lying supine (on their back), with their knees pointing upward, their buttocks elevated 4 inches off the ground, and their feet flat on the floor.
- Patients with gastrointestinal diseases should begin their training lying flat on their backs. As the condition improves, they should combine lying and sitting meditations to promote the digestion and absorption of food.
- Patients with Heart disease, hypertension, or nervous disorders should begin training from a sitting position. Later, they should combine sitting and standing meditations in order to direct their Qi and Blood downward.
- Patients with Lung diseases, asthma, chronic bronchitis, emphysema, or cardiopulmonary function disorders should begin their training from a semi-reclining position (usually a 45 degree angle) to help respiration flow smoothly and to alleviate stress on the Lungs.

  In the hospital, each pillow that the patient uses for elevation represents the degree of strain that is placed on the Lungs. The patient is said to have strong Lungs, for example, if he or she is reclining and breathing comfortably on one pillow. If however, it takes three pillows before the patient is reclining comfortably, the Lungs are considered weak and congested (e.g., in cases of dyspnea).
- Patients with severe physical weakness (e.g. chronic fatigue syndrome and fibromyalgia) should begin their training from a lying or sitting position. Later, they can combine sitting and standing meditations as their constitution improves.

PRIMARY AND SECONDARY POSTURES

Patients are taught a primary and a secondary posture to prevent fatigue, and increase the healing effect of the Medical Qigong prescriptions. A primary standing posture is performed, for example, in the morning when the patient is strongest, and the energy is cleanest. A secondary sitting posture is performed in the afternoon, or evening when the patient is tired, with a focus on quiet regulation.

After a patient has learned a particular lying, sitting, or standing meditation, he or she can be taught the secondary posture without the risk of depleting his or her Qi.



Figure 15.1. Sleeping Dog Posture



Figure 15.2. Supine Posture (Hibernation Posture)

LYING POSTURES

The Chinese saying, "The body should lie like a bow," is a perfect description of the curled position of the patient's body, while in the Sleeping Dog posture (Figure 15.1). This particular position is beneficial for aiding digestion and the absorption of food.

In prescribing the Sleeping Dog posture, the patient should lie on their right side with the left knee bent and the right leg extended straight. To avoid compressing the Heart, do not allow the patient to lie on their left side. Keep the patient's head raised slightly to allow the Blood to flow downward into the torso. Have the patient bend the right arm at the elbow.

When the patient is chronically ill, however, an exception is made. In this case it is important that the patient lie on the "healthy side" and not the side of the diseased organ (e.g., in cases of Liver disease, patients might lie on their left side). Remember to always adjust the patients' postures as needed and encourage them to practice "natural breathing."

Another popular posture is called the Hibernation posture. By lying supine in the Hibernation posture, the patient will regulate the functional activities of the central nervous system (Figure 15.2). Lying supine is also suitable for patients with serious diseases who are debilitated (this is also a sleep inducing method of training).

SITTING POSTURES

The Chinese saying, "The body should sit like a bell," describes the secure (or rooted) position of the patients' body, especially the lower legs and torso. Sitting is the most commonly used position for Medical Qigong therapy. This position helps the patients to relax and focus their mind's intent.

There are several sitting postures used in Medical Qigong therapy, and are prescribed according to the patient's flexibility: sitting upright on a chair (Figure 15.3), a cross-legged posture called the Full Lotus, another called Half Lotus, or with the legs loosely crossed (Figure 15.4-6). Make sure the patients sit on a raised cushion in order to keep their buttocks slightly higher than their knees.



Figure 15.3. Upright Sitting Posture



Figure 15.4. Cross-Legged Zi Wu Posture



Figure 15.5. Cross-Legged Buddhist Greeting Posture



Figure 15.6. Cross-Legged Buddha's Warrior Attendant Posture

One of my Medical Qigong instructors in China suggested elevating the hips at least four inches off the floor when meditating, to avoid undue stress on the lower back, spine, and leg circulation. This elevation of the hips forms a triangle between both knees and the Lower Dantian, establishing a firmer connection to the Earth energy. This allows the Earth Qi to easily flow from the patients' knees and coccyx into their body.

When sitting in a chair meditating, the feet should touch the ground firmly, instead of being suspended in midair. This allows the Earth Qi to flow easily from the patients' feet into their body. Otherwise patients may develop swollen feet and lumbago due to Blood stagnation, or even hallucinations.

Keep the patients' spine straight by aligning the tip of the nose on a vertical line with the navel, to release pressure and tension on the cervical nerves.

STANDING POSTURES

The Chinese saying, "The body must stand like a pine tree," describes a relaxed position of the body's structure, standing with the bones stacked on top of each other, from the ground up. Standing meditations are particularly tonifying in nature, and are absolutely essential for accumulating Qi. The advantage of the standing position is that the flow of energy can be easily regulated and promoted. This posture helps to normalize blood pressure, and calm the Heart. Standing meditations also produce a unique psychophysiological change within the patients, allowing them to shed energetic obstructions, and to create a healthier body, mind, and spiritual awareness. Standing meditations are also essential for the Qigong doctors, as it facilitates the accumulation of Qi that is necessary for the emitting of energy.

Standing meditations, however, are not suitable for patients who are extremely ill or in poor health. Therefore, exercises in the standing postures should only be prescribed for minimal durations during convalescence, to build up the patients' constitution, promote health and to enhance their strength slowly.

The body should be held in an upright posi-



Figure 15.7. Wuji Posture



Figure 15.8. Immortal Post Posture



Figure 15.9. Buddhist Greeting Posture



Figure 15.10. Extending Palm Posture



Figure 15.11. Embracing Dantian Posture



Figure 15.12. Square-Round Posture

tion, with three points connected in a straight line: Baihui GV-20 point at the top of the head, Huiyin CV-1 point at the bottom of the perineum, and the Yongquan K-1 point at the bottom of the feet. The patient's posture should be kept relaxed, still, solid, and rooted like a tree. The patient should also imagine their feet growing roots deep into the ground, to absorb the Earth's energy from the soil.

Standing exercises are usually accompanied by a variety of hand positions (Figures 15.7–15.12). The most popular are (1) Wuji: hands hang down by sides, (2) Immortal Post: hands embrace an invisible ball, (3) Buddhist Greeting: both hands press together at the solar plexus level, (4) Extending Palm: both hands press downward, (5) Embracing the Dantian: folding the hands and resting them on lower Dantian, and (6) Square-Round: left palm's heel rests inside the right palm's center.

In each posture, whether lying, sitting, or standing, the function and flow of body energy shifts and changes in relationship to, and as a manifestation of, the patient's mental belief structure.

If, for example, the patient while standing, shifts his or her weight and mental focus onto the balls of the feet, the energy will naturally flow through the front of the body via the front Yin channels. If the patient shifts his or her weight and mental focus onto the back on the heels, the energy will naturally flow through the back of his or her body via the back Yang channels. The center of the feet connect the patient's flow of energy to the Taiji Pole and can be used either to transfer the energy forward or backwards.

Generally, before beginning standing meditations, patients are encouraged to relax, sink, and shift their body weight back and forth between their heels and their toes. This practice massages their internal organs and disperses any blockages by stimulating the corresponding organ areas at the bottom of the feet as described in the therapeutic use of the Lower Hexagram Yaos (see Chapter 3).

Patients should inhale while shifting their weight backwards and exhale while shifting forwards. Their attention should be placed on their internal organs and the body's surrounding field of energy. The patients' awareness is also focused on the body moving back and forth, like the rhythm of an ocean tide.

Women are generally encouraged to practice meditation in the standing position (especially around the time of their menstruation), as the sitting position tends to decrease energy circulation, and may cause energy blockages in their lower abdominal area.

THE EIGHTEEN RULES OF PROPER MEDICAL QIGONG STRUCTURE

The most important basic techniques of Medical Qigong training are guided by eighteen rules of proper form and structure. The main point of Postural Dao Yin training is to relax and seek quiescence while in the various postures. Tension in any area of the body restricts the whole structural system, since the body seeks to balance its structure naturally by shifting its energy and weight. The general function of the muscles is to guide the flow of energy through the channels.

The following is a list of the Eighteen Rules for proper standing postures, these rules apply to every school of energy cultivation:

1. Stand with the feet flat,
2. Bend the knees,
3. Relax the hips,
4. Round the perineal area,
5. Close the anal sphincter,
6. Pull in the Stomach,
7. Relax the waist,
8. Tuck the chest in,
9. Stretch the back,
10. Relax the shoulders,
11. Sink the elbows,
12. Hollow the armpits,
13. Relax the wrists,
14. Suspend the head,
15. Tuck the chin,
16. Close the eyes for inner vision,
17. Close the mouth and turn your hearing inwards, and
18. Touch the tongue to the upper palate,

Each of these eighteen rules is described in detail as follows.

RULE 1—STAND WITH THE FEET FLAT

Stand with the feet flat, parallel to the outside of the shoulders. Weight should be distributed evenly on both feet about an inch and a half inward (anterior) from the heels, and perpendicular to the tibia. Focus on dropping the weight down behind the legs, not down the front. This action takes the pressure away from the knees and places it in the center of the feet (Figure 15.13).

Stretch the feet and let the toes softly grasp the ground to keep the body firmly rooted as you tuck the sacrum under (Figure 15.14). Relaxing is important. Rigid, contracted feet disrupt the flow of energy from the Earth into the body. The Kidney energy flowing within the bone can be accessed by shifting the weight onto the heels. The Heart energy can be accessed by shifting the weight onto the balls of the feet. The weight in the center of the feet accesses the Taiji Pole.

While training, the feet may vibrate or feel hot, as if on fire. This is a normal reaction to correct postural training and is beneficial because it dissolves the calcium deposits stored within the extremities of the feet. If, however, the Fire in the feet is too intense (due to Excess Liver Fire), hit the heels on the ground and rub the lumbar spine, using the mind's intention to send more of the Kidney Yin (Water) down to the feet to cool the Fire.



Figure 15.13. Stack the bones on top of each other from the bottom of the feet to the skull.



Figure 15.14. The three points (Baihui, Huiyin, and Yong quan) can be connected by a straight line.

RULE 2—BEND THE KNEES

The knees should be slightly bent and facing the same direction as the feet. The knee caps should be directly aligned and extended no further than the tips of the middle toes. Do not allow the knees to twist inward.



Figure 15.15. Keep the center of the body's weight aligned to the center of the knees, to relax the connective tissue surrounding the knees.

To secure the structure, imagine holding a large beach ball between the knees. Many patients develop knee problems because they extend their knees too far forward or allow their knees to twist to the side, rather than aligning them with the toes. If pressure is felt on the sides or front of the knees, check the positioning. Knees that are unable to point in the direction of the toes are most often the result of tight hip joints (Figure 15.15). If the energy in the legs is tightly constricted around the knee area, Qi flow will be severely limited. A relaxed knee-joint, on the other hand, will increase the Qi and Blood flowing through the legs, making it easier to relax the hip and to round the perineal area.

Relaxing the knees also permits free flow of energy through the three descending Yang channels on the outside of the leg, and the three ascending Yin channels on the inside of the leg (Figure 15.16). The techniques for relaxing the knees will vary according to the emotional and structural pattern of each individual, as emotions of fear, etc., have a tendency to gather and pool behind the knees.

RULE 3—RELAX THE HIPS

Drop the buttocks slightly while sinking the Qi from the upper torso into the Lower Dantian, and relax the hips. Keep the hips facing forward. The buttocks should be gently tucked under the body to facilitate straightening of the spine and the keeping the Qi in the Lower Dantian.

Imagine a weight of a thousand pounds hanging from the coccyx (Figure 15.17). As the weight pulls down, tilt the sacrum under the body. When the hip-joints are relaxed, the lower limbs will be able to move freely.

RULE 4—ROUND THE PERINEAL AREA

There are three parts to rounding the perineal area. First, set the knees apart, turning them both outward. This allows the groin and hips to shift to an anterior tilt. Second, bring the knees back together and turn them inward, while also relaxing the hips. This allows the groin and hips to shift to a posterior tilt. Third, suspend the perineal area to lift the perineum and the anus slightly. This allows the groin and hips to come to a center balance and to sink. Rounding the perineal area keeps the perineum free from pressure, yet sealed. This ensures better functional activities of the Qi, and allows the "lower door" (the anus) to remain closed to avoid leakage of vital energy.

RULE 5—CLOSE THE ANAL SPHINCTER

The anus is called the Lower Bridge and it is where the Yang and Yin channels meet and combine. The anus is considered the door of the Seven Corporeal Souls (Po). Although the anal sphincter is held closed, it is important that the perineum remain relaxed. There are three stages in controlling the anal sphincter:



Figure 15.16. Relaxing the knees also permits the free flow of energy through the ascending Yin channels and descending Yang channels of the legs.



Figure 15.17. Imagine a 1000-pound weight hanging from the coccyx and a heavenly cord suspending the head.

1. In the first stage, the anus is contracted with slight muscle control, and the energy is directed into different energy centers along the Microcosmic Orbit. When first beginning, inhale and expand the abdomen while imagining that the anus is connected to the navel and is pulling up towards it. On the exhalation, contract the abdomen and draw the energy from the navel back down towards the anus. Next, inhale and create a connection between the anus and the Mingmen. On the exhalation, draw the energy from the Mingmen back down towards the anus. It is important to synchronize the drawing up of the anus towards the navel and Mingmen area with the expansion and contraction of inhalation and exhalation. This will facilitate a

sacral-cranial rhythm throughout the body.

2. In the next stage of training, the constriction of the anus is used to lead the energy up the Governing Vessel in the Microcosmic Orbit (Figure 15.18). Upon inhalation, draw the mind's intention from the navel towards the anus and then down to the tip of the spine (the coccyx), allowing the Qi to flow up the spinal column towards the Mingmen, past the Shendao to the base of the skull. Upon exhalation, roll the eyes back into the head and use the intention to meet the energy at the base of the skull. Next, lead the energy over the Baihui at the top of the head and down the Conception Vessel and back down to the naval.
3. At the third stage, imagine twisting the energy of the anal sphincter, spiraling the Qi up the center of the body, to connect with the Baihui area at the top of the head. Close the anal muscle gently, inhale and imagine the energy vibrating and spiraling in a counterclockwise direction up the body's Taiji Pole. This connects the Lower, Middle, and Upper Dantians through the Taiji Pole. Upon exhalation, lead the vibrating Qi down the Taiji Pole in a clockwise spiral ending within the Lower Dantian area. Continue this meditation until the entire body pulses with the rhythm of the Taiji Pole.

The anus is divided into five regions: Front, Middle, Back, Left, and Right. By contracting the anus in different parts, you can bring more Qi to the various organs and glands.

1. The Front region opens the gate to the sexual organs, as well as to the Conception Vessel when it is contracted.
   - For Men, this will affect the prostate gland, Bladder, Small Intestine, thymus gland, thyroid gland, parathyroid gland, mouth, nose and front part of the brain (Figure 15.19).
   - For Women, this will affect the vagina, uterus, vena cava, aorta, Stomach, thymus gland, thyroid gland, parathyroid gland, mouth, nose, pituitary gland, and front part of the brain (Figure 15.20).
2. By contracting and pulling the middle region of the anus, more Qi is drawn into the Thrusting Vessel and Taiji Pole, as well as to the genitals, aorta, vena cava, Stomach, Heart, thyroid gland, parathyroid gland, tongue, pituitary gland, pineal gland, and Baihui area (Figure 15.21).



Figure 15.18. The anus is used to draw the Qi from the navel into the Lower Dantian and lead the Qi up the Governing Vessel.

3. By contracting the back region of the anus the Qi is connected to the Governing Vessel, as well as the sacrum, lumbar, thoracic and cervical vertebrae, and the cerebellum (Figure 15.22).
4. By contracting the left side of the anus the Qi connects to the left side of the body.
   - For Men, this affects the left testicle, Large Intestine, left Kidney, left adrenal gland, Spleen, the left side of the Heart, left Lung, left ear, left eye, and left hemisphere of the brain (Figure 15.23).
   - For Women, this affects both ovaries, both Kidneys and both adrenal glands, Spleen, Liver, Heart, both Lungs, thyroid gland, parathyroid gland, and both hemispheres of the brain (Figure 15.24).
5. The Right Side. By contracting the right side of the anus the Qi connects to the right side of the body.
   - For Men, this affects the right testicle, Large Intestine, right Kidney, right adrenal gland, Liver, Gall Bladder, right side of the Heart, right Lung, right ear, right eye, and the right hemisphere of the brain (Figure 15.25).



Figure 15.19. The Front of the Anus



Figure 15.20. The Front of the Anus



Figure 15.21. The Middle of the Anus



Figure 15.22. The Back of the Anus



Figure 15.23. The Left Side of the Anus



Figure 15.24. The Left Side of the Anus



Figure 15.25. The Right Side of the Anus



Figure 15.26. The Right Side of the Anus

After the orgasmic energy has charged all the organs and created the multi-orgasm energy, it can then be combined with the compassion energy at the Tan Tien. This creates the one energy that lasts the longest.

When we are aware of the cosmic galaxy and expand our combined energy of compassion and orgasm through the universe, it multiplies and flows back to us and we will be in touch with universal compassion and unconditional love.



Fig. 6.7 *Through cultivating compassion energy, we can eventually build the one lasting energy.*

- For Women, this affects both ovaries, both Kidneys and both adrenal glands, Spleen, Liver, Heart, both Lungs, thyroid gland, parathyroid gland, and both hemispheres of the brain (Figure 15.26).

RULE 6—PULL IN THE STOMACH

Pull the stomach in above the pubic bone, and avoid tensing of the abdominal muscles. This helps to restrain the Yuan Qi, thereby increasing the internal pressure and promoting the flow of internal Qi throughout the whole body.

RULE 7—RELAX THE WAIST

If the waist is not relaxed the Qi can not sink back to the Lower Dantian. Relax the waist by relaxing the hips and bending the knees. When the waist is relaxed, the spine will stand upright, yet remain relaxed.

The waist and the abdomen are two important areas in training and guiding Qi. The abdomen is considered to be the furnace for refining Qi. The waist is the residence of the Kidneys and Mingmen Fire and is an important junction for Qi and Blood circulation.

The waist is considered the master of the body and must be kept sunken and relaxed (Figure 15.27). As the buttocks tuck under and the waist sinks, small pockets should form on the inner thighs where the pelvic bones meet the femur bones of the legs. Most people usually keep the pelvis area tight and immobile, as it is associated with shock, fear, and sexual trauma (when this area becomes loosened, such emotions are often released).

The specific actions to relax the waist are as follows: lift both shoulders in order to stretch the back, then release them downward immediately as you exhale, relaxing the waist. To achieve genuine waist relaxation, you must also relax and tuck the sacrum, this action opens the sacrum. When the sacrum is opened, the Lower Dantian will expand and the storehouse of Yuan Qi will be enlarged. Be sure that the waist and hips face forward in the same direction as the knees and feet.

RULE 8—TUCK THE CHEST IN

The chest should relax inward so that air flows freely and the Qi sinks down into the Lower Dantian. Fill the abdomen with air while relaxing the chest inward. The back should be open and expanded. Relax the scapulae and allow them to sink to their lowest point, this will help the shoulders to sink. Rounding the scapulae (pushing to the sides and forward) will help open and expand the back.



Figure 15.27. Relax and sink the waist, allowing the hips to drop.

Do not thrust the shoulders inward, nor intentionally close the thoracic cavity. The intentional tucking in of the vertebral area requires the outward opening of the ribs and expansion of the intercostal muscles. The action of opening the chest outward, then tucking the chest inward, helps to relax the thoracic cavity and avoids tension in the thoracic muscles.

RULE 9—STRETCH THE BACK

The key point to stretching the back is to hang the shoulders and "open the scapulae." When the two shoulders drop evenly, the lumbar vertebrae straighten out. The function of tucking the chest and stretching the back calms the Heart and Lungs.

The Heart controls mental and emotional activities, and also directs Blood circulation. When the thoracic cavity is spacious and the back is upright, the Heart and mind will be calm, and the Lungs will be clear and free from Heat. Tucking the chest and stretching the back allows the chest and back to relax, permitting the Conception and Governing Vessels to communicate with each other and improve energy movement.

Imagine a weight hanging from the coccyx and a rope pulling up on the crown point of the head. Feel the elongation of the spine with each inhalation and exhalation. Remain relaxed (Figure 15.28), do not hold yourself unnaturally erect and avoid contracting the abdomen to straighten the lower back. The abdomen must remain relaxed. When sinking the body's weight, try to feel the spine press into the heels of the feet.

RULE 10—RELAX THE SHOULDERS

If you relax the shoulder joints and let them hang naturally, the shoulders and neck will relax. If you elevate your shoulders when you are standing or sitting, the energy will not sink and you will begin to feel tired, the shoulders will be stressed, and the flow of Blood and Qi will become blocked.

When the shoulders are encouraged to relax and are allowed to drop and roll forward, this action facilitates the hollowing of the chest and the expanding and opening of the back, allowing the energy to flow into the arms (Figure 15.29). Try to feel your arms link up with the scapulae as the clavicles press downward. Your shoulders should remain very loose and free.

RULE 11—SINK THE ELBOWS

When practicing the Immortal Post posture (refer back to Figure 15.8), and the hands are positioned by the Heart, it is important to bend the elbows slightly at the elbow joint, holding them lower than the hands.

While in a Wuji posture, imagine that a weight is hanging from the elbows, or a sensation of compression will be felt at the shoulder and elbow joints. The elbows should be slightly bent and relaxed, remaining structurally correct and not weak. This will help to roll the shoulders forward



Figure 15.28. By imagining a rope pulling on the head and coccyx, the spine is allowed to naturally stretch, expanding the body's Qi in all directions.

Figure 15.29. When the shoulder (here viewed from above) relaxes, the Qi flow into the arm increases.

and open up the back. If the elbows are not bent, there will be decreased energy flow (Figure 15.30).

RULE 12—HOLLOW THE ARMPITS

Hollow the armpits as if each one is holding an egg, this allows the Qi and Blood to flow freely in the upper limbs. To relax the shoulders, move the tips of the elbows outward to the left and right. Avoid sloping or squaring the shoulders.

When practicing the Immortal Post Posture (refer back to Figure 15.8), the arms must embrace inward as if holding a large ball or barrel. Do not push the elbows out so far that you loose the curve in your arm, this is of extreme importance. Your arms should not bend inward more than 45 degrees. The energy flowing in your arms is like water running through a hose. If you bend it too sharply, much of the supply will be cut off.

RULE 13—RELAX THE WRISTS

This includes hollowing the palm, and the comfortable curling of the fingers. Relaxation of the wrist allows the Shu-Stream points in the wrist to communicate with the fingers (see the Five Antique Shu Points in Chapter 8). Hollowing the palm and curling the fingers allows for the natural stretching and curving of the hand, which prevents the Qi from diffusing. It is important to avoid being rigid and purposefully bending the fingers, as all hand postures effects the brain and the body's Qi flow.

Relaxing the wrists helps to regulate the three Yang and three Yin channels of the hands so that Qi and Blood can flow freely. The wrist must form a line with the shoulders. Do not bend the wrists, but hold them straight so that the middle finger forms a line with the forearm, allowing the hands and fingers to hang relaxed but not limp.

RULE 14—SUSPEND THE HEAD

The classics say that "the head is held aloft not by force, but as if it were placed there by a ruling power." Hold the head as if it were suspended, keeping the Baihui point pointed to Heaven (Figure 15.31). This produces space in the body by elongating the spine. When suspended, the head must be kept upright, positioned in the middle of the chest and shoulders. This helps to set the whole body in the upright position, and



Figure 15.30. Allow the bones in the arms to feel heavy, naturally stretching the tissues and increasing Qi flow to the extremities.



Figure 15.31. Suspending the head allows the body to become sensitive to the surrounding environment and external fields of Qi.

also directs the Qi and Blood to flow upward to nourish the brain and the mind. The Shen will be reinforced while the Jing and the Qi will be invigorated (it is the Shen which controls all the physical activities). An effective visualization is to imagine your head lifting high into space, your waist positioned in the clouds, and your feet sunk deep into the Earth.

RULE 15—TUCK THE CHIN

The head cannot be properly suspended if the chin is not tucked in. Only then can the Baihui point on the top of the head be correctly positioned and the nasal respiration kept free.

Tuck the chin and slightly lean forward to stretch and straighten the spine. You should feel the stretch all the way down into the coccyx. Next, slowly shift the weight backwards, stacking each vertebra on top of the next, starting from the bottom of the coccyx and sacrum and moving upwards.

RULE 16—CLOSE THE EYES FOR INNER VISION

The Chinese have a saying: "close the curtain." This refers to dropping the eyelids to facilitate inner-vision, and focusing on any specific areas where Qi is being trained or circulated. The eyes are of great importance in Medical Qigong exercises. It is said that the functional activities of Qi are determined by the eyes, and that the eyes are the messengers of the mind, and the mind is the residence of the Shen.

Completely closed eyes induce an absolute Yin state which is generally used in meditations for tonifying any Deficiencies. However, when used excessively (with all Yin and no Yang energy), the Qi can become too inactive.

Completely open eyes induce an absolute Yang state which is generally used in meditations for dispersing any Excesses. However, if overused, or if the patient has an Excess Yang condition, this type of meditation can make the practitioner too restless.

When the goal is to regulate the body's energy, slightly open the eyes in order to leave a small thread of light inside the eyes. This will keep the Yang (light) within the Yin (dark), so that the Qi will be more balanced. Because energy leaves the body through the eyes, after performing various Medical Qigong exercises, or prescriptions, allow your eyes to close halfway to continue the cultivation of life-force energy.

Tightly shutting the eyes causes tension in the upper and lower eyelids. Closing the eyelids gently, however, will restrain the vision, which helps to calm the Shen and the mind.

When meditating, if the eyes look to the distant horizon, they should not be focused but stare into infinity, this technique is also called the One Thousand Yard Stare, and it helps in regulating the venous pressure in the cranial cavity.

Strive for balance. Each eye has its own specific responsibility and energetic function.

- The right eye is generally used to project intention and extend emotion, energy, and spirit out from the body. The right eye relates to Water, the Kidneys, Qi, moon, Yin, Earth, Metal, and the Po.
- The left eye is generally used to receive, drawing in images, emotion, energy, and spirit into the body. The left eye relates to Fire, the Heart, Shen, sun, Yang, Heaven, Wood, and the Hun.
- If both eyes look upwards towards the Upper Dantian, the body's energy will draw up into the infinite space of the Wuji and merge with the divine.
- If both eyes look towards the tip of the nose, the Middle and Lower Dantians are linked together for transforming Yuan Qi.
- Crossing the eyes results in the union of the Wood and Metal, the elements of alchemic transition, for increasing the development of psychic energy. This intensification of psychic development is due to the union of the Hun and Po within the body, and is said to connect the meditator with his or her Yuan Shen.
- After meditation, store the Qi of the eyes behind the posterior orbital surface of the eyeballs themselves. This prevents the eyes from overheating and drying out.

RULE 17—CLOSE THE MOUTH AND TURN YOUR HEARING INWARD

In order to enhance the Yang during Medical Qigong exercises, close the lips with the teeth gently touching. Closing the lips will prevent the internal Qi from flowing out.

The Chinese use the expression: "Stopping the ears," which means to focus the hearing inward so as to be free from outside interference.

RULE 18—TOUCH THE TONGUE TO THE UPPER PALATE

When the tongue touches the upper palate, it forms what is called the Bird's Bridge. The connection of the tongue links both the Governing Vessel (which ends at the nose and upper palate) and the Conception Vessel (which ends in the mouth). As the tongue touches the upper palate, the body's field of Wei Qi expands. This can help to eliminate diseases and prolong life. The belief is that when someone has a disease, the Governing and Conception Vessels are to some extent disconnected.

Some Qigong doctors test their patients' progress by having them meditate with their tongue suspended in their mouth. Upon command, they connect the tongue to the upper palate. The suddenly increased expansion and strength of the patients' Wei Qi, observed by the doctor, indicates the degree of their progress.

1. The technique called "Gathering the Saliva," begins when the tongue touches the upper palate, causing the saliva secretion to be increased. Saliva contains many enzymes, which not only aid digestion, but also benefit the patient's physiology. In ancient China, this practice was called Gathering the Immortal's Water or the Juice of Jade to create the Immortal Pill.

   There is an exchange of Yin and Yang energy within the saliva, as Heaven Qi and Earth Qi are gathered within man's Fluid Essence in order to create the Immortal Pill.

   Before swallowing the saliva, it is important to tilt the head slightly forward (after inhaling). Swallow the saliva three times with three big gulps, using the breath as a cork to enclose the saliva. Send the Immortal Pill, i.e., the combined saliva and air down the Conception Vessel, bathing the Five Yin Organs, and ending at the Lower Dantian. Next, draw the energy up the Governing Vessel into the brain to replenish and nurture the Upper Dantian.
2. There are Five Elemental Tongue Positions. Each tongue position is related to one of the Five Yin Organs and can be used to direct the Qi to that specific organ. Sometimes, while practiscing Medical Qigong prescriptions, if too much Heat is created, the patient will be instructed to "change the tongue position" as well as meditation. These Elemental tongue positions are described as follows.
   a. The Earth (Spleen) position requires that the tongue be placed on the bottom of the jaw at the base of the lower palate, beneath the teeth and gum line (Figure 15.32).
   b. The Metal (Lungs) position requires that the tongue be placed between the maxilla and mandible bones, suspended, behind the teeth (Figure 15.33).
   c. The Fire (Heart) position requires that the tongue be placed on the hard palate, at the front of the upper palate, behind the teeth and gum line (Figure 15.34).
   4. The Wood (Liver) position requires that the tongue be placed on the hard palate, at the middle of the upper palate at the center of the roof of the mouth (Figure 15.35).
   e. The Water (Kidneys) position requires that the tongue be placed on the soft palate, at the back of the upper palate (Figure 15.36).

DYNAMIC POSTURE DAO YIN TRAINING

While Static Qigong exercises accumulate and strengthen the Qi internally, Dynamic Qigong exercises train the channels, collaterals, muscles, and bones externally. The more dynamic movement a patient makes, the more the energy will be converted and transformed inside the body. When dynamic movement is discontinued, some of the accumulated energy will begin to dissipate, while the remainder will flow through the channels and increase the patient's Qi circulation.



Figure 15.32. For the Earth position, which is related to the Spleen, the tongue is placed on the bottom of the jaw at the base of the lower palate, beneath the teeth and gum line.



Figure 15.33. For the Metal position, which is related to the Lungs, the tongue is placed between the maxilla and mandible bones, suspended, behind the teeth.



Figure 15.34. For the Fire position, which is related to the Heart, the tongue is placed on the front of the upper palate, behind the teeth and gum line.



Figure 15.35. For the Wood position, which is related to the Liver, the tongue is placed on the middle of the upper palate at the center of the roof of the mouth.

The lymphatic system is pumped by normal muscular contraction. When a patient performs Dynamic Postural Movements, the lymphatic system is flushed, thus freeing the body of toxins.

Dynamic Qigong is divided into two methods of training: The Yun (Yin) Method and the Dong (Yang) Method.

1. The Yun Method is a more Yin approach, and employs slow, even, graceful movements. The focus of the mind's intention is placed on the internal organs, resulting in emotional relaxation.
2. The Dong Method is a Yang approach, and employs intense physical movements. Focus is placed on the movement of the body's ex-



Figure 15.36. For the Water position, which is related to the Kidneys, the tongue is placed on the soft palate at the back of the upper palate.



Figure 15.37. Hands Rise, Leading to the Ascending of the Qi.



Figure 15.38. Hands Fall, Leading to the Descending of the Qi.

tremities, resulting in tissue regulation.

Both Yin and Yang (Yun and Dong) training methods must be balanced when prescribing proper Medical Qigong exercises. With the Yin method, the patient will experience external quietness with internal energetic movement. With the Yang method the patient will develop internal quietness with external, physically active movement.

USING THE ENERGY OF THE HANDS TO LEAD QI

Dynamic Postural training is performed by the extensive movements of the hands and torso. Because the palms have a stronger electromagnetic field than any other part of the body, the hands are used for leading and guiding the Qi. These movements are in harmony with the rotating, bending and stretching movements of the head, neck, torso, and limbs. Any change of the body's position or movement can change the direction or position of the electromagnetic fields of the hand. Likewise, any change or movement of the hands or palm positions, also changes the direction and flow of the electromagnetic field of the body. In Medical Qigong therapy the Dao Yin Hand Techniques have the following four functions:

- Hands Rise—Qi Ascends (Figure 15.37)
- Hands Fall—Qi Descends (Figure 15.38)
- Hands Open—Qi is Spread (Figure 15.39)
- Hands Close—Qi is Restrained (Figure 15.40)

The positions of these hand techniques can be further divided into three ranges: upper, middle, and lower. These ranges can relate to either the position of the body's Triple Burners, or the body's three Dantian areas, depending on the specific Medical Qigong prescription, and the doctor's intention for the exercise. The directions of these hand movements can further divide a posture into four front and four oblique types of Qi regulations. Moreover, depending on the arm movements, each posture can be divided into Yin (palms facing down) or Yang (palms facing up), as well as half Yin or half Yang regulations (Figure 15.41).

The actions of these methods supplement, regulate, smooth, and reinforce the vital Qi. Using these techniques will improve Blood and Qi circulation, as well as sharpen the sensory nerves. Since all hand postures relate to the brain and the function and flow of the body's energy, they also have a psychological and physiological affect on the nervous system.

When training, posture and Qi movement are



Figure 15.39. Hands Open, Leading to the Spreading of the Qi



Figure 15.40. Hands Close, Leading to the Restraining of the Qi

sometimes in unity, and at other times proceed in opposite directions. Raising the arms, for example, causes the energy to rise; if the torso also rises, the rising power of the energy increases. This is an example of synergistic promotion of Qi regulation.

The following are three examples of the use of each separate hand action, and demonstrate how the body's reaction to energy can be used to treat patients with Medical Qigong therapy.

1. If you have hyperactive ascending Qi (e.g., hypertension) place your hands, palms facing downward, at the side of your body. Inhale quickly and move your hands quickly upward. Allow the middle fingers on each hand to touch each other, connecting the Pericardium Channels. Exhale, while slowly moving the hands downward along the front and side of the body. Purge and guide the Toxic Qi to descend the Liver and Gall Bladder Channels down the


Four Hand Techniques
(Ascend, Descend, Spread, Restrain)
Three Ranges
(Upper, Middle, Lower)
Four Front Directions
Yin and Yang Postures
Four Oblique Directions
Yin and Yang Postures

Figure 15.41 Hand Position Techniques

torso to the hips (GB-30), and then to the outside of the legs (Figure 15.42).

2. If you have a Yin and Yang imbalance (e.g., chronic illness) place your palms facing your Lower Dantian and slowly raise them upwards to the chest. At the level of the Heart, turn the palms away from the body as you move your arms outward. Once the hands are extended away from the body begin moving them downward. Regulate the speed of motion of the hands and breath in order to guide and induce the Clear Yang to ascend (as you raise your arms), allowing the Turbid Yin Qi to descend (as you lower your arms). This balances the body's Yin and Yang Qi (Figure 15.43).
3. If you have a Deficiency of ascending Qi (e.g., hypotension or prolapse of the viscera) begin with the palms facing upward, in front of your Lower Dantian. Slowly inhale while gradually raising the palms close to your body. When exhaling, move the hands downward quickly away from the body to avoid any excessive downward flow that would counteract the tonifying upward flow (Figure 15.44).

MEDICAL QIGONG WALKING THERAPY

Dynamic postural training can be performed by keeping the feet stationary and rocking the weight between the heels to the balls of the feet, or by walking. The Chinese saying, "The body must walk like the wind," describes the relaxed placement of the feet and supple stepping techniques used in Medical Qigong Walking therapy. Walking, or Toe-Raised Stepping, as it is commonly called in China, is excellent in treating the diseases of the Five Yin Organs. It can stimulate the Qi of the Spleen and Liver (due to their channels originating on the big toes), and can cause the body's internal Qi to rise and flow vigorously, thus reinforcing the function of Qi and Blood.

With each step of the Walking Meditation, the patient should practice tranquil mind and body balancing. This is the same imaginative technique as is used in standing, sitting, or lying meditations. The inner stillness and outer motion are in harmony. Touching the heel to the ground, with the



Figure 15.42. With palms facing downward (1), move the hands quickly upward (2). As the hands move slowly downward (3), allow the middle fingers on each hand to touch (4).



Figure 15.43. With palms facing the body (1), move the hands upward (2). Face the palms away from the body (3) as the hands move downward (4).



Figure 15.44. With the palms facing upward (1), raise the hands slowly close to the body (2). When moving the hands downward (3) in order to start again, quickly move them away from the body (4).

toes raised can also activate the Yin and Yang Heel Vessels (which originate from the center of the heel), and allow the energy to flow between both vessels so that the internal energy, exiting from the Yin Vessel, can enter the Yang Vessel, and vice versa. This allows the vessels to be dredged and the Yin and Yang energies to be regulated.

The heel is also stimulated when stepping, thus increasing the flowing action of the Bladder and Kidney Qi (due to their channel placement on the ankle). While stepping, focus the intention on the Lower Dantian to guide downward any abnormal rising of Lung Qi, which can cause shortness of breath, and affect the Heart and blood pressure. Each step is placed deliberately, with intention, and without collapsing of the feet. This stepping action relieves any Excess Qi syndrome of the upper torso and coordinates the balance of both the upper and lower portions of the body's Qi. Medical Qigong walking therapy consists of three training methods.

1. The Preparation (before walking), consists of the following steps:
   - The Opening and Closing of the Three Dantians, and
   - The Stationary Qi Strengthening and Regulating Exercises.
2. The Walking Therapy, consists of one or several prescriptions of the Toe Raised-Stepping techniques.
3. The Ending (after walking), consists of the following steps:
   - Leading the Qi back into the Lower Dantian,
   - Kneading the abdomen, and
   - Closing the Dantians and self-massage.

THE FUNCTIONS AND BENEFITS OF THE PREPARATION STAGE (THE OPENING AND CLOSING OF THE THREE DANTIANS)

Before beginning Medical Qigong Walking Therapy, the Opening and Closing of the Three Dantians must be practiced. In Medical Qigong training there is a saying, "When the body is Open, the Evil Qi will be expelled. When the body's surface is free from Evil Qi, it is better to Close it." The terms "opening" and "closing" refer to the purification of the body by means of Opening (purging) and Closing (sealing) specific areas of the body. The Opening and Closing of the Three Dantians can regulate either an Excess or Deficiency syndrome that is caused by an imbalance between the upper and lower, or interior and exterior parts of the patient's body. The purpose of the preparation stage is to:

- Eliminate the body's Evil Qi,
- Descend the Turbid Yin Qi, and
- Circulate the Clean Yang Qi through the organs and channels before walking.

The focus of this particular technique opens and closes the Upper Dantian (at the Yintang point), the Middle Dantian (at the Shanzhong CV-17 point), and the Lower Dantian (at the Qihai CV-6 point).

The Opening and Closing technique utilizes four specific disciplines:

- Using the Mind's Intention,
- Dividing the Yin and Yang Energy (ascending the Clear Yang Qi and descending the Turbid Yin Qi),
- The Hand Postures for Opening and Closing the Dantian, and
- The Focus on the Breath.

The Opening and Closing of the Three Dantians also requires multiple soft focusing that becomes easier with each practice session. Arm movements and the breath need to be perfectly coordinated; the expelling of Toxic Qi from the internal organs needs to be visualized; and the abdomen needs to be contracted while inhaling, and expanded while exhaling. The mind's intention must assist in the Opening and Closing of each Dantian, the coordinated movements alone do not suffice.

1. When focusing the mind's intention while performing the Opening and Closing techniques, imagine a dark Turbid energy from deep inside the body exiting through the body's pores. As the energy leaves, seal off the tissues to prevent it from returning to the body. Imagine the dark Turbid energy being absorbed into the ground, and being purified by the Earth.
2. The Dividing the Yin and Yang Energy refers

Practice of Creating the Compassion Fire and Multi-Orgasm

Compassion originates from the Heart



Fig. 6.8 *Smile until you feel the heart soft with love, joy and happiness.*

We can connect with the Universal Love.

1. Be aware of the Tan Tien and the universe and feel the unconditional love flow down.



Fig. 6.9 *Smile to the heart and the small intestine, to make the heart feel soft. Feel the heart pakua spiral.*

to separating the Yin and Yang energy within the body for healing. The Yin Qi stores the substance of vital energy, and the Yang Qi guards against pathogenic Evils and protects the body.

a. Ascending the Clear Yang Qi. When the Upper Dantian is Opened and Closed it allows the Clear Yang Qi to ascend to the upper orifices. The increased circulation of Clear Yang Qi through the channels and organs of the body stimulates and energizes the body's surface, as well as strengthens the four extremities. When the Clear Yang Qi moves upward its pure nature helps to tranquilize the Shen.

b. Descending the Turbid Yin Qi. When the Middle and Lower Dantians are Opened and Closed, it allows the Turbid Yin Qi to descend and facilitates the storing of the Clear Yang Qi.

3. The hand postures for Opening and Closing the Dantian is described as follows. The action for the Opening of Qi is directed by the outward movement of the hands and arms, and the mind's intent on Opening (or expanding) the abdomen.

   The Closing of Qi is directed by the inward movement of the hands and arms towards the abdomen, and the mind's intent on Closing (or contracting) the abdomen.

   The function of the Dao Yin Posture training, while regulating the breath and reinforcing the body's Qi, relies primarily on the movement of the hands and arms to arouse and invigorate the Qi circulating in the Large Intestine and the Lungs' channels. The action of opening and closing the Upper, Middle and Lower Dantians causes the Turbid Yin Qi to descend and be expelled, while the Clear Yang Qi ascends to the upper orifices of the body.

4. The focus is placed on the breath. The Opening and Closing exercise uses Reversed Breathing, i.e., the abdominal muscles contract while inhaling and relax and expand during exhalation (Figures 15.45 and 15.46).


Exhale while separating the hands and arms.
Expand the abdomen.

Figure 15.45. The Opening of Qi is directed by the outward movement of the hands and arms and an opening (or expanding) intention in the abdomen.

This method of breathing is also referred to as Daoist breathing. The action of abdominal compression acts as a bellow to purge any Toxic (Yin) Qi from the body. These contractions and expansions of the abdomen are combined with the mental focus on the Lower Dantian. The nerve plexuses in the Lower Dantian area are considered, in modern Medical Qigong theory, to connect the Tai Yang Channels (Major Yang channels). If the mind is concentrated on the Lower Dantian for a long period of time, a conditioned reflex will occur that causes the nerve plexuses to produce bioelectricity, which spreads into the surrounding areas of the Tai Yang channels. This reflex causes the small blood vessels and capillaries to dilate. This reaction reduces the pressure in the blood vessels and improves Blood circulation to the Heart.

- Contraindications:

  It is important to note that Reversed Breath-


Inhale while bringing hands and arms together.
Contract the abdomen.

Figure 15.46. The Closing of Qi is directed by the inward movement of the hands and arms toward the abdomen for a closing (or contraction).

ing is contraindicated for young children, older patients and for people suffering from high blood pressure, stroke, or Heart diseases. In these cases, the Reversed Breathing techniques should be replaced with Natural Breathing. When practicing with Natural Breathing, the patients imagine Heavenly Qi descending into their body, filling and expanding the Lower Dantian, as they inhale. This expansion of the abdomen (upon inhalation) allows their Lower Dantian to Open, causing the Heavenly Qi to naturally purge the body of Toxic Qi. Upon exhalation, the patients contract their lower abdominal muscles to Close and seal their Lower Dantian.

THE OPEN AND CLOSE THE THREE DANTIANS METHOD

Normally an exercise begins with an equal number of inhalations and exhalations receptively, as the arms move toward the body, and away from the body. In this particular exercise, however, when approaching each separate Dantian, the first Open and Close action is to be performed by inhaling through the entire movement, without any exhalation. This action stimulates the opening of the Dantians. For the second through fourth Open and Close movements, the patients exhale when Opening and inhale when Closing. Practice the Opening and Closing of the exercise, step by step.

- Begin from Wuji posture. Raise your arms and hands to face the Upper Dantian. As you inhale, sperate your arms outward away from the body as you contract the abdominal muscles, then while still inhaling, bring the arms back to the Dantian. Exhale as you separate the arms away from the Dantian, allowing the abdomen to expand, inhale and contract the abdomen as you bring the hands back together. Repeat this action two more times.
- Place your arms and hands in front of your Middle Dantian. As you inhale, separate your arms outward away from the body as you contract the abdominal muscles, then while still inhaling, bring the arms back to the Dantian. Exhale as you separate the arms away from the Dantian, allowing the abdomen to expand; inhale and contract the abdomen as you bring the hands back together. Repeat this action two more times.
- Place your arms and hands in front of your Lower Dantian. As you inhale, sperate your arms outward away from the body as you contract the abdominal muscles, then while still inhaling, bring the arms back to the Dantian. Exhale as you separate the arms away from the Dantian, allowing the abdomen to expand; inhale and contract the abdomen as you bring the hands back together. Repeat this action two more times.

STATIONARY REGULATING EXERCISES (PREPARATION FOR WALKING)

This next preparation exercise is good for the patient's general tonification and for increasing respiration for Lung cancer patients.

- Start from a Wuji posture, inhale and exhale through the nose. Place your palms facing your lower abdominal area and begin extending Qi into the naval. Imagine the energy flowing into your navel, extending deep into your Mingmen and Lower Dantian area (Figure 15.47).

- Next, face your palms toward the ground and absorb the Earth Qi into your Lower Dantian (Figure 15.48). Absorb the Earth's energy for a few minutes.
- Turn your palms upwards, towards the Heavens, and begin absorbing the Universal Qi for several minutes (Figure 15.49). Finally, begin to close the exercise by allowing your palms to turn back towards your navel, absorbing and rooting the Qi back into the Lower Dantian

WALKING COMBINED WITH COLOR THERAPY

In China, to help visualize specific colors for therapeutic use, patients will carry brightly colored silk ribbons while walking. The colors and their affect on the internal organs are matched in accordance with the Five Elemental colors.

WALKING COMBINED WITH SOUND THERAPY

In China, in order to help the patients step with a structured rhythm, coordinate breathing patterns, and improve mental intention, Medical Qigong practitioners beat large wooden drums, click wooden sticks, and clang large metal cymbals. These rhythmic wooden and metal sounds resonate the walking area with an energetic field vibrating with Yin and Yang Qi. The patients, while walking in a circle, naturally absorb the Yin and Yang energy resonating from the instruments and seek to naturally regulate their internal organs.

THE THERAPEUTIC EFFECTS OF MEDICAL QIGONG WALKING THERAPY

The purpose of "raising your toes when stepping" is to invigorate the Yin and Yang channels and vessels of the legs. The energetic nature of the Spleen necessitates walking slowly during this exercise. The Spleen is the source of Postnatal Energy and is responsible for the activity of the muscles and extremities. The movements of the four limbs therefore strengthen the Spleen; this is why "toe-raised walking" and the "hand swaying" methods have both been adopted into the exercises and postures of most Medical Qigong therapies.


Figure 15.47. Begin by placing the palms toward the navel, in order to stimulate the Lower Dantian Qi.

Waist rotation plays a leading role in regulating the Liver Channels, as well as invigorating the circulation of Kidney Qi. This is achieved through all activities that initiate the actions of dropping, bending, relaxing, and turning the waist.

The opening and closing actions, combined with the rising and falling movements, and the swaying action of all four limbs, promote a pumping action within the muscles. This action is further intensified with the bending and leaning of the upper body, squatting and crouching of the lower body, and the alternate weight shifting when stepping. This pumping action greatly benefits the circulation of the lymphatic system.

Clinically, the Medical Qigong walking exercises result in increased appetite, strengthening



Figure 15.48. Next, begin to absorb the Earth energy into the Lower Dantian and Mingmen areas.



Figure 15.49. Turn the palms up to absorb Heaven Qi into the Lower Dantian Area.

of the patient's body, tonification of the Kidneys, Lungs, Liver, and Spleen, and the strengthening of Heart function.

Cancer patients need to regulate the function of their tissues and Yin and Yang organs to increase their healing potential. The initial goal in treating cancer with Medical Qigong, is to have the patient focus on the condition of the tumor, and its collection of energy. The patient imagines that the tumor area is beginning to soften, and the tissues are gradually transforming back into insubstantial energy. This technique is used to gradually dissolve tumors and certain types of less aggressive cancer.

The following are examples of Toe-Raised Slow Walking therapeutic exercises and prescriptions used in Medical Qigong therapy:

- Dynamic Regulation Walking Therapy
- Lung Tonification Walking Therapy
- Kidney Tonification Walking Therapy
- Liver and Spleen Tonification Walking Therapy
- Heart Tonification Walking Therapy
- Cancer-treatment Prescriptions

The explanation of these walking and breathing exercises and prescriptions are described as follows:

1. Dynamic Regulation Walking Therapy is a good exercise for regulating the Yin and Yang Qi of the patient's entire body. It can be prescribed for general tonification and nourishing of the patient's body, as well as strengthening the "anti-pathogenic" or True Qi. The Dynamic Regulation Walking Therapy is the primary walking exercise used to treat cancer patients.

In every exercise the patient starts and ends with the Opening and Closing the Lower Dantian method. When stepping, the toes should be raised with the heels touching the ground (rocking back and forth), stimulating the Yin and Yang Heel Vessels of the legs, to strengthen the Kidney and Bladder Channels. As you step forward with the heel of the right foot, the Kidney and Bladder Channels open up. Swing your left hand up to the center of your Heart (CV-17 point) while your right hand swings to your right hip around and near the GB-30 point (Figure 15.50).

It is important to utilize the mind's concentration in conjunction with the breath. The breathing pattern is as follows:

- First step—inhale through the nose
- Second step—inhale through the nose
- Third step—exhale through the mouth
- Fourth step—hold the breath

The same details of stepping and hand movements apply to stepping forward with the left foot.

2. Lung Tonification Walking Therapy is a good exercise for tonifying the Qi of the patient's entire body. It can be prescribed for nourishing the patient's skin, as well as strengthening the True Qi. It is used for treating Lung Qi Deficiencies, bronchitis, tuberculosis, asthma, emphysema, and sinusitis.

The heel stepping pattern is similar to the Dynamic Regulation Walking exercise, however, when stepping, the hand postures will now switch from a normal relaxed position to the thumbs and first fingers touching at the tips (Figure 15.51).

Some Medical Qigong hospitals encourage the patients to rub their thumb and index fingers together when practising the Lung Tonification Walking Therapy. This rubbing action causes friction to develop between the Shaoshang Lu-11 and the Shangyang LI-1 points, which in turn stimulates and invigorate the flow of Qi along the Lung and Large Intestine Channels, strengthening the Lungs.

The breathing pattern is as follows:

- First step—inhale, inhale
- Second step—inhale, inhale
- Third step—exhale
- Fourth step—no breath

3. Kidney Tonification Walking Therapy. This exercise will purge the Liver Fire and tonify the Kidney Yin. It can be prescribed for patients who suffer from Kidney Qi Deficiencies, edema, blood diseases, gynecological diseases, and cancer of the Kidneys.



Figure 15.50. With each step, the opposite hand swings up to the Heart and Middle Dantian area.



Figure 15.51. Tonification Hand Position for the Lungs

Begin this exercise with the palms embracing an imaginary ball at the naval and Lower Dantian area. This walking therapy causes the Qi to tonify your Lower Dantian.

Step forward so that the toes of the right foot touch the ground first, followed by the heel. This stepping action will open up the Yang Channels on the outside of your foot. Next, step with the left heel and point the toes up. This stepping pattern should be toe, heel, then step with heel (Figure 15.52).

On the first step, inhale through the nose while imagining the Qi filling your thorax. On the second step, sound the tone "Xu" (pronounced Shu) as you exhale. This particular sound is used to purge Toxic Liver Qi out the patient's body, allowing the Kidneys to fill with the rising Earth Qi.

- First step—inhale
- Second step—exhale "Shu"

The breathing pattern is as follows: inhale for the toe and heel, step and exhale on the heel step (all three actions equal one set). After walking in a circle for nine complete rotations, pause and begin again, starting with the left foot as the downward foot that makes the toe heel step as you exhale.

While stepping, keep both palms on your Lower Dantian. Regulate your breathing, while drawing the Earth Qi upward from the Yongquan Kd-1 point at the bottom of each foot. Press the Mingmen area backwards while breathing in the Earth Qi; this reinforces the Kidneys' Yuan Qi.

When ending the Kidney exercise, place both hands at the center of your chest at the CV-17 point. For men the right hand is on the outside, the left hand is on the inside, touching the chest. The hand position is opposite for woman. Make the sound "Shu" three times. End with the Opening and Closing of the Lower Dantian.

4. Liver and Spleen Tonification Walking Therapy activates the Liver's function of storing Blood and the Spleen's function of transforming Blood. It is used to treat digestive and blood diseases, hepatitis, Liver cancer, sclerosis of the Liver, and Gall Bladder stones.



Figure 15.52. The Kidney Strengthening Step is as follows. While stepping, place both palms on the Lower Dantian, regulate your breath and draw the Qi upward from the bottom of each foot. Press your Mingmen area backwards while breathing in the essence of the Qi.

The starting position is similar to the exercise for tonifying the Kidneys with the toes pointing down, except that you step forward with the left toes. Step forward so that the toes of the left foot touch the ground first followed by the left heel. While this step is taken inhale twice through the nose. Then step out 45 degrees with the right heel while inhaling twice more through the nose. Next, step out with your left heel 45 degrees, exhale through your nose twice, then step out with your right foot with the toes pointed down as you exhale once.

- First step—inhale, inhale
- Second step—inhale, inhale
- Third step—exhale, exhale
- Fourth step—exhale

When walking with the toes raised, let the big toe touch the ground to stimulate the Yinbai Sp-1 and the Dadun Lv-1 points on the big toe. This promotes the ascension of the Qi flowing upward along the Liver and the Spleen Channels. The internal energy of these two channels is then reinforced, and the Liver and Spleen are strengthened.

After walking in a circle for nine complete rotations, pause and begin again starting with your right foot. Spleen and Liver Channels are activated when the toes pull up and the heel steps down.

The hand postures are as follows:

a. For Spleen problems the thumbs touch your ring fingers only when you step out to the fourth step (Figure 15.53).
b. For Liver problems the thumbs continuously touch your ring finger.

5. The Heart Tonification Walking Therapy calms the mind while tonifying the Qi and Blood. It is used for treatment of coronary Heart diseases, arthritis, palpitations, and angina pectoralis.

The starting position is the same as for the Liver and Spleen Walking therapy. The stepping is exactly like the last exercise, with the exception of the hand positions. In this exercise, the hands are opened and relaxed until they reach the chest (CV-17 point) at which point the middle fingers of each hand touches the Pc-8 point at the center of each palm (Figure 15.54).

When breathing, focus your Mind on inhaling the Qi upward from the Earth. When exhaling, imagine that the Qi within your chest is flowing downward.

- First step—inhale
- Second step—exhale

This walking exercise is practiced at a slightly slower speed then the previously described exercises. On the third step, the middle finger of each hand touches the center of your palms. This stimulates the Zhonchong Pc-9 point on each finger and is used to invigorate the flow of internal energy along the Pericardium Channels.

THREE STEPPING METHODS USED TO TREAT CANCER

These supplementary Medical Qigong Step-


Figure 15.53. Hand Position for Tonification of the Liver and Spleen


Figure 15.54. The Heart Strengthening Step is practiced at a slightly slower speed. On the third step, the middle finger of each hand touches the center of the palm.


The Fast Walking Method
(for Liver, Lung and Stomach Cancer)
1st Step - Inhale
2nd Step - Exhale
70 - 100
Steps per Minute
The Moderate Walking Method
(for Gastric and Intestinal Cancer)
Inhale - Exhale
Each Step
60 - 80
Steps per Minute
The Slow Walking Method
(for Kidney and Urogenital Cancer)
Each Step
Inhale - Inhale - Exhale
Heel
Toe
Under- 60
Steps per Minute

Figure 15.55. Cancer Walking Therapy

ping exercises are given to cancer patients for breath regulating and Qi reinforcement. These breathing methods are applied with the Dynamic Regulation Walking therapy (the first walking exercise taught in this section). These walking methods use the "exhaling method" to strengthen the Kidneys, increase oxygen intake and enhance the patients' immune system.

The stepping methods are performed at three different speeds depending on the patients' symptoms (Figure 15.55). The patients are encouraged to walk at least once a day for 15-20 minutes. These walking exercises are classified into three kinds of prescriptions according to the following breathing rates.

THE FAST EXHALING METHOD

This walking method is mainly prescribed for patients in the early stages of cancer and is especially suitable for patients with Liver, Lung, and Stomach cancer. This exercise is practised using even breathing, inhaling for one step, followed by exhaling for another step. The patient steps out with the left foot, while inhaling through the nose. Then steps out with the right foot, and exhales through the nose. Both hands swing naturally up to the chest, while walking.

The main point to remember while stepping, is that the head leads the waist in turning and swinging the arms. The speed should be 70-100 steps per minute. When practicing the Fast Exhaling method it is important not to overexert yourself, as this would be counterproductive, and would lead to depleting the immune system.

THE MODERATE EXHALING METHOD

This walking method is mainly prescribed for patients in the early stages of cancer and is especially suitable for patients with gastric and intestinal cancer. The patient breathes in and out through the nose with each step taken. When taking each step, focus is on the respiratory rhythm. The speed should be between 60-80 steps per minute.

THE SLOW EXHALING METHOD

This walking method is mainly prescribed for patients with Kidney and urogenital cancer. The patient steps out with the left foot first and then with the right foot. Each step is accompanied by two inhalations and one exhalation. The patient steps out with the heel while taking two inhalations and then touches the ground with the ball of the foot, while exhaling. Because one step involves three breathing movements, the walking speed should be a bit slower, under 60 steps per minute.



Figure 15.56. Secure the Upper and Middle Dantians in order to come to a tranquil state of relaxation.

ENDING AND CLOSING THE WALKING THERAPY

To end the Medical Qigong Walking therapy, the following exercises are taught to the patients in order to bring their Qi back into their Lower Dantian and to return to a state of quiescence. The Ending and Closing procedures are divided into three forms of practice: (1) Leading the Qi back into the Lower Dantian; (2) The official Closing of the prescription; and (3) Self-massage Regulation. These three ending procedures are described as follows.

LEADING THE QI BACK INTO THE LOWER DANTIAN.

This particular exercise is divided into four separate stages: (1) Securing the Three Dantians, (2) Kneading and Rooting the Lower Dantian, (3) Circle Massaging the Lower Dantian, and (4) Rooting the Qi.

1. The Securing the Three Dantians exercise has three purposes: to initiate a tranquil state of relaxation, to secure a harmonious balance of the body's Yin and Yang organs, as well as to bring the Qi back into the Lower Dantian.

   From a standing Wuji Posture, imagine embracing a ball of energy at the Lower Dantian (hold this posture for several breaths). After exhaling, separate the hands without inhaling, moving, and massaging the Qi along the hub of the body's Belt Vessel (at the waist).

   Inhale and begin raising the palms above the head. Imagine inhaling the Earth Qi into the body while the palms are facing the ground. At hip level, rotate the palms to face the sky, and begin inhaling Heaven Qi into the body. Continue raising the palms until they are positioned above the Baihui area on top of the head (left hand on top, opposite for women).

   Exhale and imagine the combined Earth and Heaven Qi flowing into the Taiji Pole, connecting all Three Dantians together. Descend the palms in front of the body, facing the Yintang, throat, Heart, upper abdomen (at the Yellow Court), and navel, then end by embracing the Lower Dantian. Begin again and repeat this exercise nine times (Figure 15.56).
2. Kneading and Rooting the Lower Dantian fills the Liver and Spleen with Blood and Qi, helping to further detoxify these organs.



Figure 15.57. Knead the abdomen 36 clockwise then 24 counterclockwise.

After performing the Securing the Three Dantians exercise, secure the Qi in the Lower Dantian and knead the abdomen until it is sufficiently stimulated.

3. Circle Massaging the Lower Abdomen combines the body's organ energy together, thus forming the One True Qi. This allows the body to alleviate any Excess or Deficient conditions which may be caused from the excessive accumulation of Qi, due to the previous Qigong Walking exercises.

   Begin at the navel and start to circle massage the lower abdominal area thirty-six times in a counterclockwise direction (the movement should be directed against the flow of Qi in the Large Intestine). Begin with small and end with large circles, completing the movements at the base of the Lower Dantian. Next, reverse the direction of Qi flow by circle massage twenty-four times in a clockwise direction (with the flow of the Large Intestine), starting with big and finishing with small circles that end at the base of the Lower Dantian (Figure 15.57).

4. Rooting the Qi is sometimes referred to as "leading the Qi back to its origin." Rooting, extending, and stabilizing the energy into the Lower Dantian will facilitate the regulation of the Conception Vessel, Lower Burner, and Water pathways. Rooting the Qi also tonifies the Kidneys, Qi, Blood, and Yuan Qi, and allows the Toxic Qi to be easily expelled from the body.

   Leave the hands on the Lower Dantian and push the Mingmen backwards while inhaling the Qi and heat from the hands into the Lower Dantian (right hand on outside, opposite for women).

THE CLOSING

The closing procedure should be initiated after each practice period. After three deep breaths, click your teeth together thirty-six times (to stimulate the Kidney Qi), then circle the tongue eighteen times in each direction (to stimulate the Spleen Qi). Circle thirty-six times from the bottom of the teeth to the back of the throat. Tilt your head forward slightly, then swallow the saliva three times while imagining the Clear Qi of Heaven and Earth mixing with the saliva and flowing down to the Lower Dantian.

SELF-MASSAGE REGULATION

This method shifts the attention slowly off the area of concentration, while leading the Qi back down to the Lower Dantian. After the mind disengages from the specific point, relax the body, slowly open the eyes and perform self-massage.

Self-massage includes rubbing the hands, bathing the face (rubbing the face with the palms), combing the hair with the fingertips, and dredging the Twelve Primary Channels.

1. After rubbing the hands to heat the palms, place both hands on the face, cup the eyes, and draw the heat in through the eyes, into the Upper Dantian.
2. Next, comb the hair with your fingertips and drain the Excess Qi from off the head and neck area (Figure 15.58).
3. Then, rub from the feet to the abdomen to dredge the three Yin channels of the feet (Figure 15.59).

2. Smile to the spleen and let the love, joy and happiness from the heart activate the openness and fairness.



Fig. 6.10 *Let Positive Heart Energies activate Positive Spleen Energies.*

3. Let it flow back to the heart pakua and spiral, blend together and feel the yellow light flow from above and flow down to the heart.



Fig. 6.11 *Blend the Two Energies with Universal Energies.*



Figure 15.58. After rubbing the hands to heat the palms, place both hands on the face and draw the heat in through the eyes and into the Upper Dantian (1). Next, comb the hair with the fingertips (2), and drain the excess Qi from the head and neck area (3).

4. Rub from the chest to the hands to dredge the three Yin channels of the hands (Figure 15.60).
5. Rub from the hands, shoulders and lateral sides of the head, down the sides of the chest and abdomen to dredge the three Yang channels of the hands (Figure 15.61).
6. Rub from the waist and hips to the feet to dredge the three Yang channels of the feet (Figure 15.62).

These closing and self-massage procedures should be performed seven times each, followed by stretching to end the exercise.



Figure 15.59. Rub from the feet to the abdomen (1–2) to dredge the three Yin channels of the foot.



Figure 15.60. Rub from the chest (1) to the hands (2-3) to dredge the three Yin channels of the hand.



Figure 15.61. To dredge the three Yang channels of the hand, rub from the hands (1), shoulders (2), and lateral sides of the head (3).



Figure 15.62. Continue down the sides of the chest (1) and abdomen (2). Next, rub from the waist and hips (3) to the feet (4) to dredge the three Yang channels of the foot.

CHAPTER 16
RESPIRATORY DAO YIN

THE PURPOSE OF RESPIRATORY DAO YIN

Respiratory Qigong therapy is often called Tu Gu Na Xin which means "expelling the old, drawing in the new." The purpose of Respiratory Dao Yin is to increase the intake and absorption of Clear Qi through regulating the breath. The extra absorption of Qi enhances the body's vitality, and harmonizes the Blood and Qi to promote health and eliminate disease.

Because the breath is also the link between the body and mind, by controlling the pace and quality of the breath, individuals can affect deep changes in their physiological functions. Breathing exercises have proven to be effective in reducing anxiety, depression, irritability, muscle tension, and fatigue. These techniques are also used in the treatment and prevention of agoraphobia, hypertension, hyperventilation, shallow breathing, and cold hands and feet.

THE ROLE OF THE LUNGS IN QI CULTIVATION

The Lungs control the body's Qi, although the Kidney Qi is responsible for aiding the Lungs by regulating the respiration (i.e., upon inhalation, as the Qi descends into the thorax, the Kidneys hold down and stabilize each breath). The Yuan Qi stored in the Kidneys must be continuously supplemented by the Gathering Qi derived from air, food, and water.

The internal absorption of air, food, and water rely on the smooth circulation of the Lungs' energy. Because of the significant role the Lungs play in absorbing universal and environmental Qi, the ancient Qigong masters placed a great deal of importance on breathing exercises. They believed that a patient's health and emotional condition were deeply affected by their breathing patterns, and by the amount of oxygen consumed in proportion to the amount of carbon dioxide released.

Through the study of these ancient Qigong observations, modern research confirms that relaxed and natural breathing patterns cause every tissue and cell to decrease its consumption of energy, while increasing its storage of Qi.

The ancient Qigong masters recommended that "vigorous breathing," in the form of Dynamic Breath Regulation, should be used when training Qi, and "gentle breathing," in the form of Quiescent Breath Regulation be used after training practice for nourishing and replenishing the Qi. Each breathing regulation exercise has long been considered a powerful prescription used to balance the patient's health.

DEEP INHALATION AND EXHALATION BREATHING METHODS

In breathing regulation exercises and prescriptions, the patient's inhalation is used to gather universal and environmental Qi into the body for tonification. Exhalation is used to eliminate Turbid or Toxic Qi from the body through purgation. Once the patients are in the prescribed posture, relaxed and free from distractions, they should, for example, exhale and imagine releasing Turbid Qi from out the mouth, nose, and pores of the body.

Clinical studies show that the Deep Inhalation of Medical Qigong prescriptions can have the following effects on the patient's body:

- increase stimulation of the sympathetic nervous system,
- cause the blood vessels to contract,
- raise the blood pressure, and
- increase the pulse rate.

On the other hand, the Deep Exhalation methods of Medical Qigong prescriptions can also have the opposite affects on the patient's body:



Dao Yin Breathing

1. Natural Abdominal Breathing Method
(increases Qi in the Kidneys and Lower Dantian)

2. Long and Deep Abdominal Breathing Method
(calms the Shen and creates feelings of euphoria)

3. Reverse Abdominal Breathing Method
(increases Qi flow to the extremities)

4. The Deep Exhalation Method
(excites the parasympathetic nerves, dilates the blood vessels and decreases blood pressure)

5. Abdominal Breath Holding Method
(invigorates the circulation of Blood and quickly improves the microcirculation of Qi and Blood)

6. The Windy Breathing Method
(stimulates the pituitary gland, and strengthens and regulates the endocrine system)

7. The Aspirating Method
(purges the internal organs of pathogenic factors)

Figure 16.1. The Seven Dao Yin Breathing Techniques

- increase the stimulation of the parasympathetic nervous system,
- dilate the blood vessels,
- lower the blood pressure, and
- decrease the pulse rate.

Deep exhalation helps to keep the body's Yin energy moving downward, and so has a downward regulating action on diseases caused by Yang Qi domination. Deep inhalation helps to keep the body's Yang energy moving upward, and has the effect of sustaining the Yang and tranquilizing the mind.

Students beginning Medical Qigong practice should focus their mind's intention primarily on the method of exhalation, to simultaneously stimulate the parasympathetic system and to relax. Once health is regained, patients will begin to alternate between deep inhalation and deep exhalation. This alternation produces a diastolic and systolic action of the blood vessels that also enhances the elasticity of the blood vessels' walls.

SEVEN DAO YIN BREATHING TECHNIQUES

The Seven Dao Yin Breathing Techniques are intended to regulate the symptoms caused by the Excess of Yang and Deficiency of Yin, which are characterized by too much energy in the upper part of the body and a weakness in the lower portion of the body.

Today, in China's Medical Qigong clinics, the breathing regulation exercises employ seven types of Dao Yin breathing techniques (Figure 16.1). Normally, all inhalation is done gently through the nose and exhalation is released slowly through the mouth. Inhalation and exhalation through the nose is also important, but should only be used when a higher state of "stillness" is obtained by the patient. This is to prevent the patient from falling back into his or her old shallow breathing patterns, until the Deep Abdominal Breathing method has been perfected.

1. The Natural Abdominal Breathing Method is also called Natural Breathing, and is used in

conjunction with mental concentration. In this method the abdomen expands upon inhalation and contracts upon exhalation. It naturally increases the body's peristaltic action, massages the internal organs, invigorates and increases the movement of Qi from the Kidneys into the Lower Dantian. Because of the differences in energetic physiology between men, women, and the breathing habits of each individual, Natural Breathing is further divided into Natural Thoracic Breathing, Natural Abdominal Breathing, and a combination of the two.

2. The Long and Deep Abdominal Breathing Method is also called Wen Huo Breathing. It is a gentle breathing method that consists of natural, deep, and full breathing. This results in a relaxed and comfortable feeling of euphoria. This method of breathing is performed as follows:
   a. At the beginning of the breath, inhale all the way down into the perineum, feeling the lower abdomen expanding in all six directions:

- from the bottom - at the base of the perineum,
- from the front - to the pubic bone and navel,
- from the back - to the coccyx and Mingmen,
- from the right - to the hip and lower ribs,
- from the left - to the hip and lower ribs, and
- from the top - at the base of the diaphragm.

   b. While continuing to inhale, feel the oxygen expanding and filling the upper thoracic cavity completely. The entire torso, from the perineum to the collar bones is expanded in six directions:

- from the bottom - at the top of the diaphragm
- from the front - to the solar plexus, Heart, and collar bones,
- from the back - to the base of the ribs, spine and top of the shoulders,
- from the right - to the rib area,
- from the left - to the rib area, and
- from the top - to the throat and neck area (Figure 16.2).

   c. Upon complete expansion, tuck the pelvic bowl under to increase the capacity of storing more energy. On the inhalation the pelvis performs a slight posterior tilt, on the exhalation the pelvis tilts slightly in the anterior direction. These actions will naturally ripple the spine. Exhale the breath from the upper thoracic cavity downward, to the lower abdomen.



Figure 16.2. Inhale all the way down to the perineum. Make sure that the anal sphincter is closed in order to keep the Qi full and expanded in the Lower Dantian.

3. The Reverse Abdominal Breathing Method is an example, and subcategory of Long and Deep Abdominal Breathing. This method is performed by contracting the abdomen (and anus) when inhaling and expanding the abdomen upon exhaling. This is the primary breathing method used in Qigong training for guiding and emitting Qi, because the quality of air pressure and exertion of energetic pressure is greater. The Reverse Abdominal Breathing method results in superior efficiency in leading Qi to the extremities and has a much greater effect in raising the Qi from the legs into the brain.

However, when prescribing Medical Qigong therapy to treat diseases and alleviate physical stress, the Reverse Abdominal Breathing Method is prohibited except for very specific conditions. The reason it is not encouraged in Medical Qigong prescriptions is because patients with clinical hypertension or Heart disease often practice Reversed Breathing automatically. Scientific studies confirm that 90% of these patients practice reverse breathing chronically, as do most individuals with anxiety problems. Reverse Abdominal Breathing can also cause a constriction of the blood vessels and thus exacerbate problems such as cardiac diseases (i.e., angina) and migraine headaches.

4. The Deep Exhalation Method is often referred to as Wu Huo, which means "vigorous breathing." It is conducted with strong conscious intent. It can excite the parasympathetic nerves, dilate the blood vessels and decrease blood pressure.

   When practicing the Deep Exhalation method, the patient expels the Qi through the mouth, followed by a shallow inhalation.

5. The Abdominal Breath Holding Method invigorates the circulation of Blood and reduces swelling within the tissues, quickly improving the microcirculation. This method is also used to deepen the breath by stopping or holding the respiration for a short period of time.

   One Abdominal Breath Holding Method, known as Two Breathings, consists of inhaling through the nose, deep into the Lower Dantian, with one breath, pausing, then exhaling out through the mouth. The pause should be sustained for as long as possible without feeling tension (although a feeling of slight pressure building up is normal). After practicing deep abdominal breath holding, the breath will begin to develop its own stopping patterns. This stage involves the discipline and interdependence of the Heart and mind (Emotion and Spirit) with the breath.

6. The Windy Breathing Method consists of inhaling and exhaling through the nose. It is often referred to as "Windy" because it employs shallow breathing which resonates in the nasal passages. This kind of breathing purifies and warms the air as it passes through the nasal tract, resulting in air oscillation which stimulates the pituitary gland, thus strengthening and regulating the endocrine system. This method is designed to be used by patients with Lung disease because "the Lung energy opens at the nose."



Figure 16.3. An example of tone resonation by aspirating the body's Excess Heat from the Liver is by using the sound "Shu."

7. The Aspirating Method refers to the method of drawing out by suction. This popular method can be used with healing sounds (or "tones") to purge pathogenic factors, or to regulate the body's internal organs. The pronunciation is based on resonating the sounds to stimulate specific organs such as the Heart, Spleen, Lungs, Kidneys, Liver and Triple Burners (Figure 16.3). There are two primary



Figure 16.4. The body has seven main spatial cavities, as well as individual spatial cavities that surround the Yin and Yang organs.

sound systems of tone resonation used in Medical Qigong therapy, The Six Healing Sounds and the Tumor and Cancer Tone Resonations. These two healing sound methods are described as follows.

- The Six Healing Sounds are used to regulate, strengthen or detoxify the body's Yin and Yang Organs. This healing sound system is generally prescribed for patients with acute, or less serious conditions such as indigestion, insomnia, or Excess Heat in the organs, etc.
- Tumor and Cancer Tone Resonation Therapy is used to vibrate and destroy malignant tissue and cell growth in patients with chronic and serious organ diseases (see Chapter 40). This healing sound system is prescribed for diseases such as cysts, tumors, and cancer.

The choice of organ, and the number of times to pronounce each sound or character, is determined by the physical and energetic constitution of each individual. Each sound vibrates a specific organ or organ system, and surrounding set of involuntary muscles. Through repetition, the muscles acquire a kinesthetic memory of the vibrational sound. The doctor, or patient, can then trigger this memory by mental concentration alone to produce the desired results. As the patient performs the Sound Therapy, not only are the channels and organs cleansed, but also the spatial cavities (or Orbs) which surround the specific organs (Figure 16.4). For more information on Sound Therapy, see Chapter 40.

RESPIRATORY GUIDING AND REGULATING

There are four Respiratory Dao Yin methods the Qigong doctor can prescribe to regulate the


Respiratory Dao Yin Breath Regulation Methods
1. The Counting the Breath Method
2. The Following the Breath Method
3. The Observing the Breath Method
4. The Listening to the Breath Method

Figure 16.5. The Four Methods to Prescribe Respiratory Dao Yin For Breath Regulation

patient's breath (Figure 16.5): Counting the Breath, Following the Breath, Observing the Breath, and Listening to the Breath.

1. The Counting the Breath Method can be utilized to eliminate distractions of the mind during Walking Qigong Therapy by having patients silently count the number of their breaths. This method is also performed silently to regulate the body. In this particular method, one inhalation and one exhalation equals one breath.
2. When practicing the Following the Breath Method, the patients will contemplate each inhalation and exhalation of breath without counting. The patients mind, free from distractions or thoughts, follows each breath into and out of the body.
3. When practicing the Observing the Breath Method, the patients will observe their body's tissues conforming to the tranquil mental images from their subconscious imagination (e.g., relaxing, sinking, etc.).
4. When practicing the Listening to the Breath Method, patients are encouraged to listen to the "sounds" of their breathing (used in the Windy Breathing Method) to achieve a state of tranquillity.

RESPIRATORY TONIFICATION AND PURGING METHODS

Medical Qigong Respiration Therapy has its own unique methods and techniques for tonifying and purging the body's Qi. The primary technique used is focused concentration on the breathing. Through breath regulation, syndromes of Excess and Deficiency may be brought into balance either through tonification or through purgation.

1. Inhalation is used for tonifying the Qi in cases of Deficiency. The duration of the patient's inhalation should be longer than that of the exhalation. Tonification or Qi reinforcement patterns are created by applying the following methods:
   - more inhalation, and less exhalation
   - long inhalation, and short exhalation
   - focusing the mind on the inhalation
2. Exhalation is used for purging and reducing the Qi in cases of Excess. The duration of the exhalation should be longer than that of the inhalation. Purgation or Qi reducing patterns are created by applying the following methods:
   - more exhalation, and less inhalation
   - long exhalation, and short inhalation
   - focusing the Mind on the exhalation

BASIC ESSENTIALS OF RESPIRATORY TRAINING

Medical Qigong Respiratory training consists of the regulating, tonifying or purging exercises practiced in accordance with the doctor's treatment and specific homework prescriptions. There are four basic essential guidelines used to assist the patient in achieving maximum results in respiratory therapy, these guidelines consists of: Ensuring the Correct Posture Before Beginning, Purifying and Cleansing the Body's Qi, Tonifying and Purging the Qi, and Regulating the Body's Qi.

1. Before beginning Respiratory Dao Yin training, it is important that the doctor make sure the patient's posture is correct. When prescribing dynamic and static Medical Qigong therapy, it is best to start with a solid foundation and proper structure. Breath training should only begin when the patient becomes proficient in Postural Dao Yin, otherwise adverse effects may occur, (i.e., emotional trauma, headaches, chest stuffiness, or respiratory distress).
2. After their posture has been corrected, have the patients open their mouth and focus on their exhalation. As the patients exhale, they imagine all of the obstructed channels and collaterals being simultaneously purged of Turbid Qi. Each time the patients exhale they are to relax their body, more and more.

   Next, the patients close their mouth, and focus on inhaling clean, fresh Qi in to their body (through the nose). Have the patients practice this method using Natural Breathing. Each time the patients inhale and exhale they are to continue to relax the body.
3. After the body's Qi has been cleansed, the patients will focus their intention on any and all internal organs that specifically need to be purged. Breathing exercises used for purgation include focusing the patients' intention on the exhalation, as well as exhaling specific healing sounds. The patients continue to purge their body in this manner in accordance to the doctor's instructions.

   Having completed the purgation exercises, the patients are free to begin their tonification prescriptions. Breathing exercises used for tonification include the focus of the patients' intention on the inhalation, as well as visualizing specific colors being ingested into certain internal organs.
4. After practicing the tonifying or purgation prescriptions, the final goal of respiratory training is to achieve a long, natural, even and deep respiration. Urgent respiration causes the body's internal Fire to escape into the pores, resulting in uncontrolled Heat, feverish conditions and irritability. Normal breath regulation consists of even inhalation and exhalation patterns. The patient must avoid speeding up their breath, as this will also interrupt the breathing rhythm and lead to deviations of Qi.

BREATHING PATTERNS FOR COLLECTING AND REGULATING QI

The following are examples of exercises used for regulating and collecting Qi in the Lower Dantian. The doctor or patient will perform the breathing patterns as follows:

1. Collecting Qi in Lower Dantian is used to tonify and increase the collection of Qi gathered in the Lower Dantian.
   a. Inhale through the nose, filling the lower Dantian (expanding the abdomen), pause, then exhale through the mouth. Repeat and continue this breathing pattern for three times then proceed to b.
   b. Take three partial inhalations through the nose, filling the lower Dantian, pause, then complete one exhalation through the mouth. Next, inhale 50% of the breath into the Lower Dantian (expanding the abdomen), hold for three heartbeats, inhale remaining 50% into the Lower Dantian and hold for five heartbeats, relax and slowly exhale. Repeat and continue the pattern for thirty minutes a day (for three months), or until it becomes effortless.
2. Regulating Qi in Lower Dantian is used to stabilize the energetic balance of the Lower Dantian.
   a. Inhale through the nose, filling the lower Dantian (expanding the abdomen), exhale through the mouth, and

4. Smile to the lungs and the large intestine. Send love from the heart to the lungs to activate courage and righteousness.



Fig. 6.12 *Let Love and Joy from the Heart activate Positive Lung Energies.*

5. Let it flow to the heart, spiral and blend with love, joy, happiness, openness and courage. Blend the three energies into one energy, and feel the white light from above flow into the lungs and the heart.



Fig. 6.13 *Blend the Three Energies into One Energy.*

then pause. Repeat and continue this breathing pattern for three times then proceed to b.

   b. Inhale through the nose, then perform three partial exhalations through the mouth, pause, then one complete inhalation through the nose. Next, exhale 50% of the breath out of the Lower Dantian (contracting the abdomen), hold for three heartbeats, exhale remaining 50% out of the Lower Dantian and hold for five heartbeats, relax and slowly inhale. Repeat and continue the pattern for thirty minutes a day (for three months), or until it becomes effortless.

3. The Mysterious Pass is the pause between the inhalation and the exhalation. The ancient Qigong Masters believed that in the pause was the realm of infinite space (Wuji), existing between the Earthly Heaven (the congenital form of energy) and the Later Heaven (the acquired form of energy) where time and space stands still.

   For clinical practice, the Qigong doctors train in the method of accessing the Mysterious Pass in order to extend Qi through the entire body and to access the energy of the Wuji (Infinite Space). In the clinic, the training is divided into two stages (a and b).

   a. Begin this training by holding the breath from three to twelve counts (known as the "Small Count Breathing Regulation").
   b. Eventually increase to the "Big Count Breathing Regulation," which consists of 120 counts. This method enriches the Yuan Qi by breathing in more and exhaling less, and is sometimes used in Medical Qigong prescriptions to cure specific types of illness. When used with a strong intent, breath holding can constrict the blood vessels and raise the blood pressure; it is therefore sometimes prescribed for patients with hypotension. This Qigong method is, however, contraindicated for patients or doctors with hypertension.

THE FOUR PROGRESSIVE STAGES OF RESPIRATION

There are four progressive phases of difficulties that patients may experience during the beginning stages of their Medical Qigong Respiratory training: The Wind Phase, The Gasp Phase, The Unbalanced Air Phase, and The Quiescent Phase.

1. During the Wind Phase, the breathing is audible and may prove distracting to a beginner. The goal of focused concentration is to allow the energy to become gathered and collected. If the goal of the breathing prescription is to focus on a Deficient internal organ or specific tissue area, for example, and the patient's concentration becomes diverted (shifting to the noise of their own breath), it may disrupt the patient's mind. This can result in the patients collected Qi being dispersed instead of gathered.
2. During the Gasp Phase, the breathing is no longer audible, but any stagnant air, or obstructed air in the throat may disrupt the mind's concentration. Focused concentration on the stagnant air or obstruction may cause a sense of physical obstruction and mental anxiety, resulting in Qi stagnation in the throat (known as Plum Pit Qi).
3. During the Unbalanced Air Phase, the breath remains silent and there is no sensation of obstructed air in the throat. The patient's breathing, however, may be uneven, or unbalanced. Focused concentration at this phase may cause strain in the patient's mental awareness. If the mind becomes overstrained (trying to balance the inhalations and exhalations) the result will be fatigue.
4. During the Quiescent Phase, patients are able to achieve a long, natural, even and deep respiration without sound or stagnation, resulting in a state of extreme quietness. Concentration on this phase will result in a restful peace of mind.

DURATION TIME FOR RESPIRATION THERAPY

Patients in relatively good health should practice for about five minutes a day in the first week, when seeking to regulate their body's internal energy. In the second week patients should increase to ten minutes a day, and in the third week, fifteen minutes a day. Thereafter, five more minutes each day should be added until the patients reach a minimum of twenty minutes and a maximum of forty minutes per day for optimal Qi development.

When treating patients (for general tonification) using multiple standing meditation postures, have them begin by counting up to sixteen breaths per each posture. As the patients progress, the respiratory rate during meditation begins to slow down naturally. Normally, within a few months of training, respiratory rate drops from an average of sixteen breaths per minute, to three or five breaths per minute. This naturally increases the time spent in each posture, extending each posture from one to five minutes in duration.

Qigong doctors, on the other hand, should practice a minimum of forty minutes of standing posture each day to recharge and increase the efficacy of their treatments.

EMOTIONAL EFFECTS ON BREATHING PATTERNS

Breathing patterns are directly related to both the patients' thoughts and emotions. Any shift in one will affect the other. Each of the five primary emotions is associated with a specific breathing pattern as follows.

1. An angry patient's exhalation will be much stronger than the inhalation.
2. A grieving or sad patient's inhalation will be much stronger than the exhalation.
3. A fearful or scared patient's breathing will be fast, held high in the Lungs, and shallow because of the Kidneys' inability to hold the Lung Qi down.
4. A happy patient's inhalation and exhalation will be moderate, and irregular, with quick bursts.
5. When worried or deep in thought, the patient's inhalation will be shallow and weak, sometimes held for long periods of time, followed by a long gulping burst of inhalation and exhalation. The patient may also experience spontaneous sighing for prolonged periods of time.
6. When a patient experiences fright or shock, the breath immediately stops as the Qi attacks the Heart.

RESPIRATORY DAO YIN CANCER PRESCRIPTIONS

Respiratory prescriptions such as the Deep Relaxed Breathing Method described below, are used in treating cancer, and require the patient to combine the use of two methods of exercise and treatments:

1. The Opening and Closing Methods of Qi regulation (see Chapter 41), and
2. The Deep Relaxed Breathing methods for purgation, rather than tonification purposes.

The purpose of these treatment methods is to purge Excess Qi from the body, remove Blood stasis, and disperse Qi stagnations.

THE DEEP RELAXED BREATHING METHOD

The function of this exercise is to purge the channels and collaterals and to promote the circulation of Qi. It is also used to harmonize the ascension of Yang and the descending of Yin. Calming the Yin and suppressing the Yang promotes the flow of Qi and Blood through the organs, and has the effect of eliminating Evil pathogenic factors, and supporting healthy energy.

The Deep Relaxed Breathing method requires the patient to inhale through the nose and exhale through the mouth. The main points to remember in this method are as follows:

1. The patients inhalation and exhalation should be gentle, thin, even and long. They should focus their mind on the Hibernation Breathing Method. This method requires inhaling and exhaling through every pore on the body's surface while lying supine. The patients should not focus on their lower abdomen or the expansion of the upper chest and

Lung region. Instead, they should imagine inhaling through the pores into the Taiji Pole, and exhaling out from the Taiji Pole through the tissues and out the pores.

2. When breathing, the patients' whole body should stay relaxed; the key part to relaxing the whole body is to relax the waist.

Through training in these respiratory methods, the patients' immune system is enhanced and their vital Qi is nourished.

CHAPTER 17
MENTAL DAO YIN TRAINING

INTRODUCTION

There are two divisions of the Mind (Yin and Yang), each consisting of three different levels. The Yin part belongs to the energy of the Earth and is a more body-oriented type of mind. The Yang part of the Mind belongs to the energy of Heaven and is a more consciousness-oriented type of mind. The three levels of the Mind are as follows.

1. The first and deepest level exists within the Jing and the Shen, and represents the Original (Yuan) and primordial form of the mind.
2. The second or middle level exists within the Seven Corporeal Souls (Po) and Three Ethereal Souls (Hun) and represent the moving and active aspects of the mind (e.g., body movements, reflexes, instincts, drives, and astral projection - when accompanied by the Yuan Shen).
3. The third and superficial level exists within the Will (Zhi) and Intention (Yi) and represents the mind's everyday function (i.e., cognitive thinking). The Zhi is considered the "thinking body," while the Yi is considered the "thinking mind" (for more information refer to the Five Yin Organ components of Shen in Chapter 13).

These different levels of energies create the body, as well as activate the mental and emotional transitional states of the Mind. All three levels of the Mind are interactive and interdependent (Figure 17.1).

Energetic Division (Qi)	**Yin**	**Yang**
Energy of the Mind	Earth	Heaven
First Level of the Mind	Essence (Jing) Kidneys	Spirit (Shen) Heart
Middle Level of the MInd	Corporeal Soul (Po) Lungs	Ethereal Soul (Hun) Liver
Third Level of the Mind	Will (Zhi) Kidneys	Intention (Yi) Spleen

Figure 17.1. Mental and Emotional Transitional States of the Mind

Traditional Chinese Medicine believes that the Heart stores the Spirit (Shen). The Shen is further divided into Yuan Shen (the intuitive congenital spirit) and Zhi Shen (the analytical acquired spirit). The Shen is responsible for feeling and controlling the body's mental and emotional activities. The Zhi Shen is generally strong and can be stubborn and suspicious, therefore, it must be led by a master; the Yuan Shen must be that master, and must lead the Heart's Shen as one unit.

The brain is considered the house of the Yuan Shen, and the seat of mental function. It is believed that the senses and control of the body's physical movements are related to the brain. If the Heart has any functional disorder, the mental activities of the brain, and the emotional activities of the Heart also become disorganized. The Heart, which is the seat of all emotions, controls not only the Shen, but also the blood vessels, therefore Blood circulation is also influenced by the emotions.

The preservation of Jing depends on the cultivation of Qi, which in turn depends on the mental focus of the Shen. The mental focus of the Shen is to Qi as a mother is to her child. Mind concentration must combine with Qi; without the Shen


Mind
Acquired Postnatal Mind (Zhi Shen)
Acquired Benign Thought Patterns
Internal: Subconscious Praise
External: Environmental Praise
Acquired Malignant Thought Patterns
Internal: Subconscious Condemnation
External: Environmental Condemnation
Congenital Prenatal Mind (Yuan Shen)
Congenital Spiritual Patterns
Innate Connection to the Divine
Congenital Energetic Patterns
Vital Activities of the Major Viscera

Figure 17.2. The Differentiation Between the Prenatal and Postnatal Patterns of the Mind

guiding it, the body consumes the energy. The concentration of the Shen and Yi (intention) causes Qi to consolidate, while any distraction to the Shen and Yi causes Qi to disperse.

This concept is considered similar to that of regulating the emission of light, because Qi is emitted similar to the wave patterns of rippling water, and Shen is emitted similar to the wave patterns of light. When the Mind begins to focus concentration on the projection of Qi, both Qi and Shen unite, enabling the Qigong doctor to regulate the emitted Qi, changing its form from an expanded energy field to a finely honed beam.

THE PRENATAL AND POSTNATAL MIND

In Traditional Chinese Medicine, it is believed that the cerebral activity of the mind falls into two distinct categories: the Prenatal (Yuan Shen) Mind, and the Postnatal (Zhi Shen) Mind.

1. The Prenatal Mind (Yuan Shen) is inherited from the Jing of both parents and dominates the vital activities of the major viscera, as well as the function of the body's entire energetic organism and spiritual matrix.
2. The Postnatal Mind (Zhi Shen) is developed through interaction with people and the en-

vironment after birth. It dominates thought and interaction, and engages in unlimited mental activity.

The Yuan Shen and Zhi Shen are interactive and interdependent. If the Zhi Shen is active and chattering (sometimes called the Monkey Mind), it is difficult for the Yuan Shen to convey its perceived information. Regulating the Mind is therefore needed to harmonize the analytical and intuitive aspects of the Mind.

BENIGN AND MALIGNANT THOUGHT PATTERNS

Mental activity and thought processes can also be categorized into two clinical syndromes: benign and malignant thought activity (Figure 17.2).

BENIGN EMOTION AND THOUGHT ACTIVITY

This is a gentle or favorable belief structure of the subconscious mind, resulting in relaxed, pleasant thoughts. This thought pattern will both improve and regulate the excitation and inhibitory processes of the cerebral cortex. These positive thoughts and beliefs help to restore strength to the Yin and Yang organs, and thus promote health. Benign emotional thought activity can be further divided into internal and external influences:

1. Internal benign thought activities stem from the inner Hun's influences over the subconscious mind. These positive thought patterns tend to enhance self-esteem, by complementing and encouraging our thinking and actions.
2. External benign thought activities consist of praise and encouragement received from others (parents, friends, co-workers, etc.), which have been accepted and believed. These positive thought patterns promote confidence and self-esteem.

MALIGNANT EMOTION AND THOUGHT ACTIVITY

This is a harmful belief structure causing excited, nervous, stressful, and unpleasant thought patterns that interfere with the performance of the cerebral cortex, resulting in internal organ dysfunction and disease. Malignant emotional thought activity can be further divided into internal and external influences.

1. Internal malignant thought activities are the thoughts stemming from the subconscious mind, which tend to destroy self-esteem, cause obsessions, and discourage productive thoughts and actions. This thought pattern extends from the influences of the Po.
2. External malignant thought activities are internalized negative cynical beliefs and criticisms that originated from the surrounding environment (work, parents, teachers, friends, mate, etc.). External malignant thought activities cause thought distortions that destroy our self-esteem and discourage us.

THE IMPORTANCE OF MIND CONCENTRATION

An essential requirement for training the Qi is the training of mind concentration. If the concentration is forced, the Qi from the Lower Dantian rises up to the head causing the Stomach to become nauseated. If the Qi continues to ascend to the head, the result will be dizziness, headaches, and Qi deviations.

Thoughts and mental activities are reflexes of the brain and cerebral cortex. A Mind (whole body consciousness and awareness) agitated or depressed over a long period of time causes a long-term disorder to the whole nervous system, and leaves the body vulnerable to various kinds of chronic diseases. Long-term anger, for example, leads to the contraction of the blood vessels, sclerosis of the arterioles, gastric ulcers, and hypertension. Long-term emotional disturbances disrupt the endocrine system, and lead to a weakened immune system.

Psycho-neuro immunological research confirms that the Mind (whole body consciousness and awareness) can both cause and cure diseases. Healing visualizations sometimes act as a catalyst, increasing the rate of chemical reaction within the tissues. Improper concentration, however, can transform good Qi into Toxic Qi, and can lead to chemical imbalances that perpetuate the diseased condition. This is especially true when guiding and emitting energy.

According to medical statistics in China, with certain types of cancer, patients whose worry and anxiety were the main cause of their disease made up about 52% of the patients. These patients had been emotionally upset for half a year before becoming sick. The focus of the patients' mental concentration was directed on detrimental thoughts. It is a fact that chronic diseases are closely related to the patients' thoughts, emotions, and mood swings. To treat chronic diseases, it is necessary for the Qigong doctor to first relieve the patients' depression, irritability, and resentment and then place the patients, when possible, in a quiet comfortable environment.

It is important for the patients to relax their Mind (i.e., mind and body). Relaxation can be achieved through tissue manipulation (massage), or by inducing meditations, or trance states. To relax the Mind the Heart must be regulated. To regulate the Heart means to adjust the agitated or depressed Mind and place it into tranquility. One of my teachers in China, Qigong Master Zheng Zhan Ding would often say, "When the spirit, like a lake, is undisturbed, it mirrors the Heavens perfectly." Meaning that, the clarity of the Mind emerges gradually (or slowly) when entering into stillness, much like mud slowly settling in water. This allows ones true inner nature to be revealed.

According to research published by Dr. Karl Lashley, specific memory is not located in any one place in the brain. He found that destroying a portion of the brain does not destroy the memory assigned to that specific area, and also that memory could not be located in specific brain cells. His observation is that memory is distributed all over the brain as an energy field. Other researchers have made similar observations that support the conclusion that the human brain functions as a hologram, collecting and reading information from a holographic universe.

REGULATING THE MIND

Mental Dao Yin training involves regulating the Mind. This requires the Qigong doctor to diminish the mental activities (or judgements) of the Zhi Shen to prevent interference with the intuitive understanding of the Yuan Shen. The diminished mental activity allows for true relaxation, peace, and inner tranquility.

If the Zhi Shen is allowed to become unbridled through excessive internal chatter, it can become injured by the Excess accumulation of energy attributed to the Seven Internal Emotions: anger, worry, joy, fear, fright, sorrow, and grief; as well as the Four Desires that become pathogenic when in Excess: sex, money, fame, and power. These Seven Internal Emotions and Four Desires engage the mind, robbing the body of its life-force energy by depleting the Yin and Yang organs, disrupting their balance, and causing obstruction in Qi and Blood circulation that results in disease.

All thoughts carry within them emotional reactions, these in turn have a significant physiological as well as psychological effect on an individual's health. The degree of intensity as well as the frequency of returning thoughts determines the extent of the internal transitions experienced in the individual's body.

To illustrate this difficulty, when I began my initial Qigong training, my instructor informed me that the internal training would keep me warm in the winter and cool in the summer. Excited about the possibility of possessing my own internal air conditioner, I practiced diligently.

After three years of difficult training I had not yet developed this ability. I slowly began to lose trust in my instructor, and approached him to inquire about the promised skill. He informed me that it was the "imagination" that changes our thoughts and belief structures, enabling the body's tissues to feel what the mind directs. Stating that, "The Imagination leads the mind, the mind leads the Qi." My teacher further stated, "Whenever training in the summer when the heat is unbearable, focus your mind on the coolness of the sweat and imagine the air around your body as a cloud of cold air. In the winter time, when the cold is severe, focus your mind on the heat that your body is producing and imagine the air around yourself as a circle of hot fire." After applying these principles to my training, I experienced both the warmth and cool sensations that I was trying to achieve, and regained trust in my teacher.

Thoughts and emotions create electromagnetic waves in the brain. Your breath can also create or control these waves and cause your mind to take


Mental Dao Yin Concentration
Internal Objects: Localized and Directed Mind Concentration
External Objects: Symbolic and Suggestive Mind Concentration
Both Internal and External Objects: Rhythmic Mind Concentration

Figure 17.3. The Three Categories of Mental Concentration

on the thought wave patterns of specific emotions. When the mind is tranquilized after certain Medical Qigong exercises, all disturbances stop, there is a quiet and comfortable feeling sensation (produced by the deep inhibitory state of the cerebral cortex) that facilitates the expansion of consciousness and awareness throughout one's entire being. This state of being is referred to as the Mind.

THE THREE CATEGORIES OF MENTAL CONCENTRATION

Mental Dao Yin training can be summarized by the following three foundational modalities: concentrating on internal objects, concentrating on external objects, and concentrating on both internal and external objects (Figure 17.3).

These three modalities of mental concentration encompass regulation of both the benign and malignant emotional thought activities which influence our everyday lives. People focus their mental concentration everyday on either benign or malignant internal objects (inner thoughts and feelings), external objects (outer thoughts and feelings), or engage in both internal and external thoughts and feelings through conversation.

CONCENTRATING ON INTERNAL OBJECTS

In China, the method of concentrating on internal objects is called "localized" and "directed" mind concentration. In this type of training, the mind is absorbed in concentrating on a specific area of the body. Patients, for example, are directed to focus their eyes downward along the nose in the direction of their navel, while simultaneously using inner-vision to concentrate on their Lower Dantian. Patients can also focus their concentration on other external or internal areas of the body such as:

1. The palms or feet to lead Excess Qi away from the head or torso.
2. A specific channel point (called "energetic point therapy") or pathway, to direct Qi into or away from specific areas of the patient's body, or
3. A Yin or Yang organ to direct Qi into or away from specific internal organs.

The ancient Qigong Master Li Shizhen once said, "When the mind is concentrated upon the inner channels, the practitioner is able to look within his own self." Qigong doctors and patients who are energy sensitive can feel the channels along which their own vital energy flows. This sensitivity is experienced in the more advanced stages of tranquility.

CONCENTRATING ON EXTERNAL OBJECTS

In China, the method of concentrating on external objects is called "symbolic" and "suggestive" mind concentration, and is focused through vivid imagery. In this type of training the patient's mind is absorbed in concentration on some form of object outside of the body. As the mind enters a state of tranquility, it focuses through vivid imagery, or energizes through sound vibrations. Some excellent examples of external objects are: music, the sound of rain or water flowing, a calm ocean, the sky, clouds, light, sound vibrations, mantras, a golden or white glowing ball, specific colors, trees, etc. In this type of concentration, the patient's internal vibration connects with and matches the external form of some object in nature or some specific symbol (such as a lit candle).

When focusing on external objects, it is important for patients with high blood pressure to choose low lying objects, such as a meadow, quiet stream, flower, etc. Patients with low blood pressure should choose objects that are eye level, such as a small pine tree, to balance the energy of the Heart.

When practicing this particular method of mental concentration it is important to focus on external objects that can be physically observed without straining. This way if distracting thoughts interfere with the concentration, the patients can return to the real image, or sound, to reestablish their concentration. The focus should never be forced or too intense. Dr. Xu, of the Xi Yuan Hospital in China, once stated, "In the state of emptiness you will see an image through your imagination. This image will arouse your emotions. These emotions help you to form a more colorful image. From these colorful images you will obtain a deeper state of emptiness. This is the state of Mind sought after in order to obtain emptiness and maintain tranquility." In this particular case the patient's mind is like still water, free from expectations or desires. In quietness you become the observer of images, allowing what will unveil itself to occur naturally.

CONCENTRATING ON BOTH INTERNAL AND EXTERNAL OBJECTS

These methods employ "rhythmic Mind concentration" and are the primary methods used in Medical Qigong therapy. They are simple, easy, safe, and effective. In this type of mental training, the patient's body responds to their thoughts. Patients focus their attention on the breath as it flows in and out of the body, listening to the sounds of their breathing and sensing the expanding and contracting movements of their abdomen. During this type of mental concentration the patients are sometimes given a mantra, such as thinking the word "quiet" during the inhalation and "relax" during the exhalation, or they are instructed to silently count numbers. Sometimes, the patients are also directed to imagine the feeling of quietness, like a mist, flow from their feet into their head (absorbing quiescent Earthly Qi), or from their head down into their feet (absorbing quiescent Heavenly Qi).

When first teaching patients the methods of mind concentration, keep the images simple. When the patients have recovered from their illness, they can begin to concentrate on either an internal or external object to further strengthen their health.

ESSENTIALS OF TRAINING MIND CONCENTRATION

These three mental Dao Yin techniques can be utilized to their full potential once the Qigong doctor understands the essentials of training the mind, the three stages of mental tranquility, and the skill of regulating the mind.

Mental activities should be coordinated naturally with respiration and posture. In Dynamic Qigong Dao Yin exercises, for example, mental activities must be adapted to the posture and the lifting, opening, and closing manipulations of the hands. When using an active (Yang) posture (if the goal is to regulate the patients' Qi), the inner concentration should be motionless (Yin). The ultimate goal is to combine both physical and mental activities that promote harmony in the body's energetic fields. The Qigong doctor should monitor their patients' mental concentration, making sure that they comprehend the following three concepts: Relaxing the Mind, Being Self-Confident, and Being Mentally and Emotionally Stable.

1. The purpose of relaxing the mind is to allow all mental activities to be carried out (without straining) in a composed state of mind. The mind should be kept clear and all distracting thoughts expelled gently. During concentration, the mental focus should never be forced. Mental concentration can be either strong (active) or mild (motionless).
2. Self-Confidence is a prerequisite, for without it, the training of mind concentration cannot happen. No matter what kind of mental activity the patients train in, they should be confident that they can reach their goal. This establishes a strong faith, which is the root of all mental Qigong projection abilities. Patients should also be realistic about not expecting quick results. Although miracles do happen, healing often takes time. The dynamic or active postures and exercises train the body's Qi, while quiescent or motionless exercises sustain and nourish the patients' Qi.
3. The purpose of being mentally and emotionally stable is to assist patients in not becoming overjoyed or frightened if something unexpected happens, or is perceived, during the Qigong exercise. It is important that patients take advantage of this time to keep their mind concentrated and the Qi consolidated. If patients feel weary, remind them that sleep and food can reinforce their mind and Qi.

CONCENTRATIVE MEDITATION AND INSIGHT MEDITATION

When Medical Qigong practitioners begin their meditative practices, they are generally encouraged to keep their mind focused and under control, this is known as "concentrative meditation." Concentrated power is manifested through silence; when the mind is noisy (distracted by physical sensations and chatty), the internal power becomes diffused. When Qigong doctors reach the place of silence in their Mind, they can connect with the divine power, a place of true power, and a place where "all is one." Through concentrated intention, Qigong doctors can bring all of their energies to bear on one point of focused power or force. At the same time, they contact and connect with the divine in silence (the hookup), and become one with the divine healing power.

This transition and conscious union with the divine occurs only when the Qigong doctors turn from the chaotic external world of sensory input (sight, hearing, smelling, etc.), to the quiescent state of silence. This divine energy is then manifested as power, substance and true intelligence, flowing through the Qigong doctors for healing.

Contact with the divine is only obtained in the deepest part of silence. Within oneself, and within this silence abides a state, or dimension, where the true "Gate of Heaven" can be opened and enlightenment obtained. Ideas conceived in this divine state of consciousness come into expression and can manifest as form. All Jing, Qi, and Shen can be transformed and transmuted into form, through this change in consciousness. When the doctor's Intention (Yi) and Will (Zhi) are aligned with the Dao (or divine will) all things are possible. The doctor is in direct contact with the universal Mind, and can manifest in physical form, that which is needed through faith. The divine energy resides within the body's Eternal Soul as power, substance, and intelligence and is brought into form and expression through consciousness. The degree to which the doctor can tap into and utilize the consciousness imbedded in the infinite Mind of the divine, is determined by the concept, or belief, that is held in the doctor's as well as the patient's conscious and subconscious mind.

In the silent state of quiescence, when the Qigong doctor sees a mental pattern or mold, a template is created into which will flow the substance (Qi) needed to bring it into being. The pattern will manifest into the form intended by the doctor's consciousness. Through the power or process of faith and thought, the doctor (or patient) can transmute and evolve the body or outer conditions and surroundings, by recognizing the divine consciousness within themselves.

As the practitioners advance in ability, they are encouraged to focus their attention indiscriminately on all sensual stimuli they receive, this is known as "insight meditation." In practicing insight meditation, practitioners are encouraged to

6. Smile to the kidneys and let the love of the heart activate the gentleness, softness and calm in the kidneys.



Fig. 6.14 *Let Love and Joy from the Heart activate Positive Kidney Energies.*

7. Let the gentleness, softness and calm in the kidneys flow into the heart. Blend and spiral into one energy.



Fig. 6.15 *Blend Positive Kidney Energies with the Compassion Energy in the Heart.*

reevaluate their experiences and world views according to the cause and effect of their disease(s). Patients are also taught to use this type of insight to observe their physical and mental processes. This self-observer is used as a vehicle through which to observe, scrutinize, and carefully examine the fundamental energy transformations within the body for spiritual growth.

THE THREE STAGES OF MENTAL TRANQUILITY

Before the mind surrenders to a state of tranquility, it must first transition through three stages. The Qigong doctor must experience all three of these stages in his or her effort to become effective when treating patients. In China, Qigong masters have a saying, "When you root the Mind, the Heart will open up to ten thousand voices." This means that when the Mind is removed from all distractions and excess chatter, the Yuan Shen is free to receive intuitive perceptions. This state of "tranquility" or "stillness" also dissolves time perception, allowing time to disperse into nothingness (Wuji). The three stages of mental tranquility are described as follows:

STAGE 1

In the first stage, the doctor's four extremities and Lower Dantian may experience heat and tingling as the mind slowly eliminates distracting thoughts and begins to withdraw from the external world. The doctor's mental focus and concentration, however, is not consistent. While emitting Qi, distracting thoughts still emerge, and the doctor must patiently wait for the chattering mind to subside.

In this stage of training, especially in male Qigong doctors, the cognitive, analytical thinking and speaking may sometimes become sporadically impeded. This is due to the thin energetic field within the corpus callosum that separates the right (intuitive) from the left (analytical) hemispheres of the brain. This makes it more difficult for men to access both hemispheres simultaneously. Men should therefore train to rely more on their intuitive perceptions instead of analyzing (they must feel the energy, and not think it).

This however, is not a problem in female Qigong doctors, as the energetic field which separates the corpus callosum is much wider and already active. This allows female Qigong doctors to easily access both sides of their brain simultaneously, enabling them to draw upon the perceptive, intuitive as well as cognitive, analytical thinking and speaking hemispheres of their brain.

STAGE 2

In the second stage, there is an increase in heat to all four of the doctor's extremities from the Lower Dantian. Through intention, the connection to the Lower Dantian is strengthened and the body's Qi feels like a rushing wind flowing throughout the doctor's torso.

While diagnosing and treating, the doctor experiences one or several of the patient's "eight manifestations of Qi" (also called the Eight Energetic Touches). These manifestations consists of the following physical and sensory phenomena of energy: shaking, rippling, heat, coldness, sinking, floating, itching, and heaviness. As the doctor focuses on extending energy, he or she will be able to remove internal distracting thoughts, but will still hear the distracting sounds from the external world.

STAGE 3

In the third stage, all of the doctor's sensory input (seeing, hearing, tasting, touching, smelling, and perceiving) is sealed from outside distractions. The doctor's Yuan Shen and Zhi Shen are now relaxed and in a state of mental tranquility. The Qigong doctor can now approach the patient free of chattering thoughts, judgments and all outside distractions. This enables the doctor to intuitively perceive and sense the patient's energetic traumas, stagnations, deviations, and energetic clusters.

THE THREE PROCESSES OF THE MIND

The mind can be divided into three separate but interdependent processes, which are responsible for our everyday actions, responses and health (Figure 17.4). Thoughts, ideas, and feelings are constantly being implanted, influencing and affecting the spiritual, emotional, mental, energetic, and physical process of healing. The heal-


The Three Interdependent Processes of the Mind
The Conscious Mind:
Perceives reality through the five senses.
The Personal Subconscious Mind:
Records and stores our interpretations of reality.
The Creative Subconscious Mind:
Maintains reality by making us act like the people we see ourselves to be.

Figure 17.4. The three interdependent processes of the Mind, which are responsible for our everyday actions.

ing process includes reprogramming and regulating the conscious, personal subconscious and creative subconscious mind.

1. The Conscious Mind perceives reality through the five ordinary senses. It evaluates reality by investigating and interpreting the data through the filter of the past experiences. The conscious mind makes decisions based on personal goals, and manifests conscious thinking patterns. It is considered to be the Postnatal Mind (related to the Zhi Shen).
2. The Personal Subconscious Mind records and stores the conscious mind's interpretations of reality. It consists of the personal, perceptual data that were received through our five senses. The personal subconscious mind shares responsibility for how we think, what we say and imagine about ourselves and our emotional and behavioral reactions to those experiences. It is also responsible for the automatic function of the living mechanism (i.e., heartbeat, breathing, digestion, etc.) through its energetic connection to the autonomic nervous system. It is considered to be influenced by the spiritual aspects of the Wu Jing Shen (especially the Hun and Po).
3. The Creative Subconscious Mind maintains our reality by making us act like the people we see ourselves to be. It solves problems and provides the drive and energy to succeed or fail, heal or become sick. It is the center core energy of our innate spirit or soul consciousness. It is considered to be influenced by the spiritual aspects of the Yuan Shen.

CREATING THE BRIDGE OF LIGHT

The Bridge of Light is an energetically patterned wave frequency which consists of three main components of the body's energetic field. Its energetic connection to the body's tissues functionally envelops the conscious, personal subconscious and creative subconscious mind, and is considered to be the bridge between the three process of the mind. It consists of three separate but intertwining threads: the thread of life, the thread of consciousness, and the thread of creativity.

1. The thread of life comes directly from the Eternal Soul and is rooted in the Heart during conception. It is connected to all feelings that stem from the divine higher energy field and is considered the "seat of life."
2. The thread of consciousness also comes directly from the Eternal Soul and is rooted in the pineal gland within the brain. It embod-


Personal Subconscious Mind:
Records and stores our interpretations of reality (Related to the Zhi Shen).
Thread of Consciousness:
Rooted in the brain (pineal gland)
Creative Subconscious Mind:
Maintains reality by making us act like the people we see ourselves to be (Related to the Wu Jing Shen).
Bridge of Light
Thread of Life:
Rooted in the Heart
Conscious Mind:
Perceives reality through the five senses (Related to the Yuan Shen).
Thread of Creativity:
Rooted in the throat

Figure 17.5. The Bridge of Light

ies portions of the energies of consciousness and is considered to be the "seat of consciousness."

3. The thread of creativity is rooted in the throat and is unique in that it is created and specifically constructed by each individual. It is also an extension, or synthesis, of the thread of life and thread of consciousness.

   The thread of creativity is in itself made up of three main components. These three components, or additional threads, intertwine as one unified thread of creativity and are explained as follows.

   a. The first portion of this thread extends from the physical Heart to the Spleen, and is connected from the body to the first external field of Wei Qi.
   b. The second portion of this thread extends from the solar plexus to the Heart and eventually extends and connects from the body to the second external field of Wei Qi.
   c. The third portion of this thread extends from the Yintang (Third Eye) through the brain, ascending through the Baihui region and beyond. This energy field is connected from the body to the third external field of Wei Qi.

After all three threads of creativity have been activated, energized, and developed, the next goal is to align and integrate the Qi of the thread of life and the thread of consciousness, with the frequencies of the thread of creativity.

Because the thread of life is connected to the Eternal Soul, the integration of the three threads allows an individual the direct connection to his or her core self (Figure 17.5). This enables the individual the ability to consciously access his or her true inner voice (the voice of his or her soul) and receive information and guidance from the divine. The goal in accessing the Bridge of Light is to unite these three energetic threads into one powerful and functional energy field.

When all three major threads (which compose the Bridge of Light) are connected as one harmonious cord of light (extending upward through the Taiji Pole), a spiritual gateway is opened that enables access to the Pure Heavenly Sound (also known as Hearing the Sounds of the Universe) (see the Six Transportations of Shen in Chapter 13).

REPROGRAMMING THE MIND TO HEAL

The mind holds specific energetic patterns which maintain a patient's physical, mental, emotional, and spiritual belief structures. These patterns are maintained by the dictates of the personal subconscious mind and can only be changed when the creative subconscious mind is engaged.

To change specific destructive patterns, the personal subconscious mind must be reprogrammed. There are three things that are needed in order to reprogram the personal subconscious mind: imagination, visualization, and positive affirmation. Imagination combines with vivid pictures, sounds, sensations, etc., and creates a new reality on a creative subconscious level. It is the awakening to this new reality that reconnects the individual to the creative subconscious mind.

If patients do not use imagery and affirmations to change their present personal subconscious representation of reality, the patient's personal subconscious mind will automatically seek to correct any newly made change. The personal subconscious mind views any new deviation from the normal energetic pattern as a mistake, and will automatically resist, or sabotage, any change of pattern, returning the patient back to his or her original state of mind and body sickness.

It is a simple fact that "we bring about what we think about," and act in accordance with the truth that we have come to believe. If we act out of a particular new state of mind and feeling over a sufficient time period, it will become a permanent reality of the self. In using the mind to make transitions, it is important to note that words, images, and sensations have tremendous power, and the spirit behind the intent is the key to any permanent transformation.

Because patients trust their doctor, it is the doctor's responsibility to direct the patients into a healing mental state for the purpose of restoring health. The doctor must never be guilty of "clinical hexing." Clinical hexing occurs when a patient (who completely trusts the doctor) is told by that doctor, that there is no hope. The patients, believing the doctor, may give up their desire to change and heal. Thus, through accepting the inevitability of death, they suppress their desire to live. Qigong doctors are therefore taught to always encourage their patients on their recovery, and to never destroy their hope.

Through positive affirmation and reinforcement, it is possible for the patients to turn around the progression of their disease. Scientific studies in China have proven, for example, that through imagination, visualization (which include using all of the five senses) and positive affirmation, the rate of phagocytosis (the ability of the immune cells to engulf and destroy invading germ cells) greatly increases and enhances the body's immune function.

USING THE IMAGINATION

The Yi (which consists of the imagination and intention) leads the Shen (composed of the thought, emotion and spirit) which in turn leads the Qi (the body's life-force energy). The power of the imagination has a strong influence on health, and can be used to help cure diseases, or to further complicate the condition. If, for example, patients imagine that their immune cells are effectively destroying the cancer cells, Western medical treatments such as chemotherapy or radiation can become more effective. Research from China reveals that patients with a positive belief structure produce certain physical transformations, which manifest in the increased production and release of hormones and immune cells. The imagination is the inner form of all things, the primal inspiration from which reality later manifests. In a sense, patients bring about what they think about. While treating disease, Qigong doctors encourage their patients to imagine healing energy from the divine being directed into the diseased area. Once the treatment is finished, the patients are instructed to imagine that their disease has become completely healed.

During the state of relaxed meditation, the foundational aspect of the patients' disease, which is normally hidden from consciousness, reveals itself in the form of images and impressions. After a Medical Qigong treatment, or meditation, the patients may describe to the doctor any unusual thoughts, images, or feelings that they may have experienced while in the deep state of relaxation. The doctor then helps the patients find the origin of the image (a past incident, unhealthy belief structure, or trauma, etc.) through the doctor's ability to trace the images and emotions associated with it to the patients' internal organ or organ systems involved in the creation of the illness. Once the connection is made to the patients' disease, and the Medical Qigong homework is prescribed.

Medical Qigong prescriptions initiate energy movement. This energetic movement brings about the release of trapped emotion and energetic feelings. As the emotions unravel, a new level of awareness surfaces that allows the patients to become cognizant of certain mental functions that were previously unconscious. This awareness in turn allows patients to access their creative subconscious Mind to change the conditioned programming of their Zhi Shen (Figure 17.6).

Through creative imagination, the patients' spirit is expressed and the patients' body is spiritualized. The imagination is an energetic world founded on the interrelation of various levels of spiritual, imaginative and physical realities. These energetic dimensions lie between what the Chinese call the "realm of the unfathomable hidden mystery" and the "world of animated physical forms." The imagination is an energetic and spiritual world that exists between the reality within oneself, and the reality outside of oneself. This energetic and spiritual world seems imaginary, but in fact it is very real, in that the patients live in it, and through it create a new belief system and self.


The Creative Subconscious Mind and the Conditioned Programming of the Zhi Shen
Mental Function of Conscious and Personal Subconscious Mind
Release of Emotion and Energetic Feelings
Energy Movement
Medical Qigong Prescriptions

Figure 17.6. Five stages of transition and energy awareness allow patients to access their creative subconscious energy in order to reprogram their initial belief structures.

TWELVE STAGES TO TRANSCEND AND TRANSFORM

During the Ming Dynasty there began to surface twelve specific poems accompanied with twelve pictures, describing the twelve stages to enlightenment through contemplation. In this series there are ten pictures which describe the first ten stages of mental, emotional, and spiritual transcendence, and two additional pictures which describe the last two stages of mental, emotional, and spiritual transformation. These pictures and poems use the image of the ox (water buffalo) to describe man's animal nature, which in the first stage of spiritual training is identical to man's spiritual nature. The image of a young man is used to depict human intention and will. The interaction of the ox and young man reflects the idea that by coming to terms with our own animal nature, we can move toward transformation and arrive at a new way of being.

The images of the ox changing from dark, Turbid Yin, to bright, white Yang, represent the field of consciousness transforming through the controlled deliberate intention of one's Zhi (Will). Such metaphors as capturing and controlling the ox represent an explanation of the difficulties and dangers of transforming one's self, as well as the inner changes of alchemical purification and the reconciliation with one's darker side. These pictures suggest the combination of both the sacred and the natural within Man.

These stages of controlling the mind are described as follows.

1. In the wild, the first stage of training is divided into three separate phases:
    a. The Searching for the Ox phase depicts the state in which the young man is unaware of his own true nature. Although he is not sure what he is seeking, he has begun searching for something he is desperately missing within his life. He is in a state of omnidirectional searching, without an instinctive direction.
    b. The Finding the Tracks phase depicts the young man undergoing the first traces of mental, emotional and spiritual transformation. Realizing that other people have walked along this path, the young man begins to rediscover his own spiritual instincts. He is in the beginning phase of achieving focus and direction.
    c. The First Glimpse of the Ox phase depicts the young man experiencing his first "awakening." He has the first glimpse of the true union of nature and spirit in the form of a spiritual vision. The animal nature, however, is still uncontrollable and in the wild state (due to its connection to the painful memories of the past). The young man must chase after and entice the ox, which displays its horns, bellows aloud, runs away, and is overshadowed by a dark cloud (anger, despair, grief and fear). It tramples the wheat seedlings (beginning moments of spiritual insight) wherever it goes. In this phase the ox is unruly, Yin, and pure black in color (Figure 17.7).
2. The Initial Training Begins with this next stage. The ox is controlled by a rope through its nose, and runs swiftly under the young man's whip. The young man struggles hard to control the ox's willful temper. He begins talking and listening to the ox, matching its consciousness with his own. At this stage the ox is still Yin, and pure black (Figure 17.8).
3. The Ox Comes Under Control through con-


Figure 17.7. The Ox is in the Wild


Figure 17.8. The Initial Training Begins


Figure 17.9. The Ox Comes Under Control


Figure 17.10. A Time of Transition

stant training. The ox stops its dashing about, and begins to follow the young man. In spite of his fatigue, the young man tends the ox all day long, not daring to loosen his control of the whip or his grip on the rope. Gaining control of the ox requires the young man to also become more vulnerable and honest, using less force to control the situation. In this stage only the ox's head, which is under control, is Yang and white, the rest of his body is Yin and black (Figure 17.9).

4. During the Time of Transition, the young man feeds and takes care of the ox with respect. He also does not abuse it. At this stage, the natural strength of the ox harmonizes with the will of the young man. A long time has passed and the restless temper of the ox gradually has turned gentle. However, still not trusting the ox, the young man maintains control of the rope. The ox is one third Yang and white and two thirds Yin and black (Figure 17.10).
5. The Ox Is Now Tamed and moves in harmony with nature. It follows the young man, who no longer uses a rope to lead the ox, but still maintains control of the whip. The ox is half Yang-white and half Yin-black (Figure 17.11).
6. The Ox Is Freed of Worldly Hindrance. The ox no longer needs the whip for control. The young man can begin to experience and enjoy the inherent rhythm of life, because he now has the ox's undivided attention. The ox is three quarters Yang-white and one quarter Yin-black (Figure 17.12).
7. The Ox Is Under Complete Control. After a long stage of struggling against its instincts, the ox is now tamed and free from worldly distractions. It drinks when it is thirsty and eats when it is hungry. The young man can now enter into deep sleep. If he so desires, he can sit atop the ox and play his flute, because the ox knows where its going and the young man does not have to direct it. The ox is now completely Yang-white (Figure 17.13).
8. The Young Man and the Ox Unite With Heaven. The white ox wanders among the heavenly clouds. The young man is free from



Figure 17.11. The Ox Is Now Tamed



Figure 17.12. The Ox Is Freed of Worldly Hindrance



Figure 17.13. The Ox Is Under Complete Control



Figure 17.14. The Young Man and the Ox Unite With Heaven

worldly concerns, and so is the ox. Penetrated by moonlight, the Heavenly clouds grow whiter and drift away (Figure 17.14).

9. The Ox Transcends and A Single Light Remains. The clouds drift away and the ox vanishes. The young man finally enjoys his leisure time, singing under the moon (Figure 17.15).
10. Both the Ox and Young man Transcend and Return to the state of Wuji. As the moon continues to illuminate the vast void, both the young man and the ox vanish into Wuji and are nowhere to be found. Everything is formless, quiet, and pure. Existence is nonexistence and vice versa (Figure 17.16).
11. The Young Man and Ox Transform and Return to the Source. There is a difference between transcendence and transformation. Transcendence is a temporary or periodic experience of unity within the divine, the heavens and the earthly environment. It is a state, or condition of consciousness. Whereas transcendence implies a unifying experience that informs one of a new way of being, transformation is a process and a means to arrive at a new way of being. Mature transformation leads to an all-inclusive way of being that embraces the physical, mental, emotional, energetic, and spiritual existence of everything. In this stage man returns back to the original source of prenatal understanding, and is able to harmonize with Heaven and Earth (Figure 17.17).
12. The Young Man and Ox Transform and Live in the World. This stage depicts what happens after the transformation experience, and the reentry through nature into the everyday world. In this stage, man reenters the world as a transformed person with a new connection to his center core. He is able to become a guiding light to others. When needed, he can instantly return to a deeper state of enlightenment for additional instruction and personal guidance. Living in the world he can be in the seductions and temptations of the world, without being in any way affected by them (Figure 17.18).



Figure 17.15. The Ox Transcends and A Single Light Remains



Figure 17.16. Both the Ox and Young Man Transcend and Return to the State of Wuji



Figure 17.17. The Young Man and Ox Transform and Return to the Source



Figure 17.18. Transformation and Living in the World


Seven Steps of Awareness
1. Respect
2. The Interception of Karma
3. Controlling the Mind
4. Detachment from Worldly Affairs
5. True Observation of Self and Others
6. Intense Concentration
7. Realization of the Dao

Figure 17.19. The Seven Steps Needed to Transform the Mind

SUMMARY

During mental, emotional and spiritual transformations, individuals undergo stages of physical and psychological purification, as they begin to experience the active, conscious introspection into their mind, body and soul. These individuals are able to eventually identify and connect their own personal will to that of the divine, and begin to lose their attachment to the ego, developing a new and more expansive identity. These individuals will also begin to see themselves as truly spiritual beings that are merely housed in fragile, physical frameworks, which are subject to all the transformations that their spirit must transcend. Generally, when using Medical Qigong as a vehicle for transformation, individuals will evolve through seven steps to awaken the spirit and reach a stage of enlightenment: Respect, The Interception of Karma, Controlling the Mind, Detachment from Worldly Affairs, True Observation of Self and Others, Intense Concentration and Realization of the Dao (Figure 17.19).

1. The first stage, Respect, encompasses the self, others and the divine. Through the cultivation of respect a stronger faith develops.
2. During the second stage, The Interception of Karma, individuals begin to accept accountability for all their actions, deeds, and thoughts. At this stage individuals receive instant karma for all their actions.
3. During the third stage, Controlling the Mind, individuals begin to discipline their conscious actions (Taming the Ox).
4. The fourth stage begins the process of Detachment from Worldly Affairs. At this stage individuals begin to develop and maintain a spiritual priority.
5. The fifth stage of True Observation of Self and Others, enables individuals to perceive themselves and others clearly. At this stage they begin perceiving the universe and environment from a deeper, more spiritually evolved understanding.
6. The sixth stage involves the development of Intense Concentration. At this stage individuals transform thought, through faith, into manifestation. They can now initiate into reality what they focus their intention on.
7. In the final stage to transformation, Realizing the Dao, individuals become aware of their relationship with the divine, not only believing in God, but personally knowing God or the Dao.

SECTION IV

QI DEVIATIONS IN QIGONG TRAINING

8. Smile to the liver and gall bladder. Let the softness and the love from the heart flow down to activate the kindness and generosity of the liver.



Fig. 6.16 *Let Love and Joy from the Heart activate Positive Liver Energies.*

9. Let the kindness and generosity flow to the heart, spiral and blend in the heart to become compassionate; be aware of the green light flowing from above.



Fig. 6.17 *Blend Positive Liver Energies into the Compassion Energy.*

CHAPTER 18
INTRODUCTION TO QI DEVIATIONS

Energetic deviations occur naturally through the course of everyday life, however, the body's energetic constitution quickly corrects any disharmony in energy flow. The difficulty when cultivating Qi is not in the development of large amounts of energy, but in the creation of a constitutional system strong enough to use this energy without being damaged by it. This is one reason why Qigong doctors initially spend a lot of time developing the safety measures and internal reservoirs necessary to ensure that their body will not be damaged by creating too much energy too fast. These alterations of energetic patterns can result in feelings that can range from simple discomfort to an abnormal susceptibility to disease. Through proper Medical Qigong therapy, Qi deviations can be rectified.

Qi deviations can be precursors to disease. In recent years, medical researchers in China have reported that some patients admitted to the Medical Qigong clinics had developed mental as well as physical disorders as a result of Qi deviations. A deviation refers to abnormal phenomena occurring within the patient or Qigong practitioner. The clinical symptoms include abnormalities in perception, thinking, and behavior.

If the Qigong doctor has not been adequately trained in internal purging techniques, his or her body's increased energetic field can act as a magnet and begin to attract the toxic energy from the surrounding environment (including the patient's pathogenic Qi). Once toxic energy enters into the body, it can immediately create a Qi deviation. Qi deviations should be treated immediately if possible. If Qi deviations occur during Qigong exercises or meditations, the practitioner should stop the practice immediately and guide the Turbid Qi (and bad feelings) out from the body, discharging the toxic energy out through the four extremities and into the ground.

The process of Medical Qigong meditations and exercises is said to cause an alchemic transformation of Shi Shen (Turbid Spirit) into Yuan Shen (Original Spirit). This transformation occurs when first beginning Qigong practice, at the "laying a foundation" stage of the workout. If the Turbid Qi is not removed at the beginning of practice, the Qi concentrated in the Dantian areas (or other parts of the body) will also become Turbid. This may bring about internal disturbances when the practitioner encounters unfavorable external factors such as suddenly being startled or becoming angry. Too much concentration and hard focus on the exercises and meditations can also lead to Qi deviations. Turbid Qi can create Turbid Shen.

When Turbid Qi travels along the Governing Vessel to the head, there is a feeling of heavy pressure in the head. In severe cases, psychosis can occur. Turbid Qi that escapes into the body's channels can result in distending or numbing of the body. To avoid such side effects, it is extremely important to establish an equilibrium between the Five Yin Organs. No matter which Medical Qigong system is followed, the primary task is always to dredge or purge the channels of pathogenic Qi, to regulate the Yin and Yang organs and to cultivate the body's Jing, Qi, and Shen.

THE MAIN CAUSES OF QI DEVIATIONS

Mental disorders and personality disorders may exist in some individuals prior to their study of Medical Qigong. Sometimes, individuals with a family history of psychosis and certain other mental disorders (such as bipolar disorder and depressive disorder) may be more predisposed towards these diseases. The practice of Medical Qigong meditations and exercises may trigger the onset of symptoms in predisposed individuals, especially if Qi deviations are not properly addressed.

1. A Week Constitution	From severe disease and weak respiration
2. Improper Dao Yin Qigong Regulation	From forced practice, hastily and indiscriminately training
3. Disbelief and Suspiciousness	From a closed mind, superficial mind, or preoccupied mind
4. Too Much Mental Concentration	From concentrating too hard, resulting in Qi and Blood to stagnation

Figure 18.1. The Main Causes of Qi Deviations

The main causes believed to contribute to Qigong deviations, according to research gathered by Dr. Wei Lin Shen of Shanghai, China, include the person's constitution and pathological state, improper Dao Yin Qigong regulation, disbelief in and distrust of the Qigong exercises and meditations, or too much mental concentration (Figure 18.1).

1. A week constitution can lead to a pathological condition. Patients with a weak constitution should not be required to sit or stand for long periods of time. Patients with severe disease and weak respiration incur Qi deviations if they are allowed to stand too long.
2. Improper Dao Yin Qigong regulation can result in Qi deviations. Qigong deviations may also occur as a result of forced practice (when the state of illness does not allow relaxation), or when individuals hastily and indiscriminately train in the techniques that circulate internal Qi. Lack of proper instruction from a qualified master of Medical Qigong therapy often results in a failure to train in the correct way. The failure to correctly apply the three Dao Yin principles and methods (proper regulation of the body's Jing, breath's Qi, and mind's Shen) in training practice, for example, leads to Qi deviations. Creating new techniques, training recklessly before mastering the primary techniques, or changing the techniques at random can also result in Qi deviations. For this reason the practitioners should be patient when practicing Dao Yin regulations. The goal is to achieve a tranquil, quiet, and empty state.
3. Disbelief, and suspiciousness can induce Qi deviations. Disbelief or an inability to adopt a correct attitude toward Medical Qigong effects (such as extreme suspiciousness), results in mental tendencies that will become deviations over the course of time. Qi deviations can result from: A Closed Mind, A Superficial Mind, and A Preoccupied Mind.
    a. A closed mind, full of fear, pride or bitterness may prevent the patients from connecting with their True Self.
    b. A superficial mind, or lack of commitment and belief in energetic healing, may cause the patient to fail in taking the Medical Qigong prescriptions seriously.
    c. A preoccupied mind may cause the patient's spirit (Hun) to "wander off" while practicing Medical Qigong therapy.
4. Too much mental concentration is the most frequent cause of Qi deviations. The strong focus of mental attention on the flow of Qi can distort its path and lead to Qi deviations. It can cause too much concentrated Qi and Blood to flow into the brain. Concentration on internal objects with too intense a focus can actually cause a stagnation, or Excess of

Qi in the area (e.g., concentrating too hard on a tumor can actually cause it to grow instead of dispersing it). Mild concentration is always preferred when practicing Medical Qigong exercises and meditations. A relaxed mind and body allows the Qi to flow freely.

CORRECTING QI DEVIATIONS

To correct any Qi deviation, it is important to understand the root cause of the deviation. The Medical Qigong doctor should check for the following causes of Qi deviations.

1. Postural Dao Yin deviations result from incorrect postural changes.
2. Respiratory Dao Yin deviations result from improper breathing methods.
3. Mental Dao Yin deviations result from improper mental activities and emotional disturbances. These emotional disturbances (due to the accumulation of toxic emotions within the internal organs) may manifest as spontaneous emotional outbursts.
4. Stressful life activities resulting from an improper balance of work and play, lack of sleep, or an improper diet may likewise cause Qi deviations.
5. Environmental disturbances during Medical Qigong practice such as the phone or doorbell ringing, may startle the practitioner and cause Qi deviations.

To correct the Qi deviation, the Qigong doctor addresses each possible cause separately, beginning with the patient's posture.

POSTURAL DAO YIN DEVIATIONS

To diagnose Qi deviations due to incorrect postural alignment it is important to observe whether:

- relaxation is being achieved,
- the posture is structurally correct to facilitate relaxation, and
- the appropriate tonifying, purging, or regulating technique is being used.

When a deviation occurs, the patient should examine it in accordance with the basic laws of postural alignment. A beginner is more prone to some disorders due to incorrect postures that cause headaches, dizziness, and a stiff neck.

MANIFESTATIONS OF POSTURAL QI DEVIATIONS

If postural deviations occur, first review the Eighteen Rules of Proper Medical Qigong Structure in relationship to the sitting or standing positions, and then review the other Dao Yin Qigong patterns (respiratory and mental Dao Yin training). The following are examples of specific Qi deviations related to improper postural alignment.

1. Eye distention results from excessively staring at external objects during the meditations and exercises. To prevent this type of Qi deviation, encourage the patients to always use a soft focus.
2. A stiff or painful neck is usually caused by forcefully attempting to suspend the head. To prevent this type of Qi deviation, have the patient relax the neck muscles and sink the shoulders.
3. Shoulder and back pain can occur when patients fail to relax the muscles of the shoulders and back, stretch the back excessively, hollow their chest too much, or hold an unfamiliar posture too long. To prevent this type of Qi deviation, have the patients relax and sink their shoulders and imagine the back melting down into the hips and legs.
4. Waist and hip pain (Lumbago) come from several factors.
    a. Tension in the hip muscles causes pain in the hips that extends to the waist.
    b. Twisting the waist without first relaxing the hips can result in both hip and waist pain.
    c. Forcefully twisting the waist may also cause pain.

    To prevent this type of Qi deviation, have the patients relax their waist and hips and sink the energy into the Earth via the feet.
5. Abdomen and lower extremity distention or flatulence results from the forceful pulling-in of the Stomach, or too much concentration of the mind on the lower extremities. To prevent this type of Qi deviation, have the patients relax their abdomen and lower extremities, allowing the Qi to sink naturally.
6. A swollen and painful anus, or dry stool, can

result from raising the anus too forcefully. Also, hemorrhoids can develope from holding the breath too forcefully while focusing on the lower abdominal area during the Abdominal Breathing Holding method. To prevent this type of Qi deviation, have the patients close their anal sphincter softly and relax their buttock muscles.

7. Sore knees are a result of crouching too low, over-bending the knees, or extending them past the toes. To prevent this type of Qi deviation, have the patients keep their knees in proper alignment and guide the pressure of the body weight to flow behind the legs and not in front.
8. Heel pain can be caused by shifting the body's weight excessively onto the heels during walking or standing practice. Heel-ache can also occur if the patients focus too much attention on their heels instead of the center of their feet for balance. Knocking, stomping, or excessively dropping the heels against the ground, as well as sexual Excess, or a Kidney Deficiency can all cause pain in the heels. To prevent this type of Qi deviation, have the patients relax their legs and waist and imagine that their feet are kneading the ground. This squashing and kneading action is used to encourage the free flow of Yin Qi from the Earth into the body.
9. Improper hand movements occur when patients fail to distinguish between Yin and Yang energetic properties, or apply either too much or too little strength in the raising and lowering of the arm movements during Qigong practice. Both the alignment and energetic function of the patients' arms, hands, and fingers should be checked.
   a. If the arm movements are too dynamic, they will cause an abundant amount of energy to become either gathered or dispersed; this results in Qi deviations.
   b. While performing a tonification exercise, if the palms of the hands are turned outward, away from the body (instead of inside facing the body) this can easily cause diarrhea or a Qi Deficiency.
   c. If the fingers move up to point at the chest, the energy released from the hands can cause tightness in the patients' chest. If the patients' hands point obliquely at their neck and face, the emitted Qi can cause dizziness, nausea, and edema of the face in those patients who are sensitive to the energy movement within their channels and collaterals.

RESPIRATORY DAO YIN DEVIATION

Deviations in breathing often result from the incorrect practice of the deep inhalation and exhalation methods, when first starting Qigong meditations. Both inhaling and exhaling should be gentle, thin, even, and long. When practicing, the patient should breathe properly and naturally to regulate the breath and should avoid holding the breath.

1. Deviations can be due to improper exhalation. Determine whether the exhalation is long enough for relaxation and quiescence when sinking the breath. Excessive sinking of the breath, however, can cause pain in the legs by depleting Qi flow to the upper torso, and by increasing the weight and gravitational pressure within the tissues of the lower torso. Exhalations that are too long or too deep can cause shortness of breath, headaches, tightness in the chest, discomfort in the Heart, and abdominal distention.
2. Deviations can be due to improper inhalation. Determine whether the inhalation is long enough for relaxation and quiescence. For example, when practicing the Abdominal Breath Holding technique (the Two Inhaling and One Exhaling Method, which employs Reverse Breathing), the two inhalations should not be connected, for tightness in the chest will occur. Pause, therefore, between each breath and allow the exhalation to be fast and short rather than sustained and drawn out. Otherwise, the condition will cause general weakness and fatigue.

To rectify this condition, when you inhale twice through the nose, simultaneously pull in the navel and perineum area as if to lift your body. When you exhale through the nose, guide the Qi down into the Middle Dantian.

If this method is applied, the symptoms such as tightness in the chest, shortness of breath, and abdominal distention will disappear (The Rectifying Respiratory Qi Deviations exercise can also be used). When the breath is well regulated there will be no difficulty sinking the Qi down to the Lower Dantian.

3. Deviations can be due to improper tone resonation. Another Respiratory and Mental Dao Yin deviation can be created through the improper use of healing words or tone resonations. The improper use of tones (with too much breath or mental concentration placed on the rising and falling sound) may cause symptoms such as dizziness and slight fever, tightness in the chest, weakness in the legs, foul breath, and bloody stool.

These symptoms cannot be relieved by Western medicine. Some patients, however, have succeeded in rectifying such deviations by practicing the Opening and Closing the Three Dantians exercise (see Chapter 15). This exercise is used to regulate the Excess Yang, and to restore the body's energetic equilibrium.

Some patients are given the prescription of uttering one pitch sounds (known in China as the first or straight tone). This straight sound has a steady tone, and a rising volume, which can easily cause the energy to ascend. After the patients have completed their prescription and ended the exercise, if the energy continues to rise, the Qi deviation will cause dizziness and nausea. In this particular case, the patients should stop the exercise immediately. To rectify this condition, have the patients utter the sound in the third tone (the descending and ascending tone), and by deepening his or her voice, then raising the pitch. This increasing volume and deepening tone relaxes the body and causes the Qi to descend.

This example illustrates the fact that if the patient is allowed to select any prescription at random for mental concentration, without understanding the theory of Medical Qigong, he or she can easily get into trouble.



Figure 18.2. Rectifying Respiratory Qi Deviations

4. To rectify respiratory Qi deviations, the following exercise can be used. It will amend respiratory deviations and balance the Yin and Yang Qi, as well as clear any stagnant Qi.

When the practitioner feels uncomfortable after Medical Qigong exercises, practice this method for 20 minutes. This is an alternate nostril breathing exercise and requires both inhaling and exhaling through the nose. The abdomen expands upon inhalation and contracts upon exhalation.

From a seated posture, begin by imagining that there are three channels that start at your tailbone and travel up the body. The first channel intersects with the right nostril, the second channel joins the Baihui GV-20 point and the third channel intersects with the left nostril (Figure 18.2).

Place your left hand on your Lower Dantian, with the right hand resting on the nose. It is important to focus the mind on the energetic flow of the breath. Inhale through the left nostril and allow the Qi to flow down the Conception Vessel into the Lower Dantian and tailbone area. Hold the breath, pinch the nose and draw the Qi up the Governing Vessel into the Baihui area, and then circle the energy down to the Conception Vessel to the coccyx to complete the Microcosmic Orbit. Exhale through the right nostril. Repeat this sequence, alternating the focus of the mind's concentration to follow the beginning flow of energy from the left to right nostril and visa versa.

When training in Medical Qigong prescriptions, it is equally as important to relax the mind as the body. Therefore, this exercise should be practiced in a leisurely manner, with a carefree attitude, and a smile.

MENTAL DAO YIN DEVIATIONS

Deviations in mental activities are primarily caused from excessive thinking and too much focused concentration. These type of mental deviations should be rectified by controlling one's mental activities. It is important to fully understand the foundational principle of the Shen controlling all mental activities that determine the physical, emotional, and energetic activities. Any mental deviation should be regulated and controlled through intention.

It is sometimes difficult for patients who have just started Medical Qigong prescriptions to become absolutely tranquil; this may lead to mental Qi deviations. One way mental Dao Yin deviations can be rectified is by a mantra, or counting breaths (using one thought to replace many thoughts). After this technique is mastered the patients can advance to concentrating their mind on an external object in the surrounding area.

1. The cerebral cortex plays an important role in Qi deviations of the mind. Medical Qigong regulates the cerebral cortex to restore balance to the energetically unbalanced parts of the brain. If the mind is agitated or depressed for a long time, it can cause a long term disorder of the whole nervous system and, thus, cause various kinds of chronic diseases. A healthy nervous system takes the leading role in adjusting, regulating, and unifying all functional activities. It is responsible for maintaining a dynamic equilibrium.

   If deviations occur during Medical Qigong practice, the cerebral cortex loses control of the nervous system. Abnormal phenomena may occur and mental and emotional activities may become uncontrollable. If patients are not careful, they can actually develop meditation induced diseases, or meditation induced psychosis known as Tsou Huo Ru Mo, which translates to "the Fire becomes Excessive and the demons enter." In other words, the patient's Heart and Liver become overheated, causing the Hun to leave and Po to take control of the body. This in turn can lead to chronic psychoses or demon possession.

   Because Qi deviations can have serious consequences, the Qigong doctor must have an extensive knowledge of Medical Qigong principles to prevent and correct Qi deviations, stagnations, and adverse Qi flow. The mind should, for example, always be free from overconcentration or "distortions of consciousness" during practice. If a beginning patient feels a hot sensation in certain parts of the spine, and tries to force its energetic movement up through the Five Passes of the Governing Vessel (see Chapter 30), this can cause "distortions of consciousness" and mental confusion, which may result in hallucinations.

   A deviation caused by excessive focused mental concentration can also lead to a loss of self-control and produce such disorders as uncontrollable head-shaking, shoulder shrugging, hand and leg quivering, stumbling, staggering, uncontrolled crying or laughing, or even stiff and twisted extremities and opisthotonosis. To avoid this loss of self-control, do not allow the patients to use their mental intention and focused concentration at random, but rather have them focus their attention on quiescence to tranquilize the mind and recuperate their health.

Failure to properly lead and guide energy during Medical Qigong practice may also cause adverse deviations of Qi in the patient's Middle Dantian. In the Middle Dantian, the patient's Lung Qi rises and returns through the opening and closing actions of the Shan Zhong CV-17 point. If the Qi within the Middle Dantian begins to deviate, it can condense and cause stiffness, pain, and a feeling of suffocation in the chest region. To correct this condition the Qigong doctor extends energy into the patient's Middle Dantian to regulate and tonify the patient's Qi, and especially the Gathering (Zong) Qi. This treatment also regulates and tonifies the patient's Lungs and Upper Burner, as well as diffuses any Rebellious Lung Qi (see Chapter 22) as it unburdens the emotions of the Heart.

2. There are three rules for determining proper mental focus. The following three rules determine the focus of the patient's mental activities and are implemented to help avoid Qi deviations while practicing Mental Dao Yin training:
    a. Concentrate the mind on a motionless object. A patient suffering from hypertension can, for example, concentrate on still lake water, but not on a stormy sea.
    b. Concentrate the mind on a near object. A patient with Liver trouble can, for example, concentrate on a nearby pine tree. If the patient is at a park, absorbed in concentration on a pine tree that is far away, the patient must mentally trace and locate the pine tree with painstaking effort. This is achieved through expanding and extending the imagination. If the patient suddenly becomes mentally distracted or preoccupied, the purpose of the meditation is defeated. Once distracted, it will be very difficult for the patient to reconnect to the pine tree because of its distance. As a result, the patient's mind wanders and the patient may become discouraged.
    c. Concentrate the mind on a familiar object. Concentrate on something which creates a peaceful, emotional connection. The emotional connection will facilitate the proper attitude and diminish any likelihood of mental strain.

    When deciding on which familiar object to focus the attention on, patients must not choose a person, their own work or creations, or obscene things. Objects that have been used to do harm or evil should also be avoided. Patients are also forbidden to shift their thoughts from one thing to another or back and forth without stopping. Remember that it is the individual's Shen (Spirit) which guides all mental activity and determines the body's energetic actions, therefore the mental concentration should have purpose.

Adjust each technique according to the specific case. When prescribing Medical Qigong therapy, it is important for the doctor to adjust each meditation and exercise according to the patient's specific case. In all cases, the Yi (imagination and intention) must lead the Shen and the Shen must lead the Qi.

The following examples demonstrate how to adjust prescriptions for different patient's needs.

- Patients with hypertension should concentrate on a low place instead of a high place, or on an object below eye level.
- Patients with hypotension (including other Deficient conditions such as anemia) should concentrate on a high place instead of a low place, or on an object placed above eye level.
- Patients with Lung problems such as tuberculosis should concentrate on white and light objects (e.g., white clouds).
- Patients with Spleen and Stomach diseases should concentrate on yellow objects (e.g., yellow chrysanthemum, dahlia).
- Patients with Liver problems like hepatitis should concentrate on green objects (e.g., pine and cypress trees).
- Patients with a Heart Deficiency should concentrate on red objects. Patients with an Excess conditions of the Heart, however, should

never concentrate on the color red, and should only choose pink objects instead. A pure red color is too energetic for patients with Excess conditions and may overexcite their Heart, making it difficult for the patient to become relaxed.

- In Medical Qigong, the color black is sometimes assigned to the Kidneys. Focussing on this color can, however, easily cause the Kidney energy to sink downward, creating an emotional state of depression or anxiety. Therefore, when treating patients with Kidney diseases, it is preferable to choose things of purple, indigo and vibrant blue color.
- Mentally depressed patients (in a severe cases) should not practice any dynamic Qigong exercises until their depression has passed. Otherwise, they may develop headaches, tightness in the chest, or in severe cases, shock. To rectify this condition, the Qigong doctor must lead the toxic and stagnant Qi downward along the channels and out of the body.
- Patients with uncomfortable light or heavy sensations should concentrate on the opposite side on their body instead of the afflicted area. If they feel that their lower limbs are too heavy to lift during the exercises, for example, they can correct this symptom by focusing on the Baihui GV-20 point at the top of the head. If the patients feel that their body is too light and unsteady, they can focus on the Yongquan Kd-1 point located on the soles of the feet.

STRESSFUL LIFE ACTIVITIES

Stressful life activities create a flood of adrenaline within the body. This occurs not only from the core of the adrenal gland in the medulla (which responds to stress by releasing adrenaline in to the blood stream), but also from the endings of the vertebral lumbar division at the core segment of the major internal organs. Adrenaline spreads throughout the body and activates not only the body's sympathetic nervous system, but also the adrenal glands. The Heart rate, respiratory rate, blood pressure, and Blood flow to the muscles are all increased as they respond to the "fight or flight syndrome."

When this happens, the immune system is called upon to balance the whole stress mechanism and is, therefore, called away from its normal activities which include monitoring cellular activity and fighting the growth of disease. A life of constant stress, therefore increases susceptibility to illness. Meditation takes the patient out of the stress mode, thereby shutting down the adrenal glands, and allowing the immune system to return to its normal functioning.

Chronic stress wears down the mind and body, thereby producing anxiety or depression. Stress begins with an overexcitement of the nervous system and then slowly works its way deep into the body like wet cement, causing the shoulders and upper back to become tense and rigid. Happy occasions (such as weddings) and other normally pleasant events, also produce stress, which can be detrimental when the patient's life style is not properly balanced. An unstable life style is very stressful and can lead to depression, anxiety, and Qi deviations. The capacity to bear stress depends upon the individual's constitution, diet, support system (or lack thereof), the nature of the stress, and the congenital strength of the nerves. When stress levels surpass the nervous system's capacity to handle them, "the nerves break down", resulting in all sorts of physical, mental, and emotional disturbances. Certain neurotransmitters are depleted, leading to a chemical imbalance which can be aggravated by self medication (e.g., alcohol or drug abuse). These disturbances, if unheeded can eventually lead to organ malfunctions, cysts, tumors, cancer, and premature death. In order to avoid such states, a balance between work and rest must be maintained.

At a conference of the International Society for Neuro-immunomodulation (entitled *The Effects of Stress and Depression on Physical Disease*) Dr. Philip Gold, of the National Institute of Mental Health, stated that stress and depression cause the body to secrete high levels of hormones; (for example, cortisol) into the bloodstream. These hormones, if unregulated, can destroy the appetite, cripple the immune system, shut down the processes that repair tissue, inhibit sleeping patterns, breakdown bone density, aid the onset of infection, and even instigate cancer cell growth.

An individual's emotional past determines his or her present state of health, both physical and emotional. Past emotional belief structures are responsible for both creating and healing diseases. Just as thoughts drift through the mind but do not manifest until they reside within a belief structure, so emotional wounding resides within the tissues and cells waiting to be activated by emotional upheavals. Our thoughts materialize via choices and manifest within the body.

In American society, sharing traumatic wounds is often the first act of intimacy and bonding. It provides a common ground for relationships and supports the "pain structure" that deepens the bond. People can become addicted to empowering their wounds which, in turn, support and empower the disease. This exchange of painful personal traumas is reinforced by receiving sympathy and strong empathy, but does not fully release the pain from the tissues.

Although talking about past traumas can begin the process of healing, problems can emerge when these past traumas manifest through the following belief structures.

1. The individuals believe that they can only receive affection and attention when they suffer, and use their "neediness" to keep their significant other(s) from leaving or becoming more independent.
2. The individuals become stuck in one emotion -- anger, grief, fear, worry, or hurt -- and are unable to express a healthy range of emotions.
3. The individuals do not have an adequate support system.
4. The individuals do not have the incentive to heal themselves or the belief that they can be healed.
5. The individuals bond to anyone, out of fear of being alone, as long as they receive the attention they crave.
6. The individuals have low self-esteem and do not seek help or work out their emotional issues; they have difficulty trusting anyone to understand their pain.

The desire for sharing ones pain in order to feel loved can lead to a habitual way of relating to those closest and dearest. When such individuals feel taken for granted, or unappreciated, they may immediately resort to past traumas. If this fails to illicit the desired response, a new trauma or wounding may be unconsciously created to get back the attention and love and need. The individuals may, for example, physically injure themselves in an accident, or manifest a physical illness. This in turn can become an addiction, empowering old wounds and creating new ones, and may lead to chronic illness. The Shen becomes divided to support the new belief structure, and the Qi deviates from its assigned job of protecting the body, thus creating illness. This is not a conscious process, but an unconscious one, which needs to be brought into the patient's awareness to be healed. Then, and only then, can the Yuan Shen and Zhi Shen act as one unit directing the body's Qi towards its proper function of healing.

Because energetic healing occurs in the present and not in the past, victims of past traumas will never heal if their energy continuously regresses to the armored traumatic belief structure. Both the doctor's and the patient's Yi (Intent) must therefore, focus on forgiveness (of self, others and the specific tragic situations) to free the patient from toxic wounds. The patient's desire and determination to be well must reach the degree that they are willing to do anything to get well, including giving up on the "secondary gains" of illness (i.e., risking abandonment, or loss of attention received during the illness). Patients must be encouraged to find new ways to fulfill their needs, and must be encouraged and supported through this difficult transition. This point is illustrated effectively in the following traditional Chinese story.

> There once was a palace official named Cheng Guang Wei who owned a servant named Song Li. As the pressures of life wore on Director Cheng, he began to sink into a deep depression. Soon he began to lose all hope in life and desperately sought relief. Not content with the wine and festivities at hand, his attention soon turned to his servant Song Li, who always seemed to be happy. Song Li was plowing the fields, up to his ankles in

10. Smile to the heart and feel all the good virtuous energy from all the organs flow into the heart and spiral and blend into compassionate energy.



Fig. 6.18 *All the Organs' Positive Energies blend with the Heart to create the Compassion Energy.*

11. Your compassion rises up. Be aware of the galaxy, the cosmos, and expand your compassion through the universe. The universe allows us to be in touch with the universal compassion.



Fig. 6.19 *Expand our Compassion to be in touch with the Universal Compassion.*

mud, singing and seemingly enjoying his life. Upon observing this, Director Cheng walked up to the edge of the field and called out, "Song Li, why are you so happy? What is the secret of your contentment?" To which Song Li responded, "Sir, come into the field with me, and I will tell you." The director, not wanting to get himself muddy said, "No, tell me from where you are." To which Song Li replied, "I cannot explain everything to you if you do not come into the field." Director Cheng, aggravated by this reply, answered, "Very well, since you refuse to tell me, tomorrow you will work in the stables." Song Li answered, "If that is your wish, sir," and went about his work contentedly.

Two weeks went by, and the pressures of the palace were starting to take a serious toll on Director Cheng. All of his problems, it seemed, were insurmountable. Locked in turmoil, he began to roam his property seeking peace until he heard singing coming from one of the stalls in the stables. Director Cheng went to investigate and sure enough, it was Song Li, now up to his knees in horse manure and still singing as beautifully and joyfully as a bird. At first Director Cheng was enraged at Song Li's contentment, but then became perplexed, because the duties of Song Li's new job were much more difficult than the previous work.

Director Cheng approached the edge of the stables and called, "Song Li, why are you so happy? What is the secret of this contentment you possess?" To which Song Li responded, "Sir come into the stall with me, and I will tell you." Repulsed by the stench of the horse manure and filth, not to mention feeling protective of his royal robe, Director Cheng answered, "Song Li, tell me the secret of this joy and contentment that you possess even in the midst of a barn full of stench and dung." Song Li answered, "I will tell you sir, but first you must come in to where I am." "If that is your answer, then tomorrow you will work in the hog pens!" shouted Director Cheng. To which Song Li answered, "If that is your wish, sir," and went about his work contentedly.

Well, things went from bad to worse for Director Cheng in the palace; seeing that he was about to lose everything, he contemplated taking his own life. Making one last round of his property, he again heard singing, this time from the hog pens. Realizing it was Song Li, Director Cheng slowly approached. Sure enough, there was Song Li, up to his thighs in pig dung, slop and filth, and still singing. Leaning against the fence, Director Cheng called out, "Song Li, why are you so happy? What is the secret of your contentment and joy?" To which Song Li responded, "Sir, come into the pen with me, and I will tell you." Director Cheng, now at the end of his rope, answered, "Very well, I will come in with you," and began to climb the fence to enter the hog pen. "Stop!" shouted Song Li, "I will come over to you, it is not right that you defile yourself on my account. But now you will truly listen to what I have to share and are ready to hear the words I speak. For now you are willing to sacrifice all, even your physical comfort, to receive spiritual knowledge and insight."

The moral of the story is clear: unless we are ready to abandon all masks (pretenses and defence mechanisms) of the emotional ego, it is extremely difficult to free ourselves from the toxic emotions that steal our life-force energy and direct our lives. If we are not intimate with our emotions, we cannot perceive the dynamics behind those emotions. After all, emotions are only energy currents which flow in, out, and through our bodies. Because our emotions reflect our intentions, any awareness of unprocessed emotions will lead to an awareness of deep-seated intentions. It is through this understanding that Qigong doctors train their emotions and mental thinking to regulate the Shen.

SHEN DISTURBANCES AND EMOTIONAL DYSFUNCTIONS

All Shen disturbances relate to emotional energetic dysfunctions. Generally, Shen disturbances can be divided into two categories: Yin disturbances and Yang disturbances (Figure 18.3). These

Yin and Yang disturbances affect the patient's thoughts and emotions.

A thought is energy that has been shaped by consciousness. Every experience, or change in experience, reflects intention, desire, and will. Any discrepancy between intention and emotions leads to a splintering reaction of the energetic self, which can cause a breakdown of the body's life-force energy and ultimately lead to disease.

Emotional energetic currents have different frequencies, resonating between low (fear, anger, worry, etc.) and high (love, forgiveness, joy, compassion, etc.). Lower frequencies deplete the physical body, draining it of its precious reserve of life-force energy. This deterioration begins to manifest in the spiritual fields of energy surrounding the body, and percolates down to the emotional, mental, and finally the physical level. Conversely, high frequency emotional energy raises the body's energetic frequency and begins to radiate outside the physical body. This does not mean that the patient must learn to suppress feelings of anger, hurt, etc. These are natural emotions that serve a positive function in protecting the individual from harm. It is only when emotions are suppressed, denied, and accumulated that they become highly toxic to the body. When this happens, new anger is fueled by old anger. The new hurts are suddenly blown out of proportion (related to the event), fueled by ancient emotional pain, until the patient's physical structure is overwhelmed.

Patients may become overactive and overemotional when under stress, when their energy becomes disrupted. Every emotional disturbance alters the breathing pattern, changing from slower to faster respirations (each breathing pattern varying according to the internal organs involved).

According to *The Yellow Emperor's Inner Cannon* (Spiritual Axis), the Blood, Ying, Jing, Qi, and Shen are stored in the Five Yin Organs (Liver, Heart, Spleen, Lungs, and Kidneys). An Excess condition will cause any of these components to leave their respected organs. This will:

- deplete the patient's Jing (Essence),
- cause the patient's Hun (Ethereal Soul) and Po (Corporeal Soul) to become unsettled,
- cause the patient's Zhi (Will) and Yi (Intention) to become muddled, and
- cause the patient's Shen (Spirit) to leave the patient's body.

Shen Disturbances	
Yin	**Yang**
Qi is compressed.	Qi is expanded.
Patient is depressed, withdrawn.	Patient is manic, expressive, impulsive, volatile.
Patient is too quiet.	Patient is too loud.
Patient avoids feelings.	Patient inappropriately expresses feelings.
Patient is too introverted.	Patient is too extroverted.

Figure 18.3. Shen Disturbances

When emotionally upset, energy literally rises upward, affecting the organs and releasing additional emotions stored within the tissues. To become free from these emotional reactions, patients must be taught to relax and release the energetic charge of emotions. This will allow stagnant Qi to become energetically discharged from the body. By cultivating a healthy attitude, and not holding onto, or suppressing, the emotions, the body will begin to seek its energetic balance naturally. This is initiated by having the patient sink his or her Mind and breath deep into the Lower Dantian to rebalance the life-force energy.

TREATMENT TECHNIQUES

When treating patients with Shen disturbances, the Qigong doctor categorizes the emotional and thought dysfunctions into Yin and Yang Shen disturbances.

1. In Yin Shen disturbances the patient's energy compresses inward. These patients have a tendency to avoid feelings, becoming quiet, withdrawn, and depressed. They also tend towards an introverted personality and posture.

   When treating patients with a Yin Shen disturbance it is important for the Qigong doctor to redirect the patient's Shen towards specific actions, and encourage them to use spiritual mantras and affirmations to gain inner strength and confidence.
2. In Yang Shen disturbances the patient's energy expands outward. These patients have a tendency to express their feelings, are loud, impulsive, volatile, and manic. They also tend to be extroverted in personality and posture.

   When treating patients with a Yang Shen disturbance it is important for the Qigong doctor to redirect the Shen (with a "reality check" towards the patient's actions) and set parameters for their boundaries. A sudden awakening to the responsibility of personal actions will generally send the patient into emotional shock.

   One treatment technique commonly used in the clinic to calm and restore harmony in the patient's Shen (due to a Deficient condition) is for the Qigong doctor to extend Qi into the patient's Middle Dantian and Yellow Court areas. Once this area has been sufficiently balanced, the doctor then ends the treatment by rooting the patient's Qi, by drawing it into the Lower Dantian.

PRESCRIPTIONS AND HOMEWORK

Several of the most recommended meditations used for the purpose of calming the patient's Shen are listed as follows.

1. The Energy Melting Meditation is used to relax the body and reduce stress. Relax and imagine melting from the top of the head to the bottom of the feet, like ice melting into water and water flowing downward into the Earth. This image centers, grounds and roots the Mind.



Figure 18.4. During the exchange of Fire and Water meditation, the fusion of Heart Fire and Kidney Water creates steam.

   If the patients are lying down, have them feel the upper layers of their body melting through the lower layers and into the Earth. Ice melts into water and pours into the Earth.
2. The Exchange of Fire and Water Meditation unifies the energies of the Kidneys (Water) and the Heart (Fire) and is often called the Fusion of Kan and Li. It is used to unify opposite principles within the body, to balance the energies of the mind, body, and Prenatal and Postnatal Shen for creating wholeness. It also strengthens the immune system and the bones, thus slowing or preventing osteoporosis.

   Sit and begin by breathing naturally, while inhaling and exhaling through the nose. Visualize the Lower Dantian as an ocean of water, and the Heart as a ball of fire. Imagine the waters of the Lower Dantian beginning to flow up the center of the body, reversing their natural flow. Now imagine the Fire of the Heart beginning to descend the center of the body, reversing its natural flow. As the Water and the Fire join in the Yellow Court (located in the lower part of the solar plexus), the Water vaporizes and becomes steam (Figure 18.4). This hot mist travels throughout the entire body. It should feel warm and pleasant.

Next allow the hot mist to enter into your bones and flow through the Marrow. Imagine this mist beginning to solidify and harden making your bones solid and radiant with white light. Upon completion of the meditation, relax and allow the images to disperse as you sink into the Wuji.

These following exercises are a series of meditations used in the clinic for detoxifying emotional stasis.

3. The Sun and Moon Meditation is used to detoxify emotional stagnation and establish physical, emotional, and spiritual clarity.

   Begin from a sitting or Wuji posture (Figure 18.5). Inhale and exhale through the nose. Imagine the sun over the left eye, and the moon over the right eye, appearing side by side over the head. Feel their presence over the Baihui point, at the top of the head. Imagine that the sun (on the left side of the body) pours golden light, and the moon (on the right side of the body) pours silver light. Both streams of light meet at the Baihui point on the top of the head, combining into white light energy. This white light energy pours into the body, filling the entire body from the feet to the top of the head (like a pitcher of water filling a glass). Once the body is completely full, the energy begins to spill out of the pores. At first a thick, black, sticky energy pours out of the pores, and flows down to the ground. This energy contains all the physical, mental, emotional, and spiritual toxins that are being released from the body. As more and more of these toxic substances leave the body, they start turning from black to gray, then from gray to white. Feel the body radiate this white energy in all six directions (front, back, right, left, up, and down) filling the entire room. After several minutes of purging and tonifying the body, relax the mind and focus your attention on to the Lower Dantian, before ending the meditation.



Figure 18.5. During the Sun and Moon Meditation imagine that the white light energy that is pouring down the body, is purging toxins from the internal organs, releasing the Evil Qi out from the pores.

4. The Releasing Emotional Blockages and Energetic Armoring Meditation is used to dissolve emotional blockages from the internal organs. When these blockages are released, the emotions are restored to balance. Begin from a Wuji posture, and inhale through the nose and exhale through the mouth.
   a. Direct your attention to your Liver. Every time you inhale, visualize and feel the emotions of kindness and compassion entering into your Liver. As you exhale, release anger or jealousy. Repeat for 18 breaths.
   b. Direct your attention to your Heart. Every time you inhale, visualize and feel the emotions of joy, contentment, and tranquillity entering into your Heart. As

you exhale, release nervousness and excitement. Repeat for 18 breaths.

c. Direct your attention to your Spleen. Every time you inhale, visualize and feel the emotions of trust, openness, and sincerity entering into your Spleen. As you exhale release worry, obsessiveness, and self-doubt. Repeat for 18 breaths.
d. Direct your attention to your Lungs. Every time you inhale, visualize and feel the emotions of dignity, integrity, and courage entering into your Lungs. As you exhale release grief and anxiety. Repeat for 18 breaths.
e. Direct your attention to your Kidneys. Every time you inhale, visualize and feel the emotions of self-confidence and inner strength entering into your Kidneys. As you exhale release fear and loneliness. Repeat for 18 breaths.
f. Finally, inhale, visualize and feel the emotion of a full-bodied state of peace and bliss. As you exhale, ripple and resonate this feeling into the room, filling the surrounding energetic space with this emotional enlightenment. Repeat for 18 breaths.

DISTURBANCES DURING QIGONG PRACTICE

The patient should carefully choose a safe and quiet environment for Medical Qigong exercises and meditations. Most often a patient is already in a state of relaxation when they become startled by disturbances generally caused by an unexpected sound or event. This sudden disturbance can disrupt the Heart Qi. When training, if you become startled, do not open your eyes. If you open your eyes, the disturbed energy will be thrown into disarray, causing a blockage of vital Qi (usually in the Heart). This reaction will cause deviations which can be difficult to rectify.

If instead you continue exercising with your eyes shut as if nothing had happened, you can restore your mind to a normal state of quiescence, by guiding the Qi up the Governing Vessel and down the Conception Vessel (i.e., the Microcosmic Orbit). Even if you were shocked by the un-



Figure 18.6. The doctor strikes the patient's Mingmen area and focuses his or her attention to lead the disruptive Qi downward into the Earth. This helps the patient stop the uncontrollable muscle deviation spasms.



Figure 18.7. The doctor directs energy into the patient's foot, through the Lv-3 point, rooting the patient's Rebellious Qi into the Earth.

expected sound or event, restore the mind to a normal state of calmness by immediately performing the Opening-and-Closing the Two Dantians technique. The two Dantians refer to the Upper Dantian (Yintang point) and the Lower Dantian (Qihai point) areas (see Chapter 20).

To perform this technique, raise both hands to the lower jaw and breathe in with a hissing sound as if inhaling a mouthful of cold air. After the inhalation, the hands will move up to the Upper Dantian, and perform the opening exercise while exhaling slowly. Next, exhale while closing slowly. After four repetitions move the hands to the lower abdomen and perform the Opening and Closing of the Lower Dantian four times.

Usually the emotions will calm down after performing this exercise four times. If you still feel uncomfortable, you can perform the exercise eight times or more, until you become calm.

Note: It is good to ensure a quiet, safe environment in which to practice, preferably a place outside, with fresh air, among flowers, grass or thick, healthy green trees. Because the inside of the body matches the outside environment, when searching for specific directions to face while practicing Medical Qigong, it is important to avoid training in or near:

- extremely intense direct hot sunshine,
- a cold strong wind,
- a thunder and lightning storm,
- old withered trees,
- old graves or tombs,
- electric generators, power lines or power plants,
- dump sites,
- polluted sites, rivers, etc., and
- do not practice shortly after earthquakes, tornadoes, hurricanes, hailstorms, etc.

UNCONTROLLABLE MUSCLE DEVIATIONS

Sometimes a patient's body begins to automatically quiver, shake, tremble, or vibrate, revealing an energetic re-patterning causing muscle movement which cannot be stopped. When this happens, part of the body often keeps moving for several hours, causing exhaustion. Sometimes Qi in the legs and Heart rushes into the head, compounding the problem.

For older patients this is considered a dangerous symptom because their lower extremities are generally weaker. In mild cases the patients feel energy rushing upward into their head. In severe cases the whole body trembles because the Qi leaves the Conception and Governing Vessels and empties into the body itself. In these extreme cases energy muscle patterning should be controlled in the following manner.

1. Advise the patient by saying, "It is time to relax and calm down. You need to end your exercise and rest." This method is usually very effective when repeated over and over, again. If the patient is unable to stop, perform the next method.
2. Direct the patient to place their left hand on the Middle Dantian and the right hand on top of the left hand. Tell the patient that you will help them stop by striking their Mingmen area (Figure 18.6). Press their right hand with your left hand, to compress their Middle Dantian, while using your right palm to strike the patient's Mingmen three times, directing your attention down to their feet. This can help them stop moving.
3. If the above two methods do not help, direct the patients to turn their right foot inward with the big toe pointing at the heel of the left foot. If they cannot do it without help, take their left hand in your right hand and with your foot push the big toe of the patient's right foot to point at the left heel. That should stop the movement.

   Next, touch the patients' Taichong Lv-3 point, between the big toe and second toe, with the "sword fingers" Qi emitting technique. In this technique, the doctor uses the index and middle fingers to emit Qi into the patient and guide their Toxic Qi down into the ground (Figure 18.7).

RECTIFYING QI DEVIATIONS USING TAIJI RULER

If patients are experiencing too much Heat, they are concentrating too much and need to change the position of their tongue and perhaps



Figure 18.8. The Qi regulation exercises of the Taiji Ruler system are excellent for correcting Qi deviations.

switch meditations. The Taiji Ruler is very effective in rectifying deviations caused by inappropriate tonification or purgation, and can be used to dredge the channels and collaterals to promote the flow of Qi and Blood.

When performing this exercise, the rotation of the Ruler upward and outward (away from the body) is generally used for leading and increasing the energetic flow of Qi and Blood in the upper extremities. The downward and inward rotation of the Ruler is generally used for leading and increasing the energetic flow of the Qi and Blood in the lower extremities.

The purgation of energy blocks are usually cleared through downward movements (from Heaven to Earth). Tonification is implemented through upward movements (from Earth to Heaven). Using these methods, the patients can amend their deviations and promote the increase of Qi (Figure 18.8).

CHAPTER 19
DISORDERS AND DEVIATIONS OF THE SOUL AND SPIRIT

INTRODUCTION TO SPIRITUAL DIMENSIONS

An accepted reality in Medical Qigong therapy is the body's relationship to both the physical and spiritual world. The physical world of the living is considered a Yang state of existence, while the supernatural-spiritual world is in a Yin state of existence. Once the Qigong doctors' Shen has reached a high state of sensitivity, they can transcend their normal conscious perceptions and senses, to observe, and even communicate with the spiritual Yin world (see Six Transportation's of Shen, Chapter 13).

Within the subtle realm of the spiritual world, the existence of spiritual entities and ghosts are divided into two divisions of Yin and Yang (Figure 19.1). There is a significant difference between spiritual entities and ghosts.

1. A spiritual entity belongs to the Yang category of the Subtle Realm, and comes from the formation of nature. Spirits are considered the ethereal beings of the universe, who depend on the absorption of natural energy and are affected by the energetic cycles of the Earth. They are conscious beings, able to transform themselves into any size, shape, animal, or being (shape-shifting). A spiritual entity can affect changes in electrical current within the body's energy fields, or control certain areas on the body's nervous system. Spiritual entities can be separated into two divisions: Yang (good) and Yin (evil) influences.
   a. Yang spiritual entities are commonly referred to as angels, guides, spirits of the light, enlightened masters, and similar positive beings. These spiritual entities assist mankind (communicating through the body's Hun) in their quest for enlightenment. They assist individuals to make beneficial decisions that promote spiritual maturity.


Physical World
Spiritual World
Yang
Yin
Yang
Yin
Qi
Shen
Jing
Projection of Qi and Shen, Spirit Travel, Soul Travel
Yang Spiritual Entities
Yin Ghosts
Yang
Angles, Guides, Spirits of the Light
Yin
Devils, Demons, Spirits of Darkness
Yang
Phantoms, Free-Floaters
Yin
Poltergeists, Banshees

Figure 19.1. The Spirit World

   b. Yin spiritual entities are commonly referred to as devils, demons, spirits of darkness, evil spirits, and other similar negative spiritual manifestations. Yin spiritual entities challenge mankind (communicating through the body's Po) by confusing the human spirit. If given the opportunity, these spiritual entities can possess an individual and become extremely territorial.

2. Ghosts or Gui, as they are commonly called in China, belong to the Yin category of the subtle realm. Ghosts are developed from the subtle form of the combined spiritual essence of an individual's Eternal Soul. When the body dies, the energies of the Corporeal Soul (Po) enter into a state of rest, returning back to the Earth, thus allowing the Ethereal Soul's (Hun) to return back to Heaven. The individual's Eternal Soul then fuses with the energies of the Three Dantians (within the Taiji Pole) and is projected outside the body, entering the tunnel of light to return back to the divine. Sometimes, however, because of unprocessed emotional issues, traumatic death, unfinished business, or extreme attachment to people, places, or possessions, an individual's Eternal Soul can begin to wander the Earth, becoming a Gui or ghost. Generally, it is believed that it takes three days for the Corporeal Soul to withdraw their energy completely from a deceased body. Ghosts are considered Eternal Souls that have departed from human life and are unable to detach from their life experiences; they are bound by their unprocessed issues. Ghosts can also be separated into two divisions of Yang (good) and Yin (evil).
   a. Yang Ghosts are commonly referred to as phantoms and free floaters. These disembodied souls can either be lost, confused, delusional, or purposely return in order to guide and protect the living.
   b. Yin Ghost are commonly referred to as poltergeists, banshees, or other names varying by location. These disembodied souls are angry, malicious, mischievous, and destructive.

It is difficult, if not impossible, to be immune to the influence, or encroachment, of the spiritual world. Spiritual manifestations are usually evident through audible sounds, unusual unexplainable smells, extreme cold, and the displacement of objects. Other phenomena include tactile sensations, visual images, voices, and the apparent psychokinetic movement of objects. Spiritual entities seem to move through solid matter and can appear or disappear abruptly. They can also cast shadows and be reflected in mirrors; some seem corporeal, while others are luminous, transparent, or ill defined. Many spiritual entities have jerky or limited movements, while others are lifelike in movement and speech. Encounters with spiritual entities can be divided into five main categories.

1. Spiritual manifestations of the dead generally occur within a short time after the death of the person. Visits from the departed are usually to bring comfort, to announce their role as a guardian, or to complete unfinished business. If an individual's life ends in an untimely manner, or so violently that the soul does not realize the body is dead, the disembodied soul often goes about its daily routines. Occasionally these souls will manifest as mischievous entities, attempting to get the attention of the living, but they lack the malevolence of an evil poltergeist manifestation.
2. Deathbed phenomena are generally of divine beings, religious figures, or luminous apparitions. Visions of previously deceased loved ones, who come to guide the dying soul into the next level of existence, are common occurrences.
3. Manifestations of impending tragedy are visual images of an entity which usually appears in a "waking vision" or in dreams. When they appear, these spiritual entities either communicate about the death or severe crisis of a loved one, or to give warning of an impending tragedy.
4. Reincarnating spiritual entities sometimes appear in a dream to a member of the family into which they will be born. Such dreams are referred to as "announcing dreams."

5. Manifestations of poltergeists are generally mischievous and often malevolent. They may be either disembodied souls, or demon-like entities (see Chapter 18). These disembodied souls were often extremely dissatisfied and bitter while living, and may be unable to reintegrate into the Earth after death, or to ascend into the Heavens. This may cause spiritual hauntings, either around the location of their death or around a person, or persons, that the disembodied souls blame for their life's misery. They make their presence known by assaulting the living, either human or animal. The most common phenomena include: battering with a rain of small stones or sand, throwing and moving of objects, loud noises and shrieks, strange lights and vile smells.
6. The ghostly images of the astral body can be projected and manifested in distant locations as a disembodied apparition. Sometimes the astral body can travel to other locations and actually appear in holographic-like form to others. This image is not actually considered a ghostly apparition (although it may appear so), but the extension and material form of an individual's Eternal Soul.

One example of this type of phenomenon was demonstrated in France in 1908 by scholar Hector Durville, who was researching "traveling clairvoyance." In one series of tests, Mr. Durville and a colleague hypnotized a female psychic to facilitate her astral projection to another location. An observer was placed in another part of the house. The experimenter's instructed the female psychic's to touch, hit, or pull at the observer's body while in her astral body. The observer had no idea what to expect, but felt the touches, strikes and pulling on his body by invisible hands. The astral body was even visible as a whitish apparitional figure to some of the people Durville used as witnesses.

EVIL STATES AND MENTAL DELUSIONS

Sometimes the "spirit world" itself can affect the physical body through a subconscious emotional connection with the individual's Shen. These affected subconscious emotions can never be totally repressed because they will continually surface as dreams, visions, flashes of images, etc., and can only be redirected into either positive or negative actions.

Seeing a spiritual entity or ghost is a normal part of Medical Qigong training and is accepted as a natural energetic phenomena; however, disorders such as schizophrenia and psychosis (delusions and hallucinations, etc.) are considered Qi deviations and can be caused by improper Medical Qigong practice. These mental states are known as "evil states" and are difficult to correct. Evil states also include: infatuation, delusions, obsessions, encounters with seductive spirits, demon oppression or possession, and multiple personality disorder. This does not mean, however, that the individuals suffering from these disorders are themselves evil.

INFATUATION WITH THE TREATING DOCTOR

Infatuation is culturally regarded in China as an evil state. This generally refers to the occurrence of deceptions of the subconscious mind during, or after, Medical Qigong healing, which lead to mental derangement. While under the influence of these self-deceptions, patients display intensely amorous affection towards the doctor. As the doctor's energy becomes more intensified within the patients' nervous system, the patients experience a type of biological euphoria which gives way to feelings of unexpressed emotions, suppressed fantasies, and symptoms of eccentric disposition, such as sluggishness, apathy, or elation.

During treatment, patients become extremely open and vulnerable, as their boundary systems completely dissolve under the influence of the doctor's emitted Qi. The Qigong doctor's ability to channel divine light and compassion may easily be mistaken for displays of personal love toward the patients. Sometimes this divine love has never before been experienced by these patients, making them infatuated with the doctor, who is the apparent source of this love. This is an illusion which can usually be dispelled by the doctor's explanation. When the doctor is unable to dispel this illusion by conversing with the pa-

12. Let them blend and multiply, and flow back to enhance you. You feel your whole body to be filled with the universal compassion. You have such abundance, it overflows.



Fig. 6.20 *Let the Universal Compassion within us overflow.*

Multi-Orgasm Energy Smile to the Sexual Organs



Fig. 6.21 *Smile down to the Heart and feel warm Energy from Heart flow down to Kidney and the Sexual Organs.*

tients, this indicates an underlying, often long standing, mental disorder. Such patients should be referred out to a mental health practitioner for professional counseling.

ENCOUNTERS WITH SEDUCTIVE SPIRITS

On rare occasions, individuals who do not have a strong enough connection with the divine may become susceptible to encounters with seductive spirits. These spirits are known as Incubus (male) or Succubus (female), and tend to manifest in dreams. These dreams can range from the romantic and seductive, to rape and sodomy. Although these encounters occur during the individual's sleep, physical sensations are always a large part of the encounter. Often, once the victim has awakened, the physical sensations continue.

DELUSIONS

This is the occurrence of delusions of the subconscious mind during or after Medical Qigong treatment or training, which lead to mental derangement. A delusion is a false belief brought about without appropriate external stimulation (seen most often in psychoses), and is inconsistent with the individual's own knowledge and experience. Patients suffering from delusions display unsociable and eccentric dispositions, sluggishness, apathy, and trance. Some patients may become very disillusioned and depressed. They may lose confidence in life, and think about committing suicide; others may have symptoms similar to those of psychosis, such as persistent visual or auditory hallucinations. These symptoms occur because of preexisting emotional problems, which the patient has not worked through, or has consistently avoided facing.

In all truth, the practice of Medical Qigong does not create these problems; Medical Qigong can, however, occasionally allow patients to become extremely sensitive to the preexisting unresolved problems that continue to surface into their subconscious mind due to their overactive denial system.

SPIRIT DEMONS

An encounter with the phenomenon known as demon oppression or demon possession rarely occurs during clinical practice, but never the less, it must be addressed. Demon oppression or possession describes the state of mind attributed to the patient who has come under the influence of the "spirits of the objective world." These spirits of the objective world (also called "fallen angles," "spiritually hostile forces," or "demons") can either influence, or inhabit, a patient's thoughts and body. They can affect anyone who becomes open to their influence. Any practice or situation which opens the individual's subconscious mind may increase the person's vulnerability to such states. Spirit demon oppression or possession can occur from:

- misguided or improper use of meditations,
- misguided or improper use of hypnosis, or self-hypnosis,
- indulging in the practice of astral projection,
- meditations that cause adverse psychological side-effects,
- general anesthesia,
- drug and alcohol abuse,
- indulging in the practice of channeling, or Ouija board playing,
- deep emotional or physical traumas,
- indulging in the practice of deviant psychosexual encounters (Tantric sex with the wrong individual)
- exposure to places that are haunted by evil spirits when the individual is very stressed out, or deeply fatigued and depleted, and
- indulging in the practice of "black magic."

When the patient's connection to their Shen becomes extremely Deficient, to a point that they surrender their Hun, the patient's Hun may leave their body and wonder, making them vulnerable to the possibility of spirit oppression or possession.

One of the first things a demon seeks, once it enters a body, is to fulfill its sensual appetite (be it sexual pleasures, rage, or emotional addictions, etc.). A disembodied spirit lacks the ability to feel physical sensations due to the disconnection with its bodily senses (touching, feeling , smelling, tasting, etc.). Thus, it can only satisfy these cravings through someone else's living body. Consequently, if a patient is disassociated from the divine center core, or has little or no boundary system, a condition of oppression or spirit possession may occur. In China this condition is commonly described as, "the Spirit (Hun) leaves and the demon enters, uniting with the body's Po" and must be rectified with spiritual atonements and soul retrieval.

Although such encounters in the clinic are rare, it is still important to recognize and treat these conditions when they occur. While treating patients in China, I was fortunate enough to share my experiences with demon oppressed or possessed patients with certain doctors at the Xi Yuan Hospital. It was refreshing to talk with another doctor about this particular subject, as in America it is difficult, if not impossible, to find other individuals who can discuss such a topic in a clinically sound manner.

In understanding the phenomenon of spirit demons, it is important to realize that in the clinics in China, encounters with these types of spirits are divided into two categories: Projected Spirit Demons from the Subconscious Mind, and Actual Encounters with Spirit Demons.

PROJECTED SPIRIT DEMONS FROM THE SUBCONSCIOUS MIND

Sometimes through meditation, the subconscious mind will release visions into the conscious mind in the form of ghosts, phantoms, spirits, demons, etc. These energetic visions are subjective projections of part of the self, released through emotional arousal. Each color image represents certain feelings and repressed memories within the organ which the subconscious mind is trying to communicate to the conscious mind. This also applies to dreams and nightmares in which the patient is continually being haunted by certain spirits, demons, or monsters. For example:

- A green demon represents the deeply suppressed emotions of anger, rage, and irritation which are connected to the Liver.
- A red demon represents the deeply suppressed emotions of excitement, panic, and even anxiety which are connected to the Heart.
- A yellow demon represents the deeply suppressed emotions of worry and pity which are connected to the Spleen.
- A white demon represents the deeply suppressed emotions of sadness, grief, sorrow, guilt, anxiety, distress, and heartache which are connected to the Lungs.
- A black demon represents the deeply suppressed emotions of fear, paranoia, horror, panic, and terror which are connected to the Kidneys.

The patient's subconscious demonic images may tend to be culturally influenced. Each patient may find himself or herself observing something quite different, but with the same underlying emotion. In modern Western culture, individuals are more likely to dream of thugs and assassins that are threatening and pursuing them, as well as monsters.

ACTUAL ENCOUNTERS WITH SPIRIT DEMONS

These spiritual encounters have an objective reality, as they are true spiritual entities which exist outside an individuals thoughts or feelings. For obvious reasons it is extremely important for Medical Qigong doctors to have a strong spiritual foundation. Without a powerful connection to the divine, the doctor risks absorbing the patients' pathogenic Qi, and may become more vulnerable to "evil states" that may place him, or her, at the mercy of spirit demons who seek to dominate, control, and feed off of the negative emotions of the human body.

The spiritual state of the energetic field controls the emotional field, the emotional field in turn controls the mental, and the mental controls the physical field. This is the spiritual template used in the Medical Qigong clinics in China for initiating the energetic laws of dominance and control over the body's tissues. When there is a spiritual interaction involved, the emotions manifest the outcome. There are two ways a spirit demon can attach itself to the body; through spirit oppression, or through spirit possession.

1. Demon or spirit oppressed patients tend to first have had severe emotional trauma, resulting in extremely low self-esteem, depression, fear, rage, and so on (these are the emotional energies on which the evil spirit feeds). The spirit demon becomes attached to the patient's second field of Wei Qi, drawing energy and sustenance from the patient's chronic release of negative emotions.

   These spirit demons are external energy feeders. They are spiritual parasites which provoke and increase negative emotional reactions. Once the patient discharges these negative emotions into their second field of Wei Qi, the spirit demons then ingest and absorb this energy as food. If, for any reason, the spirit demons leave or abandon the patient's second field of Wei Qi, they will, like a predator, continue to look for their next feeding ground. This is why, in certain families, oppressive dynamics are passed from generation to generation, due to certain congenital spiritual patterns.

2. Demon or spirit possession occurs when the patient's Spirit / Mind (i.e., the focused power of their consciousness) becomes too attached to something; it may leave the patient (becoming a wondering spirit) and not return. The vacuum that is left by the original consciousness leaving its residence can become filled by the spirit of other beings. These alien energies tend to enter the patient's body, replacing their original consciousness (Yuan Shen), which is now lost. The resulting state is one of demon or spirit possession. Because the spiritual quality and stability of the patient's mind is lost, the patient will become increasingly dependent on the alien spiritual consciousness for orientation towards others, and the outside environment.

When either a demon or spirit entity possesses a patient's body, it tends to be extremely territorial and protective. This is because, as the demonic spirit surrounds the very core of the patient's energetic body, it initially has a strangle hold on the patient, feeding and distorting the patient's reality. This results in wild mood swings, and sometimes, in displays of extraordinary intuitions, perceptions, and incredible physical powers.

In most cases the spirits causing the pathology are not of a high order of intelligence; they are more on the level of spiritual bacteria, viruses, or parasites. In some cases, however, spirits can be of a high order of demonic intelligence, such as depicted in the movie "The Exorcist."

EXAMPLES FROM PERSONAL CLINICAL EXPERIENCE

Through my personal clinical practice, I have treated several patients who were actually demon possessed, or demon oppressed. One example occurred in 1992, when a patient came to me with a tumor located on her pituitary gland. The Western doctor who was treating her had suggested that she receive immediate surgery, so as a last resort she came to me.

Knowing that she had written several books that were currently being used in a major university as a standard text, I was quite impressed and even intimated by her reputation as an intellectual. She, being the mentor of several of my students who were psychotherapists, did not ease my apprehension. Although she was elderly, she was very strong willed, and quite opinionated. She requested that I lower the treatment table to the floor before starting the therapy. I thought that this was a little strange, but complied never the less, and so we began the initial treatment with the patient lying supine on the table, placed on the floor.

I always begin each treatment with a connection or "hookup" to the divine After connecting with the divine, the energy of the treatment room changes, as the room's energetic field transforms into a divine healing energetic field. Immediately upon "hookup" something in the patient shifted. Although her eyes were closed, the patient began to thrash about on the table like a wild animal, literally snarling, and gnashing her teeth. The power radiating from her body was quite incredible. I knew and believed, that if she wanted to, this elderly, frail woman, could now lift my body up, and toss it across the room like a rag-doll. I was quite aware of the supernatural power and spiritual demonic form that I was now facing, and knew that my 27 years of martial arts training would not serve me in this situation. To my advantage, I had previous exposure to such spiritual demonic phenomena, and had been successful in dealing with demon possessed individuals. Believing that the current healing work was part of my ministry and life purpose, and having participated in several demonic exorcisms, I was aware of the procedure which needed to transpire.

I began dredging and casting out the demons


Evil Essence
Devils, Demons,
Spirits of Darkness
Divine Essence
Angels, Guides,
Spirits or Light
False Self
Masks and Defense Mechanisms
True Self
Core Self
Personal Subconscious Mind
(filters information in accordance with prior experiences and belief structure)
Creative Subconcsious Mind
(intregrates new knowledge, shifting and changing old belief structure, shedding new light on past expierences)
Reacts,
Engages the Denial System
Conscious Mind
Perceives,
Adds
Intention and Will
Acts,
Analyzes new information and takes action

Figure 19.2. All human beings are subject to divine and evil spiritual influences. These influences can affect the subconscious and conscious mind, as well as the sensory perceptions and physical performance.

one by one, claiming each portion of her body for the glory of Christ (my divine authority). This procedure continued for six weeks, each treatment involved reclaiming certain areas of her body. Beginning at her head, I continued treatment down the patient's body. On the sixth week, when I reached her Lower Dantian, the last spirit demon left her body, and she immediately curled up into a fetal position and began to cry. Her Hun then returned to her body, and for the first time in many years she could feel loving emotions again.

It is important to note, that while the treatments were being administered, the patient was not consciously aware that anything out of the ordinary was happening. She had been so completely detached from her body, that she had no conscious recollection of her own emotional-spiritual field of existence, or its affect on her physical body. She had literally hid within the confines of her intellect, where she felt safe. She was also not aware of being demon possessed, or even that her body thrashed about during each treatment. In effect, she had disassociated from her Yuan Shen during childhood, and thus became dissociated from her emotions. After six weeks of treatment her brain tumor had completely dissolved. But, far more remarkable, was the change in her personality, for she became both friendly and courteous.

OVERVIEW

As mentioned before, once the Qigong doctors' Shen has reached a high state of sensitivity, they are able to transcend their conscious perceptions to sense, observe, and communicate with the spiritual world (Figure 19.2). This ability to see disembodied spirits or ghosts is a normal part of Medical Qigong training and a natural part of energy observation.

These spiritual presences can be seen or felt for either brief moments in time (usually as a hovering image of light, or a dark shadow), or for extended periods of time (usually an encounter). Some of these spiritual entities can also take the form of animals.

Some doctors view these energetic entities as either individuals who are astral-projecting (from the past, present, or future), or forms of energy that can either be ascended spirits of light (divine guides or angels), or fallen spirits of light (demons and hostile forces). In any case, encounters with such entities of the spiritual world should not startle or scare the Qigong doctor, but be expected as a part of the existence of the spiritual domain.

A final important note to make is that, although demon possession is real, the location, or type of the patient's disease, has nothing to do with demonic possession. Demonic possession is related to the disassociation from the Yuan Shen and the absence, or suppression, of the patient's Hun. It is not caused by obstructed tissue formations or physical disease.

After helping the patient uncover any severe emotional trauma, the Qigong doctor should assist the patient in "soul retrieval" meditations, in order to return the patient's Hun back into its residence (the patient's physical body) and to facilitate a strong reconnection to the Yuan Shen. During soul retrieval meditations, patients sometimes talk about viewing certain traumas from different visual perspectives, such as: watching the incident from above their body, or watching from a different corner of the room. The reason for this change in visual perspective is due to the displacement of the patient's Hun once it leaves the body. Although the Hun are outside the body, they still observe, listen, and record. This accounts also for the numerous cases of astral projection during surgery, as well as during near death experiences. Under anesthesia, many patients travel out-of-body and observe in fine detail what the doctors and nurses are saying and doing. They accurately recall the doctors' and nurses' conversations, and the experience of viewing the operation from above the body. These experiences are becoming more documented in recent years partly due to modern techniques in resuscitation, that have made such experiences more frequent. First hand accounts of out-of-body experiences abound in "near death experience" literature.

Similar experiences have been recounted by many physically and sexually abused patients, who, as children, learned to dissociate from the body, and observe the abuse from the ceiling, or corner of the room. In most cases, these adults, and children, do not suffer from multiple personality disorder. Only in the most severe cases does the personality fracture and become multiple.

MULTIPLE PERSONALITY DISORDER (DISSOCIATIVE IDENTITY DISORDER)

Occasionally the Qigong doctor may encounter a patient with a multiple personality disorder. The condition of a multiple personality disorder is generally due to extreme sexual, physical, and emotional abuse during childhood; in some cases, demon possession may also occur. This is a condition in which the patient has developed a split in their consciousness, resulting in the development of two or more distinct identities or personalities that recurrently take control of the patient's behavior and consciousness, one at a time.

It is believed that the original personality splinters during childhood (usually around the age of 6 or 7 years, or as early as 3) creating several different personalties, or personality states, that are disassociated from the patient's original whole personality. The different personalities created can number as few as two, or upwards of one hundred. They are often referred to as alternate identities or simply 'alters.' These alters, in fact, often themselves give birth to more fractured alters, each with its own gender, age (corresponding to the fracturing trauma) and function (or role). Some alters may be very aggressive and protective, others will be more passive and submissive.

Some alters will have different medical conditions from the others, which inhabit the same body. As the patient changes personalities (alters), the internal and external energetic fields likewise undergo changes. Each personality can differ in age and stage of development. In most cases, the personalities are usually unaware of the words, actions, and feelings of the other personalities, especially at the beginning of the treatment. Each personality can exhibit a different set of symptoms, as well as diseases. One personality may have chronic asthma and allergies, but when switching to another personality, the patient may suddenly display healthy lungs but display nearsightedness or high blood pressure.

Usually one personality becomes a helper to the doctor, while another personality may be psychotic, indifferent, and so on. Some of the alters may have access to highly advanced transpersonal states of consciousness, i.e., a finely honed and active psychic realm which may have provided a haven, or sanctuary during the abuse.

TYPES OF ALTERS

Over time, an alter's role in the patient's personality changes. There is a difference between an established personality which maintains both an internal and external role and just a fragment personality (e.g., washes the dishes only). Also, there will usually be a number of child personalities included, as well as adult personalities. The patient's past history of violence is the best indicator of whether there are dangerous alters. Some of the most prevalent personality types of alters are described as follows.

1. The first personality encountered by the doctor, or psychologist, is usually the patient's host personality, not the patient's original personality.
2. The demonic or spiritual personality type is generally found in very religiously oriented patients.
3. The persecutor personality type is generally responsible for the patient's attempts at self mutilation (a very common type syndrome with multiple personality disorder) or suicide. They tend to be children or teenagers. It is believed that these types of personalities are either interjections of the patient's original abuser, or have evolved from "helper" personalities.
4. The helper personality type is generally responsible for providing the patient with the emotional support to counteract some of the self-destructive behavior of the patient's persecutors.
5. The administrator or obsessive-compulsive personality type is often responsible for allowing the patient to earn a living. They generally appear cold and aloof.
6. The imitator, or impostor, personality type generally mimics other personalities and is responsible for handling certain situations that are difficult for the patient to bear.
7. The autistic or handicapped personality type generally emerges when the patient feels that he or she is under intense scrutiny, or feels that he or she is being controlled or confined. They may manifest autistic or catatonic states or become functionally deaf or blind.
8. The promiscuous personality type is generally responsible for the patient's overactive or uncontrollable sexual urges (e.g., nymphomania).

While treating patients with multiple personality disorder, the therapeutic goal is usually to integrate all the different personalities, merging them together through creative visualization (usually using hypnosis). This is achieved by having the patient imagine each personality and subset "alters" merge into one.

Some patients, however, opt to remain multiple, as merging incurs the "death" of others. In such cases, contracts are made with the different alters to keep each other informed of events occurring during their "coming out," and some of the more responsible personalities keep watch over the more self-destructive ones. Due to the complexity of treating multiple personality disorder, and due to the high potential of suicide in multiple personality cases, it is recommended that the Qigong doctor refer these type of patients out to specialists who are familiar with such conditions and their recovery.

SOUL RETRIEVAL AND MEDICAL QIGONG THERAPY

According to the Medical Qigong perspective, one of the major causes of illness is "soul loss" (the loss of parts or memories of the Eternal Soul). On the spiritual plain, the Eternal Soul is the manifestation and sum total of our energetic associations and the energy of the Wu Jing Shen (see

Chapter 2). The Eternal Soul serves as a middle point between the source and organization of all life-force energy. The Eternal Soul is considered the seat of all emotions, feelings, and sentiments. As a crystal grows around a central matrix, so the body grows around the Eternal Soul. In revue, the Eternal Soul radiates energy in all directions, like the sun, and is responsible for life, health, and the formation and growth of the body. In the scope of energetic manifestations, the Eternal Soul expresses its innate qualities as energetic movement, functioning through the physical form (led by the Shen). It is connected to all parts of the body, and its light or energy is reflected through the eyes via the Hun. It is through the influence of the Eternal Soul that all of the body's energetic processes (organs and organ systems) seek wholeness. It knows exactly what is needed in every situation for survival and health preservation, and takes action via the Po. Whole body consciousness is the main characteristic of the Eternal Soul. Without the process of the Eternal Soul, energy would have no specific direction and remain in meaningless activity.

"Soul loss" is not demon possession, but a spiritual illness that causes emotional, mental, and physical disease. When disturbed, the Hun leave the body and the Mind (Shen) wanders off on its own. When the Hun leave and the Shen wanders off for very short periods of time, it is sometimes called, "dissociating" or "spacing out." When the Hun leave for extended periods of time, it is called soul or spirit travel, which generally happens when the patient is asleep. It is believed that if the Hun completely vacate the body, the patient will die. A coma is one example of a chronic physical state where the Hun have left, but are still attached to the body, through the Hun's connection with the patient's energetic Qi field. When a patient is in a coma, the Hun and Shen abandon their residence, wandering about in the astral plane of existence.

The Hun and Po create the sustaining energy for the Wu Jing Shen, which provides the energy for the Yuan Shen. If the Qigong doctor can retrieve the lost parts of the patient's Eternal Soul (the suppressed memories attached to the Hun and Po), then the individual's Shen can be restored back to harmony and health.

REASONS THE ETHEREAL SOUL LEAVES THE BODY

In ancient times, disease was attributed to the Hun having strayed away, or having been stolen. It was believed that the Hun would leave the body through three main incidents: they could be stolen (through deep infatuation), frightened away, or simply wander off. In addition to soul theft or "rape of the soul," some Qigong doctors relate Hun loss to the interference of Gui (ghosts, demon spirits), as well as other human beings (i.e., a broken heart or severe trauma).

Soul retrieval is an essential part of Medical Qigong therapy; the body and mind without the Hun, or the spiritual connection of the Yuan Shen, remain in a suspended state of spiritual and emotional shock. When the spiritual needs of the Eternal Soul are neglected, the Shen begins to disassociate, and symptoms of addiction to drugs or alcohol, obsessions, violence, or deep depression take over (see Chapter 32).

Because we are born understanding hidden spiritual realities, patients will inevitably succumb to various mood swings; these are due to deep emotional pain and experiences that stay within their memory and touch their Heart. A spiritual life of some kind is absolutely essential for psychological health. Traditionally, the Hun are said to suspend themselves midway between the conscious and the unconscious, and that their perceptual modality is neither the mind's nor the body's, but the imagination's (i.e., the Creative Subconscious).

From a clinical perspective it has been noted that the Hun leave the body during severe emotional traumas (i.e., surgery, the death of a loved one, miscarriages, abortions, incest, molestations, physical and emotional abuse, the end of a deep relationship, and the stress of combat). Whenever we experience trauma, our Hun, which are part of our vital spiritual essence, separates from us to survive the experience and to escape the full impact of the pain (Figure 19.3). When patients be-


Gui
(ghosts, demon spirits)
Humans
(a broken heart, the end of a relationship, the death of a loved one)
Severe Trauma
(surgery, miscarriages, abortions,incest, molestations, physical abuse, emotional abuse, the stress of combat, etc.)
Soul
Stolen
Frightened Away
Wander Off

Figure 19.3. Reasons for the Ethereal Soul Leaving the Body

come dissociated, aspects of their personality separate from the mainstream of their consciousness, resulting in gaps of memory loss. An extreme example of personality separation occurs in multiple personality disorder.

When a patient has been violated or wounded in some way and remains in an emotionally present state of mind, within the body, the result usually encompasses feelings of anger from past hurts, grief from present pain, or fear of future harm. If an over-stimulation of the energetic organs occurs, it may wound the patient's Shen, causing the patient to close off from the Yuan Shen, to shut off all emotions. This action is similar to that of a sea-anemone, whose natural response (for the purpose of survival) is to immediately close itself after being touched.

THE PURPOSE OF SOUL RETRIEVAL

The purpose of Medical Qigong soul retrieval therapy (called age regression therapy in Western psychology) is to bring the awareness of emotions back into areas of the physical body, allowing the patient to express and release the feelings and reactions that are the cause and symptoms of his or her disease. This will help the patient transform the trapped, or frozen energy (stagnated Qi), back into its energetic potential to be reintegrated with the Shen.

A Qigong doctor will accompany and tend to the patient's Eternal Soul in times of emotional transformation, including times of crisis, illness, and emotional death and rebirth. This allows the patient to remain in the energetic present time mode. This also results in the relief from symptoms of illness and the return of the patient's personal power, creating the potential for fulfillment in work and rewarding relationships. Some patients may come to the realization that they must quit their job and find another that is more spiritually rewarding. They may also find themselves discarding old friendships and making new ones, as their energetic, emotional, and spiritual fields undergo growth and change.

WOUNDING AND CLOSING THE SPIRIT

The body's Yuan Shen is the main expression of the Eternal Soul as it moves from its inactive state to a state of dynamic activity. The Yuan Shen is the medium or active environment of the Eternal Soul. The Yuan Shen also expresses its energetic influence through a continual interchange between the personal-self and the higher-self through the act of breathing. The Eternal Soul expresses itself specifically through the Yuan Shen, and the Yuan Shen manifests itself through the physical body.

If a person's Yuan Shen becomes wounded (feels attacked, violated, taken for granted, etc.), it begins to close itself off from its environment. When the Yuan Shen "closes", the emotions begin to shut down, and the Hun wander. Depending upon the patient's set patterns, this entire process can occur within seconds. Once the Hun wander, the acquired (analytical) Zhi Shen and surviving Seven Corporeal Souls (Po) take over the body, and the patient responds like a machine (i.e., the patient can still think and function; reflexes remain intact, but he or she is void of interpersonal feelings). Patients whose Shen have closed down cannot make emotional attachments, and live in a state of perpetual hunger. These patients go through three stages of isolation before their spirit leaves.

1. The first stage involves anger and grief.

   Once a patient has been hurt (before his or her spirit begins to close), his or her natural survival energy immediately affects the Liver and Lungs, causing emotional reactions that are a natural response to feeling attacked. Hurt, sadness and anger are natural responses to feelings of rejection, betrayal and abandonment. These emotions reflect a spiritual, emotional and mental protest to feeling insignificant, excluded, and dis-empowered.

   a. The patient's congenital emotions of kindness and compassion, stored within their Liver, instantaneously shut down as the Liver Qi expands violently outward. This energetic reaction gives way to releasing the patient's acquired feelings of anger and rage, stored within the Liver. The energy of anger and rage is projected outward to protect the patient's emotional boundaries. If the patient has deep seated emotional problems, however, the energy can also implode inward creating self-hate.
   b. If this protective emotional reaction is not effective in obtaining the needed results (being heard, honored, valued, etc.), the patient's energetic field rebounds inward affecting the Lungs. Once the congenital emotions of integrity and dignity stored within the patient's Lungs become effected, the Lung Qi becomes obstructed, and the acquired emotions of grief and sorrow are released. The energy of grief and sorrow is encapsulated internally to encase the patient's wounded spirit.

2. During the second stage anger and grief transform into depression and despair.

   As the patient begins to lose hope, the Shen begins to close, causing two reactions.

   a. The patient's Liver Qi becomes obstructed and stagnant. This in turn transforms the emotion of anger into depression;
   b. At the same time the patient's Lung Qi transforms grief into despair.

   The patient slowly begins to feel helpless, hopeless, and empty inside. Because of the increased depression and despair, the patient becomes physically, mentally, emotionally, energetically and spiritually tired, and gives in to feelings of insignificance, unfulfillment and loss of control over his or her life.

3. During the third stage depression and despair transform into indifference and detachment.

   In the final stage, the patient has lost all hope of resolution and gives up entirely. The Shen closes down, and the Hun wander. The patient feels emotionally detached from people, the surrounding environment, and his or herself. The patient wanders around "dead to the world," isolated, internally unfilled, and alone. This creates what is known as a "depersonalization disorder."

   A depersonalization disorder involves the persistent, recurring episodes of depersonalization, characterized by a feeling of detachment, or estrangement from one's self. The individual may feel as if he, or she, is living in a dream, or movie, and responds to life like

Three Stages of Emotional Transitions before the Spirit Closes


Stage #1
Stage #2
Stage #3
Liver
(Qi expands outward, rising upwards)
Anger
Depression
Heart
becomes hurt
Disassociation
(Indifferent, withdrawn, antisocial)
Lungs
(Qi withdraws inward, becomes obstructed)
Grief
Despair

Figure 19.4. There are three stages of emotional transition the patient must experience before their Shen closes and their denial system engages. After these stages are experienced the patient's defense mechanisms take over.

a robot. They may also have the sensation of being an outside observer (to their mental processes, body, or specific parts of the body). This feeling is often accompanied by sensory anesthesia, a lack of affective response, and a feeling of lack of control over their actions (including speech).

Voluntary induced expressions of depersonalization or derealization that are meditative, or cultural trance practices, should not be confused with this involuntary disorder. It is believed that approximately 50% of the population may experiences a single, brief episode of depersonalization, usually precipitated by severe stress. Approximately one-third of individuals exposed to life-threatening danger incur a brief episode of depersonalization. Depersonalization episodes may be accompanied by visual distortions, such as the shape or size of objects, and other people may appear unfamiliar or mechanical. Other common associated features include: anxiety or depressive symptoms, obsessions, somatic concerns, and time distortion. Depersonalization and derealization are some of the symptoms of panic disorders (not due to drugs or medication), which are usually caused by long-standing anxiety and stress. Panic disorder can also be brought on by emphysema and asthma due to the difficulty in breathing.

When the Eternal Soul becomes wounded, the first two stages in closing down the Yuan Shen are caused by the patient trying to repress feelings of anger (stored within the Liver), and sadness and grief (stored within the Lungs). This reaction is incurred because the Liver stores the body's Three Ethereal Souls (Hun), while the Lungs store the body's Seven Corporeal Souls (Po). These two emotions are expressions of the patient's natural protest against the lack of love that their Yuan Shen (which encompasses or contains both the Hun and Po) is experiencing (Figure 19.4).

HEALING THE SPIRIT

The first stage of healing in soul retrieval is to open the patient's Yuan Shen by giving them hope and encouragement. Hope helps the patient's perspective to be positive and restores meaning to life. Once the patient has closed his or her Yuan Shen, it cannot be opened through argument or logic. Instead the Qigong doctor must use a gentle, soft tone of voice expressing compassion and high regard for the patient. The patient must feel honored and valued by the doctor to feel safe enough to release the hurtful and negative emotions.

1. Be aware of the sexual organ and use your hand to cover the sexual center. Smile and feel the fire from the Tan Tien flow down.
2. Recall the time when you were with your loved one and the high orgasmic feeling. Guide the orgasmic energy up to the kidneys, and feel the kidneys charge with Chi and orgasm.
3. Guide the orgasmic energy spiraling up to the small and large intestine, liver, spleen, pancreas, stomach, and up to the lungs, and heart. Continue up to the thymus, thyroid and parathyroid and up to the brain and the senses. Charge them with orgasmic energy, and let the Chi flow back down to the sexual organs and blend and spiral into one multi orgasmic energy.



Fig. 6.22 *Bring the Orgasm up spiraling up to the organs.*

Praise must be used carefully and gradually, since some patients may be as yet, unable to accept a higher concept of themselves. Too much praise may cause the patient to feel "mocked" or "lied to", given his or her very low self-esteem. This type of healing only happens when the patient's spirit is engaged, stimulating the inner emotions and not just the intellect.

Once the patient's Yuan Shen begins to open, it is important for the doctor to increase the patient's hope for interpersonal relationships. This is initiated by using silent mental affirmation, or prescribing positive affirmations in conjunction with vivid visualizations. The patient's imagination can reengage his or her feelings and return them to the body's organs and tissues. Instilling hope and giving encouragement allows the doctor's influence on the patient to be increased.

As the patient's Shen begins to open, it is important for the Qigong doctor to take the time to energetically and emotionally travel with the patient back into the memories of the past, to encounter the precise moment in which the patient's Hun left the body. The choice to return the emotional spirit back into the body must come from the patient's desire to retrieve his or her original feelings, no matter how painful the process. The patient must be ready to reexperience and release these feelings. It is important that the patient's "adult observer" be present in retrieving these painful memories. The "adult observer" refers to the patient's ability to suspend his or her judgemental attitude towards his or herself, and to observe the events that are being released with compassion (i.e., as if they were happening to a friend to whom loving support can be given). This allows the patient to experience true healing with the help of a compassionate companion (his or herself).

Tears often come as the memory of the original trauma releases from the patient's body or flows back into the Mind. Many patients notice that after these experiences their dreams change significantly, becoming more vivid. Also, their life environment as well as their relationships tend to change drastically.

EMOTIONAL REBIRTHING PATTERNS

Often, when patients experience deep emotional and spiritual traumas, they also experience physical sensations which reflect the trauma of their biological birth. These psychophysical sensations are due to the physical, energetic, and spiritual connection each individual has with the maternal host while inside the womb. Although these experiences are natural, they can sometimes be disturbing and even frightening to patients unfamiliar with deep emotional and spiritual transitions. The following are but a few examples of physical rebirthing patterns, and the emotional reactions related to these types of spiritual transformations.

- In patients born with the umbilical cord wrapped around their neck, each time they experience deep emotional and spiritual changes it will feel as if they are being strangled.
- In patients born through C-section, each time they experience deep emotional and spiritual changes it will feel as if they are being torn asunder.
- In patients born through the natural birth cannel, each time they experience deep emotional and spiritual changes it will feel as if they are falling through space with nothing to support them.
- In patients born breech, each time they experience deep emotional and spiritual changes it will feel as if they are being crushed in by all sides and suffocated.
- In patients with mothers who were heavily sedated, each time they experience deep emotional and spiritual change they will feel mentally disoriented and unstable.

SOUL RETRIEVAL MEDITATION

The following comes from my clinical experiences in dealing with patients who are very eager to heal, but reluctant, or unable to tolerate rapid change within themselves. The patients' family dynamics, as well as the quality of traumatic and nourishing experiences they received while growing up, play an important role in shaping their individual personalities. It is an accepted fact within modern psychology that an individual's present emotional life is shaped by the events occurring in the "formative" years (especially the years before the individual can articulate their thoughts and feelings). These experiences sink deep into the individual's psyche, hidden from consciousness through repression and denial. This repression is generally due to the inability to understand and express in words the traumas they suffered.

This particular Shengong (which literally means working with spirit) technique involves creative visualization (in a very relaxed, quiescent state of mind), and is used to gain access to the patient's unconscious past emotional experiences. The goal of this meditation is to allow the patient to free him or herself from the repressed emotional material which systematically surfaces during daily life. These programed emotional responses systematically affect the patient's behavior, causing neurotic symptoms, slips of the tongue, associated dreams, and fantasies.

Many patients believe they are ready for this experience, but in reality they are not yet able to deal with such intense pain. These patients are likely to unconsciously choose the least painful memories in order to test how the doctor will handle their feelings, or fail in the attempt to retrieve the lost parts of the soul. Gradually, as trust grows, these patients will be able to access more painful and relevant memories (this is similar to peeling an onion layer by layer). Sometimes patients try very hard to access the memories and obtain nothing, or very little information, leaving them feeling frustrated. This frustration must then be processed and resolved.

The doctor must instill hope and dispel this frustration by explaining to the patients that they have made an important step forward by seeding the unconscious mind with the request, or concept, that past memories must be recalled. In time, this seed will sprout and give forth results. It just needs a little time to incubate. It is extremely important that the doctor never show disappointment or take away the patients' hope.

In such cases, the patient must be reassured that their higher-self (the observer self) senses that the timing is not right. There may be current issues or events, that must first be worked through for a successful soul retrieval to take place. To have done so now would have resulted in more trauma, or more precisely, re-traumatization. They may need to strengthened and develop more self-trust before trying again. Counseling may be recommended, and in time they will succeed.

Some patients may need several sessions before feeling comfortable enough with just entering and surfacing from trance states, before undergoing soul retrieval. It may be necessary to first retrieve pleasant memories that build self-trust and self-confidence before re-attempting soul retrieval (i.e., learning to fly a kite, etc.).

The Qigong doctor should have some training in hypnosis and hypnotic trances before giving this type of trance inducing meditation to their patients. The doctor should know what to do and be able to identify whether or not the patient is able to connect with their Yuan Shen or "higher self." As the doctor induces trance in the patient through this meditation, the following changes in the patient may be noted:

- a change of color in the complexion,
- a relaxation of the facial muscles,
- a change in breathing patterns, and
- sporadic eye movement (behind closed eyes).

If none of the above signs are noted, the patient may need more time to relax deeply before continuing with the meditation. Suggestions of imagining and feeling the body's tissues melting into the Earth may be given, along with suggestions of taking deep relaxing breaths to calm the patient's Shen.

While performing this meditation the patient may experience all the sensory, emotional, and physical sensations of these repressed memories, causing specific core memories (that have been repressed from infancy and childhood) to be brought to the surface and relived. As the patient experiences these memories, his or her facial expressions and demeanor, will often change, regressing to reveal the appropriate age and period of time during which the original trauma occurred.

This particular method of soul retrieval is divided into two stages. The first stage involves locating the body's three storage chambers of past, present, and future emotions. The second stage focuses on accessing the location of, and coming in contact with, the patient's unconscious repressed emotional traumas.

This meditation must first be understood in depth before it is given to the patient. It is very complex, and is not meant to be simply read through to the patient. Also, the doctor should set aside sufficient time to process what the patient experienced after ending the meditation.

STAGE 1. ACCESSING THE ENERGETIC CHAMBERS

The purpose of this meditation is to locate the patient's three storage chambers which access his or her past, present, and future emotions. This meditation also allows the patient to acquire a starting point, or outlet, for removing these painful experiences.

In this meditation, the patient first concentrates on feeling his or her entire body. Begin by having the patient sit comfortably in a chair, both feet on the floor, hands resting on the thighs, eyes closed, tongue on the upper pallet, and breathing naturally through the Lower Dantian. It is important that the patient relax, feel, and experience the body completely. The patient should also be encouraged to accept and feel everything as one unit, to connect with the Yuan Shen or "higher self."

The Storage Chamber of Past Emotional Memories

In order to find the chamber of past emotional feelings, the patient begins to focus attention on remembering and feeling a painful childhood experience. Once the patient has retrieved the memory and is experiencing the painful trauma, he or she points to the tissue area of the body where the feelings are located. This area is considered to be the current storage chamber, where the patient stores the energy of past emotional memories.

The storage areas change over a period of time, given the fact that the patient continues to process emotions throughout life. Each emotional healing causes the previous energetic holding pattern to die, and a new pattern is to be born within the patient's energetic structure. The chamber of the patient's past usually coincides with a tissue area where the patient is already experiencing disease or discomfort.

The Storage Chamber of Present Emotional States

In order to find the chamber of the present emotional states, the patient focuses attention on feeling the doctor's voice within his or her body. As the doctor continues to speak, the patient feels where the sounds are resonating. Once the patient experiences and locates this tissue resonation, he or she points to that area. This area is considered to be the current storage chamber, where the patient stores the energy of present emotional states.

The Storage Chamber of Future Emotions

To find the chamber of future emotional states, the patient focuses on a specific project that he, or she, is planning to do in the near future. Once the patient experiences slight physical sensations, he or she points to the area where the feelings are located. This area is considered to be the current storage chamber, where the patient stores the energy for future endeavors and future expectations. The patient's current ambitions may change as the patient begins to heal from past emotional wounds and makes life-style changes.

STAGE 2. RETRIEVING THE LOST MEMORIES

The final part of this meditation explores the patient's unconscious feelings and reprograms the destructive subconscious patterning. It is used to access the repressed memories stored within the patient's individual Personal Subconscious, which is hidden from through their denial or defense mechanisms. Sometimes after practicing this meditation, patients will not only gain access to the repressed memories of their infancy and childhood, but will also connect to their life within the womb, as well as their birth-process.

1. Begin by having the patient sit comfortably in a chair, both feet should be placed on the floor, hands resting on the thighs, eyes closed,

tongue on the upper pallet, anal sphincter lightly closed. The patient should breathe naturally, expanding the Lower Dantian with each inhalation, contracting the abdomen with each exhalation.

2. The patient focuses attention on the area of the body where the energy of the past emotions is stored. The doctor directs the patient to imagine opening the chamber of the past emotions, allowing the energy, like steam, to release itself from this area. This steam is gathered to the left side of the body. Once all of the energy has been released, it begins to form into a cocoon shaped cylinder of past emotional memories.
3. Next, the patient focuses attention on the area in the body that stores the energy of the present emotions. The patient imagines releasing this energy from out of the body like steam, creating a second cocoon shaped cylinder. The patient places this second cocoon in front of the body, next to the first cylinder.
4. The patient then focuses attention on the area in the body that stores the energy of future emotions. The patient imagines releasing this energy from out of the body like steam, forming a third cocoon shaped cylinder. The patient places this third cocoon to the right side of the body, next to the second cylinder.
5. Next, the patient imagines that all three separate energetic cocoons are joined together. The energetic cocoons are to be connected end to end, in a straight line, with the past on the left, the present in the middle, and the future on the right side of the patient's body.
6. The patient then focuses attention on his or her Taiji Pole, imagining the energy of the Upper Dantian descending and combining with the energy of the Middle Dantian (where the Eternal Soul is stored). Next, the patient imagines the collected energies of the Upper Dantian, Middle Dantian, and his or her Eternal Soul, descending and combining with the energy of the Lower Dantian. The patient uses the collected energies of the Three Dantians to create an "energy bubble" within the Lower Dantian to surround the Eternal Soul. While focusing on the center of the energy bubble, the patient imagines the Eternal Soul transforming into a small energetic form of his or herself.
7. Encapsulated within the energetic bubble, the small energetic form of the patient's self manifests within the physical body. The patient's Eternal Soul, now in small energetic form, begins slowly ascending the Taiji Pole, leaving the body through the Baihui GV-20 point. As the patient's Eternal Soul leaves, it is still connected to the physical body through a silver energetic cord.
8. The patient's Eternal Soul floats over the three energetic cocoons, hovering over the cocoon shaped cylinder on the left side of the body (to access the past emotional memories). Next, the patient observes the black, oval shaped cylinders, imbedded within the structures of the energetic cocoon of past emotional memories. These dark cylinders are energetic emotional clusters. They contain the memories of hurtful feelings and specific times in the life of the patient when he or she felt humiliation, degradation, shame, rejection, or emotional deprivation.
9. The patient descends into the energetic cocoon of past memories and allows the Eternal Soul to find the particular cylinder which currently needs addressing. In choosing a specific area to work on, the patient's Yuan Shen automatically selects the most relevant material from the patient's unconsciousness.
10. The patient then removes his or her Eternal Soul from the energetic cocoon, bringing with it a specific dark cylinder. The cylinder is removed from its webbing within the walls of the energetic cocoon and placed in front of the hovering soul. The cylinder is still connected to the energetic cocoon through an attached energetic cord. Through vivid concentration the patient focuses on the color of the cylinder emitting light from the Yin Tang (Third Eye) point of the little energetic self. This projected light pulsates and changes the dark cylinder, from black to white. As the cylinder pulsates and changes its color, it begins

to open and reveal the lost memories and unresolved feelings. These memories of emotional traumas are brought to the surface. Some of these experiences may be memories of events where the survival or integrity of the patient's physical body was threatened.

11. Next, the patient connects with the divine (God or "higher power") and begins the process of feeling, expressing, understanding, forgiving, and letting go of the emotional charge attached to the memories. This process of emotional purging is connected to the emotions stored within the patient's Five Yin Organs, and are expressed through the following stages:
    a. Anger, blame, and resentment are stored in the patient's Liver.
    b. Hurt, pain, sadness, and disappointments are stored in the patient's Lungs.
    c. Fear and insecurity are stored in the patient's Kidneys.
    d. Remorse, regret, and responsibility for keeping the painful memories and feelings alive are stored in the patients's Spleen.
    e. Love, understanding, and forgiveness are stored in the patient's Heart.
12. As the emotions begin to release themselves from the energetic cylinder, the energetic debris transforms into a vaporous cloud. After understanding and resolving the emotions contained within the energetic cloud, the patient divides the released energy into either a receiving or discharging cloud of energy.
13. At this point, the patient focuses on the energetic cloud and begins separating the pain and hurtful memories from the knowledge and wisdom gathered from the experience.
    a. First, the patient places those memories gathered from the knowledge and wisdom of the experience on the right side of the room, imagining them as sparkling gold, silver, and white light energy.
    b. Second, the patient places those memories gathered from the pain and hurt of the experience on the left side of the room, imagining them as thick, dark, black energy.
14. The patient focuses on the right side of the room, imagining this energy as bright, pure, and illuminating. The patient then inhales, absorbing the knowledge and wisdom gathered from the past experience into his or her small energetic body. Since this is actually the energy of the patient's soul, the patient's body immediately feels the emotion, energy and spirit becoming empowered, as it can now review these past experiences without the feelings of hurt, pain, and judgment.
15. Next the patient focuses on the left side of the room where the feelings of hurt and pain are stored. The patient imagines this hurt and painful energy as a dark, turbid cloud. Because the cylinder has a direct life line connected to the patient's past, the energetic cord attached from the cylinder to the energetic cocoon must be severed. Once the cord connecting the cylinder to the patient's past is severed, the patient is then truly released from the spiritual and energetic connection of the memory. This is initiated by imagining an angelic being, with the "sword of truth," severing the energetic life line connected to the patient's cylinder. The sword of truth represents the patient's decision to regain his or her power by deciding to no longer suppress and carry the painful memories. Once the energetic cord is severed, it causes the cylinder to vaporize, forming an energetic cloud. The patient then imagines severing any last connection or attachment to these toxic emotions, and releases this cloud of hurt and pain, visualizing it floating up out of the room, through the ceiling, out into space.
16. The patient then imagines that God (the patient's divine healing power) is seated in the Heavens, with ripples and pulsations of love and mercy emanating from the center of this divine presence. The patient visualizes one of these waves of love and mercy form the divine descending towards the Earth. As the wave of love and mercy touches the as-

cending dark cloud of hurt and pain, it immediately explodes and destroys the dark cloud. The moment that this dark cloud explodes, the patient sees the cloud's negative energy transforming into blue crystal drops of divine healing energy.

17. Next, the patient visualizes these bright, fluorescent blue, drops of pure, clean energy descending from the heavens and pouring down like rain on his or her small energetic self, saturating it completely. This energy immediately transfers into the patient's physical body. The patient inhales and absorbs this energy flowing into every tissue of the body, allowing the divine healing light to penetrate and radiate throughout his or her entire being.
18. Next, the patient observes the changes created within the three energetic cocoons. The energy in each cocoon will have shifted slightly, revealing an energetic alteration of the patient's present state of mind, and a change in the patient's future. By transforming the past, the patient has altered the present and initiated a change in the future course of events.
19. Finally, the patient returns his or her energetic bubble (containing the small energetic self) back down through the Baihui point into the Taiji Pole, drawing the energy back into the Lower Dantian. From the Lower Dantian the patient's soul energy will return back into the Middle and Upper Dantians, as well as the surrounding tissues. Finally, the patient reabsorbs the energetic cocoons back into the body, and returns to a quiescent meditation.

THE DOOR TO THE CHAMBER OF MEMORIES

A simple visual meditation can also be used to access the patient's suppressed past memories. This exercise is a form of guided meditation, in which the doctor leads the patient into the imagined hidden parts of his or her own soul.

Begin by having the patient lie supine. Ask the patient to close the eyes and imagine walking down a flight of stairs. Lead the patient through three separate doors, descending three separate staircases (this is performed in order to arrive at the patient's "chamber of memories").

After entering through the last door, the patient descends one final staircase until he or she reaches the chamber of memories. This is where all of the memories of the patient's past traumas have been kept, hidden deep within the subconscious mind.

Inside the Chamber of Memories, the patient discovers dark cylinders of past emotional pain. Each cylinder represents a specific trauma experienced and stored within the patient's energetic field. The patient then makes a decision to heal and free the body of the enormous energetic field used to suppress certain memories. To heal and dissolve the energetic cyst, the patient follows the same process of eliminating past memories (repeating section 8 through 15 from the previous meditation).

Once this process is completed, the Qigong doctor guides the patient back up the flight of stairs, through the three doors, and back to consciousness. Because these meditations have a profound affect on the patient's constitution (affecting their physical, mental, emotional, energetic, and spiritual nature) it is important for the patient to be referred to a psychotherapist while undergoing this type of Qigong therapy to further facilitate the patient's healing transformation.

FINDING THE LIFE PURPOSE

Another aspect of Soul Retrieval consists of an exercise that assists the patient in finding his or her purpose in life. Finding the purpose of the patient's life encourages interpersonal healing, and fills the empty space deep within the patient's heart. This in turn increases the healing potential by providing the patient with hope.

1. The first step is to ask patients to write down on paper what is was they wanted to be when they were very young. Have them list the people that they imagined or fantasized being while they were still children (e.g., a super hero, doctor, fireman, etc.). This exercise allows patients to access their emotional past, and to feel and recover pleasant, lost memories, and phantasies.

2. Next, have the patients link all the peak experiences of each imaginary character (e.g., a doctor and fireman possess power to save lives, and can be considered heroes, as they are both admired for their skills, etc.). This knowledge informs patients regarding the underlying nature of each imaginary character and may also reveal hidden talents, passions and ideas.
3. Then, have the patients write down a list of their personal priorities. This list should contain the patients' present state of active priorities, and their current value system.
4. Then, have the patients write down their own "code of conduct," i.e., their conscious value system. The patients' code of conduct represents the ethical standards by which they strive to act. This code of conduct influences feelings, thoughts, and beliefs. It affects the patients' personal priorities and reflects the quality and nature of their interpersonal relationships. It is from this personal code of conduct that they accept, or condemn, themselves and others. By physically writing down these moral conducts, patients can emotionally connect with new found feelings of moral integrity, as well as a establish a stronger connection with their True Self.
5. Finally, have the patients write down a "life purpose" statement, linking together the collected emotions gathered from the peak experiences of their childhood and their code of conduct.

It is important that patients know and feel that what they are writing is a true and accurate account of their thoughts and emotions. The patients' live purpose statement can always be modified and changed, as they undergo personal transformation and spiritual growth through experience and expanding knowledge.

SECTION V

DIFFERENTIAL DIAGNOSIS OF ENERGETIC PRINCIPLES

CHAPTER 20
INTRODUCTION TO DIFFERENTIAL DIAGNOSIS

DIAGNOSIS IN ENERGETIC MEDICINE

Chinese Medicine developed into a comprehensive and extremely effective diagnostic system, over many centuries of accumulated clinical experiences. The symptomatology to identify disease patterns and their underlying disharmony follows the way of nature in its relationship to cause and effect. To identify the patterns of disharmony, the Qigong doctor combines diagnosis of pathology and treatment principles into one continuum. The identification of the disease pattern is not only developed through categorizing a list of symptoms, but also through observing the pathogenesis of the disease. A symptom is a feeling, or reaction, that is a sign of disease, resulting from certain disorders (physical, mental, emotional, energetic, and spiritual).

Treatment must be aimed at finding and treating the cause of the disease. This is one of the most fundamental principles of Traditional Chinese Medicine in terms of differential diagnosis and treatment. The fundamental purpose of diagnosis is to find:

- the cause of the disease,
- the root of the disease, and
- the location of the disease.

Finding the primary cause (or root) of the disease requires understanding its nature, and allows the doctor to focus treatment on the most important etiological and pathological aspects of the disease. When diagnosing a disease, emphasis is placed on observing the energetic movement (or lack thereof), as well as energetic transformation, and not on the present set structures of the existing tissues. The tissues's structures are temporarily generated by the existing energetic changes and are therefore of secondary interest to the changes themselves.

ETIOLOGY IN MEDICAL QIGONG THERAPY

The etiology, or study of the causes of diseases in Medical Qigong therapy can be divided into what is commonly called in Traditional Chinese Medicine as the "three periods of life." These three periods encompass the developmental activities of the patient's Jing, Qi, and Shen formations during the transitional periods of their life, i.e., within the womb, childhood, and adulthood. Each patient's constitution results from the continuous interaction between his or her inherited form and the environment.

Within each period of life Three Stars develop and determine some of the major characteristics and traits of each person. Each group of Three Stars accounts for one third of what, and who, the person is. They combine together to form and complete a Nine Star System of life evaluation.

ETIOLOGY WITHIN THE WOMB

Problems arising during the Three Star Period within the womb (and during birthing) encompass the formative time span of 40 weeks. This time period can be influenced by the following factors.

1. The state of the patient's Jing prior to conception. If the Jing of one or both parents is deficient, the sperm and/or ovum will be weakened.
2. The mother's mental state during pregnancy has a deep affect on fetal formation, and directly affects the developmental activities of the fetus's Jing, Qi, and Shen. If the mother is malnourished, ill, emotionally disturbed, or taking alcohol or drugs during pregnancy the development of the fetus will be affected.
3. If the birth is abnormal, difficult and/or prolonged, it can cause an emotional shock within the newborn.

4. Be aware of the Muti-Orgasmic Energy in the organs and bring them up to the crown and continue spiral up to the Universe. Let the orgasm multiply and be aware of the Cosmic Orgasmic and let it flow down to the crown and feel all the cells fill with Cosmic orgasm and flow into the heart then down to the sexual organ filling them with compassion and Muti-Orgasmic Energy.

Universal Compassion: Your compassion arises up. Be aware of the multi-orgasm sexual energy and feel it combine with the compassion into one energy at the Tan Tien. Be aware the cosmos galaxy and expand your compassion through the universe. The Universe puts us in touch with the universal compassion.



Fig. 6.23 *Universal Compassion*

This compassion practice is the major practice for all the Fusion and Kan & Li practices. The compassion fire is the most important energy of the transformation and will be use in all the practices.

Diseases may originate from one or more of these factors causing the baby to be born with an illness or a predisposition to illness. This predisposition can be manifested as a particular type of emotional or mental imbalance, a diseases of particular Yin and Yang organs (or organ systems), or a general weakness as a whole. These conditions are commonly observed as "prenatal shock," and are indications of active fetal toxins. Prenatal shock can also be indicated when newborn babies are restless sleepers, continually opening and closing their eyes, and / or having fevers.

These problems are sometimes difficult to diagnose; simple observations however, can help the Qigong doctor to determine if the patient has experienced prenatal shock. A bluish color on the forehead of the patient, for example, is one indication of this condition.

ETIOLOGY DURING CHILDHOOD

Problems arising during the Three Star Period of childhood encompass the formative time span of 18 years. These internal problems can result from abuse, malnutrition, trauma and excess sex (during the teenage years). The subconscious mind of a child is extremely impressionable to both positive and negative influences.

If, as children, the patients experienced any physical, emotional, or sexual abuse, suffered a traumatic loss (of a relationship with either or both parents, siblings, peers, etc.), then they may become predisposed to illness later in life, or develop a disease during this time period. These traumas can affect the adolescent developmental activities of the patient's Jing, Qi, and Shen formations, as this is the child's greatest time of physical growth and development.

ETIOLOGY DURING ADULTHOOD

Problems arising during the Three Star Period of adulthood (from the age of 18 onwards), encompassing the time span of 60 years. These problems are caused by the patient's internal emotions and reactions to surrounding environmental factors. Environmental factors include: diet, relationships (be they social, work related, family or other), frequency of sex, and so on, and will affect the continual developmental activities of the patient's Jing, Qi and Shen formations. An adult, although less impressionable than a child, is less resilient than the child to trauma and illness.

PROGNOSIS

If the patient's constitution has been poor since birth, or if a specific disease has been present since birth, the prognosis is generally poor. If, however, the specific disease is acute, or has only developed during the patient's adult time period, the prognosis is more favorable.

There are always energetic interactions between these Three Periods of life. If, for example, a young female patient has a hereditary imbalance between her Conception and Governing Vessels, and also has severe emotional strain during puberty, she may suffer mental problems later on in her life.

THE GROWTH AND PEAK CYCLES OF JING, QI AND SHEN

By studying the physical, mental, emotional, spiritual, and energetic qualities inherent within the human body, the Qigong doctor is able to observe and predict the various changes according to the Nine Star System of life evaluation. It is believed that the body is given specific time periods in which to flourish during the three periods of life. The following chart depicts the body's natural time frame of each physical, mental, emotional, spiritual, and energetic peak (Figure 20.1).

- From birth to age ten represents a time of growth and development on each dynamic level. The child is in a formative stage, growing physically, mentally, emotionally, spiritually, and energetically.
- From age ten to age twenty represents a time of peak physical growth. Within this time frame the child physically enters into puberty, and is able to reproduce; the growing process is stabilizing.
- From age twenty to age thirty represents a time of peak mental growth. Within this time frame the adult actively acquires knowledge for survival sake. He or she is now able to work, produce results and begins planning for the future.



Figure 20.1. Chart of Physical, Mental, Emotional, Spiritual, and Energetic Peak

- From age thirty to age forty represents a time of peak emotional growth. Within this time frame the adult actively acquires knowledge for emotional comprehension of his or her surrounding environment. The adult is now able to creatively express his or her emotions in a civil manner and deal well with emotional disruptions.
- From age forty to age fifty represents a time of peak spiritual growth. Within this time frame the adult actively acquires knowledge for spiritual growth. Now comprehending his or her mortality, the adult begins to actively seek spiritual peace.
- From age fifty to age sixty represents a time of peak energetic growth. Within this time frame the adult's previous experiences come into fruition. If the adult has successfully acquired physical, mental, emotional, and spiritual harmony, the energetic peak will prepare the adult for the rebirth. If the physical, mental, emotional, and spiritual energy is not in harmony, the life-force is terminally exhausted, and the patient dies.

  It is commonly noted that when martial arts masters practice their training excessively or incorrectly, it is within this energetic time frame that they die. The cause of death is generally due to the over exertion of the master's Liver and Lungs, and the weakening of the Spleen, Heart, and Kidneys. This energetic disharmony stems from an improper balance of combat training with little or no spiritual training.
- From age sixty on is a time of new beginnings. This time frame represents new challenges of leadership within the family and the community.

DISORDERS OF THE HUMAN BODY

Disorders of the human body are generally due to three factors: constitutional failure of the body's Prenatal or Postnatal Qi, pathogenic factors and unrestrained Evil Qi, or one or more of the Eight Miscellaneous Factors.

CONSTITUTIONAL FAILURE OF PRENATAL AND/OR POSTNATAL QI

Prenatal and postnatal constitutional failure results in a constitutional Qi Deficiency, disease, or stagnation of the vital energy.

The Prenatal Constitution is determined by the strength of the parents when a child is being conceived, or during the pregnancy. If the parents are weak, sick, drunk, or on drugs during pregnancy or conception, the parents' Qi, Blood, and Body Fluids will be deranged and the child will be affected.

In uterus, if the mother is sick, the energy of the child will be affected. Also, negative emotions, poor nutrition, smoking, drugs, and alcohol used by the mother can affect the child within the womb and predispose the child to illness after birth (e.g., prenatal alcohol syndrome and crack babies are born addicted and with mental and physical defects). The prenatal constitution is inherited from both parents and is unchangeable.

The Postnatal Constitution is determined once the child is born. Proper nutrition and a nurturing environment enhances his or her constitution. While it is not possible to entirely erase the effects of the patient's prenatal constitutional patterning, it is possible to enhance it through a balanced life-style and development of their postnatal constitution.

PATHOGENIC FACTORS AND UNRESTRAINED EVIL QI

Pathogenic factors and Evil Qi are derived from Six External Factors and Seven Internal Factors.

The Six External Factors arise from the six climatic changes (Wind, Summer Heat, Damp, Dryness, Cold, and Fire). When the patient's energy system is not well balanced, or the Qi is Deficient, the body is unable to adapt to climatic factors. These climatic factors can then invade the patient's Wei Qi fields and penetrate deeply into the channels and internal organs of the body.

The Seven Internal Factors arise from excessive internal emotions (anger, joy, worry, grief, sadness, fear, and shock). These feelings overwhelm the patient's mental state as the individual responds to social, emotional, and environment interactions. Under normal circumstances, emotions in and of themselves do not cause problems, if they are allowed to be expressed and released. The excessive accumulation of one or more emotions can, however, cause Qi deviations, affecting the corresponding organ or organs of the body.

EIGHT MISCELLANEOUS CAUSES OF DISEASE

Sometimes a patient's disease is caused by what is known in Traditional Chinese Medicine as the Eight Miscellaneous Factors (Diet, Overexertion, Sex, Excessive Child Bearing, Exposures to Poisons, Parasites, and Iatrogenic Disorders). The Eight Miscellaneous Factors offset the patient's balance of Yin and Yang energy and are described as follows.

1. An improper diet can throw the patient's body and mind out of harmony. Nutritional problems can be divided into three main categories:
    a. The excess intake of certain particular foods, as well as overeating food in general.
    b. Unwise eating habits such as:
    - eating foods that are inconsistent with the seasons,
    - eating a diet of too many Cold, Damp, Dry, Hot, greasy, spicy or raw foods,
    - eating irregular meals,
    - oscillating from feasting to fasting, or
    - eating while hurrying or emotionally upset.

    c. Malnutrition, which is developed from a deficient intake of the basic requirements needed to maintain a balanced diet. This condition can be caused from ignorance, poverty, or an impaired digestion, absorption and metabolism.
2. Overexertion consumes the Qi and results in energetic deviations. This condition pertains to both mental/emotional and physical exhaustion, and can stem from loss of sleep, inadequate rest, etc.
    a. Mental and emotional overexertion can stem from a dissatisfaction with one's work (or the lack of work), or a dissatisfaction with one's life. It can lead to stress, frustration, boredom, apathy, or depression.
    b. Physical overexertion varies according to the individual's occupation, as each job has its own characteristics hazards to the patient's health. Problems arising in this area can range from structural damage to organs and tissues (caused from Qi and Blood stagnation), to sensory impairment.
    c. Lack of sleep and inadequate rest can also be either a contributing factor or direct cause in the development of Qi deviations.
3. An unbalanced sex life can cause disease. An individual's sex life is innately connected to the personal spiritual qualities of his or her Hun and Po. Therefore, the majority of sexual problems are rarely of purely physical origin, and reflect the energetic balance of each individual's emotional and spiritual passions.
    a. An Excessive sex life: what is excessive for one individual may not necessarily be excessive for another. The condition of Sexual Excessiveness should therefore be based on the individual's con-

stitution. When an individual exceeds his or her body's normal sexual function, the excessive sexual act can burn up the body's Yin, Jing, and Kidney Qi, causing Deficient syndromes (this condition is more prone in men then women). The act of sex itself is considered a Hot and Damp state.

   b. A Deficient sex life: when an individual abstains from sex, his or her Jing production begins to increase. If this increased energy buildup is not transformed into spiritual energy, it can overflow into the Sea of Marrow affecting the brain. The prolonged lack of sex sometimes creates an emotional need and dependency towards addictions to replace the need for intimacy.

4. Excessive childbearing injures the mother's Blood and weakens her Qi. Women suffer loss of Jing during childbirth, therefore excessive childbirth can cause a Deficient condition.
5. Traumatic accidents and injuries pertain to physical traumas which disperse or congeal the body's Qi and Blood, resulting in energetic deviations. Even after the physical trauma has healed, a site for potential weakness often remains. As the patient ages, the site becomes vulnerable to further injury due to old age, physical exhaustion, stress, and exposure to cold. All traumatic accidents and injuries also pertain to emotional trauma as they are energetically inseparable.
6. Exposure to poisons pertains to any substance taken into the body by ingestion, inhalation, injection, or absorption that interferes with the patient's normal physiological functions. These poisons include both chemical as well as environmental toxins (e.g., pesticides, carbon monoxide, electromagnetic fields, and radiation).
7. Parasites include infections and infestations, and pertain to the numerous organisms capable of living within the body.
8. Iatrogenic disorders pertain to any adverse mental, emotional, or physical condition induced through medical treatment.

THE DIFFERENTIATION OF SYNDROMES

The essence of Chinese medical diagnosis is holistic and based on the concept that all things and events are interrelated. Thus the Chinese physician takes into account not only the physical symptoms of the disease, but also spiritual, mental, emotional, and environmental factors or events, that both interrelate and interact to form "patterns of disharmony" within the patient. The doctor studies and seeks to understand these patterns of disharmony, called "syndromes," to provide the framework for treatment.

Syndromes can include External or Internal factors, congenital or acquired disorders, and symptoms of stagnation, Excess, and Deficiency, or traumatic injuries to the organs and tissues. The Qigong doctor must first determine whether the patient's disease is primarily due to an energetic disorder (e.g., an Excess or Deficient condition) or a physical disorder (i.e., structural damage). Once this determination has been made, the goal or goals of treatment can be set, and the means of treatment chosen. In the treatment of the lower back, for instance, if lumbar pain is due to a subluxation of the vertebra, caused by external injuries, the doctor should first reposition the vertebra through hand manipulations, by using Tui Na therapy, then remove the Qi stagnation. If the doctor is unfamiliar with such techniques, it is better that he or she first refer the patient out for spinal adjustment, and then remove the Qi stagnation. Only in this way can a satisfactory curative effect be obtained. If, on the other hand, the back pain is due to abdominal distention or a Kidney malfunction (i.e., primarily an energetic disorder) then treatment must proceed through Qi emission.

Several methods can be used singly, or in combination, to diagnose syndromes. They are described as follows.

1. Diagnosis according to the identification of the Eight Energetic Principles.
2. Diagnosis according to the identification of Qi, Blood and body fluid distinctions.
3. Diagnosis according to the identification of

the Five Elemental patterns.

4. Diagnosis according to the identification of the Six Stages.
5. Diagnosis according to the identification of the Four Levels.
6. Diagnosis according to the identification of the Triple Burners' System.

THE CATEGORIZATION OF SIGNS AND SYMPTOMS

In order to categorize symptoms into syndromes, the Qigong doctor must determine: The Onset, Location, Aggravating or Relieving Factors, Type of Pain or Sensation, and Course Since Onset.

1. The Onset includes the date the symptoms first appeared, whether they appeared suddenly, or had a gradual onset, and the order of their appearance.
2. The Location specifies whether the symptoms remain fixed, or migrate throughout the body.
3. The Aggravating or Relieving Factors indicate the specific conditions that affect the symptoms in a positive or negative way. Aggravating or Relieving Factors may include:
   - if the symptoms feel better or worse during daytime or nighttime,
   - if the condition is better with application of warmth or cold,
   - if the condition is better with pressure or worse with pressure,
   - if the condition is relieved by movement or aggravated by movement, and
   - if the condition is relieved by eating or made worse by it.
4. The Type of Pain or Sensation describes the nature of the symptoms, such as:
   - sharp or dull
   - pounding
   - stiffness
   - burning
   - itching
   - intermittent (coming and going)
   - electrifying
   - pulling or shooting
   - nauseated
   - distended
5. The Course Since Onset includes the incidence, progress, and the effectiveness of the treatments received.

The syndromes do not equal the patient's disease, but are the patterns of the illness. In determining the patient's syndrome, the Qigong doctor takes into account that these patterns can occur simultaneously, and vary in degree of severity. The purpose for assigning the patient's disease a syndrome is not merely to classify the disease, but to understand its process. Not all the symptoms listed for a particular illness need to be present in order to properly determine the patient's syndrome.

DIAGNOSIS AND TREATMENT OF THE PATIENT

The assessment and evaluation of the patient generally proceeds in eight stages. The first seven of the eight stages are performed prior to the initiation of the actual treatment. The final stage is undergoing the treatment plan and the periodical reevaluation of the course of the disease since the beginning of the treatment (Figure 20.2). During these eight stages, the Qigong doctor assess: The Whole Person, The Patient's Constitution, The Signs and Symptoms of the Disease, The Syndrome, The Patient's Organs, The Etiology of the Disease, The Treatment Goal, and the Treatment Plan.

1. The Whole Person must first be evaluated according to his or her whole being. This process involves assessing the patient's:
   a. physical appearance (e.g., is the patient disheveled or appropriately groomed),
   b. energetic demeanor (is the patient very nervous, calm, manic, etc.),
   c. structural build:
   - according to the physical Yao formations,
   - introverted or extroverted features, and
   - Yin or Yang appearance.
2. The Patient's Constitution is assessed according to the Five Elemental Constitutions and their subdivisions of balance, and Yin or Yang predominant element.
3. The Signs and Symptoms of the Disease are then classified as:
   a. Objective Signs that are apparent to the doctor,



Figure 20.2. The Qigong doctor begins to diagnose the patient by first observing the patient as a whole. Next the doctor observes the patient's constitution, symptoms, syndrome, health and state of the internal organs, and the cause of the energetic dysfunction, before treating the disease. All the acquired knowledge is placed against the different diagnostic templates of the Eight Parameters, Five Element Theory, Qi, Blood and Body Fluid Dysfunctions, etc. This entire process is initiated in order to assist the Qigong doctor in prescribing the correct treatment. The treatment focuses on the specific cause of the disease and how it affects the patient's internal organs. The primary goal being to relieve the patient's symptoms, strengthen the constitution, and return the patients to a state of wholeness.

   b. Subjective Symptoms that the patient reports to the doctor,
   c. Cardinal Symptoms and Signs that are used for differential diagnosis of disease, and
   d. Constitutional Symptoms and Signs that are indicative of a systemic disorder.
4. The Syndrome (a pattern of disease) is then determined according to the patient's symptoms and signs of disordered function, by assessing their relationship to one another.
5. The Patient's Organs are then evaluated according to any pathological changes occurring within the internal organs.
6. The Etiology (or root causes) of the syndrome is determined to complete the comprehensive diagnosis.
7. The Treatment Plan is then formulated, taking into account all the data gathered by the doctor. The Qigong doctor devises a treatment goal and determines a strategy of treatment

that addresses the patient's syndrome or disease, in accordance with the agreed upon goal and needs of the patient.

8. The Treatment is implemented and prescriptions are assigned to initiate the healing process. Over time, the treatment plan is reevaluated, as the patient improves or suffers setbacks (for various reasons). Prescriptions, likewise undergo changes in accordance with the patient's changing condition.

Once treatment begins, the process of the development of the disease is usually reversed, or the symptoms are alleviated. After the initial treatment begins, the causes of the disease are addressed, thus affecting the organs, which in turn changes the syndrome and the symptoms. This process strengthens the constitution and establishes a dynamic balance of health and well being.

UNDERSTANDING THE THEORY OF ENERGETIC COUNTERACTION

When treating patients it is important for the Qigong doctor to understand the theory of Energetic Counteraction. This theory describes the body's natural regulation, wherein no two specific symptoms (affecting the patient's general constitution) can occur at the same time, for any considerable period, within the same system.

Generally as a disease progresses, the old symptoms will give way to the newer ones. Consider, for example, a patient who has asthma, which is brought about by Wind Cold invading the Lungs (resulting in a dyspnea, wheezing, coughing, and severe mucous). If this patient unexpectedly suffers from an attack of gout (a painful inflammation and swelling of the joints), caused from the Wind Damp invading the joints and channels, the sudden attack of gout will cause the patient's asthmatic symptoms to disappear. When the gout subsides, the asthmatic symptoms will return. The new disease naturally prevails over the original condition.

CHAPTER 21
DIAGNOSIS ACCORDING TO THE EIGHT ENERGETIC PRINCIPLES

The method of diagnosis according to the Eight Energetic Principles was formulated by doctor Cheng Zhong Ling during the early Qing Dynasty. The Ba Gan or Eight Principles of Differential Diagnosis is a system using four pairs of opposite symptoms viewed in Traditional Chinese Medicine as being essential to the understanding and treatment of disease. In most cases, knowledge of the diagnostic systems and treatment principles of general Yin and Yang conditions is enough to give the Qigong doctor some good guidelines for steering the patient's training program. Similar principles can be found in most ancient healing traditions.

The four opposite pairs are Yin-Yang and the three subdivisions of Yin and Yang into: Internal-External, Hot-Cold, and Deficient-Excess.

1. Internal and External Symptoms inform the doctor of the origin of the pathogenic condition.
2. Hot and Cold Symptoms inform the doctor of the disease's onset (how it came on) and whether the patient's temperature has been altered due to a viral infection or a metabolic change.
3. Excess or Deficient Symptoms inform the doctor whether the condition is either to be tonified or purged, and the strength of the patient's constitution.
4. Yang and Yin Symptoms inform the doctor how to establish a physical (external), as well as energetic (internal) balance.

A detailed knowledge of the Eight Energetic Principles is required to pinpoint more subtle patterns of disharmony. This understanding allows the Qigong doctor to unravel complicated patterns and identify the basic contradictions within them. The main purpose for applying these principles is to understand the etiology of the disease and the nature of the dysfunctions; not simply to categorize the illness. Only then can a treatment pattern be initiated.

INTERNAL AND EXTERNAL PATHOGENIC FACTORS

Diagnosis according to internal and external pathogenic factors is not based on the etiology but on the basis of the disease's location. If a disease is caused, for example, by an "external" pathogenic factor but is currently affecting the internal organs it is classified as an Interior condition. An Exterior condition affects the patient's skin, muscles and channels, known as an "exterior pattern" of pathogenic factors. An Interior condition will affect the bones and internal organs, known as an "interior pattern" of pathogenic factors.

EXTERIOR CONDITIONS: SIX EXOGENOUS PATHOGENIC FACTORS

The external pathogenic factors—Wind, Cold, Dampness, Fire, Heat, and Dryness—are the six "evil" factors that come from the environment outside of the body. Under normal circumstances they are good for the health, but can be very harmful when they become abnormal.

Unseasonable weather (weather that is too cold or too hot for the body to tolerate) can make people ill by impeding the normal flow of internal energy thus making the body vulnerable to disease.

Each external factor, once it enters the body can manifest as an internal factor (i.e., External Wind can penetrate and become Internal Wind, etc.). It is also important to know that an external invasion once it penetrates the organ can transform into another internal factor (i.e., an External Cold invasion can give rise to Internal Heat).

These external factors are seen as not only the cause of disease, but also as manifestations of the disease. A disease may be due to any one of these Six External Pathogenic Factors, or simply manifest as an external "evil," even though that pathogenic factor was not present at the time the patient got sick (e.g., Damp-Heat). Treatment is therefore based on how a disease manifests itself, rather then the specific cause. However, it is wise to have a sense of the etiology of the disease to determine where to intervene and what might be expected next.

The Six External Pathogenic Factors are categorized in China according to the seasons, temperature, and climate. These transitions are explained as follows.

1. The Heat Season is characterized by temperatures that are usually above 90 degrees Fahrenheit. The Heart, Small Intestines, and blood vessels are the most vulnerable at this time. This is most evident in summer.

   Heat is a Yang pathogenic factor that rises and spreads excessively, consuming and diminishing the Prenatal (Yuan) Qi, Body Fluids and Lung Qi. As Heat rises, the body's Qi is drawn upward and dispersed, causing the Yin energy to descend. Symptoms can range from restlessness, anger, delirium, loss of consciousness to even coma. This condition is most evident during the summer. The Heart organ benefits from bitter tasting foods which directly stimulate and enhance the Heart's Qi.

   a. Mild Heat that has been created within the body, causes an ascending action of Qi. This ascending action causes the body's Yin energy to become disturbed creating an energetic imbalance.
   b. Fire (Extreme Heat) is a Yang pathogenic factor and spreads excessively, consuming and diminishing the Yuan Qi, Body Fluids, and the Lung's Qi. It produces an explosive reaction, causing the Qi to flow up into the head and disturb the Blood. This action causes symptoms ranging from nosebleeds, skin infections, swelling, and skin eruptions, to hemorrhaging and vomiting Blood.

2. The Damp Season most often affects the Spleen, Stomach and muscles that are at their most vulnerable time. The Spleen organ benefits from sweet tasting food. The temperature is usually between 75 and 90 degrees Fahrenheit. This is evident in the late summer, during the rainy season.

   Dampness is a Yin pathogenic factor that easily obstructs the body's production of Qi and impairs the Yang. It is considered a Yin pathogenic factor because, as the invasion of Dampness moves downward, it manifests as a heavy and turbid energy, resulting in a full chest, nausea, vomiting, and a sticky sweet taste in the mouth. During the damp season, an invasion of Dampness may affect the urinary organs, causing stagnation of Qi. Once pathogenic Dampness enters the body, it becomes foul in nature. If the body becomes obstructed, the results will become evident in skin diseases with abscesses, and oozing ulcers with turbid, cloudy urination. Disease also manifested through infections, in combination with Heat.

3. The Dry Season is characterized by temperatures that are usually between 60 and 70 degrees Fahrenheit. The Lungs and skin are the most vulnerable at this time. This is most evident in autumn, because of the lack of humidity.

   Dryness is a Yang pathogenic factor because as the Heat rises, dryness consumes the body's Yin Qi, especially in the Lungs. This results in dry, chapped skin, cracked skin, and dry cough with sputum, throat pain, or asthma. The Lungs themselves benefit from pungent tasting foods, which directly stimulate and enhance the Lung's Qi.

4. The Cold Season is characterized by temperatures that are usually below 60 degrees Fahrenheit. The Kidneys, Bladder, and bones are most vulnerable at this time. This is most evident in the winter.

   Cold is a Yin pathogenic factor characterized by astringency of the tissues. During the Cold season the Yin pathogenic factors consume the Yang Qi. Cold blocks the channels and collaterals, causing pain and damage to the Heart, as well as consuming the Kidney Yang. Pathogenic Cold also causes the channels and collaterals to contract, resulting in the slowing down of Qi and Blood circulation. As the Yin energy moves downward consuming the body's Kidney Yang, the body's Yang is unable to generate heat causing chills, pallor, shivering, diarrhea with undigested food, stiffness, pain, numbness, and clear urine. Internal Cold is characterized by conditions of overall stagnation and contraction. The Kidneys themselves benefit from salty tasting foods which directly stimulate and enhance the Kidney's Qi.

5. The Wind Season affects the Liver, Gall Bladder, and tendons that are at their most vulnerable time. The beneficial taste is sour. The climate in the Wind season, depending on the area, is usually between 60 and 70 degrees Fahrenheit. This is most evident in the spring. Wind is Yang in nature and tends to injure the patient's Blood and Yin. It is divided into both internal and external pathogenic Wind conditions. External Wind is called "the mother of one thousand pathogenic factors," and is responsible for the propagation and growth of the pathogenic environment, because it combines with other pathogenic factors to create Wind Heat, Wind Cold, Damp Wind, Dry Wind, etc.

   In the Wind season the Yang pathogenic factors are in the upper portion of the body, weakening the Wei Qi, and causing derangement of the opening and closing of the pores on the body's surface. The pathogenic Wind tends to move constantly causing abnormal motion and rigidity in the trunk and limbs. External Wind affects the upper part of the body, shifting and moving the pain like blowing a leaf. Once External Wind invades the body, the symptoms are stiff neck, itchy sore throat, watery eyes, headache, nasal obstruction, facial puffiness, aversion to Wind, irritability, abnormal sweating, migrating joint pain, tremoring, convulsions, rigidity, and facial paralysis.

   Internal Wind is manifested through the same symptoms. Because of its serious nature, it can also cause tremors, convulsions, and paralysis throughout the body (with the exception of the face, which is due to External Wind invasion).

INTERNAL PATHOGENIC FACTORS

An interior disharmony is diagnosed when the internal organs have become affected by pathogenic factors, creating an Interior syndrome. Interior syndromes are the pathological conditions which have resulted from one of three factors: (1) the invasion of the channels by external pathogens, which can be transmitted to the body's Yin and Yang organs; (2) the direct attack on the Yin and Yang organs by external pathogens; and (3) sudden emotional changes due to improper diet and stress which directly affect the body's Yin and Yang organs leading to functional disturbances.

1. A Persistent Exterior Invasion by one of the Six Exogenous pathogenic factors can penetrate deeper into the body creating an Interior syndrome, if it is not purged from the patient's body.
2. A Direct Invasion of the Yin and Yang organs can also occur from an Exterior Invasion of pathogens. In such cases, the affected organ will manifest as an Interior Excess or Deficient condition depending on the syndrome.
3. Emotional Factors can likewise cause damage to one of the Yin organs, which in turn can cause damage to the other Yin and Yang organs. People encounter emotional upheavals in everyday activities. Under normal circumstances, the Seven Emotions are good for health (see Chapter 21). Appropriate anger helps to disperse stagnant Liver Qi, preventing stasis of Liver energy and helps the patient to establish a healthy boundary system. Rage, on the other hand, leads to the abnormal increase and ascension of Liver Qi, resulting in a flushed face and dyspnea (shortness of breath). If the pattern continues (i.e., the person is a rage-aholic), the violent and uncontrolled anger may lead to serious disorders of the Liver, including eye injury, fainting due to inadequate Blood flow to the brain,

Practice compassion through the Act of Forgiveness.
To forgive is to let go.
Always meet conflict with compassion.



Fig. 6.24 *Be aware of the people that you feel resentment toward.*



Fig. 6.25 *People who make you feel angry.*



Fig. 6.26 *People that you hate or people who hate you.*



Fig. 6.27 *People who hurt you or people who have been hurt by you.*



Fig. 6.28 *Send out the abundance of compassionate energy that you have from the universe, to fill the person and to forgive whatever he/she did to you.*



Figure 21.1. Cycle of Disharmony

cerebral hemorrhaging, or even death. It is believed therefore, that Internal conditions can arise from either an Excess emotional condition caused by emotional suppression, or a Deficient emotional condition caused by excessive emotional discharging.

It is also believed that a person's personal emotional history determines his or her biology (life processes). Each person creates this reality through his or her belief system. Hence the patient creates the disease by embracing traumatic past wounds and formulating belief structures that support these traumas. These energetic clusters are then fed via the major viscera by the excessive emotional energy. This pathological emotional process can result in the formation of cysts, tumors, cancer, etc.

Any imbalance of the Seven Emotions leads to the unnecessary consumption, or blockage of, the internal Qi flowing through the channels of the viscera. In either instance, this results in abnormal Qi activity and creates a functional disorder of the cerebral cortex.

Emotional disharmony induces a vicious cycle which affects the mind, body and spirit. Any factors (Yin and Yang disharmony, emotional disharmony, disturbed behavior, or environmental disharmony) can trigger the cycle (Figure 21.1). When caught in this cycle, emotional energy can deplete the physical body.

Anger, for example, generally causes the Qi to rise; however, when anger turns inward it can transform into depression. Mental depression may obstruct the functional activities of Qi and this stagnation may cause Fire. The Fire syndrome is caused by the disorders of the Seven Emotions and may burn up the fluid of the organ related to the predominant emotion.

In Western culture, people are generally not encouraged to acknowledge painful emotions; feelings are usually disregarded and conquered by a strong will. The storage of emotional energy in the muscles and organs of the body leads to tension, stress, and illness. The Qi cannot circu-



Figure 21.2. Five Elemental Controlling Cycle

late with emotional blocks. Many specialists in Western medicine today agree that a large percentage of diseases being treated are, indeed, caused or aggravated by stress.

The Five Elements have a creating (generating) and restrictive (controlling) relationship. The sequence of the creative relationship of the Five Elements is: Wood creates Fire; Fire creates Earth; Earth creates Metal; Metal creates Water; Water creates Wood. This circle is endless.

The sequence of the controlling relationship of the Five Elements is: Wood controls Earth; Earth controls Water; Water controls Fire; Fire controls Metal; Metal controls Wood. This circle is also endless.

The controlling relationship can be applied to problems with emotions. Anger, for example, belongs to the rising of Excess Liver energy and can be counteracted by descending the Lung's Qi (Figure 21.2). The Lungs control sadness, and sadness may lead to the consumption of abnormal rising Liver Qi (Metal controlling Wood).

Excessive sadness may lead to the extravagant consumption (and depletion) of Lung Qi, which damages the body's Yin and the Heart. The consumption of the Lung Qi can be stopped by the Heart's energetic release of the emotion of joy. Joy causes the rapid rising of the Heart's Qi. It can be regulated by fright and terror, which are controlled by the rapid descending energy of the Kidneys. Terror leads to the abnormal falling of Qi, it therefore counters the abnormal rapid rising of Heart's Qi. Excessive fright and terror may lead to the abnormal sinking of Gathering Qi, which damages the Kidney's Qi (Figure 21.3).

Because over-thinking can cause Qi to gather, it can be used as a tool to help bring back dispersed energy. Over-thinking and anxiety, however, may lead to the depression and stagnation of Qi, which weakens the transporting and converting ability of the Spleen's energy, and causes a lack of appetite. Mild cases of this condition can manifest as dyspepsia (indigestion), abdominal distention and diarrhea. In severe cases, the Qi

The Seven Emotions			
Chinese Word	English Translation	Organ Association	Qi Manifestation
Xi	joy, happiness, excitement, pleasure	Heart	slows down and relaxes the Qi
Nu	anger, irritation	Liver	causes Qi to rise
Si	meditation, contemplation, pensiveness, worry	Spleen	stagnates the Qi
You	anxiety, sorrow, grief	Lungs	obstructs the Qi
Kong	fear, extreme anxiety	Kidneys	causes Qi to descend
Jing	shock (sudden intense fear), fright	Heart then Kidneys	scatters and deranges the Qi
Bei	grief, affliction, sadness	Lungs	disperses and consumes the Qi

Figure 21.3. The Seven Emotions Chart

and Blood stagnate in the chest and abdomen, causing a feeling of fullness in the chest or upper abdomen. This stagnated, ever-sinking Spleen energy can be smoothed and aroused by anger (the Liver's energy expanding upward and outward). In short, the hyperactivity of Yin is treated with Yang to check the unnecessary consumption of internal energy, and to promote a mild Yin energy. Then the Qi and Blood can flow without interruption and disease can be prevented.

One effective technique to avoid an emotional and energetic overload or depletion of a Yin organ's Qi, is to apply the Five Elemental counter-emotion to restore emotional balance (see Chapter 53).

OVERVIEW OF EXTERNAL AND INTERNAL CONDITIONS

The internal and external diagnostic parameters locate the depth of the condition of the disharmony and are fairly easy to distinguish, relative to the other pairs of opposites. Thus, determining the internal or external nature is usually the first step in diagnosis of a disorder.

Internal conditions are usually caused by internal disharmonies, such as excessive emotional energy in the form of anger, excitement, sorrow, anxiety, fear, and mourning, or other imbalances associated with the Seven Emotions. Excessive thinking and stress can also lead to an imbalance that is characterized as internal. Internal conditions are often chronic and tend to have a gradual onset and a longer duration.

Conditions of External disharmony are typically caused by the external influences on the body, known in Chinese medicine as "pernicious influences." They are Wind, Cold, Heat, Damp, Dryness, and Summer Heat. Pernicious influences usually invade the body when the body's Wei Qi is weak.

Typical External diseases are colds, influenza, skin eruptions, or diseases caused by injury or shock. Excessive amounts of eating, drinking, working, and sexual activity can also lead to both Internal and External disharmony. External conditions are often acute, with sudden onset, and of short duration.

Many times Internal conditions will develop when an External condition moves inward. This represents a further weakening of Wei Qi and the body's natural immune system. Before the condition has developed into a full Internal sickness, it will go through a stage of being half-external and half-internal.

Examples of conditions which may be considered as being half-internal and half-external are: alternating fever / chills, heaviness in the chest, restlessness, nausea, vomiting, no appetite, dry throat, irritation of the mouth, and dizziness. A bounding pulse is also an indication of this type of condition.

This is one reason why treatment of an External disease (colds and flu) requires sweating therapy to encourage the disease to remain external. The contractile mechanism of the skin is a specific external representation of the body's Yang immune system at work.

When treating extreme cases, such as internal injuries and shock, conserve the patient's Yang Qi by keeping them warm.

HOT AND COLD

Hot and Cold describes whether the condition is the result of a Hot or Cold state and is determined by hot or cold sensations. The nature of this clinical manifestation depends on whether it is combined with a Full or Empty condition.

HOT CONDITIONS

Hot conditions usually arise when there is excess activity of the body's Yang functions, or if there is an insufficiency of Yin Qi or Fluids in the body. A Hot condition can be further divided into either Full Heat or Empty Heat.

1. A Full Heat conditions manifest as the following physiological and mental / emotional symptoms.
    a. Physical symptoms include:
    - increased energy and metabolism, i.e., physiological hyperfunction
    - fever with thirst, and desire for cold liquids
    - dry stool and constipation
    - dark yellow and reduced urine
    - flushed face, red eyes, hot red skin
    - warm extremities
    - aversion to warmth
    - a rapid, full pulse and a red tongue with yellow fur

b. Mental and emotional symptoms include:

- irritability
- restlessness
- loud voice, talkativeness
- extroverted and aggressive behavior

Inflammations, ulcers, and infections are typical of Full Heat diseases. There are many other symptoms depending upon which organ is affected.

These Full Heat symptoms arise when there is an Excess of Yang energy in the body. Excess Yang energy can be caused from overconsumption of Hot foods (which cause Stomach or Liver Heat), or long-standing emotional problems (which cause Liver or Heart Heat) due to Qi stagnation. Full Heat can also develop from the invasion of external pathogenic factors which have transformed into Heat.

2. An Empty Heat conditions manifest as the following physiological and mental/emotional symptoms.

a. Physical symptoms include:

- dry mouth and throat (at night)
- night sweats
- afternoon fever
- a feeling of heat in the chest, palms and bottoms of feet (Five Palms Hot)
- dry stool
- scanty, dark urine
- a floating, empty and rapid pulse, with a red, peeled tongue

b. Mental and emotional symptoms include:

- fidgeting and mental restlessness
- vague anxiety
- insomnia

There are many other symptoms depending upon which organ is affected.

These Empty Heat symptoms arise from a Deficiency of Yin. If the patient's Yin becomes Deficient (usually due to a Deficiency of Kidney Yin), this affects the Yin of the Liver, Heart, and Lungs and causes a relative Excess Yang condition.

COLD CONDITIONS

Cold conditions usually arise when there is excess activity of the body's Yin functions, or if there is an insufficiency of Yang Qi in the body. A Cold condition can be further divided into either Full Cold or Empty Cold.

1. A Full Cold conditions manifest as the following physiological and mental/emotional symptoms.

a. Physical symptoms include:

- diminished physiological function and lowered immunity
- decreased energy
- aversion to cold and craving for warmth
- cold extremities
- lack of thirst
- clear urine, watery stool
- desire for hot drinks
- white face
- a slow pulse and a pale, white tongue with moist fur

b. Mental and emotional symptoms include:

- timid behavior and soft speech
- slow movement
- a lack of motivation

Generally, discomfort is increased by cold and reduced by warmth. Cold symptoms may also appear at later stages of fevers and chronic peptic ulcers, denoting a weakening of the body's ability to overcome the disease.

These Full Cold symptoms arise when there is an excess of Yin Qi in the body. Excess Yin Qi can be caused from the direct invasion of External Cold into the body's interior. In this particular condition, the External Cold can either invade the Stomach causing vomiting and epigastric pain, invade the Intestines causing diarrhea and abdominal pain, invade the uterus causing dysmenorrhea, or it can invade the Liver Channels causing pain and swelling in the scrotum. One of the main manifestations of Interior Full Cold is abdominal pain caused from the Cold constricting and obstructing the circulation of Yang Qi. Full Cold can also develop from the invasion of external pathogenic factors which have transformed into Cold.

2. An Empty Cold conditions manifest as the following physiological and mental/emotional symptoms.

a. Physical symptoms include:

- cold limbs and chills
- pale face
- fatigue
- no thirst
- loose stools
- clear, abundant urination
- sweating
- pale tongue with thin, white coating and a deep, slow or weak pulse

b. Mental and emotional symptoms include:

- tiredness and lack of motivation
- slow movement

An Empty Cold disharmony usually arises when the Yang Qi of the body is insufficient, and fails to warm the body. This is caused by a Deficiency of Spleen Yang, Kidney Yang, or Heart Yang (sometimes Lung Qi Deficiency). The most common cause is related to the Spleen Yang Deficiency, which fails to warm the muscles and thereby causes chills. If the Spleen does not receive heat for its function of transforming food, the result will also be loose stools.

COMBINATION OF HOT AND COLD SYMPTOMS

While distinguishing Hot diseases from Cold diseases may appear to be fairly straightforward, the doctor may find that there are many circumstances where both Hot and Cold symptoms appear simultaneously. The use of sensory input is just a general indicator, however, because it provides the doctor with only partial data; it can sometimes be misleading if other considerations are not taken into account. The doctor needs to consider the other symptom characteristics according to Yin-Yang or Deficient-Excess patterns.

1. An External Cold with Internal Heat syndrome manifests when a patient has a preexisting internal Heat condition and is subsequently invaded by External Wind Cold. This condition can also occur in attacks of latent Heat combined with the invasion of Wind Cold. Symptoms can include fever with an aversion to cold, body aches, irritability, and thirst.
2. An External Heat with Internal Cold syndrome manifests when a patient with a preexisting Cold condition is attacked by exterior Wind Heat. Symptoms can include fever with an aversion to cold, chills, headache, sore throat, and thirst.
3. A Heat Above-Cold Below syndrome manifests when a patient's pathogenic Heat rises resulting in Heat above and a Cold syndrome below. Symptoms can include thirst, bitter taste, sour regurgitation, irritability, Herpes Simplex I, borborygmus, loose stools, and pale and profuse urination.

Qigong patients must be aware of these signs of Hot and Cold disharmony. If a patient's training routine is too Yang, this will burn the body's Fluids, thus diminishing the Yin Qi's ability to contain the Excess Yang, which in turn produces a Hot condition. An overactive metabolism can also induce a Hot condition, while a sluggish metabolism can produce a Cold condition. Less extreme conditions are classified as warm, cool, or neutral.

EXCESS AND DEFICIENT

The capacity of an individual to maintain resistance to the invasion of pathogens is relative to the strength of the disease and the strength of the individual. An Excess condition is characterized by the presence of a pathogenic factor (interior or exterior) and by the fact that the body's Qi is still functioning normally. The battle against the pathogenic factors results in the symptoms and signs of an Excess condition. A Deficient condition is characterized by a weakness of the body's Qi and the absence of a pathogenic factor. If the body's Qi is weak, but the pathogenic factor continues to attack, the condition is considered Deficient and is characterized by an Excess.

EXCESS CONDITIONS

An Excess condition will usually occur when a bodily function becomes overactive or Qi accumulates unnaturally due to a blockage. It is characterized by strength, buoyancy of spirits and often acute symptomatic reactions. Disharmonious conditions which begin and end suddenly are due to Excess. Yang Excess can be quickly improved, in most cases, with a diet of predominately vegetables and fruits.

It is not unusual for patients whose diets are heavy in meat proteins, to suffer from Excess diseases. Many Naturopaths advocate the predominant use of raw fruits and vegetables and have experienced outstanding results due to the elimination of Excess Yang (from meat toxins) from the body.

Such a diet is not good therapy for individuals who eat a relatively balanced vegetarian diet, because it serves to make them more Yin and threatens to throw them off balance. This is a good reason to avoid "fad" diets. A diet or method that works well for one person may have the opposite affect for someone else; each case must be considered separately.

Some indications of an Excess condition are as follows: flushed face, loud voice, coarse and full breathing, acute pain, extreme menstrual pains, a tender abdomen, which worsen with the application of heat. A strong pulse can also be a sign of an Excess condition.

In cases of Excess, to expel pathogenic evils, the patient imagines that the Toxic Qi is being expelled from specific channel points upon exhalation. The results are always more effective when Qigong prescriptions are given in conjunction with the treatments.

Any interior pathogenic factor (Heat, Cold, Damp, Wind, Fire, and Phlegm) can give rise to an Excess condition, including the stagnation of Qi and stasis of Blood.

DEFICIENT CONDITIONS

Although Deficiency is characterized by insufficient Jing, Qi, Shen, Blood, and Fluids, it does not generally mean a lack of some nutrient as it does in Western medicine. It is more a statement about the body's inability to find, or produce, what is necessary for its immune function to provide a functional integrity in the body. Deficiency, therefore, is taken in a more general sense and denotes the overall condition of the patient, or of the disease.

Conditions which linger are usually due to Deficiencies. The general indications are: great weakness, inconsistent energy, shallow and rapid respiration, pain characterized by soreness, weak or inconsistent volume of voice, moderate menstrual pains, withered face, low spirits, and abdominal pain. A Deficient condition will generally respond well to heat and pressure. A weak pulse can also be an indication of a Deficient condition. There are four types of deficiencies: Deficient Qi, Deficient Blood, Deficient Yin, and Deficient Yang.

1. Deficient Qi is the first and least severe stage of Deficiency. Most symptoms arise from a weakness of the Lungs' Qi (which fails to control the breathing) and a weakness of the Spleen's Qi (which fails in its function of transforming and transporting).
2. Deficient Blood is caused from a dysfunction of various internal organs. Most symptoms arise from a weakness of the Liver, Heart, and Spleen.
3. Deficient Yin is caused by a dysfunction of various internal organs. Most symptoms arise from a deficiency of Yin within the patient's Liver, Heart, Stomach, Lungs, and Kidneys.
4. Deficient Yang is caused by a dysfunction of various internal organs. Most symptoms arise from a deficiency of Yang in the patient's Liver, Heart, Spleen, Lungs, and Kidneys.

In cases of Deficiency, when replenishing Qi is required, the best effect can be obtained when the patient cooperates with the doctor's extension of Qi through mental concentration and focused inhalation.

COMBINED EXCESS AND DEFICIENT CONDITIONS

Sometimes Excess and Deficiency conditions can occur simultaneously. Although Excess is one of the characteristics of a Yang disease, this condition can also give rise to certain symptoms of Deficiency. These are mostly a result of Qi being blocked in the utilization of its own vital nutrients.

YIN AND YANG THEORY

Yin and Yang energy is usually represented through the image of the Taiji symbol. Yang Qi is represented through the color white and Yin Qi is represented through the color black. Through the image of the Taiji symbol the interrelationship of Yin and Yang represent the stages of waxing and waning of energy (Figure 21.4). In Traditional Chi-


Yang - hot, bright, strong, upward, outward, clear, movement. Qi (non-substantial matter) function of an organ
Yin - cold, dark, weak, downward, inward, muddled, stillness. Blood (substantial matter) substance of an organ.

Figure 21.4. In Traditional Chinese Medicine the theory of Yin and Yang represent the dynamic duality of balance and harmony within the body, as well as within the universe itself, and as represented through the image of the Taiji Symbol. There is always Yin within Yang and Yang within Yin. These two energies are always changing and transforming the body's life force energy.

nese Medicine, the theory of Yin and Yang is also used to explain both the psychological and pathological phenomena of the body. It is considered a major principle for diagnosing and treating diseases.

Generally speaking, an Excess of Yang may lead to a Deficiency of Yin, and vice versa. A Hot syndrome can be the result of either Excess Yang or Deficient Yin. A Cold Syndrome can be the result of either Excess Yin or Deficient Yang (Figure 21.5).

The Qi activities of these Yin and Yang aspects unite and regulate the body's internal organs and tissues. The direction and energetic nature of Qi (Excess or Deficient, strong or weak, evil or vital) can be detected at corresponding body surfaces so that information for diagnosis and treatment can be obtained. For example:

A strong, dense, dry, and hot sensation of Qi in the head area may be a symptom of Excess Yang in the upper portion of the body and a Yin Deficiency in the lower portion. This would require the Qigong doctor to guide the Yang Qi to descend and the Yin Qi to ascend to restore the balance of Yin and Yang energy.

To treat patients with an overabundance of Yang Qi and hyperactivity of Fire, the Qigong prescription meditations should be practiced during the Yin periods (11 a.m. to 11 p.m.) while facing north, with emphasis placed on exhaling to purge the Heat. The doctor should adhere to the principle of replenishing the patient's Yin to regulate the Yang, or leading the Yang to descend to supplement the Yin.

Once the nature of Yin and Yang disequilibrium is determined, the proper method of treatment can be selected to regulate the Excess or Deficiency. The doctor always treats Yin for Yang diseases and Yang for Yin diseases. A Yang syndrome, for example, should be treated with Yin herbs, and a Yin syndrome should be treated with Yang herbs. The treatment should be aimed at purging the Excess, replenishing the Deficiency, and regulating the Deficient Yin or Yang to restore a normal balanced state of energy with in the body.

In Medical Qigong therapy, the principle of "using Yin for treatment of a Yang disease and using Yang for treatment of a Yin disease" must be strictly adhered to. It is important to dredge or purge the Excess before replenishing and tonifying any Deficiencies. The intake of cold foods (fruit, salad, ice cream, etc.) or drinks, for example, may lead to an Excess of Yin, which gives rise to a Cold syndrome of the Spleen and Stomach. This manifests as pain, diarrhea, aversion to cold, and cold extremities.

To treat this Excess, the doctor guides the Cold Qi out of the body by way of St-36 and Sp-9 points, then projects Hot Yang Qi towards specific channel points on the patient's body, such as CV-12 and St-25.

DIAGNOSING YIN AND YANG IN THE BODY

Every person has both Yin and Yang elements, but will tend to be predominantly one or the other in terms of personality, physique, life-style pref-



In cases of Excess, the doctor should Purge.

In cases of Deficiency, the doctor should Tonify.

In cases of Excess and Deficieny combined, the doctor should Regulate.

Figure 21.5. Yin and Yang Energetic Diagnosis

erences, speech patterns, mannerisms, etc. Within a general constitution there will be more subtle fluctuations within the Yin/Yang continuum as the body reacts to external and internal energetic movements. In designing the patient's exercise program, diet, or herbal remedies, it is necessary to first determine whether the patient is predominantly Yin or Yang in constitution.

YIN/YANG CONSTITUTION CHART

There are general indications that will help the doctor diagnose a patient's condition as predominantly Yin or predominantly Yang. The patient's basic Yin/Yang constitution, and an analysis of the current Yin/Yang balance of the body will play an important role in determining the type of exercise and the time of day that it will be performed. In most cases, a Yang condition should be balanced by a Yin exercise and vice versa.

There are varying levels of disharmony in the patient's body. Yin and Yang are only relative terms, and they are often not enough to adequately describe the character of the body's condition. Other factors such as Hot - Cold, Deficient - Excess, Internal - External must be considered in more detail. Yin and Yang are never in a permanent state; there is always dynamic movement. All relationships based on Yin/Yang are relative, and their mutual interaction must be considered.

Yin and Yang theory is valuable because it provides a tool for understanding the patient's constitution at a given point in time. This information enables the doctor to determine the best course of treatment, including exercise, food, or herbal formulas that the patient's body needs. Consideration of the patient's inherited and acquired attributes (developed through diet and life-style, environmental influences, natural energy cycles, and other miscellaneous influences such as sleep, work conditions, and relationships) should be based on observation and contemplation of the patient's physical, mental, emotional, and spiritual state of mind.

Designing a program to establish balance and harmony requires a keen awareness of energetic and mental states. In evaluating the patient's condition the doctor takes into account the location and nature of the disharmony, the severity of the condition and the overall physical, mental, and emotional condition of the patient (Figure 21.6). Furthermore, the doctor may notice a combination of both Yin and Yang symptoms or any of the other contrasting pairs be they Hot/Cold, Internal/External, Excess/Deficient. A combination of such symptoms creates a challenge when diagnosing a patient, since symptoms and indicators tend to be more extreme in a person who is ill (Figure 21.7).

YIN CONDITIONS

Primary Yang generates primary Yin. Everything in the universe needs support from Yin. On a basic level, Yin conditions in the body tend to be Cold, internal, Deficient, and degenerative in nature. If a condition becomes overly Yin, it may express some Hot or Yang symptoms. Extreme cold in the form of snow, for example, can cause frostbite. This is called a "false Yang" condition because the condition created is manifested as Yang instead of Yin.

Type of Sign	Yin	Yang
General	• Cool skin temperature • Pale, dark, dull, or yellow complexion • Cold hands and feet • Aversion to cold • Discomfort relieved by warmth and pressure • Senses dull • Curled lying posture	• Warm skin temperature • Red, oily, shiny complexion • Warm hands and feet • Aversion to heat and pressure • Five senses strong • Stretching posture in sleep
Diet	• Prefers warm food and drinks • Poor appetite • Poor sense of taste • Indigestion	• Prefers cold drinks and cold food • Strong appetite • Thirsty, dry mouth
Energy	• Tired • Weak	• Forceful, restless • Strong, stout
Behavior	• Underactive • Quiet, withdrawn	• Overactive • Noisy, outgoing
Breathing & Voice	• Weak, shallow breathing • Weak voice, quiet	• Deep, heavy breathing • Loud, coarse voice, talkative
Excretion	• Copious clear urine • Watery stool	• Scanty dark urine • Hard solid stool
Reproduction	• Sexually underactive • Scanty, pale menses • White leukorrhea	• Sexually overactive • Profuse, red menses • Yellow leukorrhea
Pulse	• Deep, slow • Empty, weak • Fine	• Superficial, rapid • Full, strong • Flooding
Tongue	• Pale, fat body • Moist, thin white coat	• Red, solid, sharp body • Dry, thick yellow coat

Figure 21.6 Signs of Yin and Yang Conditions

Yin conditions are typically characterized by the following: watery stool, clear and copious urine; depression; pale, dull, and yellow complexion; weak, tired, and thin constitution; cool skin, cold hands and feet; dulled senses; curled lying posture when sleeping; soft voice; silent, shallow breathing; preference for warm food; and a tendency towards indigestion. A Yin condition will also be reflected in a deep, weak, fine, slow, or sluggish pulse and a fat, pale, moist, and smooth tongue with possibly a white coating.

YANG CONDITIONS

Yang conditions tend to be Hot, External and Excessive. A Yang disease is generative. Under cer-

Attribute	Progression from Extreme Yang to Extreme Yin
Spirit	Aggressive, outgoing, joyful, sad, fearful, anxious, depressed (The degree of outward expression determines the yangness of the spirit, not so much the emotion itself.)
Body Type	Large and muscular, normal build, thin, emaciated
Posture	Stiff, erect, relaxed, hunched over, limp
Activity	Very animated, normally active, little movement, still
Respiration	Heavy and loud, loud sighing and stretching, breathing heavily through mouth, shallow light breathing, soft intermittent sighs
Voice	Loud, rough, high pitched, regulated and moderate, soft, murmuring, almost inaudible
Skin Cast	Red, yellow, green, pink, white
White of Eye	Red, yellow, blue-green, pink, white
Lip Color	Red, yellow, blue-green, pink, white
Moistness of Lips	Cracked, dry, moist, overly wet
Sputum	Yellow and thick, white and thick, thin, clear
Smell of Breath	Strong, mild, faint
Body Odor	Strong, mild, faint
Urine	Thick, yellow, smelly, thin, whitish, no odor
Feces	Dark, strong smelling, soft, loose, light color

Figure 21.7. The Continuum of Yin and Yang Constitutional Signs and Symptoms

tain conditions, an overabundance of Heat (Yang) may transform into Cold (Yin) to bring about a condition known as "false Yin." Extreme heat and sun, for example, can cause sunstroke. This is called a "false Yin" condition because the condition created manifests as Yin instead of Yang. If an acute Yang condition persists, it will become Yin.

Yang conditions are typically characterized by the following: hard, solid, dry stool; thick, yellow urine; outwardly excited appearance; strong, stout, muscular constitution; restless, active, irritable in character; warm hands and feet and overall warm skin and temperature; strong senses; tendency to stretch frequently; loud voice, talkative; heavy breathing; thirsty, dry mouth; and a preference for cold drinks. A Yang condition will also reflect a floating, flooding, fast, or strong pulse, and a red or yellow, solid, dry tongue with cracks and little or no coating.

SIGNS OF YIN AND YANG

Determining true from false Yang may seem confusing. Yin Deficient people who are very thin and emaciated are often quite hypertensive, this can be seen in their excessive loud talking, rest-

Oneness with Universe (Oneness with God)

Fuse Inner Positive Energy with Universal Energy through Turning the Dial

In Fusion of the Five Elements, the collection points were used to gather and store the energy of the organs. From the collection points in the body, the energy was drawn down into the pearl. Now, in Cosmic Fusion the collection points are expanded to encompass the Energy Body and the Universal Aura body. So, not only are we fusing the emotional energy of the physical body (negative emotions, senses and thoughts), but now we fuse the energy of the Energy Body and the Universal Body. This creates a much more complete practice and a highly refined pearl of energy. Fusing the elements is the secret to internal alchemy.

You can think of the different collection points like ingredients for a delicious soup. The more energy we can collect, the more spices we have for our soup. Alchemy is like cooking. What creates a really good soup or food is a combination of ingredients. Alchemy is about fusing the elements at our disposal to create balance and harmony within ourselves and the world we live in.

In the beginning of the fusion practice, it seems intricate and detailed. Once you get used to the formulas it is a very easy and simple practice. Learning a new recipe always takes some time and study, but once you have it in your mind, it is easy. The same is true with the fusion practice.

Forming the Collection Points

The collection points were introduced in Fusion of the Five Elements as a way to collect the negative energy from the organs. This energy was then directed into the pearl through the pakuas. In Fusion of the Five Elements the collection points were associated with the energy of the infants and the protective animals. In Cosmic Fusion, we are going to expand this practice by forming the collection points of the Energy Body and the collection points of the Universal Aura Body. These collection points are a reflection of the collection points in the physical body.

For example, the physical heart collection point is located at heart center just behind the sternum. The Energy Body collection



Figure 21.8. The Nine Regions of Pulse Diagnosis

lessness and insomnia. Such individuals can also develop erratically feverish symptoms which usually change from Hot to Cold.

Generally, a true Yin or Yang condition is determined by three or more symptoms that simultaneously manifest either one of those conditions.

False Yin symptoms occur when the Yang becomes overly strong, causing a weakening of the Yin. (Again, the overall condition should be assessed before making a differential diagnosis.) False Yin symptoms include weakness, coldness, wetness, and other Yin symptoms in an otherwise Yang condition. One should bear in mind that there are seldom purely Yin or Yang symptoms because Yin and Yang are so interdependent on each other.

Furthermore, stages of Yin and Yang may change during the course of the day, or over the course of an illness. If a Yang stage is allowed to progress, it can degenerate into weakness described as a Yin stage. Therefore, if a Yang condition changes to Yin it is probably not a good sign, but if a Yin condition changes to an acute Yang condition it may be a positive sign of movement towards overall balance. The focus is to understand that it takes active energy (Yang) to manifest an acute condition, and the stronger the manifestation, the stronger the energy.

YIN AND YANG CATEGORIZATION OF TRAINING

Chinese herbs and foods are typically classified in terms of Yin and Yang, as are Qigong exercises and meditations. With exercises and meditations the state of mind and level of relaxation during the exercise or meditation is critical in determining the Yin or Yang categorization. It is important to be aware of this when developing a patient's program to provide the proper energy adjustments to maintain a healthy balance. If a disharmonious condition develops and the wrong prescription is given, the patient can be thrown further off balance, making it more difficult to restore good health.

PULSE DIAGNOSIS OF THE EIGHT ENERGETIC PRINCIPLES

The body's pulse in considered another form of energy manifestation. The pulse is imagined as waves of various Fluids flowing within the body, originating from within the Heart, where the Shen resides. Pulse diagnosis can give the Qigong doctor detailed information on the state of the patient's internal organs, as it reflects the patient's flow of Qi and Blood, as well as Yin and Yang energy. The pulse is felt at the radial artery, which is divided into three areas (front, middle, and lower), and at three different levels (superficial, middle, and deep), creating "nine regions" of pulse diagnosis (Figure 21.8).

The three areas of the wrist relate to the energetic manifestations of the Triple Burners. The front position corresponds to Heaven and reflects the diseases from the head to the chest; the middle position corresponds to Man and reflects the diseases



Figure 21.9. Pulse Correspondence with the Triple Burners

from the diaphragm to the umbilicus; the lower position corresponds to Earth and reflects the diseases from the umbilicus to the feet (Figure 21.9).

The three different levels relate to the energetic manifestations of the body's diseases. The superficial level corresponds to exterior diseases, the body's Qi and Yang organ energy; the middle level corresponds to the condition of the Blood, as well as the energy of the Stomach and Spleen; the lower level corresponds to interior diseases, the body's Yin energy and Yin organ energy.

The important thing is to diagnose how the body's energy is flowing, taking into consideration the relationship of the Yin and Yang on the pulse, i.e., whether it is superficial or deep, fast, or slow, Excess or Deficient. The quality of the pulse may also vary according to the patient's:

1. General Constitution and Body Build, with bigger frame patients generally having a stronger pulse then smaller frame individuals,
2. Level of Activity, with patients who engage in heavy physical work having a stronger pulse then those who engage in mental work, and
3. Exposure to Seasonal Weather, as a deeper pulse is generally felt in the winter and a more superficial pulse is felt in the summer.

PULSE QUALITIES AND CLASSIFICATIONS

In China, attention is placed primarily on the overall quality of the pulse. While reading the superficial pulses, it is important to note that they indicate the condition of the patient's Qi and Yang Organs. The deep pulses indicate the condition of the patient's Jing, and Yin Organs. Pulses can be divided into three main classifications, which are related to either Yin and Yang qualities: The Depth, The Speed, and The Strength (Figure 21.10).

1. The Depth at which the pulse can be felt is considered first.
    a. Superficial/Floating Pulses are felt with a light touch, barely touching the artery. They indicate an Exterior syndrome (e.g., Wind-Cold or Wind-Heat), chronic illness, or a general weakness. This informs the doctor that there is an Excess at the patient's Qi level (or a Deficiency at the Yin level).

- Superficial and Weak (Empty) pulses are felt in Yang Excess diseases (superficial diseases), when the patient's Wei Qi is fighting the pathogenic factors at the superficial level.
- Superficial and Forceful (Full) pulses are felt in interior diseases due to Yin or Jing Deficiency.

    b. Deep Pulses are felt on heavy pressure, near the bone. They indicate an interior syndrome (problems within the Yin Organs), and relate to the patient's Jing.

- Deep and Weak (Empty) pulses are felt in diseases due to a Deficiency of Qi and Yang.
- Deep and Forceful (Full) pulses are felt in deep diseases (when the disease has penetrated into the patient's internal organs). They confirm an Excess at the Yin level, or Deficiency at the Qi level, and point to a stasis of Qi or Blood, and to a Cold or Heat condition.

2. The Speed of the pulse is considered next.
    a. Slow Pulses are less then 4 beats per the patient's breath; they indicate a Cold syndrome.

- Slow and Weak (Empty) pulses indicate Empty Cold and Yang Deficiency.
- Slow and Forceful (Full) pulses indicate Full Cold and Yin Excess.

    b. Rapid Pulses are more then 5 beats per patient's breath and indicate a Heat syndrome.

- Rapid and Weak (Empty) pulses indicate Empty Heat and Yin Deficiency.
- Rapid and Forceful (Full) pulses indicate Full Heat and Yang Excess.

	YANG	YIN
DEPTH	Superficial — Exterior	Deep — Interior
SPEED	Rapid — Hot	Slow — Cold
STRENGTH	Forceful — Excess	Weak — Deficient

Figure 21.10. The Eight Energetic Principles are manifested through the body's pulses.

	LEFT HAND **Superficial - Deep**	**RIGHT HAND** **Superficial - Deep**
FRONT POSITION	Small Intestine - Heart	Large Intestine - Lungs
MIDDLE POSITION	Gall Bladder - Liver	Stomach - Spleen
LOWER POSITION	Bladder - Kidneys' Yin	TB & Pc - Kidneys' Yang

Figure 21.11. Left and Right Hand Correspondence

3. The Strength of the pulse is considered last.
    a. Weak (Empty) Pulses are weak and disappear on heavy pressure; they indicate a Deficient syndrome.
    b. Forceful (Full) Pulses are forceful and are felt on deep pressure; they indicate an Excess syndrome.

- Forceful (Full) and rapid pulses indicate Full Heat.
- Forceful (Full) and slow pulses indicate Full Cold.

THE CLASSICAL PULSE DIAGNOSTIC POSITIONS AND DEPTH

Traditionally the best time to take the patient's pulse is when the patient is calm and relaxed. There are several schools of pulse diagnosis, each one with its own specific methods of approach to understanding the patient's symptoms. The most important aspect in listening to the patient's pulse is to feel the strength, quality, and spirit of the pulse. Only then can the doctor receive accurate information about his patient's condition (Figure 21.11).

Pattern	Signs	Pulse	Tongue
Internal	Vomitting, high fever, gradual onset, chronic, long duration	Deep	Changes in texture and coating
External	Cold, flu, skin eruptions, sudden onset, acute, short duration	Superficial	Changes in coating
Cold	Diminished physiological function, decreased energy, lowered resistance, lowered immunity, white face, aversion to cold, cold extremities, lack of thirst, craving for warmth, clear urine, watery stool, desire for hot drinks, diarrhea, coolness of limbs, timid behavior, soft voice, slow movement, lack of motivation	Slow, tight	White coat, pale body, moist fur
Heat	Physiological hyperfunction, increased energy, increased metabolism, acute pains, fever, thirst, desire for cold liquids, flushed face, red eyes, restlessness, irritabiliity, dry stool, dark yellow urine, reduced urine secretions, aversion to warmth, hot red skin, constipation, warm extremities, loud voice, talkative, extroverted manner, aggressive behavior	Rapid	Red tongue with yellow fur
Deficiency	Great weakness, low syptomatic reactions, inconsistent energy, shallow and rapid respiration, less severe pain, pain characterised by soreness, weak or inconsistent voice, dull menstrual pain, withered face, low spirits, abdominal pain	Empty, weak	Little or no coat
Excess	Flushed face, loud voice, coarse and full breathing, sharp and acute pain, extreme menstrual pain, tender abdomen, condition worsens with apllication of heat	Full	Thick coat

Figure 21.12. Signs of Internal, External Cold, Hot, Deficient and Excess Conditions

Usually, in men, the pulse on the left (Yang) side of the body should be slightly stronger then that of the pulse on the right (Yin) side, and vice versa for women. Also in men, the front (Yang) positions should be slightly stronger, while in women the lower (Yin) positions should be stronger.

OVERVIEW

In the clinic we have a saying, "Where the Qi goes, the Blood flows." Although a patient's pulse is produced by the movement of Blood in the arteries, the activity of that movement is initiated by the force of the patient's Qi. By feeling the movement of Blood in the vessels, the activity of the patient's Qi, Blood, and Body Fluids are diagnosed. This internal communication is summarized in the above chart (Figure 21.12).

CHAPTER 22
DIAGNOSIS ACCORDING TO QI, BLOOD, AND BODY FLUID DYSFUNCTIONS

INTRODUCTION

This method of diagnosis identifies patterns on the basis of disharmonies according to Qi, Blood, and Body Fluids. It is used in clinical practice (especially for internal diseases) for diagnosing according to the pathological changes occurring in the internal organs.

The essential cause of disease is due to an imbalance of Qi, Blood, or Body Fluids. When one or more of these substances are unbalanced, the body's normal physiological function is disrupted and sickness results. This can be caused by the effect of the Six Exogenous Pathogenic Factors, Seven Emotional Pathogenic Factors, and is influenced by the patient's general constitution. Each of the patient's organs and channels have sets of symptoms or syndromes of these types of imbalances, which can then be identified for treatment. The Qigong doctor's ability to identify problems based on the pathological manifestations of Qi, Blood, and Body Fluids is founded on clinical observations of Excess, Deficient, Stagnant, and Rebellious patterns (Figure 22.1). These patterns can be further defined as predominantly Yin or Yang. These patterns also described as the various disorders of Qi, Blood, and Body Fluids, and sometimes overlap, for example:

- Excess conditions can give rise to Rebellious Qi and also create stagnation;
- Deficient conditions can give rise to Rebellious Qi and also create stagnation.

DISORDERS OF THE QI

Whenever energy movement is impeded, disorders in Qi functions occur. Generally, these dis-



Figure 22.1. Pathological Manifestations of Qi, Blood, and Body Fluids

Fire		**Water**
Constraint of Qi	**First Stage**	Stasis of Qi
Arrogant/Agitated	**Second Stage**	Fluid Builds Up
Full on Fire is Created	**Third Stage**	Phlegm is Created
Heart Fire is Created	**Final Stage** ——> Mania <——	Phlegm Fire is Created

Figure 22.2. Disorders caused from the obstruction of Qi flow result in either Fire or Water energetic dysfunctions.

turbances cause either disorders of Fire, or disorders of Water (Figure 22.2).

The cause and progression to these disorders can be further broken down and classified according to their energetic dysfunction (Figure 22.3). There are several types of Qi disorders observed in the clinic and are generally described as follows.

LEAKAGE AND LOSS OF QI

During or after the training practice, the patient may feel that Qi is continuously and uncontrollably leaking out of the body from the genitalia and anus or anywhere else on the body. This loss of Qi can lead to Qi Deficiencies, and manifest through the following symptoms: emaciation, weakness of the limbs, grayish and dull complexion, nervousness, mental disturbances, distractibility, failing memory, spontaneous sweating, night sweats, seminal emission, insomnia, lassitude, and sluggishness.

DEFICIENT QI DISORDERS

Deficient Qi exists when the entire body, or particular organ, is not being sufficiently nourished by the Qi. This results in there being too little energy to maintain proper organ function. This condition is usually caused by a weakness of the Lungs, Spleen, or Kidneys, by chronic illness, or a weak constitution, poor diet, or fatigue. Deficient Qi is unable to:

- transform, resulting in symptoms such as diarrhea,
- transport, resulting in symptoms such as stagnation of Qi,
- hold, resulting in symptoms such as bruising,
- warm, resulting in symptoms such as cold extremities,
- protect, resulting in symptoms such as sickness, and
- raise, resulting in symptoms such as prolapse.

Deficient Qi is divided into three subcategories from which the patient can suffer. These subcategories are Empty Qi, Sinking Qi, and Qi Collapse. Each of these subdivisions can further be divided into Yin and Yang types.

1. Empty Qi is considered the first type of Deficiency. If not treated, Deficient Qi may progress to a condition known as Empty Qi. Diseases that are classified as Empty Qi are characterized by a serious weakness or Deficiency of the body's Qi. Empty Qi, especially Empty Yang Qi manifests as a weakness


Turbidity flowing against the course of the channels
Turbidity flowing with the course of the channels
Deficient Rebellious Qi
Excess Rebellious Qi
Turbid Qi
Rebellious Qi Disorders
Excess Qi Disorders
Disorders of Qi
Qi Stagnation
Deficient Qi Disorders
Qi and Blood Stagnation
Obstructed Qi
Empty Yang Qi
Empty Qi
Wind Obstruction
Sinking Qi
Cold Obstruction
Qi Collapse
Damp Obstruction
Heat Obstruction
Collapse of Yang
Collapse of Yin

Figure 22.3. Whenever energy movement is impeded or in excess, disorders in Qi function occur, resulting in Qi Deviations.

in the function of holding, moving, and transforming Qi.

   a. Empty Qi originates primarily from the patient's constitution and manifests as malnutrition, fatigue, premature signs of old age, and an excess of extreme emotions.
   b. Empty Yang Qi belongs to the category of Yang. Because Yang Qi has the function of warming, Empty Yang manifests as an inability to adequately warm the energy, resulting in Cold symptoms. Empty Yang is generally caused by a weak constitution, poor diet (excessive raw, cold food and drink), overwork, old age, and excess sex.

2. Qi Sinking is also a subcategory of Deficient Qi, and is considered the second type of Deficiency. If not treated, Empty Qi may progress to a more serious Deficient condition known as Qi Sinking. This condition results in symptoms such as tiredness, listlessness, and mental depression, and may eventually lead to the prolapse of one or more of the organs.
3. Qi Collapse is a subcategory of Deficient Qi and is considered the third and most severe type of Deficiency. A Qi collapse exists when the Qi is so Deficient that it can no longer hold the internal organs in place. This Qi depletion not only causes a weakness of the body's Righteous Qi, which leads to the prolapse of the organs (Stomach, uterus, intestines, rectal area, vagina, or Bladder), but also induces prolonged diarrhea, upper abdominal distention, and dizziness.
   a. The Collapse of Yin results in pure Fire. The main manifestations are abundant perspiration and external tissue, which is hot to the touch.
   b. The Collapse of Yang results in pure Cold. The main manifestations are chills and external tissues which are cold to the touch.

EXCESS QI DISORDERS

An Excess Qi condition is caused from too much Qi, which overacts on an organ, affecting its function, and usually produces too much transformation and Heat in a given organ. This can be due to over-energizing the organs and channels, from excessive Qigong exercises and meditations, or too much energy stimulation during a Qigong doctor's treatment.

QI STAGNATION DISORDERS

Qi stagnation exists when the Qi is not flowing smoothly, and becomes sluggish when moving within the body's channels, organs, or tissues. Qi stagnation can be caused by many different factors such as: suppressed emotions, trauma, contraction of microorganisms, poor diet, and weak digestion. Qi stagnation, over time, results in localized pain, distention, cysts, tumors, etc. Qi stagnation disorders have two subcategories: Qi and Blood Stasis, and Obstructed Qi.

1. Qi and Blood Stasis refers to the sensation of local pain, heaviness, soreness, distention, and compression, which are caused by the stagnant Qi and Blood in certain areas of the body. These sensations do not disappear by themselves. This stasis may occur during or after Medical Qigong training practice from Qi disorders and visceral malfunctions.
2. Obstructed Qi is also considered a subcategory of Qi stagnation, and exists when the Qi becomes so stagnant that it no longer flows. At this stage the Qi can not move the Blood. This can be caused by trauma, surgery, and acute Qi stagnation.

When Qi becomes obstructed inside the body, certain clinical manifestations result, such as:

- Cold Obstruction causes Qi to become fixed with local numbness that improves with heat;
- Damp Obstruction causes Qi to become fixed with local swelling;
- Heat Obstruction causes Qi to become inflamed, red, and swollen;
- Damp Heat Obstruction is a combination of Damp and Heat. It is called "summer Damp Heat," and results in poor appetite, dizziness, diarrhea, heaviness of the head, and sensations of chest suffocation;
- Wind Obstruction causes migrating pain that moves from joint to joint.

Organ	Normal Flow	Rebellious Flow	Symptoms
Liver	Upwards	Excessively Upwards Horizontally to Stomach Horizontally to Spleen Horizontally to Intestines Downwards	Dizziness, Headache, Irritation Nausea, Belching, Vomiting Diarrhea Dry Stool Burning Urination
Heart	Downwards	Upwards	Insomnia, Mental Restlessness
Spleen	Upwards	Downwards	Diarrhea, Prolapse of Organs
Stomach	Downwards	Upwards	Hiccup, Nausea, Belching, Vomiting
Lungs	Downwards	Upwards	Coughing, Asthma
Kidneys	Downwards	Upwards	Asthma

Figure 22.4. Chart of Rebellious Qi Flow

REBELLIOUS QI DISORDERS

Rebellious Qi disorders manifest as Qi flowing in the wrong direction (a direction different from its normal physiological progression); this causes a disturbance within the harmonious flow of energy and affects the organs' functions. The symptoms have to be analyzed according to the internal organ which is involved. There are two types of Rebellious Qi, the Excess and Deficient type. Rebellious Qi is categorized as follows:

DISORDERS OF EXCESS REBELLIOUS QI

Disorders of Excess Rebellious Qi occur when the vital Qi increases and forces the pathogenic Qi to move; leading to local sensations of pain, soreness, distention, heaviness, cold or heat, which can develop during a patient's Qigong practice (Figure 22.4).

DISORDERS OF DEFICIENT REBELLIOUS QI

Disorders of Deficient Rebellious Qi refers to the disorderly flow of Qi and Blood during or after the training practice, which causes dizziness, fright, a heavy feeling in the chest, shortness of breath, shaking limbs, trembling of the hands and feet, or fainting. Generally, energy sensitive patients know the location and direction of the disorderly flow of Qi in their tissues.

TURBID QI

While transforming and transporting energy, the body divides ingested and absorbed Qi into Clear and Turbid energy for distribution (keeping and redistributing the clean, while disposing of the turbid). Turbid Qi refers to any dark, murky energy which can originate within, or from outside of the body's organ system, and sometimes travels throughout the body's channel system. Turbid Qi attaches to the body's wounds (physical, emotional, or spiritual), manifesting as dark, discolored clouds of energy. This energy can adversely affect the body's physical, emotional, and energetic balance, especially when combined with any pathogenic internal or external factor.

PATHOGENIC SENSING OF TURBID QI

Feeling the sensations of Turbid Qi is referred to as "pathogenic sensing." This skill is acquired by the doctor while projecting energy to his patients. While emitting energy, the Qigong doctor can sense the patient's Yuan Qi, as well as the Turbid Qi inside the patient's body. This enables the doctor to diagnose and treat their patients' diseases according to the various Qi sensations, and to categorize the patients' Turbid Qi. The Turbid Qi is also called Evil or "pathogenic Qi." The flow point is located at the Lower Tan Tien at the top of the navel. And, the Universal Aura body collection point is located above the head in the Universe.

These collection points are utilized to create a powerful method of fusing all the elements into the pearl. Once all the collection points are established, the Energy Body and Universal Aura body collection points are rotated. This way there are different colors at the various collection point sites. For example, the collection points at the Energy Body are turned clockwise – the green is on the upper point, red is at the left, white is at the bottom, and blue is on the right. The Universal collection point is rotated counterclockwise – white is the upper point, blue is at the left, green at the bottom, and blue at the right. Creating different colors at each of the collection points takes the fusing process to another level of intensity. These colors are then mixed and blended into the cauldron and formed into a powerful pearl.


Universal Body
1
Heart Energy
Physical Body
1
S
Top
Energy Body
1
Universal Energy/Force
2
Liver Energy
2
Right
2
4
4
Left
4
Lung Energy
3
3
N
3
Kidney Energy
Universal Body
Physical Body
Energy Body

***Fig. 6.29** Fuse inner position energy with universal energy.*

of Turbid Qi within the patient's channels is characterized as follows:

- Turbidity flowing with the course of the channel indicates transference of Turbid Qi towards the body's interior.
- Turbidity flowing against the course of the channel indicates the beginning production of Turbid Qi.

Turbid Qi differs from the pathogenic factors of infectious diseases referred to in Western medicine. According to clinical experience, the pathogenic sense of Turbid Qi can be classified as: Dry or Hot Sensations, Cold or Chilly Sensations, Soreness or Numbing Sensations, Impure or Foul Sensations, The Sensations of The Seven Emotions, and The Sensations of The Six Climate Conditions.

1. Dry or Hot Sensations are considered Yang signs or symptoms of Heat. This type of Turbid Qi feels feverish and flaccid; it can cause perspiration, irritation, etc. The sensations of dry-heat on the body or hands of the doctor often cause the doctor to fidget, as if being scorched by a fire. It may also serve as an indicator of syndromes of Excess Heat and hyperactivity of Fire due to a Yin Deficiency.
2. Cold or Chilly Sensations are considered Yin signs or symptoms of Cold. This type of Turbid Qi feels cold, rigid, and stagnant. It may be so cold that the doctor's fingertips turn cold immediately. This coldness transmits from the doctor's fingertips upward, causing shivering and contractions of the sweat glands ("goose-bumps"). This gives the doctor a particular feeling of cold and discomfort. Cold feelings often serve as a message of Deficiency and Cold syndromes such as rheumatism, rheumatoid disease, Deficiency of the Kidney Yang, and certain types of cancer.
3. Soreness or Numbing Sensation often indicate syndromes of hyperactivity of the Liver Yang and Excess of Wind, Cold, Dampness or Phlegm, as well as arthralgia syndrome and cancer. The doctor may experience an uncomfortable feeling of local soreness or pain, heaviness, numbness, tingling and itching.
4. Impure or Foul Sensations can be felt when the doctor is standing opposite the patient, or when extending energy towards the patient. It is an indescribable unpleasant feeling that is often felt when the open palm and fingers are used to detect a disease.
5. The Seven Emotions (joy, anger, worry, anxiety, fear, shock, and grief) in excess will cause discomfort to the doctor. During treatment, the doctor may detect and feel the different natures of these emotional pathogenic Evils flowing through the doctor's body. The doctor may, for example, have a specific feeling of anger if the disorder of the patient is due to excessive anger. Once these pathogenic emotions are discovered, the doctor must purge or disperse them, as well as determine their origin, and cause.
6. The Six Climate Conditions (Wind, Cold, Summer Heat, Dampness, Dryness, and Fire) will also cause discomfort to the doctor. During treatment, the doctor may detect and feel the different natures of these pathogenic Evils. The doctor may, for example, have a specific feeling of slippery wet ooze if the disorder of the patient is due to Dampness.

RECTIFYING QI DISORDERS

The primary treatment principles for rectifying Qi Disorders are as follows:

- for Qi leakage - tonify
- for Deficient Qi - tonify
- for Empty Qi - tonify
- for Qi sinking - raise and tonify
- for Collapsed Qi - tonify
- for Excess Qi - reduce
- for Stagnant Qi - move
- for Obstructed Qi - move
- for Rebellious Qi - calm and subdue
- for Turbid Qi - remove, dredge, and purge

These are often found in combination with other patterns. Here are some examples of treating combined patterns:

- for Excess and Rebellious Qi, reduce Excess and calm Rebellious Qi;
- for Deficient and Rebellious Qi, tonify Deficient and calm Rebellious Qi;



Figure 22.5. Whenever Blood movement is impeded or in excess, disorders in Blood function occur.

- for Excess and Stagnant Qi, reduce Excess and move the Stagnant Qi;
- for Deficient and Stagnant Qi, tonify Deficient and move the Stagnant Qi;
- for Excess and Deficient Qi, drain Excess and tonify Deficient Qi; and
- for Rebellious and Stagnant Qi, calm Rebellious and move the Stagnant Qi.

DISORDERS OF THE BLOOD

To understand Blood disorders it is important to understand the concept of Blood from the perspective of Traditional Chinese Medicine. In Chinese Medicine, Blood is different in concept, characteristics and function from that of Western medicine. Blood originates from the transformation of food and drink by the Spleen, which then transfers the refined food energy (Gu Qi) to be further enhanced by the Heart, Lungs, and air energy. Blood is therefore considered a transformation of constructive energies.

Disorders of the Blood can relate to disorders of the Qi. Qi and Blood flow together, Qi being the active force which makes the Blood circulate and keeps it within the blood vessels. Both Qi and Blood flow within the channels and blood vessels, continuously circulating throughout the body nourishing, maintaining, and moistening the tissues. Qi is an energetic form and is considered a Yang substance, while Blood is a liquid form of energy and considered a Yin substance. The cause and progression to Blood disorders can be further broken down and classified according to their energetic dysfunction (Figure 22.5). There are several types of Blood disorders observed in the clinic and are generally described as follows.

DEFICIENCY OF BLOOD

A Deficiency of Blood exists when the entire body, or a particular organ, is insufficiently nourished by the Blood, or not enough Blood is present to nourish the organs and channels, to support the Qi. Blood Deficiency is usually caused from Blood loss, chronic illness, poor diet, or Spleen Qi Deficiency, which weakens the Qi. This in turn affects the Liver (causing symptoms of dizziness, blurred vision, and numbness) and Heart (causing symptoms effecting the mind, memory, and Shen).

LOSS OF BLOOD

Loss of Blood is considered a subcategory of Deficient Blood. Loss of Blood is caused by Spleen Qi failing to control the Blood, resulting in the Blood spilling out of the vessels and organs, etc. Loss of Blood is divided into two main types:

- Deficient loss of Blood is caused by an insufficiency of Qi to hold the Blood.
- Excess loss of Blood, is caused by either Blood-Heat pushing the Blood out of the vessels, or by Blood stagnation and Yin Deficiency which causes the Blood to pool.

EMPTY BLOOD

Although Empty Blood is a subcategory of Deficient Blood, it is considered a serious Deficient condition, mostly due to the Blood of the whole body becoming Deficient. Empty Blood corresponds to a Deficiency of Qi, caused by:

- Inadequate nutrition,
- Loss of Blood through accident or disease,
- Loss of Body Fluids through excessive sweating, urination, vomiting, or diarrhea,
- Extreme emotions (e.g., rage, terror and shock),
- Blood stagnation, which leads to poor Blood circulation.

Since the Empty Blood fails to nourish the tendons and muscles, it results in shaking in the extremities and head, dizziness, and blurred vision.

Empty Yin

Blood belongs to the category of Yin. Because Yin Qi has the function of cooling and moistening, when an Empty Yin condition is present, the symptoms manifest as Excess Heat and Dryness. Empty Yin is caused by a weak constitution and a poor diet (overcooked foods and hot liquids). The organs most likely to be effected by the Empty Yin condition are the Kidneys, Lungs, Heart, Liver, and Stomach.

BLOOD STAGNATION

Blood Stasis exists when the Blood is unable to flow smoothly, and becomes obstructed or congeals. Blood stasis is usually caused by an impact trauma, Deficient Blood, stagnant Blood, Blood Heat, Blood Cold, or stagnant Qi. It results in localized pain which worsens with pressure, swelling of the internal organs, cysts, and tumors. The organ most often affected by Blood stasis is the Liver.

BLOOD HEAT

Blood Heat is mostly due to Liver Heat and External Wind. When toxic Heat enters the Blood, the Blood may break out of the vessels and cause: nose bleeding, hemorrhaging, and broken blood vessels. Heat consumes the Blood and Yin, injuring the tendons and muscles, causing spasms and rigidity. The Blood Heat also injures the Governing Vessel, Pericardium, and the Shen.

The Four Main Treatment Principles

- for a Deficiency of Blood, tonify
- for Empty Blood, tonify
- for Blood Stasis, move Stasis
- for Blood Heat, cool down

THREE DISORDERS OF BODY FLUIDS

To understand disorders of the Body Fluids it is important to understand the concept of Body Fluids, from the perspective of Traditional Chinese Medicine. Body Fluids are a denser form of Qi, and depend on Qi for transformation and transportation. Qi occupies and directs the movement of Blood and Body Fluids. The function of the Fluids is to moisten and nourish the body's tissues, as well as thin the Blood to prevent stasis. Body Fluids are formed from ingested food and drink, and are then transported by the energy of the Spleen to the Lungs and Small Intestines for distribution.

Disorders of the Body Fluids can relate to disorders of the Blood. There is a constant interchange between Fluids and Blood, such as, for example, a Deficiency of Fluids can be developed from a heavy loss of Blood. Body Fluids are divided into two categories:



Figure 22.6. Whenever Body Fluid movement is impeded or in excess, disorders in Body Fluid function occur.

1. Jin refers to the light, thin, watery, clear, quick-moving Fluids and is considered Yang. These Fluids are under the control of the Lungs which circulate them with the Wei Qi. These Fluids also permeate and moisten the skin and have the function of warming and nourishing the muscles. The Upper Burner is responsible for controlling the Jin transformation and moving it towards the skin. The Jin is manifested in the body in the form of sweat, tears, saliva, mucus, and parotid serum.
2. Ye refers to the heavier, thicker, turbid, dense, slow moving Fluids and is considered Yin. These Fluids are under the control of the Middle and Lower Burners, which circulate the Ye with the Ying Qi. The Spleen and Kidneys are responsible for controlling the Ye transformation. This Fluid lubricates the joint cavities (synovial fluid), nourishes and lubricates the brain and spinal cord (cerebrospinal fluid), bone marrow and the orifices of the sensory organs (eyes, ears, nose, and mouth).

There are three primary disorders of Body Fluids observed in the clinic, they are described as follows (Figure 22.6).

1. Deficient Body Fluids exists when the entire body, or a particular organ, is insufficiently nourished by Body Fluids. This is generally due to insufficient Yin to create or nourish the body's organs or joints. Deficient Body Fluids are usually caused by prolonged loss of Fluids (sweating, diarrhea, and vomiting), prolonged illness, a Heat condition, or a Yin Deficiency which leads to Dryness. A Deficiency of Body Fluids usually affects the Lungs, Kidneys, Stomach, and Large Intestines.
2. Excess Body Fluid accumulation is usually caused by an Excess Yin and one of three factors, or a combination of all of them. They are:
   - A Lung Qi Deficiency, which affects the top of the body, face and hands,
   - A Spleen Qi Deficiency, which affects the middle part of the body, and abdomen,
   - A Kidney Qi Deficiency, which affects the lower part of the body, legs and ankles.

   If there is a Deficiency within one or all three of these organs, and the Body Fluid is not able to transform properly, it will overflow the channels and settle under the skin.
3. Retention of Phlegm is due primarily to a Deficiency of the Spleen failing to transport

and transform the Body Fluids. If Phlegm is retained for long periods of time, disease of the organs (Substantial Phlegm), as well as channels, skin, and joints (Non-Substantial Phlegm), can form.

The Three Main Treatment Principles

- for Deficient Body Fluids, moisten;
- for Excess Body Fluids, dry or drain;
- for Retention of Phlegm, resolve.

TYPES OF PHLEGM

The concept of Phlegm is an important pathological and etiological factor in Traditional Chinese Medicine. If Phlegm is allowed to accumulate and becomes retained within the body, it causes disease.

The main cause of Phlegm formation is Spleen Deficiency. If the Spleen becomes weak and fails to transform and transport the Body Fluids, these will accumulate and transform into Phlegm. However, Phlegm formation can also occur if the Lungs fail to disperse and lower Fluids, or if the Kidneys fail to transform and excrete Fluids.

In Traditional Chinese Medicine, there are two types of Phlegm: Substantial Phlegm and Non-Substantial Phlegm.

1. Substantial Phlegm is described in ancient texts as "having a form." It can be observed as the thick mucus that collects within the Lungs and spat out during bronchial infections and other Lung diseases. As the Lung disease progresses, the patient's mucus changes color, progressing from clear watery to yellow and thick, then to green and pussy, and finally brown and red.
2. Non-Substantial Phlegm is described in ancient texts as "having no form." This type of Phlegm can accumulate within:
   - the body's organs forming stones,
   - the joints forming arthritic bone deformations,
   - the skin forming lumps or cysts, and
   - the channels causing stagnation of Qi and Blood, resulting in numbness.

Both Substantial and Non-Substantial Phlegm can assume different forms of disease, developing in accordance to its associations with Heat, Cold, Damp, Wind, Qi, and Fluids. For example:

1. Phlegm Heat is a type of Substantial Phlegm that affects the Lungs, Stomach, or Heart. It manifests as yellow sticky phlegm, a red face and a red tongue with sticky yellow coating.
2. Cold Phlegm is a type of Substantial Phlegm that affects the Lungs and Stomach. It manifests as white watery phlegm expectoration, cold feelings in the back and extremities, and a pale tongue with a white and wet coating.
3. Damp Phlegm is a type of Substantial Phlegm that affects the Lungs. It manifests as a profuse white sticky phlegm, feelings of stuffiness in the chest and epigastrium region, and a sticky tongue coating.
4. Wind Phlegm is a type of Non-Substantial Phlegm and is seen in Wind Stroke. It causes dizziness, nausea, vomiting, coughing up of Phlegm, numbness of the limbs, rattling throat, and aphasia.
5. Qi Phlegm is a type of Non-Substantial Phlegm which affects the throat. It manifests as a "plum pit" syndrome within the throat. Its formation is related to emotional problems, created when the Liver Qi rises and stagnates within the throat. Its condition manifests as a feeling of swelling in the throat, difficulty in swallowing, and stiffness in the chest and diaphragm.
6. Phlegm Fluids is a type of Substantial Phlegm which has a fluid or watery nature, and is called Yin in Chinese medicine. There are four types according to their location:
   - Phlegm Fluids located in the Stomach and intestines manifest as abdominal fullness, distension, and vomiting;
   - Phlegm Fluids located above the diaphragm manifest as coughing, asthma, edema, and dizziness;
   - Phlegm Fluids located within the hypochondrium manifest as distension in the hypochondrium area, with pain and coughing;
   - Phlegm Fluids located in the four limbs manifest as heaviness and pain in the muscles.

CHAPTER 23

DIAGNOSIS ACCORDING TO THE FIVE-ELEMENT THEORIES

INTRODUCTION TO THE FIVE ELEMENTS

This method of diagnosis is based on the interpretation of clinical manifestations according to the creative, controlling, invading, and insulting sequences of the Five Elements. The Five Elements are five phases of transition used in Chinese Medicine and are sometimes referred to as the Wu Xing. Wu translates to mean the number five, Xing translates to mean a process of movement or walking. The concept of the Five Elemental theory began to first appear in documents in China during the Zhou Dynasty (from 1000 to 770 B.C.). This theory classified tangible and intangible substances into five categories for observation and study, as well as diagnosis and treatments.

1. The Wood Element is associated with the active functions of birth in nature's growth stage of development.
2. The Fire Element is associated with maximum functional activity in nature's growth stage of development.
3. The Earth Element is associated with the function of stabilization in nature's growth stage of development.
4. The Metal Element is associated with nature's declining functions of the growth stage of development.
5. The Water Element is associated with the maximum state of rest in nature's growth stage of development.

The Five Elemental theory is used to explain the classifications and characteristics along with the laws of universal cycles (creating, controlling, invading and insulting). These interactions are studied today in Traditional Chinese Medicine to assist the doctor's diagnosis in comprehending the growth and development of the body's energetic anatomy, physiology, disease processes, and symptom development (Figure 23.1).



Figure 23.1 The Five Elements

THE FIVE ELEMENTS AND YIN AND YANG THEORY

It is important to understand the Five Elemental theory's energetic origin and its interaction with Yin and Yang Qi to appreciate its energetic categorizations.

The ancient Chinese Qigong masters believed that the creation, development, and declining transitions of all things throughout the universe were the result of the interaction of Yin and Yang Qi. The Yin and Yang theory was therefore used to describe the opposing, interdependent, as well as waxing and waning transitions of all things, especially the interactions of the Five Elements (Wood, Fire, Earth, Metal, and Water). Fire and Wood are considered active Yang elements, while Water and Metal are considered quiescent Yin elements. The Earth is considered a balance point between Yang and Yin.

Qigong doctors assign the Five Elements of Traditional Chinese Medicine to the body's organs and tissues. The Five Elements are considered the Jing of the body's Yin and Yang energy pools. Imagine each element organ as a pool of liquid energy. The energetic movement, much like water, flows from element to element. This flowing movement of liquid energy is considered to be the body's energetic pulse, moving Qi to and from these pools.

The rivers of Qi cannot exist without the pools of Jing to nourish their flow and function; and the pools of Jing cannot act without the rivers of Qi stimulating their action. Therefore the principle action of the Five Elements is the circulation of the Yin and Yang Qi.

The human body is like a living Taiji symbol (see Chapter 21). Its back channels are considered Yang; its front channels are considered Yin; and its center channel is contained through the energetic actions of the Taiji Pole. The Taiji Pole produces Yang Qi by the inhalation of life-force energy through the breath. When Yang Qi reaches its peak, it rests, while the Yin Qi begins to increase. When the Yin Qi reaches its peak and comes to rest, then the Yang Qi begins to increase once more. This continuous interaction of Yang energy with Yin energy produces and enhances within the body, the Five Elemental organ energies of the Liver (Wood), Heart (Fire), Spleen (Earth), Lungs (Metal), and Kidneys (Water).

The first stage of Qigong exercises and meditations create an energetic transformation which regulate, refine, and reduce these Five Elemental organ energies into two primary Yin and Yang energies known as Fire and Water Qi. The second stage of transformation consists of combining the Water and Fire energy into one union of Three Human Treasures (Jing, Qi, and Shen). This energetic transformation is responsible for "bringing 10,000 things into being" (Figure 23.2). In China, these meditation stages are used for exploring the stimulation of the energetic functions of the central nervous system, the peripheral nervous system, cardiovascular system, digestive system, reproductive system, etc.

The Five Elemental theory assists the Qigong doctor in examining the energetic correspondences for clinical evaluation. This is only one phase of clinical observation however, and should always be applied with the Yin and Yang theory.



Figure 23.2 Stages of Energetic Transformation

THE CREATIVE OR GENERATIVE CYCLE

Within every Qi cycle each element has two main aspects: it is either (1) creating or being created, or (2) restricting and / or being restricted. In the process of growth and development, both creative and restrictive patterns are needed. Without creation, growth would have no origin, and growth without restriction can create harm. The creative element is called the Mother, and the element created is called the Child. This is the "Mother and Child" relationship referred to in Traditional Chinese Medicine. The Creative Cycle is generally used for tonification, as the stimulation of one organ enhances the function of the next (Figure 23.3). The Five Elemental Creative Cycle and its organ correspondences are as follows.

1. The Liver's element is Wood, which is used to create the Heart's element Fire. The Liver is the Mother of the Heart, which is the Child. The Liver stores the Blood and Blood houses the Shen. If the Mother (Liver) becomes Stagnant, the Child's Heart (Shen) will suffer. Clinical manifestations include indecision, timidity, lack of courage, palpitations, and early morning insomnia.
2. The Heart's element is Fire, which is used to create the Spleen's element Earth. The Heart is the Mother of the Spleen. The Heart's Qi pushes the Blood, thereby helping the Spleen in its function of transporting. If the Mother (Heart) becomes stagnant, the Child (Spleen) will suffer, creating a Spleen Yang Deficiency. This is due to failure of Heart Fire in providing Heat to the Spleen. Clinical manifestations include chills, weakness in the limbs, and loose stools.
3. The Spleen's element is Earth, which is used to create the Lungs' element Metal. The Spleen is the Mother of the Lungs. The Spleen Qi provides Gu Qi (food energy from the Earth) to the Lungs where it combines with air (energy from Heaven) to form Gathering (Zong) Qi. If the Mother (Spleen) becomes Deficient, the Child (Lungs) will suffer, creating Phlegm which obstructs the Lungs. Clinical manifestations include Phlegm in the chest, coughing, and general weakness.
4. The Lungs' element is Metal, which is used to create the Kidneys' element Water. The Lungs are the Mother of the Kidneys. The Lungs send Qi down to meet the Kidney Qi, as well as Fluids to nourish the Kidneys. If the Mother (Lungs) becomes stagnant, the Child (Kidneys) will suffer, due to the Kidneys not receiving enough Qi. Clinical manifestations include breathlessness, loss of voice, coughing, and asthma.
5. The Kidneys' element is Water, which is used to create the Liver's element Wood. The Kidneys are the Mother of the Liver. The Kidneys' Yin nourishes the Liver Blood. If the Mother (Kidneys) become Deficient, the Child (Liver) will suffer (i.e., Liver Yin Deficiency). Clinical manifestations include headaches, blurred vision, dizziness, and vertigo.



Figure 23.3 The Five Elemental Creative Cycle

THE CONTROLLING OR RESTRICTIVE CYCLE

This is a condition in Traditional Chinese Medicine where one element brings under control, or restrains, a corresponding element, thus ensuring that a dynamic balance is maintained among the Five Elements. The element that restricts is considered successful, while the element being controlled is in check. It is commonly referred to as "the strong controlling the weak," and is generally used for sedation, to ensure that the Creative Cycle does not over-create and cause imbalances. The element prior to the Mother is commonly referred to as the Grandmother. In the Controlling Cycle, it is the Grandmother who controls the Child (Figure 23.4). The Five Elemental Controlling Cycle and its organ correspondences are explained as follows.

1. The Wood absorbs nutrients from the Earth, i.e., the Liver (Grandmother) controls the Spleen and its paired organ the Stomach (Child). Two of the Liver's energetic functions are to help the Stomach "rot and ripen" the food and the Spleen to transform and transport the Gu Qi.
2. The Earth restricts Water, i.e., the Spleen (Grandmother) controls the Kidneys (Child). Both the Spleen and Kidneys control the transformation of Body Fluids.
3. The Water extinguishes Fire, i.e., the Kidneys (Grandmother) control the Heart (Child). The energetic aspect of the Kidneys' Water controls the energetic balance of the Heart's Fire.
4. The Fire melts Metal, i.e., the Heart (Grandmother) controls the Lungs (Child). The Heart governs the Blood, while the Lungs govern Qi (both Qi and Blood mutually assist and nourish each other).
5. The Metal chops Wood, i.e., the Lungs (Grandmother) control the Liver (Child). If the Lungs' Qi is weak it will not descend thus allowing the Liver Qi to rise.

THE INVADING OR OVERACTING CYCLE

This is a condition in Traditional Chinese Medicine where an element overacts, overcontrols and invades, the element it is supposed to control (Figure 23.5). Instead of the role of checking and restraining, one element severely attacks another element, stealing Qi from its energetic pool. This is generally observed in cases of Excess or Deficiency conditions of the organs. The Five Elemental Overacting Cycle and its organ correspondences are as follows.



Figure 23.4. The Five Elemental Controlling Cycle

1. The Wood invades the Earth, i.e., the Liver (Grandmother) overcontrols the Spleen (Child) and its paired organ the Stomach. In the clinic, this is commonly called "Liver invading the Spleen." Clinical manifestations include hypochondriac and epigastric pain and distension, irritability, poor appetite, loose stool, and a green face color.
2. The Earth invades the Water, i.e., the Spleen (Grandmother) overcontrols the Kidneys (Child). This occurs when a Deficient Spleen fails to transform and transport Fluids. These Fluids accumulate and obstruct the Kidneys' function of transforming and excreting Fluids. Clinical manifestations include edema, difficulty urinating, and a yellow face color.
3. The Water invades the Fire, i.e., the Kidneys (Grandmother) overcontrol the Heart (Child). This pattern is almost never seen in clinical practice since the Kidneys are rarely in Excess.
4. The Fire invades the Metal, i.e., the Heart (Grandmother) overcontrols the Lungs (Child). This results in Full Heat in the Lungs.

Pulmonary disease can be caused by cardiac disorders, this is known as "Fire Overacting and Invading Metal." Clinical manifestations include cough with yellow sputum, a feeling of Hot sensations, and a red face color.

5. The Metal invades the Wood, i.e., the Lungs (Grandmother) overcontrols the Liver (Child). Clinical manifestations include irritability, a feeling of distension, fatigue, and a white face color.

THE INSULTING OR COUNTERACTING CYCLE

This is a condition in Traditional Chinese Medicine where the elements reverse their restrictive cycle and the Child insults the controlling element, the Grandmother (Figure 23.6). This is generally observed in cases of Excess or Deficiency within the Five Elements. The Five Elemental Insulting Cycle and its organ correspondences are as follows.

1. The Wood dulls the Metal ax, i.e., the Liver (Child) insults the Lungs (Grandmother). If the Child (Liver Qi or Liver Fire) becomes stagnant, it can obstruct and prevent the Lung's Qi (Grandmother) from descending. Clinical manifestations include coughing, a feeling of distension in the chest and hypochondrium area, and asthma. If pulmonary disease is due to the impairment of the Liver, it is explained as "Wood Insulting or Counteracting Metal."
2. The Metal controls the spread of Fire, i.e., the Lungs (Child) insult the Heart (Grandmother). If the Child becomes Deficient, it can cause the Heart Qi (Grandmother) to become Deficient. Clinical manifestations include palpitations, breathlessness and insomnia.
3. The Fire dries up the Water, i.e., the Heart (Child) insults the Kidneys (Grandmother). If the Grandmother (the Kidneys' Yin) becomes Deficient, then the Heart (Child) can become excessive, giving rise to Heart Empty Heat. Clinical manifestations include dizziness, lower back pain, night sweating, insomnia, malar flushes, and dry mouth (at night).
4. The Water erodes the Earth, i.e., the Kidneys



Figure 23.5 The Five Elemental Invading Cycle



Figure 23.6 The Five Elemental Insulting Cycle

The Concept of Fusing Inner Position Energy with Universal Energy

The fused collection points are utilized to create a powerful method of fusion all the elements into a pearl.

There are four collections points of the elements; fire, water, metal and wood of the physical body, energy body and universal body.

Once all the collection points are established in the Physical Body, the Energy Body and the Universal Body we use a dial to assist in rotating the patterns of energy.

- Understanding that the physical body is more dense and stable; the collections points are fixed.
- The energy body is not fixed and is very sensitive to external events and the universe. This can be changed.
- Universal Energy is always changing and is not fixed. As the planets and the body's celluar matter, nuclei, electrons, protons all move at different speeds; we use the differences to create energy.
- The Dial: We use a dial of color to understand the different patterns of energy that can be created. Fusing different energies will generate more intense energy and a powerful pearl.

  Moving the color dials assists the imaginative mind to connect to the patterns of energy. It is a formula, a pattern for the mind to follow.

  In this approach we fuse inside to outside universe and outside to inside. You mix fire and water first, then wood and metal together. You can do it in pairs of points and then all four points, creating four balls of fused energy which are then spun very fast above the cauldron where they fuse to form a pearl. You can reproduce as many pearls as you want.

  The intensity can make you feel a oneness with the universe as part of you becomes part of the universe and universal forces.

(Child) insult the Spleen (Grandmother). In this case, the Child (the Kidneys' Yang) becomes Deficient causing the Grandmother (Spleen) to become Deficient. Clinical manifestations include weak limbs, fatigue, edema, and loose stools.

5. The Earth resists the Wooden plow, i.e., the Spleen (Child) insults the Liver (Grandmother). If the Spleen (Child) fails to transform Fluids, a Damp condition can result. This Dampness can accumulate and begin to obstruct the flow of the Liver's Qi (Grandmother). Clinical manifestations include hypochondriac pain and distension, bile obstruction, and jaundice.

THE FIVE ELEMENTAL TONIFICATION CYCLE

The Five Elemental tonification cycle can be used for balancing the life-force energy of the body in conjunction with nature. Wood corresponds to spring, Fire corresponds to summer, Metal corresponds to autumn, Water corresponds to winter, and Earth corresponds to the late stage of each season (late spring, late summer, late autumn and late winter). The element Earth is centrally placed, associated with the 18 days of transformation at the end of each of the four seasons. The object of using the Five Elemental Tonification Cycle is to support and strengthen the next organ in the cycle (Figure 23.7).



Figure 23.7 The Five Elemental Tonification Cycle

FIVE YIN ENERGETIC ORGAN MANIFESTATIONS

The Five Elemental energies are manifested through five different directions of movement. The Qigong doctor studies the movements and actions of a patient while they are in a meditative state (usually a sitting or standing posture), to diagnose their energetic disposition. After being in a meditative state for awhile, the patient's organs will overflow with Qi. When the organs overflow with Qi, certain physical reactions are evident, indicating which particular element has a problem.

1. Wood or Liver Qi is responsible for the dispersing effect of Qi, and is manifested by expansive outward movements in all directions, causing the body to sway with gentle and soft motions. When the Liver's energy is overabundant the torso makes a gentle, soft movement like a pine tree swaying in the wind. This is caused by the sprouting and branching manifestation of the Liver Qi's rising warm current.
2. When Fire or Heart Qi is overabundant, it is evident through the physical manifestation of the upward ascending actions of the torso caused by the flaring up of Yang Heat. This affects the energetic body and is manifested by upward movements and sometimes jerky actions (like a flame crackling in a fire).
3. Earth or Spleen Qi is generally manifested by stable movements, however, when overabundant, it is evident through movements that are both smooth and swift. This allows the body to progress in a limber, flexible, and free moving action (think of the body movement similar to a spinning ball).
4. When Metal or Lung Qi is overabundant, it is evident through the twitching actions of the torso and is manifested by contracted, inward movements, causing the body to violently jerk from side to side (think of the body as a metal bell being violently struck).
5. When Water or Kidney Qi is overabundant, it

is evident through the clumsy, awkward, heavy downward moving action of the torso (think of a waterfall descending onto rocks).

When the patient's body, unintentionally or unconsciously, rocks or sways gently as a result of a meditative state, the patient does not feel tired upon completing the meditation. However, when a patient consciously tries to force relaxation or augment the movement of his or her body while meditating, he or she will be tired by the end of the meditative session.

Note: While interning at the Medical Qigong Ward at the Xi Yuan Hospital in China, I found it fascinating to observe meditating patients displaying the results of both energetic organ manifestations or consciously induced augmentation of movement. All the above listed energetic manifestations were evident.

CHAPTER 24
OTHER DIAGNOSTIC SYSTEMS AND TECHNIQUES

DIAGNOSIS ACCORDING TO THE SIX STAGES

This system of diagnosis was formulated by Dr. Zhang Zhong Jing in the early Han Dynasty. The application of the six stages of diagnosis provides the key link in treating febrile diseases which are due to an attack of Cold. The six stages are described as Tai Yang, Shao Yang, Yang Ming, Tai Yin, Shao Yin, and Jue Yin.

THE THREE YANG SYNDROMES

The signs and symptoms of these pathological changes result from attacks by exogenous factors, especially cold weather. The first three syndromes describe the pathological changes occurring in the six Yang organs and channels (Small Intestine, Bladder, Large Intestine, Stomach, Triple Burners and Gall Bladder), and are called the Three Yang Stages. In the Three Yang Stages, the pathogenic factors predominate, but the body's energy is still relatively strong. The major symptoms are signs of Heat, and the treatment is directed at eliminating the pathogenic factors. These are the external conditions which can progress from the superficial Tai Yang Stages to the deeper Shao Yang Stages.

1. The Tai Yang or Great Yang Stage affects Qi on the exterior surface of the body and all three Wei Qi levels. This energetic disturbance affects the Small Intestine and Bladder Channels and organs that govern the exterior of the body. Although they are the most superficial channels, they are very rich in Wei Qi.
   - Clinical Manifestations of an Attack of Cold include: Aversion to cold, stiff neck, headache, no sweating, fever, body aches, floating-tight pulse, and shortness of breath.

     The focus of the Qigong treatment is to first open the pores to eliminate pathogenic factors by purging and dispersing, followed by tonification of the Lungs.
   - Clinical Manifestations of an Attack of Wind include: Aversion to wind, stiff neck, sweating, body aches, floating pulse, and fever.

     The focus of the Qigong treatment is to first open the pores to eliminate pathogenic factors by purging and dispersing, then to relax the muscles for diaphoresis (profuse sweating) in order to regulate the Ying and Wei Qi, and finally to prescribe herbs (or refer out for herbal treatment).
2. The Shao Yang or Lesser Yang Stage affects the interior and exterior levels of the body equally. This energetic disturbance affects the Triple Burners and Gall Bladder organs and channels. The patient experiences an alteration of fever and chills with a fullness of the costal and hypochondriac regions, blurred vision, loss of appetite, irritability, and wiry pulse with a white-slippery tongue coating.

   The focus of the Qigong treatment is on dispersing Heat with purging techniques and promoting the production of Body Fluids using herbs.
3. The Yang Ming or Bright Yang Stage affects Qi at the interior level of the body. This energetic disturbance affects the Large Intestine and Stomach organs and channels. The pathogenic factors transform into Heat.
   - Clinical Manifestations of the Bright Yang Channel Stage include: Pure Interior Heat known as the Four Bigs (fever, thirst, sweating, and pulse). In addition the patient also experiences an aversion to heat and has a red tongue with a yellow coating.

     The focus of the Qigong treatment is on dispersing Heat with purging techniques and on promoting the production of Body Fluids through herbs.
   - Clinical Manifestations of the Bright Yang Or-

gan Stage include: Interior Heat and the Four Bigs with constipation, profuse sweating, high fever which worsens in the afternoon, fullness and pain in the abdomen (which becomes worse if you press it), and a red tongue with a dry, yellow or black coating.

The focus of the Qigong treatment is on eliminating pathogenic factors with purging and dispersing techniques, and relieving constipation.

THE THREE YIN SYNDROMES

The second three syndromes are those of the Three Yin Channels. They are based on the pathological changes of the Six Yin Organs and channels (Lungs and Spleen, Heart and Kidneys, Pericardium and Liver). These syndromes are the reflection of pathological changes within the Yin and Yang organs, channels, and collaterals. In the three Yin stages, the pathogenic factors are still present but diminishing. The body's Qi has become weakened, and there are Deficient signs of Cold. The treatment is focused on strengthening the body's Qi. These are internal conditions that progress from the Tai Yin stages deeper into the body until they reach the Jue Yin stage.

1. The Tai Yin or Great Yin Stage affects the Yin organs, as the penetration of pathogenic factors flow deep into the energetic layers. This energetic disturbance affects the Lung and Spleen organs and channels, resulting in a Deficiency and Cold syndrome. The clinical manifestations are: Vomiting and diarrhea, abdominal fullness, absence of thirst, and a slow, deep pulse with a pale tongue.

   The focus of the Qigong treatment is on heating and energizing the Middle Burner and dispersing the Cold using herbs. It is also important to tonify the patient's organ Qi.
2. The Shao Yin or Lesser Yin Stage affects the Heart and Kidney organs and channels. Clinical manifestations are as follows:
   - The transformation of Cold Deficiency to Kidney Yang Deficiency: Aversion to cold, chills, cold limbs, diarrhea, listlessness, lethargy, abundant-pale urine, deep-fine pulse, and pale tongue.

     The focus of the Qigong treatment is on tonifying the patient's organ Qi, preventing the Yang from collapsing and treating with herbs.
   - The transformation of Heat Deficiency to Kidney Yin Deficiency: insomnia, fever, irritability, dry throat and mouth, scanty-dark urine, fine-rapid pulse, and a red tongue without coating.

     The Qigong treatment should focus on tonifying the patient's organ Qi, nourishing the Yin, and dispersing Fire using herbs.
3. The Jue Yin or Terminal Yin Stage affects the Pericardium and Liver organs and channels. This is the final stage of pathogenic invasion before the life-force energy vanishes altogether.

   Clinical manifestations are as follows: cold limbs, diarrhea, vomiting, pain, feeling of heat and energy expanding in the chest, and feeling of hunger with no desire to eat.

   The focus of the Qigong treatment is on purging, tonifying and regulating the patient's organ Qi. Applying Cold and Hot herbal medicines simultaneously can be used to drive out the patient's pathogenic factors and aid in purgation. Herbal tonics can also be used to increase the patient's resistance to pathogenic diseases and aid in tonification (Figure 24.1).

DIAGNOSIS ACCORDING TO THE FOUR LEVELS

This system of diagnosis was formulated by the famous Chinese physician, Dr. Ye Tian Shi in the late 1600's. These syndromes are used to explain the etiology and pathogenesis of febrile diseases. The differentiation of syndromes pertaining to the Four Levels of Diagnosis is concerned with febrile diseases caused by externally contracted Heat. Because exogenous diseases are always developing and changing, by studying the transmission of pathological changes the Qigong doctor is able to deduce the prognosis. These four levels are identified by four types of energy, and are classified as follows: The Wei Qi Level, Qi Level, Ying Qi Level, and Blood (Xue) Level.

1. At the Wei Qi Level (Protective Energy), the



Figure 24.1. The Six Stages of Pathogenic Invasion are illustrated here. The invasion of external pathogenic factors follows a systematic progression through the body's Six Levels of Qi.

1. The Great Yang Stage (Tai Yang)

Affects the Small Intestine and Bladder Organs and channels. At this stage the pathogens are at the superficial level of the body's Wei Qi, caused by an attack of Wind and/or Cold Invasion. This stage is considered an External Cold Invasion at the Wei Qi level.

2. The Lessor Yang Stage (Shao Yang)

Affects the Triple Burners and Gall Bladder Organs and channels. At this stage the pathogens are half Exterior and half Interior, flowing in and out of the body, causing alternating chills and fever. This stage is also considered an Internal condition at the Qi level.

3. The Bright Yang Stage (Yang Ming)

Affects the Large Intestine and Stomach Organs and channels. At this stage the pathogens absorb deeper into the body's tissues, transforming into Heat affecting the internal organs and/or channels. This stage is considered an Internal condition at the Qi level.

- Bright Yang Organ Stage: Results in Interior Heat with constipation.
- Bright Yang Channel Stage: Results in pure Internal Heat with "Four Bigs" (fever, thirst, sweating, and pulse).

4. The Great Yin Stage (Tai Yin)

Affects the Lungs and Spleen Organs and channels. At this stage the penetration of pathogenic factors flow deep into the energetic layers affecting the Yin organs, invading the Middle Burner (affecting the Spleen) causing a Deficient condition. This stage is considered an Internal condition at the Ying Qi level.

5. The Lesser Yin Stage (Shao Yin)

Affects the Heart and Kidney Organs and channels. At this stage the pathogenic factors transforms either into Cold or Heat, causing further Deficient conditions. This stage is also considered an Internal condition at the Ying Qi level.

- Pathogens will transform into Cold due to a Deficiency of Kidney Yang.
- Pathogens will transform into Heat due to a Deficiency of Kidney Yin.

6. The Terminal Yin Stage (Jue Yin)

Affects the Pericardium and Liver Organs and channels. At this stage the pathogenic factors continue to deplete the body's life-force energy. This is the final stage of pathogenic invasion before death occurs. This stage is also considered an Internal condition at the Blood level.

pathogenic Heat invades the outer level of Wei Qi, causing the human body to manifest certain disorders which are clinically observed as fever, aversion to wind and cold, excessive or absence of sweating, sore throat, coughing, headache, red tongue with thin coating, and a floating and rapid pulse.

The Qigong treatment should focus on dispersing pathogenic factors and tonifying the exterior by utilizing pungent tastes and cooling herbs. Points are generally selected from the Lungs, Large Intestine, and Bladder Channels, as well as from the Governing Vessel.

2. At the Qi Level, the pathogenic Heat continues to progress deeper into the body, attacking and affecting the Qi system. At this stage, the body system is still strong, but the normal functions of the Yin and Yang organs are impaired. Because of the different functions of the Yin and Yang organs the manifestations differ. The three conditions associated with this stage of pathogenic invasion are as follows:

- Heat in the chest and diaphragm is the first stage and is not considered a severe syndrome. The symptoms manifest as fever, burning sensation in the epigastrium, thirst, and a yellow coated tongue.

  The Qigong treatment should focus on dispersing pathogenic Heat accumulated in the chest and diaphragm.
- Heat in the Stomach Channel is the second stage, and is considered a more severe Heat syndrome. These symptoms manifest as Heat, thirst, a dry tongue with yellow coating, and a slippery, rapid pulse.

  The Qigong treatment should focus on purging pathogenic Heat, and tonifying the body's Fluids.
- Heat in the Lesser Yang Channel is considered the final stage of Qi invasion. This syndrome is similar to the Lesser Yang Stage of the Three Yang Syndromes (according to the Six Stages), except that there is Dampness.

  The Qigong treatment should focus on purging pathogenic Heat from the Lesser Yang Channel, dispelling Dampness and dispersing Phlegm.

3. At the Ying Qi Level (Nutritive Energy), the pathogenic factors have penetrated deeper to the level of the Ying Qi and the organs, the Blood, blood vessels, and the Heart are therefore all affected. The symptoms in this stage are generally caused by the burning up the Yin. Clinical manifestations include: irritability, insomnia, mental restlessness, fever that worsens at night, dry mouth, absence of thirst, faint skin eruptions, a deep red tongue with little or no coating, and a fine-rapid pulse.

   Focus the Qigong treatment on purging pathogenic Heat from the Ying Qi level, using dispersing techniques. As an auxiliary method, bleeding may be performed by pricking the Heart and Pericardium Channels, as well as the Governing Vessel.
4. The Blood (Xue) Level, is the deepest and final level of pathogenic invasion. This stage contains the most serious manifestations that the disease can cause. Clinical manifestations include: high fever, skin that is hot to touch, Bloody stool, vomiting of Blood, Blood in urine, delirium, skin eruptions of purple or black color, a deep red tongue, a fine-rapid pulse, and in severe cases convulsions.

   The Qigong treatment should focus on purging pathogenic Heat from the Blood using bloodletting techniques (points are mainly selected from the Heart, Pericardium, Liver, Stomach, and Large Intestine Channels, along with the Governing Vessel), Cool the Blood, relieve convulsions, calm the mind, and reduce pathogenic factors with herbs.

DIAGNOSIS ACCORDING TO THE TRIPLE BURNERS

This system of diagnosis was developed by the famous Chinese physician, Dr. Wu Ju-Tong in the late 1700's. This system is concerned with febrile diseases caused by externally-contracted Heat, invading the body's Triple Burners. This Heat syndrome generally proceeds from the Upper Burner to the Middle and ends up at the Lower Burner. However, in cases of diseases due to Damp Heat, the pathogenic invasion of Heat begins at the Middle Burner in the Spleen.

1. The Upper Burner encompasses the body from the top of the head to the diaphragm. This area includes the Heart, Lungs, Pericardium, throat and head, and is responsible for respiratory and cardiac functions. The Upper Burner moves the body's Clean Qi, circulating and distributing nutrients and Qi throughout the body like a mist.

   Clinical manifestations of diseases in the Upper Burner correspond to those of a pathogenic invasion of the Lungs and Pericardium.
    a. When Wind Heat invades the Lungs, it is either manifested at the Wei Qi level or deeper in the Lungs themselves. The symptoms include: fever, sweating, coughing, stiffness and pain in the chest, wheezing, thirst, a red tongue with a yellow coat, and a rapid pulse.
    b. When pathogenic Heat invades the Pericardium, it is manifested at the Wei Qi level. These symptoms include: fever, coldness of the limbs, delirium, aphasia, burning sensation in the epigastrium, and a deep red tongue with spots.

   The Qigong treatment should focus on purging pathogenic Heat and dispersing Phlegm.
2. The Middle Burner encompasses the area from the diaphragm to the umbilicus. This area includes the Stomach, Spleen, pancreas, and Gall Bladder and is responsible for digestion, fermentation, and transformation of food and drink into nutrients for distribution. It moves the body's energy, circulating it like a swamp.

   Manifestations of diseases in the Middle Burner from pathogenic Heat are divided into two syndromes: Heat in the Bright Yang and Damp Heat in the Spleen.
    a. Heat in the Bright Yang include: symptoms of interior Heat and the Four Bigs (severe excess fever, sweating, thirst, and pulse) with constipation, profuse sweating, high fever which worsens in the afternoon, fullness and pain in the abdomen (which becomes worse when pressure is applied), and a red tongue with a dry, yellow or black coating.
    b. Damp Heat in the Spleen include: symptoms that are identical to the early stages of diseases caused by externally-contracted Heat.

   The clinical manifestations include: aversion to cold, fever that worsens in the afternoon, a heavy sensation in the head, body and limbs, fullness of the chest and epigastrium, nausea and vomiting, a white, sticky tongue, and floating or slippery pulse.

   The Qigong treatment should focus on Heating the Middle Burner, tonifying any Deficiency, purging Dampness, and prescribing herbs.
3. The Lower Burner encompasses the area from the umbilicus to the feet. This area includes the Liver, Kidneys, Bladder, intestines, external genitalia for men, and the uterus for women. The Lower Burner is responsible for filtering and eliminating waste products and for reproductive functions. It moves the body's Turbid Qi, circulating it like a drainage ditch.

   Manifestations of diseases in the Lower Burner are caused from pathogenic Heat attacking the Kidneys or Liver and are divided into two syndromes:
    a. Invasion of the Kidneys by pathogenic Heat dries up the Kidneys' Yin causing Heat symptoms due to a Yin Deficiency. Clinical manifestations include: lingering fever, hot hands and feet, dryness of the mouth, deafness, lassitude, a red-peeled tongue, and a rapid, floating or empty pulse.

   Focus the Qigong treatment on tonifying Yin, and purging the Heat.
    b. Invasion of the Liver by Heat occurs after the Kidney Yin has been exhausted. A condition known as Liver Wind is created. Clinical manifestations include: low-grade fever, cold limbs, dry and cracked lips, convulsions and trembling, a dry, reddish-purple tongue, and a rapid-deep pulse.

   The Qigong treatment should focus on tonifying Yin, and purging the Heat and Wind.

CHAPTER 25
CLINICAL EXAMINATION AND DIAGNOSIS

SENSORY, INTUITIVE AND PERCEPTUAL DIAGNOSIS

Clinical diagnosis can be categorized into two primary methods of energetic examination and treatment: Sensory Diagnosis and Intuitive and Perceptual Diagnosis. The clinical methods of Sensory Diagnosis are quite prevalent throughout China, especially within the acupuncture, massage, and herbal clinics. The methods of Intuitive or Perceptual Diagnosis, however, have been kept secret for many years, and are primarily found only within the Medical Qigong clinics. The latter methods (Intuitive or Perceptual Diagnosis) will be explained later in this chapter.

The root of any disease can be drawn from its complex symptoms and signs, by using the two main methods of Sensory and Intuitive and Perceptual Diagnostic principles. These two main methods of diagnosis serve as guidelines for the Medical Qigong doctor in clinical evaluation. Once the cause and extent of the disease is known, a treatment plan can be developed. There are four main types of Qigong treatment, which are chosen according to the treatment goals:

- a routine treatment (basic or nonspecialized),
- a specialized treatment (designed for the specific patient and his or her condition),
- a treatment aimed at etiology, or
- a treatment focused on alleviating the symptoms and signs.

It is therefore important to determine and assess the cause (root) and the manifestations (branches) of the patient's disease.

SENSORY DIAGNOSIS

Before treatment begins, the Qigong doctor performs a clinical intake, examining and evaluating the patient's condition, using various methods of sensory diagnosis. This clinical format involves taking a history of the patient's complaints. Next the doctor inquires about the patient's medical history. The doctor then conducts an examination for diagnosis, and devises a treatment principle on which the treatment plan is based, before implementing the treatment.

CLINICAL INTAKE, EXAMINATION AND EVALUATION

It is important that the doctor clearly identify the patient's problem before any treatment may be given. Never treat a patient without first making a diagnosis. The diagnosis is developed from the doctor's sensory examination and is evaluated according to symptom observation.

Both the root (the source and cause of the disease) and its branches (the symptoms or manifestations of the disease) should be examined carefully before treating the patient. In the case of an emergency, the doctor may choose to treat the urgent symptom first before treating its source.

The diagnosis and treatment of each patient traditionally begins by observing the patient as a whole, followed by an evaluation of the patient's individual constitution. Next, the doctor observes the symptoms and syndromes of the individual's organs. From these observations the cause of the disease is determined and treatment is begun. The treatment usually focuses on addressing the cause of the disease, to return the organ or organ system back into harmony with the rest of the patient's body. This affects changes within the patient's constitution and returns him or her back to a normal state of health.

Sensory examination for diagnosis is divided into five primary methods: diagnosis by visual observation, diagnosis by listening, diagnosis by smelling, diagnosis by palpation, and diagnosis

Activate the Three Fires

The Abdominal, the Kidney and the Heart Fires.

Tan Tien Fire: Bring the fingertips to the navel. Feel the abdominal fire warming and opening the Lower Tan Tien. The abdominal fire elicits deep awareness within the body. This awareness has the power to expand and connect to the entire Universe.

Kidney Fire: Bring the palms to the kidneys, the fingertips to the door of life. Feel the warmth in the kidneys, like a fire under the sea.

Heart Fire: Bring the hands to the heart, palms facing the chest. Visualize a glowing ball of light in the heart. Feel the warm radiant energy of compassion shimmering through the chest. Make the heart soft. Remember the Yin within the Yang.



Fig. 6.30 *Activate the Three Fires.*

Create the Front Pakua just behind the navel. Control the formation of the front pakua with assistance from the eyes, ears, nose and mouth. As you balance the energy, let the pakua glow with light.

by questioning the patient. By looking, listening, smelling, touching, and asking the patient specific questions, a Qigong doctor is able to diagnose the patient's syndrome (this includes the etiology of the disease).

DIAGNOSIS BY VISUAL OBSERVATION

1. Observe the patient's Shen, overall appearance, spirit, emotional nature, energy field, and composure. Look at the Shen of the patient's face; a healthy patient should have a brightness or vibrant shininess to his or her countenance. The Shen of the face should be checked against the state of the patient's eyes.
2. Observe the patient's eyes, especially the spirit in their eyes -- the glitter or dullness, and the expression of a controlled or uncontrolled emotional state. The eyes manifest the Essence of all the organs, and are the messengers of the Heart. There are two things to look at in the eyes -- glitter and focus.
    a. Are the patient's eyes bright and do they glitter? The less the glitter, the more long-standing the emotional and mental problems. It is said that there are three emotions that make the eyes lack glitter: sadness, grief, and shock. If the patient's eyes are dull, it looks as if he or she is seeing through a mist or film.
    b. Are the eyes focused, is the attention sustained and penetrating or uncontrolled? Uncontrolled attention is actually worse then having no glitter. If the patient has unfocused eyes it means that there is an obstruction of the patient's Shen and mind, generally due to guilt, preoccupation, or anxiety. It is said that Excess joy makes the "eyes uncontrolled."
3. Observe the color of the patient's face, complexion, eyes, ears, nose, mouth, tongue, skin zones, and ask about the discharges (mucus, vaginal, urine, and stool). Anger manifests as a greenish tinge on the cheeks or forehead (if it is affecting the Stomach); worry manifests as a grayish color, pensiveness as a sallow complexion, fear as a white complexion (unless combined with Kidney Yin which turns the cheeks red). Shock creates a bluish tinge on the forehead. A change in the complexion often indicates a deeper and longer-standing psycho-emotional problem. Also, if the eyes show no Shen but the face does, it indicates a recent problem.
4. Observe the patient's body and any outstanding structural features. Are they thin, emaciated, obese, or paralyzed? Are there deviations or obstructions in or on the body, face, head, mouth, teeth-gums, eyes, nose, and ears? Are there blemishes on the skin? Observe the appearance of the nails, hair and so on.
5. Observe the way the patient moves. Do they shake and tremor? Are they rigid or loose? Notice if the movements are fast or slow, and so on. When you shake hands upon meeting for the first time, are his or her hands clammy or dry; is his or her grip strong or weak?
6. Observe the patient's tongue. Is it cracked, serrated, fat, thin, or thick? If you observe a central crack, the deeper it is, the more long-standing the emotional problem. A red tipped tongue can also indicate a Shen disturbance.
7. Observe the patient's channels and points. Are there darkened red blotches, blemishes, swelling, sweat, etc.?

DIAGNOSIS BY LISTENING

1. Listen to the patient's speech for slurring or clarity.
2. Listen to the patient's tone. Is it high, low, loud, or quiet?
3. Listen to the patient's tempo. Is it fast or slow?
4. Listen to the patient's words. Do they make sense? Are his or her thoughts well ordered, or does the patient change subjects abruptly and frequently (if so, the patient may be suffering from a severe mental disorder).
5. Listen to the patient's respiration. Is it loud, strong, weak, or wheezing?
6. Listen to the patient's cough. Is it loud, dry, or wet?
7. Listen to the patient's Stomach and Intestines. Are they gurgling or quiet?

DIAGNOSIS BY SMELLING

1. Does the patient smell strong, weak, or odorless? Does the patient smell of medications, or alcohol?
   - For Liver problems, the patient's body or breath will smell like a goat.
   - For Heart problems, the patient's body or breath will smell like something has been burnt.
   - For Spleen problems, the patient's body or breath will smell fragrant or sweet.
   - For Lung problems, the patient's body or breath will smell like fish or a tide pool.
   - For Kidney problems, the patient's body or breath will smell rotten.

DIAGNOSIS BY PALPATION

1. How does the patient's pulse feel? Is it strong or weak? The pulse shows more about the patient's Qi than the state of his or her Shen. Because the pulse reflects the short-term state of the patient's Qi, it should always be integrated with tongue and complexion diagnosis.
2. How do the patient's channels and points feel? Are there tender areas, movable nodules (Qi stagnation), or fixed nodules (Blood stagnation) along the patient's channels?
3. How does the patient's abdomen feel?

DIAGNOSIS BY QUESTIONING

1. Ask about the history of the patient's main complaint (illness, disorder, or injury).
   - When did it begin?
   - What other signs or symptoms accompany it?
   - Ask about the course of the illness, is it improving or getting worse?
   - What makes it better or worse (i.e., pressure, warmth, cold, and so on)?
   - What other treatments has he or she tried?
2. Ask about the patient's general medical history.
   - Has the patient had any surgeries?
   - Has the patient experienced any past or recent physical or emotional traumas?
   - Ask if the patient is on any medication(s).
   - Ask about self-medication with alcohol or drugs.
   - Ask about his or her current coffee, soft drink and sugar intake.
   - Ask about the patient's extremities, do they feel hot or cold?
   - Ask about his or her sweat.
   - Ask about his or her thirst.
   - Ask about his or her appetite and diet (how often does the patient eat, and how regular are the meals?).
   - Ask about his or her digestion (gas, belching, etc.).
   - Ask about his or her stool (loose, well formed, hot, smelly, cold, fishy, color, etc.).
   - Ask about his or her urine (frequency, urgency, and color).
   - Ask about his or her sleeping patterns (difficulty falling asleep, remaining asleep, or recurring nightmares).
   - Ask for an energetic self-evaluation on a scale of 1 to 10.
   - Ask about current emotional and mental problems or concerns.
   - Ask about his or her current physical exercise program.

EXAMINATION FOR DIAGNOSIS

There are certain general principles used by all doctors of Traditional Chinese Medicine to become proficient in diagnostic skills. In Medical Qigong therapy, becoming skilled and accurate in clinical diagnosis requires the Qigong doctor to become proficient in combining perceptual and mental skills with spiritual understandings and insights. The following is a thorough and systematic approach for arriving at an accurate diagnosis.

1. Record all information observed and gathered as meticulously and impartially as possible. When first encountering a patient, be open minded, but note all first impressions.
2. Organize all the information according to the Eight Energetic Principles or Five Elemental Theories.
   - When diagnosing according to the Eight Energetic Principles, the doctor should first determine whether the condition is Yin or Yang (chronic or acute), then classify the patient's

symptoms according to the condition's general location (External or Internal), followed by the disease's symptomatic appearance (Hot or Cold), and finally, the physio-energetic nature of the disease (Excess or Deficient condition).

Next, the Qigong doctor focuses on the Yin or Yang aspects of the patient's body, in terms of the physiological properties of the patient's disease, noting which is more affected, the Qi and Blood, Yin and Yang organs, etc.

The Qigong doctor then determines the precise depth and severity of the patient's disease, observing whether it is the patient's surface channels which are being affected, or the patient's internal organs. If it is determined that the condition is an internal problem, the Qigong doctor then differentiates the energetic level of penetration into the patient's body. This level of pathogenic penetration is diagnosed according to either the Six Stages, Four Levels, or the Triple Burners method of diagnosis.

- If the doctor is diagnosing according to the Five Elemental Theory, he or she should first determine the condition of the patient's pulse to assess which organ or organs are Excess or Deficient. The doctor must then decide whether the imbalance is attributed to either an individual internal organ or a combination of internal organs. If the patient's pulse does not match with the information gathered through the examination, the doctor must reconsider whether the patient's disorder will in fact conform to a Five Elemental pattern.

3. Evaluate all information: The doctor should evaluate the gathered information according to the patient's signs and symptoms, determining what is of primary and secondary importance. It is in this stage of evaluation that the Qigong doctor determines the "root and branch" of the patient's disease. If the disease is External in origin, the doctor determines what pathogenic factors are involved. If the disease is Internal in origin, the doctor determines whether the cause is emotional, hereditary, dietary, or an energetic charge remaining from a previous external disruption.

Finally, the doctor should determine whether the cause of the disease is still active within the patient's life. If it still is, the doctor must take this factor into consideration before treating the patient and prescribing homework.

DEVISING A TREATMENT PRINCIPLE

In devising a treatment principle, the Qigong doctor should always include the Condition of the disease, Location of the disease, and Possible Cause of the disease.

1. The Condition of the Disease refers to the categorization of the disease, and may be diagnosed according to a combination of the Eight Energetic Principle's criteria. The patient's condition could, for example, be considered Excess or Deficient, Hot or Cold, Internal or External, or a combination thereof, such as: Excess Heat, Internal Heat, Deficient Heat, etc.
2. The Location of the Disease refers to the physio-energetic level of the patient's body that the disease is affecting (whether it is in the Upper, Middle or Lower Burner, or affecting certain Yin or Yang organs, channels, or muscles, etc.).
3. The Possible Cause of the Disease is either a result from a congenital or acquired illness. If congenital, consider the patient's DNA patterns, and all hereditary and ancestral traits. If acquired, consider environmental exposure to toxic poisons, diet, trauma (physical or emotional), electromagnetic fields, etc.

TREATMENT STRATEGY

Once the working diagnosis and treatment principle has been established, it is time to determine a treatment strategy. A treatment strategy consist in applying the treatment principle. It is the foundation from which the Qigong doctor chooses the approach in treating the patient's disease (Figure 25.1). The doctor will choose to treat the internal organs, channels, collaterals, points, and tissue areas which are the primary cause of the patient's disease. These areas are specifically chosen in order to facilitate a rapid affect on the patient's disease, to purge, tonify, or regulate the tissue area.

TREATMENT

The treatment usually focuses on the specific cause of the disease and how it affects the patient's internal organs. The primary goal is to relieve the patient's symptoms, strengthen the constitution and return the patient to a state of wholeness. This process may involve restructuring the patient's belief structure, to emotionally release old traumas.

AFTER THE TREATMENT

After treating the patient's condition, the Qigong doctor explains to the patient in clear, comprehensive terminology, what the doctor has discovered, and his or her approach in rectifying the condition. The more the patient understands the


1. History of the Patient's Complaint
2. Patient's Medical History
3. Examination for Diagnosis
4. Treatment Principle
5. Treatment Plan
6. Treatment

Figure 25.1. Examination, Diagnosis, and Treatment: The Qigong doctor begins diagnosing the patient by taking a "history of the patient's complaint." Next the doctor inquires about the "patient's medical history." Then, the doctor begins the "examination for diagnosis," observing the patient's constitution, symptoms and signs and determines the syndrome(s), health and state of the patient's internal organs, and the cause of the energetic dysfunction. Next, all the acquired knowledge is assessed in accordance with the different diagnostic templates of the Eight Parameters, Five Elemental Theory, Qi, Blood and Body Fluid Dysfunctions, etc. and the doctor "devises a treatment principle." Before treating the disease the doctor "develops a treatment plan." The treatment focuses on the specific cause of the disease and how it affects the patient's internal organs. The primary goal is to relieve the patient's symptoms, strengthen the constitution and return the patient to a state of wholeness. This entire process is initiated to assist the Qigong doctor in prescribing the correct treatment.

doctor's diagnosis and approach in addressing the treatment, homework prescriptions, and suggestions for life-style modifications, the greater the likelihood of a successful healing.

After the initial treatment, it is important for the Qigong doctor to establish a treatment schedule. This establishes a realistic goal and time frame for the therapy. With each treatment, the doctor monitors the patient's progress, and may choose to modify the treatment approach in accord with the patient's changing condition.

As the patient's symptoms improve, the doctor lengthens the time between treatments. This continues until the symptoms are completely relieved, and the doctor is satisfied that the disease will not return.

ALTERNATIVE TREATMENT STRATEGIES

As the human body is in a constant state of change, the doctor's diagnosis and treatment approach will sometimes have to be altered. The doctor may also choose to modify each treatment according to the patient's changing symptoms or disease development. When choosing alternative treatment strategies, it is important that the doctor choose adjunctive therapies that enhance the primary goal of purging, tonifying, and regulating the patient's condition.

INTUITIVE AND PERCEPTUAL DIAGNOSIS

THE METAPHYSICAL DIMENSIONS OF MEDICAL QIGONG HEALING

The dictionary describes "metaphysical" as "the study of psychic phenomena beyond the limits of ordinary or orthodox psychology." There are other dimensions of reality that are very tangible, and access to them is only limited by fear and ignorance. Since theories on the nature of the mind and spirit cannot be easily verified or disproved by intellectual analysis or scientific experiment, sometimes certain kinds of knowledge are disbelieved, ridiculed, and dismissed. The advanced energy theories that are presented in this textbook are based upon the five thousand years of cultivation and experience of Chinese medical healing. The energetic form of Qi is neither good nor evil, it is simply another aspect of matter. The ancient Chinese Qigong masters refined the ability to analyze and diagnose these different forms of energy into an effective healing modality.

The existence of energy and its multidimensional patterns is embraced and accepted by many other cultures and societies, with the exception of Western conventional thinking, which is unfamiliar with this unorthodox approach to healing.

These energetic realms, which form the reality of the Medical Qigong doctor's clinical healings, are actually normal perceptional skills that the doctors have developed and trained within themselves. These doctors have simply rediscovered and trained their sensitivity to energies that they were open to during childhood. These energies encompass more then just the physical world. These perceptive skills and abilities of Shen are actually our natural, energetic "birthright," and have been with us since birth. Shen Gong skills, and all psychic powers, lie within the Eternal Soul of an individual, although in most people these skills are undeveloped and largely unused. Often we fear the most the things we understand the least. It has also been my observation that individuals are taught to ignore these skills because of one or more of the following reasons:

1. They have become frightened of them, because as children they were told that these abilities do not exist;
2. They were told that such abilities were evil, or of the 'devil';
3. Unable to understand them, they do not know how to integrate them into their personal lives;
4. They may fear the emotional and spiritual responsibility of knowing the truth about themselves and others; or
5. The known is familiar and therefore more comfortable then the unknown and new.

Sometimes even facing our own human potential alarms us so greatly (fear bordering on terror) that we are willing to deny empirical evidence that these paranormal skills and abilities are real.

We live, therefore, with a paradox. These paranormal abilities seem to be part of our nature, yet they can disturb us so greatly that we often violently reject them. Medical Qigong doctors are healers who have learned to accept these paranormal abilities and direct their energy, spirit and psychic skills towards the focus of alleviating pain and suffering. They are "wounded healers" who have learned to face their fears, and have the courage to walk through and overcome them.

THE AWAKENING

For the Qigong doctor to understand spiritual insights, three phases of energetic transformation must first be experienced. These three phases are collectively known as "the awakening" and are described as follows.

1. The awakening describes the beginning phase or "opening" of the Qigong doctors' Mind and Spirit to their energetic potential. This acceptance becomes rooted within the doctors' intention, emotion, and thought, and sets into motion the correct vibrational field for accessing their higher consciousness.
2. Entering the inner sanctuary describes the phase wherein Qigong doctors begin to receive greater clarity of mind and an elevated consciousness. The doctors receive information on a multidimensional level and are now able to access, as well as better understand their inner core being. This sets into motion the Qigong doctors' understanding of their interconnectedness to everything in the universe. At this point, the doctors must accept responsibility for their actions and non-actions.
3. Accessing the Wuji through the Creative Subconscious Mind describes the Qigong doctors' ability to access and reprogram their Mind and core vibration. This sets into motion the doctors' personal contact with their higher-self, or Eternal Soul.

LEARNING INTUITIVE AND PERCEPTUAL DIAGNOSIS

Before beginning the primary methods of Intuitive and Perceptual Energy Diagnosis, it is important to understand the initial training needed to access and train these skills. Without an understanding of these subtle energies, the risk of misdiagnosis of the microprojections of life-force energy is high. The subconscious mind communicates within ourselves and the outside world through the Three Dantians, by way of three distinct mechanisms:

- Physical or kinetic communication is established through the Lower Dantian.
- Emotional or empathic communication is established through the Middle Dantian.
- Spiritual or intuitive communication is established through the Upper Dantian.

These three modalities of energetic communication must be finely honed into effective, receptive listening tools.

Memories, thoughts, emotions, and knowledge are stored in the patient's tissues throughout the body at the pre-atomic and pre-cellular levels. They are arranged and structured similar to the way sounds and images are recorded on the magnetic molecules of a video cassette tape. Not only are emotions and sounds stored, but tastes, smells, and touch can be invoked simultaneously in vivid detail as the cells are stimulated. The patient feels that they are actually reliving the event from the past exactly as if it were occurring now.

The Qigong doctor must be ready to recognize, uncover, and be able to feel his or her patient's pain when interceding as an empath. Sometimes the doctor will not only stumble upon pockets of unresolved pain, but also suppressed memories hidden deep within the patient's tissues. When this occurs, the doctor diagnoses the patient's toxic emotional symptoms through his or her own body and spirit. To perform this type of diagnostic technique successfully, doctors must be secure in their established emotional boundaries. Otherwise they might project their own feelings onto the patient, or absorb the patient's pathogenic energy into their own body, where it may become trapped.

The goal is to absorb and receive the patient's symptoms briefly for diagnosis, and then release them by exhaling out the mouth (away from the patient). This expels the Toxic Qi into the ground, and allows the patient's feelings to pass through the doctor's body without harm.

The state of consciousness in which the doctor listens and feels the patient is more important than the technique or modality used. This is why there are so many diagnostic tools available to assist doctors in their evaluation. The patient's body maintains the energetic pattern of trauma until it is released and dispersed. The amount of energy required to neutralize this traumatic charge and return the tissues back to their normal state is in direct proportion to the intensity of the original trauma.

RECEIVING AND INTERPRETING THE PATIENT'S FIELDS OF BIO-INFORMATION

The human body emits several "bio-fields" of energy, varying in density and frequency and resonating within a holographic field. Like radio waves and other modern technological wave transmissions, these fields are encoded with information. The key to what we absorb and radiate lies in the energetic qualities of the rate or frequency of vibration, amplitude, and wave length of these bio-fields.

The physical world as we know it is made up of energetic fields. These energetic fields hold our universe together (Figure 25.2). Matter is simply the temporary expression of these energetic fields as they interact. The human body consists of Shen, Qi, and Jing actively resonating within the cells and tissues. Qi, as energy, is considered both substantial and insubstantial. Qi creates matter and acts as a medium between matter and spirit; it carries their mutual interactions in the form of waves. Because matter manifests as a distinctive type of consciousness, it operates at discreet levels of awareness, differing only in its complexity of structure and degree of freedom. Matter also manifests itself at every level of organization, from fundamental particles in physics, to biological organisms within the human body. The cells are governed by these bio-fields which determine their growth.

It is the conscious aspect of energy that dictates how, where and in what form energy is manifested within the body. This energetic consciousness releases bio-information which transmits encoded information about the patient both internally and externally. Form, force, and medium are three aspects of energy held in dynamic patterns by consciousness. The bio-information released from the patient's consciousness is read and diagnosed by the Qigong doctor before treatment begins.



Figure 25.2. The Energetic Fields

The body's bio-information resonation Xin Xi or the "message" as it is called in China, is not limited by space or time. This Message refers to the energy fields that emanate to and from the Wuji or Void (infinite space embodied in between matter and energy).

The Wuji is the state of no boundaries, of pure openness, of complete oneness. Its essence is emptiness (as depicted by the empty circle), which relates to the awareness aspect of our Yuan Shen. When it begins to manifest within the relative universe of Qi, Yin, and Yang (referred to as Taiji), its nature appears as clear light which dispels darkness. When it manifests as a pure and tangible physical form, it appears as an enlightened being (saint or immortal) or as the "divinity" inherent within each one of us.

All of these levels exist within each individual, on both a pure level and pathological level. These levels can be detected and interpreted by the trained Qigong doctor as bio-information resona-


The Body's Chemical and Electrical Messages Expressed through the Five Levels of Bio-information
1. Jing (form or tangible matter)
2. Qi (intangible energy)
3. Shen (spiritual energy)
4. Wuji (infinite space of the Void)
5. Dao (Divine Energy)

Figure 25.3. The Five Levels of Bio-information

nce. Bio-information resonance is subdivided into five levels of expression:

1. Jing (form or tangible matter) contains the least amount of encoded information which is emitted at the lowest frequency.
2. Qi (intangible energy) contains more encoded information which is emitted at a higher frequency than Jing.
3. Shen (spiritual energy) emits an even higher frequency containing still more encoded information than Qi.
4. Wuji (the infinite space of the Void) contains even more encoded information than Shen which is emitted at a still higher frequency.
5. Dao (Divine Energy) emits the highest, most complete encoded information or Message and is the most powerful of all the emissions.

Medical Qigong views congenital disease as a form of distorted bio-informational vibration. The body's cellular systems internally regulate themselves via communication through these coded Messages. Messages are sent and received both on the energetic level (Shen, Qi, and Jing) and on the biochemical-electrical level. These two different levels interact continuously. Distortions on the energetic level interfere with the necessary transformations of Jing into Qi, Qi into Shen, and vice versa. Failures in energetic transformations also affect and distort chemical and electrical Messages between the different types of cells in the body (blood cells, tissue cells, nerve cells, and so on).

The maturity of the physical body depends on the transference of these Messages as the source of its evolution. Each time the egg cell divides (morula, embryonic, and fetal stages) the Message is transcribed into the newly-generated cells. Some encoded Messages are transformed but, due to the adverse evolutionary conditions or pathogenic factors, some become latent. Germ cell Messages, however, are not restricted by these evolutionary conditions since they multiply, evolve, and transform at an accelerated pace.

Information of the body's disharmonies is received as a distorted, biological resonation, which indicates the location and severity of the patient's condition. All diagnostic scanning techniques utilize this type of perception. The body's cellular systems internally regulate themselves via communication through coded bio-informational signals. This biological information exists in energetic, electrical, and chemical forms which are constantly being transformed from one form into another (Figure 25.3). The function of Medical Qigong therapy is to provide the correct bio-informational instructions (or Message) to the patient's body in the form of Qi emission (or coded energetic bio-informational signals) to initiate healing. By receiving Messages from the patient, the Qigong doctor can project energy while receiving and diagnosing the patient's energetic patterns.

ACCESSING THE KNOWLEDGE STORED WITHIN THE WUJI

When the Qigong doctors emit healing energy to the patient, they are sending healing Messages encoded within the Qi. When these Messages are received by the patient's cells the healing process is initiated. Qigong doctors access the knowledge needed to treat patients, by remaining receptive to the Messages stored within the patient's Jing, Qi, Shen, and surrounding energetic space (Wuji or Void).

Within the energy of the Wuji is the knowledge stored throughout time. In Medical Qigong practices, accessing the knowledge of the Wuji is the Chinese equivalent of the Sanskrit concept of accessing the Akashic Records. "Akasha" is a Sanskrit term used to describe the all-pervasive space of the universe. There are two kinds of Void: the first type of Void is internal, limited by the material plane (or matter) and can be associated with the enveloping of the internal human form. Matter can be described as consisting of more space then actual physical matter and, therefore, is considered infinite in its internal division of energetic properties. Within this Void forms the foundation for the matter or the body's personality by way of physical forms, sensations, perceptions, mental formations, and consciousness.

The second type of Void is external, unlimited, beyond all description, unbound by the material, yet contains all things material. It is the vehicle for all life, resonating through sound and light, permeating everything in the universe. In the practice of Medical Qigong the Wuji is one of three universal principles, along with Qi and Shen, which form a trinity of sources of intuitive and psychic power. These three universal principles also manifest the Eternal Soul, allowing divine thought to infuse matter.

The knowledge of the Wuji records the vibrational resonance of every action (all thought and emotion), as well as light and sound. These energetic impressions are stored within the astral plane. These records exist as impressions in the astral / spiritual dimension, providing a sort of accessible filing system for those who wish to receive information about past history or past lives, or even for the examination of their own spiritual progress. Admittance to this sea of knowledge and wisdom can be triggered in the hypothalamic limbic system of the brain, and is accessible through the energetic stimulation of the third ventricle of the Qigong doctor's brain.

The body is composed of literally billions of energetic molecules. Each molecule is a hologram of ancestral particles, knowledge, and experiences existing throughout time, spanning our entire history as we know it. These molecules gather together to form and create matter. They function for specific purposes of life transitions and energetic interaction, and then dissolve, and transform back into Qi and Shen. Each molecule stores its energetic experiences, to be later accessed through spiritual intention.

As the molecules gather to form a fetus, energy as well as ancestral history is stored within the tissues and cells of the child via the environmental, universal, mother and father's energetic fields.

Once the Qigong doctor has fused with his or her patient, he or she will be able to access specific information about the patient through the internal connection to the energetic impressions of the patient's Void. This allows the doctor to study and learn about the patient's past history of disease formations, as well as the information contained within the molecular structures of the patient's tissues.

UNDERSTANDING PAST-LIFE REGRESSION

Although seldom talked about, and much less understood, the clinical significance about past-life regression is quite important. Psychiatrists Sigmund Freud and Carl G. Jung both believed that the patients' worst fears, pain, and traumas are buried deep within their unconscious mind. Sometimes the patients' emotional traumas are so deeply entrenched that they can only be expressed through the energetic presence of a different time-space reality. One metaphor used by patients to describe this other form of reality is through a "past-life trauma."

During Medical Qigong treatments, patients will sometimes describe traumas or situations that do not relate to present life experiences. These experiences might be explained through past life theories. There are six major theories used to explain past-life recall (Figure 25.4). These theories are described as follows.


Past-Life Regression
1. Projections of the wounded ego
2. Ancestral traits, inherited skills, and memories stored within the molecular structures, cells, and energetic prenatal Jing
3. External emotional histories from other people that have been absorbed into the subconscious mind
4. The spirit of a past individual's consciousness that has been absorbed into the body of the fetus upon conception
5. The spiritually recycled and refined Eternal Soul
6. A combination of some or all of the above theories

Figure 25.4. The Six Major Theories of Past Life Regression

1. Some Qigong doctors contend that these past-life memories are the projections of the patient's wounded ego, used by the subconscious mind to assist the patient in dealing indirectly and symbolically with life's present painful experiences. These are painful memories that are consciously avoided by the patient, but are necessary for healing to take place.
2. Other doctors believe that these past-life phenomena are the ancestral traits, inherited skills, and memories stored within the molecular structures, cells, and energetic Prenatal Jing of the patient, that periodically surface from time to time and generation to generation.
3. Some doctors believe that apparent memories of past-life regressions, as well as of past-life traumas, are external emotional histories from other people that have been absorbed into the patient's subconscious mind. The patient responds like an energetic empath to sensations of telepathy, registered by the patient's hypothalamic limbic system. These external memories are triggered when the patient accesses the knowledge of the Wuji.
4. Other doctors believe that the spirit of a past individual's consciousness can be absorbed into the body of the fetus upon conception. This means that wherever a child is conceived, the environmental energy, as well as any native hovering spiritual entity, can be implanted into the forming energetic field of the fetus.
5. Other doctors believe that one's Eternal Soul is constantly being recycled and refined through generation after generation, constantly being reborn in order to evolve into a higher plane of consciousness.
6. Still other doctors believe that past-life memories can be a combination of some or all of the above theories.

Some patients feel that they experience spontaneous past-life recall through the treatment of Medical Qigong therapy. While receiving treatments or performing Medical Qigong prescriptions these patients may experience intuitive flashes or visions. Whether the patients' memories actually are of their own historical past lives, or are reconstructions from subconscious material, is a matter of controversy. The primary objective is for the doctor to accept the patients' reality, supporting them in this belief system to facilitate their healing process.

Chant the Eight Forces by sounding all the trigrams. Visualize the trigrams forming the front pakua. Chant the proper Yin and Yang combinations with each trigram.

Form the Back Pakua: Let it reflect off the front pakua like a mirror. In a similar manner form the **Left** and **Right Side Pakuas**. Feel the energy starting to spiral and blend into the center of the abdomen.

Form the Facial Pakua: The facial pakua is the reverse direction of the abdominal pakua because we are looking at the pakua in front of the face. Feel the energy of the senses and the face gathered and collected. If you have time, chant the eight trigrams of the facial pakua.

Form the Universal Pakua: Feel the immensity of this pakua surrounding your entire body in every direction. Again if time permits, chant the eight directions, forming the pakua.

Be aware of the heart and all the good virtue energy and fuse them together into compassion fire in the heart.

Be aware of the orgasm energy and multiply then to the organs and finally combine them into the heart and becoming one compassion fire of unconditional love.

Form the Collection Points in the Physical Body: Feel the red light in the heart collection point, the blue light in the kidney collection point, the green light in the liver collection point, the white light in the lungs collection point, and the yellow light in the spleen collection point.

Remove Negative Energies from the Organs:

Use the senses to help locate the negative energies in the organs. Look deep inside; smell deep inside; taste deep inside. Locate anything you find that you do not like.

Form the organs' collection points. Spiral the negative energies into the collection points spiraling them into the front pakua where they will blend and transform.

As you spiral the energies from all four Pakuas into the cauldron, you are concentrating them in the cauldron of the body. The cauldron, as the center point of the human being, is the center that contains the essence of all sense, organ and gland energy. The energy directed to the cauldron is transformed and stored for later use in the development of the soul and spirit bodies.

It is the doctor's responsibility to respect the patient's reality and not impose his or her own interpretations on everything the patient says. By accessing the knowledge of the Wuji, the doctor can assist the patient to connect with and benefit from these past life recollections or "reconstructions" to facilitate the healing process. Ultimately it matters not if the memories are reconstructions of subconscious material, true past life events, or even telepathic experiences. What is important, however, is that these memories are processed, learned from, and integrated to promote a better balance within the patient.

PAST-LIFE HEALING THERAPY

Clinically, past-life regression therapy has been effective in treating such problems as chronic fears and phobias, detrimental habits and cravings, suppressed hostility and guilt, depression, the fear of death, sexual dysfunctions, chronic pains and headaches, as well as many physical disorders. It is also used for understanding relationship problems, since the theory maintains that we often meet the same souls in different lives (and bodies) until the problems are worked out.

The Qigong doctor is not qualified to perform past-life regression therapy. This requires a specialist or at least supervision by an expert. The Qigong doctor can, however, facilitate healing by accepting the patient's experience and validating it to prepare the way for the healing process. In Medical Qigong therapy, the doctor accepts the patient's belief that the causes of his or her present physical or psychological problems can be traced to past-life traumas or death experiences. The improvement attained through past-life memories is said to be achieved through the release of the energetic charge that is trapped in the patient's body from a former life. This energetic charge keeps the patient's emotions prisoner, chained to the old feelings that are associated with the painful past-life experience. It is important for the Qigong doctor to realize that the same therapeutic benefits as the retrieval of current-life real memories can be achieved by allowing the patient to relate any images, impressions and so on, that may or may not stem from his or her present life experiences. The foundational base of the emotional trauma will often be rooted in feelings associated with rejection, betrayal, and abandonment. The psychological and physiological reactions to the patient's past-life memories, whether they be real or contrived, will have a profound affect on the patient's healing.

LEARNING MEDICAL QIGONG TECHNIQUES

According to Qigong Master Zheng Zhan Ding from Beijing, China, when learning Medical Qigong techniques, the doctors experience what is known as the Three-Part Wisdoms.

1. The Upper Dantian Wisdom is achieved through divine calling. When the full potential of the Upper Dantian is tapped, the doctor suddenly finds him or herself able to utilize skills and techniques that were previously completely beyond his or her ability. This is a major energetic breakthrough for the doctor, enabling him or her to perform supernatural feats that he or she immediately recognizes and accepts as part of a personal spiritual calling.
2. The Middle Dantian Wisdom is achieved through inspirational observation. Upon seeing energetic techniques performed, the doctor immediately establishes an emotional belief that he or she possesses that same energetic ability. This is a kind of "if they can do it, I can do it" observation and belief structure.
3. The Lower Dantian Wisdom is achieved through practice. This is a type of "practice makes perfect" method of transition which allows the doctor time to accept and integrate new beliefs and abilities through long hours of constant practice, observation, and tutelage.

All Qigong techniques are based on the imagination and spiritual belief. It is necessary to create an image (a spiritual belief) within the mind, to create a positive environment for healing transformations (the spirit transforms energy, and energy transforms matter). Sometimes the Qigong doctor will want to utilize a certain image of his or her belief, but because of certain doubts, is unable to bring it into existence. In order to successfully cultivate this image, the doctor must use creative thinking to focus his or her life-force energy on this specific objective, accept it as true and know it will happen. To create this image the doctor must use his or her imagination, emotional feelings, unwavering belief, visualization, affirmation, and acceptance.

Energy (Qi) is the bridge between the material and the spiritual, and is the medium through which consciousness interacts with the world. Through intention, Qi is gathered, focused, and used to transform light, sound, and other resonations. Through intention, the Qigong doctor is able to change structural formations, and to transform tangible and intangible forms and vice versa, to dissolve tumors, cysts, and so on. Of the many methods of healing available in Medical Qigong, it is important for the Qigong doctor to explore the healing skills suited to his or her body and personality, to become most effective. Once the doctor has learned and mastered these healing techniques, he or she will no longer need to think about the methods, or when they need to be employed, they will become second nature.

PERCEPTUAL COMMUNICATION TRAINING

Subconscious communications are divided into physical, emotional, and intuitive forms of interaction and perception. The internal-vision techniques required to utilize energetic perception in a clinical setting are expressed and enhanced through these types of communication. These types of communications are realms of perception that can be explored, wherein, the Qigong doctor is so present in "the moment" that his or her attention begins to dissolve the perceptual realities of all five senses, and begins to perceive and diagnosis patients on a spiritual level. At this level, all feelings, sounds, colors, or any combination of the doctor's senses take on new dimensions of reality.

DIAGNOSIS THROUGH DANTIAN COMMUNICATION

Any treatment, exercise, or meditation the Qigong doctor prescribes must connect with the energetic resonation of the patient's disease. This connection is established through the doctor's ability to communicate with the patient's body via the Three Dantians.

1. The Upper Dantian's perceptional awareness is received through a type of spiritual/intuitive communication. Through this intuitive subconscious communication the doctor is able to interact and perceive the patient's spiritual and energetic disturbances. This allows the doctor to perceive the patient's spiritual condition without bias.
2. The Middle Dantian's perceptional awareness is received through a type of emotional/empathic communication. Through this empathic subconscious communication the doctor is able to interact and perceive the patient's feelings, actively empathizing, listening, and hearing what patients communicate about their pain and problems. This allows the doctor to perceive the patient's true emotional condition by bypassing the person's ego.
3. The Lower Dantian's perceptional awareness is received through a type of kinesthetic communication. Through this physical subconscious communication the doctor is able to interact and perceive the active condition of the patient's physical tissues. This allows the doctor to perceive (through his or her hands and physical body) the patient's physical symptoms, such as pain, Heat, and so on.

UTILIZING INTERNAL-VISION AS A CLINICAL MODALITY

The brain has the ability of receiving and recording the vibrations of any object that the senses see, hear, smell, taste or feel. The vibrations of light, sound, smell, color, and object's shape are all recorded. This also holds true for thoughts, words, and actions. The brain also has the ability of reproducing these vibrations and projecting them out again through the use of inner vision and the imagination.

Before beginning internal Qi diagnosis it is important that the Qigong doctor have a thorough understanding of the internal energy's function and flow within his or her own body. Dr. Li Shi Zhen pointed out during the Ming Dynasty that, "The internal organs and channels can be perceived as unobstructed and free from disease only by those who can see internally."

This is achieved by performing the Nei Guan or Internal Viewing Meditation. The purpose for internal-vision is to carefully examine, through conscious introspection, the energetic flow and structure of the body and mind. Most doctors in the Ming Dynasty studied the Nei Guan Meditation as part of their clinical practice to develop the light for internal viewing. It is believed that light enters the body through the Baihui Point (at the top of the head), the Yin Tang Point (the Third Eye area) and through both eyes. Since internal-vision uses light that has a higher vibration than visual light, it is able to penetrate through the skin deep into the tissues.

Many years ago I was truly skeptical of this phenomenon, although I met many Qigong masters who possessed such skills. After acquiring this skill, however, I was able to demonstrate its effectiveness quite thoroughly while interning in the Qigong hospitals of Beijing, China. It is actually a simple matter of consistent practice and focused concentration which allows this sense of perception to become tangible. It is important to remember that to know something, one must first think it, then feel it in order to integrate the knowledge fully. Always watch as an observer, void of emotional attachment, noticing what is actually there.

Nei Guan—Internal Viewing Meditation

The best way to practice the Nei Guan Meditation is through relaxed, quiescent breathing. Begin from a Wuji posture. After quieting the mind, relax and focus the imagination. Imagine that the left eye is a bright radiant sun, while the right eye is a bright and luminous moon. Both the sun and moon join together at the Yin Tang (Third Eye point). As their energies come together, they form a bright white ball. This light actually gathers around the pituitary gland, illuminating the optic chiasm, filling the occipital lobes (for internal perceptual vision) and the thalamus (for oculomotor control) (Figure 25.5).

As the light expands it stimulates the corpus callosum and penetrates the pineal gland (which acts as a projector for internal vision) (Figure 25.6).



Figure 25.5. The Internal Viewing Meditation

Next, focus your intention on directing this ball of white light, allowing it to shine down into the body, illuminating all the internal organs. This enables you to see directly inside your own body and view each organ. Observe and feel the energetic strengths and individual weaknesses of the bones, organs, and tissues. Allow both energy and information to gather and expose itself through the Third Eye region of the Upper Dantian. After a while, relax and return to Wu Wei (i.e., No Mind), allowing all of these images to settle.

After a relatively short time of constant practice Qigong doctors learn to discern the state of their own organs, and are able to regulate their own physical and energetic body. This internal diagnostic ability sets the foundation for doctors to extend their Internal-viewing capability outside their own body to use on patients.

Once this occurs, doctors find it possible to effectively diagnose patients while scanning and using the Flat Palm Detection technique. The patient's points and areas for diagnosis are revealed to the doctors through this modality of energetic extension.

When using internal-vision, extend your intention as deep into the patient as possible, to slowly scan the patient's tissues, layer after layer, observing any cellular changes and distortions. Use the internal light resonating from inside the patient's body to identify the pathogenic factors. Then, look deeper into the energetic currents to find the root and origin of the patient's disease.

When you use your hands to read the patient's internal organs through Flat Palm Detection or any other diagnostic modality, it is extremely important to use internal-vision to determine the severity of the disease. You may observe a specific color, texture, or feel pools of emotional energy. According to Dr. Zheng Zhang Ding, doctors will be able to determine the condition of the diseased organ by its shade of color. The internal-vision colors most commonly observed in internal-vision diagnosis are as follows:

- A red or yellow color represents a healthy or normal organ;
- A white color signals the beginning of energetic dysfunction, but is not serious enough for treatment;
- A gray color signifies sickness; and
- A black color denotes, tumors, cancer, etc.

APPLICATIONS OF INTUITIVE AND PERCEPTUAL QI DIAGNOSIS

There are a variety of methods concerning the application of intuitive and perceptual diagnosis of diseases. The specific physiological methods such as remote sensing, hand detection and physical body observation are very popular in the Medical Qigong clinics in China today. Five of the most favorite modalities of intuitive and perceptual Qi diagnosis are described as follows.



Figure 25.6. The inner light gathers at the pituitary gland, illuminating the optic chiasm, filling the occipital lobes and thalamus, stimulating the corpus callosum and penetrating the pineal gland.

DIAGNOSIS BASED ON FLAT-PALM DETECTION (HAND SENSING)

Because the body's energetic field reflects the state of health or dysfunctions of the physical body, any changes occurring in the tissues and organs are detectable through sensing this energetic field. Detection of these changes with the palm is termed Flat-Palm Detection.

To perform this technique, the doctor begins by asking the patient to take a standing, sitting or lying posture. The patient's whole body should be relaxed, the mind focused on breathing naturally. The doctor positions his or her palm several inches from the patient's energy field, with the Laogong Pc-8 point or fingertips facing the direction of the patient's body.

The doctor then emits a little energy, slowly, followed by Pushing, Pulling and Leading manipulations used to detect the Qi of the patient's energetic body. The patient's surface tissue is divided into upper and lower, left and right aspects. The doctor focuses on the surface tissue area first, specifically the area corresponding to the region of the patient's disease. The doctor then determines the energetic nature of the corresponding regions by making comparisons between the sensations gained in different areas to find where energy feels abnormal. Gradually, the doctor's emitted energy is extended deeper into the body to purge, disperse, tonify or regulate the patient's organs and organ systems (Figure 25.7).

The Qigong doctor then analyzes these energetic sensations, comparing how they feel from the different areas of the body (both on the superficial and deep layers). The doctor categorizes the pathological findings (the location, nature, and severity of the disease) in accordance with the Eight Principles of Diagnosis and the energetic patterns of The Five Elemental Theory.

Feeling a great difference in energy intensity between the two sides of the Stomach Channels, for example, indicates a Yin and Yang imbalance of energy circulation between the left and right sides of the body. The Deficiency and Cold syndrome of the Spleen and Stomach may be manifested by a cold and contracted sensation in the epigastric region.

When an acupuncture needle is inserted into an obstructed point the energy grabs the needle and vibrates it. Once this energy block is removed, the needle ceases to vibrate because the channel is now open. This same phenomenon occurs when the palm is placed on an area of stagnant Qi. The palm vibrates until the obstructed energy is dispersed.

Energy blocks are commonly cleared by dredging in a downward direction from the head (Heaven) to the feet (Earth). When treated this way, patients will experience a temporary feeling of fatigue as the stored toxins are released from the body. Tonification is facilitated by bringing the energy current up the patient's body from the feet to the head (Earth to Heaven). This action will sometimes cause patients to have psychic experiences and see visions, as the energy enters the patient's Upper Dantian region.



Figure 25.7. In Flat Palm Detection, the Qigong doctor uses the entire palm to sense the condition of his or her patient's internal organs and tissues.

DIAGNOSIS BASED ON KINESTHETIC AND EMPATHIC QI ABSORPTION

There are some individuals who tend to easily absorb the feeling and emotions of other people, even without trying. Sometimes when treating a patient, a Qigong doctor will inadvertently ingest a small amount of their patient's energy. As this energy absorbs into the doctor's body, it infuses throughout his or her entire energetic field. This energetic fusion sometimes causes the doctor to experience abnormal feelings in the locations that correspond to the pathogenic areas of the patient's body. From these feelings, the doctor can diagnose the location and the nature of the patient's disease.

To actively perform this method of Kinesthetic and Empathic Qi Absorption, the Qigong doctor stands facing the patient (Figure 25.8) and projects white healing light energy toward the top of the patient's head (Baihui GV-20 point). The patient is thus enveloped by the white healing light energy, from the top of the head, to the bottom of the feet. Next, the doctor directs the Qi to flow from the bottom of the patient's feet into the bottom of his or her own feet, absorbing the patient's energy. This energetic action forms a complete cycle of energy between the doctor and the patient's body. The Qigong doctor then begins to carefully feel the sensations of the patient's energy in his or her own tissues and organs. The locality of abnormal feelings, their shape, and/or prominent characteristics reflect the locality and nature of the patient's illness.

Note: It is generally encouraged to avoid this type of body detection on cancer patients, because the risk of pulling in the patient's excessively Hot pathogens into the doctor's body is too high, especially if the doctor's energy has become depleted.

HAND DIAGNOSIS BASED ON BODY ASSOCIATION

A small percentage of energy absorbed from the patient can suffice to diagnose the whole energetic system. Because the law of bio-holograms holds that one part of the body contains information about the whole (including various parts of the body, such as the viscera, Qi, and Blood, etc.), information obtained from certain isolated areas can reflect the condition of the whole body. Such parts may include the hand, foot, eye, ear, nose, face, etc. The location on these parts that represent different areas and organs are termed as "points" or "zones:" they include hand points, foot points, ear points, and so forth.

Hand diagnosis (called Shou Zhen) is used to evaluate the physical predispositions and ailments of patients. This diagnostic technique first appeared in Chinese medical literature during the Sui Dynasty (618-581 B.C.) from the clinical writings of Dr. Chao Yuan Fang, who authored the "General Treatise on the Origin and Symptoms of Various Diseases." To begin diagnosis through hand-body association, the Qigong doctor first neutralizes his or her left palm (by releasing the energy into the Earth) to balance and stabilize its sensitivity. The left hand is generally used for reviewing energy and diagnosing diseases.



Figure 25.8. In Diagnosis based on Kinesthetic or Empathic Absorption of the patient's Qi, the Qigong doctor temporarily absorbs the patient's energy field into his or her own body.

Once the left palm has been neutralized, the doctor uses his or her intention to gather the patient's Qi into the left palm, distributing the absorbed energy evenly throughout the hand. Focused concentration on any one specific area of the hand should be avoided. The doctor imagines the patient's energy enveloping the left hand and fingers, like an energetic glove. The doctor carefully begins to sense the sensations of the patient's energy on his or her palm. The center and front of the doctor's palm is considered the center and front of the patient's body, while the back of the hand is considered the back of the patient's body. The doctor feels various kinds of sensations on specific areas of the left palm, which indicate the location of the patient's disorders. These different sensations,



Figure 25.9. Diagnosis through Hand/Body Association

such as distention, heaviness, numbness, heat, cold, itching, and throbbing correspond with the features of the disorders (Figure 25.9).

While in Beijing, China, I was fortunate to study under Qigong Master Zheng Zhan Ding. Master Zheng had a remarkable gift for diagnosis and was compassionate enough to share his particular skills and training with me and two of my senior Medical Qigong students.

There are many schools of teaching for hand diagnosis. I have used several methods with great success in diagnosing and treating patients in both China and North America. The primary requirement for correct diagnosis is the use of the mind's intention. The imagination sets the foundation for the "energetic blueprint" of the patient's body (Figure 25.10). The method for employing this technique is described as follows.

1. Begin to scan the left palm and feel for Hot (Excess) or Cold (Deficient) areas. These areas will relate to specific locations of illness. The doctor begins to treat these regions of disease by using one of the following three methods:
    a. The doctor uses intention to tonify or purge the troubled areas inside his or her own left palm;
    b. The doctor uses his or her right hand (usually with the index and middle finger) to tonify or purge the energy from his or her left palm; or
    c. The doctor extends and treats the patient's body with his or her right hand while reading and diagnosing with the left palm.
2. Another variation of hand diagnosis is practiced by first having the patient breathe evenly into the Lower Dantian. Next, the patient focuses on his or her entire body, while placing the right palm (facing outward) towards the direction of the doctor. The patient is encouraged to relax while keeping his or her palm steady.

The doctor slowly moves the index or middle finger of his or her right hand towards the patient's right palm. While continuing to focus on the patient's energetic field (emitted from the patient's extended right palm), the


Nasal Cavity
Head
Oral Cavity
Eyes
Notch
Hyoid Bone
Throat/Thyroid
Wrist
Wrist
Elbow
Elbow
Ankle
Breasts/Chest
Knee
Shoulder
Liver
Hip
Heart
Lungs
Ankle
Stomach
Gall Bladder
Spleen
Knee
Pancreas
Hip
Large Intestine
Urinary Bladder
Ovaries or Testes
Small Intestine
External Genitals
Occiput
Cervical Vertebrae
Thoracic Vertebrae
Lumbar Vertebrae
Sacral Vertebrae (sacrum)

Figure 25.10. Front and Back View of the Hand/Body Association

Qigong doctor gently points to where he or she feels a particular energetic sensation (Figure 25.11). This special feeling or sensation that the doctor is receiving, represents the location of an energetic problem or disease. While scanning the patient's right palm, each different feeling or sensation represents a diversity of energetic manifestations related to the patient's disorder.

DIAGNOSIS BY OBSERVING AURA FIELDS

Some Medical Qigong doctors use aura readings to determine the physical, mental, emotional, energetic, and spiritual health of the patient. Aura colors will sometimes appear in the form of waves or other energy patterns (for example: evenly layered, blotchy, mixed together, etc.). Aura colors are in a state of constant flux, shifting their colors and patterns with each shift of the patient's moods and emotional thoughts. These colors merge and blend as they fluctuate, weaving in and around the patient's field of Wei Qi.



Figure 25.11. Variation of Finding the Patient's Disease Area by Diagnosing the Patient's Hand



Figure 25.12. Diagnosis by Observing the Patient's Aura Fields.

To begin observing auras, ask the patient to relax his or her whole body, while sitting or standing in front of you. The patient should breathe evenly, to release any distractive thoughts, and then concentrate on the location of the specific disorder. The Qigong doctor focuses his or her attention on the space surrounding the patient's body, while simultaneously concentrating on his or her own Upper Dantian.

Focusing on the Upper Dantian to view the patient's body facilitates seeing the patient's aura field. The patient's aura field may be observed in the form of transparent or opaque Qi flow, or masses of different densities and colors. This may be used as a basis for determining the location and features of diseases (Figure 25.12). Each Yin and Yang organ will have its own color vibration.

When the energy of an organ is healthy, the Qi color is clean, clear and lucid. When an organ is diseased its Qi becomes dark gray and turbid. These colors reveal whether an organ is in an abnormal state and to what extent it has been affected.

COLOR VIBRATIONAL CLASSIFICATIONS

The variety of shifting colors can be interpreted according to their density and tone. The following chart displays the color frequency correlation in nanometers. All living organisms vibrate at a frequency between 300-2,000 nanometers. When analyzed, specific colors emanate consistent frequencies and wave forms. The slower frequencies register in the infrared light spectrum. The highest vibrational frequencies register in the ultraviolet light spectrum (for more information see Chapter 4).

Red	700 nm	Infrared
Orange	600 nm	
Yellow	550 nm	
Green	500 nm	
Blue	450 nm	
Violet	400 nm	Ultraviolet

SEEING AURAS AND EMOTIONAL ENERGY

Seeing auras is a visual phenomenon which occurs after many hours of regular Qigong training. This ability to see the external energy field is not limited to Medical Qigong training; many people are born with this special gift. The word "aura" literally means "breeze," manifesting as shimmering layers of luminous, colored energy that circulate around and penetrate into the physical body. These colors are part of the body's biophoton emissions (radiant light energy that emanates from all living systems). These colors are constantly in motion, reacting to thoughts, feelings, emotional patterns, and environmental influences.

Through the stimulation and physical dilation of the occipital lobe of the brain, the doctor begins to develop this unique perceptual ability. In the beginning stages the doctor may see energy coming off the patient's body like steam.

Later, brilliant, luminous colors become visible. The doctor is actually observing the infrared and ultraviolet radiation color patterns that the patient's body emits. The infrared spectrum is just below the average body's visual spectrum, while the ultraviolet is just above the average visual spectrum. By stimulating and dilation the occipital lobe, the visual spectrum expands to include the infrared frequency, allowing the doctor to observe from a much greater range of colors.

It has been my personal observation that students who possess a large bump on the back of the cranium, specifically between the channel points GV-16 and GV- 17, begin to see auras at a very early stage. These points are below and just above the external occipital protuberance and surround the internal branches off the occipital arteries, veins and nerves. When energy fills this area, the stimulation and dilation of these nerves and arteries causes the visual receptors of the brain to observe certain phenomena at a faster rate, which causes time to seem to slow down (Figure 25.13).



Figure 25.13. As the occipital lobe fills with Qi, the visual spectrum changes.

It is very important to note that these observations are all possible due to the occipital membranes being dilated. To maintain this dilation the doctor must remain calm and relaxed. Any tension brought about by stress only diminishes this ability. Auras are generally seen through the peripheral field of vision.

If the doctor begins to stare at any particular object, focused concentration will contract the occipital membranes, causing tension and pressure that inhibit the dilation process. The secret in maintaining this altered state of observation is to anchor the mind deep into the ground. By focusing the mind on a specific area, focus can be shifted to receiving and observing auras in addition to extending energy without distraction.

The following meditation can be used to stimulate the occipital membrane and enhance the perception of auras.

Seeing Aura Meditation

This meditation can be practiced either sitting or standing. The mind must be free of all distractions and tensions in order for the energy to permeate the occipital lobe. Draw an imaginary line from the top of the head (Baihui) down the spine, down the back of the legs, out the heels and deep into the Earth. This is your mental anchor line

Using the Dial: Feel the reflection of the colors in the collection points in the energy body that surrounds the cauldron.

Feel the outward reflection of the collection points into the Universe. The red ball of light above the head, the blue ball of light deep below the feet, the green ball of light to the right, and the white ball of light to the left.

1. Turn the collection points of the energy body clockwise one station. Turn the collection points of the Universe one station counterclockwise.
2. The physical body collection points always remain stationary. Now the color sequence is red at the physical heart collection point, green below it in the energy body, and white above in the Universal collection point. Below, the physical collection point is blue, the energy body is white, the Universal is green, the right physical body collection point is green, the energy body is blue, and the Universe is red, and on the left the physical body is white, the energy body is red, and the Universe is blue.



__Fig. 6.31__ Fuse inner positive energy out with universal energy through turning the Dial-1.

which is used to drain your mind of all thoughts (Figure 25.14).

By continuing to drain your thoughts deep into the Earth, you free your Yuan Shen to rely on intuitive perceptions that allow for this altered enhanced peripheral field of vision. This meditation should be practiced for a period of 15 to 30 minutes each day to establish a pattern of relaxation.

As you scan a patient, look to the sides of the patient's body, observing the silhouette of the outer shell of the patient's Wei Qi. It is important not to stare, but just observe the patient's external Wei Qi field (e.g., observing where the field is large, full, thin, or broken). Sometimes different lighting will affect the dilation of the occipital lobe, enhancing visual receptivity.

Next, allow the silhouette to become different colors. Usually, in the beginning, you can see only two or three different colors. With time and practice you will be able to differentiate more colors, with finer detail.



Figure 25.14. Root the Mind deep into the Earth.

DIAGNOSIS BASED ON THE BODY'S EXTERNAL CHANNELS AND AURA COLORS

Each of the five emotions are related to both the Yin and Yang organs and their Yin and Yang natures. These five emotions are also related to five major colors, both inside and outside of the body's physical structure. By comprehending the colors and understanding their connection to the emotions of the body, the Qigong doctor can successfully analyze the abundance or depletion of energy in his or her patient's major organs. Not only will this reveal the patient's present psychological state of being, but will also expose which internal organs are weakened.

The color chart (Figure 25.15) is used to correlate the patient's energetic fields. These colors are similar, yet have their own unique variations from the physical body's tissue colors.

Think of these colors as extensions from the original organ pools. The mist of the organ pools flows into the body's aura fields, and can be observed in the patient's external energy fields. They are generally very vibrant colors and veil themselves around the first two layers of the Wei Qi. Observe their location around the body, whether they are static or pulsing. If a particular body organ malfunctions, or if any disease is present, then certain parts of the aura may become dim, murky, or produce a dark void.

It is important to remember that each patient has his or her own color schemes. When observing the color spectrums of the patient's energy field the most important characteristic is the clarity of the colors. Observe if the colors are sharp, murky, or too concentrated.

The Yang patient's colors will vary in tone and brilliance from the color spectrums of Yin patients. Each aura adjusts to match the patient's mood and temperament. People also often choose for their environment colors that reflect the characteristics of their aura and emotional spectrum (e.g., clothing, furniture, house, and room color, etc.).

When using color energy for healing, the Qigong doctor chooses which specific color to emit, e.g., using blue to cool the Qi or red to heat the Qi (see Chapter 4). Generally, when treating patients, the Qigong doctor will either wear all white (which is the combination of all colors, and is used to naturally project energy), or all black (which is the absence of all colors, and is used to naturally absorb energy), but never the color red (the color red is too intense or "Hot" for Qi extension).

DIAGNOSIS BASED ON INTENTION

The doctor's own developed inner vision can provide a diagnosis through observation of a mental image of the patient. The doctor begins by observing an image of the patient as a complete and whole energy system. Next, the doctor imagines the energetic form of the patient's internal organs (Figure 25.16).

If any part or organ is dark or gives a feeling of turbidness, this indicates the location of the disease. When using this type of energetic diagnosis, the sense of smell, the sense of taste, direct perspective, and remote sensing are also helpful diagnostic skills to enhance detection.

LONG DISTANCE MEDICAL QIGONG THERAPY

Long Distance Medical Qigong Therapy has been with us for centuries. One of the ministers of Huang Di, the Yellow Emperor and patriarch of Chinese medicine, was a shaman named Zhu You. Zhu You was a famous doctor who advocated exorcistic prayer over the use of acupuncture needles and herbs to treat illness. Some scholars believed that Zhu You practiced Qi emission healing at the same time that he prayed for his patients. So effective was this healing approach that The Yellow Emperor's Classics states that, in ancient times, most illnesses were treated according to the methods of Zhu You. In fact, at one time, professional "prayer healers" were once widespread throughout China.

There are several schools of thought on the modalities of long distance healing. Each school

Internal Organ	Aura Color
Lungs	Pure White
Large Intestines	Off-white
Stomach	Deep Yellow
Spleen	Orange Yellow
Heart	Red with Slight Blue Tint
Small Intestine	Pink
Bladder	Deep Blue
Kidneys	Light Flame Blue
Pericardium	Purple Red
Triple Burners	Orange Red
Gall Bladder	Yellow Green
Liver	Deep Green

Figure 25.15. The internal organs are each associated with a specific aura color.



Figure 25.16. The Qigong doctor can diagnose the patient's body through energetic observation and intention.

has its own unique, yet extremely effective application of this esoteric skill.

Although I believe in the effectiveness of prayer, at one time I sincerely doubted the existence of long distance healing. I was thoroughly convinced that it was a matter of projected influential visual and auditory input, similar to hypnotherapy. I expected the doctor to talk to the patient and have him or her close the eyes to facilitate an emotional and mental healing over the telephone. The difficulty in this kind of healing is that if the patient does not trust you, his or her consciousness will not cooperate and will sabotage any healing energy extended in his or her direction.

As fate would have it, one of my Medical Qigong instructors called me one day. As we were conversing, my Kidneys began to heat up. This heat was quite intense, and I was extremely startled because no prior warning of this particular kind of treatment had been given. Yet, I could not dismiss the overwhelming searing heat that I felt in my lower back, Kidneys, and Mingmen area. This healing was done without my conscious consent or foreknowledge! My instructor laughed and explained that as she was talking to me, she was holding a pillow (which represented my body) and visualizing treating my Kidneys with her right hand.

At that point, my beliefs surrounding long distance Medical Qigong healing began to change radically. I began to inquire as to the qualifications needed to treat with that modality of therapy. I learned from my instructor that long distance energy transformation is similar to close range energy transformation. The only difference is that in long distance healing, the doctor's faith and psychic faculty has to be extremely developed and accurate.

To become proficient at long distance therapy, the Qigong doctor must extend his or her thought vibration into the atmosphere, which connects with the thought vibration of the distant patient. Both vibrations collect and blend, drawing together at a selected point on, or within, the patient, creating and reproducing the patient's energetic fields, organs, and tissues.

Zhu You's long distance healing through prayer may be compared to the effectiveness of prayer groups today. Larry Dossey, M.D., for example, documents one double-blind experiment involving nearly 400 patients admitted to the coronary care unit of San Francisco General Hospital for heart attacks or suspected heart attacks. These patients were evenly subdivided into two groups. Both groups received "state of the art" medical care; the only difference was that one group was prayed for by Protestant and Catholic prayer groups throughout the country. These prayer groups had only the patients' first names and sketches. The patients in the experimental group had no idea they were being prayed for; yet when the study was concluded, they experienced significantly fewer complications and deaths than did the non-prayed for control group.

SPACE/TIME AND ENERGY

To study long distance energetic healing, we need to look at a three-dimensional energetic pattern which includes Positive Space / Time, Negative Space / Time, and Energy.

1. Positive Space / Time Energy includes commonly accepted forms of energy (such as electromagnetism, nuclear energy and gravity), and all vibrations ranging from extremely slow to the speed of light. It includes lower vibrations (from inanimate objects) and the higher vibrations of thoughts.
2. Negative Space / Time Energy includes all vibrations which travel faster then the speed of light (super-luminal), and accounts for such phenomenon as telepathy, psychokinesis, precognition, and levitation. In negative space-time, particles have a negative mass and are known as antimatter. When activated to super-luminal speeds, these particles appear to dematerialize, and produce a levitation force which balances the gravitational effects of positive space / time. This also accounts for the Qigong doctor's ability to transmit energy through all known force shields (excluding mirrors, due to their ability to reflect light-energy).
3. Energy and matter form a continuum as does space / time. Energy is the medium between

the positive and negative forms of space. It is the medium between which matter and spirit interact with the space/time continuum, through which heat, light, sound, and resonant vibrations travel.

Matter is composed mostly of space with a minute amount of mass, bound in a particular pattern. This pattern is unique for every form of matter, including the human body. Particles of matter in the human body are constantly vibrating in intermediate stages of energy interaction. Consciousness (the qualitative and directional aspect of energy), acts as a medium for the Qigong doctor's intention to project into the time/space energy field. Consciousness functions as the energy source for resonant vibrations which create the physical world.

To perform long distance healing, the Qi in the Lower and Middle Dantians (the body's Fire and Water energy) must overflow and transform into Shen. The Shen is then united with the divine Qi and extended outside the body for long distance healing of the patient. This allows the energy to cross both spatial and temporal boundaries, thus enabling the Qigong doctor to heal patients in the absence of physical contact.

The first priority in long distance healing, is to establish a connection between all three Dantians through the absorption of divine Qi into the Taiji Pole; this process is called the "empowerment with divine Qi," or simply, the "hookup." This action surrounds the doctor's Wei Qi with Tian Qi (Heavenly Energy), which then is transformed into Tian Shen (Heavenly Spirit).

The doctor then visualizes a long stream of white light extending from the Yin Tang (Third Eye) point, which connects to the patient's body (Figure 25.17).

Once the doctor feels this connection, he or she may now begin the treatment. The physical manifestations of long range healing are the result of the Shen affecting the Qi, and the Qi affecting the body's Jing.

LONG DISTANCE SCANNING EXERCISE

Long distance scanning can be develop by practicing the following mediation exercise.



Figure 25.17. The Qigong doctor absorbs divine Qi through the Baihui area, filling the center Taiji Pole, then projects the divine energy out the body through the Yin Tang or Third Eye area.

- The patient sits in front of the doctor. After connecting with the divine, close your eyes and start to scan the patient's external and internal energetic body. Try to feel the patient's different shades of light and different color spectrums, as well as the patient's temperature, projections, resonant vibrational essence, and varying qualities of texture in the patient's electromagnetic fields.
- Next, open your eyes and scan the patient, comparing and contrasting any differences from your initial readings. Continue to practice this modality of distant scanning until your reading and diagnosing abilities become very accurate. Perfecting your long distance scanning abilities may require several months of training.

LONG DISTANCE THERAPY

To dredge the channels, tonify and regulate the patient's energetic fields using long distance energy transformation, the Qigong doctors sometimes practice the two following meditation exercises.

Long Distance Dispersing Meditation

The doctor begins by placing his or her patient in the next room. After the doctor connects with the divine, he or she imagines his or her body surrounded by a ball of brilliant white light. The doctor then extends a stream of this white light energy out from the top of his or her head and onto the top of the patient's head, enveloping the patient's entire body.

As this white light energy descends down the patient's body, the doctor visualizes the patient's diseased energy dispersing and melting away into the ground. The patient's pathogenic energy is extended into the center core of the Earth, where it is transformed by the Earth's center core fire and then recycled back into the patient as pure, refined Earth Qi.

Next, the doctor focuses on specific areas of the patient's body. The doctor visualizes any area which needs specific attention such as dark areas in the patient's body. The doctor imagines these areas becoming brighter until all the dark areas are dispersed. After energizing the patient's diseased area, it is important for the doctor to disconnect from the patient and withdraw his or her projected Shen (Spirit) back into his or her body.

Long Distance Purging Meditation

The doctor begins by sitting on the edge of a chair with both feet firmly on the ground. Next, the doctor brings both palms up in front of his or her body, at throat level (middle fingers pointing straight upwards), and imagines a ball of white light suspended in-between the palms.

The doctor now pulls the Heavenly Qi towards the center of the ball via the fingers. As the ball fills completely, the doctor imagines the Excess Qi beginning to overflow into the center of his or her palms (Laogong points), descending down the arms and spine, and collecting into his or her Kidneys and Lower Dantian area. The goal is to first collect and store Heavenly Qi in the doctor's Lower Dantian and Taiji Pole (Figure 25.18).

To facilitate long distance healing, the doctor imagines the patient in the center of the ball of light. The doctor focuses on the Excess energy no longer overflowing into the palms, but flowing into his or her patients body, cleansing, filling, and healing the disease (Figure 25.19).

FAITH PROJECTION AND MEDICAL QIGONG THERAPY

This technique is a combination of both psychosomatic and visceral healing. It entails speaking to the patient and establishing a curative relationship through belief modalities, similar to those of "faith healing" used in the West.

It is a form of mind projection; the stronger the Qigong doctor's faith and intention, the better the healing will be. It is important for the patient to have an extremely strong faith in the doctor and to feel secure in the healing environment. The stronger the patient's and doctor's faith, the better the healing.

One popular example of this faith projection ability comes from the famous Qigong Master Shen Chang. Master Shen, lecturing at a conference sponsored by the China Ministry of Broadcast, Film and Television (with hundreds of witnesses present), extended Qi into a woman patient (in her 50's) with a three inch tumor on her leg. As Master Shen began his transmission he began to shout "Gone!" Instantly the tumor started to shrink. After shouting "Gone!" two more times, the tumor had completely disappeared. To the astonishment of everyone, Master Shen then shouted "Grow!" and caused the tumor to reappear. After this amazing demonstration, he then removed the tumor, and completely healed the patient.

Perhaps the body manifests what the mind believes and the Heart feels. It then adjusts itself according to the belief structure and forms a new holding pattern (both physically and energetically). Usually, the doctor will say an instructional phrase four times to the patient, intensifying his



Figure 25.18. The Qigong doctor imagines creating a ball of divine healing white light, suspended between his or her palms.



Figure 25.19. The Qigong doctor imagines that his or her patient is positioned in the center of the ball of divine healing light.

or her intention and instruction each time. The doctor's intention begins to reprogram the holding patterns of the tissues by shocking the system into a new and healthier pattern; a kind of "Be Healed Now!" approach. It is important to know that the energetic field surrounding the patient is strongly affected by either positive emotions and support, or negative emotions, suspicion and disbelief.

To illustrate this fact, I would like to recall an incident that took place in a Santa Cruz bible college in the late 1980's. One morning a colleague was lecturing in an auditorium full of 250 young seminary students. Suddenly, the back door of the auditorium swung open, and a young woman carrying a small baby came walking in. She was crying, and asked for help. She told my colleague that "God" had spoken to her in a dream and told her that if she came to this particular bible college and asked for help, that he would heal her child of a serious disease.

My colleague was both startled and shocked. Not knowing what to do, or even how to handle the situation, he quickly turned the meeting over to a local spiritual elder who was monitoring the lecture. This elder, seasoned in these types of spiritual phenomena, again asked the woman what the problem was. After hearing her story a second time, he informed her that while "God" had not spoken to him directly about the situation, he would be obedient to whatever "God" wished.

Next he looked up to the 250 young seminary students sitting in the auditorium and stated, "If anyone here does not believe that God can and will heal this child instantly, please leave now." All but three seminary students left the auditorium. The elder called to the three remaining students to join him with my colleague in praying for the baby. The child was instantly healed (a follow-up visit confirmed this fact), and the mother left, smiling. My colleague, perplexed by the whole event, turned to the elder and inquired as to how he knew what to do. The elder responded, "Even Jesus, who was the greatest healer of all time, couldn't heal in his own home town because of everyone's disbelief. Here in this auditorium it would have been five of us who had the faith in healing, versus 247 who were skeptical and full of doubt. It is better to have a few with great unwavering faith than to have many with little faith at all."

AUXILIARY MEDICAL QIGONG HEALING MODALITIES

The following are auxiliary Qigong modalities used by various Qigong doctors in hospitals and clinics, as well as their personal practices throughout China.

One of the methods used for these Medical Qigong therapies is the projection of Qigong Messages into specific material objects (i.e., a liquid, food, a scroll of calligraphy, a talisman, a cloth, a necklace, etc.). Once the object contains the Qigong doctor's Message it will have a powerful effect on the patient's body. This is a form of "transmission of intention" which is a form a Qi and Shen projection. Qi and Shen projection transcend time and space, lasting an indefinite amount of time depending upon the belief of the Qigong doctor and patient.

Certain Qigong doctors can transfer their energy or "thought message" through works of art. I experienced this technique quite accidently while lecturing at the Third World Conference on Medical Qigong in Beijing, China in 1996. I was in the back of the lecture hall sketching while one speaker was sharing his dissertation. Another Qigong Master seated in front of me noticed my artwork and asked to see it. Curious as to what he would do, I gave him my notebook. He placed his hand above my drawing and began projecting Qi into the picture. Immediately energy flooded my being from head to toe. I was literally vibrating all over, being filled with light and sound resonation (that felt similar to a strong electrical current). Since my original piece of art contained a direct connection to my physical energy, the Qigong doctor was able to extend energy into my body, by simply projecting his Qi into my artwork.

The doctor can transmit healing energy through any object which has had contact with or was created by the patient. This technique is possible because creative artwork, or any object touched or created by hand, is imprinted with the person's energy. This energy contains a unique blend of the individual's encoded energy patterns. This information regarding the individual can be retrieved through psychometry (the act of sensing the thoughts, images and so on, with which the object has been imprinted). A connection to the person who created or held the object can thus be established through the Wuji. This object can then serve as a focusing point to send healing to that person, through the doctor's intent.

Energy, in the form of waves, is expressed in the abstract form of thoughts, accessible to the vibrational medium of space and time. This allows for the energetic transformation of the individual's emotional patterning.

USING MEDICAL QIGONG TO HEAL BY PROJECTING CHINESE CHARACTERS

There are other Qigong doctors who draw specific Chinese characters in the air and send them encapsulated in a bright white light ball of energy into their patient's body to initiate healing (Figure 25.20). This projected energy is created through the doctor's intention and is absorbed into the patient's body, through the patient's receptive attitude and desire to heal.

USING MEDICAL QIGONG WITH SUPPLEMENTARY APPARATUSES

There are certain Qigong doctors who will use specific objects ranging from such supplementary equipment as rubber acupuncture dolls to pillows, in order to perform long distance healing. To utilize these objects for long distance healing, these Qigong doctors place the object, a doll for example, on the table in front of them and begin to draw their patient's Essence (from many miles or even across other countries) into the doll. The doctors then treats the patient by draining off the pathogenic excess from the doll (Figure 25.21). Once the doctors feel that the patient has been sufficiently cleansed and the disease dispersed, they begin to tonify the patient's weak organs. While



Figure 25.20. Another skill utilized by Qigong doctors, is to create different colored balls of energy to encapsulate specific Chinese characters (or Messages) within them, which are then projected into the patient's body as a form of treatment.

the Qigong doctors work on a patient, you can actually feel hot and cold spots emitting from the rubber acupuncture doll. Several of my students have been able to successfully implement this modality of training and find it fascinating.

USING MEDICAL QIGONG TO ENERGIZE HEALING CLOTHS

Some Qigong doctors extend Qi into pieces of paper or cloth, to be placed on the patient's body to invoke a healing. This is similar to the "prayer



Figure 25.21. Some Qigong doctors use a rubber acupuncture doll (man or woman) as an energetic medium, while treating patients at a distance. The Qigong doctor is removing pathogenic Qi and throwing it into a glass of salt water (used to neutralize the Turbid Qi).

cloths" and other techniques used today in the Pentecostal Churches. The energy stored within the cloth or paper, will last indefinitely, however, the most important component of this type of healing is the patient's belief structure (Figure 25.22-23).

USING MEDICAL QIGONG WITH CRYSTALS

The energy in the human body produces a polarity similar to that present in crystals. Because crystals emit a very strong white light energy, they can be used for energetic surgery, allowing the

Qigong doctor to cut into the patient's energetic field like a laser beam. Crystals can additionally be used for scooping energetic toxins, cleansing and purging the patient's body, and for cutting loose pathogenic Qi within the patient's tissues and external fields of Qi. Crystals can also be used for tonification, by enhancing the doctor's energetic extension and projection abilities.

USING MEDICAL QIGONG TO ENERGIZE LIQUID COMPONENTS

Other Qigong doctors extend their energy into herbal teas, wines, and I.V. fluids, as well as simple components such as water, to energize and utilize these liquids for healing. These doctors send the energized liquid substance to the patient, who ingests the medicine to tonify deficiencies. Water is an excellent repository for electromagnetic energy, and absorbs vibration better then any other substance (Figure 25.24).

USING MEDICAL QIGONG TO ENERGIZE FOOD

There is an ancient Chinese proverb which poses the question, "Is food medicine or medicine food?" Because a basic principle of Traditional Chinese Medicine states that anything ingested is transformed into energy (Gu Qi) by the body, some Qigong doctors extend their energy into the patient's food before it is ingested. This belief is not isolated to the Orient, but is also part of the Western culture, hence the practice of praying and blessing over food before eating it.



Figure 25.22. Emitting Qi into Cloth



Figure 25.23. Emitting Qi into Paper



Figure 25.24. Emitting Qi into Liquid

3. The fusion process begins here. Fuse the white energy from the energy body with the blue ball in the physical collection point at the perineum, and fuse both of these energies down to the Universal collection point with green light.
4. The same process continues with all the collection points. Next, fuse the green energy body point with the red physical body collection point, moving upward to fuse the white Universal collection point. Feel the energies fusing together above you.
5. Moving to the right side, fuse the blue ball of the energy body collection point with the green ball of the physical body, and outward to fuse with the red ball of the Universal collection point. Feel the energy fuse together at the right side.
6. Moving to the left, fuse the red ball of light of the energy body with the white ball of the physical body and moving out to fuse with the blue ball of the Universal collection point. Feel all these energies fuse together at the left.
7. Now we bring the fusion process back inside the body. Take the fused light below you, drawing it first to the physical collection point and then into the energy body collection point. Bring the fused energy above the head down to the physical collection point and then into the energy body collection point.
8. Draw the fused energy from the right back to the physical body collection point and then to the energy body collection point.



Fig. 6.32 *Fuse the Universal energy force back to inner positive energy and Energy Body through turning the Dial-1.*

SECTION VI

ESTABLISHING THE MEDICAL QIGONG CLINIC

CHAPTER 26
TREATING THE PATIENT

SETTING A SPACE/TIME FOUNDATION

Before treating patients, and to establish a sacred healing space, the Qigong doctor must first bring his or her true self into what is called the center of space and the center of time before performing the divine hook-up.

This establishes a foundation for treating patients, and allows the doctor to fuse with the patient, while accessing the energies of the divine, as well as the universal and environmental energies. Once this is achieved the doctor can allow him or herself to act as an observer, viewing the patient from a non-judgemental position.

FINDING THE "TRUE SELF"

The Qigong doctor's "true self" is defined as his or her pure innate spiritual existence, void of all ego masks and personalities. The "true self" is spiritually connected to, and rooted in, the energy of the divine. It is the part of the soul that unconditionally accepts self and others, and is more in the role of a compassionate observer than a judge. The "true self" allows the doctor to observe the patient's condition (spiritual, emotional, mental, energetic, and physical), void of any personal emotional biases. The "true self" is a state where unconditional love and acceptance is fostered and supported by the divine.

To discover the "true self", the Qigong doctor is trained through special Shengong (Spirit skill) meditations. One such meditation asks the question "Who are You?" This is repeated over and over until the doctor realizes and experiences his or her "true self". Who you are is not determined through expressing a correct answer, but by actually experiencing the spiritual quest. It is through the realization of this innate truth, which is inherent within one's own enlightenment, that the doctor is freed from the ego (known as the "Death of the Ego Fear"). Once the doctor realizes who he or she truly is, the answer is reflected from the light within the doctor's eyes and not through any specific mental concepts. There is a saying from Lao Zi, written in the *Dao De Jing* (The Way and Its Power) that explains this phenomenon: "The Dao that can be named is not the true Dao."

FINDING THE CENTER OF SPACE

Before treating a patient, the Qigong doctor must also place his or her body, mind, emotions, energy, and spiritual essence into a place of infinite existence called the center of space. The center of space is actually a spiritual and energetic concept, wherein the doctor imagines him or herself as being the actual center of the universe. This concept and image maintains that all energy, light, and energetic fields extend from the middle of the doctor's center core, expanding outward into infinite space (Wuji). This energy continues to extend and envelop the entire universe and all the energetic dimensions beyond.

To access the center of space the doctor must place his or her "true self" into the Taiji Pole, connecting the core self with the divine. It is from the orientation of the core self that the Qigong doctor accesses the deeper, hidden, spiritual, and energetic fields of the patient's body.

FINDING THE CENTER OF TIME

The final image that the Qigong doctor visualizes before the divine hook-up is to place himself or herself into the space known as the center of time. The center of time is the place of "Now." It is a dimension where infinite future is forever flowing into the doctor's center core, while the infinite past is forever rushing away.

To grasp the center of time concept, think of time as a linear progression of light and energy. The concept of future time is rushing directly into the front of your body. Within a split second, the Yang changes into Yin and the future transforms into the past, and continues rushing out the back of your body. You must find the still point, inside of your body, where Yang transforms into Yin, and the future transforms into the past - this is the center of time. From the center of time the Qigong doctor brings the patient into the present moment. This process enables the doctor to access the hidden past memories trapped deep within the patient's tissues.

ESTABLISHING THE MEDICAL QIGONG TREATMENT ROOM

Before receiving patients it is important to establish an environment that is conducive to healing. The density and quality of energy in the healing room is a very critical factor. Filling both the treatment room and clinic with the energy that flows from the Heavens to the Earth sets up an energetic vortex. Through the creation of this energetic vortex the patient's pathogenic factors will automatically flow into the ground once they are dispersed from the patient's body. The more energy that the healing room contains, the more successful the treatment will be. It is important to cleanse the healing room before and after each patient. This cleaning is achieved through the doctor's divine hook-up.

When establishing a treatment room it is also important to have adequate lighting and clean air ventilation. Avoid fluorescent lighting; if this is impossible, then use a full spectrum light.

It is important to also keep the patient's living quarters and bed energetically cleansed, as pathogens have a habit of collecting in areas of sickness and disease. The patient is encouraged to burn salt with a little alcohol to cleanse the treatment room (at least once a day) and fill the room with fresh air and light. Often neglected is the living space of the patient. Energetically cleaning the entire house or apartment often, during and after there has been an illness, allows the toxic energy to be purified from the patient's home.

One example of how energy stagnates is observed in hospital wards. Each ward has an energetic "feeling," associated with the different types of diseases or conditions treated there. The cancer ward, for example, feels entirely different from the maternity ward, emergency room, etc.

The treatment room must also be kept uncluttered, as energy stagnates in cluttered environments. Also, after each treatment, always change the bedding and energetically clean the clinic or treatment room.

WHEN TO AERATE, ILLUMINATE, OR SMUDGE

It is important to daily cleanse the energetic field of the treatment room. This facilities a fresh uncontaminated environment, allowing the next patient to feel safe and protected from any previous contaminants which may have been left from a prior patient. The three most common ways to cleanse the clinic before and after each patient (besides changing the table coverings), are:

1. Aerate by ventilating the clinic, making sure that the air circulation is fresh and clean (free from pathogens, Toxic Qi, dust and pollens, foul orders, smoke, etc.).
2. Illuminate by exposing the clinic to bright sunlight, or divine healing light (through prayer).
3. Smudging is performed by burning fragrant herbs in the form of certain incense (such as, sandalwood, myrrh, frankincense, or sagebrush, etc.). Remember to aerate after smudging.

The Qigong doctor may wish to incorporate either one or several modalities of cleansing. Each particular technique offers its own advantages and disadvantages, depending on the size and location of the clinic and its surrounding environment.

ESTABLISHING A RAPPORT WITH THE PATIENT

It is important to establish a foundation of trust between the doctor and patient before the treatment begins. This trust is enhanced by: Talking with the Patient to Establish Treatment Goals, Explaining and Reaching Agreements on the Treatment Modalities to be Used, Honoring the Patient's Spiritual Belief System, Receiving the Patient's Consent Before Treating, Matching the


Doctor
1. Talking with the Patient to Establish Treatment Goals
2. Explaining and Reaching Agreements on Treatment Modalities
3. Honoring the Patient's Spiritual Belief System
4. Receiving the Patient's Consent Before Treating
5. Matching the Patient's Respiration
6. Maintaining the Doctor-Patient Relationship
7. The Four Major Priorities of Clinical Qigong Healing
Patient

Figure 26.1. Establishing a rapport with the patient begins with trust.

Patient's Respiration, Maintaining the Doctor-Patient Relationship, and The Four Major Priorities of Clinical Qigong Healing (Figure 26.1).

TALKING WITH THE PATIENT TO ESTABLISH TREATMENT GOALS

After completing the diagnosis, establishing the treatment principle, and determining the treatment strategy, the Qigong doctor discusses with the patient the treatment goal (i.e., which internal organs, channels, and tissue areas are affecting the primary cause of the patient's disease, and how to address it). The treatment areas are specifically chosen to facilitate a rapid affect on the functioning process of the patient's disease. The doctor explains the intended goal of using the purging, tonifying, or regulating techniques, and how they will affect the patient's body.

EXPLAINING AND REACHING AGREEMENTS ON THE TREATMENT MODALITIES TO BE USED

The Qigong doctor explains, in clear, comprehensive terminology, what he of she has determined as to the best way of approaching and rectifying the patient's condition (e.g., having the patient in a lying, sitting or standing posture), and what treatment modalities the doctor will be using (i.e., through Qi Emission, Qigong Massage, Sound Therapy, Light Therapy, etc.).

The more the patient understands the doctor's approach in addressing the condition, the greater the likelihood of the patient relaxing during the treatment. This explanation also assists the doctor and patient in developing trust, which will encourage the patient when practicing the homework prescriptions, or in receiving suggestions on life-style modifications.

HONORING THE PATIENT'S SPIRITUAL BELIEF SYSTEM

When treating patients, it is important that the Qigong doctor not become distracted by the illusion of solid tissue matter, remembering that we are spirit, and that healing begins in this fifth dimension. The primary belief in Medical Qigong therapy is that tangible and intangible energy, through faith, will merge at the highest level of cultivation. Prayer is an invocation that extends the mind, emotion, and spirit to the divine, while meditation is a state of mental, emotional, and spiritual receptivity for divine inspiration, guidance, and manifestation. Both actions (prayer and meditation) connect the doctor and patient to the divine to bring patients back into awareness of their body and to initiate divine healing.

In China, Qigong doctors have a saying, "train your virtue and morality to increase your energy, allow your Spirit to lead your Qi and the Qi will flow pure." Meaning, the stronger the individual's virtue has been developed, the more powerful his or her spiritual intention will flow, and Qi move.

The healing modality choosen by the doctor must be congruent with the patient's spiritual belief structure. The patient must be connected to his or her own unique interpretation of universal consciousness (God) in order for divine healing to take place.

When the patient disbelieves in a Higher Power -- be it God or a universal consciousness -- the doctor can still help the patient heal, providing the patient has established sufficient trust and hope in the doctor. If the patient feels understood and listened to by the doctor, this can empower the patient to heal, regardless of his or her own conscious belief system.

If the doctor, on the other hand, does not believe that a true healing can take place unless the patient believes in a Higher Power or God - then no healing will take place, for the doctor will lack confidence, hope, and trust. The therapeutic bond between the doctor and patient will be broken and replaced by a battle of wills.

For patients who lack faith, applying a hands on Qigong technique may be more effective. Gradually, over the course of time, the doctor may incorporate other healing modalities as greater trust is built.

The Qigong doctor should always begin treatment in harmony with the patient's spiritual belief system (that may change in time), through touch, verbal conversation and unconditional love (empathy). The doctor should also communicate mind to mind, for this will facilitate trust at the subconscious level.

RECEIVING THE PATIENT'S CONSENT BEFORE TREATING

The treatment modalities should be decided together by the doctor and the patient. It is important for the Qigong doctor to provide the patient with enough information about the type of therapy he or she will receive, so that informed consent can be given for the treatment. This empowers the patient and allows relaxation and trust to occur.

MATCHING THE PATIENT'S RESPIRATION

Another technique to relax the patient is called "matching and pacing." The Qigong doctor matches the patient's breath and breathing patterns, and gradually shifts his or her own breathing to a slower and deeper pace. It is important to note that the patient's physiology affects his or her energy, which in turn affects his or her emotions and respiration. This technique of matching the patient's and doctor's breath and leading it into a state of quiescence is very often used by Medical Qigong doctors to relax their patients. It not only connects the doctor with the patient on an energetic and emotional level, but also provides a strong spiritual connection.

Note: Do not match an asthmatic patient's breathing, as this is disruptive to the flow of Qi within your own body.

MAINTAINING THE DOCTOR-PATIENT RELATIONSHIP

Whenever the doctor begins to judge or formulate negative opinions of a patient, he or she is no longer operating in the divine "present" state of spiritual intuition, but has shifted into the "past" (as all judgements are based on past experiences and emotional encounters). The doctor is then in danger of absorbing the discharged energetic pathogens from the patient, or projecting subconscious biased opinions onto the patient. Whenever the doctor relates, relives, or orients from his or her own personal past (the feelings can be either positive or negative), the doctor is at high risk of absorbing the patient's energetic pathogens.

When the patients come to the doctor, they are giving their consent for the doctor to learn about personal things which the patient has often withheld from their mate, family, or even themselves. They are further giving the doctor permission to utilize their combined energies to affect changes within their physical, mental, emotional, energetic, and spiritual fields and body.

Each treatment will be different for the patient, as each experience will vary according to the patient's present state of mind and emotional spirit. The patient's willingness to allow the Qigong doctor's emitted energy to penetrate deeper into his or her body with each session will depend upon the level of trust established, as well as any outside influences that may have a positive or negative effect on the patient's ability to be open and vulnerable. Patients who experience ridicule or criticism from family and friends for their choice of a non-Western form of treatment, may temporarily shut down their receptivity in self-defence against others. At times, patients may also close-off as a result of an event that has a strong impact on their emotional and spiritual well-being, such as a death of a friend, a physical trauma, or other upsetting news.

The patient always has the final control over the doctor's emitted energy, and can choose to either absorb and utilize the energy, or disperse and sabotage the doctor's treatment. It is for this very reason that the doctor-patient trust factor, as well as the goal orientation, must be securely established before the treatment begins.

Be sure the patient's arms and legs are not crossed, as this can impede, or "short-circuit," any energetic flow, causing Qi obstructions. The patient should close his or her eyes, but should not be allowed to internally guide or direct the Qi unless specifically instructed to do so by the doctor. A patient's unguided imagery can cause the body's energy to increase, alter, or obstruct the flow of the doctor's energy, which may cause Qi deviations or aggravate an existing condition. Usually the patient is given the image of dissolving his or her tissues into space, which encourages relaxation and freedom from distractions. If the patient is lying down, he or she is given certain visualizations, such as floating on a sea of warm water (or basking in the sun on the beach or shore of a lake). These images relax the patient and enable the Qigong doctor to disperse the patient's armoring. Once the patient's "street armor" is down, the doctor will have easier access into the patient's tissues.

After the treatment, the doctor and patient evaluate each session, discussing any and all feelings, observations, transitions, and sensations that both the doctor and patient experienced. Homework, in the form of Medical Qigong prescriptions are then generally given, in addition to follow-up treatments (depending on the patient's case and condition).

THE FOUR MAJOR PRIORITIES OF CLINICAL QIGONG HEALING

According to China's prominent Qigong Grand Master Pang Ming, clinical Qigong healing is based on four basic priorities. In establishing a clinical environment it is important to inform the patient about the structures of these four priorities: A Strong Faith, Group Healing, Medical Qigong Therapy, and Medical Qigong Prescriptions and Exercises.

1. A strong faith that Qi or life-force energy can heal the patient's specific ailment is built up by the patient listening to testimonials. These testimonials are given by other patients who have recovered from the same type of disease, as well as those patients who are experiencing improvement through Medical Qigong therapy.

   Qigong deals directly with the psychological aspects of diseases. It is well known that two side effects of cancer are depression and fear. A very popular theory maintains that depression (being the suppression of anger) can cause cancer. Even before the cancer patients begin their treatment program, their confidence is bolstered by the positive experiences of more advanced students of Qigong, who at one time also suffered from these particular kinds of cancer. In addition, as part of the Qigong exercises, the new patient's mind is focused on pleasant images or memories. All of this creates a positive mental attitude in the patient.

Sometimes patients come to the doctor for healing, yet at a deeper level they feel that they need or deserve the illness. Sometimes the secondary gain of illness (for example, to keep the wife or husband underfoot) outweighs the benefits of healing completely. If a patient is subconsciously unwilling to be healed, his or her attitude or disbelief will sabotage all clinical modalities of healing (both Western and Eastern). You cannot make someone better against his or her own will. Illness, like health, is often a matter of choice.

2. Before a group of patients begin Qigong, the doctor verbally synchronizes the thinking of the group by absorbing Heavenly Qi (the divine hook-up), and bringing it down into the healing energy field which surrounds everyone including the doctor. The healing effect is enhanced because the group is acting as one unit, with one faith.
3. The doctors initiate the actual Qigong healing by bringing divine healing energy to each individual patient.
4. The patients are taught how to easily follow Medical Qigong exercises and meditations, practicing them over and over again.

When a patient enters a Qigong hospital in China, they are diagnosed by a doctor and then assigned a specific Qigong class for a twenty-four day treatment period. The patient spends eight hours a day practicing Qigong without television, newspaper, or telephone. This is required to help the patient avoid regression into a previously established belief structure or subconscious pattern. Those who are able, practice Qigong from a standing posture. Other patients with limited mobility practice Qigong sitting or while lying in bed. After the twenty-four day treatment program is over, the patient is again diagnosed by a Qigong doctor. The diagnoses is classified into one of four categories for statistical purposes.

1. The patient has been cured: symptoms have disappeared and appropriate instruments (e.g., EKG, ultrasound, etc.) register normal tissue.
2. The treatment has been very effective: symptoms have almost disappeared and allopathic tests indicate great improvement.
3. The treatment has been effective, in that the patient is now able to eat, sleep, and feel good.
4. The treatment has been noneffective: there has been no change, or the condition has worsened.

PREPARING THE SELF TO TREAT THE PATIENT

This section prepares the Medical Qigong doctor to treat patients. The "preparation" sets the energetic ambiance for the clinical treatment and secures the foundation for dispersing pathogens. The preparation includes: The One through Ten Meditation, Creating a Sacred Healing Space, The Divine Hook-Up, Rooting to Prevent Energetic Shock, and The Energetic Circle Drawing Pattern (Figure 26.2).

THE ONE THROUGH TEN MEDITATION

The following is called the One through Ten Meditation and is used to prepare the Qigong doctor for clinical work. It allows the Qigong doctor to relax, sink, and root the mind. This meditation allows the doctor to extend his or her energetic field before connecting with the divine. This meditation is used to create a sacred healing space and is taught in a rhyming one through ten counting format, described as follows.

1. One Is Fun, therefore take pleasure in your work. Imagine a smile melting down the front of your body like warm oil, melting all stress and tension into the Earth. A second smile melts down the back of your body, dissolving all stress and tension down into the Earth. A third and final smile melts down the center of your head, relaxing all thoughts, judgments and feelings, and flows down your shoulders and arms and out your hands. The melting continues to flow down the center of your torso, like warm oil, melting all emotional blocks and tension, then flows down your legs and into the ground. At this point your mind and body should feel content, relaxed, and peaceful.
2. Two Is Shoe, thus imagine your feet melting into the Earth, like ice melting on a hot side-


The Qigong Doctor's Energetic Preparation for Clinical Therapy
1. The One through Ten Meditation
2. Creating a Sacred Healing Space
3. The Divine Hook-Up
4. Rooting to Prevent Energetic Shock
5. The Energetic Circle Drawing Pattern

Figure 26.2. The Qigong Doctor's Preparation for Treating the Patient

walk. The energy of the feet fuses with the Earth, melting in five directions (forward, backward, right, left, and down). This connects your mind and body with Earth energy.

3. Three Is Tree, therefore feel yourself extending tree-roots twice your body's height deep into the ground. The roots expand in five directions (forward, backward, right, left, and down), securing your rooting and connection with the Earth energy.
4. Four Is Core, thus imagine your roots extending deep into the core of the planet. The Earth energy flows into these roots, ascending up the legs, spine, over your head, down the chest, and enters your Lower Dantian. This action allows you to draw Earth energy into your body and circulate it through the Microcosmic Orbit. A solid connection to the Earth roots your physical, mental, emotional, and spiritual energies, and fills up your Lower Dantian with Earth energy.
5. Five Is Alive, therefore feel the Earth energy building up within your Lower Dantian. The energy increases to the point that your Dantian can no longer contain its power. It rushes up the center of your chest like a mighty river, dividing into two streams which flow out each palm into the earth. This action releases and emits the energy stored within your Lower Dantian.
6. Six Is Thick, thus imagine the room or environment where you are standing being filled with energy. This energy becomes so thick, it is as if you are submerged under water. This fuses the environmental energy with your energy, and the Earth's energy into one dynamic field of energy.
7. Seven Is Heaven, therefore allow your Baihui point to open up and draw in the divine healing white light into your Upper Dantian. Let the divine light fill your head and the entire Upper Dantian area till it floods and shines down from the Upper Dantian into your chest, filling up the entire Middle Dantian. Finally, the light shines down from the Middle Dantian filling up the lower abdominal area and the entire Lower Dantian. This light connects you with the Heavenly healing white light energy from the divine, filling up all three Dantians and your Taiji Pole. Thus Heavenly and Earthly energies fuse within your body.
8. Eight Is Open the Gates, therefore imagine opening every pore on your surface tissues, and begin to draw the environmental energy into your Taiji Pole upon inhalation. Upon exhalation imagine your center core vibrating and glowing like a neon light. This visualization energizes your center core, harmonizes your energy and breath, and prepares you for Qi and Shen (energy and light) projection.
9. Nine Is Shine, therefore imagine that your center core becomes completely full of energy and overflows by shining (from the Taiji Pole outward) through your pores until it fills up the entire room, like a bright phosphorus flare. This visualization fuses Heaven Qi, Earth Qi, and Man's Qi with the external clinical environment.

Draw the fused energy from the left back to the physical body collection point and then to the energy body collection point. Allow the four balls of fused energy to spiral around the cauldron. Let them increase in intensity and speed, going faster and faster, until they blend in the middle of the cauldron forming the pearl.

9. Feel any residual energy spiral through the pakuas and fuse together into the cauldron, connecting with the brilliant pearl of white light. Feel the colors blend and fuse. This is where the alchemical process comes to life. At any time during the Fusion practice, if you feel the pearl you are working with is lost or diminished simply become aware of the pakuas spiraling into the center of the cauldron.
10. Once you feel the form of the pearl you can simpy fuse the energy from inside of the energy body out to the physical and out to the universe and back and there is no need to be aware of the different color.



***Fig. 6.33** Four fused energy balls spiral on top of the cauldron, forming one energy pearl.*

Do as above, only the colors are changed and fuse from the energy body to physical body, to the universe and back as Four Balls, spiraling faster and fuse into One Pearl.

10. Ten Is Begin, with all things now in order, you are physically, mentally, emotionally, energetically, and spiritually in harmony, with your body, the Heavenly energy, and Earthly energy. You can now begin treating patients.

CREATING A SACRED HEALING SPACE

After completing the preparation, the Qigong doctor creates a sacred healing space in which to treat patients. Creating the sacred healing space allows the doctor and patients to interact in a safe environment without outside distractions.

The Qigong clinic should be a place of complete sanctuary, a consecrated place of refuge, where the patient feels safe, warm, and cared for (spiritually, emotionally, mentally, energetically, and physically). The patient should experience the peaceful ambiance of the treatment room as being enveloped in unconditional love and security.

To create the sacred healing space, the Qigong doctor performs the divine hook-up. Only after completing the divine hook-up should the Qigong doctor treat his or her patients.

THE DIVINE HOOK-UP

Once the doctor has established energetic grounding, the next step in establishing a clinical environment is to connect with his or her spiritual center through the divine hook-up. From this spiritual center the Qigong doctor observes the patient, void of personal thoughts, feelings, and judgments. This spiritual state of open receptivity allows patients to feel secure and to release their guarded emotions. Lacking a safe environment, patients may feel the need to repress emotions or to be distracted from experiencing and letting go of the original trauma.

The Qigong doctor, once healing has begun, enters into a state of "oneness" with the patient and the divine, in which the doctor's will and intention envelops and fuses together with the divine will and wisdom. Both doctor and patient begin to communicate through deep subconscious interactions. The doctor's success or effectiveness as a Qigong healer depends on a willingness and ability to connect with the patient and the divine healing light. Drawing from this interpersonal communication with the patient, and the deep spiritual connection with the divine, the doctor begins the treatment.

According to Dr. Meng Xian Tong of the Beijing Chengjian Integrated Traditional Chinese Medicine and Western Medicine Experts Clinic, when Qigong doctors perform the divine hook-up, they increase their own body's Righteous Qi, which then extends the energetic Message encoded in their Qi into the patient's body. The doctor's Righteous Qi is then absorbed by the patient's body and fused together with his or her Qi. This fusion empowers the patient to heal his or her disease.

Before contact with any patient the doctor first connects with the divine to purify and stabilize, not only him or herself, but also the treatment room (with a constant flow of Heavenly Qi pouring into the room). This divine hook-up enables the Qigong doctor to not only establish a sacred healing space, but also to access both spiritual insights and divine healing power.

ROOTING THE DIVINE HEALING LIGHT

Rooting the divine healing light is accomplished by visualizing a beam of healing light (the doctor can also choose specific colors) streaming into his or her body via the Baihui and Sishencong points (at the top of the head), and entering into the Taiji Pole. The doctor holds this frequency until the divine healing light becomes rooted or "anchored" within the Lower Dantian.

Next, the doctor brings the healing light vibration up the Taiji Pole to energize each Dantian until the healing light infuses and harmonizes all of the body's tissues. As the doctor feels the healing light reach the Middle Dantian, he or she visualizes the light intertwining with the "bridge of light," which connects the doctor's Heart (Middle Dantian), throat and Yintang (Upper Dantian) areas together. This energetic connection fuses at the Upper Dantian, becoming one unified cord. The healing light is then stored within the doctor's body and released during Qi emission.

USING THREE DIVINE INVOCATIONS

To assist the doctor in rooting the divine healing light, I encourage my students to begin each treatment with a small prayer and three invocations, for example:



Figure 26.3. As the divine healing Qi absorbs into his or her body, the Qigong doctor expands this field to envelop the entire treatment room.

1. "Lord God, fill me with your Holy Spirit and divine healing power. Increase my skill, power, knowledge, and wisdom and use me for Your Glory." The first invocation connects the doctor to the healing energy of the divine and roots the doctor deep into the Earth. This prevents the patient's pathogenic Qi from entering into and contaminating the doctor's body.
2. "Fill this room with your Holy presence and healing virtue, and let your Glory shine through me into this room." This second invocation connects the doctor and the treatment room to the divine and secures a sacred healing space (or sanctuary) for the patient. It also establishes an expansive divine energetic field by causing the doctor's Wei Qi field to overflow with divine healing light, filling the treatment room. This divine energetic field produces a dynamic field of healing energy (Figure 26.3).
3. "I lift (the doctor will mention the patient's name) before Your Holy Presence, and ask that you may heal these wounds and free him or her from these chains of despair, agony and disease. Thank you, God. Amen." After this final invocation, the doctor envelops the patient with an energetic bubble of light and love.

Next, the doctor roots the patient's energetic bubble deep into the Earth, and creates an energetic vortex underneath the patient. The energetic vortex will spiral clockwise, deep into the center of the Earth. This energetic rooting technique is practiced to purge and drain the patient's Toxic Qi into the Earth, where it is cleansed and then recycled back into the patient's body.

ROOTING TO PREVENT ENERGETIC SHOCK

Rooting (sometimes called "energetic grounding") is an important technique used by the Qigong doctors to establish and maintain a firm physical, mental, emotional, energetic, and spiritual connection to the Earth. Connecting to the Earth is essential to prevent energetic shock (a jolt of energy which flows from the patient into the doctor's body), which can result in the doctor ab-



Figure 26.4. The Qigong doctor envelops the patient in an energetic bubble (or healing circle) before beginning the treatment.

sorbing the patient's energetic pathogenic disease. To prevent energetic shock from happening, Qigong doctors go through several steps to prepare themselves and the clinical environment before treating patients. Energetic rooting is utilized in all phases of meditation and allows doctors to maintain a strong physical connection to the Earth. It is especially used when the doctor is absorbing and emitting environmental and universal energy.

- From a Wuji posture, imagine an energetic cord extending from your Lower Dantian, down the Taiji Pole and out the Huiyin point (at the base of the spine) deep into the center of the Earth. This energetic cord will root your energy into the Earth. It is also affected and maintained by your will and intention. The energetic cord follows the doctor's movements smoothly and easily.
- If the patient is lying, sitting, or standing in front of you, extend your energy to envelop the patient within an energetic cocoon called "energetic circle drawing."
- Imagine extending an energetic cord from the patient's Lower Dantian through this energetic cocoon, to root the patient's body deep into the Earth. This process energetically grounds the patient's body, mind, emotion, and spirit.

THE ENERGETIC CIRCLE DRAWING PATTERN

Once the divine hook-up is completed, the doctor grounds the patient by drawing an energetic circle around the patient's body. This is used to charge the patient's energy field. This energetic projection also roots the doctor's intention around the patient and strengthens the doctor's concentration. This circular field changes the patient's static field to a divine dynamic field and enables the Qigong doctor's energy to enter the patient's body with ease.

The enveloping of the patient's body allows the patient's body and energetic fields to become even more accessible to the Qigong doctor, while keeping the patient's pathogens isolated from the doctor's body (Figure 26.4). As the doctor steps into the energetic bubble, he or she is able to treat the patient's tissues, feeling absorbed and enveloped within the Messages expressed from the patient's energetic fields.

The energetic bubble is created by emitting Qi towards the patient, and enveloping and circle wrapping the patient in a clockwise energetic rotation. This energetic bubble forms a shield, maintaining protection for the patient and the doctor. Next, the doctor creates an anchoring line to root the patient's energetic field deep into the ground. Finally, the doctor creates an energetic vortex (spiraling in a clockwise direction) underneath the patient, to pull any dispersed pathogens deep into the Earth (this helps when the doctor is dredging and purging the patient's energetic fields).

USING THE ENERGETIC CIRCLE DRAWING PATTERN TO PURGE PATHOGENS

The energetic circle drawing pattern helps to facilitate energetic cleansing. Energetic purging facilitates the absorption of Clear Qi and also reduces the risk of contamination within the body's channels and collaterals by expelling energetic toxins and other pathogenic factors.

After creating the energetic circle, the doctor begins using dredging and purging techniques to expel pathogens from the patient's body. Next, the doctor treats the patient with tonification and regulating techniques, ending the treatment by closing the diseased area and sealing the patient's three energetic fields (three Wei Qi fields). This ending technique will securely close the energetic holes in the patient's outer field of Wei Qi (see Chapter 13). Without this sealing, the healing process is hindered due to the patient's Qi having a tendency to leak or disperse itself (even after tonification). Once the sealing is completed, any Excess Qi will be evenly distributed throughout the patient's body, establishing a Yin and Yang balance within the visceral organs.

USING THE ENERGETIC CIRCLE DRAWING PATTERN TO PURGE TOXIC HEAT

Before treating patients who have received radiation or chemotherapy, the Qigong doctor should wrap the patient with an energetic bubble and then purge the Toxic Heat from the patient's body. The Toxic Heat is dispersed into the energetic vortex created under the patient's body, and then released deep into the Earth. The Qigong doctor can then step into the energetic bubble and begin combing, dredging and purging the patient's tissues.

USING THE ENERGETIC CIRCLE DRAWING PATTERN TO PURGE TOXIC COLD

When using the circle drawing method to purge pathogenic Cold, the doctor stands outside of the energetic bubble, and extends energy deep into the patient's Taiji Pole. Once the doctor feels the patient's center core Qi, he or she draws the pathogenic Cold or Hot energy out from the patient's tissues (in all directions), filling the energetic bubble. The doctor, standing outside the energetic bubble, observing the patient's energetic field, waits for an energetic shift which is immediately followed by Toxic Cold (or Hot) Qi filling up the energetic bubble. Once this occurs, the Qigong doctor must drain the pathogenic Cold (or Hot) Qi down into the Earth to rid the patient of the Toxic Qi.

TREATING THE PATIENT

After the Qigong doctor has "circle wrapped" the patient, the treatment begins. First, the doctor dredges the patient's external energetic fields, channels and collaterals (from head to feet). The doctor senses the patient's Qi with his or her hands, changing the depth of penetration of the touch by extending intention deeper into the patient's tissues. Once the patient's pathogenic Qi has been reached, the doctor feels various energetic sensations (vibration, warmth, thickness, etc.) and removes any pathogenic energy from around the patient's body.

The doctor continues the treatment by extending his or her intention deep into the patient's body, purging and dispersing the toxic pathogens from out of the patient's internal organs and channels. It is usually during this deep internal purging that the patient experiences profound emotional discharges, observes flashes of light, patterns of colors, see visions, or relives deep seated past emotional traumas. This purging releases toxic emotions which are generally the cause or contributing factor to the patient's disease.


Treating the Patient
1. Use Energetic Circle Drawing to Purge Hot and Cold Pathogens.
2. Dredge and Purge the Patient's Body.
3. Perform Energetic Diagnosis.
4. Find, Locate, Detach, andRemove Energetic Cords.
5. Purge, Tonify and Regulate the Patient's Body.
6. Dispose of Pathogenic Toxins.

Figure 26.5. The Different Steps Involved in Treating a Patient

After the patient has been sufficiently purged and cleansed of pathogenic energy, the Qigong doctor begins to tonify the patient's internal organs, channels, collaterals, and Righteous Qi. This is done to help the patient build a stronger immune system, and fight or avoid any future complications caused by an Excess or Deficient internal organ condition (Figure 26.5).

DREDGING AND PURGING TECHNIQUES

When treating a patient, the doctor purges an internal organ and dredges a channel. The technique of dredging is a particular type of purging method. The energetic circle drawing techniques are always performed with dredging techniques (using the pulling and stroking methods of energy manipulation), to drain the energy into the Earth. These techniques can be initiated with the patients either sitting, standing, or lying.

It should also be noted that the diseased area of a patient's body must be thoroughly dredged and prepared before any kind of tonification or energizing is performed. This technique is similar to a Western doctor cleaning a wound before operating.

If the Qigong doctor does not dredge and purge the pathogens from the patient's body before treating, the patient can suffer adverse reactions when the doctor's clean energy fuses with the patient's Turbid Qi.

DREDGING AND PURGING THE PATIENT

There are two stages of clinical purgation which are described as follows.

1. The doctor dredges and purges the surface pathogens from the patient's body. The doctor moves to the right lateral side of the patient's body and energetically combs the patient's body from head to toes using the Tiger Kneading and/or Extended Fan Palm techniques (in this particular example the patient is lying supine on a treatment table). The combing technique is performed to energetically evaluate the patient's reaction to the doctor's emitted Qi, while dredging the patient's three energetic fields of Wei Qi.
2. The doctor purges from the bottom of the patient's feet. The Qigong doctor stands by the patient's feet and continues to dredge the patient's body by energetically combing the patient from head to toes. This action further purges the patient's body of pathogenic energy.

ENERGETIC DIAGNOSIS

After performing the clinical purgation, the Qigong doctor begins the energetic diagnosis. Some examples of energetic diagnosis are described as follows.

- The doctor can begin energetic diagnosis by first connecting with patient's heels (either by touching or not touching). This particular method and approach to diagnosing allows the Qigong doctor to energetically connect with the patient's inner-fascia. It is through this connection that the Qigong doctor feels the energetic flow of Qi moving through the patient's internal organs. By extending energy from the patient's heels up to the head (like a rippling ocean wave or sonar), the doctor can "listen" for obstructions or deviations of Qi flow.

- Next, the doctor can use the Flat Palm diagnosing technique to scan the patient's entire body for any Excess or Deficient areas within the patient's Wei Qi fields. This second type of diagnosis serves to verify the obstructions or deviations of Qi flow that the doctor discovered while first connecting with the patient's heels.

PURGING, TONIFYING AND REGULATING THE PATIENT'S BODY

After diagnosing the patient's body, the Qigong Doctor purges, tonifies, or regulates the energetic fields, channels, tissues, organs, and organ systems, according to the etiology and prognosis of the disease.

While dredging and purging the patient's body, the Qigong doctor may discover several energetic cords attached to the patient's tissues and internal organs. These energetic cords may sometimes contribute to the cause of the disease.

UNDERSTANDING THE BODY'S ENERGETIC CORDS

The human body attaches, extends, absorbs, and collects energetic cords. The size and shape of these cords can be big, small, thick, or thin, depending on the amount of emotion invested in their attachment. These cords are located within the Three Dantians and Chakra Gates, and form the spiritual, emotional, mental, and physical connection of the patient to the outside world. Generally, what makes the patient sick is not his or her genetic predisposition, but the negative, co-dependent bonds the patient creates in his or her relationship with others. It is the spiritual, emotional, mental, and physical reactions to these relationships that either promote health or disease. Energetic cords are also formed towards objects, pets and places that have special sentimental or emotional value (be they positive or negative) to the patient. Energetic cords are also sometimes used to feed the formation of the preexisting energetic clusters and cysts, which later transform into the patients' diseases.

Energetic cords are the psychophysical connection between what the patient feels, believes and knows to be true; they represent the connection to the patient's personal reality. This does not mean that the patient's reality is valid, only that the patient has come to believe it to be true. By removing these cords an energetic shift is initiated, allowing the patient to reprogram his or her feelings, thinking processes, and behavior, by becoming proactive instead of reactive. Energetic cords are full of light and energy and can be categorized into two distinct divisions: prenatal (congenital) and postnatal (acquired) energetic cords.

- Prenatal Energetic Cords originate in the fetus, when the baby is still in the womb. They form the strong congenital attachment and permanent bond the child has with the mother and father. Because of the mother's energetic/ spiritual connection with her egg, and the father's energetic/spiritual connection with his sperm, when the egg and sperm unite, the energetic cords of each parent fuse together with the universal and environmental energy creating the energetic structure of the child. It is through the parents' energetic cords that inherited talents and defects are passed along to the infant.
- Postnatal Energetic Cords are acquired after the baby is born through interaction with siblings, relatives, and other individuals (in some cases animals or places are involved). These cords will either form the emotional attachments which can help the child through life by being a means of support, or set the foundation for disease by depleting the child of his or her life-force energy. They represent the emotional bonding (positive or destructive) inherent within each one of us.

In a clinical environment, the attachment of these cords (prenatal and postnatal) will affect the healing relationship of both the patient and the doctor.

- The Patient's Energetic Cords are still connected to the patient after the pathogenic Qi has been removed from the patient's body. These small cords are the energetic attachments to part of the patient's old belief structure (which created the disease or emotional attachment). Although there is still an energetic connection to the departed pathogenic Qi, these energetic cords will soon disperse once the patient's Creative Subconscious is able to reprogram the individual's belief structures. Only then can the physical body, as well as the mental, emotional and spiritual energetic Wei Qi fields maintain the new energetic pattern. This new belief structure creates an energetic transformation, allowing the patient to release his or her hold on to the painful past and begin to heal. The patient is encouraged to emotionally disconnect from old emotional belief structures through creative visualization, and by affirming the new belief structure. Through affirmation and positive emotional, spiritual visualizations, the patient is able to "sever" any energetic cords that connect to the pain and disease.

- Energetic Cords between the doctor and patient are formed during healing sessions. These new energetic cords are passed back and forth between the Qigong doctor and the patient. Sometimes this occurs without either party being aware of this energetic connection. Usually, as the doctor steps away from the patient and reconnects with the divine, an energetic purging is automatically initiated, freeing the doctor from the attachment to the patient's energetic cords. If, however, there has been an emotional connection between the doctor and the patient, these cords can remain attached even when the patient leaves the office.

The doctor should make every effort to disconnect from the emotional attachment of the patient's cords, otherwise the increased energetic pull on the doctor's center will affect the doctor on every level. Staying connected to the patient through an energetic cord can cause not only emotional, but physical and spiritual influences on the doctor. Any remaining cord can be used by the patient to unconsciously project thoughts and feelings onto the doctor. This can result in the doctor being depleted of energy either through direct draining of his or her Qi, or through obsessing about the patient's well-being, long after the treatment has ended. The drain of the energetic cord can lead to either clinical "burnout" from absorbing excessive negative emotions, or deep emotional bonding, which can lead to unethical sexual indiscretions.

FINDING, DETACHING, AND REMOVING ENERGETIC CORDS

Energetic cords manifest through their effects on behavior and emotional responses of the patient. They are relationship based patterns, located within the patient's tissues. Energetic based patterns can evoke certain reoccurring emotional responses, such as attractions, addictions, etc.

1. To assist the patients in removing the toxic energetic cords, the Qigong doctor must first locate the cords.
    a. Through the emission of Qi, the doctor may elicit (from the patient) either an attraction or repulsion response. This response occurs when certain memories are stimulated within the patient's body, indicating that there is an energetic cord attached within the tissues.
    - The attraction response causes the patients to experience deep emotional release through laughing, crying, shouting, etc.
    - The repulsion response causes a physical jerking of the patient's muscles, anywhere within the patient's body (observed by the wincing and grimacing of the patient's face). Often the patient will "Shen-out" (emotionally and spiritually leave their body) to avoid feeling the painful surfacing emotions.

    b. The doctor locates the origin and entry point of the energetic cord through Flat Palm detection. The root of an energetic cord acts as an open receptor to a specific psychophysical problem that the patient is experiencing. When stimulated, these cords may manifest physical symptoms such as nausea, hot flashes, vertigo, dizziness, headache, and muscle contractions. The patient may also experience emotional reactions such as momentary panic, fear and so on.

2. Before detaching the energetic cords, the doctor requests the patient's permission to do so either verbally, or silently through mind to mind communication.
3. To remove the energetic cord, the doctor dredges and purges the patient's body, while silently communicating through the Creative Subconscious mind. The doctor encourages the patient to let go of, and fully release, the toxic cords along with the memories that sustain them. To ensure against their recreation, the doctor discusses with the patient any images, emotions or sensations that surfaced during the removal of these cords; through this process the doctor brings the patient's conscious awareness of the fears, pain and major unresolved issues that resulted in the disease. The patient thus gains a clear identification of his or her traumas to facilitate the reprogramming of his or her dysfunctional relationships through affirmations and creative visualizations.

If the patient is not ready for such a transition (feeling scared, unprepared, undeserving, etc.), his or her subconscious mind will sabotage any effort made in that direction, and the energetic cord, emotional cluster and all energetic attachments to the disease will be recreated and reintegrated. It is important in cases such as these, that the Qigong doctor refer the patient out to a psychotherapist for additional support.

In Western society, the Twelve Step Programs (such as Alcoholics Anonymous) are but one example of a pattern based reprogramming of energetic cord attachments. Alcohol and Narcotics Anonymous groups, for example, help detach energetic cords toward illegal substances, whereas, CODA meetings help reprogram the energetic cord attachments to co-dependant relationships. In a codependent relationship, both parties rely too heavily on one another, instead of being interdependent. One person usually dominates the other, as both parties base their self-esteem on the partner's approval, or disapproval, thus avoiding the personal responsibility of their own actions.

Energetic reprogramming encourages the participants to take responsibility for filling and replacing the energetic gap that the toxic cord has left with a connection and attachment to the divine, or "Higher Power."

DISPOSING OF PATHOGENIC TOXINS

One problem a doctor may confront when dredging and purging is where to dispose of the patient's toxic and noxious Qi. To maintain a clean treatment room it is essential for this pathogenic energy to be disposed of properly. This will keep both the doctor and other patients from contamination. If the doctor's Qi becomes toxic or contaminated during treatment, this turbid energy may be transmitted to other patients.

Because the patient is in a state of energetic shock (after the therapy), attention must be placed on the patient avoiding contact with the contaminated Qi. Otherwise, there is a possibility of the diseased Qi returning into the patient's body via the energetic cords of attachment connected to the Toxic Qi.

Imagination and visualization are two of the most powerful and widely used techniques employed in healing today for disposing of Toxic Qi. Since we experience reality through creative imagination, pictures, words, and feelings are extremely powerful techniques which can be used to restructure our physical, mental, emotional, energetic, and spiritual foundations. This also holds true for the disposing of the patients' pathogenic Qi.

There are several methods for disposing of the patients' pathogenic energy in the treatment room. These methods include purification by either sound, light, or the Five Elements, in conjunction with disposing of the toxic energy through the energetic vortex.

PURIFICATION BY SOUND AND LIGHT

- Sound penetrates any substance and causes profound shifts in energy, quickly breaking up clusters of stagnant energy. Some examples of sounds used for purifying the treatment room include: music, toning, chanting, singing, wind chimes, gongs, singing bowls, bells, drumming, and clapping the hands.

- Light can be used to cleanse and purify the treatment room of toxic energy, due to the radiant heat emanating from the light source. Some examples of light being used to purify the clinic include: exposure to sunlight, candles, and imagining the divine healing light incinerating any energetic toxic debris.

PURIFICATION BY THE FIVE ELEMENTS

Some Qigong doctors utilize the energy stored within the Five Elements to cleanse the treatment room of toxic debris. This works best in conjunction with the light and sound purification methods. When using one or more of the elements, it is best to consider how much debris has accumulated from the previous treatment and choose accordingly.

1. Dispose of the Toxic Qi through Fire. By burning fire-water (alcohol with salt), lighting a candle, or releasing the Toxic Qi into the Earth's molten core, Toxic Qi can be transformed and purified.
    - To create fire-water, the Qigong doctor places a small amount of alcohol in a round dish and sprinkles a cone of salt (or camphor) in the center of the dish. Next, the doctor lights the salt and allows the smoke to purge the treatment room, making sure that the doors and windows are open to secure clean ventilation.
    - Other Qigong doctors may imagine the center of the Earth as an incinerator. This image is used to purge the patient's Toxic Qi by directing it to the Earth's molten core. Once the patient's Toxic Qi is incinerated (at the speed of thought), the transformed / purified energy is reabsorbed back into the patient's body.
2. Dispose of the Toxic Qi through Water. Water can also be used to absorb toxic energy and for healing and purifying. Some examples of water usages include: Holy Water and salt water. Some doctors use a container of salt water as their disposal unit for the patient's Toxic Qi (Figure 26.6). Once the patient's toxic energy reaches the container of salt water (usually placed underneath the treatment table), it is immediately absorbed due to the molecular structure of the salt crystals. Sometimes it is advisable for the Qigong doctor (after a full day at the clinic, or at the end of a busy week) to submerge him or herself in a baking soda or take an Epsom salt bath in order to cleanse and purify the body.
3. Dispose of the Toxic Qi through Wind / Air. Wind and air can be used to purify the room of toxic energy. Some examples of this include open air ventilation along with the placement of indoor plants.
4. Dispose of the Toxic Qi through Divine Healing Light. Some doctors dispose of the patient's pathogens into the air, where it is immediately incinerated by a divine healing light. Because of the preestablished divine healing field of energy, once the patient's toxic energy leaves the doctor's hand, it is immediately absorbed by the divine healing light and is instantly transformed into purified energy and reabsorbed back into the patient's body.
5. Dispose of the Toxic Qi through Wood. Wood can also be used to purge toxic energy from the treatment room. Some examples of the Wood Element used to cleanse the room are: the burning of incense or herbs such as myrrh, frankincense, cedar, sage (an old American Indian method), sandalwood or camphor.
6. Dispose of the Toxic Qi through the Earth. Certain stones can be used in the clinic because of their ability to absorb Toxic Qi. Strategically placed in the clinic, these Earth Elements can be used as a natural filtering device. Some examples of this include: amethyst, salt, clear and colored quartz, as well as many other minerals or gemstones. These crystals require cleaning at the end of each treatment day to dispose of the toxic Qi they have absorbed, and should be cleansed by placing them in salt water till they are clean, or burying them in the ground for three days.



Figure 26.6. One example of a Qigong doctor using a rubber acupuncture doll for treating and disposing of the patient's toxic energy into salt water.

MEDICAL QIGONG TREATMENTS

The following is a clinical procedure that a Medical Qigong doctor will use when treating a patient. The clinical procedure known as the "preparation" remains the same for all Medical Qigong treatments (i.e., the hook-up, dredging and purging the patient, as well as energetic diagnosing). However, the initial treatment will vary depending on the patient's constitution, disease, and personal goals.

After scanning the patient the doctor has a solid understanding of which areas or organs in the patient's body are currently in a state of Excess or Deficiency. The doctor then chooses which area to begin dredging and purging in accordance with the treatment plan. Only after purging all areas of Excess should the doctor then move to tonifying those areas that are Deficient.

TONIFYING A PATIENT'S BODY

After completing the diagnosis, if you have determined that the patient's body is not in an Excess condition, but is instead constitutionally weak or depleted due to Kidney exhaustion, the treatment may be continued as follows.

1. Begin by extending energy through the patient's Yongquan Kd-1 point at the bottom of each foot. Imagine that the Qi is ascending up the patient's legs, via the Yin channels, filling the Lower Dantian, Kidneys, thorax and spinal column into the brain. Hold this position for several breaths, then proceed to the next area.
2. Physically embrace the area of the patient's ankle with one palm, while the other palm embraces the Kd-1 point on the same foot. Start with the right ankle first and then the


Universal Body
Physical Body
Energy Body
S
N
1
2
3
4
Universal Energy/Force

__Fig. 6.34__ Fuse inner positive energy with universal energy through turning the Dial-2.


Universal Body
Physical Body
Energy Body
S
N
1
2
3
4
Universal Energy/Force

__Fig. 6.35__ Fuse the Universe force back to the body and energy body.

left. Project energy into the foot and ankle, by holding the mind's intention on that specific area for several breaths, then begin circling the energy up the Yin channels and down the Yang channels. Hold this position for several breaths, then proceed to the next area.

3. Energize each of the patient's knees (back and sides) by holding the mind's intention on those specific areas for several breaths, then connect each knee to the Yongquan Kd-1 point at the bottom of each foot (the right foot first, then the left). Connect and emit energy into the bottom of each foot to the knee, circling the Qi up the Yin channels and down the Yang channels. Hold this position for several breaths, then proceed to the next area.
4. Energize each of the patient's hips, by holding the mind's intention on that specific area for several breaths, then connect each hip to the Yongquan Kd-1 point at the bottom of each foot (right first, then the left). Connect and project energy into the bottom of each foot to the hips, circling the Qi up the Yin Channels and down the Yang Channels. Hold for several breaths, then proceed to the next area.
5. Energize the patient's Lower Dantian by holding the mind's intention on that specific area for several breaths, allowing the Qi to completely fill up the energetic chamber. Place your left hand on the patient's Mingmen GV-4 point. Your right hand is placed on the patient's navel (CV-8) with your fingers extending down to the patient's Qihai CV-6 point. Mentally connect the Lower Dantian with both Yongquan Kd-1 points on the bottom of the patient's feet and imagine the energy simultaneously traveling down the outside of both legs into the feet. Imagine the energy from the feet continuing to travel along the inside of both legs back into the patient's Lower Dantian area. Hold this intention for several breaths, then proceed to the next area.
6. Energize the patient's Yellow Court by holding the mind's intention there for several breaths. Your left hand is placed on the Jizhong GV-6 point, your right hand should be placed on the Juiwei CV-15 point. Mentally connect the Yellow Court with the patient's Lower Dantian, allowing this energy to connect and fuse both areas. Hold this intention for several breaths, then proceed to the next area.
7. Energize the patient's Middle Dantian by holding the mind's intention there for several breaths. Place your left hand on the Shendao GV-11 point, while your right hand is placed on the Shanzhong CV-17 point. Mentally connect the Middle Dantian area with the patient's Lower Dantian. Hold this position for several breaths, then proceed to the next area.
8. Energize the patient's throat area by holding the mind's intention on that specific area for several breaths. Your left hand is placed on the Dazhui GV-14 point, while your right hand is placed on the Tiantu CV-22 point. Mentally connect the throat area to the Middle Dantian area, then to the patient's Lower Dantian. Hold this intention for several breaths, then proceed to the next area.
9. Energize the patient's Upper Dantian area by holding the mind's intention there for several breaths. Your left hand should be placed to stimulate the occipital region at the Naohu GV-17 point. Your right hand is simultaneously stimulating the Yintang (Third Eye) and Baihui (GV-20) areas. Mentally connect the Upper Dantian area to the Middle Dantian first, and then to the patient's Lower Dantian. Hold this intention for several breaths, then proceed to the next area.
10. Regulate the patient's Microcosmic Orbit, to balance the Heart Fire and Kidney Water energy. Remove your hands from the patient's body, yet still remain energetically connected through your intention. Having stepped away from the treatment table, continue treating the patient with external Qi emission, regulating the patient's Microcosmic Orbit (extending energy up the Governing Vessel and down the Conception Vessel). Hold this intention for several breaths, then proceed to the final step in the treatment.

11. Envelop and seal the patient's three external fields of Wei Qi by connecting the patient's body with the divine energetic field. Hold this intention for several breaths, then proceed to the "closure."
12. Disconnect yourself from the patient and close the healing session. Be sure to disconnect physically, mentally, emotionally, energetically, and spiritually from the patient by willfully detaching all energetic connections to the patient.
13. After disconnecting from the patient, center yourself, then regulate your own energetic fields to balance, recharge, and replenish any energetic depletion.
14. Finally, after you have completed centering yourself, finish the cleansing by washing your hands to purge any of the patient's lingering pathogens which may still be attached to your body.

GENERAL THERAPEUTIC TREATMENT

The following is an example of a clinical routine used in the Medical Qigong Clinic for "emotional purging." The following purging routine is separate from the previous clinical modalities for tonifying a patient. It is important to note that when treating a patient, the Qigong doctor usually purges the patient's Liver and Lungs before tonifying the Spleen and Kidneys.

After completing the diagnosis, if you have determined that the patient has both Excess and Deficient conditions, you may decide to continue the treatment as follow.

1. Begin by dredging, purging, and activating (energizing) the patient's Upper Dantian area to reconnect the patient to the divine, to activate the patient's spiritual/emotional presence.
    a. Start by purging the patient's Upper Dantian.
    b. Then regulate and energize the patient's Upper Dantian by performing a small Microcosmic Orbit within the patient's head.
    c. Finally energize the patient's Taiji Pole through the Baihui area.
2. Purge and dredge the patient's Lungs, to disperse the emotions of grief and despair caused by "rejection, betrayal, and abandonment issues" which are stored in the patient's Lungs.
    a. Start by dredging the patient's neck (trapezius, clavicle, and manubrium) of grief and despair. Begin by standing on the right side of the patient's body, and use the Kneading Tiger Palm and Dragon's Mouth Palm hand techniques (see Chapter 33) to pull the Toxic Qi from the patient's body. Switch from the right to the left side and continue purging.
    b. Then roll the patient's shoulders back to open the Lungs and to facilitate their purging of any deep seated grief. Start on the left Lung first. This area is responsible for storing the emotions related to the patient's mother.
    c. Next dredge the inside Yin Channels of the patient's left arm by using Qi Massage techniques (see Chapter 37).
    d. Regulate and treat the patient's body through "hand diagnosis and treatment" (based on energetic hand/body association, see Chapter 25) by focusing on the patient's left hand.
    e. Finally, begin the entire Lung purging procedure again, this time focusing the attention on the right side of the patient's body. This side reflects the patient's issues with his or her father.
3. Regulate and tonify the patient's Heart to calm the Spirit.
    a. Your left hand connects and extends energy deep into the patient's Shendao GV-11 point, the area in-between the patient's shoulder blades. Your right hand connects to the Shanzhong CV-17 point above the patient's Heart, purging emotional toxins.
    b. Finally, regulate the Heart by circulating Qi through the patient's upper Microcosmic Orbit (between patient's Upper and Middle Dantian). This reconnects the divine light emanating

from the Upper Dantian back with the spiritual emotions (unconditional love, devotion, etc.) stored within the upper chamber of the Heart (see Chapter 5).

4. Purge and dredge the patient's Yellow Court to rid the body of toxic emotions stored within the tissues of the Yellow Court. Your left hand remains secure on the patient's back, at the Shendao point to maintain contact with the Heart Qi. The patient's true feelings are stored within the Yellow Court and expressed through the patient's Heart. Place your right hand on patient's Juiwei CV-15 point, located below the patient's xiphoid process. Sometimes you may see images of the patient's past as traumas are released from the tissues.
5. Your left hand remains secure on the patient's back, at the Shendao point while your right hand purges the patient's Liver organ of anger and depression caused through the storing of "rejection, betrayal and abandonment issues." As you dredge the Liver's Hot toxic emotions from out of the patient's body, purge the pathogens out the patient's right Gall Bladder Channel.
6. Keep your left hand on the patient's back, at the Shendao point while you tonify and regulate the patient's Spleen with your right hand.
7. With your left hand on the patient's back, at the Shendao point, tonify and regulate the patient's Kidneys with your right hand.
8. Maintain contact with the patient's back, at the Shendao point, as your right hand connects with the patient's Mingmen (GV-4) area to regulate all three Dantians. This is initiated through the Microcosmic Orbit (extending energy up the Governing Vessel and down the Conception Vessel), to balance all of the patient's energetic reservoirs.
9. Then slowly remove your hands from the patient's body, but remain energetically connected through intention. Step away from the treatment table, as you continue to regulate the patient's Microcosmic Orbit. Hold this intention for several breaths, then proceed to end the treatment.
10. Envelop and seal the patient's three external fields of Wei Qi, by connecting the patient's body with the divine energetic field. Hold this intention for several breaths, then proceed to the "closure."
11. Disconnect physically, mentally, emotionally, and spiritually from the patient to close the healing session. It is important to shake or whip your palms to completely disconnect from the patient's energy. The shaking or whipping action frees the doctor from any energetic attachment which may have occurred while treating the patient.
12. After disconnecting from the patient, center yourself, then regulate your own energetic field. This balances, recharges, and replenishes any energetic depletion you may have suffered during the treatment session. If you are affected by any pathogenic Qi, immediately expel it from your body.
    a. Next, focus your attention on your Taiji Pole, imagining both the universal and environmental energy collecting, absorbing, and resonating deep within your Lower Dantian and center core. This image draws Qi into your body like a magnet, replenishing any energetic depletion you may have experienced. By placing the fingertips together in front of the Lower Dantian, you will further facilitate the replenishment of the energy.
    b. During this time the patient is allowed to continue relaxing on the treatment table and to slowly come out of the trance state induced by the treatment. The patient should then allow the Yuan Qi to settle back to its origin (the Lower Dantian), by relaxing and calming the mind, breathing, and posture. Instruct the patient not to wash the area that was treated for several hours because water absorbs some of the Qi that was projected into the diseased area.
13. Finally, wash your hands, using tepid water (hot water allows turbid Qi to enter the



Figure 26.7. As the patients practice their own individual Medical Qigong prescriptions, the Qigong doctor extends energy into the patients, helping to facilitate a stronger therapeutic reaction.

doctor's channels, cold water closes off the channels) to purge any of the patient's lingering pathogens.

ADJUSTING AND FORTIFYING THE PATIENT'S ENERGETIC GRIDS

At the end of the treatment the doctor regulates the patient's energetic fields by adjusting and fortifying the patient's energetic grids (the webbing within the patient's energetic fields). This keeps the patient's energy in harmony, allowing both his or her internal and external fields to operate at their maximum potential for health and healing.

The Qigong doctor adjusts and fortifies the patient's energetic grids, to initiate a permanent energetic transformation for healing within the patient's energetic fields, tissues, and cells. The body's energetic grids are responsible for tissue formation and for maintaining the production, growth, and development of energy. These grids are influenced by thoughts and emotions.

The creative subconscious mind maintains the body's energetic grid formations and causes the physical body to act (grow stronger or weaker) in accordance with the energetic "blueprint" encoded within the structure or webbing. After the Qigong doctor has changed, or corrected, the energetic grid, the patient is given Medical Qigong prescriptions (homework) in the form of visualizations and affirmation meditations, as well as Qigong exercises.

TREATING MULTIPLE PATIENTS

Once an energetic field in the treatment room is established, the patients can begin their individual Qigong regulations. The doctors position themselves according to the number of patients needing treatments; for example, one doctor may be positioned in front of several patients and extend Qi into the patients' energetic fields (Figure 26.7). The doctors' postures and energy extension varies according to their individual skill and energy projection level. It is important for Qigong



Figure 26.8. The Qigong doctors will position themselves back to back, in the center of a circle, in order to induce energetic movement within the multiple patients' tissues.

doctors to set the pace for treatment. The patients' rhythm is based on the pulse and vibration of the Qigong doctors.

In China, doctors usually rotate every fifteen minutes when treating patients. This prevents the doctors from fatiguing while allowing the patients to absorb new and fresh Qi every fifteen minutes.

If only one or two Qigong doctors are available when treating several patients, then the doctors will position themselves back to back in the middle of the room, with their patients surrounding them in a circle (Figure 26.8). After several minutes the doctors will slowly begin to rotate the center circle extending their energy, and treating each patient individually. The doctor's emitted Qi combines and synergizes with the patient's Qi to produce a much stronger energetic healing field.

By establishing a treatment room that facilitates the regulation of the patients' Qi, the treatments tend to become more effective with faster results. In China, patients are treated in a group treatment room environment three times every day (sunrise, sunset, plus one time before bed).

ENDING THE TREATMENT

When the treatment is over, encourage each patient to relax and then return the patients' Qi back to its origin (the Lower Dantian). The duration of the treatment time, and proper recuperation after Medical Qigong treatment will be addressed next.

DURATION OF TREATMENT TIME

The duration of treatment time varies according to each patient's disease, condition, constitution, and age. A long treatment is usually between twenty and thirty minutes and is generally performed on cancer patients, senior citizens, or for severe traumatic or chronic illnesses. A short treatment is generally between three to fifteen minutes and is usually administered for athletic sprains and ligament dislocations.

PROPER RECUPERATION AFTER MEDICAL QIGONG TREATMENT

Proper recuperation is very important for the replenishment of strength and energy after the treatment session (even after the patient's own prescription practice). This may include having the patient change his or her life activities. The patient must incorporate a balance of work and rest, and acquire regular healthy eating habits (with reasonable nutritional goals). Establishing adequate sleeping patterns is also necessary. Of equal importance is an open-minded positive attitude by the patient, for this reason, a supportive network can be invaluable.

After the Qigong treatment the patient is also encouraged to avoid cold showers, the consumption of alcohol, excessive sex, and recreational drugs. Also prohibited is anything that will emotionally shock the patient, as remaining in a quiet state of mind and spirit is essential.

CHAPTER 27

COMBINING MEDICAL QIGONG THERAPY WITH OTHER HEALING MODALITIES

COMBINING MEDICAL QIGONG THERAPY WITH TCM MODALITIES

Traditional Chinese Medical treatments in conjunction with clinical Qigong modalities are generally broken down into exclusive Medical Qigong Therapy, Medical Qigong and Chinese Massage Therapy, Medical Qigong and Acupuncture/Moxa Therapy, and Medical Qigong and Herbal Medicine Therapy.

EXCLUSIVE MEDICAL QIGONG THERAPY

Medical Qigong therapy can be administered by the Qigong doctor (Figure 27.1) to tonify and promote energy circulation or to sedate the body's energetic channels and collaterals. Qigong prescriptions can also be given for the patient to practice alone. Medical Qigong therapy by itself is excellent for the treatment of ailments such as:

- Insomnia
- Neurasthenia (Chronic Fatigue)
- Hypertension
- Stroke
- Acute abdominal pain
- Injuries to the nerves
- Hemopleura (Blood in the walls of the thorax and diaphragm, along the pleural space)
- Myopia
- Migraines
- Muscle atrophy
- Sprains
- Cancer
- Tumors
- Cysts

MEDICAL QIGONG AND CHINESE MASSAGE THERAPY

Medical Qigong therapy in conjunction with Chinese Massage therapy is a powerful form of combined clinical modalities (Figure 27.2). It enhances tissue response as well as the activation of psychophysical reactions within the body. These therapies can be combined to clear the joints before setting the bones (as in Jie Gu therapy), to purge and dredge the channels to adjust the Qi circulation before regulating the body's muscular system (as in Tui Na and Gua Sha therapies), or to disperse toxins before regulating the body's internal viscera



Figure 27.1. Medical Qigong Therapy



Figure 27.2. Medical Qigong Therapy with Chinese Tissue Regulation Therapy

(as in An Mo and Jing Point therapies). Qigong and Chinese Massage therapy are most commonly used in the treatments of patients with:

- Deep tissue obstruction
- Stiff muscles
- Frozen shoulder
- Low sensitivity to emitted energy

MEDICAL QIGONG AND ACUPUNCTURE/MOXA THERAPY

Acupuncture needles are inserted into the patient's body before the doctor extends Qi into the patient to facilitate healing (Figure 27.3). This also applies in the treatment of Moxa sticks in which the doctor extends energy into the patient through the burning herb. The combined energies (the Moxa heat and doctor's own Qi) initiates increased Qi flow within the patient's channels resulting in a stronger tonification. Moxa is especially beneficial in the treatment of arthritis. Qigong and Acupuncture therapy are combined in tonification or purgation treatment.

MEDICAL QIGONG AND HERBAL MEDICINE

Medical Qigong Therapy in combination with herbal therapies (or with pharmaceutical prescriptions) are becoming more popular. There is ample evidence that the combination of self-applied Medical Qigong therapy and drug therapy is far superior to that of drug therapy alone. In China, this data is reported in several studies of patients with hypertension as well as in cancer patients.

Medical Qigong therapy relaxes the body, promotes the flow of Qi, Blood, oxygen, and nutrients to all cells of the body, as well as promotes the removal of waste products from the cells. Medical Qigong also promotes drug uptake by the cells and tissues by means of increased microcirculation within the body's microcirculatory system. This increased Qi flow through the body's microcirculation nourishes diseased or stressed tissues.

One diagnostic herbal technique I observed at the Xi Yuan Hospital was performed by a Qigong doctor who absorbed into his body the effects of a specific medicine by touching the bottle that contained the herbs. He then extended energy to his patient and began absorbing the patient's Qi to see if the patient's body was affected by the herbal prescription (Figure 27.4).

The Qigong doctor is encouraged to prescribe herbs along with certain of the Medical Qigong exercises. If the Qigong doctor is not qualified to prescribe Chinese medical herbs, then a referral can be made to an acupuncturist/herbalist. The herbal prescriptions will vary according to the patient's condition, constitution and illness.



Figure 27.3. Medical Qigong Therapy with Acupuncture



Figure 27.4. A Qigong Doctor Testing the Efficacy of a Specific Herbal Medicine for his Patient

Qigong and herbal therapies are most commonly used in the treatments of:

- Tumors
- Stomach cancer
- Lung cancer
- Hepatitis
- AIDS
- Stroke

COMBINING MEDICAL QIGONG THERAPY WITH WESTERN MEDICAL MODALITIES

Traditional Chinese Medical Qigong serves as a powerful tool in aiding Western medical approaches in alleviating patients' suffering. Because of its emphasis on mental, emotional, energetic, and spiritual approaches to healing, Medical Qigong therapy has been successfully combined as a complementary source of medical treatment with the following Western professional approaches:

- Pediatrics
- Geriatrics
- Gynecology
- Neurology
- Psychology
- Oncology
- Surgery


Universal Body
Heart Energy
Physical Body
S Top
Energy Body
Liver Energy
Right
Left
Lung Energy
N
Kidney Energy
Universal Energy/Force
Universal Body
Physical Body
S
Top
Energy Body
Right
Left
N
1
2
3
4

Fig. 6.36 Fuse inner positive energy with universal energy through turning the Dial-3.


Universal Body
Heart Energy
Physical Body
S Top
Energy Body
Liver Energy
Right
Left
Lung Energy
N
Kidney Energy
Universal Energy/Force
Universal Body
Physical Body
S
Top
Energy Body
Right
Left
N
1
2
3
4

Fig. 6.37 Fuse the Universe force back to the body and energy body.

CHAPTER 28

PRECAUTIONS AND ETHICAL CONSIDERATIONS FOR THE QIGONG DOCTOR

AVOIDING ENERGETIC DEPLETION

Because Medical Qigong therapy consumes energy, as long as the Qigong doctor's quantity of energy is higher than that of the patient's, the doctor can transmit energy into the patient with no ill effect. If, however, the doctor is very tired or depleted and tries to treat a patient, the energy that the doctor is able to produce may become weaker than that of the patient.

It is important to note that energy currents flow from high to low (much like water). Therefore, the doctor may, if in a weakened state, absorb the Turbid Qi or disease energies from the patient. Any imbalance in the doctor's organ system can increase the doctor's vulnerability to foreign pathogens. These pathogenic sensations may also be transmitted into the body of healthy people, or other patients as well. Individuals who have not practiced Qigong, however, and whose energy circulation and channel points are not open, are not as prone to interference by these sensations. These individuals have a natural barrier, or to put it plainly, they are not sensitive to energetic fields of transmission and because of their denial system, cannot perceive energy sensations.

If the Qigong doctor already has a tendency towards a particular illness, exposure to pathogens may instigate or intensify the disease. If the doctor is suffering from any energetic Deficiencies, for example, the end result may be that the doctor performing the treatment may experience Qi deviations due to absorbing the patient's Toxic Qi. This means that more Qi and energy have been extended outside of the doctor's body than can be replenished, weakening the doctor's energetic constitution.

When treating patients the doctors receive and diagnose information from their Six Openings (also called the Six Windows of the Body). These Six Openings are described as follows:

- The eyes -- open for seeing energy patterns and colors,
- The ears -- open for hearing energy patterns and tones,
- The nose -- opens for smelling different odors,
- The tongue -- opens for tasting or flavor sensing,
- The body -- opens for energetic feeling sensations, and
- The Spirit (Heart/Mind) -- opens for energetic perceptions of emotions, thoughts, and spiritual insight.

While using the Six Openings for diagnosis, the doctor naturally depletes some life-force energy. Since all five organs (eyes, ears, nose, tongue, and body) are directed by the doctor's Spirit (Shen), the expenditure of energy is considerable. Any imbalance due to organ depletion will cause the doctor to absorb Turbid Qi from the patient. This Turbid Qi can move within the doctor's body causing Qi deviations, especially if it mixes with the doctor's Clear Qi.

1. If this happens within the doctor's Upper Dantian, the symptoms may include mental fatigue, dizziness, headaches, etc.
2. If this happens within the doctor's Middle Dantian, the symptoms may include emotional fatigue, discomfort in the Liver (hepatic region), etc.
3. If this happens within the doctor's Lower Dantian, the symptoms may include physical fatigue, cold in the extremities, discomfort in the lower abdomen, etc.

This is why Qigong doctors must constantly be refilling and rebalancing themselves energetically. It is important to note that if the Qigong doctor has indeed ingested the patient's pathogens, and Qi deviations have resulted, no Western doctor, acupuncturist, or herbalist can help him or her. Only the doctor with the Qi deviation (or with the help of another Qigong doctor) can change the Turbid Qi back to Clear Qi, by using divine energy and purging the body's Shen, Qi, and finally the Jing. This supports the doctor's Righteous Qi and fights the invasions of the patient's pathogens.

Emission of Qi should also be avoided if the doctor becomes sick, tired, hungry, overfed, deeply grieved, indignant, or drunk. Also, if the doctor is unable to stay in the present mind-frame he or she will inevitably fall asleep or "Shen out." To avoid this state of depletion, the Qigong doctor should:

- Cut back on the number of patients,
- Decrease treatment time—from 25 to 20 minutes maximum,
- Maintain a consistently healthy diet with supplements,
- Receive frequent exposure to fresh air and sunlight, and
- Perform the Microcosmic or other regulating Qi meditations in between patients.

Note: When treating patients with Medical Qigong therapy the doctor should never wear the color red. The color red is too hot and has a dispersing affect on Qi, which tends to scatter the body's energetic fields, distorting the Qigong doctor's Qi emission.

PREVENTING THE INVASION OF TURBID QI

When Turbid Qi enters the doctor's body, it interferes with normal Qi circulation, causing disorders in part of, or in all of the energy circulatory system. In mild cases, Qi may stagnate in a certain areas of the body (i.e., shoulder, arm, chest, or back), causing physical and mental symptoms.

- Physical symptoms may include: tingling, pain, cold, contraction, heaviness, soreness, and distention and stuffiness in the chest; and
- Mental symptoms may include: interference with mental activity, causing dizziness, headache, heaviness in the head, vexation, and restlessness.

In severe cases, the doctor may experience the same symptoms as the patient, but upon physical examination there is no verification of any existing disease. The doctor should therefore be on the alert to avoid any danger of developing symptoms from the patient after Turbid Qi is perceived.



Figure 28.1. In order to disperse the patient's Evil Qi, the Qigong doctor exhales while slinging the toxic energy into the Earth.

It is very important for doctors who treat patients with Medical Qigong therapy to possess the ability to prevent and expel Turbid Qi so that it will not disturb their own energetic activities. Qi deviations are most often seen in those individuals who treat patients after they have gained some knowledge of Medical Qigong but have no experience, though they can occur even to some veterans of Medical Qigong practice. The interference by Turbid Qi is often an important factor in the the doctor's health.

When the interference by Turbid Qi is perceived, the doctor should use proper hand manipulations and readjust energy activities to expel the Turbid Qi immediately. If the Turbid Qi invades the doctor's fingers, or penetrates into certain channels or points, the doctor should guide the Qi to the specific points, channels, and infected areas and then relax and shake the hands to discharge the Turbid Qi while exhaling.



Figure 28.2. The Qigong doctor gathers energy into his or her Lower Dantian and expels any and all pathogenic invasions out through the hands and feet.



Figure 28.3. To avoid absorbing the emotions from an energetic discharge (released from dissolving an energetic cluster), the Qigong doctor turns his or her head and expels the patient's toxic emotions.

The doctor should be able to stop the Turbid Qi before it reaches the Dazhui GV-14 point on the upper back, Tiantu CV-22 point at the base of the throat, Quepen St-12 points on the front of the shoulders, and the Fengfu GV-16 and Fengchi GB-20 points on the back of the head. It is important to expel the Turbid Qi when it has reached the fingers, wrists, elbows, and at most the shoulders.

When this occurs the doctor should drive the Evil Qi out and regulate his or her Qi circulation as soon as possible. There are several ways to do this:

- Exhale while swinging the arms toward the ground, driving the Evil Qi deep into the center of the Earth. When treating tumors, be careful to disperse the pathogens out your fingers and do not allow the toxins to stick to your palms (Figure 28.1).
- Exhale while "blowing Qi" (extending Qi) out of the palms (Pc-8) and feet (Kd-1) (Figure 28.2).
- Exhale out of the mouth (but never over the patient, or towards anyone else). A shift in breathing is a common reaction when the emotions are discharged, or when an energetic cluster is reached (Figure 28.3).

GUIDELINES FOR THE MEDICAL QIGONG DOCTOR

1. The Qigong doctor must avoid practicing Medical Qigong in wet clothes. If the doctor perspires a little when training, he or she should avoid standing in the wind; if the doctor perspires profusely, practicing should be discontinued as it is liable to damage the doctor's Yin Qi.
2. The doctor should not go to the toilet within half an hour after practicing in order to avoid developing a conditioned reflex. This will help prevent the leakage of vital energy.
3. Patients suffering from cancer may affect the doctor's Qi circulation more seriously. Care should be taken when treating these patients, or avoid treating them completely, until sufficient energy has been cultivated, and sufficient experience has been gained.
4. The doctor must always wash his or her hands

with soap after each patient's treatment to prevent the energetic transference of diseases. It is important to note that washing the hands in cold water immediately after Qi emission is harmful to the doctor's energetic field because of the sudden shock to the system. Washing with hot water immediately after treatment, opens the channels on the doctor's hands and arms, sending the Toxic Qi deep into the doctor's body. To avoid these complications, the doctor should wait several minutes after completing the treatment, before washing his or her hands.

While waiting, the doctor should touch his or her finger tips together and focus on the Lower Dantian, allowing the Qi to settle back into its origin (minimum of three minutes). The doctor then washes up to the elbows with water that is room temperature to reduce the possibility of absorbing the patient's Turbid Qi.

If the doctor is not able, during treatment, to expel the Turbid Qi right away because of some distraction, or if the doctor's internal energy is not substantial, the Turbid Qi may enter his or her body through the fingers traveling up the wrists, elbows, or entering the Baihui GV-20, Tanzhong CV-17, Fengchi GB-20, Yintang (Extra Point) and Yongqauan Kd-1 points. If this begins to happen, the doctor should not continue to extend energy, but should stop the treatment immediately and perform a "closing," expelling the Turbid Qi by flicking the fingers, wrists, and shaking the arms until all discomfort has been eliminated. If any Turbid Qi still lingers, the doctor should practice Medical Qigong exercises to regulate the energetic activities.

5. It is important that doctors, as well as patients, avoid strenuous activities (such as running immediately after Medical Qigong exercises) to prevent the wrong flow of vital energy or pain in the legs. It is always better for the doctors and patients to be active first (running, swimming, forms training, etc.) and then cool down with the Medical Qigong Quiescent exercises (unless otherwise prescribed).

WU ZANG (FIVE ORGAN) MEDITATION FOR ENERGETIC PROTECTION

Even after the treatment of diseases, the doctor must perform certain Medical Qigong exercises to prevent and expel any undetected pathogenic Qi. Otherwise the doctor may develop the symptoms of the illness of the patient in corresponding locations. For instance, if the patient has a headache or pain in the hepatic area, the doctor may also acquire a feeling of discomfort, numbness, itching, and pain in the head and hepatic region. Therefore, in clinical practice, a deep understanding and correct judgment of the pathogenic Evils is compulsory.

Today in China, the Wu Zang meditation is still taught to Qigong doctors for clinical use to prevent invasion from the patient's pathogenic Qi. This meditation requires the doctor's Shen to guide the Qi of the Five Yin Organs (also known as the Wu Jing Shen, see Figure 28.4), to make the body's Qi substantial. The ending of the meditation, which causes the doctor's Qi to be reabsorbed into the Taiji Pole, allows the transformed Qi to flow into the appropriate organs, strengthening the doctor's energetic fields.

When a Qigong doctor enters the space of a diseased patient, the potential for absorbing the patient's pathogenic Qi is high. Noting this potential for harm, the ancient Chinese Qigong masters developed certain meditations to protect themselves from the patient's diseased or Turbid energy.

The Yellow Emperor's Classics on Internal Medicine states that before treating patients of any kind, the doctor should first perform the Wu Zang Energy meditation. It encouraged doctors to practice this meditation before treating patients in a clinical environment and before entering the treatment room, because it surrounds them with a strong field of protective energy (Wei Qi).

The Wu Zang meditation focuses on six directions (north, south, east, west, Heaven and Earth). It is very powerful and can be used to gather environmental Qi at the beginning of each season. The focus of the meditation is to extend each of the five organs' energy far into the horizon to gather the Qi. When practicing the Wu Zang


Fire
Front
Heart
(Red Phoenix)
Spirit
Left
Wood
Liver
(Green Dragon)
Spirit/Soul
Golden Sun
Intention
Spleen
Center
Lungs
(White Tiger)
Material Soul
Right
Metal
Kidneys
Dark-Blue Turtle
Essence
Back
Water

Figure 28.4. The Wu Jing Shen Relationship of the Wu Zang Meditation

meditation the Qigong doctor should:

- face east during the spring equinox;
- face south on the day of the summer solstice;
- concentration on the center of the Earth during late summer, before the fall equinox;
- face west on the day of the fall equinox;
- face north on the winter solstice.

Start by focusing on the center of the body. Imagine opening up the Baihui point (at the top of the head) and begin to pull in the Qi from the Heavens. Imagine the divine light as a bright shining white light, illuminating and filling your entire body through the Baihui. Feel the body radiating this divine white light energy. Next, imagine this white light energy coalescing into the body's center core, forming an energetic tube of Heavenly energy that extends from the Baihui point to the Huiyin point. The center core vibrates and resonates with the divine white light energy.

1. Now, imagine a golden yellow mist of Qi arising from under the Earth and filling your body and connecting with the Spleen organ. Next, feel this golden light Earth energy envelop the center core of divine white light energy, merging together and synergizing. This represents the energy of your Yi (Intention), to root and stabilize your power.
2. Begin to focus on your Heart and imagine a portal opening and the Qi flowing out of your Heart like a red swirling wind in front of you, full of power, protecting you with your Shen and the fire of a red phoenix. This represents your innate spirit, alive, graceful yet powerful.
3. Focus your attention on your back and the Kidneys and Mingmen area. Imagine a portal opening and the Qi flowing out of your Mingmen behind you like water. Out of this water grows an enormous dark blue turtle,



Figure 28.5. The Wu Zang Meditation

whose shell protects you like a mighty shield. This represents the energy of your Zhi (Willpower), and the Jing and Zhi of all your ancestors, backing you and supporting you.

4. Place your attention on your Lungs and visualize a portal opening on your right side of your body, under the right ribs. Imagine the Lung Qi flowing out of to the right side of your body like steam, forming a white tiger, as strong as steel. This represents the Po and the body's animal nature, that guards and protects you with an animal passion for survival.
5. Next, place your attention on your Liver and visualize a portal opening on your left side of your body, under the left ribs. Imagine the Liver Qi flowing out of to the left side of your body like steam, forming a green dragon, sinewy and resilient as bamboo. This represents the Hun and the body's divine nature, guarding and protecting you with a spiritual passion for victory.
6. Each animal begins to rotate to the left, protecting, stalking, and defending the previous animal's position (Figure 28.5). Slowly begin

to circle these energies, then increase their speed (like a mighty wind) counterclockwise around your body, blending these colors together, to form an energy bubble.

After forming a protective rainbow hue around your body, draw the energies back in through the Baihui point and return the energy of each organ color back to its origin (the color red returns back to the Heart, dark blue to the Kidneys, white to the Lungs, and green back to the Liver). As the colors return back to their organ of origin, imagine steam (white light) flowing out of the pores and filling up the energy bubble created by the animal rotation. This forms a solid connection between the body's internal organs and the body's external field of energy.

7. When the protection of the body with the Five Elements is done, imagine that there are many sparkling lights like the Big Dipper above your head. Then you can enter the room of the patient, safe and protected.

Keep in mind that you can send the five organ energy outside of your body instantly, any time you need protection. Some schools teach the doctor to extend his or her energy like mist out through the eyes, enveloping the body with the five organ colors (green, red, yellow, white, and dark blue/indigo).

CREATING A PROTECTIVE ENERGETIC FORCE FIELD

This second meditation also establishes a powerful energetic force field, needed to protect the doctor from any attack or attachment of external pathogenic Qi. It consists of wrapping the doctor's external fields of Wei Qi to increase the energetic field's power.

This is similar to wrapping a magnet with coils of wire to increase its magnetic field (Figure 28.6).



Figure 28.6. Creating a Protective Energetic Forcefield

1. Begin from a standing Wuji posture. Focus on all the body's energy collecting into the Lower Dantian. Concentrate the Qi in the Lower Dantian, condensing it into a dense ball of white light energy. Imagine this ball of white light energy exiting the body through the navel and circling the body, spinning in a counterclockwise direction nine times, wrapping the Belt Vessel, Mingmen GV-4 and Shenque CV-8 points.
2. Move the energy ball down to the perineum and continue circling the lower body in a counterclockwise direction nine times, spinning and wrapping the Huiyin CV-1 and Changqiang GV-1 points.
3. Move the energy ball down to the knees and continue circling in a counterclockwise direction nine times, spinning and wrapping the ascending Yin channels and descending Yang channels of the legs.
4. Move the energy ball down to the ankles and continue circling in a counterclockwise direc-

tion nine times, spinning and wrapping the ascending Yin channels and descending Yang channels of the legs.

5. Move the energy ball down to the bottom of the feet and continue circling in a counterclockwise direction nine times, spinning and wrapping the Yongquan Kd-1 points.
6. Move the energy ball several feet into the ground and continue circling in a counterclockwise direction nine times, spinning and wrapping the body's Earth Transpersonal point. This energetic point (under the ground) is responsible for establishing the body's rooted connection to the Earth and for absorbing the Earth energy into the body's internal organs, channels, and collaterals.
7. Next, imagine the energy ball slowing down and stopping its rotation, pulsing for several heartbeats, then reversing its energetic rotation, and beginning to spin in a clockwise direction nine times. The direction and flow of the energetic ball now reverses its orbit, ascending and circling the same areas and points nine times, until it returns back to the navel.
8. From the navel move the energy ball up to the solar plexus area and continue circling the body in a clockwise direction nine times, spinning and wrapping the Jiuwei CV-15 and Zhiyang GV-9 points.
9. Move the energy ball up to the Middle Dantian at the center of the chest, and continue circling in a clockwise direction nine times, spinning and wrapping the Heart, Shanzhong CV-17 and Shendao GV-11 points.
10. Move the energy ball up to the throat and continue circling in a clockwise direction nine times, spinning and wrapping the Tiantu CV-22 and Dazhui GV-14 points.
11. Move the energy ball up to the Upper Dantian at the Third Eye area, and continue circling in a clockwise direction nine times, spinning and wrapping the Yintang and Naohu GV-17 points.
12. Move the energy ball up to the top of the head and continue circling in a clockwise direction nine times, spinning and wrapping the Baihui GV-20 point.
13. Move the energy ball several feet above the head and continue circling in a clockwise direction nine times, spinning and wrapping the body's Heavenly Transpersonal point. This energetic point (above the head) is responsible for establishing the body's extended connection to the Heavens and for absorbing the divine energy into the body's internal organs, channels, and collaterals.
14. Next, imagine the energy ball slowing down and stopping its rotation, pulsing for several heartbeats, then reversing its energetic rotation, and beginning to spin in a counterclockwise direction nine times. The direction and flow of the energetic ball now reverses its orbit, descending and circling the same areas and points nine times, until it returns back down to the navel. The body should now be encircled, above and below, with several haloes of white light energy.
15. Finally, imagine the white light energy ball absorbing back into the body through the navel. As the energy ball descends back into the Lower Dantian, imagine energetic steam filling the entire body.
16. Once the body is completely full, the steam begins to exit the body through the pores and begins connecting and filling the space outside the body with white light energy, forming an energetic cocoon. This cocoon creates an energetic force field which protects the Qigong doctor from pathogenic invasion.

CLINICAL ETHICS

The study of clinical ethics refers to the morality of the Qigong doctor and the ability to set boundaries. The study of morals in the therapeutic relationship involves reflecting upon the ideals the doctor assumes as a professional care giver and the enforcement of these professional standards in his or her actual behavior. Both the morality and the self reflection are engaged, both consciously and unconsciously, to align the doctor's values with his or her actions.

Ethical behavior stems from the doctor's internal values and actions (emotionally, cognitively, and spiritually) and his or her sense of external connection (physically, existentially, and socially). The Qigong doctor's behavior should be always congruent with high ethical standards and in harmony with his or her values, intuition, knowledge, and feelings.

The importance of establishing ethical standards for the doctor-patient relationship is to avoid those behaviors which prove to be counter therapeutic, and encourage those that are most effective therapeutically for the patient. The patient, as well as the doctor, rely upon each others' trust and boundaries. It is the Qigong doctor's responsibility to create a context for the patient, in which the patient can make a change in his or her life in safety.

When patients are treated energetically, they relax into an altered state of consciousness. This causes the patient's boundaries to become relaxed or nonexistent. Because Medical Qigong therapy often reveals intimate knowledge of the patient's life and life-style, there is a danger of enmeshment, i.e., of co-dependent relationships forming (see Chapter 19).

When working with patients, doctors sometimes encounter intense physical, mental, emotional, and spiritual reactions from the patients. These experiences tend to disperse the patients' boundaries and can confuse the roles between the doctor and patients, intensifying transference and triggering countertransference.

When both the doctor and patient have a personal relationship with a divine higher power, it naturally brings them into a state of divine healing and spiritual wisdom. The acknowledgment and honor of this divine relationship should establish ethical boundaries. This is especially true as the doctor begins to see the bigger picture of how his or her intentions and actions (in relationship with patients) affect others in a rippling outward motion. It is important that doctors also see the effect on themselves when they take certain actions towards others, including their patients.

CONSCIOUS AND SUBCONSCIOUS CLINICAL INTERACTIONS

Clinical experiences are divided into two states of interactions: the body / mind and emotional / spiritual.

- The body / mind interaction deals with ordinary states of consciousness, such as: talking, thinking, analyzing, working, interacting with the material world and other human beings. These different qualities of interactions help the doctor to define and categorize, educate, and establish his or her solid belief structures.
- The emotion / spirit interaction deals with subconscious states of communication, such as: perceiving, sensing, intuiting, interacting with the spiritual / metaphysical world, as well as with energetic fields. Every day people go into states of light trance (daydreaming, spacing-out, etc.) allowing their focus of attention, thoughts, feelings, sensations, and intuitions to interconnect with their environment and that of the divine. This allows access to information and facilitates the healing and understanding of themselves and their life experiences.

Because most wounding involves an emotional / spiritual trauma at the time of the incident, the patients must relive this trauma during their healing process. Through the emotional / spiritual interaction between the Qigong doctor and his or her patients, ingrained habits of thought, feelings, and perceptual understandings begin to recede, diffuse and break down. This causes the patients to find a new understanding of certain traumas and allows them to reclaim disconnected parts of their past (soul retrieval).

Each time patients transcend to a new level of understanding of their fears and belief structures, they change, mature, and expand to adjust to the new mental, emotional, and spiritual growth. The moment that patients break out of their old boundary structure, feelings of emotion rush through their body / mind, followed by a sense of either expansiveness or disorientation as they find themselves in unfamiliar territory.

It is not useful for patients to relive their emo-

Do the same procedure as before using the Four Fused Energy Balls spiraling on top of the cauldron, forming One Energy Pearl as you turn the Dial. You spend more time using Dial-2 and Dial-3 positions.



Fig. 6.38 *Forming the Cauldron and the Pearl*

Creation Cycle Foundation Practice

1. Fuse the Pearl to help activate virtue energy. The Inner Smile is the first step to connecting your consciousness to all your organs and glands. This is actually the first step of the Fusion of the Five Elements practice. It is important to remember how powerful and sublime smiling inward can be.
2. The next stage of practice is removing negative emotional energy from the organs. The negative energy is brought from each organ to its corresponding organ collection point and then to the pakua where it is neutralized. When all negative energies are brought to all four pakuas and are under control and all residual energies have been brought to the back and side pakuas, the energies are then spiraled and compressed into the cauldron. There they are formed into the pearl of energy. As you collect the energies and direct their flow to the cauldron, you feel your center point illuminate with the bright light of the pearl.

tional traumas without the awareness, understanding, and insight of the process they are undergoing. To relive the trauma without this awareness leads to re-traumatization. That is why the Qigong doctor coaxes the patients through the "five stages of emotional healing" (see Chapter 19). The patients can then experience their past emotions in the present time, and become free of them through present awareness, rather then repeating the past through a continuous loop of repression and denial. In the clinic, this is known as "emotional time traveling" and refers to the practice of allowing the patients the experience of reliving past traumas through their presently increased state of awareness and knowledge. At this point of transition, the patients will not only experience the emotions and sensations from their past, but may also experience the motivations and emotions of the perpetrators as well.

The empathic knowledge of the perpetrator's emotions is due to the victim's identification process with the abuser. This phenomenon is well recognized in helpless hostage situations, and is a major contributor to childhood victims of physical, sexual or emotional abuse "acting out" their repressed fears, angers, and pain, in similar ways to the manner in which they were abused.

ESTABLISHING DOCTOR AND PATIENT AGREEMENTS

For the protection and integrity of both the doctor as well as the patients, it is important that a description of the clinical procedures that are to be used, their physical and energetic boundaries, as well as their limitations, be firmly established. The following seven principles are used to establish the foundation of clinical ethics.

1. The Qigong doctor will cause no harm (physical, mental, emotional, or spiritual). The Qigong doctor will maintain a high standard of skill, knowledge, and professional conduct, offering his or her services without favoritism, prejudice, or discrimination with regards to race, religion, nationality, gender, or sexual orientation.

   The Qigong doctor is committed to the patients' education and personal development of practicing Medical Qigong methods that relieve pain, suffering, and other symptoms of illness. The doctor will exercise his or her best judgement to determine if the therapeutic techniques prescribed for patients are contraindicated, dangerous, or not in the best interest of the patients.

   The doctor will never make negative suggestions, criticize, or tell the patients that they will get worse or are in bad shape, as that destroys the patients' hopes and is counterproductive to healing (this is known as "clinical hexing"). Clinical hexing will cause patients, who trust the doctor, to sabotage their own healing potential by succumbing to the doctor's particular beliefs about their conditions.

   One example of trusting a doctor's diagnosis to ruin, happened last year in 1999, when two patients' lab tests were accidently switched. The healthy patient, whose lab test had been switched, was informed by the Western doctor that she had terminal cancer; and the patient with terminal cancer, on the other hand, was given a clean bill of health. The healthy patient died several months later as a result of believing the doctor's diagnosis of having a terminal condition; whereas the patient with terminal cancer (believing that there was nothing wrong) resumed a normal, active life-style, and the patient's cancer went into remission.

2. The Qigong doctor will keep all sessions in confidence. The Qigong doctor will keep all patient information strictly confidential, in keeping with ethical and legal standards held by other health care professionals. This allows patients to experience the treatment in safety and give honest feedback.

   Exceptions to the rule of confidentiality are as follows: when the patient is a danger to self (intending suicide), or others (intending homicide), when the patient has a life threatening emergency, in cases of suspected child abuse (sexual, physical, or neglect), and elderly abuse (sexual, physical, neglect or fiduciary).

3. The Qigong doctor will first receive informed consent from the patient before starting the treatment, or informed consent of the patient's legal guardian. Before treatment, the Qigong doctor explains to the patient the therapeutic goal of the treatment, and what the patient may energetically and emotionally expect to experience. The doctor will respect the patient's boundaries at all times, before, during, and after each treatment. At times the doctor may have to impose boundaries for patients who cannot do so for themselves, in order to avoid total enmeshment, which would endanger the professional relationship.
4. The Qigong doctor and the patient will tell the truth to each other. No part of the Medical Qigong diagnosis should ever be hidden from the patient, yet the truth should always be delivered with hope, since no one can be certain of the future.

   The Qigong doctor should never make unrealistic, inaccurate, or false claims about Medical Qigong therapy, or give the patient false hope. A realistic assessment of the patient's condition should always be conveyed, and if need be, the patient should be referred for additional medical or psychological modalities of treatment.
5. The Qigong doctor will honor all agreements established with the patient. It is important for the patient to be able to rely on the doctor's trust. Because this is a critical factor, the doctor is never allowed to borrow money, cars, etc. from patients.
6. The Qigong doctor and the patient will not act sexually or romantically with each other. The Qigong doctor will not instigate or tolerate sexual advances while interacting with his or her patients. Although there are times that the patient, or doctor, may experience certain attractions towards each other, acting out on these feeling will cause an emotional/sexual entanglement which will be detrimental to the patient's healing.
7. The Qigong doctor and the patient will agree on the time, place, duration of treatment, and fee. The Qigong doctor must be consistent in maintaining an established clinical treatment time and location. This instills a stable security for the patient and doctor. If this boundary is not maintained, patients without strong boundaries will take advantage and hurt both doctor and themselves. The Qigong doctor is responsible for giving adequate advance notice (two weeks) to the patient of any and all treatment or fee changes. If, for example, the original agreement was for six or fewer sessions and the doctor changes fees after the first session, the original agreement must be upheld (new patients however, will be charged the new fee).

POWER DYNAMICS AND ETHICAL BEHAVIOR

In any clinical setting there is an active power dynamic at work. Generally it is the doctor who maintains the power over the patient, as the purpose of the patient's visit is for help or assistance in specific healing. As the patient has come to the doctor with expectations, it is important for the doctor to be congruent with these expectations. These expectations set both the standard of the patient's healing and the power dynamics of the relationship. Through the power dynamics of the doctor-patient relationship there can develop three classical problems: Transference, Counter-transference, and Emotional-Sexual Entanglement.

1. Transference is the process whereby a patient unconsciously transfers feelings, thoughts, beliefs, and patterns of behavior that had been previously experienced towards others onto the doctor.
2. Counter-transference is the process whereby a doctor loses his or her objectivity and unconsciously transfers feelings, thoughts, beliefs, and patterns of behavior to the patient.
3. Emotional-Sexual Entanglement is the process whereby the doctor and patient both lose their objectivity and transfer emotional-sexual feelings, thoughts, beliefs, and patterns of behavior onto each other.

In order to prevent these types of enmeshment and co-dependent relationships from happening, it is important for the doctor to constantly maintain his or her boundaries. The doctor and patient both must remember that it is the patient who actually does the healing in energy work, the doctor merely creates the situation in which this energetic transformation can transpire.

PITFALLS

There are certain pitfalls the Qigong doctor should be aware of and may experience, if a boundary has already been, or is beginning to be violated. These experiences are described as follows.

- The doctor begins to identify with the patient's problem and feels the need to discuss his or her own similar problems with the patient.
- The doctor begins to become emotionally attached or attracted to a patient sexually and feels the need to act on it (i.e., asks for a date, inappropriate touching or sexual contact).
- The doctor begins to feel the need to go out of the way above and beyond the normal course of responsible treatment to meet a patient's needs.
- The doctor begins to treat the patient for free.
- The doctor begins to find him or herself becoming overprotective, or worrying about a patient at inappropriate times.
- The doctor begins to need validation from his or her patient (this approval can be either as a healer, emotionally, or sexually).
- Arranging an exchange of services with a patient can often lead to the patient feeling abused or hurt.
- Allowing the patient to build up a large bill to be paid back later is unethical and may lead to legal action.
- Disclosing too much personal information regarding self (the doctor) in order to help the client can make the patient feel responsible for the doctor's well-being. Self-disclosure can be used very sparingly when the patient can benefit from solutions that worked for the doctor. It is safer, however, to pretend that these situations came from someone else.
- The doctor does not listen carefully to what the patient is saying, thinking that he or she knows what the problem is in advance.

It is important for the doctor to remember that the patient's emotional / spiritual safety and health must always come first. To avoid sinking into one of these pitfalls, the Qigong doctor is encouraged to constantly monitor his or her own actions and motivations. This is a broad and important topic that is often neglected in professional training and education. Because it is well dealt with in Kylea Taylor's book entitled, *The Ethics of Caring*, I encourage the reader to refer to this work for indepth treatment of this subject.

CLINICAL BURNOUT AND MEDICAL QIGONG THERAPY

One classic problem all healers encounter is clinical burnout. The condition known as clinical burnout results from chronic job stress, and may sometimes occur to the Qigong doctor. This condition is characterized by extreme frustration, disappointment, physical and emotional exhaustion, and sometimes physical illness. The result of this condition is the doctor's loss of concern for the patients, or the loss of fulfillment with his or her performance as a healer. The Qigong doctor is susceptible to experiencing clinical burnout, especially if he or she feels that:

- There are too many or too few patients;
- Too little time is spent for recreation;
- There is too much stress in his or her life;
- Not enough attention is placed on self care and personal psychological growth; and
- Not enough attention is placed on a personal spiritual path and practice.

If the Qigong doctor's life revolves primarily around the clinic (which is usually the case), he or she will disproportionately come into contact with the patients' pain and emotional traumas, as well as be chronically bombarded with toxic energetic discharges released from the patients.

Sometimes patients, in order to heal their intense emotional traumas, require an enormous amount of spiritual, emotional, and mental support from the doctor. If the doctor does not carefully monitor his or her own energetic reservoir, this may result in Qi depletion.

If Qigong doctors expend all their spiritual/emotional energy from intense personal interaction and enmeshment with their patients during treatment, the toxic interaction will deplete the doctors, resulting in complete physical and mental exhaustion. If Qigong doctors become depleted in the middle of a treatment, they may abandon their Upper Dantian (psychic) connection with patients (spiritually, emotionally, and/or energetically), and begin to suddenly express feelings of criticism, anger, disappointment, or grief. This reaction occurs when the Qigong doctors' own internal organ energy, depleted and worn, becomes susceptible to absorbing the patients' powerful emotional discharges. The problem of clinical burnout usually stems from energetic boundary invasion. Remember, Medical Qigong healing requires that the doctor heal him or herself first.

Often, a Qigong doctor's clinical burnout is primarily related to the unresolved personal issues and not the number of patients on the case load, or the amount of environmental stress the doctor experiences.

ENERGETIC BOUNDARY INVASION

In understanding clinical burnout due to energetic boundary invasion and its relationship between the doctor and patient interaction, it is important to review seven important factors which control and transform the body's energetic fields.

1. Energy exists on different planes. The body is like a complex hologram, composed of physical, mental, emotional, and spiritual planes of energy. The spiritual field of energy controls the emotional and mental energetic field, which in turn controls the physical energetic field. These energetic planes affect and control the energetic formation of the body's cells, tissues, organs, and organ systems.
2. Because the body produces heat, light, electricity, magnetic energy, and resonate vibrations, these natural energetic releases create a basic Yin (negative) and Yang (positive) polarity, which is found in all manifestations of energy.
3. Everything in the body is in vibratory motion. Various forms of tissue develop from different energetic vibrations. When the body's energy begins to slow down, it begins to take on a denser form of resonant vibration. The impediment of this resonant energetic vibration can stem from trauma or shock to the system (physical or emotional), resulting in energetic stagnations and disease.
4. The body's internal organs collect and store emotional energy, both positive and negative. As any suppressed, or "stuffed," emotional energy begins to culminate, the body will naturally (and quite frequently) disperse these internal emotional charges. They are generally released externally through: the Respiration, the Posture, and the Mental Dialogue.
   - The respiration, (which includes sighing and laughing), is released from the Heart, shouting released from the Liver, groaning from the Kidneys, crying from the Lungs, and singing from the Spleen.
   - The posture includes the body's physical structure adapting or conforming to an Expanded-Yang or Contracted-Yin energetic influence.
   - The mental dialogue includes both benign and malignant thought patterns.
5. The body has three primary energy centers known as Dantians. Each Dantian resonates at its own distinct vibration and is responsible for specific modes of interacting with others in interpersonal communication.
   - The Lower Dantian is considered the most physical energetic base. It is the most dense and has the slowest vibratory rate of the Three Dantians and communicates kinetically with the outside environment.
   - The Middle Dantian is considered the emotional and mental base. It has moderate resonances and communicates empathetically with the outside environment.
   - The Upper Dantian is considered the spiritual base and has the fastest and most delicate of the vibrational interactions. The Upper Dantian functions at an intuitive level.

6. When communicating, the body will interact from all five levels: physical, mental, emotional, energetic, and spiritual. This interactive communication will sometimes energetically fuse with the external environment, including people.
7. Our external and internal thoughts and feelings, as well as tissues and cells are all byproducts of energetic interactions, stemming from communication from within ourselves and our environment.

After reviewing the following facts, the Qigong doctor can understand why every time he or she connects with a patient, the patient's energetic fields will automatically be energetically ingested by the doctor. The doctor does this consciously in order to analyze the patient's emotional past, as well as present emotional outbursts. Although the doctor and patient's energies fuse together, the fields of energy around the doctor's internal organs generally protect the doctor from absorbing negative emotions. These energetic boundaries also extend out into the doctor's Wei Qi field.

Both the patient's and doctor's Wei Qi fields are fused during interaction and treatment. It is therefore imperative that the doctor's energetic boundary system maintain its structure (both internally and externally), yet be permeable while treating the patient. The doctor must not lose sight of his or her purpose. Any criticism aimed at the doctor should not be taken seriously, nor should any inappropriate behavior by the patient. The doctor's Wei Qi field should be at maximum strength. If not, the cords of energetic attachment flowing from both the doctor and the patient allow energetic emotional transference to happen. If the doctor, for example, has a preexisting Liver Heat condition, it will be further compounded by the inflowing of the patient's released of anger and rage. If and once this happens, the patient may feel relieved, but the doctor will become quite agitated.

STRENGTHENING THE DOCTOR'S ENERGETIC BOUNDARIES

It is important for the Qigong doctors to allow the patients' emotions to constantly flow through their own bodies, feeling, understanding, then releasing these feelings. If at any one point in this transition, a doctor (because of personal issues) suddenly stops the flow of emotions and begins to focus, or dwell on, a particular type of energetic charge, the patients' discharging emotions will invade the doctor's body.

To avoid energetic boundary invasion the doctor should maintain a regular Qigong meditation and exercise program. This program should include the following exercises and meditations.

1. Practice Qi dredging and emotional dispersing exercises and meditations to release your own emotional traumas.
2. Perform Qi and organ strengthening exercises and meditations to strengthen both your internal organ energies, as well as the three fields of Wei Qi. Since the emotions are stored within the body's internal organs, strengthening these organs will facilitate a stronger control of the body's emotional energy.
3. Practice Qi regulation and balancing exercises and meditations to balance the body's Yin and Yang, as well as internal and external energetic channels, organs, and organ systems. This helps to control the energetic surges released from internal emotional discharges.
4. Maintain emphasis on the energetic grounding and the divine hook-up meditations before treating patients. These meditations are important for establishing an emotional as well as spiritual boundary, and will assist you in avoiding clinical burnout and energetic boundary invasion.
5. Maintain emphasis on personal time, including any and all spiritual, social, and recreational times away from the clinic.

CAUSES OF SPIRITUAL DRYNESS

Sometimes clinical burnout can result from "spiritual dryness." This type of burnout can result from experiencing a "dry period" of spiritual insight and perception. It can occur during clinical observations and treatments, resulting in frustration for the doctor. Spiritual dryness is commonly due to one or more of the following five conditions.

1. If the doctor is tired, hungry, or sick, the fo-

cus will tend to be on the doctor's own particular needs instead of the patient's.

2. A disconnection from the divine is caused by guilt, lack of forgiveness (self-blame), shame, etc., resulting in a loss of spiritual vision. It is important for the Qigong doctor to have an open and honest connection with the divine to receive the more subtle spiritual insights. Without this type of transpersonal relationship, the Qigong doctor's ability to dissolve into the Wuji surrounding the patient's tissues can be hindered.
3. Rushing personal meditation time is caused by failing to relax during the preparation meditation practice (the divine hook-up). This condition is normally caused by worries or preoccupations due to hidden agendas, that disturb the doctor's Shen prior to meditation. It is important for the doctor to relax and return to a state of quiescent peace, in order to truly listen to the divine.
4. Getting into a rut is caused by the doctor performing repetitive Shengong meditations in a mechanical way (i.e., the same way an individual will routinely brush his or her teeth), thus losing the emotional and spiritual connection with the core self. The meditation then becomes meaningless and powerless (just words and no spirit). To avoid getting into a rut, the doctor should try to experience each meditation as a time of new beginnings and enlightenment, and not as a mandatory routine.
5. It is important for the doctor to be able to share emotional and spiritual insights with other colleagues in the same field of work, and when appropriate, with the patient. This sharing of spiritual insights, observations, fears, and triumphs renews the doctor's confidence in his or her spiritual gifts, and maintains a strong faith in the healing potential of Medical Qigong therapy.

SECTION VII

THE TREATMENT PRINCIPLES OF MEDICAL QIGONG THERAPY

CHAPTER 29

PRINCIPLES AND PARAMETERS OF MEDICAL QIGONG THERAPY

The foundational factors of the patient's state of health originate from their actions, thoughts, and feelings. A Qigong doctor, studying a patient's physical problems, understands that the origin and solution to these problems are to be found within a patient's recurring thought patterns, both conscious and unconscious.

The brain processes data consistent with what it is familiar with; patients will generally experience and accept information that coincides with their own belief system. Their consciousness then, creates its own reality, resulting in either health or disease.

Good health is a result of bringing the patient's own unique spiritual and emotional essence back into consciousness and increasing the awareness of the physical body. Both health and disease are created through this process which is the foundational base for clinical Qigong treatments.

THE FIVE METHODS FOR TREATING PATIENTS

Qigong doctors generally use five methods for treating their patients' diseases (Figure 29.1). These methods initiate an energetic restructuring within the patient's body. The five methods are described as follows.

1. The doctor uses his or her own Qi to initiate the healing.
2. Qi is drawn, by the doctor, from the surrounding natural environment (from the energetic fields of the Earth) to be emitted to the patients.
3. Qi is drawn, by the doctor, from the surrounding universe (from the energetic fields of the Heavens) to be emitted to the patients.
4. Divine energy is channeled through the doctor to treat the patients.
5. Homework is prescribed in the form of self-regulation exercises and meditations to support the healing process.

THE NINE STAGES OF TREATMENT

Using these five methods of treatment, the Qigong doctor initiates nine stages of healing within the patient's body. The healing process will always vary according to the belief structure of the patients, their acceptance and performance of the Medical Qigong prescriptions, and their willingness to change. The Qigong doctor's nine specific stages in treating a patient are described as follows.



Figure 29.1. Five Methods Used For Treating Patients

3. Be aware the energy, physical and universal collection points, fuse them together and fuse back to form the bigger pearl.
4. The pearl is capable of activating, attracting and absorbing a great amount of good virtue energy. For this reason the pearl is circulated to each organ following the Creation Cycle. After practicing Fusion of the Five Elements, the pearl is brought from the cauldron to the perineum and is then circulated in the Microcosmic Orbit.
5. When you are ready to begin Cosmic Fusion, the pearl is brought to the Heart to begin the Creation Cycle. The Heart is the beginning point of this cycle because it is in the Heart that Compassion resides.
6. At this point there is a great awareness of each organ and the energy that each one is supplying. A continuation of this awareness is necessary for properly practicing the Creation Cycle of Cosmic Fusion. It is especially important that all negative energy has been removed and neutralized beforehand; otherwise, as the virtue energy of the pearl increases, so will the negative energy as you move the pearl through the Cycle.
7. In Fusion of the Five Elements, you remove the negative emotion of fear from the kidneys, by first listening to them, because the ears and kidneys have a connection. The removal of fear from the kidneys leaves room for the positive virtue of gentleness inherent in the kidneys to grow.
8. Now, in beginning the Creation Cycle of Cosmic Fusion, you focus your smile on the virtues of joy, love and happiness in the Heart. Feel the virtues growing and purifying. It is important to develop a genuine virtue here. You can spit out words like love, joy and happiness without meaning them. But like the love that is mentioned in the Bible (1 Corinthians 13), it has to be real and true; otherwise it is just a sounding brass or a tinkling cymbal. You have to flesh it out and breathe life into it.
9. Here is the way to do the Creation Cycle of Cosmic Fusion: Feel the unconditional love of the Universe flowing down into the Heart. With this combination of virtues – love, joy, happiness, unconditional love – you can definitely transform yourself, your organs and those around you.

The Subtle Wonders	Expensive or Contracted, Heavy or Weightlessness, Cold or Hot, and Tingling, or Vibrating Sensations
The Mysterious Wonders	Flashing Light Sensations, Sound Sensations, Smell Sensations, and Fainting (Syncope) Sensations
The Incredible Wonders	The patient will experience various colored lights, sounds, smells and other sensations according to the doctor's intention.

Figure 29.2. The Three Wonders

1. Activate, connect, and energize the patient's energetic field;
2. Dredge the patient's channels and collaterals;
3. Purge and eliminate any energetic Excess;
4. Tonify any energetic Deficiencies;
5. Regulate the Qi and Blood content of the patient's Yin and Yang organs (harmonize the organ Jing);
6. Regulate the patient's Prenatal and Postnatal Qi (harmonize the Qi of the Three Dantians and Taiji Pole);
7. Balance the patient's Yin and Yang Shen (harmonize the Heart/Mind and Emotions);
8. Seal the patient's external field of energy;
9. Give prescriptions.

THE THREE WONDERS OF MEDICAL QIGONG THERAPY

The cultivation of Qi and Shen through Medical Qigong therapy generates what is described as the Three Wonders. These Three Wonders consist of the three separate transformations of energetic abilities that the Medical Qigong doctor and, sometimes, the patients experience (Figure 29.2). The Three Wonders are explained as follows:

THE SUBTLE WONDERS

The Subtle Wonders consist of subtle changes inside and outside the body, known as the Eight Energetic Touches. These interactions of tissue and energy form the physical sensations and manifestations of Yuan Qi. When the doctor emits Qi to treat diseases, involuntary phenomena can occur instantly, or gradually, in local areas of the limbs, or the patient's whole body. In some cases the muscles stir slightly, while in other cases the limbs, or the body, will perform extreme, harsh movements. This results from the patient's external energy (Wei Qi) inducing spontaneous movements.

When the Qigong doctor emits energy to treat diseases, some patients produce, in local areas, electromagnetic, or stimulating, sensations of Qi similar to those felt in Qigong circulation/cultivation exercises and meditations. This includes: cold or hot sensations, feelings of compression or tugging, impressions of creeping or tingling, experiences of heaviness or lightness, and of floating or sinking, as well as other sensations. The Subtle Wonders result from energy in the channels circulating and responding to the doctor's intention.

Generally, the effects of Qi on the body are manifested in physical sensations and sensory phenomena during Qigong exercises. These phenomena are all manifestations of the free movement of Qi in the channels, collaterals, and inner body circulation.

The doctor may also experience these same sensations while extending energy into the patient. The doctor should be able to sense the patient's Qi circulation, density, direction, as well as his or her own energy. The sensations known as the Eight Energetic Touches of the Subtle Wonders are: Expansive, Contracted, Heavy, Light or Weightlessness, Cold, Hot, Tingling or Itching, and either Vibrating, Shaking, Rippling or Moving.

1. When the Qi is circulating freely within the body, the capillaries expand as the body's energetic field expands, resulting in the sensation of being very large, tall, and expanded.
2. When the Qi enters from the outside of the body to gather in the Lower Dantian, the patient experiences the sensation of feeling very small or contracted.
3. When the Qi sinks down (upon exhalation), the body feels heavy, condensed, and solid as a rock.
4. When the Qi rises upward (overflowing the channels), the body feels light and weightless.
5. When the Qi circulates through the Microcosmic Orbit (balancing the Qi of the Heart and Kidneys), the Kidney-Yang becomes sufficient to allow the Kidney Yin to well up; this results in a pleasant cool sensation.
6. When the Qi is vigorous and thermal energy is gathered, the parts of the body where the Qi passes will feel hot.
7. Once Qi circulates vigorously and passes through the body's obstructed channels, collaterals and minute collaterals, the result is itching or tingling of the skin and scalp. This is an energetic manifestation of the body's obstructed channels, collaterals, and minute collaterals being cleansed.
8. When the Qi passes through the channels, collaterals, and parts of the body it has opened, the patient feels electrical and creeping sensations in the extremities as well as the body, causing the tissues to vibrate, shake, ripple, or move, etc.

These are all normal phenomena of Qi cultivation and circulation. As long as the patient remains calm and present, these sensations will appear and disappear as spontaneously as they were formed.

THE MYSTERIOUS WONDERS

Patients may also experience elusive as well as dynamic transitions inside and outside of the body, called the Mysterious Wonders. These energetic changes are sometimes present, but are rare, and may be confusing to the patient. The sensations known as the Mysterious Wonders are: Flashing Light Sensations, Sound Sensations, Smell Sensations, and Fainting (Syncope).

1. Flashing Light Sensations sometimes occur in some patients during Qigong treatment. The photoelectric phenomena is due to the interaction of light with matter. In some cases, patients feel electric sensations in the limbs and body, and in other cases light patterns may be seen in different forms, most of which present as round, sheet light, or lightning patterns.

   One of the manifestations of the Qigong doctor's cultivation through Shen Gong meditations is a flashing light sensation which is seen and felt within the doctor's head and body. This glow may sway back and forth, pulse like a white neon light, or pierce into the doctor's brain, and illuminate the spinal column. It may also appear as a ball of white light rotating at high speed through the Microcosmic Orbit.

   This ball or beam of light may exist continuously at the Qigong doctor's Baihui GV-20 point throughout the duration of the meditation and several hours afterwards. The degrees of light sensations and their colors will vary in accordance with the doctor's skill level. Also, it is this beam of light that the Qigong doctor will later utilize for inner vision diagnosis.
2. Sound Sensations are sometimes experienced during treatment, such as a rustling, rumbling, or high-pitched sound.
3. Specific Smell Sensations may occur, such as the sweet scent of sandalwood, or fragrances of various flowers, or incenses.
4. Fainting (Syncope) can occur during Qigong treatment. A few patients may suffer from perspiration and accelerated heart rate, fol-

lowed by syncope (fainting). When this occurs, the doctor lightly presses the patient's channel points: Baihui (GV-20), Mingmen (GV-4), Jiangjing (GB-21), and Yintang (Extra Point). The doctor then grasps the shoulders and presses down on the GB-21 points with force. Finally, the doctor emits Qi along the Governing and Conceptual Vessels and leads the patient's Qi to the Lower Dantian. This allows the patient to recover consciousness.

THE INCREDIBLE WONDERS

The Qigong doctor's ability to have complete conscious and automatic control over the patient's reaction to energetic projections constitutes what is known as the Incredible Wonders. When the Qigong doctor takes control over the patient's energetic projections, he or she can willfully initiate the patient to experience various colored lights, sounds, smells and other sensations according to the Qigong doctor's will. This procedure is commonly known as Cultivating the Spirit to Generate Wonders.

When the Qigong doctor emits energy towards patients to treat their diseases, most patients will either instantly or gradually feel some form of energetic sensation from the increased life-force energy. The degree of energetic sensation felt by patients is in accordance with their emotional/spiritual sensitivity and degree of connection to their own physical body.

The sensations of Yuan Qi are the most common reactions felt by both the Qigong doctors and their patients. In rare instances some patients display no physical effects and experience no Qi sensations during treatment. These patients can still achieve good therapeutic results by improving the degree of their emotional/spiritual connection to their body.

In some cases, patients may even feel miserable or uncomfortable. When this occurs, they should continue training so that their Righteous Qi can overcome their Evil Qi. This ongoing battle will also affect their spiritual and emotional being. Fear usually arises at this point causing them to question their ability to continue in their practice. This is a normal transition and can be resolved through encouragement, patience and continual practice.

CONTRAINDICATIONS FOR MEDICAL QIGONG THERAPY

There are several contraindications that the Qigong doctor should be aware of before treating patients, or even prescribing Medical Qigong exercises. The following is a list of different personality types that may be encountered in the clinical settings that require special treatment modifications.

1. The very "nervous" type of patient should not practice Medical Qigong, or must be under strict supervision due to the patient's emotional instability.
2. The "extreme temperament" type of patient who has a fanatical type of personality should also avoid Medical Qigong training or remain under strict supervision. Patients of extreme temperament generally suffer from Excess disorders and compulsive overtraining. They are therefore prone to Qi deviations.
3. The "extremely introverted" type should be careful when practicing Medical Qigong meditations because strong emotions may be set into motion, and even certain mental disorders may be violently released that the patient may have been unaware of.
4. The "narrow minded" type will generally condense Qi into smaller areas of the body causing stagnations. Such patients should be instructed to relax and let go of their stress to allow the condensed energy to disperse.
5. Patients with the following conditions should be restricted to very specific Medical Qigong therapy: serious mental disorders, congestive Heart failure and severe organ failure, severe hemorrhaging, menstruation, nerve suppression, bone fracture, pregnancy, geriatric patients, young children, and cancer patients (Figure 29.3).

- Patients with mental disorders such as schizophrenia and bipolar (previously called manic depression) disorders (or individuals with a family history of such mental diseases), should refrain from training. The Qigong exercises and meditations could induce symptoms of these said disorders, or could enhance


Medical Qigong Prescriptions must be Modified
Mental Disorders
Congestive Heart Failure and Severe Organ Failure
Severe Hemorrhaging
Menstruation
Nerve Suppression
Bone Fracture
Pregnancy
Geriatric Patients
Young Children
Cancer Patients

Figure 29.3. Restricted Conditions for Prescribing Medical Qigong Exercises and Meditations

the symptoms due to the patient's mental and emotional instability.

- Patients with congestive Heart failure and severe organ failure (any internal organ that has experienced an energetic collapse), require that the treatment be specifically oriented towards this condition.
- Patients with severe hemorrhaging require prescriptions that prevent the leakage of Blood and Qi, since Blood and Qi flow together.
- Women during their menstruation cycle should not store Qi in their Lower Dantian. Any Blood and Qi stored in the uterus will purge from the woman's body naturally, drawing with it any Qi stored within the Lower Dantian.
- Patients suffering from nerve suppression (cervical spondylosis) may experience a worsening of their condition. In severe cases, the additional pressure on the nerve roots may complicate the patient's condition, especially when the body's energy field expands causing the Marrow within the spinal column to ascend.
- Patients with bone fractures must first have the bones set correctly and immobilized to prevent further injury. The subtle involuntary movements of the limbs during Qigong treatment or practice can disturb the bone's healing process.
- Pregnant women must be treated by a Medical Qigong doctor who specializes in obstetrics, otherwise the risk of involuntary abortion (miscarriage) or other complications can arise.
- The treatment of geriatric patients prohibits Dynamic Qigong because of the delicate nature of their internal tissues. All exercises and meditations should be kept slow, quiescent, and tranquil.
- The treatment of young children requires that all exercises and meditations be age appropriate, and be specifically oriented toward healing his or her disease. Some Qigong exercises, meditations and treatment methods may interfere with the natural development of the child's internal organs and tissues.
- The treatment of cancer patients requires modified prescriptions in accordance to the specific disease. With certain cancers, Dynamic Qigong is contraindicated to prevent the cancer from further metastasizing.

CHAPTER 30
BALANCING THE BODY'S ENERGETIC SYSTEM

PURGING, TONIFYING, AND REGULATING

In Medical Qigong therapy, successful results can be achieved only when the doctor adheres to the principle of "treating Deficient syndromes with tonification and Excess syndromes with purgation." Tonification supplements the insufficiency and strengthens the body's resistance, while purgation reduces the Excess and expels pathogenic factors. The final aim is to balance Yin and Yang to regulate the physiological functions of the body.

Medical Qigong Therapy adheres to the traditional Chinese medical explanations of illnesses and general principles of healing. Only the techniques used during treatment differ. Qigong doctors Purge the patient's body, then emit Hot or Cold Qi in conjunction with the Five Elemental energies, using various hand manipulations, including: pushing, pulling, rotating, leading, and shaking.

Through energy extension, the doctor can reinforce the patients body's resistance to pathogenic factors, replenish the Yin and Yang organ energy and enhance mental clarity.

THE THREE TREATMENT MODALITIES

Medical Qigong therapy is divided into three treatment modalities (Figure 30.1). These treatment modalities enable the Qigong doctor to purge, tonify, and regulate the patients' body. These techniques are described as follows.

1. Medical Qigong Purging techniques are used by the doctor to treat the patient's Excess syndromes, and to detoxify the body of pathogenic Qi. The "lower aspect" of classical Chinese medicine governs the treatment of the patient's illness and corresponds to Earth. It involves purging pathogenic influences and dispersing stagnations in order to cure the patient's illnesses. This allows the patient the ability to remove Excess Qi from organs and tissues.
2. Medical Qigong Tonification techniques are used by the doctor to treat the patient's Deficient syndromes, as well as strengthen and stabilize the organs and organ systems. The "middle aspect" of classical Chinese medicine governs the nourishment of the patient's nature and corresponds to Man. It involves helping the patient prevent illness by tonifying



In cases of Excess, the doctor should Purge.

In cases of Deficiency, the doctor should Tonify.

In cases of Excess and Deficieny combined, the doctor should Regulate.

Figure 30.1. Purgation, Tonification, and Regulation

Heaven — Regulation — Balance Qi and Blood — Nourish the Patient's Destiny

Man — Tonification — Treat Deficient Conditions — Strengthen the Body to Prevent Illness

Earth — Purgation — Treat Excess Conditions — Detoxify the Body to Treat Illness

Figure 30.2. Ancient Chinese Perspective on Purgation, Tonification, and Regulation

organ energy Deficiencies. This allows the patient the ability to replenish organ energy depletions and tissue emaciation.

3. Medical Qigong Regulation techniques are used by the doctor to balance the patient's Yin and Yang energy, as well as organ Qi. The "highest aspect" of classical Chinese medicine governs the nourishment of the patient's destiny and corresponds to Heaven. It involves regulating the patient's Three Dantians, Taiji Pole, Yin and Yang organs and energy fields. Regulation techniques promote a balance of Jing, Qi and Shen for the optimal development of all the aspects of man, i.e., body, mind, emotion, spirit and energy. Thus, in China, Medical Qigong regulation is said to "nourish the patient's destiny" (Figure 30.2).

PURGATION TECHNIQUES

The patient's body can be dredged and purged by using two different expelling methods. The first method is the direct removal of pathogens from the patient's tissues and organs. The second method is the indirect purging of the patient's tissues and organs through the channels and points of the patient's body. These two methods serve two different purposes: The Direct Removal of Pathogenic Factors, and The Purgation of Channels and Points.

1. The Direct Removal of Pathogenic Factors is achieved through extending Qi into the tissues and organs where they are lodged, and dredging the Toxic Qi directly out of these locations. This method is used to expel pain due to Excess Heat or Cold. The various techniques used in this type of purging employs stationary Qi-guiding manipulations. The various hand manipulations used for the direct removal of pathogenic factors consists of such techniques as: The Five Thunder Fingers Hand Posture, Shaking and Trembling Hand Posture, Bellows Palm, Vibrating Palm, Dragon's Mouth Palm, Tiger Kneading Palm, and Spiraling Palm (see Chapter 33).
2. The Purgation of Channels and Points techniques are used to expel External pathogenic Evils (such as the invasion of Wind, Fire, Heat, Dry, Damp, Cold, and environmental toxins, etc.), or Internal pathogenic Evils (such as fear, anger, and grief, etc.) from the organs and tissues of the body. It is also used to redirect Rebellious Qi (e.g., Stomach Qi). The various techniques used in this type of purging employs dynamic-linear Qi-guiding manipulations such as the Pulling, Leading, and Guiding methods (see Chapter 34).

TONIFICATION AND PURGATION METHODS

The doctor should always purge before tonifying the patient's body. In the clinical setting, these two methods are often used together in combination with other methods in treatment. These combined methods are as follows.

TONIFICATION AND PURGATION WITH RESPIRATION

Tonification occurs as the doctor exhales while guiding and directing Qi into the channels, points, and the internal organs and tissues of the patient's body. Purgation happens when the doctor inhales while guiding, emitting, and leading the patient's Qi, or pulling the pathogenic Evils out of the patient's body.

During treatment, it is important that the patient cooperate with the doctor by matching (if possible), per the doctor's instruction, his or her breathing rhythm to the doctor's treatment. The patient should assume a proper posture (lying, sitting or standing), relax, and concentrate his or her mind on the location being worked on. When the doctor exhales and emits Qi toward the patient, the patient should inhale to absorb the doctor's Qi into the designated location. When the doctor performs purgation, the patient should exhale to release Toxic Qi out of his or her body.

TONIFICATION AND PURGATION ALONG AND AGAINST THE CHANNEL FLOW

With regard to acupuncture therapy, the classics say that, "puncturing along the direction of the channels yields a tonifying effect, while going against it induces purgation." In Medical Qigong, however, due to the Qigong doctor's nature of emitting, leading and guiding the energetic flow of Qi, certain modifications are used. The following are a few examples of tonification and purgation techniques used along and against the energetic flow of the channels:

- Causing Qi to flow up the Yin channels of the legs and into their associated organs in the torso is considered tonification (think of following the river to the sea). One example of this type of treatment therapy is emitting energy into the base of the patient's feet (at the Kd-1 points); this causes the energy to flow into the torso to strengthen the Kidneys.
- Moving Qi from the torso down the legs against the flow of the leg Yin channels is considered purgation (following the river from the sea). One example of this treatment therapy would be pulling Excess Qi from the Liver organ, down the right Liver channel and out the feet to sedate the Liver Fire (the Gall Bladder Channels can be used to purge Excess energy from the Liver organ down the leg Yang channels).
- Moving Qi against the flow of the arm Yin channels into their associated organs is considered tonification (think of following the river to the sea). One example of this treatment would be emitting energy from the base of the thumbs, at the Lu-11 points, into the torso to strengthen the Lungs.
- Moving Qi against the flow of the arm Yang channels into their associated organs is considered purgation (following the river from the sea). One example of this treatment would be pulling Qi against the flow of the Large Intestine Channels down and out the hands to purge Excess Qi in the head.

TONIFICATION AND PURGATION POINT THERAPY WITH THE HORARY CYCLE

When prescribing Jing Point therapy as a means of self-regulated homework, the Qigong doctor encourages the patients to follow the formula of tonification and purgation according to the energetic flow of the Horary cycle. According to ancient Chinese medical theory, the ebb and flow of Qi and Blood along the different channels is related to designated days and hours (see Chapter 11). This theory applies to two specific tissue manipulations: Holding the Point for Tonification, and Closing the Point for Purgation.

- Holding the point for tonification requires the patient to use the Massage Tapping method (see Chapter 37) on specific points two hours prior to its opening or peak flourishing time (high-tide).
- Closing the point for purgation of the internal organs or channels requires that the Qigong doctor drain the diseased area at high-tide (when it is most full of Qi and Blood). When the patient is applying Jing Point therapy for homework prescriptions, however, the application is quite different. This technique requires the patient to use the Massage Tapping method on specific points two hours after its opening time.

The patients may also be instructed in self-massage using the Tapping method for self-healing. If the patient has a Kidney disease, for example, the specific points should not be tapped during its peak time (5–7 p.m.), but rather two hours prior to its peak time (3–5 p.m.). This will improve the Kidneys' function.

TONIFICATION AND PURGATION GUIDELINES

When the Qigong doctor purges and tonifies a patient, he or she must remember to adhere to the following guidelines carefully.

GUIDELINES FOR THE DOCTOR

When treating the patient, the doctor must always consciously direct and be aware of the movements of each hand.

- Generally, the right hand is used for tonification, while the left hand is for purgation. Diseases that require purgation are treated by draining Toxic Qi with the left hand. Diseases that require tonification are treated by extending Qi through the right hand.
- Turning hands towards the body is used for tonification, while turning the hands away from the body is used for purgation.
- Moving the hands away from the body and upward can regulate the Yang energy, causing it to rise, and is inclined to tonify. Moving the hands downward pulls the Yang energy down, and is inclined to purge.
- Clockwise drilling (the palm or extended fingers move in a clockwise direction over an area) is used for tonification and increasing Qi; counterclockwise drilling is used for purgation and decreasing Qi.

GUIDELINES FOR THE PATIENT

The patient, (like the Qigong doctor), must be aware of hand movements when practicing Qigong prescriptions. In addition, the patient must be aware of his or her posture, respiration, and mental attitude.

- The eyes are open for purgation; closed eyes are used for tonification. The patient should apply these principles according to the symptoms of the disease.
- Inhalation is used for tonification, exhalation is used for purgation. During purgation treatments, the patients assume the proper postures, relax, and concentrate their mind on the disease area while exhaling the pathogenic Qi. This exhalation technique is used not only to promote the removal of the surfacing toxins, but is also used to enhance the doctor's efficacy in purging the diseased area.
- The audible and silent tone resonations (see Chapter 40) also have the function of either tonification and purgation. Speaking the silent tone when inhaling can be used for tonification; while exhaling, the tone is used for purgation.

UNDERSTANDING MEDICAL QIGONG REGULATION

The Qigong doctor must master three main techniques of Qi regulation to facilitate clinical healing through Qi emission. These techniques include: Training the Qi, Guiding and Inducing, Tonifying and Purging the Qi, and Emitting the Qi.

1. Training the Qi exercises and meditations are used to gather Qi and to promote its circulation within the body. The Qigong doctor must have an extensive comprehension of several Medical Qigong techniques used to gather and circulate energy throughout the body. This includes a complete understanding of Postural, Respiratory, and Mental Dao Yin modalities, as well as the static and dynamic clinical modalities. These training techniques provide the Qigong doctor with the ability to regulate and balance the patients' Qi, and set the foundation for the patients' Medical Qigong prescriptions.
2. Guiding and Inducing, Tonifying and Purging the Qi are used to circulate Qi within the external field of energy (Wei Qi). These techniques require a complete understanding of guiding and inducing (leading the Qi), and tonifying and purgation techniques, to being able to rectify Qi deviations and remove energy blocks.

These training techniques provide the Qigong doctor with the foundation for the patients' Medical Qigong therapy.

3. Emitting Qi techniques must be learned and perfected by the doctor. The Qigong doctor must have an extensive understanding of the multiple techniques used to extend Qi into the patient's body. These include electromagnetic energy, light, sound, and hot and cold Qi projections. These training techniques and abilities also set the foundation for the patients' Medical Qigong therapy (see Chapter 34).

QI REGULATION AND GUIDING PRINCIPLES

Qi regulation is considered a combination technique for reinforcing and reducing. It is used to readjust and balance the Yin and Yang energy. If the patient's Qi rises adversely, the doctor should guide and secure it downward. The same principle is applicable for any Deficiency or Excess of Qi in the left or right sides of the patient's body.

Qi regulation also includes purgation after tonification, and tonification after purgation. This method of guidance is used when Qi stagnation, stasis of Blood, or disorders of the channel Qi develop. Under pathogenic conditions, Qi of the viscera and channels may become weak and stagnant. This is manifested by symptoms such as listlessness, general weakness, and the hypofunction of certain organs or tissues. Stagnation of Qi and stasis of Blood can also obstruct the channels causing pain. Pain may also be caused by outside pathogenic factors such as trauma, inflammation, muscular spasms, and adhesive degeneration. In these circumstances, the channels are dredged to promote Blood circulation, and to remove the stasis in order to relieve spasms, and dispel pain.

Every organ in the body has its own Qi that circulates and interacts with the rest of the body. When the normal function of the organ is affected, the circulation of Qi may become disturbed. This disturbance of Qi in one organ may influence the functional balance of the whole Qi system.

The doctor regulates the patient's channel Qi by dredging the channels and collaterals. This facilitates Qi circulation and leads Qi back to its origin. In the case of a weak and hypofunctional Lung Qi, for example, emitting Metal-Qi plus Pushing, Shaking and Leading manipulations (see Chapter 34) can be adopted to activate the Lungs' Qi. The combination of these techniques causes the channels' Qi to overflow freely, thus improving the function of the Lungs.

ENERGY BALANCING PROCEDURES

When extending energy into the patient the main emphasis is placed on balancing the patient's energetic fields. The doctor must have both physical and emotional releases from the patient's body, to detoxify and liberate the trapped Qi.

It is important to not let the patients avoid facing their problems; keep them centered around the troubled area, focused on the awareness of what they are feeling. Basic energy balancing procedures are as follows.

1. If the treatment area is Hot, cool it down. The doctor must continue treating the patient until the Hot area has cooled. A strong and quick moving hand gesture is best used to treat a Heat syndrome.
2. If the treatment area is Cold, heat it up. For a Cold syndrome, use a longer treatment to warm up the channel in the area treated, to eliminate the Cold.
3. If the tissue's energy is dark or cloudy, change it to light and clear.
4. If you feel tingling on any area or organ, remain there until the tingling subsides and the organ or area completes its energetic unwinding. Tingling in an area indicates that the patient's body is releasing an energetic cluster. The patient may or may not be aware of any feelings or sensations when this occurs.
5. If the area is emitting electric shocks, dampen or sedate it by connecting it with its associated organ. Connecting Yang (positive) into Yin (negative) will ground the energy.
6. If you sense pressure or Excess, dredge the area, and circulate the Qi.
7. If you feel intense pulsation, decrease the intensity and make it rhythmical.
8. When treating an energetic field that is De-

10. Let the positive Heart energies of love, joy and happiness activate the positive Spleen energies of openness and fairness and centeredness. Blend this with the Universal energy and feel the yellow light descending to the Heart and Spleen.
11. Let the positive Heart energies of love, joy and happiness activate the Lung energies of courage, strength and righteousness. Blend these energies with the Universal energy and see the white light from above flow into the Heart and Lungs. Let the Positive Heart energies of love, joy and happiness activate the Kidney Energies of gentleness, softness and calm in the Kidneys. Blend both energies with Universal Energy and see the blue light coming down from above into the Heart and Kidneys.
12. Let the positive Heart energies of love, joy and happiness activate the Liver energies of kindness, generosity and benevolence. Blend these energies with Universal energy and see the green light flowing from above into the Heart and Liver. You can do this meditation a few times.
13. Blend all the positive organ virtues in the Heart, creating Compassion Energy. You may manifest this as a Pearl. Move it in the Microcosmic Orbit spiralling it from 10,000 to 60,000 times a minute.


Fire
Wood
Earth
Water
Metal
S
Love
Fire-Li
Yang
Red
Summer
Fairness
Earth-Kum
Harmony
Yellow
Indian Summer
Wind
E
Kindness
Thunder-Chen
Lighing
Green
Spring-Wood
W
Courage
Lake-Tui
Rain
White
Fall-Metal
Mountain
Heaven
Blue
Winter
Water-Kua
Yin
Gentleness
N

Yin movement Feeds

Fig. 6.39 *Creation Cycle*



Figure 30.3. Locations of Energetic Blockages

pressed (sinking or contracting inward), use an "ascending method" of Qi manipulation for tonification (i.e., move and emit Qi from the lower areas of the body upwards). Some examples of this type of ailment are:

- Lower Burner Depression
- Middle Burner Depression
- Immune System Depression and Breakdown
- Autoimmune Diseases (Lupus and Fibromyalgia)
- Chronic Fatigue Syndrome
- Heart Failure
- Kidney Failure
- Prolapse of the Stomach

9. Assign Medical Qigong prescriptions for patients, including meditations and exercises, as needed.
10. Treat patients with severe diseases by:
    - Stopping and controlling the spread and development of the disease,
    - Stopping the patient's Excess consumption of Qi,
    - Treating the cause and root of the disease, after the patient's condition is under control, and
    - Assigning homework.
11. For chronic diseases, use the method of purging and dredging stagnation to move any impacted Qi.
12. For sprains, use Qi compression (using the Qi to press the tissues) around the local area. Close the channels surrounding the sprain first, isolating the trauma. Then pull out the stagnant Qi. If the doctor immediately treats the local area, he or she will disturb and further complicate the injury. It is important to close off the surrounding channels around the wound first, leaving only the affected channel open, before pulling out the stagnant Qi. This controls the flow of energy in to the stagnated area.

Check the patient after seven treatments to determine if the therapy has been effective. Reevaluate each patient according to each individual's constitution.

CLINICAL OBSERVATIONS OF PATHOLOGICAL ENERGETIC PATTERNS

When the Qigong doctor begins to treat patients, certain energetic observations and phenomenon will be experienced while diagnosing the energy inside the patient's tissues. These energetic experiences are quite different from the Eight Energetic Touches which focus on the feelings of the body after meditation practice (see Chapter 29). The Internal conditions of the patients' disease, its energetic nature, as well as its clinical manifestation, are expressed through the following: Hot, Cold, Deficient, Excess, moving, stagnant, Damp, Dry, Clear (Clean), Turbid (Impure), open (accessible), closed (armored), and leaking.

LOCATIONS OF ENERGETIC BLOCKAGES

In clinical practice we generally observe six main areas in the patient's body where energy becomes trapped and blocked. Each energetic blockage is an expression of the patient's ability to armor and protect him or herself from emotional wounding. These six main areas in the patient's body can be the foundational base and the root cause for the patient's disease (Figure 30.3). These six main areas are described as follows.

THE AREA OF THE HEAD

The area in the cranium that is most commonly obstructed is within the base of the occiput, at the back of the head. This obstruction is usually noted within patients who suffer from migraine headaches and brain tumors. This barrier is often created through chronic stress patterns which cause the Liver's Heat to rise up the patients' back and become trapped inside the head. This condition is usually caused by intense concentration. Too much hard focusing can also cause Qi to condense and stagnate. The location of Qi obstructions due to physical trauma vary according to each type of trauma, and the and the severity of the injury.

THE AREA OF THE THROAT

This area separates the Upper Dantian (the spiritual/perceptive center) from the Middle Dantian (the emotional/empathic center). Messages of divine inspiration and awareness descend downward from the Heavens through the Baihui area seeking to stir the emotions of the Heart. If the patient is not receptive (due, for example, to a disconnection or even a resistance to spiritual growth) a barrier is sometimes formed within the patient's throat, dividing the Upper Dantian from the Middle and Lower Dantians.

This barrier can also be created to stop emotions from flowing through the Heart and rising upward to be released through the windows and caverns of the soul (the eyes, ears, nose, tongue, body, and spirit). If, for example, the teeth become clenched and the throat tightens from feelings of grief or anger, these emotions can become trapped in the throat, forming a "plum seed" or "knot." When the Lungs' Qi congeals in the areas of the upper chest, shoulder blades, neck and the back of the occiput, this indicates chronic suppression of these emotions. It is also evidence of the mind and body struggling to reconnect and express the emotional and spiritual self.

THE AREA OF THE HEART

The Heart is energetically divided into two main chambers. The upper chamber houses and responds to spiritual emotions, while the lower chamber houses and responds to sensual emotions.

Patients will tend to suffer not only from repressing their basic biological drives (the sensual emotions based in the lower chamber of the Heart), but also by repressing their emotional connections with the divine (by failing to accept their higher spiritual calling or spiritual enlightenment associated with the upper chamber of the Heart). The higher self is the focal point of the superconscious realm; it is all-inclusive and at the very center of our being where individuality and universality blend (center core).

Patients who have chronically armored their Heart tend to exist in a state of guarded suspicion. This pattern of emotional suppression tends to lead to Qi stagnation and the creation of disease. When patients armor their upper chamber, they tend to hide in the emotions of their lower chamber and visa versa. Patients who armor the upper chambers of the Heart, for example, may become involved in relationships of extreme sensual passions related to the Heart's lower chamber, to avoid painful unresolved issues hidden within the past. The deeper and more energetically charged the issues, the stronger the sensual passions. Whereas, patients who armor the lower chamber of the Heart, might become involved in relationships of extreme spiritual, or religious passions related to the Heart's upper chamber to hide from their painful unresolved issues. The deeper and more energetically charged the issues, the stronger the spiritual or religious passion.

THE AREA OF THE DIAPHRAGM

The diaphragm area separates the Middle Dantian (the emotional center) from the Lower Dantian (the physical/sexual center). When a barrier in this particular area is created, it separates the emotional Heart from feeling the sexual passion which rises up from the Lower Dantian and the Kidneys' area.

It is interesting to note that patients with a


Energetic Complications and Stagnations
Compressed Energy Stagnation
Contracted Energy Stagnation
Bloated Energy Stagnation
Expanded Energy Stagnation
Energetic Armoring
Energetic Depletion
Energetic Leakage
Migrating Qi Deviation
Psychosexual Qi Deviations

Figure 30.4. The Body's Energetic Complications and Stagnations

barrier in the diaphragm sometimes enjoy the physical sensations of sexual intercourse, but are separate from their spiritual/emotional connection to true bonding or "oneness" with their partner. Again, the connection between the emotional spirit and body/mind has been severed.

THE AREA OF THE YELLOW COURT

The Yellow Court (CV-12) is an area located in the center of the chest, just below the diaphragm and xiphoid process of the sternum. Its function is that of being the access area to release the body's internal organs' emotional memories. Its location is also attributed to the Third (solar plexus) Chakra.

To access the patient's stored emotional memories and release them from the Yellow Court, the Qigong doctor supports the patient's Shendao GV-11 (Spirit Gate) with the left hand while energetically manipulating the patient's Yellow Court area with the right hand. If the patient is not energy sensitive, the doctor uses a slight Compression/Release technique (see Chapter 37) to disperse the patient's armoring system.

The patient should be in a supine position, with knees pointed upward, feet flat, arms by his or her sides, mouth open, inhaling deeply into the Lower Dantian. As the patient exhales, the doctor lightly compresses the patient's Yellow Court until a deep groaning sound begins to resonate from the patient's thorax. The doctor circulates the energy from the patient's Yellow Court into the Shendao, filling up the patient's Heart with energy. The doctor then moves this energy back into the patient's Yellow Court. This process continues until the patient's suppressed emotions surface and are released.

Note: It is important to first purge and release the Lungs of grief before attempting to access the patient's Yellow Court.

THE AREA OF THE LOWER ABDOMEN

This area also separates the Lower Dantian from the Middle Dantian, insulating the sexual feelings from the middle and lower torso. This energetic freezing of the pelvis is usually found in victims of rape, sexual molestation, or in women who have had one or more abortions. The Qi flowing into the lower pelvis and legs becomes blocked due to stored fear, shame, guilt, and sorrow. Sometimes the patient's physiology in that particular area may become obese; the abdomen, thighs or hips may be heavily padded and armored due to Qi stagnation. Often times, victims of childhood sexual abuse become overall obese to avoid attracting the opposite sex, or to block and pacify these hidden traumatic memories.

TYPES OF ENERGETIC COMPLICATIONS

Each organ and channel has the potential to carry or create several types of energetic complications and stagnations. The doctor should observe and feel the shifts in the patient's energetic balance to determine the specific conditions of the disorder (Figure 30.4).

COMPRESSED AND CONTRACTED ENERGY STAGNATION

Compressed or Contracted energy stagnations are sometimes considered a Yin condition due to the type of energetic compression involved in its formation.

- Compressed Stagnation is caused by the patient's energy pressing downward (externally moving inward) and will feel armored and hollow (Figure 30.5). When this type of energetic stagnation disperses it does not energetically unwind, but disperses and dissolves into the surrounding tissue areas. Because the patient's surrounded consciousness has armored the tissue area, the energetic dispersion can sometimes cause spontaneously released emotions or behavior such as crying, laughing, shouting, screaming, sighing, coughing, etc.
- Contracted Stagnation is caused by the patient's energy pulling inward, and will generally feel armored and solid (Figure 30.6). This type of energetic stagnation can be formed by an emotional core, or focused concentration, that draws additional Qi into its center, compacting the belief structure, layer after layer with energy. When this type of energetic stagnation disperses it can sometimes begin energetically unwinding throughout the entire body. This energetic unwinding sometimes creates involuntary muscle twitches and physical undulations.

Body tissues and muscles accumulate emotional energy, becoming hard and tense in the adjacent areas. Denseness indicates the accumulation of pathogenic stagnant Qi. If this energy block remains, disease can manifest as ovarian cysts and tumors, or even in extreme cases as cervical cancer. Breast cysts, tumors, and cancer can result from stagnant Qi in the Lungs, or from a combination of Lung and Liver Qi stagnation. This type of stagnant energy feels very Hot and volatile because of the accumulated anger and rage.



Figure 30.5. Compressed Stagnation



Figure 30.6. Contracted Stagnation

Treatment Principals for Compressed and Contracted Energy Stagnation

The Qigong doctor disperses and purges the patient's stagnant Qi using the Thunder Palm technique, Tiger Kneading techniques, and counterclockwise Circular Spiraling (see Chapter 34).

BLOATED AND EXPANDED ENERGY STAGNATION

Bloated and Expanded energy stagnations are sometimes considered a Yang conditions due to the type of energetic expansion involved in their formation. Qi stagnation, with a characteristically expansive or bloated appearance, can be caused from an accumulation of Phlegm and Body Fluids (in addition to Qi and Blood) in the adjacent tissue areas of the body (Figure 30.7 and 30.8). This type of stagnation usually occurs in the Lower Dantian and abdominal areas. These are examples of Excess syndromes of stagnant energy and manifest as: distending, turbid, leaking, tingling, and dense Qi.

If this type of energy stagnation remains obstructed, the resulting disease can manifest as edema within the tissues, colitis, or angina pectoralis due to unprocessed despair and grief (in the Lungs) with anxiety (in the Spleen). The energy of grief and despair feels thick, heavy, and slimy like phlegm or mucus. Often this energy is felt in the Lungs, as well as in the Spleen.

Treatment Principals for Bloated and Expanded Energy Stagnation

The Qigong doctor disperses or dissolves the patient's stagnant Qi by using the Tiger Kneading, Vibrating Palm, and Shaking Palm techniques (see Chapter 34).

ENERGETIC ARMORING

This condition can result from the patient protecting specific tissues, organs, or areas of the body. Energetic armoring is initiated when the patient freezes certain emotional feelings to maintain the denial system. Patients may be unaware of this armoring condition because they dissociate from the original trauma, or minimizing its severity. Emotions attributed to energetic armoring are generally manifested as anger, fear, guilt, and shame. The angry patient's denial system is maintained through physically or emotionally attacking others; the anxious patient, full of fears, guilt, and shame, copes by "Shening out." Both of these reactions shield the patients in emotional situations from their own feelings, while reinforcing the energetic armoring.



Figure 30.7. Bloated Stagnation



Figure 30.8. Expanded Stagnation

Armoring results in tense organs and tissues. When patients cannot feel their body, other complications can arise, such as compressed, contracted, bloated or expanded energetic stagnations.

Treatment Principals for Energetic Armoring

The Qigong doctor can assist the patient through "soul retrieval" to unlock the feelings logged deep within the body's tissues (see Chapter 19). The primary goal is to first help the patients acquire a sense of security within their own body, then address the root of the disease.

ENERGETIC DEPLETION

Whole body depletion results from the following conditions:

- Not receiving enough Postnatal Qi for restoration, resulting in improper internal organ functioning,
- From suppressing emotions (e.g., worry or fear),
- Experiencing a damaged energetic field due to trauma, or
- Being born with a Deficient prenatal constitution.

Generally, energetic depletion can result in physically undeveloped areas in the body. In some cases, emotional traumas can cause specific organs or tissues to become energetically depleted to the degree that their natural development cannot take place.

Treatment Principals for Energetic Depletion

The Qigong doctor, if qualified, can assist the patient by prescribing herbal tonics. The patient should also be encouraged to eat regular, nutritional meals and to balance work with relaxation time. If the patient's energetic field has been damaged, the Qigong doctor can repair it by using Flat Palm and Circle Spiraling techniques (see Chapter 34).

ENERGETIC LEAKAGE

Energetic leakage is a result of the patients releasing Qi from out of their joints, due to injury or unconscious sabotage. When energy drains from the patients' joints, the specific areas along the channels become depleted, resulting in a Deficient Qi which can cause an atrophy syndrome. Any type of energetic thinness along the Wei Qi field indicates an insufficiency of Qi. A Deficient energetic field can result in an empty, numb, or weak feeling of Qi within the tissue areas.

Treatment Principals for Energetic Leakage

The doctor envelops the patient's depleted tissue area (which is leaking) with Spiral Wrapping techniques to create an energetic cast that allows the patient's energetic field to completely heal (see Chapter 34).

MIGRATING QI DEVIATION

Migrating Qi Deviations can result from either the patient's suppressing and avoiding feelings, or from Wind invasion (either Internal or External). In Traditional Chinese Medicine this condition is known as Wind Bi (Wind Pain) or Wandering Bi (Migrating Pain). Once patients feel cornered by a specific memory, they subconsciously shift the toxic energy to another part of their body; this energetic shifting requires the treatment to be restarted. When treating these patients, it is important to first connect the original trauma to the Heart to prevent these energetic shifts, and to stabilize the condition. Once stabilized, disperse the Wind Invasion and tonify any Deficient organ.

Treatment Principals for Migrating Qi Deviation

The Qigong doctor first envelops the primary area of complaint, isolating the pain, and then begins to internally Spiral Circulate the patient's internal Qi. Once the energy is in motion, the doctor leads the Toxic Qi out of the patient's body.

PSYCHOSEXUAL QI DEVIATION

Psychosexual Qi Deviations can result from an immediate energetic tissue over-stimulation. Patients with this condition experience intense sexual undulations and orgasms when being treated in a safe clinical environment. This reaction is due to their avoidance issues, brought about by an energetic trigger mechanism. This psychosexual reaction usually takes place when touching any part of the torso or extremities. Because the energy seeks balance (much like water), when it flows into the genital area, the sexual neurons become overstimulated, activating and releasing the energetic turbulence already stored therein. This condition is mostly found within patients who have either been raped or molested as children.

Treatment Principles for Psychosexual Qi Deviation

The doctor is encouraged to refer the patient to a psychotherapist who specializes in such trauma. Meanwhile, the doctor continues to treat the patient by rooting the patient's Heart (emotional chamber) to the patient's Lower Dantian (sexual chamber). Once this connection is established, the doctor reconnects the patient's Lower Dantian to the patient's Upper Dantian (spiritual chamber), forming a complete body connection within the patient's Taiji Pole. By reconnecting the sexual chamber with the spiritual chamber, the doctor empowers the patient, allowing the patient to reclaim his or her true sexual/ spiritual identity.

PATIENT'S ENERGETIC FACIAL DISTORTION

Sometimes, when treating a patient, the Qigong doctor will notice the patient's facial features energetically distort, changing their facial pattern. These facial distortions can appear and disappear rapidly, or maintain their illusion for several seconds. The cause for the patient's energetic facial distortion can be brought on by several factors: The Patient Reliving A Past Trauma, The Ancestral Patterning of the Patient's Jing, or The Energetic Manifestations of the Patient's Active Spiritual Guardians.

1. The patient reliving a past trauma can release an energetic distortion that expresses itself on the energy field of the patient's face. This projected image reflects the age and time frame wherein the patient received the initial trauma. Often, as the doctor connects with the energetic root of the patient's disease, the patient's face will regress to reveal the delicate features of the patient as a young child. This visual facial pattern of energetic age regression reveals the exact age the patient suffered the initial trauma.
2. The ancestral patterning of the patient's Jing can also be released as energetic distortions that express themselves on the energy field of the patient's face. Occasionally, these projected images can reflect the patient's ancestry, or reveal an ancestral guide. Multiple projections of racially identifying features; images of men, women, and sometimes children will appear to shadow the patient's features, much as a projected image over an original form.
3. The energetic manifestations of the patient's spiritual guardians are believed to project their image onto the face of the patient during treatment. Some cultures accept that these guides manifest in the form of animals. The animal form will appear to flicker across the patient's face and then dissipate. This phenomenon is the most rarely seen of all the energetic facial distortions.

PATIENT RESISTANCE TO ENERGETIC THERAPY

Sometimes, in order to avoid the painful memories, the patient will subconsciously sabotage the treatments. Resistance can manifest in one of four ways.

1. Falling asleep is a form of physical escape.
2. Excessive talking is a mental form of avoidance behavior.
3. Irritability or sexual response is a form of emotional escape.
4. "Shening out," also called "spacing out," is a form of spiritual escape.

When observing these patterns, the doctor encourages the patient back into the body to feel the emotions and memories trapped in the particular areas being treated. It is important for the doctor to let the patient know the cause and effect of the patient's chosen defense mechanism. These personal conversations are necessary for the patient's growth and emotional healing. In cases of sexual response, tact and appropriate professional boundaries are especially important.

When emitting Qi, the doctor can encourage the patient's Shen to stay in its residence by asking the patient to focus his or her breathing on the tissue areas being treated. This focused attention causes the patient's Po to settle and calm themselves within the patient's body, allowing the patient's Hun to communicate the feelings surfacing within the patient's Heart.

UNBLOCKING THE FIVE PASSES

The Wu Guan or Five Passes refer to the five important gates on the Governing Vessel. These gates, or passes, are sometimes called Tie Bi, which translates as the "iron wall," and are the areas of the body where it is most difficult for the energy to pass through when circulating the Microcosmic Orbit. Free passage through the Governing Vessel is important, especially when tonifying the patient's body or regulating the patient's Qi. To circulate the Qi up the Governing and down the Conception Vessels, these five gates must remain open.

Opening these Five Passes are essential for the treatment of diseases in the neck and lumbar-sacral regions. In Medical Qigong therapy, disease is sometimes an indication that both the Governing and Conception Vessels have been, or are, in a state of disconnection. If disorders of Qi, along with Qi obstruction, develop along the Governing and Conception Vessels, the doctor should emit Qi into one of the Five Passes (depending upon the affected area) to facilitate the regulation of Qi (Figure 30.9).

THE LOWER SPINAL PASS

The Lower Spinal Pass or "Coccyx Pass" (Wei Lu Guan) is located on the lowest segment of the spine just posterior to the anus, near the Chang Qiang GV-1 point. If Qi becomes blocked in this area the patient suffers a dull persistent pain by the coccyx, along with feelings of heaviness.

To treat, have the patient direct energy up the Lower Spinal Pass, using mild or gentle intention; have the patient position the tongue against the upper palate and inhale deeply while gently contracting the anus and abdominal muscles. These gentle contractions of the muscles along with the position of the tongue on the upper palate create an energetic sacral pump, which facilities the release of the energetic block.

THE MIDDLE SPINAL PASS

The Middle Spinal Pass consists of the Mingmen (GV-4) area and two points (Jia Ji Guan) located on the lateral sides of the Mingmen. If Qi becomes blocked in these areas the patient suffers a dull persistent pain in the middle of the spine, or on one or both sides of the Mingmen. This obstruction causes a physical sensation that feels like a spinal rupture, break, or herniated disc near the waist area when Qi circulates through these points.

To treat this disorder, the doctor extends Qi into the patient's Middle Spinal Pass, while leading the patient's energy upward along the Governing Vessel.

THE UPPER SPINAL PASS

The Upper Spinal Pass is located between the shoulders on the Shendao point (GV-11) Spirit Gate. If Qi becomes blocked in this area, the patient suffers a dull persistent pain on the midline of the upper back below the fifth thoracic vertebra. This obstruction causes a physical sensation that feels like a spinal rupture, or causes intense Heart pain when Qi circulates through this point.



Figure 30.9. The Five Spinal Passes

To treat this condition, the doctor extends Qi into the patient's Upper Spinal Pass, while leading the patient's energy upward along the Governing Vessel.

THE OCCIPITAL PASS

The Occipital Pass (Yu Zhen Guan) is located just inferior to the occipital bone where the brain originates. If the Qi becomes blocked at this area, the patient suffers a dull persistent pain around the occiput, stiff neck, feelings of heaviness, as if there is something were stuck inside the back of the head.

To treat this problem, the doctor should instruct the patient to close the eyes, raise the head slightly and look upward, while gently concentrating on the Baihui GV-20 point. Have the patient imagine the energy block as a cube of ice. The ice melts into water, the water dissolves into vapor, and travels upward along the Governing Vessel into (and through) the Baihui area, then proceeds down the Conception Vessel toward the Lower Dantian.

THE CRANIAL PASS

The Cranial Pass is located at the vertex on the midline of the skull. If the Qi becomes blocked at this area, the patient suffers a dull persistent pain around the eyes and the top of the head, as well as feelings of heaviness, as if there is something were stuck inside the top of the head.

To treat this condition, the doctor instructs the patient to close the eyes, raise the head slightly, while gently concentrating on the Lower Dantian. Have the patient imagine the energy block as a cube of ice. The ice melts into water, the water dissolves into vapor, and travels downward along the Conception Vessel toward the Lower Dantian.

FURTHER COMPLICATIONS

In balancing the patient's energetic body, the doctor first locates the Excess or Deficient condition, determines if the tissues should be tonified, purged, or regulated, then ascertains which energetic complications have initiated the patient's disease.

The doctor must also determine if the patient is sensitive to treatment or resistant to energetic therapy. Below is a summary listing several energetic complications and suggestions on how to rectify them.

1. For Compressed Stagnation, break up the stagnation, purge the pathogens, then tonify and regulate the patient's Qi.
2. For Contracted Stagnation, break up the stagnation, purge the pathogens, then tonify and regulate the patient's Qi.
3. For Bloated Stagnation, break up the stagnation, purge the pathogens, then tonify and regulate the patient's Qi.
4. For Expanded Stagnation, break up the stagnation, purge the pathogens, then tonify and regulate the patient's Qi.
5. For Energetic Armoring, access the patient's Heart (through the Shendao GV-11 area), and induce "soul retrieval" (see Chapter 19).
6. For Energetic Depletion, tonify and regulate the patient's Qi.
7. For Energetic Leakage, envelop the patient's tissues creating an energetic cast to stabilize the energetic fields.
8. For Migrating (Wandering) Qi Deviations, purge the pathogens and then isolate and stabilize before tonifying and regulating the patient's Qi.
9. For Psychosexual Deviations, root the patient's Heart, then regulate the patient's Taiji Pole with divine healing light.

CHAPTER 31
THE MAGIC SQUARE OF THE YELLOW RIVER

The configuration known as the Lo Shu (Lo Writings) or Magic Square of the Yellow River, is shown below. It is said to have been derived from markings on the shell of a "spiritual turtle" that crawled out of the River Lo when the Emperor Yu was draining off the floods. It is considered a mathematical model of the universe. The relationship between the numbers presented in this chart may be used to diagnose the energetic relationship between universal and environmental phenomena, as well as the various pathologies within the occurring internal organ correspondence.

It corresponds to the Later Heaven sequence of the trigrams of the Yi-Jing (I-Ching) and is arranged in accordance with the directions of the compass, with the number "5" at the center of the compass, in an arrangement known as the "Magic Square."

The numerals 1–9 are assigned to each position in accordance with the Lo Scroll markings and represent the Acquired Essences (Postnatal Jing).

Understanding the concept of balance is paramount in Qigong medicine. When Yin and Yang energies in the body are balanced, health is established. The Chinese have given numerical relationships to Yin and Yang properties representing this dynamic connection.

Yang energy is represented by all the odd numbers (1, 3, 5, 7, and 9). Yin energy is represented by all the even numbers (2, 4, 6, and 8).



Figure 31.1. Yin and Yang Number Balance



Figure 31.2. The Magic Square

The cycling of Yang (odd numbers) and Yin (even numbers) indicates the law of motion of Yin and Yang in all things. In Chinese medicine the numerical configuration is based on the sum totaling ten (Figure 31.1).

The numbers arranged together create what is known as the Magic Square. Investigation will uncover several numerological correspondences (Figure 31.2). The sum of any two numbers opposite each other in a row, column, or diagonal (with the number "5" between them) equals 10; thus the sum in any of these rows, columns, or diagonals equals 15. Fifteen is the number that represents "Man," who lives between Heaven above (the number being 20, which equals the sum total of the four primary directions) and Earth below (the number also being 20, which equals the sum total

14. This completes the basic Fusion practice. These steps will be repeated through the rest of the formulas in the book. In the beginning it seems like a lot of work in constructing all the pakuas, chanting, collecting the energy to fuse into the pearl. Once this formula is set up, the whole process happens very quickly. It is not necessary to do all the steps every time. You might only want to chant the trigram one time instead of three. Remember, these extra steps are there to increase the strength of the pearl and expand our consciousness to connect with the Universe. With this powerful pearl it is time to begin Cosmic Fusion with the Creation Cycle.

Begin Cosmic Fusion: Creation Cycle

1. Activate the compassion fire and multi-orgasm energy and combine them together connecting with the universe.
2. Form the pearl through the fuse from the inside to the universe and from the universe and back to the body to the form a pearl. Bring the Pearl down to the Perineum.
3. Feel the pearl connecting to the kidney energy.
4. Listen to the Gentleness Virtue of the Kidneys.
5. The negative emotion of fear has already been removed from the kidneys. The energy remaining in the kidneys is their virtue energy of gentleness. Listen quietly to the gentleness of the kidneys, and be aware of the qualities of gentleness energy: **cold, calm, blue, soft** and **silky** and **tenderness**. Enjoy these qualities. You can intensify them by concentrating on them. Bring the pearl from the perineum to the kidneys, and add the gentleness energy to the pearl at any moment when you feel the pearl weak, just form another pearl.
6. Now bring the pearl back to the kidneys collection point at the perineum, where the gentleness will grow in intensity. All of the neutralized energy that is the pearl now will take on the virtue energy of gentleness.

SW = 2 } SE = 4}
NE = 8 } NW = 6}
10 + 10 = 20 Yin Earth Qi

S = 9 } W = 7}
N = 1 } E = 3}
10 + 10 = 20 Yang Heaven Qi

Figure 31.3. Heaven and Earth Numbers

of the four secondary directions). The numbers in the four primary directions (north, south, east and west) are odd and represent Yang Heaven Energy, while the numbers on the corners are even and represent Yin Earthly Energy (Figure 31.3).

EARTHLY YIN ENERGETIC FLOW

The numbers on the corners of the Magic Square are "terrestrial" in design. All the terrestrial numbers are even numbers. They represent the Earth's energetic field and flow counterclockwise in their circular progression. These terrestrial cycle phases are expressions of Earthly Yin energy and are designed in progressions of "times two." For example, (2) Fire: 2 × 2 = (4) Metal: 4 × 2 = (8) Wood: 8 × 2 = (16) Water (which is reduced to 6, as the ten position is not counted): 16 × 2 = 32 (which is reduced to 2). This completes one cycle in the terrestrial progression, which then returns to the element Fire and begins all over again in the same fashion, continuing in an endless progression of "times two." (Figure 31.4).

Through understanding the Yin energetic progression, the Qigong doctor rotates the patient's energy in a counterclockwise direction to purge Excess conditions and expel pathogenic Qi (called "Yin destroying Evils").

HEAVENLY YANG ENERGETIC FLOW

The numbers on the sides of the Magic Square are "celestial." All the celestial numbers are odd numbers. They represent the Heaven's energetic field and flow in a clockwise circular progression. These celestial cycle phases are expressions of Heavenly Yang energy and are designed in progression of "times three." For example, (1) North: 1 × 3 = (3) East: 3 × 3 = (9) South: 9 × 3 = (27) West (which is reduced to 7, as the ten position is not counted): 7 × 3 = 21 (which is reduced to 1). This completes one cycle in the celestial progression, which then returns to the North and begins all over again in the same fashion, continuing in an endless progression of "times three."

In understanding the Yang energetic progression, the Qigong doctor will rotate the patient's energy in a clockwise direction to tonify. This technique facilitates the continuous circulation of Yang Qi and is used in order to help the tonification of Qi and Blood and replenish Deficiencies (called "Yang promoting growth").


South
Front
Heaven Cycle
Yang
Metal
Fire
Left
East
Right
West
Center
Earth
Earth Cycle
Yin
Back
North
Wood
Water

Lo Scroll

	South East	South	South West	
	☴ (GB-41) 4 Belt Vessel	☲ (Lu-7) Heart 9 Fire Conception	(Kd-6) ☷ 2 Yin Heel	
East	Liver (TB-5) ☳ 3 Wood Yang Linking	5 Spleen Earth	(SI-3) Metal Lungs 7 ☱ Governing	West
	Yin Linking 8 ☶ (Pc-6)	Yang Heel (Bl-62) Kidneys 1 Water ☵	Thrusting 6 (Sp-4) ☰	
	North East	North	North West	

The Magic Square

Figure 31.4. The reason the South is positioned on the top of the page is because, in China, maps were specifically designed for the convenience of the Emperor, whose throne was always positioned facing South, the direction of Yang energy. As the magistrates of his court unrolled the maps before him, the East would be positioned on his left, the West to his right, and the South furthest away at the top of the map (whereas, in the Western culture North is at the top).

THE MAGIC SQUARE AND EIGHT TRIGRAMS

The following Eight Trigram Hand chart represents the terrestrial aspect of the body's acquired structures, evolution, and exchange of Yin / Yang energy.

It should be noted that if the trigrams associated with the numbers shown in the Magic Square are placed in their correct positions, the postnatal or "Later Heaven" trigram arrangement will form. The middle number "5" does not correspond to a trigram because it is the unifying number placed in the center.

In order to use the Eight Trigrams in conjunction with the Magic Square, the patient's palm is divided into nine sections. The Eight Trigrams form the exterior of the palm, while the heart of the palm (known as the Bright Hall or Ming Tang) aligns the Magic Square to the patient's internal organs. The Qigong doctor observes the color, luster, sinking or bulging of skin, as well as any prominent blue veins appearing on the surface of the patient's skin. These observations are compared to the organs and functions associated with each trigram that rules that particular area of the patient's palm (Figure 31.5).

1. The Trigram Kan, located at the base of the palm's heel, is associated with the patient's Kidney and Bladder organs, as well as the function of their urogenital and reproductive systems.
2. The Trigram Kun, located on the palm just below the little finger, is associated with the patient's left Lung organ and the left side of the chest (the left breast in women).
3. The Trigram Zhen, located on the upper part of the patient's thenar eminence, is associated with the function of the patient's Liver and Gall Bladder organs.
4. The Trigram Sun, located on the palm, just under the index finger, is associated with the patient's right Lung, and the right side of the chest (the right breast in women).
5. The Bright Hall (Ming Tang), located on the center of the palm is associated with the patient's Heart, blood vessels, and mental health.



Figure 31.5. The "Magic Square" can be superimposed on the human body for observation, diagnosis, and treatment. For example:

2 and 4 represent the location of the Lungs

3 and 7 represent the location of the Liver and Spleen

8 and 6 represent the location of the Kidneys

9 represents the location of the Upper Burner

5 represents the location of the Middle Burner

1 represents the location of the Lower Burner

6. The Trigram Qian, located on the lateral edge of the palm's heel, just above the wrist crease, is associated with the patient's descending and sigmoid colon.
7. The Trigram Dui, located on the lateral edge of the palm's heel, midway between the little finger and the wrist crease, is associated with the patient's Spleen, pancreas, and Stomach organs.
8. The Trigram Gen, is located on the lower half of the thenar eminence, is associated with

Trigram Correspondences

Trigram	Name	Meaning	Channel	Shu Point	Direction	Number	Season
☲	Li	Fire (Clinging)	Conception	Lu-7	South	9	Mid Summer
☷	Kun	Earth (Receptive)	Yin Heel	Kd-6	South West	2	Start of Fall
☱	Dui	Lake (Joyful)	Governing	SI-3	West	7	Dividing of Fall
☰	Qian	Heaven (Creative)	Thrusting	Sp-4	North West	6	Beginning of Winter
☵	Kan	Water (Abysmal)	Yang Heel	Bl-62	North	1	Absolute Winter
☶	Gen	Mountain (Keeping Still)	Yin Linking	Pc-6	North East	8	Start Of Spring
☳	Zhen	Thunder (Arousing)	Yang Linking	TB-5	East	3	Dividing of Spring
☴	Sun	Wind (Gentle)	Belt	GB-41	South East	4	Start of Summer

Figure 31.6. The Eight Trigram Correspondence

patient's appendix and ascending colon.

9. The Trigram Li, located on the palm between the middle and ring finger, is associated with the patient's blood circulation, Heart and eyesight.

THE MAGIC SQUARE AND THE EIGHT EXTRAORDINARY VESSELS

In Chinese medicine, the Lo Writings and their correspondences form the model which is the basis for the Ling Gui Pa Fa (The Eight Techniques of the Mysterious Turtle) system of acupuncture. In this system there are Eight Confluential Points that are associated with the Eight Trigrams (Figure 31.6). These points are where the Eight Extraordinary Vessels and Twelve Primary Channels intersect each other.

This method describes the theory that all the points on the body are dominated by the Shu Points, which are in turn dominated by the Eight Confluential Points. The confluential points and their trigram correspondences are Kd-6 (Kun Gua), Lu-7 (Li Gua), GB-41 (Sun Gua), TB-5 (Zhen Gua), Pc-6 (Gan Gua), Sp-4 (Qian Gua), SI-3 (Dui Gua), and Bl-62 (Kan Gua).

UNDERSTANDING THE METAPHYSICAL ASPECT OF NUMBERS

The Chinese medical text of the Nei Jing explains numerology and its mystical significance, as well as the practical utilization of the correspondences between numbers and natural phenomena. Man's physical, mental, emotional, energetic, and spiritual form manifest as part of the microcosm of these nine correspondences, and are explained as follows.

1. Number One corresponds to Heaven, the Center Taiji Pole, and represents the skin.
2. Number Two corresponds to Earth and represents the muscles. The number two also cor-

responds to the two primary forms of Yin and Yang.

3. Number Three corresponds to Man and represents the blood vessels. The number three also corresponds to the Triple Burners, Three Powers, Three Treasures, Three Dantians, and Three External Fields of Wei Qi.
4. Number Four corresponds to the four seasons and represents the muscles corresponding to the body's four extremities, the Four Earthly Quadrants and the Four Divisions of Heaven (N.S.E.W.), and the Four Prenatal Trigram Essences (Great Yang, Small Yang, Great Yin, and Small Yin).
5. Number Five corresponds to the Five Notes of the Chinese pentatonic scale and represents the voice. The number five also corresponds to the Five Elements, Five Colors, Five Tastes, Five Planets, and the Five Elemental Constitutions.
6. Number Six corresponds to the Six Divisions (Tai Yang, Shao Yang, Yang Ming, Tai Yin, Shao Yin, Jue Yin) and represents the union of Yin and Yang. The number six also corresponds to the Six Yao lines and their correspondence to the body, and the Six Accomplishments (intelligence, humanity, holiness, sincerity, moderation, and benevolence).
7. Number Seven corresponds to the Seven Luminaries (sun, moon, and the five planets), which represent the Seven Openings of Man (two eyes, two ears, two nostrils, and one mouth). The number seven also corresponds to the Seven Emotions, and the Seven Stars of the Big Dipper.
8. Number Eight corresponds to the Eight Extraordinary Channels from which the body's prenatal energy flows and represents the breath. The number eight also relates to the Eight Trigrams and their various correspondences.
9. Number Nine corresponds to the formless Void or Wuji, as well as the Nine Heavens (one is centered, and the others are in the eight separate divisions of the Lo Pan compass) and the Nine Lo River Chart (Magic Square). The number nine also represents the nine openings of man (two eyes, two nostrils, two ears, one mouth, one anus, and one urethra).

THE FIVE ELEMENT ENERGETIC FLOW OF THE MAGIC SQUARE

The number formations on the Magic Square are not only considered the energetic ebb and flow, evolution and exchange of Yin and Yang Qi, but also correspond to the energetic harmony of the Five Elements. The energetic harmony of the Five Elements are arranged as follows.

- The Kidneys are positioned in the North; their element is Water and number is 1.
- The Liver is positioned in the East; its element is Wood and number is 3.
- The Heart is positioned in the South; its element is Fire and number is 9.
- The Lungs are positioned in the West; their element is Metal and number is 7.
- The Spleen is positioned in the Center; its element is Earth and number is 5.

These five numbers are arranged in accordance to their energetic progression and are used as a templet for observation and diagnosis of the patient's body, according to their Five-Elemental postnatal structure.

CROSSOVER ENERGY PATTERNS

According to the theory of energetic harmony, when one area of the body lacks Qi, there is generally an Excess energy accumulation in another area. Because the body is symmetrical, one can naturally look on the opposite side for the misplaced Qi. The Qigong doctor may dredge the full side in order to drain the Excess and support the Deficient area.

If the imbalance is not on the opposite side, the doctor can scan for Excess Qi using a figure eight pattern (Figure 31.7). Classically, the Crossover Energy Pattern is one of the most powerful pathways by which Qi flow in the body can be stimulated, and is excellent for balancing internal body energy. The figure "8" pattern can also be used in order to balance all sides of the body (top and bottom, as well as left and right).

When the Qigong doctor must balance the energy in the left and right sides of the brain, the patient may be assigned homework that requires them moving Qi in a figure "8" pattern sideways (i.e., drawing the infinity symbol). This exercise prescription stimulates, strengthens, and balances the right and left hemispheres of the patient's brain. It is used successfully in the treatment of patients with dyslexia.

When patients have internal problems that affect the function of the whole body, it may be necessary to treat two areas simultaneously. The Spleen and Stomach areas, for example, may be tonified along with the Lung areas to strengthen and increase the patient's resistance to External pathogenic factors.

Because organ imbalances are deeper, and tend to be the result of years of energetic deviations, they may take longer to reverse.



Figure 31.7. In this Crossover Energy Pattern, area 4 is treated using area 6 and so on.

CHAPTER 32

HEALING THE PATIENT'S EMOTIONAL TRAUMAS

INTRODUCTION

In my personal practice I feel the main problem for patients is in dealing with their own "hurt," which may have been inflicted upon them several years prior to the manifestation of their disease. It is a recognized truth that when people isolate themselves from each other, their environment, and their spiritual life, it is because they feel the need to guard themselves.

They guard and protect themselves and their belief structures from invasion, criticism, exploitation, or attacks, whether real or imagined, allowing interchange only if it supports their beliefs.

People build energetic walls, and when the walls are penetrated they often experience anger, self-hatred, pain, fear, and shame. Consequently, masks and defence mechanisms are created to hide and support these hidden belief structures.

How the patients develop and maintain their energetic patterning will determine which clinical modality the Qigong doctor will utilize to initiate healing. To free themselves from personal hurt the patients must reconnect with their anger, pain, fear, or worry. Eventually, with the unconditional loving support of the doctor, patients are able to reintegrate the hurt and anger, and accept parts of themselves they had rejected for so long. This acceptance of painful feelings and memories affects the Heart and frees the patients from the emotional traumas of the past.

To heal and release these pathogenic emotions, the patients go through a five-stage detoxifying process during which they feel, experience, and release the emotional trauma that initiated their disease. This is a natural progression in the process of Medical Qigong therapy and healing.

THE PHYSIOLOGICAL EFFECTS OF BENIGN AND CHRONIC EMOTIONS

Within the clinic it is observed that benign emotions (love, joy, peace, etc.) bring about a calm and restful condition within the patient's physiology. Chronic emotions however, create a detrimental stressful physiology, adversely affecting the quality of the patient's life-force energy. As discussed previously, emotional internal and external environmental factors can and do affect the quality of the body's Qi.

1. Excessive joy from the Heart slows down the Qi.
2. Excessive worry and thinking from the Spleen stagnates the Qi.
3. Excessive sadness from the Lungs obstructs the Qi.
4. Fear from the Kidneys descends the Qi.
5. Excessive anger from the Liver ascends the Qi.

FIVE LEVELS OF FEELING AND THEIR GOVERNING ORGANS

To complete their initial healing, the patients go through five stages of emotional resolution. These stages act as a template for the patients' emotional healing, allowing them to progress through, and detoxify each of their Five Yin Organs. The Five Yin Organs store the patients' emotional history in their tissues. Each of the Five Yin Organs also affects different functions and parts of the body (Figure 32.1).

1. The Liver governs the emotions dealing with the past. The Liver stores the negative emotions of irritability, jealousy, anger, rage, blame, and resentment. These emotions and mental states affect the flow of Qi in the channels, influencing the patient's tendons, ligaments, nails, small muscles, peripheral nerves,


(1)
Heart
Seat of all Emotions
(Affects Blood Circulation, Mental and Emotional Activity)
Hurt Triggers Emotional Reactions
(2)
Liver
(Stores Anger from Past)
Affects External Strength and Decision Making
(3)
Lungs
(Stores Grief of the Present)
Affects Breath, Skin and Metabolism of Body Fluids
(4)
Kidneys
(Stores Fear of the Future)
Affects Will Power, Jing, Sexuality and Short Term Memory
(5)
Spleen
(Stores Worry of the Future)
Affects Concentration, Memorization, Digestion and Muscles

Figure 32.1. Diagram of Five Elemental Emotional Transitions

external strength, the iris of the eyes, vision, tears, the Gall Bladder, bile, decision making, the external genitalia, and the Hun (Three Ethereal Souls).

2. The Lungs govern the emotions dealing with the present. The Lungs store the negative emotions of grief, sorrow, sadness, anxiety, shame, guilt and disappointment. These emotions and mental states affect the flow of Qi in the channels, as well as the patient's breath, skin, Large Intestine, mucous membranes, the metabolism of the Body Fluids, body hair, smell, and the Po (Seven Corporeal Souls).
3. The Kidneys govern the emotions dealing with the future. The Kidneys store the negative emotions of fear, loneliness, and insecurity. These emotions and mental states affect the patient's energetic channel flow, as well as the Jing, bones, brain, bone marrow, inner ear, hearing, head hair, pubic hair, spinal cord, cerebrospinal fluid, ovaries, testes, anus and urethra, sexual fluid, reproduction, short term memory, and the Zhi (Will Power).
4. The Spleen governs the emotions dealing with resolution and responsibility. The Spleen also stores the negative emotions of worry, remorse and regret, which can create obsessions. These emotions and mental states affect the flow of Qi within the channels, as well as the patient's large muscles, lymph and saliva secretions, the mouth, lips, taste, the Stomach, digestion, concentration, the ability to memorize, and the Yi (Intention).
5. The Heart governs the emotions dealing with

shock, nervousness and excitement, as well as the final stages of healing (i.e., peace, love and forgiveness). These emotions and mental states affect the patient's energetic channel flow, as well as the patient's blood vessels and circulation, complexion, perspiration, mental and emotional activity, long term memory, Small Intestine, and the Shen (Spirit).

In the process of forgiveness, the anger and resentment are traversed to reach through to the levels of original hurt, sadness and grief. Only after reaching this level, and working through the pain, can the patient begin the process of letting go of the anger, blame, and resentments that protect them from feeling the full impact of the original trauma. Forgiveness begins only after the anger and crying ends. There are three stages of forgiveness: forgiving oneself, accepting the situation, and forgiving the abuser.

1. The forgiving oneself stage deals with the energy involved in healing oneself, and is divided into two specific stages:
   - Forgiving oneself for allowing the hurt to occur in the first place (even if the patient had no choice in being victimized), or for not fighting back strongly enough, if at all, and
   - Forgiving oneself for hanging on to all that anger and pain for so many years.
2. The accepting the situation stage deals with releasing the energetic emotional charge within the environment, or the unwanted consequences connected to the original trauma (e.g., forgiving the accident, injury, handicap, illness, trauma) within the patient.
3. The forgiving the abuser stage is the most difficult final step. Many factors can interfere with this process, such as the patient's fear of re-abuse or continued abuse if forgiveness is genuinely given. Another major factor is the negative, toxic, external energy projected by the abuser upon the patient, sometimes over many years. This energy is absorbed by the patient over time and often leads to the patient identifying with the abuser. The fear of being, or becoming, just like the abuser can be overwhelming. Anger at the abuser may seem to be the only thing standing between them; and allowing any feelings of love, compassion, or understanding may appear to be an acceptance of "evil," not only within the abuser, but within the patient's own self. An acceptance of a dark side within each of us is necessary to forgive the abuser. Often victims of abuse cannot tolerate the idea that they are anything like their abuser. Only the conscious mind, working in concert with the patient's spirit, can reintegrate this essential part of the self that has been utterly rejected and denied.

Children who have experienced abuse may be especially hard pressed to accept anger as a natural, integral part of themselves without which they cannot feel whole. They frequently view all and any anger as not only dangerous but an "evil" force. Thus, forgiveness of the abuser requires restructuring of belief systems, and the acceptance of one's own dark side, as well as the abuser's.

Through conscious intent and creative subconscious intuition, it is possible to come to an understanding that the "evil" experienced stems not from the devil, but from ignorance and pain. In most cases the abuser's intent was not to harm and destroy, but ironically, to teach and discipline for the good of the patient. The abuser did the best that he or she could at the time, given all the unresolved pain and anger within the self.

When patients experience extreme abuse, or prolonged abuse, they may lose the ability to distinguish the difference between wrong actions and the abuser. The abuser is not evil incarnate though evil deeds were done. This often leads victims to see the world only in terms of black and white with no shades or colors. The true healing requires acquiring the ability to see anew (as a little child), to reawaken to the amazing diversity of life.

These skills sometimes require teaching the patient and may necessitate referring the person out to a professional, especially if the patient suffers from a character disorder (e.g., borderline personality disorder, schizo-affective disorder, and so on).

Generally, after performing specific Qigong


Heart
Collection
Point
Lung
Collection
Point
Spleen
Collection
Point
Lung
Collection
Point
Kidney
Collection
Point
Kidney
Collection Point
Liver
Collection Point

Fig. 6.40 *Front and Back Collection Points*


Heart
Collection
Point
Lung
Collection
Point
Liver
Collection
Point
Lung
Collection
Point
Kidney
Collection
Point

Fig. 6.41 *Left and Right Collection Points*

exercises and meditations which release the patient's pent-up, toxic emotions, the patient begins to come out of denial and awaken to genuine spontaneous emotions and feelings. This transition can be very painful at first. I usually tell the patients that this transition is similar to having their arm frozen, and then thawed out.

Imagine if the arm is placed into ice cold water, and left there. The first thing the body would feel is shock, followed by pain. As the feelings slowly begin to leave, the pain begins to diminish, and the arm becomes numb. As the mind shifts its attention away from the feelings in the arm, it begins to establish a denial system, ignoring, minimizing, or suppressing the condition in which the arm has been placed. When first removing the arm from the ice water, the tissues are still numb. After awhile, however, as the numbness begins to wear off, feelings begin to return to that particular area of the body, and pain is felt. The body is no longer in shock and is now feeling the pain and the memory of the past experience.

Our lives are the same way, in regard to physical, mental, emotional, and spiritual pain. While growing up, we are subject to constant trauma on all four levels of existence. Through an instinctive ability, we adapt and learn to become numb to our true feelings in order to survive. When we begin to awaken, we are suddenly thrust into shock, then pain, as we begin to face the source and cause of our trauma.

From a Traditional Chinese Medical perspective, pain is a means by which the body communicates its needs to the mind. In cases of chronic pain, the patient generally learns to divert awareness away from the area of pain through distracting thoughts and emotions. This helps the patient to cope with the pain, but also interferes with the healing process. If the patient reduces conscious awareness of the painful area(s) in the body, the mind/body connection becomes blocked and slows or prevents healing. The initial clarification of the "Message" regarding the disturbance can cause both a sensation of increased pain and an activation of the healing process.

By comprehending the five levels of feeling and their progressive transitions, the patient gains understanding and healing from these past traumas.

STAGES OF EMOTIONAL HISTORY AND RESOLUTION

After the patient understands the five levels of feeling and how they affect their respective organs, the Qigong doctor can assist patients in the cognitive restructuring of their disease-causing belief structures. This emotional re-patterning is initiated through the unveiling of several stages of painful emotional history, which affect the energetic healing abilities within the patient's body.

It is important for the Qigong doctor to remember that all physical matter is conscious energy activated and focused by consciousness. The patient's perceptions create the physical presence of the disease. Since all matter and energy is unified, all matter down to the smallest subatomic particle has awareness, makes choices, and communicates simultaneously with all other matter in the universe. Choices are initiated in the patient's body through the active fields of environmental and universal energy.

Understanding these subatomic communications allows the Qigong doctor to assist the patient in discharging toxic energy trapped and stored within the tissues. The experience of the emotional trauma, and its destructive emotional energetic patterning, is clinically explained and described in the following stages.

1. The patient is hurt (physically, mentally, emotionally, and/or spiritually). The patient receives the original trauma through either an aggressive, direct attack (i.e., being struck, screamed at, belittled, or shamed, etc.), or by a passive, indirect attack (i.e., being abandoned, rejected, ignored, betrayed, etc.). In this stage of development, the patient's trusting connection to life is violated.
2. The patient registers the hurt, feels the pain, and naturally expresses this trauma in an outburst of emotion (i.e., screaming, crying, laughing, groaning, etc.). In this stage the patient recognizes the wounding.
3. The patient seeks attention and looks for a

human emotional response, seeking validation and self-affirmation. In this stage, if the patient does not seek and receive attention for healing the trauma or, if the individual is not free to express his or her real feelings, healing will not take place.

4. The patient's hurt remains unresolved and becomes history. At this point in the transition it is important that the patient feel the hurt, understand the circumstances surrounding the hurt, then discharge the pain. If the patient's hurt does not become completely discharged from the body, it becomes stored within the patient's tissues. Thus, the patient's hurt becomes internalized; the emotions of unexpressed anger, fear, pain, and shame begin to accumulate in the body. The trauma remains as an active charge of unexpressed emotional energy.
5. The patient's whole body stores the distressful emotional memories. This distress gets restimulated in the present (through various trigger mechanisms), and alters or blocks the patient's flow of energy and thinking.
6. The patient learns defense mechanisms to survive. The patient develops strong defense mechanisms instead of healing from the emotional wounds (known as a pathological recovery). At this point the patient's denial system is reinforced, and kept active to protect the patient from any further hurt, in order to ensure survival and maintain at least the semblance of a normal, functional life.
7. A dynamic polarity arises that seems to take on a life of its own. The patient swings back and forth between overcontrolling emotions and loosing control over them completely. The patient becomes obsessed with the painful feelings, either hiding from them or becoming overwhelmed by them. The patient then chooses either one of two options:
   - To become isolated, emotionally removed and distant, or
   - To become needy, co-dependent and attention hungry.
8. The patient develops addictions to continually hide from the pain. The patient's actions become based on the unhealed feelings resulting in four overlapping ways to hide:
   - Physically through sports, excessive exercise, food, sleeping, etc.,
   - Mentally through compulsive behavior (e.g., studying, being a work-a-holic, compulsive book reading, etc.).
   - Emotionally through either chronic rage, grief, obsessive worrying, and chronic fear, or through a compulsive search for love, joy, and excitement (sex / love addiction), etc., and
   - Spiritually through fanaticism of various types, or extreme spirituality.
9. The patient begins to recover from the trauma. To heal and recover, the patient must cease concentrating on the pain and redirect his or her full attention towards setting healthy boundaries and positive affirmations. Some patients' boundaries are too solid and immovable (i.e., they won't allow for any meaningful interaction with others). These patients do not really need to set boundaries, they need to allow their boundaries to become more permeable. Patients' boundaries need to be flexible in order for them to be healthy. Patients must learn when to open and when to close their boundary system, and not just constantly shut everything out (people, relationships, responsibilities, etc.) or let everyone and everything in.

It is important for patients to understand that perpetrators of abuse are in a state of denial of their own shame and imperfection; thus they inflect pain and suffering onto anyone present at the time. Some perpetrators single out one family member as a recipient for their pain. Sometimes the chosen victim reminds the perpetrator of his or her younger innocent self; thus all the accumulated self-hate is projected onto this one child through no fault of the victim. The resemblance may be real (slight physical similarities for instance) or imaginary (the child's vulnerability, for example, or a singled out personality trait that triggers the abuser's anger). The one common factor among abusers is their inability to see their victims for who they really are. Abusers make no effort to know the victim, to really see the whole person; instead they see a distorting mirror which reflects their own image back to them, magnifying their own flaws and fears. Through setting boundaries and affirming their own self-worth, the patients will be able to release years of toxic emotions stored within their tissues. This can initiate health and healing on every level of their being (physical, mental, emotional, and spiritual).

ASSISTING THE PATIENT IN ESTABLISHING HEALTHY BOUNDARIES

The patient is generally informed that in order to make it through the spiritual, emotional, and mental transitions brought about by Medical Qigong therapy, it is important to establish an active but flexible boundary system. The patients are then taught to divide their relationships into three categories: True Friends, Acquaintances, and Toxic Relationships (Figure 32.2).

1. True Friends consist of people with whom the patient can share and expose his or her most intimate hidden secrets and emotional feelings, without worrying about being judged. In the presence of true friends, the patient feels emotionally accepted and loved unconditionally. The boundary system should be down, and the patient should feel completely open. It is safe to be completely vulnerable.
2. Acquaintances consist of people with whom the patients should share only limited amounts of information regarding their personal/emotional life experiences. The most hidden secrets could be judged, misconstrued, and gossiped about. All conversation with these individuals should, and must be, kept on a fairly superficial level. The patient's boundary system should be up, and the patient should monitor the conversation, as it is not safe to be totally vulnerable.
3. Toxic Relationships consist of people with whom the patient cannot and should never share any knowledge of their personal/emotional life. These individuals chronically abuse, mistreat, belittle, and attack others (whether they are members of the patient's own family, work, or neighborhood). All conversation with these individuals should be kept to a minimum. The patient's boundary system should be on full armor, and whenever possible, these individuals should be avoided.



Figure 32.2. Types of Relationships for Setting Flexible Boundaries

REJECTION, BETRAYAL, AND ABANDONMENT

From a young age, people are introduced to the multidimensional experience of being hurt (physical, mental, emotional, and spiritual). This affects the individual's center core and initiates a coping response due to feelings of rejection, betrayal, and abandonment. The normal reaction to such emotions results in experiencing emotions ranging from fear to frustration. These individuals begin to develop masks, that warp and scar their developing personality. As these individuals continue to grow, the illusions of these masks demand more Qi to sustain their form, which in turn drains vital energy from the growing body, and weakens the immune system. This denial system, fortified by the individual's emotional patterning,



Figure 32.3. The True Self is contained within the Core Self.

sustains him or her until they can heal and re-pattern the no longer beneficial belief system.

To re-pattern their belief systems, patients and Qigong practitioners must first be made aware of their initial programming patterns and the reasons for which these were created in the first place. The following "spiritual template" is applied to all patients, regardless of culture, race, or religion.

To access the patient's center core, the Qigong doctor must help the patient identify the masks which have taken on a life of their own and created the false "ego self." Next, the patient must address personal self-hate issues, which have driven the patient to develop the masks and defense mechanisms. Finally, the patient must face the foundational fear that has severed his or her connection with their "true self" contained within the center core (Figure 32.3).

In the Medical Qigong clinics in China there is a saying, "Patients must first stop running from their fears, and face the "Paper Tiger" (i.e., the illusions and fantasies that have been chasing them); in the West, it is considered "stopping and facing your internal demons."

MASKS AND DEFENSE MECHANISMS

To armor the ego, individuals resort to what Sigmund Freud labeled as "ego defense mechanisms." There are nine strategies; and with the exception of the last one listed, i.e., "sublimation," they serve to mask the core self. The nine defense mechanisms and their strategies are: Repression, Displacement, Projection, Intellectualization, Regression, Fixation, Denial, Reaction-Formation, and Sublimation.

1. Repression is the pushing down of unwanted ideas and emotions into the unconscious;
2. Displacement is the shifting of impulses aroused by one person, or situation on to a safe target;
3. Projection is the attribution of unacceptable impulses within oneself to other people;
4. Intellectualization is an elaborate rationalization of a naked impulse, to justify it;
5. Regression is the return to an earlier childhood stage of behavior to reduce the demands on the ego;
6. Fixation has the same result as Regression, but the person becomes fixated at a particular stage of mental and emotional development;
7. Denial is a conscious refusal of an impulse-evoking fact, feeling or memory;
8. Reaction-Formation is the conversion of one feeling into its opposite, typically seen in love turning into hate;
9. Sublimation is the channeling of unacceptable impulses into acceptable, refined social forms and is the only defense mechanism considered to be a healthy reaction.

The ego mediates between the "id" (i.e., the primordial survival drives and impulses) and the "super ego." The super ego consists of the ideals and conscience of the individual.

EMOTIONAL SECURITY

Each individual has basic emotional needs that must be met to feel secure. Without the comfort of these needs being met an individual will sometimes lash out and react in an antisocial behavior. This reaction is generally due to the individual fostering feelings of rejection, betrayal, and abandonment. The three personal needs required


Significance
self worth, personal value and importance
Inclusion
affirming social value
Power
control and authority to speak and act

Figure 32.4. The Three Personal Needs That Foster Emotional Security

to foster emotional security are as follows: Significance, Inclusion and Power (Figure 32.4).

1. For an individual to feel significant, he or she must be given self worth, personal value and importance. Without personal value the individual will feel insignificant, unimportant, and worthless.
2. For an individual to feel included, he or she must be given affirming social value (knowing that they play an important role in the family, relationship, or society as a whole). Without personal acknowledgment the individual feels isolated, segregated, and separated.
3. For an individual to feel powerful, he or she must be given the ability to control and the authority to speak and act. Without personal power the individual feels powerless, weak, and incapable.

In addressing the patient's disease, it is important to sometimes address his or her living and work environment, as both can contribute and influence the patient's healing potential.

HEALING EMOTIONAL TRAUMAS

There are several techniques and methods used to assist patients in healing through emotional traumas (Figure 32.5). Such meditations as Pulling out the Pain are often prescribed as homework along with other treatment methods of Medical Qigong therapy. Some of these methods used to heal emotional trauma are described as follows.

1. Medical Qigong Distance Therapy affects the body, mind and emotions. The Qigong doctor alters the patient's energetic tissues and fields to re-pattern the patient's emotional responses.
2. Medical Qigong Massage Therapy and Bodywork involves lightly touching and stimulating the patient's tissues, to release the trapped emotions so that they may be appropriately reprocessed.
3. Medical Qigong Respiration Therapy unites the body, mind, and emotions by moving the energy through specific breathing techniques. By changing the breathing pattern, the Qigong doctor changes the patient's energetic emotional patterns, releasing trapped memories deep within the patient's tissues.
4. Medical Qigong Dynamic Postural Therapy expands and stretches the patient's tissues. This active adjustment of the patient's body alignment increases the flow of Qi and Blood through his or her internal organs, facilitating an emotional release (e.g., the Dry Crying exercise).
5. Medical Qigong Imagery and Meditation Therapy uses awareness meditations and images to sedate the patient's reactive mind in order to connect with the higher self-identity. The doctor interrupts the patient's emotional


Healing Emotional Trauma
1.Medical Qigong Distance Therapy
2.Medical Qigong Massage Therapy and Bodywork
3.Medical Qigong Respiration Therapy
4.Medical Qigong Dynamic Postural Therapy
5.Medical Qigong Imagery and Meditation Therapy
6.Music and Art Therapy

Figure 32.5. Six Methods Used For Healing Emotional Trauma

thought patterns by changing the patient's sequence of sensations, word pictures and feelings. This emotional reforming changes the meaning of the patient's interpretation and challenges his or her self-limiting beliefs.

6. Music and Art Therapy are sometimes prescribed to change the patient's mood and awareness. Through playing a musical instrument, dancing, singing, or creative free-association drawings, sculptures, pottery, and so on, patients can access their Creative Subconscious Mind to repattern old belief structures and enhance the body's energy. Some patients will resist this form of therapy as they do not consider themselves to be good artists. It is vital to explain that these creative endeavors are not for the purpose of creating art, but for expressing feelings and emotions. These art forms need not be pretty, perfect, or shared with anyone if the patient does not desire to do so. They need not even be kept so long as the patient has released some feelings and emotions. The process itself is the healing. This type of therapy is used to help the patient recreate, identify, and release trapped emotions deep within the subconscious mind.

PULLING OUT THE PAIN MEDITATION

This meditation uses part of the guided imagery used in the Soul Retrieval Meditation (found in Chapter 19). It releases and transforms the patient's conscious feelings and helps to change or remove the Personal Subconscious toxic holding patterns.

After the meditation, patients should feel as if they have been cleansed and purified of toxic emotional debris. This is, however, only the first level. Patients can only release and transform the surfacing emotions one level at a time. Like peeling an onion, the patients must continue to work through each level until reaching their core issues. These core issues surround the suppressed feelings of hurt and pain.

The doctor instructs and guides patients through this meditation matching the rhythm of his or her words to the patient's exhalations. Patients draw their painful memories and traumas out of their body in the form of dark smoke; they then separate the distilled wisdom and knowledge from this dark cloud, reabsorbing the healing light into every pore and cell of their body. The dark cloud must then be released with the help of an angelic being who severs the energetic cord(s) still attaching the patients to their pain and suffering. When the patients reach this sixth step, the doctor assists them by clapping his or her hands as the patients visualize the "sword of truth", held by this holy being, severing the dark energetic cord(s). The sword of truth represents the patients' decision to regain their power by letting go of their attachment to their illness. This attachment creates very real energetic cords that bind the patients to their painful memories and toxic emotions. Severing these cords, or cord, symbolizes the end of the patients' investment in their disease, and the beginning of true healing. This releases all the pain and despair, i.e., the black cloud ascending into the Heaven into the hands of God or a "higher power," in accordance with the belief structure of the patients. As the cloud reaches the first wave of love and compassion emanating from God or a "higher power," a mighty explosion transmutes the black despair and pain into divine healing light. The doctor then assists the patients in accepting this healing, loving light back into their body to experience, perhaps for the first time in their lives, true forgiveness and a state of grace.

1. Begin by sitting comfortably in a chair, with both feet on the floor, hands resting on your thighs, eyes closed, tongue on the upper palette. Breathe naturally through the Lower Dantian.
2. Focus your attention on the Yellow Court area below the diaphragm where you store painful memories and trauma. Imagine opening up this area to release the toxic energy out of your body as a stream of dark steam releasing from a pot.
3. As the dark steam flows out of your body you are releasing feelings and memories of guilt, anger, rage, humiliation, abandonment, degradation, rejection, insecurity, and sorrow. These toxic emotions have, until now, prevented your healing through creating a deep distrust of self and others.
4. Focus your attention on this energetic cloud, and begin separating the pain and hurtful memories from the knowledge and wisdom gathered from these experiences. Visualize this knowledge and wisdom in the form of golden, white, and silver light energy gathering on the right side of the room. Continue to drain the dark cloud of misery and pain, now occupying the left side of the room, until you have extracted all the new insights from it. As you do so, you will notice the dark cloud becoming heavier and darker.
5. Focus on the right side of the room. Through your intention, begin to inhale and imagine this bright, illuminating energy flowing back into your body. Absorb this knowledge and wisdom gathered from past experiences, void of any feeling of hurt, pain, and judgement into every cell of your body. This distilled knowledge and wisdom empowers you to heal from your wounds on a physical, mental, emotional, energetic, and spiritual level.
6. Next focus your attention on the dark black cloud containing all your pain and suffering. Imagine an angelic being, righteous and holy, holding a "sword of Truth," standing by your side, ready to sever the dark energetic cord(s) still connecting your physical body to this dark cloud of despair. The sword descends and severs the cord(s) (*the doctor claps his or her hands as the sword severs the cord(s)*.
7. The cloud of darkness begins to float up, through the ceiling, through the sky into space. Far in the distance you begin to perceive God or a "higher power" emanating waves of compassion, love, and mercy descending towards the Earth. One of the waves touches the dark cloud of hurt and pain, exploding it into a brilliant light. The cloud is immediately transmuted into fluorescent crystal blue drops of light. This pure, clean energy descends from the Heavens like gentle rain. Breathe in this crystal blue healing energy, let it penetrate deeply into every pore, every tissue and cell, saturating your body completely. Feel the light cleansing and radiating throughout your being.

UNDERSTANDING WHY A PATIENT WON'T HEAL

Normally, in a clinical setting, 80% of the patients will respond favorably to Medical Qigong therapy. In some cases, complete remission of the disease is achieved. An additional 10% will improve, but stabilize in their condition, while a final 10% will not respond at all to the treatments and will progressively get worse. When the patient does not respond to the treatments, the reason can usually be related to the following conditions: Failing to Carry Out the Prescriptions, The Pathogens are Just Too Strong, and Divine Will Guides the Outcome.

- Failing to carry out the prescriptions can be caused by the patient subconsciously sabotaging the healing. Refusing to practice is usually due to deep unresolved emotional issues, e.g., feeling unworthy to heal, fear of abandonment by spouse or others, and so on.
- The pathogens are just too strong to be healed by Medical Qigong therapy alone; when an illness is long-standing, additional complementary treatments, i.e., herbs, Western medicine, or surgery may become necessary to achieve healing.
- Divine will guides the outcome in some cases. The patient's time in the physical realm may be complete, and the soul is preparing to return back to the divine.

Sometimes the healing process takes more time then expected. I explain to patients that permanent transitions can sometimes be instantaneous, but are more likely to be gradual. I explain that they are like a sea captain, standing at the helm of a great ocean liner. If the captain decides that the present course is unsafe, and destructive to the ship and its crew, he quickly orders an immediate change in the course of the ship's direction. With a flick of a switch and a hard spin of the steering wheel, the direction of the rudder is immediately changed. However, because of the perpetual inertia of the massive ship, it will take some time to observe any alteration in the course of the ship's current direction. Although the eyes of the captain can be focused on the new direction, the ship still requires enough time to effectively move in the new direction. It is the patient's spiritual intentions and focused goals that eventually direct the patient's emotional belief system, which in turn, redirects their thoughts and body's physical reactions.

Sometimes, toxic emotions and memories are released through diligent Qigong practice and treatments. With some patients, however, although major changes have already occurred in their conscious attitude, belief structure, and spirit, it may take longer for the unconscious reprogramming to take hold and stop reinforcing the old fears, and traumas. This impediment of unconscious reprogramming is due to the patient's conscious mind not being able to fully integrate the new reality and belief structure. A cancer patient may, for example, have been diligently practicing the prescriptions and the disease may now be in remission, but, the patient still visualizes the cancer as all-invasive. Rather then starting with an image of less cancer in the body, the patient continues to start the meditations with the cancer condition visualized at its worst peak. This sends a double message to the subconscious mind (heal and don't heal).

The same thing applies to observing the patient's transitions of chronically programmed patterns. New behaviors and attitudes cannot become habits overnight. It simply takes time, endurance, and constant encouragement in order to make progress. It is important for the patients to keep their eyes focused on their intended goal and not give up hope.

It is also important not to force mental imagery when feeling angry, depressed or upset. To be effective, creative visualization requires a quiescent mind and soft focus; it should not be hard work. Time allotted to creative visualization can be brief (only a couple of minutes), several times a day, for it to be effective.

FACING THE DEATH OF A PATIENT

Because human beings are created from the energies of Heaven and Earth, they are subject to the transitions of nature, death being part of that transition. Sometimes, no matter who the doctor is, or what his or her specific training has been, there is nothing that can be done to physically heal the patient. Because patients have made attachments during their stay on Earth (physical, men-



Figure 32.6. The Five Stages and Transitions of Accepting Death

tal, emotional, and spiritual), it is important for the doctor to assist them in their final transitions of releasing and letting go. The fear of death often causes patients to feel loss of control of their life, facing and conquering this fear allows them to regain a sense of control.

According to Dr. Elisabeth Kubler Ross, there are five stages of dying that facilitate closure for patients, especially in the life and death transition (denial, anger, bargaining, depression, and acceptance). These transitions also occur when facing the death and closure of any personal relationship or job, as well as the termination of one's life (Figure 32.6). Although these stages were originally believed to follow each other in an orderly fashion, further research has indicated that these stages need not, and most often do not occur one at a time. The different "stages" can occur at any time going from "denial" to "acceptance," back to "bargaining," etc., (sometimes in just a few minutes). Every individual reacts differently. Some never accept death and struggle to the very end. Medical Qigong therapy describes these transitions as follows: Shock, Numbness and Disbelief, Denial and Isolation, Anger and Rage, Bargaining, Depression, and Acceptance.

1. Shock, numbness, and disbelief occur when an individual is faced with the fact that his or her own death is near. Because of shock, the mind will generalize, rationalize, delete, or distort information to make the information acceptable to the patient's belief system. When these initial feelings of shock, numbness, or stoicism begin to disappear, most patients then experience disbelief. They can not believe or will not accept what is happening to them.

   Some patients bypass this stage all together. They feel great relief at learning of their impending death. They look forward to the cessation of pain and rejoining those close to them who have passed on.
2. Denial and isolation is the first semi-conscious choice the patient makes after hearing the news. The patients' disbelief allows them to establish their own denial system. This denial system functions as a shield to protect them, as they emerge from the shock. Denial and isolation further allows these patients time to gather additional knowledge, hoping that the original diagnosis was incorrect.
3. Anger and rage arise as the denial system breaks down. Patients experience anger, rage, envy, and resentment, as they view their terminal progress as an injustice. The patients' discomfort and anger are usually displaced and projected towards anything and everyone (usually people and God). Patterned, fear-based behaviors get stored in the body and mind. These emotions affect the patients' future perceptions, diminishing their belief system in personal survival.

4. Bargaining is the next stage in the process of adjusting to the verdict. Patients offer counterproposals (usually with God), hoping to change or alter the course of events and postpone the inevitable from happening.
5. Depression replaces hope and the patient experiences a deep sense of loss. Still resisting the outcome, patients sink into depression, sometimes lingering for quite some time before death. Depression is divided into two different categories, each one is different in nature.
   - Regretful depression is caused by guilt and shame for not having lived life to the fullest. The patients regret having given in to fears and having held on to past hurts (both real and imaginary) for so long, that many dreams were abandoned. Opportunities for healing and enjoyment were missed, and old sorrows and conflicts never resolved. Patients with this type of depression often seek to voice their regrets. Many ask to let go of the bitterness and open up to a spiritual healing, rather than a physical healing.
   - Preparatory depression is not caused by regrets, but by mourning the loss of projected future experiences. These patients are usually quiet and reflective, as they face the process of losing everything and everyone that they love.
6. Acceptance is the final stage before death. Having nowhere else to go, patients evaluate what was learned in life. They are now able to express their feelings of envy for the living and the healthy, as well as anger at those who do not have to face their fate so soon. They finally accept the inevitability of death. Depression gives way to a time of rest before the divine journey home. The patients, having faced their life's work, fears, and feelings, now have a new outlook on life and are prepared for the spiritual transition of death.

Facing death is an important transition in life and must be approached with a reverent respect for spiritual transformation. When a patient is dying it is extremely important for the doctor to accept the "higher order" or "divine will" for the patient, and not harbor a win or lose attitude. No matter what stage of transition the patients are in, they will almost always maintain some glimmer of hope, even though they may claim otherwise, to the very last moment of their life. It is the doctor's responsibility to accept and support patients to their inevitable end and not cease to treat them for reasons of personal fears, sorrows, or regrets. Listen to your patients, and allow them to release their fears. This continued support, acceptance, and encouragement for the patient allows them to die in peace and with dignity.

SUMMARY

Death is considered merely a change of residence for the patient's spirit. The ailing body is sometimes viewed as "a house with rotting walls." Once the dying body becomes unusable, it is best to abandon it, and look for another place to stay. The spirit-body is immortal and will exists forever in accordance with the will of the divine. This is why one is taught to be unattached to the physical transformations of this world and accept and embrace death as part of the natural process of existence.

Think of the transition of death as similar to that of a baby chick which is about to be hatched. Although it has lived and existed within its shell all its formative life, as the baby chick continues to develop, it has slowly begun to outgrow its place of existence. The baby chick is now becoming harshly compressed and crushed within the security of its own shell. As the little chick exhausts itself, trying to get free from what has now become its prison, it seemingly faces death. With its apparent last breaths, the little chick shatters the surrounding shell. Immediately, an intense light appears, followed by a whole new world that reveals itself in new wonderment. The baby chick is now reborn into a fresh new realm of existence, with new room to grow and the ability to experience true freedom.

Once, while in China, I was talking to Dr. Wong of the Xi Yuan Hospital, in Beijing. He made the profound statement that everyone he had ever treated had gotten healed. I have never heard such a bold statement being made by a Qigong master, Direct the pearl to the liver. Gentleness energy fuses with the kindness virtue of the liver.


Note: Use the power of the mind more than muscle power to gather the energy.
1. Become aware of the kidneys.
2. Do the Kidneys' Sound (Choooo) subvocally.
5. Relax and draw the cold energy to the collection point from the kidneys.
4. Pull up the perineum and push the energy ball out. Form the kidneys' collection point.
3. Pull up the left and right sides of the anus. Send the energy to the kidneys.
Kidneys' Collection Point
Right Side the Anus
Left Side

Fig. 6.42 *Forming the Collection Point to gather the Kidneys' Energy.*

7. Gentleness blends with kindness, the virtue of the liver. Look into the liver, connecting the eyes with the liver. Be aware of the kindness energy there. As you bring the pearl carrying the gentleness energy from the kidneys toward the liver, feel the gentleness energy activate and enhance the kindness energy. Enjoy the kindness energy. Feel the kindness intensify. Circulate the kindness energy in the liver. Its qualities can feel **strong, round, smooth, soft, green, sweet and fragrant, warm and pleasant**. You can feel satisfied.

or by any doctor for that matter, so I immediately began to inquire as to what his special techniques were. Dr. Wong responded, "Everyone I treat gets healed; some get healed spiritually, others emotionally, some mentally, and some physically. Not all get cured, but all do get healed. Some patients that come to me for therapy are supposed to die. It is their time of passage, and I help them accept death with dignity and honor. This is achieved by helping the patients heal their spiritual, mental and emotional wounds before they pass on. Other patients that come to me are in an active stage of energetic transition, and I help these patients to see where they've become stagnant, Excessive, or Deficient in their bodies and release their pathogenic Qi." Life is a pathway of transition and change, and so, in the field of energetic medicine, all patients are moving toward or away from healing their relationship with themselves and others.

SECTION VIII

QI EMITTING METHODS

CHAPTER 33
ENERGY EXTENSION AND QI MANIPULATION TECHNIQUES

ENERGY PROJECTION

The body's energetic constitution is a combined matrix of sound, light, heat, and electromagnetic energy. Studies on the effects of Qi projection conducted by Chinese scientists concluded that energy released by a Qigong doctor into a patient carries the properties of infrasound, electromagnetics, static electricity, infrared radiation, gamma rays, particle and wave flows, organic ion flows, and light. These properties produce the physiological changes in the patient's tissues during the Qigong treatment.

A Qigong doctor can emit energy during a treatment with or without touching the patient. The treatment with the doctor's hand moving at a distance from the patient's body is considered Qi Emission. If the doctor's hand touches the patient's body, it is considered Qi Massage, which combines both tissue manipulation and energy flow. Functionally, it is also helpful if the Qigong doctor also has a thorough grasp of the tissue manipulation skills of Chinese massage therapy (Jie Gu for bone setting, Tui Na for traumatology, and An Mo for Internal diseases and visceral manipulation), as well as acupressure and TCM theory, to ensure a highly proficient quality of treatment and to avoid misdiagnosis and erroneous treatments.

Qi is projected outside the body and travels in ripples and vibrational pulses similar to the ripples of an ocean wave. The frequency of this energy wave can be modulated into dense or dispersed resonating patterns depending on the Qigong doctor's needs.

Shen is projected outside the body as light and travels in light beam particles. This particle light extension can change in color and intensity depending on the doctor's intention. When Qi and Shen are combined, the light and wave frequencies facilitate maximum energy projection.



Figure 33.1. Palm Qi Extension

TYPES OF ENERGY EXTENSION

There are nine types of energy extension and projection skills that are divided into three categories based on the source of the projected energy. The first three are projected from the extremities: palms, fingers, and soles of feet. The next category of Qi projection originates from the three Dantians: Upper, Middle, and Lower Dantian. The third category includes Qi emission from the eyes, throat (sound resonation), and thought projection.

ENERGETIC PROJECTION FROM THE EXTREMITIES

The first three energetic projections are released from the extremities (palms, fingers, and the soles of feet) in accordance with the doctor's imagination and intention.

- Palm extension is the ability to release emitted energy through the center of the doctor's palm (Pc-8). It is considered the primary hand posture used by all Medical Qigong doctors for emitting Qi (Figure 33.1).
- Finger extension is the ability to release emitted energy through the extended fingers (usually through the index and middle fingers).

The finger extension techniques allow the Qigong doctors the ability to finely hone their energetic projections into a smaller, condensed energetic beam (Figure 33.2).

- Soles of feet extension is the ability to release energy through the bottom of the feet (Kd-1); this method is usually used to surround and envelop the treatment room as well as the patient (Figure 33.3).

ENERGETIC PROJECTION FROM THE DANTIANS

The next three energetic projections are released from the Upper, Middle, and Lower Dantians. These energetic projections are based upon the doctor's kinesthetic, empathic and intuitive abilities.

- Upper Dantian (Yin Tang) extension from the Qigong doctor's Third Eye area can be used in conjunction with the eyes for intensifying the doctor's Shen projection towards the patient.
- Middle Dantian (CV-17) extension from the Qigong doctor's Heart area can be used in conjunction with projection from the doctor's hands or throat, for vibrational resonation. This technique intensifies the emotional connection between the doctor and the patient.
- Lower Dantian (CV-6) extension from the Qigong doctor's abdominal area can be used in conjunction with Qi emission from the feet for expansion or extension of Wei Qi. This method intensifies the projected External field of Qi around the patient (Figure 33.4).

ENERGETIC THOUGHT PROJECTION OF QI AND SHEN

The last three energetic projections are released from the eyes, throat and mouth (sound resonation) and thought projection. These techniques are a form of long-distance thought projections, based upon the doctor's ability to project Qi and Shen.

- Projection from the eyes releases energy through the eyes and is generally used to increase the doctor's intention and focus of Qi (Figure 33.5).
- Sound resonation projects the voice to tonify or disperse the patient's energy through visceral resonations (Figure 33.6).



Figure 33.2. Finger Qi Extension



Figure 33.3. Extending Energy from the Soles of the Feet



Figure 33.4. Qi Extension. When treating a patient, all Three Dantians extend their energy into the patient.

- Thought projection is another way to release Qi. It is used for long distance energy therapy and is a form of transmuting Qi into Shen, which is transmuted through the Wuji into the patient's Yuan Shen (Figure 33.7).

CONTROLLING ENERGETIC PROJECTIONS

The problem with energy extension lies not in releasing life-force energy but in controlling the power and flow of its projection. If the doctor is distracted or unstable in his or her projection of energy, the doctor may induce more problems in the patient's body. Qi projection can be stabilized in two specific ways:

- First, by visualizing and projecting specific colors (blue, red, violet, etc.) with the energy extension. This causes the Qi to take on a dense and fuller projection, which facilitates the rooting and stabilizing of the energy into the patient's tissues.
- Second, by using intention to mentally focus the size and shape of the projected energy (like a laser), to intensify the Qi projection.

When treating a patient, the diseased tissue must be sufficiently energized. Inadequate energizing results in only slight improvement or a slower rate of healing; over-energizing may cause Qi congestion.

The degree of curative effect depends on the competence and versatility of the doctor, as well as the responsiveness of the patient. If the patient is not responsive, repeated stimulation and regulation of Qi is needed to raise their sensitivity.

Sometimes the patient's emotion and spirit are outside and disconnected from their body and mind. Although this is a perfect adaptation for a military environment, it is not conducive for an energetic healing environment. The patient must undergo a series of Shen Gong training sessions to retrieve their emotional spirit. This training is commonly referred to as "soul retrieval" because the patient's soul is in a state of shock (or suspended animation) due to severe emotional trauma, and must be returned to its Yuan Jing within the patient's tissues. (See Chapter 19).



Figure 33.5. Energy Projection from the Eyes



Figure 33.6. Sound Resonation Projection



Figure 33.7. Thought Projection

In addition to Shen Gong training, the Qigong doctor must make the patient's Qigong meditations and prescriptions more active so that a satisfactory effect can be achieved. However, a desirable effect can only be attained when the patient is cooperative with the doctor and is consistent with the assigned homework.

HAND POSTURES FOR QI EMISSION

There are many hand postures used in emitting and drawing in energy. Each variation depends on the skill and particular background of the doctor. Generally the doctor uses the entire hand to extend energy, constantly changing the intensity of the Qi being extended. By expanding and contracting the hand and fingers, the "beam of Qi" being emitted into the patient's body will expand and contract. Presented here are six hand postures most preferred by myself and many other Medical Qigong doctors in clinics throughout China.

THE EXTENDED FAN PALM

This first hand posture is the most popular in terms of Qi emission. It releases the widest field of Qi emission. In the Extended Fan Palm hand posture, all five fingers stretch naturally, separate, and open like a Chinese fan (Figure 33.8). There should be no tension, and the focus of the energy should be in the center of the palm (Pc-8). This Extended Fan Palm is the primary hand posture for extending energy because it can be easily used for emitting either Hot or Cold energy. It can also be used in conjunction with other techniques as a reinforcing method to strengthen the flow of energy extension.

Note: Before beginning these exercises, it is important not to eat a heavy meal (at least one and a half hours before practicing).



Figure 33.8. The Extended Fan. This palm is the primary hand posture used for emitting Qi.



Figure 33.9. The Image of Holding a Ball of Energy

PALM BREATHING ENERGY EXERCISE—STAGE 1

1. From a Wuji posture, bring both hands up in front of the body, with the palms facing the Lower Dantian. Breathe naturally while concentrating on the Lower Dantian. Next, place

the left palm facing the right palm, as if holding an imaginary ball. Allow the energy between both hands to build and increase its energetic field (Figure 33.9).

2. Press the Mingmen backwards and feel the energy absorbing through the arms into the Lower Dantian. Next, release the pressure from the Mingmen and feel the Qi return back into the center of the palms.
3. Shift the attention to the center of the right palm, and begin to extend energy into the center of the left palm. Next, shift the attention from the center of the right palm, and begin extending energy into the center of the left palm.
4. As a feeling of pressure begins to build between the hands, perform the "Pushing" (energy extension) and "Pulling" (energy retraction) manipulation technique. This technique is practiced by pushing the Qi of the right palm into the center of the left palm. Hold it there, feeling the pressure mount, then withdraw the Qi back into the center of the right palm. Repeat for several minutes, then move to step five.
5. After several minutes switch the mind's focus to the opposite hand and perform the exercise again. Do this exercise twice a day for 15-30 minutes each practice. Be careful not to let the hands touch when running the energy back and forth between the palms. After 100 days go to Stage #2.

When training to increase their own energetic field, the Qigong doctors must strive to overcome the Pituitary Pain Syndrome. This is a state of transition during which the body is overcome by pain to the extent that the mind gives up and the doctor quits practicing (e.g., feeling fatigue when practicing a Holding the Ball posture). It is important that as the doctor become stronger, the training posture be maintained longer, so that the pituitary gland is challenged to activate the hypothalamus. The hypothalamus causes the body to produce endorphins such as ACTH, which is a natural form of cortisone that helps to escalate the doctor's healing potential. This physical reaction is similar to a runner who must overcome physical cramping when racing to obtain a second wind.



Figure 33.10. Posture for Palm Breathing Exercise

PALM BREATHING ENERGY EXERCISE—STAGE 2

1. Light a candle and place it on a table. From a Wuji posture place the center of the right palm several inches to the right of the tip of the flame (Figure 33.10). The left palm should be placed on the opposite side of the candle, facing the right palm. The Laogong points and the tip of the candle should be in a straight line with each other.
2. Breathe naturally while concentrating on the Lower Dantian. Shift the attention onto the center of the right palm, and begin extending energy into the center of the left palm.
3. Once a feeling of pressure begins to build between the palms, begin the Pushing and Pulling energy manipulation technique. Push the Qi of the right palm into the left palm. Hold it there for several minutes, feeling the pressure mount, then draw the Qi back into the center of the right palm. Practice this exercise for several minutes.
4. Next place the left palm on the Lower Dantian while continuing to extend and retract energy from the right palm. After several minutes, switch hands. Notice that as the Qi is being extended out of the palm that the flame bends away, and as the Qi is retracted back

into the palm the flame bends towards the center of the palm. Practice this exercise twice a day for 15-30 minutes each time.

Note that the Yin Tang area (the Upper Dantian's projection point) can grasp the flame and hold it stationary. Since this technique (grasping and rooting) is used for rooting and securing the patient's Qi, its application can be counter productive when trying to move the flame tip. To avoid this condition, the doctor should relax the mind and use the imagination when projecting Qi.

THE SWORD FINGERS

In this second hand posture, the expansive field of Qi being released is reduced and condensed into a more solid beam of light. In the Sword Fingers hand posture, the index and middle fingers of the right hand are extended and joined together, the ring and little fingers curl into the center of the palm (Figure 33.11). The thumb should rest on the nails of the ring and little fingers forming a circle where Qi is gathered.

The index finger indicates Wood or Liver's Qi, and the middle finger indicates Fire or the Heart's Qi. Together, both fingers activate the Qi of Fire and Wood, which is a catalyst for the Yang energy needed for guiding Yang Heat with the intention (Yi). When extending energy, the Qi is gathered first in the palm and the circle between the thumb and last two fingers, then it is released through the tips of the index and middle fingers.

SWORD FINGER QI EXTENSION—STAGE 1

1. From a Wuji posture, extend both hands to form an imaginary circle of energy in front of the Lower Dantian. As soon as the Dantian is activated and full, bring the ball of energy in front of the body, level with the Middle Dantian (Heart / solar plexus level). Direct the Qi from the Lower Dantian into both hands (Figure 33.12).
2. Point the middle and index fingers of the right hand towards the left palm (Pc-8) and feel the energy press into the tissues (Figure 33.13). After a while, neutralize the energy by turning the palms towards each other, then switch and feel the energy of the left sword fingers


Figure 33.11. The Sword Fingers Technique



Figure 33.12. Imagine a ball of energy in front of the Lower Dantian, then raise it up to the level of the Middle Dantian.


Figure 33.13. Point the Sword Fingers of the right hand towards the center of the left hand.

(index and middle finger) press into the center of the right palm. Practice this exercise twice a day for 15-30 minutes each practice. After 100 days go to the next stage.

SWORD FINGER QI EXTENSION—STAGE 2

1. Light a stick of incense and place it in a standing upright position on a table. From a Wuji posture, place the center of the left palm (Pc-8) several inches to the left of the incense. The right hand sword fingers point through the tip of the incense, extending Qi into the center of the left palm. All three points - left center palm (Pc-8), tip of the incense, and the right sword fingers - should be in a straight line (Figure 33.14).
2. Breathe naturally while concentrating on the Lower Dantian. Shift your attention onto the tip of the incense and focus your concentration there. Continue to extend Qi until you have a strong feeling of Qi in the center of your left palm. After a while switch to the right palm. Practice this exercise twice a day for 15-30 minutes each time.


Figure 33.14. The Sword Fingers point at the tip of the lit incense.

THE ONE FINGER SKILL

In this third hand posture, the field of Qi being released is further condensed into an more solid beam of light. In the One Finger Skill hand posture, the hand forms a soft fist with one appendage (finger or thumb) extended (Figure 33.15). The energy is projected in a straight line (like a laser beam) and can be used to Heat the patient's tissues, channels, or points, as well as to lead, extend, and tonify the energetic field (Figure 33.16).


Figure 33.15. The use of the finger or thumb to emit Qi is an example of the One Finger Skill technique.

One Finger Skill can be used to extend long range energy into the patient's channels, or for tissue and channel point regulation. The former technique is regarded as an internal application, and the later technique is regarded as an external application.

- The external application requires that the doctor make physical contact with the patient's tissues, extending the mind deep into the specific areas, channels, or points to be treated. The Qigong doctor physically rotates and shakes a specific finger (or thumb) from side


Figure 33.16. Energy is extended through the One Finger Skill technique.

8. Absorb the kindness energy into the pearl, and bring the pearl to the liver collection point (at the level of the navel and in line with the right nipple).

   Here the combination of gentleness and kindness will intensify. Remember to relax and smile. Direct the pearl to the heart. Gentleness and kindness energy fuse with love, honor and respect and joy in the heart.


1. Become aware of the liver.
2. Do the Liver's Sound (Shhhhhh) subvocally.
4. Form the liver's collection point by pulling up on the right side, under the ribs, and forming a green sphere. Gather the liver's energy.
3. Pull up the right side of the anus toward the liver.
Right Side
The Anus

Fig. 6.43 *Forming the Liver's Collection Point to gather the Liver's Energy.*

9. Connect the tongue with the heart. Using your mind's eye and senses, allow the pearl, now consisting of gentleness and kindness, to flow up to the heart. Let the virtue energy of the pearl activate and enhance all the loving energy, joy and happiness, honor, respect and peace in the heart. These good virtues of the heart can feel **straight** and **open, bright red, warm, deep, calm, comfortable** and **satisfying**. Enjoy the virtuous feelings of the heart. The feeling will be different for each person as the energy blends. Feel the warmth and openness in the chest.

to side while emitting Qi into the patient's tissues or energetic fields (Figure 33.17).

- The internal application requires that the Qigong doctor extend his or her arm, pointing a specific finger at a particular area on the patient's body. The doctor then focuses on that specific channel point, leading and directing the emitted Qi into or out of the patient's body.

ONE FINGER SKILL ENERGY EXTENSION EXERCISE

1. From a Wuji posture, focus the concentration on the Lower Dantian area and bring both arms up to chest level and form an energy ball. Once the Qi in the Lower Dantian becomes activated, direct its energy flow to the tip of the right index finger. Once a feeling of heat and expansion of energy is felt within the right index finger, point the energy beam into the heart of the left palm (Figure 33.18).
2. Once the energy is felt pressing into the left palm, begin to circle-rotate the energy beam in a clockwise direction for several minutes, then in a counterclockwise direction for several minutes.
3. Next, extend and focus the Qi from the Dantian into the left index finger, and repeat the exercise.

SOARING DRAGON TECHNIQUE

The Soaring Dragon technique is a variation of the One Finger Skill energy extension technique. If the pathogens are strong and too much Heat is being emitted from the patient's tissues (as in certain types of cancer), the Qigong doctor may decide to use this particular variation to avoid absorbing the dangerous toxins being released from the patient's body. The Qi is emitted out the doctor's middle finger into the patient's body while the other four fingers disperse the pathogenic Heat into the ground (Figure 33.19).

Before initiating the Soaring Dragon technique, it is important for the Qigong doctor to use his or her mind's intention to seal the wrist. This enables the doctor to pull the patient's Qi into the palm and to disperse it into the Earth via the other four fingers, while avoiding the absorption of the patient's pathogenic Qi.



Figure 33.17. The doctor makes contact with the patient's tissues, extending his or her intention along the patient's channels, leading the Toxic Qi out her body.



Figure 33.18. One Finger Skill Energy Extension Exercise



Figure 33.19. Soaring Dragon Hand Posture Technique

I have found this technique very effective in my personal practice. As the pathogenic Heat from the patient's tissues releases upward, the dispersing energy that flows from the four fingers cause the patient's toxic Heat to dissipate and be carried away from the doctor.

BELLOWS PALM TECHNIQUE

Another variation of the One Finger Skill is the Bellows Palms technique, which uses the Lao Gong Pc-8 point at the center of the palm as a pump, to expel Qi out the middle finger. Originally, while treating patients, the palm is Hot (in a Yang state). However, when pulling Qi from the center of the palm and directing it out the middle finger, the polarity of the palm changes from Yang to Yin, causing the center of the palm and the middle finger to turn white (Figure 33.20).

Because this technique is used to pull out Heat from the patient's body, before initiating the Bellows Palm it is important for the Qigong doctor to use his or her mind's intention to seal the wrist. The doctor then pulls the patient's Qi into the palm and disperses it into the Earth via his or her middle finger to avoid absorbing any of the patient's pathogenic Qi (Figure 33.21).

THE BACK BRIDGE BAR TECHNIQUE

The Bellows Palm technique is also used with the "back bridge bar" (where the trapezius muscles join both arms across the doctor's shoulders) to aspirate toxic energy from the patient's body. In this particular technique, the doctor's left palm is used as a vacuum to aspirate a specific area inside the patient's body. The toxic energy travels through the doctor's left arm, across the shoulders and back (never the front), and out through the right palm into the Earth. The right palm applies the "bellows" technique used to create the energetic suction applied by the left palm, for removing Toxic Qi. This technique is contraindicated when treating cancer patients.

THE INVISIBLE NEEDLE PALM

In this fourth hand posture, the field of Qi being released is further condensed into an intense beam of light, similar to that of a laser beam (Figure 33.22). In the Invisible Needle Palm hand posture,



Figure 33.20. When using the Bellows Palm technique, the center of the palm and middle finger remain white in color, while the rest of the palm remains red.



Figure 33.21. Absorb the patient's Toxic Qi from the middle of the palm and disperse the pathogens out the middle finger into the Earth.



Figure 33.22. The Invisible Needle Palm

three fingers on the right hand are curled into the center of the palm with the thumb resting against the tip of the index finger (see Chapter 35 for Invisible Needle Theory and Application).

THE DRAGON'S MOUTH PALM

This hand posture is sometimes also called the Duck's Bill Palm, and is used to pull energy (like pulling a silk thread). The thumb and all four fingers perform the action of "pulling the golden thread" in order to lead or pull energy along and through the body's channels and points. The intensity of the Qi and movement between the thumb and fingers is determined by the relaxed movements of the wrist and finger joints. This hand technique is often used to purge energy away from specific points when treating areas of Excess (Figure 33.23).

THE KNEADING TIGER PALM

In this hand posture, all five fingers naturally curl as if embracing a ball. The wrist action is very fluid and supple, allowing the fingers to expand open like the Extended Fan Palm, and then gently close as if kneading a cotton ball. The entire action should be similar to a jellyfish moving in the ocean. This is an excellent technique for pulling, shaking, and rotating energy (Figure 33.24).

KNEADING TIGER TECHNIQUE

This hand posture is used for dispersing stagnations and dissolving energy blocks. Once the doctor has selected the proper hand posture and the area to be treated, the doctor places his or her hands and fingers above the patient's body, performing a circular kneading action (slightly opening and closing the palm) while simultaneously extending energy into the patient's body. The spiraling energetic frequency should be synchronized with the doctor's hand kneading and the patient's pulse and respiration. Both the pressure and the strength of energy extended into the patient are determined according to the severity of the illness. The Tiger Kneading technique is used for extending energy into energetic points of the chest, abdomen, and extremities to purge Qi stagnation and improve energetic circulation.



Figure 33.23. The Dragon's Mouth Palm



Figure 33.24. The Kneading Tiger Palm



Figure 33.25. The Five Thunder Finger Palm



Figure 33.26. The Five Thunder Fingers. This technique is used primarly to destroy cysts, tumors and pathogens.

THE FIVE THUNDER FINGERS

This hand posture is one of the most popular techniques used for dispersing stagnations, dissolving energy blocks and treating tumors and cysts. In the Five Thunder Fingers hand posture, all four fingers curl into the center of the palm with the thumb resting against the nail of each finger. Keep the center of the palm hollow. Qi is gathered and collected there upon inhalation (Figure 33.25).

When emitting or extending Qi, the doctor exhales while suddenly stretching the palm open like "a tiger exposing its claws." After extending the energy, the doctor inhales and resumes the Five Thunder Fingers posture while gathering Qi back into the center of the palm (Figure 33.26).

Note: Because it builds up the doctor's guiding and gathering skill, this is an important technique and should be practiced consistently.

QI BLAST EXERCISE

From a Wuji posture, raise both palms upward to shoulder level. Both hands form the Five Thunder Fingers posture. Concentrate on the Lower Dantian when inhaling. Imagine drawing the Qi up through the chest, gathering the energy into both palms as the arms raise upward. Upon exhalation, sink the body's weight, and suddenly stretch out the fingers (like a claw) at chest level, striking the air. This action should look like each hand is heaving a rubber ball. Perform this exercise once or twice a day, using 24 or 48 breaths each practice time.

CHAPTER 34

QI EXTENSION, GUIDANCE, AND REGULATION TECHNIQUES

Qi extension is most effective in activating and balancing the patient's flow of Qi, since both the doctor and patient are enveloped in a strong field of Wei Qi. In Qigong massage the patient's channels are more easily dredged and their Yin and Yang energy are often adjusted much more quickly because of the stimulation produced by the doctor's hand on the patient's channels and points.

Therefore, both modalities - Qigong massage and Qi extension - are usually combined to provide the most effective and efficient means of energetic therapy.

QI EXTENSION TECHNIQUES

The clinical guiding and directing of Qi is performed by extending energy outside of the doctor's body. The energy follows the dictates of the doctor's mind as to the pattern, amount, and direction in which to flow. Qi is emitted in three basic formats: linear, circular/spiral, and stationary flows of energy. The combination of these three forms insures that the patient is receiving the maximum benefit from the treatments, and may be combined with Hot and Cold energy extension, the Five Elemental energy extension, as well as with Qigong massage. These following exercises lay a foundation for guiding and directing the patient's Qi within the channels, points, and Wei Qi fields.

GUIDING THE LINEAR FLOW OF ENERGY

This method refers to a straight line of energy being emitted either between both hands or between one of the doctor's hands (usually the right) and a certain point or area on the patient's body. This is the primary Qi guiding method used in Medical Qigong therapy to sweep over the patient's body in a straight line in the direction of the outgoing flow of energy.



Figure 34.1. An example of a Qigong doctor using the Pushing Energy technique in a Straight Linear energy flow

Because patients vary in their sensitivity to transverse energy wave flow, the doctor should be aware of the influence of the different wave patterns affecting the patient during treatment. Linear energy is relatively mild and often gives the patient a sensation of constriction, of heat or cold, or of heaviness, pressing, tugging, tingling, or pulling. This is the basic means of inducing the channel Qi to purge Excess and to supplement any Deficiencies. Energy is directed within the body through either pushing, pulling, or leading the patient's Qi.

PUSHING ENERGY

Pushing energy is initiated by first extending energy over the surface area of the patient's body (Figure 34.1). Once the doctor has selected the appropriate hand posture above the patient (between 4 inches to 3.5 feet from the channel point or area), he or she will decide whether to push the energy in a linear or circular fashion.

Using intention, the Qigong doctor gently extends energy to the desired area and begins treatment. Pushing energy is an essential energetic



Figure 34.2. An example of a Qigong doctor using the Pulling Energy technique in a Straight Linear energy flow



Figure 34.3. An example of a Qigong doctor using the Leading Energy technique (with the left hand) while Pulling Toxic Energy (with the right hand) from the patient's body

manipulation used to open up the points to activate or replenish the body's Qi. The patient feels pressure from the doctor's Qi, and may experience heat, tingling, condensation, expansion, swelling, or heaviness.

Sometimes when the doctor uses the pushing energy technique, the patient may spontaneously lift the stimulated body area towards the hand of the doctor. This spontaneous reaction enables the doctor to implement a combination of manipulation therapies such as push-pull, push-pull-rotate (spiral), push-pull-shake, etc.

PULLING ENERGY

Pulling energy is initiated first by extending energy over the surface area of the patient's body. After selecting the appropriate hand position, the doctor chooses to either pull the energy in a straight line or spiral it along the channels.

Using intention, the Qigong doctor usually begins to pull the patient's toxic energy along the channels while extending clean energy to the affected area (Figure 34.2). Pulling energy is an essential energetic manipulation used for dredging and expelling pathogenic factors from the patient's body, and can also be used to open up channel points to activate or replenish the patient's Qi.

During treatment the doctor actually feels the pathogenic factors being pulled out of the patient's body. This causes the patient to feel heavy, tingling, dryness, heat, cold, or chills. When combining multiple manipulation methods, the pushing and pulling actions cause the energy inside and outside of the patient's body to flow into each other, opening up the patient's channel points.

The combination of pulling and shaking techniques promotes the flow of the patient's Qi, and induces spontaneous reactions of the tissue's energetic fields.

LEADING ENERGY

Leading energy is initiated first by extending energy over the surface area of the patient's body. After selecting the appropriate hand posture, the doctor extends energy towards the affected area and begins to lead the patient's channel Qi up, down, left, right, with, or against the flow of the body's channels (Figure 34.3).

The Qigong doctor bases the decision of whether or not to lead the patient's energy (and which technique should be used) upon the patient's condition and severity of the illness. This manipulation technique is used for guiding the circulation of channel Qi, regulating any Excess or Deficiency of Yin and Yang energy and to transfer Qi back to its origin. Once the channel Qi and point Qi have been stimulated, it is important that the doctor immediately use the "leading energy" technique to guide the patient's energy in as smooth a transition as possible.

CIRCULATING THE QI IN A CIRCLING PATTERN

Emitting a flow of energy in a circling pattern is used to move and circulate stagnant Qi. The flow of energy can be moved in a continuous pattern with or against the channel flow, and is used to regulate the patient's channel and organ Qi (Figure 34.4).

This method refers to techniques of rotating Qi in a circle pattern inside the patient's body. When using circling energy, the doctor extends Qi into the patient's body and implements the circle technique with the right (Yang) hand, while rooting and discharging the patient's toxic Qi with the left (Yin) hand, which points to the Earth. There are many variations of this technique and the doctor must become familiar with each modality of healing and its potential for treating the patient.

ENERGETIC CIRCULAR PATTERNS

The following patterns are specific templates used for circulating the body's internal and external Qi. Each pattern has an advantage over the others when used for the regulation of Yin and Yang disharmony. The depth of energetic penetration will vary in accordance with the doctor's intention. Each pattern's movement will utilize the ring of energy that surrounds the center of each Dantian (Figure 34.5).



Figure 34.4. An example of a Qigong doctor using the Circling Energy technique to regulate the Heart Fire and Kidney Water, through the Microcosmic Orbit

1. **The Eternity Pattern** is used for balancing the energy between the Lower Dantian and the Middle Dantian. The doctor moves the energy in a figure "8" pattern, Guiding and Leading the Qi from the Lower Dantian


Throat
Middle Dantian
Yellow Court
Lower Dantian
Huiyin
Eternity Pattern
Baihui
Upper Dantian
Throat
Middle Dantian
Yellow Court
Lower Dantian
Huiyin
Train of Pearls Pattern
Upper Dantian
Taiji Pole
Front of Body (CV)
Back of Body (GV)
Lower Dantian
Microcosmic Orbit Pattern
Middle Dantian
Right Side of Body
Left Side of Body
Lower Dantian
Yin and Yang Pattern

Figure 34.5. A Qigong Doctor Using Circling Energy

(through the Yellow Court) to the Middle Dantian, and back again. The doctor continues this pattern until the patient's energy is regulated. If the patients are suffering from an Excess Yang condition in the upper part of the body, and a Deficient Yin condition in the lower part of the body, the doctor must regulate this condition by using the Eternity Pattern of Qi regulation.

2. **The Train of Pearls Pattern** is used for balancing the energy between all three Dantians. The doctor moves the energy from the Lower Dantian (through the Yellow Court) to the Middle Dantian (through the throat), and into the Upper Dantian, then back down again. The Qi is swept up and down the entire torso, combining and regulating the energies of the patient's Wei Qi, Channel Qi and Organ Qi. The doctor continues this pattern until the patient's energy feels regulated. If the patients are energetically disconnected from the upper and lower parts of their body due to emotional congestion and energetic stagnation in the throat and Yellow Court areas, the doctor reconnects these areas by using the Train of Pearls Pattern of Qi regulation.

3. **The Microcosmic Orbit Pattern** is used for balancing the energy between the Three Dantians, Taiji Pole, the Heart's Fire and the Kidneys' Water. The doctor moves the energy from the Lower Dantian (Mingmen area) to the Middle Dantian (Shendao Area), then back down again, completing the Fire Cycle of the Microcosmic Orbit. The doctor continues this pattern until the patient's energy is regulated. The Microcosmic Orbit Pattern is used for the complete regulation of the body's Yin and Yang energy, naturally purging, tonifying, and regulating any Excess or Deficient condition along the Governing and Conception Vessels.

4. **The Yin and Yang Pattern** is used for balancing the energy between the right and the left sides of the body. The doctor moves the energy in a horizontal figure "8" pattern, Guiding and Leading the Qi through the left and right quadrants of the patient's body. In cases of paralysis after a stroke, for example, the doctor regulates the Qi of the patient's left and right quadrants and energetically balance these areas by using the Yin and Yang Pattern of Qi regulation.



Figure 34.6. An example of a Qigong doctor moving the incense smoke, using the image of an energy ball

The Qigong doctor selects the appropriate energetic pattern according to the patient's condition.

ENERGY BALL ROTATION FOR DEVELOPING CIRCLE ENERGY FLOW

- Light a stick of incense and stand it on a table. From a Wuji posture, place the center of both palms on opposite sides of the tip of the incense. All three points, the tip of the incense, and the heart of each palm (Pc-8), should form a triangle (a tree or flower can be substituted for the incense).
- Breathe naturally while focusing on the Lower Dantian. Slowly shift the attention to lead the energy into the center of each palm to form a ball of energy (basketball size). Concentrate and

imagine the ball condensing to form a powerfully compacted ball of energy (about the size of a marble). Next, imagine a circle or rounded triangle between both palms and the tip of incense. Exhale lightly while extending the energy ball toward the tip of the incense. Imagine the ball of energy moving counterclockwise from the right palm to the incense and then to the left palm, moving in a circle. The right hand pushes while the left hand pulls. The incense smoke should move in accordance with the Qi movement. After a while reverse the flow of the circle. Practice this exercise twice a day for 15-30 minutes each time (Figure 34.6).

SPIRALING ENERGY FLOW

A spiraling flow of energy moves the energy in a spiral pattern (clockwise or counterclockwise) to drill the energy deep inside the patient's body (Figure 34.7). This "drilling" action, caused by the spiraling energy, allows for deeper penetration and is excellent for breaking up stagnations when combined with the Kneading Tiger Palm or the Five Thunder Fingers techniques.

Spiraling energy can also be used in the clinic to regulate the patient's Qi activities. Patients may feel the energy penetrating deep into their body and experience light, sound, and mild electric shock. When patients are lying supine, the doctor may choose to spiral the energy superior to the internal organs to pull toxic Qi out of the tissues of the organ; or the doctor may spiral the energy inferior to the internal organs to push the Qi back into the tissues of the organs (Figure 34.8).

Spiraling energy is an essential energetic manipulation used for activating the channel Qi, guiding the energy to spiral in, up, or down, much like a cyclone. The Qigong doctor chooses to use either the circle or spiral energy flow, based upon the patient's condition. Most often these two energetic flows are combined to achieve a more functional treatment. The Qigong doctor will, for example, use "spiraling" energy to drill deep into the body to access the toxic energy stored deep inside the patient's organs. Once the patient's toxic Qi has been reached, the doctor utilizes purging techniques to remove the energetic debris. After purging the doctor can circulate the patient's energy to move the stagnant Qi out of the organs. This may be followed by the Microcosmic Orbit to regulate the patient's energy.



Figure 34.7. A Qigong doctor using the Spiraling Energy technique, to purge Toxic Qi from the patient's body



Figure 34.8. A Qigong doctor Spiraling the Qi in order to penetrate the patient's tissues

CLOCKWISE AND COUNTERCLOCKWISE ENERGY FLOW

The doctor focuses on sensing and creating an internal energy vortex within the Lower Dantian that moves up the body in a clockwise or counterclockwise spiral pattern. Only then is the spiraling Qi projected out through the doctor's right hand into the patient's body.

Using the appropriate hand position, the doctor slowly spirals the energy in either a clockwise direction to guide the patient's energy into the affected area, or in a counterclockwise direction

10. Let the pearl absorb the honor, respect, love and joy. Bring the pearl down to the heart collection point behind the sternum.


1. Become aware of the heart.
2. Do the Heart's Sound (Hawwwww) subvocally.
4. Pull the heart and thymus's energy into the heart's collection point.
6. Pull the heart energy into the front pakua. Use your mind and eyes to blend the hot and cold energies.
5. Pull the kidneys' energy from the perineum into the front pakua.
3. Pull up the anus toward the heart and form the heart collection point.

Fig. 6.44 *Form the Heart's Collection Point and blend the Heart's Energy with the Kidneys' Energy in the Pakua.*

The pearl can now blend the virtue energies of the heart in a balanced way with the kindness and gentleness energies already within the pearl. Feel the collection point glowing. Then direct the pearl to the spleen/pancreas.

Note for Women: Women should be careful when the pearl is in the heart center. As a natural endowment women tend to have more loving energy in the heart. When a woman loves she often forgets herself. This amount of love can heat up the heart center and the practice can feel uncomfortable. It is best not to remain for too long in the heart if you feel uncomfortable.



On Yang Channels

As Yang Qi travels down the body, reinforce the patient's descending channel with a clockwise rotation along the flow of energy.

Reduce the energy with a counterclockwise rotation against the flow of the descending Yang channel.

On Yin Channels

As Yin Qi travels up the body, reduce the energy flow in the patient's ascending channel with a clockwise rotation against the flow of energy.

Reinforce the energy with a counterclockwise rotation against the flow of the ascending Yin channel.

Figure 34.9. The reinforcing and reducing techniques of moving energy along the patient's channels is determined by the direction of the Spiraling Energy flow.

to remove the patient's Toxic Qi out of the diseased area.

- The counterclockwise rotation is considered Yin and is used to reduce Heat and to cool the patient. It is generally used to purge conditions of Excess (think of unscrewing the pathogens from the diseased area when purging).
- The clockwise rotation is considered Yang and is used to increase energy and warm the patient. Generally, it is used to tonify conditions of Deficiency (think of drilling and filling the Deficient area when tonifying).

The clockwise spiraling energy originating in the Lower Dantian is emitted and synchronized with the doctor's circling hand movements to reinforce the patient's Qi. To reduce the flow of the channel's Qi, the counterclockwise spiraling technique is used (Figure 34.9).

The Qigong doctor must cultivate these movements into a conditioned reflex before applying these treatment methods in a clinical environment.

SPIRALING ENERGY EXERCISE

- From a Wuji posture, place the left palm on the Lower Dantian. Slowly extend the right palm (keep elbow bent) in front of the chest, aligned with the center line at the Middle Dantian (CV-17), palm facing outward.
- Breathe naturally, while focusing on the Lower Dantian. With the mind's intention, begin to spiral the Qi in the Lower Dantian in a clockwise circle. Lead the energy up through the chest and out the extended right palm. Make sure that the spiraling of the Lower Dantian is synchronized with that of the right palm, making the inner Lao Gong Pc-8 points the center of concentration (Figure 34.10). Start off slowly, and gradually increase speed. The energy circle spirals outward with increasing or decreasing radius, depending upon the doctor's intent.

Repeat the exercise, only this time use counterclockwise spiraling.

ENERGETIC CUPPING

One popular clinical technique called "energetic cupping" is initiated by creating an energetic vortex which remains on the patient, pulling or drawing in energy, similar to that of an acupuncturist's cupping method. These energetic vortices can be used to drain or purge pathogens from a specific point or area on the patient's body. These energetic vortices can also be used to fill or tonify the patient's body. For example, when the patient is prone, the Qigong doctor can stimulate points LI-15, GV-4, and GV-14 (Figure 34.11). Then, using his or her intention, the doctor can pull with one hand while the other hand pushes, increasing the spiraling action already set in motion. This initiated energetic torque can sometimes cause the patient's body to turn, twist, bend, and sway. This modality of treatment simultaneously activates the patient's channel Qi, regulates the Yin and Yang organs, and balances the patient's Yin and Yang energies.

The doctor is advised to rely on intuition or divine guidance in choosing the right method, after careful consideration of the patient's condition (age, sex, personality, illness, etc.).

Note: If combined with the "shaking" technique, the circle/spiraling energy becomes especially effective for relieving pain.

GUIDING THE STATIONARY FLOW OF ENERGY

Stationary energy is emitted from a non-mobile position and can be used to stimulate the channel Qi, points, and Dantians, while restoring and replenishing the patient's Qi. After selecting the appropriate hand posture, the doctor positions his or her hand above the area being treated and emits energy from a fixed or stationary position. This is the most common energy projection technique, in which Qi flows like dense waves or is spaced like a chain of moving pearls flowing outward one after another (Figure 34.12). The patient often feels the sensation of vibration, tingling, or heat. It is not uncommon for the patient to develop spontaneous involuntary reactions such as full body spasms or shaking, leg jerking, etc.

Stationary energy is emitted from a station-



Figure 34.10. An example of a Qigong doctor practicing the Spiraling Energy exercise



Figure 34.11. An example of a Qigong doctor performing multiple point stimulation with the Energetic Cupping Technique



Figure 34.12. When a Qigong doctor extends energy from a stationary position, the Qi flows either like a dense wave, or is spaced like a chain of moving pearls.



Figure 34.13. An example of a Qigong doctor using the Shaking Energy technique along with the Kneading Tiger Palm



Figure 34.14. An example of a Qigong doctor using Vibrating Energy through the Extended Fan Palm technique

ary palm position. There are two main energetic pulsations utilized in the Stationary Palm techniques: Shaking Energy technique and Vibrating Energy technique.

SHAKING ENERGY TECHNIQUE

The Shaking Energy technique is initiated by the doctor first extending his or her energy over the surface area of the patient's body. After using the Tiger Kneading Palm technique to grasp the Turbid Qi, the doctor slowly begins to guide the patient's Qi out of the tissue area with a stationary manipulation. The doctor then shakes his or her hand from side to side, while continuing to pull the Qi from the area being treated (Figure 34.13).

To practice this particular skill, the Qigong doctor begins from a Wuji posture, using natural and slow breathing. The doctor imagines the waist as the axis and the abdomen as a pump and vibrates the Qi inside his or her Lower Dantian. The doctor then allows the energy to flow upward and out the palm, into the patient. It is important for the doctor to use the mind's intent to follow, guide, and direct this vibration of energy flow, instead of forcing the muscles and palm to shake.

VIBRATING ENERGY TECHNIQUE

Vibrational trembling is one way that memory is stored or processed in the physical body. The Qigong doctor's vibration penetrates the patient's field of "vibrational activity" (the body's natural vibrational rhythm), awakening this memory, allowing the patient to release trapped thoughts and emotions (Figure 34.14).

Qi naturally oscillates and vibrates in the doctor's Three Dantians, each Dantian vibrating at its own unique frequency pattern. The body's bone structure is built with natural formations similar to that of "tuning forks," positioned in both the arms and the legs. These tuning forks are connected together through the body's spinal column and are used to vibrate and increase the body's energetic resonance. Through a balanced interplay of stretching and releasing the body's tendon, ligament, and muscle fibers (in a rhythmic pattern), a natural vibration is produced. After some time of training (through naturally twisting and stretching the tendons), the Qigong doctor, using proper hand postures and intention, is able to direct and lead this vibration throughout his or her entire torso and extend it outwards through the hands.

Vibration is released through three forms of resonation:

1. Jing vibrational resonance is felt within the patient's external tissues and bones. It is related to the energetic release of Heat and the energy of the doctor's Lower Dantian.
2. Qi vibrational resonance is felt deep within the patient's internal organs. It is related to the energetic release of the patient's emotions and the energy of the doctor's Middle Dantian.
3. Shen vibrational resonance is felt within the patient's center core. It is related to the ener-

getic release of the patient's spirit and the energy of the doctor's Upper Dantian.

The release of energetic vibration is primarily used to activate the patient's channel Qi. Clinically, it is most effective when the frequency of the doctor's hand vibrations matches and synchronizes with the vibrational frequency of the patient.

While treating the patient, the doctor's palm usually gets hot and vibrates when coming in contact with Qi stagnation. If a patient's channel point becomes blocked, energy builds up causes Qi stagnation. Once the Qi stagnation is removed, the doctor's hands will cease to vibrate as the channels open and flow freely. When cleared, the patient feels fatigue as the toxins are released from the body and the energy seeks to balance itself.

To apply the Vibrating Technique, the doctor selects the proper hand posture and the area to be treated, then barely touches the patient's body. Any firm pressure should be avoided so as not to hinder the extending and directing of Qi. The doctor initiates the vibrational extension of Qi from the Lower Dantian, slowly turning clockwise or counterclockwise, while directing the vibration out through the hands. The doctor focuses on his or her own breath to adjust the frequency and amplitude of the vibration, the shape and nature of the emitted Qi (Yin or Yang, etc.), and the strength of the energy.

Some examples of hand postures and tissue regulation techniques for emitting vibrational energy include:

a. The Extended Fan Palm is used for activating and regulating Qi activities by:
   - Vibrating the Extended Fan Palm on the Baihui GV-20 point, to descend the patient's Yang Qi, tranquilize the patient's mind, regulate Qi in the Upper Burner, and induce sleep;
   - Vibrating the Zhong Wan CV-12 point to replenished the patient's Qi, to regulate the Stomach's energy and to induce sleep;
   - Vibrating the patient's Lower Dantian, to Lead the Qi back to its origin through supplementing its Qi;
   - Vibrating the Mingmen GV-4 and Da Zhui GV-14 points, to activate Qi in the Governing Vessel.

b. The Sword Finger Palm is used for directing and emitting concentrated vibrational energy into channel points, to stimulate the patient's energetic field.

c. The Invisible Needle Palm is used for directing and emitting the most condensed form of concentrated vibrational energy into the channel points, to stimulate the patient's energetic field.

VIBRATING PALM EXERCISE

The training for this kind of vibrational extension usually begins from a static Wuji posture, then gradually progresses into a dynamic state of energy projection.

- From a Wuji posture, press both palms together at the center of the chest forming a "Buddhist greeting" posture (see Chapter 15). Press the Baihui point upward and the Mingmen backward, while slightly drawing in the chest. Keep hips relaxed, knees bent, tongue on palate, and eyes closed.
- Breathe naturally while focusing the mind on the Lower Dantian. When the Heat and Qi begin to circulate, exhale while mentally guiding the Qi up the chest into both of the palms, by sending the energy through the three Yin channels of the hands.

When inhaling, mentally guide the Qi along the three Yang channels of the hands, back down the back into the Lower Dantian. Maintain natural breathing, and continue to focus attention on both the palms and the fingertips. The palms should heat up and the fingertips tingle, as they expand with Qi (Figure 34.15).

Lead the vibrating energy in the Lower Dantian up into the palms and fingertips, feeling the tissues dissolve inch by inch, cell by cell. The Qi is always centered on the inner Lao Gong Pc-8 point, gathering and collecting but not dispersing. Practice this exercise once or twice a day for 3-10 minutes.

Note: It is imperative that the doctor, when using the technique of "stationary energy pro-



Figure 34.15. The Vibrating Palm exercise helps to increase the Qigong doctor's projected vibration.

jection," never hold his or her breath, or purposely make the hand vibrate by forcefully shaking the muscles. To do so causes Qi stagnation which results in pain and stiffness in the chest and sharp pain in the arms that feels similar to having a fractured bone or a laceration of the muscles. To ensure that there are no difficulties, the doctor should first master the Vibrating Qi method, allowing the vibrating energy to extend and project naturally.

GUIDING THE HOT AND COLD FLOW OF ENERGY

This method refers to the doctor's release of energy being emitted into the patient's body to either regulate Hot syndromes with Cold energy, or Cold syndromes with Hot energy. These two Yin and Yang energetic properties are used to develop the emission of both Hot and Cold energetic flows, through breathing, mental concentration and finger placement.

When Yin Qi is applied, the patient will feel "cold as iron," when Yang Qi is applied, the patient will feel "hot as fire." The mind plays an important role in regulating the doctor's and patient's Yin and Yang energy. When the Qigong doctor thinks of fire, the doctor's body will naturally become hot; conversely, when the doctor thinks of water, his or her body will naturally become cold.

HAND MANIPULATION OF YIN AND YANG ENERGY EXTENSION

The Yin (Cold) and Yang (Hot) energy extension utilizes specific palm and finger arrangements. The index and middle fingers together are assigned Yang properties, whereas the ring and little fingers together are assigned Yin properties. The doctor's left thumb connects with the selected two fingers, to determine the release of Yin or Yang energies. This energy is first gathered from the doctor's left hand, through the arm into the Lower Dantian, then emitted out through the right hand. The Qi that is emitted when the doctor's thumb, index and middle fingers connect, for example, releases the Heart's Yang Qi through the right hand. This technique is used to replenish the patient's Yang and regulate the patient's Heart energy.

GATHERING AND ISSUING YANG (HOT) ENERGY

Before emitting Hot energy into the patient, the doctor's Qi is first gathered into his or her left palm by imagining a small "fiery red sun" radiating heat, light, and fire. This small sun is imagined within the circle created between the thumb and first two fingers on the left hand. The hot energy of the sun is then absorbed through the doctor's left arm into the Lower Dantian. The Heat is then blended with the Lower Dantian's Qi and released out the doctor's right arm through either the tips of the index and middle fingers (the Yang Sword Fingers hand technique) for a deeper, concentrated type of penetration, or through the Extended Fan Palm hand technique for a dispersing type of penetration.

To extend Hot energy deeper into the patient, the right hand Yang Sword Finger posture is used. The doctor's index and middle fingers are extended and joined together, the ring and little fingers curl into the center of the palm. The thumb should rest on the nails of the ring and little finger, forming a circle.

The first or "index" finger indicates the Wood Element, i.e., the Liver's energy, and the middle finger indicates the Fire Element or the Heart's Qi. Together, both fingers activate the Qi of Fire and Wood, which catalyze the Yang energy needed for guiding Heat during point concentration.

Guiding Hot Yang Qi Exercise

This particular meditation is used to increase Heat and light in specific areas of the patient's body (usually for chronic, Deficient, or Cold syndromes). The following meditation, for example, can be used to Heat and tonify the Kidneys in chronic fatigue patients.

- Sit on the edge of a chair in front of a table, feet flat, eyes closed, with the left hand resting comfortably on the left thigh. The right palm is extended face down suspended over the table.
- Breathe naturally while concentrating the mind on the Lower Dantian. Imagine the energy in the Lower Dantian is a hot, burning sun expanding out and enveloping the entire body. Gather the energy back into the Lower Dantian, transforming it into heat and light. Draw the heat and light up into the chest, down the arms, and out the right palm. Concentrate and imagine the heat and light burning and extending into the table, penetrating deep into it. After awhile, switch palms. In China, this exercise is practiced while standing or sitting in the sunshine, facing south or east. Practice for 20-40 minutes (Figure 34.16).

GATHERING AND ISSUING YIN (COLD) ENERGY

Before extending Cold energy into the patient, the doctor's Qi is first gathered into his or her left palm by imagining a small, watery blue moon, radiating cool light. This small moon is imagined within the circle created between the thumb and last two fingers. The cool blue energy of the moon is then absorbed through the doctor's left arm, into the Lower Dantian. The cool blue energy is then blended with the Qi of the doctor's Lower Dantian and released out the doctor's right arm through either the tips of the ring and little fingers (the Yin Sword Fingers hand technique) for a deeper, concentrated type of penetration, or through the Extended Fan Palm hand technique for a dispersing type of penetration.



Figure 34.16. Guiding Hot Yang Qi Exercise

In extending cool blue energy into the patient, the right hand Yin Sword Finger posture is generally used. The doctor's ring and little fingers are extended and joined together, and the index and middle fingers curl into the center of the palm. The thumb should rest on the nails of the index and middle finger forming a circle.

The ring finger indicates the Metal Element or the Lungs' energy, and the little finger indicates the Water Element or the Kidneys' energy. Together, both fingers activate the Qi of Metal and Water, which is a catalyst for the Yin energy needed for guiding cool Yin Qi during point concentration.

Guiding Cold Yin Qi Exercise

This meditation is used to cool specific areas in the patient's body in acute, inflamed Excess or Heat syndromes. It can also be used, to cool down and dredge the Liver in cases of chronic depression.

- Sit on the edge of a chair in front of a table, feet flat, eyes closed, with the left hand resting comfortably on the left thigh. The right palm is extended face down suspended over a table.
- Breathe naturally while concentrating the mind on the Lower Dantian. Begin to gather energy from the heels and Bubbling Well (Kd-1) points, directing the energy through the chest (CV-17), out the arms, and into the right palm. Imagine the right palm turning as cold as ice. Focus the mind on the coldness of the right palm and imagine the cold energy penetrating deep into the table. In China, this exercise is practiced at night, facing north or west for 20-40 minutes (Figure 34.17).

Note: While practicing the Cold Yin Guiding exercise, never imagine that the whole body is cold, also do not direct and keep the cold energy into your body (only through it). Otherwise the Cold energy will affect the balance and energetic harmony of the Qi's flow. You can, however, use the image of cool blue water or vapor flowing through your body into the right hand (which is freezing cold), without causing harm to your body's energetic balance.

CLINICAL APPLICATION OF YIN AND YANG ENERGY EXTENSION

Traditionally, the Qigong doctor would emit Hot Yang Qi during the Yang period of the day (from midnight to high noon) to warm the patient's Cold areas. During the Yin periods of the day (from high noon to midnight) the doctor would apply the Cold Yin Qi to cool the Hot areas of the patient's body.

In China today, the clinical application of issuing Hot or Cold energy is no longer limited to the position of the sun and moon, but is applied according to the doctor's ability to regulate the Excess or Deficient condition of the patient's disease.

GUIDING THE ENERGETIC FLOW OF THE FIVE ELEMENTS

This particular Medical Qigong healing system is divided into two popular methods of energy extension: The Five Elemental Organ Energies Method and The Five Elemental Channel Energies Method.



Figure 34.17. Guiding Cold Yin Qi Exercise

Both systems can be used for diagnosing the patient (using palm detection) or for treating Excess or Deficient conditions within the patient's body (using energy extension techniques). Each of these two powerful systems of treatment has its own unique advantage in application. Both systems combine healing sound resonances with energy light extension of various colors, and are used in accordance with the theory of the Five Elements.

THE SIX CHARACTER FORMULA

When utilizing either the Five Elemental Organ, or Five Elemental Channel system of energy projection, the Qigong doctor will guide the energy of the Five Elements in conjunction with the Six Character Formula. The Six Character Formula includes: The Five Elemental Energies, Time of Treatment, Direction of Energy, Position of the Thumb, Guiding Energy, and Emitting Energy and Sound.

1. The Five Elemental Energies of Wood, Fire, Earth, Metal, and Water relate to either the Five Elemental Channel system of energy projection and the Blood / Heat Cycles; or the relate to Five

Elemental Organ system and the energy of the Five Yin Organs. The decision regarding which of the two methods to choose is determined by the patient's condition.

2. The time of treatment is traditionally determined by the doctor in accordance with the patient's Blood/Heat Cycle, the time of day (sunrise, noon, sunset, and midnight) and the season (summer, winter, autumn, or spring).
3. The direction of energy emitted into the patient's body is determined by the doctor in accordance with his or her intention to purge, tonify or regulate the patient's tissues.
4. The position of the thumb is determined in accordance with the type and amount of energy the doctor wishes to absorb into his or her Lower Dantian.
5. Guiding (Pushing, Pulling and Leading) the energy is determined by the doctor in accordance with the Excess or Deficiency of the patient's Five Yin Organs: Liver (Wood), Heart (Fire), Spleen (Earth), Lungs (Metal), and Kidneys (Water).
6. The type of energy (Qi or Shen) and the choice of sound to be emitted are determined by the doctor's intention and the condition of the patient's organs and channels. Qi and sound are emitted like water, Shen is emitted like light.

EMITTING THE ENERGY OF THE FIVE ELEMENTAL ORGANS

The method of projecting the Five Elemental Organ Energies is utilized by blending a specific organ energy together with the Qi stored in the doctor's Lower Dantian. Both of these energies are combined and then issued out the doctor's right palm into the patient. The fusion of the doctor's Lower Dantian Qi with the selected organ Qi is very powerful. This synergized Qi is further combined with sound resonation and colored light to treat patients with extreme conditions of Deficiency.

The left thumb connects with either the tip of the index (Wood), middle (Fire), ring (Metal), little finger (Water) or upper pad of the palm (Neutral) to connect with the selected organ energy (Figure 34.18).



Figure 34.18. Left Palm - The Five Element Organ Energy Pattern: the left hand is used in order to absorb the organ Qi into the doctor's Lower Dantian. This arrangement corresponds to the Five Seasonal Pattern Cycle and the Five Elements.

Five Fingers	**Five Elements**	**Five Viscera**
Thumb	Earth	Spleen
Index	Wood	Liver
Middle	Fire	Heart
Ring	Metal	Lungs
Little	Water	Kidneys

Figure 34.19. Hand Chart of the Five Elements

After choosing the appropriate thumb and finger position on the left hand to tap into the selected organ's energy, the doctor descends this energy into the Lower Dantian. This energy is then blended together with the energy of the Lower Dantian and led out of the doctor's body, to be emitted into the patient using the right hand, along with the sound and specific organ color (Figure 34.19).

EMITTING THE ENERGY OF THE FIVE ELEMENTAL CHANNELS

The method of projecting the Five Elemental Channel Energies is utilized by blending a specific channel energy together with the Qi stored in the doctor's Lower Dantian. To tap into the selected channel's energy, the thumb is positioned on the corresponding finger, or palm segment (Figure 34.20). The selected channel's energy is then blended with the Qi stored in the doctor's Lower Dantian. These combined energies are then issued out the doctor's right palm into the patient. The blending of channel and Lower Dantian Qi is strong but not as powerful as the doctor's organ energy.

The resonant sound and light emitted from the combined channel and Lower Dantian energy is considered appropriate for patients with moderate Deficiency conditions. Healing sounds in combination with specific colors can be emitted by the Qigong doctor to stimulate the internal tissues. When healing sounds are directed into the patients tissues they have a tonifying action, as opposed to the purging affect which happens when the patient's practice healing tones by themselves (see Chapter 40).

The treatment is conducted according to the Five Elemental Creative Cycle. First the energy of the "mother" element is gathered into the doctor's Lower Dantian to be combined with the doctor's Lower Dantian energy. After the doctor collects and mixes the mother's elemental channel energy with the Lower Dantian's energy, the doctor switches the left thumb's position to the mother's corresponding "child" element position. This enables the mother's channel energy to support the strength of the child's channel energy, which is emitted into the patient's body (Figure 34.21).

Note: The doctor first connects to the mother element, then to the child element. Thus the mother's elemental channel energy, Lower Dantian energy and the child's elemental channel Qi are synergized and projected into the patient's corresponding "child" organ. The patient's organ, into which the Qi is emitted, has the same elemental attribute as the doctor's "child" transmitted energy.

1. To Emit Liver Energy and Guide Wood Qi proceed as follows:
   - First, from a Wuji posture, press the left thumb into the channel Water bands (9, 10). Inhale this Water energy into the Lower Dantian, mixing it together with your Lower Dantian energy.
   - Second, extend the right hand facing outward from the chest, facing the patient. Then exhale and press the thumb onto the Wood channel bands (1, 2) while uttering the sound "Shu." Guide the Wood energy out of the right palm into the patient's Liver organ or channel. In this particular technique, the doctor is using Water energy to support the extension of Wood energy.
2. To Emit Heart Energy and Guide Fire Qi proceed as follows:
   - First, from a Wuji posture, press the left thumb into the channel Wood bands (1, 2), while inhaling the Wood energy into the Lower Dantian, mixing it together with your Lower Dantian energy.
   - Second, extend the right hand facing outward in front of the chest, towards the patient. When exhaling, press the thumb onto the Fire channel bands (7, 8) with the thumb while uttering the Heart sound "Haa." Guide the Fire energy out the right palm into the treatment area. In this particular technique, the doctor is using Wood energy to support the extension of Fire energy.
3. To Emit Spleen Energy and Guide Earth Qi proceed as follows:
   - First, from a Wuji posture, press the left thumb into the channel Fire bands (7, 8) gathering this Fire energy into your Lower Dantian.
   - Second, extend the right hand in front of the

Colors		Element	Channel
1.	Green	Wood	Gall Bladder
2.	Green	Wood	Liver
3.	White	Metal	Lungs
4.	White	Metal	Large Intestine
5.	Yellow	Earth	Stomach
6.	Yellow	Earth	Spleen
7.	Red	Fire	Heart
8.	Red	Fire	Small Intestine
9.	Blue	Water	Bladder
10.	Blue	Water	Kidney
11.	Red	Fire	Pericardium
12.	Red	Fire	Triple Burner

Figure 34.20. The Twelve Channels are superimposed onto the Qigong doctor's left palm, arranged according to the progression of the Two Hour Qi and Blood/Heat Cycle.

This Blood/Heat Cycle also corresponds to the Four Principle Time Periods and can be divided into quarters and arranged according to the Midnight, Sunrise, Noon, and Sunset patterns of the Sun.



Figure 34.21. Left Palm - The Five Elemental Channel Pattern:

The left palm is used in gathering and absorbing the channel Qi of the doctor's Five Yin Organs. As the Qigong doctor's thumb touches the specific areas on the fingers, the energy is gathered into the doctor's Lower Dantian and released out from the right palm.

chest, facing outward towards the patient. When exhaling, press the thumb into the Earth's channel bands (5, 6) while uttering the Spleen sound "Who." Guide the Earth energy out of the right palm into the treatment area. In this particular technique the doctor is using Fire energy to support the extension of Earth energy.

4. To Emit Lung Energy and Guide Metal Qi proceed as follows:

- First, from a Wuji posture, connect the left thumb onto the tip of the left index finger (i.e., the Earth channel bands #5, 6), thus forming a circle. Imagine this circle full of golden light. When inhaling, draw this golden Earth energy into the Lower Dantian, while also inhaling Heavenly Qi into the Yellow Court area (CV-12) below the solar plexus. Mix all three of these energies together.
- Second, extend the right hand facing outward in front of the chest, towards the patient. When exhaling, press the thumb the Metal channel bands (3, 4) while uttering the Lungs' sound "Sss." Guide the Metal energy out of the body by way of the right palm into the treatment area. In this particular technique, the doctor is using

11. Be aware of the connection of the mouth with the spleen and pancreas. As the pearl arrives at the spleen and pancreas, the honor and respect, love and joy energy that is now part of the pearl fuses with the spleen virtues of fairness and openness. The fairness and openness virtues of the spleen can feel **expansive, clean, dry, bright yellow, smooth, warm, clear** and **soft**. Enjoy these feelings.
12. Let the pearl absorb the fairness and openness energy. Feel the pearl take on the qualities of the fairness and openness virtues in addition to the kindness, gentleness, honor and respect virtues that already are present there. Bring the pearl to the spleen collection point behind the navel at the front pakua.


1. Become aware of the spleen.
2. Do the Spleen Sound (Whoooo) subvocally.
3. Pull up the spleen energy form the navel and blend into front pakua.
Spleen
The collection point of the spleen's energy is the center of the front pakua.

***Fig. 6.45** Gathering the Spleen's Energy Directly into the Pakua.*

Feel the fairness and openness energy intensify as it combines and blends with all the neutral and virtue energies already present in the pearl. Direct the pearl to the lungs.

13. The Energy of fairness and openness fuses with the courage and righteousness virtues of the lungs.

imagination to draw the Earth's golden light energy into his or her Lower Dantian to support the extension of Metal energy.

5. To Emit Kidney Energy and Guide Water Qi proceed as follows:
   - First, from a Wuji posture, press the left thumb into the Metal channel bands (3, 4). Inhale the Metal energy into the Kidneys, mixing it together in the Lower Dantian.
   - Second, extend the right hand facing outward in front of the chest. As you exhale, press the Water channel bands (9, 10) while uttering the "Chree" sound (in a very low pitch). Guide the Water energy out of the body by way of the right palm. In this particular technique, the doctor is using Metal energy to support the extension of Water Qi.

Once skilled in these five exercises, the Qigong doctor should continue to practice them in combination with the Linear, Circular, or Spiral Energy Guiding Methods, creating an individualized, structured technique.

COMBINING THE ENERGY OF THE FIVE ELEMENTAL TONGUE POSITIONS

The doctor can also use the Five Elemental Tongue Positions to increase the power and energetic potential of the doctor's internal organ. Each tongue position connects with the organ's Orb (the complete organ system), thereby increasing the power of the doctor's Qi projection. These tongue positions are described as follows.

1. To connect with Earth (Spleen) energy—the tongue is placed on the bottom of the jaw at the base of the lower palate, beneath the teeth and gum line.
2. To connect with Metal (Lungs) energy—the tongue is placed between the maxilla and mandible bones, suspended, between the teeth.
3. To connect with Fire (Heart) energy—the tongue is placed on the hard palate, at the front of the upper palate, behind the teeth and gum line.
4. To connect with Wood (Liver) energy—the tongue is placed on the hard palate, at the middle of the upper palate at the center of the roof of the mouth.
5. To connect with Water (Kidneys) energy—the tongue is placed on the soft palate, at the back of the upper palate.

COMBINING THE ENERGY OF THE FIVE ELEMENTAL COLORS

The doctor can also include the Five Elemental Colors to increase the power of his or her internal Qi projections (see Chapter 4). The Five Elemental Colors are described as follows.

- Earth (Spleen)—The organ color bright yellow, the channel color is soft yellow.
- Metal (Lungs)—The organ color bright white, the channel color is soft white.
- Fire (Heart)—The organ color bright red, the channel color is soft red.
- Wood (Liver)—The organ color bright green, the channel color is soft green.
- Water (Kidneys)—The organ color bright blue, the channel color is soft blue.

SUMMARY OF QI EMITTING METHODS

When the Qigong doctor emits Qi into the patient, it effects the quality of light, sound, heat, vibration, and electromagnetic energy stored within the patient's tissues and cells. There are many variations of Qi emission hand postures and techniques used by Qigong doctors in China. Each differs according to the various schools, colleges, and styles of Medical Qigong training. These changeable and diverse hand postures, as well as the various Qi extension, guidance, and regulation techniques can all be combined and grouped together to assist the Qigong doctor in understanding the clinical treatment potentials. The following is an outline of the aforementioned Hand Postures and Extension, Guidance, and Regulation techniques (described in Chapter 33 and 34), along with their applications.

HAND POSTURES USED FOR EMITTING QI

1. The Extended Fan Palm Hand Posture energy emission has the widest beam of Qi extension.
2. The Sword Finger Hand Posture energy emission has the width and beam reduced into a more condensed form of Qi extension.
3. The One Finger Skill Hand Posture energy emission is further reduced into an even more condensed form of Qi extension.

4. The Invisible Needle Hand Posture energy emission is condensed even further into a finely honed needle of light, similar to that of a laser beam.

HAND TECHNIQUES USED FOR BREAKING UP ENERGETIC STAGNATIONS

1. The Thunder Fingers Hand Technique is the strongest, most aggressive hand technique, and is used to break into the energetic boundary of the Qi stagnation. It is used as a preparation technique before purging the stagnation.
2. The Shaking and Trembling Hand Technique is the second most aggressive hand technique, and is used to purge stagnation and toxic Qi from the patient's body.
3. The Vibrating Hand Technique is a powerful, yet subtle hand technique, which can be used to expand, contract, vibrate, and loosen the patient's Stagnant Qi.
4. The Kneading Tiger Hand Technique is used to separate the Toxic Qi, and to dredge and purge it out of the patient's body.

ENERGY EXTENSION AND GUIDANCE TECHNIQUES FOR MOVING QI

1. The Pushing Technique is used to push and move the energy within the body's tissues, channels, and energetic fields.
2. The Pulling Technique is used to pull and move the energy within the body's tissues, channels, and energetic fields.
3. The Leading Technique is used to lead, guide, and move the energy within the body's tissues, channels, and energetic fields.
4. The Circling Technique is used to lead, guide, and move the energy in a circling pattern within the body's tissues, channels, and energetic fields.
5. The Spiraling Technique is used to spiral or drill energy into or out of the body's tissues, channels, and energetic fields.
6. The Energetic Cupping Technique is used to lead, guide, and move the energy within the body's tissues, channels, and energetic fields.

HAND POSTURES USED FOR PURGING, DREDGING, AND REMOVING TOXIC QI

1. The Bellows Palm Hand Posture is used like a vacuum to remove toxic Qi
2. The Dragons Mouth Palm Hand Posture is used to grasp, pull, and lead toxic Qi from the body.
3. The Sword Fingers Hand Posture is used to circle-wrap toxic Qi (like a fork wrapping spaghetti) and remove it from the body.
4. The Kneading Tiger Hand Posture is used to grasp, seize, and pull toxic Qi from the body.
5. The Shaking and Trembling Hand Posture is used in order to grasp, seize, and pull toxic Qi from the body.
6. The Thunder Fingers Hand Posture is used to shake and release toxic Qi from the doctor's body.
7. The Extended Fan Palm Hand Posture is used to dredge, pull, and purge toxic Qi from the body.

TYPES OF ENERGY RELEASED THROUGH QI EMISSION

1. Hot Qi Emission is used to tonify or sedate a specific area, organ, channel, or energetic field.
2. Cold Qi Emission is used to cool down or sedate a specific area, organ, channel, or energetic field.
3. Color Qi Emission is used to tonify or sedate a specific area, organ, channel, or energetic field.
4. Sound Emission is used to tonify or sedate a specific area, organ, channel, or energetic field.
5. Five Elemental Organ Qi Emission is used to tonify or sedate a specific area, organ, channel, or energetic field.
6. Five Elemental Channel Qi Emission is used to tonify or sedate a specific area, organ, channel, or energetic field.

CHAPTER 35
THE INVISIBLE NEEDLE THEORY AND APPLICATION

INTRODUCTION

In China today, the use of Invisible Needles in Medical Qigong therapy is usually reserved for patients who are hypersensitive to energy flow. As the patient's sensitivity increases, the treatments are modified in order to complement their perceptive abilities.

To perform the Invisible Needle technique, the Qigong doctor must first connect with the divine energy. This is performed by drawing energy from the Heavens through the Baihui GV-20 point at the top of the head and extending it out through the hands, enveloping the patient. Some Qigong doctors imagine that needles of light, from the Heavens, descend through their Baihui point. As this light fills their body, they become empowered with a never-ending reserve of Invisible Needles to treat the patient. In order to use these needles, the doctors rotate their wrist clockwise and the Invisible Needle flows out the Pc-8 Point at the center of their palm (Figure 35.1).

Other Qigong doctors use a single needle image. The doctor imagines needles of light coming out of the Heavens, spiraling around the head like a golden halo. This golden halo is positioned above the head, above the Heavenly Transpersonal Point (located about a foot above the head). To use these needles, the doctors reach above their head and pluck the needles from the Heavens. These needles are then inserted into the patient's body (Figure 35.2). When using either visualization, the important factor is to focus on how deep the needles should penetrate. When treating an area deep in the major organs, a clockwise rotation reinforces and tonifies, while a counterclockwise rotation sedates the organ area.

PREPARATION

Before inserting an Invisible Needle into the



Figure 35.1. The Qigong doctor imagines divine healing light descending from the Heavens, filling the doctor's body with the energy to create the Invisible Needle.



Figure 35.2. Another variation is for the Qigong doctor to imagine divine healing light descending from the Heavens and encircling the doctor's head like a golden halo. Contained within this halo are the Invisible Needles.

patient, it is important for the doctor to dredge the diseased area first. This is similar to swabbing an area with alcohol (or disinfectant) before inserting an acupuncture needle. As one hand extends the Invisible Needle, the other is used to reinforce its energy. The doctor works the Invisible Needle into the patient's tissues until he or she feels it inside the patient's body. Sometimes the patient may feel a cold sensation while being treated by the doctor. This is a normal reaction to the Invisible Needle insertion. The longer that the doctor keeps the Invisible Needle inserted inside the patient's body, the better the healing effect.

ANGLE OF INSERTION FOR TONIFICATION OR SEDATION

The skill of using Invisible Needles encompasses a complete system of energetics that utilizes both reinforcing (tonifying) and reducing (sedating) techniques. The polarity of the patient's channel (Yin or Yang) determines the angle at which the Invisible Needle is inserted.

- When performing reducing or sedating techniques, it is important to insert the Invisible Needles perpendicularly into the patient's points or channels, forming an energetic dam to slow the flow of Qi (Figure 35.3). The doctor removes the needle slowly, and leaves the point open (this allows the point to continue to release Qi naturally).
- When performing any reinforcing or tonifying techniques, insert the Invisible Needle at an angle, pointed in the direction of the channel's flow (provided that the channel is flowing towards the direction of the intended organ). Then, when retracting the Invisible Needle, remove it quickly and seal the point. This quick retraction method is done to prevent the Qi from escaping the area once it is stimulated, and is followed by pressing the needle hole to seal the point (Figure 35.4).

One favorite tonification technique used by certain Qigong doctors in Beijing, China is to leave the Invisible Needles inside the patient, while regulating the Conception and Governing Vessels. Once they have strengthened the patient's Microcosmic Orbit (Fire Cycle), they retract the Invisible Needles and disperse them one by one into the Earth. The insertion and manipulation of the Invisible Needles is performed with the Invisible Needle Palm technique.



Figure 35.3. The doctor's right hand extends the Invisible Needle perpendicularly into the patient's point or channel, to reduce or sedate the energy flow. The doctor's left hand is used to reinforce the energetic purging of the patient's toxins.



Figure 35.4. Insert the Invisible Needle at a 45 degree angle with the flow of the patient's channel to reinforce or tonify, provided the channel's flow is towards the organ.

In order to prevent the Qi from escaping, when performing any reinforcing or tonifying techniques, the Qigong doctor presses the patient's channel point after retracting the Invisible Needle.

Another favorite technique used for tonification is for the Qigong doctor to first insert the Invisible Needle deep into the patient's Kd-1 point at the bottom of the feet. Once the needle is inserted, the doctor extends his or her intention, causing the needle to grow and extend up the patient's legs and into the Kidneys. Next, the doctor emits energy up the patient's legs to further tonify the Kidneys and Mingmen area.

The Invisible Needles can also be transformed into the specific colors of the Five Elements to enhance tonification. A blue needle, for example, can be used to intensify Kidney tonification. Each needle can additionally be spiraled in a clockwise or counterclockwise direction to generate an energetic vortex used for either tonification or purgation (Figure 35.5).

THE HAND POSTURES OF THE INVISIBLE NEEDLE

The following is a description of the various hand postures used when treating patients with the Invisible Needle technique.

THE DOCTOR'S RIGHT HAND

The doctor's right hand is generally used for controlling and projecting the energy of the Invisible Needle into the patient. It is not only responsible for the formation but also the insertion of the Invisible Needle. The action and movement of the right palm projecting and stimulating Qi is sometimes referred to as the Chicken Pecking technique. In this hand posture, the thumb connects with the index finger or index and middle finger to form the shape of a bird's beak (Figure 35.6). While these fingers are joined together, the other fingers on the hand relax in an extended, straight position. The doctor's intention is focused on the image of an Invisible Needle which is projected into the patient's body.

The pricking, insertion, and manipulation of the Invisible Needle is only effective when the Qigong doctor connects and roots his or her intention deep within the patient's Jing, Qi, and Shen. This intention connects the doctor with the patient's Qi and Blood, and their animated Spirit.

THE DOCTOR'S LEFT HAND

The doctor's left hand is used to either manipulate the patient's tissues to enhance the Qigong treatment, or to collect Qi into the doctor's Lower Dantian to be projected into the patient. This technique is similar in method to collecting the Yin (Cold) and Yang (Hot) energy before emitting it into the patient. Once the thumb connects with any of the fingers, the released energy bears the nature of the associated element and its Yin and Yang properties (Figure 35.7). The Qi that is collected when the thumb and middle finger connect, for example, is the Yang Qi within the Heart.



The needle can be made to grow and extend deep inside the patient's tissues or channels.

The needle can be made to grow fat inside the patient's tissues or channels to increase Qi projection.



Clockwise spiraling the needle is used to create an energetic vortex for tonification.

Counterclockwise spiraling the needle is used to create an energetic vortex for purgation.

Figure 35.5. The Invisible Needle Techniques



Figure 35.6. The Invisible Needle Palm

This Qi replenishes the Yang Qi and regulates the energy of the Heart (Figure 35.8). If the doctor's hand is positioned over the Pericardium Channel and energy is emitted into the patient, the patient's Shen will become peaceful. When treating with the Five Elemental organ energy, the index and middle finger stand for Fire and Wood; this combination is considered Yang. The ring and little finger stand for Water and Metal; this combination gathers and creates Yin energy.

TIME AND DURATION OF TREATMENT

In general, Medical Qigong Invisible Needle Technique and Point Therapy is applied once a day. A routine therapeutic course includes six to eighteen treatments. Patients with mild diseases may continue the therapy from six to twenty-four treatments. For chronic patients, however, treatment may last as long as one to three months depending on the patient's condition (i.e., for paraplegic patients the treatment is generally from three to six months).

As far as the time sequence of when to treat the patient, or when the patient is to treat themselves, the chronometric rate is based on the high-tide sequence of the patient's channels (i.e., 11 am to 1 pm is the Heart time, which is the best time period to treat patients with Heart disease).

REMOVING THE INVISIBLE NEEDLES AND ENDING THE TREATMENT

During tonifying treatment, the Qigong doctor removes the Invisible Needle quickly from its point of origin while the patient is inhaling. This allows the patient to keep the Qi and Shen within the body's channels and tissues. After extracting the needle, the doctor presses down on the acupuncture point with emitted Qi and lightly rubs it in a clockwise direction until the open point has closed.

During a sedating treatment, the Qigong doctor has the patient exhale to expel the Evil Qi and Heat from the patient's tissues. After extracting the needle slowly, the doctor allows the acupuncture point to naturally drain and eventually close by itself. This aids in draining the Evil Qi and Excess Heat from the patient's body.



Figure 35.7. When treating patient's with the Invisible Needle technique for tonification, the Qigong doctor emits the required amount of energy into the patient, according to the specific Deficient organ and channel's condition.

The thumb, being the Earth Element and neutral, allows the Qigong doctor the ability to connect and combine the energy of the Five Yin Organs into his or her Lower Dantian, before extending the Qi into the patient.

Five Fingers	Five Elements	Five Viscera
Thumb	Earth	Spleen
Index	Wood	Liver
Middle	Fire	Heart
Ring	Metal	Lungs
Little	Water	Kidneys

Figure 35.8. Hand Chart of the Five Elements

CHAPTER 36

ENERGETIC POINT THERAPY

The importance of Energetic Point therapy as a Medical Qigong modality can best be understood when exploring the amount of information stored within the body's tissues. According to theoretical physicist Michio Kaku, the body's DNA contains over one hundred trillion times the information stored in current computers. There is an even greater amount of information stored within the three subtle energy fields outside of the human body. Most of this information is not readily translatable or decipherable, and is hidden from the conscious mind.

By stimulating certain energy points, for a specific length of time, an energetic trigger mechanism, or response reflex is created. This energetic reaction releases memories and stored information unique to each patient. To facilitate the unlocking of this stored information, the Qigong doctor must maintain a deep state of Alpha consciousness when stimulating the patient's energy points.

Energetic Point therapy involves two distinct modalities of treatment: Channel Point treatments and Channel Point meditations. Either can be used in conjunction with the Invisible Needle therapy. In these particular modalities of treatment, the Qigong doctor can either emit Qi into specific channel points on the patient's body to enhance the Medical Qigong treatment, or have the patient meditate on a specific point while the doctor administers the therapy. Both approaches can be used by the Qigong doctor to gather energy, move Qi, or release trapped energy from the patient's tissues.

CHANNEL POINT TREATMENTS AND PRESCRIPTIONS

The following treatments are generally used in the clinic by the Qigong doctor for Invisible Needle therapy, but are not necessarily limited to that modality of treatment. These Energetic Point treatments are arranged and categorized according to specific diseases. The Energetic Points are located on the patient's front and back as depicted in the anatomical graphs (Figures 36.1 and 36.2). These points are clinically used for the following treatment goals:

POINT THERAPY TO TONIFY YIN ENERGY

1. To Tonify Yin energy and to reduce a Deficient type of Fire, extend Qi into the patient's Kd-3 point.
2. To nourish the Yin energy and to reduce Fire, extend Qi into the patient's Kd-3 and Lu-10 points.
3. To treat a Deficiency of Yin of the Liver and Kidneys and to reduce the causes of Deficient Fire, extend Qi into the patient's Sp-6 and Lv-3 points.
4. To treat a Deficiency of Yin causing a dryness of the Lungs, extend Qi into the patient's Lu-1 and Bl-13 points on the front and back of the body. Regulate the respiratory tract, as well as the patient's Lu-7 and Kd-6 points, thereby tonifying the body's Yin energy and activating the descending function of the Lungs.

POINT THERAPY TO TONIFYING OR DISPERSE YANG ENERGY

1. To strengthen the Yang of the patient's Kidneys, extend energy into the patient's GV-4, Bl-23, and Kd-3 points.
2. To warm, and tonify the Yang of the patient's Spleen and Kidneys, extend energy into the patient's Bl-20 and -23 points. This treatment is ideal for eliminating Damp fluid caused from Deficient types of edema.
3. To fortify the Yang and avert a state of Yang collapse, tonify the patient's Yuan Qi by extending energy into the patient's Lower Dantian, focusing specifically on the patient's CV-4, -6, and -8 points.


Bl-7
Bl-7
CV-22
Pc-3
CV-13
CV-12
Pc-3
Pc-5
Lv-15
CV-8
CV-6
Lu-7
CV-3
St-29
CV-2
Lv-15
Pc-5
Lu-7
St-29
Sp-10
Sp-10
St-36
Sp-9
Sp-9
St-40
Lv-5
Lv-5
Sp-6
Sp-6
Lv-3
Lv-2
Lv-3
Lv-2
Sp-4
Sp-3
Sp-1

Figure 36.1. Chart of Specific Channel Points

4. To treat a condition of Deficiency of Yang of the Spleen, strengthen the patient's Stomach and Spleen to eliminate Damp and Phlegm. This is done by extending energy and tonifying the patient's St-36, CV-12, and Bl-20 points. Then activate and warm the Qi of the patient's Lungs by extending Qi into Bl-13, and -43 points.
5. To strengthen the Yang of the Spleen, promote the Spleen's transporting function by extending energy into the patient's CV-12, Bl-20, Lv-13, and Sp-3 points.
6. To raise the patient's Yang Qi or the Yang Qi flowing within the patient's Governing Vessel, extend energy into the GV-20 point.
7. To reduce hyperactive Yang of the patient's Liver, first dredge and disperse the patient's GB-20, Bl-18, and Lv-2 points to pacify the Yang of the Liver; then tonify by extending energy into the patient's Bl-23 and Kd-3 points to strengthen the Kidneys.
8. To reduce Excess Yang within the patient's Governing Vessel which has caused a hyperactivity of Heat, dredge and sedate the patient's GB-2O point. Then purge the Heat from the patient's GV-14 and LI-4 points.

POINT THERAPY TO TONIFY OR DISPERSE QI

1. To strengthen the patient's Yuan Qi, extend Qi into the patient's Lower Dantian, focusing on CV-4 and -6 points.
2. To fortify the patient's Qi and reestablish their Yang, extend energy into the patient's GV-20, CV-6, and St-36 points.
3. To subdue the patient's ascending Qi, extend Qi into the patient's CV-22 and Bl-17 points.
4. To disperse the patient's stagnant Qi and Phlegm, extend Qi into the patient's Bl-13 point.
5. To tonify the Kidneys' Qi and Jing and to reduce any Kidney Deficiency, extend Qi into the patient's GV-4, Bl-52, and Kd-3 points.
6. To stimulate the circulation of Qi and Blood, extend Qi into the patient's LI-4 and Lv-3 points.

POINT THERAPY TO TONIFY AND NOURISH THE BLOOD

1. To activate the patient's Blood circulation, extend energy into the patient's Sp-10 point.
2. To stimulate the function of conducting Blood, extend energy into the patient's Sp-1 point.
3. To control the production of Blood, extend energy into the patient's Bl-20 point to control the Blood, as well as Bl-15 to increase the production of Blood.
4. To activate Blood circulation and remove stasis, extend energy into the patient's Sp-6 and Bl-17.
5. To strengthen the source of Blood formation, extend energy into the patient's St-36 and Sp-6 points.
6. To remove Blood stasis of the uterus, extend energy into the patient's Bl-32 and St-29 points.

POINT THERAPY TO ELIMINATE COLD AND DAMP

1. To warm the Spleen and Stomach to eliminate Cold, extend energy into the patient's Lower Dantian and CV-12 and -13 area.
2. To disperse Cold, relieve pain, pacify the Stomach and strengthen the Spleen, extend energy into the patient's Sp-4 and Bl-20 points.
3. To strengthen the Spleen to disperse Dampness, extend energy into the patient's Sp-6 and St-36 points.
4. To eliminate edema above the waist, extend energy into the patient's Bl-20 and Lv-13 points.
5. To eliminate edema below the waist, extend energy into the patient's Bl-28, LI-6, and Sp-9 points.

POINT THERAPY TO ELIMINATE HEAT

1. To eliminate Heat from the patient's body, extend energy into the patient's LI-11 points, or dredge and disperse energy from the patient's Shi Xuan points (at the tips of the fingers).
2. To move Heat downwards from the patient's body, dredge and disperse energy from the patient's Kd-1 points.
3. To disperse External Heat, dredge and disperse energy from the patient's SI-3 points.
4. To eliminate Internal Heat, dredge and disperse energy from the patient's Pc-5 points.
5. To eliminate Damp Heat, extend energy into the patient's Bl-20 and Sp-9 points.

Connect the nose to both lungs. As the pearl arrives at the lungs, split the pearl into two pearls, one for each lung. The energy of fairness and openness that is now part of both pearls fuse and enhances the courage and righteousness energy of the lungs. When you feel righteous, you can feel **tall, straight, uplifted, comfortable, strong, firm, proud** and **satisfied**. The energy can be **fresh, bright, white** and **pure**. Enjoy the qualities of this energy.

14. Let the pearls absorb the courage and righteousness energy. Bring both pearls to the collection point of the lungs (at the level of the navel and in line with the left nipple). Feel the courage and righteousness energy intensify as it circulates in the lungs. Let the pearls blend these virtues with their kindness, gentleness, honor, respect, fairness and openness energies.


1. Become aware of the lungs.
2. Do the Lungs' Sound (Sssssss) subvocally.
4. Form the lungs' collection point by pulling up on the left side and forming a white sphere. Gather the lungs energy.
3. Pull up the right and left sides of the anus to the lungs.

Fig. 6.46 *Forming t* *er the Lungs' Energy.*

Direct both pearls to both kidneys. Courage and righteousness fuse with gentleness: the cycle begins again at the kidneys.


GV-20
GV-16
GB-12
GB-12
GB-20
GB-20
GV-14
Bl-43
Bl-12
Bl-13
Bl-43
Bl-15
Bl-17
Bl-18
Bl-19
Bl-20
Bl-52
Bl-52
LI-11
LI-11
Bl-23
Bl-23
LI-6
Bl-32
Bl-32
GV-4
LI-6
TB-5
Bl-28
Bl-28
TB-5
LI-4
LI-4
SI-3
SI-3
Bl-38
Bl-38
Bl-40
Bl-40
GB-34
GB-34
Kd-7
Kd-7
Kd-3
Kd-3
Kd-1

Figure 36.2. Chart of Specific Channel Points

6. To eliminate Damp Heat from the Blood, dredge and disperse energy from the patient's Bl-40 points, then extend energy into the Pc-3 points.
7. To reduce Fire of the Liver, dredge and disperse energy from the patient's CV-3 and Lv-5 points.
8. To reduce Liver and Gall Bladder Upward Fire disturbance, dredge and disperse energy from the patient's GB-12, as well as Bl-19 and -18 areas.

POINT THERAPY TO ELIMINATE WIND

1. To eliminate Wind Cold, dredge and disperse energy from the patient's GV-16, Bl-12, GB-20, Lu-7, LI-4, and Kd-7 points.
2. To eliminate Wind Heat, dredge and disperse energy from the patient's GV-14, LI-4, TB-5, and GB-20 points.
3. To eliminate Wind from the upper portion of the patient's body, dredge and disperse energy from the patients Bl-7, GV-20, and -16 points.
4. To eliminate pathogenic Wind, extend energy into the patient's Lu-7 points to activate the natural dispersing function of the Lungs.
5. To eliminate Wind and reduce Fire, dredge and disperse energy from the patient's GB-20 points.
6. To calm the Wind of the Liver, dredge and disperse energy from the patient's Lv-3 points.

POINT THERAPY TO ELIMINATE PHLEGM

1. To eliminate Damp Phlegm in the Interior, first strengthen the function of the patient's Spleen and Stomach to eliminate the Dampness, by extending energy into the patient's Bl-20 and CV-12 points, then eliminate the Phlegm by dredging both of the St-40 points.
2. To eliminate Phlegm Fire in the patient's Stomach, dredge the patient's GB-34 and St-40 points.

CONTRAINDICATIONS

Never apply Energy Point therapy to patients who are in an acute stage of inflammatory diseases (especially of the abdomen). Also avoid using Energy Point therapy on patients with hypertension, heart diseases, severe cases of pulmonary tuberculosis, hemophilia, purpura hemorrhagic, purpura allergic, and severe skin diseases.

CHANNEL POINT MEDITATION

After applying the Invisible Needle technique or Energetic Point therapy, the Qigong doctor may decide to initiate Channel Point meditation to intensify the treatment. This is achieved by having the patient concentrate on specific points along the channels. This concentration will produce two distinct results. First, it will get rid of any of the patient's distracting thoughts, and second, it will cause different fluctuations of the Qi and Blood circulation through the patient's Yin and Yang organs. This focused concentration will allow the internal organs to supply the patient's body with either: a more concentrated flow of Qi and Blood into the tissue area; or the focused attention will have a stronger dispersing effect on the patient's tissues (depending on the patient's focus).

Each time a patient switches the focus of concentration to a different point in a different area of the body, the circulation and regulation of Qi and Blood will alter to accommodate the mental transitions of intention. In giving the patient a specific point meditation as a prescription, the Qigong doctor should be careful to select the areas and points in accordance with the particular Qigong exercises that will arrest the patient's Yin and Yang organ disease.

Generally speaking, when treating an Excess condition with Channel Point meditation, the Qigong doctor has the patient imagine draining the Excess Qi out through the extremities. In the case of a Deficiency, the doctor has the patient focus on tonifying the Deficient organ(s) by absorbing energy and light into the Deficient area. Below is a list of channel point regulations and their applications.

QIHAI (CV-6) SEA OF QI

The CV-6 point, located in the Lower Dantian, is the most frequently selected point (Figure 36.3). It is chosen for normal conditions to lead the Qi back to its origin. It is this area from which Qi emanates and returns, hence its name, Sea of Qi. Focusing on this point will allow the patient to tonify the Kidneys (Yuan) Qi, and can be used to regulate the Lower Burner, Conception Vessel, and Water pathways. The Qigong doctor may also extend energy into this area to:

- restore collapsed Yin or Yang Qi,
- raise the patient's Middle Burner Qi,
- warm a patient's Yang Qi,
- warm a patient's Cold condition,
- treat mental disorders,
- treat male sexual problems,
- treat urinary problems,
- treat local pain,
- treat fatigue, and
- treat Qi and Blood Deficiency.

MINGMEN (GV-4) GATE OF LIFE

This point is also called the Palace of Essence (Figure 36.4). Located between the two Kidneys, this point is used for patients with a Deficiency of the Kidney Yang and declining Fire of the Mingmen (this condition is manifested as lumbago pain, seminal emissions, and an aversion to cold). Focus the patient's concentration on the navel first, then gradually have the patient focus deeper into the Mingmen area. This area is known as the Sea of Blood and Essence. Focusing on this point will allow the patient to tonify and stabilize the Kidney (Yuan) Qi and Jing. A Qigong doctor extending energy into this area can regulate the patient's water pathways, heat the body's Yang Qi, and lower blood pressure. This point is also used to treat lower back pain, sciatica, as well as sexual / genital problems.

SHAO SHANG (LU-11) LESSER SHANG

This point is also called Ghost Sincerity, and is considered the second of eleven ghost points (Figure 36.5). The sound "shang" is a musical note and corresponds to the Element Metal. This particular point is used for patients with a Deficiency of Lung Qi (this is manifested by asthma and coughing). It reinforces the Qi and regulates the Lungs. A Qigong doctor can pull energy from this area to dredge and clear Lung Fire, Heat, and Summer Heat, as well as dispel Wind Heat from the patient's body.

ZHONG CHONG (PC-9) MIDDLE RUSHING

This point is used for patients with a Deficiency of Heart Qi (which manifests as palpi-



Figure 36.3. Lower Dantian (CV-6)



Figure 36.4. Mingmen (GV-4)



Figure 36.5. Shao Shang (Lu-11)

tations and restlessness). It reinforces the Qi and calms the Heart and mind. This area is good for regulating the Heart's Qi, reviving consciousness, and restoring collapsed Yang. It can be used to dredge and clear the patient's body of Heart Fire, Heat, and Summer Heat conditions (Figure 36.6).

ZU SAN LI (ST-36) FOOT THREE MILES

This point is used for patients with a disorder of transporting and transforming Spleen and Stomach Qi (which manifests as abdominal distention and pain). This point has a strong tonifying effect (especially for the Spleen) and regulates the Stomach. It also tonifies the Ying (Nutritive) Qi, and regulates the Lower and Middle Burners. It can be used by a Qigong doctor to dredge and reduce digestive stagnation, to redirect Rebellious Qi, to drain pathogenic influences from the Stomach, and to soften hard abdominal masses or tumors (Figure 36.7).

DA DUN (LV-1) GREAT PILE

This point is used for patients with hyperactive Liver Yang or overactive Liver and Heart Fire. It calms the Liver to treat diseases of the upper portion of the body (primarily the head). By focusing on this area, the patient can regulate and tonify the Liver Qi and Blood. The Qigong doctor may dredge this area to disperse Liver Qi and transform Damp Heat in the Lower Burner (Figure 36.8).

YONG QUAN (KD-1) GUSHING SPRING

This point is used for patients with Yin Deficiencies of the Liver and Kidney, hyperactivity of Fire due to Yin Deficiencies, or Excess in the upper torso and Deficiency in the lower torso. Concentration on this area will also calm the spirit, clear Fire and Heat from the head area, restore collapsed Yang, and transform Heart Phlegm (Figure 36.9).

BAIHUI (GV-20) HUNDRED MEETINGS

This point is used for patients with a Deficiency of Qi in the Middle Burner (manifested by a shortness of breath, dizziness, intractable diarrhea, and a prolapse of the internal organs). This point is known as the Sea of Marrow. Focusing on this area will clear the brain and calm the spirit. If the Qigong doctor treats this area, the patient's



Figure 36.6. Zhou Chong (Pc-9)



Figure 36.7. Zu San Li (St-36)



Figure 36.8. Da Dun (Lv-1)



Figure 36.9. Yong Quan (Kd-1)

lower orifices can be stabilized, the Qi can be warmed and tonified, and Yang Qi can be warmed and a collapse can be prevented. This point is also used in order to treat hypertension, insomnia, seizures, dizziness, headaches, and the prolapse of internal organs (Figure 36.10).

HUIYIN (CV-1) MEETING OF YIN

This point is used for patients with a Deficiency of Lung Qi and Kidney Yin (manifested by asthma and coughing). Focusing the patient's concentration on this area stabilizes the patient's Jing and lower orifices, as well as calms the spirit and clears the brain. It can be used by the Qigong doctor to tonify and regulate the patient's Qi, to clear Heat from the patient's body, to treat irregular menses, urethritis, prostatitis, and to raise the blood pressure (Figure 36.11).

YIN TANG (EX. HN. 3) SEAL HALL

This point is used for patients to calm the spirit, and can be used by the Qigong doctor to dispel Wind and clear Heat from the patient's body. This point is also used to treat epilepsy, nausea and vomiting, insomnia, sinus headaches, dizziness, and vertigo (Figure 36.12).



Figure 36.10. Baihui (GV-20)



Figure 36.11. Hui Yin (CV-1)



Figure 36.12. Yin Tang (Ex.Pt.)

CHAPTER 37
MEDICAL QIGONG MASSAGE

INTRODUCTION TO TISSUE FUNCTION

To understand the energetic function of surface and deep tissue stimulation through Medical Qigong Massage, it is important to first understand the reflexes and spontaneous energetic reactions within the body's tissues. The tissues of the human body are in a constant state of perpetual change. No matter where illness or damage has occurred, everything in the body is linked to the organs' and bowels' functions of producing and governing energy, and their interaction with the body's surface tissues (Figure 37.1–37.2).

In Traditional Chinese Medicine, the human body is viewed as a conglomeration of Qi, Blood, channels, tendons, fascia, bones, Marrow, bowels (Yang organs), and viscera (Yin organs). Each part is interdependent, each having inseparable Yin and Yang relationships and all of them interacting with each other. The following describes the interaction of: Qi and Blood, Tendons and Fascia, Bones and Marrow and the Bowels and Viscera.

1. Qi is considered the Blood's leader: as the Qi leads, the Blood follows. If the Qi ceases to flow, the Blood stops.
2. The tendons and fascia are used for channel energy movement. As the tendons and fascia stretch, they cause the channel Qi to increase its energetic movement and flow. When the tendons and fascia are calm, the channel Qi slows down.
3. The bones are the Marrow's residence. When the bones are hard, the Marrow is solid; when the bones are soft, the Marrow is hollow.
4. The bowels (Yang organs) are the viscera's (Yin organs') manifestations. If the bowels are strong, the organs become robust; when the bowels become weak, the viscera begin to fail.

Medical Qigong massage takes into consideration the function and flow of the body's tis-



Figure 37.1. The Human Body (Anterior)

sues, in conjunction with the interacting systems of the body's energetic fields, striving to regulate both systems at the same time.

TWO APPROACHES IN TREATMENT

Medical Qigong massage can be divided into two schools of treatment modalities: Surface Tissue Massage Therapy and Visceral Tissue Massage Therapy.

1. Surface Tissue Massage Therapy utilizes the Five Elemental Qi Massage Therapy techniques in conjunction with external tissue stimulation. All external tissue manipulation techniques used in Qigong massage should be light as a feather and should not exceed the pressure one would place on an eyeball. When treating with Surface Tissue Massage, the doctor's focus must be centered on the dispersion of pathogenic Qi and the expansion of the patient's Wei Qi, while softly touching the patient's tissues.
2. Visceral Tissue Massage Therapy utilizes the Five Elemental Qi Massage Therapy techniques in conjunction with deep tissue stimulation. By matching the patient's pulse frequency and respiration with that of the doctor's, a stable, energetic resonance is secured and treatment begins. When treating with Visceral Tissue Massage, the doctor's focus must be centered deep into the patient's internal organs without touching the patient's external tissues.

After external tissue massage is used to treat the patient's tissues, it is important for the doctor to maintain focused intention on the patient's channels while slowly removing his or her hands. If a break in contact with the mind's intention is made, the patient's tissues will return to their pretreatment state. Once the doctor has physically disconnected from the patient in this manner, Distance Qi Emission and Qi manipulation techniques can be applied.

It is believed that the treatment of diseases should be carried out primarily by Qi emission as the main approach, and secondarily through Qigong massage. By combining both external and internal tissue manipulation skills with energy



Figure 37.2. The Human Anatomy (Posterior)


Energetic Tissue Manipulation
Focus on a specific point
health maintenance
therapeutic point regulation
Focus on a specific area
local region treatment
general body treatment
Focus on a specific channel
health maintenance
therapeutic channel regulation

Figure 37.3. Energetic Tissue Manipulation Chart

extension techniques, the Qigong doctor greatly improves the quality of treatments. In the clinical setting, this type of energetic tissue manipulation is utilized before or after energy extension. This facilitates the relaxation of the patient's muscles and joints and the opening or closing of their points. It also aids in dredging the channels, guiding the flow of energy, and in regulating Yin and Yang energy.

TISSUE REGULATION THROUGH MEDICAL QIGONG MASSAGE

The external treatment of the patient's tissues encompasses a wide variety of body manipulation and alignment methods to provide a complete treatment program (Figure 37.3). Used for toning the organs, glands, nervous system, and joints, Qigong massage is applied to treat soft tissue injury. The following are the six treatment goals of Qigong Massage:

- To relax the tendons, activate the channels, promote circulation of Qi and Blood, and relieve pain,
- To disperse Blood stagnation,
- To relieve muscle spasms,
- To expand the tendon sheaths,
- To treat fascia in order to move stagnations and separate adhesions, and
- To correct dislocations.

The following is a list of the five predominant external tissue manipulation techniques used by Qigong doctors in China today.

THE FIVE ELEMENTAL QI MASSAGE THERAPY

Traditionally there are five different techniques for Medical Qigong massage therapy. These five techniques are very important for reestablishing the energetic vitality of the patient's body. Each of these techniques relates to a specific action and organ associated with one of the Five Elements. The objective of these techniques is to influence the muscles, nerve fibers, and deep-lying tissues of the body in order to aid metabolism and stimulate energy flow (Figure 37.4). The applications of these five methods of energy manipulation and their affect on the body's tissues are described as follows.

THE CIRCLE-TWISTING METHOD

This technique relates to the Spleen, which rules and affects the muscles, and is implemented as a quick drilling motion into the body's surface tissues, using the fingers, palms, knuckles, or heel of the palm.

When treating a patient's tissue area, a circle-twisting movement will stimulate the Qi and Blood within the channel points. This will generate a numbing and tingling sensation that will

Circle-Twisting Method	Spleen-Earth Element: affects the muscles, stimulates and improves Blood circulation.
Compression Release Method	Kidneys-Water Element: affects the bones, and regulates the Wei and Ying Qi.
Thrusting Method	Heart-Fire Element: affects the Blood, pulse, and regulates and activates the Qi.
Grasping and Shaking Method	Liver-Wood Element: affects the tendons, ligaments and muscles, promotes, clears, and activates Qi flow, and balances the Yin and Yang energy.
Tapping Method	Lungs-Metal Element: affects the Qi and skin.

Figure 37.4. The Five Elemental Qi Massage Methods

cause the channel points to induce the energy to counterattack the foreign invasion of Turbid Qi and disease. The circle-twisting action will also stimulate and improve Blood circulation and is divided into two modalities of treatment:

- To stimulate, massage the area in a clockwise, spiraling, circular motion from the outside to the center of the point. The purpose of this action is to gather energy from the surrounding areas of the patient's body and collect it into the center point the doctor is treating.
- To sedate, massage the area in a counterclockwise, spiraling circle from the center of the point outward. The purpose of this action is to disperse the energy from the area the doctor is treating. This Excess energy will later be either moved into other organs, or dredged outside the patient's body through an adjacent channel (Figure 37.5).

THE COMPRESSION RELEASE METHOD

This technique relates to the Kidneys, which rule and affect the bones, and is performed by the doctor extending his or her intention into the patient, softly pressing the body's surface tissues, using the whole palm, parts of the fingers, or elbows. The Compression Release method is commonly used to purge or drain the tissues of pathogenic Qi.

The Compression Release techniques are generally used to regulate the Ying and Wei Qi, which travel along the channels and collaterals. Deep pressure reaches the Ying Qi, while shallow pressure stimulates the Wei Qi. Once damage has occurred in the body, the damaged channel points and organ regions cause certain changes in the Wei Qi, Ying, Qi, and Blood areas of the body, resulting in numbness, aches, pain, swelling, etc. Both Circle-Twisting and Compression Release techniques can eliminate these symptoms and create a more stable energy flow.

The Compression Release Technique

Once the proper hand posture and area to be treated has been selected, the doctor guides Qi into his or her palm and fingers using Hot, Cold, vibrating, or spiraling energy. The doctor then initiates a rhythmic compression over the patient's tissues stimulating the patient's energetic field. This action has the function of relieving stagnation or congestion and can be used to dredge the



To sedate, purge, or disperse, move the energy in a counterclockwise direction.

To stimulate, tonify, or gather, move the energy in a clockwise direction.

Figure 37.5. Circle Twisting Method of Energy Therapy

channels and energetic points, as well as to relieve muscle spasms and physical pain.

The doctor must apply the correct amount of pressure for the patient's physical condition:

1. A slow Compression Release method is applied to any kind of hyperactive illness, nervous system disorder, mental disorder, or loss of Blood.
2. A medium Compression Release method is applied to illness for Spleen and Stomach disorders.
3. A fast Compression Release method is applied to hypoactive or Cold illnesses.

It is important to note that when applying the Compression Release method to tonify a specific area, the doctor should energetically press on the channel at a forty-five degree angle, slightly above where the channel flows into the injured area. This augments the flow of energy along the channel.

To disperse or drain a particular area, the doctor should apply slight pressure at an angle past where the channel flows into the injured area. This downward pressure will cause the energy to flow away from the injury. This application is used when treating Excess conditions.

THE THRUSTING METHOD

This technique relates to the Heart, which rules and affects the Blood and Blood pulses. It is utilized to gently push the tissues, extending the Qi and Blood along the patient's surface channels, using the thumb, ball of the thumb, or heel of the palm. The thrusting method can draw energy into a Deficient area or move Qi out of an Excess area.

The Thrusting Technique

Once the proper hand posture and area to be treated has been selected, the doctor guides Qi into his or her palm and fingers using Hot, Cold, vibrating, or spiraling energy. The doctor then rubs lightly or lightly touches above the patient's tissues while simultaneously emitting Qi.

The technique should be synchronized with the frequency of the patient's pulse and respiration. The Thrusting technique has the function of regulating and activating the patient's Qi, alleviating pain, and dredging the channels.

THE GRASPING AND SHAKING METHOD

This technique relates to the Liver, which rules and affects the tendons. It is administered by lightly vibrating the skin (gently at first, then slowly increasing the intensity). The Grasping and Shaking method sends a wave of vibration throughout the patient's body, and is used to increase Qi and Blood flow to the tissue area.

The Grasping and Shaking Technique

Once the proper hand posture and area to be treated has been selected, the doctor guides Qi into his or her palm and fingers using Hot, Cold, vibrating, or spiraling energy.

The doctor then lightly grasps and shakes the

15. As the pearls arrive at each kidney, the combined virtues of the pearls (especially the energy of courage and righteousness) enhance gentleness and the cycle begins again at the kidneys. Repeat the cycle two more times. As you circulate the pearl in the second cycle, you will begin to notice that as the pearl arrives at each organ, the virtues will grow by themselves. Little by little, the energy will blend more evenly.
16. For the third cycle, bring the pearl from collection point to collection point without going into the organ first. With your attention on the collection point, the energy will flow into the organ without conscious effort, and will join with the virtue energy to flow back toward the collection point. In this way the virtue energies are enhanced and increased each time you bring the pearl to a collection point. If you wish you can practice the third round of the Creation Cycle three more times simply by bringing the pearl to the collection points. Each time you blend the energy, you increase it.
17. Your energy now begins to have the quality of fine soup, with the proper combination of ingredients. Be aware of the quality of this energy. It is very special. Fuse all good virtues energies into compassion energy. Creating a pearl of compassion energy requires a tremendous amount of purified energy. Compassion energy is not just love or kindness, gentleness or openness, but is a combination of all the good virtues' energies, blended in proportion to become compassion energy. When you fuse the proportional blend of good virtue energy into a pearl of compassion energy, you will feel more centered. The energy of this pearl feels very different from the pearl you first formed. Move the compassion energy through the microcosmic orbit.
18. When you feel the pearl of compassion energy strongly, move it down to the perineum. Using your mind and senses, begin to move all of the compassion energy through the microcosmic orbit, letting its bright pearl shine as it travels along. Feel the different quality of this energy. Be aware of the loving, comfortable, very beautiful way the organs feel as the energy runs through and spreads into them, filling them with life-force energy. If you feel tired at any time, you can temporarily rest the pearl at your navel and practice the spinal cord breathing technique described in the Chapter preceding this meditation. Return your concentration to the pearl to form it again and return it

energetic field within the patient's tissues, while extending energy. The Grasping and Shaking technique is used for directing Qi to flow with or against the natural currents in the body's channels. It promotes, clears, and activates the channels and flow of Qi, relaxes the muscles and tendons, and balances the Yin and Yang energy.

THE TAPPING METHOD

This technique relates to the Lungs, which rule and affect the Qi and skin. This technique is administered by lightly and rhythmically tapping the patient's skin (with varying degrees of force), using the fingers, palms or fists (Figure 37.6). The Tapping method sends a pulsating ripple throughout the patient's tissues and is used to disperse stagnation from a point, channel, or organ.



Figure 37.6. In the Massage Tapping Method, the Qigong doctor will extend his or her intention deep into the patient's tissues in order to stimulate the channel point.

YIN AND YANG ENERGETIC POINT MANIPULATION

Before treating patients with Five Elemental Regulation therapy, the Qigong doctor should be aware of the principals of Yin and Yang energetic polarity involved within the Energetic Point Manipulation. This method of treatment is used to regulate the patient's Wei Qi, Ying Qi, and Qi and Blood systems (as a whole), in order to form a governed systemic balance. In the Energetic Point Manipulation methods, the treating techniques are directly based on Yin and Yang theory.

THE YIN THEORY OF QI MANIPULATION

This technique is expressed as a passive, quiet, or motionless action (more energy and less physical movement). The energetically passive Yin movements are used to push, fill, or tonify the patient's Righteous Qi, located within the patient's tissues. It is used for treating external tissue conditions and for internal organ conditions.

- If the external tissue area is in an inactive or Yin state, apply a Yin technique. Treat a Cold area with soft, passive manipulations, while extending the mind superficially onto the patient's surface tissues to fill or tonify anti-pathogenic factors, and to revitalize the Deficient area.
- If the internal organ area is either in an active or Yang (Hot or hard) state, the doctor must apply a Yin, passive, or slow action technique, while extending his mind deep into the patient's tissues and organs.

THE YANG THEORY OF QI MANIPULATION

This technique is expressed as an active technique, in motion. The active energy of the Yang movements are generally used to pull or purge pathogenic factors. It is used for treating external tissue conditions and for internal organ conditions.

- If the external tissue area is in an active or Yang state, apply a Yang technique (treating an External Hot or hard area with fast dredging manipulations) while extending the mind superficially onto the patient's surface tissues. This is done to pull or purge pathogenic factors, or break up the stagnation.
- If the internal organ area is either in an inactive or Yin (Cold or flaccid) state, the doctor must apply a Yang, quick, or active technique, while extending his or her mind deep into the patient's tissues and organs.

This combination of movement (Yang) and non-movement (Yin) is embodied in both the Circle-Twisting and Compression Release Methods of the Five Elemental Regulation Techniques.

APPLICATION FOR YIN AND YANG TECHNIQUES

The following text gives examples of specific Yin or Yang hand techniques, and when to apply them:

1. The Qigong doctor uses Yin hand techniques for tonifying, filling and pushing Qi and

Blood through the patient's organs, tissues, and channels. The Yin hand actions are demonstrated through slow or inactive hand movements.

2. The Qigong doctor uses Yang hand techniques for sedating, purging, and pulling Qi and Blood. The Yang hand actions are demonstrated through fast or active hand movements.

YIN AND YANG TREATING METHODS

The following text gives examples of specific Yin or Yang hand treatment methods, and when to apply them:

1. When a patient's tissues are in an Excess Yang state (Hard or Hot), the Qigong doctor sedates the area with counterclockwise rotations, leading the Excess energy from inside the tissue area out of the body.
2. When a patient's tissues are in a Deficient Yin state (Flaccid or Cold), the Qigong doctor tonifies the area with a clockwise rotation, to bring energy into the Deficient tissue area.

TREATING THE TISSUE AREA OR ENERGETIC POINT

In treating the patient's surface tissue area or specific energetic points, some Qigong schools teach that with a male patient, one should begin with points on the left side, then on the right side; whereas for female patients, one begins working on the points on the right side of the body, then on the left.

DEEP AND SHALLOW PRESSURE

Energy compression (deep or shallow) is controlled by the doctor's release. A deep compression relates to the Ying Qi, while a shallow compression pertains to the Wei Qi. This Compression Release technique affects the body's Blood and vital energy harmony. It seeks to balance the body's energy by preventing the Qi from flowing in the wrong direction. This technique also leads the pathogenic Qi outside the patient's body and is commonly called "The Dispersing Evil Qi Technique."

If stagnant energy remains in the center of a channel point, then the doctor must employ a Compression Release method. The compression causes the channel point to contract, leading it toward a calm, stable state. When the doctor releases the compression on the channel point, it expands and becomes stimulated into an active state.

THE GRADUAL ENERGETIC PENETRATION OF TISSUES

When treating a patient with External Tissue Regulation, there should always be a gradual penetration of energy permeating the patient's tissues. The Qigong doctor first sinks his or her focused intention onto the patient's surface tissues. The intention is then slowly sunk deeper, first into the patient's muscles and inner fascia, then into the bones or internal viscera.

At no time should pressure damage the tissues or compound pain. Treatment or pressure time at each area or energetic point should not be excessive. To establish the correct amount of pressure, determine the normal energetic pulsation in accordance with the Five Elemental Qi Massage methods, then decide if the technique is to be light, medium, or heavy.

ADDITIONAL GUIDELINES

The following are specific guidelines of Qigong massage treatment methods, and when to apply them:

1. Before beginning Qigong massage, the patient must be comfortable and relaxed. Otherwise the patient's body will not be receptive to the tissue stimulation or Qi emission.
2. When first touching the patient, the touch should be slow, as if the doctor is dipping his or her hand to test the water. The movements should have an established rhythm.
3. The doctor should never hold his or her arm, or the patient's arm, rigid or fully extended; the elbows should always be bent to some degree.
4. A symptom or damaged area occurring on one area or point at the extremity of a channel may be effectively treated by stimulating the point at the opposite end of the channel (see Magic Square, Chapter 31).
5. Points which are painful with light pressure

are in a state of Yang and need to be purged and sedated.

6. Points which are painful to deep pressure are in a state of Yin and need stimulation.
7. When an organ is functioning normally, it should receive weak, short stimuli that will increase the function, action, and energetic potential of the organ.
8. Cool skin over a point or channel indicates a Deficiency in that channel and should be tonified.
9. Hot skin indicates Excess Qi accumulation. It also indicates a current or pending illness in an organ, or area associated with that channel, and should be purged immediately.

SECTION IX

MEDICAL QIGONG EXERCISES AND PRESCRIPTIONS

CHAPTER 38

INTRODUCTION TO MEDICAL QIGONG PRESCRIPTIONS AND REGULATION EXERCISES

HISTORY OF MEDICAL QIGONG PRESCRIPTIONS

Many of the earliest known Medical Qigong prescriptions were derived from the movements of animals. Dating back to the second century B.C., the Qigong Classic (Dao Yin Tu) illustrates, in manuscripts written on silk, over 45 Qigong postures with descriptions of the movements as well as the names of the diseases which they treat. Over half of these illustrated postures are animal movements.

In the ancient Chinese text called the *Spring and Autumn Annals,* it is written, "Flowing water never stagnates, and the hinges of an active door never rusts. This is due to movement. The same principle applies to the body's Jing and Qi. If the body does not move, Jing does not flow. When Jing does not flow, Qi stagnates." The soft flowing movements in the Medical Qigong prescription exercises enhance and increase the flow of the body's Qi and Blood.

THE FUNCTION OF MEDICAL QIGONG PRESCRIPTIONS

When a disease develops, certain active points of the disease correspond to different organs, muscles and limbs of the body, and a pathological reflex is formed. Trigger and reflex points which are painful to touch are perfect examples of this phenomenon. The cerebral cortex can be inhibited in specific ways by regulating the Mind and entering a state of tranquility through Medical Qigong prescriptions, thus overriding the pathological reflex pattern, allowing the body time to heal.

Although acupuncture and herbs can, in addition to relieving pain, move Qi, Blood, and Phlegm (the roots of the disease), they fail to address the patient's life-style which is often a major contributing factor. Problems such as stagnation, Excess or Deficient conditions are often exacerbated by a patient's sedentary life style. A responsible doctor of Medical Qigong therapy addresses this particular element by prescribing physical therapy, exercise, and meditations as part of the overall treatment strategy.

Tonify	Deficient Conditions	Color Visualizations
Purge	Excess Conditions	Sound Resonations
Regulate	Yin and Yang	Qigong Massage

Figure 38.1. Medical Qigong Treatments

The standing rule for treatment in Medical Qigong prescriptions is to:

- Tonify the Deficient organs and organ systems with color visualization, by using the Mind's intention to focus on moving Qi into a Deficient organ, strengthening, thus illuminating its tissues;
- Purge the Excess organs and organ systems with sound resonation, by using the Mind's intention to focus on moving the Qi out from an Excess organ, resonating, and draining its tissues;
- Regulate the body's Yin and Yang organs and organ systems with Qigong massage, by using the Mind's intention to balance the energetic fields by moving the Qi up and down, right and left, and inside and outside of the tissues (Figure 38.1).

The therapeutic effects of Medical Qigong meditations and prescriptions are designed to move Qi and Blood stagnation, to tonify the internal organs and organ systems, and to enhance the autonomic nervous system. These prescriptions stimulate the patient's body, thereby gradually eliminating fatigue, as the normal body functions are restored. Another important aspect of the Medical Qigong meditations and prescriptions is the enhancement of the body's immune system functions.

MEDICAL QIGONG AND THE IMMUNE SYSTEM

The many health benefits of Medical Qigong include increased white blood cell production, stabilized blood pressure, and an improved immune function. The immune system, unlike the vascular circulation system, defies a clear anatomical description. It can only be understood through its functions and interrelationships with the mind and various other parts and systems of the body, such as the lymph nodes, Spleen, tonsils, appendix, Peyer's patches (in the ilium), thymus gland and the bone marrow.

The lymph nodes contain specialized compartments - some contain B cells (B stands for Blood), some T cells (T stands for Thymus), and some contain macrophages. The tonsils likewise contain B and T cells. The appendix and Peyer's patches are components of the lymphatic drainage system, and serve as locations where the B cells mature and where antibodies are produced by the B cells. The body's T cells mature in the thymus gland.

Both B and T cells begin their life in the Liver, when the fetus is only nine weeks old. They then migrate to the bone marrow where they form precursor cells. Afterwards, the T cells migrate to the thymus and the B cells remain in the bone marrow.

The immune system utilizes two major strategies for protecting the body from an infectious disease: The Humoral Immunity and the Cell Mediated Immunity.

- In humoral immunity the B cells play the primary role, and the T cells as well as other related cells play supporting roles.
- In cell mediated immunity the T cells play the main role, while B cells and other related cells play auxiliary roles.

Both T cells and B cells are called "Lymphocytes." They are two types of white blood cells that originate in the body's bone marrow and travel in the blood and lymph circulatory system (Figure 38.2). Both T cells and B cells are concentrated in the lymph nodes, which are found in clusters near groups of veins, and are heavily concentrated under the arm pits, in the adenoids, the Spleen and in the groin area.

When B cells encounter an antigen or foreign substance, they differentiate into plasma cells. These plasma cells secrete antibodies that fight and neutralize bacteria, or coat the antigen to mark it for destruction by other components of the immune system (such as the T cells).

T cells specialize in destroying cells infected by viruses, in attacking tumors, and in rejecting transplanted organs and tissues. The T cell, after leaving the bone marrow, travels to the thymus gland where it undergoes further development before returning to the lymph and blood circulatory systems. The T cells respond to an antigen by differentiating into several kinds of T cells, three of which are of primary importance: Killer T cells (also called cytotoxic T cells), Helper T cells and Suppressor T cells. Killer T cells bind to viral antigens displayed on the surface of infected cells and destroy them. Helper T cells bind to the antigens on the surface of a B cell that has already bound itself to the antigen. Each Helper T cell then releases Lymphokines (one well know class of lymphokines is interferon), that enhance the maturation of the B cells, or signal them to differentiate and multiply into plasma cells that secrete antibodies. The Suppressor T cells function to dampen the immune response and to signal the "all clear."

A third group of important immune cells are the phagocytes. These cells are the body's natural scavengers. They engulf antigens and destroy them. Those that specialize in cleaning up the debris are called macrophages. The macrophages can also signal B or T cells to the presence of foreign material.

Another important group of cells are called Null cells, among which the N.K. or "natural killer" cells are found. These cells are able to identify tumors and virally infected cells, and kill them without having any prior encounter with such an antigen.



Figure 38.2. The Body's Immune System

A final important group consists of Mast cells. They contain powerful chemicals: heparin - an anticoagulant, serotonin - a neurotransmitter, and histamine - a biochemical released in overabundant quantities in allergic reactions.

These white blood cells live in the blood and lymph fluid, and are commonly known as the leukocytes. There are two main varieties of white corpuscles: The Polymorphonuclear Leucocyte (Polymorphs) and Lymphocyte.

- Polymorphs are found in the bone marrow stem cells; they destroy invading bacteria and remove dead or damaged tissue.
- Lymphocytes are found in the lymph glands, Spleen and thymus gland and circulate in the blood along with the polymorphs. They are the smallest of the leucocytes, and designated the lymphocyte because it is identical with the lymphoid cell derived from the lymphatic glands.

Both the white blood cells called polymorphs and lymphocytes move into the body's surrounding tissues as a part of the immune function. The purpose of these cells is to work together to defend the body from invasion of pathogenic factors. Their function is to identify, ingest, destroy and eliminate disease-causing organisms, as well as to remove any and all dead, damaged, or irregular cells.

Immune cells are produced in the lymphoid tissue and red bone marrow, and are stored in the lymphatic organs and blood. In order to perform their function of protecting and cleaning, these cells must circulate throughout the entire body. The capillaries and lymphatic vessels carry the lymph fluid through the lymph nodes and the lymphatic organs of the thymus gland, spleen, and tonsils, where the lymph fluid is filtered, cleansed of impurities, and infused with new lymph cells.

In order for an external pathogen to affect the body, it must first pass through the protective layers of cells. Generally, the macrophages (specialized white blood cells) present within the tissues ingest the pathogens and dead tissues. This action of the macrophages is reinforced by the action and movement of the Wei Qi. When a pathogenic intruder invades the body, the macrophages are the first to attack the intruder. If the macrophages are not strong enough, more blood and fluid, which contain more immune cells, are brought to the area. The increased fluid engorges the tissue, and brings more cellular activity. The increased


The Body's Immune System
Congenital Immunity Established Through:
1. Antibodies passed from mother to fetus via the placenta
Acquired Immunity Established Through:
1. Antibodies passed to the infant during breast-feeding
2. Infection (contact with pathogen)
3. Injection of immune serum (gamma globulin)
4. Injection of vaccine (dead or attenuated pathogens)

Figure 38.3. Congenital and Acquired Immunity

blood and cellular metabolism increases the local temperature. The immune cells try to break down and ingest the pathogen, creating a process which continues until the disease is eliminated.

Once the battle is won, some of the Killer T cells and Helper T cells will remain circulating in the blood and lymph circulatory system as Memory cells that will be able to deal more efficiently with any future antigen of the same kind. Likewise, some of the mature B cells will also become Memory cells that hover around lymph nodes which they use as a base of operation.

Because Qigong movements generate heat and soften the body's connective tissues, this encourages the flushing of the intercellular fluid throughout the body's tissues and organs. When combined with Breathing, Mental, and Postural Qigong exercises, the entire body is affected. These energetic Qigong actions increase oxygenation of the blood and improve circulation, thereby enhancing lymphocyte production and strengthening the body's immune system.

CONGENITAL AND ACQUIRED IMMUNITY

The body has two ways of establishing or maintaining its immune functions: Congenital Immunity and Acquired Immunity (Figure 38.3).

- Congenital Immunity (Prenatal) is established during gestation, through antibodies that are passed from the mother to the fetus via the placenta.
- Acquired Immunity (Postnatal) is established in the following ways: immediately after birth during breast-feeding (through the colostrum-mother's first milk), through contracting an infection (contact with external pathogens), the injection of an immune serum (gamma globulin), and the injection of vaccines (dead or attenuated pathogens).

Due to the importance of establishing a strong immune system within the body's Prenatal Jing, Traditional Chinese Medicine strongly endorses fetal education, instruction on diet and nutrition, maintaining emotional well-being during pregnancy, and Qigong exercises specifically designed to enhance the child's Prenatal Essence, Energy, and Spirit.

OVERVIEW

One specific goal of Medical Qigong treatments, exercises and meditations is to activate and strengthen the immune function. Qigong therapy can be used to not only strengthen the metabolism of the organs and cells, but also increase cellular energy, thus making the immune system stronger.

In China, even though the lymphatic function itself was unknown and unnamed, its effects were


Medical Qigong Self-Regulation Therapy
1. The patient is taught to increase self-awareness.
2. The patient is taught to cleanse and purify his or her energetic field.
3. The patient is taught to strengthen and recharge his or her body.
4. The patient is taught to circulate the Qi internally and externally throughout the body's entire energetic structure.
5. The patient is taught to dissipate any Excess Qi from the body.

Figure 38.4. The Five Stages of Healing Transitions That Occur Through Self-Regulation Therapy

generally ascribed to the proper action of the Qi and Body Fluids. Therefore, elaborate methods for generating and circulating lymph were developed, and faithfully practiced through Qigong. Breath, movement and postural modification as well as meditations have specific effects on the circulation of the lymph and therefore enhance the overall function of the lymphatic system.

THE FIVE STAGES OF HEALING

When practicing Medical Qigong exercises and meditations, there are five basic stages of healing transitions which occur through self-regulation therapy (Figure 38.4).

1. The patient is taught to increase his or her awareness of the body (physically, mentally, and emotionally) and its current condition.
2. The patient is taught to cleanse and purify the body's energetic fields to rid it of Qi stagnations and toxic pathogenic factors.
3. The patient is taught to strengthen and recharge his or her body to replenish the Qi.
4. The patient is taught to circulate the Qi internally and externally throughout the body's entire energetic structure, thus moving any stagnant Qi and strengthening the body.
5. The patient is taught to dissipate any Excess Qi from the body by way of self-massage (lightly brushing the skin to release stagnant Qi).

THE THREE CATEGORIES OF MEDICAL QIGONG PRESCRIPTIONS

The Medical Qigong prescriptions are divided into the same three categories (or goals) used in Medical Qigong therapy: tonification, purgation and regulation. These three goals are achieved through both Dynamic and Quiescent Qigong exercises, meditations, prayers, and mantras. These prescriptions enable the patient to reinforce the treatments performed by the Qigong doctor, and prevent the patient's energy from reverting back to old destructive patterns.

The Qigong doctor selects the proper Qigong prescription to fit the patient's illness (to Tonify, Purge, or to Regulate) and formulates a rational program that suits the patient's case. The patient should never be allowed to practice at random, otherwise pathological changes or Qi deviations may occur.

The following are but a few examples of Qigong prescriptions, which are interchangeable, to the microcosmic orbit for circulation. Move the pearl through the microcosmic orbit 9-18 times.



Fig. 6.47 *Circulate the pearl in the Microcosmic Orbit.*

Shoot the Pearl above the Crown.

1. As the pearl runs through the Microcosmic Orbit, begin to activate the Cranial Pump. Press your tongue to the palate, clench your teeth, pull back your chin and roll your eyes up toward the crown. Feel the pulsing in your heart and in your head at the crown. You can touch your pulse at the wrist to help your awareness of the pulse both at the wrist and the crown. Your mind also helps to activate the Cranial Pump.



Fig. 6.48 *Pull the eyes into their sockets.*
Roll the eyes up and look up to the crown.

as there are certain variations of purging exercises that can be modified and used for tonification and visa versa.

QIGONG PURGING EXERCISES

Qigong Purging exercises are practiced by the patient to detoxify pathogenic Qi. Some examples are already presented in this textbook are:

- Channel Purging exercise (Chapter 15)
- Cleansing the Body meditation (Chapter 12)
- Dry Crying meditation (Chapter 53)
- Energy Melting meditation (Chapter 18)
- Internal Organ Sound Therapy exercises (Chapter 4 and Chapter 40)
- Old Man and Tide Pool meditation (Chapter 40)
- Pulling Out The Pain meditation (Chapter 28)
- Releasing Emotional Blockages and Energetic Armoring meditation (Chapter 18)
- Sun and Moon meditation (Chapter 18)
- Tumor and Cancer Tone Resonating exercises (see Chapter 40)

QIGONG TONIFICATION EXERCISES

Qigong Tonification exercises are practiced by the patient to strengthen and stabilize the internal organs and organ systems. Some examples are already presented in this textbook are:

- Channel Point meditations (Chapter 36)
- Color Visualization meditations (Chapter 4)
- Cultivating Yuan Qi meditation (Chapter 50)
- Daoist Five Yin and Yang Organ exercises (Chapter 42)
- External Qi Cultivation meditations (Chapter 41)
- Gaining Wisdom meditation (Chapter 49)
- Gathering Energy from the Five Planets meditations (Chapter 11)
- Gathering Moon Cream meditation (Chapter 11)
- Gathering Sun's Essence meditation (Chapter 11)
- Gathering Qi from Mountains, Valleys, and Deserts (Chapter 12)
- Gathering Qi from The Four Directions (Chapter 12)
- Gathering Qi from Trees, Bushes, and Flowers (Chapter 12)
- Improving the Intellectual Facilities meditation (Chapter 49)
- Internal Qi Cultivation meditations (Chapter 41)
- Nei Guan - Inner Viewing Meditation (Chapter 25)
- One Through Ten meditation (Chapter 26)
- Opening and Closing the Three Dantians exercise (Chapter 41)
- Organ Massage exercises (Chapter 39)
- Qigong Walking exercises (Chapter 15)
- Seeing Auras meditation (Chapter 25)
- Soul Retrieval meditations (Chapter 19)
- Tian Wu Zang meditation (Chapter 11)

QIGONG REGULATION EXERCISES

Qigong Regulation exercises are practiced by the patient to balance their Yin and Yang, as well as their internal organ energy. Regulation exercises usually follow Tonification or Purgation exercises, because the goal is to reestablish balance. Some examples already presented in this textbook are:

- Exchange of Fire and Water meditation (Chapter 18)
- Gathering Qi in the Upper and Lower Dantians (Chapter 41)
- Microcosmic Orbit meditations Chapter 41)
- Opening and Closing the Three Burners (Chapter 41)
- Opening and Closing the Three Dantians exercise (Chapter 15)
- Pulling Down the Heavens (Chapter 41)
- Qigong Self-Healing massage (Chapter 41)
- Taiji Ruler exercises (Chapter 18)
- Wu Zang meditation (Chapter 28)

CHOOSING PRESCRIPTIONS ACCORDING TO THE PATIENT'S QI CIRCULATION

When prescribing Medical Qigong prescriptions, the priority is to get the patient to move and circulate the Qi and Blood superficially and deeply within the body. According to Chinese physician, Professor Yan De-xin, the motion and quality of Blood flow in young and middle-aged patients is different from that in the elderly, which should be kept in mind when prescribing exercises.

- When prescribing Medical Qigong therapy for young patients, use mostly Dynamic and some Quiescent Qigong regulations.
- When prescribing Medical Qigong exercises for both adolescent and middle aged patients, it is important to increase Yin Qi cultivation while maintaining and storing the patient's Yang Qi.
- When prescribing Medical Qigong for senior citizens, focus is placed on Quiescent Qigong, with a minor emphasis on Dynamic breathing exercises, depending on their age and constitution.
- When prescribing Medical Qigong therapy for patients with very weak health or constitution, the doctor should prescribe mostly Quiescent Qigong regulations to start with.
- When prescribing Medical Qigong therapy for senior citizens with a strong constitution and health, the doctor can prescribe Qigong regulations that increase Yin Qi cultivation while maintaining and storing the patient's Yang Qi.

MEDICAL QIGONG PRESCRIPTIONS FOR GENERAL SYNDROMES

The following are some examples of the proper application of Dynamic and Quiescent Qigong prescriptions as presented by Dr. He Si Hai of the Zhe Jiang Qigong Hospital in China:

1. For Excess and Heat Syndromes it is recommended to prescribe static (quiescent) Medical Qigong exercises. After the gradual decline of the patient's fever or disease, the Qigong exercises are gradually increased in numbers and duration, and the purging training method is added (provided they have not excessively consumed their constitution).
2. For Deficiency and Cold Syndromes it is recommended to prescribe Dynamic Medical Qigong exercises. Gradually increase the exercises to include methods of lifting the limbs. If however, the pathological state is more serious, then static exercises are prescribed first.
3. For Cerebral Hemorrhage, have the patient practice static exercises such as the Hibernation Breathing exercise (quiescent lying posture, see Chapter 15) while combining it with the Yongquan (Kd-1) purging exercise (once the patient has regained consciousness). Dynamic Medical Qigong exercises that use methods of passing, circulating, or distributing Qi through the head are forbidden.
4. For Cerebral Embolism combine the training methods to include exercises that accelerate Blood flow and strengthen the function of the limbs as well as quiescent tonifying methods.
5. For Malignant Tumors (in a state of non-diffusional transference, in situ), combine an effective Dynamic exercise with a Quiescent exercise. Some examples of non-aggressive tumors / cancers are considered energetically warm and in a non-aggressive state of transition are:

- Prostate cancer
- Cervical dysplasia
- Endometrial adenocarcinoma (uterine)
- Basal cell skin cancer
- Squamous cell skin cancer

6. For Malignant Tumors (in a state of diffusion, i.e., metastatic) prescribe Quiescent Medical Qigong exercises which are similar to the Hibernation Breathing exercise, in combination with strengthening exercises for patients with chronic diseases. Dynamic Medical Qigong exercises which accelerate the Blood flow are forbidden. Some examples of tumors that are considered energetically Hot and in an aggressive state of transition are:

- Pancreatic cancer
- Leukemia
- Cervical cancer
- Clear cell carcinoma (uterine)
- Melanoma (skin cancer)

NUMBER OF BREATHS REQUIRED IN MEDICAL QIGONG PRESCRIPTIONS

Each Medical Qigong treatment will generally last up to three days. The Medical Qigong prescriptions that the doctors gives their patients will extend the treatment's effects indefinitely, providing the patients do all their homework.

The number of breaths required to Regulate the patient's Yin and Yang energy in a Medical Qigong prescription is often calculated in respiratory cycles, and on the basis of the number of the Yin and Yang aspects of diseases. This is often determined by the Yin and Yang energy numbers. Yang energy is represented by all the odd numbers (1, 3, 5, 7, 9, etc.). Yin energy is represented by all the even numbers (2, 4, 6, 8, etc.). These numbers are related to the Five Elements (Figure 38.5). For example: 6 is the number of the Kidneys, 7 the Heart, 8 the Liver, 9 the Lungs, and 10 the Spleen (Figure 38.6). The cycles of Yin and Yang numbers can be implemented through the utilization of the Magic Square (see Chapter 31).

The Yang number is used to calculate the respiratory cycles for Tonification and Purgation of the Yang channels; likewise, the Yin number is used for the Yin channels. This calculation should only be used as a general reference guide in treatment. Clinically, respiratory cycles should be determined based on the location and nature of the disease (if it is Yin or Yang, Exterior or Interior, Deficient or Excessive). The primary goal for using respiratory calculations is to ensure that sufficient Qi is administered when applying Medical Qigong treatments and therapeutic prescriptions. A disease due to a Deficiency of Yin, for example, should be treated with a tonification method for 18 or 64 respiratory cycles. To treat a Deficiency of Yang, a tonification method is used by the patient for 24 to 36 breaths.

	General Treatment	Moderate Treatment	Strong Treatment
Yin	6	18 or 36	64
Yang	9	27 or 49	81

Figure 38.5. Number of Yin and Yang Respirations

5 Yin Organs	Kidneys	Heart	Liver	Lungs	Spleen
Number of Respirations	6	7	8	9	10
Element	Water	Fire	Wood	Metal	Earth

Figure 38.6. Yin and Yang Five Element Respiration

CHAPTER 39
SPECIFIC ORGAN SELF-MASSAGE PRESCRIPTIONS

INTRODUCTION

The next few chapters of this book include some of China's most popular clinical therapies. It is the author's sincere desire to educate the reader as to the diversity, yet effectiveness of these prescriptions. It is important to remember that it is not necessarily the exercise or prescription's history that matters, what does matter is the initial goal of the prescription (whether to purge, tonify, or regulate) and the correct posture, breath, and mental focus.

This section begins with energy massage techniques, which are prescriptions that require the patient to regenerate his or her own body energy for self-healing, cultivation, and circulation. These exercises are designed to purge, tonify and regulate the Five Yin Organ System. They are not arranged in any particular order, and can be singled out by the doctor and given to patients for specific ailments. Each massage prescription is named after the organ it stimulates. For clinical therapy, perform these exercises three to five times a day.

HEART MASSAGE

The doctor can chose to give the patient either the One Through Four meditation (1-fun, 2-shoe, 3-tree, 4-core; from Chapter 26), or the Stacking the Bones meditation (described below) to prepare for the following meditations.

1. Begin in a Wuji posture to perform the Stacking of the Bones meditation. Imagine the energy in your body sinking and melting into the ground; the bones vertically stack, one by one, on top of each other. Each of the body's articulations stacks on top of the next section of bone, from the bottom of the feet, ankles, knees, etc., to the top of the head.

   The spine is kept straight but relaxed, the anal sphincter is closed, the tongue is touching the top of the upper palate, the Mingmen is slightly pressing towards the back, and the body is completely relaxed.



Figure 39.1. The patient uses the mind's intent to regulate the Qi of the Heart.

2. Perform the Heart Regulation. When prescribing these exercises for male patients, have them place the left hand over the Heart with the right hand on top of the left hand (for women, the hand positions are opposite, and the beginning placement of the hands is below the left breast). Massage in twelve circular rotations clockwise to the left, then twelve rotations counterclockwise. The hand can either lightly touch the skin (using Qi massage), or be slightly off the skin, up to several inches away from the patient's body (using Qi Distance therapy), depending on the degree of energetic sensitivity and projection skill (Figure 39.1). Focus the mind's intention on the Heart organ, allowing the energy within the Heart area to flow and circulate with the movement of the hands.



Figure 39.2. Pulling Down the Heavens allows the patient to sink the Qi, returning the excess energy back into the Lower Dantian.



Figure 39.3. Exhaling and Opening the Lower Dantian allows the body to expel the Evil Qi from the internal organs. Expand the abdomen.

The purpose of the rotating action of the Heart's Qi is for promoting Blood circulation and dispersing Blood Stasis, while dredging the channels and collaterals.

3. Perform the Point Respiration. This technique focuses breathing and imagination into the channel points for the specific treatment area. For this particular exercise, the patient should leave the hands over the Heart, while concentrating the focused intention and breath deep into the tissue of the organ. The patient should then exhale while lightly squeezing and pressing the area of the Heart, and imagining divine healing light radiating outward from the tissues. While inhaling, the patient should lift the hands away from the body and imagine divine healing light flowing into the Heart organ area. This action is similar to that of a bellows. This exercise should be performed twelve times, then lead the Qi down into the Lower Dantian.
4. Perform the Pulling Down the Heavens method. Inhale, pause, then exhale while slowly bringing the arms down the center line of the torso, while quietly drawing the energy back down into the Lower Dantian. When lowering the arms, imagine the energy of the Heart like water, melting and flowing down the torso.

   Pause for a breath at the Lower Dantian, rooting the energy. Then slowly raise the hands above the head, while inhaling. Exhale slowly and imagine the energy in the arms and head melting down the body, beginning at the top of the head and tips of the fingers, flowing down and into the Lower Dantian.

   This action is important, because if the Qi is not brought back into the Lower Dantian after each exercise, the energy will be easily dispersed (Figure 39.2).
5. Perform the Opening and Closing of the Lower Dantian. Finally exhale and imagine the Evil Qi being expelled through the mouth. As you exhale, separate both of the hands away from the abdomen (as you contract the abdomen). This is called the Opening (Figure 39.3).

   After completing the Opening of the Lower



Figure 39.4. Inhaling and Closing the Lower Dantian allows the body to seal itself from outside pathogenic factors. Contract the abdomen.

Dantian, inhale through the nose while bringing both hands back to face the Lower Dantian (as you expand the abdomen). This action is called the Closing. When Closing, imagine sealing the body in a protective energetic field, so that the pathogenic factors cannot get inside (Figure 39.4). Perform the Opening and Closing method three times.

Note: The techniques 1 through 5 are one complete set. Perform a total of three sets. Three sets are necessary because the body will naturally progress through three stages. The first time the body is introduced to a new pattern it will shock the system. The second time the body begins to understand the pattern. The third and final time the body recognizes and accepts the changes the patient is attempting to reprogram.

LIVER MASSAGE

1. Begin from a Wuji posture and perform either the One Through Four or Stacking the Bones method as described in Heart Massage (1).



Figure 39.5. The patient will focus their mind's intent on the Liver area while massaging, allowing their energy to circulate into the organ's tissues.

2. Perform the Liver Regulation. Place the left hand on the Liver with the right hand on top (opposite for women). Massage in twelve circular rotations to the left in a clockwise direction, then twelve rotations in the opposite direction. When massaging, focus the mind on the Liver. Inhale and imagine divine healing light coming down from the Heavens and filling the Liver. Exhale and purge the Liver of Turbid Qi through the mouth.

   The purpose of this exercise is to smooth and regulate the activities of the vital energy flowing inside the Liver, encouraging the hyperactive and Rebellious Liver Qi to flow downward (Figure 39.5).
3. Perform Point Respiration with both hands still over the Liver, for twelve breaths, as described in the Heart Massage (3).
4. Perform Pulling Down the Heavens by leading Qi down into the Lower Dantian, as described in the Heart Massage (4).
5. End with Opening and Closing method as described in the Heart Massage (5).



Figure 39.6. The patient focuses the mind's intent on the Lung area while massaging, allowing the energy to circulate into the organ's tissues.

Note: The techniques 1 through 5 form one complete set. Perform two more sets for a total of three to complete the prescription.

LUNG MASSAGE

1. Begin from a Wuji Posture and perform either the One Through Four or Stacking the Bones method as described in the Heart Massage (1).
2. Perform the Lung Regulation. Place both palms on the Lungs (specifically on an injured or diseased region, if known). Massage in twelve circular rotations from the bottom, up the center to the top and then to the outside of the chest. Then massage twelve rotations in the opposite direction, from the top, down the center and to the outside. When massaging, concentrate on the Lung region. Inhale and imagine divine healing light coming down from the Heavens and filling the Lungs. Exhale and purge the Lungs of Turbid Qi.

   The purpose of this exercise is to bring Blood and Qi into the Lung area, clean and purify the inhaled breath and support the Lungs' Qi flowing downward (Figure 39.6). TB patients with pulmonary holes should concentrate on abundantly filling and expanding the vital energy in the Lungs while visualizing the Qi activating the body's cells to close the holes. If the patient is unable to visualize this, or the reaction is too uncomfortable, have the patient mentally pull the Qi downward.
3. Perform the Point Respiration with both hands still over the Lungs, for twelve breaths, as described in the Heart Massage (3).
4. Perform Pulling Down the Heavens method, leading the Qi back down into the Lower Dantian as described in the Heart Massage (4).
5. End with Opening and Closing method as described in the Heart Massage (5).

Note: The techniques 1 through 5 are one complete set. Perform two more sets for a total of three to complete the prescription.

SPLEEN & STOMACH MASSAGE

SPLEEN MASSAGE

1. Begin from a Wuji Posture and perform either the One Through Four or Stacking the Bones method as described in the Heart Massage (1).
2. Perform the Spleen Regulation. Place the left hand on the Spleen with the right hand on top (opposite for women). Massage in twelve circular rotations to the left in a clockwise direction, then twelve rotations in the opposite direction. When massaging, concentrate the mind on the energy within the Spleen area, imagining the Spleen Qi movement flowing with the movements of the hands (Figure 39.7). Inhale and imagine divine healing light coming down from the Heavens and filling the Spleen. Exhale and imagine the Spleen absorbing the divine Qi.

   The purpose of this exercise is to strengthen and increase the Spleen's function of transporting and converting Qi. This is an excellent massage for patients with splenomegaly (enlargement of the spleen) and dyspepsia (painful digestion).
3. Perform the Point Respiration with both hands still over the Spleen, for twelve breaths,



Figure 39.7. The patient focuses the mind's intent on the Spleen area while massaging, allowing the energy to circulate into the organ's tissues.



Figure 39.8. The patient will focus their mind's intent on the Stomach area while massaging, allowing their energy to circulate into the organ's tissues.

as described in the Heart Massage (3). Then move both hands to the Stomach area.

STOMACH MASSAGE

4. Perform the Stomach Regulation. Place the left hand on the Zhongwan CV-12 point at the middle of the Stomach with the right hand on top (opposite for women). Massage in twelve circular rotations to the left in a clockwise direction, then twelve rotations in the opposite direction. When massaging, concentrate on warming the Stomach area (Figure 39.8). Inhale and imagine divine healing light coming down from the Heavens and filling the Stomach. Exhale and purge the Stomach of Turbid Qi.

   This is an excellent massage for patients with thoracic depression, abdominal distention, gastritis, and gastric ulcers.
5. Perform the Point Respiration with both hands still over the Stomach, for twelve breaths, as described in the Heart Massage (3).
6. Perform the Pulling Down the Heavens method to draw the Qi down into the Lower Dantian, as described in the Heart Massage (4).
7. End with the Opening and Closing method as described in the Heart Massage (5).

Note: The techniques 1 through 7 are one complete set. Perform two more sets for a total of three to complete the prescription.

KIDNEY MASSAGE

This exercise is excellent for tonifying the Kidneys, as well as healing impotence, premature ejaculation, lumbago, lower back problems, and pelvic inflammatory disease (for PID use reverse breathing with static Qigong training).

This is an extremely important exercise for patients and for Qigong doctors to practice; it enables them to increase their Qi projection when treating patients.

1. Begin from a Wuji Posture and perform either the One Through Four or Stacking the Bones method as described in the Heart Massage (1).
2. Perform the Kidney Regulation. Close the eyes and place both hands on the back (waist



Figure 39.9. The patient will focus the mind's intent on the Kidney area while massaging, allowing the energy to circulate into and warm the organ's tissues.



Figure 39.10. The patient will focus the mind's intent on the bottom of the foot while massaging, allowing the energy to flow through the Kidney Channel into the Lower Dantian.

level), middle fingers touching the Shen Shu Bl-23 points. Focus on the Kidneys. Begin massaging twenty-four times inward, then twenty-four times outward, until the area becomes warm (Figure 39.9).

3. Perform the Point Respiration with both hands still over the Shen Shu Bl-23 points for thirty-six breaths. Exhale as you press the palms into the Kidneys, inhale as you raise the palms from the back. While inhaling, imagine divine healing light coming down from the Heavens and filling the Kidneys completely. While exhaling, imagine the Kidneys absorbing the divine Qi.
4. Perform the Pulling Down the Heavens method, drawing Qi into the Lower Dantian as described in the Heart Massage (4).
5. Perform the Opening and Closing method as described in the Heart Massage (5).

Note: The techniques 1 through 5 are one complete set. Perform two more sets for a total of three to complete the prescription, then proceed to the Closure.

6. Perform the Closure. After completing three sets of the Kidney exercise, place the right hand on the navel and the left hand on the Mingmen. Focus on gathering Heat and Qi in the Lower Dantian. Next, place the right foot on the left knee (opposite for women). With the right hand still on the Lower Dantian, place the left hand at the bottom of the right foot and gently massage the Yongquan Kd-1 point. Massage this area 100 times in a clockwise direction, then 100 times counterclockwise. When massaging the Kd-1 point, work slowly, focusing the mind's intention through the center of the palm into the center of the foot, imagining the Qi flowing up the leg into the Lower Dantian (Figure 39.10).

Note: Some Medical Qigong Clinics in China perform this same exercise while slapping the bottom of the feet (instead of using circular massage). They begin this treatment with 100 strikes on each foot for the first day, increasing an additional 100 strikes each consecutive day (not exceeding 300 strikes) until the desired result is achieved.

7. Perform the Point Respiration for twelve breaths, with the right hand still on the Lower Dantian and the left hand still on the bottom of the right foot, as described in the Heart Massage (3).
8. Switch feet, placing the left hand on the Lower Dantian while the right hand gently massages the Kd-1 at the bottom of the left foot, 100 times clockwise then 100 times counterclockwise.
9. Perform the Point Respiration for twelve breaths, with the left hand still on the Lower Dantian and the right hand still on the bottom of the left foot.
10. End with the Opening and Closing method as described in the Heart Massage (5).

Note: Do not use this ending method (5 and 10) for patients who suffer from insomnia, as it will have an awakening effect as it invigorates the vital energy. When performed at bedtime it can be used for treating insomnia by following the simple prescription below.

TREATMENT FOR INSOMNIA

This is a very famous prescription for insomnia. I have used it in my clinical practise for many years and have found it to be extremely effective. If the insomnia is due to a Deficiency of Kidneys' Yin, or the patient is restless during the night due to the Liver's Heat rising and causing the patient's mind to wander, this prescription will help. After clinically treating patients for insomnia, the Qigong doctor can prescribe the following exercise to be performed by the patient.

This exercise is to be practiced just before the patient is going to sleep. Begin by sitting at the edge of the bed, repeating the previous Kidney exercises 2, 3, and 6.

1. Perform the Kidney Regulation. Close the eyes and place both hands on the back (waist level), middle fingers touching the Shen Shu Bl-23 points. Focus on the Kidneys. Begin massaging twenty-four times inward, then twenty-four times outward, until the area becomes warm (Figure 39.9).
2 Perform the Point Respiration with both hands still over the Shen Shu Bl-23 points for thirty-six breaths. Exhale as you press the palms into the Kidneys, inhale as you raise the palms from the back. While inhaling, imagine divine healing light coming down from the Heavens and filling the Kidneys completely. While exhaling, imagine the Kidneys absorbing the divine Qi.
3. Perform the Closure. After completing three sets of the Kidney exercise, place the right hand on the navel and the left hand on the Mingmen. Focus on gathering Heat and Qi in the Lower Dantian. Next, place the right foot on the left knee (opposite for women). With the right hand still on the Lower Dantian, place the left hand at the bottom of the right foot and gently massage the Yongquan Kd-1 point. Massage this area 100 times in a clockwise direction, then 100 times counterclockwise. When massaging the Kd-1 point, work slowly, focusing the mind's intention from the Lower Dantian through the leg into the center of the foot, imagining the Qi flowing down the leg into the bottom of the foot (Figure 39.10). As the mind begins to relax, close the eyes and fall sleep. If you become fatigued, do not complete the exercise.

An explanation for the reason for this exercises success is as follows:

1. The Kidney exercise 1 and 2 will root the body's Blood, Heat, and Heart Qi back into the Kidneys and Lower Dantian, where they will become stabilized.
2. The Kidney exercise 3 will draw the body's Heat, Blood, and the Heart Qi away from the torso and Lower Dantian into the extremities of the feet, quieting the mind and causing sleep.

2. Inhale, be aware of and squeeze the anus and then exhale quickly to push the pearl up through the crown.
3. You might be aware of a light, beam or frequency shooting out of your crown. This is the lead light first introduced in Fusion of the Five Elements. Sometimes it is called an indicator light because it will indicate how high up your pearl will be able to go. Just as a light is used to guide helicopters to their landing point, so will you use the lead light to guide the pearl back to the crown point.
4. Direct all of your senses to push the pearl up to the area six inches to two feet (15-60 centimeters) above your head. Move the pearl up and down, left and right.
5. Feel the Universal Force, the forces of the North Star and Big Dipper above your head, and the Cosmic Particle Force in front of you as they shine down to your pearl. Feel your pearl start to absorb this energy and then feel it expand.
6. Bring your awareness to your feet. Feel the energy supplied throughout your body through your feet. This is the Earth Energy. The pearl continues to expand with all the energy coming to it from outside the physical body.
7. When you are ready, activate the Cranial Pump again. Press your tongue up, clench your teeth, pull back your chin, pull up your anus and look up to the crown. Feel the beating in your heart and the pulse at your crown.
8. Activate the lead light, and let it shine up from your crown. It may feel like a frequency going out of the crown. Draw the pearl down to the lead light. Inhale and draw the pearl down.
9. Circulate the pearl in the Microcosmic Orbit. Then bring it down to the navel and to the cauldron at the body's center. Collect the energy at the cauldron.
10. As you collect the energy and relax the mind, the pearl may disintegrate. Sometimes when you release the pearl, it vanishes. It is returning its energies, now enhanced by all virtue energies and the outside forces, to the organs and glands. They become stronger and healthier each time you practice. Each time you gather the energy and form the pearl again, the pearl will be stronger.

CHAPTER 40
HEALING SOUND THERAPY AND PRESCRIPTIONS

INTRODUCTION AND HISTORY

As early as the Qin Dynasty (221-207 BC) healing sounds have been recorded in China. For thousands of years, Qigong masters have studied occurrences in nature and in the physical body to develop a holistic approach to health and longevity. One of the many discoveries made is that all humans produce similar sound patterns in certain situations. For instance, after a tense situation many people utter a sigh of relief. This sigh is the body's way of releasing emotional stress. Specific situations will release different emotional sounds, because emotions are stored as tone resonances in the different chambers of the Five Yin Organs.

During the Sui Dynasty (590-618 AD), ancient Qigong Master Zhi Zhuan pointed out that there are six ways of expelling toxic energy from the internal organs, using the six different sounds formula. The silently spoken six sounds are coordinated with the breathing and the movements of the body's extremities to purge and cleanse the organ cavities and particular channels of stagnant Qi. These exercises are excellent for treating muscular injuries and for the Yin and Yang organs. The impure Qi produced by external pathogenic factors (from food, air, and drink) and internal pathogenic factors (toxic emotions and negative mental attitudes) will be expelled directly from each organ.

The healing sound techniques can either be used by the patient as a form of static Medical Qigong prescription (for purgation), or projected into the patient by the doctor as a clinical form of energetic stimulation (for tonification or purgation). The six words are: Xu (Shu), Ke (Haa), Hu (Who), Si (Sss), Chui (Chree), and Xi (Shee). These sounds are also used in chanting (in spiritual Qigong). Ancient documents state that these six sounds denote the Five Yin Organs as well as the five seasons.

It is important to note that there are several healing sound systems used by different Medical Qigong schools and other cultures. These sound systems all affect the body's sympathetic and parasympathetic nerves to some degree. The main emphasis, when performing any healing sound, should be placed on the connection of the mind, breath, and imagination to the area or internal organ focused on by the patient. This will reduce the potential for causing Qi deviations. The patient must have an internal image and actually hear and feel the resonating sound inside the body. It is also important that the patient feel enveloped in the sound, vibration, energy, and light of the therapeutic tone.

SOUND VOLUME RESONATION

The pronunciations of the sounds must be correct. The resonant effects of the sounds must be brought into full play to be successfully transmitted to the diseased areas of the internal organs. Therefore, it is extremely important that the patient focus the mind and intention on the area being treated. There are three volume resonations commonly used in Medical Qigong sound therapy: soft, moderate, and loud.

1. Soft volume is spiritual in its energetic nature and is related to the projection of Shen. A soft volume is generally used when beginning sound therapy treatments. With soft volume pronunciation, the patient can easily feel where the sound waves reach and acquire resonant effect, but the amplitude of the sound wave is not wide enough to produce the desired healing effects, and its vibrational force is very weak.
2. A moderate volume of sound is emotional and mental in its energetic nature and is related to the projection of Qi. A moderate volume is

considered the standard for all healing sound treatments. Moderate volume is decided by the individual's own voice. It should be limited to the range in which the patient's voice does not strain and in which the voice can be raised or lowered effortlessly.

3. Loud Volume is related to the projection of Jing. A loud volume is used to shock the patient into feeling the diseased tissue area. This is due to the fact that loud volume is more tangible (or physical) in its energetic nature. With loud volume pronunciation, the patient can easily feel the body's internal organs and tissues vibrate; however, this sound is only used to reintroduce a desensitized patient to his or her body. The problem with prolonged use of loud volume is that the increased volume is liable to create tension and cause Qi deviations.

The volume of sound uttered also depends on the patient's current state of health. People who are physically weak can usually practice the breath regulating and Qi reinforcing exercises, but should not practice the sound pronouncing method until they feel appropriately energetic.

To practice the word pronouncing method, the patient should start from the soft volume and increase it gradually. Diseases of different parts of the body require different volumes. For example:

- Patients with Heart or Lung trouble can comfortably take the soft to moderate volume pronunciation;
- Patients with Liver, Spleen, Stomach, Kidney and intestinal diseases can take the moderate to louder volume pronunciation.

HIGH-, MIDDLE-, AND LOW-PITCHED SOUND

The healing sounds have high, middle, and low pitches with different penetrating potentials. When correctly vocalized, they cause resonant vibrations in the body, producing certain states of consciousness that have both a psychological and a physiological effect on the nervous system.

As the tones change from a high to low pitch, they regulate the depth of the tone penetration. Similar to a dimmer switch on a light bulb, the tone adjusts the depth of the vibration resonance in the body.

The three pitch sounds also affect the energy movement of the body's Triple Burners, as well as the internal organs positioned within the thorax.

1. The high-pitched sound is pronounced in a straight tone with the head slightly drooped. The high pitch focuses the energy resonation into the specific organs of the patient's Upper Burner from the sternum to the manubrium. After completing the sound resonation exercise, return back to the Wuji position and relax; regulate the body using natural breathing.
2. The middle-pitched sound is pronounced in either a rising or descending tone, depending on the patient's specific conditions. The rising tone will cause the patient's Qi to ascend, while the descending tone will cause the Qi to drop. The middle pitch focuses the energy resonation into the specific organs of the patient's Middle Burner from the navel to the sternum within patient's body. Middle-pitched sounds are only prescribed for specific conditions (organ prolapse or organ energetic overload).
3. The low-pitched sound is pronounced in a dropping, then rising tone, within one breath. This causes the energetic resonation to saturate the diseased organ from top to bottom, then from bottom to top. This focuses the energy resonation into the specific organs of the patient's Lower Burner from the navel to the perineum. The method of pronouncing the low-pitched sound is usually practiced immediately after sounding the high-pitched tone.

After pronouncing either the high-, middle- or low-pitched sounds, perform the Open and Close the Three Dantians method once, then close with the Pulling Down the Heavens exercise. This completes one set.

BREATH AND MIND CONTROL

Healing sounds produce an aspirating effect analogous to vacuuming a room. This analogy describes to the patient the desired intention needed to successfully utilize this modality of healing. Toning without proper focused intention, breath, and mind control placed on the specific internal organ is like trying to vacuum a room while waving the hose in the air. Although the hose is sucking the air, it is not performing the desired result of purging the room of dust and dirt. To become proficient and establish the desired result, the individual must focus the attention and place the vacuum hose onto the specific area that needs cleaning.

Healing sound and toning therapy work the same way. It is not just sounding the tone which allows the technique to work, but the combination of the breath and mind focused on the intended internal organ. When practicing sound therapy, the patient generally uses the Natural Breathing method, along with focused intention and color visualization.

While inhaling, the patient imagines breathing in divine, white light healing energy through the nose and absorbing this healing Qi into the diseased area, vibrating it.

When exhaling, the patient imagines breathing out the dark, diseased, Turbid Qi through the mouth. It is important for patients to maintain the healing color (i.e.: green, red, golden yellow, white, or blue) vibration inside the diseased organ, even when they exhale.

SEPARATING THE BREATH INTO YIN AND YANG

The breath can be divided into either Yin or Yang qualities. When breathing shallow and focusing the mind on the front of the throat, the breath feels cool and is therefore considered Yin; however, when shifting the mind's attention towards the back of the throat, the breath, when released, feels hot, and is considered Yang. This change in temperature is due to the front of the body being Yin in nature and the back of the body being Yang.

AUDIBLE AND INAUDIBLE SOUND RESONATION

Before projecting sound therapy in a clinical setting, the Qigong doctor must vibrate the three Dantians while focusing on his or her Taiji Pole. Once the sound vibration has filled the doctor's body, the resonate healing sounds can be projected into the patient's tissues and organs.

Another way to produce sound is to imagine that the sound is appearing as a specific color and causing a vibration within the body. Clinical sound therapy is further divided into three distinct levels of emitted energies: Obvious Sound Resonation, Hidden Sound Resonation and Mysterious Sound Resonation.

1. The Obvious (Ming) Sound Resonation is audible sound. This energy sound resonation is considered Yang and is produced through the vocal organs. When toning audibly, the healing sounds fills the Qigong doctor's energetic fields. These fields can then be transferred onto the patient to produce a very strong, physical affect on the patient's tissues and organs. The Qigong doctor connects (through intention) with the patient's internal organ, and imagines his or her voice penetrating the diseased organ's tissues. The doctor then imagines the patient's tissues vibrating like rippling water with the sound exhalation, to purge the pathogenic Qi.
2. The Hidden (An) Sound Resonation is slightly audible sound. This energy sound is considered Yin transitioning into Yang, and is produced by softly exhaling sound energy resonation into the patient's body. This slightly audible energy sound resonation affects the patient's tissues and organs more on an emotional plane, enveloping and penetrating the patient's tissues like a mist.
3. The Mysterious (Hua) Sound Resonation is inaudible sound. This energy sound resonation is considered Yin and is mentally produced inside of the doctor's body. The Qigong doctor first focuses and fills his or her body and energetic field with the vibrant sound. The doctor then focuses the mind on the healing sound like a mantra. This inner sound fills the Qigong doctor's field with resonant vibration which can be transferred into the patient's body. This energy sound resonation affects the patient's tissues and organs on a more spiritual dimension, enveloping and purging like a gentle light.

The Qigong doctor can also coordinate the projection of the healing sounds with the patient's toning to synchronize their energetic fields. All sound techniques have specific postures, breathing, and mind regulations to facilitate whole body integration.

Patients and students are usually encouraged to practice the audible sound vibrations until they can vibrate the tissues of the organs at will, before they proceed to the inaudible sound resonation.

THE SIX HEALING SOUND PRESCRIPTIONS

Before starting any organ sound exercise, there are certain grounding and cleansing techniques that the patient should practice. These preparation exercises are described as follows.

1. Always begin sound resonation from a Wuji standing posture.
2. Breathe naturally from the abdomen, inhaling through the nose and exhaling through the mouth. The body should be relaxed, and respiration should be gentle, thin, even, and extended. The mind should not concentrate on the expansion of the Lungs, but on the Lower Dantian first, and then on the treatment area. Also, breath through every pore of the body into the Lower Dantian.

   Upon exhaling, sound the healing word with a low volume pronunciation, feeling where the sound waves reach. Once the tissue area is stimulated, increase the volume. At the same time draw in the abdomen, draw up the anus, slightly knead the ground with the feet, sink the shoulders, and then shift the body weight to both heels. This will access the Kidneys' Water Qi. When inhaling, close the mouth, raise the tongue against the hard palate, and shift the body weight to the anterior soles of the feet. This will access the body's Fire energy. Exhale the specific sounds through the mouth while imagining the impurities of that specific organ being expelled.
3. Pull Down the Heavens (the ending breath regulation). Inhale and exhale through the nose. When inhaling, slowly raise both arms forward and upward from the sides of the body, with both palms facing downward until reaching shoulder level. Then turn the palms up, and continue to circle the arms over the head. When exhaling, bend the elbows to make a curve in front of the chest, and press the abdomen. Then separate the arms to the sides of the legs, and return to the Wuji posture (Figure 40.1).

   Regulate the breath three times in the Wuji posture after completing the exercise. Breathing Regulation (Pulling Down the Heavens) is required after the exercise of each sound is completed and before the next exercise begins.



Figure 40.1. Pulling Down the Heavens allows the patient to sink the Qi, returning the excess energy back into the Lower Dantian.

THE SOUND "XU" (SHU) NOURISHES THE LIVER

This sound relieves Liver stagnation, aids in correcting certain types of visual distortions, and purges the accumulation of Phlegm in the body (e.g., the condition of Lung Hot Phlegm, due to an already existing cold).

Both hands overlap the inner Laogong Pc-8 points, with the left hand on the outside for men (opposite hand position for women). The Shaoshang Lu-11 point of both thumbs presses against the navel, with the Laogong points pointing at the umbilicus.

When inhaling, expand the abdomen and close the eyes, feeling the breath envelop and penetrate the Liver organ. At the same time direct the Qi of the Liver's Channels to flow upward from the Dadun Lv-1 point on the lateral portions of the big toes. Visualize the Qi rising through the lower abdomen, linking the Gall Bladder to the Lungs, traveling to the throat, and eyes, to the forehead, and then to the Baihui GV-20 point.

When exhaling, contract the abdomen and release the pathogenic factors. Focus the attention and imagination on the Qi flowing down the face, to connect with the Lungs' Channels, flowing downward to the Shaoshang Lu-11 points on the medial portions of the thumbs. The Qi is then directed and rooted into the Lower Dantian. Open the eyes wide, and sound the word "Shu" (the lips are slightly brought together, the tongue tip stretches forward with the lateral sides slightly curling toward the middle). Exhale completely.

In this particular exercise, the breath should feel lukewarm as you exhale (Figure 40.2). Perform six times.

THE SOUND "KE" (HA) REPLENISHES THE HEART

This sound relieves Fire from the Heart and expels Heat from the body; it also improves poor circulation and reduces fevers. The respiration patterns are the same as those in the previous (Liver) sound prescription.

When inhaling, raise both hands to shoulder level as if embracing a post. Both palms should face each other with the arms making a curve in front of the chest. Expand the abdomen and close the eyes; feel the breath envelop and penetrate the Heart organ. At the same time direct the Qi of the Spleen's Channels to flow from the Yinbai Sp-1 point on the medial portion of the big toes, along the inner portions of the legs, upward to the abdomen to meet with the Thrusting Channels, and enter into the Heart.



Figure 40.2. The sound "Xu" (Shu) is used to purge Liver stagnation as well as to disperse the accumulation of Phlegm in the body (Lung Hot Phlegm).



Figure 40.3. The sound "Ke" (Ha) is used to purge Heart Fire as well as expel Heat from the body.



Figure 40.4. The sound "Hu" (Who) is used to treat digestive problems, by purging Stomach and Intestinal stagnation.

When exhaling, softly open the eyes and draw the Qi out from the Heart, past the Lungs, through the armpits, along the inner portions of the arms, to the Shaochong Ht-9 point on the medial portion of the little fingers. Point the fingers forward to release the pathogenic Qi, and sound the word "Ha." The mouth is half closed with the tongue placed against the lower mandible. Exhale completely. This breath should feel hot (Figure 40.3).

Return to the beginning position and perform six times.

THE SOUND "HU" (WHO) STRENGTHENS THE SPLEEN

This sound is used to correct digestive problems, especially when the Stomach or intestines feel full or sluggish.

When inhaling, raise both hands upward in front of the abdomen, as if embracing a ball in the Lower Dantian area. Both palms should face each other with the arms making a curve. Expand the abdomen and close the eyes; feel the breath envelop and penetrate the Spleen organ. Direct the Qi of the Spleen's Channels to flow from the Yinbai Sp-1 points on the medial portion of the big toes, up to the abdomen to enter the Spleen, and to link up with the Stomach.

When exhaling, the right palm turns outward, rolling over and pushing above the head, thus forming the posture of Holding the Heavens. At the same time, imagine the Qi ascending up to the throat, to the root of the tongue, and spreading under it. Imagine a secondary river of Qi flowing from the Stomach to the Heart, and ascending along the Heart's Channels to the Shaochong Ht-9 point on the medial portion of the little fingers, and exhale the sound "Who." The lips are brought together as if playing a flute, the tongue is level and stretched forward as much as possible to allow the ascending energy of the Thrusting Channels to rush out. Exhale completely while the left palm turns downward and presses down to the outside of the left hip (Figure 40.4).



Figure 40.5. The sound "Si" (Sss) is used in order to Purge the Lungs.

Next, inhale and turn the right palm over to face the body; slowly descend the right arm in front of the body, while the left arm turns towards the body and ascends. The two hands cross in front of each other (with the ascending arm on the inside, and the descending arm outside). Now the left hand pushes up and the right hand pushes down. At the same time, exhale and repeat the sound "Who." Pressing both left and right hands form one set. Perform six times. At the end, cross both arms in front of the chest and return to the beginning position.

THE SOUND "SI" (SSSS) MOISTENS THE LUNGS

This sound is used to nourish the Lungs, treat problems such as tuberculosis, abscesses, and dermatitis.

From the beginning Wuji posture, inhale and raise both hands as if holding a ball, moving it upwards, until the hands face the Shanzhong CV-17 point at the front of the chest. Direct the Qi of the Liver's Channels to ascend from the Dadun Lv-1 point on the lateral portions of the big toes, along the inner portion of the legs, through the lower abdomen into the Lungs.

When exhaling, turn over both palms to face downward, then separate the palms horizontally to the sides. Guide the Qi along the Lungs' Channels to the Shaoshang Lu-11 points on the inner portion of the thumbs, while exhaling the sound "Sss" The lips are slightly drawn back, the upper and lower teeth are slightly brought together forming a small slit; the tip of the tongue is placed against the slit in-between the teeth to articulate the sound. Exhale completely, then allow both arms to descend to the sides of the body (Figure 40.5). Repeat six times.

THE SOUND "CHUI" (CHREE) STRENGTHENS THE KIDNEYS

This sound is used to regulate the Kidneys, expel chills, and to maintain the Internal Heat of the Lower Dantian and Mingmen Fire.

Inhale and raise both arms to embrace an imaginary ball in front of the chest (Middle Dantian area).



Figure 40.6. The sound "Chui" (Chree) is used to regulate the Kidneys and the Mingmen Fire, as well as to expel chills from the body.



Figure 40.7. Massage the sides of the body.

The joints in between the thumb and index finger of both hands are stretched wide open. Lead the Qi to flow upward from the Yongquan Kd-1 points of the Kidney Channels, through the inner portions of the thighs, along the spinal column, and into the Kidneys.

When exhaling, hold the posture and stretch the fingers, while leading the Qi from the Kidneys into the chest and then to the Lungs. The channel Qi then transfers into the Pericardium Channels and flows down the arms to the Zhongchong Pc-9 points at the tips of the middle fingers. While exhaling, sound the word "Chree." The mouth is nearly closed with the corners slightly drawn back; the tongue moves forward. The breath should feel cold (Figure 40.6).

Slowly straighten the body as the hands circle downward, from the lower back to the thighs. Rub the lower lumbar region (Shenshu Bl-23 points) and the sides of the thighs (Huantiao GB-30 points), moving the hands upward while massaging the buttocks. Return to the holding the ball posture and repeat six times (Figure 40.7).

THE SOUND "XI" (SHE) REGULATES THE TRIPLE BURNERS

This sound is used to eliminate Excess Heat, for treating rheumatism, poor circulation, and problems of the Triple Burners. This exercise helps to recharge the body's Qi metabolism, regulate Internal Qi, and balance the eight systems of the body (respiratory, digestive, reproductive, circulatory, lymphatic, nervous, muscular/skeletal, and excretory systems).

The "She" sound of the Triple Burners is always prescribed for patients undergoing radiation or chemotherapy. This allows the patient to disperse the toxic Heat left within the tissues.

From a beginning Wuji posture, inhale and raise both hands as if holding an imaginary ball up in front of the chest at the Middle Dantian. Direct the channel Qi of the Triple Burner Channels in the arms to flow downward to the Lower Dantian, then down the legs via the Gallbladder Channels to the tips of the fourth toes of the feet at the Qiaoyin points (GB-44).

Exhale the sound "She," at the same time rotating both arms upward to form the Embracing the Heavens posture. The lips are slightly open and drawn back; the tongue suspends behind the teeth. When exhaling, direct the Qi to flow from the Qiaoyin GB-44 points on the outer portion of the fourth toes upward, along the Gall Bladder Channels, through the outer portions of the legs to the head, and transfer the energy flow into the Triple Burner Channels, directing it along the outer portions of the arms to the Guanchong TB-1 points at the ends of the ring fingers. Exhale completely.

Inhale, while turning the palms over to face downward, and begin lowering both arms along the front of the chest. Imagine the Qi flowing down from both arms into the Lower Dantian. Exhale without sounding "She," and press both palms down along the front of the abdomen to the sides of the hips, returning to the Wuji posture (Figure 40.8). Repeat the entire sequence six times.

This exercise is different from the others in that the energy circulates back and forth through the channels but does not disperse outside the body. Meaning you inhale Qi from fingers to toes, exhale Qi from toes to fingers and sound, inhale Qi from fingers to Lower Dantian, exhale Qi from Lower Dantian to toes, without sound, then begin entire sequence again.



Figure 40.8. The sound "Xi" (She) is used to purge Excess Heat from the body.

THE PROPER NUMBER OF BREATHS FOR HEALING SOUND PRACTICE

When practicing all six healing sounds, each sound should be practiced a minimum of three to six times before proceeding on to the next sound. If the patient wishes to practice the six healing sounds daily, the patient should perform each sound no more than twenty-four times. If the patient is practicing one or more healing sounds for a specific therapy, then the number of times for tone resonances should be thirty-six.

Practice the six healing sounds in the sequential order of the Fire Cycle (i.e., Liver, Heart, Spleen, Lungs, Kidneys, and Triple Burners) to enhance the

Summary

1. Trust and Believe (Concept and Desire).
2. Visualization turns into activation.
3. Think and let it happen. It will become easier with practice.

Once you understand the practice and go through the practice a few times, you can just simply use the mind and recall the past experience and there is no need to go through all the steps. Think and let it happen.

Fusion Opening: Fusing Universal Energy

1. Inner Smile–Activate Compassion first (Love and Sexual Energy combined).
2. Activate Three Fires.
3. Create Pakuas; Front, Back, Facial, Universal.
4. Form Cauldron, spin Pakuas.
5. Form organ Collection Points of Physicial Body.
   Energy Body and Universal Body.
6. Remove Negative Energy from the Organs.
7. Sense the Colors of the Collection Points imagine the Dial-1,2,3 of Colors.
8. Fuse inner Positive Energy of the Energy Body and Physical Body with Universal Energy through turning the Dial-1,2,3.
9. Fusion of the Universe Energy back into Body and Energy Body.
10. Create Four Balls of fused energy and spin them very very fast above the Cauldron.
11. Form a Pearl.

Begin Cosmic Fusion: the Creation Cycle.

Be aware of the heart and cauldron activating the compassion fire.

1. Listen to the Gentleness Virtue of the Kidneys.
2. Gentleness Energy activates the Kindness Virtue of the Liver.
3. Kindness Energy activates Honor, Respect, Love in the Heart.
4. The Energy of Honesty and Respect activates the Fairness and Openness Virtues of the Spleen and Pancreas.
5. The Energy of Fairness and Openess activates the Courage and Righteousness Virtues of the Lungs.
6. Courage and Righteousness enhance Gentleness: the Cycle Begins again at the Kidneys.
7. Combine all Good Virtues energies into the Heart and create Compassion Energy.
8. Move the Compassion Energy through the Microcosmic Orbit.
9. Shoot the Pearl above the Crown.
10. Practice Chi Massage.

Yang energetic field. Practice the six healing sounds in the sequential order of the Water Cycle (i.e., Liver, Kidneys, Lungs, Spleen, Heart, and Triple Burners) to enhance the Yin energetic field.

It is advisable to practice the healing sounds at the end of a meditation practice. This is because the free circulation of Qi is already in motion and freely accessible after meditating.

COMBINING MULTIPLE ORGAN SOUNDS

The six healing organ sounds may be performed as in the prescribed series, or as individual therapies ranging from single to multiple organ sounds. Some examples are:

1. Single organ sound regulation, like the "Haa" sound for the Heart, is used followed by swallowing the collected saliva (after Qi purgation) to relieve a fast, irregular heartbeat.
2. Multiple organ sound regulations, like the sounds of "Shu" (Liver), "Haa" (Heart), and "Sss" (Lungs), are used in sequence to quench the pathogenic Fire inside the patient's body (for mild symptoms).
3. All six healing sounds are used for regulation and balance to treat "False Cold" (a feverish sensation followed by a feeling of cold all over the body). This symptom is caused by Excess Fire. The Internal Fire drives the Yin to the body's surface, thus producing the cold sensation. To treat, the Qigong doctor guides the patient's Yin Qi back to its original organs and uses all six sounds to regulate the body.
4. Sounding according to the Five Seasons will also be beneficial to the patient's Qi regulation. The five sounds are divided according to each season, and the vulnerability of each organ. They are categorized as follows:
    a. "Shu" sounding in the springtime will benefit the Liver.
    b. "Ha" sounding in the summer will benefit the Heart.
    c. "Ssss" sounding in the autumn will benefit the Lungs.
    d. "Chree" sounding in the winter, and during all seasons, will vitalize the Kidneys and harmonize Qi and Blood.
    e. "Who" sounding in all seasons helps vitalize the Spleen and regulates the function of Postnatal Qi.
5. Combining healing sounds according to the specific prescriptions is similar to taking combinations of Chinese herbs. The Six Healing Sounds may be combined in order to target specific areas on the body's energetic system. Generally, the doctor gives the patient specific healing sound combinations as prescriptions to purge stagnation, and to increase the energetic movement within the diseased tissues or organs.

One such combination prescription used to treat overall Shen disturbances due to emotional depression, from suppressed anger, guilt or grief is called, "Old Man Searching for the Reflection of the Moon at the Bottom of the Tide Pool." In Medical Qigong Soul Retrieval, this healing sound prescription is used to bring the patient back in touch with his or her painful emotions.

OLD MAN SEARCHING FOR THE REFLECTION OF THE MOON AT THE BOTTOM OF TIDE POOL

This particular exercise was introduced into the United Stated in the early 70's by Dr. Her Yue Wong. Doctor Wong believed that after the Qigong student has spent a sufficient amount of time practicing the Five Elemental Daoist Qigong tonification exercises, his or her deep seated emotions will begin to surface and must be purged from the body. In order to purge the toxic emotions, this healing sound prescription was given:

1. Begin this exercise prescription from a standing posture. Both feet are facing forward, shoulders width apart. Inhale, and imagine divine healing light filling the Lungs. While inhaling, separate and stretch both arms to the sides of the body, forming the shape of a "T" (Figure 40.9).
2. Lean over and begin to exhale, making the "Sh-h-h-h" sound. While exhaling imagine Toxic Qi from both Lungs flowing down each arm and pouring into the ground. Both arms should swing from one side to the other, crisscrossing



Figure 40. 9. Old Man and Tide Pool (a)



Figure 40. 10. Old Man and Tide Pool (b)



Figure 40. 11. Old Man and Tide Pool (c)



Figure 40. 12. Old Man and Tide Pool (d)

while making the purging sound (Figure 40.10).

3. Return to an upright position, while inhaling and imagining divine healing light filling the chest (especially the Heart, Liver and Spleen areas). When inhaling, look upward and raise the hands over the head (Figure 40.11).
4. When exhaling, both hands should descend to shoulder level, making soft fists (as if embracing two sparrows). Focus the mind's intention on the center of the chest and imagine the Toxic Qi releasing from the Heart while making the "Haa-a-a-a" sound. Exhale only half of your breath. Next, exhale the second half of your breath while imagining Toxic Qi releasing from the Liver and Spleen and making the "Who-o-o-o" sound. While exhaling, move both hands down to the hips while keeping the fists soft (Figure 40.12). Repeat the last two steps (c. and d.) three times. This equals one set. Practice 36 sets to complete the exercise. It should take about 25 minutes.

There is an story associated with this ancient healing sound prescription; it is described as follows.

One night, on a full moon, an old man on the southern coast of China, went looking for sea crustaceans to feed his family. Holding his lamp upward, he gazed down and saw a large beautiful pearl at the bottom of a tide pool. "Oh My!" He exclaimed, as he quickly placed his lamp on a rock. "Look at the size of that pearl! With a pearl that large, I'll be able to retire! Even my family won't have to work, and we'll all live in the lap of luxury for the rest of our lives!"

So the old man stretched his hands wide and began splashing his arms in the tide pool, trying to grasp the large pearl. Sh-h-h-h-h-h-h-h! went the water as the old man frantically grasped at nothing. Perplexed, the old man looked up. Reaching into the night sky, the old man's eyes widened as he saw the full moon. "Ha-a-a-a-a-a!" exclaimed the old man, "It's the moon!" "Whooo-o-o-o-o-o" cried the old man, "There's no money!"

CONTRAINDICATIONS FOR THE SIX HEALING SOUND THERAPY

There are several counter-indications for the use of the Six Healing Sound Therapy:

- The resonating sounds have a strong affect on the tissues, therefore patients who have broken or fractured bones are forbidden to practice sound therapy. Only after the bones tissues have mended are the patients allowed to practice the healing sounds.
- Due to the stimulating effect of the Six Healing Sound Therapy, it is advisable for the Qigong doctor not to prescribe the practice of the six healing tones in a very acute stage of illness. Vibrating the patient's internal organs in the beginning stages of a disease (i.e., a high fever) may stimulate the patient's virus or bacterial growth.
- Women are prohibited from practicing Tone Resonation therapy when pregnant, as the tone resonations have a pattern of dispersing clots and may lead to spontaneous miscarriages.
- Women are prohibited from practicing Tone Resonation therapy when menstruating, as it is important for the woman's body to be allowed to naturally Purge Toxic Blood from the body.

SOUND RESONATION THERAPY FOR TUMOR AND CANCER

Cysts, tumors, and cancer are characteristic of Excess stagnation of Qi and Blood, as well as stagnations of Heat and Cold. Chronic diseases, marked by obstruction of channel Qi, disorders of Qi and Blood, and the breakdown of Yin and Yang balance, are also included as Excess stagnation syndromes. The following sound methods involve a special series of tone resonation exercises (similar to, but stronger then the six healing sounds) which are utilized to disperse stagnations.

In order to find the correct pitch, the patient starts with a soft volume sound to experience the physical characteristics of the internal organ vibrating. While pronouncing the tone with the vocal cords relaxed, the patient gradually increases the sound to a louder volume.

While exhaling the sound, the patient focuses on an internal image of the diseased tumor dissolving. The patient must actually hear and feel the sound resonating the body's tissues, saturating the organ with sound vibration, energy, and light.

The following sounds are prescribed for the treatment of tumor and cancer therapy: the "Guo" sound is used by patients with Liver diseases, the "Zheng" (pronounced as jang) sound is pronounced by patients with Heart trouble, the "Gong" sound by patients with Spleen diseases, the "Shang" sound by patients with Lung trouble, and the "Yu" sound by patients with Kidney diseases. The relationship between the five pronunciations and the five solid organs as well as the number of pronunciations are shown in Figure 40.13.

PREPARATION FOR TUMOR AND CANCER SOUND THERAPY

Have the patient begin this exercise in a Wuji posture, and encourage the patient through the One Through Four meditation (One-Fun, Two-Shoe, Three-Tree, and Four-Core) described in Chapter 26.

Each tumor and cancer healing sound is pronounced in a straight tone, facing the left and exhaling the tone while rotating the body to the right. This allows the patient to purge the specific diseased organ. After completing the required number of straight tone exhalations, the patient faces forward and pauses.

The patient then begins the second half of the

		Elements				
		Wood	Fire	Earth	Metal	Water
Yin organs	solid organs	Liver	Heart	Spleen	Lung	Kidney
Yang organs	hollow organs	Gall Bladder	Small Intestine	Stomach	Large Intestine	Bladder
body turns left to right body turns right to left	high-pitched straight tone low-pitched descending-ascending tone	guo	zheng	gong	shang	yu
number of repetitions		8	7	10	9	6

Figure 40.13. Tumor and Cancer Sound Therapy Chart

prescription by facing the right direction and exhaling a descending tone while rotating the body to the center of the room, then rising tone while rotating the body towards the left side of the room. This application causes the patient to purge the diseased organ's channels of Toxic Qi.

Upon completion the patient performs the Pulling Down the Heavens technique to cleanse the body of any leftover energetic residue.

THE PROPER AMOUNT OF TONE REGULATIONS

The beginning patient should not be too anxious to perform the required number of pronunciations. By gradually reaching the required number, and slowly adapting themselves to the Tone Resonation method, the patients avoid getting tired. The sound "Shang," for example, is pronounced nine times for each exercise in the case of Lung disease. However, a beginner may start by pronouncing the tone three times, and then gradually progress to six times in twenty days. Then, in another thirty days, the patient can reach the required number of times. The number of repetitions is always dependent upon the patient's age, type of constitution and the severity of the disease.

In other words, the amount of times in a day that the patient performs the healing sounds depends upon the patient's general condition. The sounds used in tumor and cancer therapy, for example, will be prescribed more frequently with less volume then that of the regular six healing sound therapies. For Lung cancer, for example, the patient should perform the "Shang" sound eighteen times a day, nine breaths in each direction, right and left; for Lung congestion, perform the "Sss" sound three times a day, 36 breaths for each set.

SPECIALIZED PRESCRIPTIONS FOR TUMORS AND CANCER

The sound therapies used for treating tumors and cancer are quite different and much more powerful then the six healing sounds previously prescribed to purge and regulate the body's internal organs. Because of the dramatic difference in power and energetic potential between these two healing sound systems, the cancer patient will be given a lower number in tone respirations, but an increased number of times of practice per day.

The healing sounds used for treating tumors and cancers are as follows: for Liver/Gall Blad-



Figure 40.14. For Liver diseases the sound is "Guo."



Figure 40.15. For Heart trouble, the sound is "Zheng" (Jang).



Figure 40.16. For Spleen diseases, the sound is "Gong."



Figure 40.17. For Lung trouble, the sound is "Shang."



Figure 40.18. For Kidney diseases, the sound is "Yu."



Figure 40.19. For chemotherapy, the sound is "Xi" (She).

der tumors, use the sound "Guo" (Figure 40.14); for Heart/Small Intestine tumors, use the sound "Zheng" (Jang - Figure 40.15); for Spleen/Stomach tumors, use the sound "Gong" (Figure 40.16); for Lung/Large Intestine tumors, use the sound "Shang" (Figure 40.17); and for Kidney/Bladder tumors, use the sound "Yu" (Figure 40.18). The Triple Burners' sound "Xi" (She) is used to purge Heat from the body after radiation and chemotherapy (Figure 40.19).

The choice of sound resonation must suit the patient's specific disease. Generally, in the beginning, patients with cancer should mainly pronounce the purgation sound "Haa" nine times to purge the Heart of stagnant emotions (Figure 40.20). After pronouncing the sound "Haa" for a certain time period, the patient begins to become emotionally vulnerable. The doctor then adds the specific sounds for the treatment of the diseased internal organs. The "Shang" sound, for example, is prescribed for patients with Lung cancer.

1. The tones for Radiation and Chemotherapy patients should include the Triple Burners' sound "She." This toning should be done when their blood count is low after chemotherapy or radiation therapy and is used to purge Excess Heat from the body. The sound "She" is pronounced six times. Its high-pitched sound is in the straight tone (perform six times), and its low-pitched sound is in the dropping and rising tone (perform six times).

   After the patient has stabilized and the red and white blood count has reached a normal level, the "She" sound is dropped and replace by the sound "Haa." This is done to stabilize the patient's emotions. Instead of "Haa," the doctor can also replaced the healing sound with the specific sound needed to treat the diseased internal organ.
2. The tones for Stomach cancer patients should include the sound "Dong." The Dong sound has a deeper penetrating affect than the "Gong" sound (which is usually prescribed for Stomach diseases). The "Dong" sound should be pronounced ten times (Figure 40.21). Its high-pitched sound is "Dong" in the straight tone (perform ten times), and its low-pitched sound is "Dong" in the dropping and rising tone (perform ten times).
3. The tones for Brain tumor patients (with cerebral carcinoma) should include the sound "Duo." The "Duo" sound should be pronounced ten times (Figure 40.22). Its high-pitched sound is "Duo" in the straight tone (perform ten times), and its low-pitched sound is "Duo" in the dropping and rising



Figure 40.20. For cancer in general, the sound is "Ha."



Figure 40.21. For Stomach cancer, the sound is "Dong."



Figure 40.22. For brain cancer, the sound is "Duo."



Figure 40.23. Back View for the Cancer Prescriptions

tone (perform ten times). In addition the patient should also practice techniques to strengthen the Kidneys and Heart.

4. The tones for Lung tumor patients (with carcinomas of the Lungs) should include the "Shang" sound. The "Shang" sound should be pronounced nine times. The patient should also use the Fast Breathing Method technique (2 inhalations, followed by 1 exhalation of the sound "Shang"), in addition to practicing Lung and Kidney strengthening exercises.
5. The tones for Large Intestine tumor patients (with carcinomas of the Large Intestine) should include the "Shang" sound. The "Shang" sound should be practiced nine times using the Fast Breathing Method technique, in addition to practicing Lung strengthening exercises.
6. The tones for Nasopharyngeal tumor patients should include the "Shang" sound. The "Shang" sound should be practiced nine times using the Fast Breathing Method Walking technique (see Chapter 15), in addition to practicing Lung strengthening exercises.
7. The tones for Small Intestine tumor patients (with carcinomas of the Small Intestine) should include the "Zheng" sound. The "Zheng" sound should be practiced seven times, using the Fast Breathing Method technique, in addition to practicing Heart strengthening exercises.
8. The tones for Liver Cancer and Gall Bladder tumor patients (with carcinomas of the Liver and Gall Bladder) should include the "Guo" sound. The "Gou" sound should be practiced eight times, using the Fast Breathing Method technique, in addition to practicing Lung, Liver, and Spleen strengthening exercises.
9. The tones for the Bladder and uterus tumor patients (with carcinomas of the Urinary Bladder and uterus) should include the "Yu" sound. The "Yu" sound should be practiced six times, using the Fast Breathing technique, in addition to practicing Kidney strengthening exercises.

   While in a Wuji posture, the patient places both hands on the Kidneys and presses the middle fingers at the Shenshu Bl-23 point beside the Mingmen before pronouncing the sounds (Figure 40.23).
10. The tones for Prostate cancer patients should include the "Yu" sound. The "Yu" sound should be practiced six times, using the Fast Breathing Method technique, in addition to practicing Kidney strengthening exercises.
11. The tones for Skin Cancer patients (with dermal carcinomas) should include the "Shang" sound. The "Shang" sound should be practiced nine times, using the Fast Breathing Method technique, in addition to practicing Lung, Liver, and Spleen strengthening exercises.

CONTRAINDICATIONS FOR TUMOR AND CANCER SOUND THERAPY

As previously mentioned, the tumor and cancer healing sounds are only prescribed for purging Excess conditions within the patient's diseased organs, and not for treating Deficient organ conditions. If a specific internal organ is already in a state of Deficiency and the patient is allowed to focus on that organ with one of the tumor and cancer sounds, the patient's condition will worsen. This increases the potential for rapid growth of the disease.

CHAPTER 41
MEDICAL QIGONG REGULATION EXERCISES

INTRODUCTION

The following chapters explore several systems of Medical Qigong exercises used in regulation, purgation, and tonification prescriptions. Conceived in ancient China, these exercises originate from the various medical, martial, and Daoist schools of energy cultivation. It is from these ancient energetic systems that today's modern clinical Qigong prescriptions originate.

Each Qigong system has its own unique approach to circulating, balancing, and storing the body's life-force energy. No one particular style of energetic healing is superior to the next, only different in its approach. The primary goal of each of these systems is removing stagnant pathogenic energy and replenishing and circulating clean life-force energy.

The Xi Yuan Hospital in Beijing, China is famous for its advanced Medical Qigong clinics and Medical Qigong prescriptions. These exercises utilize both Static and Dynamic Postures and are generally taught in both the inpatient and outpatient clinics. The static exercises are used to store the Qi, while Dynamic Qigong exercises are used to open the patient's channels and circulate the Qi.

Each prescription should be practiced for five to ten minutes for each organ or organ system on a daily basis; or if the patient is practicing only one set (e.g., Regulation of Spleen and Stomach Qi), they should practice for thirty minutes. Unless otherwise indicated, all breathing should be "natural."

The goal is for patients to empty their body and mind, so that their emotions can be felt and activated. In the Medical Qigong clinic there is a saying, "The patient can only heal what they feel."

STARTING AND ENDING THE PRESCRIPTIONS

Before starting any Medical Qigong prescription, it is important for the patient to understand that every Qigong exercise must start and end with specific preparations.

- Before starting the Medical Qigong prescription, the patient must always purge his or her body. It does not matter if the exercise they are about to begin is used to purge, tonify, or regulate the internal energy; they must always purge first. This is similar to washing a dirty glass before filling it with clean water.
- After ending the Medical Qigong prescription, the patient must always gather the generated Internal Qi and the return to its origin. The term "Return to its Origin" refers to a three fold process:
  - cultivating, collecting, and accumulating the prenatal energy,
  - developing and transforming it into postnatal Jing, Qi, and Shen, and
  - returning it back to prenatal Jing, Qi, and Shen.

This allows the Post-Heaven Kan and Li (Water and Fire energies) to return to their origin and restores them to Pre-Heaven Qi (Heaven and Earth energies). This fusion into one energy, often called the Hun-Yuan or Blended Originals, requires the patient's original substances to condense into one energetic substance and be merged with the patient's Lower Dantian energy.

In order to collect the energy, the patient is taught to apply the Three Natures Become One technique of focused concentration (all thinking, seeing, and listening is focused into the Lower Dantian). The Three Natures are as follows: the eyes represent the perceptive nature, the ears rep-

Chapter 7

Opening the Thrusting Channels

Theory of the Thrusting Channels

After the positive emotional energy of the organs is absorbed into the pearl, it is then circulated in four of the four special channels: the Microcosmic Orbit (Governor and Functional Channels), the Thrusting Routes, and the Belt Routes. The Thrusting Routes run through the center of the body, linking the “chakra” centers. The Belt Routes spiral around the body, strengthening the aura and providing a form of psychic self-defense. The second part of the Cosmic Fusion practice involves opening these three Thrusting Channels.

The Thrusting Channels are a powerful means to clean out the negative emotions and detoxify the organs and glands. Set into action, the three Thrusting Channels will serve as strong and efficient ways to check your center and observe the status of your emotions.

The Thrusting Channels run from the perineum to the crown and are separately identified as the Middle, Left and Right Thrusting Channels. The Middle Thrusting Channel begins directly at the perineum and runs vertically up to the crown. The Left Thrusting Channel is located one and a half to three inches to the left of the Middle Channel, while the Right Thrusting Channel is one and a half to three inches to its right.

When you are feeling emotional, you can check the Thrusting Channels, especially the Middle Channel, to discern whether you are off-center. You will know if you are out of balance when you feel the emotions running more on the left side or on the right, instead of through the middle of the body. If you center the emotions through the Middle Thrusting Channel, and keep the Left and Right Thrusting Channels in balance, you will very quickly center yourself. The Thrusting Channels serve as guidelines to decision-making in your daily life.

resent the spiritual nature, and the Heart represents the courageous nature. When all three natures unite into one, the energetic refinement is called "collecting the body's true nature." The patient can then collect the body's power.

MEDICAL QIGONG CULTIVATION EXERCISES

The body is composed of different densities of energy and matter in the form of internal organs, organ systems, channels, and collaterals. When practicing Qi cultivation methods both students and patients are instructed to train in a progressive order of Qi cultivation.

First, the students and patients are taught how to purge, tonify, and regulate their internal and external channels. Once the Yin and Yang energy of the channels are balanced, the practitioners learn how to balance the Yin and Yang energy of the internal organs. This training likewise involves purging, tonifying and cultivating methods. The directed focus of intention on specific points, channels, or areas of the body causes the Qi to gather in those locations and to be absorbed into the body's tissues through the Mind's intention (whole body awareness and consciousness). The final step of training the Yuan (Original) Qi is undertaken only after the first two steps have been accomplished.

All cultivation practices of Medical Qigong therapy can be divided into two main categories of gathering and training Qi: the External Elixir Cultivation (Wai Dan Shu) and the Internal Elixir Cultivation (Nei Dan Shu). These two Qi cultivation training methods are described as follows.

EXTERNAL QI CULTIVATION

The External Elixir Cultivation (Wai Dan Shu) involves several methods of gathering energy from the external environment (Heaven and Earth) to strengthen the body's organs, organ systems, channels, and collaterals.

HERBS AND FOOD

The first method is developed through food and herbal soups, teas, and pills to increase the body's energy. When herbs are prescribed as a tonic, they stimulate the organ's energy by increasing the flow of Qi in the patient's channels. Qigong and herbology go hand-in-hand with respect to the energetic regulation and balance of the body's life-force energy. Herbs can be extremely important for maintaining the physiological balance of the metabolism and restoring any depletion of the body's energetic mechanism. Herbs act as a form of energetic nutrient, allowing the Earth energy to be ingested into the body through a natural substance.

MEDITATION

The second method is developed through meditation. Qi is cultivated through the body's extremities from energy originating outside of the body's torso (i.e., both palms, both soles of the feet, and the top of the head). The External Elixir Cultivation meditation focuses the concentration on either the Heaven or Earth energy fields to draw their energy into the torso for increased Yin or Yang Qi regulation. The Postural Dao Yins in External Elixir Cultivation may be either static or dynamic.

Two examples of External Elixir Cultivations are: the Earth Yin Qi Regulation and the Heaven Yang Qi Regulation. The Earth Yin and Heaven Yang Qi Regulations are used to balance the energy along the body's ascending and descending energetic channels. To balance along the horizontal energetic channel, perform the Turning and Winding the Belt Vessel exercise described later on in this chapter.

- **Earth Yin Qi Regulation**

  The Earth Qi is considered Yin Qi or electronegative energy. Blood also pertains to Yin Qi. Through Earth Regulating Qigong meditations, the body's Blood cells can be replenished with Earth Yin energy.

  Begin the Earth Qi Regulation meditation from a Wuji posture, while using Natural Breathing. In this particular exercise, the practitioner takes advantage of the Kd-1 points at the bottom of the feet, and the Pc-8 points at the center of the palms which are sensitive to the magnetic pull of the Earth.

  After standing in the Wuji posture for several minutes, inhale and begin to absorb the

Earth Qi up from the ground through the centers of the palms and the bottom of the feet (Figure 41.1). After several more minutes of drawing the Earth energy into the Lower Dantian, begin circulating the energy through the Microcosmic Orbit's Fire Cycle. The palms should begin to expand and feel almost swollen; the red and white blotches on the palms and feet indicate that the exercise has been practiced correctly.

- **Heaven Yang Qi Regulation**

Heaven energy pertains to the sun's Yang Qi or electropositive energy, which is used to tonify the body's Yang Qi.

Begin from a Wuji posture, placing both palms above the head, facing upwards, like two antennas collecting the sun or Heaven's Qi into the Middle Dantian. Use Natural Breathing. Imagine the sun's golden light showering the outside of your body. Open your mouth and imagine swallowing the sun's Qi, allowing it to mix with your saliva. As you swallow, feel the energy flow down into your Lower Dantian, and then out of your pores. Once the Dantian is full, the body should feel expansive. Always end the meditation by returning the energy to the Lower Dantian to avoid any Qi deviations (Figure 41.2).



Figure 41.1. Absorb the Earth Qi into the body through both hands and feet, and store the Qi in the Lower Dantian.



Figure 41.2. Absorb the sun's energy into the body through both palms, moving it into the Middle Dantian, and store the Qi in the Lower Dantian.

INTERNAL QI CULTIVATION

The Internal Elixir Cultivation (Nei Dan Shu) method focuses on first training the energetic substances already gathered and existing inside the torso, and then extending this accumulated energy out into the extremities. Since it first appeared in the Han Dynasty, the training and theory of Internal Elixir Cultivation has become the primary focus of many Qigong masters, working with postnatal energy transformations. Internal Elixir Cultivation focuses on transforming the body's Jing, Qi, and Shen. When practicing this exercise, ancient Qigong masters imagined the Lower Dantian as a stove, the Shen as a Fire, and the body's Jing, Qi, and Shen as the internal medicine.

At birth, the energy flows up the front of the body (Conception Vessel) and down the back (Governing Vessel). This is considered the circulation of the Yuan Qi (generated from the prenatal Jing stored in the Kidneys). It is considered the Perceptual Yin or Water Cycle of the Microcosmic Orbit. This Perceptual Yin Cycle allows the newborn child to possess powerful psychic, empathic, and kinetic abilities; it enables the child to energetically connect with the environment in order to ensure survival.

As the child advances in age, he or she begins to encounter and experience some hostile messages in the form of physical or emotional frustration and pain from both parents, siblings, and the environment. For protection, the child armors and creates a denial system, which insulates him or her from the energetic and emotional wounding. The child begins to instinctively stop the energetic flow of the perceptual Yin Water Cycle and begins to activate the acquired rational mind, trying to cope with his or her feelings and the stress of his or her surroundings. Whenever the child begins to experience painful emotions, he or she learns to avoid experiencing these hurtful feelings through certain mental and physical actions by contracting the throat and thorax. These acquired actions further create an energetic restriction and impede the flow of Qi along the Conception and Governing Vessels. This physical activity naturally causes the Yin Water Cycle to stop its perceptual flow of energy, and allows the child's body to deal with the trapped emotional experiences by storing them within the tissues. Although this is not a healthy response, it allows the child to survive and develop in a sometimes difficult environment. In cases of deep traumatic wounding (physical, emotional or sexual), the child becomes void of deep emotional connections, while still allowing for certain perceptual survival instincts.

Also, our culture emphasizes left brain thinking for educational purposes, and later to enable young adults to rival others in the competitive job market. The child thus must forgo most of his or her innate intuitive perceptions to succeed in school and to appropriately integrate society's values and belief structures. Very little encouragement is given to right brain activity; it is in fact discouraged by society at large.

REGULATING THE BODY'S QI

The first stage in circulating and cultivating the Qi is to regulate the Yang or Fire Cycle of the Microcosmic Orbit. This allows the trapped emotions within the tissues to be released. This is initiated through mental concentration, focusing the flow of the Qi up the back and down the front of the body. It is extremely important to allow the trapped energy to release itself naturally from the body through the Fire Cycle of the Microcosmic Orbit. Otherwise, trapped emotions deep within the tissues can cause Qi deviations within the body, which may lead to energetically induced psychosis.

When regulating the Microcosmic Orbit, there are three primary methods of energetic cultivation that harmonize the body's Jing, Qi, and Shen. They relate to the sun (Fire and Heaven), moon (Water and Earth) and stars (Wind and Man).

THE FIRE PATH OF THE MICROCOSMIC ORBIT

The Yang or Fire Path is the most popular method of cultivating energy along the Small Heavenly Cycle or Microcosmic Orbit (Figure 41.3). Because it joins together the body's Yin and Yang rivers of Qi, which regulate the Twelve Primary Channels, it is considered the foundational meditation for the Internal Elixir Cultivation methods. The circulation of Postnatal Qi is generated from the Acquired Essence (food, air, and water). In this cycle, the Qi moves up the Governing Vessel and down the Conception Vessel, and is considered the ascension of Yang or the opening of the Fire Channel. The initial goal is to circulate the Fire energy from Yang to Yin to convert Jing to Qi and then to Shen. The Yang (Fire) Qi supports awareness of the emotional side of consciousness.


Exhale down the Conception Vessel.
Inhale up the Governing Vessel.
Lower Dantian

Figure 41.3. The Fire Path of the Microcosmic Orbit flows up the back and down the front of the body.

The Heart and Middle Dantian are considered the House of Shen; Fire and passion (Qi that manifests as emotions) and are related to the flow of the Conception Vessel. The Kidneys and Lower Dantian are considered the House of Jing, Water and pleasure and are related to the flow of the Governing Vessel. It is important to use Reverse Breathing while uniting the Heart's Fire and Kidneys' Water, to cause the alchemical transformation of Jing into Qi in the lower abdomen.

When moving the Qi along the Governing Vessel, practitioners must move the energy through the Five Gates (see Chapter 30). The energy first gathers at the Lower Dantian, then overflows into the Governing Vessel, collecting, building, and then passing through to the next gate, one gate at a time. As the energy gathers at these gates, the Qi and Blood begins to Heat and vibrate the tissues. This energetic reaction affects the patient's emotions that correspond to or are embedded in each specific gate, causing a powerful emotional release. As the Qi passes through to the next gate, a new set of emotions is experienced, then released.

THE JIAJI POINTS' EFFECT ON THE GOVERNING VESSEL'S ENERGETIC FLOW

Jia translates to mean "besides." Ji translates as "the spinal column." These points are located lateral to the lower border of each spinous process of the cervical, thoracic, and lumbar vertebrae. Each point has its own Luo pathway (energetic channel), which intersects with the spine and connects to the Jiaji point located on the opposite side of the Governing Vessel. It is believed that one pair of the ascending Governing Vessel's Luo Channel intersects and connects to all of the Jiaji points along the spine.

This being the case, when the two energetic flows from the Jiaji points (via the Luo pathways) are superimposed, the reaction causes a crisscrossing and intertwining of Qi flow, which resembles the intertwining energies of the caduceus or double snakes.

THE TWELVE EARTHLY BRANCHES' RELATIONSHIP WITH THE MICROCOSMIC ORBIT

Within the Fire Cycle of the Microcosmic Orbit, there are twelve channel points located along the Governing and Conception Vessels which relate to the Twelve Earthly Branches and the waxing and waning of the Yin and Yang cycles (see Chapter 11). The Fire phase of the Microcosmic Orbit starts at the Zi branch located at the Sheng Si Qiao area at the root of the penis in men and at the vagina in women. Moving up the back of the body, there are four phases of Qi ascent in the Governing Vessel. The four phases are: from Zi to Chou, from Zi to Yin, from Zi to Chen, and from Zi to Si. The Mao point is one of the four cardinal points (along with Zi, Wu, and You) and is a point of purification. The path up the Governing Vessel cleanses the energy through this point of purification.



Figure 41.4. Twelve Earthly Branch Relation with the Microcosmic Orbit: the main channels of the back and front of the body correspond to the ecliptic path of the sun. These twelve special energy points are associated with the Twelve Chakra Gates.

When the energy reaches the Wu point at the top of the head (also known as the Ascending point), it stays there briefly before beginning the descent of Yin in the Conception Vessel. The descent down the Conception Vessel purifies the energy (Figure 41.4).

While at the perineum and Zi point in the orbit, the Yang Qi begins to develop as the Yin Qi reaches its zenith. Once the energy reaches the Mao point at the middle of the back, the Yang energy has developed fully and begins to prosper. At the Wu point at the top of the head, the Yin Qi begins to develop while the Yang Qi reaches its zenith. This point represents the turning point from Yang to Yin.

If the energy is to flow properly down the Conception Vessel, there must be an opening of the energy centers via a connection with the Shen. This purification of energy commences at the Wu point when the Yang Qi turns to Yin Qi. While the Earth's daily orbit around the sun has the same Yin-Yang transitions, the body absorbs the Yang energy during the hours of Zi and Wu, and expels Yin energy during the hours of Mao and You.

At the Zi hour (11 p.m.–1 a.m.), the Jing naturally collects at the Sheng Si Qiao point at the root of the penis (prostate area) in men causes a natural erection while the man is sleeping. This hour also marks the commencement of the Yang half of the day. This period of the day is the best for collecting Jing and, thus, is the best time to perform Wuji standing practice.

CONTRAINDICATIONS

Whenever the practitioners are weak, it is important that they practice Natural Dantian Breathing and avoid practicing the Microcosmic Orbit. If patients attempt to practice Circular Breathing while in a depleted state, the Qi may become trapped in their head causing Qi Deviations, and initiating more problems. Circular Breathing is achieved by guiding the Qi in a circular pattern through even inhalation (e.g., up the spine) and exhalation (e.g., down the front of the body).

THE WATER PATH OF THE MICROCOSMIC ORBIT

The Water Path is trained only after the completion of the Fire Path circulation exercise. After the patient's Prenatal Qi has been cultivated and accumulated to a substantial level, the patient may lead the Qi up the Conception Vessel and down the Governing Vessel (Figure 41.5).

This is opposite the direction of the flow of the Fire Path, and is considered the ascension of Yin or the opening of the Water Channel. The purpose for the Water Path circulation is to change, regulate, and charge the body's Yuan Shen. The Water cycle supports the perceptional side of consciousness, cools down the body's overheated Yang Qi, and regulate the Qi circulation of the Fire Path to rebalance the body.

THE WIND PATH OF THE MICROCOSMIC ORBIT

The Wind Path of the Microcosmic Orbit is the third method of circulation and requires practitioners to lead energy up the center of their body through the Taiji Pole (Figure 41.6). This energy pathway flows up through the Marrow of the spine, through the brain, and washes over the falx cerebri into the pineal and pituitary gland. It then descends down along the Conception Vessel and back into the Lower Dantian.

The purpose of the Wind Path is to increase divine perception (by accessing the energy of the Wu Jing Shen), and to regulate the body's glandular and endocrine systems, to enable the practitioner to slow down the aging process.


Exhale down the Governing Vessel.
Lower Dantian
Inhale up the Conception Vessel.

Figure 41.5. The Water Path of the Microcosmic Orbit travels up the front and down the back of the body, ending at the Lower Dantian.


Exhale down the Conception Vessel.
Inhale up the center of the spine.
Lower Dantian

Figure 41.6. The Wind Path of the Microcosmic Orbit travels up the center of the spine into the brain and third-eye point, down the front of the body, ending at the Lower Dantian.

MEDICAL QIGONG PRESCRIPTIONS

The following exercises are taken from various hospitals, universities, and institutes of Medical Qigong. These regulation prescriptions are used throughout China.

DESCEND THE QI AND CLEANSE THE ORGANS

This exercise was developed to utilize the body's Hun-Yuan Qi (the body's internal combined organ energy) to flush and cleanse the Triple Burners and the Five Yin Organs. This is a purging exercise, used to:

- eliminate the body's Turbid Qi,
- unclog the channels and collaterals,
- wash the bones,
- transform the Marrow, and
- combine the remaining pure energy with the body's Yuan Qi.

It can be prescribed for patients with Excess conditions to descend the Liver's or Heart's Fire.

PULLING DOWN THE HEAVENS

This exercise requires the focus of energy to flow down the body in three directions (front, center, and back) to complete one set.

1. Begin in a Wuji posture, with both feet facing forward, a little wider than shoulders width apart. Both hands are at the sides of the body. The spine is kept straight, with the body relaxed and centered (see Chapter 15 for proper alignment). Stand with the eyes focused on the horizon. Pull the Qi from the horizon into the eyes and down to the Lower Dantian, filling the entire body. Hold this posture for one to three minutes (Figure 41.7).
2. Inhale through the nose. With the palms facing downward, begin to scoop the energy from the Earth into the body, gathering and absorbing the environmental energy. Focus on slowly filling the body with Earth Qi while moving the hands upwards to about waist level (Figure 41.8).
3. Continue inhaling, turning the palms to face the Heavens and drawing both hands upwards at a forty-five degrees angle. As both palms continue to move upwards, begin pulling in and absorbing the Heavenly Qi while guiding the hands above the head. Complete the inhalation with the arms above the head, palms facing the top of the head. Pause when the hands are above the Baihui area (Figure 41.9).
4. Exhale through the nose, and begin descending the palms in front of the body. Allow the palms to face the body and direct the Qi flow through the head and throat area (Figure 41.10).
5. Imagine the energy continuing to pour down through the chest and abdominal areas (Figure 41.11).
6. While exhaling, slowly lower the hands in front of the body in one continuous movement, until they reach just above the knees (Figure 41.12).
7. Inhale and begin the sequence again. Each time the hands pass in front of the body, exhale and imagine the Qi being emitted through the hands into the tissues. Three passes over the front of the body equal one set, practice 36 sets. The energetic pathway of each set is explained as follows:
    a. The first pass begins by leading the Qi down the front of the body from the Baihui area. Each palm facing the body divides the energy into two rivers, which flow from the top of the head, over the ears, and down the throat. Continue guiding the two rivers down the front of the chest, joining again at the navel. From there lead the Qi down into the Huiyin CV-1 point at the perineum, then separate them again into two rivers which continue to flow down the Yin channels on the inside of each leg, ending at the Yongquan Kd-1 point at the bottom of each foot.
    b. Start the next pass at the middle of the head above the Baihui area. Lead the Qi down the center of the body, and absorb the Heavenly Qi as it passes through all the body's internal organs, till it reaches the Lower Dantian area. From the Lower Dantian divide the energy into two rivers and descend the Qi down the center of the legs ending



Figure 41.7. Wuji Posture



Figure 41.8. Pulling Down the Heavens (A)



Figure 41.9. Pulling Down the Heavens (B)



Figure 41.10. Pulling Down the Heavens (C)



Figure 41.11. Pulling Down the Heavens (D)



Figure 41.12. Pulling Down the Heavens (E)

at the Yongquan Kd-1 point at the bottom of each foot.

c. The final pass likewise begins at the top of the head, at the Baihui area. Imagine the energy flowing like a river, down the midline of the back of the head and back, until it reaches the Mingmen GV-4 point. From there it divides into two rivers, descending into the Huantiao GB-30 point at the side of each buttock, and continues to flow down the outside of each leg and ends at the Yongquan Kd-1 point at the bottom of each foot. As the Qi descends (on each pass), it washes the organs from the top of the head (Baihui point) to the bottom of the feet.
d. To end the exercise, relax the whole body and return to the Wuji posture, allowing the Qi to return to its origin. As the Qi descends through the body, imagine the environmental energy fusing with the body's Yuan Qi, forming a mist and dew. Imagine this mist slowly flowing down (from top to bottom) and bathing, cleansing, and purifying the entire body. As the mist descends, if a certain organ is diseased, pause for a while to bathe the area with the vapor before continuing the flow of energy. Consciously disperse the pathogens out the extremities.

GATHERING QI IN THE UPPER AND LOWER DANTIANS

This exercise is designed to strengthen, tonify, and regulate the body's internal organs and energetic fields. It is excellent for promoting and maintaining health, and can be used for tonifying the Kidneys, as well as to treat impotence, premature ejaculation, lumbago, lower back problems, and pelvic inflammatory disease (PID). When treating PID, use reverse breathing with Static Qigong training.

This is a tonification exercise, used to increase the production of Jing (sperm or ovary energy), transforming it into Qi, and to lead the Jing up the spinal cord to support the brain, as well as nurture the bone marrow. This exercise adds Fire to the Mingmen, simmering the condensation of energy within the Kidneys. When the Kidney (Water) and Heart (Fire) energies are sufficient, their energies merge to form the True Qi which cultivates one's nature, spirit, and life. This exercise also assists the Microcosmic Orbit and establishes a base for refining and gathering energy in the Upper and Lower Dantians and Huiyin.

GATHERING QI IN THE UPPER DANTIAN

Begin from a Wuji posture. Inhale, as both hands gather energy while moving up the sides of the body and embrace the Qi into the Upper Dantian. Pause and exhale while separating the hands (Figure 41.13).

Inhale and imagine the middle fingers of each hand gathering the Heaven and Earth Qi into the Upper Dantian. Imagine the body absorbing these energies through the Yin Tang point (Third Eye), into the pineal gland at the center of the brain. Imagine the light of the Upper Dantian getting brighter as the energy begins to increase (Figure 41.14). Repeat this exercise nine times.

Upon completion, focus on the Upper Dantian and begin to gather and fuse the body's Yuan Shen along with the collected Heaven and Earth energies into one energy. As this energy collects, imagine it forming into an energetic ball of white light and allow the hands to guide the light downward into the Lower Dantian.

During the process of descending the Qi from the Upper to Lower Dantian, the focus should be on feeling, guiding, listening, and seeing the energy traveling downward. As the energy of the Shen descends, the Jing energy naturally ascends. This descending and ascending action of Jing and Shen energies cultivates an abundant amount of Qi in the Lower Dantian. After the Qi has been gathered and stored there, pause a moment, allowing the energy to settle. Then proceed to regulate the Lower Dantian.

GATHERING QI IN THE LOWER DANTIAN

Both hands sink down to waist level and form an embracing posture in front of the navel. Inhale while slowly drawing the palms inward towards the navel, gathering the Qi into the center of the Lower Dantian. Pause a moment and relax, allow-



Figure 41.13. Gathering Qi in the Upper Dantian (A)



Figure 41.14. Gathering Qi in the Upper Dantian (B)



Figure 41.15. Gathering Qi in the Lower Dantian (A)



Figure 41.16. Gathering Qi in the Lower Dantian (B)


Nose
Governor Channel
Back
12
Right Thrusting Channel
Middle Thrusting Channel
Right
9
3
Left
Left Thrusting Channel
6
Front
Functional Channel

Fig. 7.1 *Four Psychic Channels*

Procedure for Opening the Thrusting Channels

The Thrusting Channels need the tremendous energy of good virtue to help them open. Begin by forming a pearl of virtue energy. With your continued, conscientious practice of the compassion fire and the fuse the inside with the outside energy to form the pearl, you will be able to assimilate the energies into a new and stronger pearl, a pearl that responds to your intention. This means that all you need do to form a new pearl is concentrate on the cauldron and the pearl in it, and on the front, back, left and right pakuas and fuse inside with the outside energy. Control of the internal weather, senses, organs and emotions will be possible in as little as a few seconds. You do not have to go through all the steps of chanting and collecting the energies every time you do the Fusion practice. It is helpful and creates a stronger experience if all the steps are taken. So the first step to opening the Thrusting Channels is to construct the pakuas, chant the eight directions, form the collection points of the Physical Body, the Energy Body and the Universal Body, and fuse them together into the pearl.



Figure 41.17. Gathering Qi in the Huiyin Area (A)



Figure 41.18. Gathering Qi in the Huiyin Area (B)



Figure 41.19. Gathering Qi in the Huiyin Area (C)



Figure 41.20. Gathering Qi in the Huiyin Area (D)

ing the energy to settle, then exhale and separate the hands (Figure 41.15).

Inhale and imagine the body absorbing the universal and environmental energies in through the navel and Lower Dantian areas (Figure 41.16). Repeat this exercise nine times.

Imagine the Lower Dantian as a reservoir, storing but never overflowing. The expansion and contraction of the abdominal muscles creates a "beating and drumming" movement which improves the abdominal muscles' elasticity while massaging the digestive system. The "beating and drumming" movement strengthens and increases peristalsis.

GATHERING QI INTO THE HUIYIN AREA

Continuing from the last posture, both hands begin to move downward from the Lower Dantian (Figure 41.17).

As you inhale, bend over and imagine scooping the Earth energy along the inside of the legs, directing the Qi through the three Yin channels into the body's Huiyin, coccyx, and Mingmen areas. While inhaling, it is important to pull up on the anal sphincter and imagine gathering the Earth Qi directly through the lower body's orifices (testicles and penis, or vagina) into the Kidneys and Mingmen area (Figure 41.18).

Move both hands from the insides of the thigh, groin, and lower abdomen backward, along the Belt Vessel, expanding the energy into the Kidneys and Mingmen area. Hold this posture and exhale, imagining the Qi flowing into the Kidneys and Mingmen areas (Figure 41.19).

Next, circle the Qi down to the Lower Dantian and Huiyin area. Pause for a moment to allow the Qi to settle and root (Figure 41,20). Repeat this exercise nine times and end this exercise.

ROLLING THE BALL WITH BOTH PALMS

The purpose of this exercise is to regulate the Yin and Yang balance of energy in the body. This exercise also causes the capillaries along the Microcosmic Orbit to open up, improving the Qi circulation and nerve stimulation in the extremities.

It is excellent for purging and regulating emotions from the Heart and Yellow Court, as well as for descending Rebellious Lung Qi downward and purging Yang Qi Rising.

SHAKING THE SUN AND MOON

Begin from a Wuji posture. Both arms raise up in front of the shoulders, palms and fingertips pointing upward. Imagine the left palm embracing the sun and the right palm embracing the moon. Vigorously shake the palms, focusing the mind's intention on the center of the palms and fingers (Figure 41.21).

Place both palms in front of the chest and Middle Dantian area, and imagine the energy of the sun and moon melting into each other, creating a huge ball of energy. Make sure the eyes focus on the center of the ball (Figure 41.22).

ROLLING THE BALL

Wait until you can feel the sensation of the energy ball before beginning the rotations. Imagine the energy ball in the hands and the energy ball in the Lower Dantian blending naturally into one energy, simultaneously rotating and rolling together both internally and externally.

Begin rolling the ball, keeping the mind's intention focused on the center of each palm. Imagine the ball is slowly growing between the hands. Roll the ball, with the hands opposite each other, (one hand is up while the other is down), eighteen times in a clockwise direction, then reverse the direction and repeat another eighteen times (Figure 41.23). After the last rotation, relax the arms and return to Wuji posture.



Figure 41.21. Shaking the Sun and Moon (A)



Figure 41.22. Shaking the Sun and Moon (B)

OPENING AND CLOSING THE UPPER, MIDDLE, AND LOWER BURNERS

This exercise is used to regulate the body's Yin and Yang energy, tonify the Yin organs, calm and harmonize the Yang organs, Regulate the Triple Burners, and help open the Conception and Governing Vessels. This is an excellent exercise for purging and regulating Excess conditions within the Triple Burners, as well as for purging the patient's Liver Fire.

There is an ancient Chinese saying, "Open, close, and come and go, one hundred illnesses will be healed." When opening, the Qi circulates into the muscles. When closing, the Qi sinks and gathers into the bones. The purpose of this exercise is to train the mind's intention, making it easier to increase the body's external field of Wei Qi.

OPENING AND CLOSING THE UPPER BURNER

Begin from a Wuji posture. Both arms raise up to shoulder level. Vigorously shake the hands, palms facing down. Before opening and closing the Upper, Middle and Lower Burner areas, the awareness must settle in the Laogong area (center of the palms) for a few minutes. Wait until heat



Figure 41.23. Rolling the Ball with Both Palms (A)



Rolling the Ball with Both Palms (Side View)



Figure 41.24. Vigorously Shake the Hands



Figure 41.25. Open and Close the Upper Burner (A)



Figure 41.26. Open and Close the Upper Burner (B)



Figure 41.27. Open and Close the Middle Burner (A)



Figure 41.28. Open and Close the Middle Burner (B)



Figure 41.29. Open and Close the Lower Burner (A)



Figure 41.30. Open and Close the Lower Burner (B)

is felt in the center of the palms before beginning (Figure 41.24).

After a while, bring both hands close to each other in front of the throat and manubrium sterni area (the upper segment of the sternum). Both palms face each other, with the fingers facing upwards. Pause a moment, focusing the mind's attention on the center of the palms, forming an energetic ball (Figure 41.25).

Slowly begin to open by pulling the arms apart, while imagining the energy between the center of the palms stretching like warm taffy. When the hands separate and open, the mind and body (chest and abdomen) also open. Slowly begin to close by bringing both palms together, pushing and condensing the stretched energy to form an energetic ball. When the hands close, the mind and body close by removing the attention away from the outside world (Figure 41.26).

When inhaling, imagine extending the fingers deep into the body and the Qi pouring deep into the tissues. When exhaling, separate the hands while imagining the Excess Heat and toxic energy being purged from the body. Repeat the exercise eighteen times.

OPEN AND CLOSE THE MIDDLE BURNER

Both hands sink down in front of the diaphragm and xiphoid process (just above the navel). Pause a moment, keeping the eyes on the energy ball and an imaginary line which connects the inner Laogong Pc-8 points at the center of the palms (Figure 41.27).

Slowly begin to open by pulling the arms apart, while imagining the energy between the center of the palms stretching like warm taffy. While exhaling, separate the hands while imagining the Excess Heat and toxic energy being purged from the body (Figure 41.28).

Slowly close by bringing both palms together, forming an energetic ball as you push and condense the energy. While inhaling, imagine extending the fingers deep into the body and the Qi pouring deep into the tissues. Repeat the exercise eighteen times.

OPENING AND CLOSING THE LOWER BURNER

Both hands sink down in front of the reproductive organs and perineal area. Pause a moment, keeping the eyes on an imaginary line which connects the inner Laogong Pc-8 points at the center of the palms (Figure 41.29).

Slowly begin to open by pulling the arms apart, imagining the energy between the center of the palms stretching like warm taffy. When exhaling, separate the hands while imagining the Excess Heat and toxic energy being purged from the body (Figure 41.30).

Slowly close by bringing both palms together, forming an energetic ball by pushing and condensing the Qi. While inhaling, imagine extending the fingers deep into the body and the Qi pouring deep into the tissues. Repeat eighteen times.

To end the exercise, draw the Qi back into the Lower Dantian, and return to a Wuji posture.

SUN AND MOON ROTATING TECHNIQUE

This exercise will massage the internal organs of both the Heart and the Lungs. In Medical Qigong, the sun is sometimes referred to as the energy of the Heart, which is the considered the master of the three Yang energies. The moon pertains to the Lungs, which are the masters of the three Yin energies. Through the harmony of these dual powers the body's Yuan (Original) Qi is born. This exercise increases the elasticity of the Heart muscles and arteries and improves Blood circulation. It also flushes the Eight Extraordinary Vessels, increases vitality, and causes the upper half of the body to become lighter while making the lower half more solid.

This exercise can also be used in conjunction with the healing sound "Shang" to treat Lung diseases (i.e., asthma and chronic bronchitis), as well as breast cysts and tumors by purging Toxic Qi from the tissues of the Lung.

ROTATING THE PALMS

Begin from a Wuji posture, start by vigorously shaking the hands and then rubbing the palms together (Figure 41.31).

Place both hands on the chest, and draw the heat from the center of the palms into the chest, inhaling three times. Once the chest has absorbed a certain amount of heat, both palms begin to ro-



Figure 41.31. Vigorously Shake the Hands



Figure 41.32. Sun and Moon Rotating Technique (A)



Figure 41.33. Sun and Moon Rotating Technique (B)



Figure 41.34. Expanding and Contracting the Rings (Forward-A)



Figure 41.35. Expanding and Contracting the Rings (Forward-B)



Figure 41.36. Expanding and Contracting the Rings (Forward-C)

tate up the center line of the chest. The rotation of the arms forms two circles, that circulate the energy from the inside to the outside of the breast. The focus of the intention should be on the "chest opening and the back closing" of the thorax. Repeat this exercise 18 to 36 rotations, depending on the severity of the condition (Figure 41.32).

Next, rotate the circles in the opposite direction, moving from the outside towards the center line of the chest and then down, circulating the energy from the outside to the inside of the breast. Repeat 18 to 36 rotations, depending on the severity of the condition (Figure 41.33).

When the rotations are completed, the middle fingers of both hands slightly press the Conception Vessel downward to descend the Qi into the Lower Dantian. Rub the abdomen three times and resume a Wuji posture.

EXPANDING AND CONTRACTING THE RINGS

Expanding and contracting the rings refers to the expansion and contraction of the spinal vertebra. This exercise reinforces the flow of the Microcosmic Orbit, invigorates and strengthens the Yuan Qi, aids in transforming Jing to Qi, and strengthens the entire spine. The patient's coordination and balance are also positively affected.

While performing this exercise, the body should move like a "dragon playing in the ocean waves" by appearing and disappearing, rising and sinking, and twisting and coiling. The goal is to stretch and loosen the spinal column, rib articulations, and the back. This will cause the body's Fire to descend and Water energy to ascend naturally through the body's center channels.

This exercise can be modified into a stationary position for convalescing patients or patient's confined to a wheelchair. The patient bends forward, allowing the spine to slowly stretch, shifting the body to a forty-five degree angle.

Begin this exercise from a right Bow Stance (weight is shifting 70% to the back, 30% forward) with both hands positioned in front of the Lower Dantian (Figure 41.34).

Both hands raise upward and stretch forward, creating an arc and stretching the spinal column. When extending and stretching the spine forward, imagine the Earth Qi traveling up the back leg, through the spine and Governing Vessel to the top of the head (Baihui point), and extending down to the Yin Tang and both Laogong points at the center of the palms (Figure 41.35).

While extending the energy outward, use intention to connect with the Heavenly Qi, the energy of the horizon, or a tree (Figure 41.36).

As both hands withdraw, shift the weight to the back leg, allowing the spinal column to contract. As you shift your weight back to the starting position, imagine drawing Qi up from the Earth into your body. Repeat nine times. End in the Wuji posture. Then switch directions by switching the position of the feet and repeat the entire sequence while reversing the rotation.

To perform the second half of the exercise, shift the body's weight forward and begin moving the body in the reverse circular direction (Figure 41.37).

Imagine the Heaven Qi traveling from the Baihui point down the Conception Vessel and out the front foot, extending deep into the Earth (Figure 41.38).

As the weight shifts back, imagine drawing Qi from the Heavens back into the body through the head and hands (Figure 41.39).

Sink the Qi deep into the Earth allowing the body to be cleansed and purified (Figure 41.40). Repeat the exercise nine times. End in the Wuji posture. Then switch directions and repeat the entire sequence.

DESCENDING THE YANG AND ASCENDING THE YIN TECHNIQUE

This exercise cultivates Qi in the channels and collaterals of the lower body, aids the free flow of Qi to the Lower Dantian, strengthens the Kidneys, Spleen, Stomach, and the Liver Qi, while regulating the Gall Bladder Qi.

It is an excellent exercise for pulling the Earth Qi (Spleen Qi) up while sinking the Stomach Qi, and is good for treating problems such as irritable bowel syndrome and problems caused from Excess Heat in the Middle and Lower Burners. In order to treat such conditions, the exercise should be performed for twenty minutes, twice a day.



Figure 41.37. Expanding and Contracting the Rings (Reverse-A)



Figure 41.38. Expanding and Contracting the Rings (Reverse-B)



Figure 41.39. Expanding and Contracting the Rings (Reverse-C)



Figure 41.40. Expanding and Contracting the Rings (Reverse-D)

This exercise can furthermore be used in conjunction with the healing sound "Yu" to treat reproductive organ diseases (i.e., uterine and ovarian cysts, tumors, and cancer, as well as prostate cancer). The patient should practice a total of one to four hours each day, depending on the severity of the condition.

Begin from a Wuji posture and embrace the abdomen (Figure 41.41).

Gather Qi into the Lower Dantian and turn towards the left, both hands move into the Huantiao GB-30 point at the side of the hip (Figure 41.42).

Both hands slowly descend the three Yang channels down the outside of the left leg with a "pushing" action, ending on the outside of the left foot at the Bubbling Well point (Kd-1) at the bottom of the foot. As both hands reach downward to the foot, stretch the body and allow the waist to follow the descending Qi with a downward crouching movement (Figure 41.43).

Next, shift the hands around the foot and begin ascending the three Yin channels with the hands inside the left leg. Continue the movement all the way up into the Huiyin point, pubic bone, and Lower Dantian area with a "pulling" and "drawing" action. Pull the anal sphincter upward while drawing the Earth Qi into the body. When both hands raise and gather Qi upward, the body and waist must follow the ascending and rising movements (Figure 41.44).

Pause for a few seconds and let the Qi settle into the Lower Dantian (Figure 41.45).

Shift the body's weight, and repeat the entire sequence on the opposite leg. The turning of the waist should match the movements of the thighs. The toes should naturally grasp the ground and the soles of the feet should feel full of Qi. Repeat nine times on each leg, and end in a Wuji posture.

End the exercise by ascending and descending the Earth Qi through both legs.

From a Wuji posture, both hands embrace the abdomen to gather the Qi of the Lower Dantian and to separate the energy into two balls of energy (Figure 41.46).

Both hands then slowly descend the outside Yang channels of each thigh, all the way to the outside of the feet, ending at the Bubbling Well points (Figure 41.47).

Move the hands along the front of the feet, toward the inside of the foot, slowly ascending the inside Yin channels of each thigh all the way up the body into the Huiyin and Lower Dantian areas (Figure 41.48)

Pause and allow the Qi to settle in the Lower Dantian, then begin again (Figure 41.49). Repeat



Figure 41.41. Descend the Yang and Ascend the Yin Technique (Single-A)



Figure 41.42. Descend the Yang and Ascend the Yin Technique (B)



Figure 41.43. Descend the Yang and Ascend the Yin Technique (C)



Figure 41.44. Descend the Yang and Ascend the Yin Technique (D)



Figure 41.45. Descend the Yang and Ascend the Yin Technique (E)



Figure 41.46. Descend the Yang and Ascend the Yin Technique (Double-A)



Figure 41.47. Descend the Yang and Ascend the Yin Technique (B)



Figure 41.48. Descend the Yang and Ascend the Yin Technique (C)



Figure 41.49. Descend the Yang and Ascend the Yin Technique (D)

this exercise 18 times, then return to the Wuji posture and end the exercise.

TURNING AND WINDING THE BELT VESSEL TECHNIQUE

This tonifying exercise is divided into two methods: the Small Turning and Winding, and the Large Turning and Winding techniques. Each method of exercise causes a different action between the rotation of the energy's circle, the form's circle, and the internal turning action of the Lower Dantian.

Practice the Small Turning and Winding technique first, then proceed to the Large Turning and Winding technique. The small method uses a 180 degree semicircular rotation in addition to the Belt Vessel and Lower Dantian circle rotation.

When practicing the Large Turning and Winding method, the patient's mind must imagine a 360 degree circle rotation of the Belt Vessel. The body moves externally in one direction, while the energy in the Lower Dantian rotates in the reverse direction.



Figure 41.50. Small Turning and Winding (A)



Figure 41.51. Small Turning and Winding (B)



Figure 41.52. Small Turning and Winding (C)



Figure 41.53. Large Turning and Winding (A)



Figure 41.54. Large Turning and Winding (B)



Figure 41.55. Large Turning and Winding (C)



Figure 41.56. Large Turning and Winding (D)

The back and forth, side to side movements of the Turning and Winding action move the body's Qi, and stimulate the energy moving within the Belt Vessel's Qi circle. This energy circle fuses with the external rotation of the hands, allowing the energy from both external and internal Qi circles to be absorbed into the Lower Dantian. Once absorbed into the Lower Dantian, the Qi expands into the body's center core and blends with the Yuan Qi. This strengthens the waist, spine, and enables the Middle Burner's Qi to pervade through the upper and lower parts of the body. This exercise also develops strong and vigorous Kidneys and thus promotes the transportation of the Kidney's Jing and Qi.

SMALL TURNING AND WINDING TECHNIQUE

From a Wuji posture, step forward with the left foot to form a Leaning Horse stance. Raise both palms to waist level, in front of the Lower Dantian, with the palms facing the ground (Figure 41.50).

Inhale and shift the body forward towards the right direction and begin to rotate, turning and twisting the body in a clockwise direction. Imagine gathering the Earth's Qi into the Lower Dantian (Figure 41.51)

Exhale, but allow the mind to focus on absorbing the Earth Qi into the Lower Dantian. Pause for a minute, allowing the Qi to settle after filling the Lower Dantian (Figure 41.52). After nine circle rotations switch directions, moving in the opposite direction nine times.

LARGE TURNING AND WINDING TECHNIQUE

Bring the hands to the right side of the Mingmen and right Kidney area, while placing the mind's intention onto the Lower Dantian and navel area (Figure 41.53).

Inhale, as you extend both hands forward, and begin gathering the Earth's Qi (Figure 41.54).

Begin to circle rotate a 270 degree turn towards the left, while internally the energy of the Lower Dantian circles in the opposite direction to the right (Figure 41.55). Imagine the navel to be the center of the external circle and the Belt Vessel to be the internal circle. The mind's intention leads the energy which guides the hands and moves the body and the waist. The hand movements and center of weight shifting must be synchronized.

Exhale and gather the Earth's Qi into the left Kidney and Mingmen area; repeat nine times. Allow the Qi to fill the Mingmen and Kidneys, then switch directions for nine times (Figure 41.56). End in the Wuji position.

OPENING AND CLOSING THE HEAVEN AND EARTH TECHNIQUE

The purpose of this exercise is to cultivate and strengthen the Lower Dantian energy by blending it together with the Heaven and Earth Qi using the Beating and Drumming the Qi method of Qi cultivation. This cultivation method roots and stabilizes the body, causing the Five Hearts to return to their origin. The Five Hearts (sometimes called the Five Palms) are as follows:

- The Heart of the Baihui area (the Crown Chakra)
- The Hearts of each Laogong area (the palm Chakra)
- The Hearts of each Yongquan area (the bottom of each foot Chakra)

When the energy of the Lower Dantian disperses through the body, as the Mingmen pushes back, the Yuan Qi returns and gathers into the navel. This gathering and extending, back and forth action of energy of the Five Hearts transforms the body's Yuan Qi, strengthens the Yin and Yang energy, opens the body's channels, and encourages the merging of the Heart's Fire and the Kidneys' Water Qi. This method is divided into two techniques: Open the Heaven and Close the Earth, and Open the Earth and Close the Heaven techniques.

OPEN THE HEAVEN AND CLOSE THE EARTH

Begin from a Wuji posture with the left hand on the Lower Dantian and the right hand resting on top of it, both Laogong points face the navel (Figure 41.57).

Keep the mind's intention focused on the navel as the center base. Inhale as both arms raise up the center line of the body (Figure 41.58).

Extend the intention into the Heavens and begin to gather the universal Qi (Figure 41.59). Imagine Heavenly Qi descending and completely

The pearl will be thrust up from the perineum (or testicles in men). Each Thrusting Channel precisely penetrates the body.

Although it may seem difficult at first, using your beautiful pearl will help make it easier. Other aids such as pulling up the anus and inhaling help the energy move in each of the three Channels. Once you are able to pass the energy through the Channels, you will find that the energy will move by itself without assistance.

Note: You must be very careful and gentle with this procedure. If the energy reaches the heart and head too quickly using the Thrusting Channels, the heart will become congested and you may experience pressure. If the heart becomes congested and overheats with energy: (1) Do not thrust above the diaphragm and (2) Practice the Heart Sound. Do not overheat the heart, liver or head.

Initially the Thrusting Channels have approximately a one-half to one inch diameter. Once they are activated, they can become very wide. At first concern yourself with drawing the energy directly up. Later, when you have become familiar with the process, the energy can be spiraled up each route.

Seated Position

Like many other Universal Tao exercises, the methods of opening the Thrusting Channels are practiced from a seated position. Sitting on a chair with your feet touching the floor and your spine erect connects you with two important energy “wires”: Earth Energy and Heavenly or Universal Energy. The Energy Body you eventually create needs the ground wire of Earth Energy to hold and support it. Otherwise, you can become disoriented and lost. Once your are more in control of the energy you can practice standing, or lying down on a bed or the floor.


Figure 41.57. Open the Heavens and Close the Earth (A)


Figure 41.58. Open the Heavens and Close the Earth (B)


Figure 41.59. Open the Heavens and Close the Earth (C)


Figure 41.60. Open the Heavens and Close the Earth (D)


Figure 41.61. Open the Heavens and Close the Earth (E)


Figure 41.62. Open the Heavens and Close the Earth (F)


Figure 41.63. Close the Heavens and Open the Earth (A)


Figure 41.64. Close the Heavens and Open the Earth (B)


Figure 41.65. Close the Heavens and Open the Earth (C)


Figure 41.66. Close the Heavens and Open the Earth (D)


Figure 41.67. Close the Heavens and Open the Earth (E)



Figure 41.68. Collect the Qi and Return it to the Lower Dantian (A)



Figure 41.69. Collect the Qi and Return it to the Lower Dantian (B)



Figure 41.70. Collect the Qi and Return it to the Lower Dantian (C)

filling the body (Figure 41.60). Exhale and gather the Heavenly Qi deep into the body's center core (Figure 41.61).

Lead the energy from inside of the body's center core to the outside, imagining Heavenly Qi, like steam, releasing through the pores and filling up the body's external energy bubble like a mist (Figure 41.62). Repeat 18 times.

OPEN THE EARTH AND CLOSE THE HEAVENS

This is the exact reverse action of the Open the Heaven and Close the Earth technique. Begin from a Wuji posture with the left hand on the Lower Dantian and the right hand resting on top of it, both Laogong points face the navel (Figure 41.63).

Inhale and begin to separate the hands, moving them to the outside of the body (Figure 41.64). Imagine gathering the Earth's Qi into the body as the hands raise upwards towards the head (Figure 41.65). Exhale and gather the Earth's Qi deep into the body's center core (Figure 41.66).

Lead the energy from inside of the body's center core to the outside, imagining the Earth's Qi, like steam, releasing through the pores and filling up the body's external energy bubble like a mist (Figure 41.67). Repeat 18 times, then pause and relax, returning to the Wuji posture.

COLLECT THE QI AND RETURN TO THE LOWER DANTIAN TECHNIQUE

The purpose of this exercise is to gather both universal and environmental energy and to store it in the navel. This exercise is used for treating Deficient conditions.

COLLECT AND RETURN

Begin from a Wuji posture and step out to the right, forming a Horse Stance. The left hand swings to embrace the navel and Lower Dantian as the body shifts its weight and twists toward the right (Figure 41.68).

The body slowly begins to shift from side to side while the opposite hand gathers the universal and environmental energy, gathering and packing it into the navel and Lower Dantian area (Figure 41.69).

During the exchange of left and right hands collecting Qi, imagine that the body is swimming in water. Imagine the energetic consistency of the air, like water, following each arm as it moves, flowing into the center of a whirlpool located in the navel and Lower Dantian area (Figure 41.70). Repeat 18 times. End in Wuji posture.

QIGONG SELF-HEALING MASSAGE AND POINT THERAPY

Qigong Massage and Point therapy is usually practiced after the Qigong meditations and exercise prescriptions. It involves having the patient lightly massage or tap the skin, while extending Qi into the various channels, points, and tissues. These self-healing massage techniques are specifically designed to disperse stagnations and Excess conditions, as well as to activate and regulate the energetic flow within the body's external and internal channels, thereby increasing the energy flow.

These massage techniques can be practiced from either a lying, sitting, or standing posture.

WASH THE FACE

This exercise stimulates the skin and facial muscles. Begin from a Wuji posture. Shake the hands vigorously to remove any External pathogenic Qi. Then slap the palms and rub the hands together vigorously until they get hot. Gently place both hands over the eyes and inhale, absorbing the heat into the face and Upper Dantian. While inhaling, allow the Qi to enter the Taiji Pole.

Exhale and imagine the energy gathered in the Upper Dantian descending down the center of the body, flowing into the Lower Dantian. Perform this gathering and descending action three times.

Next, both hands begin to wash the face, in an outward circular motion. Allow the hands to massage the face, up from the nose, eyes, and forehead, down along the temples, cheeks, and across the chin and mouth, returning back to the nose. Perform this face massage technique for 9 breaths.

Shake the hands vigorously to remove any External pathogenic Qi, then proceed to the next exercise.

MASSAGE THE HEAD

Guide all ten fingers over the head and down over the back of the neck (this is called Ten Dragons Run Through the Forest). Repeat nine times. This can be performed either by touching or not touching the head (Figure 41.71).



Figure 41.71. Wash the Face and Massage the Head: After rubbing the hands to heat the palms, place both hands on the face and draw the heat in through the eyes and into the Upper Dantian (1). Next, comb the hair with the fingertips (2), and drain the excess Qi from the head and neck area (3).



Figure 41.72. Beating the Heavenly Drum

BEATING THE HEAVENLY DRUM

This exercise balances the air pressure in the eustachian tubes and ear canals, relieves tinnitus, helps prevent vertigo, relaxes the mind, helps to improve hearing, expels stagnant Qi collected at the back of the head (within the Jade Pillow), and also stimulates the pineal gland and Kidneys' Qi.

Begin by interlacing the fingers and place both hands on the back of the head. The palm of each hand should cover the ears. While compressing the ears, close your eyes and practice the Beating and Drumming thumping method at the back of the head in the rhythmic sequence of a heart beat. This causes relaxation and creates an altered, in-utero state of consciousness. The index fingers of each hand should thump the Jade Pillow (Bl-9) at the back of the occiput pass 36 times (Figure 41.72).

After thumping the back of the head, clench the teeth, close the mouth, and bend the body over. Exhale while bending over and bring the head between the legs. The legs are straight, waist and buttocks are relaxed, and both eyes look towards the back from in-between the legs, while holding the breath (Figure 41.73).

Next, raise the body up, inhale and again perform the Beating the Heavenly Drum sequence. Practice this exercise 14 times.



Figure 41.73. Bend the Body Over While Holding the Breath

PRESSING THE EARS

This exercise is used to enhance hearing, stimulate mental energy and also to stimulate the Kidneys' Qi. Use the Laogong areas at the center of each palm to compress the ears (like a plunger). Repeat this exercise nine times (Figure 41.74).

Next, move the right hand behind the head and pull the left ear (at a 45 degree angle) towards the back, with the left hand is placed on the Lower Dantian. Hold this posture for 9 breaths, then reverse for 9 breaths.



Figure 41.74. Pressing the Ears

RUBBING THE EYES

RUBBING THE EYES (SEQUENCE #1)

This exercise is good for enhancing Qi and Blood circulation to the eyes for improving vision, treating eye diseases (especially glaucoma), relieving fatigue (caused by eye strain), and also for stimulating the Liver Qi.

With both thumbs resting on the cheekbones, form two soft fists and, using the edge of the index knuckles, begin to massage in a circle the top of the eyelids (from the bridge of the nose out along the eyebrows). Next massage just bellow the bottom of the eyelids from the bridge of the nose. Alternate from top to bottom 18 times (Figure 41.75).



Figure 41.75. Rubbing the Eyes (Sequence 1)

RUBBING THE EYES (SEQUENCE #2)

With the thumbs still resting on the cheekbones, use the tip of the index fingers to massage the points around the eyes, from the inner corners of the skin, in a circular motion. Start rotating in a small circle, at the Bl-1 point. Circle nine times towards the inside, then nine times towards the outside, for a total of three breaths.

Next massage the middle of the eyebrows at the Extra Point Yu Yao. Then proceed to the outside of the eyes at the GB-1 point. (3) End at the base of the eyes at the St-1 point. Each area should be massaged 18 times (9 times towards the inside, then 9 times towards the outside) (Figure 41.76).



Figure 41.76. Rubbing the Eyes (Sequence 2)

MASSAGING THE NOSE

This exercise is performed to treat colds, reduce swelling of the sinus tissues, eliminate mucus from the airways, stimulate the sinus nerves, open the nasal passages, and also stimulate the Lungs' Qi.

Begin by making soft fists and use the sides of the thumbs to massage the sides of the nose at the LI-20 points in an up and down motion 9 times pressing inward, and then 9 times pressing outward (Figure 41.77).

Next, use the tips of the index fingers and press deeply at the base of the nose at the LI-20 points, for a period of ten seconds, then circle-massage for 18 rotations. Press deeply midway up the nose, on both sides at the Bitong points for a period of ten seconds, then circle-massage 18 times. Finally, both fingers press deeply at the upper point at the bridge of the nose at the Shangen points for ten seconds, then circle-massage 18 times.

CLICKING THE TEETH

This exercise is good for strengthening the teeth and gums, tonifying the jaw muscles, improving the Qi and Blood circulation to the gum tissues, and also to enhance the Kidneys' Qi. Clamp the jaws shut so that the teeth are pressing together and the jaw muscles flex. Click the teeth 36 times.

WAGGING THE TONGUE

This exercise is good for stimulating the salivary ducts beneath the tongue, and also for stimulating the Heart's Qi. Wag the tongue on the outside gums 18 times in one direction, 18 times in the opposite direction, then 18 times from the lower to upper palate, and finally, 18 times pressing the tip of the tongue against the back of the teeth (Figure 41.78).

SWALLOWING THE SALIVA

Saliva contains many kinds of enzymes which aid in digestion. In ancient China, this practice was sometimes called the Immortal's Water or Juice of Jade, because the saliva is energized during the Qigong meditation and believed to contain special healing properties.

To begin, inhale and swallow the saliva with a big gulp (three times), using the breath as a seal or bubble to enclose the air, then send it down the Conception Vessel to bathe the Five Yin Organs, ending at the Lower Dantian. It is important to tilt the head slightly forward (after inhaling) before swallowing the Immortal's Water.

WHIRLING THE NAPE AND TURNING THE NECK

The purpose of this exercise is to massage the thyroid and larynx as well as to stretch the muscles and tendons throughout the neck and cervical vertebrae.

To begin, place the back of the hands on the Kidneys. While relaxing, allow the head to relax and naturally hang, slowly rotating its motion to the left and right nine times (Figure 41.79).

Next, suspend the head and slowly twist the nape of the neck to the right and left direction nine times. While performing this exercise, focus the mind's intention on the Lower Dantian. When finishing, focus the mind's attention on the Bubbling Well points at the center of the feet.



Figure 41.77. Massaging the Nose



Figure 41.78. Wagging the Tongue

MASSAGING THE CHEST AND ABDOMEN

The purpose of this exercise is to disperse Excess Qi from the chest and abdominal area. This allows the body to balance the energy of the upper torso with that of the lower torso.

Beginning with the mind's attention focused on the Laogong areas at the center of each palm (Pc-8), brush the chest and abdomen downward nine times, starting from the collar bone and ending by the pubic bone (Figure 41.80).

MASSAGE TAPPING THE HANDS (LI-4)

Stimulating the Hegu or Joining of the Valleys points. The purpose of this exercise is to clear and activate the channels and collaterals, regulate, tonify and promote the circulation of Qi, to dispel pathogenic Wind, clear Fire and Heat, and to tranquilize the mind.

Begin by extending both arms in front of the body and allow both hands to collide into each other, thus tapping the Hegu points located between the thumb and first finger. Repeat nine times (Figure 41.81).

MASSAGE TAPPING THE FOREARMS (PC-6)

Stimulating the Neiquan or Inner Border Gate points. The purpose of this exercise is to regulate and tonify the Qi and Blood of the Heart and Stomach, to clear the Heart Fire, transform the Heart Phlegm, and to calm the Heart.

Begin by forming a hollow fist with the right hand and then lightly tap the Neiquan point located three fingers up from the wrist fold, on the lower left forearm area, nine times. Switch arms and repeat (Figure 41.82).

MASSAGE TAPPING THE ELBOWS (LI-11)

This exercise stimulates the Quchi or Crooked Pond points. The purpose of this exercise is to help dispel pathogenic Wind from the body, to regulate the Stomach and intestines, eliminate stasis, relax the muscles and tendons, lubricate the joints, and to cool the Heat in the Blood.

To begin, the right hand forms a hollow fist



Figure 41.79. Whirling the Nape and Turning the Head



Figure 41.80. Massaging the Chest and Abdomen



Figure 41.81. Massage Tapping LI-4

and lightly taps the Quchi point located at the end of the left elbow-fold, nine times. Switch arms and repeat (Figure 41.83).

MASSAGING UNDER THE ARMS (HT-1)

This exercise stimulates the Jiquan or Supreme Spring points. The purpose of this exercise is to regulate the Qi of the Lungs and Heart, promoting the circulation of Qi and Blood, as well as to regulate the blood vessels.

To begin, the right hand reaches under the left arm pit and circle massages nine times. Switch sides and repeat nine times (Figure 41.84).

MASSAGE TAPPING THE UPPER SHOULDERS (GB-21)

This exercise stimulates the Jianjing or Shoulder Well points. The purpose of this exercise is to regulate the body's Qi activities, disperse Liver Qi stagnation, extinguish Liver Wind, dispel Wind and Cold, redirect Rebellious Qi downward, and to dredge Excess Qi from all the Yang channels.

To begin, the right hand forms a hollow fist or soft palm and taps the left Jianjing point located on the upper ridge of the neck, while the left hand alternately taps the right Jianjing point. Both left and right tapping count as one set. Perform nine times (Figure 41.85).

MASSAGING THE ARMS

This exercise stimulates the six channels of the arms (the three Yang channels located on the outside, three Yin channels located on the inside).

Begin by placing the right palm on the inside of the left shoulder. Exhale and rub the entire arm from inside the shoulder and arm to the fingers. Next inhale and rub the entire outside of the arm from the fingers to the outside of the shoulder. Continue this movement for 18 breaths, then repeat on the other side (Figure 41.86).

MASSAGE TAPPING THE LOWER DANTIAN (CV-6)

This exercise stimulates the Qihai or Sea of Qi points. The purpose of this exercise is to energize and tonify the lower abdominal organs, as well as to stimulate the Qi of the Lower Dantian.



Figure 41.82. Massage Tapping Pc-6



Figure 41.83. Massage Tapping LI-11



Figure 41.84. Massaging Under the Arm Ht-1



Figure 41.85. Massage Tapping GB-21

Begin by stroking the chest, gathering the body's Qi down into the Lower Dantian. Using either soft fists, palms, or fingers, both hands lightly tap the Lower Dantian and navel area for three breaths (Figure 41.87).

MASSAGE TAPPING THE BACK OF THE WAIST (GV-4)

This exercise stimulates the Mingmen or Gate of Life point. This exercise stimulates and tonifies the Kidneys, adrenal glands, and the Mingmen. It is used to regulate the Governing Vessel, excite and strengthen Kidneys' Yang Qi, to replenish the Kidneys, as well as to strengthen the lower back and bones.

Begin by slightly leaning the body forward. Using the right and left soft palms or hollow fists, lightly tap the back of the waist, Mingmen and the Kidneys' area for three breaths (Figure 41.88).

MASSAGE TAPPING THE SIDES OF THE HIPS (GB-30)

This exercise stimulates the Huantiao or Jumping Circle points. The purpose of this exercise is to dispel Wind and Cold, reduce pain in the thighs and legs, as well as to strengthen the lower back, and tonify the lower extremities.

Using the right and left hollow fists or soft palms, lightly tap the hip bone Huantiao points nine times (Figure 41.89).

MASSAGE TAPPING THE THIGHS (GB-31)

This exercise stimulates the Fengshi or Wind's Market points. The purpose of this exercise is to dispel Wind and Cold, clear Heat, tonify the legs, reduce flaccidity and numbness of the lower extremities, and to transform Dampness.

Using the right and left hollow fists or soft palms, lightly tap the upper thighs at the Fengshi Points nine times (Figure 41.90).

MASSAGE TAPPING THE OUTSIDE OF THE KNEES (GB-34)

This exercise stimulates the Yanglingquan or Yang Mound Spring points. The purpose of this exercise is to relax the muscles and tendons, acti-



Figure 41.86. Massaging the Arm Channels



Figure 41.87. Massage Tapping the Lower Dantian



Figure 41.88. Massage Tapping the Mingmen GV-4



Figure 41.89. Massage Tapping GB-30

vate the flow of Qi and Blood in the channels and collaterals, relieve spasms and pain, clear away Damp-Heat, and disperse stagnant Liver and Gall Bladder Qi.

Using the right and left hollow fists or soft palms, lightly tap the outside of the knees at the Yanglingquan points nine times (Figure 41.91).

MASSAGE TAPPING THE INSIDE OF THE KNEES (SP-9)

This exercise stimulates the Yinlingquan or Yin Mound Spring points. The purpose of this exercise is to regulate and tonify the Spleen (Yang), Stomach (Yin), and Lower Burner, to resolve Dampness and Damp Heat, as well as to treat knee pain and problems with difficulty in urination.

Using the right and left hollow fists or soft palms, lightly tap the inside of the knees at the Yinlingquan points nine times (Figure 41.92).

MASSAGE TAPPING THE BACK OF THE KNEES (BL-40)

This exercise stimulates the Weizong or Entrusting Middle points. The purpose of this exercise is to relax the muscles and tendons, activate the flow of Qi and Blood in the channels and collaterals, cool the Blood to stop bleeding, transform Damp Heat in the Bladder and intestines and to strengthen the waist and knees.

Using the right and left hollow fists or soft palms, lightly tap the back of the knees at the Weizhong points nine times (Figure 41.93).

MASSAGE TAPPING BELOW THE KNEES (ST-36)

This exercise stimulates the Zusanli or Foot Three Miles points. The purpose of this exercise is to regulate the Stomach and intestines, facilitate the flow of Qi to relieve bloating and distention, to dissipate stagnation and obstructions, to promote the circulation of Ying Qi, to alleviate water retention and subdue swelling, and to activate the flow of Qi and Blood in the channels and collaterals.

Using the right and left hollow fists or soft palms, lightly tap the lower leg Zusanli points nine times (Figure 41.94).



Figure 41.90. Massage Tapping GB-31



Figure 41.91. Massage Tapping GB-34



Figure 41.92. Massage Tapping Sp-9



Figure 41.93. Massage Tapping Bl-40

Anal Muscle

If you do not strengthen your anal muscle, you will not progress very far in any of the Universal Tao System's practices. The anus muscle is connected to the perineum and everything in the body above it. If you invest all of your money on building the top floors of a building, and do not invest anything in the foundation, the building will fall. Think of the anus and perineum as your foundation. The anus muscle is used to seal your "lower gate." Closing this orifice helps to retain and prevent loss of your energy.



***Fig. 7.2** Anal Muscle*

MASSAGE TAPPING ABOVE THE MEDIAL MALLEOLUS (SP-6)

This exercise stimulates the Sanyinjiao or Three Yin Crossing points. The purpose of this exercise is to tonify and regulate the Qi and Yang of the Spleen, as well as regulate the Qi of the Stomach, Middle and Lower Burners, reduce digestive stagnation, and to facilitate Blood flow.

Using the right and left hollow fists or soft palms, lightly tap the inside of the lower leg at the Sanyinjiao points nine times. (Figure 41.95).

MASSAGE TAPPING THE HEELS (KD-1)

This exercise stimulates the Yongquan or Bubbling Spring points. The purpose of this exercise is to tonify the Kidneys' Yin and Jing, tranquilize the mind, clear away Heat, purge pathogenic Fire, calm the Liver and to stop pathogenic Wind.

To begin this exercise make sure that the knees are slightly bent. Quickly rise and fall on both heels to stimulate the Yongquan points and shake the back nine times (Figure 41.96).

TREMBLING THE KNEES

The purpose of this exercise is to disperse stagnant Qi, as well as to relax the perineum.

To begin this exercise, relax, then bend and straighten the knees quickly for nine times. Next shake them from side to side quickly in order to tremble and shake the entire body. Repeat nine times (Figure 41.97).

CIRCLING THE ABDOMEN

The purpose of this exercise is to balance the Lower Dantian Qi, stimulate the Stomach and bowels, and enhance digestive peristalsis.

To begin, place the center of both palms on the Lower Dantian, embracing the navel (for men, the left palm is on the top, opposite for women). Focus the mind's intention deep into the Lower Dantian. While using the navel as the center, connect the energy of the Lower Dantian with the center of the palms as they rotate.

Begin to circle 36 times counterclockwise for men (from the patient's point of view), whereas the rotation is clockwise for women. Allow the circle to gradually move from a smaller to a larger



Figure 41.94. Massage Tapping St-36



Figure 41.95. Massage Tapping Sp-6



Figure 41.96. Dropping the Heels to Stimulate Kd-1

rotation (as the hands circle, imagine that they are dispersing the Qi). Pause and reverse the circle, rotating 24 times in the opposite direction, gradually reducing the circle's size. This will draw the Qi from the outer portion of the body and collect it into the Lower Dantian. Pause for a moment then return to the Wuji position (Figure 41.98).

COMPLETING THE EXERCISE

Upon completion of the exercise, close the Four Doors (the center of each palm and foot) and cultivate the Qi with stillness, allowing the energy to return to its origin. Hold a quiet Wuji postue for about 15 minutes.

The purpose for the first circle rotation is to release the Yuan Qi which has been collected and gathered in the Lower Dantian. This is to avoid any stagnation which may cause the energy flow to slow down. This also disperses and releases the Yuan Qi, allowing it to blend with the Essential Qi of the Five Yin Organs.

When performing the reverse or second circle rotation, allow all the dispersed energy to gather together and return back to the Lower Dantian. This accumulates and stores the organ energy, blending it together with the Original Qi.



Figure 41.97. Trembling the Knees



Figure 41.98. Circling the Abdomen to Finish

CHAPTER 42

DAOIST QIGONG REGULATION EXERCISES

This particular school of Daoist Medical Qigong Regulation was first introduced in the West by one of my teachers, Dr. Her Yue Wong. These techniques have become increasingly popular, as they are simple, yet extremely effective in tonifying and regulating the body's organ energy.

The interesting thing about Western healing practices is that they focus on the neuromuscular skeletal system to the exclusion of the visceral system, not recognizing that the visceral system is necessary to supply the fuel for the neuromuscular system. These following exercises focus on the visceral system and enhance the quality of life of the viscera.

The system as a whole is divided into two sections. The first section stimulates, energizes, and regulates the body's Yang organs and channels. The second section stimulates, energizes, and regulates the body's Yin organs and channels.

The exercises can be practiced as a complete system, or singled out individually and practiced as tonification prescriptions. As with any Medical Qigong prescription, the patient must purge his or her body of Toxic Qi before starting the tonification exercise and return the Qi back to the Lower Dantian upon completion.

DAOIST FIVE YANG ORGAN REGULATION EXERCISE

This exercise massages the five Yang digestive organs, strengthens the peristaltic action of the body's digestive system, as well as increases the capillary circulation through the stimulation of the autonomic nervous system. The Yang digestive organs (Stomach, Small Intestine, Large Intestine, Urinary Bladder, and Gall Bladder) are used by the body to release waste and Turbid Qi; therefore, it is important to keep the Yang organs strong and functioning smoothly.

The Beating and Drumming the Qi Breath Regulation (which is employed within this exercise) is beneficial for those patients who suffer from digestive problems and irregularity (i.e., spastic colon, chronic diarrhea, irritable bowel syndrome, etc.).

When the patient's arms swing rhythmically throughout the exercise, the nerves and Qi channels of the shoulder joints become stimulated. The swaying action of the arms increases the circulation in the energetic channels which connect the different internal organs and terminate at the hands.

Although this exercise is simple, the result in strengthening the body's peristaltic action and curing digestive illnesses is very effective. The patient is therefore cautioned not to eat prior to practicing this exercise.

SWAYING THE ARMS WHILE BEATING AND DRUMMING THE QI

Assume a wide stance with the arms suspended by the sides of the body. While inhaling, swing the arms up straight out in front of the body and then bring the hands in by the chest (Figure 42.1). Expand the abdomen fully focusing the mind's inten-



Figure 42.1. The Daoist Five Yang Organ exercise. Inhale and draw the Qi into the Lower Dantian while swinging the hands forward.

tion on filling the lower abdomen with Qi.

When exhaling, swing the arms back behind the body while compressing the abdomen down and inward directing the Qi to flow from the lower perineum, circulate back into the sacral area, then to the navel and back down to the perineum (Figure 42.2).

Continue to swing the arms back and forth at a pace that is comfortable using natural breathing. The abdomen should expand and contract without forcing the respiration. The patient must have the anal sphincter closed throughout the entire exercise. Continue this repetition for at least 50 breaths. Try to work up to 250 breaths or more for chronic conditions of abdominal obstruction and Qi stagnation within the digestive system.

The pressing and releasing action of the abdomen stimulates the energetic functions of the autonomic nervous system. The autonomic nervous system has two divisions:

1. The fight or flight mechanism of the sympathetic division -- which shuts down the digestive system due to the production of adrenaline or norepinephrine and redirects Qi and Blood flow to the brain and skeletal muscles, and
2. The vegetative, renewal mechanism of the parasympathetic division -- which draws Qi and Blood from the brain into the digestive system.

The centers for neuronal control of the autonomic nervous system and also control the digestion and tubal contraction are located in the cranium and in the sacrum. The accessory nerve and vagus nerve carries from the brain stem, its nucleus (or center), all of the information to supply the digestive system with impulses to stimulate peristaltic contraction. At the lower end of the digestive system, the sigmoid colon, rectum, Bladder and uterus are controlled by nerve fibers coming from the first, second, and third sacral foramina. The action of the cranial-sacral division of the parasympathetic nervous system is to stimulate peristaltic action (hence the movement of nutrients through the digestive system).

The movement of the abdominal cavity, diaphragm, and thoracic cavity changes the position of each organ and enhances its function. By tightening the anal sphincter and compressing and releasing the urogenital diaphragm, the reproductive organs are also stimulated, including the uterus, prostate, urethra, and testicles. Finally, the Daoist Five Yang Organ Regulation exercise also enhances the peristaltic action of the body's lymphatic system, circulatory system, and tubal systems.



Figure 42.2. Exhale and compress the abdomen, allowing the hands to swing behind the body.

DAOIST FIVE YIN ORGAN TONIFICATION AND REGULATION EXERCISES

Each of the following exercises are designed to stimulate the specific internal Yin organ, as well as the paths of energy that flow from the channels of each organ. Since the Yin organs have the responsibility of storing energy, each exercise is named for the organ it tonifies.

The Yin exercises are performed in the sequence shown below without pausing in-between transitions. Unless specifically prescribed as a therapeutic modality, each exercise should flow directly into the next. The transitions are very important for continuity of energy flow. This particular Five Yin Organ series begins with an opening exercise and ends with a closing exercise.

OPENING, COLLECTING, AND MOVING THE QI

The opening exercise is designed to stretch and loosen the spinal vertebrae and to facilitate the energy flow through the patient's Governing Vessel. The spinal stretch also stimulates the flow of fluids and electrical impulses in the central nervous system (brain and spinal cord), which is nurtured by the cerebral spinal fluid. When the fluid starts to move, it awakens the nervous system causing more nutrients to enter the cellular structure of the nerves. The stretching, compressing, and pumping action of the spinal cord stimulates the movement receptors located in all of the ligaments and fascia energizing the body's entire proprioceptor mechanism.

The opening exercise is also designed to stretch the connective tissue, warm the body's intercellular matrix and tissues, stimulate the somatic system, free adhesions, as well as enhance the elasticity and compressibility of the ligamentous structure.

After finishing the Daoist Five Yang Organ Regulation exercise, return both hands to the Lower Dantian. Next, raise both hands above the head as you inhale (Figure 42.3).

Imagine energy (like a rushing river) flowing up from the feet, filling the legs, hips, waist, chest, arms, and head. Every square inch of the body is absorbing and being saturated with this Earth energy. When the entire body is completely full, the hands should still be positioned above the head (Figure 42.4).

Begin to exhale and feel the hands getting very heavy. The heaviness pulls the hands forward and then slowly starts to pull the body over. Slowly bend the head forward and feel the cervical vertebrae stretch. Let the hands pull the arms, which in turn will pull the shoulders and torso, followed by bending at the waist. The purpose of this movement is to feel each vertebra of the spine stretch sequentially so that a rippling effect descends down the spine. This will facilitate maximum stretch of the spine. While bending over, exhale and imagine the energy melting away from the entire body (like ice melting into water) slowly dissolving and rushing down through the feet and out into the ground (Figure 42.5).

Once completely bent over, imagine picking up a ball. Bend the knees and slowly stand up. While standing up, reverse the rippling of the spine from the coccyx, sacrum, and lower lumbar vertebrae to the base of the skull (Figure 42.6). Repeat these movements five times. Remember to inhale while raising the body, bring both arms over your head, and exhale as the body descends.


Figure 42.3. The Daoist Five Yin Organ Opening exercise. Begin by stretching the arms above the head.


Figure 42.4. Inhale and imagine the Earth Qi like water filling the entire body.


Figure 42.5. Exhale, bend the body and imagine any tension melting out the body into the Earth.


Figure 42.6. For the transition movement to the Lung Tonification exercise: inhale, bend the knees and slowly stand up.

LUNG TONIFICATION AND REGULATION EXERCISE

This exercise is designed to massage the Lungs' tissues and nerves, as well as tonify the entire Lung organs and channels. In the Lung exercise, both the sympathetic and parasympathetic divisions of the autonomic nervous system are stimulated. The compression and release action of the scapulae and thoracic vertebrae stimulate the nerves, arteries, veins and capillary system in the thoracic region.

Compressing and releasing of the muscles and blood vessels in the back and chest areas stimulates the transforming of the Qi and Blood and enhances the health of the individual tissue cells. The compression and release of the thorax also increases the stimulation of the nervous system in the Lung area, as well as stimulates the "release and return" action of the lymphatic system. All the major lymphatic ducts are located in the posterior portion of the thoracic wall.

The compression and release of the second, third, and fourth thoracic vertebrae stimulates the sympathetic preganglionic fibers from the spinal cord, which in turn stimulates the postganglionic fibers and the sympathetic outflow to the Lungs and bronchi. Patients practice this exercise to strengthen their respiratory system as well as increase the production of their Wei Qi to enhance their body's immune system.

Upon completion of the Opening exercise, the patient brings the hands above the head and places them in front of the torso at shoulder level while exhaling. The patient's palms should be facing downward parallel with the floor (Figure 42.7).

Inhale and bring the arms straight out to the sides (both hands should not go any higher than the shoulders) (Figure 42.8).

As the arms reach the sides of the body, rotate the palms until they face upward. Keep the shoulders stable and relaxed (Figure 42.9).

While exhaling, bring the arms straight out in front of the body returning to the beginning posture (Figure 42.10).

Allow the scapulas to gently push the arms forward. The sternum at this point is pushed inward so as to hollow the chest. Once the hands are aligned in the front of the shoulders, rotate the arms and



Figure 42.7. The Lungs Tonification exercise: Inhale as the hands separate.



Figure 42.8. Separate the Hands and turn the palms upward.



Figure 42.9. Exhale as you bring the arms toward each other.



Figure 42.10. Draw the hands toward each other and turn the palms facing the Earth.

inhale to begin again. Repeat 20 times.

Note: Do not let the hands touch when bringing the arms back together towards the center line of the body. The body will short circuit itself, resulting in a mild shock or a sick feeling inside the thorax by the Heart.

KIDNEY TONIFICATION AND REGULATION EXERCISE

This exercise is designed to massage the Kidneys' tissues and nerves, as well as tonify the entire Kidney organs and channels. According to Western physiology, the Kidneys maintain the chemical, pH (potential of hydrogen), and temperature balance of the Blood. The Kidneys function like a rheostat changing the body's ability to absorb, retain, or release water according to the environment (e.g., retaining water in hot climates).

The twisting back and forth, pumping action of the exercise stimulates an opening and closing action within the Kidney organ. The Kidneys receive the major Blood supply from the abdominal aorta. In the Kidney exercise, the action of raising the torso upwards will literally suck Qi and Blood into the Kidney area.

Patients practice this exercise to strengthen their reproductive system, as well as increase the production of their Jing. It also helps balance the body's general energy condition, and can be used to treat sexual disorders and malfunctions.

Upon completing the Lung exercise, both arms are extending straight out in front of the body (Figure 42.11).

Inhale and drop the elbows and bring the hands down in front of the Lower Dantian (Figure 42.12).

Exhale and shift the weight to the left. As the left outer palm wraps around the back, resting itself on the right Kidney, the right palm extends towards the left direction (Figure 42.13).

The right palm, facing outward towards the left direction, begins to circle upwards in front of the face at eye level. As the palm begins to move, the eyes watch the back of the right palm (Figure 42.14).

Shift the weight towards the right side of the body and begin leaning towards the right direction. The eyes continue to follow the right palm as it begins to circle downwards in front of the body. Ex-



Figure 42.11. After completing the Lung exercise, center the body to prepare for the Kidney Tonification exercise.



Figure 42.12. Preparation for the Kidney Tonification Exercise



Figure 42.13. Kidney Tonification Exercise: exhale as the left outer palm wraps around the right kidney, and the right palm extends outward in a left direction.



Figure 42.14. Begin to inhale as the right palm circles upwards and turns outward at eye level and begins to descend.

hale while shifting the weight (Figure 42.15).

Shift the weight, bend the knees and begin to lean over. While continuing to exhale, imagine scooping water with the right palm. Bend at the waist and scoop with the right arm. Keep the back relaxed and straight (Figure 42.16).

Allowing the right arm to follow the motion of the body, begin rising up slightly while turning forming an arc in front of the torso. As the palm raises, imagine the energy (which has been scooped into the arm) draining down the right arm across the shoulders and down the left arm into the right Kidney. Repeat this side for ten breaths (Figure 42.17).

After completing 10 breaths switch directions by shifting the weight onto the right leg (Figure 42.18 and Figure 42.19).

The right hand wraps the torso ending at the left Kidney and Mingmen area while the left palm is positioned in front of the face. Begin to inhale and repeat 10 times on the opposite side.

LIVER TONIFICATION AND REGULATION EXERCISE

This exercise is designed to massage the Liver's tissues and nerves, as well as tonify the entire Liver organ and channels.

According to Western physiology, the Liver is the body's master filter, collecting all of the nutrients that are being absorbed from the digestive system via the hepatic portal vein. The Liver functions like a series of channels. The cells of the channels are considered the processing factory for the entire body. If the body has a need for a particular nutrient, the Liver will create the enzymes for digestion, breaking down into components that which the body needs (or storing the components until needed). The Liver is also responsible for detoxifying, producing antibodies, and creating new cells to handle foreign substances recently absorbed by the body (storing substances of which it has no need).

The compression and release action of the torso causes a physical compression within the Liver organ itself, flushing Qi and Blood from the digestive system through the Liver and into the Gall Bladder where bile is stored.



Figure 42.15. Continue inhaling as you bend over at the waist. Once your head sinks below your hips begin to exhale. Allow your right palm to circle downward to the left.



Figure 42.16. Continue exhaling as your weight shifts to the other foot and imagine the palm scooping up water as the body begins to circle upward.



Figure 42.17. As the torso begins to arch upwards, allow the right arm to follow the body's movement. As the arm reaches the chest level, turn the outer palm towards the face and begin inhaling.



Figure 42.18. Preparation to switch hand positions: Shift the body's weight onto the right leg as the right arm begins to move to the back left Kidney and the left arm leaves the right Kidney to move forward.



Figure 42.19. Kidney Regulation exercise final movement: begin to inhale as the left palm circles upwards and turns outward at eye level and begins to descend to the left.

Patients practice this exercise to strengthen their tendons and ligaments. This exercise helps to regulate the patient's emotional state.

Upon completing the Kidney exercise, begin to unwind the arm from behind the back and rotate the hips so they face forward (Figure 42.20).

Place the right arm straight out in front of the body, shoulder level, palm facing down. Place the left hand by the left hip, palm facing up (Figure 42.21).

Simultaneously draw the right palm back and extend the left palm forward while inhaling. The left hand moves forward passing the right hand which is moving backwards (Figure 42.22).

The hands continue in this motion extending outward from the center line of the body. Use long, slow inhalation and exhalation, inhaling and exhaling every three moves. Relax and continue to repeat this sequence for 20 breaths (Figure 42.23).

HEART TONIFICATION AND REGULATION

This exercise is designed to massage the Heart's tissues and nerves, as well as tonify the entire Heart organ and channels.

The compression and release of the skeletal muscles squeezing and releasing the cardiac muscle energetically stimulates the pericardium surrounding the heart. The twisting movement and compression of the torso also enhances the fluidity of all the connective tissues that are involved with the Heart. Every time the thoracic wall moves, expands, contracts, or twists, the tissues of the Heart are pulled, stretched, and released.

Patients practice this exercise to strengthen their circulatory system. This exercise helps to



Figure 42.20. Preparation for the Liver Tonification Exercise: upon completing the Kidney exercise, begin to unwind the arm from behind the back and rotate the hips so they face forward.



Figure 42.21. Liver Tonification Exercise: place the right arm straight out in front of the body, shoulder level, palm facing down. Place the left hand by the left hip, palm facing up.



Figure 42.22. Simultaneously draw the right palm back and extend the left palm forward while inhaling. The left hand moves forward, passing the right hand which is moving backwards.



Figure 42.23. Use long, slow inhalation and exhalation, inhaling and exhaling every three moves.

Saliva

Saliva is yet another aid in performing these exercises. Once you have been able to bring the energy up through all the routes to the crown successfully, saliva generation becomes very important.

In the body, the moon influences the kidneys, which are linked with the salivary glands, the ovaries and semen. When the kidneys are stimulated during sex, the Chi is raised up through the spine, then it flows down in the saliva, and the kidneys' essence transforms into sexual energy. The saliva has two functions: purifying the mouth, and nourishing our immortality, the water of life. The energy from the saliva lubricates 100 joints, and it stimulates and harmonizes the organs. It is very important to enhance the production of saliva by absorbing the moon's energy through the breath absorption exercises. It is a sign that the techniques are working when the saliva floods into the mouth.

Although saliva is a lubricant for the Channels, it first serves as an agent to burn and clean them out of any impurities that could block the flow of energy. So when resting during the practice of opening the thrusting channels move your tongue around to create saliva. Make it thick and swallow down forcefully, feeling it go down the channels that you are working on (See the book *"Elixir Chi Kung"* by Mantak Chia).



Fig. 7.3 *Saliva*



Figure 42.24. Preparation for the Heart Regulation Exercise: upon completing the Liver exercise allow both hands to sink down in front of the lower abdomen.



Figure 42.25. Heart Tonification Exercise: imagine the hands embracing a ball, placing the right hand on top, and the left hand on bottom: inhale.

stimulate the patient's intellectual activity and mental acuity or clarity.

Upon completing the Liver exercise allow both hands to sink down in front of the lower abdomen (Figure 42.24).

Imagine the hands embracing a ball, placing the right hand on top, and the left hand on bottom (Figure 42.25).

Exhale and twist the hips to the left, simultaneously raising the left hand up over the head while extending the right hand towards the left (Figure 42.26).

Continue pressing until both hands extend to the furthest point (Figure 42.27).

Inhale and turn the right palm upwards facing the sky as the body twists back to the center allowing the right hand to end up in front of the navel (Figure 42.28).

The left hand simultaneously turns so that the palm faces the center of the right hand following it to the center line of the body (Figure 42.29).

As the body reaches the point where it faces forward, twist to the right side and push in the same manner while exhaling. Repeat 10 times on each side (Figure 42.30).



Figure 42.26. Exhale and twist the hips to the left simultaneously raising the left hand up over the head while extending the right hand towards the left.



Figure 42.27. Continue pressing until both hands extend to the furthest point.



Figure 42.28. Inhale and turn the right palm upwards facing the sky as the body twists back to the center allowing the right hand to end up in front of the navel.



Figure 42.29. The left hand simultaneously turns so that the palm faces the center of the right hand following it to the center line of the body.



Figure 42.30. As the body reaches the point where it faces forward, twist to the right side and push in the same manner while exhaling.

SPLEEN TONIFICATION AND REGULATION EXERCISE

This exercise is designed to massage the Spleen's tissues and nerves, as well as tonify the entire Spleen organ and channels.

Raising the arms above the head stretches all of the suspensory ligaments of the Spleen making the Spleen energetically accessible by the twisting movements of the torso. The compression and release action on the connective tissue and fascia that support the placement of the Spleen allows the internal channels to become dilated facilitating a greater flow of Qi and Blood into the organ.

While looking up and turning to the right, the left brain is stimulated. Consequently, by looking up and turning to the left, the right brain is stimulated. According to Western physiology, light waves come into the eyeballs through the retina stimulating the optic nerve, chiasma, tract, lateral geniculate body (stimulating the thalamus), superior colliculi (in the brain stem where visual reflexes are initiated), optic radiations, cerebral cortex, and occipital (visual) cortex, which integrates both visual and memory impulses responsible for the perception of the image. Half of the information received from the right eye goes to the right side of the brain, while the other half of the information crosses over and stimulates the left brain.

Patients practice this exercise to strengthen their digestive system, as well as to enhance their visual equilibrium.

Upon completion of the Heart exercise, bring both hands down to the waist level, palms facing downward. Circle them above the head and perform the Pulling Down the Heavens exercise. Next, move the palms towards the outside of the knees while twisting the thumbs to point towards the back of the body (this stimulates the Luo points of the arms and squeezes the Wei Qi of the hands and arms deep into the bones) (Figure 42.31).

The thumb and index fingers touch and form a triangle as the hands slowly raise above the head (Figure 42.32).



Figure 42.31. Preparation for the Spleen Regulation Exercise



Figure 42.32. Spleen Regulation Exercise: the thumb and index fingers touch and form a triangle as the hands slowly raise above the head.

The eyes look through the center of the triangle as the upper torso is turned from side to side. It is important that the hips remain stationary and that the upper torso rotate in order to massage the digestive organs. Inhale in the center. Exhale on each side. Repeat 10 times on each side (Figure 42.33).

ENDING, ROOTING, AND STABILIZING THE QI

The purpose of the ending is to gather the Qi back into the patient's Lower Dantian rooting and stabilizing the patient's Qi. This ending exercise is very important as its initial goal is to gather any excess Qi developed from the over stimulation of the Five Yin Organs and to collect the runoff energy into the Lower Dantian (where it can be absorbed and used by the Eight Extraordinary Vessels). Otherwise, if the individual unknowingly has a preexisting Excessive condition in a particular Yin organ, the additional tonification can exasperate the organ's condition. To avoid this Excess condition, certain Medical Qigong schools will use external massage and lightly brush the energetic channels after practicing certain Qigong exercises and meditations to disperse any excess Qi.

The soft compression used during the ending exercise increases the partial pressure of oxygen in the Blood as more oxygen passes into the cells. The action of moving oxygen into the cells creates a movement of carbon dioxide out of the cells increasing the exchange rate and establishing a greater metabolic breakdown.

The breathing initiated for the ending exercise is known as "Turtle Breathing." The Turtle Breathing method requires slow respiration and stimulates the center hub of the Belt Vessel.

Upon completion of the Spleen exercise, exhale and start to separate both hands (as if embracing a ball) (Figure 42.34 and 42.35).

Bring both hands down to waist level and separate the arms, moving the hands away from the center of the body (Figure 42.36). Inhale and raise the arms up over the head. Each hand is placed above the head as if embracing a ball (Figure 42.37).

Exhale and form loose fists with the hands (Figure 42.38).



Figure 42.33. The eyes look through the center of the triangle as the upper torso is turned from side to side. Inhale in the center, exhale on each side.



Figure 42.34. Preparation for Ending the Daoist Five Yin Organ Exercise (a)



Figure 42.35. Preparation for Ending the Daoist Five Yin Organ Exercise (b)



Figure 42.36. Preparation for Ending the Daoist Five Yin Organ Exercise (c)



Figure 42.37. Ending the Daoist Five Yin Organ Exercise: each hand is placed above the head as if embracing a ball.



Figure 42.38. Exhale and form loose fists with the hands.



Figure 42.39. As you bend over, slowly turn the soft fists so that the curled fingers face the body and begin squatting, forming a Turtle Posture.



Figure 42.40. Inhale and slowly begin to raise the body up while opening the fists, and allow the hands to return back to their original position at the sides of the body.

As you bend over, slowly turn the soft fists so that the curled fingers face the body and begin squatting forming a Turtle Posture (Figure 42.39).

Inhale and slowly begin to raise the body up while opening the fists and allow the hands to return back to their original position at the sides of the body (Figure 42.40). Repeat five times and end in the Wuji posture.

When practicing the Turtle Breathing method, the mind's intention and respiration should be focused onto the Lower Dantian, navel, and Mingmen areas of the body.

The Lower Dantian is divided into eight sections (see Figure 42.41). Each section is numbered, beginning with the front of the Lower Dantian at the navel area (1), increasing in number as one continues over the left and right sides of the waist (4), ending at the Mingmen area (8).

Think of the anal sphincter as a great funnel, attached in eight different segments (like canals) which progress up the torso. As you focus your mind on each section (begin with the navel at section 1), allow any excess energy to flow downwards from that particular section to be gathered into the Lower Dantian. With your imagination, direct the breath and Qi from your torso to flow into each of the eight areas.

The breath and Qi should be slowly inhaled and guided into the Lower Dantian via the anal sphincter area for an even three counts. Then, proceed to gather Qi from the next consecutive area of the body. By pulling upwards on the anal sphincter and perineal areas, an energetic vacuum is created within the pelvic diaphragm and urogenital diaphragm. This energetic vacuum is used to gather the internal organ's excessive Qi.

Begin with collecting Qi from the front of the body, to the navel via the anal sphincter. Hold the Qi in the Lower Dantian area for three counts, then proceed to the next areas at the sides of the body absorbing the Qi into the Lower Dantian via the anal sphincter for three counts.

Next, proceed to the sides of the body continuing in progression until you reach the Mingmen area (8). Then, reverse the progression beginning with the Mingmen and working around


Left Ovary,
Left Breast,
Heart,
Conception Vessel,
Reproductive Organs,
Bladder
Right Ovary,
Right Breast,
(1)
Navel
Transverse Colon,
Small Intestines
(2)
(2)
Transverse Colon,
Small Intestines
(3)
(3)
(4)
(4)
Descending
Colon
Ascending
Colon
(5)
(5)
Spleen,
Stomach
Liver,
Gall Bladder
(6)
(6)
Left
Lung
Right
Lung
(7)
Mingmen
(7)
Left
Kidney
(8)
Right
Kidney
Governing Vessel,
Spinal Cord,
Brain

Figure 42.41. When practicing Turtle Breathing, inhale and slowly begin drawing the Qi from the front of the body into the navel area (1), absorbing the energy from the Heart, Conception Vessel, reproductive organs, and Bladder into the Lower Dantian. This absorbing action is created by pulling upwards on the anal sphincter in the direction of the intended energy. Next, proceed to the sides of the body. In women, the next area (2) will include the excess energy gathered from both the left and right ovaries, as well as the left and right breasts. In men, however, this area (2) is considered general and not specific to certain internal organs or tissues. Continue in the progression of circling the waist until you have reached the Mingmen area (8). Then, reverse the order of the tissue areas (8, 7, 6, etc.).

the waist until you reach the navel (8, 7, 6, etc.). Make sure that you push your anal sphincter towards the direction of the area of the body from which you are absorbing Qi.

After perfecting the Turtle Breathing, a practitioner can create the energetic vacuum and initiate the absorption of excess Qi into the Lower Dantian by moving his or her intention from the anal sphincter through the Lower Dantian and torso at an extremely fast speed.

SECTION X

TREATMENT OF INTERNAL DISEASES WITH QI EMISSION THERAPY

INTRODUCTION

Clinical records from China verify that Medical Qigong treatments are most effective on nervous system diseases, migraines, bronchial asthma, nocturnal enuresis, psychosomatic diseases, gastric ulcers, arthritic pains, sterility, and in the elimination of ovarian cysts and benign tumors.

The following chapters are designed to assist the Medical Qigong doctor in his or her professional clinical practice, by explaining the various techniques and prescriptions used in several Medical Qigong Hospitals, Institutes and Colleges throughout China.

These Medical Qigong techniques are presented as basic guidelines for the Qigong doctor to use, and need not be followed exactly to the letter. They are presented as an example to advise Qigong doctors in treatment and prescription protocols.

I have personally found these various approaches of Chinese energetic medicine to be extremely effective in my own clinical practice, and have therefore encouraged the directors of the International Institute of Medical Qigong to instruct their students in the following techniques.

This particular section of the book (Section X) deals with the treatment of Zang (Yin) and Fu (Yang) disharmonies in clinical practice, and discusses general and specific diagnosis, treatments, and prescriptions. I will begin by exploring several examples of the Five Elements' disease patterns and the various techniques used to treat them (Chapter 43-48). Starting with the treatment of Liver diseases, I will progress to the treatment of Heart, Spleen / Stomach, Lung and Kidney Diseases.

In the ending chapter in this section emphasis will be placed on the practical application and theoretical principles of "Miscellaneous" diseases and their treatments.

CHAPTER 43
QI EMISSION THERAPY FOR LIVER DISEASES

INTRODUCTION

The Five Yin Organs' interrelationship with each other, and their complex interrelationship with the energetic ebb and flow of Qi must constantly be regulated to maintain health. The constant flux of energetic flow within the body sometimes causes an Excess or Deficiency of Qi requiring specific organ therapy for restoration and balance. This therapy is designed to bring the specific organ or organ systems back into balance by using various meditations, visualizations and breathing exercises.

This section focuses on specific Liver diseases and how to rectify them. The Liver is responsible for the circulation and smooth movement of the body's internal Qi.

The Liver is a solid (Zang) organ which stores the Blood and is attributed to the element Wood. The Liver is sometimes referred to as the Green Emperor. The Liver is in charge of strategy without hesitation. It is energetically paired with the Gall Bladder (a hollow organ) which carries out the decisions made by the Liver (Figure 43.1).

The Liver houses the Hun. The Liver's association with the environment is through the eyes. Through observation, the Qigong doctor's eyes can receive images that reveal the status or intention of the patient. These images are absorbed into the doctor's Shen via the Hun. There is an old Chinese saying, which goes, "When the Hun swim to the eyes, a person can see."

In the springtime, Liver Qi becomes more active in individuals with strong Liver Qi; whereas, it may become Deficient in those with weak Liver Qi. When Liver Qi is Deficient, the patient becomes fearful; when the Liver Qi is in Excess, the patient becomes consumed by anger. The excessive eating or drinking of sour foods, and overexposure to wind depletes the Liver.



Figure 43.1. The Liver (Lv) Channel

A person experiences the Thrusting Channels according to his or her kinesthetic or visual perceptions. The majority of people are more kinesthetic and can undeniably feel the quality of the condensed energy as it passes through each level of the channels.

Visual people can see patterns and colors. The Thrusting Channels, like the organs they intersect, have corresponding colors. The Left Channel is Red, Middle - White and Right - Blue. Regardless of your perceptual tendency, both the senses and the organs are used to control the Thrusting Channels.

The denser or more polluted the organ, the more energy is requires to pass through the affected Thrusting Channel.

As a safety precaution and as preparation to be able to move the energy to prevent it from sticking, the Thrusting Channels are opened in four stages. The pearl is brought (1) up to the diaphragm; (2) up to the neck; (3) up to and out of the crown; (4) down to the feet, into the ground; and up to the crown.

This will be done a total of nine times at each stage in the following sequence: (1) left, (2) middle, (3) right, (4) middle, (5) left, (6) middle, (7) right, (8) middle and (9) left.

LIVER COMPLICATIONS AND SYMPTOMS

Liver diseases often manifest with the following symptoms which are common to the organ's energetic dysfunction: headaches, dizziness, tiredness, and mental and emotional problems. When Liver disorders occur, the patient may experience Qi movement below the left side of the navel (which feels hard upon pressure), pain and distention in the hypochondria, cramps, drowsiness, blurred vision, etc. A list of Liver syndromes and their symptoms are described as follows.

1. Stagnation of Liver Qi can cause such symptoms as: headaches, mental and emotional problems, hypochondriac pain, abdominal pain and masses, diarrhea, constipation, painful urination, dysmenorrhea, and premenstrual tension.
2. Stagnant Liver Qi Invading the Stomach can result in epigastric pain.
3. Stagnant Liver Qi Invading the Lungs can cause wheezing.
4. Liver Yang Rising can cause such complications as: headaches, dizziness, and tiredness.
5. Liver Fire Blazing can cause such symptoms as: severe headaches, dizziness, breathlessness, wheezing, coughing, mental and emotional problems, insomnia, tiredness, painful or scanty urination, and constipation.
6. Liver Wind can cause headaches, dizziness, seizures, tremors, muscle spasms and tiredness.
7. Liver Blood Deficiency can cause such symptoms as headaches, mental and emotional problems, tiredness, hypochondriac pain, constipation, and premenstrual tension.
8. Liver Yin Deficiency can cause such symptoms as wheezing, mental and emotional problems, insomnia, tiredness, and hypochondria pain.
9. Stagnation of Liver Blood can cause such symptoms as headaches, mental and emotional problems, hypochondriac pain, abdominal pain, and dysmenorrhea.
10. Damp Heat in the Liver and Gall Bladder can cause such symptoms as jaundice, headaches, mental and emotional problems, hypochondriac pain, and abdominal pain.

GENERAL TREATMENT FOR LIVER DISEASES

The following is a description of a general protocol used for treating common Liver diseases. The goal is to introduce the Qigong doctor to the basic hand positions and areas of the patient's body towards which Qi is emitted or Turbid Qi is removed. Once the Qigong doctor becomes proficient at locating these specific points, the treatment flows more smoothly.

The reader will notice that after comparing the various Liver and Gall Bladder therapies, certain patterns repeat themselves.

1. Generally, the Qigong doctor accesses the patient's Liver through either direct energetic insertion into the Liver's anatomical location, or through the patient's channels or external energetic fields.
2. After purging, tonifying, and regulating the patient, the Qigong doctor stimulates the back gates to the patient's Liver and the Yellow Court.
3. Next, the doctor roots the patient's Middle Burner Qi into the Lower Dantian.
4. Finally, the Qigong doctor leads any remaining Turbid Qi down the right Gall Bladder Channel and out of the patient's body (Figure 43.2).

Keep in mind that these areas are general, and that specific treatment patterns must change as they apply to the patient's exact condition (Excess, Deficient, etc.).

MEDICAL QIGONG THERAPY FOR LIVER QI DYSFUNCTION

The primary therapies used to treat Liver diseases include the Windy Breathing Method (see Chapter 16) to strengthen the Liver, Spleen, Lungs, and Kidneys, and Quiescent Qi Regulating meditations (see Chapter 14).

1. Patients with Deficiency of Qi and Cold syndromes of the Liver may feel cold and are li-


Purge
Toxic Qi
out the
patient's
Liver
organ.
Root
Rebellious
Liver Qi into
the Lower
Dantian, then
regulate.
Lead and purge
the Toxic Qi out
of the patient's
GB-34 points
Lead and purge
the Toxic Liver Qi
out of the patient's
right Gall Bladder
Channel.

Figure 43.2. Basic Treatment for Liver Stagnation


Shu
Heart
Haa
Green
Liver
Spleen
Kidneys
Lungs

Figure 43.3. Purging the Child to Treat the Mother

able to feel frightened. To treat this condition, the patient can practice the meditation of Taking in the Green Qi to nourish the Liver and also Taking in the Blue Qi to nourish the Kidneys (Formula: nourishing the mother to replenish the child).

2. Patients with an Excess of Qi and Heat syndromes of the Liver may have dry eyes, pain in the hypochondria that may radiate down to the lower abdomen, and changing moods accompanied by flushed cheeks. To treat this condition, the patient can practice uttering "Xu" (pronounced Shu) for the Liver, and "Ha" for the Heart (Figure 43.3. Formula: purging the child to treat the mother).

   Note: In treating Liver diseases, exhaling the sound "Shu" purges and sedates, while inhaling "Shu" replenishes and tonifies (see Chapter 40).
3. Stagnation of Liver Qi and Liver Fire Rising (anger or rage impairing the Liver) may cause an abnormal dispersing and impair the Liver's function. The patient may experience headaches, deafness, and swelling cheeks. To stabilize the hyperactive Liver Yang (and guide the flaring up Liver Fire to descend), the Qigong doctor guides the patient's Qi back to its origin with external energy projection. If treatment of Liver stagnation is not undertaken, there may be an organic change in the

Liver, resulting in hardening of the Liver or Liver cancer.

4. Patients with Rebellious Liver Qi resulting in hypochondriac pain and stiffness with spasms, should be treated by guiding their Qi back to the origin of the Liver with external Wei Qi therapy.

LIVER QIGONG PRESCRIPTIONS

The following system of exercises can be used to regulate the Qi and Blood of the Liver Channels, soothe and regulate Qi circulation, and suppress hyperactive Yang. These exercises can also be used to prevent and treat diseases and syndromes such as hypertension, psychoneurosis, chronic hepatitis, and hepatosplenomegaly (the enlargement of both Liver and Spleen), as well as bitter taste in the mouth, dry throat, dizziness, vertigo, and fullness in the chest and hypochondrium.

COLOR VISUALIZATION AND ORGAN CORRESPONDENCE

In China, the clinical use of color therapy is prescribed according to the Five Color Correspondence Theory. Each of the five major colors are assigned to specific organs and their channels (see Chapter 4). If an organ is diseased, it will generally appear in various shades from gray to black. To heal the disease, the patient imagines taking in the organ's clean color, while dispersing the turbid pathogenic color. This visual meditation helps to return the organ's Qi back to its origin, in order to achieve balance and health.

PRESCRIPTIONS FOR TONIFYING THE LIVER

Taking in the Green Qi can be used to tonify the Liver. The properties inherent within the color green have a persistent vibratory rate also used for tonifying the Liver and Gall Bladder.

1. Assume a standing, sitting, or lying posture. Relax the whole body, breathe naturally, and get rid of any stray thoughts. Place the tongue against the soft palate on the roof of the mouth.
2. Visualize green energy in front of you. Draw from a visual/emotional association with green trees, grass, bushes, etc. from your imagination, or if possible, actually look at a green object. Inhale the green light energy in through the nose and down into the Liver organ. As you exhale through the mouth, the dark, pathogenic Qi leaves the Liver; however, the bright, clean color remains in the organ, stimulating and vitalizing it. With each breath the organ retains more clean energy and begins to glow. Repeat for five breaths.

   Next breathe the color green in through the nose, filling the entire mouth. When exhaling, send the Qi slowly to both costal portions at the sides of the Lungs, and then down to the Lower Dantian. Practice eight to sixteen times.

PRESCRIPTIONS FOR PURGING THE LIVER

Purge the Liver by having the patient rub his or her chest while sounding "Shu." Have the patient assume a sitting or standing posture, and place both palms flatly on both sides of the chest and inhale slowly. When exhaling, the patient should sound the word "Shu," while gently rubbing both costal regions in a clockwise circular motion with both palms. Practice for ten to twenty breaths.

PRESCRIPTIONS FOR SOOTHING THE LIVER AND CONDUCTING QI

The following exercise is used to regulate and soothe the Liver Qi; it is used after the purging or tonifying exercises.

1. Stand relaxed with both arms naturally hanging down, palms facing downward, with the five fingers of each hand slightly held up. Press down with slight force and imagine Qi reaching the palms and extending to the fingertips. Press the palms down three times (Figure 43.4).
2. Lift both hands up in front of the chest, with each palm facing forward. Focus the mind on both palms. Push the palms forward three times, first drawing them closer to the body and then pressing them further away from the chest (Figure 43.5).
3. Stretch both hands horizontally out to the sides of the body (as if imitating a bird that is stretching out its wings) with all the fingers pointing upward, and the palms pushing to



Figure 43.4. Press the palms downward three times.



Figure 43.5. Press the palms forward three times.



Figure 43.6. Press the palms to the sides of the body three times.



Figure 43.7. Direct the Qi to flow downward from the Middle to the Lower Dantian three times.

the sides. Focus your attention on extending the Qi out the palms to the fingertips. Press the palms out to the sides three times (Figure 43.6).

4. Draw both palms back to the front of the chest, palms facing upwards, elbows down. Rotate the palms to face downwards, and circle them down to the pubic arch, while focusing the mind on both palms (Figure 43.7). When Qi flows to the Lower Dantian turn the palms to face upward as if embracing a ball at the Lower Dantian.

Perform this exercise three times, then place both hands against the sides of the body. This completes one set. Do three sets.

MEDICAL QIGONG THERAPY FOR SPECIFIC LIVER DISEASES

The following are several Medical Qigong treatments used in China to treat specific Liver diseases.

DISORDERS OF THE BILIARY TRACT

The biliary tract includes the organs and ducts that participate in the secretion, storage, and delivery of bile into the duodenum.

ETIOLOGY

Disorders of the biliary track mainly include cholecystitis (inflammation of the Gall Bladder), cholelithiasis (formation of calcium or bile stones in the Gall Bladder), and ascariasis of the biliary tract (infestation by ascaris lumbricoides parasites). Traditional Chinese Medicine teaches that the first two diseases belong to the category of hypochondriac pain or jaundice, while the last condition is called biliary ascariasis.

Disorders of the biliary track can be caused by mental depression, stagnation of Gall Bladder Qi, the excessive intake of fatty foods, exopathogenic invasion, failure of biliary drainage system resulting from stagnation of Dampness and Heat, or obstruction by ascarid parasites. Although the causes and symptoms of these disorders are different, the Medical Qigong treatments and prescriptions are the same.

SYMPTOMS

The onset of biliary tract disorders are usually acute, and the pain is felt on the right upper abdomen and the right hypochondrium area of the thorax. Other symptoms include nausea, vomiting, rigor, high fever, yellow-colored skin pigmentation (jaundice), yellow sclera of the eyes, and whitish-grey stool.

Patients with biliary ascariasis may experience severe colic or a tearing pain below the xiphoid process. The pain is sometimes so severe that the patient experiences extreme perspiration accompanied by nausea and vomiting. If the ascarid parasites withdraw from the biliary tract, the pain is immediately relieved, but can return intermittently. If the ascarid parasites move completely into the Gall Bladder, the pain will be continuous, causing Gall Bladder distention. Symptoms such as jaundice, rigor, and high fever may appear, and a tenderness on the upper right quadrant of the xiphoid process can be felt with deep pressure.

TREATMENT

Cholelithiasis (gall stones) and cholecystitis (inflammation) are often treated by guiding the Toxic Qi downward and out of the patient's lower extremities along the Liver and Gall Bladder Channels, and by balancing the Qi activities between the upper and lower quadrants of the patient's body, as well as the right and left sides.

1. To begin treating disorders of the biliary tract, place the patient in a sitting position on the table. Stimulate the Bl-18, -19, -20, -21 points beside the patient's lower thoracic vertebrae, paying particular attention to the right side of the patient's body.
2. Next, extend Qi into the Gall Bladder area for 24 breaths (on the front of the patient's body), stimulating this area with the Tiger Kneading Palm technique, using Pushing, Pulling, and Shaking Qi manipulations.
3. To regulate the patient's Qi, and relieve epigastric distension, the doctor purges the patient's Toxic Qi, guiding it to flow out of the body downwards along the patient's Gall Bladder and Stomach Channels and out of the feet.
4. Using the Vibrating Palm technique, stimulate the patient's Bl-18, -19, -20, -21 points on the right side of the body once more, this time for 28 breaths. Then use the same Vibrating Palm technique on the front side of the body while directing the energy towards the Gall Bladder for 28 breaths.
5. Finally extend energy into the patient's Bl-19 point on the right side of the body for 12 breaths, and using the Sword Fingers technique, lead the Qi down the right Bladder Channel to the foot and out the small toe three times.

TREATMENT MODIFICATIONS

When treating the condition of ascariasis of the biliary tract, also include rubbing the abdomen 18 times in a counterclockwise direction.

PRESCRIPTIONS AND HOMEWORK

In prescribing homework, place the patient in a standing Wuji posture, with both palms placed against the hypochondria. Have the patient slowly massage the Gall Bladder area while purging the organ with the sound "Shu" for 24 exhalations.

Next, have the patient sit or lie down in a comfortable setting. As the patient inhales, he or she should meditate on the word peace; as the patient exhales, he or she should focus on relaxation. The patient should focus on releasing all tension in the head, chest, Liver, Gall Bladder, back, abdomen, and waist, for 36 breaths.

GALLSTONES

A gallstone is a Gall Bladder stone formed as a result of an excess of cholesterol in relation to the bile acids. The formation of calculi which results from this skewed relationship of cholesterol and bile is believed in Traditional Chinese Medicine to be dependent on the Liver Qi.

ETIOLOGY

Stagnant Liver Qi is believed to be a prerequisite for the formation of gallstones. If the Liver Qi stagnates, the bile will not secrete properly, leading to an accumulation of Damp Heat in the Gall Bladder. The steaming action of Heat on Dampness over prolonged periods of time, leads to the formation of gallstones.

It is generally believed that gallstones are related to cholestasis, an infection of the biliary tract, and metabolic disturbances of cholesterol. Gallstones form when the bile contains more cholesterol than it can keep in solution. The cholesterol precipitates out to form gallstones. The incidence of gallstones in women is approximately twice that in men. Any factor which increases the patient's cholesterol or decreases bile acids may lead to the formation of gallstones (i.e., obesity, high fat diet, Liver disease, and bile stasis increase the risk of developing gallstones). There are three types of gallstones: Cholesterol Stones, Mixed Stones, and Pigment Stones.

1. Cholesterol stones are usually single stones, which are composed almost entirely of cholesterol, and correspond to the pattern of Damp Heat in the Liver and Gall Bladder.
2. Mixed stones are the most common type of stones, consisting of lamellated layers of cholesterol, bilirubin, and calcium.
3. Pigment stones are less common and are always numerous. They are composed of bile pigment.

Gallstones are clinically manifested as pain in the right upper abdominal quadrant and right costal region, and are classified in Traditional Chinese Medicine as being placed in the categories of either hypochrondriac pain or jaundice.

SYMPTOMS

- Liver Qi stagnation is manifested by pain and distention in the right upper abdominal quadrant and right hypochondriac region. The pain can range from mild to severe. The patient may experience a distention and fullness in the Stomach with no obvious fever or jaundice.
- Damp Heat in the Liver and Gall Bladder is manifested by persistent pain in the right upper abdominal quadrant and right hypochondriac region. The pain manifests proximally or radiates up to the right shoulder. The patient experiences abdominal distention, fever, and jaundice.

TREATMENT

Have the patient sit on the edge of the table. Begin stimulating the patient's middle-back area, focusing on the Bl-21, Bl-20, BL-19, and Bl-18 points, on the right side of the back and drain the Toxic Qi down the torso and out the GB-34 point below the knee.

Use the Vibrating Palm hand technique and emit Qi into the patient's mid-back area for 14 breaths at each point. Then emit Qi into the painful area of the front side of the patient's body for 28 breaths.

Next, applying the Extended Fan Palm hand technique, emit Qi into the patient's Gall Bladder for 24 breaths using the Pulling and Leading manipulation skills to draw the Qi down through the Gall Bladder and Stomach Channels and out the patient's feet.

TREATMENT MODIFICATIONS

When treating a patient with a Liver Qi stagnation, use the Pulling and Leading manipulations to draw Qi down the lower limbs of the patient's body.

When treating patients with Damp Heat in the Liver and Gall Bladder: use the Extended Fan Palm hand technique and emit Qi into the patient's CV-12 and St-21 points, leading the Qi down the right Stomach Channel to the feet.

PRESCRIPTIONS AND HOMEWORK

Have the patient practice Liver Massage described in Chapter 39, while exhaling the sound "Shu" for 36 breaths.

PRESCRIPTION MODIFICATIONS

- For patients with Liver Qi stagnation, have the patient practice rubbing the hypochondrium while imagining the Toxic Qi descending down and out the body. Instruct the patient to practice the Descending the Yang and Ascending the Yin Technique (see Chapter 41).
- For patients with Damp Heat in the Liver and Gall Bladder, have the patient practice rubbing the hypochondrium while imagining the Toxic Qi descending down and out the body as he or she sounds the "Hu" sound to purge and regulate the Spleen.

CIRRHOSIS

Cirrhosis is a generalized disease marked by hepatic lesions. It is a chronic disease of the Liver characterized by the formation of dense lobular connective tissue, degenerative changes in the parenchymal cells, structural alterations in the Liver lobules, and sometimes fatty and cellular infiltration within the Liver.

ETIOLOGY

Cirrhosis refers to a series of pathological changes of degeneration, necrosis and regeneration of Liver cells, as well as the proliferation of fibrous tissue due to prolonged or recurrent damage of the Liver caused by various pathogenic factors. Cirrhosis is clinically manifested as a series of symptoms caused by a hypofunction of the Liver and portal hypertension.

SYNDROMES

1. Liver Qi stagnation and Spleen Deficiency results in lassitude, weakness, fullness in the chest and abdomen, hypochrondriac distension and pain, occasional nausea, belching, and vomiting.
2. Qi and Blood stagnation results in poor appetite, hypochrondriac distention and pain, and enlargement of the Spleen and Liver marked by spider nevus and Liver spots.
3. Water retention results in hardness and fullness of the abdomen with a severe fullness in the Stomach, distention of the abdomen or intestines (by gas), nausea, vomiting, and anorexia. Patients with an insufficiency of Spleen and Kidney Yang suffer from symptoms of cold limbs, pale complexion, and an aversion to cold. Patients with a Deficiency of Liver and Kidney Yin experience sporadic fever, irritability, and a dark complexion.

TREATMENT

Place the patient on the edge of the table and stimulate the Bl-18 and BL-20 points on the mid-back, as well as the Lv-13 and Lv-14 points (at the sides of the body), and the CV-12 point (at the center of the body). Use a Vibrating Palm hand technique to emit Qi into these points for a period of 14 to 18 breaths.

Use the Extended Fan Palm technique and emit Qi into the patient's mid-back at the Bl-18 points, as well as the sides of the torso at the Lv-13 and Lv-14 points. Purge and drain the Toxic Qi down and out the patient's body along the Gall Bladder and Liver Channels.

TREATMENT MODIFICATIONS:

When treating patients with Liver Qi stagnation and Spleen Deficiency, use the Vibrating Palm to emit Qi into the Bl-20 and CV-12 points.

When treating patients with Qi and Blood stagnation, use the Extended Fan Palm technique to emit Qi into the Lv-13 and Lv-14 points, conducting the Qi along the Gall Bladder Channel down the leg to GB-34, and out the body.

When treating patients with water retention, use the Extended Fan Palm technique to emit Qi into the Sp-21 points. Lead the Qi down the Spleen Channels into the lower limbs. For patients with a Spleen and Kidney Yang Defeciency or a Liver and Kidney Yin Deficiency, use a Vibrating Palm technique to emit Qi into the Lower Dantian and Mingmen areas.

PRESCRIPTIONS AND HOMEWORK

Have the patients practice self-regulation exercises to tonify the entire body's energetic system.

PRESCRIPTION MODIFICATIONS

1. For patients with Liver Qi stagnation and Spleen Deficiency, have the patients practice the Old Man Searching for the Reflection of the Moon at the Bottom of the Tide Pool (see Chapter 40).
2. For patients with Qi and Blood stagnation, have the patient perform the Liver Massage while exhaling the sound "Xu."
3. For patients with water retention, have them practice rubbing the Yellow Court area (CV-12) and sounding the word "Hu" to dredge the Spleen and Stomach. For patients with a Spleen and Kidney Yang Deficient, have them practice Gathering the Sun's Essence (see Chapter 11), and for patients with a Kidney and Liver Yin Deficient, have them practice Gathering the Moon Cream. (see Chapter 11).

CHOLECYSTITIS

In Traditional Chinese Medicine, both sides of the hypochondrium are related to the Liver Channels. In Western medicine, however, only the right side reflects a possible Liver pathology. Thus, it is important to have a distinction between left and right hypochondriac pain. Cholecystitis consists of the inflammation of the Gall Bladder with or without gallstones. It is related to hypochondriac pain on the right side of the body. It is created when cholesterol is maintained in the bile solution within the bile acids. Hypochondriac pain on the left side of the body extending to the epigastrium and left scapula is often related to acute pancreatitis.

ETIOLOGY

Cholecystitis is mostly caused by a bacterial infection or an obstruction of the bile duct. Clinically it is characterized by pain in the upper right quadrant of the abdomen and dyspepsia, and may be accompanied by nausea, vomiting, and sweating.

SYNDROMES

- Damp Heat manifestations are alternating attacks of chills and fever. Sometimes there is fever without chills, nausea, vomiting, loss of appetite, and pain in the right hypochondrium region.
- Qi stagnation manifestations are distending or moving pain in the right hypochondrium, belching, acid regurgitation, nausea, and anorexia.

TREATMENTS

1. Have the patient sit at the edge of the table. Stimulate the patient's mid-back, emitting Qi into the Bl-18, Bl-19, and Bl-20 points as well as the GB-34 point below the right knee.
2. Using the Vibrating Palm, first emit Qi into the patient's mid-back for 14 breaths, then directly into the painful area on the front side of the patient's body for 28 breaths.
3. Using the Extended Fan Palm hand technique, emit Qi into the patient's Gall Bladder region for 24 breaths, then purge the Toxic Qi down their right Gall Bladder Channel to the base of the foot and out of the body.

TREATMENT MODIFICATIONS

- For patients with Damp Heat, use the Extended Fan Palm hand technique to emit Qi into the patient's CV-12 area, then purge the Toxic Qi down the Stomach Channels to the base of the feet and out the body.
- For patients with Qi stagnation, use mostly purging and dredging Qi manipulations, focusing on the patient's lower torso.

PRESCRIPTIONS AND HOMEWORK

It is advisable to have the patient perform the Six Healing Sound Regulation exercise (see Chapter 40).

PRESCRIPTION MODIFICATIONS

- For patients with Damp Heat, it is advisable to have them perform the Spleen Massage (see Chapter 39) while exhaling the sound "Hu" to purge the Spleen and Stomach, allowing the Toxic Qi to flow down the Spleen and Stomach Channels into the ground.
- For patients with Qi stagnation, it is advisable to have them perform the Liver Massage (see Chapter 39) while exhaling the sound "Shu."

HYPOCHONDRIAC PAIN

Hypochondriac pain is a syndrome characterized by pain in one or both sides of the hypochondrium. The hypochondrium is located on the part of the abdomen beneath the lower ribs on each side of the epigastrium.

Chronic hepatitis, hepatolithiasis, cholelithiasis, cholecystitis and other diseases related to the Liver and Gall Bladder can be differentiated and treated in accordance with the exercises described in the prescription section.

ETIOLOGY

Hypochondriac pain may be caused by different factors such as trauma, the accumulation or blockage of Qi, stagnation of Phlegm and the Deficiency or Excess of Liver Qi (commonly seen in patients with Excess Liver Fire or Liver Qi stagnation). The symptoms of hypochondriac pain may occur in one or both sides.

SYNDROMES

- An Excess syndrome occurs when a patient suffers from Excess Liver Fire. This condition manifests with symptoms such as severe pain in the hypochondrium area with difficulty in breathing. The pain may radiate from both sides of the body, or from one side only.
- A Deficient syndrome occurs when a patient suffers from a Liver Yin and Kidney Yin Deficiency (often caused by mental depression or hemorrhage). This condition is observed clinically with symptoms such as a dull or sharp pain in the hypochondrium areas.

TREATMENT

1. Begin by stimulating the patient's Middle Dantian and Lv-14 and Lv-13 points at the front of the chest in the hypochondrium area (on both sides or the right side only). Next, stimulate the patient's mid-back around the Bl-17 and Bl-18 points and the base of the outside of the knees around the GB-34 areas.
2. Using the Extended Fan Palm hand technique, emit Qi into the patient's Lv-13 and Lv-14 points and the painful region of the chest and hypochondrium and begin purging the Toxic Qi, dredging it down the body and out of the extremities through the patient's Liver and Gall Bladder Channels.

TREATMENT MODIFICATIONS

- For patients with an Excess syndrome, extend energy into the patient's mid-back at the Bl-18 points. Then grasp and softly rock this tissue area to free the trapped Qi.
- For patients with a Liver and Kidney Yin Deficiency, emit Qi into the patient's Lower Dantian and Mingmen area using the Extended Fan Palm technique for 12 to 24 breaths.

PRESCRIPTIONS AND HOMEWORK

1. Have the patient perform the Liver Massage (see Chapter 39) and sound the healing tone "Shu" for 36 breaths.
2. If the pain is on the left side of the patient's chest, have the patient place his or her palms on the painful area and begin to purge the Toxic Qi from the midline of the thorax, down the left side of the body, following the Gall Bladder Channel to the ground, for nine breaths.
3. Finally, have the patient stand in a Wuji posture and focus the mind's intention on his or her palms. The patient then raises the arms sideways, like a bird stretching its wings (creating a "T" formation). Next, both arms embrace (as if holding an imaginary ball) at the Middle Dantian level. The patient imagines the Qi from the middle chest flowing downward and rooting into the Lower Dantian.

CHAPTER 44
QI EMISSION THERAPY FOR HEART DISEASES

INTRODUCTION

The Heart is a solid (Zang) organ and controls Blood circulation. The Heart corresponds to the element Fire and is sometimes referred to as the Red Emperor. The Heart houses the Shen and is in charge of mental activities and long term memory. It is energetically paired with the Small Intestine (a hollow organ), which is in charge of separating the pure, clean energy from the impure Qi (Figure 44.1).

The Heart's upper external connection with the outside is through the tongue, hence sensations of the tongue (from food, kissing and so on), as well as talking can travel directly into the spirit, mind, and emotion, affecting the Heart's desires and senses.

In the early summer months, the Heart energy becomes more active in individuals who already have strong Heart Qi, but can become Deficient in those who already have weak Heart Qi. Excessive eating and drinking of bitter foods, and overexposure to heat depletes the Heart.



Figure 44.1. The Heart (Ht) Channels

HEART COMPLICATIONS AND SYMPTOMS

The Heart is responsible for governing the flow of Blood through the body's arteries and veins. Coronary artery disease (CAD) is a disease in which the patient's coronary arteries begin to harden, or impede adequate vascular flow to the myocardium, resulting in an insufficient supply of Qi and Blood throughout the body. This causes such diseases as hypertension, vasculitis, myocarditis, congenital Heart disease, rheumatic Heart disease, nervous malfunctioning of the Heart, organic pathological changes of the Heart, and arteriosclerosis of the brain.

In general, patients with Heart disease may have an arterial pulse above the navel which often disappears upon pressing, as well as a hot sensation in the soles of the feet and palms, dry mouth, stiffness of the tongue, and absentmindedness. A list of Heart syndromes and their symptoms are described as follows.

1. Heart Qi Deficiency can cause such symptoms as: physical tiredness, palpitations, sweating, pallor, and shortness of breath when exerting oneself.
2. Heart Yang Deficiency can cause such symptoms as: tiredness, tightening in the chest, and edema.
3. Heart Blood Deficiency can cause such symptoms as: headaches, mental and emotional problems, tinnitus, and tiredness.

Men & Women Practices: Open Channels Differently

Once the channels have been completely opened, men and women practice differently. Without stopping, men will thrust the energy directly up through the Thrusting Channels and out of the crown. They then will bring the energy back in to flow down the Thrusting Channels and down through the soles of the feet into the ground. They can continue to bring the flow up around the body and in through the crown. Without stopping, women will thrust the energy down through the soles of the feet into the ground and then up through the Thrusting Channels to and out of the crown. They then spray the energy down around the body, tuck it under the feet and draw it back in through the toes.



For Men: Spiral six inches clockwise above the crown and draw the universal Chi down into the three Thrusting Channels and down to the ground.

For Women: Spiral six feet under the ground anticlockwise. Once the pool of energy is built up, draw the universal Chi plus the healing earth Chi up to the feet and through the body.

Fig. 7.4 *Cosmic Thrusting and Belt Channels*

4. Heart Blood stagnation can cause such symptoms as: mental and emotional problems, as well as tightness or pain in the chest.
5. Heart Yin Deficiency can cause such symptoms as: tiredness, insomnia, and mental and emotional problems.
6. Heart Fire can cause such symptoms as: insomnia, painful urination, and mental and emotional problems.

GENERAL TREATMENT FOR HEART DISEASES

The following is a description of a general protocol used for treating a patient's Heart. The goal is to introduce the Qigong doctor to the basic hand positions and areas of the patient's body towards which Qi is emitted (or Turbid Qi is removed). Once the Qigong doctor becomes proficient at locating these specific points, the treatment will flow more smoothly.

After comparing the various Heart therapies, the reader will notice that certain patterns repeat themselves.

1. Generally, the Qigong doctor can access the patient's Heart through four methods:
   - direct energetic insertion into the Heart's anatomical location,
   - the patient's channels,
   - the external energetic Wei Qi fields, or
   - the patient's Taiji Pole (Figure 44.2).

   To avoid energetic armoring (while accessing the Qi in the front of the Heart), it is important for the doctor to already be connected to the patient's Shendao point (through the back of the Heart).
2. After treating the patient (purging, tonifying, and regulating), the Qigong doctor stimulates the patient's Heart and Shendao area, and roots the Upper Dantian Qi into the Lower Dantian.
3. Next, the Qigong doctor leads any remaining Turbid Qi down the Pericardium and Heart Channels and out from the patient's hands (Figure 44.3).

Keep in mind that these areas are general and


Stimulate and Root the Heart through the Taiji Pole.
Access the patient's Heart through the Shendao (GV-11) point.
Root the Heart in the Lower Dantian

Figure 44.2. Treating Heart Conditions



Figure 44.3. Lead the Toxic Qi out of the body through the patient's Pericardium Channels.

that specific treatment patterns must change as they apply to the patient's exact condition (Excess, Deficient, etc.).

MEDICAL QIGONG THERAPY FOR HEART QI DYSFUNCTION

The primary therapies used to treat cardiovascular diseases include: the Windy Breathing method to strengthen the Heart and Kidneys, Toe-Raised Walking, Heart Massage, and Quiescent meditation (see Chapter 15).

- Patients with an Excessive Qi syndrome of the Heart with extreme Heat may have a flushed complexion, full pulse, and excess sputum; they may feel pain in the chest, hypochondrium, back, shoulders, and arms. This syndrome can be treated by having the patient utter the "Ha" sound while guiding the Kidney Water Qi upwards to suppress the Heart Fire (Figure 44.4). Alternatively, the Qigong doctor may guide the Evil Qi out of the patient's body along the Heart and Small Intestine Channels with Pulling and Leading Qi manipulations.
- Patients with Deficient Heart Qi may dream of flames and red colored objects and have a radiating pain in the abdomen. This condition can be treated by having the patient perform the Taking in Yellow Qi meditation (see Chapter 4) which replenishes the child (Spleen), and Taking in Pink Qi meditation to nourish the mother (Heart); or, by using the Pushing and Guiding Qi manipulations to reinforce the Heart Qi and the Qi in the Lower Dantian.

In this particular case (Deficient Qi syndrome of the Heart), the reason the patient should not take in the energetic color red is because the Heart has already established a draining pattern, and any energy pouring into the Heart will only continue to drain away.

HEART QIGONG PRESCRIPTIONS

To tonify the Heart, tranquilize the mind, promote Blood circulation, and remove obstructions in the channels, prescription exercises can be used. The following exercises can be used to prevent and treat diseases and syndromes such as coronary Heart disease, hypertension, angina, arrhythmia, rheumatic Heart disease, cardiac neurosis as well as palpitations (ranging from mild to severe), pericardial pain, and insomnia.



Figure 44.4. Treating Patients with an Excess Qi Syndrome of the Heart

PRESCRIPTIONS FOR TONIFYING THE HEART

Taking in the Red Qi can be used to tonify the Heart. The properties inherent within the color red have a persistent vibratory rate used for tonifying the Heart and Small Intestine.

1. Assume a standing, sitting, or lying posture. Relax the whole body, breathe naturally, and get rid of any stray thoughts.
2. As you inhale, visualize red energy in front of you. Inhale the red light energy in through the nose and down into the Heart organ. As you exhale through the mouth, the dark, pathogenic Qi leaves the Heart; however, the bright, clean color remains in the organ, stimulating and vitalizing it. With each breath the organ retains more clean energy and begins to glow. Repeat for five breaths.
3. Next breathe the red energy in through the nose and fill the entire mouth with it. When exhaling through the nose, send the Qi slowly to the Heart, then to the Lower Dantian, to connect the energy of the Heart and Kidneys and to remove obstructions in the whole body. Perform this exercise seven or fourteen times. Return to the first step and close the training.



Figure 44.5. Hands rest in front of the Lower Dantian.



Figure 44.6. Both palms simultaneously press forward.

PRESCRIPTIONS FOR PURGING THE HEART

Purge the Heart by having the patient rub his or her chest while sounding "Ha."

1. The preparatory postures are the same as above.
2. Begin by clicking the teeth, stirring the tongue, and swallowing the saliva, then place the palms on the pectoral region of the left side of the chest (left hand on the outside for men, opposite for women). Inhale slowly, then gradually exhale the sound "Ha," focusing the mind on the Heart area. Repeat for six to twelve breaths altogether while rubbing with the palm lightly in a clockwise circle.

PRESCRIPTIONS FOR REGULATING THE HEART AND CONDUCTING QI

The following exercise is used to regulate the Heart after purging or tonifying.

1. Assume a standing or sitting posture. Relax the whole body, breathe naturally, and raise the tongue against the hard palate, just behind the teeth. Bring both palms loosely together (left over right for men, opposite for women) at the Lower Dantian; stand still for several minutes and concentrate the mind on the Lower Dantian (Figure 44.5).
2. Turn both palms outward, and push the arms along the sides of the body towards the back. Hold this posture for several minutes.
3. Turn both palms upward and lift them to the sides of the chest.
4. With both palms facing forward, stretch both hands level and forward. Focus your attention on the ends of the middle finger of each hand, while the thumb and little fingers stretch and separate (Figure 44.6).
5. Clench both hands into fists and pull them along the sides of the body towards the back, as if dragging heavy weights. Perform this movement three times (Figure 44.7).
6. Raise the right palm, as if holding a heavy weight in front of the chest, and push the palm out vertically to the right. Then, draw the right hand back to the side of the body near the hip. Repeat on the left side, and finally return to the starting posture. Perform these movements three times (Figure 44.8). This completes one set. Perform three sets.

SPECIFIC MEDICAL QIGONG THERAPY FOR HEART DISEASES

The following are several Medical Qigong Treatments used in China to treat specific Heart diseases.

HYPERTENSION

Hypertension is considered a condition in which the patient has higher blood pressure then what is determined to be normal for his or her



Figure 44.7. Both hands simultaneously clench into fists and pull to the hips.



Figure 44.8. Alternate each palm as it presses towards the side of the body.

chronological age and physique. Generally, Traditional Chinese Medicine places it in the categories of vertigo and headache.

ETIOLOGY

Hypertension is one of the most common problems impacting the Heart. It is the result of an imbalance of the Yin and Yang functional aspects of Deficient Kidney Yin and Excess Liver Yang, and/or an overabundance of Phlegm and Dampness within the body.

Hypertension can be caused by the patient eating too much food or salt, by too much stress, or not enough exercise. A renin imbalance within the patient's Kidneys, increased cholesterol, a preexisting genetic predisposition, a secondary illness (diabetes, nephritis, or hyperthyroidism), or even pregnancy can also lead to hypertension. These causes of hypertension can result in one of three internal factors: high cardiac output due to stress, reduced elasticity of the vessels, and resistance to Blood flow.

1. When the body experiences emotional tension it releases adrenaline, which speeds up the Heart rate and causes the blood vessels to narrow, increasing the body's blood pressure.
2. A buildup of plaque and normal aging reduces the vessel's elasticity and can lead to hypertension.
3. Old age, certain hormonal imbalances or disorders, or a genetic predisposition can likewise cause high blood pressure.

The overall goals in treating hypertension patients are to:

1. Lower blood pressure,
2. Stabilize blood pressure,
3. Establish a quiescent state of mind (generally, meditating 20 minutes, twice a day provides the patient with a prolonged state of deep relaxation needed to combat stress), and
4. Encourage life-style changes (i.e., monitor potassium intake, decrease sodium intake, weight control, and stress reduction management). Treatment programs are established as described below.

SYNDROMES

As previously stated, there are three underlying causes or syndromes relating to hypertension: Excess Liver Yang, Deficient Yin, Excess Liver Fire, and Kidney Yin and Yang Deficiency.

1. If the body's Kidney Yin is Deficient, it fails to nourish the Liver Yin, which leads to a condition of hyperactivity of Liver Yang. The clinical manifestations are feelings of fullness in the head, daydreaming, headaches, dizziness, tinnitus, insomnia, and dysphoria with feverish sensations in the chest.
2. Excess Liver Fire can cause headaches, dizziness, restlessness, irritability, flushed face, and constipation.
3. If the body's Kidney Yang is Deficient the Yin (Water) accumulates, if the Yang does not move, the blood vessels cannot relax. This results in

obstructed Blood flow. The clinical manifestations are dizziness and tinnitus, daydreaming, palpitations, amnesia, lassitude and weakness in the legs, as well as insomnia.

TREATMENT FOR PATIENTS SENSITIVE TO ENERGY

1. Use Medical Qigong therapy, and have the patient sit in a chair with his or her feet flat on the ground. Begin the treatment by cleaning the patient's Conception and Governing Vessels, using purgation methods. Focus specific attention on clearing the patient's head area (Figure 44.9). Literally sweep with the entire hand, and comb the patient's Wei Qi fields with the fingers.

   By scanning the occipital region of the patient, you can verify that the Excess Qi in the patient's upper extremities has abated. Once these vessels are clean, you can focus on treating the hypertension.
2. Stand behind the patient, using the Extended Fan Palm technique (with both hands) extend energy from the left hand into the top of the patient's head at the Baihui GV-20 area, while your right hand extends energy into the back of the patient's head, beginning at Yuzhen Bl-9. The two streams of Qi flow downward to the Dazhui GV-14 area, where they join into one river, which continues to flow downward through the patient's Taiji Pole. Continue to visualize these two streams joining and filling the Lower Dantian, for a period of 6 to 12 breaths (Figure 44.10).
3. Next, move your left hand and extend energy into the patient's Yellow Court, while your right hand is placed above the patient's Mingmen area. Lead the Qi from the Yellow Court into the patient's Lower Dantian, continuing to root the Qi, for a period of 6 to 12 breaths.

TREATMENT MODIFICATIONS

These modifications are additional formulas which are added onto the previous treatment according to the specific cause and condition of the patient's Heart.

1. When treating patients with Excess Liver Yang and Deficient Yin, use the Extended Fan Palm



Figure 44.9. The Qigong doctor begins by dredging, purging and cleaning the patient's Conception and Governing Vessels.



Figure 44.10. The Qigong doctor emits Qi into the patient's Baihui, Yuzhen and Dazhui points, in order to access the Taiji Pole and fill the patient's Lower Dantian.

hand technique and emit Qi into the patient's mid-back, drawing the energy down and rooting it in the patient's Lower Dantian and Mingmen.

2. When treating patients with Excess Liver Fire, it is important to treat the Lv-13 and -14 points, by dredging and purging the Excess Qi, and leading it down the patient's right Gall Bladder Channel, through the foot and into the Earth.
3. When treating patients with Kidney Yin and Yang Deficiency, use the Extended Fan Palm technique to emit Qi into the patient's mid-back, drawing the energy down and rooting it in the patient's Lower Dantian and Mingmen.

TREATMENT FOR PATIENTS NOT SENSITIVE TO ENERGY

Use Jing Point therapy in conjunction with Medical Qigong therapy (see Chapter 36). Have the patient lie prone. Using the Sword Finger technique, touch the patient's head with the left hand and extend energy into the Baihui GV-20 point. Guide this Qi down to the Lower Dantian through the Taiji Pole, while your right hand embraces and energizes the patients' Mingmen GV-4 point, thereby filling the Lower Dantian and rooting the patient's Heart Qi (Figure 44.11). Next, treat the patient's LI-11, St-36, Lv-2, and Sp-6 points on both sides of the body to lower the patient's blood pressure.

PRESCRIPTIONS AND HOMEWORK

1. A static posture can be given to convalescing patients as part of a meditative homework prescription for treatment of high blood pressure. The prescription is as follows.
   a. Have the patients lie supine (the patients may use a pillow under the head for comfort) and have him or her imagine that they are floating in warm water.
   b. The patients should perform the toning sound "Zheng" (prenounced Jang), and imagine dispersing Qi out of his or her body. The patient should use natural breathing while toning and dispersing the Toxic Qi. There are ten major areas, from the top of the head to the bottom of the feet, from which the patients must discharge the toxins. These areas include: the top of the head, Upper Dantian, throat, Middle Dantian, Yellow Court, Lower Dantian, the center of the thighs, knees, ankles, and bottom of the feet (Figure 44.12).
   c. After several minutes the patients will relax and focus their attention on the Lower Dantian or Bubbling Well points at the bottom of the feet.



Figure 44.11. If the patient is not sensitive to energy, have them lie prone, and apply Jing Point Therapy in conjunction with Qi emission.



Figure 44.12. In this Static posture used to treat high blood pressure the patient lies supine and performs the toning sound "Zheng" (Jang), for dispersing Qi.

2. Another meditation prescription given to patients with hypertension is to have them sit and imagine the feeling of warm water pouring down over the head, torso, extremities, and feet. This meditation should be practiced several times a day, using 36 breaths each time.
3. The patient can also be given the prescription of rubbing the hypochondrium and toning the sound "Shu" to purge Excess Heat from the Liver.

PALPITATION

A palpitation is an abnormally rapid throbbing or fluttering of the Heart. The symptom is characterized by nervous feelings or restlessness due to strong anxitey or fright. Clinically, it mostly attacks paroxysmally and is caused by emotional stress or overexertion. Symptoms such as insomnia, vertigo, tinnitus, etc. often accompany palpitations.

Diseases with palpitation as the main manifestation include arrhythmia, iron-deficiency anemia, aplastic anemia, hyperthyroidism and anxiety disorders. These diseases may all be differentiated and treated in reference to the prescriptions described in this section.

ETIOLOGY

There are several factors which contribute to palpitations. These factors and their symptoms are described as follows.

1. In patients suffering from Deficient Qi and Blood, and Deficient Heart Qi, palpitations may occur following sudden mental irritation. The patient may note unduly rapid heartbeat accompanied, in cases of Deficient Heart Qi, by pallor, restless sleep at night, dizziness and vertigo. This condition may also be caused by Deficient Heart Blood that fails to nourish the Heart.
2. Phlegm Fire disturbing the Heart may also give rise to palpitations. In cases with internal disturbances of Phlegm Fire, symptoms also include fidgeting and disorientation.
3. Another factor causing palpitations is a Deficiency of Heart Yang that leads to fluid retention. In cases of fluid retention with epigastric stiffness symptoms will also include: dizziness, excessive salivation and mental fatigue.

TREATMENT

1. Begin by extending Qi into the patient's Bl-14, Bl-18, CV-15, and CV-17 points. To open up these points, emit Qi into the tissue areas surrounding these points using the Extended Fan Palm technique.
2. Next, use the Sword Fingers hand technique and vibrate Qi into each of these points for the duration of six to twelve breaths at each point. Upon completion, the doctor will then guide the Qi back down the patient's torso and root it into the patient's Lower Dantian.
3. Finally, the doctor emits Qi into the patient's Yellow Court area using the Extended Fan Palm technique and then guide the Heart and Pericardium Channel Qi down the patient's arms using Pushing, Pulling and Leading techniques. This ending is performed to balance the Qi in the upper and lower aspects of the patient's body.
4. As with every treatment, end the procedure by regulating the patient's Microcosmic Orbit (Fire Cycle).

TREATMENT MODIFICATIONS

These modifications are additional formulas which are added onto the previous treatment according to the specific cause and condition of the patient's Heart.

1. In cases of insufficiency of Heart Blood, add Bl-17 and Bl-20 to the treatment points.
2. In cases of internal disturbance of Phlegm Fire, purge from the CV-12 to St-40 points.
3. In cases of Fluid retention, add Bl-21 and Bl-22 to the treatment points, for 14 to 24 breaths. Then, guide the Qi to flow down the patient's Gall Bladder Channels into their Bl-40 points.

PRESCRIPTIONS AND HOMEWORK

1. For treatment of palpitations due to Deficient Heart Blood, have the patient practice the method of Taking in the Red to nourish the Heart (see Chapter 4). Have the patient send the red Qi slowly down into the Heart and then to the Lower Dantian during the exhalation. Practice should be for several minutes, according to the patient's strength and constitution.
2. For treatment of palpitations due to Phlegm Fire, have the patient place both hands on the Heart and slowly inhale. As the patient exhales, he or she should pronounce the sound "Ha." This exercise should continue for several minutes.
3. For Heart regulation, have the patient practice the Heart exercise from the Daoist Five Yin Organ prescriptions (see Chapter 42).

RHEUMATIC HEART DISEASE

Rheumatic valvular Heart disease is a condition where there is chronic damage of the cardiac valve caused by rheumatosis. It clinically manifests with palpitations, dyspnea and edema.

SYNDROMES

1. Heart Blood stagnation is manifested through symptoms such as severe palpitations, bad cough with hemoptysis, lassitude and weakness, purplish-red color of the lips, nails and zygomatic facial regions, pain in the Heart, chest, or both.
2. Deficient Qi and Blood manifests through such symptoms as shortness of breath, palpitations which are aggravated on exertion, perspiration and pale complexion.
3. Heart and Kidney Yang Deficiency manifest through such symptoms as palpitations, pale or darkish complexion, edema, cough, cold hands and feet and dyspnea.

TREATMENT

1. Have the patient sit at the edge of the table, and begin to stimulate the Shendao (GV-11) and Middle Dantian areas.
2. Use the Vibrating Palm hand technique and emit Qi into the patient's Yellow court and Shendao (GV-11) area for 6 to 12 breaths.
3. Use the Extended Fan Palm hand technique and emit Qi into the patient's Heart region, leading Qi down the Heart and Pericardium Channels to the tips of the fingers (on both sides of the body).

TREATMENT MODIFICATIONS

1. When treating patients with Heart Blood stagnation, use the Extended Fan Palm hand technique and emit Qi into the patient's Middle Dantian, leading the stagnant Qi down the Heart and Pericardium Channels and out the hands (on both sides of the body).
2. When treating patients with Deficient Qi and Blood, use the Extended Fan Palm technique and emit Qi into the patient's Middle Dantian (both Shendao GV-11 and CV-17 areas), leading the Qi down the Conception Vessel to the Lower Dantian to root and stabilize the patient's Qi.
3. When treating patients with Heart and Kidney Yang Deficiency, use the Extended Fan Palm technique and emit Qi into the patient's Shendao (GV-11) and Mingmen (GV-4) for 24 breaths.

PRESCRIPTIONS AND HOMEWORK

When prescribing homework for patients with rheumatic Heart disease, have them begin with a quiescent sitting meditation, while focusing on their Lower Dantian.

PRESCRIPTION MODIFICATIONS

1. Have patients with Heart Blood stagnation perform the Heart Massage exercise (see Chapter 39), while toning the sound "Ha."
2. It is advisable for patients with Qi and Blood Deficiency to practice the method of Taking in the Yellow Qi into the Spleen and Red Qi into the Heart from the natural environment.
3. Have patients with Heart and Kidney Yin Deficiency practice Gathering the Moon Cream (see Chapter 11), as well as the method of Taking Yellow Qi into the Spleen and Red Qi into the Heart from the natural environment (see Chapter 4).

CONTRAINDICATIONS

The Heart may either have functional or structural problems. In either condition, Medical Qigong is contraindicated when working directly over a pacemaker.

Also, when treating Heart conditions, make sure the patient is under a Western doctor's care, and inquire as to any medications the patient may be taking.

CHAPTER 45
QI EMISSION THERAPY FOR SPLEEN/STOMACH DISEASES

INTRODUCTION

The Spleen is a solid (Zang) organ and it stores and nourishes Ying (Nourishing) Qi. The Spleen corresponds to the element Earth and is sometimes referred to as the Yellow Emperor. It houses the Yi, which governs the intention, thought, study, concentration, and memorization. It is energetically paired with the Stomach (a hollow organ). The Spleen is in charge of transporting, distributing and transforming nutrients and Qi into Gu Qi, as well as controlling Blood circulation (Figure 45.1).

The Spleen's external connection with the outside world is through the mouth, hence any connection with the mouth can affect the body's acquired constitution, developing a tolerance or intolerance to specific substances (allergies), as well as affect concentration and thought.

In the late summer months, Spleen Qi becomes more active in individuals who already possess strong Spleen Qi, but can become Deficient in those individuals who already have weak Spleen Qi. Excessive eating and drinking of sweet foods, and overexposure to dampness weakens the Spleen.

SPLEEN COMPLICATIONS AND SYMPTOMS

Because of the importance of both the Spleen and Stomach, this chapter is divided into two separate sections. The first section focuses on specific Spleen diseases and how to rectify them. The second section explores the energetic dysfunctions of the Stomach.

The following discussion of treatment begins with an explanation of Spleen complications and symptoms. Spleen syndromes have symptoms which are common to the organ's energetic dysfunction such as: diarrhea, tiredness, and edema. A list of Spleen syndromes and their symptoms are described as follows.



Figure 45.1. The Spleen (Sp) Channels

Practice of Opening the Thrusting Channels

1. Form a Pearl and Send it to the Perineum

In a seated position smile down to your organs and glands, and put yourself in a state of relaxation and happiness. Begin with the meditation exercises of the Creation Cycle to form a pearl of compassion energy.

As you have learned, there are many steps in forming such a pearl. However, once you have programmed yourself to all of these steps through continued practice, you can simply push the button and the whole program is activated. When you are able simply to sit quietly and feel the sensation of compassion energy forming, you are pushing the button and the entire process takes very little time. In other words once you have experienced compassion energy, all you need to do is to recall the state to create the energy again. You will not need to go through the entire process each time. You will know when you look at the pearl whether or not the process has been completed. If you find something is not right, you can review the steps and find out where the problem is.

As the pearl is forming, use your mind and senses to control it. Slowly move it down to the perineum. At any time during your practice, if the pearl seems to weaken, diminish, or you lose track of it, return to the navel and quickly form a new pearl. Bring that pearl to the perineum and resume practice.

While you are learning how to bring the energy up through the channels, it is easier to focus on the organs the channel passes through than to focus on the channel. You might think of the process as learning how to read. Once you are able to read, you no longer have to think about your ABC’s.

2. Stage One: Thrusting Channels to Below the Diaphragm

A. Left Thrusting Channel to the Diaphragm

In all Universal Tao practices it is important to train the power of the mind and senses to control our energy (Chi). The power of mind, eye and heart guides the Chi, providing a way to control and direct your life force. Breathing techniques also help to activate the Thrusting Channels. It is necessary to have some control over independent breathing through each nostril. Since in the beginning this is difficult to do, you can use your right index finger to cover the right nostril. Feel the breath on the left side only. Use the left eye, ear, and nostril to assist you in drawing up the energy.

1. Spleen Qi Deficiency can cause such symptoms as: wheezing, tiredness, abdominal pain, diarrhea, constipation, painful urination, enuresis, bleeding and menorrhagia.
    a. Patients with a failure of normal transporting and transforming Qi activity in the Spleen may have a poor appetite, abdominal distention, loose stools, edema and retention of Phlegm.
    b. Deficient Spleen Qi may cause the Qi in the Middle Burner to sink. This results in shortness of breath, unwillingness to talk, persistent diarrhea, prolapse of the anus or uterus, or gastroptosis (downward displacement of the Stomach).
    c. Spleen Qi Deficiency can result in failure of the Spleen to control the Blood circulation and may be manifested by the following symptoms: bloody stool, bleeding from the uterus, and subcutaneous hemorrhaging.
2. Spleen Yang Deficiency can cause such symptoms as: tiredness and edema.
3. Spleen Blood Deficiency can result in fatigue.
4. Spleen Yin Deficiency can result in tiredness.
5. Damp Heat in the Spleen can cause such symptoms as: sinusitis, edema, common cold, and influenza.
6. Dampness in the Spleen can cause such symptoms as: diarrhea, tiredness, edema, and Wind Stroke.

GENERAL TREATMENT FOR SPLEEN DISEASES

The following is a description of a general protocol used for treating the Spleen. The goal is to introduce the Qigong doctor to the basic hand positions and areas of the patient's body towards which Qi is emitted (or Turbid Qi removed). Once the Qigong doctor becomes proficient at locating these specific points, the treatment will flow more smoothly.

After comparing the various Spleen therapies, the reader will notice that certain patterns repeat


Energize the Deficient Spleen.
Energize the Lower Dantian.
Purge the Toxic Spleen Qi down the Stomach Channel and out the St-36 point.

Figure 45.2. Treating Spleen Conditions

themselves.

1. Generally, the Qigong doctor accesses the patient's Spleen through either direct energetic insertion into the Spleen's anatomical location, or through the patient's channels and external energetic fields.
2. After treating the patient (purging, tonifying, and regulating), the Qigong doctor stimulates the patient's Spleen and Yellow Court areas, and roots the patient's Middle Burner Qi into the Lower Dantian.
3. Next, the Qigong doctor leads any remaining Turbid Qi down the Stomach Channels and out of the patient's St-36 points (Figure 45.2).

Keep in mind that these areas are general and that specific treatment patterns must change as they apply to the patient's exact condition (Excess, Deficient, etc.).



Figure 45.3. The "Hu" sound will purge the Spleen.

MEDICAL QIGONG THERAPY FOR SPLEEN QI DYSFUNCTION

The primary therapy used to treat the Spleen and gastric diseases include the Windy Breathing method (see Chapter 16) to strengthen the Liver, Spleen, Lungs, and the Kidneys.

1. Spleen diseases should be treated by vocalizing the "Hu" sound, which is effective for removing Turbid Qi accumulated in the Spleen, as well as for aiding digestion (Figure 45.3).
2. To treat insufficiencies of the Middle Burner, the doctor emits Qi into the patient's Zhong Wan CV-12 point and Lower Dantian points to reinforce the patient's Qi in the Middle Burner area.
3. Patients with an Excess Heat syndrome of the Spleen should be treated by guiding the Qi out along the Spleen and Stomach Channels with Pulling and Leading Qi manipulations to expel the Turbid Qi from both the Spleen and Stomach.

SPLEEN QIGONG PRESCRIPTIONS

The following exercise regulates the Qi and Blood of the Spleen Channels, strengthens the Spleen and replenishes Qi. It also regulates the Stomach and promotes digestion. It can be used to prevent and treat diseases and syndromes such as: gastritis, gastric and duodenal ulcers, colitis and gastrointestinal neurosis, abdominal distention, diarrhea and constipation.

PRESCRIPTIONS FOR TONIFYING THE SPLEEN

The method of Taking in the Yellow Qi can be used to tonify the Spleen. The properties inherent within the yellow color have a persistent vibratory rate used for tonifying the Spleen and Stomach.

1. Assume a standing or sitting posture. Relax the whole body, breathe naturally, and get rid of any stray thoughts.
2. When inhaling, imagine yellow energy in front of you. Inhale the yellow light energy in through the nose and down into the Spleen organ. As you exhale through the mouth, the dark, pathogenic Qi leaves the Spleen; however, the bright clean color remains in the organ, stimulating and vitalizing it. With each breath the organ retains more clean energy and begins to glow. Repeat for five breaths.
3. Next breathe the color yellow in through the nose, filling the entire mouth. When exhaling through the nose, send the Qi slowly to the Zhongwan CV-12 point, then out to the four limbs, skin, and hair. Repeat five to ten times. Return to the beginning posture and close the training.



Figure 45.4. Twist at the waist, swing the arms, and look towards the opposite direction, focusing the mind's intention on the heel.



Figure 45.5. Turn and look over the shoulder with both eyes wide open.

PRESCRIPTIONS FOR PURGING THE SPLEEN

Purge the Spleen by having the patient rub his or her epigastrium while toning the sound "Hu."

Assume a sitting or standing posture. Gently place both palms (left on the outside for men, opposite for women) flatly on the Zhongwan CV-12 point on the upper abdomen. Exhale, rubbing the palms in a clockwise direction while sounding "Hu". Perform ten to twenty breaths.

Dredging the Spleen and Stomach

The following exercise is used to purge Toxic Qi from the Spleen and Stomach.

1. Assume a standing posture and breathe naturally. While relaxing the whole body, twist at the waist as you swing both arms in front of the body to the left, then to the right. Look in the opposite direction when turning the torso. As you turn your torso, your mind should be focused on your heels. Continue until you feel all tension has left your body (Figure 45.4).
2. Assume a sitting posture. While sitting on a bed, press the palms level on the mattress and meditate until you feel peaceful and relaxed. Turn the head towards the left and look over your left shoulder into the distance. Then turn the head to the right and look back over your right shoulder into the distance. Pause in the center, facing forward (Figure 45.5). When looking over the shoulders, both eyes should be wide open. Repeat five times in each direction.

PRESCRIPTIONS FOR REGULATING THE SPLEEN AND CONDUCTING QI

The following exercise is used to regulate the Spleen after purging or tonifying.

1. In a Wuji posture, begin by placing the hands on the Yellow Court and begin circle rotation in a clockwise direction for 36 rotations, ending at the Lower Dantian. Pause for 18 breaths to root the Spleen Qi in the Lower Dantian.
2. Next, rotate the abdomen in a counterclockwise direction for 36 rotations, ending at the Lower Dantian. Pause for 18 breaths and return to Wuji posture.

SPECIFIC MEDICAL QIGONG THERAPY FOR SPLEEN DISEASES

The following Medical Qigong treatment is used in China to treat specific types of Spleen disease.

DIABETES

Diabetes refers to a syndrome characterized by polydipsia (excessive thirst), polyphagia (excessive eating), and emaciation. It is a general term used to describe diseases characterized by insufficient secretion of insulin and excessive urination.

The prescriptions described in this section can also be used for the treatment of such disorders as: psychogenic polyuria, polyphagia due to hyperthyroidism, hyperhidrosis (excessive sweating), and emaciation.

ETIOLOGY

According to Traditional Chinese Medicine, diabetes is caused by disturbances in the Spleen and Stomach functions of transforming and transporting energy and the accumulation of toxic Heat in the body. These malfunctions can be due to eating too much sweet and greasy food, or drinking too much alcohol.

From the Western medical perspective, there are two types of diabetes, one type can be controlled through diet, the other cannot (usually hereditary). Diabetes is included in metabolic diseases (the Beta cells in the pancreas do not produce enough insulin) and caused by pathogenic factors relating to genetic predispositions, environmental stress, diet, obesity, and alcohol consumption.

In the Medical Qigong clinic there are three main factors that can contribute to the origination of diabetes: improper diet, emotional factors, and congenital predisposition.

1. The first factor is due to improper diet, including the excessive intake of alcohol, acrid, sour, pungent and greasy foods. The excessive intake of these types of foods can cause stagnation at the Middle Burner (which houses the Stomach and Spleen), and failure of the Stomach and Spleen to transport the accumulated Heat inside the body. This in turn can give rise to failure of the body's Yin fluids to nourish the Lungs and Kidneys, resulting in diabetes.
2. The second factor is due to a state of constant emotional upheaval. Emotional upsets can lead to stagnation of Qi which in turn impairs the body's Fluids, causing a Yin Deficiency with a hyperactivity of Evil Fire, resulting in diabetes.
3. The third factor is due to a genetic predisposition that can eventually surface if the patient is negligent with his or her diet and emotional health.

The Qigong doctor focuses on strengthening the patient's Spleen and Stomach, regulating the Liver Qi, and tonifying the Lung, Stomach, and Kidney Yin (which has been consumed by the Toxic Heat). It also is helpful to monitor the patient's eating habits to correct the disturbed metabolic rate and promote the regeneration and secretion by the patient's pancreatic islet cells.

SYMPTOMS

1. Diabetes involving the Upper Burner is characterized by excessive thirst, dry throat, dry tongue, and frequent urination.
2. Diabetes involving the Middle Burner is characterized by consuming abnormally large quantities of food during meals, emaciation, or constipation.
3. Diabetes involving the Lower Burner is characterized by frequent sweet smelling urination, or chyluria (passing of fat globules in the urine), and weakness and softness in the waist and knees.

TREATMENT

1. Begin by stimulating the Bl-23, Bl-20, Bl-13, St-36, and Sp-6 points on both sides of the patient's body.
2. Then purge and dredge the patient's CV-12, CV-4, and St-21 points.
3. Next, use the Extended Fan Palm hand manipulation with the Vibrating Palm technique to emit Qi into the patient's Bl-23, Bl-20, Bl-13, CV-12, and CV-4 for six to twelve breaths.
4. Continue emitting Qi into those points and into the Middle Dantian to regulate the Qi

activities of the Upper, Middle, and Lower Burners.

5. End the treatment by softly holding on to the patient's LI-11, LI-4, and Ht-1 points on both sides of the body, and with a gentle rocking or shaking motion allow the Qi to flow into the patient's body, settling into the patient's Lower Dantian.

PRESCRIPTIONS AND HOMEWORK

The "Inner Health" cultivation meditation is given to patients with diabetes, and is prescribed as follows.

1. Have the patient begin in a sitting posture, eyes closed, body relaxed using natural abdominal breathing.
2. While inhaling, the patient places the tongue against the hard palate, and begins to mentally repeat the mantra "I am quietly sitting."
3. While holding the breath, the patient mentally continues by saying the words "I am healthy."
4. The patient then exhales, releasing the tongue from the palate, while thinking the last phrase.

MEDICAL QIGONG THERAPY AND STOMACH DISEASES

This second section focuses on specific Stomach diseases and how to rectify them (Figure 45.6). The following discussion of treatment begins with an explanation of Stomach syndromes and symptoms. Several Stomach diseases have symptoms which are quite common to the organ's energetic dysfunction, such as epigastric pain.



Figure 45.6. The Stomach (St) Channels

STOMACH COMPLICATIONS AND SYMPTOMS

A list of Stomach syndromes and their symptoms are described as follows.

1. Stomach Heat can cause headache, epigastric pain, and bleeding.
2. Stomach Damp Heat can cause sinusitis and epigastric pain.
3. Stomach Phlegm Fire can cause epigastric pain and mental and emotional problems.
4. Stomach Deficiency can cause epigastric pain, diarrhea, atrophy syndrome, and bleeding.
5. Stomach Yin Deficiency can cause tiredness, epigastric pain, and bleeding.
6. Cold invading the Stomach can result in epigastric pain.
7. Stagnant Blood in the Stomach can result in epigastric pain.

GENERAL TREATMENT FOR STOMACH DISEASES

The following is a description of a general protocol used for treating the patient's Stomach. The goal is to introduce the Qigong doctor to the basic hand positions and areas of the patient's body towards which Qi is emitted (or Turbid Qi removed). Once the Qigong doctor becomes proficient at locating these specific points, the treatment will flow more smoothly.

After comparing the various Stomach therapies, the reader will notice that certain patterns repeat themselves.

1. Generally, the Qigong doctor accesses the patient's Stomach through either direct energetic insertion into the Stomach's anatomical location, or through the patient's channels and external energetic fields.
2. After treating the patient (purging, tonifying, and regulating), the Qigong doctor stimulates the patient's Stomach, Spleen, and Yellow Court areas, and then roots the patient's Middle Burner Qi into the Lower Dantian.
3. Next, the Qigong doctor leads any remaining Turbid Qi down the Stomach Channels and out of the patient's St-36 points (Figure 45.7).

Keep in mind that these areas are general and that specific treatment patterns must change as they apply to the patient's exact condition (Excess, Deficient, etc.).

SPECIFIC MEDICAL QIGONG THERAPY FOR STOMACH DISEASES

The following are several Medical Qigong treatments used in China to treat specific Stomach diseases.

ABDOMINAL PAIN

Abdominal pain is an abnormal condition of the abdomen in which there is a sudden, abrupt onset of severe pain in any part of the abdomen below or just around the umbilicus.

Diseases such as acute pancreatitis, gas-


Stimulate the patient's Stomach and Yellow Court area.
Energize the Lower Dantian.
Purge the Toxic Stomach Qi down the Stomach Channels and out the St-36 points.

Figure 45.7. Treating Stomach Conditions

trointestinal spasm, stress induced abdominal pain, dyspeptic abdominal pain, and peritonitis, etc., in which abdominal pain symptoms appear, should be differentiated. Each differential diagnosis can be treated according to the exercises taught in the prescription section.

ETIOLOGY

The treatment for abdominal pain that is primarily intestinal in origin is different then that of gynecological abdominal pain, which is related to the menstrual cycle (see Chapter 51). There are four main factors which can contribute to the intestinal type of abdominal pain: abdominal pain due to the internal accumulation of Cold in the Lower Burner, abdominal pain due to dysfunction of Spleen Yang, abdominal pain due to food stagnation, and abdominal pain due to emotional stress.

1. Internal Cold in the Lower Burner may accumulate from eating too many cold foods and drinks, or can be due to the invasion of pathogenic Cold caused by exposure to the elements. Women in particular are more prone to Cold invading the abdomen during or immediately after menstruation. When Cold contacts the tissues, it slows down the movement of Qi and Blood, thus causing pain. External Cold may invade the patient's intestines directly without causing exterior symptoms, resulting in a sudden onset of pain and diarrhea.
2. Patients who are usually Deficient in Yang Qi often have a weak digestive system and a dysfunction of the Spleen Yang Qi. In this condition, pain often follows a pathogenic invasion, no matter how mild it may be. The pathogenic invasion may be due to overeating, overexertion, or brought on by eating after fasting and dieting, or simply by an Exterior Cold invasion.
3. Food stagnation is related to food intake or constipation, and is induced by Qi stagnation. The Stomach fails in digesting the food and the Spleen fails in separating and transporting the Clear and Turbid Qi.
4. Emotional stress is related to the circulation of Qi and Blood in the abdomen, and thus affects both the Liver and Spleen. Anger, frustration, and resentment can cause Liver Qi stagnation in the intestines, resulting in abdominal pain. Pensiveness and worry affect the Spleen and Lungs, impairing the transforming ability of the Spleen Qi and the downward descending ability of the Lung Qi, and likewise result in abdominal pain.

SYMPTOMS

1. Abdominal pain due to the internal accumulation of Cold, occurs abruptly, and may be relieved by defecation.
2. Abdominal pain due to Spleen Yang dysfunction, is characterized by continuous recurring pain, which may be relieved by pressure. Symptoms include loose stool, mental fatigue, and aversion to Cold.
3. Abdominal pain due to food stagnation, is characterized by gastric and abdominal distention, severe tenderness in the abdominal area, aversion to food and belching with acid regurgitation.
4. Abdominal pain due to emotional stress, is characterized by crying and vomiting.

TREATMENT

1. Have the patient lay on his or her side and begin stimulating the Bl-21, Bl-20, CV-12, St-36, and St-25 points on both sides of the body.
2. Purge the patient's Bladder Channels from the mid-back and waist area down to the feet three to five times.
3. Using the Vibrating Palm, emit Qi into the patient's CV-12, St-25, Bl-21, and Bl-20 points on both sides of the body. Purge and guide the Toxic Qi through the abdomen and down the lower extremities along the Stomach and Bladder Channels and out the patient's feet.
4. Using the Extended Fan Palm technique, extend Qi into the patient's CV-12 and both St-25 points for 14 breaths. Using Pulling and Leading manipulations, guide the patient's Qi down along the Stomach Channels and out both of the patient's feet.
5. Finally, Circle Rotate the patient's abdomen for 81 breaths in a clockwise direction.



Figure 45.8. To tonify Deficient Stomach Qi, the patient must imagine drawing Qi into the body through the Baihui point at the top of the head, and the Yongquan points at the bottom of the feet. All three rivers of energy must meet to form a pool of energy within the Stomach area, which the body will absorb and store.



Figure 45.9. To treat Excess Stomach Qi, begin from a supine posture. While inhaling, imagine the Qi flowing down the Stomach Channels from the Baihui point ending just below the sternum at the Stomach area. Exhale and imagine the Turbid Qi dissolving and melting into the Lower Dantian, then disperse it from the body, out the pores.

TREATMENT MODIFICATIONS

1. In cases of abdominal pain due to the internal accumulation of Cold, add the method of extending Hot Qi.
2. In cases of pain due to Spleen Yang dysfunction, extend Hot Qi into the patient's Bl-21, Bl-20, and Mingmen area.
3. In cases of pain due to food stagnation, emit Qi using the Extended Fan Palm with clockwise then counterclockwise Spiraling methods into the patient's CV-12, CV-4, and St-25 points.
4. In cases of pain due to emotional stress, emit Qi using the Extended Fan Palm hand technique into the patient's Ht-7 and Pc-6 points on both sides of the body. Purge and Circle Massage the Shendao (GV-11) area in a counterclockwise direction.

PRESCRIPTIONS AND HOMEWORK

1. Have the patient place his or her right palm on the CV-12 area and begin to Circle Massage 36 times in a clockwise and then 36 times in a counterclockwise direction.
2. After completing the circle rotations, the patient pauses for a moment, and then leads the Qi down to the navel and continues the 36 rotations, in both clockwise and counterclockwise directions.
3. Next, the patient inhales and presses the fingers of both hands gently below the xiphoid process. The patient exhales and directs the Qi down along the midline of the body to the pubic symphysis area for 36 times.
4. Finally the patient overlaps his or her hands (right over the left in men and opposite in women) and places them on the midpoint of the lower abdomen to knead the tissue area clockwise and then counterclockwise 36 times.

PRESCRIPTIONS MODIFICATIONS

- In cases of Stomach pain due to Deficient Stomach Qi, have the patient lie supine. The patient must imagine drawing Qi into his or her body through the Baihui point at the top of the head, and the Yongquan points at the bottom of the feet. All three rivers of energy must meet to form a pool of energy within the Stomach area, which the body will absorb and store into the Stomach's spacial cavity (Figure 45.8).

- In cases of Stomach pain due to Excess Stomach Qi and to treat Excess Stomach Qi symptoms, have the patient lie supine. As the patient inhales, he or she is to imagine the Qi flowing down the Stomach Channels (from the Baihui point) ending just below the sternum at the stomach area. As the patient exhales, he or she imagines the Turbid Qi trapped within the Stomach dissolving and melting into the Lower Dantian. Next, the patient disperses the Toxic Qi from the body out through the pores (Figure 45.9).

CHRONIC GASTRITIS

In Traditional Chinese Medicine, this disease belongs to the category of epigastralgia. Gastritis is described as an inflammation of the Stomach. Inflammation of the gastric mucosa is the main clinical manifestation of chronic gastritis, and results in chronic epigastralgia and dyspepsia (air hunger, resulting in difficult breathing, shortness of breath, sometimes accompanied by pain).

ETIOLOGY

Generally, emotional factors such as worry, anxiety, or anger may cause stagnation of Qi. Stagnant Qi, by impeding the function and flow of the body's energy, causes Qi deviations and obstructions that result in a stomach ache.

Gastritis can be superficial (affecting only the superficial layers of the Stomach) or atrophic (causing thinning of the Stomach mucosa). Its main manifestations are epigastric pain, which occurs about one hour after eating, followed by nausea, belching, and vomiting with sour regurgitation.

SYNDROMES

1. Liver and Stomach Qi stagnation, manifests as a distending pain, fullness, and discomfort in the Stomach, which is aggravated after a meal. The pain is not fixed to any specific Stomach location and worsens under emotional stress, causing belching with acid regurgitation and nausea.
2. Stomach Yin Deficiency due to Stomach Heat manifests as a stomach ache accompanied by a scorching sensation. The pain is not fixed to any specific Stomach location and is aggravated when the Stomach is empty, and is alleviated after a meal. The symptoms are expressed as irritability, dysphoria, and excess appetite.
3. Weakness of the Spleen and Stomach manifests as a dull stomachache which is relieved by Heat and pressure. Symptoms are expressed as abdominal distention, dim complexion, lassitude, cold limbs, and anorexia. If the patient has congenital insufficiency of Yang in the Middle Burner (the functional area of the Spleen and Stomach), Cold may originate from the interior of the body.

TREATMENT

1. Have the patient lie supine and relax his or her whole body, focusing especially on the Stomach area. The patient imagines the Toxic Qi dispersing upon exhalation.
2. Begin to purge and dredge the patient's CV-15 point (just below the xiphoid process), leading the Qi down to the Lower Dantian.
3. Next, use a Vibrating Palm hand technique to emit Qi into the patient's CV-12 point and both St-21 points for 14 to 28 breaths.
4. Applying the Extended Fan Palm hand technique to the patient's CV-12 and Middle Dantian, begin drawing Qi downward along the Conception Vessel and Stomach Channels to the bottom of the patient's feet.
5. Finally, have the patient lie prone and stimulate the Bl-20 and Bl-21 points on the lumbar-dorsal region, directing the energy from the upper back down to the Mingmen area.

TREATMENT MODIFICATIONS

1. For Stagnant Liver and Stomach Qi, use the Extended Fan Palm hand technique to emit Qi into the patient's Bl-18 points, pulling and conducting Qi along the Gall Bladder and Liver Channels down the legs and out the feet on both sides.
2. For Stomach Yin Deficiency due to Stomach Heat, use the Vibrating Palm hand technique

to emit Qi into the patient's Bl-20 and Bl-23 points, leading the Qi down the patient's Bladder Channels to the feet.

3. For Spleen and Stomach Deficiency, use the Extended Fan Palm hand technique to emit Qi into the patient's Lower Dantian area.

PRESCRIPTIONS AND HOMEWORK

Have the patient practice the Descending the Yang and Ascending the Yin technique (see Chapter 41).

PRESCRIPTION MODIFICATIONS

1. For patients with Liver and Stomach Qi stagnation, have the patient practice the Spleen and Stomach Massage (see Chapter 39). Then perform the healing sounds "Hu" to regulate the Spleen and "Shu" to regulate the Liver.
2. For treating patients with Stomach Yin Deficiency due to Stomach Heat, have the patient first dredge the Spleen and Stomach and then perform the "Chui" (pronounced Chree) healing sound to regulate the Kidneys. Next, have the patient practice the tonification method of Taking in the Yellow Qi (see Chapter 4).
3. For treating patients Deficient Spleen and Stomach Qi, have the patient first practice the Daoist Five Organ Regulation exercise (see Chapter 42). Next, have the patient practice the tonification method of Taking in the Yellow Qi to strengthen the Spleen and Taking in the Red Qi to strengthen and regulate the Heart.

GASTRIC AND DUODENAL ULCERS

An ulcer is an open sore or lesion of the skin or a mucus membrane, accompanied by sloughing of inflamed, dead, or dying tissue, that causes the Stomach's lining to become more vulnerable to acids. If the sore becomes infected puss is discharged.

ETIOLOGY

A gastric or duodenal ulcer refers to a chronic ulcer seen only in the regions where the gastrointestinal tract contacts the patient's gastric juice. Its formation and development is closely related to the digestive functions of the acidic gastric juices and pepsin. Clinically this type of ulcer is characterized by chronic recurring epigastralgia, lasting for a few weeks, with pain occurring from 30 minutes to two hours after eating.

Currently, Stomach ulcers are also being treated through either herbs or antibiotics (from Western medicine). They are caused by bacterial infections resulting from either Qi and Blood stagnation or a Deficient Cold syndrome of the Spleen and Stomach.

SYNDROMES

- Qi and Blood stagnation results in a distended pain and fullness in the Stomach, tenderness, belching, and acid regurgitation, which becomes aggravated by emotional stress.
- A Deficient Cold syndrome of the Spleen and Stomach results in a dull pain within the Stomach which is relieved by heat and compression and aggravated by cold. There can also be vomiting with watery regurgitation, shallow complexion, cold extremities, lassitude, and weakness.

TREATMENT

1. Have the patient sit at the end of the treatment table, and begin extending energy into the patient's mid-back along their Bl-18, Bl-20, and Bl-21 points using the Extended Fan Palm technique.
2. Next, use the Vibrating Palm to extend energy into the patient's Yellow Court area. When the area has been sufficiently stimulated, purge the Toxic Qi out of the patient's body by leading the Qi down to the Lower Dantian for 14 to 28 breaths.
3. Finally, use the Extended Fan Palm hand technique to emit Qi into the patient's CV-12 and St-34 points for 14 breaths. Then lead the Qi down the Conception Vessel into the Lower Dantian to root and stabilize the patient's energy.

TREATMENT MODIFICATIONS

- When treating patients with Qi and Blood stagnation, use the Extended Fan Palm hand method to emit Qi into the CV-12, CV-13, and St-21 points. Next, direct the Qi along the patient's Conception Vessel and Stomach Channels, leading the Toxic Qi down the

1. Left Testicle (Men), Left Ovary (Women) and Left Kidney
    a. Sit up, using your mind, heart and eye power to look inside and be aware of the perineum. Also become aware of your left nostril, left ear, left eye and left anus.
    b. Activate the Left Thrusting Channel by inhaling through the left nostril in short sips (about ten percent of lung capacity with each breath.)
    c. Then men slightly pull the left testicle and the left side of the anus up toward the left. Women slightly pull the left side of the anus up toward the left. Draw the pearl up with each sip of air. The left eye should internally look down, and then use the mind/eye power to look up as the pearl is drawn up. (The physical eyes do not actually look up.) Women direct the pearl to the left ovary and the left kidney; men direct the pearl to the left kidney.
    d. Exhale, relax the eye and the muscles, letting the pearl drop to the left side of the anus (and left testicle in men), and rest. Rest and feel the left side become lighter as the energy begins to flow up without effort. Practice nine times. Each time you rest use your mind to trace the Left Thrusting Channel.


Left Side of the Brain
Eye
Ear
Left Lung
Heart
First Pull Up in the Middle
Spleen
Adrenal Gland
And Pull Up to the Left Side
Left Kidney
Large Intestine
Prostate Gland
Left Testicle

Fig. 7.5 *Left Part in the Male*

patient's legs and out of the body via the St-36 points.

- When treating patients with a Deficient Cold syndrome of the Spleen and Stomach, use the Extended Fan Palm hand method to emit Qi into the patient's Mingmen and Lower Dantian areas.

PRESCRIPTIONS AND HOMEWORK

In treating patients with ulcers, have them practice the Old Man Searching for the Reflection of the Moon at the Bottom of the Tide Pool exercise (see Chapter 53).

PRESCRIPTION MODIFICATIONS

- For patients with Qi and Blood stagnation, have them perform the Spleen and Stomach Massage (see Chapter 39) while sounding "Hu." Next, have the patient dredge the Spleen and Stomach using the sound "Shu" to purge the Liver and regulate Liver Qi.
- For patients with a Deficient Cold syndrome of the Spleen and Stomach, have them practice the method of Taking in the Yellow Qi from the natural environment.

CHRONIC CONSTIPATION

Chronic constipation refers to the prolonged retention of feces in the intestinal tract and difficulty in discharging the fecal matter. This condition is not only painful to the patient, but also increases toxicity in the body. It is clinically characterized by decreased times of fecal discharge or small amounts of feces which are considered either too dry and hard, or too difficult to be discharged.

Generally, the transitional time for food to pass through the digestive tract for humans takes 24 to 40 hours. The postponement of defecation over two days is considered constipation, although some normal patients may have regular defecation every two to three days.

ETIOLOGY

The common causes of constipation are: Diet, Febrile Diseases, Emotional Stress, and A Sedentary Life-style.

1. Diet plays a major role in causing constipation. Constipation can result from the excessive consumption of hot, spicy, or greasy foods. This excess consumption of hot and greasy foods can dry up the fluids of the Stomach and intestines, thereby drying up the stool so that it cannot properly move through the intestinal walls.

   An excess consumption of Cold foods can block the Spleen's function of transporting and thus prevent the stool from moving downwards.

   Finally, a lack of fiber in the food, lack of sufficient fluid intake or excessive alcohol consumption can cause constipation.
2. Febrile diseases can be caused by External Wind Heat invasion, which if not rapidly expelled from the body, can turn into an Interior Heat condition. The Interior Heat usually attacks the Lungs, Stomach, and intestines causing the Body Fluids to dry up. A Deficiency of Body Fluids from the retention of Heat within the intestines (even after the febrile disease has passed) can cause dry stool and constipation.
3. Liver Qi stagnation (due to mental depression, anger, resentment, or frustration) can cause a Qi obstruction in the Lower Burners that affects bowel movements and leads to constipation, abdominal distention, and pain. Excessive studying, worrying, and thinking affects the Spleen, slowing down its transportation of food in the intestines, this in turn can lead to constipation.
4. A sedentary life-style, whether from choice or due to a weak constitution from a chronic or severe illness (or surgery), can cause constipation. Patients in convalescent homes often suffer from constipation due to a lack of exercise and poor diet, which can lead to Spleen Qi and Blood Deficiency. Lack of exercise weakens the Spleen Qi and can cause Liver Qi stagnation. When Spleen Qi becomes Deficient for long periods of time, the Spleen energy fails to provide the Qi to move the stool, resulting in constipation.

SYNDROMES

- Constipation due to an Excess condition is caused by decreased times of fecal discharge (once every three to seven days), and is usually accompanied with fever, thirst, poor appetite, and emotional anxiety.

- Constipation due to a Deficient condition is mostly seen in patients who have just recovered from an illness, or have just given birth and have become Deficient in Qi and Blood. It may also be observed in patients who suffer from a congenital insufficiency of Yang Qi in their Lower Burner and an accumulation of Yin Cold, which makes it difficult for the intestines to perform their normal transporting function. Patients with a Deficient condition may have bowel movements every three to seven days. The stool may be very dry, hard, and difficult to pass. This condition is clinically manifested by a pale and dull complexion, listlessness, and cold pain in the abdomen which is relieved by heat. The patient may also experience emotional fright due to a Kidney Qi Deficiency.

TREATMENT

1. Have the patient sit at the end of the treatment table, and begin to stimulate the patient's mid-back between the Bl-23 and Bl-25 points. Then stimulate the patient's lower lumbar and coccygeal areas, dredging and purging the Toxic Qi down the patient's thighs and the feet, while stimulating the Bl-31 through Bl-34 points.
2. The doctor will then have the patient lie supine and begin to stimulate the patient's Yellow Court and Lower Dantian areas, using the Vibrating Palm hand technique for 14 breaths.
3. Next, apply the Kneading Tiger Palm with the Vibrating and Quivering hand manipulations to emit Qi into the back of the patient's head at the Bl-10 points for 12 breaths, and then onto the patient's Lower Dantian for 14 breaths.
4. After energizing the patient's Lower Dantian, emit Qi, using the Extended Fan Palm technique, into the patient's middle epigastrium and navel area, as well as into the Lower Dantian. Finally, use the Spiraling and Quivering hand manipulation in a clockwise direction to gather the stagnant Qi and to lead it down the patient's Stomach Channels and out the legs.

TREATMENT MODIFICATIONS

- When treating patients with an Excess type of constipation, use the Extended Fan Hand Palm technique to emit Cold Qi into the patient's lower abdomen. Rotate the hand in a counterclockwise direction, while purging the Toxic Qi from the patient's body. Repeat for 14 breaths.
- When treating patients with a Deficient type of constipation, use the Vibrating Palm technique to emit Qi into the patient's Lower Dantian and Mingmen area for 8 to 16 breaths.

PRESCRIPTIONS AND HOMEWORK

To treat chronic constipation, have the patient practice the Daoist Five Yang Organ Regulating exercise (see Chapter 42) for 250 breaths twice a day.

PRESCRIPTION MODIFICATIONS

- For patients with an Excess type of constipation, place them in the Wuji posture with their hands resting on their lower abdomen. Begin with a clockwise rotation, imagining the Toxic Qi draining from the patient's Spleen and Stomach areas, down into their Stomach Channels and out their feet.
- For patients with a Deficient type of constipation, have them practice rubbing their Lower Dantian to strengthen the abdominal Qi, and have them practice the Gathering the Sun's Essence meditation (see Chapter 11).

CHAPTER 46

QI EMISSION THERAPY AND LUNG DISEASES

INTRODUCTION

The Lungs are solid organs that control the cycles of Qi circulation in the body, and are sometimes referred to as the White Emperor. They correspond to the element Metal. The Lungs house the Po (Corporeal Souls) and are in charge of respiration and regulating the metabolism of the Body's Fluids (Figure 46.1). The Lungs are also responsible for keeping Qi pure and extending it downward. The Lungs are energetically paired with the Large Intestine (a hollow organ).

The Lungs' upper external connection with the outside world is through the nose, hence any fragrance or odor inhaled through the nose affects the senses and evokes emotional responses from the Po.

In the fall months, the Lung Qi becomes more active in individuals that already possess strong Lung Qi, but becomes Deficient in those who already have weak Lung Qi. The excessive eating and drinking of pungent foods and the overexposure to dryness drains the Lungs.

LUNG COMPLICATIONS AND SYMPTOMS

This section focuses on specific Lung diseases and how to rectify them. The following discussion of treatment begins with an explanation of Lung syndromes and symptoms. Several Lung diseases have symptoms which are quite common to the organ's energetic dysfunction, such as headaches, cough, the common cold and influenza. A list of Lung syndromes and symptoms are described as follows.

1. Wind Cold invading the Lungs usually enters the patient through the pores of the skin and body hair (which are ruled by the Lungs). If the Lungs' energetic field is invaded by Wind Cold, it may cause the Lung Qi to become impure, ascend, and cause obstructions in the pores, resulting in a Wind Cold syndrome. This can cause the following symptoms: severe aversion to cold, headache, cough, the common cold or influenza, breathlessness, asthma, and allergic rhinitis.
2. Wind Heat Invading the Lungs usually enters the body by way of the mouth and nose; the nose being the orifice to the Lungs. If the Lungs' energetic field is invaded by Wind Heat, it may cause the Lung Qi to become impure, ascend, and impede the ability of the



Figure 46.1. The Lung (Lu) Channels

pores to expel pathogenic Evils, resulting in a Wind Heat syndrome. This can cause the following symptoms: slight aversion to cold, headache, cough, the common cold or influenza, asthma, allergic rhinitis and sinusitis.

3. Wind Dampness is a type of Wind Cold syndrome. It consists of both Wind and Dampness together, invading either the skin (causing itching and rashes) or the channels and joints (causing painful obstruction syndrome). If the Lungs' energetic field is invaded by Wind Dampness, it causes the following symptoms: skin rashes, swollen joints, body aches, headaches, the common cold and influenza.
4. Wind Dryness invading the Lungs causes the following symptoms: dry, itchy sore throat, dry lips, dry mouth, the common cold and influenza, cough and bleeding.
5. Lung Heat causes the following symptoms: restlessness and a feeling of heat, common cold and influenza, cough, sinusitis, breathlessness and atrophy syndrome as the body's functions begin to shut down.
6. Lung Phlegm Heat causes the following symptoms: common cold and influenza, cough with expectoration, breathlessness and a sensation of oppression in the chest.
7. Cold-Damp Phlegm invading the Lungs causes the following symptoms: a feeling of heaviness, cough with profuse expectoration, wheezing, nausea, poor appetite and breathlessness.
8. Lung Qi Deficiency causes the following symptoms: breathlessness, wheezing, slight cough with no phlegm, asthma, allergic rhinitis, tiredness, spontaneous sweating, and enuresis or incontinence.
9. Lung Yin Deficiency causes the following symptoms: night sweating, extreme tiredness, breathlessness, asthma, dry cough in short bursts, and Five Palms Hot (a condition also known as "Five Center Heat," in which the patient feels a hot sensation in the palms and soles of the feet, accompanied by heat and agitation of the chest and/or head area).


Access Lu-1 and 2, to purge the Lungs.
Access GV-14, Bl-12 and 13, to purge the Lungs.

Figure 46.2. Treating Lung Diseases


Purge the Lungs through the Lung and Large Intestine Channels.

Figure 46.3. Drain the Turbid Qi out of the Lungs, down the Lung Channels and out of the hands.



Figure 46.4. Replenish the mother (Spleen) to nourish the child (Lungs).

GENERAL TREATMENT FOR LUNG DISEASES

The following is a description of a general protocol used for treating a patient's Lungs. The goal is to introduce the Qigong doctor to the basic hand positions and areas of the patient's body towards which Qi is emitted (or Turbid Qi removed). Once the Qigong doctor becomes proficient at locating these specific points, the treatment will flow more smoothly.

After comparing the various Lung therapies, the reader will notice that certain patterns repeat themselves.

1. Generally, the Qigong doctor accesses the patient's Lungs through either direct energized insertion into the Lungs' anatomical location, or through the patient's channels and external energetic fields (Figure 46.2).
2. After treating the patient (purging, tonifying, and regulating), the Qigong doctor stimulates the patient's Lungs and Upper Burner areas and roots the patient's Qi into the Lower Dantian.
3. Next, the Qigong doctor leads any remaining Turbid Qi down the Lung Channels and out the patient's hands (Figure 46.3).

Keep in mind that these areas are general and that specific treatment patterns must change as they apply to the patient's exact condition (Excess, Deficient, etc.).

MEDICAL QIGONG THERAPY FOR LUNG QI DYSFUNCTION

Patients with Lung disease may have a pale complexion, dry hair, dyspnea (difficult breathing), hyposmia (a deficient sense of smell), stuffy nose, dryness and itching of the skin, or discomfort and pain in the chest and back. Patients may dream of the sun, moon, clouds, or of having sex. The primary therapies used to treat Lung diseases include the Breath regulation and Qi reinforcing meditations (see Chapter 16).

- Patients with an Excess Heat syndrome of the Lungs may have a flushed right cheek. To treat this type of syndrome, have the patient utter the sounds "Si" (Sss) for the Lungs and "Chui" (Chree) for the Kidneys. Guide the Evil Qi out of the patient's body along the Lung and Large Intestine Channels using the Pushing, Pulling and Guiding Qi manipulations.
- Patients with a Deficient syndrome of the Lungs may have shortness of breath and be unable to regulate their breathing. To treat this type of syndrome, have the patients inhale the sound "Hu," as they visualize absorbing the color yellow to replenish the Spleen (the mother); this will nourish the Lungs (the child). Next, the patient guides the Qi back to the Lungs (Figure 46.4).

LUNG QIGONG PRESCRIPTIONS

These exercises regulate the Qi in the Lung Channels, tonify the Lungs, replenish Qi, ventilate the Lungs, and relieve asthma, coughing, and sputum. These exercises can be used to prevent and treat the following diseases and syndromes: bronchitis, pulmonary emphysema, and bronchial asthma, as well as dyspnea and abundant expectoration.

PRESCRIPTIONS FOR TONIFYING THE LUNGS

The Taking in the White Qi meditation can be used to tonify the Lungs. The properties inherent within the color white have a persistent vibratory rate used for tonifying the Lungs and Large Intestine.

1. Assume a standing, sitting, or lying posture.



Figure 46.5. Inhale



Figure 46.6. Exhale



Figure 46.7. Inhale



Figure 46.8. Exhale

Relax the whole body, breathe naturally, and get rid of any stray thoughts.

2. When inhaling, imagine a white energy in front of you. Inhale the white light energy in through the nose and down into the Lungs. As you exhale through the mouth, the dark, pathogenic Qi leaves the Lungs; however, the bright clean color remains in the Lungs, stimulating and vitalizing them. With each breath the Lungs retain more clean energy and begin to glow. Repeat for five breaths.
3. Next breathe the color white in through the nose, filling the entire mouth. When exhaling through the nose, send the Qi slowly into the Lungs, then down to the Lower Dantian, and then further out into the skin and hair of the whole body. Repeat nine to eighteen times. Return to the beginning posture and close.

PRESCRIPTIONS FOR PURGING THE LUNGS

Purge the Lungs by having the patient rub his or her chest while sounding "Sss."

The patient should assume a sitting or standing posture. Both palms are placed flat on the sides of the chest as the patient inhales slowly. When exhaling, the patient sounds the word "Sss" while rubbing the chest with both palms (circling up and down, from the center outward). This exercise is performed for six to twelve breaths.

PRESCRIPTIONS FOR REGULATING THE LUNGS AND CONDUCTING QI

The following exercise is used to regulate the Lungs after purging or tonifying.

1. Sit with the legs crossed, breathe in with the spine arched backwards and the hands by the sides pressing against the ground; extend the chest, and inhale until the chest is full (Figure 46.5).

   Pause, then push the upper back in a posterior direction and draw in the chest while exhaling through the nose (Figure 46.6). Repeat four to nine times.
2. Next, still sitting with the legs crossed, place the palms on the knees. Inhale with the spine erect and turn the head allowing the torso to turn slightly to the left (Figure 46.7). Then bend forward and exhale while facing the center (Figure 46.8). Next, inhale and turn to the right, then again bend forward and exhale while facing the center. Always inhale when turning to the sides, and exhale while facing the center.

SPECIFIC MEDICAL QIGONG THERAPY FOR LUNG DISEASES

The following are several Medical Qigong treatments used in China to treat specific Lung diseases.

TREATING THE COMMON COLD AND INFLUENZA

Upper respiratory tract infections belong to the category of common colds, while influenza belongs to the category of seasonal epidemic colds. Both conditions may be treated by referring to the prescriptions described within this section.

ETIOLOGY

The common cold is a generic term used to describe an Exterior condition caused from the invasion of pathogenic Wind (Wind Cold, Wind Heat, Wind Damp Heat or Wind Dry Heat). It is generally associated with coryza or inflammation of the respiratory mucous membranes.

Upper respiratory tract infection is caused by viruses or bacteria. Influenza is known as an acute, contagious respiratory infection, characterized by sudden onset. The chief clinical manifestations are stuffy nose, nasal discharge, coughing, sneezing, sore throat, fever, headache, chills, and an aversion to wind.

If the pathogenic Qi is on the Exterior level of the body, the internal organs are not affected, and only the patient's Wei Qi is involved. If the pathogenic factor becomes Interior, the patient's internal organs are affected, especially the Lungs and Spleen. If the pathogen is not cleared and purged from the patient's body, it may either penetrate more deeply into the patient's body and cause serious problems, or give rise to residual Heat which causes chronic post-viral fatigue syndromes.

SYNDROMES

- A Wind Cold syndrome has the following symptoms: chills, headache, aches and painful joints, coughs and sore itchy throat, stuffy nose, low fever, and no sweating with profuse, watery nasal discharge.
- A Wind Heat syndrome has the following symptoms: fever, cough, headache, slight aversion to cold, swollen and sore throat, thick yellow sputum, slight thirst, and perspiration. Once the pathogenic factor penetrates into the patient's interior, the body's Qi begins to fight against it, causing a fever and feeling of heat inside the body, with an aversion to cold, and shivering.

TREATMENT

1. Have the patient sit at the end of the treatment table.
2. Begin by stimulating the energy within the patient's head, purging and leading the Toxic Qi down the patient's arm and out the LI-11 and LI-4 points.
3. Then stimulate the patient's Yintang (Third Eye) and Taiyang (temple) points. Using Pulling and Leading Qi manipulation techniques, purge and guide any remaining Toxic Qi downward, along the Conception Vessel and the Stomach Channels, out the patient's feet, three to seven times.
4. Next, to balance the functional activities of the body's Qi, stimulate the tissue area on the patient's upper back and head (GV-14 and GV-16, Bl-12 and Bl-13) using the Extended Fan Palm technique, and guide the Qi downward along the Bladder Channels to the patient's feet.
5. Finally, softly grasp the patient's LI-4 and LI-11 points and gently shake the arm, stimulating the patient's Lung Qi. This technique is performed on each of the patient's arms.

TREATMENT MODIFICATIONS

1. When treating patients with Wind Cold syndrome, extend Hot Qi into the GV-14 and Bl-12 points, using the Extended Fan Palm technique, and guide the Qi downward along the Bladder Channels to the patient's feet and out the body.
2. When treating patients with Wind Heat syndrome, extend Cold Qi into the GV-14, Bl-13, and GB-20 points, using the Extended Fan Palm technique, and guide the Qi downward along the Stomach Channels to the patients' feet and out the body.
3. When treating patients with nasal obstruction, extend Vibrating Qi, using the Sword Fingers technique, into the Ll-20 points for 9 breaths.
4. When treating patients with cough, chest stuffiness, and Phlegm, extend Vibrating Qi, using the Sword Fingers technique, into the CV-17, Lu-1, and Lu-2 points for 8 breaths.

PRESCRIPTIONS AND HOMEWORK

The patients should be given the Ten Dragons Run Through the Forest exercise (see Chapter 41) to sweep and purge the Gall bBladder

Channels. Most of the attention should be placed on feeling the Qi beneath the hands, with emphasis placed on exhalation to expel the pathogenic Wind from the body. Perform this prescription for 24 to 50 times.

CHRONIC BRONCHITIS

Chronic bronchitis is a condition caused by the chronic inflammation of the mucous membranes of the bronchial tubes.

ETIOLOGY

Chronic inflammation of the bronchial mucosa and peribronchial tissues is mostly due to lingering and recurrent acute bronchitis, or may occur after an infection from other diseases. The chief clinical manifestations are chronic recurring cough, expectoration and dyspnea. Bronchitis can be divided into acute and chronic conditions.

1. Acute bronchitis corresponds to the Qi level of infection within the four level identification patterns. It is the easiest to treat, and normally manifests with Hot Phlegm symptoms.
2. Chronic bronchitis takes a little longer to heal and the doctor should focus treatment on attending to the root and manifestation of the disease simultaneously (purging Phlegm and dispersing the Heat or Cold).

SYNDROMES

- For Phlegm Dampness attacking the Lungs, the main symptoms are abdominal distention, cough with copious white sputum, stuffiness in the chest and loss of appetite.
- For Lung and Spleen Deficiency, the main symptoms are cough with sputum, shortness of breath, spontaneous sweating, loss of appetite and loose stool.

TREATMENT

1. Have the patient sit at the edge of the table. Begin to purge the patient's Lungs, dredging the Toxic Qi down the Lung Channels and out of the hands.
2. Use the Vibrating Palm technique to stimulate the patient's Middle Dantian, Lu-1, -2, Bl-13, GV-16, and St-40 points. Use 8 to 12 breaths for each point.

TREATMENT MODIFICATIONS

- For Phlegm Dampness attacking the Lungs, use the Extended Fan Palm technique to emit Qi into the patient's Lungs; purge the Spleen and Stomach Channels, leading the Toxic Qi down the channels and out of the St-40 and Sp-6 points on each leg.
- For Spleen and Lung Deficiency, emit Qi using the Vibrating Palm technique into the patient's Bl-20, Bl-23, Bl-13 and CV-12 points for 6 to 12 breaths.

PRESCRIPTIONS AND HOMEWORK

Have the patient practice the Lung exercise from Daoist Five Yin Organ Tonification and Regulation exercises (see Chapter 42) to strengthen and balance the Lungs.

PRESCRIPTION MODIFICATIONS

- For patients suffering from Phlegm Dampness attacking the Lungs, have the patient perform the Sun and Moon Rotating technique (see Chapter 41), sounding "Sss" to regulate the Lungs and the sound "Hu" to regulate the Spleen.
- For patients suffering from Lung and Spleen Deficiency, have them perform the Taking in the White Qi to tonify the Lungs, and the Taking in the Yellow Qi to tonify the Spleen.

ASTHMA

Asthma is a chronic disorder of the respiration organs characterized by difficulty in breathing, wheezing, and tightness in the chest. Bronchial asthma, chronic bronchitis and pulmonary emphysema are all included in the category of this disease.

ETIOLOGY

Asthma is an Excess condition which is caused mainly by a retention of Wind, Cold, Heat or Damp Phlegm in the Lungs. When a patient is affected by invasion of pathogenic Dampness, disorders in Qi mobility develop. Phlegm mixes with Qi and obstructs the air passages, causing dyspnea (shortness of breath) and wheezing.

Asthma may also result from an obstruction of the Lungs due to Phlegm retention caused by a failure of the Spleen to transport, or from a Deficient condition of the Kidneys. The diagnosis of this disease can be divided into two types of asthma: early onset asthma and late onset asthma.

1. Early onset asthma (also called extrinsic or atopic asthma), usually starts during childhood and is divided into non-allergenic and allergenic asthma. Allergic asthma is associated with eczema and it tends to be difficult to treat because it stems from a congenital Lung and Kidney Qi Deficiency and is often hereditary. Early onset asthma can be affected by diet (e.g., lactose intolerance), emotional problems, fatigue, chronic illness and invasion by external pathogenic factors. It is related to an allergic hypersensitivity of the immune system.
2. Late onset asthma (also called intrinsic asthma) normally starts later in life and is due to bronchial hyperreactivity. In late onset asthma there is no hereditary basis. It is generally characterized by a Lung, Spleen, or Kidney Deficiency and a retention of Phlegm. In some cases, asthma can be caused by Liver Qi stagnation or Liver Fire obstructing the descending action of Lung Qi. Late onset asthma can be affected by overwork, excessive sexual activity, emotional stress and the excess consumption of sour, greasy or cold foods.

SYNDROMES

1. For Wind Cold asthma due to External Evils, the main symptoms are dyspnea, coughing, abundant, thin expectoration and clear Phlegm accompanied with external Wind Cold syndrome.
2. For asthma due to the accumulation of Phlegm Dampness in the Lungs, the main symptoms are dyspnea, cough, abundant, thin and sticky expectoration, stuffiness in the chest and in the epigastric region.
3. For asthma due to Deficient Lung and Spleen Qi, the main symptoms include dyspnea, spontaneous perspiration, aversion to Wind, an expectoration of clear, thin Phlegm, weak voice, loss of appetite and general lassitude.
4. For asthma due to Deficient Lung and Kidney Yin, the main symptoms are dyspnea, dry throat and mouth, dry cough, inconsistent fever, night sweating, and with some patients there may be hemoptysis (the expectoration of Blood).

TREATMENT

The therapeutic effect of Medical Qigong is better for patients who have had this disease for a short time period. In chronic asthma, improvement usually takes more time.

1. Begin by stimulating the patient's CV-22, CV-17 and CV-4 points along with the Bl-13 points.
2. Using the Vibrating Palm technique and emit Qi with the left palm into the patient's lower neck and upper back area, while simultaneously extending energy into the patient's Lower Dantian with the right hand for 14 to 28 breaths.
3. Purge the Toxic Qi from the patient's CV-22 and Bl-13 areas, then lead and guide the patient's Lung Qi down the Governing Vessel and Bladder Channels into the Mingmen GV-4 and Bl-23 points. Repeat for 3 to 7 respirations.
4. Using the Sword Fingers hand posture, vibrate energy into the patient's CV-22, -17, Lu-1 and Lu-2 points. Then guide the patient's Qi to flow downward from the chest to the Lower Dantian along the Stomach Channels and Conception Vessel to stabilize the patient's Qi.

TREATMENT MODIFICATIONS

1. To treat a case of Wind Cold syndrome due to exogenous Evils, purge and sweep the patient's Gall Bladder Channels, concentrating on the head area. Then extend Qi into the patient's Lu-1 and Lu-2 points. Use Pulling and Leading manipulations to draw the Toxic Qi along the patient's Lung Channels, expelling the pathogenic Qi out of the fingertips on both hands.
2. In treating cases of Deficient Lung and Spleen Qi, use the Extended Fan Palm hand posture and Vibrating Palm technique to emit Qi towards the patient's CV-12, CV-6, Bl-20 and Bl-13 points for 9 to 18 breaths.



Fig. 7.6 *Left Part in the Female*

2. Spleen

Close the right nostril, inhale, and pull up. As you sip in the air, use the mind power and the left eye, ear and nostril to draw the energy up from the left testicle (men), through the left ovary (women), the left kidney, and up to the spleen. Exhale; release the energy down. Practice nine times. Rest, and feel the energy flow up the Left Thrusting Channel to the spleen under the diaphragm.

B. Middle Thrusting Channel to the Diaphragm

1. Prostate (Men) or Cervix (Women)

Men concentrate on the middle of the scrotum, perineum, and anus. Women concentrate on the middle of the perineum and anus. Inhale, and pull up the middle of the scrotum (men), perineum and anus. Use all the senses to draw the energy up to the prostate (men) or cervix (women). Look up with both eyes as you do so. Relax the eyes and anus muscle, and let the pearl drop back down to the perineum and scrotum (men). Feel the energy begin to flow up as you rest. Do this nine times.

2. Small/Large Intestine, Aorta and Vena Cava

Inhale and pull up the scrotum (men only) and anus. Use the eyes, ears, and nose to draw the energy to the prostate/cervix, small intestine, large intestine, aorta and vena cava. Do not thrust beyond the diaphragm. Practice nine times. Rest, and feel the energy flow up through the Middle Thrusting Channel to the vena cava.

3. In treating cases of Deficient Lung and Kidney Yin, use Extended Fan Palm hand posture and Vibrating Palm hand technique to emit Qi towards the patient's Lower Dantian, Mingmen, and Bl-13 points for 6 to 12 breaths.

PRESCRIPTIONS AND HOMEWORK

Patients are encouraged to practice physical exercises to strengthen the body and enhance their resistance to pathogenic invasion. These exercise prescriptions however, must not be too strenuous. Two prescriptions used for relieving asthma and respiratory pain are described as follows.

Exercise to Relieve Asthmatic Pain. For chronic conditions of asthma, patients are given the following prescription:

1. From a sitting or standing posture, slightly close the eyes and relax. Stimulate the energy of the chest by kneading the sternum from the sternal notch to the xiphoid process 36 times.
2. Inhale and place the right palm on the left side of the chest. Exhale, and begin dredging the left Lung Channel using a sweeping motion to purge the Toxic Qi down the arm and out through the hand. Perform this Purging exercise 10 times, then repeat 10 times on the opposite side.
3. Finally, perform the Kidney Rub exercise (see Chapter 39) for 18 breaths.

Exercise to Relieve Asthma Attacks

For acute asthmatic attacks, patients are given the following prescription.

From a sitting or standing posture, slightly close the eyes and relax the muscles of the chest and back. Take a deep breath and say "relax" silently, while simultaneously imagining the Lungs relaxing and descending the body's Qi down to the toes along both lateral sides of the body. As the Qi descends from the Lungs, imagine this energy flowing like water, down your body into the Earth. Repeat this procedure until the asthma attack has receded.

PRESCRIPTION MODIFICATIONS

- Patients with Deficient Lung Qi should practice the previous exercises in combination with Taking in the White Qi.
- Patients with a domination of pathogenic factors should practice the previous exercises in combination with rubbing their chest and uttering the sound "Sss."

BRONCHIECTASIS

Bronchiectasis is the chronic dilation of the bronchi, with a secondary infection that usually involves the lower portion of the Lungs. Dilation may involve an isolated segment or can spread throughout the entire bronchi.

ETIOLOGY

This disease is characterized by hypertrophy of the mucus-secreting glands in the bronchial tree. The dilation and deformation of the bronchi are caused by the damage of the vessel walls due to chronic inflammation of the bronchi and the peribronchial Lung tissue. In advanced cases the bronchi themselves can become inflamed with infection. The clinical manifestation is a chronic cough with an excessive expectoration of sputum. If followed by infection, there may be night sweating, fever and lassitude.

SYNDROMES

1. Liver Fire attacking the Lungs can manifest with pain and distention in the chest and hypochrondium, flushed face, cough, expectoration of yellow, thick sputum and repeated hemoptysis (Blood discharging from the larynx, trachea, bronchi, or Lungs).
2. Dry Heat scorching the Lungs manifests as a dry throat and dry cough with little sputum, which is bright red and bloody.
3. Qi and Yin Deficiency manifests through shortness of breath, lassitude, emaciation, repeated hemoptysis, cough with little sputum, erratic fever and flushed face (especially around the cheeks).

TREATMENT

1. Have the patient sit at the edge of the table, and begin to stimulate the upper chest at the Lu-1 and Lu-2 points and the upper back around the patient's Bl-13 points.
2. Using the Extended Fan Palm hand technique, emit Qi into the patient's Middle Dantian directing the energy to flow into the Lu-1 and Bl-13 points for 6 to 12 breaths.

3. Using the Leading and Guiding hand techniques, purge and dredge the Toxic Qi out the Lung Channels (i.e., down the arms and out of the hands).

TREATMENT MODIFICATIONS

1. When treating patients with Liver Fire attacking the Lungs, include the Vibrating Palm technique, and emit Qi into the patient's Bl-13 and Bl-18 points for 12 breaths. Then purge the Liver Channels down the torso and out of the legs.
2. When treating patients with Dry Heat scorching the Lungs, apply the Vibrating Palm technique to emit Qi into the patient's Bl-23 and Bl-13 points for 24 breaths.
3. When treating patients with Qi and Yin Deficiency, apply the Vibrating Palm technique to emit Qi into the Bl-13, Bl-20, and Bl-23 points for 12 breaths.

PRESCRIPTIONS AND HOMEWORK

It is advisable for patients to practice regulating Lung exercises with Natural Breathing to strengthen the Lungs.

PRESCRIPTION MODIFICATIONS

1. For Liver Fire attacking the Lungs, have the patient perform the Sun and Moon Rotating technique (see Chapter 41), while sounding the word "Sss" for 36 breaths, to purge the Lungs in addition to performing the Lung tonification and regulation exercises (see Chapter 42). Next, have the patient rub the hypochrondrium area and sound the word "Shu" for 36 breaths.
2. For Dry Heat scorching the Lungs, (from a Wuji posture) have the patient bring both hands up to the sternum and begin kneading the sternum down to the xiphoid process 36 times. Next, the patient places both palms on the chest with the fingers touching the sternum to allow the Qi to flow into the Lungs for 10 breaths. Finally, the patient rubs the hypochrondrium and purges the Toxic Qi from the body while exhaling and rubbing the sides of the chest, starting at the armpits, to direct the Qi to flow downward into the Lower Dantian.
3. For Qi and Yin Deficiency, it is advisable for the patient to practice Lung tonifying exercises and the Gathering the Moon Cream exercises (see Chapter 11), as well as the methods of Taking in the White Qi.

SINUSITIS

Sinusitis is described as the inflammation of the sinuses. Infections stemming from the common cold or influenza frequently cause secondary infections in the sinuses, these infections tend to become chronic. The body's frontal and maxillary sinuses are very prone to infection and inflammation.

ETIOLOGY

An invasion of pathogenic Wind Cold into the Lungs through the nose (the orifice of the Lungs) can bring about the accumulation of Heat and cause an obstruction of the Lungs' Qi. This condition further impairs the Lungs' dispersing and descending function, giving rise to sinusitis.

The excessive consumption of greasy, hot foods leads to a buildup of Phlegm and Heat toxins within the body and may predispose the patient to sinusitis. Greasy, hot foods may also lead to the formation of Damp Heat within the Stomach and Spleen, which can be transported upwards into the sinuses by way of the Stomach Channels.

Excess conditions, such as Wind Heat, Lung Heat, Stomach and Spleen Damp Heat, and Liver and Gall Bladder Fire, should all be purged from the patient's body, whereas chronic conditions caused by Spleen Deficiency should be tonified.

SYNDROMES

Sinusitis is characterized by consistent yellowish and foul smelling nasal discharge accompanied by cough, impairment of smell, and dull pain in the upper part of the cranium. The headache caused from sinusitis is located on the face and corresponds with either the frontal ethmoidal or the maxillary sinuses.

TREATMENT

1. Begin by stimulating the patient's frontal sinuses, focusing specific attention on the LI-20, GB-20, and Yintang points.

2. Then emit Qi into both of the patient's hands and wrist areas, focusing specific attention on the LI-4 and Lu-7 points.
3. Next, using either the Sword Fingers or Extended Fan Palm hand posture, emit Qi into the patient's LI-20 points. Begin using the Pushing, Pulling, and Leading manipulations to guide the patient's Toxic Qi down the Stomach Channels, purging it out through the St-36 point on each leg.

PRESCRIPTIONS AND HOMEWORK

The following prescription is used for relieving sinusitis.

The patient, from a seated posture, rubs his or her palms until the dorsal sides of each thumb are very hot. Then the patient places the thumbs on the sides of the nose and begins to gently rub up and down for 10 breaths. This exercise is called Bathing the Nose.

Next, the patient places the tips of the middle fingers on each side of the nose (LI-20), and begins kneading these points. This is followed by using circular rotations from the cheeks to the nose five times during inhalation, and then from the nose to the cheeks five times during exhalation. This part of the exercise is called Kneading the Apex of the Nose. This exercise is performed for 10 breaths.

CHAPTER 47
QI EMISSION THERAPY FOR KIDNEY DISEASES

INTRODUCTION

The Kidneys are solid (Zhong) organs that store the body's Jing. They correspond to the element Water and are sometimes referred to as the Black Emperor. The Kidneys house the Zhi, which is the will power, and they are in charge of life and reproduction. The Kidneys are also responsible for bone, brain and Marrow formation. They govern the Mingmen Fire and are the root of the Yin and Yang energies within all the organs (Figure 47.1). The Kidneys are energetically paired with the Bladder (a hollow organ).

The Kidneys are responsible for inhalation. Upon inhalation the Kidneys grasp the Lungs' Qi and hold it. This "holding" action secures the body's ability to maintain deep, slow inhalation. Therefore, when the Kidneys become weak (due to shock, trauma or disease), one of the clinical manifestations of Deficient Kidneys includes dyspnea (shortness of breath and gasping for air).

The Mingmen, or Gate of Life, is the root of the Yuan Qi, the residence of Water and Fire energy. The Yin Qi of the Five Yin Organs cannot be nourished without it, and the Yang Qi of these organs cannot be lifted without it. Kidney Qi flows to the brain. The ears (Yang orifice), anus and urethra (two Yin orifices) are the orifices of the Kidneys.

The Kidneys' upper external connection with the outside world is through the ears, hence any sound or tone resonation affects the core essence of the individual's spiritual and emotional will power.

In the winter months the Kidneys become more active in individuals who already possess strong Kidney Qi, but becomes Deficient in those with weak Kidney Qi. The excessive eating and drinking of salty foods and overexposure to cold depletes the Kidneys.

Kidney Yin energy flows to the Liver, Heart, and Lungs. It is responsible for the body's Jing



Figure 47.1. The Kidney (Kd) Channels

and produces the birth, growth, maturation, and reproduction cycle. Kidney Yang energy flows to the Spleen, Liver, Heart, and Lungs. It supports the Yang of all the body's organs via the Mingmen (Figure 47.2).

KIDNEY COMPLICATIONS AND SYMPTOMS

This section focuses on specific Kidney diseases and how to rectify them. The following discussion of treatment principles begins with an explanation of Kidney syndromes and symptoms. Several Kidney diseases have symptoms which are common to the organ's energetic dysfunction, such as mental and emotional problems, lower back pain, tiredness, and breathlessness. A list of Kidney syndromes and their symptoms are described as follows.

1. A Kidney Yang Deficiency syndrome manifests through such symptoms as headaches, breathlessness, wheezing, asthma, tiredness, mental and emotional problems, lower back pain, diarrhea, constipation, painful urination, enuresis, edema, menorrhagia and premenstrual tension.
2. A Kidney Yin Deficiency syndrome manifests through such symptoms as tiredness, chest tightness, asthma, breathlessness, mental and emotional problems, constipation, enuresis, lower back pain, bleeding, Parkinson's disease, menorrhagia and premenstrual tension.
3. A Kidney Jing Deficiency syndrome manifests through such symptoms as tinnitus, dizziness, and mental and emotional problems.

GENERAL TREATMENT FOR KIDNEY DISEASES

The following is a description of a general protocol used for treating a patient's Kidneys. The goal is to introduce the Qigong doctor to the basic hand positions and areas of the patient's body through which Qi is emitted (or Turbid Qi removed). Once the Qigong doctor becomes proficient at locating these specific points, the treatment will flow more smoothly.



Figure 47.2. Kidney Yin flows from the Kidneys to the Liver, then to the Heart and Lungs. Kidney Yang flows from the Kidneys to the Spleen, Liver, Heart and the Lungs.

After comparing the various Kidney therapies, the reader will notice that certain patterns repeat themselves.

1. Generally, the Qigong doctor accesses the patient's Kidneys through either direct energetic insertion into the Kidneys' anatomical location on the back, through the naval and Mingmen access gates, or through the patient's channels and external energetic fields (Figure 47.3).
2. After treating the patient (purging, tonifying, and regulating), the Qigong doctor will stimulate the patient's Kidneys, Mingmen, and Lower Burner areas, and roots the patient's Qi into the Lower Dantian.
3. Next, the Qigong doctor stimulates the patient's Kidneys and Lower Dantian through the Taiji Pole and Bubbling Spring (Kd-1) points, regulating the body's Yin and Yang Qi via the Microcosmic Orbit (Fire Cycle).

Keep in mind that these areas are general and that specific treatment patterns must change as they apply to the patient's exact condition (Excess, Deficient, etc.).


Energize the Kidneys through the patient's Taiji Pole.
Energize the Kidneys through the Mingmen (GV-4) point.
Energize the Kidneys through the Shenque (CV-8) point at the navel.
Regulate the Kidneys through the Sanyinjiao (Sp-6) points.
Energize the Kidneys through the Yongquan (Kd-1) points.

Figure 47.3. Treating Kidney Diseases

MEDICAL QIGONG THERAPY FOR KIDNEY QI DYSFUNCTION

Some symptoms of Kidney disease can manifest as dark circles under the eyes, decaying teeth, distended abdomen, dyspnea, and perspiration. The primary therapy used to treat Kidney diseases include: the Windy Breathing method to strengthen the Kidneys, Toe-Raised Walking, and Kidney massage (see Chapter 15).

1. An Excess Heat syndrome of the Kidneys should be treated by purging through uttering the "Chui" (Chree) sound, and reinforcing its effectiveness by focusing intent on the exhalation (Figure 47.4). This gradually relieves sluggishness and stagnation of the Kidney's Qi.
2. A Kidney Deficiency syndrome manifests mid-lower back pain at the waist level, and should be treated by Taking in the Blue Qi (see Chapter 4) into the Kidneys, Mingmen, and Lower Dantian.
3. A Deficiency of Mingmen Fire should be treated by emitting Qi into the patient's Lower Dantian and Mingmen area with the Pushing technique along with clockwise Qi rotation. This manipulation invigorates the Kidneys' Qi and replenishes the Fire of the Mingmen.


Heart
Spleen
Lungs
Kidneys
Liver
Chree

Figure 47.4. The Kidney sound is "Chui" (Chree).

KIDNEY QIGONG PRESCRIPTIONS

These exercises promote the flow of Qi and Blood of the Kidney Channels, nourish the Kidneys, strengthen Yang, and increase the Yuan Qi. These exercises can also be used to prevent and treat the following diseases and syndromes: nephritis, psychoneurosis, lumbago, rachialgia (spinal inflammation), tinnitus, deafness, frequent micturition and aversion to cold due to having a Cold condition.

PRESCRIPTIONS FOR TONIFYING THE KIDNEYS

The Taking in the Blue Qi can be used to tonify the Kidneys. The properties inherent within the color blue have a persistent vibratory rate used for tonifying the Kidneys and Bladder.

1. Assume a standing, sitting, or lying posture. Relax the whole body, place the tongue against the hard palate behind the teeth, and get rid of any stray thoughts.
2. When inhaling, visualize blue energy in front of you. Inhale the blue light energy in through the nose and down into the Kidney organs. As you exhale through the mouth, the dark, pathogenic Qi leaves the Kidneys; however, the bright clean color remains in the organ, stimulating and vitalizing it. With each breath the organ retains more clean energy and begins to glow. Repeat for five breaths.
3. Next breathe the blue color in through the nose, filling the entire mouth. When exhaling through the nose, send the blue Qi slowly down to the Kidneys, then into the Lower Dantian. Perform six to twelve times. Return to the beginning posture and close.

PRESCRIPTIONS FOR REGULATING THE KIDNEYS

Remove stagnation from the Kidneys by having the patient rub the abdomen while sounding "Chree."

Assume a sitting or standing posture. Place both palms flatly on the lower abdomen (left hand on the outside for men, opposite for women), inhale slowly, and exhale the sound "Chree" while rubbing the lower abdomen clockwise, gently with the palms. Perform ten to twenty breaths.



Figure 47.5. Rotate the waist in a clockwise and counterclockwise direction.

PRESCRIPTIONS FOR STRENGTHENING THE KIDNEYS AND CONDUCTING QI

The following exercise is used to tonify the Kidneys.

1. Assume a standing posture. Clench both hands into fists, and place them against the soft tissue on both sides of the Mingmen. Rotate the waist, turning towards the left in a clockwise direction for six rotations. After the six rotations pause in the center, then rotate in the opposite direction for six times (Figure 47.5).
2. Assume a standing or sitting posture. Rub the sides of the Mingmen with both hands, up and down thirty-six times, focusing the mind on the lumbar region (Figure 47.6).
3. Tuck the sacrum under (to stimulate the renal capsule), placing both palms on the groin, under the junction of the pubic bone (left hand on the outside for men, right for women).

Support and gently pull up the area around the perineum with both hands eighty-one times (Figure 47.7). Switch hands and repeat. Note: The Kidneys are injured by irregular



Figure 47.6. Rub the Kidney and Mingmen area.



Figure 47.7. Support the groin and perineal area.

sleep patterns, fear, excessive caffeine, sex, drugs, alcohol, and smoking. Excess saltiness and Cold (climate and food) have a draining effect on the Kidneys.

SPECIFIC MEDICAL QIGONG THERAPY FOR KIDNEY DISEASES

The following are several Medical Qigong treatments used in China to treat specific Kidney diseases.

TINNITUS AND DEAFNESS

Tinnitus is a condition of a high-pitch or rushing-wind sound within one or both ears. The sound may be a consistent pitch or vary in intensity and modulation.

ETIOLOGY

Although the ears are the opening of the Kidneys, there are other influences which must be addressed when dealing with tinnitus. Tinnitus is most commonly caused by stagnation of the Triple Burner and Gall Bladder Channels. These channel stagnations are due to three adverse conditions: the rising of Liver Wind Fire which may be induced by violent rage, the obstruction of the orifices in the head due to External Wind invasion, or by failure of the Kidney Jing to reach the ears due to a Kidney Deficiency.

This disease can be divided into Full and Empty Types of tinnitus:

1. The Full Type of tinnitus is caused by the flaring up of pathogenic Wind, Yang, Fire, Phlegm, or Phlegm Fire. It is most noted in the Excess rising of Liver and Gall Bladder Fire, or Phlegm Fire flaring upwards. This type of tinnitus is experienced as a sudden onset with a loud sound and is aggravated by cupping one's hands over one's ears.
2. The Empty Type of tinnitus is caused by a Deficiency of Kidney Qi, Kidney Jing, Lung Qi, or Heart Blood that is unable to extend to the ears. It is most noted in Kidney Jing Defi-

ciency, Deficient Upper Burner Qi and Heart Blood Deficiency. This type of tinnitus manifests clinically through a gradual onset with a low sound and is improved by cupping one's hands over one's ears.

SYMPTOMS

1. The Excess Type of tinnitus manifests as a sudden deafness or distending pain in the ears accompanied with a loud-pitched ringing noise. The adverse rising of Liver Wind Fire or Gall Bladder Wind Fire causes vexation and irritability, and often manifests as a flushed face and dry mouth.

   The Excess condition caused by an invasion of External Wind also includes symptoms such as chills, fever, and headache.
2. The Deficient Type of tinnitus can either occur constantly or intermittently, and may be aggravated by overstraining and relieved by hand pressure. This condition is often accompanied by dizziness, soreness of the waist, seminal emission, or leukorrhea.

TREATMENT

1. Begin by stimulating the patient's TB-3, TB-17, SI-19, and LI-4 points on both sides of the body.
2. Emit Qi towards the patient's Lower Dantian, using the right Sword Finger hand posture and left Extended Fan Palm hand posture.
3. Next, extend energy into the patient's affected ear and focus the Qi emission around the patient's TB-17 and TB-21 point areas. Next, guide the Qi to flow down the head, neck, shoulders, and arms along the Triple Burner Channels and out of the hand 3 to 7 times.
4. Finally, extend Qi into the patient's affected ear and guide the Qi down and out of the body along the corresponding Gall Bladder Channel ending at the corresponding foot.

MODIFICATIONS

- In cases of adverse rising of Liver Wind Fire, use the Vibrating Palm to emit Qi into the patient's Bl-18 and -19 points for 14 breaths on both sides of the body.
- In cases of Kidney Deficiency, emit Qi into the patient's Bl-23 points for 14 breaths.

PRESCRIPTIONS AND HOMEWORK

In the following three prescriptions make sure the patient heats his or her hands before beginning.

1. Have the patient perform the Beating the Heavenly Drum exercise (see Chapter 16) for 24 breaths.
2. Have the patient press the ears with the palms in a compression-release fashion 10 times each. Be sure to warn the patient to avoid forceful or violent compression. The patient's intention should focus deep within the orifice of the ears.
3. Have the patient pinch the top of the auricles of the ears gently, and massage them from the top downwards 24 times.

LUMBAGO

Lumbago is a general non-specific term for dull aching pain in the lumbar region of the back.

ETIOLOGY

Lumbago is a common symptom observed in many diseases, such as acute and chronic muscular strain of the lower back, subluxation of the discs, prolapse of the lumbar vertebra, etc. Patients may suffer from lumbago with pain radiating down to their lower limbs. Lumbago pain can also be aggravated by weather changes. Traditionally, there are three general causes of lumbago: lumbago due to Wind Cold and Dampness, lumbago due to Kidney Deficiency, and lumbago due to trauma.

1. Lumbago due to Wind Cold and Dampness, is caused by retention of Cold and Damp pathogens in the channels and collaterals. This in turn leads to the obstruction or stagnation of Qi and impairs Blood circulation.
2. Lumbago due to Kidney Deficiency is caused by an over consumption of the Kidney Jing due to an overactive sex life. This results in the failure of the Kidneys to nourish the Triple Burner Channels.
3. Lumbago due to trauma occurs from an injury to the tissues and muscles (e.g., dislocated vertebra, fractures, ruptured spinal disks, etc.), and leads to stagnation of Qi and Blood. Qi and Blood stagnation leads to obstructions in the channels and collaterals.

SYMPTOMS

1. Lumbago, due to Wind Cold and Dampness, is manifested by heaviness and pain at the waist, which may radiate to the hips and down the legs, or may be accompanied by muscular stiffness. In chronic cases, the pain is intermittent with various degrees of severity. On wet and cold days the patient often feels cold at the waist and lumbar area.
2. Lumbago, due to Kidney Deficiency, is manifested by continuous, dull pain, accompanied by soreness and weakness of the waist and knees, cold limbs and nocturnal emission.
3. Lumbago due to trauma is manifested by localized pain along with tenderness and limited mobility.

TREATMENT

1. Place the patient in a sitting position on the table. Begin stimulating the patient's Mingmen area with your left hand while the right hand guides the energy down to the patient's Bl-40 points behind the knees.
2. Using the Extended Fan Palm hand manipulation emit Qi into the patient's Mingmen and Bl-18 areas, guiding the Qi to flow along the Bladder Channels down the legs.
3. Next, place the patient in a supine posture, knees pointing upwards and feet flat on the table. Position yourself over the patient allowing the weight of your chest to support and compress the physical structure of the patient's knees, lower legs and feet. Embrace the patient's hips and imagine separating the inner fascia and tissues. The purpose for this compression is to initiate a strong internal stretching action within the tendons and smaller muscles of the patient's lower back and sacral area. This technique is used to disperse stagnant Qi and Blood within the patient's lumbar vertebra, sacrum and femur articulations. At the same time, direct the Qi upwards along the patient's spine and Governing Vessel. Hold this compression for several minutes.
4. To avoid respiratory congestion (while your weight is stretching the patient's sacrum and lower lumbar), the patient is instructed to raise the arms above the head.
5. As the patient experiences the lower back compression, he or she imagines the stagnant energy (trapped within the lumbar area) melting like ice into water and flowing through the Microcosmic Orbit (Fire Cycle). With each exhalation the patient relaxes to a deeper level, imagining him or herself sinking deeper into the table.

TREATMENT MODIFICATIONS

1. For lumbago due to Wind Cold and Dampness, purge the pathogenic Qi out of the patient's body first, and then emit Heat into the channel points associated with the specific location of the patient's pain.
2. For lumbago due to Kidney Deficiency, use a Vibrating Palm technique to emit Qi towards the patient's Mingmen, Bl-23 and Bl-18 points for 14 breaths each point on both sides of the body.
3. For lumbago due to trauma, extend Qi for 28 breaths into any Ah Shi point (painful tissue area).

INSOMNIA

Insomnia is described as a sleeping disorder that disrupts the patient's normal sleeping pattern. In mild cases, the patient may have difficulty falling asleep or remaining asleep (waking numerous times during the night). In severe cases the patient may be unable to fall asleep at all. Diseases with insomnia as part of their manifestation include anxiety disorders and menopausal syndrome.

ETIOLOGY

The amount and quality of sleep depends on the state of the patient's Shen, which is rooted in the Heart (specifically, the Heart Blood and Heart Yin). If the Heart is agitated or Deficient, the Shen cannot root, and sleep will be affected. Any disharmony of the body's internal organs due to an Excess or Deficient condition affects the patient's Jing and Blood. Since the Jing and Blood root the Shen, the Shen will have no residence and insomnia may result.

3. Stomach and Pancreas

Follow the above procedure and thrust through the middle organs to the stomach and pancreas. Practice nine times. Swallow the saliva, rest and feel the energy flow in the Middle Thrusting Channel up to the diaphragm.


Crown
Pineal Gland
Pituitary Gland
Thyroid Gland
Heart
Stomach
Vena Cava
Aorta
Prostate Gland

Fig. 7.7 *Middle Part in the Male*


Crown Point
Pineal Gland
Pituitary Gland
Tongue
Thyroid Gland
Thymus Gland
Heart
Stomach
Vena Cava
Aorta
Genitals
Fourth Pull Up
Third Pull Up
Second Pull Up
First Pull Up

Fig. 7.8 *Middle Part in the Female*

Insomnia can be caused by insufficient Blood due to impairment of the Spleen Qi, or from malnourishment of the Heart Qi due to a Deficiency of Heart Blood. This condition can also result from overfatigue, anxiety or irritability. This may be due to a disharmony between the Heart and Kidneys (resulting from Deficient Kidneys), irritability (due to mental depression) or from disharmony between the energetic function of the Stomach and Spleen (resulting from an improper diet).

Since the Hun (rooted in the Liver Blood or Liver Yin) play an important role in the length and quality of sleep, Liver Blood Deficiency can cause the Hun to be deprived of their residence and to wander at night causing restless sleep.

SYMPTOMS

The main symptom is an inability to sleep, which based on the different conditions of this illness can be further classified as:

- An inability to get to sleep,
- Sleepwalking, and an
- inability to fall asleep after waking.

The symptoms vary with the causes of the disease.

1. Insomnia due to a Deficiency of the Heart and Spleen (resulting from severe worry) may cause shallow sleep, or dream disturbed sleep. It is manifested by palpitations, poor memory, vertigo, dizziness and spontaneous sweating.
2. Insomnia due to Kidney Deficiency (resulting from excessive sexual activity) is manifested by dizziness, tinnitus, soreness in the loins and back area, as well as involuntary seminal emission.
3. Insomnia due to upward stirring of Liver Yang is manifested by pain and distention of the chest and epigastrium, belching, and acid regurgitation, as well as mental hyperirritability, dizziness and headaches.

TREATMENT

1. Begin by having the patient sit at the edge of the table. Your right hand emits Qi into the patient's CV-12 point, directing the energy to flow down into the patient's Lower Dantian. The left hand extends energy into the patient's mid-back around the area of the patient's Bl-18, Bl-19, Bl-20 and Bl-21 points, and leads the Qi down the Bladder Channels to the feet on both sides.
2. Next, use the Vibrating Palm technique to extend energy into the patient's Baihui, GV-14, Mingmen, CV-12 and Lower Dantian areas for 9 to 18 breaths each.
3. Emit Qi into the patient's Baihui area and leads the Qi from the top of the patient's head down the Conception Vessel into the Lower Dantian.
4. Finally, emit Qi into the patient's GB-8 point by the top of the ears and guide the Qi down the patient's Stomach Channels to the St-36 points.

TREATMENT MODIFICATIONS

1. For treatment of insomnia due to Deficiency of Heart and Spleen, emit Qi into the patient's Bl-20 and Bl-15 points, guiding the Qi down along the Bladder Channels to the feet.
2. For insomnia due to Kidney Deficiency emit Qi into the patient's Mingmen and Bl-23 points for 18 respirations.
3. For insomnia due to emotional depression, emit Qi towards the patient's Lv-3 and Lv-4 points (on both sides of the body), guiding the Qi down to the patient's lower extremities along the Liver and Gall Bladder Channels.
4. For insomnia due to Spleen and Stomach disharmony, use the Vibrating Palm hand technique to emit Qi into the patient's CV-12, St-36, and St-21 points on both sides of the body.

PRESCRIPTIONS AND HOMEWORK

For the best results, have the patient practice Medical Qigong prescriptions one to two hours before going to bed. For chronically ill patients, the causes of the insomnia should be removed first, followed by Medical Qigong prescriptions and regular physical exercise for lasting therapeutic results.

Have the patient perform the Kidney Massage for treating insomnia prescribed in Chapter 39.

PYELONEPHRITIS

Pyelonephritis is an infectious disease caused by bacteria invading the renal parenchyma and renal pelvis unilaterally or bilaterally. It clinically manifests through the following symptoms: fever, lumbago and abnormal discharge of urine.

SYNDROMES

1. Damp Heat in the Bladder is clinically manifested through symptoms such as frequent and painful urination, fever, distention and pain in the lower abdomen, lumbago and aversion to cold.
2. Stagnation of Liver and Gall Bladder Heat is clinically manifested through symptoms such as fever with or without chills, nausea, loss of appetite, lumbago or pain in the lower abdomen, frequent urination with cloudy urine and feeling agitated.
3. Spleen and Kidney Deficiency with Heat stasis is clinically manifested through such symptoms as edema of the face, swelling of the feet, abdominal distention, thin stools and frequent urination, lassitude and weakness in the entire body (especially the legs), dizziness, tinnitus and anorexia (lack of appetite).

TREATMENT

1. Have the patient sit at the edge of the table and begin stimulating the Mingmen and Lower Dantian areas using a Vibrating Palm technique for 11 to 22 breaths.
2. Next, have the patient lay supine on the table and stimulate the patient's Sp-6 and Kd-3 areas on both sides of the body.
3. Use the Extended Fan Palm hand technique to emit Qi into the patient's Lower Dantian, guiding it down the Kidney Channels to the bottom of the feet.

TREATMENT MODIFICATIONS

1. When treating patients with Damp Heat in the Bladder, use a Sword Fingers hand posture and apply the Vibrating technique, emitting Qi into the patient's Mingmen and Lower Dantian for 14 to 28 breaths.
2. When treating patients with stagnant Heat in the Liver and Gall Bladder, use the Extended Fan Palm hand posture to emit Qi into the patient's mid-back and Liver, purging Toxic Qi down the Liver and Gall Bladder Channels and out of the body via the legs.
3. When treating patients with Deficient Spleen and Kidneys, use the Extended Fan Palm hand posture to emit Qi into the patient's mid-back Bl-20, and Bl-23 points, CV-12 and Lower Dantian areas.

PRESCRIPTIONS AND HOMEWORK

Have the patients practice the Standing Post Posture with arms suspended at the Middle Dantian, and the mind's intention focused on the Lower Dantian. Use natural abdominal breathing (see Chapter 16).

PRESCRIPTION MODIFICATIONS

1. For patients with Damp Heat in the Bladder, have them practice rubbing the costal area and sounding "Who."
2. For patients with stagnant Liver and Gall Bladder Heat, have them practice massaging the costal area and sounding the word "Shu."
3. For patients with Spleen and Kidney Deficiency, have them practice the method of Taking in Yellow Qi, as well as the Gathering the Moon Cream exercise (see Chapter 11).

IMPOTENCE

Impotence is a weakness and inability of the male to achieve or maintain an erection. Symptoms vary from premature ejaculation to partial penile erection (the penis is erect but not hard, resulting in the incapability of sexual intercourse), to a complete failure to achieve any erection at all. Impotence indicates a weakness in all Five Yin Organ energies. The combined energies must be sufficient to culminate an erection, as described below.

1. The Heart energy quality is strongly affected by the nature of the sexual encounter. Casual sex may not involve the highest spiritual energy of the Heart's upper chamber (see Chapter 5), only the basic instincts and drives of the lower chamber. The Heart may also be affected by the individual's moral values and beliefs, as well as the quantity and quality of emotional passion (i.e., with or without guilty feelings) at the time of arousal. Heart energy also pertains to the energy of the Blood.
2. The Spleen energy pertains to what the man

is thinking and his intention at the time of arousal. This also affects the man's muscles.

3. The Liver energy pertains to visual stimulation that affects a man's sexual drive. This affects the man's strength. Many aspects of man's sexuality are relate to the Liver's functions, i.e., visual images evoking emotions, Blood filling the erectile tissue, and the power of desire.
4. The Kidney's Qi pertains to the Jing energy stored within the Marrow, and relates to the man's will power and endurance. It is associated with audible stimulation and affects the man's endurance.
5. The Lung Qi is man's somatic expression of sexual passion and is stimulated through touch and smell. This energy also affects the man's endurance.

ETIOLOGY

There are two main factors ascribed to impotence: psychogenic and organic. In the first case, the patient's physical, mental, emotional, and spiritual energies are out of harmony. This can be caused by fear, excitement, performance anxiety, etc. In the second case, impotence can be caused by medications, drugs, alcohol, etc. In most organic cases, however, impotence is caused by prostate failure, cardiovascular disease or diabetes. If this condition persists long enough the man looses sexual interest and the condition becomes psychosomatic.

SYNDROMES

- Insufficiency of Kidney Yang is clinically manifested through symptoms such as impotence, lumbago, weakness in the knees, dizziness, tinnitus, aversion to cold, cold limbs and a cold sensation in the external genitalia, listlessness and shortness of breath.
- The downward flow of Damp Heat is clinically manifested through such symptoms as impotence, itching and pain around the external genitalia and scanty, dark urine.

TREATMENT

1. Stimulate the patient's Mingmen and Lower Dantian areas using the Vibrating Palm technique for 12 breaths.
2. Next, stimulate the patient's Sp-6 areas on each leg, leading the Qi up into the Lower Dantian for 12 breaths.
3. Finally, return back to the Mingmen and Lower Dantian areas using the Extended Fan Palm hand technique. Emit Qi for 24 breaths, rotating in a clockwise direction to gather the Qi in the Lower Dantian.

TREATMENT MODIFICATIONS

- When treating a patient with an insufficiency of Kidney Yang, vibrate the energy using the Sword Fingers Hand technique, while emitting Qi into the Lower Dantian for 16 to 18 breaths.
- When treating a patient with a condition of Damp Heat flowing downward, purge the Qi along the Kidney Channels down into the Lower Dantian. Use the Extended Fan Palm hand technique and emit Qi into the patient's Lower Dantian, Kd-13 and Kd-14 points on both sides of the body, as well as the navel area, for 24 breaths.

PRESCRIPTIONS AND HOMEWORK

It is advisable to have the patient perform the Deer exercise, prescribed for increasing the body's Jing.

1. Have the patient sit on the edge of the chair, rubbing the palms to create heat. This right hand will cup his testicles so that the palm completely covers them with slight pressure. The left hand is placed on the area of the Lower Dantian just below the navel. The left hand moves in a circular clockwise direction 81 times. Next, the hands are rubbed together again, reversing the hand positions so that the left hand cups the testicles and the right hand is on the Lower Dantian. The circle rubbing is repeated in the opposite direction 81 times. Concentrate on the heat and Qi filling up the Lower Dantian and genital area.
2. The patient should tighten and draw up the anal muscle while inhaling, feeling the Qi being drawn up the rectum and prostate area, filling up the Lower Dantian. He should hold the breath as long as possible, then exhale, release and relax. The anal contraction exer-

cise should be repeated beginning with 25 breaths, and eventually working up to 250 breaths.

PRESCRIPTION MODIFICATIONS

1. When treating patients with Kidney Yang Deficiency, it is advisable to have them practice Beating and Drumming the Qi with lower abdominal breathing (see Chapter 42).
2. When treating patients with a downward flow of Damp Heat, it is advisable to have the patient rub the Lower Dantian and sound the healing tones "Chree" for 36 breaths and "Shu" for 36 breaths.

CHAPTER 48

QI EMISSION THERAPY FOR MISCELLANEOUS DISEASES

INTRODUCTION

This chapter deals with miscellaneous diseases that are classified as either complicated multiple diseases, or energetic conditions which have not yet been classified. This section describes the conditions, symptoms and treatment for these syndromes. The discussion of these various treatments begins with energetic dysfunctions stemming from the Qi of the Three Dantians, and expands further to include other tissues, internal organ and energetic organ system complications.

DEFICIENT DANTIAN QI

One of the most common problems found in the body's energetic system is Deficient Dantian Qi. The symptoms vary according to the location of the Deficiency, as well as the patient's constitution.

1. If the energy is Deficient within the Lower Dantian, the symptoms and syndromes cover a large range that includes: chronic diarrhea, asthma due to Kidney Deficiency, hypertension due to Yin Deficiency, Blood Deficiency, insomnia, spermatorrhea, collapsing syndrome due to Deficiency, abandoned-type Wind Stroke, abandoned-type coma and all types of organ prolapse.
2. If the energy is Deficient within the Middle Dantian, the problems may include shortness of breath, bronchitis, asthma, chest pain, palpitations, intercostal neuralgia, all breast disorders including acute mastitis and breast abscesses.
3. If the energy is Deficient within the Upper Dantian, the problems may include frontal headaches, dizziness, vomiting, fainting due to Blood loss, insomnia, eye soreness, febrile convulsions and insanity.

PRESCRIPTIONS FOR REGULATING THE THREE DANTIANS

The following meditations are prescriptions used to regulate the heat, vibration, and light in the Lower, Middle, and Upper Dantians.

1. The Lower Dantian meditation solidifies the Qi in the Lower Dantian that allows for stable energy transference to take place. The purpose for Heat Regulation in the Lower Dantian is to cause the internal organs to steam; this transfers energy from organ to organ to nurture and regulate the body's Qi.

   Have the patient focus on breathing into the center of the Lower Dantian. Upon inhaling, the patient imagines drawing Qi into the body from the nose, urethra and anus, and directs it into the Lower Dantian. After inhaling, the patient closes the lower orifices and circulates the Qi up through the coccyx and Mingmen area, then down into the navel and into the Lower Dantian. It is important that the patient visualize a ball of energy rotating in the lower abdomen like a spinning wheel. As this Qi begins to collect in the Lower Dantian, heat and vibration begin to resonate in the lower abdominal area.
2. The Middle Dantian meditation expands the patient's Wei Qi, which in turn enhances the body's protection against an attack of Hot or Cold pathogenic factors. The patient should draw the Toxic Qi out of the Yang Channels of the arms, through the center point of the palms. This is an excellent meditation for treating diseases caused from Excess Heat, such as insomnia, headaches, hypertension, and arthritis of the joints:

   To regulate the heat of the Heart Fire and Middle Dantian area, the patient focuses the breath and mind's intention on the center of the chest (CV-17) while placing the right thumb inside the heart of the left palm (Pc-8), while resting both hands on the lap.

3. The Upper Dantian meditation not only expands the patient's Wei Qi, but also fills the body with sound and light vibration. Sound and vibration are used in the Qigong clinic to purge Toxic Qi out of the patient's body. This is an excellent meditation for balancing and energizing all Three Dantians.

   The patient begins in a standing or sitting Wuji posture, with the spine straight, Mingmen pressed back, anal sphincter closed, tongue on upper palate, and breathing naturally. This particular exercise follows the opening and closing pattern of Qi regulation. The focus is placed on each Dantian area for a period of 18 to 24 breaths. Each Dantian area needs a specific sound and light visualization to open, purge, close, and regulate its energy. The sounds and physical actions are as follows.

- To open, energize and regulate the Upper Dantian, use the sound of "Om." The arms separate and come together above the Baihui area (above the head) in order to open and close the Upper Dantian. The focus of the mind's intention is placed on drawing in divine healing light while inhaling, to fill the Taiji Pole. When exhaling, imagine the energy rushing into the Upper Dantian while toning the first vowel sound "O." Then imagine light shinning outside of the body while sounding the consonant sound "m." On the beginning of the vowel sound, the tongue is placed on the lower palate. As the tone and breath reach its midpoint, the tongue rises to connect with the upper palate to finish the sound "Om."
- To open, energize and regulate the Middle Dantian use the sound of "Ha." The arms separate and come together above the chest at the CV-17 point while opening and closing the Middle Dantian. The focus of the mind's intention is placed on drawing in divine healing light while inhaling, to fill the Taiji Pole. When exhaling the tone "Ha", separate the arms and imagine that the Qi rushes into the Middle Dantian and then expands to shine outside of the body. On the beginning of the tone "Ha," the tongue should be placed on the lower palate. As the tone and breath reach its midpoint, the tongue maintains its connection to the lower palate.
- To open, energize and regulate the Lower Dantian use the sound of "Hai-riem." The arms separate and come together above the lower abdomen at the CV-8 point while opening and closing the Lower Dantian. The focus of mind's intention is placed on drawing in divine healing light while inhaling, to fill the Taiji Pole. When exhaling, imagine the Qi rushing into the Lower Dantian with the first syllable "Hai," then shines outside of the body when the syllable "reim" is pronounced. At the beginning, the tongue is placed on the lower palate to pronounce the sound "Hai." As the tone and breath reach its midpoint, the tongue changes its position to behind the teeth to tone the sound "reim."

All three sounds are used to activate and energize the body's Three Dantians by practicing these sounds in the following two step progression:

1. Upon inhalation, focus the mind's intention on drawing divine healing light into the body to fill the Taiji Pole.
2. While exhaling, sound the specific tone of each Dantian, while both hands perform the opening (the expanding movements of the arms and hands) and closing (the contracting movements of the arms and hands) technique at each Dantian. The mind visualizes the light resonating and shining out from the body at each Dantian during the toning.

IMPROPER YIN AND YANG ENERGY BALANCE

Another common problem observed in the clinic is an imbalance of Yin and Yang Qi within the patient's body. Converting and balancing the Yin and Yang energy diverts the Qi before it has a chance to overload the body's system. The Qigong doctor first removes any obstruction in the patient's Governing Vessel and then harmonizes the patient's Yin and Yang energy by extending Qi into the patient's back, on the GV-13 and -14 points.

The following meditations are used as prescriptions to develop a strong electrical charge in the body, that balances the Yin and Yang currents:

Have the patient place the thumb in the heart of his or her palm (Pc-8), fingers touching the back (dorsal) side of the hand, opposite the (Pc-8) point (Figure 45.1). To energize the Lower Dantian the patient concentrates on his or her lower abdominal area. To energize the Middle Dantian the patient should concentrate on the area at center of the chest. The only difference between the Lower Dantian exercise and the meditation used to heat the Middle Dantian is the focal point of the patient's concentration. In these particular exercises, the hand postures are the same, however, the mind is focused on either the hands near the Lower Dantian, or on the middle of the chest.

- For men to develop a stronger electropositive Yang energy field, the right hand should cover the top and center of the left hand. To develop a stronger electronegative Yin energy field, the left hand should cover the top and center of their right hand.
- For women to develop a stronger electropositive Yang energy field, the left hand should cover the top and center of the right hand. To develop a stronger electronegative Yin energy field, the right hand should cover the top and center of the left hand.

Note: In generating energy within each Dantian area it is important to understand basic Yin and Yang polarities and their relationship to male and female. The female chest is considered Yang while the female genital area is considered Yin. The female Middle Dantian (or Heart area) is the focal point of female Yang (positive) energy; the genital area is the focal point of female Yin (negative) energy. Conversely, the male chest is considered Yin while the male genital area is considered Yang. The Middle Dantian (or Heart area) is the focal point of male Yin (negative) energy; the genital area is the focal point of male Yang (positive) energy (see Chapter 5).

DISORDERS OF THE QI

Whenever energy movement is impeded, disorders in Qi functions occur. Generally, these disturbances cause either disorders of Fire, or disorders of Water (see Chapter 22).

The cause and progression to these disorders can be further broken down and classified according to their energetic dysfunction. There are several types of Qi disorders observed in the clinic and they are generally described as follows.

LEAKAGE AND LOSS OF QI

During or after training practice, the patient may feel that Qi is continuously and uncontrollably leaking out of the body from the genitalia and anus or somewhere else on the body. This loss of Qi can lead to Qi Deficiencies and manifest through the following symptoms: emaciation, weakness of the limbs, grayish and dull complexion, nervousness, mental disturbances, distractibility, failing memory, spontaneous sweating, night sweats, seminal emission, insomnia, lassitude and sluggishness.

To treat this condition apply the Extended Fan Palm technique, use the Pushing, Pulling, and Shaking manipulations to emit Qi into the Mingmen; then use Vibrating and Shaking manipulations to emit Qi into the Lower Dantian.

QI STAGNATION DISORDERS

Qi stagnation exists when the Qi becomes sluggish when moving within the body's channels, organs, or tissues. Qi stagnation can be caused by many different factors such as suppressed emotions, trauma, contraction of microorganisms, poor diet, and weak digestion. Qi stagnation, over time, results in localized pain, distention, cysts, tumors, etc. Qi stagnation disorders have two subcategories: Qi and Blood Stasis, and Obstructed Qi (see Chapter 22).

1. Qi and Blood Stasis refers to the sensation of local pain, heaviness, soreness, distention, and compression, which are caused by the stagnant Qi and Blood in certain areas of the body. These sensations do not resolve by themselves. This stasis may occur during or after

Medical Qigong training practice from Qi disorders and visceral malfunctions.

2. Obstructed Qi is also considered a subcategory of Qi stagnation, and exists when the Qi becomes so stagnant that it no longer flows. At this stage the Qi can't move the Blood. This can be caused by trauma, surgery, and acute Qi stagnation.

Reconstructive Qi therapy, for conditions of Qi stagnation use the following two methods:

1. Select corresponding channel points in the region of the Qi and Blood stasis. Knead the selected channel points, then push and rub along the obstructed channel.
2. Finish the treatment by applying the Extended Fan Palm technique; use the Pushing, Pulling and Shaking manipulations to emit and conduct Qi along the channels to open them.

REBELLIOUS QI DISORDERS

Rebellious Qi disorders manifest as Qi flowing in the wrong direction (a direction different from its normal physiological progression); this causes a disturbance within the harmonious flow of energy and affects the organ functions. The symptoms have to be analyzed according to the internal organ which is involved. There are two types of Rebellious Qi, the Excess type and the Deficient type. Rebellious Qi is categorized as follows.

DISORDERS OF EXCESS REBELLIOUS QI

Disorders of Excess Rebellious Qi occur when the vital Qi increases and forces the pathogenic Qi to move. This causes local sensations of pain, soreness, distention, heaviness, coldness or hotness which can develop during Qigong practice. To treat for conditions of Rebellious Qi, use the following two methods:

1. From the head and torso, follow the routes of the channels and collaterals out to the extremities. Pinch and lightly pull on the extremities (fingers and toes). Then press, knead, push and rub the location of the discomfort, guiding and leading the Qi along the channels away from the area of discomfort.
2. Apply the Extended Fan Palm method; use the Pulling and Leading manipulation to pull and guide the Qi, or open up the channel points to disperse the Qi.

DISORDERS OF DEFICIENT REBELLIOUS QI

Disorders of Deficient Rebellious Qi refer to the disorderly flow of Qi and Blood during or after training practice, which can cause dizziness, fright, a heavy feeling in the chest, shortness of breath, shaking limbs, trembling of the hands and feet or fainting. Generally, energy sensitive practitioners know the location and direction of the disorderly flow of Qi in their tissues.

To treat conditions of Deficient Rebellious Qi use the following two methods:

1. Open the appropriate channel points to regulate the functional activities of the Eight Extraordinary Vessels.
2. Select appropriate regions and channel points and apply the Extended Fan Palm or Sword Fingers technique. Use Pushing, Pulling, and Shaking manipulations to activate the channel Qi of that particular channel or region. Then, use the Leading manipulation to direct the Qi into specific channels or return it to the Lower Dantian.

ARTHRITIS

Arthritis is defined as inflammation of the joints, usually accompanied by pain, swelling and frequently changes in structure. This is a chronic, multiple arthropathy and can be divided into the peripheral type (pertaining to the four limbs), and the central type (pertaining to the spinal column, i.e., rheumatoid arthritis or ankylosing spondylitis).

ETIOLOGY

Arthritis is caused by pathogenic Wind, Cold and Dampness attacking the body's channels and hindering the Qi and Blood circulation. This invasion can give rise to pain, soreness, heaviness, and numbness of the tendons and muscles, as well as swelling and difficulty in moving the joints. This condition can be caused from an unstable lifestyle weakening the body's Wei Qi, overexposure to a draft after sweating, wading in water, exposure to cold weather, or laying on a damp ground for long periods of time.

SYMPTOMS

Arthritis is clinically manifested primarily as arthralgia and dysfunction of the joints and can be accompanied by muscle spasm, loss of muscle tone, loss of muscle mass and deformity. Symptoms can be divided into early and late stages.

- In the early stages of arthralgia, the local swelling usually starts from the small joints of the fingers and toes, wrists and ankles, or from the iliosacral joint and spreads upward into the body. Several weeks or months later, the patient may feel local tenderness and inflexibility of the joints with some clicking or cracking sounds. In this stage the pain is worse at night and early in the morning, and may be alleviated with gentle exercise. In the early stages of arthritis, the patient's condition can be controlled and even restored back to normal through Medical Qigong prescriptions.
- In the later stages of arthritis, the articulation of the joint movement is markedly limited, and patients may experience deformity in the joints, as well as stiffness, muscular atrophy and paralysis. The phalangeal and carpal joints of the patient's hands may become rigid and deviate to the ulnar side of the arm. The fingers may also become deformed with restricted mobility, and the elbow and shoulder joints may also be affected. In the late stages of arthritis, the treatment can only control the progression of the disease and alleviate local symptoms. The patient's locomotive function can only be gradually improved.

If the patient's lower limbs are affected, the ankle, knee and hip joints may become rigid, and he or she may experience motor impairment. If arthritis occurs in the patient's spinal column, it may cause kyphotic deformity and dyspnea, as well as restriction in neck movement. At this stage a sudden backward flexing of the neck may cause sudden death in patients with rigid forward bending neck deformity.

When treating an External invasion of pathogenic factors, the Qigong doctor observes three main symptoms of arthritis:

1. Wind or migratory arhtralgia is manifested by pain that has no particular fixed location, but moves throughout the body's extremities and joints, and is sometimes accompanied by chills and fever.
2. Cold arthralgia is manifested by localized pain of the joints, which may be relieved by heat and aggravated by cold.
3. Damp arthralgia is manifested by fixed pain and swelling in the joints and extremities, or by numbness of the skin which may be aggravated in cloudy and rainy weather.

TREATMENTS

1. Place the patient in the standing posture and begin dredging the Governing Vessel, drawing the energy into the ground.
2. Use the Extended Fan Palm hand technique and begin to emit Qi into the patient's GV-14, Mingmen, and Lower Dantian areas.
3. While emitting Qi into the painful joint areas, purge the pathogenic energy out of the patient's body, leading the Toxic Qi along the channels and out of the extremities.

PRESCRIPTIONS AND HOMEWORK

In treating arthritis it is important to prescribe exercises which lubricate the joint articulations to increase the production of Qi and Blood to the extremities. The Daoist Five Yin and Yang Organ exercises will accomplish this goal quite easily.

The patients are required to perform Qigong prescriptions which improve the body's resistance, but do not cause fatigue. Patients should also improve their diet and should be encouraged to consult a nutritionist for natural supplements that can help rebuild healthy cartilage and reduce pain. They should also make every effort to keep their body warm.

For patients with osteoporosis, stretching techniques, as well as sudden forward flexing of the neck are absolutely prohibited.

PRESCRIPTION MODIFICATIONS

1. When treating patients who suffer from arthritic pain in the upper limbs, advise them to practice shoulder and arm Dynamic Medical Qigong, moving at a slow, fluid pace.
2. When treating patients who suffer from ar-

C. Right Thrusting Channel to the Diaphragm

1. Right Testicle (Men), Right Ovary (Women) and Right Kidney
    a. Close the left nostril with the index finger of the left hand. Use the right eye, ear and nostril to direct the energy up the right channel. Put your right hand on the right kidney.
    b. Inhale in short sips equal to ten percent of lung capacity. Look up with the right eye. Pull up the right testicle (men only) and the right muscle of the anus toward the right side. Direct the energy up the right Thrusting Channel to the right ovary (women) and kidney. Practice nine times.
    c. Exhale and rest. Let the pearl drop down, returning to the perineum and right testicle (men only.) Feel the right side become lighter as the energy flows up the Right Thrusting Channel to the right kidney without effort.


Left Side of the Brain
Eye
Ear
Right Lung
Heart
First Pull Up in the Middle
Liver
Right Side
Adrenal Gland
Right Kidney
Large Intestine
Prostate Gland
Left Testicle

Fig. 7.9 *Right Part in the Male*

thritic pain in the lower extremities, advise them to practice Dynamic Walking Medical Qigong (see Chapter 15), moving at a slow, fluid pace.
3. When treating patients who suffer from arthritic pain in the waist and lower back, advise them to practice the Expanding and Contracting the Rings exercise (see Chapter 41).
4. When treating patients who suffer from arthritic pain in the neck, advise them to practice slow-moving non-forceful neck rotation exercises in conjunction with stationary neck massage.

VERTIGO

Vertigo is a syndrome manifested mainly by dizziness and dim eyesight. It is defined as a sensation of moving around in space or having objects move about the person as a result of a disturbance of equilibrium. Vertigo is sometimes used as a synonym for dizziness, feeling light headed, or giddy.

Patients with mild vertigo may experience relief from this condition after a short bed rest, with their eyes closed. In severe cases, patients may suffer from a serious rotary vertigo and will not be able to stand or walk straight (e.g., sea and air sickness), sometimes followed by nausea, vomiting, perspiration, or even syncope (fainting).

Diseases that have vertigo as their main manifestation include cerebral arteriosclerosis, auditory vertigo, hypertension, anemia, and psychosomatic illnesses such as hyperventilation (which often accompanies anxiety disorders, especially panic disorders). These diseases may be diagnosed, categorized, and treated with reference to the prescriptions described in this section.

ETIOLOGY

Several factors contribute to the vertigo syndrome. In ancient times, Chinese physicians believed that vertigo was caused by Yin Deficiency and Excess Liver Wind, or by a head trauma. In Excess conditions, vertigo is caused by Phlegm Fire or Wind Phlegm. Currently, the clinical protocol for treating vertigo is divided into three conditions:

1. Hyperactive Liver Yang causing an insufficiency of Kidney Yin,
2. A Deficiency of Qi and Blood in the Heart and Spleen causing a Deficiency in the Marrow reservoir, and
3. Stagnation of Phlegm Dampness caused by a Deficiency of Spleen and Stomach Qi (which fail to transport the Phlegm).

Vertigo may be caused by a variety of factors affecting the ear, the eighth cranial nerve, and the brain stem; including middle ear disease, infectious diseases, trauma, tumors, toxemia due to food poisoning, hypertension, sun stroke, and toxic conditions such as those caused by alcohol and drugs. Over medication and malnutrition (especially in the elderly who suffer from dehydration) also cause vertigo.

SYMPTOMS

1. In cases where the patient has hyperactive Liver Yang, the syndrome of vertigo is characterized by severe dizziness, splitting headache, blurred vision, nausea, soreness and weakness of the waist and legs, mental fatigue (caused by emotional upset and anger), flushed face, constipation and tinnitus.
2. In cases of Qi and Blood Deficiency, the symptoms include rotary vertigo, blurred vision or night blindness, listlessness, disinclination to talk, palpitations, insomnia and anorexia.
3. In cases of stagnation of Phlegm Dampness, the symptoms include chest pain and distress, nausea and vomiting, poor appetite, listlessness of the body and heaviness in the head.

TREATMENT

When treating patients with vertigo, begin with the upper body working downward and from the medial aspect of the body towards the lateral part of the body.

1. Begin with the patient sitting on the edge of the table. Stimulate the patient's Baihui, the sides of the head, (GB-4, GB-8, and Taiyang areas), GV-14, Shendao, Mingmen, and the Lower Dantian.
2. Next, use the Vibrating Palm hand manipulation to emit Qi into the patient's Baihui, GV-14, Yellow Court and Lower Dantian for 12 to 24 breaths.

3. Use the Extended Fan Palm hand technique to emit energy into the patient's St-8, St-21 and St-36 points on both sides of the body.
4. With the left palm, emit Qi into the patient's Baihui point while using the right hand Sword Fingers to guide the patient's Qi from the Yellow Court down the Conception Vessel into the Lower Dantian.
5. Next, direct the Qi from the patient's St-8 points down to the St-36 points via the Stomach Channels.
6. Purge the energy of the upper torso out through the hands via the Large Intestine Channels.
7. Finally, lightly pat and knead the patient's Baihui and GV-14, softly rocking their upper limbs to end the treatment. Softly pressing and kneading the patient's tissues along their channels can push Qi and Blood downward to free the patient's mind from Toxic Qi and can improve the eyesight. The soft grasping can relieve stasis of Qi and Blood in the patient's blood vessels and promote circulation, thus reducing and relieving vertigo.

TREATMENT MODIFICATIONS

1. In cases of hyperactive Liver Yang, use the Extended Fan Palm hand method to emit Qi into the patient's Bl-18, Mingmen, and Lower Dantian. Guide the Qi to flow along the channels (or in a clockwise direction) to nourish the patient's Yin and to suppress the hyperactive Yang.
2. In cases of Deficient Qi and Blood, use the Extended Fan Palm hand method to emit Qi into the patient's mid-back (Bl-17, Bl-18, and Bl-20 points) and Lower Dantian to nourish the patient's Qi and to replenish the Blood.
3. In cases of stagnation of Phlegm Dampness, use the Extended Fan Palm hand method to emit Qi into the patient's Yellow Court. Guide the Toxic Qi down the Stomach Channels and expel the pathogens out from the patient's St-36 points.

PRESCRIPTIONS AND HOMEWORK

To treat vertigo, have the patient practice the Descend the Qi and Cleanse the Organs exercise (see Chapter 41).

PRESCRIPTION MODIFICATIONS

When treating patient's who suffer from a Deficiency of Kidney Yin and a hyperactivity of Liver Yang, prescribe the following meditation. Have the patient take a standing or sitting posture, breathing naturally, and relaxing. While inhaling through the nose, the patient imagines blue energy filling the mouth. When exhaling, the patient imagines this dark blue energy slowly pouring down the throat, like warm water, filling the Kidneys and Lower Dantian area. The patient should practice this meditation for 7 breaths.

HEADACHES

A headache is defined as a diffused pain in different portions of the head which is not confined to any one nerve distribution area. It may be acute, chronic, frontal, temporal, occipital, confined to one side of the head, or affect the region immediately over one or both eyes. The character of the pain may vary from dull and aching, to acute stabbing pain that is almost unbearable. There may be intermittent, intense pain, a throbbing pain, a pressure in the head which feels as if it will burst the head, or a penetrating pain driving through the head.

ETIOLOGY

Transient, acute headaches may vary in their etiology. Disease of the perinasal sinuses, teeth, eyes, ears, nose or throat, acute infections, invasion of Wind Cold pathogens into the channels of the head, or trauma to the head are among the most frequent causes of headaches.

Chronic headaches may also be caused by a variety of conditions including physical, emotional, psychosomatic, or psychogenic factors, including fevers, metabolic conditions (hypertension, etc.), or even exposure to toxic chemicals.

SYNDROMES

Headache syndromes can be divided into five categories which are described as follows.

1. A Shaoyang headache (migraine) is clinically manifested through symptoms such as a severe headache (splitting pain) in the temple region accompanied by Excess Heat in the

head, conjunctive congestion, and sometimes intercostal fullness or pain. Nausea often accompanies a severe migraine attack.

2. A Taiyang headache (occipitocervical headache) is clinically manifested through such symptoms as a headache and pain in the back of the head which can be accompanied by fever, aversion to cold, and rigidity at the back of the neck.
3. A Jueyin headache (vertical ache) is clinically manifested through such symptoms as a vertex headache, vertigo, insomnia, dizziness, and irritability with a flushed face.
4. A Yangming headache (frontal ache) is clinically manifested through such symptoms as a headache in the upper part of the cranium accompanied by dysphoria (depression and anxiety) with a smothering sensation, thirst, bad breath and constipation.
5. A Deficient Qi and Blood headache is clinically manifested through such symptoms as a lingering headache with a heavy sensation in the head, blurred vision, lassitude, and weakness.

TREATMENT

Begin by purging and dredging the patient's Upper Dantian, focusing on the Yintang, Taiyang, Baihui, GV-16, GV-20, and GB-4 points. Purge the pathogenic Qi down the patient's arms and out the LI-11 and LI-4 points, as well as down the Gall Bladder Channel out of the GB-41 points. The point and channel purging is specific to the location (right or left side) of the headache.

Next, using the Extended Fan Palm hand technique, emit Qi into the patient's headache region, purging it down the Conception Vessel to the Lower Dantian.

TREATMENT MODIFICATIONS

1. When treating a patient with a Shaoyang headache, apply the Extended Fan Palm hand technique to emit Qi into the GB-4, GB-8, and TB-20 points, leading the pathogenic Qi out of the Triple Burners and Gall Bladder Channels.
2. When treating a patient with a Taiyang headache, apply the Extended Fan Palm hand technique to emit Qi into the LI-11 and Bl-10 points, Purging pathogenic Qi down the Large Intestine and Bladder Channels and out of the hands and feet.
3. When treating a patient with a Jueyin headache, start at the head using the Circle Spiraling hand technique in a counterclockwise direction, purging the Toxic Qi out the patient's Gall Bladder Channels and out of the legs.
4. When treating a patient with a Yangming headache, use the Extended Fan Palm hand technique to emit Qi into the patient's Taiyang, Yintang, and St-8 points, purging the Toxic Qi down the Stomach Channels and out of the legs.
5. When treating patients with Deficient Qi and Blood, use the Extended Fan Palm hand technique to emit Qi into the patient's mid-back, at the Bl-17 and Bl-20 points, and the chest at the CV-17 point. Then emit Qi into the patient's CV-12 and Lower Dantian areas.

PRESCRIPTIONS AND HOMEWORK

1. It is advisable to have the patient practice the Ten Dragons Run Through the Forest exercise found in the Wash the Face and Massage section of Chapter 39.
2. It is beneficial to prescribe the following meditation to prevent the advancement of an acute attack. The main focus of this meditation is to direct Blood, Heat, and Qi to the body's upper extremities (the arms and hands), away from the original source of pain (i.e., the head).
    a. From a sitting, semi-reclining, or lying posture, the patient begins to relax and quiet the mind, with the eyes closed.
    b. The patient imagines that it is summertime and he or she is at the beach. Next, the patient focuses on both arms and hands, imagining them growing warmer and warmer in the hot sun. The patient imagines feeling massive amounts of heat radiating from the arms and hands, redirecting the Blood flow away from the head.
    c. Then, the patient imagines the face becoming cooler, as the pressure and pain

melts down the neck, shoulders, arms, forearms and out of the hands.

Prescription Modifications

1. For patients with a Shaoyang headache, focus the prescription meditations and exercises on treatments that purge the bilateral sides of the patient's head along the Triple Burners and Gall Bladder Channels, dredging the pathogenic Qi down and out of the patient's arms and legs.
2. For patients with a Taiyang headache, focus the prescription meditations and exercises on treatments that purge the patient's occiput and cranium, the Small Intestine and Bladder Channels, and that dredge the pathogenic Qi down and out of the patient's arms and legs.
3. For patients with a Jueyin headache, focus the meditations and exercises on treatments that purge the patient's vertex cranium, dredging the Toxic Qi down the Liver Channels and out of the legs.
4. For patients with a Yangming headache, focus the prescription meditations and exercises on treatments that purge and dredge the energy from the patient's forehead down the Large Intestine and Stomach Channels and out of the legs.
5. For patients with a Deficient Qi and Blood headache, focus the prescription on Lower Dantian Cultivation exercises and meditations.

MIGRAINE HEADACHES

This type of headache initially consists of a constriction in the head arteries, followed by vasodilation of the extracerebral cranial arteries.

ETIOLOGY

Migraine headaches are usually brought about by stress, and can also be initiated by an allergic reaction to what the patient's body considers to be a toxic invasion (e.g., cheese, chocolate, red wine, contraceptive pills, etc.). These types of stresses on the body's system result in internal organ dysfunction, which is generally caused by one or more of the following three factors.

1. The energy of the Heart and Spleen are not regulated.
2. A rising up of Liver Heat and Fire occurs.
3. A Deficiency of Kidney Yin and rising of Heart Fire occurs simultaneously.

The result of stress-related internal organ dysfunctions causes the initial constriction of the arteries in the head, followed by vasodilatation and distention of the vessels.

SYMPTOMS

The clinical manifestations of migraine headaches are hypersensitivity to light and sound, followed by severe, throbbing pain (most commonly felt on only one side of the head), nausea, dizziness, and sometimes vomiting. Some migraine patients experience seeing an aura or visual disturbances (colors, shapes, lines, flashing spots, or temporary reduction in the field of vision) before the head pain begins.

TREATMENT

For treatment, the Qigong doctor must pull the pathogenic energy out of the patient's head, from the location of the pain; then lead the Excess Toxic Qi out of the patient's extremities, and open up the channels so that Qi can rise and fall to the patient's head unobstructed.

1. In a severe case, combine Medical Qigong therapy with Jing Point therapy.
   a. Begin the treatment by pulling out (with strong intention) the stagnant Qi trapped in the patient's head. First, purge the patient's Wei Qi field, then enter the patient's Jade Pillow at the base of the head. Next, emit Qi along the falx cerebri and circulate it using your intention to create a small Microcosmic Orbit (circling from the back of the head to the nose and back). This encourages the patient's stagnant Qi to move.
   b. Next, dredge around the area of the patient's eye (from the inner corner of the eye to the side of the eye), starting at the Bl-1 point to the Yin Tang point (Third Eye), following the sphenoid arch across to the temple at the Taiyang point, then to the back of the ear at the

TB-17 point. Next, lead the pathogenic Qi down the neck and pull out the stagnant Qi through the extremities (Pc-6 and LI-4 on the hand). If the patient is feeling nausea, purge the Toxic Qi from the Yellow Court and lead the Toxic Qi down and out the body through the St-36 point on the leg and Lv-3 point on the foot.

c. To remove sluggish Qi stagnation, squeeze the patient's trapezius muscles, draining the pathogenic Qi out of the axillary fold of the patient's arm. The patient should breathe into the painful areas, and imagine any remaining Toxic Qi descending down the arm into the fingertips when exhaling. The doctor should squeeze the patient's arm as the patient exhales, to support the descending action of the Toxic Qi.

d. The patient should be given homework, depending on his or her constitution.

2. In treating chronic migraine headaches, combine Medical Qigong therapy with An Mo therapy, working from the branch to the root.
   a. Begin the treatment by pulling out the stagnant Qi trapped in the patient's head. This is done by first purging the patient's Wei Qi field, then entering the patient's Jade Pillow (at the base of the head) to purge and remove Toxic Qi and stagnation. Then emit and guide the Qi with your intention, to flow along the patient's falx cerebri. This forms a small Microcosmic Orbit (circling from the back of the head to the nose and back) and encourages the patient's stagnant Qi to move.
   b. Extend Qi into the patient's Bl-1 point (on the inside of the eye).
   c. Next, focus energy into the patient's Yin Tang point and begin circulating the Qi along the orbicularis oculi muscle of whichever eye is in pain (along the eyebrows to the ear). Work from the inside of the eye, out along the eyebrows (Figure 48.1).



Figure 48.1. For treating chronic migraine conditions (which dominate behind the left eye), begin by extending Qi into the patient's Bl-1 point and start to dredge the Toxic Qi from the patient's Yin Tang area, circulating the orbicularis oculi muscle of the eye in a clockwise direction.

   d. After several rotations, follow the sphenoid arch to the back of the ear at the TB-17 point (if the pain is bilateral, for men treat the left side first; for women treat the right side first).
   e. Next, beginning at the TB-21 point, outline the outside of the ear, then massage the lateral aspect of the ear's ridge (upper auricle) (Figure 48.2).
   f. Hold both of the patient's ears firmly and begin to apply slight pressure at a 45 degree angle towards the sides of the patient's head. This allows the Qi trapped within the patient's head to escape. Using intention, move the Qi from the Jade Pillow (along the tentorium cerebelli) into the patient's pituitary gland. Then divide the energy into two rivers of Qi that circulate through the middle of the cerebrum and end back at the Jade Pillow.



Figure 48.2. Outline the outside of the patient's ear, then massage the lateral aspect of the ear's ridge.

g. From the front of the head, at the edge of the hair, gather the Qi and lightly scratch the patient's head, as you use the Kneading Tiger technique. Visualize pulling the Toxic Qi down the front and sides of the patient's head (down the Gall Bladder Channels) to the base of his or her neck (Figure 48.3).

h. From the base of the neck, pull the Toxic Qi down and out of the arms.

i. The patient should be given seated Quiescent Qigong meditation homework, the length of meditation time will depend on his or her constitution.

Note: When treating migraine headaches, the head should always be treated first before treating the extremities.



Figure 48.3. Using the Kneading Tiger technique, visualize pulling the pathogenic Qi out of the patient's head, down the side of the neck and down along the sides of his or her arm.

SECTION XI

SPECIALIZED QI EMISSION THERAPY FOR PEDIATRICS, GERIATRICS, GYNECOLOGY, NEUROLOGY, PSYCHOLOGY, ONCOLOGY, AND SURGERY

INTRODUCTION

In this section we will explore disease treatment techniques and prescriptions unique to Medical Qigong doctors who specialize in Pediatrics, Geriatrics, Gynecology, Neurology and Oncology.

The last two chapters will address Medical Qigong therapy and the treatment of radiation, chemotherapy, and surgery.

CHAPTER 49

QI EMISSION THERAPY FOR PEDIATRICS

INTRODUCTION

Pediatrics is the branch of medicine which deals with the care of children and the treatment of childhood diseases.

From a traditional Chinese medical perspective, children are different than adults in several important ways. First, the Yin and Yang energy in children is fresh and pure, and their vitality usually flourishes. Second, although the internal organs of children have begun to take shape, the organs are still in the process of developing Qi; the organs are still maturing and are not yet fully developed. Because children are still growing organs and tissues, stimulating the channels and channel points has a different effect on their body than on an adult.

Specifically, the Lungs, Spleen, and Kidneys are especially delicate in children. The Lungs and Spleen are weak, and the Kidneys are particularly vulnerable. The Lungs control the Qi of the whole body. The Spleen is responsible for the transformation of food and the transportation of Gu Qi (food Qi). The Lungs and Spleen are the postnatal foundation of health. The Kidneys are in charge of the bones and Marrow and are the prenatal foundation of health. Children are still full of Prenatal Qi; they are just beginning to use their Lungs and Spleen for the function of acquiring Postnatal Qi. Consequently, their energetic system is vulnerable and unstable.

If children are born without congenital defects or weakness, are nursed properly, and avoid contracting major diseases, the internal organs should develop normally. However, because of inherent weakness or immaturity of the digestive system, almost all pediatric diseases of children under the age of six usually begin with some element of indigestion. A child's tiny digestive system makes him or her prone to the creation of Phlegm. Since the Spleen is the root of Phlegm production, and the Lungs are the storehouse of Phlegm, then a congenitally weak Spleen can lead to the creation of Turbid Dampness within the child's body. This Turbid Dampness can congeal into Phlegm and lodge within the child's Lungs. These symptoms can be observed in young children as runny noses, ear infections, phlegmy coughs, and other respiratory difficulties.

EARLY STAGES OF CHILD GROWTH AND DEVELOPMENT

In childhood, growth and development occur rapidly. In the ancient Chinese medical classic entitled *"Prescriptions Worth a Thousand Gold Ducats"* it states, "A newborn is feeble and tender; two months later, its pupils begin to become well developed, it can smile and distinguish parents from strangers; 150 days later, its sacral bones have been well developed, it can sit independently; 210 days later, its metacarpal bones have been well developed, it can crawl; 300 days later, its patellae have been well developed, it can stand alone; at one full year of life, its shank and occipital bones have been well developed, it can walk and speak."

In the natural course of childhood growth and development, there may be fever, irregular pulse signs, or perspiration due to the imbalances of Yin and Yang. The child usually recovers spontaneously within a day or two. Such episodes are called Changing and Steaming. Changing implies the transformation of the Five Yin Organs, with the accompanying variations of emotions, and the development of the child's intelligence. Steaming implies the vaporous exchanges within the six Yang organs induced by accumulated Heat. The ancient Chinese discovered that there is one Changing every 32 days, and one Steaming every 64 days. Thus, within 320 days, there are 10


Left Side of the Brain
Thyroid and Parathyroid Gland
Fourth Pull up
Right Lung
First Pull Up in the Middle
Right Side
Liver
Adrenal Gland
Right Kidney
Ovaries

Fig. 7.10 *Right Part in the Female*

2. Liver

Close the left nostril, inhale and pull up. Use the right eye, ear and nostril; draw the energy up from the right testicle (men only), through the right ovary (women only), the right kidney and up to the liver. Exhale, relax and let the pearl return to the perineum. Practice nine times. Rest, and feel the flow of energy through the Right Thrusting Channel to the liver, under the diaphragm.

a. Combine all Three Routes

Continue to practice moving the pearl up and down through a combination of all three Thrusting Channels to under the diaphragm in the following nine steps until the energy is flowing easily: (1) Left Channel; (2) Middle Channel; (3) Right Channel; (4) Middle; (5) Left; (6) Middle; (7) Right; (8) Middle; and (9) Left. It helps to quicken the speed with each attempt.

Note: Stay relaxed during this exercise, and avoid using force. Once you are accustomed to thrusting the pearl and feel that the channels are clear, there is no need to close the nostrils for the left and right channels. Just simply pull up the perineum and anus, and use the power of the mind.

Changings, and within 576 days, there are 9 Steamings. Every Changing or Steaming is an ordinary event in the course of growth and development, and should not be mistaken for a condition of childhood disease. However, if children are not cared for properly during Changing and Steaming, they are more apt to fall ill.

PATHOLOGY

In *"Detailed Analysis of Epidemic Febrile Diseases,"* Dr. Wu Tang stated that children's diseases are apt to change because the internal organs are frail and their defense mechanisms are incomplete; children contract infections easily because the skin and muscles are still tender, and the vitality is timid and weak. Propensity to illness, inclination to Excess and Deficiency, and being prone to suffer from Heat and Cold syndromes are common features of pediatric pathology. Since children are full of pure Yang, the course of disease is changeable and unpredictable. Nevertheless, recovery of health is generally easy.

DEFICIENT LUNGS

Children are apt to suffer from internal organ disorders, especially of the Lungs, manifested by symptoms of cough, dyspnea, retention of Phlegm and Dampness in the Lungs, seasonal febrile diseases, allergies, asthma, and other Lung disorders.

The Lung is a delicate organ in charge of the skin and hair. Therefore, particularly in children, junctures between the skin and muscles are not compact enough to resist the invasion of Exogenous Cold, Heat, Dampness, Wind, and other pathogens. Seasonal pathogens may attack the Lungs through these slackened junctures and through the nose, thereby interfering with the descending and dispersing functions of the Lungs. This results in the accumulation of Heat, fullness in the chest, productive cough, or dyspnea.

DEFICIENT SPLEEN

Since the Spleen is not yet matured and thus usually Deficient, it may be harmed or damaged due to improper diet, irregularity of meals, or imbalances caused by excessively Hot or Cold diets. Consequently, Clear Yang fails to rise, Turbid Yin fails to descend, and Stomach Qi becomes disharmonious. Therefore, children frequently suffer from abdominal masses, abdominal pain and distension (stomachache), belching, hiccups, vomiting and diarrhea, infantile malnutrition, and other digestive disorders. These conditions often lead to children becoming hypersensitive to the foods they consume.

According to Five Elements theory, the Spleen (Earth) generates the Lungs (Metal) and the Lungs (Metal) generate the Kidneys (Water). The elements work in coordination and influence each other. In children suffering from Spleen Deficiency, there will also be a Deficiency of Lung Qi; in children suffering from Lung Deficiency, there will also be a Kidney Deficiency.

DEFICIENT KIDNEYS

Kidney problems can manifest in two different ways: Kidney Jing Deficiency, which can cause retardation, or Congenital Qi Deficiency (i.e., Deficiency in the Sea of Marrow), which can lead to Down's Syndrome, Attention Deficit Disorder (ADD) and learning disabilities. Since the Kidneys control the lower orifices, Deficient Kidney Qi can also lead to chronic bed wetting.

If the child was improperly nursed when they were young, the Deficient Kidney Yin not only fails to nourish the bones and Marrow, but also fails to nourish tendons. During depletion of Liver and Kidney Yin, there can be atrophy, weakness of tendons, five types of developmental retardation, as well as five kinds of flaccidity.

LIVER YANG EXCESS

By contrast, Liver Yang is usually Excessive, and Liver Wind may be brought on by Heat or Fire, resulting in infantile convulsions, twisting, and even opisthotonos.

HEART (SHEN) IMBALANCE

The Heart is responsible for the child's mental stability. The Heart Fire and the Kidney Water must constantly be balanced to stabilize the child's Wu Jing Shen. An imbalance of the Heart can lead to Shen disturbances which can result in mental instability or disability.

According to the active energetic balance of the child's Wu Jing Shen, the Hun tend to naturally be overactive, and the Shen of the Heart is generally unstable. The reason for this instability is because the Hun are very active within a child. The Hun are responsible for creativity, enthusiasm, dreaming, going in and out of the body, and seeing into the Spirit world. The Shen, which is responsible for the child's discriminating mind, respect and conveying the appropriate behavior, is not fully developed. Consequently, young children tend to often be wild, hard to control, and get easily bored.

In treating a child's overactive Hun and unstable Shen, the Qigong doctor harmonizes the child's Heart Fire and Kidney Water energy, and opens the Heart's orifices (using Qi massage on the child's eyes, ears, nose, mouth and all upper sensory orifices) to stabilize the Wu Jing Shen.

HOT AND COLD EXOGENOUS FACTORS

Susceptibility to Exogenous Cold and Heat reflects the characteristics of puerile Yin and Yang. When children are invaded by Exogenous Evils, for example, there will be Excess Heat syndromes; when the child's healthy energies are depleted, there will be Deficiency Cold syndromes.

Although various defects and Deficiencies do exist in children, their Yang, Liver, and Heart are in a hyperfunctional state. Therefore, children are full of vitality and their anti-pathogenic responses are sensitive and immediate. The causes of childhood diseases are usually comparatively simple, relative to adults, and their convalescence is easier and quicker provided they receive appropriate treatment and care.

THERAPY

Because the internal organs of children are still forming and are, therefore, still frail and tender, children are much more sensitive than adults, and cannot stand strong energetic stimulation. This is why the primary modality for treating young children is gentle pediatric Tui Na, which is usually on the child's hands, feet or abdomen, or Qigong massage (lightly touching the child's body). Acupuncture is used only infrequently, and when it is, the needles are usually not retained for long - the points are quickly and lightly stimulated and then the needles are removed. Similarly, when using Medical Qigong emission therapy, a milder stimulation is applied than would be used for adults when purging, tonifying, and regulating.

Medical Qigong is useful for treating pediatric neurological disorders, and particularly for such conditions as epilepsy, hyperactivity, attention deficit disorder (ADD), and mental retardation. Effective points for tonification include Tianzhu (Bl-10), Sishencong (four extra points, located around the Baihui area at the top of the head), Baihui (GV-20), Yamen (GV-15) and Fengfu (GV-16).

When children under the age of six practice self-regulation Medical Qigong exercises (such as Qigong to increase intelligence), they frequently develop special abilities. These abilities include ESP (e.g., telepathy and telekinesis), and special Qigong healing abilities.

ENERGETIC MOVEMENT AND FLOW

The child's Microcosmic Orbit naturally flows in the direction of the Water cycle, moving up the front (CV) and down the back (GV) in order to facilitate the child's spiritual, intuitive, and psychic perceptions. This energetic movement continues in this direction until the child reaches puberty, at which time the energy reverses its direction and flows up the back (GV) and down the front (CV), in the direction of the Fire cycle. This energetic switch in direction facilitates the child's cognitive development and the ability to control emotions and impulses. The time of the Microcosmic Orbit's energetic reversal varies depending on the child's physical constitution, state of health, and his or her environment.

MEDICAL QIGONG EXERCISE PRESCRIPTIONS FOR CHILDREN

The following Medical Qigong exercise is considered a basic training method for children. This exercise is specifically developed for children of all ages and physical conditions, and is used to improve a child's physical and mental health, as well as aid in curing some common childhood diseases. This exercise can also help to cure food allergies, loss of appetite, malnourishment, a weak immune system, neurasthenia, insomnia, dreaminess, and disturbances of the Spleen and Stomach. It is believed that this exercise also helps moderate a child's stubbornness and impatience.

IMPROVING INTELLECTUAL FACILITIES QIGONG (DA-ZHI-GONG)

This particular Medical Qigong exercise is excellent for children who range from 3 to 12 years old. The time and frequency of the following Qigong exercise is not fixed. It is important, however, that the child be consistent with the practice, and that the body and mind remain relaxed while training.

It is important that the child practice the entire Qigong sequence in its proper order. The child is not allowed to practice only a part of the exercise.

Prohibited from this particular exercise are children who have weak constitutions (i.e., have difficulty in standing up) or suffer from serious diseases.

1. Begin by having the child assume a standing Wuji posture. Have him or her relax the body, with the eyes either open or closed. The child then raises both hands in front of the Upper Dantian. Boys will place the left hand facing the forehead, about three inches from the Yintang point. Girls will place the right hand facing the forehead, about three inches from the Yintang point. At the same time the opposite hand should be level with the other palm and should be facing outwards (Figure 49.1).
2. Both hands begin to make a clockwise circle rotation (from the child's point of view). The child keeps the Yin Tang point as the center of the circle, for 18 breaths. Next, the child moves both hands to the front of the right eye and continues the same clockwise movement while keeping the right eye at the center of the circle. Rotate for 18 breaths. Then, the child moves both hands to the front of the left eye and continue the clockwise movement for 18 breaths. Finally, the child returns to the front of the forehead and continues the rotation, keeping the Yintang point as the center for 18 breaths, then



Figure 49.1. Improving Intellectual Facilities (1)



Figure 49.2. Improving Intellectual Facilities (2)



Figure 49.3. Improving Intellectual Facilities (3)



Figure 49.4. Improving Intellectual Facilities (4)

ends the meditation (Figure 49.2).

3. The child places both hands in front of the ears, with the center of the palms facing the external opening of the ear canals; breathing naturally, the child moves both hands forward and backwards while emitting Qi into the ears. Make sure the child does not concentrate on any specific thing, but simply relaxes (Figure 49.3).
4. Next, the middle fingers softly touch the navel with the left hand, and the right hand softly touches the Mingmen. Have the child imagine that there is a big red ball of fire in his or her abdomen (where the child's two middle fingers are pointing). The child's fingers should remain is this position until warmth is felt in the abdomen. If the heat becomes too hot, have the child exhale the sound "Ha" three times to release the Excess Heat (Figure 49.4).
5. To end the exercise, have the child cover his or her tailbone with both hands and jump up and down gently for several minutes. Do not allow the child to become tired from jumping. Again, make sure that the child does not concentrate on any specific thing (Figure 49.5).



Figure 49.5. Improving Intellectual Facilities (5)



Figure 49.6. Gathering Wisdom Qigong (1)



Figure 49.7. Gathering Wisdom Qigong (2)

MEDICAL QIGONG FOR GAINING WISDOM QIGONG (TONG-LING-GONG)

This particular Medical Qigong exercise is excellent for children who range from 3 to 16 years of age. The time and frequency of this particular Qigong exercise is not fixed, and may be decided by the child. Also, there are no contraindications for this particular Qigong exercise.

1. The child begins by standing with his or her feet flat, shoulders width apart. The child should place one hand on the Lower Dantian (below the navel) and the other hand at the back, below the Mingmen (opposite the Lower Dantian). Have the child close his or her eyes and relax the body and mind for about three minutes. The child is to imagine that the upper part of the body (above the waist) is extended into the blue sky above, and that below it (around waist level) are clouds (Figure 49.6).
2. Next, the child imagines that he or she has changed into an Immortal (a Super-Hero). Encourage the child's imagination to flow freely with this concept, allowing the child to move about, gently shaking the knees (Figure 49.7). After several minutes end the meditation.

CHAPTER 50
QI EMISSION THERAPY FOR GERIATRICS

Geriatrics is a branch of medicine which deals with the problems of the aging. Geriatric specialists addresses the physiological, pathological, psychological, economic, and sociological problems of the elderly. The importance of geriatrics is emphasized by the fact that the expected life-span of the average person is increasing.

Diseases of the internal organs can spread throughout the body via the channels and collaterals, and vice versa, as channel diseases can be transmitted to the internal organs. If Qi and Blood lose their harmony due to old age, and the patient's internal organs, channels, and collaterals become obstructed, then Phlegm and Stasis will develop internally. The accumulation of Phlegm, Qi and Blood stasis may lead to a chain reaction of pathological transformations, such as Hot, Cold, Excess or Deficiency Syndromes in the patient's internal organs. The following are examples of some of the pathological transformations.

1. If the patient's Qi and Blood in the Liver lose their harmony, the patient may experience fatigue and depression with dry eyes or diminished vision. The patient may also experience numbness in the extremities and muscle spasms due to a weakening of the sinews and blood vessels.
2. If the patient's Qi and Blood in the Heart lose their harmony, the patient may experience poor memory, insomnia, heart palpitations, and shortness of breath (which may be aggravated by movement).
3. If the patient's Qi and Blood in the Spleen lose their harmony, the patient may experience fatigue and general weakness in all four limbs. The patient may also experience loose or bloody stools, and there will be abdominal distention after food consumption.
4. If the patient's Qi and Blood in the Lungs lose their harmony, the patient may experience coughing with Phlegm and panting, as well as spontaneous sweating.
5. If the patient's Qi and Blood in the Kidneys lose their harmony, the patient may experience poor memory, anxiety, tinnitus or deafness, as well as a sore or weak lower back, knees, and teeth.

The Chinese have a saying, "When the Heaven (Heart Qi) connects with the Earth (Kidney Qi), all seven emotions are kept in moderation." When Qi becomes scattered the Heart Fire and the Kidney Water cannot converge. This results in an unbalanced and unstable energy flow.

The Kidneys are extremely important for health maintenance and healing in all patients, and especially in senior citizens. As one gets older, the Kidneys, lower back, and legs are the first things to be affected.

It is important to stabilize the Heart because the Heart is responsible for mental and emotional orientation. Traditional Chinese Medicine holds that, "when the Heart is moved, all the other organs will be shaken."

In teaching Medical Qigong to senior citizens, first quiet the Heart, so that the other organs can begin to relax. When the mind becomes disturbed, the body becomes disturbed. To affect one is to affect the other.

The eyes are considered the seedlings of the Heart as they receive information, gathering it and feeding it to the brain. It is important for the Heart's Qi to descend into the Lower Dantian to calm the mind. When the patient is in a hurry, the Heart is in a hurry, thus inducing the Qi to rise to the head. This results in nervous tension and anxiety. It is only through rest and quiet training that the mind and the Heart can begin to settle.

One method of quieting the mind is through prayer and meditation. This is considered "active rest." Sleep is considered "passive rest." When focusing inward and not using the eyes to see or the ears to hear, the Qi begins to converge in the middle of the body and the energy is drawn back into the organs, settling down into the Lower Dantian. This convergence of Qi nourishes and cultivates the natural energetic structure of the internal organs. Senior citizens are encouraged to sit for longer periods of energy cultivation. If they practice Taijiquan they are to avoid low postures and big motions. The arm movements should be kept small, soft, and slow.

TREATING THE PATIENT'S EMOTIONAL STABILITY

When treating the elderly, the Qigong doctor bases the regulation therapy prescriptions on two major priorities. The first is to achieve emotional stability and the second is to improve the Qi and Blood circulation.

The first priority in working with healing prescriptions is to focus on the patient's psychological profile. When teaching Medical Qigong to senior citizens, first teach them how to quiet the Heart. Once the Heart is calm the other internal organs begin to relax. Always keep in mind that when the mind becomes disturbed, the body becomes disturbed. To affect one is to affect the other.

Depression and sadness can have a profound effect on the patient's healing ability. Medical Qigong regulation can be a strong aid in releasing an elderly patient from a chronic, detrimental attitude that complicates the healing cycle. Take for example the three stages of emotional transition the patient endures before his or her Spirit closes (see Chapter 18).

If anger and grief are not allowed to be expressed by the patient (which is the first stage of energetic expression and release of emotional pain), then anger transforms into depression, and grief transforms into despair. This is the second stage of the energetic/emotional transformation due to emotional pain. If the patient's depression and despair are not alleviated, then indifference, the final stage of energetic/emotional transformation, is developed. The patient becomes withdrawn, apathetic and either antisocial, or obsessive/compulsive in his or her thinking and behavior.

When the patient's Spirit closes, they tend to be extremely difficult to work with, and can easily sabotage their own healing potential. Though the use of Soul Retrieval meditations (see Chapter 19), Medical Qigong prescriptions can be used to reconnect the patient with their disassociated emotions. This allows the patient the ability to feel and regain contact with his or her true feelings.

Pleasant emotions bring about a calm and relaxing physiology, while strong, chronic negative emotions cause Qi and Blood stagnation, as well as Excess conditions within the patient's body, effecting the quality of the body's life force energy.

ENERGIZING THE PATIENT'S QI CIRCULATION

The second priority is to get the patient to move and circulate the Qi and Blood deep and superficially within his or her body. Static Blood is considered the primary mechanism of senility. All growth, development, decline, and debility of the human body, is related to the condition of the patient's Qi and Blood.

Pathophysiologically, both Qi and Blood affect each other; if one becomes diseased, the other is affected. Due to the Kidney's influence, as seniors get older, their hearing, hair, memory, lower back, and legs become adversely affected. Traditionally, all senility-combating formulas of Medical Qigong stress treating the patient's Spleen and Kidney Deficiency by supplementing the patient's Yin and/or Yang. Then, by applying the balancing methods of activating the patient's Blood and rectifying the Qi, the doctor can also combat the patient's senility.

Senility is also frequently caused by dehydration and malnutrition. Both conditions are frequently overlooked by Western medicine. The dehydration is usually due to a breakdown of the body's thirst signal. The patient does not feel thirsty, and thus forgets to drink. Malnutrition may be caused by a lack of enzymes that aid in absorbing nutrition from foods. Overmedication likewise can cause senility. These issues should always be addressed when treating the elderly, along with Medical Qigong exercises and meditations.

One example of a Medical Qigong exercise for aiding Qi and Blood circulation for geriatric patients is the Microcosmic Orbit (Fire Cycle) which can be practiced in a sitting position.

The elderly are more subject to musculoskeletal disorders and visceral diseases, especially in the Kidneys and Liver. As the Kidney Yang rises, it begins to restrict the heat in the upper portion of the body, thereby affecting the Heart. Also, as the patient gets older the Lungs cannot sustain liquid retention; this affects the Wei Qi, and results in a thinner layer of skin covering the body.

The Qigong movements prescribed for the elderly should be kept slow and smooth. Qi regulation can be cultivated safely by focusing the patient's intention on the center of the palms while keeping the mind's intention moving downward. The patient must not exert strain when using the muscles. When the patient turns his or her body, make sure that the center of each palm (Pc-8) faces the other. Slow and even breathing will calm the patient's emotions and sedate the mind.

It is important to begin Medical Qigong regulation training for senior citizens with natural breathing. Natural breathing allows their respiration to become soft, natural, gentle and quiet. The focus of the mind should be on relaxation. In dealing with senior citizens, if the focus of their mind's intention is allowed to become too concentrated, it can cause the Qi in their body to constrict and develop into Qi or Blood stagnation. Redirect their focus of intention on their breathing by practicing the Small Heavenly Cycle meditation. The Small Heavenly Cycle meditation is used to regulate the body's Yin and Yang energy and to strengthen the patient's mind and spirit. The Large Heavenly Cycle meditation can be prescribed to increase the patient's Qi and Blood circulation, to rejuvenate the body and the sense organs, to clear the complexion, and to improve mobility.

TAPPING THE KNEES TO PREVENT SENILITY

One exercise prescription that the doctor can use to assist the patient in combating senility is to have the patient lightly tap above, below, and around his or her knees. This exercise stimulates the Kidneys' energy and can also be used as an important adjunct to maintaining health for senior citizens, especially when combined with the foot tapping (Kd-1) Kidney Tonification exercise (see Chapter 39). Combined, both of these exercises can help to strengthen the patient's Kidneys, lower back, and legs. When combining both exercise prescriptions, the Knee Tapping exercise should follow after the Kidney Tonification exercises.

To begin the Knee Tapping exercise, have the patient sit in a chair, with both knees lower then the thighs. Encourage the patient to direct the focus of his or her attention in and around the knee area. As the patient taps or softly slaps the tissue surrounding the knees, he or she should imagine the energy and vibration flowing into the Lower Dantian. After several minutes (about 36 breaths) the patient can stop.

CULTIVATING THE PATIENT'S YUAN QI BY ABSORBING ENERGY FROM NATURE

Another priority of focus for older patients is the gathering, storing and cultivation of his or her Yuan Qi. In China, in order to tonify the Yuan Qi, elderly patients practice their Qi Tonification and Regulation Exercises facing a cypress tree daily (a cypress tree is considered very powerful and full of energy). If a cypress tree is not available, then the patient can use a pine or oak tree. This exercise prescription is considered a slow and gentle Dynamic cultivation. Any Dynamic exercise for senior citizens should always be practiced slowly, and gently, in order to replenish the Yuan Qi during the Static Qigong posture (in this case, standing).

The flexion and extension of the muscles relates to the interaction of Yin and Yang within the body's energetic tissues and muscles. This flexion and extension of the muscles becomes the foundation of energy balance. Relaxation of the body results in soft, gentle movement, peacefulness and tranquillity. Muscular rigidity, on the other hand, results in hardness, restlessness and disease.

In order to practice Medical Qigong exercises, senior citizens are encouraged to keep their body's energy connected with the energy of the Earth. This connection is obtained via their energetic attachment through the bottom of their feet and the center of their palms. If the patients are confined to wheelchairs, or are bedridden, they can still focus the mind's intention on the Lower Dantian, and then extend their energy deep into the Earth.

As with all Medical Qigong prescriptions, the patients must first purge and cleanse their body before gathering, collecting, tonifying and regulating the body's energy. To purge the body of Toxic Qi, the patients imagine divine healing energy pouring down from the Heavens, filling the entire body, as they inhale. This vibrant healing energy is absorbed into their tissues and the Toxic Qi stored within the patient's body is dispersed into the Earth.

As the patients exhale, they imagine the Toxic Qi melting out their tissues and flowing downward, deep into the ground. The patients perform this purging and dispersing sequence for several breaths until they feel cleansed. Next, the patients begin to fill and regulate their body.

To fill and regulate the body, the patients imagine circulating the energy downward, deep into the Earth, and into the root system of a tree.

Next, the patients imagine the Earth's energy ascending up through the top of the tree, blending with the energy of Heaven, and then descending through their head, filling their entire body from the feet upward like water being poured into a glass and filling it up (Figure 50.1).

The inhalation and exhalation should follow the Natural Abdominal Breathing method, and the mind's intention should be focused on filling, gathering and circulating the universal and environmental Qi.



Figure 50.1. Extend Qi and Intention deep into the root system of the tree and absorb its natural energy through the Baihui point at the top of the head.

FURTHER OBSERVATIONS AND INSIGHTS ON GERIATRIC PATIENTS

According to Mark Johnson (an expert who has been treating "Seniors" with Medical Qigong Therapy and Taijiquan since 1987), any encouragement to undertake new experiences is very cathartic for older patients. Getting involved in anything creative seems to prolong the quality of their life.

Understanding the physical and emotional transitions that geriatric patients undergo in their every day life helps the Qigong doctor establish a better awareness of the patient's energetic dynamics. These physical and emotional transitions can best be understood when realizing the internal and external conflicts senior patients must constantly address.

COMPANIONSHIP

Many people tend to lose meaning in their life when they retire, lose a spouse, witness the death of countless friends, or when their children move away. Patients who lose their life purpose (or their meaning of life) usually do not live long. Elderly patients, who have lost their friends, usually have an extremely strong emotional attachment to any pet they may own. If the pet dies, this is usually as devastating as the loss of a close family member.

According to clinical observation, most older patients who become involved in spirituality, social service or voluntary work tend to be the most fulfilled and therefore most healthy. Humor and laughter as a means of internal emotional medicine for older patients cannot be overemphasized. Socializing with an understanding yet active support group also tends to bring healing to their heart.

In addressing the issue of being lonely, it has been found that the healing quality of having a pet to love can be very helpful for seniors who have become solitary or isolated.

OVERMEDICATING

Too many older patients are overly medicated. Taking up to ten pills a day is not unusual for many seniors. In a book initiated by Ralph Nader, titled "Worst Pills, Best Pills" the author emphasizes the fact that if an older person is taking over three different drugs, they are taking too many and should consult their doctor with the expressed purpose of cutting down to a maximum of only three types of medication.

The drugs given to seniors are usually tested on 30 year old individuals who are generally much stronger than most 70 year olds. Therefore half dosages are usually considered safer. In addition, there is a minimum of thirty-three drugs on the market today that can give the symptoms of Parkinson's disease. Several healers have gotten their patients off Parkinson's medication after demonstrating the fact that one of their other medications initiated the patient's symptoms.

SEDENTARY LIFE-STYLE

Too many older patients are sedentary, especially men. It is generally agreed that people living today move only 35% as much as people living 100 years ago. This has got to have a major impact on one's health, especially on older people whose circulation is not what it once was. Our bodies are designed to move; to become sedentary violates one of our basic needs. The studies conducted at Emory College confirm that the safest and most beneficial exercises for seniors is Medical Qigong, Taijiquan, walking, mild aerobics and light weight training. Seniors are encouraged to stay away from running.

IMPROPER DIET

Because of the patient's age and changing metabolic needs, diet is as equally important for seniors as exercise. Proper nutrition can be used to augment the benefits from the patient's prescriptions, as well as to increase the patient's healing potential. The diet in senior housing communities is usually atrocious. Sugar, canned vegetables and too many heavy meats are the norm. When prescribing Medical Qigong exercises for seniors, the Qigong doctor must also take into consideration the patient's diet and fluid intake, making sure that it is not sabotaging the healing effect of the Qigong prescriptions.

SLEEP DEPRIVATION

As patients gets older, their Kidney Jing becomes weak, their hair begins to turn grey, the hearing and sight becomes affected, the bone structure, mental comprehension and sleeping patterns also undergo changes. These physical transitions can and do affect the patient's emotional outlook on life. This however, is all part of the natural course of ageing.

Due to the weakening of the patient's Kidneys, sleep deprivation is more common in seniors than most people realized. More training in dealing with insomnia and changing sleeping patterns is necessary for Western doctors, as the serious impact on health by sleep deprivation is poorly understood in Western society.

Sleep is needed to invigorate and stabilize the patient's Wu Jing Shen (Five Essence Spirits). Without sleep, the patient's Hun (Spirit Soul), Shen (Spirit), Yi (Intention), Zhi (Willpower) become depleted and they lose control of their Po (Corporeal Soul). This affects the patient's intuitive perceptions, mental comprehension, drive and willpower, and can result in dementia.

b. Clearing the Routes with Saliva
   End by preparing the saliva. First sweep your tongue across the outer surface of your upper teeth, starting on the left side at your wisdom tooth, with the tip of the tongue going along the gums. When you arrive at your upper right wisdom tooth, move the tip of your tongue down to the lower right wisdom tooth and move along the front of the lower teeth. When you arrive at the lower left wisdom tooth, start again at the upper wisdom tooth. Circle around in this manner a few times. Then similarly sweep along the inner surface of the upper and lower teeth and gums. Your mouth will begin to fill with saliva.

Gather the saliva into a ball using your tongue. Press your tongue to the roof of your mouth and swallow the saliva quickly with a gulping action. Feel the saliva burn out the impurities in the Channels and lubricate them.

Practice this stage for about one or two weeks until you can control the energy very well, then continue to the next stage. Each time you finish, move the energy in the Microcosmic Orbit and collect the energy in the cauldron. When you are ready to continue to the next stage, practice Spinal Cord Breathing at this point in your preparation.


Thoracic Vertebrae
Aorta
Esophagus
Ribs
Pleural Cavity
Right Lung
Left Lung
Pleural Cavity
Lungs
Serratus Anterior Muscle
Vena Cava
Sternum
Thymus Gland
Pericardial Cavity

Fig. 7.11 *Cross Section of the Thorax*

UNDERSTANDING DEATH AND DYING

Classes and workshops on death and dying should be more available, and both patients as well as doctors should be encouraged to attend them. The doctor can benefit greatly by learning specific meditations being taught to facilitate this major transition, and also how to relate better to their elderly and young dying patients. The patients can benefit greatly by increasing their awareness and understanding of this process, as well as learning the numerous meditations that help resolve unprocessed emotions. Furthermore, patients can meet others with whom they can share their fears and hopes openly.

Too often the elderly do not wish to share these feelings, even with those closest to them for fear of burdening their family and friends. Patients may also be very reluctant to disclose their personal concerns for fear of being alienated, even with Qigong doctors, especially if the doctor's fear of death becomes evident through too much encouragement to get well and not lose hope.

CHAPTER 51
QI EMISSION THERAPY FOR GYNECOLOGY

INTRODUCTION

Gynecology is the study of diseases of the female reproductive organs. The earliest records of Chinese gynecological medical writings date as far back as the Shang Dynasty (1500–1000 BC). From a Traditional Chinese Medical perspective, a woman's physiology is characterized and diagnosed in accordance with her menstrual flow and vaginal discharge (also included are the energetic formations and transitions during pregnancy and childbirth). A woman's physiology is dominated by, and rooted in Blood. Her Lower Burner houses the uterus, which stores Blood, and corresponds to her Lower Dantian.

MENSTRUAL FLOW

Normally, a woman will follow the cycles of the moon and will menstruate every 28 days. Her cycles can be categorized into either new moon or full moon periods. The length of days between menstruation and the time of duration vary; four days of flow is considered average.

A woman's menstrual cycle can be categorized into four distinct time periods: Irregular Menstruation, Early Menstruation, Late Menstruation, and Prolonged Menstruation.

1. An irregular menstrual cycle is never consistent: sometimes early, sometimes late. The cause of an irregular menstrual cycle can be due to either a stagnation of Liver Qi (from suppressed anger or emotional shock), Liver Qi invading the Spleen (emotions affecting the Liver invades the Spleen), or a constitutional weakness of the Kidneys.
2. The cause of an early menstrual cycle can be due to either Heat in the patient's Blood or Qi Deficiency.
3. The cause of a late menstrual cycle can be due to either Cold stagnation of Blood, Blood Deficiency, stagnation of Qi (caused from emotions), or Deficiency of Qi.
4. The cause of a prolonged menstrual cycle can be due to either Qi Deficiency or Heat in the Blood (this is because Blood that is Hot wanders out of the vessels).

QI AND BLOOD REGULATION

Due to periodical menstruation and the complex changes that occur in the uterus and the organs (ovaries, cervix, and vagina) associated with reproduction, women tend to become especially vulnerable to Blood damage. The formation, circulation, and control of Blood depends upon the transformation, regulation, and production of the woman's Qi. This interdependence of Qi and Blood is regulated through the harmony of the body's Five Yin Organs. For example:

1. The Liver stores the Blood.
2. The Heart controls the Blood.
3. The Spleen contains or keeps the Blood in its vessels. In addition, the body's Spleen and Stomach are also known as the source of reproduction and transformation of Qi and Blood.
4. The Lungs store the Qi, which commands or moves the Blood.
5. The Kidneys store the Jing, which transforms or creates the Blood.

The woman's Sea of Blood can only flow freely when the Qi and Blood of the Five Yin Organs are in harmony. When a woman's Sea of Blood is full and exuberant, then her menstruation will be healthy and normal.

Regarding the Eight Extraordinary Vessels, a woman's Governing, Conception and Thrusting Vessels all originate within her uterus. The Governing Vessel governs the body's Sea of Yang and represents the Yang aspect of a woman's reproductive functions. The Conception Vessel governs the body's Sea of Yin and provides the Yin substances for all physiological and hormonal transitions, including puberty, conception, pregnancy, childbirth, and menopause. The Thrusting Vessels function as the Sea of the Twelve Primary Channels, and influence the supply and proper movement of Blood in the uterus, and control all aspects of menstruation.

The Belt Vessel encircles the Governing, Conception, and Thrusting Vessels, and governs, guides, and supports the energetic flow of Qi and Jing to the uterus.

Regarding the Twelve Primary Channels, their internal network is distributed throughout the uterus and is connected to both the Heart and Kidneys. In addition, the energetic connection with the uterus is further strengthened by the convergence of the Liver, Spleen, and Kidney Channels, along with the Conception Vessel, through the connecting vessels in the genitalia.

ETIOLOGY AND PATHOLOGY OF GYNECOLOGICAL DISEASES

In order for the Qigong doctor to make a correct diagnosis pertaining to a woman's menstrual flow and reproductive organ function, attention must be placed on identifying the primary etiology of the imbalance in the patient's Qi and Blood.

The Governing, Conception, Thrusting, and Belt Vessels are the most important vessels in terms of diagnosing gynecological pathophysiology. Consequently, any damage or disease of the these vessels are believed to be the main causes of gynecological disorders.

Either a direct or indirect attack to the Conception and Thrusting Vessels can cause disharmony of Qi and Blood, resulting in a loss of internal organ regulation.

DIRECT CAUSE

A direct cause of damage to the Conception and Thrusting Vessels can result from either Evil Toxin infections or from hygienically unclean sexual encounters. If the Conception and Thrusting Vessels become damaged, the result can manifest in symptoms such as profuse abnormal vaginal discharge or uterine bleeding.

INDIRECT CAUSE

Indirect causes of damage to the Conception and Thrusting Vessels can result from internal damage due to: The Seven Emotional Factors, Invasion of the Six Exogenous Factors, and An Inconsistent and Undisciplined Diet.

1. The Seven Emotional Factors tend to be the major factors in determining the root causes in most gynecological diseases.

   The suppression of anger, rage, resentment, and jealousy often results in Liver Qi depression, which eventually leads to Blood stagnation. This can result in such symptoms as delayed, painful, or blocked menstruation. If a hyperactive Liver Yang condition occurs, the patient can develop symptoms as serious as pre-eclampsia or eclampsia (coma and convulsive seizures that can occur between the 20th week of pregnancy and first week postpartum; symptoms include edema of the legs and feet, puffiness of the face, hypertension, severe headaches, dizziness, epigastric pain, nausea, sudden convulsive seizures and coma). The Liver's Blood Heat can lead to profuse uterine bleeding, leaking of Blood, hemoptysis (throwing up Blood) or epistaxis (bleeding of the nose).

   The suppression of worry and regret, or obsessiveness, can harm the Heart and Spleen. This can lead to amenorrhea (the absence or suppression of menstruation) or a fetal leakage (after conception, if a small amount of bloody fluid discharges from a woman's vagina, it is known as Tai Lou or fetal leakage).

   The suppression of fright, fear, loneliness, and insecurity can damage the Kidneys and lead to miscarriages.

2. Invasion of the Six Exogenous Factors, in particular, Cold, Heat, and Dampness, are the primary causes for gynecological diseases.

   If the Blood is invaded by Cold, it congeals, causing delayed menstruation, painful menstruation, or severe contractions and thick conglomerations of Blood.

   If the Blood is invaded by Heat, it moves, causing the Blood to flow recklessly. This reckless movement of Blood leads to early menstruation, excessive menstruation, and uterine bleeding.

If the Blood is invaded by Dampness (Damp Evils invading the Spleen), it can lead to abnormal vaginal discharge, uterine bleeding, and irregular menstruation.

3. An Inconsistent and Undisciplined Diet can lead to a Spleen and Stomach disharmony. If the Spleen and Stomach's ability to transform and transport food becomes hindered or weakened, the Sea of Blood becomes Empty. This can lead to delayed menstruation or scanty menstruation.

   If the Spleen loses its ability to restrain and contain the Blood, both Blood and Qi leak out of the vessels. This leaking of Qi and Blood can lead to excessive menstruation and uterine bleeding.

   If the Spleen's Yang does not perform its transporting function, Dampness and Turbidity will descend, resulting in abnormal vaginal discharge.

VAGINAL DISCHARGE

In Traditional Chinese Medicine, abnormal vaginal discharge (Dai Xia) is considered a disease of the Belt Vessel. If the Belt Vessel loses its restraint on the other vessels, then abnormal vaginal discharge is produced. This is usually caused by a Spleen Deficiency, Dampness, and descending Turbid Qi.

CONSISTENCY

The consistency of the patient's vaginal discharge can be divided into three categories: Turbid, Watery, and Clotting (thick and pasty).

1. A Turbid discharge refers to Blood Heat and an infection in the uterus. It also refers to signs of Cold stagnation.
2. A Watery discharge is considered a Cold Damp and / or Deficient condition.
3. Clots (thick and pasty) are considered a Damp Heat and Excess condition.

SMELL

The smell of the patient's vaginal discharge can be divided into conditions of either Damp Heat, indicated by a leathery smell, or Cold Dampness, indicated by a fishy smell. Also, if the patient's menstrual Blood has a strong, foul smell, it usually indicates a Heat condition.

COLOR

Vaginal discharge color is divided into five colors (Wu Se Dai): white, yellow, red, green-blue, and dark brown or black. The pathology of the discharge color is mostly caused from a Deficient Conception Vessel, loss of restraint from the Belt Vessel, Spleen Dampness, or Evil Wind invading the uterine vessels. These conditions create Heat, which descends into the uterine area causing disease.

Only profuse vaginal discharge, which bears an unnatural color and gives off a malignant odor, is considered pathological. The five colors of vaginal discharge are as follows.

1. White vaginal discharge (Bai Dai) is the most commonly seen type of vaginal discharge. It is a Cold condition caused by a Spleen or Kidney Yang Deficiency, or from Exterior Cold Dampness. It manifests as a white, sticky, slimy fluid discharge from inside the patient's vagina with a fishy smell. Symptoms include sore lower back, weakness, and irregular menstruation.
2. Red vaginal discharge (Chi Dai) is caused from Damp Heat in the Lower Burner or Fire Blazing through the Heart and Liver channels. The latter eventually causes a Yin Blood Deficiency. Red vaginal discharge manifests as thick and sticky, white with red mixed together, pale red, or red vaginal discharge with a foul odor. Symptoms include thirst, bitter taste in the mouth, and reddish urine. Continued red vaginal discharge may be a sign of cancer, and the patient should immediately be referred out to an oncologist.
3. Yellow vaginal discharge (Huang Dai) is caused from Heat, usually Damp Heat in the Lower Burner produced from a Deficient Spleen not transporting the Dampness. This condition causes Water Dampness to brew and bind, which then transforms into Damp Heat. The Damp Heat invades the Conception Vessel which causes the Belt Vessel to lose its ability to restrain. It manifests as a yellow, sticky, and

slimy vaginal discharge with a foul odor. A vaginal discharge that has yellow and red with white pus (after menopause) is considered a manifestation of Toxic Damp Heat in the uterus and can indicate endometrium cancer.
4. Green-blue vaginal discharge (Qing Dai) is caused by Damp Heat in the Liver or Gall Bladder Channels. A yellow-green color with pus accompanied by itching and soreness is also a sign of Damp Toxic invasion.
5. Dark brown or black vaginal discharge (Hei Xia) is seen as a form of Blood stagnation.

All gynecological disorders are closely related to the patient's whole constitution, even though the manifestations appear in the reproductive organs. The patient's general constitution, age, dietary habits, home and work environment, should all be taken into account when diagnosing clinical pathophysiologies.

MENSTRUAL COMPLICATIONS

DYSMENORRHEA

Dysmenorrhea is one of the most frequent gynecologic disorders observed in the clinic today. It is described as pain associated with menstruation and refers to cyclic pain (before, during or after menstruation) felt in the lower abdomen or lumbosacral area of the woman's body before, during, or after menstruation. Serious cases of dysmenorrhea can be accompanied by headache, nausea, vomiting, and even syncope.

ETIOLOGY

From a Traditional Chinese Medical perspective, a woman's body is more susceptible to an attack of external pathogens and injury from internal emotional disturbances during her menstrual period. Mental depression may injure the Liver and cause Qi and Blood stagnation.

The invasion of Cold into the Thrusting and Conception Vessels may also cause stagnation and coagulation of Blood, which in turn causes Qi and Blood Deficiency (leading to poor nourishment of the uterus). Excessive exposure to Cold and Dampness can cause Cold to invade a woman's uterus, causing stasis of Blood. A women is prone to Cold invasion when her uterus and Blood are in a weakened state, during and soon after her period.

There are four different phases identified during a woman's menstrual cycle: Before Menstruation, During Menstruation, After Menstruation, and During Mid-cycle.

1. Before menstruation, the woman's Yang rises in preparation to move Blood during her menses; Liver Qi also moves into the lower abdomen in preparation to move the Blood. If a woman's Liver Qi stagnates, it can cause the Blood stagnation in the uterus, leading to pain, especially before her period. This type of stagnation is the most important pathological condition causing dysmenorrhea. Liver Qi stagnation can be caused from emotional strain resulting from suppressed emotions, such as anger, resentment, hatred, and frustration.
2. During menstruation, the woman's Blood is moving. The movement of Blood relies on Liver Qi and Liver Blood. If a woman's Liver Blood stagnates, it will cause pain during her period.
3. After menstruation, the woman's Blood and Yin are Empty.
4. During mid-cycle, the woman's Blood and Yin gradually fill up the Thrusting and Conception Vessels.

According to Western medicine, dysmenorrhea is related to mental stress, emotional instability, mental depression, and fright. Dysmenorrhea can also be due to diseases of the ovaries, uterine, or endocrine glands.

The menstrual pain may appear one to two days before the onset of the menstrual period, and remain until the start of the menstrual flow. It usually lasts from just a few hours to one to two days.

SYMPTOMS

In Traditional Chinese Medicine, dysmenorrhea is classified into two types of syndromes: the Excess type and the Deficient type.

- The Excess type of dysmenorrhea can be caused by either Qi and Blood stagnation, Cold stagnation, or Damp Heat. An Excess

condition manifests as distention and pain in a woman's lower abdomen and / or lumbago, occurring before or during menstruation. Symptoms also include obstructed menstruation with pale-purplish color and clots.
- The Deficient type dysmenorrhoea can be caused by either Qi and Blood Deficiency or Kidney and Liver Yin Deficiency. Symptoms of this condition manifest as pain in the lower abdomen, occurring before or during menstruation, which can be relieved by heat and compression. The patient will experience soreness and distention of the waist and legs with pale and scanty menses.

TREATMENT

1. To begin, have the patient sit at the edge of the table and begin stimulating the Yellow Court, Mingmen, and Lower Dantian areas, using the Vibrating Palm technique, for 6 to 8 breaths.
2. Emit Qi, using the Extended Fan Palm technique, into the patient's Lower Dantian, purging the Qi down the Stomach Channels to her feet.

TREATMENT MODIFICATIONS

- When treating patients with the Excess type of dysmenorrhea, emit Qi into the patient's Lower Dantian, St-21, and Lv-14 points, then purge the Stomach and Liver Channels down to and out of the feet.
- When treating patients with the Deficient type of dysmenorrhea, emit Qi into the patient's Lower Dantian, then guide Qi along the Stomach and Spleen Channels to regulate the body.

PRESCRIPTIONS AND HOMEWORK

Have the patient practice the Descending the Yang and Ascending the Yin techniques (see Chapter 41).

PRESCRIPTION MODIFICATIONS

1. For patients with the Excess type of dysmenorrhea:
    a. Have the patient sit at the edge of a chair, relax and breath naturally, with the tongue placed up against the hard palate. The patient's mind should concentrate on her Lower Dantian and navel area.
    b. The patient should imagine the navel as the center of a wheel. When inhaling, she should move the Qi upwards, rotating the energy clockwise, from the lower portion of the right side of the abdomen. The patient silently chants the phrase: "The white tiger hides in the east." Exhaling, she rotates the Qi from above the navel to the left side of the abdomen back to the beginning point, while silently chanting the phrase: "The blue dragon shelters in the west." The patient continues circulating the Qi around the navel, rotating it in a clockwise direction for 36 breaths. In this particular meditation, it is important the patient start with small circles and gradually increase the circumference of the energy circle, in order to disperse the accumulated Heat in the uterus.
2. For patient's with a Deficient type of dysmenorrhea:
    a. Have the patient sit at the edge of a chair, relax and breath naturally, with her tongue placed up against the hard palate. The patient's mind should concentrate on the Lower Dantian and navel area.
    b. Imagine the navel as the center of a wheel. When inhaling, she should move the Qi upwards, rotating the energy counterclockwise, from the lower portion of the left side of the abdomen. The patient silently chants the phrase: "The blue dragon shelters in the west." Exhaling, she rotates the Qi from above the navel to the right side of the abdomen back to the beginning point, silently chanting the phrase: "The white tiger hides in the east." She continues circulating Qi around the navel, rotating from large to small circles in a counterclockwise direction for 36 breaths. In this particular meditation, it is important that the patient start with large circles and gradually decrease the en-

ergy circle's circumference in order to gather energy into the uterus.

MENOXENIA

Menoxenia refers to the pathological changes of menstruation occurring in the cycles, such as the color, quantity, and quality. This includes extended or delayed menstrual cycles, as well as menorrhagia (excess bleeding) and scanty menstruation.

SYMPTOMS

1. Blood Heat symptoms include: prolonged menstrual cycle, profuse menstruation of bright red or purplish color, viscous in quality, and a heavy feeling in the chest.
2. Deficiency of Qi symptoms include: prolonged menstrual cycle, profuse, pale and watery menstruation, listlessness, palpitations, shortness of breath, and an empty or dropping sensation in the lower abdomen.
3. Blood Stasis symptoms include: delayed menstrual cycle, purplish and massed menstruation with pain and distention in the lower abdomen.

TREATMENT

1. Have the patient sit at the edge of the table and begin to stimulate her Yellow Court, Lower Dantian, and Mingmen areas using the Vibrating Palm, for 8 to 16 breaths.
2. Use the Extended Fan Palm hand posture to emit Qi into the patient's Mingmen and Lower Dantian using the Spiral Rotating method of Qi manipulation. Rotate the energy in a counterclockwise direction for conditions of Excess and a clockwise direction for Deficient conditions.

TREATMENT MODIFICATIONS

- When treating a patient with Blood Heat, emit Qi into her Yellow Court and Lv-14 points, drawing the energy down her Liver Channels and out of her feet.
- When treating patients with a Deficiency of Qi, use a Extended Fan Palm hand method while tonifying and filling her Mingmen and Lower Dantian areas.
- When treating a patient with Blood Stasis, use the Extended Fan Palm hand method to emit Qi into her Lower Dantian and rotate the Qi in a clockwise direction.

PRESCRIPTIONS AND HOMEWORK

In order to move the energy and allow Qi and Blood to flow smoothly in the uterus, have the patient practice the Microcosmic Orbit Fire Cycle (see Chapter 41).

PRESCRIPTION MODIFICATIONS

- For patients with Blood Heat, it is advisable to have them practice the Liver Massage method (see Chapter 39) and sound the word "Xu" (Shu).
- For patients with Qi Deficiency, have the patients perform Natural Breathing meditations, as well as the Daoist Five Yin and Yang Organ Exercise (see Chapter 42).
- For patients with Blood Stasis, have the patient practice Circling the Abdomen, for 36 breaths in a clockwise direction (see Chapter 41).

CYSTS AND TUMORS

BREAST CYSTS AND BENIGN TUMORS

A breast cyst or benign tumor is a lump or nodule found within the breast tissue.

ETIOLOGY

The fibrocystic changes that can occur in a woman's breast tissue are commonly divided into three levels of benign breast disorders. Beginning with Level-1 breast cysts (which include the development of benign lumps, nodules or fibroadenoma), progressing onto the development of Level-2 breast cysts (which include the development of mastitis or carbuncles), and ending with Level-3 breast tumors.

The Qigong doctor's treatment will vary according to the type and condition of the lump enclosed within the patient's breast tissue.

DIAGNOSIS ACCORDING TO DIFFERENT TYPES OF BREAST LUMPS

The Qigong doctor differentiates among the types of breast lumps and initiates treatment accordingly. Breast lumps can be divided into three major categories: Phlegm, Blood Stasis, and Toxic Heat.

1. Phlegm lumps are soft with distinct edges, mobile and slippery. They are not swollen, and the skin surface around the area is white.
2. Blood Stasis lumps are hard, immobile nodules. The skin surface around the surrounding area is purple.
3. Toxic Heat lumps are hard, immobile, with indistinct edges. The skin surface of the surrounding area is indented and red.

LEVEL-1 BREAST CYSTS (BENIGN LUMPS, NODULES OR FIBROADENOMA)

These are lumps that feel like hard nodules; they are usually painless, round, flat, and mobile. The lumps do not feel hot or cold to touch, the skin color is unchanged, and the size of the lump may vary depending on the patient's mood changes.

ETIOLOGY

Level-1 cysts are usually caused by the patient's Liver and Spleen being affected by anger, worry, and depression. The Spleen Qi is weakened, thus disrupting the free-flow of the Liver Qi. This leads to conditions of nodules due to both Qi and Phlegm stagnation. Long term Qi stagnation eventually leads to the accumulation of Phlegm and Stasis of Blood.

SYMPTOMS

These type of cysts are characterized by their process of development; they generally start off small and increase in size after several months.

TREATMENT

Eliminate the stagnation and remove the Phlegm using Qi purging and dispersing techniques.

LEVEL-2 BREAST CYSTS (MASTITIS OR CARBUNCLE)

This condition is a painful inflammation of the breast skin and underlying tissue.

ETIOLOGY

Level-2 cysts are usually caused by Qi and Blood stagnation, resulting from the stagnation of the Liver or Gall Bladder Qi, which is accompanied by excessive stagnation of Toxic Heat in the Stomach Channels. Breast cysts can be internally induced by suppressing the emotions, especially grief. Generally mother issues relate to the left breast and Lung area, while father issues relate to the right breast and right Lung area.

TREATMENT

1. After clearing the diseased area of Toxic Qi, the Qigong doctor uses the Sword Fingers technique to stimulate CV-17, St-18, Lu-1, Bl-18, and -21 points, to open the points along the Liver, Lung, and Stomach Channels.
2. Next, the Qigong doctor emits Qi, using the Vibrating and Shaking techniques, to disperse the cyst.
3. The doctor then applies the Dragon Mouth manipulation to dredge the patient's body, by pushing, pulling, and leading the Stagnant and Toxic Qi down the patient's Lung Channels (out the arms), and Stomach Channels (out her legs), via the St-36 points.
4. The patient is given homework, consisting of Jing Point Therapy, and of kneading the surface and surrounding tissue of the cyst at least once a day. This prescription should also include the use of the "Shang" sound tone resonation to further dissolve the cyst, and to dispel the Toxic Qi out of the breasts.

LEVEL-3 BREAST TUMORS

This type of breast cyst corresponds to a severe condition of dysplasia.

ETIOLOGY

Level-3 cysts are usually caused by Liver Fire, accompanied by Heart and Lung Qi stagnation due to the accumulation of grief, sorrow, exasperation, and being upset, or due to the derangement of the patient's Thrusting and Conception Vessels.

TREATMENT

1. After clearing the diseased area of pathogenic Qi, the Qigong doctor uses the Thunder Palm technique to disperse the tumor.
2. After several minutes of blasting the area, the Qigong doctor uses the Spiraling and Circling Energy techniques to circle the tissue areas

surrounding the tumor, drawing the pathogenic Qi down and out of the patient's nearest arm via the Lung Channel (Figure 51.1).

3. The Qigong doctor then uses energetic Pulling and Shaking techniques to release the pathogenic Qi from the patient's body and to draw it out of the arm. The doctor must then pull and snap each of the patient's fingers and thumbs, to release and disperse the Excess Heat and pathogenic Qi.
4. Next, circle rotate the energy within the patient's Lower Dantian, pulling the Qi down the lower legs and out the St-36 points.
5. Finally, fill her Lower Dantian and circle regulate her Governing and Conception Vessels using the Microcosmic Orbit to balance the Yin and Yang energy.
6. Give the patient homework consisting of Jing point therapy that stimulates the GB-21, St-36, CV-17, and Sp-6 points, once a day. If the patient is using magnetic therapy, she should place the magnets on the points for 1 hour. This prescription should also include herbs, and the use of the "Shang" sound tone resonation (straight tone and descending/ascending tone prescriptions) to further dissolve the tumor.

OVERVIEW OF TREATMENT

The general treatment for breast diseases, depending on the severity of the condition, is divided into five main components: Medical Qigong therapy, Medical Qigong massage, prescriptions, Jing point therapy, and herbal teas.

MEDICAL QIGONG THERAPY

The doctor's emitted energy can assist the patient in dispersing stagnations, as well as dissolving breast tumors and cysts. Generally, the doctor's treatment lasts for a period of three days, and can be indefinitely prolonged and increased in effectiveness if the patient is given additional Medical Qigong prescriptions as homework.

MEDICAL QIGONG MASSAGE PRESCRIPTION

This therapy is most important as it allows the patient to reconnect with her tissues and further allows her to feel and release emotions trapped



Figure 51.1. After purging the Toxic Qi from the patient's upper body, the Qigong doctor continues to disperse the patient's Toxic Qi from the lower abdomen, leading it down the patient's leg and out of the St-36 points.

within her body (remember, you can only heal what you feel). This healing process is as follows.

1. The patient begins by rubbing her hands together to get them hot.
2. Placing her hands on her breast, the patient inhales and draws the heat from her hands into the breast tissue, while imagining divine healing light flowing from the Heavens, and pouring into her body to fill up her chest.
3. The patient circle massages her breasts 36 times towards the outside of her body, concentrating on the breast tissue filling up with the divine healing energy that destroys any and all pathogens stored within her breast tissues.
4. After completing 36 times in one direction, the patient reverses directions but maintains the same visualization.
5. Next, the patient exhales the straight healing sound "Shang" for 9 breaths, toning, while turning the body from the left to the right side. The patient focuses on purging the pathogens out of her breast area through her mouth. This purges her Lungs and the surrounding breast tissues.
6. The patient then exhales the descending/ascending healing sound "Shang" for 9 breaths as she turns at the hips, toning from the right to the left side of her body, and focuses on purging the pathogens out of her breast area. This purges her Lung Channels and the surrounding energetic connections to the breast area.
7. The patient then rubs 36 times in a clockwise direction, from her abdomen to her Lower Dantian, leading the Qi downwards. This is performed to root the energy back into her Lower Dantian.
8. The patient ends the prescription in a quiescent state of mind.

MEDICAL QIGONG PRESCRIPTIONS

This therapy allows the patient to purge the organs that are found to be the root cause of the disease. In Medical Qigong, the doctor views the patient's cysts or tumors as a flower. If, through surgery, the top of the flower is plucked from its stem (and the branch, stem, and root cause of the disease is left still intact), the tumor or cyst will return again. In order to heal the patient's condition, the doctor must also address the original cause of the disease and destroy the entire support system. The purpose for these prescriptions is to destroy the disease's entire root system to kill the flower.

1. The Dry Crying prescription is given to purge the emotions of grief and sorrow from the patient's Lungs (see Chapter 53).
2. The "Guo" healing sound is given to purge the patient's Liver Fire.
3. The "Shang" healing sound is given to dissolve the cyst or tumor.
4. Prescribe Jing Point Therapy. Specific points are prescribed for the patient to enhance the doctor's treatments, and increase her own healing potential. The patient is encouraged to stimulate specific areas of her body, by emitting Qi while pressing and focusing her intention into the following points:
    a. The Small Intestine 3 point affects the patient's breast disease caused by Rebellious Qi and Qi depression.
    b. The Stomach 18 point frees Qi flow locally in the patient's breast.
    c. The Stomach Channel transverses the breast, and the Stomach 36 point regulates Qi of the patient's entire body.
    d. The Spleen 6 point is specifically chosen for treating breast cysts.
    e. The Gall Bladder 21 point (Shoulder Tapping) is prescribed to assist the patient in sinking Liver Qi Heat.

HERBAL TEAS

All herbal teas are administered to move the Qi and assist the doctor's treatment. Dandelion tea, for example, is mixed with green tea to clear Heat from the patient's body; or green orange peel is added to help move the Qi.

OVARIAN CYSTS AND UTERINE TUMORS

In an ovarian cyst, there is a closed sack or pouch containing fluid, semifluid, or solid material, usually characterized by Phlegm, Damp Heat, and Stasis of Blood.

3. Stage Two: Thrusting Channels to the Neck

A. Left Thrusting Channel to the Neck

1. Diaphragm

Using the procedure described above, bring the pearl up the Left Thrusting Channel to below the diaphragm and let it return down to the perineum.

2. Left Thyroid and Parathyroid Glands

Using the same procedure, bring the pearl up through the left ovary (women), left kidney and spleen, and continue to bring the pearl up to the left lung, and left thyroid and parathyroid glands. Hold for a while, and then exhale. Let the pearl return to the perineum. Practice nine times.

Be aware of the energy flow up to the neck through the Left Thrusting Channel.

B. Middle Thrusting Channel to the Neck

1. Diaphragm

Using the procedure described above, bring the pearl up the Middle Thrusting Channel to below the diaphragm, and let it return down to the perineum.

2. Thymus, Thyroid and Parathyroid Glands

Using the same procedure, bring the pearl up from the perineum through the prostate (men), cervix (women), small/large intestine, aorta and vena cava, stomach and pancreas. Continue to bring the pearl up to the heart, to the thymus gland under the sternum, and up to the middle of the neck, thyroid and parathyroid glands. Practice nine times. Exhale, relax and let the pearl drop down again.

Be aware of the Middle Thrusting Channel as the energy flows up to the neck.

C. Right Thrusting Channel to the Neck

1. Diaphragm

Using the procedure described above, bring the pearl up the Right Thrusting Channel to below the diaphragm and let it return down to the perineum.

2. Right Thyroid and Parathyroid Glands

Using the same procedure, bring the pearl up from the perineum to the right ovary (women), right kidney, liver and continue to bring the pearl up to the right lung and to the right thyroid and parathyroid glands. Exhale, and slowly release the energy down. Practice nine times.

ETIOLOGY OF OVARIAN CYSTS

Ovarian cysts can be caused by psychological upheavals which lead to enlarged follicles that fail to rupture, as well as by Liver Fire stagnation. Ovarian cysts are usually related to the anger from the Liver turning inward and attacking the body.

ETIOLOGY OF UTERINE TUMOR

A uterine tumor, or myoma, is a solid benign growth in the myometrium, and is often called a fibroid. It contains muscle tissue. Excessive uterine bleeding is a common effect of myomas. Ovarian cysts and uterine tumors are generally divided into three types of myomas:

1. The subserous type is located on the outside wall of the uterus;
2. The interstitial type is located within the wall of the uterus;
3. The submucous type is located on the inside of the uterus.

TREATMENT

The same treatment is used for both ovarian cysts and uterine tumors. To treat these conditions, the doctor uses Medical Qigong therapy in conjunction with Jing point therapy and herbs.

1. Begin with the patient in a supine position and purge and clean the diseased area of pathogenic Qi, using the Thunder Palm technique in conjunction with the Vibrating Palm, to disperse the stagnation in the ovaries or uterus.
2. Disperse pathogenic Qi out the patient's body via the Gall Bladder Channels.
3. Tonify the patient's Lower Dantian with Qi and circulate the energy through the Microcosmic Orbit.
4. Press and stimulate with Jing point therapy the Sp-6, Sp-9, St-36, GB-34, and GB-38 points (Figure 51.2).

PRESCRIPTIONS AND HOMEWORK

The patient should be given homework, in accordance with her constitution. The prescriptions should include:

1. The "Guo" sound to disperse Liver Fire.
2. The "Yu" sound to disperse ovarian cysts.
3. Prescribe Lower Dantian regulation exercises to access and regulate the ovarian energy.
4. Prescribe herbs for chronic conditions.



Figure 51.2. When treating ovarian cysts, use Jing Point therapy in conjunction with Qi emission, to stimulate Sp-6,-9, St-36, G.B.-34 and 38 points.

UTERINE COMPLICATIONS

MISCARRIAGE

A miscarriage is the termination of a pregnancy, at any time before the fetus has attained extrauterine viability. Miscarriage occur usually between conception and the fourth month of pregnancy.

In Traditional Chinese Medicine, a miscarriage can have several stages and levels of severity, ranging from such conditions as Fetal Leakage, Restless Stirring of the Fetus, Falling Fetus, and Small Birth. Within each of these conditions there are several patterns of disharmony.

ETIOLOGY

There is an ancient Chinese saying which states "A miscarriage is more serious than child birth." According to Traditional Chinese Medicine, there five basic mechanisms associated with the cause of a miscarriage: Empty Conception and Thrusting Vessels, Blood Deficiency, Depressed Liver Fire, Blood Stasis, and External Injuries.

1. An Empty condition of the Conception and Thrusting Vessels causes miscarriages. The mother's Kidney Qi consolidates the fetus and is responsible for constricting the anal and vaginal orifices. If the Conception and Thrust-

ing Vessels become empty, they cannot consolidate and secure the fetus within the womb. If any of the following three conditions occur singly or in concert, both the Conception and Thrusting Vessels may indeed become Empty: (1) the mother's Yin Essence is depleted or consumed; (2) the Mingmen Fire is insufficient, and (3) both the Yin and Yang Qi are Deficient. Any of these three conditions may be due to: congenital weakness and insufficiency, chronic disease, extreme or prolonged stress, unrestrained sex after conception, or the mother's age (over 40).

2. Blood Deficiency from an irregular diet, excessive worry and anxiety may deplete the Spleen and Stomach organs resulting in a miscarriage. Since the Spleen is the postnatal root for Blood generation and transformation, an Empty or Deficient condition of Spleen Qi may cause Blood Deficiency. Furthermore, as the Spleen Qi restrains and supports the mother's abdomen, a Spleen Qi Deficiency, or Empty Spleen Qi, may lead to the prolapse of the Central Qi and produce insufficient Blood to nourish the fetus. Both the Central Qi prolapse and the Blood Deficiency can present the Conception and Thrusting Vessels from consolidating the fetus and securing it in the womb.
3. Depressed Liver Fire due to suppressed emotional frustration (with mental agitation, anger, jealousy, and envy) may cause a miscarriage. The excessive Heat generated by the depressed Liver Fire may in turn attack the mother's Sea of Blood, scorching and injuring the Thrusting (Chong) Vessel. This injury, in turn, may cause the mother's Yin Blood to flow recklessly downward, leaving no place for the fetus to rest.
4. Blood Stasis may be due to three different factors: past internal injuries, iatrogenic disorders, and long term Qi stagnation. The excessive accumulation of Qi and Blood within the mother's womb during conception can sometimes aggravate a preexisting condition, and thereby cause hemorrhaging, as well as initiate energetic patterns which fails to stop her from bleeding.
5. External Injuries from accidents (sustaining a sprain or strain in the abdominal region), or battery (being hit or struck) can lead the body into a state of shock. This shock to the mother's body may damage either the Conception or Thrusting Vessels, preventing them from securing the fetus within the womb.

TREATMENT

In the Medical Qigong clinics in China, doctors are cautioned to be extremely careful when treating pregnant patients. Qi emission can cause a spontaneous miscarriage if done incorrectly. It is therefore recommended that only Medical Qigong doctors, who have specialized in the specific treatment of pregnant women, be allowed to diagnose and treat them. The interdependencies of the mother's and the fetus' energy circulation is too complex and delicate for a generalized practitioner to handle.

Treatments for miscarriage vary, based on pattern discriminations of Kidney Deficiency, Qi and Blood Deficiency, Blood Heat or physical trauma. An example of an ancient Chinese prescription requires the doctor to treat Yingu Kd-10 for miscarriages with vaginal bleeding, dark urine, abdominal distention, and fullness with an inability to lie down.

If the patient has already experienced a miscarriage, and is in the state of recovery, specific treatments vary according to the doctor's diagnosis concerning the etiology and pathology of the patient's condition.

HOMEWORK AND PRESCRIPTIONS

Each consecutive miscarriage causes further injury to the patient's Kidneys, creating or aggravating the stagnant Blood condition in the uterus. Doctors of Traditional Chinese Medicine therefore encourage their patients to take herbal medicines, and to practice Medical Qigong for six months before attempting to conceive again.

When they do become pregnant again, they are encouraged to continue to practice Medical Qigong meditations and exercises for strengthening and balancing their body's energetic fields and internal organs.

A patient recovering from a miscarriage is given specific prescriptions according to her emotional condition, organ dysfunction, and the etiology of the condition.

UTERINE COMPLICATIONS DUE TO ABORTIONS

Another important aspect of Medical Qigong and gynecology is helping a patient face the loss, or termination of a pregnancy. This can occur either intentionally (through an abortion), or unintentionally through a miscarriage, spontaneous abortion, or the death of a fetus by other causes.

When a woman has undergone an elective abortion, the Qigong doctor must not only consider the potential for scar tissue formation and physical complications within her uterus, but also the energetic and emotional complications resulting from the abortion.

While treating the patient, the doctor may discover within the uterus what appears to be the energetic remains of the aborted embryo. These phantom embryos may in fact be thought forms created by the mother's feelings of guilt and shame at having undergone an abortion. These difficult emotions are further compounded by deeper feelings of self-hate, that go unnoticed by others.

Most people feel little compassion for women who suffer a miscarriage, and discourage them from grieving. They are frequently advised by well meaning friends to believe that the miscarriage was all to the good, preventing a possible deformed or sickly baby from being born.

If women who miscarry are discouraged from grieving, those who make the painful decision to abort often face scorn and disbelief when they grieve their loss. Silently they mourn as best they can, haunted by feelings of shame imposed upon them by others and their own conscience.

Most women struggle long and hard before resorting to abortion. Afterwards, they often obsess about the living embryo, and what it felt like to be pregnant, centering all their attention on the uterus. Such intense, emotional concentration creates phantom embryos that, in fact, take on the form of ghostly embryos. These thought forms or energetic imprints are clearly visible to the doctor's inner vision. The energetic imprint contains the location, exact age and size at the time of the embryo's termination. The unprocessed energetic charge of the embryonic ghost's location creates an energetic vortex. This vortex, in turn, draws emotions such as rage, anger, guilt, and shame into itself. If this area is not purged, the resulting accumulation of negative emotions will develop into cysts, tumors, and possibly cancer.

This energetic reaction to surgical abortions has been confirmed by several Western doctors (all wishing to remain anonymous). These doctors observed that after many years of performing abortions, within a very short time period several patients (whose ages ranged from 16 to the mid 30's) developed reoccurring cysts and tumors. The location of the cysts or tumors in the majority of the patients uteri was at the exact tissue area of the embryo.

HEALING THE ENERGETIC TRAUMA

When the patient has decided to heal from her loss, she must not only address her physical condition (scar tissue formation, etc.), but also heal from the spiritual and emotional woundings as well. To assist the patient to heal emotionally and disperse the energetic charges, the doctor must help the patient transform the energy stored within her Wu Jing Shen, which is responsible for maintaining the toxic energetic pattern. Only after experiencing and releasing the emotions stored within the Wu Jing Shen (see Chapter 13) is the patient ready to heal. The healing process is divided into three distinct steps:

1. The patient is encouraged to completely forgive herself for losing the child and to reconnect with her higher power.
2. The patient is encouraged to completely forgive herself for being in the situation, and assume the responsibility of the pregnancy and the loss.
3. The patient is encouraged to completely forgive the person responsible for making her pregnant.

It is important for the patient to completely feel and experience all three stages of forgiveness in order to begin healing these energetic wounds.

Withholding the smallest bit of guilt or anger will seek to sabotage the healing process, and will also allow the toxic energetic charge to remain within the patient's tissues. Even the smallest bit of anger or guilt that remains will continue to recreate a destructive energetic cycle, storing and retaining the patient's toxic emotions.

RELEASING THE EMBRYO'S ETERNAL SOUL

The purpose and goal of releasing the embryonic thought form is to free the patient from the energetic remnants of the phantom embryo. The patient is encouraged to make peace with herself and with the energetic form of her unborn child, as well as the divine (God or higher spiritual force incorporated in the patient's own belief system). The patient does this through deep, meditative prayer, positive affirmation, and an attitude of honor and respect for the relationship between herself and the embryo's energetic remains. Even though the Eternal Soul does not remain present during the abortion, the mother may still need to atone for her decision not to bring the baby to term. This atonement may be necessary to fully release all feelings of guilt in accordance with the patient's religious belief system.

The patient must also make peace with the embryo's Eternal Soul, by enveloping the phantom embryo in a circle of divine healing light and love, to return it back to the divine. In order to achieve this, it is helpful for the patient to visualize creating a small energetic bubble, full of love and healing light, to house the departed embryo's energetic remains before returning it back to the divine. This serves to complete the emotional closure. Once closure is established, the energy of the embryo's energetic remains will leave her body, allowing the patient to feel a fulfilling sense of release, completion, calmness, and inner-peace.

UNDERSTANDING ENERGETIC ABORTIONS

The gift of life is an incredible miracle. If a difficult decision is made to not keep a pregnancy, however, then the patient should consider contacting the embryo's Eternal Soul. Through prayer, meditation, imagination, and visualization, the mother and father can connect to the developing embryo and request that the embryo's Eternal Soul return back to the light of the divine. Sometimes called an energetic abortion, this energetic transformation can take place within the first developing stages of the mother's pregnancy.

Since the Eternal Soul is ageless, it is possible to carry on a mind to mind conversation. When a baby is born, its brain must have time to develop before it can grasp complex information; the mind itself must have time to direct the brain's growth and the body's maturation. Once the Eternal Soul is freed from the body, however, it is not confined by the physical limitations of the infantile brain and should be spoken to as an equal. This method is used by psychotherapists on the leading edge today, using hypnosis to facilitate the patient's connection to the Eternal Soul through visualization.

Patients who have undergone age regression psychotherapy to the state of conception and embryonic state often describe visiting the mother's womb during the time of conception, then leaving and returning at various times during the embryonic stage of development. The Eternal Soul's residence does not appear to be permanent until the end of the first trimester (see Chapter 2). Until then, the Eternal Soul may come and go as it chooses, staying, at times, just long enough to insure the continued growth and development of its physical body.

It may be for this reason, that talking mind to mind with the embryo's Eternal Soul to request its departure, is often successful in precipitating a miscarriage. As the Eternal Soul leaves the embryo's body (sometimes observed as a small ball of white light energy), all that remains in the mother's womb is an empty, lifeless mass of tissue. Usually the mother's body will naturally abort the lifeless tissue mass, either immediately, or by the next morning.

CHAPTER 52

QI EMISSION THERAPY FOR NEUROLOGY (STROKE, COMA, PARALYSIS, AND MULTIPLE SCLEROSIS)

INTRODUCTION

Neurology is a branch of medicine that deals with the nervous system and its diseases, as well as neuropathology. Neuropathology is the study of diseases of the nervous system and the structural and functional changes occurring within them. Neurological diseases are divided into either congenital predispositions that develop over time into full-blown disorders, or those in which acquired destructive pathogenic factors act upon the brain. The latter are usually caused by toxic, traumatic, mechanical, inflammatory factors or neoplastic types of diseases (abnormal tissue formation).

The following is a description of several treatments and prescriptions used in various Qigong clinics and hospitals throughout China. Please be aware that specific treatments will vary according to each patient's constitution and the nature of his or her diseases.

STROKE (WIND-STROKE)

A stroke is a sudden loss of consciousness followed by paralysis, and may be caused by one of several different factors, including a brain hemorrhage, the formation of an embolus or thrombus in an artery, or the rupture of an extracerebral artery causing subarachnoid hemorrhage.

ETIOLOGY

Although a stroke occurs suddenly, in actuality, the causal factors build up for several years. A stroke can be caused from high blood pressure, diabetes, high cholesterol, chronic dehydration, overwork, emotional stress, irregular diet, excessive sexual activity and severe migraines. Strokes usually occur at night, or early in the morning (the same is true regarding heart attacks).

There are four pathogenic factors involved in causing stroke. These factors are: Wind, Phlegm, Fire and Stasis. The Liver is dependent on the Kidney Water (Yin Qi) to moisten and soften it. If, however, the Kidney Yin becomes Deficient, this may cause the Liver Yang energy to grow, and to generate Fire. Excess Liver Fire may stir up Internal Wind which causes the Qi and Blood to rebel upwards. Phlegm is then formed, which obstructs the cavities and vessels, causing the patient to lose consciousness. This can further develop into Penetrating Wind (i.e., stroke). Internal Wind may also develop from Heat and Phlegm caused by the patient eating too many sweet and fatty foods (irregular diet), overwork, emotional stress, excessive sexual activity, and inadequate rest.

In the clinic, conditions referred to as stroke (Wind-Stroke) include cerebral hemorrhage, cerebral thrombosis, cerebral embolism, and cerebrovascular spasm. These four conditions are termed in Western Medicine as "Cerebro-Vascular Accident" (CVA), and include: Cerebral Hemorrhage, Cerebral Thrombosis, Cerebral Embolism, and Cerebrovascular Spasm.

1. Cerebral Hemorrhage consists of bleeding, which is caused from a rupture of a sclerosed, or diseased vessel in the brain;
2. Cerebral Thrombosis is an obstruction of a cerebral artery by a thrombus (blood clot);
3. Cerebral Embolism is a condition which occurs when an embolus (bubble of air, or piece of a thrombus) detaches from a thrombus and obstructs a cerebral artery; and
4. Cerebrovascular Spasm (Ischemia) is a condition which occurs when a cerebral vessel temporarily contracts, or constricts, impeding Blood flow. Hence, the oxygen supply is obstructed sufficiently to cause symptoms. When reversible, or when there is no permanent damage, they are known as Transient Ischemic Attacks, or TIA's. The TIA's are pre-stroke symptoms, commonly known as a mini-stroke.

SYMPTOMS

In dealing with stroke patients, it is important to differentiate between the severe type (which attacks the internal organs and channels), the mild type (which attacks only the channels), and the chronic type.

Stroke manifestations can either arise independently from an attack on the channels, or as a result of an attack on the internal organs. After a severe type of stroke, the patient enters into the next stage, clinically manifesting symptoms similar to that of the mild type. The shorter the time lapse before beginning treatment on a stroke patient, the better the chances are for recovery.

THE SEVERE TYPE OF STROKE

In a severe type of Wind-Stroke, the energy attacks the patient's internal organs and channels. It is characterized by a loss of consciousness, aphasia, numbness, paralysis and/or coma. If the right side of the brain is damaged, there will be paralysis on the left side of the patient's body with accompanying memory defects and language difficulties. If the left side of the brain is damaged, there will be paralysis on the right side of the patient's body, speech and language difficulties, slow, cautious movements, and memory problems.

Clinically, severe stroke patients are further classified into two categories: Tense or Flaccid. The Tense type (also referred to as the Closed type) corresponds to the Collapse of Yin. The Flaccid type (also referred to as the Open type) corresponds to the Collapse of Yang. These conditions and symptoms are further described as follows.

1. The Tense Stroke Symptoms include: clenched hands, open eyes, clenched jaw, red face, coarse breathing, and a forceful pulse.
   - **Treatment for Tense Stroke conditions.** Rescue the patient's Yin by giving herbs, as well as extending Qi into the patient's GV-20, -26, Kd-1, Lv-3, St-40, and the 12 Jing-Well points on both hands (Lu-11, LI-1, Ht-9, SI-1, Pc-9, TB-1). The patient should be given homework upon recovering, depending on his or her constitution.
2. The Flaccid Stroke Symptoms include: limp hands, closed eyes, open mouth, weak breathing, and a weak pulse.
   - **Treatment for Flaccid Stroke conditions.** Rescue the patient's Yang by giving herbs, as well as extending Qi into CV-8, CV-6, and CV-4 points, and GV-20 points (with or without the application of Moxa), to increase the patient's Yang. Patient should be given homework upon recovering, depending on his or her constitution.

THE MILD TYPE OF STROKE

In the Mild Type of Wind-Stroke, the energy attacks only the patient's channels. This is characterized by numbness, slurred speech, and unilateral paralysis. Clinically, mild stroke patients are further classified into two categories that are determined by the type of channels that are attacked.

1. An attack of the main channels causes no loss of consciousness or coma; however, there will be unilateral paralysis (hemiplegia), numbness of the limbs and deviation of the eye and mouth. Clinical manifestations vary according to the location of the channels and collaterals that have been affected.
   a. Symptoms of an attack on the channels include: facial paralysis, hemiplegia, motor impairment and numbness of the limbs.
   b. Symptoms of an attack on the collaterals consists of a unilateral numbness of the face and extremities.
2. An attack of the connecting channels is characterized by numbness.
   - **Treatment for mild stroke conditions.** In order to treat a Mild stroke condition combine Medical Qigong therapy with acupuncture therapy and herbs, to:
     a. Remove obstructions from the patient's channels,
     b. Purge Wind and transform Phlegm,
     c. Invigorate the patient's connecting channels,
     d. Regulate the circulation of Qi and Blood in the patient's channels, and
     e. Prescribe homework in accordance with the patient's constitution and condition.

In the acute stage, stroke patients should immediately be treated in combination with Western medicine, utilizing Qigong, acupuncture and herbal therapy. Treatments should be given everyday (usually every six hours) for the first month, and every other day for the second month. The general treatment is aimed at relieving the patient's spasms, and lowering his or her blood pressure (if the condition is due to hypertension). The primary points treated are determined by the type of stroke, which internal organs were affected, and the extent of damage to the patient.

THE CHRONIC TYPE OF STROKE

This condition is characterized by slurred speech or an inability to talk or eat, and involves either a unilateral (hemiplegia) or bilateral (paraplegia) paralysis.

- **Treatment for Chronic Stroke conditions.** In order to treat a chronic stroke condition the Qigong doctor must invigorate the patient's Blood, tonify the Spleen and open the patient's channels. The specific points will vary according to the area and location where the channels are blocked. The most commonly used points include: St-4, St-6, St-7, TB-17, GB-14, LI-4, SI-18, Tai Yang (Temple), and Yin Tang (Third Eye Point).

  If the body is in a state of unilateral paralysis, the doctor also treats the opposite side of the patient's head using Jing Point Scalp Therapy, in order to move stagnation, purge any Excess, and stimulate and fill any Deficiencies.

COMA

A coma is an abnormal, deep stupor occurring during illness, as a result of the illness, or due to an injury.

ETIOLOGY

From a Traditional Chinese Medical perspective, a coma results from Qi obstruction to the brain. More then 50% of coma cases result from trauma to the head, or circulatory accidents in the brain. A coma can be initiated from several different types of conditions.

1. A trauma induced coma is caused by an injury to the head as a result of accidents and internal hemorrhages. Electrocution can also induce a coma.
2. Insufficient Blood flow to the brain can cause a coma. This can result from circulatory accidents within the brain caused from hypertension, arteriosclerosis, thrombosis, and tumors.
3. An overdose of drugs, alcohol or medications, poisoning, gases or fumes such as carbon dioxide or carbon monoxide can all induce a coma.
4. Temperature abnormalities, such as hypothermia or sunstroke can cause vomiting, diarrhea, shock and then coma.
5. Insulin shock, epilepsy, electrolyte abnormalities, endocrine problems, meningitis, uremia or renal problems, and hyperglycemia can all induce a coma.
6. An infection induced coma is caused by an acute infection and bacterial intoxications as in fevers, botulism, and other infectious diseases; or as a result from abscess formations.
7. Psychogenic comas are also known as a hysterical coma.
8. Windstroke comas are caused by tension, hyperactive Liver Yang and Phlegm Fire overheating the brain. This results in urine and stool incontinence, cerebral hemorrhaging, and thrombosis. This is often located at the union of the anterior and posterior cerebral arteries, called the Circle of Willis.

SYMPTOMS

When a patient is in a coma, the Shen is completely out of its residence and the patient cannot be aroused by external stimuli. The patient's Shen is inactive, yet the Hun and Po are still there. For death to occur, it is not enough for the patient's Shen to leave, but the energy of the Hun and Po must also leave.

TREATMENT

In treating coma patients, it is mandatory to use methods that will activate the patient's Qi, remove the Blood stasis, and return the Shen back into the body. In the acute stages of treatment, use Medical Qigong therapy in addition to the Invisible Needle technique (see Chapter 35). It is most important to treat the coma patient as soon as possible. I have trained with three doctors of Traditional Chinese Medicine who were proficient in coma revival. Below are two accounts of coma revival cases from Dr. Lu Guo Hong's clinic at the Hai Dan Medical Qigong College in Beijing, China.

Case Study #1. Dr. Lu's patient had been in a coma for four hours prior to treatment. The patient regained consciousness within fifteen minutes during the treatment. Dr. Lu treated his patient using the Vibrating Palm technique (on points GV-20, Yin Tang, GV-15, CV-17, Bl-15, Pc- 6, TB- 5, and the extra points Shi Xuan at the tips of the fingers). By squeezing the Shi Xuan points, the Excess Heat was allowed to disperse (Figure 52.1).

Case Study #2. A female patient apparently incurred a series of Transient Ischemic Attacks (TIA) over a period of two years prior to coming to Dr. Lu. As the condition progressed, she developed a thrombosis on the left side of the brain, which paralyzed the right side of her body. The patient then apparently incurred thrombosis of the right side as well.

Because there were thrombosis on both sides of the brain, the patient was expected to die within a month. Dr. Lu, assisted by two other doctors, treated the patient for three days using the Extended Fan Palm technique, Invisible Needles, and Vibrating Palm technique. In this particular case, the doctors used the same points as in the previously mentioned case to cultivate the patient's Yuan Qi, adding points Bl-23, GV-4, CV-4, and CV-8. The patient was treated twice a day for 15 minutes, both morning and evening.

On the fourth day, the patient regained consciousness, and the treatment was continued once a day for a month using the Conception and Governing Vessel circulation points (to move the Qi along the Microcosmic Orbit), in addition to points on the arms including LI-4, LI-11, LI-15, TB-5, and TB-14 points.

When treating the lower limbs, he used GB-30, GB-31, GB-34, Sp-6, Sp-10, and St-41 points. The patient was given prescriptions and homework, specific to her constitution, state of consciousness, and motor control.



Figure 52.1. Common Points used for Coma Revival

The patient gradually regained movement in her limbs. Once the patient could move her limbs, she was given Dynamic Qigong to increase the flow of energy to her extremities. This included meditations and exercises that used guided imagery to regain muscle cellular memory. After two months, the treatment time was changed to every other month until the patient was fully restored.

FACIAL PARALYSIS (BELLS PALSY)

This condition is known as the sudden onset of unilateral facial paralysis.

ETIOLOGY

The patient experiences the swelling of the seventh facial nerve due to the External Wind and Cold invasion.

SYMPTOMS

The disease is characterized by hemiparalysis of the face which manifests as numbness of the affected area, deviation of the eye and mouth, distorted mouth with the corners tilted on the healthy side, and a half closed eye with dacryorrhea (excess tear flow).

TREATMENT

For this type of paralysis, it is important that the Qigong doctor treat the patient as soon as possible. The shorter the duration time from the initial onset and the treatment, the more successful the therapy tends to be.

1. Begin by purging the Toxic Qi out from the patient's face and head area, dredging the Toxic Qi down the arm and out the LI-4 point.
2. Using the Extended Fan Palm hand technique, emit Qi into the affected area, guiding the Qi to circulate in the Microcosmic Orbit from the anterior to the posterior of the patient's head.
3. Finally, initiate the Fire Cycle Microcosmic Orbit to regulate the patient's Qi.

TREATMENT MODIFICATIONS

- For treatment of the first stage of paralysis, the doctor is advised to apply gentle Pressing and Kneading techniques to the patient's face before using the Extended Fan Palm hand technique.
- To treat patients whose paralysis has remained in a chronic state, the doctor is advised to use deep pressing and kneading techniques before using the Vibrating Palm technique.

PRESCRIPTIONS AND HOMEWORK

1. Have the patient massage the affected side of the face from the corner of the mouth to the ear and forehead, down over the side of the ear and down the side of the neck 81 times.
2. The patient then focuses on specific areas on the face, circle massaging with the tips of the thumbs for 24 times.
3. Finally, the patient is given the Wash the Face and Massage the Head exercise to perform for 18 times (see Chapter 39).

MULTIPLE-SCLEROSIS (MS)

In Chinese medicine, multiple sclerosis is considered a type of Atrophy Syndrome. It is an inflammatory disease of the central nervous system in which infiltrating lymphocytes (predominantly T cells and macrophages) deteriorate the myelin sheath of nerves. Its pathology consists in the partial destruction of the myelin sheath around the spinal cord, brain and optic nerves.

ETIOLOGY

Multiple sclerosis is suspected to be an autoimmune disease, somehow linked to a viral infection originating from an invasion of External Dampness (especially in the beginning stages). As the External Dampness invades the body it begins to obstruct the channels, causing heaviness, numbness, and tingling in the limbs.

Diet is another contributing factor. The excessive consumption of greasy fried foods, dairy foods, or Cold foods can impair the Spleen, leading to the formation of Dampness.

In the later stages of MS, excessive sexual activity can also be a contributing factor for weakening the body and escalating the disease's progression. Excessive sexual activity can weaken the patient's Kidneys, contributing to such symptoms as dizziness, blurred vision, urgency or hesitation of urination, and extreme weakness of the legs. If excessive Liver Yang develops, symptoms will also include stiffness of the legs, severe vertigo, and vomiting. In the later stages of development, Liver Wind can cause tremors and severe spasms of the patient's legs.

Clinically MS is categorized as either a passive aggressive type of disease, in which episodes of neurologic dysfunctions are followed by times of remission, or a steady progression of neurologic dysfunction.

SYMPTOMS

The symptoms of MS were once thought to develop gradually; however, this is not necessarily true. In about 40% of clinical cases, the onset may occur in less than a few hours. In about one half of the patients, at onset the symptoms include weakness, or numbness in one or more limbs; later, the tendon reflexes become hyperactive.

In young patients the first obvious symptom is often retrobulbar neuritis (inflammation of the nerves behind the eyeball) causing blurred vision. In older patients the most common symptom is weakness of the legs.

Patients may experience vertigo, retrobulbar or optic neuritis, double vision, unstable walking, vomiting, and difficulty urinating. Also included are numbness or tingling of the extremities, as well as periodical electric shocks radiating through the limbs. These symptoms may be due to optic nerve, brain stem, cerebellar and spinal cord involvement.

Traditional Chinese Medicine divides these

Be aware of the Right Thrusting Channel as the energy flows up to the neck.

D. Continue to Practice the Three Thrusting Channels to the Neck

Practice all three Thrusting Channels to the neck, nine times each, as delineated for the diaphragm: left, middle, right, middle, left, middle, right, middle and left.

E. Clear the Routes with Saliva

If your throat feels dry, you can collect and warm the saliva in your mouth. Tighten your neck a little bit, and swallow the saliva with a guttural sound down to the stomach. Feel the saliva like a fire clearing all three channels.

Practice this stage for about one or two weeks, each time finishing by moving the pearl in the Microcosmic Orbit and collecting it in the cauldron.

F. Rest and Concentrate on All Three Channels

Rest and concentrate on all three channels, visualizing the left route as red, the middle as white, and the right as blue.

4. Stage Three: Thrusting Channels to the Crown

In stage three of opening the Thrusting Channels, the pearl is thrust through the channels up to and out of the crown.

A. Left Thrusting Channel to Crown

1. Left Eye

Follow the above procedure for thrusting through the Left Thrusting Channel to the neck, and continue thrusting to the left eye.

2. Crown

Repeat the Left Thrusting Channel to the left eye and continue to thrust the pearl up through the left hemisphere of the brain to the crown. Practice nine times. Rest, and mentally trace the Left Thrusting Channel from the perineum to the crown.

B. Middle Thrusting Channel to the Crown

1. Mideyebrow

Repeat the Middle Thrusting Channel procedure as described to the neck and continue thrusting to the mideyebrow.

symptoms into two categories of clinical manifestations: Damp Phlegm with Spleen Deficiency, and Liver and Kidney Deficiency.

Clinical manifestations in patients with Damp Phlegm and Spleen Deficiency include feeling weak and tired, dizzy, as well as numbness, tingling and feeling of heaviness in the legs.

Clinical manifestations of patients with Liver and Kidney Deficiency include progressive weakness of the back, legs and knees, blurred vision, dizziness, poor memory, and a hesitancy, or an urgency to urinate.

TREATMENT

There are two basic treatment patterns in Medical Qigong for multiple sclerosis. If the treatment is started within its early stages, the symptoms can be completely eliminated, and the progression of the disease indefinitely stopped. This, of course, must be done in conjunction with an alteration in the patient's eating habits (no red meat, processed meat, sugar additives, or high fat diary products). The patient should reduce the amount of sexual activity, get plenty of rest and exercise, and avoid allergy causing agents. Treatments are described as follows.

1. To treat a patient with Damp Phlegm and Spleen Deficiency, first resolve the Dampness by purging the patient's torso and extremities. Next Dredge the Toxic Qi down the legs and out the Sp-9, and Sp-6 points. After purging, emit Qi into the Yellow Court (CV-12) to tonify the Spleen. Finally tonify the patient's Lower Dantian and regulate his or her Microcosmic Orbit (Fire Cycle).
2. To treat a patient with Liver and Kidney Deficiency, first tonify the patient's Kidneys and Liver by emitting Qi into the patient's Mingmen and Lower Dantian. Next emit energy into the patient's Bubbling Spring (Kd-1) points and direct the Qi to flow up the patient's Yin Channels into the patient's Lower Dantian and Kidney area. Finally, regulate the patient's Microcosmic Orbit (Fire Cycle).

PRESCRIPTIONS AND HOMEWORK

Patients often benefit from Medical Qigong exercises such as the Descending the Yang and Ascending the Yin Technique, Walking Therapy, Daoist Five Organ Exercises, as well as Taijiquan (Tai Chi Chuan) practice. One prescription I have found to be very effective in treating MS patients is as follows.

1. Have the patient sit in a chair, feet flat on the ground, hands resting on the knees, anal sphincter closed, tongue touching the upper palate while inhaling and exhaling through the nose.
2. While using natural breathing, the patient focuses on the Lower Dantian to create an energy ball. With each inhalation, divine healing light is absorbed into the body and stored in the Lower Dantian. With each exhalation, this healing light radiates within the Lower Dantian. After several minutes, the patient notices the Lower Dantian becoming full of heat and light.
3. Next, the patient imagines the energy ball in the Lower Dantian leaving the body through the coccyx into the Earth upon exhalation. Upon inhalation, the patient imagines the energy flowing up the center of both legs and filling the Lower Dantian. This meditation should continue for at least 20 to 30 minutes per sitting.

CHAPTER 53
QI EMISSION THERAPY FOR PSYCHOLOGY

INTRODUCTION TO ENERGETIC PSYCHOLOGY

The object of Chinese psychology is to study and understand the interplay of internal and external events on physical, mental, emotional, energetic and spiritual dimensions of human existence. These interactions include the human qualities and characteristics, as well as the fundamental attributes that exist and evolve within the changing environment and evolutionary development of nature. These interactions at the most fundamental level can be viewed as the transformational interactions of Yin into Yang, and Yang into Yin vibrational energy.

All matter vibrates regardless of its form (gaseous, liquid, solid, or in a transitional state such as ice melting into water). The human body receives these vibrations through the skin, eyes, ears, nose, and mouth, and records them in its cells. The mind interprets these incoming vibrations as images, sounds, smells, and sensations, and organizes these into memories. The extent to which the mind interprets the incoming data, depends upon the level of consciousness and awareness of the individual at the time of the recording. In times of danger, alertness normally increases and consciousness either expands or focuses more sharply until the danger is past; or if an injury occurs consciousness and awareness may be lost (e.g., a car crash).

When a Qigong doctor, attunes his or her vibrations to the patient's energetic field and emits Qi, the body's cells responsible for storing the vibrations are stimulated. The doctor's intention to heal the patient by releasing traumatic memories, combined with his or her projected Qi, often causes the patient to relive the original traumatic experience as the recorded vibrations are released. The Qigong doctor (still in tune with the patient's energy) is receptive to the patient's reaction and is able to interpret the released energy in the form of images, sensations, smells, sounds, and emotions while they are being reexperienced by the patient. If the doctor is sufficiently attuned, he or she may even pick up the conscious thoughts of the patient during this process.

As doctors tune in to their patients' cell emissions they are also able to project their own thoughts and interpretations of these memories back to the patients. This creates a positive feedback system, wherein the doctors' thoughts can influence the patients' thoughts and emotional reactions. Through thought transmission, Qigong doctors are often able to break the vicious cycle of negative thinking that so often leads to disease in the body.

In Western psychology, it is believed that a person's tendency to interpret events - even negative imaginary events (e.g., assigning malicious intentions to peoples' actions), can result in a self-fulfilling prophecy. By assuming and expecting the worst behavior in people, such a person always feels on the defensive and provokes others around him or herself to anger or irritation, thus reinforcing the negative viewpoint.

Chinese energetic medicine adds to this simple behavioral understanding of self-fulfilling prophesies, a new level of comprehension based on energetic interchange between people. When someone observes, or imagines, a specific negative thing happening, certain brain cells record this information in the form of vibrations. These vibrations can be received by another person's corresponding brain cells and projected back to the original sender, reinforcing the negative interpretation of the event(s). If this feedback loop continues - an imaginary wrong may become manifest, i.e., the negative event imagined actually occurs.

It is believed that different cells store different types of information, received in the form of vibrations. The silent thought communications between doctors and patients is believed to involve different sets of cells than those used to receive and record emanations of divine energy. These cells interrelate with the patient's emotional changes that are stored and released from the Yin and Yang organs and tissues, and are expressed through the patient's Wu Jing Shen.

The patient's ontology also includes the patient's growth and self-realization in relationship to the Wu Jing Shen (Five Essence Spirits) and the emotions stored within the body's Yin and Yang organs. Each of the Five Yin Organs has a Yin and a Yang aspect within its energetic substance, as well as emotional factors, and dynamic interconnections. The Yin and Yang aspects give rise to the Creative and Controlling Cycles and the Five Yin organs with their associated elements and emotional energies (Figure 53.1 - 53.3).

Summary of the Five Elements		
Wood	Liver	Anger, irritation and rage
Fire	Heart	Joy, happiness, pleasure and excitement
Earth	Spleen	Worry, sympathy, anxiety, contemplation and meditation
Metal	Lungs	Grief, sorrow, anguish, distress and heartache
Water	Kidneys	Fear, terror, panic, horror and fright

Figure 53.1. The Five Elements, Organs and Acquired Emotions

THE EMOTIONAL ENERGY STORED WITHIN THE FIVE YIN ORGANS

Traditional Chinese Medicine classifies the etiology of diseases into Internal and External physical, mental, emotional, energetic, and spiritual influences. In Chinese psychology, the primary focus is placed on the "root" of the energetic/emotional dysfunction. The root of the energetic/emotional dysfunction is often the unprocessed emotions which are stored in their associated organs. Once the patients' mental and emotional symptoms have been alleviated, the energy that was being used to suppress the excessive emotions, is then freed to be focused on their physical healing.

Traditional Chinese Medicine also recognizes the power of thoughts, images (including psychotic delusions and hallucinations), and fantasies to generate and release emotions. Qigong doctors study these images and emotional reactions of attraction or aversion to evaluate their patient's condition. When traumatic memories and emotions are suppressed over a long period of time, or are still fresh in the mind, any minor incident can precipitate a tidal wave of emotions. A rapid influx of thoughts and images sweeps through the mind, too fast for the conscious brain to register. These thoughts and images are of past painful experiences, and are loaded with emotional energy. Getting cut off by someone on the freeway, for example, may cause a momentary reaction of surprise, or an explosive enduring rage, depending upon the condition of the Five Yin Organs. In the latter case, the driver is overwhelmed by the Liver's sudden release of rage, triggered by the traumatic images and emotions from the past.

Clinical pathology is considered an Excess or Deficiency of the emotions at the level of the Five-Elements and their corresponding organs. The Excess or Deficiency of an internal organ can cause a release of thoughts or images that sweep through the patient's mind, bringing a sudden emotional response. In some instances these emotions first affect a specific organ, and then the entire balance of energy, as the first organ's energetic field deteriorates or adversely expands. When emotionally charged Qi is trapped within the tissues of the patient's internal organs, it travels through the channels, affecting the metabolic order of the viscera, glands and nervous system.

Creative Cycle			
Wood	Anger	Creates Joy	Fire
Fire	Joy	Creates Worry	Earth
Earth	Worry	Creates Grief	Metal
Metal	Grief	Creates Fear	Water
Water	Fear	Creates Anger	Wood

Figure 53.2. The Creative Cycle

Controlling Cycle			
Wood	Anger	Controls Worry	Earth
Earth	Worry	Controls Fear	Water
Water	Fear	Controls Joy	Fire
Fire	Joy	Controls Grief	Metal
Metal	Grief	Controls Anger	Wood

Figure 53.3. The Controlling Cycle

Emotions consist of energetic light that is either tempered and softened by the patient's belief structure and energetic fields. When the emotions and life purpose are in harmony, the Wu Jing Shen become focused; the Hun and Po do not disperse, grief and anger do not arise, and the Five Yin Organs effectively combat pathogenic influences. If this energetic light becomes unstable, i.e., too Excessive or Deficient, the patient's inner strength and individual nature begins to undergo dramatic changes.

The body's internal organs and their relationship to the Five Elements are as follows.

EXCESSIVE ANGER INJURES THE LIVER (WOOD)

The Chinese character for anger (Nu) is depicted by the Heart ideograph underneath two characters, a woman (placed on the left) and someone who has the upper hand (placed on the right). It expresses the feeling and frustration of an enslaved woman being dominated by someone.

PATHOLOGICAL MANIFESTATIONS OF ANGER

Pathological anger is considered the perverse movement of the element Wood. Anger is a generated force that has the potential to unleash explosive amounts of Qi, pushing the energetic manifestations to the extreme.

THE YIN AND YANG ASPECTS OF ANGER

The emotion of anger can be divided into Yin and Yang tendencies. The Yang type of anger can burst out due to accumulated pressure, resulting in the upward flow of massive amounts of Blood and Qi. The Yin type of anger implodes, remaining buried or held inside, thereby causing internal agitation and dissatisfaction which generates blockages.

The Liver's negative nature is one of being stubborn and rude; its positive nature is one of being compassionate, unselfish, kind, and merciful. The rising of Heat from the Liver's Qi corresponds to the level of anger; since the Liver stores the Blood and the Blood stores the Hun (Ethereal Soul). When the Hun leaves the body due to anger and rage, the animal nature of the Po take over. As the individual's Liver Fire rises, it causes the eyes and the face to become red. Liver Fire can also injure the Liver as well as the Blood, bile and Body Fluids associated with this organ.

ANGER AFFECTING THE LIVER

When Liver Qi becomes depleted it retracts, causing the emotion of fear to arise. When Liver Qi fills to Excess, the result is progressive restlessness, irritability, anger, and rage. In some instances, these emotions affect the entire balance of energy so that the organ begins to deteriorate.

Anger can cause trembling of the entire body due to the Liver's control of the tendons and ligaments.

When an individual experiences any type of boundary invasion, the Liver Qi triggers the Heart (Shen) to recall from its long term memories past traumas (containing both anger and fear). At the same time, the Liver also drains the Kidney Qi to meet the apparent life-threatening situation; this prepares the body for the flight or fight response. The power of the emotional response causes the Heart to go into shock and prevents the Shen from directing the mind. Thus another trauma is experienced by the patient's interpretation of the event (e.g., getting cut off on the road) and will automatically trigger an exaggerated emotional response in the future.

Given that the Liver is the mother of the Heart (responsible for long term memory) and the child of the Kidneys (responsible for short term memory), the Liver can drain the Kidneys and flood the Heart with anger, causing one's mind to go blank and the face to turn red.

ANGER AFFECTING THE SPLEEN AND STOMACH

Anger can damage the Spleen and Stomach, causing digestive problems, loss of appetite, and a sour taste in the mouth. These symptoms are directly related to the level of anger.

ENERGETIC PATTERN OF ANGER

The Qi pattern of anger has a very hot energy associated with it. When discharged, this hot energy swells up like a tidal wave expanding from behind the person's back over the head (Figure 53.4). It crests over the head and rushes forward like a wild animal attacking. The emotion also travels from the groin up the back of the body and out through the eyes.

Grief controls anger as metal cuts wood. At the root of anger is pain and sorrow. The anger protects the patient from feeling the initial hurt that festers like an infected wound. When the doctor lances the wound, allowing the toxic anger to drain, the uncovered original hurt can heal cleanly. Anger is transformed to sorrow and grief. The compassionate, non-judgmental attitude of the doctor allows the patient to grieve openly. The release of toxic anger and pain enables the patient to listen to the Hun. By focusing on the patient's emotional hurt from past experiences, which are the root of his or her anger, a shift from anger to hurt occurs. This exchange of emotions allows the patient to confront the hurtful past memories and discharge the toxic anger.



Figure 53.4. Anger rushes from the Liver over the back like a tidal wave, causing the Qi to ascend.

EXCESSIVE JOY INJURES THE HEART (FIRE)

The Chinese character for joy (Le) is depicted by the ideograph of a large drum, framed by bells mounted on a wooden stand. It expresses the feeling of rhythmical ceremonies and excitation. The character gives the image of a hand beating a drum during a festival (this same character is used for music).

THE YIN AND YANG ASPECTS OF JOY

When the Heart's emotions are balanced, they can be experienced as love, joy, happiness, excitement, and pleasure. This warmth radiates through the body affecting the expansion of free and easy Qi circulation. Joy is communicated and felt throughout the body, mind and soul.

PATHOLOGICAL MANIFESTATIONS OF JOY

Excessive joy and laughter can injure the Heart and scatter the spirit; the Qi becomes congested and the Heart flutters erratically. When the Heart Qi becomes depleted, it can no longer control the Lungs: the emotion of grief arises, and when the Qi fills to Excess, hysteria results. Water extinguishes Fire, therefore the emotion of fear controls the emotion of joy. By supporting a hysterical patient to become aware of his or her underlying fears, the doctor can startle the patient into a sense of sobriety.

Pathological joy and laughter are considered the perverse movement of the element Fire. If the patient's Fire becomes uncontrollable, the Qi - which expands outward towards the periphery - will cause the patient to become hysterical. After Fire has exhausted the patient's life-force, it leaves the patient exhausted, dazed, and disenchanted. The Heart's negative nature is confused, doubtful, and greedy; the positive nature is open-minded, loving, non-judgemental, and trustful.

ENERGETIC PATTERN OF JOY

Joyful feelings make the body's Qi become soft and relaxed. This energetic pattern is expansive, and causes a slower movement of the Qi. As the Heart controls the blood vessels and stores the Shen, a joyful spirit produces a clear, calm mind and a healthy body. This energy bubbles out from the center core of the body and ripples out in all directions (Figure 53.5). A light energy gently flows from the recipient back to the person expressing the emotion. While in this state, the patient's head is usually held erect, the face is full of color, and the limbs are relaxed.



Figure 53.5. Joy bubbles out from the center core of the body, rippling out in all directions, causing the Qi to slow its flow.

EXCESSIVE WORRY INJURES THE SPLEEN (EARTH)

When the Spleen Qi becomes depleted, all four limbs lose their strength and the Five Yin Organs become unstable. When the Spleen Qi becomes Excessive, the body becomes swollen and the flow of urine and menses loses its smoothness.

THE YIN AND YANG ASPECTS OF WORRY

The emotions associated with the Spleen are relative to the energy expended in contemplation, meditation, anticipation, and worry. Too much worry and thought produces Qi stagnation. A stagnant condition causes Stomach disorders, such as poor appetite, indigestion, ulcers, constipation, or diarrhea. Stagnation can also block the Shen, which is responsible for emotional and mental balance, and thus result in a lack of common sense. The Spleen's negative nature is suspicious and self-centered; the positive nature is truthful, sincere, and compromising.

WORRY AFFECTING THE MEMORY

The Spleen stores the Yi, and the Yi stores ideas. The Spleen transfers short term memory to the Kidneys; the Kidneys later transfers the acquired memory to the Heart, which is responsible for long term memory. In trauma victims, the Kidneys' role in transferring memories, can also account for the loss of memories that are too terrible to accept, since these memories are transferred along with great fear, or fail to get transferred at all.

THE ENERGETIC PATTERN OF WORRY

When one is worried, the energy comes up from the Earth and congests in the Middle Dantian area, thus weakening the Wei Qi (Figure 53.6).

CONTROLLING THE EMOTION OF WORRY

Because the element Wood controls the element Earth, the emotion of anger controls worry. It is very important that any anger uncovered be directed at the root cause, and not at the doctor who is trying to help a patient end a negative pattern. The doctor will gently challenge toxic belief structures held by the patient, until the patient begins to confront whatever issue is at the root of the anger.

When the patient becomes angry with the doctor, it is generally a condition known as "transference." If and when transference arises, the Qigong doctor can ask the patient, "Who do I remind you of right now?" or "When was the last time you felt this way?" Trace the patient's feelings as far back as possible. If the doctor gets mad at the patient, it is called "countertransference." Both transference and countertransference can involve any emotion (e.g., falling in love, feeling afraid, etc.).

EXCESSIVE SADNESS AND GRIEF INJURES THE LUNGS (METAL)

The Chinese character for sadness (Bei) is depicted by the Heart ideograph underneath the character for the back (placed on the top). It portrays a picture of a person who has turned his or her back on the true feelings of the Heart. The Chinese character for grief (Ai) is depicted by the mouth ideograph (wailing, groaning, and lamenting) placed within the center of the character of someone dressed in a special garment for mourning. Pathological grief is considered the perverse movement of the element Metal.

When grief is experienced, its natural movement of condensation begins to compress the Heart, interfering with Blood circulation. This obstruction destroys both the respiratory flow of the Lungs, as well as the body's liquids. The Lungs store the Qi, the Qi stores the Po (Corporeal Soul). When the Lung Qi becomes depleted, shortness of breath develops. When the Lung Qi becomes excessive, the result is a feeling of discomfort in the chest, panting, and difficult breathing.



Figure 53.6. Worry binds the Qi, causing the Qi to stagnate.

THE YIN AND YANG ASPECTS OF GRIEF

The feelings associated with the Lungs are sadness, melancholy, grief, sorrow, and anxiety. The negative nature is cunning, jealousy, and pessimism; the positive nature is generosity and righteousness. In the Five Elemental Controlling Cycle, the Lungs (Metal) affect the Liver (Wood). Excessive sadness from the Lungs can cause the Liver Qi to stagnate the Blood (Metal Overcontrolling Wood), leading to possible intercostal and hypochondriac pain, bloating, and depression.

GRIEF'S AFFECT ON THE INTERNAL ORGANS

Grief disperses the Qi, and thus injures the Lungs. Crying can lead to the release of toxic anger (that suppresses the feelings of sorrow) and grief. Depression and despair may also be manifestations of abnormal Liver Qi stagnation. When grief from the Lungs is excessive, the Spleen may be affected (this almost always happens after a major loss, such as a death in the family).

THE ENERGETIC PATTERN OF GRIEF

The external energetic patterns of grief and sorrow have a heavy, downward moving energy (Figure 53.7). The internal energetic patterns and manifestations of grief have a very thick, sticky energy, and a denseness like gelatin. Long periods of extreme grief also injure the Heart, Pericardium, and the Triple Burner Channels.

CONTROLLING THE EMOTION OF GRIEF

Because Fire melts Metal, the emotion of joy controls grief. The grieving process is a very important part of healing; however, chronic grief can be extremely detrimental, and when it is extreme and prolonged it can lead to spiritual oppression or possession. If the survivor cannot accept the death, he or she may prevent the departure of the loved one's spirit for many years on end. The patient may beg the Eternal Soul not to leave and cling with unrelenting grief to the lost one's energy. This type of dependency deepens, rather than lessens over time, as the patient opens more to receive the loved one's spiritual essence. In so doing, other Gui (spirits) are given power to enter as well.

After a death of someone loved, the patient may consciously suppress any joy or pleasure. The patient may believe that to allow any relief to suffering is tantamount to a betrayal of the deceased. This belief structure must be addressed by the doctor and patient. Establishing a sense of empathy with the patient will provide a safe environment for the patient to release the emotion of grief. The doctor can work towards empowering the patient to begin to recognize times of joy, and learn, or remember, how to count his or her blessings, to let go of sadness and grief, and reclaim lost joy.

Grief may give way to despair and anxiety. Because anxiety suppresses respiration, anxiety lowers the body's resistance to pathogenic factors by weakening the Wei Qi; anxiety also damages the Large Intestine, resulting in symptoms that range from constipation to ulcerative colitis.

Just as too much grief can cause inappropriate laughter, or gallows humor; too much laughter masks the accumulated and suppressed grief. Gallows humor is a syndrome whereby the patient laughs instead of grieving about hurtful past, or current experiences. Gallows humor is a defence mechanism of the patient's denial. Grief and humor are examples of opposites (Yin and Yang) transforming into each other.



Figure 53.7. Grief causes the Qi to become obstructed.

The concern in dealing with many grieving people (pertaining to the death of a patient's mate or close friend, etc.) is that the patient may be using grief to suppress other unresolved emotions, such as: guilt, fear and loneliness.

1. Fear of forgetting the deceased voice, appearance, etc. may be due to feelings of guilt over not having expressed enough love towards the person when it was possible to do so.
2. Guilt over any expressed feelings of joy or happiness, may seem morally wrong because they cannot be shared by the departed.
3. Guilt may arise from too many hurtful things said, or too many things left unsaid to the departed.
4. Guilt over never having had the chance to really say good-bye (as with victims of accidents and sudden death) may become all consuming.
5. Loneliness and isolation may result from the loss of friendships.

6. Worry that loss of income and security may cause financial difficulties and health problems may cause the patient to cling to the past.

To assist the patient to heal from these toxic beliefs, the doctor prescribes creative visualizations, such as the following.

"Imagine, see and feel yourself and your loved one clothed in your astral bodies. Embrace and express your feelings and thoughts, knowing that these will be heard and received. Listen to your loved one's answer.

Ask forgiveness for any cruel remarks or failures to be as loving as you wish you could have been. Visualize your loved one accepting the request for forgiveness; embrace with love, and release him/her to be with God with your blessings."

In cases where the patients could not attend the funeral, have the patient imagine the funeral and perform a ritual closure (e.g., lighting a candle at home and saying a prayer).

Finally, encourage the patient to give him or herself permission to experience some joy in life and to go on living.

EXCESSIVE FEAR INJURES THE KIDNEYS (WATER)

The Chinese character for fear (Kong) is depicted by the Heart ideograph underneath two characters, a structure (placed on the left) and repeated strokes by the small blows of a hammer (placed on the right).

THE AFFECT OF FEAR ON THE INTERNAL ORGANS

The Kidneys store the Jing, the Jing stores the Zhi (actions that the mind expresses). Pathological fear is considered the perverse movement of the element Water. Fear is the unrestrained sinking and uncontrolled descent of Water Qi. When the Shen of the Heart is no longer supported by the Kidneys' Jing, the Shen leaves its residence. This results in the emotional release of panic. If the Heart Fire becomes weak, the Kidney Water rapidly draws downward and freezes. Insecurity, hesitation, immobility, and paralysis ensue. If the Heart Fire become Deficient, it cannot radiate warmth, causing the patient to crouch and hide.



Figure 53.8. Fear causes the Qi to move inward and downward.

If the Kidney Yin is Deficient, the vision deteriorates, there is a ringing in the ears, dizziness, night sweats, and nocturnal emissions. If the Kidney Yang is Deficient, the Mingmen Fire becomes Deficient, and causes a counter-flow of energy affecting the hearing. Kidney Yang Deficiency also results in shortness of breath, cold limbs, and impotency. When the Kidney Qi becomes Excessive, swelling occurs and the Five Yin Organs become unstable. The feelings associated with the Kidneys are fear, paranoia, and panic.

THE YIN AND YANG ASPECTS OF THE KIDNEYS

The Kidneys' negative nature is arrogant, troublesome, and ignorant; the positive nature is peaceful, soft, and tender. Fear can cause loss of Bladder control, weakening of the knees, renal failure, and permanent damage to the Kidneys. It can injure the Heart, affecting the speech, eyes, and the Shen.

When fear injures the Kidneys, this can affect the Liver, causing muscle spasms, trembling, and disruption of the menses cycle. When the Gall Bladder is affected, decision-making becomes more difficult.

THE ENERGETIC PATTERN OF FEAR

The energetic pattern of fear is very cold and implodes into the center of the body, drawing all the energies inward and downward. Fear travels from the eyes down the front of the body into the groin (Figure 53.8).

Because Earth absorbs Water, contemplation controls fear. Therefore, the doctor can help the patient control the fear through visualization and meditation. The purpose of the visualization is to resolve and reprogram the patient's thinking patterns.

THE EMOTION OF FRIGHT

The emotion of fright is distinguishable from fear by the sudden, unexpected shock to the system. The Chinese character for fright (Ju) is depicted by the ideograph of a small bird opening its frightened eyes, in fear, anxiety, and dread. Fright startles the Shen, which then scatters the Qi and injures the Heart. Persistent fright causes damage to the Kidney Qi and results in a negative cycle of chronic fear.

FIVE YIN ORGAN EMOTIONAL RESPONSES

The common ingredient in any emotional dysfunction is the power element maintaining it. Holding on to original traumas, whether consciously or unconsciously, requires a great deal of energy. It is possible to stop this negative pattern by releasing the toxic emotional energy, thereby creating the opportunity for the mind, body, and spirit to heal. A new pattern of harmonious balance can be maintained, however, only after the old dysfunctional patterns are consciously recognized during their occurrence. Old habits die hard; new patterns require time and continuous effort before becoming as automatic as the previous dysfunctional habits. Every emotion is meant to serve a positive function, even anger, fear, and grief. Patients often require reminding of this fact. Every emotion also has its darker side when repressed for too long and when avoided at all costs.

1. Learning how and when to express anger is as important as not holding on to it for extended periods of time. Anger serves as a warning sign that personal boundaries are being violated, threatened, wounded, or that injustices are being committed. Patients must be taught better communication skills so they need not resort to screaming or insulting others to protect themselves. Appropriate assertiveness skills must be learned, and may require either psychotherapy, or classes in assertiveness training. Patients must also learn how to ask for what they need and desire, without expecting those close to them to mind read. Without learning how to set appropriate boundaries, without the ability to say "no" to those who take advantage of them, they will fall into the old habit of accumulating resentments; or they will alienate their employer, friends, and family through unguarded candor when angry.
   - On its negative side, anger can cause rage and destructive patterns (both internally and externally).
   - On its positive side, anger can cause constructive boundary setting and the righting of wrongs.
2. Fear, like anger, serves as a warning sign. Fear informs patients when they are in danger, so that appropriate measures can be taken to insure safety and survival. Some patients do not recognize the danger signals until it is too late to avoid falling victim to unscrupulous people. Some may require counseling and instruction in how to establish healthy relationships, and in how to identify individuals who are potential abusers before it becomes too late to avoid the ensuing violence.
   - On its negative side, fear can cause disabling panic.
   - On its positive side, fear can cause an awareness of the need for self-protection.
3. Joy in excess can lead to disharmony. Nervous laughter, or always playing the clown to gain acceptance, can be extremely difficult to unlearn. Often professional help is needed to increase socialization skills and self-esteem.

2. Crown

Repeat the Middle Thrusting Channel to the mideyebrow, and continue to thrust the pearl up through the pituitary gland to the pineal gland at the crown. Practice nine times. Rest, and mentally trace the complete Middle Thrusting Channel.

C. Right Thrusting Channel to the Crown

1. Right Eye

Repeat the Right Thrusting Channel procedure as described to the neck and continue thrusting to the right eye.

2. Crown

Repeat the Right Thrusting Channel to the right eye, and continue thrusting the pearl up to the right hemisphere of the brain and then to the crown. Practice nine times. Rest and trace the route mentally from the perineum to the crown.

D. Continue to Practice the Three Thrusting Channels to the Crown

Continue to practice the three Thrusting Channels to the crown nine times as was delineated for the diaphragm and again for the neck: left, middle, right, middle, left, middle, right, middle and left.



Fig. 7.12 *Three Thrusting Channels up to the Crown*



Figure 53.9. The Five Element Cycles

- On its negative side, joy can cause hysteria.
- On its positive side, joy can be a source of happiness to the spirit.

4. Sorrow is necessary at times to motivate patients to change. The old self must periodically die to make room for new experiences and learning. Risking sorrow is part of the process of bonding and maturing. Sadness is often a signal of imbalance in the patient's life, indicating insufficient rest or recreation, and far too much work.
    - On its negative side, sorrow can cause self-pity, rather than compassion for oneself.
    - On its positive side, sorrow can release distress.
5. Worry and anxiety are normal reactions to change. When these emotions become pathological in intensity of duration, patients may need professional help in the form of medication (e.g., for obsessive compulsive disorders), and/or psychotherapy (e.g., in the case of generalized anxiety disorder and posttraumatic stress disorder).
    - On its negative side, worry can cause great anxiety.
    - On its positive side, worry can be a motivating source for change.

The healing stages used in Medical Qigong Therapy employ these transitions in order to assist the patient's emotional and spiritual growth.

The picture in Figure 53.9 summarizes the Five Elements, their associated organs, and their associated emotions.

The cycles serve a functional importance for emotional transitions. The elements can be arranged in a number of ways. For clinical purposes, the main emphasis is on the Creative and Controlling Cycles.

EMOTIONAL DISHARMONY

It is becoming more common in the Western belief system that if a patient concentrates his or her mind and emotions on healing the illness, they can accelerate the recovery. Some Western research suggests that when the patient stops thinking and trains the mind to relax (reaching an alpha state), the healing is accelerated.

Emotional disharmony can resonate and penetrate one's entire being, thereby creating a vicious

Major Organ Disharmony	→	Emotional Disharmony
↑		↓
Environmental Disharmony	←	Disturbed Behavior

Figure 53.10. The Cycle of Emotional Disharmony

circle affecting the body, mind, emotion, energy, and spirit. As evidenced by the diagram (Figure 53.10), any disharmony in one of these four factors can trigger the cycle.

This vicious circle can be set in motion by any major disharmony, be it environmental, physical, emotional, or behavioral. Once in motion the disease can feed on itself. The power of emotional energy generated can at times overwhelm the conscious mind. The mind then has three options: to give in to the emotional tidal wave, to become eventually paralyzed through the effort of controlling it, or simply to deny that anything is wrong.

When emotional energy is suppressed it accumulates within the body, causing the Qi to flow incorrectly or to condense. The unresolved emotions cause chronic blocks in the body, particularly in the back, neck, Stomach, and intestinal areas. This toxic energy stored in the muscles and organs leads to tension, stress, and illness. The root cause of chronically tense shoulder muscles, for example, can be traced to: tensing the muscles to suppress the emotion(s), a strong negative belief system, and an accumulation of unresolved past traumatic memories, which continue to resurface.

Unless the initial cause of tension is released, the tissue memory associated with the initial trauma will repeat its programmed pattern, resulting in chronic tension and pain. Painful and negative emotions are not the only emotions suppressed. Many people also suppress feelings of joy and love. Most do so out of fear, guilt, and sense of unworthiness. Some do so out of religious beliefs, believing that suffering is good for the soul, or that the are being punished by God for sins of omission and / or commission to test their faith.

All emotions are triggered by sensory associations with pleasant and unpleasant past memories. In many cases patients are completely unaware of the triggering smell, image, sensation, or sound. To them it seems that the trauma, or memory, resurfaces from nowhere. This inability to pinpoint the trigger mechanism may indicate the progression of the patient's illness. Patients suffering from panic attacks, for example, have no idea what stimulus may have caused the overwhelming terror that they feel. Quite often panic attacks increase in frequency, partly out of the anticipatory fears of having another one, and partly due to their fear spreading and generalizing.

The first panic attack may have taken place in a restaurant, triggered by one of the five senses registering similar data (a smell or image for instance) which occurred during one of their traumatic memories. Henceforth they will avoid this restaurant, or perhaps all restaurants because new data has been added to the original trigger mechanism. New smells and images occurring during the attack may now stimulate the old memory of the trauma. Eventually, such patients may become home bound as they try to limit themselves to only safe places; their panic attacks have generalized to agoraphobia (fear of places or situations from which escape might be difficult or embarrassing). Each panic attack requires more energy to suppress both the original trauma and all of the new traumas added to it from surfacing.

Outgoing, successful people can thus transform themselves into anxiety ridden hermits. They can also develop physical symptoms, or turn to alcohol and drugs in attempts to cope. In less extreme mental / emotional diseases, changes in skin colors, tone of voice, mannerisms, and nervous twitches may manifest. As the mind tries to suppress uncomfortable emotions, these unresolved feelings often manifest as physical symptoms.

At times, however, the symptoms manifest more on the mental level, as in obsessive compulsive disorder. The logical mind, failing to completely suppress the emotion, may develop frantic obsessive thinking patterns, that seem to take on a life of their own. Some patients may obsess about dying, even if they seem by Western medical standards to be physically completely healthy; or they may obsess about killing their own child, or forgetting to lock all the doors when leaving the house and so on. They have no control over their repeating thoughts, and are aware of the unrealistic and unreasonable nature of these obsessions. Nevertheless, they are helpless to stop themselves.

Obsessions often manifest with compulsive addictions such as washing the hands so often during the day that they are raw and bleeding, or pulling out the hair on their head, or folding and unfolding their clothing. Any ordinary daily activity may turn into a compulsion, requiring the patients to continue performing a meaningless action again and again.

Another frequent disease found in traumatized patients goes by the name of posttraumatic stress disorder. Patients suffering from this condition have flash backs, i.e., they can not stop having moments of releasing the original traumas again and again with full intensity.

In posttraumatic stress disorder patients' symptoms are often disabling. Anxiety is chronic, they are in a state of hyper-alertness. They have become good at disassociating from their body, since it has become a very uncomfortable place to be. The Shen wanders and the patients may, or may not, be aware of where their spirit goes or what it experiences at these times. In extreme cases the ego fractures, usually during early childhood, and a full blown identity disorder (previously called multiple personality disorder) ensues.

Patients suffering from obsessive compulsive disorders, posttraumatic stress disorder, agoraphobia and panic attacks, or identity disorders should be referred out for extra help to a mental health professional specializing in these disorders.

Ideally, the doctor can teach and encourage the patient to get in touch with their body, and learn how to achieve and maintain a balance between the physical, mental and emotional planes. The doctor can also teach the patients how to transition detrimental energy into a higher level of consciousness, when the patients become aware of an unpleasant emotion. When patients learn how to channel their own energy in a more healthy way, the cycle of reliving the past can be broken. A negative emotion can be transmuted and expressed as a positive emotion; emotional energy can be converted to positive life-force energy.

EMOTIONAL FREQUENCY RESONATION

When the Qigong doctors are appropriately sensitive to the patients' emotional transitions, they are able to detect, and recognize, recurring energetic patterns. These energetic patterns are in constant resonation throughout the body's tissues. As patients shift their emotional thinking, their energetic frequency resonation (the body's Hz rhythm) shifts. These different emotions establish specific patterns of energy in the body. Each individual has a brain wave pattern that is as unique as their fingerprints. According to Richard Lee, director of the China Healthway's Institute, individuals resonate at different frequencies depending on their state of consciousness. Mr. Lee's research reveals the following.

1. Those motivated by fear and instinct will resonate at the delta wavelength, between 0 and 4 Hz (hertz, i.e., cycles per second). This level of energetic resonation, as measured by an electroencephalograph (EEG), is normal in an awake infant and a sleeping adult. This delta wavelength, however, indicates brain pathology in adults that are awake.
2. Those motivated by attachment and desire will resonate at the theta wavelength, between 4 - 7 Hz. This level of energetic resonation is generally common in children and in adults in the early stages of sleep. This frequency range also occurs when an individual creates mental imagery, and often manifests when a person is involved in deep altered states of consciousness. This level of energetic resonation also occurs in many brain disorders.
3. Those motivated by service and compassion will resonate at the alpha wavelength, between 8 and 13 Hz. These low amplitude alpha waves usually occur when the brain is in a calm, and the mind is relaxed (in a state of wakefulness). It was discovered that Qigong masters emit energy within this frequency range.
4. Those motivated by organization and planning will resonate at the beta wavelength, between 14 and 25 Hz. This level of energetic

resonation usually occurs when the nervous system is active and the body is awake. It manifests during sensory input and mental activity. This frequency range is usually common for those suffering from nervous overload and excessive thinking.

When the patients' vibratory rate shifts towards the alpha rhythm, they begin to experience deep relaxation and clarity of mind. Relief from chronic pain and symptoms associated with low energy is achieved.

According to Richard Lee, the infrasonic sound produced by Qigong masters is effective because it causes decreased resonation in the theta and beta ranges. This simultaneously decreases attachments and desires, calms the emotions, and reduces excess thinking, thereby freeing the patient's vital sources to be redirected towards healing.

DIFFERENTIATION OF PSYCHO-EMOTIONAL DISORDERS

Traditional Chinese Medicine has, for centuries, recognized the fact that psycho-emotional states, energy, and physical health are intertwined. In the Huang Di Nei Jing, the emperor's medical adviser, Qi Po, outlined the Internal Factors (emotions) as primary causes of disease.

Within the context of Traditional Chinese Medicine, Medical Qigong therapy is useful for treating many types of psycho-emotional disorders. Qi emission therapy can be used to calm the patients' Shen, as well as accelerate the patients' recovery time. In China, psycho-emotional problems are commonly called Jing Shen disorders and are differentiated as follows: Obstructed Shen, Unsettled Shen, and Weakened Shen.

1. Obstructed Shen is a condition due to the Shen becoming obstructed with Phlegm, or in mild cases, becoming obstructed by Qi or Blood. Symptoms are characterized by confused thinking, clouding of the mind, and in severe cases, complete loss of touch with reality. Degrees of severity range from very mild disorders to severe schizophrenia or mania.
2. Unsettled Shen is a condition due to the Shen becoming unsettled from Blood or Yin Deficiency (in mild cases), Qi stagnation, Blood Stasis, Fire, Empty Heat, Phlegm Fire, or Internal Wind. Symptoms are characterized by agitation, restlessness, and anxiety.
3. Weakened Shen is a condition due to Deficiency of Qi, Yang, Blood, or Yin. Symptoms are characterized by depression, mental exhaustion, and melancholy (dysthymia).

ETIOLOGY

The cause for psycho-emotional disorders can range from a variety of factors, including prenatal or postnatal constitutional imbalance, diet, unbalanced sexual activity, overwork, alcohol or drug abuse, trauma, stress, emotional immaturity, and instability, as well as a lack of love or spiritual perspective.

TREATMENT PRINCIPLES

There is a considerable degree of overlap among Jing Shen disorder symptoms. Therefore, the treatment principle must be based on a clear distinction between Excess and Deficiency, as well as the cause (root) and manifestation (branch) of the symptoms. The main treatment principles are as follows:

1. Nourish the Heart and calm the Shen to treat Shen weakness due to Qi, Yin, Yang, Blood, or Body Fluids Deficiency.
2. Purge the Excess, move stagnation, and calm the Shen to treat Shen obstruction or Shen agitation (unsettled Shen) due to Excess conditions of Qi, Blood, Phlegm, and/or Fire stagnation.
3. Purge the Excess, nourish the Heart and calm the Shen to treat Shen obstruction due to Yin Deficiency with Empty Heat.
4. Resolve the Phlegm, open the Heart's orifices, and calm the Shen to treat Shen obstruction due to Phlegm or Phlegm Fire.
5. Sink and calm the Shen to treat unsettled Shen due to rising Qi.

The term "calm the Shen" is used to describe the treatment principles in all psycho-emotional disorders. It should be understood to mean not only calming the mind, as in anxiety, but also lifting the patient's mood (as in depression), or clearing the mind (as in schizophrenia or mania).

SELF-TREATMENT PRESCRIPTIONS FOR PSYCHO-EMOTIONAL DISORDERS

Most meditations are difficult for patients with psycho-emotional disorders due to several factors. One factor is the problem of maintaining focused attention, as well as retaining the memory of specific medical Qigong prescriptions. The success, or failure of the treatment will also depend on the severity of the disorder.

POINT MEDITATION FOR EMOTIONAL TRAUMA

In China, Channel Point meditation is used in conjunction with the Massage Tapping method for treating patients with conditions such as anxieties, phobias, and addictions. In acupuncture, 135 of the original 365 acupuncture points are used to treat mental, emotional, energetic, and spiritual disharmonies. In fact, many of the "new" points can be applied for the treatment of Jing Shen disorders.

The cause of fear and anxiety is the disruption to the body's energy system from emotional trauma. When a patient is focusing on a particular anxiety or fear, the Shen becomes disrupted, and the energetic harmony of the body becomes unbalanced. This energetic imbalance causes certain physical reactions within the patient (abnormal breathing, pulse, etc.), and results in pathological behaviors.

TREATING EMOTIONAL ANXIETIES, PHOBIAS, AND ADDICTIONS

To treat anxieties, phobias, and addictions, the doctor encourages the patient to focus attention on the specific fears, or cravings for the particular addiction, to initiate a maximum emotional charge of distress. When the patient reaches maximum emotional distress, the doctor calls out specific channel points for the patient to tap.

The patient is given a specific mantra to repeat while tapping, to discharge the accumulated emotionally charged Qi, such as; "I accept this fear (or other emotion or craving)" or "I am being healed." The treatment continues for five to ten minutes, as the patient focuses on feeling the distress as much as possible, until all the trapped emotion has been discharged. Some energetic points commonly chosen for treating emotional anxieties, phobias, and addictions are GV-26, Ht-7, and Pc-6. These specific points are used to draw the energetic charge away from the Heart and into the extremities; this action facilitates calming the patient's Shen.

The initial tapping method, in conjunction with vivid imagination and positive affirmation, disperses the energy away from the Heart and other organs and calms the Shen. The spontaneous dispersing of the emotional charge, stored within the patient's tissues, releases all feelings of stress and anxiety. This type of guided Tapping Meditation therapy not only reduces and disperses the patient's emotional trauma, but also causes an energetic reprogramming within the patient's psychophysical dynamics.

MEDICAL QIGONG TREATMENT OF THE PHOBIA AND ANXIETY OF DEMON POSSESSION

These specific treatments are used in China to treat specific mental, and emotional disorders, that lead the patient to imagine that they are being haunted by spirit demons. In rectifying this type of psycho-emotional disorder, it is recommended that the Qigong doctor proceed as follows.

1. Perform Channel Point therapy to open the energetic points of the Eight Extraordinary Vessels (Figure 53.11).
2. Press and knead the Baihui GV-20, Dazhui GV-14, Lingtai GV-10, and Feishu Bl-13 points. Then apply the Extended Fan Palm or Sword Fingers method (see Chapter 33), using the Pulling and Shaking manipulations (see Chapter 34) to emit and conduct Qi along the Governing Vessel.
3. Press and knead the following channel points Baihui GV-20, Yintang (Ex.Pt.), Renzhong GV-26, Tinggong SI-19, Jiachè St-6, Quchi LI-11, Hegu LI-4, Weizhong Bl-40, and Chengshan Bl-57 points.
4. Apply the Sword Finger technique, using the Vibrating and Shaking manipulations to emit Qi into the Jiuwei CV-15 and Zhongwan CV-12 points and conduct Qi along the Conception Vessel to return it to the Lower Dantian.

MEDICAL QIGONG TREATMENT FOR SPECIFIC SPIRIT/GHOST HALLUCINATIONS

These specific treatments are also used in


GV-20
Yin Tang
SI-19
St-6
GV-26
SI-19
St-6
CV-15
CV-12
LI-11
LI-11
LI-4
LI-4
GV-20
GV-14
Bl-13
Bl-13
GV-10
Bl-40
Bl-57

Figure 53.11. Medical Qigong Channel Point Therapy for the Treatment of Energetic Delusions

China to treat specific mental and emotional disorders that lead the patient to see spirit/ghost hallucinations. The Qigong doctor may additionally treat the patient according to the following therapeutic point stimulation:

- If the patient is disoriented, sees and hears floating corpse ghosts, or hears crying ghosts, treat the Tianfu Lu-3 points.
- If the patient is manic-depressed, sees and hears ghosts talking, treat the Tianchuang SI-16 points.
- If the patient is having seizures, sees and hears ghosts talking, treat the Tianzhu Bl-10 points.
- If the patient is manic, suicidal with incessant wild talking and actions, treat the Fengfu GV-16 point.
- If the patient experiences chronic nightmares, confused dreaming, and restless sleep, treat the Tianyou TB-16 points.

MEDICAL QIGONG TREATMENT FOR DEMON OR SPIRIT POSSESSION

Since the creation of Traditional Chinese Medicine in the People's Republic of China, the notion of spirits has been down-played. However, within the confines of the Medical Qigong clinics, I have been fortunate enough to be able to discuss with several Qigong doctors the cause, effect, and treatment of demon and spirit possession.

These following Thirteen Ghost Points are listed in the *Thousand Ducat Formulas*, prescribed by the famous physician Dr. Sun Simiao in the 7th century China, and were once used for the treatment of spirit possession (Figure 53.12). Today in China, these points are now used in the TCM clinics for the treatment of manic and depressive mental disorders, as well as for treating epilepsy. In extreme manic cases (with Heat) the doctor bleeds all of these points as well as all twelve Jing-Well points on the patient's hands. Classically, the patient is treated by bleeding each of these points, or by inserting an acupuncture needle into each point and then immediately withdrawing it. These Ghost Points are stimulated in a sequence of progressive point therapy, wrapping and enfolding the patient's body in five consecutive circles.

1. The Guigong (Ghost Palace), also known as the Renzhong GV-26 (Middle of Man) point, is the first point to be stimulated and is treated to calm the Shen and clear the brain.
2. The Guixin (Ghost Faith), also known as the Shaoshang Lu-11 (Lesser Metal's Note) points on both thumbs, are treated to calm the Shen and restore Collapsed Yang.
3. The Gullei (Ghost Fortress), also known as the Yinbai Sp-1 (Hidden Clarity) points on both big toes, are treated to calm the Shen, clear the brain, in order to instill clarity of thought and mind.

These first three points are used to complete the energetic pass of the first circle, covering the head, tips of the thumbs and tips of the big toes. The GV-26 point is considered the meeting point of Yin and Yang in the body, while the Lu-11 points on both hands and the Sp-1 points on both feet are located on the body's Hand and Foot Tai Yin Channels.

Next, the following two points are used to complete the second circle:

4. The Guixin (Ghost Heart), also known as the Daling Pc-7 (Big Mound) points on both wrists, are treated to calm the Shen and clear the brain.
5. The Guilu (Ghost Path), also known as the Shenmai Bl-62 (Extending Vessel) points under both outside ankles, are treated to calm the Shen.

The Ghost Heart and Ghost Path points complete the energetic pass of the second circle, covering and wrapping the patient's wrists and ankles. The Pc-7 points on the wrists are located on the body's Hand Jue Yin, and the Bl-62 points on the outside of the ankles are located on the body's Foot Tai Yang Channel points.

The following set of four points are stimulated to complete the energetic pass of the third circle:

6. The Guizhen (Ghost Pillow), also known as the Fengfu GV-16 (Wind's Palace) point just below the occiput, is treated to clear the brain.
7. The Guichuang (Ghost's Bed), also known as the Jiache St-6 (Jaw Vehicle) points on both sides of the jaw, are treated to dispel Wind and Cold and to clear Heat.
8. The Guishi (Ghost Market), also known as the Chengqiang CV-24 (Receiving Liquid) point under the lower lip, is stimulated to treat mental disorders, dispel Wind and Cold, clear


GV-23
GV-26
St-6
St-6
CV-24
LI-11
Lu-11
Lu-11
Pc-8
Pc-8
Jade Gate
Sp-1
GV-16
Pc-7
CV-1
Bl-62
Bl-62

Figure 53.12. Medical Qigong Treatment for Spirit Possession

Heat, and to transform Dampness and Phlegm.

9. The Guicu (Ghost Cave), also known as the Laogong Pc-8 (Palace of Labor) points at the center of both palms, are stimulated to treat mental disorders and to clear the brain.

These four points complete the energetic pass of the third circle, by covering and wrapping the patient's head, then drawing the energy into the center of the patient's palms. The GV-16 point on the back of the patient's head is located on the back gate of the Upper Dantian, the St-6 points are located on the sides of the mandible, and the CV-24 point is located in the depression in the center of the patient's mentolabial groove (jaw).

The next two points complete the energetic pass of the fourth circle:

10. The Guitang (Ghost Hall), also known as the Shangxing GV-23 (Upper Star) point, is treated to brighten the Shen and clear Heat.
11. The Guicang (Ghost Store), also known as the Yumentou (Jade Gate) in women, and Yinxiafeng (Below the Hidden Seam) in men, is used to treat mental disorders. The Jade Gate is located at the opening of the vagina, the Below the Hidden Seam is located in the Huiyin area in men.

These two points complete the energetic pass of the fourth circle, by covering and wrapping the patient's body from the head to the lower perineum. The GV-23 point is located on the anterior hairline, at the top of the patient's forehead, and the Ghost Store point is located in the lower perineum.

The following two points are stimulated to complete the fifth energetic pass:

12. The Guitui (Ghost Leg), also known as the Quchi LI-11 (Crooked Pool) points, are treated in order to drain the pathogenic influences from the Lungs and to calm the Po (Corporeal Soul).
13. The Guifeng (Ghost Seal), also known as the Haiquan (Sea Spring) and She Xia Zhong Feng (Under Tongue Middle Frenulum) are two Extra points located below the tongue. They are stimulated in order to treat mental disorders.

These final two points complete the energetic pass of the fifth circle, by covering and wrapping the patient's body from the arms to the head. The LI-11 points are located in the depression on the lateral end of the elbow crease, and the Haiquan Sea Spring points are located under the tongue.

TREATING PHOBIAS AND DEPRESSION USING "THE WINDOWS OF THE SKY" POINTS

If we observe the body as a figure 8, with the head being the upper portion and the torso being the lower portion, the neck would represent the area where the two circles meet. The points and orifices of the head, face and neck are like great windows in which Qi moves.

The trunk of the body is considered Earth and the realm of the physical; the head pertains to Heaven and the realm of the spirit. The neck is where all of the classic "window" points are located. The neck is the junction between Heaven and Earth, and is considered the Earth's window to Heaven. With the exception of Lu-3 (upper arm) and Pc-1 (chest), eight of the ten Windows of the Sky points are located on the neck itself, and seven of the ten points have the word Tian (Heaven) as part of their name.

Over the last quarter century, the Chinese have used the Windows of the Sky points in treating such psychological disorders as depression and phobias. In the Qigong clinic, we look for three indications before prescribing the Windows to the Sky points.

1. According to the Nei Jing, the Windows of the Sky points are used when the Yang Qi is unable to ascend to the patient's head. The result is that the patient will have physical symptoms in the head or Heart (i.e., loss of hearing, or pain described as being behind the Heart.
2. The second indication is that there is something missing in the Heavenly aspect of the patient's spiritual life. When the patient becomes stuck in their own negative patterns, these particular points can be used to open a window of hope by bringing into the patient's body the illuminating light from Heaven.

   In these cases, the patient's disconnection from emotions and spiritual insight is due to the chronic negative patterns that block the descent of Heavenly light.

3. The third indication is a constant attitude of despondency by the patient. This behavior is not in accordance with his or her own values and beliefs, but the patient cannot control this pattern. Some patients know that something is amiss but cannot discern the source of the problem.

The Window points induce a hypnagogic state (a transitional state between sleeping and awaking) that allows some patients to experience out-of-body projection and past life regressions.

TREATMENT

When treating patients with the Windows of the Sky points, the Qigong doctor should use slow, gentle pressure on the skin to dip into the tissues, and then proceed with pure intention. The ten Windows of the Sky points are described as follows.

1. The Tian Fu Lu-3 (Heaven's Residence) point is sometimes called the Celestial Palace. The word Heaven represents divinity, clarity of vision, and the sense of the spirit (Figure 53.13). This point has a powerful psychological effect on all emotional problems deriving from Lung Qi disharmonies (e.g., depression, claustrophobia, agoraphobia, mental confusion, and forgetfulness).
2. The Fu Tu LI-18 (Support the Prominence) point is also known as Support and Rush Out. It is used on patients who feel out of touch with their own inner strength (Figure 53.14). This point relieves coughing, resolves Phlegm, and disperses masses (cysts and tumors) in the neck area. It is also used to treat a patient's inability to speak.
3. The Tian You TB-16 (Heaven's Opening) point can be used to calm the patient of anxieties and to soothe Heart palpitations (Figure 53.15). This point is also used for dizziness, sudden deafness, and diminished visual acuity.
4. Tian Zhu Bl-10 (Heaven's Pillar) is a Sea of Qi point. It is used to clear the brain, open the orifices, brighten the patient's eyes, and re-



Figure 53.13. Heaven's Residence



Figure 53.14. Support the Prominence



Figure 53.15. Heaven's Opening

You now have succeeded in bringing the pearl through the Thrusting Channels to the crown. Your goal is to follow the sequence above using nine thrusts distributed among these three channels. Be aware of how and where the energy flows through the three Thrusting Channels, and how the three channels penetrate all the organs and glands. These channels are very powerful. They clean, detoxify and purify the organs at a much deeper level.

E. Bring the Pearl into the Microcosmic Orbit

When you have finished this stage of practice, you can bring the pearl into the Microcosmic Orbit and circulate it. Feel the Microcosmic Orbit encircling the Thrusting Channels. The top and bottom of the Thrusting Channels are joined with the Microcosmic Orbit at the crown and the perineum.

Use your mind to assist the flow of energy through the Thrusting Channels and through the Microcosmic Orbit when the pearl reaches the crown point or the perineum point.

Your Microcosmic Orbit practice will change dramatically after you learn the Fusion of the Five Elements meditations. When you first practice the Microcosmic Orbit, the energy you move through your channels is raw energy. By contrast, when you reach the level of Fusion practice, the energy is more refined and condensed, and it is therefore much more powerful. The Fusion practice includes the Microcosmic Orbit, so it might be said that the Fusion meditation is simply a more advanced way of practicing the Microcosmic Orbit meditation.

Practice this stage for two or three weeks until feel you have gained control of the energy.

5. Extending the Three Thrusting Channels above the Crown

Once we have purified and transformed the negative energy of the organs back into usable life-force energy (Fusion of the Five Elements), distilled this energy along with the virtue Chi of the organs into the pearl (Cosmic Fusion), and opened all our reservoirs or special channels, giving us a larger energy capacity, we can increase our virtue energies further by connecting with the external sources of Five Elements Chi and directing the external Chi toward its associated organs. Moving the pearl out of the physical move obstructions from the channels. The energy that moves and is located at these points has to do with the patient's will, ambition, and inner fortitude (Figure 53.16). Energetic dysfunction located at the Heaven's Pillar may manifest as deep sadness or anxiety, and be related to a lack of inner strength, or will. This point is also used when the patient's feet are unable to support the body.

5. Ren Ying St-9 (Man's Welcome) is a Sea of Qi point. The ancient Chinese philosophers associated this area of the body with Man in the triad of Heaven, Man, and Earth. This point is known as a place where energy is being welcomed into the body (Figure 53.17). It is a very sedating point of Blood and Qi, and is used to reduce blood pressure. Opening up this point allows the patient to become receptive to nurturing energy (Ying Qi). The doctor should be gentle and only treat one side at a time. It is also used to disperse Lung Qi and Regulate Qi.
6. The Tian Tu CV-22 (Heaven's Rushing Out) point is also known as the Celestial Chimney, and is an area where the body's internal energy and spirit leaves the body through sound (Figure 53.18). Heaven Rushing Out is related to emotional and spiritual expression, and is relevant when the patient's spiritual self (i.e., the individual's life purpose) is not being supported by physical actions (his or her code of conduct). In other words, the patient's life purpose is not in alignment with the patient's behavior. This point can also be used to regulate the Lungs, stimulate the descending action of the Lung Qi, clear Heat, and resolve Phlegm.
7. Feng Fu GV-16 (Wind's Palace) is a Sea of Marrow point, and is also a very good point for strengthening the body's Wei Qi (Figure 53.19). This point connects directly to the brain, and is used to eliminate Wind, clear the mind, open the sensory orifices, and benefit the energetic function of the brain (used for treating convulsions, epilepsy, or palsy).
8. The Tian Chuang SI-16 (Heaven's Window)



Figure 53.16. Heaven's Pillar



Figure 53.17. Man's Welcome



Figure 53.18. Heaven's Rushing Out



Figure 53.19. Wind's Palace

point is used to open a window to Heaven, especially in patients who need help in perceiving how to change a negative behavior pattern into a productive and harmonious one (Figure 53.20). This point is used for dispersing the Liver's Qi and for eliminating buzzing, pain, or deafness of the ears.

9. The Tian Rong SI-17 (Heaven's Appearance) point is also known as the Celestial Countenance. This point is where the Small Intestine's Channel Qi is received by, and enters into, the Heaven's Body Chamber (the head or skull). It can be used to produce a strong movement of energy from the head downward into the body.

   This point is used in spiritual emergencies, when patients have lost their connection with Earth energy, and remain blissed out, and oblivious of reality. It is often used in cases of addictions, once the patient is conscious of the addiction (Figure 53.21). This point is also used in order to expel Excess Fire and remove obstructions from the patient's channels.

10. The Tian Chi Pc-1 (Heaven's Pond) point is also known as the Celestial Pool. The term pond represents a source, resource, or reservoir of energy for the spirit. This point influences the area where the Shen gathers or pools in the chest region (Figure 53.22). It is capable of enhancing the transition from normal consciousness to feelings of being submerged in a sea of energy.

    It affects the Heart and Pericardium which govern the Shen, and whose symbolic home is Heaven. The doctor uses this point to remove the patient's street armor, and to begin the process of opening the patient's Heart protector at its source. This point is also used to disperse the Lungs' Qi, expand and relax the chest, regulate Qi, and clear Heat.

    Note: Because of the proximity of the breast tissue, the Heavenly Spring points (Pc-2) are sometimes used in women instead of the Heaven's Pond points (Figure 53.23). The Heavenly Spring point is located halfway down the anterior face of the biceps muscle.



Figure 53.20. Heaven's Window



Figure 53.21. Heaven's Appearance



Figure 53.22. Heaven's Pond



Figure 53.23. Heavenly Spring

TREATING PSYCHO-EMOTIONAL DISORDERS RELATED TO STRESS

The following prescriptions are used in order to assist the patient in dealing with suppressed anger and grief, for additional prescriptions used in order to treat emotional problems (see Chapter 19).

TREATING EXCESS LIVER FIRE AND THE REPRESSION OF ANGER

One of the most common problems observed in the clinic is Excess Liver Fire. One of the many causes of Excess Liver Fire is the repression of anger and a suppression of the spiritual components of the Hun. When anger is suppressed, its volatile Heat will sometimes attack and drain the Kidney Yin (Water). Therefore, Excess Liver Fire is generally related to a Deficiency of the Kidney Yin energy. When Qigong doctors reduce the Excess Liver Heat, they must also increase the patient's supply of Kidney Yin (Water) Qi (see note #2).

If the Liver's Yin becomes Deficient, the body's Qi will not be able to keep the patient's Internal Fire from rising. This causes the Yang to rise to the patient's head, and the Blood to become Deficient. The patient becomes irritable as the Liver's Yang begins to rise. This in turn, causes high blood pressure, which is associated with such problems as headaches, dizziness, insomnia, tinnitus, hypertension, and migraine headaches. Deficient Liver Yin, if unchecked, turns into Liver Fire, which causes severe high blood pressure, and heats the patient's Blood. As the Blood heats, it becomes Deficient, and causes Liver Wind. Unchecked Deficient Liver Yin results in shaking and trembling. If the Liver Wind mixes with the patient's Phlegm, it blocks the patient's channels resulting in paralysis, aphasia, memory problems, and eventually stroke.

The method of treatment is chosen according to the patient's syndromes:

1. For patients sensitive to energy, use Medical Qigong therapy while the patient is lying supine.
   - Purge and disperse Qi from the patient's Liver;
   - Pull pathogenic Qi out the patient's Liver Channels;
   - Tonify the patient's Kidneys through the Lower Dantian;
   - Give Liver purging and Kidney tonification prescriptions and homework.
2. For patients not sensitive to energy, use Tui Na and An Mo in conjunction with Medical Qigong therapy while the patient is lying prone.
   - Purge and reduce the Fire in the patient's Governing Vessel and Bladder Channels;
   - Start at the Mingmen and dredge the patient's Liver Fire, ending at the sacrum, using a counterclockwise circle rotation to reduce the Liver's Qi;
   - Give Liver purging and Kidney tonification prescriptions and homework.

Note #1. If the Liver Fire attacks the Stomach, resulting in vomiting and migraine headaches, have the patient lie supine. Because the Liver's Fire can travel transversely along the hypochondrium area, the Qigong doctor rocks and gently shakes the patient from the center of the thorax down to the Kidneys using intention, lead and disperse the Heat out from the patient's torso. Next, pull the Stomach Qi down and out of the patient's feet.

Note #2. Tonify the patient's Kidneys by using Jing Point therapy on the following points: St-36, GB-34, Sp-6, Lv-3, and Kd-1 on both sides of the body.

BEATING THE BAG AND SHOUTING TO DETOXIFY LIVER HEAT AND RELEASE TRAPPED ANGER AND RAGE

Beating the Bag and Shouting is the most common Medical Qigong homework given to patients with Excessive Liver Fire. The concept of Beating the Bag and Shouting is best comprehended when the function and flow of Liver Qi Heat is understood. When striking the bag and shouting, the shaking movements of the body will:

- facilitate an energetic discharge from the Liver organ,
- help alleviate pressure stored within the Liver organ itself (detoxifying suppressed feelings), and
- purge the body of Excess Liver Heat.

It is important for the patients to understand, that when shouting and striking on the surface of the bag (while focusing their intention deep into the bag's center), they are releasing deep seated pathogenic rage. This is why it is prohibited for patients to substitute such things as pillows, bed, etc., for the bag. If a patient takes a pillow and pounds it, for example, screaming and shouting to release the aggression, he or she is releasing and discharging pathogenic Qi into the pillow. If after releasing this Toxic Qi into the pillow, it is returned to the bed for a person to sleep on, the patient will reabsorb the discharged energy. To avoid this occurrence, patients are encouraged to set aside a space where they can safely discharge internal pathogenic Qi (preferably outdoors). This is similar to isolating and storing garbage away from living quarters.

While striking the bag, in addition to feelings of anger and rage, sometimes the patient may start crying or experience overwhelming feelings of grief and despair. This is also a normal reaction to dispersing toxic emotion. It sometimes occurs while discharging Stagnant Liver Qi, because the Lungs, which store the emotion of grief, have the function of keeping the Liver organ in check, in accordance with the Five Elemental Controlling Cycle.

What the patient needs to perform this exercise is two wooden dowels (1–1.5 inches in diameter and three feet long), a large bag of rice from the grocery store, and some duct tape. Completely encase the bag of rice with the duct tape to prevent spilling. Place the bag on a table, or a hard surface, level with the Lower Dantian. Hold a dowel in each hand, strike the bag, and focus on the Liver's Qi traveling up the back, down the arms, and through the wooden dowels.

With each impact, imagine the body releasing Toxic Liver Qi into the bag. It is important for the patient to exhale completely and deeply from the lower abdomen when shouting and striking the bag. Sometimes the patient is encouraged to shout "no" or "stop." These words will help the patient to facilitate complete emotional discharging, while also reestablishing a patient's broken energetic/emotional boundary system.

Bag striking should be performed for 10–15 minutes to achieve maximum benefit. Afterwards patients may feel euphoric and exhausted due to the heightened endorphin activity now occurring within the tissues. If the patient still feels angry, he or she should try writing out the rest of the rage on paper, which is then discarded. In order to end the exercise, patients should sit for five minutes in quiet solitude. It is important for the patient to reflect on any emotional memories which have been released and brought back into consciousness. The patient may then begin sharing these feelings and memories with the doctor, and commence the process work for healing the unexpressed emotions.

Some patients may become absolutely horrified at themselves for getting so angry during bag beating that they feel terrified afterwards; especially if so much rage was built up that is seems there is no end to it. Often patients are forced to stop from overwhelming fatigue, aches, and pain caused by this purging exercise. If the patient allows the rage to build and never completely processes the rage, it may cause the patient to feel that without the anger he or she would literally cease to exist, or that he or she is innately evil. The patient may feel that he or she "is" the anger, and that the exercise is making it worse, and may strive to control the anger even more than before.

Some patients will get so mad, they will walk out on the Qigong doctor without processing anything. This unprocessed rage can be extremely dangerous, especially if the patient is prone to beating his or her mate, kids, or pets. Many people are completely unaware of how much anger they have suppressed. Some patients are like bottomless wells, especially patients with borderline personality disorder. Patients with this disorder should never be given this exercise, as it could lead to self-mutilation. Refer such patients out for psychotherapy.

In our culture, women are not allowed to express anger, much less rage. If the patient has ever been beaten, or witnessed a loved one being abused, he or she may believe that he or she is just like the abuser, and that he or she has been lying to him or herself about not being bad and may become suicidal.

The Qigong doctor should never prescribe this exercise unless he or she fully understands the complexity of the patient's circumstances. Some patients require a period of time, in a safe place, with supervision to help them deal with such intense emotions.

Other possible reactions might be that the patient goes into stronger denial of the rage, blames the doctor for causing him or her to beat their mate or children, or blames the doctor for causing the rage. The Qigong doctor must make sure there is sufficient time for the patient to process all the reactions aroused. The patient must not feel hurried.

ANGER MANAGEMENT

With some patients it is best to start them off journalizing the anger, not in a dairy, but on sheets of paper. They address the letters to the person, or persons, with whom they are angry. They continue writing until all the anger has been discharged. They are not to mail the letters, or give them to the addressee, or show them to anyone including the Qigong doctor. In writing the letter, they allow themselves to fully express the anger without judging themselves. The patient should not be concerned about grammar, foul language, etc. No matter how trivial the upsetting incident was, it should be written down. The flow of consciousness is initiated and continued until the end of the letter. No event (no matter how silly or insignificant) that comes to mind should be left unexpressed.

When finished, the letter is to be torn up, or safely burned in a ritual of healing and letting go (e.g., light some incense or candles, then blow them out after the paper has been incinerated). Symbolically the patient must let go of the anger for good, and that is why the letter is destroyed in a ritualistic act.

Only later, as the patient continues to practice this purging technique, slowly gaining control of the emotions, can the angry letters be kept for a few days and reread. In rereading the letters the patient engages his or her discriminating, judging faculties (i.e., "Was I right to get upset over this incident? Did I over-react? What did this incident remind me of from my childhood?"). This is a safe and very powerful method of discharging anger from the patient's body. The patient is encouraged and allowed to say everything he or she thinks of when writing, holding nothing back. It is nonthreatening, and allows the patient to come to understand him or herself better in time.

TREATING STAGNANT LUNG QI AND THE REPRESSION OF GRIEF

The Lungs dominate the Qi and respiration. A common problem observed in the clinic is stagnant, or obstructed Qi within the Lungs, from the toxic buildup of sorrow, grief, and worry. Sadness and sorrow can cause a Deficiency of Lung Qi, while worry can cause the Qi in the chest to stagnate. Stagnant Qi within the Lungs is usually directly or indirectly related to the suppression of emotional issues.

The right Lung is considered more Yang than the left Lung; it therefore tends to reflect, and sometimes manifests physically, any unresolved, or suppressed emotional conflicts experienced within the father-child relationship (or other main male figures in the patient's childhood). These unresolved emotional issues tend to carry over and help shape the nature of subsequent conflicts experienced in other male relationships. These ongoing emotional reactions provide a further opportunity in life to express, work through, and resolve these emotional issues.

The left Lung is considered more Yin and thus reflects emotional issues stemming from the mother-child relationship (or main female figure in childhood). The left Lung may likewise manifest these issues in subsequent female relationships.

Generally, cysts, tumors, or cancer originating in these corresponding regions reflect the emotional history. Because of these emotional patternings, the method of treatment for Lung diseases (that are Internally induced) is chosen according to the patient's syndromes in relationship to the root of the original trauma. After determining the specific Lung which dominates and manifests the patient's pathogenic condition, the Qigong doctor proceeds as follows.

1. For patients sensitive to energy, use Medical Qigong therapy while the patient is supine.
   - Disperse Qi over the patient's throat and Lungs;
   - Purge pathogenic Qi out the afflicted Lung Channel;
   - Tonify the patient's Spleen and Kidneys;
   - Prescribe Homework.
2. For patient's not sensitive to energy, use Medical Qigong therapy in conjunction with An Mo Qi therapy while the patient is supine.
   - Disperse Qi over the patient's throat and Lung area;
   - Purge pathogenic Qi out the afflicted Lung Channel;
   - Dredge Fire from the patient's Liver;
   - Tonify the patient's Spleen and Kidneys;
   - Prescribe Homework.

DRY CRYING TO DETOXIFY STAGNANT LUNG QI AND RELEASE TRAPPED SORROW AND GRIEF

The most common homework prescription given to patients with stagnant Lung Qi is the Dry Crying exercise. The concept of "dry crying" is best understood if we look back to when we were little children. When little children cry hard, they generally release full body resonances. They shake and undulate from the middle of the body, allowing the pain to resonate outwards. When children reach puberty, they learn (through parental or peer pressure) to suppress their feelings, and to restrain full body resonance, by tensing the muscles in the throat. The constant pressures from society, parents and peers, result in self-conscious feelings and shame regarding the loss of control over the emotions. The following exercise allows the patient to experience full body resonation and to release deeply suppressed emotions.

Begin the exercise from a standing position. Stand with the feet more than shoulders width apart, toes pointing straight and the knees comfortably bent. With each hand, touch the thumb to the index finger to form a circle. Relax the arms letting them hang naturally. Close the anal sphincter, and breath naturally from the abdomen. Tilt the head backwards, opening the mouth wide, and relax the jaw. Allow the upper body to lean and bow backwards (without straining the spine), but stretching the psoas muscles. Hold this posture from 5 to 15 minutes, concentrating on relaxing the body, and allowing it to resonate (Figure 53.24).



Figure 53.24. Dry Crying

The psoas muscles are located in the lower back and Mingmen area. They articulate from the transverse process of the lower lumbar vertebra. These muscles travel near the center of the abdomen down to the inner thigh. These particular muscles are associated with the storing and releasing of powerful emotions. As the psoas muscles stretch, the body begins to resonate and shake from the pelvic cavity upward. This action returns patients back to the preadolescent state of energy release, allowing them to detoxify deep seated grief within the tissues.

In order to complete the exercise, it is extremely important to ground. This prevents the uprooted toxic emotions from causing Qi stagnations in the throat and chest area. After holding the posture for the prescribed amount of time, slowly lean forward and tilt the chin down. Allow the arms to continue to hang naturally. Slowly lean forward until the hands touch the floor. Imagine Qi, flowing like water, from the torso out your arms, cleansing your body, sending the pathogenic Qi deep into the center of the Earth.

CONTRAINDICATIONS

Patients should avoid this particular exercise if they have previously injured their back. For patients who have difficulty with the stretching of the cervical or lumbar vertebrae, it is encouraged that they wear a cervical collar or lumbar support to prevent injury to the spine. Also, the exercise can be modified to allow the patient to sit comfortably on the edge of a chair while stretching the psoas muscles if the standing stretch is too difficult.

CHAPTER 54
QI EMISSION THERAPY FOR ONCOLOGY

HISTORY OF CANCER TREATMENTS

The ancient doctors of Traditional Chinese Medicine understood about the formation of tumors. The earliest records found were inscriptions recorded on "Oracles of Bone," unearthed from the ruins of the Yin Dynasty (16th–11th century B.C.). The word "ai" (cancer) first appeared in the Chinese Medical classic *Wei Ji Bao Shu* during the Song Dynasty, in the year 1171.

In Traditional Chinese Medicine, cysts, tumors, and cancers are considered multifaceted diseases, originating from imbalances in one or more of the five following sources: environmental, chemical, biological, physical, and psychological. According to the *General Treatise on the Etiology and Symptomatology of Diseases,* a tumor is one of the many diseases that responds to Dao Yin (Medical Qigong) exercises and meditations. To prevent the formation of cysts, tumors, or cancer, and to increase the strength of the immune system, Qigong doctors encourage patients to monitor their diet, maintain emotional stability, increase physical exercises through Medical Qigong prescriptions, and avoid exposure to pollutants.

From a Western Medical perspective, tumors and cancer are likewise considered multifaceted diseases. They are generally viewed as being created and formed through a constant bombardment, attack, and weakening of the tissues, caused by the following three factors:

- A congenital tendency towards specific types of tumors and cancers (inherited weakness);
- Exposure to radiation, environmental pollutants, and chemical poisoning, and
- An inability to repair weakened DNA, leading to uncontrolled replication.

In Traditional Chinese Medicine, cancer cells are considered "infant bodies" which absorb nourishment from the host (mother) body for their own growth; thus they are called "pathogenic or evil embryos." Cancer cells are actually components of the "original" or "mother" body.

CATEGORIZATION OF TUMORS

In Chinese Medicine, tumors and cancers are commonly referred to as "a retention of mass." Retention has the meaning of stagnation. Tumors and cancer originate from flowing substances within the body such as Qi, Blood, Phlegm, and food. These substances stagnate when they are attacked by pathogenic factors, and they gradually take on the form of a lump as a result of excessive accumulation. If the lump subsides spontaneously, it is commonly referred to as a cyst, or benign tumor. Many benign cysts and tumors, however, persist indefinitely.

BENIGN TUMORS

A benign tumor grows slowly, and can spontaneously stop growing, or disappear by itself. A benign tumor also grows in expansive ways. Its margin is clearly defined with firm boundaries, and is easily manipulated through palpation. There is no temperature differentiation between the skin surrounding a benign tumor and normal skin tissue.

Often, no symptoms surround the internal location of a benign tumor. As the tumor grows in certain areas of the patient's body, however, it can disrupt the functional activity of an affected organ. Benign tumors have been known to cause bleeding and inflammation. If the tumor is located within the endocrine glands, it can cause an abnormal function within the gland itself. A tumor located within an endocrine gland does not usually endanger the patient's life. Benign tumors can, however, become life threatening if the location compresses specific areas of the patient's brain or vital organs.



Figure 54.1. The Three Formations of Cancer Growth

MALIGNANT TUMORS

A malignant tumors grow very fast (potentially doubling every two months). Degeneration, festering, and hemorrhaging often accompany malignant tumors. A malignant tumor is infiltrative in its growth, with no clearly defined boundary. Its appearance is irregular and fastened (not easy to move through palpation). The skin temperature surrounding the malignant tumor is considered energetically Hot, as it is warmer than the normal surrounding tissue.

Most malignant tumors either metastasize to nearby, or distant areas of the body. The body's symptoms include fever, pain, anemia, fatigue, and general weakness. In many cases, if left untreated, they can cause death. Malignant tumors, and cancers can be divided into two main categories: a Carcinoma, and a Sarcoma.

1. A carcinoma is a malignant growth or tumor that occurs in the epithelial tissue (the outer surface or first layer of tissue that lines the body's cavities, as well as the principal tubes and passageways leading to the exterior of the body). Skin cancer, esophageal squamous cancer, adenocarcinoma of the Stomach, and breast cancer all belong to this type of carcinoma. A carcinoma may affect any organ, or part of the body, and may spread by direct extension, or indirectly through the lymphatic system and bloodstream.
2. A sarcoma is a malignant growth, or tumor, that occurs within the connective or mesenchymal tissue. It may affect the muscles, bones, fat, blood vessels, lymph system, Kidneys, Bladder, Liver, Lungs, Spleen, or parotid glands. Rhabdomyosarcoma (sarcoma of the muscles), osteosarcoma (sarcoma of the bones), and lymphosarcoma (sarcoma of the lymphatic system) all belong to this type of sarcoma.

THREE FORMATIONS OF CANCER GROWTH

According to Dr. Pan Mingji, Director of the Fuzhou Cancer Institute of Integration of Traditional Chinese and Western Medicine, there are three forms of cancer growth: Expansive Growth, Infiltrative Growth and Exophytic Growth (Figure 54.1).

1. Cancers of the Expansive Growth type consist of tumor cells crowded together on certain parts of the body. These cells proliferate, grow constantly, and expand towards the outside. The cells of the surrounding tissue form a wall to resist the tumor's expansion. The wall becomes the external membrane of the tumor, which has an evident boundary separating it from the normal tissue. Tumor growth begins in this way in the early stages of both benign tumors and malignant sarcomas.
2. Cancers of the Infiltrative Growth type consist of cells that not only group together, but, also separately invade the intercellular spaces, and tubular tissue of normal cells. They establish their foundation within the tissues, and proliferate daily, expanding outward with no boundary system between the cancer tumor and the normal tissue. Since there is no surrounding wall of membrane, the growth spreads in mass. Malignant tumors, especially carcinoma growth, infiltrate in this way.
3. Cancers of the Exophytic Growth type consist of cancer cells that occur on the skin, body cavity, or gastrointestinal mucosa; they often form on the surface of the body's tissues through papillary masses, projecting outwards on the skin and mucosa. Polyp, papilla-

shaped tumors, papilloma, gingival cancer, esophagal cancer, Stomach cancer, and intestinal cancer all grow in this way.

Benign tumors do not spread; they only grow in an expansive or exopathic way. The malignant tumor is different, however, as the cancer cells do not remain in their original location but expand from the mass outward. This expansion extends into other organs and tissues by way of the body's lymphatic plexus and blood circulation. This phenomenon is known as metastasizing.

ETIOLOGY, THE SIX PATHOGENIC EVILS THAT CAUSE CANCER

The following is an analysis of the causes of tumor formation. Traditional Chinese Medicine maintains the concept that a tumor is a systemic disease (affecting the whole body). It can be summarized as a disorder of the internal organs caused by emotional strains, and an imbalance of the viscera, that has allowed the pathogenic Evils to enter the body and obstruct the channels and collaterals. These pathogenic Evils cause problems, that may eventually lead to the stagnation of Blood and Qi and develop into tumors. The pathology of cancer is as follows: Qi stagnation, Blood stagnation, Retention of Toxic Dampness, Retention of Phlegm, Toxin Attack, and Weakness or Deficiency of Energy (Figure 54.2).



Figure 54.2. The Six Pathogenic Evils That Cause Cancer

1. Emotional strains, depression of Liver Qi, or External pathogenic Evil factors can lead to a stagnation of Qi. Long term Qi stagnation can cause stagnation of Blood, which eventually causes clots. It is known that pathogenic Cold and Heat, and the prevailing pathogenic Evil factors, inevitably cause Blood clots.
2. Since Blood and Qi flow together, the obstruction of Qi can lead to an interference in Blood circulation. This interference gradually leads to Blood stasis; Blood Stasis is always further complicated by stasis of Qi. Blood stasis is sometimes referred to as "Dead Blood," due to the fact that the Blood is not moving. When Dead Blood accumulates in a certain area of the body, it eventually develops into an immovable mass or lump.
3. A weakness of the Spleen and Stomach, as well as indigestion, can cause retention of fluid in the body. Long term fluid retention will produce toxic materials that can accumulate and form lumps.
4. Functional disorders of the Lungs and Spleen lead to poor digestion of watery food, and poor distribution of Body Fluids. Fluid retention causes Phlegm, especially when it is complicated by Excess Heat. If Phlegm is unable to move upward to be dispersed out of the body, it collects and stagnates. The stagnation of Phlegm in the Lung(s) leads to asthma. The stagnation of Phlegm in the Stomach causes gastric disorder and nausea. If Phlegm goes beneath the skin, it will take the form of a movable mass or lump.
5. Toxic Evils may come from poisonous external environments (exposure to chemicals, asbestos, ultraviolet rays, radiation, etc.) or may be generated by the stagnation of Excess Heat within the body. This Excessive Heat causes abnormal cell fusion and growth within the body, leading to cancer formation, and a systemic breakdown of normal cell growth.
6. Deficiency of both Qi and Blood, as well as a weakness of Yuan Qi, make the body more vulnerable and susceptible to the formation of new growth. When pathogenic Evils enter the body, they damage the Blood and Qi. If the Yuan Qi cannot be restored, the disease will lead to a vicious, destructive cycle, mak-

body makes it easier for the pearl to absorb these energies. It becomes like an antenna that receives the external Chi and conducts it into the physical body. In this way, we again nourish our health in this life as well as strengthening the Energy Body and spirit in preparation for the next.



Fig. 7.13 *Three Thrusting Channels above the Crown*

After you gain full control of the energy, you will be able to send the pearl out of the body at the crown. Begin to practice quickly forming a fresh pearl in the practice of formimg the pearl by fuse in and out and back to the inside to form a pearl. Follow with the Creation Cycle. Then, thrust the pearl up through the Thrusting Channels to quickly clear out these routes. You are now ready to extend the channels above the crown.

ing the individual more and more debilitated.

These six pathological changes may occur either alone or in combination: i.e., Qi and Blood stasis, Phlegm stagnation and Toxic Dampness, Phlegm stagnation and Blood stasis, a weakness of the body's Yuan Qi and strong pathogenic Evils.

The choice of which Medical Qigong therapy to use should be based on differentiation of symptoms and signs. Since cancers are primarily caused by emotional strains, strong pathogenic Evils, and a weakness of the patient's Yuan Qi, clinical therapy should be focused on tonifying the patient's Yuan Qi, and purging the Evil pathogenic factors.

EMOTIONAL COMPONENTS OF CANCER FORMATION

From the clinical perspective, if the cancer is internally induced through emotional suppression, there will be a series of emotional transitions the Qigong doctor will observe during its development. When there is an accumulation of negative emotions, for example, the patient's body begins to wall off this type of energy, and creates an energetic cyst, instead of dissipating and disposing of the Toxic Qi. The patient's suppressed internal emotions intensify the production and formation of the cyst, and feed the cancer cells, which result in an uncontrolled, rapid growth rate of these cells.

The body creates potential tumors and cancer cells every day. The macrophages or monocytes (large phagocytes) in the immune system aggressively attack and dissolve the cancer cells once the body becomes aware of them. Areas in the body, however, which are armored in denial, tend to attract and protect these distorted cells, allowing them to cluster and mass together.

Cancer cells can grow and accumulate wherever emotions are being repressed. The patient's denial maintains the constant unconscious flow of energy to these tissue areas. The phagocytes and other components of the immune system do not attack these toxic pockets of emotional energy, because of the patient's continuous denial of their existence. Consciousness and awareness exists even at the cellular level of the body. The continuous emotional energy bombarding the cells and tissues causes these tissues to go into an emotional state of shock. Emotional shock causes a release of endogenous opiates and corticosteroids, that deplete the white blood cells, and prevent the immune system from protecting the body. Because of the immune system's weakened state of resistance, infection and even the formation of cancer cells are now free to enter and coagulate within the tissue areas.

Scientific studies based in China, and the West, have shown that stress can stimulate the neuroendocrine system to the extent that it leads to depression of the immune system. Furthermore, the creation and growth of cancer can be influenced by stress. Removal of psychological stress alone can alter the neuro-immunologic functioning of the body to the extent that it can prevent and even change the course of cancer development.

In a patient with emotional blocks, chronic tension begins to interrupt the flow of Qi. If the emotional block is deep and long standing, this tension becomes constant. The capacity to express or discharge the trapped emotion becomes very difficult.

As the awareness dims, the natural communication between the conscious and subconscious mind breaks down. The original conscious decision to suppress certain emotions becomes a habit; it thus becomes an unconscious aberrant automatic function. When emotions are expressed, the conscious and subconscious mind are in harmony and synergized. When emotions are suppressed, the subconscious mind can no longer perform its job of healing the body; it diverts all its energy to shield the patient's denial system. Thus, the Shen itself, becomes misaligned with the patient's life purpose. The patient's posture, movements and lack of spiritual growth, reflect this misalignment. Changes also occur in skin temperature, body chemistry, and skin tone. The overall level of vital life force visibly drops.

Dr. Xu, at the Xi Yuan Hospital in Beijing, China, often pointed out that emotional upheaval, and the restriction of the breath, could cause the patient's energy to stagnate or deviate from its path. The deviated Qi draws more energy to its pathway, compounding the disease. The unstable emotional and mental focus of the patient further causes adverse effects to the body. Medical Qigong therapy and exercises expose the patient's deepest secrets, and thus reveal the underlying causes of the disease, which can then be treated. The patient's being is energized through his or her personal perceptions and belief structures. Therefore, it is necessary to change the patient's belief structure to increase the level of awareness and perceptual accuracy. The patient must be enabled to let go of suppressed emotions to fully experience deep emotional and spiritual changes. The Qigong doctor initiates the release of Toxic Qi to begin this healing process that can thereafter be maintained through appropriate prescriptions.

When cysts, tumors, or cancer are internally induced, they are formed from long-standing suppressed emotions which have become trapped within the tissue itself. These emotions usually consist of anger, guilt, grief, shame, and disappointment. The energetically formed cyst, or tumors, will remain walled off until the emotional energy is dissipated. Cysts, or tumors, can lodge themselves anywhere, penetrating deep into the major viscera causing visceral dysfunction; or they can superficially lodge themselves beneath the skin.

If the nature of the emotional energetic matrix (i.e., belief structure) is negative, the patient retains the energy of the injury, making it difficult to heal the trauma. If, however, the emotional matrix is positive, then the energy of the injury can be easily dispersed.

Once the Qigong doctor's energy reaches the cyst or tumor, the patient's energetic resonance supporting the tumor formation is interrupted. As the doctor continues to break up the cyst or tumor's physical mass, the frozen energetic pattern begins to unwind. The doctor continues to unravel the energetic mass until all the Heat has been released from the tissues, and the energetic pattern's unwinding is completed.

The underlying pathophysiology of healing can be broken down into four components:

1. The mind affects tissue matter through the emotions.
2. The emotions cause neuropeptides to be released.
3. The emotions (via the neuropeptides) influence the direction and movement of the immune cells (e.g., monocytes), sending them to various parts of the body.
4. The immune system (e.g., monocytes and phagocytes) heal the body.

The neuropeptide receptor sites are located on the immune cells, linking the body's immune system with the functions of the mind, emotions, and spirit. Neuropeptides are produced in response to the individual's state of mind and emotions; they influence the state of health of all the internal organs.

Through Dynamic Medical Qigong training, neuropeptides, in the form of endorphins, are released within the body's system. This release of energy and endorphins helps to facilitate the patient's healing.

Through the use of Medical Qigong therapy, exercises, and meditations, areas of denial and subconscious energetic patterning can be altered. The energetic matrix which supports the tumor(s) or cyst(s) thus dissolves.

When a healing session occurs, the Qigong doctor's external energy field envelops the patient's tissues, thus allowing the patient's cells to receive new information to reprogram the toxic energetic patterns. This reaction occurs providing the patient's tissues are open to receive the informational structures needed to either rebuild them, or disperse the disease's cell formation.

CANCER FORMATION AND THE PATIENT'S MIND, EMOTIONS, AND SPIRIT

Emotions strongly influence the increase or decrease of tumor size; therefore, it is important to regulate the patient's mind, emotions, and spirit. When the patient's mind, emotions and spirit are free from distractions and are in harmony, the patient is able to manage negative emotions. Regulating the Mind (whole body awareness and consciousness) is considered the primary Medical Qigong technique used for teaching patients how to avoid creating the dark abyss of negative emotions.

The patient must learn to let optimism prevail over pessimism. The practice of Medical Qigong not only cultivates vital energy and builds up the patient's health, but promotes the development of optimism through creating a quiescent mind. Tranquility and optimism improve circulation of Qi and Blood (which strengthens the immune system) thereby inhibiting cancer cells until they gradually perish.

While visiting in Maui, Hawaii, I came in contact with four people who had been diagnosed with terminal cancer, and had a life expectancy of two weeks according to their physicians. Each person had their own unique story as to how they had come to the Hawaiian Islands to die. What struck me as fascinating was the fact that each one of these individuals had either left successful but extremely stressful businesses, or long term abusive relationships. Each made amends the best they could with relationships from their past (those who had anger against them or those whom they had hurt). They had come to paradise to live their last weeks in peace. That was several years ago! It seems that upon resolving all personal conflict, and leaving their stressful environment, their cancers went into spontaneous remission. Each individual was now concentrated on enjoying the pleasures of a simpler life, and on focusing on their own spiritual growth.

STRESSFUL LIFE ACTIVITIES AND THE IMMUNE SYSTEM

Stressful life activities create a flood of adrenaline within the body. This occurs not only from the endings of the vertebral lumbar division at the core segment of the major internal organs, but also from the core of the adrenal gland in the medulla (which specifically is a sympathetic ganglion, and responds to stress by releasing adrenaline into the blood stream). Adrenaline spreads throughout the body and activates not only the body's sympathetic nervous system, but also the adrenal glands; the heart rate, respiratory rate, blood pressure, and Blood flow to the muscles are increased in response to the Fight or Flight Syndrome.

When the release of adrenaline causes the mind and body to react, the immune system must then seek to balance the chemical imbalances created within the body, before it can return to its normal job of monitoring cellular activity, and defending against pathogens. If a patient is already vulnerable to a specific disease, added stress causes the patient to get sick quicker. Meditation takes the patient out of the stress mode, deactivates the adrenal glands, and normalizes the function of the immune system.

An unstable life style is very stressful and can lead to depression and Qi deviations. Conflict produces stress which causes anxiety; chronic stress wears down the mind and body, which leads to anxiety, or depression. Stress begins with an overexcitement of the nervous system, slowly working its way deep into the body like wet cement. It causes the shoulders and upper back to become tense and rigid. Stress can result from happy occasions (such as weddings) and other normally pleasant events. When the patient's life style is not properly balanced, over time Qi deviations, and illness can result. The capacity to bear stress is related to the strength of the nerves. When stress levels surpass the nervous system's capacity to handle them, the nerves "break down"; this results in all sorts of physical, mental, and emotional disturbances. These disturbances, if unheeded, can eventually lead to organ malfunctions, cysts, tumors, cancer, and premature death. To avoid such states, a balance between work and rest must be maintained.

At a conference of the International Society for Neuro-immunomodulation (*The Effects of Stress and Depression on Physical Disease*), Dr. Philip Gold, of the National Institute of Mental Health stated that stress and depression send hormones (e.g., cortisol) flowing into the bloodstream. An imbalance of hormones, if unregulated, can:

- destroy the appetite,
- cripple the immune system,
- shut down the processes that repair tissue,
- inhibit sleeping patterns,
- break down bone density,
- aid the onset of infection, and
- instigate the growth of cancer cells.

An individual's emotional past determines his, or her, present state of health, both physical and emotional. Past emotional belief structures are responsible for both creating and healing diseases. Just as thoughts drift through the mind (but do not become active until they reside within a belief structure), so emotional wounding resides within the tissues and cells waiting to be activated by emotional upheavals. Our thoughts become form via choices, and manifest within the body.

In most societies, sharing traumatic wounds is often the first act of intimacy and bonding. Traumas provide a common ground for relationships, and support the pain structure that cements the relationship. People become addicted to empowering wounds, which in turn supports and empowers the disease. The exchange of painful personal traumas is reinforced by receiving sympathy and strong empathy, which binds rather than releases the pain from the tissues. Desire for sharing one's pain in order to receive love can lead to a habitual way of relating to those closest and dearest. When such individuals feel taken for granted, or unappreciated, they may immediately resort to sharing past traumas to illicit the desired response. When such techniques fail to elicit the desired response, a new wounding is experienced. Many of these individuals will continue to unconsciously create new traumas, in the hope that, this time, the desired outcome will be achieved. This in turn can become an addiction, empowering old wounds as it creates new ones, including illness. Thus, the spirit becomes divided to support the new belief structure (i.e., that pain and misery grin love and attention), and the life-force energy deviates from its assigned job of protecting the body, which creates illness. Setting the self up for new wounds is not a conscious process, but an unconscious one, which needs to be brought into the patient's awareness in order to be healed. Then and only then can the mind and spirit act as one unit, directing the body's Qi towards its proper function of healing.

Because energetic healing occurs in the present, not in the past, victims of past traumas will never heal if the energy continuously regresses to the armored traumatic belief structure.

USING MEDICAL QIGONG TO STRENGTHEN THE IMMUNE SYSTEM

Medical Qigong increases leukocyte production, stabilizes the body's blood pressure, and improves the immune function. The immune system is not so much an independent system, but is rather an interactive functional system throughout the body. Immune cells which live in the Blood and lymph fluid are commonly known as leukocytes (white blood cells); lymphocytes are a type of leukocytes that is created in the Spleen. The purpose of these cells is to work together to defend against pathogenic factors. The function of leukocytes and lymphocytes is to identify, ingest, destroy, and eliminate disease-causing organisms, as well as remove all dead, damaged, or irregular cells.

Immune cells are produced in the lymph tissue and red bone marrow, and are stored in the lymphatic organs and the Blood. To perform the function of protecting and cleaning, immune cells must circulate throughout the entire body through the capillaries and vessels that carry Blood and lymph fluid. Immune cells travel from the lymph nodes and the lymphatic organs of the thymus gland, Spleen, and tonsils, which are responsible for filtering the lymph fluid to remove impurities, and produce more lymph cells.

For an External pathogen to affect the body, it must first pass through protective layers of cells. Generally, the macrophages present within the tissues ingest the pathogens and dead tissues. Macrophages are reinforced by the action and movement of the body's Wei Qi. When a pathogenic intruder invades the body, the macrophages are often the first to attack the intruder. If the macrophages are not strong enough, more Blood and fluid are brought to the area, which contain more diverse immune cells. The increased fluid engorges the tissue, which engenders more cellular activity. The increased Blood and cellular metabolism increases the local temperature. The immune cells break down and ingest the pathogens, creating a process which continues until the disease is eliminated.

The dynamic movements of Medical Qigong


1.The Fast Walking Method
Cancer Treating Prescriptions
2.The Deep Breathing Method
3.The Tone Resonating Method

Figure 54.3. Three Prescriptions Used For Treating Cancer

exercises generate Heat, soften the body's connective tissues, and encourage the flushing of the intercellular fluid throughout the body's tissues and organs. Energetic Qigong practices increase oxygenation in the Blood and improve circulation, thereby enhancing leukocyte production, and strengthening the body's immune system.

CANCER TREATMENT METHODS

Tumor and cancer cells make their own room within the body's tissues by crowding the normal tissues. The tumor and cancer cells grab nourishing energy at the expense of the host, thus damaging the patient's body.

Medical Qigong cancer treatment methods are techniques designed to purge the energy that supports the tumor. These techniques are based on the fundamental Qigong patterns mentioned previously. The goal of these patterns focuses on treating the patient's Excess syndrome first, by purgation. Purgation is then followed by tonification, then regulation. The rapid growth of healthy energy, and the fast expulsion of Evil factors, should lead to normal body function restoration, and create more vigorous metabolic activity. More nourishment can be absorbed, delivered and distributed throughout the body, leaving no room to feed the tumor cells.

In Medical Qigong clinics, tumors are viewed as being similar in their expansion and growth to that of the energetic pattern of a plant's Qi flow. When tracing the origin of a tumor, the Qigong doctor begins at the tumor's location (considered the flower or fruit of the disease) and traces its energetic branches to the organ of origin (the actual root of the disease). If the disease is internally induced, the original source, i.e., the dysfunctional internal organ, feeds the tumor through suppressed emotional trauma.

To address this problem, the doctor prescribes the following three cancer treatment methods as homework, in addition to Medical Qigong treatments and herbal therapy: the Fast Walking Method, Deep Breathing Method, and the Tone Resonation Method (Figure 54.3).

1. The Fast Walking Method stimulates the electromagnetic fields within the tissues and reinforces the patient's Yuan Qi. By walking fast and changing the normal breathing patterns, the cancer cells can be destroyed. This is because the dual action of shocking the system with more Qi and Blood flowing through the body tends to stimulate the electromagnetic fields within the tissues, causing the tissue cells to become stimulated and the immune system to be aroused and thus enhanced.
2. The Deep Breathing Method tranquilizes the patient's mind, and enhances their Yuan Qi. The Deep Breathing method is used to treat various cancers due to mental and emotional factors, by changing the patient's normal breathing patterns.

By changing the normal breathing into rapid exhaling, slow deep exhaling, or relaxed toning, Blood clots and tumors can be dissolved. This breathing technique has a special effect on reinforcing the patient's Yuan Qi. When prescribing Medical Qigong therapy, it is important to match the patient's Yin disease with a Yang method of treatment, and a Yang disease with a Yin method of therapy. For example: rapid exhalation (a Yang method) would be used when treating an abdominal mass caused by a Cold (Yin) condition.

3. The Tone Resonating Method is utilized to purge any residual Evil pathogenic factors from the patient's body.

When first starting the Medical Qigong Cancer Tone therapy, a patient's practice time should be short. The performing time can be extended gradually with the increase of the patient's physical strength. To bring the Medical Qigong exercises to peak efficiency, a patient should practice a minimum of four hours (including 15 minute breaks), and up to six hours each day. The patient can take a break after half an hour to avoid fatigue.

Through various kinds of breathing and fast walking therapies, Qi can be energized to flow so vigorously through the Conception Vessel that the patients' Yin and Yang is balanced and their Lung Channels are strengthened. In the course of treating the tumor or cancer, True Qi (Zhen Qi) is fostered and the immunity of the body strengthened. Research from China proves that persistent training, vigorous enough to increase a person's heartbeat up to 70-80% of its maximum rate, helps dissolve Blood clots. Other reports state that long distance running can be effectively used to cure cancers. These reports may help explain why fast walking, and breathing methods, are effective for preventing and treating cancer.

SOCIAL ONCOLOGY—ESTABLISHING A CANCER SUPPORT GROUP

In China, cancer patients join support groups to practice Medical Qigong. This form of treatment is called social oncology; it was created by the Cancer Recovery Society for the purpose of supporting human interaction and the recovery of health by cancer patients.

Cancer recovery groups meet daily in parks throughout China, practicing self-healing (in particular, Guo Lin's Cancer Recovery Qigong and Walking Qigong Therapy). After practice, the groups gather together for about an hour to socialize in a nearby tea house. The patients sing songs, tell jokes, laugh, introduce new members, read poems, and tell stories that highlight the possibilities of recovery from cancer. As part of the social meeting, the group regularly sings "Happy Birthday" to each patient who has an anniversary after his or her cancer diagnosis. Laughter becomes a top priority in social oncology, and is considered the strongest medicine for healing.

According to Dr. Roger Jahnke, O.M.D., the advantages of social oncology are three fold: stress reduction, positive reinforcement of hope, and the establishment of deep interpersonal relationships.

1. Stress is reduced through socializing rather than isolating and fretting. The social healing aspect of the patient's recovery program serves as a constant reminder that the physical healing is enhanced when he or she becomes lighthearted and free of worry.
2. Increased hope and faith is achieved through the power of personal testimony. Each day during the social healing session, patients hear stories of close friends whose recovery process proves the benefits of healing from various forms of Medical Qigong.
3. The value of love and encouragement from friends mitigates depression, fear, and worry. Isolation is like a food to cancer; social oncology provides fun, encouragement and a deep, caring interpersonal connection within the recovery group.

SOCIAL ONCOLOGY WITHIN THE HOSPITALS

In several Medical Qigong hospitals in China, when the patients first check-in, they are assigned a support group. The support group consists of previous and current patients, who have survived the same type of cancer as the entering patients.

To assist patients in healing and to give them every emotional advantage during recovery, visitors, phone calls, letters, TV, and newspapers are forbidden for six weeks; this ensures a controlled environment in which neither family nor friends can adversely affect the healing process (through critical comments or attitudes). Patients are immersed in a support group full of caring, motivated individuals all working towards the same goal. Furthermore, patients who have been there the longest share their success stories, boosting everyone's moral.

The concept of clinical social oncology is based on the belief that the patients' high spirits affect the emotional perspective, and thus mental thinking. These emotional and mental changes alter the physical body. It was recently discovered that the group of breast cancer patients, who participated in the Stanford Hospital Cancer Support Group, lived twice as long as the women who refused to join the group. This difference in longevity was attributed to the love, support, and social aspect of the cancer support group. This recently discovery has given rise to the increase of several support groups in the United States now being established for patients recovering from AIDS, heart attacks, and many other illnesses including several types of cancer.

CANCER RESEARCH

Noted research scientist Feng Lida pioneered cancer research in China by showing that emitted Qi from Qigong masters produced marked changes in cancer cell cultures from mice. Several studies reported the effects of emitted Qi on tumors in animals. The emission of Qi, for example, was reported to inhibit the growth of implanted malignant tumors in mice, but did not destroy the tumors. Encouraged by the results with animals, researchers carried out clinical research on the effects of Medical Qigong on human subjects with cancer.

In one study, 127 patients with medically diagnosed cancer were divided into a Qigong group of 97 patients, and a control group of 30 patients. All patients received drugs, and the Qigong group practiced Medical Qigong for more than two hours a day over a period of 3 to 6 months. Both groups improved, but the Qigong group showed improvements four to nine times greater than the control group for strength, appetite, and weight gain. The Qigong group also did not experience bouts of diarrhea. The phagocytic rate, which is a measure of the immune function, increased in the Medical Qigong group, but decreased in the control group. These cancer treatment results were gathered and compiled from clinical research by Dr. Kenneth M. Sancier, available in the first Appendix of this text.

MEDITATIONS FOR CANCER PATIENTS

The following meditations are frequently used within the Medical Qigong clinic to aid healing. As previously discussed, it takes focused concentration to initiate an energetic transformation. Focused concentration is achieved through proper imagination, visualization and positive affirmation; it is practiced to reprogram the body's energetic cell patterns, and initiate healing.

DIVINE HEALING LIGHT MEDITATION

A very effective Medical Qigong meditation called Divine Healing Light is practiced by cancer and tumor patients throughout China to dissolve and disperse energetic pathogens. This meditation begins as follows:

Begin in a seated posture. Relax, and feel a quiet comfort. Imagine yourself seated on a quiet mountain overlooking the ocean, resting under a clear, dark blue evening sky. At the rim of the ocean, the full moon begins to rise. It continues to ascend until it faces you, suspended in the sky above your head. Slowly the moon begins to shrink, becoming smaller and smaller, yet brighter and brighter until it becomes the size of a small luminous pearl. This brilliant white pearl begins to pulse and expand, as it grows it opens to form a large orb, vibrating with divine power. From the center of the divine power flows unconditional love, healing, and compassion.

Breathe in this vibrant, healing light; allow it to penetrate deep into your body, permeating every cell, illuminating and dispersing all illness. Open fully to the divine healing. Feel the love and compassion enveloping you, and penetrating all the diseased areas of your body. Continue to breathe the healing energy in through your nose and exhale out through your mouth (imagining all the unclean energy descending into the ground). Continue this breathing pattern until all the negative energy has been expelled and replaced with divine love and healing light.

PULLING OUT THE PAIN MEDITATION

This meditation is an effective treatment prescription for treating many illnesses, including cancer and tumors. The goal is to eliminate all toxic belief structures that stand in the way, and sabotage the patient's healing. Gentle acceptance of the illness and emotional pain opens the pathway to understanding and unveiling hidden traumas. Force does not work in trying to change the tumor or cancer energetic patterns. Only honesty, respect, tenderness, and understanding will begin the healing process. As pain and suffering are allowed to surface into consciousness, the immune system is able to recognize diseased cells, and can mobilize an army of immune cells. These are then able to effectively identify, dissolve, and remove any tumors and disease.

The doctor instructs and guides patients through this meditation matching the rhythm of the words, to the patients' exhalations. Patients draw their painful memories and traumas out of their body in the form of dark smoke; they then separate the distilled wisdom and knowledge from this dark cloud, reabsorbing the healing light into every pore and cell in their body. The dark cloud then is released with the help of an angelic being who severs the energetic cord(s) that still attach the patients to their pain and suffering. The doctor assists the complete severance by clapping his or her hands as the patients visualize the "Sword of Truth" (held by this holy being), severing the dark energetic cord(s). The sword of truth represents the patients' intent to regain their power by letting go of their attachment to their illness. This attachment created very real energetic cords that bound the patients to their painful memories and toxic emotions. Severing these cords, or cord, symbolizes the end of the patients' investment in their disease, and the beginning of true healing. All the patients' pain and despair is released, as the black cloud ascends into the Heavens, and into the hands of God (or a higher power, in accordance with the belief structure of the patients). As the cloud reaches the first wave of love and compassion emanating from God (or a higher power), a mighty explosion transmutes the black despair and pain, into divine healing light. The doctor then assists the patients in accepting this healing, loving light back into their body, to experience, perhaps for the first time in their lives, true forgiveness and a state of grace.

1. Begin by sitting comfortably in a chair, with both feet on the floor, hands resting on the thighs, eyes closed, tongue on the upper palette. Breathe naturally through the Lower Dantian.
2. Focus your attention on the Yellow Court area below the diaphragm where you store painful memories and traumas. Imagine opening up this area to release the toxic energy out of your body as a stream of dark steam releasing from a pot.
3. As the dark steam flows out of your body you release feelings and memories of guilt, anger, rage, humiliation, abandonment, degradation, rejection, insecurity, and sorrow. These toxic emotions have, until now, prevented you from healing through creating a deep distrust of yourself and others.
4. Focus your attention on this energetic cloud, and begin separating the pain and hurtful memories from the knowledge and wisdom gathered from these experiences. Visualize this knowledge and wisdom in the form of golden, white, and silver light energy gathering on the right side of the room. Continue to drain the dark cloud of misery and pain, now occupying the left side of the room, until you have extracted all the new insights from it. As you do so, you notice the dark cloud becoming heavier and darker.
5. Focus on the right side of the room. Through you intention, begin to inhale and imagine this bright, illuminating energy flowing back into your body. Absorb this knowledge and wisdom gathered from past experiences, void of any feelings of hurt, pain, or judgement, into every cell of your body. This distilled knowledge and wisdom empowers you to heal from

your wounds on a physical, mental, emotional, and spiritual level.

6. Next focus your attention on the dark black cloud containing all your pain and suffering. Imagine an angelic being, righteous and holy holding a "Sword of Truth" standing by your side, ready to sever the dark energetic cords still connecting your physical body to this dark cloud of despair. The sword descends and severs the cords (the doctor claps his or her hands at this moment).
7. The cloud of darkness begins to float up, through the ceiling, through the sky into space. Far in the distance you begin to perceive God, or a higher power, emanating waves of compassion, love, and mercy descending towards the Earth. One of the waves touches the ascending dark cloud of hurt and pain, exploding it into a brilliant light. The cloud is immediately transmuted into fluorescent crystal blue drops of light. This pure, clean energy descends from the Heavens like a gentle rain. Breathe in this crystal blue healing energy, let it penetrate deeply into every pore, every tissue and cell, saturating your body completely. Feel the light cleansing, healing, and radiating throughout your being.

SUMMARY

Cancer is defined by Traditional Chinese Medicine as, "an obstruction of Qi and Blood circulation resulting in stagnation." The root cause for cancer is the breakdown and stagnation of the patient's Yuan Qi. Once cancer becomes established within the patient's body, or metastasizes, it is difficult to heal.

In order for cancer to form, it must elude the body's immune system, undergo many divisions, and produce countless generations of cells without resistance. By the time the cancer cells have formed into a cluster mass, a fixed energetic pattern has been established to support its existence and survival.

Only when the patient's Yuan Qi is returned to its original state, can the body begin to heal itself. Medical Qigong Cancer treatment methods strengthen the True Qi which in turn strengthens and cultivates the Yuan Qi. In this manner, the body is returned to its natural state of Yin and Yang balance.

It is the author's hope that these effective methods of treating cancer will soon be available to the American public. To this end, I have established a three-year master's and plan to offer a five-year doctorate program in Medical Qigong Science at the Five Branches Institute, College of Traditional Chinese Medicine, in Santa Cruz, California.

TREATING TUMORS AND CANCER WITH MEDICAL QIGONG THERAPY

The following are several Medical Qigong techniques and treatment modalities, currently used in China, to treat different types of energetically induced cysts, tumors, and cancers. It is advisable to accompany the prescriptions with various herbal prescriptions.

BRAIN TUMORS

A brain tumor is a generic term used to describe any intracranial mass, which includes: neoplastic, cystic, inflammatory (abscesses), or syphilitic.

ETIOLOGY

There are many causes for intracranial tumors. The most common cause is Kidney Yin (Water) failing to wash over the brain to disperse the pathogens. This condition can be caused by Excess Liver Fire dissolving the body's Kidney Water.

SYMPTOMS

Intracranial tumors produce symptoms primarily by two mechanisms: the infiltration and destruction of the normal brain tissue; or the tumor mass affecting the surrounding tissue, which causes edema, thus increasing the intracranial pressure.

General symptoms include headache (due to intracranial pressure), changes in the retina, and vomiting (without nausea). Additional symptoms include mental and emotional changes such as dullness, giddiness, or epileptiform convulsions.

TREATMENT

1. The doctors first step is to analyze the syndrome and the patient's emotional outlook.

When treating brain tumors, the growth of the disease must first be stopped. Check the patient's external living conditions, and do a psychological profile to determine any detrimental patterns.

2. Dredge and disperse toxic Heat out of the patient's Yang channels. Remove any Excess Liver Fire by drawing it out the Liver organ; then dredge the patient's Liver Channels, dispersing toxins out through the Lv-3 points.
3. The doctor must reverse the process of tumor development to dissolve the tumor. Instruct the patient to visualize energy from the Lower Dantian rising up to the tumor and transforming the mass back into Qi. The tumor growth must be reversed by first converting the solid tumor into soft tissue, then into fluid Qi that is then dispersed.

   In cases of cranial thrombosis, tumors must be dissolved slowly; otherwise other tumors will be created. The tumors must be softened, then slowly dispersed to avoid any recreation of the energetic channels' dysfunctions.
4. Extend Qi into the patient to reinforce the Kidneys' Qi by extending Qi into the patient's feet via the brain tumor point, Shihmein, at the bottom of the heels (Figure 54.4). Next, lead the patient's Kidney Water up into the brain to rinse over and slowly dissolve the tumor.
5. Finally, regulate and balance the patient's Yin and Yang energy.

PRESCRIPTIONS AND HOMEWORK

1. Have the patient practice the healing sound "Duo" (10 times in a straight and 10 times descending / ascending tone) five times a day.
2. Assign tonifying exercises for the Kidneys and Heart.
3. Prescribe herbal teas to enhance the patient's Kidney Yin.

BREAST CANCER

Mammary cancer is one of the most common types of malignant tumors in women; it is considered a malignant neoplasm of the breast.

ETIOLOGY

There are multiple factors associated with breast cancer. These factors can be categorized under genetic family factors, hormonal factors, dietary factors, environmental factors, and benign breast disease. Heredity can play an important role, especially if the patient's mother (or close relative) had bilateral breast cancer diagnosed prior to menopause. Also, a history of chronic breast disease (especially epithelial hyperplasia), or obesity can predispose the patient to breast cancer.



Figure 54.4. The Qigong doctor will emit Qi into the patient's "Brain Tumor" point (also called the Shimian, meaning insomnia point) located at the bottom of the patient's Heel.

SYMPTOMS

Symptoms consist of hard lumps which lack mobility, and progressively increase in size. The hard lumps may be concave, convex, or protrude; or the nipple may be inverted. Breast cancer is usually related to stagnation of the Liver's Qi, stasis of Blood, Phlegm and Toxic Heat, as well as weak Kidneys. The emotional components which lead to breast cancer are suppressed grief, worry, sorrow, and depression.

Bring the energy down to the perineum, and start with the Left Thrusting Channel up to the left crown. Push the pearl out at the crown of the head to about three to six inches (seven and a half to fifteen centimeters) above the crown. Similarly, push the pearl out of the crown through the Middle Thrusting Channel, and then the Right Thrusting Channel.



***Fig. 7.14** Use Physical and Mental Power to push the Pearl of Energy up through the Crown.*

Each time you push the pearl out at the crown, be aware of an energy ball hovering about six to ten inches (fifteen to twenty-five centimeters) over the crown. Draw and absorb the Heavenly Energy to the pearl. Then slowly let the energy melt and flow down to the crown, and then into the body, all the way down through the three Thrusting Channels to the perineum.

6. Stage Four: Leg Routes and Thrusting Channels into the Ground

In the final stage of opening the Thrusting Channels, the energy will go all the way down to the feet and into the ground, and then up through the channels with each thrust. After you have formed another new pearl by practicing Fusion of the Five Elements and the Creation Cycle of Cosmic Fusion, bring the energy down to the perineum.

TREATMENT

1. Purge and eliminate the stagnation from the breast tissue (Figure 54.5).
2. Subdue the Rebellious Qi.
3. Clear the Liver and tonify the Kidneys. When treating breast cancer, the doctor should use the Vibrating Palm in conjunction with projected Tone Resonation (projecting both vibration and the "Ni" tone resonation into the cancerous area).
4. Tonify the patient's Conception and Thrusting Vessels, and end with the Microcosmic Orbit regulation (Fire Cycle).

UTERINE CANCER

Uterine cancer is considered a malignant neoplasm of the uterus.

ETIOLOGY

The etiology of uterine cancer is unknown. Possible causes of the disease may be:

- chronic stress
- toxins
- suppression of emotions
- pathological changes of the endometrial hyperplasia, or
- cervical carcinoma spreading onto the uterus.

SYMPTOMS

A uterine carcinoma is generally more common in women after menopause, roughly 75% of uterine cancers occur in postmenopausal women, 15% peri-menopausal women and 10% of menstruating women. The main clinical manifestations include pain in the lower abdomen, waist and thighs, abnormal uterine bleeding with a bloody, purulent discharge.

TREATMENT

One Medical Qigong therapeutic technique used in China to treat uterine cancer is as follows.

1. Purge the diseased area of stagnant Qi using the Thunder Palm technique in conjunction with the Vibrating Palm technique.
2. Project the sound "Yu" into the uterus to disperse Heat from the cancer cells.
3. Disperse Excess Heat from the patient's Liver and uterus, leading the Toxic Qi out the patient's body via the right Gall Bladder



Figure 54.5. After Purging the pathogenic Qi from the patient's upper body, the Qigong doctor continues to disperse the patient's Toxic Qi from her lower abdomen, leading it down her legs and out her St-36 points.

Channel.

4. Fill and tonify the patient's Lower Dantian and Kidneys with Qi. Circulate the energy through the Microcosmic Orbit to improve Qi and Blood circulation through the Governing and Conception Vessels.

PRESCRIPTIONS AND HOMEWORK

The Conception Vessel moves Qi in the Lower Burner and uterus; it is the primary Vessel used in treating uterine and cervical cancer. Sexual activities are therefore prohibited from the start of the treatments, until treatment is no longer needed.

1. Have the patient practice the Descending the Yang and Ascending the Yin Technique (see Chapter 41), ending with the healing sound "Yu" for 24 breaths, 9 times a day.
2. Prescribe the Fast Exhaling Breathing Method along with the Cancer Walking methods for treating Kidney disease (see Chapter 15).
3. Have the patient practice the method of Taking in the Blue Qi, three times a day for 15 minutes each session, to strengthen the Kidneys.
4. Have the patient practice the Filth Dispelling meditation, while focusing on her uterus. This meditation is practiced as follows:
    a. From a sitting posture, with the eyes closed, and the body relaxed, place the tongue up against the upper hard palate, behind the teeth.
    b. Breathe naturally and evenly.
    c. Imagine Qi whirling in through the upper portion of the uterus, circulating clockwise, building momentum as the energy flows downward to the base of the uterus.
    d. Once the energy has reached just above the cervix area, imagine the whirling Qi absorbing the noxious Heat and Toxic Qi from the uterus, transforming it into wind, and dispelling it out the vagina. Repeat this sequence 10 times.
    e. Next, gently close the vagina and anal sphincter, then inhale, and imagine the Qi flowing into the body through the vagina. As this energy flows into the uterus and Lower Dantian area, it transforms into wind. This wind circulates in a counterclockwise direction, spiraling up the body, through the Thrusting Vessel and exits the body through the mouth with each exhalation. Repeat this visualization 10 times.
    f. Finally, focus attention on the Lower Dantian, imagine the Qi returning to its origin, and rub the abdomen 36 times in a clockwise direction to end the prescription.

CERVICAL CANCER

Cervical cancer is considered one of the most common malignant tumors in China. It is considered a malignant neoplasm of the cervix of the uterus, and can occur at any age.

ETIOLOGY

Cervical cancer is suspected to be an oncogenic papilloma virus that is transmitted sexually. Risk factors include:

- sexual intercourse at an early age,
- multiple sexual partners and promiscuous male sexual partners (especially those whose previous partner had cervical cancer),
- serious cervical lacerations caused from the penis being too long, or the insertion of foreign objects,
- unsanitary sexual relationships,
- closely spaced births, and
- a family history of cervical cancer.

Excessive sexual activity predisposes young teenage girls to cervical cancer, because, with the onset of ovulation and the changes in vaginal PH, active squamous metaplasia is taking place in the cervix. During this time of cellular immaturity and vulnerability, a carcinogen is most likely to have an influence on the squamous epithelium; this can predispose the teenager girl to cervical cancer later on in life.

THE DEVELOPMENT OF CERVICAL CANCER

There are two main types of cancer of the cervix. The squamous cell carcinomas make up 85-90% of cervical cancer, the rest (a small 10-15%)

are developed from a malignant adenoma arising from a glandular organ known as a adenocarcinoma.

Cervical cancer begins with the growth of abnormal precancerous cells and tissues called dysplasia. Dysplasia is first detectable in the squamous epithelium of the cervix (the muscle lining of the cervix), and spreads to create a tumor called a cervical intraepithelial neoplasm (CIN). The cervical intraepithelial neoplasm progresses through three levels of severity, from mild, to moderate, to severe. At the severe level of CIN, the precancerous growth turns malignant; it becomes a carcinoma in situ (localized). If left untreated, the carcinoma progresses through four more stages of development, each of which is subdivided into two grades of severity. These grades indicate the location and spread of the carcinoma. The four stages and their subdivisions are described as follows:

In the beginning stages of the disease, cervical dysplasia is characterized by three stages of abnormality and severity (CIN-1,-2,-3), which later progress onto four stages of invasive carcinoma (Stages I through IV).

- CIN-1: Corresponds to a mild condition of dysplasia.
- CIN-2: Corresponds to a moderate condition of dysplasia.
- CIN-3: Corresponds to a severe condition of dysplasia, and carcinoma (in situ). The cancer, however, is found only in the layers of the cells lining the cervix, and has not yet extended deeper into the tissue lining.
- Stage I-A: Corresponds to a microinvasive carcinoma. The cancer is beginning to spread from the lining of the cervix into the deeper connective tissue.
- Stage I-B: Corresponds to an invasive carcinoma confined to the cervix. The cancer has now spread from the lining of the cervix into the deeper connective tissues.
- Stage II-A: Corresponds to a tumor extending beyond the cervix, into the upper third of the patient's vagina, but is still inside the pelvic area.
- Stage II-B: Corresponds to a tumor extending beyond the cervix, into the loose connective tissues around the patient's uterus (parametrium), but is still inside the pelvic area.
- Stage III-A: Corresponds to a tumor extending into the lower third of the patient's vagina.
- Stage III-B: Corresponds to a tumor extending into the patient's pelvic wall. At this stage, the cancer may be blocking the ureters (responsible for carrying urine from the Kidneys to the Bladder).
- Stage IV-A: Corresponds to a tumor extending into the patient's Bladder or rectum.
- Stage IV-B: Corresponds to a tumor extending into the patient's Liver or Lungs.

SYMPTOMS

Clinical symptoms include bleeding after sexual intercourse and between periods, abnormal bowel movements, or fatigue. Bleeding may also be noticed after severe exertion or straining during defecation. As the disease develops, the leukorrhea (vaginal discharge) may become filthy and mixed with blood, or foul and mixed with sloughed pieces of Body Fluid or tissue. Additional symptoms include lumbar, sacral and abdominal pain, Bladder irritation, frequent and urgent urination, blood-tinged vaginal discharge, unilateral lymphoedema, and unilateral ureteral obstruction (this indicates a very advanced stage).

TREATMENT

When Righteous Qi is increased through Medical Qigong therapy and prescription homework, the energy feeding the patient's cancer begins to decrease.

One Medical Qigong therapeutic technique used in China to treat cervical cancer is as follows:

1. Purge the diseased uterine area of pathogenic Qi using the Thunder Palm technique in conjunction with the Vibrating Palm to disperse the stagnation.
2. Use the "Yu" sound Qi projection into the uterine and cervix area to disperse Heat from the cancer cells.

3. Disperse the Excess Heat from the patient's Liver and cervix areas, leading the Toxic Qi out the patient's body via the right Gall Bladder Channel.
4. Fill and tonify the patient's Lower Dantian and Kidneys with Qi. Circulate the energy through the Microcosmic Orbit to improve Qi and Blood circulation through the Governing and Conception Vessels.

PRESCRIPTIONS AND HOMEWORK

The Conception Vessel moves Qi in the Lower Burner and uterus, and is the primary vessel used to treat uterine and cervical cancer; therefore, sexual activities are prohibited from the start of the treatments, until treatment is no longer needed.

The prescriptions and homework required for cervical cancer treatment are exactly the same exercises that are used for the treatment of uterine cancer.

PROSTATE CANCER

Prostate cancer is considered a malignant neoplasm, and is usually an adenocarcinoma of the prostate gland. It is the major type of cancer in males. Prostate cancer occurs in less than 1% in men under 50. Men with a family history of prostate cancer are three times more likely to develop it then the general public. Many prostate cancers remain dormant, but once awakened, can become life-threatening.

ETIOLOGY

The etiology of prostate cancer is unknown. Speculations suggest that prostate cancer can be related to an imbalance between male and female hormones. From a Western Medical perspective, the carcinogenesis is a multistep accumulation of genetic lesions. These lesions may result in uncontrolled cellular proliferation, a decrease in cellular death or an apoptosis, invasion, and the metastatic spread of the disease.

From a Traditional Chinese Medical perspective, prostate cancer is due to Excess Liver Fire and Kidney Deficiency. The suppression of anger and fear, as well as a diet consisting of a high alcohol intake, or consumption of too many hot spicy foods, may also cause, or contribute to prostate cancer.

SYMPTOMS

In the early stages there are no symptoms; however, as the disease progresses the inflamed prostate gland impedes urination and results in outflow obstruction, preventing the Bladder from emptying completely. Dull pain is experienced around the external genitals and Bladder. There is frequent burning, unfinished and dripping after urination with white discharge. Also, in some cases, there will be sexual function disorders (an inability to attain erection) as well as sciatica-like symptoms with pain radiating downward to the perineum and anus.

If the prostate is hard and firm, it indicates cancer; if the prostate is large and swollen, it indicates an infection. Inflammation of the prostate can be divided into acute and chronic conditions.

In acute prostatitis caused from Damp Heat in the Lower Burner, symptoms include pain and discomfort in the genital and Bladder areas, fever, and chills.

In chronic prostatitis, symptoms include dull pain in the urogenital area, discharge from the penis, discomfort during sexual intercourse, and frequent urination (especially during the night).

TREATMENT

One of the Medical Qigong therapeutic techniques used in China to treat prostate cancer is as follows.

1. With the patient supine, begin to purge the diseased prostate area of pathogenic Qi using the Thunder Palm technique in conjunction with the Vibrating Palm to disperse the stagnation.
2. Next, use "Yu" sound projection into the prostate area to disperse the Heat from the cancer cells.
3. Disperse Excess Heat from Liver and pathogenic Qi from the prostate, out of the patient's body via the right Gall Bladder Channel.
4. Fill and tonify the patient's Lower Dantian and Kidneys with Qi, and circulate the energy through the patient's Microcosmic Orbit to improve Qi and Blood circulation within the Governing and Conception Vessels.

PRESCRIPTIONS

Depending on the patient's condition, one or more of the following prescriptions may be given:

1. The "Guo" sound resonation is used to disperse the Liver Fire.
2. The Kidneys' "Yu" sound resonation is used to disperse Toxic Qi from the prostate.
3. Tonification and regulation exercises are prescribed for the Lower Dantian, Spleen, and Kidneys.
4. The following three exercises are used to treat prostate cancer, and were made popular in the West by Dr. Hong Liu.
    a. Sit at the edge of the chair with your feet flat on the floor. The right leg crosses over your left leg. With your left hand grasp the bottom of the right foot.

       Then extend your right hand out in front of the body, palm facing upward, while you imagine releasing toxic energy from your body through the mouth as you exhale. As you inhale, twist your hand as far as possible towards the right side keeping your eyes on the palm, while simultaneously pulling your foot towards the body and contracting the anus and perineum. This opens the Liver Channel and directs Qi into the Kidneys and prostate area.

       After completing the movement, hold your breath for a moment. Imagine Blood and Qi flowing into the prostate area and exhale while returning to the starting position. The exercise is repeated for 18 breaths per each side.

    b. The next exercise begins from a Wuji posture. Bend over as you flex your toes upwards. Hold this position as long as you can before standing erect, focusing on breathing naturally from the abdomen. This movement increases the flow of Qi and Blood into the prostate area. It is important to make sure this exercise is performed slowly. The exercise is repeated 9 times.

    c. This last exercise is done sitting on the floor while facing a wall. Place the balls of your feet against the wall while resting your heels on the floor. Wrap your arms around your bent knees, while keeping the back straight and breathing naturally through the Lower Dantian.

       While inhaling, focus on breathing from the lower abdomen instead of the chest. This causes the Qi of the Thrusting Vessel to stimulate the prostate gland, and increases the flow of Qi and Blood into the prostate area. The exercise is repeated for 18 breaths.

5. The "Filth Dispelling Meditation," is also prescribed, with the patient focusing on his prostate area. This meditation is practiced as follows:
    a. From a sitting posture, with the eyes closed, and the body relaxed, place the tongue up against the upper hard palate, behind the teeth.
    b. Breathe naturally and evenly.
    c. Imagine Qi whirling in through the upper area of the Bladder, circulating clockwise, building momentum as the energy flows down to the prostate area.
    d. Once the energy has reached the prostate, the patient will imagine the whirling Qi absorbing the noxious Heat and filthy Qi from the Bladder and prostate areas, transforming it into wind, which is dispelled out through the penis. The exercise is repeated 10 times.
    e. Next, gently close the anal sphincter while inhaling and imagine the Qi flowing into the body through the penis. This energy flows into the Lower Dantian, becoming transformed into wind. This wind begins circulating in a counterclockwise direction, spiraling up the body, through the Thrusting Vessel and exits through the mouth with each exhalation. This is also practiced for 10 repetitions.

f. Finally, focus the attention on the Lower Dantian; imagine the vital Qi returning back to its origin, while rubbing the abdomen in a clockwise direction to end the prescription.

LUNG CANCER (PULMONARY CARCINOMA)

Lung cancer, also called a "Bronchial Carcinoma," is a malignant Lung tumor that originates in the bronchi. It can also spread to the trachea appearing as an ulcer in the windpipe, a small flattened bump or nodule. It can extend into the body's lymphatic system, as well as into the blood vessels.

The most common type of bronchogenic tumor is the squamous cell or epidermoid (on the airway lining). The oat cell and adenocarcinoma are the next most common.

ETIOLOGY

Squamous cell cancer is usually associated with a history of cigarette smoking and second-hand smoke. Statistically it is the most common of all carcinomas and accounts for 40% of all male deaths. Other chemical carcinogens may cause Lung cancer, especially among workers in industrial and mining areas.

SYMPTOMS

The main clinical manifestations include: chest pain, coughing with scanty sputum (sometimes with blood), pectoralgia, fever, loss of appetite, loss of weight, weakness and breathlessness in the later stages due to a Lung Yin Deficiency.

TREATMENT

Purge the Excess Heat from the patient's Lungs and Liver. Tonify and regulate the patient's Kidneys and Mingmen area, then strengthen the patient's Spleen and Lungs.

PRESCRIPTION AND HOMEWORK

1. Have the patient practice the Dry Crying exercise for a period of 15 minutes twice a day (see Chapter 53).
2. Have the patient practice the Sun and Moon Rotation Technique (see Chapter 41), ending with the healing sound "Shang" for 24 breaths, 9 times a day.
3. Prescribe the Fast to Moderate Exhaling Breathing Method along with the Cancer Stepping Method for treating Lung diseases (see Chapter 15).
4. Have the patient practice the method of Taking in the White Qi, three times a day for 15 minutes each time to strengthen the Lungs.
5. Have the patient practice the method of Taking in the Blue Qi, three times a day for 15 minutes each time in order to strengthen the Kidneys.

LIVER CANCER

The Liver is the most usual site for the metastatic spread of tumors that disseminate through the Blood system. Carcinoma of the Liver is quick in development, high in mortality, and is regarded as one of the common malignant tumors.

ETIOLOGY

The etiology of Liver cancer is unknown. There are speculations suggesting that the following list of items may cause, or contribute, to the creation of Liver cancer:

- exposure to chronic stress and the suppression of anger,
- toxic poisoning (Liver cancer is usually associated with a long history of alcohol, drug abuse and chronic hepatitis), and
- a congenital weakness, with heredity being the predisposing factor.

SYMPTOMS

The Liver may have a single nodule, or multiple nodules. The main clinical manifestations include: distension and severe hypochondriac pain, hemorrhage of the digestive tract, and progressive hepatomegaly (enlargement). Its surface feels irregular on palpation (central depression or umbilications can often be detected).

TREATMENT

Purge the Excess Heat from the patient's Liver and Gall Bladder Channels, then tonify and regulate the patient's Kidney and Mingmen areas. Strengthen the patient's Spleen and Lungs, then regulate the patient's Liver.

PRESCRIPTIONS

1. Have the patient practice the Descend the Yang and Ascend the Yin Technique (see

Chapter 41), ending with the healing sound "Guo" for 24 times, 9 times a day.
2. Prescribe the Fast to Moderate Exhaling Breathing Method along with the Cancer Walking Method for treating Liver disease (see Chapter 15).
3. Have the patient face, or embrace, a tree while practicing the method of "Taking in the Wood Element Qi," but only upon inhalation. With each exhalation the patient should purge the toxic Qi, sending it into the ground. This prescription is practiced three times a day for 15 minutes each time.
4. Have the patient practice the method of "Taking in the White Qi," three times a day for 15 minutes for each session to strengthen the Lungs.
5. Have the patient practice the method of "Taking in the Green Qi," three times a day for 15 minutes for each session to strengthen the Liver.
6. Have the patient practice the method of "Taking in the Yellow Qi," three times a day for 15 minutes for each session to strengthen the Spleen.

ESOPHAGEAL CANCER

Carcinoma of the esophagus is one of the common malignant tumors, caused from a carcinoma of the squamous epithelium of the esophagus. This type of carcinoma is called "Ge Shi" or dysphagia in Traditional Chinese Medicine.

ETIOLOGY

The cause of esophageal cancer is unknown. There is speculation that the following list of items may cause or contribute to the creation of esophageal cancer:

- consumption of foods with a high content of nitrates,
- large quantities of spicy, hot foods, or mouldy food,
- chronically eating too fast, thus irritating the throat,
- strong alcoholic drinks,
- smoking,
- poor oral hygiene, resulting in tooth decay, and
- chronic stress and the suppression of emotions.

There are three types of esophageal cancer that invade the wall of the esophagus.

1. An ulcerous carcinoma of the esophagus that grows towards the outside of the esophagus. Dysphagia (difficulty in swallowing) is not evident in this type of cancer.
2. A tumor which grows in a circular formation. In this type of cancer, the lumen is narrow and easily obstructed.
3. The tumor attaches itself to one side of the esophagus, while the other side is still healthy and can still dilate. In this type of cancer, symptoms of obstruction appear slowly.

SYMPTOMS

More common in men over 40, carcinoma of the esophagus causes pain in the epigastric and sternal area. Swallowing aggravates the symptoms. The main clinical manifestations include the following symptoms:

- enlarged lymph nodes in the neck,
- difficulty in swallowing (dysphagia),
- excessive salivation,
- poor digestion,
- vomiting,
- loss of weight,
- pain in the chest and back, and
- emaciation and weakness.

TREATMENT

Purge the Excess Heat from the patient's throat, Lungs and Liver area. Tonify and regulate the patient's Kidney and Mingmen area, then regulate the Qi of the patient's esophagus, rooting it within the Lower Dantian.

PRESCRIPTIONS

1. Have the patient practice the "Dry Crying" exercise for a period of 15 minutes twice a day (see Chapter 53).
2. Have the patient practice the healing sound "Shang" for 24 breaths, 9 times a day (see Chapter 40).
3. Prescribe the Fast to Moderate Exhaling Breathing Method along with the Cancer Walking method for treating Lung disease (see Chapter 15).

4. Have the patient practice the method of "Taking in the White Qi," three times a day for 15 minutes for each session to strengthen the Lungs.

STOMACH CANCER

Carcinoma of the Stomach is regarded as one of the common malignant tumors. It is sometimes categorized as a carcinoma, lymphoma or sarcoma.

ETIOLOGY

The etiology for Stomach cancer is unknown. Speculations suggest exposure to chronic stress, and a suppression of emotions, may cause, or contribute to this disease. There is also an association between the development of gastric cancer and previous partial gastrectomies for benign diseases.

SYMPTOMS

The symptoms of Stomach carcinoma often do not appear until they have developed to the middle and late stages. Most common in men over 40, carcinoma of the Stomach causes a continual pain and burning sensation in the epigastric and sternal area, which is usually aggravated by swallowing. The main clinical manifestations include: shallow complexion, lack of appetite, loss of weight, extreme anemia, blood in the stool, debility, vomiting of partially digested food, and sometimes Blood that looks like coffee-grounds. The Liver may also be enlarged with nodules.

TREATMENT

Purge the Excess Heat from the patient's Stomach, Liver and Gall Bladder Channels, then tonify and regulate the patient's Heart and Spleen. End by regulating the patient's Kidney and Mingmen areas.

PRESCRIPTIONS

1. Have the patient practice the Descend the Yang and Ascend the Yin Technique (see Chapter 41) ending with the healing sound "Dong" for 24 times, 9 times a day (see Chapter 40).
2. Have the patient practice the method of "Taking in the Yellow Qi," three times a day for 15 minutes each time in order to strengthen the Spleen.
3. Have the patient practice the "Taking in the Red Qi," three times a day for 15 minutes each session to strengthen the Heart.

PANCREATIC CANCER

Carcinoma of the pancreas is regarded as one of the common malignant tumors. Statistics state that 22% of deaths from gastrointestinal cancer are due to cancer of the pancreas.

ETIOLOGY

The etiology for pancreatic cancer is unknown. Speculations suggest cigarette smoking and diet (in particular, a high intake of fat and / or meat) may cause, or contribute to the cancer. Recent investigations have identified a number of factors that may also contribute to the cause of pancreatic cancer, including: environmental factors, surgical or associated medical factors, genetic factors, and occupational exposures to toxins.

SYMPTOMS

This type of cancer is more common in men between 50 and 70. A carcinoma of the pancreas causes pain in the epigastric area, which starts as a dull ache and usually becomes aggravated by lying down. The main clinical manifestations include dyspepsia, diarrhea and constipation, loss of weight, nausea, vomiting and fatigue.

The symptoms of pancreatic cancer can sometimes vary in accordance to its exact location. The head of the pancreas is close to the duodenum, while its tail reaches to, and energetically connects with, the Spleen. The middle of the pancreas lies horizontally across the upper aspect of the abdomen.

1. Carcinoma of the Pancreas's head has as for its main symptom jaundice, due to the common bile duct of the Gall Bladder becoming obstructed. This obstruction causes the bile to back flow into the Liver and thus contaminates the Blood. This causes both the Gall Bladder and Liver to swell. As the amount of bile and Blood increases, it causes the skin, mucous membrane and sclera to become yellow, and the urine to turn brown. During the later stages, the skin color changes from a yellowish color to orange or dark yellow.
2. Carcinoma of the Pancrea's body has for its

main symptoms sharp abdominal pain and swelling. The abdominal pain reacts to the compression of the abdominal cavity nerve. This type of pain can occur sporadically, radiating to the patient's shoulder and back. The patient will notice this type of pain becoming aggravated when sitting up or lying down. Bending forward, however, can ease the pressure on the celiac nerve plexus and reduce the pain.

3. Carcinoma of the Pancrea's tail usually does not have detectable, early symptoms. At times, it can only be discovered when the tumor has metastasized to the peritoneum, Lungs, bones or other organs. Once the tumor has developed to sufficient size, the manifestation of symptoms include anorexia, fatigue, and loss of body weight.

TREATMENT

Purge the Excess Heat from the patient's pancreas, then dredge the Stomach, Liver and Gall Bladder Channels. Next, tonify and regulate the patient's Heart and Spleen, then regulate the patient's Kidney and Mingmen areas.

PRESCRIPTIONS

1. Have the patient practice the Descend the Yang and Ascend the Yin Technique (see Chapter 41), ending with the healing sound "Dong" for 24 times, 9 times a day (see Chapter 40).
2. Have the patient practice the method of "Taking in the Yellow Qi," three times a day for 15 minutes each session to strengthen the Spleen.
3. Have the patient practice the "Taking in the Red Qi," three times a day for 15 minutes each time in order to strengthen the Heart.

COLON AND RECTUM CANCER

Carcinoma of the Large Intestine or rectum is regarded as one of the common malignant tumors of the digestive tract.

ETIOLOGY

It has been long accepted that colorectal cancer is caused, or promoted, by environmental factors, especially diet. It is suspected that carcinogens are present in the patient's feces.

Also, chronic ulcerative colitis is considered a predisposing factor for colorectal cancer. The following chronic diseases are believed to be related: benign tumors of the colon and rectum (especially frequently occurring Large Intestine polyps), and chronic colitis (especially chronic amoebic dysentery and chronic ulcerative colitis).

SYMPTOMS

Colorectal cancer is more common in patients over 50 years of age. A carcinoma of the colon causes pain in the lateral abdominal area, which also may be umbilical. The main clinical manifestations include a sudden change of bowel habit (constipation or diarrhea), loss of weight, fatigue and Blood in the stool.

Large Intestine cancer can be divided into two quadrants of right and left intestinal dysfunction.

- Cancer on the right half of the Large Intestine is measured from the cecum to the right half of the transverse colon. The early symptom of this disease is dull pain and discomfort within the right epigastrium, or lower abdominal area. As the disease progresses, the pathological changes of the tumor initiate poisoning symptoms which appear as: weakness of the body, poor appetite, loss of weight, and anemia. In the midterm, or late stages, the patient can sometimes feel the tumor on the right side of their abdomen (located where the right Large Intestine stores food residue from the Small Intestine).
- Cancer on the left half of the Large Intestine is measured from the center of the transverse colon to the junction of the sigmoid colon and rectum. Symptoms of cancer in the left half of the Large Intestine appear earlier because the frequency of defecation increases with mucus and Blood in the stool. Moreover, because the narrow opening of the Large Intestine is now occupied by the tumor, it is difficult for the fecal matter to pass through, causing inflammation, as well as alternating diarrhea and constipation. If the tumor continues to grow, the intestinal cavity can be clogged, causing abdominal distention and toxicosis of the whole body.

TREATMENT

Purge the Excess Heat from the patient's Large Intestine and rectum area, purging and dredging the toxic Qi out the body and down the Stomach, Liver and Gall Bladder Channels. Next, tonify and regulate the patient's Kidney and Mingmen areas, emitting Qi through the soles of the patient's feet. End with regulating the patient's Fire and Water Qi through the Fire Cycle of the Microcosmic Orbit.

PRESCRIPTION AND HOMEWORK

Have the patient practice the "Filth Dispelling Meditation," focusing on the Large Intestine and rectum area. The meditation should be practiced as follows.

1. Begin from a sitting posture, eyes closed, body relaxed, with the tongue placed up against the upper hard palate, behind the teeth.
2. The breathing should be natural and even.
3. Imagine Qi whirling in through the upper orifice of the Stomach, circulating clockwise through the Small Intestine, building momentum as it flows to the Large Intestine.
4. Imagine the whirling Qi driving through the colon. As it moves through the colon, the whirling Qi begins absorbing the noxious Heat and filthy Qi from the Large Intestine, transforming it into wind, and dispelling it out the anus. This is practiced for 10 repetitions.
5. Next, gently close the anal sphincter while inhaling; imagine the Qi in the lower abdomen again becoming transformed into wind. This wind begins circulating in a counterclockwise direction, spiraling up the body, through the Stomach, and is expelled out the mouth. This is also practiced for 10 repetitions.
6. Finally, focus the attention on the Lower Dantian; imagine the vital Qi returning back to its origin, and begin rubbing the abdomen clockwise to end the prescription.



Fig. 7.15 *Three Thrusting Channels down to the Ground.*

A. Bring the Energy Down to the Soles of the Feet

1. Left Thrusting Channel

Split the pearl in two, and bring the energy from the perineum down the back of both legs to the backs of the knees, and then down to the heels and soles of the feet. Stop for a while, and absorb the Earth Energy through the soles. Then bring the energy up the front of the legs through the big toes, knees, front of the thighs, all the way back to the perineum. Recombine the pearl at the perineum. Then run the energy through the Left Thrusting Channel by slightly tightening the left side of the anus and looking up with the left eye. Bring the pearl all the way up through the left hemisphere of the brain and left crown, and out to three inches (seven and a half centimeters) above the crown. Relax, and bring the pearl down to the perineum.

CHAPTER 55

QI EMISSION THERAPY FOR RADIATION AND CHEMOTHERAPY

The purpose of Cytotoxic treatments (radiation and chemotherapy) is to kill the dividing cells responsible for the formation of the tumor mass. The well-known side effects of these types of therapy are loss of hair, loss of appetite, nausea, vomiting and damage to the patient's skin and gastrointestinal tract. When facing radiation and chemotherapy, the damage to the patient's immune system, although less obvious, is the major concern for the Qigong doctor. The cure of the cancer inevitably lies in activating and increasing the function of the immune response, so that it can recognize and eliminate the malignant tissue.

In China, Medical Qigong Therapy is commonly prescribed as an adjunct to both radiation and chemotherapy. The value of Medical Qigong Therapy is that it is very useful in reducing the harmful side effects caused by both radiation and chemotherapies, as well as enhancing the patient's immune system. Both radiation and chemotherapy assist the body in weakening a pathogenic cluster, but do not completely kill all of the tumor or cancer cells. That function is still left to the patient's immune system (which has consequently been weakened by the radiation or chemotherapy). Because Medical Qigong treatments, prescriptions and meditations enhance the body's immune system, its utilization as a adjunctive therapy is paramount.

MEDICAL QIGONG THERAPY AND RADIATION THERAPY

In most cases, radiation is much safer than chemotherapy because it can be directed into one specific area of the patient's body. However, it may also cause scarring that can interfere with the patient's internal organ function. Although radiation therapy is strong, its effect on the patient's body can be corrected by the Qigong doctor with dredging, purging, dispersing and tonifying techniques. The tissue damage left after radiation therapy should be rectified by dredging, purging and dispersing the afflicted area first. Then, after the toxic Heat has been purged, begin to tonify the patient's supporting organs and tissues surrounding the treatment area.

Sometimes the harmful side-effects of radiation therapy can be avoided by giving the patient Resonant Sound Therapy. In order to alleviate the patient's toxic Heat and pain, it is important for them to practice the "She" sound to cool the tissues after radiation treatments. After the organs have been sufficiently cleansed, the doctor may then tonify the patient's tissues, as well as the Wei Qi Fields, which have been damaged by the radiation therapy.

MEDICAL QIGONG THERAPY AND CHEMOTHERAPY

All forms of chemotherapy are cell-killing agents that damage the DNA and injure actively dividing cells, including those of the body's immune system. The tissue damage after chemotherapy is extremely extensive; the white blood cells decrease, causing secondary infections. Unlike radiation therapy, which is generally isolated to specific areas of the patient's body, chemotherapy affects all of the body's internal organs.

When treating patients who have undergone chemotherapy, it is important for the Qigong doctor to dredge, purge and disperse all the patient's Yin and Yang organs. As with radiation therapy, Sound Resonation Therapy is also mandatory in alleviating the patient's pain.

It is important for the patients to practice the "She" sound to cool the tissues after chemotherapy treatments. Specifically, cancer patients should pronounce the "She" Healing Sound therapy several times a day when their blood count is low, after both chemotherapy or radiation therapy. The sound "She" is pronounced six times. Its high pitched sound is in the straight tone, and its low pitched sound is in the dropping and rising tone. This sound is dropped and replaced by the sound "Ha," or the sound for the specific internal organ, as soon as the red and white blood count reaches a normal level.

After pronouncing the sound "Ha" for a certain period of time, add the sounds for the specific internal organs that have been affected (for example, add "Shang" for a patient with Lung cancer, and "Guo" for a patient with Liver cancer, etc.).

When treating the patient, after the diseased organs have been sufficiently cleansed, the doctor may then tonify the patient's Blood, Jing and tissues, as well as their energetic fields, which have been damaged by the chemotherapy.

RELIEVING SYMPTOMS ASSOCIATED WITH RADIATION AND CHEMOTHERAPY

After receiving radiation or chemotherapy, patients may suffer from several internal complications due to the severe organ and tissue trauma caused by these therapies. The following are six common problems resulting from radiation and chemotherapy.

1. A gastrointestinal infection can result from both radiation and chemotherapy, which have a tendency to burn up the body's Yin. This frequently results in causing Rebellious Qi, which is accompanied by such symptoms as nausea, vomiting, and poor appetite. Treat by tonifying the patient's Stomach Yin by prescribing herbs, and use Jing Point Therapy to quiet the digestion by tonifying Pc-6, St-36 points, as well as the Ear Shenmen points.
2. An infection of the Large Intestine can occur from the accumulation of toxins in the Lower Burner creating Damp Heat Symptoms (caused from radiation and chemotherapy). These toxins can cause abdominal pain, constipation or diarrhea with bloody mucous. Treat by tonifying the patient's Yin to prevent loss of Body Fluids (also give astringent herbs), and use Jing Point Therapy to stop any internal bleeding, by tonifying St-25, St-36, St-37, St-38, LI-4 and LI-11 points.
3. A Urinary Bladder infection can be caused by both radiation and chemotherapy that have a tendency to create Damp Heat in the Lower Burner. Damp Heat in the Lower Burner can result in cloudy, bloody and scanty urination, with a feeling of an urgency to urinate but an inability to do so. To treat, use Jing Point Therapy and tonify Sp-6, Sp-9, CV-2, CV-3, Bl-23 and Bl-29 points.
4. Edema in the limbs can occur from both radiation and chemotherapy that have a tendency to create Wind Damp and Deficiency, which leads to an accumulation of Body Fluids in the extremities. Treat by tonifying the Spleen and draining the body of Dampness. Use Jing Point Therapy to tonify Sp-6, Sp-9, Lu-7, LI-4, and Bl-20; also prescribe herbs.
5. A diminished white blood cell count can be caused by radiation and chemotherapy and can lead to secondary infections. Treat by tonifying the patient's Blood and Jing, and prescribe herbs.
6. Pneumonia can be caused by radiation and chemotherapy that have a tendency to cause damage to the Lungs. When both the Lung Qi and Yin Qi are damaged, pneumonia can result. Treat by tonifying the patient's Yin and Lung Qi, and prescribe herbs to enhance the immune system.

CHAPTER 56
QI EMISSION THERAPY FOR SURGERY

Medical Qigong Therapy is useful for treating patients before, during and after surgery. Qi emission can be used to reduce the patient's bleeding, enhance the immune system, minimize the risk of infection, strengthen the body, and to accelerate the recovery rate. Medical Qigong modalities are involved in preoperative therapy, surgery, postoperative therapy, follow-up therapies and remedial prescriptions.

MEDICAL QIGONG AND PREOPERATIVE THERAPY

Although Medical Qigong Therapy has had incredible results in healing and in stopping the progression of certain diseases, it is not a "cure-all." As with other clinical modalities, it has its own limitations. Currently, conventional medicine only utilizes three modalities for treating tumors and cancer; these include surgery, radiation and chemotherapy. In the healing process, undergoing surgery is sometimes unavoidable, and should never be viewed by the patient as a defeat, but only as a necessary step in the healing transition.

Having to face surgery should not be viewed as a negative reflection of a Qigong doctor's healing potential, nor as a patient's inability to heal. Surgery should be viewed as a necessary life saving intervention, that can firmly establish the patient on the road towards health and recovery. It is a positive affirmation of the patient's commitment to getting well and taking responsibility for the healing. Sometimes, surgery is a necessary step towards health and healing.

Before surgery, it is important for the doctor to consider the emotional relationship that the patient has developed with his or her diseased tissues. The mental, emotional, energetic and spiritual aspects of a disease must not be ignored.

The doctor's involvement with the patient and the tissues which are about to be surgically removed is extremely important, since this emotional interaction affects the patient's healing potential. For healing to take place, a trusting relationship with the patient must first be solidly established; this includes a compassionate attitude of the doctor towards the tissues that will be removed. The doctor models the correct attitude to facilitate an accelerated healing for the patient. It is believed that scar tissue formation is in direct proportion to the patient's fears and negative expectations surrounding the surgery. These fears and expectations form energetic and spiritual attachments to the physical body. Often the patient attempts to disconnect these spiritual attachments out of fear and survival instinct.

A patient is spiritually, emotionally and energetically interconnected with his or her body. This energetic attachment includes any and all organs, organ systems, or areas of the body which can be involved in the operation.

A patient may sometimes feel disillusioned about his or her own interpersonal relationship with the body, and try to disconnect all energetic attachments to the body's tissues out of fear and survival instinct. It is important for the Qigong doctor to help the patient get in touch with the suppressed feelings of loss surrounding the tissues which will soon be operated on. This is because surgery represents the death of a relationship with part of the self. Although the relationship that the patient has with the diseased organ is not considered a healthy one, it exists nevertheless. Allowing the patient to deny his or her true feelings related to the surgery interferes with the healing process. Denial may lead to increased scar tissue formation, and can promote the return of certain disease formations.

The Qigong doctor therefore encourages the patient to talk to, and "brief," each organ and tissue area regarding the surgical procedure to prevent further denial, and to promote the release of feelings. Otherwise, the patient may experience feelings of loss, grief and depression; this reaction can of course also be due to the aftereffects of the anesthesia. It is important that these feelings be experienced and expressed before the surgery. After the surgery, the patient may then experience feelings of relief and gratitude about the new changes in his or her body.

To prepare for surgery, the patient is usually given Medical Qigong meditations and prescriptions that strengthen the Lower Dantian, Kidney and Mingmen areas. One, or several sessions may be specifically devoted to allowing the patient to connect with the diseased organ(s), as well as the regions that are to be operated on. A request for divine intervention can facilitate the patient's relinquishing control, and for the removal of any and all energetic armor surrounding the diseased area (and the subsequent release of emotions associated with this armoring). The patient is then encouraged to disconnect any energetic attachments that the diseased tissues have formed with the surrounding cells, facilitating a final closure. This gradual process allows for an easier transition, as the patient's body must completely release any attachment to the diseased tissues during surgery.

Just before surgery, the patient is given a meditation, and encouraged to imagine a divine white light energy submerging and enveloping the regions of the body which are to undergo the operation. The Lower and Middle Dantians, as well as the areas which will soon be operated on, should also be energized. In addition, the Liver should also be energized to make sure that the Blood coagulates properly during the surgery.

USING MEDICAL QIGONG FOR ANESTHESIA

According to research on Western Surgeries (presented at the Second International Symposium on Memory and Awareness in 1992), patients who undergo anesthesia may be aware of both the pain and conversations within the operating room. Many kinds of drugs used to supplement anesthesia, such as neuromuscular blocking agents, paralyze all the muscles in the body but do not affect the central nervous system and consciousness. During surgery, patients have been observed flinching, twitching and making other facial expressions. Many patients later can give an accurate detailed account of the surgical procedure and conversations between the doctors and nurses. Even when unconscious, patients (whether energetically inside or outside of their bodies), can record, see and remember everything.

Qigong energy emitted during surgery, can however, reduce pain and wound shock, as well as calm the patient's Shen. Qi emission also reduces postoperative complications such as respiratory tract infection, functional disorders of the gastrointestinal tract, retention of urine, etc. The energy received by the patient also speeds up the healing process.

Medical Qigong therapy is found to be very useful in relieving pain by affecting the body's neuro-chemicals. The energy stimulates the peripheral and cutaneous nerves that carry sensory information, via the spinal cord, to the brain. This stimulation of the cutaneous nerves activates neurotransmitters which carry pain messages to the brain, and facilitates the closure of the body's pain-relay gates. The brain produces endorphins, or endogenously generated morphine-like chemicals in response to this closure. The body's opiate receptors are then able to dull the pain. This process is the basis for Qigong Anesthesia. Because Medical Qigong therapy safely produces an analgesic affect on the body's cutaneous tissues, its use in hospitals for surgery as well as for pre and postoperative procedures is gradually increasing.

The first operation in which Qigong anesthesia was applied (recorded in modern times), was performed successfully for the removal of a thyroid tumor in the Shanghai #8 People's Hospital, on May 9, 1980. Qigong Master Lin Hou-sheng demonstrated the ability to induce anesthesia during surgery by pointing his fingers at specific acupuncture points, using external Qi projection without the use of any Western anesthetic. The patient's blood pressure, pulse and respiration rate remained stable during the operation, and the patient's physiological function remained normal after the operation. The success of the Qigong anesthesia boosted the resident doctor's confidence and laid a solid foundation for future applications of Qigong anesthesia in surgical operations.

Qigong anesthesia has begun to follow in the wake of the widely accepted acupuncture anesthesia, as a holistic alternative to conventional pharmaceutical methods. The number of cases treated in China with Qigong anesthesia is steadily increasing, primarily for the following six benefits.

1. Arresting the patient's pain,
2. Resisting the pulling reflex action or shock reaction of the body's internal tissues and organs when the scalpel is inserted,
3. Reducing infection,
4. Reducing the body's opposition or contrary action/reaction to operative wounds,
5. Preventing wound shock (response of the body to the tissue trauma), and
6. Promoting the healing of wounded tissues.

Since Qigong analgesia is effective through the stimulation of certain points on the body's surface, both the location of the points, and the type of energetic application are crucial. There are three methods commonly used in selecting points: According to the Channels, According to the Segmental Innervation, and According to the Auricular Points.

1. The analgesic approach used according to the patient's channels includes two main applications:
   - The selection of points according to the course of the channel which traverses the site of the operation, and
   - The selection of points according to the differentiation of symptoms and signs of a disease, as well as the responses that may be elicited from the patient's body during the operative procedure.
2. The analgesic approach used according to the segmental innervation includes three main applications:
   - The selection of points according to the adjacent segment, or an area that is supplied by the same spinal nerve, or an adjacent spinal nerve of the operative site,
   - The selection of points according to the remote segment, in an area not supplied by the same spinal nerve, or an adjacent spinal nerve (on the operative site), and
   - The selection of points according to the stimulation of the nerve trunk within the same segment, stimulating directly the peripheral nerve of the operative site.
3. The analgesic approach used according to the Auricular Points employs the insertion and stimulation of acupuncture needles with Medical Qigong Therapy, and includes three main applications:
   - The selection of points according to the corresponding Auricular areas pertaining to the operative site and its involved internal organs,
   - The selection of points according to the theory of the Yin and Yang Organs pertaining to the operative site and its involved internal organs, and
   - The selection of points according to such things as tenderness, reduction of electro-resistance, the appearance of deformation and/or discoloration when a certain internal organ or area of the body is affected.

It is important preoperatively that the patient have confidence in the doctor's method of Qigong application. Any misgivings should be dispelled by explaining the procedure to gain the patient's full corporation and trust. In order to know the level of response that the patient will experience, it is necessary to test the patient's response to Qigong anesthesia prior to any surgery.

To use external Qi as an anesthetic, the Qigong doctor must first focus Qi into his or her Lower Dantian, increase its charge and density and then extend it out through the palms, or sword fingers, into the patient's body through specific channel points. The goal is to numb a specific area on the patient's body without touching the patient.

When Qigong anesthesia is being administered successfully, 96% of the nerve fibers responsible for pain sensation become anesthetized and the patient loses consciousness within ten minutes. Ten minutes after cessation of the Qigong anesthesia emission, 24% of the anesthesia has disappeared; while 72% of the tissue remains numb. The remaining tissue quickly recovers from the anesthetic effect and the patient quickly returns to consciousness.

Patients suffering from pain caused by such conditions as cancer or dysmenorrhea also respond positively to Qigong anesthesia.

MEDICAL QIGONG THERAPY AND SURGERY

Surgery has been performed in China for thousands of years. In ancient times, the legendary physician Hua Tuo was noted, not only for his expertise in Medical Qigong, acupuncture, massage and herbs, but also for his surgical skills as well. In Western culture, surgical therapies are applied for the removal of tumors, cysts, and abnormal tissue growth, as well as the transplantation of organs (heart, lungs, and kidneys) and the replacement of dysfunctional systems (joint replacement). Surgery, however, having a potential to both hinder and obstruct the body's flow of life force energy, is generally considered a last resort modality.

During surgery, the Qigong doctor assists the surgeon by applying External Qi Emission to the patient's body, energizing and strengthening specific areas. This is done to reduce pain and alleviate or eliminate the pulling reflex action (shock reaction) of the body's internal tissues and organs when the scalpel is inserted, prevent infection, and reduce bleeding.

When assisting surgeons during an operation, I personally have found that it is important to maintain a physical connection with the patient's body before beginning the Qi emission, until the anesthesia has fully taken effect. As the anesthesia relaxes the patient's tissues, the Qigong doctor can feel and see the patient's spirit leave the body.

Just before the scalpel begins its first incision, it is important for the Qigong doctor to physically disconnect from the patient's body. Even though the Qigong doctor has physically disconnected from the patient's tissues, it is extremely important for the Qigong doctor to increase his or her energy extension deeper into the center core of the patient's body. This protects the Qigong doctor from experiencing the shock, and initial trauma from the scalpel's first incision, which resonates throughout the patient's entire body.

It is also important for the Qigong doctor to focus the attention on extending and circulating his or her energy deep into the patient's Taiji Pole while the surgery is being performed. As the patient begins to lose Qi and Blood due to the operation, the Qigong doctor replenishes the patient's lost Qi, as well as energizes the incoming Blood from the transfusion. The Qigong doctor should also slow down the bleeding by slowing the patient's pulse.

During surgery, the surgeon's scalpel will sever several of the patient's channels as the doctor cuts through the surface of the skin and continues into the deeper regions of the patient's body. Each channel that is being disconnected will weaken the patient's energetic field corresponding to that specific organ or organ systems. It is the Qigong doctor's responsibility to maintain connection with the patient's energy field, and also to monitor and maintain the patient's energy level. The Qigong doctor maintains this connection as the surgeons open up the patient's body cavity, move internal organs, remove the diseased tissues (and any associated structures), and then sutures and closes the patient's body cavity.

When the patient is being sutured, the Qigong doctor must facilitate the patient's circulation of Qi through the Microcosmic Orbit; this stimulates the re-connection of any of the patient's internal and external channels which have been severed. The Qigong doctor must also change and rebuild the Energetic Grid formations in the body's internal and external energetic fields. The patient's Energetic Grid is reconstructed to a pre-diseased pattern to prevent the regrowth of the disease.

MEDICAL QIGONG AND POSTOPERATIVE THERAPY

The separation and restructuring of the inner fasciae that occurs during surgery can cause serious postoperative problems by either stopping the Qi from flowing (causing stagnations), or altering the energy's natural course (causing deviations). This is why after the surgery has been completed, it is extremely important for the Qigong doctor to immediately dredge and disperse the Turbid Qi from the patient's body. This is performed by energetically combing over the fresh incisions, to reconnect the patient's energetic preoperative patterns. Energetic combing also promotes the rapid healing of the patient's wounded tissues, reduces the formation of scar tissue, and continues to alleviate the effects of the surgery.

To facilitate an escalated healing, the Qigong doctor must also energize the patient's Kidneys and any energetic field which may have been depleted. Also, to bring the patient's temperature back to normal, and to disperse any feelings of nausea after the anesthesia and shock of surgery wear off, certain Heart, Pericardium and Stomach Channel points require stimulation.

It is important to note that after an operation, the patient's Dantians and all the body's tissues have been depleted, and are in need of revitalization. While the patient is healing, the color of the aura (located in the Wei Qi field surrounding the area of the surgical trauma) is usually dark to light gray. To increase the healing potential, the Qigong doctor gives the patient specific prescriptions in accordance with the internal organ(s) affected, such as white light meditation images. This is prescribed to energize and replenish the patient's damaged tissues and energy fields. The Qigong doctor also continues to work on rebuilding, reconnecting and reinforcing the patient's channels and Energetic Grids which the surgeon has severed during the operation.

MEDICAL QIGONG THERAPY AND RECREATING ORGAN ENERGY

Once an organ has been removed, there remains an energetic "void" within the spatial cavity of the patient's tissues. The energy of the organ, however, still exists within the patient's body as a "Phantom Organ." This energetic phenomena is due to the creative "blue-printing" of the prenatal and postnatal formation of the body's tissues. Because mass and energy are interconnected and interchangeable, it is therefore possible to energetically stabilize, as well as energize, the spatial cavity wherein the surgically removed organ once resided. To assist the patient in recreating active organ energy, the Qigong doctor prescribes the following meditation:

Lungs	Brilliant Pure White
Large Intestines	Abalone-Shell White
Stomach	Deep Yellow
Spleen	Orange Yellow
Heart	Red with Blue Tint
Small Intestine	Pink
Bladder	Deep Blue
Kidneys	Light Pastel Blue
Pericardium	Purple Red
Triple Burners	Orange Red
Gall Bladder	Pale Chartreuse
Liver	Dark Green

Figure 56.1. Organ Color Chart

STAGE 1 - THE HOOKUP

Generally several days after the surgery, while the patient is still recovering, the Qigong doctor has the patient imagine him or herself being connected to the Heavens and rooted to the Earth. Next, the patient uses color visualization.

STAGE 2 - CHOOSING THE APPROPRIATE COLOR

To prescribe the correct color, it is important for the Qigong doctor to know which organ or organ systems have either been removed, or seriously affected by the surgery. The patient is then assigned specific color meditations to tonify and strengthen the energetic fields that support the traumatized tissues. These meditations are also used to reestablish a physical, mental, emotional, energetic and spiritual connection to the area of trauma.

Figure 56.1 categorizes the general colors associated with the body's organs and channels. These colors can be viewed as extensions of energy originating from the original organs.

STAGE 3 - CLEANING AND ENERGIZING THE SPATIAL CAVITY

After the doctor has selected the proper organ color, the patient is given specific images used to cleanse, purify, and energize the tissues. These meditations create a solid energetic transformation that stabilizes the patient's energetic field.

1. The Cleansing and Purifying meditation is as follows. The patient imagines that his or her fingers and toes are straws. As the patient inhales, he or she will imagine divine white light energy flowing from the Heavens and Earth into the fingers and toes, filling the specific area which has been traumatized by the surgery (Figure 56.2). While exhaling, the patient imagines any pathogenic Qi leaving the tissues and body via the fingers and toes. The patient continues to perform this cleansing meditation for several minutes until he or she feels that the specific area has been purified.
2. The Creating and Energizing meditation requires that the patient imagine a clean, vibrant color (the Five Element Color associated with the particular organ), flowing into the spatial cavity, and areas, surrounding the removed organ. As the patient inhales, the organ color fills the vacant cavity, energizing the remaining energetic structure and surrounding tissues. The patient continues with this imagery until the specific organ area is full of heat, light and vibration (Figure 56.3). Because the surgery has permanently removed the organ from the patient's body, it is important for the patient to continue with this meditation every day for the rest of his or her life.



Figure 56.2. As the patient inhales, he or she will imagine the divine white healing light flowing into his or her body through the fingers and toes. This image is used to purge the patient's body and cleanse the tissues.



Figure 56.3. Once the patient is cleansed, in order to energize the tissues, he or she will imagine a clean vibrant energy color flowing into the specific spatial cavity associated with the removed organ.

MEDICAL QIGONG THERAPY AND ORGAN TRANSPLANTATION

Each particular organ in the human body has its own unique history and experience. This emotional memory and experience is active in the donated organ, as well as in the patient's diseased organ. Before the body can, or will receive a foreign organ, there must first be a time of reconciliation between the memories stored within the negative (as well as positive) physical cells of the organ soon to be replaced, and that of the donor's organ. To assist the surgeon in transplanting an organ, the Qigong doctor must perform visceral cleansing, preparation and purification of the transplanted organ. This method is explained in the following three stages:

STAGE 1

The patient must release all attachment to the departing organ. This includes all negative (as well as positive) physical, mental, emotional, energetic and spiritual memories and experiences.

STAGE 2

The history and emotional memory of the transplanted organ must be cleansed. This includes all negative (as well as positive) physical, mental, emotional, energetic and spiritual memories stored within the donor's organs.

STAGE 3

The relationship between the patient's tissues and the spatial cavity wherein the initial diseased organ was, or is located, must be established and harmonized.

The patient's body will either receive or reject the transplanted organ due to unresolved emotional trauma stored within the patient's tissues, or within the transplanted organ itself. Current research reveals that emotions trapped within transplanted organs can surface within the patient's subconscious mind, affecting his or her behavioral patterns. This is manifested through certain unnatural behavioral traits, which are transferred via the donated organ to the patient.

A famous example of a lingering emotional connection between an organ donor, the organ, and the recipient is described in the following true story. A few years ago a young woman (vegetarian) received a heart transplant from a young man who died in a motorcycle accident. Upon being discharged from the hospital, the woman began craving Chicken McNuggets, which was the young man's favorite food. This was in direct opposition to her previous diet and eating habits.

It is important to note here that organ rejection is not always due to the donor or patient's unresolved emotional issues. Organ rejection can also be caused from biological reactions complicating the acceptance of the foreign tissue.

FOLLOW-UP AND REMEDIAL PRESCRIPTIONS

The follow-up and remedial prescriptions will be determined according to the specific type of surgery the patient has undergone. The prescriptions must be designed to purge, strengthen and regulate any organ(s) that have been weakened by the surgery. Follow-up and remedial prescriptions must also circulate the patient's energy to reduce any energetic stagnations which may have been caused by internal organ movement and fascia damage. This will assist the patient in an escalated recovery, as well as reduce postoperative depression, which often follows after major surgery.

Sometimes, when assisting a patient who is healing from a severe disease (i.e., malignant tumors), additional Western therapies such as radiation or chemotherapy are required. The following is a testimonial by a patient of mine, Thea Sagen (female - age 50), illustrating the use of Qigong therapy in combination with radiation therapy.

Here is a summary of events surrounding my pancreatic surgery, June 16, 1997 at Community Hospital of the Monterey Peninsula.

"On June 16, 1997, emergency surgery to remove a fist-sized tumor from the tail of my pancreas, resulted in my former Sifu (Martial Arts Master), Jerry Alan Johnson, changing roles to become an "Energy Therapist." Thanks to my admitting physician, Dr. Stephanie Taylor, who facilitated the arrangement, Dr. Johnson was the first representative of Chinese Medical Qigong therapy allowed to enter surgery at the Community Hospital of the Monterey Peninsula.

2. Middle Thrusting Channel

From the perineum, split the pearl, and bring the pearl down the backs of both legs to the soles of both feet. Absorb the Earth Energy through the soles, then move the energy up to the toes, to the knees, returning to the perineum. Recombine the pearl at the perineum. Now bring the pearl all the way up the Middle Thrusting Channel, squeezing the middle of the anus and looking up with both eyes. Bring the pearl all the way up through all the organs and glands to the crown, and out to three inches (seven and a half centimeters) above the crown. Then bring it down to the perineum again.

3. Right Thrusting Channel

From the perineum, split the pearl, and bring it down the backs of both legs. Absorb the Earth Energy through the soles of the feet. Then bring the pearl up again to the perineum. Recombine the pearl at the perineum. Use the right anus muscle, look up with the right eye, and bring the pearl all the way up the Right Thrusting Channel through the right hemisphere of the brain and out of the crown three inches (seven and a half centimeters.) Bring it down to the perineum.

Continue bringing the pearl to the Thrusting Channels in the following sequence: left, middle, right, middle, left, middle, right, middle, and left, finishing each step by looping the pearl through the leg route. End on the left side of the perineum. Swallow the saliva, as described before.

B. Bring the Energy into the Ground

Once you have practiced bringing the pearl down to the soles of the feet for a while, add a new step. Begin by shooting the energy from the perineum down the backs of the legs and through the soles of the feet, from six inches to one foot into the ground. Feel a connection or rooting to the earth, then draw the energy up to the soles of the feet, to the toes, up the front of the legs, and into the Thrusting Channels.

With this step you have completed opening all the Thrusting Channels. Practice for two or three weeks until you develop full control of the energy traveling through these channels.

7. Men and Women Now Practice Differently

At this stage all the Thrusting Channels and Leg Routes are

As my Energy Therapist, Dr. Johnson conducted a preoperative session during which he facilitated the energetic and emotional release of my tumor. He then accompanied me into the four hour surgery, during which he maintained my energy levels, while reminding my tissues of their preoperative energetic patterns in order to facilitate rapid healing. He continued to work with me through the postoperative healing, and followed up several days after surgery. It was his vital support and insights that helped me to undergo the recommended course of radiation therapy.

The following is a synopsis of the Medical Qigong therapy that I experienced along with the traditional Western modalities used to treat my pancreatic islet-cell tumor.

Phase 1. The Preoperative Stage. Consisted of a Medical Qigong session directed toward putting me in touch with the tumor, my relationship to it, and the emotions associated with it. This was followed with an atonement with the Divine and relinquishment of control, removal of the armoring around my tumor, and subsequent release of emotions with it. I actually "saw" the disconnected energetic attachments of the tumor as they detached from my organs and were blowing like ostrich feather segments in a wind. I also saw a bright neon sign on the tumor that identified its emotional source. This entire process took only an hour, yet it facilitated closure with the tumor in order for me to easily release it during the surgery, which immediately followed the session. It also provided me with insights that helped my emotional healing over the months following surgery.

Phase 2. Surgery. I entered surgery without any sedatives and was filled with a tremendous sense of peace and empowerment in knowing that the hospital was honoring my energetic, as well as my physical needs. The surgery lasted for four hours during which Dr. Johnson connected with my energy fields and monitored, as well as maintained, my energy levels. He continued treating me, and working with my energetic fields, as the anesthesia was administered, and as the two surgeons opened my cavity, moved structures, removed the tumor (along with the tail of my pancreas and the spleen), and then sutured and closed my abdominal cavity.

Throughout the surgery Dr. Johnson stood at my head, where energy enters through the crown, and facilitated the running of energy into my center channel in the core of my body. He described his work as following the actions of the surgeons, and my body's response to these actions: the incision, the movement of internal organs, the resection of the tumor, and the final suturing. He used this opportunity to change the energetic grid formations in the tumor bed to prevent regrowth of the tumor, which was malignant.

Phase 3. The Postoperative Stage. This stage involved a continuation of the mitigation of the effects of surgery. He worked to tonify my Kidneys, to bring my temperature up, and to offset the shock of surgery, as well as used acupressure points to calm my heart and stomach during the nausea. I was reminded upon awakening, to do my Microcosmic Orbit exercise. Dr. Johnson then proceeded to "dredge" or comb over the incision to reconnect my pre-energetic channel and tissue patterns in order to facilitate healing, and to reduce scar tissue. The healing of the incision was fast. My doctors later remarked at how quickly I healed, and how little scar tissue there was compared to similar surgeries.

Phase 4. Follow-Up and Remedial Prescriptions. During the days following surgery, Dr. Johnson taught me several meditations: The "Divine Healing Light Meditation" for healing the tumor bed and incision, and the "Heaven and Earth Spleen Meditation" that fuses a ball of energy where the spleen once was – allowing me to continue to produce the energetic pattern of the spleen within my body. I began doing these meditations the day following surgery for the week of hospitalization, and continued to practice them along with the Microcosmic Orbit exercises throughout my recovery.

Phase 5. Radiation. After several weeks of recuperation, I was scheduled to received radiation treatments daily (Monday through Friday) for six weeks. Each day I would perform the Medical Qigong exercises (vocal and physical prescriptions) outdoors in a field overlooking the ocean.

Then I would drive to the hospital for the 15 minutes of radiation, followed by a session with Dr. Johnson every other day. I understood that the Medical Qigong exercises and sessions would offset the heat in the tissues while protecting the surrounding organs from unwarranted harm. There was concern about the possible loss of function in one kidney, but blood tests during the treatments showed no noticeable effects on them, or on my liver. In addition, unexpected by-products of the Medical Qigong sessions involved the release of emotional memories and an experience of the Divine in my healing process.

On alternate days after radiation, I had acupuncture and pranic healing with Jason Gill L.Ac. who teaches classes in Chinese Herbs and Traditional Chinese Medicine at Dr. Johnson's International Institute of Medical Qigong. Through these treatments, and the use of Chinese herbs, my immune system was strengthened. These complimentary modalities, combined with my body's own healing abilities and visualization practice, enabled me to avoid the typical side-effects of nausea and diarrhea. Aided by the positive energy from these two therapists, I was able to maintain my energy levels in sufficient quantity to continue driving to the radiation treatments on my own.

It is hard for me to imagine what this entire experience might have been like without the support of a doctor of Medical Qigong. I am truly grateful for Dr. Johnson's dedication, discipline and expertise that enabled him to be present for me throughout all aspects of this illness. It was a gift that I would encourage other patients to utilize for themselves in combination with any traditional allopathic program for cancer. I had the best of both worlds working for me in a remarkable manner thanks to all of my doctors."

PHANTOM PAINS OF AMPUTATED ORGANS

Amputation may be necessary as a result of severe injury or massive infection, such as gangrene. During surgical amputation, the soft tissues are cut in such a way that they cover the end of the remaining bone to heal completely. This allows the body's tissues to seal and protect themselves from the external environment. "Ghost" or "phantom" pains are caused by the patient's energetic connection with the amputated tissues, through the internal "energetic spacial cavity," or external "energetic boundary system." The phantom limb (usually one of the body's extremities, e.g., finger, hand, arm, etc.) exists in an energetic state and continues to interact with the patient's external Wei Qi field, as well as with the patient's Shen. Any interaction with the space, or energetic field of the amputated organ, will produce a direct response in the patient, similar to that of contacting the actual physical limb.

Rehabilitation programs generally do not prepare the patient for such reactions as phantom pains, which tend to leave the patient perplexed and frustrated. To alleviate the symptoms of phantom pains, the Qigong doctor sedates the patient's Wei Qi field that surrounds the amputated limb, and assists the patient in re-patterning the old energetic field to fit the postoperative tissue formation. The Qigong doctor can also prescribe Juniper Berries, which will relieve the phantom pain symptoms.

MEDICAL QIGONG THERAPY AND THE TREATMENT OF SCAR TISSUE

Medical Qigong therapy may be effective for treating pathologies caused by scarring due to surgical procedures. The formation of scar tissue often becomes the source of other physical problems by either obstructing, or weakening, the flow of Qi within the body's channels. In most cases of pathological scar tissue, the scar itself transverses several channels within the superficial and deep tissues.

The topological relationships of each scar will vary according to each patient. Therefore, different therapeutic approaches may be required for treatment, depending on the patient's strength, weakness, Elemental Constitution, and the patient's emotional state surrounding the surgery. Manifestations of scar tissue pathology include some of the following symptoms:

- a feeling of discomfort, or unpleasant sensations that originates around the scar area,

- radiating sensations that occur when the scar is being pressed, and
- a sharp, pulling type of pain that originates from the scar.

These conditions can be present, even if it has been several years since the surgery was performed.

TREATMENT

Medical Qigong treatment for scar tissue formation follows the principle of emitting Qi along the pathway of the channels. Before treatment, the doctor should take into consideration the energetic flow and function of the channels that have been affected by the surgery. If, for example, a patient's Yang channel (e.g., Stomach) becomes obstructed due to surgery, it can create an Excess condition within the Stomach Channel, which in turn creates a Deficiency of the Spleen Channel. Therefore, the treatment of both the Stomach and Spleen channels should be addressed.

After surgery, some scar tissue formation is inevitable, since both the body's inner-facia and channels (which are responsible for the lubrication of the tissues) have been severed. To minimize the degree of scar tissue formation, the Qigong doctor uses Qi extension techniques on the sutured area, extending his or her intention deep into the patient's body. The doctor's focuses on dispersing stagnations and regulating the flow of the undercurrent of Qi through the sutured tissues. Emphasis should be placed on reconnecting the patient's channels and collaterals. Next, the doctor focuses on regulating the external and internal flow of energy from within and without the patient's tissue area.

In treating scar tissue formation which has laid dormant for quite some time, tissue regulation through Tui Na therapy is required. After using the proper tissue regulation method (see Chapter 37), the Qigong doctor ends the treatment by using the One Finger Skill technique along the line of the patient's external scar. To perform this method, one thumb is placed on the end of the scar, while the doctor's other thumb presses into tissue, slowly outlining the entire scar (this heats and energizes the patient's tissues). The doctor ends the treatment with both thumbs placed at the beginning and ending of the scar, extending his or her energy through the patient's tissue in a circular pattern. This technique naturally induces an energetic emotional release of the memories trapped within the scar tissue.

SECTION XII

MEDICAL QIGONG APPENDICES

INTRODUCTION TO THE APPENDICES

There are many documents discussing the experimental research of Medical Qigong Therapy written within the past ten years. Among these documents, are listed a collection of abstracts from five national congresses on Medical Qigong researches as well as four World Conferences. The research has covered a variety of topics ranging from Medical Qigong and its relationship with: Physics, Chemistry, Biology, Western and Traditional Chinese Medicine, Optics, Magnetism, Electromagnetism, Acoustics and the Projection of Sound Resonation, Fluid Mechanics, Nuclear Physics, Electro-Chemistry, Organic Chemistry, Inorganic Chemistry, Analytical Chemistry, Physiology, Bio-Chemistry, Molecular Biology, Micro-Biology, Cytology, Genetics, Pathology, Pharmacology, Psychology, and Sports Medicine.

The experimental research of Medical Qigong is actually a study with multiple sciences. Of all the research reported, Biology and Medicine are in the forefront of the material collected.

The following research was conducted by distinguished scholars at various Universities, Scientific Academies, and Institutes through out the world (i.e.: Beijing Medical University, Qinghua Medical University, Nanjing Medical University, Tokyo Medical University, Tokyo Electro-engineering University, Higher Energy Institute, Physics Institute, International Institute of Medical Qigong, China Healthways Institute, etc.).

This research was focused on the Extension of Emitted Qi by various Medical Qigong Masters / Doctors, the result being positive in it's conclusion on the effectiveness of Medical Qigong Therapy as a solid and effective clinical modality.

This section of the text is devoted to the scientific approach of analyzing and scrutinizing the claims made as to the actual effectiveness of Medical Qigong Therapy as a clinical modality.

For this purpose, I have elicited the help of my good friend, the renowned scientist and research investigator, Dr. Kenneth M. Sancier. Dr. Sancier (a Material Scientist) is the president of the Qigong Institute, of San Francisco, California, and an active Council Board Member of the World Academic Society of Medical Qigong (Beijing, China). His many years of extensive research in the field of Energetic Medicine has led him to help organize the first International Congress of Qigong in conjunction with the Fifth International Congress of Chinese Medicine (at the University of California, Berkeley) including maintaining an active annual Qigong Science Forum for scientists. He is also responsible for developing the first computerized Qigong Data Base, which is currently being sold worldwide.

Dr. Sancier has actively collected scientific information on Qigong by attending international conferences, and meeting scientists in China, Japan, Canada and the United States. He has published several reviews of clinical and experimental studies of the medical aspects of Qigong therapy in many scientific journals and magazines. Although the following information in this appendix represents but a fraction of Dr. Sancier's findings, I am confident that the reader will find the data fascinating.

Dr. Jerry Alan Johnson May 2000

APPENDIX 1A

MEDICAL APPLICATIONS OF QIGONG

Kenneth M. Sancier, Ph.D.
Qigong Institute
Menlo Park, California

ABSTRACT

This article reviews selected scientific studies of medical applications of Chinese Qigong. The intention of the review is to outline research on Qigong and its potential for improving health care in western countries. The review centers on clinical and experimental studies to show that Qigong exercise can beneficially affect many functions of the body and improve health. The studies were selected to illustrate the following points: medical applications of Qigong are diverse, some studies were conducted in depth, and many applications hold promise to improve western health care.

Several specific clinical and experimental studies are outlined. The study using electroacupuncture according to Voll shows that almost all organs and functions of the body can be balanced by Qigong. The research on hypertension serves as a model to illustrate the many ways that the effects of Qigong on the body can be measured. Studies on brain waves are included to show that the mind is involved in Qigong and probably in the healing process. Research on Qigong's role in high altitude adaption suggests some practical applications for treating cardiovascular disease. A combination of Qigong and drug therapies is superior to drug therapy alone, as indicated in the case of two diseases, hypertension and cancer. In conclusion, there is a plea to medical practitioners and scientists to collect existing information on medical Qigong, promote research if needed, and identify applications that hold promise for improving western health care.

INTRODUCTION TO MEDICAL QIGONG

Traditional Chinese Medicine (TCM) is a holistic system for promoting health and for healing that includes several therapies such as acupuncture and moxibustion, herbal medicine, acupressure massage, nutrition, and Medical Qigong. These therapies are often used in combinations. The underlying theory of TCM is based on balancing Qi, the vital energy in the body, according to the theory of "yin-yang" and the Five Elements, that has been used for more than three thousand years. In practice, the flow of Qi is regulated, and "blocks" to the flow of Qi are removed. Energy blocks or Qi in excess or deficiency may result from disease, injury or stress. Qigong (pronounced chee gong) has a history of thousands of years, and it is unique among TCM therapies because almost anyone can learn and practice Qigong. However, it best to study Qigong with a qualified teacher to avoid adverse side effects. It is claimed that 60 million people in China practice Qigong daily, primarily to maintain health and achieve long life.

The word Qigong is a combination of two ideas. Qi is the vital energy of the body, and gong is the skill of working of the Qi. Medical Qigong for health and healing consists primarily of meditation, physical movements, and breathing exercises. Qigong practitioners develop an awareness of Qi sensations in their bodies and use their mind, i.e., intention, to guide the Qi in the body. It is said that the benefits of Qigong extend beyond health and healing to enhance spiritual life and even special abilities, such as psychic powers. Qigong is also used in martial arts to help develop physical and mental powers for self defense and healing.

Medical Qigong is divided into two parts: internal and external. Internal Qi is developed by individual practice of Qigong exercises. When Qigong practitioners become sufficiently skilled, they can use external Qi to "emit" Qi (Wai Qi in Chinese) for the purpose of healing another person. There are many reports of the medical efficacy of emitted Qi. This therapy has limited application on a large scale because there are a limited number of skilled Qigong masters. The present article will focus mainly on internal Qi because almost everyone can learn Qigong exercises for maintaining health and for self-healing.

In the early 1980s, scientists in China began investigating the many medical benefits claimed for Qigong. Since then, research on hundreds of medical applications of Qigong has been reported in the literature, which, unfortunately for the West, is written primarily in Chinese. A wealth of material is published in English in the proceedings of international conferences of Qigong. The proceedings contain abstracts of talks given at the conferences, and since 1986 there are 837 abstracts, more than half in English.

EXAMPLES OF MEDICAL APPLICATIONS OF QIGONG

Some examples of the applications of medical Qigong and emitted Qi on humans, animals, cell cultures, and plants were reviewed. Clinical and experimental evidence showing that Qigong exercise and external Qi affects various functions and organs of the body have been discussed. A short list of some of the functions and organs affected by Qigong, and the measurement techniques employed, include: the brain (EEG and magnetometer); blood flow (thermography, sphygmography, and rheoencephalography); heart functions (blood pressure, EKG, and UCG); kidney (urinary albumin assay); biophysical (enzyme activity, immune function, sex hormone levels); eyesight; and tumor size in mice.

In the following discussion, some clinical and experimental research studies will be discussed to illustrate the scope of research on medical applications of Qigong. The studies have been selected because they contain scientific information on important chronic medical conditions, such as hypertension and aging. Most of these studies on Qigong used controls and statistical analysis. This review focuses on the main accomplishments of selected research studies. Details may be omitted because of space limitations or because relevant information is not available. The critical evaluation of research studies will be left to medical specialists.

THERAPEUTIC BALANCING OF THE CHANNELS AND FUNCTIONS OF THE BODY

Electroacupuncture According to Voll (EAV) can monitor the effects of Qigong practice on therapeutic balancing of the Channel system, the classical TCM organs, and body functions. In EAV the electrical conductance of the skin above individual acupuncture points is measured using a low voltage and low current. Diagnosis depends on measuring the relative electrical conductance and its time dependence. An important diagnostic criterion of degeneration of an organ is an "indicator drop" that may occur during the measurement when the conductance reaches an apparent maximum value but then decreases before leveling off.

Measurements were made at 24 acupuncture points at the ends of the Channels of the fingers and toes of subjects and were made by the same operator and equipment. The subjects were asked to perform a Qigong exercise of their choosing, for example, sitting or standing meditation or moving Qigong. Two series of EAV measurements were made before and after healthy subjects practiced Qigong. In the first series, four subjects were examined by EAV before and after they practiced Qigong for 10 to 15 minutes. Qigong exercise decreased the average of the EAV measured values in the range of -19 to -31% ($p<0.004$) for the four subjects. Qigong essentially eliminated the indicator drops. In the second series, each of seven subjects was examined by EAV three times in a blind protocol so that the operator did not know whether a subject had practiced Qigong before the second or third examination. In the second series, Qigong exercise changed the average EAV measured values in the range of -17% to -35% for four subjects and in the range of 4% to 15% for three subjects. Indicator drops again were decreased.

These preliminary results show that Qigong can make significant changes in the therapeutic balancing of the Channel and organ systems, the goal of TCM.



Figure 1. A 30-year folow-up of the effect of Qigong on mortality and stroke of 242 hypertensive patients. Both groups received drug therapy. (Qang. Xu, et al. ref. 7)

HYPERTENSION

Several groups in China have investigated the effects of Qigong on hypertension (i.e., high blood pressure). Research on the short- and long-term effects of Qigong practice on hypertensive patients has been carried out at the Shanghai Institute of Hypertension by Wang Chongxing, Xu Dinghai and their colleagues. Their research is reviewed extensively because it serves as a model of the effects of Qigong on many functions of the body. For these studies, the patients practiced "Yan Jing Yi Shen Gong" for 30 minutes twice a day. This Qigong is claimed to be especially valuable for therapeutic purposes and delaying senility. The Qigong exercise consists of a combination of sitting meditation and gentle physical movements that emphasizes a calm mind, relaxed body, and regular respiration.

PREVENTION OF STROKE AND MORTALITY

In 1991, the researchers reported a 20-year controlled study of the anti-aging effects of Qigong on 204 hypertensive patients. Recently, the researchers performed a 30-year follow-up on 242 hypertensive patients who were divided randomly into a Qigong group (n = 122) and a control group (n = 120). All patients were given drug therapy to control blood pressure, but only the experimental group practiced Qigong 30 minutes a day, twice a day. The results show that the accumulated mortality was 25.41% in the Qigong group and 40.79% in the control group ($p<0.001$). The incidence of stroke was 20.49% and 40.73% ($p<0.01$), and death rate due to stroke was 15.57% and 32.50% ($p<0.01$), respectively. These results, which are shown graphically in Figure 1, indicate that Qigong has potential for preventing strokes and extending life.



Figure 2. Serum estrdiol levels of hypertensive men (ages 40–69) and women (ages 51–57) who practice Qigong one year compared to healthy controls. (Ankun, Eang, et al. ref. 6)

The researchers also reported that over the 20-year period, blood pressure of the Qigong group stabilized while that of the control group increased. Remarkably, during this period the drug dosage for the Qigong group could be decreased and for 30% of the patients could be eliminated. However, the drug dosage for the control group had to be increased. These results suggest that Qigong activated the natural healing process of the body.

IMPROVEMENTS IN HEART FUNCTION AND MICROCIRCULATION

Aged hypertensive patients usually are found to have a deficiency of Heart-energy, which often leads to a weakened function of the left ventricle and a disturbance of microcirculation. The researchers evaluate the effects of Qigong by using ultrasonic cardiography (UCG) and indices of microcirculation. The 120 male subjects, 55 to 75 years of age, were divided into three groups: 46 cases of hypertensive subjects with Heart-energy deficiency, 34 cases without Heart-energy deficiency, and 40 cases with normal blood pressure. Patients whose blood pressure measured more than 160/95 mm mercury were accepted as subjects after regulation with anti-hypertensive drugs for 4 weeks.

The results showed that subjects with Heart-energy deficiency experienced several improvements: increases in cardiac output, ejection fraction mitral valve diastolic closing velocity, and mean velocity of circumferential fiber shortening, while the total peripheral resistance decreased ($p<0.05-0.01$). Significant changes did not occur in the group without Heart-energy deficiency.

Multiple quantitative evaluation of nailfold disturbance in microcirculation was made on the above three groups by observing 10 indices of abnormal conditions: configuration of micrangium, micrangium tension, condition of blood flow, slowdown of blood flow, thinner afferent limb, efferent limb and afferent limb ratio, color of blood, hemorrhage, and petechia. At the beginning of the study, the incidence of microcirculation obstruction for the above three groups was 73.91%, 26.47% and 17.50%, respectively. After practicing qigong for one year, the group with

Heart-energy deficiency showed a decrease in nailfold microcirculation obstruction from 73.91% to 39.31% (p<0.05). Significant changes did not occur in the group without Heart-energy deficiency.

These studies show that proper TCM diagnosis is essential for qigong therapy. The investigators emphasized that the kind of qigong must be selected according to the patient's condition.

IMPROVEMENT IN SEX HORMONE LEVELS

One consequence of aging is that the levels of sex hormones change in unfavorable directions. For example, female hormone (estrogen) levels tend to increase in men and decrease in women. Two studies indicate that this trend can be reversed by qigong exercise. The effect of qigong exercise on plasma sex hormone levels was determine for hypertensive men and women. The sex hormones levels were measured before and after qigong practice for one year.

The 70 male patients with essential hypertension (ages 40 to 69; disease stage II) were divided into two groups. For the qigong group (n = 42), the estradiol level (E2) decreased from 70.12 to 47.71 pg/ml, a decrease of 32% (p<0.01), while no significant changes occurred in the control group (n = 20). The testosterone levels (T) of both groups decreased about 7%. The value of E2 for the qigong group (47.71 pg/ml) approached that of healthy men (42.23±5.82 pg/ml) of the same age but without hypertension or cardiovascular, pulmonary, hepatic, renal, or endocrine diseases (p<0.05). For women (ages 51 to 67, the number in group not available), the aging process was associated with failure of ovarian function manifested by decreased E2 and increased T levels. Qigong resulted in an increase of E2 from 40.9±.3.5 to 51.6±3.5 pg/ml, a value about equal to that of normal menopausal controls without hypertension or cardiovascular, pulmonary, hepatic, renal, or endocrine diseases. The value of T was also increased by qigong from 25.5±2.2 to 37.2±2.2 ng/dl. These favorable changes in estradiol levels, E2, brought about by qigong are summarized in Figure 2 for both men and women.

In an auxiliary study, the 24-hour urinary estradiol levels were determined in 30 men ages 50 to 69. Qigong for one year resulted in a decrease of 31% in E2 and a decrease of 54% in the estradiol/testosterone ratio (E2/T). These changes were accompanied by improvements in symptoms associated with Kidney deficiency hypertension, such as soreness, dizziness, insomnia, hair loss, impotence, and incontinence. The average score for these symptoms was changed by qigong from 5.53±2.31 to 2.83±1.32 (p<0.001).

Ye Ming and co-workers reported similar favorable changes in plasma sex hormone levels E2 in 77 male and female qigong exercisers after 2 months qigong compared with 27 controls. They did not observe significant changes in testosterone.

The above studies show that qigong exercise can help restore the sex hormone levels that had deteriorated because of aging.

INCREASED BONE DENSITY

Aging may result in a decrease in bone density, especially in women. As a consequence, bones become more brittle and subject to fracture.

Bone density of male subjects was found to increase by practicing qigong for one year. For subjects 50 to 59 years of age (18 cases), the bone density increased from 0.627±0.040 to 0.696±0.069 g/cm3 (p<0.01). For subjects 60 to 69 years of age (12 cases), the bone density increase was somewhat less, namely, from 0.621±0.039 to 0.672±0.083 g/cm3 (p<0.05). For both age groups, the bone density increased to values exceeding those of normal men of the same age, 0.695±0.096 and 0.657±0.102 g/cm3, respectively. The results are shown graphically in Figure 3.

It is likely that qigong therapy also would help restore the bone density of women, especially menopausal women. If so, hormone replacement therapy and its side effects could be reduced.

CHANGES IN BLOOD CHEMISTRY IN HYPERTENSIVE PATIENTS

Auxiliary studies by Wang, Xu and co-workers on the effects of qigong exercise on blood chemistry of hypertensive subjects include improvements in plasma coagulation firbrinolysis open, and men and women start to practice differently. Both quickly practice Fusion I, and the Creation Cycle and Thrusting Channels of Fusion II, and bring the pearl to the perineum.

A. Men start by bringing the Pearl to the Crown.

Men bring the pearl from the perineum up to and out of the crown to about six inches (fifteen centimeters.) Feel your pearl hook up with the higher energy source, Heavenly Energy. Absorb this energy into the pearl. Then bring the energy back into the body. As it enters the crown, let the pearl split in three. Feel the energy penetrate through three holes at the top of the head. Feel it flowing back down to the perineum through the three Thrusting Channels, penetrating all the organs and glands.



Fig. 7.16 *Bringing the Pearl to the Crown*

From the perineum men will push and guide the energy down the back of both legs to the soles of the feet, and then six to twelve inches (fifteen to thirty centimeters) into the ground. Feel a connection or rooting to the earth, then draw the Earth Energy up to the soles of the feet. Bring the energy to the toes. Start to spread indices, blood viscosity, erythrocyte deformation index, levels of plasma tissue-type plasminogen activator (tPA), plasminogen activator inhibitor (PAI), VIII factor related antigen (VIII R:AG), and anti-thrombin (AT-III). In another study, they reported that qigong exercise significantly and beneficially changed the activities of two messenger cyclic nucleotides (cAMP and cGMP).

These results provide further evidence that qigong affects many complex functions of the body.

CANCER

Feng Lida pioneered in research showing that emitted qi from qigong masters produced marked changes in cell cultures of cancer cells from mice. Several studies reported the effects of emitted qi on tumors in animals. For example, emitted qi was reported to inhibit the growth of implanted malignant tumors in mice but did not destroy the tumors. Encouraged by the results with animals, researchers carried out clinical research on the effects of qigong on human subjects with cancer. Detailed results are not available in English for all these clinical studies.

Some results are available for a clinical study of qigong as a therapeutic aid for patients with advanced cancer. In this study, 127 patients with medically diagnosed malignant cancer were divided into a qigong group of 97 patients and a control group of 30 patients. All patients received drugs, and the qigong group practiced qigong for more than 2 hours a day over a period from 3 to 6 months. Both groups improved, but the qigong group showed improvements four to nine times greater than the control group for strength, appetite, diarrhea free, and weight gain of 3 kg. The phagocytic rate, which a measure of the immune



Figure 3. Changes in bone density of hypertensive men who practice Qigong one year compared to healthy males of the same age. (Xu Wang, et al. ref. 9)



Figure 4. Comparison of Qigong, drug and drug-alone terapies for patients with advanced cancer. (ref. 25)

function, increased in the qigong group but decreased in the control group. These results are shown in Figure 4.

REVERSING SENILITY

To study the mechanism of keeping fit by qigong, a controlled study was made of 100 subjects classified either as presenile or with senile impaired cerebral function. The subjects were divided into two groups of 50 people each with a mean age of 62.7 years and with a similar distribution of age and sex. The qigong group practiced a combination of static and moving qigong. The control group exercised by walking, walking fast, or running slow. According to TCM method of classifying the vital energy, more than 80% of the patients in each group were classified as deficient in vital function and vital essence of the Kidney. Criteria for judging outcome were based on measuring clinical signs and symptoms including cerebral function, sexual function, serum lipid levels, and function of endocrine glands.

After six months, 8 of the 14 main clinical signs and symptoms in the qigong group were improved above 80%, whereas none of the symptoms in the control group was improved above 45%. These results suggest that qigong can reverse some symptoms of aging and senility.

MIND-BODY REGULATION

The main function of qigong is to regulate the mind, and according to TCM theory the mind leads the qi. The mind-regulating function of qigong mainly refers to the regulation of the functions of the brain and related body reactions. One tenant of qigong is that "the mind leads the qi, and the qi leads the blood." This somewhat mysterious statement can be interpreted to mean that intention (the mind) can direct the qi within the body. This mechanism is perhaps similar to the role of volition in biofeedback self-regulation.

BRAIN WAVES

The main focus of research has been on the effects of qigong on brain waves as measured by electroencephalography (EEG). During static, e.g., sitting meditation, alpha brain waves dominate over beta waves and spread to the frontal areas of the brain. Kawano and Wang have found differences in the EEG of Zen Buddhist priests and qigong masters. During almost all types of qigong training, the frequency of the alpha waves increased in the range from +0.6 to 1.0 Hz. During deep Zen meditation, the frequency decreased in the range from -1.0 to -1.5 Hz, and sometimes theta waves appeared. Also, frontal and occipital alpha waves tended to synchronize with a phase difference that depended on the type of meditation. This phase difference became smaller with qigong meditation (i.e., better synchronization) and larger for Zen meditation. According to Kawano and Wang these differences in brain function suggest that internal qigong involves a "semi-conscious" process, which involves some awareness and activity, while Zen meditation is a neutral process that releases the meditator from all concerns. This difference may relate to qigong being a healing art, whereas Zen is generally not considered to be one.

As mentioned earlier, a qigong master can emit qi to heal a patient, and the literature contains many references to this subject. The interaction between the qigong master and his subject has been followed in double blind tests. Both qigong master and subject were simultaneously measured by EEG, polygraphs, biochemical blood tests, and psychological tests. The EEG studies showed that brain wave patterns of the subject and qigong master were synchronized in type of brain waves and their location in the brain. Such synchronism may be required for healing by emitted qi.

Machi has studied qigong masters by combining EEG measurements with simultaneous measurements of physiological changes. He found that while the qigong master was emitting qi, the alpha-1 waves showed extremely high potential on the right frontal lobe, and there were increases in blood pressure, heart rate, and skin surface temperature. He also detected a far infrared emission with 1 Hz modulation signal coming from the Laogong point (a major acupuncture point in the palm of the hand.)

BLOOD FLOW TO THE BRAIN

Qigong exercise has been shown by rheoencephalography to increase blood flow to the brain. For 158 subjects with cerebral arteriosclerosis who practiced qigong for 1 to 6 months, improvements were noted in symptoms such as memory, dizziness, insomnia, tinnitus, numbness of limbs, and vertigo headache. During these studies, a decrease in plasma cholesterol was also noted. These results may offer hope to people with cerebral arteriosclerosis.

EFFECT OF RAPID AND LARGE CHANGES IN ALTITUDE

Studies have been made to determine whether qigong exercise would protect pilots from altitude stress when they increased altitude by going rapidly from low altitudes to the Tibetan highlands.

CARDIAC FUNCTION

Before entering the Tibetan highland, 66 persons were divided into two groups: a qigong group of 32 young men who did Qiyuan Qigong exercise for 4 weeks, and a control group of 34 young men who exercised to radio music. The two groups of men suddenly entered the highlands from a lower altitude. Before and after entering the highland, measurements were made of symptoms of altitude sickness and physiological changes. The qigong group suffered less altitude stress than the control group as measured by blood pressure, heart rate, oxygen consumption, microcirculation on epex of tongue and nail fold, and temperature at Laogong point (P8) of the left hand ($p<0.01$). The researchers suggest that qigong can prevent stresses from altitude changes.

These results with healthy subjects suggest that qigong also should be effective in improving the health of people with cardiovascular conditions. In fact several research studies have been reported the beneficial effects of qigong on cardiovascular diseases.

MICROCIRCULATION DISORDERS

Air force pilots were randomly divided into two groups: a qigong group of 22 persons who had practiced Qiyuan Qigong exercise for eight weeks, and a control group of 18 persons who did physical exercise for eight weeks before entering the Tibetan highlands. Microcirculation was measured at tongue apex and the nail fold, and also from the temperature at the Laogong point in palm of the left hand. When the men entered the high altitude, abnormal blood pressure and microcirculation of tongue apex and nail fold occurred in both groups. However, the abnormalities were statistically less in the qigong group than in the control group ($p<0.01$). The temperature at Laogong kept steady in the qigong group, but was reduced in the control group ($p<0.05$).

STUDY OF LUNG FUNCTION

The men were divided into three groups. Forty young males were in the qigong group and practiced Qi Yuan qigong for 4 weeks prior to entering the highlands; 40 young men were in the control group and exercised to radio music for 4 weeks prior to entering the highlands; and 40 young males were residents living at high altitudes. The results show that the integral value of symptoms of acute mountain sickness was lower in the qigong than in control group ($p<0.05$—0.01). Pulmonary ventilation of the qigong group was significantly improved compared with the control group ($p<0.05$—0.01), and nearly equal to the resident group.

The favorable outcome of these studies suggests that qigong may be a valuable therapy for people suffering from cardiac, microcirculation and lung disorders.

SUMMARY AND CONCLUSIONS

This review deals with only a small fraction of a large collection of research already performed on medical applications of qigong, mainly in China. Hopefully, the information presented is sufficient to illustrate the potential of qigong exercise for restoring normal body functions. The main conclusion from many studies is that qigong enables the body to heal itself.

Medical practitioners and scientists are encouraged to evaluate the potential value of medical applications of qigong. They should collect as much information as possible from original sources, develop bibliographies, and then determine whether additional research is required to validate given medical applications. They should then recommend those applications most likely to be suitable for western health care. It is recommended that TCM and qigong be considered to complement western medicine.

There are several issues that should be addressed for the successful introduction of qigong into western health care. It is necessary to win the support of scientists, medical practitioners and the public who know very little about TCM and qigong. A crucial step is to collect scientific evidence from research already performed. Regrettably, there are few research reports in English, and original scientific reports in Chinese are often difficult to obtain and translate. Further, some of the best technical research papers are incomplete scientifically. Recently this has become less of a problem in China. Although some scientific reports have flaws, we must not reject all research on qigong. We must give credit to China for developing the science of qigong and recognize that it is a science in development.

On the positive side, qigong is emerging rapidly among a public interested in improving their health. Qigong is a subject being addressed by the public press and in books and magazines. Increasing numbers of medical practitioners are becoming active in alternative medicine, although few physicians have studied TCM. At least one insurance company has paid for qigong therapy. HMOs and state and federally funded medical programs would benefit from paying for qigong therapy because it is effective and inexpensive. Pharmaceutical companies are already exploring many herbs, and these companies also could benefit from qigong research because of the synergic effect between qigong and drugs mentioned in this review. The Office of Alternative Medicine (OAM) of the National Institutes of Health is working to develop a basis for evaluating the merits of different alternative therapies, and in 1994 it funded one grant involving qigong. Incidentally, the Japanese Ministry of International Trade and Industry (MITI) is reported to be taking a pragmatic approach to alternative therapies by encouraging the development of industrial applications of therapies such as acupuncture and qigong.

There are many medical applications of qigong. Some of the most promising for introducing into western health care are chronic problems such as hypertension, cardiovascular disease, aging, asthma, allergies, neuromuscular problems, and cancer. These areas of public health deserve consideration by the western medical establishments.

*The p-value is the probability that two quantities are not different: the smaller the p-value greater the difference.

REFERENCES

1. Qigong Database™ is available from the Qigong Institute,450 Sutter Street, Suite 2104, San Francisco, CA 94108.
2. Sancier K M, Hu B. Medical Applications of Qigong and Emitted Qi on Humans, Animals, Cell Cultures, and Plants: Review of Selected Scientific Studies. Am J Acupuncture.1991:19 (4) 367-377.
3. Sancier K M. The effect of qigong on human body functions. Proceedings, Fifth International Symposium on Qigong, Shanghai, China.1994:179.
4. Sancier K M. The effect of qigong on therapeutic balancing measured by electroacupuncture according to Voll (EAV): a preliminary study. Acupuncture & Electro-Thera Res Int J. in press.
5. Wang Chongxing, Xu Dinghai, Qian Yuesheng, Medical and health care qigong, J Traditional Chinese Medicine. 1991:11(4) 296-301.
6. Kuang Ankun, Wang Chongxing, Xu Dinghai, Qian Yuesheng. Research on the anti-aging effect of qigong. J. Traditional Chinese Medicine. 1991:11 (2) 153-158.
7. Hong Shunhua, et al. Microcirculation of nail fold and immunogenicity after qigong practice for short periods. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 56-57.
8. Li Ziran, Li Liziang, Zhang Boli. Group observation and experimental research on the prevention and treatment of hypertension by qigong. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 113-114.
9. Jing Guinian. Observations on the curative effects of qigong self adjustment therapy in hypertension Proceedings, Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 115-117.
10. Bian Huangxian. Clinical observation of 204 patients with hypertension treated with qigong. Proceedings, First International Congress of Qigong. Berkeley, Calif., 1990: 101
11. Wang Chongxing, et al. The beneficial effect of qigong on the hypertension incorporated with coronary heart disease. Proceedings, Third International Symposium on Qigong, Shanghai, China. 1990: 40.
12. Wu Renzhao, Liu Zhewei. Study of qigong on hypertension and reduction of hypotensor. Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 125.
13. Bornoroni Corrado, et al. Treatment of 30 cases of primary hypertension by qigong techniques. Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 126.
14. Zhang Guifang. Development and application of a series of qigong feedback tapes Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 125.
15. Wang Chongxing, et al. Effects of qigong on preventing stroke and alleviating the multiple cerebro-cardiovascular risk factors—a follow-up report on 242 hypertensive cases over 30 years. Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 123-124.
16. Wang Chongxing, Xu Dinghai, et al. Beneficial effects of qigong on the ventricular function and microcirculation of deficiency in heart-energy hypertensive patients. Pri-

vate communication.

17. Xu Dinghai, Wang Chongxing, et al. Clinical study of delaying effect on senility by practicing "Yang Jing Yi Shen Gong" in hypertensive patients. Proceedings, Fifth International Symposium on Qigong, Shanghai, China, 1994:109.
18. Ye Ming, et al. Relationship among erythrocyte superoxide dismustase activity, plasma sexual hormones (T, E2), aging and qigong exercise. Proceedings, Third International Symposium on Qigong, Shanghai, China. 1990:28-32 (in English and Chinese).
19. Kuang Ankun, Wang Chongxing, Xu Dinghai, Qian Yueshang. Research on "anti-aging" effect of qigong. J Traditional Chinese Medicine. 1991:11 (3) 224-227.
20. Feng Lida, Effect of emitted qi on human carcinoma cells. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 1-4.
21. Feng Lida, Effect of emitted qi on the L 1210 cells of leukemia in mice. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 4-5.
22. Zhao Shan, et al. Preliminary observation of the inhibitory effect of emitted qi on transplanted tumors in mice. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 46-48.
23. Liu Tehfu,Wan Minsheng,Lu Oulun. Experiment of the emitted qi on animals. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 60-61.
24. Feng Lida,Peng Liaomin. Effect of emitted qi on prevention and treatment of tumors in mice. Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 106-107.
25. Sun Quizhi, Zhao Li. Clinical observation of qigong as a therapeutic aid for advanced cancer patients. Proceeding, First World Conf Academic Exchange of Medical Qigong, Beijing, China. 1988: 97-98.
26. Chen Guoguang. The curative effect observed for 24 (cancer) cases under my emitted qigong treatment. Proceedings, Second International Conference on Qigong, Xi'an, China. 1989: 141-142.
27. Lo Jifeng, et al. Changes of peripheral blood cell population and immune functions in 31 nasopharyngeal carcinoma (NPC) patients treated with radiotherapy and qigong. Proceedings ,Third National Academic Conference on Qigong Science, Guangzhou, China. 1990: 94-95.
28. Yu Yi, et al. Effect of self-controlling qigong therapy on the immune function of cancer patients. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China.1993: 128.
29. Zhao Hongmei, Bian Jingnan. Curative effect of intelligence qigong on 122 tumor patients. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China.1993:130.
30. Wang Ying. Clinical observation on 30 cases of cancer treated by qigong therapy Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China. 1993: 131.
31. Xong Jing, Lu Zhong. Curative effect on 120 cancer cases treated by Chinese-Western medicine and qigong therapy. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China. 1993: 131
32. Fu Jingzhi. Treatment of advanced gastric cancer in the aged by the combination of qigong and medicinal herbs. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China. 1993: 132-133.
33. Zhang Shengbing. Effects of mind-regulation by qigong on the human body. Proceedings, Fifth International Symposium on Qigong, Shanghai, China, September. 1994:68.
34. Kawano Kimiko, Wang Fengfong. Difference between the EEG of Zen priests and internal qigong masters. Society of Mind-Body Science. 1994: 3 (1) 99-104. (in Japanese).
35. Machi Yoshio. Various measurements to qigong masters for analyzing qigong mechanism. Society for Mind-Body Science. 1994:3 (1) 65-87. (in Japanese).
36. Kashiwasake Masaki. Double-blind tests of qi transmission from qigong masters to untrained volunteers. Society for Mind-Body Science. 1993:2 (1) 81-87 (in Japanese).
37. Machi Yoshio. Various measurements of qigong masters for analyzing qigong mechanism Society of Mind-Body Science. 1994:3 (1) 65-87. (In Japanese).
38. Liu Yuanliang, He Shihai, Xie Shanling. Clinical observation on the treatment of 158 cases of cerebral arteriosclerosis by qigong. Proceedings, Second World Conference on Academic Exchange of Medical Qigong, Beijing, China. 1993:125.
39. Liu Yuanliang. Private communication, 1993.
40. Mo Feifan, Xu Yongchun, Lu Yongpin, Xu Guang. Study of prevention of cardiac function disorder due to immediate entry into highlands by qigong exercise. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China. 1993: 78.
41. Chu Weizong, et al. Changes of blood viscosity and RCG in 44 cases with cardiovascular diseases after qigong ex-

ercises. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 57-58.

42. Qin Chao, et al. Bidirectional adjustment of blood pressure and heart rate by daoyin tuina on the arterial blood and heart rate. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 107.
43. Wang Chongxing, et al. Beneficial effect of qigong on improving the heart function and relieving multiple cardiovascular risk factors. Proceedings ,Third International Symposium on Qigong. Shanghai, China. 1990: 42 (in Chinese).
44. Mo Feifan, Wan Lurong, Jia ZiZi, Xu Guang. Study of prevention of microcirculation disorders of pilots in highlands by qigong. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China.1993: 78.
45. Mo Feifan, Lu Yongpin, Zhao Guoliang. Effect of exercise with qigong on lung function of persons entering highland. Proceedings, Fifth International Symposium on Qigong, Shanghai, China.1994:186.
46. Wang Chongxing, Xu Dinghai, et al., private communication.
47. Wang Chongxing, Xu Dinghai, et al. Proceedings, Fifth International Symposium on Qigong, Shanghai, China, September. 1994::22 (Chinese),109.
48. Wen-hsien Wu, Intractable reflex sympathetic dystrophy
49. McGee C T, Chow E P Y. Miracle Healing from China — Qigong. 1st ed. Coeur d'Alene, ID: Medipress; 1994: 8-19.

APPENDIX 1B
ANTI-AGING BENEFITS OF QIGONG

Kenneth M. Sancier, Ph.D.

INTRODUCTION

In the early 1980s, scientists in China began to study the medical benefits claimed for qigong. Since then, research on hundreds of medical applications of qigong have been reported in the Chinese literature. Of special interest for the present article are clinical reports of the medical benefits of qigong that claim to retard or reverse some diseases associated with aging.

Most of the original research was reported in Chinese, but access in English to most of this material is possible by reference to the proceedings of international conferences of qigong. Since 1986, ten such proceedings contain about 840 abstracts of talks given at the conferences, more than half of which are in English. These abstracts, along with about 160 abstracts of articles in the scientific literature, have been organized as a computerized database. The database enables searches and development of bibliographies across this entire body of information by using any key word. The clinical outcomes reported in this article are partly based on material in the database and partly on the author's person contacts with researchers.

The word qigong is a combination of two ideas: qi the vital energy of the body, and gong the skill of working of the qi. Medical qigong for health and healing consists primarily of meditation, physical movements, and breathing exercises. Qigong practitioners develop an awareness of qi sensations in their bodies and use their mind, i.e., intention, to guide the qi in the body. The benefits of qigong are said to extend beyond health and healing to enhance spiritual life and even special abilities, such as psychic powers.

Medical qigong is divided into two parts: internal and external. Internal qi is developed by individual practice of qigong exercises. When qigong practitioners have sufficiently mastered the skill, they can "emit" qi (external qi or waiqi in Chinese) for the purpose of healing another person. There are many scientific reports of the medical existence and efficacy of emitted qi. The present article focuses mainly on internal qi because almost everyone can learn qigong exercises for maintaining health and for self-healing, whereas, there are a limited number of skilled qigong masters available for healing.

There are numerous reports of the effects of emitted qi on living systems and the functions and organs of the human body. The present author reviewed some examples of medical applications of qigong and emitted qi on humans, animals, cell cultures, and plants, and he also published some of his experimental research on physiological effects of qigong. He discussed some clinical and experimental evidence showing that qigong exercise and external qi affects various functions and organs of the body. A short list of some of the functions and organs affected by qigong, and the measurement techniques employed (in parentheses), include: the brain (EEG and magnetometer); blood flow (thermography, sphygmography, and rheoencephalography); heart functions (blood pressure, EKG, and UCG); kidney (urinary albumin assay); biophysical (enzyme activity, immune function, sex hormone levels (laboratory analysis); eyesight (clinical); and tumor size in mice.

CLINICAL STUDIES INDICATING THE ANTI-AGING BENEFITS OF QIGONG

Several clinical studies will be described to illustrate the scope of research on medical applications of qigong to treat chronic medical conditions that may affect the aging process. Some details may be omitted because of space limitations. The critical evaluation of the research studies will be left to medical specialists.

THERAPEUTIC BALANCING OF THE CHANNELS AND FUNCTIONS OF THE BODY BY QIGONG

The profound effect that internal qigong practice may have on balancing the energies of the organs and functions of the body is illustrated by measurements using Electroacupuncture According to Voll (EAV). In EAV the electrical conductance of the skin above individual acupuncture points is measured using low voltage and low current. Diagnosis depends on measuring the relative electrical conductance and its time dependence. An important diagnostic criterion of degeneration of an organ is an "indicator drop" that may occur during the measurement when the conductance reaches an apparent maximum value but then decreases before leveling off.

Measurements were made at 24 acupuncture points at the ends of the 12 Channels in the fingers and toes of subjects and were made by the same operator and equipment. The subjects were asked to perform a qigong exercise of their choosing for 10 to 15 minutes, for example, sitting or standing meditation or moving qigong. Two series of EAV measurements were made before and after healthy subjects practiced qigong.

In the first series, four subjects were examined by EAV before and after they practiced qigong. Qigong exercise decreased the average of the EAV measured values of the four subjects in the range of -19 to -31% ($p<0.004$). Qigong eliminated almost all the indicator drops.

In the second series, each of seven subjects was examined by EAV three times in a blind protocol so that the operator did not know whether a subject had practiced qigong before the second or third examination. The results showed that qigong exercise changed the average EAV measured values in the range of -17 to -35% for four subjects and in the range of 4 to 15% for three subjects. Indicator drops again were markedly decreased.

These preliminary results show that internal qigong practice can make significant changes in the therapeutic balancing of the Channel and organ systems.

In a similar type of study, the electric current at acupuncture points on 14 Channels was measured using a single square wave voltage pulse technique. Both a qigong master, who emitted qi, and a qi-receiver were measured simultaneously and continuously. The results show that internal and external qigong produce different values in some measurement parameters, and also some synchronous behavior was observed between the sender and receiver.

BLOOD PRESSURE

The effect of qigong exercise on blood pressure is shown graphically in Fig. 1. The blood pressure (systolic and diastolic) in millimeters mercury is plotted as a function of time over 20 years for the group consisting of 242 patients, 122 in the qigong group and 120 in the control group. During the first two months, the blood pressure of all patients dropped in response to the hypotensive drug. Subsequently, and over the period of 20 years, the blood pressures of the qigong group stabilized while that of the control group increased. Remarkably, during this period the drug dosage for the qigong group could be decreased, while the dosage for the control group had to be increased.

Fig. 1. Effect of qigong on blood pressure of hypertensive patients over 20 years. Qigong group (n = 104) practiced 30 min/day twice/day, control group (n = 100).

MORTALITY AND STROKE

The incidences of mortality and stroke for the 30-year study are shown in Fig. 2. These results show that qigong exercise decreased by about 50 percent the incidence of total mortality, mortality due to stroke, and morbidity due to stroke. At the end of 30 years, 86 patients survived in the qigong group and 68 in the control group. These results clearly show that qigong has significant potential for preventing strokes and extending life.

Fig. 2. Effect of qigong on mortality and stroke of hypertensive patients over 30 years. Both groups received drug therapy; qigong group (n = 122) practiced qigong 30 min/day twice/day; the control group (n = 120).

IMPROVEMENTS IN HEART FUNCTION AND MIRCROCIRCULATION

Aged hypertensive patients usually are found to have a deficiency of Heart-energy, which often leads to a weakened function of the left ventricle and a disturbance of microcirculation. The researchers evaluated the effects of qigong for120 aged patients by using ultrasonic cardiography (UCG) and indices of microcirculation.

Experiments showed that the left ventricular function (LVF) in the hypertensive aged group (80 cases) was lower than that in the aged normal blood pressure group (40 cases), while the LVF in the deficiency of Heart-energy hypertensive patients (46 cases) was lower than in the non-deficiency Heart-energy hypertensive patients (34 cases).

After practicing qigong for one year, cardiac output was increased, the total peripheral resistance decreased, and the ejection fraction mitral valve diastolic closing velocity and the mean velocity of circumferential fiber shortening tended to be increased. Significant changes did not occur in the group without Heart-energy deficiency.

Quantitative evaluation of nailfold disturbances in microcirculation was made on the above groups by observing 10 indices of abnormal conditions: configuration of micrangium, micrangium tension, condition of blood flow, slowdown of blood flow, thinner afferent limb, efferent limb and afferent limb ratio, color of blood, hemorrhage, and petechia. The results showed that hypertension had an accelerating effect on the disturbance of microcirculation. The incidence of disturbance of microcirculation disturbance was 73.9% in the deficiency of Heart-energy hypertensive patients. After a year of qigong practice, the incident of disturbance was 39.1% ($p<0.01$).

The results suggest that qigong exercise has beneficial effects on Heart-energy and regulation of the blood channel, and qigong seems to have improved abnormal conditions of blood circulation.

ENHANCED ACTIVITY OF ANTI-AGING ENZYME SOD

Superoxide dismutase (SOD) is produced naturally by the body but its activity declines with age. SOD is often called an anti-aging enzyme because it is believed to destroy free radicals that may cause aging. The effects of qigong exercise to treat disorders of retired workers were studied by Xu Hefen and coworkers and included determinations of plasma SOD.

For their study, 200 retired workers,100 males and 100 females, ranging in age from 52 to 76 were divided into 2 groups: the qigong exercise group and the control group, and each group consisted of 50 males and 50 females. The main qigong exercise was Emei Nei Gong (one kind of qigong exercises of the Emei School), and was practiced at least 30 minutes a day.

The result showed that the mean level of SOD was increased by qigong exercise. For example, the SOD level was larger in the qigong group (about 2700 μ / g Hb) and than in the control group (1700 μ / g Hb), and this difference was significant ($p<0.001$). This study shows that qigong exercise can stimulate physical metabolism, promote the circulation of Channels and regulate the flowing of qi and blood, thus preventing and treating disorders of aging and promoting longevity.

CARDIOVASCULAR FUNCTION

Several studies reveal the potential benefits that qigong may have for improving the cardiovascular function of those with heart disease as well as old people. This conclusion is based on three studies reporting that qigong exercise can protect healthy pilots from altitude stress when they flew rapidly from a low altitude to the high altitude of the Tibetan highlands.

Before entering the Tibetan highland, 66 healthy young men were divided into two groups: a qigong group of 32 men who did Qiyuan Qigong exercise for 4 weeks, and a control group of 34 men who exercised to radio music. The two groups of men rapidly entered the highlands from a lower altitude. Before and after entering the highland, measurements were made of symptoms of altitude sickness and physiological changes.

the energy out from the ten toes, shooting the energy up to and into the crown, like a waterfall with a reverse flow. Draw the pearl back down to the perineum, and then repeat the process.

Practice nine times. Feel the flow of energy like a magnetic field surrounding your body.

B. Women start by bringing the Pearl to the Feet.

Women bring the pearl down to the perineum, divide it, and shoot it down the backs of both legs, through the soles of the feet, six to twelve inches (fifteen to thirty centimeters) into the ground. Feel a connection or rooting to the earth, and absorb the Earth Energy into the pearl. Then draw the Earth Energy up to the soles of the feet. Bring the energy all the way up the front of the legs to the knees, and back to the perineum. As the energy travels up the legs, feel it penetrate the bones.



Fig. 7.17 *Women bring the Pearl to the Feet.*

Spread the energy into the three Thrusting Channels, and thrust it as though it were on a three lane highway all the way up to the crown. Feel the energy spread from the crown like a spring or wa-

The qigong group suffered less altitude stress than the control group as measured by blood pressure, heart rate, oxygen consumption, microcirculation on the epex of tongue and the nail fold, and the temperature at the Laogong point of the left hand ($p<0.01$). The researchers suggest that qigong can prevent stress from altitude changes.

In another study of changes in altitude, healthy young men were divided into three groups. Forty males were in the qigong group and practiced Qiyuan qigong for 4 weeks prior to entering the highlands; 40 men were in the control group and exercised to radio music for 4 weeks prior to entering the highlands; and 40 males were residents living at high altitudes. The results show that the integral value of symptoms of acute mountain sickness was lower in the qigong than in control group ($p<0.01$ to 0.05). Pulmonary ventilation of the qigong group was significantly improved compared with the control group ($p<0.01$ to 0.05), and nearly equal to the resident group.

In another study, air force pilots were randomly divided into two groups: a qigong group of 22 men who had practiced Qiyuan Qigong exercise for eight weeks, and a control group of 18 men who did physical exercise for eight weeks before entering the Tibetan highlands. Microcirculation was measured at tongue apex and the nail fold, and also from the temperature at the Laogong point in palm of the left hand. When the men entered the high altitude, abnormal blood pressure and microcirculation of tongue apex and nail fold occurred in both groups. The abnormalities were statistically less in the qigong group than in the control group ($p<0.01$). The temperature at Laogong kept steady in the qigong group, but was reduced in the control group ($p<0.05$).

The results of these three studies with healthy subjects lead to the conclusion that qigong also should be effective in improving the health of people with cardiovascular conditions including the aged. In fact several research studies have reported such beneficial effects of qigong on cardiovascular diseases. The three studies also provide evidence that qigong exercise is superior to physical exercise such as calisthenics.

COMBINATION OF MEDICAL QIGONG AND DRUGS THERAPY

There is ample evidence in the literature that therapy by a combination of qigong exercise and drugs is superior to that of drugs alone. The advantages of a combination therapy of qigong and drugs over drugs alone were discussed earlier in this paper for hypertension and cancer.

The mechanism of this apparent synergism is not entirely understood, but undoubtedly relates to the fundamental mechanism of qigong. Qigong is believed to remove blocks to the ready flow of the qi (energy), blood, oxygen and nutrients to all cells of the body as well as to promote removal of waste products from cells of the body. Blocks to energy (qi) flow may result from injury, disease or stress.

Increases in qi flow and blood circulation help nourish diseased or stressed tissue, providing a means for the body to heal itself. This mechanism suggests that qigong also could promote drug uptake to tissue and cells via increased blood circulation. Omura's research shows that drug uptake was increased by using qigongized paper (i.e., paper to which emitted qi was sent) applied to afflicted area of the body.

CONCLUSIONS

This review deals with a small fraction of the large collection of clinical research on medical applications of qigong. The information presented is intended to illustrate the potential of qigong exercise for restoring normal body functions in people with chronic conditions, many of which accelerate the aging process. The main conclusion from many studies is that qigong exercise helps the body to heal itself. In this sense, qigong is a natural anti-aging medicine. Two studies indicate that qigong exercise is superior to some physical exercises.

Qigong can complement Western medicine in many ways to provide better healthcare. For example, qigong has special value for treating chronic conditions and as a preventive medicine, whereas Western medicine has special value for treating acute conditions. There are many medical applications of qigong that can complement Western medicine to improve health care. Some examples include chronic problems such as hypertension, cardiovascular disease, aging, asthma, allergies, neuromuscular problems, and cancer. These areas of public health deserve consideration by the Western medical establishment.

REFERENCES

1. Kenneth M. Sancier, Ph.D., Copresident & Director of Research, 561 Berkeley Avenue, Menlo Park, CA 94025, USA. Phone/Fax +1-415-323-1221.
2. Some of the material in this article was adapted from the article, "Medical Applications of Qigong," by K.M. Sancier, Ph.D., and published in Alternative Therapies in Health and Medicine. 1996;2 (1): 40-46.
3. Qigong Database™ is available from the Qigong Institute, East West Academy of Healing Arts, 450 Sutter Street, Suite 2104, San Francisco, CA 94108, USA.
4. The p-value is the probability that two quantities are not the same: the smaller the p-value smaller the probability and the more significant the result.
5. Wang C, Xu D. Private communication, May 1995.
6. Duration of the study is not available.

ENDNOTES

[1] Sancier K M, Hu B. Medical Applications of Qigong and Emitted Qi on Humans, Animals, Cell Cultures, and Plants: Review of Selected Scientific Studies. Am J Acupuncture.1991:19 (4) 367-377.

[2] Sancier, KM, Medical applications of qigong. Alternative Therapies in Health & Medicine. 1995; 2(1) in press.

[3] Sancier KM, Chow EPY. Healing with qigong and quantitative effects of qigong. J. American College of Trad. Chinese Medicine. 1989: 7(3):13-19.

[4] Sancier KM. The effect of qigong on therapeutic balancing measured by electroacupuncture according to Voll (EAV): a preliminary study. Acupuncture & Electro-Therapy Res Int J.:1995;19:119-127.

[5] Sancier K M. The effect of qigong on human body functions. Proceedings, Fifth International Symposium on Qigong, Shanghai, China.1994:179.

[6] Kido M. Channel measurements of qi-gong operation and synchronous phenomena. J. Mind-Body Science: 1993: 2(1): 19-26.

[7] Wang Chongxing, Xu Dinghai, Qian Yuesheng, Medical and health care qigong, J Traditional Chinese Medicine. 1991:11(4) 296-301.

[8] Kuang Ankun, Wang Chongxing, Xu Dinghai, Qian Yuesheng. Research on the anti-aging effect of qigong. J. Traditional Chinese Medicine. 1991:11 (2) 153-158.

[9] Hong Shunhua, et al. Microcirculation of nail fold and immunogenicity after qigong practice for short periods. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 56-57.

[10] Li Ziran, Li Liziang, Zhang Boli. Group observation and experimental research on the prevention and treatment of hypertension by qigong. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 113-114.

[11] Jing Guinian. Observations on the curative effects of qigong self adjustment therapy in hypertension Proceedings, Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 115-117.

[12] Bian Huangxian. Clinical observation of 204 patients with hypertension treated with qigong. Proceedings, First International Congress of Qigong. Berkeley, Calif., 1990: 101

[13] Wang Chongxing, et al. The beneficial effect of qigong on the hypertension incorporated with coronary heart disease. Proceedings, Third International Symposium on Qigong, Shanghai, China. 1990: 40.

[14] Wu Renzhao, Liu Zhewei. Study of qigong on hypertension and reduction of hypotension. Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 125.

[15] Bornoroni Corrado, et al. Treatment of 30 cases of primary hypertension by qigong techniques. Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 126.

[16] Zhang Guifang. Development and application of a series of qigong feedback tapes Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 125.

[17] Wang Chongxing, et al. Effects of qigong on preventing stroke and alleviating the multiple cerebro-cardiovascular risk factors—a follow-up report on 242 hypertensive cases over 30 years. Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 123-124.

[18] Wang Chongxing, Xu Dinghai, et al. Beneficial effects of qigong on the ventricular function and microcirculation

of deficiency in heart-energy hypertensive patients. Private communication, January 1994.

[19] Xu Dinghai, Wang Chongxing, et al. Clinical study of delaying effect on senility by practicing "Yang Jing Yi Shen Gong" in hypertensive patients. Proceedings, Fifth International Symposium on Qigong, Shanghai, China, 1994:109.

[20] Ye Ming, et al. Relationship among erythrocyte superoxide dismustase activity, plasma sexual hormones (T, E2), aging and qigong exercise. Proceedings, Third International Symposium on Qigong, Shanghai, China. 1990:28-32 (in English and Chinese).

[21] Kuang Ankun, Wang Chongxing, Xu Dinghai, Qian Yueshang. Research on "anti-aging" effect of qigong. J Traditional Chinese Medicine. 1991:11 (3) 224-227.

[22] Xu, Hefen; Xue, Huining; Bian, Meiguang; Zhang, Chengming; Zhou, Shuying. Clinical study of the anti-aging effect of qigong. Proceedings, Second World Conference for Academic Exchange of Medical Qigong. Beijing, China. 1993: 137.

[23] Mo Feifan, Xu Yongchun, Lu Yongpin, Xu Guang. Study of prevention of cardiac function disorder due to immediate entry into highlands by qigong exercise. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China. 1993: 78.

[24] Mo Feifan, Lu Yongpin, Zhao Guoliang. Effect of exercise with qigong on lung function of persons entering highland. Proceedings, Fifth International Symposium on Qigong, Shanghai, China.1994:186.

[25] Mo Feifan, Wan Lurong, Jia ZiZi, Xu Guang. Study of prevention of microcirculation disorders of pilots in highlands by qigong. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China.1993: 78.

[26] Chu Weizong, et al. Changes of blood viscosity and RCG in 44 cases with cardiovascular diseases after qigong exercises. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 57-58.

[27] Qin Chao, et al. Bidirectional adjustment of blood pressure and heart rate by daoyin tuina on the arterial blood and heart rate. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 107.

[28] Wang Chongxing, et al. Beneficial effect of qigong on improving the heart function and relieving multiple cardiovascular risk factors. Proceedings ,Third International Symposium on Qigong. Shanghai, China. 1990: 42 (in Chinese).

[29] Zhang Shengbing. Effects of mind-regulation by qigong on the human body. Proceedings, Fifth International Symposium on Qigong, Shanghai, China, September. 1994:68.

[30] Liu Yuanliang, He Shihai, Xie Shanling. Clinical observation on the treatment of 158 cases of cerebral arteriosclerosis by qigong. Proceedings, Second World Conference on Academic Exchange of Medical Qigong, Beijing, China. 1993:125.

[31] Liu Yuanliang. Private communication, 1993.

[32] Feng Lida, Effect of emitted qi on human carcinoma cells. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 1-4.

[33] Feng Lida, Effect of emitted qi on the L 1210 cells of leukemia in mice. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 4-5.

[34] Zhao Shan, et al. Preliminary observation of the inhibitory effect of emitted qi on transplanted tumors in mice. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 46-48.

[35] Liu Tehfu,Wan Minsheng,Lu Oulun. Experiment of the emitted qi on animals. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 60-61.

[36] Feng Lida,Peng Liaomin. Effect of emitted qi on prevention and treatment of tumors in mice. Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 106-107.

[37] Sun Quizhi, Zhao Li. Clinical observation of qigong as a therapeutic aid for advanced cancer patients. Proceeding, First World Conf Academic Exchange of Medical Qigong, Beijing, China. 1988: 97-98.

[38] Chen Guoguang. The curative effect observed for 24 (cancer) cases under my emitted qigong treatment. Proceedings, Second International Conference on Qigong, Xi'an, China. 1989: 141-142.

[39] Lo Jifeng, et al. Changes of peripheral blood cell population and immune functions in 31 nasopharyngeal carcinoma (NPC) patients treated with radiotherapy and qigong. Proceedings ,Third National Academic Conference on Qigong Science, Guangzhou, China. 1990: 94-95.

[40] Yu Yi, et al. Effect of self-controlling qigong therapy on the immune function of cancer patients. Proceedings,

Second World Conf on Academic Exchange of Medical Qigong, Beijing, China.1993: 128.

[41] Zhao Hongmei, Bian Jingnan. Curative effect of intelligence qigong on 122 tumor patients. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China.1993:130.

[42] Wang Ying. Clinical observation on 30 cases of cancer treated by qigong therapy Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China. 1993: 131.

[43] Xong Jing, Lu Zhong. Curative effect on 120 cancer cases treated by Chinese-Western medicine and qigong therapy. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China. 1993: 131

[44] Fu Jingzhi. Treatment of advanced gastric cancer in the aged by the combination of qigong and medicinal herbs. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China. 1993: 132-133.

[45] McGee C T, Chow E P Y. Miracle Healing from China—Qigong. 1st ed. Coeur d'Alene, ID: Medipress; 1994: 8-19.

APPENDIX 1C

THE EFFECT OF QIGONG ON THERAPEUTIC BALANCING MEASURED BY ELEXTROACUPUNCTURE ACCORDING TO VOLL (EAV): A PRELIMINARY STUDY

Kenneth M. Sancier, Ph.D.

ABSTRACT

Electroacupuncture According to Voll (EAV) was used to monitor the effects of qigong practice on therapeutic balancing of subjects. In EAV the electrical conductance of the skin above individual acupuncture points is measured using low voltage and current. Diagnosis depends on measuring the relative electrical conductance and its time dependence. An important diagnostic criterion of degeneration of an organ is an indicator drop which occurs during the measurement when the conductance decreases from an apparent maximum value and then levels off. Two series of EAV measurements were made before and after healthy subjects practiced qigong. Measurements were made at 24 acupuncture points at the ends of the Channels of the fingers and toes of a subject and were made by the same operator and equipment. The subjects were asked to perform a qigong exercise of their choosing. In the first series, four subjects were examined by EAV before and after qigong exercise. Qigong exercise decreased the average EAV measured values of the four subjects in the range of -19 to -31%. Qigong eliminated indicator drops for three subjects and reduced the indicator drop by 80% for the fourth subject. In the second series, each of seven subjects was examined by EAV three times in a blind protocol so that the operator did not know whether a subject had practiced qigong before the second or third examination. Qigong exercise changed the average EAV measured values in the range of -17 to -35% for four subjects and 4 to 15% for three subjects. Indicator drops appeared for three subjects, and they were eliminated for two subjects and reduced by 50% for the third subject. These preliminary studies indicate that EAV can monitor the effects of qigong on changes in the therapeutic balancing of the Channel-organ system. Suggestions are made of how EAV can provide basic information about qigong and its applications.

INTRODUCTION

Electroacupuncture According to Voll (EAV) is one of several electroacupuncture techniques for measuring local skin electrical conductance for diagnostic and therapeutic purpose(1). In general, EAV emphasizes preventive medicine by providing the medical practitioner with a diagnosis of a subject's health and its change at every stage of therapy. In the present study, EAV was used to monitor the effects of qigong practice on therapeutic balancing of subjects (2,3). The equipment is basically a D.C. resistance meter that measures relative changes in electrical conductance of the skin above an individual acupuncture point. Diagnosis depends on measuring the relative electrical conductance and its time dependence. The relative conductance is measured by a meter that is calibrated from 0 to 100. The "normal" value of 50 is expected when the acupuncture point and associated organ are in a physiologically balanced condition. Higher values (higher conductance) are associated with inflammation and lower values (lower conductance) with degenerative disturbances. The indicator drop is an important diagnostic criterion in EAV of a functionally disturbed organ. An indicator drop occurs during a measurement when the conductance of a given acupuncture point increases to an apparent maximum value and then decreases to a lower equilibrium value. In the present study, EAV was used to monitor the effects of qigong practice on therapeutic balancing of healthy subjects.

Two series of EAV measurements were made by the same operator and equipment. In both series, the subjects were asked to perform a qigong exercise of their choosing, usually sitting or standing meditation or moving qigong. The first series was performed during an international conference (4) at which qi and the human Channel system were among the main topics. About six months later, the second series was conducted in San Francisco with different subjects (5).

MATERIALS AND METHODS

The EAV instrument, a Computronix Acupro II system (Synergy Health Systems, 1223 Wilshire Boulevard #321, Santa Monica, CA 90403) was designed and operated by Douglas C. Leber. The instrumental test parameters were: 1.25 volts D.C. output voltage, 12.7 microamperes current output at full scale, and 95,000 ohms resistance at midscale of 50. A schematic of the electrical circuit is shown in Fig. 1. The instrument was calibrated from 0 to 100, and the value of 50 indicates that an organ associated with the acupuncture point was free of pathological problems. The tester pressed the brass probe electrode (0.13 cm diameter and connected to the positive side of the circuit) gently onto the acupuncture point as shown in Fig. 2. To minimized variations of skin conductance due to perspiration, tap water was applied to the skin in the region of the acupuncture point before the measurement. The cylindrical brass hand electrode (1-inch diameter and connected to the negative side of the circuit) was held in the subject's free hand, which was also moistened with water. Twenty four acupuncture points at the ends of the Channels of the fingers and toes of a subject were tested in about 5 minutes. The computer was programmed to provide information on the right and left side of the body for twenty organs and physiological functions of the body.

The subjects were 30 to 65 years of age. They were examined by EAV before and after practicing a qigong exercise for 10 to 15 minutes. The subjects went to a secluded spot to practice their own style of qigong, which was sitting or standing meditation or a form of moving qigong. The subjects were asked to balance their energies, and they were examined within 15 minutes after practicing qigong. One subject was examined by EAV before and after receiving qigong therapy from a qigong master and was also examined by EAV three more times within 22 hours.

RESULTS AND DISCUSSION

Series 1: In Series 1, four subjects were examined by EAV before and after qigong. Subjects A, B, and C, who had practiced qigong for more than 10 years, practiced their own style of qigong for 10 to 15 minutes. Subject D, who had studied qigong for about one year, was given a qigong balancing treatment for about 10 minutes by subject A, a qigong master who used a combination of acupressure massage and emitted qi to balance the Channels and organs of subject D. Subject A was not aware of that variations in the polarity of qi may exist in different parts of the his hands and of the body of the subject (6).

Examples of the EAV measurements before and after qigong are shown for subject D in Fig. 3 and for subject C in Fig. 4. The 20 pairs of horizontal bars represent the measured values at the acupuncture points associated with specific organs and functions of the body as described below the pair of bars. For a given pair of bars, the upper bar represents the value on the left side of the body and the lower bar that on the right side of the body. For example, LUCL and LUCR represents the lung Channel on the left and right side of the body, respectively. The scale for the measured values is shown at the bottom of each graph in the figure. A vertical line at the "normal" reading of 50 is a convenient reference for comparing changes that resulted from qigong practice. The two numerical values to the left of each bar are the actual measured values. The maximum value is on the left and the equilibrium value, which may be lower if there is an indicator drop, is on the right. The magnitude of the indicator drop is represented by a "white" bar and its numerical value is the difference between the maximum and the minimum measured values.

Visual inspection of Fig. 3 and Fig. 4 shows that qigong had decreased all measured values and had either eliminated indicator drops or reduced their numbers. However, qigong did not restore balance to some of the Channels and the corresponding organs. For example after the qigong balancing treatment for subject D, the measured values for the spleen, liver and gall bladder Channels on the right side of the body remained elevated with respect to the others at values of 66, 69 and 67, respectively. In the case of subject C, the measured values remained elevated for the stomach at values of 77 and 66 and for the urinary bladder on the right side of the body at a value of 68, and two of the nine indicator drops remained. These observations suggest that EAV can be used to monitor the effects of qigong therapy on individual organs of the body.

The results of the EAV measurements obtained before and after qigong for each of the four subjects are summarized in Table 1. For each subject, average measured values were calculated from the 40 values, 20 on the left and 20 on right side of the body (see Fig. 3). For each subject, a percentage change (change %) was calculated from the average measured values obtained before and after qigong. The results show that qigong had changed the average measured values of each practitioner in the range of -19 to -31%. The sum of all indicator drops (in meter divisions) for a given EAV examination were either eliminated or reduced markedly by qigong. The style of qigong of each subject and the duration of the practice are noted in a separate column in Table 1.

In Table 1, the plus and minus value that follows an average EAV value is an apparent "standard deviation" that indicates that individual Channels or body functions have measured values greater or less than the average value. This standard deviation would be zero if all the Channels and body functions were balanced and had the same measured AEV values. Individual Channels and body functions may not be balanced for many reasons, including chronic, acute, stress, and emotional factors. The magnitude of the apparent standard deviation may be regarded as a semiquantitative indicator of imbalance in the Channel system.

In a preliminary study to determine possible lasting effects of qigong, subject D was examined by EAV a total of four times over a period of 22 hours. The average measured value was 75.1±5.2 before qigong, 51.5±9.9 twenty minutes after qigong balancing, 55.7±10.4 four hours later after lunch, and 59.0±8.1 twenty-two hours later after breakfast. The increases in the standard deviations after the first 20 minutes were mainly due to large elevations in the measured EAV values of the Channels of the liver at a value of 85, spleen at 85, large intestines at 68, and kidney at 65. These changes are probably caused by food eaten at lunch.

Series 2. A blind protocol was used in Series 2 so that the EAV operator did not know when the seven subjects practiced qigong. This was accomplished by measuring the EAV of each subject three times, and in between measurements the subject left the examination room. After the initial EAV examination, the subjects were given a random selected card instructing them to practice qigong after the first or after the second EAV examination. Later the subjects informed the examiners when they practiced qigong. Of the seven subjects, E, F, G, H, I and K were experienced qigong practitioners, while subject J had studied qigong one year. Computer printouts similar to those in Fig. 3 and Fig. 4 were analyzed for each subject. The averages of the 40 measured values and the sum of indicator drops are tabulated in Table 2. The average measured values obtained just after qigong practice are indicated in boldface.

The results show that qigong practice changed the average measured readings of most subjects. The average measured values decreased for four subjects (E, F, G, H) in the range of -17% to -35%, increased for two subjects (J and K) in the range of 12% to 15%, and remained essentially unchanged for subject I. For subject I, a decrease in the average measured values was observed after qigong, that is, from the second to the third examination (82.7±2.7 to 61.2±11.8, respectively). This decrease may be due to a delay in the effects of qigong exercise. Indicator drops were present in the EAV of only three subjects before qigong, and these drops were either eliminated or decreased by qigong.

In series 2, the average measured values for four subjects (E, F, G, H) showed similar decreases in magnitude as those in series 1. However, the average measured values for the other three subjects (I,J, K) increased. This difference in response of individual qigong practitioners can be accounted for in many ways, such as by differences in qigong style, intention of the practitioner, and physical and emotional states. For example, we had asked the subjects to balance their energies, but subject J later told us that she had tried to increase her qi, thus perhaps explaining the increase of 12%.

Because of scheduling problems, we were unable to carry out control experiments. However, the reproducibilities of successive AEV measurements before or after qigong were satisfactory for five of the subjects. This can be seen in Table 2 by comparing the second and third measurements (after qigong) for subjects E, F, H, and J, and by comparing the first and second measurements (before qigong) for subject G. These successive readings changed less than 4%.

CONCLUSIONS

Our preliminary studies suggest that the EAV technique can monitor the effects of qigong on the therapeutic balancing of the Channel-organ system. EAV also should be valuable in other applications of qigong: 1) evaluating the effectiveness of different types of personal qigong exercises for balancing organs of the body, 2) measuring the receptivity of subjects to emitted qi, 3) evaluating the effects of different kinds of emitted qi, for example, positive and negative qi (8), 4) determining the duration of the balancing effects of qigong, 5) determining the relative healing power of qigong masters for certain medical problems, 6) comparing the relative effectiveness of energy balancing by qigong with other therapies, such as acumassage, acupuncture, healing with hands, Reiki, as well as conventional physical exercise, 7) investigating the therapeutic effectiveness of qi energy stored on materials such as paper (7), 8) investigating the therapeutic effectiveness of electrical, mechanical and laser stimulation(8), and 9) investigating the interaction between a qigong master and a subject (9).

ACKNOWLEDGEMENTS

The author acknowledges the cooperation of Douglas C. Leber of the Computronix Electro-Medical Systems, who designed and operated the EAV instrument. He also acknowledges support in arranging the experiments by Jim Jose of Synergy Health Systems, qigong master Gong Xin Xiong, Harry Kung, Linda Kung, and the qigong practitioners.

REFERENCES

1. Fred M. K. Lamb, Jr., M.D., Julia J. Tsuei, M.D., Zixian Zhao, M.D., M.S.: Bioenergetic Regulatory Measurement Instruments and Devices. Am. J. Acupuncture, Vol.16, No. 4: pp. 345-349, Oct.- Dec., 1988.
2. R. Voll: Twenty years of electro-acupuncture diagnosis in Germany: A progress report. Am. J. Acupuncture, Vol. 3, No. 1: pp. 7-17, 1975.
3. See collection of nine articles on Electroacupuncture According to Voll in the Am. J. Acupuncture, Special EAV issue, pp. 5-99, Second printing, 1989.
4. International Conference on Bioenergetic Medicine, Past, Present and Future, University of Hawaii, September 30, 1989.
5. Presented at the Second World Conference on Academic Exchange of Medical Qigong, Beijing, China, September 1993.
6. Omura,Y., Common factors contributing to intractable pain and medical problems with insufficient drug uptake in areas to be treated, and their pathogenesis and treatment: Part I. Combined use of medication with acupuncture, (+) Qigong energy-stored material, soft laser or electrical stimulation, Acupuncture & Electro-Thera. Res. Int. J., Vol. 17: pp. 107-148, 1992.
7. Omura, Y., Storing of Qigong energy in various materials and drugs (Qigongnization): its clinical application for treatment of pain, circulatory disturbance, bacterial or viral infections, heavy metal deposits, and related intractable medical problems by selectively enhancing circulation and drug uptake, Acupuncture & Electro-Thera. Res. Int. J., Vol. 15: pp. 137-157, 1990.

8. Omura, Y., Connections found between each Channel (heart, stomach, triple burner, etc.) & organ representation area of corresponding internal organs in each side of the cerebral cortex; release of common neurotransmitters and hormones unique to each Channel and corresponding acupuncture point & internal organ after acupuncture, electrical stimulation, mechanical stimulation (including Shiatsu), soft laser stimulation or Qigong, Acupuncture & Electro-Thera. Res. Int. J., Vol. 14: pp. 155-186, 1989.
9. Omura, Y., Unique changes found on the Qigong (chi gong) master's and patients's body during Qigong treatment; their relationship to certain Channels and acupuncture points and the re-creation of therapeutic Qigong states by children and adults, Acupuncture & Electro-Thera. Res. Int. J., Vol. 14: pp. 61-89, 1989.

Table 1. The effect of qigong exercise on the average measured EAV values and sum of indicator drops for each of 4 subjects before and after qigong (Series 1).

Each subject was tested before and after practicing qigong. Subject D was given qigong balancing therapy by subject A. The change (%) refers to the difference between the measured values before and after qigong. The indicator drop (ID) divisions are the sum of all such drops for a given subject. The style and duration of qigong practice is shown in the right-hand columns. Average measured values for before and after qigong were calculated from the average of 40 readings, 20 on the left side of the body and 20 on the right side (see Fig. 3).

Average measured values Sum ID Divisions Qigong
Before After Change Before After Time
SubjectQigongQigong(%)QigongQigongStyle(min.)
A69.0±3.351.4±4.4-26200Moving15
B72.0±3.953.3±7.1-26220Standing10
C67.0±6.654.6±5.7-1912928Sitting10
D75.1±5.251.5±9.9-31530Therapy10

Table 2. A blind study of the effect of qigong exercise on the average measured EAV values and sum of indicator drops for each of 7 subjects before and after qigong exercise (Series 2).

Each subject was tested 3 times. The bold faced numbers indicate measured values obtained just after qigong practice. Secret instructions informed the subjects to practice qigong either after the second or third EAV test. The change (%) refers to the difference in measured values before and after qigong practice. Indicator drop (ID) divisions are summed for a given subject. The style and duration of qigong practice are shown in the right-hand columns. The average measured values before or after qigong were calculated from the average of 40 measured values, 20 on the left side of the body and 20 on the right side (see Fig. 4).

Average Measured Values Sum ID Divisions Qigong
Change Before After Time
SubjectFirst testSecond testThird test (%)QigongQigongStyle(min.)
E61.3±15.439.6±11.238.6±9.7-35140Moving 15
F74.8±3.052.0±5.251.7±4.0-3000Sitting10
G76.1±2.6 79.1±4.258.1±8.6-2700Sitting10
H74.4±3.262.1±12.758.9±10.5-1700Sitting10
I79.2±4.182.7±2.761.2±11.8400Sitting10
J67.5±8.974.5±7.071.1±4.2122814Moving15
K67.2±11.5 53.9±13.562.1±14.71580Sitting10

APPENDIX 2

INTRODUCTION

This second Appendix includes research information on Medical Qigong therapy, collected by my good friend Richard H. Lee, Director of China Healthways Institute, San Clemente, California. Mr. Lee, a council board member of the World Academic Society of Medical Qigong, in Beijing, China, is a specialist in Western medical technology. He has worked extensively with the research department of the Beijing College of Traditional Chinese Medicine, studying the relationship of infrasonic waves emitted as Qi.

This research, focused on the Extension of Emitted Qi by various Medical Qigong Masters/ Doctors, was motivated by the pioneering research of Professor Lu Yan Fang at the National Institute of Electro-Acoustics in Beijing, China. Professor Lu developed prototype devices which simulated the frequency output of Medical Qigong doctors.

Mr. Lee has spent many years in China and abroad researching and collecting scientific data which led to the development of several Infratonic Medical Qigong Therapeutic Machines (in Chaotic resonances), which are currently being sold worldwide.

This second Appendix is a continuation of the research devoted to the scientific approach of analyzing and scrutinizing the claims made as to the actual effectiveness of Medical Qigong Therapy as a clinical modality. The result on the effectiveness of Medical Qigong Therapy as a solid and effective clinical modality being positive in conclusion.

The following information in this second appendix represents but a fraction of Mr. Lee's findings, however, I am confident that the reader will find the data fascinating.

Dr. Jerry Alan Johnson May 2000

ter fountain pouring out of the body, entering into the soles of the feet, where it again joins together with energy from the earth. While the energy is outside and circling the body, it is also gathering pure, radiant Cosmic Energy. Repeat this meditation nine times.

8. Finishing the Meditation

Both men and women should finish by collecting the energy at the cauldron and practicing Chi Massage. This completes the practice of the Thrusting Channels. Continue to practice for a few weeks until you gain control of it.

Additional Exercise for Opening the Thrusting Channels

Alternate Nostril Breathing

The alternate nostril breathing helps to generate more power in moving the pearl up and down the Thrusting Channels. By closing one side of the nose, it is easier to move the pearl through the specific left or right channels.

Hold the right nostril closed with the finger tips.

Inhale up through the left nostril, and feel the pearl move up from the perineum to the crown.

Exhale out through the left nostril and bring the pearl back down to the perineum.

Inhale through the left nostril and bring the pearl to the Middle of the perineum.

Close both nostrils and suck the pearl up through the middle Thrusting Channel to the crown. This suction is created by an inhaling motion without actually drawing any air into the lungs.

Hold the right arm down towards the ground and exhale any cloudy or gray energy out of the Thrusting Channel.

The same procedure is repeated in the Right Thrusting Channel.

Hold the left nostril closed with the finger tips.

Inhale up through the right nostril, and feel the pearl move up from the perineum to the crown.

Exhale out through the right nostril and bring the pearl back down to the perineum.

Inhale through the right nostril and bring the pearl to the middle of the perineum.

SCIENTIFIC INVESTIGATIONS INTO CHINESE MEDICAL QIGONG THERAPY

Richard H. Lee
Director China Healthways Institute
San Clemente, California

INTRODUCTION

In the years since the first edition of "Scientific Investigations" was published, the debate over the existence of Qi, the legitimacy of healers, and the reality of PSI phenomena has heated up. While most readers embrace energetic concepts like Qi as a useful framework for understanding otherwise unexplainable phenomena, some continue to reject Qi. Even in China, while an estimated 100 million people practice Qigong, many professionals remain skeptical. Scientists who actually investigate Qigong generally conclude that the phenomena really do happen, but still try to maintain an arms-length distance from it. Many doctors are also reluctant to discuss Qi openly even though most of the general public is quick to identify Qi as feelings of abundant vitality, and the absence of Qi as fatigue.

There appear to be three principal barriers to serious consideration of Qi.

1. Inertia: "There is not enough data." "These studies have not been replicated." This seems to stem from an unwillingness to explore the studies that have been done. This book presents enough information to satisfy the open-minded investigator and the Qi explorer, but nothing was added in this edition to satisfy those who demand overwhelming evidence.
2. Hidden Bias: This is probably the biggest resistance that Qigong research faces. Many people simply refuse to consider the possibility of action at a distance, as exhibited in Qigong and PSI research. On the basis of this single assumption, all empirical data which supports such phenomena must be rejected as mistakes, experimenter bias, or falsification. Nothing was added to this edition to try to overcome this hidden bias.
3. Need for a framework: While the information presented in the first edition of this book answered the question, "Is the phenomenon of Qigong scientifically measurable?," It left readers without a framework other than faith by which they can understand these phenomena. Without a framework of understanding, many are reluctant to accept these strange experimental results.

Others are less concerned about physical substance and seek to understand Qi as an aspect of intention or consciousness. This more closely parallels the approach of most Qigong masters who, through years of training, gradually gain mastery over their own mind (through focus of attention), emotions (through calmness and releasing desires), and physical body (through discipline). Interestingly, this second viewpoint is similar to the view of many skeptics who insist that phenomena of Qi are simply "a product of the mind." Combining the idea that Qi is strongly influenced by the mind, with the research in this book which shows that Qi is measurable in the physical world, we get a picture of Qi as a mind / body connection which is appealing to most readers.

The Chinese do not view Qi as a scientific substance, but rather, as the essence of life, the bridge of consciousness between mind and body, and the "eternal now" in which all activity occurs. The physical body supports physical fields (Qi) which support vibrational frequency patterns (Qi) which allow communication (Qi) between some kind of abstract consciousness (mind) and a physical body which is our vehicle.

Richard H. Lee, January, 1999

QIGONG MASTERS AND ENERGETIC MEDICINE

For thousands of years, China has been a major source of the world's technology. We are surrounded by Chinese inventions such as paper, movable type, gun powder, and surgical anesthesia. And while the West has shot past China in many technological areas, there are still areas where China holds an edge. The Chinese investigations into the phenomenon of Qigong over the last ten years have, in some ways, placed Chinese researchers at the forefront of energetic medicine. Many findings of this research are presented on the following pages.

Qigong has been practiced for thousands of years in China. Yet it has never before had the broad acceptance that it has today. This is because the scientific investigations into the nature of Qigong show clearly that something is going on beyond what physics might predict. Measurable energy is emitted from the hands of those who have mastered these Qigong techniques. These masters can influence events from a distance with energy (or signal) emitted from their hands. Further, these energy emissions and Qigong training exercises have scientifically measurable, beneficial effects on health and healing.

Qigong masters have demonstrated many remarkable feats. Some can soften and bend steel. Some can light fluorescent tubes with their bare hands. Others can kill cancer cells in laboratory experiments, and many can, from another room, alter the brain wave patterns of test subjects including test animals.

The energy they emit from their hands is measurable with scientific equipment in the forms of infrared, magnetic, and acoustical energy. In one test, a strong pulse of static electricity was measured at a point 50 mm above the head of a Qigong master. In another, a strong magnetic field was measured just at the instant that a heavy iron bar hit a Qigong master's head. The bar bent as it would against Superman's head. He was unharmed with no sign of a lump or a bruise.

In 1979 and 1980, the leaders of China decided to put Qigong to the test. The Western scientific test. High technology government organizations across the country, many as prestigious as the National Atomic Energy Lab in Shanghai, and the Space Science and National Electro-Acoustics Institutes in Beijing, started testing Qigong masters and promptly discovered that the phenomenon of emitted Qi was measurable. Some of these laboratories went further and actually developed therapy equipment such as the Infratonic QGM which reproduces the infrasonic component of the emitted Qi. This research has led me into Qigong and taught me many things I didn't think I ever wanted to know.

Today's Western scientists know little about Qigong, but it is an important healing technology in the world today. It is the basis of acupuncture and traditional Chinese herbal medicine, yet it presents effective medical intervention when used alone. Americans have been radiating cancer with energy emitted from machines for the last few decades. The Chinese have been using energy emitted from the hands of Qigong doctors to treat cancer for thousands of years, finding that, in many cases, tumors can be shrunk without side effects.

These scientific experiments are repeatable. Scientific laboratories in America will reach the same conclusions as those in China. The evidence is persuasive that systematic Qigong training produces real benefits. And advanced practitioners can emit energy from their hands that is measurable with scientific equipment. Further, therapeutic equipment has successfully reproduced many of the beneficial effects observed. The Chinese scientific investigations into medical Qigong are indeed at the heart of a medical revolution that is improving the science of health and healing around the world.

THE SCIENCE OF CHINA

For thousands of years China has been a center for the advancement of civilization. The science of China has produced a wide variety of technologies. Gunpowder is the central ingredient to modem warfare. Paper and printing with movable type have for centuries been at the center of education, communication, and information storage. Despite the growth of computers, this system will continue to be the world's dominant information storage method.

Many centuries ago, a physician named Hua Tou invented surgical anesthesia and performed many kinds of surgeries like appendectomies and other of today's popular surgeries. While the Chinese contributed to what has today become modem medicine, they also created "Chinese medicine," a system of medicine based on the Chinese science of "Qi" or vital energy. It is this system from which acupuncture and Chinese herbal medicine have evolved. And at the heart of this system lie the science and practice of Qigong.

QIGONG'S LONG HISTORY

Through the millennia Qigong has been an influential force in the molding of China. Until recently it has been hidden from public view. Like many other disciplines, the art of Qigong has been taught from father to son or from master to disciple only after a strict oath of secrecy has been given. Knowing a science that others don't know gives a practitioner a decided advantage in earning a living. Thus, until recently, very few books have been written about Qigong, particularly about the more advanced techniques of study. The exception is the secret books that have been maintained in religious monasteries, being copied and recopied by studious monks through the centuries.

Even this activity in monasteries came to an abrupt halt with the Communist government in China when Mao put an end to most religious activities. Through the Cultural Revolution, monasteries and temples were shut down. Many of the ancient texts and artifacts were destroyed. Others were stored in government libraries. Many of the Qigong masters were killed. A few went into hiding or escaped from the country.

At the end of the Cultural Revolution, Deng Xiao Peng set about rebuilding much of the cultural heritage of China, allowing limited freedom of religious expression. He also promoted the rediscovery and preservation of traditional Chinese science and medicine, which included Qigong.

It is interesting to note that much of the willingness to share the secret teachings of Qigong came from outside countries. Masters who had emigrated to the West had started teaching the techniques openly without the strict code of silence. And some of the secret Qigong texts that had been taken from the temples and monasteries were published for people around the world to read. Qigong was no longer a secret so there was no longer any value to secrecy in China and Qigong masters became much more willing to teach what they knew.

The most influential factor in the Qigong revival was, perhaps, the new policy on the part of the China government to allow freedom of religion, particularly religion that had a basis in China's cultural heritage. Thus, Taoists and Buddhists who had preserved its teachings in secret for centuries were free to share their knowledge. This allowed Qigong practitioners to demonstrate their skills freely in public without fear of being condemned to death as witches or evil beings. Paranormal skills were again publicly accepted as a product of China's cultural heritage.

The big boost to Qigong came in the early 1980's when modern science turned to study the tradition of Qigong. The leaders of China reasoned that, if Qigong is to be accepted, it must pass the rigorous screening of scientific scrutiny. Studies were funded in the prestigious scientific institutes of China to determine whether the special skills of the Qigong masters could be scientifically verified. The results were most impressive. Many forms of energy were measured coming from the hands or bodies of Qigong practitioners in reproducible scientific experiments.

Scientific investigations into the effectiveness of medical Qigong quickly showed that, for many illnesses, medical Qigong was unsurpassed by any other medical system in the world. The discovery that energy emitted from the hands of Qigong doctors under controlled laboratory conditions was highly effective in killing cancer cells, gained extensive press coverage around the world.

Qigong science is a very new field with valuable technologies just beginning to surface. But given the fundamental nature of these discoveries, Qigong science could easily dominate the world of the 21st century.

SIMULATION OF EMITTED QI

Simulation of emitted Qi has been the goal of much of the Chinese Qigong research that has been conducted since about 1980. Many devices have been developed and tested, some of which have considerable potential. The following is a description of the most common forms:

Infrared devices have been developed some of which, through rare-earth emission surfaces, emit characteristic frequency bands, while others modulate the infrared output according to recorded patterns emitted by Qigong masters. These devices tend to have the most effect where coldness in the body is effectively treated with heat.

Electrical devices are often adapted to deliver current through the skin at frequency patterns that follow patterns produced by Qigong masters. These units have been used principally by acupuncturists.

Acoustical devices, which reproduce the subsonic output of the emitted Qi in the form of deep acting massage action, have been shown to be effective in pain management, circulation of Qi, blood, and endocrine fluids, and relaxation. The Infratonic QGM was used in several of the laboratory tests described in this book to simulate the emitted Qi in experiments. Because this device offers many insights into the nature and function of emitted Qi, and because many of the readers of this book use the Infratonic QGM at home or in their medical practices, much of the research around this device is included in this book.

SCIENTIFIC PLAUSIBILITY OF QI, THE HUMAN ENERGY FIELD

Some readers might tend to reject the findings of this study based on their assumption that the existence of human energy fields and the altering of a person's energy field are outside the laws of physics, and therefore impossible. It is therefore appropriate here to briefly review some of the findings of researchers mostly within the last decade to show that these energy fields are quite measurable with existing equipment and that there is strong evidence that known biophysical mechanisms can account for the observed phenomena.

First, the human body clearly has a vibrating electrical field, measurable for decades through such techniques as EMG, EEG, and EKG. How is this possible? The classical view of the human cell as a bag of water with a nucleus has been, for the most part, rejected in favor of models in which a highly structured collection of filaments, tubes and fibers connect the cell's nucleus not only to the surface of the cell but beyond, in a matrix which connects and interrelates the cells of the entire body (Oschman 1994) and (Pinta and Coffee 1991). Second, helical molecules within the body, such as DNA, keratin, collagen, actin, and myosin have piezoelectric qualities. As they elongate and contract they produce voltages. Also, when voltages are applied, they expand or contract producing mechanical activity and acoustical energy.

While it is well established that electrical signals are produced and received by the body, readers are more likely to question whether a magnetic field interpenetrates and surrounds the body. In 1963 researchers at Syracuse University reported the first measurements of the magnetic field of the human heart, just a millionth the strength of the earth's magnetic field, yet highly coherent and measurable throughout the body and beyond. Then in 1971, the SQUID, a highly sensitive superconducting magnetometer, was developed which was used to measure the magnetic field of the brain, 100 times weaker than that of the heart (Cohen 1972).

Many researchers now believe that the magnetic field of the heart, which extends throughout the body plays a role in regulating biological functions. Then, in 1991, Seto and colleagues measured the magnetic field between the hands of healers to be as strong as 1 milligauss. This is less than 1% the strength of Earth's magnetic field, but 1000 times as strong as the magnetic field produced by the heart. If the heart regulates biological functions with it's weak field, it is certainly feasible that a magnetic field from the hands of healers, measured to be many times stronger than the heart field might influence biological functions.

But, how can a magnetic field be produced from the hands? The Josephson junction, a superconducting semiconductor which is the basis of the SQUID's extremely high sensitivity to weak magnetic fields, has been predicted in quantum physics calculations to be present in living tissue. This was verified just ten years ago. (Del Giudice et al 1989). DNA is one of the biochemical structures shown to act as a superconducting magnetic field detector, able, through the Hall effect, not only to detect very weak magnetic signals, but also to produce magnetic signals (McCraty 1993). Thus DNA may act as a signal amplifier, releasing its energy coherently into passing magnetic waves, much as the ruby rod of a laser releases its light energy coherently with a passing photon to produce a laser beam. This provides a mechanism by which healers might produce the observed relatively strong biomagnetic signals, and by which a test subject or patient might be influenced by such signals (Oschman 1993).

Thus, modern advances in science now provide mechanisms by which it is possible for healers to produce magnetic and electric signals of significant magnitude to influence patients. For those who seek a more indepth overview of this rapidly advancing field of knowledge, "The Scientific Basis of Energy Medicine" by James L. Oschman, 1998, is highly recommended.

REFERENCES

Cohen D 1972 Magnetoencephalography: Detection of the brain's electrical activity with a superconducting magnetometer. Science 175: 664-666

Del Guidice ES, Doglia S, Milani M, Smith JM, Vitiello G 1989 Magnetic flux quantisation and Josephson behaviour in living systems, Physica Scripta 40: 786-791

Dumitrescu I, Kenyon JN Electrographic imaging in medicine and biology, Nevil Spearman Limited, Suffolk England, 1983

Konikiewicz L, Griff L Bioelectrography a new method for detecting cancer and monitoring body physiology, Leonard Associates Press, Harrisburg, 1984

Lee R Bioelectric vitality- exploring the science of human energy, China Healthways Institute, 1997

Liu G, Wan P, Peng X, Zhong X The influence of the emitted Qi on the auditory brainstem evoked responses (ABER) and auditory middle latency evoked responses (MLR) in cats, Proceedings of the First World Conference for Academic Exchange of Medical Qigong, Beijing College of Traditional Chinese Medicine, 1988.

McCraty R, Atkinson M, Tiller WA 1993. New electrophysiological correlates associated with intentional heart focus, Subtle Energies 4: 251-268

Niu Xin, Liu G, Yu Z Measurement and Analysis of the Infrasonic Waves from the Emitted Qi, Proceedings of the First World Conference for Academic Exchange of Medical Qigong, Beijing College of Traditional Chinese Medicine, 1988.

Oschman JL 1993 A biophsysical basis for acupuncture. Proceedings of the First Symposium of the Committee for Acupuncture Research, CAR, Boston.

Oschman JL, Oschman NH 1994, Somatic recall, parts I-II Soft tissue memory / Soft tissue holography, Massage Therapy Journal, American Massage Therapy Association, Lake Worth, FL 34: 36-45, 66-67, 101-116

Pinta KJ, Coffee DS 1991 Cellular harmonic information transfer through a tissue tensegrity-matrix system. Medical Hypotheses 34:88-95

Seto A, Kusaka C, Nakacato S et al 1992 Detection of extraordinarily large bio-magnetic field strength from human hand. Acupuncture and Electro-Therapeutics Research International Journal 17:75-94

THE FUTURE OF QIGONG

Chinese research has found that Qigong training increases balance, quickness and endurance in athletes, and that fighter pilots trained in Qigong have quicker reactions and greater tolerance for the G-forces of sudden turns. Qigong has provided revolutionary treatments for hypertension and cancer, and has the potential for much more.

If, as the Chinese claim, Qi is the fundamental substance of the universe making up both matter and energy, and if we can through our bodies and our awareness, control and direct this Qi, not only within our own bodies, but as has been seen, beyond the limits of our bodies, the fantasy of "the Force" in Star Wars comes within the grasp of reality. Psychic phenomena like telekinesis and mental telepathy become minor extensions of the human manipulation of Qi. The Western ideas of positive thinking take on new meaning:

"The mind is the builder" and "Your thoughts create your reality."

The Chinese science of Qigong gives us proven tools to strengthen our ability to structure the world around us by training our minds and bodies to feel and understand Qi.

Remember that Western science and technology gave us electric motors which, when coupled with man-made equipment, can do the work of a thousand men. This came with our understanding of the principles of electricity. Emitted Qi simulation devices such as the Infratonic QGM provide this work-saving feature of machines. As we learn more about Qi, how it functions, and how it is directed by the human body, we will learn how to construct more and more powerful machines. We will see Qigong devices not only in hospitals but also in agriculture, in building air conditioning systems, in chemical processing plants and in space flight. The scientific Qigong research that started just a decade ago will grow and grow, and perhaps dominate our world of the 21st century.

However, the real emphasis of the Qigong movement and the intent of most Qigong teachers is not just to heal patients with illness, but to expand human potential. The research presented in this book shows that Qigong exercises help people to develop, not only the ability to heal themselves and others, but to do things which scientists considered impossible just a few years ago. Through a study of Qigong, there is strong evidence that we can become more than we ever thought possible.

INFRASONIC QIGONG RESEARCH

The discovery that specific bands of very low frequency sound influence healing and vitality was an accident. A "friend of the family" walked in to the National Electroacoustics Laboratory in Beijing and asked Prof. Lu Yan Fang, an acoustics scientist, if she would test his hand to see if any sound was coming out of it when he emitted Qi. She thought he was crazy but went along because she didn't want to dishonor her family by turning out a friend.

Prof. Lu's discovery that he did indeed emit a very strong signal in the infrasonic range was quite a surprise. This signal was 100 times stronger than that of a healthy, normal person. Elderly and sick people had even lower readings.

To verify that this infrasonic sound had a physiological effect, she built a device to simulate this output and tested it in hospitals. It worked to relieve pain and assist recovery in a wide variety of patients.

Prof. Lu's patent for the Infratonic QGM was the first ever filed in China and her device was awarded three awards for outstanding contribution to science and medicine from Chinese national science organizations.

It is clear from the Chinese infrasonic research presented in this chapter that infrasonic sound is an important component of emitted Qi.

INFRASONIC SIMULATION OF EMITTED QI FROM QIGONG MASTERS

by Professor Liu Guo-long, MD, PhD
Beijing College of Traditional Chinese Medicine
with Richard Lee

SUMMAY OF RESEARCH

Emitted Qi from Qigong masters clearly has a strong effect on the central nervous system, not only in humans but also in animal subjects. Qigong meditation and the Infratonic QGM have similar effects. These findings are summarized below:

Repetition of these tests with animals confirmed that these changes are physiological and not psychological phenomena by eliminating placebo effects.

DOUBTS ABOUT EMITTED QI

At the beginning of my research with Qigong, I was confident that a study of neurophysiology would prove that the "Wai-Qi" emitted by Qigong masters was nothing more than a psychological factor induced by the waving of hands and hypnotic suggestion.

Qigong is a system of physical and mental exercises which has been practiced in China for thousands of years. Up until the 1980's, most Chinese considered Qigong masters (those who have mastered this Qigong training) to be mythical story book characters with super-human powers. However, as the Chinese government began to support scientific research into Qigong, the few remaining true Qigong masters began to surface, amazing researchers with feats like killing bacteria in test tubes and causing previously paralyzed people to get up and walk.

I thought that these were all tricks of one sort or another, perhaps magicians' sleight-of-hand, hypnosis, or optical illusion. When I got the chance to work with people claiming to possess these abilities, I was fascinated. This was my chance to test with scientific equipment, whether there was any truth behind the excitement about Qigong masters. I was confident that I could disprove the myths.



Emitted Qi has a pronounced and repeatable effect on EEG. It enhances frontal and occipital EEG power spectra, and often enhances the frontal so much that frontal becomes the dominant EEG activity whereas occipital dominance is more common. Emitted Qi also enhances and synchronizes the Alpha.

BACKGROUND

I was a specialist in Western medical technology assigned to the research department of the Beijing College of Traditional Chinese Medicine. The project was sponsored by the China Government Department of Education and the Department of Natural Sciences. My research group was assigned to study the relationship of infrasonic waves to emitted Qi. These research grants were motivated by the pioneering research of Prof. Lu Yan Fang at the National Institute of Electro-Acoustics in Beijing, who developed prototype devices to simulate the output of Qigong doctors.

Research has confirmed that humans have a very high degree of acoustic activity in the subsonic range below 20 Hertz (infrasonic), similar to the alpha rhythm of EEG. Also, people with chronic illnesses were found to have a much lower level of infrasonic activity, while Qigong masters had a much higher level of infrasonic output when they were emitting Qi.

The implication was that infrasonic sound might be related to human functioning, and further, that it might be in some way involved in the mechanism of brain functioning. We searched the available scientific literature for research papers for relationships between sound waves and brain waves but found none that had been done.

Extensive clinical research, based on infrasonic Qigong simulation, showed it to be effective for a wide variety of hospital problems. These results are what motivated the National Departments of Education and Natural Sciences to look further into the importance of infrasonic sound and what led to the research I am about to describe:

THE BRAIN AS A DETECTOR OF EMITTED QI

I had learned in my many years of research with the Electro-Encephalograph (EEG) that the human brain responds to even the most subtle of stimuli to the body, so I reasoned that, if there were really any scientific basis to emitted Qi, it would show up in the brain waves of test subjects who were placed in the path of these emissions. I expected to see no difference between the resting states and the Qi emission states.

What we saw was extraordinary. Within a few seconds after the Qigong master began to emit Qi, the subject's EEG would begin to shift. The EEG power spectrum was enhanced on all channels while the most pronounced increase was in the frontal lobe. Also, there was an enhancement and synchronization of the Alpha Rhythm in all channels. When the Qigong master stopped emitting Qi the EEG would gradually shift back toward the baseline readings.

To determine whether infrasonic energy was a significant part of the emitted Qi, we used the infrasonic Qigong prototypes in the same experiment. It was located 18 inches away, directly behind the back of the head of the test subject. The EEG electrodes were attached as before. The simulator was activated for short periods of time and the results recorded. We found that the effects on the receiver's EEG were quite similar to those of the emitted Qi.

Our further research involved monitoring the various sensory-cortical evoked potentials during Qigong meditation, emitted Qi, and infrasonic Qigong simulation. We again found very similar results from all three stimuli. We found that a large portion of the cerebral cortex was inhibited while other somatosensory cortex were excited. One of the significant findings of this study is that the inhibition of the cerebral cortex during Qigong meditation is clearly different from the excitation of the cerebral cortex that is measurable during sleep.

Through Acoustical Brainstem Evoked Response (ABER) it was found that the brainstem structures from the medulla to the hypothalamus were significantly facilitated. The brainstem plays an important role in regulating the functions of the inner organs, motor function, and emotion.

The implications of these studies were startling. Qigong masters can, without touch, voice, eye contact or any other traditional communication means, induce a clear, strong, and highly measurable change in a subject's brain functioning. A synchronization of alpha rhythm indicates deep relaxation, and is closely associated with accelerated healing. Enhanced power spectrum in the frontal lobe is especially significant because the association cortex of the frontal lobe is concerned with higher motor action, higher sensory function, emotional and motivational aspects of behavior, and integration of autonomic function. Facilitation of the brain stem, with its regulation of internal organs, may be a mechanism by which physical healing is induced or accelerated.

Despite these highly significant changes in EEG and evoked potentials, the subject had felt nothing and had no idea of the profound changes taking place within them.

The findings of these studies are solid evidence that a Qigong master can induce real physiological changes in a subject from several feet away, and further, may help to explain the high rate of recovery from chronic degenerative diseases in groups of hospital patients under the care of Qigong masters. These studies also show that the infrasonic Qigong simulator can induce similar changes in brain function and that, through Qigong meditation, a Qigong master can induce these same changes in his own brain.

SCIENTIFIC CONTROLS

There is much disagreement on how emitted Qi affects the brain. Many doctors insist that brain changes are psychologically induced, and that verbal suggestion, impressive hand motion, and expectation of the subject account for the observed phenomena.

To test this, we had several Qigong masters and people pretending to be Qigong masters treat the test subjects. The subjects were told that all were Qigong doctors, and all moved their hands in similar ways. We saw no significant changes in brain wave patterns with the fake Qigong masters, but when the real doctors emitted their Qi, or when we used the infrasonic Qigong simulator, we repeatedly got the highly significant changes.

Even this did not satisfy many of the doctors who reviewed our work, so we repeated the study with animals. We monitored EEG in awake rabbits and ABER in anesthetized cats as Qigong masters emitted Qi toward them. Even though there was no voice or eye contact between the Qigong masters and the animals, and the masters emitted Qi from several feet away, we saw shifts in EEG and ABER (Acoustical Brainstem Evoked Response) similar to those observed in the human subjects. This is a highly convincing result because all kinds of placebo effects are eliminated, yet modification of brain function at a distance remains.

INFRASONIC VS. ELECTROMAGNETIC INTERFERENCE

Extremely low frequency (ELF) electromagnetic signals can affect EEG. There is growing concern about the low frequency radiation produced by 60 Hz electrical power lines located close to people's homes and schools because of apparent disruption of brain and cellular function. ELF signals will cause the principal EEG power spectrum to show a spike at the frequency of the ELF signal. This is because the EEG is easily entrained by ELF signals. When the signal is discontinued, the EEG abruptly returns to normal. Electrical power lines operate at 60 Hz, which corresponds to EEG in the high Beta range, associated with mental anxiety and confusion. The entrainment of EEG to 60 Hz around power transmission lines may be why researchers are finding that people who live close to these power lines show a higher incidence of brain tumors.

The results using the infrasonic Qigong simulator were quite different from ELF signal entrainment. The shifts in EEG were gradual rather than abrupt, and while dominant EEG frequency did drift toward the dominant peak infrasonic frequency, it was a broad spectrum of EEG activity rather than a spike. The enhanced power spectrum continued after simulation was stopped, gradually decreasing and returning to the pretest state. From these observations it is clear that the effects of infrasonic are quite different from the entrainment of ELF electromagnetic signals.

SUMMARY

When I started this project in 1976, I had serious doubts about Qigong masters and emitted Qi. Now I am convinced that emitted Qi is very real and that Qigong is a very valuable art. With the support of the China government, an estimated 50 million Chinese are practicing Qigong daily, and many Western hospitals have added Qigong departments for patients with chronic and degenerative diseases. In addition, the China government has funded extensive scientific research into the nature of emitted Qi with the goal of advancing science and medical technology.

The study of emitted Qi and infrasonic sound, as they relate to human health and functioning, is a broad and exciting field. The use of Qigong in treating chronic degenerative diseases such as cancer and hypertension in China has proven very effective. It has been employed to accelerate healing for thousands of patients with a wide variety of diseases in Chinese hospitals. I am confident that emitted Qi, Qigong meditation, and the infrasonic Qigong simulator will play an increasing role in health care around the world.

SECONDARY ACOUSTIC BIOLOGICAL RESPONSE

(The following is from a technical paper presented in Beijing, China by Professor Lu Yan Fang, the inventor of the Infratonic Qigong Machine.)

"People often talk about sound. Common sense suggests that sound is what the ear can hear, the frequencies between 60 Hz. and 20,000 Hz.

Secondary sound is that sound that is outside of the range of the human ear, specifically low frequency sound below 60 Hz. Secondary sounds travel long distance with little attenuation.

In the 20th century, in the 1930's, this secondary sound was discovered, but it wasn't until the 1960's that it started drawing much attention. Since then the study, measurement, and analysis of the physical features of secondary sound have

Close both nostrils and suck the pearl up through the Middle Thrusting Channel to the crown.

Hold the left arm out and down to the ground, exhaling any cloudy gray energy down to the Earth.

Repeat 3 – 9 times or until you feel the Thrusting Channels clean and clear with positive energy.



Fig. 7.18 *Alternate Nostril Breathing*



Fig. 7.19 *Exhale cloudy energy out of the Thrusting Channel.*

included:

1. Physical Features
2. Secondary Sound Measurement
3. Technology of Analyzing, and
4. Protecting the Body Against Strong Secondary Signals

Initial secondary sound biological response studies emphasized protecting against high level secondary sound which can damage the human body. Laboratory studies showed that strong secondary sounds beyond 150 dB are harmful to biological bodies. The American Environmental Protection Agency sets standards for secondary sound, concluding that secondary sounds below 130 dB are not harmful.

To this date there had been almost no studies investigating how secondary sounds affect biological processes. And never before has there been any thought of testing of the human body as a secondary sound source. Since 1983, we have worked with more than 70 Qigong masters, and have discovered for the first time that the human body actually emits a secondary sound signal. The frequency distribution peak of the signal is located in the secondary sound region of the sound spectrum, at about 10 Hz.

Through more than 100 repeated lab experiments we found almost identical results of frequency distribution. According to the analysis of test results in 1984, the first infrasonic Qigong prototypes were constructed. These machines used electroacoustic technology to simulate the frequency distribution of the Qigong master's low frequency signal, but stronger. This simulation of the human body life signal emission is then fed back to the human body. In the two years that followed, many clinical and animal tests proved that weak secondary sounds benefit the human body. The discovery that infrasonic sound is a basic substance of Qigong emission opens Qigong science's big door, opening an exciting new field for medical science.

Through hospital and clinical use, 1,134 patients were treated by the Infratonic QGM. Animal studies were also performed. Clinical use and animal use prove that this kind of secondary sound signal can strengthen many functions of the human body. The Qigong machine can have significant treatment value to the human body and works by reproducing the acoustic waves produced by the human body. It can promote circulation, regulate Qi and blood, open channels, and relieve pain.

The Qigong master is not alone in this ability to emit the secondary acoustical signal. Most everybody generates a similar signal. Young people with good health can emit the signal to a degree similar to that of a Qigong master. People with a weak body and elderly people have similar signals but much lower in power. People having Qigong training have a signal that is strong all the time, but especially strong during Qi emission. However, in normal people, as age increases or health condition worsens, the signal decreases. This explains why the human body is only sometimes a source of secondary sound. In the meantime, the body is also a receptor of secondary acoustical signals, and can be benefited by receiving the weak secondary acoustic signals.

Very early in the development of traditional Chinese medicine, this effect had been shown to exist. Anmo, and tuina, Chinese therapeutic massage techniques, give the human body this kind of low frequency stimulation. This stimulation through acupuncture points follows the cell as the basic pathway, and then goes to the meridian, and reaches the problem area. Then the problem can improve. Just like an old Chinese saying: "If you can get enough energy into the problem area, you can use that energy to treat the problem."

The human body's secondary acoustical biological effect is a scientific reality. The human body produces, delivers, emits, receives and controls this low frequency energy. This weak secondary acoustic effect has beneficial biological effect on the human body. It and its relationship with traditional Chinese medicine are of great value to the medical world. It is hoped that all scientists do research in this area.

MEASUREMENT AND ANALYSIS OF INFRASONIC WAVES FROM EMITTED QI

Niu Xin, Liu Guolong and Yu Zhiming
Beijing College of Traditional Chinese Medicine,
Beijing, China

The theory of traditional Chinese medicine suggests that Qi is one of the fundamental substances in human bodies. Modem scientific research of the essence of the emitted Qi has yielded some positive results. In order to find out the relation between the emitted Qi and infrasonic waves, to explore the mechanism of the emitted Qi, to find out how a person generates and receives the emitted Qi, and to provide a quantitative physical scale for indicating the strength of the emitted Qi for experimental studies of the effect of it, we measured and analyzed the infrasonic waves from the Qi emitted by Qigong masters.

The test, which was done by an infrasonic testing system made in Denmark, was conducted in a noise-proof room in the Institute of Sound and Electronics under the Ministry of Electronic Industry. The background noise in the room was lower than 30 dB (decibel). The microphone was hung in the air over Laogong (P-8, acupuncture designation for a point in the center of the palm), the distance being 2 cm with no contact.

The experiment tested the release of emitted Qi at Laogong (P-8) in the palm, Mingmen (Du-4), Baihui (Du-20), Dantian, and Jianzhi. Special attention was paid to the test of Laogong (P-8).

1. The peak frequency of the infrasonic waves from the tested Qigong and non-Qigong masters ranged from 8 to 12.5 Hz. In one case the frequency reached 16 Hz. In another two, it reached 6 Hz.
2. The infrasonic waves from the Qigong masters ranged from 45 to 76 dB and those from the non-masters, 45-50 dB. Comparison of the intensity of infrasonic waves during the Qigong state and the non-Qigong state before and after the emission of Qi showed a statistically significant increase ($P<0.01$).* The increase of wave intensity of the Qigong masters compared with that of the non-Qigong masters was also obviously significant ($P<0.01$).* **The energy of the Qigong masters was over 100 times higher than that of ordinary persons.**
3. The masters who had practiced Qigong for many years and often emitted Qi to treat patients had a higher intensity of infrasonic waves, reaching over 70 dB. Those who started to practice Qigong a short time before and mainly practiced *Nei Yang Gong* had a lower intensity of the infrasonic waves (lower than 60 dB.)

Infrasonic and ultrasonic waves are all sound waves which cannot be detected by human ears. The frequency of infrasonic waves is below 20 Hz. Many natural phenomena and artificial actions may generate infrasonic waves. Human bodies may act as a source or a receptor of infrasonic waves giving rise to a biological effect. The infrasonic information we acquire a from the measurement of the Qi makes it possible to study the effect of the emitted Qi.

The Valsalva state in which a Qigong master emits his Qi, is the breath regulating state of Qigong and also the state of emitted Qi in the breath holding exercise. Non-Qigong masters who simulate the Valsalva state also send out more intense infrasonic waves. It shows that every person has infrasonic characteristics. A long period of practicing Qigong helps increase the radiative intensity of infrasonic waves. Entering the Valsalva state helps in the emission of Qi. The Qi emitted by masters who adopted Song Jing Gong (relaxed Quiescent pattern) had more intense infrasonic waves (reaching 72 dB). Thus, the mechanism of the emitted Qi released by different exercise patterns is different.

We have found by a series of tests that very able Qigong masters can keep the energy of infrasonic waves at a relatively high level (over 70 dB). So tests on infrasonic waves can be used to screen Qigong masters.

The human body can generate and emit infrasonic waves. As far as acoustics is concerned, the most suitable resonant frequency of human tissues is within the range of infrasonic waves. It shows that the human body easily receives infrasonic waves. Infrasonic waves are a strong, effective part of the emitted Qi because of their quick, long distance transmission, strong penetration, and non-decreasing vibration. It is possible that infrasonic waves themselves transmit the messages between the Qigong masters and the subjects, or serve as a carrier.

[(P<0.01) means that the probability that these test results would occur by chance is less than 1%. This measure of "statistical significance" tells us that the sample size was large enough and causative factors strong enough that the results of this study are reliable.]*

NEURO SCIENCE—NERVE IMPINGEMENT AND EMITTED QI

China Healthways Newsletter's Interview with Liu Guo Long, MD, PhD
Beijing College of Traditional Chinese Medicine
by Richard H. Lee in Palos Verdes, CA, August, 1991

(This interview came about as a result of requests by readers of China Healthways Newsletter for an explanation of neuroscience as it relates to vital energy and healing.)

Dr. Liu provides a fresh view into the role of vital energy in the nervous system and how vertebral nerve impingement affects Qi.]

China Healthways Newsletter: How has your research changed your views on Qi?

Dr. Liu: I started my research with the intention of proving that there was no physiological basis for Qigong, that it was nothing more than a circus trick. As my research progressed, I became more and more convinced that emitted Qi is both measurable and effective for healing. This was not before I eliminated all possible psychological effects by replacing human subjects in my experiments with laboratory animals and got similar results. In my view, emitted Qi is quite real because it is easily measurable using the human brain as a detector.

CHN: How does Qigong affect the function of the nervous system?

Dr. Liu: This is a very complex question because emitted Qi affects different organs quite differently. First, it clearly increases Electro-Encephalograph (EEG) activity throughout the brain and nervous system, principally in the frontal cortex and in the range of alpha, 8 to 14 Hz. This greater mental activity in the alpha range is associated with clear relaxed state of deep thought, which many agree is effective to relieve tensions and clear the mind. The frontal cortex of the cerebrum is at the top of the hierarchy. It is the center of awareness within the body, directing the cerebellum and brain stem. Increased EEG activity in the frontal cortex would indicate expanded awareness.

Secondly, emitted Qi inhibits the sensitivity of the cerebrum to outside stimulation while facilitating the sensitivity of the hypothalamus and medulla of the brainstem. The cerebrum performs high level conscious activities. When inhibited it receives less visual, auditory, and sensory input, and presumably sends fewer and clearer signals to the brain stem, which, in turn, is responsible for automatic functions such as respiration, vasodilation, and the complex functioning of internal organs. Because the brainstem is facilitated, it is more able to "tune-in" to the needs and illnesses of the body and to activate the needed repairs to restore health. I believe that this enhanced awareness of internal stimuli in the brain stem, combined with reduced sensitivity to outside stimuli, is the primary product of emitted Qi that brings about accelerated healing throughout the body.

CHN: Then, would you say that emitted Qi directed only to the central nervous system can enhance healing in all parts of the body?

Dr. Liu: That's right.

CHN: How can Qi applied to the local injury accelerate healing?

Dr. Liu: Neurons in all parts of the body are in constant oscillation, producing measurable output in the range of 8 to 14 Hz, the frequency of the alpha pattern. Neurons can both emit and receive energy in this frequency band. Therefore nerves throughout the body can be facilitated by the emitted Qi. The application of emitted Qi to the site of an injury facilitates the signals to the brain stem. Stronger and more accurate signals to the brain means a more effective healing response directed to the area of injury, including greater vasodilation, increased lymph flow, and an increased supply of nutrients for cell regeneration.

CHN: Is there any direct effect of emitted Qi on the injured tissue.

Dr. Liu: Yes, of course. Qi is the vital energy that drives the regeneration of tissue. Supplementing the available Qi can directly increase the metabolic activity of the injured tissue just as it increases the EEG activity of the brain.

CHN: How can emitted Qi strengthen the immune system against bacteria and viruses?

Dr. Liu: The mechanisms are the same. A facilitated brainstem and nervous system are able to identify the invader more quickly and accurately and to direct the immune system response more precisely to the area of infection. And, as before, the added supply of Qi fuels a more furious response from the immune system. Chinese herbs such as Huang Qi (Astragalus) are also highly effective at enhancing Qi to accelerate the immune response.

CHN: Can mis-position of spinal vertebrae disrupt this healing process?

Dr. Liu: Most definitely. There are basically three types of nerves, the sensory, the motor, and autonomic. Vertebral pressure on any type of nerve cell can inhibit sensitivity or create false signals. If sensory nerves are affected, important information may never reach the brain, or may arrive confused, misdirecting the healing effort. Affected motor nerves can result in spasm or dropsy, and most importantly, impingement of autonomic nerves affects the function of internal organs and if it continues over a long period, can result in serious degeneration or dysfunction.

Often, impingement of motor nerves can perpetuate the problem. As muscles spasm from false motor nerve signals, they may tend to pull the vertebrae further out of alignment, increasing the impingement. In this case, the problem tends to get worse with time as greater impingement further increases the muscle spasm.

The best way to deal with this sort of nerve impingement is through adjusting the position of spinal vertebrae. Often just the vertebral adjustment is sufficient to release pressure on the motor nerve and release the muscle spasm, allowing complete recovery. However, in many cases the impinged nerve is slow to recover, showing some immediate release of spasm but not complete release. The remaining muscle spasm is sufficient to pull the vertebra out of adjustment again and re-establish the motor nerve impingement.

In these cases of muscle spasm aggravating the nerve impingement, better results are achieved if a nerve facilitation technique is used in conjunction with the adjustment. Emitted Qi or the Infratonic QGM applied a few minutes before or after the adjustment facilitates the nerve to provide greater muscle relaxation and quicker regeneration of the nerve. In upper back disturbances the Chinese herbal formula, Hsiao Yao Pien is also excellent to accelerate progress by promoting improved Qi circulation through the motor nerves and through the muscle itself.

INFRASONIC TREATMENT OF ASTHMA

by Su Cheng Wu,
Department of Pediatrics,
The First Affiliated Hospital Guangxi Medical University,
Nanning, Guangxi, China.

(This clinical study finds that infrasonic sound is effective in treating symptoms of childhood bronchial asthma, and in strengthening immune function as measured by T-lymphocyte population.)

Fifty cases of child bronchial asthma were treated with the Infratonic QGM and routine drugs. T lymphocyte subpopulation (CD2 , CD4, CD8, and CD4/CD8) of peripheral blood was measured to evaluate this treatment's clinical effectiveness on raising immunity. The control group of 15 cases was treated with routine drugs only.

TREATMENT METHOD

Based on the features of child bronchial asthma and a dialectical therapeutics of traditional Chinese medicine, the following four points were treated for 5-10 minutes each morning for 5 days:

Dingchuan (located on the back, 0.5 cun lateral to the lower border of the spinous process of the 7th cervical vertebra). Indications: Facilitating the flow of the lung-qi to relieve asthma. Feishu (Located on 1.5 cun lateral to the lower border of the spinous process of the 3rd thoracic vertebra). Indications: Facilitating the flow of the lung-qi to resolve cough. Tiantu (located on the neck, on the anterior midline, in the center of the suprasternal fossa). Indications: Cough, asthma, chest pain and so on. Danzhong (located on the chest, on the anterior midline, on the level of the 4th intercostal space, on the midpoint of the line connecting the two nipples). Indications: Checking upward adverse flow of the lung or the stomach-qi).

OBSERVATION CRITERIA—FOUR GRADES

1. Clinically controlled: Remission from symptoms. Occasional mild asthma attacks are remitted without taking any medicine.
2. Obviously curative effect: Asthma attack is relieved within a short time.
3. Improvement: Some abatement.
4. Inefficacy: Symptoms, signs and reproduction rate of T lymphocyte subpopulation are unimproved or exacerbated.



T- lymphocytes in Control vs Experimental Groups

THERAPEUTIC RESULTS

94% of the experimental group showed improvement (as shown to the right). In the control group 80% showed improvement as follows: Clinically controlled - 6 cases; obviously curative - 3 cases, improvement - 3 cases, inefficacy - 3 cases. X^2 determination indicates that there is a more obvious therapeutic effect in the treatment group than that in the control group (P<0.01).

LABORATORY RESULTS

T Lymphocyte subpopulation showed a significantly greater increase in the experimental group than in the control group treated by routine drugs alone as shown below:



*Notes: Comparison before/after treatment P<0.01 unless noted: * = P>0.05*

In this study, clinical symptoms of wheezing, coughing and asthma caused by infection of the upper respiratory tract are obviously relieved using the Infratonic device. Testing of peripheral blood showed that the reproduction rate of T lymphocytes subpopulation in treatment group is greater than those receiving routine treatment, indicating increased level of immunologic function of human cells. The Infratonic QGM reduces the course of treatment without discomfort or side-effect. Its biological mechanism of action should be explored in the future.

THE INFRASONIC SIGNAL FROM THE QIGONG PERSPECTIVE

Sun Hua Ling, MD, Beijing Military Qigong Research Institute

(Dr. Sun, a physician and gifted Qigong doctor presents her analysis of the mechanism of emitted Qi and infrasonic signal.)

With the development of human society, health care has become an important part of daily life. Qigong training and techniques and devices like the Infratonic QGM can provide valuable influence. This instrument simulates the low frequency sound of Qigong doctors, which penetrates tissues and organs of the human body, influencing the function of cells, providing clinical results. This study reflects clinical treatment with the QGM of more than 1000 patients.

Cells are units of the human body. Biological electric waves transfer information between cells, forming a biological field of consciousness. The aim of Qigong training is the unification of this field, making the human body more in tune with nature and able to affect nature.

Some "hard Qigong" masters can break stones but can't treat disease because their emitted Qi's amplitude and frequency can not be absorbed by the human body. To be effective, emitted Qi or simulated emitted Qi must be close to the biological waveform of the patient. Then it is easily absorbed and treatment is more likely to be successful. Effective treatment protocols for 30 disease conditions were developed.

MECHANISMS OF THE QGM

1. Relieves pain and edema.
2. Strengthens immune function and reduces inflammation.
3. Normalizes autonomic nervous system.
4. Relieves some symptoms of heart disease.

RELIEVES PAIN AND EDEMA

When applied to sprain of joints, fracture, and arthritis, the QGM has the obvious result of reducing pain distention and edema. It also relieves pain due to sciatic neuralgia, cancer, lumbago, periarthritis of shoulder and stiffness of neck and shoulder muscles. Thus the QGM can effectively treat disease caused by disturbance of blood circulation and can improve local blood circulation.

Patients may feel a sensation of heat, relaxation of muscles, and gradual reduction of pain. This phenomenon may be due to excitation of cells, nerves, and blood vessels around the diseased area. This excitation may contribute to the reduction in pain.

STRENGTHENS IMMUNE FUNCTION AND REDUCES INFLAMMATION

The QGM has a function similar to short wave and ultrashort wave diathermy which strengthens immune function and reduces inflammation. It strengthens metabolism of organs and cells, increasing cellular energy, thus making the immune system stronger.

Diseases such as nephritis, inflammation of intestines and gall bladder, pancreatitis, gas, duodenal ulcer, and infantile dyspepsia, all respond favorably to treatment with the QGM, probably because of this factor of increased cellular energy.

NORMALIZES AUTONOMIC NERVOUS SYSTEM

Where the autonomic nervous system is disturbed, the QGM is often useful. This includes neurasthenia, tenseness of the cerebral cortex, and fatigue. Research shows that the low frequency signals emitted by the QGM penetrate the tissues and organs, altering the internal environment of cells, improving cellular metabolism, and relaxing nerves and muscles, thus regulating the balance between internal and external environment of nerve cells.

Some scholars suggest that emitted Qi may increase cerebral bioelectricity, balancing cell environment, resulting in disappearance of disease. In traditional Chinese medicine, this corresponds to "regulating the meridians and collaterals", "improving blood circulation", and "nourishing internal organs".

RELIEVES SOME SYMPTOMS OF HEART DISEASE

The QGM can relieve symptoms such as lack of blood in the heart muscle, arrhythmia, pressure on the chest, palpitation, and shortness of breath for pulmonary heart disease. This result may be due to improved metabolism of cells and improved local blood circulation.

EMITTED QI TRAINING INCREASES INFRASONIC SOUND EMISSION OF HEALERS

Prof. Lu Yan Fang, National Institute of TV and Electroacoustics, Beijing
Richard H. Lee, Director, China Healthways Institute, USA

(This study supports the premise, proposed by researchers earlier in this chapter, that infrasonic sound can be used as a measure of Qigong ability and indicates that Qigong skills, in this case, the ability to emit infrasonic sound from the palms, can be increased through intensive training.)

Can students in an intensive Qigong training increase the output of infrasonic sound from their hands after one week of training?

To answer this question (and others), 29 Americans traveled to China. The strength of their infrasonic emission was measured before and after the training at the Institute of TV and Electroacoustics, a national institute of technology and standards. Prof. Lu Yan Fang, who conducted the seminal research on infrasonic sound emission two decades ago, conducted the testing. In her research she had found that Qigong masters, powerful healers in China, were able to emit high intensity low frequency sound, 100 to 1000 times stronger than average individuals. Before the experiment she expressed strong doubts as to the possibility of increasing energy emission within one week because Qigong masters require many years to cultivate powerful Qi emission.

Prof. Lu had seen that strong young adolescent males could produce sound as high as 60 dB while average individuals emitted in the 40's and 50's. She was not surprised when in the initial testing 21 of 25 produced scores in the 40's. She felt that an improvement to 60 dB (only one participant had scored in the 60's in the pretest) would suggest improvement to supernormal ability, and that scores above 70 dB would be in the range of the powerful and well known Qigong healers.

A powerful Qigong healer who had scored well in this test before was invited to demonstrate. After several tries, the best he could do was 67 dB, which was 100 times what an average adult could produce, and still in the range of powerful healers, but not nearly as good as he had done previously. He was rather embarrassed and the translator explained that he had worked late the night before and had exhausted his Qi. An hour later he returned covered with perspiration. Apparently, in an effort to redeem himself, he had been building up power doing Qigong exercises for the past hour. This time his score was 78 dB, 10 times the power he had generated just an hour earlier. Participants applauded as he came out of the testing chamber. He had redeemed himself. Interestingly, he was massaging his shoulder as if he had strained it during the Qi emission.

This was a most interesting scenario. First the failure of an experienced Qigong doctor to produce high power, then his performing Qigong exercises to build up his Qi, and finally, his powerful sound emission, offered a persuasive picture that some sort of energy can be stored in the body during Qigong exercises and discharged rapidly through the shoulders to the hands to create intense sound, and possibly straining muscles.

Supporting this finding, one participant was experimenting with the equipment afterwards, emitting Qi into the microphone. At first he could produce high levels of infrasonic sound in front of the microphone, but after five minutes of emitting he could produce only 10% of the power he had produced earlier. He did not feel tired, but as he tried to emit sound, he found that his hand would no longer tremble as it had before. He had apparently exhausted his supply of this form of Qi!

Test Scores: The average score for the group before the training was 47 dB with only four participants scoring above 50. Under the guidance of Master Wan Sujian, a well known Qigong teacher and physician, the group began a 10-day intensive which included climbing mountains and the Great Wall, practicing emitted Qi, and receiving extensive emitted Qi. The group also received physical therapy treatments to open meridians and remove potential blockages in the arms and shoulders which would otherwise restrict the flow of Qi to the hands. The results of both tests are shown below.

After the emitted Qi intensive, the number scoring above 50 dB tripled from four to 13. Five scored above 60 and two above 70. An average increase of 7 dB (to 54 dB) means that students were producing five times the infrasonic energy they had produced before the training. (Statistical significance $t < 0.0005$) Professor Lu was quite impressed. She felt that five of the participants had both the amplitude and spectral distribution associated with powerful Qigong healers.

An interesting technique: While four of the five participants who scored above 60 were men with strong musculature, one petite woman scored 64 dB, which is 10 times the power that anyone else of similar build had scored. When asked her secret, she answered, "Well, to be honest, as I was waiting to emit Qi I silently asked our teacher for help. As soon as I did, I felt a surge of energy flowing through my arm and my hand started trembling powerfully. When I was done, my arm was sore clear up to the shoulder." She had massaged her shoulder after emitting her Qi much as the Qigong master who first demonstrated had done.

SCIENTIFIC QIGONG RESEARCH

Measuring the emitted Qi from Qigong masters has been the purpose of scientific research in many major scientific research institutes in China,



Participants were able to emit substantially higher levels of infrasonic sound after a week-long Qigong training. On the average, scores increased from 47 dB to 54 dB, a five-fold increase in infrasonic energy.

including the following:

- China Immunology Research Center, Beijing
- Institute of Space Medico-Engineering, Beijing
- National Research Institute of Sports Science, Beijing
- Institute of Psychology, Academia Sinica, Beijing
- China Academy of Traditional Chinese Medicine, Beijing
- Institute of Traditional Chinese Medicine, Beijing
- Beijing College of Traditional Chinese Medicine, Beijing
- Tangshan Health Institute for Women and Children, Hebei
- Zhejiang Research Institute of Traditional Chinese Medicine, Hangzhou
- Guiyang College of Traditional Chinese Medicine, Guizhou
- Shanghai Academy of Traditional Chinese Medicine, Shanghai
- The Second Military Medical College, Shanghai
- Shanghai Qigong Institute, Shanghai
- Xing Cheng Air Force Sanitarium
- Zhao Baofeng Beidaihe Qigong Rehabilitation Hospital, Hebei
- Shanghai Institute of Hypertension, Shanghai
- Shenyang Institute of Traditional Chinese Medicine, Shenyang
- Institute for Industrial Health, Xian
- Shandong Medical University, Shandong
- Anti Epidemic Centers of Henan Province, Xin Xiang
- Institute of High Energy Physics, Beijing
- Jiangxi Chinese Medicine and Pharmacy Institute, Jiangxi
- Nanjing Aeronautical Institute, Nanjing
- Institute of Space Medical Engineering, Sichuan
- Chinese Academy of Sciences, Chengdu

While thousands of investigations have been done, just a few have been described here, principally those that are reproducible either with Qigong masters or with Qigong simulation equipment. These studies show that emitted Qi is effective in treating digestive problems, infectious diseases, and bone fractures; that measurable changes in blood chemistry occurs a result of Qigong exercises; and that emitted Qi affects electricity and light in physics experiments.

EFFECTS OF THE EMITTED QI ON HEALING OF EXPERIMENTAL FRACTURE

Jia Lin and Jia Jinding

National Research Institute of Sports Science, Beijing, China.

(This study offers laboratory evidence that Qigong masters can accelerate recovery from fractures. From 1988 FWCAEMQG Proceedings)

The emitted Qi has been found to have a good curative effect on soft tissue injuries such as muscle soreness, scleroma in muscles, acute muscle sprain, muscle contusion and pains. Fracture is also a common injury in sports medicine. We have cured some cases of fracture with the emitted Qi. The purpose of this experiment was to investigate the biological effect of the emitted Qi on healing of fracture.

Sixteen healthy male rabbits, weighing between 1.9 and 2.5 kg, were divided into two groups: the control group and the emitted Qi group. A fracture with a gap of 3 mm was made in the left radius. The rabbits in the emitted Qi group were given the emitted Qi treatment for three minutes per day after fracture. X-ray films were taken every week. Each week specimens for light microscopy from two rabbits were cut into slices of 8*u*m thickness along vertical axis of radius, stained with H.E., and studied by a light microscope. The morphological observations are as follows:

1. Based on some radiographic indexes, such as reaction of fracture section, periosteal reaction and amount of callus formation and callus density, we found that the amount and density of callus formation were better in the emitted Qi group than in the control group. The difference was significant in the 2nd week

(n=16. P<0.01) and 3rd week (n=12. P<0.05).

2. Ultrathin sections were produced with LKB-III ultrotome, stained with uranyl acetate and lead citrate, and studied with a DXB electron microscope (EM). The changes in myofibrils were observed and photographed (x13000). Injured myofibril volume density in the pictures were calculated by means of point-count method.

The ultrastructural examination revealed that overstrain caused pathological changes such as muscle fiber edema, shortening or lengthening of sarcomeres, disorganization, breaking and disappearance of myofibrils as well as Z lines, accompanied by edema and damage of mitochondria. These changes could be seen less frequently in the emitted Qi group than in the control group. The result of quantitative analysis showed that the volume density of myofibrils of the injured muscle in the emitted Qi group was 2.47%, and that in the control group, 20.41 %.

MEASURING QI IN THE BLOOD

A Preliminary Study of the Relationship Between Qigong and Energy Metabolism—The Changes of the Blood ATP Content in Qigong Masters in the Qigong State

by Wang Zhenchang, Huang Jian, and Wu Zijuan
Shanghai Qigong Institute, Shanghai, China

[This revealing study quantifies a physiological change in the blood during Qigong exercise and Qi emission. When Qigong masters do Qigong exercises, blood ATP level increases, indicating a storing of energy. When they emit Qi, blood ATP level drops, indicating a depletion of energy. This is measurable evidence that physiological changes are occurring when a healer says he is collecting energy or emitting energy. It is also evidence that healers may be exhausted after treating patients and need rest and energy building activities to remain in good health themselves. From the 1988 FWCAEMQG Proceedings.]

Recently it has been reported that the emitted Qi by Qigong masters may have material foundation and the internal Qi cultivation can promote health. In this paper, the relationship between Qigong and energy metabolism was studied. The ATP content was measured with 20*ul* of blood drawn from the ring finger of the Qigong masters before and after the Qigong exercise, and, at rest, by the method of bioluminescence assay.

The instrument (FG-30 Type Luminescence Meter) and the chief reagent (luciferase-luciferin) were produced by Shanghai Plant Physiology Institute. The experiments were conducted in three groups:

1. The experimental group: The blood was drawn from each Qigong master's ring finger after he had taken a short rest, and before he exercised Qigong and entered the Qigong state. If he could emit Qi, he would do it for 5-10 minutes. If he exercised internal Qi cultivation, he would do it for half an hour. After the Qigong exercise the blood was drawn again. After rest for half an hour the blood was drawn once more.
2. The control group: The above procedure was repeated on the second day but the Qigong masters did not exercise Qigong.
3. The healthy group: Healthy persons did as the Qigong masters did at the same time. The results are as follows:

In 10 healthy persons the blood ATP contents were constant during the experiment. For nine Qigong masters in the control group the blood ATP contents did not change markedly. The blood ATP contents in 11 Qigong masters after emitting



Summary

Opening the Thrusting Channels

Begin the Fusion practice by Opening the Three Fires, activate the compassion fire forming the pakuas by chanting the eight forces, forming the collection points, fusing the colors, and forming the pearl. Review the explanation discussed previously. Once you feel the pearl is strong and full of energy, you do not have to go through all these stages all the time. Just think and let it happen.

The Thrusting Channels are Opened in Four Stages.
(1) to the diaphragm; (2) to the neck; (3) to and out of the crown; (4) down to the feet, into the ground; and up to the crown.

1. The Left Thrusting Channel penetrates the left testicle (in men), left side of the perineum and anus, left ovary (in women), left kidney, spleen, heart, left lung, left parathyroid and thyroid glands, left ear, left eye, and left hemisphere of the brain.
2. The Middle Thrusting Channel runs through the middle of the scrotum (in men), perineum, middle of the anus, cervix (in women), prostate (in men), aorta, vena cava, pancreas, stomach, heart, thymus gland, throat, tongue, pituitary, hypothalamus, and pineal glands, and crown.
3. The Right Thrusting Channel goes through the right testicle (in men), right side of the perinium and anus, right ovary (in women), right kidney, liver, right lung, right parathyroid and thyroid glands, right ear, right eye, and right hemisphere of the brain.

Note: Avoid overheating the heart, liver, or head. Be very gentle with this procedure. If the energy reaches the heart and head too quickly the heart will become congested and you may experience pressure. If the heart overheats with energy, avoid thrusting above the diaphragm, and practice the Heart Sound (***Hawwww***).

Strengthen your anus muscle, the foundation, connected to the perineum and everything in the body above it. Saliva purifies the mouth, and nourishes immortality. When resting, create and gather saliva. Make it thick and swallow down forcefully.

their Qi decreased markedly (the mean decrease was .000131 M compared with that of the healthy group ($P<0.01$). The blood ATP contents in 16 Qigong masters after cultivating the internal Qi increased markedly (the mean increase was .000054 M) compared with that of the healthy and the control group ($P<0.05$). The duration of Qigong practice influenced the changes of the blood ATP content.

The blood ATP contents in both groups of Qigong masters recovered after rest. Qigong masters were observed continually. First they exercised Qigong, cultivating the internal Qi. Then they emitted their Qi. The blood ATP contents changed as above. Conclusions were discussed. The emitted Qi may have a material foundation because the blood ATP contents decreased after the Qi was emitted. The internal Qi cultivation process promotes anabolism and increases CAMP level so that health may be improved.

EFFECTS OF QIGONG ON NEUROTRANSMITTERS

Liu Binghuai, Jiao Jie and Chen Quanzhu
Anhui College of Traditional Chinese Medicine, Anhui Province, China
Li Yefu, Shang Lili (Affiliated Hospital)

[This study shows that you don't need to be a Qigong master to gain healing benefits from Qigong exercises. New Qigong practitioners with chronic illnesses showed significant normalization of neurotransmitter concentration after Qigong practice. From the 1988 First World Conference for Academic Exchange of Medical Qigong (FWCAEMQG)]

It is well accepted that Qigong contributes to preventing and curing of diseases and prolonging life. To study its mechanisms, the authors observed by means of fluorescence spectrophotometry in 68 subjects the variations in blood content of the following monoamine neurotransmitters before and after the Qigong exercises. (5-hydroxytamine: 5-HT, norepinephrine: NE, and dopamine: DA) Forty-four of the subjects were male, 24 females. Their age ranging from 25 to 68 years old, with an average of 48. They all had practiced the Qigong exercise for one month. All were patients of common chronic diseases such as hypertension, coronary heart disease, gastric ulcer, gastritis, pulmonary emphysema, chronic bronchitis, joint system diseases, neurasthenia and neurosis. Results are as follows:

1. A comparison of monoamine neurotransmitter contents in the blood of the subjects pre- and post-exercise showed a general reduction in 5-HT, averaging from 0.42 to 0.21 *ug*/ml, close to the normal value of 0.15 *ug*/ml. The difference was notable ($P<0.001$) Variations in NE and DA tended to go up. The average NE was from 0.27 to 0.35 *ug* /ml, and DA increased from an average of 0.86 to 1.19 *ug* / ml. The above description showed that the effect of the Qigong exercise is closely related to the monoamine neurotransmitters in the body fluid.
2. Effects of the Qigong exercise on the blood monoamine neurotransmitters of patients of different diseases: The subjects were divided into five groups according to the nature of their disease. Subjects in each group showed reduction in blood 5-HT content after they had practiced the Qigong exercise. In all the groups, the content of vasoconstrictor substance 5-HT dropped to the normal concentration level, resulting in sufficient blood supply for the local tissues and organs. It also improved blood flow, promoted metabolism and strengthened the physiological function of the cells in the tissues thus helping to restore health, adding to the efficacy of Qigong.
3. The Qigong exercise helps regulate the neuro-body fluid inner environment. Through regulating the 5-HT blood concentration in the neurotransmitters of parasympathetic nerve, it causes the extra high blood 5-HT of the cardiovascular patients to drop to the normal level. It also dilates the coronary artery and improves the physiological functions, resulting in the relief of symptoms.
4. The Qigong exercise helps build or strengthen

the physiological function of the digestive system. The exercise exerts an influence on the control of nerves that govern the activities of the internal organs. It is shown by variation in the blood content of neurotransmitters NE, DA and 5-HT, with 5-HT getting lower and DA getting higher, facilitating local blood flow and metabolism in the tissues.

5. Through regulating the concentration of pain producer 5-HT in the peripheral blood, the Qigong exercise achieves an analgesic effect. The drop of 5-HT content is relative to the result of analgesia. This fact shows that the drop of 5-HT is good for invigorating blood circulation and reducing extravasation, which is a proof of the TCM principle: "pain is removed when block is eliminated."

The Qigong exercise results in preventing and curing of diseases. It helps regulate the neuro-body fluid inner environment, promotes activities of organs and maintains dynamic equilibrium of the organism through self stabilization.

PHYSICAL CHARACTERISTICS OF EMITTED QI

Gui Yongfan, Chen Qi, Li Yinfa, and Jiang Shen
Nanjing Aeronautical Institute, Nanjing, China
[Emitted Qi can alter the results of common physics experiments shown in this study from 1988 FWCAEMQG Proceedings.]

In this paper, three functions of the emitted Qi which were discovered with the aid of some physical instruments, such as the Van de Graaff generator and light sensitive plate are discussed.

1. The emitted Qi can restrain the discharge process. The discharge between the two balls in the Van de Graaff generator will be stopped or the period of discharge will become longer when the emitted Qi is exerted on the instrument. The Van de Graaff generator was used for testing. The two discharge balls in the generator were pulled apart until the critical state was reached. Then the Qigong master aimed his emitted Qi at the discharge space. The distance between the fingers or palm of the Qigong master and the discharge space was 10 cm to 3 M. We have discovered the following phenomena:
   a. The emitted Qi stopped the discharge or made the period of discharge longer.
   b. The Qigong master had no sensation of getting an electric shock when he emitted his Qi near the discharge space. Nevertheless, when he stopped emitting his Qi, he had the sensation of an electric shock if his hand was still near the discharge space.
   c. In the restraining process, a series of restraint and discharge, such as restraint—intermittent bursts of discharge—restraint, sometimes appeared.
2. The emitted Qi can cause the exposure of light sensitive plates wrapped in a piece of black paper. By false color image processing with a picture processing instrument, we obtained a color photograph, in which the image of fingers and the Laogong (P-8, center of palm) can be seen clearly. The Qigong master emitted his Qi at the emulsion layer of a light sen-



The concentration of the monoamine neurotransmitter 5-hydroxytamine decreased toward the normal value of 0.15 ug/ml in the above groups of patients after one month of Qigong exercises.

sitive plate from about 10 cm away for about 10 minutes.

RESULTS

a) The color of the controls was darker than that of the affected plates. b) After development, white speckles, various patterns or orderly stripes appeared on the affected plates.

SUPERCONDUCTING MAGNETOMETER MEASURES CHANGES DURING QIGONG

Wu Benjie, Dept. of Biophysics, Beijing Medical University
Wang Xiubi, Institute of Somatic Sciences, Beijing,
Wang Zijun, Nanjing University
Liu Jianben, Institute of Geophysics, Beijing

[Here we see that Qigong masters can produce magnetic fields from their palms, and that these fields have characteristic frequency bands. From 1988 FWCAEMQG Proceedings.]

A dynamic study of Qigong (QG) magnetic signals (MS) by a flux-gate magnetometer was conducted in a magnetically shielded room. Under the QG state, MS was <2Hz in frequency and several *n*T (T = Tesla, the unit of magnetic flux density, 1*n*T = 10^{-9} T) in amplitude. For deeper understanding of the MS dynamic properties, human weak MS were investigated by a superconducting biomagnetometer which is wider in frequency response (DC to 10 kHz instead of DC to 10 Hz) and higher in sensitivity. Through a frequency-power spectrum analysis by a computer, the MS changes under QG state were analyzed quantitatively.

Twenty persons (38 tests) were selected as subjects, and divided into two groups. (1) The control group consisting of three persons did not practise Qigong, 46.3 years old in average; (2) The Qigong group (practising for 1-20 years) consisted of 17 persons (31 tests), 48.3 years old in average.

The subjects took off all magnetic things; then came into a magnetically shielded room, with the acupoint to be measured aiming at the probe. The distance between the probe and Laogong (P 8) was about 6 cm, and that between the probe and head acupoints was about 4.5 cm. The MS dynamic changes were recorded continuously, before, during, and after QG state (3 minutes each).

MS was measured by a superconducting biomagnetometer, Model M-601. The frequency power spectra were analyzed by a signal processor, Model 7T17-S. In this paper the power changes were all of relative values.

The experimental results indicate that under the QG state three kinds of MS (1Hz, 3 Hz and <2 kHz) are measured from different acupoints Laogong (P 8), Baihui (Du 20), Yintang (Extra); there are three kinds of MS changes in intensity: increasing, decreasing and no change; and there is a good repetition of the change patterns and signal frequency of MS. Two novel phenomena were found, i.e. decrease of power and the change of frequency spectrum in MS during QG.

QIGONG AND CANCER

Cancer is one area where western science can use some help. Our government has pumped billions into cancer research, yet the problem continues to grow. Chemotherapy and radiation have such negative side effects that the time has come to look beyond therapies of killing "bad" cells, toward therapies with which the individual patient brings his own body into order.

In China, the obvious answer is Qigong. Cancer occurs when the cells of the body follow the will of an outside influence, perhaps a bacteria or a virus or a genetic predisposition. If Qi is strong and flowing smoothly within the individual, many Chinese believe that the cells will do the will of the organism, not of an outside influence.

A very interesting experiment that illustrates the will of an individual influencing cell growth is presented in a study by Dr. Feng Lida, MD, Ph.D., a famous Beijing researcher. She had Qigong masters treat vials of E-coli bacteria. The first vial was held but not treated. The Qigong master emitted Qi to the second one to try to "kill" the bacteria. He directed "health-promoting" Qi to the third one. Dr. Feng reported that, with over 40 repetitions, the health promoting dose resulted in a seven- to tenfold increase in the number of E. coli. The health destroying dose lowered the number of bacteria by one half or more. This experiment illustrates the power of the Qigong master in influencing cell growth. Every one of us has the latent ability to do the same, directing Qi to control disease within our own bodies. This can be seen from the success of programs emphasizing visualization and meditation.

If Qi is weak in an area of the body, abnormal growth will appear. Qi is weakened by poor nutrition and lack of exercise. It is also weakened by mental and environmental stress. Chemotherapy and radiation put heavy additional loads on the body, draining it of Qi. This is why methods to strengthen Qi are so valuable.

This chapter is devoted to Qigong as it is applied to cancer. It is clear from these studies that Qigong is an option that every person trying to beat cancer should consider, regardless of whether western techniques are also pursued. Chemotherapy and radiation in many cases have been shown to be of little value improving quality or length of life. They are not the only option. The following evidence shows that Qigong is an important therapeutic modality for treatment of cancer.

THE EFFECT OF THE EMITTED QI ON CARCINOMA CELLS

Feng Lida, Qian Ju Qing, Chen SuQing, et.al.
China Immunology Research Center, Beijing, China

[This influential paper is the first presented in the 1998 FWCAEMQG Proceedings, and shows that emitted Qi can kill cancer cells and alter chromosomes in vitro, providing clinical evidence that cancer patients would do well to learn Qigong.]

We used the techniques of tissue culture, cytogenics and electron microscopy to study the Hale cells and SCG-7901 human gastric adenocarcinoma cells, the change of the cellular ultrastructure and abnormal structure of the chromosomes of the cells. The results showed:

1. The effect of the emitted Qigong on the Hale Cells:

We repeated the experiment 20 times under identical conditions. After the Hale cells received the emitted Qi for 20 minutes, the survival rate of the cells in the experimental group was 69.28% of that in the control group, i.e. 30.72% of the cells in the experimental group were killed. At the same time we observed the Hale cells with a translation electron microscope, and found that degeneration and swelling took place in some of the cells which received the emitted Qi. The endoplasmic reticula were dilated obviously, and the nuclei of the cells were destroyed.

THE EFFECT OF EMITTED QI ON THE GASTRIC ADENOCARCINOMA CELLS:

After the gastric adenocarcinoma cells received the emitted Qi for one hour, the survival rate of the cells was 74.98% of that in the control group. i.e. the average destruction rate of the cells was 25.02%. We repeated the experiment 41 times under identical conditions, and through statistical analysis, found a difference between the two groups ($P<0.01$). In the meantime, a scanning electron microscope was used to study the cells. The results showed that the microvilli of the cells which received the emitted Qi had remarkably dwindled or disappeared and tiny holes could be seen on the surface of the cells.

3. The effect of the emitted Qi on the chromosomes of the gastric adenocarcinoma cells: We repeated the experiment 10 times under identical conditions. 1420 tumor cells in the control group and 1,428 tumor cells which received the emitted Qi for 60 minutes were analyzed. The subdiploid in the control group was 2.11%, the superdiploid was 0.14%, whereas the subdiploid in the experimental group was 3.29% and supertriploid was 0.56%. The statistical significance in these findings ($P<0.05$).

The structure of the chromosomes of the gastric adenocarcinoma cells also varied. In the experimental group, the total abnormality rate was

5.39%. The total abnormality rate in the control group was 1.40%. (P<0.01).

SUMMARY:

Tumor is a common disease which endangers man's life and health. The study on the effects of the emitted Qi on carcinoma cells, especially on the study of the structure and the chromosomes of tumor cells, has not been reported in the world before. The human chromosome is a material base of human heredity and a carrier of the genetic material. The results of our studies showed that the abnormality of the chromosomes of the gastric adenocarcinoma cells was significant after they received emitted Qi. The rate of exchange, breaking, and the dicentromere in the structure of the chromosomes of the gastric adenocarcinoma cells is increased. The results suggested that the emitted Qi could kill the chromosomes of the gastric adenocarcinoma cells. The study may start a new way to cure carcinoma.

QIGONG AS A THERAPEUTIC AID FOR ADVANCED CANCER PATIENTS

by Sun Quizhi and Zhao Li, Kuangan Men Hospital China Academy of Traditional Chinese Medicine, Beijing, China

[This article shows that, in clinical trials, cancer patients were far better off when they combined Qigong exercises and chemotherapy as compared to chemotherapy alone.]

One hundred and twenty three cases of advanced cancer treated simultaneously with drugs and Qigong has been reported in this paper. These were inpatients of our department during the past five years. Among them there were 60 males and 63 females. The youngest was 20 years old. The average age was 47 years old. These patients were diagnosed pathologically as malignant cancer, 70 cases were in the III stage, 53 were in the IV stage, of which, cancer of the stomach accounted for 42.23%, cancer of the large intestine 31.70%, mastocarcinoma 11.29%, and cancer of the esophagus and cardinal carcinoma, 8.1% each.

The 123 patients were divided into two groups. The experimental group included 93 cases treated with drugs and Qigong exercises. The control group, which consisted of 30 cases, was treated by drugs alone. Similar drugs were given to the two groups. Each patient who received the therapy of drugs and Qigong did the Qigong exercises for over two hours a day, three months as a course. Symptoms, signs, body weight, and immunological indices, etc. were recorded before and after treatment. The results were as follows:

1. Amelioration of general symptoms: In the experimental group, 81.7% of the patients regained strength, 63% improved appetite, 33.3% were free from diarrhea or irregular defecation in the experimental group, while in the control group the rates of patients were



Cells of lung cancer before irradiation with emitted Qi



Villus exfoliation of lung cancer cells after irradiation with emitted Qi.

10%, 10% and 6%, respectively. The difference between the two groups is significant. ($P<0.01$)

2. Body weight: In the experimental group, 50.54% of the patients' body weight increased more than 3 kg, and 5.4% of the patients' body weight decreased more than 3 kg. In the control group, the rates were 13.3% and 30.0%, respectively. The difference between the two groups is, again, quite significant.
3. Phagocytosis of macrophages: In the experimental group, the phagocytic rate of macrophages increased by 12.31 % and the index of macrophages increased from 0.45 before the combined therapy to 0.63 after. In the control group, the phagocytic rate did not elevate, but decreased by 7.87% while the phagocytic index also dropped from 0.63 to 0.50.
4. In addition, it has been observed that, in the experimental group, the erythrocyte sedimentation of 23, and hepatic function of 20 of the 93 patients returned to normal, while in the control group, there were only three patients with normalized erythrocytic sedimentation, and two patients with normalized hepatic function, out of the 30 control cases.

To sum up, these studies suggest that the Qigong therapy is helpful to some extent to ameliorating the symptoms, improving appetite, strengthening constitution, and increasing the ability of self-cure. Qigong can regulate the mind, heart, Qi, and blood so as to get rid of pessimism and eliminate evil factors. Therefore, it is really an effective, simple supplementary treatment with no side effects.

THE EFFECT OF EMITTED QI ON LEUKEMIA IN MICE

Feng Lida and Zhao Xiuzhen
China Immunology Research Center, Beijing, China

[This study by Feng Lida, MD, PhD shows that emitted Qi can decrease the reproduction rate of leukemia cells in mice and that infrasonic Qi simulators can play a similar role. From the 1988 FWCAEMQG proceedings.]

With the rapid development of modern science and technology and the enhancement of people's living standard, the constitutive proportion of diseases has changed and most infectious and parasitic diseases have been brought under control or eliminated, whereas, tumors are becoming a common problem and are endangering man's life and health. In our country, the number of patients suffering from tumor diseases is over 1,000,000 a year, and the number of patients who died from tumors has exceeded 800,000. Therefore, it is important for us to explore a new route to cure tumors.

Leukemia is a malignancy, which has a high incidence and is difficult to cure. As there are some similarities between leukemia in mice and human leukemia, we chose DBA mice as a research model to study the effect of the emitted Qi on L_{1210} cells of leukemia in mice.

The experiment chose DBA mice with a weight of 20±2 gm, and both male and female mice were used. In the experiment we killed the mice, which had been injected with the L_{1210} cells 7 to 9 days before we collected the celiac liquid and adjusted the concentration of cells to 4.70-31.00 million/ml (avg. concentration was 1.20 million/ml). 0.2 ml L_{1210} cells was injected i.p. into the abdominal cavity of mice. And after one day we randomly divided the mice into groups.

One Group Treated With Emitted Qi

Among these groups, the mice of the experimental group received the emitted Qi once per day, for between 10 and 40 minutes for 10 days, while in the control group, no treatment was given. After 10 days the mice were killed and the number of L_{1210} cells were counted with a light microscope. The average value in the control group was 200.435x0.5 million per mouse, while in the experimental group 66.458x0.5 million per mouse and there is significant meaning between the two groups. ($P<0.01$).

Second Group Treated With Infrasonic Qi Simulator

At the same time, we used an infrasonic qi



123 advanced cancer patients were treated for 6 months. The control group with drugs, the experiemental with drugs and Qigong exercises. The results show the value of Qigong exercises in cancer treatment.



Concentration of leukemia cells in mice after 10 days' treatment with emitted Qi and the infratonic Qi stimulators

simulator to stimulate the mice injected with the L_{1210} cells, once per day, two hours at a time for 10 days, after which the number of L_{1210} cells was observed. The number in the control group was 160.826x0.5 million per mouse, while in the experimental group 70.870x0.5 million per mouse. This difference is of statistical significance ($P<0.1$). The results showed that the number of L_{1210} cells which were injected into mice could be remarkably reduced after the mice received emitted Qi, and the fact suggested that the emitted Qi could kill or inhibit the L_{1210} cells in mice.

Qigong is a part of traditional Chinese medicine, which is a therapy with Chinese characteristics. In recent years, Qigong has been used to cure a lot of diseases, especially difficult diseases and tumor diseases. It is an important issue whether Qigong can kill or inhibit malignant tumor cells or not. The result of this experiment shows that the emitted Qi could kill or inhibit the L_{1210} cells of leukemia in mice. After a body received it many times, the emitted Qi could significantly reduce the number of L_{1210} cells in mice. The experimental study laid a theoretical basis for the treatment of tumors with Qigong. Qigong therapy will be a new way to cure carcinoma. However, the mechanism and way that the emitted Qi kills or inhibits L_{1210} cells of malignant tumor cells in mice needs to be further investigated.

EFFECTS OF QIGONG ON MALIGNANT TUMOR

Luo Sen, Tong Tianmin, et al.
Zhejing Institute of Traditional Chinese Medicine
Hangzhou Qigong Hospital, Hangzhou, China.

[This study, also from the 1988 FWCAEMQG proceedings shows the benefits of combining traditional and modern cancer therapies in maintaining healthy blood cells.]

Under observation in this experiment were 80 patients with 17 kinds of malignant tumors including nasopharyngeal carcinoma, breast cancer, lung cancer, and gastric carcinoma. Their diagnosis was confirmed by cytological and radiological examinations. Within this group, 48 were male and 32 female. Most of them had been operated on before hospitalization. They were at their I or II stage of the disease and had received radiation or chemotherapy before. These patients were randomly divided into three groups. 30 of them, as the first group, received Qigong treatment.

The second group, composed of 25 cases, were treated with routine chemotherapy. And the third group, another 25, received chemotherapy combined with Qigong exercises. The parameters adopted included WBC and RBC count, serum hemoglobin and platelet count in blood before and after treatment, T-lymphocyte conversion test (H3TdRLT) and urine excretion of 17-hydroxy steroids within 24 hours before and after the last week of Qigong therapy in some patients. The total period of observation lasted 60 days. Results are reported as follows:

1. Group I, the Qigong group, developed a significant rise in their WBC, RBC count and serum hemoglobin after treatment ($P<0.01$). Group II, treated with chemotherapy, presented a significant lowering in these measures ($P<0.01$). Group III, which both practiced Qigong and received chemotherapy, showed an obvious elevation of serum hemoglobin, RBC and platelet count ($P<0.005$-0.01). Their WBC remained at the same level as before the treatment ($P>0.05$)
2. T-lymphocyte conversion test in Group I also showed a significant rise ($P<0.05$). It was seen to be maintained at the original level in Group III ($P>0.05$).

This experiment proves that this kind of Qigong exercise, by exciting the circulation of Qi along meridians and modulating the functions of blood circulation, immune response and endocrine tissues, can minimize the toxic side-effects of chemotherapy and enhance energy supply to the body. This practice is effective in treatment of cancer and supported by confirmed scientific experiment.

EFFECTS OF PATIENT TUMORS ON KIRLIAN IMAGES OF HEALTHCARE PROVIDERS

Su Cheng Wu, Guangxi Tumor Hospital, Guangxi, China
Richard H. Lee, China Healthways Institute, USA

The process of emitting Qi during a Qigong treatment, while valuable at jump-starting a patient's recovery, is exhausting and requires extensive Qigong exercises to replenish the depleted Qi. However, as Qigong practitioners become more skilled, they can treat more patients with less depletion, probably through a combination of becoming more proficient at collecting Qi and more efficient at utilizing the Qi that they do have. This is an important field of study because of the prevalence of "burnout" which affects many practitioners in all the medical professions. Perhaps doctors and nurses can be taught the principles of efficient use of their Qi. The following is offered to illustrate this point:

The top two Kirlian photographs on this page show images of fingertips of healthy individuals and healers. The light recorded by the photos is created as electrons moving between the fingers and the film ionize air. In the first photo, the balls are created as electrons leaving the finger create pools of light. And the streamers are created as electrons stream back from the film to the finger. A balance between balls and streamers indicates that electrons move both to and from the fingers. The second photo shows that, around the fingers of healers, the electrons travel more as waves than particles, creating a smooth glow instead of balls and streamers.

In cancer patients, research has shown that balls appear around the cancer (not illustrated, reference Dumitrescu and Kenyon in "Electrographic Imaging in Medicine and Biology", 1983) and streamers appear around all other parts of the body, as shown in the fourth picture. (reference "Bioelectrography" by Konikewicz and Griff 1984 and Dumitrescu, 1983). This strongly suggests that the rapid growth of cancer cells is fueled by high electrical vitality at the cancer site, and that the rest of the body is devitalized as the high energy electrons are somehow attracted by the cancer.

The lower three Kirlian photos were taken in a tumor hospital. A typical cancer patient (the third photograph) shows virtually no Kirlian image. This indicates a very low flow of electrons, either in or out of the finger, and thus, low vitality. After increasing the patient's electrical conductivity using an Infratonic QGM on the foot (K-1), the patient's image brightened, but showed only streamers but no balls, as electrons shot to the fingers but did not return from the fingers to the film. Had high energy electrons returned to the film, we would have seen balls in addition to streamers in the photographs. This suggests that the entire patient, not just the photographed finger, is depleted in electrical vitality, and may be drawing electrical vitality from the Kirlian camera as high voltage electrons stream into the patient's body, but do not return to the film. This supports the common belief that cancer draws vitality from everything in the surrounding area while fueling the very rapid growth of the cancer cells.

Several doctors in the tumor hospital were photographed and those with patient contact showed a similar image dominated by streamers with almost no balls. This suggests that the doctors were in some way devitalized by the patients' low energy condition, and were, themselves, drawing electrical vitality from the camera. It appears that cancer drains the vitality of everyone, the patient, health care providers, family, and even those who visit to show their support.

Why does vitality flow to the cancer site? Qigong practitioners believe that intentionality moves Qi, which suggest that intentionality might be acting. We might suspect the intentionality of the patient, the family or the doctor. All seem to be convinced that the cancer will win. It seems that we should also look at the possibility that the cancer, itself, has intentionality, and is causing the patient to give up hope and the doctor to say things like, "You have no more than 3 to 6 months



Kirlian image of typical healthy person shows balance between balls and streamers.



Kirlian image of typical healer

Cancer patient shows low conductivity.



Cancer patient shows increased streamers after QGM treatment.



Doctor with patient contact also shows streamer dominance.



to live." Perhaps the fight against cancer is a battle of wills over the flow of vitality more than simply the biologically understood multiplication of ignorant cancer cells.

Can we reverse this flow of vitality, and will this reverse the growth of cancer? The preceding research in this chapter shows that Qigong practice and emitted Qi can kill and decrease the growth rate of cancer. Perhaps intentionality is a new weapon against cancer. And maybe the Kirlian camera will be the biofeedback technique which shows patients and researchers when their intentionality is properly applied and when they are winning the battle.

As is concluded in most research studies, "More research is necessary."

CHAOS AND CONSCIOUSNESS

The study of Qi as the relationship between the physical world and consciousness is often avoided by scientists because this violates a basic tenet of science, the experimental method, that the experimenter is not to interfere with the experiment. However, this appears to be exactly what Qigong masters are doing. Whereas religious groups have long held that our thoughts, wishes, desires, and prayers can influence our own lives and the lives of those around us, the scientific world has, for the most part, denied this possibility.

If, in our study of Qigong, we discount the conscious intent of the practitioner, we are ignoring what Qigong practitioners claim is the vital ingredient, intentionality. Thus, we are led to study the physics of the phenomenon, the interaction of electric, magnetic, and acoustical fields. However, if we allow intentionality to enter the equation, a very different view of Qigong emerges with enormous implications.

To accept that consciousness can influence the physical world, science needs some sort of field or substance which can be shaped by consciousness such as the rhythmic movement of electrical charges in the body as measured by EEG, which is shown to be influenced by Qigong masters.

From a broader perspective, this field is chaos, which might be described as uncertainty regarding the future, or instability such that subtle influences can guide the field's reorganization. In the case of EEG, the chaos is the available instability of free electrons, molecular ions, and neurochemicals. There are probably many other forms of chaos within the body including magnetic, acoustical, and electromagnetic. It is chaos, or uncertainty in these fields, which allows consciousness to enter and shape reality.

Qigong therapy is often broken into three phases. First, the practitioner "adds Qi" increasing the available energy, or chaos of the patient. Then he "sweeps the bad Qi out the feet" to remove crystallized structures which are interfering with the patient's health. Finally, he "smooths the Qi" to help bring order out of the chaotic state which results from the adding of chaos and removing of "bad Qi."

Thus, a Qigong treatment might be viewed as adding chaos to liquefy a crystallized structure, removing undesired, loosened crystals, then smoothing and harmonizing the field to "bring a higher order out of the chaos." Softening and bending metal, altering EEG in anesthetized animals, and accelerating recovery from cancer might all be explainable by "consciousness creating and guiding chaos."

LOW DIMENSIONAL CHAOS IN PRACTICING QIGONG

Yagu Lin, Jijun Gao, and Huo Lu
Shanghai Qigong Research

[In our research at CHI, we have found that chaos is a key ingredient in the effectiveness of a therapeutic signal, allowing greater penetration into the body. This Chinese chaos research shows that Qigong exercises result in reduced complexity of the EEG in the brain, providing calmness and mental clarity (bringing order out of chaos). From the FWCAEMQ.]



Fig. 7.20 *Thrusting Channel*

Recently, researchers such as Kaczmark, I.K. (1977), Nicolis, G. (1985), Skarda, C.A. and Freeman, W.J. (1987), and Xu Jinghua and Xu Nan (1987) have reported the systematic complexity and chaos of the brain electroencephalographic techniques (EEG) by the analysis of dimensionality in studies of chaotic dynamics of biological systems. However, there are few reports analyzing the Qigong functional state using this method.

In this paper, we analyze change in attractor dimensionality d values of the occipital EEG before, during, and after Qigong exercises. The results show that before exercises, d=1.8, during exercises d increases to 2.1, and after Qigong exercise, it remains at the increased value of 2.1. These results show that Qigong exercises can lower the complexity under conscious conditions, increase the orderliness, and decrease the randomness. This may explain Qigong's effect of "warding off distraction, thoughts, or evils," and may be a principal mechanism of Qigong's effectiveness.

QIGONG TRAINING AND COHERENCE OF EEG

Yang Sihuan, Yang Qinfei, Shi Jiming, Cao Yi
Institute of Qigong Science,
Beijing College of Traditional Chinese Medicine,
100029, Beijing, China

[This study shows that Qigong training increases coherence between the right and left sides of the brain. From the perspective of chaos theory, this means that Qigong helps to bring "order out of chaos" in the brains of practitioners. From Second World Conference on Academic Exchange of Medical Qigong.]

In this study, we analysed the coherence of EEG to observe the trainees' EEG regularly. The young students, who were 17 to 20 years old, had been practicing "Zhanzhuang Gong" for one year. We try to find out the effects of the Qigong training period on coherence of EEG. Thirty two persons in the Qigong group and 35 persons in the control group were involved in this experiment. During one year period of observation the subjects of the Qigong group practiced Qigong for 40 minutes every day. The EEGs of the Qigong group were analysed every half year in meditation, and the EEGs were also recorded before learning Qigong. The students in the control group did not take part in the Qigong training and their EEGs were investigated at rest twice with an interval of one year. In the test, eight channels of EEGs were simultaneously processed by a computer on line for 20 minutes. The program, "computer evaluation system for the Qigong state" was provided by the "Laboratory of Bio-Control, Department of Electrical Engineering, Zhejiang University".

After one year of Qigong training, total coherence between the left and right frontal regions increased from 0.84±0.07 to 0.87±0.06 ($p<0.05$). Before Qigong training, the total coherence between the left and right occipital areas was 0.68±0.14. After half year's training, it increased to 0.79±0.10, and after a year's training, it was 0.76±0.10. Self comparison showed the probability $p<0.001$. The total coherence between the left and right temporal areas before Qigong training was 0.48±0.17. Half year after Qigong training it was 0.55±0.13, compared with that before Qigong training ($p<0.05$). One year after Qigong training it was 0.64±0.12. Comparing before and a half year after Qigong training $p<0.001$.

Total coherence did not change significantly in the control group

VIBRATIONAL TREMBLING, CHAOS, AND EEG

Dale M. Patterson, MS, CACB, BCIA Certified
Richard H. Lee, China Healthways Institute, USA

[This article, published in China Healthways Newsletter, provides data collected from biofeedback research conducted by Dale Patterson which shows that chaos increases alpha EEG induction.]

Vibrational trembling appears to be a way memory is stored or processed in the physical body. Chaotic sound penetrates this field of vibrational activity, softening this memory and allowing us to more easily let go of fixated thoughts, addictive desires, and compulsive actions.

When someone is full of anger at being blocked from acquiring the object of desire, he may tremble extensively in the theta range of EEG. And when someone is overloaded with the stress of excess thinking (worry) and approaching a nervous breakdown, he will also tremble, but this time in the beta range. This excess vibrational activity consumes the body's Qi and causes the person to become emotionally, mentally, and physically rigid.

Applying chaotic sound breaks up these repeating patterns, often freeing the patient from frustration and worry. As the patient relaxes, capacity to process thoughts and emotions increases, new answers are found, and the increased freedom and flexibility are experienced as increased vitality. Thus, where physical memory inhibits healing, adding a chaotic alpha signal can accelerate recovery.

LABORATORY TESTING

Dale Patterson, a board certified EEG technician trained in biofeedback became intrigued with the QGM when one of his patients brought one in. He recorded EEG brain maps first with an early model of the QGM which produced a clinically significant 18% increase in Alpha. He then used the Q4 with chaos which provided eight times the increase in alpha activity, showing that chaos increases induction of alpha rhythm in the EEG.



CHAOS AND THE COLLEGE ENTRANCE EXAM

Su Cheng Wu, Guangxi Medical Hospital

[From China Healthways Newsletter: A medical researcher applied the Infratonic QGM to high school students preparing for the college entrance examination.]

There was little chance that Li Wen Chao could ever attend college. As a high school senior, he had achieved only moderate grades in his courses and had done poorly on previous national examinations. Without very high scores in the China College Entrance Examination, Li would almost certainly spend his life in a menial factory or farming job. The College Entrance Examination is terrifying, because everyone who faces it knows that only half of high school graduates will enter the nation's college system. *Failure in this examination is a common cause of suicide in China.*

Enter Su Cheng Wu, a medical researcher and Li's uncle. He had just completed a successful study involving infrasonic treatment of bronchial asthma (see page 28) and was searching for other subjects to study. He felt that stress, nervousness, and mental overload were the principal reasons that high school seniors failed the examination, and believed that the Infratonic QGM would induce the deep calmness and mental clarity of Alpha into the students' minds and bodies, helping them to relax and overcome the mental overload that causes brains to lock up during tests.

For three days before the examination, Dr. Su went to visit his nephew's class and treated each patient by holding the machine on the upper back for five minutes and encouraging the student to talk about fears and tensions regarding the upcoming test. For students suffering from symptoms such as headaches, dizziness, poor appetite, insomnia, and menstrual pain, he instead selected and treated an appropriate point, usually along the front midline of the body.

The results of this small test drew much attention. Li's class was average among the seven senior classes, yet performed the best by far. Whereas the average pass rate for the other six senior classes was 50%, 86% of the students in this class passed the examination and were placed in five year colleges! The other 14% got high enough scores that they were accepted to three year trade schools. Thus, 100% made it to some sort of college. Li Wen Chao enrolled the next year at Guangxi Medical University to become a physician.

While it sounds unreasonable that a little chaotic infrasonic sound can cause such a large increase in scores, the opposing view makes more sense. *Stress and worry can shut down the thinking process.*

SEARCHING FOR JING, QI, AND SHEN IN WESTERN SCIENCE

Traditional Chinese medicine (TCM) holds that three "vital treasures", Jing, Qi, and Shen, are real substances which envelop the human body and are essential to life and healing. These are the fields through which Qigong masters work. Jing provides the genetic structure or the physical strength of the body. Qi is the life or vitality of the body, our energy level. And Shen provides the mind, or conscious aspect. TCM goes further, introducing three seeds of consciousness, the lower, middle and upper Dan Tians located in the lower abdomen, chest, and above the head respectively, which are born and mature through cultivation, providing awareness of the physical world through Jing, Qi, and Shen.

This parallels the writings of Alice Bailey which present a three fold personality: the etheric body (Jing) is shaped by the emotional body (Qi) which, in turn, is shaped by the mental body (Shen). The substance of each body is produced by the physical body whereas the function of each body is to support a mode of consciousness.

In "A New Science of Life" by Rupert Sheldrake a "morphogenetic field" is described as a vibrational field which surrounds and shapes living things as they organize. He argues that our genetic structure doesn't contain, but rather tunes into the blueprint of the physical body through this morphogenetic field. He supports this with laboratory findings that as more and more animals and humans are taught a new behavior, others of similar genetic makeup but physically separated from the first, learn the new behavior more and more quickly. Jing appears to be the TCM equivalent to the morphogenetic field of the physical body. Qi and Shen might also support morphogenetic fields of their own. According to Sheldrake, these morphogenetic fields are programmable, obtaining their initial programming from genetic structure, and being reprogrammed through experience and learning.

Jing, from the standpoint of physics, might be a field of electrons in constant flux suspended in salt water throughout our bodies. The rhythmic movement of this electric field is measurable by EEG, EMG, and EKG. Electrostatic forces are very strong and it is conceivable that such a field can shape a physical body by catalyzing certain chemical reactions and moving certain molecules to the right place at the right time, causing, for example, differentiation between liver cells and brain cells in the embryo.

If Jing is to vibrate freely it requires sufficient energy to have free flowing electrical charges both to resonate with the morphogenetic field and to fuel biochemical reactions. Ilya Prigogine, in "Order Out of Chaos", proposes that life requires chaos, that higher forms of organization emerge out of chaos, and that raising the energy of a system allows it to reconfigure into a higher order of organization. From the standpoint of Jing, when biochemical activity exhausts the available electrochemical potential, chaos in the field of electrons has been exhausted. Then the physical body may become unresponsive, and illness may result. Research during long airline flights shows that, where crowding and recirculated cabin air reduce the availability of electrical energy in the air, people become depleted and develop exhaustion and succeptibility to illness and infection. When passengers wear portable air ionizers, which add electrical instability (chaos) to the air by ionizing it, they do not suffer from exhaustion and avoid illnesses from airborne bacteria. From the standpoint of physics, Jing might be the available electrical instability or chaos in the sea of electrons in the body.

Qi might be a field of magnetic substance which can be measured because it makes the body more electrically conductive. Such diagnostic equipment as Ryodoraku and EAV are claimed to measure the Qi by measuring the electrical conductivity of meridians. High and balanced conductivity are associated with good health and vitality, and low or imbalanced conductivity is associated with illness and debility. While the Qi may have little direct influence on the physical body, its ability to increase local electrical conductivity gives it the ability to provide selective pathways of decreased resistance which allows it to influence the flow of electrons, and thus, shape the Jing. Electrically conductive needles may give acupuncturists a similar ability.

Analysis with Kirlian photography shows that washing the hands with tap water causes the electrical conductivity of the hand to decrease considerably. However, when the hands are washed with the same water which is first passed through a strong magnetic field, the electrical conductivity of the hands increases. (ref: Bioelectric Vitality — The Science of Human Energy by Lee) This tells us, first, that water can store and transport some sort of magnetic substance, and second, that this substance can be removed from or added to the human body. To illustrate this, Kirlian research on long jet flights reveals that reduced magnetic fields on airliners often cause those who have a TCM condition called Yin deficiency to have severe exacerbations of symptoms such as anxiety, nausea, headaches, dizziness, and rising heat. Placing a magnet on the body during the flight provides a source for magnetic substance and reduces the symptoms considerably. Qi might be describable by physics as available magnetic activity within the body, though there appears to be much about magnetism that physics doesn't yet know.

Shen is described in traditional literature as mind or awareness, and often as light. If it is light, why can't we see it? Modern physics tells us that an electron is really an electromagnetic wave, an x-ray, high energy light which has been somehow captured by the nucleus of an atom. Thus, it is conceivable that a field of light or electromagnetic energy could resonate around our physical bodies and remain unmeasurable, just as electrons orbit around a nucleus undetected.

Shen may become visible when excited by electricity. Most people have Kirlian images which show small balls of light surrounding the finger during the negative pulse and streamers, lines of light perpendicular to the finger surface, during the positive pulse. However, healers and artists who use their hands with enhanced awareness, often have a smooth glow around their fingers. (Kirlian photos of the balls and streamers and smooth glow are shown on page 58.) Some even have certain fingers with a smooth glow while others show the balls and streamers. It appears that only those fingers used intelligently have the glow. For instance, a person who principally uses three fingers for massage will find that those three will have the glow while the others have the balls and streamers. The fact that electrons act differently around a healer's fingers is a big opportunity for physicists to investigate the nature of Shen, and to give us a better understanding of the special function abilities of Qigong masters and other healers.

CONCLUSION

Jing, Qi, and Shen are measurable with physical equipment, and thus are subject to scientific study. These measurements correlate with states of health and rates of healing. Thus monitoring the strength of these fields in hospitalized patients and supplementing them when low may prove of value in reducing recovery time and saving lives. In addition to studying, monitoring and supplementing these fields, it might also be productive to study how to increase a patient's resonance with his own morphogenetic field while decreasing his resonance with that of a disease process. This may be a principal area where Qigong masters and other healers excel, while western medicine has little knowledge. Jing, Qi, and Shen, long considered nothing more than useful metaphors by western scientists, may be very real substances which unlock the door for western scientists to understand human vitality.

THE ROLE OF CHAOS IN DISEASE AND HEALING

Richard H. Lee, China Healthways Institute

In the book, "Order Out of Chaos," Ilya Prigogine offers that, when a structured system is energized, its chaos increases, allowing it to reconfigure spontaneously into a higher order of organization. This may explain the evolutionary progression on Earth from the simple structures to the highly organized life forms, from the helpless child to the capable adult who chooses to serve a yet higher organization, humanity.

How can chaos be healing? Chaos is often thought of as unpredictable and destabilizing. It is the enemy of structure and overturns the law of the land. How is it possible that chaos can be harnessed to serve us? As an example: When someone's life is not working, when the basic order upon which they depend is failing them, and when they just want to run away, it may be time to "let go of life" in a way that nurtures the creation of a new order within which the world again makes sense.

Chaos is opportunity. Where there is rigid organization, there is little opportunity for restructuring. The best solutions often go ignored because their implementation would require destruction of some of the structure which holds an organization together. An organization which is flexible, receptive to new ideas, and free to adjust to changing circumstances, is willing to break down old structures for the sake of growth and efficiency. Structure provides for certainty. Chaos injects uncertainty. With a high degree of chaos, an organization can quickly adapt to strange and unfamiliar circumstances without being held back by the inertia of structure.

Within the human body, there is a great deal of structure. Physically we can have unnecessary chronic muscle tension, purposeless lumps, and other structures which don't serve us. Emotionally, we can hold onto desires which repeatedly carry us down pathways of misery. Mentally, we can so fill ourselves with conflicting thoughts that we are unable to sleep and on the edge of nervous breakdown. Whenever a structure within us becomes inflexible, we experience pain. Blocked desire provides emotional pain, and conflicting world views cause mental pain. Flexibility allows us to face the unexpected with capability and enthusiasm. We can run from the path of an approaching car, or stop to pick up a dime. We can eat a bowl of bean sprouts and tofu as comfortably as a hamburger, attend a religious service of any denomination without concern for the clothing of our creator, and be comfortable considering philosophies of strict child rearing alongside newsletters promoting chaos.

Random, unexpected events provide the chaos which exposes our rigidity, our unyielding habits, our crystallized beliefs. Sometimes these crystallized structures within us yield to the pressure but often they resist, sustaining the old ways despite conflicting forces and pain. And sometimes the strain even becomes so great that a person's entire world view shatters. This can be a hugely transformative event:

The initial stress is experienced as pain, uncertainty, or fear of the unknown. We become desperate to avoid further stressing of the crystallized structure so we hang on even tighter. Then the order governing our emotions and thoughts snaps, pops, or shatters. We burst into tears and watch as our life falls to shambles before our eyes, with seemingly nothing left for us to hang onto. We may feel an abrupt shift. Perhaps we experience an immediate release or an exhilarating feeling of freedom and relaxation. At other times, we find ourselves drowning in the unknown, trying to hang onto the structure which just crumbled, unwilling to relax and trust that a new better structure will form in its place. Sometimes we spend years trying to hang onto a crumbled, useless, and painful structure.

Chaos is an opportunity to restructure our beliefs, habits, and physical bodies into a more flexible arrangement, more suitable to the unknown but anticipated future. Whenever we face a new situation, we have this opportunity. Every time we make a new choice or break an old habit, we increase our flexibility and expand our opportunities.

How do we nurture chaos? We start by looking for patterns which restrict our choices, consume our resources, and limit our beliefs. Watching TV, smoking, recounting past experiences or gossip, consuming countless grams of animal fats and alcohol, spending endless hours or repetition in a job or relationship. Changing these patterns may be quite painful because of deep and extensive crystallization, but the result will almost certainly be free time, vitality, new experiences, and an opportunity to make less restricted new choices. While choices made in anger are easiest, and often create more chaos, choices made with love usually provide a greater opportunity for growth. If shattering and reorganization occur within the emotion of anger, the new order will embody anger. If we immediately forgive and "love our enemy", the new order within us will embody love and harmony.

THERAPEUTIC CHAOS

Richard H. Lee, China Healthways Institute

[This article describes how chaotic infrasonic sound might work to penetrate the body, break up stagnation and accelerate healing.]

Over the past ten years CHI has been studying the Infratonic QGM, trying to determine why it is effective at accelerating recovery and decreasing pain. Until recently, our focus has been on the broad spectrum frequency band of infrasonic sound produced by the QGM which infuses the local area, facilitating nerves and inducing Alpha brainwave activity, facilitating nerve transmission between the brain and the local site of pain. This is a plausible mechanism, but there appears to be more to it.

As we experimented chaos surfaced as an "active ingredient." We built prototypes with advanced microprocessor technology which produced an almost purely chaotic signal. In testing we found that these new units penetrated more deeply and stimulated resistant areas of the body which other therapies could not penetrate.

It appears that our thoughts and emotions are strongly affected by sound, and that the body defends itself against outside vibrational signals by anticipating and setting up signals which cancel them out. This may be why someone speaks loudly when he wants to persuade us of an idea, and why we may shout back to defend our own position, and why it is difficult to read or think clearly while sitting in a noisy park in a big city, or in a windstorm, or with loud music playing. It seems that it is difficult to sustain one's own complex thoughts when noise is jumbling them.

Many of the emotions and thoughts we hold within us can be the cause of chronic illness, pain, and slow healing. We might even be carrying some of these patterns from childhood, or pick them up from chance encounters or spooky movies. Like a computer virus, they are lurking among thoughts and beliefs which make up our personality. Those emotions and thoughts which are causing health problems are part of what Qigong therapists call "bad Qi."

Our ability to filter out recognizable sounds, while allowing us to maintain our own thoughts and emotions, is a major barrier to the effectiveness of therapy devices like TENS, ultrasound, and massagers. If we receive a therapeutic treatment from such a device, it may provide some relief but will only affect those surface vibrational patterns which are ready to let go. Thus many therapy devices relax muscles to some degree. But as soon as the therapy begins to intrude on dominant beliefs or emotions we automatically identify the invading signal and filter it out. Thus, predictable therapeutic signals can only do so much.

While we can defend against rhythmic signals, our old attitudes and emotions are defenseless against the random sound of a chaos therapy device because it is unpredictable. It simply goes past our vibrational defenses and softens all thoughts and emotions in the target frequency range. This may be why, after a treatment, people feel calm, clear thinking, and liberated from the problems and worries of life. A big part of what they are feeling may be the abundance of energy which is released when old unnecessary thought and emotion patterns dissolve, releasing the Qi, the substance that was vibrating to maintain them.

It is not just "bad Qi" that is softened by chaotic infrasonic sound. All structures, thoughts and emotions, may be softened as acoustical chaos increases in the body. Since accelerated healing of broken bones and sprained tendons is often reported, chaotic sound may soften these solid physical structures as well. This parallels the first step in Qigong therapy, emitting Qi to soften and liquefy the stagnant Qi.

The second step is to sweep "bad Qi" downward and out the feet. This may be a process of removing old vibrational structures which have been freed to move but have not entirely dissolved. Therapists have found that using chaotic infrasonic sound to sweep from the area of pain down the body and out the feet after treating the pain is often more effective than treating the point of pain alone.

The third step in Qigong therapy is to create a nurturing Qi field to allow the remaining Qi to harmonize, nurturing the emergence of a new order out of the chaos. The Infratonic QGM helps to do this by infusing the body with alpha EEG activity. Whereas the theta rhythm is associated with our individual identity and our relationship with the physical world (and our sense of ego and self importance), and the beta rhythm is associated with planning and thinking (stress and worry), alpha is all about relationships, putting the group before the individual. This may be why, after a QGM treatment, patients become more "compliant" in a doctor's office and people find that interpersonal conflicts are easier to resolve. This process may also occur on the cellular level toward healing and disease resolution as "bad Qi" is removed and the body's cells and organs can reorganize along the lines of teamwork and harmony.

Qigong therapy can be understood in terms of chaos theory. As we let go of old structure, we have an increase of chaotic or undefined energy, which then can transform into a higher order of organization which handles all previous requirements in a new way and has left over capacity for new endeavors.

IMPLICATIONS OF SCIENTIFIC QIGONG RESEARCH

The findings of the scientific research into human vitality have implications in broad areas of science and medicine.

1. Emitted Qi has strong measurable effects in health, healing, physiology and mental functioning. The presented research will encourage scientists around the world to seek deeper understanding of this phenomenon.
2. As human vitality becomes better understood, both in terms of measurable fields which surround the body, and chaos and consciousness, it will be integrated into the American health care system. Monitoring and treating patients accordingly will significantly improve recovery rates and shorten hospital stays.
3. Qigong exercises are effective tools for the individual to cultivate rapid healing and vitality. In addition, many who overcome chronic illness through Qigong practice will develop the ability to help treat others through the emitted Qi.
4. For those who are caught in the frenzied thinking of busy city life, practice of Qigong and other forms of concentration and meditation exercises is an answer. Qigong simulators help to get people started in their relax-

ation and Qigong exercises by relieving pain, promoting deep relaxation and mental clarity, and providing evidence that the phenomenon is real.

5. As the principles of human vitality are accepted in families, children will learn that their feelings of energy flowing through their bodies are normal, and that their awareness of these feelings is valuable. Just as children quickly learn the language that their parents speak, these children will learn to understand and use Qi if their parents accept and discuss it.

The Chinese scientific investigations into Qigong establish the phenomenon of emitted Qi as a real and fertile area of scientific study. Qigong teaching centers and Qigong simulation devices are already making a difference. Further studies into the nature of human vitality and inventions coming out of this ongoing research will do much to shape the 21st century.

APPENDIX 3

INTRODUCTION

This third Appendix includes research information on the physiological and energetic mechanisms triggered within the body, when stimulated through Medical Qigong therapy, Taijiquan or Yoga. This information was collected by my good friend Roger Jahnke, OMD, Director of the Qigong Department at the Santa Barbara College of Oriental Medicine, Santa Barbara, California. Mr. Jahnke is a doctor of Acupuncture and Oriental Medicine, and has studied extensively in China and abroad, learning Traditional Chinese Medicine and refining his clinical ability since 1967.

Doctor Jahnke is also the Director of the Health Action Clinic in Santa Barbara, California, and was one of the founding Board members of the National Qigong Association. He has written a Medical Qigong book entitled, "The Healer Within: Using Traditional Chinese Techniques to Release Your Body's Own Medicine."

This third Appendix is a continuation of the research devoted to the scientific approach of analyzing and scrutinizing the claims made as to the actual effectiveness of Medical Qigong Therapy as a clinical modality. The result on the effectiveness of Medical Qigong Therapy as a solid and effective clinical modality being positive in conclusion.

The following information in this third appendix represents but a fraction of Dr. Jahnke's findings, however, I am confident that the reader will find the data fascinating.

Dr. Jerry Alan Johnson May 2000

Chapter 8

Belt Channels

Theory of the Belt Channel

The Belt Channel is a psychic channel of power and self-defense, encircling the body with energy. It protects the body and fences the energy within the Governor, Functional and Thrusting Channels, while warding off negative energy from the outside world. Starting at the navel each Chi center of the body is crossed and encircled by one level of the continuing Belt Channel.

A cross-section at the navel level would show the Belt Channel connecting to the other channels you have learned to this point. At the front of the body, the Belt Channel connects with the Functional Channel. As it moves to the left side it connects with the Left Thrusting Channel. At the Door of Life in the back, it connects with the Governor Channel. To the right it connects with the Right Thrusting Channel. Returning to the front, the circle is completed.

When you learn to form a pearl practicing Fusion of the Five Elements, and you draw the energy from the front, back and side pakuas at the level of the navel, you are laying the groundwork for the Belt Channels.

Procedure of Forming the Belt Channel

The Belt Channel begins at the navel and spirals upward in a counterclockwise direction through solar plexus, heart, throat, mideyebrow, and crown. Then, reverse the energy flow and circle the pearl clockwise as you move down through the above points to the navel. From the navel continue down to the sexual center, perineum, knees (around both knees), and soles of the feet (slightly into the ground). Finally, reverse the direction and work up through each point back to the navel.

THE PSYCHOLOGICAL AND ENERGETIC MECHANISMS TRIGGERED IN THE HUMAN SYSTEM BY THE SELF-APPLIED HEALTH ENHANCEMENT METHODS QIGONG, TAIJI, AND YOGA

Roger Jahnke, OMD
Director of the Qigong Department
Santa Barbara College of Oriental Medicine

Western science has very clearly delineated numerous physiological systems: the digestive system, the nervous system, the cardiac system, etc. However, what might be called the "healing system" has not been discussed or clearly defined until recently. Medicine has uncovered many of the pathological processes that occur within the recognized systems and defined clinical strategies for their resolution. Strategies for enhancing the "healing system," however, have not been addressed by conventional science or medicine.

Numerous cultures, typically considered to be scientifically unsophisticated, actually noted and described the "healing system" long ago. The Chinese in traditional Chinese medicine, and the Asian Indians in Ayurvedic medicine, simultaneously developed elaborate theories of the function of the "healing system," and over thousands of years refined strategies for enhancing its function to produce a remarkable endogenous resource for self-repair. This internally generated healing resource is called an "inner elixir," literally a medicine produced within the human system.

In addition to specific clinical methods such as acupuncture, herbal therapies and tissue manipulation (massage and articular adjustment), these ancient cultures also created comprehensive health enhancement and self-healing systems to assist people in improving their own capacity to heal. Collectively such methods have been called the self-applied health enhancement methods (SAHEM). 1 Typically SAHEM includes breath practice, relaxation and regulation of the mind and nervous system through meditation, purposeful adjustment of the body posture with gentle movements and self-applied massage.

Qigong (also Chi Kung) from China and Yoga from India are ancient methodologies developed and refined over thousands of years specifically for sustaining and enhancing the "healing system." Qigong and Yoga, while they are historically based on the cultivation of factors unknown to the West (China—Qi and India—Prana), actually have specific effects on well known physiological mechanisms that are fully understood by Western science.

While there are many subtle aspects of human physiology that are triggered or accelerated by the practice of the SAHEM (including an emerging new understanding of "energetics," "bio-energetics" or "the electro-physiological system) the following three areas of conventional physiology make up a major portion of the physiological function of the "healing system" and are enhanced by the practice of the SAHEM.

1. Oxygen Delivery
2. Lymph Generation and Propulsion
3. Brain and Neurological Activity

The following sections will address each of these aspects. Other important mechanisms effected by the SAHEM including co-enzymes, antioxidants, connective tissue, precursor hierarchies, stem cell morphology , etc. do not fall into the scope of this paper and their discussion must be held for the future. The domain of subtle energy based mechanisms for the SAHEM effect will be explored briefly in conclusion.

OXYGEN

The Chinese knew about the circulation of the blood approximately 2000 years before William

Harvey described it in 1616 (Temple and Needham, 1986; Veith, 1972)). They knew about the energy generating relationship of food and air 2300 years before the elaboration of the oxidation feature of the Krebs cycle. The simplicity of the ancient Chinese formula for metabolic activity, understandable even by children, encourages wise use breath and food as health enhancing factors This is how Chinese grandmothers have passed health wisdom to children. Note that such simple wisdom is uncommon in the grandmothers of scientific cultures today.

It is often asked what difference there is between Qigong, Yoga (or other mild SAHEM) and the more vigorous conventional fitness methods like running, lifting weights, power biking and aerobic exercise. One way to discuss this is to trace the oxidation and energy cycle. In both aggressive, vigorous exercise and mild exercise the body naturally produces a powerful mix of metabolic resources. In vigorous exercise this is typically called a fuel. In the mild fitness systems of ancient cultures this inner resource has historically been called a medicine, or an elixir.

In vigorous exercise this oxygen induced resource is spent as fuel for hungry muscles. In the milder forms of SAHEM this resource is not completely spent, instead it is circulated internally and utilized as an internal reserve of self-repair factors to sustain and heal the tissues, organs and glands. At the advanced levels of Qigong this endogenous medicine is believed to be transformed into an elixir of longevity and wisdom.

Increased oxygen availability from practice of SAHEM has three potential effects, it:

1. supports energy (ATP, AMP, ADP) generation.
2. generates water as a by product of energy metabolism.
3. enhances immune function.

ENERGY GENERATION

The energy necessary for cellular processes and body heat regulation is supplied through the reaction of oxygen and glucose, in the presence of adenosine triphosphate (ATP). The combination of oxygen from air and sugar from food is catalyzed by ATP releasing chemical energy (ergs) which accomplishes all cellular processes. ATP is the basic energy storage and energy transfer molecule in the body.

The oxygen carrying capacity of the blood and the energy catalyzing ability of ATP are critical factors in the ability of the human organism to sustain a high level of vitality. This suggests that oxygen and ATP may be related to what the Chinese call "Qi" and what the Asian Indians call "Prana," the vital force or life energy. Chinese medicine distinguishes several aspects of Qi. Zhen Qi (Genuine, True or Normal Energy) is the basic dynamic force of all vital function. Ying Qi (Nutrient Energy) is the dynamic force which fuels cellular work (Kaptchuk, 1983). The interaction of oxygen, nutrients and ATP is apparently a physiological process that is a direct correlate of one particular aspect (there are many) of the activity of the Qi.

In Chinese research it was observed that blood levels of ATP increase with practices which cultivate Qi (Wang, 1988). When the mysterious practice of Qi emission (projecting Qi) was performed, the practitioner's ATP levels decreased significantly. Emission of Qi results in a decrease in stored ATP (or potential energy) as recognized by Western physiological science.

The SAHEM activate the body's energy metabolism cycle. The Chinese call this the "cycle of the transformation of energy" (Jahnke, 1989). In the West it is called the Krebs cycle, and has been nicknamed the "bioenergetic cycle."

In the West, ancient medicine is generally characterized as unscientific, superstitious or even primitive. Therefore, the Chinese "formula" for the transformation of energy (Qi) seems overly simplified:

Gu Qi + Kong (Qing) Qi = Zhen Qi

or energy of food + energy of air = essential body energy

Gu Qi (grain Qi, or food Qi) is the essence or life force of food. It mixes with Kong Qi (Kaptchuck, 1983) or Qing Qi (Kendall, 1989) (natural air Qi), the essence or life force of air to form Zhen Qi (Genuine, True or Normal Qi)) which is the life force of the body (Veith, 1972;

Kaptchuck, 1983; Kendall, 1989).

However, it is this same basic formula, hidden in the complex vocabulary of Western science, that is used in modern physiology:

$$6O_2 + C_6H_{12}O_6 = ATP = ergs + 6CO_2 + 6H_2O$$

air + glucose = catalyst = energy + carbon dioxide + water

It seems that the Chinese knew, without a particularly refined scientific method, that only a portion of the air and food, the Qi or essence, was employed in the process. In fact only 21% of air is oxygen and glucose is approximately 60% of food. (Guyton, 1992)

Science has been exploring energies, beyond metabolic energy (ergs), within the human system including the migration of ions, the ionic gates in cell membranes, the ionic discharge along neurological pathways and the electrical discharge that causes the beating of the heart. The overall understanding of body energetics will increase significantly as science explores the extent to which Qi is linked to these known physio-energetic mechanisms. The interaction of oxygen, glucose and ATP is likely only one energetic aspect of the beneficial effects of Qigong and other SAHEM.

WATER PRODUCTION

A second critical benefit of increased oxygen metabolism is linked to the cellular production of water as a by-product of the energy production cycle noted above. (Shields, 1989) This water is incorporated in interstitial fluid, lymph, blood serum, cerebrospinal fluid, synovial fluid, tears, sweat, etc.

Coincidentally, the energy which fuels the work of the cells as well as much of the water which contributes to the lymphatic fluid and other body fluids have the same source: metabolism. Metabolism is gently increased by all of the SAHEM. In addition, while the metabolic production of ergs also produces water, it is also interstitial water that has been found to conduct the physiologic flow of ions internally.

The benefits of the practice of health enhancement and self-healing methods upon the water component of the endogenous self-repair resource will be further explored in the section below on the lymphatic system. The bionic conductance will be explored briefly under energetic mechanisms.

IMMUNE FUNCTION

ATP drives the activity of every cell. Immune function as well as the production of immune resources (white blood cells, lymphocytes, T-cells, killer cells, etc.) are dependent on oxygen availability. It has been shown that exercise can mobilize the effect of natural killer (NK) cells. (Pedersen, 1988) However, in individuals who exercise so vigorously that they exceed the aerobic level and cross the anaerobic threshold, immune function is actually decreased (Brahmi, 1985; Fehr, 1989).

The scientific evidence is strong on two points: 1) oxygen deficiency leads to decreased immune function and 2) moderate amounts of mild exercise increase immune function.

In his research, Nobel Prize recipient Otto Warburg found that oxygen deficiency was typically supportive of cancer cell proliferation (Warburg, 1966). There are numerous studies that associate reduced lung volume and oxygen exchange capacity with increased mortality and reduced resistance to disease (Gordon, 1970; Cullen, 1983). In studies with elders, immunodeficiency was found to be one consequence of reduced oxygen metabolism. (Saltzman, 1987).

Oxygen's effect on immune function was demonstrated in a German study. It was found that in elderly injured, stressed and hospitalized individuals the arterial oxygen content is often reduced from normal levels. Administration of oxygen was found to elevate the arterial oxygen content and increase recovery rates. Interestingly, the experimental addition of germanium to the treatment protocol in the study further accelerated the healing process (Liem, 1985). Germanium is known to accelerate oxygen metabolism.

These mechanisms associated with oxygen's role in the endogenous "healing system," are naturally occurring and optimal in healthy individuals. One or several of these mechanisms may be deficient in individuals who are ill or at risk for disease. These mechanisms are all enhanced by the gentle movement, focused breath practice and relaxation that occur in the practice of Qigong, Yoga and other SAHEM.

LYMPH SYSTEM FUNCTION

The lymphatic system has been largely neglected in the conventional Western scientific tradition. Contrasted with cardiac function, for example, the lymph function is relatively unexplored. Perhaps, because lymph and lymph vessels are generally translucent, they drew little attention in early anatomical study compared to organs, blood vessels, muscles and bones.

Hippocrates and Aristotle referred to "white blood" and "colorless fluid." In the Middle Ages medical knowledge declined and the lymph was temporarily forgotten. Not until 1627 did Asellius, in Milan, recover the knowledge of the lymph (Rusznyak, 1976). The structure and action of the lymph system was still undefined by 1900 (Yoffey, 1970) and both the immunological function of the lymph and the actual lymphogenic process are still not clearly understood even as we enter the 21st century.

However, in Asia, medical practice is based on meticulous observation of whole organisms—the whole person and the totality of integrated functions. Even though the discrete lymphatic function itself was unknown and unnamed, its effects were generally ascribed to the proper action of the Qi and fluids in China or the Prana and fluids in India. Even though the lymph, as such, was unnamed by Asian physicians, elaborate methods for generating and circulating lymph were developed, and faithfully practiced through Qigong, Yoga and other self-care practices.

When these practices are viewed in relation to what is now known about lymphatic function and its healing role, it appears that much of Qigong, Tai Chi, Yoga and Pranayama were developed specifically with the enhancement of lymphatic function in mind. Breath, movement and postural modification as well as meditation have specific effects on the circulation of the lymph and therefore enhance the overall function of the lymphatic system.

In the West science has divided the body fluids into specific categories: blood, lymph, cerebrospinal fluid, synovial fluid, extracellular fluid, intracellular fluid. From the paradigm of the West it seems that the unsophisticated Chinese may have overlooked important information with their broad, non-specific view of "Qi, blood and body fluids." However, the lymph fluid is largely interstitial biological water. This becomes an aspect of blood plasma (Rusznyak, 1976). Plasma and lymph both contribute water to the cerebrospinal fluid, part of which migrates back into the lymphatic system (Bradbury, 1985). This cycling of fluid (essentially water) from one system into another validates the Chinese approach of thinking of the all various fluids in a single continuum: simply as "body fluids."

Recent discoveries have demonstrated that electrical energy in the form of ion streams migrate throughout the body (Nordenstrom, 1983). The conductance medium for this energy flow system (which will be discussed in the energetic section of this article) is biological water in its numerous contexts including lymph, blood serum, interstitial fluid, etc.

The practice of SAHEM activates a number of remarkable self-healing mechanisms associated with the lymphatic system:

1. Lymph generation
2. Lymph propulsion
3. Immune function
4. Cerebrospinal fluid circulation
5. Nutritive function

LYMPH GENERATION

The actual generation of the lymph has long been attributed to the filtration of blood plasma from the capillaries (Adair and Guyton, 1985). As recently as 1985 this was recognized as the primary source of the lymph. This idea overlooks a significant detail that is at the crux of the tremendous health benefits of Qigong and Yoga: a significant portion of the water in the body's fluids is produced by the identical physiological process that generates the body's biological energy as discussed in the previous section on oxygen (Shields, 1989). Just as an individual respires to sustain life, each cell is also respiring. For each gram of glucose metabolized, in excess of a gram of water is produced.

In a moderately active 70 Kg human, between 2100cc and 2800cc of lymph enters the blood stream daily at the sub-clavian vein through the thoracic duct. In a resting individual the calculations of the Krebs cycle show that the cells produce approximately 950cc (Shields, 1989) of this daily water flow. In a person engaging in moderate exercises, such as Qigong or Yoga (or walking), up to 1400cc of aerobically generated water can be produced daily. When an individual is practicing some sort of moderate body activity, as much as one half of the water that is produced and propelled through the lymph system is a by-product of cellular metabolism. Increased lymph flow improves the elimination of the by-products of metabolism and pathogenic factors (both considered toxins) and increases the circulation of immune factors.

LYMPH PROPULSION

The blood's circulatory system has the powerful heart muscle to propel its fluid. The lymph, however has no distinct heart in humans. It was understood that the movement of lymph against gravity is accomplished by the contractions of the skeletal musculature through vessels with one way valves in a uni-directional system. Nothing new emerged until the mid 1900's when studies revealed that birds and reptiles have specific lymph hearts (Shields, 1980). Even as late as 1941 important aspects of lymph propulsion mechanism remained obscure (Drinker and Yoffey, 1941).

By 1949 "spontaneous, intrinsic pulsatory contraction of the peripheral lymphatic vessels" was demonstrated in humans with a rhythm unassociated with either the heart or the breath (Smith, 1949; Olszewski, 1979).

The current literature is crowded with a wide range of questions raised by research specifically on lymph propulsion: What factors might stimulate the intrinsic contractile mechanism? Is it consistent throughout or differentiated, by what regional factors? By what autonomic and neuroendocrine factors is intrinsic contractility modified? These are just a few of the questions. The study of SAHEM will accelerate our ability to answer these and other more general questions on the lymph system such as: What regulates lymph protein concentration? What effect does passage through the lymph nodes have on the proliferation of immune cells from within the nodes (Olszewski, 1985)? And what is the nutritive role of the lymph (Shields, 1972)?

The breath, through two mechanisms, has a significant effect on the propulsion of the lymph: 1). aerobic production of water and 2). mechanical pumping of the breath apparatus, lungs and diaphragm. Several additional propulsive mechanisms are initiated by body movement and body posture.

Tentative agreement now exists on at least five mechanisms which comprise the "lymph heart" and are activated by the SAHEM, including:

1. aerobic production
2. intrinsic smooth muscle contraction
3. contraction of striated skeletal muscles
4. gravity
5. breath apparatus: lungs, rib cage and diaphragm

Aerobic Propulsion. The aerobic production of water contributes to lymph propulsion mechanically. The cellular production of water, as a by-product of oxygen metabolism, is increased by dynamic Qigong and Yoga practice. The liquid holding capacity of the tissue spaces is naturally limited. As the limit is reached, the presence of additional lymph drives the excess into the terminal lymphatic vessels, the initial vascular openings of the lymphatic system (Yoffey, 1970: Adair, 1985; Shields, 1980, Olszewski, 1985). Like a cup that is running over, the interstitial space fills, building volume and pressure, and then flows over into the lymph vessels.

Intrinsic Smooth Muscle Contraction. The automatic response of the smooth muscle tissue of the lymphatic vessels and the peripheral lymphatic capillaries is to contract when filled and stretched to a certain tolerance (Olszewski, 1985). This contraction moves the lymph forward, with the assistance of the one way valves, in much the same way as the contraction of the heart moves the blood (Bradbury, 1985). In Qigong and Yoga this mechanism is accelerated by the increase in metabolism from gentle movement which contributes to lymph volume.

A number of studies have demonstrated that the intrinsic mechanism is also triggered when the overall sympathetic aspect of the autonomic nervous system is modified by the parasympathetic. Therefore, he intrinsic contractility mechanism is accelerated or enhanced by the shifting into the deeply relaxed state that is a primary feature of SAHEM practice.

Striated Skeletal Muscle Contraction. Even slight contraction of skeletal muscles in mild health enhancement practices propels the lymph in the one way vessels. In the more dynamic practices the pumping of the skeletal muscles and compression of the body parts increases interstitial. The effect of muscle contraction on lymph is one of the classic explanations for lymph motion (Adair, 1985, Bradbury, 1985). In Qigong and Yoga this mechanism is triggered by the mechanical action of the musculature and the action of the skeleton through the relaxation and contraction of the striated muscles in the movement forms of the practice.

Gravitational Propulsion. Because gravity exerts such a substantial force and because lymph has so far to climb to get to the thoracic duct's entry into the sub-clavian vein (at the base of the neck), any inversion of the limbs or even the prone body position allows for a more free flow of lymph. In keeping with this, elevation of the limbs is often prescribed for health problems characterized by a pooling of interstitial fluids, edema.

In SAHEM, many postures and movements create this mechanical dynamic where the lymph is actually propelled by gravity. In certain walking forms, Tai Chi and Guo Lin Qigong are the most renowned, the practitioner is constantly but slowly moving all of the limbs in beautiful circular motions that recurrently activate this mechanism. In Yoga many of the asanas (postures) invert the limbs. In the head and shoulder stands the whole body is inverted.

Breath Apparatus: Mechanical Propulsion. The most powerful of the array of mechanisms that work together to form the "lymph heart" is the mechanical action of the breathing apparatus itself (Sheilds, 1980). The concentration of lymphoid tissue above and below the diaphragm is many times more dense, and contains greater fluid volume, than any of the lymphoid tissue at the periphery, or even in the moderately prolific lymphoid areas of the axilla or groin (Adair, 1985). Lymph that has been carried from all over the body, accumulates centrally and is then propelled by the breath / diaphragm in a final rush through the thoracic lymph duct into the blood at the subclavian vein where it leaves behind its identity as lymph and is transformed into blood serum (Shields, 1981).

Above the diaphragm the thoracic duct of the lymphatic system is a central collecting vessel. Its size is many times that of the peripheral lymph vessels. Below the diaphragm a substantial dilation of the thoracic duct forms a collecting capsule for lymph, called the cisterna chyli. Chyle is a milky fluid of nutrients absorbed from the small intestine, which is passed into the circulating blood through the thoracic duct.

When full inspiration of the breath occurs, the diaphragm drops downward. A tremendous pressure is exerted on the cisterna chyli and a great negative pressure is generated in the thoracic cavity. The compressed cisterna chyli shoots lymph upward through the thoracic cavity. As air rushes in to balance the negative thoracic pressure, the lungs are fully expanded. This creates a powerful positive pressure which compresses the thoracic duct. Due to the one way lymphatic valvular system, lymph is forced upward where it enters into the sub-clavian vein with a rush.

Simultaneously, when the diaphragm drops downward on full inspiration it also compresses the abdominal and pelvic organs. The contents of the lymphoid reservoirs and vessels are forced by the same arrangement of one way valves forward in the system. In research with moving X-ray film, study subjects explored various actions and breath patterns. It was demonstrated that deep inspiration pumps the lymph at a rate that is dramatically greater than resting inspiration and other activities, including massage and walking (Shields, 1981).

It is fascinating to note that in Traditional Chinese Medical theory it has been taught for several millennia that the "lungs regulate the water passages" (Xie Zhu Fan, 1988). To Westerners this seems quite strange. The kidneys are considered to be responsible for water regulation. How could the Chinese have known that the activity of the lungs and diaphragm were linked to moving the body's internal water supply? Even now as we enter the 21st century Western science, and especially average Western citizens, have little idea that the simple act of regulating the breath is such a profound healing tool. However, here we can see that the Chinese somehow arrived at a kind of remarkable wisdom about how the lungs, the breath and the oxygen literally cooperate to produce and circulate the healing resource of water in the body.

IMMUNE FUNCTION

The immunoactive aspect of the lymphatic system is well represented in the conventional literature of Western physiology (Drinker, 1941; Bradbury, 1985; Olszewski, 1985; Van Rooiijen, 1987). The bone marrow, thymus, spleen and lymph nodes participate in the interaction of the lymph and immunity. The composition of the lymph fluid itself includes a number of immune active agents such as lymphocytes and macrophages (Olszewski, 1985).

Lymphocytes that exit with the lymph fluid from the nodes come from three sources: 1) inflowing with lymph from the tissues in the peripheral vessels, 2) exchanged from the blood that enters the node's own vascular system and 3) formed by local proliferation in the node itself (Bradbury, 1985). Lymphocytes naturally collect within the node, especially when lymph flow is sluggish. Greater numbers of cells proliferate when lymph flow is greater and the numbers circulated out of the node increase with flow volume as well (Adair, 1985). Both the numbers immunoactive cells and their circulation rate are increased by the deepening of the breath, relaxation and the alternating contraction and releasing of the musculature in the gentle practices of Qigong and Yoga.

Excellent recent research has clearly delineated, localized and quantified the development of specific antibody forming cells in lymph nodes (Van Rooijen, 1987). In addition, it has been found that there are neurotransmitter receptor sites on lymphocytes where they actually interface with the neuropeptides that drive immune function (Smith, 1985). This is one of the important links between neurochemistry and immunity that is mediated through the lymph system and optimized by the practice of the SAHEM which also increases the numbers of circulating immune cells and accelerates their rate of delivery.

CEREBROSPINAL FLUID (CSF)

The cerebrospinal fluid (CSF) system was classically perceived as a closed system, though another view, unconventional for many years, held that CSF was actually circulating in an open system that allowed the fluid to flow through the aracnoid villi and into the venous blood. By the 1970's it was generally acknowledged that the CSF travels along the cranial and spinal nerves and into the perineural lymphatics (Kimber, 1977).

Research using the microinjection of tracers has suggested several possible pathways for the passage of both the CSF and the cerebral interstitial fluid (CIF) to exit the aracnoid space (Bradbury, 1985). By 1985 the flow of CSF and CIF into the lymphatics was well documented (Bradbury, 1985). Consideration has even been given to the effects of pressure and posture on this flow (Bradbury, 1985), both of which are primary effects that are enhanced in the practice of Qigong, Taiji and Yoga.

The presence of CSF in the lymphatic system and the presence of neurotransmitter receptors on immune cells (Covelli, 1988) suggests a powerful benefit of the SAHEM on the interaction between neurotransmitters and immune function in the reticulo-endothelial system.

NUTRITIVE (TROPHIC) FUNCTION

The importance of a broad availability of nutritional factors to the tissues is fully accepted. However, the role of the lymphatic system in this activity was barely understood before 1972. (Shields, 1972) The original findings of Assellius in dogs revealed the route of absorption of nutrients from the small intestine via the lacteals which are specialized lymphatic ducts. (Adair, 1985) The effect of the breath apparatus through the action of the diaphragm, during deep inspiration, on the cysterna chyli and the small intestine may significantly enhance the rate or effectiveness of nutrient absorption.

The breath gentle body movements are considered especially important in traditional Asian systems of medicine and self-care as techniques for accelerating the circulation and absorption of healing nutritional factors in the diet and in medicinal and tonic herbal formulas. The clarification and understanding of the trophic function of the lymph suggests a simple but profound effect of the SAHEM on both the volume and flow rate of the lymphatic fluid and its nutrifying potential.

These mechanisms associated with lymphatic function play a significant role in the endogenous "healing system." They are naturally occurring and optimally functional in healthy individuals. One or several of these mechanisms may be deficient in individuals who are ill or at risk for disease. Each of these mechanisms are enhanced by the gentle movement, focused breath practice and relaxation that occur in the practice of Qigong, Yoga and other SAHEM.

BRAIN AND NERVOUS SYSTEM FUNCTION

Much of what is described in traditional medical systems as the "balance" of forces or energies, such as yin and yang in the Chinese system, can be associated with the dualistic components of the nervous system. In the central nervous system yin is rest and yang is action. Balance is the state between rest and action called dynamic equilibrium. This is the state that training in Qigong and Yoga seeks to refine. In the autonomic nervous system yin may be associated with the parasympathetic and yang may be associated with the sympathetic. The balance of yin and yang is associated with homeostasis—the state of balanced function and vitality.

Because the Western world view has generally had a difficult time understanding and accepting the concepts of Qi (chi), prana or vital force from the Asian systems, there has been a strong trend toward explaining the effects of Yoga, Qigong, acupuncture, etc. through the mechanisms of the nervous system (Kendall, 1989; Mann, 1973; Melzak and Wall, 1973; NIH, 1997). While these practices do have a definite effect upon neurological function, the neurological mechanism may actually be only an intermediary feature of a more refined and less easily quantified system of dynamic subtle energy interactions. However, much research has been done that reveals the neurological mechanisms activated in Qigong and Yoga, and it is appropriate to explore them here.

Qigong and Yoga and many of the SAHEM enhance several nervous system functions. These include:

1. initiation of the "relaxation response" (RR)
2. shift of the neurotransmitter profile
3. dilation of blood capillaries
4. support of the brain/neurological aspects of immune function
5. balance of right/left brain hemispheres
6. induction of alpha, and sometimes theta waves in EEG.

INITIATION OF THE RELAXATION RESPONSE

When the predominance of autonomic nervous system activity is sympathetic (adrenergic) the human system is working, expending energy and breaking down tissue. This is associated with the action phase of metabolism, and referred to as catabolic. In the extreme, this is the "fight or flight response" with increased heart rate, breath rate and blood pressure. It is also called the stress state and can lead to adrenal exhaustion and collapse (Selye, 1978). This state, when overactive and out of balance causes internal acidosis. Biological stress is conducive to the proliferation of a number of diseases or syndromes including hypertension, pain, depression, immune deficiency and inflammation (Benson, 1975).

The opposite aspect of autonomic activity, parasympathetic (cholinergic), is a phase of rest and tissue regeneration. It is associated with the conservative anabolic phase of metabolism. In its extreme this state is associated with the "relaxation response" (Benson, 1975), characterized by decreased heart and breath rate and a lowering of blood pressure. This is also associated with the resting phase of the basic resting activity cycle (BRAC), (Kleitman, 1967). Conscious deactivation of the sympathetic function with the activation of certain parasympathetic features of autonomic activity can neutralize the negative effects of "fight or flight" overactivity. The primary steps to initiate this state are deep, slow breathing coupled with the intention to relax. (Benson, 1975) These are the identical initiating steps for the practice of Qigong and Yoga. The literature alludes liberally to traditional Asian health maintenance practices as the historic source of techniques for generating the relaxation response (RR) and the typical biofeedback response (Green and Green, 1977).

NEUROTRANSMITTER PROFILE

Much of the new science of psychoneuroimmunology is based upon findings in the area of neurohormones, neuropeptides or neurotransmitters. It has already been mentioned that neurotransmitter receptor sites have been found on lymphocytes. A characteristic profile of neurotransmitters is present in a person who is experiencing pain, anxiety or depression. (Shealy, 1989) Joy, comfort or celebration produce their own neurotransmitter profiles as well. (Ornstein and Sobel, 1987) In patients suffering from pain, increased norepinephrine, reduced cholinesterase and depressed beta endorphin were found to be typical. (Shealy, 1989)

When SAHEM methods are employed that regulate the sympathetic function through the hypothalamus (see below) a neurotransmitter profile emerges which is characterized by decreased norepinephrine, elevated cholinesterase and elevated beta endorphin. (Shealy, 1989) The neurotransmitter profile present in the predominantly parasympathetic and usually more anabolic (alkaline) environment is recognized as able to reduce pain and depression (Shealy, 1989), reduce cravings for addictive substances (Kovacs, 1988) and promote healing.

Chinese research has quantified neurotransmitter activity specific to Qigong exercise. It was found that the Qigong effect, the biological state during Qigong practice, is associated with specific shifts in the monoamine neurotransmitter content of the blood. (Liu, 1988) Serotonin and 5HE generally tend to be decreased by Qigong practice. Noradrenaline and dopamine tend to increase. This demonstrates that the aspects of Qigong and Yoga that quiet the mind and relax the body tend to induce a neurotransmitter profile that is conducive to healing.

INCREASED MICROCIRCULATION

A classic body response in Qigong and Yoga is the elevation of skin temperature. In the fight or flight state, hyper-sympathetic, the arterioles in the skin, muscles and certain organs constrict. During the systematic deactivation of sympathetic function, typical in Qigong and Yoga, vasodilation occurs with the accompanying warmth of the surface of the skin. This is one of the primary goals in biofeedback training and was found as a typical response when the skin temperature of meditators was evaluated in research. (Green, 1977)

A number of studies from China explore the microcirculatory mechanism very thoroughly and conclude that this microcirculatory dilation, increasing blood volume in a particular region, is a major reason for the continued successful application of Qigong and other ancient health maintenance methods (Zhou, 1989; Xiu, 1988; Hong, 1988; Wei, 1988; Zhao, 1988; Chu, 1988).

An ancient saying from traditional Chinese medicine is, "The Qi is the commander (leader) of the blood, and the blood is the mother of the Qi" (Kaptchuk, 1983). It is interesting that the Chinese were aware of a direct relationship between healing energy and blood circulation long ago. They were able, without science as we know it, to develop specific self-healing methods that purposefully increase the circulation of Qi and blood more effectively to the tissues, organs and glands.



Counterclockwise

Clockwise

Fig. 8.1 *Use the eyes to help spiral.*

Note:To circle to the left is to circle counterclockwise; circle counterclockwise as you move the pearl up. To circle to the right is clockwise; circle clockwise as you move the pearl down.

The pearl is circulated in each Belt Channel nine times. After the ninth time of circling each point, you will cross each channel internally with the pearl by moving the pearl from front to back, and from left side to right side. Each time you will end with the pearl at the front, and then move on to the next level Belt Channel.

BRAIN/NEUROLOGICAL ASPECTS OF IMMUNE FUNCTION

In the classic tradition of Western science, it has been thought that the immune system was an autonomous self-regulating system. A tremendous amount of research now demonstrates that mental and emotional states alter resistance to disease and infection (Ornstein, 1987). Immune organs including the thymus gland, spleen, lymph nodes and bone marrow are invested with nerve tissue (Ornstein, 1987). Lymphocytes and macrophages have receptors for neurochemicals, including catacholamines, prostaglandins, serotonin and endorphin (Roszman, 1985; Ornstein, 1987). Clearly, there is a definite relationship between brain, nervous system function and immune capability—a major interaction of the "healing system."

In the practice of Qigong and Yoga the hypothalamus regulates the autonomic nervous system function to decrease sympathetic activity. (Green, 1977; Benson, 1975) A number of studies have demonstrated that the hypothalamus has an influence over immune function (Ornstein, 1987). The hypothalamus has 40 times more receptor sites than any other part of the brain or nervous system (Pert, 1985 and 1986).

Meditation, progressive relaxation, deep breathing and slow relaxed movement all tend to move the practitioner out of the sympathetic state and induce the relaxation response. Research on the effect of relaxation and visualization sheds some light on the effect that the Qigong and Yoga states may have on immune function. Groups of elders who received relaxation training had significant increases in the activity of "natural killer cells" while control groups did not. Chinese research has corroborated the positive effect of Qigong and other SAHEM on the status of immune function as well (Hong, 1988; Yao, 1989; Xu, 1988; Wang, 1988; Shannahoff-Khalsa, 1988).

BRAIN HEMISPHERE DOMINANCE

Thousands of years ago the Oriental practitioners of self-care disciplines intuitively developed an awareness of an alternating cycle of the predominance of body activity from the right side of the body to the left side. One particular Qigong method, Taiji (Tai Chi), is founded on a constant, flowing of the limbs in circular motions, alternating from right to left. The side of the body that bears the weight is planted, stable, heavy and associated with the Yin. The side that is free to move and kick is active, light, flexible and associated with the Yang. Constant alternation of right and left side activity are thought to balance the forces of yin and yang in the body. Focusing on the right and left sides, alternatively, activates and balances the right and left motor centers in the brain.

In Yogic medicine (Ayurveda), the channels or circuits that conduct the resonating human energy field, are called nadis. Ida nadi and Pingala nadi associate with right and left brain activities (Shannahoff-Khalsa, 1988; Werntz, 1983). This association effects right and left nasal passage activity. These channels alternate dominance in a 2-3 hour cycle, causing the dominant nostril to be clear while the other nostril to swells and becomes congested. (Werntz, 1983) This phenomenon was not noted in the Western world until 1889 when the German physician R. Kayser recorded his observation of the "nasal cycle" (Kayser, 1889). Much of the research on this phenomenon up through the 1980's was motivated by the quest to develop pharmaceuticals for nasal congestion (Shannahoff-Khalsa, 1988).

It has been demonstrated that the nasal cycle is coupled with the alternating lateralization of cerebral hemispheric activity (Werntz, 1983). It was found with research subjects that when a shift occurred in either nasal dominance or brain hemisphere dominance, there was an associated shift, within moments, in the other as well. The right nasal cavity, tends to be more open and the left more congested when the left hemisphere of the brain is more active. This is associated with the active phase of the BRAC and increased general sympathetic tone (Shannahoff-Khalsa, 1988). In contrast the right brain hemisphere is more active when the left nostril is open and dominant and the individual is in the resting phase of the BRAC or the para-sympathetic mode.

A number of different physiological states have been found to be associated with the dominance of one or the other nostril.

- deep sleep is initiated more quickly with left nostril dominance.
- appetite and digestive ability are enhanced during right nostril dominance.
- left nostril, right brain dominance is more conducive to receiving new ideas, while right nostril, left brain dominance is an advantage during discourse.
- it is possible to alter the pattern of "thought waves" by consciously alternating nasal dominance by exercising the congested nostril through forced nostril breathing (Shannahoff-Khalsa, 1989).

A specific Qigong and Yoga breath technique which has been practiced for centuries is the right and left singular nostril breathing. The Salk Institute has done extensive research with this technique, originally prompted by the researcher's work with the Kundalini Yoga tradition. The studies have shown that forcing the breath through the constricted nostril can increase the EEG amplitude of the contralateral hemisphere of the brain (Werntz, 1987). It has been demonstrated that certain diseases and psychopathologies are brain hemisphere specific (Flor-Henry, 1979; McIntyre, 1976). It may be possible, therefore, that the use of alternating single nostril breathing may be applicable as therapy in cases where lateralized dysfunction has been found.

In addition, it was discovered that there is a direct correlation between nasal dominance, brain hemisphere dominance and the lateralized biochemical activity in the peripheral body parts. Recent studies of the nasal cycle comparing plasma catecholamine levels in the venous circulation of the right and left arms found that levels of norepinephrine alternated in direct correlation with the rhythm of sympathetic dominance of the nasal passages (Kennedy, 1986).

INDUCTION OF ALPHA/THETA BRAIN WAVE ACTIVITY

The intention to relax and deepening of the breath are the classic initiating actions that trigger the "relaxation response." Research with practitioners of Yoga (Green, 1977) and Qigong (Collected Proceedings, 1988) has shown that during practice brain wave frequency tends toward the alpha range and in certain cases theta frequency brain activity is achieved.

Alpha level brain function is a result of relaxation and is conducive to healing. The slowing of heart rate, reduction of blood pressure and elevation of skin temperature are common physiological features of the alpha state. Theta is a deeper trance like state that has been found in research with individuals with extraordinary capabilities such as sitting on beds of nails or immediate wound healing without bleeding. (Green, 1977)

In Qigong and Yoga the goal is to bring the lowest achievable frequency of brain wave activity to the practice. In standing Qigong, where there is no body movement, deep states of consciousness with low frequency brain waves are more likely than in moving Qigong. Similarly, in Yoga, there are methods involving movement and methods that primarily involve stillness. The pure meditation state lends more easily to the theta range of brain activity.

Several EEG studies from China have concentrated on the quiescent state—meditation with no movement (Pan, 1988; He, 1988; Wang, 1988). However, the dynamic or moving methods are effective, as well, when the alpha or theta state is achieved with the movement. In both Qigong and Yoga it is a primary focus to "allow the body and energy to sink and relax" and to "relax into the posture."

These neurological mechanisms are associated with the production and circulation of an endogenous healing resource. In healthy individuals they are optimally functional. In those individuals who are ill or at risk for disease, one or several of these functions may be deficient. The gentle movement, focused breath practice and relaxation that occur in the practice of Qigong, Yoga and other SAHEM enhance all of the neurological activities.

ENERGETIC MECHANISMS

As has been shown, the benefits of practicing health enhancement and self-healing methods are significant even though we have little or no understanding of the traditional Asian mechanisms based in Qi and Prana. There is, however, a robust exploration of energetic biophysiology in the Western world that is not new. The biological energy for the work of the cell, called ergs, is fully embraced by conventional science. The electrical discharge in the sinus node of the heart and the ability to track it electrically through EKG has an unquestionable place in science and medicine. It is fully recognized that the movement of the neurological impulse along the nerve pathway includes a discharge of ions. The permeability of the cell membrane is directly linked to the electrical charge associated with the channels of entry and exit In diagnostic medicine the MRI's ability to manipulate the electrons within the cells is clearly based on energetic subtlety that is beyond ionic exchanges.

There is really no question that there has been a profound discussion of energetic physiology that is quite evolved in Western science. As early as 1935 Harold Saxton Burr described a system of electro-dynamic fields (Burr, 1935) from studies using DC current with both salamanders and humans (Burr, 1973). Previous to that numerous European and American scientists and natural philosophers, including Hippocrates, Paracelcus, Van Helmut, Fludd, Stahl, Mesmer, Galvani, Hahnamann discussed a non-chemical basis to life and medicine: pneuma, physis, munia, magnale magnum, magnetic fluid, anima, animal magnetism, life force, odic force, vital force, elan vitale, life field, etheronic force, body electric. This is a much richer history of energetic physiology than most people in the Western world are aware.

Robert Becker confirmed Burr's work and used low frequency DC currents to regenerate salamander tails, and foster healing in wounds and non-healing bone fractures. In his work with the National Institutes of Health (NIH) Becker demonstrated that the perineural (nerve sheath) network is highly conductive. The points of highest conductivity on this network are in the same spot, in many instances, as the major acupuncture points (Becker, 1985). B.E.W. Nordenstrom has delineated the vascular-interstitial closed circuit (VICC) as a system of preferential ion conductance pathways (PICP), comprising a network of biological circuitry (Nordenstrom, 1983) which is nearly identical to the energy channels of traditional Chinese medicine.

It is unlikely that much historic time will pass before the Western scientific community turns full strength on the issues of energetic physiology. Already the notion of inherent electrodynamic fields has gained significant attention. A concept is arising in both China and the west of "bioinformation," which is an intrinsic "informing" capacity across the life continuum, all the way from molecules through mind. (Rubik, 1995) It has been proposed that the energetic mechanism of acupuncture, energy medicine and the inner capacity for self-repair is mediated through an electromagnetic vector field, intrinsic to each living entity. (Liboff, 1997)

Qigong and Yoga with their roots in energy based systems and their obvious benefits in health and healing will only accelerate the movement toward a scientific clarification of the interface between the biochemical and bioenergetic aspects of physiology.

CONCLUSION

Qigong, Taiji, Yoga and various other self-applied health enhancement methods (SAHEM) including Feldenkrais and Alexander methods have demonstrated significant potential for disease resolution, health improvement, health maintenance and performance enhancement. The efficacy of these ancient techniques and the newer innovations can be explained clearly through our conventional scientific understanding of the activation of the body's basic self-regulatory mechanisms. Though the traditional Asian explanations for such efficacy has been based on mysterious and invisible forces, Qi and Prana, the methods are, nonetheless, fully congruent with our prevailing model of physiology.

One or several of the following mechanisms (see chart) are activated during the practice of various forms of SAHEM: enhancement of oxygen availability, cellular water production, lymph propulsion, cerebrospinal fluid motion, acceleration of immune activity, modification of the neu-

Physiological Mechanisms	Structures, Processes, and Substrates	Qigong or Yoga Activity
I. Oxygen		
1. Energy generation	Oxygen uptake	Movement/breath
2. Aerobic water	Oxygen uptake	Movement/breath
3. Immune enhancement	Oxygen uptake	Movement/breath
4. Free radical neutralization	Oxygen uptake	Movement/breath
II. Lymph		
1. Aerobic generation	Oxygen uptake	Movement/breath
2. Propulsion		
a) Aerobic	Oxygen uptake	Movement/breath
b) Intrinsic contraction	Interstitial fluid volume	Breath and relaxation
c) Muscle pump	Muscle contraction	Movement
d) Gravitational	Body position	Postures and movement
e) Breath apparatus	Lungs, diaphragm, cisterna chyli	Breath activity
3. Immune function	Propulsion (2a–e)	Breath, movement, and posture
4. Cerebrospinal fluid flow	Propulsion (2a–e)	Breath, movement, and posture
5. Nutritive function	Propulsion (2a–e)	Breath, movement, and posture
III. Nervous system		
1. Autonomic	Brain, neurochemistry, nervous system	Relaxation and breath
2. Neurotransmitter profile	Hypothalamus	Relax/visualize
3. Microcirculation	Hypothalamus	Relaxation
4. Immunity	Macrophages, lymphocytes, neurotransmitters	Relaxation, meditation
5. Brain hemisphere control	Brain, nervous system	Nostril breath and right/left side movement
6. Brain wave frequency	Brain, nervous system	Meditation
7. Neuroreflex stimulation	Neuroreflex system	Rubbing points

Appendix Figure 3.1. Physiological mechanisms and the activities in Qigong and other self-applied health enhancement methods (SAHEM) which are their triggers:

rotransmitter profile, initiation of the relaxation response, alpha range brain wave frequency, etc. Each of these mechanisms is a component of a powerful internal "healing system." Together they produce and circulate internal healing resources which are historically referred to in Asia as an "inner medicine" or "healer within." In Western terms we might call this an endogenous medicine or a naturally occurring self-repair resource.

It may be that simple SAHEM practices are among the most powerful healing tools ever developed by the human race. It is clear that triggering such an array of self-regulating internal mechanisms has a profound effect on the capability of an individual to maintain health or resolve disease. Given 70% of disease is preventable (DHHS, 1991) and 8 of the 9 major causes of disease are preventable (Fries and Koop, 1993), the SAHEM may be more powerful than post symptomatic medical intervention in reducing disease overall.

Using science to study Qigong, Yoga and acupuncture will very likely help to rewrite the textbooks of medicine and physiology. Direct study of the activity of the physiological states triggered in subjects trained in Qigong or Yoga is an obvious research priority. In light of the crisis in health care costs, it is the mandate of the medical and social sciences to purposefully remove barriers to the implementation of these practices and the study of their benefits.

It was agreed in 1997 that acupuncture had health enhancing potential (NIH, 1997) even though neither its traditional Asian explanation nor its Western scientific explanation were conclusive. Given the conventional scientific understanding of the SAHEM is very much more conclusive than the understanding of acupuncture, it is likely that Qigong and Yoga will be even more easily embraced in the emerging health care delivery paradigm that is based in health improvement. This promises to eventually create a radical transformation in health care and medicine, a major redesign of public health and a significant decrease in the cost of medicine.

For now we have ample evidence to confirm the value of these practices physiologically. Eventually, perhaps, our capacity to explore more subtle realms of human energy will confirm that there is an energetic feature of anatomy and physiology that we do not yet understand. Either way, it is clear that Qigong, Yoga and other SAHEM are practical, timely and inexpensive tools for increasing health and healing disease.

REFERENCES

Adair, T.H., Guyton, A.C., Introduction to the Lymphatic System. Experimental Biology of the Lymphatic Circulation. Johnston (ed), Amsterdam, Elsevier Science Publishers, 1985.

Becker, R. O., The Body Electric: Electromagnetism and the Foundation of Life. New York, William Morrow and Co., 1985.

Benson, H.R., The Relaxation Response, New York, William Morrow and Company, 1975.

Bradbury, M.W.B., Cserr, H.F., Drainage of Cerebral Interstitial Fluid and of Cerebral Spinal Fluid into Lymphatics. Johnston (ed), Biology of the Lymphatic Circulation, Elsevier Science Publishers, 1985.

Brahmi, Z., et al., Effect of Acute Exercise on Natural Killer Cell Activity in Trained and Sedentary Human Subjects, Journal of Clinical Immunology, 5(5):321, 1985.

Burr, H.S., Northrop, F.S.C., The Electro-dynamic Theory of Life. Quarterly Review of Biology, 8: 322-33, 1935.

Burr, H.S., Fields of Life. New York, Ballentine, 1973.

Chu Weizong, et al., Changes of cerebral blood flow and microcirculation under the Qigon state. Proceedings of the First International Conference for the Academic Exchange of Qigong, Beijing, China, 1988.

Collected Proceedings, The First World Conference for the Academic Exchange of Medical Qigong. Beijing, China, 1988.

Covelli, V., Jirillo, E., Neuropeptides with Immunoregulatory Functions: Current Status of Investigation. Functional Neurology. 3(3):253-261, 1988.

Cullen, K., et al., Multiple Regression Analysis of Risk Factors for Cardiovascular Disease and Cancer Mortlality in Busselton, West Austrailia: A 13 Year Study, Journal of Chronic Diseases, 36:371-377, 1983.

DHHS, Healthy People 2000. Department of Health and Human Services, 1991.

Drinker, C.K., Yoffey, J.M., Lymphatics, Lymph and Lymphoid Tissue. Cambridge MA, Harvard University Press, 1941.

Fehr, H.G. Human macrophage function and physical exercise: phagocytic and histochemical studies. European J Applied Physiology 1989;58(6):613-7.

Flor-Henry, P., Shizophrenic-like reactions and affective psychoses associated with temporal lobe epilepsy. American Journal of Psychiatry, 126:400-403, 1979.

Fries, J., and Koop, C.E., Refducing Health Care Costs by Reducing the Nedd and Demand for Medical Services. New England Journal of Medicine,

329: 321- 325, 1993.

Gordon, T., Kannel, W.B., The Framingham Study. An Epidemiological Investigation of Cardiovascular Disease. Sections 1-26, Bethesda MD, National Heart and Lung Institute, 1970.

Green, E., Green, A., Beyond Biofeedback. New York, Delacorte Press, 1977.

Guyton, A.C., Medical Physiology, Phila, Saunders and Co., 1992

Hong Shunhua, et al., A primary observation on microcirculation of nail fold and immunogenicity after Qigong practice for a short period. Proceedings of the First International Conference for the Academic Exchange of Qigong, Beijing, China, 1988.

Jahnke, R., Qi Gong: Awakening and Mastering the Profound Medicine that Lies Within. American Journal of Acupuncture, 17(2):139-151, 1989.

Kaptchuk, T.J., The Web That Has No Weaver. New York, Congdon and Weed, 1983.

Kayser, R., Die Exakte Messung der Lufterchgangigkeit der Nase, Z Ohrenheilk, 20:96-106, 1889.

Kendall, D.E., Understanding Traditional Energetic Concepts. Energy Fields in Medicine, Proceedings of the Fetzer Foundation1989 Conference coordinated by Michael Morton, 10-43, 1989.

Kennedy, B, Ziegler, M.G., Shannahoff-Khalsa, D.S., Alternating Lateralization of Plasma Catecholamines and Nasal Patency in Humans, Life Sciences, 38:1203-1214, 1986.

Kimber, D.C., Kimber, Gray, Stackpole's Anatomy and Physiology, 17th Edition, New York, Macmillan Publishing Co., 1977.

Kleitman, N., Basic Rest Activity Cycle in Relationship to Sleep and Wakefulness. In Kales, A., Sleep: Physiology and Pathology, Philadelphia, Lippincott, 1967.

Kovacs, G.L., Telegdy, G., Hypothalamo-neurohypophyseal Neuropeptides and Experimental Drug Addiction, Brain Research Bulletin, 20(6):893-895, 1988.

Liboff, A., Bioelectromagnetic Fields and Acupuncture. The Journal of Alternative and Complementary Medicine, 3(Supp 1), S-77—S-87, 1997.

Liem, S. H., The Effect of Sanumgerman (Germanium) on the Oxygen Partial Pressure of the Oxygen Multistep Process. paper presented at the International Conference on Organic Germanium. 1985.

Liu Binghuai, et al., Effects of the qigong exercise on the content of the monoamine neurotransmitters in the blood. Proceedings of the First International Conference for the Academic Exchange of Qigong, Beijing, China, 1988.

Mann, F, Acupuncture: The Ancient Chinese Art of Healing and How It Works Scientifically. New York, Random House, 1973.

McIntyre, M., et al., Left and right temporal lobe epileptics: a controlled investigation of some psychological differences. Epilepsia 17:377-86, 1976.

Melzak, R and Wall, The Puzzle of Pain. 1973 Harmondsworth : Penguin Books, 1973.

NIH, National Institutes of Health Consensus Panal on Acupuncture, 1997.

Nordenstrom, B.E.W., Biologically Closed Electrical Circuits: Clinical, experimental and theoretical evidence for an additional circulatory system. Stockholm, Sweden, Nordic Medical Publications, 1983.

Olszewski,W.L., Lymphatic Contractility. New England Journal of Medicine, 300, 316, 1979.

Olszewski, W.L., Peripheral Lymph: Formation and Immune Function. Boca Raton, FL, CRC Press, 1985.

Ornstein, R., Sobel, D., The Healing Brain. New York, Simon and Schuster, 1987.

Pedersen, B.K., et al., Modulation of Natural Killer Cell Activity in the Peripheral Blood by Physical Exercise. Scandanavian Journal of Immunology, 27(6):673-678, 1988.

Pert, C.B., et al., Neuropeptides and their receptors: a psycho somatic network. The Journal of Immunology, 135(2):820-826, 1985.

Pert, C.B., The wisdom of the receptors: neuropeptides, the emotions

and the bodymind. Advances, Institute for the Advancement of Health, 3(3):8-16, 1986.

Rubik, B., The unifying Concept of Information in Acupuncture and Other Energy Medicine Modalities. The Journal of Alternative and Complementary Medicine, 3(Suppl), S-67—76, 1997.

Roszman, T.L., et al., Neuroanatomic and neurotransmitter influences on immune function. The Journal of Immunology, 135(2):769-772, 1985.

Rusznyak, I., Foldi, M., Szabo, G., Lymphatics and Lymph Circulation. London, Pergamon Press, 1976.

Saltzman, R.L., et al., Immunodeficiency of the Elderly. Reviews of Infectious Diseases, 9(6):1127-1139, 1987.

Selye, H., The Stress of Life, New York, McGraw-Hill Book Co., 1978.

Shannahoff-Khalsa, D., A Contemporary View of Life Force Biology: The Merging of Kundalini Yoga and the Neurosciences, in Energy Medidcine Around the World, ed T.M. Srinivasan, Pheonix, AZ, 1988.

Shannahoff-Khalsa, D., Rhythems of the Mind and Breath, Advances, Journal of Mind-Body Health, 6, #2, 51-55, 1989.

Shealy, C.N., et al., Depression: A Diagnostic Neurochemical Profile and Therapy with Cranial Electrical Stimulation, Journal of Neurological and Orthopedic Medicine and Surgery, 10(4):319-321, 1989.

Shields, J.W., The Trophic Function of the Lymphoid Elements. Springfield, Il., International Foundation of Lymphology, 1972.

Shields, J.W., "Central Lymph Propulsion," Journal of the International Society of Lymphology, 13(1):9-17, 1980.

Shields, J.W., Human Central Lymph Propulsion, Journal of the American Medical Association, 246 (18), 1981.

Shields, J.W., The Aerobic Production and Central Propulsion of Lymph. Proceedings of the 12th International Congress of Lymphology, Tokyo, Japan, September, 1989.

Smith, E.M., et al., Lymphocyte production of endorphins and endorphin-mediated immunoregulatory activity. The Journal of Immunology, 135(2):779-782, 1985.

Smith, R.O., Lymphatic Contractility: A Possible Intrinsic Mechanism of the Lymph Vessels for Transport of Lymph. Journal Of Experimental Medicine, 90, 497, 1949.

Temple, R, Needham J, The Genius of China: 3,000 years of science, discovery and invention, New York, Simon and Schuster, 1986.

Van Rooijen, n., The "In Situ" Immune Response in the Lymph Nodes: A Review. The Anatomical Record, 218(4):359-364, 1987.

Veith, I., The Yellow Emperor's Classic of Internal Medicine (Nei Ching). Berkeley, University of California Press, 1972.

Wang, Zhengchang, et al., A preliminary study of the relationship between Qigong and energy metabolism: the changes of blood ATP content in Qigong masters in the Qigong state. Proceedings of the First World Conference for the Academic Exchange of Medical Qigong, Beijing, China, Pg 58, 1988.

Warburg, O., The Prime Cause and Prevention of Cancer, 1966 Lindau Lecture, Wurzburg, Germany, K. Triltsch.

Wei Shouzhang, et al., An experimental research of the changes of blood volume in the brain and the changes of the heart rate in the Qigong and PSI state. Proceedings of the First International Conference for the Academic Exchange of Qigong, Beijing, China, 1988.

Werntz, D., Bickford, R.G., Bloom, F.E., Shannahoff-Khalsa, D.S., Alternating Cerebral Hemispheric Activity and the Lateralization of Autonomic Nervous Function. Human Neurobiology, 2:39-43, 1983.

Werntz, D., Bickford, R.G., Shannahoff-Khalsa, D.S., Selective Hemispheric Stimulation by Unilateral Forced Nostril Breathing. Human Neurobiology, 6:165-171, 1987.

Yoffey, J.M., Courtice, F.C., Lymphatics, Lymph and the Lymphomeyloid Complex. London, Academic Press, 1970.

Xie Zhu Fan, et al., Reference Guide to Acupuncture: Zang Fu Principles and Diagnosis. Wonder Lake, IL, Northern Star Press, 1988.

Xiu Ruijuan, et al., Studies of Qigong effect on the human body by the computerized synchronous system for macro and microcirculatory parameters measurement. Proceedings of the First International Conference for the Academic Exchange of Qigong, Beijing, China, 1988.

Zhao Baofeng, et al., Effects of Qigong on cerebral blood flow (CBF) and extremitic blood flow (EBF). Proceedings of the First International Conference for the Academic Exchange of Qigong, Beijing, China, 1988.

Zhou, M.R., Observation of Qigong treatment in 60 cases of pregnancy induced hypertension. Chung Hsi i Chieh Ho Tsa Chih, 9(1):16-18, 1989.

1Note: Taiji (Tai Chi) is a kind of Qigong. Pranayama is an aspect of Yoga. Feldenkrais Method, Alexander Technique and numerous systems of self-initiated health enhancement including puroseful walking and very low impact aerobics are more recently developed self-applied health enhancement methods (SAHEM).

GLOSSARY OF TERMS

A

Abdominal Breathing - to breathe from the abdomen (expand with inhalation, contract with exhalation).

Acupuncture - one of the Four branches of Traditional Chinese Medicine, which involves treating patients through the use of Needling, Cupping, Bloodletting, Moxa and Magnets in order to stimulate energy flow.

Acupuncturist - a doctor of acupuncture therapy.

Acquired Essence - also called Postnatal Jing, is acquired energetic tissue substance, developed after birth.

Acquired Force - energy pertaining to the Earth and surrounding environment.

Acquired Qi - also called Postnatal Qi, is the body's energy derived from food, air and drink, acquired after birth.

Acquired Rational Mind - also called postnatal mind, are thoughts and feelings derived from the acquired experiences of one's environment.

Acute - a rapid onset and short duration of a particular condition.

Adenoma - a neoplasm (abnormal formation of tissue) of glandular epithelium.

Adenocarcinoma - a malignant tumor arising from a glandular organ.

Affirmation - a word, phrase or sentence that is repeated frequently to influence, or change, a belief held deeply within the unconscious mind.

Agoraphobia - fear of places or situations from which escape might be difficult or embarrassing. Symptoms include panic like symptoms and a precondition towards panic attacks.

Akashic Records - a Sanskrit term used to describe the detailed knowledge of all the historical events of the world recorded within the "all-pervasive space of the universe" or "Wuji," also called the "knowledge of the infinite Void."

Alchemy - internal transformation of body and energy brought about by: 1. Nei Dan (Inner Alchemy) through internal Qigong training, and 2. Wai Dan (External Alchemy) using herbal formulas.

Amenorrhea - the absence or suppression of menstruation.

Ancestral Channel - a term used to describe one of the Eight Extraordinary Vessels.

Ancestral Qi - energy inherited from both parents at the time of conception, responsible for innate talents and skills.

Ancestral Traits - pertaining to the ancestral spiritual influence which affects the patient's body. Ancestral traits are developed according to the geographic location at the time of conception.

Anemia - a reduction in the number of circulating red blood cells.

Angina Pectoris - severe pain and a sensation of constriction about the heart.

An Jing - see Hidden Power.

Ankylosing Spondylitis - inflammation of the vertebrae, giving rise to stiffness of the back.

An Mo Therapy - a tissue manipulation therapy that focuses primarily on the treatment of internal organ disorders.

Anorexia - loss of appetite.

An Sound Resonation - Hidden or inaudible sound resonation.

Antibody - any of the numerous proteins produced by the immune system that defend against antigens.

Anxiety - emotional distress, resulting in Heart palpitations, inability to concentrate, muscle tension causing muscle aches.

Aphasia - the absence or impairment of the ability to communicate through speech, writing, or signs, due to a dysfunction within the brain center.

Aplastic Anemia - anemia caused by deficient red cell production, due to bone marrow disorders.

Apoptosis - the disintegration of cells into membrane-bound particles that are then phagocytosed by other cells.

Archetypes - a term coined by the psychiatrist Carl G. Jung to describe the collective unconscious images and motifs (e.g., warrior, healer, priest, whore, etc.). An inherited idea or mode of thought derived from the experiences of the race which is present in the unconscious of the individual.

Arrhythmia - an irregularity or loss of rhythm pertaining to the Heart.

Arteriosclerosis - term pertaining to a number of pathological conditions in which there is a thickening, hardening, and loss of elasticity of the artery walls.

Arthralgia - pain in the joints.

Arthritis - pain and inflammation of the joints, followed by progressive stiffness.

Arthropathy - pertaining to any joint disease.

Ascariasis - infestation of ascaris lumbicoides parasite (pinworm).

Ascending Qi - the action and flow of energy moving upward.

Ashi Points (also called Trigger Points) - places on the body which are tender spots or painful areas near diseased or injured tissue.

Asthma - a disease caused by increased responsiveness of the tracheobronchial tree within the Lungs, due to various stimuli, causing severe difficulty in breathing.

Astral Body - also called the Soul Body, describes the energetic vehicle in which the Eternal Soul can journey outside of the physical body. The Astral Body is connected to the Middle Dantian by a silver "cord of life."

Astral Matter - the energetic substance located within the second field of the body's external Wei Qi and attributed to the emotional energy body.

Astral Plane - an energetic and spiritual plane of existence parallel to the physical plane.

Astral Travel - also called Soul Travel (or Astral Projection) describes the condition of the Eternal Soul journeying outside of the physical body, connected to the Middle Dantian by a silver "cord of life."

Astringent - any substance or agent that causes tissues to contract or that inhibits secretion of Body Fluids such as mucus or Blood.

Antigens - any substance able to provoke an immune response in the human body.

Atrophic - pertaining to atrophy.

Atrophy Syndrome - a disorder characterized by flaccidity and weakness of the limbs and a progressive loss of strength and muscle tone.

Attention Deficit Disorder - a learning disorder manifesting through the following symptoms: habitual failure to pay attention, very distractible, inability to organize, extreme impulsiveness, difficulty in studying, often accompanied by hyperactivity.

Aura - the energetic field which radiates light and circulates around the second field of the body's external Wei Qi

Aura Colors - the body's energetic luminous colors ranging from red, orange, yellow, green, blue, violet to white.

Auspicious Powers - the energy potential contained within the Five Yin Organs.

B

Ba Gan - eight diagnostic principles used in Traditional Chinese Medicine in order to differentiate symptoms.

Bai Dai - white vaginal discharge.

Baihui Point (One Hundred Meetings) - the Governing Vessel point at the top of the head (GV-20).

Bellows Palm Technique - a palm technique in which the thumb and little finger compress and release like a bellows.

Bells Palsy - unilateral facial paralysis of sudden onset.

Benign - gentle or kindly, not aggressive, the opposite of malignant.

Bile - a secretion stored in the Gall Bladder released into the duodenum as a digestive juice.

Bio-Rhythm - three distinct cycles and energy flow that pertain to the body's physical, emotional and intellectual rhythms.

Bipolar Personality Disorder - formerly known as Manic Depressive Personality Disorder, a state of extreme euphoria or pervasive irritability, with racing thoughts, inability to sleep, and impulsive behavior (that may last for days or months), that alternate with morbid depression with suicidal ideation or attempts at suicide (see Depression). During the manic phase there may be hallucinations.

Bird's Bridge - pertaining to the energetic connection between the tongue and the upper "hard" palate, behind the teeth.

Birth Energetic Patterns - pertaining to the energetic patterns developed according to the influence of the time and geographic location of the patient's birth.

Bladder Fire - also called Common Peoples' Fire, or Perineal Fire, is located in the lower abdomen by the perineum, and is responsible for evaporating water.

Blended Originals (Hun Yuan) - the body's "internal combined energy" fused into the Lower Dantian area.

Bloated and Expanded Stagnation - stagnation with a characteristically expansive or bloated appearance, can be caused from an accumulation of Phlegm and Body Fluids (in addition to Qi and Blood) in the adjacent tissue areas of the body.

Blood (Xue) - the dense fluid which nourishes the body, transmits Qi, and provides the material for the mind and emotions.

Blood Heat - a condition categorized by Heat and Blood signs (retching of Blood, expectoration of Blood, Bloody stool or urine, nosebleeds, and menstrual irregularities).

Bloodletting - a technique used in acupuncture therapy which entails pricking the skin to release and remove Blood Heat and Blood stagnation.

Blood Stagnation - the impairment or cessation of normal Blood flow.

Blood Stasis - the same as Blood stagnation.

Blood Vessels - the body's transportation system for Qi and Blood nutrition and regeneration.

Body Fluids (Ye) - these are clear, light, and watery. They originate from food and drink and are transformed and separated by the Spleen (aided by the Kidneys) and dispersed by the Lungs and Triple Burners. (i.e., sweat, tears, saliva, and mucus.)

Body Liquids (Jin)- these are a heavier denser form of Body Fluids. Their function is to moisten the joints, spine, brain, and bone marrow. They lubricate the orifices of the sensory organs.

Bone - the body's skeletal material related in essence to the Kidneys.

Bone Marrow - sustains and nurtures the bones, composed of Kidney Jing (Essence) and Marrow.

Book of Commentaries - consisting of ten commentaries from Confucius and his disciples,

Practice of Forming the Belt Channel

Ascending from the Pakuas

1. Sit up, back straight, shoulders relaxed, feet touching the floor. Hold the hands together, and touch the tongue to the palate.
2. Practice the Inner Smile, Fusion of the Five Elements, chanting, the collection points, fusing the energy into a pearl and the Creation Cycle of Cosmic Fusion. Continue with your practice of Cosmic Fusion by sending the energy through the three full Thrusting Channels (all the way down to the feet and up to the head.)
3. You are ready to begin forming the Belt Channel. First, form the four pakuas and a pearl. Gather the pearl at the cauldron, and bring it to the navel.



Fig. 8.2 *Moving the Thrusting Channels out of the Body.*

pertaining to the study of the eight trigrams, sixty-four hexagrams, and the Yi-Jing.

Book of Oracles - written by King Wen and the Duke of Zhou, pertaining to the study of the eight trigrams, sixty-four hexagrams, and the Yi-Jing.

Borborygmus - a gurgling, rumbling sound heard over the Large Intestine, caused by the passing of gas through the liquid contents of the intestines.

Borderline Personality Disorder - a psychological disorder characterized by a pervasive pattern of intense, unstable relationships, and an unstable self-image. Such patients suffer from chronic feelings of emptiness stemming from abandonment issues. They exhibit self-destructive behavior and transient paranoia, or dissociative symptoms.

Brain - pertaining to the Sea of Marrow issuing from the Kidneys that collects within the cranium.

Brain Tumor Point - Shihmien Point located on the heel of each foot.

Bronchial Asthma - asthma caused by a hypersensitivity to an allergen.

Bronchiectasis - chronic dilatation of a bronchus or bronchi, with a secondary infection (usually involving the lower portion of the Lungs).

Bronchitis - inflammation of mucous membrane of the bronchial tubes.

C

Caduceus - medical insignia picturing double snakes wrapping a winged staff.

Calculi - the plural of calculus or stones, usually composed of mineral salts.

Cancer - an obstruction of Qi and Blood circulation resulting in stagnation and the formation of a malignant tumor that tends to spread.

Carbuncle - a circumscribed inflammation of the skin and deeper tissues.

Carcinogens - any substance or agent that produces or increases the risk of developing cancer.

Carcinoma - a malignant growth or tumor that occurs in the epithelial tissue (the outer surface or first layer of tissue that lines the body's cavities, as well as the principal tubes and passageways leading to the exterior of the body)

Catatonic - totally withdrawn, almost unconscious, frozen and unable to move.

Celestial Stems - see Ten Celestial Stems.

Center Core - pertaining to either 1. The core of light within the Taiji Pole which joins the body's three Dantians through the center of the body, or 2. The True Self (the essence of a person's spirit).

Cerebral Embolism - a condition which occurs when an embolus (bubble of air, or piece of a thrombus) detaches from a thrombus and obstructs a cerebral artery.

Cerebral Hemorrhage - bleeding caused from a rupture of a sclerosed or diseased vessel in the brain.

Cerebral Thrombosis - an obstruction of a cerebral artery by a thrombus (blood clot).

Cerebro-Vascular Accident (CVA) - in the clinic, conditions referred to as stroke (or Wind-stroke) include cerebral hemorrhage, cerebral thrombosis, cerebral embolism, and cerebrovascular spasm. These four conditions are termed in Western Medicine as "Cerebro-Vascular Accident."

Cervical Spondylosis - a degenerative arthritis (osteoarthritis) of the cervical vertebrae and related tissues.

Chakra - an energetic vortex, spiraling out from the body's Taiji Pole, manifesting in the body and extending through the external field of Wei Qi.

Chakra Gates - the twelve major energy gates located on the center line of the anterior and posterior aspects of the body, as well as at the lower perineum and the top of the head.

Chakra System- the seven major Chakra or energy centers that connect to the Taiji Pole. Five Chakras extend to the front and back of the torso, with an additional one located at the top of the head and on the perineum.

Channels - the body's energetic rivers responsible for transporting Qi, also called "meridians."

Channel Points - areas or points (similar to small pools of Qi) found along the streams of a Channel, through which energy of the Yin and Yang (Zang / Fu) organs and channels are transported internally and externally.

Channel Qi - pertaining to the Qi found within the energetic flow of a channel.

Charts of the Hall of Light - ancient diagram depicting the body's internal organs and channels.

Chemotherapy - the application of chemical agents that have a specific and toxic effect upon the disease-causing microorganism, as well as the patient's tissues, energetic fields and immune system.

Chicken Pecking Palm Technique - a palm technique wherein the doctor's hand resembles the head of a chicken while manipulating the energy flow of the Invisible Needle.

Chi Dai - red vaginal discharge.

Child Element - pertaining to the Five Element Creative Cycle of Traditional Chinese Medical, the primary organ is considered the Mother and its sequential organ is considered the Child.

Chinese Massage and Tissue Regulation - one of the four branches of Traditional Chinese Medicine, which involves treating patients through the use of tissue manipulation, including Jie Gu Therapy for bone disorders, Tui Na Therapy for muscle disorders, Gua Sha Therapy for febrile diseases, An Mo therapy for internal organ disorders, and Jing Point Therapy for channel and internal organ regulation.

Cholecystitis - inflammation of the Gall Bladder.

Cholelithiasis - formation of calcium, i.e., bile stones in the Gall Bladder.

Cholestasis - an infection of the biliary tract.

Chronic - the long duration of a specific disease or condition, showing slow or little improvement.

Chronic Fatigue Syndrome - debilitating fatigue that is not the result of physical or mental exertion, and does not diminish by resting.

Chrono-biology - the science that deals with the study of the body's biological clocks and fluctuations in accordance with the cycles of the sun, moon and nature's rhythms.

Chyluria - the passing of fat globules in the urine.

Circle of Willis - the union of the anterior and posterior cerebral arteries, forming an anastomosis at the base of the brain.

Circulating Energy Technique - this method refers to rotating Qi in a circular pattern (clockwise or counterclockwise) to move Qi and Blood stagnation, or to gather energy for tonification.

Cirrhosis - Cirrhosis is a generalized Liver disease marked by hepatic lesions, characterized by the formation of dense lobular connective tissue, degenerative changes in the parenchymal cells, structural alterations in the Liver lobules, and sometimes fatty and cellular infiltration within the Liver.

Clairaudience - the ability to hear sounds, music, and voices not audible to normal hearing (for example, receiving Messages and / or inspirations from the divine).

Clairasentience - the ability to perceive smells, taste, touch, emotions and physical sensations that contribute to an overall psychic and intuitive impression.

Clairvoyance - the ability to perceive current objects, events and / or people that may not be discerned through the body's normal senses. Both time and space are perceived on a clairvoyant spiritual dimension.

Clean Qi - Energy which has been purified.

Clinical Ethics - the moral principles and standards governing the doctor's conduct with patients in or away from the clinic.

Coccyx Pass (Wei Lu Guan) - is located on the lowest segment of the spine just posterior to the anus, near the Chang Qiang (GV-1) point.

Colitis - the inflammation of the colon.

Cold Constitution - pertaining to a physical body innately prone towards coldness.

Collapsed Qi - this is considered a subcategory of Deficient Qi, and is regarded as the third and most severe type of Deficiency.

Collaterals (Luo) - the body's energetic streams that branch off the Twelve Primary Channels and the Conceptional and Governing Vessels.

Collective Unconsciousness - concept of psychiatrist Carl G. Jung pertaining to the memories of mental patterns that are experienced and shared by all mankind.

Coma - an abnormal deep state of unconsciousness with some possible awareness of surroundings, but a total inability to communicate with the outside environment. Comas result from a Qi obstruction to the brain caused by illness or injury.

Common People's Fire - pertaining to the Bladder Fire, located in the perineal area of the body.

Compressed Stagnation - stagnation caused by the patient's energy pressing downward (externally moving inward), feels armored and hollow.

Concentrative Meditation - keeping the mind focused and under control.

Congealed - when Qi and/or Blood become thick and solid within the body's tissues, energetic fields, or both.

Congenital Qi (Prenatal Qi) - energy existing before the fetus is born, acquired from the mother's, father's energies, as well as from the environmental and universal energies. It is sustained through prayer, meditation and sleep.

Conscious Mind - acquired mental reasoning, created through learning via the five senses and interactions with other people.

Constipation - difficulty or infrequent defecation, with the passage of unduly hard and dry fecal material.

Constitutions - see Five Elemental Constitutions.

Contracted Stagnation - stagnation caused by the patient's energy pulling inward, feels armored and solid.

Contraindications - any symptom or circumstance indicating the inappropriateness of a form of treatment that would be otherwise advisable.

Controlling Cycle - pertaining to the Five Element Cycle, where one organ controls the second elemental organ in the Five Elements' Circle.

Corporeal Soul - see Po.

Coryza - the inflammation of the respiratory mucous membranes.

Cosmology - the study of the universe.

Countertransference - this is the process whereby a doctor loses objectivity and unconsciously projects feelings, thoughts, beliefs and patterns of behavior onto the patient.

Couple Point - the Master Point's secondary point of connection affecting the Eight Extraordinary Vessels.

Cranio-Sacral Rhythm - Western term given to the fluctuating rhythm of the Sea of Marrow flowing from the Kidneys.

Creative Cycle - pertaining to the Five Element Cycle, where one organ creates the energy for the next.

Creative Subconscious Mind - the part of the mind that maintains the patient's reality by making him or her act like the person they believe themselves to be.

Creative Visualization - the process of using visualization as a tool for transforming energy and spirit.

Crown Center - the name given to the Baihui Point (GV-20) and Upper Chakra Gate, at the top of the head.

Crystal Palace - the energetic field of Qi located within the third ventricle of the brain.

Cupping - a technique used in acupuncture therapy in which wooden, clay, or glass cups are adhered to the patient's skin by suction, to drain or remove pathogenic Qi from the body's pores.

Curious Organs - the body's Six Extraordinary Yang Organs which function like Yin Organs as they store Yin Essence (i.e., Blood, Marrow, or Kidney Essence), but look like Yang Organs (because they are hollow). These organs consist of the uterus, brain, Marrow, bones, blood vessels and Gall Bladder.

Cycle of Disharmony - an emotional state which induces a vicious cycle of physical, mental, emotional, energetic and spiritual disharmony.

Cyst - a closed sac that forms in tissue or a body cavity.

Cystitis - inflammation of the Bladder, usually occurring secondary to ascending urinary tract infection.

Cytotoxic Treatments - treatment containing toxins which attack the cells of the body (for example: radiation and chemotherapy).

D

Dacryorrhea - excess tear flow.

Damp - a internal pathogenic condition relating to the storage of Damp or Wet toxins.

Dantians - the body's three main energetic pools, or reservoirs located in the head, chest and lower abdomen.

Dantian Regulation - the principle of balancing the energy governing the body's three main energetic pools (Dantians).

Dao - pertaining to God or divine consciousness.

Daoist - a student of the "Dao" or way of life, pertaining to living in harmony with the universe and environment.

Dao Yin - energy regulation exercises consisting of training the body, mind, and breath.

De - pertaining to an individual's personal Virtue.

Defence Mechanisms - see Ego Defence Mechanisms.

Deficiency - a condition relating to the inadequate degree of a particular substance, e.g., Qi, Blood, Yin, Yang, Heat, etc.

Delusions - refers to the occurrence of a mental derangement in the patient resulting in a false belief based on incorrect inference about external reality. Regardless of the evidence to the contrary, the belief is strongly maintained.

Demon or Spirit Oppression - the condition of having a foreign spirit attach to a patient's external Wei Qi field, resulting in emotional disharmony.

Demon or Spirit Possession - the condition of having a foreign spirit invade and inhabit the patient's body, mind, emotion, and spirit.

Denial - a conscious refusal of an impulse-evoking fact, feeling or memory.

Depersonalization Disorder - persistent, recurring episodes of depersonalization, characterized by a feeling of detachment, or estrangement from one's self.

Depression (Major) - a psychological disorder resulting in major sadness and pessimism, feelings of worthlessness, helplessness and hopelessness. Symptoms include overeating or under-eating, insomnia or hyper-insomnia, difficulty concentrating, and fatigue.

Descending - the action of energy moving downward.

Diabetes - a general term used to describe diseases characterized by excessive urination and a sugar imbalance in the Blood.

Diaphoresis - profuse sweating.

Diathermy - the therapeutic use of a high-frequency current to generate heat within a certain area of the body.

Di Qi - Earth (Environmental) Energy.

Disharmony - pertaining to a lack of adequate balance of energy.

Disorder - an abnormal state of physical, mental, emotional, energetic or spiritual disharmony.

Dispersing- the spreading of Qi to other parts of the body, or purging of pathogenic energy from the body.

Displacement - the shifting of impulses aroused by one person, or situation on to a safe target.

Dissociated Identity Disorder - new terminology used for multiple personality disorder.

Distance Therapy - also called External Qi Therapy, Qi Emission and Outgoing Qi Therapy, is defined as extending or projecting energy into a patient from a distance.

Divergent Channels - twelve secondary channels that parallel the Twelve Primary Channels.

Divine - pertaining to God.

Divine Center - referring to the North Star's stable position in the sky.

Divine Hook-Up - the Qigong doctor's initial preparation for therapy, wherein he or she connects with the divine for guidance.

Divine Therapy - long distance Qigong healing.

D.M.Q. - a licensed Doctor of Medical Qigong Therapy, presently only obtainable in China.

Dong - the Yang method of dynamic Postural Dao Yin training.

Dragon's Mouth Palm Technique - hand technique wherein the thumb touches the other four fingers of the hand, forming an image of the head of a dragon. This hand manipulation is used for leading and pulling the Qi.

Draining Qi - drawing off pathogenic energy from a specific organ area or channel of the patient's body.

Dredging - a type of energetic purging, used to clean the patient's energetic fields and channels.

Drilling Energy Technique - this method refers to rotating Qi in a spiraling pattern (clockwise or counterclockwise) to access the energy deep inside the patient's body.

Dryness - a internal pathogenic condition relating to the storage of Dry toxins.

Dynamic Qigong - energy gathering which utilizes active movements of the body.

Dysmenorrhea - painful menstruation.

Dyspepsia - painful digestion.

Dyspeptic - one afflicted with dyspepsia.

Dysphagia - difficulty in swallowing.

Dysphoria - exaggerated feeling of depression, anxiety and unrest.

Dysplasia - the abnormal development of tissue.

Dyspnea - air hunger, resulting in difficult breathing, shortness of breath, sometimes accompanied by pain.

Dysthymia - a chronic, form of depression (lasting at least two years), for children and adolescents the mood can be irritable rather than sad.

E

Earth Element - one of the Five Elements, pertaining to Spleen and Stomach.

Earth Energy (Qi) - Energy pertaining to the Earth and surrounding environment.

Earth Jing - energy that supervises the maturation phase of the fetus's ability for emotional and spiritual bonding during the seventh month of pregnancy.

Earthly Branches - twelve energies of the Earth represented in the human body as the Twelve Primary Channels.

Earth Transpersonal Point - pertaining to the body's energetic connection to the Earth, located several feet beneath the feet.

ECG (or EKG) Eletrocardiogram - a graphic record made by an instrument that measures the Heart's electrical activity; usually used to confirm a diagnosis of a Heart condition.

Eclampsia - coma and convulsive seizures (between the 20th week of pregnancy and first week postpartum). Symptoms result in edema of the legs and feet, puffiness of the face, hypertension, severe headaches, dizziness, epigastric pain, nausea, sudden convulsive seizures and coma.

Eczema - an acute or chronic inflammation of the skin.

Edema - an acute or chronic cutaneous inflammatory condition.

EEG Electroencephalogram - a graphic record made by an instrument that measures the brain's electrical activity and records it as patterns of fluctuating waves.

Ego - the ego is the mediator between the id and the superego. According to Dr. Sigmund Freud's psychoanalytical theory, the superego combines the critical inner parent aspect with the idealistic aspect of the individual's conscience; the id consists of unconscious drives and instincts. The ego as meditator is responsible for ensuring rational behavior.

Ego Defense Mechanisms - according to Dr. Sigmund Freud's psychoanalytical theory, the ego defence mechanisms include: Repression, Displacement, Projection, Intellectualization, Regression, Fixation, Denial, Reaction-Formation, and Sublimation.

Eight Confluential Points - the areas where the Eight Extraordinary Vessels and Twelve Primary Channels intersect with each other.

Eight Energetic Principles - a system of differential diagnosis using four pairs of opposites (Yin and Yang, Cold and Hot, Deficient and Excess, Internal and External).

Eight Energetic Touches - pertaining to the somatic tissue response to energy stimulation (tingling, sensations of heat, coldness, expansiveness, contracted, heaviness, lightness, and vibration).

Eight Extraordinary Vessels - the primary channels responsible for the formation of the fetus, which after birth, are considered the body's reservoirs for collecting the overflow energy from the Twelve Primary Channels.

Eight Miscellaneous Factors - eight factors that can off set the patient's Yin and Yang balance (diet, overexertion, excessive sex, child bearing, traumatic injuries, exposure to poisons, parasites, and iatrogenic disorders).

Eight Trigrams (Bagua) - eight cosmological patterns of three lines (solid and / or broken), called Yaos, used to diagnose as well as predict future transitions.

Emaciation - the state of being malnourished and extremely lean.

Embolus - the obstruction of a blood vessel by foreign substances or a blood clot.

EMG Electromyogram - a graphic record made by an instrument that measures the muscle's electrical activity and records its function.

Emitting Qi - the Qigong doctor extending energy outside the body for the purpose of treating a patient.

Emotional Energy Body - is the external energy existing in the body's second field of Wei Qi, which is attached to the internal organs.

Emotional Spirit - pertaining to the Emotional Energy Body.

Empathic Communication - the doctor's ability to experience the feelings and thoughts of his / her patients.

Empty Qi - a serious weakness or Deficiency of the body's Qi.

Encephalomyelitis - acute inflammation of the brain and spinal cord.

Endrometrial Hyperplasia - excessive proliferation of the cells within the lining of the uterus.

Energetic Armoring - a condition resulting from the patient protecting specific tissues, organs, or areas of the body. Energetic armoring is initiated when the patient freezes certain emotional feelings to maintain the denial system.

Energetic Barriers (Energetic Boundaries) - the protective barriers existing within and outside of the body's tissues.

Energetic Complications - pertaining to energetic imbalances within the patient's tissues (e.g., compressed energy stagnation, energetic armoring, migrating Qi deviations, etc.)

Energetic Cords - energetic bands of light and vibration which form an emotional attachment, connecting the patient to certain people, places, or things.

Energetic Grids - an energetic net covering the surface of Heaven , Earth or the human body.

Energetic Leakage - a condition resulting from the patient releasing Qi out of the joints, due to an injury or unconscious sabotage.

Energetic Medicine - any and all medicine having to do with the stimulation, cultivation, tonification, purgation, balance and maintenance of the body's Qi.

Energetic Point Therapy - extending energy from a distance into specific channel points, or vessels on the patient's body.

Enteric Nervous System - pertaining to the nervous system of the Small Intestine.

Enuresis - the involuntary discharge of urine.

Environmental Energy (Qi) - Energy pertaining to the Earth and surrounding environment.

Environmental Force - energy pertaining to the Earth and surrounding environment.

Epigastric Pain - pain in the region over the pit of the stomach.

Epileptiform - having the form of epilepsy.

Epistaxis - bleeding of the nose.

Epithelial Hyperplasia - excessive proliferation of the cells within the outer surface of the body, including the secreting portions of the glands and ducts.

Essence (Jing) - referring to either Prenatal and Postnatal energetic tissue mass.

Eternal Soul - the individual's True Self, which is always connected to the divine. It is absorbed into the mother's egg at the time of conception, and is rooted within the body's Taiji Pole.

Ethereal Matter - the body's foundational energetic substance.

Ethereal Souls - see Hun.

Etiology - the causes of a disease.

Eustachian Tubes - the auditory tube, extending from the middle ear to the pharynx.

Evil Embryo - pertaining to a toxic formation in the form of a tumor or cancer mass.

Evil Influences - pathogenic factors that can be either physical, mental, emotional, energetic or spiritual.

Evil Qi (Xie Qi) - also called Pathogenic Qi, Perverse Qi, Toxic Qi, and Heteropathic Qi, is energy that causes disease or harmful effects to the body.

Evil States - a condition wherein the patient experiences mental delusions, obsessions, infatuations with the doctor, spiritual oppression or possession.

Evil Wind - toxic wind that invades the body, tissues or organs.

Excess - a condition relating to the over abundance of a particular substance. (e.g., Heat, Wind, Damp, Cold, etc.).

Exopathogenic - a disease or pathogen originating outside of the body.

Extended Fan Palm Technique - hand technique where the fingers separate like a Chinese fan, used for extending energy through the doctor's palm.

External Pathogenic Factors - an external invasion of Heat, Damp, Cold, Dryness, or Wind, or a combination thereof.

External Qi Therapy - a technique used in Medical Qigong therapy which pertains to Qi being emitted onto a patient.

Extraordinary Organs - also called Curious Organs, these six organs are shaped like Yang (Hollow) organs but store Yin Essence. The brain stores Marrow, the Marrow stores Kidney Jing, the bones store Marrow, the blood vessels store the Blood, the Gall Bladder stores the bile, and the uterus stores Kidney Jing, Blood, and Qi.

Extraordinary Vessels - secondary channels that flow in conjunction with the body's Twelve Primary Channels.

Extra Point - a point with a definite location, but not originating on the fourteen main channels.

F

False Cold - a feverish sensation followed by a feeling of cold all over the body.

False Self - pertaining to the dark emotional side of the self, i.e., the masks and defence mechanisms that serve to protect the individual from dealing with his or her issues.

False Yang - a clinical condition where an overabundance of Cold (Yin) transforms into Heat (Yang).

False Yin - a clinical condition where an overabundance of Heat (Yang) transforms into Cold (Yin).

Fascia - a fibrous membrane covering, supporting, and separating the muscles, as well as uniting the skin with the body's underlying tissues.

Febrile Diseases - any and all diseases which cause the body to produce a fever.

Feng Shui - the study of harmonizing the energetic flow of Wind and Water, and the healing art of adjusting the person's environment to create improvements in the person's health and life.

Fetal Education - regulating the mother's behavior to improve her child's physical, emotional, and mental health is called "fetal education" in Traditional Chinese Medicine, and is important in the development of the child's Prenatal Essence, Energy, and Spirit.

Fetal Leakage - after conception, if a small amount of bloody fluid discharges from a woman's vagina, it is known as Tai Lou or fetal leakage.

Fibroadenoma - a tumor with fibrous tissue, forming a dense covering.

Fire Element - one of the Five Elements, pertaining to the Heart, Small Intestine, Pericardium, and Triple Burners.

Fire Jing - energy that controls the development phase of the fetus's emotional and spiritual well-being during the fifth month of pregnancy.

Five Agents - the five energies that are linked to the moral qualities of a person's inner characteristics (the five virtues stored within the body's Wood, Fire, Earth, Metal and Water elements).

Five Elements - Wood, Fire, Earth, Metal and Water.

Five Element Animals - Green Dragon, Red Phoenix, White Tiger, Dark Blue Turtle, and Yellow Phoenix.

Five Elemental Constitutions - physical constitutions based upon the observation of the Five Elemental formations within the human body.

Five Element Organs - the organs related to the Five Elements, including: Wood - Liver and Gall Bladder, Fire - Heart and Small Intestine (also included are the Pericardium and Triple Burners), Earth - Spleen and Stomach, Metal - Lungs and Large Intestine, Water - Kidneys and Bladder.

Five Energetic Fields - pertaining to the body's five levels of energy, including: 1. External Wei Qi Fields, 2. Internal Ying Qi Field, 3. Sea of

Blood, 4. Sea of Marrow, 5. Center Core of Light (Taiji Pole).

Five Flavors - also called the Five Tastes, are sour, bitter, sweet, pungent, and salty.

Five Major Yang (Fu) Organs - also called the Five Bowels, they are the body's five hollow organs: Gall Bladder, Small Intestine, Stomach, Large Intestine, and Bladder.

Five Major Yin (Zang) Organs - are the body's five solid organs: Liver, Heart, Spleen, Lungs and Kidneys.

Five Orbs - pertaining to the 5 Yin internal organs (Liver, Heart, Spleen, Lungs and Kidneys), their complete organ system, and the surrounding areas that they influence.

Five Palms Hot - a condition in which the patient feels a hot sensation in the palms and soles of the feet, accompanied by heat and agitation of the chest and/or head area.

Five Passes - five important gates on the Governing Vessel located at the coccyx, Mingmen, Shendao, occiput and Baihui, where energy tends to stagnate.

Five Portals of the Earthly Yin Gate - pertaining to the five points at the bottom of the perineum through which the Qi of Earth enters into the body.

Five Portals of the Heavenly Yang Gate - pertaining to the five points at the top of the head through which the Qi of Heaven enters into the body.

Five Sense Organs - eyes, tongue, mouth, nose and ears.

Five Thunder Fingers Technique - hand manipulation technique wherein the fingers and thumb are rapidly extended from a closed soft fist, to strike with Qi for dispersing stagnations.

Five Thrusting Channels - see Thrusting Channels.

Five Tissues - tendons, blood vessels, muscles, skin and bones.

Five Zhi - in connection with the five mental aspects of the Mind, the Hun (Ethereal Soul), Po (Corporeal Soul), the Shen (Spirit), the Yi (Intellect), and the Zhi (willpower) are sometimes referred to as the Five Zhi.

Fixation - has the same result as regression, but the person becomes fixated at a particular stage of mental and emotional development.

Flat Palm Detection - an extended palm technique used for sensing and diagnosing.

Four Bigs - pertaining to severe excess of fever, sweating, thirst, and pulse.

Four Doors - the center of each palm and foot.

Four Winds - pertaining to the Energy of the four compass points. (North - back, South - front, West - right, and East - left.)

Fu Organs - Yang or hollow organs (Gall Bladder, Small Intestine, Stomach, Large Intestine, and Bladder). The Fu Organs operate primarily to relieve the Zang (Yin) Organs of toxic energies and wastes.

G

Gallow's Syndrome - laughing at a very painful experience instead of grieving or crying.

Gastritis - the inflammation of the stomach.

Gastroptosis - the downward displacement of the stomach.

Gate of Access - the passageway between life and death, believed to be related to the stars of the Big Dipper.

Gate of the Moon - the western energetic region, which the sun must pass through in order to create Autumn.

Gathering the Immortal's Water - pertaining to the energetic production of the saliva or Juice of Jade to create the Immortal Pill.

Gathering Qi - also called Respiratory Qi, Collection Qi, Chest Qi, Pectoral Qi, and Big Qi of the Chest. It is derived from the conversion of the purest and most potent forms of the body's Jing (particularly sexual fluids, hormones, and neurochemicals).

Ghosts (Gui) - disembodied spirits.

Ghost Points - points used for the treatment of emotional and spiritual disorders.

Gland - an organ that produces a hormone or other secretion.

Golden Gate in the East - the eastern energetic region, which the sun must pass through in order to create spring.

Gong - meaning skill or study.

Gout - sudden intense pain in a joint, usually the big toe or ankle, followed by swelling, inflammation and heat in the joint (in extreme casts alternating chills and fever are experienced).

Grandmother Element - pertaining to the Five Element Creative Cycle of Traditional Chinese Medical, the primary organ is considered the Mother and its previous organ is considered the Grandmother.

Grain Qi (Gu Qi) - Energy derived from food and drink.

Grounding - see Rooting.

Gua Sha Therapy - an external "surface" tissue scraping technique commonly used to clear Excess Heat from the body.

Guiding Qi - the technique of leading Qi.

Gu Qi - Energy derived from food and drink.

Gui - ghosts or spirits.

H

Hai - means sea.

Healing Tones - resonant sounds used to purge the body of pathogens.

Heart Fire - pertaining to the energy of the Heart, which is responsible for transforming the body's Energy into Spirit. This occurs in the chamber of the Heart's courtyard (the Yellow Court).

Heaven Qi - also known as Heavenly Qi, this energy pertains to the Heavens, the divine and the celestial influences.

Heavenly Stems - the ten energies of Heaven represented in the human body as the Yin and Yang aspects of the Five Elements or ten major internal organs.

Heavenly Transpersonal Point - pertaining to the body's energetic connection to the Heavens, located two to five feet above the head.

Hei Xia - dark brown or black vaginal discharge.

Hemiparalysis - paralysis on one side of the body

Hemiplegia - paralysis on only one side of the body.

Hemoptysis - the expectoration of Blood.

Hepatitis - inflammation of the Liver.

Hepatolithiasis - calculi or concretions in the Liver.

Hepatomegaly - enlargement of the Liver.

Hepatosplenomegaly - the enlargement of both the Spleen and Liver.

Herbal Therapy - one of the four branches of Traditional Chinese Medicine, which involves treating patients through the use of formulas created through teas, soups, tinctures, wines, oils, balms, liniments and pills to stimulate energy flow.

Herbalist - a doctor of Herbal Therapy.

Herpes Simplex I - an infectious disease caused by the herpes simplex virus. This disease is characterized by thin-walled vesicles that occur in the skin, usually at a site where the mucus membranes joins the skin.

Hexagram - a six line symbol representing the function and flow of Yin and Yang energy, formed by stacking two trigrams on top of each other.

Hibernation Breathing - a breathing method which includes inhaling and exhaling through every pore on the body's surface, from the body's Center Core (Taiji Pole).

Hidden Power (An Jing) - techniques that emphasize stretching and twisting the tendons and ligaments (known as Reeling and Pulling the Silk) to cultivate resonant vibration within the body for striking and issuing power.

4. Join the four pakuas by circulating the pearl from the ***Navel*** toward the left side (counterclockwise), to the Door of Life, to the right side, and back to the navel.

   In the beginning you can use your hand to assist you in moving the pearl, although your goal is to use your senses to control its movement. Cover the navel with the right hand. Cover the left side pakua with the left hand. Then, move the left hand to cover the Door of Life, and move your right hand to cover the right side pakua. Finally, return the right hand to the navel.

   Circle the pearl nine times counterclockwise. As you are ascending you will circle it nine times counterclockwise from each point in a similar fashion.
5. When you finish circling the pakuas for nine rounds, be aware of the navel. Be aware of the channel of the navel. Form a cross by bringing the pearl from the navel to the cauldron, and all the way back to the Door of Life. Then, bring the pearl back to the cauldron, and use it to connect the side pakuas from the left cross to the right. Return the pearl to the navel.


Nose
Right Thrusting Channel
Back
12
Governor Channel
Middle Thrusting Channel
Right
9
3
Left
Left Thrusting Channel
6
Front
Functional Channel

Fig. 8.3 *Cosmic Belt Channels connecting to all the other Channels.*

Hollow Organs - the body's Yang organs, which consist of the Gall Bladder, Small Intestine, Stomach, Large Intestine, Bladder. Also included in this list are the Triple Burners.

Hologram - pertaining to the body's energetic three dimensional image.

Hook-Up - see divine Hook-Up.

Hostile Forces - dark spiritual forces which seek to influence the physical, mental, emotional, energetic and spiritual life of an individual.

Hot Constitution - pertaining to a physical body innately prone towards heat.

Hot Evil - also known as Evil Heat, a pathogenic condition causing Excess patterns that are Hot and Yang in nature.

Hou Tian Zhi Qi (Postnatal Qi) - translates to mean after the baby sees the Heavens.

Hua Jing - see Mysterious Power

Huang - any membranous tissue.

Hua Sound Resonation - Mysterious or Spiritual Sound Resonation.

Huang Dai - yellow vaginal discharge.

Hui Yin Point (CV-1) - Conception Vessel point located between the scrotum and the anal sphincter.

Human Force - the energy or force manifesting from inside of the human body, as well as the within the human energetic field.

Hun (Ethereal Soul) - the Three Ethereal Souls which are the spiritual part of man that ascends to Heaven upon the death of the body.

Hunter Killer Cells - the body's neutrophils and macrophages, as well as the interferons and antibodies.

Hun Yuan - the body's internal energies that has been combined and fused into the Lower Dantian area.

Hyperbilirubinemia - excessive amounts of bilirubin (the orange-colored or yellowish pigment in bile) in the Blood.

Hyperhidrosis - excessive sweating due to an over-activity of the sweat glands.

Hypertension - high blood pressure.

Hyperthyroidism - a condition caused by excessive secretions of the thyroid glands, resulting in an increased metabolic rate and the consumption of food to support this increased metabolic activity.

Hypertrophy - the increase in the size of an organ or structure that does not involve tumor formation.

Hypochondriac Pain - pain in the upper lateral region on each side of the body below the thorax and beneath the ribs.

Hyposmia - a deficient sense to smell.

Hypotension - low blood pressure.

I

I-Ching - see Yi-Jing

Id - Dr. Sigmund Freud's terminology for one of the three divisions of the psyche in Psychoanalytic Theory that is the unconscious source of psychic energy responsible for the body's drives and instincts.

Immortal's Pill - pertaining to the energetic production of Heaven and Earth Qi, in conjunction with the saliva.

Immortal's Water - when meditating, another word for energized saliva.

Incontinence - an inability to control urination, involuntary urination when coughing, laughing, sneezing, running, or performing some other physical activity. This condition can also refer to involuntary defecation.

Infatuations - refers to the patient feeling intensely amorous towards the doctor.

Influenza - an acute contagious respiratory infection, characterized by a sudden onset, with chills, fever and headache.

Inner-vision - the skill of observing images of the internal organs, and energetic fields relating to the body, mind, emotion and spirit, and their transition stages.

Insight Meditation - focusing on sensual stimuli (sounds, smells, colors, etc.) while meditating.

Insomnia - a sleeping disorder.

Insulting Cycle - pertaining to the Five Elemental Cycle, wherein the Child Element counter attacks the Grandmother Element.

Intellectualization - an elaborate rationalization of a naked impulse, to justify it.

Interferons - a group of proteins released by the white blood cells and fibroblasts, responsible for fighting infection.

Interjection - the insertion or interpose the energetic pattern.

Internal Dialogues - internal conversations, which are part of the patient's personal belief structure.

Internal Pathogenic Factors - pertaining to diseases originating from the body's internal organs and emotions (e.g., anger, fear, grief, worry, etc.).

Internal Viewing - technique used by the Qigong doctor to view the patient's internal organs.

Interpersonal Relationships - close personal relationships, relating to self and others.

Invading Cycle - pertaining to the Five Elemental Cycle, wherein the Grandmother Element overcontrols the Child Element.

Invisible Needle Therapy - the insertion of invisible energetic needles into the patient's body to stimulate energy flow.

Invisible Needle Palm Technique - Qi emission in which energy is emitted in a very fine line, to stimulate specific channel points.

J

Jaundice - a condition due to deposition of the bile, characterized by the yellowing of the skin, eyes, mucous membranes and Body Fluids.

Jia Ji Guan (Spinal Pass) - two points located on the lateral sides of the Mingmen (GV-4) where Qi can become stagnant.

Jie Gu Therapy - a tissue manipulation therapy that focuses on the adjustment of bones and ligaments.

Jin - thin Body Fluids.

Jing - the human body's Essence, divided into Prenatal and Postnatal Essence.

Jing Luo - the body's channels and collaterals.

Jing Point Therapy - the original term for Channel Point Therapy or Acupressure.

Jing Shen Bing - pertains to all types of mental illness.

Jiu Wei (Yellow Court) - located in the center of the diaphragm, below the xiphoid process of the sternum. Its function is that of being the access point to release emotional memories from the body's internal organs. Its location is also attributed to the 3rd Chakra.

Jue Yin (Reverting Yin) - associated with the most severe diseases, indicates Yin Qi developing its final stage and then reverting into Yang.

Juice of Jade - Energized saliva produced in meditation practices.

K

Karma - the manifestation of consequences to our actions and beliefs: "As you sew, so shall you reap."

Karmic Related Illness - pertaining to spiritual illnesses, which can be either congenital or acquired.

Ketheric Matter or Substance - pertaining to the spiritual energy located within the third external field of Wei Qi.

Kidney Fire (Mingmen Fire) - the energy that heats the body's Essence (Jing), and dominates all Twelve Primary Channels. It is the motivating force of the body.

Kinetic Communication - the intuition of the physical body, felt by the Qigong doctor as a movement in or of his or her own body.

Kneading Tiger Palm Technique - hand manipulation technique resembling the movement of a tiger kneading the ground, used for dispersing Qi stagnations.

Kyphotic - the exaggeration or angulation of the normal posterior curve of the spine (humpback).

L

Laogong - channel point located at the center of each palm.

Large Heaven Cycle (Macrocosmic Orbit) - Qigong Meditation which connects the Qi of the extremities to the Qi within the Governing and Conception Vessels.

Leading Qi - technique of manipulating the patient's Qi by using a guiding gesture with the hands.

Leukocyte - the body's white blood corpuscles, which included lymphocytes and other immune system cells.

Leukorrhea - an acute or chronic disease caused by the unregulated clonal proliferation of stem cells within the Blood forming tissues.

Ley Lines - the energetic pathways that connect energy spots on the planet.

Life Force Energy - Qi.

Light Energy Therapy - color, light projection and visualization used for healing.

Light of the Dao - divine healing light energy.

Lipid Bilayers - the outer membrane of most cells, includes two layers of lipid molecules.

Lithotripsy - crushing of a calculus in the bladder or urethra.

Liver Wind - terminology used to describe excess Heat generated from a toxic Liver condition which can cause pathogenic symptoms.

Lobular - composed of small lobes.

Lords of the Three Dantians - three spiritual energies used to describe the energetic aspects of the human soul (Tai Yi, Si Ming and Xia Tao Kang).

Lo Scroll (Magic Square) - a tool used for diagnosis and treatment of disorders through number configurations, which correspond to the Late-Heaven sequence of the Trigrams of the Yi-Jing (I-Ching).

Lower Burner - area of the body in the Lower Dantian, responsible for the separation of Clean and Dirty Fluids. It also facilitates the production of urine.

Lower Dantian - area in the center of the lower abdomen, attributed to the body's chamber of heat and physical power. The Lower Dantian is also known as the Sea of Energy, Pill of Immortality, Root of life, Source of Generating Qi, Five Qi Collection Seat, Progenitor of Life, Stove of Spirit, Root of Heaven, and Cinnabar Field.

Lower Unconsciousness - pertaining to the acquired mind which is connected to the primal senses.

Lumbago - dull, aching pain in the lumbar region of the lower back.

Luo - translated to mean a net or web, and in Traditional Chinese Medicine it refers to the Connecting Vessels, i.e., the Fifteen Collaterals. These vessels are the major "passage ways" for the circulation of the body's channel energy, emerging out of the Luo (pathway) points on the Twelve Primary Channels (plus the Governing and Conception Vessels).

Luo Points - are the major intersecting points of the Fifteen Collaterals. The Luo points are located below the elbows and knees and provide an additional energetic barrier to keep Evil Winds from affecting the Twelve Primary Channels, being somewhat deeper then the Muscle/Tendon Channels.

Lymphocytes - immune cells present in the Blood and lymphatic tissue.

Lymphoma - a group of malignant solid tumors of the lymphoid tissue.

Lymphosarcoma - a sarcoma of the lymphatic system.

M

Macrocosmic Orbit - Qigong Meditation which connects the Qi of the Governing and Conception Vessels with the extremities of the body.

Macrophages - the major phagocytic cells of the immune system (also known as Hunter Killer Cells).

Magic Square - also known as the Lo Scroll, a tool used for diagnosis and treatment of disorders through number configurations corresponding to the Late-Heaven sequence of the trigrams of the Yi-Jing (I-Ching).

Magnetic Energy Therapy - magnetic energy affecting the body's channels and points via electromagnetic field stimulation.

Malar Flushes - pertaining to flushed skin along the cheeks.

Malignant - detrimental; growing worse; threatening to produce death.

Man Qi - general term used to describe the energy relating to the body, mind, emotion, energy and spirit of both men and women. In the body, the area between the navel and the lower sternum correspond to "Man."

Manic Depressive Personality Disorder - see Bipolar Personality Disorder

Mantra - a Sanskrit word, meaning a spiritual phase or sound repeated internally or externally, used as a tool in meditation to induce an altered state of consciousness.

Marrow - derived from the Kidneys, nourishes the brain, spinal cord and forms the bone marrow.

Master Point - the main point of energy interaction on a specific channel, used to affect another organ system or channel energy flow.

Mastitis - inflammation of the breast.

Medical Qigong - one of the four branches of Traditional Chinese Medicine.

Menorrhagia - excessive bleeding during the time of menstruation.

Menoxenia - the pathological changes of menstruation occurring in a woman's cycle, affecting the color, quantity and quality of Blood flow.

Mental Delusions - the occurrence of mental derangement in the patient resulting from a false belief based on an incorrect inference regarding external reality. This belief is firmly sustained despite incontrovertible evidence to the contrary.

Meridians - the body's channels or rivers of Energy.

Message (Xin Xi) - knowledge stored within the Wuji or the Void.

Metal Element - one of the Five Elements, relating to the Lungs and Large Intestine.

Metal Jing - Energy that supervises the development phase of the fetus's ability for emotional attachment and bonding during the sixth month of pregnancy.

Metrorrhagia - bleeding from the uterus.

Microcosmic Orbit - energetic orbits that circulate the Qi within the body's energetic channels; divided into Fire, Water and Wind pathways.

Micturition - discharging urine.

Middle Burner - area of the body pertaining to the body's digestive system, responsible for transporting Gu Qi (derived from food and drink).

Middle Dantian - area in the center of the chest, attributed to the body's chamber of emotional and vibrational power. The Qi of the Middle Dantian is called Zong Qi. Zong Qi is translated as Gathering Qi, Ancestral Qi, Genetic Qi, or Essential Qi. The Middle Dantian is also known as Middle Field of Elixir, Scarlet Palace, Central Altar, Middle Sea of Energy, Courtyard of the Heart, Opening of Suspended Gold, and the Seat of Emotion.

Middle Emotional/Mental Barrier - the second and middle energetic barrier of the Wei Qi fields.

Mind Regulation - the principles governing the conduct, action or functions of the mind.

Ming Jing - see Obvious Power.

Mingmen (Gate Of Life) - area responsible for heating the body, in particular the Kidneys and Lower Dantian.

Mingmen Fire (also known as Kidney Fire, Advisor Fire, or Ministerial Fire,) - the Energy that heats the body's Essence (Jing), and dominates all Twelve Primary Channels. It is the motivating force of the body.

Ming Sound Resonation - Obvious or Audible Sound Resonation.

Ministerial Fire - pertaining to the Energy responsible for heating the Middle Burner.

Moon Cream - energy gathered during meditation from the moon's Essence in the form of cool light.

Morphogenic Field - pertaining to the form of the energetic field of Jing.

Mother and Child Therapy - the Traditional Chinese Medical description of the primary organ (Mother) and its sequential organ (Child) in the Five Elemental Creative Cycle.

Mother Element - pertaining to the Five Element Creative Cycle, the primary organ is considered the "mother."

Moxa Therapy - herb heated and applied in a clinical setting for tonification.

Multiple Personality Disorder - also called Identity Disorder, is a mental state in which the patient develops "alter" personalities as a coping mechanism in dealing with severe emotional traumas.

Multiple-Sclerosis (MS) - an inflammatory disease of the central nervous system in which infiltrating lymphocytes degrade the myelin sheath of nerves.

Muscle/Tendon Channels - channel connections to the body's muscles, tendons, ligaments and other connective tissues.

Myalgic Encephalomyelitis - acute inflammation of the brain and spinal cord.

Myocarditis - the inflammation of the cardiac muscle (located in the middle layer of the walls of the heart).

Myoma - a uterine tumor that is a solid benign growth in the myometrium, often called a fibroid, containing muscle tissue.

Myophagism - a condition where the macrophages destroy (eats) muscular tissue.

Mysterious Pass - the space between Yin and Yang where infinite space and time (Wuji) exists.

Mysterious Power (Hua Jing) - techniques which emphasize training and conditioning the mind's imagination and intention, to project and utilize the power of the individual's Shen (Spirit).

N

Necrosis - part of an area of tissues or bone that is dying or dead and may spread to healthy tissues or bones.

Nei Dan Shu - internal elixir cultivation, that focuses on cultivating Qi from within the individual's body.

Nei Gong (Internal Skill) - the training of the body's tendons, bone, breath, mind, emotion, and spirit to facilitate internal power.

Nei Guan (Internal Viewing) - see inner vision.

Nei Jing - the Yellow Emperor's classics on Chinese internal medicine.

Neoplasm - a new or abnormal formation of tissue, as in a tumor growth.

Nephritis - inflammation of the Kidneys.

Neurasthenia - unexplained chronic fatigue and lassitude.

Neutrophils - the most common type of granulocytic white blood cell, responsible for fighting infection.

Nine Dantian Chambers - the nine internal cavities established within the energetic matrix of each Dantian.

Nine Palaces - the Later-Heaven sequence of the Trigrams of the Yi-Jing (I-Ching), represented in the human body as the Eight Extraordinary Vessels and the Taiji Pole.

Nine Star System - pertaining to the total development of the three periods of life and the three star developmental sequence.

Noxious Qi (Turbid Qi) - coarse, Toxic, Evil, unrefined, polluted, or dirty Energy.

O

Objective World - pertaining to the spiritual world existing outside an individual's thoughts or feelings.

Obstructed Qi - Energy that is immobile.

Obstruction - the inhibition of the flow of Qi or Blood, caused by Cold, Damp, Heat and Wind, etc.

Obvious Power (Ming Jing) - techniques that emphasize the training and conditioning of the muscles, strengthening the bone structure, and increasing the individual's overall stamina. This school also includes such techniques as pounding the body (arms, hands, legs, and torso) to strengthen and toughen the tissues.

Occipital Pass (Yu Zhen Guan) - the area located just inferior to the occipital bone where the brain originates (according to energetic embryology), known as a specific point where Qi often stagnates.

Oliguria - diminished amount of urine formation.

Omniscient Sight - the ability to see 360 degrees simultaneously.

One Finger Skill Technique - clinical modality involving Energy extension employed through a single finger.

Ontology - the study of the historical development of an individual.

Opening and Closing - the method of leading Qi into and out of specific internal organs, the Triple Burners areas, or one of the Three Dantians, via the hands.

Opisthotonosis - a form of spasm in which the patient's head and heels are bent backwards, and the body is bowed forward.

Organ Dysfunction - the impaired or abnormal function of an internal organ.

Organ Regulation - technique for balancing the action or functional principles of the internal organs.

Organ Qi - Energy of the body's Yin and Yang organs.

Original Spirit (Yuan Shen)- see Prenatal Spirit

Original Qi (Yuan Qi) - pertaining to the body's Prenatal Qi acquired from both parents at conception, and from the mother during gestation.

Original Force - pertaining to the Heavenly energy, manifesting as the energy of the entire cosmos.

Original Yang - pertaining to the body's Prenatal Kidney Yang.

Original Yin - pertaining to the body's Prenatal Kidney Yin.

Osteoarthritis - a chronic disease involving the joints and the deterioration of the articular cartilage.

Osteoporosis - a general term used for describing any disease process that results in the reduction of bone mass.

Osteosarcoma - a sarcoma of the bones.

Outer Spiritual Barrier - the third and furthermost energetic barrier of the Wei Qi fields.

Overcontrolling Cycle - pertaining to one of the Five Elemental Cycles, where one organ overcontrols the second elemental organ in the Five Elements' Circle.

P

Palace of Eternal Frost - the northern energetic region, which the sun must pass through in order to create winter.

Palace of Universal Yang - the southern energetic region, which the sun must pass through in order to create summer.

Palpitations - an abnormal rapid, throbbing, or fluttering of the Heart.

Pancreatitis - inflammation of the pancreas.

Panic Attack - overwhelming panic and sense of impending doom, resulting in hyperventilation (breathlessness), heart palpitations and visual distortions.

Papillary Masses - small, nipple-like protuberances or elevated tissue masses.

Paraplegia - paralysis on both sides of the body.

Parenchymal Cells - the essential parts of an organ's cells that are concerned with the organ's function.

Parkinson's Disease - a chronic nervous disease characterized by muscular weakness, rigidity and a fine, slow tremor.

Past Life Regression - pertaining to the patient's exploration and experiences of previous lives.

Pathogenic - disease-causing; see Internal Pathogenic Factors and External Pathogenic Factors.

Penetrating Wind - pertaining to the external pathogen of Wind invading the tissues.

Peribronchial - surrounding the windpipe (bronchus).

Perineural Cells - the sheath of cells around a bundle of nerve fibers within the perineurium.

Peristalsis - a progressive wave like movement that occurs involuntarily in the hollow tubes of the body.

Peritonitis - inflammation of the abdominal cavity.

Pernicious Influences - pertaining to the Six External Factors that cause disease.

Personal Subconscious Mind - part of the mind associated with the recording and storing of personal interpretations of reality.

Peyer's Patch - an aggregation of lympth nodes found chiefly in the ilium.

Phagocytes - cells that have the ability to destroy and ingest bacteria, protozoa, unhealthy cells and cell debris.

Phantom Embryo - an energetic thought form in the shape of an embryo created through the woman's feelings of grief, guilt or remorse after a surgical abortion.

Phantom Organ - the energy of a particular organ which still exists, even after surgical removal.

Phantom Pain - the feeling of pain relating to a particular organ which still energetically exists, even after surgical removal.

Phlegm - pathogenic factor responsible for the formation of diseases including tumors.

Physical Barrier - the first level and closest to the body of the three Wei Qi energetic barriers.

Piezoelectric - pertaining to the electricity created from pressure, especially pressure on or within the bones.

Po (Seven Corporeal Souls) - sometimes called the Seven Turbid Demon Natures, this spiritual energy manifests as the physical or material soul of the human body that returns to the Earth at death.

Points - specific areas on the body where energy can intersect to travel externally to internally, or visa versa.

Point Respiration - exercise which requires breathing into a specific channel point, organ, or area of the body.

Polarity - opposite negative and positive qualities of power.

Polergeists - malevolent spiritual entities. Parapsychology research indicates that poltergeist activity is often the manifestation of a psychokinetic ability.

Polydipsia - excessive thirst.

Polyphagia - eating abnormally large amounts of food at a meal.

Polyuria - the excessive secretion and discharge of urine.

Portal Hypertension - the increased pressure in the portal vein resulting from an obstruction of the Blood flow through the Liver.

Postnatal Energy (Postheaven Qi) - sometimes called the Acquired Qi, it is the Energy acquired after birth from food, drink, and air.

Postnatal Essence (Postheaven Jing) - sometimes called the Acquired Essence, it is the Essence acquired after birth from food, air and drink.

Postnatal Spirit (Zhi Shen) - also called the body's Mental Spirit, Acquired Spirit, and Conscious Spirit. This spiritual essence is acquired after birth through the refinement of one's Qi.

Post Traumatic Stress Disorder - characterized by the reexperiencing of an extremely traumatic event or events, accompanied by symptoms of increased arousal, and by avoidance of stimuli associated with the traumas. This includes the general numbing of the patient's emotional responsiveness.

Prenatal Energy (Yuan Qi) - sometimes referred to as Congenital Qi, Pre-Heaven Qi, Inherited Qi, Source Qi, Ancestral Qi, Primordial Qi, Genuine Qi, and Kidney Qi. It is Energy existing before the fetus is born, acquired from the mother's, father's, environmental and universal energies, and sustained through prayer, meditation and sleep.

Prenatal Essence (Yuan Jing)- also called Preheavenly Essence, Original Essence, Inherited Essence, Congenital Essence, Primordial Essence, and Ancestral Essence. It is the Original Essence existing before the fetus is born, acquired from the mother and father.

Prenatal Spirit (Yuan Shen) - also called the Intuitive Spirit, Perceptual Spirit, Primordial Spirit, Congenital Spirit, and the Original Subconscious. It is the Spirit essence existing before the fetus is born, acquired from fusing the mother's, father's, environmental and universal energies. The Prenatal Spirit also relates to the individual's ability to perceive and intuit information.

Prescriptions - directions given to the patient with regard to the manner of Medical Qigong exercises and meditations that must be practise after the initial Medical Qigong treatment.

Primal Senses - pertaining to the gross physical, animalistic survival senses (seeing, hearing, feeling, smelling, etc.).

Primary Channels - the body's twelve main channels, containing six Yin and six Yang rivers of Energy.

Primary Posture - the main posture, in a series of Medical Qigong prescriptions, that the patient focuses on.

Primitive Unconsciousness (Lower Unconsciousness) - pertaining to the acquired mind and related to the primal senses.

Projection - the attribution of unacceptable impulses within oneself to other people.

Proliferative Arthritis - the rapid reproduction and growth of arthritis.

Prostatitis - the inflammation of the prostate.

Protective Qi (Wei Qi) - the body's external field of defensive, protective energy (divided into three external fields of Qi).

Pruritus - severe itching.

Psychogenic - a condition developed from the beliefs originating within the mind.

Psychogenic Polyuria - pertaining to the belief that one must frequently secrete and discharge urine.

Psychometry - the act of sensing the thoughts, images and so on, with which the object has been imprinted.

Psychoneurosis - emotional disfunction caused from unresolved unconscious conflicts.

Psychosexual Qi Deviation - a condition resulting from an immediate energetic tissue overstimulation of the sexual organs. Patients with this condition experience intense sexual undulations and orgasms when being treated in a safe clinical environment.

Psychosomatic - pertaining to the relationship between the physical tissues and the emotions.

Pulling Down the Heavens - an opening and closing meditation used to energize and clear the body from the top of the head to the bottom of the feet, with breath, mind and hand movements.

Pulmonary Emphysema - a chronic disease of the lungs characterized by a destructive increase in the normal size of air spaces distal to the terminal bronchiole.

Purpura - a condition characterized by hemorrhages of the internal organs, skin, mucous membranes and other tissues, with various manifestations and diverse causes.

Purgation (Purging) - technique used in order to reduce Excess and expel pathogenic Evils located within the energetic fields and tissues of the body.

Pyelonephritis - the inflammation of the Kidneys and pelvis.

Q

Qi - is the energetic medium existing between matter and spirit (also known as Life Force Energy, when pertaining to the physical body).

Qi Collapse - pertaining to the complete absence (void) of either Yin or Yang Qi.

Qi Compression - using the Qi to press the tissues.

Qi Deviations - an alteration of energetic patterns and flow of energy that affects the body, mind, emotion and spirit, resulting in disease.

Qi Dysfunction - the impaired or abnormal function of the body's energy.

Qi Extension - the emission of energy from the body.

Qigong - Energy Skill, pertaining to exercises that cultivate Life Force Energy. There are three primary schools of Qigong training - Martial, Medical and Spiritual.

Qigong Clinic - a facility for diagnosis and treatment of outpatients with Medical Qigong therapy.

Qigong Doctor - in China, a person who medically treats patients for mental or physical disorders using Qi.

Qigong Massage - soft tissue regulation wherein the Doctor's hand lightly skims the patient's body. This gentle surface tissue stimulation is used to energize, stimulate or dredge the patient's Wei Qi fields. It is used with purging and tonifying techniques.

Qigong Therapy - one of the four branches of Traditional Chinese Medicine, which involves treating patients through the use of Energetic Point Therapy, Qigong Massage, Distance Therapy, Self-Regulation Therapy, and Invisible Needle Therapy, to stimulate energy flow.

Qigong Therapist - in America, a person who medically treats patients for mental or physical disorders using Qi.

Qi Hai - Sea of Qi point (CV-6).

Qi Manipulations - techniques used to treat or influence the flow of energy in the body.

Qing Dai - green-blue vaginal discharge.

Qi Projection (Qi Extension) - the emission of energy from the body.

Qi Regulation - energetically balancing the action or functions of the body's Yin and Yang energies.

Qi Stasis - the total stagnation of energy.

Quiescent - a meditative state wherein the individual's mind and body becomes quiet and peaceful.

R

Rachialgia - spinal inflammation.

Reaction-Formation - the conversion of one feeling into its opposite, typically seen in love turning into hate.

Rebellious Qi - energy that does not follow the correct flow or current, acting recklessly.

Reconstructive Qi Therapy - pertaining to the reconstruction and energizing of the body's energetic fields and organ systems (especially after surgery).

Reducing Qi - to lessen or decrease an organ or channel's energy.

Reflexology - the skill of pressing specific areas of the body's hands and feet to initiate internal energetic movement.

Regression - the return to an earlier childhood stage of behavior to reduce the demands on the ego.

Regulating - pertaining to the balancing of the body's Yin and Yang Energies.

Reinforcing Qi - to strengthen and support the body's organ or channel Energy.

Repression - the pushing down of unwanted ideas and emotions into the unconscious.

Respiratory Qi - Energy of the chest.

Restrictive Cycle - pertaining to the Five Elemental Controlling Cycle, where one organ restricts the energy of another organ (as depicted in the pentagram drawing).

Retrobulbar Neuritis - inflammation of the nerves behind the eyeball.

Returning To The Origin - see Rooting the Lower Dantian.

Reverse Breathing - opposite of abdominal breathing, wherein the patient will contract the abdomen with the inhalation, and expand the abdomen with the exhalation.

Rhabdomyosarcoma - a sarcoma of the muscles.

Rheumatic - pertaining to an rheumatism (a general term used to describe an acute or chronic condition characterized by inflammation, soreness and stiffness of the muscles, and pain in the joints and associated structures.

Rheumatoid Arthritis - a form of arthritis, characterized by inflammation of the joints, swelling, stiffness, cartilaginous hypertrophy, and pain.

Rheumatoid Spondylitis - a chronic, progressive disease, characterized by inflammation of the joints between the articular processes, costovertebral joints, and sacroiliac joints.

Rheumatosis - an acute or chronic condition characterized by inflammation, soreness and stiffness of the muscles, and pain in the joints.

Rhinitis - the inflammation of the nasal mucosa.

Righteous Qi (Zheng Qi) - is also called Upright Qi and Correct Qi. It is energy that heals the body and fights diseases.

Rigor - a sudden, chill with high temperature, followed by heat and profuse perspiration. Can also be referred to a state of hardness and stiffness, as in the muscles.

Root - the original cause of a disease; or to energetically secure into the Earth by extending the body's Energy deep into the ground, as if growing tree roots.

Rooting - the process of extending the body's Qi into the Earth to either establish a solid energetic foundation, or if need be, disperse Toxic Qi.

Rooting the Lower Dantian (Returning to the Origin) - returning the body's collected Qi back into the Lower Dantian.

S

San Bao (Three Treasures of Man) - pertaining to Jing (Essence), Qi (Energy) and Shen (Spirit).

San Jiao (Triple Burners) - corresponding to three main body cavities, responsible for heating the body and transporting the Body Fluids.

Sarcoma - a malignant growth, or tumor, that occurs within the connective or mesenchymal tissue. It may affect the muscles, bones, fat, blood vessels, lymph system, Kidneys, Bladder, Liver, Lungs, Spleen, and/or parotid glands.

Schizophrenia - a mental disorder, that induces hallucinations - usually auditory - through can also be visual, accompanied by very disordered thinking, delusions, disorganized

6. Move the pearl up from the navel to the left side of the rib cage to a position level with the ***Solar Plexus***. Begin to circle the pearl at the solar plexus level. Circle the pearl toward the left through T-11 at the back, to the right, and return to the solar plexus. Circle nine times, ending with the pearl at the solar plexus. Take a moment to perceive it. Then create an internal cross with the pearl, moving it from front to back, and then from left to right.
7. Bring the pearl from the solar plexus to the left side rib cage, this time at the level of the ***Heart***. Circle nine times toward the left to the middle of the shoulder blades, to the right, and back to the heart center. Circle in this manner for nine rounds. Using the pearl, form an internal cross connecting all four sides. Feel the connection of the channel.
8. From the heart center, bring the pearl up to the left side of ***Throat Center*** on the neck. Circle the pearl toward the left and back to C-7, to the right side, and to the middle of the throat center nine times. Use the pearl to form an internal cross connecting all four sides. Practice and master this step before continuing up to the crown.



Fig. 8.4 *Bring the pearl up to the upper tip of the left ear.*

speech, irrational or catatonic behavior, such as stupor, rigidity, or flaccid movement of the limbs. The ability to interact with others is greatly impaired.

Sclera - a tough white fibrous tissue that covers the white of the eyes.

Sea of Blood (Sea of the Twelve Channels) - pertaining to the Energy located in the Thrusting Vessel.

Sea of Energy - Energy located in the Lower Dantian, or Qi Hai area.

Sea of Grain and Water (Sea of Nourishment) - pertaining to the Energy located in the Stomach.

Sea of Marrow - pertaining to the Energy flowing in the spinal column and brain, originating from the Kidneys.

Sea of Qi - the chest center. Some Medical Qigong schools maintain that there are two reservoirs of Qi: the Middle Dantian, being the Sea of Postnatal Qi, and the Lower Dantian, being the Sea of Prenatal Qi (which is regulated by the Qihai CV-6 point).

Sea of Yang Channels - pertaining to the Governing Vessel.

Sea of Yin Channels - pertaining to the Conception Vessel.

Self Regulation Therapy - pertaining to the patient's Qigong prescriptions (meditations and/or exercises).

Seven Emotions - see Seven Internal Factors.

Seven Essential Stars - the Sun, Moon, Mars, Venus, Mercury, Saturn and Jupiter, associated with the body's seven orifices.

Seven Internal Factors - pertaining to the seven emotional pathogenic factors that cause disease, when in an Excess condition (Joy, Sorrow, Worry, Grief, Fear, Fright, and Anger).

Seven Material Souls - pertaining to the seven Earthly spirits that reside in the body as the Po.

Seven Orifices - ears, eyes, nostrils, mouth, anus and urethra, which are considered the gates and windows of Essence, Energy and Spirit.

Seven Turbid Demon Natures - see Po.

Shaman - an ancient Tungus term meaning "between the worlds." A Shaman is a tribal priest or priestess who heals the physical, mental, emotional, energetic and spiritual aspects of the patient.

Shao Yang - Small Yang, also called Lesser Yang, Minor Yang, or Young Yang, is affiliated with the sunrise and the waxing-moon phase. Modern physicists associate the Lesser Yang with a light force and electromagnetism.

Shao Yin - Small Yin, also called Lesser Yin, Minor Yin, or Young Yin, is affiliated with the sunset and the waning-moon phase. Modern physicists associate the Lesser Yin with a heavy force, and gravity.

Shen - meaning Spirit; when speaking about physical development, it is derived from Qi, and can be divided into both Prenatal and Postnatal Shen.

Shen Deviations - mental and emotional disorders which have caused the Three Ethereal Souls (Hun) to leave the patient's body.

Shengong - training of the spirit through meditation and visualization.

Shening Out - terminology used to describe the Ethereal Soul (Hun) wandering away from the body.

Shi Qi (Turbid Qi) - also known as Evil Qi, Toxic Qi, and Pathogenic Qi, it is coarse, unrefined, polluted or dirty energy.

Sishencong (Four Alert Spirit) Points - four points at the top of the head (that surround the Baihui Point) used to absorb Heavenly Qi into the body.

Shou Zhen (Hand Diagnosis) - a form of diagnosis, wherein, the doctor assess the "energetic blueprint" of the patient's body transformed onto the doctor's left hand.

Shu Points - five specific points below the elbows and knees identified as the Well, Spring, Stream, River and Sea points. Each point has an affect on the quantity of the energy of an organ.

Sishencong (Four Spirit Hearings) Points - a group of four points located at the top of the head (surrounding the Baihui point), used for absorbing Heavenly Qi into the body's Taiji Pole.

Six External Factors - also known as the Six Pernicious Influences, these factors pertain to the six climatic changes (Wind, Summer Heat, Heat, Damp, Dryness, Cold, and Fire).

Six Storage Areas- body's Yang organs constantly fill and empty, and include the Bladder, Gall Bladder, Stomach, Large Intestine, Small Intestine, and Triple Burners.

Skin Zones - twelve dermal-zones, based upon the surface location of the body's Twelve Primary Channels.

Soaring Dragon Technique - hand technique for Qi emission, where the energy is emitted through the middle finger bent and pointing downward, while the other fingers are extended straight outwards.

Solid Organs - the body's Yin organs, which include the Liver, Heart, Spleen, Lungs, and Kidneys (also included in this list is the Pericardium).

Soul - immaterial Spiritual Essence of an individual's life, stored within the Heart and Middle Dantian.

Soul Body- see Astral Body.

Soul Extensions - the Shen develops and contains Twelve Soul Extensions. These Twelve Soul Extensions contain the body's different personality characteristics.

Soul Loss - the loss of parts of the Eternal Soul.

Soul Retrieval - to spiritually search for and bring back one's forgotten memories (soul), which have been isolated from consciousness due to trauma and shock.

Soul Travel - see Astral Travel.

Sound Energy Therapy - sound projected as audible and inaudible tone resonation, used for healing.

Sound Resonation - healing tones used for tonifying or dispersing the patient's Energy.

Spider Nevus - a branched growth of dilated capillaries on the skin, that resemble a spider.

Spinal Pass (Jia Ji Guan) - two points located on the lateral sides of the Mingmen (GV-4), where energy has a potential to stagnate.

Spinous Process - the single midline posterior projection arising at the junction of each vertebra.

Spiraling Energy Technique - hand manipulation, that extends and spirals the doctor's projected energy.

Spirit - the energetic manifestation of the Eternal Soul.

Spirit Body - the energetic vehicle inwhich the body's Shen can travel throughout the Astral Plane. The Spirit Body can manifest through many forms (Body of Light, animal forms, etc.).

Spirit Demons - see Demon Possession and Oppression.

Spirit Soul - the Three Ethereal Souls, accompanied by the individual's consciousness, acting as one unit for spirit travel.

Spirit Travel - the spirit (Hun) journeying outside of the physical body.

Splenomegaly - the enlargement of the Spleen.

Squamous Metaplasia - the conversion of tissue into a form of scalelike cells, that is abnormal for that tissue.

Stacking the Bones - allowing the bones to stack upon each other from the bottom of the feet to the top of the head.

Stagnation - not moving, inactive; pertaining to Qi, Blood, or thought patterns.

Static Qigong - the process of stationary, quiescent Energy gathering.

Stroke (Wind Stroke) - caused by the buildup of Excess Liver Fire creating Internal Wind.

This Internal Wind causes Qi and Blood to rebel upwards causing Phlegm to form and obstruct the cavities and vessels, creating Penetrating Wind or Stroke.

Subarachnoid Hemorrhage - bleeding internally, within the spaces at the base of the brain, between the pia proper and arachnoid contain the cerebrospinal fluid.

Subconscious Mind - part of the mind associated with the recording and storing of personal interpretations of reality (not readily accessible to the conscious mind).

Sublimation - the channeling of unacceptable impulses into acceptable, refined social forms and is the only defence mechanism considered to be a healthy reaction.

Substances - pertaining to the body's essential parts of physical and energetic material.

Sui - Marrow.

Super Ego - Dr. Sigmund Freud's terminology for the division of the psyche in psychoanalytic theory, responsible for the psychic reward and punishment system.

Sun's Essence - energy gathered from the sun, ingested as warm light.

Sword Fingers Technique - hand manipulation that emits Qi through the extended index and middle fingers.

Symptoms - a subjective manifestation of a pathological condition, reported by the patient.

Syndromes - a grouping of signs and symptoms, based on their frequent reoccurrence, that may suggest a common underlying pathogenesis.

Systemic - affecting the entire body.

T

Taiji Pole - the Center Core of light which joins the body's three Dantians and the Eternal Soul together.

Tai Yang - Great Yang, also called Strong Yang, Major Yang, or Old Yang, is affiliated with high noon and the full-moon phase. Modern physicists associate the Strong Yang with a strong nuclear force.

Tai Yi - meaning Great Divinity or God.

Tai Yin - Great Yin, also called Strong Yin, Major Yin, or Old Yin, is affiliated with midnight and the new-moon phase. Modern physicists associate the Great Yin with a weak nuclear force.

Ten Heavenly Stems - the ten energies of Heaven that rule the changes of the Five Elemental seasonal transitions, and are represented in the human body as the Yin and Yang aspect of the Five Elements (represented in the human body as the ten major internal organs).

Ten Thousand Voices - pertaining to the state of open receptivity of the Qigong doctor's Heart, after rooting the mind.

Ten Wings - consisting of ten commentaries from Confucius and his disciples, pertaining to the study of the eight trigrams, sixty-four hexagrams, and the Yi-Jing.

Third Eye Point (Yin Tang) - located in the center of the forehead, responsible for spiritual intuition and communication.

Thought-forms - images of concentrated thought patterns that manifest on the vibrational resonance of the Astral Plane.

Three Ethereal Souls (Hun) - pertaining to the three heavenly spirits that reside in the body.

Three Fires - the heat in the body, generated from the energy radiating from the Heart Fire, Kidney Fire, and Bladder Fire.

Three Outer Forces - pertaining to the three natural powers of Heaven, Earth and Man.

Three Parts Wisdom - knowledge obtained through the doctor's connection and communication with his or her Upper, Middle, and Lower Dantians.

Three Periods of Life - the developmental stages of the patient's Jing, Qi and Shen divided into the womb, childhood and adulthood.

Three Stars - pertaining to the three periods of life, each period is divided into three stages of development, known as the three stars.

Three Treasures of Earth - pertaining to the energy of Soil, Water and Wind, and the study of Feng Shui (Wind and Water).

Three Treasures of Heaven - pertaining to the energy of the sun, moon and stars, and the study of Chinese astrology.

Three Treasures of Man - pertaining to the energetic interaction of the body's Essence, Energy and Spirit, and the study of the Yi-Jing (I-Ching or Book of Changes).

Three Wonders - Clinical manifestations of Qi, categorized as Subtle, Mysterious and Incredible Wonders.

Thrombosis - the formation and development or existence of a Blood clot (thrombus) within the walls of the vascular system.

Thrusting Channels - the Five Energy Channels which surround and penetrate the body's center core via the Taiji Pole.

Thrusting Vessels - also called the Chong Vessels, they are the Five Energy Vessels which originate from the center of the body and internally transverse the legs and torso.

Ti - referred to as the Divine Center.

Tian Qi (Heavenly Energy) - the transformed energy of the Yuan Qi and the divine.

Tian Shen (Heavenly Spirit) - the transformed energy of the Yuan Shen and the divine.

Tie Bi (Iron Wall) - the areas of the body where it is most difficult for the energy to pass through when circulating the Microcosmic Orbit.

Tinnitus - a ringing, tinkling, or buzzing sound in the ear.

Toe Raised Stepping - pertaining to energetic walking therapy, wherein the toes are stretched when stepping in order to facilitate the increase of Qi flowing into the body via the leg channels.

Tonification (Tonify) - to supplement the insufficiency and strengthen the body's resistance.

Traditional Chinese Medicine - Chinese Energetic Medicine, divided into four branches of healing modalities (Acupuncture, Herbal Therapy, Medical Qigong Therapy, and Tissue Regulation Therapy (Chinese Massage).

Transference - the process whereby a patient unconsciously transfers feelings, thoughts, beliefs and patterns of behavior that had been previously experienced with others onto the doctor.

Transient Ischemic Attacks (TIA) - temporary interference with the Blood supply to the brain.

Treatment - the medical care given to a specific condition.

Trigger Points (Ashi Points) - places on the body which are tender spots, or painful areas near diseased or injured tissue.

Trigram - pertains to three Yao lines stacked upon one another forming a specific symbol, which represents certain characteristics.

Triple Burners (San Jiao) - also known as the Triple Heaters and Triple Warmers, they correspond to three main body cavities (perineum to navel, navel to base of solar plexus, solar plexus to throat), and are responsible for heating the body and transporting Body Fluids.

True Fire - the original Heat or Fire Energy that regulates the body's Yin and Yang Qi, created from the radiating energy of the Heart's Fire, Kidneys' Fire and Bladder's Fire.

True Nature - one's innate nature in harmony with life.

True Qi - the energy that circulates in the body's channels and collaterals which nourishes the Yin and Yang organs and fights disease.

True Self - one's true nature, connected to the subconscious mind.

True Spirit - pertains to the spiritual nature of the True Self. The Hun and Po are expressions of the body's True Spirit.

Tsou Hou Ru Mo ("the Spirit leaves and the Demon enters") - describes self induced psychosis, pertaining to improper Qigong training, wherein the patient's Hun leave the body and the Po take over.

Tui Na Therapy - a tissue manipulation therapy that focuses on the adjustment and / or stimulation of the muscles and tendons.

Tumor - an abnormal growth, either benign or malignant, caused by a retention of mass due to the cultivation and stasis of Qi, Blood, Phlegm, etc.

Turbid Qi - also called Evil Qi, is coarse, unrefined, polluted, and dirty energy.

Twelve Pi Hexagrams - the twelve symbols pertaining to the twelve time periods of the day and year.

Twelve Primary Channels - the body's twelve main energetic rivers (Liver, Lungs, Large Intestine, Stomach, Spleen, Heart, Small Intestine, Bladder, Kidneys, Pericardium, Triple Burners, and Gall Bladder).

Twelve Earthly Branches - twelve energies of the Earth that determine the six Qi factors of the seasonal transitions (represented in the human body as the Twelve Primary Channels).

Two Breathings - pertaining to the abdominal breathing method of holding the breath.

U

Umbilications - a depression resembling a navel.

Universal Qi - energy pertaining to the Heavens, the divine and the celestial influences.

Upper Burner - pertaining to the body's complex system of Fluid distribution via the Lungs and located within the upper chest cavity.

Upper Dantian - area within the center of the head, attributed as the body's chamber of light and door to psychic and intuitive powers. The Upper Dantian is also known as Seal Palace, Ancestral Opening, Calm Fountain, Heaven's Valley, Inner Source, and Clay Pill Palace.

V

Vasculitis - the inflammation of a blood or lymph vessel.

Vertigo - the sensation of moving in space, resulting in such symptoms as dizziness and light-headedness.

Virtue (De) - pertaining to the function of the divine in man.

Virtue of Dao - pertaining to the commendable quality of the divine.

Viscera - the body's internal organs.

Void - also called Wuji, it pertains to the infinite space between matter and energy.

W

Wai Dan Shu - external elixir cultivation, that focuses on cultivating Qi from outside the individual's body.

Wai Qi - external, extended energy.

Walking Therapy - Postoral Dao Yin walking exercises and dynamic "moving" meditations used for the treatment of organ Deficiencies.

Wandering Bi - migrating pain within the body's cavities.

Waning - to grow smaller.

Water Element - one of the Five Elements, pertaining to Kidneys and Bladder.

Water Jing - energy that controls the genetic development phase of the fourth fetal month.

Waxing - to grow larger.

Wei Lu Guan (Coccyx Pass) - located on the lowest segment of the spine just posterior to the anus, near the Chang Qiang (GV-1) point.

Wei Qi - the body's external field of Defensive and Protective energy (divided into three fields of Qi).

Wen Huo - pertaining to the gentle breathing method of Respiratory Dao Yin training.

White Blood Cell - any of a group of Blood cells that have no hemoglobin and migrate into tissues to fight infection and digest cell debris.

Wind Bi - pain in the body created by toxic Wind invasion.

Wind Stroke - Stroke caused by the buildup of Excess Liver Fire creating Internal Wind. This Internal Wind causes Qi and Blood to rebel upwards causing Phlegm to form and obstruct the cavities and vessels, thus creating Penetrating Wind or Stroke.

Windy Breathing Method - pertaining to the method of breathing through the nose.

Wood Element - one of the Five Elements, pertaining to the Liver and Gall Bladder.

Wood Jing - energy that controls the development phase of the direction of the fetus's emotional and spiritual aspects during the seventh month of pregnancy.

Wu Guan (Five Passes) - five important gates on the Governing Vessel located at the coccyx, Mingmen, Shendao, occiput, and Baihui areas where energy tends to stagnate.

Wu Huo - pertaining to the vigorous breathing method of Respiratory Dao Yin training.

Wuji - pertaining to infinite space or the formless Void.

Wuji Posture - a quiet standing posture used in meditation to allow the practitioner to return to a state of tranquility.

Wu Jing Shen (Five Essence Spirits) - the spiritual energy radiating from the core of the Five Yin Organs. Combined, these energies create the foundation of the body's Shen (Spirit).

Wu Se Dai - pertaining to the five colors of vaginal discharge - white, yellow, red, green-blue, and dark brown or black.

Wu Wei - a state of "no mind," i.e., no thoughts.

Wu Zang - the Five Yin Organs. Wu translates to mean "five," Zang translates to mean "to store or hold."

X

Xie Qi (Evil Qi) - energy that causes disease or harmful effects to the body.

Xin Xi (The Message) - knowledge stored within the Wuji or the Void.

Xiphoid Process - the lowest part of the sternum bone (sometimes referred to as the Doves Tail).

Xue - Blood.

Y

Yang - the positive charged energetic polarity, opposite of its companion Yin, pertaining to man, hard, light, hot, etc.

Yang Channels - the body's Yang energetic rivers, consisting of the Governing Vessel, Belt Vessel, Yang Linking Vessels, Yang Heel Vessels, Large Intestine Channels, Triple Burner Channels, Small Intestine Channels, Stomach Channels, Gall Bladder Channels, and Bladder Channels.

Yang Fire - also called Emperor's Fire, energy of the Heart Fire.

Yang (Fu) Organs - also known as Hollow Organs, that consist of the Gall Bladder, Small Intestine, Stomach, Large Intestine, Bladder. Also included is this category are the Triple Burners.

Yang Shen Disturbances - an emotional Yang state of energetic dysfunction.

Yang Ming (Yang Brightness) - indicates Yang Qi developing its final stage and then reverting into Yin.

Yao - a solid or broken line which is representative of either Yang or Yin energy, used in combination of three as Trigrams or six as Hexagrams.

Yao Cycles - the progression of twelve hexagrams (six Yang and six Yin) flowing in a waxing and waning cycle.

Ye (humor) - thick, turbid Body Fluids.

Yellow Court - located in the center of the diaphragm, just below the xiphoid process of the sternum. Its function is that of being the access point to releasing the body's internal organ emotional memories. Its location is also attributed to the 3rd Chakra.

Yi - the intention or thought (the cognitive mind).

Yi Jing - Chinese "Book of Changes," pertaining to the natural transitions of life.

Yin - the negative charged energetic polarity, opposite of its companion Yang, pertaining to woman, soft, dark, cold, etc.

Yin Channels - Yin energetic rivers, consisting of the Conception Vessel, Thrusting Vessel, Yin Linking Vessels, Yin Heel Vessels, Lung Channels, Pericardium Channels, Heart Channels, Spleen Channels, Liver Channels, and Kidney Channels.

Yin (Zang) Organs - also known as the Solid Organs, that consist of the Liver, Heart, Spleen, Lungs and Kidneys. Also included in this category is the Pericardium.

Yin Shen Disturbances - an emotional Yin state of energetic dysfunction.

Yin Tang (Third Eye Point) - located in the center of the forehead, responsible for projecting the Spirit for psychic intuition and communication.

Ying Qi (Nutritive Qi) - the body's nourishing energy.

Yu (Surplus) Vessels - secondary vessels that branch away from the energetic flow of the major Linking Vessels (at the chest and back), connecting the Linking Vessels energetic flow to the hands.

Yuan Jing (Original Essence) - the Original Kidney or Prenatal Essence.

Yuan Shen (Original Spirit) - the Original Prenatal Spirit.

Yuan Qi (Original Energy) - the Original Kidney or Prenatal Qi.

Yun - the Yin method of dynamic postural Dao Yin training.

Yu Zhen Guan (Occipital Pass) - the area located just inferior to the occipital bone where the brain originates, known as a specific point where Qi often stagnates.

Z

Zang Organs - Yin or solid organs (Liver, Heart, Spleen, Lungs, Kidneys and Pericardium).

Zang/Fu Organs - the body's Yin and Yang organs.

Zhang Xiang Xue Shou - in Chinese medical science, the study of energetic physiology.

Zhen Qi - see True Qi

Zheng Qi - Righteous Qi, pathogenic fighting Energy.

Zhi - the Will power, mental drive and determination.

Zhong Qi - Center Qi, Energy of the chest.

Zhou Qi - Turbid Qi, Evil Qi, Impure Qi

Zong Qi - Gathering Qi, and / or Respiratory Qi.

Zygomatic Facial Regions - pertaining to the sides of the cheeks below the eyes.

BIBLIOGRAPHY

1. Anodea Judith
Wheels of Life
Liewellyn Publications, 1990
St. Paul, Minnesota 55164-0383

2. *A Barefoot Doctor's Manual*
A Guide To Traditional Chinese and Modern Medicine
A Cloudburst Press Book
Madrona Publishers
Seattle, Washington 1977

3. Robert O. Becker, M.D.
Cross Currents
Jeremy P. Tarcher, Inc., 1990
Los Angeles, Ca. 90036

4. Harriet Beinfield, L.Ac. and
Efrem Korngold, L.Ac., O.M.D.
Between Heaven And Earth
A Guide To Chinese Medicine
Ballantine Books, NY 1992

5. Barbara Ann Brennan
Hands of Light
A Guide to Healing Through the Human Energy Field
Bantam Books Publishing 1988
New York, New York

6. Paul Carus
Chinese Astrology
Early Chinese Occultism
Open Court Publishing 1989
La Salle, Illinois

7. Dr. Chen Yan-Feng
Pre-Natal Energy, Mobilizing Qigong
China Taoist Ancient Qigong
Chinese Kung Fu Series
Guandong Xin hua Printing House 1992

8. *Chinese Qigong*
Publishing House of Shanghai
College of Traditional Chinese Medicine
China 1990

9. *Chinese Qigong*
Outgoing Qi Therapy
Shandong Science and Technology Press
China 1992

10. *Chinese Qigong Therapy*
Shandong Science and Technology Press
China 1995

11. Dr. Choa Kok Sui
Pranic Healing
Samuel Weiser, Inc. 1990

12. Kenneth S. Cohen
The Way of Qigong
Ballantine Books 1997

13. Peter Deadman
Selected Articles from the
Journal of Chinese Medicine
England

14. Peter Deadman & Maazin Al-Khafaji
with Kevin Baker
A Manual of Acupuncture
Journal of Chinese Medicine Publications
England 1998

15. Luc DeSchepper MD, PhD,CA
Acupuncture for the practitioner
Asnta Monica, California 91403

16. Vincent T. DeVita, Jr., Samuel Hellman,
Steven A. Rosenberg
Cancer Principles and Practice of Oncology
Fifth Edition - Vol 1
Lippincott - Raven Publishers
Philadelphia - New York 1997

17. Vincent T. DeVita, Jr., Samuel Hellman, Steven A. Rosenberg
Cancer Principles and Practice of Oncology
Fifth Edition - Vol 2
Lippincott - Raven Publishers
Philadelphia - New York 1997

18. Paul Dong and Thomas Raffill
Empty Force
Element Books, Inc., 1996
Rockport, Mass. 01966

19. *Essentials of Chinese Acupuncture*
Beijing College of Traditional Chinese Medicine
Foreign Languages Press, 1980
Beijing, China

20. Richard Feit and Paul Zmiewski
Acumoxa Therapy
A Reference and Study Guide
Volume II The Treatment of Diseases
Paradigm Publications
Brookline, Massachusetts 1990

21. Richard Gerber, M.D.
Vibrational Medicine
Bear and Company, 1988
Santa Fe, New Mexico 87504-2860

22. Stanislav Grof,M.D. with Hal Zina Bennett
The Holotropic Mind
Harper Collins Publishers, Inc. 1993
New York City, New York

23. Rosemary Ellen Guiley
Harper's Encyclopedia of
Mystical and Paranormal Experiences
Harper Collins Publishers Inc. 1991
New York City, New York

24. Dr. Guo Liang Cao
Essentials Of Tuinaology
Chinese Medical Massage and Manipulation
Cao's Fire Dragon
Hilo, Hawaii 1983

25. Leon Hammer, M.D.
Dragon Rises and Red Bird Flies
Psychology and Chinese Medicine
Staton Hills Press, Inc.
Barrytown, New York 1990

26. *Illustration of Channels and Points For Acupuncture and Moxibustion and Qigong*
Hunan Science and Technology Press
China 1992

27. Roger Jahnke D.O.M.
The Healer Within
Harper Publishing
San Francisco 1997

28. Dr. Jiao Guo Rui
Qigong Essentials for Health Promotion
China Reconstruction Press 1990

29. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
Chi Kung Correspondence Course, Vol. 1-6
Pacific Grove, CA 1988

30. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
The Essence of Internal Martial Arts, Vol. 1
Esoteric Fighting Techniques and
Healing Methods
Pacific Grove, CA 1994

31. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
The Essence of Internal Martial Arts, Vol. 2
Energy Theory and Cultivation
Pacific Grove, CA 1994

32. Ted J. Kaptchuk, O.M.D.
The Web That Has No Weaver
Congdon and Weed, Inc., 1983
New York, New York, 10001

33. Dr. Arnie Lade, DOM
Acupuncture Points
Images & Functions
Eastland Press 1989

34. Claude Larre and Elisabeth Rochat de la Vallee
The Seven Emotions
Psychology and Health in Ancient China
Monkey Press
Cambridge, CB4 3PU 1996

35. Dr. Mariam Lee, D.O.M.
Insights of a Senior Acupuncturist
Blue Poppy Press
Boulder, Colorado 1992

36. Richard H. Lee
Qi and Kirlian Photography
China Healthways Institute, 1996
San Clemente, Ca 92672

37. Master Shou-Yu Liang and Wen-Ching Wu
Qigong Empowerment
A Guide to Medical, Taoist, Buddhist
and Wushu energy Cultivation
The Way of Dragon Publishing, 1997
East Providence, Rhode Island 02914-0561

38. Dr. Lin Huo Sheng & Dr. Luo Pei Yu
Three Hundred Questions on
Qigong Exercises
Guandong Science and Technology Press
China 1994

39. Dr. Hong Liu with Paul Perry
Mastering Miracles
Warner Books Inc., 1997
New York, New York, 10020

40. Liu Zheng-Cai and Hua Ka
A Study of Daoist Acupuncture
Blue Poppy Press
Boulder, Colorado 1999

41. Livia Kohn & Yoshinobu Sakade
Taoist Meditation and
Longevity Techniques
Center for Chinese Studies
University of Michigan 1989

42. Ke Yun Lu
The Essence of Qigong
A Handbook of Qigong Therapy
and Practice
Abode of the Eternal Tao
Eugene, Or. 1998

43. Giovanni Maciocia
Tongue Diagnosis in Chinese Medicine
Eastland Press Inc., 1987
Seattle, Washington 98111

44. Giovanni Maciocia
Obstetrics & Gynecology in
Chinese Medicine
Churchill Livingstone Inc., 1998
New York City, New York, 10011

45. Giovanni Maciocia
The Foundations of Chinese Medicine
Churchill Livingstone Inc., 1989
New York City, New York, 10011

46. Kiiko Matsumoto & Stephen Birch
Extraordinary Vessels
Paradigm Publications
Brookline, Massachusetts 1986

47. Kiiko Matsumoto and Stephen Birch
Hara Diagnosis: Reflections on the Sea
Paradigm Publications, 1988
Brookline, Massachusetts 02146

48. Hugh Milne
The Heart of Listening
A Visionary Approach to Craniosacral Work
North Atlantic Books
Berkeley, California 1995

49. Joseph Needham,F.R.S.,F.B.A.
Science and Civilization in China
Volume 5 Chemistry and
Chemical Technology
Part V: Spagyrical Discovery and Invention:
Physiological Alchemy
Cambridge University Press 1986
Cambridge, London

50. Master Ni Hua Ching
The Book of Changes and
the Unchanging Truth
Malibu, CA 1983

51. John O'Connor and Dan Bensky
Acupuncture, A Comprehensive Text
Shanghai College of Traditional Medicine
Eastland Press
Chicago, Illinois 1981

9. Bring the pearl up to the upper tip of the left ear at the level of the ***Mideyebrow Center***. Circle the pearl nine times from the left ear back to the small brain, to the right (upper tip of the ear), returning to the mideyebrow. Feel a band of energy flowing around the mideyebrow, ears, and back of the head. Using the pearl, form an internal cross connecting all four sides. The feeling is one of wearing a crown with a cross at its center connecting it.
10. From the mideyebrow bring the pearl up to the left side of the ***Crown***, and circle the energy nine times in a counterclockwise direction at the crown. End with the pearl at the front. Using the pearl, form a cross connecting the front, back, and both sides of this Belt Channel.
11. Allow the pearl to go out above the crown, and circle the energy nine times toward the left forming a ***Halo of Energy***. Use the pearl to cross the halo, front to back, and left to right. Collect the energy from above the head.



Fig. 8.5 *Spiral out clockwise above the crown.*

52. Yoshiaki Omura, Sc.D.,M.D.
Acupuncture Medicine
Japan Publications, Inc. 1982
Tokyo, Japan

53. Pan Mingji
How to Discover Cancer Through Self-Examination
Fujian Science and Technology
Publishing House
Beijing, China 1992

54. *Point Therapy*
A Chinese Traditional Therapeutic Skill
Shandong Science and Technology
Press 1990

55. Daniel Reid
Harnessing the Power of the Universe
A Complete Guide to the Principles and Practice of Chi-Gung
Shambhala Publications, Inc.
Boston, Massachusetts 1998

56. D. Scott Rago
Leaving the Body
A Complete Guide to Astral Projection
Prentice-Hall, Inc., 1983
Englewood Cliffs, New Jersey

57. Elisabeth Kubler-Ross,M.D.
On Death and Dying
Collier Books, 1969
Macmillan Pub. Co., New York

58. Jeremy Ross, C.Ac. (Nanjing), B.Ac. (M.B.Ac.A.), C.Ed.
Zang Fu,The Organ Systems of Traditional Chinese Medicine
Functions, Interrelationships and Patterns of Disharmony in Theory and Practice
Churchill Livingstone
Edinburgh, London, Melbourne
and New York 1985

59. Stephano Sabetti
The Wholeness Principle
Exploring Life Energy Process
Life Energy Media 1986
Sherman Oaks, California

60. Mikio Sankey Ph.D., L.Ac.
Esoteric Acupuncture
Gateway to Expanded Healing Vol.1
Mountain Castle Publishing
Los Angeles, Ca. 1999

61. Jack Schwark
Human Energy Systems
The Aletheia Foundation, 1980

62. Kylea Taylor
The Ethics of Caring
Hanford Mead Publishers 1995
Santa Cruz, California

63. *Textbook of Medical Qigong Therapy*
Haidian Qigong University
Medical Qigomg College
White Cloud Monestry, 1988
Beijing, China

64. Clayton L. Thomas, M.D., M.P.H.
Taber's Cyclopedic Medical Dictionary
F.A. Davis Company, 1993
Philadelphia, Pa., 19103

65. Michael Tierra
East West Master Course In Herbology
Santa Cruz, California 1981

66. Dr. Tzu Kuo Shih
Qigong Therapy
The Chinese Art of Healing With Energy
Station Hill Press 1994

67. Ilza Veith
The Yellow Emperor's Classic of Internal Medicine
University of California Press, 1966
Berkeley and Los Angeles, Ca.

68. Andrew Weil,M.D.
Spontaneous Healing
Fawcett Columbine
Published by Ballantine Books 1995
New York City, New York

69. Nigel Wiseman and Feng Ye
A Practical Dictionary of Chinese Medicine
Second Edition
Paradigm Publications 1998
Brookline, Massachusetts

70. Henry S. Wu, D.C.
Differentiation of Syndromes
California Acupuncture College 1982
Los Angeles, Ca.

71. Yan De-Xin
Aging & Blood Stasis
A New TCM Approach to Geriatrics
translated by Tang Guo-shun & Bob Flaws
Blue Poppy Press
Boulder, Co. 1995

72. Dr. Yang Jwing Ming, Ph.D.
The Root of Chinese Qigong
The Secrets of Qigong Training
Yang Martial Arts Association 1989

73. Yin Hui He
Fundamentals of
Traditional Chinese Medicine
Foreign Languages Press, 1995
Beijing, China

74. Yu Gong Bao
Chinese Qigong Illustrated
New World Press 1995

CLINICAL REFERENCES

1. Master John Fey
   Clinical Notes from Lectures
   Medical Qigong Therapy
   Reference: Differential Healing Modalities
   Los Angeles , CA 1984 to 1987
2. Michael Gershon, M.D.
   Professor of Anatomy and Cell Biology
   Columbia Presbyterian Medical Center
   Research presented by Sandra Blakeslee
   New York Times, New York 1996
3. Dr. Jason Gill, L.Ac.
   Lectures on Traditional Chinese Medicine
   Clinical Notes on Differential Diagnosis
   Pacific Grove, CA 1994 to 1997
4. Dr. Jason Gill
   Clinical notes and Lectures
   Reference: Dr. Jeremy Ross Lectures
   on Traditional Chinese Medicine
   Pacific Grove, CA. 1994 to 1997
5. Dr. Jiang Gui Zhong and
   Dr. Cai Chang Rong
   Clinical Notes from Hu Guo Hospital
   Medical Qigong Therapy, An Mo Therapy
   and Differential Healing Modalities
   Beijing, China 1993
6. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q.
   (China)
   Clinical notes from the First World
   Conference on Medical Qigong
   Medical Qigong Therapy and Differential
   Healing Modalities
   Reference Conference No. 1, Sept. 1988
7. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q.
   (China)
   Clinical notes from the International
   Symposium on Chinese Qigong Health
   Preservation and Qigong Techniques
   Medical Qigong Therapy and Differential
   Healing Modalities
   Reference Symposium, Nov. 1990
8. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q.
   (China)
   Clinical notes from the Second World
   Conference on Medical Qigong
   Medical Qigong Therapy and Differential
   Healing Modalities
   Reference Conference No. 2, Sept. 1993
9. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q.
   (China)
   Clinical notes from Xi Yuan Hospital
   on Medical Qigong Therapy and
   Differential Healing Modalities
   Internship July 1993 through Sept. 1995
10. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q.
    (China)
    Clinical notes from Hai Dian Medical
    University on Medical Qigong Therapy and
    Differential Healing Modalities
    July 1993 through Sept. 1995
11. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q.
    (China)
    Clinical notes from the Third World
    Conference on Medical Qigong
    Medical Qigong Therapy and Differential
    Healing Modalities
    Reference Conference No. 3, Sept. 1996

12. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
Clinical notes from the Second World Congress on Medical Qigong
Medical Qigong Therapy and Differential Healing Modalities
San Francisco, California Nov. 1997

13. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
Clinical notes from the Fourth World Conference on Medical Qigong
Medical Qigong Therapy and Differential Healing Modalities
Reference Conference No. 4, Sept. 1998

14. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
Clinical Notes from International Institute of Medical Qigong
Medical Qigong Therapy and Differential Healing Modalities
Pacific Grove, CA 1988 - 1999

15. Sifu Mark Johnson
Clinical Notes in Geriatric Medical Qigong Therapy and Esoteric Daoist Studies of the Yi-Jing and Feng Shui
Mill Valley, CA 1998 - 1999

16. Dr. Lu Guo Hong, Dr. Niu Yu Hua, and Dr. Li Fu Dong
Clinical notes from Hai Dian Medical University on Medical Qigong Therapy and Differential Healing Modalities
Beijing, China 1993 - 1996

17. Dr. Lu and Dr. Shu Zong Wei
Clinical Notes from Xi Yuan Hospital
Medical Qigong Therapy and Differential Healing Modalities
Beijing, China 1993

18. Dr. Hugh Milne
Clinical Notes from Cranial-Sacral Therapy
Level 1 through 6, 1990-1995
Monterey, Calif.

19. Dr. Ren Shun Tu & Dr. Xu Hong Tao
Clinical Notes from Xi Yuan Hospital
Medical Qigong Therapy and Differential Healing Modalities
Beijing, China 1995

20. Dr. Teng Ying Bo
Clinical Notes from Beijing Medical Qigong Science and Research Institute
Medical Qigong Therapy and Differential Healing Modalities
Beijing, China 1995

21. Dr. Zheng Zhan Ding
Clinical Notes on Medical Qigong Diagnosis, Therapy and Differential Healing Modalities
Beijing, China 1993 - 1996

INDEX

A

Abdominal Breathing, 392-394, 422
Abdominal Pain, 64, 206, 208, 211, 471, 473, 565, 768, 788,793-795, 838, 910, 916, 917, 920
Abortions, 444, 445, 600, 860, 861
Absorbing Qi From Nature, 125, 126, 293, 304, 306, 307
Acquired Cellular Patterns, 115
Acquired Constitution, 787
Acquired Disorders, 461
Acquired Energy, 317
Acquired Essence, 319, 607, 720
Acquired Force, 270
Acquired Mind, 91, 201, 333, 335, 336, 138, 344, 345
Acupressure, 631, 928
Acupuncture, 49, 50, 52, 54, 56, 59, 66, 126, 128, 129, 133, 159, 164, 199, 215, 245-249, 309, 507, 522, 529, 536, 537, 557, 565, 566, 595, 611, 662, 664, 839,683, 864, 865, 882, 884, 922, 923, 924, 929
Adenocarcinoma, 689, 896, 910, 911, 913
Adrenaline, 426, 781, 900
Affirmation, 87, 89, 90, 104, 115, 411, 430, 448, 519, 554, 555, 561, 619, 861, 882, 904, 921
Akashic Records, 516
Alarm Points, 252
Alchemy, 131, 132, 249, 267, 293
Alternating Current, 128
An Jing (Hidden Power), 48
An Mo, 57, 61-65, 566, 631, 832, 890, 893
Anal Sphincter, 149, 154, 200, 342, 363, 365, 366, 393, 422, 451, 691, 728, 734, 752, 824, 868, 893, 909, 912, 917
Ancestral Channel, 197
Ancestral Qi, 137
Ancestral Traits, 274, 510, 517
Anemia, 425, 784, 828, 896, 915, 916
Anesthesia, 129, 438, 442, 447, 922, 923, 924, 925, 928
Anger, 48, 64, 75, 88, 99, 108, 138, 149, 154, 155, 168, 348, 403, 404, 413, 427, 429, 431, 439, 445-447, 452, 460, 466-470, 488, 508, 545, 560, 578, 581, 582, 594, 599, 601, 602, 615, 617, 619, 624, 626, 627, 708, 767, 769, 794, 796, 798, 828, 844, 849, 850, 852, 855, 858, 859, 860, 861, 869, 871, 872, 874, 877, 890, 891, 892, 899, 900, 905, 911, 913
Angina, 384, 394, 602, 779
Anorexia, 774, 775, 796, 819, 828, 916
Antique Shu Points, 249, 250, 251 370
Anxiety, 75, 88, 108, 123, 129, 135, 170, 174, 176, 204, 208, 214, 250, 253, 391, 394, 398, 404, 426, 432, 439, 447, 469-471, 488, 508, 602, 616, 784, 796, 880, 817, 818, 820, 828, 830, 843, 859, 874, 875, 877-882, 888, 900
Aphasia, 202, 212, 219, 220, 492, 505, 864, 890
Aplastic Anemia, 784
Archetypes, 48, 87, 334, 336
Arrhythmia, 779, 784
Arteriosclerosis, 777, 828, 865
Arthritis, 64, 384, 566, 823, 826, 827
Ascariasis, 772, 773
Ascending Qi, 201, 375, 376, 667
Asthma, 172, 174, 198, 204, 251, 360, 382, 443, 447, 464, 466, 492, 495, 497, 544, 670, 672, 731, 766, 801-803, 806-808, 812, 823, 838, 897
Astral Body, 84, 85, 348, 349, 351, 437
Astral Matter, 328
Astral Plane, 344, 348, 350, 351, 444, 516
Astral Travel, 85, 91, 328, 337, 345, 346, 435
Astrology (Chinese), 99, 268, 293, 297
Atman, Adam, 50, 54
Atrophy Syndrome (Disorder), 603, 792, 802, 867
Aura, 137, 143, 147, 155, 328, 525 529, 531, 688, 831, 925
Aura Colors, 525, 528
Auspicious Powers, 280
Autumn Equinox, 280
Awakening, 74, 150, 411, 413, 430, 513, 650

B

Ba Gan, 465
Back Pain, 154, 194, 202, 219, 421, 461, 497, 670, 812, 813
Bai Yuan, 84, 86
Baihui Point, 84, 147, 201, 229, 284, 370, 371, 431, 453, 520, 547, 573, 575, 846
Base Chakra, 151
Becker, Robert O., 128, 129, 141, 245, 246
Beijing Medical University, 274

Bellows Palm Technique, 594, 639, 659
Bells Palsy (Facial Paralysis), 866
Belt Vessel, 70, 71, 185, 197, 198, 200, 206-209, 210, 253, 260, 386, 575, 718, 728, 735, 737, 850, 851
Benign Tumors, 766, 854, 895-897, 916
Big Dipper, 135, 273, 290-294, 575, 612
Biochemical, 128, 138, 515, 685
Biorhythm, 272-276
Bitter Foods, 304, 310, 311, 466, 472, 770, 777, 851
Black, 46, 105, 247, 308, 310, 311, 327, 413, 414, 426, 431, 438, 439, 451, 452, 473, 502, 504, 505, 521, 529, 617, 624, 770, 811, 851, 852, 905, 906
Bladder, 57, 78, 82, 123, 136, 146, 154, 161, 182-185, 193, 312, 324
Bladder Channel, 71, 82, 174, 182 184, 194, 201, 210, 212, 219, 221, 236, 252, 381, 501, 504, 707, 772, 794, 797, 805, 807, 817, 818, 830, 831, 890
Bladder Divergent Channel, 222, 225
Bladder Fire, 127
Bloated Energy Stagnation, 600
Blood Deficiency, 170, 214, 242, 489, 670, 768, 777, 785, 788, 798, 816, 818, 823, 828, 849, 851-853, 858, 859
Blood Heat, 490, 851, 854, 859, 890
Blood Pressure, 64, 274, 362, 377, 379, 391, 394, 398, 406, 426, 670, 672, 684, 780-783, 863, 865, 888, 890, 900, 901, 922
Blood Stasis, 180, 399, 486, 490, 667, 692, 825, 843, 854, 855, 858, 859, 881, 897, 898
Blood Vessels, 73, 76, 128, 138, 163, 170, 176, 178, 180, 189, 198, 217, 241, 243, 257, 262, 263, 322-324, 326, 329, 378, 391, 392, 394, 398, 401, 403, 466, 489, 490, 504, 610, 612, 617, 781, 843, 873
Blue, 74, 91, 101, 121-124, 147, 155, 217, 241, 247, 293, 294, 307, 326, 426, 453, 524, 526, 529, 561, 573, 575, 610, 624, 633, 653, 654, 658, 701, 769, 813, 814, 829, 842, 851, 852, 853, 904, 906, 909, 913, 925
Body Fluids, 73, 74, 92, 119, 159, 163-166, 170, 182, 184, 191, 193, 318, 324, 333, 459, 466, 481, 483, 490-492, 496, 501, 616, 687, 798, 897, 920
Bone, 79, 81, 95, 129, 198, 260-263, 319, 650, 837, 895 896
Bone Marrow, 76, 141, 166, 260, 319, 324, 330, 331, 491, 684, 685, 726, 901
Bones, 257, 260, 261, 263
Book of Commentaries, 271
Borborygmus, 472
Brain, 77, 138, 140, 141, 146, 184, 198, 201, 202, 257-260, 324, 328, 330, 331, 349, 401, 403, 404, 408, 410, 519, 527, 587, 599, 605, 671, 843, 861, 863-870, 880, 888, 895, 906
Brain Tumor, 441, 713, 906, 907
Breast Cancer, 896, 904, 907, 908
Breast Cysts, 108, 731, 601, 854, 855, 857
Breath Regulation, 355, 356, 391, 396,, 397 803
Bridge of Light, 409, 410, 548
Bronchial Asthma, 766, 803, 806
Bronchiectasis, 808
Bronchitis, 360, 382, 731, 803, 806, 823

C

Caduceus, 721
Calculi, 773
Cancer Formation, 898, 897, 899
Cancer Research, 904
Cancer Treatments, 895
Carbuncle, 854, 855
Carcinogens, 913, 916
Carcinoma, 204, 689, 713, 715, 896, 908-916
Categorization of Signs and Symptoms, 462
Categorization of Tumors, 895
Celestial Stems, 296, 300
Center Core, 131, 148, 149, 150, 151, 161, 307, 330-332, 409, 415, 438, 494, 541, 547, 573, 620, 621, 650, 737, 873
Center Qi, 321, 322, 324
Center Thrusting Channels, 120, 293, 295
Centrifugal and Centripetal, 249
Cerebral Embolism, 689, 863
Cerebral Hemorrhage, 689, 863
Cerebral Thrombosis, 863
Cerebro-Vascular Accident (CVA), 863
Cervical Cancer, 601, 689, 909-911
Chakra, 135, 139, 142-144, 151-157, 553, 600, 722, 737
Chakra System, 151, 153, 157
Channel Pathology, 193, 194, 252
Channel Point Meditation, 665, 669, 688, 882
Channel Point Therapy, 883
Channel Points, 59, 66, 126, 128, 159, 228, 246, 249, 250, 644, 651, 665-668, 675, 676, 692, 721
Chao, Yuan Fang, 71, 523
Chemotherapy, 411, 551, 707, 713, 919-921, 927
Cheng, Zhong Ling, 465
Chicken Pecking Technique, 663
Child Element, 656
China Healthways, 47, 119, 125, 129
Chinese Massage, 49, 50, 52, 56, 57, 61, 62, 129, 164, 309, 631, 565, 566
Cholecystitis, 772, 775, 776

Cholelithiasis, 772, 776
Cholestasis, 773
Chronic Bronchitis, 360, 731, 806
Chronic Constipation, 799,798
Chronic Fatigue Syndrome, 360, 598
Chronic Gastritis, 796
Chronobiology, 274
Chyluria, 791
Circle of Willis, 865
Circle Twisting Method, 677
Circular Breathing , 723
Cirrhosis, 774
Clairaudience, 146, 155, 343, 346
Clairsentience, 155
Clairvoyance, 146, 343, 346, 351, 437
Classification of Energetic Points, 249
Clean Qi, 191, 505
Climate, 215, 356, 466, 467, 488, 815
Clinical Ethics, 576, 578
Coccyx Pass (Wei Lu Guan), 605
Cold, 465-467, 470-475, 477, 480, 481, 551, 552, 597, 598
Cold Deficiency, 502
Colitis, 602, 789, 875, 916
Collapsed Qi, 488
Colon and Rectum Cancer, 916
Color Imagery, 123
Color Vibration, 119, 120, 122, 526
Color Visualization, 683, 688, 701, 770, 925
Coma, 64, 146, 444, 466, 823, 850, 864-866
Common Cold and Influenza, 801, 802, 804
Common People's Fire, 127
Compass School (Feng Shui), 270
Compassion, 75, 104, 155, 168, 429, 431, 437, 446-448, 524, 541, 617, 624, 860, 871, 872, 878, 880, 904, 905, 906, 921
Compressed Energy Stagnation, 600
Compression Release Method, 676-679
Concentrative Meditation, 407
Conception; 67-70, 72, 74, 84, 86, 119, 132, 200, 274, 275, 318, 320, 321, 333, 339, 409
Conception Vessel, 151, 157, 198, 200-208, 213, 217, 221, 242, 252, 257, 284, 294, 342, 372, 387, 432, 605, 606, 646, 670, 720-723, 733, 743, 785, 850-852, 855, 856, 882, 903, 909, 911
Congealed Blood, 241
Congenital Cellular Patterns, 115
Congenital Constitution, 99
Congenital Jing, 99, 115
Congenital Qi, 838
Congenital Spirit, 401
Connecting Channels, 208, 239, 864
Conscious Mind, 343, 409, 410, 439, 441, 617, 625, 665, 879
Constipation, 154, 174, 470, 502, 503, 505, 768, 781, 788, 789, 791, 794, 798, 799, 812, 828, 830, 873, 875, 915, 916, 920
Constitution, 61, 68, 99, 100-105, 176, 319, 356, 360, 362, 395, 419, 420, 426, 453, 457-459, 460, 462-465, 475-477, 479, 483, 484, 486, 490, 507, 511, 557, 563, 566, 569, 598, 603, 631, 689, 711, 784, 787, 798, 823, 832, 833, 839, 852, 858, 863, 864, 866, 929
Constitutional Failure, 459
Contracted Energy Stagnation, 600, 601
Contraindications for Medical Qigong, 590
Controlling Cycle, 100, 123, 313, 468, 496, 871, 874, 891
Corporeal Soul, 138, 250, 273, 429, 436, 847, 874, 886
Coryza, 805
Cosmology, 268, 348
Counter-Transference, 579
Creative Cycle, 100, 123, 249, 251, 281, 316, 495, 496, 656, 871
Creative Subconscious, 409, 412, 444, 513, 554, 555, 561, 617, 623
Crown Center, 156
Crown Chakra, 151, 153, 154, 737
Cupping, 57-59, 649, 659, 815, 816
Curious Organs, 257
Cycle of Disharmony, 468
Cycle of the Moon, 276, 284
Cycle of the Sun, 276, 277
Cycles of the Stars, 290
Cysts and Tumors, 64, 601, 731, 854, 860, 887, 895
Cytotoxic Treatments, 919

D

D.M.Q., 50, 54
Damp Heat, 174, 184, 193, 210, 486, 504, 505, 667, 669, 671, 747, 768, 773-776, 788, 792, 805, 809, 819-821, 851, 852, 857, 911, 920
Dantian Breathing, 723
Dao, 47, 84, 102, 132, 141, 142, 144, 148, 149, 199, 267, 268, 271, 317, 318, 323, 326, 333, 407, 416, 514, 515, 541, 587
Daoist, 99, 118, 131-133, 143, 249, 333, 348, 350, 378, 688, 708, 717, 751, 752, 762, 763, 784, 797, 799, 806, 827, 854, 868
Death, 86-89, 92, 93, 95, 132, 134, 135, 142, 144, 268, 270, 276, 292, 334, 339, 344, 411, 426, 436, 437, 442-445, 459, 468, 503, 518, 530, 541, 545,

625, 626, 627, 628, 827, 846, 848, 860, 865, 874, 875, 896, 900, 911, 913, 915, 921
Defense Mechanism, 149, 447, 450, 604, 619, 621, 838
Deficient Dantian Qi, 823
Delusions, 437, 438, 870, 883
Demon Oppression, 437, 438
Demon Possession, 424, 438, 442,
Denial, 142, 326, 438,441, 444, 447, 449, 450, 569, 578, 602, 618-621, 626, 720, 875, 882, 892, 898, 899, 922
Depersonalization Disorder, 446
Depression, 89, 119, 129, 156, 168, 172, 191, 202, 214, 219, 245, 335, 337, 341, 391, 404, 426, 427, 439, 444, 446, 460, 468, 469, 476, 486, 518, 545, 560, 590, 598, 626, 627, 653, 695, 708, 772, 776, 798, 818, 830, 843, 844, 850, 852, 855, 857, 874, 881, 886, 887, 897, 898, 900, 903, 907, 913, 922, 927
Diabetes, 64, 155, 311, 781, 791, 792, 820, 863
Diagnosis According to the Triple Burners, 504
Diagnosis and Treatment of the Patient, 462
Diaphoresis, 501
Diet, 46, 61, 69, 95, 99, 115, 176, 260, 308-310, 313, 421, 426, 458, 460, 467, 472, 473, 475, 484, 486, 489, 490, 509, 510, 570, 686, 773, 791, 798, 807, 818, 838, 847, 850, 851, 859, 863, 867, 881, 895, 911, 915, 916, 927
Different Schools of Qigong, 47
Differentiation of Psycho-Emotional Disorders, 881
Differentiation of Syndromes, 461, 502
Digestion, 111, 168, 174, 176, 178, 182, 189, 191, 260, 309, 310, 312, 333, 360, 361, 372, 409, 460, 486, 505, 509, 616, 694, 743, 789, 897, 914, 920
Direct Current, 128, 246
Disorders of Body Fluids, 491,490
Disorders of Qi, 483
Disorders of the Blood, 489, 490
Disorders of the Body Fluids, 490
Disorders of the Human Body, 459
Disorders of the Qi, 483, 489, 825
Divergent Channels, 160, 161, 222-227
Divine Center, 290, 438
Divine Energy, 46, 48, 91, 132, 147, 161, 260, 317, 323, 407, 515, 531, 570, 576, 587, 661, 870
Divine Guidance, 649
Divine Healing, 407, 440, 452, 453, 533, 542, 544, 546-549, 556, 577, 606, 624, 661 697, 708, 709, 846, 857, 861, 868, 904, 905, 928
Divine Hook-Up, 541, 542, 546-548, 550, 582, 583
Divine Light, 86, 115, 326, 437, 547, 559, 573
Divine Qi, 323, 531, 694, 696, 697
Divine Will, 142, 155, 340, 407, 548, 625, 627
Dossey, Larry, 530
Dragons Mouth Technique, 659
Draining Toxic Qi, 596
Dreams, 335-337, 340, 344, 347 436, 437-439, 448, 449, 627
Dry Crying Prescription, 622, 688, 857, 893, 913, 914
Durville, Hector, 437
Dynamic Qigong, 278, 355, 356, 372, 373, 406, 426, 591, 717, 866
Dysmenorrhea, 206, 471, 768, 852, 853, 924
Dyspepsia, 469, 694, 775, 796, 915
Dyspeptic, 794
Dysphoria, 781, 796
Dyspnea, 172, 198, 214, 251, 253, 360, 464, 467, 785, 803, 806, 807, 811, 813, 838

E

Earth Element, 98, 100, 293, 493, 663, 676
Earth Jing, 80, 81
Earth Qi, 67, 73, 82, 83, 132-134, 301-303, 305, 307, 308, 324, 362, 372, 380, 383, 386, 532, 656, 718, 719, 724, 726, 728, 733, 734, 737, 752
Earth Transpersonal Point, 576
Earthly Branches,156, 157, 161, 268, 269, 270, 281, 290, 291, 296, 297, 299, 721
Eczema, 241, 807
Edema, 96, 172, 242, 382, 422, 492, 496, 498, 602, 665, 667, 777, 785, 787, 788, 812, 819, 850, 906, 920
Ego, 142, 155, 331, 340, 344, 416, 428, 517, 519, 541, 621, 880
Eight Confluent Points, 253, 611
Eight Energetic Principles, 308, 461, 465, 478, 480, 509
Eight Energetic Touches, 359, 408, 588, 589, 598
Eight Extraordinary Vessels, 70, 71, 83, 84, 107, 133, 148, 159, 160, 197, 198, 199, 200, 215, 216, 253, 257, 284, 296, 332, 611, 731, 826, 849, 882
Eight Influential Points, 253
Eight Miscellaneous Causes of Disease, 460
Eight Miscellaneous Factors, 459, 460
Eight Principles of Differential Diagnosis, 465
Eight Trigrams, 270, 271, 286, 610-612
Eighteen Classifications of Qi, 321
Eighth Lunar Month, 80
Electricity, 117, 124, 126, 128, 129, 141, 581, 631
Elemental Constitutions, 83, 95, 99, 100, 106, 107, 114, 115, 320, 462, 612
Elements, 57, 75, 98, 99, 107, 118, 119, 249, 250, 251, 268, 269, 270, 273, 276, 281, 290, 299, 308,

310, 311, 313, 469, 493, 494, 496, 497, 555, 556, 575, 612, 654, 655, 663, 675, 690, 838, 870, 871, 878
Emaciation, 206, 484, 594, 791, 808, 825, 914
Embryological Development, 67, 71, 200, 206
Emotional Components of Cancer, 898
Emotional Disharmony, 468, 878
Emotional Disorder, 882
Empathic Communication, 84, 138, 139, 513, 519
Emperor, 90, 91, 138, 144, 268, 293, 296, 333, 529, 607, 609, 767, 777, 787, 801, 811
Empty Qi, 484, 486, 488
Endocrine System, 392, 394, 403
Endorphins, 129, 635, 899, 922
Energetic Armoring, 431, 600, 602, 606, 688, 778
Energetic Barriers, 327
Energetic Blockages, 598
Energetic Boundary Invasion, 581, 582
Energetic Circle Drawing Pattern, 546, 547, 550, 551
Energetic Complications, 600, 601, 606
Energetic Cords, 552-555, 624, 905, 906
Energetic Cupping, 649, 659
Energetic Depletion, 559, 560, 569, 600-603, 606
Energetic Disharmony, 459
Energetic Disorder, 461
Energetic Grids, 88, 91, 272, 326, 327, 561, 925
Energetic Leakage, 600, 603, 606
Energetic Medicine, 84, 157, 259, 628, 766, 869
Energetic Point Therapy, 57, 64-66, 247, 405, 665, 669
Energy Balancing Procedures, 597
Energy Projection, 118, 120, 155, 247, 326, 343, 348, 349, 351, 561, 631, 633 649, 651, 654, 769
Enuresis, 184, 219, 220, 766, 788, 802, 812
Environmental Energy, 48, 67-69, 88, 125, 149, 161, 199, 268, 274, 302, 307, 327, 517, 547, 553, 560, 724, 726, 739
Environmental Force, 270
Environmental Qi, 86, 144, 152, 286, 302, 306, 307, 324, 351, 587, 391, 572, 846
Epigastric Pain, 471, 496, 768, 792, 796, 850
Esophageal Cancer, 914
Esophagus, 176, 180, 914
Eternal Soul, 48, 74-76, 80, 86, 87, 90, 92, 93, 138, 251, 334-338, 340, 341, 401, 436, 447, 349, 444, 616
Ethics, Clinical, 576, 580, 578
Etiology During Adulthood, 458
Etiology During Childhood, 458
Etiology Within the Womb, 457
Eustachian Tubes, 741
Evil Qi, 290, 322-324, 357, 377, 431, 459, 460, 570, 571, 590, 664, 679, 692, 779, 803
Evil States, 437, 439
Evil Wind, 851
Excess Body Fluids, 492
Excess Heat, 51, 126, 134, 260, 394, 395, 488, 490, 510, 594, 664, 706, 707, 713, 731, 733, 783, 789, 803, 813, 823, 829, 839, 841, 856, 866, 897, 908, 911, 913, 914, 915, 916, 917
Excess Liver Fire, 364, 776, 781, 783, 863, 890, 906, 907, 911
Excess Qi, 58, 59, 61, 107, 108, 129, 140, 197, 243, 310-312, 377, 387, 388, 399, 405, 486, 488, 532, 551, 593, 595, 612, 669, 680, 687, 740, 744, 745, 779, 782, 783
Expanded Energy Stagnation, 600, 602
Extended Fan Palm Technique, 552, 634, 640, 650-653, 658, 659, 773-776, 782-785, 791, 794-799, 805-808, 810, 816, 817, 819, 820, 825 827, 829, 830, 853, 854, 866, 867, 882
External Pathogenic Factors, 48, 64, 239, 251, 312, 322, 323, 327, 328, 465, 466, 471, 503, 613, 699, 807
External Wei Qi Fields, 64, 151, 263
Extra Point, 572, 590, 742
Extraordinary Organs, 141, 197, 198, 257
Extroverted Structure, 114

F

Facial Paralysis (Bells Palsy), 194, 212, 467, 864, 866
Facing the Death of a Patient, 625
Faith Projection, 532
Fall Equinox, 573
False Self, 441
False Yang, 475, 477
False Yin, 478, 477
Fascia, 61, 67, 95, 150, 159, 163, 164, 228, 229, 241, 552, 673, 675, 679, 817, 927
Fear, 64, 75, 76, 89, 99, 104, 106-108, 129, 142, 149, 151, 154, 172, 182, 187, 327, 330, 335, 348, 365, 368, 404, 413, 427, 429, 432, 439, 445, 452, 460, 470, 488, 508, 512, 518
Febrile Diseases, 59, 501, 502, 504, 798, 838
Feng, Lida, 904
Feng Shui, 119, 270
Fetal Toxins, 68, 77, 458
Fetus, 68-77, 80-83, 86, 88, 99, 148, 197, 204, 206, 208, 257, 269, 275, 317, 320, 322, 457, 516, 517, 553, 684, 686, 858, 859, 860
Fibroadenoma, 854, 855
Fifteen Collaterals, 217
Fifth Lunar Month, 77

12. Now reverse the direction of energy flow to a clockwise direction by circling from the front toward the right, to the back, and to the left. Circle the ***Halo*** nine times, ending with the pearl at the front. Then cross the front to back, and right to left sides. Finish by bringing the pearl to the front of the halo.



Fig. 8.6 *Reverse the direction clockwise.*

13. Next bring the pearl back into the right side of the ***Crown***. Circle toward the right nine times, bringing the pearl to the back, to the left, and ending at the front of the crown each time. Then use the pearl to cross the front, back, and two sides. Return the pearl to the front of the crown.
14. Move the pearl down to the upper tip of the right ear. Circle from the right ear to the back of the head, to the top of the left ear, and to the ***Mideyebrow*** nine times. End at the mideyebrow. Use the pearl to cross the front, back, and two sides at this level, and return it to the front to the mideyebrow position.

Fire Cycle, 157, 201, 260, 293, 294, 646, 662, 707, 719-721, 784, 812, 817, 839, 845, 854, 867, 868, 908, 917
Fire Element, 79, 98, 100, 137, 251, 293, 493, 653, 676
Fire Jing, 77
First Lunar Month, 72
Five Agents, 74-78, 86, 87, 99, 118, 137, 292, 333-335, 347
Five Dominions of Energy, 45
Five Element Cycles, 878
Five Element Organs, 296
Five Element Theory, 313, 333, 463
Five Elemental Animals, 270
Five Elemental Constitutions, 83, 95, 99, 100, 106, 107, 114, 115, 320, 462, 612
Five Energetic Fields, 47, 326
Five Essence Spirits, 75, 90, 139, 141, 334, 346, 847, 870
Five Flavors, 310, 311, 313
Five Orbs, 77, 78
Five Palms Hot, 471, 802
Five Passes, 424, 604, 605
Five Portals of the Earthly Gate, 148, 342
Five Portals of the Heavenly Gate, 342
Five Sense Organs, 217, 242
Five Stages of Healing, 687
Five Thunder Fingers, 594, 641, 647
Five Tissues, 242
Five Yang Organs, 82
Five Yin Organs, 75, 77, 78, 80, 82, 84, 90, 137, 141, 204, 292, 295, 329, 333, 339, 341-344, 372, 376, 419, 429, 452, 572, 615, 655, 657, 663, 699, 724, 743, 749, 811, 837, 849, 870, 871, 873, 876
Fixation, 621
Flat Palm Detection, 521, 522, 554
Fluids, 60, 73, 74, 76, 92, 119, 137, 159, 163-166, 170, 174, 182, 184, 189, 191-193, 241, 242, 310, 311, 312, 315, 318, 322-324, 333, 459, 466, 470, 472, 473, 478, 481, 483, 490-492, 495, 496, 498, 501, 504, 537, 602, 616, 687, 752, 791, 798, 801, 871, 881, 897, 920
Food and Color, 123
Food Qi, 137, 321, 324, 837
Form School (Feng Shui), 270
Four Bigs, 501-503, 505
Four Categories of Energetic Points, 246
Four Doors, 749
Four Levels, 57, 462, 502, 510
Four Principle Time Periods, 278, 657
Four Seasonal Peak Transitions, 279
Four Winds, 306
Fourth Lunar Month , 76
Freud, Sigmund, 516, 621

G

Gall Bladder, 160, 166-168, 182, 191, 192, 194, 257, 260
Gall Bladder Channel, 73, 166, 168, 194, 215, 219, 222, 229, 253, 375, 560, 595, 707, 768, 772, 774, 815
Gall Bladder Divergent Channel, 222, 223
Gallstones, 119, 773, 775
Gastric and Duodenal Ulcers, 789, 797
Gastritis, 208, 695, 789, 796
Gastroptosis, 360, 788
Gate of Access, 292
Gate of Life (Mingmen), 135, 154, 670, 746, 811
Gate of the Moon, 279, 280
Gathering Qi, 137, 303, 305, 306, 322, 324, 391, 469, 641, 688, 726-728
Gathering Sun, 688
Generated Heat, 126
Geriatrics, 567, 836, 843
Gershon, Michael, 134, 135
Ghost Points, 254, 670, 884
Ghosts (Gui), 351, 435, 436, 439, 441, 444, 445, 884
Gill, Jason, 929
Gold, 120, 131, 132, 148, 156, 283, 293, 294, 307, 331, 406, 431, 452, 573, 624, 640, 657, 658, 661, 701, 719, 905
Gold, Philip, 426
Governing Vessel, 198, 200-203, 215, 220, 221, 253, 259, 260, 849, 866
Grasping and Shaking Method, 676, 677
Green, 53, 101, 121-123, 155, 293, 296, 307, 308, 310, 425, 433, 439, 492, 496, 508, 574, 575, 658, 701, 770, 851, 852, 857
Grief, 48, 64, 75, 88, 99, 104, 105, 108, 129, 155, 170, 172, 339, 404, 413, 427, 432, 439, 445-447, 460, 488, 508, 559, 581, 594, 599, 600, 602, 616, 617, 619, 708, 844, 855, 857, 871-875, 877, 890-892, 894, 899, 907, 922
Gu Qi (Food Qi), 83, 137, 163, 176, 180, 191, 309, 319, 321, 322, 324, 489, 495, 496, 537, 787, 837
Gua Sha, 57, 61, 62, 63, 565
Gui (Ghosts), 86, 93, 334, 338, 436, 444, 445, 611, 875
Guiding Qi, 779, 803, 368
Gynecology, 567, 836, 849, 860

H

Hai Dian University, Medical Qigong College, 51, 69
Hand Postures for Qi Emission, 634
He, Si Hai, 689
Headaches, 54, 64, 111, 115, 155, 198, 202, 211, 214, 219, 394, 397, 403, 421, 422, 426, 495, 518, 569, 599, 672, 768, 769, 777, 781, 801, 802, 812, 818, 823, 829, 831, 832, 833, 850, 890
Healing Emotional Trauma, 623
Healing Sound Therapy, 118, 699, 710, 919
Heart, 80, 84, 99, 140, 152, 179, 214, 220, 281, 293, 337, 338, 340, 341, 343, 430, 490, 495, 496, 497, 560, 603, 606, 616, 664, 726, 769, 779, 817, 838, 872, 886
Heart Channel, 178, 180, 194, 220, 235, 279, 778
Heart Diseases, 379, 384, 669, 777, 778, 780
Heart Divergent Channel, 222, 226
Heart Fire, 123, 127, 137, 151, 180, 310, 311, 430, 495, 558, 671, 704, 744, 778, 779, 823, 831, 838, 839, 843, 876
Heart Massage, 691, 693, 694, 695, 696, 697, 779, 785
Heat Deficiency, 502
Heaven Qi, 67, 83, 87, 125, 132, 139, 140, 141, 273, 308, 324, 372, 381, 386
Heavenly Stems, 161, 268, 270, 281, 286, 296, 297, 299
Heavenly Transpersonal Point, 576, 661
Hemiplegia, 864, 865
Hemoptysis, 785, 807, 808, 850
Hepatitis, 383, 425, 567, 770, 776, 913
Hepatolithiasis, 776
Hepatomegaly, 913
Hepatosplenomegaly, 770
Herbal Medicine, 49, 50, 60, 164, 336, 565, 566
Herbalist, 60, 61, 566, 569
Herpes Simplex, 472
Hexagram, 109, 111-115, 277, 278, 279, 363
Hibernation Breathing, 399, 689
Hidden Power (An Jing), 48, 260
High Blood Pressure (Hypertension), 64, 379, 406, 443, 781, 783, 863, 890
History of Cancer Treatments, 895
Hollow Organ, 767, 777, 787, 801, 811
Hologram, 325, 326, 404, 516, 581
Hong, Liu , 912
Hostile Forces, 89, 438, 442
Hou Tian Zhi Qi, 321
Housing the Shen, 48, 178, 337, 342, 343
Howell, Madeleine, 53, 56
Hua Jing (Mysterious Power), 48
Hua, Tuo, 924
Huiyin Point, 145, 201, 284, 342, 550, 573
Hun (Ethereal Soul), 48, 74-78, 80, 84, 86, 87, 88, 90-92, 132, 138, 139, 141, 146, 168, 250, 251, 273, 333-341, 344, 347, 371, 401, 409, 420, 424, 429, 435, 436, 438, 441, 442, 444, 446-448, 460, 574, 604, 616, 717, 724, 767, 818, 839, 847, 865, 871, 872, 890
Hyperhidrosis, 791
Hypertension, 51, 54, 99, 180, 211, 214, 360, 375, 391, 394, 403, 425, 565, 566, 669, 672, 770, 774, 777, 779, 780, 781, 782, 783, 823, 828, 829, 850, 865, 890
Hyperthyroidism, 781, 784, 791
Hypochondriac Pain, 215, 498, 768, 770, 772, 775, 776, 874, 913
Hyposmia, 803
Hypotension, 210, 214, 376, 425

I

I Ching, 109
Id, 621
Immortal, 842
Immune System, 47, 115, 137, 154, 198, 241, 260, 274, 322, 341, 385, 400, 403, 426, 430, 470, 552, 598, 620, 684-686, 753, 807, 840, 895, 898-902, 905, 906, 919-921, 929
Impotence, 154, 202, 230, 695, 726, 819, 820
Improper Yin and Yang Energy Balance, 824
Incredible Wonders, 588, 590
Indago, 575
Infatuation, 437, 444
Influenza, 470, 788, 801-805, 809
inner-vision, 85, 259, 325, 346, 371, 405
Insight Meditation, 407
Insomnia, 64, 138, 180, 204, 211-214, 250, 322, 335, 395, 471, 478, 484, 495, 497, 502, 504, 565, 672, 697, 768, 778-782, 784, 817, 818, 823, 825, 828, 830,840, 843, 847, 890
Insulting Cycle, 497
Intent (Yi), 49, 80, 134, 191, 278, 332, 361, 378, 394, 398, 411, 427, 534, 617, 648, 650, 691-696, 813
Internal Dialogues, 86, 87
Internal Organ Disorders, 838
Internal Pathogenic Factors, 64, 323, 467, 699
Internal Viewing (Inner-Vision), 520
Internal Wind, 202, 465, 467, 863, 881

Introverted Structure, 114
Intuition, 101, 102, 134, 140, 143, 144, 146, 154-156, 197, 201, 286, 328, 336, 343, 544, 577, 617, 649
Intuitive and Perceptual Diagnosis, 507, 512, 513, 521
Invading Cycle, 497
Invisible Needle Therapy, 65, 66, 247, 639, 640, 651, 659, 661-665, 669, 865
Iron Wall, 604

J

Jahnke, Roger, 903
Jaundice, 498, 768, 772, 773, 915
Jia Ji Guan, (Spinal Pass) 605
Jie Gu Therapy, 61, 63, 565
Jing Point Therapy, 57, 61-63, 228, 247, 595, 783, 831, 855-858, 890, 920
Jing-Luo, 159, 323
Jing-Shen Bing (Mental Illness), 141
Johnson, Mark, 846
Joy, 75, 99, 129, 178, 189, 193, 404, 428, 429, 431, 460, 469, 488, 508, 615, 619, 872-879
Jue Yin, 57, 160, 222, 501-503, 612, 884
Juice of Jade, 372, 743
Jung, Carl G., 516

K

Kaku, Michio, 665
Karma, 70, 86, 268, 416
Ketheric Matter, 328
Kidney Channel, 81, 107, 154, 184, 187, 194, 206, 208, 210, 219, 237, 706, 814, 819, 820, 850
Kidney Diseases, 426, 710, 713, 766, 811-815
Kidney Divergent Channel, 208, 222, 225
Kidney Fire, 127, 133
Kidney Jing, 133, 137, 170, 184, 260, 319, 320, 812, 815, 816, 838, 847
Kidney Massage, 695, 813, 818
Kidney Qi, 133, 184, 185, 312, 377, 380, 382, 387, 391, 461, 491, 495, 498, 799, 807, 811, 813, 815, 838, 843, 858, 872, 876, 877
Kinetic Communication, 84, 134, 347, 513
Kneading Tiger Palm, 559, 640, 647, 650, 659, 799, 833
Knees, 109, 111, 113, 215, 217, 249, 251, 360-365, 368, 422, 428, 558, 575, 600, 651, 691, 724, 746, 747, 748, 749, 753, 757, 761, 776, 783, 791, 804, 817, 820, 842, 843, 845, 868, 876, 893, 912

L

Lao, Zi, 541
Large Intestine, 71, 78-82, 98, 123, 136, 160, 161, 166, 170, 172-174, 180, 191, 194, 215, 219, 220, 222, 224, 232, 240, 252-254, 257, 276, 281, 182, 312, 339, 366, 378, 382, 387, 501-504, 525, 595, 616, 713, 715, 751, 801-803, 829, 830, 831, 875, 916, 917, 920
Large Intestine Channel, 80, 81, 172, 174, 194, 219, 232, 382, 595, 802, 803, 829
Large Intestine Divergent Channel, 222, 224
Lashley, Karl, 404
Lee, Richard H., 119, 125, 129, 880, 881
Leukocyte, 901, 902
Leukorrhea, 206, 816, 910
Ley lines, 271
Li, Fu Dong, 51
Li, Shi Zhen, 200, 519
Light, 166, 326, 331, 342, 347, 410, 442, 530, 542, 548
Light Meditation, 342, 904, 925, 928
Liu, Bing, 274
Liver, 168, 170, 174, 182, 260, 310, 929
Liver Cancer, 383, 715, 770, 913, 920
Liver Channel, 72, 168-170, 187, 194, 219, 222, 230, 380, 384, 471, 770, 775
Liver Diseases, 710, 712, 766-769, 772
Liver Divergent Channel, 222, 223
Liver Fire, 117, 155, 215, 364, 382, 497, 595, 729, 768, 769, 776, 781, 783, 807-809, 855, 857-859, 863, 871, 890, 906, 907, 911, 912
Liver Massage, 693, 774, 775, 776, 854
Liver Wind, 117, 505, 745, 768, 815, 816, 828, 838, 867, 890
Lo Scroll, 607
Locations of Energetic Blockages, 598
Long Distance Therapy, 530, 532
Lords of the Three Dantians, 84, 85, 86
Lower Burner, 57, 182, 191-193, 204, 211, 322, 387, 504, 505, 510, 598, 610, 670, 671, 700, 729-731, 747, 791, 794, 799, 812, 849, 851, 909, 911, 920
Lower Dantian, 363, 397
Lu, Guo Hong, 51
Lumbago, 362, 421, 670, 726, 814, 816-820, 853
Lung Cancer, 379, 567, 711, 713, 913, 920
Lung Channel, 79, 166, 170, 172, 194, 220, 231, 282, 802, 803, 806-809, 857, 893, 903
Lung Diseases, 155, 172, 360, 492, 731, 801-804, 892, 913

Lung Divergent Channel, 222, 224
Lung Massage, 694
Lungs, 123, 124, 137-139, 155, 161, 166, 168, 170, 172, 174, 178, 184, 191-193, 198
Luo points, 217, 218, 220, 761
Lymphocytes, 684, 685
Lymphocytes, 178, 685, 867, 901
Lymphoma, 915
Lymphosarcoma, 896

M

Maciocia, Giovanni, 194
Macrocosmic Orbit, 189
Macrophages, 684, 685, 867, 898, 901
Magic Square, 200, 270, 607, 608, 610-612, 679, 690
Magnetic Energy, 117, 124, 125, 581
Magnetic Therapy, 57, 58, 126, 856
Malar Flushes, 497
Malignant Tumors, 689, 896, 904, 907, 909, 913-916, 927
Mantra, 89, 406, 424, 701, 792, 882
Marrow, 57, 64, 141, 143, 184, 198, 202, 253, 254, 257, 259, 260, 263, 288, 315, 318, 319, 324, 326, 330, 331, 359, 431, 461, 591, 616, 671, 673, 723, 724, 837, 838, 888
Master and Couple Points, 252
Master Points, 213, 215, 252
Mastitis, 823, 854, 855
Meditation, 282, 288, 294, 307, 332, 376, 407, 426, 430, 431, 448, 520, 527, 532, 546, 547, 572, 573, 574, 591, 622, 623, 669, 688, 718, 882, 900, 904, 905, 912, 917, 928
Meditations for Cancer Patients, 904
Memory, 113, 114, 119, 140, 141, 149, 176, 178, 187, 202, 259, 319, 329, 337, 338, 340, 341, 351, 395, 404, 444, 445, 448, 450, 452, 484, 490, 603, 616-618, 621, 650, 685, 686, 777, 818, 825, 843, 844, 864, 866, 868, 872, 873, 879, 882, 890, 922, 927
Meng, Xian Tong, 548
Menopause, 204, 850, 852, 907, 908
Menoxenia, 854
Menstrual Complications, 852
Menstruation, 204, 206, 257, 274, 363, 590, 591, 794, 849-854
Mental Dao Yin Training, 357, 401, 421, 404, 405, 425
Mental Delusions, 437
Mental Disorder, 438, 508, 677
Mental Restlessness, 214, 250, 471, 504
Meridians, 159
Message (Xin Xi), 80, 134, 139, 142-245, 327, 340, 343, 344, 346, 349, 352, 488, 514-516, 534, 535, 551, 599, 618, 625, 720, 922
Metal Element, 98, 293, 493, 653, 676
Metal Jing, 78
Microcosmic Fire Cycle, 201
Microcosmic Orbit, 120, 157, 189, 199, 242, 260, 293, 294, 304, 365, 366, 424, 432, 547, 558-560, 589, 604, 645-647, 662, 688, 720-723, 726, 728, 733, 784, 812, 817, 831, 832, 839, 845, 854, 856, 858, 866-868, 908, 909, 911, 917, 924, 928
Microcosmic Water Cycle, 201
Middle Burner 57, 87, 139, 170, 191-193, 242, 321, 322, 502-505, 598, 610, 670, 671, 700, 730, 731, 768, 788, 789, 791, 793, 796
Middle Dantian, 131, 132, 137-140, 145-147, 154, 155, 161, 189, 198, 776, 783, 785, 874
Migraine, 54, 64, 394, 599, 829, 830-833, 890
Migrating Qi, 600, 603
Ming Jing (Obvious Power), 48
Ming, Qing Zhu, 50
Mingmen, 560, 590, 605, 670, 785, 812, 813, 842
Mingmen Fire, 127, 133, 368, 705, 706, 811-813, 859, 876
Moon Cream, 288, 688, 775, 785, 809, 819
Morphogenic Field, 315
Mother Element, 309, 401, 495, 496
Moxa Therapy, 57-59, 128, 212, 239, 565, 566, 864
Multiple Personality Disorder, 437, 442, 443, 445, 880
Multiple Sclerosis (MS), 863, 867, 868
Muscle Tendon Channel, 60, 161, 163, 217, 228, 239
Myocarditis, 777
Myss, Caroline, 141
Mysterious Pass, 398
Mysterious Power (Hua Jing), 48
Mysterious Wonders, 588, 589

N

Nader, Ralph, 847
Natural Breathing, 361, 379, 391-393, 397, 651, 700, 701, 718, 719, 752, 783, 809, 845, 854, 868
Necrosis, 774
Nei Dan Shu, 718, 719
Nei Guan, 520, 688
Nei Jing, 355, 611, 881, 886
Neoplasm, 907, 908, 909, 910, 911

Nephritis, 781, 814
Neurology, 50, 567, 836, 863
Neuropeptides, 135, 899
Nine Chambers, 82, 135, 136, 139, 140, 143, 144, 292
Nine Palaces, 296
Nine Stars, 135
Nordenstrom, Bjorn, 128
Ninth Lunar Month, 81
Niu, Yu Hua, 51
Nutritive Qi, 137

O

Objective World, 438
Obstructed Qi, 486, 488, 825, 826, 892
Obvious Power (Ming Jing), 48
Occipital Pass, 605
Old Age, 461, 486, 781, 843
Oncology, 50, 567, 836, 895, 903, 904
One Finger Skill Technique, 637, 638, 639, 658, 930
Opening and Closing the Three Dantians, 152, 170, 239, 322, 359, 377-383, 399, 423, 425, 433, 458, 467, 640,688, 692-697, 729, 731, 737, 824
Opisthotonosis, 424
Orange, 121, 122, 154, 311,526, 857, 915
Organ Dysfunction, 403, 831, 860
Organ Regulation, 62, 63, 751, 752, 797,850
Organ Transplantation, 927
Orifices, 79-81, 92, 159, 187, 292, 378, 491, 672, 728, 811, 815, 823, 838, 839, 858, 881, 886-888
Original Energy (Yuan Qi), 316, 317
Original Essence (Yuan Jing), 316, 317, 318, 331
Original Force, 268, 320
Original Spirit (Yuan Shen), 84, 85, 90, 316-318, 419
Original Yang (Kidney), 321
Original Yin (Kidney), 321
Osteoporosis, 430, 827
Outer Spiritual Barrier, 327
Ovarian Cysts, 64, 601, 734, 766, 857, 858
Ovarian Cysts and Uterine Tumors, 857

P

Palace of Eternal Frost, 279
Palace of Universal Yang, 279
Palpitation, 180, 384, 495, 497, 670, 777, 779, 782, 784, 785, 818, 823, 828, 843, 854, 887
Pancreas, 111, 122, 153, 154, 176, 191, 311, 505, 525 610, 791, 915, 916, 927, 928
Pancreatic Cancer, 689, 915
Pancreatitis, 775, 793
Pang, Dong Hui, 51
Paraplegia, 865
Parenchymal Cells, 774
Parkinson's Disease, 812, 847
Past Life, 344, 516-518, 887
Pediatric, 62, 567, 837-839
Penetrating Wind (Stroke), 863
Perceptual Communication Training, 519
Peribronchial, 806, 808
Pericardium, 71, 74, 79, 122, 140, 160, 161, 166, 178, 187-194, 213, 214, 219,220, 222, 227, 238, 240, 252, 253, 257, 276, 282, 375, 384, 490, 502-505, 664, 706, 778, 784, 785, 875, 889, 925
Pericardium Channel, 74, 187, 189, 194, 213, 220, 238, 375, 384, 504, 706, 778, 784, 785
Pericardium Divergent Channel, 222, 227
Perineum, 83, 109, 110, 111, 125, 127, 132, 133, 135, 145, 147, 148, 149, 151, 154, 191, 200, 201, 205, 206, 221, 284, 294, 295, 331, 332, 342, 363, 365, 393, 422, 575, 700, 722, 724, 748, 752, 814, 886, 911, 912
Peristalsis, 728, 748
Peritonitis, 794
Pernicious Influences, 470
Personal Subconscious Mind, 409, 410, 411,441
Peyer's Patch, 684
Phagocytes, 684, 898, 899
Phantom Embryo, 860, 861
Phantom Organ, 925
Phantom Pain, 929
Phlegm, 473, 492, 495, 504, 505, 602, 667, 669, 671, 683, 702, 703, 744, 781, 788, 802, 805-809, 815, 828, 829
Phlegm Fire, 176, 669, 784, 792, 815, 828, 865, 881
Phobias, 518, 882, 886
Piezoelectric, 129, 263
Pineal Gland, 141, 144, 156, 366, 409, 410, 520, 521, 726, 741
Pink, 426, 779
Pituitary Gland, 155, 366, 392, 394, 440, 520, 521, 635, 723, 832
Po (Corporeal Soul), 74-76, 80, 83-92, 134, 138, 139, 141, 146, 170, 250, 251, 273, 333-335, 338-341, 344, 347, 365, 371, 401, 403, 409, 424, 429, 436, 438, 444, 446, 447, 460, 574, 604, 616, 801, 847, 865, 871, 874, 881, 886
Point Names, 249
Point Respiration, 692, 693, 694, 695, 696, 697
Polarity, 70, 129, 152, 199, 200, 250, 268, 536, 581, 619, 639, 662, 678

Poltergeists, 435,436, 437
Polydipsia, 791
Polyphagia, 791
Polyuria, 791
Portal Hypertension, 774
Postnatal Jing, 137, 316-320, 324, 333, 607, 717
Postnatal Mind, 346, 402, 409
Postnatal Qi, 133, 137, 174, 198, 199, 309, 316, 320, 321, 333, 338, 459, 588, 603, 708, 720, 837
Postnatal Shen, 316, 333-337, 430
Postoperative Therapy, 921, 924
Posttraumatic Stress Disorder, 878, 880
Postural Dao Yin Training, 355, 359, 363
Prayer, 46, 87, 90, 91, 99, 118, 127, 146, 148, 149, 260, 305, 317, 318, 331, 333, 337, 529, 530, 535, 542, 544, 548, 687, 844, 861, 876
Pregnancy, 68, 69, 72-74, 81, 99, 204, 206, 257, 274, 275, 321, 457, 459, 590, 591, 686, 781, 849, 850, 858, 860, 861
Prenatal Jing, 141, 316, 318, 319, 320, 324, 333, 517, 686
Prenatal Jing, 517, 717, 720
Prenatal Qi, 68, 84, 120, 138,198, 199, 260, 279, 316, 317, 320, 321, 333, 723, 837
Prenatal Shen, 316, 333, 335, 337
Preoperative Therapy, 921
Prescriptions, 561, 784, 857, 902
Primary Channels, 71, 83, 84, 127, 133, 148, 159, 160-166, 189, 194-199, 206, 217, 218, 220, 222, 228, 239, 240, 241, 246, 249, 250, 253, 257, 281, 282, 284, 296, 387, 611, 720, 850
Prostate Cancer, 689, 715, 734, 911, 912
Protective Qi (Wei Qi), 132, 191, 215, 322, 323, 324
Psoas Muscles, 893, 894
Psychic Powers, 512
Psychogenic Polyuria, 791
Psychology, 49, 55, 56, 98, 117, 344, 445, 449, 512, 567, 869, 870
Psychometry, 534
Psychoneurosis, 770, 814
Psychosexual Qi Deviations, 438, 600, 603, 606
Psychosomatic, 532, 766, 820, 828, 829
Psychotherapy, 336, 861, 877, 878, 891
Pulling Down The Heavens, 283, 288, 688, 692-696, 700, 702, 711, 724, 725, 761
Pulmonary Emphysema, 803, 806
Pulse, 122, 148, 151, 152, 247, 248, 274, 312, 316, 326, 330, 331, 341, 349, 359, 391, 392, 470-473, 476-481, 494, 501-505, 509, 510, 562, 589, 640, 674, 676, 677, 777, 779, 837, 864, 882, 904, 922, 924
Pungent Foods, 311, 312, 801
Purgation Techniques, 594, 595, 596
Purging, 84, 284, 396, 397, 419, 452, 537, 551-559, 839
Purpura, 669
Pyelonephritis, 818

Q

Qi, Blood and Body Fluid, 463, 511
Qi Compression, 598
Qi Deficiency, 247, 422, 459, 472, 489, 491, 777, 788, 799, 802, 807, 838, 849, 854, 859
Qi Deviation, 419-426, 433, 434, 437, 460, 545, 569, 570, 590, 596, 600, 603, 606, 687, 699, 700, 719, 720, 723, 796, 900
Qi Dysfunction, 768, 779, 789, 803, 813
Qi Extension Techniques, 643, 930
Qi Manipulation, 598, 631, 674, 678, 772, 775, 779, 789, 803, 805, 854
Qi Regulation, 320, 374, 375, 399, 434, 582, 596, 597, 646, 708, 718, 719 824, 845
Qi Reservoirs , 197
Qi Stagnation, 471, 486, 509
Qigong Clinic, 50- 56, 64, 303, 304, 392, 419, 439, 507, 521, 548, 559, 621, 696, 717, 791, 824, 859, 863, 884, 886, 902, 904
Qigong Massage, 65, 543, 622, 623, 643, 673-675, 679, 683, 740, 839, 856
Qihai, 135, 198, 377, 433, 558, 669, 745
Quiescent, 278, 306, 318, 344, 355, 356, 391, 398, 406, 407, 449, 453, 493, 520, 572, 583, 591, 625, 687,689, 768, 781, 785, 779, 833, 857, 900

R

Rachialgia, 814
Radiation, 121, 128, 273, 302, 411, 461, 527, 551, 631, 707, 713, 836, 895, 897, 919-921, 927-929
Rebellious Qi, 208, 325, 432, 483, 487, 488, 594, 671, 745, 826, 857, 908, 920
Reconstructive Qi Therapy, 826
Red 124, 147, 154, 194, 198, 290, 294, 307, 308, 426, 470, 471, 477, 521, 529, 570, 573, 575, 633, 639, 658, 701, 751, 752, 777, 779, 784, 785, 797, 841, 851, 852, 854, 855, 857, 864, 868, 872, 915, 916
Reflexology, 61, 62, 112
Regression, 329, 445, 516-518, 546, 604, 621, 861, 887
Repression, 449, 578, 621, 890
Respiratory Dao Yin Training, 357, 397

Restrictive Cycle, 495, 497
Reverse Breathing, 394, 422, 695, 721, 726
Rhabdomyosarcoma, 896
Rheumatic Heart Disease, 777, 779, 785
Rheumatosis, 785
Rhinitis, 801, 802
Righteous Qi (Zheng Qi), 323, 324, 357, 486, 548, 552, 570, 590, 678, 910
Rigor, 772
Rooting, 380, 430, 432, 546-550, 603, 633, 636, 761
Ross, Elisabeth Kubler, 626

S

Sacred Healing Space, 541, 546, 547, 548, 549
Sadness, 75, 88, 99, 138, 170, 172, 339, 439, 446, 447, 452, 460, 469, 508, 615-617, 844, 874, 875, 878, 888, 892
Sagen, Thea, 927
Saliva, 75, 166, 324, 312, 372, 387, 491, 616, 708, 719, 743, 780
Salty Food, 313
San Bao (Three Treasures), 315
Sancier, Kenneth M., 904
Sarcoma, 896, 915
Sclera, 772, 915
Sea of Blood, 64, 71, 198, 199, 206, 253, 326, 329, 330, 670, 849, 851, 859
Sea of Energy, 326, 889
Sea of Grain and Water, 198
Sea of Marrow, 57, 64, 141, 143, 198, 253, 254, 259, 326, 330, 331, 461, 671, 838, 888
Sea of Qi, 133, 135, 137, 198, 252, 253, 669, 745, 887, 888
Sea of Yang Channels, 201
Sea of Yin Channels, 204
Seat of Emotions, 328
Second Lunar Month, 73
Self-Massage, 377, 386, 387, 388, 596, 687, 691
Self-Regulation Therapy, 57, 64, 65, 687
Seven Corporeal Souls, 75, 80, 83, 86-90, 134, 170, 251, 334, 338, 340, 341, 365, 401, 446, 447, 616
Seven Emotions, 98, 99, 467, 468, 469, 470, 488, 612, 843
Seven Essential Stars, 79, 80
Seven Internal Factors, 460
Seven Orifices, 292
Seventh Lunar Month, 79
Shaman, 529
Shang Ling (Pleasent Soul), 86, 87, 347
Shao Yang, 57, 109, 160, 222, 501-503, 612
Shao Yin, 57, 109, 160, 222, 501-503, 612
Shealy, C. Norman, 141
Shen, Chang, 532
Shengong (Spirit Skill Training), 56, 318, 326, 332, 342, 343, 348, 449, 541, 583
Shening Out, 342, 602, 604
Shimian Point, 907
Shu Point, 193, 249, 250, 251, 370, 611
Si Ming (Administrator of Destiny), 84-86, 90, 92, 347
Silver 84, 85, 151, 288, 307, 337, 348, 349, 431, 451, 452, 624, 905
Sinusitis, 382, 788, 792, 802, 809, 810
Sishencong Points, 149, 342, 548, 839
Sitting Meditation, 242, 337, 360, 785
Six External Factors, 460
Six Functions of Qi, 323
Six Stages, 57, 308, 462, 501, 503, 504, 510
Six Storage Areas, 78, 79
Six Transportations of Shen, 144, 344, 345, 346, 411
Sixth Lunar Month, 78, 79
Skin Zones, 160, 161, 163, 239, 240, 241, 276, 508
Sleep, 89, 91, 99, 166, 178, 210, 211, 212, 254, 274, 317, 323, 333, 335-337, 341, 360, 361, 407, 414, 421, 426, 438, 444, 458, 460, 475, 476, 509, 546, 563, 570, 604, 619, 651, 697, 722, 784, 815, 817, 818, 844, 847, 880, 884, 887, 891, 900
Small Intestine, 79, 98, 122, 136, 146, 160, 168, 172, 174, 178, 180-182, 191, 192, 194, 217, 219, 220, 222, 226, 235, 322
Small Intestine Channel, 180, 182, 194, 215, 219, 235, 779
Small Intestine Divergent Channel, 222, 226
Soaring Dragon Technique, 638
Social Oncology, 903, 904
Solid Organs, 165, 710, 801
Soul Extensions, 85, 90, 347
Soul Loss, 443, 444
Soul Retrieval, 91, 439, 442-450, 453, 577, 602, 606, 623, 633 688, 708, 844
Sound Vibration, 65, 117, 118, 155, 406, 701, 702, 710
Spider Nevus, 774
Spinal Pass, 605
Spiraling Energy, 647-649
Spirit Demon, 438-441, 882
Spirit Oppression, 438, 439
Spirit Possession, 143, 254, 438-440, 884, 885
Spirit Soul, 87, 273, 847
Spiritual Dryness, 582
Spleen, 75, 77-83, 99, 111, 122, 123, 160, 163, 166, 174-178, 184, 191-194, 281, 286, 290, 294, 311,

312, 380, 381, 383, 425, 432, 439, 452, 466, 469, 470, 472-474, 479-498, 503, 505, 509, 522, 525, 615, 616, 656-658, 665, 667, 669, 671, 675, 676, 677, 704, 707, 708, 709, 710, 713, 715, 717, 733, 747, 748, 761
Spleen and Stomach Massage, 797, 798
Spleen Channel, 77, 176-178, 194, 206, 209, 217, 219, 221, 234, 775, 789, 853, 930
Spleen Diseases, 710, 712, 787, 788, 789, 791
Spleen Divergent Channel, 222, 225
Splenomegaly, 694
Spring Equinox, 279, 280, 573
Stacking the Bones, 691, 693-695
Standing Meditation, 360, 399
Static Qigong Training, 355, 356, 695,726
Sternum, 139, 204, 260, 261, 600, 700, 731, 755, 795, 796, 808, 809
Stomach, 78, 79, 82, 83, 174-177, 180, 182, 191-194, 198, 276, 281, 293, 309, 311, 319, 321, 322, 363, 368, 385, 403
Stomach Cancer, 385, 567, 713, 714, 897, 915
Stomach Channel, 78, 108, 174, 176, 194, 217, 219, 233, 325, 504, 522, 776, 788, 793, 795
Stomach Diseases, 425, 713, 787, 792, 793
Stomach Divergent Channel, 222, 225
Stream Points, 251, 253, 370
Stroke, 64, 202, 250, 379, 492, 565, 567, 646, 788, 823, 828,863-865, 890
Subconscious Mind, 118, 134, 336, 344, 345, 403, 407, 409-412, 437-439, 441, 453, 458, 513, 517, 555, 561, 623, 625, 898, 927
Subtle Wonders, 359, 588, 589
Summer Solstice, 279, 280, 573
Sun, Simiao, 143, 309, 884
Super Ego, 621
Surgery, 95, 108, 124, 440, 442, 444, 445, 486, 536, 567, 625, 798, 826, 836, 857, 92-929, 930
Sweet Food, 311, 787
Sword Fingers, 433,636, 637, 652, 653, 659, 772, 784, 805, 807, 810, 819, 820, 826, 829, 855, 882, 923
Symptoms, 457, 461-464, 546, 570, 572, 578, 591, 596, 708
Syndrome, 461-464, 467, 468, 472, 474, 480

T

Tai Guang (Eminent Light), 86, 87
Tai Yang, 57, 109, 160, 222, 378, 501, 503, 612, 865, 884
Tai Yi (Great Divinity), 84-86, 92, 347
Tai Yin 57, 109, 160, 222, 501-503, 612, 884
Taiji Pole, 64, 69-71, 83, 84, 86, 88, 89, 91, 92, 118-120, 122, 125, 131, 132, 135, 144, 145, 147-154, 157, 161, 187, 197, 243, 280, 284, 288-290, 293, 294, 296, 306, 307, 326, 328, 331, 332, 334, 341, 342, 344, 347, 363, 364, 366, 386, 400, 410, 436, 451, 453, 494, 531, 532, 541, 547, 548, 550, 551, 559, 560, 572, 588, 594, 603, 606, 611, 645, 646, 701, 723, 740, 778, 782, 783, 812, 813, 824, 924
Taiji Ruler, 433, 434, 688
Tang, Rongchuan, 111
Tapping Method, 595, 596, 676, 678, 882
Taylor, Kylea, 580
Taylor, Stephanie, 53
Ten Thousand Voices, 408
Ten Wings, 271
Tenth Lunar Month, 82
The Six Stages, 308, 462, 501-504, 510
Third Eye, 92, 120, 142, 144, 332, 350, 410, 451, 520, 521, 531, 558, 576, 632, 726, 805, 831, 865
Third Lunar Month, 74, 86
Three Fires, 127
Three Formations of Cancer Growth, 896
Three Functions of Energetic Points, 247
Three Outer Forces, 132, 267-271
Three Periods of Life 457, 458
Three Treasures of Earth, 301, 313
Three Treasures of Heaven, 273, 297
Three Treasures of Man, 69, 267, 315, 316
Three Wonders, 588
Thrombosis, 863, 865, 866, 907
Thrusting Channels, 120, 148, 293-295, 342, 703, 704
Thrusting Method, 676, 677
Thrusting Vessel, 70, 168, 198, 200, 204, 206,-208, 219, 366, 909, 912
Tinnitus, 202, 215, 235, 254, 260, 741, 777, 781, 782, 784, 812, 814-820, 828, 843, 890
Tongue Positions, 372, 658
Tonification and Purgation Guidelines, 596
Tonification and Purgation Methods, 594
Tonification Techniques, 593
Traditional Chinese Medicine, 45, 47-50, 54, 56-58, 61, 67, 69, 86, 93, 95, 97, 100, 119, 138, 144, 159, 163, 164, 165, 176, 193, 217, 228, 249, 268, 272, 281, 312, 321, 330, 332, 401, 402, 457, 460, 465, 473, 474, 489, 490, 492-497, 509, 537, 548, 603, 673, 686, 772, 773, 775, 781, 791, 796, 843, 851, 852, 858, 859, 866, 867, 870, 881, 884, 895, 897, 906, 914, 929

Transference, 65, 68, 160, 315, 338, 488, 515, 572, 577, 579, 582, 689, 823, 874
Transformation, 48, 56, 91, 92, 95, 98, 99, 117, 119, 128, 132, 133, 137, 145, 172, 176, 182, 191-193, 199, 206, 259, 263, 276, 297, 299, 318, 319, 320-322, 338, 411-413, 415, 416, 419, 445, 453, 454, 457, 486, 489, 490, 491, 494, 496, 498, 502, 505, 513, 530, 532, 534, 554, 561, 580, 627, 721, 837, 844, 849, 859, 861, 904, 926
Transient Ischemic Attacks (TIA), 863
Transpersonal Point, 576, 661
Transportation, 111, 163, 172, 176, 192, 338, 490, 737, 798, 837
Trappier, Arthur, 126
Treating Phobias and Depression, 886
Treating Psycho-Emotional Disorders, 890
Treating Tumors and Cancer, 711, 906, 921
Treatment of Scar Tissue, 929
Trigger Points, 246
Trigrams of the Yi-Jing, 607
Triple Burner Channel, 76, 189, 190, 193, 194, 215, 220, 238, 707
Triple Burners, 57, 76-79, 127, 133, 135, 189-193, 222, 227, 282, 321, 374, 478, 479, 503, 504, 510, 612
Triple Burners Divergent Channel, 222, 227
True Fire 127, 135
True Qi (Zhen Qi), 81, 286, 321-324, 381, 382, 387, 726, 903, 906
True Self, 106, 139, 142, 541, 150, 331, 347, 420, 441, 454, 541, 621
True Spirit, 334
Tui Na, 57, 61-63, 65, 461, 565, 631, 839, 890, 930
Tumor, 53, 55, 327, 381, 395, 421, 440, 532, 688, 710, 711, 715, 855-857, 895-899, 902-907, 910, 913, 914, 916, 919, 922, 927, 928
Turbid Qi (Shi Qi), 191, 282, 288, 303, 391, 397, 419, 487, 488, 505, 536, 552, 569-572, 650, 676, 693-695, 701, 724, 751, 768, 778, 788, 789, 793-796, 802, 803, 812, 851, 925
Twelve Chakra Gates, 151, 152, 156, 157, 722
Twelve Divergent Channels, 222
Twelve Earthly Branches, 156, 157, 268-270, 281, 290, 291, 296, 297, 299, 721
Twelve Entry Points, 252
Twelve Exit Points, 252
Twelve Muscle/Tendon Channel, 163, 228
Twelve Pi Hexagrams, 166, 276, 277
Twelve Primary Channels, 71, 83, 84, 127, 133, 159, 160, 163-166, 189, 194-199, 206, 217, 222, 228, 239-241, 253, 281, 282, 284, 296, 611, 720, 850
Twelve Skin Zones, 163, 239, 240, 241, 276
Twelve Yuan-Source Points, 253
Two Gates of Energetic Points, 246

U

Ulcers, 155, 403, 466, 471, 695, 766, 789, 797, 798, 873
Universal Qi, 321, 380, 587, 737
Upper Burner, 57, 166, 191-193, 321, 322, 425, 491, 504, 505, 610, 651, 700, 729, 730, 791, 803, 816
Upper Dantian, 83, 84, 86, 87, 89, 120, 125, 131, 132, 137, 139-147, 155, 156, 161, 199, 283, 288, 289, 317, 328, 332, 342, 347, 350, 366, 371, 372, 377-379, 387, 388, 433, 451, 453, 513, 518-520, 522, 526, 547, 548, 558-560, 569, 576, 581, 598, 599, 603, 632, 636, 645, 646, 651, 726, 727, 740, 778, 783, 823, 824, 830, 840, 886
Uterine Cancer, 908, 911
Uterine Tumor, 858
Uterus, 69, 72-74, 76-82, 108, 133, 136,146, 366, 459, 471, 486, 505, 591, 667, 715, 908-911

V

Vaginal Discharge, 194, 210, 849-852, 910
Vertigo, 254, 495, 554, 672, 741, 770, 781, 784, 818, 828-830, 867
Violet, 121-123, 128, 155, 156, 526, 527, 633, 897
Virtue, 75, 76, 88, 89, 91, 138, 146, 147, 268, 332-334, 339, 340, 544, 549
Visualization, 49, 65, 87, 89, 243, 336, 343, 348, 356, 371, 403, 411, 443, 448, 449, 519, 545, 547, 554, 555, 561, 625, 683, 688, 701, 767, 770, 824, 861, 876, 877, 904, 929
Vlamynck, Jean Ruth, 50, 53, 54
Void (Wuji), 108, 316, 317, 331, 332, 356, 514-516, 612

W

Walking Therapy, 376, 377, 380-386, 868
Wandering Bi, 603
Water Cycle, 201, 269, 708, 720, 723, 839
Water Element, 98, 133, 251, 268, 293, 493, 653, 676
Weather, 124, 215, 270, 279, 280, 281, 290, 293, 301, 307, 322, 465, 479, 501, 816, 826, 827
Wei Lu Guan (Coccyx Pass), 605
Wei Qi (Protective Qi), 48, 57, 64, 126, 132, 137, 140, 145, 149, 151, 164, 322, 324-329, 549, 551, 552, 554, 559, 572, 575, 612

White, 46, 104, 120, 122-124, 137, 138, 147, 148, 206, 210, 241, 260, 288, 293, 294, 306, 307, 311, 327, 331, 338, 406, 412, 414, 415, 425, 431, 439, 451, 452, 471-473, 476, 492, 497, 501, 505, 508, 520-523, 529, 531-534, 536, 547, 573-576, 589, 617, 624, 639, 658, 684, 685, 701, 713, 719, 726, 803, 804, 806, 851-853, 855, 861, 898, 901, 904, 905, 911, 919, 920, 922, 925, 926
Willpower (Zhi), 151, 338, 340, 341, 348, 574, 847
Wind Bi, 603
Wind Cold, 217, 464, 467, 472, 669, 801, 802, 805, 807, 809, 816, 817, 829
Wind Damp, 464, 802, 805, 920
Wind Heat, 217, 467, 472, 505, 669, 670, 798, 801, 802, 805, 809
Wind Phlegm, 492, 828
Wind Stroke, 202, 492, 788, 823
Window of the Sky Points, 254, 886, 887
Windy Breathing Method, 392, 394, 396, 768, 779, 789, 813
Wong, Her Yue, 708
Wood Element, 98, 100, 293, 493, 556, 653, 676, 914
Wood Jing, 79
Worry, 64, 75, 88, 99, 101, 104, 108, 129, 138, 172, 178, 348, 403, 404, 427, 429, 432, 439, 460, 488, 508, 603, 615, 616, 619, 794, 796, 798, 818, 850, 855, 859, 873, 874, 876, 878, 892, 903, 907
Wu Guan (Five Passes), 604
Wu Huo Breathing Method, 394
Wu Jing Shen (Five Essence Spirits), 80, 84, 90, 141, 409, 443, 57, 847, 860, 870, 871
Wu, Ju-Tong, 504
Wu Ying (Without Essence), 84, 86
Wu Zang (Five Yin Organs), 294, 572, 573, 574, 688
Wuji, 45, 85, 132, 144, 148, 149, 267, 316, 317, 332, 344, 345, 356, 371, 398, 415, 514-516, 520, 633

X

Xi Yuan Hospital of Beijing China, 51, 52, 67, 303, 406, 439, 499, 566, 627, 717, 898
Xia Tao Kang (Below Healthy Peach/Life), 84-86, 92, 347
Xiphoid Process, 109, 111, 154, 600, 772, 808, 809
Xu, Hongtao, 52

Y

Yan, De-xin, 688
Yang Channels, 71, 72, 160, 161,165, 166, 172, 174, 180, 182, 189, 558, 595, 651, 690, 734, 745
Yang Deficiency, 472, 480, 495, 502, 777, 781, 783, 785, 788, 812, 821, 823, 851, 876
Yang Fire, 103, 137, 200, 242
Yang Heel Vessels, 70, 71, 107, 197, 198-200, 210-212, 215, 251, 259, 377, 381
Yang Linking Vessels, 70, 71, 108, 197, 200, 213-215, 251
Yang Ming, 57, 160, 222, 501, 503, 612
Yang Organs, 197, 198, 222, 242, 247, 253, 254, 257, 837, 870
Yang Polarity, 152, 268
Yang Shen Disturbances, 430
Yang Yao, 166, 276-278
Yao Cycles, 166, 276, 278
Yao Lines, 109, 612
Ye, Tian Shi, 502
Yellow, 49, 68, 99, 106, 122-124, 136, 139, 140, 147, 154, 193, 198, 241, 319, 355, 386, 429, 430, 431, 526, 529, 558, 560, 572, 598, 600, 607, 624, 645, 646, 657, 728, 768, 775, 779, 782-785, 787, 789, 790, 793, 797-799, 806, 819, 828, 829, 832, 851, 853, 854, 868, 905, 914-916
Yellow Emperor, 49, 68, 99, 106, 193, 198, 319, 355, 429, 529, 572, 787
Yi (Intent), 75, 80, 84-86, 92, 109, 139, 141, 176, 333-335, 337, 338, 340, 341, 347, 401, 402, 407, 411, 425, 427, 429, 573, 607, 616, 636, 787, 847, 873
Yi-Jing (Book of Changes: I-Ching), 268, 271
Yin Channels, 71, 160, 161, 165, 168, 170, 176, 178, 184, 187, 213, 214, 223, 251, 690, 868, 884
Yin Deficiency, 204, 242, 474, 480, 488, 490, 491, 495, 502, 505, 768, 775, 776, 778, 785, 788, 791, 792, 796, 797, 802, 808, 809, 812, 828, 853, 881, 913
Yin Essence, 200, 257, 278, 285, 321,859
Yin Heel Vessels, 71, 107, 108, 199, 210-212
Yin Linking Vessels, 70, 71, 108, 200, 213, 214
Yin Organs, 250, 253, 257
Yin Shen Disturbances, 430
Yin Tang (Third Eye Point), 120, 131, 143, 144, 332, 350, 451, 520, 521, 531, 632, 636, 672, 726, 733, 831, 832, 833, 840, 865, 866, 883
Yin Yao, 277-279
Ying Qi (Nutritive Qi), 57, 64, 137, 163, 166, 191, 193, 322, 324, 326, 329, 330, 491, 502-504, 676, 678, 679, 747, 888
Yu Jing (Hidden Essence), 86, 87, 347
Yu Vessels, 213, 215

15. Bring the pearl down to the right side of the neck at the level of the ***Throat Center***, and circle right to *C-7* at the back of the neck, to the left, and to the front of the throat center. Circle nine times, ending at the front. Cross the front, back, and two sides, also ending by bringing the pearl to the front.
16. Bring the pearl down to the right side rib cage at the ***Heart Center*** level. Circle the pearl toward the right, to the back,and so forth clockwise for nine times, ending at the front of the heart center. Then, use the pearl to cross the front, back, and two sides. Return the pearl to the front again.
17. Move the pearl to the ***Solar Plexus***. Circle it nine times to T-11 at the back, and return to the solar plexus. Cross the front, back, and sides. Return the pearl to the front.
18. Bring the pearl down to the ***Navel***. Circle it back to the Door of Life, and back to the navel nine times. From the navel bring the pearl to the cauldron, back toward the Door of Life, and return it to the cauldron. Use the pearl to cross the right and left sides. Return the pearl to the navel.

Descending From the Pakuas to the Earth.

19. Once you have controlled the pearl to this stage of the meditation, you are ready to move the pearl down to the ***Sexual Center***. Women bring the pearl down to the right side of the ovary center, located three inches below the navel. Men bring the pearl from the navel down to the right side of the sperm palace, one and a half inches below the navel. Circle clockwise back to the sacrum, to the left hip, and to the front of the ovary center/sperm palace nine times. Use the pearl to make a cross. Return the pearl to the front of the sexual center.
20. Bring the pearl down to the right groin. Circle the pearl clockwise around the ***Perineum Point and Lower Hips*** nine times. Use the pearl to form a cross by connecting the front, back, and sides. Return the pearl to the front.
21. Move the energy down and circle toward the back of ***Both Knees***, around and to the front, midway between both knees, moving the pearl clockwise nine times. Use the pearl to form a cross by moving the pearl to the midpoint between the knees and connecting the front, back, and sides from this point. End with the pearl midway between the fronts of both knees.

Yu Zhen Guan, 605
Yuan Jing, 133, 316-318, 324, 331, 333, 633
Yuan Qi, 70, 133, 135, 137-139, 191, 197, 199, 201, 204, 252, 253, 279, 316-324, 333, 368, 371, 383, 387, 391, 398, 466, 487, 560, 588, 590, 665, 667, 688, 720, 724, 726, 733, 737, 749, 811, 814, 845, 866, 897, 898, 902, 903, 906
Yuan Shen, 84-86, 90-92, 118, 138, 142, 187, 201, 259, 268, 316-318, 333, 335, 337, 338, 343, 344, 345-347, 371, 401-404, 408-410, 419, 427, 440-451, 514, 528, 633, 723, 726

Z

Zhang, Zhong Jing, 501
Zhao, Joanna, 50, 54
Zhao, Xianke, 127
Zhen Qi (True Qi), 81, 286, 322, 324, 903
Zheng Qi (Righteous Qi), 282, 323, 324
Zheng, Zhan Ding, 404, 518, 524
Zhi (Will), 75, 76, 79, 80, 85, 90, 102, 118, 139, 141, 151, 187, 201, 333-335, 338, 340, 341-347, 811, 847, 876
Zhi Shen (Postnatal Spirit), 85, 90, 201, 333, 335, 343-347, 401-404, 408-412, 427, 446
Zhi, Zhuan, 699
Zhong Qi (Center Qi), 321, 322, 324
Zhou Qi (Turbid Qi), 321, 324
Zhou, Qianchuan, 49, 99
Zong Qi (Gathering Qi), 80, 137, 138, 191, 322, 324

ABOUT THE AUTHOR

- Dean of Medical Qigong Science - Five Branches Institute, College and Clinic of Traditional Chinese Medicine (U.S.A.)
- Director of Medical Qigong Clinic - Five Branches Institute, College and Clinic of Traditional Chinese Medicine (U.S.A.)
- Director and Founder of the International Institute of Medical Qigong - (United States, Canada, South Africa, and Europe).
- Professor of Medical Qigong Science and Philosophy - Licensed by the Beijing Western District Qigong Science and Research Institute (China)
- Physician in Charge of Traditional Chinese Medicine - Licensed by the Beijing Bureau of Scientific Technology (China)
- Doctor of Medical Qigong and Anmo Therapy - Licensed by the Beijing Western District Qigong Science and Research Institute (China)
- Graduate Degree in Medical Qigong Therapy - Medical Qigong College - Hai Dian University of Beijing, (China)
- Council Board Member (United States Representative)- World Academic Society of Medical Qigong, (China)
- Council Board Member (Medical Qigong Committee)- National Qigong Association (U.S.A.)
- Ambassador of Chinese Medical Qigong Therapy to North America - Commissioned by The World Health Organization Collaborating Center for Traditional Chinese Medicine, Beijing, China (sponsored by the United Nations)


Dr. Jerry Alan Johnson

MEDICAL BACKGROUND

Dr. Jerry Alan Johnson is one of the few internationally recognized non-Chinese Grand Masters, practicing doctors and Director/Professors of Medical Qigong Therapy. Having studied for more than twenty-eight years, he is recognized both in China and the West as America's leading authority on Medical Qigong therapy. Dr. Johnson is licensed as a Doctor of Traditional Chinese Medicine (D.T.C.M.) in Beijing, China, and has served with national and international committees to promote and encourage the practice of Medical Qigong.

Dr. Johnson began his initial training in energetic medicine in 1972. He started his formal clinical studies of Traditional Chinese Medicine in Monterey, California in 1974, where he focused his studies on acupuncture, herbology, Medical Qigong therapy, traumatology and Chinese massage. After receiving certification as an Acupuncturist and Herbalist from an 1978-81 internship, Dr. Johnson operated clinics in Colorado Springs, Colorado (1981-84), working as a consultant and associate in Acupuncture and Medical Qigong Therapy to Western Medical Doctors and Chiropractors.

In 1993 Dr. Johnson furthered his clinical studies at the China Beijing International Acupuncture Training Center, and at the Acupuncture Institute of China, Academy of T.C.M. He was the first foreigner from the Acupuncture Institute invited to treat patients in the Medical Qigong Clinic at the Xi Yuan Hospital of T.C.M. (featured in Bill Moyer's special "Healing and the Mind"). There he interned as a Doctor of Medical Qigong Therapy, specializing in the treatment of cysts, tumors, and kidney dysfunctions.

Dr. Johnson also interned as a Doctor of Anmo Therapy at the Orthopedic Traumatology Clinic of the Hu Guo Si Hospital of T.C.M. (in Beijing, China) specializing in Chinese bone-setting, traumatology and tissue manipulation. His training includes Neuro-muscular Therapy, Psychophysical Integrational Therapy, Advanced Visceral Manipulation and Advanced Cranio-Sacral Therapy from the Milne Institute of Healing Arts.

In 1995 Dr. Johnson received his Graduate Degree in Medical Qigong Therapy from the Medical Qigong College - Hai Dian University of Beijing, China, and was licensed as a Doctor of Medicine Qigong. The Beijing Western District Qigong Science and Research Institute awarded Dr. Johnson a license as "Professor of Medical Qigong Science and Philosophy" after his completion of both academic doctoral thesis, and numerous clinical field studies (1995).

In 1997 Dr. Johnson became the first Qigong doctor allowed to assist in surgery at the Community Hospital of the Monterey Peninsula, in Carmel, California, where he continues to work closely with Western Doctors.

In 1997 Dr. Johnson was elected to the Board of Directors of the National Qigong Association-USA. In 1998 he was appointed the Chairman of the Medical Qigong Committee, responsible for establishing the guidelines and national standards for Medical Qigong practitioners working in clinical settings.

In 1998 Dr. Johnson was elected to the Board of Directors of the World Academic Society of Medical Qigong, centered in Beijing, China, and serves as one of four Council Board Members that represent the United States at the World Conferences. Also, in 1998, his clinical status was elevated to the position of "Physician in Charge of Traditional Chinese Medicine" from the Beijing Bureau of Scientific Technology, in China.

In the Spring of 1999 Dr. Johnson accepted the position of Dean of Medical Qigong Science from the Five Branches Institute, College and Clinic of Traditional Chinese Medicine, in Santa Cruz, California. Dr. Johnson developed a Masters Program which includes instruction and training from his textbook entitled: *Chinese Medical Qigong Therapy, A Comprehensive Clinical Text*. The course also includes the specialization of specific Medical Qigong Therapies such as Pediatrics, Geriatrics, Gynecology, Neurology, Psychology, Oncology and Surgery.

In the Spring of 2000 Dr. Johnson established within the Five Branches Institute the first Medical Qigong Clinic at a T.C.M. College in North America, facilitating the combined use of acupuncture, herbs and Medical Qigong therapies to the general public.

Dr. Johnson is also the founder and director of the International Institute of Medical Qigong, in Monterey, California, and has designed a three-year Medical Qigong program which has been implemented by several colleges and Medical Qigong Institutes throughout the United States, Canada, Europe and South Africa.

Dr. Johnson serves as the official representative for North America for The World Health Organization Collaborating Center for Traditional Medicine, sponsored by the United Nations for the promotion and development of Traditional Chinese Medical Qigong Therapy.

An active member of the World Academic Society of Medical Qigong, Dr. Johnson was a key speaker at the 1996 Third World Conference on Medical Qigong, held in Beijing, China, the 1997 Second World Congress on Medical Qigong held in San Francisco, California, the First American Qigong Association Conference, held in San Francisco, California, the 1998 Fourth World Conference on Medical Qigong, held in Beijing, China, and the 1999 National Qigong Gathering held in Baltimore, Maryland. He has lectured and taught many seminars at The American College of Traditional Chinese Medicine in San Francisco, California, The University of California San Francisco, The Qigong Institute of Menlo Park, California, The International Training Center at San Diego State University, The Monterey Institute of International Studies, The Asilomar Conference Center of Pacific Grove, California, as well as several other colleges, institutes and hospitals throughout North America.

MARTIAL ARTS BACKGROUND

Dr. Johnson is also internationally renowned as a Shifu (Master Instructor) of several Chinese Martial Arts Systems, having studied the martial arts for over 34 years.

In Shaolin, he has studied Praying Mantis, Hung Gar, Wing Chung, and Mi Zongquan Shaolin styles of fighting, weapons and Martial Qigong, and is a certified Master Instructor in Mi Zongquan Shaolin, teaching through the authority of the Mi Tsung-I Northern Shaolin Federation of Taiwan.

In Baguazhang he has studied several schools of fighting, including the Yin Fu, Cheng Ting-Hua, Liu De Kuan, Fu Zhen-Song, and the Chang Zhao-Dong Styles of combat, weapons and Martial Qigong. He is a certified Master Instructor in Chang Zhao-Dung Baguazhang, teaching through the authority of the Ching Yi Baguazhang Association, the Hsiao Mien Hu Martial Arts Association, and The Canadian Martial Arts Society.

In Taijiquan, Dr. Johnson has studied several schools of fighting, including the Yang Pan-Hou, Yang Chien-Hou, and Chen Fa Ke styles of combat, weapons and Martial Qigong. He is a certified Master Instructor as well as a "Twentieth Generation Inner-Door Disciple" from Feng Zhi Qiang's Chen Style Taijiquan, teaching through the authority of the Beijing Martial Arts Association and the Beijing Chen Style Taijiquan Association of China. He is also a certified Master Instructor in the Yang Style Taijiquan, teaching through the authority of the Tai Chi Chuan Federation of Taiwan.

Excelling in "Empty Hand," as well as "Weapons Fighting" from both the Shaolin and Wudang Martial Arts Systems, Dr. Johnson competed regularly in the tournament circuit and was titled: 1980 Southbay National Champion, 1982 Tournament of Fighters Champion, 1982 Universal Tae Kwon Do/Tang Soo Do Invitational Grand Champion, 1983 Colorado National Kung Fu Champion, 1983 Tournament of Fighters Grand Champion, 1984 Colorado National Kung Fu Champion, and the Tournament of Fighters Kung Fu Champion in 1984, when he retired from competition.

In addition to his own championships, many of Dr. Johnson's students also went on to compete at the national level, bringing several championship titles to the school. Like their teacher, Dr. Johnson's students excelled in free-form fighting, Taiji Push-hands and Chinese Gongfu forms, as well as weapon competitions.

In 1986, the state of California issued Dr. Johnson teaching credentials, allowing him to teach adult education classes in Taijiquan and Baguazhang. Since then, he has been a council member of the International Baguazhang Research and Teachers Exchange, and served as a judging official and member of the Executive Committee of the U.S. Chinese Kuo Shu Federation, as well as a coaching official, national certifier and council member of the Amateur Athletic Union (affiliated with the U.S. Olympics). Dr. Johnson also participated on the Board of Advisors for the United States of America Wushu-Kung Fu Federation, and is a member of the International Congress of Oriental Medicine and Martial Arts. He was also a standing member of the North American Chinese Martial Arts Federation.

Author and Publisher:

Dr. Johnson was a contributing author, selected to write the Medical Chi Kung section, for the book *The Complete Illustrated Guide to Chi Kung*, a cooperative project between Element Books (UK) and author James MacRitchie. Dr. Johnson was also one of the selected contributing authors for the book *Qigong-Essence of the Healing Dance*, a cooperative project between P.B.S. and Documentary Producer/Director Garri Garripoli.

Dr. Johnson has been interviewed many times on local radio programs, and has been featured in numerous local and international newspapers and magazines, including: *Newsweek Magazine* "The International Addition," *The World Medical Qigong Quarterly, Qi-The Journal of Traditional Eastern Health & Fitness, The Empty Vessel Magazine, Pent-*

house Magazine, Self Magazine, Billboard Magazine, The Mystical World of Chinese Martial Arts, Inside Kung Fu Magazine, Combat Karate Magazine, Internal Arts Magazine, Black Belt Magazine, The Pa Kua Chang Journal, and Inside Karate's Master Series Magazine.

Televised specials include: *NBC News* "Dateline," *CBS/Channel 46* "Eye on America," featured in a documentary on Medical Qigong filmed for the *"Discovery Channel,"* featured in a documentary on Medical Qigong filmed for SBS "Qi-into the world of the unknown," and *K.P.B.S.* "Managing Health and Productivity; New Approaches In Technology," as well as *The David Letterman Show.*

In 1988, Dr. Johnson created and published a six level "Pa Kua Chang Chi Kung Correspondence Course," and in 1989, founded the "Pa Kua Chang News Letter," which later became known as the "Pa Kua Chang Journal," and was distributed worldwide. Dr. Johnson has written and published five books on martial arts entitled:

- The Secrets of the Eight Animals,
- The Masters Manual of Pa Kua Chang,
- Classical Pa Kua Chang Fighting Systems and Weapons,
- The Essence of Internal Martial Arts Volume 1: Esoteric Fighting Techniques and Healing Methods, and
- The Essence of Internal Martial Arts Volume 2: Energy Theory and Cultivation.

From 1984 to 1986, Dr. Johnson produced and directed six Baguazhang instructional videos entitled:

- The Eight Animal School of Pa Kua Chang
- The Original Form of Pa Kua Chang
- The Eight Circular Pa Kua Staff
- The Eight Circular Pa Kua Broadsword
- The Dragon School of Pa Kua Chang, and
- The Fighting Techniques of Pa Kua Chang.

In 1994 he was featured in two videos on Taijiquan, as well as one Qigong video narrated by actor John Saxon, entitled:

- Tai Chi-The Empowering Workout,
- Power Tai Chi- Total Body Workout, and
- Chi Kung-The Healing Workout,

He additionally created two Meditation CD / cassette tapes with composer John Serri entitled:

- Tai Chi Meditation - [1] Life Force Breathing, and
- Tai Chi Meditation - [2] Eight Direction Perception.

Dr. Johnson's latest project includes 10 Medical Qigong videos which contain instructional information and training from his current textbook *Chinese Medical Qigong Therapy, A Comprehensive Clinical Text,* entitled:

- Gathering Energy from Heaven and Earth,
- Stationary and Dynamic Medical Qigong Posture Training,
- Treating Patients with Medical Qigong Therapy (Vol.1),
- Treating Patients with Medical Qigong Therapy (Vol.2),
- Medical Qigong Energy Techniques and Qi Emitting Methods,
- Medical Qigong Invisible Needle Technique, Five Element Qigong Massage, and Energetic Point Therapy,
- Medical Qigong Healing Sound Therapy and Prescriptions,
- Treatment of Internal Organ Diseases with Medical Qigong,
- Treatment of Cysts, Tumors, and Cancer with Medical Qigong Therapy, and
- Soul Retrieval.

Dr Johnson's books, video tapes, meditation C.D.'s and cassette tapes have been translated into other languages and are currently being sold around the world. They have been featured in *Publishers Clearing House, Columbia House, Borders Book and Music Co., The Book of the Month Club, T'ai Chi Magazine, Century Martial Arts, Qi-The Journal of Traditional Eastern Health & Fitness, The Complete Guide to Exercise Videos, the Double Day Book and Music Co, and Direct TV (both in the United States and Japan).*

For more information about the author, the reader can turn to his web page at:

www.qigongmedicine.com

ADDITIONAL BRANCHES OF THE INTERNATIONAL INSTITUTE OF MEDICAL QIGONG

The following is a list of graduating students and instructors, as well as national and international directors of the International Institute of Medical Qigong.

BRANCHES WITHIN THE UNITED STATES

Jerry Alan Johnson, Ph.D.,D.T.C.M.,
D.M.Q. (China)
Director and founder of the International
Institute of Medical Qigong
(Main Branch)
P.O.Box 52144
Pacific Grove, California 93950 USA
Phone: (831) 646-9399
Fax: (831) 646-0535
E-Mail: drjerryalanjohnson@eatrhlink.net
Web Page: www.qigongmedicine.com

Seth Lefkowitz, D.C., D.M.Q. (China)
Director of the International Institute of
Medical Qigong
(South San Francisco Branch)
351 South Baywood Avenue,
San Jose, California 95128 USA
Phone (408) 243-1565
Fax: (408) 243-1568
E-Mail: naturespath4me@yahoo.com

Arnold Tayam, D.M.Q. (China)
Director of the International Institute of
Medical Qigong
(San Jose/Silicon Valley Branch)
c/o The Longevity Center
P.O. Box 26712
San Jose, California 95159-6712 USA
Phone (408) 295-5911
Fax: (408) 971-0136
E-Mail: chi@longevity-center.com
Web Page: www.longevity-center.com

Jean Ruth Vlamynck, L.Ac., Dipl.Ac.,
M.T.C.M., M.Q.T.
Director of the International Institute of
Medical Qigong
(Santa Cruz Branch)
257 B Center Ave.
Aptos, California 95003 USA
Phone: (831) 689-9093
Fax: (831) 689-9094
E-Mail: jeanhere@bigplanet.com
Web Page: www.relaxationresources.com/
assoc/jeanv.html

Dale M. Hopkins, M.Q.P.
Director of the International Institute of
Medical Qigong
(Northern Santa Cruz Branch)
24345 Loma Prieta Ave.
Los Gatos, California 95033
Phone: (408) 353-2566

Wendy Lang, M.Q.P.
Director of the International Institute of
Medical Qigong
(Marin County Branch)
12 Skylark Dr. Apt 33
Larkspur, California 94939
Phone: (415) 924-7883
E-Mail: wendylang@altavista.com

Andy Balestracci, M.Q.P., and
Linda MacElwee, M.Q.P.
Director of the International Institute of
Medical Qigong
(Mendicino Branch)
P.O. Box 43
Philo, California 95466
Phone: (707) 895-9115

Geoffery Greenspahn, M.Q.T.
Director of the International Institute of
Medical Qigong
(Los Angeles Branch)
Los Angeles, California
Phone: 310-775-5022
E-Mail: rumblej@hotmail.com

Todd Gedryn, M.Q.T.
Director of the International Institute of
Medical Qigong
(San Francisco Branch)
c/o Qigong Institute of North America
9 White Tail Lane
Monterey, Ca 93940 USA
Phone (408) 221-0628
Fax: (831) 373-8149
E-Mail: todd@qigonginstitute.net
Web Page: www.qigonginstitute.net

Matthew B. Weston, M.Q.T.
Director of the International Institute of
Medical Qigong
(Big Sur Branch)
c/o South Coast Qigong Center
P.O. Box 223373
Carmel, California 93922 USA
Phone (831) 626-3347
E-Mail: qigongr@mbay.net

Ted Cibik, M.Q.P.
Director of the International Institute of
Medical Qigong
(Pennsylvania Branch)
c/o Inner Strength Inc.
R.D. #4 Box 64
Leechburg, Pa 15656 USA
Phone (724) 274-0586
Fax: (724) 845-7739
E-Mail: ted@inner-strength.com
Web Page: www.inner-strength.com

Judith "Lacy" Storey, L.Ac.
Director of the International Institute of
Medical Qigong
(Colorado Branch)
Breckenridge, Colorado USA
Phone (303) 274-0586
E-Mail: dakini@colorado.net

Ellie Christianson, L.L.C., M.Q.P.
Director of the International Institute of
Medical Qigong
(Arizona Branch)
481 West Greys Road
Tuson Arizona 85718
E-Mail: ellie@MIOBI.com

Donald Mead, M.Q.P.
Director of the International Institute of
Medical Qigong
(Georgia Branch)
1008 Courtenay Drive NE
Atlanta, Georgia 30306-3330
Phone: (404) 873-6557
E-Mail: dmm10@mindspring.com

Connie Comer, M.Q.P.
Director of the International Institute of
Medical Qigong
(Oregon Branch)
1427 N.W. 23rd Ave.
Portland, Oregon 97210
Phone: (503) 226-6822
E-Mail: conniecomer@hotmail.com

INTERNATIONAL BRANCHES

Cynthia McMullen, C.M.T., M.Q.P.
Director of the International Institute of
Medical Qigong
(Alaska Branch)
3713 E. 19th Ave.
Anchorage, Alaska 99508
Phone: (907) 279-0135
E-Mail: touchoftaoCM@netscape.net

Robert C. Bawol, M.Q.P.
Director of the International Institute of
Medical Qigong
(New Mexico Branch)
1145 N. Alameda
Las Cruces, New Mexico 88005
Phone: (505) 647-8827
E-Mail: arrow@HTG.net

Shirley Norway
Director of the International Institute of
Medical Qigong
(Illinois Branch)
P. O. Box 1349
Fairfield, Illinois 52556
Phone: (515) 472-8404

Andy James, M.Q.T.
Director of the International Institute of
Medical Qigong
(Canadian Branch)
c/o Canadian Practitioners' Association
of Asian Medicine
Toronto, Canada M4K IK4
Phone: (416) 463-9360
Fax: (416) 463-0045
E-Mail: emerge@powerofbalance.com

Richard Garnier
Director of the International Institute of
Medical Qigong
(Europe Branch)
c/o Chariot D'or
Villa Samicky 171 che du Suveran
06140 Vence, France
Phone/Fax: 33 493 58 51 20
E-Mail: chardor@club-internet.fr

Susan Vial, M.Q.P.
Director of the International Institute of
Medical Qigong
(South Africa Branch)
P.O. Box 235
Magaliesburg, 2805 Gauteng
South Africa
E-Mail: saspect@iafrica.com

22. Direct the energy down to the feet, just below the ankles. Circle the ***Soles of the Feet*** nine times moving the pearl clockwise to the heel of the right foot, to the heel of the left foot, to the outer side of the left foot, to the front, midway between both feet. Form a cross. End with the pearl midway between both feet.
23. Move the energy from the front of the feet down to a point ***Beneath the Earth***, and circle toward the right (clockwise) nine times. Use the pearl to form a cross ***Beneath the Earth***. Keep on spiraling more energy to enhance the pearl. Return the pearl to the front of the circle.



Fig. 8.7 *Bring the Pearl down to the ground, spiral clockwise.*



Fig. 8.8 *Spiral reverse counterclockwise moving up.*

This is Google's cache of http://lucianarchy.proboards.com/index.cgi?board=zorgon&action=print&thread=8872. It is a snapshot of the page as it appeared on 18 Apr 2011 10:28:22 GMT. The current page could have changed in the meantime. Learn more

These search terms are highlighted: **vlf haarp** These terms only appear in links pointing to this page: **thompson manitoba**

'Special Guest' Boards » The Zorgon Zone, with Special Guest Ron Schmidt » **Every One Speaks about HAARP, but did you know...**
http://lucianarchy.proboards.com/index.cgi?board=zorgon&action=display&thread=8872

Every One Speaks about HAARP, but did you know...
Post by zorgon on Sept 21, 2010, 6:46pm

Every One Speaks about **HAARP**...

It gets blames for everything, it has magical abilities etc...

While it is true that it does indeed have some interesting abilities, there are many threads and documents on **HAARP**. I have been collecting material for years BUT, though its been hinted at from time to time that other countries also have a version of **HAARP** and that incoherent scatter sites have a similar function as **HAARP** and EISCAT has been mentioned...

Very few people have taken the time to follow the leads in the various documents and threads and put together the GLOBAL NETWORK

While **HAARP** itself may not have the power to create a planetary shield (for missile defense and solar radiation) the world wide network certainly does.

So for this thread I will leave the much discussed Alaskan **HAARP** in the side lines for now and lets do a tour of the other facilities around the world.

First a little bit on connections to other facilities. In reports like the NAVY Press Release of Dr Paul A. Bernhard... we see some terms already...

Dr. Bernhardt used the high-power HF facility near Arecibo, Puerto Rico, and Nizhny Novgorod, Russia, from 1985 to 1999...

Dr. Bernhardt has conducted over eight experiments from 1985 to the present, using the Space Shuttle Orbital Maneuver Subsystem (OMS) engines, to modify the ionosphere with high-speed exhaust injections into the upper atmosphere. The results of these dedicated engine burns have been recorded using the VHF and UHF radars at Arecibo, Puerto Rico; Kwajalein, Marshall Islands; Millstone Hill, Massachusetts; and Jicamarca, Peru. Currently, Dr. Bernhardt is the principal investigator for the Charged Aerosol Release Experiment (CARE) program, designed to study the scattering of radar from electrons in the vicinity of charged particulates that form artificial "dusty plasmas."

...Coherent Electromagnetic Radio Tomography (CERTO)
...Computerized Ionospheric Tomography Receiver in Space (CITRIS)

http://www.nrl.navy.mil/pao/pressRelease.php?Y=2006&R=17-06r

So from this single press release we have three search terms. Just ignore the facts about the chemical releases and the shuttle spewing fumes, we already have a thread on that 😛)

...Incoherent Scatter Radar (ISR) (Like EISCAT for European Incoherent Scatter Radar)
...Coherent Electromagnetic Radio Tomography (CERTO)
...Computerized Ionospheric Tomography Receiver in Space (CITRIS)

and these locations mentioned directly

Arecibo, Puerto Rico
Nizhny Novgorod, Russia
Kwajalein, Marshall Islands
Millstone Hill, Massachusetts
Jicamarca, Peru

From our research collected at Pegasus we can add these...

HIPAS - High Power Auroral Stimulation Observatory
IRIS - Imaging Riometer for Ionospheric Studies

The problem is I have gathered so much material on these sites and still have more to do... that it may get lost in a single thread...

So lets start with the best **HAARP** like arrays and Incoherent Scatter facilities.

Now this will take me a while to pull up all my pages so I won't be answering any posts for a while 😉

continued...

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 6:50pm

Sura Facility

HAARP Like Facility
Nizhniy Novgorod, Russia
+56° 7' 9.70", +46° 2' 3.66"



courtesy http://sura.nirfi.sci-nnov.ru/Photogalery/Photogalery.html

SURA Official Site Russian

The Sura Ionospheric Heating Facility, located near the small town of Vasilsursk about 100 km eastward from Nizhniy Novgorod in Russia, is a laboratory for ionosphere research. Sura is capable of radiating about 190 MW, effective radiated power (ERP) on short waves. This facility is operated by the radiophysical research institute NIRFI in Nizhny Novgorod. The Sura facility was commissioned in 1981. Using this facility, Russian researchers achieved extremely interesting results regarding the ionosphere behavior and discovered the effect of generation of low-frequency emission at the modulation of ionosphere current[1]. At the beginning, Soviet Defense Department mostly footed the bill. The American **HAARP** ionospheric heater is similar to the Sura facility. The **HAARP** project began in 1993.

Technical information

The frequency range of the heating facility is from 4.5 to 9.3 MHz. The facility consists of three 250 kW broadcasting transmitters and a 144 crossed dipole antenna-array with dimensions of 300 m x 300 m. At the middle of the operating frequency range (4.5 � 9.3 MHz) a maximum zenith gain of about 260 (~24 dB) is reached, the ERP of the facility is 190 MW (~83 dbW).

http://en.wikipedia.org/wiki/Sura_Ionospheric_Heating_Facility



http://www.thelivingmoon.com/45jack_files/03files/SURA_Radar_Facility.html

Artificial Ionospheric Turbulence and Radio Wave Propagation (Sura/**HAARP**)

PDF File

Russian US cooperation

In March and May 2006 two
sessions of measurements in the framework of the SURA–**HAARP** experiment were carried out.

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 6:52pm

São Luiz Space Observatory

HAARP Like Facility
Cruzeiro Santa Bárbara, Sao Luis-MA, Brasil
-2° 35' 40.47", -44° 12' 35.90"

Coherent Back-Scatter Radar 50 MHz (RESCO)

The Coherent Back-Scatter Radar of 50 MHz (RESCO) was installed at the Space Observatory of São Luís / INPE, whose operation begun in August of 1998, is capable to accomplish measures of dynamics of the plasma of the electrojet and of bubbles equatorial ionospheric. This radar was projected to map the turbulence and the electromagnetic drift of the irregularities of short length scale (3 meters) in a height range that extends from ~90 km to ~1000 km of the equatorial ionosphere. Such plasma irregularities have big influence in the propagation trans-ionosphere of waves in a great frequency range, VHF to UHF, and, therefore, it influence all of the activities of space communications of the Brazilian tropical area. The formation, the development and the space distribution of these irregularities are highly sensitive to the space climatic change (in other words, "Space Weather") besides the convection processes and of the storms of the troposphere.

This radar resulted of the development and construction begun in INPE there are several years. It transmits signs pulse of high potency through an network antenna with 768 dipoles which allow to concentrate all the energy transmitted in only narrow beam radiation. The same antenna also captures the echo signs spread by the irregularities ionosphere. The transmitted maximum power (120 kW) it is reached through the use of a modular system of 8 transmitters in phase to maximize the transmitted energy. The operational control of the radar is made by a computer, which also accomplishes the acquisition, the treatment and processing 'on line' of the received data of the ionosphere. The data recorded are available also for the processing and analyze subsequent. This radar was already operated in several campaigns since 1998 and now it is collecting in a routine way data of the dynamics of the equatorial electrojet.

This radar, with the FCI radar of 30 MHz together offers great opportunities to the researchers of studying the peculiar phenomenon of the equatorial area. These, beside the radars of Peru (Jicamarca), of the India (Thumba) and of the Indonesia, are some of the few radars of this type that exist in the world around of the magnetic equator. Due to the peculiar configuration of the geomagnetic field, the Brazilian equatorial area have characteristics very different from the other areas. It was for this reason that NASA of the USA, in collaboration of INPE, accomplished in Alcântara in 1994 the campaign GUARÁ when 26 rockets were thrown (in the period of September-October) to study the equatorial electrojet and the bubbles ionosphere. In this campaign were used another radar similar to the radar RESCO (which was brought of the USA), Digissonde (which provided the diagnoses of the ionosphere) and of the magnetometers operated by INPE in the Space Observatory of São Luís. The radar RESCO, that is now in a phase of technological improvement, offers great potential to promote researches of the environment of the Brazilian equatorial area.

Rua Horto Florestal, 100, Cruzeiro Santa Bárbara, Sao Luis-MA - Brasil

SOURCE: São Luiz Space Observatory
http://www.dae.inpe.br/slz/english/resco.html

http://www.thelivingmoon.com/45jack_file....bservatory.html

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 6:54pm

Millstone Hill Radio Observatory

EISCAT Like Facility
Westford, Massachusetts
+42° 37' 09.25", -71° 29' 28.49"



Millstone Hill

Millstone Hill, Westford, Massachusetts, USA (Longitude: W Latitude: N)

The Millstone Hill Steerable Antenna, or MISA, is a fully steerable dish antenna, 46 meters in diameter, designed by the Stanford Research Institute (SRI) in 1959. It is currently located at MIT Haystack Observatory in Westford, Massachusetts. It was originally installed at the Sagamore Hill Radio Observatory in Hamilton, Massachusetts in 1963. The antenna operated at that location until 1978, at which time it was relocated to Millstone Hill. Since that time it has been primarily used as a UHF radar antenna to provide measurements of the near space environment using the incoherent scatter radar technique. It is one of two surviving dish antennas of this type in the world with the other antenna being located at the Stanford University radio science field site in Stanford, California. MISA is used to provide wide radar coverage in latitude and longitude.

MISA is a broad-based observatory capable of addressing a wide range of atmospheric science investigations. The incoherent scatter radar facility at Millstone Hill has been supported by the National Science Foundation since 1974 for studies of the earth's upper atmosphere and ionosphere. During this time the facility has evolved from a part-time research operation sharing radar cooling and power supply elements with the M.I.T. Lincoln Laboratory Millstone satellite tracking radar, to a separately funded, operationally independent system dedicated to upper atmospheric research. The scientific capability of the Millstone Hill facility was greatly expanded in 1978 with the installation of a fully-steerable 46 meter antenna to complement the 67 meter fixed zenith pointing dish.

The favorable location of Millstone Hill at sub-auroral latitudes combined with the great operational range afforded by the steerable antenna permit observations over a latitude span encompassing the region between the polar cap and the near-equatorial ionosphere. Since 1982 the Haystack Observatory Atmospheric Sciences Group has been supported for operating the Millstone Hill research radar as a part of the incoherent scatter radar chain and for associated studies of the auroral and sub-auroral ionosphere and thermosphere. The meridional radar chain extends from Sondre Stromfjord, Greenland through Millstone Hill at mid-latitudes, beyond Arecibo at low latitudes, to the Jicamarca facility at the magnetic equator in Peru. The radar chain forms an integral part of the NSF-supported CEDAR (Coupling, Energetics, and Dynamics of Atmospheric Regions) observing network and Millstone Hill observations and analysis have contributed extensively to the successes of the CEDAR initiative.

The Millstone Hill Radar uses Thomson backscatter from ionospheric electrons to deduce height- and time-resolved plasma drift velocities, electron and ion temperatures, electron densities, ion composition, and ion-neutral collision frequencies. These parameters provide further information about the neutral gas, neutral temperatures and winds, and electric fields present in the medium. The incoherent scatter technique provides observations of many of these parameters over an altitude range extending from less than 100 km to a thousand kilometers or more. Methods have been developed that allow these measurements to be made with an altitude resolution of hundreds of meters. The complete steerability of the radar allows horizontal gradients and structure to be examined along with vertical variations.

The Observatory is the premier scientific facility in the world for studying the equatorial ionosphere. It has a 2-MW transmitter and a main antenna with 18,432 dipoles covering an area of nearly 85,000 square meters.

SOURCE: Wikipedia Millstone Hill
http://en.wikipedia.org/wiki/Millstone_Hill

Related Links:
MIT Haystack Observatory
http://www.haystack.mit.edu/

Credit: Haystack Observatory

http://www.thelivingmoon.com/45jack_file....bservatory.html

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 6:56pm

The first American '**HAARP**'

Platteville Atmospheric Observatory

HAARP Like Facility
+40° 10' 54", -104° 43' 30"

History
of the
Platteville Atmospheric Observatory

Image courtesy Colorado University

The Platteville Atmospheric Observatory was envisioned in 1962 by what is now the Institute of Telecommunication Sciences (ITS), a part of the National Telecommunications and Information Administration (NTIA), as a site for high-powered radio experiments. While the initial experiment, that took place in 1968, studied over-the-horizon radar, the majority of later experiments used high power radio waves to modify the ionosphere in a process that is sometimes called ionospheric heating because it raises the electron temperature in the ionosphere.

The ionospheric heater was still used until 1984, when the last ionospheric experiments were performed. In the same year, the transmitters were loaned to the Office of Naval Research and sent to HIPAS in Alaska where they are still used.

With the removal of the transmitters, the focus of the facility changed to smaller-powered observation of the atmosphere rather than modifying it. In 1988 the 404 MHz RASS was installed and the ownership of the facility was transferred from NTIA to NOAA-ERL.

SOURCE: Platteville Atmospheric Observatory
http://grison.colorado.edu/Radar_Stations/Platteville/Platteville.html


CR-28
Platteville Atmospheric Observatory
40°10'54"N 104°43'30"W

http://www.thelivingmoon.com/45jack_file....bservatory.html

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 6:58pm

High Power Auroral Stimulation Observatory

HIPAS
Fairbanks Alaska
64° 52' 19" N 146° 50' 33" W


Source of ULF/ELF/VLF Emission Stimulated by HF Heating
Control of Reflector Coefficient
ULF/ELF/VLF waves
Radiator Belts
Precipitating Particles

HIPAS is located 30 miles Northeast of Fairbanks Alaska; in the small community of Two Rivers. It occupies 120 acres of land and has six buildings. The facility is located at: latitude and longitude. The facility operates year-round.

The HIPAS facility is engaged in the study of the Ionosphere through the use of high power radio transmission as well as a state-of-the-art LIDAR (LIght Detection And Ranging) facility.

The Heater system consists of 8 transmitters capable of conducting amplitude modulation of 100 Hz - 20 kHz and phase modulation of 0 -20 kHz. Each transmitter can transmit up to 150kW at 2.85 or 4.53 MHz on CW mode.

The Heater antenna system consists of a circular array of 8 crossed dipoles, copper wire ground-planes and resonant triaxial baluns.

The LIDAR facility consists of a 2.7 meter LMT (Liquid Mirror Telescope) with a 4.5 meter focal length as well as 6 state-of-the-art lasers.

SOURCE: HIPAS Home Page
http://www.hipas.alaska.edu/hipasweb/hipas.htm
Link invalid... Internet Archive Page
http://web.archive.org/web/20080212193205/http://www.hipas.alaska.edu/hipasweb/hipas.htm


HIPAS Observatory
Satellite
B Field
400 KM
200 KM
Lidar
Rocket
Bistatic Radar
VHF Radar
Phased Array Radar

Courtesy HIPAS

http://www.thelivingmoon.com/45jack_file....bservatory.html

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 6:59pm

European Incoherent Scatter Scientific Association

EISCAT
Ramfjordmoen, Near Tromsø, Norway
+69° 35' 10.94", +19° 13' 20.89"



The EISCAT Scientific Association is an international research organisation operating three incoherent scatter radar systems, at 931 MHz, 224 MHz and 500 MHz, in Northern Scandinavia. It is funded and operated by the research councils of Norway, Sweden, Finland, Japan, France, the United Kingdom and Germany (collectively, the EISCAT Associates).

EISCAT (European Incoherent Scattter) studies the interaction between the Sun and the Earth as revealed by disturbances in the magnetosphere and the ionised parts of the atmosphere (these interactions also give rise to the spectacular aurora, or Northern Lights). The radars are operated in both Common and Special Programme modes, depending on the particular research objective, and Special Programme time is accounted and distributed between the Associates according to rules which are published from time to time.

One EISCAT transmitter site is located close to the city of Tromsø, in Norway, and additional receiver stations are located in Sodankylä, Finland, and Kiruna, Sweden. See an animation that shows the basic operation. The EISCAT Headquarters are also located in Kiruna. 1996 the EISCAT Scientific Association constructed a second incoherent scatter radar facility, the EISCAT Svalbard Radar, near Longyearbyen on the island of Spitsbergen, far to the North of the Norwegian mainland.

The Incoherent Scatter Radar technique requires sophisticated technology and EISCAT engineers are constantly involved in upgrading the systems.

In addition to the incoherent scatter radars, EISCAT also operates an Ionospheric Heater facility at Ramfjordmoen (including a Dynasonde) to support various active plasma physics experiments in the high latitude ionosphere.

SOURCE ARTICLE
http://www.eiscat.se:8080/about.html

Tromsø 931 MHz Ultra High Frequency Radar [facts]
These signals are also received at Kiruna and Sodankylä

Tromsø 224 MHz Very High Frequency Radar [facts]
We have also a heating facility and a Dynasonde



http://www.thelivingmoon.com/45jack_file....mso_Norway.html

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 7:01pm

Nerc MST Radar Facility

NMRF
HAARP Like Facility
+52° 25' 28.26", -4° 00' 19.59"
Capel Dewi, Carmarthenshire, Wales, United Kingdom
near Aberystwyth, Wales, UK



This one is different but included anyway

The Natural Environment Research Council (NERC) Mesosphere-Stratosphere-Troposphere (MST)
Radar at Aberystwyth

SOURCE: NERC
http://mst.nerc.ac.uk/index.html



http://www.thelivingmoon.com/45jack_files/03files/NERC_MST_Radar_Facility.html

---

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 7:03pm

National MST Radar Facility

NMRF
HAARP Like Facility
+13° 27' 26.68", +79° 10' 30.74"
Gadanki, near Tirupati, in southern Andra Pradesh, India

I found this one on Google Earth so Pegasus has first find on that one

Ascending From the Earth Back to the Pakuas

24. Reverse the circle beneath the earth, moving the pearl counterclockwise again nine times. Use the pearl to form a cross, connecting the front, back, and sides.
25. Move the pearl to the outer side of the left foot. Circle the ***Soles of Both Feet*** nine times moving toward the left heel, to the right heel, to the right foot, and to the front (midway) of both feet. Use the pearl to form a cross. End with the pearl at the midway point in the front of both feet.
26. Move up to the left knee. Circle the pearl counterclockwise *at the* ***Knees*** nine times. Use the pearl to form a cross. Return the pearl to the midway point in the front of both knees.
27. From the front of the knees, move up to the left groin area. Circle counterclockwise at the ***Perineum*** nine times. Use the pearl to form a cross. Return the pearl to the front of the perineum.
28. Direct the energy to the left hip, and circle counterclockwise at the ***Ovary/Sperm Palace*** nine times. Use the pearl to form a cross by connecting the front, back, and sides. End with the pearl at the front of the ovary/sperm palace.
29. Return the pearl to the ***navel*** and to the ***Cauldron***.



Fig. 8.9 *Bring the Pearl up to the navel.*



Visiting the National MST Radar Facility in Gadanki, near Tirupati, in southern Andra Pradesh, India

ABOUT NATIONAL MST RADAR FACILITY

Indian scientists have carried out pioneering research work in the fields of astronomy and astrophysics, solar/interplanetary medium, earth's upper atmosphere/ionosphere, aeronomy/middle atmosphere and weather/climate phenomena. The nationally coordinated Indian Middle Atmosphere Programme (IMAP) was implemented during the period 1982-89 with well focussed campaign experiments with ground based, balloon, rocket and satellite based techniques. The IMAP programme led to the decision to conduct in-depth studies of atmosphericdynamical phenomena by developing a versatile ground based radar technique...

...The MST Radar is a state of the art instrument capable of providing estimates of atmospheric parameters with very high resolution on a continuous basis which are essential in the study of different dynamical processes in the atmosphere. It is an important research tool in the investigation of prevailing winds, waves (including gravity waves) turbulence, and atmospheric stability & other mesoscale phenomena . A reliable three dimensional model of the atmosphere over the low latitudes improves our understanding of the climatic and weather variations...

Establishment of NMRF

Attaching great importance to the scientific utilisation of the Indian MST Radar, the Government of India decided to create an autonomous Scientific Society called the National MST Radar Facility (NMRF). This society is affliated to the Department Of Space. The NMRF was registered on January 11, 1993 under the Indian Societies Act 1860.
This society is administered by a Governing Council under the chairmanship of Dr. K. Kasturirangan, Secretary DOS with, Director , NMRF as the member secretary . The present Director of NMRF is Prof D. Narayan Rao .The Governing Council consists of other eminent scientists, representatives of the National Laboratories and some of the funding agencies.The Governing Council sets broad policy guidelines to ensure the effective scientific utilisation of the facility, supported by a Scientific Advisory Commitee & a Finance Commitee.

Location Of NMRF

The scientific requirements dictated that the Indian MST Radar should be located preferably below 15 degrees North latitude. Hence after careful consideration of the various constraints, a site at Gadanki Village, near the temple town of Tirupati in the Chitoor district of Andhra Pradesh was selected for locating the Indian MST Radar . NMRF is located off the Chitoor -Tirupati main road in a picturesque landscape spreading over an area of about 42 acres. Regular train and bus services are operated between Tirupati and Bangalore/Madras. On request NMRF may provide transport between Tirupati and Gadanki.

SOURCE: The National MST Radar Facility (NMRF)
http://www.isro.org/nmrf/default.htm

http://www.thelivingmoon.com/45jack_file....r_Facility.html

Cherenkov Radiation around Antennas

Image courtesy ISRO

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 7:05pm

Jicamarca Radio Observatory

HAARP Like Facility
Lima, Peru
11° 57' 04.82" S 78° 52' 27.43" W

Image courtesy Colorado University

Introduction

The Jicamarca Radio Observatory is the equatorial anchor of the Western Hemisphere chain of incoherent scatter radar (ISR) observatories extending from Lima, Perú, to Søndre Strømfjord, Greenland. It is part of the Geophysical Institute of Peru (Instituto Geofísico del Perú, or IGP) and receives the majority of its financial support from the National Science Foundation of the U.S. through a Cooperative Agreement with Cornell University.

The Observatory is the premier scientific facility in the world for studying the equatorial ionosphere. It has a 2-MW transmitter and a main antenna with 18,432 dipoles covering an area of nearly 85,000 square meters.

SOURCE: Jicamarca Radio Observatory
http://jicamarca.ece.cornell.edu/overview.html

Piura facility: Jicamarca Radio Observatory

The Observatory is about a half-hour drive inland (east) from Lima, Peru at a geographic latitude of 11.95° south and a longitude of 76.87° west. The altitude of the Observatory is about 500 m ASL.

It is about 10 km from the Carretera Central, the main highway east in Peru.

The Jicamarca Radio Observatory was built in 1960-61 by the Central Radio Propagation Laboratory (CRPL) of the National Bureau of Standards (NBS).

Station Database
http://jro.igp.gob.pe/english/database/database_en.htm

Image Courtesy Cornell University

The Jicamarca Radio Observatory - Cornell University
http://jicamarca.ece.cornell.edu/

The 49.92 MHz ISR is the principal facility of the Observatory. The radar antenna consists of a large square array of 18,432 half-wave dipoles arranged into 64 separate modules of 12 x 12 crossed dipoles. Each linear polarization of each module can be separately phased (by hand, changing cable lengths), and the modules can be fed separately or connected in almost any desired fashion. There is great flexibility, but changes cannot be made rapidly. The individual modules have a beam width of about 7 deg, and the array can be steered within this region by proper phasing. The one way half power beam width of the full array is about 1.1 deg; the two way (radar) half power width is about 0.8 deg. The frequency bandwidth is about 1 MHz. The isolation between the linear polarizations is very good, at least 50 dB, which is important for certain measurements. Since the array is on the ground and the Observatory is the only sign of man in a desert region completely surrounded by mountains, there is no RF interference. The transmitter consists of four completely independent modules which can be operated together or separately. Only two of these modules are currently in operation. Each can deliver ~1.5 MW peak power, with a maximum duty cycle of 6%, and pulses as short as 0.8-1.0 μs. Pulses as long as 2 ms show little power droop; considerably longer pulses are probably possible. Two additional modules with the same properties will eventually be available. The third is more than 90% complete; the fourth is well advanced but its completion will require additional funding. The drivers of the main transmitter can also be used as transmitters for applications requiring only 50- 100 KW of peak power...

SOURCE: Jicamarca Radio Observatoryhttp://www.kurasc.kyoto-u.ac.jp/radar-group/local/isr/jicamarca/overview.html

MUCH BIGGER THAN **HAARP**
Main Array

Visit the Jicamarca Radio Observatory homepage
http://jro.igp.gob.pe/


N
Image © 2007 DigitalGlobe
© 2007 Europa Technologies
©2007 Google™
Pointer 11°57'04.82" S 78°52'27.43" W elev 1667 ft
Streaming 100%
Eye alt 3973 ft

http://www.thelivingmoon.com/45jack_file....bservatory.html

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 7:07pm

Jindalee Operational Radar Network

JORN
JP 2025
Laverton, West Australia
-28° 19' 36.29", +122° 0' 18.84"

Two Part System

CAND98/0153-03
JORN PROJECT RECEIVER SITE, LAVERTON W.A.
PIC BY CPL DAVE BROOS, DEFENCE PUBLIC AFFAIRS.

Projects

JP 2025 - Jindalee Operational Radar Network (JORN)

The JORN project arose out of extensive research undertaken by the Defence Science and Technology Organisation (DSTO) into over-the horizon radar (OTHR) beginning in the early 1970s. As part of the 1987 Defence White Paper, the Government placed a high priority on wide area surveillance of the north and north western approaches to Australia and OTHR was seen to be the most cost effective solution. As a consequence, in December 1990, the Government approved the design and construction of JORN.

The Jindalee Operational Radar Network (JORN) consists of two OTHR, one near Longreach, Qld. and the other near Laverton, WA, jointly operated from the JORN Coordination Centre (JCC) at RAAF Base Edinburgh, SA by No 1 Radar Surveillance Unit. The radars are an advanced development of the Australian designed Jindalee radar at Alice Receiver Site, Laverton WA - click on image to enlargeSprings which is in operational use as well as being a research and development facility used by DSTO for ongoing OTHR improvement. JORN radars are capable of all weather detection of air and surface targets inside an arc of up to 3,000 km range extending from Geraldton in the west around to Cairns in the east. JORN makes a crucial contribution to broad area surveillance of Australia's strategically important northern approaches.

SOURCE:
Australian Department of Defence
Defence Materiel Organization
http://www.defence.gov.au/dmo/esd/jp2025/jp2025.cfm

Electronic Warfare & Radar Division - DSTO, Australia
http://www.dsto.defence.gov.au/page/3603/

CAND98/0153-25
JORN PROJECT RECEIVER SITE ANTENNA ARRAY, LAVERTON W.A.
PIC BY CPL DAVE BROOS, DEFENCE PUBLIC AFFAIRS.
Courtesy Australian Department of Defence

Courtesy Australian Department of Defence



http://www.thelivingmoon.com/45jack_file....k_Laverton.html

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 7:09pm

Jindalee Operational Radar Network

JORN
Longreach, Queensland, Australia
-23° 39' 29.53", +144° 8' 49.58"

JORN Part Two

Communications '92: Communications Technology, Services and Systems; Getting It All Together

The Jindalee Operational Radar Network Communications and the Operational Concept
Nicholson, P1; Cameron, A2

Abstract: The operational concept of the Jindalee over-the-horizon operational radar network (JORN) is the centralised control and co-ordination of remote sensors. The radar sites are in Laverton, WA and Longreach, Queensland, while the co-ordination centre is situated in Adelaide, South Australia. An extensive communications network is needed to control the radars and their associated frequency management systems, transfer partly processed data for final analysis at the co-ordination centre, and pass track information to the command support systems of the Australian Defence Force and other users. The principle of operation, configuration and concept of the Jindalee project are briefly outlined to provide the context of the communications requirement. The communications infrastructure to support this operational concept is then described together with the main factors which have influenced the design of JORN communications.

Papers Available Here
http://search.informit.com.au/documentSummary;dn=563982181256363;res=IELENG

Consultancy Projects

Jindalee Operational Radar Network

RayTec Consulting has since its inception offered sub-contract services on the JORN project across a broad spectrum of Systems Engineering disciplines from Requirements Analysis and Design, Verification and Validation to
Integration and Test.

SOURCE: http://www.raytec.com.au/wp/projects

Electronic Warfare & Radar Division



High frequency surface wave radar. Credit DSTO

Electronic Warfare & Radar Division

Electronic Warfare & Radar Division provides scientific leadership and support to the Australian Defence Organisation on the exploitation of the electromagnetic spectrum to enhance the performance of our own sensors, weapons, platforms and command systems, together with the ability to destroy the effectiveness of adversarial systems.

Weapons Systems Division

Weapons Systems Division provides scientific leadership and support covering all aspects of weapon systems - including sensors, guidance, propulsion and warheads, and their integration into combat platforms and command and control systems.

Command, Control, Communications & Intelligence Division

Command, Control, Communications & Intelligence Division provides scientific leadership and support for Defence command, intelligence, communications, and business processes, at both the operational and theatre levels of command. Support to the Australian Defence Organisation includes Information Operations with special capabilities in Information Security and Digital Forensics; Communications with special capabilities in Satellite Communications, Mobile Networks and Network Management; Intelligence Processing and Analysis with special capabilities in signals analysis, communications analysis, automated fact extraction, and speech processing. The Division has organised its work program to have a strong emphasis on support achieving the goals as outlined in the Network Centric Warfare roadmap.

Intelligence, Surveillance & Reconnaissance Division

Intelligence, Surveillance & Reconnaissance Division provides scientific leadership and support for strategic intelligence, surveillance and reconnaissance systems, with a focus on the needs of the intelligence community.

Land Operations Division

Land Operations Division provides scientific leadership and support to the Land Force through structured and analytical approaches to capability development.

SOURCE: DSTO
http://www.dsto.defence.gov.au/page/3603/

http://www.thelivingmoon.com/45jack_file.... Longreach.html

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 7:12pm

[quote]*Originally posted by zorgon*

Poker Flat Research Range

Near Chatanika, Alaska
+65° 7' 23.90", -147° 28' 7.05"

Still looking for the actual array in this area but Poker Flats covers a wide terrain and the array is most likely hidden in the trees

Gate sign says NASA is lurking about and they mention the Aurora studies...


POKER
FLAT
RESEARCH RANGE
30 MI. STEESE HWY. FAIRBANKS, ALASKA
ADVANCE NOTICE REQUIRED FOR TOURS
POKER FLAT
RESEARCH RANGE
GEOPHYSICAL INSTITUTE UNIVERSITY OF ALASKA FAIRBANKS, ALASKA 99775-0800
(907) 474-7015
THE BEST EQUIPPED SOUNDING ROCKET LAUNCH FACILITY IN THE NORTH, ESTABLISHED BY THE GEOPHYSICAL INSTITUTE OF THE UNIVERSITY OF ALASKA, FAIRBANKS. THIS FACILITY IS UNIQUELY DEDICATED TO STUDIES OF THE AURORA BOREALIS AND OTHER ATMOSPHERIC RESEARCH STUDIES FOR THE PAYING CUSTOMER SUCH AS THE NATIONAL AERONAUTICS AND SPACE ADMINISTRATION, THE UNITED STATES AIR FORCE, THE UNITED STATES ARMY, THE NATIONAL SCIENCE FOUNDATION, AND OTHERS.
FIRST LAUNCH FROM THIS FACILITY MARCH 1969
LATITUDE 65°07' NORTH LONGITUDE 147°28' WEST

HAARP likely not Primary Ionospheric array in Alaska by Guy Cramer
http://www.superforce.com/**haarp**/index.htm

How to hide a **HAARP** by Guy Cramer

This first photo shows **HAARP**


Power Generation Building
and Future Operations Center
48 Element
HF Antenna Array
Temporary
Operations Center
Temporary
Riometer Pad
Aircraft Alert Radar

The second photo shows **HAARP** with a camouflaged Array


Power Generation Building
and Future Operations Center
48 Element
HF Antenna Array
Temporary
Operations Center
Temporary
Riometer Pad
Aircraft Alert Radar

The third image shows a completely concealed array, road and power generation center, to show how easy it is to hide a large facility in a location like Alaska.


Power Generation Building
and Future Operations Center
48 Element
HF Antenna Array
Temporary
Operations Center
Temporary
Riometer Pad
Aircraft Alert Radar

"The above illustrations demonstrate the capability to effectively conceal large land areas containing hardware and buildings. In a similar initiative comprising the the most comprehensive infrastructure concealment program since World War II, the design team of Dr. Resnick, Lt. Col. Timothy R. O'Neill, PhD (U.S. Army, Ret.) and Mr. Guy Cramer have produced remarkable results. Using specially designed "Fractal Based" camouflage patterns in projects related to concealment of critical infrastructure under the auspices of the US Department of the Interior's Bureau of Land Management, the team continues to achieve desired objectives such as those shown below."

SOURCE: Guy Cramer Hyperstealth Tech
http://www.superforce.com/**haarp**/index.htm

We have found this one...

Chatanika Incoherent Scatter Facility

EISCAT Like Facility
Poker Flats
+65° 7' 1.34", -147° 27' 37.23"



Also found one small Array...
+65° 7' 55.61", -147° 27' 14.98"

And several 'suspicious' areas like this one

But Poker Flats is still a work in progress

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 7:20pm

Baikal-1 and IGR sites
Semipalatinsk-21, Kazakhstan

This one is a direct tie in with Remote Viewing success and Tesla technology.

It is said Russia has several **HAARP** like facilities, bt so far I have only found SURA

Back in the scalar weapon and Tesla research days there are several objects left in Russia that are very impressive. As they deal with antennas and as they are cool I will add them here as well...

You will also have to visit my pages at the bottom of each post as I am only using a few of the images and a little of the text... the full collection is on each page as I get new data...

First one is...

URDF-3 (Unidentified Research and Development Facility-3)
Baikal-1, Semipalatinsk, Kazakhstan
50°10'12.69"N, 78°22'36.84"W

This first appeared as a CIA satellite image



U.S. satellite reconnaissance photo of suspected Soviet beam weapon installation near Semipalatinsk.
Published July 28, 1980. (Courtesy Aviation Week & Space Technology)

Much has been written about the CIA search for Russia's Tesla Beam Weapon facility and it is even one of the biggest cases for the Remote Viewing Project Stargate that the CIA ran. One of the things that was a positive hit from the RV Team was the huge crane at the site...

Well that crane is STILL THERE...

Men and Women Practice Differently

***Men**:* Shoot the Pearl out of the Crown, and Spiral the Pearl down from the Crown.

a. Bring the pearl up to the crown.
b. Allow the pearl to go out three to six inches above the head. Circle nine times counterclockwise. Collect the heavenly energy and blend it in the pearl. Then circle it nine times clockwise.
c. Bring the pearl back into the crown point.
d. Spiral it clockwise through each of the Belt Channels all the way down to the soles of the feet.
e. Move the pearl into the earth six to twelve inches to collect the earth energy, and circle the energy nine times clockwise. Reverse the direction spiraling nine times counterclockwise.
f. Return the pearl to the front of the crown, and then back down to the navel and cauldron in the same manner.



For Men: Spiral six inches clockwise above the crown and draw the universal Chi down into the three Thrusting Channels and down to the ground.

For Women: Spiral six feet under the ground counterclockwise. Once the pool of energy is built up, draw the universal Chi plus the healing earth Chi up to the feet and through the body.

Fig. 8.10 *Men and Women Practice Differently*



Space Nuclear Facility test capability at the Baikal-1 and IGR sites
Semipalatinsk-21, Kazakhstan

Hill, T. J.; Stanley, M. L.; Martinell, J. S.
Presented at the Nuclear Power Engineering in Space Nuclear Rocket Engines, Kazakhstan, Russia, 22-26 Sep. 1992

The International Space Technology Assessment Program was established 1/19/92 to take advantage of the availability of Russian space technology and hardware. DOE had two delegations visit CIS and assess its space nuclear power and propulsion technologies. The visit coincided with the Conference on Nuclear Power Engineering in Space Nuclear Rocket Engines at Semipalatinsk-21 (Kurchatov, Kazakhstan) on Sept. 22-25, 1992. Reactor facilities assessed in Semipalatinski-21 included the IVG-1 reactor (a nuclear furnace, which has been modified and now called IVG-1M), the RA reactor, and the Impulse Graphite Reactor (IGR), the CIS version of TREAT. Although the reactor facilities are being maintained satisfactorily, the support infrastructure appears to be degrading. The group assessment is based on two half-day tours of the Baikals-1 test facility and a brief (2 hr) tour of IGR; because of limited time and the large size of the tour group, it was impossible to obtain answers to all prepared questions. Potential benefit is that CIS fuels and facilities may permit USA to conduct a lower priced space nuclear propulsion program while achieving higher performance capability faster, and immediate access to test facilities that cannot be available in this country for 5 years. Information needs to be obtained about available data acquisition capability, accuracy, frequency response, and number of channels. Potential areas of interest with broad application in the U.S. nuclear industry are listed.

SOURCE: Harvard Abstracts
http://adsabs.harvard.edu/abs/1993STIN...9416773H

Here is the crane sketch from the CIA RV Team members



(a) TARGET SITE

(b) CRANE COMPARISON

Figure 1: Comparison of Target Site and Drawing by Remote Viewer

575310 3-78 CIA

SECRET
NOFORN
WNINTEL

SECRET

Here is the large crane on Google Earth



Credit for the find and info gathering goes to
admiraltogo
Fort Smith, AR
Google Earth poster

This base was also the spot where the Russians tested their version of a Nuclear Rocket

http://www.thelivingmoon.com/45jack_file....Kazakhstan.html [/quote]

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 7:26pm

Strange Towers in a Russian Forest
Tesla Generators

Sychëvka, Moskovskaya Oblast' (Russia)
+55°55'26.15"N,36°49'10.97"

Yet another old Russian project tied into Tesla research... I have included these because they are related, and just plain cool 😎

Update 2007-12-02 09:59:49

"These were part of the experiments do by the SU with Teslas work towards power transmission and communication. Pictures all over the place on the internet. Nothing mysterious or new about it. Or perhaps its a secret installation for taking over the world. Take you pick."

Below is the entry gate from Google Earth images... the caption translates to...
"Isled. the center of the high energies"


Ислед. центр высоких энергий
near Sychëvka, Moskovskaya Oblast' (Russia) by Dark Raven
Google Earth - ID: 4314798

Test benches VNITS - ALL-UNION SCIENTIFIC RESEARCH INSTITUTE OF CEMENT VEI
(high-voltage scientific research center of All-Russian electrotechnical institute).

Satellite View of the Installation near Sychëvka, Moskovskaya Oblast' (Russia)


+55° 55' 26.15", +36° 49' 10.97"

http://www.thelivingmoon.com/47john_lear....ian_Forest.html

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 7:29pm

The Russian Woodpecker

Duga Radar Array, Chenobyl, Ukraine
51°18'20.17"N, 30°04'02.60"E

"Woodpecker" Duga radar array, Chenobyl, Ukraine by Necator



РЛС Дуга-1 Чернобыль-2 (Radar arch-1 Chernobyl-2) by DM.HANTER

History

The Soviets had been working on early warning radars for their anti-ballistic missile systems through the 1960s, but most of these had been line-of-sight systems that were useful for raid analysis and interception only. None of these systems had the capability to provide early-warning of a launch, which would give the defenses time to study the attack and plan a response. At the time the Soviet early-warning satellite network was not well developed, so work started on over-the-horizon radar systems for this associated role in the late 1960s.

The first experimental system, Duga-1, was built outside Mykolaiv in the Ukraine, successfully detecting rocket launches from Baikonur Cosmodrome at 2,500 kilometers. This was followed by the prototype Duga-2, built on the same site, which was able to track launches from the far east and submarines in the Pacific Ocean as the missiles flew towards Novaya Zemlya. Both of these radars were aimed east and were fairly low power, but with the concept proven work began on an operational system. The new Duga-3 systems used a transmitter and receiver separated by about 60 km.[2]

http://en.wikipedia.org/wiki/Russian_Woodpecker

Чорнобиль-2. Приймальні антени (Chernobyl-2. Receiving Antenna) by djcrok

51°18'20.17" N 30°04'02.60" E

MANY more pictures

http://www.thelivingmoon.com/45jack_file....ar_Ukraine.html

Main Stream Media coverage..

The Missing Secrets Of Nikola Tesla - Woodpecker Signal
Russia makes Aurora's with Woodpecker Array

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 7:33pm

China Research Institute of Radiowave Propagation (CRIRP)

HAARP Like Facility

Ionospheric Laboratory

Ionospheric Laboratory, Xinjiang (Sinkiang) Region
40°24'15.91"N, 93°38'09.74"E

So far I have only found ONE of China's Arrays and one EISCAT type dish.

Not much data to go on either but the name...
CRIRP
China Research Institute of Radiowave Propagation



This facility is closest to Urumchi (Urumqi), Xinjiang Region, China. Actually the whole region is filled with odd markings and will be a whole thread on its own but not related to radio waves...

Ionospheric sounding network and data in China

Wu Jian Jiao Peinan Xiao Zuo Wan Weixing Liu Ruiyuan Zhao Zhengyu
LEME, China Res. inst. of Radiowave Propagation, Beijing;

This paper appears in: Antennas, Propagation and EM Theory, 2000. Proceedings. ISAPE 2000. 5th International Symposium on
Publication Date: 2000
On page(s): 688-691
Meeting Date: 08/15/2000 - 08/18/2000
Location: Beijing, China
ISBN: 0-7803-6377-9
References Cited: 10
INSPEC Accession Number: 6963766
Digital Object Identifier: 10.1109/ISAPE.2000.894880
Current Version Published: 2002-08-06

Abstract
Ionospheric sounding has been conducted routinely for more than 60 years in China. A complete network of ground-based sounding sites covers the Chinese subcontinent, including vertical and oblique sounding, GPS measurement of ionospheric TEC and scintillation, **VLF** receivers measuring the lower ionosphere etc. In this paper, we give a picture of the sounding network, equipment situation and data acquired with emphasis on vertical ionosonde network

SOURCE: IEEE
http://ieeexplore.ieee.org/xpl/freeabs_a....&isnumber=19345

The Ionospheric Sounding in China

The ionospheric sounding in China has a long history and has a well spread network, which is still keeping routine operation, providing a good background to do the ionospheric long-term prediction and short-term forecasting. The ionospheric sounding in China started in early 1940s (Wu et al., 2002). Fig.1 shows the ionospheric sounding network in China. The sounding equipments and operation periods are listed in Table 1. Among them 11 ionosonde stations are still in operation in China mainland. The data at integer UT hours are sent to forecasting center in Beijing twice a day through Internet.

There is also a daily exchange of ionospheric data with Russian (for 4 stations) and with Australia (for 4 stations) respectively. A method of predicting the ionospheric F2 layer in the Asia and Oceania Region (AOR Method [Sun X.R., 1987]) was adopted as a regional ionospheric long-term prediction method in China and its surrounding area. Then this was cooperated with the International Reference Ionosphere and became the Reference Ionosphere in China (CRI) [Liu et al., 1994].

http://www.irf.se/~christer/China_IONO.doc

Preliminary studies on ionospheric forecasting in China and its surrounding area

R. Liua, Corresponding Author Contact Information
E-mail The Corresponding Author, Z. Xua, J. Wub, S. Liua, B. Zhanga and G. Wangb

Polar Research Institute of China, 451 Jinqiao Road., Shanghai 200136,
China bChina Research Institute of Radiowave Propagation, Xinxiang 453003, China

Abstract

The ionospheric sounding in China has a long history and has a well spread network, which is still keeping routine operation. The autocorrelation method is adopted for the short-term forecasting of ionospheric characteristics. The performances of the forecasts at Chongqing have been examined for different combination of parameters and algorithms by estimating the prediction errors. Preliminary results show that for predictions of more than 10 h ahead the “at once” method with f0F2 is preferable. For predictions of less than 10 h ahead the “iterations” method with View the MathML source is the best. A corrected method of the International Reference Ionosphere used in China region (the CRI model) is described in this paper. By introducing an effective ionospheric index Ice into the CRI model the regional forecasting could be realized.

SOURCE: Science Direst

Home Address:

National Key Lab of Electromagnetic Environment, China Research Institute of Radiowave Propagation (CRIRP), P.O. Box 6301, Beijing 102206, China,



Fig 1 Ionospheric Sounding Network in China

Table 1 Ionospheric sounding equipments and operating periods in China



Site	Ionosonde	GPS TEC receiver	GPS scintillation receiver	VLF signal receiver	Dif. Doppler receiver	Polarimeter TEC and scintillation
Manzhouli	1954—now				1982—1991	
Changchun	1956—now					
Urumchi	1957—now				1982—1992	
Beijing	1953—now	1998—now			1994—1996	1980—1992
Lanzhou	1956—now					
Qingdao	1999—now	1994—now		1997—now	1994—1996	
Xinxiang	1988—now	1994—now		1978—now	1982—1992	1981—1992
Sheshan	1957—1966					
Wuhan	1957—now	1994—now		1988—now		1980—1990
Lhasa	1970—now					
Chongqing	1944—now				1981—1992	
Guangzhou	1955—now				1985—1989	
Haikou	1956—now	1994—now	1998—now	1999—now	1982—1987	1986—1989
Great wall	1986—now		1998—now	1998—now	1989—1996	
Zhongshan	1990—now		1998—now	1998—now		

http://www.thelivingmoon.com/45jack_file....ropagation.html

Zhong Shan Antarctic Polar Station (China)

69° 22' 23.63" S 76° 22' 19.11" E

Introduction

Of the two Chinese scientific stations in Antarctic, the one in Zhong Shan is closely conjugated with the Svalbard area in the northern hemisphere. This makes it a valuable place for coordinated measurements both with the EISCAT Svalbard Radar (ESR) and the Polar satellite. In 1991 a cooperation agreement was signed between the Ionospheric Laboratory of the China Research Institute of Radiowave Propagation (CRIRP) in Xinxiang, China, and the Department of Physical Sciences, University of Oulu, Finland, to build an auroral photometer system for the Zhong Shan station (Kaila et al, 1997). The multichannel scanning photometer agreed upon was constructed in Oulu by April 1995, and delivered to China in May. Measurements were supposed to start in March 1997, to be continued during the local winter time until October (the same schedule of measurements is planned for every year). However, due to problems mentioned above, the current status of the system is unknown!

The Zhong Shan Station, Antarctica
http://www.thelivingmoon.com/45jack_file....Zhong_Shan.html

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 7:36pm

Sheshan, Shanghai, China

EISCAT Like Facility
31°5′41.98″N, 121°11′29.72″E

The Sheshan 25m radio telescope is an alt-az antenna run by SHAO.
The telescope is located in the Sheshan area, about 40km west of Shanghai.

This one is in the middle of the Old Jesuit Cathedral lot. They have an observatory there as well

Observatory and Church

Women: Shoot the Pearl into the Earth, and Spiral the Pearl up from the Earth

a. Bring the pearl to the soles of the feet.
b. Move the pearl into the ground six to twelve inches to collect the earthly energy. Circle the energy nine times clockwise. Then nine times counterclockwise.
c. Move the pearl up through the left side of each Belt Channel, spiraling counterclockwise to the crown.
d. Shoot the pearl all the way out at the crown to collect the heavenly energy. Circle the energy counterclockwise nine times. Reverse the direction, and spiral the pearl nine times clockwise.
e. Bring the pearl back down into the right side of the crown. Continue to circle the energy clockwise down through the Belt Channel to the soles of the feet. Return the pearl to the navel and cauldron in the same manner.

Forming a Vehicle

Continue feeling all the pakuas spiraling around the energy center and around the body.



Fig. 8.11 *Spiraling the Pearl and Pakuas faster and faster.*

http://www.thelivingmoon.com/45jack_files/03files/China_Sheshan.html

Been a lot of rumors around that the Jesuits still have a lot of control in the world...

Look up Wheeling Jesuit University... search for NASA grants and ask why is NASA giving money to a Church organization?
http://www.wju.edu/

Look up the National Technology Transfer Center (NTTC) These guys are in charge of who gets new technology

The National Technology Transfer Center (NTTC) has entered its 20th year of providing technology transfer services for federal facilities of our nation. Our work has provided clients with technical and market research expertise dedicated to meeting the complex needs of technology transfer organizations, while providing close support focusing on customer service. NTTC is inspired by the technologies developed at our federal R&D institutions, and is proud of our work commercializing and disseminating federal innovation for the betterment of our nation's economy.

Ask why do the Jesuits control technology transfer?

©2009 National Technology Transfer Center, Wheeling Jesuit University
http://www.nttc.edu/

But that is a whole new story

Back to **HAARP**/EISCAT like stuff...

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 7:51pm

HAARP High Frequency Active Auroral Research Program

Gacona, Alaska

There are more but that is all I have cataloged so far

But each one of those sites links to documents that link to other cogs in the wheel...

I am sure I have missed a few

I will add more as I have time to create the webpages. Feel free to add anything that you find from those links...

I will finish with some of the original **HAARP** images. You can also go to Jack Arnesons page and look under **HAARP** and Similar Facilities



HARRP Alaska
+62° 23' 30.00", -145° 8' 48.00"

HAARP cam image...

2009/09/21 19:40 AKDT

http://www.thelivingmoon.com/45jack_file....ona_Alaska.html

This is the **HAARP** 'home page'
http://www.**haarp**.alaska.edu/

But remember that the real **HAARP** project is run by the US NAVY NRL (Naval Research Laboratory

High Frequency Active Auroral Research Program
http://www.nrl.navy.mil/content.php?P=04REVIEW106

HAARP Photo Gallery and web cam access links

http://www.thelivingmoon.com/45jack_file....Gallery_01.html

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 8:00pm

Going through my old thread for relevant posts... here is one...

Quote:

> *Originally posted by TheWretched*
> Many of the ones you have listed are nothing but observatories for looking into the stars. Some are nothing but radar stations.

If you believe THAT then you haven't read anything about them. So much for your 'expertise' Most of the ones listed came from EISCAT and **HAARP** OFFICIAL websites

I haven't even listed all yet..but the antennas at
Kiruna, Sweden
Longyearbyen, Svalbard (Spitsbergen), Norway
Sodankylä, Finland
Søndre Strømfjord, Greenland
Ramfjordmoen, near Tromsø, Norway

Are most certainly used for Ionosphere manipulation and research which is after all THE POINT of these facilities and hence the thread



Why do these skeptics always have nasty names?

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 21, 2010, 8:10pm

Lot of weird stuff happening lately... Ocker has noticed it too, he said so in an ATS thread...

Stuff I have been looking for for years is suddenly posted on Wikipedia, Buzz Aldrin now posts the confirming data on his site about Aquila and the very day I made that **HAARP** thread at ATS...

Quote:

> *Originally posted by autowrench*
> Great post, starred and flagged. Did anyone happen to watch the History Channel last night? They had as show called "That's Impossible," and the show as all about **HAARP**, and the different facilities around the world, and how they use it as a weather weapon. I too have researched this thing, but the show had all of the tech, plus computer animation, and was fabulously presented.

Now how is that for coincidence? Same dang thing happened with PBS NOVA... A week before I was going to post all the original Secret Astronaut material we had collected, NOVA does :Astrospies"

{{{insert score to 'Twilight Zone' here}}}

Re: Every One Speaks about HAARP, but did you know
Post by dragar on Sept 21, 2010, 10:09pm

Zorgon im going to add this in please feel free to delete this post.
Take alook at it see if this is a bit strange.
HAARP= High Frequency Active Auroral Research Program
The Prince Albert Radar Laboratory (PARL):The original study that led to PARL came about as the side effect of questions about the effects of the aurora on radar systems.
Work on the **HAARP** Station began in 1993
Prince Albert Radar Laboratory limited operations started in 1959.
Could this be what sparked **HAARP**?

The Prince Albert Radar Laboratory

A satellite is any smaller object traveling around a larger one. This means that the moon is a satellite to the Earth. However, the term satellite often refers to a human-made spacecraft placed in space to orbit another body.

The first "communicatons satellite" was the moon. The USA started using the moon for communications trials in the early 1950's. Signals beamed towards the moon were reflected and received back on Earth. It was a very inefficient means of communication requiring high power and large antennas to produce a detectable system. In addition, communication was only possible while the moon was above the horizon.

DRTE staff participated in the trials starting in 1959 using a large radar station at the newly-built Prince Albert Radar Laboratory (PARL) in Saskatchewan. The first demonstration was given when Prime Minister John Diefenbaker inaugurated the station on June 6, 1959. Here are some photos of the inauguration. A pre-taped greeting* from President Eisenhower was transmitted from a station at Millstone Hill near Boston and received by the PARL station. Each station was equipped with a 26-m dish antenna. Diefenbaker used the occasion to announce that Canada would initiate its own satellite program. Here* is part of Mr. Diefenbaker's speech.

http://www.friendsofcrc.ca/Projects/PARL/PARL.html

As a side note :MY family and I have been there twice. It is very active many upgrades including a new security fence around it.
You may have to dig around in the link I gave for further info . ty

At the beginning, the work of the laboratory was focused on high frequency radio and the problem of forecasting the ionospheric conditions which determined the availability of any given frequency and transmission path. To this end, a new ionospheric sounder was designed by a team led by Bill McLeish. These sounders were constructed at RPL and were installed in a number of stations established across Canada. Most of the components were those which had been removed from surplus military equipment. The stations were manned by DOT personnel who were trained in their operation by Bob Stevens in a small building below the main laboratory by the shore of the Rideau Canal.

A second project arose from some of the HFDF work during the war. It had been noted that transmissions passing through the auroral zone had been deflected by as much as 20 degrees. To investigate this phenomenon further. Jack Meek proposed what became known as the "Mobile" experiment. A railroad car was equipped with a laboratory, diesel generators, accommodation, and cooking and eating facilities. Ionospheric sounders were installed, a crew was chosen and the car was hauled up to The Pas in Manitoba. From there, it was attached to the train which ran to Churchill and was shunted onto sidings at various points along the route. Antennas would be erected, and a series of ionospheric soundings taken. The car would then be hauled to the next siding and the process repeated. A line of soundings was thus obtained crossing the auroral zone. Jack Meek was in charge of the operation for the first period from the autumn of 1947 to January 1948 when Claire McKerrow took over. With Claire were Harold Serson, Cam Baker, and Sgt. Len Hagg on loan from the Canadian Army. The cook, provided by CNR, had an unfortunate habit of disappearing whenever the expedition arrived in The Pas. He was usually found in one of the local bars shortly before the train left. On one occasion, the town was searched from end to end to no avail. He was finally located in the local hospital, and they had to carry on without him. Claire called for volunteers to do the cooking with no success until Harold Serson finally admitted that he could cook a little. (In fact, Harold could have competed with most professional chefs.) Claire and Harold then shared the task until the cook's return. Food was supplied by the CNR from Winnipeg. Both Claire and Harold were inordinately fond of Winnipeg goldeye, and they ordered several cases of this delicacy.. The rest of the crew ate smoked goldeye, like it or not.

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Sept 22, 2010, 6:14am

Nice addition Did not have that one yet

Location, Location, Location

The requirements for the radar's site were twofold.

1. The site should permit the radar beam to illuminate the ionosphere over the Churchill, Manitoba region at the height at which the Aurora Borealis (Northern Lights) normally occurs. This would enable the comparison of auroral radar returns with simultaneous geophysical measurements made from Churchill.
2. The site should be accessible to scientists from the Physics department of the University of Saskatchewan, Saskatoon, where considerable expertise in auroral studies existed.

So it seems the location was specifically chosen to mess with the Aurora's.. so yeah... not only the predecessor for HAARP but proof that all big EISCAT and other huge radar dishes can effect the ionosphere

Nice catch

Re: Every One Speaks about HAARP, but did you know
Post by dragar on Sept 22, 2010, 3:58pm

University of Saskatchewan
Auroral Radar - Saskatchewan

Early 1948
Peter Forsyth was preparing for medical school when Balfour Currie, returning from meeting in Ottawa, asked if he would help modify a radar to be borrowed from the Navy to seek radar echoes from aurora.
This turned out to be a 3000 MHz surveillance radar. It was modified and operated, but no auroral echoes were detected.

Auroral Radar - Saskatchewan

1948-49
With the aid of Nate Gerson, the USAF provided two huge 106 MHz early-warning radars. One went to Saskatoon, the other to NRC (McKinley), where it was to be modified to 56 MHz
First Canadian auroral echoes were detected with this radar in 1949 (paper in Nature, April, 1950).
As a result, Peter Forsyth decided to do his PhD on auroral echoes, rather than go into medicine.

Auroral Radar - Saskatchewan

1948-49 - Postscript
Around 1990 a phone call came to the Department of Physics at the University of Saskatchewan asking if they had an SCR-270 radar with a particular serial number
They did! It was the original radar which detected the incoming Japanese planes arriving to bomb Pearl Harbor (that information was ignored).
For over 40 years that radar had been sitting "buried" in Saskatoon. It is now at the Historical Electronics Museum near Baltimore.

Auroral Radar - Saskatchewan

1951-52
The modified radar came to Saskatoon from Ottawa, and a combined dual-frequency antenna was constructed.
Simultaneous observations of auroral echoes were observed at 56 and 106 MHz (1953 paper)
In 1951, Peter Forsyth finished his PhD and was hired to work at the Defence Research Telecommunications Establishment(DRTE) at Shirley Bay, near Ottawa, but since the facility didn't exist yet, he continued at Saskatoon for another year. It was a year later when he moved to DRTE, where he remained until 1958, rising to the position of Superintendent of the Radio Physics Lab.

Pre-History

1931 - NRC Radio Section established
1932 - Dr. John Henderson (PhD with Appleton)
1935 - Maj.-Gen. A.G.L. McNaughton new NRC President helped invent a cathode-ray tube direction-finder in the 1920s
1936-38 - Henderson developed direction-finder for marine and air use, installed in Nova Scotia in 1938
1938 - McNaughton was consulting with DND re detection of aircraft by electrical means
1939 - Henderson sent to UK to be briefed on radar developments

World War II

McNaughton contacted by Sir Charles Wright
you have expertise, get into this radar development
send physics graduates to UK Navy - badly needed
Peter Forsyth developed air-borne radar in UK, 1942-45
NRC became centre of radar development in Canada
McGill, Queens, Toronto, Western also involved in radar research
REL (Crown corporation) established to manufacture optical equipment, radar
During course of war, NRC designed more than a dozen different radars at many frequencies: 75, 95, 150, 200, 215, 2,800, 3,000, 10,000 and 24,000 MHz.
REL manufactured over 2000 radar sets, mostly for Navy, Army

Post-war

NRC
microwave experience --> Covington's 10.7cm solar radio-telescope (1946)
McKinley --> meteor radar program (1947)
DRB
established 1947 to take over defence research role which NRC refused to continue with after the war.
took over labs from services (e.g. Naval Research Establishment, CARDE), and started new ones (DRTE, DRNL, Ft. Churchill)
Weather radar
started in 1943 as a Canadian Army project in Ottawa, led by Stewart Marshall.
Post-war, at DRB & McGill, until 1950, then McGill alone. (Stormy Weather)

Re: Every One Speaks about HAARP, but did you know
Post by dragar on Sept 22, 2010, 4:09pm

EISCAT

In addition to the incoherent scatter radars, EISCAT also operates an Ionospheric Heater facility at Ramfjordmoen (including a Dynasonde) to support various active plasma physics experiments in the high latitude ionosphere.

Description of the EISCAT heating facility:

The Heating facility is situated next to the UHF and VHF incoherent scatter radars.
The Heater is used for ionospheric modification experiments applying high-power transmissions of high-frequency electro-magnetic waves to study plasma parameters in the ionosphere. The name Heating stems from the fact that these high power electromagnetic waves, which are transmitted into the ionosphre with high-gain antennas, heat the electrons and thus modify the plasma state. To create plasma turbulence, the transmitted frequencies have to be close to the plasma resonances, which are 4 to 8 MHz.

Re: Every One Speaks about HAARP, but did you know
Post by gigas on Sept 23, 2010, 9:32am

Here in wisconsin up north of me, we have clam lake and they run an ELF facility there to communicate with subs deep under the sea. This ELF transmitter is connected by another facility 128 miles east in michigan. I would guess this also holds true for the underground communications of other secret facilities regular radio communications cannot be linked up with.

This facility was said to be shut down some years ago but according to the dot mil link below, it still operates.

http://enterprise.spawar.navy.mil/UploadedFiles/fs_clam_lake_elf2003.pdf

---

Re: Every One Speaks about HAARP, but did you know
Post by pman35 on Sept 27, 2010, 11:46am

Hi guys have'nt read any of this but i have to say i'm pretty impressed zorgon with what u've posted to me it looks like if all these were connected they would indeed create a shield around the globe and because there are so many if one was to fail it might not affect the rest.

I will read this post as i have an interest in haarp.

Respect And May Disclosure Keep Moving Forwards

Re: Every One Speaks about HAARP, but did you know
Post by magooollo on Oct 5, 2010, 11:25am

buzz aldrin and edgar mitchell (apollo astronauts) are involved in the UFO community, perhaps as information conduits tho that isnt offically acknolwedged , would make good intermediatries in the disclosure race

---

Re: Every One Speaks about HAARP, but did you know
Post by somamech on Oct 5, 2010, 4:14pm

Interesting pdf Gigas!

EDIT

For anyone curious as to when Zorgon mentioned that sometimes documents coming from us mil sites cannot be accessed by folk abroad, this is what you may see showing in your browser. *Obviously I'm in Australia... and this is how our allie treats us?*


Angels Still Don't Play This HAARP
Open Minds Forum - Every One Spe...
You are not authorized to view th...

You are not authorized to view this page

You do not have permission to view this directory or page using the credentials that you supplied.

Please try the following:

- Contact the Web site administrator if you believe you should be able to view this directory or page.
- Click the Refresh button to try again with different credentials.

HTTP Error 401.1 - Unauthorized: Access is denied due to invalid credentials.
Internet Information Services (IIS)

Technical Information (for support personnel)

- Go to Microsoft Product Support Services and perform a title search for the words **HTTP** and **401**.
- Open **IIS Help**, which is accessible in IIS Manager (inetmgr), and search for topics titled **Authentication**, **Access Control**, and **About Custom Error Messages**.

EDIT: PDF in question which Gigas posted is this link below:

http://enterprise.spawar.navy.mil/UploadedFiles/fs_clam_lake_elf2003.pdf

---

Re: Every One Speaks about HAARP, but did you know
Post by winniethepooh4102 on Oct 5, 2010, 4:47pm

I found a torrent for it, but the downloading is very slow:

http://extratorrent.com/torrent_download....s+HAARP.torrent

But there is something more to HAARP if one
could believe in some claims.

Re: Every One Speaks about HAARP, but did you know
Post by gigas on Oct 5, 2010, 5:37pm

Oct 5, 2010, 4:14pm, somamech wrote:

> Interesting pdf Gigas!
>
> EDIT
>
> For anyone curious as to when Zorgon mentioned that sometimes documents coming from us mil sites cannot be accessed by folk abroad, this is what you may see showing in your browser. *Obviously I'm in Australia... and this is how our allie treats us?*


Angels Still Don't Play This HAARP
Open Minds Forum - Every One Spe...
You are not authorized to view th...

You are not authorized to view this page

You do not have permission to view this directory or page using the credentials that you supplied.

Please try the following:

- Contact the Web site administrator if you believe you should be able to view this directory or page.
- Click the Refresh button to try again with different credentials.

HTTP Error 401.1 - Unauthorized: Access is denied due to invalid credentials.
Internet Information Services (IIS)

Technical Information (for support personnel)

- Go to Microsoft Product Support Services and perform a title search for the words **HTTP** and **401.**
- Open **IIS Help**, which is accessible in IIS Manager (inetmgr), and search for topics titled **Authentication**, **Access Control**, and **About Custom Error Messages.**

EDIT: PDF in question which Gigas posted is this link below:

http://enterprise.spawar.navy.mil/UploadedFiles/fs_clam_lake_elf2003.pdf

I can no longer access that pdf as well with I am not authorized to access that page. It appears they locked it from web access. I tried to navigate to the pdf with a proxy web service and it says I am not authorized to see the pdf.

Looks like they don't like this information being out there for all to see.

Re: Every One Speaks about HAARP, but did you know
Post by somamech on Oct 5, 2010, 5:41pm

I saved a copy

EDIT

Re-reading that PDF I can clearly see why they don't like that info in the public domain

[image]

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Oct 5, 2010, 5:56pm

Oct 5, 2010, 4:14pm, somamech wrote:

> For anyone curious as to when Zorgon mentioned that sometimes documents coming from us mil sites cannot be accessed by folk abroad, this is what you may see showing in your browser.

FAS.org has a copy

http://www.fas.org/nuke/guide/usa/c3i/fs_clam_lake_elf2003.pdf

---

Re: Every One Speaks about HAARP, but did you know
Post by winniethepooh4102 on Oct 5, 2010, 6:02pm

The ELF cannot conquer the Elves.

Re: Every One Speaks about HAARP, but did you know
Post by gigas on Oct 5, 2010, 6:04pm

Oct 5, 2010, 5:41pm, somamech wrote:

> I saved a copy
>
> EDIT
>
> Re-reading that PDF I can clearly see why they don't like that info in the public domain
>
> [image]

Reading that pdf, it looks like the facility is still operating when it was supposed to be closed sept 30 2004.

Read the following link to see whats happening in the wisc land of dot mil.

http://www.zcommunications.org/project-elf-rip-by-site-administrator

---

Re: Every One Speaks about HAARP, but did you know
Post by gigas on Oct 5, 2010, 6:13pm

Thanks zorgon and somamech.

I thought I had saved it when found but maybe not since I looked and could not find it on this pc. Maybe on my other machine. I did save it from zorgons link though. really I did.

I tried to use the cache way back machines and it is scrubbed from the web as is the link to http://enterprise.spawar.navy.mil. I can't access that link as well.

Re: Every One Speaks about HAARP, but did you know
Post by winniethepooh4102 on Oct 5, 2010, 6:13pm

My favourite movie was "The Mad Max", the day after tomorrow.

Re: Every One Speaks about HAARP, but did you know
Post by somamech on Oct 5, 2010, 6:31pm

Oct 5, 2010, 6:13pm, gigas wrote:

> Thanks zorgon and somamech.

I thought I had saved it when found but maybe not since I looked and could not find it on this pc. Maybe on my other machine. I did save it from zorgons link though. really I did.

I tried to use the cache way back machines and it is scrubbed from the web as is the link to http://enterprise.spawar.navy.mil. I can't access that link as well.

Me neither

I was always able to view that previously

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Oct 5, 2010, 6:34pm

One thing I need to mention....

Normally I will NEVER post a direct link to a file at a .mil site...

Why?

1) Many cannot get access from overseas
2) Many .mil sites that I visit require a certificate acceptance, which means you give them permission to monitor you. Some are several levels deep. This scares off the looky loos
3) Some ,mil sites like Maxwell AFB Archives will 'ping' back on the IP... happened once at ATS... everyone simply opening the page on that thread with the direct link got a warning pop up... I believe that contributed to ATS getting the rep of being government owned
4) This is the most important FILES GET MOVED because of the sudden traffic

Look at it this way An obscure document from 2003 has been idle for years... then suddenly I post a link say at ATS where several thousand viewers suddenly look at that file... well that sends up a red flag real fast

I have over 16,000 files I have saved... haven't even read them all yet but a friendly spook at ATS once told me that my posts generate unique hits on sites that they would rather remain quiet

So best bet is download the file and save it then post it somewhere else to share

One time I found a link to NASA Apollo photos... the FULL RS TIFF copies... I d/led a few posted something on a thread and while ArMaP was in the middle of a d/l the directory vanished. I never got all of them and I never found them again yet...

Another case I had a link to all the Rover images in full true color... that directory also moved... but fortunately I found that one again...

Because there are 40,000 pics on each Rover, I cannot d/l them all so I keep that link to myself now

Keith Laney has some of them on his site
http://www.keithlaney.net

Re: Every One Speaks about HAARP, but did you know
Post by somamech on Oct 5, 2010, 6:48pm

Good advice!

But in my case I don't mind clicking on those sites that require accepting a security certificate. In this case the whole site is offline...

Code:
```
http://enterprise.spawar.navy.mil./
```

Re: Every One Speaks about HAARP, but did you know
Post by somamech on Oct 5, 2010, 6:50pm

BTW..the moon boggy better not look like that POS LOL

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Oct 5, 2010, 6:51pm

Oct 5, 2010, 6:31pm, somamech wrote:

> Me neither
> I was always able to view that previously

Well see? You have just witnessed the system in action... I posted that link mainly because the word 'enterprise' was in that url. A similar one before was 'hyperspace.nrl.navy.mil/TiPS/' That was the info on the other tether satellite that flew at the same time the NASA one did (STS75)

It is still available on wayback machine

LINK

But this is what happens and that is why I have stopped posting direct links to sites like that because it means that I lose my sources when they plug the 'leaks'

Grab this one quick... it offers a 'public' access portal to the enterprise link, though I doubt the really cool stuff will be found there... but you never know

http://nesipublic.spawar.navy.mil/docs/misc/PEO_C4I_NESI_Memo.pdf

---

Re: Every One Speaks about HAARP, but did you know
Post by somamech on Oct 5, 2010, 7:13pm

Thanks Zorg!

That pesky system... Arrgh. When I get time after the weeks break i will show you my own instance of posting a link in an email that had way too many coincindes to be called so.

I don't mind posting DSTO links though... USA gets way too much attention... and lets face it, a good idea is as simple as placing some magnets and concrete together ala Ed. It does not need wads of cash thrown at it. Heck any country can come up with THE right idea

---

Re: Every One Speaks about HAARP, but did you know
Post by gigas on Oct 5, 2010, 8:30pm

Oct 5, 2010, 6:34pm, zorgon wrote:

> One thing I need to mention....
>
> Normally I will NEVER post a direct link to a file at a .mil site...
>
> Why?
>
> 1) Many cannot get access from overseas
> 2) Many .mil sites that I visit require a certificate acceptance, which means you give them permission to monitor you. Some are several levels deep. This scares off the looky loos
> 3) Some ,mil sites like Maxwell AFB Archives will 'ping' back on the IP... happened once at ATS... everyone simply opening the page on that thread with the direct link got a warning pop up... I believe that contributed to ATS getting the rep of being government owned
> 4) This is the most important FILES GET MOVED because of the sudden traffic

Who knew, cept master zorgon. Ok my friend, the lesson has surely been learned and in the future, I will follow your proven advice and keep dot mil links on the low.

Thanks again exalted one for sharing that important bit of information on dot mil. We have seen it in action and know it to be true.

Now, all hail zorgon.

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Oct 5, 2010, 8:38pm

Oct 5, 2010, 6:02pm, winniethepooh4102 wrote:

> The ELF cannot conquer the Elves.

I hope not I like Elves... have a few myself

Re: Every One Speaks about HAARP, but did you know
Post by winniethepooh4102 on Oct 6, 2010, 7:38am

Observing those very strange clouds and chemtrails
in the sky above me I'm inclined to believe, as though
the atmosphere is growing wiser and overripe. Do you
admit the claims about the HAARP and the elves?

P.S. I meant exactly this and some claims surrounding it:

http://www.educate-yourself.org/cn/sylphandchemtrailindex.shtml

http://educate-yourself.org/zsl/sylphessayindex.shtml

If the elves and the sylphs really exist they have to
be in one category. Considering the UFO problem
every possible information has to be processed.

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Oct 7, 2010, 9:00am

Elves and Sprites Play above huge thunderstorms


100
IONOSPHERE
ELVE
(Expanding Disk)
SPRITE
MESOSPHERE
Tendrils
ALTITUDE (km)
50
STRATOSPHERE
BLUE JET
Upward
Superbolt
(To Be
Confirmed)
Stratiform Region
TROPOSPHERE
Negative Cloud-to-Ground
Flash Near Convective Core
Positive Cloud-to-Ground
Flash with "Spider Lightning"
0
100
DISTANCE (km)

The Sylphs on the other hand only reveal themselves to those who can see them. I have a magnificent collections of Dragons... perhaps I may do a thread 😉

Let the pakuas spiral faster and start from 10,000 miles per hour up to 60,000 miles per hour and feel the spine getting bigger and bigger.



Fig. 8.12 *All the Pakuas become a bigger and bigger Pakua spiraling around whole the body.*



They have little to do with HAARP as the Sylphs play in the atmosphere while HAARP messes several miles higher in the ionosphere, home of the Aurora...

The Dragons will come though... all you need to do is ask them to appear

---

Re: Every One Speaks about HAARP, but did you know
Post by winniethepooh4102 on Oct 7, 2010, 11:21am

I would leave the theme in this ouroboros style
not knowing how exactly the matrix is structured.
Anyway those creatures from under the ground
and under the water flying also everywhere in
the air and into the space cannot be unknown
for The Big Brother. The question is why they are
so big secret and what is their relation to us
indepedently of those massive space ships
and the ETs.

Re: Every One Speaks about HAARP, but did you know
Post by dragar on Nov 4, 2010, 5:51pm

Naughty! Naughty! Hotlinking of images is prohibited



The AN/FLR-9, operated by the Air Intelligence Agency, is part of the DOD World Wide High Frequency Direction Finding System. High-frequency radio communication signals travel to receivers over the horizon by bouncing off the ionosphere. The shell of ionised particles which surrounds the earth refracts the signals so that they return to earth rather than disappear out into space. The clarity of the signal received depends on atmospheric and topographical conditions. HF-DF stations detect radio signals from aircraft or ships, and calculate the direction, or line of bearing, of the radio transmitter from the direction finding antenna. When the same signal is received by two or more antennae, the intersection of the lines of bearing mark the transmitter's location, using either precision single station location (SSL) capability, or in a network of DF stations using both multi-station azimuth triangulation and SSL. High Frequency Acquisition (AQ) and Direction Finding (DF) operations are performed with the Narrowband System (NBS) and Wideband Direction Finding (WBDF) Subsystem in support of normal and degraded communications modes, using both adaptive reception and super-resolution direction finding techniques.

Re: Every One Speaks about HAARP, but did you know
Post by ivalen on Nov 9, 2010, 7:50pm

Sept 21, 2010, 7:03pm, zorgon wrote:

http://www.thelivingmoon.com/45jack_file....r_Facility.html

Cherenkov Radiation around Antennas



Image courtesy ISRO

http://en.wikipedia.org/wiki/Cherenkov_radiation

> Cherenkov radiation (also spelled Cerenkov or Čerenkov) is electromagnetic radiation emitted when a charged particle (such as an electron) passes through an insulator at a constant speed greater than the speed of light in that medium. The charged particles polarize the molecules of that medium, which then turn back rapidly to their ground state, emitting radiation in the process.

For this to be the case in the above photograph - what is the insulating medium?

Re: Every One Speaks about HAARP, but did you know
Post by sarentack on Nov 11, 2010, 4:10am

one would think some of these facilities was like ginormous computer chip.

or signals or landmarks for ET like that Triangle look from above.

Wonder if their any relation to what we see in Peru?

Re: Every One Speaks about HAARP, but did you know
Post by somamech on Dec 5, 2010, 5:26pm

Hey HAARP is old news to the mountain people

The uncanny resemblance to a mil array

^compare that...

To this:

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Dec 7, 2010, 8:55am

Nov 9, 2010, 7:50pm, ivalen wrote:

> For this to be the case in the above photograph - what is the insulating medium?

Good question... I might have said 'plasma' but that would require even more explanation. I do need to pinpoint exactly what these glows are... related to another glowing object on the Moon

St. Elmo's fire (also St. Elmo's light) is an electrical weather phenomenon in which luminous plasma is created by a coronal discharge originating from a grounded object in an atmospheric electric field

Physically, St. Elmo's fire is a bright blue or violet glow, appearing like fire in some circumstances, from tall, sharply pointed structures

Working on it

Re: Every One Speaks about HAARP, but did you know
Post by zorgon on Dec 7, 2010, 9:12am

Nov 4, 2010, 5:51pm, dragar wrote:



We have one of those in Japan too

Misawa, Japan
Misawa NSA Echelon Station
Code Name: Ladylove
+40° 43' 22.91", +141° 19' 43.57"


Antenna Array
+40° 43' 22.91", +141° 19' 43.57"

Quite a NAVY and AF presence there as well as an ECHELON station. We have nukes in storage in that area as well

http://www.thelivingmoon.com/45jack_files/03files/ECHELON_Misawa.html

NAVY INFORMATION OPERATIONS COMMAND MISAWA
NETWARCOM
三沢

Re: Every One Speaks about HAARP, but did you know
Post by zaggan on Dec 7, 2010, 3:31pm

I'm late in the game on this discussion, but it surfaced in June of last year in one of Dan's threads (think Reality 101). Someone had brought up one of the antenna arrays, along with a picture, and I commented back in late June. Dan got snippy and deleted all references to it, but want to add it back in here:

Received a reply to an inquiry to POA Elmendorf AFB, listed as follows:

Good Afternoon Sir,

My name is SrA Xxxxxx Xxxxxxxxx from the 3rd Wing Public Affairs on Elmendorf and I contacting you in regards to the question about the structure you saw on Google Earth.

It is a HF Antenna. If you would like more information you can go to the following link. http://www.fas.org/irp/program/collect/an-flr-9.htm

If you have any other questions, comments or concerns please do not hesitate to contact me at 552-8915 or by email.

Hope this helps!

Thank You and have a nice day!

XXXXXX XXXXXXXXX, SRA, USAF
COMMUNITY RELATIONS

3WG PUBLIC AFFAIRS
DSN: 552-8915 COMM: 552-8915

The link is pretty interesting.

Re: Every One Speaks about HAARP, but did you know
Post by gigas on Dec 7, 2010, 8:22pm

Dec 7, 2010, 9:12am, zorgon wrote:

Nov 4, 2010, 5:51pm, dragar wrote:



We have one of those in Japan too

Misawa, Japan
Misawa NSA Echelon Station
Code Name: Ladylove
+40° 43' 22.91", +141° 19' 43.57"



Looks like they had one back 5,000 years ago in the UK around salisbury called stonehenge as well.

United States Patent [19]
Eastlund

[11] **Patent Number:** **4,686,605**
[45] **Date of Patent:** **Aug. 11, 1987**

[54] **METHOD AND APPARATUS FOR ALTERING A REGION IN THE EARTH'S ATMOSPHERE, IONOSPHERE, AND/OR MAGNETOSPHERE**

[75] Inventor: **Bernard J. Eastlund**, Spring, Tex.

[73] Assignee: **APTI, Inc.**, Los Angeles, Calif.

[21] Appl. No.: **690,333**

[22] Filed: **Jan. 10, 1985**

[51] **Int. Cl.**^{4} **H05B 6/64**; H05C 3/00; H05H 1/46

[52] **U.S. Cl.** .... **361/231**; 89/1.11; 380/59; 244/158 R

[58] **Field of Search** .... 361/230, 231; 244/158 R; 376/100; 89/1.11; 380/59

[56] **References Cited**

PUBLICATIONS

Liberty Magazine, (2/35) p. 7 N. Tesla.
New York Times (9/22/40) Section 2, p. 7 W. L. Laurence.
New York Times (12/8/15) p. 8 Col. 3.

Primary Examiner—Salvatore Cangialosi
Attorney, Agent, or Firm—Roderick W. MacDonald

[57] **ABSTRACT**

A method and apparatus for altering at least one selected region which normally exists above the earth's surface. The region is excited by electron cyclotron resonance heating to thereby increase its charged particle density. In one embodiment, circularly polarized electromagnetic radiation is transmitted upward in a direction substantially parallel to and along a field line which extends through the region of plasma to be altered. The radiation is transmitted at a frequency which excites electron cyclotron resonance to heat and accelerate the charged particles. This increase in energy can cause ionization of neutral particles which are then absorbed as part of the region thereby increasing the charged particle density of the region.

15 Claims, 5 Drawing Figures



FIG. 1


11
NORTH POLE
M_B
10
20
12
15
TRANSMITTER 16
14
C
POWER GENERATOR 17
EQUATOR
13
R
M_B
SOUTH POLE

FIG. 2


R2
M_B1
[F=-μ•∇B]
R1

FIG. 3


[F = -μ • ∇B]
R2
11
θ
i
e
i
i
12
i
n
i
R1
e
n
i
10

FIG. 4


30
R3
11
12
f3
33
20
15
31
10
32



Fig. 8.13 *The spirals of the Pakua form and become a very big kua and form a space ship up to 50 meters in diameter or bigger.*


TREATER
MHD GENERATOR
TRANSMITTER

FIG. 5

METHOD AND APPARATUS FOR ALTERING A REGION IN THE EARTH'S ATMOSPHERE, IONOSPHERE, AND/OR MAGNETOSPHERE

DESCRIPTION

1. Technical Field

This invention relates to a method and apparatus for altering at least one selected region normally existing above the earth's surface and more particularly relates to a method and apparatus for altering said at least one region by initially transmitting electromagnetic radiation from the earth's surface essentially parallel to and along naturally-occurring, divergent magnetic field lines which extend from the earth's surface through the region or regions to be altered.

2. Background Art

In the late 1950's, it was discovered that naturally-occuring belts exist at high altitudes above the earth's surface, and it is now established that these belts result from charged electrons and ions becoming trapped along the magnetic lines of force (field lines) of the earth's essentially dipole magnetic field. The trapped electrons and ions are confined along the field lines between two magnetic mirrors which exist at spaced apart points along those field lines. The trapped electrons and ions move in helical paths around their particular field lines and "bounce" back and forth between the magnetic mirrors. These trapped electrons and ions can oscillate along the field lines for long periods of time.

In the past several years, substantial effort has been made to understand and explain the phenomena involved in belts of trapped electrons and ions, and to explore possible ways to control and use these phenomena for beneficial purposes. For example, in the late 1950's and early 1960's both the United States and U.S.S.R. detonated a series of nuclear devices of various yields to generate large numbers of charged particles at various altitudes, e.g., 200 kilometers (km) or greater. This was done in order to establish and study artifical belts of trapped electrons and ions. These experiments established that at least some of the extraneous electrons and ions from the detonated devices did become trapped along field lines in the earth's magnetosphere to form artificial belts which were stable for prolonged periods of time. For a discussion of these experiments see "The Radiation Belt and Magnetosphere", W. N. Hess, Blaisdell Publishing Co., 1968, pps. 155 et sec.

Other proposals which have been advanced for altering existing belts of trapped electrons and ions and/or establishing similar artificial belts include injecting charged particles from a satellite carrying a payload of radioactive beta-decay material or alpha emitters; and injecting charged particles from a satellite-borne electron accelerator. Still another approach is described in U.S. Pat. No. 4,042,196 wherein a low energy ionized gas, e.g., hydrogen, is released from a synchronous orbiting satellite near the apex of a radiation belt which is naturally-occurring in the earth's magnetosphere to produce a substantial increase in energetic particle precipitation and, under certain conditions, produce a limit in the number of particles that can be stably trapped. This precipitation effect arises from an enhancement of the whistler-mode and ion-cyclotron mode interactions

that result from the ionized gas or "cold plasma" injection.

It has also been proposed to release large clouds of barium in the magnetosphere so that photoionization will increase the cold plasma density, thereby producing electron precipitation through enhanced whistler-mode interactions.

However, in all of the above-mentioned approaches, the mechanisms involved in triggering the change in the trapped particle phenomena must be actually positioned within the affected zone, e.g., the magnetosphere, before they can be actuated to effect the desired change.

The earth's ionosphere is not considered to be a "trapped" belt since there are few trapped particles therein. The term "trapped" herein refers to situations where the force of gravity on the trapped particles is balanced by magnetic forces rather than hydrostatic or collisional forces. The charged electrons and ions in the ionosphere also follow helical paths around magnetic field lines within the ionosphere but are not trapped between mirrors, as in the case of the trapped belts in the magnetosphere, since the gravitational force on the particles is balanced by collisional or hydrostatic forces.

In recent years, a number of experiments have actually been carried out to modify the ionosphere in some controlled manner to investigate the possibility of a beneficial result. For detailed discussions of these operations see the following papers: (1) Ionospheric Modification Theory; G. Meltz and F. W. Perkins; (2) The Platteville High Power Facility; Carrol et al.; (3) Arecibo Heating Experiments; W. E. Gordon and H. C. Carlson, Jr.; and (4) Ionospheric Heating by Powerful Radio Waves; Meltz et al., all published in Radio Science, Vol. 9, No. 11, November, 1974, at pages 885–888; 889–894; 1041–1047; and 1049–1063, respectively, all of which are incorporated herein by reference. In such experiments, certain regions of the ionosphere are heated to change the electron density and temperature within these regions. This is accomplished by transmitting from earth-based antennae high frequency electromagnetic radiation at a substantial angle to, not parallel to, the ionosphere's magnetic field to heat the ionospheric particles primarily by ohmic heating. The electron temperature of the ionosphere has been raised by hundreds of degrees in these experiments, and electrons with several electron volts of energy have been produced in numbers sufficient to enhance airglow. Electron concentrations have been reduced by a few percent, due to expansion of the plasma as a result of increased temperature.

In the Elmo Bumpy Torus (EBT), a controlled fusion device at the Oak Ridge National Laboratory, all heating is provided by microwaves at the electron cyclotron resonance interaction. A ring of hot electrons is formed at the earth's surface in the magnetic mirror by a combination of electron cyclotron resonance and stochastic heating. In the EBT, the ring electrons are produced with an average "temperature" of 250 kilo electron volts or kev (2.5×10^9K) and a plasma beta between 0.1 and 0.4; see, "A Theoretical Study of Electron—Cyclotron Absorption in Elmo Bumpy Torus", Batchelor and Goldfinger, Nuclear Fusion, Vol. 20, No. 4 (1980) pps. 403–418.

Electron cyclotron resonance heating has been used in experiments on the earth's surface to produce and accelerate plasmas in a diverging magnetic field. Kosmahl et al. showed that power was transferred from the electromagnetic waves and that a fully ionized plasma

was accelerated with a divergence angle of roughly 13 degrees. Optimum neutral gas density was 1.7×10^{14}per cubic centimeter; see, "Plasma Acceleration with Microwaves Near Cyclotron Resonance", Kosmahl et al., Journal of Applied Physics, Vol. 38, No. 12, Nov., 1967, pps. 4576–4582.

DISCLOSURE OF THE INVENTION

The present invention provides a method and apparatus for altering at least one selected region which normally exists above the earth's surface. The region is excited by electron cyclotron resonance heating of electrons which are already present and/or artifically created in the region to thereby increase the charged particle energy and ultimately the density of the region.

In one embodiment this is done by transmitting circularly polarized electromagnetic radiation from the earth's surface at or near the location where a naturally-occurring dipole magnetic field (force) line intersects the earth's surface. Right hand circular polarization is used in the northern hemisphere and left hand circular polarization is used in the southern hemisphere. The radiation is deliberately transmitted at the outset in a direction substantially parallel to and along a field line which extends upwardly through the region to be altered. The radiation is transmitted at a frequency which is based on the gyrofrequency of the charged particles and which, when applied to the at least one region, excites electron cyclotron resonance within the region or regions to heat and accelerate the charged particles in their respective helical paths around and along the field line. Sufficient energy is employed to cause ionization of neutral particles (molecules of oxygen, nitrogen and the like, particulates, etc.) which then become a part of the region thereby increasing the charged particle density of the region. This effect can further be enhanced by providing artificial particles, e.g., electrons, ions, etc., directly into the region to be affected from a rocket, satellite, or the like to supplement the particles in the naturally-occurring plasma. These artificial particles are also ionized by the transmitted electromagnetic radiation thereby increasing charged particle density of the resulting plasma in the region.

In another embodiment of the invention, electron cyclotron resonance heating is carried out in the selected region or regions at sufficient power levels to allow a plasma present in the region to generate a mirror force which forces the charged electrons of the altered plasma upward along the force line to an altitude which is higher than the original altitude. In this case the relevant mirror points are at the base of the altered region or regions. The charged electrons drag ions with them as well as other particles that may be present. Sufficient power, e.g., 10^{15}joules, can be applied so that the altered plasma can be trapped on the field line between mirror points and will oscillate in space for prolonged periods of time. By this embodiment, a plume of altered plasma can be established at selected locations for communication modification or other purposes.

In another embodiment, this invention is used to alter at least one selected region of plasma in the ionosphere to establish a defined layer of plasma having an increased charged particle density. Once this layer is established, and while maintaining the transmission of the main beam of circularly polarized electromagnetic radiation, the main beam is modulated and/or at least one second different, modulated electromagnetic radiation beam is transmitted from at least one separate source at a different frequency which will be absorbed in the plasma layer. The amplitude of the frequency of the main beam and/or the second beam or beams is modulated in resonance with at least one known oscillation mode in the selected region or regions to excite the known oscillation mode to propagate a known frequency wave or waves throughout the ionosphere.

BRIEF DESCRIPTION OF THE DRAWINGS

The actual construction, operation, and apparent advantages of this invention will be better understood by referring to the drawings in which like numerals identify like parts and in which:

FIG. **1** is a simplified schematical view of the earth (not to scale) with a magnetic field (force) line along which the present invention is carried out;

FIG. **2** is one embodiment within the present invention in which a selected region of plasma is raised to a higher altitude;

FIG. **3** is a simplified, idealized representation of a physical phenomenon involved in the present invention; and

FIG. **4** is a schematic view of another embodiment within the present invention.

FIG. **5** is a schematic view of an apparatus embodiment within this invention.

BEST MODES FOR CARRYING OUT THE INVENTION

The earth's magnetic field is somewhat analogous to a dipole bar magnet. As such, the earth's magnetic field contains numerous divergent field or force lines, each line intersecting the earth's surface at points on opposite sides of the Equator. The field lines which intersect the earth's surface near the poles have apexes which lie at the furthest points in the earth's magnetosphere while those closest to the Equator have apexes which reach only the lower portion of the magnetosphere.

At various altitudes above the earth's surface, e.g., in both the ionosphere and the magnetosphere, plasma is naturally present along these field lines. This plasma consists of equal numbers of positively and negatively charged particles (i.e., electrons and ions) which are guided by the field line. It is well established that a charged particle in a magnetic field gyrates about field lines, the center of gyration at any instance being called the "guiding center" of the particle. As the gyrating particle moves along a field line in a uniform field, it will follow a helical path about its guiding center, hence linear motion, and will remain on the field line. Electrons and ions both follow helical paths around a field line but rotate in opposite directions. The frequencies at which the electrons and ions rotate about the field line are called gyromagnetic frequencies or cyclotron frequencies because they are identical with the expression for the angular frequencies of gyration of particles in a cyclotron. The cyclotron frequency of ions in a given magnetic field is less than that of electrons, in inverse proportion to their masses.

If the particles which form the plasma along the earth's field lines continued to move with a constant pitch angle, often designated "alpha", they would soon impact on the earth's surface. Pitch angle alpha is defined as the angle between the direction of the earth's magnetic field and the velocity (V) of the particle. However, in converging force fields, the pitch angle does change in such a way as to allow the particle to

turn around and avoid impact. Consider a particle moving along a field line down toward the earth. It moves into a region of increasing magnetic field strength and therefore sine alpha increases. But sine alpha can only increase to 1.0, at which point, the particle turns around and starts moving up along the field line, and alpha decreases. The point at which the particle turns around is called the mirror point, and there alpha equals ninety degrees. This process is repeated at the other end of the field line where the same magnetic field strength value B, namely Bm, exists. The particle again turns around and this is called the "conjugate point" of the original mirror point. The particle is therefore trapped and bounces between the two magnetic mirrors. The particle can continue oscillating in space in this manner for long periods of time. The actual place where a particle will mirror can be calculated from the following:

$$\sin^2 \mathrm{alpha}_o = B_o/B_m \quad (1)$$

wherein:

alpha_o = equatorial pitch angle of particle

B_o = equatorial field strength on a particular field line

B_m = field strength at the mirror point

Recent discoveries have established that there are substantial regions of naturally trapped particles in space which are commonly called "trapped radiation belts". These belts occur at altitudes greater than about 500 km and accordingly lie in the magnetosphere and mostly above the ionosphere.

The ionosphere, while it may overlap some of the trapped-particle belts, is a region in which hydrostatic forces govern its particle distribution in the gravitational field. Particle motion within the ionosphere is governed by both hydrodynamic and electrodynamic forces. While there are few trapped particles in the ionosphere, nevertheless, plasma is present along field lines in the ionosphere. The charged particles which form this plasma move between collisions with other particles along similar helical paths around the field lines and although a particular particle may diffuse downward into the earth's lower atmosphere or lose energy and diverge from its original field line due to collisions with other particles, these charged particles are normally replaced by other available charged particles or by particles that are ionized by collision with said particle. The electron density (N_e) of the plasma will vary with the actual conditions and locations involved. Also, neutral particles, ions, and electrons are present in proximity to the field lines.

The production of enhanced ionization will also alter the distribution of atomic and molecular constituents of the atmosphere, most notably through increased atomic nitrogen concentration. The upper atmosphere is normally rich in atomic oxygen (the dominant atmospheric constituent above 200 km altitude), but atomic nitrogen is normally relatively rare. This can be expected to manifest itself in increased airglow, among other effects.

As known in plasma physics, the characteristics of a plasma can be altered by adding energy to the charged particles or by ionizing or exciting additional particles to increase the density of the plasma. One way to do this is by heating the plasma which can be accomplished in different ways, e.g., ohmic, magnetic compression, shock waves, magnetic pumping, electron cyclotron resonance, and the like.

Since electron cyclotron resonance heating is involved in the present invention, a brief discussion of same is in order. Increasing the energy of electrons in a plasma by invoking electron cyclotron resonance heating, is based on a principle similar to that utilized to accelerate charged particles in a cyclotron. If a plasma is confined by a static axial magnetic field of strength B, the charged particles will gyrate about the lines of force with a frequency given, in hertz, as $f_g = 1.54 \times 10^3 B/A$, where: B = magnetic field strength in gauss, and A = mass number of the ion.

Suppose a time-varying field of this frequency is superimposed on the static field B confining the plasma, by passage of a radiofrequency current through a coil which is concentric with that producing the axial field, then in each half-cycle of their rotation about the field lines, the charged particles acquire energy from the oscillating electric field associated with the radio frequency. For example, if B is 10,000 gauss, the frequency of the field which is in resonance with protons in a plasma is 15.4 megahertz.

As applied to electrons, electron cyclotron resonance heating requires an oscillating field having a definite frequency determined by the strength of the confining field. The radio-frequency radiation produces time-varying fields (electric and magnetic), and the electric field accelerates the charged particle. The energized electrons share their energy with ions and neutrals by undergoing collisions with these particles, thereby effectively raising the temperature of the electrons, ions, and neutrals. The apportionment of energy among these species is determined by collision frequencies. For a more detailed understanding of the physics involved, see "Controlled Thermonuclear Reactions", Glasstone and Lovberg, D. Van Nostrand Company, Inc., Princeton, N.J., 1960 and "The Radiation Belt and Magnetosphere", Hess, Blaisdell Publishing Company, 1968, both of which are incorporated herein by reference.

Referring now to the drawings, the present invention provides a method and apparatus for altering at least one region of plasma which lies along a field line, particularly when it passes through the ionosphere and/or magnetosphere. FIG. **1** is a simplified illustration of the earth **10** and one of its dipole magnetic force or field lines **11**. As will be understood, line **11** may be any one of the numerous naturally existing field lines and the actual geographical locations **13** and **14** of line **11** will be chosen based on a particular operation to be carried out. The actual locations at which field lines intersect the earth's surface is documented and is readily ascertainable by those skilled in the art.

Line **11** passes through region R which lies at an altitude above the earth's surface. A wide range of altitudes are useful given the power that can be employed by the practice of this invention. The electron cyclotron resonance heating effect can be made to act on electrons anywhere above the surface of the earth. These electrons may be already present in the atmosphere, ionosphere, and/or magnetosphere of the earth, or can be artificially generated by a variety of means such as x-ray beams, charged particle beams, lasers, the plasma sheath surrounding an object such as a missile or meteor, and the like. Further, artificial particles, e.g., electrons, ions, etc., can be injected directly into region R from an earth-launched rocket or orbiting satellite carrying, for example, a payload of radioactive beta-decay material; alpha emitters; an electron accelerator; and/or ionized gases such as hydrogen; see U.S. Pat. No. 4,042,196. The altitude can be greater than about 50 km if desired,

e.g., can be from about 50 km to about 800 km, and, accordingly may lie in either the ionosphere or the magnetosphere or both. As explained above, plasma will be present along line **11** within region R and is represented by the helical line **12**. Plasma **12** is comprised of charged particles (i.e., electrons and ions) which rotate about opposing helical paths along line **11**.

Antenna **15** is positioned as close as is practical to the location **14** where line **11** intersects the earth's surface. Antenna **15** may be of any known construction for high directionality, for example, a phased array, beam spread angle (θ) type. See "The MST Radar at Poker Flat, Alaska", Radio Science, Vol. 15, No. 2, Mar.-Apr. 1980, pps. 213–223, which is incorporated herein by reference. Antenna **15** is coupled to transmitter **16** which generates a beam of high frequency electromagnetic radiation at a wide range of discrete frequencies, e.g., from about 20 to about 1800 kilohertz (kHz).

Transmitter **16** is powered by power generator means **17** which is preferably comprised of one or more large, commercial electrical generators. Some embodiments of the present invention require large amounts of power, e.g., up to 10^9 to 10^{11} watts, in continuous wave or pulsed power. Generation of the needed power is within the state of the art. Although the electrical generators necessary for the practice of the invention can be powered in any known manner, for example, by nuclear reactors, hydroelectric facilities, hydrocarbon fuels, and the like, this invention, because of its very large power requirement in certain applications, is particularly adapted for use with certain types of fuel sources which naturally occur at strategic geographical locations around the earth. For example, large reserves of hydrocarbons (oil and natural gas) exist in Alaska and Canada. In northern Alaska, particularly the North Slope region, large reserves are currently readily available. Alaska and northern Canada also are ideally located geographically as to magnetic latitudes. Alaska provides easy access to magnetic field lines that are especially suited to the practice of this invention, since many field lines which extend to desirable altitudes for this invention intersect the earth in Alaska. Thus, in Alaska, there is a unique combination of large, accessible fuel sources at desirable field line intersections. Further, a particularly desirable fuel source for the generation of very large amounts of electricity is present in Alaska in abundance, this source being natural gas. The presence of very large amounts of clean-burning natural gas in Alaskan latitudes, particularly on the North Slope, and the availability of magnetohydrodynamic (MHD), gas turbine, fuel cell, electrogasdynamic (EGD) electric generators which operate very efficiently with natural gas provide an ideal power source for the unprecedented power requirements of certain of the applications of this invention. For a more detailed discussion of the various means for generating electricity from hydrocarbon fuels, see "Electrical Aspects of Combustion", Lawton and Weinberg, Clarendon Press, 1969. For example, it is possible to generate the electricity directly at the high frequency needed to drive the antenna system. To do this, typically the velocity of flow of the combustion gases (v), past magnetic field perturbation of dimension d (in the case of MHD), follow the rule:

$$v = df$$

where f is the frequency at which electricity is generated. Thus, if $v = 1.78 \times 10^6$ cm/sec and d=1 cm then electricity would be generated at a frequency of 1.78 mHz.

Put another way, in Alaska, the right type of fuel (natural gas) is naturally present in large amounts and at just the right magnetic latitudes for the most efficient practice of this invention, a truly unique combination of circumstances. Desirable magnetic latitudes for the practice of this invention interest the earth's surface both northerly and southerly of the equator, particularly desirable latitudes being those, both northerly and southerly, which correspond in magnitude with the magnetic latitudes that encompass Alaska.

Referring now to FIG. 2 a first ambodiment is illustrated where a selected region R_1 of plasma **12** is altered by electron cyclotron resonance heating to accelerate the electrons of plasma **12**, which are following helical paths along field line **11**.

To accomplish this result, electromagnetic radiation is transmitted at the outset, essentially parallel to line **11** via antenna **15** as right hand circularly polarized radiation wave **20**. Wave **20** has a frequency which will excite electron cyclotron resonance with plasma **12** at its initial or original altitude. This frequency will vary depending on the electron cyclotron resonance of region R_1 which, in turn, can be determined from available data based on the altitudes of region R_1, the particular field line **11** being used, the strength of the earth's magnetic field, etc. Frequencies of from about 20 to about 7200 kHz, preferably from about 20 to about 1800 kHz can be employed. Also, for any given application, there will be a threshhold (minimum power level) which is needed to produce the desired result. The minimum power level is a function of the level of plasma production and movement required, taking into consideration any loss processes that may be dominant in a particular plasma or propagation path.

As electron cyclotron resonance is established in plasma **12**, energy is transferred from the electromagnetic radiation **20** into plasma **12** to heat and accelerate the electrons therein and, subsequently, ions and neutral particles. As this process continues, neutral particles which are present within R_1 are ionized and absorbed into plasma **12** and this increases the electron and ion densities of plasma **12**. As the electron energy is raised to values of about 1 kilo electron volt (kev), the generated mirror force (explained below) will direct the excited plasma **12** upward along line **11** to form a plume R_2 at an altitude higher than that of R_1.

Plasma acceleration results from the force on an electron produced by a nonuniform static magnetic field ($\overline{B}$). The force, called the mirror force, is given by

$$F = -\mu \nabla B \qquad (2)$$

where μ is the electron magnetic moment and $\nabla \overline{B}$ is the gradient of the magnetic field, μ being further defined as:

$$W_\perp / B = mV_\perp^2 / 2B$$

where $W_\perp$ is the kinetic energy in the direction perpendicular to that of the magnetic field lines and B is the magnetic field strength at the line of force on which the guiding center of the particle is located. The force as represented by equation (2) is the force which is responsible for a particle obeying equation (1).

Since the magnetic field is divergent in region R_1, it can be shown that the plasma will move upwardly from the heating region as shown in FIG. **1** and further it can be shown that

$$\tfrac{1}{2}M_eV_{e\perp}^2(x) \approx \tfrac{1}{2}M_eV_{e\perp}^2(Y) + \tfrac{1}{2}M_iV_{i\parallel}^2(Y) \quad (3)$$

where the left hand side is the initial electron transverse kinetic energy; the first term on the right is the transverse electron kinetic energy at some point (Y) in the expanded field region, while the final term is the ion kinetic energy parallel to B at point (Y). This last term is what constitutes the desired ion flow. It is produced by an electrostatic field set up by electrons which are accelerated according to Equation (2) in the divergent field region and pulls ions along with them. Equation (3) ignores electron kinetic energy parallel to B because $V_{e\parallel} \approx V_{i\parallel}$, so the bulk of parallel kinetic energy resides in the ions because of their greater masses. For example, if an electromagnetic energy flux of from about 1 to about 10 watts per square centimeter is applied to region R, whose altitude is 115 km, a plasma having a density (N_e) of 10^{12} per cubic centimeter will be generated and moved upward to region R_2 which has an altitude of about 1000 km. The movement of electrons in the plasma is due to the mirror force while the ions are moved by ambipolar diffusion (which results from the electrostatic field). This effectively "lifts" a layer of plasma **12** from the ionosphere and/or magnetosphere to a higher elevation R_2. The total energy required to create a plasma with a base area of 3 square kilometers and a height of 1000 km is about 3×10^{13} joules.

FIG. **3** is an idealized representation of movement of plasma **12** upon excitation by electron cyclotron resonance within the earth's divergent force field. Electrons (e) are accelerated to velocities required to generate the necessary mirror force to cause their upward movement. At the same time neutral particles (n) which are present along line **11** in region $R_1$are ionized and become part of plasma **12**. As electrons (e) move upward along line **11**, they drag ions (i) and neutrals (n) with them but at an angle θ of about 13 degrees to field line **11**. Also, any particulates that may be present in region R_1, will be swept upwardly with the plasma. As the charged particles of plasma **12** move upward, other particles such as neutrals within or below R_1, move in to replace the upwardly moving particles. These neutrals, under some conditions, can drag with them charged particles.

For example, as a plasma moves upward, other particles at the same altitude as the plasma move horizontally into the region to replace the rising plasma and to form new plasma. The kinetic energy developed by said other particles as they move horizontally is, for example, on the same order of magnitude as the total zonal kinetic energy of stratospheric winds known to exist.

Referring again to FIG. **2**, plasma **12** in region R_1 is moved upward along field line **11**. The plasma **12** will then form a plume (cross-hatched area in FIG. **2**) which will be relatively stable for prolonged periods of time. The exact period of time will vary widely and be determined by gravitational forces and a combination of radiative and diffusive loss terms. In the previous detailed example, the calculations were based on forming a plume by producing 0+energies of 2 ev/particle. About 10 ev per particle would be required to expand plasma **12** to apex point C (FIG. **1**). There at least some of the particles of plasma **12** will be trapped and will oscillate between mirror points along field line **11**. This oscillation will then allow additional heating of the trapped plasma **12** by stochastic heating which is associated with trapped and oscillating particles. See "A New Mechanism for Accelerating Electrons in the Outer Ionosphere" by R. A. Helliwell and T. F. Bell, Journal of Geophysical Research, Vol. 65, No. 6, June, 1960. This is preferably carried out at an altitude of at least 500 km.

The plasma of the typical example might be employed to modify or disrupt microwave transmissions of satellites. If less than total black-out of transmission is desired (e.g., scrambling by phase shifting digital signals), the density of the plasma (N_e) need only be at least about 10^6 per cubic centimeter for a plasma orginating at an altitude of from about 250 to about 400 km and accordingly less energy (i.e., electromagnetic radiation), e.g., 10^8 joules need be provided. Likewise, if the density $N_e$is on the order of 10^8, a properly positioned plume will provide a reflecting surface for VHF waves and can be used to enhance, interfere with, or otherwise modify communication transmissions. It can be seen from the foregoing that by appropriate application of various aspects of this invention at strategic locations and with adequate power sources, a means and method is provided to cause interference with or even total disruption of communications over a very large portion of the earth. This invention could be employed to disrupt not only land based communications, both civilian and military, but also airborne communications and sea communications (both surface and subsurface). This would have significant military implications, particularly as a barrier to or confusing factor for hostile missiles or airplanes. The belt or belts of enhanced ionization produced by the method and apparatus of this invention, particularly if set up over Northern Alaska and Canada, could be employed as an early warning device, as well as a communications disruption medium. Further, the simple ability to produce such a situation in a practical time period can by itself be a deterring force to hostile action. The ideal combination of suitable field lines intersecting the earth's surface at the point where substantial fuel sources are available for generation of very large quantitities of electromagnetic power, such as the North Slope of Alaska, provides the wherewithal to accomplish the foregoing in a practical time period, e.g., strategic requirements could necessitate achieving the desired altered regions in time periods of two minutes or less and this is achievable with this invention, especially when the combination of natural gas and magnetohydrodynamic, gas turbine, fuel cell and/or EGD electric generators are employed at the point where the useful field lines intersect the earth's surface. One feature of this invention which satisfies a basic requirement of a weapon system, i.e., continuous checking of operability, is that small amounts of power can be generated for operability checking purposes. Further, in the exploitation of this invention, since the main electromagnetic beam which generates the enhanced ionized belt of this invention can be modulated itself and/or one or more additional electromagnetic radiation waves can be impinged on the ionized region formed by this invention as will be described in greater detail herein after with respect to FIG. **4**, a substantial amount of randomly modulated signals of very large power magnitude can be generated in a highly nonlinear mode. This can cause confusion of or interference with or even complete disruption of guidance systems employed by

even the most sophisticated of airplanes and missiles. The ability to employ and transmit over very wide areas of the earth a plurality of electromagnetic waves of varying frequencies and to change same at will in a random manner, provides a unique ability to interfere with all modes of communications, land, sea, and/or air, at the same time. Because of the unique juxtaposition of usable fuel source at the point where desirable field lines intersect the earth's surface, such wide ranging and complete communication interference can be achieved in a resonably short period of time. Because of the mirroring phenomenon discussed hereinabove, it can also be prolonged for substantial time periods so that it would not be a mere transient effect that could simply be waited out by an opposing force. Thus, this invention provides the ability to put unprecedented amounts of power in the earth's atmosphere at strategic locations and to maintain the power injection level, particularly if random pulsing is employed, in a manner far more precise and better controlled than heretofore accomplished by the prior art, particularly by the detonation of nuclear devices of various yeilds at various altitudes. Where the prior art approaches yielded merely transitory effects, the unique combination of fuel and desirable field lines at the point where the fuel occurs allows the establishment of, compared to prior art approaches, precisely controlled and long-lasting effects which cannot, practically speaking, simply be waited out. Further, by knowing the frequencies of the various electromagnetic beams employed in the practice of this invention, it is possible not only to interfere with third party communications but to take advantage of one or more such beams to carry out a communications network even though the rest of the world's communications are disrupted. Put another way, what is used to disrupt another's communications can be employed by one knowledgeable of this invention as a communications network at the same time. In addition, once one's own communication network is established, the far-reaching extent of the effects of this invention could be employed to pick up communication signals of other for intelligence purposes. Thus, it can be seen that the disrupting effects achievable by this invention can be employed to benefit by the party who is practicing this invention since knowledge of the various electromagnetic waves being employed and how they will vary in frequency and magnitude can be used to an advantage for positive communication and eavesdropping purposes at the same time. However, this invention is not limited to locations where the fuel source naturally exists or where desirable field lines naturally intersect the earth's surface. For example, fuel, particularly hydrocarbon fuel, can be transported by pipeline and the like to the location where the invention is to be practiced.

FIG. 4 illustrates another embodiment wherein a selected region of plasma R_3which lies within the earth's ionosphere is altered to increase the density thereof whereby a relatively stable layer **30** of relatively dense plasma is maintained within region R_3. Electromagnetic radiation is transmitted at the outset essentially parallel to field line **11** via antenna **15** as a right hand circularly polarized wave and at a frequency (e.g., 1.78 megahertz when the magnetic field at the desired altitude is 0.66 gauss) capable of exciting electron cyclotron resonance in plasma **12** at the particular altitude of plasma **12**. This causes heating of the particles (electrons, ions, neutrals, and particulates) and ionization of the uncharged particles adjacent line **11**, all of which are absorbed into plasma **12** to increase the density thereof. The power transmitted, e.g., 2×10^6 watts for up to 2 minutes heating time, is less than that required to generate the mirror force F required to move plasma **12** upward as in the previous embodiment.

While continuing to transmit electromagnetic radiation **20** from antenna **15**, a second electromagnetic radiation beam **31**, which is at a defined frequency different from the radiation from antenna **15**, is transmitted from one or more second sources via antenna **32** into layer **30** and is absorbed into a portion of layer **30** (cross-hatched area in FIG. 4). The electromagnetic radiation wave from antenna **32** is amplitude modulated to match a known mode of oscillation f_3 in layer **30**. This creates a resonance in layer **30** which excites a new plasma wave **33** which also has a frequency of f_3 and which then propogates through the ionosphere. Wave **33** can be used to improve or disrupt communications or both depending on what is desired in a particular application. Of course, more than one new wave **33** can be generated and the various new waves can be modulated at will and in a highly nonlinear fashion.

FIG. **5** shows apparatus useful in this invention, particularly when those applications of this invention are employed which require extremely large amounts of power. In FIG. **5** there is shown the earth's surface **40** with a well **41** extending downwardly thereinto until it penetrates hydrocarbon producing reservoir **42**. Hydrocarbon reservoir **42** produces natural gas alone or in combination with crude oil. Hydrocarbons are produced from reservoir **42** through well **41** and wellhead **43** to a treating system **44** by way of pipe **45**. In treater **44**, desirable liquids such as crude oil and gas condensates are separated and recovered by way of pipe **46** while undesirable gases and liquids such as water, H_2S, and the like are separated by way of pipe **47**. Desirable gases such as carbon dioxide are separated by way of pipe **48**, and the remaining natural gas stream is removed from treater **44** by way of pipe **49** for storage in conventional tankage means (not shown) for future use and/or use in an electrical generator such as a magnetohydrodynamic, gas turbine, fuel cell or EGD generator **50**. Any desired number and combination of different types of electric generators can be employed in the practice of this invention. The natural gas is burned in generator **50** to produce substantial quantities of electricity which is then stored and/or passed by way of wire **51** to a transmitter **52** which generates the electromagnetic radiation to be used in the method of this invention. The electromagnetic radiation is then passed by way of wire **53** to antenna **54** which is located at or near the end of field line **11**. Antenna **54** sends circularly polarized radiation wave **20** upwards along field line **11** to carry out the various methods of this invention as described hereinabove.

Of course, the fuel source need not be used in its naturally-occurring state but could first be converted to another second energy source form such as hydrogen, hydrazine and the like, and electricity then generated from said second energy source form.

It can be seen from the foregoing that when desirable field line **11** intersects earth's surface **40** at or near a large naturally-occurring hydrocarbon source **42**, exceedingly large amounts of power can be very efficiently produced and transmitted in the direction of field lines. This is particularly so when the fuel source is natural gas and magnetohydrodynamic generators are employed. Further, this can all be accomplished in a

relatively small physical area when there is the unique coincidence of fuel source **42** and desirable field line **11**. Of course, only one set of equipment is shown in FIG. **5** for sake of simplicity. For a large hydrocarbon reservoir **42**, a plurality of wells **41** can be employed to feed one or more storage means and/or treaters and as large a number of generators **55** as needed to power one or more transmitters **52** and one or more antennas **54**. Since all of the apparatus **44** through **54** can be employed and used essentially at the sight where naturally-occurring fuel source **42** is located, all the necessary electromagnetic radiation **20** is generated essentially at the same location as fuel source **42**. This provides for a maximum amount of usable electromagnetic radiation **20** since there are no significant storage or transportation losses to be incurred. In other words, the apparatus is brought to the sight of the fuel source where desirable field line **11** intersects the earth's surface **40** on or near the geographical location of fuel source **42**, fuel source **42** being at a desirable magnetic latitude for the practice of this invention, for example, Alaska.

The generation of electricity by motion of a conducting fluid through a magnetic field, i.e., magnetohydrodynamics (MHD), provides a method of electric power generation without moving mechanical parts and when the conducting fluid is a plasma formed by combustion of a fuel such as natural gas, an idealized combination of apparatus is realized since the very clean-burning natural gas forms the conducting plasma in an efficient manner and the thus formed plasma, when passed through a magnetic field, generates electricity in a very efficient manner. Thus, the use of fuel source **42** to generate a plasma by combustion thereof for the generation of electricity essentially at the site of occurrence of the fuel source is unique and ideal when high power levels are required and desirable field lines **11** intersect the earth's surface **40** at or near the site of fuel source **42**. A particular advantage for MHD generators is that they can be made to generate large amounts of power with a small volume, light weight device. For example, a 1000 megawatt MHD generator can be construed using superconducting magnets to weigh roughly 42,000 pounds and can be readily air lifted.

This invention has a phenomenal variety of possible ramifications and potential future developments. As alluded to earlier, missile or aircraft destruction, deflection, or confusion could result, particularly when relativistic particles are employed. Also, large regions of the atmosphere could be lifted to an unexpectedly high altitude so that missiles encounter unexpected and unplanned drag forces with resultant destruction or deflection of same. Weather modification is possible by, for example, altering upper atmosphere wind patterns or altering solar absorption patterns by constructing one or more plumes of atmospheric particles which will act as a lens or focusing device. Also as alluded to earlier, molecular modifications of the atmosphere can take place so that positive environmental effects can be achieved. Besides actually changing the molecular composition of an atmospheric region, a particular molecule or molecules can be chosen for increased presence. For example, ozone, nitrogen, etc. concentrations in the atmosphere could be artificially increased. Similarly, environmental enhancement could be achieved by causing the breakup of various chemical entities such as carbon dioxide, carbon monoxide, nitrous oxides, and the like. Transportation of entities can also be realized when advantage is taken of the drag effects caused by regions of the atmosphere moving up along diverging field lines. Small micron sized particles can be then transported, and, under certain circumstances and with the availability of sufficient energy, larger particles or objects could be similarly affected. Particles with desired characteristics such as tackiness, reflectivity, absorptivity, etc., can be transported for specific purposes or effects. For example, a plume of tacky particles could be established to increase the drag on a missile or satellite passing therethrough. Even plumes of plasma having substantially less charged particle density than described above will produce drag effects on missiles which will affect a lightweight (dummy) missile in a manner substantially different than a heavy (live) missile and this affect can be used to distinguish between the two types of missiles. A moving plume could also serve as a means for supplying a space station or for focusing vast amount of sunlight on selected portions of the earth. Surveys of global scope could also be realized because the earth's natural magnetic field could be significantly altered in a controlled manner by plasma beta effects resulting in, for example, improved magnetotelluric surveys. Electromagnetic pulse defenses are also possible. The earth's magnetic field could be decreased or disrupted at appropriate altitudes to modify or eliminate the magnetic field in high Compton electron generation (e.g., from high altitude nuclear bursts) regions. High intensity, well controlled electrical fields can be provided in selected locations for various purposes. For example, the plasma sheath surrounding a missile or satellite could be used as a trigger for activating such a high intensity field to destroy the missile or satellite. Further, irregularities can be created in the ionosphere which will interfere with the normal operation of various types of radar, e.g., synthetic aperture radar. The present invention can also be used to create artificial belts of trapped particles which in turn can be studied to determine the stability of such parties. Still further, plumes in accordance with the present invention can be formed to simulate and/or perform the same functions as performed by the detonation of a "heave" type nuclear device without actually having to detonate such a device. Thus it can be seen that the ramifications are numerous, far-reaching, and exceedingly varied in usefulness.

I claim:

1. A method for altering at least one region normally existing above the earth's surface with electromagnetic radiation using naturally-occurring and diverging magnetic field lines of the earth comprising transmitting first electromagnetic radiation at a frequency between 20 and 7200 kHz from the earth's surface, said transmitting being conducted essentially at the outset of transmission substantially parallel to and along at least one of said field lines, adjusting the frequency of said first radiation to a value which will excite electron cyclotron resonance at an initial elevation at least 50 km above the earth's surface, whereby in the region in which said electron cyclotron resonance takes place heating, further ionization, and movement of both charged and neutral particles is effected, said cyclotron resonance excitation of said region is continued until the electron concentration of said region reaches a value of at least 10^6 per cubic centimeter and has an ion energy of at least 2 ev.

2. The method of claim **1** including the step of providing artificial particles in said at least one region which are excited by said electron cyclotron resonance.

3. The method of claim **2** wherein said artificial particles are provided by injecting same into said at least one region from an orbiting satellite.

4. The method of claim **1** wherein said threshold excitation of electron cyclotron resonance is about 1 watt per cubic centimeter and is sufficient to cause movement of a plasma region along said diverging magnetic field lines to an altitude higher than the altitude at which said excitation was initiated.

5. The method of claim **4** wherein said rising plasma region pulls with it a substantial portion of neutral particles of the atmosphere which exist in or near said plasma region.

6. The method of claim **1** wherein there is provided at least one separate source of second electromagnetic radiation, said second radiation having at least one frequency different from said first radiation, impinging said at least one second radiation on said region while said region is undergoing electron cyclotron resonance excitation caused by said first radiation.

7. The method of claim **6** wherein said second radiation has a frequency which is absorbed by said region.

8. The method of claim **6** wherein said region is plasma in the ionosphere and said second radiation excites plasma waves within said ionosphere.

9. The method of claim **8** wherein said electron concentration reaches a value of at least 10^{12} per cubic centimeter.

10. The method of claim **8** wherein said excitation of electron cyclotron resonance is initially carried out within the ionosphere and is continued for a time sufficient to allow said region to rise above said ionosphere.

11. The method of claim **1** wherein said excitation of electron cyclotron resonance is carried out above about 500 kilometers and for a time of from 0.1 to 1200 seconds such that multiple heating of said plasma region is achieved by means of stochastic heating in the magnetosphere.

12. The method of claim **1** wherein said first electromagnetic radiation is right hand circularly polarized in the northern hemisphere and left hand circularly polarized in the southern hemisphere.

13. The method of claim **1** wherein said electromagnetic radiation is generated at the site of a naturally-occurring hydrocarbon fuel source, said fuel source being located in at least one of northerly or southerly magnetic latitudes.

14. The method of claim **13** wherein said fuel source is natural gas and electricity for generating said electromagnetic radiation is obtained by burning said natural gas in at least one of magnetohydrodynamic, gas turbine, fuel cell, and EGD electric generators located at the site where said natural gas naturally occurs in the earth.

15. The method of claim **14** wherein said site of natural gas is within the magnetic latitudes that encompass Alaska.

* * * * *

HAARP, Earthquakes, and Hurricanes

montalk.net » 13 July 08

Can HAARP manipulate storms, hurricanes, and earthquakes? There is definitely a correlation between these and when HAARP is active. This article will give some examples of that correlation. And while that alone does not prove a direct causal relationship, the physics of HAARP and the political agenda behind the program suggest that weather and earthquake manipulation is both possible and likely.

Background

I assume everyone reading this knows of HAARP. Less known is that HAARP is only one of several such facilities — and not the most powerful one either. There are others, here are five:

1) Mu Radar – 1 megawatt facility in Japan (34°51'14.80"N 136° 6'19.45"E).

2) Arecibo Observatory – 2 megawatt facility in Puerto Rico (18°20'38.97"N 66°45'9.77"W).

3) HIPAS – 70 megawatt facility east of Fairbanks, Alaska (64°52'21.18"N 146°50'18.78"W).

4) Sura – 190 megawatt facility in central Russia (56° 7'10.32"N 46° 2'4.41"E).

5) EISCAT – 1 gigawatt facility in Tromsø, Northern Norway (69°35'1.06"N 19°12'57.11"E).

(you can copy and paste the coordinates into google maps)



Fig. 8.14 *Belt Channels*

DUTCHSINSE = SINCEDUTCH

"Because every dark cloud has a silver IODIDE lining..."

Want to know about Chemtrails, HAARP , VLF, UHF and weather modification? Want to prove it to a non-believer? Here you go!

Posted on October 4, 2011



These links below are for anyone still "on the fence" about weather modification / manipulation — also called Geo-engineering.

The process is simple.. globally, a project has been underway to spray particulate matter (aluminum dioxide, barium etc..) via aerosol distribution on airplanes. The small particles of aluminum and barium serve as a "blank slate" or a "palette" for weather modification ***frequency devices*** to use and manipulate the climate / weather of the planet.

Imagine it as such.. the aluminum and barium act as an ANTENNA that reaches EVERYWHERE that air reaches... this "loaded air" can be "heated" at any given point on the planet via ground and space based systems which basically act like a common household microwave (done via dishes, arrays, and other devices listed below).

There is another set of frequencies.. ULF.. "ultra low frequencies" which can cause earthquakes, and even COOL DOWN the atmosphere. Both types of frequencies, high/low are used to manipulate the natural environment.

The links below prove this 100%.

==

all links below should satisfy MOST questions: save the pdf's before they're gone for good from the net!

A few of the HAARP patents:

http://www.scribd.com/doc/26517997/Us-Patent-Harrp-5041834#fullscreen:on

http://www.freepatentsonline.com/4686605.pdf

http://www.freepatentsonline.com/4712155.pdf

http://www.freepatentsonline.com/5038664.pdf

-

download the Airforce "owning the weather by 2025 document from the military website here:

http://csat.au.af.mil/2025/volume3/vol3ch15.pdf

http://csat.au.af.mil/2025/concepts/11ta_ndx.htm

-

US laws regarding weather modification:

http://www.scribd.com/doc/12896975/US-Law-Weather-Modification-Experimenting

http://uscode.house.gov/download/pls/15C9A.txt

-

more military sites covering HAARP:

http://www.navy.mil/search/display.asp?story_id=21914

http://oai.dtic.mil/oai/oai?verb=getRecord&metadataPrefix=html&identifier=ADA134923

-

US Navy involved:

Follow

http://presscore.ca/2011/?p=1610

Follow

Follow

the USGS seeding the clouds to make it snow:

http://water.usgs.gov/wrri/09grants/progress/2009WY46B.pdf

A few of the weather modification COMPANIES in operation today inside the USA:

http://www.wtwma.com

http://www.weathermodification.com

http://www.weathermodification.org/

http://www.just-clouds.com/

****

This below is a cloud seeding generator:

Follow

North American Weather
Consultants, Inc.

Here is a very long list of links, pdf files from institutions like stanford, leicester university, cornell, University of Mass., etc.. and from several military and .gov sites.

they are easy to read.. yes there is a lot of math formula — you can read the thesis etc, and get a VERY good idea of the topic and what is being covered.

Even the average non-science minded person can understand these documents in their basic form.

some links work, others are "down" but still included to prove they DID exist. These things have a way of disappearing off the net, so download them and MIRROR them on other file sharing sites if you can.

****

University of Leicester — Ionospheric Heating

http://replay.waybackmachine.org/19980211033937/http://ion.le.ac.uk/index.html

http://replay.waybackmachine.org/19980211032156/http://ion.le.ac.uk/heating/Heating.html

Follow

precipitation "enhancement"

http://www.asr.ucar.edu/2004/RAP/precipitation-enhancement.htm

Defense Secretary from the 1990's William Cohen speaking on the subject of HAARP –

http://www.defense.gov/Transcripts/Transcript.aspx?TranscriptID=674

the USGS EAARL:

http://ngom.usgs.gov/dsp/tech/eaarl/

ocean based haarp Buoy:

http://www-star.stanford.edu/~vlf/buoy/

electronic warfare :

http://www.onr.navy.mil/~/media/Files/Funding-Announcements/BAA/2011/11-006.ashx

lower ionosphere heating:

http://www-star.stanford.edu/~vlf/publications/2008-03.pdf

AWESOME network:

http://nova.stanford.edu/~vlf/IHY_Test/pmwiki/pmwiki.php?n=Transmitters.Transmitters
(several years up to 2007)

http://vlf-alexandria.stanford.edu/live_spec_secure/chistochina/live_from_chistochina.html

http://replay.waybackmachine.org/20061229014910/http://ion.le.ac.uk/heating/history_of_rf_heating.html

http://replay.waybackmachine.org/20061229011401/http://ion.le.ac.uk/heating/6Feb.html

Sura Ionospheric Heating Facility
http://en.wikipedia.org/wiki/Sura_Ionospheric_Heating_Facility

The EISCAT Associates
(A lot of info on this site, captured from the late 90's)

http://replay.waybackmachine.org/19980210065153/http://seldon.eiscat.no/eiscat.html

France, Finland, Germany, Japan, Norway, Sweden, UK
*Incoherent scatter radars
(Below)

*Ionospheric Heating

Follow

Their Facility -
http://replay.waybackmachine.org/19980210071758/http://seldon.eiscat.no/heater.html

EISCAT Headquarters are located at Kiruna in Sweden
The EISCAT Scientific Association,
Headquarters,
PO Box 812,
S-981 28 KIRUNA
Sweden

Incoherent Scatter Facilities
Operational Incoherent Scatter Radars

North American Weather
Consultants, Inc.

Jicamarca, Peru
http://jicamarca.ece.cornell.edu/

Arecibo, Puerto Rico
http://replay.waybackmachine.org/19961105195521/http:/naic.edu/
(click on a Layman's guide for info on "probing the ionosphere" and "modifiying the ionosphere locally"
Millstone Hill, USA
(Haystack)
http://replay.waybackmachine.org/19970710073509/http://www.haystack.edu/homepage.html

Follow

Pic of Haystack facility and more info:
http://replay.waybackmachine.org/19990116225557/http://www.haystack.edu/haystack/haystack.html

Sondrestromfjord, Greenland
http://replay.waybackmachine.org/19990224220742/http://128.18.44.75/iono/issfsond.html

EISCAT, Norway/Sweden/Finland
(Main EISCAT Site)
EISCAT Svalbard Radar, Svalbard (First operations late in 1995)

http://replay.waybackmachine.org/19961117043355/http://seldon.eiscat.no/ESR_intro.html

Kharkov, Ukraine
http://www-radiophys.univer.kharkov.ua/space/
(search for scatter)

Irkutsk, Russia
The Institute possesses a complex of unique astrophysical equipment deployed in the Sayan Mountains, especially the Siberian solar radiotelescope, a large solar vacuum telescope, an incoherent scatter radar, as well as a network of astrophysical laboratories throughout the territory of Siberia.

http://www.irkutsk.org/acad/acad_e.htm

http://ursi.org/Proceedings/ProcGA05/pdf/GP2.3%280511%29.pdf


BASE
REFLECTIVITY
OKX
08/17/03 1115Z
RANGE: 230 KM
RES: 1 KM X 1 DEGREE
MODE: CLEAR AIR
ELEV: 0.5 DEGREES
DBZ
ND 0
-28 + 4
-24 + 8
-20 +12
-16 +16
-12 +20
- 8 +24
- 4 +28
0
MAX DBZ. 60

Upper Ionosphere changes HF (high frequency) into ULF (ultra low frequency)

Follow

here is a video explanation of the documents:


PDF Complete Special Edition
File Edit View Help
125%
Great offers on PDF Products
HAARP ELF-VLF Analysis.pdf
Bookmarks
Pages
Search
1 of 4

Efficiency Scaling for Ionospheric ELF/VLF Generation

K. Papadopoulos[1,2], T. Wallace[1], M. McCarrick[1],
G. Milikh[2], P. Kossey[3] and E. Kennedy[4]

Advanced Power Technologies Inc[1]
University of Maryland[2]
Physics Department
College Park, MD 20742
E-mail: kp@astro.umd.edu
Air Force Research Laboratory, VSBI[3]
US Naval Research Laboratory[4]

Abstract: Using experimental measurements and theoretical analysis, it is shown that the HF/ELF conversion efficiency is controlled by the timescale for electron temperature saturation. This is a function of the heater ERP and frequency and the ionospheric electron density profile. For the current HAARP parameters this corresponds to frequencies between 2 and 4 kHz. Efficiency optimization techniques as applied to the projected upgrading of the HAARP heater to its design power of 3.6 MW are discussed.

A most fascinating and important property of the active ionosphere is its potential to act as a frequency transformer that converts HF power injected from a high power HF transmitter into the ionosphere, into coherent lower frequency VLF/ELF/ULF waves. The conversion principle relies on modulating the electrojet currents in the ionospheric D and E regions by using amplitude modulated HF heating. The low frequency fields subsequently couple to the earth-ionosphere waveguide, while a fraction of their power upwards towards the magnetosphere. Despite several years of theoretical and experimental work, many scientific and technical issues remain unresolved. Understanding the physics underlying the low frequency wave generation is important in increasing the HF to ELF conversion efficiency and utilizing the

In essence.. this shows that “they” can send a HF (high frequency) signal into the upper ionosphere with HAARP, and it “transforms” into a ULF ultra low frequency… and vice versa.. a LOW frequency modulates into the HIGH frequency!

here is the link to the “Efficiency scaling” HF transformation into ULF/VLF/ELF via the ionosphere.

http://www.ursi.org/Proceedings/ProcGA02/papers/p0936.pdf

here is the link to the “HAARP description pdf” I am showing…

http://foia.abovetopsecret.com/ultimate_UFO/Advanced/HAARPResearchAndApplicat…

MU, Japan

Follow

Summary

Procedure of Forming the Belt Channels

Ascending from the Pakuas

1. Practice the Inner Smile from the compassion fire, chanting from pakua, forming the collection points, fusing the energy into a pearl, and the Creation Cycle of Cosmic Fusion.
2. Send energy through the three Thrusting Channels all the way down to the feet and up to the head.
3. Form the four pakuas and a pearl. Gather the pearl at the cauldron, and bring it to the navel.
4. Join the four pakuas by circulating the pearl from the ***Navel*** counterclockwise to the Door of Life and back to the navel. Continue circling the pearl nine times around the Thrusthing Channels and around the body counterclockwise.
5. Form a cross. Bring the pearl from the navel to the cauldron, and back to the Door of Life. Use it to connect the side pakuas. Return the pearl to the navel.
6. From navel move to the left side of the ***Solar Plexus***. Begin to circle the pearl at the solar plexus level. Circle the pearl to the left through T-11 and return to the solar plexus. Circle nine times. Create an internal cross with the pearl.
7. Bring the pearl to the left side of the ***Heart***. Circle nine times towards the left, to the middle of the shoulder blades, and back to the heart center. Use the pearl to form an internal cross connecting all four sides.
8. Next bring the pearl to the left side of the ***Throat Center***. Circle the pearl back to C-7, and to the middle of the throat center nine times. Form an internal cross. **Practice and master this step before continuing up to the crown.**
9. Bring the pearl to the upper tip of the left ear level with the ***Mideyebrow***. Circle the pearl nine times back to the small brain, to the upper tip of the right ear, returning to the mideyebrow. Feel a band of energy flowing around the mideyebrow, ears, and back of the head. Form an internal cross connecting all four sides.
10. Bring the pearl to the ***Left Side of the Crown****.* Circle the energy nine times counterclockwise at the crown. Connect the front, back, and both sides of this Belt Channel.

http://www-lab26.kuee.kyoto-u.ac.jp/study/mu/mu_e.html

http://www.rish.kyoto-u.ac.jp/radar-group/local/isr/EISCAT/is-methods.html
———————————-
USA (Besides HAARP)
UCLA’s
HIPAS — High Power Aural Stimulation Observatory
Located near Fairbanks Alaska

“Eight antennas like those in the picture are used to modify the ionosphere with high power radio waves near Fairbanks, Alaska. Radio wave soundings, optical diagnostics and other techniques are used to probe the ionosphere.”

http://replay.waybackmachine.org/19970722053407/http://www.physics.ucla.edu/~hipas/index.html

http://replay.waybackmachine.org/20010217055634/http://www.hipas.alaska.edu/index.html

http://replay.waybackmachine.org/20010405061931/http://www.hipas.alaska.edu/intro.html

http://replay.waybackmachine.org/20010406093357/http://www.hipas.alaska.edu/diagnostics.html

http://ulcar.uml.edu/stationmap.html
http://ulcar.uml.edu/stationlist.html

http://159.226.23.71/
http://carbon.ucdenver.edu/~mgolkows/Publications/RF2010.pdf
http://deepblue.lib.umich.edu/handle/2027.42/21659
www.physics.irfu.se/Publications/Articles/StubbeEtAl:JGR:1984.pdf
http://www.polar.umd.edu/haarp/riometer_paper/node3.html#SECTION00030000000000000000
http://www.polar.umd.edu/haarp/riometer_paper/node2.html#SECTION00020000000000000000

Follow



http://www-star.stanford.edu/~vlf/buoy/
http://www-star.stanford.edu/~vlf/buoy/systems.html

http://www-star.stanford.edu/~vlf/buoy/location.html
http://www-star.stanford.edu/~vlf/buoy/Documents/feasibilityStudyReport.pdf

CERN and HAARP –
http://cdsweb.cern.ch/record/1305357
http://arxiv.org/pdf/1011.1458.pdf
http://cdsweb.cern.ch/record/1003294/files/0612038.pdf
http://arxiv.org/pdf/physics/0101034

http://www.google.nl/url?sa=t&source=web&cd=11&ved=0CBkQFjAAOAo&url=http%3A%2F%2Fwww.calvin.edu%2F~pribeiro%2Fcourses%2Fengr302%2FSamples%2Fhaarp.ppt&rct=j&q=site%3A.edu%20haarp&ei=2fSmTaHpBIXsObOFqOQJ&usg=AFQjCNGC6l-0BQ2pkqbF6rzm353iRZjieA&sig2=

http://books.google.com/books?id=wU0EAAAAMBAJ&pg=PA52&lpg=PA52&dq=Irving+Langmuir+rainmaker&source=bl&ots=Ehqq8hZNsE&sig=tkN51NoxqMsKVq6ClZU9Hvej8g0&hl=en&ei=9mhMTO3vG93llQfjpJHGDw&sa=X&oi=book_result&ct=result&resnum=5&ved=0CCIQ6AEwBA#v=onepage&q&f=false

http://books.google.com/books?id=FVMEAAAAMBAJ&pg=PA113&dq=Irving+Langmuir&as_pt=MAGAZINES&cd=1#v=onepage&q=Irving%20Langmuir&f=false

http://books.google.com/books?id=G7t260XD8AYC&pg=PA47&dq=stormfury&hl=en&ei=9wJOTOfVE4G88gbZ3IGaDA&sa=X&oi=book_result&ct=result&resnum=3&ved=0CDEQ6AEwAg#v=onepage&q=stormfury&f=false

Follow

These shots below come from a Navy .mil website .. clearly showing the “HAARP ring” patter and circumference ..

http://wwwppd.nrl.navy.mil/whatsnew/haarp/

> *“By modulating the ambient current flowing in the ionosphere, e.g., the auroral electrojet, it is possible to generate extremely low frequency (ELF) and very low frequency (VLF) radiation. This ionospheric modification technique can provide such waves for probing both the Earth and the ionosphere- magnetosphere. The modification occurs in the lower D-region and can provide information about the ambient conditions in one of the least diagnosed regions of the ionosphere.*
>
> *The electrojet is modulated by using a high frequency heater (a few MHZ) with the power modulated at the desired ELF/VLF frequency to heat the ionospheric electrons in the lower D-region. Figure 1a shows a sketch of the heater and heated region. The heated region is typically at 75 km (though this depends upon the carrier frequency) and can be 30 km in diameter and a few km thick. Viewed from above (see Figure 1b) the heated region is a roughly circular patch. The smoothness of the heated region depends upon the antenna radiation pattern as well as D-region conditions. The heating increases the electron-neutral collision rate which changes the conductivities. Since on ELF time scales the ambient electric field is constant, modulating the conductivity produces a current modulated at the same frequency. At these altitudes the conductivity change is predominantly in the Hall conductivity. If the ambient electric field, E, is in ±y direction, a time varying current perturbation is generated, j, in the ±x direction (Fig. 1b). The time varying current launches waves both up and down the Earth’s magnetic field. In the simulations shown here, we start with a time-varying current and study the downward propagating waves and how they couple into the Earth-ionospheric wave guide.*
>
> *Animations*
>
> *The animations show 5 different representations of the same simulation. The simulation uses a time-varying current perturbation (1 kHz) in the D-region at 75 km. The current is in the magnetic east-west direction. The Earth’s magnetic field is vertical. The simulation box is 1800 by 1800 by 120 km. Isosurfaces are shown for the absolute value of the horizontal magnetic field ABSB and of the vertical electric field ABSEZ. Also shown is the east-west magnetic field in the near-field BX1 and in the far-field BX2. Since the field amplitude falls off with distance, BX1 uses a order-of-magnitude larger isosurface value than BX2 to emphasize the field close to the site. The north- south magnetic field is shown in BY1 and BY2. These plots look slightly different from the absolute value plots where both the positive and negative surfaces were shown. Also BX and BY do have a different orientation of the their radiation patterns. The direction of the radiation is determined by the total horizontal field shown in ABSB and by the vertical electric field shown in ABSEZ. The radiation pattern in the earth-ionosphere waveguide is a combination of a linear dipole antenna and a right-hand circular antenna. At ELF frequencies because of low D-region absorption the dipole is dominant. The dipole radiates in the magnetic east-west direction.*
>
> *Because 1 kHz is below cutoff the mode in the waveguide is a TEM mode. The mode consists of a horizontal B field perpendicular to the direction of propagation and a vertical electric field. With*

Follow

perfect conductors, the mode is uniform in the vertical direction. As the wave propagates in the waveguide, the top of the wave is approximately at the bottom of the ionosphere. Above the heated region, waves are also launched along the Earth's magnetic field. In the near-field (BX1 and BY1) one can see the pulse being radiated downward. It strikes the ground and reflects back up to the ionosphere. Part of the energy propagates up the field lines into the ionosphere. This is the bubble seen rising up. The D-region is highly collisional and damps this wave. Looking at BX2 and BY2 one can see that the energy mainly stays in the waveguide. If one looks closely at the top of the wave in the waveguide the wave appears to be curved. The waveguide mode is coupling into the bottom of the D-region and driving a whistler mode up the field lines. The whistlers have a much lower velocity than the waveguide mode and can only propagate along the field lines. This acts to curve the top of the waves. These waves help form the bubble that propagates up the field line. Because of this, the diameter of the bubble is much larger than the heated region.

Above the heated region in ABSEZ one can see a pair of coils revolving around each other. These are the currents that flow up and down the Earth's magnetic field forming the current loops associated with the waves propagating up the field lines. Finally, EZ1 is a blow-up of the high-altitude portion of the vertical electric field for positive values of the electric field; the current loop is more clearly seen."



Follow


HAARP; BY=0.4pT, f=1kHz,
z(km)
200
150
100
50
0
1800ns


HAARP; abs(EZ), f=1kHz,
z(km)
200
150
100
50
0
650ns

Follow


HAARP; BX=0.4pT, f=1kHz,
z(km)
200
150
100
50
0
500ns


HAARP; BX=4pT, f=1kHz,
z(km)
200
150
100
50
0
300ns

Follow


HAARP; EZ, f=1kHz,
120
110
100
90
80
70
z(km)
200ns


HAARP; abs(B)=0.4pT, f=1kHz,
200
150
100
50
0
z(km)
1950ns

http://www.telegraph.co.uk/news/worldnews/1549366/How-we-made-the-Chernobyl-rain.html

http://www.guardian.co.uk/uk/2001/aug/30/sillyseason.physicalsciences

http://www.politaia.org/umwelt-und-gesundheit/chemtrails/atmospheric-geoengineering-weather-manipulation-contrails-and-chemtrails-2/

Simulations of ELF radiation generated by heating the high-latitude D- region
H.L. Rowland, Beam Physics Branch, Plasma Physics Division, Naval Research Laboratory, Washington, D.C.
"This ionospheric modification technique can provide such waves for probing both the Earth and the iono

Follow

magnetosphere."
http://wwwppd.nrl.navy.mil/whatsnew/haarp/
——————————


BASE
REFLECTIVITY
MKX
08/15/03 07:03Z
RANGE: 230 KM
RES: 1 KM X 1 DEGREE
MODE: CLEAR AIR
ELEV: 0.5 DEGREES
DBZ
ND
0
-28
+ 4
-24
+ 8
-20
+12
16
+16
-12
+20
- 8
+24
- 4
+28
0
MAX DBZ. 46

Ionospheric modification and ELF/VLF
wave generation by HAARP
http://nlpc.stanford.edu/nleht/Science/talks/ursi_jan06.pdf

—————————————-

HAARP JOINT SERVICES PROGRAM PLANS AND ACTIVITIES: Air Force Geophysics Laboratory and Office of Naval Research, February 1990 (PDF)
http://www.wired.com/images_blogs/dangerroom/2009/07/haarp_1990.pdf

Link obtained from:
http://www.wired.com/politics/security/magazine/17-08/mf_haarp?currentPage=all
——————————————

Popular Mechanics Magazine:
The World's 18 Strangest Military Bases
http://www.popularmechanics.com/technology/engineering/architecture/strangest-military-bases-gallery

HAARP Research Station – not much info, but says:
"In past interviews, HAARP's operators readily admit they're researching potential defense applications."
————————————-

Modification of the Ionosphere by VLF Wave-Induced Electron Precipitation
http://vlf.stanford.edu/sites/default/files/publications/Doolittle%20PhD%20Dissertation.pdf
—————————————

Title : A Diagnostic System for Studying Energy Partitioning and Assessing the Response of the Ionosphere During HAARP Modification Experiments.

“The HAARP facility is classically referred to as an HF ionospheric modification facility. HF ionospheric modification entails the use of high power, high-frequency (~2-15MHZ) radio waves to modify the earth’s ionosphere.”
http://www.dtic.mil/cgi-bin/GetTRDoc?AD=ADA323070&Location=U2&doc=GetTRDoc.pdf

——————————————————
Title : High-Energy Electron Beam-Induced Ionospheric Modification Experiments

http://www.dtic.mil/cgi-bin/GetTRDoc?AD=ADA329174&Location=U2&doc=GetTRDoc.pdf

http://webcache.googleusercontent.com/search?q=cache:XgAQtkkDHaIJ:lucianarchy.proboards.com/index.cgi%3Fboard%3Dzorgon%26action%3Dprint%26thread%3D8872+thompson+manitoba+vlf+haarp&cd=12&hl=en&ct=clnk&gl=ca&source=www.google.ca

Baikal-1 and IGR sites
Semipalatinsk-21, Kazakhstan
URDF-3 (Unidentified Research and Development Facility-3)
Baikal-1, Semipalatinsk, Kazakhstan
50 10 12.69 N, 78 22 36.84 W

Strange Towers in a Russian Forest
Tesla Generators
Sychëvka, Moskovskaya Oblast’ (Russia)
+55 55 26.15 N, 36 49 10.97 W

The Russian Woodpecker
Duga Radar Array, Chenobyl, Ukraine
51 18 20.17 N, 30 04 02.60 E

China Research Institute of Radiowave Propagation (CRIRP)
HAARP Like Facility
Ionospheric Laboratory
Ionospheric Laboratory, Xinjiang (Sinkiang) Region
40 24 15.91 N, 93 38 09.74 E

Zhong Shan Antarctic Polar Station (China)
69 22 23.63 S , 76 22 19.11 E

Sheshan, Shanghai, China
EISCAT Like Facility
31 5 41.98 N, 121 11 29.72 E

Misawa, Japan

Follow

Misawa NSA Echelon Station

Code Name: Ladylove

+40 43 22.91 , +141 19 43.57

Follow

11. Allow the pearl out above the crown. Circle the energy nine times forming a ***Halo of Energy***. Use the pearl to cross the halo, front to back, and left to right. Collect the energy from above the head.

Descending Back to the Pakuas

12. Reverse the energy flow to a clockwise direction. Circle the ***Halo*** nine times. Then cross it front to back, and right to left sides.
13. Bring the pearl back to the ***Crown***. Circle to the right nine times. Then use the pearl to cross the front, back, and two sides.
14. Move the pearl down to the upper tip of the right ear. Circle from the right ear to the mideyebrow. Repeat nine times. Use the pearl to form a cross and return it to mideyebrow.
15. Bring the pearl down to the right side of the neck at the ***Throat Center***. Circle right to *C-7* at the back of the neck. Return to the front again. Circle nine times. Cross the front, back, and two sides. Bring the pearl to the front.
16. Bring the pearl down to the right side of the ***Heart Center***. Circle it clockwise nine times, ending at the front. Then, use the pearl to cross the front, back, and sides. Return the pearl to the front again.
17. Move the pearl to the ***Solar Plexus***. Circle it nine times to T-11 at the back, and return to the solar plexus. Cross the front, back, and sides. Return the pearl to the front.
18. Bring the pearl down to the ***Navel***. Circle it back to the Door of Life, and back to the navel nine times. From the navel bring the pearl to the cauldron, back toward the Door of Life, and return it to the cauldron. Use the pearl to cross the right and left sides. Return the pearl to the navel.

Descending from the Pakuas to the Earth.

19. Once you have controlled the pearl to this stage of the meditation, you are ready to move the pearl down to the ***Sexual Center***. Women bring the pearl down to the right side of the ovary center, located three inches below the navel. Men bring the pearl from the navel down to the right side of the sperm palace, one and a half inches below the navel. Circle clockwise back to the sacrum, to the left hip, and to the front of the ovary center/sperm palace nine times. Use the pearl to make a cross. Return the pearl to the front of the sexual center.


NEXRAD radar image(s) [KCA...
displayN0R.php (PNG Image, ...
YouTube - Broadcast Yourself.
http://weather.rap.ucar.edu/radar/displayRad.php?icao=KCAE&prod=n0r&bkgr=black&endDate=20110827&endTime=-1&duration=10
Most Visited
Getting Started
Latest Headlines
From Internet Explorer
Set Animation Speed
Stop
Show
Left click - toggle on/off; Right click - show frame
0308 UTC Sat 27 Aug 2011 (c) UCAR http://weather.rap.ucar.edu/radar/
-10 -5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70
Reflectivity (dBZ)


NEXRAD radar image(s) [KCA...
displayN0R.php (PNG Image, ...
YouTube - Broadcast Yourself.
http://weather.rap.ucar.edu/radar/displayRad.php?icao=KCAE&prod=n0r&bkgr=black&endDate=20110827&endTime=-1&duration=10
Most Visited
Getting Started
Latest Headlines
From Internet Explorer
Set Animation Speed
Stop
Show
Left click - toggle on/off; Right click - show frame
0243 UTC Sat 27 Aug 2011 (c) UCAR http://weather.rap.ucar.edu/radar/
-10 -5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70
Reflectivity (dBZ)

HAARP High Frequency Active Auroral Research Program

Follow

Gacona, Alaska

http://www.public.navy.mil/spawar/productsServices/Pages/default.aspx

he AN/FLR-9, operated by the Air Intelligence Agency, is part of the DOD World Wide High Frequency Direction Finding System

Andenes, NORWAY (VHF grid ALWIN)
69.29851, 16.042269

MU (Middle-Upper atmosphere),Shigaraki, Japan (circular phased array)
34.853842, 136.105710

A volcanic Island in the pacific west of Mexico and the northern direction is directly in line with the lower san andreas fault. Here is the google earth location.

28 53 23.06 N , 118 16 50.20 W Check it out, its an uninhabited island as well in the middle of no where.
MOST INTERESTING:
Misawa, JAPAN (CIRCULAR HAARP!!! code name: LADYLOVE)
40.723031, 141.328769

EAR (Equatorial Atmospheric Radar) SUMATRA made by JAPAN (circular again)
-0.203705, 100.319872

Taiwan, CHINA (dish on H-shape building, antenna grid not far, check links)
24.967858, 121.1870

Burt Plain, AUSTRALIA (strange)
-23.521497, 133.67752

Laverton, AUSTRALIA
-28.33, 122

Hart, Australia
-22.968290, 134.448124

Poker Flat, Alaska, USA (AMISR Advanced Modulator Incoherent Scatter Radar)
65.129852, -147.470623

AMISR, Resolute Bay, CANADA
74.728138, -94.924242 (dish)
Antennas everywhere following the roads(phased array) the whole place is a grid!
74.733132, -94.932071

Futur “MU” from JAPAN (Incoherent Scatter) site in ANTARTICA
-68.984348, 39.647884

Follow

http://lucianarchy.proboards.com/index.cgi?board=zorgon&action=print&thread=8872
http://www.noao.edu/nsf/presentations/FACILITIES
http://www.eiscat.se/groups/EISCAT_3D_info/Deliverable_D11_1.pdf


Riometer Beam
Heated Region
Beam Forming Network
Receiver Bank
Digital Data Acquisition, Processing, and Display

Nashville
Greensboro
Charlotte
Atlanta
Birmingham
Montgomery
intellicast.com

1- High Frequency Active Auroral Research Programn (HAARP)
Gakona Alaska
+62 23 30.00 , -145 8 48.00

2- High Power Auroral Stimulation Observatory (HIPAS)
Fairbanks Alaska
64 52 19 N , 146 50 33 W

3- Poker Flat Research Range
Near Chatanika, Alaska
+65 7 23.90 , -147 28 7.05

4- Platteville Atmospheric Observatory
Platteville, Colorado
+40 10 54 , -104 43 30

Follow

5- Millstone Hill Radio Observatory
Westford, Massachusetts
+42 37 09.25 , -71 29 28.49

6- The Arecibo Observatory radio telescope
Arecibo Puerto Rico.
18 20 38.97 N , 66 45 9.77 W

7- Jicamarca Radio Observatory
Lima, Peru
11 57 08.25 S , 76 52 30.67 W

8- São Luiz Space Observatory
Cruzeiro Santa Bárbara, Sao Luis-MA, Brasil
-2 35 40.47 , -44 12 35.90

9- Nerc MST Radar Facility
Capel Dewi, Carmarthenshire, Wales, United Kingdom
+52 25 28.26 , -4 00 19.59

10- European Incoherent Scatter Scientific Association EISCAT
Ramfjordmoen, Near Tromsø, Norway
+69 35 10.94 , +19 13 20.89

11- Sura Facility
Nizhniy Novgorod, Russia
+56 7 9.70 , +46 2 3.66

12- The Russian Woodpecker
Duga Radar Array, Chenobyl, Ukraine
51 18 20.17 N, 30 04 02.60 E

13- National MST Radar Facility NMRF
Gadanki, India
+13 27 26.68 , +79 10 30.74

14- China Research Institute of Radiowave Propagation (CRIRP)
Xinjiang (Sinkiang) Region
40 24 15.91 N , 93 38 09.74 E

15- Sheshan, Shanghai,
China
31 5 41.98N , 121 11 29.72 E

16- Mu Radar
in Japan

Follow

34 51 14.80 N , 136 6 19.45 E

17- Jindalee Operational Radar Network (JORN)
Laverton, West Australia
-28 19 36.29 , +122 0 18.84

18- Jindalee Operational Radar Network (JORN)
Longreach, Queensland, Australia
-23 39 29.53 , +144 8 49.58

19- Australia Naval Communications Station Harold E Holt (NCS HEH)
Exmouth, Western Australia. 21 48 59.47 s, 114 09 55.60

20- Zhong Shan Antarctic Polar Station (China)
69 22 43.69 S , 76 23 15.07 E

Sura Ionospheric Heating Facility
http://en.wikipedia.org/wiki/Sura_Ionospheric_Heating_Facility



Follow


Set Animation Speed
Stop
Show
Left click - toggle on/off, Right click - show frame
-10 -5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70
Reflectivity (dBZ)

oaded 66 out of 66


MAPSPACE™
MAP TYPE / ANIMATION
MAP SIZE
CENTER
PLACEMARK
VISIBLE LAYERS
HELP
GO
Barrie
Vaughan
Cambridge
London
Buffalo
Madison
Milwaukee
Grand Rapids
Flint
Detroit
Rockford
Chicago
Toledo
Cleveland
Akron
Fort Wayne
Pittsburgh
Indianapolis
Dayton
Columbus
Cincinnati
Saint Louis
Louisville
Springfield
Nashville
Knoxville
Greensboro
(C) 2011 AccuWeather.com
1000 mi
FIRST FRAME
FRAME REV
PLAY REV
STOP
PLAY FWD
FRAME FWD
LAST FRAME
ONCE
REPEAT
SWEEP
SLOWER
FASTER
Light
Heavy
Severe
Rain
Snow
Ice

U.S. Snow/Ice/Rain Radar

ANIMATION: 4 hours by 5 min

11.45PM GMT 7-Sep

Follow

HAARP, Gakona, Alaska, USA
62.390000, -145.150000

Other HAARP facilities in USA:

HAARP AREA 51(Can't find that one)
possible picture:
http://media.photobucket.com/image/image%20of%20giant%20human%20shadow%20area%2051/AsiaParanormal/google%2520earth/GiantHumanShadowClosetoArea51.jpg

HAARP, Long Island, USA (dish & antennas)
40.878455, -72.687485

HIPAS (ionospheric heater) Fairbanks, Alaska, USA
64.872425, -146.842625

Platteville, Colorado, USA (The first american HAARP)
40.181667, -104.725000

Westford, Massachusetts, USA (EISCAT-like)
42.619236, -71.491247

WORLD:

Arecebo, PORTO-RICO
18.344167, -66.752778

BRAZIL (blurred)
-2 35 40.47 , -44 12 35.90

Capel Dewi,UNITED KINGDOM
52.424517, -4.005442

INDIA
13.457411, 79.175206

CHINA
40.404062 , 93.633678

Lima, PERU (bigger than Alaska)
-11 57 6.67 , -76 52 25.71

Chernobyl, UKRAINE (monster)
51.305603, 30.067389

Östra Sallerup, SWEDEN

Follow

55.814601 , 13.728526

Tähteläntie, FINLAND
67.363842 , 26.630384

EISCAT, Tromso, NORWAY
69.582697, 19.213958

Saskatoon, CANADA (strange grid)
52.16 N , 106.53 W

Exmouth, AUSTRALIA
-21.908677 , 114.131806

Vasil'sursk, RUSSIA
56.114993, 46.027851
pictures at:

http://www.jp-petit.org/nouv_f/Crop%20Circles/haarp_russe/haarp_russe.htm

UTR-2 URAN (VLBI) Latitude 49 38 14.20 N , 36 56 11.08

URAN 1 — 49 40 29.53 N, 36 17 31.29

URAN 2 — 49 37 51.17 N, 34 49 29.80

URAN 3 — 49 38 14.20 N , 23 49 37.02

URAN 4 — 49 38 14.20 N , 30 16 21.96

EISCAT 69 35 04.24 N , 19 12 58.53

ALWIN WIBKE 69 1755.10 N , 16 02 32.32

Alomar 69 16 41.92 n , 16 00 29.66

IAP Germany 54 07 03.59 N , 11 46 13.16

TIRA 50 37 00.59 N , 07 07 45.30 W

NMRF Wales, UK 52 25 28.26 N , 04 00 19.62 W

Jicamarca 11 57 03.10 S , 76 52 29.04 W

SAO Luiz 02 35 38.34 S , 44°12'36.86" W

JORN 28 19 36.29 S , 122 00 18.85 W

Follow

JORN 2 — 23 39 29.53 S , 144 08 49.58 W

JORN 3 — 22 58 03.22 S , 134 26 52.57 W

Naval Communication Station 1 — 21 48 59.80 S , 114 10 03.01

Naval Communication Station 2 — 21 54 33.47 S , 114 07 56.72

National MST Radar Facility 13 27 25.84 , 79 10 31.19

CRIRP 40 24 15.91 N , 93 38 09.74

Chung-Li VHF Radar 24 58 03.86 N , 121 11 11.71

MU Radar 34 51 13.86 N , 136 06 20.90

http://www.public.navy.mil/spawar/productsServices/Pages/default.aspx



Sioux Falls
Milwaukee
Chicago
Detroit
Salt Lake City
Cheyenne
North Platte
Omaha
Des Moines
Denver
Indianapolis
Columbus
Kansas City
Cincinnati
Saint Louis
Lexington
Durango
Nashville
Las Vegas
Flagstaff
Albuquerque
Amarillo
Oklahoma City
Memphis
Phoenix
Abilene
Dallas
Jackson
El Paso
Intellicast.com

Follow


College of DuPage Meteorology Radar Loop - Mozilla Firefox
weather.cod.edu/cgi-bin/radarloop.pl?station=TLX&product=BREF1&loopdir=brefs
Frame Controls:
Loop Mode:
Animate Frames:
Dwell First:
Dwell Last:
Adjust Speed:
Advance One:
Frame No: 2
Omit Frame:
24-Image Loop from the College of DuPage
Base reflectivity (Dbz)TLX – TWIN LAKES/OKLAHOMA CITY OK – BREF1 0129Z 11 OCT 11
−90 −24 −16 −8.0 0 8.0 16 24
Md=cl Rng=124(0.5) El=0.5 Mx=35


Adrian
Monroe
Toledo
Bowling Green
Defiance
Findlay
Tiffin
Lorain
Cleveland
Ashtabula
Mentor
Warren
Strongsville
Norwalk
Akron
Youngstown
Alliance
Canton
Wooster
Mansfield
Marion
Lima
Sidney
Delaware
Mount Vernon
Coshocton
Dover
Pittsburgh
Strabane
Greensburg
Butler
Indiana
Altoona
State College
Saint Marys
Sandy
Sunbury
Harrisburg
Wheeling
Westerville
Columbus
Zanesville
Urbana
Troy
Springfield
Dayton
Springboro
Lancaster
Circleville
Chillicothe
Athens
Marietta
Parkersburg
Clarksburg
Morgantown
Cumberland
Hagerstown
Chambersburg
York
Hanover
Westminster
Frederick
Gainesboro
Opequon
Cincinnati
intellicast.com

List Found here
http://ulcar.uml.edu/stationlist.html
DIDBase list here
http://car.uml.edu/common/DIDBFastStationList
http://ulcar.uml.edu/DIDBase
Much more can be found
http://giro.uml.edu/

It’s the loudest sound you’ll come across on the short wave now. 8.545 megahertz is one. 8.570 ...this is before 12:00 noon. 12.815 and 12.850, 17.110, 18.370 MHz. Then in the afternoon and sometimes after 6:00 PM you will hear it on 17.110 and other frequencies as well. So we’re getting really blasted with this thing

Dr. Moshe Alamaro (worked with Dr. Eastlund in weather modification / engineering) As a graduate student and later as a Research Scientist at the MIT Department of Earth, Atmospheric, and Planetary Sciences (EAPS) Moshe Alamaro helped to design, build and manage the MIT Air-Sea Interaction Lab where he supervised six students.

Follow

20. Bring the pearl down to the right groin. Circle the pearl clockwise around the ***Perineum Point and Lower Hips*** nine times. Use the pearl to form a cross by connecting the front, back, and sides. Return the pearl to the front.
21. Move the energy down and circle toward the back of ***Both Knees***, around and to the front, midway between both knees, moving the pearl clockwise nine times. Use the pearl to form a cross by moving the pearl to the midpoint between the knees and connecting the front, back, and sides from this point. End with the pearl midway between the fronts of both knees.
22. Direct the energy down to the feet, just below the ankles. Circle the ***Soles of the Feet*** nine times moving the pearl clockwise to the heel of the right foot, to the heel of the left foot, to the outer side of the left foot, to the front, midway between both feet. Form a cross. End with the pearl midway between both feet.
23. Move the energy from the front of the feet down to a point ***Beneath the Earth***, and circle toward the right (clockwise) nine times. Use the pearl to form a cross ***Beneath the Earth***. Keep on spiraling more energy to enhance the pearl. Return the pearl to the front of the circle.

Ascending from the Earth Back to the Pakuas

24. Reverse the circle beneath the earth, moving the pearl counterclockwise again nine times. Use the pearl to form a cross, connecting the front, back, and sides.
25. Move the pearl to the outer side of the left foot. Circle the ***Soles of Both Feet*** nine times moving toward the left heel, to the right heel, to the right foot, and to the front (midway) of both feet. Use the pearl to form a cross. End with the pearl at the midway point in the front of both feet.
26. Move up to the left knee. Circle the pearl counterclockwise *at* the ***Knees*** nine times. Use the pearl to form a cross. Return the pearl to the midway point in the front of both knees.
27. From the front of the knees, move up to the left groin area. Circle counterclockwise at the ***Perineum*** nine times. Use the pearl to form a cross. Return the pearl to the front of the perineum.
28. Direct the energy to the left hip, and circle counterclockwise at the ***Ovary/Sperm Palace*** nine times. Use the pearl to form a cross by connecting the front, back, and sides. End with the pearl at the front of the ovary/sperm palace.
29. Return the pearl to the ***Navel*** and to the ***Cauldron***.

Alamaro, M.; “My Journey to Engineer the Weather”, MIT Alumni News and Views, What Matters: June 2009.

https://alum.mit.edu/news/WhatMatters/Archive/200906/

Armstrong, R., Glenn G.J., Alamaro, M. “Coordination, research needed in weather science”, Physics Today, Vol 60, Page 10, June 2007.

Alamaro, M., Emanuel, KA, McGillis, W.: “Experimental Investigation of Air-Sea Transfers at High Wind Speed,” forthcoming in Journal of Fluid Mechanics.

With Emanuel, K.A.: “Sea-Air Transfer in Tropical Cyclones,” Proceedings of the International Union of Geodesy and Geophysics, Sapora, Japan, July 1, 2003.

Popular Press:

“Scientists a step closer to steering hurricanes-schematics “, The Sunday Telegraph, October 21, 2007.

http://web.mit.edu/alamaro/www/telegraph_hurricane_rendering_oct_21_2007.pdf


Layers
Overlays
Sioux Falls
Milwaukee
Detro
Chicago
Des Moines
North Platte
Omaha
Indianapolis
Colum
Cincinnati
Kansas City
Saint Louis
intellicast.com
Lexington
2011 Apr 9 10:00 PM EST
Looping Speed:
Fast
Opacity Level:
0
10
Done
Internet


Layers
Overlays
Sioux Falls
Milwaukee
Detroit
Chicago
Des Moines
Clev
rth Platte
Omaha
Indianapolis
Columbus
Cincinnati
Kansas City
Saint Louis
intellicast.com
Lexington
2011 Apr 9 10:30 PM EST : Paused
Looping Speed:
Fast
Opacity Level:
0
10

Follow

Lincoln
Kansas City
Indianapolis
Louisville
Wichita
Nashville
intellicast.com
Oklahoma City

Ponca City
Woodward
Enid
Bella Vista
Rogers
Hico
Fayetteville
Stillwater
El Reno
Elk City
Fort Smith
Russellville
Conway
Chickasha
McAlester
Ada
Lawton
Duncan
Hot Springs
intellicast.com

Quick Picks
North Platte
Denver
Colorado Springs
Durango
Wichita
intellicast.com

Follow

Quick Picks
Layers
Overlays
Thunder Bay
Fargo
Duluth
Marquette
Minneapolis
Green Bay
intellicast.com
Medium

Layers
Overlays
Thunder Bay
Bismarck
Fargo
Duluth
Marquette
Minneapolis
Green Bay
Rapid City
Sioux Falls
Milwaukee
intellicast.com
2011 Apr 13 1:05 AM EST : Looping
Looping Speed:
Medium

Mount Vernon
Carbondale
Cape Girardeau
Parsons
Pittsburg
Joplin
Miami
Bartlesville
Owasso
Fayetteville
Tahlequah
Muskogee
Poplar Bluff
Sikeston
Union City
Kennett
Paragould
Jonesboro
intellicast.com
Medium

Follow


Layers
Overlays
Sioux Falls
Milwaukee
Detro
Chicago
Des Moines
North Platte
Omaha
Indianapolis
Colum
Kansas City
Cincinnati
Saint Louis
intellicast.com
Lexington
2011 Apr 9 9:50 PM EST
Looping Speed:
Fast
Opacity Level:
Done
Intern

“Scientists: Killer Hurricanes May Someday Be Controlled With Soot”, Fox News, October 31, 2007.

http://www.foxnews.com/story/0,2933,306201,00.html

“Activate Cloud Shield! Zap a Twister!”, Weird Magazine, January 2000.

http://www.declarepeace.org.uk/captain/murder_inc/site/pics/katrina/weather_pr.html

“Ultra-thin ‘blankets’ cut reservoir evaporation”, New Scientist, November 2003

http://www.newscientist.com/article/dn4323-ultrathin-blankets-cut-reservoir-evaporation.html

http://www.news.com.au/weird-true-freaky/bueau-of-mereology-cant-explain-mysterious-patters-on-radar-system/story-e6frflri-1225848774377

This link below shows interesting cycle of test patterns repeating series of varying arrays
http://catastrophist.wordpress.com/2010/01/30/aust-radar-rings-haarp/

ELF – http://www.mediafire.com/?579i63yq53u1q
Tesla Technology – http://www.mediafire.com/?7xn1eqog9b5au
Science & Engineering – http://www.mediafire.com/?gs2scvvhz6ww8

Johnsen-Atoll: 16 43 41.21 N , 169 31 55.53 W
Militärbasis Ascension Island: 7 56 16.43 S , 14 22 33.81 W

Militärgebiet Australien: 21 48 37.87 S , 114 10 33.30 E

Kreis-Militär China: 40 27 25.98 N , 93 18 44.87 E
Hallo Tesla^^ Russland: 55 55 27.85 N , 36 49 8.58 E
Rund-Käfig USA Utah: 40 11 59.06 N , 113 10 34.69 W
Kreise-Viereck USA Utah: 40 6 48.51 N , 112 58 19.03 W

Kreise USA Utah: 40 12 39.26 N , 113 17 22.29 W

Follow

http://alligatorfarm.wordpress.com/2011/03/30/smoking-gun-haarp/

http://i116.photobucket.com/albums/o26/squiresmurf/rad_us_loop.gif

http://www.spaceweather.ac.cn/page.php?title=meriproject

(translate with google)

http://english.cssar.cas.cn/op/mp/

http://www.angelfire.com/scifi/EclipseLab/Tesla/Oscillator.html


Haystack Observatory
Haystack Radar
HAX Radar
Millstone Hill
Ionospheric Radars
Satellite Tracking Radar
Firepond Optical Facility
Westford Radio Telescope
Optical Aeronomy Facility

Just wanted to share a list of scattering radar and heating facilities that I've come across, in case you don't know about some of these.
Had to use the wayback for a lot of these.

University of Leicester — Ionospheric Heating

http://replay.waybackmachine.org/19980211033937/http://ion.le.ac.uk/index.html

http://replay.waybackmachine.org/19980211032156/http://ion.le.ac.uk/heating/Heating.html
(several years up to 2007)

http://replay.waybackmachine.org/20061229014910/http://ion.le.ac.uk/heating/history_of_rf_heating.html

http://replay.waybackmachine.org/20061229011401/http://ion.le.ac.uk/heating/6Feb.html

Sura Ionospheric Heating Facility
http://en.wikipedia.org/wiki/Sura_Ionospheric_Heating_Facility

Follow

The EISCAT Associates
(A lot of info on this site, captured from the late 90′s)

http://replay.waybackmachine.org/19980210065153/http://seldon.eiscat.no/eiscat.html
France, Finland, Germany, Japan, Norway, Sweden, UK
*Incoherent scatter radars
(Below)

*Ionospheric Heating
Their Facility -
http://replay.waybackmachine.org/19980210071758/http://seldon.eiscat.no/heater.html

EISCAT Headquarters are located at Kiruna in Sweden
The EISCAT Scientific Association,
Headquarters,
PO Box 812,
S-981 28 KIRUNA
Sweden

Incoherent Scatter Facilities
Operational Incoherent Scatter Radars

Jicamarca, Peru
http://jicamarca.ece.cornell.edu/

Arecibo, Puerto Rico

http://replay.waybackmachine.org/19961105195521/http:/naic.edu/

(click on a Layman’s guide for info on “probing the ionosphere” and “modifiying the ionosphere locally”

Millstone Hill, USA
(Haystack)
http://replay.waybackmachine.org/19970710073509/http://www.haystack.edu/homepage.html

Pic of Haystack facility and more info:
http://replay.waybackmachine.org/19990116225557/http://www.haystack.edu/haystack/haystack.html

Sondrestromfjord, Greenland
http://replay.waybackmachine.org/19990224220742/http://128.18.44.75/iono/issfsond.html

EISCAT, Norway/Sweden/Finland
(Main EISCAT Site)

EISCAT Svalbard Radar, Svalbard (First operations late in 1995)
http://replay.waybackmachine.org/19961117043355/http://seldon.eiscat.no/ESR_intro.html

Follow

Kharkov, Ukraine
http://www-radiophys.univer.kharkov.ua/space/

(search for scatter)

Irkutsk, Russia
The Institute possesses a complex of unique astrophysical equipment deployed in the Sayan Mountains, especially the Siberian solar radiotelescope, a large solar vacuum telescope, an incoherent scatter radar, as well as a network of astrophysical laboratories throughout the territory of Siberia.
http://www.irkutsk.org/acad/acad_e.htm

http://ursi.org/Proceedings/ProcGA05/pdf/GP2.3%280511%29.pdf

MU, Japan
http://www-lab26.kuee.kyoto-u.ac.jp/study/mu/mu_e.html

http://www.rish.kyoto-u.ac.jp/radar-group/local/isr/EISCAT/is-methods.html

——————————-
USA (Besides HAARP)
UCLA's
HIPAS — High Power Aural Stimulation Observatory
Located near Fairbanks Alaska

"Eight antennas like those in the picture are used to modify the ionosphere with high power radio waves near Fairbanks, Alaska. Radio wave soundings, optical diagnostics and other techniques are used to probe the ionosphere."
http://replay.waybackmachine.org/19970722053407/http://www.physics.ucla.edu/~hipas/index.html
-

http://replay.waybackmachine.org/20010217055634/http://www.hipas.alaska.edu/index.html

-

http://replay.waybackmachine.org/20010405061931/http://www.hipas.alaska.edu/intro.html

-

http://replay.waybackmachine.org/20010406093357/http://www.hipas.alaska.edu/diagnostics.html

-

http://en.wikipedia.org/wiki/Sura_Ionospheric_Heating_Facility

-

http://www.public.navy.mil/spawar/productsServices/Pages/default.aspx

Follow

-

http://www.eiscat.se/groups/EISCAT_3D_info/Deliverable_D11_1.pdf

-

50 10 12.69 N , 78 22 36.84 W

55 55 26.15 N , 36 49 10 .97 W
51 18 20.17 N , 30 04 02.60 E

40 24 15 .91 N , 93 38 09.74 E
69 22 23.63 S , 76 22 19.11 E

69.29851, 16.042269
34.853842, 136.105710
28 53 23.06 N , 118 16 50.20 W

Misawa, au Japon (CIRCULAIRE HAARP nom de code:! Dulcinée)
40.723031, 141.328769
-0.203705 , 100.319872
24.967858 , 121.1870
-23.521497 , 133.67752

-22.968290 , 134.448124
65.129852 , -147.470623
74.728138 , -94.924242
74.733132 , -94.932071
-68.984348 , 39.647884
64 52 19 N , 146 50 33 W
65 7 23.90 , 147 28 7.05
40 10 54 , 104 43 30
42 37 09.25 , 71 29 28.49

69 35 10,94 , 19 13 20.89
56 7 9.70 , 46 2 3.66
51 18 20.17 N , 30 04 02.60 E
13 27 26.68 , 79 10 30.74
40 24 15.91 N , 93 38 09.74 E
69 22 43.69 S , 76 23 15.07 E
62.390000, -145.150000
13.457411 , 79.175206
40.404062 , 93.633678
-11 57 ’6.67 , -76 52 25.71
51.305603 , 30.067389

Follow

55.814601, 13.728526
67.363842, 26.630384
69.582697 , 19.213958
52.16 ° N , 106.53 ° W
-21.908677 , 114.131806
56.114993 , 46.027851

Airplanes around airports CAUSE snow and rain NEARBY


Getting Started
Latest Headlines
From Internet Explorer
na
MD
<10
10-20
20-30
30-40
40-50
50-60
60-70
75+
dBZ
Loop Mode:
Adjust Speed:
Dwell First/Last:
Frame No: 30
CONUS2 MergedReflectivityComposite 00:00 (2011 10/17 05:32:17 UTC)

Follow


College of DuPage
NeXt Generation Weather Lab
StormReady
what does this mean?
Home
Academics
Weather Analysis Tools
Storm Chasing Program
Local Weather
FAQs
Visible
Infrared
Water Vapor
Radar
Start
Set Animation Speed
<
>
Loop
Zoom
Show
No Enhancement
Refresh
IDs
Roads & Rivers
Counties
Lat & Lon
WX Watches
Sfc Plot
dBZ
75
65
55
45
35
25
15
5
-5
-15
-25
NEXRAD 1KM MOSAIC 1 NOV 11 23:11


Lexington-Fayette
Richmond
Virginia Beach
Nashville
Winston-Salem
Greensboro
Chattanooga
Charlotte
Huntsville
Birmingham
Atlanta
Augusta
Montgomery
Savannah
Mobile
Tallahassee
Jacksonville
Orlando
Saint Petersburg
Tampa
(C) 2011 AccuWeather.com
1000 mi

video of the article “proof”… front page of Yahoo! news…

http://www.youtube.com/watch?v=uxk2Rb6Cy4w

Follow

Men and Women Practice Differently

Men*:* Shoot the Pearl out of the Crown, and Spiral the Pearl down from the Crown.

1. Bring the pearl up to the crown.
2. Allow the pearl to go out three to six inches above the head. Circle nine times counterclockwise. Collect the heavenly energy and blend it in the pearl. Then circle it nine times clockwise.
3. Bring the pearl back into the crown point.
4. Spiral it clockwise through each of the Belt Channels all the way down to the soles of the feet.
5. Move the pearl into the earth six to twelve inches to collect the earth energy, and circle the energy nine times clockwise. Reverse the direction spiraling nine times counterclockwise.
6. Return the pearl to the front of the crown, and then back down to the navel and cauldron in the same manner.

Women*:* Shoot the Pearl into the Earth, and Spiral the Pearl up from the Earth

1. Bring the pearl to the soles of the feet.
2. Move the pearl into the ground six to twelve inches to collect the earthly energy. Circle the energy nine times clockwise. Then nine times counterclockwise.
3. Move the pearl up through the left side of each Belt Channel, spiraling counterclockwise to the crown.
4. Shoot the pearl all the way out at the crown to collect the heavenly energy. Circle the energy counterclockwise nine times. Reverse the direction, and spiral the pearl nine times clockwise.
5. Bring the pearl back down into the right side of the crown. Continue to circle the energy clockwise down through the Belt Channel to the soles of the feet. Return the pearl to the navel and cauldron in the same manner.

http://news.yahoo.com/planes-rain-wets-airport-terrain-212002695.html

“Airplanes flying through super-cooled clouds around airports can cause condensation that results in more snow and rain nearby, according to a new study.

The correct conditions for this inadvertent weather modification occur about 5 percent of the time — but 10-to-15 percent in winter — according to Andrew J. Heymsfield of the National Center for Atmospheric Research in Boulder, Colo., lead author of the study appearing in Friday’s edition of the journal Science”
49 38 14.20 N , 36 56 110.08
49 40 29. 53 N , 36 17 31.29
URAN 2 — 49 37 51.17 N , 34 49 29.80
URAN 3 — 49 38 14.20 N , 23 49 37.02
URAN 4 — 49 38 14 .20 N , 30 16 21.96

EISCAT 69 35 04.24 N , 19 12 58.53
ALWIN Wibke 69 17 55.10 N , 16 02 32.32

IAP Allemagne 54 07 03.59 N , 11 46 13.16
50 37 00.59 N , 07 07 45.30

52 25 28.26 N , 04 00 19.62 W
11 57 03.10 S , 76 52 29.04 W
02 35 38.34 S , 44 12 36.86 W
28 19 36.29 S , 122 00 18.85
23 39 29.53 S , 144 08 49.58
22 58 03.22 S , 134 26 52.57

21 48 59.80 S , 114 10 03.01
21 ° 54’33 .47 “S, 114 ° 07’56 .72
13 27 25.84 , 79 10 31.19
40 24 15.91 N , 93 38 09.74

24 58 03.86 N , 121 11 11.71

34 51 13.86 N , 136 06 20.90

-

http://jicamarca.ece.cornell.edu/

-

http://ulcar.uml.edu/stationlist.html

-

http://car.uml.edu/common/DIDBFastStationList

-

Follow

http://ulcar.uml.edu/DIDBase/

-

http://giro.uml.edu/

-

https://alum.mit.edu/news/WhatMatters/Archive/200906

-

http://web.mit.edu/alamaro/www/telegraph_hurricane_rendering_oct_21_2007.pdf

-


Radar data projected onto discrete horizontal planes
horizontal planes
radar

Follow


B FIELD
E-REGION
EXPERIMENTAL ARRANGEMENT OF THE DOPPLER PULSATION EXPERIMENT (DOPE)
EISCAT UHF TRANSMITTER /RECEIVER AT TROMSØ
DOPPLER RECEIVER AT EISCAT
DOPPLER TRANSMITTER NEAR EISCAT
EISCAT UHF RECEIVER AT KIRUNA
EISCAT UHF RECEIVER AT SODANKYLÄ


maximum elevation angle
discrete elevation angles
radar

Follow


Hole above radar
tcr_red1
Image
Z_3D_040
15:00:00
8 DEC 2001
Task: PPIVOL_=
PRF:500/375
Max Range:40 km
Proj:RED
Concentric rings


Out-Flowing Deflected Ions
Wake
Boom Tip Radius
Ionospheric Thermal Electron
Ionization Pair
Magnetic Perturbation
Suprathermal Electrons
Plasma/EM Waves
Outflowing Reflected Ions
B
Orbital Motion

Senate Bill S.601 – weather 'mitigation' bill – Sponsored by Senator Kay Bailey Hutchison and ***John Rockefeller***

(did NOT pass in its current form) instead it was put to the Air force "Owning the weather 2025″ program :

Here is the "weather mitigation bill" co-sponsored in congress:

S. 601: Weather Mitigation Research and Development Policy Authorization Act of 2009

http://www.govtrack.us/congress/bill.xpd?bill=s111-601

quote from the bill linked directly above:

"

The following summary was written by the Congressional Research Service, a well-respected nonpartisan arm of the Library of Congress. GovTrack did not write and has no control over these summaries.

Follow

7/22/2009–Reported to Senate amended. Weather Mitigation Research and Development Policy Authorization Act of 2009 -

Section 5 -

Establishes in the Geosciences Directorate of the National Science Foundation (NSF) the Weather Mitigation Research Office to establish and coordinate the national research and development program on weather mitigation described in this Act. Requires the Program to be headed by a Director, who shall be appointed by the Director of the Geosciences Directorate. Instructs the Director of the NSF to coordinate the work of the Program with the Office of Science and Technology Policy (OSTP). Authorizes the Director of the Program to: (1) fund studies, obtain information, and hold workshops necessary to carry out this Act; (2) cooperate with public or private agencies to promote the purposes of this Act; and (3) enter into cooperative agreements with the head of a U.S. department or agency, an appropriate official of a state or political subdivision of a state, or an appropriate official of a private or public agency or organization to conduct research and development (R&D) pertaining to weather mitigation. Creates a Working Group to advise the Program and to make recommendations to the Program concerning administration, research, and other matters.

Section 6 -

Requires the Director of the Program, in consultation with the Working Group, to submit an implementation plan to Congress for the establishment and coordination of the Program. Permits the inclusion in the Program of specified activities related to weather mitigation, including: (1) interdisciplinary R&D and coordination of R&D and activities to improve the understanding of processes relating to planned and inadvertent weather mitigation; (2) coordination with relevant organizations; (3) development, through partnerships among federal agencies, state agencies, and academic institutions, of new technologies and approaches for weather mitigation; and (4) establishment of scholarships and educational opportunities that encourage an interdisciplinary approach to weather mitigation. Requires the Program to promote and fund R&D, studies, and investigations with respect to: (1) improved forecast and decisionmaking technologies for weather mitigation operations; and (2) adaptation and scaling experiments in the efficacy of weather mitigation. Authorizes the Director of the NSF to establish a grant program for the awarding of grants to eligible entities (state agencies, institutions of higher education, and nonprofits that have expertise in the field of weather mitigation and experience working with state agencies) for R&D projects that pertain to weather mitigation.

Section 7 -

Requires the Director to submit biennial reports containing certain information to the President and specified congressional committees.

Section 8 -

Instructs the head of any U.S. department or agency and the head of any other public or private institution receiving research funds from the United States to cooperate with the Director of the Program.

Section 9 -

Directs the OSTP, in support of the implementation plan, to: (1) address relevant programs and activities of the federal agencies and departments that would contribute to the Program; (2) consider and use, as appropriate, reports and studies of federal agencies and departments

Follow

weather modification organizations, and other expert scientific bodies, including a specified National Research Council report; and (3) make recommendations for the coordination of Program activities with weather mitigation activities of other national and international organizations. Requires OSTP, in the support of the biennial reports required from the Director under section 7, to provide specified information.

Section 10 -

Authorizes appropriations. Allows for the acceptance, use, and disposal of gifts or donations of services or property under the Program."

intellicast.com The Authority in Expert Weather
Quick Picks
Calgary
Regina
Kelowna
Vancouver
Seattle
Great Falls
Missoula
Bismar
Billings
Portland

Montreal
Burlington
Portland
Boston
Akron
intellicast.com

- Loop of CONUS Merged Reflectivity Composite (no QC)


Frame Controls:
Thu Dec 1 02:08:16 UTC 2011
na
MD
<10
10-20
20-30
30-40
40-50
50-60
60-70
>70
75+
dBZ
Loop Mode:
Adjust Speed:
Dwell First/Last:
CONUS2 MergedReflectivityComposite 00.00 [2011 12/01 00:34:13 UTC]

Frame No: 19

Follow

- Loop of CONUS Merged Reflectivity Composite (no QC)


Frame Controls:
Thu Dec 1 02:08:16 UTC 2011
na
MD
<10
10-20
20-30
30-40
40-50
50-60
60-70
70-75
75+
dBZ
Loop Mode:
Adjust Speed:
Dwell First/Last:
Frame No: 15
CONUS2 MergedReflectivityComposite 00.00 [2011 12/01 00:14:10 UTC]
script func()


weather.cod.edu/satrad/index.php
Visited dutchsinse's Channel - Y... Intellicast - Interactive ... Earthquakes today | Ear... DUTCHSINSE = SIN... New Folder
College of DuPage
NeXt Generation Weather Lab
StormReady
what does this mean?
Home
Academics
Weather Analysis Tools
Storm Chasing Program
Local Weather
FAQs
Satellite and Radar
Visible
Infrared
Water Vapor
Radar
Hemispheric Products
Regional Products
2km Products
Visible
Infrared
Water Vapor
Radar
1km Products
NEXRAD Sites
Start
Set Animation Speed
Rock
Zoom
Show
No Enhancement
Refresh
Roads & Rivers
Counties
Lat & Lon
dBZ
NEXRAD 1KM MOSAIC 1 DEC 11 00:40


weather.cod.edu/cgi-bin/radarloop.pl?station=ICT&product=BREF1&loopdir=brefs
Frame Controls:
24-Image Loop from the College of DuPage
Loop Mode:
Animate Frames:
Dwell First:
Dwell Last:
Adjust Speed:
Advance One:
Frame No: 11
Omit Frame
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
Base reflectivity (Dbz)
ICT – WICHITA KS – BREF1
0032Z 1 DEC 11
Md=cl Rng=124(0.5) El=0.5 Mx=54
-90
-24
-16
-8.0
0
8.0
16
24

Follow


intellicast.com
Quick Picks
Huron
Brookings
Mankato
Owatonna
Mitchell
Worthington
Fairmont
Spencer
Mason City
Yankton
Storm Lake
Sioux City
Norfolk
Carroll
intellicast.com


intellicast.com
Quick Picks
Rapid City
Sioux Falls
Cheyenne
North Platte
Omaha
Lincoln
Des
Denver
intellicast.com


Bismarck
Fargo
Duluth
Marquette
Minneapolis
Green Bay
Sioux Falls
Madison
Milwaukee
intellicast.com

————————————————————

Links from R3zn8d:

http://r3zn8d.wordpress.com/2011/11/28/weather-modification-101-100-years-of-cloud-seeding

The Weather Modification Association (WMA)

Association: [Weather Modification Association (WMA)]()

Follow

Members: Full Corporate Roster

Members

Company: WMA – Advanced Radar Corp

Company: WMA – Aero Systems, Inc.

Company: WMA – Aerotec Argentina

Company: WMA – Colorado Water Conservation Board

Company: WMA – Deepwater Chemicals

Company: WMA – Direccion de Agricultura y Contingencias Climaticas (Argentina)

Company: WMA – Droplet Measurement Technologies

Company: WMA – Dynamic Aviation Group, Inc.

Company: WMA – Electronic Systems Developement CC

Company: WMA – General Aviation Applications – 3D s.a.

Company: WMA – Hydro-Tasmania

Company: WMA – Ice Crystal Engineering LLC

Company: WMA – Idaho Power Company

Company: WMA – NASIC/DEKA – US Air Force Wright-Patterson AFB

Company: WMA – North American Weather Consultants, Inc.

Company: WMA – North Dakota Atmospheric Resources Board

Company: WMA – Omni International, LLC
Attn: Tom Papachristou

Company: WMA – Radiometrics Corporation

Company: WMA – RHS Consulting, Ltd

Company: WMA – Sacramento Municipal Util Dist.

Company: WMA – Santa Barbara County Water Agency

Follow

Company: WMA – Snowy Hydro Limited

Company: WMA – Southern California Edison County

Company: WMA – National University of Technology – Mendoza, Argentina

Company: WMA – Utah Division of Water Resources

Company: WMA – Vaisala.com

Company: WMA – Vaisala Oyj

Company: WMA – Vaisala – Veriteq

Company: WMA – Weather Modification, Inc.

Company: WMA – Western Kansas Grndwater Dist 1

Company: WMA – Western Weather Consultants, LLC

Company: WMA – Wyoming Water Development

Texas Weather Modification Association (TWMA)

The Texas Weather Modification Association is associated with the Weather Modication Association (WMA)

Association: www.texasweathermodification.com

Video: Texas Weather Modification Advisory Committee – August 25, 2011

Video: Weather Modification in Texas Admitted As Recent as Aug, 2011

History: www.texasweathermodification.com/History.html

Members

Association: TWMA – West Texas Weather Modification Association

Association: TWMA – Southwest Texas Rain Enhancement Association

Association: TWMA – South Texas Weather Modification Association

Association: TWMA – Panhandle GCD Precipitation Enhancement Program

Association: TWMA - Southern Ogallala Aquifer Rain Program (SOAR)

Association: TWMA – (SOAR) old website – Seeding Operations and Atmospheric Research

Follow

Energy Body

Once you have practiced to this level, you are ready to form the pearl into the Soul Body.



Fig. 8.15 *Energy or Soul Body*

Sorcerers saw that the essence of the universe resembled a matrix of energy shot through by incandescent strands of consciousness or actual awareness. They also 'saw' the essence of the human form. It was not merely an apelike amalgamation of skin and bones, but an egg-shaped ball of luminosity capable of traveling along those incandescent strands to other worlds. (Wagner, Bruce, "You Only Live Twice", *Details*, March, 1994, p.168.)

Just as it is important for the physical body to be strong so we can enjoy optimum health, it is also vital to strengthen the Soul Body so it becomes a sturdy vehicle for our consciousness. Strengthening Chi nourishes our health and spiritual qualities in

Association: TWMA – The Edwards Aquifer

Association: TWMA – Colorado River Municipal Water District – Engineering WXMOD's

Association: TWMA – Trans Pecos Weather Modification Association

Other Companies and Associations

Association: American Society of Civil Engineers

Company: Aquiess / Drake International – Global Rain Project

Company: Aurora Flight Sciences

Institute: Desert Research Institute

Institute: Indian Institute of Tropical Meteorology (CAIPEEX)

Company: Evergreen Aviation: Supertanker

Military

Military: United States Air Force Reserve – Aerial Spray Unit – Youngstown AFB

Company: WMA – NASIC/DEKA – US Air Force Wright-Patterson AFB

Weather Modification Projects in the USA

NOAA – Project Stormfury – Hurricane mitigation study
Source: noaa.gov

> ***Project STORMFURY*** *was an ambitious experimental program of research on hurricane modification carried out between 1962 and 1983. The proposed modification technique involved artificial stimulation of convection outside the eyewall through seeding with silver iodide. The invigorated convection, it was argued, would compete with the original eyewall, lead to reformation of the eyewall at larger radius, and thus, through partial conservation of angular momentum, produce a decrease in the strongest winds.*
> *Since a hurricane's destructive potential increases rapidly as its strongest winds become stronger, a reduction as small as 10% would have been worthwhile. Modification was attempted in four hurricanes on eight different days. On four of these days, the winds decreased by between 10 and 30%, The lack of response on the other days was interpreted to be the result of faulty execution of the seeding or of poorly selected subjects.*
>
> *These promising results came into question in the mid-1980s because observations in unmodified*

Follow

hurricanes indicated:

1. *that cloud seeding had little prospect of success because hurricanes contained too much natural ice and too little supercooled water*
2. *that the positive results inferred from the seeding experiments in the 1960s stemmed from inability to discriminate between the expected results of human intervention and the natural behavior of hurricanes.*


STORMFURY Hypothesis
Seeding
Old Eyewall Weakening as New Grows
New Eyewall Dominant

US Drought Monitor Live Link:

Follow


U.S. Drought Monitor
February 28, 2012
Valid 7 a.m. EST
S
L
SL
Intensity:
D0 Abnormally Dry
D1 Drought - Moderate
D2 Drought - Severe
D3 Drought - Extreme
D4 Drought - Exceptional
Drought Impact Types:
Delineates dominant impacts
S = Short-Term, typically <6 months (e.g. agriculture, grasslands)
L = Long-Term, typically >6 months (e.g. hydrology, ecology)
The Drought Monitor focuses on broad-scale conditions. Local conditions may vary. See accompanying text summary for forecast statements.
http://droughtmonitor.unl.edu/
USDA
National Drought Mitigation Center
NOAA
Released Thursday, March 1, 2012
Author: Mark Svoboda, National Drought Mitigation Center

TWMA Projects Map: Weather Modification Association Project Locations Map

NOAA Spreadsheets – Weather Modification Programs in the USA.

PDF: 2011 NOAA Weather Modification Programs 11WXMOD5 as of July 7, 2011.pdf

PDF: 2010 NOAA Weather Modification Programs 10WXMOD5.pdf

PDF: 2009 NOAA Weather Modification Programs 09WXMOD5.pdf

PDF: 2008 NOAA Weather Modification Programs 08WXMOD5.pdf

PDF: 2006 NOAA Weather Modification Programs 06WXMOD5.pdf

PDF: 2005 NOAA Weather Modification Programs 05WXMOD5.pdf

PDF: 2004 NOAA Weather Modification Programs 04WXMOD5.pdf

Follow


Vegetation Drought Response Index
Complete
October 17, 2011
Vegetation Condition
Extreme Drought
Severe Drought
Moderate Drought
Pre-Drought
Near Normal
Unusually Moist
Very Moist
Extremely Moist
Out of Season
Water
National Drought Mitigation Center
USGS
RMA

NEO Aqua/MODIS Aerosol Particle Size (Click to Enlarge)


percentage of small particles
0
20
40
60
80
100

Studies and Papers – (Local Mirror) – (Original File)

Commercial Cloud-Seeding

Article: [(Research Application Program NCAR) 2004 Worldwide Precipitation Enhancement]()

Follow

Projects

RUSSIA
CANADA
UNITED STATES
MEXICO
KAZAKHSTAN
MONGOLIA
CHINA
INDIA
N. KOREA
S. KOREA
JAPAN
PHILIPPINES
INDONESIA
AUSTRALIA
NEW ZEALAND
BRAZIL
COLOMBIA
PERU
BOLIVIA
CHILE
ARGENTINA
ALGERIA
LIBYA
EGYPT
SUDAN
CHAD
NIGER
MALI
MAURITANIA
ANGOLA
SOMALIA
SAUDI ARABIA
IRAN
TURKEY
SOUTH AFRICA
MADAGASCAR
NORTH PACIFIC OCEAN
NORTH ATLANTIC OCEAN
SOUTH PACIFIC OCEAN
SOUTH ATLANTIC OCEAN
INDIAN OCEAN


Sketch Map of Weather Modification Operations in China in 2002
No
Precipitation enhancement
Precipitation enhancement and hail suppression

Follow


2008-09 Wyoming King Air flight pattern
(elevation range: 2000-3661 m)
□ active AgI generator sites
Elk Mtn
41.6
41.4
41.2
prevailing wind
I-80
radiosonde launch site
Saratoga
Kennedy Peak
Cedar Creek radiometer
MB03
Turpin Reservoir
seeding plume
① ② ③ ④ ⑤
MB04
Mullison Park
MB05
Barret Ridge
Medicine Bow Peak
Snowy Range
130
Centennial
along-wind flight leg
70
230
Encampment
constant flight level (14 kft)
106.8
106.6
106.4
106.2
106.0

Shifting and Creating Clouds from Nothing using Radio Waves

PDF: Aquiess RAINAID – African Drought Relief using Electromagnetic Cloud Shifting – (.COM)


Signals are launched from ground based servers, to adjust flight paths of weather systems
1
2
3
Moving Weather System
Ground Stations

Aquiess has intervened in over 40 rainfall projects, many on massive scale.

Follow

Cloud Ionizer – Creating Clouds from Scratch Using Radio Waves

Article: Have scientists discovered how to create downpours in the desert?


Moisture condenses around the charged dust. Eventually this turns to cloud which produces the rain
3
2
Negatively charged ions rise with the hot air and attract dust
1
Ionisers produce charged particles into the desert air

NASA J-2X Doghouse: Cloud Forming Rocket!

> *How much steam does this make? Well, if you ever have the opportunity to see a J-2X engine test, bring an umbrella. A full duration test will make enough steam to make its own rain cloud in the sky.*
>
> *Source: blogs.nasa.gov*

Follow

Evidence of Electromagnetic Radiation used to Modify Weather Patterns in the USA

Video: Nexrad & HAARP: Undeniable Weather Control Connection

Video: Nexrad Ring Evidence: Nationwide Weather Manipulation

Video: How Nexrad HAARP Works: Turning Natural Storms into Biblical Floods

Official NOAA Video: NEXRAD: Eye to the Sky

NOAA Website: National Oceanic and Atmospheric Administration

Weather Modification Patents – Overwhelming Evidence

1891 PDF: 0462795 – Method of Producing Rain-Fall

1914 PDF: 1103490 – Rain Maker (balloon images)

1917 PDF: 1225521 – Protection From Poisonous Gas in Warfare

1920 PDF: 1338343 – Process and apparatus for the production of intense artificial clouds, fogs, or mists

1924 PDF: 1512783 – Composition for dispelling fogs

1927 PDF: 1619183 – Process of producing smoke clouds from moving aircraft

1928 PDF: 1665267 – Process of producting artificial fogs

1932 PDF: 1892132 – Atomizing attachment for airplane engine exhausts

1933 PDF: 1928963 – Electrical system and method (for spraying chemtrails)

1934 PDF: 1957075 – Airplane spray equipment

1936 PDF: 2045865 – Skywriting apparatus

1936 PDF: 2052626 – Method of dispelling fog (MIT)

1937 PDF: 2068987 – Process of dissipating fog

1939 PDF: 2160900 – Method for vapor clearing

Follow

1941 PDF: [2232728 – Method and composition for dispelling vapors]

1941 PDF: [2257360 – Desensitized pentaerythritol tetranitrate explosive]

1946 PDF: [2395827 – Airplane spray unit (US. DEPT. OF AGRICULTURE)]

1946 PDF: [2409201 – Smoke-producing mixture]

1949 PDF: [2476171 – Smoke screen generator]

1949 PDF: [2480967 – Aerial discharge device]

1950 PDF: [2527230 – Method of crystal formation and precipitation]

1951 PDF: [2550324 – Process for controlling weather]

1951 PDF: [2570867 – Method of crystal formation and precipitation (GENERAL ELECTRIC)]

1952 PDF: [2582678 – Material disseminating apparatus for airplanes]

1952 PDF: [2591988 – Production of tio2 pigments (DUPONT)]

1952 PDF: [2614083 – Metal chloride screening smoke mixture]

1953 PDF: [2633455 – Smoke generator]

1954 PDF: [2688069 – Steam generator]

1955 PDF: [2721495 – Method and apparatus for detecting minute crystal forming particles suspended in a gaseous atmosphere (GENERAL ELECTRIC)]

1956 PDF: [2730402 – Controllable dispersal device]

1957 PDF: [2801322 – Decomposition chamber for monopropellant fuel]

Follow

1958 PDF: 2835530 – Process for the condensation of atmospheric humidity and dissolution of fog

1959 PDF: 2881335 – Generation of Electrical Fields (HAARP – FOR RE-CHARGING CLOUDS!)

1959 PDF: 2903188 – Control of tropical cyclone formation

1959 PDF: 2908442 – Method for dispersing natural atmospheric fogs and clouds

1960 PDF: 2962450 – Fog dispelling composition (SEE REFERENCES)

1960 PDF: 2963975 – Cloud seeding carbon dioxide bullet

1961 PDF: 2986360 – Aerial insecticide dusting device

1962 PDF: 3044911 – Propellant system

1962 PDF: 3056556 – Method of artificially influencing the weather

1964 PDF: 3120459 – Composite incendiary powder containing metal coated oxidizing salts

1964 PDF: 3126155 – Silver Iodide Cloud Seeding Generator (MAIN COMMERCIAL INGREDIANT)

1964 PDF: 3127107 – Generation of Ice-Nucleating Crystals

1964 PDF: 3131131 – Electrostatic mixing in microbial conversions

1965 PDF: 3174150 – Self-focusing antenna system (HAARP)

Follow

this life and builds a strong Soul Body to carry us forth into the "afterlife" (which is, paradoxically, the here and now). We begin to strengthen the Soul Body through what is called in Taoist Inner Alchemy "the Inner Elixir". It is called the Inner Elixir because we are working with the energies already within our own body and converting them into elixir-like healing essences. Through the meditation practices of the Microcosmic Orbit and the Fusion of the Five Elements, we detoxify, nourish, and integrate the physical body, the Energy Body and the emotions.

Always begin by doing the Fusion of the Five Elements practice to clean out the negative emotions.

Chant the eight forces and form the collection points. Let the Pakua spinal around the physical body.

Condense the pearl and practice the Creation Cycle, Thrusting Channels and Belt Channels.

Run the pearl in the Microcosmic Orbit, and control its movement with the senses.

Move the pearl to the perineum. Inhale in short sips, drawing in ten percent of the lungs' capacity, while gently pulling up the anus. Inhale up to the navel, then to the heart.

Inhale up to the crown. Swallow your saliva (imagine swallowing upward,) and exhale forcefully to open the crown and shoot the pearl out.

Practice moving the pearl up to one foot, two feet, three feet, four feet, five feet, and six feet above your head. Go out only as far as you are able to maintain control of the pearl.

Relax the senses, and form the Soul Body.

Run the pearl in the Microcosmic Orbit in the physical body. Open the crown, transfer the Microcosmic pathway into the Soul Body above the head.

Form another pearl in the cauldron, and shoot the pearl into the Soul Body.

Circulate the pearl through the Microcosmic Orbits in both the physical and energy bodies together.

Extend the Thrusting Channels up into the Soul Body.

Practice all the Belt Channels up through the head, or down through the soles, into the Soul Body. Spiral all the pakuas around the Soul Body like a space ship.

Continue to practice until you are in full control of the Soul Body.

***Note*:** You can also form a Soul Body below you by thrusting the pearl through the soles of the feet into the ground.



March 16, 1965 P. J. SFERRAZZA ETAL 3,174,150
SELF-FOCUSING ANTENNA SYSTEM
Filed June 29, 1962 5 Sheets-Sheet 1

FIG.1.

INVENTORS
PETER J. SFERRAZZA
RICHARD L. SMEDES
BY
S.C. Yeaton
ATTORNEY

1966 PDF: [3257801 – Pyrotechnic composition comprising solid oxidizer, boron and aluminum additive and binder]

1966 PDF: [3234357 – Electrically Heated Smoke Producing Device]

1966 PDF: [3274035 – Metallic Composition For Production of Hydroscopic Smoke]

1967 PDF: [3300721 – Means For Communication Through a Layer of Ionized Gases (HAARP)]

1967 PDF: [3313487 – Cloud Seeding Apparatus]

1967 PDF: [3338476 – Heating Device For Use With Aerosol Containers]

1968 PDF: [3410489 – Automatically Adjustable Airfoil Spray System With Pump]

1969 PDF: [3429507 – Rainmaker]

1969 PDF: [3430533 – Aircraft Dispensor Pod Having Self-Sealing Ejection Tubes]

1969 PDF: [3432208 – Fluidized Particle Dispenser (US AIR FORCE)]

1969 PDF: [3437502 – Titanium Dioxide Pigment Coated with Silica and Aluminum (DUPONT)]

1969 PDF: [3441214 – Method and Apparatus for Seeding Clouds]

Follow

1969 PDF: 3445844 – Trapped Electromagnetic Radiation Communications System (HAARP – RAYTHEON)

1969 PDF: 3456880 – Method Of Producing Precipitation From The Atmosphere

1970 PDF: 3517512 – Apparatus for Suppressing Contrails

1970 PDF: 3518670 – Artificial Ion Cloud

1970 PDF: 3531310 – Production of Improved Metal Oxide Pigment

1970 PDF: 3534906 – Control of Atmospheric Particles (DOW CHEMICAL CO)

1970 PDF: 3545677 – Method of Cloud Seeding

1971 PDF: 3564253 – System And Method For Irradiation Of Planet Surface Areas (SPACE SOLAR MIRRORS)

1971 PDF: 3587966 – Freezing Nucleation

1971 PDF: 3601312 – Methods of Increasing The Likelihood oF Precipatation By The Artificial Introduction Of Sea Water Vapor Into The Atmosphere Winward Of An Air Lift Region

1971 PDF: 3608810 – Methods of Treating Atmospheric Conditions

1971 PDF: 3608820 – Treatment of Atmospheric Conditions by Intermittent Dispensing of Materials Therein

1971 PDF: 3613992 – Weather Modification Method

1971 PDF: 3630950 – Combustible compositions for generating aerosols, particularly suitable for cloud modification and weather control and aerosolization process

Follow

1972 PDF: 3647710 – Method for Dispersing Fog with Phosphate Salt Compositions

1972 PDF: 3653383 – Algin Sponge and Process Therefor

1972 PDF: 3659785 – Weather Modification Utilizing Microencapsulated Material (GROSS)

1972 PDF: 3666176 – Solar Temperature Inversion Device

1972 PDF: 3677840 – Pyrotechnics Comprising Oxide of Silver For Weather Modification Use

1972 PDF: 3690552 – Fog Dispersal

1973 PDF: 3722183 – Device For Clearing Impurities From The Atmosphere

1973 PDF: 3769107 – Pyrotechnic Composition For Generating Lead Based Smoke (ARE YOU SERIOUS?)

1974 PDF: 3784099 – Air Pollution Control Method

1974 PDF: 3785557 – Cloud Seeding System

1974 PDF: 3795626 – Weather Modification Process

1974 PDF: 3808595 – Chaff Dispensing System

1974 PDF: 3813875 – Rocket Having Barium Release System to Create Ion Clouds In The Upper Atmopsphere (NASA)

1974 PDF: 3835059 – Methods of Generating Ice Nuclei Smoke Particles For Weather Modification And Apparatus Therefore

1974 PDF: 3835293 – Electrical Heating Aparatus For Generating Super Heated Vapors

Follow

1975 PDF: 3877642 – Freezing Nucleant

1975 PDF: 3882393 – Communications System Utilizing Modulation of The Characteristic Polarization of The Ionosphere (HAARP – US NAVY)

1975 PDF: 3896993 – Process For Local Modification of Fog And Clouds For Triggering Their Precipitation And For Hindering The Development of Hail Producing Clouds

1975 PDF: 3899144 – Powder contrail generation

1975 PDF: 3902934 – Gas generating compositions

1976 PDF: 3940059 – Method of fog dispersion

1976 PDF: 3940060 – Vortex Ring Generator

1976 PDF: 3990987 – Smoke Generator

1976 PDF: 3992628 – Countermeasure system for laser radiation

1976 PDF: 3994437 – Broadcast dissemination of trace quantities of biologically active chemicals

1977 PDF: RE29142 – Combustible compositions for generating aerosols, particularly suitable for cloud modification and weather control and aerosolization process

1977 PDF: 4035726 – Method of controlling and/or improving high-latitude and other communications or radio wave surveillance systems by partial control of radio wave et al (HAARP – CORNELL UNIV.)

1977 PDF: 4042196 – Method and apparatus for triggering a substantial change in earth characteristics and measuring earth changes

1978 PDF: 4096005 – Pyrotechnic cloud seeding composition

1978 PDF: 4111911 – Method of hardening liquid resols

1978 PDF: 4129252 – Method and apparatus for production of seeding materials

1979 PDF: 4141274 – Weather modification automatic cartridge dispenser

1979 PDF: 4167008 – Fluid bed chaff dispenser

Follow

1981 PDF: 4269637 – High-performance MHD solid gas generator

1982 PDF: 4347284 – White cover sheet material capable of reflecting ultraviolet rays

1982 PDF: 4362271 – Procedure for the artificial modification of atmospheric precipitation as well as compounds with a dimethyl sulfoxide base for use in carrying out said procedure

1983 PDF: 4402480 – Atmosphere modification satellite (SPACE)

1983 PDF: 4412654 – Laminar microjet atomizer and method of aerial spraying of liquids

1983 PDF: 4415265 – Method and apparatus for aerosol particle absorption spectroscopy

1983 PDF: 4373391 – Relative humidity sensitive material

1984 PDF: 4470544 – Method of and Means for weather modification

1984 PDF: 4475927 – Bipolar Fog Abatement System

1986 PDF: 4600147 – Liquid propane generator for cloud seeding apparatus

1987 PDF: 4633714 – Aerosol particle charge and size analyzer

1987 PDF: 4643355 – Method and apparatus for modification of climatic conditions

1987 PDF: 4653690 – Method of producing cumulus clouds

1987 PDF: 4684063 – Particulates generation and removal

1987 PDF: 4686605 – Method and apparatus for altering a region in the earth's atmosphe

Follow

ionosphere, and/or magnetosphere (HAARP – RAYTHEN)

1987 PDF: 4704942 – Charged Aerosol (ANTI-AIRBORNE BIOLOGICAL WARFARE AGENT)

1987 PDF: 4712155 – Method and apparatus for creating an artificial electron cyclotron heating region of plasma (HAARP – RAYTHEON)

1988 PDF: 4744919 – Method of dispersing particulate aerosol tracer

1988 PDF: 4766725 – Method of suppressing formation of contrails and solution therefor

1989 PDF: 4829838 – Method and apparatus for the measurement of the size of particles entrained in a gas

1989 PDF: 4836086 – Apparatus and method for the mixing and diffusion of warm and cold air for dissolving fog

1989 PDF: 4873928 – Nuclear-sized explosions without radiation (HAARP – RAYTHEON)

1990 PDF: 4948257 – Laser optical measuring device and method for stabilizing fringe pattern spacing

1990 PDF: 4948050 – Liquid atomizing apparatus for aerial spraying

1990 PDF: 4959559 – (United States) Electromagnetic or other directed energy pulse launcher

You just can't make this shit up……

Follow

BACKGROUND OF THE INVENTION – 4959559



The invention relates generally to transmission of pulses of energy, and more particularly to the propagation of localized pulses of electromagnetic or acoustic energy over long distances without divergence.

As the Klingon battle cruiser attacks the Starship Enterprise, Captain Kirk commands “Fire photon torpedoes”. Two darts or blobs of light speed toward their target to destory the enemy spaceship. Stardate 1989, Star Trek reruns, or 3189, somewhere in intergalactic space. Fantasy or reality. The ability to launch localized packets of light or other energy which do not diverge as they travel great distances through space may incredibly be at hand.

Following the pioneering work of J. N. Brittingham, various groups have been actively pursuing the possibility that solutions to the wave equation can be found that allow the transmission of localized, slowly decaying pulses of energy, variously described as electromagnetic missiles or bullets, Bessel beams, transient beam fields, and splash pulses. These efforts have in common the space-time nature of the solutions being investigated and their potential launching mechanisms, pulse-driven antennas.

Solutions to Maxwell’s equations follow naturally from these scalar wave equation solutions. Such electromagnetic pulses, characterized by their high directionality and slow energy decay, are called electromagnetic directed-energy pulse trains (EDEPTs). They are a step closer to a classical description of a photon, a finite-energy solution of Maxwell’s equations that exhibits a wave/particle duality. The corresponding acoustic pulses, which are solutions of the scalar wave equation, are called ADEPTs

1991 PDF: 4999637 – Creation of artificial ionization clouds above the earth (HAARP – RAYTHEON)

1991 PDF: 5003186 – Stratospheric Welsbach seeding for reduction of global warming

1991 PDF: 5005355 – Method of suppressing formation of contrails and solution therefor

1991 PDF: 5038664 – Method for producing a shell of relativistic particles at an altitude above the earths surface (HAARP – RAYTHEON)

1991 PDF: 5041760 – Method and apparatus for generating and utilizing a compound plasma

Follow

configuration

1991 PDF: 5041834 – Artificial ionospheric mirror composed of a plasma layer which can be tilted (HAARP – RAYTHEON)

1991 PDF: 5056357 – Acoustic method for measuring properties of a mobile medium

1991 PDF: 5059909 – Determination of particle size and electrical charge

1992 PDF: 5104069 – Apparatus and method for ejecting matter from an aircraft

1992 PDF: 5110502 – Method of suppressing formation of contrails and solution therefor

1992 PDF: 5148173 – Millimeter wave screening cloud and method

1992 PDF: 5156802 – Inspection of fuel particles with acoustics

1992 PDF: 5174498 – Cloud seeding

1993 PDF: 5245290 – Device for determining the size and charge of colloidal particles by measuring electroacoustic effect

1994 PDF: 5286979 – Process for absorbing ultraviolet radiation using dispersed melanin (WOW!)

1994 PDF: 5296910 – Method and apparatus for particle analysis

1994 PDF: 5327222 – Displacement information detecting apparatus

1994 PDF: 5357865 – Method of cloud seeding

1994 PDF: 5360162 – Method and composition for precipitation of atmospheric water



In a (NON-MILITARY) cloud top seeding mission, an aircraft releases Silver Iodide flares (1), supercooled liquid water is converted into ice particles (2), releasing latent heat, increasing buoyancy, and invigorating cloud updrafts (3).

1995 PDF: 5383024 – Optical wet steam monitor

Follow

1995 PDF: 5425413 – Method to hinder the formation and to break-up overhead atmospheric inversions, enhance ground level air circulation and improve urban air quality

1995 PDF: 5434667 – Characterization of particles by modulated dynamic light scattering

1995 PDF: 5441200 – Tropical cyclone disruption (HURRICANES!)

1996 PDF: 5486900 – Measuring device for amount of charge of toner and image forming apparatus having the measuring device

1996 PDF: 5556029 – Method of hydrometeor dissipation (clouds)

1997 PDF: 5628455 – Method and apparatus for modification of supercooled fog

1997 PDF: 5631414 – Method and device for remote diagnostics of ocean-atmosphere system state

1997 PDF: 5639441 – Methods for fine particle formation

1998 PDF: 5762298 – Use of artificial satellites in earth orbits adaptively to modify the effect that solar radiation would otherwise have on earth's weather (SPACE)

1999 PDF: 5912396 – System and method for remediation of selected atmospheric conditions (Solar Powered Blimp to Ionize Clouds)

1999 PDF: 5922976 – Method of measuring aerosol particles using automated mobility-classified aerosol detector

1999 PDF: 5949001 – Method for aerodynamic particle size analysis

1999 PDF: 5984239 – Weather modification by artificial satellites (SPACE)

Follow


U.S. Patent
Nov. 16, 1999
Sheet 5 of 7
5,984,239
PREVIOUS CYCLE
NEXT CYCLE
CURRENT CYCLE
dT
Ta
Tb
Tc
INITIATE CYCLE AT t < Ta
COMPLETE CYCLE AT t < Tb
5i
MODIFY EST LOCAL AVE WEATHER COND AT DISCRETE TIME & LOC PTS IN (Tb, Tc)
FROM 5t
5g
SPECIAL DESIRED WEATHER REQUEST AT TIME & LOC PTS IN (Tb, Tc)
5h
DESIRED LOCAL WEATHER COND AT DISCRETE TIME & LOCATION POINTS IN (Tb, Tc)
DESIGNATED REMOTE SENSING DEVICES (RSDs) UPDATES 1n'
5b
UPDATE INTEGRATED WEATHER / SEs MATH MODEL
TO 5a
DESIGNATED SATELLITE ENGINES (SEs) STATUS UPDATES 1q'
5d
FROM 5c
EXTRAPOLATE LOCAL WEATHER AT DISCRETE TIME PTS IN (Ta, Tc)
DATA UPDATES TO/FROM OTHER GROUND CONTROL STATION (GCSs) 1z
5e
INITIALIZE SEARCH IN LIBRARY FOR SEs' TASK ASSIGNMENTS SATISFY DESIRED WEATHER COND. ASSIGNMENTS INCLUDE:
- SEs ENERGY BEAM CHARACTERISTICS
-GUIDANCE LAW (AAPs)
-SEs GROUPING
1x
1y
INTEGRATED WEATHER /SWMS MATH MODEL
5p
5f
ENCYCLOPEDIA OF SEs PERFORMANCES:
- WEATHER COND.
- SEs GROUPING
- ENERGY BEAM CHARACTERIS
- GUIDANCE LAW
INDIVIDUAL MATH MODELS
5q
HISTORICAL WEATHER STATISTICS
5i
5k
PERFORM PARALLEL SIMULATIONS TO EVALUATE SEs TASK ASSIGNMENTS
5c
ESTIMATED SEs' NEXT ASSIGN'T IN (Tb, Tc)
METEOROLOGY ENCYCLOPEDIA
5s
5n
5m
SELECT & TRANSMIT OPT SEs' TASK ASSIGNMENTS TO CORRESPONDING SEs
ENCYCLOPEDIA OF MEDIA AND ENERGY BEAMS INTERACTIONS
5t
5t
EST. DESIRED LOCAL WEATHER AT DISCRETE PTS IN (Tb, Tc)
1r'
5v
EVALUATE SEs' PERFORMANCE AND STORE
1r' 1r' 1r'
SE#1, SE#2, SE#N
5a
A GCS LIBRARY

FIG. 5

2000 PDF: [6025402 – Chemical composition for effectuating a reduction of visibility obscuration, and a detoxifixation of fumes and chemical fogs in spaces of fire origin]

2000 PDF: [6030506 – Preparation of independently generated highly reactive chemical species]

2000 PDF: [6034073 – Solvent detergent emulsions having antiviral activity]

2000 PDF: [6045089 – Solar-powered airplane]

2000 PDF: [6056203 – Method and apparatus for modifying supercooled clouds]

2000 PDF: [6110590 – Synthetically spun silk nanofibers and a process for making the same]

2001 PDF: [6263744 – Automated mobility-classified-aerosol detector]

2001 PDF: [6281972 – Method and apparatus for measuring particle-size distribution]

2001 PDF: [6315213 – Method of Modifying the Weather]

2002 PDF: [6382526 – Process and apparatus for the production of nanofibers]

2002 PDF: [6408704 – Aerodynamic particle size analysis method and apparatus]

Follow

Spirit Body

Once you are well in control of the Soul Body, you are ready to form the Spirit Body.



Fig. 8.16 *Spiritual Being*

2002 PDF: 6412416 – Propellant-based aerosol generation devices and method (US ARMY)

2003 PDF: 6520425 – Process and apparatus for the production of nanofibers

2003 PDF: 6539812 – System for measuring the flow-rate of a gas by means of ultrasound

2003 PDF: 6553849 – Electrodynamic particle size analyzer

2003 PDF: 6569393 – Method and device for cleaning the atmosphere

2011 PDF: 7965488 – Methods of removing aerosols from the atmosphere (Ionizing Antennas)

Weather Modification Laws

Court Cases

Article: 2006 – Weather Modification Law in the USA

Summary of court cases and principles of tort liability for cloud seeding, including both drought or flood allegedly caused by cloud seeding.

Reporting of Weather Modification Activities

Text: 2011 – 15 USC CHAPTER 9A – WEATHER MODIFICATION ACTIVITIES OR ATTEMPTS; REPORTING REQUIREMENT

Global Geoenginnering Related Laws

PDF: Congressional Research Service (crs.gov) – Geoengineering: Governance and Technology Policy – (.ORG)

United Nations Framework Convention on Climate Change (UNFCCC)

The UNFCC opened for signature in 1992 and entered into force in 1994. The United States became a party to the UNFCCC in 1992. Under the UNFCCC, parties are required to: (1) gather and share information on greenhouse gas (GHG) emissions, national policies, and best practices, (2) launch national strategies for addressing GHG emissions and adapting to expected impacts, and (3) cooperate in preparing for adaptation to the impacts of climate change. Parties are also obligated to cooperation and exchange information on technologies, and potential economic and social consequences of response strategies, as well as to give full consideration to actions to meet the needs and concerns of developing countries

Follow

that may be adversely affected by, inter alia, the implementation of measures to respond to climate change.

Kyoto Protocol (the Protocol)

The Kyoto Protocol opened for signature in 1997 and entered into force in 2005. The United States has signed but not become a party to the Kyoto Protocol.103 The Protocol supplements the UNFCCC by committing its high income parties to legally binding reductions in emissions of greenhouse gases through 2012.

Copenhagen Accord (the Accord)

Unlike the Kyoto Protocol and the UNFCCC, the 2009 Copenhagen Accord is a non-binding political agreement. Nevertheless, the United States has indicated its intent to associate with the Copenhagen Accord. The Accord asks Annex 1 Parties of the UNFCCC to set their own individual emissions targets for 2020 and to measure, report, and verify their progress towards these targets pursuant to guidelines adopted by the UNFCCC Conference of the Parties (“COP”), and non-Annex 1 Parties to develop “mitigation actions” for the reduction of GHG emissions, though not emissions targets, and measure, report, and verify their implementation of these actions.

United Nations Convention on the Law of the Sea (UNCLOS)

UNCLOS opened for signature in December 1982 and entered into force on November 16, 1994. Despite participating in the UNCLOS negotiations, the United States declined to sign the final agreement and has not become a party since then, although it views many provisions of UNCLOS as customary international law that it was already obligated to follow. UNCLOS establishes a legal regime governing activities on, over, and under the world’s oceans and defines countries’ jurisdictions over, and rights of access to, the oceans and their resources. Article 194 of the UNCLOS imposes a duty on its parties to take, individually or jointly, measures that are necessary to prevent, reduce, and control pollution of the marine environment from any source. The UNCLOS defines pollution as any human-driven introduction of substances or energy into the marine environment that results or is likely to result in deleterious effects such as harm to living resources and marine life, hazards to human health, hindrance to marine activities, or impairment of sea water quality. This provision could have significance for a geoengineering project that pollutes the marine environment, by land, sea, or air. In addition to, arguably, mandating that a country not engage in that activity, once a geoengineering project resulted in the pollution of the


Sun
4 Together, many droplets diffuse sunlight and make a gray cloud whiter.
3 The droplets or salt crystals, if dried, suck up moisture and grow, reflecting more sunlight.
2 A super-fine mist of seawater is sprayed and lifted by warm air into the cooler cloud-forming region at an altitude of 500 to 1,000 feet.
Warm air
Seawater
1 Spraying devices are mounted on specially designed ships.

Follow

ocean environment, Article 194 would impose a duty on the member country responsible for that pollution to control and limit its spread. Article 192 of the UNCLOS imposes a general obligation on countries to protect and preserve the marine environment. These provisions could be implicated by ocean fertilization and some other geoengineering activities if they have a negative effect on the marine ecosystem. Large-scale ocean fertilization projects could also implicate several UNCLOS provisions, including Article 56, and 238 through 241 on marine scientific research.

London Convention on the Prevention of Marine Pollution by Dumping of Wastes and Other Matter (London Convention)and London Protocol

The London Convention was opened for signature in December 1972 and entered into force in August 1975. The London Protocol was agreed to in 1996 as a means of modernizing and eventually replacing the London Convention. The United States became a party to the London Convention in 1974, but it has not become a party to the London Protocol. Contracting parties pledge to take all possible steps to prevent the pollution of the sea by the dumping of substances that are liable to create hazards to human health, harm living resources and marine life, or interfere with other legitimate uses of the sea.112 However, ocean fertilization and other geoengineering projects that entail the deliberate disposal of substances into the sea might not implicate the London Convention's prohibitions on dumping if they are deemed placed into the sea "for a purpose other than the mere disposal thereof, if not contrary to the aim of the Convention."113 Nevertheless, the parties have recently considered amendments and resolutions to these agreements to address some geoengineering technologies more explicitly. For example, the 2006 amendments to the London Protocol provide guidance on the means by which sub-seabed geological sequestration of carbon dioxide can be conducted, stating that carbon dioxide streams may only be considered for dumping if (1) disposal is into a sub-seabed geological formation; (2) the substances dumped consist overwhelmingly of carbon dioxide; and (3) no other wastes or matter were added to them for the purpose of disposing of them. Two years later, in 2008, the parties adopted Resolution LC-LP.1,114 agreeing that ocean fertilization research activities do not to constitute dumping under the London Convention and Protocol.

Convention on Biological Diversity (CBD)

The CBD opened for signature in June 1992 and entered into force in December 1993. The United States has signed but has not become a party to the CBD. The key principle of the CBD is

Follow

that countries have both the sovereign right to exploit their own resources pursuant to their own domestic policies and the responsibility to ensure that activities within their control do not cause damage to the environment of other states or to areas beyond the limits of national jurisdiction.117 Under Article 8, parties must establish a system and guidelines for the selection of protected areas where special measures need to be taken to conserve biological diversity.118 They must also, to the extent possible and appropriate, rehabilitate and restore degraded ecosystems and promote the recovery of threatened species.119 Perhaps most importantly for geoengineering projects, they must regulate, manage, or control the risks associated with the use and release of living modified organisms which are likely to have adverse environmental impacts and must prevent the introduction of, control, or eradicate alien species that threaten ecosystems, habitats, or species.120 These requirements could constrain if not prohibit certain geoengineering projects that involve releasing living organisms, such as algae, into new, open ecosystems to sequester carbon. More specifically, in 2008 the Ninth Meeting of the Conference of the Parties to the CBD (COP) noted the work of the London Convention and the London Protocol regarding ocean fertilization and requested that its own Parties act to ensure that ocean fertilization activities do not take place until either there is adequate scientific basis on which to justify such activities or the activities are small-scale scientific research studies within coastal waters.

Convention on the Prohibition of Military or Other Hostile Use of Environmental Modification Techniques (ENMOD or the Convention)

ENMOD opened for signature in May 1977 and entered into force on October 5, 1978. The United States became a party to ENMOD in 1979. ENMOD's aim is to prohibit the military or any other hostile use of environmental modification techniques which have widespread, long-lasting or severe effects as the means of destruction, damage, or injury to any party. The Convention defines the term "environmental modification techniques" as any technique for changing—through the deliberate manipulation of natural processes—the dynamics, composition, or structure of the Earth, including its biota, lithosphere, hydrosphere, atmosphere, or outer space. This definition may encompass certain geoengineering activities. However, the Convention further states that the provisions of the Convention do not hinder the use of environmental modification techniques for peaceful purposes, such that parties to the Convention may undertake to facilitate, and have the right to participate in, the fullest possible exchange of scientific and technological information on the use of environmental modification techniques

Follow

for peaceful purposes.

Convention on Long-Range Transboundary Air Pollution (CLRTAP or the Convention)

CLRTAP opened for signature in 1979 and entered into force on March 16, 1983. The United States became a party to the Convention in 1979. Contracting parties commit themselves to limiting, and to gradually preventing and reducing their discharges of air pollutants and thus to combating the resulting transboundary pollution. Long-range transboundary air pollution is defined by the Convention as the human introduction of substances or energy into the air which have deleterious effects on human health, the environment, or material property in another country, and for which the contribution of individual emission sources or groups of sources cannot be distinguished.130 It is uncertain which geoengineering activities CLRTAP would regulate, or how such regulation would be implemented.

Vienna Convention for the Protection of the Ozone Layer (the Convention)

The Vienna Convention for the Protection of the Ozone Layer was opened for signature in 1985 and entered into force in 1988. The Convention, along with the Montreal Protocol on Substances that Deplete Ozone Layer, which was opened for signature in 1987 and entered into force in 1989, aims to control the production and consumption of the most commercially and environmentally significant ozone-depleting substances.132 The United States became a party to the Vienna Convention in 1986. It is also a party to the Montreal Protocol (since 1988) and has agreed to all four amendments to the Protocol. Parties to these agreements, within their capabilities, are expected to: (1) cooperate to better understand and assess the effects of human activities on the ozone layer and the effects of the modification of the ozone layer; (2) adopt appropriate measures and cooperate in harmonizing appropriate policies to control the activities that are causing the modification of the ozone layer; (3) cooperate in formulating measures for the implementation of the Convention; and (4) cooperate with competent international bodies to implement the Convention.133 Certain stratospheric aerosol injection technologies for geoengineering, to the extent that they pose a risk to the ozone layer, have the potential to implicate many of the phase-out provisions of the Convention and the protocols.

Article: 2001 – H.R.2977 Space Preservation Act – Library of Congress

Short History of the Space Preservation Act – Wikipedia

Dennis Kucinich introduced the first Space Preservation Act, on October 2, 2001, with no cosponsors. The bill was designed to “preserve the cooperative, peaceful uses of space for the benefit of all humankind.” The bill was

Follow

referred to the House Science, the House Armed Services, and the House International Relations committees. The bill DIED in committee (April 9, 2002) because of an unfavorable executive comment received from the Department of Defense.

PDF: United States Air Force – Aerial Application of Pesticides – (.MIL)

Texas Department of Licensing and Regulation

Weather Modification and Control – Agriculture Code

Texas Weather Modification Law

Texas Weather Modification Rules

Chemtrails – Cloud Seeding Software

T.I.T.A.N. (Thunderstorm Identification Tracking Analysis and Nowcasting)

TITAN Website

Download TITAN for LINUX

AGRICULTURE DEFENSE COALITION – WEATHER MODIFICATION LINKS

5AZ 2010 March 10, 2010 Colin Andrews Australia Weather Changes+Strange Radar Patterns.pdf

5A 2009 Modification of Cirrus Clouds to Reduce Global Warming Published OCT 30, 2009 Report.pdf

5A 1972 Weather Modification Nixon Adm. Kissinger May 2, 1972 National Security #165.pdf

5A 1975 Multiple Weather Modification Experiments – Simpson May 1975.pdf

5A 1975 Weather Modification 1975 Carbon Black-Solar Absorbtion AMS Abstract.pdf

5A 1975 Weather Modification Lansford 1975.pdf

5A 1983 Weather Modification 1983 Statistical Analysis Experiments.pdf

Follow

5A 1992 Weather Modification Planned Inadvertent 1992 Policy Statement AMS.pdf

5A 1993 U.S. Patent 4766725 January 12, 1993 Solar Energy Collector+Reradiation Apparatus for Localized Climate Control.pdf

5A 1995 Hail Suppression 1995 Report AGU.pdf

5A 1995 Weather Modification 1995 Summary and Conclusions.pdf

5A 1995 Weather Modification References 1995 AGU Report.pdf

5A 1995 Weather Modification Report 1995 AGU.pdf

5A 1995 Weather Modification Summary + Conclusions 1995 Report AGU.pdf

5A 1997 Weather Modification + Cloud Seeding Status Report University of Colorado 1989-1997.pdf

5A 1997 Weather Modification Status Report 1989-1997.pdf

5A 2001 Hail Weather January 20, 2001 Graphics.pdf

5A 2002 NASA Theory on Precipitation+Lightning – Weather Predictions November 27, 2002 Science Daily News.pdf

5A 2002 Weather Modification Assocation JWM Vol 35 Abstracts.pdf

5A 2003 Aluminum Oxide+Alumina-Silicate+Iron Oxide March 2003 Cirrus Cloud Study NOAA.pdf

5A 2003 Ionogenics Announces Corporate Launches New Weather Modification Technology February 25, 2003.pdf

5A 2004 NASA Press Release april 27, 2004 Clouds Caused by Aircraft Exhaust May Warm Climate-Studies.pdf

5A 2004 Weather References 2004 Search.pdf

5A 2006 Atmospheric Scientists Link Lightning to Ice Particles in Clouds October 1, 2006 Science Daily News.pdf

5A 2006 Physicists Study Lightening by Using Rockets Connected to Ground Wires April 1, 2006 Science Daily News.pdf

5A 2006 Scientists Link Lightning to Ice Particles in Clouds OCT 1, 2006 Science Daily News.pdf

5A 2006 Weather Modification – Thunderstorms+Tornadoes Satellites 2006 Abstract

Follow

Microwaves.pdf

5A 2007 33 NASA January 12, 2007 Northern Lights Ressearch Enters Final Frontier NASA-Canada UC Berkeley.pdf

5A 2007 ENN News August 25, 2007 Noctilucent Polar Ice Clouds Change Climate.pdf

5A 2007 Weather Modification Publications 2007.pdf

5A 2007 Weather Modification Tools White Paper August 2007 CILEX.pdf

5A 2008 Bolts of Blue Lighting Thrusting Upward March 30, 2008 Mechanism Man-Made Questions SD News.pdf

5A 2008 Weather+Climate Engineering March 2008 Perturbed Clouds in Climate System.pdf

5A 2008 Weather Mitigation Search December 22, 2008 Storming Media.pdf

5A 2008 Weather Modification 2008 Book.pdf

5A 2008 Weather Modification Books Abstract Search AMS 2008.pdf

5A 2008 Weather Modification Publications 2008.pdf

5A 2009 Lightning Flow Upward from Top of Storm August 24, 2009 Photograph.pdf

5A 2009 NISSE Ionospheric Water Experiment March 12, 2009 NISSE 2009.pdf

5A 2009 NISSE March 12, 2009 Ionoshperic Water Experiment via Rocket Seeding.pdf

5A 2009 NISSE Weather Modification Experiment Nordic March 10, 2009 Ionospheric Sounding Rocket-Water.pdf

5A 2009 U.S. Department of Defense Studies – Wind + Weather – Whiteman 2009 Battelle+DOE.pdf

5A 2009 Weather Modification DRI November 2009 Website Programs-Funding.pdf

5A 2009 Weather Modification Search July 2009 Solar Page 2.pdf

5A 2009 Weather Modification Search July 2009 Solar Page 3.pdf

5A 2010 33 NASA Search Cloud Dispersal March 1, 2010 Page 1.pdf

5A 2010 33 NASA Search Cloud Dispersal March 1, 2010 Page 2.pdf

5A 2010 33 NASA Search Cloud Seeding March 1, 2010 Page 1.pdf

Follow

5A 2010 33 NASA Search Cloud Seeding March 1, 2010 Page 2.pdf

5A 2010 33 NASA Search Weather Modification March 1, 2010 10 Pages of Publications.pdf

5A 2010 Making Rain Lasers Physics World May 2, 2010 Firing Powerful Laser Pulses Through Humid Air CA Stimulate Cloud Formation.pdf

5BZ 2008 No Comment CA San Gabriel Mountains Wikipedia 2008 Information.pdf

5B 1993 Weather Modification Cold Fogbusters Arcata California Tests American Heritage Miller.pdf

5B 1996 U.S. Navy UCAR Fog Study in California Press Release December 6, 1996 Why is this Fog Considered a Threat.pdf

5B 1997 Abstract Mendocino County, CA Studies Abstract 1997.pdf

5B 1998 Abstract Mendocino County, CA Abstract 1998 Navy Seasonal Variability.pdf

5B 1998 Abstract Mendocino County, CA Foggy Cloud I Project Abstract 1970.pdf

5B 2003 Weather + Trees Ukiah Daily Journal 2003.pdf

5B 2005 Weather Modification Programs Jan 5, 2005 Western States.pdf

5B 2008 California Weather Abstract Search 2008 Pentagon Reports.pdf

5B 2008 CA San Gabriel Mountains 2008 Tree Picture + Location of New Weather Mod Program.pdf

5B 2008 Cloud Graphics March 2008 Abstract U.S. Navy – California.pdf

5B 2008 Hail Cobb Mountain Lake County CA May 4, 2008.pdf

5B 2008 LATimes NOAA Cloud Seeding Schematic June 16, 2008.pdf

5B 2008 Siskiyou Daily News December 16, 2008 CA Cloud Seeding PGE.pdf

5B 2008 Weather Modification California December 24, 2008 ScrippsNews PG&E.pdf

5B 2008 Weather Modification July 28, 2008 KTVU 2 Oakland, San Francisco, CA.pdf

5B 2008 Weather Modification LATimes June 16, 2008 Los Angeles, CA.pdf

5B 2008 Weather Modification LATimes NOAA Cloud Seeding Schematic June 16, 2008.pdf

5B 2008 Weather Modification LA San Gabriel Mountains 2008.pdf

Follow

5B 2008 Weather Modification PGE Program Mount Shasta News November 5, 2008.pdf

5B 2008 Weather Modification Shasta+Siskiyou Counties CA Dec 23, 2008 Redding News.pdf

5B 2009 Cloud Seeding Plans in California PGE 2009 Defeated in Siskiyou County.pdf

5B 2009 County of Los Angeles Weather Modification Project July 2009.pdf

5B 2009 Weather Modification Programs DRI Website November 2009.pdf

5B 2009 Weather Modification U.S. + Worldwide November 2009 Website UCAR wxmodvisuals.pdf

5B 2010 Coastal Water Cycle Branch Earth Systems Laboratory March 6, 2010 http___www.esrl.noaa.pdf

5B 2010 NOAA+CA ARB Proposing Joint Field Study of Atmospheric Processes over CA+Eastern Pacific Coastal Region in 2010.pdf

5B 2010 NOAA Coastal Processes Team March 6, 2010 http___www.esrl.noaa.pdf

5B 2010 NOAA March 6, 2010 Hydrometeorological Processes Team California http___www.esrl.noaa.pdf

5B 2010 NOAA March 6, 2010 Hydrometeorology Testbed Operations http___hmt.noaa.pdf

5B 2010 PG+E Plans to Use Cloud Seeding Northern California Without Any Government Regulations June 7, 2010 Alternet News .pdf

5B 2011 PG&E Responses to Questions Regarding Cloud Seeding Lake Almanor Basin Plumas County, CA SEPT 13, 2011 Weather Modification.pdf

5C 1970 Cloud Modification Project Foggy Cloud I Abstract August 1970 Humboldt County, CA U.S. Navy.pdf

5C 2000 Farmers Skeptical of Weather Mod Programs AP News 2000.pdf

5C 2004 NOAA HMT 2004 Russian River Watershed HMT Testbed March 6, 2010 http___www.esrl.noaa.pdf

5C 2005 Weather Modification 16th Annual Conference 2005 Planned.pdf

5C 2008 What About Weather Modification Doswell 2008.pdf

5C 2009 NOAA HMT West October 13-14, 2009 Case Study Event California+Nevada.pdf

5C 2010 National Weather Service Daily Western U.S. Weather March 6, 2010

Follow

Stage One

Be aware of the Four Pakuas in each center and spiral them around the physical body and the energy body.

1. Begin to form the spirit body after doing the Soul Body practice. Leave the Soul Body above the crown. Form another pearl at the cauldron, and run the Creation Cycle.
2. Form the pearl from compassion energy, a pearl that is more blue and gold than the Soul Body pearl.
3. Move this pearl in the Microcosmic Orbit. Bring it down to the perineum.
4. Inhale in small sips, and pull up the anus. Inhale the pearl to the navel; then to the heart; and to the crown.
5. Inhale again, and swallow up. Exhale forcefully to open the crown, and project the pearl to the perineum of the Energy Body.
6. Exhale, and send the pearl to the heart of the Soul Body. Exhale again, and send the pearl above the crown of the Soul Body.
7. Move the pearl up and down approximately twelve inches (30 centimeters) above the crown of the Soul Body. Then gradually extend the pearl further up in one foot (30 centimeters) increments. Practice until you are able to move the pearl up and down six feet above the Energy Body.
8. Condense the pearl. Condense the Soul Body. Bring both pearls back to the cauldron of the physical body.

Stage Two

1. Repeat steps (1) to (7) above, and run the Microcosmic Orbit in the physical and energy bodies.
2. Transfer the Microcosmic Orbit from the Soul Body into the Spirit Body, and then run the three Microcosmic Orbits together. As an alternative, you can run the Microcosmic Orbit as one large channel incorporating all three bodies.
3. Extend the Thrusting Channels to the Spirit Body.
4. Extend the Belt Channels to the Spirit Body.
5. Finish by condensing the energy of both the Soul and Spirit Bodies into a pearl. Pull the pearl into the physical body.
6. Collect the energy at the cauldron, and practice Chi Massage.

http___www.wrh.noaa.pdf

5C 2010 NOAA Boundary Layer Profiler Network March 6, 2010 Instrumentation.pdf

5C 2010 NOAA CALJET to PACJET to HMT March 6, 2010 Website.pdf

5C 2010 NOAA Hydrometeorology Testbed HMT-West California 2010 Operations http___www.esrl.noaa.pdf

5C 2010 Space + Planetary Press Releases March 12, 2010 AAAS EurekAlert.pdf

5D 2003 NOAA M.D. Particles CSU Study Cirrus Clouds Aluminum Oxide-Alumina Silicate-Iron Oxide-Nanoscale.pdf

5D 2008 Chemists Use Edible Antifreeze to Make Smoother Ice Cream July 1, 2008 Weather Modification Questions.pdf

5D 2008 Weather Modification Disease Health Problems NYTimes September 2, 2008.pdf

5D 2008 Weather Modification Is Cloud Seeding Harmful Micou – 2008.pdf

5E 1927 U.S. Patent 01619183 March 1, 1927 Page 1 Smoke Cloud Production Method.pdf

5E 1927 U.S. Patent 01619183 March 1, 1927 Page 2.pdf

5E 1927 U.S. Patent 01619183 March 1, 1927 Page 3.pdf

5E 1927 U.S. Patent 01619183 March 1, 1927 Page 4 Smoke Production.pdf

5E 1969 U.S. Patent Weather Modification Fog Dispersing Method Compositions.pdf

5E 1971 U.S. Patent 3564253 System Method Irradiation of Planet Surface Areas FEB 16, 1971 for Heating-Weather Control-Illumination.pdf

5E 1971 U.S. Patent 3,613,992 Weather Modification October 19, 1971 Urea Potassium Nitrate-Potassium Nitrite-Ammonium Nitrate.pdf

5E 1971 Weather Modification Inadvertant 1971 Man-Made Precipitation Changes.pdf

5E 1977 U.S. Patent RE29142 Feb 22, 1977 Aluminum Link Combustible Cloud Weather Modification-Aluminum-Magnesium-Perchlorates.pdf

5E 1987 U.S. Patent 4686605 Eastlund August 11, 1987 Methods for Altering a Region of Earth Atmosphere etc.pdf

5E 1994 U.S. Patent 5360162 NOV 1, 1994 Barium Lead Copper Perchlorate Fuels Weather Modification Methods+Composition.pdf

Follow

5E 1998 U.S. Patent 5762298 June 9, 1998 Satellites Modify Solar Radiation Weather.pdf

5E 1999 U.S. Patent 5984239 November 16, 1999 Weather Modification by Artificial Satellites.pdf

5E 2003 U.S. Patent History of Aerosols – July 30, 2003 Weather Related Technology.pdf

5E 2005 Weather Modification Hail Metrics 2005 Insurance Companies.pdf

5E 2005 Weather Modification Microwaves July 3, 2005 Boston Globe.pdf

5E 2007 U.S. Patents Weather Modification Search 42 Patents 2006.pdf

5E 2008 Weather Modification Eastlund Patents 2008 HAARPWEATHER.pdf

5E 2009 BIOMETRICA Weather Modification Experiments May 2009.pdf

5E 2010 Bernard Eastlund, PH.D February 25, 2010 Bibliography.pdf

5E 2010 U.S. Patent 7714767 May 11, 2010 Storm Top Detection+Prediction Radar System.pdf

5FZ 2005 Cuba Weather Modification Technology October 20, 2005.pdf

5F 1960 Weather Modification-Artificial Precipitation China Abstract 1960.pdf

5F 1995 Weather Modification 1995 Hail Suppression North Dakota.pdf

5F 1996 Canada Weather Modification Programs Began 1996 Alberta.pdf

5F 1999 Weather Modification Experiments 1999 Mexico and Colorado.pdf

5F 2003 Australia Cloud Seeding Landline Article August 8, 2003 by Lee.pdf

5F 2004 Weather Modification BBC 2004 Rainfall Augmentation.pdf

5F 2004 Weather Modification Cloud Seeding + Interlinking Rivers BBC Water Issues 2004.pdf

5F 2006 Weather Modificaiton Precipitation Enhancement Winter Clouds 2006.pdf

5F 2006 Weather Modification Inc 2006 Alberta, Canada Weather Modification.pdf

5F 2007 China Makes Artificial Snowfall April 19, 2007.pdf

5F 2007 China Weather Modification Chemical Diatomite 2007.pdf

5F 2008 China Weather Modification August 24, 2008.pdf

5F 2008 Weather Alteration April 23, 2008 The Denver Post.pdf

Follow

5F 2008 Weather Modification Heggli Innovative Hydrology 2008.pdf

5F 2008 Weather Modification Rockets December 16, 2008 Telegraph.co.uk.pdf

5F 2008 Weather Modification Using Rockets Russia Bulgaria.pdf

5F 2009 China Dispersing Abstract Search May 2009 Page 1 = 335 Abstracts Total.pdf

5F 2009 China Dust From China Circles Earth 2009 Telegraph UK News.pdf

5F 2009 Climate Change Bolivia December 14, 2009 NYTimes by Rosenthal.pdf

5F 2009 Weather Modification Australia 2004-2009 Precipitation Enhancement.pdf

5F 2009 Weather Modification China October 1, 2009 Reuters News Chemicals+Technology.pdf

5F 2009 Weather Modification China Program Bloomberg News NOV 12, 2009 – Government Induced Snowfall.pdf

5F 2009 Weather Modification China Reuters Page 2 October 1, 2009.pdf

5F 2009 Weather Modification China Yahoo News November 11, 2009 Snowstorm Debate.pdf

5F 2009 Weather Modification Moscow October 17, 2009 Yahoo News Winter Without Snow.pdf

5F 2010 Australia BOM Bureau of Meteorology Website March 13, 2010.pdf

5F 2010 Australia February 9-23, 2010 BOM Responses to Colin Andrews Inquiries.pdf

5F 2010 Canadian National Climate Data + Information Archive March 14, 2010 Website.pdf

5F 2010 China Dams-Weather Modification Responsible for Drought in Southern China-Thailand Many Questions NYTimes April 1, 2010.pdf

5F 2010 Weather Office Radar Imagery Website Ontario Canada March 16, 2010.pdf

5F Weather Modification Mexico Washington Post.pdf

5GC 1971Cloud Modification Abstract November 15, 1971 External Heat Sources.pdf

5GC 1971 Cloud Modification Nuclei Warm Fog Abstract January 1971 U.S. Army.pdf

5GC 1972 Cloud Dissipaton Artificial Abstract May 28, 1972 Wright-Patterson AFB.pdf

5GC 1972 Cloud + Fog Dissipation Modern Methods Abstract May 28, 1972 Wright-Patterson Air Force Base.pdf

Follow

5GC 1979 Cloud Abstract December 31, 1979 Fuel-Air Explosive Simulation.pdf

5GC 1980 Clouds Blue-Green Kauai Cloud Experiments Abstract July 31, 1980 U.S. Navy.pdf

5GC 1982 Cloud DOD Executive Summary December 22, 1982 Abstract Storming Media Pentagon Reports AFB.pdf

5GC 1987 Clouds Jet Releases Vapor Clouds Abstract December 21,1987 United States Air Force.pdf

5GC 1989 Cloud-Free Lines of Sight Abstract September 30, 1989.pdf

5GC 1998 Clouds Abstract HSI AF Research Lab January 1998.pdf

5GC 2008Clouds, Vapor Abstract Search December 28, 2008 Results 23.pdf

5GC 2008 Clouds Gas Aerosol Reactions Abstract Search December 28, 2008 Results 9.pdf

5GC 2008 Cloud Abstracts December 22, 2008 Storming Media Pentagon Reports – Results 461.pdf

5GC 2008 Cloud Dissipation Abstract Search December 28, 2008 Results 10.pdf

5GC 2008 Cloud + Fog Dissipation Abstract Search December 28, 2008 Results 8.pdf

5GC 2008 Cloud Formation Abstract Seach December 22, 2008 Pentagon Reports-Storming Media-Results 44.pdf

5GC 2008 Cloud Modification Abstract Search December 22, 2008 – Pentagon Reports-Storming Media Results 22.pdf

5GC 2008 Cloud Modification Abstract Search December 28, 2008 Results 22.pdf

5GC 2008 Cloud Production Abstract Search December 28, 2008 Results 16.pdf

5G 1993 Weather Army Battlefield Atmsopherics Conference Abstract 1993 Mitigation.pdf

5G 1997 Jet Contrails Change Climate September 12, 1997 Claire Gilbert.pdf

5G 2001 Jet Contrails Effects September 11-13, 2001 Study.pdf

5G 2002 Weather Hoffman February 2002 Controlling the Global Weather-Jets.pdf

5G 2003 Weather as a Weapon 2003 ABC News.pdf

5G 2004 Weather BBC 2004 Acid Rain + Dying Forests.pdf

5G 2004 Weather Modification Equipment Wing-Tip Ice Nuclei Generators WMI 2004.pd

Follow

5G 2004 WMI Weather Modification, Inc. Airborne Seeding Equip 2004.pdf

5G 2005 Weather Modification Dispersion Fog Mist Apparatus 2005.pdf

5G 2006 NWV First Article January 16, 2006 Rosalind newswithviews article.pdf

5G 2006 NWV First Article January 16, 2006 Rosalind newswithviews article Experimental Weather Modification.pdf

5G 2007 ENN News December 10, 2007 High Cloud Changes Man-Made.pdf

5G 2007 ENN News Spetmeber 29, 2007 Increasing Atmospheric Moisture-Human Activities.pdf

5G 2007 Newswithviews November 2, 2007 Weather Modification Article by Peterson.pdf

5G 2007 Newswithviews November 2, 2007 Weather Modification Coming to Your Neighborhood Soon by Peterson.pdf

5G 2007 NWV August 10, 2007 Weather Modification – Can We Control the Weather by Rosalind.pdf

5G 2008 Nature Editorial June 19, 2008 Weather Modification.pdf

5G 2008 NWV Climate Security Act Sham July 1, 2008 Peterson – in 2010 Defeat U.S. Senate Bill 601.pdf

5G 2008 NWV What Your Meteorologist Are Not Telling You September 6, 2008 Article by Rosalind Peterson.pdf

5G 2008 NWV What Your Meteorologist & Media Are Not Telling You August 18, 2008 Peterson.pdf

5G 2008 Weather Alteration April 23, 2008 The Denver Post-Scientist Aim to Alter Weather.pdf

5G 2008 Weather As A Force Multiplier Abstract Search 2008 Results 5.pdf

5G 2008 Weather Mitigation Search Abstracts Storming Media-Pentagon 2008.pdf

5G 2008 Wind Farms May Affect Weather Systems NYTimes Sept 23, 2008.pdf

5G 2009 NOAA Weather Glossary 2009.pdf

5G 2010 Aquatic Dead Zones Contributing to Climate Change March 12, 2010 Science Daily News.pdf

5G 2010 U.S. Losing Trees FasterThan Other Heavily Forested Nations+Map April 27 2010 USA

Follow

Today News.pdf

5G Cirrus Clouds and Climate McGraw Hill Abstract Research Update.pdf

5HZ 2009 Solar Weather Modification Search July 2009.pdf

5H 1961 Project Storm Fury Page 1 Hurricane 1961 NOAA.pdf

5H 1961 Project Storm Fury Page 2 NOAA Historical Information.pdf

5H 1984 U.S. Patent 5360162 NOV 1, 1994 Barium Lead Copper Perchlorate Fuels Weather Modification Methods+Composition.pdf

5H 1990 US_Congress Operation Popeye Vietnam Weather Modification ENMOD.pdf

5H 1993 DTIC Air War College Abstract Weather Modification The Ultimate Weapon April 1993 U.S. Air Force.pdf

5H 1995 Precipitation Augmentation 1995 AGU Report.pdf

5H 1995 Precipitation Enhancement 1995 Report AGU.pdf

5H 1995 Weather Modfication 1995 References.pdf

5H 1995 Weather Modification Introduction 1995.pdf

5H 1996 Weather Modification Historical Current Research.pdf

5H 1999 AGU News June 12, 1999 Jet Contrails Significant Climate Factor.pdf

5H 1999 AGU News June 21,1999 Jet Contrails Significant Factor in Climate Change NASA.pdf

5H 2000 Controlling the Weather September 13, 2000 Weather Channel.pdf

5H 2002 Jet Contrails Alter Temperature Range 2002 Eureka News August 7, 2002.pdf

5H 2002 Standler Weather Modification History and Law in the U.S.pdf

5H 2002 Weather Modification History Bibliography Standler 2002.pdf

5H 2003 Weather as a Weapon February 17, 2003 ABC News.pdf

5H 2004 AGU Publications 2004.pdf

5H 2006 Weather Modification Bibliography 2006.pdf

5H 2006 Weather Modification Bibliography 2006 A.pdf

5H 2006 Weather Modification History 2006.pdf

Follow

5H 2007 19 DTIC July 30, 2007 Search 1 Military Weather Modification Results 15,665.pdf

5H 2007 19 DTIC July 30, 2007 Search Military Weather Modification Page 3.pdf

5H 2007 Aircraft Water Vapour Trails=Greenhouse Gases-Studies March 23, 2007 Tribune.pdf

5H 2007 BBC.co.uk Contrails (1) January 12, 2007 11 Part Series.pdf

5H 2007 BBC Inside Out Contrails January 12, 2007 Carbon Offsets.pdf

5H 2007 DTIC Defense Technical Information Center-Weather Modification Search July 30, 2007.pdf

5H 2007 DTIC July 30, 2007 Abstract Search Military Weather Modification Page 1.pdf

5H 2007 DTIC July 30, 2007 Abstract Search Military Weather Modification Page 10.pdf

5H 2007 DTIC July 30, 2007 Abstract Search Military Weather Modification Page 11.pdf

5H 2007 DTIC July 30, 2007 Abstract Search Military Weather Modification Page 12.pdf

5H 2007 DTIC July 30, 2007 Abstract Search Military Weather Modification Page 2.pdf

5H 2007 DTIC July 30, 2007 Abstract Search Military Weather Modification Page 3.pdf

5H 2007 DTIC July 30, 2007 Abstract Search Military Weather Modification Page 4.pdf

5H 2007 DTIC July 30, 2007 Abstract Search Military Weather Modification Page 5.pdf

5H 2007 DTIC July 30, 2007 Abstract Search Military Weather Modification Page 7.pdf

5H 2007 DTIC July 30, 2007 Abstract Search Military Weather Modification Page 8.pdf

5H 2007 DTIC July 30, 2007 Abstract Search Military Weather Modification Page 9.pdf

5H 2007 DTIC July 30, 2007 Abstract Seasrch Military Weather Modification Page 6.pdf

5H 2007 NASA MEME Aviation Smog Persistent Jet Contrails 2007.pdf

5H 2008 Weather Abstract Search Storming Media December 22, 2008 Results 1,000.pdf

5H 2008 Weather AMS Statements 1990 to August 16, 2008.pdf

5H 2008 Weather History NYTimes Sept 16, 2008 Climate Change.pdf

5H 2008 Weather Modification History and References 2008.pdf

5H 2009 Weather+Climate 2009 www.mrsciguy.com weather.html.pdf

Follow

5H 2009 Weather Modification History Channel Program July 21, 2009.pdf

5H 2010 DTIC Acronyms March 21, 2010.pdf

5H 2010 DTIC Acronyms March 21, 2010 DOD Dictionary+Abbreviations.pdf

5IA 2010 33 NASA Ionization Search March 1, 2010 Page 1.pdf

5IA 2010 33 NASA Ionization Search March 1, 2010 Page 2.pdf

5IZ 2008 Ionized Trails – HG2p1 2008 Abstract Diffusion Rates.pdf

5IZ 2009 C NASA Abstract 1997JGR-September 15, 2009 The Effect of Electrical Forces.pdf

5I 1932 Ionization of Air by y-Rays 1932 Abstract APS.pdf

5I 1962 DTIC December 12, 1962 Transmission of Information-Artificially Ionized Atmosphere.pdf

5I 1993 Finite Element Simulation FES Technique Studies Chemical Modification Ionosphere 1993.pdf

5I 2003 Ionization of the Atmosphere 1994-2003 Abstract.pdf

5I 2004 Ionizing Radiation Fact Sheet EPA 2004.pdf

5I 2005 Clemson University 2005 Atmospheric Physics Experiments-Ionization.pdf

5I 2005 January 11, 2005 Artificial Atmospheric Ionization-Window for Weather Modification Paper_88063.pdf

5I 2005 Weather Modification Artificial Ionization Methods-Solar Radiation March 27, 2005 India Daily News.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 1 – Atomospheric Ionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 1 – Auroral Ionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 1 – Autoionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 1 – Electron Ionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 1 – Flame Ionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 1 – Gas Ionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 1 – Ion Production Rates.pdf

Follow

5I 2010 33 NASA Ionization Search March 1, 2010 Page 1 – Nonequilibrium Ionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 1 – Photoionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 1 – Surface Ionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 2 – Atmospheric Ionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 2 – Auroral Ionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 2 – Autoionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 2 – Electron Ionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 2 – Flame Ionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 2 – Gas Ionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 2 – Ion Production Rates.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 2 – Nonequilibrium Ionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 2 – Photoionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 2 – Surface Ionization.pdf

5I 2010 33 NASA Ionization Search March 1, 2010 Page 3 – Surface Ionization.pdf

5I 2010 33 NASA Ionization Weather Modification Search March 1, 2010 Page 1.pdf

5I 2010 33 NASA Ionization Weather Modification Search March 1, 2010 Page 2.pdf

5I 2010 33 NASA Ionization Weather Modification Search March 1, 2010 Page 3.pdf

5I 2010 33 NASA March 1, 2010 Ionization Radiation Environments-Search.pdf

5I 2010 Lasers Could Trigger Downpours on Demand May 4, 2010 Physicists Already Tested This Method.pdf

5I 2010 NASA Ionization Search March 1, 2010 Page 1 – Atmospheric Ionization.pdf

5I 2010 NASA Ionization Search March 1, 2010 Page 2 – Atmospheric Ionization.pdf

5I 2010 U.S. Air Force Aircraft Ionizing Doses+Dose Rates from Radioactive Clouds+Fallout Abstract April 1976.pdf

5I 2010 U.S. Patent 4999637 Creation of Artificial Ionization Clouds Above the Earth March 12, 1991.pdf

Follow

5I 2010 Weather Modification Artificial Ionization 2008 Note Graphic.pdf

5I 2010 Weather Modification Artificial Ionization Methods March 27, 2005 India Daily News.pdf

5I 2010 Weather Modification Artificial Ionization Methods-Solar Radiation March 27, 2005 India Daily News.pdf

5I 2010 WHO Non-Ionizing Radiation March 9, 2010.pdf

5J 1977 U.S. Patent RE29142 Feb 22, 1977 Aluminum Link Combustible Cloud Weather Modification-Aluminum-Magnesium-Perchlorates.pdf

5J 2000 Mexico Weather Modification Salt Experiments Mexico Kerr 2000.pdf

5J 2001 Weather Control Cloud Removal Powder BBC 2001.pdf

5J 2004 WMI Airborne Seeding Equip 2004 Weather Modification Inc.pdf

5J 2005 Weather Modification Technologies 2005 DeFelice New Seeding Materials.pdf

5J 2008 World Markets + Weather Modification SynEnergy Forum May 28-31, 2008 Greece.pdf

5J 2010 Artificial Atmospheric Ionization-Potential Windwo for Weather Modification 2005 Abstract 88063[1].pdf

5J 2010 Google Search March 10, 2010 Charged Particles-Weather Modification Page 1.pdf

5J 2010 Google Search March 10, 2010 Charged Particles-Weather Modification Page 2.pdf

5J 2010 Google Search March 10, 2010 Charged Particles-Weather Modification Page 3.pdf

5J 2010 Google Search March 10, 2010 Charged Particles-Weather Modification Page 4.pdf

5K 1969 Wisconsin Cloud Boundary Modification Abstract Wisconsin April 1969.pdf

5K 1972 South Dakota Weather Modification Produced Flooding South Dakota 1972.pdf

5K 1972 South Dakota Weather Modification Program September 1972.pdf

5K 1974 South Dakota Weather Modification South Dakota 1974 Farhar.pdf

5K 1974 South Dakota Weather Modification South Dakota Farhar Abstract 1974.pdf

5K 1996 Mexico Weather Modification Experiments in Mexico UCAR News Release July 3, 1996.pdf

5K 1997 Minnesota Weather Modification Minnesota 1997 Statutes.pdf

Follow

Chapter 9
Fusion as a Bridge

In the overall structure of the Universal Tao, the Fusion Practices serve as a bridge between the basic preparatory practices such as the Inner Smile, the Healing Sounds, the Microcosmic Orbit, Healing Love, Tao Yin, Iron Shirt Chi Kung, Cosmic Chi Kung, Bone Marrow Nei Kung, Tai Chi and the Higher Inner Alchemy Practices of Kan and Li.

The Fusion Practices are traditionally considered as the core of internal alchemy, as they focus on the transformation of emotional energies, contained in the major organs of the body, as centers and fields of energy which resonate, each with their particular frequencies, with the energies and forces of the universe.

Through a process of balancing negative and positive energies (Fusion of the Five Elements), the growth of positive energies (Cosmic Fusion) and the opening of meridians to enhance the circulation of internal energies of the body and make it receptive for outside energies (Fusion of the Psychic Channels), the body gradually becomes more open. Thereby the self-healing process, initiated in the basic practices, is further enhanced.

Once the strength and health of the body have been restoried so that it can serve as a vessel for the forces of the universe and is in a position to process them, it is ready for the higher alchemy in the Kan and Li practices. In these Kan and Li practices the physical body can then give birth to the energy body. Once this has taken place the person is ready to give birth to the spirit body, also called the Light or Rainbow body.

Fusion as a Journey of Self-Transformation

In the Fusion Practices, the body and its path routes are not only cleansed and opened, so that the energy from within and from outside can flow with more power and ease. Also the energy flows in the body are qualitatively raised. Thus the self healing and regenerative capacity of the body, already initiated in the basic practices is further enhanced. As a result, the body’s health and vitality receive a new boost and it grows in strength. At the same time, it becomes more able to absorb and process the various forces and energies from the universe, the cosmos and nature.

5K 2000 Kansas Weather Control Programs Farmers Skeptical 2000.pdf

5K 2001 Mexico Weather Modification in Mexico Study UCAR Press Release January 16, 2001.pdf

5K 2001 Oklahoma Weather Modification 2001.pdf

5K 2001 Oklahoma Weather Modification Oklahoma 2001 Newsletter.pdf

5K 2004 North DakotaWeather Modification PDA-Based Documentation NDARB 2004.pdf

5K 2004 Utah Weather Modification, Inc. Utah Propane Seeding Experimentation 2003-2004.pdf

5K 2005 State of Washington Weather Modification 2005 Document Canada.pdf

5K 2005 Wyoming Cloud Seeding December 2005.pdf

5K 2005 Wyoming Weather Modification Wyoming 2005 Live Science 5 Year Project.pdf

5K 2006 Colorado Brown Snow Colorado Drought February 2006.pdf

5K 2006 Kansas Weather Modification Program Summary October 30, 2006.pdf

5K 2006 Nebraska Weather Modification Nebraska Authorized 2006.pdf

5K 2006 Wyoming Cloud Seeding Program Begins 2006 UCAR News.pdf

5K 2006 Wyoming Snowpack Weather Modification February 2006.pdf

5K 2007 Wyoming Weather Modification Wymoing Star Tribune March 16, 2007.pdf

5K 2008 Arizona Weather Modification + History + Arizona WRRC University of Arizona 2008.pdf

5K 2008 Guardian.co.uk January 28, 2008 Worldwide Water Shortages-21 Century Oil=Water.pdf

5K 2008 Idaho Weather Modification Idaho October 25, 2008 Standard Journal Article.pdf

5K 2008 Idaho Weather Modification October 25, 2008 Standard Journal Idaho.pdf

5K 2008 Kansas Weather Modification – Weather History Kansas 2008 USGS.pdf

5K 2008 South Dakota Weather Modification Atmospheric Studies 2008 South Dakota.pdf

5K 2008 Utah Weather Modification Utah 2008.pdf

Follow

5K 2008 Wyoming Weather Modification NYTimes June 3, 2008.pdf

5K 2008 Wyoming Weather Modification + Techniques + Fact Sheet 2008 NCAR.pdf

5K 2008 Wyoming Weather Modification Wyoming March 16, 2008 U.S. Forest Service.pdf

5K 2008 Wyoming Weather Modification Wyoming Star Tribune March 16, 2008.pdf

5K 2009 Colorado University of Colorado 2009 Climate Change + Drought Report.pdf

5K 2009 Nevada Weather modification Nevada DRI Website August 17, 2009 Nevada.pdf

5K 2009 Nevada Weather Modification Program Budget Cuts Nevada MSNBC August 17, 2009.pdf

5K 2009 North Dakota AMS May 2009 Cloud Seeding + Crop Insurance.pdf

5K 2009 North Dakota Weather Modification North Dakota 2002 Kucera + Wise.pdf

5K 2009 Utah+Wyoming Water Issues in the News-U.S. Army Corps of Engineers Pipeline 2009.pdf

5K 2009 Wyoming Weather Modification Questions NYTimes January 9, 2009 Snowfall+Rains.pdf

5K 2010 Arizona, Flagstaff Leads Snowfall Total February 2010 Arizona Daily Sun News.pdf

5K 2010 Colorado NOAA Western Water -The Climate Report Team March 17, 2010-Weather Modification.pdf

5LZ 2005 U.S. Senate Bill 517 2005 Weather Modification – Senator Kay Bailey Hutchison-Texas-No Senate Vote in 2005.pdf

5LZ 2006 U.S. Senate Bill 517 November 2006 – U.S. Senator Kay Bailey Hutchison-Texas No Senate Vote in 2006.pdf

5L 1972 Weather Modification Nixon Adm. Kissinger May 2, 1972 National Security #165.pdf

5L 1975 Canadian + United States Weather Treaty 1975.pdf

5L 1980 Convention Prohibition Understandings ENMOD Treaty 1980.pdf

5L 1995 Weather Modfication 1995 References.pdf

5L 2005 NASA The Difference Between Weather and Climate February 1, 2005 Definitions.pdf

5L 2006 Jet Contrail Picture of Interest – Weather Modification 2006.pdf

Follow

5L 2007 U.S. Senate Bill 1807 Weather Mitigation Research Act 2007.pdf

5L 2007 U.S. Senate Bill 931 National Hurricane Research Act 2007.pdf

5L 2008 U.S. Senate Bill 2192 Climate Security Act NYTimes May 28, 2008.pdf

5L 2009 Coastal State Climate Change Planning Act April 2, 2009 H.R. 1905 Text Capps CA.pdf

5L 2009 Weather Glossary.pdf

5L 2009 Weather Modification Law Chapter 15 USC 9A January 5, 2009 Reporting Requirements.pdf

5L 2010 Important Letter to Senator Hutchison U.S. Senate Bill 517 Letter 2005 www.legislative.noaa.gov U.S. Senate Bill 601 in 2010.pdf

5L 2010 Letter Applies to 2010 Senate Bill 601 – U.S. Senate Bill 517 Letter 2005 www.legislative.noaa.gov.pdf

5L 2010 U.S. House Legislation H.R. 1905 Coastal State Climate Change Planning Act 2010.pdf

5L 2010 U.S. Senate Weather Mitigation Bill 601 All Actions+Sponsors+Summary.pdf

5L 2010 U.S. Senate Weather Mitigation Bill S601 All Congressional Actions March 8, 2010.pdf

5L 2010 Weather Modification Acitivies – Report Requirements January 2010 with NOAA.pdf

5M 2003 Coal Climate Problems Science Daily News December 10, 2003.pdf

5M 2004 MONSANTO Weather Modification 2004.pdf

5N 2003 BBC News August 11, 2003 Floods-Hospitals.pdf

5N 2003 Tree Health-Weather Ukiah Daily Journal January 23, 2003.pdf

5N 2004 NASA Clouds and Smoke – Smoke May Cause Cloud Supression July 17, 2004.pdf

5N 2005 U.S. Navy NRL Study Finds Space Shuttle Exhaust is Source of Mysterious Clouds in Antarctica July 6, 2005.pdf

5N 2007 ENN News August 25, 2007 Noctilucent Polar Ice Clouds Change Climate.pdf

5N 2007 ENN News December 10, 2007 High Cloud Changes Man-Made.pdf

5N 2007 ENN News December 16, 2007 Saharan Dust-Chilling Effect North Atlantic.pdf

5N 2008 Curious Cloud Formations Linked to Recent Earthquakes New Scientist April 11, 2008.pdf

Follow

5N 2008 Epidemiologists Study Connection Between Thunderstorms-Asthma Attacks SEPT 1, 2008.pdf

5N 2008 Idaho Snow Storms Near Utah October 13, 2008 Idaho Statesman.pdf

5N 2008 Idaho Unusual Snow October 11, 2008 Idaho Statesman.com.pdf

5N 2008 Mississippi Weather Report December 2008 Rare Snow.pdf

5N 2008 NASA Joanne Simpson Weather Modification-Studies.pdf

5N 2008 Scientists Confirm Jet Stream are Shifting April 17, 2008 Could the Shift be from HAARP Alterations.pdf

5N 2008 Weather NYTimes June 16, 2008 Midwest Floods Food Crops.pdf

5N 2008 Weather Stalled Systemes NYTimes June 15, 2008 Flooding.pdf

5N 2009 U.S. Navy NRL Monitors in Real-Time Space Weather+Coastal Ocean Environemtn SEPT 10, 2009.pdf

5N 2009 Weather Related Food Shortages November 19, 2009 Pumpkins-Illinois+Midwestern States.pdf

5N 2010 Volcano Eruption in Iceland Will Change Climate+Pollute the Air NYTimes April 15, 2010.pdf

5NH 2006 Heat Burst Minnesota July 16-17, 2006 – Drying Thunderstorm-Winds.pdf

5NH 2006 Heat Burst NOAA Hastings NE June 20, 2006 Website Information.pdf

5NH 2006 Heat Burst-The Weather Channel Definition Dr. Greg Forbes May 4, 2006.pdf

5NH 2008 Heat Burst in Nebraska June 26, 2008 – Earlier Report in 2006.pdf

5NH 2008 Heat Burst NW Midland June 17, 2008 Temperature Spiked 97 Degrees – West Texas News.pdf

5NH 2011 Heat Burst Damage KWCH 12 Eyewitness News June 9, 2011 Wichita Kansas.pdf

5NH 2011 Heat Burst Definition American Meteorological Society Website June 10, 2011 Glossary.pdf

5NH 2011 Heat Burst Sends Temperature in Wichita Soaring to 102 Degrees in Middle of Night Kansas City Star News June 9, 2011.pdf

5NH 2011 Heat Burst-What is a Heat Burst Website June 10, 2011

Follow

http___www.theweatherprediction.pdf

5NH 2011 Heat Burst-Wichita Kansas Experiences Rare Heat Burst Overnight June 9, 2011 KSN3 Television News Report+Video.pdf

5NH 2011 Heat Bursts Possible Tonight Across Eastern Oklahoma June 9, 2011 KTUL 8 News Tulsa.pdf

5NH 2011 Heat Bursts Reported in Jefferson, Waukesha Milwaukee Journal Sentinel News June 8, 2011.pdf

5NHZ 2011 Heat Burst Wikipedia Website June 10, 2011.pdf

5PZ 2010 NYTimes February 1, 2010 Growing Pentagon Focus on Energy and Climate by Revkin.pdf

5PZ 2010 U.S. Air Force – TV Meteorologist Explains Weather Map Showing Chaff Effects.pdf

5P 1993 U.S. Army Battlefield Atmsopherics December 2, 1993 Abstract Battle Weather Conference.pdf

5P 1994 Owning the Weather U.S. Army.pdf

5P 1994 U.S. National Report Planned Weather Modification Research 1991-1994 Study.pdf

5P 1996 The World of 2020 and Alternative Futures 1996.pdf

5P 1996 U.S. AF2025 v3c15-1 _ Weather as a Force Multiplier_ Owning August 1996.pdf

5P 1996 U.S. AF2025 v3c15-2 _ Weather as a Force Multiplier_ Owning August 1996.pdf

5P 1996 U.S. AF2025 v3c15-3 _ Weather as a Force Multiplier_ Owning August 1996.pdf

5P 1996 U.S. AF2025 v3c15-4 _ Weather as a Force Multiplier_ Owning August 1996.pdf

5P 1996 U.S. AF2025 v3c15-5 _ Weather as a Force Multiplier_ Owning August 1996.pdf

5P 1996 U.S. AF2025 v3c15-6 _ Weather as a Force Multiplier_ Owning August 1996.pdf

5P 1996 U.S. AF2025 v3c15-7 _ Weather as a Force Multiplier_ Owning August 1996.pdf

5P 1996 U.S. Air Force 2025 – 1996 Quick Look.pdf

5P 1996 U.S. Air Force 2025 – 1996 Quotes.pdf

5P 1996 U.S. Air Force 2025 Air University 30 Years in the Future August 1996.pdf

5P 1996 U.S. Air Force 2025 Alternate Futures Security Planning-Avoid Surprise August

Follow

1996.pdf

5P 1996 U.S. Air Force 2025 Earthquake Weapon Ultrasonic Acoustic August 1996 Abstract.pdf

5P 1996 U.S. Air Force 2025 Executive Summary August 1996.pdf

5P 1996 U.S. Air Force 2025 Key Players August 1996.pdf

5P 1996 U.S. Air Force 2025 Organization Key Players August 1996.pdf

5P 1996 U.S. Air Force 2025 Project Participants 1996.pdf

5P 1996 U.S. Air Force August 1996 Weather As A Force Multiplier.pdf

5P 1996 U.S. Air Force Weather Analysis and Modification System August 1996.pdf

5P 1997 U.S. Air Force Benign Weather Modification March 1997.pdf

5P 1998 CHAFF U.S. GAO Report September 22, 1998 Military Use of Chaff.pdf

5P 1998 JETTRAX U.S. Air Force Weather Agency Contrail Forecasts March 1998 Abstract.pdf

5P 1999 AMS + AGU Atmospheric Electricity 1999 Conference.pdf

5P 2000 Cloud Electrification Studies CESAR 2000 Overview.pdf

5P 2000 RAMS Colorado Cloud Role in Global Warming Studies ENN October 1, 2000.pdf

5P 2001 Weather at Edge of Space-Upper Atmospheric Studies UCAR News December 7, 2001.pdf

5P 2002 NASA NIAC January 7, 2002 Controlling the Global Weather.pdf

5P 2003 Air Force – Cloud Seeding January 10, 2003 U.S. Air Force Website.pdf

5P 2003 U.S. Air Force Air War College Weather Operations March 2003 Lanicci.pdf

5P 2003 United States Air Force Weather Agency October 2003.pdf

5P 2004 NASA NIAC NASA Institute for Advanced Concepts Controlling Global Weather Final Report March 31, 2004 Hoffman.pdf

5P 2004 RAMS Colorado Cloud Seeding 2004 Acknowledgments RAMS Colorado Node13.pdf

5P 2004 RAMS Colorado Cloud Seeding 2004 Advocacy Questions Node 11.pdf

5P 2004 RAMS Colorado Cloud Seeding 2004 Document Node15.pdf

5P 2004 RAMS Colorado Cloud Seeding 2004 Hygroscopic Discussion Node 4.pdf

Follow

5P 2004 RAMS Colorado Cloud Seeding 2004 Importance of Natural Variability Node 8.pdf

5P 2004 RAMS Colorado Cloud Seeding 2004 Introduction Node 1.pdf

5P 2004 RAMS Colorado Cloud Seeding 2004 Lessons Learned Node 6.pdf

5P 2004 RAMS Colorado Cloud Seeding 2004 Node 12 Proof – Hard Evidence Climate Change Aerosols.pdf

5P 2004 RAMS Colorado Cloud Seeding 2004 Node 3.pdf

5P 2004 RAMS Colorado Cloud Seeding 2004 Problems + Questions Node 7.pdf

5P 2004 RAMS Colorado Cloud Seeding 2004 References Node 14.pdf

5P 2004 RAMS Colorado Cloud Seeding 2004 Static Mode Node2.pdf

5P 2004 RAMS Colorado Cloud Seeding 2004 Weather Modification 2004 Node 10 Problems.pdf

5P 2004 RAMS Colorado Cloud Seeding 2004 Weather Modification Funding Node 5.pdf

5P 2004 U.S. NAVY NRL Scientists Study Desert Air Aerosols Effect on Weather + Climate September 9, 2004.pdf

5P 2005 16th Conference on Planned and Inadvertent Weather Modification January 2005 Program Listing.pdf

5P 2005 Washington University 2005 Cloud & Haze Study UW Satellites December 6, 2005.pdf

5P 2005 Weather Modification RAM Abstract March 2005 Particulates U.S. Air Force.pdf

5P 2006 United States Air Force Weather Programs 2006.pdf

5P 2007 DTIC July 30, 2007 Abstract Defense Technical Information Center Search-Military Weather Modification.pdf

5P 2007 DTIC July 30, 2007 Weather Modification Abstract Search Page 5 – Results 50.pdf

5P 2007 U.S. Air Force 87th Annual Meeting on Weather January 2007.pdf

5P 2007 U.S. Air Force Weather Net Enabled Operations 2007 – 87th Annual 9B.0.pdf

5P 2008 NASA Aurora Borealis NYTimes August 7, 2008 Both Man-Made + Real Questions.pdf

5P 2008 NASA TOMS Review of Cloud Seeding Experiments 2008.pdf

5P 2008 NOAA Climate Prediction Center July 30, 2008 Atmospheric Blocking.pdf

Follow

5P 2008 USDA Weather Programs + Research 2008 Many Government Agencies Involved.pdf

5P 2008 Vegetation Health Climate Live Science May 10, 2008 Page 1.pdf

5P 2008 Vegetation Health Climate Live Science May 10, 2008 Page 2.pdf

5P 2008 Weather Abstract Search December 22, 2008 Storming Media Pentagon Reports.pdf

5P 2008 Weather As A Force Multiplier Abstract Search 2008 Storming Media Results 5.pdf

5P 2008 Weather Modification Damage Program U.S. Bureau of Reclamation 2008 Hunter.pdf

5P 2009 European Space Agency Climate Studies Aerosol Data Novemer 10, 2009.pdf

5P 2009 European Space Agency ESA November 11, 2009 Website Earth Observing Missions – Satellites.pdf

5P 2009 NOAA Navy Climate Prediction+Ocean Mapping OregonLive News Note Man-Made Skies Over Harbor Picture.pdf

5P 2009 U.S. Patent Search-Research Needed – A Partial History of Aerosol and Weather Related Technologies July 3, 2003 by Kramer.pdf

5P 2010 ASP Website March 2, 2010 http___www.asp.bnl.pdf

5P 2010 California Department of Fish+Game Library March 19, 2010 http___nrm.dfg.ca.pdf

5P 2010 NASA Weather Modification Search March 1, 2010 Page 1.pdf

5P 2010 NASA Weather Modification Search March 1, 2010 Page 2.pdf

5P RAMS Weather Modification + Cloud Seeding – Underestimating the Impacts Colorado EDU .pdf

5P U.S. Air Force Document Weather Modification Programs sec3b_dod.pdf

5Q 1976 Weather Modification by Absorbtion of Solar Energy-Carbon Black December 1976.pdf

5Q 1998 CLAIRE Aerosol Experiments 1998 Studies.pdf

5Q 2003 Black Carbon Aerosol Pollution Cools, Heats, Confuses 2003.pdf

5Q 2006 33 NASA Studies January 17, 2006 Increasing Aerosol Concentrations-Produce Fog-Like Haze.pdf

5Q 2007 33 NASA March 15, 2007 Global Sunscreen Thinned-Aerosols=Global Cooling+Global Warming.pdf

Follow

5Q 2007 Aerosols + Clouds + Sunlight February 25, 2007 Science Daily News.pdf

5Q 2008 Role of Aerosols on Precipitation September 8, 2008 Science Daily News.pdf

5Q 2009 Atmospheric Science Program ASP February 25, 2009 Platform Presentations.pdf

5Q 2009 Black Carbon Mark Z. Jacobson Stanford University October 18, 2009 U.S. House Testimony.pdf

5Q 2009 Weather Modification Tropospheric Microbes Diverse + Stable October 2009 Air Samples.pdf

5Q 2010 33 NASA GEWEX Working Group Aerosols Newsletter January 3, 2010.pdf

5Q 2010 NASA Goddard Institute of Space Studies Aerosols April 16, 2010 Particles – Health Sources http ____ www.giss.nasa.pdf

5Q 2010 Weather Modification McGraw Hill Abstract Encyclopedia Article.pdf

5R 2001 Cloud Study Daniel Rosenfeld Aerosols March 28, 2001 Rain.pdf

5R 2002 ROSENFELD Weather Modification Aerosols Rosenfeld Israel Clouds 2002.pdf

5R 2002 Weather Modification Rosenfeld Clouds.pdf

5R 2003 Cloud Types-Ten Major Types 2003.pdf

5R 2004 Clouds AGU 2004.pdf

5R 2005 Weather Modification Rosenfeld 2005 Presentation Recorded.pdf

5R 2006 Clouds North Pole Climate Change Study Novemer 27, 2006 ENN.pdf

5R 2007 Clouds Climate Change ENN December 10, 2007 Study High Clouds.pdf

5R 2007 Clouds Heat Trapping Cirrus November 5, 2007 Science Daily.pdf

5R 2008 Clouds Arctic April 1, 2008 Science Daily Studies.pdf

5R 2008 Cloud Types Gallery of Pictures – Man-Made Questions December 11, 2008.pdf

5R 2008 Cloud Unusual Formations Linked to Quakes April 2008.pdf

5R 2009 Air Pollution both Decreases and Increases Rainfall SEPT 11, 2008 Prof Rosenfeld Studies Aerosols.pdf

5R 2009 Drought-Particles-Clouds-Rain Rosenfeld Google Search December 25, 2009 Page 2.pdf

Follow

5R 2009 Drought-Rainfall-Clouds Rosenfeld Studies Google Search December 25, 2009.pdf

5R 2009 Drought – Rain – Snow Rosenfeld Google Search December 25, 2009 Page 4.pdf

5R 2009 Drought Rosenfeld Rain Clouds Snow Studies Google December 25, 2009 Page 3.pdf

5SZ 2010 NCAR UCAR Open House 50th Anniversary Boulder Colorado June 5, 2010-Note Research Aircraft.pdf

5S 1995 UCAR Airborne Particulates May be Cooling Earth Press Release October 27, 1995.pdf

5S 1996 Drought on Southern Plains UCAR Report Press Release April 4, 1996.pdf

5S 1996 UCAR Express Africa Study on Climate News Release October 30, 1996.pdf

5S 1997 RAMS Weather Modification by Clouds Seeding Status Report 1989-1997 Colorado State University.pdf

5S 1997 RAMS Weather Modification by Clouds Seeding Status Report Capricious Administration Science+Technology 1989-1997.pdf

5S 1997 RAMS Weather Modification by Clouds Seeding Status Report Dynamic Mode 1989-1997 Colorado State University.pdf

5S 1997 RAMS Weather Modification by Clouds Seeding Status Report Hard Scientific Evidence 1989-1997 Colorado State University.pdf

5S 1997 RAMS Weather Modification by Clouds Seeding Status Report Hygroscopic Seeding 1989-1997 Colorado State University.pdf

5S 1997 RAMS Weather Modification by Clouds Seeding Status Report Introduction 1989-1997 Colorado State University.pdf

5S 1997 RAMS Weather Modification by Clouds Seeding Status Report References 1989-1997 Colorado State University.pdf

5S 1997 RAMS Weather Modification by Clouds Seeding Status Report Scientific Credibility-Advocacy 1989-1997 Colorado State.pdf

5S 1997 RAMS Weather Modification by Clouds Seeding Status Report Static Mode 1989-1997 Colorado State University.pdf

5S 1997 RAMS Weather Modification by Clouds Seeding Status Report Technology 1989-1997 Colorado Univ.pdf

5S 1997 RAMS Weather Modification-Clouds Seeding Status Report Capricious Adm of

Follow

In the Fusion Practices, the body enters into a dynamic process towards new balances. This is an essential condition for the light to grow inside. This can then in turn attract the light from heaven as its energies become finer, as they blend into a higher quality energy created by the blending of love and compassion. This higher concentrate of energy is then condensed into a pearl which is subsequently circulated through the major organs and the psychic channels in and around the body. The pearl will help the body to feel centered and experience peace and harmony. It will also help to cleanse the special channels and enhance the free flow of energy.

The pearl will facilitate the growth and transference of consciousness from the physical to the energy body and from the energy to the spirit body (Cosmic Fusion), healing it and helping it to center and experience peace and harmony. Through the growth of love and compassion the body is able to radiate out and receive in the love and cosmic energies so that its own Chi is blended with the cosmic Chi and is thereby transformed into a higher quality of Chi.

To facilitate the process of blending and balancing the energies within the body between its organs and the gathering, processing and condensing of energies from the universe and from nature, the pakuas play an essential role (Formula 1, *Fusion of the Five Elements*).

In the earliest stage after conception, the first meridians which rule the circulation of energy of the embryo and which come into existence after the split of the egg and the formation of the body are the governor and conception channels. Successively, all other Yin and Yang meridians form in a symmetric fashion on the Yang and Yin sides of the body.

In ancient Taoists texts they are also called the sun side or outer side and the moon or inner side of the body. The sun side is that side exposed to the sun when one bows down, the moon side is that part which remains in the shadow.

The body might be visualized as grid of conduits of light which link it to the Light in which all energy and matter has its origin, a view which is supported by the new physics.

Science+Technology 1989-1997 Colorado State.pdf

5S 1997 UCAR Winter Storms Study FASTEX UCAR Press Release January 12, 1997.pdf

5S 1998 UCAR Pacific Northwest Pollutants Tags Press Release December 4, 1998.pdf

5S 1999 UCAR Indian Ocean Experiment UCAR Press Release March 4, 1999 INDOEX.pdf

5S 2001 Weather Modification in Mexico Study UCAR Press Release January 16, 2001.pdf

5S 2002 UCAR Global Pollution Hotspots Identified December 6, 2002 New Release.pdf

5S 2002 Water Vapor Study in United States UCAR News May 7, 2002.pdf

5S 2003 UCAR Dust Particle Studies July 15, 2003 Press Release.pdf

5S 2003 UCAR NCAR Studies 2003 Air Quality – Forests – Agriculture.pdf

5S 2003 UCAR Pacific Ocean Air Pollution Press Release February 4, 2003.pdf

5S 2003 UCAR Press Release February 11, 2003 Water Vapor-Clouds Corrupting Long-Term View of Climate Change Radiosonde.pdf

5S 2003 Weather Modification UCAR NCAR Experiments Continue 2003 Press Release.pdf

5S 2004 UCAR Media News Release 2004 Geoscience Careers Geo Forum.pdf

5S 2004 UCAR Postal Cloud Stamps Mystery Solved on Where They Came From 2004.pdf

5S 2004 UCAR Publicatons 2004 Clouds Soot + More.pdf

5S 2005 BBC December 21, 2005 Weather Satellite MSG-2.pdf

5S 2005 UCAR Water Vapor Studies 2005 WVSSII Flying the Skies.pdf

5S 2006 UCAR Field Campaign Mexico City – MIRAGE 2006.pdf

5S 2006 UCAR Geoengineering Atmospheric Injections Particles+Chemicals Tom Wigley 2006.pdf

5S 2006 UCAR Weather Satellites in Orbit April 14, 2006.pdf

5S 2007 NCAR UCAR Letter 2007 Rocky Mtn Study 092708 Buckmann.pdf

5S 2007 UCAR 2007 Forests as Carbon Sinks Website Press Release on Study.pdf

5S 2007 UCAR October 31, 2007 Forest Fires Release Carbon Dioxide Study.pdf

5S 2007 UCAR Scientists to Tarck Impact of Asian Dust + Pollution Clouds on Weather +

Follow

Climate Change April 2007.pdf

5S 2008 NCAR News October 25, 2008 Super Science Saturday.pdf

5S 2008 UCAR Press Releases 2008 Weather+Climate.pdf

5S 2008 UCAR Wildfires Major Mercury Emitters + Other Pollutants 2008.pdf

5S 2008 Weather AMS Statements 1990 to August 16, 2008.pdf

5S 2008 Weather Forecasts Target Meningitis Epidemics November 2008 UNCAR News.pdf

5S 2008 Weather Modification State of the Science UCAR Presentation 2008.pdf

5S 2008 Weather Super Computer BlueFire UCAR May 8, 2008. pdf.pdf

5S 2009 NCAR Heliophage.wordpress 2009 Confusion Between NASA Ship Tracks or Persistent Jet Contrails.pdf

5S 2009 NCAR May 2009 Acronyms E List University Corporation for Atmospheric Research.pdf

5S 2009 NCAR May 2009 Acronyms G List University of Wisconsin Notes.pdf

5S 2009 NCAR May 2009 Acronyms H List.pdf

5S 2009 NCAR May 2009 Acronyms I List.pdf

5S 2009 NCAR May 2009 Acronyms J List.pdf

5S 2009 NCAR May 2009 Acronyms K List.pdf

5S 2009 NCAR May 2009 Acronyms L List.pdf

5S 2009 NCAR May 2009 Acronyms M List.pdf

5S 2009 NCAR May 2009 Acronyms N List.pdf

5S 2009 NCAR May 2009 Acronyms O List.pdf

5S 2009 NCAR May 2009 Acronyms P List.pdf

5S 2009 NCAR May 2009 Acronyms Q List.pdf

5S 2009 NCAR May 2009 Acronyms R List.pdf

5S 2009 NCAR May 2009 Acronyms S List.pdf

5S 2009 NCAR May 2009 Acronyms T List.pdf

Follow

5S 2009 NCAR May 2009 Acronyms U List.pdf

5S 2009 NCAR May 2009 Acronyms V List – Note California Reference.pdf

5S 2009 NCAR May 2009 Acronyms W List.pdf

5S 2009 NCAR May 2009 Acronyms X List.pdf

5S 2009 NCAR May 2009 Acronyms Y List.pdf

5S 2009 NCAR May 2009 Acronyms Z List.pdf

5S 2009 NCAR News – Beetle Kill May Affect Weather, Pollution September 24, 2009.pdf

5S 2009 NCAR Storm News Transoceanic Flights July 7, 2009.pdf

5S 2009 NCAR Thunderstorms Glossary May 15, 2009.pdf

5S 2009 NCAR UCAR Americans Use 300 Billion Weather Forecasts Annually-Survey June 23, 2009.pdf

5S 2009 NCAR UCAR Press Release July 16, 2009 Solar Cycle Linked to Global Climate Research.pdf

5S 2009 UCAR Acronym A Listing May 2009.pdf

5S 2009 UCAR Acronym B Listing May 2009.pdf

5S 2009 UCAR Acronym C Listing May 2009.pdf

5S 2009 UCAR Acronym D Listing May 2009.pdf

5S 2009 UCAR Acronym F Listing May 2009.pdf

5S 2009 UCAR CLouds + Postage Stamps 2009.pdf

5S 2009 UCAR Glossary May 2009 Thunderstorms, etc.pdf

5S 2009 UCAR Glossary Search Page 1 May 2009.pdf

5S 2009 UCAR Glossary Search Page 2 – May 2009.pdf

5S 2009 UCAR Home Page May 2009.pdf

5S 2009 UCAR May 2009 Southeast Queensland Cloud Seeding Reasearch RAL Home.pdf

5S 2009 UCAR May 2009 Southwest Queensland Cloud Seeding Research RAL Collaborators.pdf

Follow

5S 2009 UCAR News Archive Note Pictures September 28, 2009 by C. Calvin.pdf

5S 2009 UCAR Organization May 15, 2009 Website.pdf

5S 2009 UCAR Persistent Jet Contrail Search May 2009 Page 1.pdf

5S 2009 UCAR Press Release July 16, 2009 Solar Cycle Linked to Global Climate Research.pdf

5S 2009 UCAR Publication Lists May 2009.pdf

5S 2009 UCAR Scientists Uncover Solar Cycle, Stratosphere, and Ocean Connection August 28, 2009.pdf

5S 2009 UCAR Search May 15, 2009 Contrails – Clouds.pdf

5S 2009 UCAR Springtime Volunteers Watch Plants-Clues Climate Change March 19, 2009.pdf

5S 2009 UCAR Tip Sheet on Wildfires – Health Impacts Website 2009.pdf

5S 2009 UCAR University Corporation for Atmospheric Research Website November 2009.pdf

5S 2009 UCAR Website Library May 2009.pdf

5S 2009 UCAR Website Research Section May 2009.pdf

5S 2010 EurekAlert AAAS Press Releases Earth Science March 12, 2010.pdf

5S 2010 UCAR NCAR Punch Clouds Research Article June 14, 2010 With Photograph-UCAR Struggled to Find Explanation.pdf

5S 2010 UCAR NCAR Scientists to Track Tornadoes in Largest World Tornado Study in U.S. April 28, 2010.pdf

5S 2010 UCAR NCR Press Release Aircraft Cause Rain or Snow+Hole Punch Clouds June 14, 2010.pdf

5TZ 2002 Texas Rancher Speaks Out Against Weather Modification 2002 O'Brien.pdf

5TZ Weather Modification WE ARE THE EXPERIMENT by Tiller Texas.pdf

5T 1988 Weather Modification, Inc. Texas 1985+1986+1988 Rainfall Enhancement.pdf

5T 1995 TEXAS Weather Modification 1995 Precipitation Augmentation—Summer Convective Clouds.pdf

5T 1998 Weather Modification, Inc. TEXAS TEXARC 1994-1996+1998 Assessments.pdf

5T 2000 Farmers Skeptical of Weather Modification Programs AP News 2000.pdf

Follow

5T 2000 Weather Modification, Inc. Texas Panhandle Rainfall Enhancement 2000.pdf

5T 2001 Weather Modification Inc. Texas Rainfall Enhancement 1999-2001.pdf

5T 2003 Weather Modification, Inc. Texas 2001-2003 Rainfall Enhancement-West Central Texas.pdf

5T 2006 33 NASA January 11, 2006 Deep-Rooted Plants-Trees Have Great Impact on Climate – Studies.pdf

5T 2006 Texas Dept Licensing Regulation 2006 Summary Weather Mod.pdf

5T 2006 Texas Harvesting the Skies in 2006.pdf

5T 2006 Texas Summary of Rain Enhancement 2006.pdf

5T 2006 Texas Weather Modification Summary 2006.pdf

5T 2007 Newspaper.com November 23, 2007 Sky Drones Speeding Tickets Texas.pdf

5T 2007 Texas Law H.B. No 2833 Act 2007.pdf

5T 2007 Texas Weather Modification Association Evaluation 2007.pdf

5T 2007 Texas Weather Modification Laws September 2007.pdf

5T 2008 Texas Depart of Licensing Regulation 2008 Weather Mod.pdf

5T 2008 Texas Dept Licensing Regulation 2008 Rain Enhancement Map.pdf

5T 2008 Texas Dept of Licensing Regulations 2008 Weather Modification Forms.pdf

5T 2008 Texas Dept of Licensing Regulation 2008 Weather Mod Q&A.pdf

5T 2008 Texas Dept of Licensing Regulation Meeting Agenda 2008.pdf

5T 2008 Texas Dept of Licensing Regulation Weather Modification 2008.pdf

5T 2008 Texas Dept of Licensing Regulation Weather Modification Advisory Committee 2008.pdf

5T 2008 Texas Dept of Licensing Regulation Weather Modification March 6, 2008.pdf

5T 2008 Texas Map of Rain Enhancement Programs 2008.pdf

5T 2008 Texas Rain Enhancement Programs Map 2008.pdf

5T 2008 Texas Weather Modification Administration Rules Regulations 2008.pdf

Follow

5T 2008 Texas Weather Modification Administrative Rules 2008.pdf

5T 2008 Texas Weather Modification Association 2008.pdf

5T 2008 Texas Weather Modification Association Flares 2008.pdf

5T 2008 Texas Weather Modification Association History 2008.pdf

5T 2008 Texas Weather Modification Courier May 15, 2008.pdf

5T 2008 Texas Weather Modification July 31, 2008.pdf

5T 2008 Texas Weather Modification Law 2008.pdf

5T 2008 Texas Weather Modification Meeting Archives 2008.pdf

5T 2008 Texas Weather Modification Meeting Archives 2008 – Note March 2008 Meeting.pdf

5T 2008 Texas Weather Modification Meeting August 18, 2008 Audio Tape.pdf

5T 2009 Texas Clean Water Act Violations Map NYTimes September 12, 2009.pdf

5T 2009 Texas Weather Modification Achives of Meetings July 2009 Search.pdf

5T 2009 Texas Weather Modification Meeting Mintues, Agenda and Link to Audio of Meeting March 6, 2009.pdf

5T 2009 Texas Weather Modification Programs July 19, 2009.pdf

5T 2009 Texas Worst Drought in History 9 Counties August 14, 2009 MSNBC.pdf

5T 2010 Handbook of Texas Weather Modification TSHA Annual Meeting March 4-6, 2010.pdf

5T 2010 Scorecard Toxic Chemical Releases Report TEXAS.pdf

5T 2010 Texas Power Point Presentation 2010 Fundamentals_of_Weather_Modification_ppp.pdf

5U 2003 Evaporation 2003 Study Isotopic Fractionation of Water During Evaporation.pdf

5U 2003 Evaporation Isotopic Fractionation of Water During Evaporation 2003 EGU Studies Page 2.pdf

5U 2008 Jet Stream Changes August 23, 2008 Science Daily Weather.pdf

5U 2008 Jet Stream July 8, 2008 Map Information.pdf

5U 2008 Jet Stream Maps Archives CA 2008.pdf

Follow

5U 2008 Jet Stream Map Information Analysis July 8, 2008.pdf

5U 2008 Jet Stream Map July 8, 2008 United States.pdf

5U 2008 JET STREAM Steering Eastlund ESEC 2008 Microwave Heaters.pdf

5U 2008 Jet Stream USA Today 2008.pdf

5U 2008 No Comment Jet Stream Wikipedia July 2008.pdf

5U 2010 Weather January 9, 2010 The Jet Stream NYTimes.pdf

5VZ 2009 Hurricane + Global Warming Control Standler June 2009 Method.pdf

5V 2002 NASA NIAC JAN 7, 2002 Controlling the Gobal Weather+Hurricanes Hoffman.pdf

5V 2003+2008 Hurricanes Gustav September 12, 2003-Katrina August 31, 2008 Comparison.pdf

5V 2004 NASA NIAC Controlling Global Weather Final Report March 31, 2004 Hoffman.pdf

5V 2006 Hurricanes Dyn-O-Mat June 25, 2006 Tribune News.pdf

5V 2006 Hurricanes June 25, 2006 Dyn-O-Mat Chicago Tribune News.pdf

5V 2006 NASA Finds Intense Lightning Activity Around Hurricane Eye June 23, 2006 Science Daily News.pdf

5V 2007 Hurricane Benefits NYTimes July 17, 2007.pdf

5V 2007 Hurricane Control Telegraph UK October 21, 2007.pdf

5V 2007 Scientists A Step Closer to Steering Hurricanes Telepgraph UK October 21, 2007.pdf

5V 2007 Wisconsin NOAA Hurricane Force Winds History 2007.pdf

5V 2008 Federal Lightning Capability Requirements Draft July 2008 Report.pdf

5V 2008 Hurricanes NYTimes September 4, 2008 Limited 25 Year Study.pdf

5V 2008 Hurricanes Tamed by U.S. Homeland Security 2008 Telegraph.pdf

5V 2008 Hurricanes Tamed by U.S. Homeland Security February 8, 2008 Telegraph.co.uk.pdf

5V 2008 Hurricanes to be Tamed by U.S. Homeland Security February 8, 2008 Telegraph.co.uk.pdf

5V 2008 Hurricane Abstract Search 2008.pdf

Follow

5V 2008 Hurricane Abstract Search 2008 Page 2.pdf

5V 2008 Hurricane Operatons Plan 2008 National PDF File Outline.pdf

5V 2008 Sahara Desert-Hurricane Influence Science Daily News August 19, 2008.pdf

5V 2008 Tornadoes May 2008 Recording Setting Path of Destruction.pdf

5V 2008 TORNADOES Mitigation-Reverse Enhancement Questions 2008 Eastlund ESEC.pdf

5V 2008 U.S. Navy Studying Cyclones Press Release December 15, 2008 NRL.pdf

5V 2009 Hurricane Inland Illinois Search May 8, 2009 Page 1.pdf

5V 2009 OFCM National Hurricane Operations Plan May 2009.pdf

5V 2009 Tornado Study-Experiment May 4, 2009 NCAR-UCAR News Release.pdf

5V 2009 Weather Modification Hurricane Tracking Science Technology July 2009 USA Today Graph.pdf

5V 2010 Lightning Detection Network Canada Weather Office March 16, 2010.pdf

5V 2010 March 10, 2010 GOES-12 Satellite Picture 90Q See Article on Page 1.pdf

5V 2010 March 10, 2010 Tropical Rainfall Measuring Mission TRMM Satellite Picture of Tropical Storm 90Q.pdf

5V 2010 Second Tripical Cyclone Ever Forms in South Atlantic March 11, 2010 LiveScience.pdf

5WZ 2008 Weather Modification Association Photo Album 299 – September 15, 2008.pdf

5W 1961 Weather Modification Inc. Since 1961 Meteorological Services.pdf

5W 1969 Weather Modification Journal Volume 1 Table of Contents.pdf

5W 1977 Weather Modification Inc. Illinois 1977 Rain Enhancement.pdf

5W 1977 Weather Modification Inc. Michigan Rain Enhancement 1977.pdf

5W 1978 Weather Modification-Journal of the American Water Resources Association 1978.pdf

5W 1984 Weather Modification Inc Antiqua Clouds Seeding project 1984 Rainfall Enhancement.pdf

5W 1985 Weather Modification Inc. Canary Islands, Spain 1984-1985 Rainfall Enhancement+Radar.pdf

Follow

5W 1985 Weather Modification Inc. Delaware Rainfall Enhancement 1985.pdf

5W 1989 Weather Modification Inc. Jordan 1986-1989 Rainfall Enhancement.pdf

5W 1989 Weather Modification, Inc. North Dakota Thunderstorm Project 1989.pdf

5W 1989 Weather Modification, Inc. South Dakota 1989 Snowpack Augmentation.pdf

5W 1990 Weather Modification, Inc. North Dakota University+EPA Thunderstorm Research.pdf

5W 1992 Weather Modification Inc. Greece Navy 1992 Meteorological Instrumentation.pdf

5W 1993 Weather Modification Inc. NOAA Florida 1992, 1993 Equipment Lease Weather Radar System.pdf

5W 1993 Weather Modification, Inc. North Dakota 1993 Tracer Experiment-Atmospheric Resource Board.pdf

5W 1993 Weather Modification Inc. Turkey 1993-1995 Rainfall Enhancement + Products.pdf

5W 1993 Weather Modification Inc. U.S. Department of Defense 1993 Weaher Radar System Sale.pdf

5W 1993 Weather Modification Inc. United Arab Emirates 1990-1993 RainFall Enhancement+Products.pdf

5W 1994 Weather Modification Inc. Alaska Volcanic Monitoring 1991-1994.pdf

5W 1994 Weather Modification Inc. FAA Great Lakes North Dakota Weather Observation 1991-1994.pdf

5W 1994 Weather Modification, Inc. Saskatchewan 1994 Weather Radar System+Tech Support.pdf

5W 1995 ASCE Publications Guidelines for Cloud Seeding to Augment Precipitation 1995.pdf

5W 1995 Weather Modification, Inc. New York 1995 Atmospheric Assessment+Evaluation.pdf

5W 1995 Weather Modification Inc. University of Arizona+NOAA Atmospheric Assessement.pdf

5W 1998 Weather Modification Inc. Thailand 1996-1998 Rainfall Enhancement Program Support.pdf

5W 1999 Weather Modification Inc. Mexico 1996-1999 Rainfall Enhancement+Products.pdf

5W 2001 DYN-O-MAT Corporation Weather Control Cloud Removal Powder BBC AUG 2,

Follow

2001.pdf

5W 2001 U.S. Patent 6315213 Method of Modifying Weather Cordani NOV 13, 2001 Polymers Like Cross Linked Polyacrylamides.pdf

5W 2001 Weather Modification Inc. British Columbia 2001 Snowpack Augmentation.pdf

5W 2001 Weather Modification Inc. British Columbia Weather Radar System Upgrade 2001.pdf

5W 2001 Weather Modification Inc. Greece 1997-2001 Hail Damage Mitigation.pdf

5W 2001 Weather Modification, Inc. Oklahoma 1997+2000-2001 Hail+Rainfall Enhancement.pdf

5W 2002 Weather Modification, Inc. United Arab Emirates 2001-2002 Rainfall Enhancement+Products.pdf

5W 2003 CIRES Program Full Text 2003 Climate.pdf

5W 2003 Weather Modification Inc. 2002-2003 Colorado BAMEX Experiment.pdf

5W 2003 Weather Modification Inc. Jordan Ground Based Cloud Seeding Equipment 2003.pdf

5W 2003 Weather Modification, Inc. Utah Division of Water Resources 2003 Equipment Lease.pdf

5W 2004 AI Weather Modification AI 2004 Background Information.pdf

5W 2004 AI Weather Modification Book 2004 Publications.pdf

5W 2004 AI Weather Modification Company 2004.pdf

5W 2004 Atmospherics Inc 2004 http___www.atmos-inc.pdf

5W 2004 Weather Modification Ice Crystal Engineering 2004 http___www.iceflares.pdf

5W 2004 Weather Modification Inc. 2004 Cloud Seeding.pdf

5W 2004 Weather Modification Inc. Argentina 1998-2004 Hail Damage Mitigation.pdf

5W 2004 Weather Modification Inc. India 2002+2004 Rainfall Enhancement Projects.pdf

5W 2004 Weather Modification, Inc. New Mexico 2004 Burst Light+Stratus Transmission Project.pdf

5W 2004 Weather Modification Inc. Turkey Rainfall Enhancement 1991-2004 + Products.pdf

5W 2004 Weather Modification Inc 2004 Aircraft Modification.pdf

Follow

Unity of Ying and Yang

Basic to the Taoist tradition is the view that positive and negative energies are a manifestation of the very nature of the universe as a unity of opposite energies: Yin and Yang. It is by virtue of the dynamics of the interplay of Yin and Yang that the universe exists and continues to exist. They rule all phenomena in the universe as an infinite web of mutually interconnected processes and their movement. This insight is the theoretical as well as the practical basis of the Fusion Practices.

In Taoist theory, Yin and Yang rule the relationships between stars, planets, the sun and the moon and the earth, light and dark, above and below, man and woman. It is in and through this interplay, that the universe unfolds and functions. If one of them would disintegrate or disappear, the universe would end.

In the Taoist vision on the nature of the universe, the body is a microcosmos, which manifests and reflects in its inner structure the dynamics of the universe. As such it is also ruled by the same forces of Yin and Yang.

These in turn manifest themselves in the universe in the five elements (water, fire, wood, metal and earth). These five elements operate as energies in the body, in and through the five vital organs: the kidney, heart, liver, lungs and spleen. It is the natural capacity of the body to heal and regenerate itself. The body is sustained and nurtured by cooperating and facilitating the workings of the universe through the balancing of the five forces in the organs of the body and the positive and negative properties of each of them.

It is the relationship between the positive and negative energies contained and reflected in the organs, which is the starting point of the Fusion Practices.

In the Taoist tradition, the body has always been viewed as a sacred vessel, which reflects the sacred nature of the universe as a whole. Interfering with its laws of motion, the balance between Yin and Yang is broken and with it harmony and mutual cooperation between the organs and the elements which compose the body.

As a result, the free uninhibited flow of energy streams, and with it the immunity of the body, are affected. In Chinese medicine, of Taoist origin, disease is seen as the outward manifestation of

5W 2004 Weather Modification Inc 2004 Cloud Seeding Thunderhead Picture.pdf

5W 2004 Weather Modification Inc 2004 Projects.pdf

5W 2004 Weather Modification Inc Clouds Seeding 2004.pdf

5W 2004 Weather Modification Inc Cloud Seeding Equipment 2004.pdf

5W 2004 Weather Modification Inc Equipment Dry Ice Hoppers 2004.pdf

5W 2004 Weather Modification Inc Flares + Picture.pdf

5W 2004 Weather Modification Inc Fog Dispersal 2004.pdf

5W 2005 Weather Modification 2005 New Implementation Plan Parameters.pdf

5W 2005 Weather Modification Association 1 2005.pdf

5W 2005 Weather Modification Association 2005.pdf

5W 2005 Weather Modification Association 2005 Press Release.pdf

5W 2005 Weather Modification Association 2005 Related Sites.pdf

5W 2005 Weather Modification Association Capabilities 2005 Statement.pdf

5W 2005 Weather Modification Association Code of Ethics April 2005.pdf

5W 2005 Weather Modification Inc. Projects 2005.pdf

5W 2005 Weather Modification Inc. Seeding Equipment 2005.pdf

5W 2006 Weather Modification Assoication Committee Directory 2005-2006.pdf

5W 2006 Weather Modification Inc. 2006 Florida CALIPSO CloudSat Validation Experiment.pdf

5W 2007 Weather Modification Association WMA 2007 Related Sites Weather Modification, Inc.pdf

5W 2007 Weather Modification, Inc. 2006-2007 NSF+NCAR ICE-L Field Campaign.pdf

5W 2007 Weather Modification Inc. Indonesai 2005-2007 Weather Modification Program.pdf

5W 2008 NAIWMC Weather Modification NAIWMC Home Page 2008 – U.S. Map.pdf

5W 2008 NAIWMC Weather Modification NAIWMC Presentations 2008 Arizona.pdf

5W 2008 U.S. Patent 7393908 July 1, 2008 Cross-Linked Water-Swellable Polymer Metho

Follow

5W 2008 Weather Forecasts Target Meningitis Epidemics November 2008 UCAR News.pdf

5W 2008 Weather Modification Association 2008 Image Repository.pdf

5W 2008 Weather Modification Association 2008 Journal.pdf

5W 2008 Weather Modification Association 2008 Thunderbird Awards.pdf

5W 2008 Weather Modification Association Home Page November 2008.pdf

5W 2008 Weather Modification Inc. Australia 2008 Feasibility Study Rain Augmentation.pdf

5W 2008 Weather Modification Inc. Mali 2006-2008 Rainfall Enhancement+Products.pdf

5W 2008 Weather Modification Publications Information 2008.pdf

5W 2009 DAS Weather Modification DRI Website Microbe Research November 2009.pdf

5W 2009 Weather Modification, Inc. Aircraft Types – Website October 28, 2009.pdf

5W 2009 Weather Modification, Inc. Atmospheric Research Website October 28, 2009.pdf

5W 2009 Weather Modification, Inc. BAMEX Experiment October 28, 2009 Website.pdf

5W 2009 Weather Modification, Inc. California 2008-2009 American River Snowpack Augmentation.pdf

5W 2009 Weather Modification, Inc. Cloud Seeding Equipment+Methods October 28, 2009 Website.pdf

5W 2009 Weather Modification, Inc. Home Website October 28, 2009 Atmospheric Resource Management.pdf

5W 2009 Weather Modification Inc. Naval Surface Warfare Center 2009 Radar Validation Experiments.pdf

5W 2009 Weather Modification Inc. Naval Surface Warfare Center Radar Validation Experiments 2009.pdf

5W 2009 Weather Modification Inc. Nevada 1987-1988, 2002-2009 snowpack Augmentation.pdf

5W 2009 Weather Modification, Inc. North Dakota Cloud Modification Projects October 28, 2009.pdf

5W 2009 Weather Modification, Inc. Research Projects Website October 28, 2009.pdf

Follow

5W 2009 Weather Modification, Inc. Website Alberta, Canada October 28, 2009 Website.pdf

5W 2010 Climate Institute Board of Directors Feburary 7, 2010.pdf

5W 2010 Journal of Weather Modification Volume 37 – Page 104.pdf

5W 2010 Journal of Weather Modification WMA March 20, 2010.pdf

5W 2010 JWM Vol 34 Abstracts March 20, 2010 Weather Modification Association.pdf

5W 2010 JWM Vol 35 Abstracts March 20, 2010 Weather Modification Association.pdf

5W 2010 JWM Vol 36 Abstracts March 20, 2010 Weather Modification Association.pdf

5W 2010 JWM Vol 37 Abstracts March 20, 2010 Weather Modification Association.pdf

5W 2010 JWM Vol 38 Abstracts March 20, 2010 Weather Modification Association.pdf

5W 2010 JWM Vol 39 Abstracts March 20, 2010 Weather Modification Association.pdf

5W 2010 JWM Vol 40 Abstracts March 20, 2010 Weather Modification Association.pdf

5W 2010 JWM Vol 41 Abstracts March 20, 2010 Weather Modification Association.pdf

5W 2010 Weather Modifcation Inc. Clients+Projects+Map Website March 19, 2010.pdf

5W 2010 Weather Modification Association March 20, 2010 Website http____www.weathermodification.pdf

5W 2010 Weather Modification Inc. Aerial Cloud Seeding March 20, 2010.pdf

5W 2010 Weather Modification Inc. Alberta Canada Hail Suppression 1996-2010.pdf

5W 2010 Weather Modification Inc. Burkina Faso 2001-2010 Rainfall Enhancement Program Support.pdf

5W 2010 Weather Modification, Inc. California 2007-2010 Tuolumne River Snowpack Augmentation.pdf

5W 2010 Weather Modification Inc. Cloud Seeding Agents March 30, 2010 Silver Iodide+Salt or Calcium Chloride.pdf

5W 2010 Weather Modification Inc. Cloud Seeding March 20, 2010 Increasing Precipitation.pdf

5W 2010 Weather Modification Inc. Frequently Asked Questions March 20, 2010.pdf

5W 2010 Weather Modification, Inc. Ground-Based Cloud Seeding March 20, 2010.pdf

Follow

5W 2010 Weather Modification, Inc. Idaho 2002-2010 Snowpack Augmentation.pdf

5W 2010 Weather Modification, Inc. March 20, 2010 Activities Subject to Regulation or Control.pdf

5W 2010 Weather Modification, Inc. March 20, 2010 Aircraft.pdf

5W 2010 Weather Modification Inc. March 20, 2010 Dispersing Fog.pdf

5W 2010 Weather Modification Inc. March 20, 2010 Gound-Based Seeding Generators-Iridium Questions.pdf

5W 2010 Weather Modification, Inc. March 20, 2010 Monitoring+Tracers.pdf

5W 2010 Weather Modification Inc. Mitigating Hail Damage March 20, 2010.pdf

5W 2010 Weather Modification Inc. Morocco 2002-2010 Rainfall Enhancement Program Support.pdf

5W 2010 Weather Modification, Inc. North Dakota Cloud Modification Project-Hail+Rain 1961-2010.pdf

5W 2010 Weather Modification Inc. Saudi Arabia 2004, 2006, 2007-2010 Rainfall Enhancement.pdf

5W 2010 Weather Modification Inc. Weather Radar Systems March 20, 2010.pdf

5W 2010 Weather Modification Inc. Wyoming Weather Modification Pilot Program 2005-2010.pdf

5W 2010 Weather Modification Incorporated March 19, 2010 Website http www.weathermodification.pdf

5W 2010 Weather Modification Inc-March 20, 2010 Introduction of Cloud Seeding Agents.pdf

5W 2010 Weather Modification Inc Program Services March 20, 2010 Website.pdf

5X 1979 Jet Fuel JP-10 Carbon Black Dispersion Abstract 1979.pdf

5X 1982 Low-Temperature Atmospheric Oxidation of Mixtures of Titanium+Carbon Black or Boron SEPT 23, 1982.pdf

5X 2000 Carbon Black – Soot Eats Clouds Turns up Global Thermostat 2000 CNN.pdf

5X 2000 National Space Weather Program The Implementation Plan Table of Contents 2nd Edition FCM-P31-July 2000.pdf

Follow

5X 2002 Carbon Black 2002 Isotopc Carbon Black.pdf

5X 2003 NASA Soot As Pure as Snow Aerosols DEC 2003 Black Carbon by Hansen Jets Fuel Emissions Not Included http___www.giss.nasa.pdf

5X 2004 33 NASA One Type of Graphitic Carbon Black so Resilient it Skews Carbon Cycle Calculations JAN 22, 2004 .pdf

5X 2005 ENN News March 4, 2005 Cooking Linked to Climate Changes.pdf

5X 2007 ENN News Spetmeber 29, 2007 Increasing Atmospheric Moisture-Human Activities.pdf

5X 2008 Carbon + Carbon Black Lenntech Periodic Table Health Effects 2008.pdf

5X 2008 ENN News Black Carbon Pollution Major Global Warming Player March 24, 2008.pdf

5X 2008 ENN News Brown Carbon Climate Impacts August 18, 2008.pdf

5X 2009 33 NASA News Dirty Snow-Soot Causes Early Runoff-Cascades, Rockies JAN 12, 2009 Soot-Jets-Carbon Black.pdf

5YZ 2008 Cement Information Wikipedia 2008.pdf

5Y 1970 Abstract JAN 1970 Refractive Index Aluminum-Aluminum Oxide-Gold-Silver+Magnesium Oxide.pdf

5Y 1996 Federal Budget for Meteorological Services+Support Research Executive Summary 1997.pdf

5Y 1997 Acronyms+Abbreviations U.S. Weather Programs.pdf

5Y 1997 FAA+DEPT of Transportation+FAA Weather Programs 1997 Appendix C Report.pdf

5Y 1997 Federal Coordination+Planning of Meteorological Activities 1997.pdf

5Y 1997 Federal Coordination+Planning of Meteorological Activities 1997 – Copy.pdf

5Y 1997 Federal Plan for Meterological Services+Research Fiscal Year 1997 Table of Contents.pdf

5Y 1997 Military Weather Programs 1997 Appendix B Fiscal Year 1997.pdf

5Y 1997 Military+World Weather Program 1997 Goals Appendix E.pdf

5Y 1997 OFCM Acronyms+Abbreviations U.S. Weather Programs.pdf

Follow

5Y 1997 Section 3 FY1997 Resource Infomration+Agency Program Updates Meteorological Operations.pdf

5Y 1997 Space Weather 1997 A New Challenge for Meteorologists Introduction+Imapcts.pdf

5Y 2000 National Aviation Weather Forum July 2000 Conclusions+Recommendations.pdf

5Y 2000 Proceedings of the Aviation Weather Forum July 25-26, 2000.pdf

5Y 2000 The National Space Weather Program 2nd Edition July 2000.pdf

5Y 2003 National Post-Storm Data Acquisition Plan March 2003 Meteorological Services-Supporting Research.pdf

5Y 2005 Air Travel Contrails Future Science Daily February 5, 2005.pdf

5Y 2007 Cement NYTimes October 26, 2007 Climate Change.pdf

5Y 2008 Cement Weather Modification Russia June 17, 2008.pdf

5Y 2008 Chemical Drying Agents Abstact Search December 28, 2008 Results 6.pdf

5Y 2009 Concrete Being Remixed With Environment in Mind March 31, 2009 NYTimes.pdf

5Y 2009 Federal Plan for Meteorological Services+Research Updated August 17, 2009 Publications.pdf

5Y 2009 MPAR Presentations National Symposium NOV 17-19, 2009.pdf

5Y 2009 MPAR Sumposium II Summary Report NOV 17-19, 2009.pdf

5Y 2009 MPAR Symposium II Dr. Fred P. Lewis U.S. Air Force Weather Director NOV 17, 2009.pdf

5Y 2009 MPAR Symposium II Summary Report NOV 17-19, 2009.pdf

5Y 2009 National Weather Center NOV 17-19, 2009 MPAR Multifunction Phased Array Radar Symposium II.pdf

5Y 2009 NOAA Pacific Ocean Satellite Jet Contrail Picture May 18, 2009.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 A.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 B.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 C.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 D.pdf

Follow

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 E.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 F.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 G.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 H.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 I.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 J.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 K.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 L.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 M.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 N.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 O.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 P.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 Q.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 R.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 S.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 T.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 U.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 V.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 W.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 X.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 Y.pdf

5Y 2010 NOAA National Weather Service Glossary March 1, 2010 Z.pdf

5Y 2010 OFCM Special Projects Website March 28, 2010 Conferences+Workshops+Other.pdf

5Y 2010 OFCM Website March 28, 2010 Office Federal Coordinator for Meteorology http___www.ofcm.pdf

Follow

5Z 1980 Book Weather Modification by Cloud Seeding by Arnett S. Dennis 1980.pdf

5Z 1980 Book Weather Modification Prospects + Problems 1980.pdf

5Z 1980 Book Weather Modification Prospects+Problems Book Overview 1980.pdf

5Z 2003 No Comment Weather Modification Tinkering With Clouds January 2, 2003.pdf

5Z 2003 No Comment Weather Popular Mechanics 2003.pdf

5Z 2003 No Comment Weather Wars Popular Mechanics 2003.pdf

5Z 2004 HAARP Global Researcher USAF Questions 2004.pdf

5Z 2004 No Comment Clouds Wikipedia Photographs October 15, 2004.pdf

5Z 2004 No Comment Cloud Wikipedia 2004 Some Man-Made.pdf

5Z 2004 Ultimate Weapon of Mass Destruction-Owning the Weather-Military Use Chossudovsky SEPT 27, 2004.pdf

5Z 2004 Weather Modification System-Advanced Synoptic Technologies Company.pdf

5Z 2005 No Comment Jet Contrails Airliners.net 2005 id=332946&size=L&sok=V0hFUkU.pdf

5Z 2005 No Comment Weather Modification 2005.pdf

5Z 2005 Pictures + Article 2005 WEATHER WARS by Scott Stephens.pdf

5Z 2005 Pictures + Article January 15, 2005 WEATHER WARS by Stephens.pdf

5Z 2005 U.S. Senate Bill 517 Weather Modification Bill not Voted upon in U.S. Senate in 2006.pdf

5Z 2005 U.S. Senate Bill 517 Weather Modification Bill was not voted upon in U.S. Senate in 2005.pdf

5Z 2005 Washington New World Order Weapons-Weather Modification HAARP Weather Warfare by Michael Chossudovsky June 17, 2005.pdf

5Z 2005 Weather War October 8, 2005. The Daily Express.pdf

5Z 2006 Jet Contrail Picture of Interest – Weather Modification 2006.pdf

5Z 2006 Weather Modification The View From Washington, DC 2006 A.I.Physics.pdf

5Z 2007 Climate Censorship April 2007 Monbiot.pdf

Follow

5Z 2007 No Comment Jet Contrails Spell Trouble for Planet March 16, 2007.pdf

5Z 2007 No Comment Weather Modfication Portland Independent 2007.pdf

5Z 2007 No Comment Weather We Like It or Not! Website August 2007.pdf

5Z 2007 U.S. H.R. 2684 FAA Aviation Weather Research 2007.pdf

5Z 2007 U.S. House Bill 135 21st Century Water Commission Act of 2007.pdf

5Z 2007 U.S. House Bill 2698 Weather Funding Bill Aviation 2007.pdf

5Z 2007 U.S. House Bill 3445 Weather Experimentation 2007.pdf

5Z 2007 Wall Street Journal April 25, 2007 Halt Global Warming by Controlling Weather.pdf

5Z 2008 Anticrepuscular Rays Wikipedia July 31, 2008 Questions No Comment.pdf

5Z 2008 No Comment Cement Wikipedia 2008.pdf

5Z 2008 No Comment Weather Modification PDF Reports 2008.pdf

5Z 2008 No Comment Weather Modification Website The Blanket Effect 2008.pdf

5Z 2008 Weather Modification February 5, 2008 Article.pdf

5Z 2008 Weather Modification Hoag.pdf

5Z 2008 Weather Modification Hoag – Tesla Experiments.pdf

5Z 2008 Weather Warfare Chossudovsky 2008.pdf

5Z 2008 Weather Warfare Chossudovsky May 22, 2008.pdf

5Z 2009 National Climate Service Act U.S. House of Represenatative HR 2407.pdf

5Z 2009 U.S. Weather Map & Advisory by State Website December 30, 2009.pdf

5Z 2010 Book Critical Issues in Weathre Modification Research 2010.pdf

5Z 2010 Canada-Climate change March 16, 2010 by Stephen Leahy-Notes.pdf

5Z 2010 From Trees+Grass Bacteria that Cause Snow+Rain-Little Studied Weather Ecosystem NYTimes May 24, 2010 Montana.pdf

5Z 2010 January 16, 2010 Vanishing Weather Stations-Suspect Temperature Data Telegraph.co.uk.pdf

5Z 2010 USA Today 2010 The Weather Channel Resources-History Trying to Control the

Follow

Weather.pdf

5Z No Comment Weather Modification Is Cloud Seeding Harmful Micou.pdf

5Z Weather We Like It or Not! US-Law-Weather-Modification-.pdf

Share this: Twitter 253 Facebook StumbleUpon 1

Like this: Like 7 bloggers like this post.

This entry was posted in Weather Modification. Bookmark the permalink.

7 Responses to *Want to know about Chemtrails, HAARP , VLF, UHF and weather modification? Want to prove it to a non-believer? Here you go!*

R3zn8D *says:*
October 4, 2011 at 3:09 pm

Great info, will add these locations to my Google Earth weather mod database. Dutch check out these links to weather modification companies/papers/patents: https://www.rezn8d.com/weatherwars.html
Keep up the good fight!

authorthat *says:*
October 9, 2011 at 4:58 pm

Just as the purpose of this technology is used to separate the mind of humanity from God by sealing off the pineal gland from our dual nature, as it was in the firmament in the beginning, it will kill tens of thousands as it creates the new river in the new Madrid fault that will separate the nation, accompanied by revolution now begun by the 99%, which will bring martial law. It is required of those who see evil not to keep silent. To warn and guide the people I have begun my blog. http://authorthat.wordpress.com The Blogathon Philabuster. For one simple rule Mr. Payne....love thy neighbour.Many of you people don’t know about lost causes. Mr. Payne does. ” Mr. Smith Goes To Washington” James Stewart.

Pingback: *10/9/2011 — President Ahmadinejad says weather mod in EU causes drought in Iran | sincedutch*

Pingback: *“HAARP rings” appear through entire midwest — A.M.I.S.R. might be “scalar square” cause |*

Pingback: *HAARP ring outbreak across entire central USA |*

Eddie A. Ríos III *says:*
October 13, 2011 at 3:53 am

GREAT SITE!!

Pingback: *‘HAARP ring’ frequency explosion in the southeast USA .. FL, GA, AL, TN, SC, NC, VA also TX again |*

Comments are closed.

Follow

imbalances within the body. Hence the predominant attention in Chinese medicine and Taoist self-healing practice on the balancing and strengthening of the organs and their cooperative relationships.

The Taoist view on the outer and inner universe (the body), is the fruit of several thousands of years of highly sophisticated empirical observation. Thusly, feeling and sensing in the body and its structure, processes and needs, play a crucial role in creating balance within the body and between its organs and their energies, so that inner peace and harmony may grow (Formula 2, *Fusion of the Five Elements*)

Turning Inward

This involves a process of turning inward and to feel and sense oneself "from within" so that understanding can grow. This in turn further supports the effectiveness of the inward-oriented process of listening. By turning the senses inward and reconnecting them with their corresponding organs (ears/kidneys, eyes/liver, tongue/heart, mouth/spleen, nose/lungs) the process of externalizing the consciousness and thereby draining the energies out of the body can be inverted. This allows the body to come to rest and recuperate its energies and the connected senses.

By protecting the senses from undue outside influences, the life force energies in the body and the higher energies it accumulates, through the blending with the energies from all the directions, but especially those from the stars and the sun and moon and planets, are preserved and can grow without interference (*Cosmic Fusion,* Formula 3).

This process of protection is further deepened and completed in the high formula of Sealing the Five Senses of the Kan and Li Practices where protective auras are created around the body from the accumulated energies of each of the major organs.

There is abundant evidence that in the process of externalization which has been imposed on the body in the process of modernization and its growing pressures on the body, the senses have become atrophied. By turning them inward, it becomes more easy to control them and protect the integrity of the body and its organs so that it can regenerate.

DUTCHSINSE = SINCEDUTCH

Theme: Twenty Ten Blog at WordPress.com.

Follow

ICRC

VOLUME 1

WAR SURGERY

WORKING WITH LIMITED RESOURCES IN ARMED CONFLICT AND OTHER SITUATIONS OF VIOLENCE

0973/002 03.2009 3,000

ICRC

WAR SURGERY

WORKING WITH LIMITED RESOURCES
IN ARMED CONFLICT
AND OTHER SITUATIONS OF VIOLENCE

VOLUME 1

ICRC

REFERENCE

WAR SURGERY

WORKING WITH LIMITED RESOURCES
IN ARMED CONFLICT
AND OTHER SITUATIONS OF VIOLENCE

VOLUME 1

C. Giannou M. Baldan

ICRC

International Committee of the Red Cross
19 Avenue de la Paix
1202 Geneva, Switzerland
T + 41 22 734 60 01 F + 41 22 733 20 57
E-mail: shop.gva@icrc.org
www.icrc.org
© ICRC, March 2009

Cover photos: A. Bakkour/ICRC; A. Bakkour/ICRC; V. Louis/ICRC.

PREFACE

In 1863, a small group of Swiss citizens founded the International Committee of Geneva for the Relief of Wounded Soldiers. A year later, an international diplomatic conference negotiated the first Geneva Convention for the Amelioration of the Condition of Wounded Soldiers in the Field, which to this day is one of the cornerstones of international humanitarian law, and gave the International Committee of the Red Cross its definitive name.

International humanitarian law – the law of war – has developed since, and the mandate, role and activities of the ICRC have expanded to include both protection and assistance for all the victims of armed conflict and other situations of violence. Assistance and relief programmes are now run according to a public health approach and aim to be holistic regarding human needs while respecting the dignity of each and every one.

War surgery – the care of the wounded in armed conflict and other situations of violence – remains a pillar of the ICRC's identity. Over the years, ICRC hospital teams have unfortunately been witness to a great deal of physical and mental suffering in this world. Through caring for the sick and wounded in so many different conflict zones, the ICRC and its partners in the International Red Cross and Red Crescent Movement have developed an expertise they are keen to share, and created a pool of human resources ever willing and prepared to help alleviate some of the suffering.

This new manual presents some of this expertise, gained at great human cost, in the hope that one day it will no longer be required.

Jakob Kellenberger

President
International Committee of the Red Cross

TABLE OF CONTENTS

INTRODUCTION 9

Chapter 1 SPECIAL CHARACTERISTICS OF SURGERY IN TIMES OF CONFLICT 17
1.1 Differences between surgery in times of conflict and civilian practice 19
1.2 How war surgery differs 20
1.3 "Surgeries" for victims of war 25
1.4 Differences between military and non-military war surgery: the ICRC approach 27
Annex 1. A ICRC criteria for introducing a new technology 31

Chapter 2 APPLICABLE INTERNATIONAL HUMANITARIAN LAW 33
2.1 Historical introduction 35
2.2 International humanitarian law: basic principles 36
2.3 The distinctive emblems 38
2.4 The International Red Cross and Red Crescent Movement and its Fundamental Principles 39
2.5 Rights and duties of medical personnel according to IHL 39
2.6 Responsibility of States 41
2.7 Reality check: some people do not follow the rules 43
2.8 The neutrality of a National Red Cross/Red Crescent Society 44
2.9 The role and mandate of the ICRC in situations of armed conflict 45
Annex 2. A The distinctive emblems 48
Annex 2. B The International Red Cross and Red Crescent Movement 50

Chapter 3 MECHANISMS OF INJURY DURING ARMED CONFLICT 53
3.1 The various mechanisms of injury 55
3.2 Ballistics 59
3.3 Terminal ballistics 63
3.4 Wound ballistics 70
3.5 Wound dynamics and the patient 78

Chapter 4 RED CROSS WOUND SCORE AND CLASSIFICATION SYSTEM 81
4.1 Applications of the RCWS and classification system 83
4.2 Principles of the Red Cross Wound Score 84
4.3 Grading and typing of wounds 88
4.4 Wound classification 88
4.5 Clinical examples 89
4.6 Conclusions 91

Chapter 5 THE EPIDEMIOLOGY OF THE VICTIMS OF WAR 93

5.1 Introduction: purpose and objectives 95
5.2 Public health effects of armed conflict 95
5.3 Epidemiology for the war surgeon 98
5.4 General questions of methodology 101
5.5 Aetiology of injury 104
5.6 Anatomic distribution of wounds 106
5.7 Fatal injuries 110
5.8 The lethality of context: delay to treatment 114
5.9 Hospital mortality 117
5.10 ICRC statistical analysis of hospital workload 118
5.11 Conclusions: lessons to be gained from a study of epidemiology 121
Annex 5. A ICRC surgical database 123
Annex 5. B Setting up a surgical database for the war-wounded 125

Chapter 6 THE CHAIN OF CASUALTY CARE 129
6.1 The links: what kind of care, and where? 131
6.2 Surgical hospital treating the war-wounded 133
6.3 Transport 134
6.4 Forward projection of resources 135
6.5 The reality: common war scenarios 136
6.6 Conflict preparedness and implementation 137
6.7 The pyramid of ICRC surgical programmes 138
Annex 6. A Initial assessment of a surgical hospital treating the war-wounded 140
Annex 6. B Strategic assessment of a conflict scenario 146
Annex 6. C Humanitarian intervention for the wounded and sick: typical settings 148

Chapter 7 FIRST AID IN ARMED CONFLICT 153
7.1 First aid: its crucial importance 155
7.2 First aid in the chain of casualty care 156
7.3 First aiders: an important human resource 157
7.4 Essential elements of the first-aid approach and techniques 157
7.5 Setting up a first-aid post 159
7.6 ICRC involvement in first-aid programmes 161
7.7 Debates, controversies and misunderstandings 161

Chapter 8 HOSPITAL EMERGENCY ROOM CARE 169
8.1 ABCDE priorities 171
8.2 Initial examination 171
8.3 Airway 172
8.4 Breathing and ventilation 175
8.5 Circulation 177
8.6 Blood transfusion where supplies are limited 181
8.7 Disability 184
8.8 Environment/exposure 185
8.9 Complete examination 185

Chapter 9 HOSPITAL TRIAGE OF MASS CASUALTIES 189
9.1 Introduction 191
9.2 Setting priorities: the ICRC triage system 193
9.3 How to perform triage 196
9.4 Triage documentation 198
9.5 Emergency plan for mass casualties: disaster triage plan 199
9.6 Personnel 200
9.7 Space 202
9.8 Equipment and supplies 203
9.9 Infrastructure 204
9.10 Services 204
9.11 Training 204
9.12 Communication 204
9.13 Security 205
9.14 Summary of triage theory and philosophy: sorting by priority 206
Annex 9. A Sample triage card 207
Annex 9. B Hospital emergency plan for a mass influx of wounded 208

Chapter 10 SURGICAL MANAGEMENT OF WAR WOUNDS 211
10.1 Introduction 213
10.2 Complete examination 214
10.3 Preparation of the patient 215
10.4 Examination of the wound 216
10.5 Surgical treatment 216
10.6 Retained bullets and fragments 221
10.7 Final look and haemostasis 222
10.8 Wound excision: the exceptions 223
10.9 Leaving the wound open: the exceptions 224
10.10 Dressings 225
10.11 Anti-tetanus, antibiotics, and analgesia 226
10.12 Post-operative care 226

Chapter 11 DELAYED PRIMARY CLOSURE AND SKIN GRAFTING 229
11.1 Delayed primary closure 231
11.2 Skin grafting 233
11.3 Full-thickness grafts 238
11.4 Healing by secondary intention 240

Chapter 12 NEGLECTED OR MISMANAGED WOUNDS 243
12.1 General considerations 245
12.2 Chronic sepsis: the role of biofilm 247
12.3 Surgical excision 248
12.4 Antibiotics 250
12.5 To close or not to close? 251

Chapter 13 INFECTIONS IN WAR WOUNDS 253
13.1 Contamination and infection 255
13.2 Major bacterial contaminants in war wounds 256
13.3 Major clinical infections of war wounds 257
13.4 Antibiotics 263
13.5 Neglected or mismanaged wounds 265
Annex 13. A ICRC Antibiotic protocol 266

Chapter 14 RETAINED BULLETS AND FRAGMENTS 269
14.1 The surgeon and the foreign body 271
14.2 Early indications for removal 271
14.3 Late indications 274
14.4 Technique for the removal of a projectile 275

Chapter 15 BURN INJURIES 277
15.1 Introduction 279
15.2 Pathology 279
15.3 Burn management 282
15.4 Burns presenting late 286
15.5 Nutrition 286
15.6 Care of the burn wound 286
15.7 Closure of the burn wound 289
15.8 Scar management 293
15.9 Electrical burns 294
15.10 Chemical burns 294
Annex 15. A Nutrition in major burns: calculating nutritional requirements 297

Chapter 16 LOCAL COLD INJURIES 299
16.1 Physiology of thermal regulation 301
16.2 Types of local cold injuries 301
16.3 Management 302

Chapter 17 ANAESTHESIA AND ANALGESIA IN WAR SURGERY 305
17.1 Introduction 307
17.2 Anaesthesia methods 308
17.3 Local and regional anaesthesia 309
17.4 Dissociative anaesthesia with ketamine 310
17.5 Post-operative pain management 312
Annex 17. A ICRC pain management protocols 314

Chapter 18 DAMAGE CONTROL SURGERY AND HYPOTHERMIA, ACIDOSIS, AND COAGULOPATHY 319
18.1 Resuscitative surgery and damage control surgery 321
18.2 Hypothermia, acidosis, and coagulopathy 322

ACRONYMS 329

SELECTED BIBLIOGRAPHY 333

The Taoist approach to the body is rooted in the vision that there is an inner order in the very nature of the universe and all its manifestations. The outer order is a manifestation and reflection of this inner order. If the outer order is in harmony with the inner order, then harmony and peace reign.

As our receptivity and ability to sense and feel ourselves from within grows, so grows our ability to experience the universe within ourselves. By looking deeply into ourselves we grow. Our understanding of our being and body as a microcosmos, and its intrinsic unity with the universe as a macrocosmos, grows.

From Balance through Resonance to Love

As our body and its chemistry and we ourselves are changing, our consciousness and perceptions also change and widen. Then a point will come where we begin to experience ourselves less as separate and isolated from the universe and more in resonance and in tune with the universe.

In this process, we grow more aware of the wave-like nature of our body in and through which the universe pulses within us and how we pulse in and though our bodies with the energies and forces of the universe. At the same time our ability to tune in with the energy of the universe and its frequencies and to absorb and draw this energy into ourselves will grow.

The Fusion Practices serve an essential function in making our being more open through the heightened sensitivity of the body, as our energies become purified and more fine and subtle. The desire rises within the body to enter into the primordial unity with the original energy by which it was originated as a living being.

In the ancient Taoist vision this relationship has always been seen as a love relationship which reveals itself when our body returns to its inner balance and Yin and Yang enter into balance. The ability to attract and conduce the energies from the universe into one body through the network of conduits, represented by the grid of meridians, is dependent on the quality of the inner work towards unity between Yin and Yang.

This meeting between Yin and Yang has in the Taoist tradition been seen as a marriage, born out of love between the opposites, as they move towards unity. The Fusion Practices play an important role in the preparation of a state of being which make this movement towards unity possible.

INTRODUCTION

Our common goal is to protect and assist the victims of armed conflict and to preserve their dignity. This book is dedicated to the victims of situations which, in a better world, would not exist.

Facing the challenges

One night while on duty Dr X, an experienced surgeon working in an ICRC field hospital in the midst of a civil war, performed a craniotomy on one patient injured by a bomb, an amputation following an anti-personnel landmine injury on another, and a laparotomy after a gunshot wound on the third; not to mention the emergency Caesarean section that arrived, as always, at the most inopportune time, after midnight. She was the only surgeon available that night. This was common practice at the time, and not very much has changed in the last thirty-odd years.

Standard peacetime health services are already limited or lacking in many low-income countries, and faced with the added burden of weapon-wounded they are quickly overwhelmed. A precarious healthcare system is one of the first victims of armed conflict: the disruption of supply lines, the destruction of premises and the flight of medical personnel are all too common.

The lack of adequate resources is not limited to diagnostic and therapeutic technologies. Above all there is a dearth of human resources. Surgeons trained to practise in multidisciplinary teams find themselves alone to face the entire surgical workload and deal with subspecialties with which they have, at best, only a passing acquaintance. Reverting to the philosophy, so common 50 years ago, of the multidisciplinary single surgeon who has to "do it all" is not an easy task.

ICRC teams usually include only one or two surgeons. They are generalists, able to treat all kinds of injuries from simple soft-tissue wounds to penetrating abdominal and head injuries and complicated fractures. They must also provide emergency non-trauma surgical and obstetric care for the civilian population in the area. Ideally, they should be very general surgeons with a broad approach and wide experience.

The principles of war surgery have been known for centuries but need to be relearned by each new generation of surgeons and in every new war.

This commonly held view remains true to this day. Whether performed by military or by civilian surgeons, war surgery has its particular characteristics that are due to the special nature of the context of armed conflict, its limitations and dangers, and the particular physio-pathology of high-energy, penetrating missile and blast wounds. The care of weapon-wounded patients follows accepted surgical standards, but is performed under extreme conditions, which is why the management of a gunshot wound due to criminal violence in a civilian context cannot be easily extrapolated to surgery in a situation of armed conflict.

Where only limited resources are available the surgeon must accept that he cannot fully utilize his capacities and expertise.

Working with limited resources means that the limits of surgery that can be performed are not the expertise of the surgeon, but rather the level of anaesthesia and post-operative nursing care, and the availability of diagnostic and therapeutic equipment.

Limited resources, even in peacetime, may lead to the death of patients who would have survived had more sophisticated means been available. This is often the case in remote, and not so remote, hospitals in low-income countries; a situation exacerbated during armed conflict.

When the principles of triage are applied, saving "life and limb" for the greatest number, with the least possible expenditure of time and resources, often takes precedence.

Indeed, these characteristics mean that war surgery is very different from that practised in peacetime, when most operations are elective and most trauma is blunt, and the surgeon concentrates on doing everything he possibly can – using the full range of resources necessary – for each and every patient.

Furthermore, the work of medical staff in a situation of armed conflict is governed by a special set of rules, in addition to standard medical ethics: international humanitarian law, or the law of war. This is yet another specificity of this type of surgical care and is important for the security of patients and medical personnel alike living and working under dangerous circumstances.

International humanitarian law – the law of war – complements medical ethics in times of armed conflict or other situations of violence.

The ICRC's experience

The ICRC has been providing medical care for the war-wounded ever since its inception, for example during the Franco-Prussian War (1870). The 1970s and 80s, however, saw a tremendous increase in the already considerable humanitarian activities for the victims of war, armed conflict, and other situations of violence. These included relief efforts for refugees, internally displaced persons, and the affected resident population, and medical care for the sick and wounded. In addition, many new organizations were founded and, together with United Nations agencies, they deployed renewed efforts to respond to these humanitarian challenges.

The ICRC embarked on large-scale programmes to provide surgical care for the victims of war. Several independently-run ICRC hospitals were established and surgical staff recruited from various national Red Cross/Red Crescent Societies and Switzerland. A large number of enthusiastic and idealistic surgical staff set off on humanitarian missions. The surgeons were well-trained and experienced, but their training and experience were largely confined to sophisticated hospital facilities in industrialized countries. They faced a steep learning curve.

The ICRC also faced a steep learning curve and has acquired considerable expertise in caring for the victims of conflict in settings where the healthcare system is severely disrupted. This know-how derives from three different, but related programmes in various countries afflicted by armed conflict and other situations of violence around the world.

1. Independent ICRC-run hospitals.
2. Support to local hospitals through the short-term presence of expatriate surgical teams, with a strong focus on training and capacity building; the provision of supplies and equipment; the renovation of infrastructure and water and sanitation facilities; and financial incentives and salaries for local staff when necessary.
3. Organization of war surgery seminars, which provide opportunities for colleagues to exchange experiences and expertise.

This three-pronged approach has enabled the ICRC to develop basic clinical protocols and procedures for surgical techniques appropriate to the management of weapon-wounded patients in situations of limited resources and precarious circumstances. In addition, over the last thirty years, the ICRC has trained and maintained a pool of experienced hospital personnel who do not have to re-invent everything with each new conflict.

However, thanks to more widespread educational opportunities in recent years, there has been a sharp increase in the number of surgeons in conflict-afflicted countries. This has allowed the ICRC to switch the emphasis of its programmes from one of substitution – i.e. independent ICRC hospitals – for a poorly-functioning or non-existent hospital system to one that focuses on support and training of medical personnel in the niceties of the management of patients wounded by the weapons of war.

As part of its training programmes, the ICRC has co-organized more than 120 war surgery seminars – over a dozen a year – in the last decade. On these occasions much expertise and many ideas have been exchanged between surgeons from a number of countries – with a varying degree of experience in war trauma – and ICRC surgeons. We have all learned from these discussions, and some of the lessons are reflected in the contents of this new book.

However, in several contexts the ICRC has continued to provide direct surgical services in a neutral and impartial manner. This form of substitution contributes a fundamental element to the protection of the victims and the medical mission in situations where these humanitarian principles have been sorely tried.

While a number of manuals on war surgery have been published, they are mostly produced by and for the armies of industrialized countries. Their operational norms usually require large investments in means and personnel: helicopter evacuation of patients; well-trained field medics and stretcher-bearers; sophisticated technology; multidisciplinary teams of specialist surgeons, anaesthetists, and nurses. ICRC surgical staff refer to these manuals as references but the conditions and means described therein are seldom met in present-day theatres of armed conflict. Many of their "lessons" are inadequate – or even irrelevant – to humanitarian war surgery or the functioning of public hospitals in many countries working with limited resources.

ICRC surgical care aims to be economical, non-specialized, based on solid scientific principles, and offer good returns given the constraints. The clinical protocols and surgical techniques described in this manual are the standard procedures used among the ICRC's pool of experienced surgeons.

Putting pen to paper

To meet the challenge posed by these conditions, our predecessors in the surgical department of the Medical Division of the ICRC edited a basic reference manual for surgeons embarking on their first humanitarian mission: *Surgery for Victims of War*.

The first three editions of this book have been extensively distributed and received wide acclaim the world over from surgeons who faced the challenge of treating war-wounded patients for the first time. The general surgeon in an isolated rural hospital has perhaps drawn the greatest benefit from it.

Originally intended as a fourth edition of *Surgery for Victims of War* to address the particular needs and specific requests many of our colleagues raised during ICRC-led seminars, as well as to reflect the developments in ICRC surgical practice, it soon became clear that a new book would better serve this purpose. This book now comprises a significant amount of new material to be presented in two volumes, while maintaining the basic reasoning of the original manual.

This first volume is devoted to broad topics, with a number of entirely new chapters of a more general character whose contents are relevant not only to surgeons but also to those responsible for the organization and coordination of surgical programmes in times of armed conflict and other situations of violence. It presents the characteristics of surgical care for the victims of war, in particular the epidemiological, organizational and logistic aspects, drawing on the experience of ICRC medical staff and other colleagues. The second volume will deal with weapon-related trauma to specific body systems.

The surgical techniques presented herein share many fundamental ideas with more sophisticated medical services. However, they also derive from tried-and-tested improvisation and the use of very simple methods of treatment aiming to use technological means as appropriate as possible to the prevailing conditions of limited infrastructure, equipment, and human resources.

The explanations of techniques are geared to the level of knowledge and practice of *general surgeons in a rural hospital*. These surgeons are often the first to see patients wounded in conflict and they know that, under the circumstances, referral to more sophisticated facilities – far away in an inaccessible capital city – is impractical or impossible. This book attempts to provide surgeons who do not have specialized training with basic advice about the treatment of various weapon wounds, describing the types of operations that have proved successful in ICRC and other comparable practice.

The manual and other basic ICRC surgical publications and documents of general interest are included in the DVD attached to this volume. The disk also contains several downloadable files – forms and checklists for example – that can be used in everyday practice and adapted by the reader.

Unless stated otherwise masculine nouns and pronouns do not refer exclusively to men, for the manual is gender neutral. Any use of trade or brand names is for illustrative purposes only and does not imply any endorsement by the ICRC.

We hope that civilian and military surgeons, as well as Red Cross/Red Crescent surgeons, facing the challenge of treating the victims of armed conflict and other situations of violence for the first time under precarious and, at times dangerous, circumstances will find this book useful.

Marco Baldan

Philippa Parker	Christos Giannou	Marco Baldan
Head of Health Unit ICRC Assistance Division	Former ICRC Head Surgeon	ICRC Head Surgeon

Acknowledgements

This manual is based on *Surgery for Victims of War*, first published by the ICRC in 1988 and edited by Daniel Dufour, Michael Owen-Smith, and G. Frank Stening. The authors included:
Bernard Betrancourt, Switzerland
Daniel Dufour, Switzerland
Ora Friberg, Finland
Soeren Kromann Jensen, Denmark
Antero Lounavaara, Finland
Michael Owen-Smith, United Kingdom
Jorma Salmela, Finland
Erkki Silvonen, Finland
G. Frank Stening, Australia
Björn Zetterström, Sweden
and was illustrated by Penelope L. Zylstra (Australia). Many of her line drawings have been included in the present book.

The second edition (1990) was revised by Robin Gray (United Kingdom) and the third (1998) by Åsa Molde (Sweden).

We owe a debt of gratitude to their pioneering work, and their clear and simple approach which has served as a model.

The present publication has benefited from the input of many colleagues with much experience within the ICRC and outside it. Critical comments and valuable advice throughout were provided by:
Ken Barrand, United Kingdom
Franco De Simone, Italy
Herman Du Plessis, South Africa
Jacques Goosen, South Africa
Åsa Molde, Sweden
Valery Sasin, Byelorussia
Harald Veen, Netherlands
Gunter Wimhoefer, Germany

Beat Kneubuehl (Switzerland) acted as the scientific adviser on ballistics and Sylvain Vité (Switzerland), an ICRC jurist, provided technical expertise on international humanitarian law and revised the appropriate sections. Massey Beveridge (Canada) served as technical adviser on burns and skin grafting and made significant contributions to the relevant chapters.

The chapter on the Red Cross Wound Score is largely based on the revised edition of the ICRC brochure by Robin Coupland (United Kingdom), who also provided essential comments and advice on ballistics and epidemiology, and has moreover played an important role through his many other pertinent publications. Holger Schmidt (Germany) and Eric Bernes (France) gave advice on first aid and emergency room trauma care. Haide Beckmann (Germany) and Thomas Walker (Switzerland) made contributions to the chapter on anaesthesia and Dieter Jacobi (Germany) provided comments for the chapter on chronic infections.

The ICRC Master Surgeons Workshop, held in Geneva in March 2002, revised the Red Cross Wound Score, ICRC triage categories, and established the ICRC antibiotic protocol. Participants included:
Marco Baldan, Italy
Massey Beveridge, Canada
Christos Giannou, Greece-Canada
François Irmay, Switzerland
Dieter Jacobi, Germany
Ben Mak, Netherlands
Valery Sasin, Belarus
Jukka Siegberg, Finland
Harald Veen, Netherlands
Gunter Wimhoefer, Germany

In addition, the ICRC Senior Anaesthetists Workshop, held in Geneva in November 2002, was the basis for the chapter on anaesthesia and established the ICRC pain management protocol. Its participants included:
Sunao Asai, Japan
Haide Beckmann, Germany
Lisa Bennett, Australia
Jeanne Frossard, United Kingdom
Christiane Gerber, Switzerland
Christos Giannou, Greece-Canada
Tuula Kangas-Saarela, Finland
Svante Linden, Sweden
Peter Mahoney, United Kingdom
Barthélémy Merzouga, Switzerland
Pascal Ollé, France
Erkki Saarela, Finland
Bernadette Sterckx, France
Vladislav Virago, Belarus
Eric Vreede, Netherlands
Jolanda Walker, Switzerland

Both workshops also helped define the ICRC criteria for the adoption of new technologies, the level of laboratory expertise required, and general strategies for ICRC surgical programmes.

Christiane de Charmant handled the editing of the final text and was responsible for the production while Pierre Gudel provided the graphic design. Their contribution is greatly appreciated.

The authors are ICRC staff members and no outside financial or material support has been received for the publication of this book.

Enlightenment of the Body and New Physics

The Taoist insight that human beings, with all other phenomena, share common origins in the universe and that our origins are in heaven and originate in the stars is shared in many other ancient cosmologies: those of the African peoples, the indigenous peoples of North and South America, as well as the Australian aboriginal people.

The Taoist tradition, however, is unique in that it has evolved over time concrete practical formulas and practices to work with. These help us to reconnect and in the process rediscover the inherent ecstatic nature of our body, through the process of self-transformation.

These formulas, of which the Fusion Practices are an integral part, are based on the insight of the nature of the meridians and their application in healing the body and restoring its natural functions, which form the basis of Chinese medicine.

A closely related Taoist thesis on the nature of the universe, also to be found in all ancient cosmological traditions, including those in the West (before the scientific revolution did away with them, viewing them as superstition) is the unity, indivisibility and interchangeability of matter and energy.

This thesis finds full support in the new physics which evolved from the beginning of this century with the path-breaking discoveries in quantum physics and relativity theory by the great physicists Bohr, Einstein and Heisenberg.

Their discoveries shattered the foundations of the old paradigm, underlying Cartesian-Newtonian physics, at the basis of modern science. They broke radically new ground in the interpretation of the nature of matter. In the new vision of advanced physics, matter, in its inner nature, is understood as a process and an event. Matter and energy are forms of the same reality. As matter can change into energy, also energy can change into matter. Both matter and energy are viewed in this new interpretation of reality as having their origin in light.

Therefore the Taoist vision on the intrinsic nature of the body as a light body is not a romantic vision, invented by creative minds. The image, underlying it, corresponds to the insights of advanced physics. Thus what has been called in ancient spiritual traditions “enlightenment” refers to a real material process: the illumination of the body.

Chapter 1

SPECIAL CHARACTERISTICS OF SURGERY IN TIMES OF CONFLICT

1. SPECIAL CHARACTERISTICS OF SURGERY IN TIMES OF CONFLICT

1.1 Differences between surgery in times of conflict and civilian practice 19

1.2 How war surgery differs 20
1.2.1 IHL: protection of non-combatants and those *"hors de combat"* and the rights and obligations of medical personnel 20
1.2.2 Specific epidemiology of war wounds 21
1.2.3 Predominance of emergency surgery 21
1.2.4 Surgery in a limited technical environment 21
1.2.5 Surgery in a hostile, violent environment 21
1.2.6 Mass casualties involving the principles of triage 22
1.2.7 Triage and surgery in successive echelons 22
1.2.8 Outcome of hospital patient care depends on the efficiency of pre-hospital echelons 23
1.2.9 Specific wound pathology: bullets, bombs, blast weapons and non-conventional weapons 24
1.2.10 Specific techniques appropriate to the context and pathology 24
1.2.11 Increased prevalence of endemic disease 25

1.3 "Surgeries" for victims of war 25

1.4 Differences between military and non-military war surgery: the ICRC approach 27
1.4.1 Military-civilian cooperation 27
1.4.2 Constraints: security 27
1.4.3 Constraints: logistics 28
1.4.4 Constraints: hospital equipment 28
1.4.5 Constraints: blood transfusion 29
1.4.6 Constraints: geography and climate 29
1.4.7 Constraints: culture shock 29
1.4.8 Constraints: the human factor 30

ANNEX 1. A ICRC criteria for introducing a new technology 31

1.1 Differences between surgery in times of conflict and civilian practice

The differences between civilian and war trauma are manifold – as are the differences between the experience of the ICRC and those of conventional military medical services.

Most surgeons today, the world over, derive their trauma training from road-traffic accidents and much that applies to the management of casualties in civilian settings will also apply to the situation of armed conflict: war surgery follows classical surgical standards. However, the generation of surgeons who mostly had to deal with accidents among agricultural or industrial workers were well aware of the dangers of gas gangrene and tetanus and the necessity of good wound excision and delayed primary closure. It was relatively easy for the surgeon to shift from this "septic" civilian surgery to war wounds. This is no longer the case for many surgeons trained today; laparoscopy, radioscopic embolization, and unreamed intramedullary nails will not get you very far when facing a landmine injury of the abdomen or a machine-gun wound to the thigh. Early specialist training of surgeons and sophisticated modern technology benefit many patients in a peacetime environment, but can be an obstacle to the practice of surgery during armed conflict.

War wounds are different. The extent of tissue destruction and contamination seen in war injuries is nothing like what is seen in everyday trauma practice. Working conditions during war are radically different from those prevailing in peacetime. Resources are limited and surgeons are often obliged to improvise or make compromises in their management decisions. Their aim should be to bring the best care possible to their patients under the circumstances, not the best care as described in the academic literature.

War surgery is a surgery of mass casualties. The logic of war triage has little to do with the routine emergency department triage of a major civilian trauma centre: war triage has a "leave to die in dignity" category unheard of in everyday civilian practice.

War surgery involves the staged surgical management of the wounded, often at different echelons of care and provided by different surgeons, especially in a military context. Even in a humanitarian context, such as ICRC surgical programmes, several surgeons deployed on short missions may participate in the treatment of a single patient. In everyday civilian practice on the other hand, the same surgeon assumes responsibility for the entire surgical management of his or her patient. While modern civilian practice often involves a "multidisciplinary approach", war surgery often demands a "multi-surgeon" approach.

> "All the circumstances of war surgery thus do violence to civilian concepts of traumatic surgery."
>
> Michael E. DeBakey[1]

These and other challenges mean that practitioners facing surgery for the victims of war for the first time will have to change their mindset, i.e. their "professional mental software".

---

[1] DeBakey M E. Military surgery in World War II – a backward glance and a forward look. *NEJM* 1947; **236**: 341 – 350. Michael E. DeBakey (1908 – 2008), an American surgeon of Lebanese origin, was a pioneer of modern cardio-vascular surgery. His treatise on the management of vascular trauma constitutes a basic reference. He invented the concept of Mobile Army Surgical Hospitals (MASH) for the US armed forces in Korea.

1.2 How war surgery differs

> War surgery is the management of an "epidemic of trauma" in a series of steps: echelons.
>
> N. I. Pirogov[2]

A number of special features characterize the practice of surgery in time of war.[3]

1. Special rules: international humanitarian law (IHL), i.e. the protection of the sick and wounded, and the rights and obligations of medical personnel.
2. Specific epidemiology of war wounds.
3. Predominance of emergency surgery.
4. Surgery in a limited technical environment.
5. Surgery in a hostile, violent environment: constraints of the tactical situation.
6. Mass casualties involving the principles of triage.
7. Triage and surgery in successive echelons of casualty care.
8. Outcome of hospital patient care is a function of the efficiency of pre-hospital echelons.
9. Specific wound pathology: bullets, bombs, blast, non-conventional weapons.
10. Specific techniques appropriate to the context and pathology.
11. Increased prevalence of endemic disease.

ICRC

Figure 1.1

Soldiers "*hors de combat*": POWs.

1.2.1 IHL: protection of non-combatants and those "*hors de combat*" and the rights and obligations of medical personnel

The Geneva Conventions of 1949 and their Additional Protocols of 1977 define categories of individuals who, by virtue of these treaties, are protected during armed conflict. These include non-combatants, combatants who no longer participate in hostilities – "*hors de combat*" – either through sickness, injury, shipwreck, or by becoming prisoners of war; and those who care for the sick and injured, namely medical and religious personnel. The latter two use the protective emblem of the red cross, red crescent or red crystal to mark the means and facilities that take care of the sick and wounded. According to the law, all these categories of protected individuals are immune from attack, as long as they do not take an active part in hostilities. International humanitarian law – the law of war – offers particular rights to medical personnel, but also ascribes obligations to them.

All health professionals are bound by medical ethics, in times of peace and of war. These are not replaced but are complemented by international humanitarian law. Compliance with these laws may create particular ethical dilemmas and security problems, and the military hierarchy does not always understand the demands of medical ethics. Civilian health staff may face particularly problematic and dangerous situations during a civil war where their own community is involved in the conflict. Chapter 2, Applicable international humanitarian law, explains the main principles and rules governing the rights and obligations of medical staff in times of armed conflict.

Japanese Red Cross Society

Figure 1.2

Soldiers "*hors de combat*": the wounded.

ICRC

Figure 1.3

Those who care for the sick and wounded.

---

[2] Nikolai Ivanovich Pirogov (1810 – 81): Russian anatomist and surgeon, professor at the Academy of Military Medicine, St Petersburg. Founded modern field surgery during the Crimean War (1854); devised the plaster cast and the mass use of anaesthesia on the battlefield and wrote a reference field surgery manual. Representative of the Russian Red Cross sent to inspect the hospitals on both sides during the Franco-Prussian War in 1870.

[3] List modified and adapted from bibliographic sources.

1.2.2 Specific epidemiology of war wounds

The nature of warfare – on land, at sea or in the air – will create a particular epidemiology of the wounded. The nature of weapons, protective body armour, and any delay in transport will affect the anatomic distribution of injuries and their severity. The understanding of these epidemiological factors will have important consequences in terms of preparation and allocation of resources: i.e. standardized supplies and specialized personnel (see Chapter 5).

1.2.3 Predominance of emergency surgery

War surgery primarily consists of emergency surgery, especially during early tactical field care. Sophisticated techniques or reconstructive procedures have no place here, except well after combat and in a distant referral hospital (see Chapters 6 and 8).

1.2.4 Surgery in a limited technical environment

The environment in times of war is bleak and harsh. The limits of surgical work are largely determined by the logistic difficulties attending the supply of remote and dangerous areas and the lack of maintenance, repair and spare parts. There is seldom enough technical support staff to ensure that infrastructure functions correctly.



V. Louis / ICRC

Figure 1.4
Surgery in a limited technical environment.

Despite lavish outlays for field hospitals by the armies of modern industrialized countries, equipment limitations in tactical situations are well recognized. The lack of sophisticated diagnostic equipment rather than the surgeon's technical capabilities and expertise is often what determines what can be done. What is essential must be differentiated from what is "nice to have".

1.2.5 Surgery in a hostile, violent environment

The adverse conditions of a tactical situation may put the safety of patients and medical personnel at risk, and thereby create less than optimal working conditions. Dangerous evacuation routes may compromise transport and result in delays. Security must be ensured for patients and staff, by selecting suitable sites for first-aid posts and hospitals. Health facilities and ambulances should be clearly marked with the protective emblem of the red cross, red crescent or red crystal, according to the dictates of international humanitarian law.

Not all combatants are disciplined and well trained. For anyone caught up in armed conflict, there is an all too familiar syndrome seen amongst young fighting men who are under the influence of a "toxic cocktail": testosterone, adrenaline, alcohol and cannabis (and, at times, "other substances" as well).

T. A. Voeten / ICRC

Figure 1.5
Working in a hostile environment.

The setting of surgical work can change rapidly, and surgeons must be prepared to adapt to various difficult and austere environments. With few doctors and limited staff available, and wounded people pouring in, hospital facilities are easily overwhelmed. Doctors and nurses also get tired and sick, and are sometimes frightened. The physical and mental strain of working in new and strange circumstances and at times dangerous conditions means that they may not perform as well as usual.

R. Bigler / ICRC

Figure 1.6

Mass casualties: the principles of triage.

1.2.6 Mass casualties involving the principles of triage

Much has been written about the carnage of the major wars of the twentieth century, and the role of triage in the management of thousands of casualties resulting from a single battle. These lessons are still relevant in contemporary conflicts. The logic followed must be to "do the best for the most" and not "everything for everyone". This involves the most important change in the professional mindset of the surgeon.

Triage decisions are amongst the most difficult in all medical practice, possibly creating ethical dilemmas. There may also be, at times, a conflict between medical criteria and tactical ones of military necessity that require some form of compromise. Persons performing triage must be prepared to accept these necessary compromises while maintaining their personal medical integrity (see Chapter 9).

1.2.7 Triage and surgery in successive echelons

The sick and wounded are evacuated and transferred along a chain of casualty care. The principles of triage are applied at every stage in this chain. The initial surgery must not compromise the performance of later, definitive surgery. The prognosis will be much better if the wounded are evacuated rapidly to a higher echelon hospital structure. A surgeon in the field must understand the system and know what will happen to the patient at the next echelon of care and what is required of him at his echelon (see Chapter 6).

War surgery requires a logic of phased wound management. Treatment takes place in five phases often, although not necessarily, in five different places. This is the classical set-up in military planning. It involves high costs, including the means of transportation and the discipline required of such organization. Modern concepts can be integrated into this approach, such as forward surgical teams performing damage-control surgery. The five phases are as follows.

1. First aid at the point of wounding: self- or "buddy" treatment, or that provided by a field medical officer or first aider.
2. First medical treatment: vital emergency measures including the beginning of resuscitation, generally at the first-aid or dressing post, clearing station or collection point.
3. First surgical treatment: debridement/wound excision, without primary closure, at the first echelon hospital.
4. Definitive treatment: delayed primary closure of wounds and surgical treatment according to traditional principles in a referral hospital. Physiotherapy and convalescence.
5. Reconstructive surgery and rehabilitation: specialized surgery with multiple reconstructive procedures and the fitting of prostheses when required.

The rapid turnover of medical personnel treating numerous patients at different points in a chain of casualty care creates a necessity for standard protocols, which cannot be left to the discretion or whim of the individual surgeon. One cannot individualize treatment for each single patient in a tactical situation; different surgeons will operate on the same patient at the different echelons. In civilian practice, by contrast, the same surgeon manages the surgical care of the individual patient throughout that patient's course of treatment; even in a multidisciplinary approach, the same team is involved.

These five echelons for the management of the war-wounded do not always exist in a civilian or humanitarian context, where all five phases may well occur in the same medical facility – as is in fact common practice for ICRC hospital teams. However, in the humanitarian context, there is also a rapid turnover of personnel. Standardized protocols are the only means to ensure continuity of treatment and to organize surgical and nursing care on a sound footing; the protocols cannot be changed with every change of team surgeon.

Old lessons for new surgeons

Save life and limb, sacrifice limb to save life, prevent infection, and render the casualty transportable to the next echelon.

Heroic surgery will never replace good surgery.

1.2.8 Outcome of hospital patient care depends on the efficiency of pre-hospital echelons

First aid provided at the point of wounding – or at the safest place near the battlefield – and rapid evacuation are of vital importance; mortality and morbidity increase with delay. If first aid is inadequate or unavailable and the evacuation chain is long, then the outcome will be decided by nature. However, hospital mortality decreases as evacuation time increases; with very long delays, the severely injured die long before reaching hospital and surgeons spend most of their time dealing with the septic complications of the survivors (see Chapters 5 and 7).

Old lessons for new surgeons

It is more important to provide proper first aid and render the injured fit for transport, than to give early but inadequate treatment, with insufficient means, and insufficient knowledge.



T. A. Voeten / ICRC

Figure 1.7

Inadequate pre-hospital care.

1.2.9 Specific wound pathology: bullets, bombs, blast, and non-conventional weapons

War wounds are qualitatively different from trauma seen in civilian practice: all are dirty and contaminated. Projectiles may cause massive destruction of soft tissues, bones, and important organs. Infection is the great danger and the rules of septic surgery apply (see Chapters 3 and 13).

Old lessons for new surgeons

War wounds are dirty and contaminated from the moment of injury. The rules of septic surgery apply.

Nothing in routine civilian practice is similar to the polytrauma of multiple shell fragments, traumatic amputation due to an anti-personnel landmine, or the devastating effects of a high-kinetic energy transfer from a military rifle bullet. Again, a change in the professional mindset appropriate to a modern trauma centre is required in order to adjust to the management of wounds in times of armed conflict. Surgeons practising in a low-income country, dealing with much septic pathology, will find this change much easier to handle than those whose usual work involves sophisticated technology with abundant good nursing care in an aseptic environment.

1.2.10 Specific techniques appropriate to the context and pathology

The care of numerous patients, treated in many locations by different surgeons, in austere conditions demands simplicity, security, and speed of surgical procedures. The need for speed in dealing with mass casualties with inadequate numbers of staff should not lead to confusion and disorder. Phased wound care imposes standards and a systematic approach: doing the least amount of surgical work for the greatest results, saving "life and limb", and then sending the patient on to the next stage in the chain of casualty care. The follow-up of surgical procedures by the individual surgeon in the field is difficult if not impossible, and precludes personal and individualistic techniques. Standard protocols, as mentioned, are necessary.

The majority of wounds will be to the extremities, and the objective is to treat them so that they heal as quickly as possible without becoming infected. Sepsis, potentially fatal (tetanus, gas gangrene, haemolytic septicaemia), is the greatest danger for survivors. As aforesaid: the rules of septic surgery apply.

The basic principles of management of war wounds comprise the following steps.

1. Early and thorough wound excision and irrigation.
2. No unnecessary dressing changes.
3. Delayed primary closure.
4. Antibiotics as an adjuvant.
5. Anti-tetanus vaccine and immunoglobulin if necessary.
6. No internal bone fixation.[4]
7. Early physiotherapy.

---

[4] No internal bone fixation is the rule, at least in the "acute phase". Recent experience has shown the possibility of using internal fixation once the soft tissues have healed in the absence of any infection, but only in skilled hands and with excellent conditions of hygiene and nursing care. This is not, however, standard policy in ICRC practice where no internal fixation whatsoever is used. The risk, and probability, of abuse of internal fixation precludes its availability.

Old lessons for new surgeons

The best antibiotic is good surgery.

Correct surgery gives the patient the best chance of survival with a good quality of life, and shortens the stay in hospital. High-quality physiotherapy is required to ensure early mobilization after surgery and a good functional result. Treatment is not complete, however, until the patient is rehabilitated; prosthetic workshops are needed to fit amputees and provide other suitable devices, such as orthoses, crutches or wheelchairs.

1.2.11 Increased prevalence of endemic disease

Until World War I, more soldiers died of disease than of their wounds. Battle-injury attrition was usually around 20 %, and disease four times more common among soldiers. Non-battle injury attrition rates remain very high even today; infectious and communicable diseases differ according to the geography and climate, but psychological disorders and vehicle accidents are universal.

The destruction, disruption and disorganization that accompany armed conflict often cause the public health system to be among the very first to suffer. The humanitarian consequences translate into reduced availability of basic public health requirements such as water, food, shelter, etc., for the civilian population and often overwhelm the capacities of the public health system. This compounds the challenge of caring for the civilian population in a conflict zone: i.e. residents, internally displaced persons, and refugees fleeing to or from neighbouring countries (see Chapter 5).

1.3 "Surgeries" for victims of war

There is more than one type of war surgery. While the needs of the wounded are the same, the means and resources available to meet those needs vary widely from country to country and situation to situation, giving rise to different approaches to war surgery. The management of the war-wounded as performed by the military medical services of an industrialized country is not the same as that of a public rural hospital in a low-income country. Although the principles of wound management are the same in both cases, the diagnostic and therapeutic possibilities are very different. The latter should be *appropriate* to the technological, financial, and human resources at hand. Obviously many of these same constraints apply to the practice of civilian, everyday trauma and elective surgery around the world.

At least four major scenarios for the surgical management of victims of war in contemporary armed conflicts can be described.

1. Conventional army of an industrialized society, with a high level of public financing and where the military attempt to provide the same level of surgical care that is practised in civilian life. Rapid evacuation and transfer of patients to specialized facilities is routine. Safe access to adequate medical care for the sick and wounded is perceived as a right; and the duty to provide it incumbent on the armed forces.

2. Developing country with an emergent economy where, at least in the capital and other major cities, a high-level of specialized surgical care including enough trained personnel is available, even if this is not the case in rural areas. Evacuation and transfer of patients to specialized facilities is possible, if sometimes difficult. Safe access to adequate medical care is a goal to be achieved.

3. Poor country, with limited financial and human resources. A few major surgical centres may exist in the capital city but provincial and rural hospitals are largely staffed by young general surgeons or general practitioners with some surgical experience. Supplies, budgets, and human resources are chronically inadequate or even absent. Evacuation and transfer of patients are difficult or impossible. Safe access to adequate medical care is rarely guaranteed.

4. Non-State actors, guerrilla groups, populations without safe access to public structures. Field surgery is practised by a few trained doctors and nurses, because there is no alternative. Safe access to the victims by health professionals, and the victims' access to medical care, is impossible or rare, problematic, and always a challenge.



H. Du Plessis / South African Military Health Service, U. Pretoria

Figure 1.8

Surgery for victims of armed conflict in a modern hospital.



F. McDougall / ICRC

Figure 1.9

Another type of surgery for victims of armed conflict.

Here’s what distinguishes the Taoist vision from most others: enlightenment is not understood as a process which happens “in the mind”, in separation from the body, but the process takes place in and through the body and its progressive transformation.

Thus a true process of spiritual growth in the Taoist vision implies the “enlightenment” of the body. The progression process of illumination is a bodily process, visible to the eye and tangible in the quality of energy which a person manifests and radiates in her/his body. This emphasis on transformation as a bodily process is a principal characteristic of the Taoist tradition. In that respect it differs from other ones, marked by the duality of body and mind and in which the body is viewed as a stumbling block; a hindrance.

This also explains the Taoist insistence on the central importance on rooting and grounding the body in the process of self-transformation. The more one advances in the higher practices, the greater the need to root and ground so that the energies in the body remain in balance. Equally important is centering; the balance between heaven and earth, the energies from above and below are maintained and enhanced.

It is precisely for this reason Taoist practice gives the highest priority to the creation of a healthy and strong body through a healthy and relaxed life style and an intelligent natural diet thanks to which the body can continuously regenerate and rejuvenate itself.

These insights had their basis in a new view on the nature of electromagnetic waves as particular forms of energy and in the insight that light is an electromagnetic field which takes on the form of waves which can travel through empty space as very light vibrations, also called ether. This energy is seen, in both the Chinese and Indian cosmologies, as the mother energy from which the other elements originate and of which the universe, the cosmos and nature are composed: fire and water, wood and metal and water.

In the Taoist system, these elements correspond to the five seasons, temperatures, senses, colors, sounds and positive and negative emotions. They form the theoretical and practical starting point for the Fusion Practices.

1.4 Differences between military and non-military war surgery: the ICRC approach

Non-military war surgery is practised by civilian medical structures (health ministry, missionary and private hospitals) and those of the ICRC or other humanitarian agencies. This section details the ICRC's experience and explains its approach.

The aims of war surgery for the ICRC are to protect the sick and wounded and help maintain their dignity by ensuring access to adequate care; save "life and limb"; minimize residual disability and assist amputees. Besides the direct victims, the ICRC also attempts to support the health system by assisting local medical colleagues to maintain the infrastructure and human resources necessary to resume functioning after the end of the conflict, thus providing the civilian population with at least the basics of healthcare. ICRC assistance to local structures may involve construction and renovation of health facilities, water and sanitation work, food supplements for patients and staff, equipment, supplies and basic salaries. Training programmes for doctors and nurses may be included. In addition, the ICRC may at times set up its own independent hospitals with expatriate staff supplemented by local personnel (see Chapter 6).

1.4.1 Military-civilian cooperation

Armed forces deployed in the field have a specific military mission. Their medical component aims primarily to give support to their soldiers in this mission, i.e. to achieve their tactical and strategic plans. The military may have many of the same "assistance and reconstruction" aims as civilian organizations, but medical criteria in a military context often must take second place to the tactical and strategic demands of military and political necessity.

The ICRC is a neutral, impartial and independent, totally humanitarian, institution. It promotes adherence to international humanitarian law and aims to protect and assist the victims of conflict – all the victims on all sides. Any cooperation with armies in the field of battle that compromises the perception of that neutrality, impartiality or independence can only compromise the humanitarian work of the ICRC, as well as that of other organizations and agencies.

The ICRC insists on maintaining its independence, and the independence of a "humanitarian space" separate from the "assistance and reconstruction" work of armies in the field. Many humanitarian organizations share the same opinion and approach.

1.4.2 Constraints: security

The ICRC often has little or no control over casualty evacuation because of security constraints. In many countries the wounded are transported by private means: taxis, donkeys, oxcarts or on foot. In some contexts, the ICRC has been able to set up first-aid posts, or assist a National Red Cross or Red Crescent Society in doing so. One extraordinary example was a 16-year medical evacuation system by fixed-wing aircraft run by the ICRC and United Nations' Operation Lifeline Sudan to assist victims of the conflict in southern Sudan: it transported over 30,000 sick and wounded patients to an ICRC hospital in northern Kenya. Even with aircraft available, the logistics and distances involved regularly resulted in a one- to three-week delay in evacuation.

While the armed forces deploy the necessary means to protect their health facilities from the "lethal chaos of the battlefield",[5] the ICRC depends on the red cross emblem and negotiations with all belligerent forces for its physical protection. The ICRC has no guns to protect itself and is just as dependent on local authorities and leaders as public hospitals are. The ICRC relies on the limits imposed by international humanitarian law and the discipline of combatants, and its diplomatic negotiating ability. Other humanitarian organizations who work in war zones face similar constraints.

---

[5] Butler F. Tactical Combat Casualty Care: combining good medicine with good tactics. *J Trauma* 2003; **54 (Suppl.)**: S 2 – 3.

1.4.3 Constraints: logistics

A hostile environment presents more than security risks. Remote areas with dangerous routes and extreme climates pose numerous logistic problems for the delivery of supplies and the maintenance of basic infrastructure, for both hospital and living quarters. The military often have lift, delivery and transport capacities that civilian institutions lack. Although the armed forces also have their logistic limits, they are of a different order of magnitude to those of the health ministry, non-governmental organizations, or the ICRC.



V. Mboah / ICRC

Figure 1.10

Challenging environment.

1.4.4 Constraints: hospital equipment

These limitations also affect hospital equipment. The military have lift constraints because they must also transport arms and munitions. For the ICRC, equipment limitations mean resorting to appropriate technology and mastering the tasks of maintenance, repair and availability of spare parts. This is particularly important when working in remote areas in a poor country with training programmes for local colleagues. The aim is to avoid creating a technological dependency that the permanent local staff will not be able to cope with when the conflict is over, and the ICRC leaves the hospital and the country. To this end, the ICRC has developed criteria for the introduction of any new technology into its standard list of medicines and equipment for hospital programmes (see Annexe 1. A: ICRC criteria for introducing a new technology).



K. Barrand / ICRC

Figure 1.11

Limited surgical equipment.

A standard list is a basic, limited set of essential supplies, both medical and non-medical, which corresponds to an appropriate standard of care. All items on a standard list should always be available from a central store or reliable supplier. Standardization provides a simple framework, within which resources can be used to maximum effect, promotes continuity in patient care, helps to simplify staff training, and makes it easier to introduce new and inexperienced staff into the system. The ICRC and the International Federation of Red Cross and Red Crescent Societies have established an Emergency Items Catalogue[6] with predetermined sets and kits that run the gamut of assistance programmes.

ICRC experience shows that it is possible to perform good quality surgery with basic technology such as simple X-ray, and electronic monitoring in the theatre and post-operative ward limited to a pulse oxymeter. An ICRC laboratory set-up is also basic; there is no capacity for bacteriological culture and sensitivity and no blood components.

NORWEGIAN MOBILE HOSPITAL
Box 4
NURSING UNIT
CASE NO 4
00/2

K. Barrand / ICRC

Figure 1.12

Basic supplies.

1.4.5 Constraints: blood transfusion

Blood for transfusion is often difficult to obtain in some countries because of cultural and religious restrictions and beliefs. With the steady increase in HIV infection around the world, testing must be adequate and indications for transfusion strictly limited. In some areas of the world, giving blood should probably be totally avoided. The use of blood should be restricted to vital needs and to patients with a good chance of survival, following the principles of triage. As in many, if not most, provincial and rural hospitals around the world, ICRC practice uses whole blood for transfusion, as fresh as possible, and usually donated by a relative.

1.4.6 Constraints: geography and climate

The geographic context may be important in terms of disease and the added burden it represents. The wounded may suffer from other illnesses, such as tuberculosis, malaria, typhoid and intestinal worms, as well as from malnutrition. In countries with chronic malaria infestation, there is often a peak of fever post-operatively. The surgeon must therefore try to acquire some basic knowledge of the diseases specific to the area and their treatment. Local healthcare workers are usually familiar with these conditions and more expert in their treatment than expatriate staff. These pathologies may also affect and represent a danger for expatriate staff.

1.4.7 Constraints: culture shock

Cultural constraints are another challenge that may add to the frustrations of medical work in a combat zone. In some societies, amputations and laparotomies can only be performed with the consent of the *family* of the patient. After a discussion in which the clear advantages are explained, the final decision must be left to the family. This procedure, which respects local cultural and social behaviour and norms, has to be followed and accepted even though it may be considered as a limitation and constraint by surgical and nursing staff. It is particularly difficult for committed medical personnel to see young people die because permission for necessary surgery has been denied.

In many societies, it is common for a relative to stay with a hospitalized patient, helping with nursing duties related to hygiene and feeding, and providing psychological support. This tradition must be accepted.

Adaptation to the cultural, social, and geographic context is essential.

---

[6] See Selected bibliography.

1.4.8 Constraints: the human factor

> "War surgery is a surgery of complications, performed by doctors who are often ill-trained or without surgical training. It is surgery replete with adaptations and improvisations to replace that which is missing, a surgery of surprises that new means and methods of combat reveal."[7]

This classic quotation from the Swiss army's war surgery manual describes the situation for the new military surgeon and, as is more and more often the case in contemporary conflicts, for civilian surgeons faced with the victims of armed conflict for the first time. New ICRC surgeons coming from the National Red Cross or Red Crescent Society of a rich industrialized country face the same challenges: a constantly changing field of battle with new limits and constraints that come as a surprise. One must plan for alternatives and always keep an open mind to new options.

If military war surgery is the management of an "epidemic of trauma" in a series of echelons, this is not always the prevailing situation in non-military circumstances. Unlike a military field hospital, an ICRC hospital is responsible for all levels of medical care. It often acts as a first-aid post, field hospital, base hospital, and referral centre all in one. The "multi-surgeon" military approach to treatment in echelons gives way to a more traditional one of attending to the entire surgical history of a patient. However, since deployment of ICRC surgeons is usually for a short period of time (three months on average), a number of surgeons may be involved in caring for a single patient. Continuity of care is essential.

The modern military may "project forward" technical skills by deploying field surgical teams close to the battlefield. The aim is to perform critical surgery, often damage control surgery, as soon as possible after injury in an attempt to save lives, thereby reducing the number killed in action. The ICRC has also deployed field surgical teams – Somalia in 1992, southern Sudan in 2000, and Darfur in 2005 – but with a different aim: the protection of non-combatants and wounded fighters who no longer participate in hostilities and who would otherwise have no access to surgical care. The performance of this medical act and the protection of access to surgical care are based on the essential principles of the ICRC as a neutral and impartial humanitarian actor.

The surgeon must be able to adapt to the conditions of field surgery where "somewhat clean with soap and water" replaces a "sterile" environment and "favourite" surgical instruments are not available on the standard list. Furthermore, living conditions may resemble camping out in the bush and everyone in the team (4 members: surgeon, anaesthetist, theatre nurse and post-operative nurse) participates in the preparation of food and accommodation.

The following qualities are particularly needed by personnel working in ICRC hospitals or field surgical teams:

- professionalism;
- sound judgement and common sense;
- adaptability.

Local skills and material improvisation in some countries may bring to the attention of the surgeon efficient, cheap, and useful ways of treatment: mashed papaya for burns or autoclaved banana leaves as a non-adherent dressing, for instance. Expatriate personnel must show themselves capable of learning "new old tricks" and adapting to the circumstances. War surgery is a challenge and the work trying. Medical staff must be prepared – physically and mentally – for frustrations, fatigue and long hours, and being a witness to the results of "man's inhumanity to man".

> War is deleterious to your health.

---

[7] War Surgery Commission of the Federal Military Department. *Chirurgie de guerre (Aide-mémoire 59.24 f) [War Surgery (a primer)]*. Bern: Swiss Army, 1970 and 1986.

ANNEX 1. A ICRC criteria for introducing a new technology

1. Needs assessment

What is the added value of this new technology? Are requested instruments "essential", "important" or "nice to have", or even "superfluous" and a luxury?

2. Maintenance requirements

What are the extra burdens for the daily maintenance of such equipment?

3. Ease of repair

Are specialized technicians necessary, and available?

4. Availability of spare parts

Is there a reliable local supplier?

5. Cost

Expense alone is not a criterion if the equipment is necessary. However, it is taken into account along with the other factors in a total cost/benefit analysis.

6. Competency required to use the technology in question

Is the expertise widely mastered and available or does it correspond to the particular practice of an individual doctor or nurse?

7. Continuity of the competency required

Can successive surgical teams use the equipment or does it depend on the expertise of a limited number of people?

8. Presence of the technology in the country

To all intents and purposes, the ICRC shall not be the first to introduce a new technology to a country; some local practice or competency must already exist.

9. Professionalism and ethical concerns

The supply of equipment and instruments must at all times meet demanding standards of professionalism in surgical care and address possible ethical concerns. (e.g. in Europe, following the outbreak of bovine spongio-encephalopathy – so-called "mad-cow disease" – catgut suture material has been banned by the European Union and Switzerland. It would not be ethical for the ICRC to continue to provide such sutures in its assistance programmes in other parts of the world, thereby creating a lower safety standard than in Europe.) Quality control of medicines and equipment is becoming a major worldwide problem as identified by the World Health Organization.

10. Sustainability

Only if the technologies can be sustained after ICRC withdrawal is it worth considering their utilization.

Chapter 2

APPLICABLE INTERNATIONAL HUMANITARIAN LAW

2. APPLICABLE INTERNATIONAL HUMANITARIAN LAW

2.1 Historical introduction 35

2.2 International humanitarian law: basic principles 36
2.2.1 Principles underlying IHL: the "law of war" 37
2.2.2 IHL and human rights law 38

2.3 The distinctive emblems 38

2.4 The International Red Cross and Red Crescent Movement and its Fundamental Principles 39

2.5 Rights and duties of medical personnel according to IHL 39

2.6 Responsibility of States 41

2.7 Reality check: some people do not follow the rules 43

2.8 The neutrality of a National Red Cross/Red Crescent Society 44

2.9 The role and mandate of the ICRC in situations of armed conflict 45
2.9.1 Health services: assistance to the war-wounded and sick 46

ANNEX 2. A The distinctive emblems 48

ANNEX 2. B The International Red Cross and Red Crescent Movement 50

2.1 Historical introduction

> "You may not be interested in war. War is interested in you."
>
> Leon Trotsky

One of the specificities of the war-wounded and those who care for them is their relationship to international humanitarian law, mainly the Geneva Conventions and their Additional Protocols.

In 19th century Europe, large-scale battles caused real carnage on the battlefields. Soldiers were regarded as cannon fodder and almost no medical services were available. Solferino, a town in northern Italy, was the site of one of these awful battles in 1859: in 16 hours 40,000 people were killed or wounded. Many wounded soldiers were left to die on the battlefield, although many of them could have been saved had relief been available. The medical services of the armies were too limited to respond to such a number of casualties – there were more veterinarians for the horses than doctors for the soldiers! Wounded soldiers lay agonizing for days without help.

Henry Dunant, a Swiss businessman travelling in the area, was struck by this drama. Out of compassion, he spontaneously organized help with the women from the neighbouring villages. Relief was given to all wounded soldiers without discrimination, regardless of their nationality. Others had performed humanitarian deeds on battlefields before; Dunant's genius lies in having taken things a lot further. Back in his hometown, Geneva, still traumatized, he wrote a book, *A Memory of Solferino*, published in 1862, in which he not only related the horrible battle and the suffering of the soldiers, but also launched an appeal around a vision and two key ideas.

The vision was to provide neutral medical care for wounded soldiers in the field, and the ideas to accomplish this vision were the following.

- On the one hand, to create a relief society in every country which, already in peacetime, would train volunteers who could assist the armed forces' medical services, doctors and nurses ready to care for wounded soldiers in the event of war – this later gave birth to National Red Cross and Red Crescent Societies.
- On the other hand, to negotiate an international agreement that would grant protection and assistance to the sick and wounded and the medical services which cared for them, thus guaranteeing access to the wounded. This idea became the first Geneva Convention, the basis for modern international humanitarian law (IHL). Every human society throughout history has had rules about the conduct of warfare: this was the first concerted attempt to standardize and institutionalize, on an international basis, the law of war. IHL is also referred to as the "law of war" or the "law of armed conflict".

Five citizens of Geneva, including Dunant, members of a charitable association, created the "International Committee for the Relief of Wounded Soldiers" in 1863 in response to Dunant's book. This Geneva Committee persuaded the Swiss government to convene a diplomatic conference in 1864, in order to formalize the protection of medical services on the battlefield through an internationally recognized treaty: twelve governments participated. The result was the Geneva Convention of 22 August, 1864, for the Amelioration of the Condition of the Wounded in Armies in the Field. The Geneva Committee became the International Committee of the Red Cross, and the emblem of the red cross was adopted as a symbol of protection of the medical services that cared for the sick and wounded – the symbols of the red crescent, the red sun and lion, and red crystal were introduced later. Not only was this first Geneva Convention a decisive step towards formalizing the laws of armed conflict, but it also made it the duty of signatory States to create military medical services to care for their own wounded. Soldiers were no longer to be simply regarded as cannon fodder.


Carlo Bossoli, Museo Nazionale del Risorgimento, Turin

Figure 2.1

The battle of Solferino, 1859.

2.2 International humanitarian law: basic principles

Throughout history, humanity has known war. All human societies have developed customary rules that regulate how wars are fought. Over 500 cartels, codes of conduct, covenants and other texts designed to regulate hostilities had been recorded before the advent of contemporary humanitarian law. The first laws of war were proclaimed by major civilizations several millennia before our era: "I establish these laws to prevent the strong from oppressing the weak" declared Hammurabi, King of Babylon.

Just as there is no society of any sort that does not have its own set of rules, so there has never been a war that did not have some vague or precise rules covering the outbreak and end of hostilities, as well as how they were to be conducted.

The Geneva Conventions (GCs) as they stand today are the result of a long process. Over the years, the First Geneva Convention has been extended to meet the changing needs of modern warfare. Three other Conventions were adopted, one after the other, covering victims other than wounded soldiers: shipwrecked sailors, prisoners of war, and civilian populations. The four Geneva Conventions of 1949 and their two Additional Protocols of 1977, in particular, as well as other written treaties and customary law, constitute international humanitarian law (IHL): i.e. what is and what is not permitted during international and non-international conflicts. All States in the world have now ratified the Geneva Conventions, which means that they are bound by these legal instruments.


ICRC

Figure 2.2

I. Amelioration of the condition of the wounded and sick in armed forces in the field.


ICRC

Figure 2.3

II. Amelioration of the condition of wounded, sick and shipwrecked members of armed forces at sea.


ICRC

Figure 2.4

III. Treatment of prisoners of war.


ICRC

Figure 2.5

IV. Protection of civilian persons in time of war.

The four Geneva Conventions are mainly designed to regulate the behaviour of combatants and to protect persons who are not (or are no longer) taking part in hostilities in armed conflicts between States (international conflicts).

I. Convention for the amelioration of the condition of the wounded and sick in armed forces in the field (GC I: Revision of the 1864 Convention).

II. Convention for the amelioration of the condition of wounded, sick and shipwrecked members of armed forces at sea (GC II: revision of the 1899 Convention).

III. Convention relative to the treatment of prisoners of war (GC III: revision of the 1929 Convention).

IV. Convention relative to the protection of civilian persons in time of war (GC IV: new Convention adopted in 1949).

Article 3 common to the four Geneva Conventions of 1949 also provides basic rules applicable in armed conflicts "not of an international character occurring in the territory of one of the High Contracting Parties".

In response to new needs in contemporary armed conflicts, the Conventions were developed and supplemented in 1977 by two further agreements: the Additional Protocols I and II relating to the protection, respectively, of victims of international and internal armed conflicts. A third Additional Protocol was adopted in 2005 to introduce a new protective emblem called the red crystal in addition to the red cross and red crescent emblems.

IHL regulates humanitarian issues in times of war; it aims to define the rights and obligations of the parties to a conflict in the conduct of warfare and to protect persons who are not (or are no longer) taking part in hostilities (civilians, wounded or sick soldiers, prisoners of war). These persons must be respected, protected and treated humanely by all parties. All the wounded and sick must also receive the medical care required by their condition. Those who provide such care must be respected and protected, as long as they are involved in their humanitarian tasks.

The various treaties defining IHL have become intricate, but the underlying message is simple. The human dignity of all individuals must be respected at all times without any kind of discrimination. Everything that *can* be done *should* be done to alleviate the suffering of those "*hors de combat*": persons who take no direct part in the conflict or who have been put out of action by sickness, injury, or captivity.

Return to Cosmology

The revolutionary implications for our perceptions of the universe, the cosmos, time and space and of nature and ourselves as part of nature are only slowly penetrating into the social consciousness. This social consciousness's view of its conditionings and fixations in cultural patterns and corresponding perceptions of reality prevent it from being open to an understanding our true nature.

There are multiple mechanics at work in present day culture and science and the modern view of reality which tend to prevent us from giving up the mind sets, rooted in the subconscious (and which rule the conscious mind, unaware of the forces by which it is steered). These make it appear as if the universe is composed of an infinite amount of loosely, accidentally assembled particles and solid objects; each having an independent, separate existence, rather than what is actually an ever changing web of unceasingly changing events which are mutually interconnected and interdependent.

The emergence in Western history and culture of the perception of human beings as essentially sovereign and independent from the universe and as its ruler who can alter life and the origins of life at will (with the progress of science and technology) are wholly questioned by the Taoist vision, presented above.

Such a view on the presumed independence and freedom from the laws of motion of the universe also has shaped the basic assumptions on the nature of human beings and social relations which have shaped mainstream social science and psychology, which mirror the basic premises of the Cartesian- Newtonian paradigm.

They support a view of progress and development, the new version of which emerged in the course of this century, which is essentially inspired by the view that reality can be manipulated and engineered without regard for the consequences on Nature. However, with the more recent findings of the adverse effects of such an attitude and the growing concern that the very foundations on which life on earth rest are being jeopardized, the basic premises on which this attitude is based are increasingly being questioned.

At the same time, as a natural consequence, there is a growing interest in the visions which have inspired the ancient cosmologies such as the Taoist one, especially since there is increasing evidence in advanced physics which support such visions. Thus it is

International humanitarian law: main legal sources

- Customary law
- Four Geneva Conventions of 1949 (194 States party to the Conventions)
- Two Additional Protocols of 1977
- Third Additional Protocol of 2005
- The Hague Conventions of 1899 and 1907
- United Nations Convention on Conventional Weapons of 1980
- Mine Ban Convention of 1997
- Cluster Munitions Convention of 2008

2.2.1 Principles underlying IHL: the "law of war"

- The human dignity of all individuals must be respected at all times.
- Persons no longer involved in the fighting (sick, wounded and shipwrecked combatants, and prisoners of war) and those who do not take a direct part in hostilities (civilians) are entitled to respect for their lives and physical and moral integrity. They shall in all circumstances be protected and treated humanely without any adverse distinction.
- The wounded and sick shall be collected and cared for.
- Captured combatants and civilians under the authority of an adverse party are entitled to respect for their lives, dignity, personal rights and convictions. It is forbidden to kill or injure an enemy who surrenders.
- Everyone shall be entitled to benefit from fundamental judicial guarantees. No one shall be held responsible for an act he has not committed. No one shall be subjected to physical or mental torture, corporal punishment or cruel and degrading treatment. Hostage taking is prohibited.
- The choice of methods and means of warfare is not unlimited, and must be proportional to the military goals sought. It is prohibited to use weapons and methods of warfare that cause unnecessary losses, superfluous injury or unnecessary suffering.
- Attacks shall distinguish between the civilian population and combatants and between civilian objects and military objectives. Accordingly, operations shall be directed only against military objectives.
- Medical personnel have rights and obligations in times of armed conflict.



British Museum

Figure 2.6

Soldiers blinded by chemical weapons during World War I: an example of means of warfare that cause superfluous injury and unnecessary suffering.

2.2.2 IHL and human rights law

IHL applies in situations of armed conflict, whereas human rights, or at least some of them, protect the individual at all times, in war and peace alike. Some human rights treaties permit governments to derogate from certain rights in situations of public emergency and if strict conditions are fulfilled. However, certain fundamental human rights must be respected in all circumstances and may never be waived, regardless of the emergency: in particular the right to life, the prohibition of torture and inhuman punishment or treatment, slavery and servitude, and the principle of legality and non-retroactivity of the law. No derogations are permitted under IHL because it was conceived for emergency situations, namely armed conflict.

IHL mainly aims to protect people who do not or are no longer taking part in hostilities. The rules embodied in IHL impose duties on all parties to a conflict, including non-governmental groups. Human rights, being tailored primarily for peacetime, apply to everyone. Their principal goal is to protect individuals from arbitrary behaviour by their own governments. Human rights law does not deal with the conduct of hostilities.

2.3 The distinctive emblems

The distinctive emblems of the red cross, red crescent, and red crystal are meant to mark certain medical and religious personnel and equipment which must be respected and protected during armed conflict (protective use). They also serve to show that persons or objects are linked to the International Red Cross and Red Crescent Movement including in situations other than armed conflict (indicative use). Their use is strictly defined (see Annex 2. A: The distinctive emblems).

Use of the emblems is restricted to the following entities.

1. Medical staff and services of the armed forces are the very first persons authorized to use the distinctive emblem, as a sign of protection.
2. Volunteers of a National Red Cross or Red Crescent Society, when duly authorized by the competent State Authority.
3. Staff of the International Committee of the Red Cross and the International Federation of Red Cross and Red Crescent Societies.

Persons and objects displaying the emblems must not be attacked, but on the contrary must be respected, protected, and encouraged in their work.



V. Louis / ICRC

Figure 2.7

Armed forces' medical services.



B. Fjortoft / ICRC

Figure 2.8

National Society volunteers.

B. Heger / ICRC

Figure 2.9

ICRC, International Federation and National Society staff.

2.4 The International Red Cross and Red Crescent Movement and its Fundamental Principles

The International Committee of the Red Cross and the International Federation of Red Cross and Red Crescent Societies, together with the National Red Cross and Red Crescent Societies, form the International Red Cross and Red Crescent Movement.

Fundamental Principles of the Red Cross and Red Crescent Movement[1]

Humanity

Impartiality

Neutrality

Independence

Voluntary service

Unity

Universality

In peacetime, as in time of conflict, it is the duty of the armed forces and the National Society of every country to disseminate the rights and duties enshrined in IHL. This is necessary not only for these rules to become known, understood, accepted and respected by combatants, but also so that the whole population understands and supports its Red Cross or Red Crescent Society for it to become more efficient, for the benefit of all, in times of conflict and in times of peace. Part of this dissemination includes the respect due to the red cross, red crescent and red crystal emblems as a sign of protection.

2.5 Rights and duties of medical personnel according to IHL

IHL provides medical personnel with rights in times of armed conflict, but also assigns duties to them. The duties incumbent on them are directly linked to the rights of the protected persons placed in their care. These provisions are a case-specific refinement of the basic rights and duties defined by medical ethics and the Hippocratic oath. Medical personnel are bound by medical ethics and IHL to treat patients solely on the basis of need and without regard for their nationality, race and class, religious or political beliefs. These rights and duties have been defined to enable medical personnel to perform the humanitarian task entrusted to them, born of the desire to alleviate human suffering by helping and tending the wounded and the sick, which is the very purpose of the medical mission.

The Geneva Conventions define medical personnel as:

- persons assigned by a party to the conflict, whether on a permanent or temporary basis, exclusively to medical purposes (search, collection, transportation, diagnosis and treatment of the wounded and sick, and for the prevention of disease) – this includes doctors, nurses, orderlies, first aiders, and stretcher-bearers;
- persons assigned by a party to the conflict, whether on a permanent or temporary basis, exclusively to the administration or operation of medical units or medical transport – this includes administrators, drivers, cooks, mechanics, etc.

The term "medical personnel" is thus not confined to the narrow meaning of the word. All personnel required to ensure the adequate treatment of the wounded and sick are covered by the protection granted to them, as long as they form an integral part of the medical service.

---

[1] See Annex 2. B: The Fundamental Principles of the International Red Cross and Red Crescent Movement.

Medical units, whether military or civilian, include what is set up for medical purposes:
- all buildings or installations (hospitals, clinics, first-aid posts, field hospitals, tents, etc.),
- blood transfusion and preventive medicine centres,
- medical and pharmaceutical depots and stores.

They may be fixed or mobile, permanent or temporary.

Medical equipment includes:
- stretchers,
- medical and surgical appliances and instruments,
- medical supplies, dressings, etc.

Medical transport can be organized by land, water, and air:
- ambulances, lorries or trucks,
- hospital ships, rescue craft,
- medical aircraft, etc.

Medical personnel must not be the object of attack, and must be allowed to care for the sick and wounded unhindered. They should wear the distinctive emblem of the red cross, red crescent or red crystal on a white ground and carry an identity card. Military medics may bear arms only for their own defence and to defend the wounded and sick from pillage. However, they must not use arms to prevent capture of their patients, units or themselves by the enemy; by doing so they lose their protected status.

If medical personnel fall under the control of enemy troops, they shall be allowed to continue their duties towards the wounded and sick. They shall not be compelled to perform acts contrary to medical ethics, or refrain from performing acts required by medical ethics. A patient remains a patient, and medical personnel have a responsibility to provide care according to their training and the means available. If captured medical personnel are not indispensable to the care of other prisoners, they should be repatriated. Those retained shall not be considered prisoners of war and their work shall be facilitated.

In occupied territory, civilian medical personnel should be allowed to continue providing adequate medical services for the civilian population.

The civilian population shall respect the wounded and sick, even if they belong to the enemy, and shall commit no act of violence against them. Civilians are permitted to collect and care for the wounded and sick of whatever nationality, and shall not be penalized for doing so. On the contrary, they must be aided in this work.

Medical units enjoy protected status so long as they are not used to commit acts harmful to the enemy, such as sheltering able-bodied combatants, storing arms or ammunition, or being used as military observation posts. Otherwise, their protection ceases and they become legitimate military targets. This is why strict controls must be established to safeguard the protected status of medical units and transport.

To enhance the protection of medical units and medical transport, they should be clearly marked with the red cross, red crescent or red crystal emblem, of the largest size possible. The emblem is the visible sign of protection conferred by the Geneva Conventions and their Additional Protocols.

2.6 Responsibility of States

As with any international agreement, the governments of States have a distinct responsibility whenever they become party to a treaty.

- The Geneva Conventions and their Additional Protocols are both contracts with other States and commitments towards humanity by which governments have agreed to certain rules that regulate the conduct of armed hostilities and the protection of persons who are not (or are no longer) taking part in hostilities, what is known as "law in war", or *jus in bello*. Its provisions apply to the warring parties regardless of the reasons for the conflict and whether or not the cause upheld by either party is just.
- On becoming party to the four Geneva Conventions of 1949, States agree to respect and ensure respect for their obligations in all circumstances (common Art. 1).
- Reciprocity is not supposed to be a prerequisite to a country adhering to and applying these rules, but it exists in reality and practice. It is in everyone's interest that everyone apply the law of his or her own accord.
- States are responsible for protecting those who do not participate or are no longer participating in hostilities.
- During peacetime, States are to promote IHL and train the members of their armed forces to respect IHL.
- At all times, States must take all measures necessary for the prevention and repression of any misuse or abuse of the distinctive emblems.
- On becoming party to the Geneva Conventions, States undertake to enact any legislation necessary to punish persons guilty of grave breaches of them, and are also bound to prosecute in their own courts any person suspected of having done so, or to hand over that person to another State for judgment. In other words, perpetrators of grave breaches, i.e. war criminals, must be prosecuted at all times and in all places, and States are responsible for ensuring that this is done.
- A number of independent mechanisms have been set up, each within its mandate and competency, to promote better compliance with IHL, including the ICRC, the International Fact-finding Commission, regional and United Nations bodies, and the International Criminal Court (Rome Statute of 1998). Their adequacy and sufficiency in meeting the task remains a challenge to humanity.
- Generally speaking, a State's criminal laws apply only to crimes committed on its territory or by its own nationals. International humanitarian law goes further in



ICRC

Figure 2.10

All too often the red cross emblem is used to indicate any health service without regard to its privileged legal status, which confers protection.

that it requires States to seek out and punish any person who has committed a grave breach, irrespective of his nationality or the place where the offence was committed. This principle of universal jurisdiction is essential to guarantee that grave breaches are effectively repressed. Such prosecutions may be brought either by the national courts of the various States or by an international authority. In this connection, the International Criminal Tribunals for the former Yugoslavia and Rwanda were set up by the United Nations Security Council in 1993 and 1994, respectively, to try those accused of war crimes committed during the conflicts in those countries.

- Lastly, the international community has created a permanent International Criminal Court (Rome Statute of 1998), which is competent to try war crimes, crimes against humanity, and genocide.
- The United Nations Security Council is the main UN body responsible for the maintenance of international peace and security. To this end, it may decide on measures, including coercive ones, against any State threatening or breaching international peace (Chapters VI and VII of the United Nations Charter). The rules that outlaw war, with some exceptions, are know as "the law on the use of force" or the *jus ad bellum*. This is different from the *jus in bello*, or IHL, which is the law applicable in times of armed conflict.
- "New" or "anarchic" conflicts lead to the partial, and sometimes total, weakening or breakdown of State structures. In such situations, armed groups take advantage of the political vacuum in an attempt to grab power. It is not because a State's structures have been weakened or are non-existent that there is a legal vacuum with regard to international law. The law, and its obligations, remain.

Admittedly, humanitarian rules are harder to apply in these types of conflict. The lack of discipline among belligerents, the arming of the civilian population as weapons flood the territory, and the increasingly blurred distinction between fighters and civilians often cause confrontations to take an extremely brutal turn – in which there is little room for respect for IHL.

As a result, this is the type of situation in which particular efforts are needed to make people aware of humanitarian law. Better knowledge of the rules of law will not solve the underlying problem which led to the conflict, but it is likely to attenuate its deadlier consequences.

Insofar as a "right – or even a duty – to intervene" is tantamount to justifying armed intervention undertaken for humanitarian reasons, this is a matter not for humanitarian law but for the rules on the legality of the use of armed force in international relations, i.e. of *jus ad bellum*, according to the Charter of the United Nations.



R. Sidler / ICRC

Figure 2.11

This ICRC car was targeted by "uncontrolled elements".

2.7 Reality check: some people do not follow the rules

Given what the law dictates, what is the reality on the battlefield? Whether in conflict situations or in peacetime, and whether national or international law is applicable, laws are violated and crimes committed. There are many examples of violations of IHL: surrounding a military objective with medical units so that it will not be targeted; hiding weapons in a hospital; transporting able-bodied combatants in an ambulance; using an aircraft displaying the emblem for reconnaissance missions; not respecting the non-combatant status of sick and wounded soldiers – on the contrary, all too often their survival is seen as an invitation by some to "finish the job", and atrocities are the result. All too often hospitals and medical personnel are the target of attack, or are prevented from doing their duty of caring for the sick and wounded, which is perceived by some as giving "succour and aid to the enemy". All these violations have three things in common: they seriously weaken the system of protection embodied in IHL, they divert people and objects displaying the red cross, red crescent or red crystal from their humanitarian purpose, and they put lives in danger by fostering mistrust.



T. Pizer / ICRC

Figure 2.12

Unfortunately, hospitals are not immune to attack: this photo shows a blatant contravention of IHL.

Red Cross and Red Crescent personnel are not immune to this lack of respect for IHL. Mussolini's air force bombed a Swedish Red Cross ambulance during the invasion of Abyssinia on 30 December 1935, and 28 people were killed and 50 wounded. More recently, masked gunmen entered the residence of the ICRC hospital in the village of Novye Atagi, Chechnya (southern Russia), in December 1996 and assassinated five nurses and the construction engineer in cold blood. The authors of this text have all too often been threatened, prevented from reaching and treating the victims, or seen their hospital attacked or bombed. The world over, colleagues, both civilian and military, are time and again made to suffer "simply" because they want to fulfil their humanitarian, ethical, and legal duty to care for their patients.

Humanitarian action is based on a fundamentally "optimistic philosophy", wrote Jean Pictet.[2] But this optimism in no way detracts from the "philosophy's" realism. It is aware that humanitarian work is difficult. Its greatest enemies may well be neither weapons nor disaster, but selfishness, indifference and discouragement. One should not despair, however. Rather one should see this as an incentive to redouble efforts to educate those involved in armed conflict. Medical ethics go hand in hand with IHL and the Fundamental Principle of impartiality: the sick and wounded are entitled to treatment, whatever their origin or political persuasion.

---

[2] Jean Pictet (1914 – 2002) was Director-General and Honorary Vice-President of the ICRC. He was responsible for the preparatory works that led to the 1949 revision of the Geneva Conventions and the Additional Protocols of 1977, and his writings formed the basis of the Fundamental Charter of the International Red Cross and Red Crescent Movement, adopted in 1965.

All medical personnel should not only comply with medical ethics and IHL but should also disseminate their meaning to military and civilian authorities, ordinary soldiers and citizens.

Medical practitioners have a particularly important part to play: they have responsibilities with regard to individual patients but also towards society at large. They must convince combatants of the need to respect IHL, to refrain from attacking the medical facilities and personnel of the enemy and allow them to perform their humanitarian task. While the underlying philosophy of the Movement is *not* rooted in the principle of reciprocity, in practice medical professionals can only expect to benefit from the "protection" offered by the Geneva Conventions – in a general atmosphere of respect for the Fundamental Principles – if their colleagues practising on the "other" side also benefit from the same protection. They must inform those who bear weapons of their obligations and trust that colleagues in contact with the opposing side are doing the same. This has proved true in the past, and soldiers have often respected the principle of protection afforded to the sick and wounded and medical and religious personnel.

2.8 The neutrality of a National Red Cross/ Red Crescent Society

Another major problem faced during armed conflicts of a non-international character, that is to say internal conflicts, is the question of neutrality, especially of a National Red Cross or Red Crescent Society. The requirement of non-discrimination is of particular concern to Red Cross/Red Crescent Societies, it is in fact a condition for their recognition. They must be open to all those who wish to become members and must permit all social, political and religious groups to be represented; this representativity is the guarantee of the Societies' ability to engage in exclusively humanitarian activities and to resist all partisan considerations.

It is admittedly not always an easy task to apply the principle of neutrality, not least because everyone has personal convictions. When tension mounts and passions are aroused, every member of the Red Cross or Red Crescent must exercise great self-control and refrain from expressing his/her opinions in the discharge of his duties. Volunteers are not asked to be neutral – everyone is entitled to an opinion – but to act neutrally. That is an important distinction. The next difficulty is the fact that the parties to the conflict often take a dim view of neutral behaviour. In countries where an internal conflict is taking place, the armed forces fail to understand why the National Society does not condemn the activities of those they regard as "bandits", much less why it wants to provide assistance to any of their number no longer able to fight. As for the opposition, they are critical of the Society's connections with the authorities.

Anyone trying to work on both sides to help non-combatants is considered at best naïve, at worst a traitor. The extremely polarized nature of many struggles is such that *not taking a stand* is a hostile act in itself. This is why the Red Cross and Red Crescent's neutrality and impartiality must be explained. As one National Society first aider put it: "The best argument I have is to tell one of the parties to the conflict that if I take its side and ignore the victims on the other side, I will never again be able to bring help to its own wounded members".

It would appear, indeed, that the principles of neutrality and impartiality are ideals to be attained, inner qualities that are rarely inborn but that most often require one to overcome one's instincts. They demand from members of the Red Cross and Red Crescent Societies arduous and sustained efforts to overcome their own prejudices and preferences in order to be able to perform the purest act of impartiality, which is to give more help to the adversary who is the victim of great misfortune than to the friend whose suffering is less severe, or to care for the more severely wounded, even if guilty, before assisting the innocent whose injuries are slighter.

2.9 The role and mandate of the ICRC in situations of armed conflict

Established in 1863, the International Committee of the Red Cross (ICRC) is an impartial, neutral, and independent organization whose exclusively humanitarian mission is to protect the lives and dignity of the victims of war and internal violence and to provide them with assistance. The ICRC endeavours to prevent suffering by promoting and strengthening international humanitarian law and universal humanitarian principles.

The ICRC in a nutshell

Neutral, impartial and independent humanitarian organization.

Works in situations of armed conflict.

Entrusted with an international mandate under the Geneva Conventions.

Protects and assists victims of conflict.

Part of the International Red Cross and Red Crescent Movement.

The ICRC has been named the "guardian and promoter" of IHL by the States party to the Geneva Conventions. It works during armed conflict to protect and assist the victims: the wounded and sick, prisoners of war and other detainees, and the civilian population.

The ICRC does not take sides or determine right or wrong in a conflict. The neutrality of the ICRC, however, is not a widely appreciated principle. There are many who express indignation at its neutrality in the mistaken belief that neutrality betokens lack of commitment and courage. The ICRC, for its part, has great difficulty in getting the parties to a conflict to understand that the only thing it must grant equally to each is its willingness to serve, and that in other respects its activities are proportional to the needs, and consequently unequal when distress is greater on one side than on the other.

At the beginning of hostilities, the ICRC:
- reminds the belligerents of their obligations according to IHL;
- offers its services as a neutral intermediary for the accomplishment of humanitarian activities;
- makes an assessment of the needs;
- acts in favour of victims according to the needs.

The protection role the ICRC plays consists in acting in defence of people who are not, or no longer, taking part in combat: the wounded or sick, detainees or prisoners of war, and civilians, including the inhabitants of territories administered or occupied by a hostile power. The ICRC approaches the competent authorities to ensure that these victims receive humane treatment. The ICRC has the right to have access to prisoners of war (Third Geneva Convention), and detained persons covered by the Fourth Geneva Convention, including the right to visit detention camps.

The ICRC has an official policy of discretion. Only when it observes grave and repeated breaches of IHL and when its confidential representations have been in vain and it considers that the only means of helping the victims is to ask for the support of the international community, does it make public representations. This sometimes takes the form of an appeal to the States party to the Geneva Conventions, whose responsibility it is to respect and *ensure* respect for IHL. Such initiatives are nevertheless the exception rather than the rule.

ICRC activities

1. Protection during armed conflict:
   - protection of civilians confronted with the violence of armed conflict;
   - protection and care of the wounded, sick, and shipwrecked;
   - protection of prisoners of war and other detainees (registration and visits);
   - as a neutral intermediary, facilitation and accompaniment of the release of prisoners of war;
   - re-establishment of family links through Red Cross messages;
   - re-establishment of family links through the tracing agency for the missing and dead.
2. Assistance to victims of armed conflict – public health approach (shelter, water, sanitation, food, preventive and curative medical care):
   - economic security;
   - water and habitat;
   - health services (including assistance to the war-wounded and sick).
3. Preventive action:
   - promotion of international humanitarian law (IHL);
   - advice and assistance with national measures to implement IHL;
   - mine risk education programmes to raise awareness among people exposed to the dangers posed by mines and unexploded ordnance.

ICRC delegates must be willing to talk to all those who are responsible for violations of IHL and human rights. They cannot pass judgment on them publicly, but must speak to them on behalf of those to whom speech is denied, and who have no one else to turn to. They often do so at considerable risk to their own personal safety and their words may fall on deaf ears, but if this policy of refraining from public denunciation makes it possible to alleviate the suffering of just one man, woman or child, that is ample recompense.

As a neutral and independent institution, the ICRC is authorized by the Geneva Conventions and their Additional Protocols to administer first aid and other care in the field to victims of armed conflict. Military authorities are required to permit the ICRC to collect and care for the wounded or sick of whatever nationality, even in invaded or occupied territories. The ICRC can offer its services to the parties, in particular in the medical realm to establish neutral or hospital zones, set up hospitals for the sick and wounded, assist existing hospitals, and provide rehabilitation for amputees, especially victims of anti-personnel landmines.

The ICRC helps to organize, or provide directly, relief to victims of armed conflict. These relief supplies cover the most essential needs, such as food, clean drinking water, shelter, clothing, and medical care.



Figure 2.13

The assistance pyramid: public health analysis of population needs.

2.9.1 Health services: assistance to the war-wounded and sick

Although proper medical care of sick and wounded soldiers and civilians in times of armed conflict is taken for granted by many governments today, poverty may compromise a government's efforts to provide such care. The ICRC maintains a capacity to aid States whose authorities show a willingness to assume their responsibilities towards their own soldiers and the civilian population.

The ICRC has deployed many assistance and training programmes to this effect. One example of an offer of services by the ICRC to two countries involved in a conflict was the case of the 1998 – 2000 war between Ethiopia and Eritrea. The ICRC provided assistance to help both governments to develop the programmes described below.

not surprising that one of the leading philosophers of science, Stephen Toulmin, recently published a book, *A Return to Cosmology.*

In his study he traces the process of alienation in Western culture and science, as it came to shape modern life. Especially, he focuses on the relation between body and mind. He foresees a return to ways of looking at reality which help to overcome the duality at the root of this alienation and the imbalances it has brought about in the present day world system and which it feeds through the new communication technologies.

It cannot be emphasized enough that when the Universal Tao system is called a whole of interrelated practices, this is based on the root assumption that it is only in the practice that experience is gained. Therefore, a process of self-transformation is set in motion which makes it possible to come to terms with the patterns within oneself which prohibit one to discover its relevance.

This is the very basis of Eastern epistemologies, not only basic to Taoism but also at the root of other Eastern religious and spiritual traditional epistemologies: that true knowledge can only be acquired experientially and existentially in and through the practice.

Also implicit in the Taoist vision, shared in other ancient cosmologies, is the view is that the universe is alive. Not only as it births life at every instant, but also as it sustains and nurtures life. This view is quite contrary to that underlying the materialist world view, which originated in the West with the advent of modern science, in which the universe is reduced to an accidental anomalous phenomenon .

Religious Nature of Taoist Practice

In the Taoist view, supported by the new physics, the body is not only matter but also a field of consciousness which, by its wavelike nature, is intrinsically related to the whole universe and can also get in touch with it. This provides the very basis for the Cosmic Chi Kung practice as a practice, which helps to enhance and balance the body and which is essential to the Fusion Practices.

These above views are essential to the assumptions on energy underlying the ancient Taoist Practices, contained in the practices of the Universal Tao and which offer a synthesis and which for the

ICRC EXPERIENCE

The ICRC carried out the following programmes in Eritrea and Ethiopia from 1998 to 2001.

Ethiopia

- Training in advanced first aid, triage and evacuation for the war-wounded.
- War surgery seminars.
- Specialist surgical training for the war-wounded: thoracovascular, orthopaedic and neurosurgery.
- Maxillo-facial reconstructive surgery training programme.
- Short-term ICRC surgical team presence in an emergency situation.
- Support to the Ethiopian Red Cross Society ambulance service.
- Surgical material and equipment.
- Visits to thousands of POWs and their repatriation after cessation of hostilities.
- Repatriation of thousands of interned enemy aliens.

Eritrea

- Training in advanced trauma nursing care for ambulance staff.
- Emergency Room Trauma Course for the war-wounded.
- War surgery seminar.
- Short-term ICRC surgical team presence in an emergency situation.
- Intensive care nursing training for the war-wounded.
- Development of a physiotherapy training curriculum at the Institute of Nursing Care.
- Support to the Red Cross Society of Eritrea ambulance service.
- Surgical material and equipment.
- Visits to thousands of POWs and their repatriation after cessation of hostilities.
- Repatriation of thousands of interned enemy aliens.
- Assistance to thousands of internally displaced persons (food, shelter, water, sanitation, medical care).

While the ICRC is authorized to care for the wounded and sick during armed conflict, it is also involved in post-conflict reconstruction, indeed in development assistance, and, sometimes, the ICRC achieves the right balance.

ICRC EXPERIENCE

"We want to thank the doctors and nurses of the ICRC. Thank you for coming. And, thank you for leaving."

Rui Paolo [3]

---

[3] Rui Paolo, Director of Hospital Services, Ministry of Public Health, Dili, Timor Leste, June 2001, on the occasion of the handover of the administration of the Dili General Hospital from the ICRC to the Ministry of Public Health.

ANNEX 2. A The distinctive emblems

The distinctive emblems of the red cross, red crescent and red crystal on a white ground are the symbols of impartial humanitarian work and do not represent any particular religious belief. They provide protection for military medical services and relief workers in armed conflicts. Moreover, they are also used for identification purposes by National Societies of the Red Cross and Red Crescent Movement in each country.

In the event of armed conflict, the distinctive emblems are a visible sign of the protection conferred by international humanitarian law upon medical personnel and equipment. The persons and objects displaying them must not be attacked, but on the contrary must be respected and protected.

Their use as a *protective sign* during armed conflict is authorized exclusively for:

- medical units, transport and personnel, as well as religious personnel, of the armed forces;
- civilian medical units**,** transport, and personnel, as well as civilian religious personnel, that have received special permission by the competent authorities to use the emblem;
- medical units, transport and personnel that a Red Cross or Red Crescent National Society has put at the disposal of the medical services of the armed forces.

Persons and buildings/structures/objects displaying the emblem must not be attacked, damaged or prevented from operating, but, on the contrary, must be respected and protected, even if, for the moment, they are not caring for or housing either wounded or sick people. The perfidious use of the emblems is explicitly prohibited.

In order to ensure effective protection during wartime, the *indicative* use of the emblem must be *strictly controlled* and only used for:

- Red Cross or Red Crescent National Societies, in order to indicate that persons or goods have a connection with the Society in question (it must be small in size to avoid any confusion with the emblem used as a protective symbol);
- exceptionally, ambulances and first-aid stations exclusively assigned to the purpose of giving free treatment to the wounded and sick, with the authorization of a National Society.

The International Committee of the Red Cross and the International Federation of Red Cross and Red Crescent Societies are authorized to use the emblem for all their activities and at all times.

Misuse of the emblem is a serious problem. In peacetime, hospitals, clinics, doctors' offices, pharmacies, non-governmental organizations and commercial companies tend to use the emblem in order to benefit from its reputation, although they are not entitled to do so. This abuse clearly weakens the protective value of the emblem in wartime.

Any case of misuse of the emblem should be reported to the relevant Red Cross or Red Crescent National Society, the ICRC, or the International Federation of Red Cross and Red Crescent Societies.

Parties to the Geneva Conventions shall take the precautions necessary for the prevention or repression of any abuse of the distinctive emblems.

During peacetime staff and volunteers of the International Red Cross and Red Crescent Movement, through their behaviour, activities and awareness-raising efforts, seek to ensure that the protective value of the distinctive emblems is well known to the military and the general public.

Please note:

On 8 December 2005, a Diplomatic Conference adopted Protocol III additional to the Geneva Conventions, which recognizes an additional distinctive emblem. The "Third Protocol emblem", also known as the red crystal, is composed of a red frame in the shape of a square on edge on a white background. According to Protocol III, all distinctive emblems enjoy equal status.[4] The conditions for use of and respect for the Third Protocol emblem are identical to those for the distinctive emblems established by the Geneva Conventions and, where applicable, the 1977 Additional Protocols.

J. Perez / International Federation

---

[4] While no longer in use, the red lion and sun on a white background is still recognized by the Geneva Conventions.

Annex 2. B The International Red Cross and Red Crescent Movement

The International Committee of the Red Cross and the International Federation of Red Cross and Red Crescent Societies, together with the National Red Cross and Red Crescent Societies, form the International Red Cross and Red Crescent Movement.

Born of the compassion felt by a Swiss citizen, Henry Dunant, at the sight of the dead and wounded abandoned on the battlefield of Solferino, the International Red Cross and Red Crescent Movement believes that its first duty is to render wars that cannot be avoided less inhuman, and to alleviate the suffering that they cause. Its aim has been to bring a little bit of humanity into the horrors of war. The Movement was founded as a result of a conflict and for conflicts, with the aim of helping people in distress on the battlefield.

The International Red Cross and Red Crescent Movement endeavours, in its international and national capacity, to prevent and alleviate human suffering wherever it may be found. Its purpose is to protect life and health and to ensure respect for human beings. It promotes mutual understanding, friendship, cooperation and lasting peace amongst all peoples.

The humanitarian ideas of the Movement are reflected in the seven Fundamental Principles that guide the activities of all its components at all times: humanity, impartiality, neutrality, independence, voluntary service, unity and universality.

Components of the International Red Cross and Red Crescent Movement

The International Committee of the Red Cross (ICRC)

The International Committee of the Red Cross, created in Geneva, Switzerland in 1863, is the founding body of the Red Cross/Red Crescent Movement. It is an independent humanitarian organization. As a neutral intermediary and on the basis of the Geneva Conventions or the customary law of nations, which grant it the right of initiative, it endeavours to protect and assist the military and civilian victims of international and non-international armed conflict and internal disturbances and tension.

The countries of the world have entrusted to the ICRC the roles of promoter and custodian of international humanitarian law, and the task of working for their development and worldwide dissemination.

The functions of the ICRC are defined in its own statutes, in those of the Red Cross/Red Crescent Movement, and also in the international treaties known as the Geneva Conventions of 1949 and their Additional Protocols of 1977.

The International Federation of Red Cross and Red Crescent Societies

The International Federation is the permanent liaison body between National Red Cross and Red Crescent Societies. It attempts to prevent and alleviate human suffering through the promotion of activities by National Societies and so contribute to peace. The International Federation encourages the creation and assists the development of National Societies in providing services to the community.

The International Federation organizes and coordinates international relief efforts for victims of natural disasters and promotes the adoption of national disaster-preparedness plans. First aid is an important part of both everyday community service and disaster preparedness.

The National Red Cross/Red Crescent Society

There are 186 National Red Cross/Red Crescent Societies around the world, with more currently being created. From the outset, the goal of the Red Cross/Red Crescent Movement has been to create relief societies which, in their capacity of *auxiliaries to their countries' armed forces' medical services*, would be called upon to tend wounded or sick soldiers. The establishment of such Societies was consistent with the aims of the original Geneva Convention of 1864.

The National Societies' activities have developed steadily and diversified over the years. The Societies' concern, at first directed only at members of the armed forces, now extends to protection and assistance of all those, whether military or civilian, who are the victims of conflicts, in close cooperation with the ICRC, and of natural catastrophes, in close cooperation with the International Federation of Red Cross and Red Crescent Societies. National Societies have also developed many activities in peacetime as *auxiliaries to the public authorities* to alleviate suffering, improve health, and prevent disease.

National Society membership is open to everyone and services are provided on the sole criterion of need. National Societies must fulfil stringent conditions to achieve recognition by the ICRC and obtain International Federation membership. Among these conditions: respect for the Fundamental Principles, and recognition by their home government as a voluntary aid society, auxiliary to the public authorities.

Each National Red Cross/Red Crescent Society has its own particular characteristics, and its activities cover a wide range depending on the needs of the country and on the Society's operational capabilities. The one activity that all National Societies share is the provision and teaching of first aid.

The Fundamental Principles of the International Red Cross and Red Crescent Movement

Humanity

The International Red Cross and Red Crescent Movement, born of a desire to bring assistance without discrimination to the wounded on the battlefield, endeavours – in its international and national capacity – to prevent and alleviate human suffering wherever it may be found. Its purpose is to protect life and health and to ensure respect for the human being. It promotes mutual understanding, friendship, cooperation and lasting peace amongst all peoples.

Impartiality

It makes no discrimination as to nationality, race, religious beliefs, class or political opinions. It endeavours to relieve the suffering of individuals, being guided solely by their needs, and to give priority to the most urgent cases of distress.

Neutrality

In order to continue to enjoy the confidence of all, the Movement may not take sides in hostilities or engage at any time in controversies of a political, racial, religious or ideological nature.

Independence

The Movement is independent. The National Societies, while auxiliaries in the humanitarian services of their governments and subject to the laws of their respective countries, must always maintain their autonomy so that they may be able at all times to act in accordance with the principles of the Movement.

Voluntary service

It is a voluntary relief movement, not prompted in any manner by the desire for gain.

Unity

There can be only one Red Cross or one Red Crescent Society in any one country. It must be open to all. It must carry out its humanitarian work throughout its territory.

Universality

The International Red Cross and Red Crescent Movement, in which all Societies have equal status and share equal responsibilities and duties in helping each other, is worldwide.

Humanity and Impartiality express the objectives of the Movement.

Neutrality and Independence ensure access to those in need of help.

Voluntary service, Unity and Universality enable the International Red Cross and Red Crescent Movement to work effectively all over the world.

Chapter 3

MECHANISMS OF INJURY DURING ARMED CONFLICT[1]

---

[1] Acknowledgement: the ballistics portion of this chapter is largely based on the work of Doctor of Forensic Science Beat Kneubuehl, Institute of Forensic Medicine, University of Bern, in collaboration with Armasuisse, Centre for Military and Civilian Systems, Science and Technology, Ballistics Laboratory, Thun, Switzerland. His cooperation and collaboration with ICRC surgeons over the years have permitted a whole generation of war surgeons to gain an important insight into the wounding potential of weapons. We hope that this knowledge has permitted better surgical management of the victims of armed conflict and other situations of violence where the weapons of war are used.

3. MECHANISMS OF INJURY DURING ARMED CONFLICT

3.1 The various mechanisms of injury 55
3.1.1 Blunt injury in war 55
3.1.2 Penetrating wounds caused by weapons of war 55
3.1.3 Anti-personnel landmine wounds 57
3.1.4 Explosive blast injuries 58
3.1.5 Burns 59
3.1.6 Non-conventional weapons 59

3.2 Ballistics 59
3.2.1 Introduction 59
3.2.2 Internal ballistics 60
3.2.3 External ballistics 62
3.2.4 Summary 62

3.3 Terminal ballistics 63
3.3.1 Role of kinetic energy 63
3.3.2 Laboratory experiments 63
3.3.3 Non-deforming rifle bullet: full metal jacket (FMJ) military bullet 64
3.3.4 Deforming and fragmenting rifle bullets: dum-dum 66
3.3.5 Handgun bullets 68
3.3.6 Fragment projectiles 69

3.4 Wound ballistics 70
3.4.1 Laboratory studies *versus* human body 70
3.4.2 Projectile–tissue interaction 70
3.4.3 Tissue factors 71
3.4.4 Pathological description of the permanent wound cavity 72
3.4.5 Clinical applications 73
3.4.6 Sonic shock wave in tissues 76
3.4.7 Pressure wave in tissues and blood vessels 76
3.4.8 Fragment wounds 77

3.5 Wound dynamics and the patient 78

3.1 The various mechanisms of injury

The surgeon caring for the war-wounded will face a wide variety of injuries. During armed conflict, all the usual trauma of peacetime continues unabated and natural catastrophes occur as well. Armed conflict itself provokes blunt injuries and burns, and trauma that are specific to weapons and the circumstances of warfare. More specifically, combat involves penetrating and blast injuries; these will be the major focus of this book.

Modern armed conflict causes specific penetrating and blast injuries, as well as blunt and burn trauma.

3.1.1 Blunt injury in war

Blunt trauma is common in war. Severe injury due to blunt trauma may be more difficult to detect than in cases of penetrating trauma, and X-ray diagnosis and other more sophisticated technologies are more valuable for patient assessment.

Road traffic crashes

Military vehicles often drive at high speed over difficult terrain where safe roads do not exist. In addition, the environment of any accident may be hostile (presence of enemy forces, minefields, etc.).

Collapsed buildings and falls

The collapse of bombed buildings will cause blunt and crush injuries to anyone inside. People may fall from destroyed buildings or a balcony.

Explosions and anti-tank mines

A bomb or shell explosion can throw people against objects. A car, bus or lorry carrying passengers may drive over an anti-tank mine. The explosion of the mine overturns or destroys the vehicle and people are thrown out and onto the ground, thus suffering blunt injuries.

Beatings

Mistreatment of prisoners, officials, "suspected sympathizers" or other civilians is, alas, all too common.

3.1.2 Penetrating wounds caused by weapons of war

A moving projectile has kinetic energy. When the projectile enters the human body, it releases energy to the tissues thus causing a wound. There are two types of wounding projectiles: bullets and metallic fragments (or splinters, shards, and shrapnel)[2].

Fragment wounds

Exploding bombs, shells, rockets and grenades, submunitions (cluster bomblets) and some landmines, produce metal fragments from the weapon casing (primary projectiles). In the past these fragments were usually irregular in size and shape. In many modern weapons, however, the inner lining of the casing is scored, creating weak points that break off easily on explosion. This generates a controlled fragmentation of large numbers of pre-formed fragments that are regular in size and shape, and usually less than 1 g in weight. In other, usually improvised bombs and explosive devices, nails, bolts, steel pellets or other metallic debris surround the explosive material.

T. A. Voeten / ICRC

Figure 3.1

Different types of shells and explosives.

---

[2] The word "shrapnel" is derived from the name of Major-General Henry Shrapnel (1761–1842), an English officer, who designed a new type of artillery shell. The term originally referred only to the metal balls dispersed when a shrapnel shell bursts, but is often used to describe metal fragments intentionally included in explosive devices. For shells, bombs or other munitions, the technical term for these particles is fragments, splinters or shards, fragments being the preferred name in scientific documents and the term that is used in this manual.

Fragments are shot off at a very high speed, which decreases rapidly with the distance travelled because of their non-aerodynamic character. The farther the victim is from the explosion, the more superficial the wounds. At very close range, multiple high-energy fragments combined with the blast effect create mutilating injuries and are often fatal.

Explosions may cause stones or bricks to break up, shatter glass panes, or the force of the blast wind may transport other debris, also producing penetrating fragments (secondary projectiles), as described in Section 3.1.4.

Fragment wounds are usually multiple and the wound tract is always widest at the entry. There may or may not be an exit wound.

Bullet wounds

Handguns and military assault rifles shoot bullets at high speed. Bullet wounds seen in the injured are usually single with a small entry; multiple bullet injuries are more likely to kill. There may be no exit wound but, if there is, the size is variable. The amount of tissue damage depends on a number of factors.

According to international humanitarian law – the Third Hague Convention of 1899 – all bullets used during armed conflict are supposed to remain intact. They are designed to wound, not kill. They have a full metal jacket (usually copper or plated steel) and should be so manufactured as to prevent any fragmenting when they hit the human body. Because of various ballistic effects, some bullets do break up into fragments in the body.



B. Kneubuehl

Figure 3.2.1

Examples of pistol ammunition:

a. 5.45 x 19 mm

b. 6.35 mm Browning

c. 7.63 mm Mauser

d. 9 mm Luger

e. 45 mm automatic

f. 50 mm AE (Action Express) semi-jacketed bullet



B. Kneubuehl

Figure 3.2.2

Examples of military rifle ammunition:

a. 5.45 x 39 mm Kalashnikov

b. 7.62 x 39 mm Kalashnikov

c. 7.62 x 54R Dragunov



B. Kneubuehl

Figure 3.2.3

Semi-automatic pistol 9 mm Luger (SIG-Sauer P 228).



B. Kneubuehl

Figure 3.2.4

7.62 x 39 mm AK-47 Kalashnikov military assault rifle.

first time have been published in the West. Until recently these were scattered and inaccessible, except for highly fragmented information. Essential to the Taoist tradition is religious practice in the feeling and experiencing of the sacred and the divine, and not in the beliefs about them.

The Taoist view on the nature of religiosity as an experience of connection and reconnection is very much in line with the original meaning of the root of the word religion in Latin, “re-ligare”, to reconnect.

Thus the practice is oriented to rediscovering the intrinsically ecstatic nature of the body in which it spontaneously feels the truthfulness of life as a sacred, naturally ecstatic activity. The whole practice may be summarized in facilitating the process of reconnecting and returning to the state we were in before being born.

Basic to the transformation process which is conducive to this rediscovery is the Healing Love practice by which the sexual energy is retained, its flow is inverted and the nature of this energy is transformed. The Fusion Practices play an essential role in making possible the further refinement of this energy in the Kan and Li practices through new forms of purification and by enhancing the receptivity of the body for higher energies from the universe. The Taoist practice takes literally the Christian tenet that the body is the temple of God by viewing the vital energy or life force energy as a sacred energy through which the body reveals its divine nature as an intrinsic endowment in which heaven and earth merge.

Wisdom of making Friends with the Devil

The three monotheistic religious mainstreams in their institutionalized esoteric form -- the Jewish, Christian and Islamic -- are marked by a deep duality between high and low, sacred and non sacred, right and wrong, good and evil, mind and matter, mind and body, mind and energy. This duality has also shaped other religious and philosophical systems in their social and institutional evolution; systems such as Hinduism, Buddhism, Taoism and Confucianism. These systems have been marked by beliefs and codes of ethics which have tended to split humankind between believers and nonbelievers and between those that are good and those that are bad.

Cut wounds, *"arme blanche"*

Apart from the modern soldier's bayonet, knives, machetes or *pangas*[3] may be used by combatants in "traditional" warfare in some societies. These produce incised or puncture wounds.

3.1.3 Anti-personnel landmine wounds

Anti-personnel landmines (APM) come in two basic types: blast mines with a pressure plate that explode when someone steps on them, and fragmentation mines which explode when a tripwire is touched. Unexploded ordnance is often left on the battlefield and has similar injuring effects as fragmentation mines (the lethal remnants of war consisting of cluster bomblets, bombs and shells that did not explode when fired). These weapons continue to kill and injure large numbers of civilians long after the end of hostilities and have widespread humanitarian and economic repercussions.


ICRC

Figure 3.3.1

Blast mine.


ICRC

Figure 3.3.2

Fragmentation mine.


ICRC

Figure 3.3.3

PMF "Butterfly mine".

Patterns of injury

Anti-personnel mines cause three distinct patterns of injury according to the blast effect or the production of fragments.

Pattern 1

A person steps on the pressure plate of a blast mine. The explosion and local primary blast effect cause a traumatic amputation or severe injury of the contact foot and leg. There may be wounds to the other leg, genitals, abdomen or pelvis, and the contralateral arm. The severity of the wound depends on the amount of explosive in the mine compared to the body mass (Figure 3.4).

Pattern 2

A person touches the tripwire attached to a fragmentation mine, which provokes its detonation. Fragmentation mines cause the same injuries as other fragmentation devices, such as bombs or grenades, and the severity of the injury depends on the distance of the victim from the explosion.

Pattern 3

A person handles a mine: setting a mine; trying to clear a mine; a child playing with a mine. The explosion causes severe injury to the hand and arm, and frequent injuries to the face and eyes or chest.

For further information on anti-personnel landmine injuries, see Volume 2.


R. Coupland / ICRC

Figure 3.4

"Umbrella" effect of blast mine: superficial tissues suffer less damage than deep-tissue planes. The wounds are all severely contaminated by mud, grass, and pieces of the shoe driven deep into the tissues at the moment of explosion.

---

[3] In some countries where a "traditional" form of warfare is still practised, a large, heavy knife – the machete or *panga* – is often used as a weapon. The overhead motion strikes the victim on the head, neck or shoulder.

3.1.4 Explosive blast injuries



Figure 3.5

Blast wave overpressure followed by negative pressure trough.

The detonation of high-energy explosives creates a travelling pressure blast wave in the air, (or in water for underwater explosions). The wave causes rapid and large changes in the outside atmospheric pressure: the positive pressure shock wave is followed by a negative pressure phase (Figure 3.5). Immediately behind the pressure wave is a mass movement of air: the blast wind.

As the blast wave passes any unprotected person it affects all parts of the body, especially those normally containing air. A victim of blast may not have any external injury. A single, large explosion may injure many people at the same time. Explosions in a closed space (building, bus, etc.) are more fatal than those out in the open.

Categorization of blast injuries
Blast injuries are commonly categorized into four types.

Primary
These are direct pressure effects. Rupture of the tympanic membrane is the most common injury. Rupture of the lung alveoli and their capillaries ("blast lung") is the most lethal injury amongst survivors.

Secondary
These injuries include missile wounds. Fragments may arise from the bomb casing or contents (primary missiles). Home-made bombs (improvised explosive devices, known as IED) may be packed with nuts and bolts, screws and ball bearings. In addition, the blast wind may mobilize various objects (secondary missiles) that then cause penetrating wounds.

Tertiary
These effects are directly due to the blast wind. It can cause total body disintegration in the immediate vicinity of the explosion; traumatic amputations and evisceration further away. The wind can make buildings collapse or throw people against objects. Trauma may be blunt, crush or penetrating.

Quaternary
Miscellaneous types of harm due to burns, asphyxia from carbon monoxide or toxic gases, or the inhalation of dust, smoke or contaminants.

The various injuries caused by major blasts cover a whole spectrum of trauma and many patients suffer several injuries from a variety of effects: i.e. multiple injuries from one single weapon system.

Other situations of blast injuries
The blast wave travels more rapidly and much further in water than in air. Blast injuries in water occur at greater distances and can be more severe. Moreover, underwater explosions tend to cause pure primary blast injury. A "fuel air explosive" – the liquid explosive material is dispersed in the air like an aerosol and then ignited – also tends to bring about pure primary blast injury and quaternary effects due to the consumption of all oxygen in the nearby air.

The blast effect of a marine mine exploding below an icy surface, or the "deck slap" of a ship hit by a torpedo, produces a shock wave that can severely fracture the bones of anyone on deck or inside the ship. Similarly, some anti-tank mines send a blast wave through the floor of the vehicle causing closed fractures of the foot and leg. The foot appears like a "bag of bones" inside intact skin, which was described in World War I as "*pied de mine*": a mine foot. Anti-personnel blast mines have a local blast effect, vaporizing the tissues of the contact foot, as described previously.

For further information on blast injuries, see Volume 2.

3.1.5 Burns

A large explosion may cause flash burns or the carbonization of tissues. Bombing may start secondary fires in buildings and an anti-tank mine may ignite the petrol tank of a vehicle. Burns are common amongst the crews of tanks, ships and aircraft hit by missiles. Some types of anti-personnel blast mines provoke burning as well as traumatic amputation of the limb.

Certain weapons cause specific burns: napalm and phosphorus bombs, magnesium flares.

3.1.6 Non-conventional weapons

International humanitarian law prohibits the use of chemical and biological weapons. Nonetheless, many countries have stocks of them. If not used during actual combat, they may nevertheless be released when storage warehouses are bombed.

Radioactive agents have come into greater use recently, such as depleted uranium in anti-tank shells. Residual radioactive shells and debris constitute a long-term hazard. A bomb surrounded by radioactive material – the so-called "dirty bomb" – is not a nuclear bomb. The explosion is caused by conventional means but radioactive material is spread out over a wide area. The bombing of nuclear medicine and other laboratory facilities, or nuclear power plants, may also release radioactive material into the atmosphere.

The reader should refer to standard military texts and those of the Organization for the Prohibition of Chemical Weapons (OPCW), and relevant documents of the World Health Organization for further details. Nuclear weapons shall not be discussed here.

3.2 Ballistics

3.2.1 Introduction

Blast and penetrating missile wounds occur in times of armed conflict and whenever the weapons of war are used in peacetime. Weapons cause specific but variable patterns of injury. While standard surgical techniques will suffice to treat simple wounds, the management of war wounds produced by high-energy weapons is based on an understanding of the mechanisms by which projectiles cause injury: wound ballistics. Only by understanding certain physical phenomena can the surgeon appreciate the different varieties of wounds seen in armed conflict and the difference between these wounds and the trauma that is seen in everyday civilian practice.

Although the study of ballistics may be "interesting" in its own right, the clinician does not always know what weapon inflicted the injury; and *never* knows the energy available at point of impact. One can only estimate the transfer of energy in the tissues from the extent of tissue damage.

The study of ballistics gives us an understanding of the basic mechanisms at work during wounding. The importance of this knowledge lies in the fact that projectile injuries should be neither under- nor over-treated. The clinical assessment of the actual wound is the most important factor determining management, and an understanding of ballistics allows the surgeon to better understand the pathology and assess the injuries that he sees, rather than explain every wound and determine specific treatment. "Treat the wound, not the weapon"[4] is not a vain concept.

Basic definitions
Ballistics is the part of the science of mechanics that studies the motion and behaviour of a projectile, and its effects on a target.

Internal ballistics
Internal ballistics deals with the processes that occur inside a gun barrel when a shot is fired: gas pressures on combustion of the propellant powder, the energy and heat released, and the course of the projectile in the barrel, are just some of its concerns.

---

[4] Lindsey D. The idolatry of velocity, or lies, damn lies, and ballistics. *J Trauma*. 1980; **20**: 1068 –1069.

External ballistics

External ballistics describes the projectile trajectory once it has left the barrel. The influences affecting the flight include gravity, air resistance and crosswind deflection, stability of the projectile (spin and yaw), as well as any contact prior to the projectile reaching the target, known as ricochet.

Terminal ballistics

Terminal ballistics describes what happens when the projectile hits the target, as well as any counter-effects produced by the target on the projectile. If the target is biological tissues, terminal ballistics is called *wound ballistics* and describes the effects on the tissues.

3.2.2 Internal ballistics

Bullets: fundamental concepts

Figure 3.6 shows the main components of a bullet cartridge. The primer is struck by a mechanism in the gun to produce a small detonation and flame that sets off the powder in the case. This causes a very rapid burn with the production of a large volume of rapidly expanding gas, which pushes the bullet out of the barrel of the gun. The velocity with which the bullet leaves the barrel is called the muzzle velocity.



B. Kneubuehl

Figure 3.6

Main parts of a bullet cartridge.

Bullet construction

Bullets are classified according to a number of parameters; one is their manufactured composition (Figure 3.7). They vary according to their calibre and mass.



B. Kneubuehl

Figure 3.7

Bullets according to construction.

a. 303 British Mark II produced in Dum Dum, India, 1896 (see footnote number 6).

b. Full metal jacket (FMJ): military-issue bullets have a soft core (lead) with a full metal jacket of copper. This standard has been established by various conventions and treaties of IHL, especially the Third Hague Convention of 1899.

c. Hard core bullet: the lead has been replaced by steel or tungsten for better penetrating power.

d. Tracer bullet: contains a pyrotechnical substance at the tail-end that burns up in flight and illuminates the trajectory. Used to identify and pinpoint the target.

e. Semi-jacketed bullet (SJ): part of the point is not jacketed, thus exposing the lead inside. This is supposed to be used only for hunting; its use by combatants during armed conflict is illegal.

f. Semi-jacketed hollow-point (SJ-HP): also a hunting bullet with a hollow nose tip; also illegal during armed conflict.

Apart from the hunting bullets mentioned in Figure 3.7, special rifles and their ammunition exist for hunting: shotguns whose shells give off multiple lead or steel shots (pellets) available in diameters from 2 to 9 mm (Figure 3.8).



B. Kneubuehl

Figure 3.8

Shotgun shell and load of shot.

Hunting bullets are not supposed to be used by combatants in armed conflict. These bullets are constructed in such a way as to kill rather than wound. The idea is to be more "humane" when hunting wild animals and to have a "rapid and clean kill". Nonetheless, the surgeon will be faced with wounds caused by such weapons either because of accidents, criminal activity, or because combatants have illegally used them during combat.

The international legal limits placed on bullets used by the military do not apply to domestic use during peacetime, and the civilian surgeon may at times face more devastating gunshot wounds than the military surgeon on the battlefield.

Muzzle velocities

Firearms are classically divided into two categories: high-velocity (rifles) and low-velocity (handguns).The latter fire relatively heavy bullets at low muzzle velocities of 150 – 200 m/s. A typical military assault rifle fires a smaller bullet at 700 – 950 m/s. This, however, says nothing about the actual velocity when the bullet reaches the target.

9 mm Luger pistol	350 m/s
.38 Special handgun	260 m/s
.44 Magnum handgun	440 m/s
7.62 x 51 mm NATO rifle	830 m/s
5.56 x 45 mm M16 rifle	960 m/s
7.62 x 39 mm AK-47 Kalashnikov rifle	720 m/s
5.45 x 39 mm AK-74 Kalashnikov rifle	900 m/s
12 gauge shotgun	420 m/s

Table 3.1 Some examples of muzzle velocity from different firearms.

The gun barrel

A bullet is a long projectile that only flies with stability if a high spin around its longitudinal axis is attained, thus giving it a gyroscopic effect. To achieve this spin, gun barrels are constructed with interior spiral grooves (twists). This is a "rifled" barrel, used in all handguns and high-velocity rifles (Figure 3.9).



B. Kneubuehl

Figure 3.9

Cross section of a rifled gun barrel:
5.56 x 45 mm M-16 A4 military assault rifle.
The grooves and lands (the elevated sections between the grooves) are shown.

The barrels of shotguns are smooth on the inside; they are not "rifled". This limits their accuracy and distance of fire (Figure 3.10).



B. Kneubuehl

Figure 3.10

Typical hunting shotgun with smooth barrel.

Design of firing

Another classification of firearms is according to their design of firing. A weapon operated with a single hand is a "handgun". If the barrel and cartridge chamber are in one piece, this is a "pistol". If several chambers rotate behind the barrel, it is called a "revolver". If both hands are required to operate the weapon, it is referred to as a "rifle" or "shotgun".

Firing capacity defines how individual shots are fired. For a single-shot weapon, every shot is loaded individually. A repeating weapon includes a magazine that holds a series of cartridges which load manually one after the other. If the loading movement is repeated automatically after every shot, but every shot is fired individually, this is a semi-automatic weapon. If the automatic loading of cartridges allows several shots to be fired with one pull of the trigger, it is known as an automatic weapon.

In modern military usage, most weapons are automatic rifles and sub-machine guns or semi-automatic pistols.

3.2.3 External ballistics

Flight in air

Once shot off, several variables affecting the projectile in flight tend to influence its stability, accuracy of targeting, or velocity. The most important variables include the following.

- Spin around its own longitudinal axis, giving it gyroscopic stability.
- Distance travelled and the effect of gravity, including the shooting angle – is the bullet shot upwards or is the trajectory flat?
- Air drag: friction is responsible for 10 % of total area drag, while 90 % is due to pressure effects; faster bullets are retarded proportionately more – rifle bullets are aerodynamically shaped to decrease air drag; this is not the case with shotgun cartridges or metal fragments.
- Crosswind deflection.
- Raindrops hitting the bullet.
- Bullet hitting an obstacle before hitting the target.

Yaw

A rifle bullet in flight does not travel in a simple straightforward motion. Because it is a spinning gyroscope, the bullet "wobbles" and undergoes some very complicated movements (nutation, precession), the most important being yaw: the nose of the bullet moves up and down, away from the line of flight, and describes an angle with the target surface at impact (Figure 3.11). This influences the wounding potential of the bullet, as an important degree of yaw will destabilize the motion of the bullet inside the target.



B. Kneubuehl

Figure 3.11

Angle of incidence and angle of impact:

a. longitudinal axis of bullet
b. direction of flight

Ψ. angle of incidence
δ. angle of impact

Ricochet

A bullet may hit an obstacle during its flight. This may be a branch of a tree, a belt buckle, a concrete wall or the ground, or a soldier's helmet or flak jacket. This causes a ricochet; the bullet is given a small "push" that destabilizes it (Figure 3.12). There is an increase in the deviation of the nose of the bullet (yaw); the bullet may even tumble, rotating around itself. Such a large yaw angle at point of impact, as mentioned above, will have important consequences for the wounding potential of the bullet in the target.

In addition, if the "push" is great enough, the bullet can be deformed or even broken up into fragments before hitting the target.



B. Kneubuehl

Figure 3.12

Ricochet: effect on a bullet after collision with an obstacle.

3.2.4 Summary

There are, therefore, quite a number of variables involved in determining the characteristics of a projectile *before* it hits the target and these will influence its behaviour in the target and the efficiency in creating wounds. They include:

- velocity at moment of impact and any residual velocity if there is an exit;
- mass, form and shape of the projectile, bullet construction;
- type of weapon, handgun or rifle;
- stability of the projectile in flight;
- any yaw at moment of impact.

3.3 Terminal ballistics

3.3.1 Role of kinetic energy

Any moving object has kinetic energy, whether it is a hand-wielded knife or club, a bullet fired from a gun, or a fragment given off by the explosion of a shell. This energy is described by the well-known formula:

$$E_K = \tfrac{1}{2} m v^2$$

This defines the total kinetic energy that the object possesses, but does not define the kinetic energy expended when the projectile passes into and through a target. For a bullet or fragment that does not change its mass, this is calculated from the difference in velocity between entry and exit.

$$E_{K\,EXP} = \frac{m\,(v_1{}^2 - v_2{}^2)}{2}$$

If there is no exit, then $v_2 = 0$, and all the kinetic energy has been transferred. If the bullet breaks up into fragments, then the mass (m) also changes, and $E_{K\,EXP}$ is modified.

Total kinetic energy is the potential for causing damage; transferred kinetic energy is the capacity to cause damage. Actual tissue damage, however, depends on the efficiency of this energy transfer, which is determined by many other variables, as will be shown.

Weapons according to E_K
Yet another classification of weapons is based on the amount of kinetic energy available for transfer.

- Low energy: knife or hand-energized missiles.
- Medium energy: handguns.
- High energy: military or hunting rifles, with a muzzle velocity above 600 m/s.

For metal fragments given off by an explosion the initial velocity is very high; this decreases rapidly with distance. The wounding potential depends on the mass of the fragment and the distance of the victim from the weapon.

3.3.2 Laboratory experiments

Many researchers have performed different experiments to describe the effect of projectiles on tissues. Targets have included human cadavers, various animals (pigs, dogs, goats) and tissue simulants.

Tissue simulants are specially-prepared blocks of gelatine or glycerine soap, which have a density and/or viscosity close to that of muscle tissue. Soap is plastic and any deformation remains unchanged, representing the maximum effects. Gelatine is elastic and deformations disappear almost entirely; they are studied with high-speed cameras. If the stress on gelatine exceeds the limit of its elasticity then it will crack and tear, showing fracture lines.

Compared to human cadavers and animals, tissue simulants have the advantage of allowing repetitions of the experiment, changing only one variable at a time. These laboratory experiments are all approximations, however, of what happens in a live human being.

Surgeons working for the ICRC have collaborated over many years with the ballistics laboratory of the Swiss Federal Department of Defence.[5] This laboratory uses gelatine and glycerine soap for its ballistics experiments. Its results have been confirmed by comparison with clinical cases treated by ICRC surgeons in various war zones throughout the world.

---

[5] See footnote 1.

Following these laboratory studies, five categories describe the behaviour of projectiles: non-deforming and deforming bullets, be they from rifles or handguns, and fragments.

3.3.3 Non-deforming rifle bullet: full metal jacket (FMJ) military bullet

When a standard military bullet hits a soft object while in stable flight, it produces a "shooting channel" that presents three distinctive phases: narrow channel; primary temporary cavity; and terminal narrow channel (Figure 3.13).

Figure 3.13

Non-deforming rifle bullet (FMJ) in soap.



B. Kneubuehl

Phase 1

Straight narrow channel with a diameter about 1.5 times the calibre of the bullet. The greater the velocity, the wider the channel. Different types of bullets have a different length of narrow channel, typically 15 – 25 cm.

Phase 2

The channel opens into the "primary temporary cavity". The reported diameter of this cavity is anywhere between 10 and 15 times the calibre of the bullet.

Figure 3.14 shows the motion of the bullet in gelatine. It starts to yaw, and tumbles, turning a full 270°, and then advances with its tail end forward. The whole lateral surface of the bullet comes into contact with the medium, which greatly decelerates the bullet and subjects it to an important stress.

Figure 3.14

The bullet tumbles in the gelatine or soap: it rotates 270° around a transverse axis that is perpendicular to the long axis. (Graphic demonstration of bullet superimposed on soap blocks. The proportions between bullet and trajectory are exaggerated for the sake of clarity.)



B. Kneubuehl

The slowing of the bullet involves a release of kinetic energy, which, in turn, causes the rapid and massive displacement of gelatine radially outwards, producing a cavity *behind* the projectile; there is a slight delay in the production of the cavity because of the inertia of the gelatine mass. There is an almost complete vacuum in this cavity that quickly sucks in air from the entry hole, and from the exit hole if there is one. The cavity collapses after a few milliseconds, only to reform again, with a smaller volume. The cavitation continues until all the transferred energy is used up: the cavity pulsates! In water or gelatine, there are up to 7 – 8 pulsations, in biological tissues usually 3 – 4.

The diameter of this cavity depends upon the elastic properties of the medium, as well as the amount of kinetic energy transferred. Fissures radiating from the shooting channel indicate that the shearing effect of the cavity has exceeded the elasticity of the gelatine.

Phase 3

The tumbling slows down and the bullet continues in a sideways position at a considerably reduced speed. In some cases, a narrow straight channel is observed; in others, the tumbling seems to continue but backwards, the bullet again assuming a lateral position, and a second cavity occurs. This does not reach the size of the primary temporary cavity. The bullet then creeps forward and finally stops, always with the tail end facing forwards.

In an elastic medium such as glycerine, what remains in the shooting channel at the end of the process, and all temporary effects, is called the "permanent channel".

References to these basic definitions of phases of the shooting channel will be made throughout this chapter.



R. Coupland / ICRC

Figure 3.15

The sketch shows the position of the bullet and the extent of the shooting channel at different phases. The graph represents the transfer of kinetic energy along the bullet track: bullet fragmentation occurs at the peak of energy transfer.

Please note:

These three phases are found with all FMJ rifle bullets, yet each bullet has a specific shooting channel. The narrow channel of the 7.62 mm AK-47 is long (15 – 20 cm), while the 5.45 mm AK-74 produces a narrow channel of less than 5 cm before cavitation begins.

Tumbling – yaw – in the target medium

Given a long enough shooting channel, all FMJ rifle bullets tumble. How early the tumbling motion begins determines the length of the narrow channel, and the onset of cavitation. This depends on the stability of the bullet – yaw – at the point of impact. The less stable the bullet in flight, the greater the yaw, which rapidly brings a larger bullet surface into contact with the medium, leading to early tumbling and a short narrow channel. How early FMJ bullets tumble is also a function of their manufacture: mass, centre of gravity and shooting distance, etc.

Fragmentation of FMJ bullets

It is during phase 2 – the temporary cavity – that certain bullets deform or even break apart because of the enormous stress exerted on them. This occurs when the bullet-medium interface is at its maximum, the cavity is widest, and the transfer of kinetic energy is highest (Figures 3.15 and 3.16). If the projectile acts on the target medium, this is a good example of the medium acting on the projectile. This fragmentation occurs only at short shooting distances, up to 30 – 100 m, depending on the bullet's construction and stability.



B. Kneubuehl

Figure 3.16

Fragmentation of FMJ bullet during phase 2, i.e. temporary cavitation.

The bullet flattens on its sides, bends in the middle and, finally, the jacket splits and the lead inside spills out (Figure 3.17). This gives the "shower of lead" picture often seen on X-rays (Figures 3.35, 4.5 and 10.5). If the bullet breaks, the smaller fragment typically deviates downwards. The fragmentation depends on the construction of the bullet and the velocity; with impact velocities below 600 m/s, no FMJ deforms or breaks apart.

If the bullet does fragment then the primary temporary cavity is larger than is the case with an intact bullet. This represents a much larger transfer of kinetic energy and has important clinical repercussions.



ICRC

Figure 3.17

Jacket split apart, exposing the lead within.

3.3.4 Deforming and fragmenting rifle bullets: dum-dum[6]

Some bullets (e.g. hunting bullets) are constructed to always deform or break up into fragments: hollow-nosed, semi-jacketed (SJ), soft-pointed, etc. (Figure 3.7 e and f). These are usually grouped under the term "dum-dum" bullets and are illegal for military use according to international law.

Deforming bullets are made to change their shape readily ("mushrooming"), thus increasing their cross section area, but without losing mass. The spent bullet weighs as much as the original. They are used mainly in handguns with a muzzle velocity below 450 m/s, and are available for domestic use (special police forces *and* criminals). Fragmenting bullets, on the other hand, break up and lose mass, and create a "wall" of particles, thus increasing the total effective area of cross section. They are used for hunting.

Figure 3.18 demonstrates a semi-jacketed rifle bullet mushrooming immediately on impact with a soft medium. The increased cross section causes a greater bullet-medium interaction; the bullet slows down quickly, releasing kinetic energy very early. The narrow channel almost completely disappears and the temporary cavity occurs right after impact. At first, the cavity is almost cylindrical; it then decreases conically.

Figure 3.18

Deforming semi-jacketed rifle bullet (SJ) in soap. The bullet "mushrooms" just after impact, then continues in a linear trajectory. (Graphic demonstration of bullet superimposed on soap blocks.)



B. Kneuebuehl

The principal difference between a full metal jacket and semi-jacketed bullet is at what depth of penetration the maximum energy transfer occurs in the shooting channel. The volume of the cavities is the same in both examples in Figure 3.19 indicating equal transfer of kinetic energy.

Figure 3.19

Soap blocks showing comparison between ballistic profiles of FMJ and SJ bullets – the transfer of kinetic energy occurs far sooner with the SJ bullet.



B. Kneuebuehl

---

[6] The Indian Ordnance Department of the British Army developed a bullet for its colonial troops in 1897 at an ammunition factory in the town of Dum Dum, north-east of Calcutta (Kolkata) because the previous one was judged to be ineffectual and caused insignificant injuries. The bullet had a round nose with a full metal jacket of copper-nickel covering a lead core, with the exception of 1 mm at its tip where the lead was bare. The bullet was used against the Afridi Afghans in 1897 – 98, and again against the Mahdi Army at Omdurman, Sudan, in 1898 with devastating effect. The bullet was judged to be "inhumane" according to the Declaration of St Petersburg of 1868 and was banned by the Hague Convention of 1899. Projectiles causing unnecessary injuries ("*maux superflus*") were not allowed. As an example, the Conventions mentioned projectiles whose metal jacket did not fully cover the lead core. Since then, all projectiles possessing the same qualities (deformation by expanding or flattening easily, fragmentation) have received the collective name of dum-dum.

Their focus on the duality between God/ the divine and heaven and earth, God and the Devil, good and evil, mind/spirit and body and on sin and its corollaries, fear and guilt, have created much violence and tend to continue to do so. They have also greatly affected people's sense of dignity, self-esteem and independence, as they have tended to create major dependencies on institutional intermediation with the divine.



Fig. 9.1 *Balance of Yang and Yin (Good and Bad)*

In many pre-industrial cultures there are proverbs and legends which suggest that it is wise to make friends with the devil rather than fight him. It would seem that such intuitions are based on the insight that it is better to reconcile and accept oneself so that the negative loses its power rather than opposing it, by which its power increases, especially when fear and anger rise and the negative is turned into an obsession. Simple observation confirms the truth of this insight: that the energy of what is viewed as negative and dark increases to the extent that there is an attempt to eradicate it.

This same principle shows up in the martial arts: never initiate the fight but let the enemy come and neutralize him by making use of his own energy, as in the case of Tai Chi and Aikido.

A leading philosopher of culture and humanist therapist in the West, Erich Fromm, has said that the propagation of these views, often in extremely violent ways, has broken the spiritual backbone of the people.

Esoteric systems have, however, never succeeded in wholly eradicating and repressing their esoteric roots, visible in multiple

The same effect can be demonstrated when using a synthetic bone simulant encased in gelatine (Figure 3.20).



B. Kneubuehl

Figure 3.20

Comparison of FMJ bullet versus SJ bullet: synthetic bone at a shallow depth of gelatine. The FMJ bullet breaks the bone simulant during the narrow channel phase; the shooting channel is practically the same with or without the bone simulant. At the same depth, the SJ bullet shatters the bone simulant completely.

Ricochet effect

When a FMJ bullet strikes an obstacle before hitting the target it is destabilized. After impact, there is almost no narrow channel and the shooting channel resembles what occurs with a deforming or dum-dum bullet (Figure 3.21). This phenomenon has important clinical consequences.



B. Kneubuehl

Figure 3.21

FMJ rifle bullet after ricochet effect in soap. The large impact angle after ricochet destabilizes the bullet, which tumbles easily and early in the shooting channel. Note that the cavitation occurs almost immediately on impact, similar to an SJ bullet.

Please note:

Jacket construction is not the only decisive factor in bullet behaviour be it full or semi-jacketed. It is quite possible to manufacture a bullet that will fragment at high velocities, deform at medium velocities, and retain a stable shape at low velocities.

3.3.5 Handgun bullets

Handgun bullets may be much heavier than rifle bullets.

Non-deforming bullet

The shooting channel of a non-deforming bullet shows little yaw and no tumbling; the bullet remains with the tip pointing forward with deep penetration (Figure 3.22). Temporary cavitation is long and narrow.

Figure 3.22

Standard military pistol bullet, full metal jacket in soap, no tumbling of the bullet. (Graphic demonstration of bullet superimposed on soap blocks.)



B. Kneubuehl

Deforming bullet

A soft point, deforming pistol bullet – as used by special police forces – mushrooms at entry (Figure 3.23). The large cross section area causes an abrupt reduction in velocity and transfer of kinetic energy with an immediate, and large, temporary cavity.

Figure 3.23

Deforming handgun bullet in soap: mushrooming effect. (Graphic demonstration of bullet superimposed on soap blocks.)



B. Kneubuehl

3.3.6 Fragment projectiles

Fragments given off from the explosion of a bomb, rocket or grenade are not aerodynamic; they have an irregular shape. Their velocity decreases rapidly with distance owing to air drag. They have an unstable flight path with an irregular rotation around an indefinite axis. On impact, the biggest cross section comes into contact with the target surface, immediately transferring a maximum of kinetic energy. No yaw or tumbling occurs in the target.



B. Kneubuehl

Figure 3.24

Fragment profile in soap: the widest point is at entry, the cavity is cone shaped.

The shooting channel always has the largest cavity diameter at the entry, and is larger than the diameter of the fragment. The cavity then decreases constantly in a cone-like fashion (Figure 3.24).

The depth of penetration of the fragment will depend on its kinetic energy, but with a particular relationship between velocity and mass. Figure 3.25 shows two fragments with the same kinetic energy; the volumes of the cones are equal.

Thus, a light but rapid fragment tends to transfer most of its energy shortly after impact on the target; a heavy and slow fragment penetrates further and dissipates its energy along the longer shooting channel.



B. Kneubuehl

Figure 3.25

Two fragments with the same kinetic energy – note the difference in energy deposition along the track, demonstrated by the difference in the cavities:

a. lightweight and fast fragment;
b. heavy and slow fragment.

3.4 Wound ballistics

Moving projectiles cause wounds by a transfer of kinetic energy to the body that destroys, disrupts, and deforms tissue. One studies wound ballistics in order to understand the mechanisms that produce this injury.

Potential for wounding is one thing; the *actual* wound facing the surgeon is another.

3.4.1 Laboratory studies *versus* human body

The experiments using tissue simulants as described above help one to understand the processes at work. Laboratory models are, nonetheless, only an approximation and show only the physical part of the process. The tissue structure of the human body is far too complex for a laboratory model to duplicate injuries. Tissue simulants have the disadvantage of being homogeneous media; living tissue is not, as described later. The laboratory results must be compared to clinical cases for confirmation and this has been the ICRC procedure in conjunction with the Armasuisse laboratory in Thun, Switzerland.

In the real world of clinical practice there are so many variables involved that one cannot be *predictive*; the surgeon cannot say with certainty that such and such a bullet will always result in a specific wound. One can however be *descriptive* and, after a good clinical examination, the surgeon can better understand the pathology that he sees, how it was created, and what sort of surgical management is required. The type of wound, its anatomic location, and the amount of actual tissue disruption are the determinant clinical factors.

3.4.2 Projectile–tissue interaction

When a bullet strikes a human body there is a projectile–tissue interaction that results in tissue damage, with a reciprocal influence of the tissues on the bullet. This interaction depends on a number of factors, which all result in the transfer of kinetic energy from the projectile to the tissues.

This transfer of kinetic energy either compresses, cuts or shears tissues, causing crush, laceration or stretch. The local energy transfer, at every point along the bullet track, is more important than the total quantity of energy transferred in producing tissue damage.

Tissue disruption is due to compression, cutting and shear: crush, laceration and stretch.

A bullet striking a human body demonstrates the *same three phases* as in the laboratory simulants – if the bullet track is long enough. In the laboratory experiments with glycerine, the "permanent channel" was defined as what remains of the shooting channel at the end of the process and all temporary effects. In biological tissues, the "permanent wound cavity" of the shooting channel is the definitive tissue damage after all temporary effects have been taken into account. This is the wound channel that the surgeon sees and is the final result of the crush and stretch of the tissues.[7]

Crush and laceration injury

A projectile causes physical compression and forcing apart of tissues along the shooting channel – crushing and laceration. This is the immediate physical effect of a penetrating foreign body; the bullet damages tissues with which it comes into direct contact, cutting through tissues as would a knife. This tissue damage is permanent and found in the final wound. This is the principal effect caused by low- and medium-energy weapons, such as handgun bullets.

---

[7] Much confusion has been created in surgical literature by authors calling the immediate crush damage of the phase 1 narrow shooting channel the "permanent cavity", as distinct from the "temporary cavity" where stretch damage occurs. In this manual, in accordance with the Armasuisse laboratory, the permanent wound cavity is the channel that remains at the end of the wounding process and constitutes the sum of crush and stretch injury.

At higher energies, when a bullet tumbles or deforms, a larger area of tissue is exposed to its effective cross section and suffers crush. The track left behind by crush is not equal along its length, but increases with bullet yaw in the tissues.

Stretch injury
Tissues have an elastic tensile strength that resists stretching. When a certain limit is reached, capillaries are ruptured and contusion of the tissues occurs. Beyond a critical limit, the tissues themselves are torn, just as laboratory gelatine shows fracture lines. The tissue damage from stretch may be permanent or only temporary.

Tissue stretch occurs during cavitation, which takes place in all projectile wounds, whatever the energy, type or motion of the projectile, and at all points along the entire shooting channel. There is even a minor cavitation effect during the phase 1 narrow channel.

The volume of the cavity is determined by the amount of energy dissipated and the tissue elasticity-resistance. This cavitation stretch performs work on tissues that have already been injured by crush, thus adding to the local immediate damage. In low- or medium-energy projectiles wounds, it is minimal.

When a bullet tumbles (or deforms or fragments), the release of kinetic energy is much greater and is superimposed on bigger tissue crush; the large phase 2 temporary cavity is the result: a momentary massive displacement of tissue in all directions away from the track of the bullet.

As in gelatine, the cavity pulsates: an elastic acceleration followed by a deceleration of the surrounding tissues: a shearing action. The near vacuum in the cavity sucks in air, contaminants and foreign bodies (textile strands from the clothing, dust, etc.), and bacteria, through the entry and any exit wound.

In high-energy wounds the *volume* of the temporary cavity can be up to 25 times that of the permanent cavity left behind, and anywhere between 10 and 15 times the *diameter* of the bullet. Although this volume is proportional to the kinetic energy dissipated, and will affect the amount of tissue damage, other factors related to the tissues can be even more important in determining the actual extent of injury.

3.4.3 Tissue factors

Resistance to crush, laceration and stretch differs widely among different types of tissues and according to anatomic structures. Tissue elasticity and heterogeneity are important factors in determining much of the bullet–tissue interaction.

Tissue elasticity
Elastic tissues tolerate stretch well, but may still suffer severe crush. The lung and skin have excellent tolerance, and leave relatively little residual damage after stretch. Skeletal muscle and the empty bowel wall have good tolerance. The brain, liver, spleen, and kidney are non-elastic, and shatter when stretched. Fluid-filled organs (heart, full bladder, full stomach and intestines) react badly owing to the incompressibility of the fluid contents; they may even "explode".

Nerves and tendons are mobile and blood vessels elastic; they are usually pushed out of the way by the cavitation.

Cortical bone is dense and rigid and resists stretch. However, if the cavitation accelerates a large enough muscle mass with sufficient energy the bone is bent beyond its tensile strength and breaks; it may even be shattered violently, especially the diaphysis of a long bone. This phenomenon is an example of a fracture without a direct hit by a bullet. The same mechanism takes place during fracture from a blunt injury, except that the energy transfer bending the bone occurs from the outside.

Tissue heterogeneity
Apart from these considerations of tissue elasticity, there is the particular local anatomy to consider. A block of gelatine approximates skeletal muscle in its elasticity and density, but it is homogeneous. A human limb or the face are a mixture of rigid

and elastic tissues comprising fascial compartments enclosing muscles, tendons and ligaments, large blood vessels and nerves, and bones. Not only does each anatomic element have a different elastic tensile strength, but the mixture of elements has its own interactive properties. The various interactions of projectile, soft-tissue organs and bony fragments can become very complicated.

Bound together and boundaries

How tightly tissues are bound together, and to nearby structures such as fascia of varying thickness, also affects the amount of permanent damage a cavity stretch can leave behind. If one side of a structure is fixed and the other side has free movement, a shearing force develops. Fascial planes may also serve as channels for the dissipation of energy – path of least resistance – to more remote tissues.

Boundaries limiting the pulsation of a temporary cavity can be very significant. They include not only fascia and aponeuroses, but also hollow, fluid-filled organs: the brain in the rigid cranium, the heart, the full urinary bladder. An empty stomach will be simply transfixed by a stable bullet. The same bullet will cause a full stomach to "explode".

A graphic laboratory example of boundary effect is found in Figures 3.26.1 and 3.26.2. The two pictures show the results with a high-energy bullet cavity. The apple literally explodes after passage of the bullet. Note that the cavitation effect *always follows* the passage of the bullet; it is not simultaneous.



Harold & Esther Edgerton Foundation, courtesy of Palm Press, Inc.

Harold & Esther Edgerton Foundation, courtesy of Palm Press, Inc.

Figures 3.26.1 and 3.26.2

Demonstration of boundary effect on the temporary cavitation due to a high-energy rifle bullet: the apple literally explodes after the passage of the bullet.

Clinically, these effects can create apparent paradoxes. For example, a heavy and slow bullet can cause a more severe wound in highly elastic tissue, such as lung, than a lighter, faster bullet with more kinetic energy. The heavier, slower bullet produces more crush. The faster, lighter one uses up more energy in creating the temporary cavity, which leaves little residual damage. However, the faster and lighter bullet will create more damage in less elastic tissue (liver, brain), which cannot accommodate stretch as well.

Transfer of kinetic energy does not affect all tissues to the same extent and in the same way.

3.4.4 Pathological description of the permanent wound cavity

The permanent cavity of the final wound that the surgeon sees is the result of a mixture of crushing, laceration and stretching of the tissues. Most of the damage in the majority of ballistic wounds is due to direct crush and laceration.

A number of macroscopic and microscopic changes occur. Severe vasoconstriction blanches the skin around the entry wound for 3 – 4 hours owing to the stretch. This is followed by a hyperaemic reaction that lasts up to 72 hours.[8]

---

[8] Fackler ML, Breteau DVM et al. Open wound drainage versus wound excision in treating the modern assault rifle wound. *Surgery* 1989; **105**: 576 – 584.

In the wound of skeletal muscle itself, three histological zones have been described (Figure 3.27).[9]

1. Crush zone of the wound channel filled with torn and necrotic tissues: 2 – 4 times the diameter of the bullet.
2. Contusion zone of muscle adjacent to the missile tract: the thickness of this zone is variable and averages about 0.5 cm; tissue damage is irregular and uneven.
3. Concussion zone of variable distance with congestion and extravasation of blood: the stretch is not great enough to tear tissues, but sufficient to injure capillaries. The demarcation between the contusion and concussion zones is not always well defined.



B. Kneubuehl
Figure 3.27.1
B. Kneubuehl
Figure 3.27.2
B. Kneubuehl
Figure 3.27.3

Figure 3.27

Schematic drawing of histopathological changes in the shooting channel:

3.27.1 geometric shooting channel
3.27.2 phase of maximum temporary cavitation
3.27.3 final wound channel

a: zone of crushed tissues
b: contusion zone
c: concussion zone
d: unaffected tissues

These histological changes are more severe with high kinetic-energy transfer – tumbling or deformation of the bullet – and do not change notably over 72 hours. The tissue damage is irregular along the wound track and how much of the damage is irreversible is not immediately apparent. This has obvious consequences for wound management and the extent of surgery necessary (see Chapter 10).

Bacteria are also seen within the permanent cavity. The sucking action of cavitation aspirates bacterial flora from outside, and projectiles are not sterile; the heat of firing is not high enough for long enough to sterilize the bullet.

3.4.5 Clinical applications

> The external appearance of a bullet wound can be deceptive. Tiny entrance and exit holes can be associated with extensive internal damage.

The length of the shooting channel in the body, the existence of an exit wound, and the characteristics of the particular structures traversed, will all greatly affect the final wound caused by a high-energy bullet that the surgeon sees.

The position of the phase 2 temporary cavity along the wound track is clinically very relevant. Figure 3.28 demonstrates the trajectory of an FMJ rifle bullet in a laboratory soap block with a simple entry wound and three possible exit wounds.



B. Kneubuehl

Figure 3.28

Exit wounds may occur before, during or after cavitation, depending on the length of the shooting channel in the body.

---

[9] Wang Z, Feng JX, Liu YQ. Pathomorphological observation of gunshot wounds. *Acta Chir Scan* 1982; **508**: 185 – 189.

The injured body part may not be long enough for temporary cavitation to occur. Figures 3.29.1 and 3.29.2 show small entry and exit wounds along the narrow channel of phase 1, with little intervening tissue damage.



R. Coupland / ICRC

Figure 3.29.1

Small entry and exit wounds, through-and-through injury.



R. Coupland / ICRC

Figure 3.29.2

The radiograph shows a small drill-hole fracture of the acromion: phase 1 narrow-channel injury only.

The wound is large when the exit takes place *during* cavitation (Figures 3.30.1 – 3.30.3).



R. Coupland / ICRC

Figure 3.30.1
Gunshot wound to the thigh; the small entry is medial and the large exit on the lateral aspect.



R. Coupland / ICRC

Figure 3.30.2
There is a severe comminuted fracture of the femur and fragmentation of the bullet.



R. Coupland / ICRC

Figure 3.30.3
The exit occurred during cavitation. The fragmentation of the bullet is a tell-tale sign of severe tissue damage. Wound Score: Grade 3, Type F (see Chapter 4).

When the small exit wound occurs *after* cavitation, the *intervening* damage can be severe (Figures 3.31.1 and 3.31.2).



R. Coupland / ICRC

Figure 3.31.1

Small entry and exit wounds with severe damage in between.



R. Coupland / ICRC

Figure 3.31.2

The same wound after excision and partial healing.

With a handgun bullet, the cavitation effects are minimal and the final wound channel is almost entirely due to crush whatever the length of the shooting channel (Figure 3.32.1 and 3.32.2).



B. Kneubuehl

Figure 3.32.1

Small entry and exit wounds from an FMJ handgun bullet: demonstration in a soap block.



B. Kneubuehl

Figure 3.32.2

Handgun bullet wound to the thigh.

The case of bone

The direct impact of a bullet on bone is different according to where this occurs in the shooting channel. Three clinical situations arise, corresponding to the phases of the shooting channel. In the first case, the stable bullet of phase 1 causes a small "drill-hole" fracture. A small cavitation occurs, and the bone then collapses on itself. The final hole is smaller than the calibre of the bullet (Figure 3.29.2).

In the second case, the bone is broken into multiple fragments owing to a higher release of kinetic energy from the larger cross section of the tumbling bullet during phase 2 (Figure 3.33). Each bone fragment creates its own local crush damage; the muscle is cut up in between the fragments. Afterwards, the temporary cavitation acts on this shredded muscle with lowered tensile strength; the cavity is greater and the final remaining wound channel is larger. The bone fragments always remain within the temporary cavity; they do not produce a new second wound outside the cavity. Detached pieces of muscle and the bone fragments are found inside the final wound, which is usually very severe. This is of obvious clinical relevance to the management of these wounds.

The damage that occurs to bone during the phase 3 shooting channel depends on how much kinetic energy remains in the bullet. If it is a very small amount, the bone will stop the bullet without fracturing.



ICRC

Figure 3.33

Severely comminuted fracture of the tibia.

Ricochet

As seen in the tissue simulants, a ricochet FMJ bullet creates a wound that resembles that of a soft-nosed, dum-dum bullet: early dissipation of energy through crush and stretch (Figure 3.34). This phenomenon can be significant for a soldier wearing body armour. If the armour is pierced by a bullet, the wound may be more severe than if he had not been wearing the protective device.

Please note:

People are not injured in the anatomic position. The situation of a muscle group may alter with the patient's position so that a track is obscured, lengthened or shortened.



R. Coupland / ICRC

Figure 3.34

The wound of a ricochet FMJ bullet resembles that of a dum-dum bullet. The head of the humerus has literally exploded.

Disruption of the bullet and secondary fragments

At impact velocities above 700 m/s, standard FMJ bullets tend to fragment in tissues at short shooting distances (< 30 – 100 m). Some of these fragmented pieces make their own track of crushed tissue. Tissue disruption from bullet fragmentation is then synergistic: the tissues are multiply perforated by the metallic fragments, thus weakening the tissue's cohesiveness, before being subjected to cavitation stretch. The injury is severe. The same phenomenon occurs with shotgun pellets; each pellet creates its own crush track.

Clinically, an X-ray showing a "shower of lead" from a fragmented bullet should alert the surgeon to the likelihood of a large transfer of kinetic energy to the tissues and consequent severe damage (Figures 3.35, 4.5 and 10.5).

Figure 3.35

Bullet fragmentation: a "shower of lead".



ICRC

Other secondary missiles are objects to which the bullet imparts sufficient motion through the transfer of kinetic energy. These may include foreign bodies such as a belt buckle, a small stone, the metallic contents of a pocket, or the contents of flak jackets – or autologous bodies including the teeth, dental fillings or dentures, and bone fragments (once an ICRC surgeon found a piece of a shattered mandible embedded in a patient's neck).

3.4.6 Sonic shock wave in tissues

A projectile in flight is accompanied by a series of waves propagated at the speed of sound (330 m/s in air). When the projectile strikes a person, this sonic wave is propagated throughout the body at the speed of sound in tissue (4 times the speed of sound in air).

This sonic shock wave may have high amplitude but is of very short duration, not enough to move or injure tissue. However, researchers have noted microscopic cell changes as well as stimulation of peripheral nerves, if the pressure generated reaches a certain threshold. The nerve stimulation occurs immediately, while the cell damage is apparent only after 6 hours. Occasional, short-lived neurapraxia appears to be the only clinically relevant damage.

3.4.7 Pressure wave in tissues and blood vessels

This pressure wave is part of the phenomenon of the temporary cavitation and should *not be confused* with the sonic shock wave. The outer boundary of the cavity consists of a "front" of compressed tissues, which creates a pressure wave at the limit of tissue compression. The wave develops fully only after the cavitation and decreases with distance. It is measured in milliseconds (1,000 times longer than the shock wave). The pressure wave can thus disrupt capillaries or provoke their thrombosis, rupture a full bowel or the liver, and cause retinal detachment and fractures, at a distance from the cavity.

movements throughout history, in which the body was considered sacred and a temple of the divine and in which sexuality was viewed as intrinsically sacred.

It may be said that all esoteric systems, in their origins, have called on humankind to practice love and compassion and thereby to transcend ego and enter into a state of grace.

Adepts like Jesus who has inspired the Christian tradition, Mohammed in the Islamic tradition and the Gautama in the Buddhist tradition may be seen as great masters. They showed people ways and practices of self-transformation through the practice of love and compassion. By assuming responsibility for themselves, they could attain inner freedom and bliss and transcend themselves.

In the Taoist view, the problem with religion and philosophy is not in the practice, but in the beliefs which often serve to divide rather than unite, inside the person and outside.

Unity of Light and Dark

In the Taoist perspective, there is no sin, as light and dark are two poles of the same indivisible reality. Thus, attempts to eradicate the dark, so that light will prevail, are bound to fail and tend to lead to conflict and violence. Attempts to conquer good at the expense of evil (for example, the Crusades) are bound to generate more violence. And battles to secure good over evil will create more problems than they solve. In the Taoist view there should be neither winners nor losers.



Fig. 9.2 *Light and Dark of the Tai Chi Symbol are connecting.*

Additionally, blood vessels contained in tissues are squeezed and emptied suddenly with tissue compression. This creates a pressure wave in the column of blood that is propagated away from the site of cavitation. The clinical result of this pressure wave along the course of a blood vessel can be thrombosis or dissection of the intima or muscularis.

3.4.8 Fragment wounds

Their non-aerodynamic shape means that fragments rapidly lose speed in air. If initial velocities are reported to be up to 2,000 m/s, the impact velocity in survivors is usually much lower. If the person is very close to the exploding device, the penetration is deep. If very far away, the casualty is only "peppered" superficially with multiple fragments.

Fragments do not tumble in the tissues, as was demonstrated in the tissue simulants. Thus, most tissue damage is due to crush. At the end of the trajectory, the sharp edges of an irregular fragment will cut tissues. By contrast, a bullet tends to push aside tissues at the end of its track. The wound profile resembles a *cone of tissue destruction*, with the largest diameter at the entry since most energy is dissipated at the surface. The diameter of the entry wound can be anywhere between 2 and 10 times the calibre of the fragment, depending on the impact velocity, mass and shape (Figures 3.36.1 – 3.36.3).

Large, slow fragments penetrate and crush tissues more; small, fast ones result in more stretch. This means that a large and slow fragment tends to cause the same type of wound whatever the tissues, while the wounds of small and fast fragments vary according to tissue elasticity. Nonetheless, in all fragment wounds the extent of tissue damage is always larger than the fragment.



B. Kneubuehl

Figure 3.36.1

Soap block demonstration of fragment injury.



R. Coupland / ICRC



R. Coupland / ICRC

Figures 3.36.2 and 3.36.3

Fragment wound with entry larger than exit.

Wound channel: pathological description

The sharp and irregular surfaces of fragments carry pieces of skin and clothing material into the wounds. As with gunshot wounds, fragment wounds show different zones of tissue injury. The cavity contains necrotic tissues surrounded by a zone of muscle fibre fragmentation with haemorrhage both within and between fibres, further surrounded by a region of acute inflammatory changes and oedema.

The uneven distribution of tissue damage in the concussion and contusion zones has been described as "jumping" or a "mosaic".[10] This is probably because energy has been transferred both along (crush effect) and across (shear and stretch effect) muscle fibres.

---

[10] Wang ZG, Tang CG, Chen XY, Shi TZ. Early pathomorphologic characteristics of the wound track caused by fragments. *J Trauma* 1988; **28 (1Suppl.)**: S89 – S95.

3.5 Wound dynamics and the patient

The wound has a life history, from injury to complete healing. As we have seen, tissue damage depends on a number of physical factors. However, the physical effects of energy transfer do not tell us all the pathological and physiological consequences of the act of wounding.

The tissues in and around the wound undergo reversible and irreversible pathological changes, as well as inflammatory reactions. It can be extremely difficult to diagnose injured tissue that will heal from that which is nonviable and will not heal (see Chapter 10).

Total kinetic energy is the *potential* to cause damage; transferred kinetic energy is the *capacity* to cause damage. Actual tissue damage depends on the *efficiency* of this energy transfer.

The most valuable information gained from this discussion is that small missiles may cause small and minor wounds, or large and serious wounds; and a small entry wound can be associated with large internal damage. Nothing can replace a good clinical examination of the patient and the wound. The extent of the crush and stretch is well represented by the grades of the Red Cross Wound Score (see Chapter 4).

The injurious effects on the patient, however, involve even more than the local pathology. As with all trauma and many diseases, the physiological and psychological state of the victim must be taken into consideration as well. Fit young military personnel, well-trained for their role in warfare and mentally prepared for being wounded, and wounding and killing others, are not the same as civilians. Psychological status cannot be calculated by ballistics. Only these factors can explain the many anecdotes of a person being shot – even several times – and yet continuing to advance or fight in combat.

Chapter 4

RED CROSS WOUND SCORE AND CLASSIFICATION SYSTEM

4. RED CROSS WOUND SCORE AND CLASSIFICATION SYSTEM

4.1 Applications of the RCWS and classification system 83
4.1.1 Assessment of and communication about war wounds in a standardized scheme 83
4.1.2 Establishing a scientific approach to war surgery 83
4.1.3 Surgical and hospital audit 83
4.1.4 Wound information from the field 83

4.2 Principles of the Red Cross Wound Score 84
4.2.1 Examples 86
4.2.2 Notes on wound scoring 87

4.3 Grading and typing of wounds 88
4.3.1 Wound Grade according to amount of tissue damage 88
4.3.2 Typing wounds according to the injured tissues 88

4.4 Wound classification 88

4.5 Clinical examples 89

4.6 Conclusions 91

4.1 Applications of the RCWS and classification system

Surgeons from civilian practice usually have no previous experience of managing war wounds. Even experienced surgeons often do not find it possible to tell the true extent of tissue damage. As noted in Chapter 3, ballistics studies show that there is not a uniform pattern or degree of wounding. Preparation for war surgery involves an understanding of the translation of the kinetic energy of a wounding projectile into tissue damage, i.e. the actual wounds that the surgeon must deal with.

The severity of such wounds depends on the degree of tissue damage and the structure(s) that may have been injured: thus, the clinical significance of a wound depends on its size and site. The Red Cross Wound Score (RCWS) and classification system[1] is based on the features of the wound itself, and not on the weaponry or the presumed velocity or kinetic energy of the missile.

Any wound classification system will aid the surgeon if it helps to assess the severity of the injury, influences surgical management, predicts outcome, and provides for an accurate database that can be used in comparative studies. The RCWS goes a fair way to fulfilling these criteria.

4.1.1 Assessment of and communication about war wounds in a standardized scheme

The Wound Score is a useful clinical tool to communicate the severity of the wound to staff and colleagues without having to remove the dressings. It is also an element to take into consideration for the purposes of triage.

4.1.2 Establishing a scientific approach to war surgery

The RCWS permits comparison of treatments and prognoses of similar wounds. An analogy can be made with the TNM (tumour, node, metastasis) staging of different cancers, allowing comparison of treatment regimes for a similar pathology. In the case of a gunshot wound to the thigh, treatment and prognosis will differ according to the amount of tissue damage, degree of bone comminution and whether there is injury to the femoral vessels. Other wound scoring systems are primarily devised for blunt trauma. The presence of a penetrating wound in these systems often indicates a “serious” wound, with little further nuance.

4.1.3 Surgical and hospital audit

Wound Scores can be used to evaluate quality of care when combined with information on length of hospital stay, number of operations performed per patient or units of blood used, morbidity and mortality. An example relating to the adequacy of primary wound surgery is the number and cause of deaths associated with non-vital wounds, or the number of operations performed per patient for each Wound Grade.

4.1.4 Wound information from the field

ICRC surgical teams treat thousands of war-wounded every year. Analysis of a larger number of scored wounds will eventually clarify the relationship between experimental laboratory wound ballistics and the clinical management of war wounds. Worthy of note is the fact that information gained in the field served as a scientific basis for the campaign to ban anti-personnel landmines, thus promoting new standards in international humanitarian law.

---

[1] This chapter is largely based on the brochure *The Red Cross Wound Classification, Revised Edition*, by Dr R. M. Coupland. The ICRC Master Surgeons Workshop held in Geneva in 2002 revised the original Wound Score (see Introduction).

4.2 Principles of the Red Cross Wound Score

Wounds are given a six-figure Score according to several parameters. The Scores can then be translated into a classification system:

- grading of the wound according to the severity of tissue injury and
- typing of the wound according to the tissue structures injured.

The RCWS is intended for quick and easy use in the field, its simplicity especially useful under conditions of stress. It is a simple clinical system that requires no extra equipment or sophisticated procedures. The time required for scoring wounds can be measured in seconds.

E	entry wound in centimetres	
X	exit wound in centimetres (X = 0 if no exit wound)	
C	cavity	Can the cavity of the wound take two fingers before surgical excision?
		C 0 = no
		C 1 = yes
F	fracture	Are any bones fractured?
		F 0 = No fracture
		F 1 = Simple fracture, hole or insignificant comminution
		F 2 = Clinically significant comminution
V	vital structure	Are dura, pleura, peritoneum, or major peripheral vessels injured?
		V 0 = no vital structure injured
		V N = (neurological) penetration of the dura of the brain or spinal cord
		V T = (thorax or trachea) penetration of the pleura or of the larynx/ trachea in the neck
		V A = (abdomen) penetration of the peritoneum
		V H = (haemorrhage) injury to a major peripheral blood vessel down to brachial or popliteal arteries, or carotid artery in the neck
M	metallic body	Are bullets or fragments visible on X-ray?
		M 0 = no
		M 1 = yes, one metallic body
		M 2 = yes, multiple metallic bodies

Table 4.1 Parameters of Wound Score.

E (entry)	centimetres
X (exit)	centimetres
C (cavity)	C 0, C 1
F (fracture)	F 0, F 1, F 2
V (vital structure)	V 0, VN, VT, VA, VH
M (metallic bodies)	M 0, M 1, M 2

Table 4.2 Total scheme of Wound Score.



R. Coupland / ICRC

Figure 4.1

The width of two fingers is approximately the length of a military rifle bullet.



F. Herkert / ICRC

Figure 4.2.1

Gunshot wound: F1 fracture of the ulna.



R. Coupland / ICRC

Figure 4.2.2

Gunshot wound: F2 fracture of the femur.



R. Coupland / ICRC

Figure 4.2.3

Gunshot wound: F 1 fracture (clinically insignificant comminution) of the fibula.

Wounds are scored on the patient's admission form after operation or after initial examination if there is no surgery.

ICRC EXPERIENCE

An ICRC admission sheet with Wound Score recorded.



ICRC

NAME: A. Victim
COMING FROM: THE BORDER.
NUMBER: 16838
[✓ MALE] FEMALE AGE: 40

DATE: 4.3.90 TIME: 15.00
TIME SINCE INJURY: 4 hours
GENERAL CONDITION: OK
PULSE: 90 BP: 110 RESP: 25 TEMP: N
ANTIBIOTICS: Penicillin 5 mega
ATS/ANATOXAL: ✓

[✓ GSW] MI: SHELL: BOMB: BURNS: OTHER:

◆ MEDICAL ASSESSMENT

GSW (L) Thigh
Femur
Pulse & Sensation – normal

MEDICAL ◆ ORDERS:

Hb: 12.5
Hct:
X match:

IV fluids: 1L N. Saline
NPO from: 8.00 am.

TRIAGE: I Serious [✓ II Secondary] III Superficial IV Supportive

◆ OPERATION NOTE

4.3.90

Excision GSW (L) thigh
Large wound
Dead muscle & bone fragments excised

– Saline wash
– Dry Bulky dressing
Traction pin.

◆ POST OPERATIVE INSTRUCTIONS

Antibiotics: Penicillin 5 mega qid
to stop: 48 hours
Position Physio drains traction: 4 kg traction
By mouth: [✓ Food Fluids] Nil
Other:
Next in OT: 9.3.90 JPC.

◆ PENETRATING WOUND SCORE ◆

E	1	X	8	C	1	F	2	V	0	M	2
E	☐	X	☐	C	☐	F	☐	V	☐	M	☐

◆ OTHER INFORMATION

4.2.1 Examples

The following two sketches (Figures 4.3 and 4.4) present various wounds due to weapons, and their assessment according to the ICRC's wound scoring system.



ICRC

Figure 4.3

Example of Wound Scores.

a. Simple bullet track.
b. Track produced by bullet with temporary cavitation at exit.
c. Simple track with involvement of a vital structure (artery).
d. Low-energy transfer wound with simple fracture.
e. High-energy transfer wound by fragment with comminuted fracture.

	E	X	C	F	V	M
Wound (a)	1 ?	2	0	0	0	0
Wound (b)	1	4	1	0	0	0
Wound (c)	1	0	0	0	H	1
Wound (d)	1	0	0	1	0	1
Wound (e)	6	0	1	2	0	1



ICRC

Figure 4.4

Further example of Wound Scores.

a. Through-and-through bullet wound of soft tissue with central cavitation.
b. Through-and-through bullet wound with central cavitation and comminuted fracture.
c. High-energy transfer bullet wound with cavitation and comminuted fracture.

	E	X	C	F	V	M
Wound (a)	1 ?	1	1	0	0	0
Wound (b)	1 ?	1	1	2	0	0
Wound (c)	1	6	1	2	0	2

Thus, balance between opposite forces and energies, as expressions of Yin and Yang, the positive and the negative, is essential to Taoist perspective, as expressed in the *Tao Te Ching*, attributed to the great Taoist Master of self-transformation, Lao Tzu.

From a Taoist perspective, balance is enhanced by entering into alignment with the universe, when one actualizes the universe within oneself and so is empowered and realizes oneself. This state has also been called a state of Selfhood, as one has returned to one's original Self. This process is also called "returning to one's origins". This means that one has overcome the contradictions and imbalances in oneself, so that Yin and Yang enter into balance and harmonize. The Taoist texts speak of becoming the "Undivided Being". Lao Tzu uses the metaphor of the unhewn log (p'u). It manifests a state of being in which when has returned to the original state of spontaneity, in the old Taoist texts called " Tzu-jan) which can be observed in babies and small children. This reminds us of the saying of Jesus," if you do not become as children, you cannot enter the Kingdom of Heaven".

Thus the Taoist view on harmony does not carry moral overtones, as it refers to a state of being which is intrinsic in the body. This state of being of the body as a microcosmos lies in the balance within and between its major organs, through which our body resonates with the energies and forces of the universe.

In the Taoist perception, there are no heaven and hell outside, above or below us. They are seen as states of being of our bodies and our inner selves and the way we relate to the universe, ourselves and each other. As such they reflect states of balance and imbalance between the positive and the negative. In this view, human beings are responsible for their own state of being, the quality of which depends on their state of self-awareness as the key to self-transformation.

This view is reflected in many ancient spiritual traditions and cultures which suggest that it is wiser to keep the devil as a friend than try to combat him and do away with him.

This liberating view, which frees us from self-condemnation with its tendency to obscure the positive within the negative and its transformational force, is the basis for the Fusion Practices.

4.2.2 Notes on wound scoring

1. When it is impossible to differentiate between the entry and the exit wounds, put a (?) between the E and X Scores.
2. With multiple wounds, only the two most serious are scored.
3. If a wound cannot be scored (unclassifiable), U/C is written on the Score. This applies to a minority of wounds.
4. When one missile causes two separate wounds (e.g. through the arm and into the chest), the 2 separate Scores are joined by a bracket.
5. Include penetrating wounds only, not superficial tangential skin wounds; e.g. skin wound 20 cm long and 1 cm wide but without penetration deep to the fascia.
6. Estimation of the cavity: the width of two fingers is approximately the length of a bullet from a military assault rifle (Figure 4.1). If the permanent cavity of a wound admits two fingers before surgical excision, then something other than crush by a bullet travelling sidelong must have taken place, i.e. stretch and laceration by cavitation. A C1 wound is likely to present significant tissue damage whatever the cause.
7. Fracture severity: it is inevitable that some wounds fall between F1 and F2, but for simplicity this is not accurately defined here. A further refinement is given in Volume 2. An example of a clinically insignificant comminution (F1) is a wound with a comminuted fibula but with an intact tibia (Figure 4.2.3).
8. A vital injury implies a more dangerous wound involving a surgical task in addition to simple wound management (e.g. craniotomy, pleural drainage or thoracotomy, laparotomy). VH includes the popliteal and brachial vessels but not those more distal. The outcome of injuries to the head, thorax or abdomen, or causing massive peripheral haemorrhage, is only partly determined by the clinical size of the wounds as determined by the RCWS (see below).
9. Metallic fragments: note the difference between an intact bullet (M1) and a fragmented bullet (M2), as shown in Figure 4.5. If the full metal jacket of a bullet has been disrupted and the lead interior has leaked out as fragments, this indicates a severe stress on the bullet and a large transfer of kinetic energy to the tissues (Figures 3.35 and 10.5).

   Note also the difference between multiple metallic fragments from a grenade or shell (Figure 4.6) – which are common and do not necessarily represent a large transfer of kinetic energy – and a disrupted and fragmented bullet, which does. If there are numerous metallic fragments, do not count them; only mark M = 2.
10. If X-rays are not available the RCWS is still valid. The F Score is judged clinically and the M parameter omitted, or included if fragments are found during surgical excision. X-rays should not be performed just to fill in the M and F Scores.
11. Traumatic amputation of limb (Figure 4.7): this injury is often seen with anti-personnel blast mines. The open end of the amputated limb equals a combined entry-exit, whose diameter represents the sum of E+X. It is equivalent to a cavity (C = 1), while the vaporized missing part of the limb qualifies as a severe fracture (F = 2). The level of traumatic amputation (above or below the knee or elbow) will determine if the Vital structure Score is 0 or H.


ICRC

Figure 4.5

Disrupted and fragmented bullet: M2.


ICRC

Figure 4.6

Multiple shell fragments: M2.


K. Barrand / ICRC

Figure 4.7

Traumatic amputation of the forearm.

E	X	C	F	V	M
20	?	1	2	0	0

4.3 Grading and typing of wounds

Once scored, the wound can be *graded* according to severity (E, X, C and F), and *typed* according to tissue type (F and V).

4.3.1 Wound Grade according to amount of tissue damage

The wound should be *graded* according to severity.

Grade 1
E + X is less than 10 cm with Scores C 0 and F 0 or F 1.
(Low energy transfer.)

Grade 2
E + X is less than 10 cm with Scores C 1 or F 2.
(High energy transfer.)

Grade 3

E + X is 10 cm or more, with C 1 or F 2.
(Massive energy transfer.)

These Grades represent the outcome of a simple clinical assessment that corresponds to the effective transfer of kinetic energy of projectiles to body tissues. Large wounds are more serious and require greater resources; this is particularly true of wounds to the limbs.

4.3.2 Typing wounds according to the injured tissues

Once *scored*, the wound can be *typed* according to tissue structures.

Type ST
Soft-tissue wounds: F 0 and V 0.

Type F
Wounds with fractures: F1 or F 2, and V 0.

Type V
Vital wounds putting the patient's life at risk: F 0 and V = N, T, A or H.

Type VF
Wounds with fractures and involving vital structures putting life or limb at risk: F 1 or F 2 and V = N, T, A or H.

4.4 Wound classification

Combining Grades and Types gives rise to a classification system divided into 12 categories.

	Grade 1	Grade 2	Grade 3
Type ST	1 ST Small, simple wound	2 ST Medium soft-tissue wound	3 ST Large soft-tissue wound
Type F	1 F Simple fracture	2 F Important fracture	3 F Massive comminution
Type V	1 V Small wound threatening life	2 V Medium wound threatening life	3 V Large wound threatening life
Type VF	1 VF Small wound threatening limb and/or life	2 VF Important wound threatening life and/or limb	3 VF Large wound threatening life and/or limb

Table 4.3 Grade and tissue Type categories.

These categories help determine surgical management for a number of wounds, though by no means all (see Chapters 10 and 12).

Further refinement of the fracture type is possible, especially for assessing the extent of bone defect. This can be useful in a specialized study of war wounds with fractures (see Volume 2).

4.5 Clinical examples

Epidemiological studies from the ICRC surgical database of over 32,000 patients have shown that the Red Cross Wound Score gives excellent prognostic results for surgical workload and morbidity due to war wounds. As demonstrated in the statistical analysis in Chapter 5, the Wound Grade is highly relevant to the number of operations per patient. This is particularly the case for wounds to the extremities. Vital Wound Scores to the extremities (V = H) also give good measures for mortality and the amputation rate.

One of the avowed weaknesses of the Classification concerns the prognostic mortality of vital central wounds. It is in the anatomic nature of the brain, heart and great vessels that even a very small wound from a projectile with low kinetic energy can be lethal if a vital centre is injured. The RCWS does classify such wounds as "potentially" lethal; that is why, by definition, they are categorized as "vital" injuries. However, a Grade 1 wound can be just as lethal as a Grade 3 wound depending on what particular structure is hit: medulla oblongata or temporal cortex; lung parenchyma or ascending aorta.

What is certain is that for most Grade 3 wounds to the head, thorax and abdomen, pre-hospital mortality is bound to be high. Without autopsies of those killed in action (KIA), analysis can only be made of the relatively few "survivors" who reach hospital; for them, wound Grade is not significant with respect to mortality (Tables 4.4 – 4.6).

Thus, the outcome of injuries to the head, thorax and abdomen are not only, nor even mainly, determined by the clinical size of the wound as defined by the RCWS. The various factors affecting the mortality from vital wounds; e.g. for the abdomen, number of organs injured, degree of faecal contamination, intraoperative blood loss, delay in operative treatment, etc., will be discussed in Volume 2.

	Number	Deaths	% mortality
Grade 1	75	14	18.7
Grade 2	70	15	21.4
Grade 3	9	3	33.3

Table 4.4 Mortality from head and neck injuries (VN) : N = 154. (ICRC Kabul, 1990-92)

	Number	Deaths	% mortality
Grade 1	82	4	4.9
Grade 2	41	2	4.9
Grade 3	3	0	0

Table 4.5 Mortality from chest injuries (VT) : N = 126. (ICRC Kabul, 1990-92)

	Number	Deaths	% mortality
Grade 1	120	9	7.5
Grade 2	70	11	15.7
Grade 3	5	0	0

Table 4.6 Mortality from abdominal injuries (VA) : N = 195. (ICRC Kabul, 1990-92)

Nonetheless, as explained in Chapter 5, a distinction should be made in patient databases between superficial and penetrating wounds to the head, thorax and abdomen to allow for a better analysis of results of treatment. Using the RCWS enables this.



R. Coupland / ICRC

Figure 4.8.1

Two fragment wounds to the thigh. The surgeon is assessing the larger wound cavity.



R. Coupland / ICRC

Figure 4.8.2

Both wounds are Type ST. The smaller wound is Grade 1, and the larger Grade 2.



R. Coupland / ICRC

Figure 4.9.1

Through-and-through gunshot wound to the knee.



R. Coupland / ICRC

Figure 4.9.2

There is a small fracture above the lateral condyle.



R. Coupland / ICRC

Figure 4.9.3

The popliteal artery has been injured.



R. Coupland / ICRC

Figure 4.9.4

The wound is Type V(H)F, Grade 1.



R. Coupland / ICRC

Figure 4.10.1

Gunshot wound to the abdomen.



R. Coupland / ICRC

Figure 4.10.2

The bullet is lodged in the scrotum. There is a small fracture of the right pubic bone.



R. Coupland / ICRC

Figure 4.10.3

This is a Grade 2 wound, Type V(A)F.



R. Coupland / ICRC

Figure 4.11.1

A bullet has grazed the left buttock and then entered the right buttock at the anal cleft. The exit is located laterally.



R. Coupland / ICRC

Figure 4.11.2

This is a Grade 2, Type ST wound.



R. Coupland / ICRC

Figure 4.12.1

Fragment wound to the head with entry right parietal. Note the severe linear fractures.



R. Coupland / ICRC

Figure 4.12.2

The cone of tissue destruction extends to the occipital lobe. Grade 2, Type V(N)F.

4.6 Conclusions

The Red Cross Wound Score enables medical staff to translate war wounds into surgical lesions rather than weaponry phenomena. It refines the heterogeneity of wounds and helps define them according to their clinical significance, and it is a good indicator of tissue damage due to the transfer of kinetic energy in penetrating wounds.

The limitations of the scoring system are recognized; complete accuracy cannot be obtained. It should be emphasized that the RCWS is for rapid use under adverse conditions, including extreme stress, and uses no additional equipment or sophisticated technology. The simplicity and advantages of the RCWS outweigh any disadvantages that may occasionally be introduced by observer error. As with any classification system, the more experience gained in using the RCWS, the more accurate the results and the fewer the observer errors.

Chapter 5

THE EPIDEMIOLOGY OF THE VICTIMS OF WAR

5. THE EPIDEMIOLOGY OF THE VICTIMS OF WAR

5.1 Introduction: purpose and objectives 95
5.1.1 The reader and this manual 95

5.2 Public health effects of armed conflict 95
5.2.1 Historical perspective 95
5.2.2 The public heath effects of social disruption 96
5.2.3 The burden of war-wounded civilians 97
5.2.4 Methodology 98

5.3 Epidemiology for the war surgeon 98
5.3.1 Preparation of the surgeon 98
5.3.2 Preparation of the institution 99
5.3.3 Surgical audit: monitoring 99
5.3.4 The surgeon and IHL 100
5.3.5 The surgeon and the specialized literature 100

5.4 General questions of methodology 101
5.4.1 Large and small numbers 101
5.4.2 Problems of data collection 101
5.4.3 Important first questions: who is counting whom? 102
5.4.4 Some definitions: the wounded and the dead 103
5.4.5 Clinical and operational consequences and IHL 104

5.5 Aetiology of injury 104
5.5.1 Warfare scenarios 104
5.5.2 Definitions of weapon-systems: methodology 105
5.5.3 ICRC statistics 106

5.6 Anatomic distribution of wounds 106
5.6.1 Body exposure 106
5.6.2 Definitions and methodology 107
5.6.3 Historical results 108
5.6.4 ICRC results 108
5.6.5 Primary tissue injury 109

5.7 Fatal injuries 110
5.7.1 Site 110
5.7.2 Trimodal distribution of trauma mortality 111
5.7.3 Ratio of dead to survivors 113
5.7.4 Lethality of weapons 113
5.7.5 Conclusions of clinical relevance 114

5.8 The lethality of context: delay to treatment 114
5.8.1 Historical developments 114
5.8.2 Forward projection of resources 115
5.8.3 Urban warfare: hospitals on front lines 115
5.8.4 The paradox of early treatment: changing mortality ratios and rates 115

5.9 Hospital mortality 117
5.9.1 Historical considerations 117
5.9.2 Hospital mortality *versus* post-operative mortality 117
5.9.3 ICRC hospital mortality 117

5.10 ICRC statistical analysis of hospital workload 118
5.10.1 Surgical audit: methodology 118
5.10.2 Number of operations per patient: all patients 118
5.10.3 Number of operations according to delay in evacuation 119
5.10.4 Number of operations according to Wound Grade 119
5.10.5 Number of operations according to Wound Grade and delay in evacuation 120
5.10.6 Number of operations according to weapon 120

5.11 Conclusions: lessons to be gained from a study of epidemiology 121
5.11.1 Setting up a surgical database for the war-wounded 122

ANNEX 5. A ICRC surgical database 123

ANNEX 5. B Setting up a surgical database for the war-wounded 125

5.1 Introduction: purpose and objectives

Epidemiological studies are standard practice in medicine. Doctors need to understand the characteristics of their patient population and the relationships between particular circumstances and the outcome of treatment. These elements help to establish the high risk factors.

As regards the victims of war, the total effects of conflict must be analysed, the impact on civilian populations as well as the military, the direct effects of war trauma and the indirect public health consequences. These help the ICRC and other organizations determine their response in terms of assistance (see Chapter 2).

5.1.1 The reader and this manual

Most readers of this manual will be civilian surgeons who are unacquainted with the practice of war surgery and its literature. Even among military surgeons many may have only a superficial acquaintance with these topics. This chapter on the epidemiology of victims of war presents a certain approach to the understanding of the many factors involved in patient care and outcome.

First the public health repercussions of armed conflict will be dealt with briefly, then the purely surgical aspects will be addressed in more detail. Questions of general methodology and definitions will begin the surgical study, and will be followed by a presentation of historical and ICRC experience and results. Relevant clinical conclusions will be emphasized throughout, as will recurring problems of methodology.

For the purpose of this discussion the authors refer directly only to the ICRC's experience in armed conflict and the importance of epidemiological studies in determining ICRC surgical activities. In addition, reference is made to the statistics in standard and well-accepted scholarly books and journal articles for historical results that have come to influence clinical practice (see Selected bibliography).

5.2 Public health effects of armed conflict

5.2.1 Historical perspective

It is commonly said that contemporary warfare causes more civilian victims than military, and that the public health effects are greater than those caused by trauma. In all major conflicts over the last one hundred years, with few exceptions (World War I), civilians have become a direct target and accounted for one-half to two-thirds of the casualties.

> "Throughout history there have been many small local wars, often involving wholesale starvation and occasionally the elimination of whole populations or tribes."
>
> G.W. Odling-Smee[1]

The heavy civilian toll in contemporary conflicts is therefore not new. Nevertheless, in certain recent conflicts – whether revolutionary wars of national liberation, civil wars, territorial and border disputes, or peasant uprisings – the destabilization of political, social, and economic infrastructures, the destruction of cultural symbols and institutions, and the psychological terrorizing of civilians have become explicit political and military goals. A number of reports have indicated that the indirect effects of social disruption have caused two to fifteen times more civilian deaths than war wounds have, and, in some cases, civilians may account for up to 90 % of the victims.

---

[1] Odling-Smee GW. Ibo civilian casualties in the Nigerian civil war. *BMJ* 1970; **2**: 592 – 596.

> "Today's armed conflicts are essentially wars on public health."
>
> Rémi Russbach, former Chief Medical Officer at the ICRC

5.2.2 The public heath effects of social disruption

Social disruption includes population displacement – either internal or refugee – pauperization, the breakdown of nutrition and sanitary conditions, the lack of safe drinking water, and the disorganization of medical systems (Table 5.1).

Direct effects	Indirect effects
Death	Economic pressures and disruption
Disability	Reduced food production and distribution
	Family disruption (orphans, abandoned children)
Destruction of health services	Refugees
	Psychological stress
Disruption of health programmes	Effects on housing, water supply, and sewage disposal
Psychological stress	Economic pressures on those caring for the war-disabled
Illness	Environmental (landmines, deforestation)

Table 5.1 Effects of political violence on health and health systems.[2]


Concept of imbalance between victims' needs and available services
Essential services
Victims' needs

Increase in needs associated with:
- increase in population
- increase in morbidity due to sanitary conditions

Deterioration in effectiveness of services:
- insufficient means
- abandonment of facilities by personnel
- disrupted organization

Appearance of new needs, e.g. treatment of war wounds

Destruction of medical facilities

P. Perrin / ICRC

Figure 5.1

Victims' needs and available services during armed conflict.[3]

Pathologies and the pathology of the health system

Complex emergencies during armed conflict in poor countries tend to cause death by endemic communicable disease and malnutrition. In more developed countries, increased mortality rates due to trauma and chronic disease dominate. The lack of access to care, either because of poverty, the disorganization of the medical system, or for reasons of security, aggravates the problems.

To pre-conflict poverty and fragile health services are added the problems of the collapse of medical supply and distribution, the targeting of hospitals and clinics in violation of medical neutrality, and the neglect or abandonment of preventive health programmes. In addition, health professionals are often amongst the first people to flee a conflict zone. Having to provide for war trauma also means a greater investment in curative services to the disadvantage of the preventive. The entire health system becomes organized around the conflict and there is an imbalance between the needs of victims and the available public health services (Figure 5.1).

Moreover, all too often, increased military spending in a country at war is to the detriment of social and health investments. Another recent development is the creation of a war economy controlled by criminalized military networks. The extraction of diamonds and other precious stones, oil, timber, and various minerals, the trafficking of narcotics, and sheer banditry, take a further and severe social toll.

A public health approach shows the full range of the humanitarian consequences of the use of anti-personnel landmines, especially during the post-conflict period. In addition to death and disability, there are the long-term socio-economic effects of disrupted economic activity through the loss of farmland, livestock, water resources, and industrial capacity because of the presence of landmines.

---

[2] Zwi A, Ugalde A. Towards an epidemiology of political violence in the third world. *Soc Sci Med* 1989: **28**: 633 – 642. Cited in Lautze S, et al., 2004.

[3] From Perrin P. *War and Public Health: A Handbook*. Geneva: ICRC; 1996.

Life as an Invitation to Learning

The Chinese character for crisis stands for both a negative occurrence as well as for opportunity and reflects the Taoist view on the unity of the positive and negative. In this perspective, whatever happens in life is to be seen as an invitation for learning and an opportunity for awakening. Theoretically speaking, problems are not problems, but opportunities for self-transformation, since the negative contains the positive, in the same way as the positive contains the negative, like the Yin is in the Yang like the Yang in the Yin. What may be seen and experienced as negative, carries within it the seeds of the positive, just as the light exists within the dark. In this light, all problems of life may be seen as energy potential, which can actually be a learning process.

This is a key premise in the Fusion Practices, and it helps to overcome the duality which we tend to construe, as a result of attachments to our negative experiences and emotions and therefore keep ourselves from entering into balance.

Taoists say that learning is enhanced if the organs feel at ease and find themselves in a state of well being. When a state of disease arises – which in Chinese medicine, of Taoist origin, is seen as a symptom of the breakdown or weakening of the free flow of energy – learning becomes more difficult.

It also points to an attitude which gives primacy to the need to reflect on one's own attitude and perception in resolving problems and to look inward to see in what way one has contributed to the problem and how one can contribute to its solution by changing one's own attitude, perception and way of life.

Thus from a Taoist perspective, problems are not seen as obstacles or difficulties but as opportunities to learn and as learning material.

In this connection, it is interesting to note that the word disaster, common to many European languages, has its etymological root in the Latin substantive "astrum" of which it is a negation by the prefix "dis". This suggests that originally the word had the connotation that if and when one lost touch and became alienated from the stars (as representing our origins), one was in for trouble; imbalances would arise.

Landmines and other UXO (unexploded ordnance) are not the only weapons left over after war. Demobilized combatants with guns are not often successfully reintegrated into social and economic life: criminal violence replaces political violence; peace combined with high criminality offers little respite from war. And the social and economic costs continue to cast a shadow over everyday life.

In addition, one must count the social costs of deliberate physical, psychological, and sexual abuse as methods of warfare. Torture and rape have profound and long-term consequences.

Public health effects on the military

Even among classical armies of industrialized countries, disease caused more deaths than combat until World War II. Mortality does not tell the whole story, however. Serious disease continues to affect modern armies, still accounting for high rates of non-availability of personnel for military duty. Of course, certain natural environments (jungle, high mountains) increase the incidence of non-battle pathology.

5.2.3 The burden of war-wounded civilians

Although trauma may account for only a small number of all war-related deaths in a given civilian population, the relative proportions of mortality and morbidity due to disease and trauma vary over time and between different war zones; refugee camps are different again.

In some conflicts, the burden of war trauma is greater than the public health consequences. This was the case in the wars in the former Yugoslavia (1991 – 99) in Lebanon (1975 – 90), and Rwanda (1994), among others. One must also take into consideration the relatively small population of certain countries; a limited number of deaths may represent a proportionately high death toll.

In some conflicts, the burden of the war-wounded is greater than the consequences on public health.

The type of combat may place civilians at greater risk and war casualties may overwhelm civilian medical services, even in situations where the public health effects are greater than the direct effects of trauma (Biafra 1967 – 70, Uganda 1987, Democratic Republic of the Congo since 1997 to the time of writing).

Mortality data, however, do not reflect the extent and severity of war injuries. Morbidity and disability rates due to injuries are testimony to the long-term socio-economic burdens.

Demographics of the victims

Historical military casualty statistics concern young, fit and healthy men. In the past, women were not close to combat in most classical armies; more recently, however, various revolutionary guerrilla groups have had female combatants.

When a civilian population finds itself in the midst of war, the demographic profile of casualties is closer to its population pyramid. This has clinical consequences for the treatment of endemic diseases and chronic pathologies among the wounded.

J-P. Di Silvestro / ICRC

Figure 5.2

The number of wounded and dead by direct trauma may at times far exceed the effects on public health.

5.2.4 Methodology

Public health monitoring and data collection are notoriously difficult during the chaotic and overwhelming conditions of complex emergencies. Missing and displaced persons, constraints of time, lack of access to populations, and dangerous security situations, all create formidable problems for a limited number of qualified personnel to conduct proper studies. Furthermore, the distinction between civilian and military during a civil war is not always obvious.

The ratio of military to civilian wounded and sick may be very sensitive political and military information, easily exploited for propaganda purposes by the various antagonists. In an attempt to prevent this, should ICRC delegates determine that civilians are being expressly targeted by combatants, the organization undertakes specific *démarches* regarding the conduct of hostilities with the authorities concerned through its traditional confidential procedures.

Many authors have recently written about the public health effects of armed conflict and complex emergencies. The ICRC first published its standard *War and Public Health* in 1996 and, together with the World Health Organization and a number of universities around the world, it organizes a dozen H.E.L.P.[4] courses on the management of humanitarian aid every year.

5.3 Epidemiology for the war surgeon

What should one look for in a study of epidemiology? What information will help the individual surgeon managing war wounds for the first time? What needs to be taken into consideration to set up an efficient system for the care of the war-wounded? Is it possible to determine the "normal" levels of morbidity and mortality during armed conflict?

To respond adequately to the challenge requires preparation, on the part of the individual surgeon as well as the institution's, and a system for monitoring the results of patient management.

5.3.1 Preparation of the surgeon

The surgeon facing war-wounded casualties for the first time will ask a number of questions: "What wounds should I expect? Which injuries kill? What will the surgical workload be like?"

In many conflicts, civilian surgeons, albeit without previous military experience, become heavily involved in the management of the war-wounded. Yet, epidemiological studies clearly show that combat injuries differ from those in civilian practice: different aetiology and pathology; multiple-cause injuries; delayed access to care and austere working conditions requiring different philosophies of treatment.

Epidemiological studies show that the management of the war-wounded is different from civilian trauma. The war surgeon must develop a new clinical mindset.

Various indices have been devised to define injury patterns, which differ according to the type of conflict and the nature of the weapons used: the lethality of wounding agents; the anatomic distribution of wounds; delay to treatment; and pre-hospital and post-operative mortality are among the most important. Knowledge of these helps determine the high-risk factors affecting the outcome of surgical treatment and what set of specialist skills are needed: orthopaedic surgery, vascular, visceral, etc.

---

[4] H.E.L.P.: Health Emergencies in Large Populations. The reader is directed to the publications in the Selected bibliography for further study.

These patterns also have an impact on hospital activities and surgical workload and influence the standardization of protocols for patient management.

5.3.2 Preparation of the institution

The institution involved – military sanitary services, public health ministry, ICRC or any other humanitarian agency – must also be prepared.

The standardization of protocols and knowledge of the workload permits the establishment of ready-made kits of equipment, medicines and supplies that are easily deployed in an emergency situation as a rapid response to well-known needs. This facilitates the setting up of a surgical hospital to treat the victims of war.[5]

Preparation also implies choosing the correct profile of surgeon required, and training him or her to understand the context, the pathology, and the functioning of the institution in which they will be working, as well as the prevailing clinical protocols.

Knowing what kind of patient comes through the hospital door helps in planning a response: allocation of medical resources and personnel and the training of surgeons.

5.3.3 Surgical audit: monitoring

Monitoring of the outcome of patient management in a context of of armed conflict involves a surgical audit using an epidemiological approach: demographics, types of wounds, anatomic distribution, mechanism of injury, time since injury, post-operative mortality, number of operations and blood transfusions per patient, and morbidity, etc. There are several reasons for this.

- The adequacy of surgical expertise is important: the "fog of war" and the confusion and stress of a situation of armed conflict are not an excuse for bad surgery. Professional standards must be maintained, even when resources are limited.
- The adequacy of the clinical protocols in use must be put to the test: changes must be made in response to poor or unexpected outcomes. Many surgeons will be seeing war pathology for the first time, under conditions that do not resemble their routine work circumstances. At times, a strict and rigid application of protocols is required; on other occasions, there will be a need for improvisation and adaptation.
- The adequacy of the chain of casualty care must also be put to the test: hospital as well as pre-hospital data helps to assess the efficiency of first-aid measures in the field and that of the evacuation system. Surgeons, civilian or military, may be involved in training or helping set up pre-hospital programmes so that the injured reach them in better condition and in a timely fashion, which makes their surgery easier and ensures a better outcome for the patient.
- The role of surgeons in the development and application of international humanitarian law.

---

[5] The *Emergency Items Catalogue of the International Movement of the Red Cross and Red Crescent* has a listing of such kits for the establishment of a surgical field hospital and for the treatment of 100 war-wounded hospitalized and operated on.

5.3.4 The surgeon and IHL

Surgeons working for the ICRC believe that health professionals have a duty to gather data "to prevent and not just to treat" with regard to the law and norms of behaviour in the conduct of hostilities. They are not alone in this belief.

Health professionals were instrumental in gathering the epidemiological data from clinical studies to make the humanitarian argument for the banning of blinding laser weapons and anti-personnel landmines.[6]

In the field, ICRC delegations in areas of armed conflict monitor the compliance of belligerents with IHL. This is an essential element of the mandate of the ICRC to protect and assist the victims of armed conflict and promote respect for the law of war. Epidemiological studies, in both hospital and pre-hospital settings, can help in determining certain abuses of IHL. For example, mortality statistics can help elucidate the occurrence of executions of prisoners of war being passed off as killed in combat. The ICRC then undertakes a series of confidential *démarches* with the offending party in order to promote observance of humanitarian norms.

Other actors may do likewise, in compliance with their humanitarian responsibilities.[7] The ICRC warns, nonetheless, against the possibility of exploitation and manipulation of statistical epidemiological studies for political purposes.

5.3.5 The surgeon and the specialized literature

"Statistics can be made to say whatever you want them to say" is a well-worn cliché. It is therefore important for the surgeon reading the vast literature on war surgery to understand what is being said, what the shortcomings are, and what some of the traps and pitfalls are.

Most of the war surgery literature consists of large retrospective studies written by military surgeons of industrialized countries; some of the exceptions are included in the Selected bibliography at the end of this volume. Most surgeons are not well trained in epidemiology or statistical methods, and civilian surgeons are usually not knowledgeable about military terminology. Thus, the surgeon facing the new experience of dealing with the war-wounded who wishes to read up on the topic will often find a bewildering vocabulary and methodology.

Differences

Added to the differences between war and civilian trauma are the disparities between the experience of ICRC interventions (and other humanitarian agencies) and ministry of public health structures on the one hand, and classical military medical services on the other. The rest of this chapter deals with some of these differences and disparities.

---

[6] Respectively, Protocol on Blinding Laser Weapons 1995 (Protocol IV to the Convention on Prohibitions or Restrictions on the Use of Certain Conventional Weapons Which May be Deemed to be Excessively Injurious or to Have Indiscriminate Effects,1980), and the Convention on the Prohibition of the Use, Stockpiling, Production and Transfer of Anti-Personnel Mines and on their Destruction, 1997, known as the Ottawa Convention.

[7] Burnham G, Lafta R, Doocy S, Roberts L. Mortality after the 2003 invasion of Iraq: a cross-sectional cluster sample survey. *Lancet* 2006; **368**: 1421 – 1429.; Dudley HAF, Knight RJ, McNeur JC, Rosengarten DS. Civilian battle casualties in South Vietnam. *Br J Surg* 1968; **55**: 332 – 340.

5.4 General questions of methodology

There are a number of problems and difficulties relating to how epidemiological studies have been conducted. The surgeon reading the literature should be aware of them.

5.4.1 Large and small numbers

First it must be clear which phenomenon is being studied. Comparisons of data between a single battle and longer wars may not be valid; a small cohort may not be representative. Most clinical protocols take as a basis large numbers in big wars. On the other hard, the individual surgeon will face individual casualties from particular battles. Thus, the experience with small cohorts may help prepare the surgeon to face a novel situation or specific injuries.

5.4.2 Problems of data collection

Trauma registries are notoriously difficult to maintain during war. Fatigue and lack of time, a shortage of trained staff, and the personal danger that medical staff must often confront complicate the keeping of statistics. The administrative personnel and time and effort required to keep up full documentation and archives can appear to be a luxury when faced with the stress of caring for battle casualties. In an article on American casualties during the war in Viet Nam, based on data obtained from a statistical record filled out by physicians in Viet Nam at the time of discharge or transfer, the author made the following telling comment.

> " Many of the physicians who filled out these forms recognized that they were frequently completed under stress, by command, and without enthusiasm, by physicians who considered it another thankless task, and therefore the accuracy of some of the data may be questionable…"
>
> R. M. Hardaway III [8]

Besides the problems of data collection mentioned with respect to public health statistics and the displacement of populations, other discrepancies and difficulties appear when dealing with a retrospective analysis of hospital-based data.

- The quantity and quality of data from different hospitals are irregular.
- Initial admission data, operating theatre observations, and ward medical records for individual patients do not always match.
- Hospital records are often incomplete, or contain clerical errors.
- The management of casualties at different points in a military chain of evacuation compounds reporting problems, particularly with respect to patient outcome.
- Access to medical care for the wounded – especially civilians or combatants in a civil war or during irregular guerrilla warfare – is not always available or must be done "in secret".
- Patients may disappear from the hospital before completing their treatment because of personal security concerns.
- Families do not always bring their dead for registration.

As mentioned before, one must also always consider the political and military sensitivity of trauma information; ICRC health personnel have on occasion been accused of being "spies" because they were asking a hospital director for admission statistics.

---

[8] Hardaway RM III. Viet Nam Wound Analysis. *J Trauma* 1978; **18**: 635 – 643.

5.4.3 Important first questions: who is counting whom?

Foremost is the very important problem of different definitions of epidemiological categories. Some military definitions have changed over the last century or been replaced by other terms. Articles written by civilian authors have often invented their own epidemiological categories and definitions. Who exactly composes the target population under study is different from one article to the next, although all deal with the "wounded" and during the same war. Large retrospective studies are fraught with such traps.

There are important first questions the reader must ask of all war surgery studies: who is counting whom and where? When is a wounded person counted as a wounded person? Which patients are included in the nominator and denominator in any formula or equation?

Important first questions:

Who is counting whom?
When is a wound a wound?
Who are the nominator and denominator?

Who is counting?
Different hospitals – military, public, and other (mission hospitals, non-governmental organizations, ICRC) – all have their own objectives, mandates and routines. They all collect statistics; but often for very different reasons, and very different statistics (see Annex 5. A: ICRC Surgical Database).

A well-organized classical army can tell you how many of their soldiers were killed or disabled; pensions and allowances must be paid and the necessary administrative structures to do so exist. Guerrilla forces and civilian medical facilities are incapable of fully recording such statistics, with rare exceptions.

Who is being counted and where?
Are casualties calculated at the point of wounding, at first-aid posts, first echelon or referral hospitals? The total number of wounded will depend on which level of the evacuation chain is counting, and what happens to them after injury.

The wounded that arrive at hospitals – where most studies are made – are only a sample of the casualties; they do not represent the total reality of war.

When is a wounded person a wounded person?
Many studies in the military literature, even when dealing with the same war, define the wounded differently. One example: for World War II, the United States Surgeon General's Statistical Health Report indicated 724,000 wounded and 228,000 battle-related deaths among American troops; a fatality rate of 23.9 %. The Adjutant General's Report gave the figure of 593,000 battle injuries and 235,000 deaths; a rate of 28.4 %. The latter report excluded the lightly wounded.[9] Retrospective analyses do not always indicate which figure is being used.

Studies do not always make clear if all superficial and light injuries are excluded or not from the calculations. To state the obvious: a scalp laceration is not the same as an open wound to the brain. The reader should note that non-penetrating head, chest, and abdominal injuries are not always clearly differentiated from penetrating ones. The use of the Red Cross Wound Score permits this distinction (see Chapter 4).

Similarly, studies of the anatomic distribution of wounds, the wounding agent, and delay in evacuation do not always state specifically whether the authors are dealing with the survivors only, or with total combat casualties comprising the dead as well as the wounded survivors.

---

[9] Carey ME. Learning from traditional combat mortality and morbidity data used in the evaluation of combat medical care. *Mil Med* 1987; **152**: 6 –12.

5.4.4 Some definitions: the wounded and the dead

Table 5.2 includes some basic epidemiological definitions intended to standardize reporting by the armed forces of the United States of America.

Killed in action (KIA)	Those dying from battle injuries before reaching a medical facility. Comparable to civilian dead on arrival (DOA).
Wounded in action (WIA)	Those wounded who survive to reach a medical facility staffed by a physician capable of trauma life support, whether pre-hospital or hospital.
Died of wounds (DOW)	WIA but dying from wounds later on.
Returned to duty (RTD) or Carded for Record Only (CRO)	Wounded but not hospitalized and returned to active duty within 72 hours. May include patients who are registered in a pre-hospital setting: carded for record only but not evacuated.
Hospital mortality	Died post-operatively in a surgical facility.

Table 5.2 Standardized epidemiological definitions as used by USA armed forces.[10]

ICRC EXPERIENCE

In Kisangani, a city of 600,000 inhabitants in the remote east of the Democratic Republic of the Congo, major fighting broke out in June 2000. Hostilities lasted seven days. One week later, visiting ICRC delegates recorded that 4 hospitals and 62 clinics had registered 1,691 wounded; 369 were still hospitalized (over 90 % civilians, most military casualties had been evacuated). The remaining casualties were under ambulatory care. It was impossible to determine the number killed. Almost a month later, a total of 2,393 casualties had been registered and 248 were still hospitalized. The vast majority of these patients were so superficially wounded that, had they been living in a rural environment far from a health facility, they would never have presented. These are the civilian equivalent of RTD and CRO.

In nine and half months in Beirut, in 1976, an ICRC field hospital treated 1,289 war-wounded on an outpatient basis and another 696 in hospital. Similarly, three months of urban warfare in Monrovia, Liberia in 2003 saw 2,588 patients triaged by an ICRC surgical team, but only 1,015 were admitted to hospital.

These examples tell us a great deal about the sociology of medical care during armed conflict and the effects on statistical results. In urban warfare, all civilian city-dwellers who are injured, even with very minor wounds, will seek medical treatment and be registered as war-wounded. Everybody goes to the hospital! Their reasons for presenting at a hospital or clinic are many: the medical sophistication of an urban population used to seeking curative care; the need for reassurance and being in a "safe" haven; hopes of financial compensation for all those injured; and the search for simple psychological support for a traumatized civilian population.

Although the presence in hospitals and clinics of so many superficially wounded patients may not represent the true extent of the surgical workload, the burden on the emergency department (triage and first aid), nursing care (wound dressings), and non-clinical work (administration, registration, laundry and kitchen) can be overwhelming. Statistical analysis is both difficult and tedious under such circumstances (e.g. Monrovia) or almost impossible (e.g. Kisangani).

---

[10] Holcomb JB, Stansbury LG, Champion HR, Wade C, Bellamy RF. Understanding combat casualty care statistics. *J Trauma* 2006; **60**: 397 – 401.

5.4.5 Clinical and operational consequences and IHL

A number of clinical and operational elements are significant as regards IHL.

1. For armies, the total number of casualties – soldiers removed from active participation in combat or support – and the overall lethality of the battlefield as represented by the case fatality rate (CFR) are important in terms of medical planning and allocation of fighting resources.

   For civilian health structures, the total number of casualties is only one measure of the social and economic burden of war and the humanitarian consequences of the disorganization of society.

2. Killed in action (KIA) helps to determine the lethality of weapons and the type of combat. IHL concerns itself with the lethality of weapons systems and the conduct of hostilities.

3. The KIA and died of wounds (DOW) help determine the efficiency of the evacuation chain, which is dependent on access to the wounded, appropriate pre-hospital care (field triage and initial treatment), and transport logistics (evacuation time and access to a hospital for the wounded). Access of health personnel to the wounded and access of the latter to medical facilities are supposed to be guaranteed, in accordance with the protection conferred upon these persons by IHL.

4. The adequacy of medical treatment depends on the efficiency of the evacuation system, the wounding mechanism and pathology (burns, blast, penetrating wounds, anti-personnel mines, etc.), and hospital competency. DOW and hospital mortality are the main indicators. Again, IHL is interested in the medical consequences of weapons systems.

5. These various indices of mortality are important. However, they say nothing about the severity of injury in survivors – morbidity and disability – or surgical workload that may have a greater long-term effect on civilian populations and health structures. The number of operations per patient, infection rates, amputation rates, and length of hospitalization better define the severity of injury and hospital burden of war-wounded. The humanitarian consequences of such effects are of direct concern to IHL.

5.5 Aetiology of injury

5.5.1 Warfare scenarios

The type of warfare greatly influences the kinds of wounds the surgeon sees and the anatomic distribution of injuries, which obviously affects hospital workload. The widespread use of anti-personnel blast mines in guerrilla and counter-insurgency warfare results in many traumatic amputations of the legs. Close combat with assault rifles causes many gunshot wounds with severe single injuries; shelling and bombing from a distance produce multiple fragment wounds, many of which are superficial. Major contemporary wars have seen a shift from gunshot wounds to fragment injuries in the majority of casualties.

In intercommunal strife, combatants in some societies engage in “traditional” warfare using machetes and *pangas*; slash wounds to the head, neck and shoulders predominate and, secondarily, injuries to the forearms when the victim attempts to protect him or herself. Elsewhere, the ready availability of small arms means that “traditional” combat and cattle raiding are now undertaken with the use of AK-47 Kalashnikov rifles.

Weapons systems available to belligerents vary. Classical armies of industrialized countries use air bombardment as well as artillery and armour, and their infantry is often fitted out with personal protective equipment. Classical armies of low-income countries tend to rely on infantry and artillery. Rural guerrilla formations depend on ambush with personal firearms and landmines; urban guerrilla warfare is largely street fighting with rifles, rocket-propelled grenades and, sometimes, short-range mortars. The weapons systems available to combatants can also change during the course of a war.

The intensity of fighting, being on the offensive or defensive, losing or winning a given battle, the size of the unit actually engaged, and the percentage of soldiers really exposed to combat, all affect various combat casualty statistics.

Relevant clinical consequences

The numbers and relative proportion of civilian and military wounded and dead depend to a large extent on combat strategy and operational tactics, geographical site of fighting, access to medical care, and who is winning or losing.

5.5.2 Definitions of weapon-systems: methodology

Some confusion arises in surgical literature because of differing categories and definitions for wounding agents and mechanism of injury: there is no universally accepted standard.

“Landmines” include both anti-tank (ATM) and anti-personnel (APM); the two are usually not differentiated. ATM may be the agent of wounding, but the mechanism of injury can be blast, blunt, burn, or penetrating fragment. APM may be either a blast or a fragmentation device. The severity of the injury differs with the mechanism and aetiology, but this cannot always be determined from the categories in a study.

The category of “fragment wounds” often groups together injuries from shells, bombs, and grenades, together with APM. The differences are important in terms of surgical management, however. Small, superficial wounds from preformed grenade fragments often do not require surgery; this is never the case for APM fragments (see Chapter 10). Table 5.3 gives an indication of the distribution of wounds according to projectile, from a number of conflicts.

	Bullets %	Fragments %	Other %
World War I (Western Allies)	39	61	
World War II (Western Allies)	10	85	5
Korea (USA)	7	92	1
Indochina (France)	62	38	
Algeria (France)	71	23	
Borneo (UK)	90	9	1
Lebanon: Beirut 1975 – 86	49	36	14
Northern Ireland	55	22	20
Falkland Islands / Malvinas (UK)	32	56	12
Thailand 1981	38	20	42 (APM)
Lebanon 1982 (Israel)	12	53	35
Lebanon: Bourj el-Barajneh refugee camp 1986 – 87	20	60	20
Eritrea 1988 – 91	33	63	2.2 (APM)
Bosnia-Herzegovina: Sarajevo 1992 – 96 (France)	59	37	4 (APM)
Bosnia-Herzegovina 1993 (Bosnia-Herzegovina)	49	46	5
Croatia 1991 – 93 (Croatia)	25	70	6 (APM)
Yugoslavia 1991 – 92 (Yugoslavia)	41	2	52 (APM)
Somalia: Mogadishu 1992 (US helicopter)	55	31	14

Table 5.3 **Aetiological distribution of the war-wounded: generally accepted historical examples. Anti-personnel landmines included in some. The country name in brackets indicates the source of information, see Selected bibliography.**

5.5.3 ICRC statistics

ICRC surgical teams have worked in many different wars and combat scenarios. Table 5.4 shows the mechanism of injury in different types of warfare.

Hospital	N =	Fragments %	Bullets %	Mines %
Butare	40	8	92	–
Kabul	6,244	52	29	19
Kao-i-Dang	1,067	22	16	63
Kandahar	1,159	24	50	26
Novye Atagi	186	44	35	22
Peshawar	4,340	42	23	35
Quetta	6,570	33	39	28
Lokichokio	12,196	10	87	2
Monrovia JFK Memorial	867	38	62	–

Table 5.4 Aetiology of war-wounded in a number of ICRC hospitals.

Extremes of the distribution of wounding mechanisms are to be found in these very different conflicts, and reflected in the statistics held in the various hospitals (Figure 5.3). Southern Sudan was the scene of a rural guerrilla war in semi-desert, sahelian landscapes, and reed swamps (Lokichokio hospital in northern Kenya) where most injuries were gunshot wounds (GSW). Fighting in Monrovia, Liberia, was irregular urban warfare (JFK Memorial Hospital). Patients coming to Kao-i-Dang hospital (Thailand) had been injured in rural guerrilla warfare waged in the forests and jungles of Cambodia with widespread use of anti-personnel landmines. Needless to say, the types of pathology encountered in these three hospitals differed widely.

Figure 5.3

Different combat tactics produce very different distributions of wounding agents.



5.6 Anatomic distribution of wounds

The aetiology of wounds and their anatomic distribution change constantly depending on the development of new weapons systems, personal protective material (body armour), and the nature of combat. One constant, however, is the preponderance of wounds to the limbs amongst survivors. This distribution is important in determining surgical workload.

5.6.1 Body exposure

Body exposure to injury differs according to the type of weapon:

- anti-personnel blast mines strike the legs (Pattern 1 APM injury);
- manipulation of mines injures the upper limbs, face and chest (Pattern 3 APM injury) as described in Chapter 3;
- fragmentation devices spray the whole body with multiple hits in a random fashion; and, secondarily, according to the type of combat and military activity:

Smiling as the Key Taoist Practice

Smiling and relaxation are the beginning practice of the Universal Tao. They are the key to the transformational process and to learning, as a result of which one is enabled to gently and patiently change old patterns into new, concerning oneself and the universe: new breathing, posture, inner and outer movement, and a new perception of reality.

Essential therefore in the Taoist practice to enhance learning and get in touch with the body by turning inward is to learn to relax and smile inward, so that dis-ease, manifest in many forms of stress, is overcome and one returns to a state of ease. Thus it may be said that whereas the Western approach to medicine starts from outside, the Taoist approach starts from within.

It is thus not incidental that the whole practice of the Universal Tao starts with the practice of the Inner Smile. This is actually the first practice of internal alchemy, as it serves to soften our body and its elements in which our consciousness is stored and through which it operates. It is the key agent of the whole activation and transformation process in all the practices. We do not only have a body but we also are our body. By touching it with love and gentleness, its knots and blockages start to dissolve so that the free flow of energy is restored.

Unity of Fullness and Emptiness

It is in this context not surprising that at the heart of the ancient Taoist texts is the emphasis on the practice of turning inward and of stillness. It follows that in the process of meditation as a practice of becoming aware of the inner state of being of the body and its movements, a new and fresh space is created in which renewal and transformation can take place. This space is also called the creation of emptiness and the continuous re-creation of emptiness so that new fullness becomes possible.

In the Taoist as well as in the Buddhist tradition, which historically have been closely related over long periods in Chinese history, emptiness and fullness are indivisible and a condition for each other. In the Universal Tao practices, this view has vast implications. For example, in the universe, emptiness and fullness are indivisible and are the creative source of becoming, evolving and

- aimed sniper fire targets the head or chest;
- trench warfare particularly exposes the head, resulting in the many mutilating facial wounds of World War I, known as "*gueule cassée*";
- purposeful observation and lookout activities of the soldier also increase the risk to the head and neck.

On the other hand, improved helmets and body armour, covering the chest and upper abdomen, effectively modify the relative exposure of anatomic regions.

Apart from aimed sniper fire, projectiles cause injuries in a random manner. Traditionally, combat exposure to injury has been estimated using as a basis the percentages of body surface area applied to assess burns, but taking into account operational necessities for soldiers (Table 5.5). It should be noted that combat exposure of the head and limbs is over-represented when compared to burns.

	Head	Neck	Thorax	Abdomen	Limbs
Body exposure in combat %	12		16	11	61
Surface area (burns) %	9	1	18	18	54

Table 5.5 Percentage body surface area versus surface area exposed in combat.[11]

5.6.2 Definitions and methodology

The anatomic distribution of wounds has been remarkably consistent over the last century. Reporting, however, has been remarkably inconsistent. Some studies cite only the primary site of injury if there is more than one; others include the category "multiple". Some count the "wounds" and not the "wounded", so that sites of injury exceed the number of patients. Many studies do not clearly define the counting method; in some reports only survivors are counted, while for others total combat casualties – KIA and WIA – are included. Again, the methodology is not always specified.

Anatomic regions are not standardized either. Different studies use different definitions for anatomic regions; there is again no universal standard. Some report only the "torso"; "pelvis and buttocks" are under a separate category from "abdomen" in some, and included in others. To be truly accurate, head, face, and neck categories should be clearly separated, which they rarely are. These latter wounds represent very different clinical problems – traumatic brain injury, asphyxia, haemorrhage – and degrees of lethality.

Anatomic distribution furthermore only indicates a potential threat; crude statistics often include superficial wounds, which is not a true indication of hospital workload and threat to life and limb. As has been mentioned above, it would be preferable to separate out penetrating from non-penetrating wounds of vital regions: head, thorax, and abdomen. The Red Cross Wound Score and Classification System attempts to address some of these problems in a simplified manner.

---

[11] Carey ME, 1987.

5.6.3 Historical results

The reader going through the literature will find very different figures for the same war, depending on the source and the methodology. This can make for frustrating reading. Nonetheless, some historical approximations are presented in Table 5.6. Wounds to the limbs predominate, from 50 % to 79 %.

Conflict	Head & Neck %	Thorax %	Abdomen %	Limbs %	Other & multiple %
World War I (Western Allies)	17	4	2	70	7
World War II (Western Allies)	4	8	4	79	9
World War II (USSR)	19	9	5	67	–
Korea (USA)	17	7	7	67	2
Viet Nam (USA)	14	7	5	74	–
Borneo (UK)	12	12	20	56	–
Northern Ireland	20	15	15	50	–
Arab-Israeli war 1973 (Israel)	13	5	7	40	31
Thailand 1981	10	12	4	66	8
Falkland Islands / Malvinas (UK)	16	15	10	59	–
Lebanon 1982 (Israel)	14	5	5	41	34
Lebanon: Bourj el-Barajneh refugee camp 1986 – 87	12	16	18	54	–
Gulf War 1991 (UK)	6	12	11	71	(32)*
Gulf War 1991 (USA)	11	8	7	56	(18)**
Afghanistan (USSR)	16	12	11	61	–
Chechnya 1995 (Russia)	24	9	4	63	–
Somalia: Mogadishu 1992 (USA)	20	8	5	65	(2)**
Croatia 1991 – 93 (Croatia)	15	11	4	69	1
Yugoslavia 1991 – 92 (Yugoslavia)	21	9	8	62	(23)**
Croatia 1991 (Yugoslavia)	12	15	8	65	–
Bosnia-Herzegovina 1992 (Yugoslavia)	14	15	9	62	–
Bosnia-Herzegovina 1993 (BH)	19	16	11	53	–
Bosnia-Herzegovina: Sarajevo 1992 – 96 (France)	11	11	14	61	3
Bosnia-Herzegovina: Sarajevo market bombing 1995	13	13	12	62	–
Eritrea 1988 – 91	20	9	6	63	2
ICRC surgical database	12.5	7.2	7.8	65.5	7
Overall average	~15	~10	~7	~65	

* Buttock and back wounds – all multiple fragment injuries – as a separate figure.

** Multiple wounds.

Table 5.6 Anatomic distribution of major wounds; some statistics include both dead and survivors, others include minor injuries. The country name in brackets indicates the source of information, see Selected bibliography.

5.6.4 ICRC results

The experience of ICRC surgical teams in various conflicts closely mirrors that of surgeons in other wars, particularly in relation to the type of conflict (Table 5.7). Many patients have multiple wounds; the distribution is given for injuries and not for patients, hence more wounds than patients. Only one wound is counted per anatomic region, however.

Pelvis and buttocks, back and soft tissue are given separately. Head, face and neck are not differentiated further.

Hospital	Number	Head & Neck %	Thorax %	Abdomen %	Pelvis & Buttock %	Back & soft tissue %	Upper limb %	Lower limb %	Limbs combined %
Kabul	8,804	15	9	10	4	3	24	35	59
Kao-i-Dang	1,660	15	8	7	4	3	24	39	63
Peshawar	6,840	18	8	6	5	3	25	35	60
Kandahar	1,396	11	9	11	3	2	24	40	64
Quetta	9,373	15	9	8	5	3	24	36	60
Butare	45	16	7	2	–	2	31	42	73
Novye Atagi	210	10	3	7	2	3	26	50	76
Lokichokio	14,203	7	8	3	7	3	29	44	73
Monrovia	904	14	13	4	4	–	21	43	64

Table 5.7 Anatomic distribution of wounds in various ICRC hospitals serving victims of differing types of combat.

5.6.5 Primary tissue injury

The anatomic distribution of wounds and the analysis of primary tissue injury permit the assessment of the surgical workload. In both, wounds to the limbs predominate; soft-tissue wounds and fractures of long bones constitute the majority of the injuries in all published series. The WDMET[12] statistics from Viet Nam are eloquent (Table 5.8); as are the figures from a French military field hospital in Sarajevo, 1992 – 1996, (Table 5.9). These analyses take into account non-penetrating wounds to vital regions.

Soft tissue (especially of limbs)	47 %
Extremities (long bone fractures)	26 %
Abdomen	8 %
Chest	4 %
Neck	2 %
Face	6 %
Head	2 %
Multiple	5 %

Table 5.8 Distribution of wounds according to primary tissue injury (USA).[13]

Soft tissue (especially of limbs)	56 %
Extremities (long bone fractures)	22 %
Abdomen	14.5 %
Chest	11 %
Face & Neck	6 %
Head	6 %
Peripheral vessels	6 %
Multiple	6 %

Table 5.9 Distribution of wounds according to primary tissue injury (French military field hospital in Sarajevo).[14]

ICRC results

In the hospitals included in the ICRC database, where evacuation was difficult for numerous patients and many with minor soft-tissue wounds did not bother to come to hospital, soft-tissue injuries still represented 36 % of wounds; fractures of the extremities 46 %; and vital central wounds 20 %.

Various other ICRC reports confirm these findings (Tables 5.10 and 5.11).

Soft tissue	33 %	Urogenital	5 %
Bones and joints	33 %	Chest	9 %
Vascular	11 %	Brain and spinal cord	3 %
Peripheral nerves	11 %	Maxillo-facial	3 %
Abdomen hollow organs	17 %	Eye, internal ear	2 %
Abdomen solid organs	9 %	Other	1 %

Table 5.10 Distribution of wounds according to tissue injury, hospitalized patients in the ICRC field hospital, Beirut 1976 (N = 696).[15]

---

[12] In the military literature, the Wound Data and Munitions Effectiveness Team (WDMET) of the United States set a gold standard for data collection. A large number of administrative staff meticulously collected information on 7,989 patients during the war in Viet Nam from 1967 to 1969 in a systematic way. The analysis was published by: Bellamy RF. Combat trauma overview. In: Sajtchuk R, Grande CM, eds. *Textbook of Military Medicine, Anesthesia and Perioperative Care of the Combat Casualty.* Falls Church, VA: Office of the Surgeon General, United States Army; 1995: 1 – 42. This report is often cited in review articles.

[13] Champion HR, Bellamy RF, Roberts P, and Leppäniemi A. A profile of combat injury. *J Trauma* 2003; **54 (Suppl.)**: S13 – S19.

[14] Versier G, Le Marec C, Rouffi J. Quatre ans de chirurgie de guerre au GMC de Sarajevo (juillet 1992 à août 1996) *Médecine et armées* 1998; **26**: 213 – 218.

[15] Translated from: Kjaergaard J. Les blessés de guerre de l'hôpital de campagne du CICR à Beyrouth en 1976. *Schweiz Z Milit Med* 1978; **55**: 1 – 23.

Parts injured	Total % (N = 1,033)	Bullet wounds % (n = 231)	Shell fragment wounds % (n = 508)	Mine injuries % (n = 294)
Soft tissue	73	67	75	70
Bone	39	52	20	63
Thorax	7	7.5	9	4
Abdomen	11	10.5	14	7.5
Brain	2.5	–	5	1
Other	4	2.5	4	4

Table 5.11 Tissue injuries according to wounding weapon, Kao-i-Dang ICRC hospital 1984 – 85.[16]

The clinically important point for the surgeon is the very large hospital workload represented by soft-tissue and orthopaedic injuries.

5.7 Fatal injuries

5.7.1 Site

It is not a simple matter to determine cause of death and site of lethal injury. Multiple injuries tend to have a synergetic effect and it can be impossible to define which of several wounds was the direct cause of death. Furthermore, many fatal war injuries involve total body disruption or severe mutilation.

A formal complete autopsy for every combat death is onerous even for the armed forces of a wealthy industrialized country, and this has rarely been common practice. Three examples of the anatomic distribution of fatal wounds are given in Table 5.12.

<table>
<tr><th></th><th>US dead in World War II[17]</th><th colspan="2">US dead in Viet Nam (WDMET)[18]</th><th colspan="2">Israeli dead in Lebanon 1992[19]</th></tr>
<tr><td>Head</td><td rowspan="3">42 %</td><td>37 %</td><td rowspan="3">46 %</td><td>9 %</td><td rowspan="3">34 %</td></tr>
<tr><td>Neck</td><td>6 %</td><td>3 %</td></tr>
<tr><td>Face</td><td>3 %</td><td>22 %</td></tr>
<tr><td>Chest</td><td>30 %</td><td colspan="2">24 %</td><td colspan="2" rowspan="2">45 %</td></tr>
<tr><td>Abdomen</td><td>12 %</td><td colspan="2">9 %</td></tr>
<tr><td>Multiple</td><td>–</td><td colspan="2">17 %</td><td colspan="2">–</td></tr>
<tr><td>Limbs</td><td>13 %</td><td colspan="2">3 %</td><td colspan="2">21 %</td></tr>
<tr><td>Soft tissue</td><td>–</td><td colspan="2">1 %</td><td colspan="2">–</td></tr>
</table>

Table 5.12 Anatomic distribution of fatal wounds.

Central wounds predominate, as would be expected; particularly to the head, face, neck and thorax.

> The great majority of war wounds are to the limbs.
> The most lethal wounds are to the head and chest.

---

[16] Trouwborst A, Weber BK, Dufour D. Medical statistics of battlefield casualties. *Injury* 1987; **18**: 96 – 99.

[17] Garfield RM, Neugut AI. Epidemiologic analysis of warfare. *JAMA* 1991; **266**: 688 – 692.

[18] Champion HR, et al., 2003.

[19] Gofrit ON, Kovalski N, Leibovici D, Shemer J, O'Hana A, Shapira SC. Accurate anatomical location of war injuries: analysis of the Lebanon war fatal casualties and the proposition of new principles for the design of military personal armour system. *Injury* 1996; **27**: 577 – 581.

5.7.2 Trimodal distribution of trauma mortality

Mortality in civilian trauma was classically described by D. Trunkey in 1983[20] to fall into three categories: immediate death (50 %), early death (30 %), and late death (20 %), see Figure 5.4.



Figure 5.4

Trimodal distribution of trauma deaths.

Peak 1: immediate deaths

Most deaths occur at the moment of injury or within minutes. These are due to overwhelming trauma incompatible with life (severe brain injury, massive haemorrhage).

In war, in addition to severe injuries to the head and torso (heart, liver, and major blood vessels), some casualties suffer total body disruption or incineration through burns. It is estimated that 70 % of deaths occur within five minutes, and little to nothing can be done for these patients, which represent about 17 – 20 % of the severely wounded.

Peak 2: early deaths

These occur after the first minutes until the first few hours after injury. This peak gave rise to the idea of the "golden hour"; if certain measures were implemented rapidly, the patient could be saved.

In war trauma, there are three major causes of early death:
- continuing exsanguinating haemorrhage;
- inadequate/impaired airway due to survivable penetrating head injury;
- compromised breathing due to tension pneumothorax.

Many of these early deaths are avoidable within this "golden hour" if adequate first-aid measures in the field are implemented in time.

Peak 3: late deaths

These occur a few days to weeks after injury and are the result of subsequent complications of infection, multiple organ failure and coagulopathy, and uncontrollable increased intra-cranial pressure due to post-injury cerebral oedema (closed injury).

Good and early first-aid measures can decrease infectious and other complications in the setting of armed conflict where wounds are dirty and contaminated from the very beginning. Inadequate early care affects morbidity (sepsis, disability) as well as mortality.

The understanding of this trimodal distribution of deaths stimulated an improvement in emergency medical services and patient transport in civilian settings. Rapid evacuation times and early advanced life support in many industrialized countries, in a bid to reach the injured during the "golden hour", have reduced these three peaks to a bimodal profile: immediate deaths and late.

---

[20] Trunkey DD. Trauma. *Sci Am* 1983; **249**: 220 – 227.

Applicability to the military war-wounded

The military have found that the trimodal distribution is relevant to armed conflict. They have tended to underline three categories of patients corresponding to what can be done under various operational scenarios in the field. This has an important influence on field triage categories.

1. Unsalvageable injuries: i.e. KIA for whom nothing can be done (17 – 20 %).
2. Severe but potentially survivable injury (10 – 15 %).
3. Moderate to minor injuries (65 – 70 %).

One result of improved pre-hospital care and evacuation is that some casualties become DOW (early deaths) instead of being KIA (immediate deaths) while a few others are saved. The most important field measures undertaken include stopping haemorrhage from controllable bleeding and maintaining a patent airway and breathing by simple procedures.

ICRC EXPERIENCE

Not all penetrating head injuries are so severe as to be incompatible with life. However, precarious pre-hospital care and long and difficult evacuation routes can result in large numbers of survivors of head injuries (WIA) succumbing later (DOW) because of inadequate control of the airway, resulting in asphyxia or vomiting and aspiration.

This was the case during one recent war in Africa involving a "classical" army. Large numbers of patients with salvageable head injuries were dying during a three-day evacuation in the back of lorries travelling over dirt roads in the bush. There was no possibility of monitoring endotracheal intubation.

An ICRC surgeon advised performing a tracheotomy in a front-line field hospital before evacuation, the only way to ensure an adequate airway under the circumstances in these comatose patients. The mortality rate for these cases was halved by this simple procedure.

Applicability to civilian war-wounded

At the shelling of the Markale market place in Sarajevo, August 28, 1995, only minutes away from two referral hospitals, 104 persons were injured of whom 42 ultimately died; a fatality rate of 40.8 %.[21]

Twenty-three died instantly and another ten were dead on arrival at hospital (79 % of deaths were first peak). Five patients succumbed during surgery (second peak 12 %) and another four a week later (third peak 10 %) as shown in Figure 5.5. The trimodal distribution of deaths appears to have been preserved.

Figure 5.5

Trimodal distribution of deaths after shelling of Sarajevo's Markale market.



Furthermore, in remote rural areas with difficult evacuation routes, both armies and civilian populations will probably experience the trimodal distribution of deaths, as originally described. Trauma survival under such circumstances is geography specific.

---

[21] Suljevic I, Surkovic I. Medical aspects of the mass-scale civilian casualties at Sarajevo Markale Market on August 28, 1995: triage, resuscitation, and treatment. *Croat Med J* 2002; **43**: 209 – 212.

5.7.3 Ratio of dead to survivors

Many authors have noted that the ratio of dead to survivors in modern conflicts tends to be about 1:4 over the long term. This corresponds to our threshold fatality rate of about 20 – 25 %.

$$\frac{\text{Dead} = \text{KIA plus DOW}}{\text{Survivors} = \text{WIA minus DOW}} = 1{:}4$$

Many factors can distort the specific results under given circumstances, including:

- the inclusion of minor wounds in the calculations – the famous methodological problem;
- the tactical situation (note the 40 % fatality rate of the Markale market place bombing mentioned above; burn injuries in tank crews or on ships; a successful surprise ambush, etc.);
- the lethality of particular weapons systems (anti-personnel landmines, napalm, etc.);
- any delay in medical evacuation; and
- the execution of wounded prisoners in contravention of the laws of war.

Improvement in personal protective equipment (body armour), better pre-hospital care, and the early availability of more aggressive surgery and enhanced intensive care facilities has changed the ratio in recent conflicts. For US armed forces in Iraq and Afghanistan, the dead to survivor ratio has become 1:8.[22] Effective body armour has decreased fatal wounds to the chest and abdomen, but increased wounds to the head and neck in survivors. No other armed forces use such improved body armour as extensively and the US experience is not easily translated to others, but it sets a standard nonetheless.

5.7.4 Lethality of weapons

If the KIA equals approximately 20 % and the DOW 5 %, this represents the total lethality of weapons during combat on land. Sea and air warfare are different.

It has long been recognized that different weapons systems have different lethality. In general, and over a large number of casualties the following percentages appear.

- Military rifle bullets: 30 – 40 % lethality; or one death in every 3 – 4 wounded.
- Randomly-formed fragments: 20 % for shells and 10 % for grenades.
- Preformed fragments: 15 % for shells and 5 % for grenades.
- Blast injury has a fatality of about 22 %.

Tactical considerations for distinct individual battles can change these figures. A well-laid ambush with small arms can easily result in more than 40 % of a small patrol being killed.

The particular case of anti-personnel landmines
All studies indicate the heavy surgical and nursing burden of injuries due to anti-personnel landmines, especially blast mines. Specific types of APM – bounding mines that jump up one metre in the air before exploding – invariably kill their victim: lethality lies close to 100 %.

Public health studies and ICRC surveys in poor countries where APM have been widely used in rural areas with little or no organized evacuation system and limited surgical facilities (Mozambique, Somalia, Cambodia, Afghanistan and Angola) indicate a case fatality rate of well over 50 % for traumatic amputations due to APM.

It is difficult to exclude the non-weapon factors in these studies and mortality statistics. Suffice it to say that the lethality of weapons includes their actual use in field conditions, and their total socio-economic and humanitarian effects. This is important in terms of IHL and was one of the significant factors in determining countries to negotiate the 1997 Ottawa Convention on the Prohibition of the Use, Stockpiling, Production and Transfer of Anti-personnel Mines and on their Destruction.

---

[22] Holcomb JB, et al., 2006.

5.7.5 Conclusions of clinical relevance

From this analysis and further extrapolations a number of conclusions can be drawn.

1. Wounds to the head and torso are the most lethal; they represent most of the mortality. The great majority of survivors have injuries to the limbs; they represent the majority of surgical workload and morbidity.
2. Despite the fact that the head represents only 9 % of exposed body surface area, it accounts for a disproportionate number (25 %) of all battle casualties. The lethality of penetrating head wounds is approximately 75 % and they account for slightly less than 50 % of combat deaths (KIA + DOW), and about 8 % of survivors.
3. Head wounds kill either through devastating brain injury or through asphyxiation of the comatose patient who would otherwise survive the injury.
4. Death through closed head injury is relatively greater in the civilian setting than during armed conflict.
5. Uncontrolled exsanguinating haemorrhage accounts for another 50 % or so of deaths. Most of these (80 %) present central injuries to the thorax and/or abdomen, which require surgical facilities for control. The lethality of chest wounds is about 70 %.
6. The other 20 % of haemorrhage deaths are due to bleeding from peripheral, compressible blood vessels (half in the neck and half in the limbs). Thus, about 10 % of all deaths are due to haemorrhage from the limbs.
7. Death rates through haemorrhagic shock are higher in armed conflict than in the civilian trauma setting.
8. Little can be done medically for most immediate deaths and there is a threshold percentage of killed-in-action no matter how sophisticated the medical services are.

Conclusions for improvement of patient outcome

1. Some immediate and early deaths can be prevented by personal protective armour covering the torso.
2. Many early deaths can be prevented by simple measures to:
   - control limb haemorrhage;
   - relieve airway obstruction, especially in comatose patients after head injury;
   - relieve tension pneumothorax.
3. Some early deaths due to haemorrhage, particularly of the abdomen, can be prevented by rapid evacuation to a surgical facility.

5.8 The lethality of context: delay to treatment

5.8.1 Historical developments

Possibly one of the most important developments in combat casualty care over the last half-century has been improved pre-hospital care and the timely evacuation of the wounded to a surgical facility. Lasting days during much of World War I, evacuations took an average of 10.5 hours during World War II; the use of helicopters by American troops in Korea lowered this to 6.3 hours, and an average of 2.8 hours in Viet Nam. Transfer of Israeli wounded during the 1982 war in Lebanon took an average of 2.3 hours. The use of helicopters has radically changed evacuation and pre-hospital care for the armies of industrialized countries, but requires air superiority to be truly effective. It has also revolutionized equivalent civilian trauma systems. This resource is seldom available in a low-income country.

5.8.2 Forward projection of resources

Delayed evacuation may still result from operational contingencies, tactical situations, and difficult geography. Consequently, many armies have projected forward their surgical capacities close to zones of actual combat in an attempt to reach wounded soldiers earlier and avoid the mortality and morbidity related to any delay. The aim is primarily to reduce the number of "early" deaths.

Soviet deployment of "Special Surgical Teams" in forward locations in Afghanistan shortened time to reach surgery: 31 % of wounded were in surgery within 1 hour and another 39 % within 2 hours. Cumulatively, 92 % were in surgery within 6 hours with this system. This compares with an overall average during the war of 88 % operated within 12 hours, before and after the establishment, of the forward teams.

During fighting in Croatia in 1991, a Yugoslav mobile field hospital was located 5 – 10 km from the front: 61 % of wounded were evacuated within 30 minutes and another 22 % between 30 and 60 minutes of being injured.

US troops in Afghanistan and Iraq have also seconded "Forward Surgical Teams" and "Forward Resuscitative Surgery Suites" to the field; surgical care routinely begins within 1 – 4 hours following injury. Preliminary reports give a mean time of one and a half hours for evacuation of USA military wounded in Iraq to a forward surgical facility.

5.8.3 Urban warfare: hospitals on front lines

During urban warfare, fighting can take place literally in front of surgical facilities; more than once has a patient been wounded at the front door of a hospital. This was the case during much of the fighting in Beirut in the Lebanese civil war, often with evacuation times of only minutes. A French medical team in Sarajevo in 1992 – 96 (UNPROFOR – IFOR), serving military and civilian casualties, had evacuation times of 15 – 45 minutes.

Comparable times were encountered by ICRC hospital teams in Kabul in 1992 and Monrovia, Liberia, in 2003. ICRC and Somali Red Crescent surgical teams working in the Keysaney Hospital in North Mogadishu have witnessed similar short evacuation times from 1992 up until the present time of writing.

Although the vast majority of wounded patients arrive at the hospital within minutes under these circumstances, a few suffer considerable delay. Without an organized pre-hospital system and given an absolute absence of ambulances, civilians are often cut off from care facilities during street fighting and have to wait hours or even days for evacuation.

5.8.4 The paradox of early treatment: changing mortality ratios and rates

There is an apparent paradox of early evacuation and treatment: an increase in the absolute numbers who survive, but also an increase in the DOW and hospital mortality rates. Medics reach a number of former KIA in time; more severely injured casualties enter the evacuation chain earlier, but since natural automatic triage that weeds out the more severely injured does not come into play, a higher percentage of injured now die of their wounds after they have received care.

For US armed forces who died in World War II and Viet Nam, 88 % were KIA and 12 % DOW. In the conflicts in Iraq and in Afghanistan, the figures are 77 % and 23 %.[23]

---

[23] Holcomb JB, et al., 2006.

This effect has also been observed in hospital mortality rates at ICRC facilities (Tables 5.13 and 5.14).

Time until arrival in hospital	Patients (n =)	Died	Mortality
< 6 hours	3,114	172	5.5 %
6 – 24 hours	3,588	141	3.9 %
24 – 72 hours	1,668	46	2.8 %
> 72 hours	2,430	55	2.3 %

Table 5.13 Mortality according to evacuation time to ICRC hospitals: period from January 1991 to July 1993.

Longer evacuation times allow for "natural triage" to come into play. The more seriously wounded die before they reach hospital when evacuation is delayed.

Time until arrival in hospital	Patients (n =)	Died	Mortality
< 6 hours	79	5	6.3 %
6 – 24 hours	704	21	3.0 %
24 – 72 hours	210	5	2.4 %
> 72 hours	134	2	1.5 %

Table 5.14 Mortality according to evacuation time: patients transferred from ICRC first-aid posts to Peshawar ICRC hospital 1990 – 91.[24]

A new ratio: critical area to extremity wounds

A statistical method has been used to try to overcome this "bias" of logistical progress in order to better evaluate the effect of "natural triage" due to a lack of appropriate surgical care and evacuation facilities in low-income countries. In such conditions pre-hospital mortality cannot be properly determined either. The ratio of wounds in critical areas (trunk, head and neck) to wounds of the extremities is calculated among survivors: CA : Ext.

$$\frac{\textbf{Critical areas (head, face, neck, thorax, abdomen, pelvis)}}{\textbf{Non-critical areas (limbs, back, soft tissue injuries of trunk)}} = \textbf{CA : EXT}$$

CA = critical area, EXT = extremities and other non-critical areas.

Obviously, the wearing of body armour and the inclusion in statistics of minor or superficial, non-penetrating wounds to the head or trunk will distort the anatomic distribution of wounds, and the ratio.

In most wars, with evacuation counted in hours, the ratio is approximately 0.5. In urban areas and other situations of rapid evacuation, it tends towards 1. With increasing delay of evacuation to over 24 hours, and even days and weeks, the ratio falls.

Thus, studies of guerrilla and counter-insurgency warfare in difficult geographical terrain give much lower ratios indicating that the most seriously injured patients (critical area wounds) died before treatment (Table 5.15).

Conflict	Ratio
Thailand counter-insurgency	0.39
Eritrean war of independence	0.26
Ugandan guerrilla war	0.21
Afghan mujaheddin	0.07
ICRC Lokichokio hospital: southern Sudan guerrilla war	0.33

Table 5.15 Ratio of critical area to limb wounds in various insurgency conflicts.[25]

---

[24] Korver AJH. Outcome of war-injured patients treated at first aid posts of the International Committee of the Red Cross. *Injury* 1994; **25**: 25 – 30.

[25] Adapted from Bhatnagar MK, Smith GS. Trauma in the Afghan guerrilla war: effects of lack of access to care. *Surgery* 1989; **105**: 699 – 705.

renewal, so that the universe is reborn in a continual process. We ourselves give thanks to the alternation of the inhale and the exhale, so our body is in a continuous process of dying and being reborn, through which we renew ourselves. The new can only rise if the old dissolves. So it is in Nature with the change of seasons. And so it is with all that is alive in the universe. This is the core wisdom of the *I Ching*.



Fig. 9.3 *The core is the center of the universe, earth and the body.*

In the Taoist practice this has a particular application in the counsel to empty the mind and let it come down in the body so that a major source of energy is preserved and can renew itself. At the same time the belly can be filled with Chi, so that the energy streams in the whole body are enhanced and the heart is freed from too much pressure, as the belly helps do its work. Only when we learn to renew ourselves by undoing what has become unnecessary and what obstructs the process of transformation do we renew ourselves and our body. By undoing ourselves from what is no longer needed the new can grow. An ancient Taoist proverb suggests that simplicity comes about by seeing every day what has become dispensable. Then one can walk and move more lightly, both in the mind and with the body.

Jesus often reminded people in His parables of the law of unity and alternation in nature, and in themselves of old and new. In the *Tao Te Ching* this truth is expressed in the use of rich metaphors, for example, the house which acquires its function by being empty and the wheel which receives its function by virtue of its emptiness.

5.9 Hospital mortality

5.9.1 Historical considerations

As mentioned, rates of killed in action for armies have remained relatively stable over the last half-century at about 20 – 25 %. Hospital mortality, however, has diminished greatly with medical progress (safe anaesthesia, blood transfusion, better understanding of the physiology of shock, antibiotics, and more aggressive surgical techniques) as shown in Table 5.16.

Conflict	Hospital mortality rate %
Crimean War 1854 – 55 (UK casualties)	16.7
American Civil War 1861 – 65 (Union casualties)	14.1
Boer War 1899 – 1901 (UK casualties)	8.6
World War I 1917 – 18 (USA casualties)	7.6
World War II (USA casualties)	4.5
American – Viet Nam War (USA casualties)	2.5

Table 5.16 Hospital mortality: examples from the past.

Hospital mortality has come to be an indicator of the efficiency of the management system, bearing in mind what has already been said about the paradox of early evacuation of the very severely injured. In calculating these figures, however, one must take into account the percentage of truly "vital" injuries and exclude or specify the superficial ones.

5.9.2 Hospital mortality *versus* post-operative mortality

A number of considerations must be taken into account if one wishes to use hospital mortality as an indication of the efficiency of patient management systems. In armed conflict, surgeons often face mass casualties. Some patients will be triaged into the "expectant" category, and given supportive treatment only, to die without pain and with dignity (see Chapter 9). These patients are recorded as DOW and are often included in hospital mortality figures.

Other patients die shortly after arrival, or "on-table", in an extreme attempt to save life. With a slightly longer evacuation time, many such patients would be KIA, dying before reaching hospital, as mentioned previously. Nonetheless, they are registered as DOW and are again included in hospital mortality figures.

Then there are the truly post-operative deaths; some from irreversible shock, others from irretrievable brain injury and, others still, from surgical complications, mostly sepsis, and additional medical pathologies.

Gross statistics of hospital mortality do not always take into consideration these very different categories of patients.

5.9.3 ICRC hospital mortality

Austere working conditions, often a limited number of professional staff and at times a perilous security situation, all make work in ICRC hospitals resemble that commonly seen in public hospitals in a poor country. Military medical services from industrialized countries may also face these constraints, but they tend to be of a different order of magnitude.

Post-operative mortality in ICRC hospitals varies from 2.2 % in Quetta and 3.1 % in Peshawar to 4.2 % in Kao-i-Dang, 4.8 % in Kabul, and 6.1 % in the Monrovia battle, where evacuation times were extremely short.

5.10 ICRC statistical analysis of hospital workload

5.10.1 Surgical audit: methodology

Without control over the pre-hospital phase and the known inadequacies of data collection, the mortality rate is not a credible statistic in ICRC surgical programmes and hospitals. The same is true of most public civilian structures. Far more substantial is the workload and morbidity as represented by the number of operations and blood transfusions per patient and the duration of hospitalization.

For statistical purposes, most patients, if well managed, undergo two operations: wound excision and delayed primary closure. There are a number of factors that explain this:

- the ICRC does not have a series of operative echelons of treatment as do the military; all operations are performed in the same hospital (see Chapters 1 and 6);
- rarely do ICRC surgeons perform planned serial debridements of war wounds, requiring more operations (see Chapter 10);
- some patients require a third operation for skin grafting to close the wound, or even more if a burn complicates a penetrating wound (see Chapter 11);
- others call for a single operation: (craniotomy, chest tube drainage, or laparotomy);
- some patients call for no operation, if they have been admitted solely for observation – expectant triage category, paraplegic, etc. (see Chapter 9);
- small superficial wounds are often treated conservatively with dressings and antibiotics, with the exception of those caused by anti-personnel landmines.

These "normal" single and multiple operations tend to balance each other out. (Pure burn injuries are not included in this discussion.)

Most patients require two operations: debridement and delayed primary closure. More than two usually denotes a complication, typically sepsis.

Performing more than two operations per patient usually denotes a complication, typically sepsis, and is a good indication of morbidity. Thus, as an appropriate approximation of workload and correct surgical management, the ICRC uses the average of two operations per patient in large studies. These premises form the basis for the following discussion.

5.10.2 Number of operations per patient: all patients

The number of operations per patient for all patients with the relevant information in the ICRC database is given in Table 5.17.

None	9 %
1 operation	16 %
2 operations	41 %
≤ 2 operations	66 %
3 operations	14 %
≥ 4 operations	20 %

Table 5.17 Number of operations per patient (N = 16,172).



Figure 5.6

Number of operations per patient, simplified (N = 16,172).

To simplify, the number of operations are described as two or less; three; or four and more (Figure 5.6).

Fully two-thirds of all patients in the database had two operations or less, indicating a minimum of morbidity and good surgical management. There are a number of factors that influence this surgical workload: delay in evacuation, severity of the wound, type of wound, and wounding mechanism. A brief analysis of some of these factors is given in the following sections.

5.10.3 Number of operations according to delay in evacuation

Table 5.18 shows the results for the number of operations per patient according to evacuation time to the ICRC hospital in Kabul during a period of major urban combat.

Evacuation time	N = 6,140	None	1 op	2 ops	≤ 2 ops	3 ops	≥ 4 ops
< 6 hrs	3,214	7 %	30 %	47 %	84 %	7 %	8 %
6 – 24 hrs	1,606	7 %	23 %	51 %	81 %	9 %	11 %
24 – 72 hrs	605	6 %	24 %	50 %	80 %	7 %	12 %
> 72 hrs	715	9 %	26 %	42 %	77 %	9 %	14 %

Table 5.18 Number of operations per patient according to time of evacuation to ICRC Kabul hospital 1990 – 92.

These figures are confirmed if one examines the entire database (Table 5.19).

Evacuation time	N = 16,172	≤ 2 ops	3 ops	≥ 4 ops
< 6 hrs	2,409	81 %	9 %	10 %
6 – 24 hrs	3,727	70 %	13 %	17 %
24 – 72 hrs	2,785	69 %	13 %	17 %
> 72 hrs	7,251	71 %	12 %	17 %

Table 5.19 Number of operations per patient according to time of evacuation to ICRC hospitals 1990 – 99.

While hospital mortality is influenced by delay in evacuation, morbidity as determined by number of operations per patient apparently is not. The critical limit would appear to be 6 hours delay – the category "6 – 12 hours since injury" does not exist in the ICRC database, and this is a field for future study. However, before rushing to such a conclusion, another factor must be analysed: wound severity.

5.10.4 Number of operations according to Wound Grade

War wounds are categorized into one of three Grades of increasing severity according to the Red Cross Wound Score and classification system (see Chapter 4). The distribution in the ICRC surgical database is as follows.

- Grade 1: 42 %.
- Grade 2 : 37 %.
- Grade 3 : 21 %.

If one looks at the number of operations according to Wound Grade, an important difference appears (Table 5.20 and Figures 5.7.1 – 5.7.3).

Severity of wound		Number of operations per patient					
	Patients (N =16,172)	None %	1 op %	2 ops %	≤ 2 ops %	3 ops %	≥ 4 ops %
Grade 1	n = 6,729	16	23	45	84	9	7
Grade 2	n = 5,974	4	12	44	61	16	23
Grade 3	n = 3,469	3	7	30	40	19	41

Table 5.20 Number of operations per patient according to Red Cross Wound Grade.

The Grade of the RCWS shows a distinct difference in the number of operations required. Surgical workload is definitely influenced by the severity of injury, as would be expected, and the RCWS is capable of determining this.



Figure 5.7.1

Number of operations per patient for Grade 1 wounds (N = 6,729).



Figure 5.7.2

Number of operations per patient for Grade 2 wounds (N = 5,974).



Figure 5.7.3

Number of operations per patient for Grade 3 wounds (N = 3,469).

5.10.5 Number of operations according to Wound Grade and delay in evacuation

If one now analyses the number of operations by combining the RCWS Wound Grade and the delay in evacuation the results are telling (Table 5.21).

Grade and evacuation time	Number of patients	≤ 2 operations	3 operations	≥ 4 operations
Grade 1	N = 6,729			
< 6 hrs	1,124	93 %	5 %	3 %
6 – 24 hrs	1,694	84 %	9 %	7 %
24 – 72 hrs	1,182	82 %	11 %	7 %
> 72 hrs	2,729	82 %	10 %	9 %
Grade 2	N = 5,974			
< 6 hrs	788	77 %	11 %	12 %
6 – 24 hrs	1,186	62 %	16 %	22 %
24 – 72 hrs	1,110	58 %	17 %	25 %
> 72 hrs	2,890	56 %	18 %	26 %
Grade 3	N = 3,469			
< 6 hrs	497	47 %	17 %	35 %
6 – 24 hrs	847	37 %	19 %	44 %
24 – 72 hrs	493	39 %	19 %	42 %
> 72 hrs	1,632	40 %	20 %	40 %

Table 5.21 Number of operations per patient according to Red Cross Wound Grade and time since injury.

It would thus appear that the Red Cross Wound Score better represents morbidity and surgical workload than the delay in evacuation to hospital alone, but a combination of the two is more noteworthy. Grade 3 wounds tend to be very severe and delay does not appear to make a difference. Many such patients will simply not survive to reach hospital.

5.10.6 Number of operations according to weapon

The results of an analysis of the ICRC hospitals treating a variety of weapons-induced injury (Kabul, Kandahar, Kao-i-Dang, Novye Atagi, Peshawar, and Quetta), are presented in Table 5.22.

No distinction is made in the ICRC database between anti-personnel and anti-tank mines, or unexploded ordnance. Furthermore, some wounds classified as being caused by fragments may well have been from fragmentation anti-personnel mines. Hospital staff have only the account of the patient to go by and, naturally, many patients are ignorant of weapons systems; they only know of "bombs" or "guns".

Weapon	None	1 op	2 ops	≤ 2 ops	3 ops	≥ 4 ops
Mines N = 5,236	9 %	15 %	38 %	62 %	14 %	24 %
GSW N = 5,984	9 %	22 %	44 %	75 %	12 %	13 %
Fragment N = 7,674	11 %	24 %	44 %	80 %	9 %	11 %

Table 5.22 Number of operations per patient according to weapon.

It is obvious that mines imply a much greater workload and morbidity than gunshot (GSW) or fragment wounds (Table 5.22 and Figure 5.8).



Figure 5.8

Number of operations per patient according to weapon, simplified.

Although the lethality of weapons is important, the total effects of surgical workload, morbidity and suffering, and the socio-economic consequences must also be taken into account. It is not for nothing that poison gas, bacteriological weapons, blinding laser weapons, anti-personnel mines and cluster submunitions have been proscribed and banned by international treaty.

5.11 Conclusions: lessons to be gained from a study of epidemiology

From this brief overview of the epidemiology of the victims of war, a few conclusions affecting clinical work and humanitarian action may be drawn.

1. For a civilian population in a poor country, the public health effects of war are usually greater than the effects of direct trauma. In some conflicts, war injuries carry a greater burden and post-traumatic morbidity may have more profound long-term effects than mortality. This is especially the case in a post-conflict situation with widespread contamination by anti-personnel mines whose socio-economic repercussions are long-lasting.

2. The outcome of war surgery in a civilian context is influenced by:
    - the type of injury according to wounding agent;
    - the severity of the injury;
    - the general condition of the patient (malnutrition, chronic disease, concomitant endemic disease such as malaria, etc.);
    - early and appropriate first aid;
    - the time needed for transport to the hospital;
    - the quality of hospital treatment (resuscitation, surgery, post-operative care, physiotherapy and rehabilitation);
    - possibility of evacuation to a better-equipped hospital with more experienced staff.

3. In a civilian context, and especially in a poor country, pre-hospital care is the phase most open to improvement. Much can be done to prevent death and morbidity with early and efficient first aid and life support.

    An efficient first-aid and evacuation system can prevent deaths from controllable haemorrhage and compromised airway. As pre-hospital care improves, the “killed in action” or “dead on arrival” may diminish slightly, only to see the “dead of wounds” and hospital mortality rise; more casualties are saved, but the rates become distorted. This bias should be taken into account when judging the adequacy of care.

    Long and difficult evacuation of the wounded results in an automatic “natural triage” of the most severely injured. Hospital mortality rates decrease as a result.

4. Up to 40 – 50% of the civilians wounded during urban fighting do not need hospitalization. First-aid measures – plus a simple oral antibiotic and analgesic – are all that are required. Their presence constitutes a supplementary burden on hospital management. However, discharging them from hospital can prove problematic because of security concerns, socio-economic factors and patients' fears.
5. Wounds to the head and torso are the most lethal. Injuries to the soft tissues and the limbs constitute the majority of surgical workload.
6. Gunshot wounds carry a heavier burden than injuries due to fragments; but burns and anti-personnel landmine injuries represent the heaviest hospital workload and morbidity.
7. The Red Cross Wound Score allows a good appreciation of the severity of war wounds, and the surgical workload that they represent.

5.11.1 Setting up a surgical database for the war-wounded

Various military medical services have their own categories and charts for data collection. The ICRC offers civilian health facilities an example of categories that could be placed in a simple spreadsheet (Excel ®) to allow for a collection of relevant data for further study (see Annex 5. B: Setting up a surgical database for the war-wounded).

In addition, a downloadable file form of Annex 5. B (Setting up a surgical database for the war-wounded) is available on the accompanying DVD (Annex 5. C). It can be modified by the user.

ANNEX 5. A ICRC surgical database

The ICRC set up a centralized wound database and trauma registry in 1990, originally designed to give the organization an indication of the surgical workload of its independent hospitals (i.e. hospitals that were established and run under ICRC administration). All war-wounded patients admitted to ICRC hospitals have routinely had a data form filled out on their death or discharge. Patients are not asked whether they are combatants or civilians.

Age and sex, the cause and anatomic site of injury, and the time lapsed between injury and admission are recorded for each patient. Projectile injuries are scored according to the Red Cross Wound Classification System described in Chapter 4. The emphasis is on surgical workload as described by severity of injuries, number of operations per patient, number of blood transfusions required, and length of hospitalization.

These independent ICRC hospitals have served the victims of a number of armed conflicts of very different types of combat. As at 31 December 2007, the database contained the records of 32,285 war-wounded patients. Not all are complete, however.

Hospital	Period of activity	Nature of combat
Kao-i-Dang Hospital, Thailand	1979 – 92	Jungle guerrilla warfare in Cambodia
Peshawar Hospital, Pakistan	1981 – 93	Mountain guerrilla warfare in Afghanistan
Quetta Hospital, Pakistan	1983 – 96	Mountain guerrilla warfare in Afghanistan
Karteh-Seh Hospital, Kabul, Afghanistan	1988 – 92	Irregular warfare, mostly urban
Mirweis Hospital, Kandahar, Afghanistan	1996 – 2001	Irregular warfare, mostly urban
Butare Hospital, Rwanda	1995	Irregular guerrilla warfare, mostly rural
Novye Atagi Hospital, Chechnya, Russian Federation	1996	Irregular guerrilla warfare, rural and urban
Lopiding Hospital, Lokichokio, Kenya	1987 – 2006	Rural guerrilla war in semi-desert, sahel and reed swamps of southern Sudan

The above-mentioned conflicts were different in nature. Time to treatment often included extremes – minutes to weeks. Logistic difficulties over great distances meant that the ICRC could rarely organize efficient and timely evacuation of the victims. Notable exceptions were the first-aid posts set up near the Afghan border with Pakistan and close to Kabul. The air medical evacuation programme for southern Sudan, coordinated with the United Nations Operation Lifeline Sudan, saw over 20,000 patients transferred to the ICRC hospital in Lokichokio, northern Kenya, but the distances and delays in notification of patients nevertheless seldom allowed timely evacuation.

The ICRC has also set up other hospitals, and its surgical teams have worked in local public hospitals, but their patients are not included in the database. In addition to the surgical database, other major sources of data include the Somali Red Crescent-run Keysaney Hospital in Mogadishu (1992 – present), and the JFK Memorial Hospital, Monrovia, Liberia (2001 – 2004), operated jointly by the ICRC and the hospital's Board of Governors.

When compiling ICRC statistics from the database, the limits of a retrospective analysis of prospectively collected data taken exclusively from hospital admissions must be recognized. The usual problems have been observed:

- clerical errors,
- missing patient files,
- incomplete patient files (not all categories were filled in for all patients),
- confusion as to the definition of classification categories,
- lack of continuity due to the constant turnover of hospital personnel,
- lack of properly trained administrative support staff to maintain a database.

Nonetheless, ICRC statistics are offered throughout this manual as an example of non-military experience in different combat zones as an approximation of the reality of the battlefield, especially for non-combatant populations.

ANNEX 5. B Setting up a surgical database for the war-wounded

The following categories can be recorded in an electronic database (Approach ®) or listed in the *columns* of a simple spreadsheet (e.g. Excel ®) and patients registered in the *rows*. Lessons have been learnt from shortcomings in the ICRC surgical database: this version has been modified accordingly.

Administrative data:

- hospital (if the database contains patients from more than one hospital)
- patient hospital number
- database number
- date of admission
- date of discharge
- number of days hospitalized
- re-admission of patient for the same injury?
- age
- sex

Time since injury:

- hours (or < 6 ; 6 – 12; 12 – 24)
- days (or 24 – 72 hrs ; >72 hrs)
- weeks

Weapon causing injury:

- rifle, gun
- bomb, shell, mortar, grenade
- anti-personnel mine (APM)
- anti-tank mine (ATM)
- unexploded ordnance (UXO), including cluster bombs
- "arme blanche": bayonet, machete, *panga*

Mechanism of injury:

- gunshot (GSW)
- fragment
- blast
- blunt
- burn

Please note:

A bomb, artillery shell or anti-tank mine may give off penetrating fragments, cause blast or burn injury and, by destroying a vehicle or building, also cause blunt injury. One weapon is registered; several mechanisms of injury are recorded. The same can be said of anti-personnel mines.

Clinical data:

- blood pressure on admission
- number of operations
- number of anaesthesias
- number of units of blood transfused
- outcome: healed, complications, death (including cause)

Anatomic data:

Site of injury: if more than one, each injury is given a number and the appropriate number put in the column for the anatomic region. Only one injury per anatomic region is noted.

- head
- face
- neck
- thorax
- abdomen
- pelvis, buttocks
- back and soft tissue of torso
- upper limb left (to determine bilateral limb injuries)
- upper limb right
- lower limb left
- lower limb right

Red Cross Wound Score:

This should be entered for the two most important wounds, more if so desired. The number 1 wound should correspond to the number 1 anatomic region; wound 2 for number 2 anatomic region.

- Wound 1: Entry
- Wound 1: Exit
- Wound 1: Cavity
- Wound 1: Fracture
- Wound 1: Vital injury
- Wound 1: Metallic fragment
- Wound 1: Grade
- Wound 1: Type
- Wound 2: Entry
- Wound 2: Exit
- Wound 2: Cavity
- Wound 2: Fracture
- Wound 2: Vital injury
- Wound 2: Metallic fragment
- Wound 2: Grade
- Wound 2: Type

It finds its most pregnant expression however in the law on the unity of living and dying, common to all the great spiritual traditions – Hindu, Buddhist and Christian –, which is also central to Taoist practice. The new can only emerge and grow, if the old dies and is discarded.

Attachment and Detachment

This insight is at the core of the *I Ching* in which nature with its cycles and seasons is held up as a mirror for human beings. It has shaped from ancient times the Taoist proposition that to learn to be and realize oneself, one needs to go with the flow of life and to become like a fish in the water or the clouds in the sky. This insight is essential to give depth to the Fusion Practices and balance attachment with detachment.



A: *Why don't you sit down, relax and let go of the weight and let me take you to the market.*



B: *Thank you for taking me to the market. I don't want to put too much weight on your car.*

Fig. 9.4 *Relax and let go.*

Major operation:

- craniotomy
- thoracotomy
- chest tube
- laparotomy
- peripheral vascular repair
- amputation above-elbow left
- amputation above-elbow right
- amputation below-elbow left
- amputation below-elbow right
- amputation above-knee left
- amputation above-knee right
- amputation below-knee left
- amputation below-knee right

Comments:

Please note:

This sample database is available as a downloadable spreadsheet file (Excel ®) on the accompanying DVD.

Chapter 6

THE CHAIN OF CASUALTY CARE

6. THE CHAIN OF CASUALTY CARE

6.1 The links: what kind of care, and where? 131
6.1.1 Protection: IHL 131
6.1.2 Levels and locations of medical care 132

6.2 Surgical hospital treating the war-wounded 133
6.2.1 Hospital A: rural hospital = basic trauma services 133
6.2.2 Hospital B: provincial hospital = advanced trauma services 133
6.2.3 Hospital C: major city hospital = comprehensive trauma services 133
6.2.4 Hospital assessment 133

6.3 Transport 134
6.3.1 Command, control and communications: coordination 134

6.4 Forward projection of resources 135

6.5 The reality: common war scenarios 136

6.6 Conflict preparedness and implementation 137

6.7 The pyramid of ICRC surgical programmes 138
6.7.1 Checklist 139

ANNEX 6. A Initial assessment of a surgical hospital treating the war-wounded 140

ANNEX 6. B Strategic assessment of a conflict scenario 146

ANNEX 6. C Humanitarian intervention for the wounded and sick: typical settings 148

6.1 The links: what kind of care, and where?

Modern armed conflict embraces classical war between conventional armies, urban combat between militias, and isolated and sporadic but fierce guerrilla attacks in remote rural areas. It may involve mass conflict or chronic irregular, low-intensity combat, or individual terrorist attacks. Civilians often represent the majority of victims (see Chapter 5). Field situations vary considerably, but basic medical problems for the wounded are universal. A system must be developed and adapted to deliver the best possible care in a timely manner, under all circumstances.

Modern armed conflict takes place in rural areas and cities.

Civilian populations are increasingly at risk.

Landmines and unexploded cluster munitions continue to cause victims after the conflict has ended.

Field situations vary; medical needs are universal.

The system of evacuation and treatment of the sick and wounded – the chain of casualty care – like any chain, is as strong as its weakest link. It is measured not in kilometres but in hours and days. The setting up of such a system requires planning ahead of time: an assessment of the tactical circumstances must be made; an analysis of the physical limitations and human resources carried out; and the resulting plan implemented.

Wounded patients are transferred along a chain of medical care, beginning with simple "life- and limb-saving" procedures and continuing to ever-greater levels of sophistication. The principle of echelons of care in a military system has been described in Chapter 1. In civilian practice patients also tend to follow a chain of evacuation and treatment although, in many countries, this is not very efficient.

6.1.1 Protection: IHL

Protection and prevention from further injury come first and foremost in patient care.

Article 3 common to the four Geneva Conventions and article 7 of Additional Protocol II:

The wounded and sick shall be collected and cared for.

The wounded and sick have the *right* to be cared for and to have access to appropriate medical care. The red cross, red crescent and red crystal emblems symbolize the legal protection afforded the casualty and the medical personnel, who have the right and the obligation to care for the wounded and sick. The protective quality of these emblems is a function of the training and degree of discipline of the combatant forces, and their adherence to internationally accepted norms of behaviour on the battlefield: the Geneva Conventions and their Additional Protocols. This protection begins with the first aider in the field and continues through all the levels of treatment.

Special measures must be taken to prevent further injury to any casualties and to protect them from the elements (see Chapter 7).

6.1.2 Levels and locations of medical care

The following list defines the generic places where the wounded receive different levels of medical care in the multiple-phase treatment of war wounds.

1. On the spot: first aid.
2. Collection point: first aid with/without resuscitation.
3. Intermediate stage: resuscitation with/without emergency surgery.
4. Surgical hospital: primary surgical treatment.
5. Specialized centre: definitive surgical treatment including reconstructive procedures; physiotherapy and rehabilitation, both physical and psychological.
6. Transport system for transfer from one echelon to another.

Treatment on the spot may be self- or "buddy"-treatment, or practised by a military medic or first aider. First aid starts at the point of wounding, but can be given anywhere and everywhere along the evacuation line to the place of definitive treatment. First aid is the only possible treatment on the battlefield.

The setting up of a collection point or clearing station may be a spontaneous response; alternatively, an established first-aid post (FAP), dispensary, or primary health centre might serve this purpose. Some FAP will be staffed by military stretcher-bearers and medics, others by Red Cross/Red Crescent volunteers, or other civilian personnel. The closer to the battlefield, the more prominent will be the role of military medical services. In purely civilian rural settings, village health workers, nurses or medical assistants are often the only health professionals available. Collecting the wounded at one specific location allows for the proper organization of field triage and their efficient evacuation. Besides basic first aid and trauma life support, resuscitative measures may be begun here.

A health centre or rural hospital might represent the intermediate stage, where more sophisticated resuscitation and emergency surgery are available. The military might establish a forward surgical unit.



B. Fjortoft / ICRC

Figure 6.1

National Society first aiders in the field.



J-P. Kolly / ICRC

Figure 6.2

First-aid post on the Afghan-Pakistani border.



J-J. Kurz / ICRC

Figure 6.3

Transfer of patients to the ICRC hospital in Peshawar, Pakistan.

6.2 Surgical hospital treating the war-wounded

The level of sophistication of hospital care will depend on the degree of socio-economic development within the country *before* conflict breaks out. War will then usually degrade the functioning of any pre-existing hospital. Efficient evacuation of the wounded to deficient surgical facilities is not an effective chain of casualty care.

Levels of hospital competency differ from country to country and between geographic regions. Three basic levels can be described.

M. Bleich / ICRC

Figure 6.4

ICRC field hospital, Lokichokio, Kenya.

6.2.1 Hospital A: rural hospital = basic trauma services

A district hospital (Africa) or primary health centre (South Asia) without full-time specialist doctors, especially without a fully-trained general surgeon, is a typical example. These hospitals are usually staffed by general practitioners or medical assistants with some surgical training and equipped with a minimum of proper surgical facilities. Front-line hospitals with "field surgeons" exist in some military medical services and are the equivalent. Basic resuscitation and some simple but critical operations are usually performed here.

6.2.2 Hospital B: provincial hospital = advanced trauma services

A regional hospital (Africa), district hospital (South Asia), or general hospital (Latin America) have a full-time general surgeon and proper operating theatre and sterilization facilities. Most life-threatening conditions can be dealt with adequately. The military equivalent is usually a forward field hospital specializing in damage control and resuscitative surgery.

6.2.3 Hospital C: major city hospital = comprehensive trauma services

This is a referral structure offering a broad range of specialties and sub-specialties and usually represents the highest level of care in the country or administrative region. It is often a teaching or university hospital. In military terms, this is a referral structure far from the front lines.

6.2.4 Hospital assessment

ICRC programmes aim to maintain, and upgrade if possible, the competencies of these different levels of hospital care when necessary. The ICRC has developed an analytical tool for assessing the quality of hospital management and surgical work prior to providing assistance. This tool comprises a number of factors to be considered. There are factors external to the hospital, involving an analysis of the national and provincial health systems, and internal factors: hospital infrastructure, administration and functional organization, departments, available resources, medical personnel (number and expertise), non-medical support services, finances (see Annex 6. A: Initial assessment of a surgical hospital treating the war-wounded).



Figure 6.5

Assessment of a surgical hospital caring for the war-wounded.



Figure 6.6

Assessment results of a typical hospital in a low-income country disorganized by war.



T. Gassmann / ICRC

Figure 6.7.1

National Society volunteers transporting patients by boat.



L. Petridis / ICRC

Figure 6.7.2

Airplane medical evacuation from southern Sudan to ICRC Lokichokio hospital.



T. Gassmann / ICRC

Figure 6.7.3

National Society "Zero Mobile" horse-drawn carriage ambulance.

The pie-charts above show the various factors that affect the functioning of a hospital dealing with the added burden of war-wounded patients compounded by the constraints of a weakened health system, and help identify dysfunctional areas. An additional factor is the emotionally stressful presence of casualties who are related to, or friends of, the medical staff.

6.3 Transport

Transport of some sort provides the connection between the different echelons of the chain of casualty care. Moving a patient has a price: transportation is a trauma in itself. It uses up additional resources and involves security risks ("mortality of the ambulance ride"), and perhaps even exposure to military activity. These extra costs must be weighed up against the likely benefits of moving the wounded. In many contexts, the availability of transport for the sick and wounded is almost a "luxury".

Moving wounded people is difficult, always takes longer than expected, adds to the trauma, and is often dangerous.

6.3.1 Command, control and communications: coordination

A chain of command is necessary to make the various echelons function correctly. A central command or dispatch centre will assume overall coordination (e.g. decisions about transfer/evacuation destinations, engagement of resources, etc.), and be responsible for contacts with related command levels of various authorities (e.g. armed forces, police, headquarters of the National Red Cross/Red Crescent Society, civil defence and national rescue service, etc.).

Circulation of information between the different levels is assured by some means of telecommunication – radio and mobile phones – if possible, or by other means (e.g. foot messengers) if not. Mobile telephone systems have a tendency to stop functioning – be turned off – during crises and armed conflict. The efficiency of the command and communication systems depends on strict observance of established procedures.

6.4 Forward projection of resources

Bringing more than basic first aid closer to the collection point is called "forward projection of resources". The availability of advanced procedures closer to the battlefield has many advantages. It allows quicker access to "life- and limb-saving" emergency measures, thus decreasing both mortality and morbidity. The need for potentially dangerous transport is reduced. The projection of resources applies particularly to treatment at the intermediate stage, but can be applied to any echelon in the chain.

> Forward projection of resources allows quicker access to life- and limb-saving measures.
>
> However, certain conditions must be met.

A number of factors limit the possibility to project resources.

1. Security (essential).
2. Human resources and expertise (essential).
3. Equipment (appropriate technology).
4. Supplies (appropriate).
5. Infrastructure (minimum requirements).
6. Possibility of onward evacuation.

When a front-line hospital is coming under bombardment, putting both patients and personnel at risk, there is little point in attempting more than first aid if evacuation to another facility is possible. On the other hand, a forward collection point may provide advanced treatment. Only a minimum of equipment is necessary for well-trained medics to perform endotracheal intubation or place a chest tube, and then quickly evacuate the patient. A secure building with adequate resources may be used as an intermediate stage where a forward surgical team may perform damage control and resuscitative surgical procedures.

All of these possibilities will depend on meeting the criteria defined above; but especially on *security and human expertise*. Infrastructure, equipment and supplies must all meet minimum requirements, and be appropriate to the task under the prevailing conditions.

> The most important factors determining the forward projection of medical care for the war-wounded are security and human expertise.

The appropriate choice of procedures to undertake for the injured outside a formal hospital setting will depend on the factors mentioned above, and will vary from country to country, and even from region to region within the same country.

The organization of any chain of casualty care for the war-wounded – military or civilian – should rely on a large dose of common sense to determine what is practical and what can realistically be accomplished to assure the best results for the greatest number, while at the same time guaranteeing the safety of the injured and the health workers. What exactly can be done for the injured outside a formal hospital setting will depend on the particular circumstances and means available. There is no dogma to be followed blindly; situations are different and improvisation and adaptation the key to success.

	On the spot	Collection point	Intermediate stage
Who ?	Family, friends, the community[1] Community health workers First aiders (Red Cross or Red Crescent, military stretcher-bearers and medics, combatants, etc.) Health professionals	Health professionals First aiders (Red Cross or Red Crescent, military stretcher-bearers and medics, combatants, etc.)	General practitioners, emergency room staff, other medical and surgical professionals Field surgical team
Where ?	In a combat zone, at the front lines	Spontaneously chosen (e.g. the shade of a tree) First-aid post Dispensary, primary health care centre	First-aid post, dispensary, primary healthcare centre, outpatient clinic Rural hospital Forward surgical hospital
What ?	Life-saving first-aid measures *The only appropriate care on the spot*	Collection of casualties Evaluation of their condition Advanced emergency care and/or stabilization Evacuation planning Routine care (fever, diarrhoea, scabies, etc.) and ambulatory care (pneumonia, non-combat trauma, etc.)	Advanced emergency care Forward life-saving surgery Occasional hospital care, although uncomplicated and requiring few days of observation Routine care (fever, diarrhoea, scabies, etc.) and ambulatory care (pneumonia, non-combat trauma, etc.)

Table 6.1 What can be done at which level?

6.5 The reality: common war scenarios

As mentioned in Chapter 1, there is more than one "surgery" for the care of the war-wounded. The exact number of levels of care and the path followed by casualties are determined on a case-by-case basis according to the sophistication of care and logistics available. In some armies or countries, the organization may be so efficient that a wounded soldier may expect to receive treatment virtually as sophisticated as the care available to him in peacetime.

In developing countries, however, the healthcare system might already be weak before the conflict and may almost cease to function because of it. Water and electricity supplies can be unreliable, trained staff often flee the area, drugs and disposable equipment cannot be replaced, budgets and salaries are not paid, and buildings are destroyed. The quality of hospital care is badly affected.

Every combination of levels of care is possible:

- the wounded from a modern industrialized army are transferred by helicopter from the scene of injury directly to a surgical hospital;
- patients in low-income countries reach health facilities on foot or by oxcart, donkey, private motor vehicle, taxi or lorry;
- during urban warfare, family and neighbours transport a casualty directly to the emergency room of a surgical hospital, which then serves as a collection point;
- in the rural areas of a low-income country, the hospital is the only health structure functioning and serves as all levels in one – forward referral of patients to a more sophisticated level of care is not available;
- rural health centres may flourish while surgical hospitals may exist only in large cities;
- a collection point or intermediate stage in a secure building is upgraded with the necessary equipment and personnel to serve as a forward surgical hospital, with or without possibility of forward referral.

In some contexts, the ICRC has resorted to deploying a Field Surgical Team that is not hospital based. This mobile team "goes to the wounded" rather than having the wounded come to a hospital; the chain of casualty care is turned upside-down. This

---

[1] In armed conflicts, under international humanitarian law, civilians are permitted to collect and care for the wounded and sick of whatever nationality, and shall not be penalized for doing so. On the contrary, they must be aided in this work. Furthermore, IHL prescribes that the civilian population shall respect the wounded and sick, even if they belong to the enemy, and shall commit no act of violence against them.

In the Taoist view, attachment and detachment are not to be seen as opposites, which exclude each other. What may be useful and functional in one stage of life, in one particular situation or moment, may well lose its functionality at another time. This explains why Taoists question the usefulness of externally induced and pre-arranged moral codes. Instead , they value, above all, self-cultivation in learning to act in harmony with what is inwardly experienced as genuine and truthful, because it is in tune with the universe in us.

The training in such an attitude in which one frees oneself from fixed rules imposed and determined from outside and one consults one's own body and inner feeling, creates both freedom and flexibility. It helps to avoid being trapped in positions which undermine the capacity to trust oneself, and at the same time raises self-esteem.

In the process of genuine self-reflection and the growth of self-awareness, you learn to look at yourself and your inner life from a distance and as a neutral witness, rather than as a judge. As a result, you grow into a spirit of inner freedom and you learn to look at yourself with a sense of relativity and even with a sense of humor. At the point you are able to truly smile at yourself and have reached the point you can forgive yourself, wisdom is dawning and the knots which you felt were in your way are in the process of dissolving, to create space for new and fresh energy.

Going with the Flow

This view on going with the flow in the universe and within yourself is also the basic principle underlying and inspiring the ancient Taoist arts of self defense. In Tai Chi no position is fixed and the body enters into a continuous flow of movements, as life is movement and in the movement to become one with the universe and its energies and forces one becomes invulnerable. The power gained in the martial arts is not an external but an internal one; it is generated by the process of alignment. It is this alignment through which the body is empowered from below and above and the power can flow from the center.

If you have no center, you can be easily pushed around. A person who is centered has an internal balance. He is more free from external influences and less fearful and suspicious of others, as has been necessary where casualties have not had access to medical care for reasons of personal security (Figures 1.4 and 6.8).

Techniques will also differ according to context. For the military, there is a balance between the needs of the wounded soldier and the necessities of combat. Some armed forces may teach the use of the self-applied tourniquet, which purportedly allows a wounded soldier to continue shooting. This logic does not apply to civilian institutions, and the ICRC's first-aid manual[2] proscribes the use of a tourniquet in the field except in very rare circumstances.

V. Louis / ICRC

Figure 6.8

The ICRC Field Surgical Team in Darfur.

6.6 Conflict preparedness and implementation

Every country should have a disaster plan. Part of emergency preparedness is the capacity to respond to a situation of armed conflict or internal troubles, as well as natural disasters. This is normal procedure for most armed forces. Ministries of public health and National Red Cross/Red Crescent Societies usually also have a disaster plan, which should be integrated into the national emergency preparedness programme.

> The objective of planning is to ensure that wounded people get the right care, at the right place, and at the right time.

Those who have to face the challenges of armed conflict should understand how to proceed in setting up a chain of casualty care. The best possible outcome for wounded people can only be achieved with proper planning and training. Plans must be realistic, flexible and reviewed regularly. Should a country be caught unawares at the outbreak of hostilities without having a pre-prepared plan, then the planning process must be accelerated and the necessary analysis take place immediately.

All plans begin with a *strategic assessment* of the possible conflict scenarios. What may happen and where? What needs are foreseen? What resources exist? (see Annex 6. B: Strategic assessment of a conflict scenario).

An *analysis of the assessment* will then answer the questions of what should be done, where, and by whom to improve the care for the wounded.

The reality check asks a few basic questions. Are the recommendations compatible with the context? Are they relevant? Practical? Reality checks are important; they influence planning, care, and training, and make certain that academic theory does not override simple pragmatism.

The organization of a chain of casualty care and in particular the assignment of resources (physical and human) to the different echelons must take into consideration a number of factors:

- the nature of the conflict, the tactical and geographic circumstances, and security concerns;
- the size of the casualty load;
- the quality of the casualty load, i.e. the types of injuries;
- the relative and proportionate number of human resources (surgical capacity depends on the number of teams working *and* the rate of arrival of casualties);
- the quality of human resources, i.e. expertise;
- logistics and supplies;
- the infrastructure.

---

[2] Giannou C, Bernes E. *First Aid in Armed Conflicts and Other Situations of Violence*. ICRC: Geneva; 2006.

Some typical situations of armed conflict and internal violence can be described. Model scenarios are then based on a consideration of the above-mentioned factors and the analytical tool of strategic assessment (see Annex 6. C: Humanitarian intervention for the wounded and sick: typical settings).

6.7 The pyramid of ICRC surgical programmes

ICRC delegates are often called upon to help organize a chain of casualty care. At times this will be in support of existing governmental or non-governmental structures. On occasion, the ICRC is required or asked to establish its own independently-run hospitals. The main reasons for doing so are either a question of protection – of the patients or the medical mission – or because of a dire shortage of local human resources.

Unlike a military field hospital, an independent ICRC hospital is often responsible for all levels of medical care. It acts as a first-aid post, field hospital, base hospital, and referral centre. In this, an ICRC hospital resembles many provincial hospitals in non-industrialized countries ravaged by war. The level of care is a combination of advanced and comprehensive trauma services. Only general surgeons are present, and no further referral of patients to a specialized centre is possible.

An independent ICRC hospital comprises all echelons in one structure.

In both instances – support to national structures or establishment of an ICRC hospital – a number of factors are taken into consideration to ensure the neutrality and independence of ICRC activities on the one hand, and the quality and professionalism of care on the other. The same logic applies to other humanitarian agencies. These factors are summarized in the following pyramid and checklist (Figure 6.9 and Section 6.7.1).

Figure 6.9

The ICRC surgical pyramid.


Surgery
Expertise
Expatriate & local staff
Infrastructure
Shelter, food & bed
Water, sanitation & energy
Telecommunications
Support personnel
Pre-hospital care
Evacuation
First aid
Transportation
Protection
Access security
Perception of ICRC
Neutrality & impartiality

6.7.1 Checklist

Political and operational considerations

- Perception of neutrality and impartiality, i.e. ICRC image.
- Acceptability of ICRC by political factions, the military, and the population.
- Possibility for negotiations: availability and access to interlocutors (health, defence, foreign affairs, and interior ministries, faction chiefs); contacts with owners of facilities to be rented.
- Role of the hospital in the protection of hospitalized patients.
- Role of the hospital in protecting the medical mission by providing access to neutral medical care, across enemy lines if necessary.
- Any possible competition with other health structures, private or public, i.e. "medical market".

Security

- Hospital and staff security concerns owing to the conflict or possible developments in the fighting:
  - location and environment, i.e. distance from hostilities or military targets;
  - type of building, i.e. number of storeys, ground floor, underground cellar or bomb shelter, tents.
- Incidence of banditry, hostage-taking, etc.
- Patients' safety, inside the hospital and upon discharge.

Access

- Distance and evacuation time.
- Availability of means of transportation: roads, vehicles, air evacuation.
- Safety of roads and checkpoints: military activity, political affiliation, banditry.
- Possibility of setting up a system of first-aid posts.
- Logistics: medical supply, fuel, food (local, regional, from ICRC headquarters).

Infrastructure

- Pre-existing hospital structure.
- Building capable of being transformed into a hospital (school, factory); structural integrity, possibility of expansion.
- Use of tents, prefabricated and/or temporary structures.
- Water and sanitation, electricity.
- Facilities: kitchen, laundry, residence for personnel.
- Warehouse.

Local and expatriate personnel

- Availability and number of local and expatriate Red Cross/Red Crescent medical personnel.
- Recruitment of new national staff and the question of neutrality.
- Professional competence and level of education.
- Language problems: need for translators.
- Availability of support personnel: ICRC delegates, medical and general administration, water and sanitation engineer, builder, mechanic, electrician, etc.

ANNEX 6. A Initial assessment of a surgical hospital treating the war-wounded

This form should be regarded as a guide, a kind of checklist, to help the health professional responsible for the assessment of the hospital remember certain key points.

Its purpose is to have a quick overview and understanding of the functioning of the hospital; to identify its capacity, limits and insufficiencies. It should allow for rapid and adequate decisions about the kind of *support* the hospital might need.

The form can be used *in toto* or in part according to the objectives of the assessment. It consists of questions deliberately left open to allow the health professional in charge to decide to enquire further or not according to the results expected. It is more important to try to get a correct understanding of how the hospital is working rather than to have exact figures.

The assessment is divided into six sections

General

Management and administration (including non-medical support services)

Medical support services

Clinical services *(only the surgical component is dealt with in this annex)*

Further comments

Conclusion

General

Name of the hospital: Town: Country:

Assessment done by:

Date:

Interlocutors:

1. Type (MoPH, private, military, missionary, NGO, others):
2. Catchment population:
3. Assistance from others than the authority in charge:
4. Level of reference (rural, district, regional):
5. If rural or district hospital, number of primary facilities served (first-aid posts, dispensaries, health centres):
6. Possibilities for further referral:
7. Transport system for patients (in and out):
8. Reputation of the hospital (indicate source of information):
9. Bed capacity, effective number of beds (breakdown by department):
10. Present bed occupancy:
11. Activities including specialities (surgery, medicine, paediatric, obstetric, specialized services, etc.):
12. Security (Is the area safe? Is the hospital secured? i.e. clearly marked, fenced, watchmen present, absence of arms inside the hospital compound?):
13. Endemic diseases and epidemic risk in the region:

Management & administration

I General management

1. Set-up (management team/board):
2. How are decisions taken and implemented?

II Human resources management

1. Who is in charge?
2. Does the staff receive salary/incentives?
3. Total number of personnel/breakdown by function (MD, medical assistants, nurses, students, etc.):
4. Is there a roster system in place in the hospital?

III Financial management

1. Management of finance (Is there a budget? How is the hospital financed?):
2. Is there any cost participation, "cost-recovery system"? Do the destitute have access to care?

IV Statistics

1. Management of statistics and reporting:
2. Are statistics available?
3. Is there an annual report?
4. Are there people specifically in charge of collecting data?

V Infrastructure & utilities (general condition of):

1. Wall and roof:
2. Water (running water, wells, safety of water supply, etc.):
3. Sanitation (type of toilets, etc.):
4. Electricity and/or generator (number of hours per day, fuel supply, etc.):
5. Heating/fans/air-conditioning:
6. Maintenance team (number, composition, etc.). Is there a maintenance schedule?
7. Is there a functioning workshop?

VI Waste disposal

1. Waste management systems (including toxics such as X-ray developer/fixator, etc.):
2. Incinerator (type, condition, etc.):

VII Non-medical support services

1. Kitchen (staff, nutritionist, origin of food, number of meals served per day, special diets, etc.):
2. Laundry (staff, washing by hand, machine, supplies, etc.):
3. Tailor (staff, supplies, etc.):
4. Cleaning and hygiene (system, staff, supplies, etc.):
5. Morgue (infrastructure, management, etc.):

Medical support services

I Pharmacy

1. Pharmacy staff and management:
2. Is there a standard list of medicines?
3. Are stock cards used?
4. Where do the drugs and medical equipment come from (regular supplier, local market, donations, etc.)?
5. Is there a reliable system of communication between the pharmacy and the wards (request forms, delivery forms, etc.)?
6. Did the pharmacy run out of basic drugs last month (penicillin, anti-malaria, paracetamol, ORS)?
7. What are the storage conditions (air-conditioning, refrigerator, etc.)?
8. Is medical equipment regularly maintained and serviced?

II Laboratory

1. Laboratory staff and management:
2. Tests available (haematology, chemistry, parasitology, bacteriology, serology, etc.):
3. Source of supplies:
4. Is there a reliable system of communication between the laboratory and the wards (request and results forms)?
5. Quality of the working relationship between the clinical and laboratory staff:

III Blood transfusion

1. Staff and management:
2. Policy of blood sampling and transfusion: HIV/AIDS policy?
3. Indications for blood transfusion/average number of requests:
4. How are the blood units kept? Is there a functioning refrigerator to store the blood?
5. Testing process and quality control:

IV Imaging (X-ray & ultrasound)

1. Staff and management:
2. Average number of X-rays per day:
3. Type and quality of machine:
4. Are there guidelines for the prescription of X-rays?
5. Is more sophisticated imaging equipment available?

V Other diagnostic services

1. ECG, EEG, etc.:

Clinical services

I Outpatient department (OPD)

1. Role of the OPD (consultation, follow-up of patients, admission, emergency):
2. Are there specialized OPDs?
3. Are there criteria to admit the patient to the OPD?
4. Is there a register with data about all patients seen every day?
5. Average number of cases seen every day (medicine, paediatric, surgery, obstetric, etc.):
6. Personnel in charge (MD, medical assistants, nurses):
7. Is there a clear roster?
8. Opening days and hours:
9. Main pathologies:
10. Access to laboratory and imaging:

II Admission/emergency department

1. Number of beds:
2. Is there a team on duty 24 hours a day; composition of the team?
3. Is there an on-call system in place?
4. Is there an admission book or regular procedure for admitting and registering patients?
5. Is there a regular procedure to send patients to the appropriate wards or to the OT?
6. Number and type of emergencies per day:
7. Are basic supplies and equipment available?

III Operating theatre (OT) and anaesthesia

1. Staff and roster:
2. Hygiene of the OT:
3. Is there an accurate operation book? If yes, number of surgical operations in the last month:
4. What kind of surgery is performed?
5. What kind of instruments and sets are available (laparotomy, caesarean section, debridement, skeletal traction sets, etc.)?
6. Number of operating rooms, tables:
7. Surgical linen (availability and source of provision):
8. Functioning surgical equipment (lamps, suction, diathermy, oxygen, etc.):
9. Source of materials and consumables:

IV Sterilization

1. Staff and roster:
2. Equipment (autoclaves, dry ovens):
3. Protocols in place?

V Anaesthesia

1. Staff and roster (MD and/or anaesthetist nurses):
2. Is a laparotomy performed safely with full muscle relaxation (including endotracheal intubation) by a trained anaesthetist?

3. Common anaesthesia (gas, ketamine, spinal, local):
4. Type of anaesthesia machines:
5. Availability of other equipment (pulse oxymeters, oxygen supply, etc.):

VI Nursing care

1. Is there 24-hour nursing supervision in the wards?
2. Are the patient records complete?
3. Is the nursing handover book used properly?
4. Are drugs administered on time?
5. Is a laparotomy performed safely with the patient supervised (vital signs) for 24 hours post-operatively in a room with light, and where he or she receives intravenous fluids and antibiotics?
6. What do dressings look like (clean, smelly, etc.)?
7. Are bedsores a problem?
8. Are relatives involved in patient care?

VII Frequently asked questions

1. Availability of mosquito nets for all beds:
2. Is there an admission book or regular procedure for admitting and registering patients in the ward? If yes, number of admissions to the ward in the last month?
3. Is there a person in charge of the admissions who controls a system whereby the patients are assessed and then go to the OT or receive treatment?
4. Are new admissions systematically seen by a senior surgeon/MD and within what timeframe?
5. Are there regular rounds in the wards and/or regular meetings to discuss the cases?
6. Are the diagnosis and treatment clearly formulated in the patients' files and the treatment copied onto the patients' charts?

VIII Surgical care

1. Main pathologies present in the wards (fractures, burns, chest, abdomen, etc.):
2. Management of the ward/hygiene:
3. Human resources (number, composition, roster):
4. Infrastructure and beds:
5. Is a laparotomy performed safely – patients seen a few days after operation with healing wound and eating normally?
6. Can five or more laparotomies be performed in 24 hours under good conditions including anaesthesia? If not, why?
7. What type of orthopaedic treatment is present in the surgical wards (POP, skeletal traction, external or internal fixation)?
8. What do the wounds present in the ward look like (clean, dirty, smelly, pus)?

IX Physiotherapy unit

1. Are patients walking on crutches in the wards? If not, why?
2. Management of physiotherapy department:
3. Human resources:

Further comments

1. Particularities of the context:
2. Do you have any requests for the ICRC (logic and rationality of the request)?

Conclusion

1. First general impression (cleanliness and hygiene, staff present, presence of patients):
2. Main positive findings:
3. Main negative findings:
4. Capacity to cope with mass influx of wounded:
5. Emergency/contingency plan:
6. Proposals:
7. Next step:

Please note:

This sample form may be photocopied and is also available as a downloadable document on the accompanying DVD.

ANNEX 6. B Strategic assessment of a conflict scenario

The main appraisals in a strategic assessment of a conflict situation in order to determine some of the factors influencing the chain of casualty care are the following:

1. Geography:
    a. topography of the conflict area
    b. routes of communication and transportation
    c. distribution of medical facilities available and their safety
2. Where is the fighting taking place? Safe areas, dangerous areas?
3. Where do patients come from?
4. How many wounded are there?
5. Who are the wounded?
    a. trained soldiers in a regular army
    b. guerrilla fighters, militiamen
    c. civilians
6. Who performs first aid, if anyone?
    a. National Red Cross/Red Crescent Society volunteers
    b. military services
    c. trained civilians (RC/RC community-based first aid, MoPH)
    d. untrained civilians
    e. non-governmental organizations
7. Assessment of efficiency of first-aid system
8. How are the wounded transported from point of wounding to hospital?
    a. private means
    b. public transportation
    c. ambulance service
    d. military services: air, land, etc.
9. Assessment of efficiency of evacuation system
10. Which hospitals receive the wounded ?
11. Assessment of work performed in hospitals and their capacity to receive and treat patients (see Annex 6. A: Initial assessment of a surgical hospital treating the war-wounded).

he is in tune with himself and the universe. Therefore the fusion practice may be called an internal kind of martial arts by which one learns to playfully bring into balance one's opposites so that a sense of being centered and in harmony arises and thereby self-confidence manifests.



Fig. 9.5 *Balanced, going with the flow*

It should be obvious that the practice of these arts may be most helpful, as they may help you to remember to go with the flow inside yourself and become inwardly soft and flexible. Like all true Chi Kung, the art of moving the Chi and with the Chi, outer flexibility comes from inner relaxation. Only when relaxation deeply enters the body, can it become truly receptive for the energy within and from outside. The same goes for Tai Chi.

In that sense the Fusion Practices may also be seen as an inner play in which you invite your organs as your children to play with each other and see how they can balance and support each other. It may also be compared with an ancient game, which is played by children and adults in different countries in Asia. In Thailand it is called Takara in which the players help each other in keeping the light bamboo ball in the air so that the play can continue. Nobody loses, nobody gains. All share in the joy of the game and in the process train their own ability and help the others to enhance theirs.

Central to the Taoist tradition is that the body expresses and balances both heaven and earth. How could it receive the energies of heaven and earth and become an expression of the universe, if it were not open and flexible and receptive? This explains the crucial role of Chi Kung and the various schools and forms which have been created over the ages, so as to make the body a vessel. As the *Tao Te Ching* says: the function of the vessel is to be empty so that it can be filled.

12. Which other actors are present in the area?
    - a. National Red Cross/Red Crescent Society
    - b. ministry of public health
    - c. military medical services
    - d. national non-governmental organizations
    - e. missionary clinics or hospitals
    - f. foreign non-governmental organizations

On the basis of the above assessment, the military or civilian health services or National Red Cross/Red Crescent Society should take action to fill in any gaps by creating the following facilities.

1. System of first-aid posts.

2. Transport system.

3. Reliable surgical units: central, regional, zonal, local; alternative sites for hospitals; convalescence houses.

The above-mentioned institutions have several means of intervention to face the challenge of establishing an efficient chain of casualty care.

1. Negotiation with the various belligerents to make sure international humanitarian law is respected in order to ensure that:
    - a. medical personnel has access to the wounded and sick;
    - b. the wounded and sick can reach medical care;
    - c. first-aid and health personnel and structures are safe.

2. Support to existing health structures, which may take the form of infrastructure renovation, equipment, medical supplies, or re-enforcement with human resources.

3. Mobilization of local infrastructure and human resources to improve the chain of casualty care or project forward medical care for the wounded.

4. Mobilization of international agencies to supplement national efforts.

Please note:

Points 1 – 12 of this sample form are available as a downloadable document on the accompanying DVD.

ANNEX 6. C Humanitarian intervention for the wounded and sick: typical settings

Many factors affect the deployment of humanitarian medical teams: this Annex helps to analyse a number of them. The terminology used is an operational description and has no legal significance.

Possible scenarios

1. Military activity, natural disaster or major accident? (Is health infrastructure intact?)
2. Military context: classical front lines, guerrilla war, internal troubles, post-conflict (particularly the presence of landmines, cluster bombs and other unexploded ordnance)
3. Urban or rural setting?
4. Industrially-developed or low-income country: funds available?
5. Human resources: trained doctors, nurses, and first aiders in sufficient, limited numbers, or very few?

Three typical general settings for a humanitarian intervention exist.

1. **Optimal situation:**
   adequate access to medical care in spite of the violence and conflict.
2. **Austere situation:**
   poverty before the conflict has already jeopardized access to care.
3. **Dire situation:**
   very poor access to care because of the violence and conflict, sometimes compounded with pre-existing poverty.

	OPTIMAL	AUSTERE	DIRE
Location	Urban in a developed country	Poor rural area	Developing country Major destruction
Duration of trouble	Single, isolated event (e.g. act of terrorism)	Ongoing low-intensity fighting (e.g. guerrilla warfare)	Continuous heavy fighting and/or bombardment
Casualty flow	Small irregular numbers (compared to the population of the city)	Discontinuous/ intermittent flow, including massive influx	Continuous but unpredictable flow, including massive influx
Infrastructure (roads, ambulance service, health facilities)	Intact and functioning	Poor or irregular (e.g. few good roads, hospitals lacking supplies)	Severely damaged or dysfunctional (roads damaged, debris in streets, hospitals looted, etc.)
Communications	Good	Poor to moderate Irregular	None or poor
Personnel	Adequate (in number and skills)	Variable	Minimum available or complete lack
Materials and supplies	Adequate (in quantity and quality)	Irregular and inadequate	Irregular supply or non-existent
Environment	Good (daytime, good weather)	Harsh	Bleak (night, cold, heat, etc.)
Evacuation	Safe and short	Predictable but long and arduous	Uncertain or unknown
Destination of transfers	Known and available	Known but variable	Unknown or absent

Types of situations of armed conflict and violence and their effects on humanitarian medical work[3]

Example	International armed conflict	Internal armed conflict/ guerrilla warfare	Civil disturbance/revolt	Widespread banditry and other crime
Description	A straightforward war between country X, and its allies, and country Y, and its allies	Intense fighting within one country	Unpredictable; hit and run skirmishes, often with a vested interest in the continuation of anarchy	May coincide with any of the other situations
Combatants/ Fighters	Easily visible, and wearing distinctive uniforms	Not all wear uniforms Government forces opposing well-organized military groups	Armed individuals, gangs, bandits, and militia groups	Purely self-interested individuals or groups
Front lines	Well known	May not exist, or may change very quickly	Linked to constantly shifting alliances among or between forces	At the fringes of the conflict, combatants ready to take advantage of circumstances
Chain of command	Structured and with available points of contact	Tenuous points of contact on the opposing sides.	Not clear, and variable from one faction to another (often based on an individual leader surrounded by a small group and supported by part of the population)	Traditional and local leader, personalized (e.g. street gangs)
Respect for IHL	Parties aware of their obligations and try to meet them	A certain degree of respect	Very little, with a complete breakdown of law and order	IHL unknown or no regard for, or both
Humanitarian tasks	Classic	Classic	Extremely difficult	?
Risk level	Low	Growing and less predictable	Very high, perhaps bordering on the unacceptable	Very real and very dangerous threat
Obstacles to medical work	Few, if any	More restrictions, negotiations, controls and delays, etc.	Severely restricted ability to intervene – vehicles, radios, goods, etc. are extremely attractive to the warring parties	Numerous: greatest caution required

Model scenarios

In contemporary armed conflict, health staff and structures are called upon to function in various scenarios: typical ones include the following.

1. Safe urban setting

- Urban, developed environment
- Single, isolated event
- Casualty numbers relatively small compared to population of city
- Infrastructure intact: roads, emergency vehicles
- Health infrastructure intact, sophisticated hospitals
- Short evacuation time: route is secure
- Good communications
- Personnel: adequate number and quality of trained health staff
- Materials adequate
- Environment good: weather, daytime

---

[3] The terminology used is an operational description, not a legal one.

- Final destination of the wounded is known

2. Unsafe urban setting

- Low-income country: under-developed or destroyed urban setting
- Continuing danger: street fighting and bombardment in city
- Continuing and unpredictable casualty flow including massive influx of wounded
- Poor infrastructure: potholed roads, debris in streets
- Disrupted health infrastructure: hospitals damaged or looted
- Availability and length of evacuation uncertain or unknown
- No or poor communications
- Minimum health personnel available
- Material re-supply uncertain, irregular, or non-existent
- Environment poor: cold, wet, dark
- Final destination of the wounded not always obvious

3. Unsafe rural setting

- Low-income country: under-developed rural area neglected in peacetime
- Constant danger: ongoing combat, landmines
- Continuing and unpredictable casualty flow
- Poor infrastructure: badly maintained or no roads
- Poor health infrastructure: few health posts, even fewer district hospitals
- Availability and length of evacuation uncertain, long and arduous
- No or poor communications
- Minimum health personnel available
- Material re-supply uncertain, irregular, or non-existent
- Environment poor: extreme cold or heat, rainy season and dry season
- Final destination of the wounded not always obvious

4. Safe but austere setting

- Low-income country
- Continuing danger: ongoing low-intensity warfare
- Discontinuous casualty flow; includes irregular mass evacuations
- Poor infrastructure: few good roads and few vehicles
- Minimum of health infrastructure: some rural clinics or health centres, fewer district hospitals
- Evacuation predictable but long and arduous
- Poor to moderate communications
- Minimum to moderate number of health personnel available
- Minimum material re-supply
- Environment harsh
- Final destination of the wounded: distant, but known

Chapter 7

FIRST AID IN ARMED CONFLICT

7. FIRST AID IN ARMED CONFLICT

7.1 First aid: its crucial importance 155

7.2 First aid in the chain of casualty care 156

7.3 First aiders: an important human resource 157

7.4 Essential elements of the first-aid approach and techniques 157
7.4.1 Security first and always 157
7.4.2 Basic actions 158

7.5 Setting up a first-aid post 159
7.5.1 Location 159
7.5.2 Infrastructure 159
7.5.3 Staffing, equipment and supplies 160
7.5.4 Organization 160

7.6 ICRC involvement in first-aid programmes 161

7.7 Debates, controversies and misunderstandings 161
7.7.1 "Scoop-and-run" *versus* "stay-and-treat" 161
7.7.2 Mechanism of injury and the problem of the cervical spine 162
7.7.3 ABCDE or C-ABCDE? 163
7.7.4 The tourniquet: when and how? 163
7.7.5 Resuscitation or rehydration? 164
7.7.6 Supplemental oxygen in the field? 164
7.7.7 Disability: the AVPU system 165
7.7.8 Evacuation: a risk to take 165

7.1 First aid: its crucial importance

Optimal management of the injured involves a continuum of care from the point of wounding to the surgical hospital: the chain of casualty care. The surgeon wishes to receive patients who arrive in good condition and well-stabilized, in a timely manner, and according to priority for treatment. To understand how this is achieved, or not, there are a number of things that need to be known about first aid. In addition, the surgeon working in a conflict area may well be called upon to participate in the training of first aiders to achieve a more efficient chain of casualty care.

First aid is the initial assistance given to an injured or sick person until the condition of the person is stabilized or remedied, or professional medical help is made available. How first aid is applied varies according to the security environment, the number and condition of the wounded in a particular location, the resources that can be mobilized for care, transport, and access to surgical hospitals and the latter's capacity to receive and treat patients.

Since its foundation, the International Red Cross and Red Crescent Movement has been, and continues to be, predominantly associated with the provision of first aid. It pioneered the concept of immediate response by first aiders and local communities to the consequences of war, disasters and epidemics.

The goals of a first aider in action are:
- to preserve life through the support of vital functions;
- to intervene securely and safely;
- to limit the effect of injury and to prevent further injury;
- to prevent complications and disability;
- to alleviate suffering and to provide psychological/moral support;
- to promote recovery;
- to ensure proper handover of the injured and sick to healthcare professionals when needed.

First aiders can also help mobilize their community to prepare for and respond to emergencies that happen in everyday life and during crises such as armed conflict.

Experience has shown that one of the most important factors determining the outcome of the management of the war-wounded is the pre-hospital phase. First aid saves lives and decreases morbidity. It also results in easier surgery, thus decreasing the hospital surgical burden. Furthermore, up to 40 – 60 % of the civilians and soldiers wounded during armed conflict do not require hospitalization. First aid measures – plus a simple oral antibiotic and analgesic – constitute all the treatment they need. Military terminology calls them "returned to duty" (see Chapter 5).

First aid, begun early, saves lives and can prevent many complications and much disability.

The provision of first aid is one of the fundamental responsibilities of military medical services, National Red Cross and Red Crescent Societies and, increasingly in contemporary armed conflict, of medical staff in both urban and rural public hospitals. The essential role of local communities in providing assistance on the spot should not be forgotten, as Henry Dunant, founder of the Red Cross and inspiration behind the Geneva Conventions, witnessed after the battle of Solferino on 24 June 1859.[1]

---

[1] See Henry Dunant. *A Memory of Solferino*. ICRC: Geneva; 1986.

Consequently, basic first aid, initial and refresher training, should be supported among:
- the general population;
- soldiers and members of security forces;
- community healthcare workers;
- military and other medical staff (nurses, doctors and surgeons).

Commanders do not appreciate seeing their troop levels decrease when healthy uninjured soldiers are involved in transferring their own wounded because first-aid services are inadequate in the field. The fighting capacity is then doubly reduced.

Advanced competencies can be added to the training curriculum of those specially dedicated to providing first-aid services in the field, such as military medics and the first-aid teams of the National Red Cross and Red Crescent Societies, as a forward projection of resources.

7.2 First aid in the chain of casualty care

First aid starts at the point of wounding, but can be given anywhere and everywhere along the chain of casualty care to the place of definitive treatment.

Point of wounding
On-the-spot first aid, performed in the field and often on the actual battlefield: this may be self- or "buddy-" first aid if combatants have received the proper training prior to deployment. Otherwise, it is practised by a military medic, civilian or Red Cross/Red Crescent first aider.

Collection point
It is common practice and convenient to bring all the wounded to one spot, depending on the tactical situation, to evaluate their condition, start first aid if it has not yet been given, and stabilize those for whom lifesaving measures have already been undertaken; and then to decide who needs to be evacuated for further treatment according to triage priorities. This is best served by a first-aid post (FAP).

Evacuation
The decision to transport a casualty should be assessed carefully considering the dangers and difficulties inherent in situations of armed conflict. Whatever method of transport is used along the chain of casualty care, first-aid measures should be maintained throughout.

Hospital emergency room
In the rural areas of a poor country and during urban warfare, the first site where any care is available is often the emergency reception of an established hospital. Even if there is an efficient emergency transport service, family and neighbours often do not wait for it and prefer to transport the wounded directly to the hospital, whose emergency room (ER) then serves as a first-aid post.

The degree of development and sophistication of the emergency transport and emergency medical services in a given country will determine what level of first aid and triage are performed "in the field" and what occurs only in a healthcare facility.

First aid can be performed everywhere and anywhere along the chain of casualty care.

Even in armed conflicts, ordinary life goes on. There is no let-up in road traffic crashes, accidents, or diseases among the local population, as well as combatants. The efficient work of first aiders is as necessary as usual.

Secret of Breathing and Relaxation

The essential role of the quality of breathing in all the practices is to enhance detoxification and cleansing, to create new space and openness towards the universe (in the exhale) and to fill the body with new energies and forces, by receiving, enriching and transforming Chi (the life or vital force). Breathing is central to the Taoist practice.

Changes in the quality of breathing from a short, superficial and agitated breath in the upper part of the body to a long, deep and quiet breath in the lower center/ Tan Tien of the body are crucial to the process of inner transformation. This is so because breathing is the bridge between consciousness and the body, and in the breathing process both the body and our awareness change.

The quality of breathing plays a crucial role in the processing and transformation of emotions which is a central theme in the Fusion Practices through the transformation of negative into positive emotions (Fusion of the Five Elements) and the cultivation of positive emotions (Cosmic Fusion). The emphasis in Taoist practice on self-healing is intimately related to the growth of self-awareness with regard to one's pattern of breathing as this determines the ability to regulate, control and balance emotions.

The Inner Smile practice as well as the Healing Sounds practice, designed to balance the negative and positive properties of the organs, are essential as a preparatory practice to the Fusion Practice.



Fig. 9.6 *Smile to the Lungs.*

7.3 First aiders: an important human resource

Usually first aiders are organized in teams with proper supervision and equipment, such as those of the Red Cross or Red Crescent or of the military. Civilian and Red Cross/ Red Crescent first aiders are an essential part of the healthcare team given that they are members of the local community, reflect its characteristics, and are well accepted by society. They take on many roles from the front lines to the healthcare facility; their availability and versatility are respected.

Therefore, it is important to respect their knowledge, and appreciate their courage and dedication. They have important rights and duties according to international humanitarian law, and should be trained accordingly. They should also be trained in the methods and practice of triage. Not only is it important to welcome them when they bring in a casualty but also to give them feedback on the measures they have taken and on the evolution of the casualties they have already brought in, to ensure a proper handover of the patient and prepare for future work. The surgeon plays a vital role in this communication with first aiders.

First aiders are often volunteers and an essential part of the healthcare team, and should be appreciated accordingly.

The presence of first aiders before, during and after emergencies helps rekindle the humanitarian spirit of individuals and communities, inspiring tolerance and ultimately building healthier and safer living environments.

7.4 Essential elements of the first-aid approach and techniques

7.4.1 Security first and always

One of the specific characteristics of armed conflict, as mentioned, is the particularly hazardous situations encountered, more dangerous than during natural catastrophes or industrial accidents. The situation is made even worse because of the will of combatants to continue fighting and inflict harm after the initial damage has been done, and the increasing unwillingness of many combatants to recognize and obey the rules of armed conflict.

First aiders are exposed and at great risk, or are at times even targeted in an ambush or a gun battle. All too often, when a bomb explodes or is dropped there is a rush of first-aid rescuers to the site; a second bomb goes off a short time later causing far more casualties than the first. Furthermore, the work space may be limited by an excited and angry crowd of bystanders and the casualties' friends, relatives and comrades, who may threaten first aiders.

The point of wounding is, by definition, a very dangerous and chaotic place.

This entails practical consequences for the first aider and imposes necessary constraints for the safety of patient and first aider alike. A wounded first aider needs help and cannot help others. The question of first-aid care under fire – for military personnel – will depend on the doctrine and training of each army.

As previously stated, the sick and wounded benefit from protection and the first aider has rights and responsibilities according to international humanitarian law. An opportunity to provide care more safely may be created by negotiations or a ceasefire. The military may choose to remove the threat or provide security by armed force. This does not mean first aiders need not take security measures prior to engagement in the field. Circumstances determine how and when care can be provided with acceptable risk.

The benefits of caring for the wounded must always be weighed against the risk of first aiders themselves being wounded.

An absence or limitation of transportation and the impossibility of deploying personnel in the field to perform first aid because of political or security constraints – all too often the case in the circumstances where the ICRC works – will cause some patients who might otherwise have survived to die, and surviving patients to have established infections and other complications which lower their subsequent chances of quality survival. The challenge is how to deploy and organize the necessary first-aid personnel, material, and equipment in the field. For the military, this is also a challenge but has a different connotation. Tactical considerations may mean that soldiers must "win" the firefight before treating or evacuating the wounded.

7.4.2 Basic actions

The basics of a routine first-aid deployment apply, while at the same time safety and security *must be* ensured.

Preventing further injury: removing casualties from danger
A wounded person is more likely to be injured again or even killed, especially if the person cannot take measures of self-protection, such as seeking cover from shooting or bombing. The prevention of further injury thus involves removing casualties from the point of wounding, and putting patients and medical personnel in as safe a place as circumstances allow. Furthermore, conscious and walking wounded must be separated from the others as a matter of scene security management, as well as triage.

Preventing aggravation of the injury: sheltering the casualties
Shelter offers some protection from further injury in a combat environment, and also provides a shield from the elements. Exposure to the sun and heat, or cold and rain, are deleterious to the wellbeing and stabilization of the injured. It is also easier and more efficient to deliver medical care when working under more comfortable physical conditions.

Performing the standard sequence of basic life support

1. ABCDE sequence leading to immediate life-saving measures.
2. Complete examination leading to stabilization measures.
3. Additional measures:
   - keeping the casualty warm;
   - ensuring proper rehydration;
   - providing psychological support.
4. Monitoring of the casualty's condition and the efficiency of the measures taken.

A = Airway

B = Breathing

C = Circulation

D = Disability (neurological status)

E = Environment and Exposure

Protection of the casualty, prevention of further injury, and lifesaving and stabilization measures are the fundamental responsibilities of the first aider in the field.

The analysis of the trimodal distribution of deaths in Chapter 5 demonstrated that first-aid measures in the first instance should specifically target those injuries that are severe but potentially survivable. Thus, the primary objectives of immediate life-saving measures are the following.

1. Establish and maintain an adequate open airway.
2. Maintain breathing.
3. Maintain circulation by controlling peripheral haemorrhage and reducing or preventing shock.

In the second instance, first-aid measures target the great majority of casualties: those who suffer fractures and soft-tissue injuries, which may cause disability.

The patient must be exposed in order to perform a correct and complete examination. Cultural and religious constraints, as well as the tactical situation, may impose limits as to how much a casualty may be undressed in the field.

All injured persons who have bled lose body heat, even in the tropics. It is important to avoid hypothermia, which can have disastrous results later in terms of coagulopathy (see Chapter 18). Casualties should be covered with a simple sheet or blanket, depending on the prevailing climate, without forgetting to put something *under* the patient since much body heat is dissipated into the ground.

National and institutional guidelines will establish the protocols for the level of treatment (i.v. fluids, antibiotics, analgesia, endotracheal intubation, etc.) that are implemented in any first-aid programme.

> Simple life-saving procedures in the field – immediate life-saving measures – take precedence over more complex techniques and are based on the well-known priorities of the ABCDE system.

7.5 Setting up a first-aid post

The establishment and organization of a first-aid post should rely on a large dose of common sense to determine what is practical and realistic in a given situation, and will depend on how long it will operate (from a few minutes to a few days or weeks).

7.5.1 Location

Choosing a site for an FAP should follow certain rules. It should be placed in a secure position, far enough from the fighting not to be in danger, yet near enough to enable the rapid transfer of casualties to the post. For operational and security reasons, its location should be indicated as soon as possible to the dispatch or command centre of the chain of casualty care. Its presence should be made known to the local population and combatants, who are the potential beneficiaries of its services. A prominently displayed distinctive emblem (a red cross, red crescent or red crystal) large enough to be seen from all directions and from as far as possible helps to identify the FAP and provide protection under IHL.

> Security and protection of casualties and first aiders are the primary considerations for setting up a first-aid post.

7.5.2 Infrastructure

An FAP is a functional unit: it can therefore be set up in a makeshift fashion under a tent, in a school, or any available building; or in an already existing dispensary or primary healthcare centre. Certain minimum requirements should be fulfilled: appropriate shelter against the elements; adequate size to accommodate casualties on stretchers; easy access for the "walking wounded" (e.g. avoid long stairways); and adequate in-and-out access for ambulances, and ample parking space.



ICRC

Figure 7.1.1

First-aid post: formal.



T. Gassmann / ICRC

Figure 7.1.2

First-aid post: ad hoc.

7.5.3 Staffing, equipment and supplies

The level of technical expertise of the personnel in an FAP will depend on the circumstances and standards of the country. Anyone from a first aider to a nurse, general practitioner or even a surgeon may be found working in an FAP. This allows for the "forward projection" of care for casualties (see Chapter 6). Equipment and supplies must meet minimum standards and be adequate for basic trauma care, and adapted to the personnel's skills and local standards. Telecommunication equipment, if any, should be properly installed and placed in a reserved area.

Please note:

The Emergency Items Catalogue of the International Red Cross and Red Crescent Movement contains the description of a standard first-aid and triage post, equipped for experienced nursing staff and/or a general practitioner (see Selected bibliography).

7.5.4 Organization

The premises of the FAP should be organized and the staff prepared for dealing with a mass influx of casualties. The principles and practice of triage should be well understood by all present through simulation exercises (see Chapter 9).

If the FAP stays open for a certain length of time, and the facilities allow for it, the following areas should be pre-arranged:
- admission area at the entrance to register and triage casualties;
- holding area to care for and monitor casualties awaiting evacuation;
- waiting area for relatives, friends and comrades;
- temporary mortuary;
- storage area for equipment and supplies;
- storage area for weapons removed from the wounded;
- rest area for personnel, and personal hygiene facilities.

ICRC EXPERIENCE

Occasionally, the ICRC has had to set up an ad hoc FAP where access to surgical facilities was insecure. During the long-running civil war in Sierra Leone, fighting broke out several times in the capital city, Freetown. During one such episode in 1998, the ICRC delegation was turned into a first-aid post: the parking lot became the reception and triage department and the various offices became wards and intensive care areas. Over a period of 10 days, 6 nurses and 3 Red Cross volunteers treated 244 war casualties and 228 sick patients, while a surgical team from Médecins sans Frontières (MSF) operated in the general hospital. Urban fighting often made it dangerous for patients to reach the hospital and they regularly stayed in the improvised FAP for 2 or 3 days prior to evacuation.

In addition to basic first-aid treatment, intravenous fluid resuscitation, tetanus immunoglobulin, penicillin, and analgesia were given. Many patients survived 2 - 4 days, before being transferred to the hospital, and surgery. The MSF surgical team appreciated receiving patients who had dressed wounds and were "well hydrated", ready for surgery.

Security, however, was a major concern. Looting of the ICRC delegation by armed men occurred twice and several of the 4,500 civilians, who had taken refuge in the delegation premises, effectively turning it into a displaced persons camp, were injured or killed by stray bullets. The emblem of the red cross offers only limited protection under such circumstances.

7.6 ICRC involvement in first-aid programmes

The ICRC supports first-aid programmes and activities in contexts of armed conflict and other situations of violence. These programmes include:
- deployment of medical staff to operate first-aid posts;
- training where no other organization has access (e.g. for irregular guerrilla groups);
- helping to adapt routine first-aid programmes of National Red Cross and Red Crescent Societies and other organizations to the context of conflict preparedness and response;
- development of strategic, management and planning capacities of national and local institutions and team leaders;
- provision of materials and equipment;
- assistance in the organization of an emergency care system;
- production of standards and reference documents (see Selected bibliography).

7.7 Debates, controversies and misunderstandings

Detailed first-aid techniques are described in the manuals listed in the Selected bibliography. The rest of this chapter deals only with a few topics that may give rise to controversy or misunderstanding or are specific to the scenario of armed conflict.

7.7.1 "Scoop-and-run" *versus* "stay-and-treat"

Like the rest of the chain of casualty care, the organization of first aid requires planning and training. A strategy for the efficient care and evacuation of the wounded must be established. Two well-known strategies are described by the expressions "scoop-and-run" and "stay-and-treat". These derive largely from the civilian practice of emergency medical services and may not be particularly relevant in a context of armed conflict.

In a peacetime environment, there is no impediment to patient transfer other than infrastructure and geography. The efficiency of evacuation is determined by the availability and coordination of transport, either by air (fixed wing with airports or helicopters and helipads), or by land (proper roads, necessary vehicles, etc.); and the distances involved. The context of armed conflict is not as simple.

Scoop-and-run implies basic first-aid measures, then taking the patient *immediately* to a surgical hospital. This is appropriate if the distances are short, reliable transport is available, and the nearby hospital is adequately supplied and staffed. Keeping patients on the spot until patient stabilization prior to evacuation – stay and treat – is correct if distances are great, infrastructure and transport are less than adequate, and proper surgical facilities are more difficult to access.

In a military context, the factors of ongoing combat and enemy activity must be added to those present during peacetime. Here, scoop-and-run implies air superiority if helicopters are used, safe and controlled roads for transport over land, and, in both situations, surgical facilities at a reasonable distance. These conditions are fulfilled for only a few armies in the world, and even then only under certain tactical situations. More common is the establishment of a collection point or clearing station: that is to say "stay-and-treat". How much "treatment" occurs depends on the forward projection of resources. The performance of more advanced techniques in the field has been discussed in Chapter 6.

7.7.2 Mechanism of injury and the problem of the cervical spine

The first aider, or other medical personnel, must immediately determine whether the casualty has suffered blunt or penetrating trauma. Blunt trauma above the level of the clavicles or causing unconsciousness requires immediate observation and immobilization of the cervical spine, while still giving priority to the airway. A penetrating wound to the brain causing unconsciousness requires no special care of the cervical spine.

In the case of a penetrating missile wound to the neck hitting the cervical vertebrae, any damage to the spinal cord has already been done. Unstable cervical spine injury from a projectile results in permanent cord injury. The reported mortality is over 95 %. The first aider should be careful while handling the casualty, but cannot prevent damage that is already irreversible. A combination of blunt and penetrating neck injuries should be managed in the same way as blunt ones.


M. Dalla Torre / ICRC

Figure 7.2

Gunshot wound to the mandible: no danger to the cervical spine.

ICRC EXPERIENCE

Here are two practical examples taken from ICRC experience to demonstrate the difference between blunt and penetrating trauma:

A person wounded in a road-traffic crash with a fractured mandible and bleeding from the mouth that obstructs the airway also requires care of the cervical spine in case there is hidden injury. A bullet wound to the mandible – with bone fragments, haematoma, drooling saliva, and damaged soft tissue of the floor of the mouth – does not. If the patient is conscious, he will maintain a particular position – head thrust forward and looking down, blood and saliva flowing out – in order to maintain as patent an airway as possible. There is no use in placing a protective cervical collar on this patient and, if the first aider attempts to place the casualty in a reclining position, the wounded person will resist.

A fall may result in both loss of consciousness and injury to the cervical spine. Loss of consciousness due to a bullet wound to the head, however, does not require any specific precautions regarding the cervical spine.

7.7.3 ABCDE or C-ABCDE?

In statistical terms, severe peripheral haemorrhage is the main lethal yet salvageable injury in a context of armed conflict (see Chapter 5). Various studies show that far more soldiers die from catastrophic peripheral haemorrhage than from airway obstruction or respiratory inadequacy. Thus, the "C" which stands for Catastrophic bleeding, may be put first, simply because it is more common.

Once catastrophic external haemorrhage, which is quite obvious, has been excluded – the great majority of cases – the first aider should resort immediately to the standard routine of ABCDE.

7.7.4 The tourniquet: when and how?

The tourniquet is said to save lives, but endanger limbs. It is difficult to apply correctly and to maintain and supervise, and open to many complications if widely used when not necessary. Furthermore, the prolonged application of an improvised tourniquet is usually not effective and causes tissue damage by itself (Figures 7.3.1 and 7.3.2). There is little or no use for a tourniquet in civilian practice for the war-wounded. It may be applied *as a last resort*, when all else has failed, to temporarily control bleeding while packing the wound and applying a compressive bandage. It should then be removed.


E. Winiger / ICRC

Figure 7.3.1

Improvised tourniquet: how effective?


R. Coupland / ICRC

Figure 7.3.2

Improvised tourniquet: how harmful? Here a tourniquet was applied for more than six hours, resulting in a very high above the knee amputation.

By far the most common and most effective technique for a first aider to control peripheral haemorrhage is direct pressure over the wound completed by a compressive bandage; or, if insufficient, pressure over the proximal artery in the axilla or groin, tamponade of the wound with dressings, and then a compressive bandage.

The military might continue to use a tourniquet under certain tactical circumstances: to free the hands of the single medic when dealing with mass casualties; while performing first aid under direct fire, and especially at night. Some armies equip their soldiers with a pre-manufactured self-applicable tourniquet applied with one hand to allow a wounded soldier to continue participating in combat. The ICRC declines to pronounce on these tactical considerations, but warns against an all too easy abuse of the tourniquet as has been seen in many wars in the past.

The use of a tourniquet for crush injuries (people trapped under the rubble of a collapsed building whether due to an earthquake or bombardment) is justifiable, and due precautions should be taken to ensure rehydration/resuscitation and thereby avoid the complications of the otherwise inevitable myoglobinaemia.

For further information on crush injury, see Volume 2.

New locally-active haemostatic powders and sponges to promote clotting in traumatic wounds are being tested by some armies; however direct pressure must still be applied. The ICRC has no experience with these and, like most others, eagerly awaits the published results of these field trials. Cost and availability will be factors to be taken into consideration for their use worldwide.

Peripheral haemorrhage can be controlled by external pressure and a compressive bandage.

7.7.5 Resuscitation or rehydration?

The first aider can only implement simple procedures in the field. The administration of intravenous fluids requires a certain degree of medical knowledge and specific equipment that are beyond the normal scope and competencies of a first aider. He can be involved in the monitoring of a perfusion, however.

The subject of pre-hospital i.v. fluids has given rise to considerable controversy. Maintaining adequate tissue perfusion and oxygenation is balanced off against the dilution of clotting factors and the dislodging of existing clots when the blood pressure goes up ("popping the clot"). The currently recommended "hypotensive resuscitation" involves giving fluids to a just palpable radial pulse – equivalent to a systolic blood pressure of 90 mm Hg – and no more (see Chapter 8).

A great deal of this controversy concerns efficient civilian trauma systems where evacuation times are short, less than 2 hours. It is probable that only the war-wounded showing obvious clinical signs of shock require pre-hospital i.v. fluids. In addition, in many contemporary conflicts transfer to a hospital takes much longer – days or even weeks – where "popping the clot" is not really relevant. Rehydration – as part of resuscitation – may be a more appropriate term under these circumstances.

If the wounded patient is conscious and not suffering from head trauma, the first aider can rehydrate with oral fluids (e.g. oral rehydration salts), especially if evacuation is delayed and transport long. This procedure is probably not employed nearly enough. Oral rehydration can probably be given with no detriment to the patient even in cases of abdominal trauma, and especially for severe burns.

7.7.6 Supplemental oxygen in the field?

Warning !

Oxygen cylinders are the equivalent of a bomb if hit by a bullet or piece of shrapnel. In addition to the danger they represent, the cylinders are heavy and must be replaced, lasting only a short time at high flows. Furthermore, their replenishment is complex and requires special factory capacity.

Oxygen cylinders must be ruled out in the event of any deployment to a dangerous area. This is now standard ICRC policy.



Palestine Red Crescent Society

Palestine Red Crescent Society

Figures 7.4.1 and 7.4.2

Ambulance destroyed by the detonation of an oxygen cylinder which has gone through the roof like a rocket. The photos show the ambulance and the cylinder on the ground.

Depending on security conditions, the collection point or intermediate station may have oxygen available. An oxygen concentrator (requiring an electrical supply) is preferable to compressed cylinders.

7.7.7 Disability: the AVPU system

Disability refers to the neurological status of the casualty: the state of consciousness and any paralysis due to injury to the spinal cord.

The Glasgow Coma Scale is the hospital standard. However, a simpler determination of consciousness is the AVPU system and it may be easier for first aiders to use in the field. It easily translates into the Glasgow system when the patient arrives at the hospital and gives the surgeon a good appreciation of the evolution of the patient's condition.

Alert	The casualty is awake, lucid, speaks normally and is responsive to the environment (e.g. eyes open spontaneously as you approach).
Voice responsive	The casualty is able to respond in a meaningful way when spoken to.
Pain responsive	The casualty does not respond to questions but moves or cries out in response to a painful stimulus (pinching the neck muscles, earlobe or nipple; rubbing the supra-orbital margin, or the angle of the mandible).
Unresponsive	The casualty does not respond to any stimuli.

Other conditions may influence the level of consciousness: hypoxia, shock, medication, and narcotics and alcohol (the latter all too often consumed to excess during times of armed conflict).

In the field, securing the airway is the first step to take when facing a casualty whose consciousness is compromised.

Examination of the spinal cord and vertebral column

This involves two phases: determining the movement of the limbs – comparing the two sides – and palpation of the bony prominences of the spine. Palpation of every vertebra – like "fingers playing on piano keys" – aims to identify any induration or deformity. If there is any danger to the spinal cord, then the four-person log-roll technique should be used to move the patient onto a stretcher. The cervical spine can be immobilized initially by manually controlling the head before a neck collar/ Minerva splint is placed. Immobilization of the cervical spine must not increase the risk of airway obstruction, however.

The importance of the mechanism of injury, blunt or penetrating, has already been mentioned. In all cases of suspected injury to the vertebral column, proper handling of the patient and immobilization techniques are of the utmost importance; the injury may already be there, but the first aider should act in such a way that he does not worsen the condition.

7.7.8 Evacuation: a risk to take

Transportation of the wounded is always difficult, always takes longer than expected, adds to the trauma, and can be dangerous to the patient and those transporting the casualty: the famous "mortality of the ambulance ride". In situations of armed conflict, the danger of the ambulance ride is complicated by the risks of ongoing combat.

L. Berlemont / ICRC

Y. Muller / ICRC

Figures 7.5.1 and 7.5.2

Different means of patient evacuation: modern and traditional.

Speed is less important than safety of transport: ambulance crashes are notorious. All these parameters, aggravation of the patient's condition, use of resources and security, must be weighed against the likely benefits of moving the wounded.

In an urban environment, it is normal for a first aider to bypass the neighbourhood clinic if the injury is serious, and to evacuate to a clinic for a minor wound in order not to overburden the hospitals. Unfortunately, city-dwellers often spontaneously rush patients to hospital no matter how slight the injury. Evacuation and transport may be difficult and dangerous during urban fighting even if distances are very short and transfer may be delayed while waiting for a calm period or ceasefire.

There is also the confusion that reigns during street fighting and the highly-charged emotional atmosphere to contend with. Lack of discipline to perform good pre-hospital triage – and the "pressure" of bystanders – can result in chaos in the receiving hospital. The first wave of ambulances transports the dead and badly mutilated. The second wave of ambulances carries people who are shouting, hysterical, and frightened: the lucid and superficially injured. The third wave evacuates the seriously wounded who truly require emergency treatment; these patients lie still – they are usually haemorrhaging – without shouting to bring attention to themselves.

In remote rural areas, if transportation takes many hours or even days, it is logical to project forward competencies by training local providers in more advanced skills. The principles of triage apply to the choice of which patients to evacuate first (see Chapter 9). Note that there is an important *difference* in the priority to treat and the priority to evacuate, especially if evacuation is prolonged. The recognition of injuries that are not survivable helps to spare the victim and would-be rescuers the agony and frustration of unsuccessful efforts to reach a higher level of care, and to provide better care for those who can survive.

Delay in evacuation will contribute to an increase in pre-hospital mortality; the more severely injured suffer "nature's triage". As was seen in Chapter 5, longer and more difficult evacuation sorts out central injuries, with a consequent decline in hospital mortality: only those patients with a good chance of survival reach the hospital. This remains a major problem in the care of the war-wounded.

From the above, it should be clear that the practice of the Inner Smile and the quality of breathing and relaxation – as conditions of the self-healing process – are intimately related.

It is not coincidence that the great sages and masters of self-transformation like the Taoist immortals and the Buddha are always portrayed with an inward-oriented smile, to signify the key to inner freedom and balance and the unity of Yin and Yang. The practice of the Inner Smile as the key to relaxation remains the basis of all the practices of the Universal Tao, from the most basic to the most advanced. It is the key to all forms and stages of self-transformation, as the Taoist masters discovered its secret and its power to initiate and enhance the process of self-transformation. Statues and pictures may remind us of our own transformational potential and may help us to set in motion the internal alchemical process. We may also bring into our mind images of people who have awakened or reminded us in the course of our life of our own potential for transformation and positive qualities, thereby helping us to empower ourselves.

Science of Feeling and the Power of Intuition

In this sense, the Taoist practice is a continuous invitation to turn inward and get in touch with one's own body (and organs). Begin to sense and feel the body's state of being, its expansion and contraction and the state of relations between the major organs and the senses (kidneys/ears, liver/eyes, heart/tongue, spleen/mouth and lungs/nose). Check the state between the major organs and connected organs (kidney/bladder, liver/gallbladder, heart/small intestine, spleen/stomach, lungs/large intestine). Review the overall state of relations between the organs, glands, the nervous system, the spine, the bones, muscles and tendons. How are the relations between the three centers of the body (belly, heart and crystal room)? Check on those between the center and the extremities, the front and the back and the quality of the path routes which carry the flows in the body (the electro-magnetic energy, called Chi, also called the life force or vital force, the blood and the lymph flows).

Any advance in the practice is determined by the growth in ability to feel into the body by going inward and getting in touch with it.

In this context it is of value to realize that the verb "heal", the

Chapter 8

HOSPITAL EMERGENCY ROOM CARE

8. HOSPITAL EMERGENCY ROOM CARE

8.1 ABCDE priorities 171

8.2 Initial examination 171

8.3 Airway 172
8.3.1 Opening the airway 173
8.3.2 Definitive patent airway 173
8.3.3 Definitive patent airway: endotracheal intubation 173
8.3.4 Definitive patent airway: surgical airway 174

8.4 Breathing and ventilation 175
8.4.1 Assisted ventilation 176

8.5 Circulation 177
8.5.1 Pericardial tamponade and pericardiocentesis 177
8.5.2 Haemorrhagic shock 178
8.5.3 Fluid replacement 179
8.5.4 Hypotensive resuscitation 181
8.5.5 Adjuvant therapy 181

8.6 Blood transfusion where supplies are limited 181
8.6.1 Clinical use of blood in ICRC practice 182
8.6.2 Two unit rule 182
8.6.3 Fresh whole blood 183
8.6.4 Autotransfusion 183
8.6.5 Total blood requirements: the ICRC's experience 183

8.7 Disability 184

8.8 Environment/exposure 185
8.8.1 "Fatal triad" of coagulopathy, acidosis, and hypothermia 185

8.9 Complete examination 185
8.9.1 Complementary diagnostic examinations and monitoring 187

8.1 ABCDE priorities

The framework for casualty management in a hospital emergency room (ER) is a continuation of the basic life support procedures of first aid. The logic is the same; the diagnostic and treatment means available are simply more advanced.

Whether or not the casualty arriving at a hospital has received first aid in the field, he/she should undergo the full ABCDE examination. The patient's condition may have changed during transport; important wounds may have been missed because of the confusion in the field; first-aid competence may have been limited or entirely absent. Efforts should again first concentrate on lifesaving treatment for asphyxia and shock, the most common remediable causes of death. The "golden hour" begins at the site of trauma, *not* on arrival at the emergency room.

Priorities: the **ABCDE** scheme of thinking

Airway before Breathing, before Circulation.

1. Assess:
Initial examination: **A**irway, **B**reathing, **C**irculation, **D**isability, **E**nvironment and **E**xposure. Triage in a mass casualty situation: see Chapter 9.

2. Act:
Emergency resuscitation: act on life-threatening conditions.

3. Assess:
Complete examination: head-to-toe palpation, front and back and sides.

4. Act:
Definitive treatment, surgical or not: stabilization.

5. Assess and Act:
Treatment or evacuation of the casualty, according to triage priority, to a higher echelon hospital for specialized care if necessary.

Please note:

In certain countries a very definite separation must be made for emergency examination and treatment of male and female patients. This can be problematic in a mass casualty situation; nonetheless, the emergency department must be organized accordingly.

8.2 Initial examination

The initial examination and emergency resuscitation are carried out simultaneously. The receiving ER doctor must automatically ask a series of questions.

1. Is the patient dead or alive?
2. Is the casualty conscious or not?
3. What is the mechanism of injury: penetrating or blunt?
4. What are the life-threatening conditions, if any, according to the ABCDE scheme?

The natural reflex when faced with a wounded person is to look at the bleeding first. It must be understood that the greatest threat to life is an inadequate intake of air. Airway takes precedence over breathing and over circulation. With practice, the airway and breathing can be secured quickly enough to then allow the doctor to deal with any visible haemorrhage. (The situation in a hospital emergency room is different from one of "catastrophic haemorrhage" in the field, as discussed in Chapter 7 on first aid.)

The ER doctor must learn to use the ABCDE scheme of thinking in a circular fashion. Determining if the patient is dead or alive already involves a rapid ABCDE examination. The dead have no air intake (A), no ventilation of the lungs (B), and no pulse (C); the pupils are dilated and do not react to light and there is no reaction to painful stimulus (D); there is no movement of the limbs and the body feels cold (E).

When mastered, the ABCDE scheme of thinking allows the doctor to answer all the above questions in one integrated process.

Most casualties are conscious, anxious or frightened, and in pain, and will tell you what happened and where "it hurts": they are alive, conscious, and the act of speaking shows that the airway is free. These signs of life may seem obvious. Nonetheless, one should make a mental checklist and practice the routine of asking the series of initial questions in order to establish an organized and coherent method of examination.

As mentioned in the previous chapter on first aid, blunt trauma above the level of the clavicles requires adequate care of the cervical spine, but not at the expense of a life-threatening airway problem. Simple measures include: manual stabilization in a neutral position with the head maintained in the axial line; semi-rigid collar; sandbags; taping; specialized backboard.

The initial examination should include the diagnosis of any life-threatening A, B, or C problems and the number, location and extent of *obvious* wounds. These two elements together are important for establishing triage priorities (see Chapter 9). A more complete examination to locate *all* wounds should follow the initial ABCDE examination.

It is important to determine the time since injury, estimate blood loss since injury, and the presence or absence of any allergies. In civilian casualties, past or pre-existing diseases and medications for chronic conditions should be taken into account. Young healthy combatants usually do not present such medical problems.

In a hospital environment the casualty should be completely undressed to allow for a correct examination – again, certain cultural or religious constraints may apply. Vital signs should be taken, i.v. lines placed and blood samples withdrawn simultaneously for blood grouping and cross-matching, and a haematocrit or haemoglobin estimation to determine a baseline for future comparison. Other tests, such as electrolytes, blood gases, glucose, etc. may be performed depending on local standards and laboratory capacity.

8.3 Airway

Airway obstruction is an emergency that requires an immediate response. Some injuries cause an immediate problem; others may result in delayed impairment of the airway.

The following list presents the common conditions that cause airway problems.

Head injury with decreased consciousness:
Apart from the danger of aspiration of vomitus, blood, broken teeth, bone or foreign bodies, the tongue and epiglottis may fall back and block the airway. Furthermore, the initially conscious casualty may slowly lose consciousness after some time.

Maxillo-facial injuries:
Even if the patient can breathe adequately in the beginning, the development of oedema of the tongue, floor of the mouth and pharynx will obstruct air intake after several hours.

Penetrating wounds to the larynx or upper trachea:
If large enough, they will create a "traumatic tracheotomy".

Blunt injury to the larynx (by a rifle butt):
This may crush the cartilage resulting in collapse of the airway.

Compressive haematoma in the neck:
This may accumulate slowly compressing the hypopharynx or larynx from the outside.

Burns to the face and neck or inhalation burns of the larynx and trachea:
Whether due to ordinary fire and smoke or specific irritating chemical agents, these require close observation for delayed obstruction or respiratory failure due to oedema.

Please note:

Inhalation of chemical agents requires special precautions for decontamination of the patient and of any equipment coming into contact with him. Not only is this an essential part of the treatment, but it is also necessary for the protection of the hospital staff and other patients.

The conditions causing delayed airway obstruction may develop slowly and there is a danger that they will not be recognized in time, especially during triage of mass casualties with inadequate supervision.

8.3.1 Opening the airway

As in first aid, the standard treatment for an actual or potential obstruction applies.

Basic steps for securing the airway

1. Open the mouth.
2. Displace the tongue forward.
3. Remove any blood or debris from the mouth and oropharynx.
4. Maintain the airway patent.

To open and clean the mouth the standard manoeuvres are jaw thrust or chin lift: displace the tongue forward, and then finger-sweep the mouth while protecting the finger, aided by mechanical suction if available. These techniques will cause some movement in the cervical spine. Manual in-line axial stabilization of the head during the manoeuvres will reduce such movement. Patency of the airway, nonetheless, takes precedence.

To maintain the airway patent a number of devices can be used:
- oropharyngeal airway (Guedel tube);
- nasopharyngeal airway;
- laryngeal mask airway;
- combitube (double lumen tube inserted blindly into the trachea and oesophagus).

All of these methods keep the airway open but cannot ensure protection against vomiting and aspiration of gastric contents.

During the reception of mass casualties, the overwhelmed ER personnel may have to revert to a simpler method as a temporary procedure. Under these conditions , the lateral recovery position (lateral security, post-tonsillectomy or semi-prone position) will be the position of choice for most patients with an airway at risk until more secure procedures can be achieved. The lateral recovery position affords relative protection against vomiting and aspiration.

8.3.2 Definitive patent airway

The following conditions require a *definitively* secured airway:
- apnoea or cardiac arrest, whatever the cause (with assisted ventilation);
- Glasgow Coma Scale score of less than or equal to 8, which is equal to being unresponsive to pain;
- continued seizures and convulsions (with assisted ventilation);
- unstable fractures of maxilla or mandible (usually bilateral fractures of the mandible, or instability of the whole mid-face at the level of the glabella and zygomata);
- large flail chest segment (with assisted ventilation);
- respiratory failure (with assisted ventilation);
- moderate to severe facial or oropharyngeal burn.

8.3.3 Definitive patent airway: endotracheal intubation

The best and simplest technique to maintain a patent airway with protection from aspiration is endotracheal intubation, through either a nasal or oral approach. Deeply unconscious patients can usually be intubated easily. Others may be restless, irritable, uncooperative and hypoxic. Intubation under these circumstances usually requires sedation. Various agents given intravenously will allow rapid intubation without struggling and without compromising the patient's hypoxic condition (diazepam, pentothal, propofol, ketamine). Cardiac arrest, whatever the cause, and severe haemorrhagic shock (Class IV, see below),require emergency endotracheal intubation. The alternative to endotracheal intubation is a surgical airway.

8.3.4 Definitive patent airway: surgical airway

The need for a surgical airway should be identified *early* and performed *quickly*. This may be the primary airway (maxillo-facial injuries, wounds to the neck involving the larynx or pharynx or haematoma accumulation, etc.) or following failure of endotracheal intubation. A surgical airway is also beneficial where there are no facilities for mechanical ventilation.

> Cricothyroidotomy is preferable to tracheostomy, which can be a difficult procedure under emergency conditions and be associated with profuse haemorrhage.

Cricothyroidotomy

This is a quick, safe, and relatively bloodless procedure (Figures 8.1.1 – 8.1.4). A horizontal incision is made in the skin and extended through the cricothyroid membrane. The handle of the scalpel is inserted and turned 90° to hold the membrane open until a small tracheostomy tube can be inserted.

Figures 8.1.1 – 8.1.4

Cricothyroidotomy.



P. Zylstra / ICRC

Figure 8.1.1

Surgical landmarks: the patient's neck should be placed in extension with a pad beneath the shoulders. The thyroid and cricoid cartilages are identified by finger palpation, the cricothyroid membrane is then identified as the depression in between them.



P. Zylstra / ICRC

Figure 8.1.2

A horizontal skin incision is made over the cricothyroid membrane. The wound is spread apart using the thumb and index finger.



P. Zylstra / ICRC

Figure 8.1.3

The incision is carried down through the membrane and widened by insertion of the scalpel handle, which is then rotated through 90°.



P. Zylstra / ICRC

Figure 8.1.4

A tracheostomy tube is placed through the opening and secured. The entire procedure should take no more than 30 seconds.

Tracheostomy

Tracheostomy should be an elective procedure. The only specific indication for an emergency tracheostomy in missile wounds is *direct laryngeal injury*, thus transforming a traumatic tracheostomy into a surgical one. The urgency of the problem will determine which technique is the safest and most appropriate for ensuring a secure airway.

8.4 Breathing and ventilation

The cause of respiratory distress must be found and treated. Patients with head injuries often require intubation and ventilation to support respiration, as is the case for quadriplegia, blast lung, chemical injuries and inhalation of smoke fumes. Previous disease may also impair ventilation in an injured patient.

Clinical examination may reveal a chest injury that decreases respiration including:
- flail segment of the chest;
- open pneumothorax or sucking wound to the chest;
- tension pneumothorax and haemopneumothorax.

Flail segment of the chest

This condition should be treated initially by bandaging or adhesive plaster strapping, good analgesia and positioning of the patient. More severe and complicated cases may require a chest tube and intubation with mechanical ventilation. It is usually the underlying lung trauma that causes the greatest difficulty in treatment.

For further details on flail segment of the chest, see Volume 2.

Sucking wound

A sucking wound requires a three-sided occlusive dressing in the ER. The patient then goes to theatre for debridement and closure of the wound of the chest wall and placement of an intercostal drain.

Please note:

There is a risk of transforming an open wound into a closed tension pneumothorax if all four sides of a dressing are firmly closed.

Tension pneumothorax

The diagnosis of a tension pneumothorax can be difficult on purely clinical grounds, except in the case of obvious respiratory distress; in this case no time should be wasted taking an X-ray (Figure 8.2). The condition requires an immediate wide-bore i.v. cannula to be inserted into the second or third intercostal space in the midclavicular line (needle thoracocentesis) attached to an improvised Heimlich one-way flutter valve as a temporary measure (Figure 8.3). A positive finding is indicated by the sudden rush of air as the needle enters the pleural cavity. The cannula should be long enough (8 cm) to fully penetrate the muscles of the chest wall (average thickness 4 – 6 cm). An intercostal chest tube (midclavicular or 5th intercostal space at the midaxillary line) should replace the needle thoracocentesis as soon as possible.



H. Nasreddine / ICRC

Figure 8.2

Tension pneumothorax with respiratory distress: the only thing wrong with the X-ray film is that it was taken. The diagnosis should have been a clinical one.



P. Zylstra / ICRC

Figure 8.3

Improvised Heimlich flutter valve: a wide bore cannula is inserted at the upper edge of a rib. A finger from a surgical glove, with a 1 cm-long incision in the end, is tied around the cannula.

Needle thoracocentesis may fail, however, even in the presence of a tension pneumothorax. A negative trial should not necessarily rule out its existence. A simple finger thoracostomy in the 5th intercostal space at the midaxillary line is a good alternative. A positive result, again, is indicated by the hiss of air rushing out; a chest tube is placed immediately.



H. Nasreddine / ICRC

Figure 8.4.1

Simple, but massive, pneumothorax. Patient lying comfortably and breathing without effort. X-ray films are justified.



H. Nasreddine / ICRC

Figure 8.4.2

Antero-posterior radiograph showing large right-sided pneumothorax. The arrow marks the bullet.



H. Nasreddine / ICRC

Figure 8.4.3

Lateral film.



H. Nasreddine / ICRC

Figure 8.5

Intercostal tube.

Other, less extreme presentations of tension pneumothorax are more common than is realized. Table 8.1 shows the important signs and symptoms for making the diagnosis. These pertain to the awake casualty and differ from those in the sedated and ventilated patient. It is acceptable to perform an X-ray in patients whose presentation may be suspicious but who are not in respiratory distress to confirm the diagnosis. The patient should be accompanied, however, by someone capable of performing an emergency thoracocentesis in case of rapid decompensation in his condition.

Reliable and early findings	Ipsilateral side	Contralateral side	Pre-terminal decompensation	Inconsistent findings
Pleuritic chest pain (universal)	Hyper-expansion of the chest	Increased mobility of the chest	Decreasing respiratory rate	Tracheal deviation to contralateral side
Air hunger (universal)	Decreased mobility of the chest		Hypotension	Distended neck veins
Respiratory distress (universal)	Hyper-resonance on percussion		Much decreased SpO_2	Surgical emphysema of chest wall
Tachypnoea	Decreased breath sounds on auscultation		Decreasing level of consciousness	
Tachycardia	Added breathing sounds – crackles, wheezes			
Decreasing SpO_2				
Agitation				

Table 8.1 Diagnosis of tension pneumothorax in awake patients.[1]

Haemothorax

A haemothorax should be drained using a wide bore chest tube. This procedure can be lifesaving. When clinical signs of haemothorax exist, an intercostal tube should be inserted *before X-rays are taken*. Chest tubes are usually placed under local anaesthesia. If there is a wound to excise, ketamine anaesthesia would be more appropriate.

For information on insertion of chest tube – thoracostomy – see Volume 2.

8.4.1 Assisted ventilation

After intubation, assistance with respiration may be required. Common pathologies requiring such assistance include:

- head injury;
- large flail segment;
- blast injury of lungs;
- inhalation of toxic gases or smoke or flash burn to the bronchial tree;
- aspiration pneumonitis; and
- other medical causes of respiratory insufficiency.

Assisted ventilation may be manual:

- mouth-to-mouth or -nose for infants (use a compress barrier);
- mouth-to-mask;
- bag-valve-mask;
- bag-valve-endotracheal tube or surgical airway;

or mechanical, provided by a ventilator.

In hospital surroundings it is possible to administer supplemental oxygen, either by a central oxygen supply, compressed cylinders, or an oxygen extractor/concentrator.

The ICRC usually operates in situations of limited resources, and mechanical ventilators are not standard equipment. Few patients can be maintained for any length of time using manual ventilation by nurses and doctors. Furthermore, in a mass casualty situation the principles of triage will apply and most patients requiring assisted ventilation will be Category IV; therefore, it will not be performed (see Chapter 9).

---

[1] Adapted from: Leigh-Smith S, Harris T. Tension pneumothorax – time for a re-think? *Emerg Med J* 2005; **22**: 8 – 16.

substantive “whole”, and the adjective “holy” have the same etymological root. This is in line with the Taoist insight that the process of healing is realized in the process of becoming whole and that holiness is the state of having become whole and in balance with oneself and with the universe within oneself. In this view holiness is not a moral category but an existential and relational state of being.

It is not without reason that Taoist practice has been called a science of feeling, as throughout the ages it has relied on and cultivated it. One may also call the ability to feel the power of intuition or the feeling intellect which exists at every and all levels of our body and bodily awareness in which we are wholly present. In all languages of the world, there are multiple expressions, pointing to the organs, such as the heart or the liver or the kidneys or the blood or the bones or the veins, hands, eyes, ears and feet which reminds us of this intuitive power of the whole body. The reduction of thinking to the mind and the brain, so characteristic of Western reductionism, is entirely alien to all cultural traditions in the East and the South.

It is the feeling that we open the body and open and activate the Chi from within and outside.

It is also through feeling that we can sense, taste, hear and touch the rhythms of earth and heaven and unite with them within ourselves. Becoming aware of our inner movements and what moves us are one and indivisible. In the feeling process, we also become aware of the relativity of our boundaries and learn to experience these not only as limitations and finite but as openings to the unlimited and infinite.

As a result our solitude comes to an end and we become sensitive to our intrinsic relatedness with all that is. In this sense, each practice may be seen as a step to invert the process towards alienation and separation from the sources of life, basic to Western culture and its extension over the world.

Thinking with the Heart

One is reminded of the meeting of Carl Gustav Jung, the famous Swiss psychiatrist and philosopher of culture in the 1920’s with an old Pueblo Indian in New Mexico on one of his visits to the United States of America. Jung narrates in his autobiography that his talk with him was unlike any which he had had with a European. When

8.5 Circulation

The main circulatory problem encountered in the war-wounded is hypovolaemic shock, and is usually due to haemorrhage or burns. In addition to any blood loss, big soft-tissue wounds sequestrate a great deal of tissue oedema with further loss of plasma and circulating volume. Dehydration complicates any previous fluid loss if evacuation is long and delayed.

Neurogenic, anaphylactic, and cardiogenic shock may also occur; septic shock is a late complication. Injury to the spinal cord causing quadri- or paraplegia will result in neurogenic shock due to a disproportion between blood volume and dilated vascular bed. Allergy to antibiotics must always be kept in mind. Traumatic cardiogenic shock is due to direct injury to the heart that is not immediately lethal (e.g. small shrapnel wound causing traumatic myocardial infarction and/or pericardial tamponade).

8.5.1 Pericardial tamponade and pericardiocentesis

In the rare instance of constrictive *haemopericardium* with cardiac tamponade due to a penetrating missile wound to the heart, pericardiocentesis may be required if there is acute decompensation, to *gain time* until emergency thoracotomy can be performed.

The procedure for pericardiocentesis is as follows.

1. A 20 ml syringe is attached to a long over-the-needle cannula (or alternatively a spinal anaesthesia needle).
2. The skin is punctured 1 – 2 cm to the left of the xiphisternal junction, at a 45° angle, and the needle advanced through fascia and muscle.
3. (The inner trocar is now removed if using a spinal needle – but not if using the needle of the cannula).
4. The needle is gently advanced while aiming at the tip of the left scapula and applying continuous suction on the syringe.
5. When the needle tip enters the pericardial sac, blood will immediately appear in the syringe. The needle is withdrawn if using a cannula, which is then advanced into the sac.
6. As much blood as possible is aspirated. If the tamponade has been relieved, the patient's condition improves immediately; if the right ventricle has been entered, there is no change.
7. At the end of aspiration, the synthetic over-the-needle cannula can be left in place with a 3-way stopcock valve. (The spinal needle is gently withdrawn, millimetre-by-millimetre, if this technique is being used).
8. Should the tamponade return quickly, the stopcock can be re-opened and aspiration repeated (or the spinal needle tap is repeated).
9. The patient should *immediately* be taken to theatre!

An emergency room thoracotomy should not be performed when the operating theatre is just down the corridor: it is as pointless as it is dangerous in *most* hospitals around the world.

8.5.2 Haemorrhagic shock

Types of haemorrhage

Haemorrhage may be arterial, venous or capillary and blood loss may be:

- peripheral and obvious (blood clot the size of a fist or an open wound the size of a hand represents 500 ml);
- peripheral and hidden:
  - closed fractures of long bones (tibia = 500 ml, femur = 1.5 litres);
  - open wound with small entry that is blocked by a piece of torn muscle;
- central (chest, abdomen, pelvis and retroperitoneum) – significant bleeding into the chest should have been diagnosed during the breathing phase of the initial examination; a massive haemothorax can represent 2 – 3 litres of blood, a severe fracture of the pelvis 3 litres.

Penetrating trauma causing central bleeding into a body cavity requires surgery of some sort, and severe internal haemorrhage may require urgent operation as part of the resuscitation process. Such patients have a high priority for surgery.

Direct pressure and elevation of the limb will stop most cases of peripheral venous and capillary haemorrhage. Fractures should be splinted.

If a bleeding blood vessel can be *seen* in the depths of a wound, *and only if it is clearly visible*, direct control may be obtained with haemostatic artery forceps.

Blind clamping must never be attempted.

Otherwise, severe peripheral bleeding can usually be stopped by packing the wound. Digital pressure is applied to the artery proximal to the wound (pressure point), while the wound is carefully packed with small quantities of gauze compress at first, followed by a more bulky dressing, and finally a firm compressive elastic bandage in order to apply even pressure to achieve haemostasis. Alternatively, and if available, a pneumatic tourniquet can be used to temporarily control severe arterial haemorrhage while bringing the patient to the operating theatre.

Once a wound has been packed and bleeding has been arrested, the dressing (or tourniquet) should not be removed until the patient has been resuscitated and is in the operating theatre, with blood ready for transfusion if available. The surgical team should be ready to arrest bleeding by rapid intervention to obtain access to and control of the major blood vessels.

In the same manner of thinking, implanted bullets and fragments, or other foreign bodies in the wound, should only be removed as part of the operative procedure.

Beware of removing packs from missile wounds, as the resultant bleeding can be torrential and difficult to control.

The body’s response and classes of shock

Immediately after haemorrhage, the body initiates a number of homeostatic circulatory changes that aim to stop the bleeding as well as compensate and preserve perfusion of the vital organs. The circulating blood volume represents 7 – 8 % of body weight in the adult (5 – 5.6 litres in the 70-kg male or 70 ml/kg body weight) and 9 % in children (80 ml/kg body weight).

Haemorrhage and the shock response are traditionally graded into 4 classes according to the volume of *acute blood loss*.

Class I:

Up to 15 % blood volume lost (750 ml or less). Mild tachycardia is the only clinical sign since the body’s normal homeostatic mechanisms are capable of fully compensating the loss.

Class II:
15 – 30 % blood volume lost (750 – 1,500 ml). Definite tachycardia; slight decrease in systolic blood pressure with rise of diastolic pressure (decreased pulse pressure); refilling of blanched capillary bed of fingers delayed; restlessness or anxiety.

Class III:
30 – 40 % blood volume lost (1,500 – 2,000 ml). Marked tachycardia; tachypnoea; hypotension; small urine volume; classical picture of shock. Compensatory mechanisms start to fail.

Class IV:
> 40 % blood volume lost (> 2,000 ml). Full classic symptoms of shock are present: cold, clammy and pale skin; irritability, aggressiveness and confusion leading to loss of consciousness with loss of more than 50 % circulating volume.

Class	I up to 750 ml (<15 % loss)	II 750 – 1,500 ml (15 – 30 % loss)	III 1,500 – 2,000 ml (30 – 40 % loss)	IV >2,000 ml (>40 % loss)
Pulse	<100/min Full and bounding	100 – 120/min Full	120 –140/min Weak	>140/min Thready
Systolic blood pressure	120 Normal	90 – 120	< 90 Radial not felt	< 60 Carotid not felt
Pulse pressure	Normal	Narrowed	Greatly decreased	Absent
Capillary refill	Normal	Delayed	Delayed	Absent
Respiratory rate	14 – 20/min Normal	20 – 30/min Mild tachypnoea	>30/min Marked tachypnoea	>35/min Marked tachypnoea
Urine output	>30 ml/hr	20 – 30 ml/hr	5 – 20 ml/hr	Negligible
Mental function	Lucid/ thirsty/ slightly anxious	Anxious/ frightened/ irritable	Hostile/ irritable/ confused	Confused/ lethargic/ unresponsive
Physiological status	Fully compensated	Peripheral vasoconstriction	Compensation fails, classical clinical picture	Immediately life-threatening

Table 8.2 Signs and symptoms of haemorrhagic shock according to Class.

8.5.3 Fluid replacement

The important point is to maintain adequate tissue perfusion until the haemorrhage is brought under control. Sufficient blood pressure to maintain this tissue perfusion is judged to be a systolic pressure of 90 mm Hg, equivalent to a palpable radial pulse.

The great majority of war-wounded patients are relatively healthy young adults who suffer injuries to the extremities, and in whom the amount of blood loss is not lethal. They are haemodynamically stable (Class I blood loss) and the usefulness of oral fluids for their resuscitation – in the field and in hospital – is probably underestimated. Head, thoracic and abdominal injuries, however, even with Class I blood loss, should always have an intravenous line placed.

In massive injury, with obviously gross blood loss, several wide-bore intravenous lines should be established. A venous cut-down may be required if shock is profound. Available sites include: median basilic or cephalic in the arm, greater saphenous in the groin, and the distal saphenous vein at the medial malleolus. A venous cut-down should be used for less than 24 hours, or until the patient is filled up with fluids and another i.v. line can be put in. The site of the wounds will influence where i.v. lines are placed.

Modern practice has been to give a fluid challenge and monitor the response. The challenge has usually been with 2 l of isotonic crystalloid solution[2] in 30 minutes, or 3 ml for every 1 ml of estimated blood lost as a general rule of thumb. (Except for very large estimates: 3,000 ml blood loss would require 9,000 ml Ringers lactate!). The fluid challenge for a child is calculated as 20 ml/kg body weight for the initial bolus of Ringers lactate.

---

[2] Ringers lactate is the preferred resuscitation fluid in ICRC practice.

Monitoring of clinical response

The estimation of blood loss is a very approximative measure, however. Rather than relying on this to guide resuscitation efforts, medics should observe the signs and symptoms of the *clinical response* to determine continuing fluid requirements. These include:

- pulse,
- systolic blood pressure,
- pulse pressure difference between systolic and diastolic,
- capillary refill,
- urine output, and
- mental status.

The most important simple parameter for the adequacy of fluid replacement is *urine output*: a urine flow of 0.5 – 1 ml/kg body weight/hour, and even greater in case of crush syndrome, should be aimed for.

The clinical response to a fluid challenge can be summarized as follows.

Rapid and stable response:

The pulse falls below 100, the systolic blood pressure rises above 100, and the pulse pressure widens. Urine output is good. These measurements remain stable. No further fluid resuscitation is required; the i.v. line is maintained open, however. This is the usual result with Class II and some Class III blood loss.

Transient unstable response:

An initial positive response of the pulse, blood pressure, and pulse pressure is followed by a return to subnormal values. Urine output remains low. A further challenge with Ringers lactate or a plasma expander (dextran 70, colloid, etc.) is called for. A return to normal values indicates compensated Class III blood loss, but early surgery is still required. Continuing subnormal shock values indicate continuing blood loss; the patient should be prepared for emergency surgery.

Please note:

Not more than two units of colloid or dextran should be given in any 24-hour period; besides being more expensive, colloids are less effective than Ringers lactate in diffusing into the interstitial space and can help provoke coagulation defects and interfere with cross-matching.

No response:

The patient remains in shock, indicating Class IV blood loss of more than 40 % blood volume, and requires emergency surgery – surgery as part of resuscitation – or is triaged to Category IV in a mass casualty situation (see Chapter 9);

or

other, less common pathologies that become manifest with time have been overlooked. The airway and breathing should be re-assessed to diagnose a possible cardiac tamponade, tension pneumothorax, or myocardial injury. Neurogenic shock and acute gastric dilatation should not be overlooked.

Time since injury should also be taken into account to evaluate the evolution of the shock state. If grade IV shock is present less than 1 hour after injury, emergency operation is needed for resuscitation. If grade IV shock has developed in 4 hours, resuscitation is required before operation.

Warning!

Beware of resuscitation injury: "shock lung" or acute respiratory distress syndrome in patients who receive massive crystalloid infusions that overburden the heart and lungs.

8.5.4 Hypotensive resuscitation

Giving all shocked patients a standard fluid challenge of 2 litres or more has been called into question. A rapid return to normal blood pressure *before* bleeding is controlled can be associated with hydraulic disruption of an effective blood clot ("popping the clot"), a dilution of clotting factors, and a lowering of blood viscosity that causes a decrease in resistance to flow around an incomplete clot. All of these factors may cause bleeding that has temporarily stopped to start again, especially if it is a non-compressible central haemorrhage. Thus, *moderate resuscitation* may be better than aggressive resuscitation; raising the systolic blood pressure to only 90 mm Hg rather to over 100. This is known as "hypotensive resuscitation" and should be considered in Class III and IV blood loss. It should *not* be used in head trauma where any hypotension is deleterious, or in the very young or old.

Therefore, in cases of massive haemorrhage, one must strive for a balance between death from shock after primary exsanguination or an increase in bleeding by prevention of clot formation or dislodging of formed and effective blood clot with secondary haemorrhage. In these extreme cases, surgery to stop haemorrhage is part of resuscitation: this should *never* be forgotten. Hypotensive resuscitation is widely used by ICRC surgeons today for patients who arrive quickly at a hospital.

However, if evacuation is delayed (more than 6 – 12 hours), rebleeding is less likely. In addition, delayed evacuation will result in more profound shock because of plasma loss due to post-traumatic tissue oedema and general dehydration rather than pure blood loss. Excessive sweating, vomiting or diarrhoea, rough handling of the casualty during transport, and a lack of splinting of fractured limbs will aggravate the total fluid and electrolyte loss. More aggressive resuscitation is permissible under these circumstances and the patient should be fully hydrated prior to surgery.

8.5.5 Adjuvant therapy

Never give cold fluids by rapid intravenous infusion.

No effort should be spared to prevent hypothermia in the shocked patient. Intravenous fluids should be warmed (see Section 8.8.1 and Chapter 18).

Oxygen and small doses of i.v. analgesia are equally important. The best is morphine (5 mg i.v., repeated every 10 minutes as necessary). Morphine should *not* be given if there is any question of head injury or respiratory depression. A good alternative in this case would be tramadol. Analgesia in shock should be given intravenously only.

A naso-gastric tube to prevent gastric dilatation should not be overlooked.

Steroids or a "vitamin C cocktail" should *not* be administered in cases of haemorrhagic shock.

Some clinical experiments have taken place using hypertonic saline for resuscitation. ICRC surgical teams have no experience in this and cannot comment.

8.6 Blood transfusion where supplies are limited

Where blood supplies are scarce, what should the role of blood transfusion be? This scenario is a far cry from optimal conditions in which there are relatively few limits to blood or component administration, yet it is common.

The aim of blood transfusion is to save life or to prevent significant morbidity, and *not* to restore a normal haemoglobin level. Blood is a rare and expensive commodity with serious risks attached to its administration and it should therefore be used with caution. The decision to give blood to a particular patient should be based primarily on the clinical state correlated with the laboratory findings, balanced against the risks and the shortage of supply. A better understanding of the physiology of oxygen transport, the shortage of donors and the increased risk of viral infections has led to a policy of accepting lower levels of haemoglobin than before, without overly detrimental effects to the patient. One should avoid a transfusion for reasons such as "accelerating the patient's recovery", increasing patient comfort, or providing a supplement to correct anaemia. (Certain medical conditions, such as small children with severe malaria are an exception to this last rule.)

ICRC policy is to screen donated blood for hepatitis A, B and C, HIV, syphilis, and – in non-endemic areas – malaria. In countries where malaria is endemic, it is not uncommon for trauma patients to have a malarial attack 2 to 3 days post-operatively even without a blood transfusion; this is treated when it occurs. Where donors are scare, they are not excluded because of malaria. A blood transfusion can never be 100 % safe.

The ICRC seeks blood donors in the community. Family, friends and clan members are usually the source. In certain countries, the National Red Cross/Red Crescent Society plays an important role in the collection of blood.

Culture and tradition in some societies may render blood collection extremely difficult; consequently, blood for transfusion is often in very short supply. Accordingly, and in keeping with the principles of triage, a maximum number of units of blood per intervention is set in ICRC practice. Today, this is usually about 4 units, and this figure should only be exceeded in cases of anti-personnel landmine injury with traumatic amputation and severe burn patients undergoing skin grafting. (Early tangential debridement with immediate skin grafting is not practised by ICRC teams, partly because of the risk of major blood loss.)

ICRC practice has been to transfuse whole blood, as fresh as possible. Otherwise, whole blood is stored with CPD-A anticoagulant (citrate – phosphate – dextrose – adenine). Blood components are not available in ICRC surgical programmes as is the case in many rural public hospitals. In practice, this has not been considered a handicap.

8.6.1 Clinical use of blood in ICRC practice

- Blood should not be given during resuscitation until bleeding has been controlled.
- Crystalloids and/or colloids are administered first: if the patient remains haemodynamically unstable *and* the haemoglobin is less than 6 g/dl, blood is administered. Haemoglobin less than 6 but in a stable patient is *not* an indication for transfusion. (However, there is a threshold haematocrit value of 5 – 10 %, below which continued crystalloids or colloids can provoke cardiac arrest by "washout anaemia".[3])
- In the non-resuscitation scenario (preparing the patient for a second operation), pre-operative transfusions are not administered where blood supplies are low, unless the patient is anaemic *and* symptomatic.
- The blood supply and stocks determine whether a particular patient will receive blood: the principles of triage apply.
- Consider autotransfusion where appropriate (see Section 8.6.4).

If massive transfusion of stored blood is necessary, every second unit should be supplemented with one ampoule of sodium bicarbonate (44.3 mEq) and one ampoule of calcium chloride (10 g) by a separate i.v. line. As with crystalloid fluids, blood should be warmed to body temperature to avoid increasing hypothermia. This can be achieved through the use of locally-made water baths or the body heat of staff members.

8.6.2 Two unit rule

It has been traditional practice to administer not less than 2 units of blood to any patient who requires transfusion. In the ICRC context, this rule is not always appropriate since extreme shortage of blood is so common. It is sometimes more apt to prescribe just one unit to certain symptomatic patients as this may improve their condition sufficiently, thus allowing supplies of this scarce resource to be kept for other patients in need. This is particularly true for patients in danger of "washout anaemia". World Health Organization (WHO) guidelines also accept one unit of blood in case of symptomatic anaemia.

---

[3] Takaori M, Safar P. Treatment of massive hemorrhage with colloid and crystalloid solutions. *JAMA* 1967; **199**: 297 – 302. Cited in Barkana Y, Stein M, et al. Prehospital blood transfusion in prolonged evacuation. *J Trauma* 1999; **46**: 176 – 180 and Shoemaker WC, Peitzman AB, Bellamy R, et al. Resuscitation for severe hemorrhage. *Crit Care Med* 1996; **24(2Suppl.)**: S12 – S23.

8.6.3 Fresh whole blood

This is best when screened and given within one hour of collection. Fresh whole blood is especially reserved for:

- massive haemorrhage;
- coagulopathy;
- septic shock;
- non-trauma pathologies:
  - snake bite with haemolysis
  - amniotic fluid embolism.

8.6.4 Autotransfusion

When faced with patients suffering massive haemorrhage and inadequate blood supplies, ICRC surgical teams have practised recuperation of shed blood and autotransfusion. Haemothorax and haemoperitoneum from the spleen, liver or ruptured ectopic pregnancy are the most common indications.

For further information on autotransfusion in acute haemorrhage, see Volume 2.

8.6.5 Total blood requirements: the ICRC's experience[4]

ICRC colleagues studied total blood requirements for 4,770 patients in two hospitals treating the wounded from the war in Afghanistan during a six-month period in 1990 – 91. No differentiation was made for blood transfusion given pre-operatively, peri-operatively, or immediately post-operatively: all were considered part of patient resuscitation given the difficulties and delay in obtaining blood. Guidelines at the time allocated a maximum of 6 units per patient (although this was exceeded in some cases) and a limiting haemoglobin level of 8 g/dl. Autotransfusion was not used in this series.

A comparison was made of the number of units transfused according to time since injury for all wounded patients and separately for those with central injuries (head, neck, chest, and abdomen), and according to the cause of injury.

Need for transfusion was greatest for patients arriving less than six hours after injury, steadily decreasing to those arriving after 72 hours. This was true for all patients. Surprisingly, patients with central injuries required less blood, on average, than those with peripheral wounds.

The most remarkable results were associated with the cause of injury. Blood requirement for anti-personnel landmine injuries far exceeded that for bullets or fragments, (Table 8.3) and was the main reason for the high blood use in peripheral injuries.

	Mine	Fragment	Gunshot	Burn
Patients	787	2,577	1,016	111
Percentage transfused	27.9 %	13.1 %	15.0 %	18.0 %
Average transfusion units/ patient transfused	3.7	2.6	2.7	4.1
Average units/100 patients	103.2	34.1	40.5	73.8

Table 8.3 Blood given to patients related to cause of injury: 279 patients were categorized under "other" injuries.

---

[4] Eshaya-Chauvin B, Coupland RM. Transfusion requirements for the management of war injured: the experience of the International Committee of the Red Cross. *Br J Anaesth* 1992; **68**: 221 – 223.

Consequently, ICRC recommendations for a hospital undertaking total surgical care of the wounded from conventional warfare were amended as follows:

- for every 100 war-wounded patients, the blood bank should expect to provide 45 units as a baseline;
- baseline should be increased to 60 units, if the majority of patients are admitted within 6 hours of injury;
- baseline should be increased to 100 units, if anti-personnel landmines are widely used in combat;
- burn patients require greater transfusion capacities, even in the absence of early tangential excision with immediate grafting (not practised in ICRC hospitals);
- long evacuation lines with much delay and no use of anti-personnel landmines in combat may negate the need for a blood bank, and blood for transfusion should be collected on an individual patient basis.

These recommendations may have little relevance to a modern industrialized army with very early evacuation and resuscitation but may be quite relevant in conditions of limited resources.

Please note:

ICRC guidelines have become even more stringent since: 4 unit limit and 6 g/dl haemoglobin level *with* unstable haemodynamics.

8.7 Disability

Any neurological deficit must be determined, whether central or peripheral. As mentioned previously, if the mechanism of injury is blunt trauma above the level of the clavicles then the cervical spine must be cared for in the classical manner.

According to the nursing expertise available, the AVPU system may be used or one may proceed immediately to the Glasgow Coma Scale (GCS) for the determination of the level of consciousness and any traumatic brain injury (Table 8.4). Although the GCS was originally intended for closed trauma to the head, and there are certain shortcomings when dealing with penetrating head trauma, nonetheless, it has been ICRC practice to use it.

	Response	Score
Eye opening	Spontaneous	4
	To verbal command	3
	To pain	2
	No response	1
Verbal response	Orientated and conversing	5
	Disorientated	4
	Inappropriate words	3
	Incomprehensible sounds	2
	No response	1
Motor response	Obeys verbal command	6
	Localizes pain	5
	Flexion-withdrawal	4
	Flexion-abnormal	3
	Extension	2
	No response	1

Table 8.4 Glasgow Coma Scale: the best response for each variable is scored. Maximum score is 15, minimum is 3.

A GCS < 8 indicates severe head injury and airway protection is mandatory, by intubation or cricothyroidotomy/tracheostomy.

Disability examination includes the entire vertebral column/spinal cord: presence of paraplegia, level, etc. Palpation of the vertebrae, one by one, for tenderness, induration and crepitus is more important than deformity, which may be masked by haematoma. A rectal examination to determine sphincter tonus is important for prognosis!

Proper stabilization measures should be undertaken and a urinary catheter placed. Neurogenic shock is common in paraplegic patients: fluid resuscitation and an i.v. vasopressor are often required.

For the management of paraplegic patients, see Volume 2.

8.8 Environment/exposure

Hypothermia must be avoided at all costs – rapid, yet thorough examination of the patient – and treated aggressively. With a core body temperature of 37° C, an ambient temperature of 32 – 34° C is considered neutral. Less than this and the body loses heat to the environment. After examination, the patient should be kept covered, even in a tropical climate.

8.8.1 "Fatal triad" of coagulopathy, acidosis, and hypothermia

Recently, the importance of the potentially "fatal triad" of hypothermia, acidosis, and coagulopathy in trauma patients has become recognized. Hypothermia (core temperature less than 35° C) is probably the most potent factor in causing the vicious cycle of this syndrome.

Every effort should be made to preserve heat in an injured patient, since rewarming consumes far more energy than maintaining normothermia. Warm inhaled O_2, warm i.v. fluids, and external rewarming to a maximum of 40 – 42° C should be the first step. More aggressive measures of "central reheating" such as rectal enema and gastric, bladder and peritoneal lavage (at 37° C) can be used.

Post-traumatic coagulopathy is a well-recognized danger in patients suffering severe shock and submitted to aggressive resuscitation, especially if they have received massive amounts of i.v. fluids and blood transfusions with stored blood. It results from a combination of factors. Fresh whole blood transfusion is very useful in the absence of blood components, and probably in their presence as well (see Chapter 18).

8.9 Complete examination

At this stage it is even more important than in the pre-hospital setting to undress the patient and perform a thorough examination, from head to toe, front and back and sides. In some societies, this may contravene certain cultural and religious traditions (male doctor examining a female patient). Compromises must be found.

In the more accommodating atmosphere of a hospital emergency room, a systematic approach should be used to thoroughly examine the scalp and head (mouth, nose, and ears), neck, thorax, abdomen, perineum (scrotum and urethra, rectum, and vagina), the back of the trunk and buttocks, and the extremities. The peripheral pulses, temperature and capillary refill are compared on both sides. Motor function of the main peripheral nerves is tested. The aim is to have a complete assessment of all injuries and a more accurate assessment of the organ-specific damage.

The complete examination is best described as a thorough palpation. The entry wound may be exceedingly small and not seen. This is especially the case with fragment wounds to the head or perineum where body hair matted with blood can easily hide the wound (Figure 8.6). The entry wound must be identified by close palpation. Remember also that contusion/erythema can be better felt rather than seen in dark-skinned people.


M. Baldan / ICRC

Figure 8.6

Small temporo-zygomatic entry wound hidden by hair.

One should attempt to identify the likely path through the body of the projectile. This may involve any structure between the entry and exit wounds, or the position of the projectile on X-ray if no exit exists. Remember that wounds to the chest, buttock, thigh or perineum may involve the abdominal cavity (Figures 8.7.1 – 8.7.3).



H. Nasreddine / ICRC

Figure 8.7.1

Bullet wound to the pelvis: the entry is located on the right side. A defunctioning colostomy has been performed.



H. Nasreddine / ICRC

Figure 8.7.2

Exit wound in the left buttock.


H. Nasreddine / ICRC

Figure 8.7.3

Any structure between entry and exit should be identified: here blood is seen in the rectum.

A simple outline drawing of the body on the admission chart (homunculus), front and back, is useful for recording all injuries.

Dressings on the limbs should not be removed if the casualty is haemodynamically unstable. Only once resuscitation has begun and the patient's condition is under control is it safe to examine wounds to the extremities, preferably in the operating theatre. Fractures should nonetheless be immobilized if this has not already been done in the field.

The ABCDE paradigm should be monitored for any change in condition of the patient. Resuscitation and stabilization are continued, while complementary examinations are performed. The extent of the latter will depend on the level of sophistication and competency of the particular hospital.

A basic complement is a plain X-ray, one body cavity above and below any entry or exit wound. If no exit wound exists and no projectile is evident, further radiographs should be taken to locate its position. It may be difficult to differentiate a radio-opaque bullet from a normal anatomic radio-opacity such as the heart shadow (see Chapter 10 and Figures 8.4.2 and 14.9.1).

The complete and definitive examination will involve each specialized body system. The signs, symptoms, and treatment will be described in the relevant chapters of Volume 2.

Jung asked him how he felt about white people, Ochwia Biano (Mountain Lake) said to him, that to his people, they looked quite cruel in their appearance. “You always have an inflexible expression on your face. You always seem to be wanting something. You are always restless and agitated. We don’t know what you want. You all seem to be quite crazy.” Jung then asked him why he thought them to be crazy. He replied, “They say they think with their head”. Jung, surprised, asked him: “Of course, but tell me, where do you think?” He replied, “We think here.“ And he pointed to his heart. Jung tells how he sank into deep reflection and he remarks, “For the first time in my life, it seemed to me, somebody had shown me the image of how we really are.... This Indian had touched our weak spot and pointed to something to which we are really blind.” Jung viewed the encounter with the Indian as an opportunity, which opened to him a new gate to a primordial and nearly entirely forgotten dimension and form of consciousness which could be revived.



Fig. 9.7 *Smile into the Heart.*

In another passage in his autobiography, Jung narrates a dream which he had during a visit to an Islamic country in North Africa, which deeply touched him. In this dream he had to fight for his survival with a young Arab aristocrat who descended from his horse and wanted to drown him. Jung interpreted the dream as a struggle between his own repressed unconscious (his shadow), which sought to be recognized and accepted and his own consciousness, represented by his rational mind which felt threatened by the unsuspected attack by the young man. He then observes: “In my

8.9.1 Complementary diagnostic examinations and monitoring

Electrocardiogram (ECG) monitoring is not routinely available in ICRC surgical hospitals, neither are computerized tomography (CT) scans, angiography, sonography, Doppler blood flow, or arterial blood gases. The use of central venous pressure lines in most circumstances where the ICRC works carries too high a risk of septicaemia. Diagnostic peritoneal lavage for abdominal injury is also not practised routinely.

The minimal ICRC standards for emergency war surgery under precarious circumstances in hospital settings with limited resources include:

- plain X-ray;
- pulse oxymeter;
- haemoglobin;
- haematocrit;
- total and differential white blood cell count;
- platelet count;
- coagulation time;
- bleeding time;
- fasting blood sugar;
- blood smear for malaria (other blood parasites where applicable);
- sickle-cell test (where applicable);
- urine analysis: dipsticks, pregnancy tests;
- blood grouping, testing and cross-matching.

If more general surgery, as well as internal medicine and paediatrics, is widely practised in the ICRC hospital, then more elaborate laboratory analyses are added. In more precarious situations, as experienced by field surgical teams, none of the above is usually available.

Chapter 9

HOSPITAL TRIAGE OF MASS CASUALTIES

9. HOSPITAL TRIAGE OF MASS CASUALTIES

9.1 Introduction 191
9.1.1 The logic of triage 191
9.1.2 Where to perform triage 192
9.1.3 A delicate balance 192

9.2 Setting priorities: the ICRC triage system 193
9.2.1 The ICRC triage categories 194
9.2.2 Notes on triage categories 195

9.3 How to perform triage 196
9.3.1 "Sift" 196
9.3.2 "Sort" 197
9.3.3 Avoid undertriage and overtriage 197
9.3.4 Avoid confusion and disagreements within the team 198

9.4 Triage documentation 198

9.5 Emergency plan for mass casualties: disaster triage plan 199
9.5.1 Planning 199
9.5.2 The team 200

9.6 Personnel 200
9.6.1 Triage team leader 200
9.6.2 Triage officer 200
9.6.3 Head nurse 201
9.6.4 The team 201
9.6.5 Triage groups/nursing teams 201
9.6.6 Surgeons and theatre personnel 202
9.6.7 Rest and relief 202

9.7 Space 202

9.8 Equipment and supplies 203

9.9 Infrastructure 204

9.10 Services 204

9.11 Training 204

9.12 Communication 204

9.13 Security 205

9.14 Summary of triage theory and philosophy: sorting by priority 206
9.14.1 Triage system: a simple emergency plan organizing the personnel, space, infrastructure, equipment, and supplies 206
9.14.2 Emergency hospital disaster triage plans differ and no two triage scenarios are the same 206
9.14.3 "Best for most" policy 206

ANNEX 9. A Sample triage card 207

ANNEX 9. B Hospital emergency plan for a mass influx of wounded 208

9.1 Introduction

9.1.1 The logic of triage

In daily, routine practice surgeons face patients one by one. They use all of the means, equipment, and supplies at hand to do the most they can for every patient; they try to do everything they possibly can for every single individual. The priority is high-intensity care for the sickest.

In a single mass-casualty incident means may be stretched to the limit, but one can still manage to do the best possible for all patients. With a massive influx of wounded, however, the hospital is overwhelmed; resources cannot meet the needs of all the casualties. This is when the logic of mass casualty triage comes into play. It is no longer possible to do everything for everyone. Medics must try to do what they can: the greatest good – but not necessarily everything – for the greatest number. This is another example of the change in professional "software" – the mindset – that is called for in surgery for the victims of war.

A change of mindset: from "everything for everyone"
to "best for most".

The French term *triage*, which means to sort into groups according to quality, has been applied to the sorting of battle casualties since the time of Napoleon's surgeon of the Imperial Guard, Baron Dominique-Jean Larrey (circa 1812), who recognized the need to categorize wounded soldiers during an actual battle according to their priority for treatment.

The experience of two world wars during the twentieth century, when tens of thousands were wounded during a single battle, demonstrated the importance of sorting casualties and determining priorities for evacuation and treatment. This concept of triage has now been extended to natural disasters and single mass-casualty incidents (terrorist bombings, industrial accidents, fires in social institutions, etc.) with considerable benefit, and its use is now generally accepted worldwide.

Natural disaster triage, however, is not the same as war triage. An important natural disaster is a single mass-casualty event that overwhelms hospital services; the wounded suffer injuries at one time, but there is then a respite. The same can be said for other mass-casualty incidents. Armed conflict on the other hand can involve a continuing mass arrival of freshly wounded victims that may go on for weeks or months on end; there may be no respite until the end of hostilities. Nonetheless, many of the fundamental concepts underlying war triage apply to the disaster scenario.

Establishing priorities for treatment amongst many casualties is the most difficult decision to be taken in all of medical practice. Patients with very severe wounds whose management consumes many resources and much time, and who have little chance of survival despite treatment, may have to wait or may only receive minimal care in the interest of being able to intervene effectively for the others. One must often choose to treat first the patients for whom the smallest surgery gives the biggest results; i.e. the wounded who, though seriously injured, stand a fair chance of "good survival".

The aim in a mass casualty situation is to do
the "best for most".

Some armies have practised "inverted" or "reverse" triage: the least injured were treated first so as to make them able to return more quickly to the battlefield! It should be noted that this practice contradicts the principles of international humanitarian law.

The practice of triage is not dogmatic. It is not a series of rules, but a logical approach and philosophy that must be adapted to each and every particular situation.

9.1.2 Where to perform triage

As mentioned in Chapter 1, one of the special characteristics of surgery in times of war is the staged management of patients in a chain of casualty care. The principles of triage are applied at every stage.

Triage takes place at every echelon of the chain of casualty care, including during evacuation.

The organization of a casualty collection point and effective triage permits the orderly evacuation of the wounded, the most efficient use of stretchers, ambulances or other transport, and the optimal use of medical and surgical personnel available. With the necessary training, rapid assessment of casualties can be carried out not only by doctors, but also by nurses, paramedical staff and first-aid workers. It should be possible to implement triage at *any point* along the chain of casualty care, in order to set *priorities* for first aid and evacuation of the wounded to the next echelon of treatment.

More efficient lines of evacuation and shorter duration of transport, coupled with better pre-hospital care, ensure that a greater number of the severely injured will survive to reach a surgical hospital. The number of KIA decreases; however, the DOW rate often increases (see Chapter 5).

In many low-income countries, however, civilian casualties often arrive at the hospital without having received first aid and without the help of an ambulance service. In this case the less seriously injured usually arrive first. The hospital then becomes the first triage station.

Whatever the prior treatment or sorting, however, triage must be carried out again when casualties reach the hospital; the condition of patients changes and the priorities in the hospital may be different from those in the field. All patients arriving at the hospital during an influx of casualties go through the triage process.[1]

9.1.3 A delicate balance

To set priorities for patient management a number of factors must be taken into consideration to define the needs on the one hand, and the resources available on the other. The practice of triage is a fine balance between these two.

Triage is a dynamic equilibrium between needs and resources:

- needs = number of wounded and types of wounds;
- resources = facilities at hand and number of competent personnel available.

Needs

- How many patients are arriving? 10, 50 or 100?
- Are they all suffering from penetrating injuries? Or are there many burn cases amongst them?

The number of wounded and the different pathologies should be taken into account in the total workload. Penetrating wounds will require a great deal of surgery. Burn patients require relatively little immediate surgery, but a great deal of nursing care.

---

[1] For field triage, see Giannou C, Bernes E. *First Aid in Armed Conflicts and Other Situations of Violence*. Geneva: ICRC; 2006.

Resources

- How many surgeons and anaesthetists?
- How many operating tables?
- How many instrument boxes, and what is the efficiency of the sterilization system?
- How many beds? etc.

A hospital may have three fully-equipped operating theatres, but if there is only one surgeon then only one patient can be operated at a time. If there are three surgeons and three anaesthetists, but only one theatre, then the team must improvise extra operating facilities, if there are sufficient boxes of surgical instruments.

ICRC EXPERIENCE

During fighting in Kabul in 1992 with an influx of mass casualties, four surgical teams worked in the ICRC hospital, supplemented by Afghan general practitioners with some surgical experience. There were two operating theatres in different buildings with 4 tables that could function at the same time. One team operated in one building and one in the other; the third team performed triage; and the fourth was resting!

All these factors – needs and resources – must be balanced out. No two triage situations are the same. It is this constantly changing equilibrium between needs and resources that will determine the priority for treatment among all the patients who reach the hospital. One cannot be dogmatic about which patient to operate first, since no two situations are the same. Only a full understanding of the logic and philosophy of triage will help to establish efficient priorities that will result in the best treatment possible for the greatest number of victims.

9.2 Setting priorities: the ICRC triage system

There are a number of triage category systems used throughout the world today. Some are more sophisticated than others and depend on injury severity scores and physiological parameters. There are two important factors to keep in mind when deciding upon a system to use in a hospital.

1. It should be kept as simple as possible – a mass influx of wounded always creates confusion, tension and anxiety.
2. All members of the hospital team should understand the system being used.

The ICRC uses a triage category system based upon several factors.

- Physiological appreciation of life-threatening conditions according to the ABCDE protocol – in practice, severe haemorrhage will constitute the great majority of life-threatening injuries during armed conflict (see Chapters 5 and 8).
- Anatomic factors, including the Red Cross Wound Score for penetrating injuries – in general, vital injuries (head, neck, thorax, abdomen and major peripheral vessels) will have priority, but the grade of injury must also be taken into consideration (see Chapter 4).
- Mechanism of injury – especially anti-personnel landmine injuries and burns (see Chapter 3).
- Time since injury – important for determining degree of shock and response to resuscitation as well as limb ischaemia (see Chapter 5).
- Epidemiology of the war-wounded – knowledge of the relative numbers of severe and superficial wounds (see Chapter 5).

9.2.1 The ICRC triage categories[2]

Category I: Serious wounds – resuscitation and immediate surgery

Patients who need lifesaving surgery and have a good chance of recovery. Some examples include:

- airway – injuries or burns to the face and neck requiring tracheostomy;
- breathing – tension pneumothorax, major haemothorax;
- circulation – internal haemorrhage, wounds to major peripheral blood vessels, traumatic amputation.

Category II: Second priority wounds – can wait for surgery

Patients who require surgery but not on an urgent basis. In practice this applies to many casualties, including:

- penetrating abdominal injury in haemodynamically stable patient, most probably injury to hollow organs only;
- penetrating head injuries with GCS > 8, providing definitive airway control can be maintained – if a surgical airway is necessary, then Category I for tracheostomy only;[3]
- most compound fractures: in practice, a large number of the wounded;
- major soft-tissue wounds: in practice, a large number of the wounded.

Category III: Superficial wounds – ambulatory management

Patients who do not require hospitalization and/or surgery because their wounds are so minor that they can be managed on an ambulatory basis.

They are often called the "walking-wounded". In practice, this is a very large group including those presenting superficial wounds managed under local anaesthesia in the emergency room or with simple first-aid measures.

Category IV: Severe wounds – supportive treatment

Patients with injuries so severe that they are unlikely to survive or would have a very poor quality of survival. These include the moribund, or patients with multiple major injuries whose management could be considered wasteful of scarce resources in a mass casualty situation in terms of operative time and blood. Examples include:

- penetrating head wound with GCS < 8;
- quadriplegia;
- burns > 50 % body surface area;
- major blood loss and no blood available.

---

[2] The system of triage categories employed by the ICRC was revised by the Master Surgeons Workshop held in Geneva in 2002 (see Introduction).

[3] Please note: ICRC hospitals are *not* equipped with ventilators and close monitoring of intubated patients is not always possible. A surgical airway avoids many problems, and should replace an endotracheal tube if the patient remains intubated for several days in any case.

9.2.2 Notes on triage categories

The number of casualties who require urgent treatment may exceed the surgical capacity available. A second triage within Category I is then necessary (see Section 9.3.2). On the other hand, when evacuation time to the hospital is longer than 12 hours, few patients may fall into Category I.

Many surgeons believe that all penetrating brain wounds are a Category I emergency; others believe that all penetrating brain wounds are hopeless Category IV. The use of the GCS helps to differentiate those patients who will probably survive, even with some delay in operation (Category II in the experience of ICRC surgical teams) from those whose condition is definitely a Category IV. This, evidently, provided the airway is patent.

The Category III superficially wounded may be so numerous, frightened, in pain and excited, that their uncontrolled presence in the emergency room/triage area creates great confusion. In urban contexts, they tend to be the very first evacuated to hospital, to the detriment of the more seriously wounded.

The categories are not rigid; patients waiting for surgery may change category and a single patient may fall into two categories, such as one with severe maxillo-facial injury who requires an immediate tracheostomy and basic haemostasis (Category I), while the debridement and primary reconstruction of the patient's face, which may take many hours, can wait (Category II).

Please note:

There is one exception to these categories: when an excited, and often drunk, combatant holds a gun to your head and demands that you treat his wounded comrade first. This patient immediately becomes top priority.

ICRC EXPERIENCE

Two examples of the epidemiology of triage patients recorded in recent years.

Fighting in Kisangani, Democratic Republic of the Congo, June 2000

Four hospitals and 62 clinics registered a total of 2,393 wounded. Only 25 % required hospital care, and even less a surgical operation. The vast majority were Category III and could have been treated as ambulatory cases; many were hospitalized for several days nonetheless.

Combat in Monrovia, Liberia, June – August 2003

2,567 patients were triaged in the JFK Memorial Hospital, but only 1,015 were deemed to require hospital admission (40 %), only 718 of whom (71 %) underwent operation. Of those admitted, some did not require any operation (paraplegia), while for many others there was simply not enough time or human resources available. Many patients who were originally placed in Category II – and given antibiotics, dressings and analgesia – eventually became Category III, with and without sequelae.

The equilibrium – between needs and resources – is a dynamic one; change is constant, no two triage situations are the same.

9.3 How to perform triage

Triage is a dynamic process: it requires a continuous reassessment of patients.

Patients may change triage category: their condition may deteriorate, or improve over time and with pre-operative resuscitation. As a result, a continuous reassessment of patients is absolutely necessary.

Triage is a multiple-step process: "sift and sort", then re-examine, re-examine, re-examine. "Sift" involves placing the patient in a general Category; "sort" then decides priority within that Category.

9.3.1 "Sift"

On reception of the casualties in the hospital, the triage officer must perform a rapid examination of each patient – a maximum of 30 seconds – checking the whole body, including the back. Field dressings should be changed by the nursing team as part of the examination; except for obviously large and severe wounds whose dressings are removed only in theatre. Severity of injury and probability of survival are the keys to decision-making. Clinical experience with the war-wounded – not training or reading books – is the most important preparation for this task.

To sift, the triage officer first looks for life-threatening conditions based on:
- airway, breathing, circulation;
- important physiological clues (mental status, character and rate of pulse, ease of respiration);
- anatomic site of wounds (head, chest, abdomen);
- severity of obvious wounds according to the RCWS (amputation of limb, etc.).

Based on clinical judgement alone, a first decision is made, to "sift" the casualty into a Category. The Category does *not* depend on how many patients arrive with serious wounds.

Every wounded patient must be examined *and* categorized immediately.

The idea is to quickly recognize the two extremes of injury, which, together, comprise a very large number of casualties: the very minor (Category III) and the very serious (Category IV); and to identify and separate out the dead. As little time as possible is spent on these Category III and IV patients and they must quickly be removed from the triage area to specially designated areas.

The triage officer concentrates on the critically and seriously injured (Categories I and II):
- patients who require resuscitation and immediate surgery as part of the resuscitation process;
- those who need continuing resuscitation; and
- patients who will tolerate some delay before receiving surgical attention.

The triage officer should not perform *treatment*, with one exception: if the patient is not breathing, the mouth should be opened and cleaned and the person put in the lateral recovery position, before the next patient is dealt with.

Å. Molde / ICRC

Figure 9.1
Triage officer assisted by an administrative clerk.

An "administrative team" consisting of a nurse and a clerk supports the triage officer for purposes of documentation, including all personal details of each patient, the securing of their identity papers and valuables, and the signing of any necessary consent forms. Other supporting personnel present at the entrance or in the triage area include those responsible for hospital security and crowd control.

Initial treatment is started by a dedicated team, and patients should be transferred as quickly as possible out of the triage area to theatre or the ward designated for their triage Category in order to make room for new arrivals. Resuscitation, as necessary, is continued in these assigned areas.

unconsciousness, I was in no way aware of such a situation; on the contrary I could not undo myself from a feeling of superiority, as at every step, I was reminded of being a European. I was not prepared to meet the unconscious forces within me, which emerged with such an intensity on behalf of the opposing party and which led to such an intense conflict."

Only several years later did Jung begin to understand the deeper nature of the dream. He began to see in the dream the resurgence of primordial structures or patterns in himself from a well-known past, but a past he had forgotten. He perceived the resurgence of these images as a renewed awareness of a still available potential for life, which was overgrown by civilization, a potential for life, which had been repressed and marginalized into the sub-conscious. In Jung's view, Western culture had become alienated to much of what being human represents: the primordial dimension of our being, which had been relegated to the underground.

Jung was a great admirer of the Taoist tradition and expressed his deep appreciation for its originality and wisdom in writing the foreword for the translation of the *I Ching* into German by Wilhelm Reich (the first translation into a European language).

The split between body and mind, thinking and feeling, matter and spirit, at the root of the formation of Western culture and religion and the birth of modern science, has been aggravated in the course of this century.

Feminine Underground Current

Some historians and scholars, like Morris Berman in his path-breaking studies "The Re-enchantment of The World" and "Returning to Our Senses" have argued, that in the course of this process the feminine dimension of European culture greatly suffered and in order to survive had to make itself invisible and so became its undercurrent. He means by this that in religion, with its reliance on external authority and its contempt for the body as well as in science, with its pursuit of objectivity, at the expense of other sources of cognition, the body was devalued.

Subsequently it could be turned into a mere object, an input and an instrument. It was seen in function of externally determined aims, as defined by the forces of competition, economic rationality and rational management and the new forms of communications

The use of X-rays should be *limited*; it is seldom essential under these circumstances and the triage officer should not wait for an X-ray to decide on the triage Category.

An identifying tabard or armband stating "triage officer" is useful; if, inevitably, the triage officer must move away from the triage area this can be handed over to the deputy/replacement.

9.3.2 "Sort"

After "sifting" casualties into the general Categories, a second examination is performed: "sorting". No two triage situations are equal and, therefore, according to the number of competent personnel available, the triage officer or a second physician-in-charge continues the reassessment of patients within the Category I cohort. "Sorting" decides which of the Category I patients to send to theatre first: *priority amongst the priorities*. The others, while waiting, remain under close observation and continued resuscitation.

This re-examination may reveal patients with an "emergent" condition who should receive priority over the stable: e.g. one of two Category I patients with penetrating abdominal wounds becomes haemodynamically unstable because of continuing internal haemorrhage, while the other has a stable pulse and blood pressure because bleeding has stopped.

The surgical teams should begin operating on Category I patients immediately. Since the number of casualties cannot be foreseen, it is not possible to wait for all patients to arrive and be triaged before deciding which should be taken to the operating theatre first.

When in doubt about priority amongst Category I patients, put in chest tubes and send in a laparotomy; get going!

The triage officer must keep in close contact with the operating theatre, to reassess continuously the priorities of the operating list.

The time that patients are waiting for surgery can be profitably used for completing X-rays and laboratory analyses, if necessary, but should not interfere with resuscitation efforts.

The same logic applies to the patients in the other Categories. Either the triage officer or the person in charge of the department re-examines the patients in Category II. Priorities are set for the operating list among the Category II patients.

Reassessments may result in changing a patient's Category. The condition of a patient originally triaged into Category III because he had no *obviously* serious wound may suddenly deteriorate and become Category I or II. If a second-in-charge is continuing the reassessments, a system must be available to transfer patients from one Category area to another. Referring back to the triage officer for every decision will only result in overburdening him.

Usually the hardest part of triage is having to accept that some patients may only receive analgesics and be removed to a quiet place where they can die in comfort and with dignity. After treatment of priority patients has been completed, a repeat examination of Category IV patients, if still alive, may allow the triage officer to contemplate surgery for them at this stage.

9.3.3 Avoid undertriage and overtriage

In undertriage the assessment underestimates the severity of injury and the patient is not given sufficient priority. Overtriage overestimates the injury, and a patient is assigned to a higher Category than necessary. This will divert resources from the truly seriously injured and overburden the critical care services. Repeated re-examinations will correct these errors.

It may be necessary to transfer minimal care patients to other sites for convalescence, even outside the surgical hospital. If this is done, care should be taken to identify patients for follow-up treatment and administration of medication, and to exercise some control over their whereabouts. Documentation is important: patients can easily get lost.

9.3.4 Avoid confusion and disagreements within the team

Triage decisions must be respected.

There is no time or place for disagreements during a triage of mass casualties. The decisions of the triage officer must be "dictatorial". The post-triage evaluation session is the place for "democratic" discussion and constructive criticism.

In spite of training, practising and planning, the unexpected will happen. The hospital team – led by the team leader, triage officer, head nurse – will at times have to improvise and invent new protocols and procedures to meet new circumstances. One should not be dogmatic, but rather understand the philosophy and logic of the triage process, and adapt to new situations in accordance with that logic.

9.4 Triage documentation

Good records are essential and no effort should be spared to record important aspects of the wounds, treatment, and the patient's triage category.

Each casualty should be appropriately identified, numbered, and assigned a medical chart. Large plastic bags, labelled with the patient's number, are used for clothing; smaller labelled plastic bags are used to collect patients' valuables. They are stored separately and the valuables put in a safe place.

Some system must be devised for indicating the patient's triage Category. This could be colour-coded tags tied around a hand or foot, or hung around the neck. These are easily removed and changed should the patient's triage Category change. Writing an "indelible" number on the forehead or chest only creates confusion with a change in Category.

The patient's medical chart should include basic information and be in telegraphic style: clear, concise, yet complete. It should include *at least* the following information:
- name, age, sex, time of injury, cause of injury, any first aid given;
- time of admission to hospital;
- vital signs: BP, pulse, respiration rate, neurological status;
- diagnosis: using a diagram (homunculus) is very useful;
- triage Category;
- complete pre-operative orders.

See Annex 9. A: Sample triage card.

This basic information is particularly important if patients are being transferred to another facility. A list of admitted or treated patients is necessary so that people who come looking for their relatives or friends may be informed. The local authorities may require information about the number of admissions and deaths. The media must be dealt with. These issues are addressed by the triage team leader, or replacement.

ICRC EXPERIENCE

During the post-triage evaluation, it was decided to use a plastic sleeve to hold the triage cards in order to protect them from various body fluids.


ICRC

Figure 9.2

State of the admission card after triage.

9.5 Emergency plan for mass casualties: disaster triage plan

Any hospital treating the war-wounded must be prepared to receive large numbers of casualties. Preparation means planning and training.

9.5.1 Planning

The triage tent in Figure 9.3 shows a number of key points:
- there is enough space to move around;
- the small lightweight beds/stretchers that are easily moved and inexpensive;
- small carts for emergency medical supplies;
- i.v. fluids hanging on a rope strung across the room, for flexibility of patient placement;
- a patient carried on a stretcher by dedicated bearers;
- relatively few staff members present, getting on with their allotted tasks in what appears to be a calm atmosphere.

This scene illustrates proper organization, which requires planning of the space, infrastructure, equipment, supplies and personnel.


ICRC

Figure 9.3

Inside a triage tent.

Figure 9.4 shows the premises surrounding a triage tent:
- the site is temporary;
- space is available to receive ambulances or to expand the facilities;
- the structure is lightweight and easy to set up or take down;
- the structure is inexpensive;
- there is a water tower nearby;
- there is a rubbish bin outside.

This scene illustrates proper organization, which involves planning of the space and infrastructure.


ICRC

Figure 9.4

Outside a triage tent.

A triage system cannot be organized ad hoc:
it requires planning and training.

The hospital team must be prepared for any kind of crisis: every hospital should have a disaster/triage plan (see Annex 9. B: Hospital emergency plan for mass influx of wounded). The aim of the plan is to organize:
- personnel;
- space;
- equipment;
- supplies (medical and non-medical);
- infrastructure (water, fuel for electricity generators, etc.);

- services (laundry, kitchen and cafeteria, etc.);
- training of the hospital team;
- communications;
- security.

9.5.2 The team

The hospital team should hold a series of meetings, to discuss the organization of the disaster/triage plan. Everyone working in the hospital should be aware of the plan and their respective role during a crisis. The plan should be posted so that everyone is well acquainted with it.

The plan should be put into operation as soon as notice is given of the expected arrival of mass casualties. It should include the mechanism for deciding who declares the emergency and under what conditions to implement the plan. The ordinary operating list and other routine activities should be suspended until the situation is resolved. This kind of organization does not require money or special technology; only time, effort, discipline and motivation. Any disaster plan should be an extension of the normal hospital routines, and the roles allocated to individual staff remain as close as possible to their familiar daily work. The plan should not be a complete change in the system. Introducing many new procedures will only add to the confusion.

A simple emergency plan: personnel, space, infrastructure, equipment, supplies = system.

9.6 Personnel

There are three key leadership functions in a disaster triage scenario: triage team leader, triage officer, head nurse.

9.6.1 Triage team leader

The triage team leader is the coordinator. He is usually designated to announce the onset of the hospital triage plan; he then coordinates the work of the different units and services, and makes sure that all departments are informed. The triage team leader maintains an overview of the situation, including a constant reassessment to determine the need for additional staff, supplies, and ward areas. In addition, he must be aware of events outside the hospital, maintaining contact with relevant authorities in order to anticipate any new arrival of casualties due to continuing combat.

9.6.2 Triage officer

The triage officer performs the actual clinical triage, assigning a category to each and every patient on entry. There has been much discussion about who should perform triage: surgeon or anaesthetist? Again, there is no strict rule. Each hospital team must decide according to its circumstances.

The logic of triage demands that the most experienced and respected person willing and able to take on the responsibility should do so. This person must know how to organize the emergency room/triage area and have a good understanding of the functioning and capacity of the hospital.

Even more importantly, the hospital team must be able to live with the decisions taken by the triage officer. Staff members, relatives, and military commanders might try to influence the triage decisions; nevertheless, these should be made on purely medical grounds. This can be especially difficult in a public hospital where friends and family members of the hospital staff may be among the victims. Deciding priority of treatment solely on the basis of medical need and resources available when the injured include close relatives of the personnel may be a heart-wrenching decision.

The hospital staff must be able to continue their work and live with the triage decisions for the rest of their lives. As a consequence, the experience of the triage officer and the respect with which the personnel hold the triage officer must be beyond reproach.

Triage Officer

No task in medicine requires greater understanding, skill, and judgement than the categorization of casualties and the establishment of priorities for treatment.

9.6.3 Head nurse

The head nurse organizes the nursing and paramedical personnel (laboratory, pharmacy, etc.) and non-medical support staff (trolley orderlies/stretcher-bearers, kitchen, laundry, cleaning, etc.). This is largely a coordination function. Any clinical role or supervision by the head nurse will depend on the particular circumstances of the hospital involved.

9.6.4 The team

Whether one person fills more than one leadership function will depend on the availability of competent personnel. The triage team leader may be the same as the triage officer in a small hospital; in a larger facility, this coordination function is probably best assigned to someone else, for instance an administrative officer or the head nurse. In a very large hospital, three different people should assume the three functions.

ICRC EXPERIENCE

What is the reality in the field?

In many small rural hospitals, the only surgeon is also the director. This one person often becomes the triage team leader and triage officer. After performing triage, the surgeon and the only anaesthesia nurse go to the operating theatre. A new influx of casualties arrives. Who then performs triage? Who continues the necessary coordination tasks? Either a general practitioner or the head nurse. This should be decided upon beforehand and be part of the hospital's disaster plan.

The ICRC supports the Somali Red Crescent Society in running the Keysaney Hospital in north Mogadishu, where triage has been routinely practised from 1992 until the time of writing. The triage officer in the emergency room is an "experienced female nurse, because she is the only one who can organize things".

9.6.5 Triage groups/nursing teams

Such teams should be formed for the triage area, with responsibility for the following tasks.

1. Setting up intravenous lines and taking blood for grouping and cross-matching.
2. Administration of tetanus prophylaxis, antibiotics, analgesics and other medication as prescribed.
3. Dressing wounds and splinting fractures.
4. Bladder catheterization, if indicated.
5. Arranging for an orderly flow of categorized casualties to the operating theatre or to designated areas for continuing resuscitation, delayed, or minimal treatment.

The disaster plan may be nominative, designating by name the triage officer and triage groups: who is in charge of setting up i.v. lines, dressing wounds, giving analgesics and antibiotics, etc.; *or* it may designate the function (ER doctor 1, ER nurse 3) regardless of who is on the roster that day (Figure 9.5). This depends on the staffing system, and availability of personnel, of the particular hospital.



GENERAL DISASTER PLAN OF ADI-UGRI HOSPITAL

If disaster is notified, the emergency room (ER) or first aid staff or the hospital should take the following steps or phases.
1. Inform senior medical staff or director.
2. Activate a disaster plan.
3. Actual scene with patients i.e. – screen/triage (first aid, OPD, and/or wards).
_Intervention/decision

ORGANISATION OF DISASTER TEAMS

I. TRIAGE (screening) TEAM: 1 or 2 doctors – [illegible]
1 or 2 nurses – [illegible]

II. RESUSCITATION TEAMS (A,B,C etc.)

Team "A": serves all teams in OPD, OR and/or wards.
1. Surgeons = (a) [illegible] (coordinator) (b) [illegible]
2. Anesthetist = [illegible]
3. Lab. tech. = (a) [illegible] (b) [illegible]
4. Dental clinician = [illegible]
5. Supply officer/messenger = [illegible]
6. All other OR staff
7. Stretcher-bearers = National services and gardeners.

Team "B": Nurses and health assistants (in the screening area).
1. Head nurse or coordinator = [illegible]
2. Vital sign taking = Nurse [illegible] Nurse [illegible]
= H.A. [illegible] H.A. [illegible]
3. Infusion setting = Nurse [illegible] Nurse [illegible]
= H.A. [illegible] H.A. [illegible]
4. Dressing = Nurse [illegible] Nurse [illegible]
= H.A. [illegible] H.A. [illegible]
5. Medication = Nurse [illegible] Nurse [illegible]
= H.A. [illegible] H.A. [illegible]
6. Messenger (runner) = H.A. + Others [illegible]
7. Supply = Pharmacy Tech. Or equivalent = [illegible]

Team "C" = reserves and standby:
All pharmacy, X-ray, Lab Tech .... + all administrative staff

III. CONTROL (COORDINATING) TEAM:
1. Medical director [illegible]
2. Administrator [illegible]
3. Matron [illegible]
4. Others if necessary (police etc...)
Room = Medical Director's or Administrator's Office

IV. MOBILE (FIELD) TEAM = 2 nurses + one/two health assistants
- When necessary to help casualties at the scene
- Role is to rescue, triage and life-saving treatment only
- Decision to send a team = by medical director/ senior doctor surgeon.
- If patients can arrive within 30', then send an ambulance only.

N.B. Members of teams can be increased, replaced or rotated as necessary. Each resuscitation team should have a disaster trolley or medicine-board or table for essential supplies or equipment. Example: Infusion sets, Dressing materials, BP apparatus, IV fluids, airway suction tubes, plasters etc....

M. Ghebrehiwet / MoPH Eritrea

Figure 9.5

Example of a nominative disaster/triage plan in a small rural hospital.

9.6.6 Surgeons and theatre personnel

These members of staff should have prepared the operating theatre and be ready and waiting for the casualties. The surgeon in theatre will see patients he or she has not previously examined and who may not have a name or signed consent form. Outside the mass casualty situation this would be regarded as negligent practice, and so another "mental adjustment" is required.

9.6.7 Rest and relief

Early consideration should be given to the *rest and relief* of staff. Triage is not an everyday routine activity. The shift system may need to be changed in order to deal with the increased workload: 2 twelve-hour shifts instead of 3 eight-hour ones, for example.

During a crisis the hospital team will be under severe emotional and physical stress. All staff members will need to pace themselves in order to perform efficiently and maintain a professional attitude. As mentioned before, during armed conflict there may be a mass arrival of new casualties every day for weeks on end. It is not possible to foresee how long the influx will last.

ICRC EXPERIENCE

At the beginning of the fighting in Monrovia in 2003, the surgical team worked 48 hours non-stop, without sleep: they were not able to continue operating. Subsequently, a strict 18-hour operating schedule was instituted: the team was able to maintain this schedule for three months.

A triage situation is tiring for everyone. Some, out of a misplaced sense of professional duty, find it difficult to accept that they *need* to rest; rest must be insisted upon. Working for extended periods without sleep only results in hospital staff no longer being able to adequately treat the new patients who continue to arrive.

9.7 Space

During an influx of mass casualties the various hospital departments must be re-arranged according to the pre-decided plan. Besides the original hospital site, any alternative sites (building, underground shelter, etc.) must be included in the plan, should the hospital require evacuation for reasons of security. The equivalent in cases of natural disaster is the destruction of the hospital premises and/or its access routes (earthquake, landslide, tsunami, etc.).



R. Aburabi / ICRC

Figure 9.6.1
Alternative triage department in an unused building: empty.



R. Aburabi / ICRC

Figure 9.6.2
The same premises: full.

The usual emergency reception/admissions room may not be large enough to accommodate a large influx of wounded. A large and extendable area capable of serving as a triage department should be pre-selected. The area should be cleared of all inpatients, and be large enough to permit easy movement of casualties and medical personnel.

In certain contexts, for religious and cultural reasons, it may be necessary to have separate male and female areas for incoming mass casualties. This must be taken into account during planning.

Once triaged, patients should be transferred out of the triage department to the operating theatre or designated wards.

Different units or wards should be identified for the different triage categories. Category I patients, requiring resuscitation and immediate surgery, might be put in a pre-operative intensive care unit near the operating theatre while waiting for an operating table to free up. Resuscitation with i.v. fluids can continue here under close supervision. The Category II cohort of patients who require surgery but not on an urgent basis can be grouped in a special ward where they can receive treatment (antibiotics, analgesics, i.v. fluids, dressings) under observation while awaiting surgery.

Category III patients suffering superficial wounds could be sent to the outpatient department or an area for convalescence outside the surgical hospital. This group is composed of many patients who are lucid, frightened (because of the shooting and shelling), panicky, and often in pain. Organization and basic staffing of this space are important in order to identify and isolate such patients, give them rapid treatment, and then discharge them.

Finally, a quiet, secluded room should be made available for Category IV patients with very severe wounds who should be left to die peacefully with dignity. An i.v. line should be put up and analgesics given if appropriate.

Some provisions should be made for the well-regulated visit of friends and relatives to all seriously-injured patients. This comes under the necessary security measures to be implemented (see Section 9.13).

9.8 Equipment and supplies

A large number of stretchers or trolleys are needed at the hospital entrance during triage, to accommodate the casualties left by incoming ambulances. Blankets and sheets are required in the triage area, as are lines on which to hang infusions. Complete sets of supplies for triage should be prepared and stored in boxes or trunks which can easily be carried to the triage area from an accessible storage space.

Triage boxes should include:
- disposable latex or plastic gloves;
- venepuncture equipment;
- i.v. fluids;
- dressings, bandages, scissors;
- catheters, naso-gastric tubes;
- drugs which are likely to be needed.

Needless to say, these triage boxes should be inspected regularly for the expiration date of their components. The drugs will probably need to be stored separately. Stocks should include the appropriate antibiotics and analgesics, as well as tetanus toxoid and anti-tetanus serum.

A reasonable stock of items that will be required for the management of extra cases in the wards should be maintained. There should be adequate numbers of bed blocks for elevation of the foot of the bed, supplies of i.v. bottle holders, and supplies of dressings, plaster of Paris, splints and traction apparatus.

Again, depending on the particular circumstances of the hospital, the pharmacy may hold designated emergency triage stocks or not. The re-supply of the hospital may be disrupted because combat has interrupted the ordinary lines of supply.

Standard documentation charts and patient folders, *each with a unique number*, should be prepared and maintained in readiness. Each folder should include a triage/admission form, a fluid balance chart, and laboratory and X-ray request forms.

9.9 Infrastructure

Plans must be made to ensure adequate supplies of water, sufficient electricity, proper sanitation, and the disposal of waste. This may include special reserves of fuel for electric generators. Spare parts are also important to keep in stock; things tend to break down in the middle of an emergency situation.

The designation of roles, responsibilities and tasks is not limited to the medical personnel. Technicians and maintenance workers to run the generators and ensure the water supply must be put on a special shift system so as to be available at all times.

9.10 Services

Hospital personnel, patients and their relatives, and volunteers must all eat. Hospital linen must be washed and theatre linen re-sterilized. The kitchen, cafeteria and laundry staff and facilities must all be included in the disaster plan. Relatives are a great nuisance in the triage area but their energies can be harnessed for the general good. They may be directed to give blood and engaged as volunteer stretcher-bearers, carriers of water, cleaners and kitchen staff, etc.

9.11 Training

The hospital team should regularly practise different triage scenarios, on its own and as part of any national disaster or conflict-preparedness plan. Volunteers from the National Red Cross or Red Crescent Society, and their first aiders, may be mobilized to work in the hospital and/or play the role of the injured.

Clinical protocols and guidelines for triage and patient management must be standardized and understood by all doctors and nurses. This helps to avoid confusion and disagreements under tense and tiring circumstances.

After every triage incident and when feasible, a general meeting of the staff should be held to discuss what went well and what went wrong. This evaluation permits the fine-tuning of the triage plan, to improve it for the next mass influx.

Some individuals or even the whole team may have found the experience very stressful. An open, frank discussion about what happened and why certain decisions were made can be very beneficial, and even therapeutic.

9.12 Communication

If the hospital is part of an integrated health system, then a means of coordination and communication with other health facilities may make it possible to transfer the wounded from the overwhelmed hospital to another which has received comparatively few patients. Alternatively, other health facilities may be able to provide help in the form of additional personnel.

The plan should include the means to contact staff who are off duty, bearing in mind that if combat is occurring in the area, hospital personnel may have difficulty in getting to work. Mobile telephone systems tend to stop functioning (or are stopped by certain authorities) during urban fighting or troubles.

In an age of immediate mass communication contact with the media is inevitable, and what is happening in the hospital can be easily exploited for political purposes. The patients, hospital and staff are all protected under IHL. Obviously, military and governmental civilian hospitals are not "politically" neutral and cannot be expected to be. However, hospital personnel must act and speak publicly in accordance with their "medical" neutrality and impartiality. An "official spokesperson" for the hospital should be duly selected.

9.13 Security

Last, but certainly not least, is the safety and security of the hospital premises, patients and staff. When armed conflict results in mass casualties every wounded person transported to the hospital is accompanied, as a general rule, by two to four friends, relatives, comrades-in-arms, or bystanders who have helped in the evacuation or transport. Curious onlookers may try to enter the hospital as well. The civilian population may be in a state of panic and consider the hospital a safe place. This well-known phenomenon is called the "convergence reaction". People's fear and excitement add to the confusion and danger, especially if many in the crowd happen to be armed. Limiting the number of people entering the hospital reduces the confusion considerably.

One major factor which creates the convergence reaction and confusion is the lack of proper pre-hospital triage, as is often seen in an urban context. As mentioned in Chapter 7, the waves of ambulances transporting casualties evacuate the dead and badly mutilated first, the superficially injured, who are shouting to call attention to themselves, second, and the seriously wounded who require emergency surgery last.

Security must be ensured by having guards posted at the gate of the hospital. Only wounded persons, possibly accompanied by a close relative according to local cultural traditions, should be allowed to enter. All weapons must be left outside the gate.

Access to the triage area should be blocked off, and a guard posted here as well to keep other patients and onlookers from mingling with new casualties.

The large numbers of relatives and friends who inevitably rush to the hospital must be prevented from crowding the premises and impeding the work of the medical staff. A system for well-regulated visits by patients' friends and relatives must be set up to reduce the possibility of "friction" occurring. Under certain circumstances, board and lodging close to the hospital compound must also be organized and provided.

Whether the guards are armed or not will depend on the circumstances of the country concerned. IHL does not prohibit armed guards if their purpose is to maintain order and protect patients and personnel.

In extreme circumstances, the hospital can organize a "security lock"[4] at the hospital or triage area entrance. This forced channel allows for better crowd control, especially of armed men.

ICRC EXPERIENCE

The ICRC hospital in Kabul, Afghanistan, used commercial, steel containers with doors cut into the ends at the hospital entrance in 1992 to create a "tunnel" that allowed the filtering of all who entered. The width of the door was calculated to allow for the passage of a carried stretcher only.

The ICRC – Somali Red Crescent Hospital in Mogadishu, Somalia, in 1992 was located in a converted prison. A first set of guarded gates led to a triage area with a large tent. A second set of gates separated the triage tent from the hospital compound itself, permitting controlled entry to the hospital.

The ICRC hospital team working in the JFK Memorial Hospital in Monrovia, Liberia, in 2003 set up a so-called "triage tent" just outside the fence and gate entrance to the hospital. No medical triage was actually performed there, it was more of a "disarmament tent". The tent provided a space for disarming any combatants, stripping the wounded of their soiled clothing, weapons and ammunition, and performing basic first aid. The wounded were then carried into the triage department – unarmed – on stretchers where the clinical triage was performed.


R. Aburabi / ICRC

Figure 9.7.1

Monrovia "triage tent" in front of the hospital.


R. Aburabi / ICRC

Figure 9.7.2

"Triage tent" seen from the outside.

R. Aburabi / ICRC

Figure 9.7.3

Volunteers inside "triage tent" before the action.

R. Aburabi / ICRC

Figure 9.7.4

Volunteers after the action.

---

[4] A lock is a short section of a canal with gates at each end which can be opened or closed to change the water level, used for raising and lowering boats going through the canal. This permits control of the movement between areas at different water levels. By analogy, a security lock permits the control of people's movements between different hospital areas.

9.14 Summary of triage theory and philosophy: sorting by priority

The triage process has three components.

1. Clinical assessment to determine which patients take priority for the limited surgical time and resources available.
2. The organization and management involved in admitting large numbers of wounded to the hospital.
3. Re-assessment of the functioning of triage and its adaptation to the number of incoming wounded.

9.14.1 Triage system: a simple emergency plan organizing the personnel, space, infrastructure, equipment, and supplies

The sudden arrival of large numbers of casualties may occur at any time. Prior planning and training prevents poor performance. Unless a plan exists for the reception and triage of mass casualties, chaos will result. Hospital staff should be prepared, however, to improvise when faced with a new evolving situation.

Evaluation of hospital capacity is essential in emergency planning.

An emergency plan does not cost money; organization does not cost money. They cost time, effort, discipline and motivation.

9.14.2 Emergency hospital disaster triage plans differ and no two triage scenarios are the same

Hospital teams must regularly practise receiving a mass influx of wounded, resulting from armed conflict or natural disaster. Simulation exercises should be organized covering a variety of scenarios, and adapted to the particular circumstances of the hospital involved.

9.14.3 "Best for most" policy

Priority patients are those with a fair chance of "good survival" with the least amount of surgical work.

Triage is essential to put some order into a chaotic situation.

However good the disaster plan and extensive the training, a mass influx of casualties is *always* stressful and attended by confusion. Flexibility and adaptability of the hospital team are important. Triage is not a series of rules. It has a logic and philosophy that must be adapted to each particular situation. Triage is not a simple science; it is an art.

Please note:

Further practical information on the organization of hospital management in a triage situation is available in the ICRC manual *Hospitals for War-Wounded: A Practical Guide for Setting up and Running a Surgical Hospital in an Area of Armed Conflict* (see Selected bibliography).

In a military context, all standard war surgery manuals written by and for armed forces deal with the organization and implementation of triage under military constraints.

technology. This process has also seriously undermined the position of women and has greatly affected their sense of dignity and self-esteem. It has also challenged the Yin values in society, considered to be counterproductive.

Unquestionably, the growing sense of despair and disorientation which large groups of people in the world today experience is directly related to the split and the resulting imbalances which they experience within themselves.

Restoring the Balance

With the growth of a new world culture, with a process of unceasing economic growth and expansion and the simultaneous rise of both minority affluence and mass poverty, these dualist tendencies are being further aggravated. The rise of fundamentalism and dogmatism, both as an instrument to legitimize power and achieve control and as a response to a growing despair and as an expression of the thirst for security is a further sign in the world rocked by imbalances and social fluctuations has become increasingly uncontrollable. This uncontrollability is seen as unavoidable and inherent in the very mechanics of the system and as an inevitable price for economic growth and advance.

Repression of the body and of sexuality and a search to compensate for it go hand in hand. Thus repression and a desperate search for liberation from it are both on the rise. There is a trend to see the body and sexuality as the source of all evil and start crusades against them so as to secure law and order. There is at the same time a growing obsession to secure and maximize pleasure, a trend which has grown to be the object of ruthless exploitation in which the body and sexuality have become mere commodities on the market. As a result, public life is being sexualized, as a source of economic expansion and profit.

Thus the repression of the body and sexuality have precisely an inverse effect and has become a major source of a fast-growing market and rapidly expanding pleasure and amusement industry, which capitalizes on this repression.

The first law of thermodynamics is that energy cannot be created or destroyed. In terms of Taoist theory, all energy comes forth from the Great Void, the original Wu Chi which undergoes a series of transformations in the formation of the universe. Thus the human body is seen as a particular form of transformation of this

ANNEX 9. A Sample triage card

Triage Card No: ______________

Name: ____

Coming from: ____

Male / Female / Age ____

Date: ____

Time: ____

GSW: ☐ Mine: ☐ Fragment: ☐ Blast: ☐

Burn: ☐ Other: ____

Time since injury: ____

General condition:

Pulse: ________________ BP: ________________________

Resp. rate: ____________ Consciousness: ________________

Wound assessment:



Triage Category:

🟥 I	🟨 II	🟩 III	⬛ IV

ANNEX 9. B Hospital emergency plan for a mass influx of wounded

HOSPITAL EMERGENCY PLAN FOR A MASS INFLUX OF WOUNDED										
PHASE	Influx of wounded (number of patients)	Secrity + Porters/ stretcher - bearers	TTL / TO / HN	Triage Area (ER + OPD + Physio room)	OT	Wards	Administration	Laboratory X-ray	Kitchen Laundry Tailor	Transport
1	**1 – 10**	Routine	HN informed OT informed	Routine	Stop routine Inform wards	Routine No more elective patients sent to OT	Routine	Routine	Routine	Routine
2	**11 – 20**	Extra guards at patients' entrance	TTL informed TO: INITIATE TRIAGE HN: Inform wards, OT, administration	Request triage material and staff	Keep staff on duty Check supplies	Update bed situation Inform HN/TTL	"	"	"	Standby ambulance
3	**21 – 30**	Visitors leave Visiting hours suspended	Call in on-call nurses Ensure that all staff have breaks	Call in extra staff Physio staff on standby to help in triage or in wards	Extra surgical team and staff standby	"	Keep pharmacy staff on duty	"	Prepare food and drinks for OT staff if needed	"
4	**31 – 40**	"	HN: Reassess bed situation TTL/:Monitor OT situation	"	"	Assess need for additional staff Inform HN	Keep purchaser and storekeeper on duty	Call in extra staff if needed	Laundry: priority is OT linen	Standby bus for staff transport
5	**41 – 50**	Call in extra porters/ stretcher-bearers	TTL/HN: REASSESS Define needs for staff, beds, supplies	"	Check supplies Open reserve linen stocks	"	Monitor needs for staff	"	Open emergency food stocks	"
6	**> 50**	"	REVIEW AGAIN	"	"	"	Provide resting area and sleep accommodation for staff on duty	"	Provide food and drinks for all staff on request if needed	"

ER: emergency reception room

HN: Head Nurse

OPD: outpatient department

OT: operating theatre + sterilization

TO: Triage officer

TTL: Triage Team Leader

Chapter 10

SURGICAL MANAGEMENT OF WAR WOUNDS

10. SURGICAL MANAGEMENT OF WAR WOUNDS

10.1 Introduction 213

10.2 Complete examination 214

10.3 Preparation of the patient 215

10.4 Examination of the wound 216

10.5 Surgical treatment 216
10.5.1 Technique of wound debridement 217
10.5.2 Skin 218
10.5.3 Subcutaneous fat 218
10.5.4 Fascia and aponeurosis 218
10.5.5 Muscle 219
10.5.6 Haematoma 220
10.5.7 Bone and periosteum 220
10.5.8 Arteries, nerves and tendons 220

10.6 Retained bullets and fragments 221

10.7 Final look and haemostasis 222

10.8 Wound excision: the exceptions 223
10.8.1 Management of minor Grade 1 wounds 223
10.8.2 Serial debridement 223

10.9 Leaving the wound open: the exceptions 224
10.9.1 Head, neck, scalp and genitals 224
10.9.2 Soft tissues of the chest (sucking chest wound) 224
10.9.3 Soft tissues of the abdominal wall 224
10.9.4 Hand 224
10.9.5 Joints 224
10.9.6 Blood vessels 224

10.10 Dressings 225
10.10.1 The exceptions 226

10.11 Anti-tetanus, antibiotics, and analgesia 226

10.12 Post-operative care 226

10.1 Introduction

There are many factors that determine the final outcome of the management of war-wounded patients:

- the actual injury – the clinical significance of the wound is a function of the severity of tissue damage and the anatomic structures involved i.e. size and site;
- the general condition of the patient – nutritional status, dehydration, concomitant diseases, host resistance, etc. ;
- pre-hospital care: protection, shelter, first aid, triage, evacuation time;
- resuscitation, especially in the presence of haemorrhagic shock;
- hospital triage;
- surgery;
- post-operative nursing care;
- physiotherapy and rehabilitation.

However, the single most important act that the surgeon performs for the great majority of casualties is wound excision or debridement.[1]

The basic principles of trauma wound management have been known for a considerable period of time. Ibn Sinna commented on this (Figure 10.1), as did Alexander Fleming one thousand years later.

Å. Molde / ICRC

Figure 10.1

"Damaged tissues must be removed in time."
Ibn Sinna, *Qanun fi al-Tib*.[2]

> "The severity of these [war] wound infections is merely the result of the very extensive destruction of the tissues by the projectile, thus furnishing an admirable culture medium for the bacteria out of reach of the natural protective forces of the body, and if it were possible for the surgeon to remove completely this dead tissue I am quite sure the infections would sink into insignificance."
>
> Alexander Fleming[3]


K. Barrand / ICRC

Figure 10.2.1

Wound sutured primarily to "close the hole", without debridement.


K. Barrand / ICRC

Figure 10.2.2

Sutures removed: pus pours out.

Often, ICRC health personnel have witnessed inexperienced medical staff in a low-income country dealing with severely war-wounded patients for the first time. Their initial reaction is to try to stop the bleeding by "closing the holes". If suture material is available, they stitch the wounds shut without excising dead tissue; if not, they plug the wounds with gauze compresses. Soon, infection develops. This is treated by a frequent change of dressing and antibiotic anarchy, wasting already insufficient hospital supplies. The end of the story may be a slow recovery with a major disability, or, more frequently, major complications often leading to the death of the patient accompanied by a deep sense of frustration among the medical staff.

The basic management of war wounds is an art based on sound scientific principles. A good knowledge of wound ballistics helps the surgeon assess more accurately the extent of tissue damage and of the necessary surgery; it will not explain every wound or prescribe specific treatment for every patient. In only a few cases will knowledge of the specific causative weapon be of any clinical use.

Wound ballistics teaches us that the cavitation effect of projectiles conveys pathogenic organisms, pieces of dirty skin and clothing and dust into the depths of the wound. Anti-personnel blast mines drive pieces of the shoe or bones of the foot,

10

---

[1] "*Débridement*" is a French term originally used to mean the removal of a constriction, or to unbridle, and thus to promote drainage and relieve tension by incision. The English word "excision" means to cut away or cut out. A confusion of terminology occurred at the Inter-Allied Surgical Conference for the Study of War Wounds held in Paris in 1917, and the historic French expression came to mean a wound excision – the removal of dead tissue – for English-speaking surgeons.
A further misunderstanding may be caused by the fact that excision, when used with reference to cancer surgery, tends to mean "*excision en bloc*" with a wide margin of healthy, surrounding tissue. In this book, the expressions "excision" and "debridement" are used interchangeably and are understood to mean the cutting away of dead or devitalized tissue.

[2] Ibn Sinna – Avicenna (980 – 1036 CE), Persian physician and philosopher, author of *Qanun fi al-Tib* (The Laws of Medicine).

[3] Alexander Fleming (1881 – 1955), British physician, discoverer of penicillin.
Fleming A. On the bacteriology of septic wounds. *Lancet* 1915; **186**: 638 – 643.

gravel, soil, leaves and grass, and pieces of the weapon into the proximal tissues. Although the wounds are contaminated, infection does not set in for the first 6 – 8 hours. Ideally, therefore, war wounds should be debrided within six hours; this is not often the case.


ICRC

Figure 10.3

Anti-personnel landmine injury: war wounds are dirty and contaminated.

Old lessons for new surgeons

War wounds are dirty and contaminated, from the moment of injury.

Whatever the weapon, a thorough examination of the patient and the wound(s) is essential.

Examine the patient:

- initial examination and resuscitation;
- complete examination to identify all open wounds and any closed injuries.

Examine the wounds and damaged organs:

- to operate or not to operate;
- to establish priorities if more than one surgical procedure is required;
- to plan the operation.

Please note:

The treatment of mismanaged and neglected wounds is dealt with in Chapter 12.

10.2 Complete examination

All wounds involve soft tissues, and many of them will be complicated by damage to other structures. *War wounds are often multiple* and the *pathology often multiple*: a bomb explosion can simultaneously cause primary blast injury, penetrating metallic fragments, blunt trauma and burns. Close and complete examination of the patient is important to determine the site and size of *all* wounds present, in order to determine which wounds require surgery and to best plan the sequence of operations.



H. Nasreddine / ICRC

Figure 10.4

Entry and exit thoraco-abdominal wounds: think anatomy!

As mentioned in Chapter 8 the surgeon should try to identify the path of any projectile. The wound may perforate the body part through-and-through, or the projectile may be retained without an exit. Entry and exit wounds may be at the same or different levels. The surgeon should visualize the anatomic structures that lie along the probable projectile trajectory, which may include a vital cavity: brain, thorax, or abdomen. The surgeon must think "anatomy".

The examination may reveal a tense, tender swelling in a through-and-through wound to the calf, which indicates haematoma and severe muscle damage; by contrast, the same exit and entry wounds with soft and relaxed tissues signify minimum injury. The surgeon must think "pathology".

Fractures and peripheral vascular and nerve damage should be identified. If there has been delay in evacuation, a *bruit* or vascular murmur may be heard and a "thrill" felt, signifying a pseudoaneurysm or arteriovenous fistula. Peripheral motor function and sensation are tested. Neurapraxia is more common than a severed nerve.

Most wounds involving vital organs should already have been identified during the initial examination for airway, breathing and circulation. Nonetheless, the full-body palpation of a complete examination may reveal the small entry wound of a tiny fragment that has penetrated the meninges, pleura or peritoneum without immediately affecting the vital functions.

A full assessment may require X-rays as well – with the exception of through-and-through soft-tissue wounds, which do not require them. One body region above and below any entry or exit wound should be filmed. Deformation or fragmentation of a bullet, showing the characteristic "shower of lead particles", is a good indication of severe tissue damage. (Figures 10.5, 3.35 and 4.5). Many foreign materials, it should be noted, are *not* radio-opaque: pieces of shoe or clothing, mud, leaves and grass, plastic fragments from some landmines, for instance. On the other hand, it may be difficult to differenciate a projectile from the normal radio-opacity of some anatomic features (Figures 8.4.2 and 14.9.1). Major bone comminution also implies severe soft-tissue damage. Having radiography helps, but is not an absolute necessity for diagnosing fractures.[4]

Note that the presence of air in tissues on X-ray does not necessarily mean the gas of clostridial myositis. The temporary cavity associated with high velocity missiles often leaves behind palpable and radiographic intrafascial and intramuscular air in healthy tissue some distance from the wound. This usually indicates severe tissue damage. The diagnosis of gas gangrene is a clinical one and the radiograph is not pathognomonic: *vide* Figures 10.6 and 13.2.

More sophisticated diagnostic means can be used, of course, depending on the equipment and professional expertise of the hospital in question.



R. Coupland / ICRC

Figure 10.5

Massive comminution of humerus showing characteristic "shower of lead particles" after bullet fragmentation.

10.3 Preparation of the patient

Not only are war wounds dirty and contaminated but battlefields are dirty places as well. The wounded do not have access to basic sanitary facilities and every precaution should be taken to meet fundamental hygiene standards. The majority of casualties have wounds to the limbs and are haemodynamically stable. All stable patients should be put through a warm shower upon admission; dressings are changed as necessary for examination and triage. Only critical cases go straight to the operating theatre.

In the operating theatre, the surgeon should prepare the patient's position – in coordination with the anaesthetist and nursing staff – for the sequence of the operation before starting. A pneumatic tourniquet is very useful for limb wounds, especially before removal of a field dressing on an obviously serious injury.

In the case of multiple soft-tissue wounds, those on the posterior aspect of the trunk and limbs should be dealt with *before* those on the anterior aspect, unless there is clinical evidence of a vascular injury. Many wounds to the back have been *"forgotten"* after much work on anteriorly situated wounds, and it is easier for the anaesthetist to finish off the operation with the patient supine.



ICRC

Figure 10.6

X-ray showing air in tissues in a patient not suffering from gas gangrene.

Under anaesthesia, dressings and splints are carefully removed. The skin over a large surrounding area, including the whole circumference of the limb or torso, is cleansed with soap and water and a brush, shaved, dried, and then painted with povidone iodine. The wound is irrigated copiously.

Sterile sheets are put in place. Drapes with holes should only be used for the smallest and most superficial wounds. Most wounds will have to be extended and the operative field enlarged as a result.

The wound is then thoroughly irrigated again to remove surface dirt and debris. Under optimal conditions, sterile normal saline should be used. Under conditions of limited resources, potable water from the tap can be resorted to: "If you can drink it, you can put it into a dirty wound". Groundwater may be treated with sodium hypochlorite to reach a concentration of 0.025 % (5 ml of bleach in one litre water) if necessary.

Only in extreme cases of impending asphyxia or exsanguinating haemorrhage should the basic rules of hygiene and sterile technique be broken.



ICRC

Figure 10.7

Washing an anti-personnel landmine injury prior to surgery.

---

[4] Many ICRC surgical teams have had to operate in emergency situations with *no* X-ray equipment.



Figure 10.8

Finger exploration of the wound.

10.4 Examination of the wound

Following the initial careful examination of the patient, full assessment of the wound(s) may require finger exploration in theatre under anaesthesia. In this era of HIV and Hepatitis B and C, the surgeon should take great care not to suffer injury from sharp bony edges.

Old lessons for new surgeons

The best instrument for wound exploration is the surgeon's (protected) finger.

The surgical work required to treat a wound depends on its site and size: i.e. the location and amount of tissue damage. Knowledge of ballistics allows only for an understanding of wounding possibilities, but knowing that certain weapons have greater wounding potential does not help the surgeon in this assessment. With the exception of anti-personnel blast mines, even knowing which weapon was used is often of no practical use. Many wounds are the result of full metal jacket bullets that ricochet, creating large injuries similar to a dum-dum bullet (see Chapter 3).

The most significant component of tissue damage is the permanent wound cavity, yet energy loss by the projectile and tissue disruption along the track is not uniform, resulting in a "mosaic of tissue damage". Injury can also occur well beyond this, owing to stretch and shear during temporary cavitation: late ischaemic necrosis in the wall of hollow organs; or intimal detachment and vascular thrombosis of vessels that still look intact from the outside. The time between injury and treatment and the possible beginning of sepsis, must also be taken into account.

War wounds are never identical, even if caused by the same weapon.

There is an art to the assessment of tissue damage that is learnt largely through experience. It is important neither to under-treat – causing sepsis and even death – nor to over-treat – resulting in excess loss of normal tissue and increased disability.

This art does have a scientific basis, nonetheless. We have seen that the Red Cross Wound Score classifies penetrating weapon wounds into different categories according to the degree of tissue damage (Grade) and the structures injured (Type). This Score helps determine the extent of surgery necessary. Careful examination is important because not all wounds require surgical excision.

10.5 Surgical treatment

The surgical treatment of a major wound is performed in two stages:

- *wound debridement*, leaving the lesion wide open, without any suturing of skin or deep structures;
- *delayed primary closure* 4 – 5 days later.

The surgical treatment of most war wounds is a staged process involving two main procedures, the first being wound debridement or excision. The resulting wound is left unsutured. The open wound then undergoes delayed primary closure (DPC) after 4 – 7 days, once the exudative phase of trauma inflammation has subsided and the proliferative phase begun. In practice, DPC is usually performed after 4 – 5 days. Closure may be by simple direct suture or require sophisticated techniques of grafting and reconstruction (see Chapter 11).

original energy. The second law of thermodynamics states that energy in a closed system tends to become disorganized (entropy). Thus there is an automatic tendency for balance to be lost.

Taoist practice focuses on inverting the process of dispersion and disorganization and restoring balance. This process is set in motion and facilitated by the Healing Love practice through which the unity and balance between love and sex is restored.

Essential to the Healing Love practice is the growth of love and compassion within as a result of which love and compassion with others and the universe become possible and emerge as a natural extension. Once the inner balance is restored, it is possible to act as an effective agent of balance outward.

In the Taoist view, conflict and violence in the outer order invariably have their source in inner conflict and violence, as manifestations of inner imbalance. Equally is outward peace viewed to have its source in inner peace and balance. In this process towards inner balance, Fusion Practices, in conjunction with the Healing Love practice and other practices of the Universal Tao, play an essential role; they honor the body and its intrinsic wisdom and potential for self-healing and rebalancing itself, so that it enters into alignment with the universe.

Joseph Needham, one of the great scholars of the origins of Chinese science and civilization, who was an honored member of the Academia of Science, had called Taoism the feminine undercurrent in Chinese history and culture, with its focus on the power of silence, feeling, sensing, compassion, forgiveness, humility, gentleness, reverence for life and nature and the equality of women.

It was however relegated to the margin of Chinese civilization and its practitioners had often to go underground. As a rule they fiercely stood for the ancient communitarian practices of reciprocity and sharing as well as people’s freedom and self-reliance. At the same time, they were opposed to interfering with the natural order, to be respected as a manifestation of the higher orders.

World as a Manifestation and Reflection of the Universe

They valued ancient forms of democratic practice, rooted in a vision of village communities in early times, which formed federations, patterned on the very structure of and alignment with the cosmos. No wonder that they were staunchly opposed to any forms

10.5.1 Technique of wound debridement

Basic principles of wound debridement

1. Stop haemorrhage.
2. Make adequate skin incisions and fasciotomies.
3. Remove dead and severely contaminated tissues to prevent/control infection.
4. Leave the wound open – unsutured.
5. Re-establish physiological function.
6. Handle gently and treat the tissues with respect, as always.

Control of haemorrhage is the first priority. In a large wound with heavy bleeding, blind clamping in the depths of a blood-filled cavity is mentioned only to be condemned. Direct local pressure should be exerted while proximal and distal control of the vessels by standard surgical exposure is performed.

For management of vascular injuries, see Volume 2.

After haemorrhage, the greatest danger to the patient is sepsis. Surgical infection requires a culture medium, which in the case of weapon wounds is a mixture of dead muscle, haematoma, bone fragments, dirty skin, foreign material (pieces of cloth or shoe, mud, gravel, leaves, dust, the missile, etc.), and, at times, extrinsic bone (bone fragments which come from the wound in another part of the body or another person and whose penetration, as secondary missiles, then creates a new wound). Injury caused by extrinsic bone fragments is seen with bomb explosions and APM.

Wound debridement is the process whereby this dead and damaged tissue, grossly contaminated with bacteria and debris, is completely cut away. This leaves an area of healthy tissue with a good blood supply and capable of combating residual surface contamination, provided the wound is not closed. Excess excision of healthy tissue, however, will increase the potential for deformity and disability.

Good vascularisation and oxygenation of the wound requires relief of tension within the wound and good drainage of the inflammatory exudate. This is provided by adequate incision of the skin and fascia, and leaving the wound unsutured.

Wound debridement involves incision and excision.

A basic instrument set is all that is needed in the vast majority of cases: scalpel, Metzenbaum (tissue) and Mayo (suture) scissors, toothed dissection forceps, bone curette, six haemostats, and retractors. Diathermy is not necessary; absorbable ligature material is preferable.

For the young surgeon, or one without experience of war wounds, it is best to excise the wound layer-by-anatomic-layer, proceeding from superficial tissues to deeper ones in order to best visualize the anatomy and pathology. At all times the surgeon should anticipate the anatomic structures present. Tissue damage, haematoma, and oedema can easily *alter the visible anatomy*, and camouflage important structures.



F. Jamet / ICRC

Figure 10.9.1

Patient X: entry wound on anterior aspect of thigh.



F. Jamet / ICRC

Figure 10.9.2

Patient X: longitudinal extension of the skin incision.



F. Jamet / ICRC

Figure 10.9.3

Patient X: opening of the fascia throughout the length of the skin incision. Note the contused and necrotic muscles.

10.5.2 Skin

Skin is elastic, with a good blood supply, very resistant to damage and remarkably viable. It should be treated conservatively. Only skin that is grossly pulped should be cut away. Usually no more than 2 – 3 mm of the skin edge need be removed at both entry and exit sites.

This is followed by as generous an incision as necessary of healthy skin in order to gain access to the depths of the wound (Figure 10.9.2). Small entry and exit wounds may hide considerable internal injury. The most common error is to attempt to make a wound excision through a small entry or exit wound. In limbs, the incision should be made in the longitudinal axis, but not over subcutaneous bone, and at flexion creases it should curve in the usual way.

The commonest mistake is to attempt a wound excision through small entry or exit holes or to make incisions too short.

This extension of the skin wound not only permits better visualization, but also allows for the proper decompression of deeper tissues and their subsequent drainage.

10.5.3 Subcutaneous fat

Subcutaneous fat has a poor blood supply and is sticky, easily holding heavy contamination. This layer should be excised generously, 2 – 3 cm all the way around the original traumatic wound.

10.5.4 Fascia and aponeurosis

Shredded fascia should also be trimmed. Large amounts of damaged muscle may lie underneath a small hole in the fascia; therefore, the muscular compartment should be opened up by a large incision of the deep fascia parallel to the muscle fibres along the entire length of the skin incision (Figure 10.9.3). This essential step allows wide and deep retraction to expose the depths of the wound. It may be necessary to add transverse cuts to the deep fascia to improve access.

Post-traumatic oedema of the wound can easily cause compartment syndrome, compromising the local circulation with resultant necrosis of the muscles. The fascial incision is left open to allow oedematous and congested muscle to swell without tension, so as to avoid interference with the blood supply and to promote drainage of the inflammatory exudate and haematoma.

After haemorrhage control, the relief of tissue tension is the most important step in wound debridement.

Deep to the fascia, the gloved finger is the best and gentlest probe to follow the track and estimate the extent of damage. Again, particular attention should be paid to the sharp edges of any fractured bone.

Fasciotomy

Compartment syndrome can occur in any fascial space, but is seen most commonly in the lower leg. Great care should be taken when dealing with any penetrating wound below the knee, with or without tibial fracture.

If there is any suspicion of compartment syndrome, decompression must be performed without delay.

For information on the technique of fasciotomy of the lower leg, see Volume 2.

10.5.5 Muscle

Dead muscle is the *ideal medium* for the development of *clostridial* infection leading to gas gangrene or tetanus as well as for the growth of many other bacteria. The track of the missile through the muscles must be opened up, layer by layer, to be properly visualized. It is vital that all grossly contaminated, obviously necrotic and detached muscle lining the track be excised.

All dead or heavily contaminated muscle must be removed.

Warning!

Muscles that are completely transected contract *away* from the wound cavity. The retracted muscle bellies must be found for inspection and excision. During wound exploration, division of uninjured muscle in a transverse direction should be avoided.


F. Jamet / ICRC

Figure 10.9.4

Patient X: wound cavity completely opened and excised.

However, not all injured muscle will undergo necrosis. How to differentiate between muscle that is injured but will heal from that which is not viable? Classically, reference is made to the four Cs of muscle viability:

- colour,
- consistency,
- contractility, and
- capillary bleeding.

All muscle that is not healthy and red, that does not contract when pinched or bleed when cut, must be excised until healthy, contractile, bleeding muscle is found.

However, confusion may arise because of certain pathological changes described below.

- As mentioned in Chapter 3, wound ballistics studies have shown that there is an intense but transient vasoconstriction lasting several hours, followed by the reactive local hyperaemia of the inflammatory response. Consequently, it is not always necessary to "cut until it bleeds". The surgeon must therefore take into account the time since wounding.
- However, minimal excision is often followed by necrosis of the muscle when the wound is looked at several days later. What is irreversible is not always immediately apparent. The wound evolves and these changes demonstrate the different stages in the "life-history" of the wound[5] and should be well understood by the surgeon.
- The surgeon should also understand that shock or the use of a tourniquet can change the colour or the capacity of muscle to bleed and that contractility is affected by hypothermia and paralysing anaesthetic agents.

The criteria of the 4 Cs are very subjective and a function of the surgeon's experience, but are nonetheless the best clinical measure available. The colour and consistency – texture – of the muscle should be noted. To test for contractility, 2 cm^3 lumps of muscle should be picked up and pinched with a forceps and, if they do not contract, excised using scissors or knife. Note if the cut edge of the muscle lump bleeds. Cutting away lumps larger than 2 cm^3 may result in the inadvertent removal of healthy tissue. Meticulous technique is the key.

Intermuscular fascia should be excised if blood-stained and contaminated.

---

[5] Pearson W. Important principles in the drainage and treatment of wounds. *Lancet* 1917; **189**: 445 – 450.

10.5.6 Haematoma

The presence of a large haematoma generally implies that a major vessel has been damaged. Dislodging the haematoma can result in sudden heavy blood loss. It is wise to be prepared for vascular control before a haematoma is evacuated. If working under a pneumatic tourniquet, the anatomical structures must be clearly identified.

10.5.7 Bone and periosteum

The Haversian vascular system of bone is a fragile one. Fragments of bone with no attachment to periosteum or muscle are already sequestrated and should be discarded, but any bone still attached should be retained. Exposed medullary bone should be curetted back to firm marrow. Any bone left *in situ* must be cleaned of dead muscle and foreign material, dirty bone ends are trimmed by a bone-nibbling forceps (*rongeur*). *Bone defect* is not important at this stage, the *wound* is of paramount importance, and every attempt should be made to avoid infection, whose development will only lead to greater bone loss. The danger of non-union from the removal of multiple bone fragments is overrated.


H. Nasreddine / ICRC

Figure 10.10.1

Patient Y: gunshot wound to arm and chest.


H. Nasreddine / ICRC

Figure 10.10.2

Patient Y: wound track opened up.


H. Nasreddine / ICRC

Figure 10.10.3

Patient Y: detached bone fragments removed.

Periosteum, on the other hand, is resilient and has a rich blood supply: it plays the predominant role in new bone formation. Its debridement should be conservative and restricted to obviously dirtied and contaminated edges.

ICRC practice is to use the simplest form of bone immobilization at the first debridement; this is usually a plaster of Paris (POP) posterior slab or some form of skeletal traction. Seldom is external fixation required at this stage and internal fixation is proscribed in ICRC practice. More definitive bone immobilization is decided during delayed primary closure of the wound.

For information on indications for different techniques of fracture immobilization and repair of bone defect, see Volume 2.

10.5.8 Arteries, nerves and tendons

As aforesaid, bleeding should be controlled if a major artery to the limb is damaged and either immediately repaired or replaced by a saphenous vein graft or temporary stent if a limb is to survive. The surgeon should pay particular attention to the possibility of a vascular injury near severely comminuted fractures with multiple fragments.

All nerves must be preserved as far as possible. Large nerves are resistant to section, although they may suffer neurapraxia. They are often the only structure left traversing a wound cavity. If they are found to be damaged, the site and degree of damage should be recorded. A non-absorbable suture may be placed in the proximal and distal ends and pulled together to facilitate their identification at a future operation. Exploration of the implicated nerve should be attempted during wound debridement *only* if it does not involve opening up healthy tissue planes.

Tendons should be trimmed and only grossly destroyed fibres removed. Severed tendons, if important and requiring later repair, should be marked with a non-absorbable suture as with nerves.

No attempt should be made at primary tendon or nerve repair, as success is unlikely in these grossly contaminated wounds. The failure of immediate repair will only make subsequent efforts that much more difficult. Also, repairs take time and energy at the "wrong time of the day"; they are best dealt with as planned elective procedures. Nerves and tendons should nonetheless be protected from extended exposure, by covering them with muscle or skin flaps or wet dressings.

For techniques on artery, nerve, and tendon repair, see Volume 2.

10.6 Retained bullets and fragments

Obviously, if the surgeon comes across a projectile during wound debridement then it should be removed, but healthy tissue should not be dissected in an attempt to find one. Otherwise, there are two conditions that require *immediate removal* of bullets and fragments, and these are related to specific proven risks and complications.

1. Projectile situated in a synovial joint – the piece of metal will cause pain, disability and progressive destruction of the joint cartilage though a mechanical action, and possible toxicity if made of lead: it should be removed as part of the wound debridement of the acute injury (Figures 10.11.1 and 10.11.2).
2. Risk that the projectile may cause erosion of an important structure (usually a major blood vessel) with the possibility of major haemorrhage or embolization (Figures 10.12.1 and 10.12.2). Should the surgeon suspect a pseudoaneurysm or an arterio-venous fistula then an operation to treat these pathologies involves the removal of the foreign body.

   Whether this removal is performed as an acute or planned elective procedure will depend on the exact anatomic location and endangered structure, the haemodynamic stability of the patient, the availability of diagnostic and operative equipment, and especially the *expertise of the surgeon*. The risks of a major procedure (removal of a bullet in the mediastinum, brain, etc.) whose morbidity may be quite high (especially in inexperienced hands) must be weighed against the benefits where the overall incidence of complications is low: for further indications and details, see Chapter 14.


ICRC


ICRC

Figures 10.11.1 and 10.11.2

Retained bullet in the hip joint.


F. Irmay / ICRC


F. Irmay / ICRC

Figures 10.12.1 and 10.12.2

Retained bullet in the upper mediastinum.

10.7 Final look and haemostasis

The edges of the wound should be retracted and blood clot, dirt and missile fragments removed from the sides and depths. Gentle and copious irrigation under low pressure, preferably with normal saline at this point, will wash out any residual debris and clot and dilute any bacterial load. A plastic bottle with holes cut into the top squeezed manually with both hands provides sufficient pressure; depending on the size of the wound cavity, one to three litres of saline is used. Very large and complicated fractures may require more until the wound "looks" clean.

All the structures in the wound cavity should now be visualized and identified (Figure 10.13). The surgeon should carefully explore the wound with the finger to identify any foreign bodies or unexpected extensions of the wound.


F. Jamet / ICRC

Figure 10.13

Patient X: final appearance of the wound cavity.

- *Do not* open fresh planes in healthy tissue.
- *Do not* explore unnecessarily for metallic fragments.
- Remove fragments of clothing, in-driven dirt and vegetation.


F. Jamet / ICRC

Figure 10.14

Patient X: wound is left open.

After removal of the pneumatic tourniquet, bleeding should be controlled by pressure with gauze and by fine absorbable ligatures. Electric cautery (diathermy) is best avoided as it leaves dead burnt tissue behind, which is more harmful than the foreign body of an absorbable knot.

The wound should be left wide open (Figure 10.14). There is no use in "putting in a few sutures" to partially close the wound, "just to bring the edges together a bit". This will defeat the purpose of allowing for extensive wound decompression and drainage and, after the development of reactive oedema, a loose stitch becomes tight. In addition, although the wound may look clean, it is not sterile. Bacteria and microscopic debris still exist in the wound and will only be expelled with the post-traumatic inflammatory exudate if drainage is adequate.

Should a drain be put in place? If the wound is relatively shallow and left wide open, there is no need for a drain. If there are deep pockets in the wound, which cannot be fully opened up because of anatomical constraints, then a soft penrose or corrugated rubber drain may be required. Counter-drainage through a stab wound in a dependent part might be more useful.

These procedures are *not new*. They are the rules of all septic surgery to be found in all standard surgical reference texts. "Never close infected wounds. Do not close contaminated wounds or clean wounds that are more than 6 hours old. Systematically perform wound toilet and debridement and saline irrigation until the wound is completely clean. Perform delayed primary closure as a second procedure."

Old rules for new surgeons

In war wounds, the rules of septic surgery apply.

10.8 Wound excision: the exceptions

10.8.1 Management of minor Grade 1 wounds

Many Grade 1 soft-tissue wounds, according to the Red Cross Wound Score, can be treated conservatively. Examples include:

- perforating bullet wound with small entry and exit (narrow channel wound) without swelling of intervening tissues (haematoma/oedema) or other signs of injury to important structures (Figure 3.29.1);
- multiple superficial wounds due to "peppering" with tiny fragments of obviously low velocity and low kinetic energy (e.g. hand grenade) as shown in Figure 10.15.1.

Some superficial Grade 1 soft-tissue wounds will require only simple local wound toilet. This will suffice with many low-energy small fragment wounds where the potential culture medium is so small that the body's normal defence mechanisms can deal with it. They can be cleansed with soap, water, and a disinfectant and a simple dry dressing applied; the small wound is left open to heal by secondary intention. This is especially the case if antibiotics can be administered early (see Chapter 13). This ICRC experience has been confirmed by others.[6]

Excision of entry and exit wounds under local anaesthesia may be necessary to promote free drainage in other superficial Grade 1 wounds. This may be accompanied by syringe injection of normal saline for irrigation of the wound track with/without a drain. Some such wounds, however, will require a full surgical exploration and excision, particularly in the one well-known instance where the type of weapon is of utmost importance: anti-personnel blast mines. Even small puncture wounds from landmines can be loaded with mud and grass or the mine casing, all of which must be removed (Figure 10.16).


R. Coupland / ICRC

Figure 10.15.1

Superficial "peppering" by grenade fragments.



R. Coupland / ICRC

Figure 10.15.2

There is no penetration of the joint and no vascular injury – the wounds require simple wound toilet.

Heterogeneity of war wounds: there is no single treatment that applies to all wounds. Wounds must be considered by Grade and Type.

10.8.2 Serial debridement


ICRC

Figure 10.16

All APM fragment wounds – large and small – require debridement.

For some large wounds the line of demarcation between dead tissue and damaged, but viable, tissue is not clear. The life-history of a wound is such that apparently clean and living tissue may become necrotic after a few days, especially if there has been a delay between injury and debridement; and if the surgeon is not experienced in this type of surgery. The idea here is to debride obviously dead tissue; otherwise excise conservatively, and then re-examine the wound in theatre after 48 hours.

This method is called a "serial debridement", i.e. a wound excision over several sessions, and it should be *planned* as such. The surgeon should make a conscious decision that, "in this patient, because I am not certain of the viability of the remaining tissues and excessive excision of normal tissue would cause deformity or compromise function, I shall perform a second debridement later" (Figure 10.17).

In armies with very efficient means of evacuation and sufficient human resources, serial debridement may be the preferred method of treatment and takes place at different hospitals with different operating surgeons along the chain of casualty care.

Serial debridement cannot be considered a standard method of treatment in a situation of mass casualties and poor or no evacuation capacity. It requires sufficient personnel and resources to handle the number of wounded and to allow for a second look and follow-up. More often, the surgical workload is so great, or the tactical situation such, that serial debridement is not possible. The surgeon must treat each wound excision as a definitive one. In this instance, if in doubt about tissue viability, it is wiser to excise.

---

[6] Bowyer GW, Cooper GJ, Rice P. Small fragment wounds: biophysics and pathophysiology. *J Trauma* 1996; **40 (Suppl.)**: S159 – S164.



ICRC

Figure 10.17

Serial debridement of a large wound: the line of demarcation of necrotic tissue has now become apparent.

The practice of serial debridement should not be confused with an incomplete or failed wound excision. In the latter case, the patient returns to theatre for delayed primary closure after five days and the wound is found to be infected with remaining necrotic tissue. It is not ready for suture and requires re-debridement.

10.9 Leaving the wound open: the exceptions

As is usually the case in surgery, there are exceptions where wounds may, or even should, be closed.

10.9.1 Head, neck, scalp and genitals

The excellent blood supply and minimal soft tissue of these structures usually allows for immediate primary closure after wound excision. Only in the presence of severe contamination, or if in doubt, might it be wiser to leave these wounds open.

In maxillo-facial wounds, the oral mucosa is an exception in all respects and every attempt should be made to close it primarily.

Machete or *panga* wounds, especially to the face or scalp, are *not* incised wounds, but rather a mixture of crush and laceration. Dirty connecting tissue is found to underlie an overhanging edge of skin and galea aponeurotica. If less than 6 hours since wounding, immediate primary closure, after full debridement, with a subcutaneous drain is permissible. If more than 6 hours old, it is better to leave the wound open for delayed primary closure after 2 – 4 days.



M. Baldan / ICRC

Figure 10.18

Panga wound to the head.

In penetrating brain injury, it is best to close the dura. This can rarely be sutured directly, but the problem can easily be overcome with a patch of pericranium or aponeurosis. After debridement of the scalp wound, the skin should be closed either directly or with a rotation flap.

10.9.2 Soft tissues of the chest (sucking chest wound)

These wounds must be debrided, but healthy muscle and pleura should be closed to preserve a functional serous cavity. The skin and subcutaneous tissue should be left open and a chest tube inserted.

10.9.3 Soft tissues of the abdominal wall

As with the chest, the wound should be excised and every effort made to secure peritoneal closure. Furthermore, if the development of abdominal compartment syndrome is suspected, temporary abdominal closure is preferable (Bogotá bag, etc).

For further details on abdominal compartment syndrome see Volume 2.

10.9.4 Hand

Excision should be very conservative and all viable tissue preserved to simplify reconstruction and improve the functional result. These wounds should be left open for DPC after 2 – 4 days; however, tendons and nerves should be covered by healthy tissue, through rotation flaps if necessary. Small wounds may be closed primarily.

10.9.5 Joints

Synovial membranes should be closed; if this is not possible the capsule alone should be sutured. Little harm seems to be done if the synovium cannot be closed securely. The skin and muscle should be left open.

10.9.6 Blood vessels

Blood vessels that have been repaired primarily or by vein graft should be covered by viable muscle if possible. The skin should be left open.

For specifics of each anatomic region, see Volume 2.

10.10 Dressings

Once the wound has been adequately excised, it should be covered with a bulky absorbent dressing made of dry fluffed-up gauze re-enforced with a layer of absorbent cotton wool. This is held in place with a *loose* crepe bandage or non circumferential adhesive tape. A tight bandage wrapped around the limb and soaked with exudate that dries will have a tourniquet effect. The gauze compresses should *not* be packed tightly in the wound; this will only impede drainage. The aim is to draw inflammatory exudate out of the wound and into the dressing. Exposed tendons and joint capsules may be covered with saline-soaked compresses.



ICRC

Figures 10.19.1 – 10.19.4

Big bulky dressing of fluffed gauze covered by an elastic bandage.



ICRC



ICRC



ICRC

Vaseline gauze should not be used, and the wound should not be "packed" in any way with gauze that will form a plug and prevent the free outflow of fluid.

The dressing should not be removed until taken down in the operating theatre under anaesthesia at the time of delayed primary closure. Ward dressings are an invitation to nosocomial infection. The surgeon should resist the temptation to change the wound dressing to "have a look at how it is doing". Each dressing change constitutes trauma to the healing granulation tissue and exposes it to cross-infection. A good look at the patient instead will suffice: the wound is doing quite well if the patient is smiling, eating, and sitting comfortably in bed.

If the dressing and bandage have become soaked with exudate, either over-dress with absorbent cotton, or take down the bandage and wet cotton and replace without disturbing the gauze compress that is in direct contact with the wound. The state of the dressing is not an indication of the state of the wound.

Wounds awaiting DPC should not have dressings changed until formal closure.

10.10.1 The exceptions

- Continuing *haemorrhage* requires immediate re-exploration; as do vascular changes indicating ischaemia.
- Obvious *signs and symptoms of infection:* fever, toxicity, excessive pain and tenderness, warmth, redness or shiny surface in dark-skinned people, oedema and induration, or a moist wound dressing with an offensive smell. These indicate the need for further surgical excision, which should be attended to in the operating theatre, not by changing the dressing in the ward.

All wounds awaiting DPC develop a "sour" odour after several days: the "good-bad smell" of ammoniacal products from the breakdown of serum proteins. The infected wound has a characteristic offensive odour: the "bad-bad smell".

10.11 Anti-tetanus, antibiotics, and analgesia

All patients should receive prophylaxis against tetanus. Penicillin, 5 mega-units 6-hourly i.v. should also be given from the time of admission. This should be followed by oral penicillin, 500 mg 6-hourly for a total of 5 days (see Chapter 13).

For proper rest of the injured part, and to make the patient ready for physiotherapy, good analgesia should be given (see Annex 17. A: ICRC pain management protocols).

10.12 Post-operative care

It goes without saying that proper post-operative nursing is crucial. ICRC experience has shown that the most important factor limiting the sophistication of surgical procedures performed in an ICRC hospital is not the technical expertise of the surgeon, but rather the level of post-operative nursing care. This should not be underestimated in the context of a poor, war-ravaged country.

In all cases where there is an *extensive* soft-tissue wound, even in the absence of a fracture, the entire limb should be immobilized to provide rest. This can be achieved by a plaster of Paris (POP) back slab.

The normal catabolic response to trauma must be overcome and patients offered a good nutritious diet. In a poor country, many wounded patients will arrive at hospital suffering from malnutrition. This will only compromise the body's ability to heal and resist infection.

The functional result of ultimate wound healing depends to a great extent on proper physiotherapy to retain muscle mass and joint mobility, and should be instituted early as part of the healing process.

of feudal and hierarchical power in which undue power was exercised by some over the many and the rise of a wealthy aristocracy which lived at the expense of the common people. They were also opposed to any forms of technology which would harm nature or be at the expense of people's sense of well being. Their attitude towards the universe and towards each other is summarized in the words of Lao Tzu:

> The Universe is sacred
> You cannot improve it
> If you try to
> You will ruin it
> If you try to hold it
> You will lose it
> Surrender yourself humbly
> Then you can be trusted to take care of all things.
> Love the world as you love yourself;
> Then you can truly take care of all things.


Wu Chi
Yang
Yin
North Star
5 Planets, (5 Elements)
3 Transactional Planets
Moon
Awareness Field
Field Humanity Consciousness

Fig. 9.8 *Alignment of the Cosmos*

The principles of good wound management

1. Adequate wound excision: removal of necrotic tissue, contaminated debris, organic foreign material, and blood clots.
2. Adequate wound drainage: fascial decompression, wound left open without any suturing, large bulky absorbent dressing.
3. Haemostasis.
4. Limb immobilization until healing of soft tissues.
5. Tetanus prophylaxis, antibiotics, and analgesia.
6. Nutrition.
7. Nursing and physiotherapy: mobilization of the patient.
8. No unnecessary dressing changes.
9. Delayed primary closure (4 – 5 days).

Chapter 11

DELAYED PRIMARY CLOSURE AND SKIN GRAFTING

11. DELAYED PRIMARY CLOSURE AND SKIN GRAFTING

11.1 Delayed primary closure 231
11.1.1 Methods of delayed primary closure 232
11.1.2 Dead space 232
11.1.3 Wound care 232

11.2 Skin grafting 233
11.2.1 Types of autologous skin grafts 233
11.2.2 Requisites for skin grafting 233
11.2.3 Partial thickness grafts 233
11.2.4 Reverdin pinch grafts 235
11.2.5 Application of grafts and graft meshing 235
11.2.6 Graft take 236
11.2.7 Graft care 237
11.2.8 Dressing of donor sites 237

11.3 Full-thickness grafts 238
11.3.1 Donor sites 238
11.3.2 Technique 239

11.4 Healing by secondary intention 240

11.1 Delayed primary closure

Delayed primary closure (DPC) is wound closure performed *four to seven days after injury*, which corresponds to the fibroblastic phase of wound healing. In the practice of ICRC surgical teams, the standard has been 4 – 5 days. The timing of wound closure is important; this is still defined as healing by *primary intention*.

Attempts to close wounds before they are clean must be avoided; but DPC is seldom possible later than 8 days after wound excision because of fibrosis. At this stage, healing by *secondary intention* will set in.

No wound should be closed if there is persistent contamination or infection.

For DPC, the patient is taken to theatre and the wound opened and inspected under anaesthesia. The dressing over a clean wound is dry and greenish-black in colour, and has the ammoniacal odour ("good-bad smell") of degraded serum proteins. The muscle is adherent to the gauze and, as the dressing is gently peeled away, the muscle contracts and bleeds slightly. The surface is a bright red and oozes blood. This wound is ready for DPC. Figures 11.1.1 – 11.1.5 show an example of the full sequence of wound managment with closure by skin graft.


R. Coupland / ICRC

Figure 11.1.1
Very dirty wound.


R. Coupland / ICRC

Figure 11.1.2
After debridement.


R. Coupland / ICRC

Figure 11.1.3
Five days later, removal of dressing – note the dried haemoserous discharge. As the dressing comes off, the muscle contracts and bleeds.


R. Coupland / ICRC

Figure 11.1.4
Clean wound ready for DPC; in this case by split-skin grafting owing to the large area of skin loss.


R. Coupland / ICRC

Figure 11.1.5
Wound covered by early split-skin graft.

If the wound is infected, the dressing slides off with no resistance whatsoever because there is a film of pus between it and the wound surface, which may contain areas of necrotic tissue as well as pus. The surface is a dull- or greyish-red and does not bleed. The dressing gives off the "bad-bad smell" of wound sepsis.

Such an infected wound, or one containing residual contamination or devitalized tissue, requires further surgical excision – redebridement – and is then left open again. Closure is postponed. This failed attempt at DPC is not to be confused with "serial debridement" (see Chapter 10).



H. Nasreddine / ICRC

Figure 11.2

Direct suture as DPC.

11.1.1 Methods of delayed primary closure

This is usually accomplished by direct suture: simple approximation of the deep structures and skin with minimal mobilization of the skin edges, and *without tension* (Figure 11.2). If there is tension in the suture line, the skin edges will become necrotic and the wound will break down. Small wounds may be closed using adhesive tape to approximate the edges.

The wound should not be closed under tension.

Significant tissue loss prevents approximation of the deep structures and skin. Rotation skin flaps might be useful in some anatomic locations. If bone is exposed, a musculocutaneous flap may be necessary. Larger areas require skin grafting (Figure 11.1.5).

Adequate primary surgical excision is vital for uncomplicated wound closure by DPC.

11.1.2 Dead space

As with all wounds, the obliteration of dead space is an accepted principle of DPC management. This may be technically difficult when there has been extensive loss of deep tissue. Absorbable sutures are used to approximate deep structures, but, here again, undue tension should be avoided as it will only result in local tissue ischaemia that decreases local resistance to the development of infection and impedes healing. It is not necessary to suture fascia or subcutaneous tissues.

Drains should be *avoided* whenever possible in DPC. Drains may act as retrograde conduits for skin bacterial flora and contaminants to gain entrance into the wound, and they impair the resistance of tissue to infection; a drain constitutes an additional foreign body in the wound.

Drains should never be placed in wounds without dead space; they should only be used for those with significant dead space and where there is associated oozing of blood. Within 24 hours, the oozing has usually stopped and the drain should be removed. If used, a drain should be placed dependently and, if possible, be of the suction catheter variety. Otherwise, a simple soft penrose drain will suffice.

Avoid drains whenever possible in DPC. If used, remove within 24 hours.

11.1.3 Wound care

After DPC, the wound should be covered with some layers of dry gauze which can be left until the time of suture removal. If signs of infection develop after closure, the patient is taken back to theatre where the wound is inspected, sutures removed, and the wound re-opened for drainage and redebridement if necessary. Avoid performing this procedure in the ward, where proper inspection and drainage are difficult, as it only favours the development of cross-infection.

11.2 Skin grafting

If the wound cannot be closed by direct suture or rotational flaps because of skin loss, a skin graft can be applied, sometimes combined with partial direct suture.

11.2.1 Types of autologous skin grafts

Free skin grafts may be partial-thickness (epidermis and part of the dermis) or full-thickness (including all the dermis). Partial-thickness grafts, also called split-skin grafts (SSG), vary in thickness depending upon how much of the dermis is incorporated. The thicker the graft, the less it will contract and the more it will resemble normal skin in colour and texture; but the risk of the graft failing is greater. Conversely, thinner grafts are hardy and take more readily, but contract and distort more than thick ones and have a poorer functional and aesthetic result.

Thin partial-thickness grafts
These are used for large areas and when the development of a contracture or quality of skin cover is not important.

Thick partial-thickness grafts
These are used when skin quality is important, such as over flexion creases where contractures should be avoided. However, the recipient area must be very healthy with good vascularity.

Full-thickness grafts
These are best for a good cosmetic result in the face, or to cover a sensitive functional area on the hands or fingers.

11.2.2 Requisites for skin grafting

Skin grafts can cover any wound with enough vascularity to produce granulation tissue. This does not imply that fully mature granulation tissue must be present prior to skin grafting, and early grafting for DPC, when the wound is first opened on the fifth day post-debridement, is often used (Figure 11.1.5). Early SSG has advantages and disadvantages: the wound is closed preventing any infection from developing, which is particularly important in large wounds; but the quality of resultant skin is less and there is greater tissue fibrosis and contraction. Most full-thickness grafts are also performed early.

On the other hand, a deep wound, or one over a flexion crease, may be dressed while waiting for more granulation-tissue to grow in, and then grafted at a later date. However, excessive granulation tissue should be scraped clear prior to graft application. A limb with a wound over a flexion crease should be splinted in the extension position with a plaster back slab to avoid contracture while waiting for closure.

Tissues which cannot take skin grafts include avascular areas, such as hyaline cartilage, exposed tendon without paratenon, and exposed bone cortex without periosteum. These cases will require some form of skin or musculocutaneous flap for closure. In the case of exposed bone cortex, an alternative may be the drilling of multiple small holes in the cortex to let granulation tissue grow through from the inner cancellous bone.

11.2.3 Partial thickness grafts

Split-skin grafts (thin and thick) are taken from an area which can produce a broad area of skin. The common donor sites are the thighs, back, and arms and forearms (Figure 11.3).



P. Zylstra / ICRC

Figure 11.3
Donor sites for partial-thickness grafts.



P. Zylstra / ICRC

Figure 11.4

A dermatome: various models, with disposable blades, are available – the thickness of the split skin graft harvested is controlled by the screw at the right end of the instrument; the setting is then locked using the screw at the left end.

Split-skin grafts should be taken using a dermatome, such as a Humby knife (Figure 11.4). A free hand knife, such as a De Silva knife which incorporates a razor blade, or scalpel, can be used if a dermatome is not available or if the area to be harvested is small.

The principles for the use of all hand knives are the same. The blades are disposable and are fitted into the knife. A calibration control is adjusted to set the depth of split skin required. Once this has been adjusted, a locking nut is tightened at the opposite end of the knife. It is important to check the gap between the blade and the knife before use, by holding the instrument to the light and visually checking the gap. The gap should be even throughout its length. Electric and pneumatic knives are also available but are not standard in ICRC practice.

The gap between the knife and the blade must be visually checked before use.

Harvesting the SSG

The area of skin to be removed is washed with soap and water and shaved if necessary; povidone iodine is applied. Intradermal saline or, better still, dilute adrenaline solution (1:500,000), is injected into the donor area prior to cutting, to facilitate harvesting and diminish local blood loss. The donor site, the cutting edge of the knife, and the edge of a skin board are greased with vaseline-gauze.

An assistant applies an ungreased skin board to the distal end of the donor site and pulls in such a fashion as to tense the skin tight. The assistant's other hand grasps the underside of the donor site (thigh or arm) to flatten the area from which the graft is being taken (Figure 11.5.1).



P. Zylstra / ICRC

Figure 11.5.1

Harvesting a split skin graft from the medial side of the thigh – note the assistant's left hand flattening the donor site by exerting upward pressure on the undersurface of the thigh.



E. Winiger / ICRC

Figure 11.5.2

Surgeon's wooden board applying counter-traction.

The surgeon places the greased board about 4 – 5 cm in front of the ungreased board, and exerts counter traction to increase the skin tension (Figure 11.5.2). The knife goes into the gap between the two boards at an angle of 30° and even, gentle, side-to-side cutting movements of about 2 cm are made. Continuous movement of the knife is essential. The surgeon advances the greased board proximally while exerting *minimal effort* to advance the knife. The tendency is to cut too quickly, or exert too much pressure at too high an angle; the blade will not shave the skin off but cut deeply into the subcutaneous tissue. When the desired amount of skin has been raised, the wrist is supinated and the knife cuts through. The harvested skin is now placed on a saline-soaked gauze swab, undersurface upwards, and stored until applied to the recipient area.

11.2.4 Reverdin pinch grafts

These can be used to cover large areas of defect and where the recipient area is unfavourable, such as muscles moving in different planes. A full take is not expected and the gaps between the grafts will fill in as the skin spreads outwards and coalesces. The cosmetic result is poor.

As with SSG, an intradermal infiltration of local anaesthetic with adrenaline is injected into the donor area. This helps to avoid cutting the grafts too deeply and is often all the anaesthesia required. The grafts are cut using a scalpel blade and can vary in size up to about 2 cm^2 (Figure 11.6). The harvested skin is handled as described previously until it is applied to the recipient area.



P. Zylstra / ICRC

Figure 11.6

Reverdin pinch grafts:

a. The skin is picked up with a needle and round patches of thick SSG, 1 – 2 cm in diameter, are cut with a scalpel.

b. If the patches are taken in a line, the area can be excised and the wound closed by primary suture.

c. The patches are spread over the receptor site with gaps of a few millimetres between each piece.

11.2.5 Application of grafts and graft meshing

The recipient bed is prepared by washing with saline and scraping clean any exuberant granulation tissue.



V. Sasin / ICRC

Figure 11.7

Recipient site prepared to receive SSG.

The harvested partial-thickness skin is laid across the recipient bed and cut so that it is slightly larger than the site. This allows for the cut undersurface to be in complete contact with the recipient bed and for later graft contraction. Often a graft is placed on a wound that is deeper than the thickness of the graft. In these cases the edge of the graft at the base of the wound must be carefully approximated to include the entire height of the defect.

The graft should be meshed to allow for drainage of serum and blood; this is important to avoid the graft "floating" and provide for close contact between it and the recipient bed. Meshing is accomplished by placing the harvested skin on a surface, preferably the wooden board, undersurface facing upwards, and making numerous parallel incisions through the graft with a No. 15 scalpel blade. Optimally, the ratio of gaps to skin should be 3:1 thus allowing the SSG to cover an area three times its original size (Figure 11.8). Over a period of 10 – 14 days, the skin grows across the interstices and complete healing is obtained.

Graft meshing is particularly useful in cases where there is insufficient autograft to completely cover raw areas, such as large wounds or burns (see Figure 11.1 for a clinical example). Mechanical meshing machines are available – and expensive – but are not standard ICRC equipment except in hospitals with a large number of patients suffering from burns. A good improvisation is a sharp circular pizza cutter, modified with notches ground into its circumference, and used to mesh skin against the wooden board.



H. Nasreddine / ICRC

Figure 11.8

Meshing of a skin graft.

Grafts can often be kept in place by a suitable dressing and elastic bandaging. If graft stability cannot be ensured by the covering dressing, it should be sutured in place (Figure 11.9). One technique is a continuous 3/0 non-absorbable suture run around the edge of the graft to provide adequate contact. Another is to use several anchor sutures about the circumference, left long and used as tie-overs across the dressing; especially useful for small grafts on hollow areas (Figure 11.11). The excess skin of the graft can either be trimmed once the graft has been sutured in place, or cut 10 – 14 days later.

Figure 11.9
SSG sutured in place.



V. Sasin / ICRC

Once the graft has been sutured or placed on the recipient bed, it should be covered with a sheet of vaseline-gauze followed by a gauze compress or cotton-wool pledgets soaked with saline. These dressings should be pressed into the concavities of the defect to ensure that there is complete apposition between the graft and the bed. The dressing should then be covered with a thick layer of cotton wool held in place by a crepe bandage.

In case of consistent oozing from the recipient bed, consider delaying the application of the graft for 24 – 48 hours. The harvested skin can be stored for up to three weeks in an ordinary domestic refrigerator at 4° C without compromising the success rate. It is placed on a moist piece of gauze with the undersurface facing upwards and then put in a sterile jar containing normal saline. Jars should be stored with an airtight lid and *carefully labelled* with the patient's identification and the date of harvesting.

> Delayed application of split skin grafts is often the preferred method.

11.2.6 Graft take

Grafts adhere initially by a thin layer of fibrin and are fed by "plasmatic imbibition" from the recipient bed granulation tissue until in-growth of capillaries occurs by about the fourth post-operative day. The new capillaries link with the graft and the fibrin clot is transformed into fibrous tissue. For these reasons, there are three major factors determining the success rate of split-skin grafts.

1. A vascular recipient bed which is *free of pathogenic bacteria*. Normal bacterial flora will not necessarily interfere with graft survival. The most common pathogen causing graft failure is beta-haemolytic *Streptococcus pyogenes*, probably through its fibrinolytic enzymes. ICRC protocol suggests prophylaxis with penicillin for five days, to which this bacterium remains sensitive.

It may well be that, precisely because Taoist practitioners refused to be co-opted by the establishment and were relegated to a precarious position, the practices could survive. As such, these practices, as synthesized in the Universal Tao, constitute a synthesis of several thousands of years of the practice by generations of Taoist masters in the science of feeling and sensing inward and of observing the nature of the universe and our relations with it.

The above provides evidence that Taoists over the centuries had a genuine concern about the well-being of the common people and that their practice was no reason to disengage from the world. The many stories and legends of the Immortals show that they were greatly loved, especially by the common people and the poor whom they often protected and helped. Their practice of gentleness (kidney), of generosity (liver), love and respect (heart), fairness and openness (spleen) and courage (lungs) expressed a strong sense of compassion with those who suffered.

Body as the Primary Source of Cognition

In the evolution of Western culture with its progressive disconnection between body and mind, thinking and feeling, rationality and emotions, mind and energy, inner and outer, matter and energy, linearity and spontaneity, feeling as a source of awareness and the primary mode of cognition has been progressively devalued.

It was seen as a feminine value of little use except in some domains as that of the arts and artistic endeavor. In religion it was looked at, together with the body, sexuality and emotions, as a potential source of evil. In science with its drive for objectivity, it was also looked at with suspicion, as it tended to disturb and undermine the demands for objectivity.

Thus it was relegated to a position of inferiority, as it was supposed to interfere with rationality, discipline and order, needed for progress and the growth of modernity, as well as with the need to control the universe, the cosmos, nature and ourselves.

In the Taoist tradition, feeling as the power of intuition, rooted in the body and the ability of self-reflection has always been considered as the primary source of self-awareness. Jung has named this form of cognition the knowledge of the unconscious, which underlies all conscious activity of the mind.

2. The *vascularity* of the graft itself. Thin split-skin grafts have a higher concentration of capillaries on their undersurface than thick grafts. For this reason, a thin split-graft has a higher chance of survival than a thick one.
3. The maintenance of *close contact* between the graft and the recipient bed. If the graft is under tension, if blood or serum collects between the surfaces, or if there is movement of the graft on its bed, satisfactory contact cannot be maintained. Thus, meshing of the graft and tight contact between the graft and recipient site are important; grafts spanning joints should be splinted to prevent graft loss from shearing forces.

Grafts should be harvested under sterile conditions and placed on a clean, well-vascularized recipient bed. It is imperative that there be tight contact between the graft and its bed.

11.2.7 Graft care

Grafts must be cared for by experienced personnel. A graft may be *saved* if a collection of serum or haematoma is evacuated early. Great care must be taken not to *lose* a good graft through clumsy or careless removal of the dressing.

Grafts require careful nursing care.

In ICRC practice, the graft is first inspected after 48 – 72 hours; the dressing is carefully removed using two pairs of tissue forceps: one holding the graft and keeping it applied to its bed, the other removing the dressing. Care must be taken not to tear away the graft. If the graft is healthy and adherent to the recipient base, another vaseline-gauze and compress are bandaged in place and no further dressing is necessary for another 10 days, until the time of stitch removal.

If a haematoma or seroma is found, the fluid should be expressed through the meshed gaps using gentle pressure applied through the forceps and a pledget of soaked cotton-wool. Another firm dressing of vaseline-gauze is applied. These grafts are then inspected on a daily basis until firmly adherent to the recipient base.

Any small pus collections should be debrided with scissors to prevent spread of infection. Intra-epidermolysis is a phenomenon where the outer layer of the graft is lost while viable epithelial cells remain at the base. Dark blisters can be seen and may be debrided but great care should be taken not to disturb underlying graft that may still be viable.

On the other hand, any graft which is dead or floating on a "sea of pus" should be removed and the wound cleaned with normal saline. (If Pseudomonas is the culprit – presence of bluish-green pus – a dilute vinegar solution is useful.) If the raw area of the wound is more than 2 x 2 square cm, it should be re-grafted when clean. If smaller, it can be left to heal by secondary intention.

At ten days, a healthy graft should be firmly adherent and can be left exposed and submitted to a simple daily inspection.

11.2.8 Dressing of donor sites

Split-thickness donor sites can bleed briskly, and in children can result in significant blood loss. As mentioned above, the donor site should be infiltrated intradermally with a 1:500,000 solution of adrenaline or a local anaesthetic with adrenaline to decrease bleeding. They can also be extremely painful, especially when dressings become firmly adherent.

The following regimen minimizes discomfort and complications.

1. After harvesting the SSG, a dry dressing should be applied immediately, kept in place if necessary with an elastic bandage, and left alone while the graft is being applied; by which time haemostasis has usually been achieved.
2. The dressing should then be removed. If there is persistent bleeding, a compress wetted with the dilute adrenalin solution should be applied and direct pressure exerted for a few minutes.
3. Next, the donor site should be covered with a firm pressure dressing of vaseline-gauze, dry compresses and elastic bandage; it should be kept from falling down the limb by adhesive strapping. The dressings should be left *in situ* for 10 –14 days, unless there are signs of underlying infection.
4. A membrane dressing, such as Opsite ®, can be used if available. If fluid accumulates beneath the membrane, it can be evacuated by pricking with a needle and pressing. The perforation site should be covered with a smaller piece of membrane. If the dressing falls off it can be reapplied. Generally, this stays in place for the desired period of about ten days.

11.3 Full-thickness grafts

Full-thickness skin grafts consist of the epidermis and entire dermis. These grafts are used principally for the *head and neck* and *hands and feet* to provide thicker, better-quality cover.

Full-thickness grafts have a number of advantages apart from better texture and colour. They allow for the transfer of hair-bearing skin, as all the dermal adnexal structures are intact, and they contract less than split-skin grafts. The main disadvantages are a lower survival rate and their limited size.

The recipient bed must be in optimal condition to take a full-thickness graft; haemostasis, in particular, must be perfect. There should be meticulous suturing and approximation between the graft and the recipient edge. Generally, a full-thickness graft is small because the plasma exudate of the recipient bed is barely sufficient to feed and oxygenate the graft, and capillaries from the recipient bed and edge and graft undersurface must grow in quickly to assure survival.

11.3.1 Donor sites

The best and most readily available donor sites are the supraclavicular fossa, in front of and behind the ear, and the flexor surface of the forearm or the groin creases. In older persons, the cheek or the neck in the line of a skin crease may also be used. The donor site is sutured primarily following harvesting of the graft.



P. Zylstra / ICRC

Figure 11.10

Donor sites for full-thickness skin grafts.

11.3.2 Technique

The graft can be taken under local anaesthesia. The donor and recipient areas are cleansed in a sterile fashion and a template of cut gauze compress made to fit the defect exactly. The template is placed on the donor site and an outline drawn around its circumference. The donor area should be injected with local anaesthetic *with* adrenaline and the edge of the recipient area with local anaesthetic *without* adrenaline; both are left for five minutes before incision. The full-thickness skin should then be excised exactly.

The graft must be *thoroughly defatted* before application. This is best achieved by placing the moist graft, epidermis-side down, on the finger tip and scrupulously excising the fat using fine scissors. The graft is left unmeshed.

The graft is then sutured in place immediately and meticulously. Several interrupted nylon sutures are inserted close to the edge and left long for tie-overs (Figure 11.11). Small interrupted or continuous fine nylon sutures (5/0 if available) are placed around the circumference.


a
wound
b
wound covered with graft being sutured from within outwards
c
trim away excess graft
one end of the sutures left long all round the wound
d
cotton wool tied over in place

M. King / Primary Surgery Volume 2

Figure 11.11

Tie-over method of securing skin grafts.

Face grafts may be left open and covered with antibiotic ointment. They may be gently rolled with gauze or poked with a needle in the first 48 hours to express small serum collections.

On the hands or over a flexion crease, once the graft has been sutured in position a bolus of dressing is fashioned with vaseline-gauze and moist cotton-wool pledgets to hold the graft closely in contact with the recipient bed. The tie-over sutures are brought together over the dressing, which should be snug, but not so tight as to strangle the graft.

The dressing should be left in place for 7 – 10 days and then removed. At this point, in both light- or dark-skinned people, the graft may be any colour from pinkish or pinkish-white to bronze to black. Even a graft that has a blackish appearance on inspection can survive. No judgement on graft survival should be passed until a month from the time of application.

11.4 Healing by secondary intention

Some small wounds are difficult to suture without tension, or without very wide mobilization of skin flaps, because their surrounding edges are fibrotic. There is little benefit in another surgical operation, even skin-grafting. These wounds are best left to granulate and heal by secondary intention (Figure 12.10).

A change of dressing and gentle washing with normal saline every 4 – 5 days is usually sufficient: every dressing is a trauma to a healing wound. Daily dressings are not necessary if the wound is dry. Some traditional local dressings (sugar, honey, etc.) have an antibacterial effect and promote the formation of granulation tissue and are useful if the wound is deep. They have been used successfully by ICRC surgical teams.

Chapter 12

NEGLECTED OR MISMANAGED WOUNDS

12. NEGLECTED OR MISMANAGED WOUNDS

12.1 General considerations 245

12.2 Chronic sepsis: the role of biofilm 247

12.3 Surgical excision 248
12.3.1 Soft tissues 249
12.3.2 Bone 249
12.3.3 Irrigation 250

12.4 Antibiotics 250

12.5 To close or not to close? 251

12.1 General considerations

As described in Chapter 10, in many war zones today, characterized by irregular bush warfare, rebellions and insurrections, neglected and mismanaged wounds are amongst the commonest injuries that the surgeon sees. First aid is not available, doctors and nurses are scarce, and health services have been disrupted by poverty and conflict. Distances are long and the terrain difficult with little in the way of organized transport. Many patients reaching hospital have wounds which were inflicted more than 24 hours earlier, and some have wounds that are many days, or even weeks, old. Even if injured patients reach hospital fairly quickly, the sheer number of casualties often exceeds the surgical capacity or expertise available. The result is an inordinate delay in their treatment or frank mismanagement.

ICRC EXPERIENCE

In the ICRC hospital of Lokichokio in northern Kenya serving the victims of the conflict in southern Sudan, 12,264 war-wounded patients were registered between 1991 and 2006 in the ICRC surgical database. Evacuation was by ICRC and United Nations airplanes and few, if any, received pre-hospital treatment of any sort. Of these patients, 84 % reached the hospital more than 72 hours after injury. ICRC staff have seen similar conditions of delay in evacuation to a surgical facility in Somalia, the Democratic Republic of the Congo, Nepal and elsewhere, and have seen the same phenomenon with crush wounds after earthquakes in low-income countries.

Before reaching a proper surgical hospital, some patients receive no treatment at all; others a cursory dressing, while yet others have undergone an inadequate wound excision. Some wounds will have been sutured, generally without any form of excision.

All sutured wounds, no matter how clean they appear, must have their sutures removed and opened up for drainage. As mentioned previously, the simple rules of septic surgery apply. Never close infected or contaminated wounds primarily.

Remove all sutures from previously sutured wounds.


H. Nasreddine / ICRC

Figure 12.1.1

Patient A: The gunshot wound to the left iliac region was sutured 5 days previously. The wound to the right thigh underwent insufficient wound debridement.

After delay, some Grade 1 minor soft-tissue wounds are found to be healing spontaneously. Most wounds, however, will be inflamed or frankly infected with a degree of chronic sepsis, and some will be grossly putrefying. This is often seen in mismanaged wounds. Tetanus, gas gangrene, and invasive haemolytic streptococcal infection are ever present dangers (see Chapter 13). These wounds require aggressive excision.


H. Nasreddine / ICRC

Figure 12.1.2

The sutured wound is infected; a pearl of pus is evident at the lateral edge.


H. Nasreddine / ICRC

Figure 12.1.3

Sutures have been removed revealing abundant pus.


ICRC

Figure 12.2.1

Patient B: primary suture was performed – note the tension in the wound due to tissue oedema and infection. Some sutures have been removed.


ICRC

Figure 12.2.2

All stitches have been removed – the skin edges are ischaemic and necrotic and the subcutaneous tissues oedematous.


ICRC

Figure 12.2.3

After redebridement – the wound is now larger than the original injury.


H. Nasreddine / ICRC

Figure 12.3

Neglected gunshot wound to the knee with frank sepsis.


H. Nasreddine / ICRC


H. Nasreddine / ICRC

Figures 12.4.1 and 12.4.2

Neglected wound to the scrotum with gangrenous tissue.

This capacity to intuit reality (the ability to sense reality in its totality may be called an integral form of knowledge) exists in our whole bodily being. It may also be called a mode of thinking with the body which precedes all formalized codes of thinking which evolved with the advance of formal rationality and the split of body and mind, typical of Western culture.

In that sense it may be called a Yin form of cognition, as opposed to the Yang form of cognition, which characterizes the modern world and its connected forms of education, science and technology. Yet there is abundant evidence that at the source of all genuine creativity and inventiveness, including in the field of science, lies the power of intuition.

In that sense, the practice of the Universal Tao and the Fusion Practices, deeply rooted in the Taoist tradition, may be seen as a way to recover this form of knowledge within ourselves so that the split within ourselves between body and mind, feeling and thinking is overcome. In the great Asian traditions, thinking in its restricted sense as the linear activity of the brain has been viewed as interfering with and affecting awareness as the primary and principal form of knowledge, essential for turning knowledge into understanding.

From a Taoist perspective, the primary learning process does not take place in the brain but in the organs. Recent findings corroborate the Taoist vision of the learning process that the brain only processes what is experienced and known intuitively by the organs, in particular those in the lower Tan Tien.

Our deep memory which structures our patterns of reaction and response to the world lies in the organs. In this view, a learning process needs to be rooted in a relearning and a reprogramming of our subconsciousness in the organs from which all conscious activity springs. In terms of contemporary technology the organs are the software and the brains are the hardware.

Unity of What is Above and Below

In many recent attempts to revitalize and recuperate spirituality, a growing need is felt to counter the ominous trend towards a loss of meaning in the world of today. There is a tendency to continue the split, which inspired many spiritual traditions, which tended to be based on the duality of good and evil, higher and lower.

Please note:

Many neglected wounds are infested with maggots. There is a long historical literature about "maggot debridement therapy", especially for chronic wounds, and a number of surgeons around the world practise it today. Suffice it to say that, for cultural and psychological reasons, most patients do not accept such a method. ICRC experience in this domain, although often positive, can only be described as anecdotal.



E. Dykes / ICRC

Figure 12.5

Maggot infestation of a wound. (The colouring is due to gentian violet.)

Please note:

There is much clinical and experimental evidence to back the claim that the early administration of antibiotics, penicillin in particular, can delay the advent of serious infection in war wounds. It is ICRC practice in first-aid posts to begin penicillin as soon as possible. However, adequate first-aid measures, as described in Chapter 7, are seldom available in many contemporary theatres of war and it is to this context that the present chapter is devoted.

12.2 Chronic sepsis: the role of biofilm

The chronic pyogenic sepsis of a neglected wound has its own particular pathology and bacteriology, and life history. Bacteria exist in discrete colonies only in a laboratory. The natural state of bacteria through natural selection is to become attached to surfaces, especially to inorganic or dead matter, such as sequestrated bone and cartilage. In chronic infection, bacteria secrete a glycopolysaccharide biofilm; this is the "slime" one feels on the rocks in a river. This biofilm protects the bacteria and prevents not only antibiotics, but macrophages, leukocytes and antibodies from attacking them. It must be actively broken up in order to eradicate the infection.



Bacteria contaminate wound in significant quantities
Dead material is present
Dead material results from infective process itself
Bacteria rapidly progress through log phase of growth
Bacteria reach stationary phase
Biofilm often forms
Chronic sepsis is the result
Surgical intervention removes biofilm and dead material
Residual bacteria go back to log phase

D. Rowley / U. of Dundee

Figure 12.6

Schema of the chronic infective process.[1]

The biofilm is secreted during the stationary phase of bacterial life. Physical disruption of this biofilm and surgical removal of the dead tissues are required to push the bacteria back into the rapid multiplication of the log phase when they are most susceptible to antibiotics and the body's natural defence mechanisms.

---

[1] Rowley D.I., University of Dundee, Course on chronic bone infection, Seminar on the Management of War Wounds; ICRC: March 18, 2005; Geneva.



E. Dykes / ICRC

Figure 12.7.1

Neglected infected wound showing a layer of biofilm pus.



M. Dalla Torre / ICRC

Figure 12.7.2

Neglected wound of an amputation stump, without biofilm layer.



R. Coupland / ICRC

Figure 12.7.3

Neglected wound to the arm with necrotic tissue, but dry.

12.3 Surgical excision

Surgical excision is a more difficult procedure in these neglected and mismanaged wounds. The line of demarcation between viable and non-viable tissue, especially in oedematous muscle and fascia, is less obvious, and the zone of post-traumatic inflammatory hyperaemia is compounded by that of infective inflammation and the presence of the biofilm. The extent of adequate excision is more difficult to assess since there is not only a "mosaic" of ballistic tissue destruction in the permanent cavity itself but also that due to the septic process. Festering wounds that are days old have regions of infection mixed with regions of fibrous tissue healing.

The wound often resembles a cavity filled with detached soft tissue, bone fragments or the ends of fractured long bones, foreign debris, and fibrous tissue, covered with a coat of pus (Figures 12.7.1 and 12.8.2). Access may be difficult because of areas of wound contracture due to the tough fibrous tissue.

The principles of surgery remain the same, however. The skin and deep fascia must be widely re-incised and the wound cavity laid open for proper visualization and drainage (drainage following the same principle as for a simple abscess). The excision is directed towards the *removal* of all non-viable and heavily contaminated tissue and foreign debris, and the *physical disruption* of the biofilm.

Because surgical excision is more difficult in these wounds, there is a higher incidence of persistent infection. In such circumstances, several redebridements may become necessary. Depending on the experience of the surgeon, these are the patients who might most benefit from staged serial debridements.

12.3.1 Soft tissues

If present, all sutures must be removed and debridement performed as if no previous wound toilet had been done.

All macroscopic contamination should be excised. Skin and subcutaneous fat must be cut back until they ooze blood. Grossly infected fascia is usually shredded and dull grey, while healthy fascia is a glistening white. The muscle compartments are in even greater need of decompression than those of a fresh wound.

Contractility is the best indication of muscle viability. On the other hand, the surgeon must learn to distinguish between bleeding from small vessels in partially necrotic tissue, and capillary oozing from healthy but inflamed tissue. Experience brings an increase in the amount of tissue excised. Vessels and nerves should be left intact on the other hand, because they rarely turn septic.

Operative blood loss is usually considerable because of the inflammatory oedema and hyperaemia.

It is even more important *not* to open up healthy tissue planes in an attempt to remove any projectile. This will only help to spread the infection.

12.3.2 Bone

If there is an underlying fracture in these septic wounds, it usually contains *detached and necrotic* bone fragments that provide the perfect "surface" for bacterial adhesion. It is vital that these be found and removed. A plain X-ray will assist in their identification (Figure 12.9.2).



F. Jamet / ICRC

Figure 12.8.1

Gunshot wound 7 days after inadequate debridement.



F. Jamet / ICRC

Figure 12.8.2

Obvious sequestra presenting at the wound surface – note the presence of a pus-filled biofilm covering bone and soft tissue.



F. Jamet / ICRC

Figure 12.8.3

Wound 7 weeks after debridement.

Totally detached bone fragments are often trapped inside fibrous tissue and their localization and identification can be extremely difficult and frustrating.

- A dead bone fragment is pearly white; living bone is dull greyish-white with red capillary specks.
- If scratched with a bone curette, dead bone will give off a high and hollow resonance; living bone sounds low and dull.
- Another telltale sign can be observed when the bone fragment is grasped with forceps and a motion of pronation and supination imparted. If muscle or periosteum is holding the fragment in place, these structures will move with the pronation and supination. If the fragment is detached and held by fibrous tissue only, the movement will break the fibrous adhesion and the bone fragment will come free.


H. Nasreddine / ICRC

Figures 12.9.1 and 12.9.2

All loose bone fragments must be removed.


H. Nasreddine / ICRC


H. Nasreddine / ICRC

Figure 12.9.3

Bone fragments on the right, excised fibrous tissue on the left.

Once all loose bone fragments have been removed, the wound cavity is then curetted and a careful finger exploration performed to confirm a smooth surface: sharp bone edges may injure the exploring finger! All detached and dead bone fragments must be removed; they are already sequestra. Sometimes, several attempts may be necessary to eliminate them all, i.e. several redebridements.

All detached bone fragments are sequestra.

12.3.3 Irrigation

The wound is now copiously irrigated and dressed as for routine surgical excision. The ICRC has tested irrigation with a high-pressure pulsatile lavage and daily showering of the open cavity in these neglected septic wounds. Although both techniques appeared to clear up the biofilm and afford a better assessment of tissue viability, the results were inconclusive. Both involve a great deal of time, effort, and nursing care, and are difficult to maintain if a large number of patients are under treatment with no possibility of transfer to other less overstretched facilities.

12.4 Antibiotics

Penicillin and metronidazole are given, according to the antibiotic protocol (see Chapter 13); and gentamycin is added if there are signs of active spreading inflammation. No topical antibiotics or antiseptics are used in ICRC practice.

Bacterial culture should be done, if available. Good bacterial culture and sensitivity in a forward hospital is far more diffucult to accomplish than is usually realized. Note that clinical response does not always follow laboratory sensitivities, or lack thereof. Not only do "wild" bacteria not live in colonies, but *in vitro* sensitivity does not always reflect *in vivo* response, and the surface or discharge flora does not always represent the bacteria present *inside* the tissues.

Nonetheless, the basic rules of septic surgery still apply. Infection requires good drainage – as with an abscess – and the elimination of the bacterial culture medium, i.e. the dead tissue. Antibiotics will only be effective once the biofilm has been disrupted and the bacteria made susceptible to their action.

Persistent or recurrent wound infection requires re-excision, not ward dressings.

12.5 To close or not to close?

The primary phase of wound healing begins at the moment of wounding. It is well established by the time of presentation if the wound is a few days old. Thus, several days after surgical excision, many wounds are past the time of healing by primary intention. There is already much fibrous tissue present (Figure 12.9.3) and even more by the time the wound is clean and ready for closure. If secondary suture is attempted there is usually considerable tension on the wound edges with a high incidence of necrosis and breakdown.

The majority of these wounds are unsuitable for delayed suture and require skin grafting or rotation skin flaps for closure; or, if small, should be left to granulate and heal by secondary intention (Figure 12.10).

Most delayed or neglected wounds will be unsuitable for delayed primary closure.

It is in healing by secondary intention that several traditional local wound treatments may be of value, as mentioned in Chapter 11. ICRC surgeons and nursing staff have used dressings of honey or sugar, or hypertonic saline (add salt to normal saline until it no longer dissolves), which promote granulation tissue formation and have antibacterial properties. It must be emphasized that these topical treatments are an *adjunct to*, and *not a replacement for*, adequate surgery.



F. Jamet / ICRC

Figure 12.10

Healing by secondary intention.

Many patients with severe wound infection or frank putrefaction are malnourished, anaemic and dehydrated. As a result wound healing is poor and special measures should be taken to address these concerns.

For a discussion of post-traumatic osteomyelitis, see Volume 2.

Chapter 13

INFECTIONS IN WAR WOUNDS

13. INFECTIONS IN WAR WOUNDS

13.1 Contamination and infection 255

13.2 Major bacterial contaminants in war wounds 256

13.3 Major clinical infections of war wounds 257
13.3.1 Definitions 257
13.3.2 Gas gangrene 258
13.3.3 Tetanus 260
13.3.4 Invasive streptococcal infection 262
13.3.5 Necrotizing soft-tissue infections 263

13.4 Antibiotics 263
13.4.1 Antibiotic prophylaxis in the primary treatment of war wounds 264
13.4.2 Cephalosporins and others 265

13.5 Neglected or mismanaged wounds 265

ANNEX 13. A ICRC Antibiotic protocol 266

13.1 Contamination and infection

All war wounds are grossly contaminated by bacteria. Bullets and fragments are not sterilized on discharge and, at the entry site, bacteria are carried into the tract by the contaminated projectile itself. Furthermore, the negative pressure of the temporary cavity at both entrance and exit wounds also sucks in bacteria.

War wounds are dirty and contaminated from the moment of injury.

Other contaminants found in war wounds include clothing fragments, dust, miscellaneous organic matter (mud, grass, leaves, etc.), and wood and glass splinters from bombed buildings. Studies in Korea and Viet Nam showed that different varieties of soil are associated with different organisms – which also vary according to weather and season – with varying likelihood of producing severe infection (mud and agricultural soil contaminated with animal or human excrement are apparently the worst). In addition, the chemical composition of some soils can inactivate antibodies and impair leukocyte phagocytosis. Various home-made landmines have contained animal manure contaminant.

It is important, however, to distinguish between:
- simple contamination of a wound;
- local sepsis; and
- invasive infection.

In a contaminated wound, bacteria proliferate in dead tissues but no invasion of viable tissue takes place until the number of bacteria reaches a threshold of 10^6/gram of tissue. The presence of crushed tissues, dirt, and other foreign materials lowers the threshold of infection and invasion, by providing an environment where bacteria can grow and replicate without the patient's immune system being able to eliminate them. There are a number of *microbe-related risk factors* involved: virulence, production of enzymes and toxins, etc.

The body attempts to wall off the mass of necrotic muscle and bacteria with a fibrin barrier. Without adequate drainage, this will form an abscess; with proper drainage the necrotic mass will be expelled after 10 days.[1] In both cases, the body's natural defence mechanisms come into play to isolate the contaminants and the dead tissues.

When the local defence mechanisms can no longer cope, invasive deep tissue and systemic infection occurs. Patient immunity and resistance can also be weakened by malnutrition and chronic disease, especially HIV/AIDS. The local defence mechanisms and general resistance constitute the *host-related risk factors*.

Six hours appears to be the critical period after contamination. The efficacy of surgery and antibiotics to prevent infection decreases with time from injury, while the bacterial load increases exponentially. As with the differential grading of wounds according to the Red Cross Wound Score described in Chapter 4, a good understanding of the pathology involved is important in determining the proper and adequate procedure to follow, and the usefulness of antibiotics to *supplement* excision, drainage, and the body's natural resistance to infection. Uncomplicated soft-tissue Grade 1 wounds, as we have seen, can be treated with simple wound toilet; an antibiotic treatment helps if begun within 6 hours. Early administration of antibiotics in more severe wounds seems to inhibit bacterial growth and limit local invasion, at least temporarily. Any delay beyond six hours, however, greatly increases the risk of infection.

---

[1] Fackler ML, Breteau JPL, Courbil LJ, Taxit R, Glas J, Fievet JP. Open wound drainage versus wound excision in treating the modern assault rifle wound. *Surgery* 1989; **105**: 576 – 584.

13.2 Major bacterial contaminants in war wounds

The relative preponderance of various bacterial species differs according to geography, topology of the terrain, and climate: agricultural land, urban environment, jungle, or desert; summer or winter. The presence of community-acquired resistance in "normal" body flora also differs from region to region, and with the passing of time.

Nonetheless, certain constants remain, and the following list gives a general indication of the common pathogens involved in infections of war wounds.

Gram-positive pyogenic cocci:
Staphylococcus aureus and β-haemolytic streptococcus. These are a normal part of the skin flora. In recent years, community-acquired methicillin-resistant *Staphylococcus aureus* (MRSA) has become more of a problem in certain countries.

Gram-negative bacilli:
Escherichia, Proteus, Klebsiella, Pseudomonas, and Bacterioides are found in the gastro-intestinal tract. *Acinetobacter baumannii* is to be found in the soil and on the skin and has recently become important in causing nosocomial infections.

Gram-positive bacilli:
The Clostridia species are spore-bearing obligatory anaerobes. They are widely distributed in the environment, especially in agriculturally fertile soils, and are carried in the faeces. They are the cause of gas gangrene and tetanus.

Wounds to the upper thigh and perineum are particularly at risk from contamination by faecal organisms (Clostridia and Gram-negative bacilli), even without bowel perforation. Bowel injury demonstrably increases the risk of sepsis.

War wounds have a "bacteriological life history": contaminating bacteria change with time.

Different infections occur early or later in the wound's history.

The important point to note about this varied bacterial flora is that wound contamination is not static. That war wounds have an evolving "bacteriological life history" from the time of injury has been known since World War I and the studies made by Alexander Fleming.[2]

Many studies since have demonstrated that wound contamination – and any resulting infection – evolves with time. At the instant of wounding, there is polymicrobial contamination with particular risk from Clostridia and β-haemolytic streptococcus. Afterwards, self-contamination from skin and gastro-intestinal flora occurs; finally, hospital-acquired nosocomial bacteria may step in.

This concept is essential to understanding the roles of hygiene and environmental control measures, adequate surgery, and the use of antibiotics: i.e. the *operation-related risk factors*.[3] The widespread availability of antibiotics – and their abuse – during the last fifty years has further complicated the bacteriology of wounds because of the hospital selection of resistant strains. Whether infection follows contamination, and what type of infection develops, depends on a number of factors.

The major threats faced by the war-wounded are the development of gas gangrene, tetanus, and invasive streptococcal bacteraemia, which can all be fatal.

---

[2] Fleming A. On the bacteriology of septic wounds. *Lancet* 1915; **186**: 638 – 643.

[3] Rubin RH. Surgical wound infection: Epidemiology, pathogenesis, diagnosis and management. *BMC Infect Dis* 2006; **6**: 171. Available at: http://www.biomedcentral.com/1471 – 2334/6/171.



Fig. 9.9 *As Below So Above*

As the lower part of the body and its organs is looked at as associated with the instinctive animal obscure part, connected with sexuality, which prevents the mind and the spirit from its upward vocation, it is ignored and bypassed. The Taoist approach fully honors and recuperates the dignity of the body as a whole. The Tao recognizes the belly and its organs, connected with our sexuality and water energy which is the source of creative power from which all energy transformations flow. By getting in touch with our most intimate parts, we also gain access to the source of our creative powers.

In that sense, the Fusion Practices invite us to reconnect with those parts of ourselves, both physically and psychically, which have been the focus of repression. This repression is not only in most of our cultures but also within ourselves, as we internalized what we learned and accumulated in our culture, at home, in school and though the media. In order to reconnect and truly get in touch with our organs, we need an instrument which is capable understanding them.

13.3 Major clinical infections of war wounds

The polymicrobial nature of wound contamination can result in a variety of infections. Several specific lethal infections are notorious in war wounds, especially in neglected or mismanaged wounds, and particularly if they have been stitched closed without proper excision. Common pyogenic wound infection runs through a spectrum of disease from the minor (superficial surgical site infection) to the severe (organ or space surgical site infection) and systemic (septicaemia).

13.3.1 Definitions

Simple contamination
The surgical literature classifies wounds as clean, clean-contaminated, contaminated, and infected or dirty. War wounds are considered contaminated *and* dirty.

Cellulitis/local abscess formation
Bacteria begin to spread to tissues that are contiguous to the wound, in the zone of contusion (see Chapter 3). Little systemic toxicity exists. Superficial erythema and seropurulent discharge occur; some necrotic tissue is evident, but this is related to the original injury and not to the infection. Eventually a mass of necrotic tissue and bacteria forms; if drainage is inadequate (small skin wounds), an abscess develops. In a large wound, the mass will be walled off and then expelled.

Myositis/deep tissue infection
Bacteria spread into muscles and tissues further than the permanent cavity and the zone of contusion and invade the zone of concussion and beyond. Systemic symptoms become more pronounced and, with certain infections, come to dominate the clinical picture. Overwhelming infections usually present with the classical signs of sepsis (fever, tachycardia, etc.); but they may also present without these signs, particularly in immune-compromised patients (HIV/AIDS, chronic disease, malnutrition).

In the past, deep-tissue infections were usually caused by Clostridia and invasive β-haemolytic streptococcus and accounted for the greatest amount of tissue damage, and the most severe systemic signs and symptoms. The availability of penicillin has radically changed this clinical picture.[4]

Different types of invasive tissue infection have been described:
- pyogenic deep tissue infection – this is usually a mixed infection, Gram-positive and -negative organisms, often including non-clostridial anaerobes;
- gas gangrene: this infection is still seen in neglected and mismanaged wounds;
- tetanus: poverty and the disorganizing effects of war disrupt immunization programmes in many countries – this infection is still, all too often, a major killer;
- invasive streptococcal infection – also still seen in neglected and mismanaged wounds;
- bone infection: when deep-tissue infection extends to sequestrated bone fragments chronic sepsis tends to develop with the production of a "biofilm" – this is often seen in neglected and mismanaged wounds (see Chapter 12);
- necrotizing fasciitis, synergistic gangrene and anaerobic cellulitis.

---

[4] Polhemus ME, Kester KE. Infections. In: Tsokos GC, Atkins JL, eds. *Combat Medicine: Basic and Clinical Research in Military, Trauma, and Emergency Medicine*. Totowa, New Jersey: Humana Press; 2003: 149 – 173.

13.3.2 Gas gangrene

Gas gangrene as a peculiar complication of wounds has been known since the time of Hippocrates. Its occurrence in war wounds throughout history as well as in other trauma has been widely described mainly because of its dramatic manifestations and very high associated mortality. Delay to surgery, as may occur during war or in a civilian disaster with mass casualties, greatly increases the risk of gas gangrene.

Gas gangrene is a rapidly-spreading oedematous myonecrosis occurring characteristically in severe wounds in muscles contaminated with pathogenic obligatory anaerobes, particularly *Clostridium perfringens*. Almost every case presents a mixed bacterial flora; aerobes use up available oxygen and promote the anaerobic environment required by Clostridia.

In large muscle wounds there will always be areas of ischaemia and the potential for gas gangrene. But gas gangrene can also develop even when the trauma is not very severe. If the wound is deep, contains necrotic tissue, and is *isolated from the surface*, an anaerobic environment is formed and it is possible for a clostridial infection to become established. This deep anaerobic environment is seen particularly in wounds sutured closed without debridement. The presence of foreign material in wounds, especially soil, will increase the risk of developing gas gangrene. The prolonged application of tourniquets or tight plasters and fascial compartment syndrome also present high risks. The infection is more common in wounds to the lower limb and perineum than to the upper limb.

The features of the disease result, first, from the local action of the organisms on muscle glucose, producing acid and gas, and on muscle protein, causing digestion. Second, the organisms produce soluble, very potent toxins, which diffuse into the tissues causing further tissue destruction and profound toxaemia. The muscle breakdown products are very toxic in their own right. The combination of breakdown products and specific toxins causes the relentless and profound toxaemia which, if untreated, will inevitably lead to death.

Early and adequate surgery will prevent gas gangrene in war wounds.

The *incubation period* of gas gangrene is usually short, almost always less than three days, and in the majority of cases less than 24 hours long; it may even be as short as 6 hours. Incubation periods of up to six weeks have occasionally occurred.

Typically, gas gangrene manifests itself with the sudden appearance of increasing pain in the region of the wound. The *sudden* onset of pain, sometimes so sudden as to suggest a vascular catastrophe, always suggests the possibility of gas gangrene in a wounded person. Soon afterwards the limb becomes oedematous and is associated with drainage of thin serous or serosanguinous exudate, which may become gelatinous. The pulse rate rises markedly but the patient's temperature is rarely higher than 38° C. As classically described, clinical deterioration takes place quickly and within several hours the patient becomes anxious and frightened, or may even be euphoric, and exhibits all the signs of severe sepsis.

The skin is tense, pale, often marbled with blue, and rather colder than normal. In untreated cases, local bronzing of the skin becomes more diffuse, greenish yellow areas appear in which blebs may form and become filled with dark red fluid, and patches of cutaneous gangrene may occur. The skin *may*, however, appear normal, even when lying over massive gangrene.



R. Coupland / ICRC

Figure 13.1.1

Gas gangrene of the leg following the application of a tourniquet.



J. Goosen / South African Military Health Service, U. Witwatersrand

Figure 13.1.2

Gas gangrene of the arm.

Rapidly, swelling oedema and toxaemia increase, the serous discharge becomes more profuse and a peculiar sweetish smell may be present. The smell is variable and not pathognomonic.

Gas is usually produced at this stage and is partly responsible for the swelling of the affected part (Figure 13.2). It is produced in and between the muscle fibres, follows the fascial planes, and eventually escapes into the subcutaneous tissues under pressure through holes in the fascia, spreading rapidly beyond the confines of the infected area. Crepitus may be felt under the skin if the part is palpated. The extent of the spread of gas is not equivalent to the extent of muscle necrosis.

Infection spreads up and down the muscle from the site of the wound but has little tendency to spread to other healthy muscles; the bacteria is a *strict anaerobe*. Even in well-established gas gangrene, the bloodstream is rarely invaded by Clostridia until immediately before death.

The muscle changes are usually only seen at operation. In the early stages, they consist of little more than swelling and pallor. Later, the colour alters to a lustreless pinkish-grey, then to brick red, and finally to a dark green-purple colour.



E. Dykes / ICRC

Figure 13.2

X-ray showing gas collections between muscle groups.

Management

All patients with missile wounds should receive prophylactic antibiotics that are effective against Clostridia, such as penicillin, metronidazole, or erythromycin. But the antibiotics can only reach tissues with a blood supply and good tissue perfusion. Antibiotic concentrations in the dead muscle in the depths of an anaerobic environment are ineffective. Surgery as early as possible is the goal to be attained.

The basis of management of established gas gangrene is *thorough* excision of dead tissue, which might necessitate *urgent amputation*. The limit of excision is *necrotic muscle*, not the extent of tissues containing gas. Tissues must be cut away until healthy red, bleeding, and contracting aerobic muscle is reached.

Immediate surgical intervention is essential in the management of gas gangrene.

It is often too late for surgery when a patient presents with full-blown gas gangrene because of the severe toxaemia. Nonetheless, supportive measures including oxygen, fluids, and fresh whole blood should be instituted. Appropriate antibiotics should be continued.

13.3.3 Tetanus

Tetanus is always a risk with any penetrating wound. The risk is greater for severely contaminated wounds, especially in small, deep, punctuate-type ones. Pyogenic infection in the depth of a narrow track can create the necessary anaerobic environment. The incubation period is 3 to 21 days, but can be as short as 1 day to as long as several months.


E. Dykes / ICRC

Figure 13.3
Badly infected wound giving rise to tetanus.

Virtually total protection can be obtained by active immunization with a full course of tetanus toxoid injections.


Å. Molde / ICRC

Figure 13.4
Risus sardonicus in a patient suffering from tetanus.

Clostridium tetani is a strict anaerobe. The organism produces an extremely potent toxin called tetanospasmin that spreads along peripheral nerves to the spinal cord and brainstem. The toxin affects the motor end-plate by inhibiting cholinesterase, resulting in a build-up of acetylcholine and tonic muscle spam. There is, in addition, hyperexcitability of lower motor-neurones causing muscular rigidity and dysfunction of activity in antagonistic muscles that cause unopposed reflex activity, giving rise to the typical spastic phenomena of tetanus. Early signs are neck rigidity and *trismus* (stiffness of the jaw) with difficulty in swallowing, followed by *risus sardonicus* (grimacing smile). Profound autonomic nervous system dysfunction is also present in severe cases with unstable pulse rate, blood pressure, and temperature, which are difficult to treat. Once the toxin is fixed to the nerves, antitoxin can not longer neutralize it.

The infection may affect a single muscle group or be more generalized. Three clinical degrees are described:
- mild = no generalized spasms;
- moderate = generalized spasms on provocation;
- severe = spontaneous generalized spasms with opisthotonus.

The muscular spasms are quite painful, and can last a short time or go on for several weeks. The greatest danger is asphyxiation due to laryngeal spasm or aspiration. Frequently, there is a high temperature with profuse sweating that requires careful fluid replacement. The patient remains conscious throughout.

Prophylaxis
The best precaution against tetanus is active immunization. However, many patients in developing countries where conflict has further disrupted public health programmes are not immunized and therefore the risk of tetanus in war wounds is great. In some countries, ICRC practice is to proceed with active and passive immunization for *all* patients.

Early and adequate excision of dead tissue, and leaving wounds open, is vital to prevent its development. This is particularly important in small, deep, punctuate-like wounds. Penicillin and metronidazole are the drugs of choice.

Tetanus prophylaxis for war wounds

All patients whatever their immunization status:

1. tetanus toxoid vaccine 0.5 ml i.m. (5 LF units) – this is a booster dose in a previously vaccinated patient;
2. penicillin;
3. thorough excision of the wound.

Non-immunized patients or those in whom immunization status is in doubt, addition of:

4. human tetanus immunoglobulin 500 IU i.m. (adults) or 250 IU (children under 15 years of age) – also known as human anti-tetanus serum;
5. tetanus toxoid 0.5 ml i.m. to be repeated at four weeks and again at six months.

Please note:

Vaccine and immunoglobulin should be administered through separate syringes and at separate sites.

Treatment of established tetanus
Treatment of established tetanus should follow the steps listed below.

1. Extensive debridement of the wound. Ketamine anaesthesia should be avoided if possible as patients waking from this form of anaesthesia are often restless and have hallucinations and this may stimulate spasms. Spinal anaesthesia or a regional nerve block are excellent methods.

2. Antibiotics: crystalline penicillin G (5 MIU. i.v. QID) and/or metronidazole (500 mg i.v. TID). Erythromycin, tetracycline and chloramphenicol are also active against Clostridia, in case of allergy to penicillin.

3. Anti-tetanus human immunoglobulin (3,000 – 10,000 IU): a single large dose is given intravenously and as soon as possible. The actual dose ordered is dependent on the severity of the disease and the age of the patient. It is diluted in 20ml of normal saline and given slowly over a period of 15 minutes. This can be given intramuscularly (undiluted) in the proximal part of the wounded limb if the type of immunoglobulin is not recommended for intravenous use. An intrathecal injection of 250 IU can be given e.g. with spinal anaesthesia for debridement of the lower part of the body.

   In some regions, human immunoglobulin is in short supply or not available at all. In these circumstances, one must rely on equine anti-tetanus serum. A test dose must be administered before giving the full dose (20 000 IU).

4. Control of the spasms: the patient should be nursed in an environment as devoid of stimulation as possible in a dark, quiet room. For severe cases, and in the best of circumstances, the patient should be in an intensive care unit, anaesthetized and paralysed, with mechanical ventilation. Many hospitals lack these facilities; control is based on sedation.

Intravenous diazepam, either intermittently or continuously, is used with doses up to 20 mg or more per hour depending on the duration and intensity of the spasms. If diazepam alone does not control the spasms, chlorpromazine may be added, or thiopental (pentothal) may be required. This latter is given preferably by continuous infusion, which has been found to control the spasms more effectively with lower total dosages than if given intermittently.

Warning!
Oversedation can be as fatal as the disease.

Recently, ICRC teams have used magnesium sulphate in high doses (40 mg/kg over 30 minutes, followed by i.v. infusion of 1 – 3 g/hour) with encouraging results. This regime allows lower doses of diazepam and thiopental to be used, thus avoiding oversedation: this line of treatment is still under investigation.[5]

5. Airway management is of the utmost importance to prevent aspiration. If laryngospasms persist tracheostomy may be needed, and the decision to perform one should be taken early. Care of the tracheostomy tube is instituted with particular attention to how much this stimulates spasms, and adapting the sedation accordingly. Chest physiotherapy is required to prevent respiratory complications.
6. Fluid replacement: there may be excessive fluid loss due to sweating – this needs to be carefully monitored along with urinary output. A Foley urinary catheter should be placed.
7. Nutrition: if the spasms continue for some days, a feeding gastrostomy or jejunostomy may be required as a nasogastric tube may provoke spasms and become obstructed. Again, it is important to decide to perform this procedure early. These patients require a high calorie diet.
8. Excellent nursing care is fundamental. The patient's position must be changed four-hourly. Extra sedation may be required prior to this, as movement can provoke spasms. Patient hygiene – skin, oral and bowels – is essential.

Please note:

Clinical tetanus does *not* confer normal immunity. The patient therefore needs to complete immunization after recovering from the disease.

13.3.4 Invasive streptococcal infection

Beta-haemolytic streptococcus produces powerful toxins that trigger off a rapid progression of disease from local to systemic infection. It begins with a local cellulitis with severe pain out of proportion with physical findings, and advances rapidly to fever, tachycardia, disorientation and delirium. The wound is malodorous with large quantities of thin, blood-stained seropurulent discharge. The muscles suffer from a moist oedema, and turn from pale, to bright red, then dark purple-brown. Progression can occur in a matter of hours. It is still seen in mismanaged wounds, and especially if there is a delay in treatment.

Wound debridement, drainage, and massive doses of penicillin are the basis of management, along with supportive measures. Blood transfusion is usually necessary.



ICRC

Figure 13.5
Invasive β-haemolytic streptococcus infection of the abdominal wall.

---

[5] Thwaites CL, Yen LM, Loan HT, Thuy TTD, Thwaites GE, Stepniewska K, Soni N, White NJ, Farrar JJ. Magnesium sulphate for treatment of severe tetanus: a randomised controlled trial. *Lancet* 2006; **368**: 1436 – 1443.

13.3.5 Necrotizing soft-tissue infections

Various non-clostridial spreading gangrenous infections have been described in the surgical literature: necrotizing fasciitis, synergistic gangrene, anaerobic cellulitis, etc. There is necrosis of the skin, subcutaneous tissues and fascia, but not of the muscles. It can rapidly progress to systemic toxicity and even death. Spreading gangrene can follow trauma or thoracic and abdominal surgery (postoperative synergistic gangrene), and affect persons suffering from a general disease, such as diabetes, or malnutrition; alcoholics are particularly at risk. Infection usually affects the torso, perineum or extremities. The bacterial flora is mixed causing synergy amongst various organisms, anaerobic and aerobic, particularly microaerophilic nonhaemolytic streptococci in association with haemolytic staphylococci.

In no case are healthy muscles involved, and the clinical picture is less dramatic than in gas gangrene. Nonetheless, the systemic toxicity is life-threatening. There is severe pain disproportionate to local findings, crepitus can often be felt and soft-tissue air is present on plain X-rays. The skin is discoloured (blue, purple or black) with blistering leading to haemorrhagic bullae and induration. The necrosis can spread widely causing a large soft tissue defect. The diagnosis is primarily a clinical one, and the earlier treatment is instituted the better the result.


H. Nasreddine / ICRC


H. Nasreddine / ICRC

Figure 13.6.1 and 13.6.2

Necrotizing fasciitis with large skin loss and tissue defect.

Management includes:
- aggressive excision of necrotic tissue and the relief of tension, which may require serial debridements – amputation may be necessary in cases of necrotizing infections of the limbs – and defunctioning colostomy in cases of infection of the perineum with faecal contamination;
- leaving the wound open for drainage;
- triple intravenous antibiotics: penicillin, gentamycin and metronidazole;
- fluid resuscitation, blood transfusion and other supportive treatment.

Reconstructive surgery to cover the defect should only be considered once the patient's condition has stabilized and the infection is fully eradicated.

13.4 Antibiotics

It is important to distinguish between the prophylactic use of antibiotics and their role in the therapy of established sepsis. The surgeon must also remember the life history of wounds and their changing bacterial flora.

Prophylaxis is aimed at preventing a specific infection. It is impossible to find any reasonable cocktail of antibiotics that would be effective against the entire "polymicrobial cesspool" that can contaminate a war wound. Nor is it desirable to do so. Such a practice would constitute a simple abuse of antibiotics and contribute to the development of bacterial resistance.

Old lessons for new surgeons

The best antibiotic is good surgery.

The surgeon must realize that trust in the efficiency of antibiotics will never replace good surgery. Good surgery involves good diagnosis, good clinical decision-making, and good holistic management of the patient. Sometimes "good surgery" means knowing when *not* to operate. As we have seen, uncomplicated Grade 1 wounds and many civilian gunshot wounds can be treated conservatively and expectantly.

War wounds, however, are usually understood to be different from civilian weapon trauma; not always because of the weapon, but because of the environment. The battlefield is a dirty and contaminated place and the danger of invasive infection is always present, even in minor wounds; mass casualties cannot always be followed up correctly; there is often a long delay between injury and treatment; proper hygiene and nutrition cannot always be maintained; and immunization is not always universal.

Under such circumstances, the basis of prevention of primary infection remains complete wound excision and good drainage, respect in the handling of the tissues, and leaving the wound open for delayed primary closure. Antibiotics are only an *adjunct* to good surgical practice, and cannot replace poor surgery.

A case can be made for prophylaxis against the second series of infections, those acquired from the flora of the patient (skin, respiratory and gastrointestinal tracts) if the occurrence of such infections becomes an important clinical problem in the functioning of a given hospital, and is proven by proper bacteriological studies. Infections caused by bacteria with multiple antibiotic resistance and by opportunistic organisms, such as *Pseudomonas aeruginosa*, have become more prevalent with the uncontrolled use of wide-spectrum antibiotics. Again, good surgery and proper hygiene measures and environmental control cannot be replaced by antibiotics, and their use should be regarded as an adjunct only.

The prevention of nosocomial infection is another story. Proper clinical procedures and hygiene are the correct means of prevention: frequent hand washing; no unnecessary change of dressings on the ward; isolation of infected patients; adequate sterilization; proper cleaning of the hospital premises, etc. These alone can and will stop nosocomial infection. The use of antibiotics to *supplement* such measures will depend on the *virulence* of the particular bacteria involved.

A well-functioning bacteriology laboratory is important if antibiotic use is to be anything more than a “shotgun” approach or an “educated guess”. Wound cultures are notorious for not predicting subsequent infections or infecting pathogens. In the absence of correct collection of specimens, aerobic and anaerobic, and proper bacterial culture and sensitivity techniques, an educated guess is the best that can be hoped for in most cases. Accurate bacteriological capability is a far more difficult endeavour in a forward hospital than most people realize.

13.4.1 Antibiotic prophylaxis in the primary treatment of war wounds

Antibiotics do not reach the source of infection in a missile wound – i.e. the culture medium of dead tissue, debris and foreign material – they only affect the contusion and concussion zones around the wound. However, early administration of antibiotics seems to inhibit bacterial growth and delay invasive infection. Antibiotics especially help prevent spread to the blood stream. The benefit of antibiotics to prevent invasive infections in wounds that received no other treatment for hours to days after injury has been demonstrated,[6] and ICRC clinical experience confirms this. The ICRC recommends that penicillin treatment be begun in the pre-hospital setting if at all possible.

As mentioned, historically, the biggest killers of surviving war-wounded casualties have been primary infection by β-haemolytic streptococcus and Clostridia. This is a relatively narrow spectrum of bacteria, for which penicillin remains the best antibiotic.

Prophylaxis for war wounds can only be assured for Clostridia and β-haemolytic streptococcus: penicillin is the drug of choice.

---

[6] Mellor SG, Cooper GJ, Bowyer GW. Efficacy of delayed administration of benzylpenicillin in the control of infection in penetrating soft-tissue injuries in war. *J Trauma* 1996; **40 (3 Suppl.)**: S128 – S134.

Single-dose or the administration of prophylactic antibiotics limited to 24 hours are indicated under optimal conditions of rapid evacuation, early pre-hospital first aid, and adequate infrastructural hygiene. In the ICRC context of limited resources, often less than ideal environmental control, and delayed evacuation, antibiotics are usually given for 5 days, until delayed primary closure. This period of 5 days may be regarded as an exaggeration by some colleagues, but is considered a reasonable combination of a prophylactic *and* therapeutic regime by ICRC practitioners and has proved its worth in clinical experience (see Annex 13. A: ICRC antibiotic protocol).

Topical antibiotics and the washing of wounds with antibiotic solutions are not recommended.

13.4.2 Cephalosporins and others

The ICRC does not routinely use cephalosporins or other sophisticated antibiotics in a surgical setting. In many areas where the ICRC works, typhoid fever and shigellosis, amongst other infections, are endemic diseases. Resistance to first-line antibiotics for these fatal diseases is becoming more and more of a problem in clinical practice. Often, cephalosporins are the only recourse left available. The judicious use of antibiotics is an important element to keep in mind when dealing with the surgery of the victims of war, where proper surgical, nursing, and hygiene measures should be the basis of prevention and treatment of infection.

13.5 Neglected or mismanaged wounds

The particular, although commonly encountered, condition of neglected or mismanaged wounds has been dealt with in Chapter 12. As mentioned above, these wounds are particularly at risk of developing gas gangrene, tetanus, and deeply invasive sepsis. According to the ICRC antibiotic protocol, penicillin and metronidazole should be administered; if there are systemic signs of pyogenic infection, gentamycin is added.

Antibiotics are important in the treatment of these diseases, but do not replace the essentials of septic surgery: wide excision, good drainage, copious lavage, and leaving the wound wide open.

ANNEX 13. A ICRC Antibiotic protocol

Injury	Antibiotic	Remarks
Minor soft-tissue wounds, uncomplicated Grade 1	Penicillin-V tablets 500 mg QID for five days	Anti-tetanus measures for all weapon - injured patients
Compound fractures Traumatic amputations Major soft-tissue wounds (Grades 2 and 3)	Penicillin-G 5 MIU i.v. QID for 48 hours Follow with penicillin-V tablets 500 mg QID until DPC	Continue penicillin-V for five days if closure is performed with a split skin graft If redebridement is performed instead of DPC: stop antibiotic unless there are signs of systemic infection or active local inflammation – in latter case, add (metronidazole 500 mg i.v. TID) and gentamycin 80 mg i.v. TID
Compound fractures or major soft-tissue wounds with delay of more than 72 hours Anti-personnel landmine injuries to limbs whatever the delay	Penicillin-G 5 MIU i.v. QID and metronidazole 500 mg i.v. TID for 48 hours Follow with penicillin-V tablets 500 mg QID and metronidazole tablets 500 mg TID until DPC	
Haemothorax	Ampicillin 1 gm i.v. QID for 48 hours, followed by amoxycillin tablets 500 mg QID	Continue until two days after removal of the chest tube
Penetrating cranio-cerebral wounds	Penicillin-G 5 MIU i.v. QID and chloramphenicol 1 gm i.v. TID for at least 72 hours	Continue i.v. or orally according to patient's condition for a total of 10 days
Brain abscess	Same regime as for penetrating cranio-cerebral wounds plus metronidazole 500 mg i.v. TID	Continue i.v. or orally according to patient's condition for total of 10 days
Penetrating eye injuries	Penicillin-G 5 MIU i.v. QID and chloramphenicol 1 gm i.v. TID for 48 hours	Continue i.v. or orally according to patient's condition for total of 10 days Local instillation of antibiotic eye-drops
Maxillo-facial wounds	Ampicillin 1 gm i.v. QID and metronidazole 500 mg i.v. TID for 48 hours	Continue i.v. or orally according to patient's condition for total of 5 days
Abdominal wounds:		Continue for 3 days depending on drainage
1. solid organs only: liver, spleen, kidney; or isolated bladder injury	Penicillin-G 5 MIU i.v. QID	
2. stomach, small intestines	Ampicillin 1 gm i.v. QID and metronidazole 500 mg i.v. TID	
3. colon, rectum, anus	Ampicillin 1 gm i.v. QID and metronidazole 500 mg i.v. TID and gentamycin 80 mg i.v. TID	

MIU = million international units.

QID = quater in die (4 x day).

TID = ter in die (3 x day).

Please note:

This protocol was established by the ICRC Master Surgeons Workshop held in Geneva in 2002 (see Introduction).

That instrument is our intuitive power, which has its roots in our body as earth. It cannot be substituted by any other instrument, including our own intellect through which we are often at risk to become strangers to our own innate wisdom.

Genuine self-transformation can only be realized from within by the one who truly knows her/his personal existential history. We must see the relations between positive and negative emotions as our own most intimate history which we have often hidden from our own senses and which only reveals itself to our own compassionate inner eye and our own loving energy. Only then can we open the path to true healing from within. No medical system, medical doctor, psychologist, psychotherapist or other professional can do what you yourself can do: to observe and understand yourself emotionally and feel what your innermost self needs and longs for.

As such the Fusion Practices are a primary practice to reconnect with the somatic basis of our being and reconnect with the hidden parts of ourselves. Thus the Fusion Practices are exercises in in kinesthetic awareness through which we recover our primary form of knowledge which is somatic and is buried in our very body and our gut. For this we need to go deep down into our own emotional history and learn to feel with and within our entire body.

For this we need to let our rationalizing mind deeply sink into our body and let our intuition take over so that we get in touch with the visceral level of our being. Thus the Fusion Practices are not mental or intellectual exercises to clear our debris or accumulate virtues but an existential transformational exercise to which the formal mind only becomes an impediment.

The Fusion Practices provide a unique way to overcome the dependencies you have grown accustomed to and to train yourself in self-reliance and recover your independence and thereby your self-esteem.

Chapter 14

RETAINED BULLETS AND FRAGMENTS

14. RETAINED BULLETS AND FRAGMENTS

14.1 The surgeon and the foreign body 271

14.2 Early indications for removal 271

14.3 Late indications 274

14.4 Technique for the removal of a projectile 275

14.1 The surgeon and the foreign body

There are hundreds of thousands of perfectly healthy people walking around the present and past war zones of the world who have retained projectiles in their body. These metallic foreign bodies often catch the attention of patients and relatives, who impute to them any pains and disabilities they suffer from and insist upon their removal, even after the wound has completely healed.

It can be very difficult, and frustrating, for the surgeon to point out to an insistent patient that a projectile is dangerous when moving but is no longer so when it has come to a stop. The incidence of late infection is low (2 – 3%)[1] and vascular embolization rare and more common with fragments than bullets. The risk of embolization – "migrating bullet" – is more common in published clinical cases in the specialized surgical literature than it is in real life. One American study from Viet Nam reported a rate of 0.3% in 7,500 cases with arterial injuries; and rarer still in the overall wound population.[2]

The frustration is directly related to the number of patients presenting with such requests, who can at times be counted literally in the hundreds. The problem tends to be psychological and cultural rather than surgical. How can one convince a young combatant that the operation to remove a bullet may cause more damage than the bullet has accomplished? Such a foreign body in the midst of a muscle mass, where there are no pain receptors, is not painful and the surgeon must find a way to overcome the patient's subjective fixation; perhaps by making the bullet's presence a matter of "pride".

The experience of the ICRC shows that many of these operations to remove a projectile are risky, useless, consume time and materials, and result in new surgical trauma with its possible complications, often without identification and removal of the foreign body. There are few surgical endeavours more frustrating for an unprepared young surgeon than to spend two hours searching ever more frantically for an "easy" fragment or bullet, and finally not finding it.

14.2 Early indications for removal

However, as stated previously, there are indications for removal of bullets and fragments, which may be divided into early and late. The most important early indications have been dealt with in Chapter 10: as an integral part of the primary operation or to address the possibility of erosion of an important structure (Figures 10.11, 10.12 and 14.1).

As mentioned in the latter case, whether the removal is an immediate or planned procedure will depend on a number of factors, especially the experience of the surgeon and the possible morbidity and lethality of the operation itself compared to the relatively low incidence of serious complications. The decision is not always a simple one and the reader may consider what should be done in the following examples (Figures 14.2 – 14.8).



M. Baldan / ICRC

Figures 14.1.1 and 14.1.2

Bullet lodged in full-term pregnant uterus.



M. Baldan / ICRC

---

[1] Rhee JM, Marin R. The management of retained bullets in the limbs. *Injury* 1997; **28**: 23 – 38.

[2] Rich NM, Collins GJ, Andersen CA, McDonald PT, Kozloff L, Ricotta JJ. Missile emboli. *J Trauma* 1978: **18**: 236 – 239.


M. Baldan / ICRC

M. Baldan / ICRC

Figures 14.2.1 and 14.2.2

A fragment entered the forehead and is retained in the occipital region.


ICRC

ICRC

ICRC

Figures 14.3.1 – 14.3.3

A fragment has entered the parieto-occipital area.


ICRC

Figures 14.3.4

The fragment is evident under the bone.

R. Coupland / ICRC

Figure 14.4.1

Nurse pointing out site of fragment entry.


R. Coupland / ICRC

Figure 14.4.2

Radiograph showing a fragment retained in the neck.


M. Baldan / ICRC

Figure 14.5

Bullet in the axilla: the vessels and nerves are intact.


M. Baldan / ICRC

Figure 14.6

Fractured humerus with bullet retained in the subscapular muscles.


M. Baldan / ICRC

M. Baldan / ICRC

Figures 14.7.1 and 14.7.2

Extra-synovial bullet near the hip.


F. Herkert / ICRC

Figure 14.8

Fragmented bullet in extraperitoneal muscle mass.



F. Irmay / ICRC

F. Irmay / ICRC

Figures 14.9.1 and 14.9.2

Bullet retained in vertebral column, the patient is paraplegic.



ICRC

Figure 14.10

Metallic fragment located in a pressure point: sole of the foot.

The following scenarios should be added to the early indications already mentioned.

- A small fragment in a heart chamber – the concomitant pericardial tamponade is an urgent condition, the removal of a retained fragment is not – or a fragment obviously within the lumen of an important vessel. The possibility, and danger, of embolization is high in these particular instances. Operation should *only* be undertaken, however, if the surgeon *and* anaesthetist are experienced and the necessary diagnostic and operative equipment are available.
- A projectile located in the spinal cord: emergency laminectomy and removal should be considered *only* if there is clear progressive neurological deficit and radiological evidence of spinal cord compression by the foreign body *and* the surgeon is experienced in this field. A definitive diagnosis of paraplegia, indicating that the spinal cord is irrecoverably sectioned, means that it is already too late.
- Small metallic fragment penetrating the eye: removal is indicated if located in the anterior chamber, again, *only* if the surgeon is experienced, *and* magnification, proper instruments and suture material are available.

14.3 Late indications

Late indications are largely the result of the complications listed below.

Sepsis

If the projectile, along with surrounding contaminants, is acting as a nidus for infection: an abscess or sinus. The removal is performed as a planned operation after the necessary diagnostic procedures (X-ray, sinugram, etc.).

Pain

If located superficially, especially if over a pressure point (palm of hands, sole of foot, elbow, etc.), the projectile will cause true pain. The removal may be performed as an elective procedure after healing from the acute trauma.

Pain

If the foreign body is impinging on a nerve and causing radicular pain or paraesthesia. As above, the removal is performed as a planned operation.



ICRC

Figure 14.11.1

Bullet in antero-lateral compartment of the leg pressing on common peroneal nerve.



ICRC

Figure 14.11.2

Bullet not pressing on a nerve.

Lead toxicity

This is extremely rare, usually involves a synovial joint or intervertebral disc, and surgery should be contemplated only if there is documented elevation of serum lead level (above 10 micrograms/dl in children and 40 micrograms/dl in adults). The response to an EDTA (ethylene diamine tetra-acetic acid) challenge is a useful diagnostic test. Standard chelation therapy is instituted (EDTA, dimecaprol, d-penicillamine, succimer) and the surgical removal of the metal should not be performed before serum lead levels have been reduced to avoid acute lead poisoning.[3] This complication does not arise with an intact, full metal jacket bullet where no lead filling has spilled out.

We shall not deal with wounds not related to armed conflict where the bullet may be required as part of a legal and forensic investigation. National law of the country concerned determines what exactly can be done while not subjecting the patient to unnecessary harm and suffering.

14.4 Technique for the removal of a projectile

For those patients requiring removal of a deeply-seated metallic fragment or bullet, proper localization prior to surgery is of the utmost importance. Most rural or provincial hospitals do not have fluoroscopy or an image-intensifier in the operating theatre enabling the surgeon to operate under direct vision.

A simple stereotactic technique to assist localization involves taping a series of radio-opaque objects (paper clips, injection needles, Kirschner wires) to the body part, both anterior and lateral surfaces, to act as guides. Plain X-rays with antero-posterior and lateral views are taken. The radio-opaque object is then removed and its position on the skin marked with a felt pen.

By looking at the two X-ray views, the surgeon can estimate the relative distance of the bullet from the radio-opaque objects in the axes both across and in the depth of the body part – e.g. half-way between the second and third paper clips in the A-P view and one-third of the way between the first and second paper clips in the lateral view. The idea is to use two-dimensional X-rays to extrapolate into three dimensions. The films should be taken on the morning of the operation and the patient should be undressed (combatants often carry bullets in their pockets).



Figure 14.12.1 and 14.12.2

Stereotactic localization of metallic foreign body. Safety-pin is anterior and paper clip lateral.

In due course, the body will form tough avascular scar tissue around the metallic fragment: a foreign body granuloma. This includes other foreign matter and dirt, and should be excised together with the projectile.

---

[3] Linden MA, Manton WI, Stewart RM, Thal ER, Feit H. Lead poisoning from retained bullets: Pathogenesis, diagnosis, and management. *Ann Surgery* 1982; **195**: 305 – 313.

Healing Wounds

Often the question is asked: “Where to begin”? Such questions may suggest a hesitation to enter the practice and face oneself. A path opens at the very moment we start to walk. The inner journey is different for all of us, as our histories are unique. The formulas provide an essential guide, which tells us how to go about, which direction to take, when to walk, when to rest and the stations (practices and their sequences) we should visit.

As suggested earlier, the whole Taoist practice has its beginning in the practice of the Inner Smile. The Inner Smile as the key to refresh, create, transform, attract and blend energies presupposes a basic willingness to enter into an adventure and to face the risks in transforming old to new. It requires above all a willingness to love oneself and self-compassion. Such an inner movement towards the opening of the heart is however only possible if there is some willingness to accept and forgive oneself.

Perhaps the primary key to any process of self-transformation is the willingness to forgive oneself, as it opens the heart and sets in motion and frees the flow of Chi, both from within and from outside. That would seem a primary condition for an open space to emerge in which one can enter into dialogue with the organs and let them speak and listen to what they wish to say.

Yet forgiveness is not an act for once and for all but a primary key in a continuous process of turning inward and practicing inner observation. It is not surprising that when Jesus was asked a question on forgiveness, he pointed to its key role by saying that a man should forgive seventy times seven, meaning that it has no limit. Rather than perceiving forgiveness as a virtue which make all other virtues possible, like love and compassion, it is more useful to see it in terms of a growth generated by process towards balance as a whole between positive and negative emotions (Fusion of the Five Elements) and as the fruit of the creative cycle (Cosmic Fusion).

The refusal or inability to forgive and thereby to love oneself and others may be said to affect all the organs, affecting their chemistry and inhibiting cooperation and balance. Frequently it is rooted in a victim consciousness, which sets into motion negative emotions which tend to reinforce each other. This victim consciousness often has its roots in a presumption of betrayal as a result of which the heart closes, as others are made accountable for one’s own negativity and suffering.

Chapter 15

BURN INJURIES

15. BURN INJURIES

15.1 Introduction 279

15.2 Pathology 279
15.2.1 Burn depth 279
15.2.2 Pathophysiological changes 280
15.2.3 Types of burns 281
15.2.4 Extent of burns 281

15.3 Burn management 282
15.3.1 First aid 282
15.3.2 Resuscitation 282
15.3.3 Initial fluid replacement therapy 284
15.3.4 Monitoring resuscitation 285
15.3.5 After 48 hours 285

15.4 Burns presenting late 286

15.5 Nutrition 286

15.6 Care of the burn wound 286
15.6.1 Initial wound management 287
15.6.2 Local care 288

15.7 Closure of the burn wound 289
15.7.1 Mechanical cleansing and debridement 290
15.7.2 Surgery 290

15.8 Scar management 293

15.9 Electrical burns 294

15.10 Chemical burns 294
15.10.1 Acid and alkali burns 294
15.10.2 Phosphorus burns 294
15.10.3 Napalm injuries 295
15.10.4 Magnesium 296
15.10.5 Vesicant chemical weapons 296

ANNEX 15. A Nutrition in major burns: calculating nutritional requirements 297

15.1 Introduction

Burns are a common event in a war environment. Flame weapons, explosive blast and ignition of combustible materials all create burn hazards. The causal agent may be thermal, chemical, electrical, or linked to radiation. Each cause has specific consequences that may require specific assistance.

A serious burn injury is a painful and life-threatening event requiring an inordinate amount of hospital resources and nursing care. The most immediate threat to life is an impaired airway due to inhalation of hot air and smoke with consequent oedema; the most important subsequent threats to life are from hypovolaemic shock and infection, followed by the complex pathophysiological effects which continue after injury. It is associated with many complications, prolonged morbidity, multiple operations, and great demands on equipment, materials, medical and nursing time. The long-term sequelae, physical, cosmetic and psychological, deeply affect the morale of both patients and staff. Modern burn centres have made great progress in the successful treatment of major burns, but such facilities are never available in situations of limited resources.

Nevertheless, the principles of treatment are the same, and the aim is to do the best one possibly can under the austere circumstances, where stark reality imposes its frustrating limitations. Surgery will have the greatest impact on young people with small but potentially crippling injuries such as bilateral hand burns. Patients with burns covering 40 – 50% of the total body surface will rarely survive under field conditions and are best treated by giving sufficient fluids to relieve thirst, and generous amounts of analgesia. In a triage situation of mass casualties they are considered Category IV: i.e. given supportive treatment only.

15.2 Pathology

15.2.1 Burn depth

Burns involve varying amounts of injury to the skin, partial or full thickness, and classically correspond to three degrees of burn depth of increasing severity (Figure 15.1).

First degree burns:
First degree burns, or superficial burns, are painful, red, and have no blisters. They will heal on their own.

Second degree burns:
These may be superficial or deep partial-thickness burns. They are invariably blistered and the blister floor is usually pink or mottled red in appearance and the surface is moist. The less they blanch with pressure, the deeper they are. They are painful and have some sensation to pinprick. Hairs will be difficult to pluck out if the base of the follicle is alive. Most will eventually heal by a combination of re-epithelialization and wound contraction, but often with a seriously disabling scar contracture. Some will benefit from appropriate skin grafting.

Third degree burns:
These refer to full-thickness burns. Destruction of the full thickness of the skin gives a charred, leathery or waxy appearance. Any surviving hairs pull out easily. The burns are usually dry and have no sensation. Injury may extend to the muscles and deeper tissues. They are normally caused by flames, immersion in very hot liquids, electric current or chemicals. Smaller full-thickness burns will eventually heal by contraction but this inevitably causes severe deformity and loss of function. They are best treated by skin grafting.


First degree burn: superficial epidermis.
Second degree burn: superficial partial thickness.
Second degree burn: deep partial thickness.
Third degree burn: full thickness and may extend beyond the dermis.
ICRC

Figure 15.1

Histology of the skin and degree of burn depth.

Different regions of a burn wound have different depths of damage. A burn is basically an ischaemic three dimensional wound with:

- a zone of coagulation – a central area of irreversible skin death that creates the eschar;
- a zone of stasis – a middle layer of damaged but viable tissue with a significant inflammatory reaction, but an early stasis of local blood flow;
- a zone of hyperaemia – a deep and peripheral area that looks like cellulitis, but is only hyperaemic.

Appropriate fluid resuscitation preserves cells in the zone of stasis, but subsequent infection or drying of the wound can rapidly enlarge the injury, both peripherally and in depth.


E. Dykes / ICRC

Figure 15.2

Different regions of a burn wound have different depths of damage: central eschar of full-thickness burn surrounded by areas of partial-thickness burn.

Superficial burn wounds are painful; deep burns are anaesthetic.

15.2.2 Pathophysiological changes

The most important pathophysiological change from thermal injury is increase in capillary permeability, which, if resuscitation is successful, returns to normal within 24 – 48 hours. Plasma water and proteins up to a molecular weight of 350,000 are freely exchanged between the intra- and extravascular compartments of the extracellular space. A strongly negative interstitial fluid pressure develops that creates a strong "suction" in the burnt tissue. If the affected area is very large, these changes become widespread with the loss of important amounts of fluid from the vascular compartment.

This loss is most marked in the region of the burn wound and accounts for the local oedema, which peaks at 6 – 12 hours post-burn. However, with aggressive crystalloid resuscitation in large wounds (>25 – 30% of the total body surface area or TBSA), the hypoproteinaemia causes a systemic disorder resulting in *generalized oedema* of non-injured skin and internal tissues, above all swelling of the larynx, and resultant obstruction to the airway, and abdominal compartment syndrome.

For further details on abdominal compartment syndrome, see Volume 2.

There is an associated rapid rise in the haematocrit which, together with polymerization of some plasma proteins, causes a marked increase in blood viscosity. The immediate danger linked to the sequestration of fluids in the extravascular space is hypovolaemic shock and, with haemoconcentration, acute tubular necrosis and renal failure. The loss of skin cover, and its function as a regulator of temperature, means that hypothermia, with its complication of coagulopathy, is an ever-present danger (see Chapter 18).

15.2.3 Types of burns

Flame and scald burns are by far the most common. Flame burns are usually deep and appear so at presentation, whereas scald burns may appear much less severe at first; experienced burn surgeons usually withhold prognostication until they have inspected them on the third day. Contact flame burns are typically very deep at the centre, which should be taken into consideration if they are to be operated on.

Electrical burns fall into two distinct categories. Flash burns occur when a person causes a short circuit and resulting electrical flash, but no current travels through the body. These may be treated as regular thermal injuries. High voltage (>1,000 volts) electrical conduction injuries – the current travels through the body and is characterized by the "can't let go" phenomenon – are "iceberg injuries" as they usually present with small cutaneous wounds and severe deep-tissue damage.

Chemical burns are caused by particular agents: acids, alkalis, and specific compounds (napalm, phosphorus, vesicants, etc.), with their individual characteristics.

15.2.4 Extent of burns

The sequestration of large amounts of fluid and plasma proteins in the extravascular space is a function primarily of the extent of burnt tissues. It is thus important to estimate the total body surface area that has been burnt. The depth of the burn must also be taken into account; only second and third degree burns are included in the estimation of TBSA.

The simplest calculation is best done using the "Rule of Nines" (Figure 15.3). The size of the *patient's hand* (including palm and fingers) is about 1 % of TBSA.

The head and neck of a child under one year of age represent about 18 % and the lower extremity 14 % of TBSA (Figure 15.4). With age these figures gradually change to adult proportions.

Although it is difficult to grade the severity of burn wounds, the following provides a rule of thumb.

Minor:
- second degree less than 15 % TBSA;
- third degree less than 3 % TBSA.

Moderate:
- second degree 15 – 25 % TBSA;
- third degree less than 10 % TBSA.

Major:
- second degree more than 25 % TBSA;
- third degree more than 10 % TBSA.



P. Zylstra / ICRC

Figure 15.3

"Homunculus" diagram showing the "Rule of Nines" to assess burnt surface area in an adult.



P. Zylstra / ICRC

Figure 15.4

Assessment of burnt surface area in a child "homunculus".

15.3 Burn management

The management of burns follows a series of standard measures as with any wound or trauma.

1. First aid.
2. Resuscitation:
   - airway;
   - breathing;
   - circulation / fluid replacement therapy.
3. Analgesia.
4. Prophylactic antibiotics.
5. Tetanus prophylaxis.
6. Nutrition.
7. Hypothermia.
8. Wound management.

15.3.1 First aid

Rescuers should first ensure that the scene is safe and take suitable precautions if un-ignited fuel, explosives, electricity, or chemical agents are present. The patient should be removed to safety and clean fresh air, and the vital signs assessed. If available, oxygen should be provided if there is any indication of smoke inhalation.

The burn should then be cooled with water or wet towels (for 20 minutes), and covered to reduce pain. The patient should not, however, be left wrapped in cold wet material so long as to provoke hypothermia. After cooling the *burn*, keep the *patient* warm.

If evacuation to the hospital is delayed and the airway is not at risk, the patient should be encouraged to drink plenty of small quantities of fluids often and regularly, and the colour and volume of the urine monitored.

15.3.2 Resuscitation

The following elements should be determined:
- nature of the causal agent – flame, scald, contact, electrical conduction, electrical flash, chemical;
- possible aggravating factors – additional trauma, smoke inhalation (fire in an enclosed space equals smoke inhalation);
- time since injury – fluid resuscitation is calculated from the *time of burn*, not the time the patient arrives at hospital.

As with all injured persons, examination begins with the ABCDE sequence. Deep burns to the face, neck or anterior chest cause laryngeal oedema, which increases dramatically with fluid resuscitation. Inhalation of smoke, hot gases or chemical products contributes to this swelling. However, critical laryngeal oedema can occur in *any* deep burn to this important area. The patient should be checked for burnt hair in the nostrils or soot in the nose, mouth or sputum.

The airway must be secured and kept open, preferably by tracheostomy. This should be performed *before* the airway is compromised since it will be very difficult once oedema has closed the airway and cutting through oedematous tissues can be bloody and complicated.

Please note:

Because of this oedema even the tracheostomy hole will disappear in the depths of the tissues. Rather than an ordinary tracheostomy tube, an endotracheal tube should be inserted in the tracheal opening.

True smoke inhalation induces carbon monoxide poisoning and a chemical pneumonitis related to the inhalation of hot toxic gasses. Carbon monoxide poisoning should be assumed in any person found unconscious at the scene of a fire, and is treated by administering as high a concentration of oxygen as possible for 6 hours.

Increased fluid requirements early in resuscitation suggest severe inhalation injury, which may not appear on a chest X-ray until the second or third day. Inhalation injuries increase the 24-hour fluid requirements by 1 – 2 ml per kg of body weight per percentage of TBSA (1 – 2ml/kg/%), about 50 % increase. Hypoxia and hypercapnoea despite maximal oxygen supplementation or ventilation are ominous signs. Serious cases of smoke inhalation will not usually survive without mechanical ventilation. This can be difficult to organize in a setting offering limited resources.

The sequestration of large amounts of fluid and plasma proteins in the extravascular space produces hypovolaemic shock.

Please note:

Only second and third degree burns should be included in the estimation of the percentage of TBSA. Therefore, the patient must be completely exposed and the extent and depth of the burn carefully estimated using the "Rule of Nines". The patient should be weighed and the "homunculus" diagram used to assess and mark the extent of the injury. Particular attention should be paid to circumferential burns which may require escharotomy.

The natural tendency is to *overestimate the extent* of the burn. In controlled series this has been shown to be up to 25 %. A good idea is to first calculate the burnt area and then the area which is not burnt; the total should add up to 100 %. Another natural tendency is to *underestimate the depth* of the burn; periodic re-examination will help to determine this better.

Patients with burns of moderate and major severity should get a Foley catheter placed in the bladder to monitor the hourly urine volume, which is the most important single measurement for adequacy of resuscitation. A nasogastric tube should also be passed and, if there is no acute gastric dilatation, enteral feeds can be started within the first 24 hours. Early feeding through the nasogastric tube and appropriate acid suppression (antacids, H2 blockers) prevent acute haemorrhagic gastritis, which is usually fatal. Where maintaining an i.v. line is difficult, fluid resuscitation may be administered via the nasogastric tube or even orally in smaller burns. This may be particularly useful in small children.

Adequate analgesia (intravenous narcotic) is necessary at all stages of burn management. ICRC practice is to give penicillin for the first five days to prevent invasive haemolytic streptococcal infection; any other infection is treated ad hoc. Tetanus prophylaxis must be instituted as required. Other associated injuries (penetrating wounds, fractures, etc.) must be diagnosed and treated in parallel with the burn wound.

15.3.3 Initial fluid replacement therapy

Given adequate initial resuscitation with crystalloids, the *capillary integrity* is mostly restored within 18 – 24 hours following the burn. At this point, colloid can be given and will stay within the vascular compartment, increasing the plasma volume. Cardiac output will respond to fluid replacement long before blood and plasma volumes return to normal and a first, mild diuresis begins at about 12 hours after fluid therapy. Red cell life is reduced and although replacement of red cell mass is not necessary for the first 48 hours, for major burns blood transfusion will probably be necessary after this time.

Most minor burns presenting less than 15 % TBSA second degree damage do not require formal fluid resuscitation and can be treated with oral fluids, and patients can be managed on an outpatient basis. (Some surgeons prefer to hospitalize even a 3 % full-thickness burn, especially to the face, hands or feet.) Moderate and major burns require hospitalization and intravenous fluids. The ICRC uses the modified Brooke/Parkland formula[1] for fluid resuscitation.

There are three phases in resuscitation therapy.

1. First 24 hours following the infliction of the burn wound (not from the start of treatment).
2. Second 24 hours.
3. After 48 hours.

The first 24 hours

Ringer's lactate is the fluid of choice. Administration should be divided into three 8-hour periods.

Ringer's lactate solution 2 – 4 ml/kg/% burn = total volume for first 24 hours:

- first eight hours: one half the volume
- second eight hours: one quarter the volume
- third eight hours: one quarter the volume

Urine output should be 0.5 ml/kg/hour.

Fluid administration should start at the low end of the formula (2 ml/kg/%; for children start at 3 ml) and the hourly urine output monitored. There is a *non-linear* relationship in burn patients between the infusion rate and the urine flow. Normal urine flow is described as 0.5 – 1.5 ml/kg/hour. The *lower* limit should be aimed for, and any increase above this should call for a lowering of the infusion rate to avoid over-resuscitation.

Apparently, there is a natural "oedema-limiting mechanism" related to the amount of fluid that is easily mobilized from plasma into the burnt areas. Giving more fluid to maintain tissue perfusion and urine flow above this level may close down this mechanism and lead to more tissue fluid sequestration (tissue is a "fluid addict"[2]); giving even more intravenous fluid does not lead to improvement.

If the urinary output is low and does not respond to increased infusion in the second eight-hour period, the third eight-hour period Ringer's lactate should be replaced with colloid, plasma or 5 % albumin if available. If the vascular compartment is well-filled, however, but the patient is not making urine, the kidneys are likely to be failing and may respond to furosemide or mannitol.

---

[1] Brooke formula: 2 ml/kg/% TBSA for first 24 hours; Parkland formula: 4 ml/kg/% TBSA for first 24 hours.

[2] Sjöberg F. (Department of Anaesthesia and Intensive Care, University Hospital, Linköping, Sweden.) Monitoring of Resuscitation Adequacy. Proceedings of the International Society for Burn Injuries, 42nd World Congress of the International Society of Surgery; 2007 Aug 26 – 30; Montreal.

Other clinical vital signs must be closely watched, particularly the peripheral circulation, the patient's general condition, such as consciousness, restlessness, nausea or vomiting, and the haematocrit.

Constant monitoring is required and, after 12 hours, the patient's condition and fluid requirements should be reviewed and recalculated.

Please note:

Not only is there a natural tendency to overestimate the TBSA but, in much contemporary clinical practice, it has been discovered that over-resuscitation has become more common and more of a problem than under-resuscitation. The traditional fear of renal failure has led many clinicians to administer an excess of fluids. This has been called "fluid creep"[3] or "resuscitation morbidity" and manifests itself most commonly as pulmonary oedema and, later, abdominal compartment syndrome, delayed wound healing, increased susceptibility to infection, and multiple organ failure. It should be remembered that the fluid resuscitation formula is only a guideline, and actual amounts of i.v. fluids should be adapted accordingly.

The second 24 hours

During this phase, expansion of plasma volume can be achieved.

Plasma should be administered: 0.3 – 0.5 ml/kg/%/day.

If plasma is safe and *available*, theoretically it is best given at this stage. Albumin 5 % run at 50 ml/hour for 2 – 3 days is an expensive alternative, but the evidence to support either strategy is very slim. Otherwise, and in ICRC practice, Ringer's lactate should continue to be given at the rate of one-quarter of the first day's volume; intravenous fluid should be adjusted to urine output and enteral feeding increased as tolerated. This will provide not only essential nutrition but free water to cover evaporative losses from the burn wound.

15.3.4 Monitoring resuscitation

Clinical evaluation is particularly important in the absence of sophisticated means and laboratory measures. A clear sensorium, good tissue perfusion, good pulse, and an adequate urinary output are all signs of good progress. Less and less fluid is needed at the end of resuscitation in order to maintain urine volume. A flow sheet should be used to monitor vital signs and fluid input/output. The patient should be serially weighed if possible.

15.3.5 After 48 hours

Mobilization of burn wound oedema causes an expansion of the blood volume and results in massive diuresis, high cardiac output, tachycardia and anaemia. The better the fluid management in the first period – avoiding over-resuscitation – the less pronounced these clinical signs and the more stable the patient will be.

If available, plasma or albumin should be given to maintain serum albumin of 20 g/l and blood to maintain haemoglobin greater than 70 g/l. Deep burns cause greater anaemia. Fresh whole blood is best. Potassium, calcium, magnesium and phosphate are generally excreted in large amounts at this time, and should be supplemented where possible.

---

[3] Pruit BA Jr. Fluid and electrolyte replacement in the burned patient. *Surg Clin N Am* 1978; **48**: 1291 – 1312.

15.4 Burns presenting late

Often, patients with severe burns present late. Those presenting after a delay, but within the first 24 hours, should receive fluid resuscitation and an attempt should be made to infuse most of the calculated volume by the end of 24 hours from the time of burning.

Patients presenting after 24 hours will probably need some fluid but the amount should be guided primarily by clinical assessment of hydration and renal function. Patients who have survived the first 72 hours without renal failure have compensated the losses themselves (usually with oral fluids); they may require some rehydration but infection of the burn wound is the main concern. For those presenting weeks after the burn, infection is compounded by poor nutritional status, anaemia, and hypoproteinaemia. In these cases steps should be taken to control infection (debride grossly infected necrotic tissue) and to improve nutrition before any definitive surgery is undertaken. Early creation of a feeding gastrostomy should be considered.



E. Dykes / ICRC

Figure 15.5

Old flame burn to the leg.

15.5 Nutrition

Catabolism is particularly elevated in burn patients, especially those losing large amounts of protein through open wounds, and healing will require an important increase in caloric and protein intake for a lengthy period. Early enteral feeding is very important in maintaining gut function (reducing gastroparesis), and preventing complications. Major burn patients may require more than twice their normal protein and calorie intake until their wounds have closed. Nutritional requirements may be easily calculated for the individual patient (see Annex 15. A: Nutrition in major burns).

Blenderized enteral feeding solutions can readily be made from commonly available local foods and can be delivered by naso-gastric tube, gastrostomy or jejeunostomy. Especially when dealing with burn wounds that are weeks to months old, the patient's nutritional status should be evaluated and improved before any attempt is made at skin grafting or both the graft and the donor site risk delayed or failed healing.

15.6 Care of the burn wound

After successful resuscitation of the patient has been achieved, the next greatest threats to life that must be addressed are the burn wound itself and the complications of sepsis.

The aim of treatment is to achieve healing of the burn by the following measures.

1. Control of bacterial colonization by removal of all dead tissue.
2. Prevention of accumulation of purulent fluid and debris.
3. Prevention of secondary bacterial contamination.
4. Maintenance of an environment which promotes wound healing.
5. Avoidance of techniques or treatment which will damage the healing burn wound.

Most of the morbidity and mortality associated with major burns are the result of infection. All the methods for cleaning the wound, excising dead tissue and treating the burn are directed towards the control of "burn wound sepsis".

Untreated, eschar desiccates and sloughs off by means of bacterial enzymatic invasion of the plane between viable and non-viable tissue. Full-thickness burns will require skin grafting to heal properly; otherwise, healing will be by fibrous tissue contraction alone with chronic open wounds and disabling scar contracture.

As a result there is a refusal to even consider looking inward, as the source of misfortune is placed outward. Thus the heart's natural tendency towards love and compassion is obstructed and the wound is cultivated to legitimize one's withdrawal from life, as a result of which both the internal as well as the inward flow from outside are being impeded. All traumas first of all settle deeply in our organs from where they affect our energy flows. They can only be dissolved with patience and gentleness towards oneself. Only when internally energy is accumulating, can it flow outward.

The strengthening of the organs have in the Taoist tradition a vital role to play in mitigating and achieving control over the negative emotions. Forgiving does not mean that the wound needs to be closed. It may remain but it is no more active in generating toxins and preventing positive emotions from growing. Also forgiving does not means that one forgets. That may be too difficult and is not necessary. Only the charge, which activates to toxins needs to be defused.

The aim of the Fusion Practices also is not to eliminate pain. Pain and joy are intrinsic in life and form a unity of opposites. Attempts to eliminate it create frustration and exasperation and may well make it grow and become more difficult to control, as negative emotions such as fear, anger, worry, sadness and impatience multiply. The more negative emotions are suppressed, the more they have a tendency to run wild.

The purpose of the Fusion Practices is to achieve control and regulate them consciously so that major imbalances can be prevented and the quality of the energies, upon being fused and blended is heightened and transformations into new states of being (the energy body and the spirit body) become possible. Ups and downs are inevitable but as you grow able to accept them and balance them and grow in equanimity, a point is coming when you are less affected by what happens around you; you are less carried away by events and you become less vulnerable.

Rather than to do away with toxins, it is wiser to allow for them and it is easier to control them. This immunity is both raised in balancing positive and negative emotions (Fusion of the Five Elements) and by strengthening the positive emotions (Cosmic Fusion). The unity of the two is of great importance. To make a small tree grow one does not only weed, but also creates optimal conditions for it to grow: that it is planted in good soil, that it receives shade and water and that it is pruned at the right time.

In partial-thickness burns, viable areas of dermis underlie the necrotic tissue and if sufficient epidermal cells remain at the base of skin appendages, such as sweat glands and hair follicles, re-epithelialization will gradually take place if given the right conditions.

Infection will transform a partial-thickness burn into a complete-thickness one. Because of the complete or partial ischaemia associated with burn wounds, systemic antibiotics may not reach the site of bacterial colonization. Local treatment, both mechanical and antimicrobial, are the basic elements of wound care.

15.6.1 Initial wound management

Initial wound toilet should be undertaken after resuscitation has begun and proceed in parallel. Once the patient's condition has stabilized, attention can be turned to more *definitive* measures.

Any constricting agents (rings, wrist-watch, jewellery, etc.) should have been removed on admission. The patient should be sedated and the burn wound gently washed with soap and water. Freely running, clean water, without excess pressure but a regular flow and at a temperature comfortable for the patient, is best. This will cool the burn, decrease pain, and remove superficial debris and adherent clothing.

Small intact blisters may be left *undisturbed* but large, bloody, or pus-filled blisters, and those which interfere with joint movement, should be *unroofed and debrided*. Large burn wounds may be more easily cleaned by placing the patient in a shower. Baths should be avoided because of the attending logistical difficulties and the danger of cross-infection under field conditions. The routine daily immersion of burn patients in filthy tubs of cold water is to be condemned.

Particular attention should be paid to circumferential deep burns. During the first 48 hours the increasing oedema of the tissues and the thick unyielding burn eschar may result in a tourniquet effect. Circumferential burns of the chest will restrict breathing and those of the limbs will cause peripheral ischaemia which can lead to amputation. This disaster is easily averted.

Escharotomy is the process of incising the eschar down to the subcutaneous fat to allow relief of the constriction.

Escharotomy should be performed with a sharp knife or electric diathermy through the burnt skin into the subcutaneous fat.

Escharotomy incisions are placed in the mid-lateral and mid-medial lines of the affected extremity and should extend up to, but never include, unburnt skin. A "T-cut" at each end of the escharotomy allows tissue to expand without causing an acute constriction at the end of the incision. On the hands, the mid-lateral incisions coming down each side of the forearm should be swung onto the dorsum, and branched to make a single escharotomy incision down the mid-lateral line of each finger on its less-used side. (i.e. ulnar side of thumb, index and ring finger; radial side of middle and little finger).

A thoracic escharotomy begins at the midclavicular lines, continues along the anterior axillary folds down to the costal margin, and across the epigastrium to the xyphoid process.

Please note:

Few patients who truly need a thoracic escharotomy will survive without mechanical ventilation.


ICRC

Figure 15.6

Burn to the face with intact blisters.


M. King / Primary Surgery Volume 2

Figure 15.7.1

Sites for escharotomy incisions.


M. Beveridge / ICRC

Figure 15.7.2

Placing for escharotomy incisions on the hand.


M. Baldan / ICRC

Figure 15.7.3

Escharotomy incision of the arm.

Though full-thickness burns are usually anaesthetic, the escharotomy should be done with some form of anaesthesia as the edges can be very painful and the cut goes into the subcutaneous fat. Ketamine is ideal.

Particular attention should be paid to burns with underlying fractures or burns extending deep into the fascia; these can create a compartment syndrome. Formal fasciotomy, with excision of the aponeurosis, may be necessary in addition to escharotomy.

Severe perineal burns may necessitate faecal diversion.

15.6.2 Local care

Care of burn wounds involves an extraordinary amount of nursing care. The method used depends on the depth, extent, and location of the burn. ICRC surgical teams use occlusive dressings – and its plastic bag modification – and open therapy; both with a topical antibacterial agent.


K. Yagi / U. of Khartoum

Figure 15.8

Paraffin gauze and occlusive dressings.


K. Yagi / U. of Khartoum

Figure 15.9

Plastic bag modification of occlusive dressing.

Many antibacterial compounds can be used. Silver sulphadiazine (Flamazine®) and silver nitrate solution are unique in that they can penetrate the wound surface and reach the bacteria beneath it; therefore, they are best for infected full-thickness burns. Antibiotic ointment (polymyxin/bacitracin or similar) and paraffin gauze is another excellent dressing, particularly for partial-thickness burns with no eschar. Honey and ghee dressings can be used where expensive compounds such as silver sulfadiazine are scarce. Equal parts of honey and either ghee (clarified butter), or oil, are mixed together and poured over open sheets of gauze in a pan. The honey provides a hyperosmotic environment that discourages bacterial growth and the ghee or oil keeps the gauze from adhering. Silver nitrate solution (0.5%) is effective but oxidizes easily, staining everything it contacts black. Other agents used around the world include gentian violet, which desiccates the burn, tea which tans the burn like leather, papaya and banana leaf, boiled potato skins, fermented fish sauce, and Amazonian frog skin. In some instances local methods may be preferable to imported products.

Occlusive dressings

Bulky sterile dressings relieve pain and are comfortable for the patient, and protect the burn wound from infection. They absorb serum and exudate and foster a moist healing environment by keeping the injured part immobile and warm; they contain antibiotics able to penetrate the dead eschar (i.e. silver sulfadiazine ointment).

The dressings have three components: an inner layer of a liberal application of silver sulphadiazine covered by fine-mesh gauze or paraffin gauze; a middle layer of large gauze-wrapped absorbent cotton pads, which absorb the exudate and protect the wound; and an outer layer of bandages that secures the dressing.

If the dressing becomes soaked through, the outer layers should be changed or bacterial contamination will occur by capillarity. Dressings should be changed every day or two under adequate analgesia, and the old silver sulphadiazine washed off in the shower. The wounds should be inspected and gently cleaned at dressing time, and morsels of dead eschar removed with scissors and forceps.

Occlusive dressings are best for small burn areas, especially on the limbs, or when hygienic conditions are less than optimal.

The plastic bag or surgical glove method

This method is used for burns to the hands and feet. After cleaning the burn and applying silver sulphadiazine directly to the wound with a spatula or the gloved hand, a plastic bag is used as a glove or a sock, tied around the wrist or ankle. It must not be too tight. The limb should be kept elevated to reduce swelling. The burnt area will be kept moist and movement of the joints, both passive and active, is encouraged. A surgical glove may also be used instead of a plastic bag; it allows for more mobility during physiotherapy.

Open therapy

Where resources are inadequate to allow for occlusive dressings, this is the method of choice – as well as being the standard method for burns of the face and perineum – but requires clean and isolated surroundings, and the ambient temperature must be warm; hypothermia is to be avoided at all costs.

The patient is placed on clean sheets and the burnt area left completely exposed. Silver sulphadiazine ointment is applied to the burn wound liberally with a sterile gloved hand and repeated twice daily or as required. If the room is cold, the patient may be covered with a clean sheet and blanket draped over a frame to prevent contact with the wound. The entire bed should be kept under overhanging mosquito netting.

The *advantages* of this method of treatment include simplicity of examination of the burn wound and ease of nursing care. It also allows early mobilization by physiotherapy.

The *disadvantages* are pain, odour, and desiccation of the wound, delayed eschar separation and hypothermia. Frequent showering is required to wash away exudate and fragments of softened eschar. The bed linen must be changed regularly; it is readily dirtied by the burn exudate. Local customs and religious practice may limit the use of this "open" method.

Facial burns are best treated open with frequent gentle cleansing and application of moist warm saline gauze soaks, interspersed with application of topical antibiotic ointment (e.g. polymyxin/bacitracin). Beards and facial hair growing through the burn should be shaved at least every two days to prevent accumulation of exudate which may harbour infection. Antibiotic eye ointment should be applied frequently to the conjunctiva if the lids are burnt and retracted, to prevent keratitis and corneal ulceration. The lids should only very rarely be sutured together (blepharoplasty) as the sutures almost inevitably pull out causing yet more damage to both lid and globe.


ICRC

Figure 15.10

Open burn therapy with frame.


ICRC

Figure 15.11

Healing burn to the face.

15.7 Closure of the burn wound

The preparation of the burn wound and its subsequent closure are the two main steps in the surgical management of burns. The type of surgery required depends upon the skill and training of the surgeon, the specific burn injury, and the facilities available to support the treatment, especially the availability of blood for transfusion. Like all other injuries treated under difficult circumstances, great judgement is required to select the technical procedure that is appropriate.

Partial-thickness burns will generate new epithelium on their own if infection is prevented. The wounds should be inspected carefully as they progress. In superficial partial-thickness burns (and donor skin graft sites) epithelial cells grow out from around tiny skin appendages giving a typical "leopard spot" appearance in those with pigmented skin and, on close inspection, a slightly dull, silvery coat of epithelial cells may be seen growing atop the dermis (Figure 15.12.1). Tiny white pearls of epidermis herald re-growth and healing; areas of raspberry-red granulating dermis or fat do not have sufficient epidermal cells to heal (Figure 15.12.2). A "nicely granulating" burn wound is not a good thing unless there is a plan to graft the wound.



ICRC

Figure 15.12.1

Partial-thickness burn well on the way to healing.



E. Dykes / ICRC

Figure 15.12.2

Granulating burn: no healing. The pale colour of the granulations indicates that the patient is anaemic.

For full-thickness burns, the eschar may be removed completely in a single procedure or in a number of stages. The aim of treatment is to prepare the wound for eventual closure and to prevent colonization by bacteria and fungi.

15.7.1 Mechanical cleansing and debridement

Thorough cleaning and removal of debris and fragments of eschar are performed at each dressing session. Gentle washing and sharp debridement of dead skin fragments should be combined with thorough irrigation with water. The surface can then be cleansed with a mild disinfectant (dilute hypochlorite solution, detergent soap) and thoroughly washed again with water. Silver sulphadiazine is reapplied. Where resources are scarce, the cycle of dressing and plucking can be continued until the wound is completely free of eschar. This gives partial thickness burns the optimum chance to re-epithelialize and minimizes the area that will require grafting. Such patients need large amounts of nursing time, dressing material, and will probably require blood transfusion even without surgery.

15.7.2 Surgery

The most difficult decisions in burn care involve the timing and extent of surgery. Judicious staging of burn surgery is highly important and, where possible, should take into account the patient's livelihood. Donor and graft areas should be matched in advance and the process broken down into manageable parts. Attention should be paid to how the body parts will be positioned for the operation: if the plan is to graft the arm, it should be seen to before the hand as the latter will be needed to hold up the arm for surgery.

The hands, feet, and joint surfaces are considered priority areas in order to re-establish function; early grafting of these parts must be balanced against the metabolic advantages of closing larger areas on the limbs and torso. At least two weeks should pass before grafting of facial burns is considered, as even quite deep burns may go on to heal on their own. Eyelids are the first priority here.

Tangential excision

The removal of the full thickness of the burn wound is performed in a single session. Early tangential excision and immediate grafting of burns reduces mortality, morbidity, suffering and hospital stay while improving functional and cosmetic results, but it requires considerable resources and is *impracticable* for areas larger than 10 % TBSA outside specialized burns centres. It is bloody surgery.

Most field surgeons should be *conservative* with regard to this technique. It is, however, recommended in ICRC practice for small burnt areas, especially on the face, hands and feet, and over joint surfaces.

In tangential excision of the eschar, the superficial layers of the burnt tissue are progressively shaved away by knife, dermatome or cutting diathermy until viable tissue is reached. Traditionally, this is determined by the appearance of copious punctuate bleeding. It is accompanied by significant blood loss and is the most important limiting factor of this technique.

Blood loss can be reduced by Esmarch bandage exsanguination of the limb and a tourniquet, and subcutaneous infiltration of a dilute adrenaline solution (1:500,000); in the face, lidocaine with adrenaline can be used. The subcutaneous infiltration of some type of fluid (saline, dilute adrenaline solution, or local anaesthetic), causes a local tumescence that facilitates the excision. With adrenaline solution, as dead burn eschar is sliced away, the surgeon should look for a level with visible pearly white dermis, or glistening yellow fat, and no capillary thrombosis. After excision, larger bleeders should be cauterized and the wound wrapped for ten minutes with gauze soaked in adrenaline solution. The wrapping should be removed, and the process repeated until there is no active bleeding, before the skin graft is applied.

When tangential excision is successful, only dead tissue is removed. It can be difficult to judge how much to take away in order to leave a viable layer that will take an immediate skin graft.

Face

The skin of the face, particularly the beard areas on males, is very thick and well populated with deep epidermal cells that will provide for re-epithelialization if given time. If there is any doubt about the depth of burn on the face it is best to wait two weeks before tangential excision.

As mentioned, face burns are treated by the open technique with warm wet gauze soaks, gentle cleaning and shaving every second day, and the application of a local antibiotic ointment. Severe face burns will require scraping and cleaning under general anaesthesia to properly evaluate which areas are healing and which will eventually need grafting. Gauze soaked in an adrenaline-saline solution (1:33,000) should be used and pressure applied to control bleeding. When clean, a thin coat of antibiotic ointment should be applied and the previous dressing routine resumed while waiting to decide whether to excise and graft.

Excision of a small deep burn to the face can be performed under local lidocaine with adrenaline anaesthesia; larger areas require general anaesthesia, but simultaneous subcutaneous infiltration with a dilute adrenaline solution will render the excision easier and less bloody.

Hands, feet, and joint surfaces

Tangential excision of the hands, feet and joint surfaces can be performed at three days onwards, once the patient is well resuscitated.

Many severe hand burns will benefit from early escharotomy since deep partial-thickness or full-thickness burns heal with extremely disabling contractures; operating these early should be considered and good, thick skin for the grafts saved. Typically people clench their fists when they sustain a burn so the palmar skin extending up to the mid-lateral lines of the fingers is usually preserved, or burnt much less deeply than the dorsum, and rarely needs grafting. Therefore most burnt hands and fingers will only require grafting of the dorsum. If the escharotomy was performed accurately along the edges of the full-thickness burns along the mid-lateral lines of the fingers, this will mark the extent of excision necessary.

Proper preparation is the key to good excision. The areas to be excised should be carefully marked with ink or gentian violet. The hand and forearm should be exsanguinated by five-minute elevation and application of a rubber Esmarch bandage, beginning with the hand and progressing proximally; a pneumatic tourniquet is then applied. (Correct use of a tourniquet is painful; the operation should be performed under general anaesthesia.) Normal saline or a weak adrenaline solution should be infiltrated subcutaneously over the dorsum of the hand. The edges of the areas to be excised should be scored with a #15 blade.

Tangential excision should be performed using a small dermatome or scalpel, preserving viable dermis where possible and being very careful not to damage tendon sheaths. The hand should be wrapped in adrenaline-soaked gauze and the tourniquet briefly released. The tourniquet should then be re-inflated for ten minutes to allow natural haemostasis, then removed. The hand should be unwrapped and diathermy used to cauterize remaining bleeders. Wrapping in adrenaline gauze and cauterizing of bleeders may need to be repeated several times to ensure perfect haemostasis prior to application of the skin grafts. Sheets of relatively thick split-thickness skin should be used. Grafts should be carefully tailored over the dorsum of the hand and fingers, and sutured in place. Each finger should be covered in paraffin gauze dressing, then wrapped independently in gauze, taking care to leave the tips of the fingers exposed in order to assess perfusion.


M. Beveridge

Figure 15.13

The "safe position" for splinting a hand.

Finally, the hand should be splinted in the "safe position" (Figure 15.13) with the wrist dorsiflexed 30°, the metacarpal-phalangeal joint flexed as close to 90° as possible, the fingers splayed apart and the inter-phalangeal joints straight. The initial dressing should be left for 5 – 7 days and then unwrapped carefully. The burn should then be re-dressed daily with paraffin gauze and re-splinted. Physiotherapy and mobilization should begin as soon as the grafts are solid. A hand should never be immobilized longer than ten days. K-wires placed through the fingers may help in bad cases. The same general principles apply to the feet and over joint surfaces.

Early tangential excision gives the speediest recovery and best functional and cosmetic results when it is practicable, but should *never* be undertaken for large areas unless the resulting blood loss can be properly managed.


E. Winiger / ICRC

Figure 15.14.1

Meshed skin graft: recipient site.

Skin grafting

The hands, feet, and joint surfaces are priority areas for skin grafting, with or without tangential excision. The anterior chest and neck take priority over the belly and buttocks. The back has very thick skin, and so burns to it may be observed for some time while waiting to see if they will heal on their own.

Allowing burns to granulate and demarcate under dressings (2 – 6 weeks) is prudent practice where resources are scarce. This means accepting inevitable protein loss from open wounds, possible infection, delayed healing, and chronic anaemia; supplementary measures must therefore be taken to reduce these effects.

To prepare for grafting, the jelly-like granulation tissue must be scraped away with the back of a scalpel handle before the skin graft is carefully secured and dressed. The advantage of delayed grafting is that often a much smaller area need eventually be grafted.


E. Winiger / ICRC

Figure 15.14.2

SSG after grafting.

Grafting on burns is time-consuming and adequate time should be allocated for these operations. The staging of the surgery should be carefully planned and just one limb or body area operated at a time. In general, the thinner the graft, the better its chances of "take", and the thicker the graft, the better the functional and cosmetic result (see Chapter 11 for details on skin grafting). A limb or digit that has to be amputated should be regarded as a prime source of donor skin. Harvesting of grafts in children whose skin may be extremely thin should be performed with *great care*. If there is no solid layer of dermis left behind, the donor site will not heal. Except on the face, hands and feet, skin grafts should be meshed to allow serum to drain through rather than lift the graft off the bed of the recipient site.

Old wounds or sites where previous grafts have failed are notorious for difficulty in achieving an adequate graft take. Good nutrition and meticulous preparation of the surface are the keys to success. Early excision of grossly dead and infected tissue, topical and systemic antimicrobial therapy, and aggressive nutritional supplementation should precede any attempt at skin grafting. The best course may be to graft critical areas while leaving some of the larger, less functional areas to granulate.

The surface of the debrided burn wound often has a superficial slime of exudate and bacterial contamination. Dressings with a supersaturated saline solution (add salt to normal saline until it no longer dissolves), changed frequently for a couple of days, will produce a clean, bright red granulating surface ready for grafting.

The occlusive dressing which is applied after skin grafting plays a great part in the survival of the graft. It must be put on with great care. The dressing must hold the graft closely applied to the recipient site for the first few days for capillaries to grow in. Any blood or serum that floats the graft away from its bed will cause it to fail.

The life of a patient with a severe burn is in danger until the dead tissue has been excised and the defect closed with a healthy skin graft.

15.8 Scar management

Burns always result in scars and the burn graft itself is best thought of as a scar. One of the most disastrous consequences of burns is the severe scar contracture that may render life horrendous for the victim afterwards. Management of the burn scar begins before grafting, during local care of the burn wound. Rigorous splinting – using plaster of Paris slabs – and stretching routines should be implemented to prevent contracture of major joints: the limb should be splinted *against* the force of contracture. If a joint is equally burnt on both sides, it should be splinted in extension. Airplane-strut type splints should be used for burns to the axilla. Patients must be given adequate analgesia for the daily passive stretching exercises.


ICRC

Figures 15.15.1 and 15.15.2

Post-burn scar contractures.


ICRC

Much, if not most of the functional benefit of burn grafting depends on assiduous splinting and stretching of the tissues afterwards to manage the process of burn scar contraction. This can be particularly active in children – a perfect operation may result in recurrence of a dreadful scar if the tissues are not managed properly over the next 6 – 12 months.

All burn grafts crossing joints should be splinted at operation with plaster slabs. Later, when the grafts have taken, a plaster slab covered in tube bandage and fitted correctly makes an excellent, reusable splint that can be worn at night and removed for therapy during the day. Dedicated staff and adequate analgesia are essential to active and passive stretching of burn scars; if this hurts too much the patient will simply not comply. Burns crossing joints should be splinted and stretched even if they have not been grafted, as this will reduce the degree of contraction as the scar heals.

Pressure garments are important to optimum scar management and their use results in much softer and more pliable scars. Where they are not available, elastic bandages and a variety of tight-fitting stretchy commercial clothing may help. Water-based skin cream will help with itching as will antihistamines. Burn scar massage is also helpful where traditional practitioners are present.

15.9 Electrical burns

As mentioned, there are two distinct categories. With flash burns, the patient typically presents with fairly deep burns to the face and one or both hands and forearms. Treatment is as with regular thermal injuries.

High voltage (>1,000 volts) electrical conduction injuries have small cutaneous entry and exit wounds, which extend deep into the muscles causing myonecrosis. The rhabdomyolysis has a *systemic* effect, with myoglobinaemia and myoglobinuria leading to acute tubular necrosis; and a *local* effect, i.e. compartment syndrome.

The patient should receive Ringers' lactate, with 50 mEq sodium bicarbonate per litre, in sufficient volume to maintain urine output at 0.5 ml/kg. If the urine is dark or bloody, or urine output ceases, the vascular space should be well filled and a bolus of 20 % mannitol given (1g/kg); furosemide may be added as well.

Any suspicious compartments should be released promptly by generous full-length fasciotomy, including carpal tunnel release in the forearm. Dead muscle should be debrided conservatively, and numerous returns to the operating theatre may be needed (serial debridement).

Numerous complications attend electrical conduction injury including arrhythmias (ECG monitoring is strongly recommended), cervical fractures associated with the jolt of electricity, intestinal perforation and a variety of unusual neurological sequelae.

15.10 Chemical burns

A number of chemical substances cause specific burns. The presence of any of them on an injured person poses a danger to first aiders, hospital staff, and other patients. Careful removal of contaminated clothing and proper decontamination measures must be undertaken – of the patient and of any equipment used – and specific protocols followed to protect the medical personnel treating the patient.

> The wounding chemical agent constitutes a danger to first aiders, hospital staff, and other patients. Proper protective measures must be taken.

15.10.1 Acid and alkali burns

In general, acids cause coagulative necrosis of the skin, and strong alkalis liquefactive necrosis and burrowing of the chemical deep into the tissues. "Acid violence" involving the throwing of concentrated sulphuric acid into the face is an increasingly common phenomenon and the chemical is readily available wherever there is a motor vehicle garage. The acid burn should be washed with very large volumes of water and the eyes thoroughly irrigated. Strong alkalis may come in dry form (NaOH crystals); any remaining material must be brushed off the patient before washing with water.

After this decontamination, the treatment of chemical burns follows the same sequence as the treatment of thermal burns. Acid attacks usually involve the face and typically cause extremely disfiguring injuries which are very difficult to reconstruct.

15.10.2 Phosphorus burns

Some modern anti-personnel weapons contain white phosphorus. This element *ignites on contact with air*, and fragments of phosphorus will be scattered throughout any wounds; it is lipid soluble and sticks to the subcutaneous fat. The burn is deep and painful and the phosphorus continues to burn as long as it is in contact with oxygen or until all the phosphorus is consumed, all the way down to the bone. Local treatment is more urgent than with conventional burns because of the aggressive nature of phosphorus. Much of the injury in an individual patient, however, results from the ignition of clothing, which causes a conventional burn.

Contaminated clothing must be removed immediately, care being taken not to contaminate the staff attending to the casualty. Visible, smoking particles can be removed with a spatula or knife, and should be placed in a basin of water to exclude them from the air. Phosphorus burn wounds must then be isolated from oxygen by being kept wet through liberal soaking with water, by covering with wet dressings, or by placing the injured part in a basin of water. On no account must they be allowed to dry out.

When surgical treatment is available, the idea is to identify and remove the remaining phosphorus particles. The wet wound can be irrigated with a neutralizing agent. A freshly prepared solution of 1% copper sulphate combines with the phosphorus to form black copper sulphide, which impedes violent oxidation and identifies the particles. The black particles can then be removed with forceps and placed in a basin of water. The solution must be very dilute, the palest blue colour, since its absorption can cause haemolysis and acute renal failure. If used, the copper sulphate solution must be washed away immediately. Or, if copper sulphate solution is not available, the operating theatre lights may be put out; any remaining particles will glow with phosphorescence in the dark and can be carefully picked out with forceps and placed in a basin of water.

Care must be taken not to allow the wound and the phosphorus to dry out and re-ignite in theatre; appropriate, non-flammable anaesthetic agents should be used. In all cases, the wound should then be excised and dressed as usual.

Phosphorus may provoke hypocalcaemia and hyperphosphataemia; intravenous calcium should be given. Absorbed phosphorus can be toxic to many organs:

- central nervous system – delirium, psychosis, convulsions, coma;
- gastro-intestinal tract – abdominal colics, melaena;
- liver – hepatomegaly, jaundice;
- kidneys – proteinuria, acute tubular necrosis;
- blood – thrombocytopenia, hypoprothrombinaemia;
- myocardium – ventricular arrhythmia, myocarditis.

15.10.3 Napalm injuries

Napalm is jellied petrol, an intensely flammable agent that clings to the clothing and skin while still burning and causes serious, deep and extensive burns. Its incomplete combustion of the oxygen in the air around the victim provokes an acute rise in carbon monoxide that can lead to a loss of consciousness and even death. The intense heat and benzene fumes easily cause inhalation burns.

Napalm burns are invariably *full thickness*, with coagulation of muscles and other deep tissues. Nephrotoxicity is a serious complication of the rhabdomyolysis, and the mortality may be high in proportion to total body surface area involved. A full-thickness burn of only 10% of the body surface area may result in renal failure. The patient should be kept well hydrated and in alkalosis; mannitol may be necessary to protect renal function.

First-aid treatment includes extinguishing the burning napalm by smothering it, i.e. excluding the oxygen. Unlike phosphorus, napalm does not then reignite in contact with the air. Surgical treatment involves removal of the napalm with a stick, spatula or knife. The wound is then excised deep to any remaining contaminant, care being taken to avoid contact ("no-touch" technique), and dressed as usual.

15.10.4 Magnesium

Flares released from aircraft to avoid heat-seeking missiles use magnesium, which gives off great heat when lighted. These may reach the ground and cause fires and injuries. The intense heat causes a full-thickness burn. The wound should be excised deep to the contaminant using the "no-touch" technique. Some reports from ICRC surgical teams (Kabul, Afghanistan) have made mention of toxic side effects due to absorption of magnesium, similar to phosphorus; this has not been confirmed.

15.10.5 Vesicant chemical weapons

Unlike other agents causing specific burns, chemical weapons have been banned by international treaties.[4] However, some States retain stockpiles, which may either be used militarily or released into the air if the storage facilities are bombed. Certain chemicals have a potential dual function: they can be used in weapons and are widely employed for civilian purposes (the disinfection of public water supplies in the case of chlorine).

Traditional chemical weapons are either neurotoxic or vesicant (blistering); the latter cause burns to the skin and inhalation injury. Vesicant agents (mustard gas, lewisite, phosgene) cause skin burns similar to flame burns.

The patient's clothing must be removed and properly destroyed. The patient is then decontaminated with abundant soap and water. Care must be taken not to contaminate hospital personnel, equipment, and other patients with the chemical agent. Correct decontamination protocols include the use of protective clothing and equipment (mask, gloves, boots, etc.) by first aiders or hospital staff.

Once decontamination has been performed, the wounds are dealt with in the traditional manner; however, a "no-touch" technique should be used during wound debridement and removed tissues disposed of with care. The patient's respiratory function must be closely monitored. Inhalation of chemical fumes will burn the respiratory mucosa with the development of acute respiratory distress syndrome (ARDS). Assisted ventilation may be required.

---

[4] 1925 Geneva Protocol for the prohibition of the use in war of asphyxiating, poisonous or other gases and of bacteriological methods of warfare and the 1993 Convention on the Prohibition of the Development, Production, Stockpiling and Use of Chemical Weapons and on Their Destruction.

One practical way to effectively deal with the negative emotions is to distinguish between them, so that they can be separated and sorted so they receive the attention they require and they become manageable. We may see them like our children who each have their specific needs. We can give to each one the particular attention they deserve. To deal with them all at once is too difficult and leads easily to discouragement and a sense of powerlessness and defeat. In such a way you more easily work with them.

For each of us, the relations among and between positive and negative emotions is a unique one. So are our needs and styles to deal with them, depending on the culture we have grown up in, our different kinds of education and the ways we have responded to them and have evolved. So we will need to rely on and develop our own imaginativeness to use the formulas creatively so that they may be helpful rather than become an obstacle, as we apply them mechanically. We need to learn to feel what is good for us, and what helps us to be centered, in balance and at peace with ourselves.

Practice of Humor and the Humor of Practice

Crucial to our practice is a sense of humor and playfulness: to avoid the Fusion Practice becoming a reproduction of old patterns in a new form, as we use it as a device to track down our weaknesses in a spirit of self-condemnation. Humor is essential for balancing the energies of and in our organs. Humor is the great regulator which helps us to look with a sense of relativity, playfulness and lightness at ourselves. It is an expression of the compassionate energy of the heart which helps to look with a sense of detachment at ourselves and not to take ourselves so seriously that it becomes difficult to relax and be a witness rather than a severe judge.

With little humor, the Fusion Practice would become an accounting practice in which we record the drawbacks which prevent us from advancing. In focusing on the negative as if it were evil, we lose sight of our creative potential and prevent ourselves to gradually free ourselves from old patterns. Without humor we see no way out except by relying on some external power or force which only further undermines our own original power of self-transformation.

ANNEX 15. A Nutrition in major burns: calculating nutritional requirements

Calorie requirements = Basal energy expenditure x stress factor x activity factor
The *basal energy expenditure* is calculated as follows:

[66 + (14 x weight in kg) + (5 x height in cm) – (6.8 x age in years)]

The *stress factor* for minor procedures is 1.3; for skeletal trauma, 1.35; for major sepsis 1.6; and for major burns 2.1.

The *activity factor* is 1.2 for those in bed and 1.3 for those who are mobilizing. Women require about 4 % less than men for equal body size and age.

Example
For a 25-year-old male weighing 60 kg and 170 cm tall, in bed with a major burn, the calorie requirements =

[66 + (14 x 60) + (5 x 170) – (6.8 x 25)] x 2.1 x 1.2 = 3,997 kcal/day

Protein, glucose and fat requirements
Daily *protein* requirement for acute burns is 2 g/kg in adults and 3 g/kg in children. Protein provides about 4 kcal/g (120 g and 480 kcal in the example given above).

Daily *glucose* requirement is about 6 g/kg/day in burns.
Glucose provides 4 kcal/g (360 g and 1,440 kcal in the example).

The difference between the calculated energy requirement (3,997 kcal) and that provided by protein and glucose should be made up with fat.

Daily *fat* requirement = 3,997 kcal – 480 – 1,440 = 2,077 Kcal
Each gram of fat provides 9 kcal, therefore, 2,077 ÷ 9 = 231 g of fat

The larger the volume and the higher the fat concentration the more likely the patient is to develop diarrhoea. In an adult with a major burn, 3 litres of feeds per day is a reasonable target; therefore for the patient in the example, a "cocktail" containing 40 g of protein, 120 g of glucose and 80 g of fat per litre should be prepared.

Making a high-energy enteral feeding solution for burn patients

Ingredients	Glucose	Protein	Fat	kcal
Skimmed milk powder 110 g (244 ml)	44 g	40 g		385
Edible oil 80 g (80 ml)			80 g	720
Sugar 50 g (50 ml)	50 g			200
1 Banana (15 mEq potassium)	25 g			110
Add: Salt 3 g Calcium containing antacid 3 tablets Multivitamin tablet 1 daily Ferrous sulphate + folic acid tablets Codeine 30 – 60 mg per litre provides analgesia and reduces diarrhoea Eggs contain 15 g of protein each: beware of salmonellosis from raw eggs Supplement tube feeds with cooked eggs fed by mouth when possible				
Boiled and filtered water to make 1,000 ml of solution			Total 1,415 kcal per litre	

Make a paste of milk powder with a little water; add sugar, salt, crushed tablets and oil. Slowly add more water while mixing well; add mashed banana and mix thoroughly (using a blender if possible). Filter the mix through a gauze compress and refrigerate. Irrigate the feeding tube regularly with water to keep it from blocking. Use within 24 hours.

Chapter 16

LOCAL COLD INJURIES

16. LOCAL COLD INJURIES

16.1 Physiology of thermal regulation 301

16.2 Types of local cold injuries 301
16.2.1 Non-freezing injury 301
16.2.2 Freezing injury 301
16.2.3 Local signs and symptoms 301

16.3 Management 302
16.3.1 First aid and transport 302
16.3.2 Hospital treatment 302
16.3.3 After care 303

16.1 Physiology of thermal regulation

The significance of prevention and treatment of local cold injuries during armed conflict cannot be overemphasized. Although most commonly seen in arctic and subarctic climates, cold injuries can occur whenever the combination of cold, wet, and immobility exists. High altitudes, even in tropical or temperate regions, can experience cold weather. Wind is an aggravating factor in all circumstances.

Normal body temperature is maintained through a balance between heat production and heat loss, and is regulated by a hypothalamic "thermostat". At least 95 % of the heat produced by the metabolism of viscera and muscles is normally lost to the environment by conduction, convection, radiation, and evaporation, largely through the skin and lungs; the head and neck account for 20 – 30 %. The skin primarily dissipates heat by regulating its blood flow, which may vary from 50 ml/min to 7,000 ml/min.

In a cold environment, the *core temperature* (that is, the temperature of the vitally important visceral organs) is conserved by decreasing heat loss through peripheral vasoconstriction, and by increasing the production of heat by involuntary muscle contractions (shivering). If the heat loss exceeds the heat-producing resources of the body, the core temperature begins to fall and *hypothermia* develops. Wetness and wind increase the effect of cold in inducing loss of body heat.

In peripheral tissues subjected to low temperatures, wetness, wind, and contact with a cold surface (metal), local cold injury may result from vasomotor and/or cellular effects, including intracellular ice crystal formation.



O. Litvin / ICRC

Figure 16.1

Patient with "trench foot" affecting both feet.

16.2 Types of local cold injuries

Local cold injuries can occur at temperatures above or below freezing point and are classified as non-freezing or freezing injuries.

16.2.1 Non-freezing injury

This is also known as "immersion foot" or "trench foot", and is seen in prolonged exposure to cold ambient temperatures above freezing, with high humidity and immobilization, as often witnessed during the trench warfare of World War I, hence the name. Prolonged wetness and cooling of the feet, as can occur in a jungle or rice paddy, can also provoke an "immersion foot" injury. Such injuries are diagnosed and treated like other cold injuries, except that the feet should not be immersed in warm or hot water.

16.2.2 Freezing injury

This type of injury, also known as "frostbite", may be superficial, in which only skin and subcutaneous fat are involved, or deep, reaching structures such as muscle.

Frostbite occurs in the extremities and exposed body parts: nose, ears, etc. In the early stages of injury, it is not easy to differentiate between superficial and deep wounds.

16.2.3 Local signs and symptoms

These include:

- paraesthesia;
- numbness and insensitivity to pin prick;
- pallor (wax-white or mottled blue discoloration);
- impaired movement leading to paralysis;
- firmness of the body part;
- oedematous swelling (particularly in non-freezing injuries) followed by blister formation after 24 – 36 hours.

16.3 Management

16.3.1 First aid and transport

When a body part is frozen solid for hours it runs a lesser risk of tissue loss than when it is exposed to a cycle of thawing, refreezing, and thawing. A person can continue to walk on a frozen foot while it remains frozen; but will be unable to walk after thawing because of the pain and swelling. This should be kept in mind *before* pre-hospital treatment is attempted; it might be preferable to transfer the patient to adequate shelter and facilities rather than begin treatment with inadequate means.

The patient should be moved to a sheltered place as soon as possible. Boots and socks should be removed, avoiding trauma to the skin. As with burns, constricting agents such as rings should also be removed.

As some degree of central hypothermia generally coexists with local cold injury, the general body temperature should be raised by hot drinks, blankets, or skin-to-skin contact. The frozen extremity should be *prevented* from thawing before normal core temperature is reached.

Once hypothermia has been corrected, any available form of heat transfer (skin-to-skin contact, foot-in-axilla, hand-to-nose) should be utilized to warm the body part. Rapid rewarming in warm water (40 – 42°C, or just tolerable to elbow immersion) should only be used when it is certain that refreezing can be avoided.

Analgesia is essential, as thawing of frostbite is extremely painful.

Do not:

- rub or massage injured tissue;
- apply ointments or other topical medication;
- break blisters;
- rewarm by exposure to fire, radiant heat or excessively hot water.

16.3.2 Hospital treatment

Central hypothermia should be dealt with *first* through external rewarming by blankets and warm water bath. In severe cases (core body temperature below 30° C) combined or not with frostbite, central warming has a priority over peripheral warming because of the risk of "after-drop". This represents a situation where the core temperature tends to decrease during peripheral heating of the body. Rewarming of the limbs causes a local vasodilatation with shunting of cold stagnated blood towards the central part of the body; arrhythmias and cardiac arrest may result. Central core warming measures include warm i.v. fluids, rectal enema, and bladder, gastric and peritoneal lavage at 37° C. A low-reading thermometer is necessary to satisfactorily monitor core temperature (see Chapter 18).

Hypothermia takes precedence over local cold injury.

General rewarming should precede local rewarming.

Once hypothermia has been sufficiently corrected, attention may be given to the local cold injury. Superficial injuries may be rewarmed rapidly in 40 – 42° C water. For deep injuries, if the limbs are still frozen or cold and vasoconstricted, they should be rewarmed with dry heat at 37 – 39° C. Even if only one limb is affected, both should be rewarmed together until the nail beds become pink. The patient should receive 100 % oxygen, warmed and humidified, during the warming process.

If the patient is comatose, it should be borne in mind that the patient is not dead until he is *warm* (33° C core temperature) and dead!

Aspirin still appears to be a most useful drug for pain relief and possibly for preventing tissue loss. Pethidine may be added as necessary. Amitriptyline is the preferred analgesic for immersion injury. Tetanus prophylaxis and penicillin should be given. Smoking is contraindicated.

Heparin, anticoagulants, corticosteroids, antihistamines and intravenous dextran have all been shown to be of little benefit. Disagreement exists on the effect of sympathectomy.

16.3.3 After care

Once rewarming is complete, little more can be done to alter the course of events.

The basic treatement is conservative wound care.

Good nursing care and physiotherapy is the essence of conservative treatment. The extremities should be kept on sterile sheets under cradles. Sterile cotton pledgets are placed between toes or fingers. Warm povidone iodine soaks twice daily help prevent superficial infection. As blebs appear, precautions are taken to avoid their rupture: they should not be allowed to dry up. The limb should be placed so as to avoid pressure on the injured part as much as possible. A good functional result will be helped by maintaining active exercises and elevating the affected limb.

It is difficult to predict the extent of eventual tissue loss from frostbite during the first weeks after injury. Tissue loss, however, is generally smaller than expected. It is therefore important to wait until the damaged tissue becomes necrotic and mummified, with a clear line of demarcation and spontaneous amputation of fingers or toes. As with burns, escharotomy of circumferential injuries, and even fasciotomy, might be necessary.

Wait until a clear line of demarcation appears between necrotic and viable tissue.

The *surgical treatment* of local cold injury is to avoid excision of tissues unless secondary infection intervenes. The natural process is allowed to happen: “frozen in January, amputation in July”.

Chapter 17

ANAESTHESIA AND ANALGESIA IN WAR SURGERY[1]

---

[1] Much of this chapter is based on the report of the Senior Anaesthetists Workshop held in Geneva, November, 2002 (see Introduction).

17. ANAESTHESIA AND ANALGESIA IN WAR SURGERY

17.1 Introduction 307

17.2 Anaesthesia methods 308

17.3 Local and regional anaesthesia 309

17.4 Dissociative anaesthesia with ketamine 310
17.4.1 General considerations 310
17.4.2 Ketamine i.m. and i.v. bolus 311
17.4.3 Ketamine infusion anaesthesia 311
17.4.4 Ketamine analgesia 312

17.5 Post-operative pain management 312
17.5.1 General guidelines 312
17.5.2 Pain scoring systems 313

ANNEX 17. A ICRC pain management protocols 314

Learning to tend our Garden

What helps is to realize that we do not have negative emotions, per se, but that we and our spirit are in them. They are an integral part of us, and when we want to eradicate them, we destroy ourselves and the spirit contained in the organs.

For the Fusion Practices to become effective, we need to learn to dialogue with our organs. We must learn to express our gratitude to them for the miracle that we are alive thanks to their unceasing work. We need to give them a chance to relax and recuperate. Let us give them a chance to get in touch with each other. They are both our parents and our children. They can store Chi and provide us with energy when we need it. Let us protect them from our anger and other negative emotions, so that they do not have to suffer and feel we drain them. Let them breathe freely, accumulate Chi, expel the accumulated toxins to that we can recover, nourish and sustain our health and vitality.

It is a challenge to see the positive in the negative; negative emotions, when freed from their destructive and explosive charge, contain pure energy which we badly need to develop our vital force.

It helps to accept ourselves if we remember that our negative emotions often mirror forms of resistance which at some time early in life, served as a form of legitimate and understandable protection and rebellion. At that moment they might have been necessary, but at some point they lose their function.

Negative energies may be seen as a kind of garbage. If we discharge it on others and the environment, it becomes a major factor in generating toxins, bacteria, viruses and a variety of forms of disease by which negative emotions are multiplied and become more and more difficult to control. Or they can be seen as highly positive and urgently needed for recycling and composting, so that they can be used to help us grow and improve our balance, so that we do not become a burden and a threat for others and our environment, but a blessing, as our energies contribute to a climate of harmony and peace. The more light and Chi that enters our body and the more we radiate it into others and our surroundings, the less bacteria and viruses have a chance to grow.

The Fusion Practice (Fusion of the Five Elements, Formula Four) provides an effective method for composting, as the negative energies from the different organs, after having been separated out in

17.1 Introduction

Standard anaesthetic practices, as utilized in trauma care, should be followed. However, providing safe and effective anaesthesia under circumstances of limited resources is probably the most challenging task of hospital work. Many limitations must be accepted owing to security concerns, lack of infrastructure, and difficult logistics.

A reminder to surgeons: operations are "big" or "small".
All anaesthesia is potentially fatal.

This chapter is not intended for anaesthetists, but rather presents what surgeons should know about anaesthesia when working under precarious circumstances. There are several reasons for this.

1. Surgeons perform "big" operations and "small" operations. There is no such thing as a "small" anaesthesia. Every anaesthesia is potentially fatal. The limits of operational activity in the theatre are not those of the surgeon's expertise. They are determined far more by the level of competency and sophistication of the anaesthesia department. The anaesthetist will tell the surgeon what can be done; not the other way around. The surgeon must understand, and accept, this limit. There is only one other limiting factor that is as important as anaesthesia, if not more so, in determining the level of sophistication of surgery to be performed: postoperative nursing care.
2. In wartime, a surgeon may sometimes find himself without an anaesthetist. In this case, the war surgeon must know how to administer safe and adequate anaesthesia in order to perform the most important and basic of lifesaving procedures. There is much that a surgeon alone can do in terms of anaesthesia. Good knowledge of local anaesthesia techniques – practical, cheap and safe – can be very helpful when resources are limited.
3. Moreover, in many countries practising surgeons far outnumber the anaesthetists, and this is likely to remain the case in the foreseeable future. Anaesthesia under these circumstances is usually administered by a nurse or technician under the "guidance", and medical responsibility, of the surgeon, who must understand the important indications and contraindications of the various anaesthetic techniques. Needless to say, the surgeon must know about the possible complications of the anaesthesia used and how to counter them.

It would be presumptuous to try to explain the safe administration of anaesthesia in a half-dozen pages. This account comprises the basic precepts that a surgeon should be familiar with. For a full description of appropriate anaesthetic techniques under circumstances of limited resources, practicable by a surgeon or other medical officer, the reader is referred to the excellent texts listed in the Selected bibliography.

Figures 17.1.1 – 17.1.4

Standard ICRC equipment for anaesthesia.



R. Aburabi / ICRC

Figure 17.1.1
Typical operating theatre. Note the inhalation anaesthesia machine and oxygen concentrator.



M. Baldan / ICRC

Figure 17.1.2
Pulse oxymeter for monitoring; laryngoscope and endotracheal tube, bag for manual ventilation.



C. Gerber / ICRC

Figure 17.1.3
Foot-driven suction pump.



M. Baldan / ICRC

Figure 17.1.4
Electric suction pump.

ICRC EXPERIENCE

The points listed below have been found to be particularly important by ICRC anaesthetists and may be useful to other humanitarian organizations or foreign staff operating in a war environment in a new and strange context.

- The presence of a good interpreter, preferably with a medical background, is essential for communication with patients.
- Unfamiliarity with anaesthetic equipment and local conditions increases the likelihood of complications. The presence of an assistant knowledgeable about local standards is essential.
- The assistance of a second person – doctor, nurse – preferably with experience in anaesthesia, is mandatory for all anaesthetic procedures.
- Assessing the time the patient last ate is difficult, especially with breastfed babies.
- Many of the wounded, especially in hot climates, are severely dehydrated. It is important to correct any hypovolaemia before surgery.
- Routine premedication is not necessary.
- Arrangements for blood transfusion may be complicated (negotiating with family or clan members) and require local blood-collecting procedures to be activated. Likely blood requirements should be ordered early.

17.2 Anaesthesia methods

Local and regional anaesthesia techniques are excellent and can be used in many patients, although they tend to be underestimated and, therefore, underused: a below-knee amputation or Caesarean section can be performed under local anaesthesia, for example. They are safe in avoiding vomiting and aspiration, especially when the time of the last meal cannot be determined accurately.

Oxygen, nitrous oxide and other volatile anaesthetics may be in short supply. In the context of actual combat, oxygen cylinders are to be banned. Not only are the logistics for refilling cylinders and transporting them difficult and dangerous, but the presence of an oxygen cylinder is the equivalent of a bomb. Oxygen concentrators – with a pulse oxymeter for control – are standard ICRC equipment for these circumstances; however, they require an electrical supply.

Ketamine is the anaesthetic of choice in ICRC practice for major surgery. Equipment for the use of ketamine is minimal – not even an oxygen concentrator is necessary – and muscle relaxants can be added to provide full general anaesthesia. The further the hospital from the actual conflict zone, the more sophisticated the equipment and supplies that may be provided, and therefore the techniques employed.

The following anaesthetic agents and their characteristics should be well known to surgeons.

17.3 Local and regional anaesthesia

The clinically significant point in all forms of local and regional anaesthesia is to allow sufficient time for the anaesthetic to work. The most common mistake is to make a local anaesthetic infiltration, and then incise immediately.

	Technique	Drug of choice	Recommended volume	Remarks
Surface anaesthesia	Ophthalmic	0.4 % oxybuprocaine		If not available, 2 % or 4 % lidocaine (xylocaine) drops
	Mucosa	2 % lidocaine gel or 5 % lidocaine nebuliser spray		
Local infiltration anaesthesia	In general	1 % lidocaine with adrenaline	40 ml	If a volume greater than 40 ml is required, dilute with an equal volume of isotonic saline
	Fingers, toes, ears or penis	1 % lidocaine without adrenaline	20 ml	Danger of ischaemic gangrene if adrenaline is used
Nerve block	Digital block	2 % lidocaine without adrenaline	2 – 4 ml per digit	
	Axilla: brachial plexus block	2 % lidocaine with adrenaline or 0.5 % bupivacaine with adrenaline	30 – 40 ml	Where early movement is desired Provides prolonged sensory analgesia
	Intercostal block (flail chest)	0.5 % bupivacaine with adrenaline	2 ml for each nerve	Prolonged analgesia required
Regional intravenous anaesthesia		0.5 % lidocaine without adrenaline	40 ml	
Spinal anaesthesia	Subarachnoid block	0.5 % bupivacaine in 5 % dextrose		Hyperbaric, single dose ampoule
	Epidural	0.5 % bupivacaine	7 – 30 ml according to level of anaesthesia	Requires appropriate conditions of hygiene Not to be used routinely

Table 17.1 Anaesthetic agents of choice for local and regional anaesthesia.

Doses above are for adults. As a "rule of thumb", the maximum dose of lidocaine without adrenaline is 3 mg/kg (200 mg for an adult); and double with adrenaline: 6 mg/kg.

17.4 Dissociative anaesthesia with ketamine

The main components of safe and adequate general anaesthesia are:
- unconsciousness (hypnosis),
- analgesia,
- amnesia,
- immobility/muscle relaxation.

> Ketamine is the anaesthetic of choice for major war surgery in conditions of limited resources.

17.4.1 General considerations

Ketamine is very safe, and can be given intramuscularly, or as an intravenous bolus or perfusion.

M. Baldan / ICRC

Figure 17.2
Drugs for general ketamine anaesthesia.

It causes amnesia, analgesia, and a state of dissociation. The patient feels detached from the environment, but his reflexes are intact, particularly the laryngopharyngeal reflexes that protect the airway. Opening of the eyes, shouting, and limb movements are frequent and *normal*; the patient is nevertheless anaesthetized. It may cause hallucinations and should be combined with a sedative such as a benzodiazepine (diazepam is inexpensive but burns on injection; midazolam is not irritant but is costly).

Ketamine increases the cardiac output and the arterial blood pressure and, therefore, is particularly useful in patients with haemorrhagic shock. Ketamine dilates the bronchi, but also increases bronchial secretions and saliva. Atropine should be administered first to control saliva and bronchial secretions. There are important contraindications to the use of atropine: marked tachycardia, hypertension, valvular stenosis, hyperthyroidism, or fever. Ketamine also increases the muscular tone, which is why it makes a laparotomy, and especially the closure of the abdomen, more difficult if used without myorelaxants.

There is no absolute contraindication for ketamine anaesthesia. Relative contraindications include:
- psychiatric disease,
- mitral and aortic stenosis,
- untreated hyperthyroidism,
- eclampsia,
- epilepsy,
- operation on the eye – this is due to nystagmus, which causes the globe to move and makes operating difficult.

The question of the use of ketamine in patients with a head injury or increased intracranial pressure has been controversial, although based on very few and very early reports in the 1970s. There is no longer any contraindication for its use in these patients consistent with evidence-based medicine, and ICRC standard practice includes craniotomy performed under ketamine anaesthesia (see Selected bibliography).

The *advantages* of ketamine are the following:
- easy and rapid to administer with quick onset of action;
- safe;
- provides anaesthesia, amnesia, and analgesia;
- circulation is stimulated;
- respiration remains normal (very slow intravenous injection);
- protective airway reflexes remain intact in the majority of patients – vomiting may however occur: staff should be ready to suck clean the mouth and secure the airway;
- maintains cerebral blood flow;
- particularly suitable for infants.

17.4.2 Ketamine i.m. and i.v. bolus

A simple form of ketamine administration is represented by both the intramuscular and the bolus intravenous routes. Table 17.2 compares the two.

	Ketamine i.m.	Ketamine i.v. bolus
Indications	Short duration operation (10 – 20 minutes) Anaesthesia in children (injected while the mother is holding the infant) Repeated injections for change of dressings in burn patients with poor i.v. access	Short duration operation (10 – 20 minutes) Induction of anaesthesia
Premedication	Preferable if time allows In children diazepam may be given orally or rectally	Preferable if time allows
Technique	Ketamine and atropine can be mixed in the same syringe Diazepam should be given in a separate syringe	Place an intravenous line and inject atropine Inject diluted diazepam solution very slowly over 3 minutes, until the patient becomes drowsy Inject ketamine very slowly over one minute (rapid injection can provoke respiratory arrest)
Latent period	5 – 10 minutes	Painful stimuli (skin incision) can be tolerated after one minute
Continuing anaesthesia: second dose	Second injection can be given if necessary before the effect of the first wears off	After 10 – 15 minutes, the patient begins to feel pain and reacts to stimuli with movements and speech – not to be confused with normal movements under ketamine Administer another i.v. bolus: one-third to one-half the initial dose

Table 17.2 Comparison of ketamine anaesthesia administered intramuscularly versus intravenous bolus.

In special circumstances (repeated ketamine anaesthesias with "ketamine-resistance" and/or disturbing limb movements), one or more of the following may be added according to the reaction of the individual patient:

- 50 – 100 mg tramadol or 5 –10 mg morphine,
- 10 – 25 mg promethazine,
- 50 – 100 mg thiopental.

17.4.3 Ketamine infusion anaesthesia

This is the preferred technique in ICRC practice. It is not only more economical of ketamine, but allows for a longer operation without re-injections. It can be used either after i.v. bolus induction of anaesthesia or as an induction method on its own.

A solution is made of ketamine in normal saline and placed in a different vein from that used for fluid replacement. The rate of infusion is titrated against the patient's response, both for induction and as maintenance of anaesthesia.

Ketamine infusion anaesthesia can be combined with muscle relaxants and endotracheal intubation. This is standard ICRC procedure where muscle relaxation is necessary (abdominal or thoracic surgery). As mentioned previously, the absence of mechanical ventilators means that the paralysed patient must be bagged manually.



ICRC

Figure 17.3
Ketamine infusion.

ICRC EXPERIENCE

The Senior Anaesthetists Workshop recommended that, in exceptional circumstances (extreme emergency with a very small ICRC surgical team, no training of local staff intended, equipment to be withdrawn afterwards), the ICRC deploy small portable ventilators "to free the hands" of the anaesthetist. These ventilators must be able to function with an oxygen concentrator (there must be a regular supply of electricity) rather than with compressed air or oxygen. They were sent to Banda Aceh, Indonesia, after the 2006 tsunami hit this conflict-affected area because of an "epidemic" of tetanus cases encountered there.

Hallucinatory side effects do occur with ketamine, and once encountered are likely to be repeated on other occasions in the same patient. The frequency of hallucinations tends to differ with different population groups, and bizarre reactions may occur in heavy users of alcohol or other drugs. In addition, such patients do not reach the required state of general anaesthesia unless a neuroleptic and opioid are added.

The incidence and severity of hallucinations can be lessened by using diazepam 10 mg i.v. at least 5 minutes before induction and another 10 mg i.m. at the end of the procedure. After the operation, patients often sleep for hours. They should be in a calm and quiet place. On awakening, they respond to orders "show your tongue" or "raise your head". Sometimes these patients are very loud, they shout or sing, and move a great deal. This is normal and not dangerous for them.

17.4.4 Ketamine analgesia

The analgesic effect of ketamine can be profitably used for a number of conditions. One noteworthy example is for repeated change of dressings in burn patients. For analgesia, a lower dose than that given for intramuscular anaesthesia is administered to those whose venous access is compromised, as is often the case with major burns (see Annex 17. A: ICRC pain management protocols).

17.5 Post-operative pain management

Good post-traumatic or post-operative pain relief not only helps to alleviate suffering, but also allows for rapid mobilization of the patient and early physiotherapy which help attain as good a functional result as possible.

17.5.1 General guidelines

1. Analgesia should be given *before* the pain starts.
2. Combination therapy is recommended. Analgesic drugs have a better effect in combination than alone; e.g. paracetamol and a NSAID have additive actions because of their different sites of action.
3. Local anaesthetic infiltration or blocks are used whenever appropriate in conjunction with other forms of analgesia.
4. Injectable analgesics act more quickly and are more effective if administered as an i.v. bolus, titrated until the desired effect has been achieved. This is especially true in case of hypovolaemia and shock where the peripheral circulation is decreased and, therefore, the intramuscular or subcutaneous routes are unreliable.
5. The choice of drugs is made with the staff and facilities in mind; e.g. opioids may be undesirable if proper monitoring is unavailable.
6. It is advisable to institute a system of pain scoring, especially for post-operative pain relief.

17.5.2 Pain scoring systems

Pain intensity can be measured in various ways and the use of a system of measurement is recommended. The choice of scoring system depends on a number of factors, including cultural issues and the level of literacy and numeracy of patients and the nursing staff. In all of them it is the patient who assesses the intensity of pain.

Common scoring systems include the following.

Verbal score
The pain intensity is measured using words:
- none
- mild
- moderate
- severe
- extreme

Number scale
Numbers from 0 to 10 should be used:
- 0 means no pain and 10 the worst pain imaginable.

Visual analogue score
This is analogous to the number scale. The pain intensity is measured on a 10 cm line. The left end indicates "no pain" and the right-hand side means "the worst pain imaginable". The distance in cm from the left edge to the point the patient indicates is the pain score.

The availability of particular drugs for pain relief in a given country is often subject to importation and distribution restrictions. The widespread abuse of opioids in particular has created many problems in the proper management of patients. Annex 17. A includes various alternatives that may be used according to the availability of various medications. These must of course be adapted to specific situations.

ANNEX 17. A ICRC pain management protocols

Analgesic drugs

Modern analgesics can be very sophisticated, and expensive. The ICRC has the following simple analgesic drugs available for each of the three WHO levels:

Level 1:
Paracetamol tablets/syrup, aspirin tablets/injection, the non-steroidal anti-inflammatories (NSAID) diclofenac injection and ibuprofen tablets;

Level 2:
Tramadol injection/tablets;

Level 3:
Morphine injection, pethidine injection, pentazocine injection/tablets.

Opioids

1. When level 3 opioids are used in a hospital, naloxone must also be immediately available.

2. Morphine remains the gold standard for pain relief, intra-operatively as well as pre- and post-operatively.

3. The use of opioids – morphine and pethidine, but not tramadol – may be severely restricted because of the risk of respiratory depression. ICRC surgical teams use opioids only if nursing staff are sufficient in numbers and trained in patient monitoring, as well as in recognition and treatment of respiratory depression. In practice this will usually mean that post-operative opioids are only used in the recovery ward or intensive care unit (ICU).

4. Do not mix opioids (e.g. tramadol and morphine) until an appropriate time has lapsed.

5. In the emergency room, operating theatre and recovery area/ICU, the preferred route for opioid administration is intravenous. If they are used in the ward, the oral or subcutaneous routes are preferred.

6. The fear of addiction when using opioids for pain relief, although a generally held belief, is exaggerated; if a patient is in pain and needs an opioid, the development of addiction is extremely rare. The fear of addiction must not stop good pain control.

7. Sedation score: when using level 3 opioids the level of sedation should be monitored.
   0 = none: patient awake and alert
   1 = mild: occasionally drowsy, but easy to rouse
   2 = moderate: frequently drowsy, but easy to rouse
   3 = severe: drowsy and difficult to rouse
   S = sleep: normal sleep and easy to rouse

Monitoring, diagnosis, and treatment of respiratory depression

When using level 3 opioids the patient must be monitored regularly for:

- blood pressure
- pulse
- temperature
- respiratory rate
- sedation score
- pain score

All findings must be documented.

Respiratory depression

1. Diagnosis

   Respiratory depression is diagnosed by:
   - sedation score of 3: this is the earliest and most reliable sign;
   - respiratory rate 8 or less: this comes later than sedation;
   - decreasing pO_2, as shown by pulse oximetry: this is a late sign especially if the patient is also being given oxygen.

2. Treatment:
   - oxygen;
   - respiratory assistance with bag and mask if necessary;
   - naloxone i.v. in 50 mcg increments until clinical signs improve.

Remember that the duration of action of naloxone is shorter than morphine and therefore it may need to be repeated; alternatively, use a continuous infusion of 1 – 5 mcg/kg/hr.

Never must a patient be discharged to the ward with a sedation level of 3 or more, or a respiratory rate of 8 or less, or if respiratory depression has occurred.

Ketamine

A low dose of ketamine is a good alternative analgesic where opioids are not available or for high-risk patients. Give repeated doses 0.1 – 0.3 mg/kg i.v., titrated until the desired analgesia is achieved; or an i.m. bolus of 2 – 3 mg/kg. Ketamine in a low dose does not require routine atropine and diazepam as adjuvant therapy.

Pre-hospital care

For pre-hospital first aid, often through National Red Cross/Red Crescent Societies, ICRC distributes only:

- paracetamol tablets/syrup;
- tramadol injection (does not provoke respiratory depression).

Emergency room

The following are available in the emergency room:

- paracetamol
- diclofenac injection
- tramadol injection

In a hospital with adequate nursing care, the following are also provided:

- morphine injection
  - adult: 1 – 3 mg i.v. titrated
  - child: 0.05 mg/kg i.v. titrated
- low-dose ketamine (see above).

Operating theatre

All analgesic drugs are available and their intra-operative use is greatly encouraged. The choice of drug depends to a large extent on the quality of post-operative monitoring.

1. Opioids:

   note the level of post-operative monitoring.

2. NSAID:

   it is advisable to administer an NSAID before the end of surgery.

3. Ketamine:

   0.1 – 0.3 mg/kg boluses as analgesia can be used if opioids are unavailable.

4. Local and regional anaesthesia:

   The use of local anaesthetic infiltration or local and regional blocks is greatly encouraged.

Post-operative pain control

The level of pain control needed depends on the psychology of the patient, the type of surgery, and the time since surgery. The basic principles of post-operative analgesia are the following.

1. Give analgesia regularly and not on an as necessary basis (PRN).
2. Do not wait for the pain to be felt, but start immediately once the patient has regained consciousness. This also means that analgesia should be started before spinal anaesthesia has worn off.
3. Start with combination treatment and decrease doses in subsequent days.
4. Review post-operative analgesia regularly.
5. Use local anaesthetic infiltration or blocks as much as possible.

MILD PAIN

Paracetamol
+
Local infiltration or block

MODERATE PAIN

Paracetamol
+
NSAID
+
Local infiltration or block

SEVERE PAIN

Paracetamol
+
NSAID
+
Opioid
+
Local infiltration or block

the collection points, are brought into the pakuas which act as transformers. They can be blended with the positive energies from the organs as well as the energies from the universe, so that they become purified and enriched; energies of a higher quality and order can be generated. These then may be condensed into a pearl as the embryo of our energy body (Fusion of the Five Elements, Formula 5).

Raising the Quality of Our Energies

The Cosmic Fusion Practices basically serve to consolidate, stabilize and enhance the process towards balance, initiated in the Fusion of the Five Elements practices. The creative cycle practice of Cosmic Fusion specifically serves to further the growth of positive energies in the organs and glands, which in turn will be able to mutually support each other to create a higher quality of energy. This energy is concentrated in the compassion energy from which a pearl is formed. Only when all the positive energies merge into the fire of love and compassion by which the sexual energy is steamed and is transformed, its energy will turn into a higher creative and spiritual energy. This higher energy will then serve to nourish the energy body.

This pearl will be more powerful in healing and cleansing the body than the pearl in the Cosmic Fusion practice and may subsequently serve to create and nourish the energy body. The energy body may in the highest practices give birth to the spirit body. The Cosmic Fusion practice also serves to intensify the process of cleansing and healing through the creation of the three Thrusting Channels and by creating the the nine Belt Channels which serve to protect the body and its energies from negative influences.

Marriage of the Light from Within and from Above

All Universal Tao practices, including the Fusion Practices, consist of two dimensions. One is the activity which focuses on the processes of transformation within the body through cleansing, opening, healing and fortifying the body and raising the quality of its energies. The other activity is to get in touch with the universe, the cosmos and nature and attract their energies and the Light in which they originate towards the body so that the body may process these energies and blend them with its own refined energies.

Analgesic doses

ADULT			
PARACETAMOL	oral	1 g QID Max. 4 g/day	
IBUPROFEN	oral	400 mg TID/QID Max. 2.4 g/day	Caution in cases of asthma and renal impairment Max. 72 hours
DICLOFENAC	i.v./i.m.	75 mg BID Max. 150 mg/day	Caution in cases of asthma and renal impairment Max. 72 hours
TRAMADOL	oral/i.v.	50 – 100 mg 4 hourly Max. 600 mg/day	
PETHIDINE	i.m.	50 – 150 mg 3 hourly	
	i.v.	10 mg increments	Titrate to effect
MORPHINE	subcutaneous / i.m.	5 –15 mg 4 hourly	
	i.v.	2 mg increments	Titrate to effect
NALOXONE	i.v.	50 mcg increments	Repeat until clinical signs improve

PAEDIATRIC			
PARACETAMOL	INFANTS (0 – 12 months)		
	oral / suppository if available	Loading dose: 15 mg/kg Maintenance: 10 – 15 mg/kg QID Max. dose: 60 mg/kg/day	
	CHILDREN		
	oral / suppository if available	Loading dose: 20 – 30 mg/kg Maintenance: 20 mg /kg QID Max dose: 90 mg/kg/day	
IBUPROFEN	oral	20 mg/kg/day in 3 – 4 divided doses Max. single dose: 200 mg Max. daily dose: 800 mg	Not under 6 months (immature kidneys) Caution in cases of asthma and renal impairment Max. 72 hours
DICLOFENAC	i.m.	1 mg/kg TID Max. single dose: 50 mg Max. daily dose: 150 mg	Not under 6 months (immature kidneys) Caution in cases of asthma and renal impairment Max. 72 hours
TRAMADOL	Not recommended, but commonly used in some European countries for children under 1 year		
PETHIDINE	i.m.	1 mg/kg 4 hourly	
	i.v.	0.25 – 0.5 mg/kg increments	Titrate to effect
MORPHINE	subcutaneous / i.m.	0.05 – 0.1 mg/kg 4 hourly	
	i.v.	0.05 mg/kg increments	Titrate to effect
NALOXONE	i.v.	4 mcg/kg	Repeat until clinical signs improve

BID: *bis in die* (twice a day)

QID: *quater in die* (four times a day)

TID: *tri in die* (three times a day)

Chapter 18

DAMAGE CONTROL SURGERY AND HYPOTHERMIA, ACIDOSIS, AND COAGULOPATHY

18. DAMAGE CONTROL SURGERY AND HYPOTHERMIA, ACIDOSIS, AND COAGULOPATHY

18.1 Resuscitative surgery and damage control surgery 321
18.1.1 Damage control: three-stage protocol 321

18.2 Hypothermia, acidosis, and coagulopathy 322
18.2.1 Hypothermia 323
18.2.2 Acidosis 326
18.2.3 Acute coagulopathy associated with trauma 326

18.1 Resuscitative surgery and damage control surgery

Resuscitative surgery has long been practised, and re-invented by many surgeons beginning with Pringle in 1908 and Halstead in 1913. Today, this is especially the case in critical situations where blood for transfusion is in short supply. The surgeon controls massive haemorrhage with temporary measures and then stops the operation. The patient is taken to the ward to continue resuscitation and, 24 – 48 hours later when haemodynamically stable, is re-operated for the definitive procedure.

ICRC EXPERIENCE

Afghan colleagues working with ICRC surgical teams in the Jalalabad Teaching Hospital in 1993 developed a simple protocol for dealing with patients severely injured by anti-personnel landmines. Many patients had suffered a traumatic amputation of one leg and severe injuries to the other and succumbed, exsanguinated, by the time the debridement of the second leg had been performed.

Our Afghan colleagues then decided to divide the surgical procedure into two parts: the first operation was on the traumatic amputation, the other leg was simply washed and dressed, and the operation ended. Fresh whole blood was sought from family members and the patient fully resuscitated and given penicillin. Forty-eight hours later, another operation to debride the second leg was performed. This was Afghan "damage control surgery", locally invented, to face the situation of a lack of blood for transfusion.

Shortly after a war surgery seminar in Kinshasa, two young Congolese general practitioners belonging to the military medical services, with limited surgical expertise, told the ICRC surgeon of one of their experiences and asked a simple question. While working in a field hospital in the bush, they received a comrade with a bullet injury to the abdomen. Evacuation to another hospital was impossible. They operated and found a severe wound to the liver, and had no blood for transfusion.

"We couldn't stop the bleeding, and not knowing what to do, we packed the liver and stopped the operation", they recounted. They then managed to persuade some other soldiers to donate several units of blood, and re-operated the patient after 48 hours; the patient survived. "Did we do the right thing?" they asked. The ICRC surgeon replied that they had discovered on their own what was now standard practice in many parts of the world when faced with exsanguinating haemorrhage.

18.1.1 Damage control: three-stage protocol

Recently, it has become clear that fixing the tissues and organs during a long operation is not sufficient if certain physiological limits are thereby exceeded.

In response, a three-stage protocol for "damage control surgery"[1] has been defined to preclude the risk of pushing the patient beyond those limits into the "lethal triad" of hypothermia, metabolic acidosis, and coagulopathy that follows much major trauma.

First stage:
Operation, as short as possible, to control haemorrhage and contamination: do the least to overcome life-threatening conditions.

Second stage:
Resuscitation, to stabilize the patient by correction of shock, hypothermia, acidosis, and coagulopathy.

Third stage:
Operation, for definitive repair.

---

[1] "Damage control" is originally a United States Navy term denoting "the capacity of a ship to absorb damage and maintain mission integrity". In surgery, we mean the procedures necessary to maintain the physiological capacity to maintain life's vital functions.

The success of this formalized protocol depends almost entirely on the early recognition that the injury is so severe as to require a curtailment of the initial operation; and, especially, the second-stage capacity to correct certain physiological parameters in the intensive care unit (ICU).

Damage control surgery is obviously restricted to the very severely injured, a small minority. It is a much individualized form of management requiring many resources, and may not be compatible with a situation of triage of mass casualties. The patient who qualifies for damage control in a civilian context, or in a military one with a small number of casualties, will in many cases be triaged into the expectant Category IV in a war scenario.

In much of the world, sophisticated ICUs and blood components are simply not available and a full-scale damage-control approach is not compatible with limited resources. However, basic principles apply and simple measures can and must be adapted to try to prevent and correct the syndrome of the lethal triad.

In the two examples cited above, the time between operations – used to obtain fresh whole blood from family and friends and "stabilize" the patient – helped to fight hypothermia, acidosis, and coagulopathy without knowing it. Attention was paid only to the haemodynamics and the comfort of the patient (keeping him warm), but this was sufficient to overcome the triad. What started as a "resuscitative surgery" approach became a "damage control" one unknowingly.


ICRC

Figure 18.1

Typical patient who would benefit from a damage control approach: eventration and a shattered liver.


R. Gray / ICRC

Figure 18.2

Another candidate for damage control surgery: APM injury with penetrating wounds to the abdomen, thorax, left thigh and hand, and the face.


ICRC

Figure 18.3

Patient with APM blast mine injury: traumatic amputation of the left foot, penetrating injuries and burns to both legs, the perineum and genitalia, with penetration of the abdomen.

18.2 Hypothermia, acidosis, and coagulopathy

The effects of hypothermia in trauma patients have long been underestimated. It afflicts the injured even in tropical climates. While metabolic acidosis due to shock – the anaerobic metabolism resulting from reduced tissue perfusion and hypoxia – and coagulopathy are better known, the combined triad is far more prevalent than is often realized and its effects easily fatal. These three elements compound and reinforce each other, leading to a self-sustaining vicious circle. Haemorrhagic shock may not be corrected until hypothermia is reversed, and hypothermia can provoke the other two elements of the triad and is probably the most important factor initiating the vicious circle.

Early diagnosis is essential but simple preventive measures, that should be initiated during first aid and evacuation and continued in the hospital, are often not taken. Even if the context does not allow for staged damage control surgery, a great deal can be done with adequate but appropriate means to prevent or fight off the effects of the triad.

18.2.1 Hypothermia

Physiology

The body's temperature is kept in a homeostatic balance between heat production and heat loss. There are many non-traumatic causes and factors that can lead to hypothermia; cold injuries were discussed in Chapter 16. In trauma patients, haemorrhagic shock decreases tissue perfusion and metabolism and thus heat production. This is often compounded by exposure of the casualty to the elements, particularly in a context of armed conflict.

> It should be taken as a general rule that every injured person will lose body heat, even in a tropical climate.

Hypothermia is determined by central body – core – temperature, taken *per rectum*. A normal medical thermometer is useless; a special low-reading one beginning at 30° C is necessary. Classically, a core temperature below 35° C denotes hypothermia and medical classifications reach profound states of 25° C or less (immersion in a cold lake, hypothalamic disorders, drug abuse, etc.). Some patients suffering from severe hypothermia do survive. There are also reported beneficial effects of controlled therapeutic hypothermia in certain critical pathologies, but this topic shall not be considered here.

Pathology

It is very rare for patients suffering trauma *and* uncontrolled hypothermia lower than 32° C to survive. This observation is not new, although the threshold has changed.

> "It has been said that any wounded man in a state of stupor whose temperature sinks below 36° C will die."
>
> E. Delorme, 1915[2]

In modern practice, the temperature of 32° C is recognized as the crucial cut-off point. All enzyme systems in the body are temperature dependent and, therefore, all organ systems will tend to fail at this low core temperature, especially if stress is accentuated by trauma and shock.

Thus, medical classification systems of hypothermia with wide ranges of temperature are not suitable for the trauma patient. A more appropriate classification system has been proposed (Table 18.1), and takes into account the profound effects of trauma and haemorrhage with concomitant acidosis and coagulopathy. In the trauma patient, any temperature below 36° C should be considered hypothermic and it is particularly important to distinguish between Stage I and Stage II. A damage-control approach, with abbreviated first operation as mentioned above, is indicated at 34° C, now considered the critical clinical temperature.

General medical classification		Trauma classification	
Mild	35° – 32° C	I	36° – 35° C
		II	34° – 32° C
Moderate	32° – 28° C	III	32° – 28° C
Severe	28°– 20° C	IV	< 28° C
Profound	< 20° C		

Table 18.1 Classification systems of hypothermia.[3]

---

[2] Delorme E. *War Surgery*. [Translated by Méric H.] London: H.K. Lewis; 1915. [WWW Virtual Library, The Medical Front WWI website] Available at: http://www.vlib.us/medical/delorme/delorme.htm.

[3] Adapted from Kirkpatrick AW, Chun R, Brown R, Simons RK. Hypothermia and the trauma patient. *Can J Surg* 1999; **42**: 333 – 343.

The *clinical effects* of hypothermia are multiple and mimic intense sympathetic stimulation:

- shivering – the patient attempts to produce body heat by these muscular contractions but this leads to increased oxygen consumption and tissue hypoxia;
- hypoventilation – leads to postoperative hypoxaemia, with further tissue hypoxia;
- peripheral vasoconstriction – to shunt blood to the central organs, with tissue hypoxia;
- decreased oxygen liberation in the tissues (O_2 dissociation curve shifted to the left);
- decreased metabolism.

Furthermore, the tissue hypoperfusion and hypoxia of shock in the trauma patient also increase anaerobic metabolism. All of which result in a mixed metabolic and respiratory *acidosis*.

Enzyme failure results in compromised platelet function; platelet-fibrin clots are not sustained; and fibrinolytic activity is increased. There is dramatic prolongation of prothrombin time (PT) and partial thromboplastin time (PTT).

Please note:

Prolonged PT and PTT may be overlooked because the testing is performed at 37° C rather than at the patient's actual temperature.

There is in addition a rapid drop in the number of platelets and increased blood viscosity following shock. The end result is a disseminated intravascular *coagulopathy* with a marked bleeding tendency.

Other physiological effects include:

- decreased immune response;
- hyporeflexia and prolonged action of neuro-muscular blockers;
- reduced cardiac output, depressed contractility and bradycardia;
- arrhythmias, including atrial and ventricular fibrillation, which begin at 30° C;
- impaired hepatic and renal function;
- impaired cerebral blood flow with decreasing consciousness.

Clinical picture

Early signs include shivering and tremors; the patient first complains of cold then becomes confused. There is cyanosis and the axilla and groin (normally warm spots) feel cold to the touch because of intense vasoconstriction. Tachycardia and tachypnoea (with hypoventilation) occur. All are signs of sympathetic stimulation. Making the diagnosis of hypothermia is a challenge because *most of the early signs* are the normal physiological response to the stress of trauma and haemorrhage; the surgeon should be particularly attentive to the presence of shivering and tremors. It is also difficult to judge clinically when the patient passes from Stage I to II without close monitoring of the rectal temperature.

As the patient goes into Stage III, there is a general slowing down of all the vital functions:

- loss of shivering and hyporeflexia;
- respiratory and circulatory depression;
- decreased urine output;
- increasing acidosis;
- prolonged clotting time;
- stupor; and,
- with myocardial ischaemia, the onset of attacks of atrial fibrillation.

With even greater hypothermia the patient becomes unconscious; bradycardia and bradypnoea are pronounced; urine output fails; and ventricular fibrillation resistant to defibrillation occurs. The patient may appear dead: no palpable pulse or heart beat and dilated pupils. Re-warming should continue until a core temperature of at least 33° C before pronouncing death.

High risk cases

At high risk of developing post-traumatic hypothermia are patients who have:

- been severely injured and are submitted to a long delay in evacuation to hospital;
- remained trapped under rubble (earthquake, collapsed buildings due to bombing, etc.), and thus been exposed to the environment without being able to take protective measures for a considerable period of time;
- sustained major burns;
- suffered haemorrhagic shock treated with large quantities of room temperature intravenous perfusions or cold transfusions – banked blood is stored at 4° C and its administration acts as a heat sink that withdraws large amounts of body heat;
- been subjected to long, extensive laparotomy or thoracotomy in air-conditioned operating theatres – the surgeon and anaesthetist are comfortable, but the patient is dying;
- suffer from chronic illnesses involving metabolism, alcoholism, and drug abuse; and
- the very young and very old, in general.

Please note:

These high risk factors are partly intrinsic to the patient and partly iatrogenic.

Management

Treatment begins with active measures of prevention during first aid and evacuation: the casualty must be kept warm! The patient must be sheltered from cold and wind, relieved of wet clothing, and covered with a dry blanket or sheet, even in a tropical climate.

In hospital, active preventive measures must continue: the emergency room should be kept thermo-neutral (28° C for an adult) and, after the patient has been undressed, examined, and resuscitative measures begun, covered with a blanket. For the severely injured, further environmental measures should continue. In the operating theatre, air-conditioning should be turned off (the OT should be heated if necessary), and prolonged contact with wet drapes avoided. The impact of the latter should not be underestimated: the patient starts off dry and warm and ends up wet and hypothermic.

A patient shivering on the operating table is a clear warning sign!

Under muscle relaxant anaesthesia, a patient can no longer shiver and is particularly at risk. Since 20 – 30 % of body heat is lost through the head and neck, keeping these body parts warm is a priority (e.g. wrapping the head in a towel and plastic bag intra-operatively). The rest of the body, apart from the operative site, can equally be wrapped in dry towels and secured with plastic bags to preserve heat. Warm saline should be used for peritoneal or pleural lavage. Operating time should be kept as short as possible; an open abdomen or thorax inevitably entails loss of body heat which is just as critical at this stage as blood loss.

Administered oxygen should be humidified – a heat and moisture exchange filter (HME) should be used, if available – and intravenous fluids and blood transfusions warmed. Fluids and blood can be heated by being placed in a tub of hot water, comfortable to an elbow touch.

All of these simple measures, which do not require sophisticated equipment, should be standard procedure in all surgical patients, especially those suffering from trauma.

Not only will these simple measures prevent hypothermia, but their early implementation will help treat the condition.

If a damage-control approach is being used, or even if a major trauma case presents signs of hypothermia postoperatively, resuscitation should include active internal "central heating" of the patient by:

- gastric, colonic and bladder lavage with warm water (37 – 39° C); and
- continued perfusion of similarly warm i.v. fluids.

More sophisticated technologies exist – including extracorporeal circulation, pleural and peritoneal lavage in the ICU – but the vast majority of patients will be well served by these simple and inexpensive preventive and active measures.

A patient in Stage I hypothermia may have definitive surgery completed. A Stage II patient should have damage control surgery only. If Stages III or IV have been reached, damage control surgery may be slightly postponed in order to warm the patient somewhat before opening the peritoneum or pleura, but this will depend on the particular circumstance and haemodynamic stability of the individual patient. Again: rare is the haemorrhaging trauma patient with a core temperature below 32° C who survives, however good the surgery.

Type of measures	Procedures	Applicability
Standard measures	Passive external warming (warm environment, blankets and covers) + warmed intravenous fluids + warmed and humidified oxygen	Standard measures are applicable for all Stages and at all times
Active external warming	Electric blankets Environmental heater	Particularly suitable for ICU/ emergency room
Active internal warming intraoperatively	Irrigation of pleural/peritoneal cavity with warm saline during surgery	Should be routine surgical procedure
Active internal warming postoperatively	Warm gastric, colonic, and bladder lavage Warm pleural/peritoneal lavage if feasible	Particularly suitable for ICU

Table 18.2 Summary of management of hypothermia in the trauma patient.

18.2.2 Acidosis

As mentioned, shock will lead to tissue hypoperfusion and hypoxia with a subsequent rise in anaerobic metabolism. This acidosis is compounded by the effects of hypothermia. Full resuscitation and haemodynamic stability in a warm patient, assuring good tissue perfusion, is the best antidote. Intravenous sodium bicarbonate is risky and requires sophisticated monitoring.

18.2.3 Acute coagulopathy associated with trauma

Post-traumatic coagulopathy is also more common than realized and results from a combination of intrinsic and extrinsic factors. Amongst the intrinsic ones, the most important include:

- extensive tissue injury, which releases tissue factors resulting in consumption coagulopathy (with reduced platelet count), excessive fibrinolysis, and activation of inflammatory cascade;
- activation of the C-reactive protein inflammatory cascade independently of the release of tissue factors and entirely due to the shocked state and tissue hypoperfusion;
- haemodilution resulting from the mobilization of extravascular fluids as a homeostatic response to shock;
- decrease in the total and ionized calcium concentrations; and
- the effects of progressive hypothermia and acidosis.

The severity of the coagulopathy seems to parallel the severity of injury and shock.



***Fig. 9.10** Connecting with the Universe*

The Taoist view is that the body by its very nature and structure is a microcosmos which is able to attract and receive and use the energies from the universe, the cosmos and nature to transform itself. Quantum physics confirms the view that the mind is faster than light and that consciousness is a form of energies which can move other energies when tuning into these energies and their frequencies.

The process of getting in touch with the universe and expanding love and compassion begins in the same way as the approach to inward transformation of energy: with smiling, feeling and sensing and radiating out love energy. The cleaner and finer the energy which is emitted, the higher the response from the forces and energies from above, below and around us. The relationship with the universe has been likened with that of a love or courting relationship. In all the mystical traditions the experience of the divine is also experienced as a relationship between the lover and the beloved. Frequently such relationships have been expressed by the great mystics in the most erotic and sensuous language, a reason for which they were as a rule hardly accepted and frequently persecuted.

Important factors resulting in post-traumatic coagulopathy:

- tissue damage
- shock: hypoperfusion and homeostatic haemodilution
- hypothermia
- acidosis
- inflammation
- therapeutic haemodilution with i.v. fluid resuscitation

There are also a number of extrinsic factors. Coagulopathy itself is often exacerbated by clinical practice in a "bloody vicious cycle".[4] Haemorrhagic shock is aggressively treated with large volumes of intravenous fluids (not warmed), leading to further haemodilution, and massive transfusion of stored blood or packed RBCs (not warmed) in the attempt to maintain blood pressure (see Chapter 8); all of which adversely affect the coagulation cascade and only produce more bleeding. Bleeding and coagulation times remain prolonged despite adequate replacement of blood, plasma and platelets if the patient remains hypothermic.

It must also be remembered that the anticoagulant preservative solution and refrigeration of stored blood or its components has profound effects on the physiological properties of transfused blood with time, the most important being greatly reduced oxygen availability to the tissues through decreased 2,3-diphosphoglycerate (2,3-DPG) and loss of red cell viability because of decreased adenosine triphosphate (ATP). These effects do not help overcome early tissue hypoxia in spite of the increase in haemoglobin. In addition, the glucose in stored blood is slowly metabolized with production of lactate and fall in the pH, exacerbating the acidosis.

Warm whole blood, as fresh as possible, is probably the best treatment; and, as often repeated in this manual, in conditions of limited resources is often all that is available. With numerous potential donors (family and friends), it may be possible to build up a small reserve.

Whole blood is screened and best given within 1 hour of collection. In ICRC practice, this freshest of blood is reserved for:

- massive haemorrhage, with incipient coagulopathy and hypothermia;
- septic shock;
- snake bites with haemolysis;
- amniotic fluid embolism.

Intravenous calcium should be administered, separately and at least one ampoule added per two units of blood transfused.

Coagulopathy also attends many patients with severe head injury, and a damage control approach is applicable to injuries to most body systems. Volume 2 will include relevant observations in the discussion of war injuries to the different anatomic regions.

---

[4] Kashuk J, Moore EE, Milikan JS, Moore JB. Major abdominal vascular trauma – a unified approach. *J Trauma* 1982; **22**: 672 – 679.

ACRONYMS

ABCDE	Airway, Breathing, Circulation, Disability, Environment/Exposure
APM	Anti-personnel mine
ARDS	Acute respiratory distress syndrome
ATM	Anti-tank mine
ATP	Adenosine triphosphate
AVPU	Alert, Voice responsive, Pain responsive, Unresponsive
BID	*Bid in die* (twice a day)
CFR	Case fatality rate
CPD-A	Citrate – phosphate – dextrose – adenine
CRO	Carded for record only
CT	Computerized tomography
DOA	Dead on arrival
DOW	Died of wounds
DPC	Delayed primary closure
2,3-DPG	2,3-diphosphoglycerate
E_K	Kinetic energy
$E_{K\ EXP}$	Kinetic energy actually expended, transferred or dissipated
ECG	Electrocardiogram
EDTA	Ethylene diamine tetra-acetic acid
EEG	Electroencephalogram
ER	Emergency (reception) room
FAP	First-aid post
FMJ	Full metal jacket
FST	Field surgical team
GC	Geneva Convention
GCS	Glasgow coma scale
GSW	Gunshot wound

H.E.L.P.	Health emergencies in large populations
HIV/AIDS	Human immunodeficiency virus / Acquired immunodeficiency syndrome
HME	Heat and moisture exchange (filter)
HN	Head nurse
ICRC	International Committee of the Red Cross
ICU	Intensive care unit
IED	Improvised explosive device
IHL	International humanitarian law
i.m.	Intramuscular
i.v.	Intravenous
IU	International unit
KIA	Killed in action
LF	Low frequency
mEq	Milliequivalents
MIU	Million international units
MoPH	Ministry of Public Health
MRSA	Methicillin-resistant *Staphylococcus aureus*
MSF	Médecins sans frontières (Doctors Without Borders)
NATO	North Atlantic Treaty Organization
NGO	Non-governmental organization
NSAID	Non-steroidal anti-inflammatory drug
OPCW	Organization for the Prohibition of Chemical Weapons
OPD	Outpatient department
ORS	Oral rehydration salts
OT	Operating theatre
POP	Plaster of Paris
POW	Prisoner of war
PRN	*Pro re nata* (whenever necessary)
PT	Prothrombin time
PTT	Partial thromboplastin time
QID	*Quater in die* (4 times per day)
RBC	Red blood cell
RC/RC	Red Cross/ Red Crescent
RCWS	Red Cross Wound Score
RTD	Returned to duty
SJ	Semi-jacketed
SSG	Split-skin grafts
TBSA	Total body surface area

TID	*Ter in die* (3 times per day)
TNM	Tumour, node, metastasis
TO	Triage officer
TTL	Triage team leader
UN	United Nations
UNPROFOR – IFOR	United Nations Protection Force – (NATO) Implementation Force
UXO	Unexploded ordnance
WDMET	Wound Data and Munitions Effectiveness Team
WHO	World Health Organization
WIA	Wounded in action

SELECTED BIBLIOGRAPHY

General texts

Please note:

The publications listed under general texts serve as basic references throughout this manual.

Military publications

Kirby NG, Blackburn G, eds. *Field Surgery Pocket Book*. London: Her Majesty's Stationery Office; 1981.

Roberts P, ed. *The British Military Surgery Pocket Book. (AC 12552)* Camberley, Surrey, UK: Department of Military Surgery, Army Medical Directorate; 2003.

Bowen TE, Bellamy RF, eds. *Emergency War Surgery NATO Handbook Second United States Revision*. Washington, DC: US Department of Defense; 1988.

Lounsbury DE, Brengman M, Belamy RF, eds. *Emergency War Surgery Third United States Revision*. Washington, DC: Borden Institute, US Department of Defense; 2004. Available at: http://www.bordeninstitute.army.mil/other_pub/ews.html.

Nessen SC, Lounsbury DE, Hetz SP, eds. *War Surgery in Afghanistan and Iraq: A Series of Case Studies, 2003 – 2007*. Washington, DC: Office of the Surgeon General, Borden Institute, US Department of Defense; 2008.

Pons J, ed. *Memento de chirurgie de guerre [War Surgery Primer]*. Paris: Ecole d'application du Service de santé pour l'armée de terre, ORA éditions; 1984.

War Surgery Commission of the Federal Military Department. *Chirurgie de guerre (Aide-mémoire 59.24 f) [War Surgery (A Primer)]*. Bern: Swiss Army; 1970 and 1996.

Civilian publications

Courbil L-J, ed. *Chirurgie d'urgence en situation précaire [Emergency Surgery under Precarious Circumstances]*. Paris: Editions Pradel; 1996.

Geelhoed GW, ed. *Surgery and Healing in the Developing World*. Georgetown, TX: Landes Bioscience; 2005.

Husum H, Ang SC, Fosse E. *War Surgery: Field Manual*. Penang, Malaysia: Third World Network; 1995.

Loefler I. Africa – Surgery in an unstable environment. Weary Dunlop Memorial Lecture. *Aust NZ J Surg* 2004; **74**: 1120 – 1122.

Mahoney PF, Ryan JM, Brooks AJ, Schwab CW, eds. *Ballistic Trauma: A Practical Guide 2nd Edition*. London: Springer-Verlag; 2005.

Trauma surgery references

Boffard KD. *Manual of Definitive Surgical Trauma Care 2nd Edition*. London: International Association for Trauma Surgery and Intensive Care, Hodder/Arnold; 2007.

Botha AB, Brooks A, Loosemore T, eds. *Definitive Surgical Trauma Skills Manual*. London: Royal College of Surgeons of England; 2002.

Hirshberg A, Mattox KL. *Top Knife: The Art and Craft of Trauma Surgery*. Shrewsbury, UK: tfm Publishing Ltd; 2005.

Integrated Management on Emergency and Essential Surgical Care. *E-Learning tool Kit* [CD-ROM]. Geneva: World Health Organization; 2005.

King M, ed. *Primary Surgery, Volume Two: Trauma*. Oxford: Oxford University Press; 1987. Available at: http://www.primary-surgery.org/ps/vol2/html/index.html. Updated May 2, 2008.

Trauma.org. (Dedicated international trauma-interest web site.)
[Web site http://www.trauma.org].

Chapter 1

Emergency Items Catalogue of the International Movement of the Red Cross and Red Crescent. Geneva: International Committee of the Red Cross and International Federation of Red Cross and Red Crescent Societies; 2004. [CD-ROM] [online] Available at: http://www.icrc.org/emergency-items.

Bowyer GW. War surgery and the International Committee of the Red Cross: a historical perspective. *Int J Orthop Trauma* 1996; **6**: 62 – 65.

Morris DS. Surgeons and the International Committee of the Red Cross. *Aust NZ J Surg* 1992; **62**: 170 – 172.

Mulli J-C. Activités chirurgicales en zone de guerre: l'expérience du Comité international de la Croix-Rouge [Surgical activities in a war zone: the experience of the International Committee of the Red Cross]. *Bulletin Medicus Mundi* 1995; **57**: 42 – 54.

Russbach R. Les unités chirurgicales du Comité international de la Croix-Rouge: le personnel, le matériel, les coûts [Surgical units of the International Committee of the Red Cross: the personnel, the equipment, the costs]. *Médecine et Hygiène* 1991; **49**: 2629 – 2632.

Vassallo DJ. The International Red Cross and Red Crescent Movement and lessons from its experience of war surgery. *J R Army Med Corps* 1994; **140**: 146 – 154.

Chapter 2

Basic references

Dunant H. *A Memory of Solferino*. Geneva: ICRC; 1950.

The Geneva Conventions of August 12, 1949. Geneva: ICRC; 1995.

Pictet J, ed. *Commentary on the Geneva Conventions I-IV of 12 August 1949*, 4 vol. Geneva: ICRC; 1952 – 1960.

Protocols Additional to the Geneva Conventions of 12 August 1949, revised Edition. Geneva: ICRC; 1996.

Sandoz Y, ed. *Commentary on the Additional Protocols of 8 June 1977 to the Geneva Conventions of 12 August 1949*. Geneva: ICRC; 1987.

David E. *Principes de droit des conflits armés 4^{e} éd [Principles of the Law of Armed Conflicts 4th Edition]*. Brussels: Bruylant; 2008.

Gasser H-P. International Humanitarian Law: An Introduction. In: Haug H, ed. *Humanity for All*. Geneva: Henry Dunant Institute; 1993.

Kolb R. *Ius in bello, Le droit international des conflits armés [Ius in Bello, The International Law of Armed Conflicts]*. Brussels: Bruylant; 2003.

Palwankar U. *Symposium on Humanitarian Action and Peace-Keeping Operations, Geneva, June 22 – 24, 1994*. Geneva: ICRC; 1994.

IHL and the medical profession

Annas GJ. Military medical ethics – physician first, last, always. *N Engl J Med* 2008; **359**: 1087 – 1090.

Baccino-Astrada A. *Manual on the Rights and Duties of Medical Personnel in Armed Conflicts*. Geneva: International Committee of the Red Cross, League of Red Cross and Red Crescent Societies; 1982. (Out of print, under revision.)

British Medical Association. *Medicine Betrayed*. London: Zed Books; 1992.

The Medical Profession and the Effects of Weapons. Symposium: Montreux, Switzerland, 1996. Geneva: Media Natura, Geneva Foundation to Protect Health in War, International Committee of the Red Cross; 1996.

Coupland RM. Weapons intended to blind. [Editorial]. *Lancet* 1994; **344**: 1649 – 1650.

Coupland RM. Wounds, weapons and the doctor. *Schweiz Z Milit Med* 1995; **72**: 33 – 35.

Coupland RM. Abhorrent weapons and "superfluous injury or unnecessary suffering": from field surgery to law. *BMJ* 1997; **315**: 1450 – 1452.

Coupland RM. "Non-lethal" weapons: precipitating a new arms race. Medicine must guard against its knowledge being used for weapon development. [Editorial]. *BMJ* 1997; **315**: 72.

Coupland R, Herby P. Review of the legality of weapons: a new approach The SIrUS Project. *International Review of the Red Cross* 1999; **835**: 583 – 592.

Giannou C. The Mine Information System: The principal factors determining the severity of landmine infestation. Presented at the signing of the Convention on the Prohibition of the Use, Stockpiling, Production and Transfer of Anti-personnel Mines and on their Destruction; 1997 Sept; Ottawa, Canada.

Chapter 3

General references

Sellier KG, Kneubuehl BP. *Wound Ballistics and the Scientific Background*. Amsterdam: Elsevier; 1994.

Kneubuehl BP, Coupland RM, Rothschild MA, Thali MJ. *Wundballistik, Grundlagen und Anwendungen [Wound Ballistics, Basics and Applications]*. Berlin, Heidelberg, New York: Springer-Verlag; 2008. (Available in German only.)

Neuenschwander J, Coupland R, Kneubuehl B, Baumberger V. *Wound Ballistics: An introduction for health, legal, forensic, military and law enforcement professionals*. [Brochure and film on DVD]. Geneva: ICRC; 2008.

Journal articles

Bowyer GW, Cooper JG, Rice P. Small fragment wounds: biophysics and pathophysiology. *J Trauma* 1996; **40 (3Suppl.)**: S159 – S164.

Brismar B, Bergenwald L. The terrorist bomb explosion of Bologna, Italy, 1980: an analysis of the effects and injuries sustained. *J Trauma* 1982; **22**: 216 – 220.

Cheng XM, Liu YQ, Guo RF, Lian WK, Wang DT. Analysis of wound ballistics in 2,414 cases of battle casualties. *Journal of Trauma (China)* 1990; **6 (Suppl.)**: S169 – S172.

Cooper GJ, Ryan JM. Interaction of penetrating missiles with tissues: some common misapprehensions and implications for wound management. *Br J Surg* 1990; **77**: 606 – 610.

Coupland RM. Clinical and legal significance of fragmentation of bullets in relation to size of wounds: retrospective analysis. *BMJ* 1999; **319**: 403 – 406.

Coupland RM, Hoikka V, Sjoeklint OG, Cuenod P, Cauderay GC, Doswald-Beck L. Assessment of bullet disruption in armed conflicts. *Lancet* 1992; **339**: 35 – 37.

DePalma RG, Burris DG, Champion HR, Hodgson MJ. Blast injuries. *N Engl J Med* 2005; **352**: 1335 – 1342.

Fackler ML, Malinowski JA. The wound profile: a visual method for quantifying gunshot wound components. *J Trauma* 1985; **25**: 522 – 529.

Fackler ML, Bellamy RF, Malinowski JA. The wound profile: illustration of the missile-tissue interaction. *J Trauma* 1988; **28 (1Suppl.)**: S21 – S29.

Fackler ML. Wound ballistics: a review of common misconceptions. *JAMA* 1988; **259**: 2730 – 2736.

Farjo LA, Miclau T. Ballistics and mechanisms of tissue wounding. *Injury* 1997; **28 (3Suppl.)**: C12 – C17.

Hayda R, Harris RM, Bass CD. Blast injury research: modelling injury effects of landmines, bullets, and bombs. *Clin Orthop Relat Res* 2004; **422**: 97 – 108.

Hollerman JJ, Fackler ML, Coldwell DM, Ben-Menachem Y. Gunshot Wounds: 1. Bullets, ballistics, and mechanisms of injury *Am J Roentgenol* 1990; **155**: 685 – 690.

Houdelette P. Notions de balistique lésionnelle concernant les armes déflagrantes légères antipersonnel [A primer on wound ballistics concerning anti-personnel explosive small arms]. *Médecine et armées* 1997; **25**: 261 – 264.

Hull JB, Cooper GJ. Pattern and mechanism of traumatic amputation by explosive blast. *J Trauma* 1996; **40 (3Suppl)**: S198 – S205.

Katz E, Ofek B, Adler J, Abramowitz HB, Krausz MM. Primary blast injury after a bomb explosion in a civilian bus. *Ann Surg* 1989; **209**: 484 – 488.

Leibovici D, Gofrit ON, Stein M, Shapira SC, Noga Y, Heruti RJ, Shemer J. Blast injuries: bus versus open-air bombings: a comparative study of injuries in survivors of open-air versus confined-space explosions. *J Trauma* 1996; **41**: 1030 – 1035.

Lindsey D. The idolatry of velocity, or lies, damn lies, and ballistics. *J Trauma* 1980; **20**: 1068 – 1069.

Peters CE, Sebourn CL, Crowder HL. Wound ballistics of unstable projectiles. Part I: projectile yaw growth and retardation. *J Trauma* 1996; **40 (3Suppl)**: S10 – S15.

Peters CE, Sebourn CL. Wound ballistics of unstable projectiles. Part II: Temporary cavity formation and tissue damage. *J Trauma* 1996; **40 (3Suppl)**: S16 – S21.

Santucci RA, Chang Y-J. Ballistics for physicians: myths about wound ballistics and gunshot injuries. *J Urol* 2004; **171**: 1408 – 1414.

Through its meridians our body may be seen as a grid of light channels through which it is connected with the light grid of the universe and can tap its unlimited energies.

Learning to embrace ourselves and the universe:

The Fusion Practice may serve to visualize oneself as a network of light and as a light body. Then the practice is not only one of cleansing but also one of filling the meridians with light. Mutations in consciousness start in the body visualization and turn into actualization. But the transformation lies not in the visualization. It is only a vehicle. Actualization is the real experience of the energy transformation in the body, when its chemistry changes and energy is transformed. One begins to sense the truthfulness and miracle of being alive and one starts to feel that one is embraced and pervaded by love and a sense of gratitude for the mysterious ecstatic process taking place in the body arises.

But this is not an end term. It is always only a beginning, as the love of the infinite has no limits neither in time nor space. In the process matter turns into what is immaterial and the immaterial as energy to continue its transformation waits again for a new form to contain it and change its nature and composition. Words help to create an image and when the image is there, the word loses its function. The image serves to help us generate the energy and its transformation. When the energy has come into being, the image needs to be given up so that a new space arises for a new experience. This is an unending process. How wondrous is it that our organs, our body, that sacred vessel, as it is called in the Taoist Canon, remembers its origins and longs to be fused and serve as an instrument of the fusions which unceasingly take place in heaven so that our intrinsically divine nature is realized and can be experienced. For earthlings, the learning process starts from outside. In the process of turning inward, the learning process increasingly becomes internalized. We need the structures and the forms and formulas to help us on our path. Then when we become still, it becomes spontaneous and starts to move by itself.

Then our child has been born and just wants to play without end to feel that they are welcome and loved so that they feel at home. For this quality in us to arise, we need to learn to embrace ourselves and the universe, as a mother her newborn child.

Written by: Joost Kuitenbrouwer
Universal Tao Instuctor

Sebourn CL, Peters CE. Flight dynamics of spin-stabilized projectiles and the relationship to wound ballistics. *J Trauma* 1996; **40 (3Suppl)**: S22 – S26.

Vail S. The study of wound ballistics is based on a significant amount of science and a tremendous amount of art [Defense Review Web site]. May 14, 2006. Available at: http://www.defensereview.com/modules.php?name=News&file=article&sid=875.

Volgas DA, Stannard JP, Alonso JE. Ballistics: a primer for the surgeon. *Injury* 2005; **36**: 373 – 379.

Volgas DA, Stannard JP, Alonso JE. Current orthopaedic treatment of ballistic injuries. *Injury* 2005; **36**: 380 – 386.

Wang ZG, Feng JX, Liu YQ. Pathomorphological observations of gunshot wounds. *Acta Chir Scand* 1982; **508 (Suppl.)**: S185 – S195.

Wang ZG, Tang CG, Chen XY, Shi TZ. Early pathomorphological characteristics of the wound track caused by fragments. *J Trauma* 1988; **28 (1Suppl.)**: S89 – S95.

Chapter 4

Bowyer GW, Stewart MPM, Ryan JM. Gulf war wounds: application of the Red Cross Wound Classification. *Injury* 1993; **24**: 597 – 600.

Bowyer GW. Afghan war wounded: application of the Red Cross Wound Classification. *J Trauma* 1995; **38**: 64 – 67.

Coupland RM. The Red Cross classification of war wounds: the EXCFVM scoring system. *World J Surg* 1992; **16**: 910 – 917.

Coupland RM. *The Red Cross Wound Classification, Revised Edition.* Geneva: ICRC; 2005.

Giannou CP. Penetrating missile injuries during asymmetric warfare in the 2003 Gulf conflict. [Correspondence]. *Br J Surg* 2005; **92**: 1047 – 1048.

Hinsley DE, Rosell PAE, Rowlands TK, Clasper JC. Penetrating missile injuries during asymmetric warfare in the 2003 Gulf conflict. *Br J Surg* 2005; **92**: 637 – 642.

Rosell PAE, Clasper JC. Ballistic fractures: the limited value of existing classifications. *Injury* 2005; **36**: 369 – 372.

Rowley DI. *War Wounds with Fractures: A Guide to Surgical Management.* Geneva: ICRC; 1996.

Savic J, Cernak I, Jevtic M, Todoric M. Glucose as an adjunct triage tool to the Red Cross Wound Classification. *J Trauma* 1996; **40 (3Suppl.)**: S144 – S147.

Stewart MPM, Kinninmonth A. Shotgun wounds of the limbs *Injury* 1993; **24**: 667 – 670.

Vassalo D, McAdam G. Modification to the Red Cross Wound Classification. *Injury* 1995; **26**: 131 – 132.

Chapter 5

Public health

Aboutanos MB, Baker SP. Wartime civilian injuries: epidemiology and intervention strategies. *J Trauma* 1997; **43**: 719 – 726.

Burnham G, Lafta R, Doocy S, Roberts L. Mortality after the 2003 invasion of Iraq: a cross-sectional cluster sample survey. *Lancet* 2006; **368**: 1421 – 1429.

Coupland RM. The effects of weapons on health. *Lancet* 1996; **347**: 450 – 451.

Coupland RM, Meddings DR. Mortality associated with use of weapons in armed conflicts, wartime atrocities, and civilian mass shootings: literature review. *BMJ* 1999; **319**: 407 – 410.

Coupland RM, Samnegaard HO. Effect of type and transfer of conventional weapons on civilian injuries: retrospective analysis of prospective data from Red Cross hospitals. *BMJ* 1999; **319**: 410 – 412.

Giannou C. Antipersonnel landmines: facts, fictions, and priorities. *BMJ* 1997; **315**: 1453 – 1454.

Guah-Sapir D, van Panhuis WG. The importance of conflict-related mortality in civilian populations. *Lancet* 2003; **361**: 2126 – 2128.

Horton R. Croatia and Bosnia: The imprints of war – 1. Consequences. *Lancet* 1999; **353**: 2139 – 2144.

Ityavyar DA, Ogba LO. Violence, conflict and health in Africa. *Soc Sci Med* 1989; **28**: 649 – 657.

Jeffries SJ. Antipersonnel mines: who are the victims? *J Accid Emerg Med* 1996; **13**: 343 – 346.

de Jong K, Mulhem M, Ford N, van der Kam S, Kleber R. The trauma of war in Sierra Leone. *Lancet* 2000; **355**: 2067 – 2068.

Lautze S, Leaning J, Raven-Roberts A, Kent R, Mazurana D. Assistance, protection, and governance networks in complex emergencies. *Lancet* 2004; **364**: 2134 – 2141.

Meddings DR. Weapons injuries during and after periods of conflict: retrospective analysis. *BMJ* 1997; **310**: 1417 – 1420.

Meddings DR, O'Connor SM. Circumstances around weapon injury in Cambodia after departure of a peacekeeping force: prospective cohort study. *BMJ* 1999; **319**: 412 – 415.

Meddings DR. Civilians and war: a review and historical overview of the involvement of non-combatant populations in conflict situations. *Med Confl Surviv* 2001; **17**: 6 – 16.

Perrin P. *War and Public Health: A Handbook*. Geneva: ICRC; 1996.

Perrin P. *H.E.L.P. – Health Emergencies in Large Populations: Public Health Course in the Management of Humanitarian Aid*. Geneva: ICRC; 2001.

Spiegel PB, Salama P. War and mortality in Kosovo, 1998 – 99: an epidemiological testimony. *Lancet* 2000; **355**: 2204 – 2209.

Taback N, Coupland R. Towards collation and modelling of the global cost of armed violence on civilians. *Med Confl Surviv* 2005; **21**: 19 – 27.

The Sphere Project: Humanitarian Charter and Minimum Standards in Disaster Response. Geneva: The Sphere Project; 2004. Available at: http://www.sphereproject.org.

Toole MJ, Galson S, Brady W. Are war and public health compatible? *Lancet* 1993; **341**: 1193 – 1196.

Udwadia TE. Surgical care for the poor: a personal Indian perspective. *Indian J Surg* 2003; **65**: 504 – 509.

Civilian war surgery literature

Bhatnagar MK, Smith GS. Trauma in the Afghan guerrilla war: effects of lack of access to care. *Surgery* 1989; **105**: 699 – 705.

Cutting PA, Agha R. Surgery in a Palestinian refugee camp. *Injury* 1992; **23**: 405 – 409.

De Wind CM. War injuries treated under primitive circumstances: experiences in an Ugandan mission hospital. *Ann R Coll Surg Engl* 1987; **69**: 193 – 195.

Dudley HAF, Knight RJ, McNeur JC, Rosengarten DS. Civilian battle casualties in South Vietnam. *Br J Surg* 1968; **55**: 332 – 340.

Fosse E, Husum H, Giannou C. The siege of Tripoli 1983: war surgery in Lebanon. *J Trauma* 1988; **28**: 660 – 663.

Fosse E, Husum H. Surgery in Afghanistan: a light model for field surgery during war. *Injury* 1992; **23**: 401 – 404.

Nassoura Z, Hajj H, Dajani O, Jabbour N, Ismail M, Tarazi T, Khoury G, Najjar F. Trauma management in a war zone: the Lebanese war experience. *J Trauma* 1991; **31**: 1596 – 1599.

Odling-Smee GW. Ibo civilian casualties in the Nigerian civil war. *BMJ* 1970; **2**: 592 – 596.

Rukovansjki M. Spinal cord injuries caused by missile weapons in the Croatian war. *J Trauma* 1996; **40 (3Suppl.)**: S189 – S192.

Suljevic I, Surkovic I. Medical aspects of the mass-scale civilian casualties at Sarajevo Markale Market on August 28, 1995: triage, resuscitation, and treatment. *Croat Med J* 2002; **43**: 209 – 212.

Military war surgery literature

Acosta JA, Hatzigeorgiou C, Smith LS. Developing a trauma registry in a forward deployed military hospital: preliminary report. *J Trauma* 2006; **61**: 256 – 260.

Bellamy RF. Combat trauma overview. In: Sajtchuk R, Grande CM, eds. *Textbook of Military Medicine, Anesthesia and Perioperative Care of the Combat Casualty*. Falls Church, VA: Office of the Surgeon General, United States Army; 1995: 1 – 42.

Bilski TR, Baker BC, Grove JR, Hinks RP, Harrison MJ, Sabra JP, Temerlin SM, Rhee P. Battlefield casualties treated at Camp Rhino, Afghanistan: lessons learned. *J Trauma* 2003; **54**: 814 – 822.

Burkle FM Jr, Newland C, Meister SJ, Blood CG. Emergency medicine in the Persian Gulf War – Part 3: battlefield casualties. *Ann Emerg Med* 1994; **23**: 755 – 760.

Carey ME. Learning from traditional combat mortality and morbidity data used in the evaluation of combat medical care. *Mil Med* 1987; **152**: 6 – 12.

Chambers LW, Green DJ, Gillingham BL, Sample K, Rhee P, Brown C, Brethauer S, Nelson T, Narine N, Baker B, Bohman HR. The experience of the US Marine Corps' Surgical Shock Trauma Platoon with 417 operative combat casualties during a 12 month period of Operation Iraqi Freedom. *J Trauma* 2006; **60**: 1155 – 1164.

Champion HR, Bellamy RF, Roberts P, Leppäniemi A. A profile of combat injury *J Trauma* 2003; **54 (5Suppl.)**: S13 – S19.

Danon YL, Nili E, Dolev E. Primary treatment of battle casualties in the Lebanon war, 1982. *Is J Med Sci* 1984; **20**: 300 – 302.

Eastridge BJ, Jenkins D, Flaherty S, Schiller H, Holcomb JB. Trauma system development in a theater of war: experiences from Operation Iraqi Freedom and Operation Enduring Freedom. *J Trauma* 2006; **61**: 1366 – 1373.

Fekadu T. *Mass Casualty Management Under Unique War Situation: Inside Eritrea's War for Independance*. Asmara, Eritrea: self published; 2002.

Garfield RM, Neugut AI. Epidemiologic analysis of warfare. *JAMA* 1991; **266**: 688 – 692.

Gofrit ON, Kovalski N, Leibovici D, Shemer J, O'Hana A, Shapira SC. Accurate anatomical location of war injuries: analysis of the Lebanon war fatal casualties and the proposition of new principles for the design of military personal armour system. *Injury* 1996; **27**: 577 – 581.

Gofrit ON, Leibovici D, Shapira SC, Shemer J, Stein M, Michaelson M. The trimodal death distribution of trauma victims: military experience from the Lebanon war. *Mil Med* 1997; **162**: 24 – 26.

Grau LW, Jorgensen WA. Handling the wounded in a counter-guerrilla war: the Soviet/Russian experience in Afghanistan and Chechnya. *U.S. Army Medical Dept Journal* 1998; **Jan/Feb**: 2 – 10.

Hardaway RM III. Viet Nam wound analysis. *J Trauma* 1978; **18**: 635 – 643.

Holcomb JB. Current perspective on combat casualty care. The 2004 Fitts Lecture. *J Trauma* 2005; **59**: 990 – 1002.

Holcomb JB, Stansbury LG, Champion HR, Wade C, Bellamy RF. Understanding combat casualty care statistics. *J Trauma* 2006; **60**: 397 – 401.

Jackson DS, Batty CG, Ryan JM, McGregor WSP. The Falklands war: army field surgical experience. *Ann R Coll Surg Engl* 1983; **65**: 281 – 285.

Jevtic M, Petrovic M, Ignjatovic D, Ilijevski N, Misovic S, Kronja G, Stankovic N. Treatment of wounded in the combat zone. *J Trauma* 1996; **40 (3Suppl.)**: S173 – S176.

Johnson DE, Panijayanond P, Lumjiak S, Crum JW, Boonkrapu P. Epidemiology of combat casualties in Thailand. *J Trauma* 1981; **21**: 486 – 488.

Jones EL, Peters AF, Gasior RM. Early management of battle casualties in Vietnam. *Arch Surg* 1968; **97**: 1 – 15.

Mabry RL, Holcomb JB, Baker AM, Cloonan CC, Uhorchak JM, Perkins DE, Canfield AJ, Hagmann JH. United States Army Rangers in Somalia: an analysis of combat casualties on an urban battlefield. *J Trauma* 2000; **49**: 515 – 529.

Spalding TJW, Stewart MPM, Tulloch DN, Stephens KM. Penetrating missile injuries in the Gulf war 1991. *Br J Surg* 1991; **78**: 1102 – 1104.

Van Rooyen MJ, Sloan EP, Radvany AE, Peric T, Kulis B, Tabak P. The incidence and outcome of penetrating and blunt trauma in central Bosnia: the Nova Bila Hospital for war wounded. *J Trauma* 1995; **38**: 863 – 866.

Versier G, Le Marec C, Rouffi J. Quatre ans de chirurgie de guerre au GMC de Sarajevo (juillet 1992 à août 1996) [Four years of war surgery at the French surgical facility in Sarajevo (July 1992 – August 1996)]. *Médecine et armées* 1998; **26**: 213 – 218.

Vojvodic V. Management of war casualties in the Military Medical Academy (Belgrade) during combat operations in 1991/1992: an overview. *J Trauma* 1996; **40 (3Suppl.)**: S180 – S182.

ICRC war surgery articles

Bowyer GW. Management of small fragment wounds: experience from the Afghan border. *J Trauma* 1996; **40 (3Suppl.)**: S170 – S172.

Coupland RM. Hand grenade injuries among civilians. *JAMA* 1993; **270**: 624 – 626.

Coupland RM. Epidemiological approach to surgical management of the casualties of war. *BMJ* 1994; **308**: 1693 – 1696.

Kjaergaard J. Les blessés de guerre de l'hôpital de campagne du CICR à Beyrouth en 1976 [War wounded in the ICRC field hospital in Beirut 1976]. *Schweiz Z Milit Med* 1978; **55**: 1 – 23.

Korver AJH. Outcome of war-injured patients treated at first aid posts of the International Committee of the Red Cross. *Injury* 1994; **25**: 25 – 30.

Morris D, Sugrue W, McKenzie E. On the border of Afghanistan with the International Committee of the Red Cross. *NZ Med J* 1985; **98**: 750 – 752.

Scott-Findlay J, Smith FS. A Timor experience in war and civilian trauma. *Med J Aust* 1976; **2**: 90 – 92.

Trouwborst A, Weber BK, Dufour D. Medical statistics of battlefield casualties. *Injury* 1987; **18**: 96 – 99.

Chapter 6

Hayward-Karlsson J, Jeffery S, Kerr A, Schmidt H. *Hospitals for War-Wounded: A Practical Guide for Setting up and Running a Surgical Hospital in an Area of Armed Conflict*. Geneva: ICRC; 1998.

Hayward-Karlsson J. Hospital and System Assessment. In: Mahoney PF, Ryan JM, Brooks AJ, Schwab CW, eds. *Ballistic Trauma: A Practical Guide 2nd Edition*. London: Springer-Verlag; 2005: 513 – 526.

Pruit BA. Combat casualty care and surgical progress. *Ann Surg* 2006; **243**: 715 – 729.

Chapter 7

Butler FK Jr. Tactical combat casualty care: combining good medicine with good tactics. *J Trauma* 2003; **54 (Suppl.)**: S2 – S3.

Coupland RM. Epidemiological approach to surgical management of the casualties of war. *BMJ* 1994; **308**: 1693 – 1696.

Coupland RM, Molde Å, Navein J. *Care in the Field for Victims of Weapons of War: A Report from the Workshop Organized by the ICRC on Pre-Hospital Care for War and Mine-Injured*. Geneva: ICRC; 2001.

Dubick MA, Atkins JL. Small-volume fluid resuscitation for the far-forward combat environment: current concepts. *J Trauma* 2003; **54 (Suppl.)**: S43 – S45.

Giannou C, Bernes E. *First Aid in Armed Conflicts and Other Situations of Violence*. Geneva: ICRC; 2006.

Guidelines on First Aid and HIV/AIDS. Geneva: International Committee of the Red Cross /International Federation of Red Cross and Red Crescent Societies; 2001.

Husum H. Effects of early prehospital life support to war injured: the battle of Jalalabad, Afghanistan. *Prehosp Disaster Med* 1999; **14**: 75 – 80.

Husum H, Gilbert M, Twisborg T. *Save Lives, Save Limbs*. Tromsoe, Norway: Third World Network, Tromsoe Mine Victim Resource Centre; 2000.

Husum H, Gilbert M, Wisborg T, Heng YV, Murad M. Rural prehospital trauma systems improve trauma outcome in low-income countries: a prospective study from North Iraq and Cambodia. *J Trauma* 2003; **54**: 1188 – 1196.

Korver AJH. Outcome of war-injured patients treated at first aid posts of the International Committee of the Red Cross. *Injury* 1994; **25**: 25 – 30.

Mabry R, McManus JG. Prehospital advances in the management of severe penetrating trauma. *Crit Care Med* 2008; **36 (Suppl.)**: S258 – S266.

Roberts DL. *Staying Alive: Safety and Security Guidelines for Humanitarian Volunteers in Conflict Areas 2nd Edition*. Geneva: ICRC; 2006.

Royal Defence Medical College and the Royal Centre for Defence Medicine. *Battlefield Advanced Trauma Life Support (Incorporating Battlefield Resuscitation Techniques and Skills)*. London: British Armed Forces, UK Minister of Defence; 2003.

Wisborg T, Murad MK, Edvardsen O, Husum H. Prehospital trauma system in a low-income country: system maturation and adaptation during 8 years. *J Trauma* 2008; **64**: 1342 – 1348.

Cervical spine immobilization

Arishita GI, Vayer JS, Bellamy RF. Cervical spine immobilization of penetrating neck wounds in a hostile environment. *J Trauma* 1989; **29**: 332 – 337.

Barkana Y, Stein M, Scope A, Maor R, Abramovich Y, Friedman Z, Knoller N. Prehospital stabilization of the cervical spine for penetrating injuries of the neck – is it necessary? *Injury* 2000; **31**: 305 – 309.

Rhee P, Kuncir EJ, Johnson L, Brown C, Velmahos G, Martin M, Wang D, Salim A, Doucet J, Kennedy S, Demetriades D. Cervical spine injury is highly dependent on the mechanism of injury following blunt and penetrating assault. *J Trauma* 2006; **61**: 1166 – 1170.

Tourniquet use

Brodie S, Hodgetts TJ, Ollerton J, McLeod J, Lambert P, Mahoney P. Tourniquet use in combat trauma. *J R Army Med Corps* 2008; **153**: 310 – 313.

Lakstein D, Blumenfeld A, Sokolov T, Lin G, Bssorai R, Lynn M, Ben-Abraham R. Tourniquets for hemorrhage control on the battlefield: a 4-year accumulated experience. *J Trauma* 2003; **54 (Suppl.)**: S221 – S225.

Navein J, Coupland R, Dunn R. The tourniquet controversy. *J Trauma* 2003; **54 (Suppl.)**: S219 – S220.

Welling DR, Burris DG, Hutton JE, Minken SL, Rich NM. A balanced approach to tourniquet use: lessons learned and relearned. *J Am Coll Surg* 2006; **203**: 106 – 115.

Chapter 8

Trauma training

Driscoll P, Skinner D, Earlam R, eds. *ABC of Major Trauma 3rd Edition*. London: BMJ Books; 2001.

American College of Surgeons, Committee on Trauma. *Advanced Trauma Life Support for Doctors, Student Course Manual (ATLS) 7th Edition*. Chicago, IL: American College of Surgeons; 2004.

Kortbeek JB, Al Turki SA, Ali J, et al. Advanced Trauma Life Support, 8th Edition. The evidence for change. *J Trauma* 2008; **64**: 1638 – 1650.

International Association for Trauma Surgery and Intensive Care (IATSIC). *Definitive Surgical Trauma Care Course (DSTC)*. Various country and regional sessions.

Trauma training in low-income countries: some examples

Aboutanos MB, Rodas EB, Aboutanos SZ, Mora FE, Wolf LG, Duane TM, Malhotra AK, Ivatury RR. Trauma education and care in the jungle of Ecuador, where there is no advanced trauma life support. *J Trauma* 2007; **62**: 714 – 719.

Basic Emergency Skills in Trauma (B.E.S.T.). Manila: Philippine College of Surgeons.

National Trauma Management Course (NTMC). Academy of Traumatology of India and Trauma Unit, Johannesburg Hospital and Faculty of Health Sciences, University of Witwatersrand. Available at: http://www.indiatrauma.org.

Emergency Room Trauma Course (ERTC). Geneva: ICRC.

Pneumothorax

Leigh-Smith S, Harris T. Tension pneumothorax – time for a re-think? *Emerg Med J* 2005; **22**: 8 – 16.

Shock resuscitation

Alam HB, Koustova E, Rhee P. Combat casualty care research: from bench to the battlefield. *World J Surg* 2005; **29 (Suppl.)**: S7 – S11.

Bickell WH, Wall MJ Jr, Pepe PE, Martin RR, Ginger VF, Allen MK, Mattox KL. Immediate versus delayed fluid resuscitation for hypotensive patients with penetrating torso injuries. *N Engl J Med* 1994; **331**: 1105 – 1109.

Champion HR. Combat fluid resuscitation: introduction and overview of conferences. *J Trauma* 2003; **54 (Suppl.)**: S7 – S12.

Moore FA, McKinley BA, Moore EE. The next generation in shock resuscitation. *Lancet* 2004; **363**: 1988 – 1996.

Rhee P, Alam HB, Ling GSF. Hemorrhagic Shock and Resuscitation. In: Tsokos GC, Atkins JL, eds. *Combat Medicine: Basic and Clinical Research in Military, Trauma, and Emergency Medicine*. Totowa, NJ: Humana Press; 2003: 177 – 218.

Rhee P, Koustova E, Alam HB. Searching for the optimal resuscitation method: recommendations for the initial fluid resuscitation of combat casualties. *J Trauma* 2003; **54 (Suppl.)**: S52 – S62.

Rushing GD, Britt LD. Reperfusion injury after hemorrhage. *Ann Surg* 2008; **247**: 929 – 937.

Shoemaker WC, Peitzman AB, Bellamy R, Bellomo R, Bruttig SP, Capone A, Dubick M, Kramer GC, McKenzie JE, Pepe PE, Safar P, Schlichtig R, Severinghaus JW, Tisherman SA, Wiklund L. Resuscitation from severe hemorrhage. [Symposium article] *Crit Care Med* 1996; **24 (Suppl.)**: S12 – S23.

Blood transfusion

Eshaya-Chauvin B, Coupland RM. Transfusion requirements for the management of war injured: the experience of the International Committee of the Red Cross. *Br J Anaesth* 1992; **68**: 221 – 223.

Kiebooms L, Rouvillois A, Jones T. *ICRC Blood Transfusion Guidelines*. Geneva: ICRC; 2004.

Kauvar DS, Holcomb JB, Norris GC, Hess JR. Fresh whole blood transfusion: a controversial military practice. *J Trauma* 2006; **61**: 181 – 184.

Key NS, Negrier C. Transfusion medicine 3: Coagulation factor concentrates: past, present, and future. *Lancet* 2007; **370**: 439 – 448.

Klein HG, Spahn DR, Carson JL. Transfusion medicine 1: Red blood cell transfusion in clinical practice. *Lancet* 2007; **370**: 415 – 426.

Repine TB, Perkins JG, Kauvar DS, Blackborne L. The use of fresh whole blood in massive transfusion. *J Trauma* 2006; **60 (6Suppl.)**: S59 – S69.

Spinella PC, Perkins JG, Grathwohl KW, Repine T, Beekley AC, Sebesta J, Jenkins D, Azarow K, Holcomb JB. Fresh whole blood transfusions in coalition military, foreign national, and enemy combatant patients during Operation Iraqi Freedom at a U.S. combat support hospital. *World J Surg* 2008; **32**: 2 – 6.

Stroncek DF, Rebulla P. Transfusion medicine 2: Platelet transfusions. *Lancet* 2007; **370**: 427 – 438.

World Health Organization. *WHO Guidelines for Blood Transfusion* [WHO Web site]. Available at: http://www.who.int/bloodsafety/clinical_use/en/Handbook_EN.pdf and http://www.who.int/bloodsafety/clinical_use/en/WHO_BLS_98.2_EN.pdf.

Chapter 9

Further practical information for the organisation of hospital management in a triage situation is available in: Hayward-Karlsson J, Jeffrey S, Kerr A, Schmidt H. *Hospitals for War Wounded*. Geneva: ICRC; 1998.

Please note:

In a military context, all standard war surgery manuals written by and for armed forces deal with the organization and implementation of triage under military constraints.

Almogy G, Belzberg H, Mintz Y, Pikarsky AK, Zamir G, Rivkind AI. Suicide bombing attacks: update and modifications to the protocol. *Ann Surg* 2004; **239**: 295 – 303.

Barbera JA, Macintyre AG. *Janes's Mass Casualty Handbook: Hospital Emergency Preparedness and Response*. Coulsdon, Surrey, UK: Jane's Information Group; 2003.

Burkle FM, Orebaugh S, Barendse BR. Emergency medicine in the Persian Gulf war – part 1: preparations for triage and combat casualty care. *Ann Emerg Med* 1994; **23**: 742 – 747.

Coupland RM, Parker PJ, Gray RC. Triage of war wounded: the experience of the International Committee of the Red Cross. *Injury* 1992; **23**: 507 – 510.

Frykberg ER. Medical management of disasters and mass casualties from terrorist bombings: how can we cope? *J Trauma* 2002; **53**: 201 – 212.

Frykberg ER. Principles of mass casualty management following terrorist disasters. [Editorial]. *Ann Surg* 2004; **239**: 319 – 321.

Gertsch P. Assessment of hospital workload in war surgery. *Br J Surg* 1987; **74**: 831 – 833.

Gray RC. War surgery and triage. *Postgrad Doctor Mid East*. 1993; **16**: 150 – 157.

Hirshberg A, Scott BG, Granchi T, Wall MJ Jr, Mattox KL, Stein M. How does casualty load affect trauma care in urban bombing incidents? A quantitative analysis. *J Trauma* 2005; **58**: 686 – 695.

Hogan DE, Lairet JR: Triage. In: Hogan DE, Burstein JL, eds. *Disaster Medicine 2nd Edition*. Philadephia, PA: Lippincott Williams & Wilkins; 2007: 12 – 28.

Iserson KV, Moskop JC: Triage in medicine, part I: concept, history, and types. *Ann Emerg Med* 2007; **49**: 275 – 281.

Iserson KV, Moskop JC: Triage in medicine, part II: underlying values and principles. *Ann Emerg Med* 2007; **49**: 282 – 287.

Kennedy K, Aghababian RV, Gans L, Lewis CP. Triage: techniques and applications in decision making. *Ann Emerg Med* 1996; **28**: 136 – 144.

Rignault D, Wherry D. Lessons from the past worth remembering: Larrey and triage. *J Trauma* 1999; **1**: 86 – 89.

Rochat C-H. Le triage chirurgical en conditions de guerre (Kaboul 1989) [Surgical triage under war conditions (Kabul 1989)]. *Médicine Militaire* 1992; **69**: 35 – 38.

Ryan JM, Sibson J, Howell G. Assessing injury severity during general war: will the military triage system meet future needs? *J R Army Med Corps* 1990; **136**: 27 – 35.

Suljevic I, Surkovic I. Medical aspects of the mass-scale civilian casualties at Sarajevo Markale Market on August 28, 1995: triage, resuscitation, and treatment. *Croat Med J* 2002; **43**: 209 – 212.

Torkki M, Koljonen V, Sillanpää K, Tukiainen E, Pyörälä S, Kemppainen E, Kalske J, Arajärvi E, Keränen U, Hirvensalo E. Triage in a bomb disaster with 166 casualties. *Eur J Trauma* 2006; **32**: 374 – 380.

World Medical Association. Statement on Medical Ethics in the Event of Disasters. Adopted by the 46th WMA General Assembly,1994 Sept.; Stockholm: Sweden. Available at: http://www.wma.net/e/policy/d7.htm.

Chapters 10 and 11

Anglen JO, Gainor BJ, Simpson WA, Christensen G. The use of detergent irrigation for musculoskeletal wounds. *Int Orthop* 2003; **27**: 40 – 46.

Baldan M, Giannou CP. Basic surgical management of war wounds: the ICRC experience. *East Cent Afr J Surg* 2003; **8**: 35 – 38.

Bewes P. The Management of Wounds in Developing Countries. Health Development e-TALC [CD – ROM]. January, 2004. No. 5. [TALC: Teaching-aids At Low Cost Web site]. Available at: http://www.talcuk.org.

Bowyer GW, Cooper GJ, Rice P. Small fragment wounds: biophysics and pathophysiology. *J Trauma* 1996; **40 (3Suppl.)**: S159 – S164.

Bowyer GW. Management of small fragment wounds in modern warfare: a return to Hunterian principles. *Ann R Coll Surg Engl* 1997; **79**: 175 – 182.

Coupland RM. Technical aspects of war wound excision. *Br J Surg* 1989; **76**: 663 – 667.

Fackler ML, Breteau JPL, Courbil LJ, Taxit R, Glas J, Fievet JP. Open wound drainage versus wound excision in treating the modern assault rifle wound. *Surgery* 1989; **105**: 576 – 584.

Trunkey DD. Comments on the article by Fackler et al. [Editorial] *Surgery* 1989; **105**: 693 – 694.

Gray RC. Surgery of war and disaster. *Trop Doct* 1991; **21 (Suppl.)**: S56 – S60.

Gray RC. *War Wounds: Basic Surgical Management*. Geneva: ICRC; 1994.

Hamer ML, Robson MC, Krizek TJ, Southwick WO. Quantitative bacterial analysis of comparative wound irrigations. *Ann Surg* 1975; **181**: 819 – 822.

Molan PC. The evidence supporting the use of honey as a wound dressing. *Int J Low Extrem Wounds* 2006; **5**: 40 – 54.

Molde Å. Victims of war: surgical principles must not be forgotten (again)! *Acta Orthop Scand* 1998; **281 (Suppl.)**: 54 – 57.

Rautio J, Paavolainen P. Delayed treatment of complicated fractures in war wounded. *Injury* 1987; **18**: 238 – 240.

Rautio J, Paavolainen P. Afghan war wounded: experience with 200 cases. *J Trauma* 1988; **28**: 523 – 525.

Rochat C-H, Graber P, Ursprung T. Traitement des plaies par projectiles en conditions de guerre (Afghanistan). Suture primaire différée ou suture secondaire? [Treatment of projectile wounds under conditions of war (Afghanistan). Delayed primary suture or secondary suture?]. *Médecine Militaire* 1986; **1**: 20 – 22.

Rowley DI. The management of war wounds involving bone. *J Bone Joint Surg Br* 1996; **78**: 706 – 709.

Strada G, Coupland RM, Gray RC. Surgery for the victims of war: the experience of the International Committee of the Red Cross. *J Emerg Surg* 1991; **14**: 126 – 130.

Svoboda SJ, Owens BD, Gooden HA, Melvin ML, Baer DG, Wenke JC. Irrigation with potable water versus normal saline in a contaminated musculoskeletal wound model. *J Trauma* 2008; **64**: 1357 – 1359.

Verbeke JH. Initial treatment of war casualties in a field hospital. *Acta Anaesth Belg* 1987; **38**: 261 – 265.

Vermeulen H, Ubbink DT, Goossens A, de Vos R, Legemate DA. Systematic review of dressings and topical agents for surgical wounds healing by secondary intention. *Br J Surg* 2005; **92**: 665 – 672.

Chapter 12

Bhaskar SN, Cutright DE, Hunsuck EE, Gross A. Pulsating water jet devices in debridement of combat wounds. *Mil Med* 1971; **136**: 264 – 266.

Bhatnagar MK, Smith GS. Trauma in the Afghan guerrilla war: effects of lack of access to care. *Surgery* 1989; **105**: 699 – 705.

Coupland RM, Howell P. An experience of war surgery and wounds presenting after 3 days on the border of Afghanistan. *Injury* 1988; **19**: 259 – 262.

Craig G. Treating the Afghan war wounded. *J Roy Soc Med* 1993; **86**: 404 – 405.

Gross A, Cutright DE, Bhaskar SN. Effectiveness of pulsating water jet lavage in treatment of contaminated crushed wounds. *Am J Surg* 1972; **124**: 373 – 377.

Mellor SG, Cooper GJ, Bowyer GW. Efficacy of delayed administration of benzylpenicillin in the control of infection in penetrating soft tissue injuries in war. *J Trauma* 1996; **40 (3Suppl.)**: S128 – S134.

Morris DS, Sugrue WJ, McKenzie E. On the border of Afghanistan with the International Committee of the Red Cross. *NZ Med J* 1985; **98**: 750 – 752.

Rowley DI. War surgery in an African conflict. *Scott Med J* 1997; **42**: 163 – 164.

Biofilm

Evans LV, ed. *Biofilms: Recent Advances in their Study and Control*. Amsterdam: Harwood Academic Press; 2000.

Fletcher M, ed. *Bacterial Adhesion: Molecular and Ecological Diversity*. New York: John Wiley & Sons; 1996.

Monroe D. Looking for chinks in the armor of bacterial biofilms [Public Library of Science Web site]. Available at: http://www.plos.org. *PLoS Bio*. 2007; **5**: e307.

Wilson M, ed. *Bacterial Adhesion to Host Tissues: Mechanisms and Consequences*. Cambridge: Cambridge University Press; 2002.

Chapter 13

Dahlgren B, Berlin R, Brandberg A, Rybeck B, Seeman T. Bacteriological findings in the first 12 hours following experimental missile trauma. *Acta Chir Scand* 1981; **147**: 513 – 518.

Dahlgren B, Berlin R, Brandberg A, Rybeck B, Schantz B, Seeman T. Effect of benzylpenicillin on wound infection rate and on the extent of devitalized tissue twelve hours after infliction of experimental missile trauma. *Acta Chir Scand* 1982; **148**: 107 – 112.

Fleming A. On the bacteriology of septic wounds. *Lancet* 1915; **186**: 638 – 643.

Lindberg RB, Wetzler TF, Marshall JD, Newton A, Strawitz JG, Howard JM. The bacterial flora of battle wounds at the time of primary debridement. *Ann Surg* 1955; **141**: 369 – 374.

Mellor SG, Cooper GJ, Bowyer GW. Efficacy of delayed administration of benzylpenicillin in the control of infection in penetrating soft tissue injuries in war. *J Trauma* 1996; **40 (3Suppl.)**: S128 – S134.

Miclau T, Farjo LA. The antibiotic treatment of gunshot wounds. *Injury* 1997; **28 (3Suppl.)**: C1 – C5.

Questions and Answers about the Cosmic Fusion Practice

Q. ***Is the cauldron the point where all the pakuas join together?***
A. Yes.

Q. ***Now that we've learned about the cauldron, where do we collect the energy at the end of meditation practice?***
A. You can collect and store energy at the cauldron or you can continue to collect and store your energy behind the navel. When you collect the energy you make a vortex, which is three-dimensional, so it can veer toward the navel or the cauldron. As you do this you may feel it going deeper and deeper.

Q. ***Do we always have to do 36 and 24 spirals in the collection?***
A. The numbers 36 and 24 are a guide. There is no speed limit for spiralling the energy when you collect it. Some days you might want to do more than that; on many days you may want to do much less. On those days, 12 and 9 may be sufficient. Eventually it will go by itself.

Q. ***How do you collect the energy when there is so much energy all around?***
A. Collecting the energy will eventually become automatic. The safety features are bringing any excess energy from the pelvis up to the navel and and excess energy in the head and heart down to the navel. When you are coming back from the feet to the navel in the belt routes you are also collecting the energy.

Q. ***Does the energy stay in the cauldron or does it spread to the organs?***
A. Both.

Q. ***Should you see the collection points in color?***
A. Some people see, some people feel, and some people can even taste the energies. If you are visual, great. Then you will see the colors. If you work with the colors, the color will tell you if an organ's energy is healthy or not. If you look within and see dark muddy colors, then you know you have to work to make them clear and bright.

Munoz-Price LS, Weinstein RA. Acinetobacter infection. *N Engl J Med* 2008; **358**: 1271 – 1281.

Murray CK, Roop SA, Hospenthal DR, Dooley DP, Wenner K, Hammock J, Taufen N, Gourdine E. Bacteriology of war wounds at the time of injury. *Mil Med* 2006; **171**: 826 – 829.

Murray CK, Hospenthal DR, eds. Prevention and management of combat-related infections: clinical practice guidelines consensus conference. *J Trauma* 2008; **64 (3Suppl.)**: S207 – S286.

Petersen K, Riddle MS, Danko JR, Blazes DL, Hayden R, Tasker SA, Dunne JR. Trauma-related infections in battlefield casualties from Iraq. *Ann Surg* 2007; **245**: 803 – 811.

Polhemus ME, Kester KE. Infections. In: Tsokos GC, Atkins JL, eds. *Combat Medicine: Basic and Clinical Research in Military, Trauma, and Emergency Medicine*. Totowa, NJ: Humana Press; 2003: 149 – 173.

Rubin RH. Surgical wound infection: epidemiology, pathogenesis, diagnosis and management. *BMC Infect Dis* 2006; **6**: 171. Available at: http://www.biomedcentral.com/1471-2334/6/171.

Sebeny PJ, Riddle MS, Petersen K. *Acinetobacter baumannii* skin and soft-tissue infection associated with war trauma. *Clin Infect Dis* 2008; **47**: 444 – 449.

Tian HM, Deng G, Huang MJ, Tian F, Suang G, Liu YQ. Quantitative bacteriological study of the wound track. *J. Trauma* 1988; **28 (Suppl.)**: S215 – S216.

Tian HM, Huang MJ, Liu YQ, Wang ZG. Primary bacterial contamination of wound track. *Acta Chir Scand* 1982; **508 (Suppl.)**: S265 – S269.

Simchen E, Sacks T. Infection in war wounds: experience during the 1973 October war in Israel. *Ann Surg* 1975; **182**: 754 –761.

Tetanus

Oladiran I, Meier DE, Ojelade AA, OlaOlorun DA, Adeniran A, Tarpley JL. Tetanus: continuing problem in the developing world. *World J Surg* 2002; **26**: 1282 – 1285.

Thwaites CL, Yen LM, Loan HT, Thuy TTD, Thwaites GE, Stepniewska K, Soni N, White NJ, Farrar JJ. Magnesium sulphate for treatment of severe tetanus: a randomised controlled trial. *Lancet* 2006; **368**: 1436 – 1443.

Necrotising fasciitis

Angoules AG, Kontakis G, Drakoulakis E, Vrentzos G, Granick MS, Giannoudis PV. Necrotising fasciitis of upper and lower limb: a systematic review. *Injury* 2007; **38 (Suppl.)**: C18 – C25.

Hasham S, Matteucci P, Stanley PRW, Hart NB. Necrotising fasciitis: clinical review. *BMJ* 2005; **330**; 830 – 833.

Chapter 14

Baldan M, Giannou CP, Sasin V, Morino GF. Metallic foreign bodies after war injuries: should we remove them? The ICRC experience. *East C Afr J Surg* 2004; **9**: 31 – 34.

Linden MA, Manton WI, Stewart RM, Thal ER, Feit H. Lead poisoning from retained bullets: pathogenesis, diagnosis, and management. *Ann Surg* 1982; **195**: 305 – 313.

Rhee JM, Martin R. The management of retained bullets in the limbs. *Injury* 1997; **28 (3Suppl.)**: C23 – C28.

Rich NM, Collins GJ, Andersen CA, McDonald PT, Kozloff L, Ricotta JJ. Missile emboli. *J Trauma* 1978; **18**: 236 – 239.

Chapter 15

Arturson G: Pathophysiology of the burn wound and pharmacological treatment. The Rudi Hermans Lecture, 1995. *Burns* 1996; **22**: 255 – 274.

Cartotto R, Musgrave M, Beveridge M, Fish J, Gomez M. Minimizing blood loss in burn surgery. *J Trauma* 2000; **49**: 1034 – 1039.

Hettiaratchy S, Dziewulski P: ABC of burns: pathophysiology and types of burns. *BMJ* 2004; **328**: 1427 – 1429.

Lindahl OA, Zdolsekz J, Sjöberg F, Ängquist K-A. Human postburn oedema measured with the impression method. *Burns* 1993; **19**: 479 – 484.

Lund T, Onarheim H, Reed RK. Pathogenesis of edema formation in burn injuries. *World J Surg* 1992; **16**: 2 – 9.

Pruit BA Jr. Fluid and electrolyte replacement in the burned patient. *Surg Clin N Am* 1978; **48**: 1291 – 1312.

Sheridan RL. Burns. *Crit Care Med* 2002; **30 (Suppl.)**: S500 – S514.

Thomas SJ, Kramer GC, Herndon DN. Burns: military options and tactical solutions. *J Trauma* 2003; **54 (5Suppl.)**: S207 – S218.

Zdolsek HJ, Lindahl OA, Ängquist K-A, Sjöberg F. Non-invasive assessment of intercompartmental fluids in burn victims. *Burns* 1998; **24**: 233 – 240.

Chapter 16

Britt LD, Dascombe WH, Rodriguez A. New horizons in management of hypothermia and frostbite injury. *Surg Clin North Am* 1991; **71**: 345 – 370.

Chapter 17

Bion JF. An anaesthetist in a camp for Cambodian refugees. *Anaesthesia* 1983; **38**: 798 – 801.

Bion JF. Infusion analgesia for acute war injuries: a comparison of pentazocine and ketamine. *Br J Acc Surg* 1984; **39**: 560 – 564.

Eshaya-Chauvin B, Nyffenegger E. Anesthésie pour blessés de guerre: étude rétrospective [Anaesthesia for war-wounded: retrospective study]. *Revue Médicale de la Suisse Romande*. 1990; **110**: 429 – 432.

Husum H, Heger T, Sundet M. Postinjury malaria: a study of trauma victims in Cambodia. *J Trauma* 2002; **52**: 259 – 266.

King M, ed. *Primary Anaesthesia*. Oxford: Oxford University Press; 1986.

Korver AJH. Relation between fever and outcome in injured victims of an internal armed conflict: the experience in a war surgery hospital of the International Committee of the Red Cross. *Milit Med* 1996; **161**: 658 – 660.

Leppäniemi AK. Where there is no anaesthetist. *Br J Surg* 1991; **78**: 245 – 246.

Pesonen P. Pulse oximetry during ketamine anaesthesia in war conditions. *Can J Anaesth* 1991; **38**: 592 – 594.

Vreede E, Lasalle X, Rosseel P. *Field Anaesthesia: Basic Practice: A Guide for Anaesthetists*. Paris: Médecins sans Frontières; 2001.

Ketamine anaesthesia in head trauma

Bourgoin A, Albanese J, Wereszczynski N, Charbit M, Vialet R, Martin C. Safety of sedation with ketamine in severe head injury patients: comparison with sulfentanyl. *Crit Care Med* 2003; **31**: 711 – 717.

Gofrit ON Leibovici D, Shemer J, Henig A, Shapira SC. Ketamine in the field: the use of ketamine for induction of anesthesia before intubation of injured patients in the field. *Injury* 1997; **28**: 41 – 43.

Green SM, Clem KJ, Rothrock SG. Ketamine safety profile in the developing world: survey of practitioners. *Acad Emerg Med* 1996; **3**: 598 – 604.

Himmelseher S, Durieux ME. Revising a dogma: ketamine for patients with neurological injury? *Anesth Analg* 2005; **101**: 524 – 534.

Ketcham DW. Where there is no anaesthesiologist: the many uses of ketamine. *Trop Doct* 1990; **20**: 163 – 166.

Sehdev RS, Symmons DAD, Kindl K. Ketamine for rapid sequence induction in patients with head injury in the emergency department. *Emerg Med Austr* 2006; **18**: 37 – 44.

Tighe SQM, Rudland S. Anesthesia in northern Iraq: an audit from a field hospital. *Mil Med* 1994; **159**: 86 – 90.

Trouwborst A, Weber BK, Dufour D. Medical statistics of battlefield casualties. *Injury* 1987; **18**: 96 – 99.

Chapter 18

Damage control surgery

Burch JM, Ortiz VB, Richardson RJ, Martin RR, Mattox KL, Jordan GL Jr. Abbreviated laparotomy and planned reoperation for critically injured patients. *Ann Surg* 1992; **215**: 476 – 483.

Damage Control Surgery. *Surg Clin North Am* 1997; **77**: 753 – 952.

Hirshberg A, Mattox KL. Planned reoperation for severe trauma. *Ann Surg* 1995; **222**: 3 – 8.

Kashuk JL, Moore EE, Millikan JS, Moore JB. Major abdominal vascular trauma: a unified approach. *J Trauma* 1982; **22**: 672 – 679.

Moore EE. Staged laparotomy for the hypothermia, acidosis, coagulopathy syndrome. *Am J Surg* 1996; **172**: 405 – 410.

Parker PJ. Damage control surgery and casualty evacuation: techniques for surgeons, lessons for military medical planners. *J R Army Med Corps* 2006; **152**: 202 – 211.

Rotondo MF, Schwab CW, McGonigal MD, Phillips GR, Fruchterman TM, Kauder DR, Latenser BA, Angood PB: "Damage Control": an approach for improved survival with exsanguinating penetrating abdominal injury *J Trauma* 1993; **35**: 375 – 382.

Sharpiro MB, Jenkins DH, Schwab CW, Rotondo MF. Damage control: collective review. *J Trauma* 2000; **49**: 969 – 978.

Stone HH, Strom PR, Mullins RJ. Management of the major coagulopathy with onset during laparotomy. *Ann Surg* 1983; **197**: 532 – 535.

Hypothermia and coagulopathy

Bernabei AF, Levison MA, Bender JS. The effects of hypothermia and injury severity on blood loss during trauma laparotomy. *J Trauma* 1992; **33**: 835 – 839.

Brohi K, Singh J, Heron M, Coats T. Acute traumatic coagulopathy. *J Trauma* 2003; **54**: 1127 – 1130.

Brohi K, Cohen MJ, Ganter MT, Matthay MA, Mackersie RC, Pittet J-F. Acute traumatic coagulopathy: initiated by hypoperfusion: modulated through the protein C pathway? *Ann Surg* 2007; **245**: 812 – 818.

Brohi K, Cohen MJ, Ganter MT, Schultz MJ, Levi M, Mackersie RC, Pittet J-F. Acute coagulopathy of trauma: hypoperfusion induces systemic anticoagulation and hyperfibrinolysis. *J Trauma* 2008; **64**: 1211 – 1217.

Cosgriff N, Moore EE, Sauaia A, Kenny-Moynihan M, Burch JM, Galloway B. Predicting life-threatening coagulopathy in the massively transfused trauma patient: hypothermia and acidosis revisited. *J Trauma* 1997; **42**: 857 – 862.

Gentilello LM, Jurkovich GJ, Stark MS, Hassantash SA, O'Keefe GE. Is hypothermia in the victim of major trauma protective or harmful? A randomized, prospective study. *Ann Surg* 1997; **226**: 439 – 449.

Gregory JS, Flanebaum L, Townsend MC, Cloutier CT, Jonasson O. Incidence and timing of hypothermia in trauma patients undergoing operations. *J Trauma* 1991; **31**: 795 – 800.

Grosso SM, Keenan JO. Whole blood transfusion for exsanguinating coagulopathy in a U.S. field surgical hospital in postwar Kosovo. *J Trauma* 2000; **49**: 145 – 148.

Gubler KD, Gentilello LM, Hassantash SA, Maier RV. The impact of hypothermia on dilutional coagulopathy. *J Trauma* 1994; **36**: 847 – 851.

Hess JR, Lawson JH. The coagulopathy of trauma versus disseminated intravascular coagulation. *J Trauma* 2006; **60 (6Suppl.)**: S12 – S19.

Holcomb JB, Jenkins D, Rhee P, Johannigman J, Mahoney P, Mehta S, Cox ED, Gehrke MJ, Beilman GJ, Schreiber M, Flaherty SF, Grathwohl KW, Spinella PC, Perkins JG, Beekley AC, McMullin NR, Park MS, Gonzalez EA, Wade CE, Dubick MA, Schwab CW, Moore FA, Champion HR, Hoyt DB, Hess JR. Damage control resuscitation: directly addressing the early coagulopathy of trauma. *J Trauma* 2007; **62**: 307 – 310.

Jurkovich GJ, Greiser WB, Luterman A, Curreri PW. Hypothermia in trauma victims: an ominous predictor of survival. *J Trauma* 1987; **27**: 1019 – 1024.

Kirkman E, Watts S, Hodgetts T, Mahoney P, Rawlinson S, Midwinter M. A proactive approach to the coagulopathy of trauma: the rationale and guidelines for treatment. *J R Army Med Corps* 2008; **153**: 302 – 306.

Kirkpatrick AW, Chun R, Brown R, Simons RK. Hypothermia and the trauma patient. *Can J Surg* 1999; **42**: 333 – 343.

Luna GK, Maier RV, Pavlin EG, Anardi D, Copass MK, Oreskovich MR. Incidence and effect of hypothermia in seriously injured patients. *J Trauma* 1987; **27**: 1014 – 1018.

MacLeod JB, Lynn M, McKenney MG, Cohn SM, Murtha M. Early coagulopathy predicts mortality in trauma. *J Trauma* 2003; **55**: 39 – 44.

Niles SE, McLaughlin DF, Perkins JG, Wade CE, Li Y, Spinella PC, Holcomb JB. Increased mortality associated with the early coagulopathy of trauma in combat casualties. *J Trauma* 2008; **64**: 1459 – 1465.

Seekamp A, van Griensven M, Hildebrandt F, Wahlers T, Tscherne H. Adenosine-triphosphate in trauma-related and elective hypothermia. *J Trauma* 1999; **47**: 673 – 683.

Shafi S, Elliott AC, Gentilello L. Is hypothermia simply a marker of shock and injury severity or an independent risk factor for mortality in trauma patients? Analysis of a large national trauma registry. *J Trauma* 2005; **59**: 1081 – 1085.

Tisherman SA. Hypothermia and injury. *Curr Opin Crit Care* 2004; **10**: 512 – 519.

Watts DD, Trask A, Soeken K, Perdue P, Dols S, Kaufmann C. Hypothermic coagulopathy in trauma: effect of varying levels of hypothermia on enzyme speed, platelet function, and fibrinolytic activity. *J Trauma* 1998; **44**: 846 – 854.

MISSION

The International Committee of the Red Cross (ICRC) is an impartial, neutral and independent organization whose exclusively humanitarian mission is to protect the lives and dignity of victims of armed conflict and other situations of violence and to provide them with assistance.

The ICRC also endeavours to prevent suffering by promoting and strengthening humanitarian law and universal humanitarian principles.

Established in 1863, the ICRC is at the origin of the Geneva Conventions and the International Red Cross and Red Crescent Movement. It directs and coordinates the international activities conducted by the Movement in armed conflicts and other situations of violence.

ICRC

VOLUME 1

WAR SURGERY

WORKING WITH LIMITED RESOURCES IN ARMED CONFLICT AND OTHER SITUATIONS OF VIOLENCE

0973/002 03.2009 3,000

ICRC

WAR SURGERY

WORKING WITH LIMITED RESOURCES
IN ARMED CONFLICT
AND OTHER SITUATIONS OF VIOLENCE

VOLUME 1

ICRC

REFERENCE

Surgical Techniques

Edited by

MIHÁLY BOROS



TEXTBOOK FOR MEDICAL STUDENTS

MEDICINA

Surgical Techniques

Textbook for medical students

Edited by Mihály Boros

University of Szeged
Faculty of Medicine
Institute of Surgical Research

Szeged, 2006

Supported by ROP–3.3.1–2005–02–0001/34. project

Magyarország célba ér

NEMZETI
FEJLESZTÉSI
TERV

REGIONÁLIS FEJLESZTÉS
OPERATÍV PROGRAM

This applies to the organs and the collection points. Because the organs are affected by the emotions the colors will be affected.

Q. ***Does the Yin/Yang symbol move inside the pakua?***
A. It spins like a vortex.

Q. ***Is there always a pearl you can work with?***
A. If you practice forming a pearl every day, there will be one there when you sit down to meditate.

Q. ***Is there a minimum size for the pearl?***
A. The size of the pearl is less important than its density. As you add energy to it you might notice it glowing more brightly or feeling more energetic.

When the energy increases you might want to make more than one pearl. Then you can give it away to an organ or into your own atmosphere.

Q. ***Does the belt channel go around both legs or each one separately?***
A. It circles around both legs, although if the energy wants to go around each one, that's okay too.

Q. ***You talk about using the thrusting routes for practical purposes. Can you give an example?***
A. To clean the atmosphere in a room, you shoot the pearl out the crown and let it expand and fill the space. That way you declare the territory as your own—it is permeated now with your energy and consciousness. If there is any negative energy, any negative spirit, it will just leave of its own accord. You can't destroy negative energy, but you can work with it to make it leave, by overcoming it with your own energy. But you don't want to anger another spirit, that's not the Taoist way. Either they are using your energy to protect them or they want to tap into yours to get themselves to a higher level.

Readership:

Dr. Erzsébet Rőth
Dr. György Lázár
Dr. Csaba Gaál

Publisher:

Dr. Mihály Boros

Cover design:

Attila Pálfi

Press:

Innovariant Ltd.
3 Textilgyári Rd., H-6725 Szeged

Volume: 7.5 (A/4) printed sheets, 120 pages, 285 figures.

ISBN 963 482 785 3

© Prof. Dr. Mihály Boros, 2006

Introduction

"Surgical techniques" is a subject relating to the principles of surgery. Traditionally it discusses instrumentation, tools and sterile techniques used to perform safe operations by generations of surgeons. A relatively new, but continuously expanding element is linked to the development of clinical surgery. This part involves surgical research on the pathophysiology of the perioperative period, and scientific studies on the consequences of invasive procedures on the body functions and on the relationship of surgery and patient care in general. These aspects are of utmost importance for the achievement of good surgical results. In brief, "surgical techniques" is concerned with the methodology of classical surgery, and may also be regarded as the deontology of modern surgery (*deontology* = theory of obligations).

This handbook is based on the topics presented on the graduate courses at the Institute of Surgical Research at the University of Szeged. These courses do not cover all aspects of clinical surgery; the intention is rather to give a general overview of basic techniques which could be used in practice in all major fields and subspecialties. There are a number of conventional surgical techniques that have been in use for some time and the scalpel is the symbolic instrument of these fields. However, it is being replaced by new and more effective surgical tools, sophisticated computer technology and techniques such as laser, robotic or minimally invasive surgery. If we wish to be at the forefront of these advances, the new methods should also be discussed.

The volumes have been compiled by the staff and PhD students of the Institute (Dr. Ágnes Adamicza, Dr. Mihály Boros, Dr. Tamás Jánossy, Dr. József Kaszaki, Dr. Andrea Szabó, Dr. Csilla Torday, Gabriella Varga, Dr. Gábor Erős and Dr. Miklós Czóbel), together with Dr. László Szalay (Department of Ophthalmology), Dr. Zsolt Bella (Department of Oto-Rhino-Laryngology) and Dr. Zoltán Bajory (Department of Urology). The editor wishes to acknowledge the creative illustrations by Drs Miklós Czóbel and László Szalay and Mrs. Kálmánné Csíkszentimrei. The activities of Dr. Miklós Czóbel have made it possible to maintain a highly effective website (http://web.szote.u-szeged.hu/expsur) where the main parts of this book can be found.

The ROP-3.3.1-2005-02-0001/34 project has led to an infrastructure for skills training where specific invasive techniques can be safely practised and mastered. We hope that the new skills laboratory at the Institute of Surgical Research, this handbook and the website (http://web.szote.u-szeged.hu/expsur/rop/index.htm) will stand the test of time, and that many medical students will benefit from them.

Mihály Boros

November 2006, Szeged

Table of contents

Introduction 3

Table of contents 4

I. Asepsis and antisepsis 9
- 1. Historical overview 9
- 2. Asepsis and antisepsis in surgical practice 10
- 3. Surgical infections, sources of wound contamination, interventions 11
- 4. Types of surgical wound contaminations and their classification 12
- 5. Prevention of wound contamination 12
- 6. Risk factors of wound contamination 13
- 7. Postoperative wound management 13
- 8. Sterilization, elimination and inactivation of pathogens 14
- 9. Disinfection 14
- 10. Asepsis 14
  - 10.1. Preparation of the skin before the operation 14
  - 10.2. Disinfection and scrubbing of the skin before the operation 15
  - 10.3. Isolation of the operating area (draping) 15
- 11. Basic rules of asepsis in the operating theater 16
  - 11.1. Personnel attire in the operating room 16
- 12. Scrubbing, disinfection and gowning in general 16
- 13. Personnel attire and movement in the operating room 20
- 14. Basic rules of asepsis in the operating room 21
- 15. Further important items to ensure asepsis and to avoid wound contamination 21
- 16. Duties related to asepsis in the postoperative period 21
- 17. Surgical antisepsis 21

II. The operating room 22
- 1. Furniture, basic technical background 22
- 2. Standard equipment 22
- 3. The operating room personnel 23
  - 3.1. Organization of the operating room personnel and their duties 23
- 4. Positioning of the surgical patient 23

III. Surgical instrumentation. Basic surgical instruments and their use 25
- 1. Cutting and dissecting instruments 25
- 2. Grasping instruments 26
- 3. Retracting instruments 28
- 4. Wound-closing instruments and materials 28

IV. Basic wound-closing methods: sutures and clips 32
- 1. Types of sutures 32
- 2. Rules of wound closure 32
- 3. Correct position of the needle holder 32
- 4. Interrupted sutures 33
  - 4.1. Simple interrupted suture *(sutura nodosa)* 33
  - 4.2. Vertical mattress suture *(sec. Donati)* 33
  - 4.3. Vertical mattress suture *sec. Allgöwer* 33
  - 4.4. Horizontal mattress suture 33
- 5. Continuous sutures 33
  - 5.1. Simple continuous suture (furrier suture, *sutura pellionum*) 33
  - 5.2. Locked continuous suture 34
  - 5.3. Subcuticular continuous suture 34
  - 5.4. Purse-string suture 34
- 6. Methods of wound closure 34
  - 6.1. Suturing with simple interrupted knotted stitches (skin and subcutis closure) 34
  - 6.2. Suturing with *Donati* stitches (skin closure) 35
  - 6.3. Wound closure with metal clips *(agrafe)* 35
  - 6.4. Other wound-closing methods 36
- 7. Sutures in different tissues 36
  - 7.1. Failures of suturing technique 36
  - 7.2. Removing sutures 36

8. Surgical knots 37
  8.1. Types of surgical knots 37
  8.2. Two-handed knots 37
    8.2.1. Reef knot or sailor's knot 37
    8.2.2. Surgeon's knot 38
    8.2.3. Viennese knot 39
    8.2.4. Instrument tie 40
  8.3. Knotting under special circumstances 40
    8.3.1. Knotting close to the surface 40
    8.3.2. Tying under tension 41
    8.3.3. Tying knots in cavities 41
9. Wound closure in separate layers 42
  9.1. Approximation of tissues in the depths 42
  9.2. Closure of the subcutis 42
  9.3. Skin stitches 42
10. Drainage 42
  10.1. Passive drainage 42
  10.2. Active drainage (with negative pressure): open, open-closed and closed tube systems 43
  10.3. Important localizations of drainage 44
  10.4. Drain removal 44

V. The operation 45
1. Basic surgical interventions 45
2. Preparations for an operation 45
3. Informed consent 45
4. Operative risk 46
  4.1. Acute risk factors in surgery 46
  4.2. Chronic risk factors in surgery 46
5. Preoperative management 46
  5.1. Evaluation of preoperative investigations 47
6. The preoperative preparation 47
7. Postoperative complication 47
  7.1. Complications of anesthesia 47
  7.2. Complications depending on the time of occurrence 47
    7.2.1. Intraoperative complications 47
    7.2.2. Postoperative complications 47
      7.2.2.1. Postoperative fever 48
      7.2.2.2. Complications of wound healing 48
      7.2.2.3. Postoperative nausea and vomiting 49
  7.3. Complications associated with the operative field 49
8. Minor surgery 49
  8.1. A short historical survey of local anesthesia 49
  8.2. Local anesthetic drugs 49
    8.2.1. Main classes, the "I" rule and the dangers of local anesthesia 50
    8.2.2. Dosage of local anesthetics and duration of anesthesia 50
  8.3. Main types 50

VI. The perioperative period 51
1. General preoperative preparation 51
  1.1. Rules, interventions 51
  1.2. Medication 51
  1.3. Instruments 51
2. Special preoperative preparation 51
  2.1. Depending on the type of the operation 51
  2.2. Preoperative preparation depending on the (organ) system 51
3. The perioperative fluid balance 52
  3.1. General rules 52
  3.2. Perioperative fluid requirements 52
4. Intravenous fluids 53
  4.1. Crystalloids 53
  4.2. Colloids 53
5. Perioperative fluid therapy in practice 54
6. Clinical evaluation of the effectiveness of fluid replacement 54
7. Tools of volume correction: injections, cannulas, tubes 55
8. Types of injection techniques 56
  8.1. Intracutaneous (ic.) injection 56
  8.2. Subcutaneous (sc.) injection 56
  8.3. Intramuscular (im.) injection 56
  8.4. Intravenous (iv.) injection 57

9. Complications of injections 57
10. About veins in details 57
    10.1. Technique of blood sampling 58
    10.2. Infusions 59
    10.3 Infusion pumps (IP) 61
    10.4. Central venous catheterization, venasection, venous cut-down 61

VII. Bleeding and hemostasis in surgery 63
1. Hemostasis 63
2. Main types of hemorrhage 63
3. Clinical classification 63
4. Direction of hemorrhage 64
    4.1. Gastrointestinal hemorrhage 64
    4.2. Causes of gastrointestinal hemorrhage 64
5. Preoperative – intraoperative – postoperative hemorrhage 64
6. Surgical hemostasis 65
    6.1. Historical background 65
    6.2. Mechanical methods – temporary and final interventions 65
    6.3. Thermal methods 66
    6.4. Chemical-biological methods 67
7. Intraoperative diffuse bleeding 68
    7.1. Main causes 68
    7.2. Management of intraoperative diffuse bleeding 68
    8. Replacement of blood in surgery (for details, see transfusiology) 68
    8.1. Historical background 68
    8.2. Auto(logous) transfusion 68
        8.2.1. Preoperative autologous donation = predeposit transfusion 68
        8.2.2. Blood salvage 69
        8.2.3. Autotransfusion – adjuvant therapy 69
    8.3. Artificial blood 69
9. Postoperative bleeding 69
10. Local signs and symptoms of incomplete hemostasis 69
11. General symptoms of incomplete hemostasis 69

VIII. Hemorrhagic shock 70
1. General remarks 70
2. Types of shock 70
3. The essential patterns of circulatory shock 70
4. Anamnesis of shock 70
5. Compensatory mechanisms after blood loss 70
    5.1. Baroreceptor reflex 70
    5.2. Chemoreceptors 71
    5.3. Endogenous vasoconstrictors 71
    5.4. Brain ischemia 71
    5.5. Changes in renal water metabolism 71
    5.6. Reabsorption of tissue fluids (“*fluid shift*”) 71
6. Decompensatory mechanisms after blood loss 71
    6.1. Cardiac failure 71
    6.2. Acidosis 72
    6.3. Central nervous system depression 72
    6.4. Disseminated intravascular coagulation (DIC) 72
    6.5. Reticuloendothelial system dysfunction 72
7. Stages of hemorrhagic shock 72
    7.1. Compensated shock 72
    7.2. Decompensated shock 72
    7.2.1. Main microcirculatory phases during decompensation: 72
    7.3. Irreversible shock 73
8. Signs of progressing shock 73
9. Ischemia-reperfusion injury 73
10. Intestinal mucosa injury 73
11. Shock diagnosis 73
12. Relationship between mortality and time elapsed from injury to therapy 73
13. Treatment of hemorrhagic shock 73
14. Signs of cardiovascular stabilization 75
15. Medical – legal pitfalls 75
16. Variations in physiological responses to hemorrhagic shock 75

IX. Wounds 76
  1. Classification of accidental wounds 76
    1.1. Morphology / classification depending on the penetration route 76
    1.2. Classification according to “cleanliness” – bacterial contamination 76
    1.3. Classification depending on the time since the trauma 77
    1.4. Classification depending on the number of skin layers involved 77
    1.5. Classification depending on the factors affecting wound healing 77
    1.6. Classification depending on wound closure 78
  2. Surgical wounds 78
    2.1. Determinants of healing of surgical wounds 78
    2.2. Skin incision 78
    2.3. The requirements of skin incision 78
    2.4. Main types of skin incisions (see details later) 79
    2.5. Closure of surgical wounds 79
  3. Early complications of wound closure (See also sections I.4 and V.7.2.2.2) 79
  4. Late complications of wound closure 80
  5. Prevention of wound infection 80
  6. Signs of wound infections 80
  7. Phases of wound healing 80
  8. Wound healing disorders 81
  9. Wound management of accidental wounds 81
  10. Dressing – bandaging 84
    10.1. Types of bandages 84
    10.2. Layers of bandages 85
    10.3. Types of bandages 85
  11. Innovations in wound treatment 87
    11.1. *Lucilia sericata, Phaenicia sericata* (greenbottles) 87
    11.2. *Vacuum-assisted closure* therapy 87
    11.3. Biological dressings 87
      11.3.1. Human skin 87
      11.3.2. Xenogenous skin 87
      11.3.3. Skin supplements 87
      11.3.4. Biosynthetic materials (cultured tissues) 87
    11.4. “Wet wound healing” 87

SURGICAL TECHNIQUES, 2 – ADVANCED MEDICAL SKILLS 89

Preface 90

I. Laparotomy 91
  1. History of abdominal surgery 91
  2. Technical background of laparotomies 91
  3. Basic principles determining the type of laparotomy 91
  4. Recapitulation: Anatomy of the abdominal wall 92
  5. Principles of healing of laparotomy 92
  6. Prevention of wound complications 92

II. Incisions 93
  1. Longitudinal incisions 93
    1.1. Characteristics of longitudinal incisions 93
  2. Oblique incisions 93
    2.1. The basic type of oblique incisions 93
  3. Transverse incisions 94
    3.1. Basic characteristics of transverse incisions 94
  4. Special extraperitoneal incisions for staging 94

III. Laparotomy in surgical training 95
  1. General rules 95
  2. Middle median laparotomy 95
  3. Some important details 97

IV. Basic surgical procedures on the intestines. Appendectomy 98
  1. The history of appendectomy 98
    1.1. Recapitulation: relevant anatomy 98
    1.2. Open appendectomy 98

V. Anastomoses 101
- 1. Healing of the anastomosis 101
- 2. Causes of anastomosis insufficiency 101
- 3. The characteristics of a good technique 101
- 4. Complications 101
- 5. Anastomosis techniques 101
  - 5.1. Two-layered anastomosis technique 101
  - 5.2. Single-layered technique 102
  - 5.3. Stapler-made anastomosis 102
- 6. Surgical techniques of intestinal anastomoses 102
- 7. Closure of enterotomy 102
- 8. Surgical unification of bowel segments by end-to-end anastomosis 103

VI. Abdominal drainage 104
- 1. Historical background of invasive diagnostic procedures 104
- 2. Indication of diagnostic peritoneal lavage 104
  - 2.1. Open system 104
  - 2.2. Closed system 104
- 3. Therapeutic (chronic) lavage: peritoneal dialysis 104
- 4. Therapeutic (postoperative) rinsing drainage(see the basics in section IV.10) 105

VII. Basic thoracic surgical practicals 106
- 1. Types of pleural effusion 106
  - 2.1. Mechanism/causes of thoracic effusion formation 106
  - 2.2. General principles of treatment 106
- 3. Hemothorax 106
  - 3.1. Treatment of hemothorax 106
- 4. Pneumothorax (PTX) 106
  - 4.1. Etiology of PTX 107
  - 4.2. Clinical signs of PTX 107
  - 4.3. Types of PTX 107
  - 4.4. Closed PTX 107
  - 4.5. Open PTX 107
    - 4.5.1. Signs of open PTX 107
    - 4.5.2. Treatment of open PTX 107
  - 4.6. Tension PTX 108
  - 4.7. Signs and symptoms of tension PTX 108
- 5. Treatment of PTX 108
  - 5.1. Basic questions 108
  - 5.2. Treatment of simple PTX 108
  - 5.3. Treatment of simple PTX with needle thoracocentesis 108
  - 5.4. Emergency needle decompression 109
  - 5.5. Percutaneous thoracocentesis for the treatment of PTX 109
  - 5.6. Chest drain – chest tubes 109
- 6. Chest drainage system 110
  - 6.1. Indications 110
  - 6.2. Types 110
- 7. Flail chest 111
- 8. Cardiac tamponade 111

VIII. Tracheostomy 113
- 1. States evoking mechanical respiratory insufficiency 113
- 2. States evoking functional respiratory failure/insufficiency 113
- 3. Advantages of intubation and tracheostomy 113
- 4. The surgical technique of intubation – preparation of an upper tracheostomy 113

IX. Basics of minimally invasive surgery 114
- 1. A brief history of minimally invasive surgery 114
- 2. Present status of minimally invasive surgery 114
- 3. Advantages of minimal access surgery 114
- 4. The technical background of minimally invasive techniques. The laparoscopic tower 115
  - 4.1. Endoscopes 115
  - 4.2. Diathermy 115
  - 4.3. Suction and irrigation 116
- 5. Physiology of laparoscopy. The pneumoperitoneum 116
  - 5.1. Complications of pneumoperitoneum 116
- 6. Basic instruments for minimally invasive surgery 117
- 7. Laparoscopic cholecystectomy 118
- 8. Laparoscopic appendectomy 118
- 9. Training in a box-trainer 119

I. Asepsis and antisepsis

> *"A man laid on an operating table in one of our surgical hospitals is exposed to more chances of death than was an English soldier on the battlefield of Waterloo"*
> (Sir James Simpson: Hospitalism: its effects on the results of surgical operations. In: *Edinburgh Med J*, 1869).

1. Historical overview

19th century surgery was faced with four classical difficulties: pain, infection, obsolete technology and the enigmatic pathophysiological changes of the perioperative period. By the end of the "century of surgeons", three of these problems had been solved, and modern clinical surgery has been born.

The first milestone was reached on October 16, 1846, in Boston, when a patient of John Collins Warren (1778–1856) was successfully narcotized with ether by William Morton (1819–1868). According to the inscription in the Ether Dome of the Massachusetts Memorial Hospital: "*On October 16, 1846, in this hall, the former operating theatre occurred the first public demonstration of narcosis, which resulted in analgesia during a major surgical intervention. Aether sulfuricus was applied by William Thomas Green Morton, a dentist from Boston. Gilbert Abbot was the patient and a neoplasm of the jaw was removed by John Collins Warren. The patient declared that he did not feel any pain and he was emitted whole on December 7. This discovery has spread from this room and opened a new era for surgery.*"

John Collins Warren (1778–1856) and William Morton (1819–1868)

Within some weeks, on December 21, 1846, Robert Liston (1794–1847) applied ether narcosis in London and James Simpson soon introduced chloroform narcosis (*On a new anaesthetic agent, more efficient than Sulphuric Ether. Lancet, 21 November 21, 1847: 549-550*). Hungary kept in line with the progress: on January 25, 1847, Lajos Markusovszky (1815–1893) tested the effects of ether on himself in Vienna and then together with János Balassa he performed the first operation involving the use of ether narcosis on February 8, 1847, in Budapest (the creation of the first Hungarian medical periodical *Medical Weekly Journal* (1857) and the Hungarian Medical Publishing Company (in 1863) were also among the merits of Markusovszky).

Lajos Markusovszky (1815–1893) and János Balassa (1814–1868)

Narcosis quickly became a relatively safe and generally accepted method of surgery. In 1893, Vilmos Vajna reported on the 3-year statistics of the German Surgical Society; 3098 cases were anesthetized, with only one death.

The initial attempts to prevent wound infection were by no means so successful. Surgical incisions were still followed by *irritative* fever, which sometimes lasted for only a few days and were accompanied by *pus bonum et laudabile* (good and commendable pus, sec. Galen), but even the most brilliant surgeons had to take into account the possibility of fatal postoperative infection. The terms "*hospitalism*" and "*hospital gangrene*" were used to denote postoperative infections. The frequency of these infections is well demonstrated by the incidence of puerperal fever (childbed fever): the average death rate in the First Department of Obstetrics at the Allgemeines Krankenhaus in Vienna was 9.92%, but on occasion the incidence was as high as 29.3% (in October 1842). At that time the mortality rate in hospitals in Edinburgh and Glasgow averaged around 40%, and in Paris it was as high as 59%.

In the 1840s, Ignác Semmelweis (1818–1865), a Hungarian obstetrician and Oliver Wendell Holmes (1809–1894) an American anatomist, came closest to verifying the causes. Finally, Semmelweis unequivocally identified that decomposing organic matter on the doctors' hands propagated infection, leading to the spread of puerperal fever, e.g. sepsis. On May 15 (?), 1847, Semmelweis introduced compulsory hand-washing with chlorinated lime. He issued a directive: "*All students and doctors who enter the wards for the purpose of making an examination must thoroughly wash and scrub their fingers and hands* *in the solution of chlorinated lime placed in basins at the entrance to the wards. One disinfection is sufficient for one visit, but between the examinations of each patient the hands must be washed with soap and water. Semmelweis".* In May 1847, the mortality from puerperal fever was still 14.5% whereas in August, following the institution of these measures, it was 1.2%.

Before the era of bacteriology this was a stroke of genius. Semmelweis had proved the effectiveness of asepsis, but the adverse circumstances prevented the rapid spread of his theory and his discovery did not become generally known.


SEMMELWEIS

Die Aetiologie, der Begriff
und
die Prophylaxis
des
Kindbettfiebers.
Von
Ignaz Philipp Semmelweis,

Pest, Wien und Leipzig.
C. A. Hartleben's Verlags-Expedition.
1861.

Ignác Semmelweis (1818–1865) *Die Aetiologie, der Begriff und die Prophylaxis des Kindbettfiebers* (1861)

At the beginning of the 1860s Louis Pasteur (1822–1895) elaborated the "*germ theory*" (his motto was *"chance prefers the prepared mind")*. Then, twenty years after Semmelweis, Sir Joseph Lister (1827–1912), a Scottish surgeon described the method of wound disinfection. In the operating theatre Lister sprayed carbolic acid (phenol) onto the instruments, onto the hands of the surgeon and also onto the wound, to kill microorganisms. His publication in 1867 set the trend of antisepsis (*On the Antiseptic Principle in the Practice of Surgery, Lancet*).



Sir Joseph Lister (1827–1912) and the first antiseptic operation

In 1881, Robert Koch (1843–1910) reported postulates whereby it became possible to verify that infectious diseases are caused by living microorganisms, i.e. bacteria:

1. "After it has been determined that the pathogenic organism is present in the animal body,
2. and after it has been shown that the organism can reproduce in the body,
3. and be transmitted from one individual to another, the most important experiment remains to be done…
4. to determine the conditions necessary for growth and reproduction of the microorganism."

In a further substantial step, Ernst von Bergmann (1836–1907) introduced sublimate antisepsis (1887) and steam sterilization (1886), and Curt Schimmelbusch (1850–1895) then initiated aseptic wound management. At the end of the 1880s, Lister realized that the treatment of wounds with antiseptics has a disadvantageous effect on wound healing. Furthermore, it was shown that the effects of chemicals are only superficial: they are not able to kill bacteria in the deep tissues. Lister later admitted that the aseptic method elaborated by the German school of surgeons was more advantageous than his own.

Surgical gloves were invented by William S. Halsted, chief surgeon at the Johns Hopkins University (1852–1922). In 1890, Halsted requested the Goodyear Rubber Company to prepare thin rubber gloves for the head scrub nurse (his later wife), Caroline Hampton, who suffered from dermatitis caused by the disinfectants. Joseph C. Bloodgood (1867–1935) who succeeded Halsted, used these gloves routinely from 1896, and the method proved to decrease not only the incidence of dermatitis, but also the number of postoperative wound infections.



William S. Halsted (1852–1922)

2. Asepsis and antisepsis in surgical practice

During surgery, the body's major defense against infection, the skin is broken and the inner surfaces of the body are exposed to the environment. Every attempt must therefore be made to prevent bacteria from entering the wound (*asepsis*) and to eliminate them if they have already entered (*antisepsis*).

Definition of asepsis

Asepsis covers all those procedures designed to reduce the risk of bacterial (or other, e.g. fungal or viral) contamination, e.g. through the use of sterile instruments and the gloved “no touch” technique. They include all of those prophylactic methods, working processes and behavioral forms by which microorganisms (bacteria, fungi and viruses) can be kept away from the patient’s organism and the surgical wound. The goal of asepsis is to prevent contamination. Asepsis can be ensured by the use of sterile devices, materials and instruments and by creating an environment that is poor in microbes.

Definition of antisepsis

Antisepsis relates to the removal of transient microorganisms from the skin and a reduction in the resident flora. Techniques may be applied to eliminate contamination (bacterial, viral, fungal and others) present on objects and skin by means of sterilization and disinfection. Living surfaces, the skin, the operating field and the surgeon’s hands can not be considered sterile.

In a wider sense, asepsis concerns an ideal state, in which the instruments, the skin and the surgical wound are free from pathogenic germs, while antisepsis includes all those prophylactic procedures designed to ensure surgical asepsis. Asepsis is what is primarily important. Asepsis is primary prevention.

Definition of sterility

Sterility is a microbiologically germ-free state of materials and items. This means that they are free from all kinds of pathogenic and apathogenic microorganisms, including latent and resting forms, such as spores.

3. Surgical infections, sources of wound contamination, interventions

Disorders appearing during medical care (e.g. allergies against drugs) or caused by medication (e.g. complications of transfusion) are referred to as iatrogenic harms. They include iatrogenic infections (since the Greek word *iatros* is linked to doctors and *hospitalis* reminds us of hospitals, the medical profession uses the word *nosocomial* as an epithet). Nosocomial infections may be manifested in different forms. Some of them are well defined and originate from a single microbiologic cause. However, in most cases a syndrome evolves which is caused by many different pathogens. Surgery is primarily affected by this problem. It is rather paradoxical that, 150 years after the discoveries by Semmelweis and Lister the incidence of nosocomial infections is currently increasing.

The infection of wounds (*surgical site infection;* SSI) is one of the main manifestations of nosocomial infections. In the US, it occurs in approximately 14–16% of the cases and SSI contributes to 77% of the cases of mortality among surgical patients. On the average, SSI increases the relative risk of death 2.2-fold and extends the hospitalization period by 5–15 days. When all surgical complications are considered, the average incidence of SSI is 1–3%, but in colon surgery the level may reach 10%. As nosocomial infections are a source of great expense to the patient, the surgeon, the health care system and the society, an understanding of the etiology and pathomechanism is of the utmost importance.



Staphylococcus aureus (20%), Coagulase-negative staphylococcus (14%), Enterococcus (12%), *Escherichia coli* (8%), *Pseudomonas aeruginosa* (8%), *Enterobacter* (7%), *Proteus mirabilis, Klebsiella pneumoniae, Candida albicans, Bacteroides fragilis, and other streptococci (2-3%). (Source: National Nosocomial Infections Surveillance (NNIS) System, Centers for Disease Control and Prevention (CDC), 1996*)

The main cause of postoperative wound infections is the endogenous flora (skin: Staphylococci and Streptococci; mouth: Staphylococci, Streptococci and anaerobes; nasopharynx: Staphylococci, Streptococci, Haemophilus and anaerobes; large bowel: Gram-negative rods, Enterococci and anaerobes; the urinary tract is normally sterile). In direct wound infection, the process is started by residual skin flora, dermal infection, the surgeon’s hands or a contaminated device or bandage, or can be transmitted from drains and intravenous catheters. Airborne infections originate from the skin and clothing of other patients and the staff and from the airflow in the hospital room or operating theater. In the case of hematogenic propagation, intravenous devices or a septic process in distant anatomical regions can be the source of SSI (Leaper DJ: *Risk factors for surgical infection. J Hosp Infect, 1999*).

Q. ***Is there a breathing technique that will make you more Yin or more Yang?***

A. It's not just breathing. If you eat very Yang foods, like meat and you are trying to be Yin, it won't work. If you work with the Fusion I formula you can balance the energy more easily than with outside forms of breathing or food. Fusion I and the Microcosmic Orbit are natural ways to balance your energy.

Q. ***The meditation seems so long.***

A. Once the channels are open you don't need to spend much time. The training period seems long, but the actual practice can be quite short. When the Thrusting Channels are open you won't need to do any muscle contractions, you won't need to do it in stages, you won't need to inhale several times. You will just sit down and in a couple of minutes you will find yourself in a state where the energy will be strong enough and the channels open enough that the energy will flow through the Thrusting Channels just using the mind itself. In fact, you will be able to do it anytime, not just during meditation.

You can imagine the work it takes to connect pipes from a reservoir to each household in a city. But once the pipe is connected all you have to do is turn the faucet on.

Q. ***What can close the channels?***

A. Stress of any kind can close the channels. Tension contracts everything—muscles as well as emotions. Also, if you stop practicing for a long time the channels will close. A path that's walked on every day will be clear, but if no one travels on it the weeds start growing and soon it is covered back over. That's why we stress the importance of daily practice. Even five minutes a day, is better than one hour once a week. Fusion I and Fusion II practice can be combined together, so you can check the organs, smile down, see what you need to do, and in a few minutes you can do some maintenance work. Then when you have more time you can go and clean the organs and the Thrusting Channels. In the beginning, the Fusion practice needs the mind to form the pakua, and collection points. It's like the Microcosmic Orbit: when you first learned it, it took a lot of concentration on each point and even when it started to run by itself it wasn't dependable. But after a while you could wake up in the morning and feel your Microcosmic Orbit running.

4. Types of surgical wound contaminations and their classification

Criteria for defining an SSI as superficial

1. Infection occurs within 30 days after an operation.
2. The infection involves only the skin and the subcutaneous tissue adjacent to the incision.
3. At least one of the following is present:
   - a purulent discharge from the surgical site,
   - at least one of the signs and symptoms of infection (pain, tenderness, localized swelling, redness or heat),
   - spontaneous dehiscence of the wound or deliberate opening of the wound by the surgeon (unless the culture results from the site are negative),
   - an abscess or evidence of infection on direct examination or reoperation, or histopathologic or radiological examination,
   - diagnosis of infection by a surgeon or attending physician.

Deep incisional SSI

These infections involve deep tissues, such as the fascial and muscle layers. They include infections involving both superficial and deep incision sites and organ/space SSIs draining through incisions. Criteria:

1. They occur within 30 days after surgery with no implant (up to 1 year after surgery if an implant is left in place),
2. The infections involve deep soft tissues, fascia and muscle layers,
3. At least one of the following:
   - Purulent drainage/organism isolated from an aseptically obtained culture.
   - Fascial dehiscence or deliberate opening of the fascia by a surgeon due to signs of inflammation.
   - An abscess or other evidence of infection noted below the fascia during reoperation, radiological examination or histopathology.
   - A surgeon declares that a deep incisional infection is present.

Organ/space SSI

These infections involve any part of the anatomy, in organs and spaces other than the incision, which was opened or manipulated during operation. Criteria needed for the diagnosis:

1. The infection occurs within 30 days after surgery or within 1 year if an implant is present and the infection seems related to the operation.
2. The infection involves a joint/organ/space, or anatomic structures opened or manipulated during the operation.
3. At least one of the following:
   - Purulent drainage from a drain placed into the organ/space.
   - An organism is isolated from a culture sample obtained aseptically from joint fluid or deep tissue.
   - An abscess or other evidence of infection involving a joint, organ or space during reoperation, radiological examination or histopathology.
   - A diagnosis of an organ/space SSI by a surgeon.



5. Prevention of wound contamination

Analysis of the potential sources of infection reveals the following origins of causative agents:

- patients waiting for operation;
- members of the operating team;
- the operating theater (e.g. air, air conditioning, water, etc.);
- devices for operation (e.g. drapes, threads, bandages, etc.).

Rules of asepsis must be kept in connection with all of the above factors as this is the only way to prevent wound infections.

Before the operation

- A careful scrub and preparation of the operative site (cleansing and removal of hair) is necessary.
- Knowledge and control of risk factors (e.g. normalization of the serum glucose level in cases of diabetes mellitus, etc.).
- Perioperative antimicrobial prophylaxis (e.g. antibiotics) in high-risk patients.

During the operation

- Appropriate surgical techniques must be applied (gentle tissue preparation, exact handling of bleedings, use of absorbable sutures, etc.).

- Change of gloves and rescrub if necessary.
- Normal body temperature must be maintained. Narcosis may worsen the thermoregulation. Hypothermia and general anesthesia both induce vasodilatation, and thus the core temperature will decrease.
- The oxygen tension must be maintained and hyperoxygenization should be applied if needed. Oxidative processes play an important role in protection against pathogens. Reactive oxygen radicals (especially superoxide anions) are the frontline of defense against surgery-associated pathogens. The activity of the NADPH-linked oxidase of neutrophils is pO_2-dependent (Km ~ 60 mmHg), and hypoxia therefore transitionally decreases the killing activity of leukocytes.

After the operation

- SSI evolves shortly (within 2 h) after contamination.
- Hand washing is mandatory and the use of sterile gloves is compulsory while handling wound dressings and changing bandages during the postoperative period.

6. Risk factors of wound contamination

Systemic factors

These include age (the elderly or young children), undernourishment, obesity, hypovolemia, impaired tissue perfusion and steroid therapy. Diseases connected to altered immune responses: diabetes mellitus, cirrhoses, uremia and immunosuppressed states are all risk factors. In the majority of these cases, the surgical intervention should be performed exclusively under aseptic circumstances in the sterile operating room. The patients must usually be isolated, and hospitalized in sterile rooms, with strict adherence to the rules of asepsis. Wound management should be performed under "*operating room circumstances*".

Factors related to the wound

These may be dead or devitalized tissue left in the wound, a hematoma, foreign bodies, including drains, sutures, dead space, improper skin scrubbing, disinfection and shaving, or a previously existing infection (local or distant).

Factors related to the operation

These include an incorrect surgical technique, inadequate handling of bleeding, long-lasting surgical interventions (longer than 2 h); intraoperative infections, nonsterile operating room personnel, instruments, improper air-exchange, hypothermia, and a long preoperative stay (hospitalization).

Factors related to the type of the operation

The risk factor may be the type of the operation itself, as in certain operations the risk of wound contamination is higher than average. Surgical wounds can be categorized according to the level of wound contamination as *clean*, *clean–contaminated*, *contaminated* and *dirty-infected* groups.

Classification	Description	Infection risk [%]
Clean (Class I)	An uninfected operative wound without acute inflammation and closed primarily. Respiratory, gastrointestinal, biliary and urinary tracts not entered. No break in the aseptic technique. A closed drainage is used if necessary.	< 2
Clean-contaminated (Class II)	Elective opening of respiratory, biliary, gastrointestinal or urinary tracts and with minimal spillage. No evidence of infection or major break in the aseptic technique. Example: appendectomy.	< 10
Contaminated (Class III)	Non-purulent inflammation is present. Gross spillage from gastrointestinal tract. Penetrating traumatic wounds < 4 h. Major break in the aseptic technique.	Approx. 20
Dirty-infected (Class IV)	Purulent inflammation is present. Preoperative perforation of viscera. Penetrating traumatic wounds > 4 h.	Approx. 40

Source: CDC, 1996

7. Postoperative wound management

The decisive factor is the rigorous maintenance of the rules of asepsis:

- the primarily closed wound is covered with sterile covering bandage for 48 h;
- hygienic hand washing before and after the wound management is mandatory;
- a sterile technique must be applied during change of the covering bandage.

8. Sterilization, elimination and inactivation of pathogens

Definition: this involves the removal of viable microorganisms (pathogenic and apathogenic microorganisms, including latent and resting forms such as spores), which can be achieved by different physical and chemical means and methods or by their combined effects, in killing or inactivating all living microorganisms and their latent and resting forms.

Autoclaves

Autoclaves are highly effective and inexpensive tools of sterilization. Their effectiveness is based on the fact that the temperature of steam under pressure exceeds 100 °C. At 108 kPa, it is 121 °C (vacuum has to be created). When the pressure is 206 kPa, the temperature of steam is 134 °C. The time needed for sterilization at 121 °C is 20 min and at 134 °C is 10 min. To be effective against viruses and spore forming bacteria the steam must be in direct contact with the materials. The effectiveness can be checked via the color change of the indicator tape placed on the packing. *Disadvantage:* autoclaves are unsuitable for heat-sensitive objects.

Gas sterilization by ethylene oxide

This agent is highly penetrative and active against bacteria, spores and viruses. It is suitable for heat-sensitive items. *Disadvantages:* it is flammable, toxic and expensive, and leaves toxic residues on sterilized items. Accordingly, instruments sterilized in this way need to be stored for a prolonged period before use (airing is needed).

Sporicidal chemicals – cold sterilization

Sporicidal chemicals are often used as disinfectants, but can also sterilize instruments if utilized for a prolonged period. *The advantages* of these methods are that they are inexpensive and suitable for heat-sensitive items. *The disadvantages* are that they are toxic and irritants. The most widely used liquid sporicidal chemical is 2% glutaraldehyde (Cidex). It is able to kill most bacteria and viruses within 10 min (spores can survive for 3 h).

Irradiation

Gamma rays and accelerated electrons are excellent for sterilization. They are mostly used for industrial purposes, e.g. the sterilization of disposable items (plastic syringes and needles) and materials (bandages) rather than sterilization in hospitals.

9. Disinfection

Definition: this is the reduction of the number of viable microorganisms by destroying or inactivating them on living or inanimate (nonliving) surfaces. It can be achieved with chemicals (disinfectants) such as glutaraldehyde, formaldehyde, quaternary detergents, etc. Some of these disinfectants are sporicidal, but they should generally not be used for sterilization because most items need a very long time (up to 10 h or more) of soaking in order to render them sterile.

Low-temperature steam

Most bacteria and viruses are killed by exposure to moist heat. This is usually achieved with dry saturated steam at 73 °C, applied for more than 10 min. This procedure is effective, reliable and suitable for instruments with a lumen. It is unsuitable for heat-sensitive items.

Chemical disinfectants

These are suitable for heat-sensitive items, but are less effective than heat. The goal is to destroy microorganisms by chemical or physicochemical means. Different organisms vary in their sensitivity to them:

- Gram-positive bacteria are highly sensitive.
- Gram-negative bacteria are relatively resistant.
- Clostridial and Mycobacterial species are very resistant.
- Slow viruses are highly resistant.

The use of antiseptics (their application, making the solutions, their effective concentration, the time needed for the effective disinfection of the different chemicals, etc.) is strictly regulated in official guidelines (see “*Handout of disinfection and disinfectants*” by the Hungarian National Health Center). The chemicals used include clear soluble phenolics, hypochlorites, alcohols and quaternary ammonium compounds.

10. Asepsis

Asepsis (in a wider sense) has become a fully elaborated routine procedure. The rules of asepsis must be maintained as concerns the patient, the operating room personnel, the operating theater, the operating room devices, the tools and the instruments. Surgical asepsis demands strict precautions, while working in a sterile field presupposes the understanding that violation of the technical rules may cause fatal infections.

10.1. Preparation of the skin before the operation

The skin harbors *resident* flora (these bacteria cause no harm unless drawn into the body through a break in the skin, e.g. *Staphylococcus epidermidis)* and *transient* flora (acquired from a contaminated source); the latter includes any type of bacterium that can live on the skin.

Bathing

It is not unequivocal that bathing lowers the germ count of the skin, but as regards elective surgery preoperative antiseptic showers/baths are compulsory. Special attention is paid to the operative site. This should be bathed with antiseptic soap (chlorhexidine or quaternol) the evening prior the operation.

Shaving

This makes the surgery, the suturing and the dressing removal easier. It must be done immediately prior to the operation, with the least possible cuticular/dermal injury; in this case, the wound infection rate is only 1%. The infection rate rises to > 5% if shaving is performed more than 12 h prior to the surgery (abrasions can cause colonization, which can lead to wound infection). Clippers or depilatory creams reduce infection rates to < 1%.

Preparation of the skin

This is performed immediately before the operation. Disinfectants are applied to the skin:

- 70% isopropanol (this acts by denaturing proteins; it is a bactericidal) short-acting;
- 0.5% chlorhexidine (a quaternary ammonium compound, which acts by disrupting the bacterial cell wall, it is bactericidal, but does not kill spore-forming organisms; it is persistent, with a long duration of action (up to 6 h), and is more effective against Gram-positive organisms);
- 70% povidone–iodine (Betadine, which acts by oxidation/substitution of free iodine; it is bactericidal and active against spore-forming organisms; it is effective against both Gram-positive and Gram-negative organisms, it is rapidly inactivated by organic material such as blood; patient skin sensitivity is occasionally a problem).

Surgical disinfectants can also be grouped according to color (e.g. Betadine, Kodan gefärbt, etc.) or colorless (e.g. Kodan farblos). The advantage of color is that the prepared area is visible, while colorless compounds are used when observation of the skin's own color is important (e.g. discerning the differences between necrotic and viable tissues).

10.2. Disinfection and scrubbing of the skin before the operation

- This is performed after the surgical hand scrub and before dressing (gowning, i.e. putting on sterile gowns). All supplies used (towels, gauze sponges, sponge forceps and gloves) must be sterile.
- Scrubbing is performed outward from the incision site and concentrically (see later). The prepped/disinfected area must be large enough for the lengthening of the incision / insertion of a drain.
- The *classical method*: 1. removal of the fat from the skin surface with petrol (twice); 2. antiseptic paint (1–5% iodine tincture) is applied twice immediately.
- The skin prep must be performed in accordance with the accepted and generally applied rules of the operating room. *Currently,* only antiseptic paint is applied (usually povidone-iodine) at least twice (but usually three times), alcoholic solutions (e.g. Dodesept) could be used in the case of sensitive skin, applied with sterile sponges (gauze balls) mounted in a sponge-holding clamp.
- In aseptic surgical interventions the procedure starts in the line of the planned incision, while in septic, infected operations it starts from the periphery toward the planned area of the operation. Washing with antiseptics is begun at the exact location where the incision will be made, moving outward in a circular motion. A "no touch" technique is used. An area already washed is not returned to with the same sponge.
- The disinfectant collections in body folds must be sponged up after the skin-scrubbing procedure in order to avoid skin inflammation and burns.

10.3. Isolation of the operating area (draping)

- After the skin preparation, the disinfected operating area must be isolated from the nondisinfected skin surfaces and body areas by the application of sterile linen textile (muslin) or sterile water-proof paper (nonwoven) drapes and other sterile accessories/supplements. The isolation prevents contamination originating from the patient's skin. Draping is performed after the surgeon has donned gown and gloves.
- The use of sterile self-attaching synthetic adhesives (affixed to the disinfected operating area) is questionable, because these can help residual bacteria come to the surface, due to the increased perspiration during the operation.
- As the deeper layers of the disinfected skin always contain residual bacteria, the skin can not be touched either by instruments or by hand.
- The isolation can be performed with disposable sterile sheets which are attached to each other where they cross by self-attaching surfaces. Nondisposable, permeable linen textiles are fixed with special Backhaus towel clips; usually four Backhaus clips fix the sheets. In the draping routine, four towels are placed around the immediate surgical site: this is the "*squaring-off*" (isolation) of the site.

- In general surgical operations (e.g. abdominal operations), the scrub nurse and the assistant carry out the draping with the specially folded sheets. The first sheet isolates the patient's leg. The *Mayo* stand is then moved to the end of the operating table. The second sheet is used to isolate the patient's head; this sheet is fixed by a *Jones* or *Schaedel* towel-clip to the guard, which shields the anesthesiologist from the operative field. Placement of the two side-sheets then follows.
- The isolated area is always smaller then the scrubbed area. After being placed on the patient, sheets can not be moved toward the operating area, but only toward the periphery, because pathogens can be transferred from the nondisinfected parts to the surgical area.
- A special full sheet may be applied, too. This is positioned so that a hole incorporated in it lies over the operative site.

11. Basic rules of asepsis in the operating theater

- Only those people whose presence is absolutely necessary should stay in the operating room.
- Activity causing superfluous air flow (talking, laughing, sneezing and walking around) should be avoided. The atmosphere of the operating theater must be quiet and peaceful; movement and talking are kept to a minimum during surgery. Talking releases droplets of moisture laden with harmful bacteria into the air around the sterile field.
- Entry into the operating theater is allowed only in operating room attire and shoes worn exclusively in the operating room. All clothing except the underwear must be changed. This complete change to the garments used in the operating theater should also apply for the patient placed in the holding area. Leaving the operating area in surgical attire is forbidden.
- The doors of the operating room must be closed.
- Movement into the operating room out of the holding area is allowed only in a cap and mask covering the hair, mouth and nose. If the mask becomes wet, it should be replaced.

11.1. Personnel attire in the operating room

- Strict personal hygiene is necessary for the operating room personnel. Taking part in an operation is permitted only after surgical hand washing and scrubbing. The scrubbing person must not wear jewels. Watches and rings should be removed. Fingernails should be clean and short; nail polish is forbidden. Surgical scrubbing must always be performed in accordance with the accepted and generally applied rules of the local operating suite.
- Surgical team members in sterile attire should keep well within the sterile area; the sterile area is the space that includes the patient, the surgical team members, the sterile equipment tables and any other draped sterile equipment.
- Non-scrubbed personnel should not come close to the sterile field or the scrubbed sterile person, they should not reach over sterile surfaces, and they should handle only non-sterile instruments.
- Scrubbed team members should always face each other, and never show their backs to each other. They should face the sterile field at all times.
- Any airway infection or an open excreting wound excludes participation in an operation.

12. Scrubbing, disinfection and gowning in general

Scrub suit

In order to minimize the risk of infection, it is essential that the correct procedure should be followed before entry into the surgical suites and operating areas. All personnel should wear scrub clothes. Surgical attire acts as a barrier that protects patients from exposure to microorganisms that could cause postoperative infections. This barrier includes surgical gloves, caps, masks, gowns, protective eyewear, waterproof aprons, and sturdy footwear. They must all be the right size and properly worn.

Surgical caps and face mask

The hair, mouth and respiratory tract are rich in bacteria. The cap should cover the hair completely. The mask should be tied securely. It must be comfortable to wear, as it will be worn throughout the procedure.

Masks are effective in preventing gross contamination from saliva during talking and coughing. Masks should cover the nose and mouth, fitting snugly across the bridge of the nose, at the edge of the cheeks, and under the chin. Masks should be changed between cases or when they become wet (usually from breath). They should never be worn dangling around the neck. Rubbing ordinary soap on glasses and polishing them is the most satisfactory way to prevent fogging. Positioning of the mask:



Correct



Wrong

The scrub preparation and surgical disinfection

- The surgical hand and arm scrub procedure must be performed in the scrub suite before entry into the surgical suite/operating room. To maintain the asepsis, the hand and arm scrub is performed in accordance with the basic rules of asepsis.
- Hands can not be made sterile. The aim of the scrub is to reduce the number of transient and resident bacteria. The scrub eliminates the transient flora of the skin and blocks the activity of most resident germs located in the deeper layers. The disinfectant forms a thin film layer on the skin, thereby hindering the resident bacteria from reaching the surface from the crypts.



Participation in a surgical intervention requires participation in the complete protocol of scrubbing and disinfection. Scrubbing must be performed in accordance with accepted and generally applied rules of the local surgical suite. Simple scrubbing with ordinary soap is NOT disinfection.



The goal of scrubbing is to reduce the quantity of transient and resident bacterial flora and to inhibit its activity.

- Traditionally, scrubbing is carried out as in the *Ahlfeld-Fürbinger* 2-phase scrub. This consists of mechanical cleansing with a brush for 5 min, and rubbing with a disinfectant hand scrub agent for 5 × 1 min. Today, mechanical cleansing is restricted to the nails.
- Mechanical cleaning is the first phase of scrubbing. This first phase usually lasts for 3 min (5 min maximum).
- The second phase is disinfection. The most commonly used disinfectants include alcohol, phenol, hexachlorophene, iodine or chlorhexidine. Examples of trademarks are Dodesept Hand, Promanum N, Septoderm Hande, Skinman Intensive, Bradoderm, Spitaderm, Betadine, Betaisodona (iodine solution) and Sterillium (alcohol solution). 5 × 5 mℓ should be used, each dose for 1 min.
- Personnel must enter the operating theatre immediately after the scrub. The arms should be flexed at the elbow and the forearms should be up; the touching of nonsterile surfaces should be avoided.

The mechanical phase in detail

- Remove watch, rings, bracelets, etc.
- Cut the nails if necessary and clean the subungual areas with a nail file.
- Turn on the tap and adjust the water to an appropriate temperature and flow rate.
- Wash the hands and forearms thoroughly with liquid or foam soap. Rub each side of each finger, between the fingers, and the back and palm of the hands with soap. After the hands have been scrubbed, the arms are scrubbed. Rub the soap on each side of the forearm from the wrist to the elbow to at least 3 finger-breadths above the elbow, keeping the hand higher than the arm at all times. This prevents bacteria-laden soap and water from contaminating the hand. If at any time the hand touches anything nonsterile object, the scrub must be lengthened by 1 min for the area that has been contaminated.
- Rinse the hands and arms with water, keeping the hands above the level of the elbows, and allow the water to drain off the elbows.
- Take a sterile brush in one hand and the soap in the opposite one. Make a good lather on the brush and brush the nails and finger tips only. The brushing of any other part of the hand is forbidden.
- Finish the scrubbing and put the brush aside.
- Rinse both hands and arms thoroughly with tap water. This rinsing must be thorough, because any soap remaining on the skin may decrease or inhibit the effects of disinfectants.

Phases of scrubbing, 1.

Hygienic hand wash

Exposure of the sterile brushes...

and taking them

Phases of scrubbing, 2.



Mechanical cleaning of the nails

Phases of scrubbing, 3.



Cleaning of the hands and nails with soap

Phases of scrubbing, 4.



Phases of rinsing



This is forbidden!

Disinfection in detail

- Keep the palm below the tubing of the dosing wall-apparatus so that the hand is at the same level as the eye of the photoelectric cell. Do not touch either the apparatus or the tubing. If the hand is held properly, one dose of antiseptic will flow into the palm. The hands and arms are rubbed thoroughly with the antiseptic for 1 min. Repeat the process 4 more times.
- The disinfected area should extend to one finger under the elbow. The unwashed skin should not be touched with the clean hands.
- This process should be repeated four times more, but the affected area will be smaller and smaller. The second time, the dividing line is three fingers under the elbow; the third time, it is on the middle of the forearm. The fifth dose is rubbed only in the hands.
- If the disinfectant contains alcohol, it must not be rinsed. It is allowed to dry on the skin, in order to form a film. This film blocks residual bacteria from reaching the surface and it inactivates those which possibly appear there. If the disinfectant contains detergent, the scrub nurse gives a sterile towel with which to dry the hands.

Phases of disinfection, 1.



Correct



Wrong

Phases of disinfection, 2.



The gowning procedure

The scrubbed personnel enter the surgical suite immediately after the scrub. The hands are held above the elbows, in front of the chest. They go to the *Schimmelbush* container which is on a stand, and open the cover with the foot pedal. The further steps of gowning are as follows:

- Pick up a sterile gown with the right hand using the left hand to prevent others from pulling out. The gown is folded so that the inner surface is exposed to you when you pick it up. If you are gowning yourself, grasp the gown firmly and bring it away from the container. Never touch the outer surface.

- Remain well away from nonsterile objects while dressing, in order to allow a wide margin of safety.
- Hold the gown at the edges of the neck piece, away from your body and the container, and sufficiently high that it will not touch the floor.
- Holding the gown by the inside at the neckline, allow it to unfold gently, ensuring that the gown does not come into contact with anything that is not sterile.
- Gently shake the folds from the gown and insert both arms into the armholes, keeping your arms extended as you do so. Wait for the scrub nurse to assist you by pulling the gown up over the shoulders and tying it.
- The assistant / scrub nurse stands at the back and grasps the inner surface of the gown at each shoulder. The gown is pulled over the shoulders and the sleeves up over the wrist. The scrub nurse assists you by fastening the gown at the back.
- Meanwhile the cuffs of the gown can be adjusted. If there is a band, use it to fix the cuff. The assistant ties the bands at the back of the gown and the longer bands at the waist as well. Do not try to give these bands to the assistant, because you would risk touching a non-sterile person. The only exception is when the bands on the waist are sewn on the front of the gown. In this case you should cross your arms, grasp the contralateral bands and keep them away from you. The assistant then grasps and ties them without touching the gown.

Handling of the sterile gown



Correct

Wrong

Pulling out the gown



Wrong

Unfolding the gown



Phases of gowning



Gowning procedure



Correct

Wrong

Tying of the gown, 1.



Tying of the gown, 2.



Correct

Wrong

Tying of the gown, 3.



Forbidden

Effective ”sterile” area





Certain parts of the gown can not be regarded as sterile (!)

- the back and the armpits;
- the areas lateral to the armpits;
- below the waistline;
- the sleeves above the elbow, 10 cm from the shoulders.

Gloving

- Surgical gloves are made of latex or hypoallergic materials. Gloving is assisted by a scrub nurse already wearing a sterile gown and gloves. Surgical gloves are packed and sterilized in paper bags.
- The sterile nurse holds the left hand glove open with her fingers beneath the cuff so that her glove does not come in contact with your skin. The palm of the glove faces you. The sterile nurse holds the left hand glove open with her fingers beneath the cuff so that her glove does not come in contact with your skin. The palm of the glove faces you. Put two fingers of your right hand into the opening; pull the inner side of the glove toward you so that a wide opening is created. Slip your left hand into the glove so that the glove cuff covers the sleeve cuff.
- When you put on the right hand glove, place the fingers of your gloved left hand under the right glove cuff to widen the opening and thrust your right hand into the glove.
- You may now adjust your gloves so that they fit comfortably on the hands.

Gloving of the left hand



Gloving of the right hand



The gloved hands

To diminish friction between the skin and the glove, sterile talcum powder is used. The gloves have been lightly coated with powder. Powder entering into the abdominal cavity may lead to adhesions. When you are wearing a cap, a mask, a sterile gown and gloves, you are ready to participate in the operation.

Removing gloves

When removing the gloves, you should touch only their outer surface. In this way you can retain the cleanness of your hands if you change gloves during operation and protect yourself from infections. Grasp the cuff of your dirty left-hand glove and pull it down to the middle of the palm so that it hangs down from your finger in inside-out mode, and then repeat the process with the other one. Now you can take off both gloves one at a time without touching the dirty outer surfaces.

Removing the gloves



13. Personnel attire and movement in the operating room

- Sterile personnel should remain well within the sterile area. Operating team members should move about the suite as little as possible. Excessive movement leads to dust and air currents with the resulting spread of bacteria. Sterile team members face each other and also face the sterile field. Their backs are never turned toward the sterile field (it must be remembered that the back of the gown should be considered nonsterile).
- Hands must be kept within the sterile boundary of the gown.
- Sterile hands must not touch the cap, the mask or the nonsterile parts of the gown. Even spectacles must

not be touched; a nonsterile assistant must be asked to adjust them. You should use only sterile instruments and touch only sterile surfaces (e.g. the patient and the table covered with sterile sheets). Contact between sterile devices and objects of unknown sterility involves the risk of contamination.

- You must not stretch out your hand to attempt to catch falling instruments and you are not allowed to pick them up. Do not take any instrument from the instrument stand; ask the scrub nurse to give it to you.

14. Basic rules of asepsis in the operating room

- The operating room personnel must work in accordance with the rules of asepsis so as to ensure an aseptic germ-free wound state.
- Sterile personnel can handle only sterile equipment.
- If the sterility of an item or a person is questionable, this item or person is considered contaminated.
- Sterile tables are sterile at table height only.
- Sterile objects and surfaces in the air become unavoidably contaminated after a while.
- Humid sterile surfaces become contaminated because of capillary activity (e.g. sterile package and sheets become humid). This is called *strikethrough* contamination.
- The edges of boxes and pots can not be considered sterile. This means that the edge of any container that holds sterile supplies is not sterile.
- The skin (e.g. the field of operation) can not be considered sterile; however, it is obligatory to apply aseptic operating techniques.

15. Further important items to ensure asepsis and to avoid wound contamination

- During certain operations (e.g. after the opening of the bowel) the gloves are presumably contaminated by pathogenic microorganisms and must be changed. The gloves must also be replaced if they become damaged during sustained operations, and naturally between two operations. In the latter case, repeated disinfection or a new scrubbing procedure too is needed.
- Potentially contaminated instruments must be dropped at once into the waste bucket (e.g. scalpels used to incise the skin or to open a bowel) and must be replaced by new, sterile instruments.
- The surgical wound must be covered with a sterile wound cover.
- Closed circuit drainage must be applied for the drainage of oozing blood or confluent fluid collected in the wound.
- Easily cleanable and sterilizable metal instruments or disposable instruments and suture materials, plastic cannulas, drains and vascular prostheses must be used.
- Aseptic and septic operations must be separated in both time and space, and particularly in time. Aseptic operations (e.g. hernia operations, thyroidectomy or varix operations) must be carried out in a sterile (aseptic) operating room, and septic operations (colon surgery, appendectomy, hemorrhoidectomy and fistulas) in a septic operating theater. If these can not be separated spatially, aseptic operations must be carried out first and the septic cases only later. After these surgical interventions have been completed, the operating theater must be cleaned up and disinfected.

16. Duties related to asepsis in the postoperative period

- Bandages should be changed only when this is indicated.
- Bandages are changed first on aseptic patients.
- Bandages are changed with sterile instruments.
- Before and after bandage change hand washing is mandatory with antiseptic soap and new sterile gloves should be used for every case.

17. Surgical antisepsis

The basis of antisepsis is the killing or inactivation of pathogenic germs which have gained access to the wound. This is much less effective than prophylaxis. Antiseptic solutions (hydrogen peroxide or Betadine) or powders (boric acid, etc.) can be used locally, or antibiotics can be applied locally or systemically. The prophylactic use of antibiotics is not indicated in clean cases (except when implantation is performed), whereas in cases of contamination or dirty-infected operations antibiotic prophylaxis or treatment is mandatory (see Ministry of Health directives).

Fusion I and II are more complex and at the beginning you have to develop a different technique to get them running. I just look in the cauldron and it's like a slide projector: I can see everything. Then you can add the collecting of the energy and the blending process.

Everyone we know who has practiced Fusion II for a year or so, can do the creation cycle in a couple of minutes. As you practice and keep adding more details, sooner or later it becomes automatic. If you do Fusion II on a daily basis you will begin to get faster and faster. You will be able to look inside and see what's going on. When the process becomes automatic you open a whole area of possibilities. It will give you more time to practice because you will be doing it so fast. It will be there when you sink into sleep. It will be there when you wake up in the morning.

When you tune into your organs, your organs will have more say over what they want and what they do. So when you work with the formula correctly, the organs will love it. They will have the space and time to be themselves. The brain can be overworked and pushed too hard. It can force any organ to work until it's destroyed. You can see this in people who take drugs to control their emotions.

But when the situation is balanced by using the Microcosmic Orbit, the organs get a chance to balance themselves. The brain has a say but the organ also has a say. Then you can achieve a balance of energy when the intellect and the organs are working together. At this stage, when the senses are drawn in, not distracted and running around, you will feel calm. Gathering and conserving energy is good in itself.

The next thing that happens is that you can begin to gain Real Knowledge. Real Knowledge is beyond intuition; it comes from within and you make better choices and decisions. This Real Knowledge is an inner guide which sometimes manifests in dreams from the unconscious. It can show you a direction in life. You know yourself that these dreams are rare. In the past they only came when you were at a crossroads and there was some danger. But through the practice with emotions, organs and mind, you develop that interior communication that allows you access to Real Knowledge, so you're not operating in a state of emergency but from a state of balance and calm. Those

II. The operating room

1. Furniture, basic technical background

- The operating complex consists of many areas: dressing rooms, scrub suite, preparing rooms, and operating theaters. The floor area of an operating room is usually 50–70 square meters; it is well lighted and artificially ventilated. There is air-conditioning, and there is generally no window. The operating complex must be architecturally separated from the wards and intensive care unit.
- The temperature is normal ambient; the relative humidity is between 30% and 60%. In modern operating rooms, higher atmospheric pressure is created by *laminar air flow* equipment, which makes a nonturbulent inflow of clean air. Air movement is from clean to less clean areas.
- The walls are covered with tiles up to the ceiling, and the floor is gap-free. The wall and floor are easy to clean and disinfect.
- Doors are automatic. Personnel enter though a lock system. The staff change clothes and wear surgical attire and shoes worn exclusively in the operating room, or shoe covers when entering.
- All items of furniture have wheels. The operating room is supplied with a central or portable vacuum system and pipes for gases (compressed air, oxygen and narcotic gas).

2. Standard equipment

Operating lamp
This lamp provides cold, convergent light and can be positioned in any required position. It is supplied with a sterile handle via which the surgeon can himself adjust the lamp during the operation.

Operating table

- This is fully adjustable for height and degree of tilt in all directions; the surface is covered with a firm pad that can be removed for cleaning. Many accessories are used to meet the needs of different types of surgery. The table top is sectioned in several places and may be reflexed or extended, or flexed at one or more hinged sections. The table may be tilted laterally or horizontally, and raised or lowered from its hydraulic base. Sections of the table such as the headboard or footboard may be removed as needed.
- The position and height of the table are dictated by the situation of the organ to be exposed and by the surgeon's comfort. The ideal height of the operating table places the operative field approximately at the level of the surgeon's elbow when his arm is at his side. Positioning is very important.
- For operations performed in the abdominal region or under the umbilicus a pillow 10 cm in height should be placed under the patient's hip.
- A metal frame is to be found at the headboard of the table for the fixation of isolation sheets. This "*ether screen*" is a border, which separates the sterile surgical area and the nonsterile area of the anesthesiologists. It is strictly forbidden to lean an elbow on the frame or to reach above it.

Small instrument stand (*Mayo* stand): This is a special type of instrument table that is placed directly over (but not in contact with) the patient's leg. The most frequently used instruments are situated on it.

Back table (large instrument stand)
Extra supplies and additional instruments, except those in immediate use, are located here during surgery.

Kick bucket
Soiled (spilled) sponges and some instruments, e.g. the sponge-holding clamp used for the scrub preparation, should be dropped into these containers at the side of the table.

Anesthesia apparatus and other devices required by the anesthesiologist
The anesthesiologist and the assistant take their places behind the headboard of the operating table. They observe the patient throughout the operation. Major hemodynamic and vital parameters (e.g. blood pressure (BP), heart rate (HR), cardiac output (CO), intravascular volume, electrocardiogram (ECG), frequency of respiration, body temperature, etc.) are registered by a monitor with several channels. This is the area where devices required for airway securing and respiration are located: tubes, masks, laryngeal masks, Ambu balloon, portable respirator and instruments for endotracheal intubation (tubes, guiding wires, *Magill* forceps for nasotracheal intubation, laryngoscope, bite-blocking devices (*Guedel* tube or a short tube made of rubber) and a catheter for removing excretion). Other instruments too can be found here: braunules, "butterfly" needles (intravenous cannulas), central venous catheters, arterial catheters, infusion kits, ECG patches, a urine container sack and urine catheters of different sizes.

3. The operating room personnel

The positions of the operating team at the table will vary, depending upon the individual circumstances, and the situation of the organ. The surgeon stands on one side of the operating table. The first assistant is usually opposite the surgeon. On the other side of the table, beside the first assistant, opposite the operator, stands the scrub nurse. The second assistant stands on the left or right of the operator.



Positions of the sterile operating personnel around the operating table. A green line marks the sterile area; red colors show the border of this field. Stepping behind this line is forbidden.

3.1. Organization of the operating room personnel and their duties

Surgeon: This person ultimately guides the flow and scope of what happens in the surgical suite. He/she is primarily responsible for maintaining the asepsis, and also controlling all the activities in the surgical suite during the procedure.

Scrub nurse: She assists in the sterile gowning and gloving of the surgeon and his/her assistant. She is responsible for the maintenance of an orderly surgical field; she prevents contamination of the surgical field by the strict practice of aseptic techniques; she must call the attention of the surgeon and all members of the operating team to any error she perceives in the maintenance of asepsis.

First assistant: He/she works under the direct supervision of the surgeon and assists in such duties as hemostasis, suturing and wound dressing. The first assistant's responsibility is to position the operating table and the light, so that the field will be properly illuminated.

Second assistant: He/she ensures exposure of the operative field. He/she carries out the instructions of the surgeon or the first assistant. He/she should restrict his/her activities to holding instruments and retractors as instructed by either the surgeon or the first assistant;

Circulator / surgical technologist: This is a surgical team member who does not perform a surgical hand scrub or don sterile attire, and thus does not work within the sterile field; he/she is responsible for the nonsterile fields. It is his/her duty to deliver the patient to the operating room, safely position the patient, and to keep the operating room clean.

4. Positioning of the surgical patient

The surgical patient can be positioned on his/her back (standard positioning, e.g. abdominal operation), on his/her side (e.g. thoracic surgery), or on the abdomen (e.g. pylonidal cyst operation). Some types of positioning must be mentioned separately.

Trendelenburg position



This position was described by the German surgeon *Friedrich Trendelenburg* (1844–1924) in 1881. It is an upside down (45° head-down) position.

Indications: Depression of venous pressure (varicose vein surgery), or restraining of the small intestine from the pelvis (e.g. gynecology or laparoscopic surgery). Physiological effects of the Trendelenburg position: An elevated venous reflow, raised intracranial and intraocular pressure, and increased intragastric pressure. This leads to reflux of the gastric contents, and venous stagnation on the face and neck.

Reverse (or anti–Trendelenburg) position



The head is above the horizontal plane. Physiological effects: A reduced venous reflow leads to a CO fall, a mean arterial BP decrease, and an improvement in the functional residual capacity (FRC) of the lung.

Lateral and lateral decubitus position



Indications: Thoracotomies, renal, shoulder surgery and hip operations. This position can cause problems because it may change the respiratory conditions. In the lateral decubitus position (in addition to the lateral position), the table is flexed in the center, and a support is also applied. *Indication:* Nephrectomy. *Problems:* Direct caval compression leads to a decreased venous return and hypotension.

Lithotomy "legs up" position



Potential problems: Autotranfusion from the leg vessels will increase the preload (the effect on CO will depend on the patient's volume status), and the vital capacity is decreased**;** The effect on CO will depend on the patient's volume status. The risk of aspiration is increased: anesthesia should never be induced in this position!

Kraske (jackknife or "knee-chest") position



This is a modification of the prone position (lying on the abdomen). The patient lies in the prone position, with the table broken at its midsection so that the head and feet are lower than the midsection. *Indications:* Procedures in the perianal area, proctology and rectal and coccygeal surgery.

III. Surgical instrumentation. Basic surgical instruments and their use

Surgical instruments are precisely designed and manufactured tools. The nondisposable instruments must be durable, and easy to clean and sterilize. They should withstand various kinds of physical and chemical effects: body fluids, secretions, cleaning agents, and sterilization methods (high temperature and humidity). For this reason, most of them are made of high-quality stainless steel; chromium and vanadium alloys ensure the durability of edges, springiness and resistance to corrosion. Due to the constant improvements by surgeons and manufacturers, the number of instruments is so great that only their basic categories and the main representatives can be surveyed. Depending on their function, basic surgical instruments are categorized into four groups.

1. Cutting and dissecting instruments.
2. Grasping, clamping and occluding instruments.
3. Retracting and exposing instruments.
4. Tissue unification, wound-closing instruments and materials.

The groups of special instruments include dilators, suctioning-rinsing instruments, electric devices, dermatomes, endoscopes, fiberoptic devices, ultrasonic tissue destructors, cryotomes, laser devices, etc., some of which will be discussed below.

1. Cutting and dissecting instruments

The function of these instruments is to divide tissues, sutures, bandages, etc. These instruments have a sharp surface, either a blade or a point. This category includes knives, scissors, saws, osteotomes, drills, chisels, raspatories (used for the separation of the periosteum), *Volkmann* curettes, biopsy needles, diathermy pencils, etc.

Surgical knives – scalpels

During the dissection of tissues, scalpels cause the minimum of trauma. Instead of the conventional scalpel, disposable scalpels with a plastic handle or scalpels with a detachable blade are nowadays most commonly used. A disposable blade is attached to the stainless steel handle before the operation. A #3 handle is used with the smaller #10-15 blades, and a #4 handle with the larger #20-23 blades.



Wide-bladed scalpels with a curved cutting edge are used for the incision of skin and subcutaneous tissues. Thin-bladed sharp-tipped knives serve for the opening of blood vessels, ducts and abscesses. A bistoury blade looks like a hook and can be applied as a meniscus knife.

The use of scalpels

- The incision is started with the tip of the knife and continued with the cutting edge as soon as possible. Cutting is usually made from left to right or toward the surgeon.
- In long straight incisions, the scalpel is held like a fiddle bow: the knife is gripped horizontally between the thumb, index and middle fingers; the ring and little fingers can hold the end of the handle.





- In the case of skin and other tough tissues which are hard to cut, the handle of the knife is held between the thumb and middle and ring fingers and the index finger is placed on the back of the blade; this makes possible a strong and well-controlled incision.
- In short or fine incisions, the scalpel is held like a pencil, and cutting is made mostly with the tip. Neither the blade nor the handle far from the blade is grasped during the incision (see on page 78.).

Amputating knives

Amputating knives of different sizes are manufactured with a one- or two-sided cutting edge for limb amputations.

Scissors

Next to the scalpel scissors are most often used to divide tissues. Threads and bandages are also cut with scissors. Scissors are made in different sizes; their blades can be straight or curved (*Cooper* scissors). There are special angular scissors which are angled at the joint (e.g. *Lister* scissors). The tips of the blades can be blunt (like those of the *Mayo* and the finer *Metzenbaum* scissors with longer shanks, both of which can be used for the preparation of tissues) or sharp (like those of the iris scissors used in ophthalmology, or the vascular scissors that serve for the opening of vessels), but the tips can also be combined (i.e. one is sharp and one is blunt).



The use of scissors

The thumb and the ring finger are put into the finger rings. The index finger is placed on the distal part of the shanks, thereby stabilizing the instrument. In contrast with the scalpel, the cut is made from left to right or away from the surgeon. When cutting from left to right, the wrist is superextended. The cut is usually made close to the tips of the blades. Scissors are suitable for blunt dissection and also for the preparation of tissues. In this case, the scissors are introduced into the tissues with their tips closed, then opened, and dissection is carried out with the lateral blunt edges of the blades.



2. Grasping instruments

These instruments are used to grasp, pick up, hold and manipulate tissues, tools and materials. They can be applied for retraction, blunt dissection and hemostasis or occlusion of tubular structures - such as bowels or ducts – to prevent leakage of their contents.

Non-locking grasping instruments: thumb forceps

These are the simplest grasping tools. Forceps are made in different sizes, with straight, curved or angled blades (dental forceps). They can have blunt (dressing forceps), sharp (splinter forceps or eye dressing forceps) or ring tips. Forceps are used to hold tissues during cutting and suturing, retract them for exposure, grasp vessels for cautery, pack sponges and gauze strips in the case of bleeding, soak up blood and extract foreign bodies. Forceps should be held like a pencil; they grip when compressed between the thumb and index finger. This makes possible the most convenient holding, the finest handling and free movements. Forceps must never be held in the palm.





The teeth of tissue forceps prevent tissues from slipping; accordingly, only a small pressure is required to grasp tissues firmly. Thus, to grip skin and subcutaneous tissues, the tissue forceps is used most frequently. However, vessels, hollow viscera must not be grasped with them (risk of bleeding or perforation). For these purposes, or for holding sponges or bandages, dressing forceps should be chosen. These have blunt ends, with coarse cross-striations to give them additional grasping power. Skin gripped firmly with dressing forceps for a prolonged period can necrotize.

Locking grasping instruments: surgical clamps

For clamping, these tools have a locking mechanism which may be springy handles alone (e.g. a towel clip or a *Doyen* clamp) or combined with ratchet catches (e.g. hemostatic forceps). The design of clamps with a ratchet lock is similar to that of scissors: they have finger rings at one ends of the springy shanks, which are joined with a joint and jaws at their other ends. The ratchet catches interlocking the two shanks can be found before the finger rings. The opposing surfaces of the jaws vary, depending on the specific purpose for which the instrument has been designed: they can be smooth (e.g. *Klammer* intestinal clamp) or serrated (e.g. *Péan, Kocher* and *Lumnitzer* hemostatic forceps), and may (*Kocher* and *Lumnitzer*) or may not (*Péan* clamp) have teeth. Accordingly, traumatic (artery forceps) and atraumatic clamps (e.g. *Dieffenbach* serrafine, *Satinsky* artery forceps and intestinal clamp) can be distinguished. They should be held like scissors: the thumb and ring finger should be put into the finger rings, and the clamp is stabilized with the index finger. The lock can be opened by pressing down one of the finger rings while elevating the other one with the ring finger; in this way, the interlocking teeth are moved from one another.

Hemostatic forceps

These instruments are the main means of establishing hemostasis during an operation (also called hemostats): they are used to stop bleeding by grasping and clamping the ends of cut vessels or for preventive hemostasis by applying them before cutting the vessel.

Traumatic hemostatic forceps (crushing hemostats)

Péan, mosquito, *Kocher, Lumnitzer* (*Kocher* with long shanks). The jaws can be straight or curved, while the tips are blunt. The dissector has long shanks and the ends of the jaws are curved at 90°. Hemostatic forceps can be used to grasp and clamp tissues and materials (e.g. threads and sponges) and also for blunt dissection (*Péan*, mosquito and dissector).

Atraumatic hemostatic forceps (non-crushing hemostats)

These are applied if the damage to the vessels or tissues must be avoided because their function is expected later, e.g. if the circulation is to be restored after their removal. The *Dieffenbach* serrafine (bulldog) belongs in this group; its rubber-coated jaws are closed by springy shanks. The *Satinsky* tangential occlusion clamp permits a partial occlusion of the lumen of larger blood vessels. While an anastomosis is made, the blood flow below the clamp is undisturbed.

Instruments used for grasping and clamping other tissues and textiles

Towel-holding clamps: These serve to fix the draping towels to the ether screen, to one another and to the skin of the patient (*Jones* and *Schaedel* towel clips, and *Backhaus* towel clamp).

Doyen towel clamps are used to fasten wound towels to the edges of a skin incision. The *Mikulitz* peritoneum clamp is applied to grasp and hold the edges of the opening during draping and suturing. A cervix-holding or sponge-holding clamp is used to grasp the cervix of the uterus during gynecological operations, or to hold sponges for the scrub preparation of the surgical site or to soak up blood from the wound.



Needle holders

In modern surgery suturing is performed almost exclusively with curved needles that are held with needle holders designed for the grasping and guiding of needles. The needle holders grip the needle between the jaws, specially developed for this purpose; they usually have a ratchet lock. The *Mathieu* needle holder has curved shanks with a spring and a locking mechanism. It should be held in the palm. The *Hegar* needle holder resembles a hemostatic forceps, but the shanks are longer and the relatively short jaws are made of a hard metal. The serrations are designed to grip needles. During suturing in deep layers, needle holders with long shanks should be used.



3. Retracting instruments

Retractors are used to hold tissues and organs aside in order to improve the exposure and hence the visibility and accessibility of the surgical field. Hand-held retractors (rake retractors, plain retractors, e.g. *Roux, Langenbeck*, or visceral retractors*)* are held by the assistant. They cause minimal tissue damage because the assistant maintains tension on the tissues only as long as necessary. When applied properly, self-retaining retractors (*Weilander* self-retractor, *Gosset* self-retaining retractor, etc.) are of great help, but care should be taken not to damage the tissues when they are placed and removed.





4. Wound-closing instruments and materials

Surgical needles

Needles are classified according to the type of the eye, shaft (body) and point.

The eye of the needle is designed to cause minimal trauma to the tissue. Needle eyes may be conventional, closed or French-eyed, and there are also eyeless needles (atraumatic needles). French-eyed needles are the least traumatic of the eyed needles. Thread is pulled through the minute spring in the head, which locks it into the eye.



Atraumatic needles cause the least tissue trauma. They are manufactured with suture material already inserted. Needles are also produced that release the thread from the head if it is pulled sharply (controlled release needles).

The shape of its body can be triangular (and cutting) or curved/oval in its cross-section. In traditional cutting-edged needles, the tip of the triangle faces upward, while in reverse cutting needles, the tip of the triangle is to be found at the bottom.

The basic types of the needle points are cutting, taper and blunt.



Depending on their curvature, 1/4 circle (skin, eye or tendon sutures), 1/2 circle (muscle or fascia sutures), 3/8 circle (skin, fascia or gastrointestinal sutures), and 5/8 circle needles (muscle or urogenital sutures) are discerned. Needles are made in different sizes. Curved conventional cutting needles are used to suture firm, tough tissues (skin, subcutaneous, tissues, muscles and fascia). Round-bodied taper-point needles cause the smallest possible hole and the minimum damage in the tissues and blood vessels, the heart and the intestines are therefore sewn with such needles.



Suture materials
Suture materials are used to sew (approximate) wound edges and to ligate bleeding vessels. Surgical threads must meet different requirements: small caliber, high tensile strength, easy handling properties, sterilizability, inertness (causing minimum tissue trauma and reaction), good absorption characteristics or complete removability. They should hold securely when knotted, without fraying and cutting. Suture selection should be based on the knowledge of the physical and biological characteristics of the material, the healing rates of various tissues and factors present in the particular patient (infection, obesity, etc.). The most important properties of suture materials are as follows.

Important physical properties:
- caliber,
- tensile strength,
- elasticity,
- capillarity,
- structure (monofilament or multifilament),
- absorbent capacity,
- sterilizability.

Application properties:
- flexibility,
- slipping in tissues,
- knotting properties,
- knot security.

Biological properties:
- tolerance of tissues,
- tissue reaction.

The tissue reaction depends on the material: it is very strong in the cases of chromic catgut and catgut, moderate to linen, silk and polyamide, mild to Teflon and polyester, and minimal to polypropylene, polyglycolic acid, polydioxanone, steel and tantalum.

Threads are classified according to *absorbability* (absorbable or nonabsorbable), the *origin of the material* (natural or synthetic), and the *structure* (monofilament or multifilament: braided or twisted). Absorbable sutures are broken down in the body by enzymatic digestion or by hydrolysis. In multifilament threads, several strands of fiber are twisted or braided to make one strand; they are therefore stronger than monofilament threads. Multifilament threads are easy to handle, and can be knotted securely; however, due to their capillarity they facilitate the migration and proliferation of bacteria among the strands, and thus propagate infections. For this reason, it is reasonable to sew with monofilament threads in an infected field. In pseudo-monofilament threads, a multifilament thread is coated with a homogeneous smooth layer (e.g. with polybutylate), due to which the capillarity is lost. Coated threads combine the advantages of monofilament and multifilament threads: they are strong, easy to handle, and noncapillary.

According to the European Pharmacopoeia, the thicknesses of threads are given in metric units, 1/10 mm. For absorbable sutures, size #1 means a thread 0.1 mm in diameter (the diameter of threads can lie in the interval 0.001-0.9 mm); according to the United States Pharmacopoeia (USP), this is a 6-0 thread. For non-absorbable and synthetic threads, this corresponds to size 5-0. The cause of the discrepancy is that catgut is thicker when stored in alcohol than dry thread. The higher the size number, the thicker the thread; the more 0s in the number, the smaller the size. The size ranges from #7 to 12-0. On the Brown and Sharpe (B & S) sizing scale: #20 = 5, #25 = 1, #26 = 0, #28 = 2-0, #32 = 4-0, #35 = 5-0, #40 = 6-0, etc. The length of the thread is also standardized.

SUTURE DIAMETER AND SIZE

USP		DIAMETER LIMIT (mm)	METRIC SIZE
ABSORBABLE (Catgut Chromic and Plain)	NON-ABSORBABLE AND SYNTHETIC ABSORBABLE		
–	6–0	0.070 – 0.099	0.7
6–0	5–0	0.100 – 0.149	1
5–0	4–0	0.150 – 0.199	1.5
4–0	3–0	0.200 – 0.249	2
3–0	2–0	0.300 – 0.339	3
2–0	0	0.350 – 0.399	3.5
0	1	0.400 – 0.499	4
1	2	0.500 – 0.599	5
2	3.4	0.600 – 0.699	6
–	5	0.700 – 0.799	7

"Sutures are assigned a size which is based on a combination of diameter, tensile strength and knot security. The precise criteria vary depending on whether the suture is natural or synthetic fiber, absorbable, or nonabsorbable sutures" (USP, 1937).

The tensile force should be adjusted to the tensile strength of the thread. If it is too great, the thread is weakened, or broken. If the thread is pulled on a sharp surface (e.g. if it is pulled through the French eye of the needle), it becomes weaker. The thread should be cut where it was grasped with an instrument. Guiding the thread during suturing is the role of the assistant.

A. ABSORBABLE SUTURES

These are broken down in the body and eventually absorbed by digestion by lysosomal enzymes of white blood cells or by hydrolysis (synthetic absorbable sutures). Many of them are no longer in clinical use (e.g. catgut).

Natural materials

Today, the use of natural materials is very restricted.

Surgical gut (catgut)

This is made of collagen processed from the submucosal layer of the bovine or ovine intestine. Catgut is absorbed relatively quickly. Its tensile strength remains unchanged for 7–10 days; it is absorbed in 70 days. Treatment with chromium salt solution prolongs the absorption time. In this case, the tensile strength is retained for 10–14 days; the absorption time is 90 days. It is made in monofilament and multifilament form. It can be applied in an infected field. Plain catgut is used for the ligation of superficial blood vessels and the suturing of mucous membranes or subcutaneous tissues; chromic catgut is applied to sew the fascia and peritoneum.

Collagen

This is produced from the collagen fibers from the bovine flexor tendon in both plain and chromic form, and can be applied in the same fields as surgical gut.

Synthetic materials

These are extremely inert, and have great tensile strength. They can be used to suture and ligate in nearly all tissues (peritoneum, fascia, subcutaneous tissue and joints). One of their disadvantages is that they tend to drag through tissue rather than passing through smoothly. They are rigid and slippery, and they therefore need extra knots (up to 6 half hitches) to obtain a secure ligature.

Polyglycolic acid

Dexon is a braided suture made of polyglycolic acid and coated with polycaprolate. It has an excellent tensile strength (remaining unchanged for about 3 weeks) and excellent knot security. It is completely absorbed in 60-90 days.

Polyglactin

Vicryl is a braided suture manufactured from polyglactin 910 (and coated with polyglactin 370 copolymer) which is similar to Dexon. Its tensile strength is 65% on day 14; absorption is minimal up to 40 days, and complete after 56–70 days. It can be used to ligate or suture tissues, except where approximation under stress is needed (soft tissue surgery or vessel ligation).

Poly-p-dioxanone

PDS II is made of poly-p-dioxanone. It is a monofilament thread. The tissue reaction is minimal. The tensile strength on day 14 is 70%. Absorption is minimal up to 90 days, but complete within 6 months. It is applied in soft tissue, pediatric, plastic and gastrointestinal (colon) surgery.

B. NONABSORBABLE SUTURES

The material of these sutures effectively resists enzymatic digestion. They can be monofilament or multifilament, coated or uncoated threads. They are used in tissues that heal more slowly, or if a very secure tightening is required. They are either left in the body, where they become embedded in the scar tissue, or they are removed when healing is complete.

Natural substances

(Today, silk, linen and cotton are no longer used in human surgical practice!)

Silk

A braided thread made of the protein fibers spun by the silkworm. Silk is strong and easy to handle. It can be applied in most tissues. It should be used dry. It and causes a significant tissue reaction. Its tensile strength is preserved for more than 1 year; it is absorbed by proteolysis within 2 years.

Linen

This is a twisted thread, which is weaker than silk; however, it is straightened when wet. Therefore, it must be dipped into saline solution before use. Its tensile strength is 50% up to 6 months, and 30–40% for 2 years. Linen can also be applied in most tissues. It is sized from thick to thin as follows: #25 (0.4 mm), #40 (0.25 mm), #60 (0.167 mm), #80 (0.125 mm), #100 (0.1 mm), and #120 (0.083 mm).

Cotton

This is made from twisted cotton fibers. It should also be dipped into saline solution. Its applications are identical to those of silk and linen.

Stainless (surgical) steel

This causes almost no tissue reaction. It is manufactured in monofilament and twisted forms. It is rarely used because it is difficult to handle, it may break up and it can easily cut tissues. It can be used for tendon and bone repair, nerve and retention sutures, and skin closure. It is numbered according to Brown and Sharpe.

Synthetic materials

Polyesters

These can be monofilament (Miralene or Mirafil), but are mostly braided, either uncoated (Dacron, Mersilene or Dagrofil), or coated with Teflon (Ethiflex or Synthofil) or polybutylate (Ethibond). They give the strongest sutures, apart from surgical steel. They can be used in a wide variety of tissues, primarily in cardiovascular surgery.

Polyamide (Nylon)

This is manufactured in monofilament (Ethilon, Dermalon) or in braided, coated form (Surgilon, Nurolon or Supramid). Braided nylon can be used in all tissues where a multifilament nonabsorbable suture is acceptable (general closure or microsurgery). Its tensile strength for 1 year is 80%, for two 2 years is 70% and for 11 years 66% and it causes only a minimal inflammatory response.

Polypropylene

This is a monofilament suture material (Prolene or Surgilen). It does not adhere to tissues, it causes only a minimal tissue reaction, it has a high tensile strength (100% for 2 years) and it holds knots better than most other synthetic materials. It is used in general, cardiovascular (blood vessel sutures) and plastic surgery. It can also be applied in an infected fields.

directions will be easy to follow. So this is a process of purification. The energies will be used with purer intentions.

For example, if you have an excess of fear you feel threatened and isolate yourself. Any decision you make from that standpoint will not lead to happiness. This formula is very important and carries a tremendous amount of responsibility, for whenever you learn something that can change your life in a positive sense you will either do it or forget about it. You often hear people say, “I want to change my karma.” This formula is something that can change your karma. So this practice, this opportunity has a responsibility. You will have to take the consequences of doing it or not doing it. Because if you do it you will change.

Q. ***How can I protect myself from negative energy?***

A. The belt routes can protect you. When you circulate the energy through the belt routes, the energy centers are strengthened, and can protect you from absorbing outside energy that you don’t want. For instance, in a crowd, if there is energy you don’t like, just run the belt routes to protect yourself. This will also protect your aura. If you are upset and have a lot of emotions, the aura is very unstable. The aura might expand or shrink. This protection will become automatic through diligent practice of the belt routes.

Q. ***When you send the energy out like a shower, are you always collecting positive energy? How do we know what energy we are collecting?***

A. There is always heavenly energy around you, and there is always magnetism so when you do this work you are working with earth and heaven energy. It’s another responsibility when working with the energy. If you are an ordinary person you are absorbing only a certain level of energy. When you start raising your level, you are raising your level of positive energy. This can change the atmosphere around you (an inner pressure of positive energy). Energy has a magnetic quality that attracts. When you have strong positive pure energy you will be repelling negative energy and you won’t be affected by negative energy. For example, if someone is angry you will have enough positive energy to handle it. If you practice this and go to higher levels and

IV. Basic wound-closing methods: sutures and clips

Motto: *"Not too many—not too tight,*
not too wide—and get them out!"

At the end of the operation, wounds are closed with sutures or clips. During suturing, tissues are approximated with stitches, and threads are then knotted. The basic prerequisites of wound healing are that tissues should be precisely approximated without tension, no dead space must be left, and the optimal blood supply of the wound should be ensured. As few sutures should be applied as possible, and only as many as necessary. Sutures can be used to stop bleeding (see later).

1. Types of sutures

Sutures can be classified according to the *number of the layers*: one layer (only 1 layer is sewn), or 2 or multiple layers (retention suture); according to the *number of rows*: 1 or 2 rows (seldom multiple rows); and according to the type of *technique*: interrupted or continuous.

2. Rules of wound closure

- Sutures must not be placed too close to the wound edges, as otherwise the thread can tear them. Stitches should be placed 0.5–1 cm from the wound edges on both sides. (Suturing is usually made toward the person carrying out the procedure.)
- Stitches should be placed at equal distances (approximately 1–1.5 cm).
- Knots should be on one side of the wound and never on the wound line.
- Stitches should be placed opposite each other, so that no wrinkling and gaps occur.
- During suturing, the curvature of the needle should be followed.
- Wound edges must not be inverted (inverted wound edges heal with a thick scar).
- In the case of superficial wounds, stitches should be inserted to the base of the wound, not leaving dead space, in which blood and wound secretion may accumulate (wound infection and other complications).
- Threads must not be stretched too much, to avoid ischemia.
- Deep wounds should be closed in several layers.
- When skin is sutured, the stitches must be wider at the bottom of the wound (including more tissue) than in the superficial layer.

3. Correct position of the needle holder

- The correct position of the needle.







- 1/3–2/3 ratio, with approximately 70° deflection.





4. Interrupted sutures

4.1. Simple interrupted suture *(sutura nodosa)*

This is frequently used to suture skin, fascia and muscles. After each stitch, a knot should be tied. All sutures must be under equal tension.



The advantage is that the remaining sutures still ensure an appropriate closure and the wound will not open if one suture breaks or is removed. The disadvantage is that it is time-consuming since each individual suture must be knotted.

4.2. Vertical mattress suture *(sec. Donati)*

This is named after Mario Donati (1879–1946), an Italian surgeon. The Anglosaxon terminology (erroneously) is *Blair-Donati* suture (Lyman C. Blair described the “upside-down, continuous, subcuticular” suture in 1964).



The *Donati* suture is used most often for skin closure. It is a 2-row suture: a simple interrupted stitch is placed wide and deep into the wound edge, and a second, more superficial interrupted stitch is placed closer to the wound edge and in the opposite direction. Finally, it consists of a deep suture that involves the skin and the subcutaneous layer (this closes the wound) and of a superficial back stitch placed into the wound edge (this approximates the skin edges). The two stitches are in a vertical plane perpendicular to the wound line.

4.3. Vertical mattress suture *sec. Allgöwer*

The *Allgöwer* suture was described in 1963 by Martin Allgöwer (1917–) at the University of Basel. It is a special form of vertical mattress suture: on one side of the wound, the thread does not come out from the skin, but runs intracutaneously. In this case, a thin scar is formed.

4.4. Horizontal mattress suture

This is a double suture: the back stitch is 1 cm from the first one, parallel to it in the same layer.



5. Continuous sutures

5.1. Simple continuous suture (furrier suture, *sutura pellionum*)

This can be applied to suture tissues without tension, the wall of inner organs, the stomach, the intestines and the mucosa.



Advantages: 1. It can be performed quickly, since a knot should be tied only at the beginning and the end of the suture (here, only a part of the thread is pulled through and the strands of the opposite sides are knotted). 2. The tension is distributed equally along the length of the suture. During suturing, the assistant should continuously hold and guide the thread (with hands or forceps) to prevent it from becoming loose.

5.2. Locked continuous suture



5.3. Subcuticular continuous suture



This runs in the subcuticular plane parallel to the skin surface; it enters the skin at the beginning and comes out at the end (no sutures are visible). It is used in skin with minimal wound tension and produces a fine scar. Starting from one end of the incision, insert the needle through the dermis, taking small bites alternately on one side and then the other. At both ends, the thread can be tied or taped to the skin.

5.4. Purse-string suture

The openings of the gastrointestinal tract are closed with this suture; an atraumatic needle and thread are used. It is a suture for a circular opening, running continuously around it. The wound edges are then inverted into the opening with dressing forceps and the threads are pulled and knotted.



6. Methods of wound closure

6.1. Suturing with simple interrupted knotted stitches (skin and subcutis closure)

- For simple interrupted stitches, a needle holder, a curved needle (a 1/2 circle cutting needle) and 30-35 cm of thread are needed.
- The subcutaneous tissue must be stabilized by gently grasping it with tissue forceps 0.5 cm deep on the far side of the wound. The surgeon should insert the needle toward him- or herself, obliquely downward, 1–2 cm deep.
- Suturing should be started with the hand pronated, and the needle should be driven following its curvature by progressively supinating the hand until the point of the needle appears. The needle should exit the tissue perpendicular to the wound. With deep stitches, it can occur that the needle should be released and regrasped. The surgeon must always see the point of the needle when possible.
- When the point of the needle exits the tissue, the needle should be grasped and stabilized with the forceps, then released and regrasped with the needle holder under the forceps and removed from the tissues. The point of the needle must never be grasped.
- The free end of the thread is held by the assistant, and the thread is pulled out from the needle. The needle closed in the jaws of the needle holder is passed to the scrub nurse.
- The distance from one suture to the next should be approximately 1–1.5 cm. The elevation of tissues with knotted sutures by the assistant may provide help toward insertion of the next suture.
- All the stitches are cut just above the knots, only after the last one has been tied.



6.2. Suturing with *Donati* stitches (skin closure)

- For in vitro training and non-human practice #40 linen thread or nylon thread and a skin needle (a 3/8 or 1/4 cutting needle) are used.
- The stitch takes both deep and superficial bites and is useful for closing deeper wounds. The superficial bite allows for a more exact apposition of the skin edges, and the inversion of wound edges can be avoided. The wound edge is grasped and stabilized with tissue forceps on the far side, and the needle is inserted ~ 1 cm from the edge, close beside the forceps. The stitch is continued on the other side. The needle should exit the other skin edge at the same distance (1 cm) from the wound.
- The needle should be removed from the skin and the point is turned into the opposite direction to make a back-handed stitch (the inner curvature of the needle and the point are up). The needle is then grasped with the needle holder again. During these steps, the position of the needle holder remains unchanged.
- The closer wound edge is elevated with the tissue forceps, and a back-handed stitch is inserted 1–2 mm from the edge. The needle should leave the tissues between the cutis and subcutis. The stitch is repeated in the far side wound edge, from inside to outside.
- The thread is removed from the needle. The stitches must be tied just tight enough to appose the edges without causing ischemia, taking into account that edema will occur during the next few days. The threads are cut after complete closure of the wound, but ~ 0.5–1 cm is left above the knots.
- The wound should be disinfected with povidone-iodine or iodine tincture and covered with a bandage.

6.3. Wound closure with metal clips *(agrafe)*

Metal clips made of stainless steel or titanium can also be used for the approximation of tissues. They can be applied to close skin wounds and, for example to make gastrointestinal sutures. In the case of skin, they can be used on fields without wound tension and where wounds tend to heal quickly (e.g. after appendectomy, strumectomy or hernia repairs). Clips can be applied to close the lumen of different tissues and organs (vessels, ducts, etc.). This method is also used in video-endoscopic surgery.

1. Clips fit into the jaws of a special grasping instrument designed for their handling, the *Michel* clip applicator and remover. The clip is grasped with the forceps-like part of the applicator. The assistant approximates and lifts up the opposite wound edges with two tissue forceps. The surgeon inserts the clip with the applicator between the two tissue forceps, perpendicular to the incision, with a definite movement. When compressed, the toothed tips of the clip are closed with the instrument. The distance between the clips is 1–1.5 cm. Clips are removed with the other end of the instrument. It is forbidden to close wounds of the hand or the hairy skin of the head with clips.



2. Skin wounds can also be closed with a modern, clip applicator.



3. Staplers: These approximate tissues with staples in one or two rows. The metal clips are pressed by the apparatus into the anvil of the opposite side, where they become crooked and are closed without crushing the tissues.
   - Linear stapler: This closes tissues with double rows of staples in a straight line; it can also cut the tissues between the two rows (gastrointestinal and lung surgery).



   - Circular staplers: These can be used to approximate tubular structures (esophagus or intestinal surgery).
   - Staplers are suitable for making purse-string sutures (intestinal surgery).
   - Vascular staplers use special 3-row clips for the complete occlusion of vessels.

6.4. Other wound-closing methods

1. Surgical adhesives: These are usually produced from fibrin, collagen or thrombin and induce the last phase of blood coagulation, so that a firm fibrin mesh is produced. Application fields: Anastomosis, securing vascular and nerve sutures, fixation of skin transplants and stopping bleeding (see later).
2. Wound closure with self-adhesive strips (*Steri-Strip*): These can be applied if the wound edges can be easily and well approximated in the case of smaller wounds not requiring suturing. They are also used to fasten subcuticular sutures.



Disadvantages: Less precision is attained than with suturing; body parts with secretions (armpits, palms or soles) are difficult areas; areas with hair are not suitable for taping.

7. Sutures in different tissues

Skin
Usually, nonabsorbable sutures (synthetic materials) are used. Suture types applied: Simple interrupted suture, vertical mattress suture (*Donati, Allgöwer* suture) or subcuticular continuous suture. Metal clips, a clip-applying machine, self-adhesive strips (*Steri-Strips*) (small children and supplementary fastening of subcuticular sutures), or surgical steel (in the case of delayed wound healing) can also be utilized.

Mucosa
Thin absorbable sutures (earlier catgut) are used.

Gastrointestinal tract
The danger of suture insufficiency is great. *Lembert* sutures (involving the seromuscular layer on both sides), *Albert* sutures (passing through all layers), or *Czerny* sutures (a double row: *Albert* suture followed by a *Lembert* suture) can be applied. Different staplers are often used (see above).

Muscles
In most cases, muscles are closed with absorbable (earlier catgut) sutures, together with the fascia.

Fascia
This is closed with simple interrupted stitches, using synthetic suture materials.

Tendons
Surgical steel or other nonabsorbable monofilament sutures are applied.

Blood vessels
These are sewn with nonabsorbable synthetic thread (e.g. Prolene), often by using microsurgical techniques.

Nerves
These are approximated with microsurgical techniques, using nonabsorbable monofilament threads.

Parenchymal organs (liver, spleen and kidney)
These are sewn with absorbable material and mattress sutures.

7.1. Failures of suturing technique

Dead space:



Insufficient depth:



Inversion of wound edges:



Knot in the wound line:



7.2. Removing sutures

The saying "*without inflammation, there is no healing*" is the clue to the readiness of the wound for suture removal (there should be pink, raised healing ridge). The time of removal (usually within 3–14 days) depends on the location of the suture (sutures are removed later from a field which is under tension), the blood supply of the operative field (sutures can be removed earlier from an area that has good circulation) and the general condition of the patient. Sutures on the face can be removed after 3–5 days, those on the skin of the head and the abdominal wall after 7–10 days, those on the trunk and the joints after 10–14 days, those on the hand and arm after 10 days, and those on the leg and foot after 8–14 days.

Removing simple interrupted, continuous sutures and wound clips

- After careful disinfection of the wound site, the suture is grasped and gently lifted up with a thumb forceps. The thread should be divided as close to the skin as possible so that no thread which was outside the skin should be pulled through the wound. In this way, infection of the wound can be avoided.
- In the case of continuous subcuticular sutures, one end of the suture is cut above the skin and the other end is pulled out in the direction of the wound.

- *Michel* clips are removed with the *Michel* clip applicator and remover. The ring of one end of the clip is grasped with a tissue forceps, the edge of the remover is placed between the clip and the wound line, beneath the apex of the clip. The instrument is closed, the clip will open and the teeth of the clip will come out of the skin.

8. Surgical knots

In surgery, the ends of threads used for sutures or ligatures are tied with surgical knots. The basic requirements for tying knots are that they can be ligated quickly, the knots should hold securely and they should be safe. Incorrectly tied knots may cause serious postoperative complications: loose knots can result in thicker scar formation. Too tight knots can decrease or stop the local blood circulation which slows down wound healing and can lead to the loosening of sutures and even suture insufficiency. The knot must be as small as possible so as to prevent a tissue reaction when absorbable sutures are used, or to minimize the foreign body reaction to nonabsorbable sutures. The two ends of the threads should be cut as short as possible, just above the knots (except for skin sutures, where longer threads are left, facilitating the removal of the sutures).

8.1. Types of surgical knots

- There are different types of knots. The *granny knot* used in everyday life consists of two identical simple half-hitches tied above each other: in the second half-hitch, the direction of the ends of the thread is identical with that in the first one. As it has the tendency to slip and can open up spontaneously, it must not be used in surgery.
- The common knot used in surgery is the *square* (or *reef*) knot, a symmetrical knot which consists of at least two half-hitches, one placed on the other: the base half-hitch and then the second half-hitch which is the mirror image of the first one. A half-hitch is one revolution of one end of a thread around the other. The first half-hitch is made by crossing the segments, and the second half-hitch is in the opposite direction to that of the first one, so the knot has two mirror image half-hitches. The number of half-hitches depends on the nature of the surgical materials (synthetic monofil threads require extra knots – 5 or 6 knots).
- Techniques of tying knots in surgery: two-handed knots, one-handed knots (one hand is active, while the other only holds the thread, and the knot is then tightened with both hands) and an instrument tie.

8.2. Two-handed knots

Both hands take an active part in the formation of the knot. These knots are mostly applied on tissues under tension. The most important types of two-handed knots: the two-handed square knot (reef knot or sailor's knot), the surgeon's knot and the Viennese knot.

8.2.1. Reef knot or sailor's knot



1. The two strands of the thread are crossed; the upper (white) strand is held in the right hand. The ends of the thread are held firmly against the palm with the last three fingers; the thumbs and the index fingers are free.



2. With the right index finger, the upper strand is pushed to the left side, over the blue strand.



3. The right thumb is inserted between the strands, upward from below.



4. The left-hand strand is placed on the pulp of the right thumb.



5. The thread is grasped with the right thumb and index finger.



6. The thread is released from the left hand and transferred with the two fingers through the loop.


7. The thread is grasped with the left hand again.


8. The base half-hitch is tightened with the two hands.


9. The two strands are crossed (exchanged between the two hands) in the opposite direction: the upper (white) strand is held in the left hand.


10. With the left index finger, the upper strand is pushed to the right side, over the blue strand.


11. The right thumb is inserted between the strands, upward from below.


12. The right-hand strand is placed on the pulp of the left thumb.


13. The thread is grasped with the left thumb and index finger and released from the right hand.


14. The thread is transferred through the loop with the two fingers and grasped with the right hand again.


15. The second half-hitch is tightened with two hands.

8.2.2. Surgeon's knot

The technique of tying this knot is identical with that for the reef knot (section 8.2.1), but during the tying of the base half-hitch the thread is transferred through the loop twice, and then, similarly as for the reef knot, the base half-hitch is secured with a second half-hitch in the opposite direction. This results in a strong, safe knot that is used mainly in tissues under tension (skin and fascia).


7. The thread is grasped again with the left hand.


8. The base half-hitch is tightened with the two hands, and then the second half-hitch is tied.

8.2.3. Viennese knot

The technique of tying this knot is different, but it results in the same knot as the reef knot. However, it is faster and more elegant; it can be applied well in tissues under minimal tension (e.g. subcutaneous tissues or skin).



1. The two strands of the thread are crossed; the lower (blue) strand is in the left hand. The ends of the thread are held between the tips of the thumbs and the index fingers.



2. The left hand is placed over the thread, the ulnar side of the small finger is laid on the thread and the wrist is supinated so that the small finger rolls along the strand. The left palm faces upward.



3. The right-hand (white) strand is placed on the pulp of the extended left middle finger, and the distal phalanx is then flexed and pulled beneath the left-hand strand.



4. The left-hand strand is situated between the middle and index fingers.



5. The two fingers are closed and the thread is grasped by them. The end is then released by the thumb and index finger.



6. The thread is brought through the loop with the two fingers.



7. With the two strands of the thread held in the palms, the tips of the index fingers are placed on them, and the half-hitch is tightened.



8. The two strands of the thread are crossed (exchanged between the two hands) in the opposite direction (from left to right). The lower (blue) strand is held between the right thumb and index finger.



9. The right hand is placed over the thread, the ulnar side of the small finger is laid on the thread and the wrist is supinated so that the small finger rolls along the strand. The right palm faces upward.



10. The left-hand (white) strand is placed on the pulp of the extended right middle finger, and the distal phalanx is then flexed and pulled beneath the right-hand strand.



11. The two fingers are closed and the thread is grasped by them. The end is then released by the thumb and index finger.



12. The thread is brought through the loop with the two fingers.



13. Finally, the second half-hitch is tightened.

8.2.4. Instrument tie

This is used when knots are to be tied in deep tissues, or in a deep cavity, or the thread is short (with this technique, thread can be saved) or in work with an atraumatic needle and thread. Such knots can be tied with a needle holder (this is used most frequently), with a hemostatic forceps (*Péan*), or with other grasping instruments.



1. The instrument is placed on the long thread held in the left hand.



2. The thread is wrapped around the needle holder once when a reef knot is tied, or twice if a surgeon's knot is tied.



3. The short free end of the thread is grasped in the needle holder and pulled through the loop(s).



4. The base half-hitch is then tightened.



5. The instrument is placed under the long end of the thread.



6. The thread is wrapped around the needle holder once.



7. The short free end of the thread is grasped and pulled through the loop.



8. The second half-hitch is then tightened.

8.3. Knotting under special circumstances

8.3.1. Knotting close to the surface

The constriction of tissues should be avoided when sutures are tied. The degree of tightening should be just sufficient to oppose the tissues. The next half-hitch is tightened snugly onto the first one, and the third part of the triple throw knot is drawn tightly onto the second. As the knot is tightened, the direction of pull on the threads must be along a straight line which passes through the center of the knot.



8.3.2. Tying under tension

In general terms, tying knots under tension should be avoided. However, there are some circumstances when this can not be prevented. If knots have to be tied with threads which draw together two structures under tension, or around bulky elastic ducts that must be occluded, the slipping of the first half-hitch must be avoided while the second is being formed. This can be achieved by the following means:

1. After the first half-hitch has been tightened, a little tension is kept on the threads while the second half-hitch is formed and tightened.



2. After the first half-hitch has been tightened by pulling the threads in the correct line, they are sharply rotated to hold the first half-hitch, while the second hitch is formed.



3. The assistant's finger may be pressed on the tightened first half-hitch; the second hitch is formed and tightened onto it beneath the trapping finger, which is gently lifted.



4. The extra friction produced by a second turn on the first hitch of a surgeon's knot may be sufficient to hold the tension while the second hitch is formed and tightened.

8.3.3. Tying knots in cavities

When a knot is tightened within a cavity, it is not always possible to pull the threads in opposite directions in the horizontal plane, yet they must be tightened by pulling with equal force in opposite directions. In some situations, it is easier to form the half-hitch in a large loop outside the mouth of the cavity and to tighten this, rather than to form a half-hitch in the depths of the cavity.



Tightening a knot in a cavity can be practised on practice boards with different shapes.



Practising of knot tightening in a cavity with a small aperture (left), in the abdomen (middle) or in the pelvis (right).

then decide to stop, your pressure will again change and decrease. Our bodies always try to find a balance, that's our inner intelligence. So the pressure has dropped and the body tries to restore the familiar higher pressure. To do this you start absorbing anything, and the most abundant source is the garbage energy: anger, fear, depression, etc. As you build up your strength you need to maintain that higher level and that is a big responsibility.

So when you do the shower of energy you have to depend on the strength of the energy in your pearl. Fusion II jacks up the energy of the pearl you made in Fusion I by imbuing it with the positive qualities in the organs. So it's important to do Fusion I carefully.

When you absorb positive energy you can even affect the bacteria in the air. If you've been practicing the Microcosmic Orbit and Fusion I for a year you've probably noticed that colds don't last as long, and you don't get sick as often.

Q. ***Is it normal to feel pain or discomfort when doing the fusion practices?***

A. You can see that some systems are into suffering: staring at the sun, sticking oneself with needles or standing on one leg for a long time. This is so that when practitioners get to the level of great power, they can withstand the pain. This is how some people learn and they suffer a great deal.

Maybe you cannot take all the energy; some people bathe in the river every day to reduce the heat and can't sleep for weeks and months. When you practice to a certain level there are changes in the body—but you can take those changes. Sometimes as new energy pushes through channels you may feel a headache. Some people feel a stomach cramp when they blend the energy at the cauldron. But that is unusual. It's like trying to help a butterfly when it's hatching. Maybe you want to help by cutting the chrysalis with a scissors. But the butterfly won't survive if you do that. It has to struggle at the beginning in order to survive.

So you will have to grow over the pain. Other systems induce the suffering first. In Chinese, they call it qing ku—you don't have anything and you still have to suffer—but that is not the Taoist way. We prefer to grow first and then experience the grow-

9. Wound closure in separate layers

Sutures involving multiple layers are demonstrated on a laparotomy site.



9.1. Approximation of tissues in the depths

A lower incision of the abdominal wall is always closed with a continuous suture.



Continuous sutures should always be performed with the aid of an assistant. After the first knot has been finished, the short thread should be cut, but the remaining long one should be kept continuously under tension by the assistant. The tension on the long thread should be restored after each stitch.

9.2. Closure of the subcutis

As the diagram shows, stitches in the subcutis should be placed appreciably deep, as far from the skin stitches as possible.



Although the subcutis seems to be smooth and vulnerable, stitches placed into it contribute significantly to the security of wound closure and help to prevent hernia formation in the abdomen. Stitches in the subcutis should not be placed closer to the skin, because this makes stitching of the skin difficult and leads to the formation of space (tunnel) close to the base of the wound. This may lead to the accumulation of body fluids.

The threads are cut only after of all the stitches have been completed. This clearly exposes the layer.

9.3. Skin stitches



Donati stitches and Intracutaneous stitches (see above)

10. Drainage

Drains are inserted to empty existing fluids and those that might collect later. Drains are used to channel pus, blood, body secretions or air in order to alleviate pain and inflammation. They prevent the build-up of tension and the formation of spaces which would keep tissue surfaces from coming into contact with each other and healing.

Main types of drains

A. Passive (without suction) drain types are strips, tubes or bands made from the fingers of surgical gloves. These drains are usually laid into the wound or on the base of a cavity and enter the surface through a distinct aperture.

B. Active drainage with suction.

10.1. Passive drainage

Historical methods

- Gauze pads were earlier used for the packing of wounds with folded sheets of cotton gauze to absorb the discharge from wounds or to treat infected wounds. Because of the deposition of fibrin their removal was painful and the suture area could be damaged. Soaking with fluid was therefore applied upon removal.

- When the source of drainage cannot be fully exposed or brought close to the surface, a wick can be passed down. This is the *Mikulicz* drain (after Jan Mikulicz-Radecki (1850–1905), a professor of surgery in Cracow, one of the discoverers of gastroscopy). It rapidly becomes wet, swells and often occludes the movement of fluid discharge.
- When the fluid reaches the surface, it should be soaked up by gauze packs sutured to the skin.

Modern methods

- The track can be kept open with corrugated sheet drains made of rubber or plastic. Tube drains are supplied with multiple holes, made of silicone, rubber or latex. These also should be secured in place by sutures.
- The *Penrose* drain (after Charles B. Penrose (1862–1925), an American gynecologist) is a tube drain.
- The *Delbet* drain (after Pierre Delbet (1861–1957), a French surgeon) is a corrugated sheet drain.



Passive drainage with gauze pads (tampons) (A), a gauze wick (B), a rubber wick (C) or a tube drain (D).

10.2. Active drainage (with negative pressure): open, open-closed and closed tube systems

- In a partially closed system, a fenestrated tube leaves the body through a distinct aperture and is connected to a sterile reservoir (*Robinson* drainage).
- Low-pressure suction can be used with a compressible harmonica bottle (Polyvac).
- A closed system with strong active suction involves the use of a *Redon* drain (an ~ 50 cm-long plastic tubing visible under X-rays and with perforations).

Suction drainage (e.g. *Redon* drain)

A tube drain (made of silicone or plastic) supplied with multiple holes is used. It reaches the surface at an aperture separate from the wound. The tube is secured to the skin and connected to a sterile bottle in which subatmospheric pressure (“vacuum”) has previously been created. This bottle will suck out the discharge as long as the pressure is lower than that in the cavity.

Rinsing drainage (*Willinegger*)

Lactated *Ringer* solution with or without antibiotics is introduced into the wound via a closed system and the rinsing solution is continuously removed with a suction drain. This is particularly advantageous in cases of infected wounds (and improves wound healing).



Rinsing drainage with closed (a), partially closed (b) or (c) open systems.

10.3. Important localizations of drainage

Localization	Drains	Alternatives
Subcutis	Gauze or rubber wicks, tube drains	Open wound management
Subfascial, intramuscular	Less suitable	Leaving the fascia open
Extraperitoneal	A tube drain through a separate stab wound	Open wound management
Intraperitoneal	A tube drain through a separate stab wound. It often becomes obliterated.	
Pleural cavity	Mostly for the removal of air, introduced at the upper part of the 7th and 8th rib into the intercostal space. The drain is connected to a bottle containing vacuum and fluid.	
Abscess, cysts	Tampon, gauze or rubber wicks, tube drains	Open wound management
External fistulas	Drainage is usually not applied, but the spontaneously flowing discharge can be attached to collecting stoma bags or can be suctioned through a cannula.	Surgical management if possible

10.4. Drain removal

- A drain is a foreign body (!)
- Indications for removal: reduced fluid production and altered cell constitution (cell type or number).
- In the event of postoperative bleeding: within 1–2 days.
- In the event of bacterial infection: within 2–5 days.
- Closure of a cavity or dead space: within 3–14 days.

V. The operation

> *"With us ther was a doctour of phisik;*
> *In al this world ne was the noon hym lik,*
> *To speke of phisik and of surgerye."*
> The Canterbury Tales by Geoffrey Chaucer (? – 1400)

The word surgery originates from the Greek *cheirourgia,* meaning "*hand work*". Surgery is a branch of medicine concerned with the diagnosis and treatment of injuries, and the excision and repair of pathological conditions, by means of operative procedures. An operation is therefore a therapeutic or diagnostic procedure with instruments with the aims of recognizing or repairing damage or arresting disease in a living body. Most commonly, it is an act or series of acts performed to remedy a deformity or injury, cure or prevent diseases, or relieve pain or other symptoms. The parts of the operation are 1. opening (entry into the body by incision, puncture, etc.), 2. intervention, and 3. closure. Depending on the aim, curative (radical) and symptomatic (palliative) operations are distinguished.

1. Basic surgical interventions

- Closing an incision, wound or cavity (*suture*)
- Opening the skin or cavity *(-tomy, -puncture*)
- Moving organs or tissues (- *transplantation*)
- Removing tissue, an obstruction or a blockade (– *resection, amputation, - ectomy*)
- Connection within an organ, or between organs *(-stomy, anastomosis*)
- Separation or elimination of pathological connections (*extirpation*)
- Restoration or repair of normal anatomy (*-plasty*).

2. Preparations for an operation

- **Indications and contraindications**: These are involved in the decision-making as to whether or not to carry out a given operation, i.e. the decision before the intervention. There are different levels. The indications for surgery should be clearly known, as these will determine the urgency of the procedure.
- **Vital indications** (*indicatio vitalis*): These are involved in the case of life-saving procedures. The patient can be treated only with an operation (100% mortality without operation). The timing has narrow limits, and the possibility of evaluation and deliberation is very limited.
- **Absolute indications** (*indicatio absoluta*): These are involved in urgent procedures. The disease can be treated primarily with an operation. The time can be chosen (the operation can usually be delayed for 12–24 h to allow further evaluation). The surgeon makes a decision as to the type of operation which may be considered the most effective, and in agreement with the anesthesiologist determines the optimal time of the operation.
- **Relative indications** (*indicatio relativa*): These are factors in elective procedures, i.e. programmed operations, the aim of which is to cure the patient or to improve a condition (the disease can be treated with surgery or otherwise). The condition leaves time for a full evaluation and optimization before the operation.

3. Informed consent

1. After having been fully informed concerning the state of health that may be expected following the operation, together with the possible complications and consequences of such a regularly performed operation, patients acknowledge their approval of the intervention by their signature on a printed form.
2. If the patients are under the ages of legal consent, their legal representatives must be informed and their permission must be obtained in writing.
3. The physician makes an effort to clearly instruct a patient capable of learning. The physician who makes this effort and obtains consent has met both the legal and ethical obligations imposed upon him or her by society. The surgeon should be prepared for the possibility of a complication. In surgical cases, the rates of complication (as percentages of all operations) are as follows:

Infections:	14.3%
Wound infections:	5.1%
Pneumonia:	3.6%
Urinary infections:	3.5%
Sepsis:	2.1%
Intubation:	2.4%
Respiration > 1 day:	3.0%
Acute myocardial infarction:	0.7%

To obtain informed consent that meets ethical obligations and is acceptable to a court of law, the following information must be provided:

- The nature of the disease and the proposed treatment or surgery.
- The chances of success, based on medical knowledge.
- The known risks of the proposed treatment or procedure.
- The known adverse effects of the proposed treatment or procedure.
- Reasonable alternatives and their chances of success, risks and adverse effects.
- The consequences of deciding not to proceed with the recommended course of treatment.

4. Operative risk

- The most important general factors involved in the determination of the operative risk are as follows:
  - The operative risk comprises the summation of the surgical and anesthesiological risks, which have their own aspects.
  - The preoperative examination must answer the questions of both surgeon and anesthesiologist, allowing them to give their agreed opinion in writing.
  - In the event of a stable condition, 1-month-old findings could be acceptable. In urgent cases, an effort is made to minimize examinations.
- From the aspect of risk, operations can be divided into three main groups:

1. Low-risk surgery: Minor operations belong in this group (e.g. inguinal hernia repair or arthroscopy), where the expected blood loss is less than 200 mℓ.
2. Medium-risk surgery: Surgical interventions of medium severity can be classified here (the expected blood loss is less than 1000 mℓ), e.g. tonsillectomy, cholecystectomy, transurethral prostatectomy.
3. High-risk surgery: Extended abdominal, thoracic and intracranial operations fall into this category. The blood loss exceeds 1000 mℓ. The patient needs postoperative intensive care and treatment. The rates of postoperative morbidity and mortality are high (e.g. liver resection or pulmonary lobectomy).

- Additional classification is possible on the basis of the scheduled time of the intervention:
  - A. Life-saving operations: The mortality would be 100% without intervention (e.g. bleeding).
  - B. Urgent operations: The patient would suffer permanent organ lesions without surgery. The intervention can be delayed for a short time to improve the patient's condition. The postoperative morbidity and mortality are high (e.g. bone fractures).
  - C. Elective operations: The intervention can be delayed in the interest of the improvement of the patient's state (e.g. hernia repair).

The classification of patients on the ASA (*American Society of Anesthesiologists*) grading system (the most commonly used grading system) accurately predicts the operative morbidity and mortality. Thus ~ 50% of patients undergoing elective operations belong in ASA grade I, for which the operative mortality is < 1:10.000.

Grade	State of health of the patient	Mortality
I	Healthy	0.1%
II	Mild systemic disease	0.5%
III	Severe systemic disease	4%
IV	Decompensated life-threatening diseases	24%
V	Moribund state*	51%

* Not expected to survive 24 hours with or without surgery

4.1. Acute risk factors in surgery

- Hypovolemia or dehydration (most common).
- Inflammation (bronchial tract, urinary tract, gastrointestinal tract, etc. diffuse or localized conditions).
- Thromboembolism.
- An acute organ dysfunction.
- An acute endocrine imbalance (pancreas – diabetes, thyroid – hyperthyreoidism, adrenocortical insufficiency – Addison disease).

4.2. Chronic risk factors in surgery

- Hypovolemia (anemia).
- Age (over 65 years).
- Malnutrition or obesity.
- An immunological dysfunction (allergy or immunodeficiency).
- Cardiovascular, pulmonary or cerebrovascular disease
- A chronic renal insufficiency.
- A chronic endocrine insufficiency.
- Bleeding disorders.
- Malignancies.
- Chronic alcoholism.
- Drug abuse.

5. Preoperative management

The preoperative management of a patient with a surgical problem involves a *diagnostic work-up* to determine the cause and the extent of the patient's condition: a *preoperative evaluation* (a thorough, overall assessment of the patient's health to identify operative risks, the patient's chronic diseases, medical therapies, etc. that may influence the recovery period) and *preoperative preparation*.

Recommended investigations	Patient groups
Minimal (routine) laboratory	ASA I, ASA II
Routine hematological testing, total blood count	Males over 60 years, all adult females, cardiovascular and hematological diseases.
Chest X-ray	Cardiovascular and thoracic diseases, malignancies, upper abdominal and thoracic surgery.
Complete urine test	Age over 60 years, cardiovascular, renal and urological diseases, diabetes, steroid therapy, ACE inhibitors.
Quantitative hematological tests	Males over 60 years and all adult females.
ECG	Males over 40 years, females over 50 years, cardiovascular diseases, diabetes

5.1. Evaluation of preoperative investigations

Preoperative investigations are important and obligatory, but their value is not absolute.

- Preoperative investigations rarely (< 5%) reveal unsuspected disease conditions.
- They are inefficient as a means of screening for asymptomatic disease.
- Only 0.1% of these investigations ever change the patients' management.
- 70% of preoperative investigations could be omitted without any adverse effect.
  (Reference: *Barnard NA et al. Preoperative patient assessment: a review of the literature and recommendations. Ann Royal Coll Surg Eng, 1994*)

6. The preoperative preparation

Definition: A series of procedures that make the patient suitable for the planned intervention and ensure the optimal conditions for the operation. These procedures are implemented on the basis of the nature of the expected operation and the findings of the diagnostic work-up and the preoperative evaluation. This will allow specific measures to be taken so that the patient may be in the best possible condition for both anesthesia and surgery. The functions of the organs and organ systems should be controlled and restored if necessary:

- Cardiovascular system
- Respiratory system
- Metabolic status
- Renal function
- Liver function
- Endocrine balance
- Ion homeostasis
- Immunological status
- Energetics

7. Postoperative complication

A postoperative complication may be *defined* as any negative outcome appearing during or after the operation, as perceived either by the surgeon or by the patient, that can influence the healing of the patient. Principles of prevention:

- In the preoperative phase a proper investigation-preparation is needed.
- During the operation, careful anesthesiology procedures and fine surgical techniques should be used.
- Postoperatively, careful control, attention, checks on temperature, BP, HR, respiration, urine output, bowel movements, etc., early mobilization, and regular checks on drains, catheters and wounds are needed.

Classification of complications

Complications can be associated with:

- medical specialties, e.g. anesthesiology or surgery;
- the time of occurrence (before, during or after the operation);
- the site of operation (e.g. the thorax or abdomen);
- the primary disease (external conditions);
- the type of the operation (vital – elective).

7.1. Complications of anesthesia

The mortality rate for surgical patients is 1:200,000 – 250,000 narcose.

Nerve injuries (due to the positioning of the patient)

- Brachial plexus
- Ulnar nerve
- Radial nerve
- Common peroneal nerve

Tissue injuries

- Corneal abrasion (during the control of the cornea reflex)
- Fracture of teeth or crowns, etc. (during intubation)
- Diathermy burns
- Dislocations or fractures
- Pharyngeal or esophageal injuries

Narcosis

- Drug reactions
- Hypoxia
- Awareness
- Temperature changes (hypo- or hyperthermia)
- Aspiration

7.2. Complications depending on the time of occurrence

7.2.1. Intraoperative complications

- Bleeding (see later)
- Temperature changes (hypo- or hyperthermia)
- Organ lesions
- Circulatory, respiratory or renal disturbances, etc.

7.2.2. Postoperative complications

- Postoperative fever
- Wound healing complications
- Postoperative nausea and vomiting
- Respiratory disorders, cardiovascular complications, urinary excretion disorders, ion and water homeo-

stasis disorders, hemostasis disorders, gastrointestinal function disorders, neurological disorders, and metabolic disorders (subjects of anesthesiology and internal medicine).

7.2.2.1. Postoperative fever

- Postoperative subfebrility is common within 48–72 h. If prolonged, it can indicate an inflammatory process (phlebitis caused by an intravenous cannula, an infection caused by a urinary catheter etc.), but it can also be associated with the primary disease.
- Fever within 24 h is most frequently caused by atelectasis, and rarely by the Streptococcus and Clostridium infection of wounds.
- Fever appearing between 24 and 48 h is caused by long-lasting atelectasis, bacterial pneumonia, aspiration pneumonia or septic thrombophlebitis.
- Fever developing after 72 h is caused by a urinary tract infection (days 3–5), wound inflammation (days 4–7), the insufficiency of intestinal anastomosis, or an abscess in the abdominal cavity (approximately after the first week).

7.2.2.2. Complications of wound healing

Hematoma
Cause: Inefficient control of bleeding, a short drainage time or anticoagulation therapy. The risk of infection is high. *Signs:* Tenderness, swelling, fluctuation, pain and redness. *Treatment:* In the early phase, sterile puncture; later, surgical exploration is required.

Seroma
Cause: The collection of serous fluid under the suture line; the wound cavity is filled with serous fluid and lymph. *Signs:* Fluctuation, swelling, pain and subfebrility. *Treatment:* Sterile puncture, compression, if repeated, and a suction drain (drainage to alleviate pain and tension of the wound by using a large-bore needle and syringe); in cases of infection: antibiotics.

Wound infections
See sections I.4 and X.3.

Wound disruption
Etiology: Surgical error is the most common cause. Excessive tension on the wound and tight sutures strangulate the wound edges, causing necrosis and decreased strength (motto: "O*nly approximation; if strangulation, then evisceration*"). This is a complication of the tissues, not of the suture material (in the majority of cases, intact sutures are found). The use of electrocautery coagulation decreases the tensile strength of wounds by increasing inflammation in response to necrotic tissue.

Incisional (scar) hernias are typical consequences of a *chronic* wound disruption. An *acute* wound disruption involves the deeper layers first and finally the skin.

The major types are:
- Partial, superficial (dehiscence)
- Complete separation (disruption)
- An intestinal protrusion together with peritoneum disruption across the wound with eventeration and evisceration (sterile separation of the abdominal wall: "*Platzbauch*").

  Risk factors of disruption are:

Metabolic causes
- Malnutrition
- Poorly controlled diabetes
- Corticosteroids
- An older age (> 65)
- Malignancies

Mechanical causes
- Obesity
- Increased intraabdominal pressure, and abdominal distension (including ascites)
- Wound infection
- Stretching and coughing

Symptoms:
This situation is generally manifested within 5–14 days following surgery (on average 8 days later); the warning sign is a pink oozing (secretion) from a seemingly intact wound.

Therapy:
- Immediate intervention is usually needed, always in the operating room under narcosis, and never in the emergency room or ward.
- The wound is covered by a povidone-iodine sheet or a wide abdominal kerchief is applied. If the intervention must be prolonged (i.e. because of a recent meal), broad-spectrum antibiotics and laboratory investigations are needed.
- During the operation, necrotic tissues, clotted blood and old sutures are eliminated. A sample is taken from the abdominal excretion for bacteriological examination, and then a plentiful wash with warm saline solution is applied. If the fascia is intact, the wound should be closed by *Smead-Jones* technique, which is similar to *Donati* suturing. In the event of a damaged fascia a retention suture is used (with #2.0 nylon or polypropylene thread).
- To relieve tension, a U-type *en masse* suture is used. This is removed after 21 days on the average.

7.2.2.3. Postoperative nausea and vomiting

- These are among the most common side-effects of narcosis associated with surgical procedures (the incidence is 5–30%); they delay recovery and discharge and increase the postoperative morbidity and the costs of medical care.
- Complications related to postoperative nausea and vomiting include possible wound disruption, esophageal tears, gastric herniation, muscular fatigue, dehydration and an electrolyte imbalance.
- The etiology involves vagotonia and dehydration (an extracellular fluid loss). Preoperative fasting for 8 h is equivalent to a loss of 1 ℓ volume/70 kg bw.
- The risk is increased in cases involving preoperative preparation of the gastrointestinal tract, in geriatrics and infants; other factors are obesity, ascites, burns, trauma, ileus, peritonitis, late operative programs, perspiration, narcotic gas without evaporation, blood loss, urine loss, or the loss of other body fluids (ascites and gastrointestinal content).

7.3. Complications associated with the operative field

Abdominal cavity

- Bleeding
- Hemoperitoneum
- Peritonitis
- Biliary leakage
- Foreign body
- Acute complications of drains
- Anastomosis insufficiency
- Ileus (small and large intestine)
- Gastric atonia
- Abscess
- External fistulas (enterocutaneous fistulas: gastric, duodenal, pancreatic, and small and large intestines)
- Internal fistulas (entero-enteral, entero-vesical, etc.)
- Postgastrectomy syndromes: dumping, afferent loop and reflux gastritis
- Gastrointestinal bleeding
- Postoperative pancreatitis or cholecystitis

(For other complications such as those of the thoracic cavity, skull, joints, etc.: see later or during the courses of the appropriate specialties.)

8. Minor surgery

By the end of the 19th century, general anesthesia had made surgery much safer (according to John Collins Warren: "*Gentlemen, this is no humbug*"). The scope of surgery expanded; and methods of narcosis have subsequently progressed and become increasingly complex. Anesthesiology divorced practical surgery and became a separate subject during the second part of the 20th century. However, the overcoming of local pain (local anesthesia) is still the duty of the surgeon.

8.1. A short historical survey of local anesthesia

1860	Isolation of cocaine from *Erythroxylum coca.*
1884	Karl Koller (1857–1944): local cocaine (topical) anesthesia.
1885	William S. Halsted (1852–1922): peripheral nerve blockade.
1899	August Bier (1861–1949) tried spinal anesthesia on himself (because "*Ein Professor ist ein Herr, der anderer Ansicht ist*" – A professor is a gentleman with a different point of view).
1908	August Bier: intravenous regional anesthesia.

8.2. Local anesthetic drugs

Definition: Local anesthesia is the regional loss of sensation caused by a substance which reversibly inhibits nerve conduction when applied directly to tissues in nontoxic concentrations.



Mechanism of action of local anesthetics: By limiting Na^+ influx, local anesthetics inhibit the depolarization of the membrane, thereby interfering with propagation of the action potential. The action potential is not propagated because the threshold level is never attained.

8.2.1. Main classes, the ”I” rule and the dangers of local anesthesia

Amide	Ester
Bupivacaine	Cocaine
Lidocaine	Chlorprocaine
Ropivacaine	Procaine
Etidocaine	Tetracaine

Amino esters are metabolized in the plasma via pseudocholinesterases, they are unstable in solution, and are likely to cause true allergic reactions. Amino amides are metabolized in the liver; they are very stable in solution; true allergic reactions are rare (patient reports of “allergy” are frequently due to previous intravascular injections, e.g. tonogen). Most reactions of esters such as hydrolysis (normal metabolism), lead to the formation of PABA–like compounds. Tissue toxicity is rare. It can occur if these compounds are administered in high enough concentrations (greater than those used clinically), which is usually related to the preservatives added to the solution. Systemic toxicity is rare. It is related to the blood level of drug secondary to absorption from the site of injection; the effects can range from tinnitus to seizures and central nervous system/cardiovascular collapse.

8.2.2. Dosage of local anesthetics and duration of anesthesia

Drug	Onset	Maximum dose (with epinephrine)	Duration (with epinephrine)
Lidocaine	Rapid	4.5 mg/kg	120 min
		(7 mg/kg)	(240 min)
Bupivacaine	Slow	2.5 mg/kg	4 h
		(3 mg/kg)	(8 h)
Procaine	Slow	8 mg/kg	45 min
		(10 mg/kg)	(90 min)
Chloro-procaine	Rapid	10 mg/kg	30 min
		(15 mg/kg)	(90 min)

8.3. Main types

Local – topical anesthesia
Definition: Application of a local anesthetic drug to the mucosa or cornea. *Indications:* Awake oral or nasal intubations, in cases of superficial surgical procedures. *Pros:* Technically easy; minimal equipment. *Cons:* Potential for large doses leading to toxicity.

Local – infiltration anesthesia
Definition: This is the injection of a local anesthetic agent into the tissues for the reversible inhibition of nerve conduction within the area of operation. *Indication:* Awake minor surgery (e.g. inguinal herniotomies). *Pros:* Complete loss of pain sensation. *Cons:* The noises, etc. of the operations are present.

Regional anesthesia
Definition: This renders a specific area of the body, e.g. a foot, arm or lower extremity insensate to the stimulus of surgery or other instrumentation. Peripheral nerve blocks are achieved by injecting anesthetic solution around a nerve root to produce anesthesia in the distribution of that nerve (e.g. a foot, hand or other extremity).

A. Peripheral nerve block
This involves the injection of a local anesthetic near the course of a named nerve. *Indications:* Surgical procedures in the distribution of the blocked nerve. *Pros:* A relatively small dose of local anesthetic to cover a large area; the onset is rapid. *Cons:* Technically more complex; neuropathy can evolve.

B. Spinal (intradural)
This is a central neuro-axial blockade with the injection of a local anesthetic solution into the cerebrospinal fluid. *Indications:* Deep anesthesia of the lower abdomen and extremities. *Pros*: Technically easy; rapid onset. *Cons:* “High spinal” – hypotension due to sympathetic blockade; headache (dura puncture).

C. Peridural (extradural)
This comprises central neuro-axial blockade with the injection of a local anesthetic solution into the epidural space at any level along the spinal column. *Indications:* Thorax, abdomen or lower extremity anesthesia/analgesia. *Pros:* Controlled onset of blockade; long duration when a catheter is placed; postoperative analgesia. *Cons*: Technically complex; toxicity.

VI. The perioperative period

> *“The likelihood of successfully initiating an intravenous line is inversely proportional to the necessity of having the line to resuscitate the patient”*
> (The Law of Intravenous Access Necessity)

The exploration of the physiological–pathophysiological processes in the perioperative period began at the end of the 19th century and such investigations are continuing today. The observations made have led to the much safer pre- and postoperative procedures of modern surgery, which are used before and after the operation to ensure the safe recovery of the patients. The surgical preoperative management now relates to all organs and systems.

1. General preoperative preparation

1.1. Rules, interventions

- Psychological support (to release fear and anxiety) through the provision of information.
- Removal of cosmetics, contact lenses, dentures, etc.
- Menstruation is not a contraindication; the operation need not be postponed.
- Toilette (bathing and shaving).
- Fasting (an “empty stomach” to prevent vomiting and aspiration).

The goals of fasting are to prevent aspiration by decreasing the gastric content, but avoiding thirst and dehydration. Aspiration is a serious, frequently lethal complication. In elective cases, the incidence is 1:10,000; and the death rate is 1:200,000 (*Warner MA et al. Anesthesiology, 1993*). The process originates from Lister, who stated that: “*there should be no solid matter in the stomach, but patients should drink clear liquid about 2 hours before surgery.* (*Lister J. On Anaesthetics. In: The Collected Papers of Joseph, Baron Lister, Volume 1, 1909*). A study in the 1970s demonstrated that a gastric content of 0.4 mℓ/kg (i.e. ~ 25 mℓ in adults) and a pH < 2.5 are associated with high risk of aspiration (*Roberts RB, Shirley MA. Anesthesia and Analgesia, 1974*). The present recommendation of “nothing by mouth after midnight” should apply only to solids for patients scheduled for surgery in the morning. Clear liquids should be allowed until 3 h before the scheduled time of surgery. For patients with gastroesophageal reflux, a histamine H_2-receptor blocker or proton pump inhibitor may be advisable to minimize gastric acid secretion.

ASA fasting guidelines

Ingested material	Minimum fast
Clear liquids	2 h
Breast milk	4 h
Non-human milk	6 h
A light meal	6 h

1.2. Medication

- Premedication for sedation, analgesia and inhibition of undesired reflexes.
- Antibiotic prophylaxis (if necessary, e.g. before a septic operation).

1.3. Instruments

- Injections, securing intravenous routes for fluid therapy, drug administration or transfusion (if necessary; see later).
- Emptying the intestines (enemas and laxatives).
- Nasogastric catheter (if necessary; see later).
- Permanent urinary catheters (if necessary; see later).
- Thrombosis prophylaxis.

2. Special preoperative preparation

2.1. Depending on the type of the operation

- Before strumectomy in cases of hyperthyroidism: β-blocker, sedatives, *Plummer* solution (iodine-containing solution), securing airways.
- Operation for mechanical icterus: Vitamins K and C, fresh frozen plasma and placing stents to secure bile drainage.
- Removal of stomach tumor: Gastric lavage, acid replacement, etc.
- Colon surgery: Laxatives, enemas, potassium replacement (hypokaliemia).

2.2. Preoperative preparation depending on the (organ) system

- Acid-base system.
- Respiratory system: Lung diseases predispose to respiratory complications. General preoperative investigations should be supplemented with chest X-ray examination, spirometry and arterial blood gas analysis.

ing pains. You may feel imbalanced from time to time—constipation is a real problem. If you have a good bowel movement at least once a day, you will not suffer so much.

Now that you are more sensitive to energy, you will recognize negative energy right away and you have the tools to neutralize and purify the energy.

Some people, after they study, find that they are reacting differently to their love partners. For some of them, this difference leads to a break-up. When they look back on it, they often realize that the break-up was inevitable and that they were dissatisfied before. For others, especially couples who study together, their relationship becomes more solid and more respectful. In any case, it means that you begin to understand yourself better.

Sometimes you begin to see problems more clearly and see the energy that causes the problems. When you can enhance the energy inside, the problem goes away. There are those who get angry but don't realize they are angry and aren't aware of the effect of the anger on the liver. But those who practice Fusion I can become aware of the liver and very quickly the anger will be gone.

The Taoist system can change the course of your life, change your astrology, change your fortune and your fate. We know that because of the experiences of Taoists over many generations.

The energy inside your organs and brain makes your life what it is. So when you know how to control your energy, your organs and senses, that is the beginning of controlling your future. Those who are controlled by substances like tobacco, alcohol and other drugs are not in control of their lives.

In Taoism you don't run away from problems as long as you are in this world. Actually there is practically nowhere on the planet where you can go without being bothered.

When we started to teach Westerners, we found new ways to teach people how to balance their energy through diet as well as through the Taoist exercises. Those who eat only raw foods will be too Yin and those who eat mostly meat and dairy will be too Yang. But the only way to restore your True Knowledge is when you turn to your internal organs and senses for information. Then you will know how to conduct your life. But until you do that it's hard to know what's good or bad for you.

- Airway infections increase the risk of postoperative chest complications; in this case, the elective operation should be postponed for 2–4 weeks. In smokers the risk of postoperative chest complications is doubled. The increased risk persists for 3–4 months after they give up smoking; smoking increases the blood carboxyhemoglobin level, the concentration remaining elevated for 12 h after the last cigarette.
- Endocrine system (e.g. diabetes mellitus): The pre- and perioperative management depends on the severity of the disease. 1. In diet-controlled diabetes there are no specific precautions; a check on the blood sugar and consideration of glucose-potassium-insulin (GKI) infusion if >12 mmol/ℓ (15 U of insulin + 10 mmol of KCl + 500 mℓ of 10% dextrose/100 mℓ/h) is enough. 2. In diabetes treated with oral antidiabetics: long-acting sulfonylureas are stopped 48 h prior to surgery; short-acting agents should be omitted in the morning of the operation; earlier treatment should be restarted when the patient is eating normally; a GKI infusion is given in major surgery. 3. Insulin-dependent diabetes: conversion of long-acting insulins to 8-hourly Actrapid; early placement on the operating list; GKI infusion until the patient is eating normally.
- Gastrointestinal system (see later).
- Circulatory system (see later).

3. The perioperative fluid balance

3.1. General rules

Careful planning and maintenance of the perioperative fluid balance is *mandatory*; a regular review of the fluid therapy is essential before and after surgery. Patients are more often underfilled than overloaded. Dehydration (which can be difficult to assess in the elderly) can precipitate renal failure, while excess fluids can cause pulmonary edema. Measurement of the central venous pressure (see later) should always be considered with large fluid shifts.

Perioperative fluid therapy requires a knowledge of the body water compartments. The total body water (TBW) varies with age, gender and body habitus. In males, the TBW is ~ 55% of the bodyweight (bw); it is 45% in females and 80% in infants. The TBW is less in the obese because fat contains less water. The approximate proportions of the body water compartments: the intracellular water is 2/3 of the TBW, extracellular water is 1/3 of the TBW, the extravascular water is 3/4 of the extracellular water, while intravascular water is 1/4 of the extracellular water.

The preoperative evaluation of the fluid status includes monitoring of:

- the oral intake and output,
- the BP in the supine *and* standing positions,
- the HR,
- the skin turgor,
- the urinary output,
- the serum electrolytes/osmolarity, and
- the mental status.

Checking for orthostatic hypotension may be very useful. In this case, the systolic BP decreases by more than 20 mmHg from the supine to the standing position, indicating a fluid deficit of 6–8% bw.

Note: The HR should increase as a compensatory measure. If there is no increase in HR, this may indicate an autonomic dysfunction or antihypertensive drug therapy.

3.2. Perioperative fluid requirements

These are determined by several components; to assess the needs, several points should be considered.

1. There is a basic or continuous fluid requirement. This loss occurs continually: in adults, it is ~ 1.5 mℓ/kg/h, in infants the "4-2-1 rule" is valid: 4 mℓ/kg/h for the first 10 kg of bw; 2 mℓ/kg/h for the second 10 kg bw; and 1 mℓ/kg/h for any subsequent kg bw. In addition, an extra fluid loss is calculated for fever, tracheotomy or denuded surfaces.
2. Colon preparation may result in a fluid loss of up to 1000 mℓ.
3. Other measurable fluid losses (e.g. on nasogastric suctioning, vomiting, diarrhea and colostomy) should be reckoned with.
4. Third space losses: These cover the isotonic transfer of extracellular fluids from *functional* body compartments to *non-functional* compartments. This depends on the location and duration of the surgical procedure, the amount of tissue trauma, the temperature and the room ventilation. Replacement of third space losses is as follows:
    - Superficial surgical trauma: 1–2 mℓ/kg/h
    - Minimal surgical trauma: 3–4 mℓ/kg/h (head and neck, hernia and knee surgery)
    - Moderate surgical trauma: 5–6 mℓ/kg/h (hysterectomy and chest surgery)
    - Severe surgical trauma: 8–10 mℓ/kg/h or more (aortic repair and nephrectomy)
5. In the event of blood loss, 1 mℓ of blood is replaced by 3–4 mℓ of crystalloid solution (crystalloid solutions leave the intravascular space; see later). When blood products or colloids are used, blood loss is replaced volume per volume (1:1).

4. Intravenous fluids

The choices are conventional crystalloids, colloids, hypertonic solutions, blood/blood products and blood substitutes.

4.1. Crystalloids

These are combinations of water and electrolytes. Isotonic crystalloids are balanced salt solutions: the electrolyte composition and osmolarity are similar to those of plasma:

- Saline (0.9%, normal salt) solution:
  Na^+ 154 meq/ℓ, Cl^- 154 meq/ℓ
- Lactated *Ringer's* (*Hartman* solution):
  Na^+ 130 meq/ℓ, Cl^- 109 meq/ℓ, K^+ 4 meq/ℓ, lactate$^-$ 28 meq/ℓ, Ca^{++} 3 meq/ℓ
- Normosol-R:
  Na^+ 140 meq/ℓ, Cl^- 90 meq/ℓ, K^+ 5 meq/ℓ, Mg^{++} 3 meq/ℓ
- Plasmalyte:
  Na^+ 140 meq/ℓ, Cl^- 98 meq/ℓ, K^+ 5 meq/ℓ, Mg^{++} 3 meq/ℓ
- Hypotonic salt solution: the electrolyte composition is lower than in the plasma; example: dextrose 5%.

Isotonic crystalloids remain in the extracellular space (the interstitial place is 3 times larger than the intravasal space), and absorb less water from the intracellular space because of their mildly increased tonicity. Following the infusion of 1 ℓ of crystalloid, there is an ~ 275 mℓ increase in plasma volume. The Na^+ content of normal saline (0.9%) is 154 meq/ℓ and that of lactated *Ringer*'s solution is 140 mEq/ℓ; thus, normal saline is advantageous for *hyponatremic* patients (but its pH is 5.5). Saline can cause hyperchloremic acidosis when infused in larger volumes. Lactated Ringer's solution has pH 6.5. The lactate component is converted to bicarbonate if the liver function is normal, but it causes metabolic alkalosis when given in larger amounts. With an abnormal liver function, lactate accumulates and metabolic acidosis evolves.

The electrolyte composition of hypotonic salt solution (e.g. 5% dextrose) is lower than that of the plasma. A 5% dextrose solution is equally distributed in the TBW, and thus an increase of 85 mℓ in plasma volume occurs after the infusion of 1 ℓ of dextrose. Its indication is *hypernatremia* or the treatment of an increased plasma osmolarity, rather than volume replacement.

4.2. Colloids

These solutions contain macromolecules which remain in the intravasal space in much higher volume than do crystalloids. Thus, their volume-expanding effect is more significant (there is no capillary membrane transport because of the size of the molecules, and such solutions will remain in the space into which they are infused). There are variations depending on the properties and effects within the same colloid group. Examples of natural colloids (protein-containing) are 5% albumin and 25% albumin, while artificial colloids (non-protein containing) include gelatin, hydroxyethyl starch and dextran.

- ***Albumin***
  This is a natural (protein-containing) colloid, commercially available in 5% and 20% forms. The volume-active effect lasts for ~ 4–6 h; it increases the plasma colloid osmotic pressure and the intravasal volume by retaining water. If the capillary permeability is enhanced, a significant proportion effuses into the interstitial space, thereby increasing edema formation. Recent meta-analyses have led to conflicting conclusions, but albumin administration could be beneficial in hypo-albuminemic patients. Albumin administration combined with diuretic drugs results in an improved fluid balance, oxygenization and more stable hemodynamics in hypoproteinemic patients. Severe septic patients also respond well to albumin treatment.
- ***Gelatin***
  Gelatin originates from bovine (bone, sinew and skin) sources; it is on the average a 35,000 D polypeptide. It contains many lower molecular weight components, which move freely into the extravascular space, so that its intravascular volume-increasing effect is short, lasting for 1–2 h. It has relatively few side-effects (in higher doses it inhibits the thrombocyte function and worsens the quality of clot formation), but this is counterbalanced by an increased risk of allergic reactions or a theoretical chance of BSE. Its use in Europe is declining.
- ***Dextran***
  Dextrans are simple-chain carbohydrates of bacterial origin, with a high water-binding capacity, which are distributed with an average molecular weight 70,000 D or 40,000 D. They have an appropriate initial volume-expansion effect, which can be sustained for 3–6 h. They have severe side-effects: in doses of > 1.5 g/kg/day, they disturb blood coagulation, cause kidney failure, and increase the tone of the pregnant uterus. In spite of haptene prophylaxis dextrans

cause anaphylactic reactions most frequently among the artificial colloids. Their use as first-line volume expanders has declined, and overall, dextrans are not indicated for routine volume expansion. In special cases, their favorable effects on thrombocyte and leukocyte adhesions and inhibition of the inflammatory cascade system could be utilized therapeutically. The maximal dose is 20 mℓ/kg/day. They are currently being used less frequently; in 2004 they were administered to 8% of septic shock patients in Hungary.

- ***Hydroxyethyl starch (HES)***
  HES is a corn-derived modified amylopectine polymer, made resistant to the enzymatic effects of alfa-amylase in the plasma. The average molecular weight, substitution rate and C2/C6 hydroxyethylation rate account for the pharmacokinetics and side-effects. Today, two types of HES solutions are used with volume therapy goals in Hungary: a second-generation HES 200/0.5 infusion with 6% (isooncotic) or 10% (hyperoncotic) contents and a third line HES 130/0.4 6% product. These products eliminate the side-effects of the earlier HES solutions as concerns blood coagulation and the kidney function. HES is accumulated and broken down slowly in the reticuloendothelial system and does not activate the mononuclear-phagocyte system. Its intravascular volume-expansion effect lasts for 4–6 h. Anaphylactic reactions are rare, as compared with other colloids. The long-term use of HES may result in itching.

5. Perioperative fluid therapy in practice

There is no widely accepted routine recommendation for perioperative fluid therapy. The most important point is that preoperative dehydration (induced by starving, colon preparation, different diseases, etc.) must be corrected prior to the operation. Surgical specialties prefer liberal fluid therapy to the traditional one (5–15 mℓ/kg/h), because the stable hemodynamic state ameliorates the perfusion and oxygen supply of the tissues and therefore reduces postoperative complications, enhances restarting of the intestinal function, decreases nausea and vomiting, and shortens the duration of hospitalization. On the other hand, if there are major accompanying diseases, the administration of crystalloids in higher doses may result in significant side-effects (myocardial ischemia, a pulmonary function failure, a decreased oxygen supply of the tissues, and disorders in wound healing because of interstitial edema, prolonged paralytic ileus and metabolic acidosis). A controlled study of patients in the ASA I or II stages undergoing laparoscopic cholecystectomy demonstrated a better postoperative recovery when liberal (40 mℓ/kg/h) fluid therapy: was applied: the postoperative pulmonary function, exercise capacity and subjective recovery measures all improved (nausea, general well-being, thirst, dizziness, drowsiness and fatigue). Lung surgery seems to be the main indication of restriction of the perioperative fluid intake.

In surgical patients the effects of different solutions on hemostasis must be considered. Several studies have proved that crystalloids (independently of their type) increase the coagulability and decrease the serum level of antithrombin III. As regards postoperative bleeding, it is a benefit, but it may be harmful by worsening the perfusion of the tissues and increasing the likelihood of thrombosis. In colloids, albumin and gelatin do not influence the tendency to bleed; however, dextran and starch with a higher substitution level and with a higher molecular weight increase this tendency.

6. Clinical evaluation of the effectiveness of fluid replacement

The urine output is at least 1.0 mℓ/kg/h, while the BP and HR are in the normal ranges; on physical assessment, the skin and mucous membranes are not dry. The awake patient is not thirsty. Measurement of the central venous pressure or pulmonary wedge pressure and laboratory tests (periodical monitoring of the hemoglobin and hematocrit levels) are necessary.

When is transfusion necessary?
The "transfusion trigger" is the level of hemoglobin (Hgb) at which transfusion should be given. The tolerance of acute anemia depends on the type of the surgical procedure, the maintenance of the intravascular volume, the ability to increase the CO and HR, increases in 2,3-diphosphoglycerate to deliver more of the carried oxygen to the tissues, the Hgb and oxygen delivery (DO_2).

- DO_2 is the oxygen that is delivered to the tissues = CO x oxygen content (CaO_2). The Hgb is the main determinant of CaO_2.
- CO = HR x stroke volume (SV)
- $DO_2 = HR \text{ x } SV \times CaO_2$

The consequence of the last equation is that, if HR or SV are unable to compensate, Hgb is the major factor determining DO_2. Healthy patients have good compensatory mechanisms and can therefore tolerate Hgb levels of 7 g/dl. Patients with a compromised perfusion may require Hgb levels > 10 g/dl.

7. Tools of volume correction: injections, cannulas, tubes

The parenteral routes of drug delivery are utilized when
1. drug delivery through the gastrointestinal tract is impossible,
2. the drug is altered by ingestion (broken-down in the intestine),
3. the patient requires faster or prolonged action.

Giving an injection may lead to infection, and therefore strict adherence to asepsis to ensure sterility is mandatory. The basic requirements for injection are syringes and needles.

Syringes

Syringes, devices for injecting or withdrawing fluids, are made of glass or plastic. Their parts are a glass or plastic barrel, a tight-fitting plunger at one end and a small opening at the other end, which accommodates the head of a needle. Syringe tips may be of two main types: Record and *Luer*, but today *Luer* syringes are used exclusively. *Luer* syringes are made of plastic, are sterile, and are single-use. The syringe volume ranges from 1 (tuberculin with 0.01-mℓ gradations) to 2, 5, 10 20, 50 or 60 mℓ. Insulin syringes have unit gradations rather than volume gradations.

Hypodermic needles

Hypodermic needles are stainless steel devices that penetrate the skin for the purpose of administering a parenteral product.

Single-use ***Luer*** needles: They are metal + plastic, sterile, and can be connected to *Luer* syringes. The needle size is classified according to a color-coded scale (G = gauge). The needle gauge refers to the outside diameter of the needle shaft; the larger the number, the smaller the diameter. The needle lengths range from 1/4 to 6 inches. The choice of needle length depends on the desired penetration. The end of the needles is beveled to facilitate injection through tissues or rubber vial closures.

”Butterfly” needles: These have plastic wings which can be attached to the skin.

Braunule: This is the most often used needle + catheter combination. The commercial names include: Abbocath, Introcan, Jelco, Mecath, Surflo®, Vasofix-Braunüle, Venflon, etc. Parts: A plastic catheter (its end is smoothly beveled so that it dilates the opening made by the needle), a metal needle which is a little longer than the catheter (to pierce the skin), an injection port (with a valve which allows the infusion of medication, but the blood cannot flow out; after use, the valve closes automatically), and plastic wings.



”Butterfly” needle with cannula



Braunule



Valve mechanism of injection port



Parts of a braunule

Selecting the adequate iv. cannula

There are different iv. cannulas with various lengths and diameters to meet the various requirements. The table below gives information on B.Braun (Melsungen, Germany) cannulas (ISO=International Organization for Standardization).

Color code (ISO standard)	Outer diameter	Flow	Examples for practice
Yellow	0.7 mm	13 mℓ/min	Infants (neonates)
Blue	0.9 mm	36 mℓ/min	Infants
Pink	1.1 mm	61 mℓ/min	Thin veins; children
Green	1.3 mm	96 mℓ/min	Adults
White	1.5 mm	128 mℓ/min	
Gray	1.8 mm	196 mℓ/min	Quick volume replacement
Orange	2.2 mm	343 mℓ/min	Transfusion

8. Types of injection techniques

- Ampoules are made entirely of glass; for single use only. After an ampoule is opened, the drug must be utilized in a short time (sterility and degradation). Traditional opening: The ampoule is wrapped in thick gauze, and a file cut is made on the neck. The end of the ampoule is broken off by applying pressure on the side opposite the file score. Today, such a procedure is no longer needed as the thinned neck can easily be broken. The drug is sucked out so that the needle does not touch the outside of the ampoule.
- Vials: These are glass or plastic containers closed with a rubber stopper and sealed with an aluminum shield. They may be liquid vials or powder vials with diluents (mostly distilled water or physiological salt solution). The diluent is first added to the vial, the vial is then shaken, an air volume equal to the volume of the solution is expelled, and the solution is then sucked into the syringe.
- Air removal: Giving an injection may lead to air embolism. Before drug administration, therefore, air is removed from the syringe: the plunger is pushed into the syringe to remove air from the liquid.

8.1. Intracutaneous (ic.) injection

This is administered to layers of the skin, it is used mainly for diagnostic purposes (allergy testing, tuberculosis screening and local anesthetics). A tuberculin type syringe (1 mℓ) and a thin needle (25–27G) are used to administer a small volume (max. 0.5 mℓ) of medication. Sites: Inner forearm, posterior of upper arm. The needle should be inserted at an angle of 10 to 20°, bevel up, and the medication is administered just under the epidermis.



8.2. Subcutaneous (sc.) injection

This is administered into the fat and connective tissue underlying the skin with a thin (25–27G) needle. Sites: External-upper third of the upper arm, external-medial area of the thigh, or abdomen (insulin and heparin). The skin should be gently pinched into a fold to elevate the sc. tissue, which lifts the adipose tissue away from the underlying muscle. The injection should be given at an angle of 45° into the raised skin fold. The injection can be started only when no blood can be drawn back into the syringe. The absorption of drugs in shock states is uncertain.





The sites of sc. and ic. injections

8.3. Intramuscular (im.) injection

This is used for the injection of a larger volume (max. 5 mℓ) of medication into the muscular tissue. Sites: The gluteal muscle (m. gluteus maximus) with the ventrogluteal *Hochstetter* technique (*sec.* Ferdinand von Hochstetter, 1829–1884); in infants the lateral side of the femoral muscle. When an im. injection is to be given, the skin over the site should be stretched to reduce the sensitivity of the nerve endings, and the needle (20–25G) should be inserted at an angle of 90°. The skin should be stretched by using the Z track technique. If this does not happen, the fluid injected will come back out of the hole made. The Z track technique can be performed by stretching the skin gently between the thumb and index finger. It is contraindicated for patients treated with anticoagulants.



The sites of im. injections in adults (top) and infants (bottom)



The site of *im.* injection

8.4. Intravenous (iv.) injection

During an iv. injection, the needle is inserted through the skin into a vein, and the contents of the syringe are injected through the needle into the bloodstream.

Sites for iv. injections are the v. mediana cubiti, the v. cephalica, and the dorsal veins of the hand and foot. It is necessary to use a *tourniquet* centrally to the vein to make the vein bulge. 18–23G, "butterfly" or braunule needles are used, and the vein must be punctured with the bevel up at an angle of 30 to 45° in the direction of the vessel. Once the needle is in place, it is helpful to draw blood, thereby verifying the real position of the needle; the tourniquet is then released before the injection is slowly given. A sterile sponge is pressed on the site of the injection, the needle is pulled out and the patient's elbow should be kept in a flexed position.



The sites of iv. injection (top) and implementation (bottom)

9. Complications of injections

- The skin should be intact; injections should never be made into injured or infected skin. Nonsterile devices (needle, syringe or solution) can cause skin infections.
- Drugs injected into the tissue via an incorrect injection technique can damage the tissue or cause a nerve injury. An improperly given intragluteal injection can injure the ischiadic nerve.
- Hematoma (blood enters the surrounding tissue from the vein through the sting channel); paravenous injection ("para" – the needle slips out from the vein and drug solution passes into the tissue, causing pain and tissue necrosis). This can be decreased by means of a Novocaine infiltration or an aqueous fomentation.
- In allergic patients, a toxic reaction, edema and fever can occur. Administration of the drug must be stopped immediately.
- Sterile venous inflammation (after hyperosmolar compounds).
- Hematoma
- Intraarterial injection.

10. About veins in details

Indications for securing peripheral venous access: 1. Fluid therapy, 2. solutions with pH from 7.2 to 7.6; 3. if the osmolarity of the solution does not exceed 1100 mosm/ℓ; 4. the planned duration of therapy is less than 3 days; 5. iv. administration of drugs or taking blood samples.
Contraindications: Thrombophlebitis; local inflammation; lower limbs in adults.

For the puncture of veins, we should look for a site in the periphery (the dorsum of the hand) in order not to disturb the flow toward the heart if further interventions are necessary. Preferable features are a large lumen, branches of veins, introduction at the branching, the dorsum of the hand (here the veins can be strained better), and the dominant side (in a right-handed patient, the right hand).

Points to be avoided

- An infected skin area; inflamed veins.
- Punctures are never made in the medial-upper sector of the crook of the arm, due to the proximity of the artery.
- Thrombosis of veins (without flow).
- Paralytic arm (after a stroke), since the lack of muscle pump means that the blood flow could be inhibited.
- Blockage of lymph flow (e.g. following a breast operation).
- Joint regions (danger of inflection).
- Vein valves.
- Veins are usually vulnerable and small on the anterior side of the forearm.

Visualization of veins

- Hang the arm down.
- Ask the patient to clench his fists several times (muscle pump).
- Massage the veins with your finger.
- Apply 10 min of hypothermia (with warm water).
- Sprinkle/spray alcoholic solution on the skin above the vein.

Fixing of veins

- Stretch the skin above the vein so that it does not move before an iv. catheter is introduced.
- There are three possibilities to ensure a successful puncture: stretch the skin in the opposite direction to the puncture (dorsal hand); push the skin in the direction of the puncture (forearm); strain the skin on the side with a “C” maneuver, grasping the arm underhand.

10.1. Technique of blood sampling

Materials that should be available: Compression cuff; disinfection solution (alcoholic spray), sponges, sampling tubes, needle with syringe with closed cap, Braunule, adhesive tape/sticking plaster, container for used needles, sponges and gloves.

Position of patient

The patient is lying, supported by the elbows and with arms extended.

Localization of vein

Palpate with the fingers to identify a vein with large a lumen (see above).

Vein compression / tourniquet

Compress the cuff centrally to the vein so that the arterial pulsation is palpable. Ask the patient to clench his/her fists and wait several seconds. The tourniquet pressure can be precisely controlled following BP measurement, using the inflated cuff. The optimal counterpressure is normally 60–80 mmHg, under the level of the diastolic BP. Arterial pulsing should always be palpable, to avoid intraarterial puncture.

Disinfection

An alcoholic spray or a sponge with alcohol is used for disinfection and the skin area of the puncture is scrubbed. It is necessary to wait for 15–30 s for the effect of disinfection to be reached. It is always reasonable to disinfect the area of the puncture, because it decreases the risk of contamination even if the duration of exposure is not sufficient for the inactivation of all causative agents.

A hygienic environment is an important aspect

- Hands should be washed or disinfected.
- A new braunule is used for each attempt.
- The cap of the injection port is closed.
- The braunule should be changed every 2–3 days.
- If blood or lipid-containing solutions are administered, a more frequent change is required.

Fixing the vein

The skin above the vein is strained to block the movement of the vessel (see above).

Injection technique with a needle or braunule

- If a needle is used, it is introduced with face turned upward into the skin, at an angle of 30° to the skin surface, parallel to the axis of the vein.
- When an iv. catheter or braunule is applied, the injection port is grasped with the index and middle fingers while the stopper is held with the thumb, and the fourth and fifth fingers are placed on the patient’s skin. The catheter is pushed slowly into the vein at an angle of 30–45° until some blood appears in the blood chamber. It is then advanced about 1 cm at a decreased angle of puncture to ensure that the needle and catheter are in the lumen of the vein.
- When an iv. catheter or braunule is introduced, two resistances will be encountered: 1. the needle penetrates the skin; 2. the plastic catheter reaches the site of the puncture. (Penetration of the wall of the vein is often not be felt to be a discrete resistance.)
- When the above procedure is performed, the skin, the sc. connective tissue and the wall of the vessel should be penetrated in one continuous movement. As the first step, the skin will be penetrated; in the second phase, the catheter is introduced into the vein.
- With thinner (blue or pink) catheters, it is advisable to wait until the blood appears in the blood chamber as otherwise the posterior wall of the vein may be penetrated.

- The vein is pressed down with the ring finger above the end of the catheter while the needle is drawn back about 1 cm, until the appearance of blood in the plastic catheter. This means that the catheter is positioned in the vessel lumen. The catheter is pushed forward into the vein lumen. The drawing-back of the needle stabilizes the iv. catheter during the introduction (preventing its inclination), without damaging the wall of the vein.
- A sponge is placed under the end of the braunule. The catheter tip is touched by the right hand finger under the skin and pressed gently. The catheter is held with the thumb and index finger while the needle is removed with the other hand, and connected to a closing cap or infusion set.
- The tourniquet is released.
- Blood retraction: The needle is held with the left hand while the right hand draws back the plunger of the syringe. For blood sampling, the needle is fixed with one hand, while the blood sampling tubes are changed with the other hand.

Removing the needle or braunule

- An alcoholic sponge is first pressed onto the site of the puncture and the sponge is then pushed while the needle or braunule is removed. Next, the alcoholic sponge is pressed on the puncture site again until the bleeding has stopped (at least 1 min). The arm of the patient remains extended.

Blood sampling tubes

The sample is shaken gently to avoid damage to the blood cells, and it is mixed with anticoagulant. The coagulation (green), sedimentation (purple) and hematocrit (red) tubes should be filled exactly to achieve the correct dilution.

The sequence of sampling: a sample is first taken in the serum (white) tube, since the serum K^+ level may be elevated within 30 min as a consequence of stress. The second tube is green and serves for determination of coagulation factors. Coagulation occurs in the tube. (For this purpose, a blood sample must not be taken in the first tube because it might contain air or the concentrations of coagulation factors can be changed in the needle.) Other tubes should be filled thereafter. Blood sedimentation is usually evaluated at the department, and the sample should therefore not be sent to the laboratory for this.

Fixation of braunule

Adhesive tape is placed on the site of the puncture. The iv. catheter is fixed with the prepared adhesive tapes. The infusion tube is relaxed at the adhesive tape, the joint is fixed with a splint if necessary and apply gauze bandage is applied.

- It is important for the cannula to be fixed so as not to be pulled out or broken when the patient moves the arm. Mechanical irritation of the vein must be avoided.
- If the cannula remains in the vein for a longer period, a piece of gauze should be placed under the braunule in order to prevent pressure-induced injuries.
- A piece of adhesive tape fixed to the injection port provides protection against contamination. Furthermore, customary kits for fixation are available.

Final fixing

A loop of infusion tube is made and fixed with another adhesive tape. This will prevent the cannula being pulled out unintentionally. If the cannule is close to a joint, fixing of the joint with a splint may be helpful. In anxious patients, the limb should be covered with a bandage or fixed with a splint (e.g. children).



Checking

The tap of the connected infusion is opened for a few seconds. If the flow of the fluid is uninterrupted and no swelling can be seen at the site of the puncture, the cannule is very probably in the right position. This check can be performed prior to fixing too.



10.2. Infusions

In the event of a serious loss of fluid, or electrolyte and fluid imbalances, fluid substitution is the first thing to do. If this is not possible orally, fluid must be administered parenterally, most often as an iv. infusion. Infusion therapy provides a possibility for the administration of a major volume of fluid, electrolytes and drug into the circulatory system. The rate and duration of fluid administration can be regulated. If the concentration of a drug exceeds the physiological range, it can be administered in an infusion. Thus, a longer period of administration and a constant concentration in the blood can be achieved.

Infusion therapy is proposed before admission in the following cases:

- acute myocardial infarction, left heart failure,
- pulmonary embolism,
- stroke, hypertensive crisis,
- status asthmaticus,
- acute bleeding,
- shock, allergic reaction, burns,
- an unconscious state,
- acute artery blockade in the extremities,
- acute metabolic comas (hyperglycemia),
- Addison, or a hyper- or hypothyroid crisis.

Infusions are usually delivered into superficial veins (in the forearm, or the dorsum of the hand/foot); most often, it is delivered into the cubital vein. If a vein cannot be reached by punctures, it must be exposed surgically. In a long-term continuous infusion, etc, a catheter may be inserted into the superior vena cava after the exposure and dissection of the jugular veins. This catheter can also be used to measure the central venous pressure. The iv. infusion therapy involves many risks, and should be performed strictly in accordance with the rules of asepsis.

Infusions

Devices for iv. infusion

A sterile plastic infusion bag (infusion glass bottle), a sterile iv. administration set, hypodermic needles (“butterfly” and braunule), disinfecting solution, gauze, tapes, an infusion stand, and sterile disposable gloves.

The infusion set

The sterile set is wrapped in a double package (plastic and paper). The package should be opened only just before use. Sets of damaged packages must not be used (sterility!).

Parts of the iv. administration set

A spike, a drip chamber (flexible), and long tubing with the flow regulator (a plastic roller clamp for control of the flow rate):

The protective covering is removed from the port of the infusion bag and from the spike of the set, and the spike is inserted into the bag. The bag is hung on the stand; the lower part of the drip chamber is squeezed to set the fluid level, until the drip chamber is approximately one-third full. If the level of the fluid is too low, the chamber is squeezed to remove air to the bag. If the chamber is overfilled, the bag is lowered to below the level of the drip chamber and some fluid is squeezed back into the bag. The flow regulator is opened and the fluid is allowed to flow into the tubing (removing air). The end of the tubing is connected to the iv. catheter in the patient’s vein, and the flow rate is adjusted as desired. After a loop has been made in the tubing, the catheter is secured to the skin with strips of tape. During infusion, the patient, the administration set and the flow of fluid must be controlled continuously.

Dosage of infusion

- There are two types of drip chambers: microdrip (60 drops/mℓ; for the administration of medication or fluid delivery in pediatrics), and macrodrip (10–15 drops/mℓ; for routine/rapid fluid delivery or keeping the vein open).
- The volume of infusion fluid/drugs should be calculated. A formula to calculate drops: volume of infusion fluid (mℓ) × drop factor (drops/mℓ) / time to infuse (min) = drops/min. As an example, an infusion of 1000 mℓ of saline during 12 h with a microdrip chamber should be delivered at a rate of 1000 × 60/720=83 drops/min.
- The amount of the infusion depends on different factors (the body surface area, the physical condition, the age and the osmolarity of the infusion fluid).
- At the end of the infusion, the tubing is clamped, the tapes are removed, followed by the needle or braunule catheter, and sterile gauze is placed on the site of the puncture.

Other iv. administration sets

1. Set with hydrophobic bacteria filter

2. Dual drip infusion iv. set (with a micro- and a macrodrip chamber)



Risks and complications of iv. infusion therapy

- In peripheral iv. therapy, the position of the vein puncture should be changed after 48 or 72 h, and the catheters must be changed after 24 h.
- Hematoma: during the vein puncture, the wall of the vessel may be damaged (therapy: compression).
- Inflammation-thrombosis (during long-term infusions or the administration of acidic or alkaline solutions, or infusions of high osmolarity).
- The endothelium of the vessel wall may be damaged by the tip of the needle (compress).
- Air embolism (remove air!).
- Fever (rules of asepsis!).
- Circulatory insufficiency (in heart or renal failure during infusion at too high a rate!).

Variations of iv. infusion

Infusion of two different solutions. Two infusion sets are used. The tubes are connected with a Y tubing below the drip chambers.

Medication administration with an iv. infusion. This is delivered slowly together with the infusion fluid to attain a constant drug level in the blood.

10.3. Infusion pumps (IP)

IPs are used for the accurate, continuous, long-term and slow delivery of infusions and medication, medical fluids, enteral feeding products and blood to reach a constant blood level during therapy or in clinicopathological investigations. They are designed to allow precise control of the flow rate and the total amount of fluids for both clinician and patient use.

Types of IPs

- **Volumetric IP:** This allows the accurate, reliable, continuous, long-term and non-pulsatile iv. or ia. delivery of medical fluids (infusions, blood or enteral feeding products) to patients.

An electric or battery-operated peristaltic mechanism drives the fluid. The flow rate and volume infused can be preset. The pump is equipped with different optical and sound alarms, including air detection, empty container sensing, and occlusion alarm pressure setting (automatic shut-off). A volumetric IP can also be used to keep the vein open (a slow iv. infusion at 1 mℓ/h).

- **Syringe IP:** This facilitates the long-term, continuous iv. or ia. delivery of small volume of infusion or medication with different sizes of syringes.

The flow rate (e.g., depending on the type of syringe, from 0.1 to 1200 mℓ/h) and volume infused can be preset. Automatic shut-off is possible at the end of the infusion or at occlusion. These IPs are electric or battery-operated. They can be placed one on another, like a tower (also on an infusion stand). In this way, the simultaneous administration of several drugs can easily be checked.

- **Patient-controlled analgesia (PCA) pump** for pain management. This is a battery-operated, portable IP for patient use at home. It is easy for the patient to

wear it in a sack on the shoulder or fixed to a belt, and it does not disturb his/her movement. The PCA pump allows the patient to administer the pain-killing drug whenever he/she needs it.

10.4. Central venous catheterization, venasection, venous cut-down

The surgical catheterization of a peripheral vein was one of the first unaided interventions performed by a young surgeon. It improves practical skills, and provides possibilities for practising incision of the skin, the sharp and blunt dissection of tissues, and closure of the wound.

The golden mean, the middle, moderation are all ways of saying that when you know how nature works you will know the Tao. By knowing the Tao you start to know about God and the universe. Anything that's extreme, you have to back away from. The only thing that lasts long is balanced, middle and center.

Q. ***Is there a problem if I shake a lot during meditation?***

A. Too much shaking can scatter the energy. Moving and stillness have to be balanced. If you remain still for too long the energy might settle. But if you shake and scream and are never still you risk eventually shaking out all your life force.

If you start burning a fire, it gets hotter and hotter. When the water comes to a boiling point you turn it down and cook it very slowly. That way you can get the essence out. If you don't turn down the light all the water will boil away and the pot will be burnt or broken.

When you are into the meditation and very still, movement starts and many things are activated. If the movement becomes very strong it won't last long and you might want to stop it. You have to know the timing. If you start to shake, you can gain power by stopping the shaking and utilizing that energy inside. If you let the shaking continue, you might lose all the energy you built up.

In some forms of therapy people are encouraged to shake and jump and scream to get rid of their anger or depression or anxiety. When the session is over it seems that everything has been worked out but when they get home they are throroughly exhausted. The emotions were shaken out along with the life force. How much better to recycle the energy.

Tai Chi balances the Yin and Yang through movement and stillness. This builds up energy and then you can circulate the energy in the Microcosmic Orbit. The whole secret in the Universal Tao is having the channel for the energy to flow.

Q. ***Why do you create an Energy Body outside yourself?***

A. When you set up the Energy Body and the spirit body they start to draw out the essence of the physical body. Then it starts to work in space.

The veins of choice are the cubital veins (medial cubital vein, cephalic vein, and basilic vein), the external jugular vein in the collar region, and possibly the superficial veins of the leg (though thrombosis may develop in these veins). Major saphenal veins too can be chosen in the absence of other possibilities. During skills courses, preparation and catheterization of femoral and jugular veins can be demonstrated *in vivo*.

Technique of venous cut-down (venasection)

- A local anesthetic drug, a wide-bladed scalpel, *Mayo* scissors, *Péan* forceps (mosquito), thread, needles and needle-holder are required. Special attention must be paid to asepsis. The operating site should be disinfected and draped as usual.
- In clinical practice, a transversal incision should be applied in the cubital and collar region, but during *in vivo* training practicals an incision parallel to the vein can also be chosen. In this case, the vessel will be easier to access and there are more possibilities to practise different techniques of preparation. The scalpel should be used at right angles to the skin. The incision line is straight and the wound is the same in depth throughout its whole length. The scalpel is moved toward the operator with one decisive movement. Before the incision, the skin should be stretched with the thumb and index finger. Gross bleeding is rare. If the bleeding originates from capillaries, the bleeding area is pressed with a sponge for 1–3 min. Bleeding from major vessels is stopped by ligation.
- Subcutaneous tissues are easy to dissect. They should be cut bluntly and sharply with *Mayo* scissors. The tissue is lifted up with two forceps and a small incision is made with the scissors. The closed scissors are inserted into this gap and the tissue is dissected by opening them. The dissected layer can be cut, and thus the sc. area can be elongated to the ends of the wound. The deeper layers should also be dissected according to this method. The preparation should be made parallel to the vessel.
- The vessels appear; the artery is pink and pulsating. The veins have thinner walls and their color is blue. Closed scissors are placed next to the vessels, and veins should be dissected free by careful blunt preparation. When a 2–3-cm portion of the vein is free, a double thread is introduced under the vessel with mosquito forceps.
- The vein should be ligated peripherally. In animals, collateral vessels can replace the function of closed vessels better than in human (ligation of end-arteries and main arteries supplying organs leads to necrosis). However, after the ligation of major veins (femoral, subclavian and jugular veins) in animals, only transient signs of stagnation are to be found. A loose half-hitch is made on the proximal thread under the vein. A V-shaped incision should be made in the vein with vessel-scissors, close to the distal thread (5 mm from the knot). The incision involves 1/3 of the diameter of the vessel.
- The lumen should be opened with dental forceps. A catheter filled with saline is inserted, and the forceps are then removed. The catheter should be introduced carefully through the loose proximal loop and further, to reach a central position. Arrival at a lateral branch must be avoided. If an obstacle is found, the catheter is retracted slightly and moved to the side in order to find the way to the main branch. Before the proximal thread is tightened, saline is injected into the lumen and blood is aspirated into the syringe in order to check the function. The proximal half-hitch is tightened and a second knot is made. Care must be taken not to close the lumen!
- The catheter should be fixed with the distal thread too. Before the wound is closed, bleeding (if any) is stopped and clotted blood is removed. The wound is closed with subcutaneous sutures and vertical mattress sutures (*Donati*). The catheter is fixed to the skin with another simple suture.

Remark: At present the central venous catheterization is most often performed by percutaneous puncture of the jugular or subclavian veins.





VII. Bleeding and hemostasis in surgery

“The only weapon with which the
unconscious patient can immediately retaliate
upon the incompetent surgeon is haemorrhage”
(William S. Halsted: Bulletin of the
John Hopkins Hospital, 1912)

1. Hemostasis

Definition: This is a natural, life-saving defense mechanism which has three main factors: 1. a vascular mechanism (vasoconstriction), 2. a thrombocyte mechanism, and 3. clotting. All of these inhibit or decrease bleeding from the vessels.

During injury (incision), the endothelial damage (e.g. surgical incision) exposes matrix proteins and collagen, and the platelets clump and adhere to connective tissue at the cut end (*adhesion*). The platelets then release adenosine diphosphate (ADP), epinephrine, thromboxane A_2, serotonin (*release*), binding sites for fibrinogen appear on the platelet membrane, fibrinogen is involved in platelet-platelet adhesion (*aggregation*), and ADP + thrombin cause further platelet activation = primary thrombus. Platelet adhesion and aggregation form a plug that is reinforced by fibrin for long-term stability:


Demaged vessel wall
Platelet adhesion
Initiation of coagulation
Thrombin
Release of mediators
Fibrin
Platelet aggregates
Thrombus
Fibrinolysis
Fibrin degradation products


Intrinsic System
XII
XIIa
Extrinsic System
VII
XI
XIa
IX
IXa + VIII
X
Xa + V
Prothrombin
Thrombin
Fibrinogen
Fibrin
XIII
XIIIa
Stable fibrin clot

2. Main types of hemorrhage

Losses of circulating volume and oxygen-carrying capacity are generally termed hemorrhage.

This can be acute or chronic; primary or secondary. Secondary hemorrhage can be the aftermath of infected wounds, inadequate primary wound care, inadequate or traumatic dressings, or necrosis of the vessel wall (compression, drains, etc.).

Gross bleeding from cut or penetrated vessels
Arterial bleeding is bright-red and pulsating with the cardiac function. The volume loss depends on the size of the artery. Venous bleeding is often a continuous flow of dark-red blood with lower intensity (large veins: danger of air embolism!).

Oozing from denuded or cut surfaces
The continuous loss of blood from oozing can become serious if it remains uncontrolled. Capillary bleeding: a tamponade with dry or wet (warm saline) towels (only press) is used to stop oozing. Parenchymal bleeding: absorbable sutures or gelatin are used (see later). Minor bleeding during skin incision can be controlled by compression of the skin edges with towels.

3. Clinical classification

Hemorrhage can be classified according to the volume of blood lost. To assess hemorrhage, the patient’s mean blood volume must be known (males have ≈ 70 mℓ/kg (6% of the body weight), while females have ≈ 65 mℓ/kg).

	Class I	Class II	Class III	Class IV
Blood loss (mℓ)	Up to 750	750–1500	1500–2000	>2000
HR	<100	>100	>120	>140
BP	Normal	Normal	Decreased	Decreased
RR	14–20	20–30	30–35	>35
Capillary refill	Normal	Slight delay	>2 seconds	No filling
Skin	Pink and cool	Pale and cold	Pale, cold, moist	Mottled
Urine	>30 mℓ/h	20–30 mℓ/h	5–15 mℓ/h	<5 mℓ/h
Behavior	Slight anxiety	Mild anxiety	Anxious, confused	Lethargic, confused
Fluid therapy	Crystalloid	Crystalloid	Crystalloid, blood	Crystalloid, blood

4. Direction of hemorrhage

Clinically, bleeding can be external (e.g. trauma, or a surgical incision resulting in visible hemorrhage) or internal (e.g. urinary tract: hematuria, pulmonary: hemoptoa; see urology and internal medicine). The latter can be directed toward body cavities (intracranial, hemothorax, hemascos, hemopericardium or hemarthros), or among tissues (hematoma and suffusion).

4.1. Gastrointestinal hemorrhage

The dividing point between upper and lower gastrointestinal bleeding is the ligament of *Treitz* at the junction of the duodenum and jejunum.

- Hematemesis: The vomiting of blood or altered blood ("coffee-grounds") indicating bleeding proximal to the ligament of *Treitz*.
- Melena: Altered blood (black and tarry) from the rectum. Approximately 100 mℓ or more blood is required for one melenic stool. Melena indicates bleeding proximal to the ligament of *Treitz*, but it can be as far distal as the ascending colon. Iron, licorice, beets, blueberries and charcoal cause black stools.
- Hematochezia: Bright-red or maroon rectal bleeding. The bleeding is usually beyond the ligament of *Treitz,* but it can be due to rapid (> 1000 mℓ of blood) upper gastrointestinal bleeding.
- Occult: Unapparent bleeding. A common site is the intestines.

4.2. Causes of gastrointestinal hemorrhage

Before operation

- Mouth and pharynx: Malignant tumors or hemangiomas.
- Esophagus: An aortic aneurysm eroding the esophagus, esophagitis, hiatal hernia, tumors, peptic ulcers or varices.
- Stomach: Tumors, carcinoma, diverticulum, gastritis with erosion, peptic ulcers or varices.
- Liver: Cirrhosis.
- Duodenum: Peptic ulcer, diverticulum, tumor or duodenitis.
- Jejunum and ileum: Intussusception, tumors, peptic ulcers, enteritis, Meckel's diverticulum or tuberculosis.
- Pancreas: Eroding carcinoma or pancreatitis.
- Colon and rectum: Malignant tumors, diverticulitis and diverticulosis, a fissure, a foreign body, hemorrhoids, polyps or ulcerative colitis.

After operation

- Inadequate primary care.
- An unligated vessel or an unrecognized injury.
- Sutures or clips.
- A necrotic vessel wall; drain erosion; abscess wall erosion.
- Anticoagulant therapy or a long-term heparin effect.

5. Preoperative – intraoperative – postoperative hemorrhage

Bleeding can be classified according to the time of surgical interventions: it can be preoperative, intraoperative or postoperative.

Preoperative hemorrhage

Bleeding outside the hospital (see traumatology and anesthesiology). Prehospital care for hemorrhagic injuries includes maintenance of the airways and ventilation, the control of an accessible hemorrhage with bandages, direct pressure and tourniquets (these methods have not changed greatly in 2000 years), and the treatment of shock with iv. fluids (see later).

Intraoperative hemorrhage

This can be anatomical and diffuse. Risk factors include drugs used in clotting disorders to reduce clotting (anticoagulants, antiplatelet drugs and thrombolytics), cirrhosis, a liver dysfunction (clotting factors), uremia, hereditary coagulation syndromes/disorders and sepsis. The main factors influencing perioperative blood loss:

- The attitude of the surgeon: the training, experience and care of the surgeon (probably the most crucial factor).
- Careful planning and the optimal technique (minimally invasive/atraumatic surgical technique).
- The optimal size of the surgical team.
- Meticulous attention to bleeding points – use of diathermy (ligation, laser, argon coagulation, etc.).

- Posture – the level of the operative site should be a little above the level of the heart (e.g. the *Trendelenburg* position for lower limb, pelvic and abdominal procedures; and the head-up posture for head and neck surgery).
- The size of the bleeding vessels.
- The pressure in the vessels.
- Hemostasis: the diameter of bleeding vessels decreases spontaneously due to vasoconstriction (more pronounced in arterioles than in venules).
- Handling bleeding from arterioles is easier ("surgical") than that from diffuse venous vessels.
- Anesthesia (!): Intraoperative bleeding depends much more on the BP rather than on the CO; the BP can be maintained at an optimally low level by the anesthesiologist. Various anesthetic techniques are applied to minimize perioperative blood loss:
- If adequate levels of anesthesia and analgesia are ensured, avoiding hypertension and tachycardia due to sympathetic overactivity can be avoided.
- Controlled anesthesia (increase of the intrathoracal pressure increases CVP, while an increased pCO_2 increases MAP).
- Regional anesthesia (epidural or spinal), where appropriate (a 45% reduction in blood loss!); sympathicolysis leads to a lower MAP, and spontaneous breathing to a lower CVP).
- Controlled hypotension.
- Adequate medication of hypertonic patients.

6. Surgical hemostasis

6.1. Historical background

Ambroise Paré (1510–1590) used a hemostatic clamp and ligatures to stop bleeding at the siege of Damvillier in 1552.

Ambroise Paré

In surgery, bleeding is usually caused by ineffective local hemostasis. Bleeding is a dangerous complication as it impedes the surgical procedures, hides the tissues or organs being operated, and prevents wound healing. Surgical bleedings should therefore be controlled as rapidly as possible. The aim of local hemostasis (handling bleeding) is to prevent the flow of blood from the incised or transected vessels. Methods are 1. mechanical, 2. thermal, or 3. chemical.

6.2. Mechanical methods – temporary and final interventions

Digital pressure

- The first approach for hemorrhage control.
- When possible, direct pressure is combined with elevation of the bleeding site above the level of the heart.
- Applied over a proximal arterial pressure point.
- Intraoperative maneuvers (e.g. the *Pringle (Báron)* maneuver; compression of the abdominal aorta).

Tourniquet

- There is no completely safe tourniquet duration.
- In most cases, a tourniquet can be left in place for 2 h without causing permanent nerve or muscle damage.
- A tourniquet is commonly used in hand surgery to produce a bloodless operative field.

Ligation

- Hemostat (artery forceps: *Péan, Kocher*, mosquito, etc.): this is the most commonly used method of hemostasis in surgery.
- The source of the bleeding should be grasped by a hemostat with minimal inclusion of the neighboring tissues. This intervention (requiring the harmonized movements of the operator and the assistant) consists of three phases: soaking, clamping and ligation (see page 95).
- The assistant soaks up blood with sponge (only with a press, avoiding vasoconstriction). The surgeon clamps the vessel with the tip of a *Péan* without clipping the surrounding tissues. The point of the *Péan* should be upward and toward the surgeon. The surgeon passes the thread (nonabsorbable, thin suture material) around the vessel, and ties off the vessel with a knot.
- After the first knot (half-hitch) has been tied, the assistant removes the artery forceps. The surgeon ties the second knot, and cuts the threads with *Mayo* scissors just above the knot (leaving as little thread, as possible – foreign material!). Ligatures must not be used directly under the skin, because they hinder wound healing.

Suturing transverse, transfixing, "8": *sutura circumvoluta*): in cases of large-caliber vessels or diffuse bleeding. Nonabsorbable: silk, polyethylene or wire; absorbable: catgut, polyglycolic acid (Dexon) or polyglactic (Vicryl) can be used. A double stitch (suture twice) is applied under the bleeding tissue to form an "8"shaped loop and the knot is then tied.

Preventive hemostasis: with ligatures. In the operating field, a vessel should be clamped with two *Péans*, the vessel between them is cut, and the two ends of the vessels should be tied separately.

Ligating clips (Ligaclip®): metal or plastic.

Bone wax (Horsley and Squire in 1885–1892): This is a sterile mixture of beeswax, almond oil and salicylic acid. It adheres readily to the bloody bone surfaces, thereby achieving local hemostasis of the bone. The wax mechanically occludes and seals the open ends of bleeding vessels.

Expedients: suction, drainage (Hemovac, Jackson-Pratt, etc.) to remove body fluids and air. This
- facilitates the emptying of dead spaces,
- improves tissue regeneration, and
- blocks the development of edema and hematoma.

Other devices or mechanical methods for handling bleeding
- Rubber bands for digits.
- The *Esmarch* (1873) bandage (sec. Johann von Esmarch 1823–1908).
- The *Penrose* drain to remove fluid or blood.
- Vessel loops.
- Pneumatic tourniquets (single or double-cuffed).
- Pressure dressings, packing (compression) and tamponades.

6.3. Thermal methods

Low temperature – hypothermia
- Hypothermia (a hypothermia blanket, ice, cold solutions for stomach bleeding),
- cryosurgery: -20 to -180 °C cryogenic head
  - dehydration and denaturation of fatty tissue
  - decreases the cellular metabolism/O_2 demand
  - leads to vasoconstriction.

Heat (high temperature)
Based on protein denaturation (sec. *Galen*).

Electrosurgery
- In *Paquelin* electrocauterization (which stops bleeding by "burning" the bleeding vessels), the tissue is not part of the circuit. In diathermy, the patient is in the circuit. By 1910, the suitable frequencies had been determined, and a firm basis of knowledge on the effects of electrical heating of tissues and the concepts of fulguration, coagulation, desiccation/dehydration, and cutting current was established. Hemostatic scalpels appeared in 1928. Electrical current incises/excises or destroys tissues; the area is automatically sterilized and burned: bleeding is controlled with an aseptic technique. It can be used instead of scalpels or curettes.
- The principles involved are those of the handling of bleeding and an aseptic technique.
- When activated, the blade transfers thermal energy to the tissues as it cuts. It can be used to incise soft tissue and muscle.
- The effect depends on the current intensity and wave-form used. Coagulation is produced by interrupted (damped) pulses of current (50–100/s) and a square wave-form. Cutting is produced by continuous (undamped) current and a sinus wave-form.

Monopolar diathermy
An electrical plate placed on the patient acts as an indifferent electrode. Current passes between the instrument and indifferent electrode (large surface). As the surface area of the instrument is an order of magnitude less than that of the plate, localized heating is produced at the tip of the instrument, and a minimal heating effect is produced at the indifferent electrode.



Bipolar diathermy
In bipolar diathermy, two electrodes are combined in the instrument (e.g. forceps), and the current passes between the tips and not through the patient.



Local effects of electrosurgery

Electrocoagulation
Characteristics: A needle or disc touches the tissue directly, and burns the tissue (a grayish discharge). The tissues are expelled after 5–15 days. *Usage:* Bleeding coagulation.

Electrofulguration
Lighting or spark: The needle does not touch the tissue directly (it is 1–2 mm away). *Usage:* "Spray" function – control of diffuse bleeding.

Electrodesiccation
The current concentration is reduced, less heat is generated and no cutting action occurs (the cells dry out). The needle is inserted into the tissues. *Usage*: To destroy warts and polyps.

Electrosection
With a knife, blade or electrode. *Usage:* Excision or incision. In general, diathermy should not be used to cut skin, but only deeper layers (burn injuries). Recently, the generators operate with blended modes, i.e. they allow the operator to control the levels of cut and coagulation in combination. With high voltage, a coagulative effect is achieved, while a lower voltage produces a cutting effect.

Laser surgery
Laser surgery is based on the emission of radiation by light amplification through a tube at a microscopic level. *Usage:* Coagulation and vaporization (carbon or steam) in delicate and fine tissues (eyes – retina detachment repair, brain, spinal cord, or gastrointestinal tract). The operator must wear safety goggles. Suction of steam (CO_2) is necessary.

6.4. Chemical-biological methods

There are sterile hemostatic devices which aid the patient's coagulation system in the rapid development of an occlusive clot, and there are agents which cause vasoconstriction. *Characteristics:* Easy handling, quick absorption, non-toxic, and local effects without systemic consequences. Expected consequences: Vasoconstriction, coagulation and a hygroscopic effect.

Main types

- **Aethoxysclerol (polydocanol)**
  This is not used for active coagulation. *Main indications*: Small superficial skin varices (injection into the veins) and esophagus varix sclerotization (given to the proximity of the varix).
- **Absorbable gelatin:** (Gelfoam, Lyostypt or Spongostan) powder or compressed-pad form, made from purified gelatin solution. This can absorb 45 times its own weight in blood. Absorption takes place in 20-40 days.
- **Absorbable collagen** (Collastat®): This is in the form of a hemostatic sponge, applied dry to the oozing or bleeding site. Its use is contraindicated when there is infection or in areas where blood has pooled.
- **Microfibrillar collagen** (Avitene®): This is powder-like, absorbable material from a bovine source; it is applied dry. It stimulates the adhesion of platelets and the deposition of fibrin. It functions as a hemostatic agent only when applied directly to source of bleeding. It is applied to oozing surfaces, including bone and areas of bleeding difficult to reach.
- **Oxidized cellulose** (Oxycel®, Surgicel®): This is available as an absorbable, pad form. It is sutured to, wrapped around, or held firmly against a bleeding site, or laid on an oozing surface. It reacts with blood and quickly forms a clot. It increases in size to form a gel, and stops bleeding where other methods of control have failed; only a small amount is needed. It is absorbed in 7–30 days.
- **Oxytocin**: This is a hormone produced by the pituitary gland, but is prepared synthetically. It is used to induce labor (it causes contraction of the uterus after delivery of the placenta). It is a systemic agent used to control hemorrhage from the uterus, rather than a true hemostatic agent.
- **Epinephrine**: This hormone secreted by the adrenal gland, is also prepared synthetically. It is a vasoconstrictor used to prolong the action of a local anesthetic agent and to decrease bleeding. It is rapidly dispersed and has a short duration of action.
- **Thrombin:** This enzyme, extracted from bovine blood, accelerates the coagulation of blood and controls capillary bleeding. It combines rapidly with fibrinogen to form a clot. It is in liquid form, as a spray, mixed with saline. It must not be allowed to enter large vessels. It is for topical use only and is never injected.
- **Novel hemostatic agents** (recommended by the US Tactical Combat Casualty Care Committee and FDA approved). *Indications:* External bleeding, recombinant activated factor VII and conventional pressure dressings fail.
  1. HemCon: It is available as a chitosan-based product, made from shrimp shell polysaccharide + vinegar. This is a firm 7 × 7 cm dressing that is sterile

and individually packaged. It adheres to a bleeding wound, and exerts vasoconstrictive properties.

2. QuikClot: This granular zeolite absorbs fluid, acts as a selective sponge for water, dehydrates blood, has handling properties similar to those of sand, and can generate significant heat during the absorption process.

7. Intraoperative diffuse bleeding

7.1. Main causes

- A platelet deficiency after massive transfusion
- Hypothermia-induced coagulopathy
- DIC
- Elevated levels of circulating anticoagulants

7.2. Management of intraoperative diffuse bleeding

Locally

- Fibrin glue (fibrinogen + thrombin + XIII factor), a biological tissue adhesive, initiates the final stages of coagulation, when a solution of human fibrinogen is activated by thrombin. It is prepared during surgery by combining equal volumes of cryoprecipitate (usually one or two bags) and thrombin solution containing $CaCl_2$ (and sometimes antifibrinolytic agents). Commercial preparations: Tisseel VH, etc.
- *Indications:* Potential leaks in the dura mater, large traumatized bleeding surfaces in life-threatening conditions, leaking vascular suture lines, middle ear or microsurgical procedures, and plastic surgery.

Medication

- A thrombocyte suspension
- Aprotinine (a serine protease inhibitor)
- Synthetic lysine analogues: epsilon-aminocaproic acid (Amicar), and tranexamic acid: competitive antagonists of plasmin-fibrin binding
- Fresh frozen plasma, fresh whole blood.

8. Replacement of blood in surgery (for details, see transfusiology)

8.1. Historical background

1665	Dog-to-dog experiments were conducted by Richard Lower (1631–1691), an Oxford physician, who proceeded to animal-to-human over the next 2 years.
1818	James Blundell (1791–1878), a British obstetrician, performed the first successful transfusion of human blood to a patient for the treatment of postpartum hemorrhage.

End of 19th century: Anesthesia and asepsis and antisepsis made surgery a viable branch of medicine, though control of blood loss was still a problem.

1901	Karl Landsteiner (1868–1945) documented the first three human blood groups – blood types were discovered.
1916	Plasma was used first during World War I.
1932	The first facility functioning as a blood bank was established in a Leningrad hospital.
1936	The first blood bank in the USA was established (Cook County Hospital, Chicago).

8.2. Auto(logous) transfusion

Advantages: This reduces the risk of postoperative complications (e.g. infection, HIV, hepatitis B or C and CMV), there are no incompatibility or alloimmunization problems, no immunosuppressant is present, and the need for allogeneic blood transfusion is reduced.

8.2.1. Preoperative autologous donation = predeposit transfusion

Indications: This is performed in surgical procedures involving a large blood loss, and in delayed interventions, if the patient is suitable for blood transfusion or the blood is adequate for retransfusion. *Contraindications:* Anemia (Hgb < 11 g/ℓ), infections, circulatory insufficiency, cerebral or coronary sclerosis, a cachectic patient, or organizational difficulties.

- **Autotransfusion – whole blood transfusion**
  Blood is collected 3–5 weeks preoperatively, once a week. 1 unit of blood (400 mℓ) provides 1 unit each of concentrated red blood cells + fresh frozen plasma.

- **Autotransfusion – plasmapheresis**
  Plasma is separated from blood by centrifugation or filtration, and then frozen. The concentrated red blood cells are immediately returned to the patient to prevent O_2 transport disorders. During blood removal, crystalloid and colloid solutions are infused simultaneously.

- **Acute normovolemic hemodilution**
  Technique: Blood (1 to 3 units) is collected at the start of the operative procedure, and simultaneously replaced with crystalloid solution in a ratio of 1:3 or with plasma volume expander in a ratio of 1:1. During surgery, the diluted blood removed must be replaced at the end of the procedure. Advantages: The microcirculation is improved by the maintenance of normovolemia, and autologous blood replacement occurs. *Disadvantages:* O_2 transport is decreased, and clotting factors are diluted. *Contraindications:* Coronary and cerebral vascular diseases, a decompensated circulatory insufficiency, serious respiratory diseases, anemia, or hypovolemia.

8.2.2. Blood salvage

Technique: Blood (with anticoagulant!) is collected in a sterile container and returned to the patient through a microfilter. *Contraindications:* The blood is mixed with harmful agents (intestinal content, pancreatic fluid, cancer tissue or contaminated fluids). *Dangers:* The Hgb concentration is increased in salvaged blood, and it contains large amounts of clotting factors, fibrinolytic enzymes, damaged platelets and anticoagulants. It is necessary to control hemostasis because of hemophilia or a serious blood loss. *Advantages:* Simple and cheap.

8.2.3. Autotransfusion – adjuvant therapy

Erythropoietin (EPO) therapy
Technique: EPO-induced erythropoiesis is not related to the patient's age and gender, but depends on the patient's iron stores. Iron must first be added iv.; the number of red blood cells starts to increase after 3 days of treatment. During treatment, 1 unit of blood/week is produced; in 28 days, 5 units can be removed from the patient. *Indication:* The method can be used if the patient is not anemic, but a large blood loss is expected. *Disadvantage:* It is expensive.

8.3. Artificial blood

This can not be used in clinical practice (from 2006 on). Research pathways involve cell-free, chemically modified Hgb, synthetic perfluorocarbon solutions, or liposome-encapsulated Hgb. *Expectations*: A good O_2-binding capacity and delivery in sufficient time in the circulation; it must be similar to blood in some characteristics (viscosity, oncotic, osmotic pressure and rheology), can be stored and sterilized, does not have toxic and antigenous features and can be produced in large amount and at low cost.

9. Postoperative bleeding

Causes: Ineffective local hemostasis, a complication of blood transfusion, a previously undetected hemostatic defect, consumptive coagulopathy, or fibrinolysis (a prostate, pancreas or liver operation). Causes of postoperative bleeding starting immediately after the operation:

- an unligated bleeding vessel;
- a hematologic problem arising as a result of the operation.

Therapy

- If the circulation is unstable, immediate reoperation is essential!
  Action to be taken if the circulation is stable:
  - reassessment of the history and medication given;
  - the transfusion should be stopped, and a sample should be sent to the blood bank;
  - the body temperature should be checked; if it is low, the patient should be warmed;
  - laboratory coagulation tests and a platelet function test should be performed.

10. Local signs and symptoms of incomplete hemostasis

Visible (skin) signs: Hematoma formation, suffusion and ecchymosis. Compression, suffocation and dyspnea (thorax and neck). Myocardial insufficiency (pericardium), intracranial pressure (head), compartment syndromes (muscle), dysfunction and hyperperistalsis in the intestines.

11. General symptoms of incomplete hemostasis

Shock symptoms: A cold skin, pale mucous membranes, sweating, cyanosis, hypotension, tachycardia, dyspnea, hypothermia, mental status, hemodynamics and laboratory alterations (see the chapter on shock).

VIII. Hemorrhagic shock

> *"Igitur corde percusso sanguis multus fertur, venae elanguescunt, color pallidissimus, sudores frigidi malique odoris tamquam inrorato corpore oriuntur, extremisque partibus frigidis matura mors sequitur."*
> *Aulus Cornelius Celsus: De Medica (1478) Liber V. 28.8.*

1. General remarks

- Hemorrhagic shock was well characterized by Celsus (1st century Roman savant): "*When the heart is injured, much blood is lost, the pulse becomes feeble, the skin becomes extremely pale, the body is covered with a malodorous sweat, the extremities are frigid, and death occurs speedily*".
- Shock is a condition leading to death - according to John C. Warren (1895): "*a momentary pause in the act of death*". The treatment depends on the early recognition. Shock may be presumed suspected from the anamnesis and the risk factors.
- Shock is not equal to hypotension (shock is not always accompanied by hypotension due to the compensation mechanisms in the circulation). Not every hypotensive state indicates a shock circulation, and not every shock state is accompanied by low BP.
- The main types of shock, depending on the cause of the syndrome: hypovolemic, cardiogenic, distributive, and others, such as obstructive. There are many other shock states; the clinical shock types are not strict categories.
- Independently of the category, the key factor of shock is inadequate tissue perfusion (CO may be low or high), i.e. independently of the main cause (trigger), the main pathogenetic factor is an imbalance between the O_2 delivery and demand, resulting in a disordered cell function.

2. Types of shock

Hypovolemic	Distributive	Cardiogenic	Others
Dehydration, starvation	Anaphylactic	Congenital cardio-myopathy	Heat
Gastro-enteritis	Neurogenic	Ischemic	Pulmonary emboli
Burns	Drugs (toxicity)	Anoxic	Pancreatitis
Hemorrhage	Septic	Tamponade	Obstructive

Shock may be comprised of components of different subtypes (e.g. distributive and cardiogenic): the types are not obligate!

3. The essential patterns of circulatory shock


Normal CO
Reduced CO
Normal / elevated CO
Normal CO
Normal perfusion
Normal circulation
Reduced perfusion
■ Cardiogenic shock
– Inadequate MC
– Inadequate HR
– Excessive afterload
Reduced perfusion
■ Sepsis, anaphylaxis
– Dilated container without change in fluid volume
Reduced perfusion
■ Hypovolemic shock
– Abnormally low circulating blood volume
– Leak in container

4. Anamnesis of shock

Signs upon physical examination:
- depressed central nervous system activity,
- an abnormal mucosal color,
- a decreased urine output (a sign of systemic tissue hypoperfusion),
- tachypnea, tachycardia,
- decreased capillary refill.

Biochemical changes:
- arterial blood gases: acidosis with a base deficit (a sign of tissue hypoperfusion),
- venous blood gases: decreased venous O_2 saturation,
- an electrolyte imbalance.

5. Compensatory mechanisms after blood loss

5.1. Baroreceptor reflex

This responds to small changes in vascular tone/pressure. It leads to a decreased vagal tone, which increases the HR, and decreases the coronary resistance (improves the myocardial O_2 supply). The sympathetic tone is increased, which causes venoconstriction, constriction of blood reservoirs (increasing circulating blood volume), and decreased perfusion in the skin and skeletal muscle.

5.2. Chemoreceptors

These are sensitive to O_2 and CO_2 and sense hypoxia (due to inadequate blood flow in the peripheral tissues and a MAP of ~ 60 mmHg). Important chemoreceptors are the carotid and aortic bodies. Reflexes that regulate BP are integrated in the medulla. The results are further vasoconstriction and an improved venous return (to the pump).

5.3. Endogenous vasoconstrictors

The adrenal medullary hormones norepinephrine and epinephrine cause vasoconstriction and an increased CO. Vasopressin (anti diuretic hormone - ADH) released from the posterior pituitary causes intense vasoconstriction in cases of extremely low MAP. Renin (from a decreased renal perfusion) leads to angiotensinogen and angiotensin II production. The endothelium-derived factors endothelin-1 and prostaglandin-derived growth factor are both potent vasoconstrictors.

5.4. Brain ischemia

Low MAP (60 mmHg) causes a decreased cerebral perfusion pressure and an increased sympathoadrenal activity (which is higher than that induced by baroreceptors), involving the increased release of catecholamines from the adrenal glands and sympathetic nerves (leading to vagus nerve stimulation, which has opposite effects).

5.5. Changes in renal water metabolism

The aldosterone release stimulated by vasopressin results in Na^+ reabsorption in the distal tubules of the kidneys; water follows the Na^+.

5.6. Reabsorption of tissue fluids (*"fluid shift"*)


Hydrostatic pressure
0 mmHg
NFP= -5 mmHg
NFP= +5 mmHg
Interstitial Fluid
Hydrostatic pressure
20 mmHg
Colloid osmotic pressure
25 mmHg
Hydrostatic pressure
30 mmHg
Venous blood
Capillaries
Arterial blood

At the arterial end, the hydrostatic pressure dominates, and fluid moves out of the circulation with +5 mmHg. At the venous end, the oncotic pressure predominates and fluid moves into the bloodstream with an NFP of -5 mmHg.


Increasing
inflow
Hydrostatic pressure
0 mmHg
Decreasing
outflow
Interstitial Fluid
Hydrostatic pressure
10 mmHg
Colloid osmotic pressure
25 mmHg
Hydrostatic pressure
25 mmHg
Venous blood
Capillaries
Arterial blood

Decreased MAP and arteriolar constriction lead to a decreased hydrostatic pressure and a decreased venous pressure. The oncotic pressure is constant, so the fluid exchange from the capillaries to the extracellular space decreases, and the fluid return from the extracellular space to the capillaries increases. This "fluid shift system" increases the blood volume, which increases MAP and helps compensate for shock (the fluid shift in adults is 1 ℓ/h). Two remarks:

1. *"One great consequence of blood loss is the intense vasoconstriction, the shrinkage of the capacity of the vascular bed to accommodate the decreased blood volume...adjustments for blood loss take place...the entry of fluid into the blood vessels in a compensatory attempt. The greatest extravascular store of readily available fluid in the body is... in the extracellular space." (Beecher et al. Recent Advances in Surgery I. The internal state of the severely wounded man on entry to the most forward hospital. Surgery, 1947).*

2. Caveat: *"Possibly, too much attention has been given to the fact that on many occasions [patients in shock may have a normal blood pressure]. ...this has led to a tendency to dismiss the blood pressure as a helpful sign even when it is low - a fatal error, on some occasions. More helpful than the level of the blood pressure is the direction of its swing - a falling blood pressure, a rising pulse rate, are in most cases an urgent indication of the need for blood." (Beecher, LTC and Henry K: Annals of Surgery, 1945).*

6. Decompensatory mechanisms after blood loss

6.1. Cardiac failure

This has many potential etiologies (i.e. the actual etiology is controversial). The myocardial strength may decrease from ischemia secondary to a reduction of cir-

It's the same reason that every country wants to set up laboratories in space. You can make a lot of things better in space because there's no gravity, no dust and no germs.

The Energy Body will draw the essence up; you might even feel like it's going to pull your whole body up. And then the Energy Body draws the energy from space and the universe and mixes them in. When you bring the energy back into the body the organs will absorb all this energy and start to transform. But if you sit down without a purpose you won't get this effect.

Everytime you add more of your body's energy to the Energy Body, the Energy Body will go higher. Sometimes I feel like all my essence leaves my physical body. When you practice every day it starts to take the essence of this body and transform and mix it with the universal energy and your progress will be remarkable. There will be no resistance. When you're finished meditating, you just shrink the Energy Body down and each time you shrink it down the pearl becomes more refined.

At one time, the Taoist Masters were afraid of losing the pearl in space and did it all inside the body. This was reflected in the art in China where they worked incredible detail on miniature objects. But later the Tao masters discovered that if they know how to send the energy out the head they can expand the Energy Body and then shrink it down. That way they achieved more perfection—it's the same way they make a computer chip.

If you look inside a chip there's a whole city inside it. They draw every detail on paper the size of a football field and then with a special camera they shrink it down and down.

Set it up, do all the detail you want, then shrink it down and pull it back in.

culating red blood cells, lower oxygen saturation, or decreased coronary perfusion secondary to hypotension (especially diastolic hypotension).

6.2. Acidosis

Hypoperfusion leads to an anaerobic metabolism and lactic acidosis. As a depressant of the myocardial function, there is a decreased response to catecholamines in both the myocardium and the peripheral vasculature.

Caveat: *"Although this is a time-honored concept, recent data do not find evidence of this phenomenon. Metabolic acidosis is a sign of underlying lack of adequate oxygen delivery or consumption and should be treated with more aggressive resuscitation, not exogenous bicarbonate"* (John P. Pryor: Hemorrhagic Shock, 2004).

6.3. Central nervous system depression

This is due to opioid release (enkephalins and beta-endorphin). Naloxone has been used as treatment in shock, with some success.

6.4. Disseminated intravascular coagulation (DIC)

Abnormalities of the clotting system develop as a result of attempts to control hemorrhage, but also dilution/loss of clotting factors. Gastrointestinal hemorrhage is seen as a complication of acute hemorrhage, hours after the initial event.

6.5. Reticuloendothelial system dysfunction

Loss of the antibacterial function can lead to endotoxin release from native bacteria, aggravating an already compromised situation.

7. Stages of hemorrhagic shock

7.1. Compensated shock

This entails some decrease in tissue perfusion, but the body's compensatory responses are sufficient to overcome the decrease in available fluid.

7.2. Decompensated shock

Blood moves to more vital organs. The decreased venous return results in a fall in CO. Viscera (lung, liver, kidneys and gastrointestinal mucosa): These are congested due to the stagnant blood flow. Respiratory system: Attempts are made to compensate for the acidosis by increasing respiratory rate and producing a partially compensated metabolic acidosis. Activation of clotting mechanisms leads to hypercoagulability (DIC).

7.2.1. Main microcirculatory phases during decompensation:

a. The precapillary sphincters relax due to shock-related stimuli.



Precapillary sphincter constriction



Precapillary sphincter relaxation

b. The postcapillary sphincters resist local effects and remain closed => pooling/capillary stasis, capillary engorgement.

c. Increasing hypoxemia and acidosis lead to the opening of additional capillaries, and the vascular space expands greatly.

- The degree of change is so great that even the normal blood volume can not fill the available space.
- The circulatory blood volume can not fill the vena cava.
- Decompensated shock progresses to irreversible shock if fluid resuscitation is inadequate or delayed.

7.3. Irreversible shock

The body is no longer able to maintain the systolic BP, and both the systolic and diastolic BP begin to drop. The pulse pressure may be narrowed to such an extent that it is not detectable with a BP cuff. The loss of arterial BP causes damage from which ultimate recovery is not possible despite temporary restoration of the MAP. Multiple organ system failure and organ damage (MOF and MOD) occur, and even with treatment death is the result.

8. Signs of progressing shock

- Bradycardia
- Serious arrhythmias
- Serious hypotension
- MOF
- A pale, cold and clammy skin
- Prolonged capillary filling/stagnation
- Cardiopulmonary failure.

9. Ischemia-reperfusion injury

A complex cascade mechanism occurs in two steps, an inflammatory (a local and then a systemic) reaction, leading to MOD and MOF. The target organs of ischemia-reperfusion injury are the heart, lung, skeletal muscle and gastrointestinal tract. During ischemia, an anaerobic metabolism and cellular function disorders are initiated. Injury and cell death (necrosis and apoptosis) are caused by reductive stress. During reperfusion, the production of reactive free radicals (oxygen and nitrogen) is started with the activation of leukocyte-endothelial cell interactions and enzymes, etc. Injury/cell death (apoptosis and necrosis) are caused by oxidative stress.

10. Intestinal mucosa injury

- Splanchnic redistribution is one of the compensatory mechanisms.
- There are serious consequences if shock processes are prolonged (the mucosa is sensitive to hypoxia and ischemia-reperfusion).
- Injury to the intestinal epithelium leads to bacterial translocation (intestinal flora, toxins, etc. are translocated into the circulation); the consequences are systemic inflammatory response syndrome, MOD and MOF.

11. Shock diagnosis

The first thing to note is that this is a clinical diagnosis! In most cases, the diagnostic tools are only available after initiation the therapy.

- Decreasing Hbg, hematocrit (responds only later due to the *fluid shift*).
- Decreasing CVP (1–9 cmH_2O).
- Decreasing pulmonary capillary wedge pressure: 5–12 mmHg.
- Decreasing CO (4–6 ℓ/min).
- Decreasing mixed (venous) O_2 saturation (the normal value is ~ 75%).
- Increasing total peripheral vascular resistance (the normal values are ~ 800–1400 dyne s/cm^5).

12. Relationship between mortality and time elapsed from injury to therapy

	Interval [h]	Mortality [%]
World War I	12–18	8.5
World War II	6–12	5.8
Korean War	2–4	2.4
Vietnam War	1–4	1.7

Approximately 53% the cases of traumatic death occur onsite, 7.5% in the emergency room, and39.5% in hospitals. In the hospital 50% of the deaths are caused by central nervous system-related problems, **31%** by hemorrhage and 18% by sepsis (Trunkey DD, Holcroft JW. *Trauma: general survey and synopsis of management of specific injuries.* In: Hardy's Textbook of Surgery, 1988).

13. Treatment of hemorrhagic shock

1. Evaluation: Internal or external hemorrhage? Are there underlying cardiac problems? Amount of blood lost? Duration of bleeding? **And** stop the bleeding!

2. Level of consciousness (motto: "*Report and record*"):
    - alert,
    - verbal response to stimuli,
    - pain response to stimuli,
    - no response to stimuli.

3. Determination of aims (to determine and increase tissue perfusion and oxygenation, and to eliminate and treat the triggering cause. The cause, and not the shock, is what must be treated!).

4. The first steps involve positioning, the ABC approach, keeping the patient at normal temperature to prevent hypothermia. Ongoing assessment (every 10–15 min) is mandatory.

A = Airways
- Depends on etiology: from minimal to complex therapy (intubation, and mechanical ventilation).
- If the patient can say his/her name: the airways are free (!)

B = Positive-pressure ventilation
- Breathing: Patients need respiratory support (intubation or other respiratory support) and monitoring. In general, respiratory support and monitoring are needed even in the case of adequate O_2 saturation to help compensation for metabolic acidosis.

C = Circulation

- What is to be given? “Volume” (!)
- How to give it? The flow in the catheter is inversely proportional to the length of the tube and directly proportional to the cross-section: a short, wide and peripheral iv. infusion set must be used!
- Where to give it? Into peripheral (antecubital) visible/palpable veins. Intraosseal colloid therapy is probable in children, if an iv. route cannot be secured quickly. A central vein can be used only after a routine has been attained!
- What type of fluid? Isotonic (in the ideal case isooncotic) fluid should be given. Physiological salt solution is available everywhere; first, 2 ℓ of salt solution or lactated Ringer, but in most cases much more (20 mℓ/kg!) is given. 3 units of crystalloid is ℓ unit of intravascular fluid (!), colloid solutions supplement the volume in a 1:1 ratio (see above).
- 2 U of red blood cells are given if the circulation is unstable after the administration of 2000 mℓ of crystalloid. More blood may be needed during active bleeding (warming, taking a blood sample before transfusion, cross-reaction!).
- Fresh frozen plasma and a thrombocyte suspension are indicated for the treatment of the symptoms of coagulopathy (usually after giving 6-8 U of blood).

D = Definitive therapy / Drugs:

- The goals are to 1. increase the preload, 2. to increase the contractility, and 3. to decrease the afterload.
- Correction of acidosis
  - Background: A pH < than 7.25 will interfere with the effects of catecholamines and inotropic resistant hypotension evolves.
  - Method (see above): Na-bicarbonate is given if the deficit > 6 meq/ℓ.
    A useful formula: 0.3 × kg bw × base deficit = meq $NaHCO_3$ will compensate for half of the loss. It should be given slowly in a 1–2 meq/kg bolus; 10–20 meq/kg could be needed, which means a large Na^+ load and hyperosmolarity.

Treatment with pressors
- β effects: Increase inotropy and chronotropy - increasing CO (beta-1), and also some pulmonary and peripheral vasodilation (beta-2).
- α effects: Increase the systemic vascular resistance - maintaining the BP
- Vasodilators: Decrease the systemic vascular resistance, and decrease the afterload, potentially improving the cardiac function, but also dramatically reducing the MAP in hypovolemic patients.

	Alpha Peripheral	**Beta 1 Cardiac**	**Beta 2 Peripheral**
Norepinephrine *alpha and beta, more alpha*	++++	++++	0
Epinephrine *beta and alpha, stronger beta*	++++	++++	++
Dopamine	++++	++++	++
Isoproterenol	0	++++	++++
Dobutamine *beta-1 alone*	+/0	++++	+

(Source: NEJM, 300:18, 1979)

5. Further important interventions – correction of electrolyte abnormalities.

The Na^+ level can be markedly abnormal as a result of the underlying disease (hypo/hypernatremic dehydration); it can become elevated during the process of correcting a base deficit. The goal should be to normalize the Na^+ level- slowly! Hyperchloremia may aggravate acidosis.

The K^+ level can be elevated to the point of cardiac dysrhythmias. As the correction of acidosis occurs, K^+ can be driven back into the cells, severe hypokalemia developing in some cases.

Ca^{++} can be chelated in the treatment of a base deficit and dramatically decrease, leading to problems from seizures, hypotension and a myocardial dysfunction.

Glucose: As part of the response to compensatory mechanisms (epinephrine and corticosteroids), hyperglycemia is a common occurrence in stressed children. This can cause problems from osmotic diuresis and glucose intolerance. Care should be made not to overload the glucose management system in the body (i.e. no dextrose in flush solutions).

6. Blood gases: It is important to maintain good DO_2 so as to minimize the anaerobic metabolism and acidosis. Venous blood gases are also of benefit since mixed venous O_2 saturation is a measure of tissue perfusion and CO.

7. Hemodynamics: MAP and ECG: A decreasing MAP may be a sign of decompensation. Monitoring the CVP may be indicative of tissue hydration and the preload (see above).

8. Coagulation status: DIC is a common complication even early in shock.

9. Urinary output: This is representative of the organ perfusion. An improving urinary output can be a sign of an improving volume status, while a worsening output suggests the need for more aggressive therapy.

10. Neurologic status: Indicative of brain perfusion.

14. Signs of cardiovascular stabilization

- MAP is stable.
- HR is decreasing.
- Consciousness, and decreased anxiety.
- Increasing capillary refilling, improved color of mucous membranes.
- The urinary output exceeds 30 mℓ/h.

15. Medical – legal pitfalls

- Unrecognized occult bleeding.
- Hypotension after head trauma (hypotension and other causes!).
- Omission of rectal finger examination.
- Undiagnosed bleeding source.
- Inadequate resuscitation (*immediate, correct, sustained therapy*)

16. Variations in physiological responses to hemorrhagic shock

It is important that there are significant differences in relation to the following parameters:

- Age and relative health
- General physical condition
- Preexisting diseases
- Ability to activate compensatory mechanisms
- Older adults are less able to compensate (they develop hypotension early)
- Children compensate longer and deteriorate faster
- Medication may interfere with compensatory mechanisms.

IX. Wounds

"Notae vero inflammationis sunt quattuor: rubor et tumor cum calore et dolore".
Aulus Cornelius Celsus (BC 25-50 – 45-50 AD)
De Medica (1478) Liber III. 10.

The etymology of the word wound is the Old English "wund" and the Old Norse "und". A wound is a disruption of the continuity of tissues produced by an external mechanical force, a cut or break in the continuity of any tissue, caused by an injury or operation. As a consequence, the circulating blood volume is lost, while the breakdown of the defense mechanisms of the skin leads to the entrance of pathogens and foreign materials into the body. The exposure of body cavities and internal organs means a further risk. Surgical wounds are usually made under sterile circumstances and are closed layer by layer upon completion of the surgical intervention. Accidental wounds, however, are caused by mechanical trauma and can be either open or closed. Wounds can result from mechanical, thermal or chemical forces and irradiation, but the focus here will be on the characteristics and management of wounds caused by mechanical injury. The term injury is used synonymously with wound, but can have a wider meaning; wound (in surgery) = mechanical injury.



1. Classification of accidental wounds

1.1. Morphology / classification depending on the penetration route

A puncture wound *(vulnus punctum)* is caused by a sharp pointed tool, wood splinters, pins, nails, glass, scissors or knives and usually, misleadingly, seems to be negligible. Some punctures are merely on the surface, whereas others can be very deep, depending on the source and cause.

Treatment: Such wounds usually close quickly on their own. Treatment may be necessary to prevent infection, as the object that caused the wound may carry bacteria or tetanus spores into the skin and tissue.

An incised wound *(vulnus scissum)* is caused by sharp objects; it involves a linear cut in the skin, which is usually superficial, but may involve deep structures (surgical incisions). This type of wound exhibits the best healing. The extent of opening of the wound depends on the tissue flexibility and the directions of the Langer lines. These wounds are accompanied by considerable bleeding.

A cut wound (*vulnus caesum*) is similar to an incision, but with an additional direct, perpendicular force. The impact bursts the tissues open (e.g. an axe injury).

A crush wound *(vulnus contusum)* is caused by a blunt force and can be either open or closed. Heavy objects split the skin and shatter or tear the underlying structures. Fingers and toes are commonly involved. This is a painful injury with much swelling. The wound edges are usually uneven and torn. The bleeding is negligible, but the pain is proportionately greater than would be expected from the size of the injury (termed wound stupor).

A torn wound *(vulnus lacerum)* is caused by great tearing or pulling forces and can result in the incomplete amputation of certain body parts.

A shot wound *(vulnus sclopetarium)* consists of an aperture, a slot tunnel and an output. A shot from close range is usually accompanied by some degree of burn injury at the aperture. Other characteristic features are the incorporated foreign materials: textile fibers, bullets and the various types of tissues penetrated.

A bite wound *(vulnus morsum)* is a ragged wound with crushed tissue characterized by the shape of the biting teeth and the force of the bite. It is also accompanied by the features of torn wounds. There is a high risk of infection (transmission of malaria, rabies, etc.; human bites carry a considerable risk of infection through the transmission of HIV or hepatitis B). Such wounds should not be sutured.

1.2. Classification according to "cleanliness" – bacterial contamination

Clean wounds (operation or sterile conditions; only the normally present skin bacteria are detectable) with no signs of inflammation.

Clean-contaminated wounds (the contamination of clean wounds is endogenous or comes from the environment, the surgical team, or the patient's skin surrounding the wound). They include opening of the digestive, respiratory or urogenital tract.

Contaminated wounds (large contaminates infect the wound) arise when an incision is performed in a purulent area or in cases of a leakage from the gastrointestinal tract.

Dirty wounds (the contamination comes from the established infection), in which there are residual nonviable tissues and chronic traumatic wounds.

1.3. Classification depending on the time since the trauma

Acute wounds (mechanical and other injuries):

- Fresh wound: treatment within 8 h.
- Old wound: ≥8 h after trauma/discontinuity of the skin.

Chronic wounds (venous, arterial, diabetic and other ulcers, and skin or soft tissue defects):

- They do not heal within 4 weeks after the beginning of wound management.
- They do not heal within 8 weeks.

With chronic wounds, the normal process of healing is disrupted at one or more points (in most cases, the healing process is 'stuck' in the inflammatory or proliferative phase; see later).

1.4. Classification depending on the number of skin layers involved

- **Grade 1:** Non-blanchable erythema of intact skin. Discoloration of the skin, warmth, edema, induration or hardness may also be used as indicators in people with dark skin.
- **Grade 2:** Partial-thickness skin loss involving the epidermis, dermis or both. The ulcer is superficial and presents clinically as an abrasion or blister.
- **Grade 3:** Full-thickness skin loss involving damage to or necrosis of subcutaneous tissue, which may extend down to, but not through the underlying fascia.
- **Grade 4:** Deep wounds or complex wounds (e.g. lacerations, or vessel or nerve injuries), or wounds of the bone or supporting structures, the opening of body cavities, or penetrating injuries of organs.

1.5. Classification depending on the factors affecting wound healing



The scheme of *sanatio per primam intentionem* ("p.p. healing"). According to Galen (Galenus, BC 129-199): "the major aim" of a doctor is the gap-free healing of wounds. Wounds are closed surgically by reconstruction of the skin continuity (a) by simple suturing, (b) by the movement (relocation) of skin fragments from the surrounding area (flaps), or (c) by the transplantation of free skin elements (grafts) of different thicknesses (e.g. split- or full-thickness grafts). Primary healing is usually the case in all wounds in which the anatomical location and the size allow the skin continuity to be restored (no significant degree of tissue loss); healing takes place from the internal layers outward.



The scheme of *sanatio per secundam intentionem*. Secondary healing is the mode of healing of abrasions or split-thickness graft donor sites. The tissue loss is compensated by a granulation tissue "according to the second potential goal of the doctor". (Due to the abacterial or purulent inflammation, the wound is filled with connective tissue which transforms into scar tissue. If there is significant tissue loss in the formation of the wound, healing will begin by the production of the granulation tissue wound base and walls. After wound *debridement* and preparation, the wound is left open to achieve sufficient granulation for spontaneous closure (re-epithelialization from the remaining dermal elements or from the wound borders).

Tertiary (delayed primary) healing occurs in primary contaminated wounds or mixed tissue trauma wounds (e.g. after the reconstruction of hard tissue).

Factors influencing wound repair

- Drugs: Glycocorticoids inhibit fibroblast activity, protein synthesis and immune responses. Some antibiotics inhibit collagen biosynthesis. Cytostatic agents slow down metabolic processes. Anti-inflammatory agents reduce hyperemia and the blood supply to the wound (they may slow down the healing process if they are taken after the first several days of healing, following which anti-inflammatory drugs should not have an effect on the healing process).

- General condition, nutrition, protein level, vitamins B, C and K, and trace elements (Zn and Mg) (malnutrition slows down the healing process).
- Diabetes mellitus: There is a risk of infection, dysfunction of the micro- and macrocirculation, and hyperglycemia = chronic wounds.
- Icterus and anemia.
- Bacterial/other infections: Bacterial contamination slows down the healing process.
- Age: The older the patient, the slower the wound heals.
- The location of the wound: Poorly vascularized areas or areas under tension heal more slowly than areas that are highly vascularized.

1.6. Classification depending on wound closure

Primary wound management was pioneered by Paul Leopold Friedrich (1898).

Primary suture: Immediate surgical wound closure can be performed within 12 h after the injury if no signs of inflammation or contamination can be detected (see below).

Delayed primary wound closure: After 3–8 days of open wound management, surgical wound closure is performed (see below).

Early secondary surgical wound closure: After 2 weeks of open wound management, surgical wound closure is performed (see below).

Late secondary surgical wound closure: After 4–6 weeks of open wound management, surgical wound closure is performed (see below).

2. Surgical wounds

2.1. Determinants of healing of surgical wounds

- Preparation of the operating site, hygiene, shaving, disinfection and isolation.
- The incision should be parallel to the *Langer* lines. The skin is stretched, the scalpel is held in a vertical position and the incision is performed until the sc. layer is reached.
- It is important to be aware of the anatomical aspects of the involved area. The muscle is separated along its fascia, the handling of bleeding is of importance, etc.

2.2. Skin incision

- A skin incision is made on a prepared (cleansed, draped) operative field.
- During the incision, the surgeon and the assistant stretch the skin with sterile towels on both sides of the operative field.
- Usually a scalpel (e.g. #20 blade, #4 handle) is used. The type of the scalpel depends on the site of the incision.
- The manner of holding the scalpel varies according to the use.
    - For the delicate, curved incision of fine structures, the scalpel is held like a pen.



    - For a long straight incision, the scalpel is held like a fiddle bow.



2.3. The requirements of skin incision

- The length of the incision should be appropriate for safe surgery.
- Vessels and nerves should not be damaged.
- The skin edges should be smooth.
- The incision is made perpendicularly to the skin with a single definite cut (failed attempts result in ragged edges and prevent wound healing).

- The direction of the incision depends on the location of the organ being operated on.
- The skin is incised parallel to the *Langer* lines (better wound healing and less scar formation), usually toward the operator, and from left to right.
- The depth of the incision must be the same throughout the whole length. At the beginning, the tip of the scalpel is inserted perpendicularly into the skin, the cut is made an angle of 45° with the blade of the scalpel (not with the tip!), and the incision is completed with the scalpel held perpendicularly.
- The skin scalpel is discarded into the container after the skin incision. In the deeper layers, another scalpel is used.

2.4. Main types of skin incisions

(See details later, on page 93)

- *Kocher*'s transverse incision at the base of the neck (thyroid gland), sternotomy, thoracotomy.
- Subcostal (gallbladder or spleen), median/paramedian laparotomy (this may be upper or lower relative to the umbilicus).
- Transrectal/pararectal/transversal laparotomies.
- *Pfannenstiel* suprapubic incision (bladder, uterus or ovaries).
- *McBurney* incision (appendectomy).
- Inguinal incisions (hernia).

2.5. Closure of surgical wounds

- Fascia and subcutaneous layer: Interrupted stitches. The fat must not be sutured (fat necrosis).
- Skin: Tissue-sparing technique, with accurate approximation of the skin edges. Tension and ischemia of the skin edges are to be avoided. A simple interrupted stitch is the most fundamental type in cutaneous surgery (other possibilities: *Donati* vertical mattress suture, *Allgöwer*, continuous intracutaneous, etc.; *Steri-Strips*, clamps and tissue glues may be applied).
- Dressing: Sterile, moist, antibiotic and non-adhesive dressings. Gauze placed directly on the wound makes dressing removal difficult and painful: tearing of the closure is possible.
- Holding the dressing: Stretchable adhesive tape, such as Hypafix.
- The dressing is removed on the 2nd postoperative day, and daily in cases of infection.
- Sutures are usually removed after 4–6 days. In areas of good blood supply, such as the face, it is after 5–7 days, and in the trunk and extremities after 10–14 days.

3. Early complications of wound closure

(See also sections I.4 and V.7.2.2.2)

- Hematoma
- Seroma
- Wound infection (see also SSI). Therapy in general:
  - The type of surgery (clean, clean/contaminated, contaminated or dirty) will determine the level of the risk of infection and the likely spectrum of pathogens. Empirical antibiotic therapy should be primarily directed against Staphylococcus aureus.
  - Swabs are commonly sent for culture; pus (if available) is a better sample. Other fluids or tissue biopsy samples may also be cultured. Blood culturing is recommended in febrile patients.
  - If wounds are not grossly infected, they may respond to local measures such as the removal of sutures. Frequent saline bathing should be undertaken and the wound requires a drain to allow healing. Deep-seated infection may require broad-spectrum antibiotics and possible surgical intervention.

Superficial SSI

1. Diffuse and superficial (e.g. erysipelas). Streptococcus haemolyticus-induced lymphangitis, linear, diffuse subcutaneous inflammation. *Treatment:* Rest, antibiotics and dermatology consultation.
2. Localized (e.g. abscess, stitch abscess, *filum suppuratio*). This can occur anywhere: under the skin, between the muscles, subfascially, in the chest, brain or liver. *Therapy:* Radical surgery and drainage. In the presence of dead tissue, the most critical aspect of treatment is the surgical removal of pus (Motto: “cut out the rubbish”). Antibiotics have a supportive role.
3. Foreign material *(corpus alienum)* could be present even years later (importance of X-ray examination!).

Deep SSI

1. Diffuse (e.g. anaerobic necrosis).
2. Localized (e.g. empyema) in body cavities (chest and joints). *Therapy:* Surgical exploration and drainage (Staphylococcus aureus!)

Mixed SSI

1. Gangrene: Necrotic tissues with putrid and anaerobic infection; this is a highly lethal, severe state. The terms gas gangrene and clostridial myonecrosis are used interchangeably and refer to the infection of muscle tissue by toxin-producing clostridia. *Therapy:* A combination of aggressive surgical debridement and effective antibiotic therapy is the determining factor.
2. Generalized reaction: Bacteremia, pyemia and sepsis.

4. Late complications of wound closure

- Scar formation at the penetration site
- Hypertrophic scar
- Keloid
- Necrosis and inflammatory infiltration
- Abscess containing foreign materials.

5. Prevention of wound infection

- Basic general surgical education
- Thorough examination and preparation before surgery
- Compliance with asepsis
- "Fast" decisions and optimal exposure
- Atraumatic techniques
- Correct handling of bleeding.

6. Signs of wound infections

Inflammatory signs are classical (*functio laesa* by Virchow (1858) and *rubor et tumor cum calore et dolore*). *General therapy*: Rest and steam bandage if necessary. In the event of aggravation of the symptoms, wound exploration is performed under local anesthesia, with surgical removal of pus, necrotic tissues or foreign material, daily rinsing with 3% H_2O_2 solution (or with antiseptics, povidone-iodine: Betadine, Braunol), open wound management and daily wound toilette.

7. Phases of wound healing

Hemostasis–inflammation (days 0-2)

Signs of inflammation (heat, pain, redness, and swelling) are present. The wound fills with blood clot and thrombocyte aggregates, and fibrin production develops. The blood flow is increased, and macrophage and leukocyte mediators are released. A chemical gradient develops, with the removal of nonvital cellular material and bacterial components (see Figs A–D).

Granulation–proliferation (days 3-7)

Characterized by the formation of granulation tissue: Fibroblasts, inflammatory cells, new capillaries embedded in a loose extracellular matrix (ECM) (angiogenesis) of collagen, fibronectin (modeling the ECM) and hyaluronic acid, providing a good basis for re-epithelialization. The healthy sprout is red and does not bleed.

Injury



Hemostasis



Early inflammation



Late inflammation





Remodeling (lasting for months from day 8)

(A) Maturation = ECM remodeling, and continuous collagen deposition. The scar is characterized by intensive strand formation; the vascularity is reduced and becomes brighter. The ECM is loose and relatively weak (20% of the final strength after 3 weeks).

(B) The fibers contract and become smaller and stronger. This contraction can cause reduced of joint functions. This is pronounced for a year, but remodeling continues for an indefinite time.

(C) The final strength of the wound is around 70-80% of that of uninjured tissue.



8. Wound healing disorders

Keloids

- These are of unknown etiology; they resemble benign tumors, and affect mostly African and Asian populations.
- They have well-defined edges, with pinkish-brown, emerging, tough structures, which result from the sc. proliferation.
- They particularly affect scars on the pre-sternal and deltoid areas and ears.
- They do not cause any pain, but constantly develops.
- Treatment: Intralesional corticosteroid injections, cryosurgery, excision, radiation therapy, laser therapy and interferon therapy. Prevention with an atraumatic technique.

Hypertrophic scars

- These develop in areas of thick chorium.
- They are composed of non-hyalinic collagen fibers and fibroblasts.
- They are confined to the incision line.
- Treatment: They regress spontaneously, starting 12–18 months after surgery, and fall back to the level of the skin in 1–2 years.



Keloid



Hypertrophic scar

9. Wound management of accidental wounds

- All accidental (not surgical) wounds should be regarded as infected. Accordingly the causative agents and the devitalized tissues should be removed.
- An accidental wound should be transformed into a surgical wound.

> I had to figure a lot of this out myself. When I heard "transfer your consciousness to the next life" I decided I had to learn how to do this in this lifetime. I kept asking, but everyone had a different answer. They just said it's very simple. I told one master I'd give him anything for the secret; I'd go anywhere to learn. Either he didn't have it or else he wouldn't give it to me. After a while I discovered that I'd have to figure out myself how to transfer whatever I wanted to the Energy Body. I did this because I understood that my Energy Body will live forever.

Focusing on intellectual understanding alone is limiting and stifling. A real practice teaches one how to feel within and derive authentic knowledge based on personal experience. In the Universal Tao, we emphasize the practice of understanding nature, getting in touch with the natural forces, and getting in touch with oneself. Then the principles of philosophy will reveal themselves, and one can have real hope based on what is, not on empty promises that can never be proven.

PHASES	MANAGEMENT
Inspection	Under sterile circumstances (cap, mask and gloves)
Anamnesis	▪ Elucidation of the circumstances of the injury. When did it occur? The earlier the wound is managed, the lower the possibility of infection. Is the patient suffering from diseases associated with a poorer tendency to heal (diabetes)? Clarification of the circumstances of the injury helps the assessment of the danger of infection. ▪ The validity of tetanus vaccination should be clarified. In the presence of spoiled wounds, at least vaccination with anti-tetanus immunoglobulin is recommended. Vaccination and its registration are performed at the corresponding traumatology department. ▪ Prophylaxis of rabies in the event of bitten wounds: Vaccination with Rabipur on days 0, 3, 7, 14, 30 and 90)
Diagnostic procedures	▪ Exclusion of accompanying injury ▪ Examinations of circulatory, sensitivity and motor functions ▪ Exclusion of bone fractures by X-ray examination
Wound management	▪ Surgical wounds should be handled by the procedures described in the chapter focusing on suture types. ▪ Accidental wounds should be managed on the basis of the depth of the injury and the danger of infection, with primary or delayed wound closure (see Table below).

Types of wound management

Temporary wound management (first aid)	Aim: Prevention of secondary infection	▪ Cleansing ▪ Handling of bleeding ▪ Covering
Definite primary wound management	Surgical wound closure is performed if the injury is less than 12 h old.	▪ Cleansing ▪ Anesthesia ▪ Excision (< 6–8 h, except face and hands) ▪ Sutures (puncture, bite, shot and bruised wounds: situating sutures* + drain)
Primary wound closure is always performed	Penetrating injuries of ▪ the abdomen ▪ the chest ▪ the dura mater	
Primary wound management is contraindicated:	In the cases below, after wound cleansing, the wound is covered with saline and a surgical covering, held in rest, and delayed sutures are placed after 4-6 days in the presence of: ▪ infectious signs ▪ severe contamination ▪ an incompletely removed foreign body ▪ pouched, greatly bruised wounds ▪ special injuries in certain professions: surgeons, butchers, veterinarians, pathologists and bacteriologists ▪ bite, shot or deep incised wounds	▪ Cleansing ▪ Covering ▪ Primary delayed suturing (3–8 days)
Never perform primary wound closure (except in cases of skull, chest and abdominal penetrating injuries)	War casualties ▪ Hostility wounds should always be regarded as infected with aerobic or aerobic bacteria ▪ The reaction time of the wounded person is prolonged ▪ The circumstances of wound management are poor	Alternatives: ▪ Primary delayed suturing (3–8 days) ▪ Approximation of wound edges with tapes, and later sutures ▪ Situating suturing * + drain ▪ Early secondary wound closure (> 14 days) ▪ Late secondary wound closure (4-6 weeks) ▪ Plastic surgery solutions later.
Primary delayed suture	If no signs of infection occur within 4–6 days, suturing (or also situating suturing*) is performed after excision of the wound edges, those are sutured	3–8 days later: ▪ Anesthesia ▪ Excision (refreshment of the wound edges) ▪ Suturing
Early secondary wound closure	In the event of wound inflammation and necrosis, but healing proceeded with proliferation, the wound edges should be refreshed and closed by suturing.	2 weeks after the injury: ▪ Anesthesia ▪ Excision (refreshment of the wound edges) ▪ Suturing ▪ Draining
Late secondary wound closure	The proliferating former wound parts and scars were first excised. With greater defects, plastic surgery solutions should also be considered.	4–6 weeks after the injury: ▪ Anesthesia ▪ Excision (of the secondarily healing scar) ▪ Suturing ▪ Draining

**Situating suturing* is performed at the time of the primary management, but the distance between the stitches is ~ 2–3 times that in primary surgical wound closure.

Management of accidental wound types

Severity/ depth of injury	Conservative/ surgical management	Cleansing, disinfection	Wound management, covering, bandaging
Bruised, not pyodermic superficial injury) (“excoriation”)	Needs conservative management	Cleansing with Betadine solution, removal of foreign bodies	Treatment with mercurochrome solution. After drying, sterile bandaging (mull-sheet, then mull strip or elastic net). Open wound management can also be considered
Bruised, pyogenic injury (“excoriation”)	Conservative management is followed by surgical wound closure	Cleansing with H_2O_2 solution, rinsing with saline	Disinfection with Betadine solution, sterile bandage. Open wound management and later secondary surgical closure
Deeper penetrating mechanical injury (vulnus scissum and vulnus caesum)	Requires surgical wound closure	Cleansing with Betadine solution	Handling of bleeding, cleansing, excision of bruised edges, open wound management, sterile bandaging. The wound is later closed secondarily
Deeper blunt mechanical injury (vulnus contusum)	Requires surgical wound closure	Cleansing with Betadine solution	Cleansing, excision of bruised tissues, open wound management, sterile bandaging. The wound is later closed secondarily. Transplantation may be necessary
Bite wound (vulnus morsum)	Requires surgical wound closure, but primary wound closure is forbidden (except the face)!	Cleansing with Betadine solution	Cleansing, excision of bruised edges, open wound management, sterile bandaging. The wound is later closed secondarily. Rabies prophylaxis!
Puncture and shot wounds (vulnus punctum et sclopetarium)	Require surgical wound closure	Cleansing with Betadine solution, probing of the penetrating route, removal of foreign bodies.	Cleansing, open wound management, sterile bandaging. The wound is later closed secondarily. Antibiotic prophylaxis in special cases!
Inflamed wounds (war injuries, wounds contaminated with soil, foreign bodies, if wound edges are irregular, poor immunological status)	Combined conservative and surgical management for days, then surgical wound closure	Steam bandage, keeping in rest. If inflammatory signs accelerate: ■ Surgical exposure under anesthesia ■ The wound is opened and the excretion, necrotic tissue and foreign bodies are removed ■ Cleansing with H_2O_2 solution, rinsing with saline (or with antiseptic, Betadine, Braunol solutions, possibly diluted with saline, and intermittent flushing/ suctioning of the wound) (or disinfection with Octenisept, which does not irritate) (or soaking with Neomagnol on the limbs) ■ Open wound management with daily cleansing ■ Bacteriological sampling from the wound	■ Open wound management until completion of the inflammatory process, daily wound cleansing, sterile bandaging ■ Tranquillization of the inflamed skin (Burow ointment, ice, zinc-aluminum-containing pharmacy products) ■ For epithelization: Mercurochrome treatment, Sol. Merbromi, Mikulitz ointment, Dermasin ointment, Bepanten, Neogranormon, Actovegin 20% creams ■ Deodoration (alginate and carbon-containing bandages e.g. Kaltostat, Melgisorb, etc.) ■ Purification (fibrinolysis with Fibrolan, Iruxol mono, Mesalt, etc.) ■ Incision instead of antibiotics or Friedrich wound excision, drainage if necessary, complying with asepsis criteria.

The schemes of excision







Solutions, ointments

H_2O_2	A 3% solution which removes necrotic tissues. Bubbling can be observed on the surface when necrotic parts are present. It is allowed to act on the wound for some minutes, and then rinsed thoroughly with saline.
Betadine, Braunol solutions	Iodine-containing disinfecting solutions which (in contrast with iodine tincture) can come into direct contact with the wound.
Octenisept solution	A non-irritating disinfecting solution.
Mercurochrome tincture	A pharmacy product comprising excellent treatment for superficial wounds. Accelerates epithelization.
Vaseline ointment	Prevents adhesion formation between the wound and the bandage.
Betadine ointment	Prevents infection and also adhesion formation between the wound and the bandage.
Neogranormon ointment	Accelerates epithelization; particularly applicable in superficial erosions and sloughs.
Burow ointment	Applicable under steam bandages; facilitates the exhaustion of purulent material.
Fibrolan, Iruxol mono, Mesalt ointment	Fibrinolytic enzyme-containing substances which facilitate epithelization. Applicable to areas near ulcers, stomas and fistulas.

10. Dressing – bandaging

Definition: Bandages are stringy materials which protect injured body parts. An ideal wound dressing:

- maintains a moist environment at the wound interface,
- removes excess exudate without allowing 'strike-through' to the surface,
- provides thermal insulation and mechanical protection,
- acts as a barrier to micro-organisms,
- allows gaseous exchange,
- is not adherent and is easily removed without trauma,
- leaves no foreign particles in the wound,
- is nontoxic, nonallergenic and nonsensitizing.
- However, there is no single dressing that is appropriate for all wound types and all stages of healing.

10.1. Types of bandages

- Foils and film bandages (e.g. Tegaderm and Op-site)
- Polymer bandages
- Foam sponges and foam bandages
- Hydrocolloids (pectin, gelatin and carboxy-methyl-cellulose, e.g. Urgotul)
- Hydrogels (starch and polyacrylamide (94% water)
- Alginates (from marine algae)
- Island bandages
- Absorbent wound pillows
- Impregnated gauze sheets
- Mullsheets and mullbandages
- Flexible, tube-net bandages
- Wound approximators (strips)
- Fixing bandages
- Cotton

10.2. Layers of bandages

- The layer in direct contact with the wound (sterile, hypoallergenic, and not irritating); it is a simple sheet (e.g. mull sheet: a good fluid absorbent, but easily sticks to the wound).
- An impregnated sheet (Vaseline, paraffin, e.g. "Jelonet", but there are also sheets impregnated with antiseptic materials). It does not stick to the wound and protects it from drying-out. There are also sheets impregnated with saline which melt when they come into contact with body fluids and help cleaning of the wound, e.g. Mesalt.
- An absorbent layer (to absorb and store blood and excretions).
- A fixing layer to secure the bandage (adherent tapes, e.g. Centerplast, Leukoplast, Mefix or Mepore, the latter two for larger surfaces).

10.3. Types of bandages

Adherent/taped bandages
These are used to fix covering bandages or for the approximation of the edges of small wounds. Conditions of application: they should stick well to the skin surface and be hypoallergenic. There are self-adherent types with a surface in the middle ready to contact the wound. They should be permeable to air and good fluid absorbents.

Covering bandages
These are used to protect the wound and absorb secretion. They should be non-sticking, good fluid absorbents and well permeable to air. The bandage protects the wound from secondary infection and mechanical forces. Absorption of the secretion is very important, because this protects the skin from the irritation caused by soaking in body fluids, which also predisposes to infections. When a great amount of secretion is dried in the bandage, it compresses the neighboring skin, causing further injury.

The frequency of bandage changing depends on the fluid produced in the wound. During these procedures, the healing process is also checked. Swollen, painful, red skin indicates infection.

The bandage can be produced from natural fibers (cotton or silk), or from semi-synthetic, synthetic or synthetic materials. The advantage of natural fibers is the good fluid absorbent capacity, but they easily stick into the wound. Synthetic materials have the opposite features.

Primarily closed wounds are protected with sterile covering bandages for 2–3 days. If there is a sign of secondary bleeding or infection, earlier changing is necessary. Unnecessarily frequent changing facilitates infection. After the 5th postoperative day, a problem-free operative field can be left uncovered.

For larger traumatic areas or burn injuries, multi-layered poly-urethane sheets are applicable (e.g. Epigard). These are good fluid absorbents that are well permeable to air and provide ideal circumstances for skin transplantation.

Pressing bandages
These are for the temporary handling of capillary and venous bleeding under 40–60 mmHg.

Wedging bandages
These are used for temporary handling of capillary arterial and venous bleeding in order to prevent great blood loss before the final surgical intervention. The wound is covered by a sheet, and a gauze sponge ball is then placed on the source of the bleeding and fixed with a relatively tight bandage. The compression force must not exceed the arterial BP. The tourniquet can cause an inadequate blood supply, and it should therefore be relieved every 2 h.

Compressing bandages
These are used to prevent postoperative bleeding in the limbs, for the prophylaxis of thrombosis and for the reduction of chronic lymphedema.
They can consist of different materials:

- mull strip, which has the disadvantage of crease formation, as it is not elastic,
- elastic strip,
- synthetic, self-adherent strip,
- elastic socks.

Window or crease formation should be prevented, because these can cause circulatory disorders. The upper limbs are more endangered, because the tissues are finer, and the vessels and nerves are more superficial. Nerve injuries caused by compression (neuropraxy) and circulatory disorders (*Volkmann* contracture and *Sudeck* dystrophy) can develop. The compressing bandage should always be started distally so as to prevent venous stasis. Circumferential application is forbidden because of the danger of strangulation!

Special compressing bandages

Ear bandages
Special bandaging of the extremities. They have the advantages of stability and non-creasing. They are applied from distal to proximal (see Figure).



Ear bandage

Esmarch tourniqet

Maximal compression is elicited by using a 10-cm rubber band to stop arterial bleeding from the limbs. The duration of application should not be longer than 2 h.

Fixing/retention bandages

These are used to immobilize the injured body part or to fix the reposition. The material used should be light and be worn with minimal strain. They can be made of elastic strip, cast, plastic or metal rails, or pneumatic rails, or cotton-embedded tubes (rucksack bandage or *Charnley* loop).

Special fixing/retention bandages

(see traumatology for details)

Schanz collar

This is used to immobilize the vertebras. Its material is special: an 8-15-cm-wide, 1.5-cm-thick, 50-cm-long padded strip. It can also be made of a cotton-embedded elastic band. It should be placed loosely so as to prevent movement of the jugular vertebras.

Desault bandage

This is used to immobilize the shoulder and elbow. It can be made of a cotton-embedded elastic band or a textile net. The skin should first be talc-powdered to protect from perspiration. The injured arm (with the elbow flexed) is fixed to the trunk with circumferentially positioned bands. The bandage assumes an “8” shape around the chest, connecting the shoulder to the injured arm.



Desault bandage

Gilchrist bandage

This is used to immobilize the shoulder and elbow. Hanging the arm over the neck toward the back prevents movements of the shoulder and elbow (see Figure).



Gilchrist-bandage

Rucksack bandage

This serves for repositioning and immobilization of the clavicle. It can be made of a cotton-embedded elastic band. The route is the same as that of the straps of a rucksack. The radial pulse and the venous perfusion should be frequently checked. This bandage should be checked and adjusted on a daily basis.



Rucksack bandage

Charnley loop

This is used to fix the elbow in cases of infant supracondylar humerus fractures. After repositioning, the elbow junction should be fixed at a sharp angle elicited by support of the arm around the neck. The radial pulse should be checked.



Charnley loop

Triangular scarf bandage

This is used to fix the areas of the shoulder and arm upon injury. The arm is placed into a triangular scarf and the corners are tightened behind the neck.

Sling bandage
This is applied to stop bleeding of the nose. A compressing bandage made of a gauze sponge is placed on the nose and tightened behind the head by using a mull band.

Cast bandages (see traumatology manuals for details).

11. Innovations in wound treatment

11.1. *Lucilia sericata, Phaenicia sericata* (greenbottles)

These 2-mm sterile fly larvae are available in a „biobag". The larvae ingest bacteria which are destroyed in their gut (e.g. methicillin-resistant *Staphylococcus aureus*). *Advantages:* they can be applied to a wide range of infected wounds to remove slough and malodor. *Associated problems:* Potentially infected larvae, allergic reactions, tickling sensation, and ethical and aesthetic issues.

"Scat. orig."



Larva Lucilii

11.2. *Vacuum-assisted closure* therapy

This involves negative-pressure suction drainage. It is not a brand-new idea as drainage methods were earlier employed for decades; the fundamental difference is the application of topical negative sub-atmospheric pressure across the surface of the wound. *Advantages:* It provides a moist environment, prevents bacterial activity, evacuates excess exudate, kills anaerobic bacteria in the wound bed, and controls odor. *Contraindications:* Fistulas of unknown origin, opening into a body cavity, vulnerable body organs, malignancy, necrotic tissue with scar, and untreated osteomyelitis.



11.3. Biological dressings

11.3.1. Human skin

- Autologous (epidermal sheets, semi- and full-thickness skin)
- Allogenous (living donor, cadaver skin, amnion membrane)

11.3.2. Xenogenous skin

- Porcine skin (full-thickness skin, semi-thickness skin, subcuticular sheets)

11.3.3. Skin supplements

- Synthetic bilaminates (membranes, gels, foams and spray products)
- Collagen-based composites
- Collagen-based dermo-analogs
- Natural tissues (de-epithelized allografts)
- Dermal sheets (human, allogenous)
- Cryopreserved human and allogenic cadaver skin

11.3.4. Biosynthetic materials (cultured tissues)

- Keratinocyte suspensions and sheets (autologous and allogenic)
- Fibroblast-containing dermo-analogs
- Skin replacement composites and allograft keratinocytes
- Skin composites, autologs, and fibroblast-GAG-keratinocytes
- Artificial skin

11.4. "Wet wound healing"

- This protects the wound from drying-out
- Increased effects of local growth factors, cytokines, etc.
- Increased proteolysis
- Increased angiogenesis
- Decreased pH
- Decreased bacterial proliferation
- Increased phagocyte and neutrophil activity
- Increased fibroblast and endothelial proliferation
- Increased keratinocyte migration and proliferation

Surgical Techniques, 2

Advanced Medical Skills

Preface

The second part of "*Surgical Techniques*" is the subject-matter of the "*Advanced Medical Skills*" course. In these modules, the Institute of Surgical Research introduces surgical principles and techniques, and advanced interventions such as surgical operations, e.g. laparotomy, appendectomy, intestinal resection, bowel anastomosis, thoracocentesis and thoracotomy, to interested students. These procedures are taught in simulated real-life, clinical surroundings and circumstances.

This curricular structure is used to teach and update scientific and medical findings relevant to surgical practice, to enhance clinical reasoning and decision-making, and to provide individual feedback and career advice. Typical future careers of participants of this course include surgery and surgical specialties, such as gynecology, head and neck surgery, neurosurgery, oncology, ophthalmology, orthopedics, plastic surgery, thoracic surgery, urology, vascular surgery, anesthesiology, emergency medicine, critical care and cardiology.

The goals are to foster skills-based decision-making, and to broaden the correlation of physiology, anatomy and pharmacology to acute clinical care. Emphasis is placed on procedures, critical thinking and the assessment of skills, in order to develop the knowledge and skills to support a career choice in those specialties in which expertise in surgical anatomy is critical.

I. Laparotomy

"We took out fifteen pounds of a dirty, gelatinous looking substance. After which we cut through the fallopian tube, and extracted the sac, which weighed seven pounds and one half… In five days I visited her, and much to my astonishment found her making up her bed."
(McDowell E. Three cases of extirpation of diseased ovaria. Eclectic Repertory Anal Rev. 1817; 7:242–244.)

Terms and definitions
Laparo or lapar (Greek: λαπαρα, λαπαροσ) means the soft part of the body between the ribs and the hip; it denotes the flank or loins and the abdominal wall. This term is sometimes used loosely (and incorrectly) in reference to the abdomen in general. Laparotomy therefore means a surgical incision through the flank; less correctly, but more generally, it is an abdominal section at any point to gain access to the peritoneal cavity.

1. History of abdominal surgery

1809 On Christmas morning, Dr. Ephraim McDowell (1771–1830) in Danville (Kentucky, USA) successfully removed an ovarian tumor from Mrs. Crawford without anesthetic or antisepsis. The risk of fatal infection was very high – the operation was bitterly criticized.

1879 Jules Émile Péan (1830–1898) opened the abdomen of a patient with cancer of the pylorus. The diseased section was cut out; the remainder was sewn to the duodenum. The patient died 5 days later.

1880 Ludwig Rydyger (1850–1920) carried out the same procedure, but it had been planned in advance; the patient died within 12 hr, of "exhaustion."

1881 Christian Albert Theodor Billroth (1829–1894) performed a successful operation (the patient died 4 months later due to the propagation of the tumor). Two other, fatal operations followed: Billroth was stoned on the streets of Vienna.



1885 Billroth II (pylorus cc): Successful operations were achieved.

Today, emergency admissions account for 50% of the general surgical work load and abdominal pain is the leading cause of 50% of emergency admissions. It should be noted that 70% of the diagnoses can be made on the basis of the history alone, and 90% of the diagnoses can be established if the history is supplemented by physical examination. The expensive and complicated diagnostic tests and instrumental procedures often (> 50%) merely confirm the results of the anamnesis and physical examination (!).

Abdominal pain is frequently (35%) 'aspecific'; it can be caused by viral infections, bacterial gastroenteritis, helminths, irritable bowel syndrome, gynecological diseases, psychosomatic pain, abdominal wall pain, iatrogenic peripheral nerve lesion, hernias or radiculopathy. The frequency of acute appendicitis and ileus is 15–17%; they are followed in frequency by urological diseases (6%), cholelithiasis (5%) and colon diverticulum (4%). The frequency of abdominal traumas, malignant diseases, peptic ulcer perforation and pancreatitis is 2–3%, while that of rupture of an aorta aneurysm, inflammatory bowel disease, gastroenteritis and mesenteric ischemia is < 1%.

2. Technical background of laparotomies

- Abdominal incisions are based on anatomical principles.
- They must allow adequate access to the abdomen. They should be capable of being extended if required.
- Ideally, muscle fibers should be split rather than cut; nerves should not be divided.
- The rectus muscle has a segmental nerve supply. It can be cut transversally without weakening a denervated segment. Above the umbilicus, tendinous intersections prevent retraction of the muscle.

3. Basic principles determining the type of laparotomy

- The disease process
- The body habitus
- The operative exposure and simplicity
- Previous scars and cosmetic factors
- The need for quick entry into the abdominal cavity

Bibliography

Beinfield, Harriet, L Ac and Efrem Korngold L Ac, *Between Heaven and Earth,* NY: Ballantine Books, 1991.

Grazzaniga, Michael S, *Nature's Mind*, NY: Basic Books, 1992.

Grings, William and Michael Dawson, *Emotions and Bodily Responses: A Psychophysiological Approach*, New York Academic Press. 1978.

Haas, Elson, MD, *Staying Healthy With the Seasons*, Berkeley, CA: Celestial Arts, 1981.

Hammer, Leon, MD, *Dragon Rises, Red Bird Flies*, Barrytown, NY: Station Hill Press, 1990.

Herrmann, Ned, "How the Brain Works...and how to help it work better", *Bottom Line Personal*, November 15, 1992. p 9-10.

Locke, Steven MD, "*How To Use Your Mind To Improve Your Health", Bottom Line Personal*, August 30, 1992. p 11-12.

Melchizedek, Drunvalo, *Ancient Secret of the Flower Life* Vol. I & II, Light Technology Publishing, 1998 & 2000.

Porush, David, "*Finding God in the Three Pound Universe: The Neuroscience of Transcendence*", *Omni*. October, 1993. p 60-70.

Wagner, Bruce, "*You Only Live Twice*", *Details*, March, 1994, p.166-171, 213-319.

Tortora, Gerard J. and Sandra Rey, *Introduction to the Human Body*, Fifth Edition, NY: John Wiley & Sons, Inc., 2001.

Tortora, Gerard J. and Sandra Rey, *Tortora Grabowski*, Ninth Edition, NY: McGraw-Hill, 1999.

4. Recapitulation: Anatomy of the abdominal wall



From left to right: 1. the linea alba; 2. the linea semilunaris; 3. the lig. arcuatum; and 4. the abdominal projection of the lig. inguinale. During laparotomy, different anatomic structures are cut in the upper or lower abdominal regions at various distances from the midline (anterior vs lateral regions). During a midline incision, the following tissue layers and structures are divided:

- the skin,
- the superficial fascia (*Camper's*),
- the deep fascia (*Scarpa's*),
- the anterior rectus sheath,
- the rectus abdominis muscle
- the posterior rectus sheath down to arcuate line,
- the transversal fascia,
- the extraperitoneal connective tissue,
- the peritoneum.

Recapitulation: Important things about nerves
- Transverse incision is least likely to injure nerves.
- The iliohypogastric (ih) and ilioinguinal (ii) nerves are sensory:
  - ih injury leads to a loss of sensation in the skin over the mons;
  - ii injury leads to a loss of sensation in the labia majora.
- Both ih and ii nerves supply the lower fibers of the internal oblique and transverses; if divided, these fibers undergo denervation, which can increase the risk of inguinal hernia.

5. Principles of healing of laparotomy

- Patient risk factors that negatively affect wound healing:
  - Diabetes and obesity
  - Poor nutrition
  - Prior radiation or chemotherapy
  - Age
  - Alcohol
  - Ascites and malignancy
  - Immunosuppression
  - Coughing, retching

- Hospital factors that affect wound healing negatively
  - Long operations
  - Along period of hospitalization preoperatively
  - Drains through incision
  - Shaving prior to surgery
  - Type of suture
  - Closure technique

6. Prevention of wound complications

- The scalpels should not be the same for the skin and deep incisions.
- A scalpel should be used to cut skin and fascia and not diathermy; the infection rate after diathermy is twice as high.
- Deep sc. sutures should be avoided, but absorbable synthetic material (e.g. 4.0 Dexon) may be used subcutaneously to decrease tension on the skin.
- Use of catgut (for fascia or sc. suturing) should be avoided.
- Contaminated or dirty wounds:
  - delayed closure,
  - staples with saline-soaked gauze.
- Opening of a bacteria-containing organ:
  - delayed closure,
  - irrigation of all layers,
  - monofilament, nonabsorbable suture,
  - systemic antibiotics 30 min before operation or as soon as possible, and repeat in a prolonged case.

II. Incisions

The term *incision* originates from the Latin (in + cidere → incisio). An incision can be longitudinal, oblique or transverse. The most important types are demonstrated in association with abdominal operations; the principles are identical in the other body regions (extremities, chest, neck, etc.).

1. Longitudinal incisions



1. Midline; 2. supraumbilical (upper midline); 3. infraumbilical (lower midline); 4. right paramedian; 5. *McEvedy* preperitoneal approach for inguinal and femoral hernia repair (*McEvedy PG: Femoral hernia. Ann R Coll Surg Engl, 1950)*.

1.1. Characteristics of longitudinal incisions

Median incision

- This was the commonest abdominal intervention before the era of minimally invasive surgery. The umbilicus and the falciform ligament above the umbilicus should not be incised. Meticulous, careful handling of bleeding is necessary in the superficial layers before the peritoneum is opened. The urinary bladder can be reached through the *Retzius* space (spatium retropubicum Retzii); if there has previously been an operation in this field, a more caudal entry is necessary (the chance of scar formation and adhesions is less).
- *Advantages*: There is excellent exposure to the abdomen and pelvis, which can easily be extended, and also rapid entry into the abdominal cavity; the midline is the least hemorrhagic incision, and is easy to perform; the linea alba is the guide to the midline.
- *Disadvantages:* The scar may be wide and not beautiful, with a possible increase in hernias and dehiscence with the midline.

Paramedian incision

- The site is parallel to and ~ 3 cm from the midline. The following structures are divided: skin – anterior rectus sheath (the m. rectus is retracted laterally) – posterior rectus sheath (above the arcuate line) – transversalis fascia – extraperitoneal fat – peritoneum. Closure is performed in layers.
- *Indication:* If excellent exposure is needed to one side of the abdomen or pelvis.
- *Advantages:* A lower incidence of incisional hernias.
- *Disadvantages:* It takes longer to make and close this incision, there is an increased risk of infection, and intraoperative bleeding, and a risk of nerve damage; if sited beside the midline, and it can compromise the blood supply in the middle.

2. Oblique incisions



(1). *Kocher* incision for cholecystectomy (sec. Theodor Kocher (1841–1917), Nobel Prize for medicine and physiology in 1909, mainly for thyroid surgery); (2). *McBurney* incision for appendectomy (after Charles McBurney (1845–1913), who performed his first operation for appendicitis in 1897); (3). left inguinal; (4). thoraco-abdominal

2.1. The basic type of oblique incisions

- *Indications* for *McBurney* muscle-splitting incision (see later): Appendicitis, pelvic abscess and extraperitoneal drainage.

3. Transverse incisions



1. *Gable incision*, 2. transverse muscle splitting, 3. *Lanz* incision, 4. *Maylard* incision, 5. *Pfannenstie*l incision, 6. *Cherney* incision

3.1. Basic characteristics of transverse incisions

- *Advantages:* These incisions give the best cosmetic results, they give a much stronger scar than midline incisions and less painful than longitudinal incisions, and there is less interference with respiration. There is no difference in dehiscence rate.
- *Disadvantages:* They are more time-consuming, and more hemorrhagic; nerves are sometimes divided, spaces are opened and there is a potential for hematomas; upper abdominal access is limited.
- *Main types:*
  - *Pfannenstiel* incision: For gynecological indications. *Advantages:* Most wound security (in pelvic incisions), least exposure, usually 10-15 cm long. *Disadvantages*: Separates the perforating nerves and small vessels from the ant. rectus, and this may weaken the strength of the wound healing. If extended past the m. rectus, it can damage the ih and ii nerves.
  - *Maylard* incision: This gives excellent exposure to the lower pelvis; it is used for radical pelvic surgery; it is a true transverse muscle-cutting incision, 3–8 cm above the symphysis.
  - *Cherney* incision: This is like a *Pfannenstiel* incision, but divides the m. rectus at the tendinous insertion to the symphysis. It gives excellent access to the space of *Retzius*. During closure, re-attachment of muscle tendons to the rectus sheath, and not the symphysis, should be performed in order to avoid osteomyelitis.
  - *Rockey Davis (Elliot)* incision*:* This alternative to the McBurney incision, extends to the lateral border of the rectus (it was described first by JW Elliot in 1896, then by AE Rockey in 1905, and finally by GG Davis in 1906).
  - *Lanz* incision: This is a special incision at the right fossa iliaca. As compared with the *McBurney* incision, it is transverse, more medial toward the rectus, and closer to the iliac crest (spina iliaca anterior superior), and gives better cosmetic results. Due to its transverse direction, the ih and ii nerves can be damaged, and the incidence of hernia is higher. The main indication is exposure of the appendix and cecum; the mirror image (left iliac fossa) can be used for the left colon (not for the rectum).

4. Special extraperitoneal incisions for staging

- *J-shaped* incision: 3 cm medial to the iliac crest; this allows the extraperitoneal removal of para-aortic nodes; it can also be left-sided; but the right is easier.
- “*Sunrise*” incision: 6 cm above the umbilicus, permitting the extraperitoneal removal of para-aortic nodes, and allowing immediate irradiation.

III. Laparotomy in surgical training

Median laparotomy is indicated when the whole abdominal part of the gastrointestinal tract should be explored. This will be a task in the surgical techniques practicals (the following operative description is related to animal (e.g. pig) interventions, in which the steps are identical to those of human operations).

1. General rules

Anesthesia

- Method: General anesthesia.
- Equipment: Typical monitors, a respirator and a warming blanket. Insertion of a *Foley* catheter, and application of an electrodispersive pad. The anesthesiologist will insert a nasogastric tube after intubation.

Positioning

- Supine, with arms on armboards.
- Special considerations: High-risk areas (for geriatric patients, particular attention should be paid to the skin and joints).

Skin preparation

- Method of hair removal: Clippers or wet, with a razor.
- Anatomic perimeters: Traditionally from the nipple line across the chest from the table side to the table side to mid-thigh.
- Solution options: Betadine (povidone-iodine) or an alternative (e.g. Hibiclens in USA).

Draping/incision

- In explorations, usually 4 towels (USA: a laparotomy T-sheet) are used in the midline (but the isolation depends on the location of the lesion; it could be paramedian or oblique, etc; see above).

Supplies

- General: Blades (3) #10 and (1) #15, scissors, forceps, electric unit pencil, suction tubing, hemostats (*Péan,* all sizes), staples (optional), retractors (*Gosset*) and sutures (ample supply of free ties; sizes 2-0 and 3-0 are most common).
- Specific: Catheters, drains, etc.

2. Middle median laparotomy

- This can be applied when the diagnosis is uncertain. Its *advantages* are that a large area can be examined through a small incision and, after the abdomen has been opened, the incision can be lengthened both cranially and caudally if necessary and can be quickly closed. The *disadvantages* are that the common aponeurosis of six different strong flat abdominal muscles is cut, the statics of the abdominal wall is greatly impaired, and this predisposes to wound disruption and scar hernia often occurs.
- The first step is the scrub preparation of the operative field from the xyphoid process to the symphysis; draping should be performed as described earlier. The midline is shown by the umbilicus; two laparatomy sponges are placed, one on each side of the planned incision. Generally a short, 10–15-cm-long incision is made, partly above and partly below the umbilicus, going round the umbilicus at a distance of 1–2 cm from the left (not to injure the falciform ligament and the ligamentum teres hepatis).
- In the first phase of the operation, the skin and the sc. fat, and then the aponeurosis of the linea alba are cut. The linea alba is a line-like sheet some tenths of a mm thick below the umbilicus, while it is wider, strong and tendinous above it. The incision cuts the posterior rectus sheet, transversal fascia, preperitoneal fat and parietal peritoneum. Below the umbilicus, the arcuate linea (linea semilunaris *Douglasi*) borders the area below which there is no rectus sheet.
- After the skin incision, *Doyen* clamps are placed on the wound edges and the wound towels. The sc. fat is usually cut with a diathermy pencil; bleeding can be stopped by compression and, if necessary, by ligatures and stitches, or the preventive handling of bleeding is used. *Recapitulation:*



a. **A ligature** is applied to cuts, or bleeding vessels if the bleeding cannot be stopped by compression. Cut vessels are grasped with hemostatic clamps (*Péan* or mosquito). The position is checked by wiping off the blood.

If the grasping is not successful, a second hemostat is placed deeper. The vessel is then ligated below the clamp. After the first half-hitch has been tied, the hemostat is removed and the second half-hitch is tied.



b. **Preventive hemostasis:** The vessel to be cut is closed with two hemostats in advance. The vessel is separated between them, and the two vessel ends are then ligated separately.



c. **Suture for hemostasis:** A double, 8-form stitch is placed below the bleeding vessel, and the thread is knotted. This suture is applied if a hemostat cannot be used, e.g. in the cases of vessels that are thin-walled or lie in a fascia layer, or retract deep into the tissues.

- When the sc. connective tissues are divided, the wound edges are lifted up with two tissue forceps or clamps, and the tissues are cut transversally, layer by layer with *Mayo* scissors.



- During the blunt dissection of tissues, the closed tips of *Mayo* scissors (or *Péan,* dissector) are pushed into the tissues. The tissues are dissected by the opening of the instrument with its blunt outer edges. These steps are repeated as necessary.
- The incision is deepened until the linea alba is reached, the linea is then picked up with two tissue forceps above the umbilicus and a small incision is made between them (this can be done with *Mayo* scissors). The opening is then lengthened cranially and caudally with *Mayo* scissors while the abdominal wall is lifted up.
- If the incision is made exactly in the midline, the rectus sheet will not be opened, and the muscles will not be severed. Above the umbilicus, care should be taken not to injury the ligamentum falciforme hepatis. The thick, fatty ligament can be clamped with two *Péan* hemostats and cut between them, a better exploration being achieved in this way.
- The peritoneal cavity is isolated from the sc. layer by making a second draping. Two laparotomy sponges are placed on each side of the incision and fastened to the edges of the peritoneum with *Mikulicz* clamps on both sides.
- The abdominal wall is elevated with the surgeon's index and middle fingers or with the help of the assistant, and the incision of the linea alba is lengthened with *Mayo* scissors (or a diathermy knife) both cranially and caudally to the corners of the skin wound. During this, the peritoneum edges are fixed to the sponges with *Mikulicz* clamps.
- A *Gosset* self-retaining retractor is placed into the abdominal wound. The greater omentum or intestines should not be allowed to come between the jaws of the retractor and the abdominal wall. The abdominal organs can be moved only with warm saline-moistened laparotomy sponges.
- After median laparotomy, the following organs can be examined: 1. the greater omentum; 2. the spleen; 3. the liver, gall bladder and bile ducts; 4. the stomach; 5. the small intestine and mesenteric lymph nodes; 6. the appendix (cecum); 7. the large intestines; 8. the pancreas; 9. the adrenal glands; and 10. the kidneys.
- The abdominal wall is closed in layers. Sutures of appropriate size should be selected to close the different layers, and the wound edges should be exactly approximated. It should be checked that no foreign body has been left in the peritoneal cavity. All wound towels, sponges and instruments should be counted. During abdominal operations, sponges clamped with an instrument (a sponge-holding clamp) can be used only for wiping, and instruments are placed on the ends of laparotomy sponges.
- The *Gosset* self-retaining retractor is removed, and the laparotomy sponges isolating the peritoneal cavity are released from the *Mikulicz* clamps and removed, but the edges of the peritoneum are clamped again.
- The wound of the peritoneum is closed with a half-circle muscle needle, with a continuous running suture (in pigs with #40 linen thread). Tissue forceps can be used for the first stitch, but in most cases the wound of the peritoneum can be well explored with *Mikulicz* clamps. Suturing is usually done towards the umbilicus; the first

stitch is inserted at the cranial wound corner, but it can also be performed in the opposite direction, i.e. toward the xyphoid process. If the abdominal wall is closed in multiple layers, the first row of stitches closes the posterior rectus sheet together with the peritoneum.

- The assistant ties a knot on the short free end of the thread. He/she keeps the suture under continuous tension with his/her right hand and helps with the closing of the wound edges. When the peritoneum has been closed, only one-third of the thread is pulled through the wound and a doubled thread is left on the other side. The single and double ends of the thread are knotted and cut short.
- The anterior rectus sheet and sc. wound are closed with interrupted sutures. The skin is closed with *Donati* stitches, using a skin (1/4 or 3/8) needle and #40 linen thread. The wound is disinfected with Betadine and covered with a bandage.

3. Some important details

The principles of closing the fascia

- The fascia should be closed with the minimum number of stitches, at least 1 cm from the edges, since necrosis may occur (each stitch 1 cm from another and from the edges).
- Each stitch should be closed with the same strength; the wound edges should only be approximated (!); sewing in fat or connective tissues should be avoided (except in cases of en masse closure).
- The *Smead Jones* technique involves a “far to far, near to near” suture (en masse far stitches on both sides, then near stitches involving the fascia only). The healing tendency is theoretically good, and this technique decreases tension, but it is time-consuming and rarely used in clinical practice.



Drainage

- This may be passive or active (see earlier; the passive drain is never brought out in the line of the incision (danger of infection!).
- The most frequent indications are infection, oozing, and the need to eliminate a cavity.
- For clean wounds, the prophylactic use of drainage can be controversial; closed suction can be useful in the case of clean/contaminated wounds (especially if no antibiotics are given).

Wound irrigation

- Irrigation with physiological saline to prevent infection (motto: “*The solution to pollution is dilution*”).
- Irrigation with antiseptic solution (e.g. 1% povidone-iodine) is effective, but can be cytotoxic (e.g. fibroblasts can be damaged).

Closing the skin

- None of the methods (wound clips, suturing, etc.) is substantially better than the others.
- To cover an abdominal skin wound, Opsite, Telfa, etc. can be applied; the bandage can stay in place for 2–3 days.
- In the event of irradiation, abdominal clips should stay in the wound longer.

Special case: the obese patient

According to international standards, a subject whose body weight exceeds the ideal by 25–30% is overweight; an excess of 30–60% means that the subject is obese; in extreme obesity the body weight exceeds the ideal by 100%. The obesity is “morbid” if the weight excess is greater than 130%.

The *Pickwick syndrome* received its name after Joe, the somnolent, red-faced, fat boy character of Charles Dickens. It was given by Sir William Osler (1918): “*A remarkable phenomenon associated with excessive fat in young persons is an uncontrollable tendency to sleep like the fat boy in Pickwick.*”

Modified routine in operations on obese patients

- Extensive cleansing of the umbilicus and preoperative bath(s)
- 5000–8000 U/12 h heparin 2 h before surgery
- Elastic bandage and stockings
- Removal of abdominal hair with an electric razor only
- A very extensive scrub preparation (under skin wrinkles also), pulling the pannus caudally
- Transverse incisions should always be made far from the wet, warm fatty skin wrinkles (duplicates)
- *En masse* closure with a continuous running suture
- Drain and suction bottle over the fascia, removal 72 h later, or if the volume is < 50 mℓ/day
- Removal of wound clips after 14 days.

IV. Basic surgical procedures on the intestines. Appendectomy

Motto: "*If in doubt, take it out.*"

Open appendectomy was earlier one of the first operations of the young surgeon, but recently it is increasingly performed with minimal invasive methods (see later). The intervention is relatively simple in the majority of the cases; the consecutive steps are built on each other and illustrate the classical, well-planned and safe surgical technique. At present the urgent operation is still the only safe method of treatment of appendicitis (it must be performed even if there is only a reasonable suspicion).

1. The history of appendectomy

1521	Jacopo Berengario da Capri (1460–1530) described the *appendix* as an anatomical structure
1500s	Vidus Vidius's (Guido Guidi, 1500–1569) book of anatomy: the term *appendix* was in general use
1710	Philippe Verheyen (1648–1710) coined the term *appendix vermiformis*
1800s	"Lower abdominal pain" as a medical diagnosis
1812	A connection was found between peritonitis and necrotic appendix (John Parkinson).
1824	A connection between periappendicular inflammation and a necrotic appendix (Jean Baptiste de Louyer-Villermay)
1827	A connection between a periappendicular abscess and the appendix (François Melier)
1848	Surgical drainage of a periappendicular abscess (Henry Hancock)
1867	Several successful drainages of a periappendicular abscess (Willard Parker)
1882	Death of Leon Gambetta, Prime Minister of France. Autopsy proved a periappendicular abscess
1886	Reginald H. Fitz (pathologist) suggested that "lower abdominal pain" is "appendicitis", and proposed urgent surgery in the event of signs and symptoms
1887 April 27	George Thomas Morton performed the first successful human appendectomy: removal of a perforated appendix
1889	John B. Murphy performed a series of 100 successful appendectomies
1902	A successful operation on the British Crown Prince Edward (VII) before his coronation ceremony.

1.1. Recapitulation: relevant anatomy

- The appendix does not elongate as rapidly as the rest of the colon, thereby forming a wormlike structure. The average length is 10 cm (2–20) with inner circular and outer longitudinal (continuation of the taeniae coli) muscle layers. Submucosal lymphoid follicles enlarge (peak in 12–20 years) and then decrease in size, correlating with the incidence of appendicitis. The blood supply is from the appendicular artery (branch of the ileocolic artery).
- The location of the base is constant, whereas the position of the tip of the appendix varies: 65% retrocecal position; 30% at the brim or in the true pelvis; and 5% extraperitoneal, behind the cecum, ascending colon, or distal ileum. The location of the tip of the appendix determines early signs and symptoms.
- Even in a case of surgically verified appendicitis, the *Meckel* diverticulum should be looked for at the antimesenteric edge of the ileum, orally 40–100 cm from the appendix. Both can be considered to be developmental rudiments; their inflammation often develops simultaneously. *Meckel* diverticulum should be suspected if there is a long-lasting umbilical discharge in the anamnesis.

1.2. Open appendectomy

⚠

- An "*RLQ*" (right-lower quadrant) incision over the *McBurney* point (2/3 of the distance between the umbilicus and the anterior superior iliac spine). The incision was described by Lewis L. McArthur in June 1894, but named after Charles McBurney, who presented a case in the July 1894 issue of Annals of Surgery.



- The sc. tissue and *Scarpa* fascia are dissected until the external oblique aponeurosis is identified. This aponeurosis is divided sharply along the direction of its fibers.



- A muscle-splitting technique is then used to gain access to the peritoneum.



- The peritoneum is lifted up with two forceps or hemostats in order to avoid damage to the underlying viscera. A small incision is made in the peritoneum and, after entry to the peritoneal cavity (if a purulent fluid sample should be taken for bacteriological diagnosis), the appendix is sought out.
- Retractors are placed into the peritoneum, and the cecum is identified and partially exteriorized, using a moist gauze pad. The taenia coli is followed to the point where it converges with the other taenia, leading to the base of the appendix. The appendix is brought into the field of vision. Gentle manipulation may be required for the blunt dissection of any inflammatory adhesions.
- “Skeletization” includes cutting of the mesoappendix and ligation of the appendicular artery (this is the branch of the ileocolic artery originating from the superior mesenteric artery; if it is ligated centrally, the terminal ileum can be necrotized). The mesoappendix is cut between *Péan* hemostats in several steps (clamping–cutting–ligating), care being taken that a tissue collar should be left on the remaining proximal stump). Generally 3–0 absorbable thread is used. Finally, the appendix is completely mobilized step by step.





- The base of the appendix is crushed with a straight *Kocher* clamp (after this step, the operation cannot be regarded as “sterile”), and then ligated with a thin absorbable thread (in animals, #40 linen thread is used).



- A seromuscular, purse-string suture is placed around the stump of the appendix, using 3 or 4–0 thread, with a round-bodied serosa needle. Care should be taken as to the depth of the stitches: if they are too deep, the infected bowel content can pass into the abdominal cavity; if they are too superficial, they can be torn out.



- The appendix is clamped with a *Kocher* clamp distal to the crushed line and cut above the base tie, just below the *Kocher* clamp (the scalpel and the appendix should be thrown into the kick bucket). The stump of the appendix is disinfected with povidone-iodine and cauterized (to prevent the later secretion of mucus).



- The stump of the appendix is buried (the stump will be inverted in the lumen of the intestine), and the purse-string suture is then tied. The buried appendix stump is covered with a serosa layer with a "Z" stitch, i.e. with a zed-like serosa stitch; thin linen thread and taper needle are used (this step is not obligatory in humans).
- The cecum and appendiceal stump are then placed back into the abdomen. If free perforation is encountered, thorough irrigation of the abdomen with warm saline solution and drainage of any obvious cavity and well-developed abscesses is required.
- The peritoneum is identified, and closed with a continuous 2 or 3–0 suture. The inferior oblique muscles are re-approximated with a figure-of-eight interrupted absorbable 0 to 3–0 suture, and the external oblique fascia is closed with an interrupted 2–0 PG suture. The skin may be closed with staples or sc. sutures.
- In cases of a perforated appendicitis, the skin should be left open, with delayed primary closure on postoperative day 4 or 5.

V. Anastomoses

The origin of the word is late Latin (by Galen) and Greek (anastomoun = to provide with a mouth; ana + stoma = mouth, orifice). The basic types are side-to-side, end-to-end and end-to-side anastomoses. Anastomoses are applied not only in gastrointestinal surgery, but also in urology and vascular (etc.) surgery. However, the basis of surgical techniques can be best practised in the case of the small intestine. An important general principle is that the techniques (e.g. restoration of the anatomy) serve to restore function (!).







1. Healing of the anastomosis

The most important factors influencing the healing of the anastomosis are the good blood supply of the tissues, the lack of tension, and an adequate surgical technique, securing the appropriate approximation for the beginning of collagen formation:

- Early phase (days 0–4): There is an acute inflammatory response, but no intrinsic cohesion.
- Fibroplasia (days 3–14): Fibroblast proliferation occurs with collagen formation.
- Maturation stage (>10 days): This is the period of collagen remodeling, when the stability and strength of the anastomosis increase.

2. Causes of anastomosis insufficiency

- Distal obstruction of the lumen
- Perianastomotic hematoma, infection or sepsis
- Hypotension or hypoxia
- Icterus, uremia or diabetes
- Corticosteroids

3. The characteristics of a good technique

- The precise joining of cut tissues results in primary wound healing (per primam intentionem, *p.p.).*
- Placing the lowest possible amount of foreign material (suture) into the tissues causes the least disruption of the local circulation.

4. Complications

- Suture insufficiency
- Stricture

5. Anastomosis techniques

Traditional methods

- Suturing by hand (there is no evidence that suturing by hand is better than stapling with staplers)
- Staplers or clips (the Hungarian surgeon Aladár Petz (1888–1956) invented the gastric stapler and pioneered the technique).

New methods

- Compression (biodegrading) rings
- Tissue adhesives

5.1. Two-layered anastomosis technique

- This is the traditional method for anastomoses of the gastrointestinal tract
- An inner continuous catgut (absorbable) suture, with stitching of all layers
- An outer, seromuscular, interrupted silk (nonabsorbable) suture
- Serosa apposition and mucosa inversion; the inner layer has a hemostatic effect (there is no significant bleeding), but the mucosa is strangulated.





$16.95

Cosmic Fusion

Fusion of the Eight Forces

Mantak Chia

Illustrated by Udon Jandee

Forming the Pakuas

We can connect our being with the powers of the Earth and the Universe. The organs and senses connect using the eight forces of the Pakua via the Fusion Practice. Negative emotional energy is balanced with positive energy and fused into a pearl of pure life-force energy.

Energy Body, Spirit Body

Making your way along the path, you become aware of the great value of the practices in preparing the spirit body to move into worlds beyond - and back. You'll move from balance to resonance to love.

Manifest the Positive

With discipline and perseverance your practice will manifest a life that suits you perfectly. With smiles and diligence the fusion meditations nurture positive energies, forming the compassion pearl. You'll detoxify, nourish and integrate the physical body, the energy body and the emotions, allowing the heavenly and earthly forces to balance you.

Clarity, Wisdom, Truth

Subtle and powerful, the Fusion Practice will change your life. Relax, and come along on a journey both remarkable and priceless. The way will open.

ISBN 974-85391-9-9
9 789748 539195

Universal Tao Publications

5.2. Single-layered technique

- This is a newer, more up-to-date technique of gastrointestinal anastomosis
- An interrrupted seromuscular suture, with absorbable (e.g. 3/0 Vicryl) thread. The submucosal layer is strong and the blood supply is only minimally damaged.



5.3. Stapler-made anastomosis

- This can be a side-to-side anastomosis with a straight sewing machine (e.g. GIA = **g**astro**i**ntestinal **a**nastomosis staplers).
- It can be an end-to-end anastomosis with a circular machine (e.g. CEEA = **c**ircular **e**nd-to-**e**nd **a**nastomosis stapler).
- The stapler decreases the frequency of radiologically demonstrated anastomosis insufficiency, but the incidence of anastomosis stricture is increased.



6. Surgical techniques of intestinal anastomoses

- Requirements include a supine position, general anesthesia, a midline laparotomy and a good exposure; the affected bowel must be mobilized (freed).
- The gastrointestinal tract should always be considered infected when the intestinal lumen has been closed; new, sterile instruments and draping are necessary.
- The pathological tissue must always be excised with a normal intact margin (!); the blood supply of the remaining intestinal tissue is critical.
- Relatively equal diameter segments of bowel should be sewn together. The anastomosis should be tension-free and leak-proof.
- The mesenteric defect is closed (prevention of internal hernia formation).

7. Closure of enterotomy

- After laparotomy, the injured bowel segment is identified and isolated. The borders are temporarily closed (*Klammer* intestinal clamps) and the defect is enlarged/incised, i.e. converted to a surgical incision.
- A horizontal suture or end-to-end anastomosis is performed.
- Irrigation, handling of bleeding and closure in layers.







8. Surgical unification of bowel segments by end-to-end anastomosis

- The two bowel ends are put in close approximation and two interrupted, holding sutures are placed. A continuous running suture is applied to close the back, and then the front part of the intestinal wall.
- After closure of the deeper layer, the serosa (second layer) is closed.
- The passage of the anastomosis is checked by examination with the fingers.

1



2



3



4



5



6



7



8



9



10



VI. Abdominal drainage

The most frequent causes of surgical diseases of the small intestine are mechanical causes (obstruction, strangulation/adhesion, volvulus, intussusception or fecal impaction), vascular causes (ischemic colitis, occlusion/infarct, or arteriovenous malformations), inflammation (diverticulosis/diverticulitis, ulcerative colitis, *Crohn*'s disease or appendicitis) or traumas (blunt/penetrating injuries). Invasive abdominal diagnostic interventions may be needed primarily in these latter cases.

1. Historical background of invasive diagnostic procedures

1950	Four quadrant needle paracentesis.
1965	Diagnostic peritoneal lavage (DPL – the term was coined by *Root HD et al. Diagnostic peritoneal lavage. Surgery. 1965; 57:633–637*). The sensitivity is 98%, but the specificity is only 80% (no information is provided on the retroperitoneum).
1990s	Laparoscopy became widespread. It has the *advantage* of good visualization of the intraabdominal organs, whereas it is *disadvantageous* that no information is available on the retroperitoneum, and the closure is 'complicated' as compared with punctures.

2. Indication of diagnostic peritoneal lavage

- An equivocal clinical examination and difficulty in assessing a patient.
- Persistent hypotension, despite adequate resuscitation.
- Multiple injuries, or stab wounds where the peritoneum has been breached.
- Lack of alternative diagnostic methods (US or CT).



2.1. Open system

- After insertion of a urinary catheter and a nasogastric tube, local anesthesia is started. A vertical, ~ 2-cm subumbilical incision is made, and the linea alba is divided.
- An incision is made in the peritoneum, a peritoneal dialysis catheter is inserted, the free blood or gastric content is aspirated, etc.
- If no blood is seen, 1 ℓ of normal saline is infused, a period of 3 min being allowed for equilibration. The drainage bag is placed on the floor and drainage proceeds (motto: "*Gravity is our friend*").
- A 20-mℓ sample should be sent to the laboratory for the measurement of red blood cells, white blood cells and microbiological examination (DPL is positive if the red cell count is > 100,000 / mm^3, the white cell count is > 500 / mm^3, or bile, bacteria or fecal material is present).
- In the event of positive results, DPL is continued until surgical exposure (laparotomy), and the demonstration and treatment of the causes.
- The peritoneum is closed with a purse-string suture, and the skin and sc. layers are then closed with an interrupted suture.

2.2. Closed system

- After insertion of a urinary catheter and nasogastric tube, local anesthesia is initiated, after which a catheter is introduced with the aid of a guide wire (a blind technique; the morbidity of 9%, is mostly due to vessel injury).
- The routine is modified in obese patients (special indication for closed DPL):
- Computer tomography is impossible (weight, diameter limits, poor image, higher radiation).
- Open DPL is contraindicated as the depth of the puncture (peritoneum) can not be judged, and hence the complication rate of the closed technique is much higher. The half-closed/blind *Seldinger* or modified *Seldinger* technique is possible.

3. Therapeutic (chronic) lavage: peritoneal dialysis

- Dialysate is injected into the peritoneal space through a two-way *Tenckhoff catheter,* which remains permanently in place. The peritoneal dialysate, composed mostly of salts and sugar (glucose), encourages ultrafiltration. The peritoneum allows waste and fluid to pass from the blood into the dialysate, which is pumped out.




skin surface
subcutaneous cuff
peritoneal cuff
peritoneal cavity


skin surface
subcutaneous cuff
peritoneal cuff
peritoneal cavity



- The catheter exits the skin laterally to the midline. A 20–30 cm long connecting tube (transfer set) can be fastened to this with a screw thread, with the help of which the sacks containing the dialysing solution can be attached. The transfer tube can be closed with a roller-wheel or with a sterile screw stopper.

4. Therapeutic (postoperative) rinsing drainage

(see the basics in section IV.10)

- The main indication of continuous postoperative drainage was earlier severe sepsis. Today it is used mostly for intraabdominal abscesses and inflammatory processes. It is simple and cheap and can be life-saving (see details in *Csaba Gaál: Alapvető Sebésztechnika, Medicina, 1998*).
- *Principle:* If a cavity is present, it must be open; primary closure is forbidden.
- *Problems:* Clotting, fibrin plug and cavity compartment formation resulting from adherence, which increases the risk of bacterial infections.
- *Main types*: Rubber tubes and suction tubes (see section IV.10).

VII. Basic thoracic surgical practicals

A thoracic trauma is generally sudden and dramatic; it plays a role in 25% of the cases of mortality caused by traumas overall. Two-thirds of the deaths occur after admission to hospital. It has serious complications: hypoxia, hypovolemia, and respiratory and circulatory insufficiency are frequent. It can be blunt and non-penetrating (a traffic accident, a direct blow, a fall, or a deceleration and compression injury) or penetrating (shot and stabbed wounds, in which primarily the peripheral lung is affected). The chest wall, pleura, lung parenchyma, upper airways/mediastinum or heart may be injured. If the state of the patient is unstable, tension pneumothorax, pericardial tamponade and massive hemothorax may be suspected (the route of the trauma may be an indicator). Complementary examinations are often needed (echocardiography, bronchoscopy, esophagography, esophagoscopy and aortography). Iatrogenic traumas are frequently caused by the introduction of nasogastric tubes (endobronchial introduction), chest tubes (sc., intraparenchymal or intrafissural introduction) or central venous catheters.

1. Types of pleural effusion

- Transudate (protein content < 3.0 g/mℓ), serous fluid (e.g. malignancies)
- Exudate (protein content > 3.0 g/mℓ) caused by inflammation
- Hemothorax (blood in pleural sac)
- Empyema (pus in pleural sac), fibropurulent exudate
- Chylothorax (lymph)



2.1. Mechanism/causes of thoracic effusion formation

- Increased hydrostatic pressure – in chronic heart failure
- Increased capillary permeability – inflammation
- Decreased colloidal oncotic pressure – nephrotic syndrome, liver disease
- Decreased lymphatic drainage – metastatic obstruction

2.2. General principles of treatment

- Find the cause
- Analgetics for pleurisy
- Thoracocentesis/thoracic tube

3. Hemothorax

Definition: There is blood in the pleural sac, usually caused by a penetrating trauma. The source of the bleeding can be the alveoli, bronchi or thoracic vessels. The accumulating blood compresses the heart and the thoracic vessels (one half of the lung may contain ~ 1.5 ℓ of blood). Respiratory disorders can occur, but circulatory disorders are more common. *Signs:* Tachycardia, a weak pulse and shock-like symptoms. The diagnosis can be established via a chest X-ray (pleura infiltration) and diagnostic thoracocentesis.


The source of hemorrhage:
– injury of subcostal vessels
– rupture of the pulmonary vessels

3.1. Treatment of hemothorax

- Fluid, volume and oxygen therapy
- Small (300–500 mℓ). This may be left alone; it will be reabsorbed.
- Moderate (500–1000 mℓ): This requires computer tomography (CT) and drainage
- Large (> 1000 mℓ): CT, drainage and surgery (control of arterial bleeding) are needed.

4. Pneumothorax (PTX)

Definition: This is a condition in which air or gas is present in the pleural space. This leads to an increased intrapleural pressure, which causes partial or total collapse of the lung.



4.1. Etiology of PTX

- Spontaneous, primary PTX
- Blunt chest traumas (motor vehicle accidents and falls)
- Penetrating traumas (gunshot and knife injuries), rib fractures and flail chest
- Rib rupture and unstable chest

4.2. Clinical signs of PTX

- Tachypnea and tachycardia. Questions: Are there breathing difficulties, or pleurisy? Show its location.
- Cyanosis
- Diminished breath sounds; hyper-resonance on the affected side
- Neck vein engorgement
- Paradoxical movement of the unstable chest; deviated trachea
- Cardiogenic shock

4.3. Types of PTX

- Closed or open
- Traumatic or spontaneous
- Simple or tension
- Primary or secondary

4.4. Closed PTX

This can occur spontaneously, or it may be a consequence of a blunt trauma or an abrupt pressure rise (a blast or diving). It is particularly frequent in thin, 20–40-year-old male smokers. Most cases resolve after 1–2 days. Chest tubes and surgical repair are rarely required (< 10%). *Treatment:* Oxygen, iv. fluid, circulatory monitoring and a chest tube if needed.



4.5. Open PTX

Definition: A hole in the chest wall allows atmospheric air to flow into the pleural space, leading to an increased intrapleural pressure, resulting in partial or total collapse of the lung. This can be caused by a penetrating injury or be a side-effect of a therapeutic procedure, e.g. the insertion of a central venous or pulmonary artery catheter.



4.5.1. Signs of open PTX

- A sucking or hissing sound is audible on inspiration as the chest wall rises
- Blood, foam and blood clots are coughed up
- Shortness of breath / difficulty in breathing
- Pain in the shoulder or chest that increases with breathing

4.5.2. Treatment of open PTX

Wound toilette: Larger wounds should be treated first. Check for entry and exit wounds (look and feel). An airtight, complete cover should be provided at least 5 cm beyond the edges of the wound. Three edges of airtight material (the top edge and two sides) are taped down so as to create a “flutter valve” effect that allows air to escape from, but not enter the chest cavity (in the USA, “Petroleum Gauze” or “Asherman Chest Seal” (flutter-valve seal) can be used).



The primary treatment of PTX:
– wound-toilette
– airtight covering
– taping on 3 sides

4.6. Tension PTX

Iatrogenic or traumatic lesions of the visceral or parietal pleura (often associated with rib fracture) is responsible for one-third of preventable thoracic deaths(!); in these cases, the rupture of the pleura behaves as a one-way valve. *Mechanism:* A one-way valve allows air to enter the pleural space and prevents the air from escaping naturally. The increased thoracic pressure leads to collapse of the ipsilateral lung, and pushes the heart, vena cava and aorta out of position (mediastinum shift), leading to a poor venous return to the heart, a decreased CO and hypoxia. *Etiology*:

- barotraumas
- secondary to positive-pressure ventilation (PEEP)
- complication of enteral venous catheter placement, usually subclavian or internal jugular
- conversion of idiopathic, spontaneous, simple PTX to tension PTX (an occlusive dressing functions as a one-way valve)
- chest compressions during cardiopulmonary resuscitation
- fiberoptic bronchoscopy with closed-lung biopsy
- markedly displaced thoracic spine fractures.

Tension pneumothorax



4.7. Signs and symptoms of tension PTX

Early findings

- Chest pain and anxiety
- Dyspnea, tachypnea and tachycardia
- Hyper-resonance of the chest wall on the affected side; diminished breath sounds on the affected side

Late findings

- A decreased level of consciousness
- A tracheal deviation toward the contralateral side
- Hypotension and cyanosis
- Distension of the neck veins (this may not be present if the hypotension is severe) and increased CVP

5. Treatment of PTX

5.1. Basic questions

- How much air is present? What is its source?
- What is the general condition of the patient? What is the severity of other injuries?
- Are critical care facilities available?

5.2. Treatment of simple PTX

- If the size of the PTX is < 20%, bed rest and limited physical activity are called for.
- If the size of the PTX is > 20%, thoracocentesis or insertion of a chest tube attached to an underwater seal is necessary.



5.3. Treatment of simple PTX with needle thoracocentesis

Requirements

A 22–20 gauge needle, extension tubing, a three-way stopcock, a 20 to 60 mℓ syringe and supplementary oxygen are required, +/- iv. fluids and analgetics.

Technique: see above.

5.4. Emergency needle decompression

Indication

A diagnosis of tension PTX with any two of the following signs:

- respiratory distress and cyanosis
- mental alterations
- a nonpalpable radial pulse (hypovolemia)


The site of puncture in case of tension PTX: directly above the 3rd rib (2nd intercostal space) in the midclavicular line.

Technique

- Administration of 100% oxygen; ventilation if necessary; continuous monitoring; pulse oxymetry if possible.
- Location of anatomic landmarks. Surgical chest preparation (Betadine and alcohol) and local anesthetics (if the patient is awake or if time / the situation permits).
- In cases of trauma, the patients should be supine, with head tilt; in other patients, a 45° sitting position is required.
- Decompression catheters are placed in the midclavicular line in the 2nd rib interspace. Placement in the middle third of the clavicle minimizes the risk of injury to the internal mammary artery.
- A puncture is made through the skin, 1–2 cm from the sternum.
- A needle (14–16 gauge) or needle catheter (Braunule; 2 inch/5 cm) is used, perpendicular to the skin, just above the cephalad border of the 3rd rib (the intercostal vessels are largest on the lower edge of the rib).
- Once the needle is in the pleural space, the hissing sound of escaping air is listened for, and the needle is removed while the catheter is left in place.


PTX (valve is closed during inspiration)
The direction of air and lung movement during expiration.

The site of puncture in PTX:
– above the 3rd rib (2nd intercostal space)
– in the midclavicular line.

- *Option I:* Removal of the needle; the plastic catheter stays in place; preparation for placement of the chest tube.
  Option II: A plastic or rubber condom is placed on the end of the needle, which acts as a valve (before the definite management of the PTX).

Complications

- Injury of intercostal vessels and nerves.
- PTX (if the procedure is performed in patients without PTX, the risk rate of lung injury and PTX is 10–20%).
- Infection.

5.5. Percutaneous thoracocentesis for the treatment of PTX

Equipments

18 G Braunule, pneumocath (9 F), *Seldinger* catheter (6–16 F), chest tube (18–36 F) and water seal/Heimlich valve (see later).

5.6. Chest drain – chest tubes

Indications

Fluid and air should be evacuated from the pleural space and a negative intrapleural pressure reestablished to reexpand the lungs, with needle decompression management.

Technique

There are two main methods are: a) with a trocar, or b) a blunt technique (see above):

- Anatomic landmarks are located, and local anesthetic is administered (a 3-cm horizontal incision is made along the midaxillary line over the 5th or 6th rib). Sedation; narcotics; preparation of the area with Betadine. Draping is optional.
- A 2–3-cm long transverse incision is made in the skin, followed by the blunt dissection of sc. tissues, exactly over the rib. The parietal pleura should be stabbed with the instrument used for preparation (*Péan,* dissector).
- The rubber-gloved index finger should be introduced through the opening (to avoid injuries to the lung, etc. and free adhesion).
- The proximal end of the chest tube is introduced to the appropriate length into the pleural cavity. The tube is introduced along the inner surface of the chest in the backward and upward direction.
- During expiration, vapor can be seen in the tube, or the outflow of the air is audible.

The site and depth of the dissection


parietal pleura
pleural cavity
pleura visceralis
4th rib
5th rib
Péan


The site of incision:
– above the 5th rib
– in the mid-axillary line.
The drain is introduced along the inner surface of the parietal pleura to backward
and upward direction.

- The tube is attached to a suction bottle with an underwater seal, and then fixed to the skin with a stitch.

Complications of chest tube placement

- Mechanical failure of air or fluid drainage due to a tube obstruction: blood clots or kinks.
- Placement in a fissure, infradiaphragmatic or extrapleural.
- Infection of the entry site or pleural fluid (a sterile, aseptic technique is mandatory; the prophylactic use of antibiotics is controversial).
- Bleeding is rare (if the tube is placed over the top of the rib to avoid vessels).

6. Chest drainage system

Purpose: Negative pressure is created to facilitate re-expansion of the lungs and to remove air, blood or other fluids from the pleural space or mediastinal space. The *duration* is usually 2–3 days (24 h after re-expansion), if the drainage is less than 50–70 mℓ/h.


visceral pleura
parietal pleura
diaphragm
The place of air drainage:
2nd intercostal space, midclavicular line.
suction-pump
The place of fluid drainage:
5–7th intercostal space, midaxillar line.

6.1. Indications

- Mediastinal, cardiac surgery, chest trauma
- Traumatic injury, fractured rib (intrapleural fluid, PTX, hemothorax, pleural effusion)
- Management of complications (CVC insertion, lung biopsy)

6.2. Types

- Wet suction (*Bülau* suction or 3-bottle systems). The air or fluid is removed from the pleural space or mediastinum. The water-seal acts as one-way valve, allowing air to leave pleural space, but not to return, maintaining a negative pressure.



- Waterless/dry (*Heimlich* valve) system. A valve is opened by the pressure of the air or the fluid; after its closure, no backflow is possible. During the one-way function of the soft rubber valve in the plastic housing, air leaves to the environment. This system is portable, and can be used for home nursing.
- One-piece, three-chamber, disposable plastic systems (USA: Pleurevac, Atrium/Ocean, or Thoraseal).



- Autotransfusion: This is a variation of the water-seal system, with an attached container so that the blood which drains from the chest can be salvaged for autotransfusion.

7. Flail chest

Definition: This involves a multiple (three or more) rupture of the ribs in two or more areas or/and a fracture of the sternum. *Signs:* Severe local pain, rapid, superficial breathing, paradoxical chest wall movement (sometimes not obvious at the beginning), PTX and lung contusion can be present, which causes severe hypoxia. There is paradoxical chest wall movement: the serial rib fracture leads to chest instability, and the bellows movement of the chest ceases. *Signs:* Superficial asymmetrical and uncoordinated breathing and crepitus of the ribs. *Treatment:* Improvement of the respiratory function, administration of humidified oxygen, chest tubes, ventilation (PEEP), circulatory support, fluid therapy and analgetics.



8. Cardiac tamponade

Definition: Blood accumulates in the pericardium. As it has poor compliance, 150–200 mℓ of blood can result in a tamponade, exerting pressure on the heart and limiting the cardiac filling and CO. A decreased CO causes



The technique of pericardiocentesis:

puncturing the skin at an angle of 45°, 1–2 cm from the left lower part of xipho-chondrial junction, carefully introducing the needle to the direction of the apex of the left scapula.

Cosmic Healing I

Cosmic Chi Kung



Mantak Chia

hypotension. It may occur in patients with either a penetrating or a blunt chest trauma. *Signs:* Shock, increased jugular venous BP, pulsus paradoxus (the systolic BP decreases during inspiration as compared with expiration). In classical cases: *Beck's* triad: 1. distended neck veins, 2. muffled heart sounds, 3. hypotension. *Therapy:* Resuscitation and pericardiocentesis.

The technique of pericardiocentesis

- Before and during the intervention, the monitoring of vital signs (ECG) is necessary. The xyphoidal and subxyphoidal area should be surgically prepared (local anesthesia should be applied if time allows).
- A #16–18 G, 6-inch (15-cm) or longer needle catheter attached to a 20-mℓ syringe is necessary.
- The skin should be punctured at an angle of ~ 45°, 1–2 cm from the left lower part of the xypho-chondrial junction, and the needle should then be carefully advanced in the direction of the apex of the scapula.
- If the needle goes too deep, lesion potential (negative QRS) can be seen in the ECG: the needle should be withdrawn until normal ECG is restored. When the tip of the needle enters a pericardial cavity engorged with blood, as much fluid as possible should be aspirated.


The depth of pericardiocentesis:
the needle must be withdrawn when the lesion potential appears until the normalization of ECG.
normal QRS
lesion potential

- During aspiration, the epicardium comes close to the pericardium and at the same time to the tip of the needle, and thus the lesion potential can reappear in the ECG. The needle should then be slightly withdrawn. After completion of the aspiration the syringe should be removed, and a closed three-way stopcock should be attached to the needle catheter and fixed.
- Option: In the *Seldinger* technique, a flexible wire is advanced through the needle into the pericardial cavity. The needle is removed, a #14-G flexible catheter is then introduced through the wire, the wire is removed, and finally a three-way stopcock is attached to the catheter.

VIII. Tracheostomy

Tracheostomy has been applied for centuries for the treatment of upper tracheal obstructions threatening asphyxia. In recent decades, it has often been used for the management of mechanical respiratory insufficiency and functional (dynamic) respiratory failure too. In most cases, endotracheal intubation solves the respiratory insufficiency and tracheostomy is not required. In emergency cases, if the personal and technical conditions of intubation are lacking, conicotomy/cricothyrotomy is performed. Following a skin incision, the ligamentum conicum (lig. crycothyroidum) just underlying the skin is cut transversally between the thyroid and cricoid cartilages and endotracheal intubation is performed. Tracheostomy is performed if the airway cannot be held open in any other manner or if the endotracheal intubation (after 1 week) or conicostoma (after 48 h) must be terminated, but the airway must be maintained in an open state.

1. States evoking mechanical respiratory insufficiency

- *Obstruction:* e.g. bilateral recurrent nerve paralysis or a severe laryngeal injury.
- *Obturation:* a foreign body, blood, secretion, croup or tumor.
- *Constriction:* edema, inflammation or a scarred stricture.
- *Compression:* e.g. struma, lymphoma or other malignant tumors.

2. States evoking functional respiratory failure/insufficiency

- Diseases of the central nervous system: e.g. injuries, tumors or inflammatory states.
- Drugs and toxins influencing the function of the central nervous system.
- Pathological conditions influencing the respiratory mechanism, such as lesions and diseases of the chest wall, respiratory muscles, lungs and their innervations.
- An altered cardiopulmonary state/relations, i.e. decreased oxygenation due to decreased lung perfusion and ventillation and impaired diffusion.

3. Advantages of intubation and tracheostomy

- The upper airways are open.
- The anatomic dead space can be decreased by 50%.
- Reduced airway resistance.
- Reduced risk of aspiration.
- Suctioning of fluids from deeper airways is possible.
- Possibility of the use of a ventillator.

4. The surgical technique of intubation – preparation of an upper tracheostomy

In adults, generally an upper tracheostomy is made, except when the airway stricture is deeper.

- After the appropriate positioning, the patient is anesthetized and intubated, and the skin is scrubbed and draped. Following palpation of the cricoid cartilage, the first and second tracheal cartilages are looked for. Between them, a short transverse cutaneous incision is made.
- The white fascia running in the midline (linea mediana alba colli) is elevated with dressing forceps and cut with scissors longitudinally.
- The longitudinal strap muscles are grasped on both sides with dressing forceps and separated with blunt dissection in the midline. The wound is exposed with retractors by the assistant.
- The fascia covering the trachea is lifted by dressing forceps and divided longitudinally, and the membranous sheet of the trachea then cut transversally with a scalpel between the first and second tracheal cartilages.
- A mosquito *Péan* hemostat is placed into the opening. The second tracheal cartilage is elevated by this and cut through longitudinally in a downward direction. In this way a T-shaped opening is created/formed.
- An atraumatic stitch is placed into both corners of the cut cartilages. The edges can be opened by the stitches like casements. In the opening, the endotracheal tube becomes visible.
- A trachea cannula of appropriate size is selected. The balloon of the cannula must be previously tested.
- The air is sucked from the balloon of the endotracheal tube with a syringe, and the tube is then withdrawn over the stoma.
- With the help of the stitches, the opening is explored; and the tube is carefully placed into the opening and introduced into the trachea. The obturator is removed from the tube, and the balloon of the tube is inflated.
- The stitches are removed from the cartilage, or are individually knotted and then tied together over and under the tube.



IX. Basics of minimally invasive surgery

Motto: *"The future has already started!"*

The goal of video-endoscopic minimally invasive surgery is to replace conventional/traditional surgical methods, but maintenance of the results and standards achievable by open means is essential. Due to the additional benefits of magnification, better visualization and the less invasive approach, greater precision and improved results are possible. This new technical specialty has developed its own instrumentation, requirements and a very complex technical background, and thus the topic is discussed in a separate chapter. Nevertheless, it must be borne in mind, that the laparoscopic minimally invasive technique is based on a firm knowledge of traditional surgery. The basis of abdominal (i.e. "laparoscopic") minimally invasive techniques will be surveyed here. Other regions (e.g. the joints and the chest) are the subjects of the relevant specialties.

1. A brief history of minimally invasive surgery

1706	"Trocar" is first mentioned (trois (3) + carre (side), or trois-quarts / troise-quarts – in Old French).
1806	Phillip B. Bozzini (1773–1809) is often credited with the use of the first endoscope. He used a candle as a light source to examine the rectum and uterus.
1879	Maximilian Nitze and Josef Leiter invented the *Blasenspiegel* (i.e. the cystoscope).
1938	A spring-loaded needle was invented by the Hungarian János Veres (1903–1979). Although the "*Veress needle*" was originally devised to create a PTX, the same design has been incorporated in the current insufflating needles for creating a pneumoperitoneum (*J. Veress: Neues instrument zur ausfürung von brust- oder bauchpunktionen und pneumothoraxbehandlung. Aus der Inneren Abteilung des Komitatsspitals in Kapuvár (Ungarn). Deutsche Med Wochenschr 1938; 64: 1480–1481*).
1985	Erich Mühe in Böblingen, West Germany, performed the first laparoscopic cholecystectomy (with a "*galloscope*"). After nearly 100 successful operations, 1 patient died from a complication not related to the procedure itself. The German medical authorities declared that this was the result of "human experimentation". Mühe was charged with and found guilty of homicide.
1987	Phillipe Mouret, in Lyon, is usually credited with the first successful human laparoscopic cholecystectomy. Perrisat, Dubois and colleagues in communication with Mouret performed laparoscopic cholecystectomies shortly thereafter, and within 10 years, this had become the standard technique for cholecystectomy.

2. Present status of minimally invasive surgery

- Minimally invasive procedures routinely applied in 2006 are diagnostic laparoscopy, laparoscopic cholecystectomy and appendectomy, fundoplication, laparoscopic splenectomy and adrenalectomy, laparoscopic *Heller*'s myotomy, etc.
- The "cutting edge" is robotic surgery. The types of surgical operation (at present) are fundoplication, cholecystectomy, heart surgery and teleoperation. The greatest advantage is the elimination of the human factor (trembling hands, eye-hand coordination problems, etc.). The two main systems involve *Da Vinci* and *Zeus* manipulators (the former are better manipulators, while the latter are smaller instruments).
- Fetoscopic surgery (laparoscopic *in-utero* procedures). More frequent operations (at present) are decompression of the bladder, coagulation of vessel anomalies (radio-ablation in twin pregnancies), cutting of the amnion bands, hydrothorax drainage, and temporal trachea occlusion (in cases of congenital diaphragm hernia).

3. Advantages of minimal access surgery

- Linking diagnostic and therapeutic procedures
- Better cosmesis
- Fewer postoperative complications, hernias / infections
- Fewer postoperative adhesions:
  - fewer hemorrhagic complications
  - less peritoneal dehydration
  - lower degree of tissue trauma
  - lower amount of foreign material (sutures)

- Shorter postoperative recovery:
    - less tissue trauma
    - lower stress in general
    - less postoperative pain
- Patients are able to resume their normal activities faster (in 6 days on average). The mechanism of wound healing is identical (!), the recovery depends on the indication (cause of illness) and the healing time of incisions/ports, and the latter depends on the insults of organs and abdominal wall, the stress caused by general anesthesia, and the healing process of the peritoneal damage
- Decreased hospital stay (economic advantage)

4. The technical background of minimally invasive techniques. The laparoscopic tower

- Main parts (in general): 1. monitor (screen), 2. video system (control unit, etc.), 3. light source, 4. insufflator ± carbon dioxide cylinder, 5. suction and irrigation, 6. electrocautery device, 7. data storage system.
- The *endoscope* and *camera* are attached to the units of the tower via cables.

4.1. Endoscopes

- The ocular is the proximal end of the optical part. A video camera or conventional camera suitable for making high-resolution image capture pictures can be attached to this part (but the organs can also be examined by naked eye). The objective is at the distal end of the optical system.



- The objective can be in a 0°–30°–45°- configuration in relation to the perpendicular cross-section of the optical axis. The 0° laparoscope provides a straight-forward view, and the 30° laparoscope a forward oblique view. The amount of light forwarded to the ocular is the highest in 0° objectives.



- Conventional laparoscopes have a fixed focus. The magnification is increased / decreased either by turning the laparoscope's zooming ring, or by advancing the laparoscope toward or withdrawing it from the targeted area.
- Working in a closed environment requires a source of external illumination. Currently, a 150–300 W fan-cooled xenon light source is used to provide color-corrected light for extended periods of time without overheating. The illumination is transmitted to the laparoscope via a flexible fiberoptic light guide (180–250 cm long, 0.5–1.0 cm OD). This illumination is essentially cold: most of the lamp heat is not transferred to the laparoscope.
- A control unit receives the signals from the camera head, converting the optical image into the initial video signal. The camera head attached to the endoscope receives the image and converts it to electric signals.



4.2. Diathermy

- In a bipolar (insulated) system, the tissue is placed between two electrodes, so that the current passes from one electrode to the other through the interposed tissue. It involves the technology of precision coagulation: peripheral vascular and microsurgery.
- In a monopolar (grounded) system, the ground pad, with a surface area of ~ 50 cm^2, is placed over muscular tissue, and coated with a conductive gel to enhance conductance.

4.3. Suction and irrigation

- The rapid removal of abdominal fluid is mandatory. The irrigation and suction functions can not be separated. Central unit: An electric pump with continuous 180 mmHg positive pressure and 500 mmHg negative pressure. Fluids: Warm isotonic solutions (saline).

5. Physiology of laparoscopy. The pneumoperitoneum

In the abdominal cavity, a large dome-like space must be created to displace the viscera and enable the surgeon to see and move the instruments about. This may be done by instilling gas under pressure (a pneumoperitoneum is created). This provides a good operative field and helps stop venous and capillary bleeding. Historically, this was achieved by the insufflation of free air (in gynecology), but at present it is carried out by introducing carbon dioxide from a closed system under pressure. Strict control is needed for maintenance of the pneumoperitoneum. The intraabdominal pressure in adults (Piabd) should be < 15 mmHg; in pediatric surgery < 6 mmHg is proposed. The safety system of the insufflator prevents Piabd exceeding the set limit (e.g. 15 mmHg).

Pathological consequences of the pneumoperitoneum

- Piabd < 12–15 mmHg = a disturbance of the venous circulation prevails.
- Piabd > 12–15 mmHg = the cardiac index decreases, and the gas exchange declines.
- Constantly high Piabd = organ injuries.

Circulation

- The venous backflow (*preload*) is decreasing.
- CO ↓
- HR ↑
- MAP ↑
- Total peripheral resistance (afterload) ↑
- Pulmonary vascular resistance ↑
- The hemodynamic changes in the reverse *Trendelenburg* position are more pronounced, venous depression can occur in the lower limbs and the risk of thrombosis increases. The patient should be placed in the *Trendelenburg* or the reverse *Trendelenburg* position only if Piabd is stable.

Microcirculation

- Mechanical compression of the mesenteric vessels; decreased splanchnic microcirculation.

Neurohormonal system

- The increased intraabdominal pressure stimulates the secretion of the renin-angiotensin and renin-aldosterone-angiotensin systems which causes vasoconstriction.

Respiratory effects

- The increased intraabdominal pressure increases the intrathoracal pressure, which decreases the lung compliance.
- Compression of the lower lung lobes, caused by the intraabdominal pressure together with the anesthesia-induced diaphragm relaxation leading to a decrease in lung volume while the dead space increases (the *Trendelenburg* position enhances these effects).
- As a possibility to improve gas exchange PEEP can be applied.

Arterial blood gases

- CO_2 in the systemic circulation causes hypercapnia and respiratory acidosis. Insufflation increases $PaCO_2$ by 8–10 mmHg, together with a decrease in pH. Equilibration starts 15–20 min after production of the pneumoperitoneum.

Urinary excretion

- Piabd < 15 mmHg decreases the kidney perfusion and the glomerular filtration rate, which causes oliguria.
- Direct pressure on the kidney parenchyma, renal arteries and veins causes the renal function to decrease linearly with pressure (no clinical relevance under 15 mmHg)

Liver function

- The hepatic and portal circulation progressively decrease, while the concentrations of liver enzymes in the plasma increase.

5.1. Complications of pneumoperitoneum

Vessel injury: The most common sites are the epigastric vessels, and vessels in the greater omentum. Large veins and arteries are rarely injured (this is rare, but has a mortality of 50%).

Organ injuries: Untreated in 24 h small bowel, large bowel and liver injuries lead to severe septic complications.

Subcutaneous emphysema: This is caused by CO_2 under pressure, which dissects tissues. It can be accidental or intentional (extraperitoneal surgery).

Air emboli: The complication rate is < 0.6% (rare, but potentially lethal). Most common: lung emboli; rare: coronary arteries and brain.

Prevention of air emboli
- Safe trocar use
- Intraabdominal pressure control with soluble gases (CO_2)

Diagnosis of air emboli
- Trans-esophageal Doppler US (not in routine use in laparoscopic surgery)
- Capnography (!): detection of end-tidal CO_2, which decreases as a consequence of decreasing CO_2 + increasing dead space. A parallel decrease in PaO_2 is highly suspicious.
- ECG changes are late, mainly during large embolization (!)

Therapy of air emboli
- Stop insufflation; exsufflate pneumoperitoneum;
- The left *Trendelenburg* position decreases embolization from the right heart to the pulmonary circulation
- Central venous catheter into the pulmonary artery for gas aspiration

Pneumothorax: The cause of PTX is an elevated Piabd, which leads to the opening of embryonal peritoneo-pleural channels (this is "spontaneous" PTX). It nearly always occurs in cases of diaphragmatic preparations (classical case: fundoplication).

Consequences
- Increased airway pressure, increased pulmonary resistance
- $PaCO_2$ ↑, PaO_2 ↓
- CO ↓, compensatory HR ↑

Treatment of pneumothorax
- PEEP is applied (5 cmH_2O) to reinflate the lungs and remove CO_2.
- N_2O administration is stopped; FiO_2 is increased; Piabd should be decreased.
- Thoracocentesis is usually not necessary; CO_2 will be absorbed in ~ 30 min and PTX will cease.

Important note: Discernment of CO_2-induced PTX and PEEP-induced rupture of alveoli (caused by emphysema) is important. In the event of emphysemic rupture, PEEP will aggravate the signs and the PTX can not be eliminated "spontaneously". The therapy is use of a chest tube (!)

Increased intraabdominal pressure
- A "surgical" increase in Piabd is followed by circulatory and respiratory changes (see above), but there are large individual differences in tolerance. A significant rise will increase the risk of complications caused by diffusible gases (air embolus and sc. emphysema).
- An "anesthesiology-caused" increase in Piabd is due to an insufficient depth of anesthesia/narcosis/muscle relaxation.
- A rapid intraabdominal volume load (e.g. suction/irrigation) or simultaneous use of other gases (e.g. argon coagulation) also causes an increased Piabd.

"Laparoscopic" pain
- The character of this pain differs from that of open laparotomy. In laparotomy (open surgery), abdominal pain predominates. Laparoscopic pain is a deep visceral pain (this is covered by abdominal pain during open surgery). The *characteristics* are pain in the shoulder and in the shoulder-blade (caused by the pneumoperitoneum-induced diaphragm tension and CO_2-induced acidic irritation).
- The *therapy* includes the complete removal of CO_2, irrigation with warm saline at the end of the procedure, and the subdiaphragmatic use of local anesthetic solutions (e.g. bupivacaine).

6. Basic instruments for minimally invasive surgery

A *Veress* needle is currently the device most commonly used to gain access to the peritoneal cavity before insufflation. This needle has a blunt obturator, which retracts on contact with solid tissue to reveal a cutting tip. A marker on the hand piece moves upward as the obturator retracts to expose the cutting tip. Once the peritoneal cavity is entered, gas may be instilled through the hollow shaft of the needle. The needle is then removed, and a trocar/cannula is inserted through the same site. This method of peritoneal access is referred to as the blind or closed technique.



Trocar: This has a sharply pointed shaft, usually with a three-sided point. A trocar may be used within a cannula, a hollow tube, designed to be inserted into a body cavity. A trocar is, strictly speaking, the cutting obturator within a cannula. In practice, the term trocar is commonly used by surgeons to describe the whole trocar-cannula apparatus.

Once the pneumoperitoneum is established, a "port" must be inserted to allow the passage of the laparoscope and operating instruments into the abdomen. The entire apparatus is inserted through the abdominal wall into the abdominal cavity. The pressure of the gas producing the pneumoperitoneum must be higher then the ambient atmospheric pressure. In order to prevent gas leaking from the port sites, the trocar incorporates a valve. This allows the insertion of instruments without the escape of gas.



Hand instrumentation: For minimal access surgery, special instrumentation is needed for the remote and closed surgical environment. These instruments have been designed to offer a full range of surgical functions (i.e. clamping, grasping, dissecting and cutting and suturing). Thus, the tips of laparoscopic instruments reflect those found in open surgery. The instruments pivot about the fulcrum of the access point with the instrument jaws located within the closed environment, the handle external to it, and the shaft between them partly in and partly out of the patient. Laparoscopic instrumentation ranges from 10–50 cm in length (most commonly 30 cm), depending on the distance of the target tissue from the point of access. They can be disposable (single-use, not safe for resterilization) or reusable (on a long-term basis).

7. Laparoscopic cholecystectomy

The main advantages are a shorter operating time and shorter hospitalization (the patient can leave the hospital 1–2 days following the intervention); less postoperative pain; the structure of the abdominal wall remains intact (the risk of postoperative hernia formation is lower); the patient can easily resume his/her former life-style, and can do physical work within a week; this intervention can be safely performed on elderly patients with a poor cardiorespiratory state (under high epidural anesthesia, if necessary); in cases of obesity or in patients with a thick abdominal wall, it is an ideal surgical solution.





8. Laparoscopic appendectomy

The main advantages are a shortened hospital stay (patients can be discharged on the 2nd–3rd postoperative day, and the normal life-style can be resumed ~ 10 days following the operation); there is minimal wound pain (minimal need for pain killer medication); wound suppuration does not occur (even in cases of advanced purulent inflammation); in obese patients and those with a thick abdominal wall, it is an ideal surgical intervention.

9. Training in a box-trainer

- The goal of the training is to adapt the traditional open techniques to the laparoscopic setting (this transition is not too simple). Training should begin with exercises in a simulator (suturing trainer box) using inanimate material. This provides an opportunity for the operator to become familiar with the equipment, the instrumentation, and the particulars of intracorporeal suturing and knot tying. In a "box-trainer" ("MAT-trainer") practice should be performed with the same quality optical-video-monitor setup as used in the operating room. This creates true and correct eye-hand coordination.



- Training can be as simple as transporting beads from one container to another or threading needles through fixed eyelets. For the exercise, a 30° laparoscope (diameter 5-10 mm and length 15-30 cm) is used because this ensures an optimal view with a wider field of vision after it is turned to another position.
- The student's practical training starts with eye-hand coordination exercises to pass needles and suture materials through metal rings.



- The precision intracorporal suturing applied in endoscopic surgery was developed by Alexis Carrel (1873–1944) and Charles Claude Guthrie (1880–1963) for vascular and microvascular surgery. The intracorporal tissue-suturing procedures allow for the reconstruction of fine tissue structures, because of the higher surgical accuracy. Today, much better results can be achieved with this technique than with conventional surgical interventions.

- Suturing exercises begin with the suturing of a latex glove that has two rows of dots marked on it. A cut made through it facilitates the acquisition of skill in needle handling, precision entrance-exit bites, suturing, and the knot-tying sequence. It is particularly important that a good technique, such as targeting entrance and exit points, should be practised early on in training.






3


4


5


6


7


8


9

ENCYCLOPEDIA of ANCIENT DEITIES

Charles Russell Coulter
and Patricia Turner

Cosmic Healing I

Cosmic Chi Kung

Mantak Chia

Edited by
Colin Campbell

ENCYCLOPEDIA OF
ANCIENT
DEITIES

ENCYCLOPEDIA OF ANCIENT DEITIES

by

CHARLES RUSSELL COULTER

and

PATRICIA TURNER

Routledge
Taylor & Francis Group
New York London

Copyright © 2000 by Patricia Turner and estate of Charles Russell Coulter
Published by special arrangement with McFarland & Company, Jefferson, North Carolina

All rights reserved including the right of reproduction in whole or in part in any form.

First published in the USA and UK 2000 by

FITZROY DEARBORN PUBLISHERS
919 North Michigan Avenue — Suite 760
Chicago, IL 60611
U.S.A.

310 Regent Street
London W1R 5AJ
England

This edition published 2012 by Routledge

Routledge
Taylor & Francis Group
711 Third Avenue
New York, NY 10017

Routledge
Taylor & Francis Group
2 Park Square, Milton Park
Abingdon,Oxon, OX14 4RN

Library of Congress and British Library Cataloging-in-Publiaction Data are available

ISBN 1-57958-270-2

In memory of
Charles Russell Coulter
—*Patricia Turner*

TABLE OF CONTENTS

On Alphabetization and Spelling ix

Preface 1

The Encyclopedia 3

Bibliography 527

Index 535

ON ALPHABETIZATION AND SPELLING

The Encyclopedia Proper

For a number of reasons having to do with the intermingling of Western name styles, indigenous and non-Western styles, phrases in English, and alternate name forms (including, for instance, two or more elements closed up as one word, such elements linked with hyphens, and such elements separated as two words), it was determined that the most useful alphabetization scheme would be what is commonly known as word-by-word (as opposed to letter-by-letter spread over any number of words or word parts). In this scheme, in the encyclopedia proper, two or more elements linked by hyphens are treated as separate words (the hyphen being purely a recent Western orthographical construct).

Thus in the encyclopedia (i.e., main) portion of the book, "Aka, Aka-Kanet, Aka Maneh, Akadja" is one sequence and "Ti-yu, Tiamat" is another.

Many, probably most of the entry names have two or more spellings (as distinct from the matter of two or more elements closed up, hyphenated or separated). This is especially true of names that have for a long time been a part of or adapted by Western culture (e.g., Greek, Norse, Egyptian, Indian, Chinese). Some names have four to six or even more alternate spellings or similar versions.

Many but not all alternate versions of a name are entered into the main entry sequence as "see" references. The one entry to which they all refer may well list yet additional spellings or alternate forms of a name.

In effect there has been, out of necessity, an effort in many but not all cases to discover or decide upon the most common form of a name for purposes of determining where in the alphabetical sequence a main entry shall appear. No similar effort was, however, extended to regulating the spelling or form of any name appearing secondarily within the text of an entry. In some cases a "most common form" was not identifiable or was considered a matter of cultural or linguistic bias or in some way was almost entirely subjective; in these cases, one main entry form was simply chosen and the others subordinated as "see" references.

The Index

The index must serve numerous purposes, not least of which is as an alternate to or clarification of the main entry alphabetization sequence. Accordingly, it is arranged similarly, in a word-by-word fashion, but with hyphenated forms now considered one word (so that the reader has additional opportunities to locate a name form for which they search).

Thus, there appears the sequence

Aka
Aka Manah
Aka Mano
Akadja
A-Kahiwahiwa
Aka-Kanet
Akalo
Aka-Manah
Akamas

and the sequence

All
All Merciful, The
All Pitying One
All Sinned One
Allah
Allat
Al-lat
Allath
Allatu
All-Caring
All-Devouring
Allecto
Alligator
Alloprosallos
All-pervader
All-seeing
almond trees

Virtually all alternate spellings and forms of a name appear in the index (whereas in the encyclopedia proper only several of what were determined to be the most important alternate forms were entered as "see" references). Index references are to pages upon which any appearance of a name exists, notably in the text of entries under other deities or subjects.

The reader must therefore consult the index under two or more alternate spellings to be sure of locating all references to the appearance of a name: that is, under both "Algonquian" and "Algonquin," both "Texcatlipoca" and "Tezcatlipoca," and both "Viracocha" and "Virococha." The great majority of alternate spellings in the index nevertheless simply refer to the main entry, not to subsidiary appearances under other entries.

The index also contains, as subjects, many ordinary English-language words and phrases, a major reason for the adoption of the word-by-word approach.

Copy Editor: Colin Campbell

Assistant Editor: Matt Gluck

Contributing Editor: Kendra Moshe

Computer Graphics: Raruen Keawpadung

Photographer: Saysunee Yongyod

Design and Production: Saniem Chaisarn

Illustrations: Udon Jandee

Final Editing: Jean Chilton

Project Manager: W.U. Wei

© ***North Star Trust***

First published in 2001 by:

Universal Tao Publications
274/1 Moo 7, Luang Nua,
Doi Saket, Chiang Mai, 50220 Thailand
Tel (66) (53) 865-034 & 495-596 Fax 495-852
Email: universaltao@universal-tao.com

ISBN: 974-87672-5-6
Library of Congress Catalog Number:

Manufactured in Thailand
Second Printing, 2001

All rights reserved. No part of this book may be used or reproduced in any
manner whatsoever without the express written permission from the
author except for brief quotations embodied in critical articles and reviews.

PREFACE

Throughout history, humans have pondered the question of their existence. In nearly every society, part of the answer has included some form of god or goddess involved in the creation of the universe.

This encyclopedia was compiled to give the general reader and scholars easy access to a broad range of mythologies related to deities. In addition to ancient deities, other mythology is included that will facilitate a comprehensive understanding of the deities — so there are entries for spirits, places, festivals, sacred objects, heroes, monsters, demigods and mythical beasts.

The research was extensive, covering a century of book publishing activity. We made use of a large personal library, collected over many years, on this topic. Research was carried out in a number of libraries outside the United States, and the Bibliography includes citations to many books published in those countries. As a result the reader will find deities often missing from standard collections, notably from the Inuit, Native American and African cultures.

At over 10,000 entries, this is the most comprehensive collection of information on this topic. The primary name of the deity is followed by alternate spellings or translations of the primary name. Then in parentheses the group of people (tribes, cultures, civilizations or people who lived in a geographic region) who recognized the deity or mythology is named. All alternate names are then given. All alternate names and alternate spellings are cross-referenced. An explanation of the origin, history and function of the subject of the entry is followed by any needed cross-references to guide the reader to related topics.

A comprehensive index permits direct access to any name by any of its spelling variants, as well as to the religions, cultures and places identified in the text. Also indexed are subjects, especially including those with which a deity is associated; a reader may, for example, locate goddesses of *lightning* or gods represented by *toads* by consulting the respective entries in the index.

My coauthor, Charles Coulter, passed away in 1997 shortly after we delivered this manuscript, which had occupied much of his time and mental energy during his last ten years. I am deeply grateful for his effort.

PATRICIA TURNER • *August 1999*

THE ENCYCLOPEDIA

A

A (Maya People, Yucatan)
A is a death god who is similar to the Aztec god of the dead, Miclantecutli. A major difference is that A presides over the west and his Aztec People, Mexico, counterpart presides over the north or south. His hieroglyph is a skull, a corpse's head and a flint knife used for sacrifices. *See also* Miclantecutli.

A-Kahiwahiwa (Polynesia)
"Fiery Black Clouds." One of the thirteen children of the god of winds, storms and hurricanes, Tawhiri-ma-tea.

A-shih (India) *see* Abheda; Ajita.

Aa (Mesopotamia)
Also known as: *Aah, Aos, Iah, Khensu, Sirdu, Sirrida.*
Aa as a Chaldean deity was known as Aos. Her emblem is a disk with eight rays. As the Akkadian and Sumerian moon goddess she is the consort of the sun god, Shamash. In this aspect, she is the mother of Tammuz. Ra, in Egypt was called Aa (the sun), as a high or sky god. Aa or Aah is another name for the Egyptian moon god, Khensu (q.v.). Aa is also an Egyptian root word meaning "great." Compare Aa to Gula. *See also* Aah; Aos; Shamash; Tammuz.

Aa Sekhemu (Egypt) *see* Aaru.

Aaai (Egypt) *see* Aai.

Aaan (Egypt) *see* Aani; Ab (B).

Aaapef (Egypt) *see* Aai; Apepi; Apophis.

Aaetes (Greek) *see* Medea.

Aah *Ah, Aa* (Egyptian, Middle East)
Also known as: *Aah-Djuhty, Aah Tehuti, Aah Te-huti, Ai, Aos* (Sumerian), *Iah, Khons, Khonsu, Knosu, Thoth.*
One of the names for the god of the moon. Aah is often represented as a regal young man wearing the lunar crescent and solar disc. Aah is also a general reference to the moon, and prefix or suffix to the primary name of a deity. The combination of the gods Aah and Thoth is the god Aah-Djuhty. *See also* Aa; Aah-Djuhty; Agu; Alignak; Aningan; Anunit; Arianrod; Artemis; Khonsu; Thoth.

Aah-Djuhty (Egypt) *see* Aah.

Aah Te-Huti *Aah-Tehuti*
Also known as: *Aah, Thoth* (Egypt).
A manifestation of Thoth, this moon god is represented by an ibis head surmounted by a crescent and a disk. *See also* Aah; Tehuti; Thoth.

Aah-Tehuti (Egypt) *see* Aah Te-Huti.

Aahes (Egypt) *see* Min.

Aai (Egypt)
Also known as: *Aai Gods.*
The Aai are three guardian gods who watch over the sunboat of Ra, in the Ninth Hour or Ninth Division of the underworld known as Tuat. (Tuat is divided into twelve parts, each of which corresponds to one of the hours of the night, and the divisions are called "Field," or "City" or "Hall," or "Circle.") The specific duty of the Aai gods is to destroy the monstrous serpent Apophis. The pylon of the Ninth Division or Ninth Hour is called Aat-shefsheft. It is guarded by the serpent

Ab-ta. The guardians of the corridor are Anhefta and Ermen-ta. Nine gods in mummified forms guard the wall. On the right side of the sun god Ra's boat are four gods of the south. They each wear the white crown, and are grasping a rope that is also held by a man who is called "the master of the front." Between the four gods and the man is a pillar surmounted by a bearded head, with a white crown on it, which is being raised by the rope. There is a hawk-headed sphinx with the white crown on his head, and a bearded head with a white crown on it, resting on his hind quarters. Standing on his back is a human figure that is surmounted by the heads of Horus and Set. In attendance as well are the four gods of the north. They are each wearing the red crown and grasping a rope. The rope is also held by a man known as "the master of the back." Between the man and the four gods is a pillar surmounted by a bearded head wearing a red crown. It is being raised by the rope. A man known as Apu is holding Shemti, the serpent with four heads at each end of his body. Another person is holding Bath, the serpent with a head at each end of his body. On Bath's back stands Tepi the serpent. Tepi has four human heads, breasts and arms and four pairs of human legs at each end of his body. There are also two men holding what might be a rope. On the left side of Ra's boat are sixteen human forms. These forms represent the souls of Amentet, the followers of Thoth, the followers of Horus, and the followers of Osiris. The first four have the heads of men, the second four, the heads of ibises, the third four the heads of hawks, and the fourth the heads of rams. These sixteen beings draw a rope. The rope is attached to Khepri, the double serpent with four heads, two at each end of his body. On one of his folds, the hawk Heru-tuati is perched. Eight human forms called Akhmiu are at the other end of the rope. In the center of this Division, Ra's sun boat is being towed. Marching before Ra are six human forms, four apes and four women who appear to be holding ropes. The three Aai gods are men holding a rope that is thrown over the head and held in the hands of the prostrate ass-eared man who is also called Aai. In front of the man are the serpent Apepi and the serpent-headed crocodile, Shesshes. These beings work magic for Ra on the monstrous Apepi. They beckon the serpent to come to them to be slain. The three drive their spears into Apepi and also destroy the serpent Sesi. They tightly hold the rope of Ai, and do not let the serpent rise toward Ra's sun boat. Text found on the alabaster sarcophagus of Seti I. indicates the Aai gods drive their pikes (spears) into Apophis and also destroy the serpent Sisi. Aai is listed as one of the gods in the Second Corridor of the Tomb of Seti along with the following gods: Aaai, Aakebi, Aana-tuati, Aatiu, Amam-ta, Amen-ha, Amen-khat, Ameni, Ament, Antheti, Aper-ta, Ast, Auai, Ba-Ra, Besi-shemti, Entuti, Hai, Her-ba, Heru, Hetchuti, Huaaiti, Ketuiti, Khenti-Amenti, Khenti-qerer, Khepera, Kheperi, Khepi, Khepis, Maa-uat, Mau-aa, Mauti, Metu-khut-f, Nakiu-menat, Neb-baiu, Neb-senku, Nebt-het, Nef-em-baiu, Nehi, Netch-Baiu, Netchesti, Nethert, Nu, Nut, Qererti, Qu-ba, Ra-ateni, Rekhi, Remi, Seb, Sehetch-khatu, Sekhem-hra, Sekhen-ba, Sekheper-khati, Semaahut, Senk-hra, Senki, Seraa, Serqi, Seshetai, Shai, Shepi, Shu, Tchemtch-hat, Tebati, Tefnut, Tem, Temtemtch, Then-aru, Thenti, Thetaenen, Tuati, Uben, Urshiu. *See also* Abta; Abuk and Inet; Apepi; Apophis; Horus; Khenti Amenti; Khepri; Osiris; Ra; Set; Thoth; Tuat; Tefnut.

Aai Gods (Egypt) *see* Aai.

Aaiu-f-em-kha-Nef (Egypt) *see* Ap-Taui.

Aakebi (Egypt) *see* Aai.

Aakhui (Egypt) *see* Ab (A); Achet.

Aalu (Egypt) *see* Aaru.

Aamu (Egypt)

The Aamu are one of four classes of mortals as described by Horus in the Fifth Division or Fifth Hour of Tuat. The others are Nehesu, Egyptians, and Themehu. *See also* Aai; Horus; Tuat.

Aana (Egypt) *see* Aani.

Aana-tuati (Egypt) *see* Aai.

Aani *Aana* (Egypt)

Also known as: *Dog-faced Ape.*

Aani, a protector deity, is a dog-headed ape sacred to the god Thoth and a companion or associate of Thoth or Khnemu. In the First Hour of the night, unnamed, singing apes opened the way for the great god Ra and guided his boat through the hall to the Tuat. Two ape-gods, Benth and Aana, ministered to Osiris during the Second Hour of the night of the journey to Tuat. Khnemu is also associated with a group of eight apes; four of the apes are collectively called the Bentet apes, who are individually named Aaan, Bentet, Hetet-sept, and Qeften. Their duty was to praise the morning sun. The other four apes are known as the Utennu apes, named Ap, Asten, Kehkeh, and Utennu, and it was their responsibility to praise the evening sun. Aani is generally depicted as an ape, or an ape with the head of a dog. *See also* Aai; Ab; Khnemu; Osiris; Thoth; Tuat.

Aaru (Egypt)

Also known as: *Aa Sekhemu, Aalu, Aat, Sekhet-Aaru, Sekhet-hetep.*

Aaru is a place of bliss for good souls. This is the heaven where the soul (ka) rests after traveling through Amenti (Hades), through Aukar, and being absorbed with Osiris in a place called Ker-neter. References are made in the Book of the Dead where prayers are made for the soul to travel to Sekhet-hetep (possibly another name for Aalu). One must pass through the Underworld to get to this place and it contains either eighteen or twenty-one pylons (towers on either side of temple entrances). The domain of Osiris is sometimes called Sekhet-Aaru and is divided into fifteen or twenty-one Aats (pylons). Each pylon is guarded by demons armed with long knives. Although the Aats are named, not all the guardian gods are mentioned. The Aats are Sekhet Aaru, whose god is Ra-Heru-Khuti; Apt-ent-khet with Fa-akh, whose god is Tu-qa-Aat; The Aat of the spirits, Ammehet, whose god is Sekher-remu; Asset, Hasert whose god is Fa-pet; Apt-ent-qahu, Atu, with Sept; Unt, with Hetemet-bau; Apt-net, with Aa-Sekhemu; Kher-aha, with Hap; Atru-she-en-nesert-f-em-shet, Akesi with Maa-thet-f; Amentet-nefert or Amentet. Aaru is sometimes described as a tower or field of peace. The fields in Aaru are cultivated for food for the dead. *See also* Amentet; Elysian Fields; Ka; Nirvana; Tuat.

Aarvak *Arvak, Arvakr* (Norse; Teutonic)

Also known as: *Early Waker, Frost Mane, Hrim-faxi.*

Aarvak, also called "Early Waker," is one of the horses that pulls Sol the sun in its chariot along its course. His companion horse is Alsvid, "the fleet one," who represents the dawn. The animals were created in Muspells-heim, the land of warmth and brightness. The shield, Svalin, was formed to protect the horses and the earth from the harmful rays of the sun. A third horse, Alsvider, pulls Mani the moon in its cart along its course. Alsvider does not require the protection of the shield because of the weak rays of the moon. Aarvak may be associated with the horse mentioned in tales as Hrim-faxi, who pulled the dark chariot of Nott (Natt) through the heavens. *See also* Alsvid; Austri; Helius (Greek); Hrim-faxi; Muspells-heim; Natt; Nordri; Pegasus (Greek); Sol; Sudri; Westri.

Aat-shefsheft (Egypt) *see* Aai; Ab-ta.

Aati (Egypt)

He is one of the forty-two assessors or judges of the dead. In the hymns to Osiris from the "Book of the Dead," there are twenty-one deities on each side of the hall of the Maat (also called Maati) goddesses. These goddesses may be the goddess Maat in dual form or they may represent the goddesses from the South and North of Egypt. Two goddesses often referred to are likened to the two solar boats called Maaty. Although Aati is named he is not one of the primary deities of Egypt. *See also* Amit; Assessors; Maat; Osiris; Tuat.

Aatiu (Egypt) *see* Aai.

Aats *(Pylons)* (Egypt) *see* Aaru.

Aau (Egypt)

Aau, a jackal-headed mummy, stands at one end of the corridor of the Fifth Division or Fifth Hour (the pylon named Arit) of Tuat where the serpent Teka-hra guards the entrance. The other end of the corridor is guarded by the mummy Tekemi-aau. *See also* Aai; Tuat.

Ab (A) *Ib* (Egypt)

Also known as: *Shahar* (Arab).

The Ab, an amulet representing the heart, is said to contain the soul of Khepri, the immortal self-created god. Khepri, in the form of a beetle is made into an amulet believed to give new life. Ab is also the heart, thought to be the origin of energy, intellect, feelings and emotions. Achet, also known as Aakhui, is an amulet made of red stones or glass. It is representative of the rising sun and is said to give the owner the qualities of the sun god Ra. Another well known amulet is Tyt, a symbol of protection, said to be made from the knot of the magic girdle of Isis. The amulet Weres (Urs) was put under the pillow of the mummy to protect it from being decapitated in Tuat (the underworld). Ab is also the name of one of the numerous gods who minister to Osiris during the Second Hour of the night. Many other amulets were made to represent divine figures, animal figures, body parts (wedjat-eye), and symbols of royalty. Small amulets of the Ba made of gold and semiprecious stones were placed on the breast of the mummy to insure everlasting life. Instructions from the "Book of the Dead" were recited to endow the amulets with magic powers. The upper part of the Ab amulet was sometimes in the form of a human head. Made of red stones, it is inscribed in the chest of a mummy to represent the heart, which was buried in its own container. *See also* Abu; Anni; Ba; Ka; Khepri; Isis; Shahar; Tuat.

Ab (B) (Chaldean, Sumerian)

He is the Lord of Wisdom and Father of the Waters.

Ab-esh-imy-duat *Ab-sha-am-tuat* (Egypt)

Also known as: *Ab-she, Akhen.*

Ab-esh-imy-duat is a monster crocodile who guards the tomb of Osiris in the seventh section (hour) of Tuat (the underworld). In this section, the hidden abode of Osiris is found. It is said that when the great sun god Ra passes the monster, the god mesmerizes the beast with magic words. This allows the deceased Osiris, in the ground under the monster, to raise his head and gaze at Ra, which in turn allows the followers of Osiris to look upon Ra and be restored to life. Another demon crocodile is Ab-she who is said to eat lost souls, also in the Seventh Section or Seventh Hour of Tuat. Another serpent encountered during this portion of the journey, is Neha-hra. He attempts to stop the sun boat when it has reached a shallow junction where it appears to be impossible to go forward. Isis steps in and murmurs magical words; Neha-hra is held back at knife-point by the scorpion-goddess, Serqet and Her-tesu-f. Ra, protected by the serpent Mehen, continues his journey. *See also* Ab-ta; Akeneh; Apepi; Apophis; Ba, Shepes; Tuat.

Ab-ramu (Arabic, Babylonian, Hebrew) *see* Abram.

Ab-sha-am-Tuat (Egypt) *see* Ab-esh-imy-duat.

Ab-she (Egypt) *see* Ab-esh-imy-duat; Akhen.

Ab-ta (Egypt)

Ab-ta is a monster serpent guarding the Ninth Hour or Ninth Division of Tuat. This division is called Aat-shefsheft and here the Aai gods reside with a multitude of interesting beings. The corridor guardians are Anhefta and Ermen-ta and nine deified mummies guarding the wall. On the sun boat's right side are four gods of the South, a pillar with a bearded head wearing a white crown on top of it and a hawk-headed sphinx wearing a white crown. There is yet another bearded head, wearing a white crown with a human figure standing on his back and on top of this figure are the heads of Horus and Set. There are also the four gods of the North wearing red crowns, another pillar with a bearded head atop it, also wearing a red crown. There are two people holding serpents; one serpent, named Shemti, has four heads at each end of his body. He is held by Apu. Someone else holds a serpent with a head at each end of his body. This serpent is Bath, and Tepi, yet another serpent stands on his back. Tepi is equipped with four human heads, breasts, arms and four pairs of human legs. There are two other people who appear to have normal attributes. On the left side of the boat, there is another intriguing group. We find sixteen deities, four with the heads of men, four with the heads of ibises, four with the heads of hawks and four with the heads of rams. A double serpent with four heads is there, along with the well-known Khepri, who has Heru-tuati, the hawk poised on his back. The famous evil serpent, Apepi is there along with Shesshes, the crocodile, who has a tail which terminates in a serpent's head. The serpent Sesi meets his fate in this hour. *See also* Aai; Ab-esh-imy-duat; Abuk and Inet; Akhenet; Apophis; Ra.

Ab-u (Middle East) *see* Abu; Tammuz.

Aba (Choctaw People, North America)
Also known as: "*Great Spirit.*"

Aba is the name of the Great Spirit of the Choctaws. Originally known as mound builders, the Choctaw's important structures were made of wood and erected on huge earthen mounds, sometimes sculpted in the form of exalted animals. In legend, they believed they came from the internal regions of the earth along with grasshoppers. But, because their mother was killed by man, the revengeful grasshoppers persuaded Aba to close the opening and the men remaining inside became ants. The principal tribes known as mound builders are the Cherokee, Choctaw, Creek, Hitchiti, and Natchez who were located in what is now the Mississippi and Ohio regions of the United States. The mound builders originated from three separate cultures: Mississippians, Hopewell and the Adena. Carved stone figures thought to represent heroes, (placed in their wooden temples) and examples of fine engravings have been found on bone and copper (dating from C.E. 1000–1600).

Abaangui (South America) *see* Abaangui and Zaguaguaya.

Abaangui and Zaguaguaya (Guarayo People, South America)

Heroes, possibly divine beings. The brothers Abaangui and Zaguaguaya are culture heroes. A culture hero is a mythological creator figure, often presented in human or animal form, who shaped mortals and endowed them with their material and spiritual heritage.

Abaasy *Abasy* (Yakut People, Siberia)
Also known as: *Chebeldei.*

The Abaasy are wicked spirits from the lower regions, ruled by the great god, Ulu Tojon, or Arson Duolai (ruler of the dead). The son of the Abaasy chief is a cyclops with one eye and seven gigantic iron teeth. All these underworld spirits have one thing in common: they are each partly or fully composed of iron. They are depicted as one-eyed cyclops with seven large iron teeth. *See also* Arson Duolai; Chebeldei; Ulu Tojon.

Ababinili (Chickasaw People, North America)

He is the great or supreme spirit who is possibly a fire or sun god. Ababinili is generally thought of as the life, light, and warmth of spirit.

Abac (Irish) *see* Addane.

Abaeus (Greek) *see* Apollo.

Abaia (Melanesia)

Abaia, an evil eel was said to have caused a flood when a woman caught a fish in his lake. The only survivor was an elderly woman who had eaten a magical fish. In Saddle Island, Melanesia, there is said to be a pool "into which if any one looks he dies; the malignant spirit takes hold upon his life by means of his reflection on the water." *See also* Aokeu.

Abaios (Greek) *see* Apollo.

Abakan-Khan (Siberia) Rain or storm god.

Abanathabla (Middle East) *see* Abraxas.

Abans (Persia) Spirit of iron. Protector of iron miners.

Abantiades (Greek)

The Abantiades are the descendants of Abas, his son Acrisius, and Perseus, his great-grandson by Acrisius' daughter Danae. *See also* Abas (A); Acrisius; Danae; Perseus.

Abaris (Greek)

Priest, messenger, and possibly a Druid. Abaris, the servant of Apollo, in the land of the Hyperboreans, was transported to Greece on a golden arrow to visit Pythagoras. Abaris was the legendary instructor of Pythagoras and was described by Hecateus as a Druid apparently because Abaris had visited the area and had an impressive knowledge of the people and their philosophy. *See also* Aethalides; Apollo.

Abas (A) (Greek)

Renowned warrior. Abas, a former king of Argos, is the son of Lynceus, husband of Aglaia or Ocaleia, father of Chalcodon, twin sons Acrisius and Proetus, and a daughter, Idomene. Another son, Lycrus, was born outside of his marriage. Abas had inherited the magic shield of his grandfather Danaus, which was sacred to Hera. It was seized by Aeneas during his strife with Turnus, the Roman lord of darkness. *See also* Abantiades; Acrisius; Danaus; Hera.

Abas (B) (Greek)

Abas is the son of the great prophet Melampus and his spouse Lysippe. His brothers are Mantius and Antiphates. He married Talaus and had two children, Coeranus and Lysimache. *See also* Lysippe; Melampus.

Abas (C) (Greek)

A centaur, Abas was either the son of Ixion and Nephele or King Celeus of Eleusis and Metaneira. His brothers were thought to be Demophon and Triptolemus. He may have been the friend who traveled with Aeneas from Troy to Italy. His background, though vague, indicates that he was a skilled warrior. In one myth he roused Demeter's ire and was transformed into a lizard. *See also* Aeneas; Demeter; Ixion.

Abasoms (Africa) *see* Abonsam and Abosom.

Abasy (Siberia) *see* Abaasy.

Abathur (Gnostic)
Also known as: *B'haq Ziva.*

Abathur, a divine being known as an Uthra, is an angel. He brought forth another divine being in his own image by contemplating his reflection on black water. This being was named Ptah-il-Uthra. *See also* Ptah-il-Uthra; Uthra.

Abatwa (Africa)

The Abatwa are tiny spirits who hide under leaves of grass and sleep in anthills. They shoot their enemies with poison arrows.

Abderus (Greek, probably Thrace)

In some legends, Abderus is the hero son of Hermes from Opus. He is also said to be the son of Opian Menoetius, which would make him the brother of Patroclus. He was reputed to be the lover and armor bearer of Heracles. Heracles left him to guard the man-eating mares of Diomedes and when he returned he found that Abderus had been brutally ripped apart and eaten.

Heracles built the city of Abde'ra in honor of his friend. The city had the reputation for having a population of intellectually inferior inhabitants. *See also* Diomedes; Heracles; Hermes; Menoetius; Patroclus.

Abdu and Inet (Egypt) *see* Abuk and Inet.

Abel *Abelus, Abil* (Arabic)
Also known as: *Habel, Habil, Habl, Hebel, Hobal* (Persian, Arabic), (Hebrew, Muslim).

In the Hebrew and Christian tradition, Abel is the second son of Adam and Eve. He was the first man to sacrifice a lamb to God. The tale is told that Cain, a farmer, jealous of his brother, Abel, a herdsman and nomad, killed him. In the Islamic tradition, Abel (known as Abil or Habil) is Kabil's (Cain) younger brother. They are the eldest sons of forty children; twenty sets of twins. Abil was about to present his twin sister to Kabil so they could be man and wife. Kabil would not return the gesture by giving his brother his twin sister. The earth was without other females. Abil and Kabil's father, Adam, had been instructed by God to let the brothers marry each other's twin. God demanded to be appeased by sacrifices from the brothers. Abil offered his best ram. Kabil offered wild fruits. He then provoked a quarrel. Satan, standing nearby, was privy to the incident. He offered a large stone to Kabil, who accepted. He took the weapon and smashed his brother's skull. Abil, the first man to die, was buried by Kabil, his brother, and murderer. *See also* Adam; Cain; Eve; Hab'al.

Abellio (Celtic, Gaul)
Abellio, the apple tree god, was worshipped by the ancient Druids as were Robur, the oak tree god; Fagus, the beech tree god; and Buxenus, the box tree god. In the Gaulish "Biliomagus," a number of sacred trees are mentioned; the Oak of Mughna, the Ash of Uisnech, the Yew of Ross and others. *See also* Buxenus; Fagus; Robur.

Abeona (Roman)
She is the goddess who protects the child during his or her first efforts at walking and first departure from home. The city of Rome is protected by Abeona and she is also thought of as the protective goddess of travelers.

Abere (Melanesia)
Demoness. Abere was known as a wild, provocative woman who murdered men. It was said that the mimia reed grew around her to hide her from her victims. She was known for having a number of young female companions. Mesede, the marksman rescued Abere's son from a crocodile and then captured her young women. His jealous wife had the most beautiful of the captives beheaded and thrown into the sea and the other captives were slaughtered. In myth, the original victim's body became hard from the water and resembled a log which was washed ashore. Flies hollowed it out. The hero Morave found it, covered it with skin and made a drum. *See also* Mesede.

Aberewa (Ashanti) *see* Asase Yaa.

Abheda (Buddhist; India)
Also known as: *Mi-che-pa* (Tibet), *Mi-p'yed* (Tibet).
Abheda, meaning steadfast, is a deified mortal, the sixteenth of sixteen arhats (saints). His symbol is the caitya (the stupa which holds sacred relics). This is also the symbol for Kuvera and Maitreya (qq.v.). *See also* Ajita; Medicine Buddhas; Stupa.

Abhijnaraja (Buddhist; Tibet)
One of the Medicine Buddhas (q.v.).

Abhimanyu *Saubhadra* (Hindu; India)
Son of Arjuna, spouse of Uttara and father of Parikshit, the king of Hastinapura. *See also* Arjuna; Parikshit.

Abiku (A) (Yoruba People, Africa)
The Abiku are hungry, thirsty, evil spirits who victimize children. To satisfy their desires, they enter the body of the child and the child can die. To drive the Abiku away, the parents leave food for it and ring bells, which the Abiku dislike. If they rub pepper into open cuts on the child the Abiku will depart to escape the pain. *See also* Abiku (B); Ifa; Olodumare; Olori; Olorun.

Abiku (B) (Dahomey People, Africa)
A forest spirit who can enter the womb of a woman, be born and dwell on earth, die, and be reborn into the same family. If the parents believe their child is an Abiku, they can dedicate the child to a Vodu (god). The Vodu protects the child from being taken back to the forest. In the past, sometimes the child's face would be scarred to deliberately make him or her ugly and unappealing to the spirits. Such a child would often be fitted with iron anklets to hold him or her to the earth or bells to keep them from running away. *See also* Vodu.

Abjaja "Born from a Lotus" (India) *see* Brahma.

Abjayoni (India) *see* Brahma.

Ablathanabla (Gnostic) *see* Abraxas.

Ablu (Etruscan) *see* Apollo.

Aboatia (Africa) *see* Mmoatia.

Abok (Africa) *see* Deng.

Abokas (Malaysia) Home of the dead.

Abonsam (Guinea, Africa)
Also known as: *Abasoms.*
Evil spirits. Water or tree deities. To drive the Abonsam from the village or home and to cleanse the area it was necessary to have four weeks of silence. During this period, it was hoped that the evil spirits would be frightened away. This was followed by a night of creating noise; thunderous sounds by rattling pots, beating sticks together and screaming loudly. They are possibly the same as the Abosom, the spirits of the Ashanti people (q.v.). *See also* Asase Ya; Nyame; Tano.

Abore (Warrau People, Guyana)
A culture hero who learned his skills from Wowta, a frog-woman. She kept him as a slave when he was a young man. He escaped the evil woman by enticing her to a hollow tree full of honey where she became stuck.

Aborigine People — Creation Legend *see* Bunjil; Dijanggawls (Australia)

Abosom *Obosom* (Ashanti People, Africa)
Also known as: Probably the same as *Abonsam.*

Tree or water spirits. There are thought to be several hundred Abosoms who are descendants of Nyame (Nana Nyankopon), a rain god and Asase Ya, his wife. They had four children. The most famous child is the former thunder god Tano who is now known as a river god. Two of the other children are Bia and Ananse. The fourth is not named. *See also* Abonsam; Asase Ya; Nyame; Tano.

Abou (Egypt) *see* Abu.

Abracadabra (Gnostic) *see* Abraxas.

Abraham (Hebrew) *see* Abram.

Abram *Ab-ramu, Abraham* (Hebrew, Christian, Arab), *Ibrahim* (Islamic).

"Father of a multitude." In the Islamic and Hebrew traditions the story is basically the same. The iniquitous King Nimrod, son of Caanan, a shrewd astrologer, foretold the birth of Abram (later to become known as Abraham) by reading the stars. When he was told that a man would be born who would rise up against him, he gathered his advisors together. A plan was devised to alter the promised course of events. A large building would be erected to house all the pregnant women. They were to be held under lock and key. If a woman gave birth to a male child, it was to be murdered. Seventy thousand newborns were slaughtered. Terah, heavy with child and extremely frightened, decided to leave the city. She headed toward the desert and passing along the edge of a valley, she came upon a cave where she sought refuge. Abram was born the next day surrounded by the brilliant light of his countenance. His mother wrapped him in her garment and abandoned him. The baby cried and wailed for sustenance. God sent the angel Gabriel down to the baby with milk. Gabriel devised a method for Abram to have access to the milk by sucking the little finger of his right hand. The infant remained in the cave feeding himself for ten days. At that time not only was he fully grown, but through Gabriel he came to the realization that for him there was only one true god. In the *Old Testament* the story continues that the shepherd Abram, following his god's orders, left Haran (he came from Ur in Babylonia) and went to Canaan. It was here he made a covenant with his god. He was promised that if he followed his command, he would be given the land of Canaan. He was also given the name Abraham. God also promised him a son in his old age. When his wife Sarah gave birth to Issac, Abraham's god tested his faith by asking him to sacrifice the child. (In the Muslim tradition, it is Ishmael, Abraham's son by the slave Hagar, who was offered as sacrifice). As Abraham was about to fulfill his god's bidding, the deity showed him a ram in the bush to be sacrified instead. He was then promised by the god that his seed would multiply like the stars in the heavens. The Hebrew tradition adds to the *Old Testament* version of Abraham's story many "hero" stories. Abraham so detested Chaldean astrology that he smashed his father's idols. His mission in the world was as the spokesperson for one, living god. He was a giant, and a typical culture hero who discovered superior methods of agriculture, the alphabet, and knowledge of magic. He was a healer who used the precious stone around his neck to heal the sick. He also introduced circumcision to his people which became known as "Abraham's seal." Described as a monster with the strength of seventy-four men, Abram died at one hundred and seventy-five years of age. Compare Abram to Brahma; Buddha; Krishna; Zeus; Zoroaster. *See also* Gabriel; Noah; Zam Zam.

Abrasax (Middle East) *see* Abraxas.

Abraxas (Egypt, Semitic, Syria)

Also known as: *Abanathabla, Ablathanabla, Abracadabra, Abrasax.*

Sun god. Abraxas is found in the doctrine of Simon Magus (the "father of Gnostics"). Abraxas and Ildebaoth were serpent symbols with the head of a lion surrounded by rays and were used at Gnostic ceremonies. It is said that the name was created to replace the unmentionable name of the Supreme Being. Basilides, the Gnostic, was thought to have declared that between the unknown Father of All and this world there were interposed a series of 365 heavens corresponding to the days of the year, chief of these being Abraxas. The Persian sun god had this name and in Syria, Abraxas was a form of Iao (Yahveh, or Yahweh). The word Abraxas was used on a seal or amulet to exorcise evil spirits. Sometimes Abraxas is shown with the body of a man, the legs formed of serpents, and holding the shield of Sophia. *See also* Iao; Sophia.

Abrayanti (India) A Krittika sister. *See also* Rishi.

Abru-el (Arab) *see* Adam; Gabriel.

Abruel (Arab) *see* Gabriel.

Absusu (Sumerian) *see* Abtagigi; Ishtar.

Absyrtus (Greek)

Also known as: *Phaethon.*

King of Colchis. An Argonaut. His grandfather is the sun god Helios, his father is Aeetes and his mother is rumored to be one of any number of women including Hecate. He is the nephew of Phaethon, son of Helios and Clymene. *See also* Adon; Aeetes; Helios; Phaethon.

Abt (Egypt) *see* Anhur.

Abta (Egypt) *see* Aai.

Abtagigi (Assyrian, Babylonia, Sumer)

Also known as: *Absusu, Aphrodite, Ishtar, Kilili.*

Goddess of harlots. She is an evil spirit who preys on men. Abtagigi is the name used for Ishtar in her aspect as the patron of sacramental promiscuity. In Babylonia and Assyria she was known as Kilili. The Greek goddess of love, Aphrodite, is said by some to be an aspect of Abtagigi. *See also* Aphrodite; Ishtar; Kilili.

Abtu and Ant (Egypt) *see* Abuk and Inet.

Abu *Abou* (Arabic, Egypt)

Also known as: *Elephantine* (Greek), *Elephantis.*

Light deity. Vegetation deity. Abu was an early Egyptian god of light who was likely worshipped in the city of the same name that was the site of the temples of Khnum (Kneph). The Greek name for this deity was Elephantis from Elaphas who was an Osirian god of light or sun. Abu or Abou can mean father when used as a prefix in the ancient Arabian language. One source says the ancient Sumerians thought of this deity as a vegetation god. In ancient Sumerian texts Abu was a god of vegetation. He is possibly similar to Ab whose hieroglyph is the phallus. *See also* Ab; Khnum.

Abu-Turab (Persia) *see* Ali.

Abuda (Japan) *see* Jigoku.

Abugupham-Bumo (Dhammai People, India)
Abugupham-Bumo and Anoi-Diggan-Juje were the first mortals. Their parents are the sister and brother frogs, Lujjuphu and Jassuju. The first mortals gave birth to Lubukanlung, Sangso-Dungso and Kimbu-Sangtung. *See also* Shuznaghu.

Abuk (Dinka People, Africa)
Abuk is a creator goddess and a goddess of women and gardens. She is an ancestor of Nyalitch, creator of the world and lord of the spirits. Aywil, thought to be the founder of the Dinka religion, learned and taught the people to pray to the supreme god Nyalitch through Deng, who is said to have adopted the role of a divine ancestor, or Abuk. Diing, the first man, opposed this law and after a fight, agreed that Aywil (also a divine ancestor) and his sons would have dominion over the sky and rain and Diing and his sons would rule the food-producing earth. In one myth, Abuk and Garang were the first man and woman. It is said that they were tiny but fully formed creatures made of clay. They were placed in a bean-pot overnight and swelled to full size. Abuk's emblem is a little snake. *See also* Aywil; Deng; Nyalitch.

Abuk and Inet (Egypt)
Also known as: *Abdu and Inet, Abtu and Ant.*
Guardians. Abuk and Inet were two fish that swam on either side of the boat of the sun god Ra to drive away all the evil entities in the water. *See also* Aai; Ab-ta; Apepi; Ra. *Note:* Abuk (Dinka people) is a completely different deity.

Abundantia (Teutonic) *see* Fulla.

Abundia (Teutonic) *see* Fulla.

Abundita (Roman) Farm Goddess.

Abyrga (Central Asia)
This deified serpent or sea-monster lives at the foot of the Tree of Life and dwells in a lake of milk. In some myths he is wound around Sumur, the world mountain. The Garide bird lives at the top of the tree. Compare Abyrga to Yggdrasil.

Abyzu (Gnostic, Semitic)
Abyzu is a demoness nightmare figure who frightens children while they sleep and causes the mother's milk to turn cold. It is said that St. Michael was able to break her spell by coercing her to reveal her forty names. She corresponds to Lamassu (q.v.).

Abzu (Sumerian) *see* Apsu.

Acacallis *Acalle* (Greek)
Also known as: *Chione, Deione.*
Acacallis, a deified mortal, is the daughter of Minos and Pasiphae. Her famous siblings are Androgeus, the famous athlete, winner of all events in the Panathenaea, who was killed by a bull; Ariadne, who aided Theseus in his escape from the Labyrinth; Catreus, who was killed accidentally by his son Althaemenes; Deucalion, an Argonaut; Euryale, the mother of the famous giant and hunter, Orion; Lycastus; Glaucus, who almost died in a honeypot as an infant but was saved by Polyeidus; Phaedra, who committed suicide; and Xenodice. Apollo seduced Acacallis and she bore a son, Miletus. Enraged, her hypocritical father exiled her from Crete and sent her to Libya. She had another son by Apollo named Amphithemis, also known as Garamas, who married Tritonis and became the father of Caphaurus (also called Cephalion) and Nasamon. In some legends she is also the mother of Phylacides and Philandros. Acacallis is also the mother of Cydon by Hermes or Tegeates. It may be that Acacallis was Chione, the daughter of Daedalion. She is possibly the same as Chione, who was probably the real wife of Hermes. *See also* Apollo; Ariadne; Hermes; Minos; Orion; Pasiphae; Theseus.

Academus (Greek)
Also known as: *Echedemus.*
Hero and possibly a god of light. Academus, an Arcadian living in Attica as a guest of Theseus, informed Castor and Pollux (the Dioscuri) where Theseus had incarcerated their sister, Helen. The Spartans treated him with respect and honor while he was alive and spared his property which was a short distance from Athens and is now called Academia. In another version of Helen's rescue, the Dioscuri rampaged through Attica until the people of Deceleia, who disliked Theseus, led the brothers to their sister. *See also* Castor and Pollux; Helen; Theseus.

Acala *Acara* (Buddhist; India, Nepal, Tibet)
Also known as: *Chandamaharoshana, K'ro-bo-mi-gyo-ba* (Tibet), *Mahachandrarosana, Vajrapani.*
Acala is an epithet of the Bodhisativa Vajrapani. He is depicted with four heads. *See also* Vajrapani.

Acalle (Greek) *see* Acacallis; Pasiphae.

Acamas (A) *Acamus, Akamas* (Greek)
Hero. Joint king of Melos. Acamas is the son of the hero Theseus and Phaedra. His siblings are Demophoon and two half-brothers: his father's illegitimate son, Hippolytus, and in some versions, Melanippus, (his mother being Perigune). His father, exiled from Athens, sent Acamas and Demophoon to King Elephenor in Euboea. As adults, they joined Elephenor and fought in the Trojan War, where they were able to rescue their grandmother Aethra, said to be Helen of Troy's slave. Acamas was one of the group who climbed into the belly of the Trojan horse. In one legend, he married Phyllis, declined her father's kingdom (offered as a dowry), and sailed away promising to return. Before his departure, Phyllis gave him a box that she said contained an object sacred to the goddess Rhea. She warned him to open it only if he decided not to return. Leaving her behind, he sailed to Cyprus and decided to settle there. When he didn't return, Phyllis cursed him and hung herself. Eventually, he opened the box. Terrified by its contents, he bolted away on his horse, was thrown to the ground and died by his own sword. A variation of this story is that Acamas and Phyllis were in love and possibly married. He went to fight in Troy and when his ship didn't return with the rest of the fleet, Phyllis, certain that he had been killed, died of grief. Athene, the goddess, transformed her into an almond tree and when

Acamas returned the next day he had only the trunk of the tree to embrace. The same story is told of Demophoon, although some think there were two Phyllises, both princesses, who died of grief and turned into almond trees. In another legend Acamas falls in love with Laodice, daughter of Priam, before meeting Phyllis and either he, or possibly his brother Demophoon, fathered a son, Munitus. In this version, he returned home from the war via Thrace where he fell in love with Phyllis and later deserted her. He comes to the same end in Cyprus where he fell off his horse and was killed by his own sword. Acamas was also known as the companion of Diomedes, king of Argos, whom he accompanied to Troy to demand the return of Helen after her elopement with Paris. *See also* Demophoon; Helen; Helius; Phaedra; Theseus.

Acamas (B) (Greek)
Acamus (B) is the son of the Trojan seer, Antenor, and his wife Theano, a priestess of Athena at Troy. His siblings are Agenor; Archelous; Coon, who was killed in the Trojan War; Crino, a sister; Demoleon, who was also killed in the war; Glaucus, who fought in the war; Helicaon, who also fought and was wounded; Iphidamas, who was killed; Laocoon; Laodamas; Lycaon, who was wounded in the war; Pedaeus, a half-brother; Polydamas, who was accused of being a traitor in the Trojan War, and Polybus. Acamas was a leader of the Dardanian forces in the Trojan War along with Aeneas and Archelous. He was killed by the archer, Meriones, who was also a commander of the Cretan forces. *See also* Aeneas; Antenor; Archelous; Meriones.

Acamas (C) & (D) (Greek)
Acamas (C) was a Thracian captain killed in the Trojan War by Ajax the Greater. Acamas (D), a cyclops, is mentioned as being one of the companions of Hephaestus when he lived on Mount Etna. Three other cyclopes are named, Brontes, Pyracmon, and Steropes. *See also* Ajax the Greater; Hephaestus.

Acan (A) (Chaldean)
Serpent god. Chaldean name meaning "great one."

Acan (B) (Maya People, Yucatan)
God of intoxication. Probably a deity of wine.

Acantum (Maya People, Yucatan) *see* Becabs.

Acara (Tibet) *see* Acala.

Acaragui (Native North American) *see* Niparaya.

Acaryavajrapani (India) *see* Vajrapani.

Acastus (Greek)
Acastus is the Argonaut son of Pelios and Anaxibia or Phylomache. He married Hippolyte or according to some texts, Astydameia, who is elsewhere known as his daughter. His daughters are Laodamia, Sterope, Sthenele and unnamed sons. Against his father's wishes he joined Jason, his father's enemy, as an Argonaut and later participated in the Calydonian Boar Hunt. His wife became infatuated with Peleus, king of the Myrmidons, who rebuffed her advances. Scorned, she lied to her husband and accused Peleus of attempting to seduce her. A short time later while on a hunting trip, Acastus stole Peleus' sword while he was asleep, leaving him defenseless. Peleus was almost killed by centaurs but was saved by the centaur Cheiron. With the assistance of Jason and the Dioscuri, he returned to Iolcus, destroyed the area and murdered the treacherous woman and according to some, Acastus. *See also* Acastus; Argonauts; Calydonian Boar Hunt; Jason; Pelios; Peleus.

Acat (Maya People, Yucatan)
God of Life. God of Tattooers. Acat is one of the Bacabs who are the four wind gods and the four pillars of heaven. They are the sons of Itzama, a hero who later became sacred. Their name list differs but four common names are Yuncemil, Echua, Backlum Chaam, and Chin. Acat is also responsible for the development of children in the womb. *See also* Acatl; Bacabs.

Acatl (Aztec People, Mexico)
Year god. Acatl is one of the four year bearers or year gods. He is in charge of the east region. Acatl is the god of those persons who dwell in this space and time. The other three gods are Tecpatl (north), Calli (west) and Tochthli (south). Possibly the same as Acat of the Maya People, who along with his brothers, the Becabs, were called pillars of heaven. Also similar to the Incan Tahuantin Suyu Kapac who were lords of the four quarters. Acatl corresponds to the skybearer, Tlauixcalpantecuhtli. *See also* Acat; Becabs; Calli; Tahuantin-Suyu-Kapac; Tecpatl; Tochtli.

Acca (Roman)
Acca was the wife of Heracles and is thought to be the counterpart of the Peloponnesian White Goddess, Acco. *See also* Acco; Heracles.

Acca Larentia *Acca Laurentia* (Etruscan, Roman)
Also known as: *Lupa.*
Mother goddess. Some feel that there is only one Acca Larentia, while others believe there are two. In both instances Acca Larentia is the nurse of Romulus and Remus. Acca Larentia (A) was won by Heracles in a game of dice with the king of Rome, Ancus Martius. Heracles was not able to collect his "prize" as the servant had locked her away. Eventually, she married Carutius and became the mother of the Fratres Arvales, twelve sons. When her husband died he left her a substantial estate. Upon her death she willed money to the people of Rome. Her festival, known as Larentalia is a rowdy celebration observed on December 23. Acca Larentia (B) is the wife of Faustulus, who was the shepherd of either the flocks of Numitor or Amulisu. Faustulus found Romulus and Remus, and Acca Larentia was their nurse. *See* Lares; Lupa; Mercury (A); Romulus.

Acca Laurentia (Roman) *see* Acca Larentia.

Acesidas (Greek) Another name for Idas, one of the Dactyli.

Acestes *Acestis* (Greek)
Hero and ancient king. Acestes is the son of the river-god Crimisus and the nymph Segesta or the Trojan woman Egesta. He was the king of Eryx or Drepanum, a Trojan settlement in Sicily. A Trojan War hero, the city of Acesta was named in his honor. During the funeral games after the burial of Anchises, he became the winner of the archery contest. Acestes may have been considered a god of lightning. *See also* Anchises; Crimisus; Egesta; Rivers.

Acestis (Greek) *see* Acestes.

Contents

About the Author 9
Acknowledgements 12
Words of Caution 13

Chapter I
Cosmic Healing

Cosmic Healing Chi Kung in the Universal Tao System.................................... 14
  Foundation of the Universal Tao System 14
  Cosmic Inner Smile and the Six Healing Sounds 15
  Iron Shirt Chi Kung and Bone Breathing 15
  Stages of Mastering Chi.. 16
Four Sections of Cosmic Healing.. 17
  Connecting to Heaven and Earth 17
  Opening the Bridge and Regulator Channels & Extending your Chi Outwards 18
  Opening and Energizing the Governor and Functional Channels 18
  Activating One Finger Art and the Chi Belt 18

Chapter II
Preparing for Cosmic Chi Kung

Preparatory Practices.. 19
Warm up the Stove 19
Transform Sexual Energy.. 20
Filling the Joints with Chi 21
Bone Breathing and Marrow Washing 21
  Bone Breathing.. 21
  Marrow Washing 23
  Heavenly Marrow Washing with Violet Light 23
Microcosmic Orbit.. 25

Chapter III
Cosmic Chi Kung

Opening the Three Tan Tiens to the Six Directions 27
  Introduction 27
  Relaxation, Letting Go, Surrender and Ego 28
  Mind, Organs and Sexual Organs 28
  Opening the Three Tan Tiens 30
Combined Practice.. 32
  Warm Up Exercises 32

Acetes (Greek) *see* Evander (B).

Ach-Chazu (Babylon) *see* Ahhazu.

Achachilas (Aymara People, Bolivia; Andeans)
Also known as: *Machulas.*

Mountain deities. Frost spirits. The Achachilas are objects of reverence and worship found in nature. Many Achachilas are mountain peaks that are often claimed as ancestors and have numerous myths attached to them. When two peaks face one another, they are identified as male and female entities. The People of the Andean highlands identify the Achachilas and Machulas as good and evil spirits and identify them with objects of nature and often with the spirits of famous deceased persons. Compare to Fuji (Japan). *See also* Anchancho; Ekkekko.

Achaeans (Greek) *see* Achaeus.

Achaei (Greek) *see* Achaeus.

Achaemenides (Greek) *see* Odysseus.

Achaeus (Greek)
Also known as: *Achates.*

Achaeus is the hero son of the Thessalian Xuthus (known as "the thievish one") and Creusa. His siblings are Diomede, Ion, and in some legends, Dorus. A descendant of Prometheus and the grandson of the hero Hellen, he had two sons, Archander and Architekes (Architeles). Achaeus and Ion went to Aegialus, in the Peloponnesus, with their father. Ion eventually became the king. Achaeus and allies from Athens and Aegialus banded together and reclaimed the Thessalian throne which had once belonged to Xuthus. The general area then became known as Achaea. Achaeus' sons moved to Argos, married daughters of Danaus and became so renowned that the Argives name was replaced by Achaeans, after Achaeus. *See also* Diomede; Hellen; Prometheus.

Achamoth (Gnostic)

Achamoth was an ousted god hurled into the abyss and deemed a fallen aspect of the lower Sophia. He represents the lower Wisdom; the form where spirit succumbs to matter and becomes the basis of the real world. *See also* Aeons; Pistis Sophia.

Achates (Greek, Roman) *see* Achaeus; Aeneas.

Acheloos (Greek) *see* Achelous.

Achelous *Acheloos* (Greek)

A river god. Shape changer. Achelous is the eldest of the three thousand sons (known as the Rivers) of Oceanus and Tethys. He is also been said to be the son of Sol by Terra or Helios by Gaea. Mating with Calliope or Terpsichore, he became the father of the three Sirens: Leucosia, Ligeia, and Parthenope. He is also thought to be the father of Callirrhoe, who was the mother of Ganymede. Achelous and Hercules were the suitors of Deianira (Dejanira). After a major competition for her hand Achelous was overthrown by Hercules. He turned himself into a serpent, was nearly strangled by his foe and then turned himself into a bull. Heracles wrenched off his horn, which the Naiads presented to the Goddess of Plenty, Amaltheia, who stuffed her treasures in its hollow. It has since become the legendary "Cornucopia." Achelous changed five nymphs into islands and seduced Perimele who was also turned into an island by Poseidon. Achelous is shown with the body of a bull and the head of a bearded and horned man, and sometimes as a snake. To compare to other river gods, *see* Acheron; Amaltheia; Alpheus; Asopus; Calydonian Boar Hunt; Cephissus; Cocytus; Helius; Heracles; Melpomene; Muses; Naiads; Oceanids; Oceanus; Rivers; Sirens.

Acheren (Greek) *see* Acheron.

Acheron *Acheren* (Greek)
Also known as: *Acherusia.*

A river god. Acheron is one of the three thousand sons of Oceanus and Tethys, Gaea, or Demeter. He was also said to be the father of Asclepius by Orphne or Gorgyra. In legend, he was punished and sent to Hades by the gods for providing drinks to the Titans during their battle with the Olympians. A variation of this story is that Acheron was banished to Hades when he had outlived his usefulness on earth. Acheron, the river, is the name of one of five rivers that are said to be connected with Hades. The very name, Acheron, was a synonym used in place of Hades to signify hell and was known as the "River of Woe and Sadness." The other rivers are Cocytus (wailing or groans), Lethe (forgetfulness), Phlegethon or Pyriphlegethon (fire) and Styx (the gods sealed their oaths by this name). The ancient and difficult Charon ferried souls of the dead across the Acheron, Cocytus and Styx rivers. *See also* Achelous; Alpheus; Asopus; Cephissus; Charon; Cocytus; Furies; Inachus, Lether; Oceanids; Oceanus; Rivers; Styx; Tartarus. The Acheron is similar to the Celtic Achren (q.v.).

Acherusia (Greek) *see* Acheron.

Achet (Egypt) *see* Aakhui; Ab.

Achilles *Achilleus*
Also known as: *Pyrrha* (Greek).

Achilles, the principal character of the Homeric epic of the *Iliad*, is the son of Peleus, king of the Myrmidons in Thessaly, and of Thetis, a sea goddess. He is thought to be the father of Neoptolemus (Pyrrhus) by Deidamia. There are various accounts of his youthful years. One version states that his mother, in an attempt to bestow immortality upon him, held him in fire all night, and during the day anointed him with magical potions so that his mortal parts might be consumed. Another account relates that to make him invincible she held him in the river Styx, holding him by his heel, which became the vulnerable part of his body. It had been foretold by Calchas, a famous seer, that Troy could not be taken in battle without Achilles. Thetis, fearing for her son's safety, disguised him as a female and placed him among the daughters of Lycomedes of Scyros, where he was known as Pyrrha. Odysseus, disguised as a merchant came, to the court of Lycomedes under divine inspiration searching for the hero who would conquer Troy. The fair Achilles, looking through Odysseus' merchandise, ignored the feminine merchandise and seized upon the weapons and was said to have discovered that he was a male. His mentors were Cheiron the centaur, and the warrior Phoenix, king of the Dolopes. At the urging of Odysseus, he and his closest friend and lover, Patroclus, joined the Greeks in the Trojan War. It is said that Peleus gave Achilles his golden armor, an ashen spear and two horses to protect him in battle. He became famous for his bravery during the war and for his influence with the gods. During a campaign in Lyrnessus, Achilles slaughtered the family of Briseis and captured her as his concubine. In the tenth year of the war, Agamemnon was instrumental in taking Briseis from Achilles. Achilles then shut himself up in his tent and refused to participate in battle. Patroclus begged Achilles to lend him his golden armor so that he could lead the Myrmidons back into battle. Achilles agreed. Subsequently, Patroclus was slain by Hector, the Trojan prince, who confiscated the armor. Grief-stricken, Achilles arranged a splendid funeral for his friend and had his mother obtain new armor from Hephaistos. After slaying many Trojans, Achilles finally killed Hector by pursuing him around the walls of Troy three times, tying his body to his chariot, and dragging him in the dust to the front of the city. Xanthus, the faithful and immortal horse who had the power of speech, warned his master Achilles of his impending death. The Homeric version of Achilles' death relates that he was slain by an arrow from the bow of Paris, directed by Apollo, which struck him in his heel. Another tells how he loved the daughter of Priam, Polyxena. Hoping to wed her he went among the Trojans unarmed, and was slain by Paris at the temple of Apollo. After his cremation his ashes were placed in Patroclus' urn. For the origins of Achilles' armor, *see* Hephaistos. For the disposition of his armor after his death, *see* Sigurd (regarding vulnerability). He is associated with Helen of Troy and with Aeacus; Aphrodite; Chiron; Peleus; Phoenix; and Thetis. To compare the friendship of Achilles and Patroclus, *see* Enkidu, and Gilgamesh. Compare Achilles to Krishna (India). *See also* Agamemnon; Ajax the Greater; Amazons; Briseis; Calchas; Cassandra; Hector; Iphigeneia; Odysseus; Patroclus, Polyxena; Styx; Zephyrus.

Achilleus (Greek) *see* Achilles.

Achillides (Greek) *see* Neoptolemus.

Achiyalatopa (Zuni People, North America)
Achiyalatopa is a celestial monster, thought to be a knife or feather deity.

Achren *Acheron, Ochren* (Celtic)
Aspects or known as: *Annfwn* (Welsh), *Annwn, Annwvyn, Donn.*

Achren (in Brythonic legend) is the underworld of the ancient Celts. Often called "The Plain of Two Mists," it is very similar to the Greek Acheron (q.v.). In Welsh legend, the underworld is known as Annfwn and is ruled by Arawn. As the Celts accept death as another stage in life, Achren is not a place of hell and damnation, but a place where ancestors gather, and mortals may visit. A place out of human time, a visitor could find it a garden of delights, or a monster-filled nightmare, and could return to earth much older, and could even disintegrate. Achren is not found in a specific location but can be found in many places. Likewise, the routes to reach Achren are innumerable; even sudden understanding can take one there. Although punishment does not exist in this underworld, all is not love and light; conflict exists and is settled by the intervention of a human mediator. *See also* Annfwn; Arawn; Pwyll.

Achtaroth (Assyrian) *see* Asherah.

Achtoret (Assyrian) *see* Asherah.

Achyuta (India) *see* Vishnu.

Acidalia (Greek) *see* Venus.

Acis (Greek) River god.

Acis (Greek)
River god. Acis is the son of Faunas and Marcia, the nymph of the River Stercutus. (Some say his mother is Symoethis.) His siblings are the man-hating Dryas and Latinus, the mortal king. A handsome, young herdsman of Sicily, Acis fell in love with the sea-nymph, Galatea, a Nereid. Polyphemus, a crude, one-eyed giant who also adored the beautiful nymph surprised the lovers in a compromising position (chatting by the shore, in a grotto, or in bed, depending on the myth). Enraged, he yanked a boulder from Mount Aetna and lunged at his rival, crushing his skull. Galatea plunged into the sea to avoid certain death. She gave her loved one immortality by transforming him into the god of a stream that flows to Mount Aetna. His blood formed the stream which bears his name. *See also* Cylcops; Faunas; Galatea; Nereids; Pan.

Acmon (Greek) *see* Oceanus.

Acmonides (Greek) *see* Cyclops.

Acolnauacatl (Mexico) *see* Mictlantecutli.

Acolnauactl (Mexico) *see* Miclantecutli.

Acotzentli (Aztec People, Mexico)
Tree of Life. It gave food for the people during the second age of man. *See also* Legend of the Four Suns.

Acrea (Greek) *see* Rhea.

Acrisius (Greek)
Acrisius, king of Argos, is the son of Abas and Aglaia or Ocaleia and the twin brother of Proetus. Sibling rivalry between the twins began in the womb. His other brother was Chalcodon, king of the Abantes of Euboea. He led the Euboeans in the battle between Thebes and Euboea and was killed by Amphitryon. Chalcodon's people were known as the Abantes. Acrisius married Eurydice, the daughter of the king of Sparta, Lacedaemon. Sparte, or in some versions Aganippe was the father of Danae and Evarete. It was prophetically foretold that Danae would give birth to a son who would slay him. He hid her in a brass tower to protect himself but that did not stop the great god Zeus. He gained access to her in a golden shower, and as a result, she became the mother of Perseus. The fearful Acrisius then encapsuled them in a chest and had it thrown into the sea. The chest landed on the island of Seriphus (Seriphos), and the mother and child were rescued by Dictys, the seaman of Acetes. Danae and Perseus were shipped off to live with Dictys' brother, Polydectes, the king of the country. Eventually, the prophecy became reality when Perseus threw a disc which accidentally hit his grandfather Acrisius in the foot and killed him. The golden shower is said to represent the sun's rays, necessary for fertilization. Another interpretation is the golden shower as a cloudburst that makes the earth fertile. The cloudburst could also represent a sacred marriage between heaven and earth. Compare Acrisius to Balor. *See also* Abas (A); Aganippe; Aglaia; Danae; Dictys; Oenamaus; Perseus.

Actaea (Greek) *see* Nereids; Nereus.

Actaeon (Greek)
Actaeon is the hero son of Aristaeus and Autonoe, brother of Macris, and possibly the grandson of Cadmus. He became a celebrated hunter and hero trained by the renowned hunter, Cheiron, said to be the wisest of the centaurs. Artemis caught him spying on her as she was bathing with some nymphs. Annoyed or embarrassed, she splashed him with water; he changed into a stag and was devoured by his own dogs. Less popular variations of this legend are that Actaeon bragged to Artemis, herself a skilled hunter, that he was the better hunter; irate, she killed him. Another is that Artemis, angry that he wanted to marry her aunt Semele, whom Zeus was wooing, killed him. Yet another version is that Actaeon tried to rape Artemis and she killed him in self defense. *See also* Argus (F); Aristaeus; Artemis; Cheiron; Semele.

Actaeus (Greek) *see* Agraulos.

Actis (Greek) *see* Heliades.

Actor (A) (Greek)
Hero. An Argonaut. There are various genealogies attributed to the hero Actor. As the king of Phocis, he is the son of Deion and Diomede and the brother of Aenetus, Asteropeia, Cephalus and Phylacus. His union with Aegina produced Irus, Menoetius (an Argonaut) and Polymela. He was the grandfather of Patroclus (Menoetius' son). Peleus, king of Myrmidons, who was an Argonaut, killed Actor's half-brother Phocus. Actor purified Pelus and was said to have given him one-third of his kingdom and either Polymela or Antigone for a bride. In another legend, he is the son of Mymidon and Peisidice and brother of Antiphus and Eupolemeia. He became the king of Phtia and was said to have died childless and to have left his estate to Peleus. Yet again, he is said to have had a son, Eurytion, who was a friend of Peleus. It is also said that Eurytion was adopted. For Actor's father's background, *see* Aeolus (A). *See also* Actor (B); Actor (C); Aegina; Argonauts; Patroclus; Peleus.

Actor (B) (Greek)
Actor is the son of Phorbas and Hyrmina and brother of Augeias and Tiphys. He is said to be the father of the twins, Ceatus and Eurytus, known as the Moliones (Molionides) after their mother; though it is also said that Poseidon is their father and Moliones their mother. *See also* Actor (A); Actor (C); Moliones; Poseidon.

Actor (C) (Greek)
Actor, the Argonaut and hero, is identified as the son of either Deion, the Phoenician, or one of the many men named Hippasus. Actor has also been called the son of Poseidon and Agamede. Agamede, celebrated for her knowledge of the healing arts, had two other sons, Belus and Dictys, also by Poseidon. She is the daughter of Augeas and wife of Mulius, an early healer who knew the healing properties of all plants. Actor has also been referred to as the father of Echecles and in other legends, Astyoche. A hero, Actor was said to have been conquered by Turnus, the Roman poet and soldier. *See also* Actor (A); Actor (B); Argonauts; Poseidon.

Acuecueyotl (Aztec People, Mexico)
She is the personification of waves and an aspect of Chalchiuhtlicue (q.v.).

Acyuta (India) "Immovable" *see also* Krishna.

Ad-Ama (Hebrew) *see* Adam.

Adad (A) *Addad, Addu* (Aramean, Assyrian; Babylonian; Canaanite; Sumerian).
Also known as: *Baal of Mt. Lebanon* (possibly), *Baalsamame, Balsamem, Balshameme, Balshamin, Bardad* (Syria), *Belshim, Ber, Bir, Birqu, Birque, Dadu* (Amorite), *Hadad* (Syrian), *Haddad* (Phoenician), *Ilhallubu* (Babylonian), *Ilumarru* (Akkadian), *Iluwir, Ishkur* (possibly), *Iskur, Jashar* (possibly; Hebrew), *Kur-Gal, Kurgal* (Canaanite; "Great Mountain"), *Marri* (Sumerian), *Marru, Martu* (Amorite), *Ramman, Rammanu, Rammon* ("The Thunderer"; Amorite), *Rimmon, Riummon* (possibly; Syrian).
God of Storms and Floods. Prophet. Adad, son of Asherat of the Sea, replaced Enlil when Enlil was promoted to ruler of the earth. As his power could be used for beneficial and for destructive purposes he is both feared and worshipped. He is also a god of justice and punishment. His consort was the storm-goddess, Shala. Adad was the god who carried out the order for the Deluge given by Bel, or as others say, Ishtar. He was also known as the "Lord of Foresight." Adad is usually shown wearing a pointed helmet with his horns mounted on a bull and grasping three-pronged thunderbolts in each hand. See Enlil, or Shamash, who also could reveal the future. Adad is also similar to Hadad of Phoenician mythology. He was possibly merged with Marduk at a later date and he could be the forerunner of Zeus. He is thought to be the Amorite god Martu. Adad might be another name for Balshamin. He is also identified with Imi, Iskur, Mer, Mermer, Nigir, Nimgigri, Nimgirgirri, and Riummon. He is possibly the same as Bel, Ea, Hadad, Ishkur, Jashar, Marduk, Riummon, Yahveh, and Zeus.

Adad (B) (Syrian)
Also known as: *Hadad, Martu* (Amorite).
The spouse of Adargyns, the earth, Adad is a sun god. When husband and wife merged, creativity evolved. In Babylonia-Assyria, Adad was known as a god of thunder, storms and rainfall. *See also* Hadad.

Adad (C) (Assyrian)
The son of Anu, Adad is a god of storms who is associated with Baal and Hadad (qq.v.).

Adad-Ea (Babylonian)
In the Gilgamesh epic Adad-Ea ferried Gilgamesh. He is also credited with ferrying souls across the waters of death to Ut-Napishtim's abode. *See also* Charon; Gilgamesh.

Adam (A) *Ad-ama, Adamah*
Also known as: *Ade, Edie, Edom, Mahre* (Ancient Persian), *Odem* (Arabic, Babylonian, Hebrew, Persian, Syrian).
Adam is said to have been the first human formed by god from dust gathered by the angel Michael. His name may signify Ad-ama "father of the race." Eve (Khavah), the first female, was created from Adam's rib. According to the standard biblical version, Adam and Eve had two sons, Cain and Abel. Disobeying God's instructions, and succumbing to temptation, they were

banished from the Garden of Eden and subsequently held responsible for humans becoming mortal. In some schools of thought, the story of Adam was of Babylonian origin, later repeated in Persian legends. The Arabs differ in thought from the Christians in that Cain was the son of Lilith and not Eve. While the Christians say God created Adam from dust, the Koran speaks of Allah sending four Archangels, (Gabriel, Michael, Asraphel [Israfel] and Asrael [Azrael]) for four handfuls of earth in different colors and texture. Only Asrael brought earth which God molded into the form of man. Adam awoke one morning to find Haiwa (also known as Eve), the first woman. God taught Adam, in Arabic, the names of all the "things" surrounding him. He warned Adam not to eat the fruit from one particular tree. To do so would mean banishment from the paradisical Janna to a life of hardship on earth. Iblis, the evil serpent demon who was hovering nearby in the garden, persuaded Haiwa to eat the fruit. Adam decided to join her. Both fell to earth. In another version Adam begot demons (Shedim and Lilith) originally and it was Lilith who bore Samael, Leviathan, and Asmodeus and the rest. In tales from the Apocryphal or pseudepigrapha legends they were also the parents of the sisters, Luluwa and Aklemia. In an ancient tale, Adam was created by God from the elements of the universe. His spirit was formed from the wind, his thoughts from the clouds, his eyes from the sun, his flesh and bones from the earth and roots, and his blood from water. Adam is symbolized as a pillar or pole. This story is similar to the Akkadian legend of Adapa where the great god is Ea. *See also* Abel; Adapa; Adhibuddha (India); Azazel; Cain; Ea.

Adam (B) *Sabaoth Adamas* (Gnostic)

Underworld god. From text of the post–Christian sect of the Ophites, and referenced in the text of the "Pistis Sophia," Adam is known as Sabaoth Adamas. He is a chief of Archons, the underworld. The god Melchizidek ("Receiver of Light"), opposed Adam. *See also* Hades; Pistis Sophia.

Adam and Balujen (Tinguian People, Philippine Islands)

The sons of the creator Kadaklan (q.v.).

Adamah (Hebrew) *see* Adam.

Adamanthea (Greek) *see* Zeus.

Adapa (Mesopotamian)

Also known as: *Addu* (Aramaean).

Created by the god of wisdom, Ea, to rule over the human race, Adapa is the chief-priest of Eridu, and some say, Ea's son. Fishing one day, Adapa's boat was overturned by the southwest wind demoness, Shutu. Angered, he cursed her and crippled her wings. The celestial deity, Anu, alarmed by the mortal man's power, sent his messenger Ilabrat to summon Adapa to his court. Ea informed Adapa to expect to be greeted at the heavenly gates by the gods Tammuz and Gizida (also known as Ningizzida), who would escort him to Anu and offer him bread and water. Possibly jealous, Ea instructed Adapa to refuse the nourishment, and lying, told him that it would cause his death. Anu instructed him to appear before the great god Ea. The court had to decide if they should kill the powerful mortal Adapa or raise him to the rank of a god. Tammuz and Gizida intervened and explained that since all wisdom had been revealed to Adapa by Ea, he needed only eternal life to become a god. It was decided that Adapa would be made immortal. When he appeared before the gods he was offered bread and water, which unknown to him was the food of everlasting life. Adapa, following Ea's instructions, refused the nourishment. Not only did he lose the opportunity of immortality for all humans but it is said that he also brought illness, disease and death to other humans. The goddess of healing, Ninkarrak (said to be Anu's daughter), was able to cure all the ill effects of his act, except death. Adapa is often called the forerunner of Adam. This myth is similar to that of Yahweh and Adam (qq.v.). Compare Adapa's story to the tale of the Greek Persephone. *See also* Addu; Anu (B); Ea; Ilabrat; Ninkarrak; Tammuz.

Adar (A) (Persia) *see* Atar.

Adar (B) (Akkadian, Semitic)

Also known as: *Atar, Bar, En-ge, Nin-ib, Ninib, Nin-lil, Uras.*

Weather god. Adar is the son of the lord of ghosts and hell, Mul-lil. Known as the "Sun of the South," he controlled lightning and thunder. Adar in Hebrew means "splendid" or "shining." Uras, in Akkadian, means "the shining"; Nin-ib, "the Lord"; and Bar, "the bright" or "living." In Babylonian myth, Adar was another name for Ninib as god of the summer sun. *See also* Ninib.

Adargyns (Syrian)

"The Earth." She is the wife of Adad. *See also* Adad (B).

Adda-nari (Hindu) *see* Addanari.

Addad (Babylon) *see* Adad.

Addanari *Adda-Nari* (Hindu)

Goddess of nature, religion and truth. Addanari uses the same symbols as the Roman Mercury: a circle, cup, sword and magician's rod. She is identified with the Egyptian Isis. *See also* Mercury.

Addane (Celtic)

Also known as: *Abac* (Irish), *Avanc* (Celtic).

A water monster, sometimes described as a dwarf, Addane's abode is Lake Llyon Llion. After causing a great flood, he was dragged from his home by oxen belonging to Hu Gadarn. In a variation, he was killed by Peredur.

Addephagia (Roman)

Goddess of good cheer. She is generally shown as a smiling matronly woman surrounded by emblems of eating and drinking.

Adder (British Isles, Christians, Druids)

Evil serpent deity. The sly and crafty adder is thought by some to be an aspect of Eris, the goddess of strife. The Christians believed that the adder was a form of the devil. And, the Druids carried amulets (adder stones) as charms. An adder is said to have caused the Battle of Camlan (between Arthur and Mordred) and is also said to be the source of power of the ancient goddess Cailleach Bheur. Even though snakes were said not to exist in Ireland, the story is historically documented that the Milesius (natives of Ireland) carried banners with the symbol of a snake twisted around a rod, rather than the usual coat of arms. In Ireland, the adder was depicted as a green snake god. *See also* Arthur; Cailleach Bheur; Eris.

Addittee (India) *see* Aditi.

Addu (Aramaean)
Also known as: *Adad, Adapa, Marduk.*
Storm god. Addu is one of the fifty names that Anu proclaimed should be bestowed upon Marduk. Addu could have been a forerunner of Marduk or he could have merged with Marduk. It is possible that Addu is only an aspect of Adad. *See also* Adad; Adapa; Marduk.

Ade (Hebrew) *see* Adam.

Adee (Haida, Kwakiutl, Tlingit, Tsimshian People, North America)
Also known as: *Idi.*
Semi-divine creature. Adee, also known as the "Thunderbird" is described as an eagle with an extra head on its abdomen. Adee lives in a mountain lake and is strong enough to carry a whale with its talons.

Adekagagwaa (Iroquois People, North America)
A name for the sun as a Great Spirit. He controls the wind god Ga-oh, the thunder or storm god Hino and the god of winter, Gohone. *See also* Hino.

Adharma (India)
Brahma as the destroyer of all things. *See also* Anrita; Brahma; Maya People, Yucatan (C).

Adhibudda (India) *see* Adhibuddha.

Adhibuddha *Adi-buddha, Adhibudda* (Buddhist; India)
Also known as: *Buddha, Swayambhu* (Nepal).
Adibuddha is the primordial Buddha without beginning or end. He was manifested from the syllable AUM, and is self-existent. All things are manifested by him and emanate from him. The Dyhani Buddhas evolved from Adhibuddha. Adibuddha is said to be revealed in the form of a blue flame coming out of a lotus. *See also* Adam (Arabic, Christian, Semitic); Amida; Buddha; Dhyani Buddhas, P'an Ku (China); Purusha; Samantabhadra, Vajrasatwa.

Adhidevatas (India) *see* Devis.

Adhiratha (India) *see* Radha.

Adi (India) A shape changing demon. *See also* Vasistha.

Adi-Buddha (India) *see* Adhibuddha.

Adi-Pati (India) *see* Ganesha.

Adi-Siki-Taka-Pikone-no-Kami (Japan) *see* Three Goddesses of Munakata.

Adit (India) *see* Aditi.

Aditi *Addittee, Adit.* (Brahmanic, Hindu, Vedic; India, Iran)
Also known as: *Deva-Matri* (Mother of the Gods), *Devaki* (Inca People), *Shakti.*
Aditi, the "Mother of Worlds" is said to be self-formed. Originally, she was the mother of the early Persian Asuras and Asuris (demons), and the gods and goddesses known as the Suras and the Suris. Later, she was considered the mother of all gods. In some texts, she is called the daughter of Daksha, the wife of Kasyapa and mother of Vishnu in his avatar as Vamana. In her avatar as Devaki, she gave birth to Vishnu in his avatar as Krishna. For this reason, Vishnu is sometimes referred to as Aditi. In other texts she is the daughter of Vasus the god of wealth, the sister of the Aditya, the wife of Vishnu and mother of the Rudras. She is also portrayed as the mother of Daksha, and the mother of Indra, or the attendant of Indra. Danu (Diti) is said to be her sister and rival. There are indications that she could be the mother of Agni, the fire god. More frequently, she is known as the mother of the Adityas, a group of six, seven, eight, or twelve gods. Varuna is known as chief of the Adityas. In one well known myth, she has twelve children and she throws one of them, Martanda (the sun) also known as Vivasvat, into the sky. Her son, Indra, is said to have given his mother earrings which appeared on the water's surface when the gods churned the ocean. These earrings were stolen by the demon Naraka and returned to her by Krishna. Aditi is often invoked with Mitra and Varuna for protection, freedom from disease, and forgiveness from sin. Aditi has many titles; among them are; "The Boundless Whole," "Eternal Space," "Mystic Space," "Cosmic Space," "The Celestial Virgin," and "The Supporter of the Sky." She is invoked for the cure of headaches, epilepsy and insanity. The goddess Devaki is an incarnated form of Aditi. There is a close correspondence between Aditi and the Tibetan goddess Tho-ag, also spelled Tho-og, who is known as "The Eternal Mother," "Space," "The Eternal Ever-Present Cause of All," and "The Form of All Existence." In one description, Aditi is described as an earth cow milked by the earth goddess Prithu. Her milk appeared in the form of grain and vegetables. Aditi as the "Boundless Whole," or "Cosmic Space" and similar titles, represents infinite space. Her children, the Adityas symbolize the stars. Aditi corresponds with the goddesses Vach and Diti (also known as Danu). For information about Diti, *see* Maruts. *See also* Adityas; Asuras; Daksha; Devaki; Devis; Indra; Kasyapa; Krishna; Maruts; Mitra; Rudra; Shakti; Surya; Vach; Vamana; Varuna; The Vasus; The Vedas; Vishnu; Vivasvat.

Aditya (India) *see* Adityas.

Adityas, The *Aditya* (singular), *Agni* (Hindu, Vedic; India, Persia)
Originally the Adityas, known as great warriors, thought to be of Persian origin, were a triad of three divinities: Varuna (guardian of the night), Mitra (guardian of the day), and Angra Mainyu. In time, the deities of the triad changed to Agni, Vayu and Surya and then to Agni, Indra and Surya. At a later date they were the six, seven, eight or twelve sons of the goddess Aditi. Immortal sun gods, their element was eternal light. In one record, Aditi has seven sons: Ansa, Aryaman, Bhaga, Daksha, Mitra, Surya and Varuna. Dhatri, Indra, Martanda, Savitri, and Vishnu were added later, increasing their number to twelve. The leader of the Adityas was Varuna. Martanda the sun, also known as Vivasvat, was born from a dead egg and thrown into the sky by his mother. Groups of Vedic gods, like the Adityas, Maruts, Vasus and Ribhus, often appear as rays of the sun, as stars or as constellations. They are sometimes spoken of in human form or as having been ancient sacrificers. In astrological traditions, the number of Adityas is given as twelve. This identifies them with the positions of the sun in each of the months of the year and with the astrological signs. Compare the

Adityas to the Amesha Spentas (Persia). *See also* Adita; Angra Mainyu; Bhaga; Daityas; Daksha; Devaki; Dhatri; Indra; Kasyapa; Mitra; Parjanya; Pushan; Ribhus; Sakra (named by some as an Aditya); Savitri; Surya; Varuna; Vasus; Visasvat; Vishnu; Vrita.

Adlet (Eskimo People, Canada and Greenland)
Also known as: *Erqigdlit.*
An Eskimo woman who was the spouse of a red dog bore him ten offspring. Five of the children were dogs who were put in a boat and set to sea. They are the ancestors of the Caucasians. The other five offspring are blood-drinking monsters known as Adlet. Their offspring are the Erqigdlit.

Adlinden (Eskimo) *see* Adlivun.

Adliparmiut (Eskimo) *see* Adlivun.

Adlivun (Eskimo People)
Also known as: *Adlinden.*
Adlivun, the home of the sea goddess Sedna is located at the bottom of the ocean. It is the place of judgment for mortals who died a non-violent death. They stay in Adlivun for one year. Guarded by a huge dog, Adlivun can only be reached through a shaman known as an angakok. The Greenland Eskimo people say that all the dead, except murderers, eventually reach Adliparmiut. Located further away than Adlivun, it is a dark and stormy place, but it is not as bad as Adlivun. In some myths it is said that spirits from Adlivun, dressed in old clothes, bring disease and death to their villages. *See also* Agoolik; Aipaloovik; Nerivik; Sedna.

Ad'meta (Greek) *see* Admete.

Admeta (Greek) *see* Admete.

Admete *Ad'meta, Admeta* (Greek)
Admete, a deified mortal, is the daughter of Eurystheus and Antimache, and a priestess of Hera's temple. Hippolyte, the queen of the Amazons, owned a girdle (belt) that Admete coveted. Her father, who designated the twelve labors of Heracles, made Heracles fetch the girdle as his ninth labor. Initially, this labor did not seem taxing. Heracles and his friends docked their ship at Themiscyra. Hippolyte boarded, they entertained one another and she promised him the belt. The goddess Hera, aggravated at the ease of the transaction, disguised herself as an Amazon and spread the rumor that Heracles had abducted their leader. The warrior women attacked the ship and Heracles, thinking he had been duped by Hippolyte, killed her and took the belt. *See also* Eurytheus; Hera; Heracles; Hippolyte.

Ad'metos (Greek) *see* Admetus.

Admetus *Ad'metos* (Greek)
Admetus, a deified mortal, and the king of Pherae, is the son of Pheres and Periclymene (Clymene). His maternal grandfather, Minyas, was said to have built the first treasury. His siblings are Idomene, Lycurgus, and Periopis. He joined his cousin Jason's Argonauts and both were members of the Calydonian Hunt Club. In some legends, Jason gave Pelias' daughter Alcestis to Admetus to marry after he helped him reclaim his father Aeson's throne from Pelias. The more popular version is that Zeus sent Apollo to work in Admetus' court for a year as part of his punishment for slaying the cyclops. Admetus was extremely kind to the god, and Apollo, in gratitude, insured that his cattle (or ewes) all bore twins. Pelias, the father of Alcestis, a beautiful and popular woman, consented to her marriage to Admetus provided that he pick her up in a chariot pulled by lions and boars. Apollo insured that Admetus could keep the promise. It is said that Admetus neglected to offer the traditional sacrifice to the goddess Artemis prior to his marriage. On his wedding night, instead of finding his wife in bed, he found the bed full of snakes. Again, Apollo came to the rescue and placated Artemis. Later, after having two children, Eumelus and Perimele, Admetus fell ill. The Fates, dying to destroy Admetus, promised to spare his life, after Apollo, or in some myths, Zeus, intervened and it was agreed that he would be saved if a family member would voluntarily die in his place. Admetus asked his elderly parents, but they refused. So, Alcestis, out of love for her husband, swallowed poison. In some tales Heracles arrived and rescued her from death and in others Persephone, queen of the underworld, sent her back to the world. Admetus became a god when Apollo gave both him and his wife immortality. *See also* Alcestis; Apollo; Argonauts; Artemis; The Fates; Jason; Pelias.

Adn *Adan, Aden, Dar al Thawab* (House of Recompense); (Islamic)
Good souls will live in mansions in this paradise. *See also* Eden.

Adonaios (Greek) *see* Adonai.

Adon (A) *Adonai* (Semitic)
A title of honor meaning "lord." In the Old Testament Adonai is substituted for the Hebrew tetragram YHWH. *See also* Adonis.

Adon (B) (Middle East) The brother of Astarte (q.v.).

Adonaios (Greek) *see* Adonis.

Adonay (Greek) *see* Adonis.

Adonia (Greek)
A festival following harvest to mourn the death and celebrate the rebirth of Adonis (q.v.).

Adonis *Adon* (Egypt), *Adonai* (Hebrew), *Adonay, Adonaios, Aidoneus*
Also known as: *Alevin, Emut* (Egypt), *Hey-Tau* (Egypt) (Phoenicia, Syrian, later, Greek).
Of Semitic origin, the worship of Adonis was widely spread throughout the ancient world. Adonis is the son of Cinyras who was the king of Paphos in Cyprys and Cenchreis or Metharme, or the son of Phoenix and Alphesiboea, or the son of Cinyras and Cinyras' daughter Myrrha (Smyra). The prevalent myth is that Cinyras, himself a handsome man, bragged that his daughter Myrrha (Smyra) was more beautiful than Aphrodite. Incensed, Aphrodite made Myrrha, under the influence of wine, seduce her father. Cinyras, angry when Myrrha became pregnant, chased her with a sword. The gods changed her into a myrrh tree which eventually split open revealing the infant Adonis. To save the child from being slain by his father, Aphrodite stole him, hid him in a box and entrusted him to Persephone. When Persephone opened the box and saw the beauty of the

child she decided to keep him for herself. Aphrodite appealed to Zeus to judge who should keep Adonis. In one rendition, Zeus appointed the muse Calliope to be the mediator. It was decided that Adonis would spend equal portions of the year between the goddesses, Aphrodite in the celestial realm and Persephone in the underworld. Furious, Aphrodite caused the death of Calliope's son, Orpheus. Aphrodite and Adonis had two children, a son Golgos, founder of Cyprian Golgi and a daughter Beroe, founder of Beroea in Thrace. Some say that Adonis not Dionysus was the father of Aphrodite's son Priapus. It is said that Adonis was killed by a boar while hunting. A variation is that the boar was a weapon of the god Ares who, jealous of Aphrodite's love for Adonis, killed him. Identified with Eshmun (Phoenicia), Tammuz (Babylon) and Osiris (Egypt). Adonis was considered a prototype of Hay-Tau. The story of Adonis and Aphrodite is similar to Diana (of the Wood) and Virbius. The rivalry between Aphrodite and Persephone for the love of Adonis is similar to the rivalry of Artemis and Phaedra for the love of Hippolytus. The gods Diarmuid (Celtic), Osiris and Tammuz were all associated with fertility and killed by boars. A large stone carving found at Ghineh portrays Adonis at rest with a spear awaiting the attack of a boar while Aphrodite is seated as though in mourning. The boar represents the slayer and the slain. Following the annual harvest a festival known as Adonia is held to mourn the death and celebrate the rebirth of Adonis. *See also* Angus (Celtic); Aphrodite; Ares; Calliope; Cinyras; Naiads; Persephone; Priapus (A).

Adranos (Italy) *see* Adranus.

Adranus *Adranos* (Sicilian) An ancient deity of Italy.

Adrastea (Greek) *see* Adrastia.

Adrasteia (Greek) *see* Adrastia.

Adrastia *Adrastea, Adrasteia, Adrestea* (Greek)

Nymph of fate. Adrastia, a nymph of Crete, is a daughter of the beekeeper Melisseus and sister of the nymph Ida (also called Io) of the Cretan Mount Ida. It has been said that their father, Melisseus, is also their mother, Melissa the goddess, the Queen-bee who annually kills her male consorts. Adrastia and Ida were given the responsibility to care for the infant Zeus after he had been left in Crete by his mother Rhea because she was frightened that Cronus, her brother who was also her husband, would kill him. They fed the infant milk from the goat Amaltheia and probably honey, considering their origins. To keep Cronus from hearing the baby cry, the artistic Curetes, who assisted them, beat their shields with swords. In another version Adrastia is the goddess of fate who was later called Nemesis. Amaltheia (meaning "tender") the maiden-goddess; Io, the nymph-goddess; and Adrastis ("the inescapable one") are one of the moon-triads. Adrastia gave her charge a beautiful ball which Aphrodite, the goddess of love, later used to try to bribe her son, Eros. Adrastia may be the same as Nemesis and may have been another name for Rhea. *See also* Adrastis; Amaltheia; Cronus; Curetes; Rhea; Zeus.

Adrastos (Greek) *see* Adrestus.

Adrastus (Greek) *see* Adrestus.

Adrestea (Greek) *see* Adrastia.

Adrestus *Adrastos, Adrastus* (Greek)

King of Argos. Adrestus, the king of Argos, is the son of Talaus and Lysimache, though some think that his mother was Eurynome or Lysianassa. His siblings are Astynome; Eriphyle, who with her husband was killed by their son; Mecisteus; Aristomachus; Metidice; Pronax; and Parthenopaeus, one of the Seven Against Thebes. Adrestus married his niece Amphithea, the daughter of his brother Pronax, and became the father of Aegialeus; Aegialeia; Argeia, who was killed by Creon; Cyanippus, a king of Argo; Hippodameia; and Deipyle. Adrestus was the leader and thanks to his magic winged horse Arion, he was the only survivor of the Seven Against Thebes. This campaign was facilitated to aid Polynices, the son of Oedipus, gain the throne of Thebes from his brother, Eteocles. Since the city had seven gates, it was decided that each side would post a hero at each gate. The seven attackers were Adrestus; Polynices; Tydeus (Tydus) of Calydon; Capaneus, the nephew of Adrestus; Hippomedon, the cousin or nephew of Adrestus; Parthenopaeus, the Arcadian chieftain and brother of Adrestus; and Amphiaraus, the brother-in-law of Adrestus and the greatest prophet of his time, who knew the event would fail. The Thebans defending the city were Actor, Hyperbius, Lasthenes, Melanippus, Megareus, and Polyphontes. The brothers, Eteocles and Polynices, ended up in one-on-one combat and destroyed one another fulfilling the curse of their father, Oedipus. It was a barbaric battle and although the deities Athene and Zeus were on hand, for the most part they merely observed the mortals at war. Ten years later, the sons of the Seven Against Thebes decided to avenge their fathers. This group was known as the Epigoni ("those who come later"). In this battle, Aegialeus, the son of Adrestus, was killed and Adrestus, an old man, died of grief. Seven Against Thebes is known as one of the main episodes in the Theban cycle of myths. The list of attackers varies slightly. Some say that Meciteus, the brother of Adrestus was one of the group and that Tydeus was excluded. *See also* Adrastia; Amphithea; Apsyrtus; Eurydice (C); Hippodamia (A); Oedipus.

Adrija (India) "Mountain Borne." *See also* Parvati.

Adrika (India) *see* Apsarases and Satyavati.

Adrisyanti (India) *see* Parashara.

Adsullata (Celtic)

She is a river goddess and patroness of the river Savus in Noricum.

Adu Ogyinae (Ashanti People, Africa)

The first people to inhabit earth came from holes in the ground made by a worm. Seven men, some women, a dog and a leopard were created. Their leader was Adu Ogyinae.

Adununkisum *Uyungsum* (Saora People of India)

Sun god. *See also* Angajan; Babusum; Bomersum; Ilinbongasum; Labosum; Ringesum; Tobardasum.

Aeacides (Greek) The descendants of Aeaucus (q.v.).

Aeacus *Aiakos* (Greek)

Aeacus, the king of Aegina became a demi-god and a judge in the underworld. He is the son of Zeus and Aegina, or possibly Europa. He married Endeis, the daughter of Cheiron, and fathered Peleus and Telamon, and another son, Phocus, by the nereid Psamathe. He became the grandfather of Achilles and Ajax. His sons, Peleus and Telamon, killed their half-brother Phocus, and the population of Oenone (Oenopia) was decimated by the plague; ants covered everything. In other myths it is written that this tragedy was the consequence of Pelops' murder of Stymphalus or Aegeus' treacherous acts toward Androgeus. Nonetheless, Zeus transformed the insects into humans, whom Aeacus called the Myrmidons (ants). Some legends say that Aeacus, the son of Aegina, as a young man, lived alone on the island. Lonely, he prayed for companionship; his prayers were heard; the ants were converted to mortals. He renamed the island Aegina after his mother and became king. Aeacus, Apollo, Poseidon and others built the walls of Troy. While they were working, they were attacked by three snakes. Two of the reptiles died and the third attacked the section of the wall built by Aeacus. Apollo correctly interpreted this incident as an omen that Aeacus' descendants would wreak havoc over Troy for the following thirty years. After his death, Aeacus, renowned for his integrity, was made a judge in Hades along with Minos and Rhadamanthys. Other myths say that he was a lonely gatekeeper. The descendants of Aeacus are known as Aeacides. *See also* Aegina; Ajax the Greater; Cheiron, Europa; Hades; Minos; Myrmidons; Peleus; Rhadamanthys; Styx; Telamon.

Aeaea (Greek) An epithet of Circe (q.v.).

Aebh *Aobh* (Celtic; Irish)

Goddess of mist (or personification of mist). Foster daughter of Bodb Dearg, and wife of Ler. Her three children were changed into swans by her sister, Aeife (or Aoife). *See also* Bodb Dearg; Ler.

Aeculapius (Greek, Roman) *see* Aesculapius.

Aed *Aedh, Aodh* (Celtic)

Also known as: *Hugh.*

Possible weather god. Son of Dagda. Slain for seducing Conchean's wife. As Hugh he was changed into a swan by Aeife. In one version Aedh was the mortal son of Eochail Lethderg, Prince of Leinster. He was carried off by two Sidh-women. After escaping their clutches he was restored to human life by St. Patrick.

Aedh (Celtic) *see* Aed.

Aedon *Aedon* (Greek)

Also known as: *The Nightingale.*

Aedon was either the daughter or wife of Zethus (king of Thebes), and mother of Itylus, whom she murdered accidentally, mistaking him for her nephew Amaleus, the son of Niobe. In a variation; Aedon is the daughter of Pandareus and Harmothoe (Hormothoe). Intensely jealous of her sister, Niobe, who is adored by her six sons and six daughters, she attempts to murder her sister's son, Sipylus, and kills her own son, Itylus by mistake. Grief-stricken, she attempts suicide, fails, and is transformed into a nightingale. It is said that the mournful song of the bird is Aedon lamenting her dead son. In another myth, she is the wife of the artist, Polytechnus of Colophon. Here, Aedon is an artist as well and it is said that the competition between the couple caused bitter quarreling. Polytechnus further enraged his wife when he allegedly raped her sister, Chelidon. In revenge, the two women killed his son, Itys, and gave his flesh to Polytechnus as food. Appalled, Zeus turned them all into birds. Aedon became a nightingale, Chelidon, a swallow, Polytechnus, a woodpecker, her father, Pandareus, an osprey, her mother, Hormothoe, a halcyon, and her brother, a hoopoe (an Old World bird, with patterned plumage, a fan-like crest, and a slender, down-ward curving bill). *See also* Niobe; Tereus; Zethus.

Aeegeus (Greek) *see* Medus.

Aeeiouo (Coptic)

This is one of the gods Jesus is supposed to have prayed to. *See also* Pistis Sophia.

Aeeta (Greek) *see* Aeetes.

Aeetes *Aeeta* (Greek)

Aeetes, king of Colchis was the son of Helios and Perseis (Perse), and the brother of Perses, Pasiphae who gave birth to the monster Minotaur, and Circe the sorceress. His first marriage to the nymph Asterodeia resulted in the birth of Chalciope (also known as Iophossa) and perhaps Absyrtus (also spelled Apsyrtus.) Others feel that Absyrtus was the son of Aeetes and his second wife, Eidyia (daughter of Oceanus), by whom he became the father of the sorceress and moon goddess, Medea. Aeetes was known as a cruel leader and his people were said to be barbarians. He lived in a marvelous palace built by the famous smith and artisan, Hephaistos. Phrixus arrived on the back of the golden flying ram trying to escape from his wicked stepmother and eventually married Chalciope. The ram was sacrificed and its fleece entrusted to Aeetes, who had it guarded by the monster Argus. When the hero Jason arrived to claim the fleece, Aeetes initially resisted but later gave Jason an extremely difficult task to perform before handing over the magic fleece. Aeetes was paranoid because an oracle had said that he would die at the hands of a foreigner. He also feared that one of his sons would kill him as they had befriended the Argonauts, who as outsiders were a worry to him. It was his daughter Medea who magically arranged for Jason to capture the fleece and who eloped with the Argonaut. Aeetes was deposed by his brother, Perses, but Medea returned to Colchis, killed her uncle and restored her father to the throne. Aeetes death is questionable. In some versions, he is cruelly murdered by Medea and Jason, or by Medea's son, Medus (Medeius), and in other versions he is killed during a fight with the Argonaut Meleager. This is part of the story of Jason and the Argonauts. *See also* Apsyrtus; Argus (D); Chalciope; Golden Fleece; Hephaistos; Helius; Jason; Oceanids; Pasiphae; Phrixus.

Aega (Greek) *see* Aex.

Aegaeon *Aegeon* (Greek)

Also known as: *Briareus, Obriareus.*

According to the Olympian Creation Myth, the weather god Aegaeon was one of the first children born of the sky god Uranus and his mother, Gaea, although Poseidon has been called the father. His siblings were Cottus and Gyges. They were said to be semi-humans giants, each with one hundred hands and some say each had fifty heads. Following their births came the three cyclopes: Brontes, Steropes and Arges. Aegaeon was called Briareus, meaning strong, or Obriareus by the gods and Aegaeon by mortals. The three brothers were known as the Hecatoncheires and the Centimani. Briareus is said to represent hurricanes; Cottus, volcanoes; and Gyges, earthquakes. The brothers assisted Zeus in his battles with the Titans, but not willingly. Aegaeon (Briareus) was chosen to arbitrate in a contest between Poseidon and Helios over the ownership of Corinth. He divided the isthmus between the two. Aegaeon represents violent seas or storms. Compare to the storm deities and destructive natural forces: harpies and chimaera. *See also* Aegaeon; Briareus; Chaos; Cyclopes; Gaea; Hecatonchires; Tartarus; Titans.

Aege (Norse; Teutonic)
This little known god of the sea was once an enemy of the Aesir, but later gave feasts for them in his golden hall.

Aegeon (Greek) *see* Aegaeon.

Aeger (Teutonic) *see* Aegir.

Aegeria (Roman) *see* Egeria.

Aegeus (Greek) *see* Aegis.

Aegiale (Greek)
One of the Heliades. Daughter of Apollo or Helios and Clymene. *See also* Aegle (A).

Aegialeia (A) (Greek)
She is the daughter of Adrastus and Amphithea. Her siblings are Aegialeus, Argeia, Cyanippus, Deipyle and Hippodameia. She married Diomedes and later had an affair with her husband's friend's son Cometes. *See also* Adrestus; Amphithea; Heliades; Hippodameia; Sthenelus.

Aegialeia (B) (Greek)
This is an older name of the city of Sicyon.

Aegialeius (Greek) *see* Aegialeus.

Aegialeus (A) (Greek)
He is the son of Inachus the river god who was also and first king of Argos and his father's sister, Melia. His siblings are Io, Hera's attendant, and Phoroneus, who was the first to erect an altar in honor of Hera. *See also* Inachus; Melia.

Aegialeus (B) (Greek)
He is the son of Adrestus and his father's niece Amphithea. His siblings are Aegialeia, Argeia; Cyanippus (he may be his son and not his brother); Deipyle; and Hippodameia. Aegialeus was the only one of the Epigoni, who are the "Sons of the Seven against Thebes," to be killed. His father was the only survivor of the "Seven Against Thebes." *See also* Amphithea; Apsyrtus; Phoroneus.

Aegimius (Greek)
He was the progenitor and king of the Dorians.
Aegimius' paternal grandparents were Hellen and the nymph Ortheis (Orseis). His father was Dorus and his mother was one of Cretheus' daughters. His brother, Tectamus, became the king of Crete. In conflict with the Lapiths (*Lapithœ*) of Mount Olympus, Aegimius called upon Heracles for assistance. The demigod led the Dorians in battle and defeated the Lapiths, killing Coronus. In payment, Aegimius offered Heracles a third of his kingdom. Heracles refused but requested Aegimius to hold it in trust for his sons. After the death of their father, the Heraclids lived in Doris and assisted the Dorians in their invasion of the Peloponnesus. Aegimius' sons, Pamphylus and Dymas, were killed. Subsequently, the Dorians honored the men by naming three main divisions of their people for them and for Hyllus. *See also* Coronus; Heracles.

Aegina *Aigina* (Greek)
A river nymph, Aegina is the daughter of the river god Asopus, and Metope. She has nineteen sisters and three brothers. Impregnated by Zeus, possibly in the form of a flame, he whisked her to the island of Oenone (Oenopia), where she gave birth to a son, Aeacus. Her father, anxious to know who abducted his daughter, manipulated the king of Corinth, Sisyphus, into telling him that the perpetrator was Zeus. This disclosure is thought by many to be the reason that Sisyphus ended up in Hades, doomed for eternity to push a huge boulder to the top of a hill, only to have it roll down again. Zeus had to throw thunderbolts at the bereft father to end his persistent haranguing of the god. The jealous goddess Hera dropped a snake into Aegina's water supply and killed the woman. In time, her son Aeacus renamed the island Aegina, in honor of his mother. The island of Aegina became the home of the Myrmidons, the ants who were changed into mortals by Zeus. According to some, Aegina was also the mother of Menoetius by Actor. There are myths that say that Europa and not Aegina was the mother of Aeacus. Compare Aegina to Europa. To compare to women who were seduced by Zeus in other forms; *see* Antiope, Danae, Europa and Leda. *See also* Actor (A); Aeacus; Asopus; Hera; Menoetius; Pelasgus (B); Sisyphus.

Aegipan *Aigi'pan* (Greek)
Also known as: *Pan.*
Some authorities say Aegipan was another name for Pan, but early writers said that he was a son of Zeus and the nymph Aex or the goat Boetis. Aex, the daughter of Pan or the sun god Helius may have been a goat and not a nymph. It was the hide of Aex or Amaltheia which was used to make the sacred Aegis of Zeus. Aegipan assisted Hermes in recovering the sinews belonging to Zeus and stolen by Typhoeus. Aegipan is either the constellation Capricorn or Capra. He is sometimes shown as a goat with the lower body of a fish. *See also* Aegis; Aegisthus; Almaltheia; Hermes; Pan; Typhon for other goat-related myths.

Aegir *Aeger* (Norse; Teutonic)
Also known as: *Alebrewer, Gymir, Hler.*
Aegir, "master of the sea," was the son of the giant Fornjotr (also known as Farbuti). His siblings were Kari (the air) and the god of evil, Loki (fire). A giant, he married the pale, sea goddess of death, Ran (robber), who in some legends, is also his sister. They had nine daughters, also giants, who represented the waves and were all the mothers of Heimdal, the defender of heaven. Although Aegir was not included in the ranks of the gods, he was very friendly with them. And, as a brewer for the gods, he often entertained, especially during flax harvesting, in his sea palace in the western ocean of Vanaheim by the island of Hlesey (also known as Cattegat). His abode was said to be

well-lit by the gold he had collected from shipwrecks, for if he appeared above the waves, it was to sink ships and ransack them of their cargo. A portion of his wealth came from the tithes offered to him from Saxon pirates who hoped to stay on good terms with him. His servants were Fimafeng and Eldir. Aegir is depicted as an elderly man with a long white beard, claw-like fingers, wearing a black helmet. Sometimes he is depicted as a dragon that surrounds the worlds. For an account one of Aegir's banquets, *see* Loki. *See also* Fornjotr; Heimdal; Kari; Loki; Mimir; Niord; Ran; Thor.

Aegis *Aegeus, Aigis, Egis* (Greek)
In early Greek mythology, the Aegis was the storm cloud that surrounded Zeus' thunderbolt. Later in myth it became his sacred shield. It was created by the fire god Hephaistos from the hide of the goat Amaltheia, who nursed Zeus at birth. In other versions, the Aegis was made from the hide of Aex (also spelled Aega), thought by some to be a goat and by others to be a nymph who was the daughter of either the sun god Helius or of Pan, the shepherd god. Occasionally Zeus loaned his shield to other deities and eventually he gave it to Athena (Athene). When Perseus, the son of Zeus, chopped off Medusa's head and presented it to Athena, she had it attached to her Aegis. This magical breastplate had the capacity to make the wearer invulnerable and to turn enemies to stone. In some writings Aegis was an early king connected in legend with Minos. In Roman mythology, the Aegis was the breastplate of Jupiter and Minerva. Some say Aegeus was a form of Poseidon. For goat-related legends *see* Amaltheia, Aegisthus and Aegipan. *See also* Aegeus; Athena; Fafnir; Hephaistos; Jupiter; Medusa; Minerva; Minos; Minotaur; Perseus; Poseidon.

Aegisthus *Aighistos, Aigisthus* (Greek)
Aegisthus, the prince of darkness and deity of murderers, was born as the result of an incestuous relationship by his father, the king of Mycenae, Thyestes, and Pelopia, who was also Aegisthus' sister. Married to Clytemnestra, they were the parents of Erigone, who later committed suicide, and Aletes, who was murdered. As an abandoned infant, Aegisthus was suckled by a goat. His sister/mother Pelopia married her father's brother, Atreus; they recovered Aegisthus and raised him. In time, his true identity came to light and he murdered his stepfather/uncle and some say he also killed his natural father. The silence broken, his mother Pelopia, who did not know that it was her father who had raped and impregnated her, committed suicide. Aegisthus also conducted an affair with his stepbrother Agamemnon's wife, Clytemnestra, despite a warning from Hermes. The lovers plotted and murdered Agamemnon and the doubted prophetess, Cassandra, whom Agamemnon had won as a prize when the Greeks overcame Troy. They settled down, had their family and Aegisthus ruled Mycenae for seven years. Then another step-brother, Orestes, the son of Agamemnon, returned from exile and with the aid of his childhood friend, Pylades, he murdered Clytemnestra and Aegisthus. This act drove Orestes temporarily insane. For goat-related legends, *see* Amaltheia, Aegis, Aegipan. *See also* Agamemnon; Cassandra; Clytemnestra.

Aegle (A) *Aglaea, Aigle* (Greek)
One of the Heliades. Goddess of radiance. Aegle is the daughter of Apollo and Clymene, or Helios and Clymene. Her siblings are Aegiale (also known as Phoebe), Aetheria and Phaethon. She is the half-sister of Phaethusa, Lampetie and Lampethus. When her brother Phaethon died, her grief was so overwhelming that she turned into a poplar tree and wept tears of amber. In other renditions, the sisters, Aegiale, Aetheria, Aegle, Lampetie and Phaethusa were transformed by the gods into poplar trees when they died. Compare Aegle to Hesperides. *See also* Aglaia; Graces; Heliades; Helius; Phaethon.

Aegle (B) (Greek)
Also known as: *Charis.*
One of the Graces. She is the daughter of Zeus and Eurynome. *See also* Graces.

Aegle (C) (Greek)
One of the Hesperides, who are the guardians of the golden apples. *See also* Hesperides.

Aegle (D) (Greek) She is the daughter of Asclepius (q.v.).

Aegle (E) (Greek)
She is the daughter of Panopeus and Neaera, sister of Epeius and lover of Theseus (q.v.).

Aegle (F) (Greek) Aegle is the name used for more than one nymph.

Aegus (Greek) *see* Aether.

Aegyptus (Greek)
King of Egypt. He is the son of Belus and Anchinoe, the twin brother of Danaus, brother of Phineus, Thronia and Cepheus (possibly). Following the instructions of the Oracle at Delphi, he sacrificed his daughter Aganippe to save Egypt from a drought. His fifty sons married the fifty daughters of Danaus. *See also* Agenor (A); Danaides; Danaus; Eurydice (C).

Aeithlius (Greek) *see* Aeolus (A).

Aello *Aellopuus* (Greek)
A whirlwind deity, Aello, one of the harpies, is a daughter of Thaumas and Electra, or Neptunus and Terra, or Poseidon and Gaea, or Typhon and Echida. Her sister harpies were Podarge (Celaeno) and Ocypete. Initially depicted as beautiful, swift bird-like maidens, who could carry mortals, they evolved into loathsome creatures who harangued and sometimes snatched mortals. The harpies personify the sudden destructive forces of nature such as tornadoes or whirlwinds. Aello is possibly the same as Aeolus who was a son of Hellen and the nymph Orseis. This male version was also a keeper of the winds. The three harpies may be Athena in her triple-goddess form as a sudden destroyer. Aello is shown with a body of a bird, the pale face of emaciated woman and having claws of a lion on her hands. *See also* Aeolus (B); Briareus; Chimaera; Graeae; harpies; Phineus; Sirens.

Aellopuus (Greek) *see* Aello.

Aeneas *Aeneus, Aineias* (Greek)
A deified mortal, and sun deity, Aeneas is often called the founder of the Roman race. He is the son of Anchises the king of Dardania and the love goddess Aphrodite. He had one brother, Lyrus, who died childless. Raised by nymphs and

True Breath - Skin Breathing.. 33
Daily Practice: Opening, Connecting & Activating Chi Within & Cosmic Charging 34
  Relax and Let go - Smile to Connect with Universe Within............................ 41
  Tan Tien Consciousness: The Second Brain 37
  Three Minds into One: 'Yi' Power 44
Activating the Six Directions and the Three Fires 45
  Direction Below 45
  Front Direction and Tan Tien Fire 46
  Back Direction and Kidney Fire 47
  Heart Fire 48
  Sacred Fire (Chi Fire)... 49
Open the Third Eye 49
  Front Direction: Push/Pull Master Practice 51
  Left and Right Directions 52
  Direction Above 53
  Open the Spine.. 54
  Open the Middle Channel and Perineum.. 56
  Tan Tien and the Universe 57
Open the Three Tan Tiens 59
  Upper Tan Tien - Mideyebrow 58
  Middle Tan Tien - Heart Center - Conscious Mind 61
  Recharge and Cut Around the Armpits 62
  Lower Tan Tien - Navel - Awareness Mind 63
  Activate Chi in the Bones of the Hips, Legs and Sacrum 64

Chapter IV
General Healing Session

Three Minds into One Mind (Introduction).. 68
Activate the Six Directions (Introduction)... 68
Activate the Three Fires (Introduction) 68
Linking Personal Stars, Energy Bodies and the Universe (Introduction) 69
Protective Circle and Chi Field (Introduction).. 69
  Sacred or Chi Fire.. 69
  Chi (Sacred) Water Practice (Introduction).. 69
Empty and Fill (Introduction) 70
Clean with Green Light (Introduction).. 70
Clean with Blue Light (Introduction)... 70
Charge with Violet Light (Introduction) 70

trained by Cheiron the centaur, he grew up to become a warrior. With Acamas and Archelous, he was a leader of the Dardanian troops. During the Trojan War, armed with weapons forged by the fire god Hephaistos, he was seriously injured by Achilles. His mother rescued him from the battlefield and he was nursed to health by the goddess of hunting, Artemis, and the powerful goddess, Leto. He was kept from returning to battle by Poseidon, who explained to the gods that Aeneas and his descendants would one day rule Troy. At the fall of Troy, he escaped, holding high the sacred flame and carrying his elderly father on his back. Married to Creusa, they were separated during the flight and she died. Their son, Iulus (also known as Ascanius), stayed with him. He enlisted twenty ships of Trojans and went in his search of his promised empire. He encountered many obstacles: a miserable run-in with the harpies; wretched weather whipped up by Aeolus, the god of winds; and an obsessive affair with Dido deliberately instigated by Venus, which threw him off track. He obtained permission from the gods to visit his father in the underworld for advice and purification. Eventually, he arrived in Italy where he fought bitterly with the fearless warrior and king of Rutali, Turnus, whom he killed. He married his opponent's daughter Lavinia and they became the parents of Aeneas Silvia (Silvius). Aeneas died in western Sicily with great honors bestowed upon him. To compare to others who visited the underworld; *see* Heracles and Orpheus. *See also* Aeolus (B); Anchises; Evander (B); Golden Bough; Hephaistos; Poseidon; Venus.

Aenetus (Greek) *see* Actor.

Aeneus (Greek) *see* Aeneas.

Aengus (Celtic) *see* Angus.

Aeoina Kamui (Japan) *see* Okikurumi.

Aeolia (Greek)

She is the daughter of Amythaon, who with his half-brother Neleus re-instituted the Olympic Games and Idomene or possibly Bias, the king of Argos and Pero. She married Calydon, the son of Aetolus and Pronoe and became the mother of Epicasta, who married Agenor and Protogeneia. *See also* Agenor; Amythaon; Bias; Calydon; Pero.

Aeolus (A) (Greek)

Also known as: *Aeolus (B)* (possibly).

The ruler Aelous is the great grandson of Prometheus, known as the father of mortals, the grandson of Deucalion the builder of the ark and a survivor of the Deluge. He is the son of Hellen, the king of Phthia (some say founder of the Greek race) and the nymph Orseis (also known as Ortheis). Hellen divided up the Greek lands between his three sons, Dorus of the Dorians, the thievish Xuthus who was possibly the king of Athens, and Aeolus. Aeolus received Thessaly and called the inhabitants of this area, Aeolians. He married Enarete, the daughter of Deimachus. Their sons are Cretheus the first king of Iolcus, Athamas who was possibly the king of Achaea, and the cunning Sisyphus. Salmoneus the king of Elis, and Perieres the king of Messenia are also their sons, as are Magnes the human magnet, Macar (also known as Marareus), and Deion the king of Phocis. It is possible that Aeolus is the father of Aeithlius by Protogeneia, although he is generally thought to be the son of Zeus. Their daughters are Canace, Peisidice, Alcyone who drowned herself, Calyce, Perimele who was thrown into the sea by her father and turned into an island by Poseidon, Tangara and Arne (her mother may have been Hippe). Canace was instructed to kill herself with a sword for committing incest with her brother Macar who also killed himself. Aeolus then committed suicide. *See* Aeolus (B) the god of the winds who is often regarded as the same as Aeolus (A) by many late authors. For details of Deion's marriage *see* Actor (A). For detail's of Perieres' marriage, *see* Gorgophone. *See also* Argus (D); Arne; Boreas; Deucalion; Hellen; Promethus; Sisyphus.

Aeolus (B) (Greek)

Also known as: *Hippotades, Aeolus (B)* (possibly).

God of the winds, and father of the winds, Aeolus is the son of Poseidon and Arne (also known as Melanippe), who is the daughter of Aeolus (A) and the brother of Boeotus, or the son of Hellen the king of Phthia, and Hippe who was the daughter of Cheiron the centaur. Aeolus married Gyane (Cyane), the daughter of King Liparus. They took up residence on the cloud island Lipara (Liparus) that floated around the celestial realm. The couple had six daughters and six sons. Each son married one of his sisters. Initially, either Zeus or Hera appointed Aeolus to be a guardian of the winds. In time his status was raised to father of the winds. In myth, he is said to have invented the sail. His position allowed him to order the invisible energy to do his bidding; he could whip up a storm or delicately rustle a blade of grass. It is said that Odysseus docked his ship at the Lipara Islands and was entertained by the wind god. When he was ready to depart, Aeolus gave him a wind bag and cautioned him not to open it. His suspicious or curious crew decided to throw caution to the winds, opened it, and let loose a tempest which caused a torturous journey until they reached Laestrygones. For other wind deities *see* Astraeus; Boreas; Notus; Zephyrus. To compare to storm deities *see* Chimaera; Harpies. Compare Aeolus to Fu-jin (Japan). *See also* Aello; Aeneas; Aeolus (A); Aquilo; Astraeus; Cheiron; Eos; Harpies; Hellen; Hera; Poseidon; Zeus.

Aeons *Aion* (Post-Christian Gnostics)

Also known as: *Eon.*

Age of the universe. Aeons are also deities who were the offspring of Bathos and possibly Sige. Nous and Aletheia begot Logos and Zoe. From this pair came Agape, Ageratos, Anthropos, Autophyes, Bythios, Ecclesia, Ecclesiasticus, Elpis, Henosis, Macaria, Metricos, Mixis, Monogenes, Paracletos, Patricos, Pistis, Sophia, Synerasis and Theletas. Each of these were paired as male and female. The feasts of Agape were held in worship at many of the rites of these deities. *See also* Achamoth; Archons; Pistis Sophia.

Aepytus (A) (Greek)

King of Messenia. He is the youngest son of Cresphontes and Merope. His two brothers and his father were killed by Polyphontes, who overthrew the throne. Aepytus was raised by Cypselus, his mother's father. He regained the throne when he killed Polyphontes (q.v.).

Aepytus (B) (Greek)

King of Arcadia. He is the son of Eilatus, who is the son of Merope. Aepytus raised Evadne, the daughter of Poseidon and

Pitane. She became the mother of the prophet Iamus by Apollo. *See also* Merope.

Aer and Arura (Phoenicia)
In the beginning there was Time. From time came Desire and Darkness. From these two deities came Aer (air) and Arura (breath). Aer was intelligence, and Aura represented movement. From these two came the cosmic egg. In some versions Aer was the offspring of Uranus. Compare to Aether (Greek).

Aeracura (Celtic, Irish, Greek)
It is possible that Aeracura was a forerunner of Dis Pater. In ancient mythology she was thought to be an earth deity and is identified with the god of fields, trees and forests, Silvanus. She is also known as the Celtic earth mother of the Rhine Valley. Aeracura is shown with a basket of fruit or a horn of plenty. *See also* Dis; Dis Pater; Silvanus.

Aerolith (Syria)
Followers of Baal worshipped this stone which is said to have fallen from heaven. *See also* Baal.

Aeron (Celtic) Goddess of war and slaughter.

Aerope (Greek) *see* Agamemnon; Ares.

Aeropus (Greek) He is the son of Ares and Aerope. He is also the father of Echemus who was the king of Arcadia. *See also* Ares.

Aerth (Teutonic) *see* Hertha.

Aertha (Teutonic) *see* Hertha.

Aes Sidhe (Celtic) *see* Dana.

Aesar (A) (Teutonic) *see* Aesir.

Aesar (B) (Celtic, Irish)
Also known as: *Aesus, Asus* (Roman), *Dia, Logh.*
Aesar is thought to be an ancient creator god or god of fire and intelligence. He may have been a Druid deity and possibly a god of destruction. He was a consort of Eire. *See also* Aesir; Aesus.

Aesculapius (Greek) *see* Asclepius.

Aeshma (Zoroastrian; Persia)
Also known as: *Aesm* (Pahlavi dialect).
One of Angra Mainyu's assistants, Aeshma is the demon of wrath, fury, lust, and outrage. He constantly stirs up strife and war. If he is not successful in creating chaos among the good, he will do so among his colleagues, the demons. Aeshma assails the souls of the dead as they approach Chinvat Bridge. This fiend is in opposition to the Amesha Spenta Vohu Manah and is held in check by Sraosha, the personification of obedience and devotion, who will eventually defeat him. Aeshma may be the same as Asmodeus (q.v.). *See also* Ahura Mazda; Amesha Spentas; Angra Mainyu; Chinvat Bridge; Daevas; Sraosha; Vohu Manah; Yazatas.

Aesir *Aesar, Aisar, A'sas* (Norse; Teutonic)
Originally a race of war gods, the Aesir are sky deities led by Odin and Frigg. Their home is in Asgard. The Aesir are the opponents of the sea gods known as the Vanir who are led by the god Njord's children Freyr and Freyja. After a long battle which no one won, they agreed to a peaceful settlement and exchanged hostages. The Vanir gave Njord and his son Fryr to the Aesir. The Aesir gave Henir to the Vanir. There are several lists with the names of the Aesir. One list names Balder, Heimdall, Loki, Odin, Thor and Tyr. Usually the number of Aesir is said to be twelve. They are Balder, Bragi, Hermoder, Henir, Hodur, Loki, Odin, Svipdag, Thor, Tyr, Vali, and Vidar. In another list the following names are given of deities who at one time or another were considered Aesir: Balder, Baugi, Bragi, Forseti, Frey, Heimdal, Henir, Hodur, Loki, Njord, Odin, Thor, Ullur, Vali, and Vidar. Their female counterparts are the Asynjor. Their names are Beda, Bil, Eir, Fimila, Fjorgyn (also known as Jord), Freyja, Frigga, Frimla, Fulla, Gefion, Gerd, Gna, Hnossa, Horn, Mardoll, Nanna, Saga, Sif, Sigyn, Skadi, and Vanadis. The name Aesir may be derived from the Sanskrit Asura, or possibly the Egyptian cognate name of Asar who was form of Osiris. The name Aesir is similar to Asar (Egyptian), Asari (Babylonian), Assur (Assyrian), Azur (Hebrew) and Esar (Turkish). The name may have originated in Asia. *See also* Aesar; Asgard; Balder; Bil; Bor; Bragi; Forseti; Frejya; Freyr; Frigga; Fullar; Gefton; Gerd; Gladsheim; Gna; Heimdall; Henir; Hodur; Hofud; Jord; Jotun-heim; Mimir; Nanna (A); Odin; Sif (A); Sigyn; Skadi; Thor; Tyr; Vali; Vanadis; Vanir; Vidar; Yggdrasil; Ymir.

Aesm (Persia) *see* Aeshma.

Aeson (Greek) *see* Jason and Admetus.

Aesus *Æsus* (Roman)
Also known as: *Aesar.*
Aesus is possibly a fire god or a supreme deity, or possibly a Druid supreme being. Aesus is also the Roman name for deity. Not much else is known. *See also* Aesar (B); Dia.

Aether *Aethre, Aithre* (Greek)
Also known as: *Ether.*
He is the god of storms and winds, god of light, and god of the upper air or sky. Aether is the son of Erebus and Nyx. His siblings are Cer the goddess of violent death, Charon the ferryman of the dead, Hemera who personifies day, Hynos the god of sleep, Moros the god of destiny, Nemesis the goddess of retribution, and Thanatos the god of death. Aether has also been called the father of Uranus or Nxy and Uranus. In the Orphic tradition, Aether and Chaos sprang from Chronos or Time. In certain renditions Aether appears in the feminine form as the daughter of Pittheus (a mortal king) and Aegeus (sea) who deserted her. She is also said to be the mother of Theseus (Sun). Aether represents the upper sky, or upper air, the realm closest to the earth, as opposed to air. As a geographical location it was said by some to be the abode of Zeus. For additional information on the Orphic tradition, *see* Phanes. Compare Aether to the Phoenician Aer and Arura. *See also* Chaos; Erebus; Uranus.

Aetheria (Greek)
She is one of the Heliades. Her parents are Helios and Clymene. *See also* Aegle (A); Heliades.

Aethiolas (Greek) *see* Helen.

Aetholides (Greek)
Also known as Pythagora (possibly).

Renowned for his perfect memory, he is the son of Hermes and Eupolemia. During the Argonautic expedition, he was the herald. *See also* Abaris; Eupolemia.

Aethon (Greek) *see* Helius.

Aethra (A) (Greek)
Aethra is the mother of Theseus. She was abducted by the Dioscuri and taken to Troy where she became the servant of Helen of Troy. Her grandsons, Acamas and Demophoon, liberated her. *See also* Acamas (A); Demophoon; Dioscuri; Theseus.

Aethra (B) (Greek)
Another name for the Oceanid Pleione (q.v.).

Aethre (Greek) *see* Aether.

Aethus (Greek) *see* Arethusa (A); Arethusa (B).

Aetna (Roman) Mountain goddess. *See also* Fuji; Pele.

Aetolus (Greek) *see* Apis (B).

Aex (Greek)
Also known as: *Aega* (Greek). *See also* Aegipan; Aegis; Helius.

Af (A) (Egypt)
Af is the spirit of Ra during the first hour of the night as he journeys through the underworld. At that time he is called the "Sun of Night" which is a dead god (body) or flesh.

Af (B) (Africa) *see* Afa.

Af (C) (Hebrew)
In Gehenna (Hebrew), Af is one of the three angels: Af, Khema and Mashkhith.

Af-Osiris (Egypt) *see* Osiris.

Afa (A) (Samoan) Storm god.

Afa (B) (Dahomey People, Africa)
Also known as: *Af.* The androgynous god of wisdom, Afa was consulted on matters of marriage and sexual problems.

Afau (Egypt)
One of the gods who accompany Osiris during the Second Hour of the Night. *See also* Osiris; Shesat Maket Neb-S; Tuat.

Afi (Norse; Teutonic)
Also known as: *Grandfather.*
Deified mortal. Afi and Amma are the ancestors of the race of peasants. Heimdall slept between Afi and Amma who were Grandfather and Grandmother. From the union with Amma Karl was born. He later married Snor. They had ten sons and ten daughters. Of the ten sons there is Breid, Boddi, Bondi, Brattskegg, Bui, Bundinskeggi, and a daughter named Brud. *See also* Heimdall; Karl; Rig.

Afreet *Affreet* (Arabic)
Also known as: *Afrit, Ifrit.*
Unclean spirits, or evil genii.

Afrit (Arabic) *see* Afreet.

Afu, The (Egypt)
Protectors. They are gods who are mentioned in the Pyramid Texts. Their duty is to minister to Osiris in Second Hour of the Night. *See also* Tuat.

Ag (India) *see* Agni.

Aga-mi-ketsu-no-Kami (Japan)
Probably a deity of food. She was sent by the Emperor Yuryaku to be the companion of Amaterasu. She might be the same or similar to Ukemochi-no-Kami (q.v.). *See also* Amaterasu.

Agaku (Babylonia) *see* Marduk.

Agamede (Greek) *see* Actor (C).

Agamemnon (Greek)
Sun hero. Argonaut. Agamemnon is the son of Atreus and Aerope or according to some, the son of Atreus' son Pleisthenes and Cleolla. As the son of Atreus, he and his brother Menelaus were known as the Atreidae, meaning sons of Atreus. He may have been the brother of Pleisthenes and Anaxibia. Agamemnon married Clytemnestra and became the father of Iphigenia (Iphigeneia), Iphianassa, Electra (also known as Laodice), Chrysothemis, and Orestes. Homer names Iphigenia, Iphianassa, and Electra, Laodice. Others say that Iphigenia was raised by Clytemnestra but was actually the daughter of Helen and Theseus. He was also the father of Chryses by his slave Chryseis, and the father of the twins Pelops and Teledamas by his "war prize," Cassandra. Agamemnon murdered Clytemnestra's first husband, Tantalus, and brutally killed their baby before he married her. Agamemnon was a rich and powerful king of Mycenae who became the commander of Greek forces at Troy. He was able to convince Clytemnestra and Helen's father, Tyndareus, to choose his brother Menelaus as Helen's fiancé. In the meantime, Helen was abducted by Paris, the Trojan prince and Menelaus appealed to Agamemnon to take his forces to rescue her. As he was preparing to do so, he boasted to the huntress Artemis that he was more skilled then she. Infuriated, she sent either calm seas or violent storms to immobilize his ships. The prophet Calchas advised Agamemnon that only the sacrifice of his daughter Iphigenia would quell the rage of Artemis. Pulled between his duties as a father and as a commander-in-chief he prepared his daughter for sacrifice. It is said that at the last moment, Artemis or Hera substituted a stag for the young woman and took her away to be a priestess. In some legends, she became the goddess Hecate. Agamemnon's act incurred the wrath of Clytemnestra, who was never certain if her daughter had been sacrificed, for she never saw her again. For details about his relationship with Cassandra, *see* Cassandra. For details pertaining to the murderous deaths of Agamemnon and Cassandra *see* Aegisthus; Cassandra; Cinyras; Clytemnestra. *See also* Achilles; Calchas; Helen; Iphigenia; Menelaus; Orestes.

Aganippe (Greek)
Fountain of the Muses. Nymph of the fountain. Aganippe lived in the spring of the same name at the foot of Mt. Helicon and provided inspiration to all who drank from her waters. Aganippe, known as the nymph of inspiration, is the daughter of Permessus, a river god. See Naiads for other classes of water nymphs. *See also* Danae; Muses.

Aganju (Yoruba People, Africa)
In some myths Aganju is the son of Odudua and the brother/spouse of Yemoja. They became the parents of several

river goddesses and of Ogun, Olokun, Orunjan, Shango, Shankpanna and others. *See also* Obatala; Ogun; Yemoja.

Aganus (Greek) *see* Helen.

Agapae (Greek) *see* Agape.

Agape *Agapae* (Greek)
Early Christian love feasts which were forbidden by the Church in C.E. 391. Epiphanius, before he became a saint, was lured into a Syrian Gnostic group, the Phibionites. He reported their rituals in detail and went on to renounce the group and approximately eighty of his associates. *See also* Aeons.

Agas Xenas Xena *Aqas-Xena-Xenas* (Chinook People, United States)
This deity of the evening star became the father of Siamese twins who were separated by Blue Jay (q.v.).

Agasaya "The Shrieker" (Semitic) *see* Ishtar.

Agassou (Dahomey People, Africa)
He is a panther fetish god of the royal household.

Agastya (Hindu; India)
Also known as: *Dattoli, Kalasi-Suta* (Son of a Jar).
A Rishi and a divine teacher of science, religion and literature, Agastya was also a priest and poet. After death he was assigned a place in the heavens where he became the ruler of Canopus, the South Star. In one legend, Agastya was born as a result of the seed spilled by Varuna and Mitra (in some versions it is Surya, not Varuna), when they were filled with desire for the beautiful nymph Urvasi. Their sperm was collected in a jar of water, and in time, Agastya was born in the shape of a beautiful fish. He was later reborn as a child. The Vindya mountains wanted to be higher than Meru Mountain and were growing at a rate that threatened to block the sun's rays. The gods asked Agastya for assistance. He packed up his family and journeyed to the south. When he met Vindya, he requested the boon of the mountains to not grow until he returned at another time. His boon was granted, but Agastya continued south and never returned. Since that time, the mountains have never grown. When he was offended by the ocean he drank it up and found his enemies the Daityas, who were at war with the gods, hidden under the water. From various animal parts he molded a beautiful young woman who became his spouse Lopamudra. In later years, while living as a hermit on the mountain slopes, he provided lodging for Lakshmana, Rama, Sita, who were in exile. He gave Rama the bow of Vishnu, the quiver of Indra and the dart of Brahma. In southern India he lives invisibly on Agastya's hill in Travancore and is venerated as the divine teacher of science, Sanskrit literature, and the Hindu religion. *See also* Brahma; Daityas; Indra; Mitra; Rakshasas; Ravana; Rishi; Surya; Urvasi; Vishnu; Vrita.

Agathadeamon (Greek) *see* Agathos Diamon.

Agathodiamon (Greek) *see* Agathos Diamon.

Agathos Diamon (Greek)
Also known as: *Agathadeamon, Agathodiamon.*
Deity of health, good fortune and life. This ancient Greek spirit is the oracle of the future and teacher of wisdom. He is the spouse of Tyche Agathe (also known as Agatha).

Agave (Greek)
Agave is the daughter of Cadmus and Harmonia. Her siblings are Autonoe, Illyrius, Ino, Polydorus, and Semele. She married twice, her first husband was Echion. They had a child, Pentheus, who became the King of Thebes. Pentheus and his mother Agave ridiculed Dionysus, who in turn forced her and her sisters, to rip Pentheus to pieces. Her second husband was the king of Illyria, Lycotherses whom she murdered so her father Cadmus could take over the throne. Dionysus drove Agave insane after being ridiculed by her and her son, Pentheus. Agave and her sisters ripped Pentheus to pieces. *See also* Cadmus; Dionysus; Harmonia (A); Ino; Nereids; Semele.

Agbe (Dahomey People, Africa)
Also known as: *Arge Woyo* (Haitian).
Agbe, the son of Mahu and Lisa is the chief god of the Xevioso or Thunder pantheon. His mother (also known as Sogbo) placed him in charge of world affairs. Agbe's abode is the sea. When he has a conference with his mother he must join her where the sky and the sea meet. Although powerful, he was never instructed in the art of rain-making. He sends the water from the sea up to his mother, who causes it to fall from the sky as rain. Lightning at sea is caused by Agbe and lightning on ground by Sogbo. The Haitian deity Arge Woyo belongs to the Rada Pantheon and is also a sea deity. He has a son Agweto and a daughter Agweta. *See also* Aylekete; Leza; Mahu; Rada.

Agdistis *Agdos* (Greek)
Also known as: *Cybele.*
Deified object. In some renditions, Agdo was a natural rock from which the world sprang forth. The "Great Mother" is said to have slept on this rock. (Cybele of Asia Minor was known as "Great Mother.") Zeus couldn't impregnate her so he impregnated Agdo, the rock and produced Agdistis. Agdistis, born with both male and female organs, frightened the other gods. Liber, the ancient Roman god of fertility drugged a well from which Agdistis drank. After he fell asleep, Liber tied his foot and phallus together with a strong hair rope. In trying to get free Agdistis castrated himself and his blood fertilized the earth. It is thought by some sources that the castrated Agdistis grew up to become Cybele. Nana (also known as Naa), a river nymph, placed a pomegranate from a tree that grew in the area in her bosom and from this came her son Attis (Atys, Atos) who became the consort of Cybele. In a variation of this portion of the myth, Attis was born from an almond that grew from the severed genitals of Agdistis. Attis also castrated himself and became a pine tree. *Note:* Liber is often confused with the Greek Iacchus who is the son and possibly husband of Demeter and is identified with Bacchus. *See also* Attis; Cybele.

Agditis (Greek) *see* Agdistis.

Agdos (Greek) *see* Agdistis; Cybele.

Agemo (Africa)
Also known as: *Sky God's Messenger.*
He is a chameleon.

Agenor (A) (Sidon, Syria, then to Greece)
Also known as: *Auga-nur* (Semitic).
Deified mortal or sun god. Fire deity. Agenor, the king of Phoenicia, is the son of Poseidon and Libya who is the daugh-

ter of Epaphus and Memphis. Agenor is the twin brother of Belus and brother of Lelex. His mother Libya may have been the mother of Lamis by Agenor's uncle Belus. Agenor married Telephassa also known as Argiope. Their sons are Argus (possibly); Cadmus who became king of Thebes; Cilix who accompanied Cadmus and Phoenix in their search for the kidnapped Europa; Phineus the king of Thrace; Phoenix who became king of Phoenicia; and Thasus. They had one daughter Europa, who was raped by Zeus in the form of an eagle. Belus, king of the Egyptians married Anchinoe who was the daughter of the god Nile. They were the parents of twins, Aegyptus and Danaus, a daughter, Thronia, and possibly Cepheus. Aegyptus had fifty sons and Danaus had fifty daughters who were known as the Danaids. Agenor and Belus were thought to be ancestors of Dido, queen of Carthage and the Persian kings. *See also* Aegyptus; Agenor (B); Danaids; Danaus; Dido; Europa.

Agenor (B) to (G) (Greek)
There are numerous men named Agenor in Greek mythology. Agenor (B) was the king of Argus, son of either Ecbasus, Triopas, or Iasus. Agenor (C) is the son of Pleuron and Xanthippe (*see* Hippodamus). Agenor (D) is the brave Trojan, the son of Antenor and Theano. Agenor (E) was or Belus the father of Dido, Anna and Pygmalion, but not thought to be Agenor (A). Agenor (F) was the name of a man engaged to Andromeda and killed by Perseus. Agenor (G) is the son of Phegeus. *See also* Agenor (A).

Ageratos *see* Aeons; Nous.

Aghyu Gugu (Cherokee People, North America) *see* Unelanuhi.

Agilma (Babylonia) *see* Marduk.

Aglaea (Greek) *see* Aglaia.

Aglaia *Aegle, Aglaea* (Greek)
Also known as: *Charis, Ocaleia, The Shining One.*
Nymph. Worshipped throughout Greece. Aglaia, the daughter of Zeus and Eurynome is one of the Graces. Three of her sisters are Euphrosyne, Thalia and Pasithea. Homer called Aglaia by the name of Charis (Grace). Like the Muses with whom they lived on Olympus, they loved to sing and dance, and like the Muses, they were companions and attendants of Athena or Aphrodite. Early writers indicate that Aglaia was the wife of the fire god Hephaestus while later poets name Aphrodite as his wife. For other possibilities of Aglaia's parentage, *see* Graces. Not to be confused with Aglaea the mother of the twins Acrisius and Proetus by Abas. *See also* Charities; Muses; Proetus.

Aglaope (Greek) *see* Sirens.

Aglauros (Greek) *see* Agraulos.

Aglaurus (Greek) *see* Agraulos.

Agloolik (Eskimo)
Good spirit. Agloolik, a good spirit who lives under the ice, aids the hunters and fishers in overcoming obstacles in their daily lives. *See also* Adlivun; Aipaloovik; Sedna.

Agnar (Norse; Teutonic)
Hero or god of light. Brother of Geirrod. In a complicated tale they were saved by Odin and Frigga.

Agnayi (Hindu; India) *see* Agni.

Agne (India) *see* Agni.

Agnen (Tupinamba People, Brazil)
A fisher deity. *See also* Ariconte.

Agneya (India) Son of Agni. *See also* Karttikeya.

Agneyastra (India) A magic weapon. *See also* Sagara.

Agneyi *Suada* (India)
Daughter of Agni. *See also* Agni; Rishi.

Agni *Agne, Agnis* (Brahmanic, Hindu, Tantric, Vedic; India; possibly of Persian origins).
Also known as: *Ag, Agni Yavishta, Agoni* (Slavic), *Anala, Asani* (Lightning), *Bhava* (Existence), *Brhaspati* (Lord of Devotion), *Dhumakety, Grahapati, Grhapati* (Lord of the House), *Hotar* (The Invoker), *Isana* (Ruler), *Jatavedas* (All-knowing), *Mahadeva* (Great god), *Moloch, Narasamsa* (Praise of Men), *Ogoni* (Slavic), *Pasupati* (Lord of Cattle), *Pav, Pavaka* (The Purifier), *Pramati, Rudra* (Roarer), *Sarva* (All), *Skambha* (Support), *Slayer of Rakshasas* (Slayer of Evil Spirits), *Surya, Tanunapat* (Son of Self), *Trita, Tryambaka,* (Three-Mothered or Three-Eyed), *Ugra* (Dread), *Vaishwanara* (Universal Man), *Yavishta.*
Agni's name means "The Knower." The master of the universe, he is also the god of fire, sun and lightning. In the Vedic tradition, his parents are the earth goddess Prithivi and Dyaus the sky god. Born fully grown and eternally youthful as an all-consuming flame, he immediately devoured his parents. To sustain himself, he lapped up the clarified butter known as *ghee*, which was poured on the sacrificial fire. Sometimes, like his rival, and some say twin brother Indra, he sustained himself on the magic soma. His other siblings are the goddess of dawn Ushas and the goddess of the starlit night, Ratri. Other legends pertaining to his birth: he was born in wood from plants and springs to life whenever fire is ignited; he was born of the sky god Dyaus and brought to earth by the demigod Matarisvan; he was created from the friction of two stones generated by Indra; he was born of the waters and generated the first germ of life; he was created by Indra and Vishnu; he was created by the friction of fire sticks, his mother the lower and his father the upper; the fire sticks are his two mothers; he was generated by the ten fingers called ten maidens; he was the son of Prajapati (the Creator) and Ushas and was given eight names, which constitute his eight forms; he was born from the breath of Prajapati along with Indra, Soma and Parameshthin Prajapatya; Agni was the supreme ruler of the earth, Vayu or Indra ruled the air, and Surya ruled the sky; Angi encompassed all three worlds and their gods; therefore he was thrice-born. He is constantly born and reborn in the celestial realm as the sun. He is born again in the atmosphere, where he ignites the rain clouds and appears on earth as lightning. He is born a third time by priests and followers in the form of the sacrificial fire. He also presides at the altar and hearth where he is kindled at dawn or immediately before day breaks. In this form, known as

Grhapati, he constantly dies and is reborn. He offers warmth, protection and nourishment to mortals. To worshipers, he bestows domestic health and welfare, and consumes their enemies. The smoke from his fires rises to the heavens and becomes the clouds, which form the rain. In the form of lightning, he is known as Trita, and blazes at the heart of the sun. As the sun, he is known as Surya. When Agni is worshipped as the fire, lightning and sun, he is known as Tryambaka the Three-mothered. So it is, that wherever there is fire, there is Agni. The followers of Brahma consider his mother as Sandili. The goddess Lakshmi is also indicated as his possible mother. It is also said that he is the son of Brahma, Kasyapa and of Aditi or Angiras the king of the Manes. He is said to be the husband of Suada (also spelled Suadha, Svaha and Swaha and known as Agnayi) and father of Pavaka, Pavamana and Suci. He is the father of Karttikeya (also known as Skanda). Agni carries the Asu or Manas which is the spiritual principle to the sun after cremation of the body. He is invoked as a celestial deity and a domestic deity for he knows the realm of the gods as well as he knows the realm of the household. Agni is invoked to dispel the powers of the evil spirits known as rakshasa. A slayer of demons, he battles the flesh-eating Kravyad, who is a rakshasa (evil spirit). When ill, Agni is invoked alone or with Soma and Varuna, to drive away the fire of fever. He is invoked for abundance and prosperity and the forgiveness of sins. The river goddess Saraswati appears as his attendant or consort. Agni has two faces (Sun fire and Earth fire), three heads growing red flames and three legs (one perhaps a euphemism for the phallus, or the three fires of an individual's life), wearing a garland of fruit. He is said to have tawny flowing hair, golden teeth and he is flame red in color. He is equipped with seven tongues, each with a name, with which he laps up the ghee (sacrificial butter) and a distended stomach. The name of Agni's first tongue is Kali the goddess of destruction. She represents the dark side of Agni, his ashes and ambers. Agni has seven arms (to span the continents) and has also been depicted with three bodies. He rides on a ram. He symbolizes the creative life-giving spark of the universe. In his hideous form, he has iron tusks and roars like a bull. Agni's three heads symbolize his triple birth. His seven arms are rays of light. His two faces represent the creative and destructive nature of fire. Depicted on his ram with four arms and two heads, he holds his attributes: a fan to fan fire, an ax, a torch and the sacrificial ladle. Flames shoot from his mouth and seven rays are emitted from his body. The eight aspects of Agni are Asani (lightning), Bhava (existence), Isana (ruler), Mahadeva (great god), Pasupati (lord of cattle), Rudra (roarer), Sarva (all), Ugra (dread). Agni's mount is the ram. In the practice of yoga, Agni relates to mindfulness and wakefulness, or the fire of the mind and the Kundalini, or fire at the base of the spine. The goddess Sarasvati represents the element of water. The etymology of the goddess Suada's name means "a good offering through fire." Mystically, it means "so be it" which is the ending of many mantras. Kravyad (Flesh Eater) is depicted with red hair and shiny fangs. Sometimes Brhaspati (also called Brahmanaspati) is considered to be the same as Agni. In Agni's creation myth, Matarisvan is not to be confused with a later wind god of the same name. Agni is identified as the Rudra Shiva aspect of Shiva (destructive). Compare Agni to Cronus (Greek), Fuji (Japan), Hephaistos (Greek), Hestia (the Greek hearth goddess), Pele (Hawaiian), Vahagn (Armenian), and Vesta (Roman). For a myth about Agni and Bhrigus *see* Bhrigus. The mythology of Agni and Indra is similar (q.v.). *See also* Angirasa; Apam Napat (Inod-Iranian); Arjuna; Asuras; Brahma; Brhaspati; Daksha; Dikpalas; Durga; Dyaus; Garuda; Jogina; Kali; Kama (A); Karttikeya; Kasyapa; Kravyad; Krishna; Kuhu; Lokapalas; Matarisvan; Mitra; Moloch; Parvati; Prajapati; Prithiva; Ratri; Ravana; Rishi; Rudra; Sarasvati; Skamba; Soma; Surya; Tvashtri; Urvasi; Ushas; Vahagn; Varuna; Vasistha; Vasus; Vedas (The); Vishnu; Vourukasha; Yama.

Agni Yavishata (India) *see* Agni.

Agnimukha (India) "Fire Face." *See also* Yaksha and Yakshini.

Agnis (India) *see* Agni.

Agoneus (Greek) *see* Hermes.

Agoni God of Fire (Slavic) *see* Agni.

Agothyathik (Africa) *see* Aywel.

Agras (Finnish)

God of twins. God of grain (possibly). In some myths, Agras is the patron of turnips.

Agrasandhani (India) List of mortal's deeds. *See also* Yama.

Agrat Bat Mahalat *Igirit* (Hebrew)

On Wednesday and Friday evenings, Agrat Bat Mahalat, the ruler of 180,000 demons, climbs into her chariot and hunts everything that moves. *See also* Lilith (queen of the demons).

Agraulos *Aglauros, Aglaurus* (Greek)

The goddess of agriculture and fertility Agraulos is the daughter of Cecrops, the king of Attica, and Agraulos, the daughter of Actaeus. Her sisters are Herse, Pandrosus, and possibly Erysichthon. Hermes approached Agraulos and paid her for the opportunity to have sex with her youngest sister, Herse. The young woman took his gold but denied Hermes his wish as she was jealous of her sister's good luck. What she didn't know was that the goddess Athene had instilled feelings of envy within the young woman. Infuriated, Hermes turned Agraulos to stone and raped Herse who had two sons by him, Cephalus and Ceryx. Her sisters and her mother were asked to care for a casket and instructed not to open it. Ignoring the command, they lifted the lid and found hidden inside, the child Erichthonius, who had serpent's tails for legs. The sight of him drove two of the sisters insane. They leapt to their deaths from the top of the Acropolis. Agraulos and her sisters are known as the Augralids. Agraulos is not to be confused with Agraulus (Aglaurus), the daughter of Actaeus and the mate of Cecrops. Cecrops, the father of Agraulos has a man's body and a snake's tail. *See also* Ares; Cecrops.

Agreaskoui (Iroquois) *see* Areskoui.

Agreus (Greek) *see* Agrius (A).

Agri-manios (Greek) *see* Angra Mainyu.

Agriskoue (Iroquois) *see* Areskoui.

Agrius (A) *Agreus* (Greek, Sumerian)

Also known as: *Agrotes.*

Giant. High god. Agrius is the son of Gaea and brother of Thoas, and one of the Giants. In the war between Giants and gods, Agrius and Thoas were battered to death by the Fates who used brazen clubs or they were killed by Heracles. As Agreus, he was said to be part of the pantheon of Melqart (Melkart) of the Sumerians. The name is said to mean "hunter." One of the names of the Babylonian god Gebal was Agroueros. *See also* Fates; Gaea; Giants; Hippolytus; Melkart.

Agrius (B) to (E) (Greek)
There are other men by the name of Agrius in Greek mythology. Agrius (B) was a Centaur who attempted to kill Heracles but was killed by him. Agrius (C) was possibly the father of Thersites, who was known as the ugliest man in the Trojan War; not to be confused with Agrius the king of Calydon. Agrius (D) was the son of Odysseus and Circe. Agrius (E) was the king of Calydon, son of Porthaon and Euryte who committed suicide when his sons were killed by Diomedes the son of Tydeus. *See also* Agrius (B); Agrius (D); Agrius (E); Circe; Diomedes; Heracles; Odysseus.

Agro-manyus (Persia) *see* Angra Mainyu.

Agroata (Greek) *see* Agrius (A).

Agros *Agrotes, Agroueros* (Phoenician)
Also known as: *El.*
Hunter, or high god. Son of Technites and Geinos. Grandson of Agreus and Halieus. Associated with Melqart. *See also* El.

Agrotes (Greek) *see* Agrius.

Agroueros (Phoenician) *see* Agros.

Agrouneros (Greek) *see* Agrius (A).

Agu (Akkadian)
Also known as: *Aku.*
Male Moon God. *See also* Aah (Egypt); Sinu (Semitic).

Aguilo (Greek) *see* Aquilo.

Agunua *Argunua* (Solomon Islands, Melanesia)
Serpent deity. Agunua created men and one woman, as well as the sea, land and storms. It is said that he created rain because he was thirsty. He instructed his brother to plant a yam from which sprang the original banana, coconuts, and almond trees. One day, his brother planted a batch of yams incorrectly and from that time forth certain plants became inedible forever. *See also* Gainji; Tagaros.

Agusaya (Babylon)
Also known as: *Ishtar.*
Goddess of loud-crying. She is an aspect of Ishtar, who is also a the goddess of loud-crying or wailing. Agusaya is associated with Ea and Saltu (discord). *See also* Ishtar.

Agwe (Haitian)
Voodoo god of waters, wind, thunder, boats and seashells. He lives on an underwater island. A blue-colored ram is sacrificed in his honor. Similar to St. Ulrique of the Catholics.

Agweta (Dahomey People, Africa) *see* Agbe.

Agweto (Dahomey People, Africa) *see* Agbe.

Agyieus (Greek) *see* Apollo.

Agyieyus (Greek) *see* Apollo.

Ah (Egypt) *see* Aah; Astarte.

Ah (Egypt) *see* Astarte.

Ah-hetep (Egypt)
Sovereign Chief. One of the four chiefs guarding the Fifth Division (hour) of Tuat. *See also* Tuat.

Ah-Kiuic (Maya People, Yucatan)
Also known as: *Echauc.*
God of plenty and of merchants. He is one of the triad of Chac and Hobnel. *See also* Chac Mol; Hobnil.

Ah Puch (Maya People, Yucatan) *see* Ahpuch.

Ah Puchah (Maya People, Yucatan People, Yucatan People, Yucatan) *see* Ah Puch.

Ah-uuc-chek-nale (Maya People, Yucatan) *see* Ahmucen-Cab.

Aha (Egypt) *see* Bes.

Ahalya (Brahmanic, Hindu; India)
An early goddess, some say that Ahalya, "Night," was the first woman created by Brahma. The spouse of the sage Gautama, her great beauty caught the attention of the promiscuous god Indra. His overtures to her were on the verge of being satisfied when Gautama walked in on them. He cursed Indra with a thousand marks of the yoni (female sex organ). Later, he reconsidered his curse and transformed the yoni to one thousand eyes. The lighter sentence was given because the actual sex act had not taken place. Indra, overcome with passion, convinced the moon to assume the shape of a cock and to crow while it was still night. When Gautama heard the familiar sound, he rose and left to perform his morning prayers. Indra seized the opportunity and assumed Gautama's form and entered Ahalya's bed. This time Gautama caught them and turned his wife to stone. She remained in that state until many years later, when Vishnu, in his incarnation as Rama, kicked her. Once again alive, she was reunited with Gautama. Indra was cursed to become a eunuch and was only saved from his fate by the intervention of the gods. *See also* Brahma; Indra; Indrani; Rama; Vishnu.

Ahana (India) *see* Athena.

Ahans (India) *see* Asvins.

Aharman (Persia) *see* Angra Mainyu.

Ahat (Egypt)
Also known as: *Ahet, Ahit, Ehat, Ehet.*
Protector deity. Ahat is the cosmic cow who nurses and protects the sun god, Ra. *See also* Amen; Ra.

Ahau-Chamahez (Maya People, Yucatan)
Lord of the Magic Tooth. A god of medicine.

Ahayuta Achi (Zuni People, North America)
They are twin culture heroes, or according to some, twin

gods of war. They protect gamblers and mischief-makers. They are also responsible for destroying monsters and rapists. Protectors of Zuni villages, they live inside mountains. The Ahayuta Achi provided men with implements, and taught them to hunt. The twins are the sons of Dripping Water but were raised by Spiderwoman, their grandmother.

Aherat (Middle East) *see* Asherah.

Ahet (Egypt) *see* Ahat.

Ahhazu *Ach-Chazu* (Babylonia, Sumer)
Also known as: *Labasu.*
Demon of death, disease and pestilence. Ahhazu is probably the same as Labasu and one of the group of twelve demons of the Sumerians. These include Alu, Lamashtu, Lilith, Lilu, and Utukku. *See also* Als; Lilith.

Ahi (Egypt, Persia, India.)
Also known as: *Azi, Azhi Dahaka, Vrita.*
Ahi is the Persian Azhi Dahaka (meaning "biting snake"). The Vedic Ahi, (his alternate name is Vritra) is the celestial snake who withheld rain, and was defeated by Indra. In other interpretations, Ahi is the son of the serpent god Danu and Vrita. To the Egyptians Ahi represented daytime. Ahi is depicted as a dragon or a snake. Ahi is comparable to Visvarupa and Azhi Dahaka (qq.v.). *See also* Angra Mainyu; Azi; Ihi; Vrita; Zohak.

Ahi-Mu (Egypt)
One of the forty-two Assessors (judges of the dead). *See also* Assessors.

Ahiah (Hebrew) *see* Jehovah.

Ahimsa (India) *see* Narayana (C).

Ahit (Egypt) *see* Ahat.

Ahkinshok (Aztec People, Mexico)
No particular function, but may be one of the day gods. He lives below the earth and has several titles: Guardian of Bees, Owner of the Days, and Spirit of New Fire. *See also* Kasin; Yumchakob.

Ahkushtal (Aztec People, Mexico)
Birth deity. Little shown, but appears to be associated with other gods below the earth. *See also* Kasin; Yumchakob.

Ahmakiq (Aztec People, Mexico)
Wind deity. His function is to lock up the winds that destroy crops. Patrons of medicine and other workers who tend ill humans can be locked up or otherwise controlled by this god. He lives below the earth. *See also* Yunchakob.

Ahmes-Neferatari (Egypt) *see* Amenhotep I.

Ahmucen-Cab (Maya People, Yucatan)
Creator. The legend is rather confusing, but essentially the deity came down and covered the faces of the Oxlahun-ti-Ku, who were thirteen gods. Ahmucen-cab had other names, a sister and children but neither his other names nor the names and faces of any of them were seen. It is possible Oxlahun-ti-Ku was one of his names and he was captured by Bolon-ti-Ku (nine gods) after he brought down stones and trees. In the legend the Bolon-tsac-cab (nine orders) covered the world with a blanket of seeds and went back to the thirteenth heaven. The world was then formed. After this the legend follows that of the Legend of the Four Suns, except the four Becab (also known as Cantul-ti-Ku) destroyed this world then placed the mortal Kanxib-yui on the new world they created. The story proceeds with the goddess Itzam-kab-ain, who is a female whale with alligator feet, impregnated by Ah-uuc-chek-nale. Thus, the world began. *See also* Bacabs; Legend of the Four Suns.

Ahoeitu (South Pacific)
He is the king of Tonga, the son of the sky god Eitumatupua, and the earth goddess Ilaheva. *See also* Eitumatupua.

Ahpuch *Ah Puch, Ah Puchah* (Maya People, Yucatan)
Also known as: *Ahpuch Yum Cimil, Eopuco, Hanhau.*
God of death. A demon, Ahpuch slayed the Becabs. In one of his several aspects, he is the ruler of the ninth sector (or layer) of the underworld. In another version he was called a "Demon Destroyer" and "Lord of Death." *See also* Becabs; Ek Ahau; Hanhau.

Ahpuch Yum Cimil (Maya People, Yucatan) *see* Ahpuch.

Ahrenkonigin (Austrian) Goddess of the Harvest.

Ahriman (Persia) *see* Angra Mainyu; Drujs.

Ahrimanes (Persia) *see* Aryaman.
Ahsonnutli and Yolaikaiason (North America) *see* Atseatsan and Atseatsine.

Ahti *Ahto* (Finland)
Also known as: *Kaukomieli, Lemminikainen.*
God of the waters and fishermen. Consort of Wellamo (also spelled Vellamo). They live deep under the sea in a place known as Ahtoia (Atola). He is holder of the treasure Sampo. Some say Lemminkainen bore the epithet Ahti so he could be both god and hero. His servants are Vetehinen, and Tursa a sea monster. He is shown with a beard of moss. *See also* Lemminkainen; Naaki.

Ahto (Finland) *see* Ahti.

Ahu (Egypt)
One of the principal gods shown in the Pyramid Texts.

Ahuehuete (Aztec People, Mexico)
Tree of life. The only two survivors of the great deluge were a man and woman who climbed this tree. Some say their names are Nala and Nina.

Ahura (Persia) *see* Ahura Mazda.

Ahura Mazda *Ahura, Asura, Auramazda* (Manichean, Zoroastrian, Zurvan; Persian, Iranian)
Also known as: *Bag-Mazda, Horomazes* (Greek), *Hormazu, Ohrmazd* (Iranian), *Ormazd* (the later name of Ahura Mazda under the Sassanians), *Oromazez, Ormuz, Ormuzd, Thraetaona.*
Ahura Mazda ("Wise Lord") is the creator of all good, and the Supreme God of the Zoroastrians. His adversary and opposite is Angra Mainyu. Ahura Mazda is the president of the council of six ministers (sometimes seven), known as the Amesha

Spentas, also called the "Augmentative Immortals." The Amesha Spentas, three male and three female, are said to be aspects, personifications, or attributes of Ahura Mazda. Some scholars believe that they are based on ancient gods. In later times they were thought of as gods or archangels. Ahura Mazda revealed himself to humans through the Amesha Spentas. After the creation of the Amesha Spentas, the Yazatas were created, followed by the creation of the universe and mortals. In one myth, Angra Mainyu was born from Ahura Mazda during a moment of doubt. In another, Ahura Mazda and Angra Mainyu existed but were separated by the Void. It happened that Angra Mainyu came upon Ahura Mazda and his light and following his nature attempted to destroy him. He refused Ahura Mazda's offer of peace, which was conditional upon him praising the Good Creation. In the orthodox tradition, an agreement was reached. History spans twelve thousand years. The first three thousand years were allocated to creation. The second three thousand years passed according to the will of Ahura Mazda. The third three thousand years are mixed with the will of Ahura Mazda and Angra Mainyu. In the fourth three thousand year period, Angra Mainyu and all evil will be destroyed. There are variations of this creation myth, and some are based on a nine thousand year cycle. The Zurvan tradition considers the first nine thousand years as the period of the rule of evil. Evil will be defeated during the final three thousand years. In the Zoroastrian tradition, Angra Mainyu created the sky. It served as a cover to enclose the world and to trap Angra Mainyu. Originally, the world was in an ideal state. The first man, Gaya Maretan, shone like the sun, until Angra Mainyu, persuaded by the female demon, Jahi, woke from a deep sleep and attacked creation. In the Manichean tradition, there are two realms: light, ruled by the Father of Greatness, and dark, ruled by the Prince of Darkness. Originally, the two realms existed in a balanced state. The Prince of Darkness, attracted by the light, upset this balance by permeating light, including the light of the Primeval Man. The god Mithra attempted to punish the demons of darkness. From the skins of the defeated demons, he created the skies; the mountains were made from their bones. The earths (four or eight in number), the ten firmaments, the zodiac, the constellations and planets were created from their flesh and excrements. Uncontaminated light particles were used to create the sun and moon, while the stars contained partially contaminated substance. The animal and vegetable world, came into existence, and because of their origin, they contained undelivered light particles. Ahura Mazda is depicted as a bearded man with a winged, plumed body and a sacred tree. In an ancient bas relief Ahura Mazda is depicted in the same costume that King Darius I (521–486 B.C.E.) wore: a wide-sleeved tunic with a circle representing the sun's disk at the waist of his long robe, a cap on his head and a long beard on his face. He has wings and is poised in the air. He is also shown enclosed in a winged circle. He appears bearded, stately in demeanor, in a stance of benediction. In another depiction, he is shown putting on the solid heavens as a garment and covering himself with his symbol, flames of fire. The Zoroastrians use one hundred and eight names to denote the attributes of Ahura Mazda. He is vaguely connected with Khaldi (Armenian, Iranian). *See also* Aeshma; Akhtar (The); Ameretat; Amesha Spentas; Anahita; Angra Mainyu; Aramzad (Armenia); Asha Vahishta; Asuras (India); Atar; Avesta; Bag-Mashtu; Bundahish; Chinvat Bridge (for life after death); Fravashi; Gaokerena Tree; Gaya Maretan; Haoma; Hariati (Mount); Hvare-khshaeta; Jahi; Khshasthra Vairya; Mitra; Nairyosangha; Rapithwin; Rashu; Spenishta (sacred fire); Spenta Armaiti; Thrita; Tishtrya; Varuna (India); Vayu; Vohu Manah; Yazatas; Yima.

Ahy (Egypt) *see* Herusmatauy.

Ai (A) (Akkadian, Egypt) *see* Aah.

Ai (B) (Norse; Teutonic)
Also known as: *Great Grandfather.*
God of Serfs. Ancestor of the race of serfs. Husband of Edda. Heimdall (also known as Rig) slept between Ai and Edda. From his union with Edda came Thrall who married Thir and from their union sprang the race of Thralls or serfs. *See also* Aah; Heimdall; Thrall.

Ai (C) (Estonian)
Also known as: *Hai* (Hebrew).
Thunder god.

Ai (D) (Teutonic) *see* Dwarfs.

Ai-Willi-Ay-O (Eskimo) *see* Sedna.

Aiai (Hawaii)
Aiai, the son of Ku-ula-kai, the god of abundance in the sea, followed his father's instructions and set up numerous fishing grounds around the island. When his son Punia came of age he too was instructed in this trade. Father and son worked together and expanded to other islands. *See also* Ku-ula-kai; Ku and Hina.

Aiaiakuula (Hawaii, Polynesia)
Goddess of fishers. *See also* Kuula.

Aiapakal (Tierra del Fuego)
The shamans, known as Yakamouch, converse with the god Aiapakal and gain their power from the spirit, Hoakils. *See also* Yakamouch.

Aiakos (Greek) *see* Aeacus.

Aiapaec (Peru) Supreme Deity.

Aias (Greek) *see* Ajax the Greater.

Aibheaog (Celtic) Ancient fire goddess.

Aida-Wedo (Haiti)
The rainbow snake goddess. *See also* Damballah.

Aides (Greek) *see* Cocytus; Hades.

Aidne (Celtic)
Fire god. He created fire for the Melesians by rubbing his hands together.

Aido Hwedo (Dahomey People, Africa; Haiti)
Aido Hwedo is the great rainbow serpent who served as the vehicle for the goddess Mahu as she created the universe. His excrement formed the mountains. When Mahu had completed her creation, she realized that the earth was too heavy. She had Aido Hwedo coil himself beneath the planet to keep it from toppling. Heat disturbs Aido Hwedo, so the seas were created to keep him comfortable. Whenever he shifts, an earthquake

occurs. When he has finished eating the iron bars beneath the sea, he will devour his tail and the world will come to an end. Believers are careful not to incur the wrath of the great serpent, for he is very jealous. Before marriages take place, special offerings are presented to Aido Hwedo and relatives invoke him not to harm the newlyweds. *See also* Damballah; Mahu.

Aidoneus (Greek) *see* Adonis.

Aife (Celtic) *see* Aeife.

Aigamuchab (Hottentot, Africa)
Ogre. Little known about this fellow, except he is a cannibal with eyes on top of his feet.

Aighistos (Greek) *see* Aegisthus.

Aigi'pan (Greek) *see* Aegipan.

Aigina (Greek) *see* Aegina.

Aigis (Greek) *see* Aegis.

Aigisthus (Greek) *see* Aegisthus.

Aigle (Greek) *see* Aegle.

Ailanthus (China)
This tree of paradise has a beautiful flower that has an offensive aroma. Tenacious, it can grow under the most adverse of conditions.

Aileili (Celtic) *see* Mider.

Aillen (Irish) *see* Aine.

Ailo (Hebrew) *see* Lilith.

Ailuros (Egypt) *see* Bast.

Aimon Kondi (Arawak People, New Guinea)
In the Creation Legend, Aimon Kondi set the world on fire. Marerewana and his people sought refuge in caves. A great deluge followed, and the survivors escaped in canoes. *See also* Makonaima.

Aindra (India) *see* Aindri.

Aindri *Aindra* (India) *see* Arjuna; Indra; Indrani.

Aine (Irish)
Aine was known as the Irish goddess of love and thought by some to be a moon goddess, fertility goddess and goddess of cattle. She is variously called the sister of Aillen and daughter of the fertility Eogabal, or the sister of Fenne (Fennen) and daughter of Eogabal. Eogabal in this version was a king of the Tuatha de Danann, and Aine was the wife of Gerold, the Earl of Desmond. Their child was Earl Fitzgerald. A variation on this theme is that Gerold Iarla (Earl Gerald of Desmond) came upon Aine bathing in a river and raped her. Gerald, a magician of repute, turned into a goose and disappeared, although others say that Aine killed him with her magical powers. He is said to live in the waters of Loch Gur. Every seven years he makes an appearance mounted on a white horse which trots around the perimeter. In another rendition, Aine is known as the wife and daughter of Manannan Mac Llyr. A feast, Midsummer Night, was held in her honor. Farmers waved straw torches over the fields and cattle to insure replenishment. In later times, as Aine she was worshipped as a fairy queen in South Munster. Aine is sometimes identified with Dana, and she has been said to be identical to Anu. *See also* Anu; Dana; Manannan Mac Llyr.

Aineias (Greek) *see* Aeneas.

Aino (Finland) *see* Vainomoinen.

Ainu-rak-kur (Japan) *see* Okikurumi.

Aion (A) (Gnostic) *see* Aeons.

Aion (B) (Phoenician) *see* Kolpia.

Aior-Pata (Greek) *see* Amazons.

Aipaloovik (Eskimo)
Evil god of the sea. Aipaloovik lives deep in the ocean and is a danger to all fishermen or those who venture out to sea. *See also* Adlivun; Agloolik.

Air (A) (Phoenician)
In the Creation Legend of Damascisu, Air is the son of Omicle and Potos (meaning desire), who with his sister Aura became the parent of Otos (meaning reason). *See also* Air (B); Aura, Kolpia (for the Creation Legend of Philos Byblos).

Air (B) (Phoenician)
In the beginning, Air and Chaos existed. Their union produced Kolpia (Wind) and Potos (Desire). (From the Creation Legend of Philo Byblos). *See also* Air (A); Chaos; Kolpia.

Air (C) (Phoenician)
Air and Ether engendered Oulomos in the Creation Legend of Mochus. *See also* Air (A); Air (B); Oulomos.

Air, God of (Egypt) *see* Shu.

Airavarta (India) *see* Airavata.

Airavata *Airavarta, Airawata* (India)
Indra's divine white elephant. *See also* Dikpalas; Indra; Kurma; Lokapalas; Swarga.

Airawata (India) *see* Airavata.

Aireskoi (Iroquois) *see* Areskoui.

Aireskouy (Iroquois) *see* Areskoui.

Airmid (Celtic)
The goddess of witchcraft and herb lore, she is the daughter of Dia'necht and the sister of Miach. It was Airmid and Miach who healed King Nuada. *See also* Dia'necht; Nuada.

Airya *Iraj* (Persian) *see* Thrita.

Airyano Vaejo (Iranian)
Heaven or Eden. This is a place of bliss where no one grew old until Ahriman (earlier known as Angra Mainyu) came and brought ten months of winter each year.

Ais (A) (Armenia) *see* Devs.

Ais (B) (Greek) *see* Hades.

Aisar (Norse) *see* Aesir.

Chapter V
Cosmic Healing I - Basic

- Source of Chi and Colors 126
  - Earth Chi 127
  - Human and Nature Chi 128
  - Solar Chi 128
  - Simple Practice 128
  - General Information 128
- Healing Colors 129
  - White Chi 129
  - Blue Chi 129
  - Green Chi 129
  - Red Chi 130
  - Tangerine Chi 131
  - Yellow Chi 131
  - Violet Chi 131
  - Golden Chi 133
  - The Spleen 133
  - Cosmic Healing Planetary Colors 134
- Summary - Working with Color 135

Chapter VI
Individual Healing Session

- Almighty Knife 138
  - Outline of Practice 139
- Energizing and Activating the Immune System 141
  - Outline of Practice 142
- Cleansing the Internal Organs Technique 143
  - Healing Some Common Illnesses 143
  - General Principles 145
  - Outline of Practice 146
  - Cleansing the Spinal Cord 149
  - Cleansing the Blood (Lungs) 150
  - Outline for Cleansing the Blood/Lungs 150
  - Circulatory/Heart System 151
  - Stomach Pains 151
  - Relieving Pain: Blue Chi 152
  - Headache: Light Whitish Green and Light Whitish Blue Chi 153
  - Migraine Headache: Light Whitish Green Blue and Violet Chi 153
  - Toothache: Light Whitish Green and Blue Chi 153
  - Broken Bone: Orange - Yellow Chi 153
  - Back Injury: Light Whitish Blue and Green Violet Chi 154

Aither *Aither* (Greek)
Deities of light. Heavenly light. In Hesiod's version of creation, the god Aither and goddess Hemera (Day) were born of Gaea (Earth), Tartarus (Underworld) or Eros (Love). In other traditions, Hermera is the daughter of Erebus (Darkness) and Nyx (Night). She is also said to be the mother of Phaethon by Cephalus. Phaethon was kidnapped by Aphrodite to be the protector of her shrine. For siblings of Hemera, *see* Aether.

Aithre (Greek) *see* Aether; Aither.

Aithuia (Greek) *see* Athena.

Aitvaras (Prussian, Lithuanian)
This little demon of good fortune is found behind the big stove in the house. He feeds on leftover food. In Lithuanian legend, he is known to steal items, usually corn, milk, meal and coins to bring to his master. When he is flying he appears like a fiery tail. In the house he looks like a cock. A family can purchase him or acquire him from the egg of a seven-year-old cock. He must be fed omelets. For the price of one's soul he can be purchased from the devil. Once in a while, he is found and his identity is not known when he is brought into the house. Once ensconced, it is difficult to drive him away, although he can be killed. *See also* Domovoi.

Aiwel (Africa) *see* Aywil.

Aiwel Longar (Africa) *see* Aywel.

Aiyai (Tamil People, India)
Aiyai is an ancient goddess of hunters. Followers' severed heads were offered to her in sacrifices. Dressed in leopard skin and wearing a tiger's teeth necklace, she wields a black sword and carries a bow. Her mount is a stag decorated with snakes. *See also* Kali; Karitay.

Aiyanar (India) *see* Gramadeveta.

Aizen Myo-O (Japan) *see* Aizen-Myoo.

Aizen-Myoo *Aizen Myo-O, Aizenmyo-o, Aizenmyo-wo* (Buddhist, Shinto, Japan)
Also known as: *Raga-vidyaraja* (Buddhist).
God of Love and Sexual Desire. His look is supposed to portray the suppression of passionate lusts. In some versions he is regarded as secret. According to legend he manifests the state when agitation becomes enlightenment and the passion of love becomes the compassion for everything that lives. According to some the moment of agitation takes the form of a Vajrasattva and becomes Aizen-Myoo. Pictured as a red, glaring, three-eyed, frowning god, with six arms, and an unusual hair arrangement. He also has a lion head nestled in his hair. He carries a bell, a stick, a bow and arrow, a thunderbolt and a lotus in his hands. In some forms he can have two heads and two, four or six arms.

Aizenmyo-o (Japan) *see* Aizen-Myoo.

Aizennyo-wo (Japan) *see* Aizen-Myoo.

Aja (Babylon) *see* Aya.

Aja Ekapada (Hindu; India)
Aja is a lightning god and the name signifies a one-footed goat. Aja Ekapada may symbolize the swiftness of the strike of the lighting bolt. In the Vedic tradition, the goat is called Aja. A-ja means "unborn." *See also* Rama.

Ajagava (India) Shiva's Sacred Bow. *See also* Shiva.

Ajan (Islamic) *see* Jinn.

Ajatar *Ajattara* (Finnish)
Devil of the Woods.
An evil female dragon who suckles snakes and causes disease.

Ajattara (Finnish) *see* Ajatar.

Ajax the Greater (Greek)
Also known as: *Aias.*
Warrior and hero. Ajax, the son of Telamon and Periboea or possibly Eriboea, is known as "the greater" because of his height. It has been said that he was the tallest of the Greeks. His consort was Tecmassa and their child was Eurysaces. A prince or king of Salamis, and one of Helen's suitors, Ajax was considered almost as powerful and brave as Achilles and proved himself a hero when the Greeks attacked Troy. It was Ajax who lifted Achilles' body from the battle while Odysseus held the enemy at bay. Later it was decided that either Ajax or Odysseus should be given the armor of Achilles. A secret vote was taken and Odysseus received the honors. Ajax, ashamed and humiliated, suffered a breakdown and began to slaughter sheep, believing the animals to be his enemies. A vestige of sanity remained and it is said that he committed suicide rather than taking the chance of killing his colleagues. In other versions of his death he was said to have been murdered by Paris, Odysseus or Teucer and from his blood the purple hyacinth sprang forth. *See also* Acamas (C); Achilles; Aeacus; Ajax the Lesser; Helen.

Ajax the Lesser (Greek)
Ajax the Lesser is the hero son of Oileus, the king of Locris, who was an Argonaut and one of Apollo's lovers. Ajax's mother was either Eriopis or Rhene. Swift of foot, he had a reputation for being able to outrace all but Achilles, although in another legend he was placed at the funeral games of Patroclus and he lost a race to Odysseus. He was often in the company of Ajax the Greater and although he was a courageous warrior, he was also a brute and a braggart. It is said that when the Greeks conquered Troy, Ajax the Lesser raped Cassandra, one of Athena's priestesses. Athena struck back by causing a shipwreck when he was en route home. He survived by clinging to a rock and declaring that he did not need the assistance of the gods to remain alive. This incensed the sea god Poseidon who with his trident ruptured the rock and Ajax sank to his death in the sea. *See also* Ajax the Greater; Athena; Cassandra; Poseidon.

Ajbit (Maya People, Yucatan)
Creator deity. One of thirteen gods who tried to create man from wood after two other attempts had failed. *See also* Ajtzak; Tzakol.

Aji-suki-Taka-hi-kone (Japan) *see* Aji-suki-takahikone.

Aji-suki-takahikone *Aji-suki-Taka-hi-kone* (Japan) *see* Take-mi-kazuchi; Taki-tsu-hiko.

Ajita (Buddhist; India)
Also known as: *A-shih, Ma-p'am-pa* (Tibet), *Me-phem-pa* (Tibet), *Maitreya, Mi-Lo Fu* (China).
A deified mortal who is the second arhat (one of sixteen, later eighteen apostles). He is usually depicted in a meditative pose with his head covered. *See also* A-shih; Abheda; Maitreya; Mi-Lo Fu (China).

Ajnesvara (India) *see* Vishnu.

Ajorsum (Saora People, India)
This snake god lives in streams. For other deities *see* Adununkisum; Arsi Basum.

Ajtzak (Maya People, Yucatan)
Creator deity. Ajtzak belongs to a group of creator gods who attempted to create humans from wood. The other deities are Hunahpu, Hunahpu-Guch, Ixmucane, and Ixpiyacoc.

Ajuna (India) *see* Garuda.

Ajy-khoton (Yakut) *see* Ajysyt.

Ajysit (Yakut) *see* Ajysyt.

Ajysyt *Ajysit, Ijaksit* (Yakut People, Siberia)
Also known as: *Ajy-khoton.*
Ajysyt is goddess of childbirth and domestic animals, particularly cattle. She brings the new soul from heaven to the child being born and writes the child's fate. She is always depicted laughing. *See also* Khotun.

Ak (Akkadian) *see* Nebo.

Aka (Turkish) *see* Akha.

Aka-Kanet (Araucanian People, Chile) *see* Akanet.

Aka Manah *Aka-Manah, Akah Manah, Ako-Mano, Akoman* (Persia)
He is known as the demon of vile thoughts and discord. Aka Manah was created by Ahriman to be one of his assistants. *See also* Angra Mainyu; Daevas; Darvands; Vohu Manah.

Akadja (Dahomey People, Africa; Haitian) *see* Bossu.

Akalo (Solomon Islands)
The Akalo is the friendly ghost of the dead or the soul of the living. The Akalo is caught with a diminutive rod and placed in a container with the skull, jawbone, tooth and a lock of hair from the deceased. When illness strikes offerings are made to the Akalo. Offerings are also presented at the beginning of the yam harvest. The ghosts of mortals with spiritual power become Li'oa. *See also* Agunua.

Akamas (Greek) *see* Acamas (A).

Akanet (Araucanian People, Chile)
Also known as: *Aka-Kanet, Algue.*
Although a protector of man, this deity of fruit and grain can be cruel at times. He may have originated as a culture hero. Akanet presides over harvest festivals. His counterpart and possible twin is the evil Guecubu (his name means "The Wanderer Without"). *See also* Epunamun; Pillan.

Akar (Egypt) *see* Aker.

Akara (Egypt) *see* Aah.

Akasagarbha (Japan) *see* Dhyanibodhisattvas; Gundari-Myoo; Kokuzo-Bosatsu; Kshitigarbha; Samantabhadra.

Akatauire (Polynesia) *see* Rangi.

Akbal (Aztec People, Mexico) *see* Huecomitl.

Ake (Polynesia) *see* Aokeu.

Akebiu (Egypt)
Deities of crying. "The Wailers." These are four bearded gods found in the eleventh sector of Tuat. *See also* Tuat.

Akeneh (Egypt)
Akeneh is a serpent demon mentioned in "The Text of Unas," a king in the fifth dynasty. This text describes magical methods to destroy serpents and barbarous beasts. Other serpents mentioned are, Amen, Antaf, Hau, Heka, Hekret, Hemth, Nai, Senenahemthet, Setcheh, Tcheser-tep, Thethu, and Ufa. *See also* Ab-esh-imy-duat; Ab-ta; Apepi; Apophis.

Aker (Egypt)
Also known as: *Akar, Akeru.*
Guardian animal. Earth god. A double-headed lion god who guards the gate of the dawn through which Ra the sun god passes each morning. He is connected with Set as a deity of gloom and of early dawn and twilight when demons are about. The keeper of the gates that open to the underworld address the deceased soul by saying, "the gates of the earth-god [Aker] are opened unto you." (From "The Pyramid Texts.") Aker is represented in one version as a narrow piece of land with a human or lion head at either end. In another version these symbols guard the entrance and exit of the underworld and are depicted as a double-headed lion or sphinx seated back to back. One faces the west, where the sun begins its travels into the night and one the east, where the sun appears each morning. *See also* Teta, and Unas (the god-eating god), who were early kings in the fifth and sixth dynasties. Because the kings were as powerful in the afterworld as when mortal, it is said that the bones of Aker tremble when these deified kings pass through. Aker is sometimes identified with Qeb. *See also* Unas.

Akeru (Egypt) *see* Aker.

Akesi (Egypt) *see* Aaru.

Akethor (Teutonic) *see* Thor.

Akewa (Toba People, Argentina) Sun goddess.

Akh (Egypt)
The Akh is thought of as a spirit of a god who dwells in heaven and matches the human counterpart. At death, the Ka (double) splits and turns into a bird, the Akh, which flies into the afterlife and turns again into the Ka. The Ba (soul) stays behind on earth. *See also* Ba; Ka.

Akha *Aka* (Assyro-Babylonia, Burait, Turkey)
Also known as: *Acca Larentia* (Roman), *Alka, Akha,* (Lapp), *Ekhi* (Accadian), *Sar-Akha* (Lapp), *Ummu* (Assyrian).
A Mother Goddess. The Lapps call her Sar-Akha ("Lady Mother"). The Akkadian word Ekhi is rendered Ummu (mother) in Assyrian. *See also* Acca Larentia.

Akhekh (Egypt)
Akhekh is an aspect of the evil god Set. Shown as a griffin, he has the body of an antelope and the head of a bird. The head is surmounted by three uraei and wings. *See also* Set.

Akheloos (Greek) *see* Achelous.

Akhem-Sek (Egypt)
Celestial beings who are called "Those who never go down."

Akhen (Egypt)
Also known as: *Ab-esh-imy-duat, Ab-She.*
Serpent monster. The meaning of Akhen's name is likely indicative of his personality; it means "to split" or "wear out the eyes." A monster serpent, his responsibility is to guard the seventh section of the underworld (Tuat) as Ra, the sun god passes in his boat. *See also* Ab-Esh-Imy-Duat; Ab-she; Ab-ta; Akeneh; Apepi; Apophis.

Akhet-nen-tha *Akhenaten, Ikhnaten* (Egypt)
Also known as: *Amenhotep IV.*
Akhet-nen-tha is the son of Amenhotep III and Queen Tiy. When he succeeded his father, he moved his court from Akhenaten in Thebes to Tell el-Amarna. He forbade the worship of Amen and devoted himself to the worship of Aten. This period in Egyptian history is known as the Amarna Heresy. He was married to the beautiful Nefertiti. For further information on this period, *see also* Amen; Aten.

Akhmiu (Egypt) *see* Tuat.

Akhrokhar (Gnostic) *see* Pistas Sophia.

Akhtar, The (Persia)
They are the twelve constellations created by Ahura Mazda, who are regarded as generals of his army. Other stars or constellations mentioned are Hapto-iringa, Satavaesa, Tishtrya and Vanant. *See also* Ahura Mazda; Hapto-iringa; Tishtrya; Yazatas.

Akhtya (Zoroastrian; Persia)
Chief of the demon magicians and sorcerers known as the Yata. *See also* Pairikas; Yata.

Aki-bime-no-Kami (Japan) *see* Ukemochi.

Aki-Yama no Shitabi-onoko (Japan)
God of Winter. He is called the frost man of the autumn mountain. His brother is Haru-Yama-no-Kasumio-noko.

Akinetos (Gnostic) *see* Aeons; Nous.

Akka (A) *Aka* (Estonian, Finnish)
Also known as: *Emader-Akka, Rauni.*
Harvest deity. Wife of Jumala and later, Ukko. She is sometimes said to be a goddess of female sexuality. She created the bodies of mankind after Jumala created their souls. Akka is shown as a triangle or six-sided polygon. The mountain ash is her symbol. *See also* Jumala.

Akka (B) *Aka, Ekki* (Turkey) Mother goddess.

Akkruva *Avfruvva* (Finno-Ugric)
Also known as: *Havfru.*
Goddess of rivers. This presumably lovely half-woman, half-fish, fills the rivers with fish. *See also* Havfru.

Akna (A) (Maya People, Yucatan)
Mother goddess. Birth goddess (possibly). Wife of Akanchob. She is associated with the Becabs (q.v.).

Akna (B) (Eskimo)
"Mother." Goddess of childbirth.

Ako-Mano (Persia) *see* Aka Manah.

Akoman (Persia) *see* Aka Manah.

Akongo (Nagombe People, Africa)
Supreme god. This god once lived with people on earth or as some say, heaven. The turmoil created by humans was unbearable to him. He went off into the forest and has not been seen again. Akongo placed the giant Libanja in the east and the giant Songo in the west to hold up the sky with poles. When they let go of the poles it will be the end of the world. *See also* Amma; Nommo.

Akra (Persia) *see* Simurgh.

Akrura (India)
Chief Demon of Kansa's Court. *See also* Kansa; Syamantaka.

Aksak (Chaco People, South America)
Creator. Beetle who created men and women from clay.

Akselloak (Eskimo) The good spirit of rocking stones.

Akshobhya *Akshyobhya* (Nepal), *Aksobhya* (Tibet); (Buddhist; India)
Also known as: *Dhyani Buddha Gozanze-Myoo* (Japan), *Gozanze-Myoo* (Japan), *Heruka* (wrathful aspect), Trailokyavijaya (terrible aspect).
Akshobhya, the god of consciousness, is the second of the Dhyani Buddhas (Buddhas of meditation). He is the guardian of the East. His consort (sakti) is Locana, known as the Buddha Eye and in some renditions, Mamaki. The Japanese deity, Gozanze-Myoo, one of the Godai-Myoo (Five Great Kings), is an aspect of Akshobhya and one of the protectors of Buddhism. In some traditions of Buddhism, particularly in Nepal, Akshobhya is said to originate from the blue syllable "Hum." He is believed to represent the primordial cosmic element of Vijnana (consciousness). In Bardo, the Tibetan Buddhism after-death state, Akshobhya and Locana appear embracing. They are accompanied by two male bodhisattvas, Kshitigarbha the Essence of Earth and Maitreya the Loving One. There are also two females: Lasya, a bodhisattva of dance, and the bodhisattva Puspa, the goddess of flowers. The name Akshobhya means "Immovable." Akshobhya has one face and two arms and is blue in color. He exhibits the bhusparsa mudra (pose), which is the earth-touching gesture. This gesture commemorates Gautama Buddha's victory over temptation by the demon Mara. The right arm rests over the right knee. The palm is turned inward and the fingers extended downward with the middle fingers touching the ground. The left hand rests on the lap with the palm upward. This gesture is also characteristic of Sakyamuni. When represented in the shrine he always faces the east as this is the area he protects. His symbol is the thunderbolt, denoting spiritual and mystical power. His vehicle is a pair of elephants. His consort Locana's color is blue. Her emblems are the kapala (skull cap) and vajra (thunderbolt). Her mudras are

varada; the arm pendant, fingers extended outward, palm turned outward, and vitarka; the arm bent, fingers extended upward, except index finger, which touches the tip of the thumb, palm turned outward. The varada signifies charity and the vitarka signifies argument. The Buddha Eye, in this case, means spiritual awakening. *See also* Amida; Avalokitesvara; Bhaishajyaguru; Chandamaharoshana; Dhyani Buddhas; Gozanze-Myoo; Heruka; Maitreya; Mamaki; Mara; Prajnaparamita; Ratnasambhava; Trailokyavijaya; Vairocana; Vajrapani; Vajrasatwa.

Akshyobhya (Nepal) *see* Akshobhya.

Aksobhya (India) *see* Akshobhya.

Aktiophi (Greek) *see* Hecate.

Aku (Akkadian) *see* Agu.

Aku-Thor (Teutonic) *see* Thor.

Akua (Polynesia) *see* Atea.

Akuj (Kenya, Africa)
This benevolent deity may be consulted by anyone by throwing a sandal in the air. The way the sandal lands will indicate the answer to a question.

Akupara (Hindu, India)
The tortoise upon which the earth rests.

Akusaa (Egypt) Sunset goddess.

Akycha (Eskimo People, United States) God of the Sun.

Al (A) (Afghanistan)
A female of about twenty years old who feeds upon corpses. She has long nails and teeth and her feet are reversed.

Al (B) (Ugarit, Syria) *see* El.

Al Ait (Phoenician) God of fire.

Al-Amin (Arabic) *see* Mohammed.

Al-lat (Arabic) *see* Allat.

Al Ussa (Arabic) *see* Al-uza.

Al-Uza *Al Ussa, Al-Uzza, Al'uzzah* (Arabic)
Also known as: *Uzzah.*
An early Arabic goddess, she formed a triad of desert goddesses with Allat and Menat. Some texts say she is a little known goddess who may represent the planet Venus. In other versions she is an angel whose idol was destroyed by Mohammed. She may have been a sky deity. *See also* Allat; Unsas.

Ala (A) (Arab) *see* Alilah; Allah.

Ala (B) *Ale* (Ibo People, Nigeria)
Also known as: *Ane,* Lawgiver of Society, Queen of the Dead.
Ala the earth mother is the creator of the living and queen of the underworld. A lawgiver and guardian of morality, her name is used in courts of law to uphold oaths. During planting first fruits and harvest, sacrifices are given at her sacred tree. She is sometimes depicted with a child.

Ala (C) (Sumer)
Bisexual demons who can be impregnated by humans.

Alaghom Naom *Alaghom Naum* (Gnostic)
Also known as: *Iztat Ix, Mother of the Mind.*
Alaghom Naom is the supreme goddess and mother of wisdom. She is the creator of mind and thought. Her spouse is the chief deity, Patol. *See also* Sophia-Prunikos.

Alah (Arabic) *see* Allat.

Alaisiagae (Teutonic)
Alaisiagae is a name for the goddesses of fate, the Valkyries (q.v.).

Alaka (India) Sacred City. *See also* Kuvera.

Alakaluf (Tierra del Fuego, South America)
Also known as: *Ona, Vaghan.*
Supreme deity. He is the spirit who created the world but it was refashioned by others. His abode is beyond the stars. Alakaluf never eats or drinks. If he is angered he can cause sickness of death.

Alakh (Khumbu-patas People, India)
Supreme god who revealed himself to the mendicant Govind, and 63 other disciples in the Himalayas in 1864. They worshipped a leader known as Bhima and his wife.

Alalus (Hittite, Hurrian)
Known as the father of the gods and the king of heaven, Alalus reigned for nine years until he was deposed by his son Anus. Upon leaving the heavenly throne, Alalus descended to Earth where he was fed by Kumarbis, the son of Anus, who later deposed his father. *See also* Anus; Kumbaris; Ullikummis.

Alambusha (India) *see* Apsarases.

Alan (Philippines) Deformed forest spirits.

Alastor (Greek)
He is the father of Alastor, who was killed in the Trojan war by Achilles.

Alat (Arabic) *see* Allat.

Alatuir (Slavic)
The waters under this sacred stone on the paradisaical island of Bouyan cured all illnesses. In later myths, Alatuir became the stone at the crossroads which warned of danger. That myth dissolved into the myth that Alatuir was the stone which served as the base for the Christian cross. *See also* Bouyan.

Alberich (Teutonic) *see* Andavari.

Albion (Greek) *see* Amphitrite.

Albiorix (Celtic)
Also known as: *Rigisamos.*
War god. Equivalent to Mars (Roman). His titles are "King of the World," and "Most Royal." *See also* Cocidius; Tuetates.

Albors, Mount (Persia) *see* Alburz, Mount.

Albunea (Greek) A local goddess who wasn't too well known.

Alburz, Mount *Albors, Mount* (Persia)
This largest of the cosmic mountains developed over an eight hundred year span when evil plunged through the sky, into the waters, and up through the center of world. The intense quake

that resulted caused the growth of Mount Alburz which spreads throughout the cosmos. The base is attached to the sky and the roots hold the earth together. From these roots, all other mountains are created. The peak of this mountain is Mount Tera, located in the middle of earth. Arezur ridge, the gateway to hell, is on the rim of the mountain. Shaken from their places in the universe by the arrival of evil, the sun, moon, and constellations began to revolve around the earth. They now enter the sky each day through one of the one hundred and eighty apertures on the east, and set through the one hundred and eighty apertures on the west side of the mountain. Beyond its peak lies Vourukasha the cosmic ocean. Mithra observes the world from his dwelling on Mount Alburz. *See also* Chinvat Bridge; Hariati (Mount); Mithra; Tree of Many Seeds; Vourkasha.

Alcaeus (A) (Greek)
He is the son of Perseus and Andromeda (qq.v). *See also* Gorgophone.

Alcaeus (B) (Greek)
Heracles' name at birth. His son by Omphale, the queen of Lydia, was also named Alcaeus. Heracles was her slave for three years. They had two other children, Algelaos and Lamus. *See also* Heracles; Omphale.

Alcaeus (C) (Greek)
He ruled Thasos on the island of Paros with his brother, Sthenelus. They are the sons of the famous athlete, Androgeus.

Alcathous (A) (Greek)
King of Megara. He is the son of Pelops and Hippodamia. For family lineage, *see* Pelops. *See also* Calydonian Boar Hunt; Hippodamia (C); Pelops.

Alcathous (B) (Greek)
He is the son of Porthaon and Euryte. He died at the hands of his nephew, one of the Seven Against Thebes, Tydeus or by Oenomaus, the king of Pisa.

Alcemene (Greek)
Alcemene is the daughter of the king of Mycenae, Electryon, and Anaxo, the daughter of Alcaeus and Hipponome, or Electryon and Eurydice. Her first marriage was to Amphitryon. Her twin sons, Heracles and Iphicles have different fathers. Zeus is the father of Heracles. *See also* Eurydice (C).

Alcestis (Greek)
She is the daughter of Pelias, the king of Iolcus, and possibly Anaxibia, who is the daughter of Bias and Iphianassa. She married the kindly Argonaut Admetus, and became the mother of Eumelas, who won the chariot race at the funeral games of Achilles and Perimele. Alcestis volunteered to die in her husband's place when he was ill. For details, *see* Admetus. *See also* Pelias; Savriti (B).

Alcides (Greek) Epithet of Heracles.

Alcimede (Greek)
She is the daughter of Phylacus and Clymene, who is the daughter of Minyas. The Argonaut Iphiclus is her brother. She married Aeson, the king of Thessaly and became the mother of the Argonaut Jason and possibly Promachus (some say Polymede is his mother). *See also* Clymene; Jason; Minyas.

Alcimenes (Greek)
He is the possible son of Jason the Argonaut and Medea, the sorceress. See Medea for the siblings of Alcimenes. *See also* Jason; Pheres (A).

Alcippe (A) (Greek)
Her parents are Ares, the god of war, and Agraulos. Her fraternal grandparents are the great god Zeus and the queen of heaven, Hera. *See also* Ares.

Alcippe (B) (Greek)
She is the possible mother of Oeneus by Ares. Some say Demonice is his mother.

Alcithoe (Greek) She is the daughter of Minyas (q.v.).

Alcis (Teutonic)
Sky gods; little known twin gods who may be connected with Castor and Pollux (Greek).

Alcmaon (Greek)
He is the son of Thestor and Megara. His siblings are the prophet Calchas, Leucippe and Theonoe. *See also* Calchas.

Alcmene (Greek) *see* Eurydice (C); Rhadamantus.

Alcyone (Greek)
She is one of six sisters and seven brothers who are the children of Aeolus and Enaret. *See also* Aeolus (A); Canace; Enaret.

Alcyoneus (Greek)
Alcyoneus, an evil giant, is the son of Gaea (the earth) born of the blood of the castrated Uranus. His brother, Porphyrion, was the leader of the giants. He and Alcyoneus were known as the strongest of the group. Alcyoneus lived in Pallene, a peninsula in the Aegean Sea. Using magic, he twice stole the sacred cattle belonging to Helius the sun god. Alcyoneus was invincible only if he stayed in his own area. During the battle of the giants and the gods on Mount Olympus, Heracles clubbed or shot him and then dragged him outside of his home territory and he died. In some renditions of this legend, Telamon accompanies Heracles on this adventure. Compare Alcyoneus to Antaeus. For the names of siblings see Giants. *See also* Aloeides; Gaea; Hippolytus (B); Lamia.

Aldoneus (Greek) *see* Hades.

Ale (Nigeria) *see* Ala (B).

Ale-im (Arabic; Hebrew) *see* Abram.

Alecto *Alektro, Allecto* (Greek)
Alecto is one of the Erinyes, the goddesses of retributive justice, and personifies of enduring hate. *See also* Erinyes.

Alegeus (Greek) *see* Andromeda.

Aleion (Phoenicia) Water Spirit. *See also* Aleyin.

Alektro (Greek) *see* Alecto.

Alemona (Roman)
The goddess Alemona is the "Guardian of the Fetus."

Aletes (Greek) *see* Aegisthus.

Aletheia (Greek) *see* Aeons; Nous.

Alexander (Greek) Another name for Paris (q.v.).

Alevin (Greek) *see* Adonis.

Alexandra (Greek) *see* Cassandra.

Aleyin *Aleion* (Phoenicia)
Also known as: *Aleyn Baal, Amurru, Ba'al of the Earth, Resheph* (Egypt). (Akkadia, Babylonia, Canaan, Phoenicia, Sumer, Ugarit)
Aleyin is the god of clouds, winds, rain, spring, and possibly air or winter. He is the son of Ba'al and the brother of the goddess Anat. Aleyin acted as the intermediary between his father and Mot during their ongoing battle of death and resurrection. Described as a rider of the clouds, he is usually accompanied by seven companions and eight wild bears. As Amurru he is the brother of Qadesh. He is probably the same as Aleyn Baal. *See also* Anat; Baal; Marduk; Mot; Qadesh; Resheph.

Aleyn (Mesopotamian) *see* Aleyn-Baal.

Aleyn-Baal *Aleyn* (Akkadian, Babylonian, Canaanite, Phoenician, Sumerian, Ugarit)
Also known as: *Baal, Baal Hammon* (Carthage), *Baalshamin, Ba'al-zebub* (Canaan, Phoenicia, Ugarit), *Bel* (Akkadian, Babylonian, Sumerian), *Hadad, Marduk, Melkart.*
"God of the Waters." Storm and Weather God. He has four hundred and fifty prophets and four hundred priestesses. He perishes at the coming of every summer. *See also* Aleyin; Ba'al-zebub; Baal; Hadad.

Alf (Teutonic) *see* Dwarfs.

Alf-heim (Teutonic) *see* Alfheim.

Alfadir (Teutonic) *see* Odin.

Alfadur (Teutonic) *see* Odin; Ragnarok.

Alfar (Norse; Teutonic)
There are two groups of Alfar, both dwarfs. One group, the artistic Liosalfar are light elves who live in Alfheim and are ruled by Freyr. The other group, known as evil elves, are the Dockalfar. They live in the underground in Svart-alfa-heim, and are ruled by Wayland the Smith. *See also* Alfheim; Alvis; Dwarfs; Elves; Freyr; Sindri; Svart-Alfa-Heim.

Alfheim *Alf-heim, Alvheim* (Norse; Teutonic)
Also known as: *Ljosalfaheim.*
Alfheim, located in Asgard between heaven and earth is the home of the Liosalfar, or light elves. It is also the abode of Freyr as king of the Alfar. Alfheim is near the sacred well of the Norns at the root of the sacred tree, Yggdrasil. The evil dwarfs live in Svart-alfa-heim. In later myths from England and France, the king of dwarfs was known as Oberon and he ruled along with his wife, Titania. *See also* Alfar; Andvari; Asgard; Svart-Alfa-Heim; Yggdrasil.

Alfhild (Scandinavia)
Alfhild is a young goddess who dressed as a male warrior to avoid marriage to King Alf. They engaged in battle and found that they were equals in strength. She then agreed to wed him.

Alfrigg (Norse; Teutonic)
He is one of four dwarfs who are gods of smiths. The others are Berling, Dvalin and Grerr. Freyja slept with all four in order to procure the "Necklace of the Brisings." *See also* Freyja, Loki.

Algue (Araucanian People, Chile) *see* Akanet.

Ali (A) (Teutonic) *see* Vali.

Ali (B)
Also known as: *Abu-Turab, Ali ibn, Haidar, Murtaza.* (Islamic, Shi'a sect)
The son of Abu Talib, Ali is the cousin of Mohammed, and the husband of Mohammed's daughter Fatimah. Their marriage ceremony was celebrated in heaven with the archangel Jibril acting as the bride's guardian. The couple became the parents of two sons, Hassan (also called Hasan and Al-Hasan) and Husayn (also spelled Hussein). Ali became the second Muslim. Mohammed's wife, Khadija, was the first Muslim. In the Shi'a tradition, Ali is known as the person who received the testament of Mohammed when the prophet knew that death was imminent. See Alah; Mohammed.

Alidat (Babylonyian, Canaanite, Semitic) *see* Ashtoreth.

Alignak (Eskimo)
Also known as: *Aningan, Anningan.*
He is the god of the moon, god of the falling snow, storms, eclipses, earthquakes and tides. He is also the protector of animals, the disinherited, and orphans. He can cure sterility in women. Alignak is a ward against the mighty anger of Sedna, goddess of the sea. *See also* Pinga; Sedna.

Aliki (Hawaii) *see* Kariki.

Alilah (Arabic)
Also known as: *Ala, Allah.*
Supreme deity. Ancient deity of the Northern Arabians. In some versions he is the mate of Allat. He is similar to El and Jehovah. Alilah later became Allah.

Alilat (Arabic, Babylonia).
Also known as: *Alilta, Halitta, Ilat.*
Alilat is a mother goddess, and an earth goddess. She is also thought to be a war goddess similar to Athena. The name Alilat is another name for the early Arabic mother goddess, Ilat. The Greek sage, Herodotus, claimed that Aphrodite was called Alilat. *See also* Al-Uza; Alilah (A); Aphrodite; Athena; Ilat.

Alilta (Arabic, Babylonia) *see* Allath.

Alinda (Aborigine People, Australia)
Also known as: *The Moon Man.*
A god of death. He and Dirima the parrot fish man killed each other and the spirit of Alinda transformed himself into the moon. He decreed that all living things must die, but he would die for only three days, then return to move across the sky. Each dead moon drops into the sea and becomes the empty shell of the nautilus. In a sense he also controls the tides. At high tide the water rushes to fill the moon, then drains back into the ocean until the moon is empty and the ocean is at low tide. *See also* Purukupali.

Alittu (Mesopotamia) *see* Ashtoreth.

Aliyan (Canaan)
Son of Baal. Husband of Anat. He was killed by Mot.

Alka (Lapp) *see* Akha.

Alkuntam (Bella Coola People, Canada)
Also known as: *Alkuntam, All-Father.*
Great sky-god. Alkuntam is the highest in the hierarchy of deities. With the assistance of Senx, (the sun), mortals were created. The mother of Alkuntam is a cannibal (mosquito) who inserts her long nose into the ears of men and sucks out their brains.

All-Father (Teutonic) *see* Yggdrasil.

All Swift (Teutonic) *see* Alsvid.

Allah (Mohammedanism, Islamic; South Arabia)
Also known as: *Ala, Alilah.*
Sole divinity. The name may derive from Ailiah, a god of Arabia's pre–Islamic, polytheistic tradition. Similar to El, Il, Ilah, Jehova. Certain descriptions of Allah seem to draw upon pre–Islamic tradition as well, especially the characteristics of certain moon deities such as Ilmugah, Kahil, Shaker, Wadd, and Warah. *See also* Aliliah; El.

Allat *Alat, Ilat*
Also known as: *Alah* (Babylonia), *Al-Lat, Allath, Allatu, Asa* (Syria), *Beltis-Allat, El-Lat, Ellat* (Sumer), *Hallat, Lat* (local name), *Sad* (masculine form); (Arabic, Assyria, Assyro-Babylonia, Chaldea, Sumer).
As Allat, the Nabataean mother goddess, she is called the Queen of Heaven; she is a fate deity, and a defender of cities. She is the morning and evening star. As the morning star, she is a goddess of war. As the evening star, she is the patron of love and prostitutes. Her attributes are a turreted crown and a cornucopia. In pre–Islamic Arabia, she was worshiped by the Arabic people in the form of a large stone. Under the stone, (housed in a wooden structure), precious stones were kept. She was the patron of travelers. Trees in the area were sacred to her (the Valley of Wajj). Allat is one of three desert goddess worshiped by the Arab people before Islam. She was later condemned by the *Koran.* The other two are Al-Uza and Menat. As a triad, they are known as Unsas. Some think that there is a connection between the Unsas and Arabic angels. She may be the same as the earlier Arabic goddess, Ilat (q.v.). She is comparable to the Semite sun goddess Samas. Compare Allat and Aphrodite (Greek), and Allat and Tyche (Greek). *See also* Al-Uza; Allah; Allatu; Astarte (Phoenician); Athena (Greek); Ereshkigal; Ishtar; Quadesh (Egypt); Unsas.

Allath (Arabic) *see* Allat.

Allatu
Also known as: *Beltis-Allat* (Chaldea), *Ereshkigal* (Mesopotamia).
Allatu with her mate the god of pestilence and fever, Nergal, rules the underworld, Arallu. Her messenger is Namtaru. Allatu, also the goddess of copulation, is depicted with the body of a woman, the head of a lioness, and the talons of a bird of prey. In each hand she holds a serpent. She is shown suckling two lions. Her name Ereshkigal was borrowed from the Sumerian people of Babylonia. She is thought to be the same as the Phoenician Astarte and the Babylonian Ishtar. She parallels the Greek Persephone. (The name and mythology of Allatu is sometimes attributed to Allat, and vice versa.) *See also* Allat; Anat; Arallu; Ereshkigal, Ilat; Ishtar; Kore; Namtaru; Nergal; Persephone; Tyche.

Allecto (Greek) *see* Erinyes.

Allfather (Teutonic) *see* Ginnunga-gap; Odin.

Alloprosallos (Greek) *see* Ares.

Almus (Greek) *see* Sisyphus.

Aloadae (Greek) *see* Aloeides.

Aloeidae (Greek) *see* Aloeides.

Aloeides *Aloadae, Aloeidae* (Greek)
The twin giants, Otus and Ephialtes are known as the Aloeides. They are the children of Iphimedeia and the sea god Poseidon or Aloeus. Some say that Canace was their mother. The noble-looking giants grew a fathom a year. At a very young age, they abducted Ares, the god of war, and imprisoned him in brass chains. They were devoted to one another. Their mischief and constant bragging pressed the nerves of Zeus. He decided to shut them up by hurling a thunderbolt at them but was dissuaded by Poseidon. They stayed on good behavior for a short time and then decided to abduct the warrior goddess Artemis. She appeared to them in the shape of a white doe. They chased her over land and sea and finally caught her in an open space. One brother was in front of her and the other at her back. Artemis darted around and when they threw their javelins, neither saw the other. They each died by the other's hand. In another tradition, the twins were nine years old when they fought the gods and were killed by Apollo and Artemis. Otus and Ephialtes were the first mortals to worship the Muses of Helicon. *See also* Alcyoneus; Aloeus; Antaeus; Ares; Canace; Giants; Iphimedeia (A); Muses.

Aloeus (Greek)
He is the son of Poseidon and Canace, or some say Uranus and Gaea (the earth). As the son of Poseidon and Canace, he is the brother of Epopeus, Hopleus, Nireus and Triopas. He married his brother's daughter, Iphimedeia, and became the father of Pancratis. With his second wife, Eeriboea, either he or Poseidon became the father of the Aloeides. *See also* Aloeides; Athamas; Canace; Cretheus; Epopeus; Giants; Iphimedeia (A); Poseidon.

Aloka *Aloke Nang-sal-ma* (Tibet) *see* Avalokitesvara.

Aloke (Tibet) *see* Aloka.

Alom (Maya)
Also known as: *Hunahpuguch.*
Creator. One of the regents who attempted to create men. The others were Tzakol, Bitol and Qaholom (also known as Cajolom). *See also* Hunahpu; Tzakol.

Aloros (Greek) *see* Alulim (Sumerian).

Alphaeus (Greek) *see* Alpheus.

Alphee (Greek) *see* Alpheus.

Alpheios (Greek) *see* Alpheus.

Alpheius (Greek) *see* Alpheus.

Alpheous (Greek) *see* Alpheus.

Alphesiboea (Greek) *see* Adonis.

Alpheus *Alphaeus, Alphee, Alpheios, Alpheous, Alpheius* (Greek)

A river god. Alpheus was one of the three thousand sons of Oceanus and Tethys and a brother of the three thousand Oceanids. He was said to be the father of Orsilochus. As the principal river of Elis, Alpheus saw the nymph Arethusa bathing in his water and changed into human form to pursue her. She fled from him and possibly with the assistance of the goddess of hunting, Artemis, she was transformed into a spring a great distance away from Alpheus. Undaunted, he became a river again and flowed along until he found her and was able to merge with her waters. In some legends, Heracles used the waters of Alpheius in his labors when he had to flush out the Augeian stables. To compare to other river gods, *see* Achelous, Acheron, Asopus, Cephissus, Cocytus, Inanchus, Rivers, Oceanus. *See also* Artemis; Heracles.

Alphito (Greek)

Barley or grain goddess. Ancient deity who could be the same as Dione. *See also* Aphrodite; Dione.

Alrinach (Eastern Europe)

This demon is associated with shipwrecks. It is shown in the form of an old woman.

Als (Armenia, Babylonia, Persia)

Aspects of known as: *Al* (singular), *Alu* (Babylonia).

Originally the Als were disease demons. In later times they became childbirth demons who abduct babies from the womb at seven months. They cause blindness to the unborn and miscarriages. Their homes are made in damp, dark corners of stables or houses. They are half-beast, half-human and can be male or female. Als have fingernails of brass, iron teeth, and snake-like hair. They carry iron scissors. Sometimes they are depicted with the tusks of a boar. The king of the Als is chained away in a deep, dark place where he wails continuously. To keep his cohorts away, the woman must surround herself with iron implements. The Babylonian Alu is said to crush men while they are sleeping. Similar to the Jewish Lilith, the Greek Lamia and the Armenian Thepla. *See also* Ahhazu; Aluqa; Jinn.

Alsvid *Alsvider, Alsvinn, Alswid* (Norse; Teutonic)

Also known as: *All Swift, Hrim-faxi* (possibly).

Alsvid, meaning "All Swift" and his companion, Aarvak, meaning "Early Waker," are the horses that pull the sun chariot of Sol along its course. *See also* Aarvak; Nat (B); Pegasus (Greek); Sol (B); Svalin.

Alsvider (Teutonic) *see* Alsvid.

Alsvinn (Teutonic) *see* Alsvid.

Alswid (Teutonic) *see* Alsvid.

Altan-Telgey (Mongolian) Earth Goddess.

Althaea (Greek) *see* Althea.

Althaemenes (Greek) *see* Acacallis; Pasiphae.

Althaia (Greek) *see* Althea.

Althea *Althaea, Althaia* (Greek)

Probably a mother or earth goddess. In legend Althea was the mother of Atabyrius (the pagan Hebrew deity who was represented as the golden calf). She is also known in Greek mythology as the daughter of Thestius and Eurythemis. Her siblings are Hypermnestra, Leda and Plexippus. She became the wife of her uncle Oeneus, and mother of Meleager by Oeneus or possibly Ares. Some say she is the mother of Deianeira (Deianira), Gorge and Toxeus by Dionysus. She may also be the mother of Tyedeus and may possibly have had a son by Poseidon. When her son Meleager was born the Fates predicted a hero's future for him but Atropos foresaw his death if a brand burning in the fire was not extinguished. Althea removed the brand and hid it. Meleager joined the Argonauts when he was so young that his father sent his cup-bearer, Meleager's uncle, Laocoon, along to care for him. He went on to marry Cleopatra and became the father of Polydora. When Artemis in anger sent the Calydonian Boar to ravage his father's lands, he led the hunt, killed the monster and was awarded the skin for a trophy. During the hunt he met and fell in love with the Arcadian huntress Atalanta and it is possible that he may have fathered Parthenopaeus. According to Homer, a fight developed between the Curetes, who felt they should have the boar skin, and the Calydonians. Meleager killed his mother's brothers and quit fighting when Althea became angry with him. Without his leadership, the Curetes attempted to scale the walls of Calydon. Cleopatra urged him to put aside his anger and act on behalf of the city, which he did and died during the ensuing battle. In another version, Meleager gave the prized boarskin to his love, Atalanta, rousing the ire of his uncles who tried to wrest it from her. Angered, Meleager killed them thus infuriating Althea, who remembered the prophecy of Atropos. She pulled out the brand, rekindled it and watched her son die an agonizing death. Remorseful, she then hung herself. Grief-stricken, Cleopatra also committed suicide. The remaining women in the house of Oeneus were turned into guinea fowl by the revengeful Artemis. Some say she is represented by a flower. *See* Calydonian Boar Hunt for details about her husband Oeneus. *See also* Ares; Artemis; Atropos; Fates.

Altjira (Arunta People, Australia)

The All-Father or Sky Dweller, is indifferent to mortals. His voice is like thunder and he has the feet of an emu.

Alu (Babylonian, Sumerian)

Alu is a wicked devil who covers a man like a garment and smothers him. Alu is also one of twelve devils mentioned along with Lilith. The Alu are in the same category as the Als (q.v.). *See also* Ahhazu; Aluqa; Lilith; Utukku.

Alukah (Canaanite) *see* Ereshkigal.

Alulei (Marshall Islands, Micronesia)

Also known as: *Aluluei.*

God of Navigators. He is the son of Palulop. His two brothers are Big Rong and Little Rong. His children are Longorik and Longolap. Alulei has two faces, one looking forward and one looking back. Rata (Polynesia) is similar to Alulei. He is associated with the carpenter god, Solang. *See also* Palulop.

Alulim (Sumerian)

Also known as: *Aloros* (Greek).

First man. He descended from the celestial realm and became one of the antediluvian kings. He ruled earth before the flood for either 28,000 or 67,000 years depending on the myth. He corresponds to Adam (Hebrew).

Aluluei (Micronesia) *see* Alulei.

Aluqa (Arabic)
A seductive female demon who is known to suck her victim's blood after intercourse. Exhausted, he commits suicide. *See also* Als.

Al'uzzah (Arabic) *see* Al-Uza.

Alvheim (Teutonic) *see* Alfheim.

Alvis *Alviss* (Teutonic)
Also known as: *All Knowing Wise Dwarf.*
He is a dwarf who was turned into a stone by Odin or Thor because he had the temerity to woo Thor's daughter, Thrud. Alvis lives in the underground caves. He promised that he could marry Thor's daughter. When he went to get his bride he was detained by Thor who asked him questions until daybreak. He was forced to leave alone. *See also* Alfar; Thor; Thrud.

Alxion (Greek) *see* Oenamaus.

Am (Egypt) *see* Amen (B).

Am-Beseku (Egypt) *see* Assessors.

Am-Kehuu (Egypt) *see* Tcheser-tep-f; Unas.

Am-Khaibetu (Egypt) *see* Assessors.

Am-Mit *Am-mut* (Egypt) *see* Amit.
Door guard in the Fourth Hour of Tuat. The goddess Ammit consumes souls with fire from her mouth. *See also* Sekhemus.

Am-Senf (Egypt) *see* Assessors.

Am-Sit (Egypt) *see* Amset.

Am-Ta (Egypt) A name for Sekhem.

Ama (A) (Sumerian)
Also known as: *Mama, Mami.*
Mother goddess. Probably derived from Ana. Similar to Ariadne, Arianrhod, Athena, Marian, and Marianna.

Ama (B) (Teutonic) *see* Amma (B); Eire.

Ama (C) (Japan) *see* Ama NoUzume; Ama-tsu-Kami; Kami.

Ama (D) (India) *see* Parvati.

Ama-Amta (Egypt) A name for Sekhem.

Ama-No-Hashadate (Japan) *see* Izanami; Kami.

Ama No Hashidate (Japan) *see* Kami.

Ama-No-Hohi (Japan) *see* Ame no-Oshido-Mimi.

Ama-No-Kagaseo (Japan) *see* Amatsu-mikaboshi.

Ama-no-minaka-nushi *Ama-no-minakanushi-no-Kami, Ame-no-minaka-nushi,* (Shinto; Japan)
Also known as: *Kuni-toko-tachi no mikoto* (Eternal Land Ruler).
Supreme deity. Ama-no-minaka-nushi (Heavenly Central Lord) is the head of the triad known as the three creator Kami who sprang from chaos (darkness). The secondary deities are Taka-mimusubi (High Producing), and Kamu-mimusubi, (Divine or Mysterious Producing). These deities are also called Kuni no sa-tsuchi no Mikoto (Land of Right Soil of Augustness) and Toyo-kumu-no Mikoto (Rich Form Plain of Augustness). It is thought that Taka-mimusubi represents Kami-rogi (the Divine-Male) and Kamu-mimusbi represents Kami-romi (the Divine-Female). In some traditions, Ama-no-minaka-nushi and Taka-mimusubi are one and the same. The next deities were Uhiji-ni no Mikoto (Mud Earth) and Suhiji-ni no Mikoto also called Suhiji-ne no Mikoto (Sand Earth). They were followed by Oho-to nochi no Mikoto (Great After Door) and Oho-to mahe no Mikoto (Great Before Door). The next deities were Omo-taru no Mikoto (Face Pleasing) and Kashiko-ne no Mikoto (Awful) also called Aya-Kashiko-ne no Mikoto, Imi kashiki no Mikoto, or Awo-kashiki-ne no mikoto, or Aya-kashiki no Mikoto. The next deities were Izanagi (Male-who-Invites), and Izanami (Female-who-Invites). In other traditions, Taka-mimusubi and Kamu-mimusubi appeared after Izanagi and Izanami and Taka-mimusubi was their child. These deities are known as celestial deities, Ama-tsu-Kami *(Gods of* Heaven). The mission of Izanagi and Izanami was to unite and give birth to earthly manifestations, known as Kuni-tsu-Kami. The first created was the Japanese archipelago, followed by Kami; nature, food and fire. Kami is all things that were produced; Kami is the forces of nature. Izanagi and Izanami brought into being the divine rulers of the world. Known as their children, they were Ama-terasu Ohmi-Kami, also known as Amaterasu (Heaven-Illumining Goddess), Tsukiyomi-no-mikato (Moon-Ruler) and Takehaya Susanowo (Valiant-Swift-Impetuous-Hero). The *Kojiki* ("Records of Ancient Matters"), is the oldest chronicle in Japan. It was written in C.E. 712 by Futo no Yasumuro, the court noble. The *Kojiki* records the earliest doctrines of Shinto mythology concentrating primarily on the age of the gods. In C.E. 720 the *Nihongi* ("Chronicles of Japan") further recorded the myths of the land and included the reigns of the emperors. Mythology and history entwined called the mythical Jimmu Tenno (Sun of Heaven) a great-grandson of the sun goddess Amaterasu. He was also credited with being the founder of the empire. All following emperors dated from him and were called divine. In 1946 the emperor Hirohito renounced his divinity. The deities created after the triad emerged from chaos up to and including Izanagi and Izanami are known as the Seven Generation Deities. *See also* Amaterasu; Amatsu-Mikaboshi, Hiruko; Izanagi and Izanami, Jimmu Tenno; Kami; Kamu-Mimusubi; Susanowo; Takama-no-hara; Three Goddesses of Munakata; Tsuki-Yomi.

Ama-no-Minakanushi-no-Kami (Japan) *see* Ama-no-minaka-nushi.

Ama-no-oshiho-Mimi (Japan) *see* Ame-no-Oshido-Mimi.

Ama-no-Saug-Me (Japan) *see* Ame no-Oshido-Mimi.

Ama-no-Uki-Hashi (Japan) *see* Izanami.

Ama No Uzume (Japan) *see* Ame-no-uzume.

Ama-no-Uzume *Ame-no-Uzume-no-Mikoto* (Heavenly Alarming Female), (Shinto; Japan)

Also known as: *Ama, Otafuku, Udzume, Uzume.*

Fertility goddess. Shaman. When the sun goddess Amaterasu descended into the cave named Ame-no-Iwato (Rock Cave of Heaven), she left the universe in darkness. The eight hundred myriad of deities convened to create a plan which would entice her back into the world. The plan included a boisterous dance by the goddess Ama-no-Uzume to be performed at the mouth of the cave. Caught up in the passion of her dance, Ama-no-Uzume stamped loudly on the ground, lowered her skirt and exposed her breasts. Uproarious laughter from the audience of deities piqued Amaterasu's curiosity. She could not understand the frivolity on the outside when she was secreted in the depths of the cave. They had after all, been saddened by her absence and the resulting darkness, and until now, had been wooing her in attempts to persuade her to leave the cave. She glanced out to investigate, caught sight of herself in a mirror and attracted by her beautiful image stepped out of the cave, bringing light back into the world. This dance became known as the karuga, a pantomimic dance performed at Shinto festivals. The Sarume, an ancient family ruled by female Kimi (a hereditary title), are said to have descended from Ama-no-Uzume. The members of the family performed in ritual dances at court. Later, as recorded in the "Kojiki," Ama-no-Uzume was requested by Amaterasu to accompany her grandson Ninigi to earth. Her function was to deal with possible enemies. On earth she encountered the hostile giant Saruta-biko and was able to woo and enchant him with her beauty and gestures. In the translation of the *Nihongi* by Aston, Ama-no-Uzume bares herself before Saruta-biko whom some say she married. The karuga represents the planting of the seed and awaiting the return of the summer sun to nourish its growth. The mirror known as Kagami and also Yata-Kayami was created by the goddess Ishikoridome-no-Mikoto. *See also* Amaterasu; Kami; Ninigi.

Ama-terasu-o-Kami (Japan) *see* Amaterasu.

Ama-terasu-o-mi-Kami-me no Mikoto (Japan) *see* Amaterasu.

Ama-terasu Ohmi-Kami (Japan) *see* Ama-no-minaka-nushi; Amaterasu.

Ama-terasu-Oho-hiru-me no Mikoto (Japan) *see* Amaterasu.

Ama-tsu-Kami (Japan)

Also known as: *Kami, Kuni-tsu-Kami.*

Celestial deities. The Ama-tsu-Kami are the celestial deities who reside in Takama-no-hara (abode of the gods). Their earthly counterparts are known as Kuni-tsu-Kami. For the Shinto creation myth, *see* Ama-no-minaka-nushi. *See also* Ama-no-minka-nushi; Kami; Takama-no-hara.

Ama-tsu-mika-hoshi (Japan) *see* Okuni-Nushino-Mikoto.

Ama-Tu-piko-nasgisa-take-u-Gaya-puki-apezu-no-mikoto (Japan) *see* Jimmu Tenno; Toyo-Tama-Bime.

Ama-Tu-Pikone-no-mikoto (Japan) *see* Amaterasu.

Ama-waka-hiko (Japan) *see* Ame-no-Oshido-Mimi.

Amaethon *Amathaon* (British, Celtic, Welsh)

God of Agriculture. He is the son of Don and Beli. His siblings are Govannon, Llud and possibly Gwydion. He is credited with bringing domestic animals to earth from the "land of the gods." *See also* Amathaon; Llud.

Amagandar (Tungus People, Africa)

Also known as: *Orokannar.*

Family of protective female spirits of happiness.

Amahraspands (Persian) *see* Amesha Spentas.

Amairgin (Celtic) *see* Amergin.

Amaite-Rangi (Mangaia Island, Polynesia)

A male sky demon. *See also* Ngaru.

Amalivaca (Orinoco River People, South America)

He is the culture hero who taught the people the arts of life and agriculture.

Amalthaea (Greek) *see* Amaltheia.

Amalthea (Greek) *see* Amaltheia.

Amaltheia (A) *Amalthaea, Amalthea* (Greek)

Also known as: *Sibyl* (Roman).

A goat. Raised by Pan, Amaltheia is the goat who suckled the infant Zeus in a cave at Lyktos on the island of Crete. One of her horns flowed with ambrosia (a cornucopia) and her other horn flowed with nectar. After her death Zeus kept the horn filled with golden fruit from the Garden of Hesperides to honor Amaltheia. It became known as the "Horn of Plenty." He used her hide to cover his shield and it became known as the Aegis. It is said that in later times he hung the goat and horn in the sky and it is now known as the constellation of Capricorn. Legend associates Amalthea with Adrastia and Ida as a moon-triad. For goat-related legends, *see* Aegipan, Aegis, Aegisthus. *See also* Achelous; Adrastia; Aegis; Amaltheia (B); Cornucopia; Ida; Pan; Zeus.

Amaltheia (B) (Greek)

She is the daughter of the king of Crete, Melissus, and sister of Melissa. This Amaltheia may have fed Zeus the milk from the goat Amaltheia. *See also* Amaltheia (A).

Amaltheia (C) (Roman)

She is referred to as the Cumaean Sibyl, the prophetess of the Sibylline oracles of Rome. She owned and possibly wrote the nine books of oracular advice. Three of the nine books remained in the Temple of Jupiter until it was destroyed by fire in 83 B.C.E.

Amaltheia (D) (Roman)

She is also known as Deiphobe, Demo, Demophile or Herophile. *See also* Sibyl.

Amam (Egypt) *see* Amit.

Amam-Mitu (Egypt)

One of the seven goddess who minister to Osiris in the Second Hour of the Night. *See also* Shesat Maket Neb-S; Tuat.

    Cysts: *Light Green and Blue Chi* 154
    Infection and Inflammation: Light Green Chi 154
    Fever 154
    Insomnia: Green and Blue 155
    Tinnitus 155
    Blood Clotting: Blue Chi - Fresh Burns: Green and Blue Chi 155
    Old Minor Burns: Green and Red Chi 155
    Old Severe Burns: Green and Red Chi 156
    Old Wounds: Green and Red Chi 156
    Some Specific Points and Ailments: 156
    Solar Plexus: Blue Chi 157
    Skin Infection: Blue Chi 157
    Eyes: Green Chi 158
    Ears: Violet Chi 158
  Summary of Individual Healing Session 159

Chapter VII
Different Hand Techniques

  Forget about your Palms 165
    Don’t Focus your Mind on the Sick Part 165
    Cosmic Healing is Teaching 165
  Chi Kung Diagnosis: Hand Scanning 166
    General Variations in the Energy Field 166
    Hand Scanning the Internal Organs 167

Chapter VIII
Cosmic Chi Kung Palm and Finger Training

  Why We Practice the Cosmic Chi Kung 169
    Opening Heaven and Earth Force in the Palms - Heaven and Earth Spirals 170
    Cell Breathing 171
    Mind, Eyes, Heart and Intention (YI) 172
    Connecting the Bridge 173
    Cosmic Chi Kung Preparation 174
    Cosmic Chi Kung Preparation Standing 175
    Opening to Heaven, Earth and Nature 176
    Outline of Practice 176
  Part I - Opening to Heaven, Earth and Cosmic Chi 177
    Opening Movements 177
    Core Movements of Part I 182
    Closing Movements 183
  Part II - Opening the Bridge and Regulator Channels 189
    Theory 189

Amam-ta (Egypt) *see* Aai.

Amamet (Egypt) *see* Amit.

Amamet the Devourer (Egypt) *see* Amit.

Aman (A) (Egypt) *see* Amen (B).

Aman (B) (Japan) *see* Shichi Fukujin.

Amanki

Also known as: *Enki* (Babylonian).

A water god, Amanki is an aspect of the Sumerian god Enki (q.v.).

Amano-Iwato (Japan) *see* Amaterasu.

Amanoro (Armenian) Spring goddess.

Amaravati *Devapura* (City of Gods) (Hindu; India)

Amaravati is the capital city in the celestial kingdom of Swarga. Located on the eastern spur of Meru Mountain, it is said to have a thousand gates and contains fruits of all seasons, jewels and other objects of pleasure. Temperatures do not exist, nor does depression or sadness. The lovely Apsarases add to the beauty of the city. This land of bliss is Indra's heaven; it is the land of fallen warrior heroes or those who perform penance and sacrifice. The name means "Full of Ambrosia." Compare to Valhalla (Teutonic). *See also* Ambrosia; Apsarases; Swarga; Visvakarma.

Amardad (Persia) *see* Ameretat; Haurvatat.

Amarud (Babylonian) *see* Marduk.

Amarudu (Babylonian) *see* Marduk.

Amaruduk (Babylonian) *see* Marduk; Nimrod.

Amashilamma (Sumerian) Cow Goddess.

Amaterasu (Buddhist, Shinto; Japan) *Ama-terasu-o-mi-Kami, Ama-terasu-o-mi-Kami* (the Heaven-great-shining-Kami), *Amaterasu Ohmi-Kami, Ama-terasu-Oho-hiru-me No Mikoto, Amaterasu-Oho-hiru-me, Amaterasu-Oho-mi-Kami, Amaterasu-omi-gami, Shimmei.*

Also known as: *Oho-hiru-me No Muchi* (Great Noon Female of Possessor or Great Mistress of the Day), *Ten-sho-dai-jin, Tenshodaijin, Tenshoko-daijin, Tenshokodaijin.*

Amaterasu is a sun goddess, the founder of sericulture, the guardian of agriculture, the deity of peace and order and the ancestor of the ruling family. She is the daughter of Izanagi and Izanami. She rules the realm of light on ama (heaven) and earth and the Plain to Heaven. She is the sister of the storm god Susanowo (also known as Takehaya Susanowo, Valiant-Swift-Impetuous-Hero) and the moon ruler and ruler of the night, Tsuki-Yomi. Her younger sister, Wakahiru-Me (Wakahirume), is possibly a solar deity. She is the weaver who assisted Amaterasu in weaving garments for the gods in the Plain of Heaven. (*See* Amatsu-Mikaboshi.) In some traditions, she has an older brother, Hiruko. When Amaterasu was a young goddess, her father, Izanagi, gave her a necklace of jewels named Mi-kura-tana-no-Kami, which was an emblem of fertility. She offered her son Ama-No-Oshido-Mimi the opportunity to rule the earth. When he saw the confusion on the planet, he refused to leave the celestial realm. She is the mother of the goddesses Takiri-bime-no-mikoto, Ikiti-simapime-no-mikoto also named Sa-yori-bime-no-mikoto, and Takitu-pime-no-mikoto. Her other sons are Masa-katu-a-katu-kati-paya-pi-Ame-no-oso-po-Mimi-no-mikoto, Ame-no-po-pi-no-mikoto, Ama-Tu-Pikone-no-mikoto, Iku-Tu-Pikone-nomikoto and Kumano-kusubi-no-mikoto. She also has a favored grandson, Ninigi, who was destined to become the ruler of Izuwo province. After her brother, Susanowo, committed atrocities against her, Amaterasu withdrew into a cave and took the light of the world with her. During this period, many evil demons conducted underhanded activities without observation. A multitude of deities approached the cave named Ame-no-Iwato (Sky-Rock-Cave) to show their support and to persuade the goddess to bring her light back to the heavens and earth. Finally they resorted to a plan suggested by the god Hoard Thoughts. A mirror named Kagami (also called Yata-Kayami) and a necklace were hung in a tree. The goddess Ame-no-uzume-no-mikoto, also known as Ama-no-Uzume (Heavenly Alarming Female) performed a frenzied dance called the Kagura. She became boisterous and stripped off her clothing, causing glee in the audience. The gods howled with laughter. Curious, the sun goddess peeked out to investigate the commotion. She was told that they had found a more beautiful woman to take her position. She caught sight of the reflection of a beautiful woman in the mirror and cautiously moved closer to examine it. Several deities apprehended the goddess. Tajikaroo (Prince Mighty Power) placed a barrier made of straw rope named Shiri-kume-na-nawa (Don't Retreat-Rope) across the entrance to the cave. The light of the world returned and overcame darkness. Other deities involved in convincing her to shine were Ame-no-tajikara-wo and Tuto-Tamu. Dignified, honest, meek in temper, Amaterasu was a brilliant and wise ruler. Besides protecting rice fields, she invented and constructed irrigation canals, organized religious rites, and wove clothing for the gods. In some traditions of her following, she is associated with the god Taka-mi-musubi, (High Producing). He accompanies her as her hidden or higher entity. She also has a female companion, a food goddess, Toyo-uke-no-Kami (Abundance-Bounty Goddess) also known as Toyo-uke-hime (Plentiful-Food-August). Though shrines have been dedicated to her, little is known about her and her origin is disputed. The monk Gyogi (670–749) initiated an offshoot of Shinto, known as Ryobu-Shinto and proclaimed that Amaterasu and Buddha were the same. The name Ten-sho-dai-jin is a current name used for Amaterasu. Amaterasu is depicted as a beautiful woman. The cock is her sacred bird as it greets the morning sun. As well as a sun symbol, the cock is the emblem of vigilance and activity. In early times, a sacred crow named Yata-Garasu, who had several feet, was her messenger. (*See* Jimmu Tenno for crow symbolism.) She owned three divine rice fields, the Easy-Rice-Field-of-Heaven, the Level-Rice-Field-of-Heaven, and the Village-Join-Rice-Field-of-Heaven. She also developed the art of raising silkworms. The sacred mirror is the symbol of purity. The necklace is a symbol of fertility and spiritual power. One of the rites of worship of the sun goddess is the dance known as the Kagura. It is one of the oldest of the Japanese dances and was later the basis for the No dramas. During an eclipse, another ceremony of the sun goddess is performed. Participants gather and clash metal objects together to signify the occasion when Amaterasu peeked out of the cave to discover why it was so noisy. A great shrine was dedicted to this goddess in the province of Ise. The founder of sericulture, Amaterasu put silkworms in her mouth and reeled silk from them. The goddess Ukemochi had at this time already produced the silkworm from her eyebrows. The act of weaving symbolizes creation and life which represents accumulation, multiplication, and growth. Straw rope is tied around trees at Shinto shrines. At Amaterasu's principal shrine in Ise, the rope stretches across a ravine through which the sun is seen at dawn. For the Shinto creation myth, *see* Ama-no-minaka-nushi. For details of her birth, *see* Izanagi and Izanami. For details of her brother's outrageous behavior toward her, *see* Susanowo. *See also* Ninigi (her grandson), Hikohohodemi (her great-grandson), Hosuseri (her great-grandson), Jimmu-Tenno (her great-great grandson). She is sometimes identified as an aspect of Amita (Amida). She is sometimes identified with Dainachi Nyorai (an aspect of Buddha). Compare Amaterasu's necklace (Mi-kura-tana-no-Kami) to the Teutonic goddess Freyja's necklace (Brisinga-men) and the Greek Amazon goddess Hippolyte's girdle. For details of the sacred treasures of Shintoism, see Susanowo. Compare to Kami-mimusubi, who collected the seeds for food produced by Ogetsu-hime-no-Kami. For the origins of Amaterasu's food supply, *see* Ukemochi. *See also* Ama-no-Uzume; Ame-no-Oshido-Mimi; Haya-ji; Ishikoridome-no-Mikoto; Kusanagi; Ninigi; Okuni-Nushino-Mikoto; Sengen, Take-mi-kazuchi; Three Goddesses of Munakata; Toyo-Tama-Bime.

Amaterasu-Oho-hiru-me (Japan) *see* Amaterasu.

Amaterasu-Oho-mi-kami (Japan) *see* Amaterasu.

Amaterasu-omi-gami (Japan) *see* Amaterasu or Ama-Terasu-Oho-Hiru-Me No Mikoto.

Amaterasu Takehaya Susanowo (Japan) *see* Ama-no-minaka-nushi.

Amathaon *Amatheon* (Celtic)

The son of Anu, he is a wizard who taught his art to his brother Gwydion. When Amathaon stole a dog and a roebuck from Arawn, a fight broke out between Arawn and Gwydion which became known as "The Battle of the Trees." *See also* Anu (A); Arawn; Gwydion.

Amathaounta *Amathaunta* (Egypt, Sumer)

Also known as: *Ashima.*

She is a goddess of the sea.

Amathaunta (Egypt) *see* Amathaounta.

Amatheon (Celtic) *see* Amathaon.

Amatsu-Mikaboshi (Early Shinto; Japan)

Also known as: *Ama-no-kagaseo* (The Brilliant Male).

God of Evil. God of Stars.

Amatsu-Mikaboshi (The August Star of Heaven) in early times was later identified with the Pole Star, Myo-ken, and later assimilated with Ama-no-Minaka-nushi (The Heavenly Central Lord), the head of the triad who sprang from Chaos. The *Nigongi* speaks of Amatsu-Mikaboshi. *See also* Ama-no-Minaka-nushi.

Amatsu-Otome (Japan)

Japanese angels. They are all young, virgin females. Carvings of Buddhist angels from the Asuka period (C.E. 552 to C.E. 645) hang from a canopy in the Kondo (Golden Hall) at Horyu-ji, in Nara, Japan. *See also* Apsarases (India).

Amatupiko-Pikonagisa (Japan) *see* Toyo-Tama-Bime.

Amayicoyondi (Pericu People, North American) Sky Mother.

Amazons (Greek, Scythian)

Also known as: *Aior-pata, Kakasians, Sauromatai.*

Hunters and warrior women. The Scythians thought of them as Airo-pata or "man-slayers," while the Greeks said the name meant "without breast." It was their custom to integrate with males from neighboring tribes from time to time. If the children born of these unions were male, they were sent back to their fathers, mutilated, or used as slaves. Female children had a breast removed so they could handle their weapons more effectively. In early times, Io in her cow shape encountered the female warriors. Later, Heracles, in an attempt to secure the girdle of Hippolyte was involved in a battle with them. During the latter part of the Trojan War, they joined Priam, the last king of Troy, in fierce battle against their hated enemies, the Greeks. Their queen, Penthesileia (some say Thalestris), was killed by Achilles. The Amazon female warriors of South America were similar to their valiant sisters. The Amazons worshiped the moon. They are associated with Artemis (q.v.). *See also* Antiope (A); Hippolyte.

Amba (A) (India) "Mother."

An epithet for Uma-Parvati. *See also* Parvati.

Amba (B) (India) A Krittika sister. *See also* Rishi.

Ambalika (India) *see* Pandavas; Vyasa.

Ambi (India) *see* Ambika.

Ambika *Ambi, Amvika Devi.*

(Hindu, Vedic; India) Ambika, "the Mother" is the moon goddess aspect of the great goddess Devi. She is the spouse and perhaps the sister of Rudra. *See also* Devi; Parvati; Purusha; Rudra; Sati (A); Vyasa.

Ambrosia (Greek)

Also known as: *Amrita* (Sanskrit).

Nectar of the gods. Ambrosia is the honey-flavored food of the gods. When served with nectar it preserved their immortality and gave them eternal youth. It was also the ointment used for anointing sacred stones. Ambrosia is similar to the Indian Amrita and Soma. *See also* Amaravati; Amrita; Chandra; Haoma; Soma.

Amburaja (India) *see* Varuna.

Amchimalghen (Araucanian People, South America)

Every person has an invisible, beneficent nymph known as Amchimalghen in attendance.

Ame-no-hohi (Japan) *see* Ama-no-oshido-mimi; Amaterasu.

Ame-no-ina-fune (Japan) *see* Izanami.

Ame-no-iwato (Japan) *see* Amaterasu.

Ame-no-minaka-nushi (Japan) *see* Ama-no-minaka-nushi.

Ame-no-murokumo-no-tsurugi (Japan) *see* Kusanagi.

Ame-no-Oshido-Mimi *Ama-no-oshiho-mimi* (Shinto; Japan)
Also known as: *His Augustness Truly Conqueror, I Conquer Conquering, Swift Heavenly Great Ears.*

Celestial deity. Son of the sun goddess, Amaterasu. Ame-no-Oshido-Mimi was instructed by his mother, the sun goddess Amaterasu to descend to earth as the sovereign to calm the warlike mortals. Before departing, he stopped on the Floating Bridge of Heaven, observed the tumult below and told his mother that he could not fulfill her request. The eight hundred deities held a conference and appointed the God-Who-Hoards-Thoughts to determine a plan. They decided that Ame-no-Hohi would descend to earth and organize worldly affairs in Izumo. They waited three years for a report from the god. Nothing. They sent his son and never heard from him again. Earthly attractions may have seduced them. The divine group reconvened and delegated the courageous warrior, Ame-no-Wakahiko (Ama-Waka-Hiko), equipped him with a sacred bow and arrows, and sent him on the mission. When he arrived to take up his duties, he fell in love with Shita-teru-Hime, the daughter of Okuni-nushino-mikoto, and neglected to contact the deities in the celestial realm. Eight years later, the gods sent a pheasant named Nakime (also known as Nanaki or Na-naki-me) to investigate. She perched on a branch outside Ame-no-Wakahiko's home. The women of the household saw her and became alarmed fearing that it was an evil omen. Ame-no-Wakahiko took charge and shot the bird with one of his divine arrows. Some say he followed the advice of his servant, Ama-no-sagu-me. The arrow punctured the pheasant and landed at the feet of Amaterasu in the heavens. She recognized the sacred arrow, hurled it back to earth and it pierced Ame-no-Wakhiko in the heart. He died. The tears of his grief-stricken widow were so penetrating that the gods heard them, took pity and sent her parents from the celestial realm to attend the funeral. The divine delegation sent two more deities to earth. They informed Okuni-nushi-mikoto that Amaterasu was taking control of the land. A skirmish developed but the sun goddess prevailed and sent her grandson Ninigi to bring order to the land. In other renditions of this legend, the arrow fell at the feet of Amaterasu's adjunct Taki-mi-Mushubi, who hurled it back to earth and killed Ame-no-Wakahiko. The pheasant and the cock have similar symbolic definitions. For a variation of the myth of Ame-no-Wakhiko, see Haya-ji. *See also* Amaterasu; Ninigi; Okuni-nushino-mikoto.

Ame-no-puya-kinu-no-kami (Japan) *see* Kushi-nada-hime.

Ame-no-tajikara-no (Japan) *see* Amaterasu.

Ame-no-tajikara-wo (Japan) *see* Amaterasu.

Ame-no-uki-hashi (Japan) *see* Izanami.

Ame-no-uzume-no-mikoto (Japan) *see* Ama-no-Uzume.

Ame-no-wakahiko (Japan) *see* Ame-no-wo-ha-bari; Haya-ji; Okuni-Nushino-Mikoto.

Ame-no-wo-ha-bari (Shinto; Japan)
Also known as: *Itsu-no-wo-ha-bari.*

Sacred object. Ame-no-wo-ha-bari (Heavenly-Point-Blade-Extended) is the sword Izanagi used to remove head of his son, the fire god, (Fire-Burning-Swift Male Spirit) whose birth caused the death of his mother Izanami. From his blood sixteen deities were born. The fire god meeting with the cold metal blade could indicate the severing of earth from heaven. When the sword is associated with fire it often symbolizes purification. After slaying his son, Izanagi went to the sea to purify himself. Compare to the sacred sword, Kusanagi. *See also* Izanagi and Izanami.

Amehetp (Egypt) *see* Amenhotep I.

Amen (A) (British)
The magic cauldron which belonged to Keridwen (q.v.).

Amen (B) *Aman, Ammon, Amon, Amum, Atum* (Egypt; possibly Nubian and Syrian)
Also known as: *Am, Amen-ra, Amen-ur, Amon-ra* ("King of Gods"), *Amun-re, Hammon, Jupiter-Ammon, Niu.*

"The Hidden One." Patron deity of the city of Thebes. Son of Thoth and Maat. A primeval deity, Amen was originally a god of the dead. His association with death may indicate that he was an agricultural god. His name signifies "the hidden one," the soul (ba) of all things. His influence waxed and waned throughout many dynasties. He is known as a supreme creative god, a god of war, and the force behind the wind. His name appeared as early as the fifth dynasty and he is said to have introduced civilization to Egypt. Prior to being elevated to a supreme god (Amen-Ra) around the Twelfth Dynasty, he was a local god, probably of Apt (a section of Thebes) where he was said to have ousted the war god Mont (Month). During the eighteenth dynasty he was the Supreme God of Egypt and the Great God of Thebes. Amen and his consort Ament (also called Amenet), are described in the Pyramid Texts as members of the Ogdoad, a company of eight gods who were worshipped as mothers and fathers of the world. He is shown with the potter's wheel forming the egg said to create mortals. During the New Kingdom, he was the husband of the mother goddess Mut and one of the Triad of Thebes with Mut and his son, the moon, Khensu. In other forms he was the god Par (lord of the phallus), or Ahat (a form of the goddess Meh-urt, or Net). As a creator god he was worshipped chiefly as a goose (symbol of sexual power). The ram with curved horns (his fertility aspect) is generally regarded as his sacred animal. Amen (as Amun) is depicted as Amun-Min and has as an aspect the snake Kematef ("He Who Has Completed His Time"). When he is with Ament, she is uraeus-headed (serpent-headed) and he is shown with a frog's head; and if he is shown with the uraeus, she appears with the head of a cat. As Amen-Ra he is shown as a bearded, blue man, with a tail (lion or bull), wearing a double plumed headdress, either red and green, or red and blue. He wears a tight skirt, a large neck-piece and numerous bracelets. He holds an ankh in his right hand and a scepter in his left hand. He is also depicted with a hawk's head and as Amen-Ra-Temu he has the head of a hawk. In some cases he is shown as having the head of a crocodile or with the head of a man and the body of a beetle with the wings of a hawk, the legs of a man and the claws of a lion. He is also shown with the head of a goose or a ram. As Amen he has been depicted as a black lingam (stylized phallus) in the Ammonium of the Libyan desert. In Greece he was identified with Zeus, in Rome with Jupiter; thus the name, Jupiter Ammon. Under this name he was worshipped at Siwa. Amen is also identified with Amsu and Khnemu, and the Greek Harsaphes (q.v.). *See also* Ahat; Akeneh; Akhet-Nen-Tha; Amen-Ra; Ament; Amentet; Amsu; Amunet; Aten (for period when worship of Amen was forbidden); Hehui; Heru-Khu; Horus; Khensu; Kheperi; Maat; Min; Mont; Mut; Nau and Nen; Nu; Ogdoad; Par; Ra; Sekhemus; Temu; Thoth.

Amen-ha (Egypt) *see* Aai.

Amen-khat (Egypt) *see* Aai.

Amen-khum (Egypt) *see* Khnum.

Amen-Ra (Egypt)

The priest of Amen created the deity Amen-Ra in an attempt to establish a connection between Amen and the cult of the sun god, Ra. *See also* Amen (B); Ament; Amun; Maat; Min; Nekhbet.

Amen-Ra-Temu (Egypt) *see* Amen (B).

Amen-Ur (Egypt) *see* Amen (B).

Amenaber (Armenian) *see* Aramazd.

Amenet (Egypt) *see* Ament.

Amenhetep (Egypt)

Also known as: *Son-of-hapu.*

God of healing. Amenhetep, an architect as a human, was one of the few humans deified after death. He was close to Amenhetep III of the Eighteenth Dynasty. As a god, he had a small following. *See also* Imohotep; Pedesi; Pehor.

Amenhotep, Son of Hapu (Egypt)

Also known as: *Amenophis* (Greek).

Sage. Master builder. Amenhotep, (1379–1417 B.C.) was renowned as a sage and an architect and his reputation continued to grow throughout the centuries. He was a devoted follower of Thoth and was said to have written books of magic. Many myths were built around this creative man who was the master builder for Amenhotep III. Although statues were erected in his honor, and a temple was dedicated to him along with Hathor and Imhotep, he never became a bona-fide deity. Amenhotep, son of Hapu is usually depicted as a scribe, in a crouching position, with a roll of papyrus on his knees. *See also* Imhotep.

Amenhotep I *Amehetp* (Egypt)

Also known as: *Amenophis I* (Greek).

Deified Pharaoh. God of protection. Am-henth-f (1557–1530 B.C.), worshipped west of Thebes with his mother, Ahmes-Nefertari. He became a god of protection by saving the life of a worker, who had been bitten by a snake. He is one of the gods mentioned in the Pyramid Texts. Am-henth-f is depicted as a bearded, black man.

Amenhotep III (Egypt) *see* Amenhotep, Son of Hapu.

Ameni (Egypt) *see* Aai.

Ameno-uzume-no-kami (Japan) *see* Ama-no-Uzume.

Amenophis (Egypt) *see* Amenhotep, son of Hapu.

Amenophis I (Egypt) *see* Amenhotep 1.

Amenotsudoe-chine-no-kami (Japan) *see* Kushi-nada-hime.

Ament (Egypt) *see* Aai and Amentet.

Also known as: *Amenet, Ament-ra, Amentet; Amenti, Amonet, Amunet, Iment.*

Goddess of the Underworld. Earth Mother. Originally from Libya, Ament was said to live in a tree near the World Gates. Her name means "hidden" from the word Amenti. Amentet, also called Amenti, Ker-neter, Tan, The West, or The Land of the Setting Sun, is where the dead assembled waiting for the sun god Ra's boat to pass. Her function was to offer nourishment to approaching souls. If they accepted, they were bound to follow the gods, live in the realm of Osiris and never return to earth. She was an early Egyptian deity, possibly the mother of Ra, and said to be an aspect of Isis in Thebes. As Ament or Amunet, she was a consort of Amen at Karnak, a primeval deity, member of the Ogdoad, and mentioned in the Pyramid Texts. From the hymn inscribed on the walls of the temple of Hebt, in the Great Oasis, it is indicated that Ament had all the attributes of the goddess, Net. She is shown as Ament-Ra, the wife of Amen, who in this context is a local god in Apt. She appears as a ram-headed goddess breast-feeding Horus. In time, Ament was usurped by the goddess, Mut. Ament's emblems are the hawk and the feather. She is depicted with the head of a cat, ram, sheep or serpent and is often portrayed with the crown of Lower Egypt. For goddesses of the west who welcomed the dead, *see* Aai, Amentet, Hathor, Isis, Maat, Neith, and Nut. *See also* Amen; Mut; Ogdoad.

Ament-Nefert (Egypt)

One of the seven goddesses who minister to Osiris in the Second Hour of the Night. *See also* Aaru; Shesat Maket Neb-S; Tuat.

Ament-Ra (Egypt) *see* Ament.

Amentet (Egypt)

Also known as: *Amenthes, Amenti, Ker-neter, Tan, The West.*

The Underworld. The Egyptian meaning for Amentet is "hidden place." In Plutarch's account of the introduction of the deity Sinope into Egypt, he used the word Amenthes as a "subterraneous region." In Egyptian mythology, Amentet is where the sun sets and the dead come into contact with the deities; a hidden place. When the deceased souls encountered the deity they had worshipped while alive, and if they knew the magic words necessary for entry, they were granted admission to Ra's sun boat for the journey through Tuat (the underworld). When the sun rose at daybreak, they were allowed to roam around until sunset when they again continued their journey. Osiris (Khenti Amentet) was another name for him when he usurped the god An-her. *See also* Aaru; Amen; Ament; An-her; Apis (A); Hathor; Hell; Maat; Neith; Nut; Seker; Serapis; Sinope (Greek).

Amentet-Nefert (Egypt) *see* Aaru.

Amenthes (Egypt) *see* Amentet.

www.ebook3000.com

Amenti (Egypt) *see* Aaru; Ament; Amentet.

Ameretat *Amardad, Amererat, Murdad* (Persia)
He is the god of all green plants, health, and long life. Ameretat is also one of Ahura Mazda's attendants. *See also* Ahura Mazda; Amesha Spentas; Haurvatat.

Amergin *Amairgen, Amairgin, Amhairghin* (Celtic)
A divine judge, a bard, and a shape-changer, Amergin was one of the leaders of the Milesian conquerors of Ireland. A poem by Amergin dating to the seventh century C.E. is said to be the oldest Celtic literary record (in the "Yellow Book of Lecan"). A Druid, he was known as the chief counsellor of the Sons of Mil (Melesians, Milesians), who are descendants of the Gaels. In some myths, the Celtic goddesses, Banbha, Fotia and Eriu separately approached him to request that the island, named after her. Eriu, an eponym for Ireland, was chosen. When the Sons of Mil encountered the Tuatha De Danann and demanded surrender, the Tuatha De Danann decided to let Amergin judge who should stay on the island. His decision was that the Sons of Mil should leave for the magical boundary known as the ninth wave. They did as requested but in time returned and landed again. The Tuatha De Danann mystically whipped up a wind storm that sailed them back into the sea. Amergin, with a change of heart, in turn invoked the wind and the sea to be still, permitting the Sons of Mil to return. Amergin's poetry is often compared to the ancient British poet, Taliesin. For the results of this episode see Tuatha De Danann. *See also* Banbha; Cu Chulain; Tuatha De Danann.

Amesha Spentas *Amahraspands, Amesho Spends, Ameshospends Amshashpands* (Pahlavi dialect), *Amshaspends* (Zoroastrian; Persia)
Ahurha Mazda is the president of the council of six ministers known as the Amesha Spentas. They are Vohu Manah, who represents "Good Mind" or "Benevolence," protects animals and is responsible for taking the souls of the just to Paradise; Asha Vahishta ("Perfect Order"), who is the protector of fire and of the physical and moral order of the world against demons; Khshasthra Vairya ("Good Power," in Pahlavi Shahriver), the protector of metals and the defender of the poor; Spenta Armaiti ("Devotion and Wisdom") the ancient and wise patroness of the earth, who appears devoted, adoring and submissive; Haurvatat ("Wholeness," "Health," "Prosperity") who represents water, and brings prosperity and health to mortals; and Ameretat ("Immortality"), who oversees plants. Haurvatat and Ameretat are usually joined to represent their position of presiding over all the necessaries of life, including fruit and vegetation. Sometimes Sraosha ("Obedience") is included to complete the holy number of seven when Ahura Mazda is not included in the group. The Amesha Spenta, three males and three females, are said to be aspects, personifications, or attributes of Ahura Mazda. Some scholars believe that they are based on ancient gods. In later times they were thought of as gods or archangels created by Ormazd (the later name for Ahura Mazda) out of sun matter. Their function is to assist him in creating and governing the universe. Ormazd reveals himself to humans through the Amesha Spenta. These gods are depicted seated on golden thrones in the House of Song on the heaven or bridge known as Chinvat where all mortals pass at death. Compare the Amesha Spentas to Adityas (India) and Kudai (Siberian). *See also* Aeshma; Ahura Mazda; Ameretat; Apo; Asha Vahishta; Atar; Chinvat; Haurvat; Khshasthra Vairya; Pairika; Rashnu; Spenta Armaiti; Vayu; Vohu Manah; Yata; Yazatas.

Amesho Spend (Persia) *see* Amesha Spentas.

Ameshospend (Persia) *see* Amshaspands; Amesha Spentas.

Amet-tcheru (Egypt)
One of the seven goddesses who minister to Osiris in the Second Hour of the Night. *See also* Shesat Maket Neb-S; Tuat.

Amhairghin (Celtic) *see* Amergin.

Ami-Hemf (Egypt)
Also known as: *Dweller in His Flame.*
He is a mighty serpent fifty feet long who lives on top of Bakhau, the Mountain of the Sunrise. He is possibly connected with the underworld. *See also* Apepi.

Amida (Buddhist; Japan; originally India)
Also known as: *A-mi-t'o-fo* (China), *Amidas* (Japan), *Amita* (Japan), *Amitabha* (The Buddha of Immeasurable Light, India), *Amitayus,* (The Buddha of Immeasurable Life Duration; India), *Avalokitesvara* (India), *Bato Kannon* (India), *Bato-kwannon* (India), *Dai Itoku-Myoo* (Japan), *Dhyani Buddha Amitabha* (India), *Hod-dpag-med* (The Buddha of Immeasurable Light; Tibet), *Kanro-o* (Japan), *Muryoju* (Japan), *Muryoka* (Japan), *Od-dpag-med* (Tibet), *Omito, Omit'o-fo, Omito-fu, O-mi-t'o Fo* (China), *O-pa-me* (Tibet).
Amida is the same as Amitabha (India). While still a Bodhisattva, Amida Buddha refused enlightenment for himself unless he was granted the ability to bring Nirvana to anyone who appealed to his name. He vowed not to enter Nirvana until he saved all humans. His western abode, Sukhavati, meaning "Land of Bliss," is known as Gokuraku-Jodo (Japan), Nirvana (India), and Hsi T'ien (China). Nirvana is open to all who call on his name. Here one has the opportunity for rebirth. The Sanskrit original of the name Amita is Amitabha. Amitabha is the incarnation of Gautama, who became Buddha. Amida, known as Omito-fu (see above for variant spellings), in China, was brought to that country by the middle of the second century C.E. although the transcription of Sanskrit to Chinese began in approximately C.E. 65. The worship of the Amida Buddha was taught in Japan by the monk Kuya in 951 and Genshin (942–1017). Initially, Amita was one of the innumerable deities in the Shingon pantheon; later he became the primary deity of the Jodo and Shinshu sects in Japan. Amida in his aspect as one of the Five Dhyani Buddhas is known as Amitabha in Japanese Buddhism, and is favored by the Shinshu and Jodo-Shu traditions of Buddhism. The worship of Amida was never as popular in India proper as it was in Central Asia and the Far East. In India, Amida, known as Amitabha, was thought to be the incarnation of Buddha as compassionate spirituality. The esoteric traditions recognize three Amidas: Muryoju, Muryoko, and Kanro-o. In some traditions, Avalokitesvara is the spiritual son of Amitabha and the ruler of Sukhavati. His sakti (consort) is Pandara. Amitabha or Amitayus rules the Western Paradise known as Sukhavati; Aksobhya rules the Abhirati universe in

the east; the Master Physician, Bhaisajyaguru is also in the east. Dharmadhvaja was the first Tashi Lama of Tibet (also called Panchen Rimpoches) and is considered to be an incarnation of Amitabha. His Tibetan name is bLo-bzan-chos-kyi-rgyal-mtsan or Lob-sang-chho-chi-gyal-tshen. Amida is often depicted sitting with crossed legs on a lotus. He is often shown with his two palms folded face up, one on top of the other resting on his lap. He is also shown standing with an uncovered head, dressed in Indian costume, with one arm bent, fingers pointing skyward. The other arm is extended, with the fingers directed to the earth. He is usually red, which is the color of paradise, and is frequently shown enthroned in the center of paradise. His arm and hand positions indicate that heaven and earth are witness to his vow not to enter Nirvana until all human beings have been saved. His escort is the peacock. In the Japanese iconography, he is usually red and is frequently shown enthroned in the center of paradise. This depiction is known as "Kuwarishiki no Amida." Another popular Japanese depiction shows Amida appearing behind the mountains. This is known as "Yamagoshi no Amida." His emblems are the bell (ghanta) and the begging bowl (patra). His symbol is the pink lotus which he often holds. The lotus represents purity and the acceptance of situations outside of itself. When shown on the alter (stupa), he always faces west (the location of paradise). In the World of Forms mandala, Muryoju (Amitayus) is in the central group underneath the Dainichi-nyorai; in the World of Ideas mandala, he is above the head of Dainichi-nyorai. Amida in his Dhyani Buddha form as Amitabha or Amitayus is red and is seated in a meditative posture. His station is west and his vehicle is the swan. Amitabha sits on the Peacock Throne, symbolizing openness and acceptance. The peacock symbolizes the power and beauty of transmutation. The peacock is said to have the ability to eat poisons and transform them into the beauty of its feathers. Amitabha is the symbol of passion and desire. The wisdom corresponding to the poison is discrimination, which gives the detachment for passion to become compassion. In Japanese Buddhism, Amida is considered by some to be a manifestation of the Shinto sun goddess Amaterasu. For a description of Amida's dwelling place, *see* Sukhavati. As Amitabha, he is on the mandala of the five Tathagatas; *see* Dai Itoku-Myoo (Japan), Vairocana, and Yamantaka for Amida's wrathful manifestation. Compare to Adam. *See also* Aksobhya; Amaterasu; Avalokitesvara; Bhaishajyaguru; Dai Itoku-Myoo; Dainichi-nyorai; Dhyani Buddhas; Fuji; Heruka; Miroku-Bosatsu, Monju-Bosatsu; Pandara; Stupa; Sukhavati.

Amida Buddha (Japan) *see* Amida.

Amidas (Japan) *see* Amida.

Amighavajra (India) *see* Amoghasiddhi.

Amirini (Yoruba People, Africa) An early goddess.

Amisodaurus (Greek) *see* Chimaera.

Amit *Amam, Am-mit*
Also known as: *Amamet, Amamet the Devourer, Ammut, Amunet, Eater of the Dead, Devourer of Amenti;* (Egypt).

Demonic goddess. Heart-eater of sinful dead souls. Amit, a monster deity, with the head of a crocodile, the body of a lion and the rear end of a hippopotamus, stands by in the Hall of Judgment, ready to chew up the hearts of departed souls who are judged as guilty. It appears that Amit was likely hungry as records do not indicate that he ever performed this task. The Egyptians presented a list known as the "Negative Confession" list to the judges. It was prepared before death and placed in the tomb upon death. This list prefaced every unacceptable act with the phrase, "I have not," thus insuring safe passage through the Hall of Judgement, if a series of other questions were answered properly. *See also* Aati; Anubis; Maat; Negative Confession; Thoth.

Amita (Japan) *see* Amida.

Amitabha (India) *see* Amida.

Amitayus (India) "The Buddha of Immeasurable Light." *See also* Amida.

Amitolane (Zuni People, United States) "The rainbow."

Amm (South Arabia)
The meaning is either ancestor or uncle in the ancient tongue. It can also be construed to be a name for the moon. *See also* Ab; Shahar.

Amma (A) (Dogon People, West Africa)
Supreme creator and god of fertility and rain. His wife is Earth. They are the parents of the twins. The twins have snake-like appearances including forked tongues. After leaving his wife he created four males and four females which were the first humans. He was said to have created the first jackal named Ogo. In a variation of the myth, the goddess Akongo created the first mortal. Amma mated with her and they created the twins. *See also* Akongo; Nommo.

Amma (B) (Teutonic)
Also known as: *Ama, Grandmother.*

In Teutonic belief, Amma was a mortal woman. Heimdall (also known as Rig), slept between Amma and her husband Afi. From Heimdall's union with Amma, Karl, the founder of the race of peasants was born. *See also* Afi.

Amma (C) (India) Goddess of the Kaveri River.

Amma (D) (India) *see* Gramadeveta.

Amma-Ana-Ki (Assyro-Babylonian) *see* Ea.

Ammanavaru (India) *see* Gramadeveta.

Ammehet (Egypt) *see* Aaru.

Ammi-Seshet (Egypt) A form of Maat as a fire goddess.

Ammon (Egypt) *see* Amen.

Ammon, Oracle of (Greek) *see* Andromeda.

Ammut (Egypt) *see* Amit.

Amogha-Siddhi (India) *see* Amoghasiddhi.

Amoghapasa Lokeswar (Buddhist; Nepal)
Also known as: *Avalokitesvara.*

Amoghapasa Lokeswar is shown four-faced, with eight arms. He stands on a lotus. In his four right hands, he holds the Vajra, the sword, the goad and the bow. In his four left hands he holds

www.ebook3000.com

the Ghanta (bell), the Tridandi, the noose and an arrow. He is honored to prevent poverty. *See also* Avalokitesvara; Vasundhara.

Amoghasiddhi (Buddhist; India)

Also known as: *Amogha-Siddhi* (Almighty Conqueror; Sanskrit), *Amoghasiddi, Amoghavajra* (Sanskrit), *Dhyani Buddha Amoghasiddhi, Don-yo-dup-pa* (Tibet), *Don-yod-grub-pa* (Tibet), *Fuku* (Japan), *Heruka.*

Amoghasiddhi is the fifth Dhyani Buddha, the Buddha of meditation. On the mandala of the five Tathagatas, he represents the cosmic element of confrontation (sanskara), and the pure quality of air and wind. He is the embodiment of the rain season. Known as the "Omnipotent Conqueror," he is from the powerful Karma family. He appears on the fifth day in Bardo from the Realm of Accumulated Actions. His name means "Accomplishing All Actions, All Powers." His spiritual consort (sakti) is Samaya-Tara, also known as Dolma, or the Green Tara, an aspect of Tara. With him on the fifth day are the male bodhisattvas Vajrapani (also known as Sgrib-pa-rnam-sel in Tibet) who is the "Clearer of Obstructions," and Sarvanivaranaviskambhin (Sgrib-pa-rnam-sel in Tibet), known as the "Clearer of Obturations." There are also two female bodhisattvas, Ganda, also known as Gandhema (and as Dri-chha-ma in Tibet), meaning "She Spraying Perfume" and Naivedya (also known as Nidhema in the Sanskrit language and as Zhal-zas-ma in Tibet), meaning "She Holding Sweetmeats." She is associated with the light of wisdom and is depicted as green in color. In front of Amoghasiddhi's shrines in Nepal, a small square pit is found which is meant for the snake, a symbol of protection from the rain. The wrathful manifestation of Amoghasiddhi is the green Heruka Buddha. Amoghasiddhi is green in color and his symbol is the sword (khadga) or the double thunderbolt (visvavajra). Green is the color of envy and is also called the light-path of the all-performing wisdom. The visvavajra, indestructible, is the symbol of fulfilling all actions. He always faces his region, the north. Seated in a meditative pose (asana dhyana), his left hand lies open on his lap and his right hand is held in the gesture of protection (abhaya mudra). In this gesture the arm is elevated and slightly bent. The hand is lifted to shoulder level with the palm turned outward and all the fingers extended upward. Sometimes he is depicted with a seven-headed serpent in the background which serves as an umbrella. His mount (vahana) is a dwarf or Garuda (half-bird and half-man). He is sometimes mounted on an eagle. When Amoghasiddhi and Samaya-Tara are depicted embracing on the back of the Garuda, who is a musician, it plays the cymbals as it flies through the air. This particular type of Garuda is known as shang-shang and is sometimes called the Harpy-throne. In Greek mythology, the Harpy is female. In the Buddhist tradition, the harpy can be either sex. It symbolizes mightiness, conquest over all the elements and fulfillment. The goddess Ganda ("She Spraying Perfume") is depicted holding a shell-vase of perfume. She represents sense-perception required to accomplish skillful activity. The sweetmeats held by Naivedya represent meditation as the food required to nourish skillful action. For the five Tathagatas; *see* Avalokitesvara; Ganda; Heruka; Vairocana; Vajrapani. *See also* Dhyani Buddhas; Tara (B); Vajrasatwa.

Amoghasiddi (India) *see* Amoghasiddhi.

Amon (Egypt) *see* Amen (B); Atum.

Amon-Ra (Egypt) *see* Amen.

Amon-Re (Egypt) *see* Amen.

Amonet (Egypt) *see* Ament.

Amor (Roman, Greek)

Also known as: *Cupid, Cupido, Eros* (Greek).

Boy-god of love. He is the son of Venus and Mars or Mercury. *See also* Cupid; Eros.

Amphianax (Greek) Another name for Iobates (q.v.).

Amphiaraus (Greek) *see* Adrestus; Argonauts.

Amphibia (Greek)

Another name for Nicippe, the daughter of Pelops and Hippodameia. *See also* Nicippe.

Amphinome (Greek) *see* Jason.

Amphion (Greek)

Amphion is the hero son of Zeus and Antiope and the twin brother of Zethus. Abandoned at birth, the brothers later became joint rulers of Thebes. Amphion married Niobe, the daughter of Tantalus, and they became the parents of twelve children. The brothers later became co-rulers of Thebes and settled into a friendly partnership. Amphion played a lyre given to him by Hermes and provided the cultural atmosphere. Zethus, more pragmatic, was interested in breeding cattle. His family life fell into chaos when Niobe began bragging about her numerous children and berated the goddess Leto for only giving birth to two offspring. The offended goddess instructed her children, the deities Apollo and Artemis, to slaughter the offensive women's pride and joy, her children. Some say only two survived, Amyclas and Chloris. Amphion was either killed in melee, or grief-stricken committed suicide. Zethus also encountered tragedy that he could not bear. For details about Amphion's birth, *see* Antiope. For details about the deaths of their children, *see* Niobe. *See also* Apollo; Leto; Tantalus (A); Zethus.

Amphithea (Greek)

She is the daughter of Pronax and the sister of Lycurgus. Amphithea married her uncle, Adrestus. She became the mother of Aegialeus, Aegialeia, Argeia, Cyanippus, Hippodameia, and possibly Deipyle. *See also* Adrestus; Anticleia (A); Apsyrtus; Autolycus (A).

Amphithemis (Greek) *see* Acacallis.

Amphitrite (Greek)

Also known as: *Salacia* (Roman).

Sea goddess. Amphitrite, the personification of the sea, is the daughter of Nereus and Doris or of Oceanus and Tethys. As the daughter of Oceanus and Tethys, she is one of their fifty daughters, known as the Nereids. Poseidon fell in love with her and attempted to court her. She rebuffed him and ran to Atlas for protection. Undaunted, Poseidon sent scouts the world over in search of her. One of his envoys, Delphin, found her and convinced her to marry the sea god. To show his gratitude, Poseidon placed the Dolphin constellation in the sky in Amphitrite's honor. Poseidon and Amphitrite were the parents of many children, including Albion, Benthesicyme, Charybdis, Rhode, and Triton. As Salacia, she is the Roman goddess of springs. Amphitrite is shown riding in a chariot with Poseidon drawn by Tritons blowing conch-shells. She carries a trident in her hand. *See also* Nereids; Poseidon; Scylla.

Amphitryon (Greek) *see* Acrisius; Alcestis; Rhadamantus.

Amra (Afghanistan) *see* Imra.

Amraphel (Babylonian) *see* Hammurabi.

Amrata (India) *see* Amrita.

Amrita *Amrata, Amrta* (Hindu, Vedic; India)
Also known as: *Nia-Jara, Pi-Yusha.*

Amrita, the "Elixir of Life" or "Water of Immortality," is what the gods searched for during the Churning of the Ocean of Milk. The vial containing the beverage is known as Amrita-Kumbha. Amrita is sometimes said to be the fruit of a tree. The celestial goddess associated with Amrita is Amritika. In the Vedas, the name Amrita is used to signify various items that are sacrificed, but it is particularly applied to soma juice. Often Amrita and soma are confused but are considered to be closely associated and the mythology is often the same. *See also* Admida; Ambrosia (Greek); Amida; Amrtakundali; Haoma (Indo-Iranian); Indrani (regarding the Parijata Tree); Kurma (regarding the Churning of the Ocean of Milk); Sesha; Soma; Vishnu.

Amrita-Dhari (Tibet) *see* Amritahari.

Amrita-Kumbha (India) *see* Amrita.

Amrita Kundika (Japan) *see* Gundari-Myoo.

Amrita Surabki (India)
Buddha's begging-bowl. *See also* Buddha.

Amritahari Amrita-Dhari (Tibet) *see* Ankusha; Kinkini-Dhari.

Amrite Kundalin (Japan) *see* Gundari-Myoo.

Amritika (India) *see* Amrita; Soma.

Amrta (India) *see* Amrita.

Amrtakundali *Amitra-Dhara* ("Urn of Nectar"), *Gundari-Myoo* (Japan); (Buddhist; Tibet)

Amrtakundali (Coil of Nectar) is one of the four wrathful guardians of the gates in Bardo, the after-death state between death and rebirth. He is responsible for the northern gate and for the distribution of Amrita, the beverage of immortality. The other guardians are Vijaya the Victorious, who guards the eastern gate; Yamantaka, Destroyer of Death, the guardian of the southern gate; Hayagriva the Horse-Necked, who guards the western gate. There are also four female guardians: Ankusa, the Hook; Pasa (Pashadhari), the Noose; Srnkhala, the Chain; and Ghanta, the Bell. On the sixth day in Bardo, along with the guardians, the five Dhyani Buddhas appear. Vairocana and his consort appear from the central realm. The central realm is the All-pervading Circle. Amoghasiddhi and his consort appear from the northern realm, the Realm of Perfected Actions. Vajrasattva and his consort appear from the eastern realm, the Realm of Complete Joy. Ratnasambhava and his consort appear from the southern realm, The Glorious Realm. Amitabha (Amida) and his consort from the western realm, the Blissful Realm of Lotuses. Each Buddha and his consort have their attendants with them. The six sages, known as the Blessed Ones also appear. They represent the six realms of the world. They are Indra, of the hundred sacrifices, sage of the gods; Vemacitra, Splendid Robe, sage of the jealous gods; the Lion of the Sakyas, sage of the mortals; Dhruvasinha, Steadfast Lion, sage of the animals; Jvalamukha, Flaming Mouth, sage of the Pretas (hungry ghosts); and Dharmaraja, the Dharma King, who presides over the hell-beings. The All-Good Mother and Father of all the Buddhas, Samantabhadra and Samantabhadri also appear. A total of forty-two deities appear. The four goddesses who guard the doors of Bardo are known as the Wang-Chugmas. They have human-like bodies and animal heads and appear on the twelfth day in Bardo. To compare to the Four Great Kings, *see* Dhritarashtra. Compare to the Lokapalas. *See also* Gundari-Myoo; Hayagriva; Yamantaka.

Amset *Am-Sit* (Egypt)
Also known as: *Imseti, Meslam, Mestha, Mesti.*

A guardian spirit, Amset is one the the four divine sons of Horus. His brothers are Tuamutef, who guards the east, Hapy, who guards the north, and Qebhsneuf, who guards the west. Amset is the guardian of the south. (Some say he guards the northern section.) He is the Canopic guardian of the stomach, liver, and lower or large intestines. (Canopic vases hold the viscera of the dead.) Amset and his brothers are all connected with the life in the underworld. Amset assisted Horus when Osiris was mummified. He is represented by a human head on an egg shaped vase. *See also* Hapy (A); Horus; Osiris; Qebhsneuf; Tuamutef.

Amseth (Egypt) A god who is associated with Thoth.

Amshashpands (Persia) *see* Amshaspands.

Amshaspands *Amahraspands, Ameshospend, Amshashpands* (Pre-Christian Gnostics; Simon Magus sect; Zoroastrian; Persia)
Also known as: *Amesha Spentas.*

Immortal spirits. Archangels. A half-Gentile, half-Jewish sect of Gnostics who believed, as did Zoroaster that there were six "roots" or aspects of the Supreme Being. (Some ancient texts say seven.) These later deities are Ameretat (Immortality), Asha Vahishta (Truth), Haurvetat (Good Health), Khshathra Vairya (Right Law), Spenta Armaiti (Wisdom), Vohu Mano (Good Mind). Simon called them Mind, Thought, Voice, Name, Desire, and Reason. Ahriman created six evil archangels to oppose the Amshashpands. Among them were Tauru, Zairicah, also spelled Zairicha (sickness and death), Khurdad and Murdad (hunger and thirst) and others. Some say they were created out of sun matter by Ormazd. They are a form of Amesha Spentas (q.v.).

Amshaspends (Persia) *see* Amesha Spentas.

Amsu (Egypt)
Also known as: *Amsu-Amen, Min-Amen.*

www.ebook3000.com

Local creator deity. A god worshiped in the nomes (cities or districts) of Herui and Amsu. In one of the hymns Amsu-Amen or Min-amen is called "Maker of Everlastingness" and "Lord of Eternity." Amsu is depicted as a human figure wearing the double plume headdress and holding a flail in his left hand. Identified with Amen-Ra. *See also* Amen; Amsu; Min.

Amsvartner (Teutonic)
This is the ocean that surrounds the island where Fenrir the wolf is chained. *See also* Fenrir.

Amu-Aa (Egypt)
One of the gods who accompany Osiris during the Second Hour of the Night. *See also* Shesat Maket Neb-S; Tuat.

Amulet
This is a charm worn to ward off evil or to bring good fortune. *See also* Ab; Guabonito; Kagu-tsuchi; Khepri; Lilith; Marduk; Scarab; Shina-tsu-hiko; Stupa; Talisman; Tet; Vessavana.

Amulets (Egypt) *see* Ab.

Amun (Egypt) *see* Amen (B); Atum; Keket; Khensu; Min; Nut.

Amun-Kneph (Egypt) *see* Khnum.

Amun-Min (Egypt) *see* Amen (B).

Amun-Re (Egypt) *see* Amen (B).

Amunet (Egypt)
Also known as: *Nuit.*
Goddess of Mystery. She and Amen created light. *See also* Amen; Flame; Island of Flame; Neith; Niut.

Amurru (Babylonian, Phoenician) *see* Aleyin; Anat; Qadesh; Reshep.

Amvika (India) *see* Ambika; Sati (A).

Amyclas (A) (Greek)
He is one of the six sons of Amphion and Niobe. He also has six sisters. Apollo murdered his brothers and Artemis murdered all of his sisters except Chloris. Amyclas is thought to have survived as well. *See also* Amphion; Apollo; Artemis; Leto.

Amycus (A) *Amykos* (Greek)
Amycus is the son of Poseidon and the ash nymph Melie and the brother of Mygdon. He was the king of the Bebryces who challenged all strangers to boxing matches. A giant, known for his strength, he was reputed to have killed many opponents. His brother Mygdon had died in an earlier battle with Dascylus the king of Mariandyni or his son Lycus over a land dispute. Amycus was killed in a match with Polydeuces when the Argonauts landed on his shores. *See also* Argonauts; Polydeuces; Poseidon.

Amycus (B) (Greek) *see* Ixion, Nephele.

Amycus (C) (Greek)
He was the companion of Aeneas. They were both killed by Turnus (q.v.). *See also* Aeneas.

Amykos (Greek) *see* Amycus (A).

Amymone (Greek)
River goddess. A Danaid, she is one of the fifty daughters of Danaus and Europa. She is the mother of Nauplius by Poseidon. She married Enceladus, the son of Aegyptus and murdered him on their wedding night. After having sex with Poseidon, in arid Argos, a perpetual spring issued forth. In another story, she was attacked by a Satyr but rescued by Poseidon who told her to draw his trident from a rock. This she did and a spring came forth. In that spot, the monster Hydra was born. *See also* Aegyptus; Danaides; Danaus; Europa; Hydra; Hypermnestra; Poseidon.

An (A) (Akkadian, Assyrian, Babylonian, Sumerian; possibly Egyptian)
Also known as: *Ana, Anat, Anath, Anatu, Anu, Anum.*
High God of Heaven. The goddess Nammu who personified the eternal primeval sea is the mother of the Sumerian sky god An. With Ki, the earth goddess, An became the father of the god of air, Enlil. In later times, Enlil superseded An as chief of the Sumerian pantheon. Semitic Assyrians referred to Anu and Anatu (Anath) as god and goddess of heaven. He was part of the Sumerian triad of high gods: An, Enlil, and Ninhursag. Some say the trinity was An, Enlil and Enki. There is a possibility that Babbar was included. In another tale, it is related how the cosmos was divided among a slightly different tripartite: the sky to An, the Earth to Enlil, and the underworld to the goddess Eriskigal. Some writers say the goddess Innini represented the female principle of An. Most legends refer to Anu, but An might have been a separate deity. In a separate tale An was the brother of Ki and they were the sons of Nammu. Both were depicted in the shape of a mountain. They were also said to be the creators of Enlil. In the Babylonian Genesis, "Enuma Elish," the tale is told of the conflict between Anu and Kumarbi. It is in this narrative that the theme of castration first appears. The tale of An is similar to that of Ra of the Egyptians where Isis refers to the supreme god. The Egyptians called An a form of Osiris. Some say the name Anu is the Akkadian form of An. *See also* Ana; Anat; Anath; Anatna; Anatu; Anu (Celtic); Anum; Innini; Nammu.

An (B) (Teutonic) *see* Dwarfs.

An (C) A title for Osiris meaning sun or moon god.

An Ut (Egypt) *see* Anubis.

An-a-f (Egypt)
A little known Egyptian god, possibly of the underworld. One of the forty-two assessors or judges of the dead. *See also* Assessors.

An-Aareretef (Egypt)
Also known as: *An-Aretf.*
Assessors of a section of the Tuat (q.v.).

An-Aretf (Egypt) *see* An-Aareretef.

An-her *see* Amentet; Anhur.

An-hetep-f (Egypt).
One of the forty-two assessors or judges of the dead. *See also* Assessors.

An-Hur *Anher, Anhur* (Egypt)
Sun god. An-hur was a form of the Egyptian sun god Ra. He

is the son of Hathor (goddess of beauty, love and joy) in her form of Her-t. An-hur stood in the prow of the sun's boat as "Slayer of the Enemies."

An-Kung (China)
Goddess of Sailors. Wife or consort of H'ien-hou.

An-mut-f (Egypt) One of the gods in the Pyramid Texts.

An-pu (Egypt) *see* Anubis.

An-tcher-f (Egypt) One of the gods in the Pyramid Texts.

Ana (A) (Celtic) *see* Anu (A).

Ana (B) (Middle Eastern) *see* Anat; Anu (B).

Ana-Hid (Armenian) *see* Anahita.

Ana Nse Kukuroko (Ashanti People, Africa) *see* Ananse.

Ana-purna *Anapurna, Anna Perenna* (Roman), *Anna-Purna, Annapurna* (Hindu; India)
Also known as: *Parvati.*

Ana-Purna is the ancient Indian goddess of daily bread. Her name means "full of food." Her abode is on the top of Annapurna mountain. She is often shown seated, feeding a child. The Romans called her Anna Perenna the goddess of spring, who personified life, health, and plenty. Mars used her to secure Minerva for himself. She is often identified with Devi (q.v.). *See also* Durga; Parvati.

Anadyomene *see* Aphrodite.

Anahit (Persia) see Anahita.

Anahita *Anahit, Anahite, Anait, Anaitis* (Chaldean, Iranian, Persian, Semitic [possibly])
Also known as: *Anaitis* (name in later times), *Anta* (Asia Minor), *Ardevi Sura Anahita* (The High, Powerful, Undefiled One), *Nane, Venus* (Roman).

Female Yazata water genius. Goddess of procreation. During the times of the Achaemenians (558–330 B.C.), Anahita was widely worshipped. She is the ancient Persian Great Mother; goddess of fertility and fertilizing waters; particularly the spring among the stars from which all the rivers of the earth flow. She appears in the Mazdaism pantheon as a chief deity associated with Ahura Mazda and Mithra. Known as Ardevi Sura Anahita in the "Avesta," she purified the seed of all males, sanctified the womb of all females and purified their breast milk. Women in childbirth appealed to her for aid and comfort. She was also called upon in times of severe illness. In Armenia, she was the Mother Goddess, known as the mother of all wisdom, the giver of life, and the daughter of Ahura Mazda. She is approached by female followers of marriageable age for guidance. Men desiring strong females as spouses call upon her. In the past, green branches accompanied sacrifices to her. Her followers, nobility of both sexes, entered her services as slaves; the women engaged in sacred prostitution at her shrine before marriage. In Chaldean astrology she was associated with the planet Venus. The bull was her sacred animal and sacred herds of white heifers were branded with her mark, a torch. The heifers were also sacrificed to her. She drives a chariot pulled by four horses who represent the wind, rain, clouds and sleet. She is depicted as strong, tall, beautiful, and pure. She wears a golden crown with eight rays and a hundred stars, a golden mantle and a golden necklace around her neck and is adorned with thirty otter skins. Compare Anahita to the Vedic sun goddess, Surya (B). *See also* Ahura Mazda; Apam Napat; Hvare-khshaeta; Mitra; Qadesh; Tishtrya; Vourukasha (A); Vourukasha (B); Yazatas.

Anahite (Persian) *see* Anahita.

Anait (Persian) *see* Anahita.

Anaitis *Anahita* (Persia)
The goddess Anahita was called Anaitis in later times. As Anaitis, she was popular in Asia Minor and the Mediterranean. *See also* Anahita.

Anakhai (Mongol)
Spirit of the dead. Anakhai is the soul that haunts its former home. It is dangerous to infants.

Anakim (Hebrew) *see* Rephaim.

Anala (India) *see* Agni; Vasus.

Anamaqkiu (Menominee People, United States)
This malignant spirit who caused the great flood by dragging Moqwais (the wolf) under the sea.

Anan (Celtic) *see* Eire.

Ananda (India) "Joy, Happiness." An epithet for Shiva.

Ananga (Hindu; India)
God of Love consumed by the fire of Shiva's third eye. *See also* Kama; Kami (A); Shiva.

Ananke (Greek)
Another name for the goddess of law and justice Themis.

Ananse *Anansi, Annancy* (Ashanti People, Africa)
Also known as: *Ana Nse Kukuroko, Annancy* (Native American People).

Creator and trickster deity. He is the son of Asase Ya and Nyame. Known as "The Enormous Spider," he is the creator of the sun, moon, stars, day and night. He often intercedes between gods and mortals and aids mortals by giving them the first grain. He is the first king of human beings. Some say Ananse won his stories (power) from the sky-god, Nyankopon. He is generally known in Native American lore as Annancy, who is also a spider. *See also* Abosom.

Anansi (Africa) *see* Ananse.

Ananta (India) An epithet of the world serpent Sesha (q.v.).

Ananta-Shayana (India) Epithet of Vishnu (q.v.).

Anaplades (Greek) *see* Hermaphroditus.

Anapurna (India) *see* Ana-Purna.

Anar *Annar* (Norse; Teutonic)
Also known as: *Onar.*

Creator. He is a creating father, who was the second husband to Nat (night). His child is Jord (the earth). Anar is possibly associated with water. *See also* Nat; Onar.

www.ebook3000.com

    - General Functions of the Eight Extraordinary Channels 190
    - The Eight Extraordinary Channels and Chi Kung 193
    - Special Functions of the Bridge and Regulator Channels............................. 193
    - Bridge Channels Yin and Yang Chiao Mo Function 193
    - Summary.. 195
    - Practice 196
- Part III - Opening the Functional and Governor Channels.................................. 205
    - Theory: The Functional and Governor Channels... 205
    - Chi Ball 206
- Part IV - Activating the Yin and Yang Channels on the Chi Belt.......................... 217
    - Theory 217
    - Yin and Yang Channels of the Arms.. 217
    - Projecting Healing Energy through the Fingers 217
    - Activating the Chi Belt - Dai Mo.. 222
    - Practice 223
- Healing Others.. 226
    - Summary and Combined Practice 226
    - Cosmic Chi Kung: Simple Combined Sequence 226

Chapter IX
Universal Tao Basic Practices

- Cosmic Inner Smile 232
- Six Healing Sounds... 236
    - The Six Healing Sounds - Practice 235

Appendix 241
- Guide to Acupuncture Points used in Cosmic Chi Kung 241
- Bibliography.. 249

Anat (Assyria, Canaan, Chaldea, Sumer then Egypt)
Also known as: *Ana, Anata, Anath, Anath-yahu, Anatha, Anatu, Anna-nin, Annuthat, Anta, Antit, Antum, Hanata, Quadesh* (Phoenician).

"Lady of Heaven." "Mistress of the Gods." Mother goddess. Earth goddess. She is the virgin daughter of Baal and sister of Aleyin, although in some legends she is the sister of Baal. As his sister, she is grief-stricken when he is murdered by the harvest-god Mot, who had attempted to woo her sexually. Overwhelmed, she wandered through the fields mutilating herself by gashing her cheeks. The goddess Shaphash came to her aid and together they went in search of the murderer. When they located him, they made him vomit his rival Baal. Then Anat murdered Mot in a particulary horrific manner. When he did not remain dead, he was killed again by her brother, Aleyin. Introduced in Egypt by the Hyskos (shepherd kings) Anat was said to be the consort of Baal-Sutekh. Her epithet is Qadesh and she is depicted as a warrior, defender of cities and dragon-slayer. She is the female counterpart of the god of war and thunder, Reshef, and was said to be his consort. The Sumerians regarded her, under the name Anatu, as the wife of Anu while the Egyptians considered her the wife of Set. She is the mother of Lamashtu, the Anunnaki and the seven Utukki. She, or as some say, the goddess Athirat, interceded to have El build a palace for Baal. As Anat, she is depicted with a helmet, shield and battle ax. When she is seated she is shown holding a shield and spear in her right and a club in her left. When standing, she is shown dressed in a panther skin and holding a papyrus scepter in her right hand and the ankh (emblem of life) in her left. She wears a white-feathered crown, sometimes with a pair of horns at the base. As Anat she compares to Aphrodite and Athena, and is the same as Anaitis. Anat is the northern Semitic name of Allat. She may have been a composite of Ashera, Astarte and Ishtar. Her name is connected with the Semitic word "ayn" ("source"). *See also* Aleyin; Allat; Asherah; Astarte; Baal; Qadesh; Reshef; Shaphash.

Anata (Middle East) *see* Anat.

Anath (Middle East) *see* Anat.

Anath-Yahu (Middle East) *see* Anat.

Anatha (Middle East) *see* Anat.

Anatis (Arthurian) *see* Vivien.

Anatu (Middle East) *see* Anat.

Anax (Greek) *see* Giants.

Anaxibia (A) (Greek)
There is a possibility that she is the daughter of Crisus. Her siblings are Astyoche and Strophius I. *See also* Acastus; Agamemnon; Antilochus; Helios.

Anaxibia (B) (Greek)
She is the daughter of Bias and Iphianassa. Her husband is possibly Pelias. Her children are Acastus, Alcestis, Hippothoe, Pelopia and Pisidice. *See also* Acastus; Alcestis; Hippothoe; Pelias.

Anaxibia (C) (Greek)
She is the sister of Agamemnon and Menelaus. Pylades is her son by Strophius I. She had a number of other children by Nestor, including, Antilochus, Perseus, Polycaste and Peisidice. *See also* Agamemnon; Antilochus; Menelaus; Perseus; Pylades.

Anaye (Navajo People, North America)
Also known as: *Alien Gods, Child of the Waters.*
Evil spirits. Destroyers of mortals. It was thought that the Anaye were destroyed long ago by the brothers Nayanezgani and Thobadzistshini some of them remain. They are Cold, Hunger, Old Age, and Poverty. The Anaye are monsters, giants and beasts. They are similar to the Tshindi devils. The Anaye are opposites of the Yei. *See also* Nayanezgani; Thobadzistshini.

Ancaeus Great (Greek) *see* Argonauts.

Ancaeus Little (Greek) *see* Argonauts.

Anchancho (Collao People, South America)
Also known as: *The Supay.*
Evil spirits. The Anchancho dispense all diseases and are sometimes thought to be the disease. They take possession of humans while they are asleep or frightened. They also entice mortals with an evil eye, enter their body, suck their blood and cause death. The Anchancho frequent mountain peaks, especially during storms. Their voices, sounding like the braying of an ass, can be heard during storms. *See* Ekkekko (good spirits) for a myth pertaining to the Anchancho and the Ekkekko. *See also* Achachilas; Supay.

Anchile, The *Ancile* (Roman)
The Anchile is the sacred shield belonging to Mars. It is guarded by the priests of Mars, the Salii. *See also* Mars.

Anchinoe (Greek) *see* Agenor (A); Danaus.

Anchises (Greek)
Light deity. Anchises and his brother Laocoon are the sons of Capys, who was the son of Assaracus, and Hieromneme. His cousin Themiste is the daughter of Ilus and Eurydice. Anchises, a king of Dardania, noted for his beauty was the lover of Aphrodite and the father of Aeneas, Hippodameis and Lyrus (about whom little is known). It is also thought by some that Hippodameis and Lyrus may be the children of Anchises and a mortal woman. Zeus, tired of listening to Aphrodite brag about the numerous affairs that she had magically arranged between unsuspecting deities and mortals, arranged a liaison between the great goddess and the youth. Overwhelmed by passion, she had the Graces anoint her with oil and bedeck her in a blazing red dress and jewels. She appeared to Anchises disguised as a mortal as he was tending his herd on Mount Ida. Delighted to accommodate her desires, he spent a heavenly night with her. The following morning, Aphrodite stood before him in all her glory and revealed her true identity. Anchises was astonished and fearful, for he had heard that mortal men who slept with goddesses would age prematurely. Cautioning him to keep their relationship a secret, she assuaged his fears and promised him a son who would be like a god. Drunk one night, Anchises forgot his promise and began to brag about his affair with the beautiful goddess. A very angry Zeus thrust a lightning bolt at him and from that day Anchise walked with a limp. Their son, Aeneas, known as "the pious one," went on to become a national hero of Rome. Compare this myth to the

myths of Attis; Cybele. In each case the male is wary of being depleted by sleeping with a goddess. *See also* Acestes; Aeneas; Aphrodite; Eurydice (C).

Ancient Spider (Micronesia) *see* Areop-Enap.

Andarta (Celtic) Bear Goddess.

Ander (Persia)

Ander is one of the evil spirits created by Ahriman to be his assistants. *See also* Ahriman.

Andhaka (Hindu; India)

Andhaka is the son of Kasyapa and Diti. This demon, who had a thousand heads and two thousand hands and feet, was a general nuisance to the gods. He walked around pretending to be blind although he had perfect vision. The great Hindu triad of gods, Brahma, Shiva and Vishnu, held a meeting to decide how to handle this menace. As they discussed the issue, the energy from their eye contact manufactured a brilliant feminine form. When they gazed upon her multi-colored beauty, each deity wanted to possess her. She divided herself into the three goddesses, the white Sarasvati, the red Lakshmi and the black Parvati. When Andhaka attempted to steal the magic Parijata tree from Swarga, he was slain by Shiva. Andhaka represents famine and the goddesses represent the past, present and future. *See also* Brahma; Diti; Kasyapa; Lakshmi; Parijata Tree; Parvati; Sarasvati; Shiva; Swarga; Vishnu.

Andhrimner (Teutonic) *see* Andrimne.

Andra (Persian)

Also known as: *Indra* (India).

Andra waits on Chinvat Bridge for the souls of sinners which he hurls into hell. *See also* Asha Vahishtra; Chinvat Bridge; Indra.

Andreus (Greek) *see* Cephissus.

Andriamanitra & Andrianahary (Madagascar)

Good and evil gods who created the earth and mortals. Andriamanitra made domestic animals and the hive with honey. Andrianahary made wild animals, and hornets. This in turn caused Andriamanitra to create magical cures for the evil caused by Andrianahary. Possibly the same as Ndriananahary and Zanahary (qq.v).

Andrianahary (Madagascar) *see* Andriamanitra and Andrianahary.

Andrimne *Andhrimner, Andhrimnir* (Norse; Teutonic)

Cook for the gods. Andrimne is the cook who roasts the meat from the boar Saerimne (also spelled Saehrimnir) in the cauldron Eldrimne, which never runs out of food. After the feasting on the meat the boar is restored to its former self, alive, well and ready to be eaten during the next meal. *See also* Odin.

Androgeus (Greek)

Also known as *Eurgyes.*

He is the son of Minos and Pasiphae. His siblings are Acacallis, Ariadne, Catreus, Deucalion, Euryale, Glaucus, Lycastus, Phaedra, Xenodice and others. His children are Alcaeus and Sthenelus. A famous athlete, Androgeus, under the name of Eurgyes, won every race at the Panathenaean games. While on his way to race in Athens, he was killed by the Bull of the Marathon. That incident was the cause of Athenians being sacrificed to the Minotaur. *See also* Acacallis; Aeacus; Ariadne; Minos; Minotaur; Pasiphae; Sthenelus.

Andromeda (Greek) Lunar deity.

Hero. Andromeda is the daughter of Cepheus (Ethiopian king of Joppa) and Cassiopeia. She is the wife of Perseus and mother of Alcaeus, Electryon, Heleus, Mestor, Perses, Sthenelus and Gorgophone. Andromeda's mother bragged that she and Andromeda were more beautiful than the Nereids. The incensed sea-nymphs complained to their protector Poseidon. To placate them, he sent a flood and a sea-monster to Philistia. Andromeda's father Cepheus consulted the Oracle of Ammon and was told that the only hope was to sacrifice his daughter. Naked, save for a few jewels, she was chained to a rock and left to be devoured by the sea-monster. Perseus, flying overhead saw her and swooped down. He consulted with her parents and agreed to rescue her if they would allow her to marry him. Reluctantly, they agreed. Andromeda was saved and the marriage followed immediately. Her fiancé, who was Agenor, the father of Phineus, or by some accounts, her uncle Phineus, barged into the wedding festivities with friends and a fight ensued. Perseus ended the fray by turning the upstarts to stone with the head of Medusa. This myth may come from the Babylonian tale of Marduk and Tiamat. It also parallels Heracles' rescue of Hersione. *See also* Ariadne; Gorgophone; Marduk; Nereids; Persus; Tiamat.

Anduruna (Mesopotamia)

In Babylonian mythology, Anduruna is one of the ancient names for the underworld. In Mesopotamian mythology it is defined as a heaven where the gods play. *See also* Arallu.

Andvare (Teutonic) *see* Andvari.

Andvari *Andvare* (Norse; Teutonic)

Also known as: *Alberich, Elbegast, Gondemar, Laurin, Oberon.*

Andvari, the fish-shaped dwarf king, guarded treasures of the gods, including the ring of magic, Draupnir (also called Andvarinaut). From this golden ring other golden rings constantly dropped. Hreidmar was holding the gods prisoners because Loki had killed his son Ottor (also spelled Otr). (Earlier, Ottor had been changed into an otter.) The price of the gods release was a quantity of gold. Loki stole the treasures and the ring Draupnir from Andvari to gain the prisoners release. Andvari, however, had put a curse on the ring. So it was that when Hreidmar received the ransom, he was killed by Fafnir, who in turn was killed by Sigurd. The House of Hredimar was torn apart with jealousy over the golden treasure and as noted, it was the cause of the downfall of Sigurd. As a pike, Andvari frequented waterfalls that came to be known as the Cascade of Andvari. *See also* Alberich; Andvarinaut; Fafnir; Hreidmar; Loki; Sampo; Sigurd.

Ane (A) (Nigeria) *see* Ala (B).

Ane (B) (Arabic) *see* Ala.

Anean People — Creation Legend (Peru, South America) *see* Sibu.

Anga-Raja (India) *see* Karna.

Angada (India) *see* Bali (A).

www.ebook3000.com

Angajan (Saora People, India) Moon goddess. *See also* Adununkisum.

Angana (India) *see* Apsarases.

Angara (India)

She is an Apsaras and monkey queen, the wife of Kesari and mother of monkey god Hanuman. *See also* Apsarases; Hanuman.

Angels (Arabic, Christian, Hebrew, Syrian)

Also known as: *Angel* (Singular), *Archangels, Cherubim, Lords, Powers, Seraphim, Thrones, Rulers.*

Messengers. When confronted with the problem of worshiping both the supreme god and the lesser divinities under one name, the early priests invented the orders of angels who were assistants to the primary deity. The Koran classifies them in various ways. Nineteen are in charge of hell-fire, eight support the god's throne on Judgment Day, several remove the souls of the righteous at death, two accompany every mortal during life; one writes the good deeds, and the other the evil deeds. Four of these are Archangels: Gabriel, Azrael, Israfel, Michael. The Syrians had three classes of angels: the upper are Cherubim, Thrones, Seraphim; the middle, Lords, Powers, and Rulers; the lower Angels, Archangels, Principalities. Some believe Gabriel was the highest of all angels. The early Hebrews grouped the angels into ten classes: the Bene Elohim, Cherubim, Erelim, Hashmalim, Ishim, Malachim, Ophannim, Seraphim, Sishanim, and Tarshishim. According to some authors all of the angels originated from the Egyptians who classed the inferior or lesser deities under one god. Some say they have two or more pair of wings. When Mohammed saw the archangel Jibril (Gabriel) he reported that he had six hundred pairs of wings. *See also* Angirasa; Anunaki; Apsarases; Cherub; Rishi.

Angerboda *Angerbodha, Angrboda, Angrbodha* (Norse; Teutonic)

Also known as: *Iormungandr, Jormungandr, Ljod, Midgard Serpent, Midgardsormen.*

Giant. Angerboda is a giant who lives in Utgard. She is in charge of the East wind. She is either mother or foster-mother of Loki, Fenrir the wolf, the death queen Hel and Jormungandr, who is also known as the Midgard Serpent. Under the name Ljod she became the maidservant of Freyja. Some say that she is the mate of Loki, the trickster god. *See also* Fenrir; Gullveig; Hel; Loki; Midgard.

Angerbodha (Teutonic) *see* Angerboda.

Angerona (Etruscan, Roman)

Angerona is the ancient Goddess of the Winter Solstice and sometimes called a goddess of death. She is associated with the practice of keeping the name of a god from the enemy. She may represent the silence of winter and the fragility of the ecosystem. She is shown with her mouth sealed and one finger placed on it. Her feast known as Angeronalia or the Divalia is held on December 21. *See also* Ceres.

Angervadil (Icelandic; Teutonic)

Also known as: *Angurvadel.*

Magic sword. This sword belongs to the Icelandic hero, Frithiof (also spelled Fridthjof). It blazes in time of war and shines with a dim light in times of peace. The saga of Frithiof was created in later times (approximately C.E. 1300).

Angeyja (Norse; Teutonic)

Water goddess. Angeyja is the personification of the waves. She is one of Heimdall's nine mothers (for the names of the other eight mothers, *see* Heimdall). *See also* Ran.

Angiras *Angiris* (India) *see* Agni; Brihaspati; Daksha; Kuhu; Rishi.

Angirasa (Hindu; India)

The Angirasa are descendants of the fire god Agni who are charged with protecting the sacrificial fires. These celestial bodies are deities of fire and light and may be seen as meteors. *See also* Agni; Brihaspati.

Angiris (India) *see* Angiras.

Angitia (Italian)

Also known as: *Circe* (Greek).

Goddess of healing, herbs, oration and witchcraft. *See also* Circe.

Angoi (Borneo) Creator.

Angoi gave breath to mortals, but was cut to pieces by another deity. From the god's pieces, noxious animals were created.

Angpetu Wi (Dakota People, North America)

Name of the sun.

Angra Mainyu *Angro Mainyus* ("Angry Spirit") *Anro-mainyus* (Mazdaism, Zoroastrian; Persia)

Also known as: *Agri-manios* (Greek), *Agro-manyus, Aharman* (name used in later times), *Ahriman* (Pahlavi dialect), *Ahrimanes, Drauga* (Old Persian), *Druj, Manyu.*

This wicked, evil prince of demons is the chief opponent of Ahura Mazda, the god of light. It is said that he may have been created by Ahura Mazda in a moment of doubt, or that he arose from the abyss of endless darkness. At the resurrection he will be slain by Keresaspa on Mount Damavand, or imprisoned for eternity. With his disposal, all evil will be removed from the world. Angra Mainyu created a host of demons to assist him in his quest to overcome good. Azhi Dahaka, the dragon, was created by Angra Mainyu to destroy the faithful. A great lizard was formed by him to destroy the Gaokerena Tree which grows in the cosmic ocean, Vourukasha. Other demons who fall under his command are the Drujs, who were his servants and the Daevas. His epithet, Druj, signifies Ahura Mazda as the embodiment of deception. In some renderings, Druj is said to be at his side representing the female embodiment of evil. All sorrow, pain, disease, and death are caused by Angra Mainyu. The greatest satisfaction for this "demon of all demons" is when a mortal turns away from Ahura Mazda. Angra Mainyu presides over a host of Drugas who are monstrous female fiends, Daevas, Pairikas, and the Yata. The Kavis and Karapans, who are priests of false religions, also fall under his jurisdiction. Jahi, a female fiend, roused Angra Mainyu from a long sleep and convinced him to pour poison over the body of Gaya Maretan, the first man. By doing so, Angra Mainyu created sin, misery and disease in the world. He can change his outward appearance to a lizard, snake, or a youth. When Zoroaster was born this arch

demon attempted to seduce him into evil. *See also* Aeshma; Ahi; Ahura Mazda; Asha Vahishtra; Azazel (Islamic); Azi Dahaka; Daevas; Darvands; Drujs; Gaokerena Tree; Gaya Maretan; Jahi; Keresaspa; Nasu; Pairikas; Sraosha; Vayu; Vourukasha; Yata; Zahhak; Zoroaster.

Angrboda (Teutonic) *see* Fenrir.

Angrbodha (Teutonic) *see* Angerboda.

Angro Mainyus (Persia) *see* Angra Mainyu.

Anguissance (Celtic) *see* Arawn.

Angurvadel (Teutonic) *see* Angervadil.

Angus *Aengus, Cengus, Engus, Oengus, Oenghus* (Celtic, Irish)

Also known as: *Angus Mac Og, Angus Od, Angus of the Brugh, Mac Ind Og, Mac Oc, Mac Og, Oengus of the Bruigh.*

Angus is a god of love, a patron deity of young people, the deity of youth and beauty and a shape-changer. A Tuatha De Danann, he is the son of Dagda and the river-goddess, Boann. In some myths, Dana, (Danu) is mentioned as his mother. As was the custom for royal children, he was raised by a foster parent, in his case, the god, Midir. A minor deity, his tale is one of magic, music and romance with several variations. A musician, he played a golden harp and all who heard it were enchanted and fell under his spell. In this version of his story we are told that he slept all winter and arose at spring's dawn. In a dream, the beautiful Caer Ibormeith (Caer Yewberry) appeared from the Otherworld and he instantly fell in love. Determined to make his dream a reality, he set out in search of her with the help of Bodb, king of the Sidi of Munster. Although he had the gift of eternal youth, he was sick with love and became gravely ill during his travels. Eventually he found his loved one, bound by silver chains to one hundred and forty-nine other young women, all in the images of swans. He changed himself into a swan and rescued her. Together, as they flew off to the safety of his palace in the fairy mounds, their beautiful swan song put everyone to sleep for three days and three nights. Angus' dark, obsessive side was illustrated when he abducted his brother Mider's wife Etain, kept her encased in glass and carried her with him all the time. In this vein, it is said that Angus, after being away, returned to find that his father, Dagda, had not given him a castle *(sidhe)*, as he did the other members of the Tuatha De Danann. Furious, he evicted his father from his dwelling and took it for himself. In other versions of this myth, Angus ousted Elcmhaire (Elcmar) and not his father from the castle, Brugh na Boinne and it became his residence. Elcmhaire was his mother Boann's husband. Angus was the result of an illicit affair she had with Dagda. Angus' sacred animal is the pig. He is similar to other dying gods, Adonis, Attis, Dumuzi, and Tammuz. Compare him to Mabon. *See also* Boann; Cailleach Bheur; Dagda; Dana; Etain; Mider.

Angus Mac Og (Celtic) *see* Angus; Cailleach Bheur.

Angus Od (Celtic) *see* Angus.

Angus of the Brugh (Celtic, Irish) *see* Angus.

Angusta (Eskimo) *see* Anguta.

Anguta (Eskimo)

Also known as: *Angusta.*

Anguta is called the shadowy father of the sea-goddess Sedna. In myth he cut off her fingers when she ran from the sea-birds. *See also* Sedna.

Anhefta (Egypt)

Anhefta is the protective spirit who guards one end of the corridor in the Ninth Sector of Tuat. Ermen-ta guards the other end. *See also* Ab-ta; Tuat.

Anher (Egypt) *see* Anhur.

Anhert (Egypt) *see* Anhur.

Anhir (Egypt) *see* Anhur.

Anhoret (Egypt) *see* Anhur.

Anhorte (Egypt) *see* Anhur.

Anhur *Anher, An-her, Anhert, Anhir, An-hur* (Egypt)

Also known as: *Anhur-Shu, Anhoret, Anouris, Onouris* (Greek), *Onuris, Theb-ka* (as God of the Underworld).

Sky god. God of the dead. God of war. Anhur is the son of Hathor in her form of Her-t. His wife was the lion-headed goddess Mehit. As a solar deity he was worshiped at Abydos. In the metropolitan area of Heliopolis he was often associated with Shu (a local god) and called Anhur-Shu; his consort was Tefnut. Anhur was also known as the divine huntsman of This in Upper Egypt. He stands in the prow of the sun god Ra's boat as "Slayer of the Enemies." Anhur is shown as a warrior wearing a headdress with four plumes. He wears a long embroidered robe and carries a spear. Sometimes he holds a cord leading the sun. The Greeks identified Anhur with Ares. In the Christian era, he was identified with St. George. *See also* Ares; Hathor.

Anhur-Shu (Egypt) *see* Anhur.

Ani (Egypt)

His residence is in Tuat (the underworld). He is possibly a lord of festivals and the new moon. Ani is mentioned in one of the ancient hymns in relationship to Amen-Ra. *See also* Amen-Ra; Tuat.

Anila (India) *see* Vasus.

Animiki (Ojibway People, North America)

He is the god of thunder and the creator of the west wind.

Aningan (Eskimo) *see* Alignak; Idlirvirissong.

Anioch (Greek)

Also known as: Eniocha.

It was either Anioch or Eurydice who was married to king Creon of Thebes. Anioch is the mother of Enioche, Haemon, Megara, Menoeceus and Pyrrha. *See also* Eurydice (C); Megara; Pyrrha.

Aniran (Persia) *see* Khshasthra Vairya.

Aniruddha (India) *see* Bana; Kama (A); Krishna; Pradyuma.

Anit (Egypt) A goddess of one of the cities of ancient Egypt.

Anith (Celtic) *see* Eire.

www.ebook3000.com

Anitsutsa (Cherokee People, North America) The Pleiades.

Anjama (India) *see* Dikpalas.

Anjana (India) *see* Lokapalas.

Anjea (Australia)
Creator. She forms babies from mud and places them in the womb of women.

Ank (Egypt) *see* Ankh.

Ankamma (India)
She is one of the Mutyalamma goddesses who are deities of the household. She is the goddess of cholera or sometimes as disease in general. *See also* Mutyalamma.

Ankh (A) (Egypt)
Also known as: *Ank.*
Emblem. The ankh is the symbol of "life." It is a T-shaped figure with a loop on top. The name is similar to the Ankus which is the scepter of Indra and is also an elephant goad.

Ankh (B) (Egypt)
Also known as: *Anukis* (Greek), *Khnum.*
Ankh is another name for Khnum as a creator. *See also* Anuket, Khnum.

Ankhat (Egypt) *see* Isis.

Ankhi (Egypt)
A monster serpent with a bearded mummiform god growing out from each side of its body.

Ankt (Egypt) *see* Anouke.

Ankusha (India)
Also known as: *Chak-yu-ma* (Tibet)
This tiger-headed goddess is a Shakti. With her consort Vijaya, she is the Door-keeper of the East. On the Sixth Day in the Bardo World, she is found with three other female goddesses: Kinkini-Dhari, Pashadhari, and Vajra-shringkhala. There are also four male Door-keepers: Amritahari, Hayagriva, Vijaya, and Yamantaka. *See also* Amrtakundali; Hayagriva; Kinkini-Dhari; Shakti; Vijaya; Yamantaka.

Anna-Nin (Middle East) *see* Anat; Nana.

Anna Perenna (Roman) *see* Ana-Purna.

Anna-Perenna (India) *see* Ana-Purna.

Annancy (Africa) *see* Ananse.

Annapurna (India) *see* Ana-purna.

Annar (Teutonic) A dwarf. *See also* Anar; Dwarfs.

Annfwn (Celtic) *see* Achren.

Anningan (Eskimo) *see* Alignak.

Annis (A) (Celtic) *see* Ked.

Annis (B) (Sumer) *see* Inanna.

Annun (Celtic) *see* Annfwn.

Annunaki (Sumer) *see* Anunnaki.

Annuthat (Middle East) *see* Anat.

Annwn (Celtic)
Also known as: *Annfwn.*
This is the home of the dead, ruled by Arawn. Annwn is a beautiful paradise island that permeates serenity. In later legends Arthur sailed with a large crew to raid Annwn and carry off a magic cauldron. *See also* Achren; Arawn; Pwyll.

Annwvyn (Celtic) *see* Achren, Pwyll.

Anobret (Greek) *see* Cronus.

Anoi-Diggan-Juje (Dhammai People, India)
Anoi-Diggan-Juje and Abugupham-Bumo were the first mortals. Their parents are the brother and sister frogs, Lujjuphu and Jassuju. *See also* Shuznaghu.

Anonach (Celtic) *see* Eire.

Anos (Mesopotamia) *see* Anu (A); Anu (B).

Anouke (Egypt)
Also known as: *Ankt.*
Goddess of War. Anouke is a member of a Nubian triad. She wears a curved feathered crown, and carries a spear. Anouke may be the same as Anta or Anath who is an Egyptian deity originating from the Asiatic people.

Anouris *see* Anhur.

Anpao (Dakota People, North America)
A Janus-like two-faced being.

Anpu (Egypt) *see* Anubis.

Anquat (Egypt) *see* Isis.

Anquet *Anuket* (Egypt)
"Giver of Life." With Khnum and Satis this goddess is one of the Elephantine Triad. *See also* Anukis; Isis; Khnum.

Anrita (India)
She is the wife of Adharma and mother of Maya. *See also* Maya (C).

Anro-mainyus (Persia) *see* Angra Mainyu.

Ansa (India) *see* Adityas; Mitra; Varuna.

Anshar *Anshur, Ashur, Asshur* (Assyro-Babylonia, Sumer)
Also known as: *Assorors, Shar.*
God of Sky and Heavens. Warrior god. Anshar and his sister-wife Kishar are the offspring of Lakhame and Lakhumu. They in turn produced the gods Anu, Anatu, and Ea. Some say they are also parents of Enlil. Anshar and Kishar were the grandparents of Marduk. Anshar is the progenitor of the Babylonian pantheon. He was victorious over the Dragon of Chaos during the great work of Creation. Sometimes his principal consort was the goddess Ninlil. As Ashur, he is the head of the Assyrian pantheon. He is shown as a winged disk, or mounted on a bull. Sometimes he is depicted floating in the air. Anshar is similar to Apsu. He might be the same as the Greek Assoros and Kissare. Anshar is associated with Ea in the legend of Tiamat. *See also* Apsu; Anu (B); Ea; Enlil; Igigi; Lahamu and Lahmu; Marduk; Ninlil; Tiamat.

Anshashpands (Persia) *see* Amesha Spentas.

Anshumat (India) *see* Sagara.

Anshur (Sumer) *see* Anshar; Ashur.

Ansuman (India)
This god keeps vital organs functioning properly. *See also* Surya.

Anta (Asia Minor) *see* Anahita.

Antaeus (Greek)
God of Darkness. Antaeus, a Libyan giant, is the son of Gaea (the Earth) and the sea god Poseidon, or perhaps Gaea and the blood of the castrated Uranus. His sister, Charybdis, guarded the straits of Messina with Scylla. His brother Ogyges, was a king of Athens who married Thebe, the daughter of Zeus. A wrestler, Antaeus would challenge all strangers visiting his kingdom. Occasionally he was thrown, but when his feet touched earth he was immediately revitalized and became even stronger. The roof of the temple he had built in Poseidon's honor was adorned with the skulls of his former opponents. When Heracles discovered that the earth was the source of his strength, he lifted him above the ground and gave him a bear hug that killed him. Tinga, the widow of Antaeus, became the mother of Sophax, by Heracles. Compare Antaeus to Alcyoneus. For siblings names, see Giants. *See also* Charybdis; Gaea; Poseidon; Scylla.

Antaf (Egypt) *see* Akeneh; Apepi.

Antaka (India) "He Who Ends Life." *See also* Yama.

Antanzah (Mesopotamia) *see* Anu.

Antares (Persia) *see* Hapto-iringa.

Antariksha (Vedic; India)
The atmosphere where gods and demons struggle for supremacy. *See also* Prithiva.

Antauges (Greek) *see* Dionysus.

Antea (Greek) Another name for Stheneboea (q.v.).

Antenor (Greek)
Antenor was a Trojan prophet and advisor. His spouse is Theano who was one of Athena's priestesses. His sons are Acamas, one of the leaders of the Trojan War, who was killed in the war; Agenor, a Trojan hero; Archelous, a leader in the Trojan War; Coon, who was killed by Agamemnon in the Trojan War; *Demoleon*, who was also killed in the Trojan War; Glaucus, who was also killed by Agamemnon in the Trojan War; Helicaon, wounded in the Trojan War; Iphidamas, also killed by Agamemnon in the Trojan War; Laocoon; Laodamas; Lycaon, also wounded in the Trojan War; Pedaeus, who was Antenor's son by another woman; Polybus; Polydamas, accused of being a traitor. Antenor has one daughter, Crino. The idea for Odysseus to steal the Palladium came from Antenor. It was also Antenor's idea to built the Wooden Horse. *See also* Acamas (B); Agenor; Archelous; Palladium; Polydamas.

Antero Vipunen *Antero Wipunen* (Finnish)
Deity of Wisdom. Wainamoinen received the three lost words of magic from this giant by entering his body and working magic.

Antero Wipunen (Finnish) *see* Antero Vipunen.

Anteros (Greek)
God of Passion. God of mutual love. God of tenderness. Avenger of unrequited love. Anteros is the son of Ares and Aphrodite. (In some versions of his legend, he is said to be the son of Aphrodite and her husband, the fire god, Hephaistos.) His twin brother and adversary is Eros, the god of love. His other siblings are Phobos, the god of panic; Pallor, the god of terror; Deimos, sometimes known as the god of dread; Enyo, goddess of war; Harmonia (Hermoine), goddess of harmony. His brother, the beautiful god of love, Eros received most of the attention. Anteros is mentioned as his attendant. *See also* Aphrodite; Ares; Eros; Harmonia (A); Hephaistos.

Antetu (Egypt) Another name for Sekhem or possibly Ra.

Antevorta (Roman)
Goddess of Prophecy. The Future. She is the sister of Postverta (at one time they were one goddess), the goddess of the past. *See also* Postverta.

Anthat (Asia Minor)
Also known as: *Anta.*
Mother goddess. She is possibly a horse deity or a goddess of battle. Little else is known. She is sometimes shown in battle garments. *See also* Anat.

Antheia (Greek)
Antheia was Hera's name when she was an adolescent. *See also* Hera.

Antheti (Egypt) *see* Aai.

Antheus (Greek) *see* Dionysus.

Anthios (Greek) *see* Dionysus.

Anti (Egypt)
God of the Ferrymen. Anti is the ferryman who brought Isis across to the island where Seth had isolated himself. *See also* Isis; Seth.

Anticleia (A) *Antikleia* (Greek)
Dawn goddess. Anticleia is the daughter of the thief Autolycus and Amphithea. She was seduced by the cunning Sisyphus and became pregnant. In some renditions she was married to Laertes, the king of Ithaca, at the time and in others Sisyphus arranged the marriage upon learning about her pregnancy. The father of the child, Odysseus, could have been either man. Anticleia adored her son and when she thought that he had been killed at Troy she died of grief or killed herself. Anticleia is often identified with dawn's light or evening light. She is also associated with Odysseus in his visit to hell. *See also* Autolycus; Odysseus; Sisyphus.

Anticleia (B) (Greek)
Also known as: *Philinoe*
She is the daughter of Iobates (also known as Amphianax) the king of Lycia. Her sister is Stheneboea (q.v.). *See also* Bellerophon; Iobates.

www.ebook3000.com

Anticleia (C) (Greek)
She is the wife of the surgeon Machaon, the co-ruler of parts of Thessaly, who was one of Helen's suitors. *See* Machaon.

Anticleia (D) (Greek)
She is the mother of Periphetes, by Poseidon or Hephaestus.

Antigone (A) (Greek)
Dawn goddess. Antigone is the daughter of Oedipus and Jocasta or possibly Euryganeia. She is the sister of Eteocles, Ismene and Polynices. When her blind father Oedipus was exiled by the Thebans, Creon and his own sons, Polynices and Eteocles, Antigone guided and cared for him. His sons stayed behind, squabbled over the throne and finally killed one another in the war of Seven Against Thebes. The disgraced father and his loving daughter finally found solace in Colonus, near Athens. On his deathbed, the king of Athens, Theseus restored honor to the old man. Before her father's death, Antigone was abducted by Creon, who wanted to capture the old man. Theseus rescued her. When she heard of her brothers' deaths she defied an order by Creon and administered rites to Polynices. Enraged, Creon punished her by incarcerating her in a cave or burying her alive in her brother's grave. She committed suicide or was killed by Haemon, Creon's youngest son. It has also been said that when Haemon found her dead, he killed himself. In a different rendition, Hyginus wrote that Haemon aided her escape from his father Creon. They had a son together, who in later years, traveled to Thebes. The young man was recognized by his grandfather Creon, who identified him by a family birthmark. The bitter man would not forgive his son Haemon for defying his orders. Haemon then murdered Antigone and killed himself. *See also* Actor; Anticleia; Oedipus.

Antigone (B) (Greek)
She is the daughter of Laomedon and the sister of Priam. Hera turned her into a stork for comparing her own beauty to Hera's. *See also* Hera; Priam.

Antigone (C) (Greek)
She is the daughter of Pheres and mother of the Argonaut Asterion. Her husband Cometes committed adultery with Aegialeia, Diomedes' wife. *See also* Aegialeia; Pheres.

Antigone (D) (Greek)
She is the daughter of Eurytion the Argonaut and king of Ohthia who was accidentally killed by Peleus. She married Peleus and became the mother of Polydora. When Peleus deserted her, she committed suicide. *See also* Peleus; Polydora.

Antikleia (Greek) *see* Anticleia.

Antilochus (Greek)
He is the eldest son of the wise, brave Nestor, the king of Pylos, and Anaxibia or possibly Eurydice. His siblings are Aretus, Echephron, Paeon (he is possibly the son and not the brother of Antilochus), Peisidice, Peisistratus, Perseus, Polycaste, Stratius and Thrasymedes. He was one of Helen's suitors and fought in the Trojan War. He died while defending his father Memnon and was buried in the same grave as his dear friend Achilles and Patroclus. *See also* Achilles; Memnon; Patroclus; Perseus.

Antimache (Greek) *see* Admete.

Antimachus (A) (Greek)
A Trojan, he is the father of Hippolochus, Hippomachus and Peisander.

Antimachus (B) (Greek)
His parents are Heracles and one of the fifty daughters of Thespius.

Antion (Greek)
Antion is associated with Perimele and is possibly the father of Ixion (q.v.).

Antiope (A) (Greek)
Also known as: *Hippolyta, Melanippe.*

Queen of the Amazons. Antiope is the daughter of the god of war, Ares, and the Queen of the Amazons, Otrera. She is the sister of Hippolyte. A warrior, Antiope had a child named Hippolytus by the hero, Theseus. It is debatable if Antiope fell in love with Theseus and left her territory willingly or was kidnapped by this adventurer. He did campaign against the Amazons, with the assistance of Peirithous, the king of Lapith, and possibly Heracles and left with the Amazon queen, variously called Antiope, Melanippe or Hippolyta. The Amazons, led by Antiope's sister Hippolyte, descended on Athens in retaliation and a fierce battle ensued. Many of the Amazons were slaughtered and it is said that Hippolyte died of a broken heart. After the birth of her son, Hippolytus, Antiope also died. There is the possibility that Theseus, generally known as a just person and defender of the oppressed killed her when she opposed his marriage to Phaedra, the daughter of Minos. *See also* Amazons; Ares; Arne; Minos; Phaedra; Theseus.

Antiope (B) (Greek)
Lover of Zeus. She is the daughter of the river god Asopus and Metope, or Nyceteus and Polyxo. Antiope is the mother of the twins Amphion and Zethus. Zeus, who lusted after the beautiful young woman, came to her disguised as a satyr and impregnated her. Fearful of her father's wrath, she escaped from Thebes to Sicyon were she married King Epopeus, the son of Poseidon and Canace. Her father pursued her, intending to vent his wrath on her husband and either killed him or found him dead. In some renditions, Epopeus committed suicide when he found out that Antiope was pregnant by Zeus. Asopus died as well, either from a wound suffered in the encounter with Epopeus or from the humiliation of his daughter's pregnancy. With his last breath he begged his brother Lycus to punish Antiope. On the way back to Thebes with Lycus, she gave birth to twins, Amphion and Zethus. Her uncle made her abandon the babies and he dragged her home. Once there she was imprisoned and treated cruelly by Lycus' wife, Dirce. Years passed, Antiope managed to escape and was reunited with her sons. Outraged when they heard how their birth mother had been treated they went after Dirce and Lycus. Lycus was either murdered or driven from the throne and Dirce was tied to a bull and dragged to her death. In a variation of the theme; Dirce was punished with insanity by the god Dionysus. She wandered around Greece until she met Phocus, who cured and married her. Not to be confused with Antiope, also known as Hippolyta, the wife of Theseus. To compare to other women who were seduced by Zeus in different forms, *see* Aegina; Danae; Europa; Leda. *See also* Amphion; Zethus.

Antiope (C) (Greek) *see* Muses.

Antiope (D) (Greek)
She is the wife of Eurytus and the mother of Clytius, Iole and Iphitus. When Eurytus refused to give her to Heracles, he was killed.

Antiphates (Greek) *see* Abas (B).

Antit (Middle East) *see* Anat.

Antiu and Hentiu (Egypt)
Assistants and protectors. The Antiu are four beings, each having four serpent heads, and armed with knives and ropes, on the right hand of Ra's sun boat. They are found in the Tenth Division of Tuat. *See also* Tuat.

Antu (Assyro-Babylonian)
Also known as: *Antum.*

Antu was the first consort of the sky god, Anu. Their offspring are the underworld gods, the Anunnaki and the seven evil demons, the Utukki. She was replaced by Anu's second consort, Ishtar (Inanna), who is sometimes called her daughter. *See also* Anat; Anu; Anunnaki; Enlil; Utukki.

Antum (Assyro-Babylonian) Another spelling for Antu.

Anu (A) (Celtic)
Also known as: *Ana, Black Annis, Buan-Ann, Dana, Danu, Don, Nanu.*

Mother of gods. Goddess of fertility. Wind goddess (possibly). Culture hero. Anu is an ancestor of the Tuatha De Danann. She is said by some to be the daughter of Dagda. In another myth she is known as the sister of King Math, the spouse of the powerful Irish lord of life and death, Bile, and the mother of Amathaon, Arianrhod, and Gwydion. She is sometimes confused with Danu as part of a triple concept of one deity. "The Paps of Anu" in Co. Kerry were named after Anu. She is also known as Don, the spouse of Beli (the British name for Bile). In the Dane Hills of Leicestershire, where she was known as Black Annis, she was offered human sacrifices. Compare Anu to Aine. *See also* Amathaon; Arianrhod; Bile; Brigit; Dana; Tuatha De Danann.

Anu (B) (Akkadian, Babylonian, Hittite, Hurrian, Sumerian, Syrian)
Also known as: *An* (Sumer), *Ana* (Sumer), *Anos, Anum* (God of Storms, Wind and Waves).

"Heaven." In Mesopotamian mythology, Anu, lord of the firmament, is considered the source of order and the divine king of the natural and supernatural worlds. In Babylonian mythology, Anu the sky god is the son of Anshar and Kishar. He is the father of Ea or others say Ea's father is Anshar.

Anu's first consort was Antu by whom he became the father of the underworld gods known as the Anunnaki and the seven evil demons known as the Utukki. His second consort was Innini (Ishtar). The star spirits and the demons of darkness, rain and cold were created by Anu. His shooting stars, known as kishrus, have great strength. Anu is the chief of a triad with Ea and Enlil. In Hurrian-Hittite mythology, tales are told of Anu, Ea and Enlil and the conflict between the older and younger gods. This triad has been credited with teaching divination by pouring oil on water. It is said that Anu created the heavens, and Ea created the dry land. When he was castrated by Kumbaris, Anu announced to his gleeful foe that in turn he had impregnated Kumbaris with three fearful gods; Atanzah, Teshub and Tigris. Anu has little to do with mortals, although in some instances he is called on to cure illnesses. One of his primary functions is to act as arbiter of the disputes of the gods. His power and authority are wielded with the aid of his creation, the stars, which are his troops, and whose place it is to punish the wicked. Other gods were later identified with him and took on the name Anu. The goddesses Ninkarrak and Gula are both thought to be daughters of Anu, as is Ishtar, who is also known as his second consort. Some of the demons of disease are said to be the offspring of Anu and Enlil. Anu's throne is in Atrahasis, the third or highest heaven. This is where he keeps the Bread and Water of Life (food of immortality). The gate to his heaven is guarded by Tammuz and Nigishzida. From a piece of clay, Anu created the brick god Kulla. Numbers played an important role in Babylonian society. Every proper name could be written in numbers. Anu, the father of the gods, had the perfect number sixty (60). He is shown as a tiara or turban placed on a throne. Anu is the counterpart of the god An of the Sumerians (q.v.). He is associated with Adapa and Marduk. Anu's son, Enlil, was originally the leader of the pantheon. Anu later took over that position. *See also* Adapa; An; Anath; Anshar; Anunnaki; Anus; Apsu; Damkina; Ea; Enki; Enkidu; Enlil; Gula; Igigi; Ishtar; Kishar; Kulla; Kumbaris; Mirsu; Ninkarrak; Nusku; Tammuz; Tigris; Utukki.

Anubis (Egypt)
Also known as: *An-pu, Anpu, Am Ut, Hermanubis* (Greek), *Khent Sehet, Mercury* (Roman), *Sekhem Em Pet, Tep-tu-f.*

Underworld deity. Early god of the dead. God of the cemetery. Guardian God. God of the soul through the Land of the Shades. Director of embalming. Anubis, known as the jackal-headed god, may be the son of Osiris, Set or Ra and Nephthys or Isis. One myth states that he was abandoned by his mother and raised by Isis. In the Pyramid Texts, he is known as the fourth son of Ra, and his daughter is Kebehut. As the son of Osiris and Nephthys he is said to have swallowed his father (this myth alludes to the night swallowing day). He is the judge and protector of the dead, and possibly the messenger of Osiris. Some say he was replaced by Osiris. He was also the protector of tombs and one of the eight early Egyptian gods. He is the dog or jackal-headed god of funerals and mummification. He is in charge of the scales that weigh the hearts of the dead against the Feather of Truth in the Hall of Judgment before Osiris and the forty-two gods. His duty is to cast the dead to the Eaters of Souls if the heart is not in balance. Anubis accompanies Osiris during the Second Hour of the Night. He is also the guardian of Khersek-Shu, the door which the deceased enter (see Tuat or Shesat Maket Neb-S). Anubis is the Greek rendering of the Egyptian name Anpu. As Anpu he is the god of the nomes of Anpu and Sep. It is suggested that Anubis was originally a jackal who became a god because he devoured corpses. An image of a reclining black jackal is depicted on the doors of numerous rock tombs. He is represented as a bushy tailed black jackal, or a black skinned man with the head of a dog, or with a human body and the head of a jackal. The antelope is sacred to Anubis. The sharp eyesight of this animal deemed it prophetic. As

www.ebook3000.com

conductor of the souls, he was also given the name Hermanubis by the Greeks. The Romans identified him with Mercury. *See also* Amit; Ap-uat; Hermes; Horus; Osiris.

Anuket (Egypt) *see* Anukis.

Anukis *Anqet, Anquet, Anuket, Anukisuas, Anukit* (Egypt, Greek, Sudan; possibly introduced from Ethiopia)
Anukis is the Greek rendering of the name Anuket. She is the second wife of the god Khnum and the mother of Satis. She was charged with controlling the the narrow course of the upper Nile and the Cataracts. She is one of the Triad of Elephantine with Khnum and Satis. Her principal place of worship was in Nubia. She is depicted as a woman wearing a crown of feathers, usually found with a red parrot, or as a woman holding a tall papyrus scepter and wearing a high crown of feathers. Her sacred animal is the gazelle. *See also* Khnum; Satis

Anukit *see* Anukis.

Anulap (Island of Truk, Micronesia)
Possibly a creator. Husband of the creator Ligoububfanu. Teacher of magic and knowledge. *See also* Ligobund.

Anum (Mesopotamia) *see* Anu (B).

Anumati (India)
The moon worshiped as a goddess during the latter half of the lunar cycle immediately before becoming full.

Anunaki (Sumer) *see* Anunnaki.

Anungite (Pawnee People, North America)
The abode of spiritual power.

Anunit (Assyria, Babylon, Sumer)
Also known as: *Anunitum.*
Moon goddess. She is known variously as the daughter of Baal, Samas or Sin. Sometimes she is known as the sister of Samas and the wife of Sin. Anunit is the mistress of battle, the bearer of the bow and quiver. Her symbol of the sun with eight rays is similar to that of the goddess Ishtar (q.v.).

Anunitum (Babylon)
An early goddess worshiped at Sippar. She later merged with Ishtar (q.v.).

Anunnaki *Annunaki, Anunaki, Ennuki* (Assyro-Babylonia, Sumer)
Assembly of high gods representing the Sumerian pantheon. Presided over by An and Enlil, the Anunnaki is composed of Anu, Ea and the Igigi who are the children of Anshar and Kishar. (Some say the Anunnaki were created by Marduk and others say the Anunnaki were created by Anu.) The Assyrians and Babylonians believed that the Anunnaki were the three hundred gods of the lower of the three heavens. It is also said by some that the Anunnaki created Babylon, Eridu and Esagilla from the sea. When the Anunnaki decided to destroy humankind with a great flood, one of the gods informed Ziusudra, King of Shurappak, of the decision. He built an ark in which the seeds of the mortals were preserved during the seven days and seven nights the waters raged. After surviving the deluge, he was accepted as a deity and put in charge of the country of Dilmun. The Anunnaki lived in or below Arallu, the place of the dead. Their palace is known as Diligina or Ekalgina. Anunnaki corresponds to the Igigi who were gods of the middle or upper heaven. As the offspring of Anu and Antu, the Anunnaki are the siblings of the seven evil demons known as the Utukki. *See also* Anat; Anu; Apsu; Arallu; Dilmun; Igigi; Utukki.

Anunu (Egypt) *see* Neith; Net.

Anup (Egypt) *see* Anubis.

Anus (Hittite, Hurrite)
Alulus, the sky god, was king of heaven for nine years before his son Anus ousted him. Anus ruled for nine years, then he in turn was overcome by his son Kumarbis. Kumarbis swallowed his father's testicles. Anus cursed him and fled to Heaven, where he hid. Anus is comparable to the Akkadian Anu (q.v.). *See also* Alulus; Kumarbis; Ullikummis.

Anush (Armenian)
The first queen of Azdahak. Mother of dragons.

Anzety (Egypt)
He was a local god of the town of Busiris, who preceded Osiris. Later his attributes were incorporated into those of Osiris. Anzety was depicted by a human head on a pole. His arms hold the crook and the flail. *See also* Osiris.

Anzu (Persian, Sumerian) *see* Zu.

Ao (A) (Polynesia, New Zealand)
First element. Ao represents light and the opposite of Po, the primeval darkness. Ao is also considered the first ancestor of the Maori People. *See also* Aos; Po; Tangaloa.

Ao (B) (China)
In Chinese cosmology, Ao is a fish or a monster. *See also* Dragon Kings.

Ao Ch'in *Ao K'in* (China) *see* Dragon Kings.

Ao-Jun (China) *see* Dragon Kings.

Ao-Kahiwahiwa (Polynesia) *see* Tawhiri-ma-tane.

Ao-Kanapanapa (Polynesia)
"Glowing Red Clouds." One of the children of the god of winds, storms and hurricanes, Tawhiri-ma-tea.

Ao Kuang (China) *see* Dragon Kings.

Ao-Marama (Polynesia)
This light deity is one of Po's children. *See also* Ao.

Ao-Nui (Polynesia)
"Dense Clouds." One of the thirteen children of the god of turbulent weather, Tawhiri-ma-tea.

Ao-Pakakina (Polynesia) *see* Tawhiri-ma-tea.

Ao-Pakarea (Polynesia)
"Wildly Drifting Clouds." *See also* Tawhiri-ma-tea.

Ao-Potango (Polynesia)
"Dark Heavy Clouds." *See also* Tawhiri-ma-tea.

Ao-Pouri (New Zealand, Polynesia)
Also known as: *Po.*
World of darkness. When Rangi the sky lay in union on Papa the earth, in the beginning, all the gods were held under their

bodies. This was the darkness called Ao-pouri. The gods involved in the separation of Rangi and Papa are Tu-matauenga, Tane-mahuta, Tawhiri-ma-tea, Rongo-ma-tane, Tangaroa, and Haumia-tikitiki. *See also* Papa; Po; Rangi; Tangaroa.

Ao-Roa (Polynesia) *see* Tawhiri-ma-tea.

Ao Shun (China) *see* Dragon Kings.

Ao-Toto (Polynesia)
An ancestor of Tawhiri, Ao-Toto is either a god or an early culture hero. *See also* Tawhiri-ma-tea.

Ao-Whekere (Polynesia) *see* Tawhiri-ma-tea.

Ao-Whetuma (Polynesia) "Fiery Clouds." *See also* Tawhiri-ma-tea.

Aobh (Celtic) *see* Aebh; Aed.

Aoi (Coptic)
This was a god that Jesus prayed to. *See also* Pistis Sophia.

Aoide (Greek)
She is the Boeotian muse of song. Her sisters are Melete, the muse of practice, and Mneme, the muse of memory.

Aoife (Irish)
Also known as: *Aeife, Aife.*

Aoife was a warrior woman who resided in Scotland. She was a rival of Scathach the Amazon queen who is the eponymous goddess of Skye. Aoife was defeated in battle by CuChulainn, the mortal son of the deity Lugh. A peace treaty was drawn up with a provision that Aoife would bear CuChulainn's son. She abided by the agreement. When she heard that CuChulainn had mated with Emer, she decided to get even. She raised her son Conlaoch to excel in every skill. She also instructed him never to refuse a challenge, never to back down from anyone and never to reveal his name. The last dictate cost him his life, for he was killed by his father, CuChulainn, who did not know his identity. In another version,Aoife began life as the adopted daughter of Bodb Dearg. She replaced her sister Aebh as the mate of Ler and became the step-mother to Aed, Conn, Fiachra and Fionnuala. Extreme jealousy of the children caused her to turn them into swans. She designated that they would roam the world for nine hundred years. Boadh Dearg in turn changed Aeife into a witch of the air and assigned her the duty of sweeping the wind forever. *See also* Bodb Dearg; Manannan Mac Llyr.

Aokeu (Polynesia)
Also known as: *Aokeu and Ake.*

Probably a sky or flood deity. He and the sea god, Ake, quarrelled about who was the greatest and most powerful. To prove himself Ake caused the sea to rise dramatically while Aokeu poured rain down on the land. The resulting flood destroyed all but Rangi (a mortal in this case) who prayed to Rongo. Rongo brought things back to normal. *See also* Rangi; Rongo.

Aokeu and Ake (Polynesia) *see* Aokeu.

Aos (Chalean, Greek, Sumerian)
Also known as: *Aa, Hoa, Oannes.*

God of light. Some say that Aos is the Greek rendering of the god Ea. The Assoros and Kissare descended from Aos. *See also* Aa; Aah.

Ap (Egypt) *see* Aani; Apepi; Apophis; Utennu.

Ap-Taui (Egypt)
Attendant deity. Ap-taui is one of the gods responsible for administering to Ra in the Eleventh Hour (Section) of Tuat. Five of the gods are armless, and from the neck of one, juts two serpents' heads. Ra's breath gives them life. Their souls live on the sun god's hidden light and their soul food comes from provisions stored in his sun boat. The other attendants' names are Aaiu-f-em-kha-nef, Aunaauif, Hepa, Khnem-renit, Maa, Merenaaui-f, Meskhti, Nerta, Rest-f, Tua-Heru.

Ap-Uat (Egypt)
Also known as: *Ophois, Ophois Wepwawet, Sekhem Taui, Upuaut, Upwuat, Wepwawet.*

Ap-uat, one of the principal gods mentioned in the Pyramid Texts, is often referred to as Wepwawet in mythology and is often been confused with Anubis, who is his brother. A wolf or jackal-headed god, Ap-uat is mentioned as "The Opener of the Ways," in the First Section (Hour), of the night (which is an ante-chamber of Tuat). Ap-uat rides on the bow of Ra's boat acting as a guide, and a protector. He is also mentioned in connection with the god of the Nile, Hapi, in the text of the *Unas*, where they are commanded to raise the waters of the great river so that grain could be grown for the king to eat on his journey to the Underworld, and for his future home in the Elysian Field. He was specifically "The Opener of the Ways" to the south, while Anubis was responsible for the northern ways. He is a friend and companion of Osiris. Ap-uat, the oldest-known god worshipped in Abydos (Aabdju) was deposed by Khenty-amentiu. At Asyut or Siut, he was a cemetery god. The standards of Ap-uat and Anubis were the same: a human head wearing a white crown which projects from the back of a lizard. Ap-uat, wolf or jackal-headed, is depicted with a grey or white head, often standing, dressed in a soldier's uniform. *See also* Anubis; Elysian Field; Khenty-amentiu; Tuat.

Apa (India) *see* Vasus.

Apam Napat (Indo-Iranian; Hindu)
Known as "Grandson of Waters," he is the son of Vourukasha, the cosmic sea, who was born on a cloud, and became the lover of Anahita. Apam Napat represents lightning and is identified with the Hindu fire god Agni (q.v.). He is the purifier of the seed of the earth and in the animal kingdom. *See also* Anahita; Vourukasha (A).

Apaosha (Zoroastrian; Persia)
Draught demon. *See also* Ahriman; Tishtrya.

Apap *see* Apophis.

Aparna (India) *see* Shiva.

Apason (Assyro-Babylonia) *see* Apsu; Belus (B).

Ape (Egypt)
Also known as: *Hedj-wer.*

This baboon god, called the "Great White One" during the Archaic Period was regarded as a form of Thoth during the Pyramid Age. His duty is to keep watch over Thoth. Thoth is

www.ebook3000.com

About the Author

Mantak Chia

Master Mantak Chia is the creator of the Universal Tao System and is the director of the Universal Tao Center and Tao Garden Health Resort and Training Center in the beautiful northern countryside of Thailand. Since childhood he has been studying the Taoist approach to life. His mastery of this ancient knowledge, enhanced by his study of other disciplines, has resulted in the development of the Universal Tao System which is now being taught throughout the world.

Mantak Chia was born in Thailand to Chinese parents in 1944. When he was six years old, Buddhist monks taught him how to sit and “still the mind.” While still a grammar school student, he learned traditional Thai boxing. He was then taught Tai Chi Chuan by Master Lu, who soon introduced him to Aikido, Yoga and broader levels of Tai Chi.

depicted with the ape god sitting on the back of his head or shoulders. *See also* Thoth.

Apep (Egypt) *see* Aai.

Apepi (Egypt)
Also known as: *Aaapef, Ap, Apap, Apep, Apophis, Pepi.*

Deity of darkness. Ruler of the underworld. Enemy of the sun. Apepi is the fiery, serpent-devil of mist, darkness, night and storms. In order to destroy him, it was necessary to curse him by every name he was known: Am, Aman, Amen, Beteshu, Hau-hra, Hemhemti, Hem-taiu, Iubani, Iubau, Karau-anememti, Kenememti, Khak-ab, Khan-ru, Khermuti, Khesef-hra, Nai, Nesht, Qerneru, Qettu, Saatet-ta, Sau, Sebv-ent-seba, Sekhem-hra, Serem-taui, Sheta, Tetu, Turrupa, Uai, and Unti. The priests of Amen-Ra burned wax figures of Apep who daily endeavored to prevent the sun from rising. There are other feared serpents mentioned by the ancient Egyptians. They are Akeneh, Amen, Antaf, Hau, Heka, Hekret, Hemth, Senenahemthet, Setcheh, Tcheser-tep, and Thethu. Although some have the same names as gods, they are different entities entirely. One serpent named Ami-Hemf who lived on the top of Bakhau, the Mountain of Sunrise, is described as being fifty feet long. Apepi could be associated with Rahabh (Hebrew). Compare Apepi to Tiamat. *See also* Aai, Ab-esh-imy- duat; Ab-ta; Abuk; Aken; Akeneha; Apophis, Gehenna (Hebrew underworld); Hades (Greek); Tuat.

Aper-ta (Egypt)
Another name for Sekhem and possibly Ra. *See also* Aai.

Apet *Epet* (Egypt) *see* Taueret.

Aphangak (Brazil, Peru; South America)
A class of demon. *See also* Kilyikhama.

Aphareus (Greek) *see* Gorgophone.

Apheliotes (Greek) *see* Boreas; Eurus.

Aphrodite (Greek, possibly of Phoenician origins)
Also known as: *Acidalia* (surname); *Acraea* (surname), *Alilat, Alitta, Amathusia* (surname), *Ambologera* (surname), *Anadyomene* (surname; Rising from the Sea), *Androphonos* (Man-slayer), *Antheia* (surname), *Apaturia* (surname), *Aphacitis* (surname), *Aphrodite Genetrix, Aphrodite Nymphia, Aphrodite Pandemos, Aphrodite Porne, Aphrodite Urania, Apotrophia, Aracynthias* (surname), *Areia* (surname), *Argennis* (surname), *Callipygos* (surname), *Cnidia* (surname), *Colias* (surname), *Ctesylla* (surname), *Cypria* (surname), *Cythera* (surname), *Delia* (surname), *Despoena* (surname), *Dionaea* (surname), *Epidaetia* (surname), *Epitragia* (surname), *Epitymbria* (Of the Tombs), *Erycina* (Roman; surname), *Euplios* (fair voyage), *Genetyllis* (surname), *Hecaerge* (surname), *Hippodameia* (surname), *Idalia* (surname), *Ishtar* (Babylonian), *Kypris, Limenia* (surname), *Mechanitis* (surname), *Melaenis* (Black One; surname), *Melinaea, Migonitis* (surname), *Morpho* (surname), *Nicerphoros* (surname), *Pandemos* (surname), *Paphia* (sexual love; surname), *Peitho Suadela* (Roman), *Pelagia, Philia* (surname), *Pontia* (she who arose from the sea), *Scotia* (Dark One), *Urania* (surname), *Venus* (Roman), *Zephyritis* (surname), *Zerynthia* (surname).

One of the twelve Olympians. Goddess of love, beauty and sensual desire. Patron of courtesans. She is the beautiful, sensual daughter of Zeus and his aunt Dione, or Cronus and Euonyme, or Uranus and Hemera. Some say her mother is Eileithyia, the goddess of birth, who is said to be the daughter of Zeus and Hera. Alternately, she was born of sea foam where the severed genitals of Uranus were thrown into the sea by Cronus. Using the prior scenario, she landed either at Paphos in Cyprus or at Cythera, hence her epithets "Kypris" and "Cythera" which also indicate her connection with the goddesses Ishtar and Astarte. Zeus arranged her marriage with his half-brother, the god of fire, Hephaistos. He is an ugly god who has a lame leg. From appearances, their marriage was an unlikely match. Hephaistos, however, made his beauty shine through his works of art as a smith to the gods. Aphrodite was renowned for her extra-marital affairs with gods and mortals. Her lovers' stations in life were not of importance to her. She delights in her sexuality. Some of her lovers were Adonis, Anchises, Ares, Butes, Dionysus, Hermes, Poseidon and Zeus. Her favorite lover was the god of war, Ares, who is the son of Zeus. They had children together: Phoebus, Deimos, Harmonia, Eros, and Anteros. Her other children by gods are Hermaphroditus by Hermes; Eryx by Poseidon; Priapus by Dionysus. Children from her relationships with mortals are Aeneas and Lyrus by Anchises; and a boy and a girl by Adonis. She is also the mother of Aeneas, Beroe, Golgos, Hymen, Herophilus, and Rhodos. She was worshipped as Aphrodite Urania (goddess of the sky or, goddess of higher intellectual love), and Aphrodite Pandemos (goddess of the folk, marriage and family life). The red poppy, the rose, the myrtle, the apple, the dove, swan and swallow, the tortoise, ram, the planet Venus and the month of April are sacred to her. She is usually shown nude or slightly clothed in diaphanous drapery material. She is also identified with Astarte, the Egyptian Hathor, the Roman Syria Dea and Venus. Comparable to Benten (Japan) and Sarasvati (India). She is connected to the Oceanids (q.v.). For more information regarding her relationships, *see* Adonis; Anchises; Ares; Dionysus; Hermes; Poseidon. *See also* Achilles; Adonis; Adrastia; Aeneas; Aglaia; Aither; Alitta; Anat; Anchises; Anteros; Ariadne; Asopus; Atalanta; Chaos; Eos; Fates; Gaea; Graces; Harmonia (A); Helius; Hephaistos; Hermaphroditus; Hymen; Ishtar; Sirens; Tiamat; Venus.

Aphson (Babylonia) *see* Apsu.

Api (Egypt) One of the gods in the Pyramid Texts.

Apis (A) (Egyptian)
Also known as: *Asar-Hap* (Greek), *Asar-Hapi* (Greek), "Bull of Amentet," "Bull of the Underworld," *Epaphus* (Egypt), *Hap, Hapi, Hapi-Ankh, Osiris-Apis* (Greek), *Osiris-Hapi* (Greek), *Osorapis* (Greek), *Ptah, Serapis* (Greek).

Originally Apis was considered to be the god of Memphis, Ptah. The bull symbolized the sacred life of Ptah (q.v.). Apis is the Greek modification of the name Hap. Later in the same animal shape the bull was regarded as Osiris. At that time Osiris was called the "Bull of Amentet" or the "Bull of the Underworld." Apis became the most important of the sacred bulls in Egypt. He was Osiris incarnated in bull form. He went to earth as his own representative in the shape of a bull. He was recognized by his black hide, triangle of white on his forehead, white crescent spot on the right side and a knot under his tongue. When the original Apis died, mourning for him continued until a new bull fitting the description of the original Apis was found. The new bull symbolized resurrection. Each apis was venerated by the priests who gave him food and shelter. During his twenty-fifth year he was drowned in a holy spring. Later, before the Roman invasion when the Greeks ruled Egypt, Apis was worshiped as Serapis. In another myth the sacred bulls Apis of Memphis, and Mnevis of Heliopolis were dedicated to Osiris. It was commanded that all Egyptians worship these animals as they had assisted in the discovery of corn and in sowing the seed, thus spreading the benefits of agriculture to the people. After the Late Period Apis was depicted on many coffins as a sacred bull running with the mummy of the deceased to the tomb. After the New Kingdom he turned up with a sun-disk on his head. Apis is pictured as a bull with a star or crescent between his horns and with an amulet hanging from his neck. Sometimes Isis sits on his back. He has also been seen wearing the disk and figure of a sacred serpent (Uraeus) on his head. Apis is linked to Epaphos, the son of Io. In Greek mythology Epaphus, the son of Zeus and Io, became the King of Egypt, was married to Memphis, and founded the city of Memphis. He was rumored to be the bull Apis. *See also* Amentet; Cherub; Hap; Mnevis; Osiris; Ptah; Serapis.

Apis (B) (Greek)
Ruler of Apia. Seer. Apis is the son of Phoroneus and Teledyne and the brother of Car and Niobe. A cruel and unjust ruler, he was deposed by Thelxion and Telchis and killed by the son of Endymion, Aetolus. He died childless and his nephew Argus, son of Niobe, succeeded him. Aeschylus wrote that Apis was a son of Apollo, a seer and a physician originally from Naupactus, who practiced in Argos. *See also* Niobe (B).

Apisirahts (Blackfeet People, North America)
Also known as: *The Morning Star, The Morning Venus God.*

A deified mortal, Apisirahts is the son of the sun god. He took a mortal girl to heaven. She was allowed to dig for every root but that of the "forbidden turnip." Out of curiosity, she disobeyed and uncovered the hole to earth. Forced to return to earth, she was let down by Spider Man's web. She died longing for Apisirahts. *See also* Napi.

Apit (Egypt)
One of the goddesses of the city of Unnu or Hermopolis or possibly another of the many cities of ancient Egypt.

Aplu (Greek) *see* Apollo.

Apo (Persian)
He is a water deity and a Yazata (q.v.). *See also* Amesha Spentas; Anahita.

Apocatequil (Inca, Peru)
A popular god of lightning, he is the son of the first mortal Guamansuri (posthumously), and the twin brother of Piguero. The mother of the twins was brutally murdered by her brothers, the Guachimines. Apocatequil brought his mother back to life and killed the Guachimines. Ataguchu showed them how to make a hole from Pacari, the Cave of Refuge, that would lead them to the land of the Incas. The twins released the first Peruvians from the underworld. They are possibly deities of night and day. *See also* Creation Legends of the Inca; Pacari (for other versions of the Inca Creation Legend).

Apochquiahuayan (Aztec, Mexico)
This is another name for the Aztec underworld, Mictlan (q.v.).

Apoconallotl (Aztec) *see* Chalchiuhtlicue.

Apollo *Apollon* (Greek)
Also known as: *Abaeus, Abaios, Acersecomes* (surname meaning Unshorn), *Aguieus, Agyieus, Agyieyus, Aplu, Cynthius* (born on Mount Cynthius), *Delius, Far Darter* (Dealer of Death), *Helios, Hobal, Loxias, Lycean, Lykeious* (wolf god), *Moiragete* (guide of the Moirae), *Musagetes* (patron of the Muses), *Namios* (He of the Pastures), *Paean* (the Healing God), *Phaenops, Phoebus* (the Shining One), *Phoebus Apollo, Reshep* (Babylon), *Smintheus* (mouse-god), *Tushna* (Etruscan).

God of light. God of prophecy. Patron of medicine, music, the lyre and archery. One of the twelve Olympians. Apollo may have originated in Asia and was possibly a Hittite god (Hobal). There is a remote possibility he originated from a Nordic divinity. He is the son of the great god Zeus and Leto (also known as Latona), the twin of the goddess Artemis and the father of the physician god Asclepius. Apollo and Artemis, were born on Delos. He spent three months of the year with the Hyperboreans. The remaining months were spent at Delphi. His various lovers and numerous children are by Acacallis, Amphithemis and Miletus; Acantha (no children); by Arsinoe, Eriopis; Asteria, no children; Bolina, no children; by Calliope, Orpheus; by Calaeno or Thyia, Delphus; Cassandra, no children; Castalia, no children; by Chione, Philammon; by Chrysorthe, Corona; Clymene, no children; by Coronis or Arsinoe, Asclepius; by Creusa, Cyrene, Autychus, Idom (possibly), Aristaeus; Daphne, no children; by Dryope, Amphissus; by Evadne, Iamus; by Issa, Hecuba (possibly) Troilus; Melia, no children; by Ocyrrhoe, Phasis; by Parthenope, Lycomedes; by Phtia, Dorus, Laodocus, Polypoetes; by Procleia, Tenes; by Psamathe, Linus; by Rhoeo, Anius; by Stilbe, Centaurus, Lapithus; by Syllis, Zeuxippus; by Thyia, Delphus; by Thyria, Cygnus and Phylisu. His homosexual lovers were Cyparissus and Hyacinthus. Apollo killed the Python and the Cyclops. The Cyclops, manufacturers of Zeus' thunderbolts, made the thunderbolt that killed Apollo's son, Asclepius. Apollo in retaliation killed the Cyclops. As a result of the Cyclops' death, Apollo was forced to serve, in the capacity of a herdsman, the Argonaut Admetus for one year. After Tityus, the Euboeoan giant attempted to rape their mother, Leto, Apollo and Artemis killed him (some say he died by Zeus' hand). They were also responsible for slaying Niobe's children. As a sun symbol, Apollo's spreading golden hairs on his head are likened to rays of the sun. The bow and arrow represents the same symbology, as well as depicting the male-female principles. In Greece and Pre-Columbian America, the arrow represented the sun's rays. As well as being a phallic symbol, the arrow symbolizes the light of supreme power. Apollo's sacred birds are the raven and the swan. His sacred tree is the laurel. His sacred instrument the lyre, and his sacred island, Delphos. Compare Apollo to the Hindu god, Vishnu, the Babylonian, Shamash, and the Egyptian god, Horus. *See also* Abaris; Acacallis; Achilles; Actaeon; Admetus; Aeacus; Aegle; Ajax the Lesser; Aloeides; Amphion;

www.ebook3000.com

Apis (B); Ares; Argus (A); Artemis; Aristaeus; Asclepius; Behedety (Egypt); Bel (Celtic); Borvo; Cassandra; Clytia; Curetes; Cyclops; Eurydice (C); Graces; Helius; Hestia; Hymen; Leto; Muses; Niobe; Oceanus; Sinope; Tityus; Zephyrus.

Apollodorus (Greek) Mythologist of the 2nd century B.C.E.

Apollon (Greek) *see* Apollo.

Aponbolinayen *Aponitolau* (Philippine) *see* Ina-Init.

Apophis *Apopophis*

Also known as: *Aaapef, Ap, Apap, Apep, Apepi* (Egypt).

Underworld deity. Apophis is the serpent-devil of mist, darkness, storm, and night. His fiends are called the "the children of rebellion." This immense serpent lives in the other Nile that flows through the vault of heaven. He constantly attempts to thwart the god Ra as he rides daily across the sky in his sunboat. Whenever Apophis is successful, an eclipse occurs. Apophis represents darkness and its struggle against the light of the sun. Because he is the sun's enemy, he was confused and identified with Seth, the enemy of the gods, in later times. Existing ritual texts refer to the "overthrowing of Apophis" and offer magical protection. It is said that each morning when the sun rises and each evening as it descends, the sun boat is attacked by Apophis causing the sky to turn red from the defeated serpent. In the "Book of the Dead," the "great cat" cuts off the head of Apophis when his body threatens the sacred Persea Tree. Apophis is generally pictured as a massive animal, sometimes pierced with spears or knives by Horus. He is similar to the Babylonian Tiamat. *See also* Aai; Ab-esh-imy-duat; Ab-she; Ab-ta; Akeneh; Akhen; Apepi.

Apsaras (India) *see* Apsarases.

Apsarases *Apsaras, Apsarases* (Brahman, Buddhist, Hindu, Vedic; India)

Also known as: *Devaki, Kshiti-Apsarases* (terrestrial Apsarases), *Vrikshakas* (tree nymphs).

The Apsarases are music-making angels in the Buddhist faith. In Hinduism they reside in Indra's heaven Amaravati as water nymphs or celestial dancers. According to the Ramayana, they rose from the Churning of the Ocean. In later Hindu mythology they are depicted as beautiful courtesans of the sky who were the consorts of the Gandharvas. The Apsarases were given as rewards to heroes slain in battle. They often lived in the sacred Banyan tree (*Ficus benghalensis*). It is a species of the fig tree and is sacred because it is believed that a woman who desires children will be blessed if she prays under its leaves. When wedding processions passed the trees they were asked to bless the wedding party. The Apsarases, who are shape changers, have a dark side that is employed when the gods want holy people driven mad so they will not become too powerful. They bring good or bad luck to the gambler. One of the legends of Ganga, the Hindu river goddess of the sacred river Ganges, is connected with the Apsarases. They are sometimes thought of as clouds but are generally shown flying through the clouds. They are shown as beautiful, voluptuous, large-hipped, lightly clad, young women. In Cambodia they are often depicted dressed in long skirts, holding flowers, or dancing with their knees apart. In Cham representation, the Apsarases are shown to the waist, holding a lotus bud and appearing as though they are coming out of a wall. In one reference, it is stated that there are five hundred Apsarases. Some of their names are Adrola, Alambusha, Angana, Bhima (Terrible), Caksusi (the Clairvoyant), Harini, Lavangi (She of the Clove Tree), Manasi (the Intelligent One), Marisha, Menaka, Misrakesi, Pramlocha, Purvachitti, Rambha, Sahaganya, Sanumati, Sasilekha, Saudamani, Shakuntala, Sukanthi, Surabhidatta, Surapamsula, Urvasi. The Apsarases are associated with Ganga, the Hindu river goddess of the Ganges. *See also* Amaravati; Amatsu-otome (Japan); Angara; Devaki; Devas (A); Gandharvas; Ganga; Hanuman; Kama (A); Kurma (regarding Churning of the Ocean); Marisha; Menaka; Pramlocha; Pishachas; Rambha; Sarasvati; Satyavati (regarding Adrika); Shakuntala; Swarga; Urvasi.

Apsarasras (India) *see* Apsarases.

Apsu *Abzu* (Sumerian), *Apzu* (Assyro-Babylonian)

Also known as: *Apason* (possibly), *Aphson* (Babylonian), *Rishtu, Zigarun* (Akkadia, "The Mother Who Has Begotten Heaven and Earth).

In the very beginning, in Assyro-Babylonian mythology, only the primordial oceans existed. The Apsu was sweet water which encircled the earth. Earth was a round plateau bounded by mountains. The vault of heaven rested on the mountains which floated on the Apsu. Apsu fused with the female principle, Tiamat, in the form of salt water, and all things were created, beginning with Lahamu and Lahmu (also known as Lakhmu and Lakhamu), who possibly represented a type of silt and have been described as monstrous serpent gods. They were followed by Anshar, possibly the earth aspect, and Kishar, possibly the sky aspect. They created the sky god Anu, and Anu created the earth god and god of wisdom, Nudimmud (also called Ea or Enki), and Inlil. As the gods grew they attempted to create order out of chaos. Their rebelliousness angered Apsu and Tiamat. They called upon Mummu, to assist them in slaying their offspring. Before this feat was accomplished Tiamat had a change of heart and declined to be involved. Ea, with the aid of a magic incantation, killed Apsu and locked Mummu away. Later, after establishing his abode on the corpse of Apsu, he and his spouse, Damkina, became the parents of Marduk. Tiamat, with an army of monsters and renegade gods attempted to avenge her spouse's death. Marduk overcame her, split her corpse in two, and created heaven and earth. With the assistance of his father, Ea, mortals were created from the blood of the renegade god Kingu's blood. At first Apsu was a feminine deity, but later, as a god, he was the dragon husband of Tiamat and father of the other gods. The Babylonian version gives Apsu the mate named Mummu. In other versions Mummu is known as the commander-in-chief or messenger of Apsu. In a Sumerian version where Apsu is thought to be a river or sea, Ea gathered clay from the Apsu and created the gods. In one tale, Apsu was kept awake by the noise of the gods and wanted to destroy them, but was captured by the overlord Ea. Ea cast a spell on him that caused him to fall into a deep sleep. While sleeping Ea killed him and took over his dwelling. Ea cast the same spell on Mummu and became powerless. The Sumerians believed this was the sea where the Anunnaki and Igigi dwelled and where they were ruled by Marduk. As Aphson, in the Babylonian Creation Myth of Damascius, he was the spouse of Tauthe. Compare Apsu to the Greek Oceanus. *See also* Anshar; Anu (B);

Anunnaki; Damkina; Ea; Enuma Elish; Igigi; Kingu; Kishar; Lahamu and Lahmu; Marduk; Mummu; Nudimmud; Tiamat.

Apsyrtus *Apsyrtos* (Greek)
Also known as: *Aegialeius, Aegialeus, Phaethon* (Shining One).

Apsyrtus was born with the name Aegialeus and became known as Apsyrtus, meaning "swept down" after his death. His father was Aeetes, the ruthless king of Colchis and his mother was either Asterodeia or his father's second wife Eidyia (the daughter of Oceanus and Tethys). In one myth it is related that Aeetes sent Apsyrtus in pursuit of the ship Argos, which carried his daughter Medea, Jason the Argonaut and the Golden Fleece. He trapped the ship at the mouth of the Danube. The Argonauts agreed to set Medea ashore on an island while they debated whether she should return home or follow Jason to Greece and who should have possession of the Golden Fleece. Meanwhile, Medea sent an untruthful message to Apsyrtus telling him that she had been abducted and begging him to rescue her. When he arrived on the island he was murdered and dismembered by Jason. In the version by the Greek poet Apollonius Rhondius, Jason killed Apsyrtus but Medea dismembered him and threw his body parts into the sea. Aeetes then abandoned his pursuit of the Argos to collect his son's remains. There are accounts of this myth wherein Jason also kills Aeetes. For various accounts of the route taken by the Argos, *see* Aeetes, Jason, and Medea. There are two other figures named Aegialeus. One is the son of Inachus and Melia, and the brother of Io and Phoroneus; the other is the son of Adrastus and Amphithea. This man was the only Epigoni killed in the taking of Glias by Laodamas. *See also* Aeetes; Aegialeus; Golden Fleece; Jason; Medea.

Apt *Apet, Aptu* (Egypt) *see* Apet; Aptu; Hathor.

Apt-ent-khet (Egypt) *see* Aaru.

Apt-ent-qahu (Egypt) *see* Aaru.

Apt-net (Egypt) *see* Aaru.

Aptu (Egypt)
Also known as: *Apet, Apt.*
A water monster. Also, the ark on which Osiris floats. *See also* Apet; Osiris.

Apu (Egypt)
A god in the ninth sector of Tuat. He holds the serpent Shemti, which has four heads at each end of his body. *See also* Ab-ta; Tuat.

Apu-Hau (Polynesia)
"Fierce Squalls." The son of the god of winds, Tawhiri-ma-tea.

Apu-Matangi (Polynesia)
"Whirlwind." The child of Tawhiri-ma-tea.

Apu Punchau (Peru) *see* Inti.

Apu-Punchau *Apu Punchau* (Inca, Peru) *see* Inti.

Apzu (Assyro-Babylonian) *see* Apsu.

Apzu-Rishtu (Assyrian) Counterpart to Tiamat (q.v.).

Aqas-Xena-Xenas (Chinook People, North America) *see* Agas Xenas Xena.

Aquila (Greek)
This is the eagle that flew Aphrodite's slipper to Hermes, or the eagle that took Ganymede to the celestial realm. It could also be Metope, after she was transformed by the goddess Hera.

Aquilo *Aguilo* (Roman)
North wind personified. Equivalent of the Greek Boreas (q.v.).

Ar-Ast-Neter (Egypt)
One of the gods who accompany Osiris during the second hour of the night. *See also* Tuat or Shesat Maket Neb-S.

Ara (Armenian, Phrygian)
Culture hero. Possible sun-god. Ara is the husband of Nvard. He was captured and possibly killed by Queen Semiramis. He is possibly related to, or the same as Er, the son of Armenius. There are similarities in Ara's life to the story of Gilgamesh.

Ara-Mi-Tama (Japan) *see* Amaterasu.

Ara-mi-tama (Japan)
Susanow's wicked soul. His beneficent soul is known as Nigi-mi-tama. *See also* Susanow.

Ara Tiotio (Morai People, New Zealand)
Also known as: *Awhiowhio* (Australia).
God of tornadoes. *See also* Awhiowhio.

Arabus (Greek)
He is the son of Hermes, brother of Daphnis and father of Cassiopeia (q.v.)

Arachne (Greek)
Deity of weaving.
She is the daughter of Idmon and Colophon. She challenged Athena to a weaving contest. They came out even. The jealous goddess Athena took her competitor's cloth and destroyed it. Arachne hung herself. Athena then changed her into a spider. *See also* Amaterasu (Japan); Athena.

Araga (India) This is another name for Vishnu as Rudra (q.v.).

Arak (Cambodia)
A family guardian spirit, the Arak lives in the house or a tree. When someone is seriously ill, a shaman (kru) is called to have the Arak incarnated in himself. The Arak tells the shaman what evil spirit is torturing the patient. The patient is then gashed and rice wine is poured over him or her. Special festival days are set aside for the Araks between January and March.

Aralez (Armenian) *see* Arlez.

Arallu *Aralu* (Assyro-Babylonian, Sumer)
Also known as: *Anduruna, Ganzir, Shualu.*
The underworld. Arallu is a kingdom ruled by Ereshkigal and her consort, Nergal. This is the place where the dead are judged. Sometimes it is depicted as a lower world and sometimes a mountain. There are seven entrances by seven gates in the west, the place of the setting sun. Arallu is infested with monster and demon souls of the wicked dead, the etimmu and gigim. In the legend of Gilgamesh the goddess, Irkalla or Allat

www.ebook3000.com

was possibly the ruler Arallu. The goddess Ishtar followed Tammuz in his annual descent into Arallu. The watchman of Arallu is Nedu (also known as Neti). *See also* Anduruna; Ishtar; Tammuz.

Aralu (Babylonian) *see* Arallu.

Aram (Armenian) *see* Armenak; Ba'al Shamin.

Aramaiti (Persia) *see* Amesha Spentas; Amshaspends; Daevas.

Aramati (India) Goddess of devotion.

Aramazd (Armenian, Persian)
Also known as: *Ahura Mazda, Ormizd.*
Supreme god. Creator. He is the chief deity, possibly of the Zoroastrianism cult, in early Armenia. Some say he is the father of Anahita, Mihr and Nane. He is probably a sky god and a fertility god similar in nature to the Persian Ahura Mazda. In some versions, he is thought to be the son of Zervana Akarana and twin brother of Ahriman. Although called the father of gods, there is no indication of a wife or consort. There is a vague reference in some texts that Anahit was his wife but, although possible, there is no direct evidence. Aramazd's messengers or angels are the Hreshtak which might be the same as the Persian, Firistak. Some of Aramazd's attributes are similar to those of Dionysus. *See also* Ahura-Mazda; Anahita; Aramazd (for Firistak); Dionysus; Tiur.

Aranunna (Babylonia) *see* Marduk.

Arawak People — Creation Legend (New Guinea) *see* Makonaima; Sigu.

Arawn (Celtic, Irish)
Also known as: *Anguissance, Augusel.*
God of the underworld. Arawn, the ruler of the underworld, Annwn and owner of the magic cauldron, frequently contended with would-be usurpers for his title. In one myth, Arawn, said to be the originator of pigs, gave Pwyll the underworld animals as a gift in return for ridding him of his rival Hafgan (also spelled Havgan). Hafgan was Arawn's enemy from the otherworld whom he had to fight yearly. Once, Arawn and Pwyll magically exchanged bodies for a year and a day so that Pwyll could get Hafgan out of Arawn's life. In the Arthurian cycle, he was known as one of the kings of Scotland. Arawn is depicted as a huntsman, with a pack of red-eared dogs, chasing a white stag. *See also* Achren; Amathaon; Annfwn; Pwyll.

Arazu (Akkadian, Sumer)
God of crafts. Arazu is one of the gods created by Ea at the beginning. From an ancient prayer, it could be construed to mean Arazu was a priest. "[He] Created the god of carpenters, molders, and Arazu, as completers of the work of his creation."

Arbhu (India) *see* Ribhus (The).

Arbidihist (Persia) *see* Asha Vahishta.

Archelous (Greek) *see* Acamas (B) and Aeneas.

Archander and Architekes (Greek) *see* Achaeus.

Archons (Post-Christian Gnostics, the Ophites)
Also known as: *The Great Archon, Ruler According to Valentinus.*
They are the seven ruling spirits created by the god Ophiomorphus, the serpent son of Ialdabaoth. The first was either Adonaeus or Adonai; the second, Ialdabaoth; third, Iao; fourth, Sabaoth; fifth, Astaphaios; sixth, Ailaiosastaphaios; seventh, Horaios. They are associated with Abraxas (q.v.). *See also* Pistis Sophia.

Ardabahisht (Persia) *see* Asha Vahishta.

Ardevi Sura Anahita (Persian) *see* Anahita.

Ardhanari (India) *see* Ardhanariswara; Shiva.

Ardhanari-Ishvara *Ardhanari, Ardhanari-Ishavara, Arhhanariswara* (Hindu; India)
Also known as: *Hara Gauri.*
Brahma, unhappy with his creation of male deities, called forth Shiva, who appeared in the form of Ardhanari-Ishavara, "The Lord Who Is Both Male and Female." Ardhanari-Ishavara is the combination of Shiva and his wife Devi, who were so in love, they became one. Ardhanari-Ishavara is depicted with a bare torso, and one of two breasts, obviously female, is full and sensuous. The forehead is extremely high and represents the lingam. When the image is of half–Shiva and half–Gauri it is called Hara Gauri. *See also* Brahma; Devi; Lakshmi; Shiva.

Ardhanariswara (India) *see* Ardhanari-Ishvara.

Ardi-bahisht (Persia) *see* Asha Vahishta.

Ardusht (Persia) *see* Zoroaster.

Ardvi Sura Anahita *see* Anahita.

Ardvi Vaxsha (Persia)
Goddess of Water and Moisture.

Areimanios (Roman) *see* Mithras.

Areius (Greek)
He is the Argonaut son of Bias, the king of Argos and the beautiful daughter of Neleus and Chloris, Pero. For a list of siblings, *see* Pero. *See also* Bias.

Arekoi (Iroquois People, North America) *see* Areskoui.

Aremata-Rorua and Aremata-Popoa (Polynesia)
"Long Wave and Short Wave." These are two powerful ocean demons.

Arene (Greek)
Arene is the daughter of Oebaulus, the king of Sparta and Gorgophone. *See also* Gorgophone; Hippocoon.

Areop-Enap (Gilbert and Nauru Islands, Micronesia)
Also known as: *Ancient Spider.*
This creator god floats in space. He created the moon from a snail he found in a large mussel, then created sun from another snail. He then made earth from the lower half of the mussel shell with the help of a worm or grub (Rigi). The sweat from the grub in his efforts to raise the top of the shell became the sea. *See also* Nareau; Rigi; Yelafaz.

Ares (Greek; possibly worshiped in Thrace and Scythia. May have originated as a Minoan deity).
Also known as: *Alloprosallos, Enualios* (possibly), *Enyalius*

(possibly), *Gradivus* ("Leader of Armies"), *Maris, Mars, Tues, Tuesco, Tui.*

Storm god. God of war. Ares is the only son of Zeus and Hera. His sisters are Aphrodite the goddess of love; his twin Eris (also known as Discordia), the goddess of strife and discord, the nymph Arge, Eileithyia, the goddess of childbirth, and Hebe (also known as Ganymeda), the goddess of eternal youth. Ares never married but he had numerous affairs with goddesses and mortal women and he fathered many children. One of his great loves was his sister Aphrodite and they had a number of children even though she was married to the fire god Hephaistos. They were the parents of Deimos (Fear), Phobos (Panic), the god of fear and terror, Harmonia, who was turned into a snake by Ares, Pallor (Terror), Anteros, the god of passion, and possibly Eros, the god of love. Their affair ended when Helius, the sun god, betrayed them. They were discovered when Aphrodite's husband was away. Ares took his usual advantage of the time to slip into bed with the love goddess. Helius, the sun god, arranged to have a net fall over the naked lovers and then invited other Olympian gods into the bedroom to look and laugh. Poseidon stepped in and convinced the wronged husband to accept reparation from Ares and he let the guilty couple go their opposite ways. The virile Ares also had children by Demonice, the daughter of the Calydonian Agenor; Evenus, who eventually committed suicide, and possibly Thestius, Pylus, Molus and Oeneus (their mother may be Alcippe). Dryas, the Argonaut, was his son by an unknown woman in Aetolia. He may have been the father of the Argonaut Meleager, by Althea, who eventually hung herself. He was the father of Ialmenus and Ascalaphus, both Argonauts, by Astyoche. By either Dotis or Chryse (also known as Comana) he was the father of Phlegyas who became the king of Orchomenus and had a daughter who was raped by Apollo. By the nymph Cyrene, who loved to wrestle lions, or possibly Asteric, he was the father of Diomedes who was made to eat his flesh-eating horses by Heracles. Cygnus, who was turned into a swan, is Ares' son by Pelopia or Pyrene. Some say he was the father of Parthenopaeus by the huntress Atalanta. By Otrere (Otrera), he was the father of the Amazon queen, Penthesileia, and Antiope (Melanippe) and Hippolyte, who was either killed by Heracles or died of a broken heart. He was also the father of Tereus, who after raping his sister-in-law, cut out her tongue. By Asterope or Harpina, he is thought by some to be the father of King Oenomaus, who killed all but the last of his daughter's suitors. King Oxlus was also his son by Protogeneia. It is possible that he is the father of Ixion. Another son, Aeropus, was born from his union with Aerope, who died in childbirth; the child was miraculously saved by Ares. He also had an affair with the dawn goddess Eos. When his lover-sister, Aphrodite found out, she punished Eos by making her be perpetually in love. Ares seduced Agraulus and they had a daughter, Alcippe. Halirrhothius, the son of Poseidon, raped Alcippe, and an inflamed Ares killed him. This action resulted in him being the first person, mortal or divine to be tried for murder. He was acquitted by his daughter's testimony. Though Ares is called a warrior, he fared better in the bedroom then on the battlefield. He was captured by the twin giants Otus and Ephialtes and stuffed into a bronze encasement for thirteen months. Hermes apparently rescued him. Heracles overcame him four times in battles. He was so gravely injured during the Trojan War that he fled the battle arena screaming and ran off to complain to Zeus, who was not impressed. Zeus told him that he was hated by the other gods. Whenever he was at war he was accompanied by his sons, Deimus (Fear) and Phobus (Panic). He was able to redeem his warrior character to an extent when he killed the Giant Mimas during the battle between the gods and the Giants. Menoeceus, the son of Creon, sacrificed himself to Ares to save the city of Thebes from destruction. His symbols are a spear or an arrow or the burning torch, and a spear. Ares is sometimes shown as a helmeted warrior dressed in armor. The cock is his emblem and he is associated with the dog and vulture. Some say he is identified with the Egyptian god, Anhur, and is similar to Eres (Teutonic) and Maruts (Vedic). He is sometimes associated with Athene. Ares is frequently identified with the Roman Mars. He is deified for his warlike spirit rather than as war god. Similar to the Norse god of war Thor. *See also* Adonis; Aloeides; Althea; Anhur; Anteros; Enyalius; Graiae; Harmonia (A); Hephaistos; Ixion; Mars; Oenamaus.

Areskoui *Agreaskoui, Agriskoue, Aireskoi, Aireskouy, Arekoi* (Iroquois People, North America)

Also known as: *Great Spirit.*

A creator god. He was offered first fruits of the chase, and woman captives were sacrificed to him. Possibly a god of hunting and war. *See also* Kitshi Manito.

Arete (Greek)

Goddess of virtue. Representative of courage. Wife of Alcinous (King of the Phaeacians). She accompanied and guided Hercules along a thorny path where he did many virtuous things. She was also worshiped by Jason of the Argonauts. *See also* Argonauts; Heracles; Jason; Odysseus.

Arethusa (A) *Aethusa* (Greek)

Wood nymph. Nymph of springs and fountains. Artemis' attendant. Arethusa, the daughter of Oceanus. She was pursued by the river god Alpheus until Artemis changed her into a spring on the island of Ortygia. She is forever joined to the river Alpheus. Heracles had to divert the river's waters in order to clean the Augeian stables, one of his labors. Arethusa may be an aspect of Artemis. *See also* Alpheus; Artemis; Heracles; Oceanus.

Arethusa (B) *Aethusa* (Greek)

She is the daughter of Atlas and Pleione (also known as Aethra). She is one of the Hesperides (Aegle, Erythia, Hesperia). Her other siblings are the Hyades, Pleiades, Hyas and Calypso. *See also* Atlas; Calypso; Hesperia; Hesperides.

Aretia (Chaldea)

Also known as: *Horchia, Titae-Aretia, Titaea Magna.*

Little known Earth Goddess. Some say Aretia is connected with Janus. She is possibly the same as the Greek Arete.

Aretus (A) (Greek)

Son of Nestor and Anaxibia. *See also* Anaxibia; Antilochus.

Aretus (B) (Greek)

He is one of fifty sons of Priam, the last king of Troy.

Arganthone (Thracian) Goddess of Hunting.

www.ebook3000.com

Argayu (Yoruba People, Africa)

He is the sun god and god of the desert. *See also* Ogun; Olodumare.

Arge (Greek) *see* Ares; Argos; Cyclops; Hephaistos.

Arge Woyo (Haitian) *see* Agbe (Dahomey People, Africa).

Argeia (Greek) *see* Adrestus; Amphithea; Argus (C).

Arges (Greek) *see* Aegaeon; Gaea.

Argetlam "The Silver Handed" (Celtic) *see* Llud.

Argia (Greek) *see* Inachus; Meliae.

Argiope (A) (Greek) Nymph.

She is the spouse of the poet and musician, Philammon, and the mother of Thamyris, the minstrel of Thrace. *See also* Agenor (A); Europa.

Argiope (B) (Greek)

Argiope may be the same as Telephassa (q.v.), or they could be two different people.

Argonauts (Greek)

Heroes. The Argonauts are the crew of heroes recruited by Jason in his quest for the Golden Fleece. They sailed to Colchis on the Argos about eighty years before the Trojan War. Because a number of the Argonauts, including Jason, were said to have sprung from the blood of Minyas' daughters, they are also known as the Minyans. *See also* Actor (A); Actor (C); Amycus; Argonauts (Names of); Argus (C); Argus (D); Argus (E); Harpies; Heperides; Hylas; Jason; Nereids.

Argonauts (Names of) (Greek)

Acasus, son of King Pelias; *Actor*, son of Deion the Phocian; *Admetus*, prince of Pherae, son of Pheres and Periclymene; *Amphiaraus*, the Argive seer; *Great Ancaeus* of Tegea, son of Poseidon; *Little Ancaeus*, the Lelegian of Samos; *Argus* the Thespian, builder of the Argo; *Ascalaphus* the Orchomenan, son of Ares; *Asterion*, son of the Pelopian Cometes and Antigone; *Atalanta* of Calydon, the virgin huntress; *Augeias*, son of King Phorbas of Elis; *Butes* of Athens, the bee-master; *Caeneus* the Lapith (he had once been a woman); *Calais*, the winged son of Boreas; *Canthus* the Euboean; *Castor*, the Spartan wrestler, one of the Dioscuri; *Cepheus*, son of Aleus the Arcadian; *Coronus* the Lapith, of Gryton in Thessaly, son of Caenus; *Echion*, the herald, son of Hermes and Eupolemeia; *Erginus* of Miletus; *Euphemus* of Taenarum, the swimmer; *Euryalus*, son of Mecisteus, one of the Epigoni; *Eurydamas* the Dolopian, from Lake Xynias, son of Ampycus and Chloris; *Heracles* of Tiryns, the strongest man who ever lived, now a god; *Hylas* the Dryopian, squire to Heracles; *Idas*, son of Aphareus of Messene; *Idom* the Argive, son of Abas or Apollo and Asteria or Cyrene; *Iphiclus*, son of Phylacus or Cephalus and Clymene or of Thestius the Aetolian; *Iphitus*, son of Naubolus the king of Phocis; *Jason*, the captain of the expedition, son of Aeson and Alcimede; *Laertes*, son of Acrisius the Argive; *Lynceus*, the look-out man, brother to Idas; *Melampus* of Pylus, son of Poseidon; *Meleager* of Calydon; *Mopsus* the Lapith, son of Ampycus and Chloris; *Nauplius* the Argive, a noted navigator, son of Poseidon; *Oileus* the Locrian, father of Ajax; *Orpheus*, the Thracian poet, son of Oeager and Calliope; *Palaemon*, son of Hephaestus, an Aetolian; *Peleus* the Myrmidon; *Peneleos*, son of Hippalcimus, the Boeotian; *Periclymenus* of Pylus, the shape-shifting son of Poseidon; *Phalerus*, the Athenian archer; *Phanus*, the Cretan son of Dionysus; *Poeas*, son of Thaumacus the Magnesian; *Polydeuces*, the Spartan boxer, one of the Dioscuri; *Staphylus*, brother of Phanus; *Tiphys*, the helmsman, of Boeotian Sipae, son of Hagnias or Phorbas and Hyrmina; *Zetes*, the brother of Calais.

Argos (Greek) *see* Argus.

Argrius (Greek) *see* Calydonian Boar Hunt.

Argunis (Greek) *see* Arjuna (India).

Argus (A) *Argos* (Greek)

King of Argos. Argus is the son of Zeus and Niobe, a mortal who is the daughter of Phoroneus. He was the first child born of a god and a mortal woman. His siblings are Osiris, who was murdered by his other brother Typhon; Pelasgus, who became the first king of Arcadia. Argus married Evadne, the daughter of Strymon and Neaera. They became the parents of Peiras, Ecbasus, Criasus and possibly Epidaurus. (In other accounts he is the son of Pelops or Apollo.) Argus was said to have introduced the cultivation of grain to the city of Argos (named after him) where he remained king for seventy years. The city of Argos was founded by Phoroneus and was originally named Phoronea. The main deity of the city of Argos from Pre-Hellenic times was Hera. *See also* Apis (B); Niobe (B); Osiris; Phoroneus; Typhon; Zeus.

Argus (B) *Argos* (Greek)

Also known as: *Argus of the Hundred Eyes, Argus Panoptes* (All-Caring).

Monster. Argus was either born of Gaea (the earth) or he was the son of Agenor or Inachus, river gods and brothers. His grandfather, a monster also named Argus, killed the dragon Echidna. His grandson Argus inherited his looks; he was a monster giant with one hundred eyes all over his body; fifty watched while fifty slept. Argus was sent by Hera to guard Io from the amorous Zeus. He was killed by Hermes when Hera felt that he had over-stepped his boundaries. She used his eyes to decorate the tail feathers of the peacock. *See also* Echidna; Gaea; Hera; Hermes; Io.

Argus (C) *Argos* (Greek)

Builder of the magic ship, Argo. An Argonaut. Argus is the son of Argeia who was the wife of Polybus. He was a Thespian who was asked by Jason to build a ship capable of carrying his men on the journey to retrieve the Golden Fleece. Argus built the famous Argo, a fifty-oared ship empowered with magic from Athene's beam in the prow built from Zeus's oak tree. Argus joined the crew and became an Argonaut for the famous expedition. *See also* Argonauts; Golden Fleece; Jason.

Argus (D) (Greek)

Argus (D), the oldest son of Phrixus and Chalcipe, persuaded his grandfather, Aeetes, to give the Golden Fleece to Jason. In an escape, he was rescued by the Argonauts. It is thought by some that Argus was the father of Magnes, the human magnet, and not Aeolus. *See also* Aeetes; Golden Fleece; Jason; Magnes, Medea; Phrixus.

Argus (E) (Greek)

The son of Jason and Medea. It was thought that he was murdered by his mother. *See also* Jason; Medea; Phrixus.

Argus (F) *Argos* (Greek)
Faithful pet. Argus was the only one to recognize his master, the warrior Odysseus, when he returned after his twenty year sojourn. He was so delighted to see his master that he died of joy. Actaeon also had a dog by the same name. *See also* Odysseus.

Argus (G) (Greek) *see* Agenor (A).

Argyron (Greek) *see* Telchines.

Arhats (Buddhist, Taoist; China)
Also known as: *Shi-pa Lo-han.*
Protectors and instructors. Either sixteen, eighteen or five hundred spirits who protect the Buddhist religion and instruct followers in the Buddhist and Taoist law. The Arhats are usually associated with the Eight Immortals. Various names are given to these deities. Among them are Han Chung-Li, Lu Tung-pin, Chang-Kuo-Lao, Lan-Ts'ai-ho, Han Siang-Tzu, Tsao-kuo-chia, Ho-hsien-ku and T'ieh-Kuai Li (also called Li). *See also* Buddha; Chang-Kuo-Lao; Chung-Li-Ch'uan; Eight Immortals; Han Chung-Li, Han Siang-Tzu Ho-hsien-ku; Lan-Ts'ai-ho; Lu Tung-pin; T'ieh-Kuai Li; Tsao-kuo-chia.

Ari-em-ab-f (Egypt) *see* Assessors.

Ari-hes (Egypt) *see* Bast.

Ari-hes-nefer (Egypt)
Protector deity. Ari-hes-nefer's statue, in the form of a lion-headed god, was found by the entries of palaces and tombs to protect the living and the dead from evil spirits.

Ariadne (Greek)
Also known as: *Aridella.*
Goddess of dawn. Moon goddess. Fertility goddess. Vegetation goddess. She is the daughter of Minos, the king of Crete and the moon goddess, Pasiphae. Her siblings are Acacallis; Androgeus; Catreus; Deucalion; Eurydale; Glaucus; Lycastus; Phaedra; Xenodice. It was Ariadne's ball of thread that enabled Theseus to find his way out of the Labyrinth and survive certain death from the Minotaur. He married her as promised and then deserted her, leaving her on the island of Dia (Naxos). The rationale for his actions varies. Some think that she was abducted by Dionysus and died of grief, or that she was rescued by Dionysus and married him. Perhaps Thesesus abandoned her of his own free will. There is also a possibility that she married Oenarus, who was Dionysus' priest. Others say Theseus died in a storm at sea; he did not abandon her. An early story is that Artemis killed her because of something Dionysus had told her about Ariadne, or Artemis killed her while she was giving birth to twins. It is agreed that she had children by Dionysus: Ceramus, Peparethus, Phanus, and Thoas. Her other two children, Oenopion and Staphylus, are thought to be by Theseus. In another rendering of her story, Ariadne hung herself. After her death, Dionysus placed the constellation Corona Borealis, which he had given to her when they were married, in the sky in her honor. In another tradition, it is Theseus who placed this symbol of her in the heavens. After her ascension, she became known as Aridella. Her cults practiced orgiastic rites and males were sacrificed to her. The fire god Hephaistos forged her wedding tiara. The inventor Daedalus built a dance floor for her at Cnossus. Compare Ariadne to Andromeda and Medea. She is identified with Aphrodite in some areas. The ball of thread given to Theseus is compared to Clotho's thread of life. Compare to the Cymric moon goddess, Arianrhod. *See also* Daedalus; Dionysus; Minos; Minotaur; Pasiphae; Theseus.

Arianrhod *Arianrod* (Celtic)
Also known as: *Ethne* (possibly).
Moon goddess. Goddess of birth. Mistress of the Otherworld Tower of Initiation. She is one of "The Children of Don," who are children from the lineage of the ancient goddess Don who has been associated with Danu. Don is represented as the mother of the Cymric pantheon as recorded in the "Mabinogion" also known as the "Four Branches." The "Mabinogion" is a collection of stories usually called British, although most of the stories are set in Wales. She is the daughter of Don and Beli and sister of Gwydion. Her brother had offered her services to Math as his footholder, a position of honor. The stipulation was that she had to pass a virginity test. She took the test, failed, and then gave birth to two twin sons, Dylan and Llew. Either Arianrhod or Math threw Dylan into the sea where he became a sea deity. Llew was rescued by Gwydion. Humiliated, Arianrhod cast a spell on her son Llew, stating that he would never have a name, weapons, or a wife. Gwydion, with the use of magic, was able to revoke her "guise." It has been suggested that perhaps Gwydion tricked his sister into having an incestuous relationship and when she realized the circumstances, she rejected her children. Her name means "Silver Wheel." The constellation Corona Borealis is said to be named after Arianrhod and Ariadne. It is sometimes called Arianrhod's castle. Corona Borealis is also known as a purgatory. Arianrhod is described as pale and very beautiful. She is compared to the Greek Ariadne as both names link them to the spider and both are associated with Corona Borealis. *See also* Ama (A); Anu (A); Ariadne; Bile; Don; Gwydion; Llew Llaw Gyffes; Lugh; Math.

Arianrod (Celtic) *see* Arianrhod.

Ariconte *Aricoute, Arikute* (Tupi-Guarani People, Brazil)
This god of night is generally known as the twin of Timondonar (also spelled Tamendonar and Tamanduare), the god of light. They are the sons of either the culture hero Maira Ata or the mortal Sarigoys. The brothers struggle with one another daily. Once, during a quarrel, Tawenduare stamped his foot with great emphasis and caused the great deluge. All were killed except the brothers and their wives, who climbed trees in search of safety. From the survivors, the Tupinamba and the Tominu people were born. They constantly fought with one another. In some myths the brothers are opposed by a fisher deity known as Agnen. *See also* Irin Mage; Maira Ata; Monan.

Aricoute (Tupi-Guarani People of Brazil) *see* Ariconte.

Aridane (Greek) *see* Bacchus.

Aridella (Greek) *see* Ariadne.

Arikute (Tupi-Guarani People, Brazil) *see* Ariconte.

Arimans (Persia) *see* Angra Mainyu.

Arinitti (Hittite) *see* Arinna.

www.ebook3000.com

Arinna (Hittite)
Also known as: *Arinitti, Ishtar* (possibly), *Wurusemu.*
Goddess of the sun or fertility goddess. War goddess (possibly). Arinna shares the same attributes as Cybele, the mother goddess of Phrygia and Asia Minor and the Roman Ma-Bellona. As the sun goddess, Wurusemu, she was originally the goddess Hepat. She is sometimes called an aspect of Ishtar. *See also* Cybele; Hepat; Ishtar.

Arion (Greek) *see* Adrestus; Demeter; Gaea.

Arishta (India) "The Bull-fiend." *See also* Krishna.

Aristaeus *Aristaios* (Greek, Libyan)
Also known as: *Agreus, Nomus.*
Benevolent deity. Agricultural deity. Instructor of beekeeping. Protector of beekeepers. Possibly a deified man. He is the son of Apollo and Cyrene, brother of Autychus. His wife is Autonoe, the daughter of Cadmus. Their children are Actaeon and Macris. (In some versions, Aristaeus is called the son of Uranus and Ge.) He is the half-brother of Orpheus and the spouse of Autonoe. The Centaur Cheiron taught Aristaeus the art of healing. In one legend, Aristaeus was born in Libya, raised by the Horae and as a god lived on nectar. He worked as a beekeeper and cheese maker and was the inventor of bookkeeping. He fell in love with Eurydice, the new bride of Orpheus. As she was fleeing from a swarm of his bees, she was killed by a snake. His mother advised him to seek the advice of the sea god Proteus, who instructed him to sacrifice cattle in Eurydice's memory. He found new swarms of bees in the carcasses of the cattle. He disappeared near Mt. Haemus. Aristaeus is associated with Proteus. *See also* Actaeon; Cheiron; Eurydice (A); Macris.

Aristaios (Greek) *see* Aristaeus.

Aristomachus (Greek) *see* Adrestus.

Arisudana (India) "Slayer of Enemies." *See also* Krishna.

Arjuna *Arjuni, Arjunis* (Hindu; India)
Also known as: *Aindri* (possibly).
Arjuna is the third son of Pandu and one of the five Pandava princes. As a result of his virgin birth by Kunti with Indra, he is also known as Indra's son. He shared his wife Draupadi with his four brothers to honor his mother's request. His eldest brother Yudhisthira lost everything in a gambling match with his cousins, the Kauravas. Arjuna and his family were forced to spend twelve years in exile. The following year they spent in bondage as King Virata's servants. During his years in exile, he performed twelve labors. Vishnu in his sixth avatar as Parashur Rama taught Arjuna the use of weapons. He became a brilliant archer and warrior. Arjuna journeyed to the Himalayas to request celestial weapons to use in an upcoming battle against the Kauravas. From there he went on to Indra's heaven, Swarga, to improve his battle skills. In Swarga, he fought the Daityas and emerged the victor. With a celestial bow named Gandevi (also spelled Gandiva), given to him by Agni and originally owned by Soma, he fought his own father, Indra. When Indra was threatened by the indestructible demon Niwatakawaca, he sought help from Arjuna. Before doing so, he felt it necessary to test Arjuna's inner strength. He sent the beautiful nymphs Tilottama and Suprabha to tempt him during his meditation. Although they perfumed and beautified themselves, they were not successful. (Tilottama in another escapade was able to captivate the Asura brothers, Sunda and Upasunda.) In another episode, Arjuna unknowingly fought Shiva who was disguised as a Kirata. When he returned to battle the Kauravas, Krishna acted as his charioteer. Before marching into war, Krishna recited the *Bhagavad-Gita* to the hesitant soldier who was about to engage in warfare against his cousins. One of his wives was Subhadra, the sister of Krishna, with whom he had a son Abhimanyu also known as Saubhadra. He also mated with Ulupi, the Naga princess, and had a son, Iravat. They were married in her abode in Patala (the underworld). He was killed by his own son, but was revived by a Naga charm given to him by Ulupi. Some say that Arjuna is a form of Indra called Aindri. Arjuna is similar to Heracles (Greek). *See also* Abhimanya; Agni; Asuras; Bhishma; Daityas; Draupadi; Duryodhana; Indra; Jara-Sandha; Kamadhenu; Karna; Kauravas; Krishna; Kunti; Kuvera; Naga and Nagini; Pandavas; Pandu; Parashur Rama; Parikshit; Prajapati; Patala; Shiva; Soma; Subhadra; Swarga; Varuna; Vishnu; Yama; Yudhisthira.

Arjuni (India) *see* Arjuna.

Arjunis (India) *see* Arjuna.

Arkate (Etruscan)
An obscure god who cautioned Favnu against another obscure deity, the goddess Alpanu. Arkate appears as an old man in a cloak.

Arkharokh (Gnostic) *see* Pistis Sophia.

Arkheokh (Gnostic) *see* Pistis Sophia.

Arlez *Aralez* (Armenia)
Also known as: *Jaralez.*
Benevolent spirits. By licking the wounds of brave men who fell in battle, they are able to restore their lives. The Arlez are the invisible spirits of dogs. *See also* Devs.

Armaita (Persia) *see* Spentas Armaiti.

Armat (Armenia) *see* Perkunis.

Armati (Persia) *see* Armaita; Spentas Armaiti.

Armen (Semite) *see* Baal.

Armenak (Armenian)
Sky god and folk-hero. He is the son of Hayk and possibly the same as the Teutonic god, Irmin. He is similar to the hero, Aram of Armenia. *See also* Hayk; Irmin.

Arnaeus (Greek) Another name for Irus (q.v.).

Arnaknagsak (Eskimo) *see* Sedna.

Arnamentia (British) Ancient goddess of spring waters.

Arnarquagssaq (Eskimo) *see* Sedna.

Arne (Greek)
Also known as: *Melanippe*
She is the daughter of Aeolus and Hippe or Enarte. She has seven brothers and six sisters (for a list of their names, *see* Canace). She became pregnant by Poseidon when he was in the

shape of a bull. They became the parents of Aeolus II and Boeotus. *See also* Aeolus (A); Boeotus; Enarte; Poseidon.

Arohi-rohi (Maori People, New Zealand)
Also known as: *Mirage.*
Creator. He created the first woman, Ma-riko-riko (Glimmer) from the warmth of the sun. According to some he created Echo.

Aroueris (Egypt) *see* Horus.

Arpacana (Tibet) *see* Arpacanamanjusri.

Arpacanamanjusri *Arpacana* (Buddhist; Tibet)
Also known as: *Jam-pa-i-dbyans, Jam-pe-yang, Manjusri* (Tibet).
God of wisdom. He is a manifestation of Manjusri.

Arrets (Egypt) Seven halls of the underworld. *See also* Tuat.

Arsa (Syria) *see* Allat.

Arsai (Canaan, Syria, Ugarit)
Arsai is the symbol of the earth. Her sister, Pidray (meaning "mist"), is a nature goddess who symbolizes light. Another sister, Tallai, symbolizes dew and rain. They are the daughters of Baal.

Arsan Duolai (Yakut) *see* Arson Duolai.

Arsaphes (Egypt)
Also known as: *Herishef, Hershef.*
Fertility god. Known as "Lord of Awe." Arsaphes refers to the Egyptian Herishef (He Who Is Upon His Lake). Hershef appeared in Herakleopolis as an image of the sun god. He was a primitive fertility god in the form of a ram. Arsaphes was praised as a giver of sustenance. In the Ninth and Tenth Dynasty he was identified with Ra and with Osiris. The ram's head served as a symbol for worship by his followers. He is shown with a solar disc headdress or the Atef crown. He assimilated with Heracles according to Greek interpretation. *See also* Hershef.

Arsi Basum (Saora People, India)
Monkey god. *See also* Ajorsum.

Arson Duolai *Arsan Duolai, Arsan-duolai* (Yakut People, Siberia)
Also known as: *Syga Tojon, Ulu Tojon.*
Ruler of the dead or underworld deity. Arson Duolai is the king or chief of the Abasy. He is a devourer of souls and bestower of diseases, who was assuaged only by blood sacrifices. His mouth is in his forehead and his eyes are at his temples. *See also* Abaasy; Ulu Tojon.

Arta (Persia) *see* Asha Vahista.

Artemis (Greek; possibly originated in Asia)
Also known as: *Artemis Calliste* ("Artemis the Fairest"), *Artemis Caria, Artemis Caryatis, Artemis Laphria, Auge, Cynthia, Delia, Diana* (Roman), *Dictyanna, Dictynna, Diktynna, Hecate, Kalliste* (Fairest), *Lukea, Luna, Parthenos* (Virgin), *Phoebe, Pythia, Selene.*
Nature goddess. Goddess of fertility. Moon goddess. Birth goddess. Goddess of hunting. Guardian of the Forest, Lady of Wild Things. This virgin goddess is the daughter of Zeus and Leto (also known as Latona). As "Lady of the Wild Things," she was patroness of all the totem clans and was annually offered a sacrifice of animals, birds and plants, a ritual which survived the Classical time at Patrae, in Calydonia. When Oeneus, the king of Calydon, neglected to give her the proper sacrifices, she sent the Calydonian Boar to destroy his crops and plunder his land. Later she was associated with Selene (Moon) and Hecate (Night). A similar burnt offering was presented by the Curetes at Messens and yet another is recorded from Hierapolis. As Lukea, the Greeks called her "Goddess of Light." She turned Actaeon into a stag and he was killed by his own hounds. She had only one love, the hunter god Orion whom she accidentally killed with an arrow. However, in another writing, we are told that she had a scorpion sting him to death for having the temerity to touch her. Artemis withheld the wind in an attempt to prevent the Greeks from reaching Troy. Like her brother, Apollo, Artemis was adept at using the bow and arrows and had the ability to send plagues and pestilences. Attended by a train of nymphs, she ranged at night through the land hunting deer. Artemis represented the feminine principle. She presides over births. Sudden deaths of women were attributed to her arrows. Rites performed in her honor included erotic dances, the clashing of cymbals, and the sacrificing of live animals over fire. The Laconians built a temple to Artemis from which Caryatids, female statues used as columns, are named. She is often represented with a bow, arrows, and quiver attended by hounds, or in a chariot drawn by two white stags and sometimes as a young virgin wearing a short tunic. Her sacred animal is the tragelphus, which is part goat and part stag. As the Priapian Diana, she appears with male organs. She is sometimes identified with Athene, Bast, Hecat, Isis, and Nephthys. As Artemis of Ephesus she is identified with Roman Diana. Compare Artemis to Lakshmi (India). *See also* Aah; Actaeon; Admetus; Aeneas; Agamemnon; Aloeides; Alpheus; Amazons; Amphion; Ariadne; Atalanta; Britomartis; Callisto; Calydonian Boar Hunt; Car; Ceto; Curetes; Diana; Ephesus; Leto; Mama Allpa; Napaeae; Orion; Pelops; Sekhmet.

Artemis Calliste (Greek) *see* Artemis.

Artemis Caria (Greek) *see* Artemis.

Artemis Caryatis (Greek) *see* Artemis.

Artemis Laphria (Greek) *see* Artemis.

Artemis of Ephesus (Greek) *see* Artemis.

Arthur (British, Celt)
Also known as: *Artus.*
Hero. Arthur is the son of Uther Pendragon and Igerna or he is an illegitimate son or a creation of Merlin the Magician. The original tales of Arthur date to Roman times. Some identify Arthur with the word Aruthr, meaning "great." Most of the current information comes from the work of Geoffrey of Monmouth (C.E. 1147) He is related to Mordred. In some myths, he is the nephew of Merlin and creator of the "Round Table." Arthur proved his right to the throne by withdrawing the sword "Excalibur" from a rock. His sister is Morgan Le Fay. Most of Arthur's legends center around his Round Table, knights, and the Holy Grail. Arthur's wife is Guinevere. Arthur is similar to

www.ebook3000.com

Years later, when he was a student in Hong Kong excelling in track and field events, a senior classmate named Cheng Sue-Sue introduced him to his first esoteric teacher and Taoist Master, Master Yi Eng (I Yun). At this point, Master Chia began his studies of the Taoist way of life in earnest. He learned how to circulate energy through the Microcosmic Orbit and, through the practice of Fusion of the Five Elements, how to open the other Six Special Channels. As he studied Inner Alchemy further, he learned the Enlightenment of the Kan and Li, Sealing of the Five Senses, Congress of Heaven and Earth and Reunion of Heaven and Man. It was Master Yi Eng who authorized Master Chia to teach and heal.

When Mantak Chia was in his early twenties he studied with Master Meugi in Singapore, who taught him Kundalini, Taoist Yoga and the Buddha Palm. He was soon able to clear blockages to the flow of energy within his own body. He learned to pass the life force energy through his hands also, so that he could heal Master Meugi's patients. He then learned Chi Nei Tsang from Dr. Mui Yimwattana in Thailand.

A while later, he studied with Master Cheng Yao-Lun who taught him the Shao-Lin Method of Internal Power. He learned the closely guarded secret of the organs, glands and bone marrow exercise known as Bone Marrow Nei Kung and the exercise known as Strengthening and Renewal of the Tendons. Master Cheng Yao-Lun's system combined Thai boxing and Kung Fu. Master Chia also studied at this time with Master Pan Yu, whose system combined Taoist, Buddhist and Zen teachings. Master Pan Yu also taught him about the exchange of Yin and Yang power between men and women, and how to develop the Steel Body.

To understand the mechanisms behind healing energy better, Master Chia studied Western anatomy and medical science for two years. While pursuing his studies, he managed the Gestetner Company, a manufacturer of office equipment and became well acquainted with the technology of offset printing and copying machines.

Using his knowledge of Taoism, combined with the other disciplines, Master Chia began teaching the Universal Tao System. He eventually trained other Instructors to communicate this knowledge and he established the Natural Healing Center in Thailand. Five years later, he decided to move to New York, where in 1979, he opened the Universal Tao Center. During his years in America, Master Chia continued his studies in the Wu system of Tai Chi with Edward Yee in New York.

Since then, Master Chia has taught tens of thousands of students throughout the world. He has trained and certified over 1,200 instructors and practitioners from all over the world. Universal Tao Centers and Chi Nei Tsang Institutes have opened in many locations in North America, Europe, Asia, and Australia.

In 1994, Master Chia moved back to Thailand, where he had begun construction of Tao Garden, the Universal Tao Training Center in Chiang Mai.

Master Chia is a warm, friendly and helpful man who views himself primarily as a teacher. He presents the Universal Tao System in a straightforward and practical manner, while always expanding his knowledge and approach to teaching. He uses a laptop

Mercury Artaeus (Gaul). His final resting place is in Avalon. *See also* Adder; Vivien.

Artimpaasa (Sythian) Ruler of the moon. Goddess of love.

Artinis (Armenian, but probably originally from a prior civilization called Urartians [from the Assyrians]).
Sun god. Artinis is one of a triad of early gods with Khaldi (high god or moon god) and Theispas (weather god). They are possibly the forerunners of Babylonian Shamasa; Sin, and Ramman (qq.v.). *See also* Khaldi; Theispas.

Artio (Celtic)
Goddess of wildlife, who appeared as a bear. She may have been the spouse of Essus. Artio was also worshiped at Berne (meaning "bears") in Switzerland.

Artus (British) *see* Arthur.

Aruna *Arushi* (Plural), *Rumar* (Hindu; India)
Aruna is the dawn god and charioteer of the sun. With Garuda, they are the horses that draw Surya's or Vishnu's chariot. Aruna is also called Rumar the son of Kasyapa. He is sometimes shown as a bird. The name means red, rosy-colored, ruddy or tawny. *See also* Garuda; Kaspaya; Surya; Vishnu.

Arundhati (India)
"The Morning Star." One of the Krittika sisters, and the faithful spouse of Vasistha. *See also* Karttikeya; Rishi; Vasistha.

Aruru (Assyro-Babylonia, Chaldea, Sumer)
Also known as: *Belet-ili, Mami, Ningal, Ninhursag, Ninmah, Nintue.*
Mother Goddess. Goddess of Creation. Earth goddess. This goddess helped Marduk mould the first human and create mankind. In one version, at the request of the gods, Aruru molded Enkidu (or Esbani) from mud or clay to be the rival of Gilgamesh. She was also the creator of Gilgamesh by some accounts. Aruru is the personification of earth. In the Sumerian version, at Nippur, it was the earth goddess Aruru or Mami who was said to have created men from clay. Some say Aruru was the sister or wife of Enlil. She might have been given the additional title of "Goddess of Childbirth." Her son or husband might have been Nesu. She is sometimes identified with the Sumerian earth mother, Ki, and sometimes Nammu. Sometimes she is said to be the sister of Enlil. Aruru is possibly identified with Mah or Belit-ili. *See also* Belit; Mah (B); Mami; Marduk; Nammu; Ningal, Ninhursag; Ninlil; Ninmah; Ninsun; Nintu.

Arushi (India) *see* Aruna.

Arusyak (Persia) *see* Anahit; Vahagn.

Arvak (Teutonic) *see* Aarvak.

Arvakr (Teutonic) *see* Arvak.

Arya Achalanatha (Japan) *see* Fudo-Myoo.

Arya Sarasvati (Tibet) *see* Sarasvati.

Arya Tara (Nepal)
Protector goddess. Arya Tara is from the group of twenty-one Green Taras. She protects mortals from the eight evils: fire, theft, lightning, flood, earthquake, enemies, famine and untimely death. Arya Tara is depicted sitting gracefully in the Ardhapayanka position. *See also* Tara.

Aryaman (Persia)
Also known as: *Ahriman, Ahrimanes.*
Might be a god of marriage. He is the third member of the Aryan trinity (the Adityas), with Mitra and Varuna. In one rendition he is known as the evil prince of the kingdom of darkness. In another, Aryaman is an Aditya, the son of Aditi, the Mother of All Gods. His name means "Bosom Friend." Aryaman brings sacrifices to fruition. He is associated with Ohrmazd and is said to be his elder twin. Each controls the world for 6,000 years. Aryaman is identical to Angra Mainyu. *See also* Aditi; Adityas; Armenak (Armenian); Ariman; Mitra; Surya; Vahagn; Varuna.

Aryong-Jong (Korea) Goddess of rainfall.

Asa (A) (Persia) *see* Asha Vahishta.

Asa (B) (Teutonic) *see* Bifrost.

Asa Poorna (India) *see* Shakti.

Asabru (Teutonic) *see* Bifrost.

Asag (Sumer) Underworld demon. *See also* Ninurta.

Asaheim (Teutonic) *see* Asgard.

Asakku (Assyro-Babylonia) *see* Lahamu and Lahmu.

Asama (Japan) *see* Sengen.

Asamanjas (India) *see* Sagara.

Asapishachikis (India) Female Demons. *See also* Pishacha.

Asar (A) *Asir* (Egypt)
Also known as: *Osiris.*
Aspect of a god. One of the gods in the Pyramid Texts. An aspect of Osiris. Similar to Assur (Assyrian), Asari (Babylonian), Azur (Hebrew) Aesir (Teutonic). *See also* Marduk.

Asar (B) (Babylonian) *see* Marduk.

Asar-Apis (Egypt) *see* Serapis.

Asar-hap (Egypt) *see* Serapis.

Asar-Hap (Greek, Egypt) *see* Apis (A); Serapis.

Asar-Hapi (Greek, Egypt) *see* Apis (A); Serapis.

Asarhap (Egypt) *see* Serapis.

Asari *Asarri* (Assyro-Babylonia)
Originally a Syrian god of agriculture, Asari later became confused with Osiris (q.v.). *See also* Ea; Marduk.

Asarri *Asaru* (Babylonian, Sumerian) *see* Marduk.

Asartaiti (Egypt) *see* Osiris.

Asaru (Babylonia) *see* Marduk.

Asarualim (Babylonia) *see* Marduk.

Asarualim Nunna (Babylonia) *see* Marduk.

Asaruludu (Babylonia) *see* Marduk.

A'sas (Teutonic) *see* Aesir.

Asase Efua (Africa) *see* Asase Yaa.

Asase Ya *Asae Yaa* (Ashanti People, Africa)
Also known as: *Aberewa, Asase Efua.*
Asase Ya, "Old Woman Earth," is the great goddess who created humanity and at death returns them to her fold. The earth, and specifically the plowed field, is her temple. A goddess of fertility, the farmers pray to her and their ancestors at planting. She is mate of Nyame and Mother of the Gods. Her name-day is Thursday and is considered a sacred day of rest. She is petitioned when land is cultivated or when a grave must be dug. Some say she is androgynous. *See also* Abosam; Nyame; Tano.

Asbet (Egypt)
In the Pyramid Texts she is associated with Isis and Nephthys.

Asbru (Teutonic) *see* Bifrost.

Ascalaphus (A) (Greek)
An Argonaut. He was the co-ruler of Orchomenus with his brother, Ialmenus. Both men were suitors of Helen of Troy. They took thirty ships to Troy. Their parents are Ares and Astyoche. *See also* Ares; Argonauts; Ialmenus.

Ascalaphus (B) (Greek)
His parents are the river god Acheron and Gorgyra or Orphe. When it was learned that he had spied on Persephone, he was turned into an owl by Demeter. *See also* Acheron; Demeter; Persephone.

Ascanius (Greek)
Another name for Iulus (q.v.). *See also* Aeneas.

Ascension, The (Islamic) *see* Mohammed.

Asclepius *Aeculapius, Aesculapius, Ascalaphus, Asklepios, Esculapius* (Greek, known in Carthage; possibly originated in Egypt)
Also known as: *Eshmun* (Carthage).
God of healing and medicine. Physician for the Argonauts. Deified mortal. Asclepius is the son of Apollo and the nymph Coronis or possibly Arsinoe. He might be the son of Acheron and Orphne. He married Epione, the daughter of Merops. His daughters are Acesis (meaning "remedy"), Aegle, Iaso (cure), Janiscus, Hygieia (health) and Panacea (all-healing). His sons are Machaon and Podalirius. As an infant, his mother was burned to death for adultery. Asclepius was saved from the flames by a dog. Later, he learned the art of healing from the Cheiron the Centaur. Zeus, fearing that mortals would be revived from death, threw a thunderbolt at Asclepius and killed him. In one tale, Asclepius was able to copy Apollo and bring the dead back to life. The ruler of the underworld, Cronus, worried that Asclepius would depopulate Hades, was frantic. So, the great god Zeus was about to hurl his thunderbolt at Asclepius when Apollo interceded and pleaded for Asclepius. Instead of murdering him, Zeus relented and placed Asclepius among the stars as Serpentarius the snake-bearer. His staff with coiled snakes is our modern day symbol of medicine. He later became a god of medicine with the symbol of a snake. There are tales that indicate that he was loved by the Phoenician goddess and Mother of Gods, Astronoe. Sometimes he is shown as a serpent, but more often as a benign middle-aged man. Sometimes he is with the dog Cerberus, who is at his feet. The staff is his attribute (as it is for Bacchus Dionysus, Hermes, and Mercury). The dog is the sacred animal of Asclepius, who was said to have been raised by a bitch. The animal symbolizes fidelity and love. In past days, followers offered sacrifices to dogs in his temples. The tongue of the dog was thought to have healing properties. To dream of a dog signified a cure for the follower. He is sometimes confused with the Egyptian god Serapis. The Greeks say this god is identified with a son of Ptah, Imhoteph. He is associated with Persephone and Demeter. He is sometimes identified with Eshmun. Compare Asclepius to the twin Vedic healers, the Asvins. *See also* Acheron; Astronoe; Athene; Cerberus; Dia'necht (Celtic); Eshmun; Fates; Lycurgus (A); Serapis.

Asdar (Sumer) *see* Ashdar; Astarte.

Aser (Hebrew) *see* Asherah.

Aset (Greek) Greek rendering of Isis.

Asfandarmad (Persia) *see* Spentas Armaiti.

Asgard (Norse; Teutonic)
Also known as: *Asaheim.*
The dwelling place of the Aesir (gods) known as Asgard is located in Midgard, the middle earth. Gladsheim Castle, built by the gods, is located in Asgard. Inside is the great banquet hall of Valhalla with thrones for Odin and the twelve highest gods. It has 640 doors and 960 warriors can walk abreast through each door. The ceiling is made of spears and the roof of shields. The hall and everything in it is solid gold. The twelve Aesir (gods) and twenty-four Asynjur (goddesses) assemble in the hall at the bidding of Odin. In one myth, Lidskjalv, Odin's throne, is located in the meadow Idavollen. Frigga and other goddesses have their own hall known as Vingolv (Hall of Friendship). Another hall for the gods, known as Valaskjalv, is covered with silver. Jotunnheim, the home of the giants; Svartheim, the home of the dark elves; and Mannheim, the home of mortals, are all a part of the Norse world. The Bifrost, also known as the Rainbow Bridge, connects the Norse world to the outside world. *See also* Aesir; Alfheim; Bifrost; Valaskjalv.

Asgaya Gigagei (Cherokee People, North America)
Also known as: *The Red Man, The Red Woman.*
Asgaya Gigagei is a bisexual thunder deity.

Ash (Egypt of foreign import)
Also known as: *Lord of the Land of the Olive Tree, Lord of the Land of Tehennu.*
A minor three-headed deity: lion, vulture, and snake. He is mentioned five times in inscriptions from the eleventh to the eighteenth dynasty. In the fifth dynasty, he was known under the names noted above.

Ash-hrau (Egypt)
Five headed-monster serpent in the sixth sector of Tuat. Its body is twisted so that its tail almost touches one of its heads. *See also* Tuat.

www.ebook3000.com

Ash of Uisnech (Celtic) *see* Abellio.

Ash-Vahishta (Persia) *see* Asha Vahishta.

Asha (Persia) *see* Asha Vahishta.

Asha Vahishta (Persia) *Ash-Vahishta, Asha Vahista*
Also known as: *Arbidihist* (Pahlavi), *Ardabahisht, Ardibahisht, Asa, Asha, Arta, Rta* (Old Persian).

The most beautiful of the Amesha Spentas, Asha Vahishta is representative of divine law, good thought, and moral order in the world. The protector of fire, and the protector of the physical and moral world against demons. In hell Asha Vahista assures that mortals do not suffer more punishment than they deserve. Believers say that all who do not know Asha Vahishta are outside the whole order of god and therefore must forfeit heaven. Asha's chief opponent is Indra (known in the Avesta as Andra), who represents the Spirit of Apostasy. Asha Vahishta is associated with the Yazatas (q.v.). *See also* Ahura Mazda; Amesha Spentas; Angra Mainyu; Avesta; Daevas; Vohu Manah.

Asha Vahista (Persia) *see* Asha Vahishta.

Ashanti People — Creation Legend (Africa) *see* Adu Ogyinae.

Asharu (Babylonia) *see* Marduk.

Ashdar *Asdar, Ashtar, Astar, Athtar;* (Akkadian, Arabic, Semitic, Sumerian)
Mother goddess. She was originally a Sumerian deity who was adopted by the Akkadians. She is likely from the South Arabian god Athtar which was the name of the planet Venus. The only Semitic name in early history of a deity was Asdar. The South Arabians speak of Astar or Athtar which meant Venus. Ashdar may have been the original creator deity of the Semitic people of that region. Possibly a moon goddess. She could be a mother goddess of the Abyssinians and mother/sister/wife of Tammuz. Ashdar is associated with Shamash. Possibly identified with Innini and Ishtar. *See also* Athtar; Babbar; Utu.

Ashem (Egypt)
One of the messenger gods mentioned in the Pyramid Texts.

Ashemu *Ashen* (singular) (Egypt)
They are a class of beings associated with Heru, the hawk god and Sekhem. The Ashemu are sometimes referred to as the form in which a god is visible. *See also* Afa; Henmemet; Unas; Utennu.

Ashen (Egypt) *see* Ashemu.

Asher (Hebrew) *see* Asherah (B).

Ashera (Hebrew) *see* Anat; Asherah (B).

Asherah (A) (Phoenician) *see* Hathor.

Asherah (B) *Asher, Ashera, Aser* (Assyria, Canaanite, Phoenician, Ugarit; Mesopotamia)
Also known as: *Achtaroth; Achtoret; Anath-Yahu, Asherat; Ashertu; Asirat* (Hittite); *Asirtu; Asratu; Assir; Astar; Astarte* (Phoenician); *Astert; Astirati; Astereth; Ashtoreth* (Phoenician); *Athrar; Ess-eorradh* (Celtic); *Istar* (Akkadian); *Kaukabhta* (Syrian).

Mother goddess. Fertility goddess. National goddess of Sidon. Originally, she was the wife of the father god, El. She is often shown nude and holding her breasts. Her hair is done in two long ringlets (attributes of the goddess Hathor). A number of oval pottery plaques show her nude figure holding lily stalks or serpents similar to the poses of the Egyptian deity Hathor. She is identified with Venus (Greek), Ishtar (Babylon), and Isis (Egypt). She is sometimes identified with the goddess Astarte as Kaukabhta (Syrian), and Anahit (Armenian). *See also* Anat; Astarte; Baal; El; Qadesh.

Asheratian (Ugarit) *see* Astarte.

Ashertu (Middle East) *see* Asherah (B).

Ashi Vanguhi (Persia) *see* Yazatas.

Ashima (Egypt, Sumeria) *see* Amathaounta.

Ashir (Assyria, Sumer) *see* Ashur.

Ashmadai (Middle Eastern) *see* Asmodeus.

Ashnan (Chaldea, Sumer)
Ashnan, the goddess of grain, is a kind and bountiful deity sent to earth by Enki. She, along with Lahar, Ningizzida, Ninsar and Siris, were created at the same time by either Anu or the gods he created. In some myths, the god of wisdom, Enki, suggested to Enil that he create Ashnan and Lahar. Ashnan and Lahar, the cattle god, were created to control the crops and cattle and to supply food and drinks to the gods. One day they imbibed heavily and were unable to carry out their duties. Mortals were formed to take over their chores. Ashnan is similar to the Chaldean goddess of grain, Nisaba (not to be confused with Nisaba the architect goddess). *See also* Ea; Enki; Enlil; Lahar; Nisaba.

Ashrapa (India) "Drinkers of Blood." *See also* Dakinis.

Ashshur (Assyria, Sumer) *see* Ashur.

Ashtareth (Babylonia, Canaan, Semite) *see* Ashtoreth.

Ashtaroth (Palestinian, Syrian) *see* Astarte; Chaos; Ishtar.

Ashtart (Phoenician) *see* Astarte.

Ashtoreth *Ashtareth* (Babylonian, Canaanite, Semitic)
Also known as: *Alidat, Alittu, Belit, Mylitta.*

Earth goddess. Alittu and Alidat were originally titles of Ishtar as a Babylonian mother goddess. Later it became Mylitta, then Ashtoreth. The name Mylitta was used by the Assyrians for Aphrodite. *See also* Astarte; Belit; Ishtar.

Ashur *Anshar, Anshur, Ashir, Ashshur, Asur, Asshur, Assur, Azur* (Assyria, Sumer)
Chief deity. A creator god with many powers. He was the National God of Assyria known originally as Ashir. According to some, his attributes were borrowed from the Sumerian gods Enlil and Marduk. He has the attributes of Anu and is similar to Yahweh. Ashur is a dragon slayer and a warrior. Sometimes Belit is his consort. Ashur is the Lord of the Four Cardinal Points. He is a god of four faces: the bull, eagle, lion, and man. Sometimes he is depicted standing above a bull, sometimes as a huge winged god wearing bracelets and carrying a basket and arrows. His emblems are the winged disk, the fir cone, and the bow and arrow. *See also* Anshar; Ashur; Ashura; Marduk; Tiamat.

Ashura (Canaanite, Semitic)
A goddess who is thought to be the wife or mate of Yahweh (q.v.).

Ashvamukhi (India)
"Horse-face." *See also* Yaksha and Yakshini.

Ashvatthaman (India) *see* Duryodhana; Parikshit.

Ashvins (India) *see* Asvins.

Ashwins (India) *see* Asvins.

Ashyggr-drasil (Teutonic) *see* Yggdrasil.

Asi (India) Sacred Sword. *See also* Brahma.

Asi-na-duti (Japan) *see* Kushi-nada-hime.

Asia (A) (Greek) Another name for Hesione (q.v.).

Asia (B) (Greek)
An Oceanid. She is the daughter of Oceanus and Tethys. *See also* Oceanids.

Asiaq (Eskimo)
This goddess, who was originally human, is the spirit of the weather. She is one of the triad of spirits with Pinga and Sila. She produces thunder by rubbing two pelts together and brings rain by shaking out a pelt dipped in urine (thunder). *See also* Pinga; Sila.

Asir (Egypt) *see* Asar (A).

Asirat (Middle East) *see* Asherah (B).

Asiri (Egypt) *see* Osiris.

Asitanga (India) "With Black Limbs." *See also* Shiva.

Ask *Askr* (Norse; Teutonic)
In the Norse creation myth, Ask is one of two trees or blocks of wood, possibly from an Ash tree, that were used by Odin, Ve, and Vili to carve the first mortals. (The word Ash is frequently used as a prefix to the tree of life, Yggdrasil [q.v.].) The first male was named Ask and the female, Embla. Odin gave them breath and life, Vili gave them understanding, and Ve gave them human senses and attributes. In a variation of this myth, Ask and Embla were saved by Odin and his brothers during the great deluge. *See also* Embla; Midgard; Odin; Ve; Vili; Ymir.

Askefruer (Danish) Forest spirits who cure diseases.

Asken (Egypt) One of the gods in the Pyramid Texts.

Asklepios (Greek) *see* Asclepius.

Askr (Teutonic) *see* Ask.

Asman (Persia) *see* Khshasthra Vairya.

Asmegir Citadel (Teutonic)
Home of deities. This citadel had eight architects, all dwarfs, to design it. Presently, it is guarded by the dwarf Delling. Asmegir is also the name of the spirits who dwell with Balder.

Asmodeus (A) (Arabic, Hebrew)
Also known as: *Ashmadia.*
Demon. He probably originated from the demon of Arabia named Aeshma-deva. He is the lame, demon husband of Sarah who was the daughter of Raguel. As Ashmadia, he was said to have made Noah drunk. In legend he killed Sarah's seven bridegrooms, then he fled to Egypt where he was bound by the angel Raphael. In another legend he was captured by Solomon. *See also* Aeshma.

Asmodeus (B) (Semitic)
Spirit of lust. Asmodeus is the beautiful goddess daughter of the fallen angel Shamdon and sister of Tubal-Cain.

Asogguano (Yoruba People, Africa)
Representative of health matters and epidemics. *See also* Olodumare.

Asoka (India) Shiva's sacred plant. *See also* Shiva.

Asopus (A) (Greek)
River god. Asopus is the son of Oceanus and Tethys and the brother of the three thousand river gods, known as Rivers, and the three thousand goddesses known as Oceanids. A river god of Boeotia, he married Metope, and they became the parents of twelve or twenty daughters and two sons. Some of the daughters are Aegina, Cleone, Corcyra, Salamis, Sinope, Thebe. Their sons are Ismenus and Pelasgus. Under false guise, Zeus seduced, abducted and impregnated Aegina. Asopus went to Corinth in search of his daughter. Sisyphus, who knew what had happened, would not reveal it to the distraught father until he promised to produce a spring of water behind Aphrodite's temple. Asopus produced the spring, known as Peirene, found that the culprit was the great god Zeus, and went in pursuit of him. He attempted to make Zeus accountable for his actions but the powerful deity, Asopus with his famous thunderbolts, drove to his river bed and subsequently punished Sisyphus for betraying him. To compare to other Greek river gods, *see* Achelous, Acheron, Alpheus, Cephissus, Cocytus, Inachus, Oceanids, Oceanus, Rivers, Tethys. *See also* Aeacus; Aegina; Antiope; Oenamaus; Sinope; Sisyphus.

Asopus (B) (Greek) He is the son of the sea god Poseidon and Eurynome.

Aspelenie (Lithuanian)
Aspelenie is a household goddess who rules the area behind the cooking range. She appears as a small, harmless snake who can keep the area free from rodents and can be treated as a pet.

Asrafel (Mohammed) *see* Gabriel.

Asrapa (India) *see* Dakinis.

Asratu (Middle East) *see* Asherah.

Asri (India) Goddess of fortune.

Ass (Egypt)
Another name for the sun god Ra, who in this form, was devoured by a gigantic serpent.

Assara Mazaas (Persia)
Creator god of Ashurbanipal. *See also* Ahura Mazda.

Assarac (Assyrian)
Little known except this deity was worshiped on a mound called Birs.

Assaracus (Greek) *see* Anchises.

www.ebook3000.com

Assessors (Egypt)
Also known as: *Forty-two Assessors or Judges.*
Assessors or judges of dead souls. The Forty-Two Assessors were located in the Judgment Hall (also known as the Hall of the Maati Goddesses). Twenty-one assessors lined either side of the wall and heard the Negative Confessions of the deceased soul. The confessions were forty-two denials declaring that the deceased had not committed certain "sins" during his or her lifetime. The names of the Assessors according to the "Papyrus of Nebsent" in the British Museum are Usekht-nemmat, Heptshet, Fenti, Am-khaibetu, Neha-hau, Rerti, Maati-f-em-tes, Neba-per-em-khetkhet, Set-kesu, Uatch-nes, Qerti, Hetchabehu, Am-senf, Am-beseku, Neb-Maat, Thenemi, Aati, Tutu-f, Uamemti, Maa-an-f, Heri-seru, Khemi, Shet-kheru, Nekhen, Ser-kheru, Basti, Hra-f-ha-f, Ta-ret, Kenemti, An-hetep-f, Nebhrau, Serekhi, Neb-abui, Nefer-Tem, Tem-sep, Ari-em-ab-f, Ahi-mu, Utu-rekhit, Neheb-nefert, Neheb-kau, Tcheser-tep, An-a-f. *See also* Maat; Negative Confessions; Tuat.

Asset (Egypt) *see* Aaru.

Asshur (Assyria, Sumer) *see* Anshur; Assur.

Assorors (Sumer) *see* Anshar.

Assorus (Babylonia) *see* Anu (C); Belus (B).

Assur (Assyria, Sumer) *see* Ashur.

Assuras (India) *see* Asuras.

Assyro-Babylonian — Creation Legend (from the Tablets of Ashurbanipal) *see* Apsu; Bel (B); Tiamat.

Ast (Egypt)
One of the gods in the Pyramid Texts. *See also* Aai; Astarte.

Astaik *Astik* (Armenian, Semitic, Syrian)
Also known as: *Aphrodite.*
"Little Star." She is the spouse of Ba'al Shamin. Vahagn, the god of fire, abducted her. In later Armenian tales, Astaik is identified with Arusyak ("Little Bride"). Astaik is also a title of Anahit (q.v.). She is thought to be a rival of Anahit and Nana. She might represent the planet Venus. *See also* Astarte; Baal Shamin; Ishtar; Nana; Vahagn.

Astamatrikas (Hindu; India)
Also known as: *Saktis.*
In Hindu mythology, the Astamatrikas are divine mother goddesses. They are known as Saktis when they are seven or ten in number. When they are eight in number they are called Astamatrikas.

Astanpheus (Gnostic) *see* Astaphaeus.

Astaphaeus (Ophite of the post-Christian gnostics)
Also known as: *Astanpheus, Astaphaios.*
Possibly another name for Yahweh. He is associated with the seven spheres of the planets: Adonai, Ailoaios, Astaphaios, Horaios, Ialdabaoth, Iao and Sabaoth. *See also* Yahweh.

Astaphaios (Gnostic) *see* Astaphaeus.

Astar (Sumer) *see* Ashdar; Asherah (B).

Astarete (Phoenicia) *see* Astarte.

Astarte *Astar, Ashtart, Astart* (Greek), *Astarete, Astartu.* (Assyro-Babylonia, Canaan, Carthage, Egypt, Phoenicia, Sumer, Syria)
Also known as: *Ah* (Egypt), *Ast* (Egypt), *Ashdar, Asherah, Ashtareth* (Babylonia), *Asherah, Asheratian* (Ugarit), *Ashtaroth, Ashtoreth* (Hebrew), *Astoreth, Innini* (possibly), *Ishtar* (Babylon), *Kaukabhta* (Syrian), *Qadesh, Qedeshet* (Semite).
Astarte is a goddess of love, battle, war, sex, fertility and maternity. She is the Near Eastern mother goddess worshiped in Egypt in the Eighteenth Dynasty, possibly in relation with Seth and thought to be the daughter of the sun god Ra or Ptah. She is both a mother goddess and a warrior goddess. Astarte is said to be the sister of Anat and Baal. She is the sister and bride of Tammuz. Some say she was worshiped in Egypt as the goddess Ah or Ast (Isis). Her origin might go back as far as the goddess of Sumer, Innini. She could be a goddess of harlots since one of her titles is Qadesh which is similar to the Babylonian Qadishtu, a word for harlot. The singular of the name Ashtaroth is Asthoreth and is a title (meaning "Lady") of the ancient Semitic deities, and similar to that of Baal or Baalim, which means "lord." She is identified with the planet Venus. Babylonian astronomers charted her changes from a morning to an evening star. She was shown with the head of a lioness topped by the disk of the sun. She drove a chariot pulled by four horses. Sometimes Astarte was shown armed with a shield and club, riding a horse into battle. Sometimes she is depicted with the head of a cow or bull. In Egypt she appears naked riding bareback on a horse wearing the Atef-crown and carrying weapons. She also appears sketched on limestone flakes possibly by workers in the Necropolis. She is possibly derived from the Phoenician goddess Tanit. Sometimes she is confused with Hathor and Isis. There are some writers who say the Canaanite gods Adon, Eshmun, Kemosh and Melquart were regarded as brothers, sons, or husbands of Astarte who was then considered as an earth goddess. She corresponds to the early Arabian male deity, Athtar. Astarte is also identified with Aphrodite and Mylitta and sometimes Tyche. She is also identified with the deities Istaru of the Assyrians and Ashtoreth of the Hebrews. Compare her to Hathor, Isis and Tanit. *See also* Adon; Allatu; Anat; Asherah (B); Ashtoreth; Athar (B); Baal; Chemosh; Ishtar; Isis; Qadesh; Tyche.

Astartu (Phoenicia) *see* Astarte.

Asten (Egypt) *see* Aani; Thoth; Utennu.

Aster paeus (Greek)
He is the son of Pelagon who was killed in the Trojan War by Achilles.

Asteria (A) (Greek)
Her parents are the Titans Phoebe and Coeus. She is the sister of Leto (also known as Latona). She married Perses, the Titan son of Crius and Eurybia. Asteria committed suicide by drowning and was turned into a quail. *See also* Ceos; Leto.

Asteria (B) (Greek)
She is one of the fifty daughters of Danaus, known as the Danaids. *See also* Danaus.

Asterie (Greek) *see* Ares.

Asterion (A) (Greek)
River god. He is the son of Oceanus and Tethys. In a contest between Hera and Poseidon, the judges were Asterion, Cephissus and Inachus. The Asterion river was in Peloponnesus. *See also* Hera; Inachus; Poseidon; Rivers.

Asterion (B) (Greek)
An Argonaut, he is the son of Cometes and Antigone, the daughter of Pheres. *See* Argonauts.

Asterios (Greek) *see* Minotaur; Zeus

Asterius (A) (Greek)
King of Crete. He adopted Minos, Rhadamanthys and Sarpedon, the sons of Zeus and Europa. *See also* Argonauts; Europa; Minos; Minotaur; Sarpedon (A).

Asterius (B) (Greek)
"Star." Another name for the Minotaur (q.v.).

Asterius (C) (Greek) Another name for Asterion.

Asterius (D) (Greek) The Argonaut brother of Amphion.

Asterodeia (Greek)
A nymph, she is the first wife of Aeetes, the king of Colchis, and the mother of Chalciope (also known as Iophossa). *See also* Aeetes; Apsyrtus.

Asterope (A) (Greek)
An epithet of Sterope (q.v.). *See also* Ares; Oenamaus; Sirens.

Asterope (B) (Greek)
She is the wife of Hippalcimus and mother of Penelaus, the Argonaut.

Asterope (C) (Greek)
She is the daughter of the river god, Cebren, and the wife of Aesacus.

Asteropeia (Greek) *see* Actor.

Astert (Assyro-Babylonian) *see* Asherah (B).

Asthertet (Egypt)
Associated with the goddess Hathor, she is known as "The Mistress of Horses." *See also* Hathor.

Asti (Egypt) A name given to Thoth by the sun god Ra.

Astik (Middle East) *see* Astaik.

Astika (India)
Astika, a sage, is the son of the serpent goddess Manasa. Injury or death by a snake bite can be avoided by uttering Astika's name when bitten. *See also* Manasa; Takshaka.

Astioche (Greek)
It was either Astioche or Axioche who was the mother of Chrysippus who was murdered either by his half-brothers or by Hippodameia, the wife of Pelops. *See also* Danaus; Hesione; Pelops.

Astirati (Middle East) *see* Asherah (B).

Astoreth (Phoenician) *see* Asherah (B); Astarte.

Astovidad (Persian) Demon of Death *see* Varuna (India).

Astraea (Greek)
Also known as: *Dike, Virgo.*

Goddess of justice. Astraea is the daughter of Zeus and Themis, who was also the personification of justice. Astraea's sisters are the Horae and the Moirai. Astraea, fed up with mortals, left the earth during the bronze and iron ages. She is now seen as Virgo in the heavens. *See also* Ceos; Dike; Horae; Justitia; Moirai; Themis.

Astraeus (Greek)
He is the Titan son of Crius and Eurybia. His brothers are Pallas and Perse. With Eos, the goddess of dawn, he became the father of all the stars and the winds: Boreas, Hesperus, Notus, Phosphorus, Zephyrus, and perhaps Aura. *See also* Boreas; Eos; Notus; Zephyrus.

Astrerodeia (Greek)
She is the nymph wife of Aeetes and mother of Chalciope. *See also* Apsyrtus.

Astronoe (Phoenician)
She turned Eshmun into a god using generative heat. *See also* Asclepius; Cybele; Eshmun.

Astrope (Greek)
One of the sun god Helius' horses who pulled the chariot Quadriga through the sky. *See also* Helius.

Astydameia (A) (Greek)
Pelops and Hippodameia are her parents. She married Acastus and became the mother of Laodamia, Sterope, Sthenele and sons who are not named. It appears that she fell in love with Peleus, the king of the Myrmidons, and Argonaut, who ignored her. Slighted, she took revenge and in the end was cut into pieces by her would-be lover. For a list of her siblings *see* Pelops. For details regarding her attack on Peleus, *see* Acastus. *See also* Peleus.

Astydameia (B) (Greek)
Also known as.

Her parents are Amyntor and Cleobule. Her siblings are Crantor and Phoenix. By Heracles, she could be the mother of Ctesippus and Tlepolemus.

Astynome (Greek)
Her parents are Talaus the Argonaut and Lysimache or Lysianassa. She married Hipponous, the king of Olenus, and became the mother of Capaneus, one of the Seven against Thebes and Periboea. *See also* Adrestus; Capaneus; Hipponous.

Astyoche (A) (Greek)
Daughter of Laomedon and Strymo, or daughter of Actor. *See also* Actor (C).

Astyoche (B) (Greek)
The daughter of the river god, Simoeis, she married Erichthonius, who at the time was the richest man in the world. Their son was Tros, the eponym of Troy. *See also* Ares; Erichthonius.

Astyoche (C) (Greek) Daughter of Crisus (q.v.).

Astyoche (D) (Greek)
Daughter of Phylas. Mother of Tlepolemus by Heracles.

Asu-Niti (India) *see* Yama.

Asu-su-namir (Assyro-Babylonian) *see* Asushunamir.

Asur (Sumer, Assyria) *see* Ashur.

www.ebook3000.com

Asura (Persia) *see* Ahura Mazda.

Asuras *Assuras*

Also known as: *Ahura Mazda, Asuris* (female Asuras), *Danavas, Hormusda* (Mongolian); (Vedic; India).

In the Vedic tradition, Asuras are beings who existed before the creation of our universe. Roughly translated, the name means "living power," and in ancient Vedic texts meant "god." Agni, Indra and Varuna were known as Asuras. In later times, the meaning of the word changed and the Asuras, said to be born from Brahma's hip, became enemies of the gods. The word that once meant "god" became "Sura." The Asuras, according to the Satapatha Brahmana, are descendants of Prajapati and are described as giant shape changers who can become invisible. In their constant battles with the gods, many Asuras have been killed. Shukra, the seer and son of Bhrigus, is the guru of the Asuras. He personifies the planet Venus. Jalandhara, the son of the goddess Ganga, is an Asura who married Vrinda, the daughter of a heavenly nymph. Other well known Asuras are the demons Vrita and Kansa. The Asuras live in Patala, the underworld, in surroundings said to surpass the splendor of the celestial realm. The names of their towns are Shining, Startassel, Deep and Golden. Historically, they were thought to have been connected to mining. The Asuras are associated with Karttikeya, the god of war, and Parvati. *See also* Adidti; Agni; Ahura Mazda (Persia); Amitra; Arjuna; Bhima (A); Brahma; Brighus; Daityas; Danavas; Devas (A); Devas (B); Ganga; Hiranyakasipu, Indra; Jalandhara; Kansa; Kurma; Patala; Prajapati; Rakshasa; Upasunda; Varuna; Vishnu; Vrita.

Asuris (Persia) Female Demons. *See also* Asuras.

Asus (Roman) *see* Aesus.

Asushunamir *Asu-su-namir, Asushu-namir, Uddushunamir* (Assyro-Babylonian)

The beautiful eunuch Asushunamir was created by the great god Ea for one purpose. He was to travel to the underworld to wield his charms on Ereshkigal and persuade her to release Ishtar. *See also* Ea; Ishtar; Tammuz (for a variation of this myth).

Asva (India) "The Dawn"; "The Mare." *See also* Ushas.

Asvaghosa (Buddhist; India)

Originally a Brahmin, Asvaghosa converted to Buddhism (circa C.E. 100). He is The Twelfth Ancestor in the Ch'an line that begins with Gautama Buddha and ends with Bodhidharma. *See also* Buddha.

Asvamedha (India) Early Vedic horse sacrifice. *See also* Rama.

Asvamuttakha (India) *see* Ma-mien (China).

Asvinau (India) *see* Asvins.

Asvins *Ahans, Ashvins, Ashwins, Asvinau, Atvins* (Brahmanic, Hindu, Vedic; India)

Also known as: *Dasra* (Wonder Workers), *Dasra and Nasatya, Dioskouroi* (Greek), *Divo Napata, Nakula and Sahadeva, Naonghaithya* (called this name in later times).

In Vedic mythology, the Asvins are cosmic deities, the sons of Dyaus, or of the sun god Surya, or Savitri and the nymph Sanja, or Surya and the nimble cloud goddess Saranyu. She is also said to be the mother of twins Yami and Yama, which would make them the siblings of the Asvins. They are variously said to be the cosmic gods of the dawn, of heaven and earth, of day and night, sun and moon, or morning and evening (one half dark, the other light). In the *Rig-Veda*, they are called the joint husbands of Surya, the sun maiden. Tales are told of their rescue of Bhujyu (the Sun), who was thrown into the ocean by his evil father. The twins renewed him by taking him in their chariot on the path of the gods. In Brahman mythology they are twin healing deities who cure all infirmities. The elder is Dasra and the younger twin is Sahadeva. As the physicians of Swarga, the heavenly abode of Indra, they were known independently or collectively as Nasatya, or Nasatya and Dasra. In the *Mahabharata*, it is written that they rejuvenated the aged and wealthy sage Chyavana. Other patients of the Asvins were Vispala, for whom they fitted an iron leg, and Upamanyu who had his eyesight restored. The Asvins were the fathers of Sahadeva and Nakula, the youngest Pandu princes, by the goddess Madri. According to the *Ramayana*, they were the fathers of the monkeys Dvivida and Mainda. The goddess Vadaba (also spelled Vadava), the wife of Vivasvat, is said by some to have given birth to the twins while in the form of a mare. The Asvins are invoked by warriors in battle, by the heavy burdened and down trodden, the ill, the humble, and by brides who wish to be fertile. In later times, the Asvins declined in mythological status and became the Zoroastrian archdemon Naonghaithya. The Asvins are described as being handsome young twins, one light and one dark in color, on horseback or in a golden three-seated, three-wheeled car drawn by horses, a bird, an ass, or a buffalo. Their vehicle was made by the three generous elves known as the Ribhus. The Asvins' color is red. When Ratri, the goddess of night, dissolves, the Asvins bring up the morning light and make a path for the goddess of dawn, Ushas. They are depicted as the drivers and the horses for the sun's chariot. They are symbolized by two circles, two mountain peaks, two eyes, or two wheels. The name Nasatya indicates that they were either born from the nose of their mother or may have been elephant (long nosed) deities. In astrology, they represent Gemini. They are associated with the lotus and used honey for many of their healing activities. Bhujyu represents the sun at its ebb during the winter solstice and its restoration in spring or summer. Bhujyu also represents consciousness lost in a materialistic world. The monster Mada represents thought. Other Vedic physicians are Agni, Indra, Rudra, Soma. Regarding Naonghaithya, *see* Spentas Armaiti. The Asvins are comparable to the Greek Dioscuri, and the Greek healer Asclepius. They are associated with Mitra and Ratri. For another myth involving the Asvins, *see* Mada. *See also* Bhrigu; Chandra; Pandavas; Pushan; Ribhus; Sanja; Saranyu; Surya-Bai; Swarga; Ushas; Vivasvat.

Aswini (India) *see* Surya.

Asyngur (Teutonic) *see* Asynjor.

Asynja (Teutonic) *see* Asynjor.

Asynje (Teutonic) *see* Asynjor.

Asynjor *Asynja* (singular form), *Asyngur, Asynje* (Teutonic)

The Asynjor are the female counterparts to the Aesir (q.v.). *See also* Aesir; Asgard; Fjorgyn; Jord.

At-Em (Egypt) Mother goddess of all-devouring time.

At-en-ra (Egypt) *see* Adon.

Ata (Middle Eastern) *see* Atargatis.

Atabei *Attabeira* (Haiti; Taino People, Antilles)

Also known as: *Guacarapita, Guimazoa, Iella, Illa, Mamona, Momona.*

Atabei is the First Woman or Mother Earth. She is the mother of the Haitian sky god Joca-huva and, in some versions, Iocauna. Her messengers are Coatrischie the hurricane goddess and Guatauva. Atabei is associated with Guabanex (q.v.). *See also* Guamaonocon; Iella; Iocauna.

Atabyrius (Greek) *see* Althea.

Ataensic (Iroquois Indian People). *See also* Ataentsic.

Ataentsic *Ataensic, Ataeusic* (Huron, Iroquois People, North America)

A water goddess. High goddess. Spouse of the Chief of Heaven. She is a mortal woman who was sent to the upper regions. After enormous pain and suffering she was sent back to earth with the gift of maize and meat. Ataentsic became the Great Earth Mother. Her twins Yoskeha (also spelled Ioskeha) and Tawiscara caused her death during childbirth. Her next tribulation was to fall or be kicked from heaven. The animals who created the emerging earth came to her rescue. In some legends, it is Ataentsic's daughter "Breath of Wind" who gave birth to Yoskeha and Tawiscara. *See also* Yolkai Estan; Yoskeha and Tawiscara.

Ataeusic (Huron, Iroquois People, North America) *see* Ataentsic.

Atago-Gongen (Buddhist, Shinto; Japan)

Also known as: *Atago-Sama, Kagu-tsuchi no Kami, Susan-owo.*

God of fire and destruction. The son of Izanagi and Izanami, this deity is worshiped on the mountain Atago. He is shown as a warrior mounted on a horse who carries a pearl and a crozier. Atago-Gongen is possibly the same as Jizo. *See also* Izanagi; Kagu-Tsuchi.

Atago-sama (Japan) *see* Atago-Gongen.

Ataguchu (Inca) *see* Apocatequil; Pacari.

Atahocan (Algonquin, Montagnais People, North America)

Also known as: *The Great Spirit.*

Supreme Being. Atahocan is the creator of all things. *See also* Gitchi.

Ataksak (Eskimo)

God of joy. This good spirit lives in heaven. When he dies his body will shine. Ataksak is shown as a sphere with many brilliant cords on his body.

Atalanta (A) *Atalante* (Greek)

Atalanta, goddess of the hunt, may have originally been a death goddess. She is the daughter of Iasus and Clymene. Her father abandoned her on Parthenia because he wanted a son. Artemis, the goddess hunter, sent a bear to raise her in the woods. Later, hunters found her and took her under their wings. Her upbringing gave her superior skills as a hunter, runner and warrior and she became famous for her foot racing. Her father reappeared on the scene and claimed the paternal right to choose her mate. She agreed, with the stipulation that she would not mate with any man who could not outrun her and if she could outrun him, she could kill him. Renowned for her beauty, there were many contenders for her hand who ended up dead. She was finally defeated in a foot race by Melanion (also spelled Meilanion and Milanion) who threw three golden apples in her path. The apples from the garden of Hesperides were given to him by Aphrodite. (His adventures are often attributed to Hippomenes.) In time, the couple were turned into lions by Zeus for desecrating his temple or for desecrating the temple of Cybele. In another version, they were punished because Melanion forgot to thank Aphrodite for the Golden Apples. Atalanta might be a form of Artemis or Diana (qq.v.). *See also* Althea; Aphrodite; Ares; Argonauts; Calydonia Boar Hunt; Cybele; Hesperides, Jason; Paris (A); Zeus.

Atalanta (B) (Greek) She is the daughter of Schoeneus, king of a section of Boeotia. She had wanted to remain a virgin, but eventually changed her mind and married Hippomenes.

Atalanta (C) (Greek) The daughter of Maenalus.

Atalante (Greek) *see* Atalanta.

Atamas (Greek) *see* Ino.

Atanea (Polynesia) *see* Atunua.

Atanua *Atanea* (Polynesia). Dawn goddess. *See also* Atea.

Atanzah (Mesopotamia) *see* Anu (B).

Ataokoloinona (Madagascar, Africa) Messenger.

He is the son of Ndriananahary who sent him to earth to see if it was a good place to inhabit. Because earth was hot and dry Ataokoloinona buried himself in the ground and was never seen again. *See also* Ndriananahary.

Atar *Adar, Atarsh* (Zoroastrianism; Persia)

Chief of the Yazatas. Atar, the son of Ahura Mazda, is a god of fire. Sometimes he is classified as an Amesha Spentas and said to be one of the assistants of Asha Vahishta who presides over righteousness in the moral sphere and is the spirit of fire in the material sphere. Atar conquered the evil dragon Azi Dahaka in a battle for the control of Divine Glory. Personified, he is a source of comfort to mortals. He offers wisdom, virility, and a paradise for the virtuous. In the eyes of Atar, only one sin is unforgivable: to burn or cook dead flesh. He is comparable to the Hindu god of fire, Agni (q.v.). *See also* Ahura Mazda; Amesha Spentas; Asha Vahishta; Azhi Dahaka; Fravashis; Yazatas.

Atarate (Middle Eastern) *see* Atargatis.

Atargate (Middle Eastern) *see* Atargatis.

Atargatis *Atarate, Atargate, Atergatis, Ataryatis, Atharate.* (Aramaic, Hittite, Roman [later], Syrian)

Also known as: *Ata* (possible original name), *Ataryatis Derketo, Dea Syria* (Syria), *Derceto, Derketo, Tar-Ata.*

Atargatis was originally a goddess of fertility. She descended as an egg from heaven and emerged as a mermaid goddess. Her origins lead some to call her the mother of mermaids. A jeal-

www.ebook3000.com

ous rival cursed her with an unabiding love for a handsome young man. To ensure his fidelity, she caused him to disappear. A daughter, Semiramis, resulted from the union. Atargatis left her daughter in the care of doves in the wilderness and then threw herself into a lake and became a fish. She may have been the mate of Hadad. At a later date, she was worshiped by the Romans. Devoted eunuchs self-abused themselves and performed ecstatic dances in her honor. Atargatis is depicted with the tail of a fish, as a sky-goddess in a diaphanous veil with eagles around her head, and as sea goddess with a dolphin crown. She may be a combination of Athar and Ate. *See also* Ate; Cybele; Ishtar; Oannes; Semiramis.

Atarsh (Persian) *see* Atar.

Ataryatis Derketo (Syrian)
Another name for the fish goddess Atargatis (q.v.).

Atchet (Egypt) *see* Ra.

Ate (Greek)
She is the goddess of infatuation, rash actions, and mischief. The daughter of either Zeus or Eris, Ate is the sister and friend of Ares (war and storm). After Zeus threw her out of heaven for causing Eurystheus to be born before Heracles, she took refuge among men and led them to impulsive actions. Zeus sends the Litai (prayers) to follow her around, trying to straighten up the trouble she creates. Her toy, the Apple of Discord, has caused numerous conflicts and was the cause of the Trojan War. Ate is identified with Atargatis. She is similar to the Erinyes, Furies, and the Roman goddess Discordia. *See also* Ares; Atargatis; Zeus.

Atea *Akua, Atua, Autu, Etua, Otua* (Polynesia)
Also known as: *Atea Rangi, Rangi, Te Tumu* ("The Source"), *Vatea, Wakea.*

"Great Expanse of the Sky." The Sky. Atea and Papa are the primeval couple, the procreators of all who followed. In some myths however, we are told that Atea, the god of light, is the son of the god of darkness, Tanaoa. He is the brother of Ono, spouse of the dawn goddess Atunua, and father of Hakaiki. He is one of the triad with Ono and Hakaiki. The Mangaians say that Atea and Papa's first son was Tangaroa. The people of Tuamotu have Atea married to Fa'ahotu. Their first son is Tahu who became a renowned magician. Their second son is Tane (some say). Their third son is Ro'o. At one time, Atea and Tane were fastened in a deadly embrace. Finally, Tane used his thunderbolt Fatu-Titi to kill Atea. In other myths, Atea is released from Rua, the god of darkness, by Ru, Hina, Maui, Tane or Atea depending on the legend. Sometimes all five deities were involved in the release of the god of light. *See also* Atuna; Hina; Maui; Mutuhei; Ono; Papa (A); Rangi; Rongo; Rua; Ta'aroa; Tanaoa; Tane; Tangaroa; Vari (A); Vatea.

Atea Rangi (Polynesia) *see* Atea; Rangi.

Atem (Egypt) *see* Atum.

Aten *Adon, Aton, Atum* (Egypt)
Also known as: *Horus, Khepri, Ra, Ra-Harakhte, Shu, Tem.*
God of the sun, light, providence and life. Depending on the position of the sun, he was called Aten, Khepri, Ra or Atum. Under the name of Horus, he was joined with Ra and was then called Ra-Harakhte. Called Aten, Pharaoh Amenhotep IV took the name Ikhnaton or Akhenaton (Akhenaten), meaning "pleasing to Aten." Married to the beautiful Nefertiti, he declared Egyptian religion to be monotheistic, although the god was probably worshiped at an earlier date. The monotheistic worship of Amenhoteps lasted from fifteen to seventeen years until the death of this Pharaoh. (It has been suggested that he and Nefertiti were murdered.) His reign initiated a revolutionary change in Egyptian art. During this period, artistic forms took on a naturalistic, as opposed to a stylized, form. The priests of Amen-Ra destroyed the records of his reign, and Akhenaten's son-in-law, Tutankhaten, who changed his name to Tutankhamen, restored the worship of Amen-Ra. Aten is usually pictured in the form of a large red disk with rays tipped with hands. At times he is shown as a falcon with speckled wings. *See also* Yahweh, the only god for the Egyptians at the time. Sometime during the reign of Amenhotep, Aten was changed to Shu, then changed again to Re or Ra. *See also* Akhet-nen-tha, Amen (B), Atum; Khepri.

Atene (Greek) *see* Ares.

Ater-Asfet (Egypt) One of the gods in the Pyramid Texts.

Atergata (Middle Eastern) *see* Atargatis.

Atergatis (Middle Eastern) *see* Atargatis.

Ateseatine (Pueblo People, United States) *see* Atseatsan.

Atesh (Persia) *see* Atar.

Athamas (Greek)
Athamas is one of seven sons of Aeolus and Enarete. He has six brothers and seven sisters (for a list of their names *see* Canace). His first of three marriages was to the nymph Nephele. He became the father of Helle and Phrixus. His second marriage to Ino produced two more children, Learchus and Melicertes. When he married his third wife, Themisto, he became the father of Erythrius, Leucon, Ptous and Schoeneus. Except for Leucon and Learchus, all of his children were accidentally killed by Themisto (she subsequently committed suicide). Athamas killed his son Learchus accidentally when he mistook him for a stag. When this happened, he was exiled to Thessaly. He renamed Thessaly, Athamantia. *See also* Aeolus (A); Canace; Helle; Nephele; Phrixus.

Athar (A) (Southern Arabic)
Male counterpart of the Assyro-Babylonian goddess Ishtar, who came into being after matriarchy was rejected.

Athar (B) (Ugarit)
One of the children of Asheratian of the sea. *See also* Astarte.

Atharate (Middle East) *see* Atargatis.

Atharvan (India) *see* Matarisvan.

Athena *Athenaa, Athenaia, Athene* (Greek)
Also known as: *Aithuia* (Diver Bird), *Baze, Bulaia* ("She of the Council"), *Glauk-Opis* ("Owl-faced"), *Gogopa* (Death Goddess), *Grogopa, Merchanitis, Minerva* (Roman), *Nice, Nike* (Goddess of Victory), *Pallas* (Storm Goddess), *Pallas Athene, Parthenia, Parthenos* ("Virgin"), *Polias* (Goddess of the City), *Soteira, Tritogeneia, Victoria* (Roman).

Assimilated from Minerva (Roman) and originally part of the triad of Jupiter, Juno and Minerva, the name Athena may have come from the Albanian goddess Ethona or Vedic Ahana. Hesiod connected her with Eris (strife) and at first she was a goddess of battle and storms. The Greeks identified her with the Egyptian sky goddess Neith. The grey-eyed Greek virgin goddess of war, wisdom, and handicrafts, and patroness of Athens, Athena is the daughter of Zeus and Metis. Zeus, fearing that Metis would bear a son stronger than himself, turned her into a fly and swallowed her. The child, Athena, sprang from his head fully armed with helmet, shield, and spear. Some say Prometheus or Hephaestus split open Zeus's head with an axe for this miraculous birth. Athena won the contest with Poseidon for Athens by producing the olive tree which the Athenians judged more useful than Poseidon's salt spring. The Parthenon was her temple. The owl is her bird. She is often depicted as a maiden in warlike array attended by the owl and the serpent, both emblems of wisdom. She is credited with the taming of horses and the use of chariots. In the form of Gogopa she is a death goddess. As Pallas, she was a storm goddess presiding over war. During times of peace she instructed people in useful crafts. Aithuia is her name when she is in the shape of a seabird. In the Wars of the Gods with the Giants and Titans, she defeated the monstrous giant Enceladus. She also assisted Heracles in various tasks. Athena taught Danus to build a two-prowed ship and helped Epeius build the wooden horse. Athena invented the loom, the spindle and the flute. It is said that she remained a virgin, rejecting all suitors. On the third year of each Olympiad, a festival, celebrated by games, banquets and sacrifices, was held in her honor. The prize was a jar of olive oil pressed from one of her sacred trees. Some old texts refer to Minerva using the name of Athena, and some consider them one and the same deity. As Athena, she was associated with the legend of Prometheus when he was considered a creator god. The Greeks also associated Athena with the goddess Net by representing her as a vulture and a scarab. She is shown with a conical cap surmounted with a cock's comb. She wields a spear and wears a scaly tunic trimmed with snakes. Between her breasts, she wears an ornament symbolizing the head of Medusa. She is associated with Hermes (q.v.). Athena is comparable to the goddess of dawn, Eos, and the Roman Aurora. *See also* Aegis; Aello; Aglaia; Agraulos; Ajax the Lesser; Anat; Argus (C); Artemis; Belleraphon; Cassandra; Corybantes; Enceladus; Epeius; Eris; Hephaistos; Hesperides; Inachus; Kore; Medea; Medusa; Minerva (Roman), Naiads; Neith; Nike; Pallas; Pegasus; Perseus; Stymphalian Birds; Zeus.

Athenaa (Greek) *see* Athena.

Athenaia (Greek) *see* Athena.

Athene (Greek) *see* Athena.

Athensic (Iroquois People, North America)

An ancestor, she fell from heaven during the great deluge. When the waters receded, she was on dry land which became a continent. *See also* Enigohatgea; Enigorio; Itapalas.

Ather (Greek) *see* Nemesis; Nox.

Atheret (Ugarit, Syria) *see* Athirat.

Athirat *Atheret* (Ugarit, Syria)

Mother of the gods, and known as "Athirat the Merciful," she is the official wife of El, the Supreme God. She suckled two of the gods, Shahar and Shalim, who were fathered by El. She rides a donkey with a silver harness. Athirat is often depicted seated at the seashore, spinning. *See also* Anat.

Athor (Egypt) *see* Hathor.

Athrar (Middle Eastern) *see* Asherah (B).

Athtar (Arabic, Babylonian, Canaanite)

Also known as: *Ashdar, Ishtar.*

Sky deity. In South Arabia Athtar was the planet Venus, but later Sumerian and Babylonians converted him to a female version who became Ashdar and Ishtar. *See also* Astarte; Innini.

Aththar (Ugarit, Syria) God of irrigation.

Athuma (Egypt) *see* Atum.

Athwya (Persian) *see* Haoma; Thraetaona.

Athyr (Greek) *see* Hathor.

Ati-Auru (Polynesia) *see* Tiki.

Atira (Pawnee People, North America) *see* H'uraru; Tirawa.

Atius (Pawnee People, North America) *see* Shakuru; Tirawa.

Atius Tirawa (Pawnee People, North America) *see* Tirawa.

Atlacamini (Aztec)

Storm god aspect of Chalchiuhtlicue (q.v.). *See also* Apoconallotl.

Atlantiades (Greek) *see* Hermaphroditus.

Atlantius (Greek) *see* Hermaphroditus.

Atlas (Greek)

Also known as: *Hyas.*

King of Mauretania. He is the Titan son of Iapetus and Asia (the consort of Prometheus) or Clymene, the river nymph daughter of Oceanus and Tethys. Others say he is the son of Uranus and Gaea. His siblings are Epimetheus, who opened Pandora's box; Menoetius, who was hurled into the underworld by Zeus' thunderbolt; and Prometheus, who was chained to a rock for thirty years while eagles nibbled daily on his regenerating liver. Atlas owned one thousand flocks of every type and fruit-bearing trees. He married Pleione (also known as Aethra) and was the father of Asterie, the Hesperides, the Pleiades, Hyades, Hyas, and Calypso. (Some write that Hesperis is the mother of the Hesperides.) He was also the father of Dione. Atlas fought with the Titans against Zeus. The unhappy Zeus doled out heavy punishment and sentenced Atlas to carry the weight of the world on his shoulders. At a later time, Heracles tricked Atlas into giving him the three Golden Apples. Atlas eventually was turned to stone by Perseus. Atlas is similar to the Egyptian god Shu. In the Pelasgian creation myth, Atlas was coupled with the Titan Phoebe as the rulers for the Moon. He is usually shown holding the sky with outstretched arms. *See also* Amphitrite; Calypso; Clymene; Epimetheus; Eurynome (A); Harmonia (A); Maia; Mercury (A); Oceanids; Orion; Pelops; Perseus; Prometheus; Themis.

www.ebook3000.com

computer for writing and is totally at ease with the latest computer technology.

Master Chia estimates that it will take thirty five books to convey the full Universal Tao System. In June 1990, at a dinner in San Francisco, Master Chia was honored by the International Congress of Chinese Medicine and Qi Gong (Chi Kung), who named him the Qi gong Master of the Year. He is the first recipient of this annual award.

In December 2000, the Tao Garden Health Resort and Universal Tao Training Center was completed with two Meditation Halls, two open air Simple Chi Kung Pavilions, indoor Tai Chi, Tao Yin and Chi Nei Tsang Hall, Tai Chi Natural Swimming Pool, Pakua Communications Center with a complete Taoist Library, Internal World Class Weight Lifting Hall and complete 8 Court Recreational Facilities.

In February 2002, the Immortal Tao practices will be held at Tao Garden for the first time using Dark Room technology, creating a complete environment for the higher level Taoist practices.

He has previously written and published these Universal Tao books:

Awaken Healing Energy of the Tao - 1983
Taoist Secrets of Love: Cultivating Male Sexual Energy
co-authored with Michael Winn - 1984.
Taoist Ways to Transform Stress into Vitality -1985
Chi Self-Massage: the Tao of Rejuvenation - 1986
Iron Shirt Chi Kung I - 1986
Healing Love Through the Tao: Cultivating Female Sexual Energy - 1986
Bone Marrow Nei Kung - 1989
Fusion of the Five Elements I - 1990
Chi Nei Tsang: Internal Organ Chi Massage - 1990
Awaken Healing Light of the Tao - 1993
The Inner Structure of Tai Chi co-authored with Juan Li - 1996
Multi-Orgasmic Man co-authored with Douglas Abrams 1996 - published by Harper/Collins
Tao Yin - 1999
Chi Nei Tsang II - 2000
Multi-Orgasmic Couple co-authored with Douglas Abrams 2000 - published by Harper/Collins
Cosmic Healing I - 2001
Cosmic Healing II co-authored with Dirk Oellibrandt - 2001

Also many of the books above are available in the following foreign languages: ***Bulgarian, Czech, Danish, Dutch, English, French, German, Greek, Hebrew, Hungarian, Indonesian, Italian, Japanese, Korean, Lithuanian, Malaysian, Polish, Portuguese, Russian, Serbo-Croatian, Slovenian, Spanish,*** & ***Turkish*** editions are available from the Foreign Publishers listed in the Universal Tao Center Overview in the back of this book.

Atlatonan (Aztec, Mexico)
Goddess of the coast. She is generally associated with Tezcatlipoca in festivals. In some legends Atlantonan, Uixtochihuatl, Xilonen and Xochiquetzal were assigned to Tezcatlipoca as wives. *See also* Tezcatlipoca; Uixtochihuatl; Xilonen.

Atmu (Egypt) *see* Atum.

Atnatu (Aborigine People, Australia)
This High Being constructed himself out of nothing and gave himself a name. He has a wife and sons. All his sons have his name, Atnatu. He is described as a "great black man."

Aton (Egypt) *see* Aten.

Atonatiuh (Aztec, Mexico)
In the Creation Legend, this god caused the deluge of the "first earth." He was later equated with Tlaloc (q.v.). *See also* Legend of the Four Suns; Nata and Nena; Tlazolteutl.

Atreidae (Greek) *see* Agamemnon.

Atreus (Greek)
King of Mycenae. He is the son of Pelops and Hippodameia. His siblings are Alcathous, Astydameis, Chrysippus, Copreus, Lysidice, Nicippe, Pittheus, Thyestes and Troezen. He married Aerope who earlier had been the wife of Pleisthenes. Aerope had an affair with her brother-in-law, Thyestes, resulting in the birth of twins. The twins Tantalus and (possibly) Aglaus or Pleisthenes were slaughtered by Atreus who served them as a meal to Thyestes. Atreus is the father of Agamemnon and Menelaus. There is a possiblity that he is the father of Anaxibia and Pleisthenes. In another scenario, Thyestes married Pelops (who is actually Thyestes' exiled daughter), whom he believed was the daughter of Thesprotus. She was already pregnant by Thyestes at the time of their marriage. Atreus' death, in this case, was caused by the son of Thyestes and Pelops, Aegisthus. *See also* Aegisthus; Agamemnon; Hippodameia (B); Pelops.

Atri (India) Son of Brahma. *See also* Brahma; Rishi; Soma.

Atropos (Greek)
Also known as: *Fates, Moirai.*
Goddess of life. "The Unbending." One of the Fates. Her parents are Zeus and Themis, and Clotho and Lachesis are her sisters. Atropos, who carries the scissors to cut the thread of life, is said to be the smallest of the Fates, and the most terrible. Similar to Roman goddess Morta. *See also* Fates.

Atroposy (Greek) *see* Fates.

Atru-she-en-nesert-f-em-shet (Egypt) *see* Aaru.

Atse Estsan and Atse Hastin (Native American) *see* Atseatsan and Atseatsine.

Atseatsan and Atseatsine *Atse Estsan and Atse Hastin.* (Navaho, Pueblo, and Iroquois People, North America)
Also known as: *Ahsonnutli and Yolaikaiason.*
Creators. First man and first woman. God and goddess who raised the sun in the heavens. Ahsonnutli, with the help of twelve men, created a blaze from a crystal, but it was too hot so Atseatsan and Atseatsine appeared to give assistance. With a great deal of effort and much stretching of the earth, they raised the blaze to its present position in the sky. The twelve men who are the Yiyantsinni still hold the sun or heaven up with poles. In another version these were the first woman and man. They were created out of ears of corn by the four strange beings who suddenly appeared. These beings were Bitsis Lakai (also known as Hasteyalti), Bitsis Dotli'z (also known as To'nenili), Bitsis Litsoi, and Bitsis Lizi'n (also known as Hastezini). In another rendition, Atseatsan and Atseatsine intermarried with some underworld people named Kisani and from this intermarriage came the human race. They are probably the same as Hasteyalti and Hastehogan. *See also* Anaye; Estsanatlehi; Klehanoai; Nayanezgani; Thobadzistshini.

Attabeira (Antilles Islands; Haiti) *see* Atabei; Iocauna.

Attes (Greek) *see* Attis.

Atthis (Greek) *see* Athena.

Attis *Attes, Attus, Atus, Atys* (Greek; Phrygian)
God of vegetation. Attis is the son of the Akkadian mother goddess, Nana, and an almond that had fallen to the ground. The almond had grown from the the genitals of Agdistis, who had castrated himself and turned into a pine tree. When Attis broke his vow of chastity and married the daughter of the river god Sangarius, he was driven insane by Cybele, who was supposedly his consort. He castrated himself and died. Violets grew from his blood and Cybele resurrected him in the form of a fir tree. Compare Attis to Anchises and to the Sumerian Dumuzi. *See also* Agdistis; Angus; Hephaistos; Uranus.

Atu (Egypt) *see* Aaru.

Atua (Polynesia) Flying ancestor spirits who live in trees. *See also* Atea.

Atugan (Mongol; Siberia)
Early goddess of the Mongols. Worshiped as one of the "Goddesses of Earth."

Atum (Egypt) *Atem*
Also known as: *Amen-Ra, Atmu, Atum-Ra, Atum-Re, Atumu, Khepri, Ra, Ra-Tem, Tem, Tem-Asar, Temu, Tum.*
Originally, Atum was a local god of the city of Annu or Heliopolis. His sacred animal was Merwer the bull. At a later time, he merged with Ra and was known as Ra-Tem. Later still, Atum was personified as the rising and the setting sun. He is generally thought to be the first born of the gods, father of the setting sun, and the ancestor of mortals. He is the son of the primeval Nun. In some accounts, he was created by four frogs and four snakes. In a variation, he is said to have originally been a serpent who changed into a man. At the end of the world he is to change back to a serpent and return to the primeval Nun. He became the father of the first divine couple, the twins Shu and Tefnut, by self-fertilization, either from his own spit or by self-copulation. His daughter Tefnut is also considered to be his consort. Later, when his cult spread, he had two female counterparts: Iusaas, (also called Iusaaset), and Nebhet Hotep (also called Nebt-Hetep). The births of Shu and Tefnut are also attributed to his union with Mebet Hotep. Atum is a member of the Ennead (the council of nine gods) which also includes Shu, Tefnut, Geb, Nut, Osiris, Isis, Set and Nephthys. The earliest records of him came from about 2350 B.C.E. during the

fifth dynasty. He is shown with a human head, wearing the *pschent*, (the double crown of the Egyptian pharaohs), or shown as an old man leaning on a stick. A symbol of "Atum and his hand" appear as a divine couple on coffins of the Herakleopolitan period. Some think the Benu Bird is an aspect of Atum. Also see Benu. He is sometimes confused with Amon. *See also* Amen (B); Aten; Bennu; Ennead; Geb; Horus; Isis; Iusaas; Khepri; Nephthys; Nu; Nut; Ra; Set; Shu; Tefnut; Temu; Tum.

Atum-Ra (Egypt) *see* Atum.

Atum-Re (Egypt) *see* Atum.

Atuma (Egypt) *see* Atum.

Atumu (Egypt) *see* Atum.

Atus (Greek) *see* Attis.

Atvins (India) *see* Asvins.

Atymnius (Greek)
The son of Zeus and Cassiopeia, Atymnius was the possible lover of Minos. If it was not him, it is thought to be Miletus. *See also* Cassiopeia; Minos; Sarpedon (A).

Atys *Attis* (Greek) *see* Attis, Cybele.

Au Sept (Egypt) Ancient creation goddess.

Auai (Egypt)
Another name for Sekhem or possibly Ra. *See also* Aai.

Auchimalgen (Araucanian People, Chile, South America)
Moon goddess, seer, protector of mortals and mate of the sun. Her face revealed everything. When red in color, it was an indication that an important person would die. *See also* Cherruve; Pillan.

Aud (Norse; Teutonic)
Also known as: *Audr.*
Deity of the night. Aud is the son of Nott (also known as Nat) by her first husband, Naglfari. He is the brother of Jord and Dag. *See also* Dag; Jord; Naglfari.

Audhumla *Audumla* (Norse; Teutonic)
Audhumla, the divine cow, was created in Ginnunga-gap before the beginning of the world as we know it. The evil giant Ymir fed from the four rivers of milk that she produced. From his smelly armpits he produced his own offspring. Audhumla sustained herself by feeding from the salty ice. After eons had passed, she was still licking when a man's hair appeared. By the evening of the second day his head appeared, and by the evening of the third day the whole man appeared. He was the first man and his name was Buri. He became the father of Bor, who in turn was father of Odin, Ve, and Vili. Some say Audhumla was created by Surtr. Compare to Kamadhenu (India). *See also* Bor; Buri; Ginnunga-gap; Surtr, Ve; Ymir.

Audjal (Caroline Islands)
A minor goddess of the earth. The care of the earth was given to her by the god Ifaluk.

Audumla (Teutonic) *see* Audhumla.

Auf (Egypt) *see* Ra.

Auga-nur (Semitic) *see* Agenor (A).

Auge (Greek) *see* Artemis.

Augeias (Greek) *see* Actor (B); Argonauts; Helius.

Augelmir (Teutonic) *see* Ymir.

Augralids, The (Greek) *see* Agraulos.

Augusel (Celtic) *see* Arawn.

Aukele-nui-aiku (Hawaii) *see* Kaneapeua.

Aukert *Aukar* (Egypt)
Aukert is possibly another name for the underworld. It is mentioned in relation to Amen-Ra. *See also* Aaru; Tuat.

Aukhesia (Akkadian, Greek) *see* Lamia.

Aulanerk (Eskimo)
Ocean deity. This naked deity lives in the ocean. His struggles cause the waves.

Auler (Teutonic) *see* Ull.

Aumakua (Hawaii)
Guardian spirits. The Aumakua (spirits) come to meet the soul and protect it from the perils of the journey to the otherworld. *See also* Po.

Aumanil (Eskimo)
Sea deity. He is a god of the whales, who lives on land.

Aun (Semitic, Syrian)
Also known as: *An, On.*
Ancient Semite fish god. The name may be associated with the fish god Dagon. The Syrians believed that Aun is the husband of Derketo. *See also* Atargatis; Dagon (A); Dagon (B).

Aunaauif (Egypt) *see* Ap-taui.

Aura (A) (Greek) *see* Aurora.

Aura (B) (Phoenician)
In the Creation Legend of Damascius, Aura (meaning intelligence) and Air were the parents of Otos (meaning reason). Aura and Potos (meaning desire) were the parents of a daughter Omicle, who was known as "The Mother of All Things." *See also* Air (A).

Aura (C) (Greek)
Her parents are Lelantos and Periboea. She became the mother of twins by Dionysus. During a mental breakdown, she tore one of her twins apart and ate it. She then committed suicide by drowning.

Auraka (Polynesian) "All-Devouring." Death deity.

Auramazda (Persia) *see* Ahura Mazda.

Aurboda (Teutonic) *see* Gulveig; Jotuns.

Aurentil (Teutonic) *see* Aurvandil.

Aurgelmir (Teutonic)
This is another name for Ymir, the primeval frost giant (q.v.).

www.ebook3000.com

Aurgenimir (Teutonic) *see* Ymir.

Aurora (Roman)
Also known as: *Eos* (Greek).

Aurora, goddess of dawn, is the Roman name for the Greek dawn goddess, Eos. She is shown flying before the chariot of the sun, sometimes carrying a torch and flowers. Aurora is comparable to the Greek Athene, Ausera of the Lithuanians, the Vedic goddess of dawn, Ushas, and the Slavic Zorya Utrennyaya. *See also* Athena; Ausera; Eos; Gaea; Ushas.

Auroras, The Two *Auroras* (Serbian), *Zarya* (Slav), *Zoryas*
Also known as: *The Two Zarys or Zoryas.*

These two beautiful virgins sit at the side of the Sun King (possibly Dazhbog). One is Aurora of the Morning, the other, Aurora of the Evening. The Slavic people call Aurora of the Morning "Zorya Utrennyaya" and Aurora of the Evening "Zorya Vechernyaya." *See also* Aurora; Eos; Ushas; Zorya.

Aurva (India)
A Bhrigus sage, Aurva hated the Kshatriya race. *See also* Sagara.

Aurvandil *Aurentil, Orendil, Orvandel* (Norse; Teutonic)
Also known as: *Egil, Egilorvandel.*

A hero and a solar or wind deity, he is the spouse of the seer Groa, and the father of Hadding and Svipdag. His second wife was Sith the mother of Ull. He is also said to be the father of Roskva and Thjalfi. Aurvandil lives on the border of Jotunheim. Thor threw his frozen toe into the heavens where it became a star that some say is the morning star, or the constellation Orion. *See also* Groa; Thor.

Aus (Babylonian)
In the Creation Legend of Damascius, Aus is the brother of Anu and Illinus, and with his mate, Dauce, he is the father of Belus. *See also* Belus (B).

Ausaas (Egypt) She is the spouse of the sun god Harakhtes.

Ausar (Egypt) *see* Osiris.

Ausares (Egypt) *see* Osiris.

Ausera (Lithuanian)
She is the goddess of dawn comparable to Aurora, Eos, Saranyu and Ushas. *See also* Ausrine.

Aushedar (Persia) The First Savior. *See also* Zoroaster.

Aushedar-mah (Persia) The Second Savior. *See also* Zoroaster.

Ausiri (Egypt) *see* Osiris.

Ausrine (Lithuanian) Dawn goddess. *See also* Ausera; Breksta.

Aust (Egypt) *see* Isis.

Auster (Greek) *see* Notus.

Austi (Teutonic) A Dwarf. *See also* Dwarfs.

Austri *Austre* (Norse; Teutonic)
One of the four dwarfs who support the heavens (made from the skull of Ymir) on his shoulders. The other dwarves are Nordri, Sudri, and Westri. *See also* Aarvak; Muspells-heim; Ymir.

Autak (Persia)
The demon mother/spouse of Angra Mainyu and mother of Azhi Dahaka (qq.v.).

Authades (Gnostic)
Also known as: *The Proud God.*

The *Pistis Sophia* text is from an early gnostic sect similar in belief to that of the Ophites and of Valentinus. It is a composite of the writings of several scribes. The date of the original document is around the seventh century C.E. It is not known the age of the composite parts. There is a part of the universe called the Thirteenth Aeon which is controlled by a triad of vague unnamed deities called the Great Forefather or the Great Unseen One, a goddess named Barbelo, and a god named Authades. This triad from the book *Pistis Sophia* are variously named the Twenty-four Unseen Ones, the Three Tridynami or Triple Powers. Of these twenty-four powers, Pistis Sophia is the one whose name is the title of the book. *See also* Pistis Sophia.

Autolycus (A) (Greek)
Thief. Argonaut. He is the son of Hermes and Chione and the grandfather of Odysseus. He married Amphithea and they had several sons and Anticleia. He taught Heracles how to wrestle. Autolycus has the power of changing anything that he steals, and of never getting caught. He has only been outsmarted on one occasion, by Sisyphus (q.v.). *See also* Anticleia (A); Hermes; Odysseus.

Autolycus (B) (Greek) An Argonaut. Father of Polymede.

Autonoe (Greek)
She is the daughter of Cadmus and Harmonia. Her siblings are Agave, Illyrius, Ino, Polydorus and Semele. Her children, by her marriage to Aristaeus are Actaeon and Macris. After tormenting Semele, Dionysus drove her and her sisters insane. *See also* Actaeon; Aristaeus; Harmonia (A); Ino; Semele.

Autophyes (Gnostic) *see* Aeons.

Autu (Polynesia) *see* Atea.

Auxo (Greek) *see* Graces, Charities.

Avagdu *Avaggdu* (Celtic)
The ugly son of the fertility goddess Keridwen (q.v.).

Avaggdu (Celtic) *see* Avagdu.

Avaiki *Havai, Havaiki, Hawaiki* (Polynesia)
Avaiki is the coconut shell that is the universe. From the bottom of this shell came Vari and Take, the origin of all life. Some demons in Avaiki are Te-aka-ia-oe, Te-tangaengae or Te-vaerua, and Te-manava-roa. In the Tuamotuan version, a creator deity named Kiho dwelled beneath the foundations of Avaiki. *See also* Kiho; Vari (A); Vatea.

Avallon *Avilion* (Britain)
Also known as: *Avallach.*
God of the Underworld.

Avalokit-Isvara *see* Avalokitesvara.

Avalokitesvara (Buddhist; India)
Also known as: *Amitabha, Amoghapasa Lokeswa* (Nepal), *Avalokit-Isvara, Avalokiteswara* (Nepal), *Chen Resic* (Tibet),

Cheresi (Tibet), *Kuan Yin* (China), *Lokeswara, Mahakaruna, Padma-pam, Padmapani, Sahasrabhuja* (Nepal), *Samantamukha* (Nepal), *Sitatapatraparajita* (Tibet), *Tara.*

Avalokitesvara is known as the downlooking deity. One of five Dhyanibodhisattvas, he is the Bodhisattva of compassion and instruction, the protector of health from poisonous snakes, ferocious animals, robbers and demons. Avalokitesvara is one of the one hundred and eight forms of Lokeswara. Sharing in the misery of mortals, he symbolizes infinite compassion and a willingness to aid those in distress. He refuses to accept Nirvana since he considers such acceptance selfish because most mortals have not attained that stage. He appears in Bardo on the fourth day. In attendance with him are Amitabha and his consort Pandaravasini and Manjusri and two female Bodhisattvas, Gita and Aloka. Aloka (also spelled Aloke), who is also known as Nang-sal-ma, personifies light. She is associated with fire and her color is red. Avalokitesvara's invocation "Om Mani Padme Hum," which means "The Jewel of Creation in the Lotus," is found inscribed on rocks, loose stones, prayer wheels and other objects. In his manifestation with eleven heads he is known as Samantamukha. Avalokitesvara is often in the company of the goddess Tara. She is also the consort, according to some, of Amoghasiddhi and Akshobhya. Avalokitesvara, who has a million eyes and a hundred thousand hands, can appear in any guise. Sometimes he is shown as half-male and half-female. He is usually depicted standing and holding in his hand the indestructible jewel. He is shown in fifteen different shapes in sculptures. As Padmapani, he wears an effigy of Amitabha in his hair to indicate his divination and he holds a pink lotus. He corresponds to the Hindu Padmapami. *See also* Akshobhya; Amida; Amoghapasa; Amoghasiddhi; Dhyani Buddhas; Dhyanibodhisattvas; Kannon; Kharchheri; Kuan Yin (China); Lokeswara; Lu-ma; Manjusri, Matsyendranatha; Sahasrabhuja; Samantabhadra; Samantamukha; Shimhanada; Sristikanta; Tara; Vajrapani; Varuna.

Avalon (Celtic, Gaelic)

Also known as: *Avilion.*

Heaven. Avalon is an idyllic island in the west, the home of heroes after death. Some say that Avalon is near Glastonbury. It is also the place where King Arthur was buried by his sister, Morrigu (q.v.).

Avanc (Celtic) *see* Addane.

Avany (Ceylon)

Mother of Buddha Sakyamuni. *See also* Sakyamuni.

Avatar (Hindu, India)

Also known as: *Avatara.*

Reincarnated deity. An avatar is the reincarnation on earth of a deity in the form of an animal or human. For an example, see the section "Also known as" under the entry for Vishnu.

Avatea (Polynesia) *see* Vatea.

Aventina (Roman) *see* Diana.

Avesta (Zoroastrian)

The sacred book containing the teachings of Zoroaster (q.v.). *See also* Anahita; Bundahish; Yashts.

Avfruvva (Finno-Ugric) *see* Akkruva; Havfru.

Avilayoq (Eskimo People) *see* Sedna.

Avilix (Maya) *see* Xumucane.

Avlekete (Dahomey, Fon People, Africa) *see* Aylekete.

Awahili (Cherokee People, North America)

"The Sacred Eagle."

Awanawilona (Native American) *see* Awonawilona.

Awar (Islamic)

He is the crafty demon of evasion and lasciviousness who is the son of Iblis and the brother of Dasim Sut, Tir and Zalambur. His name means "one-eyed." *See also* Azazel.

Awejsirdenee (India) *see* Kalki.

Awhiowhio (Aborigine People, Australia)

Also known as: Ara Tiotio (New Zealand)

God of whirlwinds. As Ara Tiotio, he is the god of tornadoes.

Awitelin Tsita *Awitelin Ts'ta* (Zuni People, North America)

Also known as: *Awonawilona, Hatai Wugti* (Spider Woman).

Awitelin Tsita is the mother goddess who was created from the spit of Shiwanokia. As the mate of the sky god Apoyan Tachu, the two created life. In another legend she was created by Awonawilona (q.v.). *See also* Shiwanni and Shiwanokia.

Awo-kashiki-ne No Mikoto (Japan) *see* Ama-no-minaka-nushi.

Awo-mikoto (Japan) *see* Ama-no-minaka-nushi.

Awonawilona *Awonawilone* (Pueblo, Zuni People, North America), *Awonawilone*

Also known as: *Awitelin Tsita, Awitelin Ts'ta, He-She, Sun Father.*

"Maker and Container of All." "All-Father." Awonawilona created himself in the form of the sun. The sun brought light to the dark void and mist clouds from which the waters evolved. He impregnated the sea waters from the surface of his person and produced the scum. From the green scum, the "Four-fold Containing Mother Earth," known as Awitelin Tsita, and the "All Covering Father Sky," known as Apoyan Ta'chu, were created. From Awitelin Tsita and Apoyan Ta'chu, all terrestrial things were created. In other versions of the myth Awonawilona ruled above while Shiwanni and his wife Shiwanaokia ruled the earth. Awonawilona, the Supreme Spirit and life-giving power, is often thought of as the Sun Father. In another version of this myth, Awonawilona filled the sea with bits of his own flesh, then hatched the resulting mass into Father-sky and Mother-earth. He is associated with Achiyalatopa, the knife-feathered monster. *See also* Awitelin Tsita; Shiwanni and Shiwanokia; Tloque Nauaque.

Awun (Formosa) God of destruction.

Awwaw (Bantu Iyala People, Northern Nigeria, Africa)

Supreme God.

Axibia (Greek) *see* Helius.

Axioche (Greek) *see* Astioche.

www.ebook3000.com

Axiothea (Greek) *see* Hesione.

Axius (Greek) *see* Rivers.

Aya *Aja* (Assyrian, Babylonian, Chaldean)
"The Bride." Deity of the sea. Dawn goddess. She is the consort of Shamash and the mother of Misharu and Kittu. In later times, she merged with Ishtar (q.v.). Different versions say this deity may be male or female. Aya is a Babylonian goddess of dawn who later merged with Ishtar (q.v.). Compare Aya to Aurora, Eos, Saranyu and Usha.

Aya-kashiki No Mikoto (Japan) *see* Ama-no-minaka-nushi.

Aya-kashiko-ne No Mikoto (Japan) *see* Ama-no-minaka-nushi.

Ayar Aucca (Inca) *see* Tahuantin Suyu Kapac, and Manco Capac.

Ayar Cachi (Inca) *see* Tahuantin Suyu Kapac, and Manco Capac.

Ayar Manco (Inca) *see* Tahuantin Suyu Kapac, and Manco Capac.

Ayar Uchu (Inca) *see* Tahuantin Suyu Kapac, and Manco Capac.

Ayida (Haiti) Rainbow goddess. *See also* Damballaha.

Ayido (Haiti) *see* Damballah.

Aylekete *Avlekete* (Dahomey, Fon People, Africa)
Also known as: *Agbe.*
Thunder deity. A member of the Vodu family of gods. In the Dahomey belief, Aylekete is the chief god of thunder. *See also* Agbe; Rada; Vodu.

Ayllu (Inca)
The spirit of dead ancestors. *See also* Ka (Egypt).

Aymur (Ugaritic)
A magic weapon. *See also* Kothar and Khasis.

Ayodhya (India) Capital city of Rama. *See also* Sagara.

Aywil *Aiwel* (Dinka People, Africa)
Also known as: *Aiwil Longar.*
Spear god. Ancestor. Founder of Dinka religion. Born with great power and a full set of teeth, Aywil is the son of the creator goddess of women and gardens, Abuk. Aywil preached that people had to pray through his son, Deng, and his mother, Abuk. The first man, Diing, disagreed and finally it was decided that Aywil would control the sky and rain, while Diing would have the earth. As "spear master," he gave the first spears to men after an altercation with a man named Agothyathik. *See also* Abuk; Deng.

Az (Manicheism, Zoroastrian; Persia)
In the *Avesta,* Az appears as a minor male demon. In the Zoroastrian faith, Az is represented as the female prototype of "wrong-mindedness." In Manicheism, Az is also a female demon who is responsible for blinding man to his divine origin. *See also* Vohu Manah.

Azacca (Haitian)
God of agriculture. He is said to be brother of Ghede. His origin could be Indian rather than African.

Azai-Dahaka (Persian) *see* Azhi Dahaka.

Azapane (Sudan, Africa) *see* Bele.

Azariel (Hebrew)
This angel, invoked by people who fish, is responsible for the earth's waters.

Azazel *Azazil* (Arabic, Hebrew, Persian)
Also known as: *Eblis, Iblis* ("The Calumniator," Islamic), *Satan* ("The Hater"), *Shaitan, Taus, Zeraili* (Islamic; Africa).
A fallen angel, he is called a desert fiend and a seducer of women. He is the governor of the earth and the lowest heaven. In the African Islamic tradition he is the angel of death. Other accounts vary; one holds that after God created Adam, he commanded the angels to worship man. Azazel, at that time an angel, refused. God turned him into a devil and he became Iblis, the father of all evil genii. In another account, all the angels including Azazel gathered to look at the clay that their god intended to shape into the first man, Adam, who was to be superior to the angels. Azazel vowed never to accept man's superiority and kicked the clay until it rang. As Iblis, he had five sons Awar, Dasim, Sut, Tir, and Zalambur. In other accounts, he is the father of Sut and Ghaddar by a wife created by Allah. The thorny acacia bush was sacred to him according to Arab tribes. His name is pre-Jewish and pre-Islamic. Some speculate that he may have been an early Semitic goat god whose worship later became repulsive to the Jewish and Islamic faiths. Azazel is also known as Taus, the peacock angel. Sometimes Azazel is called Shaitan. *See also* Adam; Angra Mainyu (his Zoroastrian counterpart); Azrael; Daevas; Dasim; Devil; Jinn; Satan; Tiur.

Azazil (Middle Eastern) *see* Azazel.

Azdahak (Persia) *see* Azhi Dahaka.

Aze (Japan) Female pine tree spirit.

Azhdak (Persia) *see* Azhi Dahaka.

Azhi (Persia) *see* Azhi Dahaka.

Azhi Dahaka *Azai-Dahaka* (Iranian), *Azdahak, Azhdak, Azhi, Azi, Azi-dahak, Azi Dahaka* (Iranian, Zoroastrian; Persia)
Also known as: *Ahi* ("The Throttler; India) *Bivar-asp, Dahhak, Vishapa* ("Whose Saliva Is Poisonous"), *Zahhak, Zohak.*
His name means "Fiendish Snake." His greatest desire is to exterminate mortals from the face of the earth. He is one of the numerous demons created by Angra Mainyu to destroy the faithful. If he were cut open the whole world would be crawling with serpents, lizards and scorpions. In the *Avesta,* he ruled the second millennium of human history (the eighth of creation). In the "Bundahish," he is the son of fiendish demon Angra Mainyu by Angra Mainyu's mother, Autak. Azhi Dahaka, in an attempt to conquer Yima, was captured by Thraetaona and chained to Mount Demavand. He will remain there until the end of history. At that time, he will devour one-third of the mortals and one-third of the vegetation of the world. When Keresaspa is resurrected, he will slay Azhi Dahaka. This evil fiend evolved into the mythical king of Babylon, Zohak, who was an enemy of Persia. In Zoroastrian myth, Azhi Dahaka was

overcome by Faridun and chained to Mount Demavand. The last of his dynasty and that of the serpent-worshipping kings of Media is known as Bevarash. He is variously described as a three-headed serpent; a serpent with three mouths, triple heads, and six eyes; sometimes seven heads; or as a man with two serpents growing from his shoulders. *See also* Ahi; Ahura Mazda; Angra Mainyu; Atar; Avesta; Bundahish; Bushyansta; Demavand (Mount); Drujs; Faridun; Keresaspa; Thrita (for Thraetaona); Verethraghna; Yima; Zohak.

Azidahaka (Persia) *see* Azhi Dahaka; Azi; Drujs.

Aziza (Dahomey People, Africa)
Forest spirits who give magic and knowledge of the worship of gods to mortals.

Azrael (Hebrew, Muslim)
He is the angel of death who watches over the dying. At the moment of death he separates the soul from the body. At Judgement Day, Azrael will be the last to die. His death will come when the Archangel's horn sounds the second time. *See also* Angels; Azazel.

Azrua (Gnostic)
High god. A name for the supreme being who some believe is the equivalent of Zervan. (It is likely a corruption of Ahura Mazda or possibly the Sanskrit Asura.) In the context of the Manichaean belief it means the "King of the Paradise of Light," but not the highest god. That name is reserved for Fihrist. *See also* Ahura Mazda; Zervan.

Aztec People — Creation Legend (Mexico) *see* Chicomontoc, Legend of the Five Suns.

Aztlan (Aztec, Mexico)
Aztlan is the legendary home of the Aztecs. There are seven cities in Aztlan that correspond to the seven tribes, or seven sons, of Mixcoatl. *See also* Mixcoatl; Ixtaccihuatl.

Azur (Assyria, Sumer) *see* Ashur.

B

B (Maya)
Carrying the axe and fasces, this thunder god is depicted frequently on statues and in ancient manuscripts. He may be the thunder god Chac (q.v.). *See also* "K."

B-Iame (Australia) *see* Baiame.

Ba (Egypt)
Also known as: *Bia, Ka* (Spirit), *Kah, Khu* (Mummy), *Ta* (Shade).

Soul of the Dead. The Egyptians believed that each mortal was made up of three parts: the Ka (the double), Ba (the soul), and the Akh (glorified spirit). The Ba departs the body temporarily after death, returning to the mummy to preserve it. Once the body is buried, the Ba continues to visit the cemetery at night and is given refreshments by Neith, Hathor, or other tree of life goddesses. Ba is usually shown as a hawk with a human head. Ka is shown as a heron. *See also* Ab; Akh; Amenti; Assessors; Hathor; Ka; Neith.

Ba Neb Tetet (Egypt) *see* Banededet.

Ba-neb-tettu (Egypt)
Creator god. *See also* Hathor; Heru-pa-kaut.

Ba-Ra (Egypt) *see* Aai.

Ba-tau (Phoenician)
He is either the brother of Hay-Tau or an incarnation of Hay-Tau (q.v).

Ba Xian (China) *see* Eight Immortals.

Ba'al (Phoenicia) *see* Baal.

Baal *Ba'al Bal, Bel, Belu* (Babylonia, Phoenicia, Sumer, Syria)
Also known as: *Aleyn Baal, Armen, Ba'al Lebanon, Ba'al of Tyre, Ba'al Shamin, Ba'al Tsaphon* ("Lord of the North"), *Ba'al-zebub, Ba'alim, Baalim, Baalsamame, Balsamem, Balshameme, Barshamina, Bel* (Sumer, Babylonian), *Belshim, Belu, Belus,* (Phoenician), *El, Elagabalus* (Roman), *Great Baal, Hadad, Melkart* ("God of the City"), *Rider of the Clouds.*

Baal is a title meaning lord, or master. The Phoenicians used the title to disguise the real name of the god. They feared that strangers would win the god's favor if they knew his true name. There were many local Baals. The greatest, known as the "Great Baal," is the son of the Father of the gods, El, and brother of the god of seas and rivers, Yam-Nahar. Baal, known as "Rider of the Clouds," is a fertility god representing the beneficent aspects of water as rain. His lightning and thunder depict his power, and the fertile earth his beneficence. In conflict with Yam-Nahar, who was El's favored son, Baal eventually subdued him. After his victory, his home of cedar and brick seemed inappropriate. Baal wanted a grander dwelling, like the other gods. With his sister Anath, he approached Asherah, goddess of the sea and mate of El, and asked her to intercede on his behalf and make his request known to his father El. Permission was granted and it was decided that the abode would be constructed from the tree of Lebanon, the cedar of Antilebanon, and with lapis-lazuli, gold, and silver. Kothar-u-Khasis,

www.ebook3000.com

the god of crafts, was called in to work on the project. Baal argued with the contractor, insisting that his home be built without windows. It is thought that he did not want Yam-Nahar to see him frolicking with his lovers. Kothar-u-Khasis prevailed and it was finally agreed that there would be a window in the edifice. This window was ostensibly for Baal to use to send out his thunder and lightning. Upon completion of the home, Baal arranged a magnificent celebration. A host of family, including Asherah's seventy children, were invited. His father, El, had a new favorite: the god of the underworld and sterility, Mot, who represents aridity. Baal sent his messengers Gapn and Ugar to inform Mot that he was not invited to his celebration. Displeased, Mot returned a threatening message. Victorious over Yam-Nahar, Baal now had to deal with Mot. The message frightened him, and he responded that he was Mot's slave forever. In one interpretation, Baal was devoured by Mot. Mot was then forced to regurgitate him by Baal's sister, Anath, with the aid of Shapash. In another rendition, El, grief-stricken when he heard of his son's death, wandered around lamenting and gashing himself. Anath searched for her brother and when she found his body Shapash helped her carry it to Mount Zaphon. A great funeral feast was held in his honor. Anath went in search of her brother's murderer, Mot. When she found him, she brutally massacred him. After a time, El had a dream that Baal was still alive. Joyously, he announced the news to Anath and Shapash. His absence had left the soil dry and parched. Lady Asherah of the Sea had put her son Ashtar on the throne during Baal's absence. He found that his feet would not touch the footstool, nor his head the top of the throne, so he declined to rule in the heights of Mount Zaphon. Baal was eventually found and restored to the throne. His battle with Mot was renewed. After an intense struggle, they both fell to the ground and were separated by Shapash. It appears that they came to a meeting of the minds for Baal was restored to his throne. Baal's name as the god of thunder and lightning is Hadad. As Hadad, he sent monstrous creatures to attack Asherah and the moon god, Yarikh. They appealed to El for assistance. He advised them to hide in the wilderness and give birth to wild beasts so that Hadad would be distracted and chase the beasts. As forecast, Hadad hunted the monsters. He was captured by them and disappeared for seven years. During this period, the earth fell into what is described by some as chaos but may have been a severe draught. In a Canaanite myth, Anath is looking for Baal, and is told by his servants that he is hunting. She searches for him and when they meet he falls in love with her. Although she is in the shape of a cow, they have sex. From this union, a wild ox was born. Baal is portrayed as a bull, the emblem of animal and vegetable fertility. *See also* Anath; Asherah (B); Bod-Baal; El (the father god was the equivalent to Enlil and at times they were identified with each other); Hadad; Kothar and Khasis; Mot; Shapash; Yam-Nahar; Yarikh.

Baal Enet Mahartet (Ugarit)
Rain god.

Ba'al Hammon *Baal Hammon* (Carthage)
Also known as: *Aleyn-baal.*
Sky god. Fertility god. Husband of Tanit. He appears to have been worshiped along with Tanit Pene Ba'al (a little known goddess). Romans thought him to be the god Jupiter Ammon from Africa. He is shown as a bearded old man wearing ram's horns on his head. The bull is a manifestation of Baal among the Canaanites. *See also* Aleyn-Baal; Baal; Tanit.

Ba'al Lebanon (Semite)
God of lightning, rain, and thunder. *See also* Baal.

Baal-Peor (Moabite) *see* Chemosh.

Baal Sapon (Canaanite, Hurrite, Syrian)
Ancient god similar to Jupiter.

Baal Shamin *see* Baalshamin.

Ba'al Shamin *Balsamem, Balsamin, Balshamin, Balshameme, Belshim* (Arabic, Armenian, Hittite, Phoenician, Semitic, Syrian)
Also known as: *Baal, Adad.*
"Lord of the World." "Good and Rewarding God." "Master of the Skies." Ba'al is the head of the pantheon consisting of Dur-Europas, Hatra, Palmyra, Shahr and Shamash. His chief opponent is Vahagn. In some renditions, Vahagn was responsible for stealing Ba'al Shamin's wife Astaik. As a Syrian deity, he was destroyed by the Armenian god, Aram. As an Armenian god, originally from Phoenicia, Ba'al Shamin is known for his heroic deeds. *See also* Adad; Aleyn-Baal; Armenak; Astaik; Baal; Vahagn.

Baal-Sutekh (Egypt) *see* Anat.

Ba'al Tsaphon (Semite) *see* Baal.

Ba'al-zebub *Baalzebub, Ba'al-zebul, Beelzebub, Beelzebul* (Semite)
Also known as: *Fly.*
Demon. Lord of Flies. Lord of Zebulon. God of the city of Ekron. Although frequently called Beezlebub, it is an incorrect name for him. Some writers say the early Hebrews changed the name of Yahveh to Ba'al-zebub because they couldn't associate an idol with their god. He is similar to Satan. *See also* Baal.

Ba'al-zebul (Semitic) *see* Ba'al-zebub.

Ba'alat *Baalat, Baalath* (Semitic), (Phoenicia, later connected to the Egyptians and Semites)
Also known as: *Baaltis, Belili, Beltis, Belit.*
"The Lady." "Queen of Gods." Goddess of books, libraries, writers. She is the female equivalent of Baal. Her principal city is Byblos, which gave humans papyrus. (Papyrus was called Byblos by the Greeks, who then applied the same word to books.) She is depicted with an elaborate Egyptian hairstyle, wearing a tight robe, with shoulder straps. Her dress on a cylinder seal resembles that worn by the goddess Hathor. The Phoenicians depicted her generous body naked, with her hands covering her full breasts. She is sometimes identified with the Egyptians Isis and Hathor. Ba'alat corresponds to Baalti and Beltu. *See also* Cybele; Ishtar.

Baalath (Semite)
The female aspect of Baal. She is identical to Ba'alat, Baalti and Beltu.

Ba'alim (Semite) *see* Baal.

Baalim (Phoenician) *see* Baal.

Baalith (Middle East) *see* Belili.

Baalsamame (Phoenician) *see* Adad; Baal.

Baalshamin (Mesopotamian) *see* Ba'al Shamin.

Baalti *Belti* (Phoenician) *see* Belti.

Baalzebub (Phoenician) *see* Ba'al-zebub.

Baau (A) (Assyro-Babylonian) *see* Bau; Tiamat.

Baau (B) (Phoenician)

In the Creation Myth of "Philo Byblos," she is the spouse of Kolpia, and the mother of Aion and Protogonos. *See also* Kolpia.

Bab (Egypt)

Also known as: *Baba, Set, Seth.*

Trickster. In legend, this roguish god upset the tribunal during the trial between Osiris and Seth. *See also* Neith.

Baba (Egypt)

Another name of the evil god Seth. The name generally means parent or father. *See also* Ab.

Baba Yaga *Baba Jaga* (Russian, Slavic)

Deity of the dead. Baba Yaga is a thunder witch and the grandmother of the Devil. This supernatural hag lives in a house with a picket fence tipped with skulls. She rides through the sky in an iron cauldron and sweeps away the traces of her passage with her broom. (Some say her chariot is a mortar and pestle.) She eats or petrifies her victims. *See also* Bertha (German).

Babas (Armenia)

An ancient Armenian deity. The name may just mean "father." *See also* Ab; Baba.

Babbar (Sumer)

He is the sun god of Larsa, and a member of the earliest Sumerian pantheon. *See also* Shamash; Utu.

Babhru-Vahana *Babru-Vahana* (India)

He is the son of Arjuna and Chitrangada. *See also* Arjuna.

Babru-Vahana (India) *see* Babhru-Vahana.

Babusum (Saora People, India)

This guardian god rides on a horse through each village nightly. *See also* Ajorasum.

Babylonian — Creation Legend (from Berosus) *see* Belus (C).

Babylonian — Creation Legends (from Damascius) *see* Aus; Belus (C).

Babylonian — Creation Legend (Chinese, Greek) *see* Chaos.

Bacab (Maya) *see* Becabs.

Bacchantes *Bassarids* (Greek) *see* Dionysus; Maenads.

Bacchus *Bakchos, Bakkhos* (Roman, Arabic, Egypt, Ethiopia, Greek, Phoenicia, Roman, Semite)

Also known as: *Dionysus* (Greek), *Iacchus, Lakchos, Liber, Orotal, Salmoxis, Zalmoxis.*

Originally a nature god. Later a god of wine and revelry. Fertility god. The worship of Bacchus was carried into Greece where he became the Greek Dionysus. However, he was also known as Bacchus (indicating noisy and rowdy) by the Greeks and Romans. The eternally youthful Bacchus represents the social and beneficent aspects of wine, as well as its intoxicating properties. He is the son of Semele and Jupiter. Semele had encouraged Jupiter to come to her in his divine splendor. He reluctantly agreed. When he appeared before her as thunder, she was killed by lightning. Jupiter was able to save their unborn child, Bacchus. After the death of Semele, Jupiter placed Bacchus with the Nysaean nymphs. While growing up he became familiar with the properties of grape growing. Juno, the enemy of his mother, struck Bacchus with madness. Bacchus set off in his altered consciousness to wander the earth. The goddess Rhea cured him in Phrygia. He left the area and traveled through Asia and India teaching the people how to cultivate the grape vine. When he returned to Greece, the rulers, particularly Pentheus, who feared the negative effects of the grape juice, refused to receive him. Pentheus' mother, Agave, and her friends, members of the Bacchus cult, were extremely unhappy with his stance. Likely in a highly inebriated state and full of anger, she tore her son Pentheus apart. At another time in Bacchus' travels he was on a ship en route to Asia. The sailors, who were really pirates, came up with the idea that they could make extra money by selling Bacchus into slavery. They threatened Bacchus, who was not happy with their plan. Using his skills as a deity, he changed himself into a ferocious lion. The ship, at his command, became a vessel of serpents with jungle-thick plant life covering it. When he added music to the air, he terrified the pirates. They plummeted to their deaths in the sea where they became sweet, docile dolphins. Bacchus is shown in purple robes in peacetime and wearing panther skins in time of war. In early representation he was a pillar of stone and is sometimes shown as a goat. The goat is a symbol of fertility as well as lasciviousness, agility, and sociability. It also symbolizes stupidity and stench. He is also depicted seated in a chariot drawn by panthers, leopards or tigers. He is crowned with vine leaves, and is surrounded by a group of intoxicated satyrs and nymphs. The staff is his attribute as it is for Asclepius, Dionysus, Hermes and Mercury. The symbolism of the staff represents support or an instrument of punishment. Red wine symbolizes blood and sacrifice, as well as youth and eternal life. The grape represents fertility and sacrifice, for from the grape comes the wine. Bacchus is the personification of the sun as ripener. The ass was sacred to Bacchus as well as Silenus. This animal symbolized wisdom and prophetic powers. The bull with a human face represents Bacchus. (Pan wore the ears of an ass to indicate acute perception.) Compare Bacchus to Set (Egypt), for whom the ass was an insignia. Sometimes Bacchus is identified with Liber. *See also* Bes; Dionysus; Juno; Maenads; Rhea; Satyrs; Semele; Silenus.

Bach-ma (Indo-China) *see* Ma-Mien.

Bachis (Egypt) *see* Buchis.

Bachue (Chibcha People, Colombia, South America)

Also known as: *Turachogue.*

Goddess of water. Goddess of farming. Protector of vegetation and harvest. Bachue emerged from her home under the waters of Lake Iguaque bearing a small boy with whom she later mated. They had four or six children, although some myths say they created the human race. When she was content that mortals could live without her, she transformed herself and her mate into dragons. They returned to their home in the lake, where they still reside. *See also* Bochica; Chiminagua.

www.ebook3000.com

Backlum Chaam (Maya)
God of male sexuality. One of the Becabs, he is similar to Priapus of the Greeks (who is originally from Asia). *See also* Acat; Becabs.

Badari *Bhadri-Nath* (Hindu; India)
An ancient title for Shiva, later given to Vishnu as Lord of Badari, a shrine on the Ganges. Durga was called Bhandrakali. The name is connected with Bhadra or Bhandra which means "piety." In the Maratha country he was worshiped as Bhadra Vira. Under this name, he is depicted with the sun and moon, and is mounted on Nandi, the sacred cow. The goat-headed Daksha accompanies him. Badari is armed with a bow and arrow, sword, spear, and shield. *See also* Daksha; Durga; Nandi; Shiva; Vishnu.

Badava (India) *see* Vadava.

Badb Catha (Celtic, Irish)
Also known as: *Badb, Badhbh, Battle Raven, Cauth Bodva* ("War Fury," Gaul), *Morrigu* (possibly).
"Battle Raven." Goddess of war. Goddess of death. Storm goddess (possibly). Death is eminent when the Celtic fury Badb Catha appears. After the Battle of Moytura when the Tuatha De Danann's fought and drove away the Formonians, Badb recounted the event and prophesied doom. There is a possibility that Badb Catha is an incarnation of the goddess Morrigu. Badb later deteriorated into the Banshee. She is usually depicted as a crow, sometimes as a bear, wolf, cow, a foul hag, a gigantic woman, or a beautiful young woman. *See also* Banshee; Bean-Nighe; Morrigu.

Badessy (Dahomey People, Africa; Haiti)
Sky god. Badessy is a minor deity who was worshiped along with the male deities called hougouns and the females called mambos.

Baduh (Semite)
Invoked by writing the numerals 8, 6, 4, 2, (these numerals represent the letters in the Arabic alphabet that form his name), Baduh insures that messages are quickly delivered.

Baduhenna (Teutonic)
Goddess of war and storm goddess.

Baeldaeg (Teutonic) *see* Balder.

Bafur *Bavor* (Teutonic) *see* Dwarfs.

Bag-Mashtu (Iranian; possibly a local god of the earlier Urartian people)
Also known as: *Bag-Mazda*
Sky deity. He is often confused or identified with Ahura Mazda. There is a possibility that he is an ancient form of that god. Bagos Papaios, the Phrygian sky god, might be associated with Bag-Mashtu. *See also* Bagos Papaios; Khaldi.

Bag-Mazda *(Persia) see* Ahura Mazda.

Bagadjimbiri (Aborigine People, Australia)
Creators. They are two heavenly brothers who created everything. They started out as Dingos (wild dogs), but changed to giants, whose heads touched the sky. They had a great deal of hair that they pulled out and gave to every tribe. They were killed by a man, but Dilga, their mother, detected the odor of the corpses and sent the milk from her breasts underground to where they lay. It revived them and killed the man. The brothers eventually became water snakes.

Bagavatcbi (India) *see* Parvati.

Bagos Papaios (Pyrygian)
Sky deity. This little known deity of the early Pyrygian people might have been worshiped with the earth goddess, Semele. She is possibly identified with Kybele and Ma. *See also* Bag-Mashtu; Semele.

Bahman (Persia) *see* Vohu Manah.

Bahram (Islamic) Protector of travelers. *See also* Verethraghna.

Bahu (India) *see* Bau; Bohu; Sagara.

Bai Ulgan *Bai-Ylgon* (Altaic, Tartars)
Also known as: *Kudai Bai-ulgon.*
A high god, his name means "Most Grand." He lives in the sixteenth heaven on the Golden Mountain. His three sons are Pyrshak-khan, Tos-khan, and Suilap. Two of his grandsons, Kyrgys-khan and Sary-khan, are gods of happiness. Later, he was replaced by Tengere Kaira Kan, to whom horse sacrifices were offered. *See also* Tangri.

Bai-Ylgon (Altaic, Tartars) *see* Bai Ulgan.

Baiame (Aborigine People, Australia)
Also known as: *B-Iame, Biamban, Birral, Bunjil, Byamee, Daramulun, Kohin, Koin, Maamba, Munganngaua, Nurelli, Nurrundere.*
Father of all things and master of life and death, Baiame resides in a sky palace constructed of fresh water and quartz crystal. It is generally thought that at one time he lived on earth. Invisible, sometimes he appears as a human in the form of an old man. He is the father of Daramulun. Sometimes he is depicted as an old man sitting with his legs under him or sometimes asleep. Baiame, the force of good, is opposed by the Darawigal, the force of evil. *See also* Bunjil; Daramulun; Nurrundere.

Baidya-isvar (India) *see* Shiva.

Baidya-nith *Byju-Nath* (Hindu; India)
Little is known about this ancient deity, but some say Shiva changed his name to Byju to please an aboriginal worshiper at the shrine of Baidya-Nath. As Baidya is also the name for some of the peaks of the hills, it could signify Baidya-nith as a deity of the hills or mountains.

Bairam (Persia)
A later name for the god of victory Verethraghna (q.v.).

Bairavi (India) "The Terrible." *See also* Kali.

Baiyuhibi (Indonesia)
God of clouds, fog and rain. Creator of mountains and valleys.

Baj Bajaniai *Bajanai* (Yakut People, Siberia)
Forest god. God of hunters. His tears are rain and his voice the wind. In some instances, his game herd is called Baj Bajaniai.

Bajanai (Siberia) *see* Baj Bajaniai.

Bajang *Badjang* (Malaysia)
A malignant spirit who foretells disaster.

Bak (India) *see* Vach.

Bakasura (India) A demon. *See also* Krishna.

Bakchos (Greek) *see* Bacchus.

Bakh (Egypt) *see* Buchis.

Bakha (Egypt) *see* Buchis.

Bakkhos (Greek) *see* Bacchus.

Bala-Bhadra (India) *see* Bala-Rama.

Bala-Deva (India) *see* Bala-Rama.

Bala-Hadra (India) *see* Bala-Rama.

Bala-Rama (Vedic, Hindu; India) *Balarama*
Also known as: *Bala-Bhadra, Bala-Deva, Bala-Hadra, Gupta-Chara, Hala-Bhrit, Hala-Yudha, Halayudha* (Whose Weapon Is a Ploughshare), *Kam-Pala, Langali, Madhupriya* (Friend of the Wine), *Musali, Nila-Vastra, Sankashana, Sesha, Silappadikaram* (Tamil People, India).

Bala-Rama, the god of shepherds and ploughers, is the elder brother of Krishna. It had been ordained by the gods that order had to be restored to the earth. Vishnu, therefore, created an avatar of himself in the form of Krishna to combat the forces of evil. Vishnu plucked a white hair from Seshu the serpent that would become Bala-Rama and a black hair from his body that would become Krishna. These hairs were placed in the womb of Devaki, the wife of Vasudeva. When the demon Kansa heard about the impending birth of forces that would kill him, he ordered that Devaki's first six children be slaughtered. Bala-Rama was transferred to the womb of Rohini, the other wife of Vasudeva. The demon Kansa was told that Devaki had miscarried. When Bala-Rama was older, he ploughed the course of the river Yamuna with his ploughshare Hala, and created all things with his club, named Khetaka (also named Saunanda), and Musala, his pestle. Bala-Rama shared many of Krishna's adventures and assisted him in slaying many demons. He instructed Bhima and Duryodhana in the skills of warfare. Later, in the great war of the Mahabharata, he rescued Krishna's son Samba from Duryodhana. He did not participate in the battle between his cousins, the Kauravas and the Pandavas. King Raivata thought that his daughter Revati was too beautiful to be the wife of a mortal. He searched for and found the god Bala-Rama. Bala-Rama and Revati had two sons, Nishatha and Ulmuka. In the Vaishnava tradition, Bala-Rama is considered Vishnu's eighth avatar instead of Krishna, who is considered a god in his own right. Others say that Bala-Rama is an avatar of Vishnu's endless, thousand-headed serpent, Sesha. When he died, under the Banyan tree in Krishna's celestial abode Dvarka, Sesha slithered out of his mouth and flew to Vishnu's ocean. A marvelous funeral was held for Krishna and Bala-Rama. When Vasudeva, Devaki and Rohini heard of Krishna's death, they died of grief. Krishna's eight primary wives, Bala-Rama's wives, and King Ugrasena threw themselves on the funeral pyre and burned to death. Bala-Rama is described as being of fair complexion and wearing a blue vest. Compare Bala-Rama to Heracles. *See also* Bana; Bhima; Devaki; Duryodhana; Jagannath; Kaliya; Kansa; Kauravas; Krishna; Pandavas; Sesha; Sisupala; Syamantaka; Yami.

Balam (Quiche People, Central America)
A jaguar god. *See also* Gucumatz.

Balam-Agab (Maya) *see* Xumucane.

Balam-Quitze (Maya) *see* Xumucane.

Balamma (India)
She is one of the Mutyalammo goddesses who are deities of the household. Her function is to preside over the family carts. *See also* Mutyalammo.

Balams (Quiche People, Central America)
The Balams are the ancestor gods of the Quiche. *See also* Gucumatz.

Balan (Celtic) *see* Bel (B).

Balandhara (India) *see* Bhima (A).

Balarama (India) *see* Bala-Rama.

Balbog (Slavic)
Also known as: *Belbogh, Bjelbog.*
Sun god. He is often called the "Pale One," or the "Shining One." Balbog is similar to Balder.

Baldag (Teutonic) *see* Balder.

Balder *Baldr, Baldur* (Norse; Teutonic)
Also known as: *Baeldaeg, Baldag, Beldeg, Beldegg, Paltar, Wodan* (later Germanic form).

Sun god. God of innocence and piety. Balder is the son of Odin and Frigga, and the brother of Hermod. Nanna is his wife and their child is Forseti, the dispenser of justice. Balder lives in his zodiacal house, Breidablik, which corresponds to the sign of Gemini, the twins. When Balder had a series of troubling nightmares about death, he reported them to the Aesir council. The goddess Frigga listed all things and commanded that nothing would harm Balder, but she neglected to include mistletoe. In one myth, Loki the jealous fire god and trickster was aware of Frigga's omission. He persuaded the blind god of darkness, Hodur, to throw either the mistletoe branch, or sprig, or a spear, or in some myths, a magic sword named Mistelteinn. It hit Balder and he fell dead. His ship, Hringhorn, became his funeral pyre. Nanna committed suicide. Odin's son Hermod, who was a messenger for the gods, took his father's horse Sleipnir, and rode it to Hel in an attempt to rescue Balder. In one myth he offers to pay a ransom for Balder's return. Hel agreed, with the stipulation that everything in the world, dead and alive, must weep for Balder. The magic ring, Draupnir, which had been placed on his funeral pyre, was given to Hermod by Balder, to be given to Odin. Nanna, who also had a magic ring, gave it to Hel to give to Fulla. Hermod returned to earth where everything dead and alive wept for Balder, except for Loki, the trickster fire god, who had disguised himself as a female giant named Thok. Balder could not return to earth. He is expected to return with several other gods and two humans after Ragnarok (also known as "The Twilight of the Gods"). Balder's death was

www.ebook3000.com

Acknowledgments

The Universal Tao Publications staff involved in the preparation and production of *Cosmic Healing I: Cosmic Chi Kung* extend our gratitude to the many generations of Taoist Masters who have passed on their special lineage, in the form of an unbroken oral transmission, over thousands of years. We thank Taoist Master I Yun (Yi Eng) for his openness in transmitting the formulas of Taoist Inner Alchemy.

Thanks to Juan Li for the use of his beautiful and visionary paintings, illustrating Taoist esoteric practices.

We offer our eternal gratitude to our parents and teachers for their many gifts to us. Remembering them brings joy and satisfaction to our continued efforts in presenting the Universal Tao System. For their gifts, we offer our eternal gratitude and love. As always, their contribution has been crucial in presenting the concepts and techniques of the Universal Tao.

We wish to thank the thousands of unknown men and women of the Chinese healing arts who developed many of the methods and ideas presented in this book. We offer our graditute to Master Lao Kang Wen for sharing his healing techniques.

We wish to thank Colin Campbell for his editorial work and writing contributions on the first printing of this book, as well as his ideas for the cover. We appreciate his research and great labor. We wish to thank Matt Gluck for his editorial contributions on the revised edition of this book, as well as thanking our instructors, Dennis Huntington and Annette Derksen, for their insightful contributions to the revised version. We thank Dirk Oellibrandt for his technical editing and clear writing throughout the book.

A special thanks goes to our ***Thai Production Team*** for their cover illustration and book design and layout: Raruen Keawapadung, Computer Graphics; Saysunee Yongyod, Photographer; Udon Jandee, Illustrator; and Saniem Chaisarn, Production Designer.

Thanks to the testing institutes: Gerhard Eggelsberger, Institute for Applied Biocybernetics Feedback Research, Vienna, Austria and Dr. Ronda Jessum, Biocybernetics Institute, San Diego, California.

We also wish to express thanks to Cosmic Healing Certification Retreat Organizers around the world who have worked with us for many years and helped us prepare this manuscript throughout the Retreats: Beate Nimsky, Vienna, Austria; Serguei Orechkine, Moscow, Russia; Christopher Larthe, London, England; Masahiro Ouchi, Rye, New York; Dr. Angela C. Shen, San Francisco, California; Dirk Oellibrandt, Hamme, Belgium; Brita Dahlerg, Frankfurt, Germany and Lizbeth Cavegn, Zurich, Switzerland.

We wish to further express our gratitude to all the instructors and students who have offered their time and advice to enhance this system, especially Felix Senn, Barry Spendlove, Chong-Mi Mueller, Clemens Kasa, Andrew Jan, Marga Vianu, Harald Roeder, Salvador March, Dr. Hans Leonhardy, Peter Kontaxakis, Thomas Hicklin, Gianni Dell'Orto, Walter and Jutta Kellenberger.

avenged by Vali who is a son of Odin and Rind. Balder is depicted as a very handsome man. Balder is associated with Heimdall (q.v.). He corresponds to the Slavic Byelobog, and is similar to the Slavic god Balbog (qq.v.). *See also* Aesir; Asmegir Citadel; Balbog; Boe; Breidablik; Draupnir; Forseti; Frigga; Hel; Hermod; Hodur; Loki; Miming; Nanna (A); Njord; Ragnarok; Rind; Skadi; Sleipner; Thok; Thor; Vali; Vanir; Wodan.

Baldr (Teutonic) *see* Balder.

Baldur (Teutonic) *see* Balder.

Baleyg (Teutonic)
"One with Flaming Eyes." Another name for Odin.

Bali (A) *Balin, Wali, Valin* (Hindu; India)
The giant ape and monkey prince Bali is the son of Indra and the half-brother of Sugriva. They shared the same mother, who was a monkey queen. Bali had a long and powerful tail. Once, the king of the demons, Ravana, came up behind him and grasped it as Bali was performing ablutions. Without missing a beat, Bali used his tail to tie Ravana's hands and feet. He set out on a jaunt to visit the western, eastern and northern oceans with the demon held captive on his tail. He kept him that way for twelve years. As the son of Indra, he was endowed with more power than Sugriva. He had the ability to look at anyone and assume half of that person's strength. He usurped his brother from the throne and held reign as King of the Monkeys until he was killed by Rama. His spouse was Tara, also known as Dara, and he had a son, Angada. *See also* Indra; Rama; Ravana; Sugriva.

Bali (B) *Baly* (Brahman, Hindu; India)
He is the demon grandson of Prahlada; son of Virochana; spouse of Vindhyavali; and the father of Bana (also called Vairochi), the demon with a thousand arms, and a daughter Putana, who had poisonous breasts. His austere devotions earned him the authority to reign over the three worlds known as Triloka. Triloka consists of akasa (heaven) where the sun shines but there are no clouds, apas (atmosphere) where clouds are found, and vasumdhara (earth) where mortals are generally found. His power was a threat to the gods, so Vishnu, in his dwarf avatar as Vamana, asked Bali if he could have as much land as he could cover with three steps. When Bali consented, Vamana immediately assumed his cosmic size as Vishnu and with one step covered the earth from one end to the other. His second step covered the heavens. His third step could have covered the entire underworld but he left the lowest portion, known as Patala, for Bali. In another legend, a battle took place between Indra and the demons led by Jalandhara. Bali was struck, and when he fell, a flood of jewels came from his mouth. Indra threw his vajra (thunderbolt) at him and ripped him to pieces. Because of his severe austerities and pure conduct, precious jewels came from various parts of his body and his blood was changed to rubies. *See also* Bana; Daityas; Krishna; Nara-Simha; Patala; Prahlada; Surya; Vamana; Vishnu.

Balin (Celtic) *see* Bel (B).

Balius (Greek)
This immortal horse and his brother, Xanthus, belonged to Achilles. They are the sons of Boreas and Podarge, the Harpy. *See also* Achilles; Boreas; Harpies; Podarge; Xanthus; Zephyrus.

Balmarcodes (Phoenician)
God of revelry and the dance. He is probably another form of Hadad. *See also* Hadad.

Balmung (Teutonic)
Also known as: *Gram.*
The dwarfs fashioned this magic sword for Siegfried. *See also* Sigurd.

Baloi (Basuto People, Australia)
The Baloi haunt graves. They are also known for working harmful magic on an extracted tooth and on the person who previously owned the tooth.

Bal'or (Celtic) *see* Balor.

Balor *Bal'or* (Celtic, Irish)
"Evil Eye." King of the Fomorians. The god Balor is the monster son of Buarainech and the grandson of Net. One of his eyes had been poisoned. Everything he glanced at could be destroyed. This one-eyed monster was the champion of the Fomorians. He was killed by a stone from the sling of his grandson, Lugh, that hit him in his only eye and scattered his brains in all directions. This took place at the second Battle of Moytura. His corpse was hung on the sacred hazel tree. Since that time, the tree has dripped poison. Balor now lives under the sea. Compare him to the Greek Acrisius. *See also* Cian; Dagda; Lugh; Yspaddaden (Welsh).

Balsamem (Mesopotamia) *see* Adad; Baal; Ba'al Shamin.

Balshameme (Mesopotamia) *see* Adad; Baal, Ba'al Shamin.

Balshamin (Mesopotamia) *see* Adad; Ba'al Shamin.

Baltein (Celtic, Irish) *see* Beltine.

Baltis (Phoenician)
Cronus gave the city of Byblos to this goddess. *See also* Dione.

Balubaale (Africa)
Spirit beings of the Bantu people of Africa. Some say this is a collective name for all the gods of earth, death, lightning, plague and the rainbow. *See also* Kibuuka; Mukasa.

Balujen (Tinguian People, Philippine Islands) *see* Adam.

Baly (India) *see* Bali (B).

Bamun Owtar (India)
An avatar of Vamana (q.v.)

Bana *Vairochi* (Hindu; India)
Bana, a demon with one thousand arms, is son of Bali and brother of a sister, Putana. She is the demon who nursed Krishna with her poisoned breasts and was subsequently killed by the god. Bana's daughter Usha was in love with Krishna's grandson Aniruddha. Bana brought the couple together by using his magic powers. Krishna and Bala-Rama attacked Bana. Skanda (also known as Karttikeya) and Shiva attempted to protect him, but Skanda was injured and Bana's arms were cut off. Krishna and Shiva engaged in a fight which Krishna won. Shiva pleaded with Krishna to spare Bana and his wish was granted. Bana is usually shown with multiple arms, riding in a chariot

drawn by lions. *See also* Bala-Rama; Bali (B); Karttikeya; Krishna; Shiva; Usha.

Banaded (Egypt) *see* Banebdedet.

Banalingas (Hindu; India)
Sacred stones, small and elliptical with a natural polish produced by the action of the river water. They are frequently found in the Narmada river, one of the sacred rivers of the Hindus, and are used as a symbol for Shiva.

Banana (Sumer)
The coachman for the sun-god Shamash.

Banba (Celtic) *see* Banbha.

Banbha (Celtic, Irish)
Also known as: *Banba.*

Death goddess. Banbha, according to an ancient document, is said to be the first person to settle in Ireland. At that time it was known as "the Island of Banbha of the Women," or "Banbha of Fair Women." In some myths, her father is Cain and in others, Dagda. Her sisters are Erui and Fotia, said to be the daughters of Cain. The three, known as the "Goddesses of Sovereignty," were worshiped as triple goddesses. Following Banbha's arrival on the island came Cessair and her group. They died, leaving one survivor. The race of Giants, known as Fomorians, followed and they were defeated by the Partholanians from Spain. They, too, died, save one, and the Nemeds, also from Spain, came ashore. The Fomorians regrouped and subdued the Nemeds until the advent of the Firbolgs, who came from Greece via Spain. They battled the Fomorians but were in turn conquered by the Tuatha De Danann. Banbha was the goddess-queen of the Tuatha De Danann; she and her sisters were married to the kings: Mac Cuill, Mac Cecht, and Mac Greine, who are also known as the "Kings of Tara." Amergin, the poet and judge of the Milesians (also spelled Melesians), was allowed to bring his people to the island after promising the goddesses to name an island after each of them. They opposed the Milesians with magic but were overcome by them. Compare Banbha to Morrigu. The Milesians are thought by some to have been the original Celts. They are shown with bird-like characteristics. The name Banbha means "pig," which is connected to cults of the dead. *See also* Amergin; Bress; Cessair; Dagda; Firbolgs; Fomorians; Partholanians; Tuatha De Danann.

Baneb Djedet (Egypt) *see* Banebdedet.

Banebdedet (Egypt) *Banaded*
Also known as: *Ba Neb Tetet, Baneb Djedet, Binded.*

A local deity, who later acquired greater status, Banebdedet is a god of arbitration. During creation Banebdedet settled an argument between Horus and Set by having them write a letter to the goddess Neith for her opinion. Banebdedet is a member of the Mendean Triad with Hetmehit and Harpakhrad. He is depicted as ram, or goat-headed. *See also* Horus; Neith; Set.

Banitu (Assyro-Babylonian) *see* Ishtar.

Banka-Mundi (Khond People, India)
Goddess of hunting.

Bannik (Slavic, Russian)
Spirit of the Bath. Bannik is one of a group of household spirits known as Domovoi. He is the spirit of the bath and he lives in the out-house. He allows only three bathers to enter. He is the fourth, and if someone tries to take his place in line, he pours hot water on the person. Bannik can foretell the future. To do so, the subject must place his or her naked buttocks through the half-open door of the bath house and wait. If caressed softly, the future will be bright, but if clawed, it is a bad omen. He is depicted as a wizened little character with straggly white hair and a beard. Sometimes Bannik lives under the toilet seat. The bather is advised to leave a little bath water and soap for Bannik in case he decides to bathe. There are instances when Bannik takes up residence under the stove. *See also* Chlevnik; Domovoi; Kikimora; Ovinnik.

Ban'shee (Celtic) *see* Banshee.

Banshee *Ban'shee, Banshie.* (Celtic, Irish, Scots)
Also known as: *Ban'sith* (Gaelic), *Bansith, Baobhan Sith, Bean-Nighe* (Scotland), *Bean Si, Bean-Sidhe* (Irish), *Caoineag, Caointeach.*

Banshee is presented by some as a female fairy and by others as a wind or death spirit. Originally, she may have been a princess of the Celtic hill people. When her wail is heard under one's window, it foretells death in the house. She is depicted wearing a grey cloak over a green dress. Her hair is long and streaming, and she has red eyes from weeping. Sometimes she appears as a beautiful woman. The Bean-Nighe of Scottish Highlands is more like a female ghost who died in childbirth, although she is called a water spirit and seer. She appears as a small-boned woman with long breasts who dresses in green. You can't mistake her. She has one nostril, one tooth, and red, webbed feet. If you can grab and suck one of her breasts, you will be granted any wish. Baobhan Sith is similar to Banshee but is a dangerous kind of succubus who is similar to a fairy rather than a god.

Banshie (Celtic) *see* Banshee.

Ban'sith (Gaelic) *see* Banshee.

Bansith (Gaelic) *see* Banshee.

Banyan Tree (India)
Sacred tree. *See also* Apsarases; Bala-Rama.

Baobhan Sith (Celtic) *see* Banshee.

Bar (Akkadian) *see* Adar.

Bara (A) (Aborigine People, Australian)
God of the northwest winds. He brings the monsoons from November to March. During the rest of the year he resides in a large hollow tree. It is believed that spirit children riding in on Bara's winds hide in the grass until they see the woman who will become their mother. *See also* Maijunga, the god of the dry season.

Bara (B) (Babylonian) *see* Baragulla.

Baragulla (Babylonian)
Also known as: *Bara.*

The son of Ea, Baragulla is an oracle god who reveals the future. *See also* Ea.

www.ebook3000.com

Barashakushu (Babylonia) *see* Marduk.

Barbelo (Gnostic)
Mother Goddess. Feminine power derived from the primordial father. She is the mother of Ialdabaoth or Sabaoth. Barbelo is associated with the Archons. Her origin is dated circa C.E. 150–180. Her name probably originated from the Gnostics who came from either Syria or Egypt. *See also* Archons; Sabizios.

Bardad (Semite) *see* Adad.

Barhishmati (India)
Daughter of the divine architect Visvakarma and sister of Sanja. *See also* Sanja; Viskvakarma.

Barku (Syria) *see* Rimmon.

Baron Cimetiere, Baron La Croix, Baron Piquant (Haitian)
Names used for Ghede, god of the dead. *See also* Ghede.

Barshamina (Mesopotamia) *see* Baal; Ba'al Shamin.

Bas (Egypt) *see* Bast.

Basileus (Greek) "The King." An epithet of Zeus.

Basilisk (Gnostic)
Deified creature. This frightening-looking lizard is able to run on water. Those who annoy it can be frozen in their tracks by its angry glare. It is generally found by those who are not looking for it in the inaccessible regions of the Swiss Alps and the African deserts. It has the body and wings of a dragon and the head of a serpent. It is usually shown with its tail in its mouth. Sometimes it is depicted as half cock and half snake. Basilisk is connected with Gnostic Abraxas in that Agathodemon or "good spirit" was said to have hatched by a cock from a serpent's egg. *See also* Abraxas.

Bassareus *Bassarides* (Greek)
They are the followers of Dionysus. *See also* Dionysus.

Bast *Bas* (Egypt)
Thought by some to be of Semitic or Phoenician origin (perhaps connected with the Hebrew Bosheth).
Also known as: *Bastet; Bubastis; Oubastet; Pakht; Pasht; Sekhmet.*
Cat goddess of life, fruitfulness, pleasure, music, dance and cats. Bast is the mother of Mahes and wife of Bes (Bas). Bes was a form of Set (evil god of night), and she was a form of Sekhmet (a ferocious lion-headed goddess of sunset and fiery heat who is the daughter of the sun-god Ra). In another rendition, she is the wife of Ra and mother of Hes (a form of Horus). She is also regarded as the mother of the lion-god Miysis (lord of slaughter). Bast was worshipped at Bubastis in early times. During Bast's festival, it was forbidden to hunt lions according to an inscription of Rameses IV. Bast was known as the "Eye of the Moon." She is known by the Greeks as Artemis or possibly Pasht. As a male god, he might have been connected with Bosheth (a name of Baal). He was also thought to be a form of Set. As the male deity, Bes, or Bas, is the god of laughter. Because of this confusion, Bast was also thought to be a goddess of pleasure. She corresponds to the goddess Hathor. She is also identified with Artemis, Baal and Typhon. Sometimes she is confused with Mut and Sekhmet. Bast is represented as a cat-headed woman holding in her right hand either a sistrum or an aegis, and in her left hand, a basket. Sometimes, she is depicted as a cat. A bronze figure in the British Museum shows her holding her aegis in her left hand and a Hathor-headed sistrum in her right hand. *See also* Bes; Bosheth; Hathor; Mut; Sekhmet; Uadjit.

Bastet (Egypt) Festival of. *See also* Bast.

Basti (Egypt) *see* Assessors.

Bata (Egypt)
Also known as: *Bet.*
Agricultural deity. He is a farmer god who looks like a mummified bull or ram. Possibly connected with Anubis.

Batara Guru (Sumatra)
Unhappy because they did not have children, Batara Guru and his wife moved to a hut by the sea and planted a garden. They hoped that by living a simple life they would have a family. Batara Guru's garden was destroyed by a serpent. When he tried to chase the serpent away, the serpent refused to leave until Batara Guru gave him food. He propped the serpent's mouth open and gave him nourishment. When Batara Guru withdrew his hand there was a ring on his finger. The ring enabled he and his wife to have children. The earth was created by one of his sons. It hung on cords from the sky. However, the earth kept light from reaching the god of the underworld. He was so furious that he destroyed the earth. Seven times his son attempted to recreate the earth. On the eighth attempt, with the help of Batara Guru, they were successful. They placed the earth on pillars. The underworld god shows his anger from time to time by causing earthquakes.

Bateia (A) (Greek)
Mother of the Trojan People. She is the daughter of Teucer, king of Phrygia and wife of Dardanus. Her children are Erichtonius and Ilus. *See also* Dardanus; Erichtonius.

Bateia (B) (Greek)
A Naiad. She could be the mother of Hippocoon, Icarius and Tyndareus by Oebaulus, the king of Sparta. The other possibility is Gorgophone (q.v.). *See also* Hippocoon; Icarius.

Bath (Egypt) *see* Ab-ta.

Bati Khan (Toda People, India) Hunting god.

Bato Kannon (Japan) *see* Amida.

Bato-Kwannon (Japan) *see* Amida.

Battle of the Trees (Celtic) *see* Amathon.

Battle Raven (Celtic)
A name for the goddess of war, Badb Catha.

Battle Shaker (Teutonic)
Another name for Vigrid, the plain where the Norse gods will fight on the day of Ragnarok. *See also* Vigrid.

Bau *Ba'u* (Akkadian, Babylonian, Phoenician, Sumerian)
Also known as: *Baau* (possibly), *Bahu, Bohu, Gula, Gur, Ninhursag, Ninki.*
"Goddess of the Dark Waters." A primeval goddess, early

references refer to her as the mother of Ea. She was Anu's spouse, the first wife of Ninib, the wife of Ningirsu. Sometimes she is referred to as the sister of Enlil. In some accounts, she is the wife of Ninurta. She is also said to be the consort of Tammuz. Most references to Bau are in relation to Ninurta. In Babylonia, at the end of harvest, a festival was held to celebrate the sacred marriage of Bau and Ningirsu. The festivities also ensured bountiful crops for the following year. She is possibly a water or creator goddess who preceded Tiamat, and is identified with Gula. She may be the same as the Phoenician goddess Baau. In later times, she was replaced by Ishtar. *See also* Bohu; Gula; Ninhursag; Tiamat.

Baubo *Babo* (Greek)
Also known as: *Ceres* (Roman).

Baubo was Demeter's nurse while she was mourning for her lost daughter Persephone, whom Hades had abducted. Baubo had the reputation for telling indecent jokes. She is depicted without a head or limbs. Her breasts appear as eyes and her genitals are shaped like a bearded mouth. Some scholars believe Baubo to be the same as Hecate (q.v.). She is similar to the Japanese Uzume (q.v.). *See also* Ceres; Demeter; Persephone.

Baucis (Greek)
Baucis is the wife of Philemon of Bithynia. While in their golden years of marriage, they received an unexpected visit from the great god Zeus and the messenger of the gods Hermes. The elderly couple were not aware that their visitors were gods or that they had been turned away from other shelters. They invited the gods into their home and made them comfortable. For their unselfish act they were saved from the Deluge. Their unpretentious cottage was turned into a magnificent palace. After death, Baucis became a linden tree and Philemon an oak tree. They were planted in front of the doors of the temple.

Baugi (Teutonic; Norse)
He is the giant brother of Sattung. When Odin, disguised as Bolverk, was on his journey to Jotun-heim to find the mead of poetry, he worked for Baugi. Sattung guarded the mead made from Kvasir's blood. The mead was distilled in the magic cauldron, Odraerir. The drinker of Kvasir was given the gifts of wisdom and poetry. Odin tricked Sattung into giving him the secret recipe for the production of Kvasir. *See also* Aesir; Bolverk; Jotun-heim; Kvasir; Odin; Odraerir; Sattung.

Baugreginn (Teutonic) *see* Mimir.

Baumbur (Teutonic) *see* Bombor.

Bavor (Teutonic) *see* Bafur.

Bayl (Sumer) *see* Bel.

Baze (Greek) *see* Athene.

bDe-mch-og-dpal-kor-lo-dom-pa (Tibet) *see* Dorje Phagmo.

bDug-spos-ma (Tibet) *see* Dhupa.

bDul-Rgal (Tibet) King of Demons.

Bealtuinn (Celtic) *see* Beltine.

Bean Si (Celtic) *see* Banshee.

Bean-Nighe (Scots) *see* Banshee.

Beann (Egypt) *see* Benu.

Beanu (Egypt) *see* Benu.

Beav (Teutonic) *see* Vali.

Becabs *Bacabab, Becab* (Maya, possibly Toltec)
Also known as: *Acantun, Cantul-ti-ku, Four Wind Gods, Pillars of Heaven, Water Sprinklers.*

Wind gods. Deities of agriculture, rain, and fertility. Patrons of beekeepers. Representatives of the four winds, the four cardinal points, and one-quarter each of the 260-day calendar. The Mayan earth, created by the omnipotent god Hunab Ku, was flat and four-cornered. Above the earth are the thirteen levels of the upperworld, and below, nine levels of the underworld. Fashioned by Hunab Ku to hold up the heavens are the four Becabs. One list of their names, positions, and colors states that Cauac is in the south, his color is red. Ix is in the west, his color is black. Kan is in the east, his color is yellow. And Mulac is in the north, his color is white. Sometimes the lists of point names differ. These four gigantic gods are variously known as Acantun, "Water Sprinklers," "Four Wind Gods" and "Pillars of Heaven." Acantun is also the name used for the pillars or stones erected for the Becabs. As seasonal deities, the first Bacab is blue (some say yellow) for the south. The second is red for the east, the third white for the north, and the fourth black for the west. Each Becab also presided over one-quarter of the 260-day calendar. The Becabs are the divine intercessors for beekeepers. During Zotz, the fourth month, owners of beehives prepared for their feast, which was held in Tzec, the fifth month. The Becabs were consulted to determine the most auspicious day to hold the annual ceremony during their festival period. The brothers are often shown as old men with upraised arms. They are personified by animals and human-headed water jars. The Becabs are closely associated with the four Chacs. In another interpretation,Hunab Ku created the rain god Itzamna and his consort Ixchel, the goddess of childbirth, medicine, and weaving. They became the parents of all other deities, including the Becabs. In each case, when the deluge destroyed the world, the four Becabs escaped. Another Mayan belief to consider is that the sky is held up by four different species of trees, each tree a different color. In the center stands the green ceiba tree (also called the silk-cotton tree). *See also* Acat; Acatl; Backlum Chaam; Tahuantin Suyu Kapac.

Beda (Teutonic) An Asynor. *See also* Aesir.

Beelsamin (Phoenician).
A lord of the sky similar to the Greek Zeus (q.v.).

Beelzebub (Semite) *see* Ba'al-Zebub.

Beelzebul (Semite) *see* Ba'al-Zebub.

Befana (Roman)
Also known as: *Befana, La Strega, La Vecchia, Saint Befana.*

Spirit. An old woman who is as kind as she is ugly. Each January 5 she distributes sweets to good children and lumps of coal to naughty children. Befana is possibly a corruption of Epiphania or Epiphany. *See also* Bertha.

www.ebook3000.com

Begelmir (Norse; Teutonic)
Survivors of the flood. When Ymir flooded the earth with his own blood, the Begelmir, a husband and wife team, were the only survivors.

Begochiddy (Navajo People, North America)
A great god.

Behdety (Egypt)
Also known as: *Apollo* (Greek), *Hor Beditite, Hor Behdetite, Horus.*
Another name for Horus. As Behdety, he was worshiped at Behdet in ancient Edfu. He led the forces of Ra-Horakte against Set. Behdety is falcon-headed and is depicted with the winged disk of the sun. He is often shown in the form of a winged solar disk or a falcon with outstretched wings. His claws hold a fly-whisk and a ring. *See also* Horus; Set.

Bekotshidi (Navaho People, North America) *see* Klehanoai.

Bel (A) (Babylonian, Sumer)
Also known as: *Aleyn-baal, Bayl, Belit, Enlil, Marduk.*
A title meaning "lord." The Babylonians gave the title Bel to Marduk, calling him Bel-Marduk or simply Bel. When the deities of the Sumerians were integrated with their own, the god Enlil became identified with Bel. Belit, the feminine form, was the title given to Ninlil and was also an honorary title given to numerous other goddesses. *See also* Aleyn-Bel; Baal; Bel (B).

Bel (B) (Gaelic)
Also known as: *Balan, Balin, Belenos, Belenus, Belinus, Bellin.*
God of the dead.

Bel (C) (British)
Also known as: *Bel (B).*
Sun god and mythical king of Britain. *See also* Bel (B).

Bel (D) (Celtic)
Also known as: *Bel (B).*
He is an ancient god who was appeased by human sacrifice. *See also* Belinus; Borvo.

Bel (E) (India) *see* Vilva.

Bel Marduk (Babylonia) *see* Marduk.

Bel Matati (Babylonia) *see* Marduk.

Belatucadros (Celtic)
He is a horned god of war, who is equated with Mars.

Belbogh (Slavic) *see* Balbog.

Beldeg (Teutonic) *see* Beldegg.

Beldegg (Teutonic) *see* Balder; Odin; Thor.

Bele (Eastern Sudan, Africa)
Also known as: *Azapane, Mba, Tul.*
A trickster god. Counterpart of the god Tere (q.v.).

Belenos (Celtic) *see* Bel (B); Borvo.

Belenus (Celtic) *see* Bel (B).

Beletersetim (Assyria, Sumer)
This is another name of Belit-Sheri, the scribe of Arallu, the underworld. *See also* Belit-Sheri.

Be'li (British) *see* Bel (B).

Beli (Celtic) *see* Arianrhod; Bel (B).

Belili *Belial* (Akkadia, Assyro-Babylonia, Hebrew).
Also known as: *Baalith, Belit-ili* (title for Ishtar).
Goddess of the Underworld. Sister of Tammuz. Some writers say she was also a goddess of the moon, trees, springs, love and wells. They also say she was the predecessor of Ishtar and mistress of Tammuz. As Belial, this deity is a male and chief of the demons and enemy of God. In New Testament times the name "Belial" is associated with Satan and is a demon of evil. *See also* Belit; Devil; Satan.

Belinus (Celtic) *see* Bel (B).

Belisama (Celtic)
She is the goddess of the Mersey River. Some scholars think that she is a version of the Roman goddess Minerva. *See also* Sequana.

Belit (Assyro-Babylonia, Sumer)
Also known as: *Ba'alat, Beltis, Belit-Ilani* (Mistress of the Gods), *Belit-Ile, Belit-Ili, Belit-Illi, Mylitta, Ninhursag, Nintud.*
Belit is considered to be a title of Astarte, Ninlil, or some say, Nintud. As Belit-Ili she was the "Lady of the Gods." As Nintud (Nintu), she was "Lady of Childbirth." Some say she was consort of Assur or Bel. Others say she was the wife or sister of Enlil. She is shown seated and dressed in a tight robe, her hair made up in the style of the Egyptians. She wears a disk with two horns on her head. She is also depicted with her right hand in an attitude of blessing the baby that she holds as it suckles her left breast. Similar to Hathor and possibly the same as Astarte and Ishtar. She is associated with Tammuz. *See also* Arura; Bel; Ninhursag; Nintud.

Belit-Ilani (Mesopotamia) *see* Nintud.

Belit-Ile (Mesopotamia) *see* Belit.

Belit-Ili (Mesopotamia)
"Lady of the Gods." *See also* Belit; Mah (B); Ninhursag; Ninki.

Belit-Illi (Mesopotamia) *see* Belit.

Belit-Sheri *Belit-Seri, Belit-tseri* (Assyro-Babylonian)
Also known as: *Beletersetim, Nana* (possibly).
Belit-Sheri, the scribe and goddess of writers, is the sister and lover of Tammuz and some say the sister of Ishtar. A scribe of the underworld, she sits in front of the Queen of Death, Ereshkigal, with recordings of the activities of mortals. Upon their deaths she calls out the judgments. *See also* Nana; Tammuz.

Belitis *Beltis* (Mesopotamia)
Also known as: "Lady."
Another name for Ninlil, goddess of fertility. *See also* Beltis; Ninhursag; Ninki; Ninlil.

Bellerophon *Bellerphontes* (Greek)
Also known as: *Deophontes, Hipponoos* (Slayer of horses or monsters), *Hipponous, Leophontes.*
Greek hero. One of the Seven Great Slayers of Monsters. Bellerophon is the grandson of Sisyphus and son of Glaucus

and Eurymede (also known as Eurynome), although according to Homer, Poseidon was his father. His brother was generally known as Deliades. He married Philinoe and became the father of Deidamia, Hippolochus, Isander and Laodamia. Exiled from Ephyra for unintentionally killing Deliades or Bellerus the tyrant of Corinth, he went to Proetus for purification. Prodded by his spurned wife Anteia (also known as Stheneboea), Proetus had Bellerophon deliver a sealed letter to Iobates requesting that he kill Bellerophon. Indirectly, Iobates attempted to fulfill the request. He urged Bellerophon to search for and kill the Chimaera, a fire-breathing monster. Before departing, Bellerophon sought advice from the sage Polyeidus, who suggested that he enlist the aid of Pegasus, the winged horse. He directed him to the temple of Athene where the goddess presented him with a golden saddle and instructed him to go to the well of Peirene. There he found Pegasus, who upon seeing the golden saddle, allowed Bellerophon to mount him. On the back of the moon-horse, in mid-air, Bellerophon slaughtered the Chimaera by shooting arrows through him and in another version by also shoving lead down his throat, which, melted by his fiery breath, seared his intestines. Returning as the victor, the surprised Iobates tried another tactic. He sent him to fight the Solymians, a neighboring tribe, then the Carian pirates and the Amazons. Undaunted, Bellerophon emerged victorious after each battle. Finally, Iobates decided to send the strongest of his soldiers to kill him. Bellerophon petitioned Poseidon to flood the Xanthian Plain to drive the soldiers away. His request was answered and once again Bellerophon was undefeated. Iobates, convinced that Bellerophan was favored by the gods, offered him his daughter Philonoe in marriage and made him successor to his throne. Inflated by his successes and envious of the gods, Bellerophon mounted Pegasus and attempted to fly to the heavens. Annoyed, Zeus sent a gadfly which stung Pegasus and threw Bellerophon, seriously injuring him. Blinded, lame and spurned by the gods, he became an outcast who wandered the fields alone and died miserably with neither his death nor burial place marked. Another myth relates that Bellerophon finally evened the score with Antea by inviting her to ride Pegasus and then from a great height he shoved her to her death. Hyginus wrote that she committed suicide when she learned that Bellerophon married her sister. Other myths say that Bellerophon received Pegasus from either Athene or Poseidon. *See also* Athene; Chimaera; Iobates; Pegasus; Philinoe; Poseidon; Proetus; Sarpedon (A); Sarpedon (B); Sisyphus.

Bellerphontes (Greek) *see* Bellerophon.

Bellerus (Greek) *see* Bellerophon.

Bellin (Celtic) *see* Bel (B).

Bellona (Roman)
Also known as: *Enyo* (Greek), *Mah-Bellona* (in later times).

Bellona, the goddess of war, is the daughter of Phorcys and Geto, and either sister or companion of Mars. Her priests, called Bellonarii, inflicted wounds on themselves when offering sacrifices. Bellona is shown with dishevelled hair, dressed in full armor and holding a bloody lash. She is identified with the Greek Enyo. *See also* Aruru; Mah.

Bellonarii (Roman) Priests of the war goddess Bellona (q.v.).

Belos (Babylonia) *see* Marduk.

Belshim (Semitic) *see* Adad; Baal.

Beltaine (Celtic, Irish) *see* Beltine.

Beltan (Celtic, Irish) *see* Beltine.

Beltane (Celtic, Irish) *see* Beltine.

Belti *Baalti* (Babylonian, Phoenician, Semite, Sumer)
Also known as: *Baalath, Beltis, Belitis, Beltu.*

Mother goddess. Generally used as a name which signifies "lady." Usually indicates a term for Astarte and Ishtar. *See also* Baalath; Ishtar.

Beltine *Baltein, Bealtuinn, Beltaine, Beltan, Beltane* (Celtic, Irish)
Also known as: *Galan-Mai* (Welsh), *Shennda Boaldyn* (Isle of Man).

Festival day. Several historical days in mythology are said to have taken place on the first of May (of the old calendar). It is said that on this day the race of Partholon, led by Partholon and his queen Dealgnaid, one of the earliest settlers of Ireland, came ashore. On the same day three hundred years later they left Ireland. On this day the Tuatha De Danann were said to have first stepped foot on the island. The first Gaelic people are said to have arrived in Ireland on this day. May 1 marked the beginning of summer on the old calendar. Beltaine (Beltine) means "the fire of Bel" and relates to the deity Bel also known as Belinus. It is said that on the evening before May 1, all household fires were extinguished and relit from a main fire thought to be ignited by the Druids. Various rituals accompanied this tradition which were thought to protect the people from evil and illness. Later this became the feast for Saint Brigit. *See also* Bel (B); Brigit; Tuatha De Danan.

Beltis (Sumer, Babylon) *see* Belti.

Beltis-Allat (Arabic, Chaldean) *see* Allat; Allatu.

Beltiya (Assyro-Babylonian) *see* Zerpanitum.

Beltu (Sumer, Babylonian) *see* Belti.

Belu (Semitic) *see* Baal.

Belus (A) (Phoenician) *see* Baal.

Belus (B) (Greek)

King of the Egyptians. Belus is the son of the sea god Poseidon and Libya (eponym of Libya, which, to the ancients, was her homeland Egypt). He is the twin brother of Agenor and brother of Lelex. His spouse is Anchinoe (q.v.). *See also* Agenor (A); Danaus; Lamia; Lelex.

Belus (C) (Babylonian Creation Legend of Berosus, 280 B.C.E.) (Babylonian Creation Legend of Damascius, sixth century C.E.)

In the story of Berosus, Belus (who is the same as Bel) ripped Thalath in half. She ruled the abyss and its horrendous monsters. Belus destroyed the monsters and created heaven with one half of Thalath and earth with her other half. He ordered Kingu to cut off his head. From his blood and earth, mortals, animals, the five planets, the sun, and the moon were formed. In the story of Damascius, Tauthe and Apason (the same as

www.ebook3000.com

Apsu) existed in the beginning. They created the gods Moymis, Lakhe, Lakhus, Assorus, and Kissare. Assorus and Kissare were the parents of Anu, Illinus, and Aus. Aus and Dauce were the parents of the creator of the world, Belus. For the Creation Legend from the Tablets of Ashurbanipal (circa 650 B.C.E.) *see* Tiamat. *See also* Apsu; Aus; Bel (B); Bile.

Belus (D) (Greek)
Phoenix, the king of Phoenicia, is possibly his father.

Belus (E) (Greek)
He is possibly the father of Anna, Dido and Pygmalion. The other possibility is that Agenor is their father.

Bendegeit Vran (Celtic) *see* Bran.

Bendigeid Fran (Celtic) *see* Bran.

Bendigeid Vran (Celtic) *see* Bran.

Bendis (A) (Cappadocian) Earth goddess.

Bendis (B) (Thracian)
Moon goddess. Worship of Bendis spread from Thrace to Lemnos and later to Attica. Her worship involved the celebrated mysteries in Samothrace. She is identified with Artemis, Hecate, Persephone and Rhea. *See also* Artemis (possibly her counterpart); Cybele; Hecate; Persephone; Rhea; Sabazius.

Benen (Egypt)
Guardian of the eighth sector of Tuat. *See also* Tuat.

Benet (Egypt) *see* Aani.

Benjaiten (Japan) *see* Benten.

Bennu Bird (Egypt) *see* Benu.

Bensai-Ten (Japan) *see* Benten.

Bentakumari (Assamese People, India) Water Goddess.

Benten (Buddhist; Japan; Hindu origins)
Also known as: *Benjaiten, Bensai-Ten, Benten* ("Coin-washing Benten"), *Benzai-Ten, Benzai-Tennyo, Benzaiten, Ichiki-Shima-Hime* (an ancient name), *Sarasvati* (India), *Zeniari.*
Goddess of the sea, and of good luck. Originally, she was known as the Hindu love goddess, Benzaiten. As Benten she is a jealous goddess, however, she absorbed the qualities of her former rival, Kichijo-ten and became the only goddess of the Shichi Fukujin (the "Seven Deities of Good Fortune"). She rose from the sea as the daughter of the Dragon King Ryu-wo. As a sea goddess, she was worshiped primarily on the smaller islands. She is also the goddess of good fortune, the goddess of music and public speaking. Later, she became the Goddess of Waters, and in some way is associated with an obscure deity named Uga-jin. Benten's avid followers are business people, gamblers, actors, dancers, musicians and geishas. Some say she has two sisters. She is depicted as a beautiful woman dressed in ornate clothing. She variously holds a lute, sword or jewel in two hands. In other depictions, she is shown with eight arms holding various objects. Sometimes she is shown with her messenger, a white snake. She is also depicted riding on a dragon. As a Shichi Fukujin, she holds a lute. As with other images of the Shichi Fukujin, her image has been carved on rice grains. Women often carried her talisman as they believed that she made them more fruitful and accentuated their beauty and talents. As Zeniarai Benten, she increased the prosperity of all who threw coins into her well. She is similar to the Greek goddess of love, Aphrodite, and almost identical to the Indian goddess of the arts, Sarasvati. As Benzaiten, she is associated with Bishamon, the god of happiness and war. *See also* Bishamon; Kichijo-Ten; Sarasvati; Shichi Fukujin.

Bentet (Egypt) *see* Aani.

Bentet Apes (Egypt) *see* Aani.

Benth (Egypt) *see* Aani.

Benthesicyme (Greek)
Daughter of Poseidon and Amphitrite, she raised her half-brother, Eumolpus, who had been thrown into the sea by his mother Chione. *See also* Amphitrite; Chione; Eumolpus.

Benu (Egypt)
Also known as: *Atum* (possibly), *Beann, Beanu, Bennu, Byanu*; (possibly as the Phoenix; he flew from Arabia to Egypt).
Mythical bird. He is shown as a huge golden hawk with a heron's head. He makes his appearance once every 500 years. He came from Arabia with the body of his father enclosed in an egg of myrrh. Other sources indicate that the Benu Bird, in this case a heron, is an aspect of Atum. It was said to have flown through the first dawn, coming to rest on a rock in the primordial waters (the Nun), where it opened its beak and let out a cry breaking the silence of the Nun. His plumage was colored part gold and part red, and he was about the size of an eagle. Benu is sometimes called the soul of Osiris. The name Beanu or Beann is also that of the Celtic mother goddess. The Benu, like the phoenix, re-creates itself from fire. *See also* Atum.

Benu Bird (Egypt) *see* Atum.

Benzai-Ten (Japan) *see* Benten.

Benzai-Tennyo (Japan) *see* Benten.

Benzaiten (Japan) *see* Benten.

Berchta (Teutonic) *see* Bertha.

Berecyntia (A) (Greek)
A surname of Cybele derived from Mount Berecynthus in Phrygia, where Cybele was worshiped. *See also* Cybele.

Berecyntia (B) (Celtic, Gaul)
This earth goddess may be the same as Brigit.

Bergelmir *Bergelmer* (Norse; Teutonic)
This frost giant came from the feet of Thrudgelmir, who in turn was produced by Ymir. Bergelmir is the father of all the evil frost giants, who are known as Hrim-Thurs. He and his wife were the only ones to survive the war with Odin and his brothers. Bergelmir escaped and made his home in a place in Jotunheim. Here he began a new race of frost-giants who continued the war with Odin and his group. In another rendition, Bergelmir and his spouse were the only survivors of a deluge caused by the blood of Ymir. *See also* Bor; Buri; Jotun-heim; Ymir.

Berkta (Teutonic) *see* Bertha.

Berling (Norse; Teutonic)
Dwarf smith. One of four dwarfs who slept with Freyja in

return for the gift of the Brising Necklace. The others were Alfrigg, Dvalin, and Grerr. *See also* Alfrigg; Freyja.

Beroe (Greek) *see* Adonis; Semele.

Berserker (Teutonic) *see* Berserkir.

Berserkir *Berserker, Berserks* (Norse; Teutonic)
Also known as: *Bear Shirts, Berserksgangr.*
Deified mortals. They are the human warriors who went into a frenzy, possibly induced by drugs or by large quantities of alcohol, before battle. As warriors, they were immune to weapons. After battle, when their fury subsided, they became unusually weak. In their weakened state, they were captured. The Berserkir (Old Norse for "bear" and "shirt") fought wearing animal skins and are under the special protection of Odin. Originally, there were twelve Berserkir born on the island of Bolmso, the sons of Arngrim and Eyfura. Thor killed the serpent-wives of the Berserkir. They are the relatives of Ottar. The Berserkir are often described as "fantastically ugly," and are often mistaken for trolls. *See also* Odin.

Berserks (Teutonic) *see* Berserkir.

Berserksgangr (Teutonic) *see* Berserkir.

Bertha *Berchta, Berkta, Brechta* (Teutonic)
Also known as: *Frigga, Frau Berchta, Gode, Holda, Huldra, Nerthus, Percht, Perchta, Precht, Vrou-elde, Wode.*
"White Lady." Bertha could be a spirit of spring. Bertha is not attractive, but she is kind and sweet. Her duties are to watch over the souls of unborn children (who are known as "the Heimchen"). She also watches over children who die before baptism. Bertha is reputed to be the female form of Odin. In this form she is known as "Frau Gode," or "Frau Wode." In Holland she is known as Vrou-elde and in Germany she is known as Nerthus. In Scandinavia, they call her Huldra. She is identified with Freyja and the Slavic Baba Yaga. She is associated with Holda, Wera and other goddesses of the New Year. Bertha is similar to the Roman Befana (q.v.). *See also* Baba Yaga; Befana; Holda; Nerthus.

Bes (Egypt, Phoenicia, Sudan, and Nubia; possibly of Semitic origin)
Also known as: *Aha* (fighter), *Bas, Besam Bisu.*
Bes is the god of marriage, god of music, fighting, dancing, protector of women in childbirth and protector against terrors, evil spirits, dangerous beasts and insects. He may have been a god of birth. He was also a god of fashion, particularly of the adornment of women. Later he was known as a god of the dead or fate. He carried the sa (symbol of protection), a knife for defense, and musical instruments to ward off evil spirits. His image was found on mirrors and cosmetic pots to aid in averting the "Evil Eye." He is akin to Bacchus the Roman god of gaiety *in nature. He* does not resemble the other members of the Egyptian Pantheon in appearance. Bes might have a mate named Ta-weret. In some legends, he is the husband of Bast. He is depicted as an ugly, hairy dwarf god. He has a huge beard, protruding tongue, flat nose, shaggy eyebrows and hair, large projecting ears, long thick arms, and bowed legs. He wears an animal skin whose tail hangs down to the ground, and a tiara of ostrich feathers. There are those who say he had feathers instead of hair. In the Eighteenth Dynasty, pictures of Bes with wings were popular. Bes is associated with Hathor and her son Ihy. Bes is the counterpart of the goddess Theoris. Compare Bes to Bacchus, Gilgamesh, Silenus. Some say he is Horus' nurse. *See also* Bast; Bastet; Hathor; Theoris.

Beset (Egypt)
She is a patron of art, music and childbirth, and the female counterpart of Bes (q.v.)

Besi (Egypt)
Otherworld deity. God in the tenth sector of Tuat (q.v.)

Besi-Shemti (Egypt) *see* Aai.

Besla (Teutonic) *see* Bestla.

Bestla *Besla, Bettla* (Teutonic)
Bestla is the giant daughter of Bolthorn, who became the mate of Bor and the mother of Odin, Ve and Vili. She is the daughter-in-law of Buri. In another myth, she is known as the daughter of Ymir and twin of Mimir. *See also* Bolthorn; Bor; Buri; Mimir; Odin; Ve; Vili; Ymir.

Besu (Slavic)
Devil or disagreeable god.

Bet (Egypt) *see* Bata.

Betsune Yeneca (Chippewa People, North America)
Star deity. Name of the Old Woman's Grandchild, a magic boy from the stars.

Bettla (Teutonic) *see* Bestla.

Bevarash (Zoroastrian; Persia)
The end of the dynasty of the fiendish snake, Azhi Dahaka (q.v.).

Beyla (Teutonic)
Earth goddess. Wife of Byggvir. Handmaiden of Freyr.

Bhadra Vira (India) *see* Badari.

Bhadracharu (India) *see* Rukmini.

Bhadrakali (India) *see* Badari; Durga; Karttikeya.

Bhadri-Nath (India) *see* Badari.

Bhaga (Hindu; India)
God of strength, beauty, good fortune and marriage. An Aditya, Bhaga, the "divine," is the brother of the god Varuna and Ushas the goddess of dawn. There was a time, when Daksha held an important event, to celebrate a sacrifice. He invited everyone from near and far — except Shiva. Enraged, Shiva created the monster, Virabhadra, who blinded Bhaga. *See also* Aditya; Daksha; Durga; Mitra; Parvati; Shiva; Ushas; Varuna.

Bhagavad-Gita *Bhagavadgita* (Hindu; India)
"Song of the Divine One."
This is the sixth book of the *Mahabharata*, in the form of a dialogue between Krishna, an avatar of Vishnu, and Arjuna, expounding philosophical theories on duty and death. The conversation took place when Arjuna was unwilling to do battle and questioned the remarks of Krishna, his charioteer, on the subject. The Bhagavad-Gita consists of 606 verses and is thought to have been written in the first century C.E.

www.ebook3000.com

Bhagavata Purana, The (Hindu; India)
Dedicated to Bhagavata (god, said to be Vishnu), this Sanskrit work by Vopdeva (c. 1300), is composed of 12 books, divided into 322 chapters. The name means "The Old Book of Divinity."

Bhagiratha (India)
Great grandson of King Sagara (q.v.).

Bhairab (Nepal)
One of Shiva's numerous destroyer forms, Bhairab is either dark blue or black and is depicted nude. In pictures he is occasionally shown as white. He has many arms and usually one head shown with rolling eyes and unruly hair. In his hands are a skull-cup, a wand with three skulls, or a noose. He may wear sandals and is often shown standing on a recumbent figure. *See also* Shiva.

Bhairava (Hindu; India, Indonesia, Tibet)
Also known as: *Jigs-Byed* (Tibet), *Shiva.*
Bhairava, the "destroyer," is one of eight (or twelve) terrifying aspects of Shiva. As Bhairava he destroys for the pleasure of destruction. He is depicted frowning. His eyes are angry, his hair flaming and his tiger teeth appear razor sharp. Naked, a snake is coiled around his neck and he wears a necklace of skulls. He carries his noose, trident and drum. He is often accompanied by demons, imps and a dog, sometimes said to be a jackal. In some locales, Bhairava and the village god Bhairon have merged. Bhairava is worshiped in northern and central agricultural districts of India as a black dog, a snake-girded drummer, or a red stone. Depictions of Bhairava are often very similar to depictions of the Buddhist god of death, Mahakala. *See also* Bhairon; Shiva.

Bhairavi (India)
"Terrifying Female." *See also* Durga; Kali; Parvati.

Bhairoba (India) *see* Bhairon.

Bhairon *Bhairava, Bhairoba* (Bombay), *Kala Bhairava* (Bombay); (Hindu; India)
A local village god, Bhairon is the personification of the field spirit. In some places, he has merged with Shiva's terrifying aspect as Bhairava. In Benares he serves as a guardian at Shiva's temples. As Kala Bhairava, or Bhairoba, he is depicted with a sword or club, carrying a bowl of blood. *See also* Bhairava; Gramadeveta.

Bhaisajyaguru (India) *see* Bhaishajyaguru.

Bhaishajyaguru *Bhaisajyaguru*
Also known as: *Man-la, Sang-gyeman-gyila-beduryr-o-chi-gyal-po* (Tibet); (Buddhist; India)
God of healing. God of sex change. A Bodhisattva and the fifth Buddha, he is a the master physician and god of healing and of spells. He rules the east (as does Akshobhya) and is depicted as blue in color. He holds fruit in his right hand. *See also* Akshobhya; Amida; Yao-Shih Fu.

Bhama (India) Krishna's wrathful wife. *See also* Krishna.

Bhangi (Cambodian) *see* Rahu (B).

B'haq Ziva (Gnostic) *see* Abathur.

Bharadvaja *Bharadwaja, Bharawaya* (Hindu; India)
The son of the Rishi Brihaspati, Bharadvaja, a great poet and sage, was the spiritual leader of the Pandavas. He is the father of Drona (q.v.). *See also* Brihaspati; Pandavas; Rishi.

Bharadwaja (India) *see* Bharadvaja.

Bharata (A) *Bharatha, Bharati* (Hindu; India)
Bharata is one of four sons of King Dasaratha and Queen Kaikeyi. He was the spouse of Madavi (also called Mandavi) and the cousin of Sita. He reigned in place of his half-brother Rama during the latter's exile which was caused by Kaikeyi. His other siblings are Lakshmana and Satrughna. (He is not to be confused with Bharata, the Vedic king of the Bharatas, nor Bharata the hermit who was associated with Vishnu.) *See also* Dasaratha; Lakshmana; Rama; Sita.

Bharata (B) (Hindu; India)
An ancestor of the Kauravas and Pandavas and the son of King Dushyanta and the nymph Shakuntala (q.v.).

Bharatha (India) *see* Bharata (A).

Bharati (India)
Goddess of Speech. A name for Sarasvati (q.v.). *See also* Vach.

Bharawaya (India) *see* Bharadvaja.

Bhargavi (India) Wife of Shiva. *See also* Devi.

Bharundas (Hindu; India)
Birds who carry away the dead.

Bhava (India) "Existences." A title of Agni (q.v.).

Bhava-Siva (India) *see* Daksha.

Bhavani *Bhawani, Bhowanee, Bhowani, Devi, Devi-Uma, Kali, Mari, Parasu-Pani, Parvati* (Hindu; India; possibly Dravidian)
"Bestower of Existence." Bhavani is a name alternately used for Devi, Kali, or Parvati. In one depiction, she is shown as young, wearing a crown, and containing within her body a landscape incorporating the sun, moon and the sea. Perfume was burned in her honor by women in childbirth. The Korwa (also called Korama) people of India worship Bhavani as Mari, the goddess of death. *See also* Dakinis; Devi; Kali; Mari.

Bhawani (India) *see* Bhavani.

Bhiarav (Nepal) *see* Varahi.

Bhima (A)
Also known as: *Bhima-sena* ("The Terrible"), *Bhimul Pen, Bhimsen, Bish-nat* (as an earlier incarnation), *Vrikodara* ("Wolf's Belly"); (Hindu; India)
As the son of Vayu "the wind" and Kunti "the earth," Bhima has the ability to fly. The second of the five Pandavas, his older brother is Yudhisthira. Hanuman, the flying monkey, is his half-brother. A giant in size, he is the spouse of the Rakshasis Hidimbaa and the father of Ghatotkacha. She is the sister of the demon Hidimba whom Bhima killed. With princess Balandhara of Kasi, he has another son, Sarvaga. Trained by Drona and Bala-Rama to use the magic club, he became a ferocious warrior. His cousin Duryodhana once poisoned him and threw him into the Ganges River. His body sunk to the bottom but he was revived

by resident serpents. The fiery-tempered god insulted the solar Karna and became his enemy for life. He killed the demon Vaka and so many other Asuras that they promised not to accost humans if he would leave them alone. When Jayadratha, and at another time, Kitchaka attempted to rape his spouse Draupadi, he trounced them thoroughly. Disguised as a demon and, aided by his magic club, he rescued Draupadi from death by fire. During the great Battle of the Mahabharata, he fought Bhishma, killed the two sons of the king of Magadha, fought his old master Drona, killed Duhsasana and smashed Duryodhana's thigh. When the devious king Dhritarashtra summoned him to his court, Krishna intervened and substituted an iron statue, which the enraged king crushed in an embrace. In another adventure, he set out for Lake Kubera and the life-giving lotus in the northeastern area of the celestial realm. He found the lake and killed the Yakshas who guarded the lotuses. The water from the lake gave him youth and strength. *See also* Bala-Rama; Bhishma; Draupadi; Duryodhana; Jara-Sandha; Karna; Krishna; Kunti; Pandavas; Rakshasa; Takshaka; Yaksha and Yakshini; Yudhisthira.

Bhima (B) (India) *see* Apsarases.

Bhima (C) (India) A name for Shiva or Rudra (q.v.).

Bhima-Devi (India) "Terrifying Goddess." *See also* Kali.

Bhima-sena (India) *see* Bhima (A).

Bhimsen (India) *see* Bhima (A).

Bhimul Pen (India) *see* Bhima (A).

Bhishma
Also known as: *Gangeya* ("Son of Ganga"), *Jalu-Ketu* (banner name), *Nadija* (River-born); (Hindu; India)

Bhishma, a deified mortal, is the son of the river goddess Ganga and the sage Santanu. He was known for his devotion and honor. When his aged father wanted a young wife, he accommodated him and gave him the woman he himself loved, Satyavati. To ensure that his father's new sons would become kings, he gave up his throne. Later, he found mates for his youngest half-brother. They were the daughters of the Raja of Kasi. When their husband died, Bhishma gave the women to his other half-brother Vyasa. Their children were Dhritarashtra, who was blind, and the pale Pandu. Bhishma tried to prevent the war between the Kauravas and Pandavas but ended up leading the Kauravas. He was killed, but not instantly, by a thousand darts shot by Arjuna at the Battle of Kurukshetra. His divine power permitted him to decide the day of his death, so he lay for fifty-eight days with the darts sticking out from his body. During this period he gave many discourses on morality. Bhishma was welcomed into Mount Meru where he became one of Indra's advisors. *See also* Arjuna; Bhima; Ganga; Indra; Meru Mountain; Pandavas; Satyavati; Vyasa.

Bhishmaka, King (India)
Father of Rukmini. *See also* Sisupala.

Bhisma (India) *see* Bhima (A).

Bhogavati (India) *see* Nagas and Nagis.

Bhogini (India) *see* Nagas and Nagis.

Bhowanee (India) *see* Bhavani; Devi.

Bhowani (India) *see* Bhavani; Devi.

Bhradrakali (Hindu; India)
Goddess of death.

Bhramara (India) "Relating to the Bee." *See also* Devi.

Bhrigu (India) *see* Bhrigus.

Bhrigus *Bhrgu* (singular) or *Bhrigu* (Hindu; India)
A Bhrigu, who was the first wise man, was married to Puloma, who in turn was betrothed to a demon. It was Bhrigus the sage who cursed Agni then repented and revoked his curse. Along with Matarisvan they represent the wind. In another version, the first wise man was Bhrigu and his descendants were the Bhrigus, meaning "the Shining Ones." A son of Bhrigus was the wealthy sage Chyavana who was rejuvenated by the healing twin deities, the Asvins. (Chyavana is also spelled Cyavana and Syavana.) Agni betrayed Bhrigus' wife into the hands of a Raksha. Bhrigus condemned Agni to forever consume everything. Agni retaliated by hiding himself from the gods and mortals. Realizing that Agni was indispensable, Bhrigus revoked his curse and Brahma urged him to return. They had to decide which of the three gods, Brahma, Shiva or Vishnu, was most deserving of the Brahmans' worship. Bhrigus was sent by the Bhrigu to find out who was the most deserving deity of the Hindu triad. He went to visit Shiva who was preoccupied with his wife and would not grant him an interview. Bhrigus, infuriated, cursed Shiva and decreed that henceforth the god would be worshipped as a lingam. Bhrigus went on to see Brahma, who was not remotely interested in granting the sage an audience. He then went on to Vishnu, and when he found him sound asleep, he kicked him in the ribs. Although rudely awakened, Vishnu's first concern was for Bhrigus. He asked him if his foot was injured from the kick. This concern won Bhrigus over, and he declared Vishnu to be the most deserving of adoration. Bhrigus is the father of the deity Shukra (meaning "Bright"), who became a guru to the Asuras. Blind in one eye, with the ability to bring the dead to life with his incantations, he personifies the planet Venus. As well as being a sage of the *Mahabharata*, he is thought of as a minor deity. Bhrigus foretold the life of all people born. His prophecies, written down, are known as the "Bhrigu Collection" ("Bhrigu Samhita"). *See also* Agni; Asuras; Asvins; Brihaspati; Lakshmi; Loka; Mada; Prajapati; Rishi; Shiva; Vishnu.

Bhu (Brahmanic, Hindu; India)
She is Mother Earth, who reclined at the bottom of the ocean before Creation. Brahma raised her to the surface where she appeared as a lotus flower which opened when the light enveloped her. *See also* Bhumi.

Bhu-Devi *Bhudevi* (India)
An earth goddess similar to Pritha. *See also* Bhumi; Darti Mai; Pritha; Prithivi; Sita.

Bhudevi (India) *see* Bhu-Devi.

Bhugangi (Hindu; India) *see* Kundalini.

Bhujagas (India) *see* Naga and Naginis.

www.ebook3000.com

Words of Caution

The practices described in this book have been used successfully for thousands of years by Taoists trained by personal instruction. Readers should not undertake the practice without receiving personal transmission and training from a certified instructor of the Universal Tao, since certain of these practices, if done improperly, may cause injury or result in health problems. This book is intended to supplement individual training by the Universal Tao and to serve as a reference guide for these practices. Anyone who undertakes these practices on the basis of this book alone, does so entirely at his or her own risk.

The meditations, practices and techniques described herein are ***not*** intended to be used as an alternative or substitute for professional medical treatment and care. If any readers are suffering from illnesses based on mental or emotional disorders, an appropriate professional health care practitioner or therapist should be consulted. Such problems should be corrected before you start training.

Neither the Universal Tao nor its staff and instructors can be responsible for the consequences of any practice or misuse of the information contained in this book. If the reader undertakes any exercise without strictly following the instructions, notes and warnings, the responsibility must lie solely with the reader.

This book does not attempt to give any medical diagnosis, treatment, prescription, or remedial recommendation in relation to any human disease, ailment, suffering or physical condition whatsoever.

Chinese Medicine and Chi Kung emphasizes balancing and strengthening the body so that it can heal itself. The meditations, internal exercises and martial arts of the Universal Tao are basic approaches to this end. Follow the instructions for each exercise carefully and do not neglect the foundations, i.e, the Microcosmic Orbit and any other supplemental exercises. Also pay special attention to the warnings and suggestions. People who have high blood pressure, heart disease or a generally weak condition should proceed cautiously, having prior consent from a qualified medical practitioner. People with venereal disease should not attempt any practices involving sexual energy until they are free of the condition.

The Universal Tao is not and cannot be responsible for the consequences of any practice or misuse of the information in this book. If the reader undertakes any exercise without strictly following the instructions, notes, and warnings, the responsibility must lie solely with the reader.

Bhujangi (India) *see* Kundalini.

Bhujyu (India) The Sun. *See also* Asvins.

Bhumi *Bhumidevi* (Hindu, Vedic; India)
Bhumi is referred to as the fourth earth and the mother of the planet Mars. She is one of seven sisters who are not named, but may be associated with seven stars or planets. She is thought by some to be the spouse of Vishnu. Bhumi is the mother of Sita, known as Bhumija, who sprang from a furrow in the earth and in the end returned to Bhumi, the earth. The Indian goddesses Medini and Mahi are also known as the mother of Mars. Bhumi corresponds closely to Prithivi. Sometimes they are said to be two forms of the same goddess. *See also* Bhu; Bhu-devi; Bhumiya; Brihaspati; Sita; Varaha (Vishnu's avatar as a boar); Vishnu.

Bhumija (India) *see* Bhumi; Sita.

Bhumiya (Northern India)
Also known as: *Khetrpal, Rani* (feminine).
Bhumiya is an ancient earth god or goddess who is worshipped at the time of marriage, birth and harvest. He sometimes changes sex and is identified with the earth mother. People who are disrespectful to Bhumiya become ill. The Dangis People worship Bhumiya as a snake. *See also* Bhumi.

Bhumiya Rani (India) *see* Bhumiya.

Bhur-Loka (India) *see* Loka.

Bhura (India) *see* Bura-Penu.

Bhuri (India) *see* Bura-Penu.

Bhut (India) *see* Bhutas.

Bhuta (India) *see* Bhutas; Daksha.

Bhutanayaki (India) Spirit Leader. *See also* Devi.

Bhutapati (India) Prince of demons. *See also* Rudra; Shiva.

Bhutas *Bhut, Bhutias, Buta* (Hindu; India)
The Bhutas, children of Krodha, the daughter of Daksha, and her mate Bhuta, are malignant spirits, vampires, ghosts, or goblins who despise humans and frequent cemeteries. Mortals who have died a violent death become Bhutas. The Bhutas never rest on earth, so they can be avoided by lying down. Burning turmeric will also keep them away. Bhutas speak with a nasal twang, hate fire and do not have shadows. *See also* Daksha; Demons; Incubus; Jinn (Persian); Krodha; Nagas; Pishachas; Rakshasas; Satyrs (Greek).

Bhutesvara (India) Lord of Spirits and Demons. *See also* Shiva.

Bhutias (India) *see* Bhutas.

Bhuvana-Matri (India) "Mother of the World." *See also* Devi.

Bhuvanisvari (India) "Mistress of the World." *See also* Devi.

Bhuvar-Loka (India) *see* Loka.

Bia (A) (Greek, Egypt)
Also known as: *Ba, Ka.*
God of force and violence. He and his brother, Cratus (also spelled Kratos) helped Hephaestus nail Prometheus to a cliff. They were also great helpers of Zeus. Another version tells that Bia (violence) was a daughter of the nymph Styx, who was the personification of the river Styx and the Titan Pallas. Bia was the sister of Zelos, Nike, and Caratus. She also helped the Olympians in the revolt of the Titans. *See also* Nike; Prometheus; Styx.

Bia (B) (Ashanti People, Africa)
He is the son of Nyame and Asase Ya and the older brother of Tano. Bia was deprived of his inheritance by his younger brother and was left poor land on the Ivory Coast. *See also* Asese Ya; Nyame.

Biadice (Greek) *see* Cretheus.

Biamban (Australia) *see* Baiame.

Biambun *Biamban* (Aborigine People, Australia)
Supreme deity. A god whose name is not to be spoken. He may be same as Biamban. *See also* Daramulun.

Bibhishan (India) *see* Vibishana.

Biblindi (Teutonic) *see* Odin.

Bielbog (Slavic) *see* Byelobog.

Bifrost *Bivrost, Bilrost* (Norse; Teutonic)
Also known as: *Asa, Asa Bridge, Asabru, Asbru.*
The Rainbow Bridge, Bifrost, links Asgard to the world of the mortals. The bridge stretches high above Midgard between the edges of Niflheim, or, some say, between Asgard and Midgard. It is built of fire, water, and air. It crosses the rivers of the dead (Kerlaug). The bridge is watched by the god Heimdall who is armed with a sword and carries a trumpet called Giallarhorn. The trumpet is used to announce the coming or going of the various gods. Only Thor is denied the privilege of using the bridge. During Ragnarok, Bifrost will be broken down by Sutur as he leads the sons of Muspell. *See also* Asgard; Niflheim; Thor.

Bifur (Norse; Teutonic)
Dwarf. One of the dwarfs who made Glepnir, the chain that binds the wolf Fenrir. The other named dwarfs are Bafur, Bombor, Dain, Nain, Nar, Niping and Nori. Skirnir, Freyr's messenger, was sent to the dwarfs to have them make the chain. *See also* Dain; Dwarfs; Fenrir; Yggdrasil.

Bihishan (India) *see* Shurpanaka.

Bijadari (India) Benevolent demigods. *See also* Vidyadhara.

Bil (A) (Teutonic)
This minor goddess, an Asynjor, is the waning moon, who with Hiuki (also known as Hjuki), follows Mani the moon god on his course. She is described as a little girl. *See also* Aesir; Asynjor; Mani.

Bil (B) (Celtic) *see* Bel (B).

Bila (Aborigine People, Australia)
Sun goddess or sun-woman. She is a bloodthirsty cannibal who was wounded by the lizard-man Kudnu with a boomerang because she ate his people. She disappeared and the world was in darkness. Kudnu threw his boomerangs to the north, west,

and south. It was only when he threw his last one to the east that she changed into a ball of fire and returned to the world.

Bildjiwararoju *Bildjiwruaroiju* (Australia) *see* Djanggawuls.

Bile (Celtic)

A culture hero, he is the spouse of Don and the father of Arianrhod, and Caswallwan. *See also* Arianrhod; Bel (B).

Bileyg (Teutonic)

"One with Evasive Eyes," an alternate name for Odin.

Bilflindi (Teutonic) *see* Odin.

Bilrost (Teutonic) *see* Bifrost.

Bilskirnir (Norse; Teutonic)

It is the dwelling place of the god Thor in Asgard. *See also* Asgard; Thor.

Bilva (India) Sacred Fruit. *See also* Shiva.

Bima (Aborigine People, Australia) *see* Purukupali.

Bimbo-Gami (Japan) *see* Bimbogami.

Bimbogami *Bimbo-Gami* (Japan)

A god of poverty who is exorcised by throwing away the bamboo tube that lights the household fire.

Binded (Egypt) *see* Banebdedet.

Bingo (Bantu People, Africa)

God of knowledge. Son of Nzame and a mortal woman known as Mboya. After a quarrel with his wife over the affections of Bingo, Nzame threw his son from heaven. Otoyum, a great sorcerer, saved and hid Bingo. When Bingo grew up, he became the teacher of mortals. *See also* Nzame.

Binzuru *Binzuku* (Buddhist; Japan)

Originally he was a mortal disciple of Buddha. He became a god because of his miraculous abilities to heal the sick. In some myths, Binzuru broke his vow of chastity and so is denied entrance to Nirvana.

Bir (Assyrian) *see* Adad.

Biral (Australia) *see* Baiame, and Bunjil.

Birque (Semite) *see* Adad.

Birral (Australia) *see* Baiame.

Birren (Celtic) *see* Bith and Birren.

Birushana (Japan) *see* Dainichi-nyorai.

Bis-Bis (Assyro-Babylonian) *see* Tiamat.

Bish-nat (India) *see* Bhima (A).

Bishamon (Buddhist, China; Buddhist, Japan; originally of Hindu origins)

Also known as: *Bishamon-Ten, Bishamon-tenno, Bishamonten, Tamon, Tamon-tenno, Tamontennu.*

God of war, happiness, wealth and good luck. Guardian. Bishamon ("Wide Hearing"), a Shi-Tenno, is the guardian of the north. He is also one of the Shichi Fukujin (seven deities of good luck), and in this capacity is the god of war and wealth. As a warrior he is the protector of human life and chaser of demons. He is the brother of Kishijoten, a goddess of luck and beauty who corresponds to Lakshmi the Indian goddess of fortune and Sri the Indian goddess of prosperity. As a guardian, Bishamon is depicted as a soldier with a ferocious expression, usually shown with a small container in the shape of a pagoda in one hand and a spear in the other hand. As a Shichi Fukujin, he is also depicted as a soldier, holding similar items, sometimes with a halo in the shape of a wheel. *See* Lakshmi and Sri for similarities to Kishijoten. *See also* Benton; Daikoku; Jikoku-Ten; Kichijo-Ten; Komoku-Ten; Shi Tenno; Shichi Jukujin; Tamontennu; Zocho-Ten.

Bishamon-Ten (Japan) *see* Bishamon.

Bishamon-Tenno (Japan) *see* Bishamon.

Bishamonten (Japan) *see* Bishamon.

Bishen (India) *see* Devi; Gauri; Parvati.

Bishenjun (India) *see* Kalki.

Bisi-Bisi (Assyro-Babylonian) *see* Ishtar.

Bisimbi (Congo, Africa) *see* Nymphs.

Biswarupa (Nepal)

Biswarupa, a representation of many gods in one, has many heads and arms. The rear circle of arms has the hands in various hand poses. Other circles of arms hold implements and weapons. The heads, terrible and gentle, are those of the deities.

Bith and Birren (Irish)

This couple, similar to Adam and Eve, survived a deluge. They were the parents of Cessair (q.v.).

Bitje (Egypt)

A monster serpent with a head at each end, it is found in the ninth sector of Tuat.

Bitol (Maya)

Also known as: *Ixmucane.*

Creator deity. One of the council of Seven Gods of Creation. After the second attempt at creating mortals, four of the gods (regents) changed their names and sculpted men out of wood. Bitol became Ixmucane (q.v.). *See also* Alom.

Bivar-Asp (Persia) *see* Azi; Zahhak.

Bivrost (Teutonic) *see* Bifrost.

Bjelbog (Slavic) *see* Balbog.

Bjorno-hoder (Teutonic) *see* Hodur.

Black Annis (British)

Also known as: *Black Agnes.*

Black Annis lived in a cave alone. She hid in the branches of the last oak tree from her forest. This blue-faced hag feasted on people that she had snatched from their firesides. Others believed that she would grab children who played in her territory and scratch them to death. Early each spring, a dead cat would be dragged before a pack of hounds in front of her cave in Dante Hills to celebrate the death of winter. *See also* Cailleach Bheur.

www.ebook3000.com

Black Hactcin (Jicarilla Apache People, South America) *see* Hactcin.

Black Mother, The (India) *see* Kali.

Black Surt (Teutonic) *see* Surtr.

Blathine (Celtic) *see* Blathnat.

Blathnat *Blathine* (Celtic)
The daughter of King Mider, she married Curoi, who was the guardian of the king's magic cauldron. Blathnat conspired with Cuchulain to steal the cauldron from Curoi. *See also* Cuchulain; Curoi; Mider.

Bleifstr (Teutonic) *see* Loki.

Blodeuwedd (Celtic, Welsh)
Also known as: *Flower Face.*
She was created by Math and Gwydion from a tree and flower-blossoms. The spouse of Llew, she loved Gronw Pebyr. To him she divulged the secret of how Llew could be killed. Gwydion punished her by death, or by turning her into an owl. This myth is similar to the myth of Blathnat (q.v.). *See also* Gwydion; Llew Llaw Gyffes.

Blue Jay (Chinook People, Pacific Coast People, North America)
A creator god, Blue Jay decides how each animal and bird will live, make its home, and eat. He is also a protector of humans. In the Chinook belief Blue Jay was orginally a mischief-maker, the gods turned him into a zoomorphic being. His sister is Ioi. *See also* Agas Xenas Xena.

Bn-Ym (Ugarit) *see* Khoser-et-Hasis.

Bo (Ewe People, Dahomey; Africa)
Bo protects people in war. During ceremonial occassions, his priests carry bundles of painted red and white sticks that are four to six feet in length. They also carry brass axes. Bo is associated with the god of lightning, Khebieso (also known as So).

Boand (Celtic, Irish) *see* Boann.

Boann (Celtic, Irish)
Also known as: *Boand, Boannan, Buan.*
Mother deity. River nymph. Boann is the goddess or priestess of the Boyne River in eastern Ireland who, by her union with Dagda, became the mother of Angus, Bodb, Brigit, Mider, and Ogma. Some say she is the river nymph wife of Ecmar (also spelled Elcmar, Elcmhaire. Accused of adultery with Dagda, she drowned in Connla's well trying to prove her innocence. It is said the result of her infidelity was the birth of Angus. To conceal this from Ecmar she and Dagda held the sun still for the nine months of her pregnancy but made it seem like only one day had passed. Angus was raised by the underworld deity, Mider. For other river deities, *see* Brigantia, Sequana. Compare Boann to Tammuz. *See also* Angus; Dagda.

Boannan (Celtic, Irish) *see* Boann.

Boar with the Nine Tusks (Maya) *see* Cit-Bolon-Tum.

Bochica *Bochicha, Bokika* (Chibecha; Muyscaya People, Colombia, South America)
Also known as: *Chiminizagagua, Nempterequeteva, Nemquetheba, Xue, Zuhe.*
Sun God. Supreme creator and lawgiver. Bochica brought agriculture, social laws, crafts and other skills to the people. Before he left the mortal plane, he imprinted the shape of his foot on a rock. His wife was Chia (or possibly Huythaka or Cuchaviva) who brought a great flood which angered Bochica. He exiled his wife to the sky where she became the moon. He defeated the demon Chibchacum and forced him to carry the earth on his shoulders. Earthquakes are the result of Chibchacum getting restless. Bochica was possibly brought to Mexico by the Buddhist missionaries. In legend, an old bearded man clothed in robes came from the east to teach the people skills and crafts. Thinking he was one of the Apostles, they gave him the epithet "Chiminizagagua," meaning "messenger of Chiminingua" (q.v.). *See also* Bachue (goddess of water); Chaquen (god of boundaries); Chia; Chibchacum; Cuchavira (god of air and the rainbow); Fomagata (storm god); Nencatacoa (god of weavers).

Bochicha (Bogata, South Africa) *see* Bochica.

Bod-Baal (Ugarit)
He assisted Baal in his battle with the Son of the Sea, Khoser-et-Hasis, and the Lord of the Sea, Zabel, and the beast Suffete, the Lord of the River. *See also* Baal.

Bodb (Celtic)
Also known as: *Bodb Dearg, Bodb Derg, Bod the Red, Bov.*
Father of deities. Bodb is either the son of Dagda and Boann, or the father of Dagda. He succeeded his father as ruler of the gods. After the defeat of the Tuatha De Danann, he became their king. His daughter, Aoife (also spelled Aeife), turned his stepchildren into swans, so he punished her by transforming her into a wind demon. Bodb eventually retired to the retreat of the gods. The name Bodb is sometimes confused with Badb, who is a goddess of battle. *See also* Aebh; Angus; Balor; Boann; Dagda.

Bodb the Red (Celtic) *see* Bodb.

Boddhisattvas (India) *see* Bodhisattvas.

Boddi (Teutonic) *see* Heimdall.

Boden (Teutonic) *see* Bodn.

Bodhisats (India) *see* Bodhisattvas.

Bodhisattva Cakdor (Tibet) *see* Vajrapani.

Bodhisattva Cheresi (Tibet) *see* Avalokitesvara.

Bodhisattvas *Boddhisattvas, Bodisats, Bodisatvas, Buddhas*
Also known as: *Pu-sa* (China); (Buddhist, India)
Bodhisattvas originated in the Mahayana branch of Buddhism. They are spiritually advanced persons who have achieved complete enlightenment. This qualifies them for Nirvana, the state of detachment from suffering. However, Bodhisattvas have chosen to remain in the world to assist and guide humans who have not achieved enlightenment. Although there are numersous Bodhisattvas, the common Bodhisattva trinity is composed of Avalokitesvara, Manjusri and Vajrapani. Maitreya, the future Buddha, is the last of the Bodhisattvas. Bodhisattvas are usually

shown in a group of five, seated in an attitude of profound meditation (dhyana). Manjusri and Maitreya are shown seated on a throne. *See also* Dhyani Buddhas; Dhyanibodisattvas.

Bodisats (India) *see* Bodhisattvas.

Bodisatvas (India) *see* Bodhisattvas.

Bodn *Boden* (Norse; Teutonic)
Bodn is the crock used to create the mead of poetry which was brewed from Kvasir's blood. Two other vessels were used to mix the brew: the crock Son, and the kettle Odraerir. Kvasir was killed by the dwarfs Fjalar and Galar. *See also* Kvasir; Odraerir.

Boe (Teutonic)
Also known as: *Vale.*
One of the sons of Odin and Rind (the personification of the hard, frozen earth). He avenged the death of Balder by killing Hodur. *See also* Hodur; Odin; Rind.

Boeotus (Greek)
He is the son of Poseidon and Arne (also known as Melanippe), the brother of Aeolus, the father of Itonus, and grandfather of Hippalcimus. *See also* Aeolus (B); Arne.

Boetis (Greek)
This goat or the goat Aex became the mother of Aegipan with Zeus. *See also* Aegipan.

Bogatyri (Slavic)
Also known as: *Bogatyr* (singular).
Spirits or gods of the Christian era. Some say they are river spirits. Their names are Ilya-Muromyets, Mikula, Potok-Mikhailo-Ivanovich, Sadko, Svyatogor, Volkh (Volga). Epic poems, known as "byliny," were written about these deities. Eventually, the Bogatyri were beaten. They fled to caves where they turned to stone.

Bogu (Sumer) God of Wealth.

Bohu (Mesopotamia)
Also known as: *Baau, Bahu, Bau, Gur.*
Earth Mother. *See also* Bau; Ea.

Boi (Celtic, Gaelic) *see* Cailleach Bheare.

Bokika (Bogota, South America) *see* Bochica.

Bolon-Ti-Ku (Maya People, Yucatan) *see* Ahmucen-Cab.

Bolon-Tsac-Cab (Maya People, Yucatan) *see* Ahmucen-Cab.

Bolthorn (Norse; Teutonic)
He is the frost giant brother of the wise giant Mimir, and grandfather of Odin, Vili, and Ve. *See also* Bestla; Bor; Buri; Mimir; Odin; Odraerir.

Bolverk *Bolverkr, Boverkin* (Norse; Teutonic)
Also known as: *Evil Doer, Odin.*
Aspect of Odin. Bolverk is one of the names chosen by Odin when he journeyed to Jotun-heim to find the mead of poetry made from Kvasir's blood. He also uses this name when in the role of a war god. *See also* Baugi; Jotun-heim; Kvasir; Odin.

Bolverkin (Teutonic) *see* Odin.

Bombor *Baumbur* (Teutonic) *see* Dwarfs.

Bomersum (Saora People, India)
God of the marketplace. *See also* Adunankisum; Babusum.

Bomong (India) *see* Bong.

Bona Dea (Roman)
Also known as: *Fatua, Fauna.*
An ancient goddess of women. Possibly a goddess of fertility. She is reputed to be a relation of the god Faunus (possibly wife or daughter), or possibly just a female form of Faunus. She is supposed to be a goddess of fertility. Her true name is not known because she has refused to give one hint of it. She is a great prophet, a dispenser of healing herbs, and is quite chaste. She also permits no wine to be imbibed in her presence. Her name means "the Good Goddess." She was worshiped in early December in secret by women only. Bona Dea ("Good Goddess") was the most popular name used in the worship of Fauna Fatua. Bona Dea is identified with Maia and Rhea. *See also* Cybele; Faunus; Ops (a Sabine goddess).

Bondi (Teutonic) *see* Heimdall.

Bong and Bomong (Minyong People, India)
Sky and earth goddesses.

Bonus Eventus (Roman)
Agricultural deity. He is a rural god in charge of the harvest. Some say he is a god of success or luck.

Boodh (India) *see* Buddha.

Boodha (India) *see* Buddha.

Bor *Borr* (Norse; Teutonic)
He is the son of Buri and spouse of the giant Bestla, who is the daughter of Bolthorn. Bor and Bestla are the parents of Odin, Vili, and Ve, the ancestors of the Aesir. Odin, Vili, and Ve finally succeeded in slaying the great giant Ymir, and all of the other Giants except Bergelmir. *See also* Audhumla; Bergelmir; Bestla; Bolthorn; Buri; Midgard; Odin; Ve; Vili; Ymir.

Boreadae (Greek) *see* Boreas; Zetes.

Boreades (Greek) *see* Boreas; Zetes.

Boreas (Greek)
Also known as: *Aguilo* (Latin), *North Wind.*
God of the North Wind. Boreas is the son of the Titan Astraeus ("Starry Night") and Eos ("Dawn"). Boreas, who resided in Thrace, fell in love with the nymph Oreithyia (also spelled Orithyia) who lived in Athens. The match did not sit well with the Athenians, who hated the Thracians because of the despicable deeds of Tereus. Boreas, as the North Wind, took matters into his own hands and whisked his loved one off her feet and took her to Thrace. His mother is the goddess of dawn, Eos, who had earlier abducted her lover, the beautiful Cleitus. Boreas and Oreithyia became the parents of Chione, Cleopatra, the winged twins Zetes and Calais, and Haemus. In the Pelasgian creation myth, Boreas is the fertilizing force which impregnates Eurynome, the Goddess of All Things. Boreades (also spelled Boreadae) is generally used as a name for the twins, Calais and Zetes, but it is sometimes used when referring to

www.ebook3000.com

the children of Boreas. It is also used when referring to the twelve horses sired by Boreas in stallion form when he mated with the mares of Erichthonius (also spelled Erechtheus), king of Dardania, said to be the world's richest man. Astraeus is the daughter of Erechtheus who was referred to by Homer as the grandson of Erichthonius. Other sources write that they are one and the same person. Boreas is usually depicted with snake tails in place of feet, or as a young man flying about in a playful way and sometimes as being the father of rain, snow, hail and tempests and also as an old winged man, veiled in clouds. Compare to Fujin (Japan). Boreas is the equivalent of the Roman Aquilo. *See also* Aello; Chaos; Chimaera; Cleite; Eos; Eurus; Eurynome (A); Harpies; Notus; Tereus; Zephyrus.

Bori (Teutonic) *see* Buri.

Bormanus (Celtic, Gaul) *see* Borvo.

Bormo (Celtic, Gaul) *see* Borvo.

Borr (Teutonic) *see* Bor.

Borus (Greek)
He is the son of Perieres and Gorgophone. His siblings are Aphareus, Icarius, Leucippus and Tyndareus. Borus married Polydora (q.v.). *See also* Gorgophone; Icarius.

Borve (Celtic) *see* Borvo.

Borvo *Bormo* (Celtic, Gaul)
Also known as: *Belenos, Bormanus, Borve* (possibly), *Gramnnos.*

"God of Hot Springs." He is a divine healer who wards off illness, and a god of health giving springs. Borvo means "to boil." His consort was the Gaulish goddess of cattle, "The Divine Cow," Damona. In some renditions, he is thought to be the son of the early mother goddess, Sirona, (also known as Dirona), whom he displaced. Borvo may be the same as Borve, a Cymric king. The deity Bel, also known in the British tradition as Belinus, was called Belenos, as is Borvo. They are likely aspects of the same deity originating with Apollo (q.v.). *See also* Bel (B); Damona.

Bosheth (Hebrew) *see* Bast (Egypt).

Boshintoi (Siberia)
God of blacksmiths. Boshintoi and his nine sons made the horse post of the North Star.

Bossu (Dahomey People, Africa; Haiti)
Also known as: *Akadja.*

Malevolent spirit. A voodoo deity worshiped by the criminals of the underworld. Some say he might have been a mortal king named Kadja Bossu whom the Dahomey called Akadja. He is said to be a rival of the god of iron, Ogun. Bossu is related to the work god, Mounanchou. *See also* Ogun.

Bouddha (India) *see* Buddha.

Boulaia (Greek)
Another title of Athene as a goddess of council. *See also* Athene.

Bous (Teutonic) *see* Vali.

Bouto (Egypt, Greek) *see* Buto.

Bouyan (Slavic) An island paradise. *See also* Alatuir.

Bozaloshtsh (Slavic)
Messenger of death. She is described as a small woman with long hair who appears under the window of someone approaching death. Similar to Banshees (q.v.).

Brage (Teutonic) *see* Odin.

Bragi (Teutonic)
Also known as: *Brage, Odin* (possibly).

An Aesir, Bragi is the son of Odin and Frigga, and spouse of Idun (also known as Iduna). He is the lord of the sky and day, the god of poetry and eloquence, and the patron of bards. He may be an aspect of Odin. Bragi and Hermod welcomed all heros to Valhalla. Bragi is depicted as an old man with a long white beard. He carries a harp. *See also* Aesir; Hermod; Hoenir; Ull; Vali.

Brahma *Brahmans* (Brahmanic, Buddhist, Hindu; India)
Also known as: *Abjaja,* ("Born from a Lotus"), *Abjayoni, Adharma* ("Destroyer of All Things"), *Maha-pita* ("The Great Father"), *Narayana, Pitamaha* ("Grandfather"), *Prah Prohm* (Cambodian), *Prajapati* ("Lord of Creation"), *Purusha, Ts'ana-Pa* ("White Brahma"; Tibet).

Brahma, a creator god, received the basics of his mythological history from Purusha. During the Brahmanic period, the Hindu Trimurti was represented by Brahma with his attribute of creation, Shiva with his attribute of destruction and Vishnu with his attribute of preservation. The later Brahmans gave him the role of the Vedic Hiranyagarbha and Prajapati. He was born from Narayana, the golden primeval egg. The *Ramayana* states that he is self-existent, created himself as a boar, raised the world from the primeval waters with his tusks and formed the universe. In the *Mahabharata* epic he sprang from the right side of the great god Mahadeva. Others believe that Mahadeva sprang from Vishnu's forehead and Brahma sprang from Vishnu's navel, or from the lotus growing from Vishnu's navel, which makes him an avatar of Vishnu. In the "Laws of Manu," The "Self-Existent" Brahmam created the primeval waters and the golden egg with his seed within it. He emerged from the egg as Brahman and is simultaneously the son of the primal spirit, Narayana, the primal man, Purusha, and the creator god, Brahma. The "Vishnu Purana" presents Brahman as the essence of the world and the creator. In another creation myth, Brahama initially created ignorance, which he threw away. She survived and became Night. From Night came the Rakshasas and Yakshas, who are sometimes enemies but usually helpful. He then created the immortals. From his hip came the Asuras, who became enemies of the gods. The earth came from his feet, and all other elements of the world from other parts of his body. In other renditions, Brahma began the creation process and became discouraged, so he created four Munis (sages) to complete his work. Their interest in worshiping the universal spirit, Vasudeva, took precedence over their assignment from Brahma. This angered the great god and from his anger the deity Rudra was formed to complete the creation process. Brahma's paradise was Brahmaloka, located on Mount Meru. Some say that Surya, the sun god, may be the son of Brahma. The goddess of learning, Sarasvati, is Brahma's principal wife.

He is the father of the capable Daksha, who was born from his thumb, and the wise Atri. He is the grandfather of King Yudhishthira. Narayana is said by some to be an aspect of Brahma and by others an aspect of Vishnu. In some renditions of the Buddhist tradition, Brahma and Indra interacted with Buddha. In one myth the two gods bathed the newborn Buddha. The god Brahma initially was not the same as the neuter gender god-force of the "Upanishads," Brahman. In later times, however, Brahma did become identical with Brahman. Brahma, often in fish form, is usually depicted as having four bearded faces and four arms (representing the four Vedas) and seated on a lotus throne. With his four faces, he controls the four quarters of the universe. The lotus represents Mani, the earth. He holds the disk, alms dish, or spoon in his hands. Originally Brahma had five heads, but one was burnt off by Shiva's third eye when he discovered that Brahma lusted incestuously after his daughter Sandhya. Sometimes he is imaged with three faces. His color is red, and he is sometimes shown as a peacock or a swan. He is also shown riding on Hansa his goose, who has a spotted red and blue peacock's tail. Sometimes he is seated in his chariot, pulled by seven swans who symbolize the seven worlds, or some say clouds. He wears the skin of a black antelope and is dressed in white. His sword, named Asi, is the sun's ray born of a sacrifice made on his altar called Samantapancaka. In his aspect as Abjaja (also known as Abjayoni) he is depicted sitting on a lotus, rising out of the navel of Varuna, who is connected by a flower stem (umbilical cord) to Narayana-Vishnu. When Brahma surveyed the four corners of the universe before beginning the creation process, it symbolized the four functions of the consciousness that the mortal must achieve: thought, feeling, intuition, and sensation. At all rites for Brahma he is presented with a single flower and Ghee (sacrificial butter). During the full moon night in January, he is adorned with Vishnu and Shiva on either side. The next day, the images are cast into holy waters. The symbol of the Trimurti is the syllable om, made up of the three sounds, a, u, m. Brahma's arrow is named Naga-pasa. The Tibetan Ts'ana-pais is usually shown brandishing a sword and carrying a white bull. Compare Brahma to the creation myths of Manu and Varuna. Compare him to Abram. *See also* Agastya; Agni; Ahalya; Andhaka; Ardhanari-Ishvara; Asuras; Brahman; Buddha; Daksha; Dwaparayuga; Gandharvas; Ganesha; Garuda; Gramadeveta; Hansa; Hiranyakasipu; Hiranyagarbha; Kama (A); Karttikeya; Kuvera; Loka; Manjusri; Manu; Marichi (B); Meru Mountain; Narada; Narayana (A); Narayana (B); Narayana (D); Prajapati; Purusha; Rakshasas; Ratri; Ravana; Rishi; Rudra; Sandhya; Sarasvati; Savitri (B); Shiva; Skambha; Surya; Tara (A); Vach; Vasistha; Vishnu; Visvakarmna; Yaksha and Yakshini.

Brahma-Kapla (India) *see* Kalpa.

Brahmaloka (India) Brahma's Paradise. *See also* Brahma.

Brahman (Hindu)
Also known as: *That, Absolute.*

"Truth." Infinity or the Absolute. According to some authorities, the world is illusion. It can exist inwardly or outwardly. It is the indescribable world of illusion. Brahman was the neuter gender world spirit, the All-god. In later times, Brahman and Brahma were considered the same. *See also* Brahma; Sarasvati.

Brahman — Creation Legaue (Hindu; Vedic) *see* Brahma; Prajapati (A); Purusha

Brahmanaspati (Hindu; India) *see* Brhaspati.

Brahmani (India)
Wife of Brahma. *See also* Brahma; Devi; Sarasvati.

Brahmans (India) *see* Brahma.

Brahmapura (India)
Brahma's heaven, located on Meru Mountain (q.v.).

Brahmarishis (India) *see* Rishi.

Brahmi (India) *see* Sarasvati.

Bramanaspati (India) *see* Brihaspati.

Bran (British, Celtic, Welsh)
Also known as: *Bendegeit Bran, Bendigeid Fran, Bendigeid Vran, Bran the Blessed, Leodegrance, Vron.*

A brave giant, Bran is the brother of Branwen and Manawyddan and the son of Llyr by Iweridd or, some say, Febal. He has two half-brothers, Nissyen and Evnissyen (also spelled Efnissien), who were enemies. Bran was the possessor of a cauldron with the power to bring the dead back to life, but without the restoration of the power of speech. When his sister, Branwen, married the king of Ireland, Matholwch, he gave the cauldron to the Irish. This gift was compensation for the humiliation Evnissyen had caused the Irish. The ungrateful Matholwch subsequently imprisoned his new wife in the castle kitchen and treated her like a servant. Bran, with the British fleet behind him, walked through the sea to rescue his sister. A battle ensued and the defeated Irish offered to get rid of Matholwch and allow Gwern, the son of Branwen and Matholwch, to assume the throne. Evnissyen reappeared on the scene and killed Gwern. The fighting resumed but neither side emerged the victor. The Irish brought their dead to life until Bran smashed the magic cauldron. Seven Britons survived: Pryderi; Manawydan; Glunen, the son of the culture hero Taran; Taliesin; Ynawc; Grudyen, the son of Muryel; and Heilyn, the son of Gwynn the Ancient. Bran, severely wounded by a poisoned arrow, asked the survivors to behead him. It was said that his head was buried in London with eyes toward France to ward off all invaders. His head, which supposedly lived for eighty-seven years, is variously called: Uther Ben ("Wonderful Head,") Uther Pendragon, or Urien. (A starling brought Bran the message of his sister's distress. The birds of Rhiannon kept his head distracted from discomfort by their sweet singing.) *See also* Branwen; Manawydan Ap Llyr; Pryderi; Rhiannon.

Bran the Blessed (Celtic) *see* Bran.

Branwen *Brangwaine, Brynwyn, Dwynwen* (Celtic, Irish, Welsh)

A deified mortal, Branwen was the daughter of Llyr by Iweridd, and sister of Bran and Manawyddan. Famous for her beauty, she attracted the king of Ireland, Matholwch (also spelled Matholwych). Their marriage temporarily united Britain and Ireland. When Bran heard from a starling that the king was keeping his sister prisoner in the castle kitchen, he went to rescue her. A battle developed and peace resulted for a brief period. Branwen's step-brother Evnissyen, murdered

www.ebook3000.com

their son Gwern, bringing about war. Grief-stricken, Branwen died. *See also* Bran; Evnissyen; Manawydan Ap Llyr; Pryderi.

Brathy (Phoenician)
One of the giants of the mountains. They were the inventors of incense. Three others were named Cassios, Lebanon, and Antilebanon.

Brattskegg (Teutonic) *see* Heimdall.

Breathmaker (Seminole People, North America)
The Milky Way was created by Breathmaker by blowing at the sky. This is the path the people and their animals follow when they die en route to a "city in the western sky." Breathmaker also taught the people how to dig wells and find fish.

Brechta (Teutonic) *see* Bertha.

Breg (Celtic) *see* Dagda.

Breid (Teutonic) *see* Heimdall.

Breidablik (Norse; Teutonic)
Also known as: *Broad Splendor.*
This is Balder's residence in Asgard. It has golden pillars and a silver roof. It became his zodiacal house, which corresponds to the sign of the twins, Gemini. *See also* Asgard; Balder; Gladsheim; Sovabek.

Breit-Hut (Teutonic) *see* Odin.

Breksta (Lithuania)
Goddess of the passing hours of darkness. Her companions are Ausrine, the dawn, and Zleja, the high day.

Bres (Irish) *see* Bress.

Bres mac Elatha (Celtic) *see* Bress.

Bress *Bres* (Celtic, Irish)
Also known as: *Bres mac Elatha.*
Sun deity. Bress "the beautiful" is the son of the Fomorian sea king, Elathan, and the Tuatha De Danann earth mother goddess, Eriu. He married the goddess Brigit, who is the daughter of Dagda. Bress was appointed king of the Tuatha De Danann when king Nuada had his hand severed during the First Battle of Magh Tuiredh against the giant Firbolgs. Their motive in appointing him was an attempt to appease their enemies the Firbolgs. He turned out to be a dreadful tyrant who raised taxes and monopolized food sources which humiliated the people and made them subservient. In legend, there are many horror stories about his evil practices. Fortunately, the Tuatha De Danann had a rule that kings who were physically maimed could not reign. King Nuada lost the throne to Bress under that edict. A poet could cause the disfigurement of a king by satirizing him. In one eventful happening, the chief poet Cairbe's words were so scathing they caused Bress' face to erupt in boils. The Tuatha ousted him and he joined the Fomorians. In the Second Battle of Magh Tuiredh, he fought against the people he had once ruled and was defeated. *See also* Banbha; Brigit; Dagda; Dia'necht; Lugh; Nuada; Tuatha De Danann.

Brhaspati *Brahmanaspati* (Hindu; India)
The "Lord of Devotion," he brought light to the world. His worshipers are given long life and victory. Brhaspati is sometimes thought to be the same as Agni (q.v.).

Brian (Celtic) *see* Cian; Dana.

Briareus (Greek)
Also known as: *Aegaeon, Obriareus.*
He is one of the Hecatonchires, sons of Uranus and Gaea. *See also* Aegaeon; Gaea; Hecatonchires.

Brid (Celtic) *see* Brigantia.

Bride (Celtic, Irish) *see* Brigantia; Brigit.

Bridge of Pain (China) *see* K'u-ch'u K'iao.

Bridge of the Gatherer (Persian) *see* Chinvat Bridge.

Bridge of the Requiter (Persian) *see* Chinvat Bridge.

Bridget (Celtic, Irish) *see* Brigantia; Brigit.

Brig (Irish) *see* Brigit.

Brigantes (Celtic) *see* Brigantia.

Brigantia *Brigindo* (British, Celtic, Irish)
Also known as: *Brid, Bride, Bridget, Brighid, Brighit, Brigid, Brigin-do, Brigit, St. Bridget.*
Protector deity. Multi-function goddess. Brigantia is a goddess of northern England, the protective goddess of the Brigantes, the largest tribe of Britain, which was named after her. It is said that she was raised on the milk of a magic cow from the Otherworld who was white with red ears. A goddess of the seasons, she watched over springs, streams, cattle and lambs. She is also a goddess of the hearth and fertility. She oversees the pain of women in childbirth. In Scottish mythology, she is Brigid, the goddess and saint, who oversees the coming of spring and ends the winter reign of Cailleach Bheur. Brigantia corresponds to the goddess Brigit of Ireland and also has aspects of the Irish Danu. She is often equated to the Romano-British goddess, Minerva. She is shown wearing a globe shaped crown, armed and wearing a breastplate, or bare-breasted. *See also* Bheur; Boann; Brigit; Cailleach Bheur; Dana; Minerva.

Brighid (Celtic) *see* Brigantia; Brigit.

Brighit (Celtic) *see* Brigantia; Brigit.

Brigid (Celtic, Irish) *see* Brigantia; Brigit.

Brigindo (Celtic) *see* Brigantia.

Brigit *Brighid, Bridget, Brigid* (British, Irish, Scottish)
Also known as: *Bride, Brig.*
Patroness of culture and learning. Goddess of healing. Brigit is the daughter of Dagda, who was a leader of the Tuatha De Danann. In some myths, she has two sisters of the same name; however, this could be her aspects as a triple-goddess, patroness of poets, healers and smiths. She is said to have a brother, Angus, who is the Irish Cupid. Brigit married a Fomorian, Bress, and had a son, Ruadan. Ruadan was slain by the Tuatha De Danann weapon-maker, Goibnui. In her grief, Brigit initiated the first "keening" in Ireland, a wailing lamentation. She is often equated with the Celtic Brigantia, as they share the attributes of fertility and abundance. However, Brigit had the additional aspects of culture and skills. She has been equated with Dana and Anu, but the worship of Brigit was more widespread as illustrated in the eventual adoration of St. Brigit. Like

Brigantia, she is referred to as the Celtic version of Minerva. *See also* Angus; Anu; Boann; Bress; Brigantia; Dagda; Dana; Minerva; Ruadan; Tuatha De Danann.

Brigitte (Haitian)

Also known as: *Maman Brigitte.*

Deity of cemeteries. Goddess of the dead. Female counterpart of Ghede who was an aspect of Baron Samedi. *See also* Ghede.

Brihadratha, King (India) Big Carriage. *See also* Jara-Sandha.

Brihaspati (Brahmanic, Hindu, Vedic; India)

Also known as: *Angirasa, Bramanaspati, Purohita* (the family priest of the gods), *Vyasa* (an incarnation in the fourth Divapara age).

He is a creator deity, a god of incantation and ritual, who is called the "Chaplain," "Master of Formula," "Creator of All Things," and "He Whom the Gods Themselves Would Consult." In the Vedic tradition, he is an abstract deity, known as the first of the Vedic priests. To the Brahmans, he is the divine sage Angirasa, son of Angiras. The Puranas tell of a battle between the gods, with Brihaspati leading the Angirasa line of seers, and the Asuras, led by Shukra (the personification of Venus) of the Brigus. His spouse, Tara (the personification of the stars), was abducted by the moon, Soma. A divine war, known as the Tarakamaya, erupted. Indra supported Brihaspati, and Rudra, the Daityas and the Danavas. The sage Usanas, who had an ancient feud with Brihaspati, supported Soma. The earth, Bhumi, was so unsettled that she appealed to Brahma to bring an end to the battle. He acknowledged her request and ordered Soma to allow Tara to return to Brihaspati. She gave birth to a dazzling son named Budha, who represents the planet Mercury, and had to admit to Brahma that he was the child of Soma. When Brihaspati found out, he was so enraged that he turned her to ashes. Brahma intercepted and returned her in a purified form and Brihaspati reunited with her. Soma was disinherited by Varuna as punishment for his role in the event. Brihaspati is one of the Rishis, who were poets, sages and prophets born from Brahma's mind. His son Bharadvaja also became a poet and sage to the Pandavas. Another son, Kacha, was sent to study with the chief priest of the Asuras to learn the secret of the charm that restores life to the dead. The Asuras killed him several times, but he was restored to life by his teacher. The Balis of Ceylon identified Brihaspati as the planet Jupiter, but worshiped him as phallic. He is depicted with a large halo of moon and stars over a conical headdress. His body is gold, his legs striped blue. In each hand he holds a phallus. Sometimes he is shown holding a container of soma in his left hand. He is also shown sitting or leaning on a tiger. At his feet rests a half-fish, half-human monster. His vehicle, the Niti-ghosha, is drawn by eight pale steeds. He is also shown with seven mouths, sharp horns, a hundred wings, holding an ax and a bow. His day of the week is Thursday and his zodiac sign is either Sagittarius or Pisces. *See also* Bharadvaja; Bhumi; Brighus; Daityas; Pandavas; Prajapati; Rishi; Rudra; Tara (A); Vach.

Brimir (Norse; Teutonic)

Giant. His hall will survive Ragnarok. It is a warm place where there will be plenty of food and drink. *See also* Ragnarok.

Brimo (Greek) *see* Demeter; Hecate; Persephone; Rhea.

Briseis (Greek) *see* Brises.

Brises (Greek) *see* Achilles; Calchas.

Brisingamen (Norse; Teutonic)

Also known as: *Brisings' Necklace, Sviagris.*

Freyja had sex with the four dwarfs, Alfrigg, Berling, Dvalin and Grerr, to gain ownership of the deified necklace, Brisingamen. Odin was so angry when he heard about Freyja and the dwarfs, he forced Loki to steal Brisingamen. In the meantime, Freyja broke the necklace when she heard that the giant Thrym demanded to marry her as compensation for returning to Thor his magic hammer, Mjollnir. *See also* Dvalin; Dwarfs; Freyja, Mjollnir; Thor; Thrym.

Brisings' Necklace (Teutonic) *see* Brisingamen.

Britomaris (Greek) *see* Britomartis.

Britomartis *Britomaris* (Crete, Greek)

Also known as: *Aphaea, Aphaia* (her name in Aegina, meaning "invisible"), *Dictynna* ("Lady of the Nets" or "Netted One").

Goddess of fishers, hunters, sailors. Britomartis, the daughter of Zeus and Carme, was a Cretan nymph. She received the name Britomartis from King Minos of Crete because she refused his advances and tried to kill herself. She flung herself from a cliff into the ocean. The fishing nets that she had invented as a gift to mortals saved her life. From that time, she was known as Dictynna ("netted one"). For protecting her chastity, Artemis placed her with the immortals in the heavens as a star. Other sources state she ruled the eastern end of the island as Britomartis and the western section as Dictynna. She became an aid to navigators. Her name became a title of Artemis as a fish goddess. As Aphaia, a local deity of Aegina, Britomartis is comparable to Athena, the goddess of wisdom. As she attempted to escape the advances of Minos, she was trapped in a fishing net and brought to Aegina by the fishermen. One of the men fell in love with her and ran into a densely wooded area and disappeared. In another rendition, her attempted escape from Minos caused her death. Her name was changed to Dictynna and she was made immortal. *See also* Artemis; Minos; Dictyanna; Pasiphae.

Broad Splendor (Teutonic)

Another name for Balder's residence, Breidablik (q.v.).

Brokk (Norse; Teutonic)

A dwarf who, along with Sindri or as some say Eitri, manufactured the golden hair for the goddess Sif after Loki cut off her real hair. Loki also received Skidbladnir, a magic ship for Freyr, and a magic spear named Gungnir for Odin. *See also* Dwarfs; Eitri.

Bromius and Evan (Greek) *see* Bacchus.

Bronte (Greek) *see* Helios.

Brontes (Greek)

"Thunder." Brontes, one of the Cyclopes, has a single eye in the middle of his forehead. *See also* Acamas (D); Aegaeon; Cyclopes; Gaea.

www.ebook3000.com

Broteas (Greek)
The son of Tantalus and Dione, the brother of Niobe and Pelops, Broteas was renowned for the figure of the Mother Goddess that he had carved in stone. When he was asked by the great hunter-warrior goddess Artemis to carve her likeness, he refused. Broteas went insane and burned himself to death. *See also* Artemis; Niobe; Pelops; Tantalus (A).

Broth of Oblivion (China) *see* Mi-Hung-T'ang.

Brownie (Scot)
This goblin is similiar to the elves. There is a possibility that Brownie was originally a pre–Celtic god. *See also* Dwarfs; Elves.

Brud (Teutonic) *see* Heimdall.

Brunhilde (Teutonic) *see* Brynhild.

Brut (Celtic)
Also known as: *Brute, Brutus.*
Deified mortal. In Geoffrey of Monmouth's account of early history, a descendant of Aeneas who, after his conquest of Albion, became king of the island, then called Britain after his name. At the direction of Diana, Brut the mortal and a group of Trojans founded Britain, which was at that time known as Albion and was inhabited by a race of giants.

Brute (Celtic) *see* Brut.

Brutus (Celtic) *see* Brut.

Brynhild *Brunhild, Brunhilde* (Teutonic)
As Brynhild, she was one of the Valkyries. In some versions she was queen of Iceland and wife of Gunther. Associated with Siegfried. *See also* Valkyries.

Buan-Ann (Celtic) *see* Anu (B).

Buana (Celtic, Irish) *see* Boann.

Bubastis (Greek) *see* Bast; Buto; Uadjit.

Buchis *Bacis* (Egypt)
Also known as: *Bakh, Bakha, Bkha, Bukhe* (Egypt), *Menthu-Ra, Mont.*
Buchis, the sacred bull, lived at Hermonthis in Upper Egypt. It is believed that Mont (also known as Menthu, Mentu, and Muntu) was often incarnated as Buchis. As Bacis or Bakh he was the Egyptian bull representing the sun-god Ra. Buchis is also the Greek rendering of the Egyptian Bukhe. Buchis is also thought to be an incarnation of Osiris. His counterpart was the sacred Apis bull at Memphis. He is shown with black hair that grows in the opposite direction from other animals. He changes his color every hour of the day. *See also* Aa Nefer; Apis (A); Mnevis; Mont.

Buddh (India) *see* Buddha.

Buddha *Boodh, Boodha, Bouddha, Buddh* (Buddhist, Hindu; India)
Also known as: *Buddha-Avatara* (Vishnu's ninth avatar), *Gautama, Gotama, Jina, Sakyamuni* ("Sage of Sakya"), *Siddartha* ("One Who Has Achieved His Purpose"), *Shih-Chia-mou-ni* (China), *Tathagata* ("One Who Has Thus Arrived").
The name Buddha means the "Awakened One." As the future Buddha or Bodhisattva (meaning the would-be-Buddha), he had passed through thousands of years before coming to earth. Most Western scholars agree that his birth date was 566–486 B.C.E. Others say the date is 563–486, or 558–478 B.C.E. While Buddha was in Tusita heaven, he determined the time, date, location, and the mother who would give birth to him. He came into the world as Gautama, the son of Maya and a Rajah, Suddhodhana, the chief officer of the Sakyas in Kapilavastu. Maya dreamed that a white elephant with six tusks entered her womb. Then she saw the full moon drop into her lap. Sixty-four Brahmans predicted the birth of a son who would be a Buddha or a universal emperor. The quasi-virgin birth of her son followed, as he issued forth from her right side. At the same moment, his future wife, his horse, elephant, charioteer and the bo-tree (*Ficus religiosa*) were born. Seven days after his birth, his mother died of joy. Raised by his mother's sister, Mahaprajapti, he grew up surrounded by luxury. When he was sixteen years old, he won his bride, Yasodhara, the daughter of Dandapani, in an armed contest. They became the parents of a son, Rahula. At twenty-nine years of age, Gautama tired of worldly ways. His faithful driver and confidant Channa prepared the horse Kanthaka for his master. Gautama left his wife and son and retired to contemplate in the wilderness for six years. During this period he survived torments and temptations and arrived at a state of complete enlightenment (bodhi) as he sat under a banyan tree. He could have entered Nirvana at that point, but his compassion led him back to the world to share his wisdom. Assisted by his son, he wandered throughout India and taught to anyone who would listen. In his eightieth year, he left the world and retired to Paranirvana, the highest state of absolute bliss. Buddha regarded himself as a Tathagata: one who has "arrived," one who has experienced and transcended the imperfections of life. Numerous stories of Buddha's life are found in a collection of stories known as the "Jatakas." According to some, Buddha was the ninth avatar of Vishnu (Buddha-Avatara). Buddhists do not accept this theory. The original Buddha was depicted as a wheel, empty throne, or a tree. The white elephant was a royal symbol. In later times, he was depicted with short, curly hair, seated on or in a lotus. In the Mayayana tradition, Buddha is sometimes depicted in princely attire complete with jewels and a diadem. Buddha, Vairocana and Maitreya share the same mudra: dharmacakra (both hands against the breast, left hand covering the right). This mudra is the mudra of preaching. Often he is shown with the jnana mudra (the hand held up with the thumb touching the tip of the index or middle finger; the sign of insight). The book containing the essential teachings of Buddha is known as "The Dhammapada" (q.v.). For a similar legend, *see* Mahavir. *See also* Arhats; Asvaghosa; Brahma; Dipamkara; Hariti; Jagannath; Manushi Buddhas; Mara; Marichi (A); Maya (A); Miroku-Bosatsu (Japan); Mucalinda; Sakra; Sakyamuni; Stupa; Tushita; Vairocana; Vajrapani; Vishnu.

Buddha-Avatara (India) *see* Buddha; Vishnu.

Buddha Dakini (Tibet) *see* Khados.

Buddha Dakinis (India) *see* Dakinis; Khados.

Buddhi (India)
Goddess of wisdom and knowledge. *See also* Ganesha; Karttikeya.

Buddhist Universe (India) *see* Chakravala.

Budha (India)
The son of Tara and Soma, and spouse of Ida. He personifies the planet Mercury. *See also* Brihaspati; Ida (B); Tara (A).

Bugan *Bigan* (Ifugao People, Philippines)
He is the son of the first woman and brother of Wigan, the mother of humanity after the Deluge. *See also* Wigan.

Bui (Teutonic) *see* Cailleach Bheare; Heimdall.

Bukhe (Egypt, Greek) *see* Buchis.

Bulaia (Greek) *see* Athena.

Bull of Amentet (Egypt) *see* Apis (A).

Bull of Confusion (Egypt) *see* Iti.

Bull of Meroe (Egypt) *see* Ra.

Bull of the Underworld (Egypt) *see* Apis (A).

Bull of the West (Egypt) *see* Osiris.

Bumba (Bantu, Bushongo People, Africa)
Also known as: *Chembe, Jambi* (possibly the same, or a similar creation god), *Nyambe, Nyambi, Nzambi.*

Bumba is the high god of creation, who established the tabus and appointed the rulers. After he returned to heaven, he only communicated with mortals in dreams. He is described as a giant white being who vomited up the sun, moon, stars and living creatures. He taught the mortal, Kerikeri, the secret of making fire. He is similar to Leza (q.v.) *See also* Nyambe.

Bumerali (Aborigine People, Australia)
Lightning goddess. *See also* Pakadringa.

Bunbulama (Aborigine People, Australia)
Goddess of Rain. *See also* Bumerali; Pakadringa.

Bundahish *Bundahisn, Bundahishn*
Also known as: *Zandagahih* (Zoroastrian; Persia).

Thought to have been translated from an original Zend manuscript, the "Bundahish" is an important Zoroastrian work encompassing the six days of creation, astronomy, the wars of Ahura Mazda and numerous other topics. Another important work is the "Denkart," an encyclopedia of religious lore. *See also* Ahura Mazda; Ahzi Dahaka; Avesta; Tishtrya; Yashts.

Bundahishn (Zoroastrian) *see* Bundahish.

Bundahisn (Zoroastrian) *see* Bundahish.

Bundinskeggi (Teutonic) *see* Heimdall.

Bunjil *Bun-Jil* (Kulin, Wurunjeri People, Australia)
Also known as: *Biral, Daramulun, Mami-Ngata, Ngurunderi, Pun-Gel.*

The supreme being. He is said to have two wives. His son is Binbeal, the rainbow. He could have other children. Bunjil created man out of clay while his brother, the Bat (Ngunung-ngunnut), brought women out of water. Bunjil is probably the same as Baiame, Daramulun, or Nurrundere. *See also* Daramulun; Gidja; Pun-Gel.

Bunomus (Greek) *see* Helen.

Bunosi (Melanesia)
Bunosi is the snake child of a normal woman and the brother of Kafisi. He coughed up the first plants and pigs. His large tail fills a room. *See also* Kafisi; Marruni.

Bunyip (Australia)
These water monsters were involved in the great deluge. Apparently, a group of men caught a small Bunyip. Its mother was so angry she flooded the land until it covered everything. The people who managed to escape were turned into black swans.

Bur (Teutonic) *see* Buri.

Bura-penu *Bhura* (India)
God of light and mate of Tari-penu, also known as Bhuri, goddess of darkness.

Buraq (Islamic) *see* Mohammed.

Bure (Teutonic) *see* Buri.

Buri *Bori, Bur, Bure* (Norse; Teutonic)
In the beginning, before earth and heaven existed, Buri was created from ice by the cow Audhumla. He had a son named Bor who married Bestla, the daughter of the frost giant Bolthorn. Their children, all males, were Odin, Vili, and Ve. In the war with the frost giants, Buri, along with his sons, succeeded in slaying Ymir and all the frost giants except for Bergelmir (q.v.). *See also* Audhumla; Bestla; Bor; Ve; Vili; Ymir.

Bursiris (Egypt) *see* Osiris.

Bushongo People — Creation Legend (Africa) *see* Bumba.

Bushyansta (Zoroastrian; Persia)
These yellow demons of lethargy and sloth cause men to oversleep and neglect their spiritual obligations. They are associated with Azhi Dahaka and the female demon of corpses, Nasu (q.v.). The Bushyasta are depicted with long hands.

Buso (Malay)
The Buso live in the branches of graveyard trees and feast upon the flesh of the dead. Forests and rocks are their favorite haunts. They have curly hair, two long pointed teeth, one eye which can be red or yellow, a flat nose and long bodies.

Buta (India) *see* Bhutas.

Butes (A) (Greek)
When Butes, the Argonaut son of Poseidon or Teleon and Zeuxippe, was sailing from Colchis, he jumped overboard to swim to the Sirens. Aphrodite, the goddess of love and beauty, rescued him. *See also* Argonauts; Poseidon; Sirens.

Butes (B) (Greek) He is the son of Boreas (q.v.).

Butes (C) (Greek)
Pandion and Zeuxippe are his parents. His twin brother is Erechtheus and other siblings are Philomela and Procne. His spouse is Cthonia, the daughter of Erechtheus and Praxithea (Butes is Cthonia's father's twin). They became the parents of Erechtheus II (also known as Erichthonius). *See also* Zetes (for Erechtheus).

Buto (A) *Bouto* (Egypt)
Also known as: *Edjo, Gozu Tenno* (Japan), *Inadjet, Uadjit, Uajet, Uatchet, Uatchura, Uazai.*

www.ebook3000.com

Chapter I

Cosmic Healing

Cosmic Healing Chi Kung in the Universal Tao System

Cosmic Healing Chi Kung is an important branch of the Universal Tao, an entire system of Taoist practices for cultivating the body, the Chi and the spirit. Your level of skill in Cosmic Healing Chi Kung will be based upon your mastery of the Universal Tao System as a whole. One of the most important parts of the Taoist practices is working with the energy moving within the body.

Foundation of the Universal Tao System is the Microcosmic Orbit Meditation

This is the major practice to connect with the earth, cosmic and universal forces. This is the way to make a connection with the North Star and the Big Dipper's violet/red light which is one of the very powerful universal healing lights. Through this practice you learn to feel Chi and to use your mind/eye/heart power to guide the Chi flow through the primary energy routes in your body. This practice is later extended to include the arm and leg routes too; it is then called the Macrocosmic Orbit.

Many people, including Chi Kung Masters, come to me and say that they have been practicing Chi Kung for years and nothing is happening. They don't feel any energy and they think that they must be performing their Chi Kung incorrectly. I tell them that they also need to do meditation. Hand movements are nothing by themselves. There are hundreds of different Chi Kung forms in China. You could spend seventy lifetimes just learning the hand movements. The practice of the Microcosmic Orbit meditation will help you to feel the Chi more easily inside, outside or around the body and in the extremities of the hands and feet.

When I was a child I liked to practice Chi Kung so much I had to save my lunch money to learn. After many years of practice of many Chi Kung forms, I started to forget the first form, so I learned it again. One day when I tried to practice and review all the forms that I had learned, I couldn't remember many of them. I sat down and thought, "I only have two hands, two legs and one head. Why are there so many forms? And why are there are so many religions and beliefs." I said to myself that there must be one main thing that they have in common. I started to search and I found out that the most important thing is feeling the Chi within us. Being able to increase, transform, take in and stay in touch with the universal, the cosmic, nature and the earth force. Letting

Protector goddess. Mother of the sun and moon. Buto is the Greek name of the goddess who protects Lower Egypt or as some say, a Greek transcription of the name of the town, Per Uadjit, where she was worshiped. Buto is also the name of the swamp where Isis hid the coffin containing the body of Osiris. Buto is a snake goddess often represented in the form of a cobra. She is often depicted with a red crown on her head. She was sometimes shown as a snake, often a cobra, or as a woman with her head topped by a vulture and crown. She is shown both with and without wings. Buto is sometimes shown beside the vulture-goddess Nekhebet. In this depiction, she is called Nebti (meaning two mistresses). Buto is identified with the goddesses Bast and Sekhmet when she is shown in cat or lion form. She is the equivalent to Leto and Latona. *See also* Gozu Tenno; Latona (mother of Apollo); Leto; Uatchet.

Buto (B) (Japan)
Also known as: *Gozu Tenno, Susanowo.*

As Buto crossed the earth in search of a spouse, he stopped in southern India and asked the wealthy King Kotan-Shorai for food and shelter. The king refused him entry. Buto carried on with his journey and went to a palace under the sea where he found his bride-to-be. On his return trip, he stopped in on the inhospitable Kotan, chopped his body into five pieces, and massacred his people. Kotan's poor brother Somin-Shorai, known as the god of hospitality, welcomed Buto. In exchange, for thanks and to discharge his indebtedness, Buto gave him a talisman to protect him from disease. Buto is an aspect of Gozu Tenno, the protector against plagues, and is thought to be of foreign import. Buto is also said to be an aspect of the storm god, Susanowo. The above myth pertaining to Buto is comparable to a myth about Susanowo. Buto is depicted as ox-headed. Regarding the importance of hospitality, *see* Susanowo. *See also* Fuji; Gozu Tenno.

Butterfly Maiden (Hopi People, North America)
A kachina who rules springtime.

Buxenus (Celtic) Box-tree god. *See also* Abellio.

Byamee (Australia) *see* Baiame.

Byampsa (Tibet) *see* Maitreya; Mi-Lo Fu.

Byanu (Egypt) *see* Benu.

Byas River (India) *see* Vasistha.

Byelobog *Bielbog* (Slavic)
Also known as: *Bylun.*

God of light. Both names mean "White God." In Slavic mythology, Byelobog has an evil counterpart called Chernobog or "black god." Some say Byelobog only shows himself during daylight hours, and is a benevolent god of travelers who lose their way. He is shown as an old man with a white beard dressed in white robes. *See also* Chernobog.

Byelun (Slavic) *see* Byelobog.

Byleipt (Teutonic) *see* Loki.

Byleipter (Teutonic) *see* Loki.

Byleist (Teutonic) *see* Loki.

Bylun (Slavic) *see* Byelobog.

Byul-Soon (Korea)
Star goddess.

C

Cabaguil (Maya People, Yucatan)
One of seven creator gods. Called "Heart of the Sky."

Cabeiri (Greek) *see* Caberi.

Caberi *Cabeiri, Cabiri, Kabeiroi, Kabirs* (Greek)
Also known as: *Cyclopes, Qabirim* (Phoenicia).

Known in various parts of the ancient world, the Caberi of Samothrace are the children of Zeus and Calliope. Some say they are the children of Uranus. They could be the sons of Hephaestus as they were his helpers at the forge. Others call them descendants of Sydycos (Sydyk) and brothers of Esmun. The Caberi are variously known as spirits of the underground or of fire. They have also been called fertility spirits. They are associated with the tale of the Argonauts and with Demeter and Kore. They are similar to the Dactyls and similar to if not the same as the Cyclopes. The Caberi are identified with the Curetes, Dioscuri, the Corybantes, and sometimes with Persephone, Rhea and Hecate. There are similarities to Kubera of the Hindu and the Roman Penates. *See also* Ceres; Corybantes; Cyclopes; Dacytls; Demeter; Dioscuri; Ignis; Telchines.

Cabrakan (Maya People, Yucatan) *see* Hunahpu.

Caca (A) (Roman)
Also known as: *Vesta.*

Goddess of Excrements. Caca is associated with Cloacina, the Roman goddess who oversees sewers. It is possible that Caca's father is Vulcan, the god of metal-working. In later times, Caca was succeeded by Vesta, the goddess of the hearth. *See also* Cloacina; Medusa; Vesta; Vulcan.

Caca (B) *Cacia* (Greek)
She is the sister of the Italian cattle thief, Cascus. When she learned that he had rustled cattle belonging to Heracles, she told Heracles where to find his animals. Heracles killed Cascus and rewarded Caca with divine honors. A perpetual flame was kept in her sanctuary. *See also* Cacus.

Cacce-Olmai (Lapp)
This fish god is associated with water and fishermen. He can be destructive if not given the proper sacrifice.

Cacia (Greek) *see* Caca (B).

Caculha Huracan (Central, South America) *see* Huracan.

Cacus *Kakos* (Greek)
Also known as: *Coeculus.* (Originally, he was probably an ancient Roman god.)

A three-headed, fire-breathing giant. His residence was in a cave on Mount Palatine in Rome. He stole the cattle of Geryon and dragged them by their tails to his cave so their footprints could not be traced. It was one of Heracles' labors to retrieve the cattle. One of his twelve secondary labors was to kill the cattle thief. Heracles found the cattle, (thanks to Cacus' displeased sister, Caca) and killed Cacus. *See also* Caca (B); Heracles; Medusa.

Cadmus (Greek)
The son of King Agenor and either Telephassa or Argiope, Cadmus became the King of Thebes. His siblings are Cilix, Electra, Demodoce, Phineus, Thasus, Europa, Phoenix, and possibly Argos. The gods attended his wedding to Harmonia, the daughter of Aphrodite. He became the father of Agave, Autonoe, Illyrius, Ino, Polydorus and Semele. Sometimes his children are said to be Actaeon, Ino, Pentheus and Semele. When his sister, Europa, was raped by Zeus, King Agenor sent Cadmus to try to find her. He was advised by Apollo's oracle to follow a cow that he would come upon. When the cow stopped, Cadmus was to found a city and call it Thebes. While in the area he decided to share drinks with the gods. The fierce dragon of Ares turned up in the water well. Cadmus drew his sword and slaughtered it. He took the monster's teeth and buried half of them. From the teeth armed dragon-men issued forth from the ground and fought with Cadmus and his men. Eventually they reached a calm and the dragon-men helped him build Thebes. Four of his children died violently, and it was thought to be tied in with Cadmus' slaying of the dragon. Later, he and Harmonia moved to Illyria where they were changed into beautiful snakes. Cadmus introduced the alphabet and writing into Greece. *See* Actaeon; Agenor (A); Harmonia (A); Ino; Semele.

Caecinus (Greek)
He is the river god son of Oceanus and Tethys and possibly the father of Euthymus, the Olympic boxer. *See also* Oceanus; Rivers.

Caelestis (Greek) *see* Tanit.

Caelus (Greek) *see* Uranus.

Caeneus (A) (Greek)
Also known as: *Caenis.*

Caeneus was born a female and named Caenis. She is the daughter of the Arcadian Lapith chieftain, Elatus, and Hippea, the daughter of Antiphus. Caeneus' siblings are of Ischys and Polyphemus. As Caenis, she changed her sex after being raped by the sea god Poseidon. Caeneus participated in a fracas between the Lapiths and the Centaurs at the wedding party for Perithous and Hippodameia and was changed into a bird by Zeus. *See also* Polyphemus; Poseidon.

Caeneus (B) (Greek)
He is the Argonaut father of two Argonaut sons, Phocus and Priasus.

Caenis (Greek)
The name taken by Caeneus when she changed her sex to male. *See also* Caeneus.

Caer Ibormeith (Celtic, Irish) *see* Angus.

Caer Yewberry (Celtic, Irish) *see* Angus.

Caesar (Roman) *see* Dis Pater; Mercury (B).

Cagn (Bushman, Hottentot People, Africa)
Also known as: *Coti, I Kaggen, Kaang, Kaggen.*

"Praying Mantis." Creator deity. A shape changer and creator god, his home is known only to the antelopes. Cagn rules with his two sons, Cogaz and Gewi. His wife's name is Hyrax, or some say Coti, although in some versions Coti is another name for Cagn. Cagn has daughters but their names are not known. Cagn's power is located in one of his teeth. *See also* Gaunab; Kaang.

Caillagh ny Groamagh (Isle of Man) *see* Cailleach Bheare.

Cailleach Bheare (Celtic, Gaelic)
Also known as: *Bherri* (Northern Ireland), *Black Annis* (Britain), *Boi, Bui, Cailleach Bherri, Cailleach Bheur, Cailleach ny Groamagh* (Isle of Man), *Cally Berry* (Northern Island), *Caolainn, Hag of Beare* (Ireland).

"Mountain Mother." Cailleach Bheare is known as the controller of the weather of winter months, a mover of islands and a builder of mountains. She is also known as queen of the Limerick fairies. She is the epitome of longevity and repeatedly passes from youth to old age. During these cycles, Cailleach Bheare has many husbands and numerous children. Her children, grandchildren, and great-grandchildren became people and races. She resides in the old southwest Munster, thought to be the home of the dead. Under the name of Boi she is the wife of the god, Lugh. As Caolainn, she is the ruler of a healing well in County Roscommon in Ireland. Cailleach has red teeth and one eye in the middle of her blue-black face. Her hair is matted and she wears a kerchief. Over her gray clothing she wears a faded plaid shawl. *See also* Cailleach Bheur; Cally Berry; Lugh.

Cailleach Bheur *Cailleach Bheare* (Irish, Scottish)
Also known as: *Cailleach Mor, Carlin.*

Winter season. Cailleach Bheur, a ferocious mother goddess known as a hag, is reborn every October 31. She is responsible for the falling of snow. During February, her power is dissipated by the appearance of Brigantia (also known as Brigit) in her aspect as springtime. With the approach of warmer weather, Cailleach Bheur places her staff under a holly bush and turns to stone. Her son is a god of youth (possibly an aspect of Mabon

www.ebook3000.com

and Angus mac Og), whom she pursues battles with constantly. In other myths, she has more than one son; all giants, but none as powerful as she. *See also* Adder; Angus; Black Annis; Brigantia.

Cailleach Mor (Scottish) *see* Cailleach Bheur.

Cain *Kain* (Gnostic, Semite, Muslim)
Also known as: *Kabil* (Arabic).

Deity of soil or agriculture. Eldest son of Adam. Murderer of his brother, Abel. Father of Enoch, Irad, Mehiyya-El, Methusha-El, Lamech, Jabal, Jubil and Tubal-Cain (Tubal-Kain). The last three were said to be deities. The Koran names them Kabil (Cain) and Habil (Abel). Cain founded the city of Un-ug. *See also* Abel; Banbha; Itzamna.

Caipre (Celtic) *see* Etan.

Cairbe (Irish) *see* Bress.

Cairima *Salm* (Persian) *see* Thrita.

Caitya (Buddhist) *see* Stupa.

Cajolom (Maya People, Yucatan) *see* Hunahpu; Qaholom.

Cakra-Samvara (India) *see* Dorje Phagmo.

Caksusi (India) *see* Apsarases.

Calais (Greek)
An Argonaut. One of the Boreades. Calais is the son of the wind god Boreas and Oreithyia. He is the twin of Zetes. His other siblings are Chione, Cleopatra and Haemus. Calais and Zetes accompanied the Argonauts. When they rescued Phineus from the Harpies they were given wings. Heracles killed the twins and they were turned into birds or winds. *See also* Argonauts; Boreas; Harpies; Phineus; Zetes.

Calakomanas (Hopi, Zuni People, North America)
Corn or maize goddesses.

Calchas (Greek)
Soothsayer. Calchas, the son of Thestor and Megara and advisor to Apollo, was the most famous seer of the Greeks of his period. His siblings are Alcmaon, Leucippe and Theonoe (also known as Eidothea). He is the father of Cressida and Briseis (although some legends indicate that her father was Brises of Lyrnessus). Calchas' prophecies about the Trojan War were accurate as was his warning that the Greeks would lose the battle without the assistance of Achilles. He advised the Greeks to build the Trojan Horse. He also advised Agamemnon to sacrifice Iphigenia so the proper winds could guide his fleet to Troy. A vain man, he was certain that he was the most powerful seer and the he could not be outdone in his field. He accepted a guessing game challenge by Mopus and when he failed to ascertain the correct number of figs on a tree, he strangled on his own vanity or died of envy. *See also* Achilles; Agamemnon; Briseis; Iphigenia; Phineus.

Cale (Greek) *see* Charities.

Callalamma (India)
She is one of the Mutyalammo goddesses who are deities of the household. Her function is to preside over the buttermilk. *See also* Mutyalammo.

Calli (Aztec People, Mexico)
One of the four year-bearers or year gods. Calli is in charge of the west region. He is god of those mortals who live in that space and time. *See also* Acatl; Tecpatl; Tochtli.

Calliope *Kalliope* (Greek)
Muse of epic poetry. Talented musician on any instrument. One of the nine Muses. Calliope is the daughter of Zeus and Mnemosyne. She is said to be the mother of the Corybantes (lovers of music and wild dancing) by Zeus; of Hymen, the composer and god of marriage; Ialemus, also a composer; and Linus, composer of songs, by Apollo; of Rhesus, the Thracian prince, by the Strymon River; of the Sirens, all of whom had beautiful voices, by the river god Achelous; and of Orpheus, the most famous of poets by Oeagrus. Calliope taught her friend Achilles how to sing among friends at banquets. Zeus asked her to mediate the disagreement between Aphrodite and Persephone over Adonis. *See also* Adonis; Aphrodite; Corybantes; Muses; Persephone; Sirens; Zeus.

Callirius (Gallo-Roman) *see* Silvanus.

Callirrhoe (A) (Greek)
She is the Oceanid daughter of Oceanus and Tethyus. Her spouse was Chrysaor. She could be the mother of Cerberus; Echidna and Geryon. With Manes, she had a son, Cotys. *See also* Ceto; Chrysaor; Oceanids; Tethyus.

Callirrhoe (B) (Greek)
The river god, Scamander, is her father. Her spouse is Tros and her children are Assaracus, Cleopatra, Ilus and Ganymede. A fountain in Attica is named for her on the spot that she committed suicide.

Callirrhoe (C) (Greek)
She is the daughter of Amphione and Niobe. Callirrhoe and four of her sisters were killed by the warrior goddess, Artemis. Apollo killed five of her six brothers. *See also* Apollo; Artemis; Niobe.

Callirrhoe (D) (Greek)
Lycus of Libya is her father. When her lover, Diomedes, deserted her, she committed suicide. *See also* Diomedes.

Callirrhoe (E) (Greek)
Achelous, the river god, is her father. Her siblings are Castalia, Peirene and possibly the Sirens. She became the second wife of Alcmeon and the mother of Acarnan and Amphoterus. *See also* Achelous.

Callisto *Kalisto* (Arcadian, Pre-Hellenic, Greek)
Also known as: *Calliste, Kalliste.*

Originally Callisto was a Pre-Hellenic goddess. When Arcadia was invaded by the Greeks, she was reduced to the status of a nymph. Her attributes were given to the Greek goddess Artemis. As a nymph, she is the daughter of Lycaon, Nycteus, Ceteus, or Zeus. She is the sister of Pallas. Earlier, she was the nymph companion of Artemis. An affair with Zeus caused her death by the hands of Artemis, but she gave birth to a son named Arcas (ancestor of the Arcadians). She is depicted in animal form as a mother bear. In human form, she is shown as a young athlete racing through the woods. There is a tale wherein Artemis accidentally killed Callisto and was so upset that she took her name and her symbols and called herself Artemis Calliste. She is sometimes confused with Artemis because her symbol is also a she-bear. *See also* Artemis; Zeus.

Cally Berry (Irish)
She is known as the "water hag" or the "old gloomy woman," who protects lakes from being drained and controls the weather. She is generally thought to be the same as Cailleach Bheare.

Calyce (Greek) *see* Aeolus (A); Canace.

Calydon (A) (Greek) He is the son of Thestius.

Calydon (B) (Greek)
His parents are Ares and Astynome. Artemis, the goddess of hunting, caught him peeking at her while she was bathing. She turned him to stone. *See also* Ares; Artemis; Astynome.

Calydon (C) (Greek)
He is the son of Aetolus, the king of Elis, and Pronoe, who is the daughter of Phorbus.

Calydonian Boar Hunt (Greek)
The boar represents the sun causing drought. Oeneus was the king of Calydon, husband of his niece Althaea and later Periboea. He was the father of Deianira who killed Heracles and then committed suicide, Gorge who was possibly changed into a guinea fowl by Artemis, Toxeus who was killed by Oeneus, Olenias, Perimede, Tydeus one of the Seven against Thebes, Laocoon (by a servant woman) and possibly Meleager an Argonaut. His parents are Porthaon, the first king of Calydon, and Euryte, the daughter of Hippodamas. His siblings are Alcathous who was slain either by his nephew Tydeus or Oenomaus the king of Pisa, Agrius who expelled Oeneus from the throne and eventually committed suicide, Melas the friend of Heracles, Sterope who was possibly the mother of the Sirens by Achelous and Leucopeus. When he neglected to make the expected annual sacrifices to the goddess Artemis, she sent a monstrous boar to his area to deplete the crops and ravish the land and its people. Oeneus sent word to other Greek cities for assistance with the offer of the boar's skin as a trophy to the victor. A marvelous assortment of warriors and heroes, including their hostile neighbors the Curetes, arrived to conquer the beast. Apparently the only female to join the hunt was the skilled Atalanta with whom Meleager fell in love. Meleager, the son of either Oeneus or Poseidon, felled the vicious boar and was awarded the skin which he gave to Atalanta. This caused dissension and resulted in a war between the Calydons and the Curetes. Artemis transformed Meleager into a guinea fowl after his death and Althaea's guilt for her role in his demise caused her suicide. Oeneus, the hospitable host of deities and celebrities, who introduced the art of wine making to his constituents, was said to have died in Argos at an advanced age. For details of the battle between the Calydonians and the Curetes *see* Althaea. *See also* Artemis; Jason.

Calypso *Kalypso, Kalupso* (Greek)
Immortal nymph. Death goddess. Calypso is either the daughter of Atlas and Tethys, Atlas and Pleione or of Oceanus and Tethys. She is said to be the sister of Hyas, the Hyades, the Hesperides, Maia and the Pleiades. The shipwrecked Odysseus was offered safe harbor and her love when he was washed ashore on her island Ortygia (also spelled Ogygia, Ogugia) in the Ionian Sea. They have two children, Nausinous and Nausithous. After seven years together Odysseus was homesick and longed for his wife and family. Calypso tempted him with the offer of eternal youth and immortality if he would remain with her, but Zeus sent Hermes with a message instructing her to let him go. In some versions of this myth, Calypso and Odysseus are said to be the parents of Telemachus and Telegonus. More often, Odysseus and Penelope are the parents of Telemachus and Odysseus and Circe are the parents of Telegonus. Calypso's name means "to hide." Calypso is shown in a cavern surrounded with alder (a shrub or tree that grows in cool moist places), which was sacred to the deity of death, Cronus. In the branches sit Cronus' sea-crows and Calypso's horned owls and falcons. To compare to other nymphs *see* Naiads. *See also* Hesperides; Oceanids; Oceanus; Odysseus; Scylla; Zeus.

Cama (India) *see* Kama.

Camalotz (Maya People, Yucatan People, Yucatan)
Demon. After the gods created mankind from various materials they decided to destroy them in a flood. Camalotz helped by cutting off the heads, while Xecotcovach ate their eyes, Cotzbalam devoured their flesh and Tucumbalam ground their bones and sinews. *See also* Alom; Cotzbalam; Tzakol; Xecotcovach.

Camaxte (Aztec People, Mexico; Mexico) *see* Texcatlipoca.

Camaxtle (Aztec People, Mexico; Mexico) *see* Xipe Totec.

Camaxtli (Aztec People, Mexico; Chichimees, Tlascalan People, Mexico)
Also known as: *Tezcatlipoca, Xipe Totec; Yoamaxtli.*
Creator deity. Son of Ometecuhtli (Tonacatecuhth) and Omecihuatl (Tonacacihuatl). Brother of Tezcatlipoca, red, blue, white and black; Quetzalcoatl, and Huitzilopochtli. One of the gods who were instructed by their parents to create the world. He was said to be a God of vegetation, God of thunderstorms and War God, sometimes associated with tornadoes and hunting. Some believe that Camaxtli is identical or similar to the deities of various early races: Curicaveri of the Tarascan, Mixcoatl of the Chichimec, Otontectli, and Xocotl of the Tepanec and Otomi people, and Huitzilopochtli of the Aztec People, Mexico. *See also* Coxcoxtli; Huitzilopochtli; Legend of the Four Suns; Mixcoatl; Tezcatlipoca; Yoamaxtli.

Camazotz (Maya People, Yucatan People; Yucatan)
Bat god of Xibalba. Hun Hunahpu and his twin brother Vukub Hunahpu were sacrificed by the people of the hellish underworld, Xibalba. The blood-thirsty bat god, Camazotz, used his claws to cut off Hun Hunahpu's head. The head was placed in a barren tree, likely to ward off ill-wishers. Hunahpu regained his life, but Camazotz was defeated. *See also* Hunahpu; Ixbalanque; Xibalba.

Camdhen (India) *see* Kamadhenu.

Camenae *Camena, Carmenai* (Roman)
Also known as: *Carmentes, Casmenae.*
They are fountain nymphs, spirits of springs and rivers and goddesses of prophecy in Roman mythology. Their leader is Carmenta. The most famous of the Camenae is Egeria. They

www.ebook3000.com

are worshiped in the same month as the Fons. On October 13, their festival day, known as Fontinalia, wreaths are thrown into wells for good luck. They are identified with the Greek Muses. *See also* Egeria; Fons; Muses.

Cameiro (Greek) Another name for Cleothera (q.v.).

Campe (Greek)
A monster female dragon who guarded the Hecatoncheires and Cyclopes in the underworld prison of Tartarus until Zeus released them. *See also* Cyclopes; Erebus; Hades; Hecatoncheires; Tartartus.

Camulos (Celtic) *see* Camulus.

Camulus *Camulos* (Celtic)
Also known as: *Cumhal* (Gaelic), *Coel, Cole* (British), *Cocidius* (British).
Ancient war god. As Cumhal, he is the father of Finn. Camulus equates with Mars. *See also* Albiorix; Cocidius; Tuetates.

Camunda (India) *see* Kali.

Canace (Greek)
She is the daughter of Aeolus of Magnesia and Enaret. She has seven brothers and six sisters. Her brothers are Athamas, Cretheus, Deion, Macareus, Perieres, Salmoneus, Sisyphus, and six sisters: Alcyone, Arne, Calyce, Peisidice, Perimele and Tanagra. By Poseidon she became the mother of Aloeus, Epopeus, Hopleus, Nireus and Triopas. When her father found out that she was having sex with her brother Macareus, he demanded that she commit suicide. *See also* Aeolus (A); Aloeides; Aloeus; Arne; Epopeus.

Canache (Greek) *see* Aeolus (A).

Canapa (Peru) *see* Coniraya.

Canda (India) A Demon. *See also* Durga; Kali.

Candelifera (Roman)
Goddess of childbirths.

Candi (India) *see* Kali.

Candra (India) *see* Chandra.

Candramas (India) *see* Chandra.

Candulus (Greek) *see* Heliades.

Canola (Irish)
This goddess invented the Irish harp.

Canopic Vases (Egypt) *see* Amset; Horus.

Canopus (India) The South Star. *See also* Agastya.

Canthus (Greek) *see* Argonauts.

Cantul-Ti-Ku (Maya People, Yucatan People, Yucatan) *see* Ahmucen-Cab; Becabs.

Caoineag *Caointeach* (Scottish)
Another name for the Banshee.

Capaneus (Greek)
He is the son of Hipponous and Astynome. His marriage to Evadne produced Sthenelus, who is one of the Epigoni. Capaneus, the inventor of the scaling ladder and one of the "Seven against Thebes," was killed when Zeus hurled a thunderbolt at him for bragging that he could not be stopped from entering Thebes. There is a possiblity that Capaneus was brought back to life by the great physician, Asclepius (q.v.). *See also* Adrestus; Astynome; Hipponous.

Caphaurus (Greek)
Also known as: *Cephalion.*
He is the shepherd son of Ampithemis and Tritonis and brother of Nasamon. When the Argonauts Canthus and Eribotes attempted to steal his sheep, he killed them. Subsequently, he was killed by other Argonauts.
See also Acacallis; Argonauts.

Capheira (Greek) *see* Telchines.

Capra (Greek) *see* Aegipan.

Caprakan (Maya People, Yucatan People, Yucatan)
An evil spirit of mountains and earthquakes. Destroyer of mountains. He was put to death by the hero twins Hunahpu and Ixbalanque. Caprakan is the son of the giant Gukup Kakix and Chimalmat, and brother of Zipacna. *See also* Hunahpu and Ixbalanque.

Capricorn (Greek) *see* Aegipan; Amaltheia.

Capys (Greek) *see* Anchises.

Car (Greek)
Also known as: *Carius, Carys, Great God Ker, Karu, Karus, Q're.*
First king of Megara. Solar King. He is the son of Phoroneus and Cerdo, Peitho or Teledice. His siblings are Niobe and Teledice. Car founded Megara, the principal city of Megaris, on the Isthmus of Corinth and established the worship of Demeter. His hair was shaved off annually before his death. At the annual feast of Comyria (hair trimming), young men mourned him and had their hair shorn. These men were later known as Curetes. The name Car may have derived from Artemis the moon goddess, Caria or Caryatis. *See also* Apis (B); Curetes; Niobe (B); Phoroneus; Satyrs.

Caragabi (Choco People, Colombia, South America)
Caragabi was born from the saliva of the high god Tatzitzebe. He is the creator of humans and animals (who were made from some humans), the sun, moon, and stars, and he filled the tree which holds the spirit of life. He taught the people to gather food plants. Tutruica, his rival, is always trying to reverse Caragabi's work. After the world has been destroyed by fire, Caragabi will return.

Cardea (Roman)
Goddess of thresholds and door pivots. Hunter. Cardea had to devise numerous ways to protect her virginity. Her love was Janus, the god of beginnings and endings, who is also a god of doors. Cardea transferred her powers to Janus. *See also* Janus.

Caria (Greek) *see* Car.

Carian Pirates (Greek) *see* Bellerphon.

Cariclo (Greek) *see* Cheiron; Oceanus.

Caridad (Africa) *see* Ochun.

Caridwen (Celtic) Corn goddess. Patroness of poetry.

Carius (Greek) *see* Car.

Carlin (Scottish)

Spirit of Hallowmas, the eve of winter. On this night, ghosts of the dead appear on earth. To protect farmers from their visitations, ears of corn made in Carlin's likeness are put on display. *See also* Cailleach Bheur.

Carmenai (Roman) *see* Camenae.

Carmenta (Greek) *see* Carmentis.

Carmentes (Roman) *see* Camenae.

Carmentis *Carmenta* (Roman)

Also known as: *Nicostrata, Postverta.*

Birth Goddess. Goddess of Healing. Goddess of the Future. She is one of the Camenae (prophetic nymphs linked with the Muses). Carmentis, a fountain nymph, is possibly the mother and Hermes the father of Evander (he introduced the Greek alphabet, the flute, lyre and triangular harp into Italy). There are writers who say that Carmentis adapted the Greek alphabet to the Latin language. *See also* Evander (B); Postverta.

Carna (Roman) Goddess of the heart and other body organs. Goddess of over-hinges. *See also* Cardea.

Carpo (Greek)

"Autumn." Goddess of autumn season. Carpo, one of the Horae, is the daughter of Zeus and Themis, who is the Titan daughter of Uranus and Gaea. Carpo is worshipped with Thallo, who is the personification of spring. *See also* Horae; Thallo.

Carpus (Greek) *see* Chloris; Zephyrus.

Caryatids (Greek) *see* Artemis.

Caryatis (Greek) *see* Artemis; Car.

Carys (Greek) *see* Car.

Casmenae (Roman) *see* Camenae.

Cassandra *Kasandra* (Greek)

Also known as: *Alexandra.*

Goddess of prophecy. Cassandra is the daughter of the king of Troy, Priam, and the moon goddess Hecuba. She came from a large family of eleven sisters and fifty brothers. Some of her siblings were her twin Helenus, who was her only brother to survive the Trojan War; Paris, who was abandoned at birth; Polyxena, who was sacrificed; Hector, the brave leader of the Trojans who was killed by Achilles; Deiphobus, also a brave warrior, who was forced to marry Helen; and Creusa, who was captured by the Greeks, rescued, and then disappeared. Cassandra had twin sons, Teledamas and Pelops, by her master Agamemnon. Cassandra promised to marry Apollo if he conferred the gift of prophecy upon her. When he fulfilled her wish she reneged and refused to marry him. Incensed, he rendered her gift worthless by making everyone who heard her prophecies disbelieve her. She fled to Athena's sanctuary after the fall of Troy, was raped by Ajax the Lesser and awarded as a prize to Agamemnon. He ensconced her in his chariot and took her to his home in Mycenae. Like everyone else he ignored her accurate visions of doom. Cassandra, Agamemnon and their infant twins were murdered by his wife Clytemnestra and her lover Aegisthus. A shrine near Amyclae was erected in Cassandra's honor under the name of Alexandra. *See also* Aegisthus; Agamemnon, Ajax the Lesser; Apollo; Athena; Clytemnestra; Creusa; Hector; Hecuba; Paris; Pelops; Teledamas.

Cassiepeia (Greek) *see* Cassiopeia.

Cassiopea (Greek) *see* Cassiopeia.

Cassiopeia *Cassiepeia, Cassiopea, Kessiepeia* (Greek)

Night goddess. She is the daughter of Arabus who is the son of Hermes. She married Cepheus, the king of Ethiopia and became the mother of Andromeda. She is also the mother of Atymnius, by Zeus. (Atymnius was the possible lover of Minos.) Poseidon sent a flood to the country because of the displeasure of the Nereids caused by Cassiopeia's constant and irritating bragging about her daughter. Andromeda was offered as a sacrifice but was saved by Perseus. *See also* Andromeda; Hermes; Perseus.

Cassotis (Greek) *see* Naiads.

Castalia (Greek) *see* Naiads.

Castalius (Greek) *see* Cephissus.

Castor and Pollux *Castor and Pollus, Kastor and Polydeukes* (Greek)

Also known as: *Dioscures, Dioscuri, Polydeuces* (the name also used by the Greeks for Pollux).

Assistants to men and women in battle. Gods of weights and measures. Gods of commerce. Assistants to people traveling. Protectors of sailors. Zeus came to Leda in the form of a swan. They engaged in sex and she delivered two eggs. Each egg contained a brother and sister (Castor and Clytemnestra, Pollux and Helen). (In the Homeric version, Castor and Pollux are the sons of Leda and king Tydracus.) The brothers are commonly known as the Dioscuri. Castor became a famous horse trainer and Pollux became a well known boxer. When their sister Helen (the wife of Menelaus) was abducted by Theseus, the brothers were able to rescue her in Aphidnae. While they were there, they overtook the city. The brothers were also involved in the Argonauts expedition, and in the Calydonian Boar Hunt. They became involved in an episode with Lynceas and Idas (the sons of Alphaeus) where they stole a herd of oxen from Arcadia. Idas steered the oxen to his home in Messene. The displeased brothers ransacked the city and retrieved the oxen. From this incident a feud developed between Lynceas and Idas and Castor and Pollux. Castor was killed. The death of his dear brother sent the grieving Polydeuces begging to Zeus for his own death. Zeus told Polydeuces that he could make a choice of staying on Olympus with the gods for the rest of time, or he could share the fate of Castor and stay one day on earth and one day on Olympus for the rest of time. He chose the fate of his brother. After their deaths they became the constellation Gemini. Castor and Pollux were extremely popular in Greece and in Rome. *See also* Academus; Argonauts; Calydonian Boar Hunt; Curetes; Helen; Leda.

Castor and Polydeuces (Greek) *see* Jason.

www.ebook3000.com

Caswallwan (Celtic)
Son of Bile (q.v.).

Cataclothes (Greek) *see* Harpies.

Catamitus (Roman) The Roman name for the Greek Ganymede (q.v.).

Catequil (Inca People, Peru)
God of lightning and thunder. God of twins (possibly). In early times, he was propitiated by the sacrifice of children. He is one of the attendants of Mama Quilla (q.v.). Catequil is associated with Cuycha, the rainbow.

Catha (Etruscan)
Sun deity.

Cathena (Mojave People, North America)
Also known as: *Quakuinahaba.*
First woman. Virgin sister of Ku-yu.

Catreus (Greek) *see* Acacallis; Ariadne; Minos; Pasiphae.

Caucasian Eagle (Greek)
His parents are Typhon, the destructive one hundred–headed whirlwind, and the monster, half-woman half-snake, Echidna. For a list of his monster siblings, *see* Echidna. *See also* Chimaera; Typhon.

Cauldon of Dagda (Celtic) *see* Dagda.

Caurus (Greek) *see* Harpies; Zephyrus.

Cauth Bodva (Celtic)
"War Fury." This is a name for the goddess of war, Badb Catha.

Cave of Refuge (Inca People, Peru) *see* Pacari.

Cavern of the Seven Chambers (Aztec People, Mexico) *see* Chicomoztoc.

Cavillaca (Inca People, Peru) *see* Coniraya; Pacha-Camak.

Ce Acatl (Mexico) *see* Quetzalcoatl.

Ceacht (Celtic, Irish)
Goddess of medicine. *See also* Dagda; Dia'necht.

Cearas (Celtic, Irish)
God of fire. An aspect of Dagda (q.v.).

Ceasar (Irish) *see* Cessair.

Cebrew (Greek) *see* Rivers.

Cecrops (Greek) *see* Agraulos; Gaea.

Cedalion (Greek)
Cedalion is a dwarf, possibly the son or father of the fire god Hephaistos. The goddess Hera assigned Cedalion the job of teaching Hephaistos the art of metal working. When the giant hunter Orion was blinded, he hoisted Cedalion to his shoulders and the dwarf led Orion to the sun where he was healed by Apollo. *See also* Hephaistos; Orion.

Celaeno (A) (Greek) She is the daughter of Poseidon and Ergea.

Celaeno (B) (Greek) One of the Harpies (q.v.)

Celaeno (C) (Greek)
One of the fifty daughters of Danaus, known as the Danaids. *See also* Asteria; Danaids; Danaus; Hypermnestra.

Celaeno (D) One of the Pleiades (q.v).

Celestial Kings (China)
Guardians. These deities replaced the two door guards, Shen-t'u and Yu-lu, who in turn were replaced by the Sniffing and Puffing Generals. The Celestial Kings are similar to the Buddhist divinities, Dhartarastra,Vaisravana, Virudhaka and Virupaksha, who were entrance guards. *See also* Men-shen.

Celestial Mandarin (China) *see* Ch'eng Huang.

Celestial Toad (China)
A title for the moon goddess, Chang-O.

Celeus (King) (Greek)
King of Eleusis. With Eumolpus, the co-founder of Eleusinian Mysteries. Teacher of agriculture. Inventor of agricultural tools. King Celeus married Metaneira. Their children are Demophon, possibly Abas and Triptolemus, and four daughters. *See also* Abas (C); Demophon.

Celmis (Greek)
With Acmon and Damnameneus, Celmis is one of the three original Dactyls (q.v.).

Cenchreis (Greek)
The spouse of Cinyras, she is the mother of Adonis and Myrrha. *See also* Adonis; Cinyras; Myrrha.

Cengus (Celtic) *see* Aengus.

Cenn Cruaich (Celtic)
Known as the "Lord of the Mound," first born children were sacrificed to him. His likeness was produced in gold, surrounded by twelve stones.

Centauras (Greek) *see* Centaurs.

Centauroi (Greek) *see* Centaurs.

Centaurs *Centauras, Centauroi, Kentaurs, Kentauros* (Greek).
Cloud deities. The race of half-man, half-horse, Centaurs live in the mountains of Thessaly. They are the children of Ixion and Nephele, who is cloud-shaped like Hera, the queen of heaven. In some renditions of this myth, Centaurus is named as the Centaurs' father. It is possible that he is the father of some of the Centaurs. Only the centaur Cheiron is the son of Cronus and Philyra, and the centaur Pholus is the son of Selenus and an ash-nymph (possibly Philyra). It is always difficult for the Centaurs to bridle their passions. They are renowned for their abusive treatment of nymphs and human women. The name Centaurs is probably derived from the Turanian word for man-beast. They are described as half-man, half-horse, or the upper torso, arm and head of a man with the body of a horse or ass. Centaurs are similar to the Gandharva. They are associated with Atalanta. Generally, the Centaurs are said to be followers of Dionysus. *See also* Cheiron; Ixion; Nephele; Nessus.

Centeal (Mexico) *see* Cinteotl.

Centeatl (Aztec People, Mexico) *see* Cinteotl.

Centeol (Aztec People, Mexico) *see* Cinteotl.

Centeotl (Aztec People, Mexico) *see* Cinteotl.

Centimanes (Greek) *see* Hecatonchires.

Centimani (Greek)

This is the Roman name for the Hecatonchires (q.v.). *See also* Aegaeon.

Centipede (Egypt)

Also known as: *Sepa.*

Protector against harmful animals and enemies of the gods. Sepa (meaning "centipede") is a minor god mentioned in the Pyramid Texts. As a charm, he is summoned to ward off malevolent animals and enemies of the gods. He is connected with the necropolis and linked with Osiris as a mortuary god. *See also* Osiris.

Centzon Huitznahuas *Centzon Totochtin, Centzonhuitznauac, Centzonuitznaua* (Aztec)

Also known as: *The Four Hundred.*

Evil deities. Star gods of the South. They are the sons of Coatlicue born prior to the birth of her son Huitzilopochtli. When the Centzon Huitznahuas and their sister Coyolxauhqui found out about the impending birth of their brother they became enraged and attempted to murder their mother. Huitzilopochtli sprang from his mother dressed in full battle gear. He killed his siblings using his powerful weapon, a fire serpent named Xiuhcoatl. The Centzon Huitznahuas are also known as the "Four Hundred Southerners." The Four Hundred Northerners are called Centzon Mimixcoa. *See also* Centzon Mimixcoa; Coatlicue; Huitzilopochtli.

Centzon Mimixcoa

Also Known as: *The Four Hundred Northerners.*

(Aztec People, Mexico) Star gods. *See also* Centzon-Huitznahuas.

Centzon Totochtin (Aztec People, Mexico)

Also known as: *Four Hundred Rabbits, Pulque Gods.*

They are the four hundred deified rabbits who are gods of drunkenness and licentiousness, who were thrown into the face of the moon. Some of their names are Texcatzoncatl, Colhuatzincatl, and Ometochtli. They are associated with Xochipilli. *See also* Centzon Huitznahuas; Colhuatzincatl; Ometochtli; Patecatl (discoverer of peyote); Texcatzoncatl.

Centzonuitznaua (Aztec People, Mexico) *see* Centzon Huitznahuas.

Centzonhuitznauac (Aztec People, Mexico) *see* Centzon Huitznahuas.

Ceos *Coeus* (Greek)

God of night. Ceos, a Titan is the son of Gaea and Uranus. He is the father of Asteria by his sister, the original moon goddess Phoebe, and Mnemosyne by Leto, the goddess of the night. Hesiod called him the father of Leto and Asteria by Phoebe. He is also named the father of the witch goddess Hecate in some references. The name Ceos means "intelligence." *See also* Aurora; Cronus; Eos; Eurynome (A); Gaea; Hecate; Leto; Titans; (The) Two Auroras.

Cephalion *Caphaurus* (Greek)

Another name for Caphaurus (q.v.). *See also* Acacallis.

Cephalus (A) (Greek)

His parents are the god Hermes and the dew, personified by Herse, and his brother is Ceryx. He is the possible father of Phaethon by Hemera (Other possiblities for Phaethon's parents are Tithonus and Eos.) *See also* Eos; Hermes.

Cephalus (B) (Greek)

He is the son of the King of Phocis, Deion, and Diomede, the daughter of Xuthus, "the thievish one." His siblings are Actor, Aenetus, Asteropeia and Phylacus. His first wife was Procis, whom he accidentally killed. He was sentenced to the island of Taphos and while there he helped Amphitryon conquer Taphos. At a later time, Clymene became his second wife, and they became the parents of the Argonaut Iphicles. *See also* Actor (A); Diomede; Xuthus.

Cepheus (A) (Greek)

The King of Ethiopia. He married Cassiopeia and became the father of Andromeda (q.v.). *See also* Cassiopeia.

Cepheus (B) (Greek)

King of Tegea. Argonaut. His parents are Aleus and Neara. He is the father of Aerope, Echemus, Sterope, and unnamed others. The kingdom of Tegea could not be destroyed as he held a lock of hair from Medusa's head that had been given to him by the goddess of love, Athena. When he went to sail with the Argonauts, he gave the lock of hair to his daughter, Sterope. *See also* Aerope; Medusa; Sterope.

Cephissus (Greek)

River god. Cephissus is one of the three thousand sons of Oceanus and Tethys, known as the Rivers, and brother to his three thousand sisters, the Oceanids. As a river, the Cephissus flows into the Saronic Gulf near Athens. As a deity, Cephissus and the nymph Leiriope are the parents of the vain Narcissus. Cephissus is thought to be the father of Thyia, although Castalius has also been called her father. Either Cephissus or Andreus is the father of Eteocles, a king of Boeotian Orchomenus, who was the first man to name the three Graces and sacrifice to them. To compare to other river gods, *see* Achelous, Acheron, Alpheus, Asopus, Cocytus, Inachus. *See also* Graces; Narcissus; Oceanids; Oceanus; Rivers; Tethys.

Cer (Greek)

Goddess of violent death. She is the daughter of the underworld darkness, Erebus, and the goddess of the night, Nyx. Her siblings are Aether, the god of light; Charon, ferryman of dead souls; Oneiroi (also known as Dreams); Hypnos (also known as Somnus, the god of sleep); Momus, the god of fault-finding; Moros; Nemesis, the goddess of retribution; Thanatos, the god of death. *See also* Aether; Charon; Erebus; Hypnos; Keres; Nemesis; Nox; Thanatos.

Ceramus (Greek)

He is the son of Dionysus and Ariadne (qq.v).

Cercaphus (Greek)

An intelligent man, known for his interest in astronomy, Cercaphus is one of the Heliades. It was either Cercaphus or

www.ebook3000.com

Macar who were the first to sacrifice to Athena. *See also* Athena; Heliades.

Cerberus *Kerberos* (Greek)
Watchdog of Hades. Cerberus, the offspring of Echidna and Typhon, is a three-headed (or fifty-headed) dog with a voice of bronze who is the watchdog of Hades. Stationed at the gates of death, Cerberus allows people to enter but devours them if they try to leave. Only twice has he been negligent in his duties. Once was when the sweet music of Orpheus put all his heads to sleep. The second time was when Heracles in his quest to accomplish his twelfth labor was to bring Cerberus from the underworld to King Eurystheus. He strangled each of the monster dog's heads and rendered it unconscious. Heracles then carted the animal to the king, who was so petrified at the sight of the beast that he hid and demanded that Heracles return it to the portals of Hades. Heracles merrily accommodated the king and returned Cerberus to his owner, Hades, demanding and receiving a payoff from him. In the Roman version it was Sibyl conducting Aeneas through hell who brought sleep upon Cerberus by feeding him honey-cake seasoned with poppy seeds. *See also* Chimaera; Echidna; Hades; Heracles; Orpheus; Tartarus; Typhon.

Cercopes (Greek)
The Cercopes are gnomes with two tails who are known for thievery. They are the sons of Oceanus and Theia. *See also* Oceanus; Passalus; Theia.

Cercyon (Greek)
King of Eleusis. This king, son of Hephaistos, required all visitors to wrestle with him. In the end, he was killed by Theseus. *See also* Hephaistos; Theseus.

Cerdo (Greek)
"The Wise." She is the wife of Phoroneus and the mother of Car. *See also* Car; Niobe (B); Phoroneus.

Ceres *Kerres* (Greek)
Also known as: *Angerona* (Etruscan), *Cabiria* (a derivative of Babylonian Kabiri or Cabiria), *Demeter* (Greek).

Earth Mother. Agricultural goddess. Goddess of grain and corn. Goddess of fruit and flowers. One of the twelve great Olympians. Chief of the Penates (household deities). Ceres is the daughter of Cronos and Rhea. She became the mother of Arion by Poseidon and Proserpine by Jupiter. It is thought that Ceres replaced the early agriculture goddess Tellus Mater or possibly Kerres. She is shown as a wheat ear. Ceres is associated with Liber and Libera, who were also earth deities. She is the Roman equivalent of the Greek Demeter. The word cereal is derived from her name. *See also* Angerona; Baubo; Cabiri; Demeter; Evander (B).

Ceridwen (British, Celtic) *see* Keridwen.

Cerklicing (Latvia)
God of fields and corn.

Cermait (Celtic) "The Honey-mouthed." *See also* Ogma.

Cernobog (Slavic) *see* Chernobog.

Cernunnos *Cernunnus* (Celtic)
Possibly a god of animals or an underworld deity. Various depictions indicate he might be a god of providence or plenty. Some writers think he might be a fertility deity. Later Christians tended to assimilate him to Satan. Cernunnos is depicted as horned, sitting cross-legged, holding a collar in one hand and a ram-headed serpent in the other hand. He is flanked by animals. Sometimes he is shown with a beard and sometimes with three heads. In some depictions he has the legs of a serpent. He is also depicted as the antlered stag of the Celts. Dances were performed around him near the small temples. He is similar to Shiva in his aspect as Pashupati. Cernunnus resembles the Slavic Chernobog. *See also* Sucellos.

Cerridwen (British, Celtic, Welsh) *see* Keridwen.

Ceryx (Greek)
He is the son of the messenger of the gods, Hermes, and Herse, the personification of dew, and brother of Cephalus. *See also* Agraulos; Hermes; Herse.

Cesair (Irish) *see* Cessair.

Cesar (Irish) *see* Cessair.

Cesara (Irish) *see* Cessair.

Cesarea (Irish) *see* Cessair.

Cessair *Ceasar, Cesar, Cesara, Cesarea, Cesair* (Irish)
Cessair, possibly a moon goddess, is said to be Noah's granddaughter, and the daughter of Bith and Birren. In legend, she was refused entry into the ark and fled with her husband, Fintan (also spelled Finntain), along with Ladru, another man and fifty women to Inisfail, which is now Ireland. Forty days after arriving on the island all except Fintan perished in the Great Flood. Ladru became known as the "first dead man of Erin." Fintan survived as a salmon. Through the centuries he assumed many shapes as he watched Ireland's history develop. He lived to be six hundred years old and he verbally transmitted this history to more recent generations. The next influx of people to the island were Partholon and his followers. *See* Banbha, said to be the first settler in Ireland. *See also* Partholon.

Cethe (Celtic)
He is the brother of Cian and Cu, and the son of Dia'necht (q.v.).

Ceto (Greek)
Sea monster. Ceto is the sea monster daughter of Pontus and Gaea, or Oceanus and Gaea. In one myth, she married her brother, Phorcys, and became the mother of Callirrhoe (also called Echidna), the sea monster Scylla, the Gorgons, the Graiae and the dragon Ladon. In other legends she is said to have been her brother Phorcys' daughter, a result of his union with their mother Gaea. They became the parents of the Gorgons. In yet another version of this myth she was one of the fifty Nereids, the water nymphs, who are children of Nereus and his sister/wife Doris. *See also* Callirrhoe; Doris; Echindan; Gaea; Gorgons; Graiae; Hesperides; Ladon; Medusa; Nereids; Nereus; Oceanus; Pontus; Scylla.

Ceus (Greek) *see* Ceos.

Cexochitl *see* Cinteotl.

Cezalcouati (Mexico) *see* Kukulcan.

Cghene (Isoko People, Southern Nigeria, Africa)
He is the Supreme Being and the creator of all. His abode is in the sky, which is a part of him. He rewards the just and punishes the unjust. The intermediary between Cghene and mortals is known as an *oyise*, also called uko Cghene ("messenger of Cghene"). It is made from the oyise tree, and is about eight feet long. It stands on the grounds of the eldest family member. Each morning he throws his used chewing stick before the pole and prays for the family and village members.

Ch-Ien Niu *Kien Niu (China)*
Heavenly cowherd. Husband of Chih-Nii (q.v.).

Cha-dog-ma (Tibet)
Also known as: *Vajra-Shringhala* (Sanskrit). *See also* Hayagriva; Kinkini-Dhari; Vajra-Shringhala.

Ch'an Tzu-fang (China)
God of the fire or furnace or hearth. *See also* Tsao Chun; Tsao-Shen; Tsao-wang.

Chaac (Maya People, Yucatan) *see* Chac.

Chac *Chaac* (Maya People, Yucatan)
Also known as: *"B"* (possibly), *Xib Chac.*

Rain god. Patron of agriculture. Chac is analogous to the Aztec god Tlaloc. The Mayas sacrificed to Chac for rain. Elsewhere he is referred to as one of a triad with Hobnel and Ah-Kluic, who are both gods of plenty. During festivals, human sacrifices, particularly children, were offered to the rain god. An important part of the ceremonies was to listen to the prophecies of a shaman named Chilam. He is often depicted in Mayan temples, wearing a mask, or sometimes as having a tapir's nose, tusks, and holding an axe. He is also shown with body scales, long whiskers, his abundant hair bound up above his head. One may also see him in wells, rivers, and streams, often net fishing. *See also* "B"; Chacs; Tlaloc.

Chacs (Maya People, Yucatan)
Minor rain deities. The ruler of the Chacs is Chac. Initially there were four Chacs, one for each point of the compass. During spring festivals, the hearts of wild animals were sacrified to the Chacs. They are associated with the Becabs and Itzamna (q.v.). The Chacs, depicted as old men, are similar to the Tlalocs and their ruler, Tlaloc. *See also* Becabs; Chac; Tlalocs.

Chadanta (Buddhist; India)
Chadanta was the Bodhisattva in another life. He appeared as a white elephant with six tusks. As an elephant he had two wives, one who was jealous of the other. The jealous woman desired to be reincarnated as a human princess. Her wish was granted and in her next life she was a princess who grew up and married the King of Benares. When she remembered her prior life, she sent a hunter out to search for her husband, the white elephant with six tusks. His instructions were to kill him and return his tusks to her. The hunter tracked Chadanta, captured him in a pit, and wounded him with his arrows. Chadanta asked the hunter what motivated him to visit harm upon him. The hunter relayed his instructions to the elephant. When Chadanta realized that it was his fate to die in this manner, he helped the hunter fulfill his task. The hunter was unable to saw through the elephant's tusks. Chadanta relieved him of his task by sawing off his own tusks. He died in his own blood. When the news reached the queen, she too died.

Chafura (Egypt) *see* Khepri.

Chahuru (Pawnee People, North America)
Water Spirit.

Chaitraratha (India) Celestial Garden. *See also* Kuvera.

Chak-na-rin-chhen (Tibet) *see* Ratnasambhava; Vairocana.

Chak-yu-ma (Tibet) *see* Ankusha.

Chakra (Hindu; India)
This magic weapon, shaped like a wheel, was given to Vishnu by Shiva to destroy demons. The Chakra symbolizes the sun.

Chakra Sambara *Heyvajra, Sambara* (Buddhist; Nepal)
Chakra Sambara, an aspect of Sambara, the deity of supreme bliss, is also a manifestation of Heyvajra, the central figure of Vajrayana Buddhism. Chakra Sambara is depicted embracing his consort Vajrabarahi in a mystic position which symbolizes the union between wisdom and method leading to ultimate bliss. *See also* Sambara (B).

Chakravala *Buddhist Universe* (Buddhist; India)
The Buddhist Universe of Chakravala has three planes above, around and below Mount Meru. The lower plane is the abode of a specific type of sinner. It contains one hundred and thirty-six hells reserved for the enemies of Buddha. The lowest realm of hells is known as Avici. The minimum stay in this realm is twenty-five thousand years until the soul is reborn. Around the peak of Mount Meru is the Heaven of the Four Great Kings. This plane is populated with pretas (ghosts), animals, demons and men. The Four Great Kings guard the entrance to Sukhavati, the Buddhist paradise. Above the Heaven of the Four Great Kings is the Heaven of the Thirty-three Divinities. This is also called the Heaven of Sakra (Indra). There are twenty-four heavens above the Heaven of the Thirty-three Divinities. Six of these heavens are for souls who relish the pleasures of the senses. The twenty remaining heavens are known as the Chyana Lokas and the Arupa Lokas. The Arupa Lokas are the regions of Abstract Meditation. The Chyana Lokas are the dwelling places of enlightened souls. *See also* Dhartarastra (for a description of the Heaven of the Four Great Kings); Lokapalas; Sukhavati (Paradise); Visvakarma; Yidak.

Chakrisvari (India)
A Yakshini with sixteen arms. *See also* Yaksha and Yakshini.

Chala (India)
Goddess of fortune.

Chalchihuitzli (Aztec People, Mexico) *see* Chimalmatl.

Chalchiuhcihuatl (Mexico) *see* Xilonen.

Chalchiuhtlicue *Chalchihuitli'cue, Chalchihuitlicue, Chalchiuhcueye* (Aztec People, Mexico)
Also known as: *Acuecueyotl, Apoconallotl, Atlacamini, "Emerald Lady," "I"* (possibly), *Petticoat of Blue Stones* (sometimes called this name).

www.ebook3000.com

them all combine within us is what is important. Likewise in religion there is God (a Force in Taoism we call Wu Chi, the nothingness, the supreme power controlling the universe); with a good heart and virtue energy we can connect with this force.

The complete practice of the Microcosmic Orbit Meditation is fully described in the book "Awaken Healing Light of the Tao" by Mantak Chia.

Cosmic Inner Smile and the Six Healing Sounds

These are very important practices to make the connection among the organs, the colors and the good virtue energy; each organ color will enhance your connection to the cosmic and the Universal Healing power.



Fig. 1.1 *Red for the Heart*
White for the Lungs
Yellow for the Spleen
Blue for the Kidneys
Green for the Liver.

Each organ has its own vital color and when abundant it will radiate out as an aura for healing and protection. These organ colors and their associated universal connections have great healing power. The power of the 'Six Healing Sounds' will help enhance the connection to the cosmic source. Each sound will foster different healing energy. The practices also help balance, refine and transform the negative energy back to positive energy.

Iron Shirt Chi Kung and Bone Breathing

Iron Shirt Chi Kung and Bone Breathing are a system of standing meditations. These exercises help you to become grounded and to root your connection into the earth force, in order to build a good structure and absorb greater force. In turn, this will help draw in the heavenly force, which will combine with the very potent healing power of the earth's yellow light. The practice also strengthens the body so you can hold a higher energetic charge. These abilities are essential prerequisites for handling greater amounts of energy.

Chalchiuhtlicue is known as a beneficent and a malevolent deity. She is the Goddess of the East, ruler of the water sun Nahuiatl, goddess of the sea, springs, and all running water. She is the protector of newborn babies and of marriages. She ruled the fourth universe, which the flood destroyed. Tlaloc is her brother and perhaps her spouse. In some renditions, she is the spouse of Tlaloctecutli who was created to rule the waters. Sometimes she appears as the wife of Quetzalcoatl. She is the Lord of the Third Hour of the Day, and the Sixth Hour of the Night. She wears a skirt covered with jade. Her headdress is similar to that of Tlazolteotl. Her colors are blue and white. She is associated with flowers and mushrooms and often carries amaranth stems. Sometimes she is depicted as a snake or frog. The Mayan water goddess "I" (q.v.) may be the same as Chalchiuhtlicue. She preceeded the Mayan rain and thunder god Chac (q.v.). *See also* Acuecueyotl; Legend of the Four Suns; Lords of the Day Hours; Lords of the Night Hours; Ometecutli and Omeciuatl; Quetzalcoatl; Tlaloc; Tlaloctecutli.

Chalchiuhtonatiuh (Aztec People, Mexico) *see* Legend of the Four Suns.

Chalchiuhtotolin (Aztec People, Mexico) *see* Tezcatlipoca.

Chalciope (Greek)

Also known as: *Iophossa*

She is the daughter of the king of Colchis and his first wife, the nymph Asterodeia, and half-sister of Absyrtus and Medea. Chalciope was the first wife of Phrixus. Their children are Argus, Cytissorus, Melas, Phrontis and Presbon. Thessalus is her son by Heracles. She persuaded her sister to help Jason in his search for the Golden Fleece, after the Argonauts rescued her four sons from a shipwreck. *See also* Aeetes; Argus; Golden Fleece; Medea; Phrixus.

Chalcipe (Greek) *see* Argus (D).

Chalcodon (Greek)

King of the Abantes of Euboea. The son of Abas and Ocaleia, his siblings are Acrisius and Proetus. Amphitryon killed him at Thebes. *See also* Abas (A); Acrisius; Amphitryon; Proetus.

Chalcon (Greek) A Myrmidon. *See also* Telchines.

Chalmecatciuatl (Aztec People, Mexico)

Paradise. This is the heaven where the Tree of Milk grows. It is reserved for children. When Tlaloc is in residence, it is called Tlalocan. May be similar to Iztaccihuatl (*see* Mixcoatl). *See also* Mictlan; Tlaloc.

Chalucas (Zoque People, Mexico; possibly originally Maya)

Also known as: *Homshuk* (Popoluca People), *Kondoy* (Mixe People).

Culture hero. There is little known about Chalucas. He might have been a corn spirit. The few legends available indicate he defeated enemies and started present day civilization.

Champ-pa (Tibet) *see* Maitreya; Mamaki.

Chamunda (India)

This is the name of the goddess Kali in her bloodthirsty manifestation as the slayer of the demons Chanda and Munda. In battle, her mount is the buffalo. *See also* Kali.

Chanda (India) *see* Durga.

Chanda Maharoshana (Nepal) *see* Chandamaharoshana.

Chandamaharoshana *Chanda Maharoshana* (Buddhist; Nepal)

Also known as: *Acala, Akshobhya, Mahachandrarosana.*

Chandamaharoshana is an aspect of Akshobhya. He bears on his crown the effigy of Akshobhya. Worshipped in secret, he is kept secluded from public gaze. He has one face, two arms and squinted, slightly red eyes. His bare fangs are framed by a beastly face. A jewelled headdress decorated with a garland of severed heads adorns his head. In his right hand he carries the sword and in his left hand the noose around his raised index finger against his chest. His left leg touches the ground and his right leg is slightly raised. Clothed in tiger skin, he is adorned with jewels. White snakes compose his sacred thread. *See also* Acala; Akshobhya; Tara.

Chandi (Buddhist, Hindu; India)

Also known as: *Devi, Durga-Kali, Tou Mu* (China).

Chandi, meaning "fierce," is an aspect of the Great Mother Devi. It is also the name applied to Durga-Kali, who is an aspect of Devi, in her terrifying aspect when she slays the demon Mahisha. Compare Chandi to Marichi (A) and Tou Mu (Chinese). *See also* Devi; Durga; Kali.

Chandika (India)

"The Burning," or "The Fierce." *See also* Durga; Kali.

Chandra *Candra* (Hindu, Vedic; India)

Also known as: *"Bright One," Candramas, Soma.*

Chandra the moon god was created from the churning of the milk ocean which produced soma and amrita, the beverages of the gods. Once considered an independent god, Chandra was later assimilated by Soma. In some renditions, Chandra is the lover of the beautiful goddess of dawn, Ushas, or Surya, the sun goddess. The goddess Rohini (also known as Red Cow) is the wife of Chandra and Soma. Chandra's steed is the antelope. He rises up from the ocean each night and influences the lives of mortals from birth until death. Chandrakanta is the moon-gem prized by healers. It is said to reduce fevers and eliminate headaches. The Chandrakanta is retrieved from ponds at midnight by divers who are willing to risk having spells cast upon them by water nymphs. The stone is created by the rays of the moon falling on water that is free of all pollutants. In Vedic mythology, Chandra is one of the eight attendants of Indra, who are known as the Vasus. *See also* Amrita; Asvins; Kurma; Parvati; Rohini; Soma; Surya (B); Ushas; Vasus.

Chandra-Prabha (India) *see* Gwakko-Bosatsu.

Chandrakanta (India) Sacred moon-gem. *See also* Chandra.

Chandraprabha (Jain; India)

Lord of the moon and ruler of the present age, Chandraprabha is the eighth of twenty-four forebears of Jainism.

Chang (Buddhism, Taoism; China)

Also known as: *Chang Hsien, Chang Kung, Chang-Sien, Chang Yuang-Hsiao, Immortal Chang.*

God of male children. This ancient deity of Szechwan is still worshiped in a ceremony using a bow of mulberry and arrows of silkworm wood. Chang is the father of Kien t'an. He protects all children from the Celestial Dog, T'ien Kou (Serius). Originally, Chang was responsible for the birth of male children, but later he was responsible for the birth of all children. He is the father of two mortal writers; Su Shi and Su Ch'e. Chang is shown as an old man bending a bow pointed at the sky. He is the counterpart to Avalokitesvara who is a deity of women. *See also* Avalokitesvara.

Chang Fei Khang Fei (China)
Deity of butchers. *See also* Fan K'uei.

Chang Hsien (China) *see* Chang.

Chang-Kuo-Lao *Chang Kuo* (China)
One of the Eight Immortals. He is known by his miraculous donkey. After traveling thousands of miles in a day, he is folded up like a piece of paper. Chang-Kuo-Lao is depicted as an old man, usually riding a donkey backwards and carrying a feather in his hand. *See also* Arhats; Chung-Li-Ch'uan; Eight Immortals; Han Chung-Li.

Chang-O *Ch'ang-O* (China)
Also known as: *Heng-O, T'ai-Yin Huang-Chun, Yueh-Fu Ch'ang O.*

Goddess of the moon. Chang-O's husband Yi, the Excellent Archer, possessed the drink, or pill, of immortality. He was furious to learn that his wife had taken the potion in his absence. Fearful, Chang-O sought refuge in the moon. This ancient legend is still part of traditional belief. Chang-O's other titles are "The Celestial Toad" and "The White Beauty." She is shown as a beautiful young lady. (In some versions Chang-O is a male deity.) *See also* "I" (A); Yi.

Ch'ang-Sheng T'u-Ti (China)
Also known as: *God of the Place.*

Guardian. They are a group of deities who guard the home and its contents. Ch'ang-Sheng T'u-Ti and his wife Jui-k'ing fu-jen are usually named as head of this group. *See also* Ch'uang-kung; K'eng-san-ku.

Chang-Sien (China) *see* Chang.

Chang Tao-ling (China)
Also known as: *T'ien-shih* (Celestial Master).

He is the founder of existing Taoism. Born in the second century (common era), he was deified in the eighth century. He was the recipient of numerous divine revelations during his life. Chang Tao-ling also prepared the drug of immortality. With the aid of his magic talismans and magic powers, he successfully overcame eight king-demons. After passing his wisdom and learnings on to his son, he ascended to the heavens with his wife and two disciples. *See also* Chang-O; Lao-tzu.

Chang Tung-Ch'ang (China) *see* Ch'eng Huang.

Chang Yuang-Hsiao (China) *see* Chang.

Chango (Africa, Caribbean, Central America, South America)
Warrior god. He defends mortals against enemies who want their land, wealth and women.

Channa (India) *see* Buddha.

Chantico (Aztec People, Mexico)
Fire goddess of the home and hearth. Fertility goddess. Chantico is generally associated with wealth and precious stones. She appears with a golden face. Her symbols are a red serpent and cactus spikes.

Chaos (Chinese, Babylonian, Greek)
There are variations of the creation myth in Greek mythology. Hesiod said that Chaos, also known as "The Gap" came into being first, followed by the earth, Gaea. Next followed Tartarus, the dark abyss below Hades, which was followed by Eros (Love). (Eros is not to be confused with Aphrodite's son, who appeared in later works.) All things followed these creations. Chaos gave birth to Nyx (Night) and Erebus (Darkness). Gaea bore Uranus (Sky), Ourea (Mountains), and Pontus (Sea). (*See also* Gaea.) In the Orphic creation myth, Chaos, Erebus, and Nyx existed at the beginning. In the Pelasgian creation myth, Eurynome, the Goddess of All Things, emerged from Chaos, and from the North Wind, also called Boreas, her consort Ophion was created. In the Olympian version, Mother Earth emerged from Chaos and bore her son, Uranus (Sky). In Greek mythology, Darkness existed first and Chaos sprang from Darkness, or that the God of All Things, sometimes called Nature, appeared in Chaos and separated the elements. It is also said that the goddess Aphrodite (foam born) who rose from the sea is the same as the wide-ruling goddess who emerged from Chaos, called Eurynome, in the Pelasgian creation myth, and in Syria and Palestine as Ishtar, or Ashtaroth. In Babylonian mythology, Chaos is a feminine principle meaning mother of all gods and is personified by the goddesses Neith and Tiamat. Air and Chaos, who existed in the beginning, created Kolpia (the wind) and Potos (desire) in the Phoenician Creation Legend of Philo Byblos. In a Chinese version Chaos was likened to an egg and from this egg was born Phan-ku. When the parts of the egg separated the heavy elements became earth and the light, pure elements became the sky. These became Yin and Yang. Also in Chinese mythology, Ch'i and Tien Li were created from Chaos. Phan-ku of China is represented as a squatting man holding the egg of Chaos which is symbolized as Yin and Yang. For the role played by Chaos in the Pelasgian creation myth *see* Eurynome (A). To compare to the Orphic creation myth *see* Phanes; for the Homeric version *see* Oceanus; for the Olympian version, *see* Gaea. *See also* Aether; Air; Boreas; Erebus; Nox; Pan-ku; Tartarus.

Chapala (India)
Goddess of fortune.

Chaquen (Chibcha People, Bogota, South America)
Guardian and god of boundaries. *See also* Bochica.

Char (Armenian) *see* Devs.

Charis *Aegle* (Greek) *see* Aegle; Aglaia; Graces.

Charites (Greek) *see* Graces.

Charities, The (Greek) *see* Aglaia; Graces.

Charon *Kaharon* (Greek)
Ferryman of the dead. Charon is the son of Erebus and Nyx. His siblings are Aether, Cer, Dreams, Hemera, Hypnos, Momus, Moros, Nemesis and Thanatos. He ferries the souls of the dead

www.ebook3000.com

over the waters of the rivers Styx and Acheron in a leaky rotting boat, to Hades. He receives payment for each passenger. (This is why the ancient Romans put a coin [the obolus or obol] into the mouth of a corpse before burial.) If a coin is not produced, the spirit must wait a hundred years, then Charon could ferry them across at no charge. Sometimes he is shown as an aged or grumpy boatman, sometimes with a scraggly white beard and wearing a dirty cloak hanging from his shoulders by a knot. *See also* Acheron; Aether; Cocytus; Erebus; Golden Bough; Heracles; Keres; Nemesis; Nox; Styx; Tartarus.

Charumati (India)
She is the daughter of Krishna and Rukmini. *See also* Rukmini; Sisupala.

Charun (Etruscan)
God of death. His hammer, which is normally used when he accompanies Mars in battle, is also used to kill his victims. *See also* Hades.

Charvi (India) *see* Kuvera.

Charybdis (Greek) *see* Amphitrite; Gaea; Nereids; Scylla.

Chasca (Inca People, Peru)
Dawn goddess. Created by Viracocha, Chasca brings forth flowers and protects young women. She is identified with the planet Venus and is worshiped as an attendant of the Sun. In depictions, she is shown surrounded by clouds who are her messengers. *See also* Viracocha.

Chavah (Babylonia) *see* Eve.

Chavva (Babylonia) *see* Eve.

Chebeldei (Siberia)
Also known as: *Abaasy, Abasy.*
Inhabitants or spirits of the underworld. Chebeldei is a black spirit of the underworld who has a very long nose. Many of these underworld spirits are partly or completely composed of iron, and black in color. Their noses are eighteen meters long. *See also* Abaasy.

Cheiron *Chiron, Kheiron, Kiron* (Greek)
Instructor. Cheiron is the immortal son of the underworld god Cronus and the nymph Philyra. Unlike his uncouth fellow Centaurs, Cheiron was intelligent, cultivated and gentle. Sometimes he is referred to as the chief of the Centaurs. He was renowned for his knowledge and skills in the healing arts, music and archery. Cheiron also had the gift of prophecy. He taught the art of war to many of the famous heroes; Actaeon, Achilles, Asclepius, Jason, Heracles and Podalirius. Cheiron was accidently shot by one of Heracles' poisoned arrows. Although he was immortal, he chose to die and pass his immortality to the Titan Prometheus (q.v.). Cheiron was said to have married Cariclo. He is the father of Endeis, Ocyrrhoe (Menalippe), and Thea. (The gods changed Ocyrrhoe into a horse because of her gift of prophecy.) Cheiron is depicted as a man with a horse's body. *See also* Acastus; Achilles; Actaeon; Aeacus; Aeolus (B), Aristaeus; Centaurs; Cronus; Nessus; Oceanus; Jason.

Chelidon (Greek) *see* Aedon.

Chelovek (Russia) *see* Domovoi.

Chem-pa (Tibet) *see* Mi-Lo Fu.

Chembe (Africa) *see* Bumba.

Chemosh *Kemosh* (Canaan, Moabite, Semite, Sumer; possibly of Egyptian origin)
Also known as: *Baal-Peor, Kammus, Kamus, Shamash* (Sumer).
Chemosh, thought by some to be a deified mortal king, was the national war god of the Moabites when they fought against Israel. He was worshiped along with Eshmun and Melqart, who were said to be the brothers, sons, or husbands of Astarte. Mentioned in the Bible, he was worshiped by Solomon. As Baal-Peor this deity was androgynous. As a male he was a sun god and as female, a moon goddess. Chemosh is shown as a phallus, cone, pillar or tree branch. He is associated with Ishtar (q.v.). *See also* Astarte; Baal; Eshmun; Shamash.

Ch'en (Maya People, Yucatan)
Also known as: *Grandmother.*
Moon goddess. She was the first woman to have sexual intercourse.

Ch'en Ch'i (China) *see* Men Shen.

Chen Wu *Cheng Wu* (China)
Also known as: *Hsuan T'ien Shang Ti, Pei-chi Chen Chun* ("God of the North Pole").
God of the north. God and ruler of the abode of darkness. He is the reincarnation of T'ien Pao. *See also* Hsuan T'ien Shang Ti (q.v.).

Chen Jen (Taoist; China)
"Perfect Ones."
Chen Jen is generally used to describe those who reached perfection and are suitable for worship. The Chen Jen do not have physical bodies. They can travel between the physical and spiritual worlds.

Chen Resik (Tibet) *see* Avalokiteswara.

Ch'eng Huang *Ch'eng-huang shen* (China)
Also known as: *Celestial Mandarin, Chang Tung-Ch'ang, Shui Jung, Yang Ki-Sheng, Yu-K'ien, Yung-Ku Wang.*
God of the city. God of walls and ditches. As Shui Jung, he is one of the "Eight Spirits" (Pa Cha). Double walls surrounded all cities. The ditch between the walls was called huang while the walls were called ch'eng. Worship of Ch'eng Huang is probably from the Yao dynasty around 2357 B.C.E. Each village had its own Ch'eng Huang. They are called T'u-ti (Gods of the Place). Some versions say the original god (or founder) has one name, and is usually worshiped instead of Ch'eng Huang. Some of the gods of walls and ditches are Yank Ki-sheng, Yu-K'ien, Chang Tung-ch'ang, and Yung-ku wang. Ch'eng Huang is associated with Mr. White (Po-lao-ye), Mr. Black (Hei-lao-ye), Mr. Horse-face, and Mr. Ox-face. *See also* Ma-Mien; Men Shen.

Cheng Lung (China) *see* Heng and Ha; Men Shen.

Cheng Wu (China) *see* Chen Wu.

Chenrezig *Chenrgzi* (Buddhist; Tibet)
An incarnation of Buddha and the national tutelary deity of

Tibet, Chenrezig is the four-armed herdsman. His mantra is "Om man-ni pad-me hum." *See also* Buddha.

Chenrgzi (Tibet) *see* Chenrezig.

Chent-Ament (Egypt) *see* Osiris.

Chepera (Egypt) *see* Khepri.

Cherakan-Ixmmucane (Maya People, Yucatan) *see* Chirakan-Ixmucane.

Cheresi *(Bodhisattva)* (Hindu; India) *see* Bodhisattva Cheresi.

Chernobog *Cernobog, Czarnobog, Zcernoboch* (Slavic)
Evil deity. Chernobog is the black god who is opposite of Byelobog, the spirit of light. *See also* Byelobog.

Cherruve (Araucanian People, Chile, South America)
Depicted as man-headed serpents, the Cherruve are spirits of shooting stars who are under the command of the weather and thunder god, Pillan. *See also* Auchimalgen; Pillan.

Cherub *Choreb, Kerub* (Roman; originally, possibly Assyrian)
Also known as: *Cherubim* (plural).
Messengers. In Biblical lore they were pictured as two figures of gold whose wings covered the mercy seat on the Ark. Although often shown as cupid-like figures, most scholars think they were fierce guardians of holy places. They were possibly derived from the Assyrian guardian creatures placed at the gates of temples. These were bulls with the head of a man and wings of an eagle. Some legends indicate they were of the higher order of angels and were the supreme god's messengers. The Bible describes them with four faces, four wings, and calf-like feet. *See also* Angels; Apis (A).

Cherubim (Semite) *see* Angels; Cherub.

Chespisichis (Greek) *see* Khensu.

Chhaya *Khaya, Shaya* (India)
Goddess of the shade. *See also* Sanja; Tapati.

Chhwaskamini (Buddhist; Nepal)
Also known as: *Tara.*
Evil spirit. Chhwaskamini is the evil form of the loving goddess Tara who fights off demons and wicked spirits. *See also* Tara.

Ch'i (A) (China)
The ether. In the beginning there was Ch'i, "ether," a single cell. This divided into Yin and Yang as a result of the vibrations set in motion by Tao, a force, and thus creation began with the appearance of two opposite ethers, able to produce the elements, which went on to combine and form everything in the universe. *See also* Chaos.

Ch'i (B) (China)
Ch'i is the son of Yu and the Girl of T'u. His grandfather is Kun. In some renditions, Yu was born from his dead father's stomach three years after his death. In another myth, Yu turned into a bear while digging through a mountain, possibly in an attempt to hold back flood waters. When T'u saw him in bear form she ran away and changed into a stone. Yu hollered after her "Give me my son." That stated, the stone split open and Ch'i was born. *See also* Kun (B).

Chi (China)
Chi is the soul or the total being; the unexplainable manifestation that controls the body.

Chi-Haya-Buru (Japan) *see* Kami.

Ch'i-Lin (China)
God of animals. This unicorn is one of the "Head of All Animals," known as Ch'i-Lin. It doesn't eat living vegetation and never walks on green grass. It appears at the birth of good leaders, or sages. Ch'i-Lin has the body of a deer, the tail of an ox, and the hooves of a horse. It is multi-colored on the back and yellow on the belly.

Chi Sheng Sien-Shi (China) *see* Confucius.

Ch'i-ti *Red Lord* (China) *see* Shang Ti.

Ch'i-You (China)
God of war, weapons, smiths and dancers. He is the son, grandson, or minister of Shen-nung ("Divine Farmer"). Ch'i-You eats stone, iron and sand. His head is iron, his brow bronze, he has sharp pointed horns, four eyes, six arms, eight fingers and eight toes. His hair bristles like spears. He either has a human body with feet of an ox, or a beast body and human voice.

Chia *Chie* (Muyscaya People, Colombia, South America)
Also known as: *Huytaca, Suetiva, Xubchasgagua.*
Chia is the moon goddess mate of Bochica, or in some myths, Cuchaviva. From jealousy and as a mischievous prank, Chia used her magic to flood the land. Bochica punished Chia by banishing her to a permanent home in the sky, where she was transformed into the moon, and became a primary goddess of women. In an alternate tale, Chia told mortals that merry-making, joy and laughter should supplant the severe rule of laws made by Bochica. This angered Bochica, who turned her into an owl. To spite him, she helped Chibchachum flood the plain of Bogota. There were few survivors. If she became displeased with a man, he had to dress as a woman to avoid being punished by her. Chia is often confused with Hunthaca, the spouse of Nemquetcha. She is the same as Suetiva (q.v.). *See also* Bochica.

Chibcha People — Creation Legend (Colombia, South America) *see* Bachue; Chimaqua.

Chibchacum *Chibchachum* (Muyscaya People, Colombia, South America)
He holds up the earth. When this god is tired, he shifts the weight on his shoulders and causes earthquakes. *See also* Bochica.

Chibiabos (Algonquin People, North America) *see* Chipiapoos; Manibozho.

Chibilias (Maya People, Yucatan) *see* Ix-chel.

Chichen Izta (Maya People, Yucatan) *see* Itzamna.

Chickcharney (Andros Island, Bahamas)
A small, feathered, furred spirit of the forest.

www.ebook3000.com

Chicomecoatl *Chicomexochit* (Aztec People, Mexico)
Also known as: *Seven Snakes, Xilonen.*

Goddess of crops, particulary maize. Goddess of plenty. She is associated with Coatlicue because of her powers of fertility. She is similar to Ceres, and is identified with Tonacacihuatl. Chicomecoatl is possibly represented as a red ear of corn. *See also* Ceres; Coatlicue; Xilonen.

Chicomexochitl (Mexico) *see* Tonacatecutli.

Chicomoztoc (Aztec People, Mexico)
Also known as: *The Seven Cities of Cibola* (possibly).

Place of origin. In the creation myth, the Aztec race emerged from the Cavern of the Seven Chambers, also known as Chicomoztoc, after a great natural disaster. *See also* Legend of the Four Suns.

Chiconamictlan (Aztec People, Mexico) *see* Chicunauhmictlan.

Chiconauapan (Aztec People, Mexico) *see* Chicunauhmictlan.

Chicuna (Andean People, Peru)
"Lord of All Things." Creator deity.

Chicunauhmictlan *Chiconamictlan* (Aztec People, Mexico)
Also known as: *Apochquiahuayan, Chiconauapan, Mictlan.*

Home of the Dead. Chicunauhmictlan, frequently shortened to Mictlan, is the ninth pit where the "lords of night" rule over the affairs of men. It is the abode of Mictlantecutli and Mictlanciuatl who live in a windowless home. Xiuhtecutli is also a resident of Chicunauhmictlan. The dead are given magical spells and a water vase for their trip to the Home of the Dead. They use spells to help them when they pass the monsters guarding the "clashing mountains." They also pass eight deserts, and eight hills. After meeting the "Lord of the Dead," Mictlantecuhtli, the dead souls mount a red dog sacrificed at their death and follow the nine-fold stream in the underworld. They are then allowed to take their rest in Chicunauhmictlan. Chicunauhmictlan is the opposite of Omeyocan (q.v.). *See also* Chicuna; Legend of the Four Suns; Mictlantecutli.

Chie (South America) *see* Chia.

Ch'ien Niu (China) *see* Kengiu (Japan).

Ch'ien-T'ang (Taoist; China)
Chief of the river gods. A Dragon King. He is the brother of Ling Hsu, who is a king of one of the local rivers. One of the legends associated with this deity is that he caused a nine-year flood. *See also* Dragon Kings.

Ch'ih Kuo (China) *see* Mo'li Shou.

Chih-Nii (China) *see* Chin Nu.

Chih Nu (China) *see* Chih Nii; Chin Nu.

Chih-Wen (China)
Water dragon. His depiction, sometimes shown as a fish with a raised tail, is carved on bridges and roofs to ward off fire.

Ch'ih Yeo (China)
Satan. He is the head of eighty-one brothers who are described as having the bodies of beasts. Huang-Ti captured him and cut him to pieces.

Chikisanti (Ainu People, Japan)
Goddess of elm trees. The ancient Ainu People believed that the elm tree was the first tree. Chikisanti is the mother of the first man, Pon Okikurumi, by Okikurumi. *See also* Okikurumi.

Children of Don, The (Britain, Wales)
Deities of Wales and Britain, similar to the Irish Tuatha De Danann. The two most important of the Children of the Don are the all-powerful god Gwydion, a beneficent teacher who controlled war and peace, and his sister-wife Arianrhod. *See also* Arianrhod; Gwydion.

Children of Llyr, The (Britain, Wales)
Popular deities of the ancient Welsh and British people. Llyr became the father of Manawyddan by Don's daughter Penardun and of Bran and Branwen by Iweridd. *See also* Llyr; Manawyddan.

Chilenga (Africa) *see* Lisa.

Chimaera *Chimera, Chimaira* (Greek)
A Lycian monster. Storm deity. The Chimaera is the offspring of the whirling hurricane Typhon and Echidna, an eternally youthful, half-nymph, half-snake monster. The Chimaera did not fare well in the appearance department, nor did her siblings who are the Sphinx, Hydra, Cerberus, the Caucasian Eagle, the Crommyonian Sow and the Vultures. Raised by the Lycian chieftain, Amisodaurus, the Chimaera, personification of evil, ravaged the land and killed the innocent. Bellerophon, the slayer of monsters, had been sent by Iobates, the king of Lycia, to perform numerous dangerous tasks. Outfitted with the golden bridle on the winged Pegasus, he flew through the air, confronted the monster and slew it. Chimaera is shown with three heads or the head of a lion, goat, or snake, or with the front parts of a lion, the center of a goat and a snake's tail, and she breathes fire. In medieval times, the Chimaera was associated with lust. In current interpretations, it has been seen as an allegory of an Achaean capture of the White Goddess's shrine on Mount Helicon. It is also thought to represent an initiation. To compare the Chimaera (the essence of a storm cloud) with wind deities *see* Aeolus, Borea, Eurus, Notus, Zetes, and Zephyrus. To compare the Chimaera to other destructive forces of nature *see* Aegeon, Aello, Bellerophon, Harpies, Pegasus, and Typhon (A). *See also* Cerberus; Echidna; Hambaris; Hydra; Sphinx.

Chimaira (Greek) *see* Chimaera.

Chimalman (Aztec People, Mexico) *see* Chimalmatl.

Chimalmatl *Chimalman* (Aztec, Toltec People, Mexico)
Also known as: *Chalchihuitzli* ("Precious Stone of Sacrifice").

Ancestor of the Toltec people. She is the earth-born virgin wife of Mixcoatl and the mother of Quetzalcoatl under his name Citlallatonac. She died during childbirth and was given the title Chalchihuitzli. In other renditions, she is known as the mother of Quetzalcoatl by Camaxtle (also known as Texcatlipoca). She might be related to Huitzilopochtli (q.v.). *See also* Camaxtle; Ilancue; Mixcoatl; Texcatlipoca.

Chimata-no-Kami (Japan)
Also known as: *Sanzu-no-Kawa.*
God of cross-roads. According to some, he was a phallic deity who was removed by Buddhism. He is one of the gods of roads known as Sae-no-kami. *See also* Sanzu-no-kawa.

Chimera (Greek) *see* Chimaera.

Chiminagua *Chiminigagua, Chiminiquagua* (Chibcha People, South America)
Also known as: *Bochica.*
Creator deity. Before anything existed, light was enclosed by Chiminagua. He rose and freed the light, then created mankind. In the tale of Chibcha myth, Chiminagua was the creator of all. When the world began, the light was in Chiminagua and all was darkness. He set the light free, creating blackbirds to carry it over the earth. In some renditions, Bochica was given the name Chiminizagagua, meaning "Messenger of Chiminagua." *See also* Bochica; Suetiva.

Chimini-Pagus (Chibcha, Muyscaya People, South America)
This is the name of the casket that contained light in the beginning. In the Creation Legend, it was sent to earth where blackbirds scattered the light. *See also* Chiminagua.

Chiminigagua (Colombia, South America) *see* Chiminagua.

Chiminiquagua (Colombia, South America) *see* Chiminagua.

Chiminizagagua (Chibcha People, Bogota, South America) *see* Bochica.

Chin (Maya People, Yucatan)
He is the god of death and one of the Becabs (q.v.). *See also* Acat.

Chin Chia (China)
Also known as: *Mr. Golden Cuirass.*
God of Scholars. Protector of weak students. Avenger of evil actions. Occasionally he sometimes accompanies Chu I or K'uei Hsing as an attendant of Wen Ch'ang. Chin Chia is shown with a flag and a sword. *See also* Chi I; Wen Ch'ang.

Ch'in Ch'iung (China) *see* Men Shen.

Chin Neu (China) *see* Chin Nu.

Chin Nu *Chih Neu, Chih-Nii, Chih Nu, Kien Niu* (China)
Also known as: *Heavenly Spinster, Spinning Damsel, Stellar Goddess, Weaver Damsel.*
The goddess of spinners and weavers, Chin Nu, is the daughter of the Jade Emperor Yu Huang. One day Chin Nu came to earth from heaven to bathe. An ox, who was the guardian spirit of a cowherd, advised him to take Chin Nu's clothing. She was unable to return to heaven without her clothes, so she stayed and wed the cowherd. They had two children. Seven years passed and Chin Nu found her clothes and returned to heaven. Her spouse was very upset. He consulted with the ox. It was agreed that he would carry the children in baskets on a pole across his shoulders, and he would grasp the ox's tail and go to heaven in search of his wife. When he encountered her father, he demanded that he be permitted to see Chin Nu. Yu Huang gave her husband, Ch'ien Niu, a star to the west. Chin Nu's star is to the east of the Heavenly River. Because of their positions they are only reunited on the seventh day of the seventh month each year. On that day all the magpies each take a twig and build a bridge for them across the Heavenly River. Her husband became known as the Celestial Herdsman. In a variation of this myth, Chin Nu wove fine garments without seams for her father Tung Wang Kung (also known as Yu-ti). This so pleased him that he gave her in marriage to Ch'ien Niu, the Heavenly Herdsman, a star in the constellation Aquila. Then, because the goddess had too little time for his robes, the Jade Emperor put the Milky Way between his daughter and her husband. It was believed that once a year, crossing by a bridge made by magpies, the couple was reunited. In some versions, it is the queen who placed the Milky Way between the lovers. *See also* Kengiu (Japan).

Ch'in Shu-Pao (China) *see* Hu King-te; Men-shen.

China — Creation Legend *see* Ch'i

Ching-Tu (Buddhist; China)
Also known as: *Kun-Lun Mountain.*
Heavenly paradise. The legend is the same as that of the Kun-Lun Mountain. *See also* Jodo; Kun-Lun.

Ching Yuh (Korea) *see* Kengiu (Japan).

Chinnamastica (India) *see* Kali.

Chinnigchinich (Native North American)
Creator. He is an orphan who created men and women out of clay. It is he who taught the people the art of medicine.

Chinnintamma (India)
She is one of the Mutyalammo goddesses who are deities of the household. She functions as head of the home. *See also* Mutyalammo.

Chinta-Mani (India) *see* Cintamani.

Chintamani Lokeswar (Nepal) *see* Lokeswar.

Chinvat Bridge *Chinvat Peretu, Cinvat* (Persian)
Also known as: *Bridge of the Gatherer, Bridge of the Requiter.*
This bridge spans from Mount Tera, the peak of the cosmic Mount Alburz, to heaven. Upon death, all souls cross Chinvat Bridge. The beams of the bridge are many-sided and of varying thickness. When a righteous soul arrives, the thick rim appears. When a sinner arrives, the thin and sharp beam is presented and the soul drops to a hell below. On the rim of Mount Alburz is the Arezur ridge, the gateway to hell, where demons congregate. Mithra, Sraosha and Rashnu are the judges of the dead souls. Indra made the bridge shrink as souls passed over it, thus dropping them into the abyss. *See also* Aeshma; Alburz (Mount); Amesha Spentas; Andra; Hariati (Mount); Mithra; Rashnu; Sraosha; Yazatas.

Chione (A) (Greek)
She is the daughter of Boreas and Oreithyia. Her siblings are Calais, Cleopatra, Haemus and Zetes. The seductive sea god, Poseidon, impregnated Chione and she bore Eumolpus whom she threw into the sea. He was rescued by his father and raised by his half-sister, Benthesicyme. *See also* Acacallis; Autolycus (A); Boreas.

Chione (B) (Greek)
In one day, Chione had two children by two different gods:

www.ebook3000.com

Autolycus by Hermes and Philamon by Apollo. *See also* Autolycus; Philamon.

Chipiapoos (Potawatomi People, North America)
God of the dead. Brother of the trickster, Nanabojo. Chipiapoos was pulled under the ice by demons. He is similar to Chibiabos. *See also* Manibozho; Nanabojo.

Chiquinau (Nicaragua, Central America)
"God of Nine Winds." God of the air. He is one of the creator gods who are ruled by Tamagostad and Zipaltonal. He is associated with Ciaga; Ecalchot; Misca; Quiateot; Vizetot.

Chirakan-Ixmucane *Cherakan-Ixmmucane* (Maya People, Yucatan)
Creator. This goddess was created when four of the gods who created the world split themselves and became four additional deities. She is associated with Ixpiyacoc, Ixmucane, Hunahpu-guch and Hunahpu-utiu. Chirakan-Ixmucane, Ajtzak and Ajbit were among the thirteen deities who tried to create mortals from various materials. *See also* Alom; Legend of the Four Suns.

Chiron (Greek) *see* Cheiron.

Chiruwi (Africa)
Spirits. The Chiruwi are both good and bad. They have half-bodies, one eye, one ear, one leg, and one arm.

Chitra-ratha (India) *see* Gandharvas.

Chitragupta (India) Registrar of the Dead. *See also* Yama.

Chitrangada (A) (India) Wife of Arjuna (q.v.).

Chitrangada (B) (India) Half-brother of Vyasa (q.v.).

Chiu Kung (China)
Also known as: *Chiu I.*
"Nine Palaces." "Mountains of the Immortals," (also known as Hsien Shan). "Territory of the Immortals," (also known as Hsien Ching). Chiu Kung is the residence of the Fairies. *See also* Hsi-hua; Tung Wang.

Chiun (Hebrew) *see* Rephaim.

Chiutcoatl (Aztec People, Mexico) *see* Cinteotl.

Chixu (Pawnee People, North America) The Ghosts.

Chlevnik (Russia, Slavic)
One of the Domovoi who are household spirits, the Chlevnik is the spirit of the cattle shed or barn. To prevent harm to new animals and to be successful in raising cattle, the Chlevnik must be appeased with an offering. In some areas, the farmers attempt to drive the Chlevnik away by beating on the walls to frighten it. *See also* Bannik; Domovoi; Kikimori; Ovinnik.

Chloris (Greek)
Also known as: *Meliboea, Flora* (Roman).
Goddess of flowers. Goddess of fertility. Chloris is the personification of spring. She is the daughter of Amphion and Niobe. Her eleven brothers and sisters were murdered by Apollo and Artemis. She alone survived. In some traditions she is the wife of Zephyrus (who is the West Wind) and a son, Carpus, the personification of fruit. She has also been called the wife of Neleus. As the wife of Neleus, she is the mother of thirteen children. Chloris was a participant and winner in the Heraean Games. The Heraean Games were held every four years at Olympia and were only for female participants. They were initiated by Hippodameia in honor of Hera. At one time, the women, classed by age, with the youngest first, ran with their hair flying loose and a bare shoulder. *See also* Amphion; Apollo; Artemis; Flora; Niobe; Zephyrus.

Chnemu (Egypt) *see* Khnum.

Chnoumes (Egypt) *see* Khnum.

Choco People — Creation Legend (Colombia, South America) *see* Caragabi

Choctaw People — Creation Legend (North America) *see* Aba

Chonchonyi (Araucanian People, Chile, South America)
This evil deity has a large head with long, flapping ears which he uses as wings to fly about as he preys on the sick and weak.

Chonsu (Egypt)
God of the Moon.

Choreb (Roman) *see* Cherub.

Chos-Rgyal Phyi-Scrub (Tibet) *see* Yama.

Choun (Inca People, Peru) *see* Inti; Manco Capac; Virococha.

Chousorus (Phoenician) *see* Oulomos.

Christ *Khristos* (Greek) "Anointed One." *See also* Jesus.

Chronos (A) (Greek) see Cronus.

Chronos (B) (Greek)
This is the name of one of the sun god Helius' horses. *See also* Helius.

Chrysaor (Greek)
Chrysaor and his brother, Pegasus, sprang from the blood of Medusa at the time she was decapitated by Perseus. His father is the sea god Poseidon. Chrysaor married the Oceanid Callirrhoe. He is the possible father of the female monster Echidna and Geryon, the owner of the flocks stolen by Heracles as his tenth labor. *See also* Callirrhoe; Echidna; Heracles; Medusa; Oceanids; Pegasus; Perseus.

Chryse (A) (Greek)
Also known as: *Comana*
She is the daughter of Halmus, the king of Boeotian Orchomenus. Her relationship with Ares produced a son, Phlegyas, who later became the king of Orchomenus. *See also* Ares; Phlegyas.

Chryse (B) (Greek)
She is the daughter of Pallas, who is the son of Lycaon and Cyllene. *See also* Pallas.

Chryseis (Greek)
Also known as: *Astynome.*
When she was captured by the Greeks during the battle at Troy, she became the concubine of Agamemnon (q.v.).

Chryses (A) (Greek)
He is the son of Chryseis and Agamemnon. *See also* Agamemnon; Chryseis.

Chryses (B) (Greek)
His parents are Poseidon and Chrysogeneia and his son is Minyas.

Chryses (C) (Greek)
He is one of the many children of Hermes (q.v.).

Chryses (D) (Greek) He is the father of Chryseis (q.v.).

Chrysippe (Greek) *see* Danaus.

Chrysippus (Greek) He is the son of Pelops (q.v.).

Chryson (Greek) *see* Telchines.

Chrysothemis (A) (Greek)
Also known as: *Iphianassa, Iphigeneia.*
She is the daughter of Agamemnon and Clytemnestra. Her siblings are Electra and Orestes. *See also* Agamemnon.

Chrysothemis (B)
In the Pythian games, the Cretan Chrysothemis won first prize for poetry and music.

Chthon (Greek)
An epithet of Gaea, the personification of earth. *See also* Gaea.

Chu (China)
Spirit of the Grain. Chu is the son of Shen-Nung, the god of agriculture. *See also* Hou Chi; Shen-Nung.

Ch'u Chiang (China) *see* Chu-kiang.

Chu I (China)
Also known as: *Lu Ch'i, Mr. Red Coat, Mr. Red Jacket.*
Chu I is an assistant to Wen Ch'ang (also known as Wen-ch'ang ti-kun, or Wen-ti) the god of literature. Chu I's mortal name is Lu Ch'i and the dates given for his life are approximately C.E. 780–784. He is usually shown with K'uei Hsing (also spelled K'ue-sing), another assistant. Sometimes he is shown with Chin Chia. Chu I and Chin Chia are identified as helpers and protectors of weak candidates. Chu I has the green face of an Immortal, the lips of a dragon and the head of a panther. *See also* Chin Chia; Wen Ch'ang.

Chu Jung (China)
Also known as: *The Red Emperor.*
Chu Jung was originally the Red Emperor who reigned for two hundred years. Later he became the god of the Fourth Month and the god of fire. He punishes those who break the laws of heaven.

Chu-kiang *Ch'u Chiang* (Buddhist; China)
The ruler of the second of the Chinese hells (T'i-Yu), he judges thieves and murderers by placing them in front of a mirror which reflects their evil actions. *See also* Kshitigarbha; Ti-Yu.

Ch'uan Hou (China) *see* T'ien Hou.

Chuan-Lun *Chuan-Lun Wang* (China)
God of hell. Of the ten hells in Chinese mythology, Chuan-Lun is the ruler of the tenth and last hell. He pronounces the final sentence and assigns the soul to one of six states. *See also* Kshitigarbha; Ti-Yu.

Ch'uang-Kung (China)
Also known as: *Lord of the Bed.*
One of the deities of the bed or bedroom. Along with his mate, Ch'uang-mu, he protects the bed. He is possibly worshiped for his ability to allow a woman to have a child. Ch'uang-Kung is one of a group called "Gods of the Place." *See also* Ch'ang-sheng t'u-ti; Ch'uang-Mu.

Ch'uang-Mu (China)
Also known as: *Lady of the Bed.*
Goddess of the bed or bedroom. Paired with Ch'uang-Kung, lord of the bed. She is one of a group called "Gods of the Place." *See also* Ch'ang-sheng t'u-ti; Ch'uang-Kung.

Chuchulain (Celtic) *see* Cuchulain.

Chukum (Colombia)
God of boundaries and foot-races. He is one of deities worshiped with Bochica (q.v.).

Chukwu (Ibo People, Africa) Supreme god.

Chunda (A) (Buddhist; India)
Chunda, a benign goddess, is shown with a smiling face, four or sixteen arms, holding a lotus, rosary and a begging-bowl.

Chunda (B) (Hindu; India)
Chunda and Munda, two demon spies, were sent by Sumbha and Nisumbha to kill the goddess Durga. They approached her with their army, and she promptly devoured all of them. *See also* Durga.

Chung-Li-Ch'uan (China)
High god. He is sometimes known as the chief of the Eight Immortals (Pa Kung). His function is to revive the dead. Chung-Li-Ch'uan is shown as a fat bearded man, sometimes with a bare stomach, sometimes clothed. He carries a fan and the peach of immortality. *See also* Arhats; Eight Immortals; Han Chung-Li; Pa Hsien; Pa Kung.

Chung-Liu (China)
Also known as: *Tsao Shen.*
God of the Shaft. It refers to the air shaft in the center of the old houses. In some versions, Chung-Liu is one of the gods of the inner-doors. *See also* Tsao Shen.

Chupunika (India) A Krittika sister. *See also* Rishi.

Churning of the Ocean (India) *see* Kurma.

Chuvalete (Cora People, Central America)
This is the morning star who protects worshipers from the fierce sun.

Chuvash (Russian) *see* Kaba.

Chwezi (Uganda, Africa)
Tribal deities of the forces of nature. There are nineteen Chwezi, each with a function: earthquakes, rain, moon, et cetera. Some say the Chwezi are culture heros.

Chyavana (India) *see* Asvins; Mada.

Ciaga (Nicaragua, South America)
Water god. Under the rule of Tamagostad and Zipaltonal,

www.ebook3000.com

Ciaga shared in creation with Ecalchot, Quiateot, Misca, Chiquinau, and Vizetot. *See also* Chiquinau; Ecalchot; Quiateot; Vizetot; Zipaltonal.

Cian *Kian* (Celtic)
Minor sun deity. Later an evil deity. Cian, a shepherd, is the son of the divine physician, Dia'necht, and the father of Lugh by Ethlinn the moon goddess, who is the daughter of Balor. Cian permitted Gavidjeen, Go's cow, to return to Balor, its former owner. With the aid of the sea god, Manannan Mac Llyr (Manannan Mac Lir), he reached Balor's abode in the underworld of the sea (some say an island). Here he met Ethlinn, who had been locked in a tower by her father. They slept together and Lugh was born of their union. Cian deserted her with the cow and child in tow. Again, Manannan Mac Llyr rescued him, but now demanded compensation. Cian gave him his son, Lugh, whom the sea god raised to become the sun hero. Some time later, Cian noticed his enemies approaching: the three sons of Tuirenn (Brian, Iuchar and Iucharba). Magically, he turned himself into a pig. When they realized what he had done, they changed into hounds and gave chase, overcame, and killed him. They attempted to bury him six times but only on the seventh attempt did he stay under the ground. His son Lugh found the body and vowed vengeance. An addendum to this myth tells of Cian as a druid later in life. Evil, he delighted in changing his pupils, the children of Tuirenn, into hares and pursuing them as a hound. They banded together, struck him with his staff, thus causing Ireland to divide into the North and the South. For comparison *see* Danae and Zeus. *See also* Balor; Dia'necht; Lugh; Manannan Mac Llyr; Tuatha De Danann.

Cibola, The Seven Cities of (Aztec People, Mexico)
Also known as: *Chicomoztoc* (possibly).
In legend, the Seven Cities of Cibola are the cities from which the Aztec People originated.

Cigfa (Celtic) *see* Pryderi.

Cihauteto *Cihuateteo* (Aztec People, Mexico)
Also known as: *Cihuacoatl* (possibly).
The Cihauteto are five women who died in childbirth. They became demon goddesses who return to earth in terrible form to frighten humans. They are known to linger around crossroads.

Cihuatcoatl *Cihuacoatl, Ciuacoatl* (Aztec People, Mexico)
Also known as: *Ilamatecutli, Itzpapalotl, Quilaztli, Tamazcalteci, Teteoinnan, Tlaltecuhtli, Tlatecutli, Tonantzin.*
"Women Snake." Mother goddess. Earth goddess. Goddess of childbirth. She is the mother of Mixcoatl. She often comes to earth to weep at the crossroad market where she abandoned her infant son. Instead of finding her son, she finds a sacrificial knife. *See also* Ciuateteo; Ilamatecuhtli; Itzpapalotl; Tlaltecuhtli; Tonantzin.

Cihuateteo (Aztec People, Mexico) *see* Cihauteto.

Cilix (Greek)
His parents are King Agenor and Telephassa or Argiope. *See also* Agenor (A).

Cilla (Greek)
She is the daughter of the King of Troy, Laomedon, and Strymo, who is the daughter of the river god Scamander (also known as Xanthus). *See also* Hesione; Scamander.

Cin *Cinni* (Turkey)
One of a group of spirits known as Onlar, the Cin are spirits who can cause insanity, paralysis, or other illnesses. Shape-changers and tricksters, the Cin can appear visible or invisible. Certain prayers or curses can keep the individual safe from their evils.

Cinni (Turkey) *see* Cin.

Cintamani *Chinta-Mani* (Hindu; India)
Also known as: *Divya-ratna* (Divine Jewel), *Pearl of Price.*
The wish-granting gem, made by Brahma, that contains all of the world's knowledge. *See also* Kshitigarbha; Ratnasambhava.

Cinteotl *Centeal, Centeotl* (Aztec, Toltec People, Mexico)
Also known as: *Cexochitl, Chiutcoatl, Cihuatcoatl, Tonacajoha, Tzinteotl.*
God of maize. Grandson of "Our Grandmother," Toci. He is depicted as a young man with a yellow body. A jagged black line moves down his brow, across his cheek, and down to the base of his jaw. He often has maize in his headdress or maize growing from his head. *See also* Cihuatcoatl; Lords of the Night Hours; Tlazolteutl; Tzinteotl; Xilonen.

Cinvat (Persia) *see* Chinvat Bridge.

Cinyras (Greek)
His lineage is uncertain. He could be the son of Sandorcus of Syria, or of Paphus, Apollo, or Pygmalion. Cinyras was the king of Paphos in Cyrus, he was wed to either Cenchreis or Metharme. His children are Adonis and Myrrha. (There is a possibility that Myrrha is Adonis' mother.) His other children are Braesia, Laogore, Mygdalion and Orsedice. Cinyras, a suitor of Helen, did not go to the Trojan War. Instead, he promised Agamemnon that he would send fifty ships. Forty-nine of the ships were made of clay. The fiftieth ship was commanded by Cinyras' son Mygdalion. After an incestous relationship with his daughter Myrrha, Cinyras committed suicide. *See also* Adonis; Agamemnon; Cenchreis; Helen.

Cipactli (Aztec People, Mexico)
Also known as: *Coxcox, Coxcoxtli, Huehuetonacacipactli* (Fish God; "Old Fish God of our Flesh").
"Crocodile." Fish god. Sea monster. Cipactli is another name for Coxcoxtli (q.v.). *See also* Legend of the Four Suns; Tiamat.

Cipactonal *Cipactli, Cipattoval* (possibly) (Aztec People, Mexico) *see* Omeciutal.

Cirape (Crow People, North America)
Also known as: *Little Coyote.*
He is the younger brother of the Trickster.

Circe *Kirke* (Greek)
Also known as: *Aeaea, Angita* (Italian), *Marica* (Roman).
"The Enchantress." Sorceress. She is the daughter of the sun, Helios, and the Oceanid, Perse, and the sister of Aeetes, Pasiphae

and Perses. Her first marriage was to Odysseus. Their children are Ardeas, Agrius and Telegonus (some say she was the mistress of Odysseus and had only one son by him). Her second marriage to Telemachus produced a son, Latinus (some say he is the son of Odysseus). She is also the mother of Comus by Bacchus. Her charms enticed men and her use of sorcery changed them into swine. Circe, madly in love with Glaucus, poisoned Scylla and turned her into a monster. Circe dwells alone in the western island of Aeaea, denoting the setting sun. Her visitors are changed into animals. Aeaea is one of two islands of the same name. Aeetes' abode was the eastern island, denoting the rising sun. *See also* Aeetes; Angita; Calypso; Glaucus; Helius; Oceanids; Odysseus; Pasiphae; Perses; Skylla.

Cisa *Ciza Zisa* (German)
Possibly a harvest goddess as her festival was September 28.

Cissos (Greek) *see* Dionysus.

Cit-Bolon-Tum (Maya People, Yucatan)
Also known as: *Boar with the Nine Tusks.*
God of medicine.

Citalicue (Aztec People, Mexico)
A name of the "God of All Existence." *See also* Tloquenahuaque.

Citlalatonac *Citlallatonac* (Aztec People, Mexico) *see* Nata and Nena.

Citlalinicue *Citlalicue* (Aztec People, Mexico) *see* Nata and Nena.

Ciuacoatl (Aztec People, Mexico) *see* Cihuatcoatl.

Ciuateteo *Cihuateteo, Ciuapipiltin* (Aztec People, Mexico) *see* Cihuateto; Tlaloc; Tlalocan; Xolotl.

Ciza (German) *see* Cisa.

Cleio (Greek)
Muse of history. She is one of the nine Muses. Her symbols are a wreath of laurel and a scroll. She is often shown with Cadmus, holding a writing implement. *See also* Cadmus; Muses.

Cleite (Greek)
She is the daughter of Meropes, the king of Percote. Her siblings are Adrastus, who was killed in the Trojan War by Diomedes; Arisbe, who was the first wife of Priam and the mother of Aesacus; and Amphius, who was also killed in the Trojan War by Diomedes. *See also* Adrastus; Danaus; Diomedes.

Cleitus (Greek)
He is the son of Mantius and brother of Polypheides. Eos, the goddess of dawn, fell in love with his beauty and abducted him. *See also* Boreas; Eos.

Clemenus (Greek) *see* Phaethon.

Cleodora (A) (Greek) A Danaid. She is one of the fifty daughters of Danaus. *See also* Danaid; Danaus.

Cleodora (B) (Greek)
She is the nymph mother of Parnassus by the sea god, Poseidon.

Cleolla (Greek)
Cleolla is the spouse of Pleisthenes, the king of Argos and Mycenae, and the mother of Anaxibia, and possibly Agamemnon and Menelaus. *See also* Agamemnon.

Cleone (Greek)
The river god Asopus is her father and Metope is her mother. *See also* Asopus; Metope.

Cleopatra (A) (Greek)
Her parents are the north wind, Boreas, and Oreithyia, the daughter of Erechtheus and Praxithea. *See also* Althea; Boreas; Danaus; Harpies; Phineus; Zetes.

Cleopatra (B) (Greek)
She is the daughter of Idas and Marpessa, the wife of Meleager and the mother of Polydora. *See also* Meleager; Polydora.

Cleopatra (C) (Greek)
One of the fifty daughters of Danaus known as the Danaids. *See also* Aegyptus; Danaids; Danaus.

Cleopatra (D) (Greek)
Her parents are Tros, the son of Erichthonius and Astyoche, and Callirrhoe, daughter of the river god, Scamander. *See also* Callirrhoe; Ganymedes; Scamander.

Cleopatra (E) The name of seven queens of Egypt.

Cleostratus (Greek)
His lover was a young man from Thespiae named Menestratus who saved him from being eaten alive by a dragon who attacked people in the area every year.

Cleta (Greek) *see* Graces.

Clio (Greek)
She is the mother of Hyacinth by Pierus. *See also* Muses.

Cloacina (Roman)
Also known as: *Venus.*
Underworld deity. This goddess looks after sewers. In ancient times, she was in charge of the sewers of the Cloaca Maxima which drained the Forum. *See also* Caca.

Clotho *Klotho* (Greek)
Goddess of fate. Clotho is the youngest of the three Moirai. Called the Spinner, she spins the thread of life. Her parents are Zeus and Themis. Her sisters are Lachesis and Atropos. *See also* Ariadne; Atropos; Fates; Moirai; Themis.

Clothru (Celtic, Irish)
Fertility goddess. Clothru and Ethne.were the wives of Conchobar after Medb left him. She is known as the sister of Bres, Ethne, Lother, Medb, and Nar. In some renditions, Clothru is the wife of Cian.

Curacan (Celtic, Irish) *see* Cluricaune.

Cluricanes (Celtic)
Depicted as wrinkled, old men, these elves are known for their knowledge of hidden treasure. *See also* Dulachan; Elves.

Cluricaune *Cluracan* (Celtic, Irish)
Wine deity. Cluricaune is similar to the Leprechaun, but is

www.ebook3000.com

Iron Shirt Chi Kung also includes the art of ‘Changing the Sinews and Washing the Marrow’. Through these aspects of Iron Shirt, you learn to absorb, store and discharge large amounts of energy through the tendons and bones. *These practices are outlined in detail in the books “Iron Shirt Chi Kung” by Mantak Chia and “Bone Marrow Nei Kung” by Mantak Chia.*

To attain skill in Cosmic Chi Kung, it will help if you practice Iron Shirt, Bone Marrow and meditation as a minimum requirement. Beyond the basic level, the Universal Tao System includes many other intermediate and advanced level Chi Kung practices and meditations. The further one advances, the greater one's mastery of Chi.

Your increasing level of skill in the Universal Tao system will reflect immediately in your Cosmic Healing Chi Kung practice. Furthermore, you will discover that you can incorporate many of your Universal Tao practices directly into your practice of Cosmic Chi Kung. We will give you a simple combined practice of the Cosmic Healing Chi Kung, the Inner Smile, Microcosmic Orbit, Iron Shirt and the Sexual practices.

Stages of Mastering Chi

1. In the Universal Tao system, our *first* goal is to learn to conserve our Chi; when a battery is totally drained it is harder to charge; money makes money, Chi makes Chi. Conservation of Chi will help gain more Chi. To have more Chi we first need to maintain control of the gates through which energy normally leaks out and unwittingly drains our life force.

We leak energy: - through our reproductive system
- through negative emotions
- through constantly turning our senses outward

Without knowing how to conserve the Chi that we already have, what is the point of acquiring more?

2. We learn to balance our Chi; that is, we seek to keep a smooth and balanced flow of energy moving throughout the whole body. If our energy is imbalanced, we may have too much energy in some places and not enough in others; we may also be too yang or too yin. We may have excess or deficient heat, cold, damp or dryness. This imbalanced energy tends to make us go to extremes.

3. We learn to transform our Chi into more beneficial energies. For example, through the Taoist Sexual Chi Kung practices taught in the Universal Tao (the course known as Healing Love through the Tao), we can transform sexual energy back into basic life force Chi. Through other practices (such as the Inner Smile, the Six Healing Sounds, and Fusion of the Five Elements) we learn to transform negative emotional Chi into positive virtuous Chi. Thus Chi is not only the foundation of our health; it is also the basis of spiritual development in the Tao.

4. Once we have accomplished the three previous phases of mastering Chi, we then learn to increase it. Chi pervades all of heaven, earth and nature. In Cosmic Healing associated with the caring of wine or beer barrels. He is also a shoemaker like the Leprechaun. *See also* Leprechaun.

Clutoida (Celtic) Goddess of the river Clyde. *See also* Sequana.

Clymene (A) (Greek)
She is the daughter of the extremely wealthy Minyas. *See also* Alcimede; Atalanta; Cephalus; Periclymene.

Clymene (B) (Greek)
Her parents are Oceanus and Tethys. She married Iapetos and became the mother of Atlas, Epimetheus, Monoetius and Prometheus. *See also* Epimetheus; Heliades; Minyas; Oceanids; Oceanus; Phaethon; Tethys; Themis.

Clymene (C) (Greek) She is one of the fifty daughters of Nereus and Doris known as the Nereids. *See also* Doris; Nereids; Nereus.

Clymene (D) (Greek) Catreus, the king of Crete, is her father. Her siblings are Aerope, Althaemenes and Apemosyne. *See also* Aerope; Catreus.

Clymenus (A) (Greek) He is the father of Eurydice. *See also* Eurydice (C).

Clymenus (B) (Greek) His father is Aeneas, king of Calydon.

Clymenus (C) (Greek)
King of Olympia. Fifty years after the flood, he went to Crete. Clymenus restored the Olympic Games.

Clymenus (D) (Greek) King of Arcadia.

Clymenus (E) (Greek)
King of Boeotian Orchomenus. His father is Presbon. Clymenus was killed in a fight with the Thebans. His death was avenged by his son, Erginus.

Clytemnestra (Greek) *see* Aegisthus; Cassandra; Helen; Leda.

Clytia *Clytie* (Greek)
Clytia, an Oceanid, is one of the three thousand daughters and three thousand sons of Oceanus and Tethys. She was the spiteful lover of the sun god Helius who informed King Orchamus of Persia, the father of Leucothoe, that the sun god was sleeping with his daughter. He punished her by burying her alive. The rejected Clytia withered away and became a flower, the heliotrope. In another myth, Clytia was the devoted lover of Apollo. Whenever the god would abandon her she would transform herself into a heliotrope. Heliotropes turn their heads to follow the journey of the sun through the sky each day. *See also* Apollo; Helius; Hyacintos; Oceanids.

Clytie (Greek)
Another name for Merope, the daughter of Pandareus and Harmothoe.

Clytius (Greek) *see* Giants; Hesione.

Cmok (Slavic) *see* Zmek.

Coatepec (Aztec People, Mexico)
"Serpent Mountain." The dwelling place of Coatlicue (q.v.).

Coatlicue *Couatlicue* (Aztec People, Mexico)
Also known as: *Tlazoltoeotl, Tonantzin, Serpent Lady* (sometimes called this name), *Serpent Petticoated, Serpent Skirt.*
"Serpent Skirt." Mother goddess. Earth goddess. She is the mother of a daughter, Coyolxauhqui, and four hundred sons known as the Centzon Huitznahuas. Coatlicue is one of the spouses of Mixcoatl. One day, when she was sweeping, a ball of feathers fell into her bosom. She became pregnant. Her four hundred sons and her daughter were so outraged they decided to murder her. As they were about to put Coatlicue to death, the new child Huitzilopochtli came out of his mother's womb, fully clad in armor. He killed both his sister and brothers with a serpent weapon called Xiuhcoatl. It is said that a few of his brothers escaped to Uitzlampa "Place of Thorns" in the south. Coatlicue's dwelling was on Coatepec mountain. She is presented as the crocodile Cipactli or as a giant frog. *See also* Centzon Huitznahuas; Chicomecoatl; Legend of the Four Suns.

Coatrischie (Haiti)
Hurricane goddess. *See also* Atabei; Guabancex.

Cocalus (Greek) *see* Minos.

Cocidius (British)
Also known as: *Alator, Albiorix* (Celtic), *Belatucador, Camulus, Condates, Coritiacus, Loucetius, Rigisamos* (Celtic), *Totates.*
War god. Cocidius was also worshiped under the above names. He is identified with Mars.

Cockatoo Man (Australia) *see* Mars.

Cocytus *Kokytus* (Greek)
Also known as: *The Wailing River.*
River god. As a river god, Cocytus is one of the three thousand sons (the Rivers) and three thousand daughters (the Oceanids) of Oceanus and Tethys. He is said to be the father of Menthe, who was discovered in a compromising situation with Aides, the son of Cronus and Rhea and she was changed into a mint plant by the jealous goddess Persephone. As a river, the Cocytus is a tributary of the river of sadness, the Acheron, in Epirus. The echoes of unburied souls are doomed to wander along the banks of the Cocytus wailing and groaning for one hundred years after death. If properly buried and with the correct fare, dead souls are allowed to board the boat of the ancient boatman Charon, who will ferry them across the river. The other rivers of the Underworld are the Phlegethon (river of fire), Lethe (river of forgetfulness) and Styx (river of the unbreakable oath). To compare to other river gods, *see* Achelous; Acheron; Alpheus; Asopus; Cephissus; Charon; Cronus; Erebus; Hades; Inachus; Lethe; Oceanids; Rivers; Styx; Tartarus. *See also* Cronus; Persephone; Rhea.

Coeculus (Greek, Roman) *see* Cacus.

Coelus (Greek) *see* Uranus.

Coem (Tupi-Guarani People, Brazil) *see* Hermitten.

Coeranus (Greek) *see* Abas (B).

Coeus (Greek) *see* Ceos.

Cogaz (Bushman, Hottentot People, Africa)
The son of Cagn and brother of Gewi, he is possibly a creator deity. *See also* Cagn.

Colhuacan (Aztec People, Mexico)
Emergence myths. *See also* Chicomoztoc.

Colhuatzincatl (Aztec People, Mexico)
One of the pulque gods, Colhuatzincatl is the son of Cinteotl. He is associated with the Centzon Totochtin. *See also* Patecatl.

Colla (Inca People, Peru) *see* Ayar Aucca; Manco Capac, Tahuantin Suyu Kapac.

Colossus of Rhodes (Greek) *see* Helius.

Comana (Greek) This is another name for Chryse (q.v.).

Combalus (Syrian)
God of vegetation. Knowing of his inevitable death and of his trip to the underworld, he rejected his earth goddess and castrated himself for the redemption of mortals.

Cometes (Greek)
He is the son of Sthenelus, brother of the king of Argos, Cylarabes, husband of Antigone, and father of Asterion. He committed adultery with Diomedes' wife, Aegialeia. *See also* Asterion; Diomedes; Sthenelus.

Comus *see* Bacchus; Circe.

Con (Inca People, Peru) *see* Coniraya.

Con Ticci Viracocha (Inca People, Peru) *see* Virocacha.

Con Ticci Viracocha Pachayachachic (Inca People, Peru) *see* Virococha.

Conaire, King (Celtic) *see* Dagda.

Conchean (Celtic) *see* Aed.

Conchobar, King (Celtic) *see* Clothru; Cuchulain; Dech'tire.

Confucius (China, Japan)
Also known as: *Chi-Sheng Sien-Shi, Wen Chung.*
Deified mortal. Although debate still reigns as to whether Confucius is considered a god and worshiped as such, the fact is that most think he was a mortal. His religion (Confucianism, Fu Chiao) is that of the learned and is generally associated with scholars and officials. He is the grandfather of Tsi-si. According to some history Confucius was born in 551 B.C.E. and died in 479 B.C.E. Confucius is usually shown seated and wearing imperial costume. He is said to be a reincarnation of Wen Chung (q.v.).

Coniraya (Inca People, Peru)
Also known as: *Coniraya Viracocha.*
Supreme being. Creator of all things. Responsible for irrigation, and terracing the fields. Coniraya came to earth dressed in ripped and torn rags, like a begger. He was scorned by everyone. He came upon Cavillaca, a beautiful young virgin goddess. She was sitting under a lucma tree. Coniraya turned himself into a bird, fashioned his sperm in the likeness of the lumca tree's fruit and watched her eat it. She became pregnant and had a child. When the child was a year old she found out that the ragged Coniraya was the father. She was so full of shame and so angry that she took the child and ran off to the sea coast. When they arrived, mother and child walked into the water and became rocks. Coniraya went in search of Cavillaca and the child. Along the way, he encountered many adventures. When he finally reached the coast he found that they had turned to stone. While there he met Pachacamac's two daughters. He had sex with the eldest and then attempted to bed the younger woman. She apparently was not interested for she turned into a pigeon and flew away. Coniraya was so furious he took Urpihuachacs a few fish, which were the only fish in existence. He threw them into the sea. That is how fish came to populate the waters. *See also* Pachacamac; Viracocha.

Conopa (Inca People, Peru)
Also known as: *Huasi-Camayoc.*
Household deities. Little information is available about the Conopa. We do know that several thousand of these idols were destroyed by the Spaniards. *See also* Lars.

Consus (Roman)
Grain deity. Earth deity (possibly). Information is sparse regarding Consus. He is worshiped in the same month as Ops.

Coon (Greek) *see* Acamas (B).

Copacati (Inca People, Peru)
This lake goddess would not tolerate worship to other deities. She was known to have toppled temples or submerged them under the waters of Lake Titicaca. This lake is a few miles from the ruins at Tiahuanaco. With Mama Cocha, Copacati was a mother goddess of the lake. *See also* Mama Cocha.

Copreus (Greek) *see* Pelops.

Coqui-Xee (Mixtec People, Mexico)
Also known as: *Coqui-Cilla, Piye-Tao, Zapotec Quetzalcoatl.*
Creator deity. He is the creator of all things but himself uncreated. The Mixtec people were his first creation, followed by Cozaana, the deer god and Huichaana, the deer goddess. *See also* Mixcoatl.

Corb (Celtic) He is a god of the Fomonians (q.v.).

Corcyra (Greek) *see* Asopus.

Core (Greek) *see* Kore; Persephone.

Cori Ocllo (Inca) *see* Tahuantin Suyu Kapac.

Cornucopia *Cornu Copiae* (Greek)
Horn of Plenty. Under the secret care of the nymphs, the infant Zeus was suckled by the goat Amaltheia, whose horn he gave to the nymphs, endowing it with the power to be filled with whatever its possessor wished. According to another tradition, the cornucopia is Achelous' or Amalthea's broken horn which was filled with fruits and flowers by the Naiads. *See also* Achelous, Amaltheia.

Corona Borealis (Greek) *see* Ariadne.

Coronis (A) (Greek)
She is the Thessalian princess daughter of the king of

www.ebook3000.com

Orchomenus, Phlegyas, and the possible sister of Ixion, the King of the Lapiths of Thessaly. Apollo and Coronis had an affair that produced the great healer, Asclepius. Sometime later, she was unfaithful. As she prepared to marry Ischys, she was killed by Apollo or Artemis. *See also* Apollo; Artemis; Asclepius; Ischys.

Coronis (B) (Greek)
Coronis, the daughter of Coroneus of Phocis, was loved by Poseidon. Athena changed her into a white crow. After taking bad news to Athena, she was turned into a black crow by the fiery goddess.

Coronis (C) (Greek) She is the daughter of Ares.

Coronis (D) (Greek)
One of the Hyades, she is the daughter of Atlas and Pleione. *See also* Hyades.

Coronus (A) (Greek)
The son of Apollo and Chrysorthe, he was the king of Sicyon until Epopeus, the son of Poseidon and Canace, deposed him. *See also* Antiope; Epopeus.

Coronus (B) (Greek)
An Argonaut and leader of the Lapiths, Coronus, the son of Caeneus and father of Leonteus and Lyside, was killed by Heracles.

Corus (Greek)
Weather god. Known as the northwest wind, Corus is the son of Aeolus and Aurora. Wherever he goes, he drives clouds of snow before him. His five brothers are Aquilo, Boreas, Eurus, Notus and Zephyrus. *See* the individual entries for information about these brothers. *See also* Aeolus.

Corybantes *Korybantes, Kurbantes* (Phrygian)
Also known as: *Curetes; Galli.*
Known as the crested dancers and sometimes called divine, the priests, known as Corybantes, worship the Phrygian goddess Cybele in wild frenzied dances during which they clash spears and shields. They are thought to be the children of Apollo and Thalia or Athena, Zeus and Calliope, or Corybas or Cronus and Rhea. Ovid calls them people born of rainwater. The Corybantes rites are similar to the Satyrs who attend Dionysus. *See also* Adrastia; Curetes; Cybele; Helius; Rhea; Satyrs.

Corybas (Greek) *see* Corybantes; Cybele.

Corynetes (Greek) Another name for Periphetes (q.v.).

Cosmocrator (Gnostic) The devil.

Cosmology of Assur (Sumerian)
A myth that mentions the birth of the first two ancestors of mankind, Ulligarra and Zalgarra, from the blood of the gods known as Lamga.

Coti (Hottentot People, Africa) Another name for Cagn (q.v.).

Cottus *Cotus, Cottys, Kottos* (Greek)
Nature deity. One of three brothers known as the Hecatonchires. They fought on the side of Zeus in the war with the Titans. They each have fifty heads and a hundred hands. *See also* Aegaeon; Gaea; Hecatonchires; Titans.

Cottys (Greek) *see* Cottus; Hecatonchires.

Cotus (Greek) *see* Cottus; Hecatonchires.

Cotzbalam (Maya People of Yucatan)
Demon. The gods, dissatisfied with the men they had created with various materials, destroyed them by a flood. Cotzbalam assisted by devouring their flesh. *See also* Camalotz; Xecotcovach.

Couatlicue (Mexico) *see* Coatlicue.

Couretes (Greek) *see* Curetes.

Coventina (Celtic) *Covetina* (British)
Goddess of springs and waters. This water goddess is depicted holding a goblet in one hand as she lies comfortably on a leaf that floats on the water.

Covetina (British) *see* Coventina.

Coxcos (Aztec People, Mexico) *see* Coxcoxtli.

Coxcox *Cox-cox* (Aztec People, Mexico) *see* Coxcoxtli.

Coxcoxtli *Coxcos, Cox-cox, Coxcox, Kox* (Aztec People, Mexico)
Also known as: *Teo-Kipaktli, Tezcatlipoca.*
First man, survivor of flood. Husband of Xochiquetzal. The Aztec Noah. Some say their names were Nala (male) and Nina (female) or Nata and Nana. They escaped the flood (in a hollowed out tree) that destroyed all mankind and lived on the mountain, Colhuacan. Their children, who were dumb, were given speech by a dove but could not understand each other because all the languages were different. *See also* Cipactonal. This tale is similar to that of Nata and Nana (qq.v.). Associated with Tezcatlipoca, Citlallatonac and Citlalicue. *See also* Xochiquetzal.

Coyolxauhqui (Aztec People, Mexico)
Also known as: *Golden Bells, Tecciztecatl* (god of the moon).
Moon Goddess. She is the only daughter of Coatlicue. Her four hundred brothers are the Centzon Huitznahuas. With her brothers, she plotted to murder her mother who had been divinely impregnated with Huitzilopochtli. He emerged from his mother's womb fully dressed in battle gear, intent upon revenge. Coyolxauhqui was decapitated, and he threw her head to the sky where it became the moon. Some say her death was an accident, then in remorse he cut off her head. Huitzilopochtli killed most of his four hundred brothers. Coyolxauhqui replaced the moon god, Tecciztecatl. *See also* Centzon Huitznahuas; Coatlicue; Huitzilopochtli; Meztli; Tecciztecatl; Yohualticitl.

Coyote (Native North Americans)
Also known as: *Ola'li* (Maidu People, N.A.), *Sedit* (Wintun people), *Ueuecoyotl* (Aztec People, Mexico).
Coyote appears with many faces. He can be a creator or a teacher of the people. In some myths, Coyote is a cunning and creative trickster god, or folk-hero. He can appear with both attributes in the same story. Coyote is worshiped by numerous Indian People. He may be a god of dancers. In one myth, he

created the earth and all living creatures. He built a boat in which he drifted while the earth was covered with water. He then told two ducks to dive and bring back mud. One duck did not return, the other did what he was told. Coyote created earth from this mud. Sihu, the elder brother of Coyote, is identified with Montezuma. In a Maidu myth, Ola'li came out of the ground with his dog Kaudi (So'lla) or Rattlesnake. In legends of the Achomawi People of California, their creator emerged from a small cloud. The creator was assisted by Coyote who emerged from a mist over the land. The Zuni people say that Coyote taught them to live in peace. The Chemchuevi tell of Coyote and Puma creating man. The Crow people credit Coyote and his brother Cirape for creating the earth and everything on it. In the mythology of the Navaho, man and woman lived in the first world which was too small. They moved up to the second world, left it and went to the third world. This world was the home of the water monster Tieholtsodi. Coyote kidnapped the monster's children. Tieholtsodi retaliated by flooding the world. Coyote, the first man, and the first woman went up to the fourth world. The water monster followed them. They moved on to the fifth world which is our present world. Coyote finally returned Tieholtsodi's children. After death, people returned to the fourth world. The Poma People call Coyote the younger brother of the creator god, Madumda. Coyote is similar to Xolotl of the ancient Mexican people. *See also* Cirape; Italapas; Olle; Ueuecoyotl.

Cranaus (Greek) *see* Cronus.

Crantaeis (Greek) *see* Hecate.

Crataeis (Greek) *see* Phorcys; Scylla.

Cratus (Greek) *see* Styx.

Credne *Creidne, Creidhne* (Celtic)
God of Artificers and Braziers. Credne is a Tuatha De Danann, an ancient race of gods. One of the triad of divine craft-smith gods, his specialty was metal work. With his companions, Goibniu and Luchta (also known as Luchtaine), they forged the weapons used by the Tuatha De Dananns in the war known as the First Battle of Magh Tuiredh, against the evil Fomorians. Their weapons came with the guarantee that whomever was wounded by them would not survive. Credne also assisted the divine physician, Dia'necht, in forging an artificial hand for king Nuada. The Celts held the smiths in high esteem, as they were thought to possess magical abilities to heal through charms, spells and the implements they produced. These implements, weapons, ploughs and utensils were vitally important to their existence (not to be confused with Creidne, an Irish female warrior). Compare with the Greek metal workers, Dactyli. *See also* Dia'necht; Goibniu; Hephaistos; Tuatha De Danann.

Cree People, Canada — Creation Legend *see* Wisagatcak.

Creiddylad (Celtic)
Another name for Creudilad (q.v.). *See also* Llyr.

Creidhne (Irish) *see* Credne.

Creidiylad (British, Irish) *see* Creudilad.

Creidne (Irish) *see* Credne.

Creirwy (Celtic)
She is the beautiful daughter of Keridwen and sister of an extremely ugly brother Avagdu. *See also* Keridwen.

Crenae (Greek) *see* Naiads.

Creon (Greek) *see* Adrestus; Antigone; Ares; Eurydice (C).

Creseusa (Greek) *see* Creusa (A); Glauce.

Cresphontes (Greek) *see* Aepytus.

Cressida (Greek) *see* Calchas.

Crete (Greek) *see* Europa.

Cretheus (Greek)
He is the founder and first king of Iolcus. His parents are Aeolus and Enarete. He has six brothers and seven sisters (for a list of their names *see* Canace). His first marriage was to Sidero, his second to Tyro and the third to either Demodice or Biadice. *See also* Aeolus (A); Aegimius; Enaret; Tyro.

Creudilad *Creiddylad, Creidiylad, Creudylad* (British, Irish)
Goddess of spring. Part of a trio with Gwyn (sun god) and Gwyrthur (underworld god). She is the daughter of Llud, or some say Llyr. *See also* Gwinn.

Creudylad (British, Irish) *see* Creudilad.

Creusa (Greek)
There are numerous references to the name Creusa in Greek mythology. See the following entries.

Creusa (A)
Also known as: *Creseusa.*
Creusa and Glauce burned to death with her father Creon. *See also* Danaus; Glauce; Jason; Medea.

Creusa (B) A Nereid. *See also* Nereids.

Creusa (C) A Danaide. *See also* Aeneas; Danaides.

Creusa (D) A Naiad. *See also* Naiads.

Creusa (E)
Daughter of Priam and Hecuba, captured by the Greeks, rescued and disappeared. *See also* Hecuba; Priam.

Creusa (F)
Daughter of Erechtheus, married Xuthus, raped by Apollo and gave birth to Janus. *See also* Janus.

Creusa (G)
May be the mother of Telamon. *See also* Creusa (A); Danaus; Medea; Telamon.

Criasus (Greek)
His parents are Argus and Evadne. *See also* Argus (A); Evadne.

Crimisus (Greek)
River god. He is the son of Oceanus and Tethys. His spouse is Egesta, the daughter of Hippotes, and his son, Acestes. *See also* Acestes; Oceanus; Rivers; Tethys.

www.ebook3000.com

Crino (Greek)
She is the daughter of Antenor, the Trojan prophet, and Theano, who is the priestess of Athena at Troy. *See also* Acamas (B).

Crius *Crios* (Greek)
Crius was the Titan son of Uranus and Gaea and sibling of Thaumas, Phorcys, Ceto, Eurybia and Nereus. He married his sister Eurybia and was the father of Astraeus, Pallas and Perses. *See also* Cronus; Eurynome (A); Gaea; Nereus; Oceanus; Phorcys; Pontus; Styx.

Crnobog (Slavic)
Also known as: *Crnoglav.*
Underworld deity. The black god of the dead.

Crnoglav (Slavic) *see* Crnobog.

Crocodile (Egypt) (Greek) *see* Centipede; Helios; Horus; Suchos.

Crom-Eocha (Celtic) *see* Dagda.

Crommyonian Sow (Greek)
Also known as: *Phaea.*
The daughter of Typhon and Echidna, this feral sow raped the Corinth countryside. She is possibly the mother of the Calydonian Boar. She eventually died at the hand of the hero Theseus, the king of Athens. *See also* Calydonian Boar; Cerberus; Chimaera; Hydra; Typhon; Vultures.

Cronos (Greek) *see* Cronus.

Cronus *Chronos, Cranaus, Cronos, Khronos, Kronos* (Greek)
Also known as: *Saturn, Saturnus* (Roman).
God of the World. God of Time. High God. Harvest God. A Titan, Cronus is the son of Uranus, who personifies the Sky, and Gaea, the Earth. He is the father, by his sister, Rhea (who is known as the mother of the gods), of Zeus, Poseidon, Hades, Hestia, Demeter, and Hera. Some versions give him eleven brothers and sisters: Oceanus, Coeus, Crius, Hyperion, Iapetus, Theia, Rhea, Themis, Mnemosyne, Phoebe, and Tethys. He was also the possible father of the Centaur, Cheiron, by Philyra. Encouraged by his mother, he overthrew and castrated his father. From this point, the heavens and earth (creation) continued to develop separately. Cronus, now the supreme ruler, released his brothers, the Titans, with the exception of the Hecatoncheires and the Cyclopes. Next, he swallowed his offspring to prevent his sons from overthrowing him. His wife, Rhea, however, hid the young Zeus from him. When he was older, Zeus rebelled and Cronus was induced to vomit up his other children, who joined with Zeus in a war against their father and some of his Titan colleagues. Zeus also released the Hecatoncheires and the Cyclopes, flung his father and friends into Tartarus, the lowest realm of the Underworld, where the Hecatoncheires guarded them. With this act, the era of the Olympians began, followed by the war of the Olympians against the Titans. Another tradition calls the rule of Cronus the "Golden Age," where death did not exist and all mortals lived like gods. When his reign in Olympus ceased, he went on to become king on the Islands of the Blessed where mortals, favored by the gods went at death. Some believe he was a deified king who had a son named Anobret, whom he sacrificed and he also may have had a son named Aides. The Orphics said that Aether and Chaos sprang from Cronus as Time. In the Pelasgian creation myth, Cronus is coupled with Rhea as the rulers for the planet Saturn. For the development of the heavens during this period, *see* Nox. Sometimes he is identified with the Egyptian god Geb. Compare to Agni (India). Compare to Indra (India). *See also* Adrastia; Ceos; Cocytus; Corybantes; Curetes; Eumenides; Eurynome (A); Gaea; Hecatoncheires; Hestia; Nut; Oceanus; Rhea; Styx; Telchines; Zeus.

Crow (Tlingit People, North American)
By beating his wings, Crow created dry land. He also gave light or fire. Compare to Coyote.

Cteatus (Greek)
He is the son of Actor or Poseidon and Molione. With his twin Eurytus (they are possibly Siamese twins), they are known as the Molionides. *See also* Actor (B).

Cu (Celtic)
He is the son of the god of medicine, Dia'necht (q.v.).

Cu Chulain (Celtic) *see* Cuchulain.

Cuchavira *Chuchaviva* (Chibcha People, Bogota, South America)
Also known as: *The Rainbow.*
God of air. Part of the Bochica mythology. He was master of the air and rainbow and healer deity. He protected women in childbirth. He was not greatly respected since he was also a god of drunkenness and a protector of drunkards. He is possibly the same as Nencatacoa (q.v.). *See also* Bochica.

Cuchaviva (South America) *see* Bochica; Chia.

Cuchu'lainn (Celtic) *see* Cuchulain.

Cuchu'linn (Celtic) *see* Cuchulain.

Cuchulain *Chuchulain, Cu Chulain, Cuchu'lainn, Cuchulainn, Cuchu'linn, Cuchullin, Culain, Culann, Koo-chul-inn* (Celtic)
Also known as: *Setanta, Hound of Chulain, Watchdog of Chulain.*
God of heat and light. He is the son of Lugh, the sun god, and the mortal woman Dech'tire, who was the wife of the prophet Sualtim (also said to be of virgin birth) and the sister of King Conchobar of Ulster. He is the spouse of Emer. Cuchulain is immune to most magic spells. The witch Scatbvach, "Queen of Darkness," taught him magic. He was known throughout Ireland as a fearless warrior and a great lover. He received his name when he killed the watchdog of Conchobor, and offered to take the dog's place. One version of his birth says he was born three times, and is sometimes shown with three heads. Fergus and Cathbad taught him wisdom, courage, and warfare. Amergin prepared him for his special role in society, then Scatbvach taught him sorcery. Cuchulain has seven pupils in each eye, seven fingers on each hand and seven toes on each foot. His hair is three colors and he wears a lot of jewelry. In battle he changes shape drastically; his feet and knees are to his rear and his calves and buttocks to the front. His hair stands on end and on the tip of each strand was a spot of blood or a spark of fire. His mouth spews fire and a long stream of black blood shoots up from his head. One eye is pushed to the rear of his

skull and the other sits on his cheek. On his forehead there is a marking known as the "hero's moon." In this stage he cannot be contained and has to be doused in three tubs of cold water to keep him quiet. *See also* Amergin; Blathnat; Curoi Mac Daire; Dechter; Dech'tire; Devorgilla; Fand; Lugh; Manannan Mac Llyr; Morrigu.

Cuculcan (Mexico) *see* Kukulcan.

Culain (Celtic) *see* Cuchulain.

Culann (Celtic) *see* Cuchulain.

Cupara (Jivaro Indian People, Andes, South America)

Parents of the sun, Cupara and his spouse made the moon from mud. The moon became the wife of the sun. Their children were the animals and the tropical plant manioc. The ancestor of the tribe was the sloth.

Cupid *Cupido* (Roman) *see* Amor; Brigit; Eros.

Cupra (Etruscan)

An ancient goddess of fertility, she formed a triad with the fire god Tina and the goddess of wisdom, Minerva. Her weapon is the thunderbolt. *See also* Juno; Minerva; Tina.

Curche (Slavic) *see* Kurke.

Curetes *Couretes, Kouretes* (Greek, the aborigines of Aetolis)

Also known as: *Corybantes, Gegeneis* (children of the earth), *Imbrogeneis* (children of the rain), *Korubantes, Korybantes.*

The origins of the Curetes varies. They are said to be the children of Poseidon and Thalassa or Hecaterus and a daughter of Phoroneus. It is also thought that they might be descendants of Hephaestus, or descendants of the Semites or the most ancient people of Crete. One of their functions was to create a great deal of noise so Cronus would not hear the cries of the infant Zeus (the child Kouros) when Rhea gave birth in Crete. In one version, Hera ordered Zeus to put the Curetes to death for hiding his son by Eo, Epaphus. Some say they were priests attached to the worship of Cybele. An inscription was found in Crete, at Palaiokastro, containing the "Hymn of the Curetes," in honor of Zeus. The uproar made by Curetes, with their dancing, clashing of cymbals and swords in the Corybantic and Dactylic worship is similar to the "devil scaring" techniques practiced by the Chinese and other races in attempts to drive away the powers of evil by making noise. Other references state that the Curetes were the sacred king's armed companions. The Greek interpretation was "young men who have shaved their hair." At an annual feast called Comyria, the Curetes shaved their hair to honor Car, the solar king whose hair was shorn annually before his death. In this context they were known as Corybantes. This custom might be of Libyan origin. They are associated with Castor and Pollux, and the Corybantes. Dardunus founded a college of Salian priests who performed the same rites as the Cretan Curetes. Compare the Curetes to the Vedic Maruts. *See also* Adrastia; Althea; Apollo; Artemis; Calydonian Boar Hunt; Car; Cybele; Satyrs; Telechines.

Curicaveri (Tarascan People, Mexico) *see* Camaxtli; Huitzilopochtli.

Curoi Mac Daire (Celtic, Irish)

Curoi was a the King of Munster, and a priest of the sun god. He married King Mider's daughter, Blathnat. He was entrusted with guarding Mider's magic cauldron. His wife assisted Cuchulain in stealing it from him. When the Tuatha de Danann were defeated, Curoi was killed by Cuchulain, who became his successor. *See also* Blathnat; Cuchulain; Mider; Tuatha de Danann.

Curupira *Korupira* (Brazil)

This forest demon is known for his mischief making and his love for tobacco. A guardian spirit of the woods, he assists hunters in their search for game. Curupira has one eye, large ears and is bald. He rides a pig or a deer.

Cusco Huanca (Inca People, Peru) *see* Tahuantin Suyu Kapac.

Cuycha (Inca People, Peru)

A rainbow deity, Cuycha is one of Mama Quilla's attendants. Cuycha is associated with Catequil.

Cuzco (Inca People, Peru)

Sacred City. Originally Cuzco was thought to be the center of the earth. It was sought by the legendary family migrating to the east in prehistoric times. Cuzco is the home of Manco-Capak and his sister Mama Occlo.

Cyane (A) (Greek) She is the wife of Aeolus. Her six sons and six daughters married each other. *See also* Aeolus (B).

Cyane (B) (Greek)

Assaulted by her father, this nymph then offered him as an altar sacrifice.

Cyane (C) (Greek)

After attempting to halt the kidnapping of Persephone, this nymph was turned into a fountain by Hades. *See also* Hades; Persephone.

Cyanippus (Greek)

He was the king of Argos. His parents are Adrastus, who was the king of Argos, and his niece Amphithea. His siblings are Aegialeus, Aegialeia, Argeia, Deipyle, and possibly Cyanippus and Hippodameia. *See also* Adrastus; Amphithea; Apsyrtus.

Cyavana (India) *see* Bhrigus; Mada.

Cybebe (Greek) *see* Cybele.

Cybele *Cybebe, Cybelle, Kubele, Kybele* (Greek, Phrygian)

(Asia Minor, known as "Great Mother," then to Greece and Rome. Cybele may be derived from the Semitic Gebaliah [goddess of Gebal].)

Also known as: *Agdistis, Berecyntia* (Gaul), *Dindymene, Dindymus, Ma, Magna Mater* (Roman), *Mater Turrita* (Roman), *Ops, Rhea.*

Earth goddess. Healer. Builder of cities. Protector during war. Cybele was a fertility goddess and goddess of caverns, worshipped as mother of the gods in Phrygia and Asia Minor. Worship of Cybele traveled to Greece and Rome. If Cybele began life as Agdistis, her father was Zeus and she was born of the rock Agdos. Or, she could have been the daughter of Uranus and Gaea, or Meion and Dindyme. Cybele was the mother of King Midas by Gordius, king of Phrygia (Gordius of the knot fame) and may also have been the mother of Sabazius (Dionysus). Her great love was for Attis (Atys) and she was possibly

www.ebook3000.com

the mother of Corybas (later identified with the Corybantes) and Sabazius. She made a pact with Attis to remain celibate. He broke the pact and to satisfy the terms of his agreement he had to castrate himself. When Attis died, Cybele transformed him into a pine tree. She conducted her mourning period under the tree and all growth stopped on the earth. Zeus promised her that the tree would always remain green (evergreen). In another version, Zeus, jealous of Attis' relationship with Cybele, sends wild boars to rip the handsome young man to pieces. Cybele's priests, all castrated in her honor or in honor of Attis, were known as the Galli. Cybele was a healer, a protector and she offered immortality to her devotees. Eventually Cybele and the goddess Rhea merged. She wore a turreted crown to signify that she was a war goddess and founder of cities. She was attended by the Corybantes and rode in a chariot pulled by lions; sometimes she held a whip. She was also associated with bees. As Cybele Phrygia, she bears branches in her hands and was associated with a sacred column. Cybele is identified with Rhea, Demeter, and Bona Dea. Cybele's legends are the same as the mythology attached to the Phoenician mother-goddess Astronoe. Compare Cybele and Attis to Inanna and Dumuzi, Ishtar and Tammuz. *See also* Agdistis; Arinna; Atalanta; Attis; Corybantes; Curetes; Midas; Rhea; Sabazius.

Cybelle (Greek) *see* Cybele.

Cyclopes *Cyclops, Ky-klopes, Kyklopes; Kyklops* (Greek)
Storm or volcano deities. The Cyclopes are the one-eyed giant children of Uranus and Gaea. Their names are Brontes, who personifies Thunder; Steropes, who personifies Lightning; Arges (who is also known as Acmonides and Pyracmon), who personifies sheet lightning. Hesiod and Homer include Acamas, Polyphemus and Pyracmon as Cyclopes. The first Cyclopes were subterranean divinities or fire genii and were assistants of Hephaistos. They were the ones who manufactured the thunderbolts for Zeus, since they were the only ones who knew the process. They helped Vulcan make the thunderbolts for him, the darts for Cupid, the trident for Poseidon, a bronze helmet for Hades, and a shield for Achilles. It was Homer who changed them in his "Odyssey." Then they became the familiar evil one-eyed giants. They were reported to live on the Island of Sicily. The most famous of these ugly creatures was Polyphemus, who loved Galatea, and who killed Acis. The Cyclopes were in turn killed by Apollo in vengeance for the death of his son Asclepius. The Cyclopes are giants with one eye centered in the forehead. Later the Cyclopes were replaced by the Caberi (q.v.). *See also* Acamas (D); Acis; Aegaeon; Cronus; Gaea; Galatea; Hecatonchires; Hephaistos; Titans.

Cydon (Greek)
He is the son of Hermes or Tegeates and Acacallis, the daughter of Minos and Pasiphae. *See also* Acacallis.

Cyena *Cyene* (India) *see* Garuda.

Cygnus (Greek)
He is the son of Ares and Pelopia or Pyrene. Cygnus wounded Heracles and Heracles killed him and turned him into a swan. *See also* Ares.

Cyhiraeth (Celtic)
Originally, she was a goddess of streams. Later, she became a spirit who haunts brooks. Her mysterious cry foretells death.

Cymodoce (Greek)
She is one of the fifty daughters known as Nereids, of Nereus and Doris. *See also* Nereids.

Cymothoe (Greek)
One of the fifty daughters, known as Nereids, of Nereus and Doris. *See also* Nereids.

Cynosura (Greek)
A nursemaid to the infant Zeus, this nymph of Mount Ida became the star, Ursa Minor. *See also* Zeus.

Cynthia (Roman)
Also known as: *Diana.*
As Cynthia, she is the goddess of the moon. *See also* Artemis; Diana.

Cynthius (Greek)
Also known as: *Apollo*
This epithet of Apollo was given because he was born on Mount Cynthius on the island of Delos. Diana was also born in the same place. *See also* Apollo.

Cyrene (Greek)
Cyrene, a nymph, became the queen of Libya after she killed a violent lion. She is the daughter of Hypseus and Chilidanope. By Apollo, she became the mother of Aristaeus and Autychus. By Apollo or Abas, she is the mother of Abas. Ares is her son by Diomedes. *See also* Ares; Aristaeus.

Cythera *Cythereia* (Greek) An epithet of Aphrodite (q.v.).

Cytissorus (Greek)
Cytissorus helped the Argonauts capture the Golden Fleece and assisted them in their escape from Colchis. *See also* Golden Fleece; Phrixus.

Czarnobog (Slavic) *see* Chernobog.

D

Da (Dahomey People, Africa; Tibet)
Also known as: *Dab-Iha.*
Little known Serpent.

Da-Bog (Slavic) *see* Dazbog.

Daauke (Assyro-Babylonia) *see* Damkina.

Dab-Iha (Africa; Tibet) *see* Da.

Dabaiba (Inca People, Peru)
The "Mother of Creation."

Dabog (Slavic) *see* Dazbog.

Dactls (Greek) *see* Dactyli.

Dactyli *Dactls, Dactyls, Daktuloi* (Greek)
Giant gods of metallurgy. Their name means "fingers." It is thought that there were three Dactyli originally. Their individual *names are* Acmon, Celmis, and Damnameneus. Over the years, the number of Dactyli has ranged from three to thirty-two. Fire and the forging of copper and iron were introduced to Crete by the Dactyli. In one of the Dactyli-related myths, they came from the earth when Rhea dug her fingers into the ground while giving birth to Zeus. Other reports state that they are the servants of Rhea, and that they live at the foot of Mount Ida. Some versions say they are metal workers of Hephaistos, who taught mortals how to work metals, the use of arithmetic, and letters of the alphabet. They are also known as the ten children of Rhea or Anchiale, a nymph. Yet in other tales, there are thirty-two Dactyli, all magicians. Others say that the Dactyli are five in number. As five Dactyli they are thought of as the five fingers: Heracles (thumb), Aeonius (forefinger), Epimedes (middle finger), Jasius, (ring or healing finger), Idas (little finger). There are similarities to the Telchines and to the Cyclopes (qq.v). Compare to Irish metal workers, Cabiri, and Credne. *See also* Hephaistos; Rhea.

Dada (Yoruba People, Africa)
She is the goddess of the brain and senses. *See also* Olodumare.

Dadu (Middle Eastern) *see* Adad; Bir; Birqu; Rammanu.

Dadzbog (Slavic) *see* Dazbog.

Dae-Soon (Korea)
Moon goddess.

Daedalion (Greek)
When his father, Chione, committed suicide, Apollo changed Daedalion into a hawk. *See also* Acacallis; Chione.

Daedalus (Greek)
Deified mortal. Inventor. Builder of the Labyrinth. A brilliant inventor, Daedalus is the son of Metion or Eupalamus and Alcippe or Merope. His son is Icarus. Jealous of the talents of his nephew Talos, he murdered him. Exiled from Athens, he fled to Cnossus where he built the Labyrinth for the Minotaur. Father and son were confined within the maze. They made wings of wax and feathers to fly to safety, but Icarus flew so high, and came so close to the sun that his wings melted and he fell to his death. Daedalus fled to Sicily and sought refuge with Cocalus, the king of Camicus. In some versions, Daedalus murdered Perdix because of jealousy, since Perdix invented the saw. Daedalus also created a false bull which mated with the moon goddess, Pasiphae, the wife of Minos, the king of Phrygia. It was this union that created the Minotaur. Daedalus also invented the axe, the level, and sails for ships. *See also* Ariadne; Icarus; Labyrinth, Minos; Minotaur; Pasiphae; Perdix.

Daemon *Daemons and Daimones* (Plural); *Daimon* (Roman)
Also known as: *Demons.*
Personal spirits, both good and evil. In some traditions, daemons are thought to be the energy used to form gods. It is also said that daemons are two spirits, good and evil, who preside over mortals and areas. Zeus is said to have assigned a daemon to each individual at birth and after death as a guide to Hades. Genii, nymphs, satyrs, river gods and penates are described as daemons. Compare to Genius and Lares.

Daemons (Roman) *see* Daemon.

Daevas *Daeva, Daiva, Devas* (India); (Islamic, Mazdaism, Zoroastrian; Persia)
Also known as: *Devs* (Armenian), *Divs* (Persian).
These malevolent spirits are helpers of the prince of demons, Ahriman, earlier known as Angra Mainyu. Under the rule of Iblis, their function is to fight all that is good. Generally they are opposed to the Asuras. The Daevas are Aka Manah, the spirit of evil who opposes Vohu Manah; Indra, the deceiver of men (not the Vedic god) who opposes Asha Vahishta; Sauru, an anarchist and tyrant, opposes Khshasthra Vairya; Naonhaithya, the demon of stubborness, pride, rebellion and irreverance who opposes Spenta Armaiti; Taurvi and Zairisha, the demons who degrade men, lead them to failure, and cause old age, oppose Haurvatat and Ameretat; and Aeshma, the demon of lust and rage who opposes Sraosha. (The Vedic Daevas are gods.) *See also* Aeshma; Ameretat; Ameshas Spenta; Angra Mainyu; Azazel; Devs; Devas (A); Devas (B); Drujs; Haurvatat; Hoshang; Khshasthra Vairya; Peri; Spenta Armaiti; Sraosha; Vohu Manah; Yata.

Dag (A) (Norse; Teutonic) *see* Dagr.

Dag (B) (German)
Day goddess. She is possibly the female version of Dagr (q.v.).

www.ebook3000.com

Dagan (Semite) *see* Dagon.

Daganoweda (Huron, Iroquois People, North America)
Also known as: *Deganiwada, Hiawatha.*

Aspect. He is the son of the Great Spirit and a mortal woman, Djigonasee. It is also the name for Hiawatha or the deity who converted Hiawatha to the brotherhood.

Dagda *Dagde, Daghda, Daghdae, Daghdha, Dogdha* (Celtic)
Also known as: *Crom-Eocha, Daghdae-Cearas, Dagodevos, Eochaid Ollathair* (The Great Father), *Ruad Ro-Fhessa* (The Mighty One of Great Knowledge).

Omnipotent god of knowledge, life and death. Dispenser of plenty. Controller of weather and crops. Son of Eladu (knowledge), Dagda, usually referred to as "The Dagda," was one of the leaders of the Tuatha De Danann. He was known for his wisdom, magic and music. It is said that he could summon the seasons by playing his harp, named "the Oak of Two Greens." With Undry, his magic cauldron, and a magic pig that could be eaten daily and reappear cooked, he could provide an unending supply of food. It follows that he carried excessive weight. He also had difficulty controlling his sexual appetite. He was said to have mated with Morrigan and also with Boann by whom he had two children, the goddess Brigit and the god Angus. In another legend, Brigit appears as his wife, not his daughter. He was also said to have married a woman with three names, Breg (Lie), Meng (Guile) and Meabel (Disgrace). They had three daughters each named Brigit. The goddess Dana is said to be his child as is the goddess Bambha. Other children attributed to Dagda were Ogma, Midir, Bodb the Red, and Ceacht. As god of earth and fertility, he used a dual function magic club to heal, resurrect, wound and kill. As he dragged his gigantic club, the spikes would claw the ground leaving gaping paths behind him. When the Tuatha De Danann landed on the island they challenged the Firbolgs in the First Battle of Magh Tuiredh and emerged the victors. As a result of this engagement, the king of the Tuatha De Danann had his hand amputated. A rule of the people was that the monarch could not be physically maimed, so Nuada was replaced by the Fomorian, Bress, who was of mixed heritage. His mother, Eriu, was a Tuatha De Danann and his father, Elatha, a Fomorian. Bress turned out to be a tyrant, who subjected the Tuatha De Danann to severe penalties. Dagda and his son Ogma were reduced to menial activities and humiliating injustices by this king. Eventually, the Tuatha De Danann under the leadership of Lugh were able to topple the reign of the Fomorians in the Second Battle of Mag Tuiredh. Dagda, however was not able to retain ownership of his own property. It was not the enemy who evicted him from his castle, Bruigh na Boinne, it was his son, Angus. In some myths, we are told that this talented leader with a great zest for life ended up being a contented cook for king Conaire the Great. Dagda was shown as ugly, gross, and potbellied, usually wearing a short tunic and sandals. His two special attributes were his cauldron and his club. He is the equivalent of the Welsh Math and is similar in nature to his brother Lugh. For details involving his relationship with Morrigan *see* Morrigan. Compare Dagda's club to Thor's hammer, Indra's thunderbolt and Sucellos mallet. Compare to the mythology of Pushan (India) and Thor (Teutonic). For details of the Fomorians injustices to Dagda and his people, *see also* Angus; Anu (B); Balor; Banbha; Boann; Bress; Brigit; Dana; Nuada; Ogma; Tuatha De Danann.

Dagde (Celtic) *see* Dagda.

Daghda (Celtic) *see* Dagda.

Daghdae (Celtic) *see* Dagda.

Daghdae-Cearas (Celtic) *see* Dagda.

Daghdha (Celtic) *see* Dagda.

Dagini (India) *see* Dakinis.

Dagoba (Buddhist) *see* Stupa.

Dagodevas *see* Dagda.

Dagon (A) *Dagan, Daguaun, Dagun, Daguna* (Akkadian, Babylonian, Canaanite, Semitic, Sumerian, Ugarit)
Also known as: *Oannes, Zeus Arotrios* (Zeus the Farmer).

Dagon was analogous to Ea and the Phoenician god Dagon. He was worshiped in the city of Ashdod (Israel), where the Ark of the Covenant was kept. He has been referred to as an attendant of the great Enlil. In one legend he is one of the sons of Uranus and Ge. His brothers were Ilos (El-Cronus), Betylus, and Atlas. Sometimes he is known as one of an old Sumerian trinity with Shamash and Idurmer. Dagon was likely an androgynous deity. He is described as fish-tailed. He may be associated with Atargatis (Derketo). It is possible that he was replaced by Apollo. *See also* Atargatis; Dagon (B).

Dagon (B) *Dagan* (Phoenician)
Also known as: *Baal Dagon, Baal of Arvad, Siton, Zeus Arotrios* (Zeus the Farmer).

In the Phoenician Creation Legend of Philo Byblos, Dagon is the son of Ouranos and Ge; the brother of sisters Astarte, Rhea, Dione and probably Caribo (Cabira), the daughter of Astarte and Cronus. His brothers are Cronus, Betylus, and Atlas. He is thought of as a corn god, but later excavations (Graeco-Roman) indicate a relationship with Oannes the Chaldean fish god (q.v.).

Dagr *Dag* (Norse; Teutonic)
Also known as: *Day.*

God of the Day. Known as the "Bright and Fair." He is the son of Delling, the dwarf gatekeeper of Asmegir and brother of a sister, Nott, the personification of night. The All Father sends Dagr (Day) and Nott (Night) around the earth in a chariot every twenty-four hours. Day's horse is named Skin-faxi, and Nott's horse is Hrim-faxi. *See also* Delling; Nott.

Daguaun (Middle Eastern) *see* Dagon (A).

Dagun (A) (Middle Eastern) *see* Dagon (A).

Dagun (B) (Afghanistan) *see* Imra.

Dahak (Persia) *see* Zahhak.

Dahana (Greek) *see* Perseus.

Dahhak (Persia)
An evil spirit and enemy of Yima. *See also* Azhi Dahaka.

Dahomey People, Africa — Creation Legend *see* Aido Hweda.

Dai Itoku-Myoo *Amida, Goemmason, Yamantaka (Sanskrit).* (Buddhist; Japan)

Dai Itoku-Myoo is one of the Godai-Myoo. They are the protectors of Buddhism and incarnations of the five great Buddhas. Dai Itoku-Myoo is an incarnation of Amida and a manifestation of Amida's wrathful aspect. His function is to carry out the wishes of Amida. Dai Itoku-Myoo battles illnesses and poisons. He is reputed to be more powerful than the dragon. The name Goemmason (Destroyer of Death) is also used when applied to Dai Itoku-Myoo for he vanquished the King of the Underworld, Emma-O. Dai Itoku-Myoo is shown with six heads, six arms, and six legs. His faces show fierce expressions. He is usually seated on a white ox. He is also depicted sitting on a rock with three left legs folded and the three right legs set on the earth. In one of his right hands he holds a scepter, one is raised and holds a sword. In one of his left hands he holds a wheel, and in another hand a trident. He has been shown with one head, three eyes, bristling hair and two arms. He is seated on a rock with crossed legs. In his right hand, he holds a long stick with a trident at each end. In his left hand he holds the varja (thunderbolt). Dai Itoku-Myoo is always depicted with flames in the background. *See also* Amida; Emma-O; Fudo-Myoo; Godai-Myoo; Gozanze-Myoo; Gundari-Myoo; Yamantaka.

Daikoku (Japan) *see* Diakoku.

Daimon (Greek) *see* Daemon.

Daimones (Greek) *see* Daemon.

Dain (Norse; Teutonic)

He is one of the dwarfs who made the chain that bound the wolf Fenrir. He is also one of the dwarfs who ate the buds of the life tree, Yggdrasil. The other dwarfs are Dvalin, Duneyr, and Durathror. *See also* Bifur; Dvalin; Dwarfs; Yggdrasil.

Dainachi Nyori (Japan) *see* Dainichi-Nyorai.

Dainichi-nyorai *Dainachi Nyori* (Buddhist; Japan)

Also known as: *Birushana, Fudo-Myoo, Maha-Vairochana Tathagata* (Sanskrit), *Tathagata Mahavairokana.*

The secret doctrine that forms the tenets of the Tendai, the Shingon, the Kegon and other esoteric traditions, were said to have been transmitted through the Bodhisattva Vajrasatwa and Nagarjuna by Dainichi-nyorai (Great Sun Buddha). Known as the "Great Illuminator," Dainichi-nyorai is said to be a reincarnated form of Vairochana (meaning "belonging to or coming from the sun"). Dainichi-nyorai is sometimes considered an androgynous deity. The Shinto sun goddess Amaterasu was identified with Dainichi-nyorai when Buddhism was introduced to Japan. In some traditions, Dainichi-nyorai is thought to be a reincarnation of Amaterasu. Fudo-Myoo, said to be an incarnation of Dainichi-nyorai, is one of the Godai-Myoo (Five Great Kings). His function is to carry out the wishes of Dainichi-nyorai. When shown in the mandala of the World of Ideas (Vajradhatu), he is depicted seated in a meditative pose, wearing a crown, and holding his left index finger. The left hand pose indicates the intellectual element, the right hand, the five elements: earth, water, fire, air and the ether (or vital energy). This is known as the mudra of the Six Elements. Dainichi, as one of the Buddhist trinity, is shown wearing a replica of a dog's head on his head, the eleventh sign of the zodiac. He is also in the center of the mandala of the World of Forms immediately above Muryoju (Amitayus). In the mandala of the World of Ideas (Kongokai), Dainichi-nyorai is below Muryoju. In the Garbhadhatu mandala, the divine physician, Yakushi-rurikwo-nyorai is identified with Dainichi-nyorai. *See also* Amaterasu; Amida; Fudo-Myoo; Godai-Myoo; Vairocana; Vajrasatwa; Yakush-nyorai.

Daityas *Daitya* (Singular), *Danavas*; (Hindu; India)

The giant evil spirits known as the Daityas are the offspring of the goddess Diti and Kasyapa. The Daityas were relegated to the ocean depths in a strata known as Patala by Indra for their opposition to sacrifice. Their city is called Hiranyapura. When it breaks the boundaries set by Indra, this city moves around under the earth or sails through the air. Hiranya-kasipu, his son Prahlada and great-grandson Bali and Hiranyaksha are Daityas. The Daityas are a category of Asuras, as are the Danavas, who are also giants, and the Adityas. The Daityas and Danavas were frequently in conflict with the gods. In contrast, the Adityas represent eternal light and the power of good. The female Daityas are described as giants who wear jewels the size of boulders. Compare the Daityas to the Rakshasas. *See also* Adityas; Agastya; Arjuna; Asuras; Bali (B); Brihaspati; Diti; Hiranya-kasipu; Hiranyaksha; Hiranyapura; Indra; Kasyapa; Krishna; Kurma (regarding the churning of the sea of milk); Maruts; Nara-Simba; Patala; Prahlada; Rahu; Savarbhanu; Vamana (Vishnu's avatar as a dwarf); Varaha (Vishnu's avatar as a boar); Varuna; Vrita.

Daiva (India, Persia) *see* Devas (A); Devas (B).

Dajdbog (Slavon) *see* Dazbog.

Dajoji (Iroquois People, North America)

Also known as: *The Panther.*

A panther deity and god of the west wind, Dajoji is called "west wind" in mythology. He is said to support the whirlwind. Ga-oh summons him to fight against storms. When Dajoji's cry pierces the night, the sun hides in fear.

Dakas (India) *see* Dakinis.

Dakini (India) *see* Dakinis; Kali.

Dakini Ye-she-tsho-gyal (India)

A recent incarnation of Sarasvati, said to have lived approximately twelve hundred years ago. Her powerful memory permitted her to remember everything she heard. *See also* Sarasvati.

Dakinis *Dagini* (Buddhist, Hindu, Lamaist; India)

Also known as: *Asrapa, Ashrapa* (Drinkers of Blood), *Dakis, Kadomas,* (Tibet), *Khadhomas, Khadomas, Khados, Khandros, Mka-gro-ma* (Tibet).

Dakinis are categorized as air spirits, fairies and a class of demon goddess. Their male counterparts are known as Dakas. They are attendants to the goddess Kali. The name translated literally means "sky walking woman." They are sometimes described as giants, and sometimes with the bodies of fish. They are shown eating flesh or drinking blood. Dakinis are used to designate the female partner in the tantric initiation, and thus are human and superhuman. In this tradition, they are called "mothers" and they are able to grant paranormal powers and spiritual insight to the sincere practitioner of Kundalini yoga. The Five Orders of Dakinis in Tibetan rites are: the Vajra

www.ebook3000.com

Chi Kung we learn time tested ways to tap into these unlimited and transpersonal reservoirs of Chi and greatly expand the amount of energy available to us. It is very important to master first the stages of conservation, balance and transformation before we emphasize increasing our Chi. Otherwise we may waste the energy we bring in, or we may inadvertently amplify the imbalanced or negative energies that we have not yet learned to bring under control.

5. Finally, we learn to extend our mind to tap into the vast Chi of nature, cosmic and the universe, to heal our body, mind and spirit and to heal other people. Cosmic Healing Chi Kung practice sensitizes your hands to the feeling and movement of Chi; it uses the mind-eye power to absorb cosmic Chi into the palm and crown and to send it out through the hands and beyond, so that you can help restore balance in others without touching them or draining yourself.

This may sound fantastic at first, yet recent researchers in Chinese Chi Kung hospitals have not only measured the energies emitted by Chi Kung masters; they have also discovered that different varieties and frequencies of healing Chi can be emitted. This research has been corroborated by experiments in the United States at such places as the Menninger Institute.

Four Sections of Cosmic Healing

The next step is to learn the four sections of the Cosmic Healing Chi Kung, the 'Empty Force' sequence. Each of the four sections of Cosmic Healing Chi Kung develops a different type of energy mastery. Each section begins and ends in the same way, yet has different movements in the middle.

Connecting to Heaven and Earth

The first section of Cosmic Healing Chi Kung emphasizes connecting to the external Chi emanating from heaven and earth. This ability is very beneficial for self-healing and is essential for healing others. If you do not connect to some source of external energy when healing others, you will draw upon your own personal reservoirs. Our personal Chi is limited by nature, and can easily become depleted if we give it away too freely.

Over the past decade external Chi healing has become very popular in China. There are now hundreds of Chi Kung hospitals and clinics throughout the country. Yet many of the Chi Kung therapists can only administer two or three treatments a day; they spend the rest of their day practicing Chi Kung to replenish their own Chi. Those who practice the more traditional Chi Kung know how to connect to the Chi of heaven, earth and nature.

In this first section, you will learn to sense the energies outside your body. You will then learn to draw and absorb these energies into your body and process them in order to use them for self-healing and healing others.

Dakinis, who are white and sometimes blue in color and have the attribute of peacefulness; the Ratna Dakinis, who are yellow and have the attribute of grandness; the Padma Dakinis, who are red with the characteristic of fascination; the Karma Dakinis, who are the Dakinis of action, are green in color and associated with sternness; and the Buddha Dakinis, who are the Dakinis of Understanding and are dark blue in color. The Tibetan Dakinis are described as being "majestically divine" in appearance. In the mythology of Lamaism, Dakini was a lion-headed goddess associated with Lha-mo. *See also* Bhavani; Dorje Phagmo; Kali; Khados, Mkah Hgroma; Varahi.

Dakis (India) *see* Dakinis.

Daksha (Hindu, Vedic; India)
Daksha is an early Vedic god who was both the son and father of Aditi. In the *Brahmanas* he is identified with the creator, Prajapati. In the *Mahabharata,* he is the son of Brahma, whose right thumb gave birth to him. He married Prasuti, the daughter of Manu, who in some legends is said to have been born from Brahma's left thumb. Daksha was the chief of the Prajapatis, who are the seven (and later ten) sages and poets born of Brahma and called rishis. He was the father of sixteen daughters who became the mothers of all living things, including gods, men and demons. The youngest, Sati, an incarnation of Uma, became Shiva's wife. This made Daksha Shiva's father-in-law. Thirteen of the daughters were given to Yama, one to Agni, one to the Pitris and one to Bhava-Siva. In other legends, the number of daughters is said to be 24, 50, or 60. He gave away two of his sixty daughters to Bhuta, ten to Dharma, twenty-seven to Soma, thirteen to Kasyapa, three to Trakshya, two to Agni, two to Angiras, and one (Sati) to Shiva. In one version Daksha neglected his twenty-six daughters who then put a curse on him. Since then, the moon becomes faint at times. One of his daughters, Suaha, was called the wife of Agni and possibly Rudra. Another daughter, Krodha, meaning "anger," was the wife of Kasyapa and was the mother of all four-footed predators and all birds of prey. Two other daughters, Puloma and Kalaka, were wives of Kasyapa and mothers of the 60,000 giant demon spirit Danavas. (Some say that Puloma and Kalaka are the daughters of Vaishvanara and that they were the mothers of thirty million Danavas.) Daksha is born and killed in every generation. Some scholars say that Daksha is Vishnu who is incarnated through him to create living beings. Others say that as the first man, he created from himself a woman and fell in love with her. Their many daughters married Soma. In the *Mahabharata,* it is written that Daksha initiated a giant sacrifice, known as a hecatomb, for all the gods. As he did not know Shiva, he neglected to give him a share of the sacrifice. Shiva was so enraged that he broke Pushan's teeth, Savitri's arms and tore out Bhaga's eyes. He was then given his portion and he returned the deities to health. In the Puranas, the gods were sacrificing to Vishnu and did not invite Shiva. His mate Uma persuaded him to show his power to the gods. From his anger the giant demon Virabhadra emanated. He caused a great melee that did not end until Daksha propitiated Shiva and acknowledged his superiority. In other interpretations, Daksha considered Shiva disreputable and never liked him. Later, he was forced to acknowledge Shiva's superiority over Brahma. After a long feud, Daksha was decapitated by the god in anger. *See also* Aditi; Adityas; Agni; Badari; Bhaga; Bhutas; Brahma; Danavas; Devaki; Devi; Dharma; Diti; Durga; Garuda; Kadru; Karttikeya; Kasyapa; Lokapalas; Manu; Marisha; Medha; Mitra; Nagas and Nagis; Parvati; Pitris; Prajapati; Priti; Pushan; Rahu; Rishi; Rudra; Sati; Shiva; Simhika; Soma; Surabhi; Uma; Vasistha; Vinata; Virabhadra; Yajna; Yama.

Dakshaja "Born of Daksha" (India) *see* Devi.

Dakshina (India) *see* Devi.

Dakshina-Murti (Hindu; India)
Shiva's name, Dakshina-Murti, meaning "Facing South," is used when he sits on Mount Kailasa instructing the yogis.

Daktuloi (Greek) *see* Dactyli.

Dalhan (Arabic)
This is a species of cannibal demon who rides an ostrich in the desert. In other interpretations, the Dalhan is depicted as a man riding a camel. He lives on desert islands and feeds on shipwrecked sailors. *See also* Jinn.

Dam-c'an-r-do-rje-legs-pa *Dam-chen-dr-je-le-pa, Dor-le* (Buddhist; Tibet)
He is the chief of the demons who were subdued by Padmasambhava. He is shown in Tibetan clothing, carrying a kapala and Vajra. He is seated on a lion with a green mane. *See also* Samantabhabra.

Dam-chen-dr-je-le-pa (Tibet) *see* Dam-c'an-r-do-rje-legs-pa.

Dam-ki (Assyro-Babylonia) *see* Damkina.

Damanaka Tree (India) A sacred tree. *See also* Kama.

Damaru (Hindu; India)
Shiva's sacred drum. *See also* Nataraja.

Damballah (Haitian, of African origin)
Also known as: *Damballah-Wedo.*
Damballah, a powerful serpent deity of the Rada pantheon of Haitian voodoo gods is the patron of rains, streams and rivers. He is not concerned with mortal problems and is usually found around water. Special pools are built for his bathing. Although a sky god, he is also said to live in trees. His mate is Aida Wedo, the rainbow snake, also known as Ayida. Damballah is generally shown as an arch in the sky, colored like a rainbow. His symbol is an egg. Aida Wedo wears a jeweled headdress. During Voodoo rituals, she slithers along the floor. *See also* Aido Hwedo; Rada.

Dame du Lac (Arthurian) *see* Vivien.

Dames Vertes (Celtic, French)
Wind spirits and shape-changers, the "Green Ladies" entice travelers from their routes in the forest. Laughing, they hold their victims upside down over waterfalls. In human form, they dress in long green robes and are tall and attractive. As wind spirits, they stimulate all plant life in their paths.

Damgalnunna (Sumer) *see* Ninki.

Damia (Greek)
She is a goddess of health worshiped only by women.

Damke (Assyro-Babylonia) *see* Damkina.

Damkina *Davkina, Dawkina* (Assyro-Babylonia)

Also known as: *Daauke, Dam-ki, Damke, Damku, Dauke, Dauthe, Gashanki, Ninella, Ninhursag, Ninki.*

In Chaldean mythology, Damkina is possibly the daughter of Tiamat who personifies the primordial waters or Ki who personifies the earth. She is the sister/consort of Ea, and the mother of Marduk and possibly Tammuz. She may also be the mother of the sea goddess Gasmu. In Babylonian mythology, she is a sky deity, variously known as the consort of Ea, or Anu, who with one of them ruled the Apsu. With Ea, she is said to be the mother of Bel. In later Babylonian mythology a triad of goddesses is represented by Damkina, Belit, and Anath. In Sumerian mythology, she is the earth mother (her name in the Akkadian language means "Lady of Earth"). She is also known as the consort of Enki in some tales. Damkina is appealed to by women who are in labor. As Ninki she is the queen of the deep waters, and as Gashanki she is queen of the earth. *See also* Anath; Anu; Apsu; Bel (A); Ea; Enki; Gasmu; Ki; Marduk; Ninhursag; Ninkarrak.

Damku (Assyro-Babylonia) *see* Damkina.

Damnameneus *see* Dactyli.

Damona (Celtic, Gaul) Goddess of cattle. *See also* Borvo.

Damsel Ho (China) *see* Ho-hsien-ku.

Damu (Sumer) *see* Dumuzi; Tammuz.

Damu-zi-abzu (Babylonian) *see* Tammuz.

Dan (A) (Fon People, Africa)

Also known as: *Dan Ayido Hwedo, Danh.*

Snake god of unity and life. He is the son of the twins Lisa and Mahu. Dan is shown as a rainbow snake with his tail in his mouth. He is possibly the god Dan Petro of the Haitian people.

Dan (B) (Celtic) *see* Dana.

Dan Ayido Hwedo (Africa) *see* Dan.

Dan Petro (Haitian)

Also known as: *Danh.*

God of farmers. Originally, Dan Petro may have come from Africa as Danh. He is considered the father of tribal gods of the Haitians. His attributes are snake-like.

Dana (Celtic)

Also known as: *Ana, Anu, Danu* (Irish), *Don* (British, Welsh), *Donu* (Irish).

Goddess of plenty. Dana is the daughter of Dagda and the mother of Brian, Iuchar and Iucharbar (who may be a triple concept of one deity). As Dana, she is confused with the triad of goddesses: Danu, Anu (Ana) and Brigit (Bridgit). The Celtic race is descended from Dana. Her people, the Tuatha De Danann, came to Ireland many centuries ago from the Isles of the West and returned there at a later time. Some, who could not bear to leave the land they called Erinn, took the name Aes Sidhe and remained. It is believed they are the leprechauns who dwell beneath the surface of the land and vanish and reappear at will. In an ethical battle, they will fight beside mortals with lances of blue flame and pure white shields. Dana represents the earth, the fertility mother of all. The Welsh identified her with Don and she is comparable to their "Great Mother" Modron. She is associated with Aine the moon goddess. Compare to the moon goddess, Arianrhod. Dana is said to be the counterpart of Gaea. *See also* Aine; Angus; Anu (B); Bel (B); Brigantia; Brigit; Dagda; Don; Leprechaun; Tuatha De Danann.

Danae (Greek)

Also known as: *Abantias, Dahana.*

It is generally thought that Danae was the daughter of Acrisius and Eurydice, though some say that she may have been the daughter of Aganippe and Acrisius or his friend, Teutamias, the king of Larissa. Danae had been seduced by her uncle Proteus and later became the mother of Perseus by Zeus, despite her father's extraordinary attempts to shelter her from becoming pregnant. Danae, as a descendant of Abas, a king of Argos, was sometimes known as Abantias. *See also* Acrisius for the events surrounding Danae's pregnancy and the birth of Perseus. To compare with women who were seduced by Zeus in other forms, *see* Aegina; Antiope; Europa; Leda. *See also* Perseus; Zeus.

Danai (Greek) *see* Danaides.

Danaidae (Greek) *see* Danaides.

Danaides *Danaids, Danaidae* (Greek)

Also known as: *Danai.*

Deities of springs and waters. Possibly early agricultural deities. The Danaides are the fifty daughters of Danaus who married their cousins, the fifty sons of Aegyptus. On their wedding night, forty-nine Danaides murdered their husbands. *See also* Danaus for the complete legend of the Danaides. *See also* Agenor (A); Amymone; Eurydice (C); Hypermnestra.

Danaids (Greek) *see* Danaides.

Danaus (Greek)

King of Libya. Danaus is the son of Belus and Anchinoe. His siblings are his twin brother Aegyptus, Thronia and perhaps Cepheus (Phineus). He was given Africa as a gift from his father, and originally ruled as the king of Libya. Aegyptus ruled Arabia and later conquered the Melampodes and named it Egypt after himself. Danaus, fearful that Aegyptus might kill him for his land, fled. It is said that Athena assisted him and he sailed to Greece, reportedly in a vessel thought to be the first two-prowed ship. With him were his fifty daughters, known as the Danaides, who were escaping from their cousins, the fifty sons of Aegyptus, who wanted to marry them. When he arrived in the arid land, he supplanted the reigning king, Gelanor, and became king. It is said that he was the first person to water the land by the use of wells. The men found Danaus and demanded that he consent to the marriages of his daughters. Although the body of the story differs, the ending remains basically the same. He acquiesced, possibly under force, but on their wedding night he gave the women weapons and instructed them to murder their husbands. It is said that they beheaded the men, burying their torsos at the city gates of Argos and their heads in the marshes. Hypermnestra, who married Lynceus, was the only daughter who disobeyed her father. Later, Danaus tried to find

www.ebook3000.com

husbands for his daughters, and of course encountered difficulties. He finally decided to offer the widows as prizes in a footrace and threw in attractive shields as added incentive. After death, the sisters (except Hypermnestra) were said to have been punished in Tartarus (the underworld). They were condemned to the useless task of pouring water continually into a sieve. In some accounts, Lynceus murdered Danaus to avenge his brothers' deaths and in others they reconciled and Lynceus succeeded Danaus, and the line of Argive kings stemmed from him. The Argives and eventually the Greeks were called Danai. The names of some of the Danaides are Celaeno, Cleite, Stenele, Chrysippe, Erato, Eurydice, Glauce (also known as Creusa), Polydore, Phylodameia, Asteria, Astioche, Cleodora, Amymone, and Cleopatra. Aegyptus, following the instructions of the Delphic Oracle, sacrificed his only daughter Aganippe to end a drought in Egypt. Eventually, Aegyptus arrived in Greece, heard of his sons' fate and fled to Aroe, where he died. Compare Danaus to Endymion and Nereus. *See also* Abas; Achaeus; Agenor (A); Amymone; Argos, Erato; Hypermnestra; Lynceus.

Danavas (India)
Sixty thousand, or thirty million, gigantic evil spirits. *See also* Brihaspati; Daityas; Daksha; Kuvera; Vritra.

Dancer of the Burning Ground (India) *see* Nataraja; Shiva.

Dandadhara (India) *see* Yama.

Dandapani (India) *see* Buddha.

Danh (Africa) *see* Dan.

Daniel (Assyro-Babylonia)
A diviner of dreams, able to cast spells on wild animals, Daniel was also a prophet. He destroyed a dragon by driving a storm wind into the dragon's mouth and splitting it in half. He is famous for being cast into a den of lions. His symbol is the four-horned goat. Daniel's story is similar to the Babylonian Marduk and Tiamat.

Danil *Daniyal* (Arabic)
Danil, like the Hebrew Daniel, was also a prophet and diviner of dreams. Imprisoned, he was released by the king to interpret a dream.

Daniyal (Arabic) *see* Danil.

Danu (A) (Celtic) *see* Anu (A).

Danu (B) (India)
One of Daksha's numerous daughters. Mate of Mitra-Varuna, the Asvins and Kasyapa. Mother of the Danavas and Danavis. *See also* Aditi; Diti; Kasyapa; Mitra; Varuna; Vritra.

Danu (C) (India)
The serpent god father of Vritra and Ahi (qq.v.).

Danus (Greek) *see* Eurydice (C).

Dao (Babylonian) *see* Tammuz.

Daonus (Babylonian) *see* Tammuz.

Daphne (Greek)
A nymph, Daphne, is a priestess of Gaea who personifies the earth. She led secret female rituals to celebrate the femininity of the earth. A mortal male, Leucippus, dressed in female attire in an attempt to gain access to her services. The sun, who sees all, suggested that the females perform their rituals nude so that males could not intrude. The true identity of Leucippus was revealed and he was killed. The sun god Apollo had his own agenda. When he saw Daphne he attempted to mate with her, but she rejected him. Infuriated, he chased her and attempted to rape her. She appealed to Gaea who responded immediately and turned the beautiful nymph into a laurel tree. From that time, Apollo wore laurel wreaths in his hair and the laurel tree was honored as a source of inspiration. Compare Dapne to the Indian Urvasi. *See also* Apollo; Gaea; Oenamaus; Rivers.

Dar el-Jannah (Islam) Islamic Paradise (q.v.)

Darago (Philippines)
She is a volcano goddess and warrior. In ancient times, she required human sacrifices to keep her from erupting.

Daramulum (Aborigine People, Australia) *see* Duramulun.

Daramulun *Darramulum* (Aborigine People, Australia)
Also known as: *Biamban, Baime, Bunjil, Ngurunderi, Nurrundere, Thuremlin.*
This supreme being made earth his home a long time ago. He is sometimes called Biamban (meaning master). He wasn't married and lived with his mother, Ngalalbal. Sometimes he is said to be the one-legged son of Baiame. Daramulun is connected with a flood myth. In some myths, he is known as a culture hero from whom later medicine men could draw their power. This power enabled them to kill their enemies, fly anywhere, including to the sky land, which is the land of ghosts. He is sometimes shown with an axe, or with his mouth filled with quartz and with an enlarged phallus. He is sometimes depicted with one leg. *See also* Bunjil; Thuremlin.

Darawigal (Australia)
This god represents the force of evil who opposes Baiame (q.v.).

Darbas (Hindu; India)
The Darbas are spirits who haunt cemeteries and eat dead bodies. *See also* Dasyus; Panis; Pishachas.

Darkness (Greek) *see* Chaos; Nyx.

Darramulum (Aborigine People, Australia) *see* Daramulun.

Daru-el-Bawar (Islam) Islamic Hell (q.v.).

Daru el-Qarar (Islam)
Meaning the "Dwelling which Abideth" and symbolized by green chrysolite, this is the third stage in Islamic Paradise (q.v.).

Daru el-Salam (Islam)
Meaning the "Dwelling of Peace" and symbolized by white pearls, this is the second stage in the Islamic Paradise (q.v.).

Darvands (Persia)
Evil spirits created by Ahriman to be his assistants. They are Aka Mano, Ander, Nasatyas, Sauru, Tarik, and Zarik. The Vedic Darwands were originally good spirits, but like the Devas,

became demons in Persia. *See also* Angra Mainyu; Devas; Nasatyas; Saura.

Darwands (Vedic) Good spirits. *See also* Darvands.

Darzamat (Latvia)
Goddess of Gardens.

Dasan (Pomo People, North America)
With his father, Makila, Dasan led the bird clan, who brought civilization from over the waters.

Dasarata, King (India) *see* Dasaratha.

Dasaratha, King *Dasarata, Dasharatha* (Hindu; India)
Father of Rama. *See also* Rama and Hanuman.

Dascylus (Greek) *see* Amycus (A).

Dasharatha (India) *see* Dasaratha, King.

Dasim (Islamic)
The son of Iblis, the devil, Dasim became the demon of discord. *See also* Azazel.

Dasra and Nasatya (India) Wonder Workers. *See also* Asvins.

Dasyus (Dravidian, Hindu; India)
These evil spirits are the enemies of the gods and mortals. They appear human in the guise of ugly robbers and thugs. *See also* Darbas; Panis; Pishachas.

Datan (Slavic, Polish)
Datan is one of a group of spirits who are in charge of the prosperity of the fields. Tawals is another spirit, as is Lawkapatim, who is only concerned with the tilling process. They are grouped with the goddess Marzann who looked into the growth of fruit. *See also* Lawkapatim.

Dattoli (India) *see* Agastya.

Dauce (Babylonian Creation Legend of Damascius) *see* Aus, and Belus (B).

Daughter of the Night (Greek) *see* Nemesis.

Daughter of Themis (Greek) *see* Furies; Themis; Zeus.

Daughters of the Evening (Greek) *see* Hesperides.

Dauke (Assyro-Babylonia) *see* Damkina.

Dauthe (Assyro-Babylonia) *see* Damkina.

Davalin (Teutonic) *see* Dain; Dvalin.

Davinka (Assyro-Babylonia) *see* Damkina.

Dawat Puja (India)
"Worship of the Inkstand." Festival day. *See also* Sarasvati.

Dawkina (Assyro-Babylonia) *see* Damkina.

Day (Teutonic) *see* Dagr.

Day Gods (Aztec People, Mexico) *see* Lords of the Day Hours.

Dazbog *Da-Bog, Dabog, Dadzbog, Dajdbog, Dazh-Bog, Dazhbog* (Poland); (Slavic)
Also known as: "*Son of Svarog*" (Son of the Sky).
Dazbog is the son of Svarog, who personifies the sky, and the brother of Stribog, the god of cold and frost. Initially a sun god, in later times Dazbog was reduced to demon status in Siberia. As a sun god, he was associated with Khors, the god of health and hunting; Perun, the god of thunder; and Stribog, the god of cold and frost. In some tales, he is the part-time spouse of Myersyats, who personifies the moon. He visits her during the summer. Dazbog is depicted in wood with a silver head and a golden moustache. He is similar to the Sumerian Dazibogu (q.v.). Dazbog is identified with the Greek Helius. Compare Dazbog to the Greek Hephaistos. *See also* Perun; Stribog.

Dazh-Bog (Slavic) *see* Dazbog.

Dazhbod (Sumer) *see* Dazibogu.

Dazhbog (Slavic) *see* Dazbog.

Dazibogu (Sumer)
Also known as: *Dazhbod.*
He is a sun god, similar to the Slavonic Dazbog (q.v.).

Dazima (Semite)
One of the goddesses created by Ninhursag.

Dbyar-Gyi-Rgyalmo (Tibet) *see* Grismadevi.

De Hi No (Huron People, North America) *see* Heng.

De-Hi-No (China) *see* Heng.

Dea Artio (Celtic) *see* Artio.

Dea Syria (Greek) *see* Atargatis.

Deae Matres (Celtic)
The trinity of mother goddesses who rule fertility and creativity.

Dealgnaid (Celtic) *see* Beltine.

Death Star (Pawnee People, North America) *see* Tirawa.

Debabou and De Ai *De Babou* (Oceanic)
Also known as: *Na Atibu, Te-Po-ma-Te-Maki.*
First people. The children of Nareau. Against the orders of Nareau, this couple bore three children: the sun, the moon and the sea. *See also* Nareau.

Debee (India) *see* Devi.

Deber (Babylonian, Semite)
Pest god. Deber is worshiped with Resheph (also called Ninib) in festivals. Deber could be the same as the goddess Diban, of the Babylonian flood legend. Possibly connected with Yahweh.

Dech'tire *Dechterecul, Dechtire* (Celtic, Irish)
Mother of Cuchulain, by either Conchobar, Lugh, or Sualtam, and sister of King Conchobar. In another version she is the daughter of Maga and half-sister of Cuchulain. In other versions, she swallowed a mayfly and conceived Cuchulain, or she was impregnated by Lug's soul, or that in the form of a bird, she flew away with Lug. Cuchulain was born by his mother's vomit. Dech'tire had an enormous appetite, as did her fifty female attendants. She had the ability to change herself and the women into birds. *See also* Cuchulain; Lugh.

www.ebook3000.com

Dechtire (Celtic, Irish) *see* Dech'tire.

Decima (Greek) *see* Fates.

Dechterecul (Celtic, Irish) *see* Dech'tire.

Deduska (Russia) *see* Domovoi.

Deduska Domovoy (Russia) *see* Domovoi.

Dedusky Domovoy (Russia) *see* Domovoi.

Dee (Celtic)
War or river goddess. Little known; there was a river of the same name.

Deganiwada (Huron, Iroquois People, North America) *see* Daganoweda.

Deianeira (Greek) *see* Deianira.

Deianira *Deianeira, Dejanira* (Greek)
She is the daughter of Dionysus or Oeneus and Althaea. Her children by her second marriage to Heracles are Ctesippus, Hyllus, and Macaria. The goddess of the hunt, Artemis, transformed Deianira into a guinea fowl after she accidentally killed Heracles and committed suicide. *See also* Althea; Calydonian Boar Hunt; Heracles; Nessus.

Deidamia (A) (Greek)
Another name for Astydameia. *See* Astydameia (B).

Deidamia (B) (Greek)
When Achilles, her lover, died, she married Helenus. Deidamia is the mother of Pyrrhus.

Deidamia (C) (Greek)
Her parents are Bellerophon and Philonoe, her siblings, Hippolochus, Isander, and Laodamia. She married Evander, and became the mother of Dyna, Pallantia, Pallas, Roman and Sarpedon II.

Deimachus (A) (Greek)
He is the father of Autolycus, Deileon and Phlogius. *See also* Autolcyus.

Deimachus (B) (Greek)
His wife is Aeolus and his son is Enarete. *See also* Aeolus (A).

Deimos *Deimus* (Greek)
God of fear and dread. Deimos is the son of the god of war, Ares, and the goddess of love, Aphrodite. His siblings are Pallor, the god of fear; Anteros, the god of passion; Enyo, the goddess of war; Eros, the god of love; and Harmonia and Phobos. He accompanied his father and his brother, the god of fear, Phobos, into battle. *See* Anteros; Aphrodite; Ares; Harmonia (A); Phobos.

Deion (Greek)
King of Phocis. Deion is the son of Aeolus and Enarete. He has six brothers and seven sisters. His spouse is Diomede, and his children are Actor, Aenetus, Asteropeia, Cephalus and Phylacus. *See also* Actor (C); Aeolus (A); Canace; Diomede; Enaret.

Deione (Greek)
This is another name for Acacallis, thought by some to be the mother of Miletus by Apollo. *See also* Acacallis.

Deiphobus (A) (Greek)
His parents are Priam and Hecuba. He is the brother of Aesacus, Cassandra, Creusa, Hector, Helenus, Paris, Polyxena and Troilus. Deiphobus was renowned for his bravery during the Trojan War. He was forced to marry Helen when Paris died, and met his death by her former spouse, Menelaus. *See also* Cassandra; Creusa; Helen; Paris.

Deiphobus (B) (Greek) He is the son of Hippocoon (q.v.).

Deipyle (Greek)
She is the daughter of Adrastus and Amphithea. She married Tydeus, one of the Seven against Thebes, and became the mother of Diomedes. *See also* Adrestus; Diomedes.

Deipylus (A) (Greek)
Deipylus could be the son of the Argonaut Jason and Hypsipyle. He is said by some to be the son of Polyxo who was married to the king of Rhodes, Tlepolemus. She tried to avenge Deipylus' death at Troy by killing Helen. Instead, she killed a servant. *See also* Jason.

Deipylus (B) (Greek) He is the son of Polymnestor and Ilione.

Deivi (Prussian)
A respectful term which means goddess.

Dejanira (Greek) *see* Deianira.

Dekla (Latvia)
The goddess of fate who oversees infants and weeps when a birth is tragic.

Delia (Greek) This is an epithet of Diana. *See also* Artemis.

Deliades (Greek)
Bellerophon accidentally killed his brother, Deliades, the son of Glaucus and Eurymede. *See also* Bellerophon; Eurymede; Glaucus.

Delka (Latvia)
This gentle goddess cradles the newborn child.

Delling (Norse; Teutonic)
Also known as: *Dellinger.*
The dwarf gatekeeper at the castle of the Asmegir, Delling is the third husband of Nat (Night) and father of Dagr (Day). *See also* Asmegir; Dagr.

Dellinger (Teutonic) *see* Delling.

Delphic Oracle (Greek) *see* Lamia; Themis.

Delphin (Greek) *see* Amphitrite.

Delphyne (Greek)
Dragon-woman. Before her death by Apollo, she was responsible for guarding the sinews of Zeus, which had been stolen by Zeus' son, Aegipan, and the messenger of the gods, Hermes. *See also* Aegipan; Hermes; Typhon (A).

Dem-chho-pal-khor-lo-dom-pa (Tibet) *see* Dorje Phagmo.

Dema (Marind-anim People, New Guinea)
Dema is the term given to the divine creators and primordial beings of mythical times. They are depicted in human form, and sometimes as animals or plants.

Demarus (Greek) *see* Melkart.

Demavend, Mount *Demavend, Mount* (Persia) *see* Verethraghna, Angra Mainyu, Azhi Dahaka and Thrita.

Demavend, Mount (Persia) *see* Verethraghna, Angra Mainyu, Azhi Dahaka and Thrita.

Demeter (Greek)

Also known as: *Brimo, Centeotl* (Mexican), *Ceres* (Roman), *Deo, Doso, Kore, Kore-Persephone, Isis* (Egyptian).

Demeter (the Roman Ceres), is one of the great Hellenic divinities. She is the Greek goddess of agriculture and vegetation, protector of marriage, and corn goddess. The daughter of Cronus and Rhea, she was swallowed by her father and rescued by Zeus. Her daughter Persephone's name was kept secret; she was known as Kore, which means "the girl." This gave Demeter a double name; Kore-Persephone as Demeter is identified both with herself and with her daughter. Persephone was kidnapped by the lord of the underworld, Hades. Demeter requested Zeus' aid in returning her. Initially, he refused. She left Olympus grief-stricken and wandered the earth while the human race starved. She used the name Doso when she discarded her duties as a goddess and went to live among mortals. As Doso the Cretan she was the nursemaid of Demophon. She attempted to make the boy immortal by holding him in a magic fire each night. When his mother, Metaneira, saw them she screamed and the spell was broken. Demeter revealed herself to Metaneira. She then instructed that a shrine be built for her at Eleusis. When it was completed she lived in it. Demeter may have initiated the Eleusinian mysteries. It is said that she taught the prince of Eleusis, Triptolemus, the art of corn cultivation. He in turn spread his knowledge to the Greeks and the rest of the world. Zeus finally relented and sent Hermes to bring Persephone back. As she had eaten pomegranate seeds, food of the underworld, she had to spend one-third of the year below ground. Demeter, in another legend was the daughter of Uranus and Gaea, and sister of Hades, Hera, Hestia, Poseidon and Zeus. Demeter is said to be the mother of Plutus and Philomelus by Iasion. Known as mare-headed, her union with Poseidon produced Arion, a black stallion. She had a son, Plouton (wealth), from her union with Iasion in a ploughed field. There is reference to the possibility of Demeter being the mother of Iacchus. In another myth, as Doso, she ate Pelops' shoulder by mistake and replaced it with an ivory shoulder. The name Brimo is also applied to Rhea, Hecate, and Persephone. Her legend is similar to that of Ashtar and Tammuz. Demeter is compared to the horse goddess Epona. *See also* Abas (C); Acheron; Angerona; Car; Cronus; Cybele; Erysichthon; Evander (B); Hades; Hecate; Hestia; Isis; Pelops; Persephone; Rhea; Styx; Tantalus (A).

Demiurge (Gnostic)

Also known as: *Metropator.*

Chief of the lowest order of eons. Demiurge is credited with introducing evil into the world. Some identify him with Jehovah.

Demne (Celtic, Irish) *see* Finn.

Demogorgon (Aborigine People, Australia)

An evil spirit, Demogorgon haunts graves at night. He strolls about in skeletons of the dead by day, and bites the unwary in the stomach.

Demoleon (Greek)

Killed in the Trojan War, he is the son of Antenor and Theano. *See also* Acamas (B); Agenor; Glaucus; Laocoon; Polydamas.

Demonice (Greek)

Her parents are Agenor and Epicasta, her siblings, Hippodamus, Porthaon, and possibly Thestius. By Ares, she is the mother of Evenus, Molus, Pylus and Thestius. *See also* Ares; Crethus.

Demons *Daimon*

In Babylonian mythology are included the vampire (Lamashtu), Alu (ghost of the breasts), Namtar (ghost of the throat), Uttuka (the shoulder), Gallu (the hand), Elimmu (the bowels), Rabisu (a spy), Ahhazu (the seizer), Labasu (the overwhelmer), Lilu (male lasciviousness) and Lilitu (female lasciviousness). The list of demons is long and is covered under separate names. Not all are listed, but a partial reference follows. Persian: Al, Akwan, Div, Nar, Nara, Damrukh Nara, Shelan Nara, Mardash Nara, Kahmaraj Nara, Tahmurath, Jinn, Jann. Buddhist: Lokapalas, Yakshas, Kumbhandas, Dhritarashtra, Gandharvas, Virupaksha, Nagas, Garudas, Pretas, Hariti, Yakshini, Panchika, Tara. India: Asvins, Vala, Panis, Sorama, Asuras, Panaka, Tripura, Mahishasura, Vasuki, Daitya, Danavas, Kshatriyas, Rakshasas. Asia, including Japan and China: Ts'en-kuang, Chu-kiang, Sung Ti, Wu Kuan, Yen-lo, Pien-Ch'eng, P'ing-teng Tu-shi, Ts'en-kuang, Chaun-lun, Jizo, Kishimojin, Kubira or Kuvera, Oni, Gaki. These demons can be male or female, good or bad. Some can be regarded as gods and goddesses in their own right. *See also* Bhut (India); Daemon (Greek); Jinn (Persian); Satyrs (Greek).

Demophon *Demophoon* (Greek)

Joint king of Melos. Demophon is the son of Theseus and Phaedra or Antiope (Theseus' mistress). He secured the Palladium from Diomedes for Athens. When Troy fell, Demophon was madly in love with Laodice. On a stopover in Thrace, on his way home from Troy, he met and fell in love with Phyllis. When he left her, she committed suicide. *See also* Acamas (A); Antiope; Laodice.

Demophoon (Greek) *see* Demophon.

Dendrites (Greek)

"He of the Trees." This is an epithet for Dionysus (q.v.).

Deng (Dinka People, Africa)

Also known as: *Deng-dit, Diing, Dinga-dit.*

God of Rain. Birth deity. Deng is the son of the goddess Abuk. He is in charge of the food-producing earth. Some say he is the ancestor of all the Dinka people and that lightning comes from his club. In one version as Deng-dit he appears as the creator god. His consort is L'wal, the essence of evil. Deng-dit instructed L'wal to form mankind from a bowl of fat. He left the bowl unguarded. L'wal appropriated it and created caricatures of Deng-dit and Abuk's creatures. Abuk was an evil spirit, said to be the grandchild of L'wal. Compare Deng to the Yoruba deity, Shango. *See also* Abuk.

Deng-Dit (Dinka People, Africa) *see* Deng.

Denga (Africa) *see* Aywil.

www.ebook3000.com

Denkart (Zoroastrian) *see* Bundahish.

Deo (Greek) An epithet of Demeter.

Deohako (Seneca People, North America)
They are the spirits of corn, beans and squash who lived together on a hill. Onatha, the spirit of corn, wandered away one day looking for dew. The evil spirit Hahgwehdaetgah (an alternate name for Taweskare) abducted her and took her underground. The sun searched for and found her. However, she must reside in the cornfields until it is ripe. Some say this is the collective name for the three daughters of the earth-mother. *See also* Yoskeha and Taweskare.

Derceto (Middle Eastern) *see* Atargatis.

Derketo *Derceto* (Middle Eastern) *see* Atargatis.

Dervaspa *Drvaspa, Gosh* (Zoroastrian; Persia)
A Yazata, and the guardian of cattle, he personifies the soul of the bull. *See also* Gaya Maretan; Yazata.

Destroyer, The (Persia) *see* Mahrkusha.

Deucalion (A) (Greek)
Survivor of the nine-day Deluge. He is the son of Prometheus. His mother was either Hesione, Pronoea or Clymene. His spouse is Pyrrha, the first mortal woman born. Their children are Amphictyon, Hellen, Pandora, Protogeneia and Thyia. Deucalion was issued a dictate from the gods to build an ark. He followed instructions and with Pyrrha they were the only survivors of the Deluge. Their ark landed on Mount Parnassus. The goddesses advised them to cover their heads and throw the "bones of their mother" behind them. They did not have bones, so instead they threw stones. These stones became the new human race. Usually Deucalion and Pyrrha are shown as a pair. *See also* Acacallis; Aeolus (A); Ariadne; Minos; Pasiphae; Prometheus; Telchines.

Deucalion (B) (Greek)
The Argonaut son of Minos and Pasiphae.

Deus (Greek) *see* Zeus.

Deus Clavigerus (Roman) *see* Janus.

Dev (India) *see* Daevas; Devas (A); Devas (B).

Deva-Kanya (India) *see* Savitri (B).

Deva-Kanyakas (India) *see* Devis.

Deva-Matri (India) Mother of the Gods. *See also* Aditi.

Deva-Parvata (India)
Sacred Mountain. *See also* Meru Mountain.

Devak (India)
A guardian deity, the Devak takes the shape of an animal, tree or the tool of a trade. It is considered an ancestor or head of the household and is usually worshiped at the time of marriage or when moving into a new home.

Devaka (India) *see* Devaki.

Devaki (Hindu; India)
Also known as: *Aditi, Apsarases, Deywuckee, Dhriti, Nit, Niti.*

Devaki is the daughter of Devaka and the youngest of seven sisters. She became the spouse of Vasudeva and the mother of a daughter, Subhadra, and eight sons. Her first six sons were killed by her cousin, King Kansa of Mathura. Her seventh child, Bala-Rama was conceived by her, but placed in the womb of and born by Rohini, the daughter of Rudra and the second wife of Vasudeva. When Kansa heard of her eighth pregnancy, he imprisoned Devaki and Vasudeva. At birth, her eighth child, Krishna, assumed the form of Vishnu and arranged, with the assistance of the gods, that he replace the baby daughter born to the poor cowherds Yasoda and her mate Nanda with himself. When Kansa heard of Devaki's delivery and found that she had given birth to a female child, he set the family free. The female baby took the form of the goddess Devi and announced to Kansa that he had been outwitted and that his future enemy had escaped. Kansa took the precaution of ordering all the male babies in the city to be killed not realizing that Krishna was safe in the forest with Yasoda and Nanda. Devaki is closely connected with Aditi and is sometimes said to be an incarnation or avatar of this goddess. Samnati, one of Daksha's numerous daughters, is also associated with Devaki. *See* Rudra for details about Rohini. *See also* Aditi; Adityas; Apsarases; Bala-Rama; Daksha; Kansa; Krishna; Subhadra; Vishnu.

Devananda (India) *see* Mahavira.

Devanganas (India) *see* Devis.

Devarishis (India) *see* Rishi.

Devas, The (A) *Daevas, Daiva or Dev* (singular); *Devis* (feminine); (Buddhist, Jain, Hindu, Vedic; India)
In the Vedas, the Devas were divine spirits of good and later became known as nature spirits. The name means "bright one." They are the masculine counterpart of the Devis and their leader is Indra. The Devas were prominent in the Churning of the Ocean of Milk. They enlisted the help of the Asuras (demons) by promising them a potion of soma, the sacred elixir of the gods. Even though the Asuras were suspicious of their intentions, they helped them dismantle Mount Mandara, which was used as the churning stick. The Asuras also enticed Vasuki the serpent from his underwater abode so he could be used as the churning instrument. Vishnu instructed the Devas to take his head and the Asuras, the tail. The Asuras did not like the arrangement and insisted on changing places with the Devas. This is what Vishnu had hoped they would request, for if the Asuras gained access to the magic soma, it would have given them powers equal to the gods. When the churning progressed, the Asuras were suffocated by the hot air from Vasuki's breath while the Devas at his tail were cooled by ocean air. In some versions the Devas are Dyaus (day) and Prithivi (earth). There are thirty-three Devas, eleven in each of the three Hindu worlds, although sometimes their numbers are given as eight or twelve. The Devas are said by some to be associated with the sun, as are the Gandharvas, Apsarases, Yatudhanis and Gramanis. *See also* Asuras; Daevas; Devas (B); Devis; Indra; Kurma (regarding Churning of the Ocean of Milk); Mandara Mountain; Vasuki; Vishnu.

Devas, The (B) (Zoroastrian; Persia)
In Persian mythology, the Devas were malevolent spirits,

genii of evil, created as counterparts of the Amesha Spentas by Angra Mainyu, who ruled over them. Other names are given: Divs, Drauga, Druj, and Durugh.

Devasena (India)
Also known as: *Kaumari*; *Sena*. *See also* Karttikeya.

Devatas (India) *see* Devis.

Devayoshas (India) *see* Devis.

Devee (India) *see* Devi.

Devera (Roman)
This goddess rules the brooms used to purify ritual sites.

Devi *Debee, Devee* (Brahmanic, Dravidian [possibly], Hindu, Vedic; India).

Also known as: *Ambika, Bhairavi* ("Terrible"), *Bhargavi* (Wife of Shiva), *Bhavani, Bhowanee, Bhowani, Bhuta-nayaki* (Spirit Leader), *Bhuvana-Matri* (Mother of the World), *Bhuvanisvari* (Mistress of the World), *Brahmani* (Wife of Brahma), *Bhramara* (Relating to the Bee), *Chandi* ("Fierce"), *Chinnamastica, Dakshaja* (Born of Daksha), *Dakshina* (Right-handed), *Devi-Uma, Devi-Uma-Kali, Digambari* (Clad with the Quarters), *Doorga, Durga* (Inaccessible), *Eka* (One), *Gauri* (The Golden Lady), *Gowree, Idika* (Mother), *Jaganmatri* (Mother of the World), *Kalee, Kali* (The Black Mother), *Kali-Durga, Kalika, Kamakshi, Kotari* (Naked), *Kumari* (The Maiden), *Lilavati* (Charming Woman), *Ma, Madira* (Of Spiritous Liquor), *Maha-Maya* (Illusion), *Maha-isvari* (Great Potentate), *Mahakalee* (The Great Black One), *Maharajni* (Great Queen), *Mangala* (The Auspicious One), *Mari, Matri* (Mother), *Menakshi, Minakshi* (Fish-Eyed), *Minakshidevi, Mridani, Nairriti* (South-Western), *Parbati, Parvati* (The Mountaineer), *Parwati, Purbutty, Rudrani* (Wife of Rudra) *Shakti, Sarasvati, Sarvamangala* (Universally Auspicious), *Sarvani, Sarvavasini, Sati* (Virtuous), *Shakti, Surisi, Surisvari* (Divine Lady), *Sutty, Tariki* (Delivering), *Triambika* (Wife of Rudra-Shiva), *Triganini* (Mother of Three Worlds), *Uma* (Light), *Vaishnavi* (Wife of Vishnu), *Vari* (Fair Faced), *Vigaya* (Victorious), *Vindhyavasini, Vindhyavarini* (Dwelling in the Vindhya Mountains), *Yogisvari* (Adept in Yoga).

Devi is known as a "Great Mother" or "Universal Mother." She is one of the most important of the Indian goddesses. She is a creator, maintainer and destroyer. In one of her earliest forms, Devi as Ambika is associated with Rudra and is said by some to be his wife and possibly his sister. She appears as the early fertility goddess Gauri, meaning the "Golden Lady" or the "Shining One." She is the granddaughter of Mahakali the "Great Black One" (also an epithet for Devi-Uma-Kali). She is the daughter of Sirsootee, the sister of Bishen and possibly the mother of a daughter, Manasa. Gauri is later used as a first name for Parvati (another aspect of Devi) when she rides on a tiger. We encounter her as Sati, the daughter of Daksha and the devoted wife of Shiva. After the death of Sati, she is reborn as Parvati the youngest daughter of Mena, the sister of the goddess Ganga, once again the wife of Shiva, and according to some legends, the mother of Karttikeya (also known as Skanda) and Ganesha. As Uma, the wife of Shiva, her skin is golden and she personifies light and beauty. As Durga, once again the wife of Shiva, she is yellow, wears a menacing expression, rides a tiger and has ten arms. Kali, the "Black Mother," appears as the goddess of destruction and wife of Shiva. Devi also appeared as the female baby of Yasoda, the wife of Nanda who nurtured the baby Krishna when the demon Kansa wanted to kill him. Devi is worshiped as Mari the goddess of death, by the Korwas, also known as Korama people of India. Devi is also a name signifying any female deity. Devi as Kali-Durga killed the buffalo monster Mahisasura (Mahisha) who threatened to undo the world. Devi is depicted with four faces and four arms. She wears a diadem of shining colors. Her emblems include the bow, arrow, bowl, goad, hook, ladle, noose, prayer-book, rosary, sword and peacock's tail. For Minakshi, *see* Kuvera. *See also* Ana Purna; Ardhanari-Ishvara; Bhavani; Chandi; Daksha; Devaki; Devis; Durga; Ganesha; Ganga; Gauri; Kali; Kansa; Karttikeya; Krishna; Kumari; Laksahmi; Manasa; Mari; Maruts; Parvati; Rudra; Sarasvati; Sati (A); Shakti; Shiva; Sitala; Vishnu.

Devi-Kali (India) *see* Kali.

Devi Sri (India) Noble Goddess. *See also* Lakshmi.

Devi-Uma (India) *see* Bhavani; Devi.

Devi-Uma-Kali (India) *see* Devi.

Devil
Also known as: *Belial, Eblis, Iblis, Lucifer, Nergal, Satan, Sathan, Sathanas, Shaitan* (Islamic), *Shetan* (Islamic).

Evil spirit. Possibly from the Greek Diabolos or from the Indian meaning of "little Deva or demon." The Jews called these demons Shedim or Liliths and S'eirim in the Old Testament. In the Teutonic language they are called Deopul, Diabul, Duibhal, Duwel, and Teufel. The Egyptian devil was Set. The Islamic Shaitan more often inhabits the bodies of females. It tempts women to disobey their spouses. To rid her of the spirit, the name of the spirit must be known and the woman must be beaten. Same as the Saxon Deopul, Diabul, Diubhal and the German Teufel. In Judeo-Christian belief, the devil is the principal of evil and the archfiend. *See also* Azazel; Satan.

Deving Isching (Latvia) God of Horses.

Devis, The *Deva* (masculine); (Buddhist, Hindu, Jain; India)
If the word Devi is used as a name, it refers to Kali, Parvati, Uma and Durga. It is sometimes used to describe a female angelic, heavenly or divine being. The Devis are the daughters of Aditi. Other Devic beings are the Deva-Kanyakas, the Devayoshas and the Devanganas. Also included are the Devatas, who are divided into the following classes: the Adhidevatas, Digdevatas, Grihadevatas, Mangadevatas, Mantradevatas, Purvadevatas, Rajyadidevatas, Rakshodhidevatas, Sakunadevatas, Shastradevatas, Sthalidevatas, Ushodevatas, Vanadevatas, Vrikdevatas. The Vidyadevis are Devis who are described as Jain goddesses of knowledge. Gandhara is known as a Vidyadevis. In Cambodia, the Devatas are known as Thevadas. *See also* Aditi; Devas (A); Dorje-Naljorma; Durga; Kali; Parvati; Uma.

Devona (Celtic) River goddess. *See also* Sequana.

Devorgilla (Irish)
Her father, the king of Ireland, gave her to Cuchulain. He

www.ebook3000.com

rejected her and passed her on to another man. Wounded, she transposed herself and her female attendant into birds and they flew away. One day when Cuchulain was hunting, he threw a rock at the bird and it fell to earth and assumed the form of Devorgilla. The hero saved her life by sucking the stone from her flesh. In doing so, he swallowed some of her blood making them related by blood and therefore unable to have sex. *See also* Cuchulain.

Devourer of Amenti (Egypt) *see* Amit.

Devs (Armenian)
Also known as: *Ais, Char.*
Gigantic, shape-changing spirits, the Devs can appear as humans, serpents or in dreams as wild animals. They often have one or more eyes and seven heads. Usually harmful, sometimes they appear foolish and harmless. Their presence can be detected by insanity, itching around the throat, ear or tongue, sneezing or fainting. They can be deterred by cutting through the air with a sword or a stick. In the theological sphere the Devs are harmful spirits who are constantly riddling the path of truth with their snares. *See also* Arlez; Daevas; Hambaris; Kaches.

Dewtahs, The (India) Celestial Beings. *See also* Aditi.

Deywuckee (India) *see* Devaki.

Dhammai People, India — Creation Legend *see* Shuznagnu and Zumiang-nui.

Dhammapada, The (Buddhist)
This book contains the teachings of Gautama Buddha. The Pali version of *The Dhammapada,* which contains 423 verses divided into twenty-six chapters, is the most widely known. The Tibet and Chinese versions vary slightly from the Pali version. *See also* Buddha.

Dhana-Pati (India) *see* Kuvera.

Dhanada (India) "Giving Wealth." *See also* Kuvera.

Dhanus (India) The Sacred Bow. *See also* Kurma.

Dhanvantari (Hindu; India)
He is the physician of the gods and the keeper of soma. *See also* Kurma.

Dhara (India) *see* Vasus.

Dharani (India) *see* Lakshmi; Parashur Rama.

Dharini (Tantrayana Buddhism) Goddess of Memory.

Dharma (Buddhist, Hindu; India)
Dharma, a sage, and the personification of law and justice, was a judge of the dead. He married a number of Daksha's daughters who became the mothers of children who personified virtue. With his mate Sraddha, the goddess of faith, he became the father of Kama, the god of love. Dharma is the god who appears when mortals are being tested for strength of character. In the *Mahabharata,* Dharma is the father of the chief of the Pandavas, Yudhishthira. Dharma is an ancient title of Yama, who in his role of judge of the dead is known as Dharmaraja. In Buddhism, Dharma (The Dhamma) is the Ultimate Reality and the formulation of Buddha's teachings as presented in the sutras. *See also* Daksha; Dwaparayuga; Kama; Kunti; Medha; Narayana (C); Pandavas; Sraddha; Tretayuga; Vyasa; Yama; Yudhisthira.

Dharma Palas (India) *see* Lhamo.

Dharmacakra (India)
Soft-voiced lord of speech. *See also* Manjusri.

Dharmapala (Buddhist; India)
Depicted as hideous giants with huge teeth, tongues sticking out, and hair standing on end, the Dharmapala are the "Protectors of Religion." *See also* Vajrapani.

Dharmaraha (India) *see* Mitra; Yama.

Dharmaraja (India)
King of Virtue. *See also* Amrtakundali; Yama.

Dharmavajra (India) *see* Samantabhadra.

Dhartarastra *Jikokuten* (Japan), *Yul-khor-bsrun* (Tibet); (Buddhist, Hindu; India)
Dhartarastra dwells in the Buddhist universe of Chakravala. He lives with the other guardians in the Heaven of the Four Great Kings near the peak of the sacred Mount Meru. This plane is populated with pretas (ghosts), animals, demons and men. The Four Great Kings guard the entrance to Sukhavati, the Buddhist paradise. Dhartarastra, lord of the Gandharvas (heavenly attendants), is the guardian of the east. Another Great King is Virudhaka, lord of the Kumbhandas (giant demons and gnomes), who is the guardian of the south. Virupaksha, lord of the Nagas (dragons or serpents) is the guardian of the west. Vaisravana, lord of the Yaksas (demon disease carriers) is the guardian of the north. As a group the guardians are known to the Hindu and Buddhist as Lokapalas. In the Hindu tradition, Agni guards the north, Indra the east, Varuna the west and Yama the south. In some traditions, Kubera guards the north and Ravana is the guardian of the fifth position, which is located in the center. Dhartarastra is white in color. He wears a plumed helmet, holds a stringed instrument and feeds on incense. *See also* Chakravala; Naga Naga Knaya; Sukhavati; Virudhaka; Virupaksha.

Dharti Mai *Bhudevi, Dharti Mata*; (Hindu; India)
Mother Earth who supports the earth. Her presence is everywhere in the ground. Pregnant women are placed upon her at the time of delivery. Pigs, goats, and fowl are sacrificed to her. She is worshiped as a pile of stones or a pot in many villages. *See also* Prithivi; Sinivali; Vishnu.

Dharti Mata (India) Earth Mother. *See also* Dharti Mai.

Dhata (India) *see* Prajapati; Surya.

Dhatr (India)
Creator of All Things. *See also* Prajapati; Surya.

Dhatri (Vedic; India)
Originally, Dhatri was sometimes included in the lists of Adityas. Later, he was known as a minor deity of health and domestic harmony. *See also* Adityas.

Dhenuka (India) King of the Hayas. *See also* Krishna.

Dhisana (Vedic; India) Goddess of plenty.

Dhritarashtra (India)
He is the blind son of Vyasa and Ambika, mate of Gandhari, and father of one hundred sons. The eldest son, Duryodhana, was the leader of the Kauravas, who fought the Pandavas in the war of the *Mahabharata*. *See also* Bhima (A); Bhishma; Duryodhana; Kauravas; Kunti; Pandavas; Radha; Vyasa.

Dhriti (India) *see* Devaki.

Dhruvasinha (India) *see* Amrtakundali.

Dhumaketu (India) *see* Agni.

Dhumbarahi (Nepal) *see* Varahi.

Dhupa (India) *see* Ratnasambhava.

Dhupema (India) *see* Dhupa.

Dhurva (India) *see* Vasus.

Dhyani Buddha Akshobhya (Nepal) *see* Akshobhya; Dhyani Buddhas.

Dhyani Buddha Amitabha (Nepal) *see* Dhyani Buddhas.

Dhyani Buddha Amoghshiddhi (Nepal) *see* Amoghshiddhi; Dhyani Buddhas.

Dhyani Buddha Vajrasatwa (Nepal) *see* Vajrasatwa.

Dhyani Buddhas *Dhyanibuddhas*
Also known as: *Panch Buddhas* (Kathmandu, Nepal), *Tathagata* (Nepal); (Buddhist; Nepal)
The five Dhyani Buddhas are abstract aspects of Buddhahood which emanate from the self-existent Adibuddha. From the meditations of the knowledge-holding Dhyani Buddhas evolved the five Dhyanibodhisattvas, who are the five Buddhist creators of the universe. The five Dhyani Buddhas are Vairocana, Akshobhya, Ratnasambhava, Amitabha and Amoghasiddhi. The consorts (saktis) of the Dhyani Buddhas are known as Dhyanibuddhasaktis. Vairocana's sakti is Vajradhatvisvari, Akshobhya's sakti is Locana (Buddhalocana), Ratnasambhava's sakti is Mamaki, Amitabha's sakti is Pandara, and Amoghasiddhi's sakti is Tara. The Dhyani Buddhas represent the five Skandhas. The Skandhas are the five cosmic elements: Rupa (form), Vedana (sensation), Samjna (name), Sanskara (conformation), and Vijnana (consciousness). The Dhyani Buddhas are exceptionally popular in Nepal where they are depicted in every shrine, often found in courtyards and in the main entrance of a Buddhist home. A Dhyani Buddha may incarnate as a mortal manifestation known as a Manushi-Buddha. The Dhyani Buddhas are shown together seated on an open lotus in the lotus position with their palms and soles are turned upwards in the dhyana mudra. Their bare heads are crowned by thick curls. Their eyes are usually half-closed. Sometimes they hold a cup in the open hand, symbolizing openness. Their undergarment, held by a scarf, reaches from the chest to the knee. The outer garment is a monk's costume, which leaves only the right arm bare. Sometimes a sixth Dhyani Buddha, Vajrasatwa, is added. Generally Vajrasatwa is regarded as the priest of the five Dhyani Buddhas. For more specific descriptions, see the individual names of the deities. *See also* Adibuddha; Akshobhya; Amida; Amoghasiddhi; Avalokitesvara; Boddhisattvas; Dhyanibodhisattvas; Maitreya; Mamaki; Manjusri; Manushi-Buddhas; Pandara; Ratnasambhava; Samantabhadra, Tara (B); Vairocana; Vajrapani; Vajrasatwa.

Dhyanibodhisattvas (Buddhist; Nepal)
The five Dhyanibodhisattvas evolved from the Dhyani Buddhas and are known as the creators of the cycles of the world. They are Avalokitesvara, Ratnapani, Samantabhadra, Vajrapani, and Visvapani. Over time, the number of Dhyanibodhisattvas increased. In Northern Buddhist temples a group of eight Dhyanibodhisattvas is often seen standing to the right of an important deity. They are Akasagarbha, Avalokitesvara, Kshitigarbha, Mahasthamaprapta, Maitreya, Manjusri, Sarvanivaranaviskambhin, Trailokyavijaya. Vajrapani or Samantabhadra are sometimes substituted for one of the eight. They wear a five-leafed crown and are garbed in a scarf on the upper body, and a shawl over the lower limbs. They wear earrings, bracelets, armlets, and anklets. *See also* Boddhisattvas; Dhyani Buddhas; Kshitigarbha; Maitreya; Manjusri; Samantabhadra; Trailokyavijaya; Vajrapani.

Dhyanibuddhas (Nepal) *see* Dhyani Buddhas.

Dhyanibuddhasaktis (Nepal) *see* Dhyani Buddhas.

Di (Roman) *see* Dii.

Di-do (Tibet) *see* Gro-bdog.

Dia (A) (Greek)
She is the wife of Ixion, and mother of Pirithous. She was seduced by Zeus, who was in the shape of a horse. *See also* Ixion.

Dia (B) (Celtic) *see* Aesar (B).

Dia Griene (Scotland)
She is the daughter of the sun who was a prisoner in the Land of the Big Women and escaped with Cailleach, who was disguised as a fox. *See also* Cailleach Bheur.

Diakoku *Daikoku* (pre–Buddhist, Buddhist, Shinto; Japan)
Also known as: *Daikoku Sama, Daikoku Ten, the Great Black Belt Deity.*
Diakoku combined with Okuni-Nushino-Mikoto to become the god of wealth and one of the seven gods of luck known as the Shichi Fukujin. His son, the god of labor Ebisu, is also a Shichi Fukujin. Diakoku, as well as being a god of wealth, is a god of happiness, war, artisans, and merchants. He is a god of heaven and the north. Diakoku is depicted as dark skinned with swollen ear-lobes (a symbol of omniscience), heavy-set, with a smile on his face. He is also shown as a soldier holding a pagoda and a lance or shown with a rice bale and a protruding stomach. The rice bale symbolizes the infinite source of wealth. He is also shown carrying a mallet which grants good fortune and happiness. Diakoku is often accompanied by a rat who acts as his messenger. (In the Hindu and Buddhist tradition a rat vomiting jewels is a rain symbol.) His likeness formed in gold is carried as a charm for prosperity. His colors are black and blue. He may be one of the Shinto kami (deity), as Okuni-Nushino-Mikoto is a Shinto kami. *See also* Ebisu; Hiruko; Shichi Fukujin; Stupa.

www.ebook3000.com

Opening the Bridge and Regulator Channels and Extending your Chi Outwards

The second section opens and strengthens four of the Eight Extraordinary Channels: the Yin and Yang Bridge and Regulator Channels. This section also teaches the student to extend and take in the cosmic Chi and emit Chi out of the body for healing others. This ability is the heart of Cosmic Healing Chi Kung practice.

Opening and Energizing the Governor and Functional Channels

The third section enhances the energy in the points along the two channels used in the Microcosmic Orbit. Opening the Microcosmic Orbit strengthens and balances one's own energy, and prepares one to heal others. Practicing this section will be of great help with the Microcosmic Orbit Meditation.

Activating One Finger Art and the Chi Belt

The fourth section of Cosmic Healing Chi Kung activates the hands and you will practice emitting Chi from each of your fingers and opening the "Chi Belt." This channel is also known as the Belt Route or Girdle Vessel.

Diamond Kings (Buddhist; China)
Also known as: *Kings of Hell, Ssu Ta Chin-Kang.*
The Diamond Kings guard the register of judgments. *See also* Ssu Ta Chin-Kang.

Dian Cecht (Celtic) *see* Dia'necht.

Diana (Roman)
Also known as: *Artemis* (Greek), *Aventina, Cynthia, Lala* (Etruscan), *Lucina* (Light), *Phoebe, Selene, Tergemina, Trivia* (Three Ways).
Goddess of forests and groves. Goddess of slaves and plebeians. Diana is the daughter of Jupiter and Latona. She is the Roman equivalent for Greek goddess of hunting and the moon, Artemis. Diana's dwelling place is the forest. She loved Endymion, Pan, and Orion. She had three aspects, Hecate, Luna, and Phoebe. Some say she was a goddess of childbirth and the birthing of animals. Aventina is Diane as she was worshiped on Aventine Hill in Rome. Her epithet, Tergemina, refers to her triform divinity as a goddess of heaven, earth, and hell. She is generally shown as a woman, sometimes with three heads, a horse, a dog, and a boar. Her chariot is drawn by heifers, horses, two white stags, or a lion and panther. *See also* Actaeom; Adonis; Artemis; Atalanta; Ceto; Egeria; Gefion; Mama Quilla.

Diancecht (Celtic) *see* Dia'necht.

Dianchecht (Celtic) *see* Dia'necht.

Diane of Crete (Greek) *see* Isis.

Dia'necht (Celtic) *Dian Cecht, Diancecht, Dianchecht.*
Also known as: *The Leech.*
Dia'necht, the god of medicine and divine physician, is a member of the Tuatha De Danann, an ancient race of deities. He is the father of Airmid, Cethe, Cian, Cu, Etan, and Miach, and the grandfather of Lugh. Their king, Nuada, had his hand severed during a brutal battle with the demonic giants, the Fomorians. Dia'necht, with the assistance of Credne, the divine bronze worker, created a silver prosthesis for the ruler. However, a rule of sovereignty was that the monarch could not have any physical defects, so he was forced to resign. In an attempt to mend fences with their former enemies, the Tuatha's offered the throne to Bress, the son of the Fomorian king. This move almost crippled his subjects as he was a greedy, dictatorial monarch. In a twist of fate, Dia'necht's son, Miach, also a brilliant surgeon, was able to restore Nuada's severed hand. Dia'necht, insanely jealous, viciously attacked his son on three separate occasions and Miach survived. The fourth time, Dia'necht's assault generated a grave head injury and his son died. It is said that three hundred and sixty-five (365) different herbs grew on his grave which his sister Airmed tended. Meanwhile, the people removed Bress, who returned to his father's undersea kingdom to draw up battle plans, and King Nuada regained his throne. *See also* Asclepius; Bress; Cian; Credne; Lugh; Tuatha De Danann.

Dianus (Roman) *see* Janus.

Diarmait (Celtic)
He was the friend of Finn who was subsequently slain by him. *See also* Finn.

Diarmuid (Greek) *see* Adonis.

Diaus (India) *see* Dyaus.

Diban (Babylonia) *see* Deber.

Dice (Greek) Another spelling for Dike (q.v.).

Dictyanna *Dictynna* (Greek)
Also known as: *Britomartis.*
Dictyanna is an ancient Cretan goddess who is a follower of Artemis. She invented fishing nets. *See also* Artemis; Britomartis.

Dictynna (Greek) *see* Dictyanna.

Dictys (Greek)
The son of Magnes and a Naiad, he is the brother of Polydectes, and husband of Clymene. He was a fisherman in Crete until Perseus, the son of Zeus and king of Mycenae and Tiryns, made him the king of Seriphus in Crete. Dictys had rescued Perseus when he was an infant who had been thrown to sea by Acrisius. *See also* Acrisius; Clymene; Perseus; Polydectes.

Dido *Didon, Didone* (Greek)
Also known as: *Elissa* (possibly).
Founder and former queen of Carthage, Dido is the sister of Pygmalion and wife of Sychaeus. She is the daughter of Belus or Mutgo. Dido married her uncle, Acherbas (also called Sicharbas), whom Pygmalion killed for his money. When Aeneas was travelling to found the Roman race, he stopped in Carthage to visit her. She fell deeply in love with him. When he left to fufill his destiny, she threw herself on a flaming funeral pyre. Dido may have been worshiped as a goddess of love. *See also* Aeneas; Agenor (A); Pygmalion.

Didon (Greek) *see* Dido.

Didone (Greek) *see* Dido.

Digambara (India) An epithet of Shiva.

Digambari (India) *see* Devi.

Digdevatas (India) *see* Devis.

Dih (India) *see* Gramadeveta.

Dihwar (India) *see* Gramadeveta.

Dii Di (Roman)
Dii is the Roman name for the twelve great Greek gods: Ceres (Demeter), Mars (Ares), Phoebus (Apollo), Diana (Artemis), Mercury (Hermes), Venus (Aphrodite), Jupiter (Zeus), Minerva (Athena), Vesta (Hestia), Juno (Hera), Neptune (Poseidon), and Vulcan (Hephaistos).

Diing (Dinka People, Africa) *see* Abuk; Deng.

Diinga (Africa) *see* Aywil.

Dike (A) *Dice* (Greek)
Goddess of justice. The daughter of Zeus and Themis, Dike is one of the three Horae. Her sisters are Eirene and Eunomia. Dike is the personified goddess of justice. *See also* Dike (B); Horae; Themis.

Dike (B) (Greek)
Also known as: *Astraea.*
She is the daughter of Zeus and Themis, who was also called Dike. *See also* Dike (A).

Diko (Russia) *see* Domovoi.

Dikpalas *Dig-Gaja* (Buddhist; Nepal)
In Nepal, the Dikpalas are invoked in every religious ritual, particularly those associated with buildings. They are the guardians of the four corners and four directions. The guardians of the four corners are Agni, god of fire, ruler of the southeast; Vayu, god of wind, ruler of the northwest; Isana (a form of Shiva), the northeast; and Nairitya, (also spelled Nairrita) god of dread, the southwest. The gods of the four corners are: Indra, king of gods who presides over the east; Varuna, lord of the ocean, over the west; Kuvera, god of wealth, over the north; and Yama, god of death over the south. The eight elephant deities who support the eight corners of Dik (the universe), are also known as Dikpalas. They are Airavata, Pundarika, Supratika, Vamana, Kumunda, Anjanma, Pushpadanta and Suryabhauma. *See also* Agni; Indra; Kumunda; Kuvera; Lokapalas; Navagrahas; Varahi; Varuna; Vayu; Yaksha and Yakshini; Yama.

Diksha (India) *see* Soma.

Diktynna (Greek) *see* Dictyanna.

Dil (Ireland) Cattle goddess.

Dilbar (Babylonia)
This is Ishtar as the "Evening Star" who provokes war.

Dilmun (Sumerian)
Dilmun, the home of the gods, is the garden of paradise. Enshag (son of Enki and Ninhursag) is chief of this region. After the seven-day flood which destroyed humanity, King Ziusudra (the Sumerian Noah), who survived, was made a god and lived in Dilmun. Some say Nabu was connected with Dilmun as a scribe. It is also said that Eden is located in Dilmun. Tagtug, the gardener in Dilmun, ate a forbidden plant and lost his right to immortal life. Dilmun is associated with Enki (q.v.). The *Epic of Gilgamesh* may refer to Dilmun. It is possibly the same as Eridu. *See also* Irkalla; Nabu.

Dina-Kara (India) "Day-Maker." *See also* Surya.

Dinas (Arthurian) *see* Vivien.

Dindymene (Greek) *see* Cybele.

Dindymus (Greek) *see* Cybele.

Ding (Africa) *see* Abuk.

Dinija (Crete)
"Mistress of Wild Things," possibly the original Earth Mother. Dinija appears in connection with Zeus on records at Knossos.

Dinka People, Africa — Creation Legend *see* Abuk.

Diomede (A) (Greek)
Her parents are Xuthus, "the thievish one," and Creusa. Her siblings are Achaeus, Ion, and Dorus (possibly). Through marriage to Deion, she became the mother of Actor, Aenetus, Asteropeia, Cephalus and Phylacus. *See also* Achaeus; Actor; Asteropeia; Cephalus; Deion; Xanthippe.

Diomede (B) (Greek)
She is the wife of Amyclas and the mother of Argalus, Cynortas, Leaneira, and Hyacinthus. *See also* Amyclas.

Diomedes (A) (Greek)
King of the Bistones of Thrace. His parents are Ares and Cyrene or possibly Asterie. The eighth labor of Heracles was to kill and eat the human-eating horses belonging to Diomedes. *See also* Ares.

Diomedes (B) (Greek)
Also known as: *Tydides.*
King of Aetolia. Greatest hero at Troy (after Achilles). One of the Epigoni. Made immortal by Athena. His parents are Tydeus and Deipyle, his wife is Aegialeia. At one point, he fell in love with Callirrhoe. Diomedes was also one of Helen's suitors. He took a fleet of eighty ships to Troy from Argos. With Acamas, he threatened war if Helen was not returned. *See also* Abderus; Acamas (A); Ares; Epigoni.

Dionae (Greek) *see* Dione.

Dione *Dionae* (Greek)
Also known as: *Aphrodite.*
Goddess of water (moisture). She is the daughter of Atlas or Oceanus and Tethys, or possibly of Uranus and Gaea. It is thought by some that she was the first consort of Zeus. If that is so, she would be the mother of Aphrodite. Dione married Tantalus and is the mother of Broteas, Niobe and Pelops. In the Pelasgian creation myth, Dione is coupled with Crius as the rulers of the planet Mars. She could be a pre–Hellenic Greek goddess of sexuality and inspiration, who was later replaced by Hera. She is sometimes identified with Diana. *See also* Broteas; Eurynome (A); Pelops; Tantalus (A).

Dionusos (Greek) *see* Dionysus.

Dionysus *Dionusos, Dionysos, Dyanysos* (Greek, possibly of Thracian or Semitic origin)
Also known as: *Antauges, Antheus, Anthios, Bacchus* (Roman, God of Wine and Revelry), *Bassareus* (Lydian; pertaining to clothing worn by Dionysus' followers), *Bromius* (the Roarer), *Cissos, Dendrites* (He of the Trees), *Dithyrambos* (He of the Double-door), *Eleusis* (pertaining to Eleusinian Mysteries), *Eleutherios, Euios, Iacchus, Iakchos, Isodaites, Karpios, Kubebe, Laphystios, Lenaeus, Lenaios* (said to be his most ancient name), *Liber* (Roman), *Liknites* (as the resurrected child), *Nuktelios, Nyktelios, Osiris* (Egyptian), *Perikionios, Phytalmios, Plutodotes* (Wealth-giver), *Puripais, Sabazius* (as Thracian Corn God), *Sykites, Thyoneus, Zagreus* (Cretan).
Fertility or earth god. God of wine. God of ecstasy. God of drama. Prophetic deity. Dionysus is the son of Zeus and Semele or possibly Demeter, the goddess of agriculture. Other women said to be his mother are Io, Thyone and Dione. As Eleusis, his parents were said to be Ogygus and Daeira. As Dionysus Zagreus, he is the son of Zeus and Persephone and appears in snake form. The most popular version of his legend is with Zeus and Semele as his parents. He married Ariadne, the daughter of Minos, who first loved the hero Theseus. They had six sons: Oenopion (it is possible that his father was Theseus), Phanus, an Argonaut, Ceramus, Peparethus, Staphylus, and Thoas. He was also the father of Hymen (Hymenaeus) the god of mar-

www.ebook3000.com

riage, possibly by Aphrodite, Deianira by Althaea who was the wife of Oeneus, he was possibly the father of Phlias by Araethyrea, of Narcaeus by Physcoa and of Arete. As a young man, the divine heritage of Dionysus was not recognized so he left Greece and traveled to Asia to develop his divine powers. His charisma inspired devotion wherever he went and he soon attracted a following and had numerous exciting adventures. Upon returning to Greece his empowerment was recognized by the deities and he was accepted as the son of Zeus and admitted to the company of the Olympians. He delighted in sharing his knowledge of the virtues of wine. He is depicted either as a bearded man or a youth with ivy leaves and grapes around his forehead, wearing a "nebris" (a fawn skin), and carrying a thyrsus (a pole with a pine cone or vine leaves decorating the top). Wine, particularly red wine, symbolizes blood and sacrifice and youth and eternal life. Grapes symbolize fertility and sacrifice, because from the grape comes the wine. Dionysus represented the fertile energy of all growing things and was eventually considered the god of the vine. The goat was central to the celebrations of Dionysus. It represented fecundity and lasciviousness. Worshipers tore the animal apart and ate it raw. The festivals provided the group with an opportunity to vent repressed inhibitions. View the depictions and symbols of Bacchus. For the circumstances surrounding Dionysus' birth by Semele, which is comparable to the circumstances surrounding Christ, Adonis, Moses, Perseus, and Llew Llaw, *also see* Semele. Dioynsus is sometimes associated with Osiris. He is compared to the Armenian Aramazd (q.v.). *See also* Althea; Antiope; Bacchus; Corybantes; Giants; Graces; Hymen; Naiads; Perseus; Satyrs; Serapis; Spantaramet; Theseus.

Dioscures (Greek) *see* Dioscuri.

Dioscuri *Dioscures* (Greek)
Also known as: *The Gemini Twins, Tyndaridae.*
The twins, Castor and Pollux, are known as the Dioscuri. *See also* Acastus; Castor and Pollux; Leda.

Dipamkara *Dipankar, Dipankara* (Buddhist; India)
The Buddha of the First World Cycle, Dipamkara, known as "The Enlightener" or "The Lightmaker" was born in the mythological city of Deepavati. He is said to have lived on earth for a million years. As a child, Gautama Buddha offered Dipamkara a handful of dust. It was at this time that Gautama made his decision to attain enlightenment. Dipankar Buddha is depicted Adhaya mudra (his right hand held up in the gesture of protection) and his left hand is Varada mudra (down with the palm facing out in the gesture of charity). He either sits or stands with a monastic garment draped over the left shoulder and wears a pleated flowing skirt. *See also* Buddha; Manushi-Buddhas.

Dipankar (India) *see* Dipamkara.

Dipankara (India) *see* Dipamkara.

Dirce (Greek)
Antiope was given to Dirce as a slave. Dirce is the wife of Lycus, a regent of Thebes. Their son is also known as Lycus. Dirce's husband killed Epopeus, Antiope's husband. In turn, Antiope's children killed Dirce by tying her to either the tails or the horns of an enraged bull. Dirce became a fountain. *See also* Antiope.

Dirona (Celtic) *see* Borvo; Sirona.

Dis (A) (Celtic, Norse, Greek)
Supreme deity. As a deity, Dis is thought to have originated with the Gauls or Celts. The Gauls claimed that they were direct descendants of this god. The Romans worshiped him as an underworld deity and a god of wealth. Dis is also a name used for the world of the dead and is often a name used for Pluto, which is another name for Hades. The Celtic Dis is depicted with the hammer (for creativity) and the cup (for abundance). *See also* Hades; Pluto, Tartarus. May be related to Dis Pater (Dispater). *See also* Aeracura; Hades.

Dis (B) The singular for Disir (q.v.).

Dis Pater *Dispater* (Roman)
Also known as: *Dis, Orcus, Pluto.*
Underworld deity and god of wealth. Dis Pater might have been called Dis and is possibly Celtic in origin. Not a fashionable god, he was named by Caesar and is thought by some scholars to have replaced an earlier Celtic goddess named Aeracura. Two of his aspects were Pluto (Plutos) the Greek god of the dead, and Orcus, the Roman deity of death. In some versions he was the chief of the underworld. His spouse is Persephone. Dis Pater is shown carrying keys and riding in a vehicle pulled by four black horses. Compare to Manes, Orcus and Pluto. *See also* Aeracura; Bel (B); Dis; Sucellos.

Disciplina (Roman) Goddess of discipline.

Discordia *Discord* (Roman)
Also known as: *Eris* (Greek).
Goddess of Strife. Discordia, the Roman goddess of strife, is identified with the Greek goddess of strife, Eris. Discordia was thought to be the consort of Mars. *See also* Adder; Ares; Eris; Hephaistos.

Disir (Teutonic)
Also known as: *Dis* (singular).
Disir is a term used to designate a certain group of goddesses who were concerned for the good of the home and family. The Valkyries and Norns were Disir. Certain goddesses were also called Disir, such as Freyja (q.v.). Special sacrifices were offered to the Disir. *See also* Norns; Valkyrie.

Dispater (Roman) *see* Dis Pater.

Dithrambos (Greek) *see* Dithyrambos.

Dithyrambos *Dithrambos* (Greek, Roman)
Also known as: *Bacchus* (Roman), *Dionysus* (Greek).
Dithyrambos is an epithet of Bacchus, the god of wine. It is also the name for a wild song sung by the Bacchanals. In Greek mythology, Dithyrambos, meaning "Him of the Double Door," is an epithet of Dionysus. *See also* Bacchus; Dionysus.

Diti (Hindu; India)
She is one of the sixty daughters of Daksha, and the mate of Kasyapa. They were the parents of the giant Daityas, the enemies of sacrifice. Indra had them confined to the depths of the ocean where they were ruled by Varuna. Diti harbored resentment toward Indra and begged Kasyapa for a son who would be indestructible. He agreed with the provisions that she remain pregnant for one hundred years and remain pious and pure

throughout her confinement. When Indra found out that she was pregnant, he watched her carefully to see if she was adhering to her bargain. Toward the end of her century-long term, she went to bed one night without washing her feet. Indra seized the opportunity and thrust his vajra (thunderbolt) up her womb to destroy the unborn child. It was so strong that it divided into seven weeping sections. Their crying unsettled Indra and he tried to comfort them. It did not stop them, their wailing only became louder. Angry, Indra divided each of the seven children into seven, creating forty-nine children, who survived as the forty-nine flying warriors known as the Maruts. In some references the Maruts are numbered at twenty-seven or one hundred and eighty. Diti and Kasyapa were also the parents of the thousand-headed demon, Andhaka, and two famous Daityas, Hiranya-kasipu and Hiranyaksa. There are correspondences between Diti, Aditi and Vach. *See also* Aditi; Andhaka; Asuras; Daityas; Daksha; Hiranya-kasipu; Hiranyaksa; Indra; Kasyapa; Maruts; Rudras; Vach; Varuna.

Diuturna (Roman) *see* Juterna.

Div (Zoroastrian) *see* Jin; Daevas.

Divali (India) A Jain festival to honor Mahavira (q.v.).

Diveriks (Lithuania) Deity of the Rainbow.

Divine Cow, The (Gaulish, Celtic) *see* Borvo.

Divji Moz (Slavic)
Storm demons. They are wild spirits of the forests who were accompanied by fierce winds. The Divji Moz cause travelers to lose their way.

Divo Napata (India) *see* Asvins.

Divs (Persia) *see* Daevas; Deva.

Divya-ratna (India) *see* Cintamani.

Diwali (India) A Festival. *See also* Lakshmi.

Diwata Magbabaya (Philippine Islands)
High god. A great spirit, who lives in a house of coins. No mortal can look at him, for if he does so, the mortal will melt into water.

Djadek (A) (Czech) *see* Domovoy.

Djadek (B) (Slavic) *see* Domovoi.

Djamar (Aborigine People, Australia)
Supreme Being, who made all things. He has a mother, but not a father. He is supposed to walk with a dog. He lives in the salt water, under a rock. In some versions Djamar is in charge of two other high gods, Marel and Minan, whom he placed with other tribes.

Djanggawuls (Aborigine People, Australia)
Creator and fertility deities. The sisters Miralaid (also spelled Miralaidj) and Bildjiwararoju (Bildjiwuraroiju), are daughters of the sun goddess. They are goddesses of fertility who created human beings and vegetation. Some say the Djanggawuls are two sisters and a brother. The sisters' names are Djanggau and Djunkgao and the brother's name is Bralbral. They originally lived on the island named Bralgu (Bu'ralgu), and later moved to Arnhem Land. The sisters, eternally pregnant, gave birth to plants and animals as they walked about the earth. With each birth, a portion of their long vulvae broke off and became the first sacred objects. One day, their brother and his friend stole the sacred objects and left the sister bereft of their superhuman powers. The women left to follow the path of the sun, all the while continuing to give birth to new creatures. *See also* Wawalag Sisters.

Djed (Egypt) Deified object.
A shape in which Osiris sometimes appeared, especially as a warrior leader. The Djed, a sacred object or fetish, was at first the trunk of an evergreen tree and was later stylized in the form of a column topped by four capitals.

Djehuti Orzehuti (Egypt)
Also known as: *Zehuti.*
This is a name by which the god Thoth was known in early times. The name derives from Djehut, a former province of Lower Egypt. *See also* Thoth.

Djeneta (Chippewa People, North America) Name of a giant.

Djigona (Huron People, North America) *see* Deganiwada.

Djigonsa (Huron People, North America)
Messenger. Mother of Deganiwada, and wife of the "Great Spirit." She was the messenger between her son of the Sky-world and the tribes of the Mohawks and Onondaga.

Djinn *Djinns* (Arabia) *see* Efrit; Jinn.

Djunggun (Australia) *see* Wondjina.

Dmyal-wa (Tibet) *see* Naraka (B).

Dockalfar (Teutonic) Dark Elves. *See also* Alfar.

Doda (Serb) *see* Dodola.

Dodol (Slavic)
Air god or goddess. This deity is pulled around the sky in a chariot by white horses.

Dodola *Doda* (Serb)
Goddess of rain.

Dog-Faced Ape (Egypt) *see* Aani.

Dogdha (Celtic) *see* Dagda.

Dogoda (Slavic) The west wind. *See also* Perun; Stribog.

Doh (Yenisei People, Siberia)
One of the greatest magicians. While traveling, Doh would fly over the waves until he became weary, then he would create islands to rest on.

Dohit *Dohitt* (Mosotene, Quechua People, South America)
Creator. The Mosotene say Dohit created the first mortals from clay. The Quechua say he created the world in the shape of a raft. Next, he created mortals and then retired. Later, he returned to change some of the mortals to animals and birds. He also taught the people how to farm. *See also* Keri and Kame.

www.ebook3000.com

Dola (Slavic)
Also known as: *Dolya, Sreca* (Serbia).
The spirit of mortal fate given to a newborn. *See also* Dolya (who is similar to Sreca of the Serbian people).

Dolgthrisir (Teutonic) *see* Dolgthvari.

Dolgthvari *Dolgthrisir* (Teutonic) *see* Dwarfs.

Dolma *Tara* (Tibet)
A common name in Tibet for the goddess Tara in all her forms.

Dolphin Constellation (Greek) *see* Amphitrite.

Dolya *Nedolya* (Russia, Slavic)
This goddess of fate lives behind stoves. When her spirits are high, she brings good luck. When her mood is bad, she is known as Nedolya, appears as an old hag, and brings with her bad luck. *See also* Bannik; Chlevnik; Domovoi; Kikimora; Ovinnik.

Domfe (Kurumba People, Africa)
This water god, god of rain and wind, gave the first food-bearing seeds to humans.

Domnu (Celtic)
The goddess of the sea, she is also the mother of one of the Fomorian kings, Indech. He was killed during a battle by Ogma, one of the chiefs of the Tuatha De Danann (q.v.). *See also* Ogma.

Domovik (Russia) *see* Domovoi.

Domovoi *Domovoj, Domovoy, Domovui* (Estonian, Finnish, Polish, Russian, Slavic)
Also known as: *Chelovek, Deduska, Deduska Domovoy, Dedusky Domovik, Domovoy, Djadek* (Slavic), *Dvorovoi* (Finno-Ugric), *Haldja* (Finnish), *Haltia* (Finnish), *Holdja* (Estonia), *Iskrychi* (Poland), *Karliki* (Slavic), *Khoromozitel, Susetka, Syenovik* (Russia), *Tsmok* (Russia).
These household spirits are thrown out of heaven by the great god. The benevolent Domovoi land on houses, barns and farmlands, the evil ones land in fields, woods and wild lands. They generally live near the stove because they like fire. If they are angry they can burn the house down. If the family moves, fire from the former home is moved to the new home to welcome the Domovoi. A Domovoi is depicted as an old, gray-bearded man. He protects the household against hostile spirits as he bustles through the house at night. If a hairy person brushes against the Domovoi at night, good luck is ensured. If the hands are smooth, bad luck follows. The female Domovoi called Kikimora, Domania, or Domovikha, live in the cellar, or in ovens. One species of the Domovoi is the Chlevnik, spirit of the cattle shed or barn. The kitchen spirit is called the Ovinnik and the bathroom spirit, the Bannik. They can appear in many shapes, such as small and hairy men, animals and even objects. Under the name of Haltia or Haldja this is the ruler who precedes men almost as a ghost or shadow. In some legends, this spirit comes in the shape of a dog or cat. Halti and Holdja are house goddesses. They live in the beam of the roof in each room. If acknowledged when entering the house, they bring the occupants good luck. They are similar to the Aitvaras of Prussia and the Roman Lares (qq.v.). *See also* Bannik; Chlevnik; Dolya; Dvorovoi; Khoromozitel; Kikimora; Krukis; Ovinnik.

Domovoj *Domovui* (Russia)
Also known as: *Karliki* (Slavic) *Iskrzychi* (Poland), *Syenovik and Tsmok* (Russia), *Haltia, Haldja* (Finnish), *Holdja* (Estonia).
House spirit. These domestic dwarf spirits are similar to Domovoy of the Slavs, and Aitvaras of Prussia. Under the name of Haltia or Haldja, this spirit was the ruler who precedes men almost as a ghost or shadow. Sometimes the Domovoj come in the shape of a dog or cat. Halti and Holdja are house goddesses. They live in the beam of the roof in each room. If acknowledged when entering the house, they bring the occupants good luck.

Domovoy (Russia) *see* Domovoi; Dvorovoi.

Domovui (Russia) *see* Domovoi; Dvorovoi.

Don (British, Celtic)
Also known as: *Dana.*
Goddess of fertility. Don is known as the mother of the Welsh pantheon as related in the fourth branch of the Mabinogion. She is associated in Wales and Britain with the Irish earth mother Dana. Some of the Children of Don (meaning ancestors) were Gwydion, Govannon, Ludd, and Arianrhod. Don is thought of as the mother of the sacred tribe. Some renditions place her as mother of Math and wife of Beli. *See also* Arianrhod; Dana; Gwydion; Math.

Don the Enchanter (Celtic) *see* Gwydion; Pryderi.

Donar (Teutonic)
Also known as: *Thor, Thunar* (Anglo Saxon).
Donar is an alternate name for Thor, the thunder god. As Donar, his symbol is the swastika. *See also* Thor.

Dongo (Songhoi People, Africa)
God of Thunder. Legend says Dongo threw his axe into heaven to try it out, then when one of the villagers made a spark, Dongo threw his axe at it killing all his companions. His grandfather told him to fill his mouth with water and spray it on his companions which brought them back to life.

Donn (Celtic) *see* Achren.

Donu (Celtic) *see* Dana.

Door Guards (China) *see* Men-shen.

Doorga (India) *see* Devi.

Dor-le (Tibet) *see* Dam-c'an-r-do-rje-legs-pa.

Dori (Teutonic) *see* Dwarfs.

Doris (Greek)
She is the sea goddess spouse of Nereus, and the mother of the Nereids. Her parents are Oceanus and Tethys. *See also* Amphitrite; Ceto; Nereids; Nereus; Oceanids; Oceanus; Tethys.

Dorje-Naljorma *Toma* (Tibet), *Vajra-Yogini* (Tibet)
This Tantric goddess personifies spiritual energy and intellect. She is described as sixteen years of age, with one face, three eyes and two hands. The Flames of Wisdom form a halo around her. She is in a dancing position, with her right leg bent and foot uplifted. Her left leg is on the breast of a prostrate human. *See also* Devis; Toma; Vajra-Yogini.

Dorje Phagmo *Dorje-phe-mo* (Tibet), *rDorje-P'ag-mo* (Buddhist; India, Tibet)
Also known as: *Vajra-Varahi, Vajrabarahi, Vajravarahi.*
Dorje Phagmo is known as the Thunderbolt Sow, the Great Diamond Sow, the Female Energy of All Good, and the Most Precious Power of Speech. She is a Khadoma (female demon) and a Bodhisattva (a person who has attained enlightenment). Once when her monastery in Tibet was threatened, she turned herself and her attendant monks and nuns into pigs for protection. When the invaders saw an empty monastery, they said they would not loot it. Dorje Phagmo and her populace returned to human form in front of the invaders and then metamorphized everyone back into swine. This terrified the would-be looters into a state of awe. Instead of taking items away, they presented the monastery with priceless gifts. When called upon, Dorje Phagmo can bestow supernatural powers on her followers. As Vajravarahi, she is the consort (sakti) of Cakra-samvara, the Buddha of sublime happiness. In Tibet, he is known as dDe-mch-og-dpal-kor-lo-dom-pa or Dem-chho-pal-khor-lo-dom-pa. A dorje is a type of thunderbolt. The name Dorje Phagmo is interpreted as "Thunderbolt Sow." As Vajravarahi, she is depicted excreting a sow's head from her right ear. Her color is red; her position (asana) is dancing. One of her emblems is the kapala (Sanskrit), also called the t'od-p'or (Tibetan), an altar object that is also the emblem of Buddhasaktis, Dakinis, Dharmapala, Ekajata and Yi-dam. The Khados correspond to the Indian Dakinis (female demons). *See also* Dakini; Sambara (B); Varahi.

Dorje-phe-mo (Tibet) *see* Dorje Phagmo.

Dorje-sem-pa (Tibet) *see* Vajrasatwa.

Dorobo (Masai People, Africa) *see* Ngai.

Doros (Greek) *see* Achaeus.

Dorr-Karing (Swedish)
Door spirit. Legend says she stands by the doorway and blows out the candles of those entering or leaving. *See also* Uksakka.

Dorus (A) (Greek)
He is the son of Hellen and Ortheis. His siblings are Aeolus and Xuthus. Aegimius and Tectamus are his children. *See also* Aeolus (A); Hellen.

Dorus (B) (Greek)
Apollo and Phthia are his parents, and Laodocus and Polypoetes are his siblings. He is the father of Xanthippe. *See also* Polypoetes.

Dorus (C) (Greek) He is the son of Xuthus and Creusa (qq.v.).

Doso (Greek)
Doso is the name Demeter used while she nursed Demophon in disguise. *See also* Demeter; Demophon.

Dotis (Greek) *see* Ares.

Doto (Greek) One of the fifty Nereids (q.v.).

Drac (A) *Draca* (Middle Eastern)
The Drac are female water spirits who entice women and children into the water and devour them.

Drac (B) (French) A spirit feared by peasants.

Dragon Kings (Taoist; China)
Also known as: *Lung-Wang.*
Weather deities. There were either four, eight, or ten of these deities. Creatures said to represent the yang force (*see* Yin and Yang). They were associated with the waters of lakes, rivers, and the sea, and all fell under the rule Yu-ti. Four brothers, Ao Kuang (Eastern sea), Ao Jun (Western sea), Ao Shun (Northern sea) and Ao Ch'in (also spelled Ao-K'in (Southern sea), were lords of the seas surrounding the earth. Each had his crystal palace, court, and attendants. In the Taoist belief there are four kings; Kuang-te, Kuang-li, Kuang-jun and Kuang-she. In a similar legend, a dragon called Enlightener of the Darkness had control over light and darkness by the opening and closing of his eyes. His breath brought wind and rain, cold and fire. The Dragon Kings are generally shown as a serpent or dragon. Similar to the Nagas (q.v.). *See also* Lung; Nine Songs; Ssu-ling; Yama Kings.

Drauga (Persia) *see* Angra Mainyu.

Draupadi, Princess *Panchali* (India)
See also Arjuna; Duryodhana; Karna; Kunti; Pandavas.

Draupner (Teutonic) *see* Draupnir.

Draupnir *Draupner* (Norse; Teutonic)
Also known as: *Dropper.*
Emblem of fertility. A magic ring. Eight similar rings dropped from the original ring every night. Some say the ring produced eight rings on every ninth night. The rings were manufactured by the dwarfs who presented them as a gift to Odin. The dwarf, Sindri, is sometimes referred to as the manufacturer of the rings. Other writers say it was the dwarfs Eitri and Brokk who forged the original ring. It is pictured as a large red gold ring shaped as a snake with its tail in its mouth. *See also* Dwarfs; Odin; Sindri.

Dreams (Greek)
Also known as: *Oneiroi.*
The Oneiroi are the children of Nyx or Hypnos, or Erebus. They guard the Underworld entrance. *See also* Aether; Hypnos; Keres; Nemesis; Nox.

Dri-chab-ma (Tibet) *see* Ganda.

Dri-chha-ma (Tibet) *see* Ganda.

Dripping Water (Zuni People, North America)
She is the mother of the twins, the Ahayuta Achi (q.v.).

Dromi (Norse; Teutonic)
Dromi is the second of three chains that bind Fenrir the wolf. The other chains are Laeding and Gleipnir. *See also* Fenrir; Gleipnir.

Drona (A) (India)
Drona, a martial arts expert, is the son of Bharadvaja (q.v.). *See also* Bhima (A); Duryodhana.

Drona (B) (India)
Wife of Kripa, Mother of Ashvatthaman. *See also* Duryodhana.

www.ebook3000.com

Dropper (Teutonic) *see* Draupnir.

Droudje (Persia) *see* Drujs.

Druantia (Celtic) Goddess of fir trees.

Drudge (Teutonic) *see* Thor.

Drugas (Persia) *see* Angra Mainyu.

Druge (Persia) *see* Drujs.

Druj (Persia) *see* Angra Mainyu; Drujs.

Drujs *Droudje, Druge, Duruge, Nasu* (India, Persia)
These monstrous demons of deceit, often female, were adversaries of the Amesha Spentas. Nasu and Ahzi Dahaka were Drujs. Nasu, the female demon, disguised as a fly, would land on corpses to assist in their corruption. Ahzi Dahaka was a three-headed serpent with six eyes and three pairs of fangs. He was later assimilated into the mortal king, Zohak, the enemy of Persia. He was also said to be an adversary of Yima. Another Druj was Jahi who was associated with Ahriman. Originally, Druj was a goddess. Druj is also an epithet for Angra Mainyu (q.v.). The Drujs are associated with the Pairikas and Yata (qq.v.). *See also* Ahzi Dahaka; Amesha Spentas; Angra Mainyu; Jahi; Mashya and Mashyoi; Nasu; Yima.

Drukh (Hindu; India)
Malignant spirits who were companions of Vritra (q.v.).

Drumalika (Hindu; India)
During the second age of the world, Drumalika, a demon, assumed the form of King Ugrasena, and raped his wife Queen Pavanarekha as she strolled through the forest. After his act of violence, he resumed his demon form and revealed to her that she would bear a son, who would rule nine divisions of the earth and would become the archenemy of Krishna. The son, Kansa, was born ten months later. Kansa, evil personified, murdered children, and forced King Jarasandha of Magadha to give him two of his daughters, whom he married. He deposed King Ugrasena who ruled the peaceful, agricultural kingdom of the Yadavas of Northern India and banned all worship of the god Vishnu. The gods decided that it was time to intervene and send Vishnu to earth in his avatar as Krishna to restore a balance between good and evil. *See also* Kansa; Krishna.

Drvaspa (Persian) *see* Dervaspa.

Dryades *Dryads* (Greek)
Also known as: *Hamadryads.*
In early times Dryades were the protectors of the forest; specifically the oak tree. In later periods, these nymphs were associated with the Hamadryads and would reside in any tree; with the exception of fruit trees which were reserved for Maliades. It is said that if a branch of her tree was thoughtlessly broken or injured, the mortal would be punished by a Dryade. They are depicted as females crowned with oak leaves and armed with axes. *See also* Hamadryads; Naiads; Nereids; Nymphs; Oceanids.

Dryads (Greek) *see* Dryades.

Dryas (A) (Greek) Son of Ares.

Dryas (B) (Greek)
She is the daughter of Faunas, and the sister of Acis. She hated men and never appeared in public. *See also* Acis.

Dryas (C) (Greek) He is a centaur associated with Peirithous.

Dryas (D) (Greek) Son of Lycurgus.

Dryas (E) (Greek)
Father of Lycurgus, who was the king of the Edonians of Thrace.

Dryh Basy (Persia)
A corpse demon who is the personification of the spirit of corruption, decomposition, contagion and impurity.

Dryope (A) (Greek)
She is a fountain nymph who was so in love with Hylas that she drew him into her fountain. *See also* Hylas.

Dryope (B) (Greek)
She is the daughter of Eurytus and the mother of Amphissus by Apollo.

Dryope (C) (Greek)
Aphrodite possessed Dryope's body. She used it to arouse the women of Lemnos to kill all their men.

Dryope (D) (Greek)
Pan is possibly her son by Hermes. Dryope is the daughter of Dryops and Polydore.

Dryops (A) (Greek)
He is the father of Dryope and spouse of Polydore.

Dryops (B) (Greek) Son of Apollo.

Dryops (C) (Greek) Son of Priam.

Dryops (D) (Greek)
He is associated with Aeneas, the son of Anchises and Aphrodite.

Dsam-Bha-La (Tibet) *see* Jambhala.

Dsovean (Armenia)
Storm god. Husband of the storm goddess Dsovinar. Some think Dsovean is the same as the old god Vahagn. *See also* Agni; Vahagn.

Dsovinar (Armenia)
Storm goddess. Wife of the storm god Dsovean. *See also* Dsovean.

Duamutef (Egypt) *see* Tuamutef.

Duat (Egypt) *see* Tuat.

Dubbisag (Sumer) *see* Nabu.

Dubh Lacha (Irish) Sea-goddess.

Dufr (Teutonic) *see* Dwarfs.

Dug-Po-Ma (Tibet) *see* Dhupa.

Dughda *Dughdhova* (Persia)
Virgin mother of Zoroaster (q.v.).

Dughdhova (Persia) *see* Dughda.

Duhsasana *Dushasana* (India) *see* Bhima (A).

Dula (India) A Krittika sister. *See also* Rishi.

Dulachan (Celtic)
Similar to the Cluricanes, the Dulachan are malicious goblins or elves. *See also* Cluricanes; Dwarfs; Elves.

Dumazu (Sumer) *see* Dumuzi.

Dumu-e-zi (Sumer) *see* Dumuzi.

Dumu-zi (Sumer) *see* Dumuzi.

Dumuduku (Babylonia) *see* Marduk.

Dumunzi (Sumer) *see* Dumuzi.

Dumuzi *Dumazu, Dumu-e-zi, Dumu-zi, Dumunzi, Dumuziabzu, Dumuziapsu, Dumuzida* (Sumerian; Accadian)
Also known as: *Damu, Tammuz* (Babylon), *Ziapsu.*

This Sumerian vegetation god and shepherd god was later identified with the Babylonian god, Tammuz. To the chagrin of Enkidu and Utu, he became the mate of Inanna. His sister Gestinanna interpreted his nightmares and deduced that he was being attacked by demons. He fled and she vowed that she would never divulge his whereabouts. When the demons arrived, they attacked her but she remained steadfast in her vow of silence. (Her name means "Lady of Desolation.") Eventually, the demons discovered Dumuzi in the form of a gazelle hiding among his sister's sheep. They carried him off to the underworld. She pursued them, and in time was able to convince the underworld deities to allow Dumuzi to live six months on earth each year if she remained six months of each year in the underworld. The three most important females in his life were his devoted sister Gestinanna, his wife Inanna, and his mother, Ninsun. The dying Dumuzi is shown with the three women surrounding him. Some say he was the son of Ea and husband/son of Innini. The goddess Gula-Bau has also been called his mother/wife. His animal is the bull. Compare Dumuzi to the Babylonian Tammuz and Ishtar and the Phrygian Cybele and Attis. Some compare him to the Greek Adonis (q.v.). Compare Dumuzi to the Celtic Angus. *See* Inanna for another interpretation of his descent into the underworld. *See also* Ea; Enki; Enkidu; Gestinanna; Gula; Ninsun; Nintud; Shala; Utu.

Dumuziabzu (Sumer) *see* Dumuzi.

Dumuziapsu (Sumer) *see* Dumuzi.

Dumuzida (Sumer) *see* Dumuzi.

Duneyr (Teutonic) *see* Dain; Dwarfs; Yggdrasil.

Dunga (Assyro-Babylonia)
A name for Ea as the deity of singers and psalmists.

Dup Shimate *Dup Shimati* (Sumer)
The name of the Tablets of Fate (q.v.).

Dup Shimati (Sumer) *see* Tablets of Fate.

Dur-Europas Ba'al Shamin *see* (Mesopotamia).

Duramulun *Daramulum* (Aborigine People, Australia)
Also known as: *Baiame, Thuremlin.*

Creator. He was the first to dwell on earth, but he created man on a planet that had only animals. He gives the medicine man his powers. Some versions call him the son of Baiame of Ngalaibal. Duramulun was one of the survivors of the flood. *See also* Baiame.

Durapror (Teutonic) *see* Yggdrasil.

Durathror (Teutonic) *see* Dain; Dwarfs.

Durga (Hindu; India)
Also known as: *Ambika* (Mother), *Bhadrakali, Bhima, Chamunda, Chanda, Chandi, Chundika* (The Burning or Fierce), *Devi, Durga Mahisasuramardini, Gauri, Gaya* (The Conquering), *Jaganmatri, Kali, Karala* (The Formidable), *Karali, Kausiki* (Like an Owl), *Mahalaxmi, Mahishamardini* (Killing Mahisa), *Parvati, Pathalavati* (Pale Red), *Sarika* (Bird), *Sati, Shakti, Simharatha* (having a car drawn by lions), *Skanda, Uma* (Light), *Vetanda* (Like an Elephant), *Vetala* (Ghoul), *Vikathikarala* (Fearful).

Durga, the invincible destroyer, warrior and goddess of death, is an aspect of the Great Mother Devi, who was born from the wrath of Vishnu and Shiva. She was formed by the flames in their mouths to evict the demon Mahisasura from heaven. Equipped by the gods with the most powerful of weapons, she engaged in battle with Mahisasura who was disguised as a buffalo. After slaying the animal, she defeated the demons Kaitabha and Madhu who were born from Vishnu during his cosmic sleep. Next, the demon brothers Sumbha and Nisumbha attempted to reign over the deities. Once again, they called upon Durga. She appeared as the beautiful goddess Parvati to soothe the worried gods. After reassuring them, she marched into battle as Durga and confronted the demons Canda and Munda. As they approached her ready for combat, she furrowed her brow and the terrifying warrior goddess Kali emerged. Kali was ready for war. She flung the demons around, crushed them with her jaws and decapitated them with her sword. The heads were given to Durga as a gift. As the slayer of demons, Durga is often called Kali-Durga. Durga, meaning "inaccessible," resides on the sacred Mount Mandara. She is usually depicted as a full-breasted female clothed in yellow and riding a tiger or lion. She is shown with two to ten arms. Sometimes she has vampire teeth and four arms. She is also shown as a beautiful woman with ten arms holding the moon-disk and a skull. In her most common depiction, she has eight arms, holding a sword, arrow, chakra, shield, noose, javelin, bow and conch shell. In Indian depictions, a violent struggle is shown between Durga and the buffalo. In Javanese depictions, the buffalo is in a recumbent position and the dwarf-like figure of Mahisasura is seen emerging from the animal. In a specific rendering thought to be typical, Durga stands on its back and head with her feet apart. In her three left hands she holds a conch, shield, and bow. In three rights hands she holds a sic, sword and arrow. Her fourth hand pulls at the tail of the animal. Her festival is called the Durga-puja and is held from the seventh to the tenth days of the bright fortnight of Asvina (September–October). During this time, Durga is invoked on a twig from the sacred vilva tree. In another interpretation of Durga as an aspect of Devi, it is said the goddess Devi acquired the name Durga for her fierce form from the demon of the same name

www.ebook3000.com

whom she slaughtered after a fierce battle. He had taken over the three worlds and forced the gods to live in the forest and worship him. His power was so great that fires could not burn, stars disappeared and waters stood still. In desperation, the gods asked Shiva to attempt to rid the universe of the personification of evil. He turned to his mate Devi for a solution to the problem. Initially, she created the entity Kalaratri to rid the world of this foe, but he was unsuccessful. Devi decided to overcome him herself. The pronunciation of the name Durga is with a long final vowel when referring to the goddess and with a short final vowel when referring to the demon. *See also* Agni; Ana-Purna; Badari; Devi; Devis; Gauri; Kali; Mahalaxmi; Meru Mountain; Parvati; Rudra, Sati; Shakti; Shiva; Vilva; Vishnu.

Durga Mahisasuramardini (India) *see* Durga.

Durga Purga (India)
Hindu festival also known as Nava-ratri. *See also* Durga; Kali.

Durin (Norse; Teutonic)
Also known as: *Durinn.*
First of the Dwarfs. Assistant or second in command to Modsognir who was chief of the dwarfs. He helped create the dwarfs. *See also* Modsognir.

Duruge (Persia) *see* Drujs.

Durvasas (India) *see* Karna and Kunti.

Duryodhana (Hindu; India)
Duryodhana, a Kaurava, was the eldest of the one hundred sons of the blind king, Dhritarashtra. His father also raised his brother Pandu's five sons, the Pandavas. The Kauravas were jealous of the Pandavas and tried numerous methods to destroy them. Duryodhana's hatred was obsessive. He attempted to poison Bhima, and then set fire to his cousins' home. In desperation, he arranged a gambling match. The stakes were high. The losers were to forego their freedom. To ensure his victory, Duryodhana had the charlatan, Sakuni, prompt him. Yudhisthira, the eldest of the Pandavas, gambled and lost his own freedom and that of his brothers and their common wife, the princess Draupadi. When Duryodhana took advantage of the situation by humiliating her, Bhima swore revenge. Thirteen years later, after the great war of the Mahabharata, the defeated Duryodhana sought refuge under water. He emerged to duel with Bhima who extracted his revenge by smashing his thigh. Ashvatthaman, the son of Drona and Kripa, who was a Kaurava warrior, came upon him alone in a field. He promised to bring him the five heads of the Pandava brothers. When he returned, Duryodhana realized that Ashvatthaman had murdered the young sons of Draupadi, whom he did not hate. Duryodhana died at the grisly sight of their heads. *See also* Arjuna; Bala-Rama; Bhima (A); Dhritarashtra; Karna; Kauravas; Krishna; Pandavas.

Dus (Scrat; Teutonic) (Celtic) Demons.

Dusares *Dousares, Dusura* (Arabia, Greek, Roman)
Sun god or possibly a god of mountains. God of the vine. A local god of South Arabia, who was worshiped by the Romans. In some versions, his mother is a virgin goddess named Chaabu. He is depicted as a black stone pillar on a base of gold and sometimes as a human figure holding a cornucopia. Dusares is identified with Bacchus and Dionysus. Some identify him with Tammuz.

Dushasana (India) *see* Duhsasana.

Dushyanta (India) *see* Bharata (B); Shakuntala.

Dusii (Celtic)
They are demons comparable to the medieval European Incubus, the Persian Jinn, Greek Satyrs, and Samoan Hotua Poro. *See also* Demons.

Dusuara (Greek) *see* Dusares.

Duzakh (Persia) *see* Dzokh; Hades; Hell.

Dvalin *Davalin, Dvalinn* (Norse; Teutonic)
Dwarf smith. Dvalin was one of the dwarfs created by Modsognir. He is the son of Ivald, and brother of Sindri or Brock. He assisted Sindri in forging the sword, known as Tyrfing, or the spear, known as Gungnir, and Freyja's necklace, known as Brisingamen. He also fashioned the ship Skidbladnir for Odin. *See also* Brisingamen; Freyja; Loki.

Dvaraka (India) *see* Dvarka.

Dvarapala (Indonesia) Temple Guardians.

Dvarka (India)
Celestial Abode. *See also* Bala-Rama; Krishna; Parijata; Pradyuma; Swarga; Yadavas.

Dvergar (Teutonic) *see* Dwarfs.

Dvivida (India) Monkey Child. *See also* Asvins.

Dvorovoi (Finno-Ugric; Slavic)
Also known as: *Domovik, Domovoi, Domovoj, Domovoy, Domovui, Korka-kuzo* (Finno-Ugric), *Korka-murt* (Finno-Ugric).
These courtyard spirits hate all animals with white fur. They are not always friendly to humans. Sometimes they dwell under the floor of the house. As Korka-kuzo or Korka-murt, when they are not friendly, they cause nightmares. They have the power to substitute small children for changelings. Sacrificing a black sheep can placate them. *See also* Domovoi.

Dwaparayuga (Hindu; India)
Also known as: *Dwarpara.*
Part of the Kalpa cycle, (or Day of Brahma), Dwaparayuga is the third of the four Yugas (ages) of the current Mahayugas (epoch). The other Yugas are Krita, the first of the Yugas; Tretayuga, the second of the Yugas; Kaliyuga (named for the goddess Kali), the fourth Yuga. Dwaparayuga will last for 2,400 divine years. Each divine year is 360 human years. Dwaparayuga's total length is 864,000 human years. During this period, with virtue at 50 percent, Dharma, the god of justice and duty, is yellow in color, and walks on two legs. *See also* Brahma; Dharman; Kaliyuga; Kalpa; Krita; Tretayuga.

Dwarfs *Dwarves* (Norse; Teutonic)

Also known as: *Dvergar.*

Almost all mythology has tales of these diminutive beings. They are often called artisans, and many are smiths or gold workers. Some of the dwarfs mentioned in Norse mythology are Ai, Alf, Alvis, An, Andvari, Annar, Austi, Bafur, Bifur, Bombor, Brokk, Dain, Dolgthvari, Dori, Draupnir, Dufr, Duneyr, Durathror, Durin, Dvalin, Eikinskjaudi, Fal, Fili, Fith, Fjalar, Frosti, Fundin, Galar, Gandalf, Ginnar, Gloin, Har, Haur, Hornbori, Ingi, Jari, Kili, Lit, Loni, Mjodvitnir, Moin, Nain, Nali, Nar, Nibelung, Nidi, Nipingr, Nordri, Nyi, Nyr, Oinn, Ori, Radsuithr, Radsvid, Regin, Rekk, Sjarr, Skandar, Skirfir, Sudri, Thekkr, Thorin, Thror, Thrurinn, Vali, Veigur, Vestri, Vig, Vindalf, Virvir, Vithur, and Yingi. India had Agastya, Egypt called Bes a dwarf, and others were Cedalion (Greek), Gahongas (Iroquois), and Kaukis (Prussia). Elves and Dwarfs are frequently confused. The original elves, said to be of Norse origin, were called Alfar. There are two groups of Alfar: light (Lios Alfar) or dark (Svart Alfar). The Lios Alfar are ruled by Freyr, and the Svart Alfar, who live in the underground known as Svart-Alfa-Heim, are ruled by Wayland the Smith. If they break a rule and make an appearance during the day, they are turned to stone. Dwarfs, trolls and gnomes spend their time collecting gold, silver and valuable stones which they secret away. The fairies and elves live in a bright, airy realm located between heaven and earth. They spend their time flitting around enjoying the finery of nature or dancing in the moonlight. *See also* Alfar; Alvis; Berling; Bifur; Brisingamen; Brokk; Brownie; Dain; Draupnir; Durin; Dvalin; Elves; Fenrir; Fjalar; Freyja; Freyr; Gleipnir; Kvasir; Midgard; Nibelung; Nordri; Pusait, Regin; Sindri; Sudri; Svart-Alfa-Heim; Ymir.

Dwarka (India) *see* Krishna; Visvakarma.

Dwumwem (Celtic) *see* Dwyn.

Dwyn (Celtic)

Also known as: *Dwumwem, Oengus.*

God of Love. *See also* Angus.

Dwynwen (Celtic) *see* Oengus.

Dxui (Bushmen, Central Africa)

Also known as: *Thixo* (Ponda, Xhosa People), *Tsui* (Bushmen).

Creator god. For details, *see also* Tsui.

Dyai (Tucana People, Amazon, South America)

Dyai and his wicked brother Epi were the sons of Nutapa. Dyai was born from his father's right knee, and Epi was born from his father's left knee. When Nutapa was killed by a jaguar, his sons brought him back to life. Dyai was Epi's caregiver. He constantly rescued him from difficulties. The brothers caught a fish from which they created man. The two brothers eventually parted. Dyai went to the east, and Epi to the west.

Dyaus *Diaus, Dyu, Dyhu* (Hindu,Vedic; India)

Also known as: *Dyaus-Pita* (Sky-Father), *Dyaus-Pitar, Dyava-Prithivi* (used when speaking of Dyaus and Prithivi).

Dyaus a sky deity, god of thunder, rain and fertility, is an early Vedic deity, the husband of Prithiva (Earth). He was the father of Ushas (Dawn), Agni (Fire) and Indra and according to some the father of Surya the sun god and possibly the Asvins. Originally, the couple was considered to be the parents of the gods and mortals. Dyaus was murdered by Indra, who then established himself as ruler of the universe. Dyavan (the sky) or Varuna (heaven), is the home of Dyaus. He is sometimes confused with the Greek Dyeus or Zeus. Dyaus is called Father, Dyaus-Pital, similar to Zeus Pater and the Roman Jupiter and the Greek Zeus. Dyaus is depicted as a bull and Prithiva as a cow. *See also* Agni; Asvins; Devas; Indra; Prithiva; Ratri; Surya; Tvashtri; Ushas.

Dyaus-Pita *Dyaus-Pitar* (India)

Sky Father. *See also* Dyaus; Prithiva; Vedas.

Dyaus-Pitar (India) *see* Dyaus-Pita.

Dyaus-Pitri (India) *see* Prithiva.

Dyava-Matar (India) Earth Mother. *See also* Prithiva.

Dyava-Prithivi (India) *see* Dyaus.

Dyavaprithivi (India) *see* Prithiva.

Dyavaprthivi (India) *see* Prithiva.

Dyavo (Slavic) Serbian demons. *See also* Demons.

Dyhu (India) *see* Dyaus.

Dylan (Celtic)

Also known as: *Eilton* (Son of the Wave), *Endil.*

The brother of Llew, Dylan dove into the sea when he was born. As a sea god, he was known as Eilton and Endil. *See also* Arianrhod; Llew Llaw Gyffes; Pryderi.

Dymas (A) (Greek)

Dymas, a Trojan, disguised himself as a Greek during the Trojan War. He was killed by the Trojans. *See also* Aegimius.

Dymas (B) (Greek) King of Phrygia.

Dyna (Greek) *see* Evander (B).

Dynamene (Greek)

She is one of the fifty daughters of Nereus and Doris, known as the Nereids (q.v.).

Dyne (Greek) *see* Evander (B).

Dyotana (India) The Light Bearer. *See also* Ushas.

Dyu (India) *see* Dyaus.

Dzalarhons (Haida People, North America) *see* Dzelarhons.

Dzelarhons *Dzalarhons* (Haida People, North America)

Also known as: *Volcano Woman.*

She is a mountain spirit. Known as the Volcano Woman, she rules the creatures of the earth and punishes abusers of the creatures.

Dzhe Manito *The Good Spirit* (Algonquin, Chippewa People, North America)

He is the second in command to the Chief of Spirits, Gitche.

Dzokh (Armenia) *see* Duzakh; Hades; Hell; Santaramet.

www.ebook3000.com

Chapter II
Preparing for Cosmic Chi Kung

Preparatory Practices

In the Universal Tao, we teach Cosmic Healing Chi Kung within an entire system of exercise and meditation. As a part of this system, Cosmic Healing Chi Kung comprises the art of healing oneself and others. It focuses on energy work for projecting Chi to effect these healings. One can easily learn the simple movements of Cosmic Healing Chi Kung without doing any other Universal Tao practices, but if one truly wishes to master the art of Cosmic Healing Chi Kung, it is important to have a firm foundation in the basic Universal Tao practices. Therefore in this chapter we will introduce you to the basic Universal Tao practices that are used in conjunction with Cosmic Chi Kung.

The preparatory practice consists of a few parts; work through each part at your own pace and eventually join them together as a whole.

Always start with "warming the stove" at the abdomen and direct the fire down to the sexual center to transform the sexual energy. Next practice the Cosmic Inner Smile. The Cosmic Inner Smile is a powerful relaxation and self-healing technique that uses the energy of love, happiness, kindness and gentleness as a language to communicate with the internal organs of the body. Each organ corresponds to a specific element and color. For example, the kidneys will consist of the element of water and the color blue. The heart will consist of the element of fire and the color red. This makes it very easy to guide the healing power into each organ by using the appropriate color. The practice also aids the transformation of negative emotions into positive virtuous energy. This transformation is a very powerful Chi Kung practice. A genuine smile transforms negative energy into loving energy that has the power to relax, balance and heal. By learning to smile inwardly to the organs and glands, your whole body will feel loved and appreciated and enjoy more Chi. After the Inner Smile, practice Bone Breathing, Marrow Washing, Cosmic Healing and the Microcosmic Orbit.

Warm Up the Stove

1. Sit on the edge of a chair with your hands clasped together and your eyes closed.
2. Start by doing the "bellows breathing", moving your abdomen in and out quickly. Emphasize the exhalation by breathing out forcefully 18 to 36 times. Rest, cover your navel and feel nice and warm.
3. Next, do the "inner laughing" exercise; you feel the abdomen vibrate inside you. Practice

E

E (Maya) Maize god.

Ea (Akkadian, Assyro-Babylonian, Sumerian)

Also known as: *Amma-Ana-Ki, Aos, Dunga, Enki* (Sumerian), *Engur, Enki-Ea, Hea, Hoa* (Chaldean), *Lumha, Nadimmud, Nidim, Ninbubu, Nindubarra, Ninigiku* (King of the Sacred Eye), *Ninigikug, Nudimmud, Nurra, Oannes.*

His early names were Nudimmud and Nidim. A creator deity, Ea is the god of earth and waters, god of the deep sea and god of wisdom. He is the author of the arts of life, the teacher of civilization, and the law-giver. With Anu and Enlil he is the third member of a triad. Ea, Anu and Enlil rule the cosmos, with Ea reserving the right to rule all waters surrounding the earth. He is the water god of Eridu. He is the patron of magicians, healers, and all who practice art and crafts. His magical incantations allowed him to battle and overcome his mother Apsu, the personification of sweet waters, and Mummu (in the Babylonian Creation Myth). He divided Apsu into sections, one of which became his resting place. When Tiamat, the personification of bitter waters, intent upon avenging Apsu's death, called upon her evil forces, Ea in turn invoked Anshar for assistance and appointed his son Marduk as the leader of an order of newly established gods. From the blood of Kingu, the leader of the opposition, Ea created mortals. As a creator god, he made the gods Kulla (also known as Ki-gulla), Ninildu, Nimsimug, Arazu, Gushkinbanda, Ninagal, Ninzadim, Ninkurra, Ashnan, Lahar, Siris, Gizidu (also known as Ningizzida), Ninsar, Umunmutamku, Umunmutamnag, and Kusug. As well as Marduk, Ea is the father of the goddess Nina and some say Nanshe, the goddess of springs and canals. Some say he has a son, Asari, who is his mediator for mortals. His name means "He who does good to men." Under his titles of Dunga and Lumha, he is deity of singers and psalmists. Under the name Ninbubu, he is a god of sailors. As Nindubarra he is god of shipbuilders and as Nurra he is god of potters. As Engur he is a water-deity. Later in history he had a spouse named Damkina or Ninki. Despite his wisdom, Ea's jealousy was the cause of mortals not being able to attain immortal life. (The Sumerian god Enki in later times [second-millennium B.C.E.] became the Babylonian god Ea.) Ea is sometimes shown as a goat with a fish tail or a human with water gushing from his shoulders or from a vase. *See also* Adad (A); Adam; Adapa; Adar; Agusaya; Anshar; Anu (B); Anunnaki; Aos; Apsu; Arazu; Asari; Ashnan; Asushunamir; Baragulla; Bel (A); Belit; Bohu; Dagon; Damkina; Dumuzi; Eden; Elish; Enki (he is the same as Enki and the opposite of Enlil), Enlil; Ennugi; Enuma Ereshkigal; Eridu; Ezuab; Gasmu; Gilgamesh; Ishtar; Khi-dimme-azaga; Kingu; Kishar; Kulla; Lagamal; Lahar; Lumha; Mami; Marduk; Mummu; Nanshe; Nimsimug; Nina (B); Ninib; Ninigiku; Ninildu; Ninki; Ninkurra; Nudimmud; Oannes; Saltu; Silik-mulu-khi; Tammuz; Tiamat; Ullikummis; Umunmutamku; Usma; Utnapishtim; Ziusudra; Zu.

Eabani (Sumer) *see* Enkidu; Gilgamesh.

Eadna (Celtic) *see* Eire.

Eadon (Ireland) Goddess of poetry.

Ealur (Babylon) Another name for Zerpanitum (q.v.).

Eanna (Sumer) The dwelling place of Anu on earth.

Early Waker (Teutonic) *see* Aarvak.

Earth (A) (Norse; Teutonic)

Also known as: *Fjorgyn, Jord.*

Earth is another name for the goddess Jord who is also known as Fjorgyn. *See also* Jord.

Earth (B) (Greek) *see* Gaea.

Earthmaker (Winnebago People, North America)

Creator deity. Supreme creator of the Winnebago, He is depicted as taking pity on the human race, because having created it last, all the gifts he possessed had already been distributed to the various spirits. He created an herb which had a pleasant odor and which all the spirits immediately desired. But to them he said, "To all of you I have already given something valuable. You are all fond of this herb, is it not so? I am myself." Then he took some of the leaves, mashed them up, and, filling a pipe, smoked. The odor was pleasant to inhale. All the spirits craved tobacco, so he gave each one a puff and said: "Whatever, from now on, the human beings ask of me and for which they offer tobacco, that I will not be able to refuse. I myself will not be in control of this herb and since, of all these I have created, the human beings alone are poor, if they offer us a pipe full and make some request, we shall always grant it."

East Wind (Greek) *see* Boreas; Eurus; Notus.

East Wind Hag (Teutonic) *see* Gullveig.

Eastre (Norse; Teutonic; Saxon)

Also known as: *Eostre, Ostra.*

Goddess of spring. Probably identical with Frigga as possibly a goddess of earth or rejuvenation of spring after a long winter. *See also* Eostre; Frigga.

Eater of Hearts (Egypt) *see* Sakhmet.

Eater of the Dead (Egypt) *see* Amit.

Eaynnes (Greek) *see* Erinyes; Eumenides.

Ebhlenn (Ireland) *see* Ebhlinne.

Ebhlinne *Ebhlenn* (Ireland)
The goddess Ebhlinne, the daughter of Guaire, married a king of Cashel, and ran away with his son. She was worshiped in the southern county of Tipperary and lived in the Twelve Mountains of Ebhlenn.

Ebisu (Buddhist, Shinto; Japan)
Also known as: *Hirugo, Hiruko* (in his form as a jellyfish), *Kotoshironushi-No-Mikoto.*
God of fishermen. Patron of trade and manual workers. Ebisu is the son of Daikoku, the god of prosperity. With his father, they were members of the Shichi Fukujin (seven deities of good fortune). Ebisu and Daikoku are thought to be Shinto kami (gods). Ebisu was known as the first angler and a deity of fishermen. He represented honesty and frankness. Ebisu is depicted holding a fishing line and a large fish on a string. Usually his earlobes are swollen (a symbol of omniscience) and he wears Japanese clothes. *See also* Daikoku; Fukujin; Hiruko; Shichi.

Eblis (A) (Islam) *see* Iblis.

Eblis (B) (Muslim) *see* Azazel; Jinn; Satan.

Ec (Yenisei People, Siberia)
Also known as: *Num, Tgorem* (Ugrian people), *Torum.*
Creator deity. Supreme god of the order of the universe. A Greek name adopted by the Mongols for their high god. He abides in the seventh sky which contains the water of life. His eyes are the sun and moon. *See also* Num; Tgorem; Torum.

Ecalchot (Niquiran People, Nicaragua)
Wind god. One of the creators who are ruled by Tamagostad and Zipaltonal. He is associated with Ciaga, Quiateot, Misca, Chiquinau, and Vizetot. *See also* Chiquinau; Ciaga; Quiateot; Vizetot.

Ecbasus (Greek)
He is the son of Argus and Evadne. *See also* Argus (A).

Echauc (Maya) *see* Ah-Kiuic.

Echecatl (Aztec) *see* Quetzalcoatl.

Echecles (Greek)
He is the son of Actor and husband of the daughter of Phylas, Polymele. *See also* Actor (C).

Echedemas (Greek) *see* Academus.

Echephron (Greek)
He is the son of Nestor and Eurydice or Anaxibia. *See also* Antilochus.

Echida (Greek) *see* Echidna.

Echidna *Echida* (Greek)
Also known as: *Echis.*
Eternally youthful half-nymph, half-snake monster. There are numerous couples known as her parents. They are either Chrysaor and Callirrhoe, Phorcys and Ceto, Tartarus and Gaea, or Styx and Peiras. Her mate is the destructive whirlwind Typhon. She is the mother of the following monsters: the Caucasian Eagle, Cerberus, the Crommyonian sow, the Chimaera, Geryon, Hydra, Ladon, the Nemean lion, Orthus the dog (possibly by Orthus), the Sphinx (possibly by Orthus) and the Vultures. It is also possible that she is the mother of three children by Heracles. *See also* Aello; Argus (B); Cerberus; Chimaera; Gaea; Harpies; Phorcys; Skylla; Tartarus; Typhon (A).

Echiodna (Greek)
She is the daughter of Phorcys and Ceto. For a list of her siblings *see* Medusa.

Echion (A) (Greek)
An Argonaut. Echion is the son of Hermes and Antianeira. In the Calydonian Boar Hunt, he threw the first spear. *See also* Argonauts; Hermes.

Echion (B) (Greek)
Husband of Cadmus, father of Pentheus, he is one of the surviving Sparti (dragon-men) who sprang from the sown teeth of the dragon of Ares. *See also* Cadmus.

Echis (Greek) *see* Echidna.

Echo (Greek)
Nymph. Daughter of Gaea, and one of the Oreads. Echo, was one of Hera's attendants. Under the assumption that Echo was covering up one of her husband Zeus' affairs with nymphs, Hera took Echo's normal voice from her. She could not begin sentences, but only repeat the words of others. Echo loved Pan but left him for the beautiful Narcissus. When he spurned her, she faded away until only her voice remained. *See also* Gaea; Hera; Oreads; Pan.

Echua *Ekchuah* (Maya) *see* Ekchuah.

Echuac (Maya People, Yucatan) *see* Icona.

Ecmar (Celtic, Irish) *see* Angus; Boann.

Edda (Teutonic) *see* Ai; Heimdall; Thrall.

Eden (Hebrew, Semitic, Sumerian)
Also known as: *Garden of Eden.*
Paradise. This legend is told in the Holy Bible, third chapter of Genesis. God planted a garden in Eden toward the east. Here he placed Adam and Eve, and food trees including the "tree of life." Compare to Dilmun. The story is similar to that of Adapa, Anu and Ea. *See also* Adam.

Edie (Hebrew) *see* Adam.

Edimmu (Sumer)
The evil genie. These Utukku are the souls of unburied dead or those dead who have not received proper burial and funeral rites. They are a ceaseless thorn of revenge on the living and difficult to appease. *See also* Utukku.

Edjo (Egypt) *see* Buto (A); Nekhbet; Uadjit.

Edom (Hebrew) *see* Adam.

Edusa (Roman)
Goddess who rules the weaning of children.

Eeriboea (Greek)
She is the second wife of Aloeus (q.v.). It is possible that she is the mother of Telamon's son, Ajax.

Eeyeekalduk (Eskimo)
God of healing. He can help heal the sick. It is dangerous to

www.ebook3000.com

look into his eyes. A small man with a black face, Eeyeekalduk lives in a stone.

Ef (Egypt) *see* Khnum.

Efe (Pygmy People, Africa)
First man. Efe was sent to earth by the supreme being, but returned to heaven. When he returned to earth after a long time, he brought spears. *See also* Orish Nla.

Efnissien (Celtic, Welsh) *see* Evnissyen.

Efrit (Arabic)
Spirits of ancient Arabians. The Efrit are evil, shape-shifters who cheat mortals. *See also* Djinns.

Efu Ra (Egypt) *see* Ra.

Egeria *Aegeria* (Roman)
Originally Egeria was a goddess of wisdom and foresight. She may have been a form of Diana as she shared the shrine at Nemi with Diana and the Camenae. In some legends she appears as the water nymph wife of king Numa Pompilius. She was a prophet and served as his advisor on occult or mystical matters, taught methods of earth worship, and pronounced the first laws of the city. In later times, she was worshiped by pregnant women who prayed for an easy delivery and who were desirous of knowing the future of the baby. *See also* Camenae; Diana.

Egesta (Greek)
She is the daughter of Hippotes, the spouse of the river god, Crimisus, and the mother of Acestes. *See also* Acestes; Crimisus.

Egil (Teutonic) *see* Orvandel.

Egilorvandel (Teutonic) *see* Orvandel.

Egis (Greek) *see* Aegeus; Aegis.

Eglimi (Teutonic) *see* Englimi.

Egyptians (Egypt) *see* Aamu.

Ehat (Egypt) *see* Ahat.

Ehecatl (Aztec People, Mexico)
Also known as: *Ehecatl-Quetzalcoatl, Quetzalcoatl* (possibly an aspect), *Texcatlipoca.*
The god of the wind, Ehecatl begins the movement of the sun and sweeps the high roadways of the rain god with his breath. *See also* Quetzalcoatl; Texcatlipoca.

Ehecatonatiuh (Aztec) *see* Legend of the Four Suns.

Ehet (Egypt) *see* Ahat.

Eidothea *Theonoe* (Greek) *see* Calchas; Theonoe.

Eidya (Greek) *see* Aeetes.

Eidyia (Greek) *see* Apsyrtus; Medea; Oceanids.

Eight Immortals, The (Buddhist, Taoist; China)
Also known as: *Ba Xian, Pa Hsien, Pa Kung.*
The Eight Immortals, seven males and one female, have various duties (although none are specific), but are usually worshiped together. Some of the immortals can only perform in conjunction with others. Versatile, they can change shape at will and fly. They are appealed to when the faithful desire to ward off evil spirits, cure minor illnesses, achieve financial success, have a long life or want to produce a male child. Their names are Han Chung-Li (Han Zhung Li), Lu Tung-pin (also spelled Lu Dongbin and also known as Lu Yan), Chang-Kuo-Lao (also spelled Zhang Kuo Lau), Lan-Ts'ai-ho (Lan Cai Ho), Han Siang-tsi (Han Xiang Zi), Tsao-kuo-chia (Cao Kuo Qin), T'ieh-Kuai Li (Di Kuai Li) and the one female, Ho-sien-ku (also spelled Ho Xian Ku). In some versions, Chung-Li-ch'uan is the chief deity, in others, it is Lu Tung-pin. In another version, one of the deities is Li Theh-kuai. Lu Tung-pin, considered to be the most popular of the Immortals, is an historical figure. Quanzhen Taoism is based on his writings. Han Chung-Li, a general during the Han dynasty, converted to Taoism. Chang Kuo-Lao and Ho-sien-ku were ordinary people, who while alive, endured suffering and injustices without complaint. The gods had tested them sorely, found them worthy and deemed them immortal. Han-chung Li, associated with immortality, wears an old green mantle and carries a feather fan to calm the sea. Lu Tung-pin, a Taoist scholar was the author of the "Hundred Character Tablet." He always carries a sword and rides a donkey backwards. Associated with medicine, he tames evil spirits with his charms. Lan Ts'ai-ho, the patron of gardeners, is said to be slightly insane. He appears as a male or a female carrying a basket of magic flowers. He began life as a street singer but later renounced all human pleasures. In the summer, he wears a tattered garment with a wide wooden belt and one shoe. During the winter months, he wears cotton and sleeps on the snow. He was carried to heaven by a stork, or in other renditions his ascent was made on a waft of wine. He threw away his belt, shoe and garments en route. Han Siang-tsi is a boy with two small hair knots on his head. He is the patron of musicians and is renowned for his poetry and music. His symbol is the jade flute. Ts'ao Kuo-kiu is a judge who carries a tablet. Ho-sien-ku is a female who wears a lotus on her shoulder. T'ieh-Kuai Li is shown as an ugly beggar who is bald and bearded and leaning on an iron crutch, which is his symbol. He is bad-tempered and has unusual ways, but his cause is directed to the poor and the weak. Compare to Arhats. *See also* Chang-Kuo-Lao; Han Chung-Li; Chung-Li-Ch'uan; Han; Han Hsiang-tzu; Lu Tung-pin.

Eikinskjaudi (Teutonic) *see* Dwarfs.

Eil (Teutonic) *see* Eir.

Eileithya (Egypt) *see* Nekhbet.

Eileithyia *Eileithyia, Eilythia, Eleuthia, Ilithyia* (Greek)
Also known as: *Lucina* (Roman).
Goddess of Childbirth. She is one of four children of Zeus and Hera. The others are: Hebe, Hephaestus and Ares. Her presence is very important during childbirth. She brings both pain and relief. Eileithyia might have been one of the ancient Cretan deities. There are versions which say she was an attendant of Hera. She is shown as a kneeling woman holding a torch. *See also* Ares; Artemis; Hera; Nekhbet.

Eilton (Celtic) *see* Dylan.

Eilythia (Roman) *see* Eileithyia.

Einheriar (Teutonic) *see* Einherjar.

Einherjar *Einheriar* (Norse; Teutonic)
Heros. The Einherjar are the warriors who have died in battle in Valhalla. They fight during the day and feast at night. They await Ragnarok, the end of the world. Einherjar is also the name of the place where they feast on the meat of the divine boar, Saehrimnir, cooked by Andhrimnir, in the magic cauldron named Eldhrimir. *See also* Ragnarok; Valhalla.

Einridi (Teutonic) *see* Thor.

Eioneus (Greek)
He is the son of Magnes. His siblings are Pierus and Hymenaeus. He courted Hippodameia and was killed by her father, Oenomaus. *See also* Hippodameia; Ixion.

Eir (Norse; Teutonic)
Also known as: *Eil, Eira, Eyr, Eyra.*
Goddess of Healing. A skilled physician, she also is an attendant to Frigga. Eir lives on Lyfjaberg, the hill of healing, with Menglad, Hlif, Hlifthrasa, Thjodvara, Bjort, Bleik, Blid, Frid, and Aurboda. They are all deities of help and healing. Eir taught medicine to women who were the only physicians in ancient Scandinavia. *See also* Frigga.

Eira (Teutonic) *see* Eir.

Eire (Celtic)
Also known as: *Ama, Anan, Anith, Anonach, Anu, Eadna, Eirean, Eirin, Eirinn, Eoghana, Iath, Ith, Momo, Mumham, Nannan, Nanu, Ops, Sibhol, Tlachgo, Tlacht.*
A mother goddess, Eire is probably an earth deity or a deity of water or darkness. Eire is possibly the same as Eriu (q.v.). *See also* Aesar (B).

Eirear (Celtic) *see* Eire.

Eirene *Irene* (Greek)
Also known as: *Pax* (Roman).
Eirene, the goddess of peace, is the daughter of Zeus and Themis. She is one of the Horae. *See also* Dike; Horae; Irene; Plutus; Themis.

Eirin (Celtic) *see* Eire.

Eithinoha (Huron, Iroquois People, North America)
One of the lower powers. Mother of spirit of wheat, Onatha.

Eitri (Norse; Teutonic)
Dwarf smith. Eitri is a master smith who fashioned the three gifts for the gods. His brother is Brokk. They manufactured the magic ring, Draupnir, the golden boar, Gullinbursti, and the hammer, Mjollnir. He is associated with Loki in that Brokk sewed Loki's lips together with Eitri's awl. *See also* Brokk; Draupnir; Dwarfs.

Eitumatupua (South Pacific)
He is the sky god spouse of the earth goddess Ilaheva, and father of Ahoeitu the King of Tonga. Jealous of their earth-born brother Ahoeitu, Eitumatupua's heavenly sons attacked and ate him. When the father found out he gathered the sons together and made them vomit. With the aid of magic herbs, Eitumatupua pieced his son together and gave him the kingdom of Tonga.

Ek Oankar (Sikh; India) The Supreme Being.

Eka *"One."* (India) *see* Devi.

Eka Obasi (West Africa) *see* Isong.

Ekadanta (India) *see* Ganesha.

Ekadzati (Tibet) One-eyed Goddess of Wisdom.

Ekajata (India) *see* Tara.

Ekako (Collao) *see* Ekkekko.

Ekchuah *Echua* (Maya)
He is the god of travelers and of planters, specifically cacao planters. He was known to have battled the god "F," the god of war or sacrifice, unsuccessfully on numerous occassions. He may be the god "M." Ekchuah has a black face and an unusually large nose. *See also* Acatl; Becabs; Icona.

Ekeko (*Collao*) *see* Ekkekko.

Ekhi (Akkadian) *see* Akha.

Ekkekko *Ekako, Ekeko, Eq'eq'o* (Andean, Collao People, South America)
Prosperity deity. Domestic good luck deity. The Ekkekko is a popular icon of good luck and is the counterpart of the Anchancho. Numerous myths have been related about the good fortune bestowed upon mortals by Ekkekko. In one legend, the Anchancho are the children of Mallcu of Chacamita, a renowned prince and his mistresses. The Ekkekko are his children by his wife, Curaj Mama. The Ekkekko are usually small figures of a happy, fat, bald man often wearing a poncho and a peaked cap. *See also* Achachilas; Anchancho; Supay.

Ekki (Turkey) *see* Akka.

El *Al, Elah, Il* (Ugarit, Canaanite, Semite, Phoenician, Ugarit)
Also known as: *Agros, Allah, Elat* (femine form of El), *Elioun, Eloah, Elohim* (plural of El), *Elyon, Ilah, Ilu.*
Supreme Semitic god. Chief god in the hierarchy of the Phoenician pantheon. Father of gods, mortals and time. Fertility god. Sun god. The word "El" means god in the sense of the supreme deity. Husband of Athirat, father of Shahar and Shalim. He dwells in the hollow of the Abyss at the Source of All Rivers. Another authority states that his wife is Asherah of the Sea, though others call her a close advisor. El's son is Baal, who is often shown with horns, brandishing a club, and holding a thunderbolt. Some writers say his sons' names are Mot and Latpon, and that Mot was his favorite. Sometimes shown as a bull or an old bearded man. He was possibly replaced by Baal. El is similar to Yahweh. Some think that the Semitic El was originally a god of the oak tree. *See also* Agros; Anat; Asherah (B); Baal; Elohim; Mot.

El Gran Dios (Spanish*) see* Nukuchyumchakob; Yumchakob.

el-Khudr (Arabic) *see* Elijah.

El Lat (Arabic) *see* Allat.

Eladu (Celtic) *see* Dagda.

www.ebook3000.com

Elagabalus (Roman)
He is a Roman emperor, worshipped as a variant of Baal at Emesa (C.E. 218–22). *See also* Baal.

Elah (Ugarit) *see* El.

Elara *Elare* (Greek)
She is the daughter of Ochomenus. An affair with Zeus resulted in the birth of the Euboeoan giant, Titysus (q.v.).

Elat (Sumer) Female form of El.

Elatha (Celtic) *see* Bress; Dagda.

Elathan (Ireland) *see* Bress.

Elbegast (Teutonic) *see* Andvari.

Elcmar (Celtic, Irish) *see* Angus; Boann.

Elcmhaire (Celtic, Irish) *see* Angus; Boann.

Eldhrimir (Teutonic) *see* Odraerir.

Eldir (Teutonic) *see* Aegir.

Electra (A) *Elektra* (Greek)
Also known as: *Laodice.*
She is most frequently called the daughter of Agamemnon and Clytemnestra. Electra is also known as the daughter of Oceanus and Tethys, the daughter of Iris and mother of Dardanos and Iasion by Ilios the sky god, or the wife of Thaumas and mother of Iris and the Harpies. As the daughter of Agamemnon and Clytemnestra, her siblings are Orestes, the musician and poet, Chrysothemis and Iphigenia. She encouraged Orestes to kill their mother. The motive was to assuage her fury with her mother for having an affair with Aegisthus. This act also avenged the death of her father. Electra married her brother's childhood friend, Pylades, and became the mother of Medon and Strophius II. *See also* Aello; Agamemnon; Electra (B); Electra (C); Eumenides; Harmonia; Harpies; Oceanids; Orestes.

Electra (B) (Greek)
She is the daughter of Agenor and Telephassa. Her siblings are Cadmus, Cilix, Europa, Demodoce, Phineus, Thasus, and Phoenix.

Electra (C) (Greek)
Electra is one of Helen of Troy's attendants.

Electra (D) (Greek)
One of the Pleiades (q.v.). The daughter of Atlas and Pleione, her siblings are Alcyone, Celaeno, Maia, Merope, Sterope and Taygete. An affair with Zeus produced two children, Dardanus and Iasion. *See also* Atlas; Merope; Sterope; Zeus.

Electryon (Greek)
He was the king of Mycenae. His parents are Perseus and Andromeda. Electryon's son-in-law, Amphitryon, accidentally killed him. Amphitryon was later purified by Creon. *See also* Amphitryon; Andromeda; Gorgophone; Perseus; Sthenelus.

Eleggua (Yoruba People, Africa)
The ruler of all paths and opportunities in life. *See also* Olodumare.

Eleio (Hawaii)
A kuhuna (diviner) who sees spirits, cures diseases and resurrects the dead.

Eleithyia (Greek)
Also known as: *Lucina* (Roman).
She is the daughter of the great god Zeus and Hera, the queen of heaven. Her siblings are the god of war, Ares; the nymph, Arge; the goddess of strife, Discordia; the goddess of eternal youth, Hebe (also known as Ganymede); and the fire god, Hephaistos.

Eleius (Greek)
He is the son of Poseidon and Eurycyda, who became the king of Elis, following his uncle Aetolus' reign.

Elektra (Greek) Another spelling for Electra.

Elephantine, Triad of (Egypt)
This triad consists of Anquet, Satis, and Khnum. In ancient Egypt, their shrine was at Yebu (Elephantine), a southern frontier city. *See also* Khnum.

Elephantis (Greek) *see* Abu (Egypt).

Elephenor (Greek)
King of the Abantes of Euboea. He is the son of Chalcodon and Imenarete or Alcinoe. With Acamas and Demophon, he went with forty ships to Troy. Elephenor was killed at Troy by Agenor. *See also* Acamas (A); Agenor; Demophon.

Eleusis (Greek) *see* Dionysus.

Eleutherios (Greek) *see* Dionysus.

Eleuthia (Greek) *see* Eileithyia.

Elijah *Elish'a, Elisha* (Arabic, Hebrew)
Also known as: *el-Khudr* (Arabic), *Ilias* (Arabic), *Ilyas* (Islamic), *Ilyasin* (Islamic).
Prophet. The Jews regarded him as a mysterious being who guards men from life to death. His father is said to be Sabak. He lives in the fifth heaven under the tree of life. Some call him the angel of the covenant and the messenger. He is supposed to return three days before the coming of the Messiah. In legend, Yahweh promised him immortality because he destroyed the priest of Ba-al. In some versions Elisha was second in command under Elijah. He is called el-Khudr (the green one) or Ilias by the Arab People. He is similar to St. George and St. Elias (Christian).

Elioun (Ugarit) *see* El.

Elish'a (Arabic, Hebrew) *see* Elijah.

Elisha (Arabic, Hebrew) *see* Elijah.

Elissa (Tyrian)
She is an early goddess who may have been known as Dido in later times. *See also* Dido.

Elivagar (Norse; Teutonic)
Eleven or twelve rivers springing from the cauldron, or as some say, spring, or well named Hvergelmir (also called Kvergjelme) in Niflheim. The rivers froze into ice blocks which are said to be the source of the clay giant Ymir. The individual names of the rivers are Svol, Gunnthra, Fjorm, Fimbulthul, Slid, Hrid, Sylg, Ylg, Vid, Leipt and Gjoll. In other versions, only some of the streams are called Elivagar. *See also* Ginnungagap; Surtr; Ymir.

Eljudnir (Teutonic)
Home of a god. Hall of the dead in Hel. It is ruled by the underworld goddess, Hel. Located in Niflheim.

Ellat (Sumer) *see* Allat.

Ellen Douglas (Arthurian) *see* Vivien.

Elli (Norse; Teutonic)
Old age. This woman wrestled with Thor in the court of Utgard-Loki. Thor lost. She was actually "Old Age." *See also* Thor.

Ellil (Sumer) *see* Enlil.

Eloah (Ugarit) *see* El.

Eloaios (Hebrew) *see* Elohim.

Elohim *Elom* (Aramaic, Gnostic, Southern Hebrew)
Also known as: *El, Eloaios, Eterah, Ilmaqah, Jerah, Sahar, Terah.*

This moon god possibly originated with the Phoenician and Aramean deity, El. Elom is the name given to the moon by Southern Hebrews. Elohim may be the same as the Arabian deity Ilah or Il. Elohim may have been connected with Marduk. Perhaps the early Hebrew legends refer to Elohim, Shaddai and Elyon as a form of El (q.v.). *See also* Abram; Yahweh.

Elom (Hebrew) *see* Elohim.

Elves (Teutonic)
Also known as: *Elbes.*

Mischievous and often feared spirits of the woods, hills and streams, Elves are said to preside over metals. Elves could be helpful or detrimental to the individual. Elves and Dwarfs are frequently confused. The original elves, said to be of Norse origin, are called Alfar. There are two groups of Alfar: light (Lios Alfar) or dark (Svart Alfar). The Lios Alfar are ruled over by Freyr; and the Svart Alfar, who live in the underground, are ruled by Wayland the Smith. If they break a rule and come out during the day, they are turned to stone. Dwarfs, trolls and gnomes spend their time collecting gold, silver and valuable stones which they secret away. The fairies and elves live in a bright, airy realm located between heaven and earth. They spend their time flitting around enjoying the finery of nature or dancing in the moonlight. Elves are thought to be a Scandinavian form of the fairy. *See also* Alfar; Alfheim; Brownie; Cluricanes; Dulachan; Dwarfs; Freyja; Freyr.

Elyon (Ugarit) *see* El.

Elysian Field (Greek)
Also known as: *Blessed Isles, Elysium, Isles of the Blest, White Island.*

Elysian Field, ruled by either Rhadamanthys or Cronus, is the destination after death of the blessed. Its location is variously described as being in the center of the earth, in the sun, or in the Isles of the Blest. The Romans believed it was located in the underworld. The concept of Elysian Field possibly originated from the Minoan civilization. A few of the well-known residents of this paradise are Cadmus, Diomedes, Menelaus and Peleus. It is also the resting place for the nine horses of the sun god, Helius. *See also* Cadmus; Cronus; Diomedes; Harmonia (A); Helius; Lethe; Peleus.

Emathion (Greek)
King of Arabia, Emathion is the son of Tithonus and Eos. *See also* Eos.

Embla *Emla, Emola* (Teutonic)
The first woman, Embla was found by Odin in the rough form of a tree. She was improved upon by Odin, Vi, and Vili, from an elm, or elder tree. Sometimes she is thought to be the spouse of Ask (q.v.). *See also* Midgard; Odin; Ve; Vili; Ymir.

Emen (Egypt) *see* Kek.

Emer (Celtic, Irish)
She is one of the wives or consorts of Cuchulain. *See also* Cuchulain.

Emla (Teutonic) *see* Embla.

Emma (Japan) *see* Emma-O.

Emma-Hoo (Japan) *see* Emma-O.

Emma-O *Emma, Emma-Hoo, Emma-Sama, Yama-Raja, Yemma* (Buddhist; Japan)
Emma-O, a Buddhist god, is the ruler of Jigoku and judge of the dead. With two decapitated heads, he judges the deeds of sinners. He has the power to prolong life and to resurrect the dead. The deeds of each sinner are weighed before judgement is handed down, condemning the soul to an appropriate section of hell. Emma-O only judges men while his sister (possibly Miru-me, one of the heads) judges women. Souls that are to be judged are brought to Emma-O in a flaming chariot by devils or demons called the Oni. Emma-O is the chief of a large number of underlings: eighteen generals and eighty thousand men. Emma-O is depicted with a menacing expression and dressed in the robes of a judge, wearing a cap inscribed with his name. The mirror is his attribute. Compare Emma-O to Susanowo (Japan) and Yama (India). *See* Ishikoridome-no-Mikoto (regarding mirrors). *See also* Dai Itoku-Myoo; Jigoku; Oni.

Emma-Sama (Japan) *see* Emma-O.

Emola (Teutonic) *see* Embla.

Empousae *Empusa* (Greek)
Demonesses. Hecate uses the Empousae to frighten foreign travelers. They will withdraw if they are insulted. They may be derived from the Lilim who were devotees of Lilith, the first wife of Adam. They are also linked with the Lamiae, who are witches that suck blood. The Empousae have one leg of an ass and one leg of brass. *See also* Hecate.

En-Ge (Semitic) *see* Adar.

En-lil (Sumer) *see* Enlil.

En-Mersi (Sumer) *see* Ningirsu.

Enarete (Greek)
The wife of Aeolus, they became the parents of seven sons: Athamas, Cretheus, Deion, Macareus, Perieres, Salmoneus, Sisyphus; and seven daughters: Alcyone, Arne (her mother may have been Hippe), Calyce, Canace, Peisidice, Perimele, Tangara. *See also* Aeolus (A); Arne; Canace; Cretheus; Sisyphus.

www.ebook3000.com

Enbarr (Celtic, Irish, Welsh) *see* Lugh.

Enbilulu (A) (Sumer)
This god of canals was appointed by Enki to ensure that the Tigris and Euphrates rivers functioned properly. *See also* Enki.

Enbilulu (B) (Babylon) *see* Marduk.

Enceladus (Greek)
Giant. Storm demon. Enceladus is the son of Tartarus and Gaea or Gaea and the blood of the castrated Uranus. He is said to be the most powerful of the giants. In some renditions, Gaea sent Enceladus to avenge the death of the monster Typhon, who was killed by Zeus. Other myths say that he was killed by Heracles or Athena. He is still held by adamantine chains in the burning cave under Mount Aetna where Zeus or Athena placed him. Every now and then he changes position, and because of his huge size, causes our earthquakes. Enceladus is depicted as a hundred-armed giant. *See also* Athena; Giants; Hecatonchires; Typhon (A); Zeus.

Endil (Celtic) *see* Dylan.

Endumion (Greek) *see* Semele.

Endymion (Greek) *see* Apis (B).

Engidu (Sumer) *see* Enkidu.

Englimi *Eglimi, Eylime* (Teutonic) *see* Hjorids.

Engur (Assyro-Babylonia) Ea as a water god.

Engus (Celtic) *see* Aengus.

Enigohatgea (Iroquois People, North America) *see* Enigorio.

Enigorio and Enigohatgea (Iroquois People, North America)
These twin brothers were opposites. Enigorio was kindly, and good. He created rivers, fertile land, and fruit trees. His twin brother Enigohatgea created natural disasters, deserts, and harmful plants. They are similar to Ioskeha and Tawiscara of the Huron People.

Eniocha *Anioche* (Greek) *see* Anioche.

Enioche (Greek)
He is the son of Creon, the king of Thebes and Anioche (also known as Eniocha) or Eurydice. *See also* Eurydice (C).

Enki (Assyro-Babylonian, Sumerian)
Also known as: *Amanki* (Babylonian), *Ea* (Akkadian, Sumerian), *Lumha, Nudimmud.*
Wisdom is the attribute of Enki, a name meaning "Lord of the Earth." He is the Sumerian counterpart of the Akkadian god Ea. Enki is also called "Lord of the Watery Deep," meaning the primeval waters known as the Apsu. Enki existed in Dilmum, a place peopled by gods, and he possibly ruled the city of Eridu. He fertilized the swampy land with his own seed. His wife, the mother goddess Nintu, gave birth to Ninmu and Nindurra. After incest with Nindurra, Enki begot Uttu, the goddess of plants. He is also thought to have been the father of Marduk. In another myth, Enki and Ninhursag are married. They became the parents of Ninmu, the goddess of plants. An interesting note is that Ninhursag's gestation period was only nine days. Enki then impregnated his daughter Ninsar, who gave birth to the goddess Ninkurra. Enki also impregnated her and she gave birth to Uttu, also a goddess of plants. Ninhursag warned Uttu against Enki's advances and advised her how to deal with him. Following her advice, she asks for gifts of cucumbers, apples, and grapes. Enki fufills her request. Enki and Uttu have intercourse and from their union eight plants were born. Before Ninhursag could name the plants, Enki ate them. Infuriated, Ninhursag cursed Enki and departed. Presumably, from the curse, Enki was stricken with illness in eight parts of his body. A cunning fox was used to persuade Ninhursag to return and cure Enki. She did so by creating eight deities, one for each area of his body that had been stricken. These deities were regarded as Ninhursag's children. It was Enki who suggested that Enlil create Lahar, the cattle god, and Ashnan, the grain goddess to earth, to feed and cloth the gods. Enlil placed him in charge of supervising the earth. After ensuring that Sumerian land would be productive, he appointed a deity for each realm. Kabta, the god of bricks, was placed in charge of the pickaxe (created by Enlil) and the moulding of bricks. Buildings and foundations were allocated to the god Mushdamma, known as the "Great Builder of Enlil." The "King of the Mountain," Sumuqan, was in charge of vegetable and animal life. Dumuzi, the shepherd god, was the supervisor of sheepfolds and stables. The goddess Ishtar felt that she had been ignored by Enki, so he allocated certain provinces to her and gave her a personal insignia. Later, when the gods became aggravated and decided to destroy all mortals with a great flood, Enki disagreed. He instructed the mortal Ziusudra to build a boat to save himself, his family, along with a few other people and animals. The goddess Ninki is thought to have been one of Enki's wives, as is Nintu (see Ninmu). The Sumerian Enki became the Babylonian Ea in later times (second-millennium B.C.E.). Enki is associated with Inanna (q.v.). *See also* Anu (B); Anunnaki; Apsu; Ashnan; Damkina; Dumuzi; Ea; Enlil; Ishtar; Lahar; Lumha; Marduk; Nammu; Nanshe; Ninhursag; Ninki; Ninmu; Ninti; Nintu; Tammuz; Uttu.

Enki-Ea (Assyro-Babylonia) *see* Ea; Enki; Enuma Elish.

Enkidu *Engidu, Enkimdu*
Also known as: *Eabani, Enkita* (Hittite); (Sumerian)
The god of farmers, land owners, and grain growers, Enkidu, a primitive being, was shaped from mud by Aruru. He moulded him in the likeness of the god Anu to overcome Gilgamesh. A protector of animals, he interfered with the capture of game and led the flocks away. Once, a prostitute was sent to strip him of his primitive powers and to civilize him. After fighting with Gilgamesh they became dear friends. Ishtar, rejected by Gilgamesh, persuaded the gods to kill Enkidu. His death set Gilgamesh searching for immortality. It was Enkidu, according to some myths, that the goddess Ishtar originally wanted to marry. Her brother, the sun god Utu, preferred Dumuzi, the shepherd god, and he desperately wanted the goddess for his wife. Ishtar, the farmer god, offered him many gifts in return for Ishtar's hand, but Dumuzi rejected them. This myth deals with the competition between the pastoral and the argicultural modes of life. Compare the friendship between Enkidu and Gilgamesh to the friendship between Achilles and Patroclus. *See also* Anu; Aruru; Dumuzi; Gilgamesh; Inanna; Ishtar; Nudimmud; Utu.

Enkimdu (Sumer) *see* Enkidu.

Enkita (Hittite) *see* Enkidu.

Enlil *En-lil, Ellil* (Assyro-Babylonian, Sumerian)
Also known as: *Adad, Bel, Illillos, Ishkur, Lil.*
An air god, earth god, and storm god (particularly hurricanes), Enlil was the most important deity of the Sumerian pantheon. He is the son of heaven, personified as the god An, and earth, the goddess Ki. When he separated from his parents, heaven and earth, the universe was created as heaven and earth separated by air. He was known as lord of the storm, lord of the spirits on earth and in the air, and ghosts. He was the patron god of the city of Nippur, where his temple was called E-Kur (the mountain house). The center of his cult was in Babylon. The name Enlil means "lord of the ghost-world." In very early times, he was associated with the goddess Ninhursag. In later mythology, Enlil was sexually attracted to the goddess Ninlil. As she was sailing on Nunbirdu stream one day, Enlil raped her. He was sentenced by a council of gods and banished to the underworld. Ninlil, who became pregnant by his heinous act, insisted that she follow him. To avert having their child born in the darkness, Ninlil gave birth to three underworld deities to serve as substitutes. She was then able to make her ascension to heaven where Nanna, the moon god was born. Following the suggestion of the god of wisdom, Enki, Enlil created other deities to follow his instructions to bring order into the universe. He created Lahar, the god of cattle, and the grain goddess, Ashnan. These two minor deities were to provide food and clothing for the gods. Often drunk, they were unable to fulfill their duties. As a result, it was decided that mortals would be created to take over their tasks. Enlil placed Enki in charge of supervising the earth. It was Enlil who created the pickaxe and presented it to the people of Sumeria. When mortals became too boisterous for Enlil to tolerate, he used his weapon, the "amaru," or the great deluge, to regain control. Enlil generally resided on the Great Mountains of the East, although he had a special abode in heaven known as "Enlil's Way." Anu had an area in heaven known as "Anu's Way," but unlike Enlil, he preferred to stay in heaven. In later times, Bel and Marduk (q.v.) acquired his mythology and Anu took over his place as leader of the pantheon. Enlil's symbol is the seven small circles representing the Pleiades. Also see Ninlil (for another version of Nanna's conception). *See also* Adad; An; Anu; Ashnan; Bel (A); Belit; Ea; Enki; Igigi; Inanna; Ishkur; Ki; Lillity; Marduk; Nammu; Nanna (B); Ninhursag; Nusku; Utnapishtim; Utu.

Enmesarra (Babylon, Sumer) *see* Enmesharra.

Enmesharra *Enmesarra, Ennmeshara* (Babylon, Sumer)
Also known as: *Nergal.*
In some versions, he is a sun god, and the protector of flocks and vegetation. In other myths, he is a god of the underworld. Enmesharra is one of the names of Nergal (q.v.).

Enmessara (Assyro-Babylonia) *see* Nergal.

Ennammasht (Sumer) *see* Ninurta.

Ennead, The (Egypt)
Also known as: *Psedjet.*
Supreme beings. The deities of Heliopolis, consisting of Ra and the eight gods and goddesses descended from him, namely, Shu and Tefnut, Geb and Nut, Osiris, Isis, Set, and Nephthys. Other deities, including Horus and Khenti Amenti, were sometimes considered to be among the company of gods of the divine Ennead. Usually there were nine deities grouped in threes. There were also the Greater and Lesser Enneads. The Greater Ennead had Horus, Isis, Nephthys, Nut, Set, Shu, Tefnut, Tem, Thoth.

Ennoia (Gnostic)
Goddess of thought. She probably originated with Simon Magus. He said the prostitute who accompanied him, named Helena, was a reincarnation of this goddess.

Ennugi (Babylonia)
He is the governor of the gods and also the god of irrigation. He watchs over canals and dikes. Ennugi is associated with Anu, Enlil, Ninurta and Ea.

Ennuki (Sumer) *see* Anunnaki.

Ennyo (Japan)
The Ennyo are female deities wearing fluttering veils. They fly around (without wings) scattering flowers in the air and playing music.

Enodia (Greek) An epithet of Hecate.

Enshagme (Semite)
Lord of Dilmun. One of the gods created by Ninhursag. Possibly a god of intelligence. *See also* Dilmun.

Entuti (Egypt) *see* Aai.

Enua (Polynesia) *see* Papa (A).

Enualios *Enyalius* (Greek) *see* Ares; Enyalius.

Enuma Elish (Babylonia, Sumer)
Babylonian Poem of Creation. Seven tablets in cuneiform text. *See also* Apsu; Ea; Enki; Gilgamesh.

Enyalius *Enulios* (Greek)
God of war. Enyalius is either the companion of Ares or his epithet. *See also* Ares.

Enyo (A) (Greek)
A Graiae. She is the daughter of "the Old Man of the Sea," Phorcys, and Ceto. *See also* Ceto; Graiae; Phorcys.

Enyo (B) (Greek)
Also known as *Bellona* (Roman)
Goddess of war. Enyo is the daughter of the god of war, Ares, and the goddess of love, Aphrodite. She went to battle with Ares. Her siblings are Anteros, Deimos, Eros, Harmonia, Pallor and Phobos. *See also* Anteros; Bellona; Eros; Harmonia (A); Pallor; Phobos.

Eo (Greek) *see* Curetes.

Eochaid Ollathair (Celtic) *see* Dagda.

Eogabal (Irish) *see* Aine.

Eoghana (Celtic) *see* Eire.

Eopuco (Maya) *see* Ah Puch.

www.ebook3000.com

Eos (Greek)
Also known as: *Aurora* (Roman).
Dawn goddess. Eos, the goddess of dawn, is the daughter of the Titan sun god Hyperion, and his sister Theia (also known as Thia or Euryphaessa). She is the sister of Selene, the moon, and Helius, the sun. She abducted her mortal husband Tithonus when he was a handsome young man. As he aged, she lost interest in him and is said to have locked him up so she didn't have to listen to his endless chattering. She had numerous affairs, among them one with Cephalus, another beautiful mortal whom she plucked from the earth to live with the gods. She has been called the mother of her husband Tithonus as well as the mother of Emathion the king of Arabia, who was killed by Heracles, and Memnon, the king of Ethiopia, by Tithonus or Cephalus, and Phaethon, who was abducted by Aphrodite, also by Tithonus or Cephalus. Some say that she was the mother of the goddess of breezes, Aura, and the morning star, Eosphorus, by Astraeus. From her relationship with Astraeus (his name means "Starry") they also produced the winds: Boreas the North Wind, Notus the South Wind, Zephyrus the West Wind, and Eurus the South East Wind. Some say they are the parents of the Evening Star Hesperus (Vesper). Eos rises from her bed each morning to travel across the sky with her brother, the sun god Helius. Together they bring the first rays of daylight to mortals. She is portrayed as saffron-robed, with flaming red hair, driving a purple chariot drawn by two horses; as riding the horse Pegasus and carrying a torch; or as a winged goddess sprinkling dew from an urn. Two of her horses are Lampus and Pegasus. Compare Eos to the Vedic goddess of dawn Ushas. *See also* Ares; Aurora; Ausera; Boreas; Ceos; Helius; Orion; Pegasus; Two Auroras; Zephyrus.

Eosphorus (Greek)
Also known as: *Lucifer.*
Eosphorus, the morning star, is the son of Eos and Astraeus. *See also* Eos.

Eostre (Anglo-Saxon)
Also known as: *Eastre.*
Goddess of the Spring. Protectress of fertility, goddess of rebirth and friend to all children. To amuse the children, Eostre changed her beautiful pet bird into a rabbit. The rabbit brought forth brightly colored eggs, which Eostre gave the children as gifts. *See also* Eastre.

Eous (Greek) *see* Helius.

Epadun (Babylonia) *see* Marduk.

Epaphus (Greek)
King of Egypt. Founder of the city of Memphis. His parents are Zeus and Io. He married Memphis, the daughter of the river god, Nile. *See also* Agenor (A); Apis; Curetes; Memphis; Nile.

Epeius *Epius* (Greek)
Founder of Pisa. The son of Panopeus and Neaera, and the brother of Aegle, Epeius was the Phoenician leader at Troy. With Athena, he built the Wooden Horse. A boxer, he won the boxing event at the funeral games of Patroclus. *See also* Athena.

Epet (Egypt) *see* Apet.

Epheseus (Greek) *see* Artemis.

Ephialtes (Greek)
He is the giant son of the sea god Poseidon (or Aloeus) and Iphimedeia. His twin is Otus. *See also* Aloeides; Giants.

Epi (Tucana People) *see* Dyai.

Epicaste *Jocasta* (Greek) *see* Jocasta.

Epidaurus (Greek)
He is the son of Argus and Evadne, or the son of Pelops, or the son of Apollo. Epidaurus is also the name of a town in the Peloponnesus. *See also* Argus (A); Evadne; Pelops.

Epigoni, The (Greek)
"Those who come later." The Epigoni are the sons of the Seven against Thebes. They successfully marched on Thebes ten years after the Seven against Thebes. For the names of the Epigoni, *see also* Adrestus.

Epimetheus (Greek)
Epimetheus is the Titan son of Iapetus and the Oceanid, Clymene, or Asia, the brother of the giants Menoetius, Prometheus and Atlas and possibly the husband of Pandora and father of Pyrrha (said to be the first woman born of a mortal). Known as moronic, he ignored a warning by Prometheus not to accept gifts from the gods (his name means "afterthought"). He accepted the gift of Pandora (the first woman) from Zeus, and she unleashed the evils of the world on mortals. In another myth, he assisted Prometheus in the formation of mortals, but he bestowed his attributes, swiftness, strength and courage, on animals and had nothing to contribute to mortals. He convinced Prometheus that man needed to be endowed with a special attribute, so Prometheus vaulted into heaven and stole fire from the sun and brought it to man in a hollow tube. *See also* Atlas; Iapetus; Oceanids; Pandora; Prometheus; Pyrrha.

Epius *Epeius* (Greek) *see* Epeius.

Epo'na (Gaul, Celtic, Roman) *see* Epona.

Epona *Epo'na, Lady Godiva* (Gaul, Roman)
Epona, known as the "Horse Goddess," was originally a Celtic tutelary deity who presided over the fecundity of the soil. Later she became goddess of the equine race. She was worshiped by Roman soldiers and shrines decorated with roses were placed in every stable. The English Lady Godiva is thought by some to be a later form of Epona. Epona is shown partially clothed, riding a mare sidesaddle or standing next to a foal. She is also depicted sitting on a throne with two foals feeding from her lap. In an ancient relief, she is shown sitting on a throne with triads of horses on either side, while a pig is being sacrificed. The key which unlocks the Underworld is one of her symbols. Compare Epona to the Celtic and Welsh mare goddess, Rhiannon.

Epopeus (A) (Greek)
King of Sicyon. He is the son of Poseidon and Canace. His siblings are Aloeus, Hopleus, Nireus and Triopas. He married Antiope, who was pregnant by Zeus. Epopeus deposed Coronis, the king of Sicyon. Epopeus was killed by Antiope's uncle Lycus. *See also* Aloeus; Antiope; Canace; Coronis; Lycus; Zeus.

Epopeus (B) (Greek)
The king of Asopia, spouse of Ephyraea and father of Marathon.

Epopeus (C) (Greek)
He was the king of Lesbos who raped his daughter, Nyctimene. She was subsquently turned into an owl by Athena.

Epopeus (D) (Greek)
Aloeus, the king of Asopia, is the son of the sun god Helius, and the father of Epopeus.

Epunamun (Araucanian People, Chile)
He is a war god, possibly of Inca origin. He is comparable to the Inca sun god Punchau (q.v.). *See also* Akanet; Pillan.

Eq'eq'o (Collao) *see* Ekkekko.

Erathipa (Aborigine People, Australia)
The erathipa is a fertility stone with a vaginal-like opening on one side.

Erato (A) (Greek)
Also known as: *Errato.*
The Muse of erotic poetry. Erato is the daughter of Zeus and the goddess of memory, Mnemosyne. She is shown holding her symbol, a small lyre. *See also* Mnemosyne; Muses.

Erato (B) (Greek) A Dryad (q.v.).

Erato (C) (Greek) One of the Danaids. *See also* Danaus.

Erato (D) (Greek) A Nereid, daughter of Nereus (q.v.).

Erda (Teutonic) *see* Jord; Odin.

Erebus (Greek)
Also known as: *Hades, Tartarus.*
Underworld god. Erebus, born from Chaos and darkness, is the brother of Nox (Night). With his sister Nox he became the father of Hemera (Day) and Aether (Sky); Cer, the goddess of violent death; Oneiroi (Dreams); Somnus, also known as Hypnos the god of sleep; the twin of Somnus, Thanatos (Death); Momus the fault finder; Nemesis the goddess of retributive justice; and Charon the ferryman of dead souls. As a deity of the lower world he is the personification of the terrible darkness through which departing souls pass to Hades. Erebus is also the name of the lower region of the underworld. The dark and mysterious place further below is often called Tartarus though many writers feel that Erebus and Tartarus are the same place. Hades is a general term used for the underworld or the deity in charge. *See also* Aether; Aither; Cocytus; Fates; Hades; Hesperides; Nemesis; Tartarus.

Erech (Sumer)
The Biblical name of Uruk.

Erechtheus I (Greek)
Also known as: *Erichthonius.*
King of Athens. Inventor of the chariot and chariot harness. He is the son of Hephaistos. When his father attempted to rape the goddess of war, Athena, his sperm fell on Mother Earth, Gaea. Erechtheus was born with the tail of a snake. Athena raised him at the Acropolis. *See also* Athena; Erechtheus II; Gaea; Hephaistos.

Erechtheus II (Greek)
Also known as: *Erichtonius.*
King of Athens. Successor of his grandfather, Erechtheus I. His parents are Pandion, who was also a king of Athens, and Pandion's aunt, the Naiad, Zeuxippe. Erechtheus is the twin of Butes. His other siblings are Philomela and Procne. Some say that Erechtheus I and Erechtheus II are the same.

Eredatfedhri (Persia)
She is the virgin invoked to defeat evil. *See also* Jahi.

Ereint (Celtic) *see* Ludd; Nuada.

Eres (Greek) *see* Ares.

Erescheigal (Babylon, Sumer) *see* Ereshkigal.

Ereshkigal *Erescheigal, Erishkegal, Eriskigal* (Babylon, Greek, Sumer)
Also known as: *Allat, Allatu* (Akkadian), *Alukah* (Canaanite), *Ganzir, Ningirda.*
Goddess and queen of Arallu, the land of no return. She ruled the underworld alone until Nergal and his evil spirits marched into her territory and forced her to marry him. He also demanded that she designate him as the King of Arralu for the price of peace. When Ereshkigal's sister, the goddess Ishtar, went to Arralu searching for Tammuz, she was held prisoner. The great god Ea created Asushu-Namir to negogiate her release. Some say her spouse was Ninazu, the grandfather of Tammuz, and her son was Ningishzida, the father of Tammuz. Ereshkigal's messenger is Namtar. She may be an alter-ego of Inanna, queen of the sky and goddess of love. Sometimes, Inanna is referred to as the sister of Ereshkigal. She may be associated with the Greek Hecate and the Sumerian Nebo. In a curse from the Greek texts *Aktiophi*, Erescheigal is mentioned in relation to Hecate. *See also* Allat; Demeter; Hecate; Inanna; Nergal.

Erginus (A) (Greek)
This Argonaut piloted the Argo after the death of Tiphys. He is the son of either the god of the sea, Poseidon, or Clymenus. *See also* Argonauts; Rhadamantus.

Erginus (B) (Greek)
King of Boeotian Orchomenus. When his father was killed by the Thebans, he avenged his death.

Erh-Lang *Er-Lang* (China)
Hero. He drives away evil spirits using his dog, T'ien K'ou. Er-lang is from the family of the Jade Emperor, possibly a nephew. He is usually shown with Nu-kua. They are dressed in mandarin clothing and accompanied by oxen, buffaloes and horses. Sometimes they are accompanied by pigs. *See also* Jade Emperor.

Eriboea (A) (Greek)
She is the mother of Ajax the Greater (q.v.).

Eriboea (B) (Greek)
Also known as: *Merope, Periboea.*
Polybus is her spouse. She raised Oedipus, the king of Thebes who solved the riddle of the Sphinx. *See also* Oedipus; Polybus.

Eriboea (C) (Greek) She is the wife of Aeneus.

Eriboea (D) (Roman)
An epithet of the goddess of marriage, Juno.

www.ebook3000.com

this for a few minutes, allowing the movement of your inner laughter to grow stronger. Then rest and use the mind and eye power to gather the Chi (now felt as a warmth behind the navel) into the Tan Tien. Picture a stove with burning fire behind your navel. Feel nice and warm.

Transform the Sexual Energy

Once you feel the Tan Tien is warm enough, smile down and bring the warm Chi down to the sexual organs; women bring the Chi down to the uterus, men bring the Chi down to the testicles. It may feel like the ‘sun shining on the water’. The rays of the sun purify the water until it becomes rising steam. Keep smiling down to the sexual organs and feel the warm or fiery feeling from the navel area continue to flow down to the sexual organs; this transforms the sexual energy into Chi, and this Chi rises up the spine into the brain helping to activate the ‘crown’ and ‘mideyebrow’ energy centers.

Focus your awareness in the sacrum. At the very tip of the sacrum there is a hole in the coccyx. Breathe into this hole until you feel some activity there. This may be felt as tingling, numbness or pulsing. If you can really activate this point it will generate 'suction'. Be aware of the sacrum opening. Feel the suction force pulling through the hole in the tailbone (sacral hiatus); breathe into it until you feel it becomes activated. When the sacrum is activated you will feel the suction easily, as well as breathing in the cranium and mideyebrow. Keep on gently smiling and softly breathing into the Tan Tien and feel the suction in the abdomen. Focus 95 % of your awareness in the Tan Tien and 5 % in the sacrum, the crown and the mideyebrow. Be aware of the Tan Tien breathing and observe internally the pulsing and breathing in the sacrum, the mideyebrow and the crown. Do this 36 times.



Fig. 2.1 *Smile down to the Lower Tan Tien.*

Eriboea (E) (Greek)
An epithet of the goddess of love, Aphrodite.

Erichthonius *Erichtonius* (Greek)
He is the son of Dardanus and Arisbe. Erichthonius became the king of Dardania and at the time, he was the richest man in the world. His marriage to Astyoche produced a son, Tros. *See also* Agraulos; Boreas; Gaea; Hephaistos; Tros.

Erichtonius (Greek) *see* Erichthonius.

Eridanus (Greek)
River god. Eridanus is the son of Oceanus and Tethys. *See also* Oceanus; Phaethon; Rivers; Tethys.

Eridu (Sumer)
Heaven or paradise. Legends say this is the place where man was created and where the souls go after death. It is a great pine whose roots are in the very center of the earth and its crown extends into the sky. *See also* Aah.

Erigone (Greek)
Harvest goddess. She is the daughter of the farmer, Icarius of Athens. When her murdered father's grave was discovered by her dog, Maera, Erigone hung herself. She became either the constellation Virgo, or Bootes. *See also* Aegisthus; Icarius (B).

Erinn (Celtic) *see* Dana.

Erinyes *Eaynnes, Erinys, Erinyes, Erynnes, Irinyes* (Greek)
Also known as: *Eumenides, Furiae* (Roman), *Furies* (Roman).
The Erinyes, goddesses of retributive justice, are Alecto (also spelled Allecto, Alektro), personifying enduring hate; Megaera, jealousy; and Tisiphone, revenge. They were born with the Giants and Meliae and are the daughters of Gaea (Earth) and the blood of their father, the castrated Uranus. They harangued, hassled and tormented the disloyal whether alive or dead and also thwarted mortals from acquiring knowledge about the future. The Erinyes represent the Triple Goddessess and are said to have lived in Erebus. A combination of the harsh and the benevolent; their work of punishment in life and death defends those whom human law fails to protect. They inflicted the tortures prescribed by the gods on villains such as Sisyphus and Tantalus when they were in Hades. The Erinyes are shown as black maidens with serpents in their hair and blood dripping from their eyes. Sometimes they are shown in snake form. The Erinyes are the same as the Roman Furies and sometimes said to be the same as the Eumenides. *See also* Eumenides; Fates; Gaea; Giants; Meliae; Nemesis; Sisyphus; Tantalus; Uranus.

Erinys (Greek) *see* Erinyes.

Erinyes (Greek) *see* Erinyes.

Eriopis (A) (Greek)
She is the daughter of Jason and Medea. Her siblings are Alcimenes, Argus, Medeias, Mermerus, Pheres, Thessalus and Tisandrus. *See also* Alcimenes; Jason; Medea; Pheres (A).

Eriopis (B) (Greek)
Her parents are Apollo and Arsinoe. She is the sister or possibly the half-sister of the god of healing, Asclepius. The king of Locris became her husband and they had one child, Ajax the Lesser (q.v.). *See also* Apollo; Arsinoe; Asclepius.

Eriphyle (Greek) *see* Adrestus.

Eris (Greek)
Also known as: *Discordia* (Roman).
Goddess of discord and strife. Eris is the daughter of Zeus and the goddess Hera. Her brother is the god of war, Ares. Her son by her father Zeus is Ate. Eris' purpose in life and the celestial realm is to cause discord, strife, lies, murders and even wars. She rolled the Golden Apple to the guests at the wedding of Peleus and Thetis and thereby indirectly caused the Trojan War. Her acts have caused competition and inspiration. She is noted with Athena for inspiring Heracles. The Adder (poisonous snake) is thought to be an aspect of Eris. *See also* Adder; Ares; Athena; Discordia; Lethe; Peleus; Thetis.

Erishgal (Babylon, Sumer) *see* Ereshkigal.

Erishkegal (Babylon, Sumer) *see* Ereshkigal.

Eriskigal (Babylon, Sumer) *see* Ereshkigal.

Erisvorsh (Slavic)
God of the holy tempest. *See also* Perun; Stribog.

Eriu (Celtic) *see* Banbha; Bress; Dagda; Eire.

Erkir (Armenian) *see* Perkunis.

Erlik-Khan *Irlek-Khan* (Central Asia)
Also known as: *Erlin* (possibly the same).
God of the dead. He has a great many spirit helpers. Only those who have sinned go to his realm.

Erlin (Ural-Altaic People)
First man, or brother of the creator. Eastern king of the dead. A confused god who thought humans would graze like cattle, but realized the mistake. He handed the sun and moon to the devil and his aides had to get them back. Other legends say there were too many suns and moons and Erlik shot the excess down with arrows. *See also* Nubti.

Erma-Ta (Egypt) *see* Ab-ta; Anherta.

Ermen-ta (Egypt) *see* Ab-ta.

Ermine (Teutonic) *see* Irmin.

Erna (Teutonic) *see* Jarl.

Ernutet (Egypt) *see* Renenutet.

Ernutit (Egypt) *see* Renenit.

Eros (Greek, Roman)
Also known as: *Amor* (Roman), *Cupid* (Roman).
God of love. Initially, Eros was born of Chaos with Gaea and Tartarus. Later he was known as the son of the goddess of love Aphrodite and either the god of war Ares or the god of fire Hephaestus. From this lineage his siblings are Anteros, Deimos, Enyo, Harmonia, Pallor, and Phobos. There are renditions stating that his mother was Venus, Iris, or Ilythiae. His father is variously named as Ares, Hermes, Mars, or Zeus. Eros pierces the hearts of gods and mortals with his gold-tipped arrows of desire. He is the most splendid in appearance of all the gods. He is shown as a chubby infant, or a handsome adult male. Often he has wings and usually carries his bow and arrow. Compare

Eros to Kama (Hindu). *See also* Adrastia; Aither; Amor; Anteros; Aphrodite; Ares; Cupid; Deimos; Graces; Harmonia (A).

Erqigdlit (Eskimo People, Canada, Greenland) *see* Adlet.

Errato (Greek) *see* Erato.

Erui (Irish) *see* Amergin; Banbha.

Erulus (Greek)
King of Italy. He is the son of the goddess of orchards, Feonia. *See also* Evander (B).

Eruncha (Australia)
These cannibalistic devils have the power to transform a man into a medicine man.

Erynnes (Greek) *see* Erinyes.

Erysichthon (A) (Greek)
He is the son of Triopas and Hiscilla. For the names of his siblings, *see* Iphimedeia (A). After destroying Demeter's sacred grove, the goddess punished him by hunger; no matter the amount of food he ate, he was hungry. He even sold his daughter, Mestra, into prostitution for food. In an attempt to quell his hunger pains, he ate his own legs. Still, he died of hunger. *See also* Demeter; Triopas.

Erytheis (Greek)
A guardian of the Golden Apples. She is the Hesperide daughter of Atlas and Pleione (some say Atlas and Hesperis). *See also* Golden Apples; Hesperides.

Erythrius (Greek)
He is the son of Athamas and Themisto (qq.v.).

Erythrus (A) (Greek)
His parents are Rhadamanthus and Alcmene. *See also* Rhadamanthus.

Erythrus (B) (Greek)
His parents are Hermes and Antianeira. The Argonaut Echion is his brother. *See also* Echion; Hermes.

Erytus (Greek) *see* Eurytus.

Erzulie (Haitian)
Goddess of beauty. The best description of this goddess is that she has all the attributes of Aphrodite. She is usually shown in elaborate dress. Erzulie was sexually involved with the Voodoo gods Damballah, Agwe, and Ogoun. *See also* Ogoun.

Es-u (Middle Eastern) *see* Abu; Tammuz.

Esagil (Sumer)
The sanctuary of Marduk in Babylon.

Esagila (Babylonian) Marduk's temple (q.v.).

Esaugetuh Emissee *Esaugeteh Emissee* (Creek People, North America)
A chief god, his name means "Lord of Wind." When the waters of the deluge receded, he moved to the mountain Nunne Chaha, and created his people from mud and clay. In another version, his home is in a cave. He created men from clay and built walls where he laid them out to dry.

Escalibor (Arthurian) *see* Excalibur.

Eschetewuarha (Chamacoco People, South America)
High goddess. Wife of the Great Spirit. She ruled over the world. Mother of birds or clouds that spread rain.

Eschu (Africa, Haiti) *see* Legba.

Esculapius (Greek) *see* Asclepius; Eshmun.

Esege Malan (Buryat People, Siberia)
A little known god who presides over the western sky.

Eset (Egypt) *see* Isis.

Esharra (Babylonia)
The sacred dwelling of the gods. *See also* Marduk.

Eshmoun (Phoenicia) *see* Eshmun.

Eshmun *Ashmun, Eshmoun, Esmoun, Esmounos, Esmun* (Phoenicia)
Also known as: *Aesculapius, Asclepius.*
God of health and healing. God of the city. Formerly a god of fertility. He became more powerful in Carthage than Melqart. He is identified with the Greek Adonis, the Babylonian Tammuz and the Egyptian Osiris. Eshmun is sometimes identified with Asclepius by the Greeks. He is possibly the same as Adonis and also the Egyptian god, Thoth. *See also* Adon; Asclepius; Astarte.

Eshu (Yoruba People, Africa)
Also known as: *Olus, Sigidi.*
Messenger and guardian spirit. God of discord. Trickster. Eshu is an important orisha who loves to test the true character of mortals. He often appears in disguise and causes confusion. Eshu is a servant of the supreme god, Olodumare, the orisha Ifa and the orisha Orish-nla. Eshu is also called Sigidi, although this name is usually used to conjure up power while meditating by a practitioner who has been paid to fulfill a request to hurt somebody. Followers worship Eshu for fear that if he is not appeased, he will cause disruption. In later times Eshu was compared to the devil of Christianity and called Olusi by the followers of the Yoruba religion, though this does not seem to be an accurate description aside from the devil as a spirit of temptation. He is usually shown with a large clever head and a knowing grin. He is thoughtfully chewing the top of his knuckle. His favorite food is cocks and the dog is his sacred animal. Eshu likes palm oil, but hates oil made from the palm kernel. The Yoruba, known for their bronze casting and stone carving from early times, have depicted Eshu in statue form. Eshu is comparable to the evil genius Legba of the Dahomeans. Eshu is also similar to Esu, the trickster deity of the Edo people. *See also* Fa (A); Ifa; Olodumare; Orish-nla.

Esmounos *Esmoun* (Greek, Phoenician)
Possibly a god of fire or heat. One of the Cabiri who was loved by Astronoe. In legend she was pursuing him and for some reason he cut off his genitals with an axe before being captured. Astronoe, in remorse, turned him into a god using her own heat. *See also* Asclepius; Cabiri; Eshmun; Sydycos. Possibly the same as Eshmun.

Esmun (Phoenicia) *see* Eshmun.

www.ebook3000.com

Eso (Edo People, Africa) *see* Eshu.

Essicalibur (Arthurian) *see* Excalibur.

Estanatlehi *Estsanatlehi* (Navajo People, North America)
Mother goddess. Goddess of youth. Helper of mortals. Estanatlehi recreates herself. When she ages, she turns herself into a young girl. Estanatlehi is the highest deity of a group of nature and household gods known as the Yei. Sometimes she is known as a goddess of rain and the west. She is called the mother of Nayanezgani and sister of Yolkai Estsan. Separately, she is known as the mother of Thobadestchin. The turquoise is her symbol. *See also* Ahsonnutli and Yolaikaiason; Atseatsan and Atseatsine; Yei; Yolaikaiason.

Estiu (Ireland)
Estiu is a bird goddess and a warrior woman.

Esus *Hesus* (Gaul)
God of vegetation and war. Little is known of Esus, but it is thought he was a wood-cutter and that human sacrifices were offered to him. His victims were hung from trees and ritually wounded. An ancient relief of Esus shows him dressed in woodman's clothing, chopping down a tree. His sacred animal is the bull. Esus is equated with Mars and Mercury of the Romans. Compare Esus to Odin who also hung his enemies from trees.

Etain (A) (Celtic, Irish)
A sun and horse goddess, she was the lover of Mider, in his form as Aileili. The obsessive Angus stole her away from Mider, and encased her in glass so that he could carry her around with him. *See also* Angus; Mider.

Etain (B) (Ireland)
A female fairy who died of grief when her mortal husband was killed. Her abode was Ben Edar Hill.

Etan (Celtic)
She is the daughter of Dia'necht, the god of medicine, and the spouse of Ogma, the god of literature, and mother of the bard Caipre. *See also* Dia'necht; Ogma.

Etana (Babylonia)
Originally an early king (Kish Dynasty), he merged with an earlier hero and became a god.

Eteocles (A) (Greek)
King of Thebes. He is the son of Oedipus and Jocasta or Euryganeia. His siblings are Antigone, Ismene and Polynices. He is the father of Laodamas. *See also* Antigone; Polynices.

Eteocles (B) (Greek)
King of Boeotian Orchomenus. He is the son of Andreus or Cephissus and Evippe, Eteocles named the Graces, and was the first to make sacrifice to them. *See also* Cephissus; Graces.

Eteoclus (Greek)
One of the Seven against Thebes, Eteoclus is also the brother of Evadne. *See also* Evadne; Seven Against Thebes.

Eterah (Ugarit)
Also known as: *Jarah, Jerah, Terah.*
This is the name used for the supreme god El, in his form of the moon god, spouse of the sun goddess. *See also* El; Elohim.

Ether (A) (Greek) *see* Aether.

Ether (B) (Phoencian) *see* Air (B); Air (C).

Ethinoha (Iroquois People, North America) *see* Nokomis.

Ethlenn (Celtic) *see* Ethlinn.

Ethlinn *Ethlenn, Ethne, Ethniu* (Celtic) *see* Cian; Clothru.

Ethne (Celtic) *see* Ethlinn.

Ethniu (Celtic) *see* Ethlinn.

Ethona (Greek) *see* Athena.

Etu (India) *see* Agni.

Etua (Polynesia) *see* Atua.

Etuda (Sumer) *see* Tammuz.

Eudora (A) (Greek)
She is the daughter of Atlas and Pleione. Eudora is a Hyade. Her other siblings are Calypso, Hyas, the Hesperides and the Pleiades. *See also* Atlas, Calypso; Hesperides; Hyades; Pleiades.

Eudora (B) (Greek)
One of the Nereids (q.v.).
Eudorus (Greek). His parents are the messenger of the gods, Hermes and his lover Polymele, the wife of Echecles. *See also* Hermes; Polymele.

Euios (Greek) *see* Dionysus.

Eumelus (A) (Greek)
Winner of the chariot race at the funeral games of Achilles. Eumelus is the son of Admetus and Alcestis, the brother of Perimele, and husband of Iphthime. *See also* Alcestis; Admetus.

Eumelus (B) (Greek)
He warned Aeneas that Trojan women were setting their ships on fire. *See also* Aeneas.

Eumelus (C) (Greek) The father of Antheias.

Eumenides (Greek)
Also known as: *Eaynnes, Erinyes, Erinyes, Furiae* (Roman), *Furies* (Roman), *Irinyes.*
Fertility deities. A name meaning "good-tempered ones," the Eumenides were given to placate the avenging spirits of the Romans, known as the Furies. Some say the Eumenides are the Erinyes; however, it is thought by others that the Eumenides had a kinder aspect to their personalities and were Chthonian goddesses (deities or spirits of the Underworld) worshipped under different names in different areas. In this role their duty was to insure the general fertility of the earth. In one version, as the Erinyes, they were given the new name, Eumenides, after a trial involving Electra and Orestes. Some say they led souls into the realm of the dead. The Eumenides have black skin, dogs' heads, snakes for hair, blood-shot eyes and bats' wings. They carry brass-studded scourges and wear soiled grey robes. They are similar to Moirai. The functions of Nemesis often overlapped those of the Eumenides. In some places they were

closely associated with the Graces. They are also similar to the Three Norns (Scandinavia). *See also* Erinyes; Furies; Graces; Morai; Orestes.

Eumolpus (A) (Greek)
With King Eleusis, the co-founder of the Eleusinian Mysteries. King of Thrace. His parents are the god of the sea, Poseidon, and Chione, the daughter of the north wind, Boreas, and Oreithyia. Chione threw her son Eumolpus into the sea. He was rescued by Poseidon and raised by his half-sister, Benthesicyme. Eumolpus is the father of Ismarus or Immaradus and Ceryx and possibly Phorbas. When he tried to seize the throne from Erechtheus, the king of Athens, during a war, he was killed. *See also* Eleusis.

Eunaomia *Eunomia* (Greek)
Goddess of seasons. The daughter of Zeus and Themis, Eunaomia is the personified goddess of law and order and one of the three Horae (q.v.).

Euneus (Greek)
King of Lemnos. Euneus is the son of Jason and Hypsipyle, the daughter of Thoas and Myrina. *See also* Jason.

Eunomia (Greek) *see* Eunaomia.

Euphemus (Greek)
The Argonaut son of the god of the sea, Poseidon, and Europa or Mecionice. Euphemus had the ability to run across water without wetting his feet. *See also* Argonauts; Europa; Lamia; Poseidon.

Euphrosyne (Greek)
"Joy." One of the Graces, she is the daughter of Zeus and Eurynome. *See also* Aglaia; Graces.

Eupolemia (Greek)
By Hermes, the messenger of the gods, she is the mother of Aetholides, the Argonauts herald, who has a perfect memory. Her parents are Myrmidon and Peisidice, the daughter of Aeolus and Enarete. *See also* Aeolus (A); Aetholides; Hermes.

Europa (A) (Greek, possibly Asian)
Europa is the daughter of Agenor, the king of Phoenicia, and Telephassa or Argiope. It is also possible that she was the daughter of Agenor's son, Phoenix. At a very young age Zeus fell in love with her. He assumed the shape of a beautiful white bull and lured her to his back. He carried her off to Crete and kept her as his mistress. Her sons by Zeus were Minos, Rhadamanthus, and Sarpedon. She later married Asterius and became the mother of a daughter, Crete (the same as the island), and he adopted her sons. In another version, she is the mother of Euphemus by Poseidon and possibly the mother of Aeacus by Zeus. In some legends, Europa and not Aegina is said to be the mother of Aeacus. The rose is associated with Europa. Compare her to Aegina, also carried off to an island by Zeus. Compare to other women seduced by Zeus in another form. *See also* Aegina; Agenor (A); Antiope; Apis; Danae; Leda; Oceanids; Poseidon; Rhadamantus; Sarpedon (A).

Europa (B) (Greek)
Danaus and Europa are the parents of fifty daughters known as the Danaids (q.v.).

Europa (C) (Greek)
An Oceanid, she is the daughter of Oceanus and Tethys. *See also* Oceanids; Oceanus; Tethys.

Europa (D) (Greek) She is the daughter of Tityus.

Europa (E) (Greek) Her parents are Phoenix and Perimede.

Eurus (Greek)
Also known as: *Apheliotes.*
God of the East Wind. Little is known of Eurus, the East Wind. He is the brother of Boreas, Notus, and Zephyrus and a son of Aeolus and Aurora. Compare to storm clouds, Chimaera, Harpies. For family history *see* Boreas; Zephyrus. *See also* Aeolus; Notus; Zetes.

Euryale (A) *Euryae* (Greek)
A Gorgon, Euryale is the daughter of Ceto and Phorcys. *See also* Ceto; Gorgons; Medusa; Stheno.

Euryale (B) (Greek) Queen of the Amazons.

Euryale (C) (Greek) She is a daughter of Proteus (q.v.).

Euryalus *Erytus* (Greek)
An Argonaut. One of the Epigoni. He is the son of Mecisteus. *See also* Argonauts; Epigoni.

Eurybatus (Greek)
He killed Lamia, the monster of Crissa. *See also* Lamia.

Eurybia (A) (Greek)
A Titan. She is the daughter of Oceanus and mother earth, Gaea. Her siblings are Ceto, Crius, Nereus, Phorcys and Thaumas. She wed Crius and became the mother of Astraeus, Pallas and Perses. *See also* Crius; Gaea; Oceanus; Perses; Phorcys; Styx.

Eurybia (B) (Greek) She is the daughter of Thespius.

Eurydamas (A) (Greek)
He is the Argonaut son of Irus and Demonassa. *See also* Argonauts.

Eurydamas (B) (Greek) He is one of Penelope's suitors.

Eurydamas (C) (Greek)
An interpreter of dreams for the Trojans.

Eurydice (A) (Greek)
Eurydice, the Dryad wife of the famed musician Orpheus, died on her wedding day. As she attempted to escape the amorous attentions of Aristaeus, the beekeeper, she was bitten by a snake. She was granted permission to leave the darkness of Hades and accompany her new husband on the condition that he not turn around to look at her until they reached the light of the world. In a moment of forgetfulness, he turned and Eurydice fell back into Hades and was punished by eternal death. *See also* Aristaeus; Orpheus.

Eurydice (B) (Greek)
Her parents are Lacedaemon and Sparte. She married Acrisius (q.v.).

Eurydice (C) (Greek)
There are numerous women in Greek mythology with the name Eurydice. King Nestor of Pylos was married to Eurydice

www.ebook3000.com

who was the daughter of Clymenus. In another legend there is Eurydice the wife of Creon, who was the king of Thebes. She was the mother of Enioche (possibly), and a beautiful son, Haemon, who was killed by the Sphinx when he couldn't answer the riddle; a daughter, Megara, who married Heracles; and Menoeceus, her virgin son, who committed suicide to save the kingdom. Grief-stricken, she killed herself after his death. There was also Eurydice, one of the fifty daughters of Danaus called the Danaids, who was said to have murdered her husband Dryas, who was also her cousin and one of the fifty sons of Aegyptus. One of the numerous children of Pelops and Hippodameia was Eurydice, thought by some to be the mother of Alcmene, the last mortal love of Zeus, who became the mother of Heracles and his twin Iphicles. Eurydice, the daughter of Adrastus, married the fourth king of Troy, Ilus, who was a famous wrestler. Their children were Laomedon, who refused to pay Apollo and Poseidon for building the walls of Troy and was killed by Heracles, and a daughter, Themiste (Themis), who became the mother of Anchises and Laocoon (not to be confused with the Argonaut of the same name).

Euryganeia (Greek)
Possible wife of Oedipus, mother of Antigone, Eteocles, Ismene and Polynices. *See also* Antigone; Eteocles; Oedipus; Polynices.

Eurymede (Greek)
She is the sister of Scylla and Iphinoe. *See also* Bellerophon; Graces; Scylla.

Eurymedon (Greek)
Hermes is his father (q.v.). *See also* Eurynome (A); Perseus; Themis.

Eurynome (A) (Greek)
She is the goddess of all things, and a creation goddess. According to the Pelasgian creation myth, in the beginning Eurynome emerged from Chaos. In order to stand she had to divide the sea from the sky. She grasped the North Wind between her hands and the serpent Ophion emerged, and coiled itself around her limbs. It was the fertilizing North Wind also known as Boreas who impregnated her. In the form of a dove she laid the Universal Egg and had Ophion coil around it seven times until it hatched and spilt in half. From this egg came all things. Eurynome and Ophion lived on Mount Olympus for a time but it is said that he insisted upon being called author of the Universe which vexed Eurynome to the point that she physically removed him from their home and banished him to the Underworld. She then created the planetary powers. A Titaness and a Titan represented each planet. Theia and Hyperion, the sun; Phoebe and Atlas, the moon; Dione and Crius for Mars; Metis and Coeus for Mercury; Tethys and Oceanus for Venus; Rhea and Cronus for Saturn. The first man, however, was said to be Pelasgus, who rose up from the soil of Arcadia. Other mortals followed. It is said that Eurynome ruled until she was displaced by Cronus and Rhea and either fell into the sea or simply retired to Oceanus. Eurynome is shown in mermaid's form. Compare to the Olympian creation myth (which did not permit the influence of the planetary powers). To compare to the Homeric creation myth, *see* Oceanus. For the Orphic creation myth, *see* Phanes. *See also* Atlas; Boreas; Ceos; Chaos; Cronus; Dione; Eurynome (B); Hyperion; Rhea.

Eurynome (B) (Greek)
Sea deity. Eurynome, a Titan, is the daughter of Oceanus and Tethys. By Zeus she is the mother of the three Graces. She is not to be confused with Eurymede, who has as an alternate name, Eurynome. *See also* Aglaia; Eurynome (B); Graces; Oceanus; Tethys.

Eurynome (C) (Greek)
She could be the mother of Adrestus by Talaus. *See also* Adrestus.

Euryphaessa (Greek) *see* Eos.
She is the Titan mother of Eos, Helius and Selene. Some say Euryphaessa and Theia, the wife of Hyperion, the sun god, may be the same. *See also* Eos; Helius; Hyperion.

Eurysaces (Greek) He is the son of Ajax the Greater (q.v.).

Eurystheus (Greek) *see* Admete; Ate; Kerberos.

Euryte (Greek) *see* Calydonian Boar Hunt.

Eurythemis (Greek)
She is the wife of Thestius and the mother of numerous children, including Althea and Plexippus.

Eurytion (A) (Greek) He is a son of Actor.

Eurytion (B) *Eurytus* (Greek)
This Centaur caused chaos at the wedding of Peirithous and Hippodameia. He was killed.

Eurytus (A) *Eurytas* (Greek)
King of Oechalia. His parents are Melaneus and Oechalia. By his first marriage, he became the father of Dryope. His second marriage, to Antiope, produced Clytius, Iole and Iphitus. Heracles, who was taught the art of the bow and arrow by Eurytus, demanded that he give him Antiope, his wife. When he refused, Heracles killed him. *See also* Dryope; Melaneus; Melas.

Eurytus (B) (Greek)
He is the twin son of Actor or Poseidon and Molione.

Eurytus (C) (Greek)
He is the Argonaut son of the messenger of the gods, Hermes, and Antianeira and the brother of Echion.

Eurytus (D) (Greek)
Another name for Eurytion, the Centaur. *See also* Eurytion (B).

Euterpe (Greek)
She is the muse of lyric poetry. Her symbol is the flute. *See also* Muses.

Euthymus (Greek)
An Olympic boxer, he sailed on the Odysseus. *See also* Caecinus; Rivers.

Evadne (A) (Greek)
She is the daughter of Poseidon and Pitane. Evadne became the mother of Iamus by Apollo. *See also* Poseidon.

Evadne (B) (Greek)
Her father is Iphis, the former king of Argos. Her brother,

Eteoculus is one of the Seven Against Thebes (q.v.). *See also* Eteoculus.

Evadne (C) (Greek)
Her parents are the Thracian river gods, Strymon and Neaera. Her marriage to Argus, king of Argos, resulted in the birth of Criasus, Ecbasus, Epidaurus and Peiras.

Evaki (Bakairi People, South America)
She is the goddess of night or sleep. Evaki stole sleep from the eyes of lizards and then shared sleep with all living things. Evaki closes the lid on the pot which contains the sun each night. She reopens it at dawn.

Evan and Bromius (Greek) *see* Bacchus.

Evander (A) *Evandrus* (Greek)
Minor deity. Evander was the son of Hermes and a nymph who was the daughter of Ladon, the river god. He was associated with Pan and was worshipped in Arcadia. It is thought that he may have been an aspect of Hermes. Evander (A) and Evander (B) are thought by some to be one and the same person. *See also* Evander (B); Hermes; Pan.

Evander (B) *Evandrus* (Greek origins)
Fertility lord. Evander was thought to be a son of Hermes and Carmenta, or Sarpedon and Laodamia. As the son of Sarpedon and Laodamia it is said that he married Deidamia the sister of Laodamia and became the father of Pallantia, Pallas, who had fifty sons all slaughtered by Theseus, Dyne (or Dyna, meaning power), Roma the goddess of strength and Sarpedon (named after his father). He was the leader of a group of Arcadian colonists who settled in Italy and built the city of Pallanteum outside of Rome. Evander joined Aeneas (who with his followers had fled from Troy) and overcame the Rutali, the Italian tribe ruled by Turnus. It is said that Evander killed Erulus, the king of Italy, three times in one day. Erulus was the son of the goddess of orchards, Feronia, who had given her son three lives and three arms. In some legends, Evander was too old to assist Aeneas in battle, so he sent his son Pallas in his place. Some say that Evander was responsible for introducing the Greek gods and the Greek alphabet to Italy. *See also* Acetes; Carmentis; Sarpedon (A); Sarpedon (B).

Evandrus (Greek) *see* Evander (A); Evander (B).

Evarete (Greek)
The daughter of Acrisius and Eurydice, the sister of Dane, she married Oenomaus and became the mother of Hippodameia and Leucippus. *See also* Acrisius; Hippodameia; Keycuppus; Oenamaus.

Eve (Hebrew, Semitic, Babylonian)
Also known as: *Chavah, Chavva, Eva, Evita, Haiwa* (Arabic), *Hawwa, Heve, Mashye* (Persian).
First woman. After causing Adam to fall into a deep sleep, Yahveh took a rib from him and made Eve. In the original legend there was no mention of the name of Adam's mate. In the Koran, her name is not mentioned, and she is referred to as Adam's spouse. Later, she was called Haiwa. Adam and Haiwa had twenty sets of twins; each set a boy and girl. Eve is usually portrayed nude, her loins girded by grape leaves. Sometimes she is shown holding an apple. Her legend is similar to the legend of Adapa. *See also* Adam; Adapa.

Evenus (Greek)
He is the son of Ares and either Demonice or Alcippe. He married a woman named Alcippe. They had three children: Epistrophus, Marpessa and Mynes. When his daughter, Marpessa, was kidnapped by Apollo, Evenus committed suicide. *See also* Ares.

Evnissyen *Efnissien* (Celtic, Welsh), *Evenissyen*
The stepbrother of Bran, Branwen, and Manawyddan. Evnissyen caused a battle between Ireland and Britain when he killed Gwern, the son of Matholwch and Branwen, by casting him into the fire of the hearth. *See also* Bran; Branwen.

Excalibur (Arthurian) *see* Kusanagi; Vivian (Japan).

Excellent Archer (China) *see* Chang-O; "I" (A).

Exizkur (Babylonia) *see* Marduk.

Eylime (Teutonic) *see* Englimi.

Eyr (Teutonic) *see* Eir.

Ezuab (Sumer)
The home of Ea, Ezuab is located in the sacred city of Eridu. *See also* Ea; Eridu.

F

F (Maya People, Yucatan)
A god of war or sacrifice, F was the victor in numerous battles with the god of travelers and planters, Ekchuah (q.v.).

Fa (A) (Egypt, Africa, Dahomey people)
Also known as: *Ifa* (Dahomey, Africa); possibly *Orunmila.*
The Dahomey people consider this deity to be the greatest of all the gods. Generally thought of as the personal fate of each person. Fa may be associated with the African (Dahomey) god of destiny with the same name. In that sense the name means the soul or personal fate of each man. Some versions associate Fa with Legba and with Eshu. In general, Fa and Ka (Egypt) are the soul. Fa is associated with the palm nut. *See also* Ifa; Tuat.

www.ebook3000.com

Fa (B) (Egypt)
God of destiny. In the Egyptian cosmology the name is associated with the soul. In Egyptian mythology this is one of twelve gods in the eleventh sector of Tuat. He is the bearer or carrier who carries on his head the serpent Mehen to the eastern part of the sky. The other gods are Ermenu, Athpi, Netru, Shepu, Reta, Amu, Ama, Shetu, Sekhenu, Semsem, and Mehni. May be associated with the African (Dahomey) god of destiny with the same name. In that sense the name means the soul or personal fate of each man. In general, Fa and Ka (Egypt) are the soul.

Fa-Akh (Egypt) *see* Aaru.

Fa-Pet (Egypt) *see* Aaru.

Fa'a-ti (Polynesia)
Fa'a-ti is located within the inner shell, Timi-iti. The outer shell is known as Rumia. It existed in the primeval darkness, Po. The self-created, supreme god, Ta'aroa came from Fa'a-ti. *See also* Ta'aroa.

Fabruus (Roman) *see* Dis; Pluto.

Fachea (Irish) Goddess of poetry.

Fafnir *Fafner* (Norse, Teutonic)
A dragon deity. Brother of Otr (Otter) and Regin. Son of Hreidman (Hreidmar). When Loki killed Otr he was forced to cover Otr in gold. Because of disagreement between Otr and Regin, Fafnir turned himself into a dragon. Both brothers were slain by Sigurd. In one version Otr was killed by Loki. Fafnir wore a helmet named Aegis (helmet of dread).

Fagus (Celtic) Beech tree god. *See also* Abellio.

Fakahotu (Polynesia)
Also known as: *Hakahotu.*
The female force. The male source was Papa or Te Tumu. *See also* Papa.

Fal (Teutonic) *see* Dwarfs.

Falias (Celtic)
This is the Tuatha de Danann city of the north. The "Stone of Destiny," also known as the "Stone of Fal," came from this city. *See also* Tuatha de Danann.

Fama (Roman) *see* Pheme.

Famien (Africa, Guinea)
Fertility deity. Sometimes said to be a god of good health. If carried in the form of a knife in a bag it represents the true power of the god. Sometimes two knives are carried in the bag. Represented as a cave or carried around in a bag. Similar to grigris which are bundles of sacred objects.

Fan K'uei *Fan K'uai* (China)
God of butchers. Mortal whose occupation was a dog skinner in the Han era and was later adopted as a deity of butchers. In some legends the deity of butchers is Khang Fei or Chang Fei who was a pork seller.

Fan T'ao (China) *see* P'an-T'ao.

Fand (Celtic)
She is the abandoned wife of Manannan Mac Llyr. She became the mistress of Cuchulain. After a tryst in Mag Mell (Plain of Joy) she left him and returned to her husband. *See also* Cuchulain; Manannan Mac Llyr.

Fanus (Roman)
Also known as: *Fauna, Fauni* (Plural), *Faunus, Pan* (Greek).
God of crops. God of fertility. Inventor of herding, hunting, and husbandry. Protector of agriculture and shepherds. Inventor of poetry. Fanus is the grandson of Saturn, the nephew of Juno, the son of Picus, the prophet and demigod. His companion is Fauna (also known as Bona Dea), the fertility goddess and goddess of animals. Fanus is the father of Latinus, a mortal king, by Marica, a water nymph. He is possibly the father of Acis by a nymph. Fanus is identified with the Greek Pan. He is associated with Romulus and Remus. *See also* Bona Dea; Fauna; Picus; Saturn; Stercutius.

Faraguvaol (Antilles)
Faraguvaol is a a tree-trunk that wanders at will. It is one of the Zemis (spirits). It is shown as a wooden beam or a tree trunk. *See also* Zemis.

Faravai (Micronesia) *see* Palulop.

Farbauti (Teutonic) *see* Farbuti.

Farbuti *Farbauti* (Teutonic)
He is the mate of Laufey or Nal, and the father of Loki and Helblindi (q.v.). *See also* Forjotnr.

Faridun *Thraetana, Thraetaona, Thrita* (in earlier times); (Persia)
God of war. Bringer of fire. Faridun, a deified mortal, was an epic king who concealed his daughter. She became the mother of the hero Manushcithra (also known as Minucihr) who became Faridun's successor. The evil conqueror Zahhak was killed by Faridun with the assistance of the smith Kava. *See also* Thrita; Zahhak.

Farma-Tyr *see* Odin.

Faro (Mende People, Africa)
First man and twin of Pemba. According to legend Faro was sacrificed to atone for Pemba's sin of incest, and Faro was cut into pieces which became trees. Faro was sent back, alive, to earth in an ark which came to rest in a cave named *kaba karo.* The ark contained Faro and the eight ancestors of men. It also contained all the animals and plants that were the ancestors of those that exist now. Said to be depicted as a fish or fish-like. *See also* Mangala (B); Nyama; Pemba.

Fates *Fata, Fatum* (Greek)
Also known as: *Moirai, Moerae* (Greek), *Parcae* (Roman).
Personifications of implacable destiny. Triple Moon-goddess (in her death aspect). First identified in Hesiod's "Theogony," they were either the three daughters of Nyx (Night): Clotho (the spinner), Lachesis (Apportioner), and Atroposy (Atropos) (the cutter), or the daughters of Zeus and Themis. Their names imply the mortals' lot in life; the spinning, measuring and cutting of life. In another version, they are the daughters of Night and Erebus. The later poet Pindar makes them attendants of Themis when she married Zeus. They frequently appear in opposition to Zeus, which gave them greater power than Zeus.

As the Parcae they were Decima, Parca and Nona. Known to the Greeks as the Moirae, they aided the gods in their war with the Giants, killing Agrius and Thoas with bronze clubs. Although they usually remained distant from the affairs of gods and mortals it is recorded that they assigned Aphrodite with the one divine duty of making love, that they assisted Hermes in formulating the alphabet (although some attribute this to Io), the art of boxing, the use of weights and measures and the cultivation of the olive tree. They killed Typhon with poison fruit, and persuaded Zeus to kill Asclepius with a thunderbolt. Their number varies from one to three. In the single version Fate is called Moira and is associated with luck or fortune similar to the role Tyche plays. The Fates were worshipped in many parts of Greece. Sometimes they are associated or identified with the Keres and the Erinyes. They correspond to Tyche and to the Hebrew goddess, Meni. *See also* Admetus; Agrius (A); Clotho; Eumenides; Furies; Keres; Meliae; Moirae; Muses; Parcae; Sirens; Themis; Typhon (A).

Fatimah *Fatima* (Persia) *see* Ali (B); Mohammed.

Fatua (Roman) *see* Bona Dea; Fanus.

Faumea (Oceanic)

Also known as: *Haumea, Nona.*

Faumea, the eel-woman, taught the great god of the sea, Tangaroa, how to lure the man-killing eels out of her vagina. After sleeping together, Faumea gave birth to Tu-nui-ka-rere (or Ratu-nui) and Turi-a-faumea. Turi and his wife, Hina-arau-riki, were surfing one day, when Rogo-tumu-here, the demon octopus, captured Hina and spirited her away to the bottom of the ocean. Bereft, Turi assisted Tangaroa and Tu-nui-ka-rere in building a canoe, so he could search for his beloved. Faumea, who had withdrawn the wind into the sweat of her armpit, released it to power their canoe. When Turi and Tangaroa reached the ocean home of Rogo-tumu-here, Tangaroa baited his hook with sacred red feathers. Attracted to the bait, Rogo was pulled tentacle by tentacle into the vessel and each was sliced off by Tangaroa. When Rogo's head appeared, he decapitated him and from his head Hina, covered with the slime of the ocean, appeared. *See also* Haumea; Rata; Tangaroa.

Fauna (Roman)

Goddess of fertility. Counterpart to Fanus. Sometimes said to be either his daughter, sister or wife. Identified with Bona Dea.

Faunus (Roman, Greek) *see* Fanus.

Faustulus (Roman)

He is the herdsman spouse of Acca Larentia.

Favonius *Favonus* (Roman)

The west wind. *See also* Harpies; Zephyrus.

Febal (Celtic) *see* Bran.

Febris (Roman)

Febris is the goddess of fever and malaria. She is attended by Tertiana and Quartiana. The month of February is named after Febris.

Februus (Etruscan, Italian)

God of purification. He is probably a forerunner of Dis Pater and he might be the same as Febris, the Roman goddess of malarial fever.

Feng Huang (China)

The Phoenix, and one of the Ssu-ling. The Feng Huang has five colors, and a song of five notes. It can raise its tail to the height of six feet. It is an omen of prosperity. According to some, the Phoenix represents the empress and the dragon represents the emperor.

Feng I (China) *see* Nine Songs.

Feng Po (China)

Also known as: *Earl of Wind, Feng Shih.*

Wind god. As a male he is God of the Wind. Sometimes replaced by Feng-P'o-P'o (Mrs. Wind) who is goddess of the wind, and is shown riding on the back of a tiger. Generally associated with Tien-Mu, Yu-tzu and Yun-t'ung, all weather deities. *See also* Feng Po-Po; Fujin.

Feng Po-Po *Feng P'o P'o* (China)

Goddess of the Wind. She replaced the Count of the Wind. Feng Po-Po travels over the clouds seated on a tiger. She carries a bag of winds in her arms. *See also* Feng Po.

Feng Shih (China) *see* Feng Po.

Feng-Tu (China)

Town of the dead. The chief city of Hell. There are three bridges that must be crossed to arrive at the gate. One gold, one silver and without railings, and one narrow and dangerous to cross. These bridges are for the gods and for the souls of the good and of those deserving punishment. Inside the gate are the palaces of the Yama Kings and the dwellings of the numerous officials and assistants and of all those who carry out the functions of the world of the dead. *See also* Kun-Lun Mountains; Yama Kings.

Fenga (Iceland) *see* Mysinger.

Fenne (Irish) *see* Aine.

Fennen (Irish) *see* Aine.

Fenrir *Fenrer, Fenris* (Norse; Teutonic)

Also known as: *Hrodvitnir.*

This wolf god is the offspring of Loki and Angrboda. He is so huge and fierce that only Tyr was able to chain him. Tyr lost a hand in the process. Fenrir was first bound by a chain called Laeding (also called Leding) made of strong iron links. Fenrir broke it. Then he was bound by an even stronger chain called Dromi that he also broke. The last chain, forged by dwarfs, was called Gleipnir. Made from invisible powers of the world, and small as a silken cord, it was unbreakable. Fenrir is still bound on an island in the sea (Amsvartner), waiting for the apocalypse known as Ragnarok. At that time, he will break loose. In some sources Fenrir is bound by a chain called Gelgja tied to or drawn through a black rock named Gjoll. Some say Fenrir had two sons by Gulveig-Hoder, one named Hati and the other Skoll. The two were called the Varns. In another version Hrodvitnir was the father of Skoll and Hati. *See also* Bifur; Dain; Dromi; Dwarfs; Gleipnir; Gullveig; Hati; Laeding; Loki; Ragnarok; Skoll; Thviti.

www.ebook3000.com

Fenris (Teutonic) *see* Fenrir.

Fenti (Egypt) *see* Assessors.

Fergus Mac Roig *Fergus Mac Roy* (Celtic, Irish)
Foster father of Cuchulainn. He possesses the strength of 700 men, and a sword as long as a rainbow. He fought Conchobar because of Deidre. *See also* Cuchulainn.

Feronia (Etruscan)
Goddess of fire and fertility. *See also* Evander (B); Flora.

Fiachna (Irish) *see* Manannan Mac Llyr.

Fialar (Teutonic) *see* Fjalar.

Fides (Roman)
Goddess of good faith. Goddess of fidelity. Fides is responsible for honesty, oaths and verbal contracts. She wears a wreath of laurel and olive. Her festival date is October 1.

Figonas *Higona, Hi'ona, Vigona* (San Cristobal)
Creators. Spirits who were named Hatuibwari, Aunua, and Walutahanga. Hatuibwari was a winged serpent with a human head, four eyes, and four breasts. Walutahanga was a female serpent born to a mortal woman. The Figonas are shaped like serpents. They are similar to the Kafisi spirits. *See also* Kafisi; Ndengei.

Fihrist (Gnostic)
High God. Fihrist is possibly a forerunner of Azrua in the context of "King of the Paradise of Light." He may be related to Zurvan and Ahura Mazda. *See also* Azrua; Zurvan.

Fili (Teutonic) *see* Dwarfs.

Fimafena (Teutonic) *see* Aegir.

Fimbulthul (Teutonic) *see* Elivagar.

Fimila (Teutonic) *see* Aesir.

Find (Celtic) "Fair-haired One." *See also* Finn; Lugh.

Fingal (Celtic, Irish) *see* Finn.

Finias (Celtic)
The Tuatha De Danann city of the south. Nuada's spear came from Finias. *See also* Nuada; Tuatha De Danann.

Finn (Celtic, Irish)
Also known as: *Demne, Fi'onn Mac Cumhal, Find, Fingal, Finn Mac Cool, Finn Mac Coul, Finn Og mac Cumhail, Fionn.*

Finn was a giant who could stand on two mountain tops and stoop to drink. Superhuman in all ways, he was the leader of the Fenians (fiana), a roving band of warriors. Known as Demne in his youth and raised by foster parents, he lived for over two hundred years. In one rendition, he was the son of Cumhal and Muirne (Murine). He became the father of Oisin, by Sadb and the grandfather of Oscar. He acquired the thumb of knowledge which allowed him to foresee the future by sucking his thumb. His dogs, Bran and Sceolan, had the reputation of being the wisest of all dogs. These pets were his nephews in dog-form. In one myth, Finn approached the High King of Ireland to ask for his daughter Grainme's (Grainne) hand in marriage. While at a banquet, Grainme spied Finn's friend Diarmait and instantly fell in love. After drugging the guests she declared her undying love to her fiance's friend. Gallantly, he refused to be involved with her. Determined, she cast a spell on him and they eloped. Furious at the unexpected turn of events, Finn set off in pursuit and although he caught the couple, the gods were with them and they escaped. In time, the fences were mended and they were embraced by the Fenians, not knowing that Finn still harbored a grudge. He enticed Diarmait on a hunt and caused his death by having him walk over a boar skin, in bare feet. Like Achilles, this was Darmait's only vulnerable spot, as his friend well knew. Finn lived a lengthy life as a poet, lover, rogue and hero. In some myths, he does not die but becomes very decrepit and drifts into the Otherworld, where he is said to be sleeping. Compare Finn and King Arthur for similar traits. Regarding the thumb of knowledge *see* Finneces. *See also* Murine; Oisin.

Finntain (Irish) *see* Cessair.

Fintan (Irish) *see* Cessair.

Finuweigh and Mehu (Philippines)
When the other gods attempted to create man from wax, they failed. Finuweigh and Mehu used a different approach. They made a man from dirt. Finuweigh put the man's nose on upside down. Mehu pointed out that if the nose was left in that manner, man would drown from rain running into his nostrils. Finuweigh refused to change the nose. When he turned away, Mehu quickly turned the nose around. He left his fingerprints on each side of the man's nose.

Fiorgyn (Teutonic) *see* Fjorgyn.

Fir Bholg (Celtic) *see* Firbolgs.

Firbolgs *Fir Bholg* (Celtic)
A mythological race defeated by the Tuatha De Danann. Considered by some to be the first fairies of Ireland, the Firbolgs are giant, grotesque creatures. Some claim they originally came from Greece. *See also* Banbha; Tuatha De Danann.

Fire (Phoenician)
With Flame and Light, Fire was one of the three children of Genos and Genea in the Phoenician Creation Legend. From Fire, his sons Hyposouranios, the first to build towns, and Ousoos, the first to use skins for garments, were born. *See also* Kolpia.

Firishtak *Firistak* (Persian) Angels. *See also* Aramazd.

Fith (Teutonic) *see* Dwarfs.

Five Blossoms (Mexico) *see* Macuilxochitl.

Five Suns (Aztec, Mexico) *see* Legend of the Four Suns.

Fjalar (Norse; Teutonic)
Also known as: *Havamal, Loki, Suttung, Utgard-Loke.*

The Red Cock. Fjalar, the symbol of fire, is the son of Surtr, the chief of the fire giants. When Ragnarok, the end of the world, is near, Fjalar will warn the giants. He is the giant from whom Odin stole the magic mead. He is also associated with the gods of frost. *See* Loki; Odin; Surtr.

Fjolnir (Teutonic) *see* Odin.

Fjorgyn *Fiorgyn* (Teutonic)

An Asynjor, also known as Jord, she is the giant mate of Odin, the mother of Frigga, and the mother of wife of Thor. *See also* Aesir; Earth; Jord; Odin.

Fjorgynn (Teutonic)

He is sometimes called the father, or the spouse of Frigga.

Fjorm (Teutonic) *see* Elivagar.

Flame (Phoenician) *see* Kolpia.

Flames (Teutonic) *see* Logi.

Flames of Wisdom (Tibet) *see* Dorge-Naljorma.

Flint (Huron, Iroquois People, North America) *see* Tawiscara.

Flora (Greek, Roman)

Also known as: *Chloris* (Greek), *Feronia* (Etruscan).

Goddess of fertility, and of flowering plants. Flora is an ancient deity of spring. Her festivals were called Floralia. It was a time of theater, dance, games and wonderful food. In some traditions, she is the Etruscan goddess of fire, Feronia. She is generally associated with Pomona, the goddess of fruit trees. She is also associated with Robigus. For Flora as Feronia *see* Evander (B). *See also* Zephyrus.

Flower Face (Celtic) *see* Blodeuwedd.

Fodla (Irish) *see* Amergin; Banbha.

Foge and Toafa (Samoa) Spirits in charge of rain.

Foland (Teutonic) *see* Volund.

Fomagata (Chibcha People, South America)

Also known as: *Thomagata.*

Storm god. Terrifying fire spirit. He is able to change men into animals. Bochica removed him. *See also* Bochica; Thomagata.

Fomorians (Celtic)

Also known as: *Fomors.*

Gods of darkness and evil. The Fomorians are a race of giants symbolized by darkness or evil. They were defeated in battle by the Partholanians, who then succumbed to the plague, with the exception of one member. *See also* Goibniu; Tuatha De Danann.

Fomors (Celtic) *see* Fomorians

Fongasigde (Andes, South America) *see* Naymlap.

Fons (Roman)

They are spirits of fresh water who were worshiped with the Camena who were also water deities.

Formorians *see* Banbha (Irish).

Fornax (Roman) *see* Inari; Vesta.

Fornjotnr *Fornjot, Fornjotnr, Forjotnro, Fornjotr* (Norse; Teutonic)

Also known as: *Farbuti, Ymir.*

Supreme first god. Storm god. It is commonly accepted that Ymir is the founder of the gods, but some say it was Fornjotnr. He had three sons: Hler (sea), Kari (air), Loki (fire). From his sons came the other frost giants: Mimir, Grendel, Gymir (sea giants); Thiassi, Thrym, and Beli (storm giants); Fenris and Hel (giants of fire and death). Fornjotnr is the father of Loki and Aegir by Haufey or Nai. *See also* Aegir; Fenrir; Kaare; Loki; Ymir.

Fornjotnro (Teutonic) *see* Fornjotnr; Ymir.

Forseti *Forsete* (Norse; Teutonic)

God of justice. He is the son of Balder and Nanna. Forset is one of the twelve major deities mention in the "Eddas." His home in Asgard, called Glitnir, is made of gold and silver. For a list of the other major deities *see* Ull.

Fortuna (Roman, Etruscan)

Also known as: *Fors, Muliebris, Primigenia, Tyche* (Greek), *Univirae.*

Goddess of good luck, chance and fortune. Deity of fate. Fortuna's festival date is June 24. She is shown on a round globe with a cornucopia in one hand and a rudder in the other hand. Her symbol is the wheel of fortune. She is also shown with the god of wealth, Ploutos, in her arms. *See also* Tyche.

Fotia (Irish) *see* Amergin; Banbha.

Fotla (Irish) *see* Amergin; Banbha.

Four Branches, The (Celtic) *see* Arianrhod.

Four Great Kings (India) *see* Dhartarastra; Lokapalas; Naga Knaya.

Four Hundred, The (Aztec) *see* Centzon-Huitznahuas.

Four Hundred Northerners, The (Aztec People, Mexico)

Star gods. *See also* Centzon Mimixoca.

Fraig (Teutonic) *see* Freyr.

Fratres Arvales (Roman)

The twelve sons of Carutius and Acca Larentia.

Frau Holle *Frau Venus* (Teutonic) *see* Holda.

Fraus (Roman) Goddess of treachery and fraud. *See also* Nox.

Fravahar (Persian) *see* Fravashi.

Fravak and Fravakain (Persia) *see* Mashya and Mashyoi.

Fravar (Persian) *see* Fravashi.

Fravartin (Persia) *see* Fravashi.

Fravashi *Fravartin* (Pre-Zoroastrian, Zoroastrian, Persia).

Also known as: *Fravahar* (Pahlavi dialect), *Fravar* (Persian), *Hrotik* (Armenian).

The Fravashi (meaning "genius") appear in the *Avesta* as one of a group of angels. Their function is to assist in making plant life grow and reproduce. In Zoroastrianism, they are the guardians of divine and human beings. The Fravashi is a spirit created by Ormazd (the later form of Ahura Mazda), who exists before the birth of a mortal, protects the mortal during life, and rejoins the soul at death. Fravashis are constantly at war against evil. Prosperity is visited upon the faithful followers who fulfill

www.ebook3000.com

Filling the Joints with Chi

The bones have the ability to process Cosmic Chi (Chi above and around us) to be used by the body. The joints are also able to store Chi and they also serve as the cushion between the bones.

Be aware of your index fingers and thumbs; lightly raise the index fingers, feel a slight tension and open the thumbs to the sides and feel it magnify. Breathe into the finger tips, until you feel the sensation of Chi entering the fingers. The fingers will feel stiff as they stretch, to make way for the Chi entering the joints. Continue to breath in the Chi - the stiffness will spread to the other fingers, wrists, elbows and shoulder joints making the whole arm tense and stiff. The fingers and the arms become one piece. Eventually the Chi will fill every joint of the body making it into a complete unit.

Be aware of the big toes; breathe into the toes and feel the toes grow longer. When the Chi fills the joints the big toes become tense and stiff. Gradually it will fill the other toes rising to the ankles, knees, hips, sacrum and spine; the feeling may be one of tension and stiffness, numbness or like an electrical charge. The legs and the spine become one piece. You will certainly feel good.

Bone Breathing and Marrow Washing

Bone Breathing is one of the main practices of Cosmic Healing Chi Kung. This is a method of drawing external Chi through the skin into the bones to help replenish the bone marrow, thereby reactivating the production of white blood cells. Sending Chi into the bones will enhance functioning of the immune system. This process also helps to clean out fat in the bone marrow ("Washing the Marrow"), one of the main causes of osteoporosis (brittleness of the bones). Tension in the muscles close to the bones is decreased so Chi and blood can flow into the bones easily, enabling them to become stronger.

The Bone Breathing process uses the mind and the eyes to absorb Chi into the bones. The better your Bone Breathing is the better your Cosmic Healing Chi Kung practice will be. Mind and eyes are also used immediately after the exercise to gather the energy at the navel. Once you have it, when you move your hand, the energy will follow easily. You will be able to absorb external Chi effortlessly, so you will not need to use your own energy in your healing work.

Bone Breathing

There are several variations in the Bone Breathing and Marrow Washing process. Here we will introduce you to the first type of Bone Breathing, inhaling and exhaling Chi their duties to the Fravashi and burn incense in their honor. The 19th day of each month is devoted to them as are the last ten days of the year. The Chief of the Fravashis is Verethraghna, who personifies the idea of victory. In Armenian belief, the Fravashis live near the houses or tombs of followers. Devotions are offered on Saturdays and also before important festivals. Compare Fravashi to Manes (Roman) and Pitris (India). *See also* Ahura Mazda; Atar; Verethraghna; Zoroaster.

Fravashis *Fravartin* (Persia, Zend), *Hrotik* (Armenian)
Goddess of Souls. Guardian. Singular of the plural, Fravashi (meaning "Genius"). She-Who-Is-Many is Fravashi. Fravashi is composed of the souls of all living creatures, including the Not-Yet-Born. She is the defender of all living creatures. Said to be created by Ormazd. In some legends the Fravashis exist in heaven before birth and join the soul after death. The chief of the Fravashis is Verethraghna, who personifies the idea of victory. *See also* Atar; Verethraghna.

Frea (Teutonic) *see* Frigga.

Freki *Freke* (Norse; Teutonic)
Deified animal. With the wolf Geri, Freki, also a wolf, attends Odin.

Frey'a (Teutonic) *see* Freyja.

Freya (Teutonic) *see* Freyja; Vanadis.

Freyja *Frey'a, Freya* (Teutonic)
Also known as: *Gefjon, Gefn, Gondul* (possibly), *Horn, Mardal, Mardoll* ("Shining One over the Sea"), *Menglad, Menglod, Moertholl, Sessrymner, Syr, Vanadis.*
Goddess of Fertility. Freyja is the daughter of Njord and the twin sister and wife of Freyr. (Some writers say her husband is the mortal Od.) Her daughters are Hnoss (meaning jewel), by Odr who is possibly an aspect of Odin and Gersimi (Gerseme, meaning "precious one), and some say Frigg. Freyja is one of the Vanir. Her hall or home is called Sessrumnir. Loki borrowed Freyja's magic robe of feathers, which enabled him to fly to the land of the giants in search of Thor's hammer. Freyja's most famous possession is her amber necklace, known as "The Necklace of the Brisings." Freyja noticed four dwarves, Alfrigg, Dvalin, Berling, and Grerr, who were employed by the palace, working on a beautiful necklace. Overwhelmed with desire for the precious piece, she agreed to pay any price to call it her own. The only acceptable price to the dwarfs, who had many precious items stashed away, was to have the beautiful woman to spend a night in bed with each of them. Without second thoughts, she did so. In another attempt to procure his hammer from the giants, Thor disguised himself as Freyja and borrowed her necklace. Loki accompanied him dressed as a servant. At a later date, Loki, following Odin's orders, stole the necklace. He attempted to hide it but was apprehended by Heimdall, who was in the form of a seal. After a vicious encounter, Heimdall returned the necklace to Freyja. Gondul, the Valkyrie, who went to earth to retrieve the souls of kings who died in battle, is thought by some to be one of Freyja's disguises. Freyja is depicted in a robe of feathers, wearing her necklace and riding in a cart drawn by cats. Sometimes she is shown on the golden boar thought by some to be her brother Freyr. She loved decorative items, particularly jewelry, but she is also shown in a helmet and breastplate. Compare Freyja's necklace to Hippolyte's girdle (Greek) and to the necklace of Amaterasu (Japan). Some associate Freyja with Cyble and Isis. Compare Freyja's mode of dress to Minerva. *See also* Aesir; Brisingamen; Disir; Dvalin; Dwarfs; Elves; Frey; Gefion; Heimdall; Loki; Menglad; Odin; Vanadis; Vanir.

Freyr *Fraig, Frey, Fro* (Norse; Teutonic)
Also known as: *Fricco, Ingun, Ingunnar-Frey, Ingvi-Frey, Sviagod* (Swedish), *Yngri* (Swedish), *Yngvi.*
Freyr is god of the world, earth, patron of married couples, a fertility god, and the ruler of the dwarfs. A Vanir, he is the son of Jjord (also known as Niord and Njord). He is also the twin brother and husband of Freyja. His magic ship, Skidbladnir, could carry all the deities, or it could be folded like a napkin and put into a pocket. Freyr is the owner of a horse named Blodughofi which can travel through flames and darkness. The dwarfs, who were ruled by Freyr, gave him a golden boar named Gullin-Bursti. Some say Freyr's name is the female form of Freyja and Frigga. *See also* Aesir; Alfar; Alfheim; Dwarves; Elves; Freyja; Frigga; Gerd.

Fria (Teutonic) *see* Frigga.

Fricco (Teutonic) *see* Freyr.

Fridthjof *Frithiof* (Icelandic) *see* Angervadil.

Frigga *Friga, Frigg, Frija, Frygga* (Norse; Teutonic)
Also known as: *Frea, Fria, Holda.*
Personalization of the civilized world. Goddess of the atmosphere or clouds. Perhaps also a goddess of love and fertility. Frigga is the principal wife of Odin and most revered of the Norse goddesses. She is the mother, by Odin, of Balder, Tyr, and Hermod. She is the sister of Jord or as some say, the daughter of Jord and Odin or Fiorgyn and Fiorvin (Ertha). She is the only goddess who has the privilege of sitting on the throne, known as Hlidskialf, next to Odin. Her own palace is known as Fensalir. She is represented wearing either snow-white or dark garments. She is tall, beautiful and stately and is shown wearing heron plumes in her headdress. Hanging from her girdle are a bunch of keys. Frigga may be the same as Holda (q.v.). *See also* Aesir; Balder; Bertha; Gladsheim; Hermod; Hlin; Jord; Loki; Odin.

Frimla (Teutonic) *see* Aesir.

Frithiof *Fridthjof* (Icelandic) *see* Angervadil.

Fro (Teutonic) *see* Freyr.

Frog Princess (Haida People, North American) *see* Dzelarhons.

Frost Mane (Teutonic) *see* Aarvak.

Frosti (Teutonic) *see* Dwarfs; Fjalar.

Frygga (Teutonic) *see* Frigga.

Fu Hsi (China) *see* Fu-Hsi.

Fu-Hsi *Fu Hsi* (China)
He is a legendary sage who instructed men in the skills of hunting and fishing and in the art of cooking. He invented writing,

made marriage rules, and discovered iron. Fu-Hsi drove wild animals out of China. He also discovered the "eight diagrams" which became the symbols of the teaching of Tao. A large water horse gave him the tablets bearing the inscriptions. Fu-Hsi is one of the Three Emperors who are half-man and half-serpent. He is usually shown with long nails worn by scholars. His sister/spouse is Nu-Kua (q.v.). *See also* Kun (B).

Fu-Hsing *Fu-Sing* (China) *see* Fu-Shen.

Fu-Jin *Fujin* (Japan)

God of the winds. Fu-jin carries a large bag of winds across his shoulder. From this bag he selects the type of wind he wants to release ranging from a gentle breeze to a violent hurricane. The intensity of the wind depends on how wide the mouth of the bag is opened. In the Shinto tradition, the first wind god born from the breath of the god Izanagi was Shinaland. Fu-jin is blue in color. In the Ryobu-Shinto tradition, the wind deity Haya-ji is depicted in a contorted shape, carrying his wind bag on his shoulder. Compare to the wind deities, Tatsuta-Hiko and Tatsuta-Hime. Compare to the whirlwind god, Haya-ji (Haya-Tsu-muji-no-Kami). Compare to the Greek winds Argestes, Boreas, Notus and Zephyr. Compare to wind deities Saramaya, Trophonius, Vayu, Pan, Mercury, Linos, Aeolus, Amphion, Aeolus and Maruts. *See also* Raiden.

Fu-Shen *Fu-Hsing, Fu Shen, Fu Sing* (China)

God of happiness. Fu-Shen is thought to have come into existence during the dynasty of Wu Ti (C.E. 502–550). Presumed to be small in stature, he began life as a mortal judge. During his career he issued an edict proclaiming that small men should have the same rights as other people. The emperor, who liked small men and who had many small men in his service, was touched by the ruling. He lifted the levy against small men. From that time, Fu-Shen was known as a god of happiness. He is often shown in the company of the god of long life and the god of salaries. His symbol is the bat.

Fu Shen (China) *see* Fu-Shen.

Fu Sing (China) *see* Fu-Shen.

Fuchi (Japan)

Also known as: *Huchi Fuchi.*

Fire deity. Fuchi is a fire-goddess who gave her name to Mount Fujiama. In some versions she was originally a goddess of the early, semi-nomadic Ainus People. It is possible that Fuji is a corruption of the Ainu goddess, Fuchi. *See also* Fuji.

Fudo (Japan) *see* Fudo-Myoo.

Fudo-Myoo *Fudo* (Buddhist; Japan)

Also known as: *Arya Achalanatha* (Sanskrit), *Dainichi-nyorai, Konkara* (Japan), *Seitaka* (Japan), *Shiva* (India), *Vairochana* (Sanskrit).

God of wisdom and righteousness. Fudo-Myoo is the most important of the Godai-Myoo (Five Great Kings) who protect the Buddhist world. An incarnation of Dainichi-nyorai, his function is to carry out the wishes of the great Buddha. Fudo-Myoo is the manifestation of Dainichi's wrath against evil and is presented in a terrifying form. He fights the opponents of Buddha and protects the believer against calamities, great dangers, fire and theft. He is fond of mortals and gives them his complete support in their endeavors. He has two attendants, Seitaka Doji, also known as Seit Ka-Doji, and Kongara-Doji. A youthful incarnation of Fudo-Myoo was Konkara. It is said that in an elderly incarnation, he was named Seitaka. The Shingon sect consider Fudo-Myoo a form of the Hindu deity Shiva. Fudo-Myoo is depicted as seated or standing on a rock with the legs of his thick, muscular, ornamented body, crossed. He is also shown standing on a precipice. He has long hair with one lock falling from the left side of his head. His eyes bulge under thick scowling eyebrows. Fangs protrude from the corners of his mouth. He holds a sword in his right hand and a cord in his left. Usually there is a flaming halo behind him that resembles a raging fire. The sword is the sword of justice which conquers greed, anger and folly. The rock he stands on indicates his firmness and suggests that as his name indicates, he is "The Immovable." The cord held by Fudo-Myoo is to bind the enemies of Buddha. Seitaka Doji holds a stick in his right hand and a vajra (thunderbolt) in his left hand. The vajra is a symbol of divine or mystic power. Kongara-Doji appears in Indian costume. A sword which is still preserved was presented to Fudo-Myoo by the Emperor Shujaku (C.E. 931–946). This sword is said to cure insanity. *See also* Dai Itoku-Myoo; Dainichi-nyorai; Godai-Myoo; Gozanze-Myoo; Gundari-Myoo; Kongo-Yasha-Myoo.

Fufluns (Etruscan)

Also known as *Puphluns.* God of growing things, including mortals, he is thought to be a version of Bacchus (q.v.).

Fugen Bosatsu (Japan) *see* Bodhisattva; Monju-Bosatsu; Samantabhadra.

Fugen En-myo (Japan) *see* Samantabhadra.

Fugi-San (Japan) *see* Fuji.

Fuji (Japan)

Also known as: *Fuchi, Fugi-San, Fukiyi, Juji-Yama.*

Sun goddess. Mountain goddess. Fire goddess. Goddess of the hearth. In one legend Fuji is a female and Mt. Haku (a male) who stands higher. When the Buddha Amida ran a pipe from the top of Haku to the top of Fuji and poured water into it, the water ran down Fuji's peak. Angry that she was not the highest mountain, Fuji beat Haku's head until it cracked. Her action created the eight peaks, making Fuji the highest mountain in Japan. Fuji was probably a volcano goddess of Mount Fujiyama. As Fuchi, she was also the guardian of home and hearth of the ancient, semi-nomadic Ainu people from the northern islands of Japan. The name Fuji is derived from Fuchi. It is said that the mountain derived its name from this sun goddess. Another deity known as the goddess of Mount Fujiyama is Sengen-Sama, the daughter of Oh-yama-tsumi (Great-Mountain-Possessor). Mount Fujiyama is considered sacred, as are other mountains in Japan. A fountain of youth is said to be hidden in the mountain. The wandering ancestor god Mi-oya-no-kami, approached the miserly god of the mountain for food and was turned away. Mi-oya-no-kami became angry and sentenced the mountain to an eternity of cold, snow and scant food supplies so that few mortals would visit her. When he visited the sacred Mount Tsukuba, he was treated hospitably and in return he insured that the mountain would have an abundance of food. Compare Fuji

www.ebook3000.com

to Achachilas. Regarding the importance of hospitality *see* Susanowo. *See also* Agni (India); Buto (B); Fuchi; Hestia (Greek); Pele (Hawaiian); Sengen; Vesta (Roman).

Fujin (Japan) *see* Fu-jin.

Fukaotsu (Japan) *see* Buddha; Vajrapani.

Fuku (Japan) *see* Fukurokujin; Shichi Fukujin.

Fuku-Roku-Ju (Japan) *see* Fukurokujin.

Fukurokujin *Fuku, Fuku-Roku-Ju, Fukurokuju, Jukurokujin* (Buddhist, Shinto; Japan, China)

God of wisdom, long life, good luck and happiness. Fukurokujin is one of the Shichi Fukujin (seven deities of luck). He is easily recognizable because the length of his head is nearly equal to the length of his body. Fukurokujin originated in China. In the Shinto tradition, he is known as the god (kami) of all trades. He is also known as the southern pole star god. It is thought that Fukurokujin was a Chinese philosopher and prophet in his earthly incarnation. He is depicted with a narrow, elongated head, a high forehead and white whiskers and is often accompanied by a tortoise, white crane or a stork; symbols of longevity. For details about the crane and tortoise, *see* Jorojin. Another symbol of longevity in Japan and China is fungus. The image of Fukurokujin is worn for good luck. *See also* Jorojin; Shichi Fukujin.

Fukurokuju (Japan) *see* Fukurokujin.

Fulgora (Roman)

Goddess of lightning.

Fulla (Norse; Teutonic)

Also known as: *Abundantia, Abundia, Habone* (Danish), *Vol, Vola, Volla.*

Goddess of the toilet of Frigga. She is the sister or friend of Frejya and Frigga's first and favorite attendant. Fulla protected Frigga from Odin's anger by having a dwarf pull down a statue erected by Odin. This indirectly caused a freeze by the ice-giants, known as Jotuns. She was responsible for carrying Frigga's valuables in a coffer. Fulla's hair is long and flowing, bound by a circlet shaped like a sheaf. *See also* Frigga; Hlin; Nanna.

Fundin (Teutonic) *see* Dwarfs.

Furies *Furiae* (Roman)

Also known as: *Dirae, Erinyes, Eumenides, Poenae.*

Goddesses of vengeance. Personified curses. Underground deities. The Furies were the names given to the Erinyes by the Romans. Three hideous winged females, Alecto, Tisiphone, and Magaera, they sprang from the blood of mutilated Ouranos. They are the daughters of Terra (earth). Avenging deities, the Furies pursued and punished the guilty, especially murderers. One has to pound on the ground to get their attention. Known in hell as the Furies and in heaven as the Dirae, they appealed to Dike, the goddess of justice, to punish the wicked. They are shown as black maidens with serpents in their hair and blood dripping from their eyes. *See also* Acheron; Eumenides; Nyx.

Futemimi-no-Kami (Japan) *see* Kushi-nada-hime.

Futsu-Nushi (Japan)

Lightning or fire deity. The Sharp-cutting Lord. A general of the Sun Goddess (Amaterasu), who appears to be a weapon deity. *See also* Ninigi; Take-mi-kazuchi.

Fylgia *Fylgja, Fylgjur* (plural) (Iceland, Norway)

This is a guardian spirit, an attendant spirit or a person's soul or double. The Fylgia can appear in dreams as a guardian and offer advice or give warnings. As the soul or double it is conceived in animal form, often a wolf bridled with snakes. If a person sees his or her Fylgia (except in dreams), it means death. When a person dies, the Fylgia passes on to another family member. The Fylgia are related to the Norns (q.v.) and the Hamingjur, who are usually invisible, feminine beings who accompany men and direct their course. *See also* Ba; Fylgukona; Norns.

Fylgjur (Iceland, Norway) *see* Fylgia.

Fylgukona *Hamingja* (Norway)

A female guardian spirit who represents a family or an individual. Similar to the Fylgia (q.v.).

Fylgya (Iceland, Norway) *see* Fylgia.

G

G (Maya)

This sun god is recognized by his filed front teeth, and the sun sign Kin. He may be the same as Kinich Ahau (q.v.).

Ga-Gaah (Iroquois People, North America)

A sacred crow, Ga-Gaah came from the sun and brought a grain of corn in his ear. This was planted by Hahgwediyu (an alternate name for Yoskeha) and became the food of mankind. *See also* Ga-Oh; Yoskeha.

Ga-Gorib (Africa) *see* Gaunab.

Ga-Oh *Gaoh* (Huron, Iroquois, Seneca People, North America)

The Great Spirit of the Winds, Ga-Oh is the giant who controls the Bear, who is the north wind, the Panther of the west wind, the Moose of the east wind, and the Fawn of the south wind. Some legends say he was a cannibal who used stones as missiles and uprooted great trees. He is possibly related to the sacred crow Ga-Gaah (q.v.). He may be the same as Gahe of the Apache People (q.v.). *See also* Adekagagwaa; Hino; Manibozho.

Ga-Tum-Dug (Sumer)
Also known as: *Ninhursag, Ninki.*
Earth goddess. Little known goddess who was worshiped at Lagash where a temple was erected to her. She corresponds to the goddess Bau. *See also* Ninhursag; Ninki.

Gabil *Gerra, Gibil* (Assyria, Sumer)
Also known as: *Girau, Nusku.*
God of fire. Giver of light and the symbol of the sacrificial flame. He is the patron of those who work with metal and he also acts as an arbiter of law and order. Gabil is the son of Anu and sister of Nin-karrak, the healing goddess. The wizard Ashipu wanted to break the evil spell of a sorcerer so he burned a peeled onion and a crushed date and invoked the name of Gabil. *See also* Nin-karrak; Nusku; Shamash; Sin.

Gabriel *Abruel, Jibril, Jiburili* (Hebrew, Arabic)
Also known as: *Asrafel, Ruh el Amin* (faithful spirit), *Serafili* (Muslim; Africa).
Archangel. He is personified as an angel who appeared to Daniel as a man. At the end of the world, Gabriel will blow his horn. *See also* Abram.

Gabzur (Babylon) *see* Arallu.

Gad (Canaan, Hebrew)
God of Fortune. Biblical reference to "prepare a table for Gad and furnish a drink for Meni (deity of numbers or lots)." A similar deity from the Syrians is called Ba'al Gad who is a master of luck. Gad is represented as a lion. *See also* Menat; Menu.

Gaea (Greek, Roman)
Also known as: *Chthon, Gaia, Ge, Gea, Geb* (Egypt), *Gi, Rhea, Tellus* (Roman), *Terra* (Roman), *Titaea.*
According to the Olympian creation myth, Gaea sprang forth from Chaos. She is the personification of the earth. A virgin mother, she gave birth to her son, Uranus, who personifies the sky. From Gaea and Uranus the birds, beasts, seas, lakes, rivers, trees, flowers and grass were created. Her first children were the semi-human giants, Briareus, also called Aegaeon, Gyges, and Cottus, each with one hundred hands. They were followed by the three one-eyed Cyclopes: Brontes, Steropes and Arges, who were builders and smiths. Hesiod wrote that from Chaos, Gaea (Earth) was born, followed by Tartarus and Eros, "the love which softens hearts." Gaea then gave birth to Uranus (Sky) to cover her and formed Ourea (Mountains) and Pontus (Sea). Uniting with her son Uranus, she then created the first race, six females and six males, called the Titans. They were named Oceanus, Ceos, Hyperion, Crius, Iapetus, Cronus, Theia, Rhea, Mnemosyne, Phoebe, Tethys, and Themis. Next were born the one-eyed giants, the Cyclopes, Brontes, Steropes and Arges, followed by the monstrous Hecatonchires, named Cottus, Briareus and Gyges. Uranus, horrified with his offspring, shut them away deep in the earth. Angry with his actions, Gaea induced her son Cronus to sever the genitals of his father, Uranus. From his blood and semen, Gaea gave birth to the Erinyes, the Meliae and Aurora. From his severed genitals, Aphrodite was born. In the Olympian tradition, Gaea created the universe, and gave birth to the first race of gods and the first race of mortals. Other children attributed to Gaea are: Cecrops, Echo, Palaechthon, Rumor, and Alcyoneus. It is said that she was also the mother of Ceto, Crius, Eurybia, Nereus, Phorcys and Thaumas, all by Oceanus. By Hephaistos, she was the mother of Erichthonius. She is the mother of Echidna and Typhoeus, possibly by Tartarus; and Ogyges, and Charybdis, and Antaeus, by Poseidon. Some think that she was also the mother of the monster Arion, the guardian of the Golden Fleece. She is identified by the Romans as Terra or Tellus (q.v.). Gaea is said to be the counterpart of the Celtic goddess Dana. Compare to the earth goddess Prithiva (India), and Geb (Egypt). *See also* Acheron; Adrastia; Aegaeon; Aello; Agraulos; Agrius (A); Aither; Alcyoneus; Antaeus; Aphrodite; Aurora; Ceos; Ceto; Chaos; Cottus; Crius; Cronus; Cybele; Cyclopes; Echo; Enceladus; Erinyes; Eros; Eumenides; Giants; Golden Fleece; Harpies; Hecate; Hecatonchires; Helius; Hephaistos; Hesperides; Hyperion; Iapetus; Meliae; Mnemosyne; Nereids; Nereus; Nox; Oceanus; Orion; Phoebe (B); Phorcys; Pontus; Poseidon; Rhea; Styx; Tartarus; Tellus; Tethys; Themis; Titans; Typhon (A); Uranus; Zeus.

Gaelestis (Roman) *see* Janus.

Gaels, The (Celtic) *see* Tuatha De Danann.

Gaga (Sumer) The messenger of Anshar.

Gagnrad (Norse; Teutonic)
Another name used by Odin.

Gahe (Apache People, North America)
Wind deities. Mountain spirits who drive away disease. They have different colors representing different directions: black (east), blue (south), white (north), yellow (west). Gahe is probably the same as Ga-oh of the Iroquois People (q.v.).

Gahongas *Gahonga* (Iroquois People, North America)
Dwarf spirits who live in water and rocks. They might be deities of rocks or stones since legends tell of them having great strength and throwing stones. The Gahongas are part of a group of dwarfs along with Gandayahs and Ohdowas. *See also* Jogaoh.

Gaia (Greek) *see* Gaea.

Gajendra (India) *see* Ganesha.

Gajomartan (Iranian, Persian) *see* Gaya Maretan.

Gaki (Japan)
Also known as: *Preta* (India).
Demons. Ghosts. The Gaki, known as hungry ghosts, congregate wherever there is any waste of food or drink. These spirits are tormented by constant hunger and thirst. They can assume any shape yet in their real form are invisible to humans. They can be detected because they sing, whistle or talk. They consume the food in flames. Although the Gaki have the power to harm, they need human sympathy and pity. The Gaki are shown as wretched, footless beings, with wide mouths. They

www.ebook3000.com

appear emaciated except for their bellies, which are swollen. The belief in footless ghosts is from the depictions of the late–eighteenth century artist, Maruyama Okyo. *See also* Kappa; Oni; Preta; Shiko-Me; Tengu.

Galan-Mai (Welsh) *see* Beltine.

Galar (Teutonic) *see* Dwarfs; Fjalar; Kvasir; Odraerir.

Galatea (A) (Greek)
A Nereid. She is the sea nymph daughter of Nereus and Doris, who fell in love with Acis. Polyphemus, a jealous admirer of Galatea, killed Acis in a fight. *See also* Acis; Amphitrite; Galatea; Nereids; Thetis.

Galatea (B) (Greek)
Pygmalion carved an ivory statue of a woman. It was so beautiful that the women-hating Pygmalion fell in love with it. The goddess of love, Aphrodite, brought the statue to life. She was named Galatea. By Pygmalion, she became the mother of Paphos.

Galeru (Australia) *see* Rainbow snake.

Galgavaldyr (Teutonic) *see* Odin.

Galli, The (Greek) *see* Corybantes; Cybele.

Gallu *Gello* (Babylonian, Sumerian, Semitic)
Also known as: *Gello* (Greek), *Gelou, Gilou.*
Demons. These seven demons love to eat flesh. They are similar to Sedu.

Gama (Africa)
Male spirits who eat the flesh of corpses. *See also* Gaunab.

Gamab (Hottentot People, Africa) *see* Gaunab.

Gamati (Africa)
Female spirits who eat the flesh of corpses. *See also* Gama; Gaunab.

Gamelios (Greek) Zeus as the god of marriage.

Gamlat (Babylonia) *see* Ishtar.

Gamr (Teutonic) *see* Garm; Hati.

Gamsu (Chaldean) Sea goddess. *See also* Zerpanitum.

Ganadevatas (Hindu; India)
Minor deities who are led by Ganesha. They are attendants of Shiva and live on Mount Kailasa. Included in this group are the Adityas, when they represent the twelve annual phases of the sun, and the Visvadevas, who attend to funeral offerings. Also included are the Vasus, who personify natural phenomena and live in Swarga, Indra's heaven. Dharma's twelve sons, the Sadhyas, belong to this group in their personification of Vedic rites and prayers, as do the Rudras or Maruts.

Ganapati (India) *see* Ganas.

Ganas (Hindu; India)
They are one of nine groups of minor deities. Demon dwarfs, they are the attendants of Shiva and Parvati. Their ruler is Ganesha, who is called Ganapati in this capacity. *See also* Ganadevatas; Ganesha.

Ganaskidi (Navaho People, North America)
They are also known as "The Humpbacks." The Ganaskidi are corn spirits or harvest deities and one of the group of deities called Yei (q.v.).

Ganda *Gandha, Gandhema* (Tibet) (Buddhist; country or origin, India)
Also known as: *Dri-chab-ma* (Tibet), *Dri-chha-ma* (She Spraying Perfume; Tibet), *Hlamos* (Tibet), *Matrikas.*
Ganda is one of the mother goddesses of Buddhism known as Matris. She appears in Bardo on the fifth day with a host of deities, including Amoghasiddhi. The Matris are also called the Matrikas, and in Tibet the Hlamos. They are usually numbered as eight, though some say there are seven, nine or sixteen Matris. They often appear in disguise, for in their true form they are so beautiful that they could arouse uncontrollable sexual desire. Ganda is depicted with two or four arms and is usually standing on one foot with the other foot lifted. This asana (position) is the dancing position, known as ardhaparyankasana. She holds a shell-vase of perfume. Her color is green, symbolizing the light of wisdom. The perfume, made from numerous herbs, represents sense-perception. Matris are not to be confused with Matrs, female Hindu spirits who dwell in cemeteries, crossroads and on mountains. The Matrs are said to practice witchcraft and are disease demons. *See also* Amoghasiddhi.

Gandalf *Gandalfr* (Teutonic) *see* Dwarfs.

Gandalfr (Teutonic) *see* Gandalf.

Gandarewa *Kundrav* (Persian)
This fiendish dragon is the "lord of the abyss" and master of the deep waters of Vourukasha, the cosmic sea, and the home of White Haoma. His epithet "golden heeled" is a reminder of the charitable side of his personality. At times he distributes the Haoma plant but generally he jealously guards it. A spy for Azhi Dahaka, his goal is to destroy the world. In a brutal battle, his skin was stripped off up to his head by the heroic Keresaspa, who then tied him up and dragged him to the seashore. Somehow, Gandarewa still managed to eat fifteen of Keresaspa's horses and attempted to abduct his family. After a battle that lasted nine days and nine nights in the cosmic ocean, Keresaspa finally overcame him. Compare Gandarewa to Gandharva (Hindu). *See also* Azhi Dahaka; Haoma; Keresaspa; Srvara.

Gandayah (Iroquois People, North America) *see* Gahongas; Jogaoh.

Gandayaks (Iroquois People, North America)
Benevolent spirits. They are dwarfs who are in charge of making vegetation fruitful. They also control fish. *See also* Dwarfs; Gahongas; Ohdowas.

Gandevi (India) *see* Gandiva.

Gandha (India) *see* Ganda.

Gandhara (India) Goddess of knowledge. *See also* Devis.

Gandhari *Gundhary* (India)
She is the daughter of Subala, spouse of Dhritarashtra and mother of Duroydhana and probably Dussasana. She and her spouse retired into the forest with Kunti (q.v.).

Gandharva-Loka (India) *see* Loka.

Gandharvas *Gandharvis* (feminine) (Vedic, Brahmanic, Hindu; India)

The first Gandharva, a Vedic deity, was the measurer of space, the sun steed and preparer and guard of soma, the elixir of the gods. In the "Brahmanas," the Gandharvas and their lovely spouses, the Apsarases, preside over fertility. They are said to be descendants of Brahma or Kasyapa and Muni. Their leader is Chitra-ratha, or according to some, Visvavasu (an enemy of Indra), and Tumburu. These spirits, half-man and half-bird, are skilled musicians and medical experts who are charged with caring for the precious soma juice. They are usually found in Swarga (Indra's heaven) frolicking with the Apsarases, although they have their own beautiful cities in the foothills of Meru Mountain. Their function is to entertain the gods with their music and minister to their needs. They haunt the air, forests and mountains. The Gandharvas usually get along well with mortals although occasionally they will fight with men. Vishnu was called upon to assist the Nagas when the Gandarvas descended to Patala and plundered their treasures. They sent the river Narmada (now known as the Nerbudda) to guide Vishnu to the underworld where he defeated the Gandarvas. Gandharvas are described as shaggy, half-bird, half-human demons, who are orgiastic, phallic, taboo-breakers. They can alter themselves into beautiful human men who have mystical power over women. Others say they were men with bird wings and legs. The *Mahabharata* refers to Gandarvas as a race of hill dwellers. Gandarva parallels the Persian Gandarewa (q.v.). *See also* Asparases; Brahma; Devas (A); Hanuman; Kasyapa; Krishna; Kuvera; Loka; Lokapalas; Meru Mountain; Nagas; Narada; Patala; Ravana; Soma; Swarga; Vishnu; Visvavasu.

Gandharvis (India) *see* Gandharvas.

Gandhema (India) *see* Ganda.

Gandiva *Gandevi* (India)

This is the celestial bow that originally belonged to Soma and later to the god of war, Arjuna. *See also* Arjuna; Soma.

Ganesha *Ganesa, Ganesh* (Hindu; India)

Also known as: *Adi-Pati* (the Ancient Lord), *Bhutesa, Chakra-Raja* (Lord of the Wheel), *Ekadanta* (One-toothed), *Gajana, Gajanana, Gajendra, Gana-Pati, Ganapati* (Chief of the Ganas or dwarf demons), *Heramba, Lambakarna* (Long-eared), *Lombodara* (hang-bellied), *Panpati, Pasu-Pati, Shasti* (his female form), *Shoden* (Japan), *Sidhi Data* (Bestower of Success), *Vinayaka* (God of Difficulties).

Ganesha is the god of wisdom and eloquence, arts and letters, the remover of obstacles, the first scribe and god of scribes and patron deity of literature. He is the god of science and skills, god of seductive eloquence, god of prosperity, and ruler of the demon dwarfs, known as the Ganas. Numerous myths surround this popular deity. In some accounts, he is the son of Parvati and Shiva and his siblings are Karttikeya and Kumara. In other renditions, he was born from a mixture of dust and Parvati's body moisture or the sacred water of the Ganges river. Many of his myths involve his head. Parvati was anxious to show her newborn to Shiva. His searing glance reduced the child's head to ashes. Brahma advised her to take the first head she could find for her baby. Another myth relates that when Ganesha blocked Shiva's path to Parvati's bath, the angry god struck off his head. To keep Parvati happy he replaced it with an elephant's head. Ganesha's head is attributed to Parvati's wrath in another legend. She was jealous of his beauty and cursed him to be fat, with an elephant head. He has only one full tusk, the other tusk was lost in a fight with Parasuraman or broken to use as an implement to write the *Mahabharata* which was dictated by the sage Vyasa. Another tale tells us that Rama went to visit Shiva and was barred entrance by Ganesha. Indignant, Rama threw an axe at him. When Ganesha realized that the weapon belonged to his father he permitted it to strike him and his tusk was broken off. The goddesses Buddhi, who personifies intelligence and wisdom, and Siddhi, who personifies success, became his spouses when he won them in a contest with his brother Karttikeya. Ganesha's blessings must be obtained for any endeavor, venture or difficult matter to be successful. He is invoked before writing, weddings, trips, or opening a new business. At births, prayers are offered that every organ may receive strength from him. He is invoked at purification rites and by mothers, twelve days after the birth of the child. All household matters are under his care, particularly kitchen items. Only Ganesha can forgive one who kills a serpent. In the Smarta tradition, five principal deities are worshiped: Shiva, Vishnu, Shakti, Surya and Ganesha. Ganesha is invoked at the beginning of ceremonies, for as the remover of obstacles, he will ensure a beneficial service. He is usually depicted as red or yellow in color, with an elephant head, one full tusk and one partial tusk, four arms, and a big stomach. He holds the lotus or sacred thread, the Ankus (elephant goad), the sacred conch shell, and the Chakra (wheel). His mount is a mouse or rat. Sometimes he holds a small tooth. Ganesha must be appeased before worshiping other gods. His appetite is gargantuan and he particularly enjoys offerings of fruits and vegetables. The deep-rooted Durva-grass is his emblem. His festival is known as Ganesha-Chaturthi. It is celebrated towards the end of August on the fourth day of the first fortnight. His image is made from various substances, such as clay, wood or paper. It is placed on a platform in the house and surrounded by lamps and mirrors decorated with dyed red rice. He is offered rice pudding. After being worshiped for ten days, the images are thrown into the water. On his feast day followers are not to look at the moon. This directive stems from a story that Ganesha was once frightened by a snake and fell from his mount, the mouse. His stomach burst open and the full moon laughed at him. As Shasti, his female form, he is shown with four arms and four breasts. *See also* Brahma; Devi; Ganas; Karttikeya; Kumara; Parvati; Rama; Shakti; Shiva; Surya; Vishnu; Vyasa.

Ganesha-Chaturthi (India)

Feast day in honor of Ganesha.

Ganga *Gung, Gunga, Mai* (Hindu; India)

Ganga, the river goddess of the Ganges and fertility goddess, is the daughter of the Himalayas or Himavat (meaning "Owner of Snow") the mountain god, and consort of the gods, including Vishnu and Shiva. Her sister is the mountain goddess Parvati. The sage Bhagiratha, son of Dilipa, through prolonged asceticism prayed for her waters to bring relief to the parched land. The gods answered his prayers. Brahma warned the deities

www.ebook3000.com

that she could not be allowed to flow freely from the celestial realm (where she circled Meru mountain three times), for her weight would cause massive floods. Shiva supported her waters before their fall onto Mount Kailasa by allowing the water to flow through his thick hair. She separated herself into seven streams and flowed onto the mountains and valleys amid great rejoicing. One of her streams became the sacred river Ganges. From earth, she followed Bhagiratha's chariot to Patala (the underworld) and hence is said to water the three worlds. Ganga married the mortal king Santanu (also spelled Shantanu) so that she could keep her promise to the Vasus to be their mother in their incarnations. They in return promised that her youngest son, Bhishma, would receive one-eighth of each of their power. In some legends, her son by Shiva is Karttikeya, though his mother is often said to be Parvati. A variation is that Karttikeya did not have a mother. His father, Rutra-Shiva, ejaculated into a fire; the fire went out and his seed spilled into the Ganges River and Karttikeya was born. In another myth, Ganga is said to be one of the Apsaras who married the mortal King Santanu. Ganga is depicted as a crowned mermaid or as a white queen. She is shown on the back of a sea monster called the makara. A name of praise for Shiva is Gangadhara (Carrying the Ganges). In this aspect, he is shown restraining the powerful river in his hair to protect the earth. Ganga is also shown as a beautiful woman with her waters flowing about her. She personifies prowess, health and abundance. Her annual festival, Dasara, is held on the tenth lunar day of the bright fortnight of Jyeshtha (May-June). All rivers are considered sacred in India, but the seven most sacred are the Ganges, Jumna, Godavari, Sarasvati Narmada, Indus and Kaveri. *See also* Apsarases; Asuras; Bhishma; Devi; Karna; Karttikeya; Kunti; Lakshmi; Makara; Meru Mountain; Parvati; Sagara; Sarasvati; Shiva; Vishnu; Yami.

Ganga-ja (India) "Born from the Ganges." *See also* Karttikeya.

Gangamma (India)
She is one of the Mutyalammo goddesses who are deities of the household. She functions as the goddess of water. *See also* Mutyalammo.

Ganges (India) *see* Ganga; Varuna.

Gangeya (India) *see* Bhishma; Ganga; Karttikeya.

Gangler (Teutonic) *see* Odin.

Gansam Deo (India) *see* Gramadeveta.

Ganumedes (Greek) *see* Ganymede.

Ganv-devata (India) *see* Gramadeveta.

Ganva-devi (India) *see* Gramadeveta.

Ganymeda (Greek)
This is another name for the goddess of eternal youth, and cup-bearer to the gods, Hebe.

Ganymede (Greek)
Also known as: *Catamitus* (Roman) *Ganumedes.*

Cup-bearer of the gods. He is the son of Tros and Callirrhoe. Ganymede, an exceptionally graceful, handsome youth was kidnapped by Zeus. He sent Ganymede on the back of an eagle to Olympus. There he became Hebe's successor as cup-bearer. Ganymede later became the constellation Aquarius. *See also* Hebe.

Ganzir (Semitic) *see* Ereshigal.

Gaoh (Iroquois People, North America) *see* Ga-oh.

Gaokerelna Tree (Persia) *see* Gaokerena.

Gaokerena Tree *Gaokerelna Tree* (Persia)
See also Angra Mainyu; Haoma; Thrita; Tree of Many Seeds; Vourukasha.

Gapn (Ugaric) *see* Baal.

Garamas (Greek)
Another name for Amphithemis. *See also* Acacallis.

Garang (Dinka People, Africa) *see* Abuk.

Garden of Eden *see* Hesperides.

Garden of Hesperides (Greek) *see* Amaltheia; Nereus.

Gari (Teutonic) *see* Geri.

Garide (Central Asia)
He is the bird who resides at the top of the tree of life. *See also* Abyrga.

Garita (India) Bird goddess; mother of Garitari.

Garitari (India) *see* Garita.

Garkain (Aborigine People, Australia)
Evil spirit. Garkain lives in the jungle. He can walk and fly. His victims are captured by enfolding them in the loose skin that attaches his arms and legs. He eats his victims raw. *See also* Namarakains.

Garm *Garme, Gamr, Garnr* (Teutonic)
This ferocious, monster wolf-dog is the watchdog of the dead and the guardian of Hel. At the apocalypse, known as Ragnarok, he will break loose and attack Tyr. During their battle, they will kill one another. *See also* Hati; Ragnarok.

Garme (Teutonic) *see* Hati; Garm.

Garmr (Teutonic) *see* Hati; Garm.

Garnr (Teutonic) *see* Hati; Garm.

Garuda (Brahman, Hindu; India; Country of origin, Babylon)
Also known as: *The Kruth* (Cambodian), *Naga-Teka* (Snake Killer), *Simurgh* (Persian), *Taraswin* (The Swift One).

In the beginning, Garuda emerged from Brahma's eggshell. Following his birth, elephants were created from the same substance. In later mythology, as king of the birds, and a demi-god, he was hatched from an egg laid by his mother Vinata, one of Daksha's numerous daughters. His father is Kasyapa, his brothers are Aruna and the Suparnas, and his sister is Sumati. At birth his glow was so beautiful that he was worshiped as an incarnation of Agni. In the *Ramayana* he appears as the grandchild of Cyena and Cyene, the hawks who carried off Soma, the elexir of the gods. Another grandmother is Tamra, one of Kasyapa's mates. In the *Mahabharata*, Vinata and Kadru, the mother of the serpents and Vinata's co-wife, fought. She was enslaved along with Garuda. The serpents promised freedom only if Garuda would bring them a cup of soma. This was not an easy task. He had to extinguish the protective ring of fire surrounding the valuable drink, break through a sharp-spoked revolving wheel, and kill the serpent guards. He succeeded, but as he flew toward the netherworld, he was pursued by the gods. Indra caught up with him and a terrific battle ensued. Garuda overcame the great god and Indra's famous vajra (thunderbolt) was damaged in the fray. Garuda flew into the serpent's territory with the ransom. Indra, again, was close behind and another battle occurred. The liquid spilled to the ground and the greedy serpents licked up enough to make themselves immortal. It is said that the strength they received from the soma caused their tongues to become forked. Indra was able to retrieve the balance of the soma and return it to its rightful place on celestial Mount Meru. In a variation of this myth, Garuda attempts to fly to the moon. He encounters numerous obstacles and is involved in a battle with the gods. The gods, realizing the strength of their opponent and wishing to maintain ownership of the moon, reach a compromise by bestowing immortality upon him and appointing him as Vishnu's personal mount. This giant bird watches the earth from his perch on a heavenly tree. Whenever dragons and serpents appear, he swoops down and devours them. Garuda may be appealed to for nullifying poison from snakebites. Generally his color is green, but can be gold. Emeralds spew forth from his spittle. He has an eagle's head, which is usually white or gold. Sometimes his face is white and he has red wings and talons. His torso and limbs are like a human male. He is also depicted as a peacock with a long tail. Vishnu and Lakshmi are shown together on Garuda's back as he wings towards the heavens. Garuda is the symbol of the soaring human spirit. It can also be interpreted that the serpents represent polluted waters which are dried up by Garuda, a solar deity representing the sun. Garuda's son Jatayu was the king of the eagles. In the plural form, Garudas are giant birds who feed upon their enemies the Nagas. They can assume human form and in India they are usually shown with small wings and a beak. *See also* Agni; Aruna; Indra; Janguli; Kaliya; Kasyapa; Krishna; Lakshmi; Mara; Nagas; Sampati; Soma; Sumati; Suparnas; Vasuki; Vishnu.

Garudi (India)
One of Shiva's secret forms as a female bird of prey.

Gashan-Ki *Gashanki* (Assyro-Babylonian) *see* Damkina; Nin-ki.

Gashanki (Assyro-Babylonia) *see* Gashan-Ki.

Gasmu (Chaldaea)
She is an ancient sea goddess who may be the daughter of Damkina and perhaps the wife of Ea. Gasmu is associated with Zerpanitum (q.v.). *See also* Damkina; Ea.

Gat Tooth (Teutonic) *see* Tanngrisni; Thor.

Gatamdug *Gula* (Assyro-Babylonia)
A mother goddess who assimilated into Gula (q.v.).

Gaumaonocon (Antilles) *see* Iocauna.

Gaumukh (India) A Yaksha. *See also* Yaksha and Yakshini.

Gauna (Africa) *see* Gaunab.

Gaunab *Gamab, Gunab* (Hottentot People, Africa)
Also known as: *Ga-Gorib, Gauna* (Hottentot), *Gawa* (Damaras), *Goub.*
God of evil. Gaunab, who lives beyond the stars, is the constant adversary of the supreme, Heitsi-Eibib. Gaunab chooses mortals who will follow him through the abyss to the stars. Males who do so are called Gamagu and females, Gamati. The Gamagu and Gamati eat the flesh of dead humans. This is why only bones are left in graves. In some renditions, Gaunab lives under a pile of stones. He entices people to throw stones at him. If they do, the stone bounces back and kills the thrower. Gaunab is also challenged by Tsui-goab. And, a surprising addition — it is said that Gaunab created the rainbow. *See also* Heitsi-Eibib; Tsui.

Gauri *Gowrie* (Hindu; India)
Also known as: *Devi, Gouri* (possibly), *Isani, Jaganmata, Kali, Lokamatri, Mahagauri, Parvati.*
Gauri, a fertility goddess known as "The Golden Lady," is an early aspect of the great mother goddess Devi. She is said by some to be the daughter of the goddess Sirsootee and granddaughter of Mahakali. In other references, she is the daughter of Sirsootee, sister of Bishen and the niece of the goddesses Mahakali and Sri and the god Brahma. Gauri may be the mother of Manasa although it is generally stated that Manasa is the daughter of the sage Kasyapa and Kadru. Gauri may be the same as the goddess of abundance, Gouri, also known as Isani, a local goddess of Oodeypoor in Rajputana, India, who is the wife of Iswara. Gauri is also the first name used for Kali or Parvati when she rides on a tiger. It is also Parvati's name before her skin became lighter. Prior to Durga's entrance as a warrior she was known as Gauri. And, the name is sometimes used as another name for Varuni, the goddess of spirituous liquor. Gauri's festival is held on the new moon day in August. At bedtime, confections are eaten to ensure that the sweet grace of Gauri will be in the soul for a year. Compare Gauri to Manasa. *See also* Ardhanariswara; Devi; Durga; Kadru; Kali; Kasyapa; Parvati; Shiva; Sri; Varuna.

Gauri-Sankar (India)
Mountain goddess of Mount Everest.

Gaut (Teutonic)
"The Creator," or the "Great," an alternate name for Odin.

Gautama *Gotama* (India) *see* Ahalya; Buddha; Maitreya; Rishi; Sakyamuni.

Gavampati (Buddhist; India)
This god of drought and wind is called upon for rain.

Gavidjeen (Celtic) *see* Cian.

Gawa (Africa) *see* Gamab; Kaang.

Gaya (India) "The Conquering." *See also* Durga.

Gaya Maretan (Zoroastrian; Persia)
Also known as: *Gajomartan* ("Human Life"), *Gayomart* (Pahlavi dialect), *Gayomort, Kayumarth.*
Passages from the *Avesta* refer to Gaya Maretan as the first to hear the thought and teachings of Ahura Mazda, and the first

www.ebook3000.com

to fashion the family of the lands. With the primitive bull, Gosh, all life was created. Gaya Maretan was Ahura Mazda's sixth creation according to the *Bundahish*. As the myth developed, Gaya Maretan was depicted as the prototype of all humans. In Iranian cosmological mythology, he was born from the sweat of Ahura Mazda's brow, and lived during the first three thousand years of creation as spirit. Ahura Mazda then made him corporeal. During his thirty years on the dark and demon-infested earth, he constantly battled the forces of evil. When the female demon, Jahi, convinced Angra Mainyu to poison him, Gaya Maretan became infected with disease and hunger. When he died, his body became brass, his limbs gold, iron and minerals. Spenta Armaiti preserved his golden sperm and forty years later Mashya and Mashoi, the first human couple, were created. In later times, Gaya Maretan, as Kayumarth, was known as the first Iranian king. His reign lasted thirty years. He was the father of Siyamek and grandfather of Hoshang. The epithet Gayomart was used in later times as the name of Gaya Maretan's heavenly counterpart. *See also* Ahura Mazda; Angra Mainyu; Hoshang; Jahi; Mashya; P'an Ku (China).

Gayatri (A) (India) *see* Sarasvati.

Gayatri (B) (India)
A sacred text of the *Vedas*. *See also* Savitri (A).

Gayomart (Persia) *see* Gaya Maretan.

Gayomort (Persia) *see* Gaya Maretan.

Gbaye-Gborun (Yoruba People, Africa) *see* Orunmila.

Gdugs-Dkar-Chan-Ma (Buddhist; India, Tibet) *see* Avalokitesvara; Sitatapatraparajita; Tara.

Ge (Fon People; Africa) *see* Gou.

Ge (Greek) *see* Gaea; Gou (Dahomey of Africa)

Ge Hinnom (Hebrew) *see* Gehenna.

Gea (Egypt) *see* Geb.

Geb (Egypt) Earth God
Also known as: *Gea, Keb, Kenken-Wer* ("The Great Cackler"), *Seb*.
The son of Shu and Tefnut, Geb became the spouse of Nut and father of Osiris, Set (Seth), Isis, and Nephthys. Geb was forcefully separated from his sister Nut by Shu. Geb followed Shu as ruler of the earth and was succeeded in turn by his son Osiris. Geb was one of the company of gods comprising the Ennead and was, according to the Pyramid Texts, one of the oldest of the deities. He is sometimes called Kenken-Wer or "the great cackler" because he laid the great egg from which the world sprang. He is generally depicted as a human with a goose on his headdress. Sometimes he is shown lying under the feet of Shu. Geb also appeared in the form of a crocodile. His gaping, dangerous mouth is symbolic of the primeval abyss. He is identified with the Greek god Cronus (q.v.). *See also* Atum; Gea; Isis.

Gebal (Greek) *see* Agrius (A).

Gebaliah (Greek) *see* Cybele.

Gefion *Gefjon, Gefjun* (Norse; Teutonic)
Also known as: *Diana* (Teutonic).
Fertility goddess. Gefion was promised as much land as she could plow in one day. To ensure that it would be a huge acreage, she married a giant and had four sons. She changed her four sons into oxen and with them, pulled part of the kingdom of King Gylfi down to the sea where it became Seeland. Gefion married Skiold who was one of Odin's sons and became the ancestor of the Danish race. It is possible that Gefion the virgin attendant of Frigg was the same as the Gefion described above. She presided over those who died unmarried. *See also* Freyja; Frigg.

Gefjon (Teutonic) *see* Freyja; Gefion.

Gefn (Teutonic) *see* Freyja.

Gegenees (Greek) The Argonauts killed these six-armed giants who lived in the mountains on the Mysian coast.

Gegeneis (Greek) "Children of the Earth" *see* Curetes.

Gehenna *Ge Hinnom* (Hebrew; possibly Egyptian origin, at least that of Dumah)
Also known as: *Jaahannam* (Arabic).
The underworld. Gehenna is sixty times as large as the world, and it would take a man 2,100 years to reach it. There are seven palaces in the place, each with 6,000 chambers, each of these having 6,000 boxes and in each box are 6,000 vessels filled with gall. The place is also said to be so deep it would take 300 years to reach the bottom of it. One legend tells of Gehenna being ruled by Dumah, a prince. He has 10,000 angels who help him judge sinners and decide their doom. A second prince, Arsiei, is in Gehenna. His job is to stop the righteous from praying for the wicked. *See also* Aahannam (Arabic); Hades (Greek); Hell; Rahabh (Hebrew); Tuat (Egypt).

Geirod *Geirrod, Geirrothr, Geruthus* (Norse; Teutonic)
Also known as: *Grimner, Grimnir.*
Some say he is the giant son of Hraudung and brother of Agnar. Others say he is the brother of the giant king Geirod who ruled Glasisvellir, a land where death does not exist. Geirod also goes under the name of Grimnir, a name used by Odin when he visited the hall of Geirod in disguise. Geirod was slain by Thor. *See also* Grimmir; Thor.

Geirrod (Teutonic) *see* Geirod.

Geirrothr (Teutonic) *see* Geirod.

Gekka-O (Japan)
God of marriage. He binds the feet of lovers with red silk thread.

Gelanor (Greek) King of Argos. *See also* Danaus.

Gelgia (Teutonic) *see* Fenrir; Gleipnir.

Gelgja (Teutonic) *see* Gleipnir.

Gello (Greek) *see* Gallu.

Gelou (Hebrew) *see* Gallu; Lilith.

Gendenwitha (Iroquois People, North America)
The Morning Star.

A mortal hunter named Sesondowah was captured by the dawn goddess but seeing a beautiful girl on earth, he changed into a bird and brought the girl back to heaven. Dawn was angry and tied him to a doorpost. He transformed the girl into a star and gave her the name, Gendenwitha, the Morning Star.

Genea (Phoenician)
Mother goddess of all mortals. *See also* Fire; Kolpia.

Genethlios (Roman) *see* Neptune; Poseidon.

Genie *Genii* (Persia) *see* Jinn.

Genius (Roman)
Also known as: *Iovialis*
God of life and being. The genius is the spirit residing in all humans and animals from birth to death. *See also* Daemon.

Genos (Phoenician) *see* Kolpia.

Gerd *Gerda, Gerdhr, Gerdr* (Scandinavian)
This beautiful giant daughter of Gymer and Aurboda is the frost goddess of the frozen earth and the goddess of light. After intense wooing, Freyr finally convinced her to marry him. They lived in the home of the gods, Asgard. *See also* Freyr.

Gere (Teutonic) *see* Geri.

Geri *Gari, Gere* (Norse; Teutonic)
Deified animal. Geri is one of the two wolves who lay at the feet of the great god Odin when he is on his throne. The other wolf is Freki.

Gerold Iarla (Irish) *see* Aine.

Gerra (Assyro-Babylonian)
An alternate spelling for Gabil, the god of fire.

Gerseme (Teutonic) *see* Freyja.

Gersimi *Gerseme* (Teutonic) *see* Freyja.

Geruthus (Teutonic) *see* Geirod.

Geryon (Greek)
King of Erythia. His parents are Chrysaor, the son of Poseidon and Medusa, and Callirrhoe, the Oceanid daughter of Oceanus and Tethys. His sister is Echidna, the half-nymph, half-snake, monster. The tenth labor of Heracles was to capture the many cattle owned by Geryon, who was killed in the process. *See also* Callirrhoe; Chrysaor; Echidna; Heracles; Oceanids; Tethys.

Geshtinnanna (Sumer) *see* Gestinanna.

Gestinanna *Geshtinnanna* (Sumer)
She is the daughter of the goddess Ninsun and the sister of the shepherd god Dumuzi. A seer, poet, scribe, and bookkeeper, she was known as "The Lady of Desolation," "The Lady of the Vine," "The Recorder of Hell," and "The Bookkeeper of Heaven." *See also* Dumuzi; Inanna; Ninsun.

Geuh Urvan (Persia)
He is an assistant to the Amesha Spenta Vohu Manah.

Gevar (Teutonic) *see* Miming.

Gewi (Bushman, Hottentot People, Africa)
Possibly a creator deity. He is the son of Cagn and brother of Cogaz. His mother is either Hyrax or Coti. *See also* Cagn.

Geyaguga (Cherokee People, North America)
Magical name of the Moon.

Ghaddar (pre–Islamic) *see* Jinn.

Ghanan (Maya People, Yucatan) *see* Yum Kaax.

Ghanta (Tibet) *see* Amrtakundali.

Ghantapani (Nepal) *see* Vajrasatwa.

Ghar-Jenti (India)
She is the house spirit of good fortune who walks around at night. Her presence can be detected by the sound of nails being pulled from wood.

Ghatotkacha (India) *see* Bhima (A); Karna; Kunti.

Ghede (Haitian)
Also known as: *Baron Cimetiere, Baron La Croix, Baron Piquant.*
God of the dead. Ghede is likely of African origin. He is associated with Baron Samedi. Children are protected by him. Ghede has healing powers. He is shown as a black man wearing a black coat, top hat and dark glasses. He carries a cane and is usually shown with a cigar or cigarette. His sign is a square cross on a low tomb. *See also* Mait' Carrefour.

Ghee (India) Sacrificial Butter. *See also* Agni.

Ghirdhima (Tibet) *see* Lu-ma.

Ghul (pre–Islamic) *see* Jin.

Gi (Greek) *see* Gaea.

Giane (Sardinia)
This woodland spinning spirit had breasts so long that she could throw them over her shoulder. Her singing attracts mortal males. When they respond, she has sex, the man dies, and she gives birth three days later.

Giant Eye, The (Eskimo) *see* Issitoq.

Giant Rabbit (Algonquin People, North America) *see* Michabo.

Giants (Greek)
The Greek giants were born when Gaea was impregnated by the blood of the castrated Uranus. The strongest were Alcyoneus and the leader of the group, Porphyrion. The others were Ephialtes, Eurytus, Clytius, Mimas, Enceladus, Pallas, Polybotes, Hippolytus, Gration, Agrius, Thoas, Aloeus, Antaeus, Anax, Hecatoncheiroi, Rhotetus, Thoon and Tityos. Many of the giants were killed during the war against the giants and the gods on Mount Olympus. Heracles and Dionysus were credited with a number of the deaths. It is possible that the Giants had snakes for feet. *See also* Alcyoneus; Antaeus; Erinyes; Eumenides; Gaea; Hecatonchires; Meliae; Themis; Uranus.

Gibal (Babylonia) *see* Gabal.

Gibil (Sumer, Assyria) *see* Gabil.

www.ebook3000.com

through the skin and packing it into the bones. In this method, you imagine that your bones are like hollow tubes, and that you breathe and suck the Chi into the bones.

Bone Breathing is practiced in a three-stage process. **Let your breathing follow a normal pace. Do not strain or hold your breath too long**.



Fig. 2.2 *Bone Breathing through the Fingers*

1. You can do this practice in the sitting position or in the Embracing the Tree posture (or any other Iron Shirt Chi Kung posture). You will use your mind and eye power to breathe in a short breath and at the same time feel suction. Suck the Chi of the atmosphere into your hands, eventually expand to the universe and breathe in a few more times. Use a combination of 'mind/eyes/heart' power (Yi), to suck the Chi from the atmosphere into your hands, while taking small sips of breath. Once you can clearly feel the increase of Chi 'pressure' in your hands, you extend the feeling throughout your arms. The whole skin surface of the arms breathes in the Chi, feeling the skin holding this pressure.
2. Inhale one more deep breath and lightly contract the arm muscles to squeeze the Chi into the bones. Hold for a while to condense the Chi into the marrow of your bones. Exhale and at the same time feel a distinct heaviness in the bones, meaning that the Chi has been condensed and packed into the bones successfully. Eventually you will use more mental power (mind/eyes/heart power) and less muscle, using soft breathing, to draw the force into the bones. Do 6 to 9 times; rest and feel the Chi that has been condensed into the bones.

Gid-Kuzo (Finno-Ugric)
Protector of cattle from wild beasts and sickness.

Gidja (Australia)
Creator. Moon god. In the beginning there was only one sex, male. Nqunung-nqunnut or Mali the Bat, the older brother of Gidja, made the first woman by castrating Yalungur the Eaglehawk. For another rendition, *see* Yalungur.

Gijigouai (Algonquin People, North America)
Messenger or sun deities. These supernatural beings are servants of Michabo. The name is both singular and plural. *See also* Michabo.

Gikuyu (Africa)
Also known as: *Kikuyu*.
First man. Founder of the race of people. God showed Gikuyu a beautiful country filled with fig trees and provided him with a mate named Moombi who was a creator deity. The two had nine daughters. God provided nine young men for these daughters. This began the Kikuyu race, named Moombi after the first woman. *See also* Kere Nyaa.

Gil (Babylonia) *see* Marduk.

Gilfaethwy (Celtic) *see* Gwydion.

Gilgamesh *Gilgamas, Gilgames, Gilgamish, Gilgamos, Gishgimmash* (Hittite); (Mesopotamia)
Also known as: *Gizdubar* (Chaldean), *Izdubar*.
A super human, one-third man, and two-thirds god, he is sometimes described as a sun hero. He is variously called an ancient Sumerian king of Uruk and son of Ninmah, or the child of a peasant and his wife who was a daughter of Sakkhoras, a Babylonian king, or the son of Ninmah or Ninsun. The basic tale of Gilgamesh involves Enkidu, Ishtar, Utanapishtim, immortality and the flood. As the son of the goddess Ninsun and the god Lugalbanda (or Kullabu), he was known as the king of Uruk sometime before 2500 B.C.E. He built the city walls of Uruk and recruited all young men. Unhappy citizens, particularly the nobles, felt that he was acting in an arrogant and tyrannical manner, rather than in the role he was created for as a shepherd to the people. They prayed to the mother goddess Aruru for assistance. She created a rival hero, Enkidu. Wild and hairy, he had to be tamed by a harlot named Shamhat. She enticed him to shave and perfume himself. Once presentable, she led him to Erech to wrestle Gilgamesh. They were of equal strength so it was decided that a fight would be fruitless. Instead they became friends. They went in search of an opponent and found Khumbaba, the giant of the pine forest. With the aid of divine assistance, they killed him. Upon his return to Uruk, Ishtar, the goddess of love, fell in love with him. She made advances but he, aware of how many of her former lovers were residing in Hades, resisted. Insulted, the goddess complained to her father, the supreme god, Anu. He sent pestilence to Uruk in the form of a bull. Although it killed hundreds, Gilgamesh and Enkidu killed it. Ishtar was furious. Enkidu dreamed that either Gilgamesh or Enkidu would have to die. Enkidu fell ill and on the 13th day died. Gilgamesh was inconsolable. He knew of a man called Utanapishtim, the only survivor of the Great Flood, who has attained immortality and resides in paradise. Gilgamesh went to seek this man for the secret of immortality. After a long, hazardous journey he reached the coast. Here he met Sifuri, who told him that Urshanabi (the Babylonian Charon, the ferryman on the Sea of Hades) was the only sailor who knew the sea. Gilgamesh instructed him to build a ship. When it was completed the sailor took Gilgamesh across the sea to the land where Utanapishtim lived. He was received graciously, and Utanapishtim told him the details of the great flood and how he was able to survive and achieve immortality. Before leaving, he gave Gilgamesh the plant of eternal youth. Gilgamesh returned to his own coast, but the plant, which grew only on the bottom of the sea, was stolen by a snake. He had lost his chance to become immortal. He did however, show his guide the walls of Uruk. In another myth, Gilgamesh is presented with the gifts of a magic drum and drumstick. Somehow his gifts disappeared into the underworld. Enkidu volunteered to retrieve them. He was cautioned by Gilgamesh to adhere to all rules in the underworld or he would be held forever. Enkidu ignored him and was seized. Gilgamesh appealed to Enlil and to Sin for assistance to rescue Enkidu but was ignored. It was Ea who instructed Nergal to make a hole in the ground. This opening allowed Enkidu's spirit to rise to the upperworld. Gilgamesh begged him for details about the underworld and was told by Enkidu that his body was full of worms and had turned to dust. This distressed Gilgamesh so, that he threw himself to the ground and wept. Gilgamesh is depicted with black, curly hair, and a beard. He wears fifty-pound armor and carries a four hundred–pound axe. His wrists are adorned with heavy gold bracelets, and he has two pet monkeys perched on his shoulders. *See also* Aruru; Enkidu; Ishtar; Khumbaba; Ninsun; Siduri.

Gilling (Norse; Teutonic)
This giant father of Suttung was murdered, as was his wife, by the drunk dwarfs Fjalar and Galar. *See also* Odraerir; Sattung.

Gilma (Babylonia) *see* Marduk.

Gilou (Hebrew) *see* Gallu; Lilith.

Gilvaethwy (Celtic) *see* Math.

Gimli *Gimle* (Teutonic)
This is the best of the good dwelling places in the afterworld. Righteous beings will be found there after the end of the world, known as Ragnarok (q.v.).

Ginnar (Teutonic) *see* Dwarfs.

Ginnunga-gap *Ginnungagap* (Teutonic)
Meaning "yawning chasm," Ginnunga-gap is the primeval abyss. In the frozen northern reaches of Ginnunga-gap, Niflheim, also known as the "Home of Fogs," the world of mist and darkness is located. Muspells-heim, the world of elemental fire, is located in the southern reaches of Ginnunga-gap. The powerful being known as Allfather resides in Ginnunga-gap. *See also* Audhumla; Elivagar; Muspells-heim; Nifl-heim; Ymir.

Ginnungagap (Teutonic) *see* Ginnunga-gap.

Gioll (Teutonic) *see* Gleipnir.

Giovava (Taino People, Antilles) *see* Cacibagiagua.

Gir (Sumer) *see* Irra.

Gira (Sumer) *see* Nergal.

Girau (Sumer, Assyria) *see* Gabil.

Girija (India) "From the Mountains" *See also* Parvati.

Girra (Sumer) *see* Irra; Nergal.

Girru (Sumer)
Girru is the god of fire, and of light, patron of civilization and messenger of the gods.

Gish Bar (Babylonia)
Sun god.

Gishnumunab (Babylonia) *see* Marduk.

Gishzida (Babylonia)
This god, along with Tammuz, intervened on behalf of Adapa, to convince the gods to grant him immortality. *See also* Adapa; Tammuz.

Gita (Tibet) *see* Lu-ma and Avalokitesvara.

Gitche *Kitshi* (Algonquian, Chippewa People, North America)
Also known as: *Gitchee Manito, Gitche Manitou, Great Hare, Kitcki Manitou, Kitshi Manito.*

High god. All-father. Great spirit. Master of Life. Chief of the Manitos (spirits). His second in command is Dzhe Manito (the good spirit). *See also* Manitou; Sedna (Eskimo).

Gitche Minito (Algonquian People, North America) *see* Gitche.

Gitchee Manitou (Algonquin People) *see* Gitche; Kitshi Manito.

Gitchy Monedo (North American Indians) *see* Gitche; Kitshi Manito.

Gizidu *Ningizzida* (Sumer) *see* Adapa; Ea.

Gjall (Teutonic)
Also known as: *Giallar Horn, Gjallar, Gjallarhorn, Ringing Horn.*

This is the horn left by Heimdall under the third root of the Yggdrasil tree. It will wait there until the apocalypse known as Ragnarok. Some say it was left in Mimir's spring. At the time of Ragnarok, Heimdall will sound the horn to awaken and summon all the gods from the nine worlds to meet in council. Gjall means resounding. *See also* Heimdall; Ragnarok.

Gjol (Teutonic) *see* Gjoll.

Gjoll *Gjol* (Teutonic) *see* Elivagar; Fenrir; Gleipnir; Niflheim; Thviti.

Glads-heim (Norse; Teutonic) *see* Gladsheim.

Gladsheim *Glads-heim* (Teutonic)
Gladsheim, located in Asgard, on the Plains of Ida, is the magnificent hall where Odin and the twelve high gods are seated. Vingolf, also located in Asgard, is the high seat of Frigga and the goddesses. Gladsheim, also Odin's zodiacal house, is one of his three palaces. His other abodes are Valaskjalf (where his throne was called Hlidskialf), and the grove Glasir. The major hall in Asgard is Valhalla, the banquet hall of the Aesir, and the brave warriors are known as the Einheriar (also Einherjar). *See also* Aesir; Asgard; Breidablik; Einheriar; Frigga; Idawold; Odin; Sovabek; Valaskjalf; Valhalla.

Glasnir (Teutonic)
The name of the grove where one of Odin's sanctuaries is located. *See also* Gladsheim.

Glauce (Greek)
This is another name for Creusa. *See also* Creusa.

Glaucus (A) (Greek)
A minor sea god, he is the son of Poseidon and Nais, or perhaps Anthedon and Alcyone. Glaucus started out his life as a fisher. He did all right until he consumed a magic herb. The herb caused him to grow a tail. Whenever his catch fell on the tail, the fish came back to life. Glaucus developed a crush on Skylla. She rejected him and was turned into a monster by Circe, who was jealous that Glaucus preferred Skylla over her. Glaucus also assisted the Argonauts (q.v.). *See also* Circe; Poseidon; Skylla.

Glaucus (B) (Greek)
He is the son of Minos and Pasiphae. His siblings are Acacallis, Androgeus, Ariadne, Catreus, Deucalion, Euryale, Lycastus, Phaedra and Xenodice. Glaucus was smothered in a honey pot. Polyeidus resuscitated him.

Glaucus (C) (Greek)
Also known as: *Glaucus of Corinth, Taraxhippos.*

He was the king of Ephyra. His parents are Sisyphus and Merope. His siblings are Halmus, Ornytion and Thersander. He married Eurymede and became the father of Bellerophon and Deliades. His horses would only eat human flesh. When he refused to allow them to mate, he infuriated Aphrodite, who saw that his horses trampled him to death during the funeral games of Pelias. His ghost is known as Taraxhippos. *See also* Aphrodite; Bellerophon; Eurymede; Merope; Sisyphus.

Glaucus (D) (Greek)
He is the son of Antenor and Theano. His siblings are Acamas, Agenor, Archelous, Coon, Demoleon, Iphidamas, Laodamas, and Polybus. His half-brother is Pedaeus.

Glaucus (E) (Greek)
The son of Hippolochus, Glaucus was the co-leader of the Lycian army at Troy with Sarpedon (q.v.). When he found out that Diomedes' grandfather and his grandfather were friends, he exchanged his armor with Diomedes. While fighting for the corpse of Achilles, Glaucus was killed by Ajax the Salaminian.

Glaucus (F) (Greek)
He is the son of the king of Messenia, Aepytus.

Glauk-Opis (Greek) *see* Athena.

Gleipnir (Norse; Teutonic)
Also known as: *Gelgia, Gelgja, Gjol.*

The third and strongest chain that holds the wolf Fenrir. Made by the dwarfs, Gleipnir consists of six elements: the sound a cat makes when it moves, a woman's beard, the roots of a mountain, the sinews of a bear, the breath of a fish, and a bird's spittle. The other chains are named Laeding and Dromi. In some myths, Fenrir is bound by Gleipnir, then attached to the

www.ebook3000.com

rock Gioll, and then fastened to the black boulder, Thviti. In some versions Gjol or Gjoll is the name of one of the rivers flowing out of Nifl-heim. *See also* Dromi; Fenrir; Laeding; Niflheim; Thviti.

Gleti (Dahomey People, Africa)
Goddess of the moon.

Glispa (Navajo Indian)
Culture heroine. One of two sisters who married Bear and Snake. They were the creators of a particular dance which the shamans use for curing ills.

Gloin (Teutonic) *see* Dwarfs.

Glooscap (Algonquin) *see* Gluskap.

Glooskap (Algonquin, Penobscot Indians) *see* Gluskap.

Glunen (Celtic)
He is the son of the Gaulish culture hero Taran, and one of the seven survivors of the battle between Bran and Matholwch. *See also* Bran.

Gluskap *Glooscap, Glooskap, Glusgahbe* (Algonquin, Penobscot Indians, North America)
Representing good, Gluskap is opposed by his twin brother, Maslum, who represents evil. They created the solar system and mortals from their mother's body. He is a shape-changer but his normal form is a rabbit. Gluskap killed Malsum who then turned into a wolf. He was also involved in physical altercations with a group of powerful magicians known as the Kewawkqu, the sorcerer Medecolin, Pamola the evil spirit of the night, and another powerful sorcerer, Wimpe. He emerged the victor in each instance. Gluskap left in his birch-bark canoe after his work was finished, but he will return someday. Also *see* Nanabozho and Nichan regarding other Algonquin creation legends. *See also* Wimpe.

Gna *Gnaa* (Teutonic)
An attendant of Frigg (Frigga) and a messenger of heaven, when she mounted the steed, Hofvarpir (aka Hofvarpnir and Hofvarpner, also called Hoof-Tosser), who ran through air and water. The horse's sire was Hamskerpir. It is said she married King Rerir and bore him a son named Volsung who became a great hero. *See also* Frigg.

Gnaa (Teutonic) *see* Gna.

Gnome *see* Dwarfs.

Gnowee (Wotjabaluk People, Australia)
This sun goddess searches for her lost son every day by climbing the sky carrying a torch.

Go (Celtic) *see* Cian.

God of All Things (Greek) *see* Chaos.

God of Hanged Men (Teutonic)
A title for Odin.

God of Ravens (Teutonic)
A title for Odin.

God with Eight Banners, The (Japan) *see* Hachiman.

Godai-Myoo *Go Dai Myo-o* (Buddhist; Japan)
Also known as: *Godaison* (Japan), *The Five Kings.*
There are five Godai-Myoo, one for each of the five great Buddhas. They are known as the Five Kings, the Five Awesome Divinities, or the Five Great Ones with the Powerful Roar. Their function is to carry out the wishes of the Buddhas. They are represented as the terrible manifestation of the Buddha. Fudo-Myoo is the most important of the Godai-Myoo (Arya Achalanatha). He is the incarnation of Dainichi Nyorai (Maha-Vairocana). The other Godai-Myoo and Buddhas are Gozanze-Myoo (Trailokya-Vijaya-Raja), the incarnation of Ashuku (Akshobhyu); Gundari-Myoo, also known as Nampo Gundari Yasha and Kanro (Kundali), the incarnation of Hosho (Ratnasambhava); Dai Itoku-Myoo (Yamantaka), the incarnation of Mida (Amida, also known as Amitabha); and Kongo-Yasha-Myoo (Vajra-Yaksha), who is the incarnation of Fuko (Amoghavajra). Godaison is the popular name for the Godai-Myoo. There are two Myoo who are not considered Godai-Myoo; they are Kujaku-Myoo and Aizen-Myoo. *See also* Dai Itoku-Myoo; Dainichi Nyorai; Fudo-Myoo; Gozanze-Myoo; Kongo-Yasha-Myoo; Trailokyavijaya.

Goddess of All Things (Greek) *see* Chaos.

Goddess of Fantasy (India) *see* Maya (B).

Goddess of Illusion (India) *see* Maya (B).

Gode (Teutonic) *see* Bertha.

Godiva, Lady (England) *see* Epona.

Goemmason *Goemmson* (Japan) *see* Dai Itoku-Myoo.

Goewin (Celtic) *see* Gwydion and Math.

Gog and Magog (Celtic)
These giants are said to have been the sole survivors after Brut succeeded in destroying the giants of Britain. Brut installed them as porters at the palace gates of London. In Biblical lore, the term is generally interpreted to mean the enemies of God.

Gogopa (Greek) *see* Athena.

Gohone (Iroquois People, North America) *see* Adekagagwaa.

Goibniu *Goibhniu* (Irish, Celtic)
Also known as: *Govannon* (British, Welsh).
Goibniu is one of the Tuatha De Danann. Goibniu, Luchtaine, the carpenter, and Credne, the bronze worker, were responsible for making the weapons which were used to defeat the Fomorians. Goibniu also made the beer for the Tuatha de Dananns (q.v.). Compare Goibniu to Vulcan (Roman), and Tvastri (Vedic). *See also* Brigit; Credne; Dia'necht; Fomorians; Hephaistos (Greek); Ilmarinen (Slavic); Tvastri (Vedic).

Gokarmo (India) *see* Shakti.

Gokuraku Jodo *Gokuraku* (Buddhist; Japan)
Also known as: *Sukhavati* (India).
This is the Japanese Buddhist heaven, situated somewhere in the west. It has a pond filled with ambrosia, lotus flowers, and trees decorated with jewels. Birds of Paradise sing, and bells hanging from the trees play beautiful music. Sometimes it is known as one of three heavenly paradises: Gokuraku, Tosotsa

Ten and Royojusen. *See also* Amida; Amitabha; Chakravala (Buddhist Universe); Sukhavati.

Gold Mane (Teutonic) *see* Gullfaxi.

Golden Apples (Greek)
These apples grow in the Garden of Hesperides. One of Heracles' labors was to collect three of the Golden Apples from the garden. *See also* Eris; Heracles; Hesperides; Peleus; Thetis.

Golden Bells (Aztec)
A name for the moon goddess, Coyolxauhqui.

Golden Bough (Greek)
Deified object. On the advice of the Cumaean Sibyl, Aeneas plucked the golden bough. He gave it as a gift to Persephone, goddess of the underworld, and as a token to Charon the ancient ferryman so that he could be ferried across the river Styx to the Underworld. The golden bough was an oak branch covered in mistletoe that grew on a tree near Cumae. The golden bough was sacred to Persephone. *See also* Aeneas; Charon; Golden Apples; Golden Fleece; Persephone; Proserpina; Styx.

Golden Bristled (Teutonic) *see* Gullin-Bursti.

Golden Comb (Teutonic) *see* Gullinkambi.

Golden Fleece (Greek)
The sacred fleece of the ram was born of Poseidon and Theophane. It could speak and fly. The hide of the Golden Ram, entrusted by Phryxus to Aeetes, was guarded by Argus, the hundred-eyed monster. It was for the purpose of obtaining this fleece that Jason embarked on the Argonautic expedition. In another myth, Zeus as a young man discovered the great ram on Mount Ida. Supposedly it was the last of a breed of rams worshipped as deities during that time. He killed the ram but, distracted by a nymph, he left the carcass. A shepherd came upon it and kept the golden pelt. Wrapped around him he became powerful enough to end draughts. He made himself king, adorned the altar with the fleece and reigned for hundreds of years. In another legend, Poseidon rescued the children of Nephele from their wicked step-mother, Io. On the back of the ram they flew to Colchis. One child, Helle, fell off the ram and drowned. That part of the sea became Hellespont. His sister arrived safely and was welcomed by Aeetes, the king of Medea. The Golden Ram became the constellation Aries. *See also* Aeetes; Argonauts; Gaea; Golden Apples; Golden Bough; Ino; Jason; Medea; Phrixus; Poseidon; Zeus.

Goldfax (Teutonic) *see* Gullfaxi.

Golgos (Greek) *see* Adonis.

Gollveig (Teutonic) *see* Gullveig.

Gondemar (Teutonic) *see* Andvari.

Gondul (Teutonic) *see* Freyja.

Gonlod (Teutonic) *see* Gunnlod.

Good Striker, The (Celtic) *see* Sucellos.

Gopa (India) Cowboys. *See also* Radha.

Gopatshah (Persia) Deified half-man, half-ox. *See also* Srishok.

Gopel (India) The Cowherd. *See also* Krishna.

Gopinath (India) Lord of the Cowherds. *See also* Krishna.

Gopis (India)
They are the cowgirls, sometimes called milkmaids, with whom Krishna had affairs, or in some variations married. The *Purana* mentions 1,600 Gopis, though traditionally they number 16,108. Radha is the most famous of the Gopis (q.v.).

Gor (Pygmies of Africa)
Thunder deity. Elephant god whose loud voice is thunder.

Goranchacha (North Andes, South America) *see* Ramiriqui.

Gordius (Greek)
Gordius tied the Gordian Knot. An oracle proclaimed that whoever untied the knot would be the ruler of Asia. Alexander the Great untied the knot and became the ruler. Gordius and Cybele are the parents of King Midas. *See also* Cybele; Midas.

Gore (Slavic)
This god of misfortune can follow mortals into the grave.

Gorge (Greek)
She is the daughter of Oeneus and Althea. *See also* Althea; Calydonian Boar Hunt.

Gorgons (Greek)
Also known as: *Gorgo, Graeae, Graiae.*
Evil deities. They are the children of Ceto and Phorcys, though some say Gaea is their mother. The most popular Gorgon and the only mortal is Medusa ("cunning one"). The other Gorgons are Eurydale ("wide roaming") and Stheno ("strong"). They are the sisters of Echidna, Ladon, Scylla and the Graiae. They are described as three hideous wenches whose heads were covered with snakes instead of hair. To look into the eyes of a Gorgon meant one would turn to stone. It is possible that the Graiae guarded the cavern where the Gorgons lived. They have brass hands, wings of gold and tongues protruding between tusks, like those of a boar. It was Athene who gave Medusa her power and Perseus who killed her. *See also* Cyclops; Graiae; Harpies; Medusa; Pegasus.

Gorgopa *Grogopa* (Greek)
Goddess of death. She is an aspect of Athena in her form as a death goddess. *See also* Athena.

Gorgophone (Greek)
Gorgophone is the daughter of Perseus and Andromeda. Her siblings are Perses, Alcaeus, Mestor, Electryon, Sthenelus and Heleius. She married Perieres of Messene and became the mother of Aphareus, Borus, Icarius, Leucippus and Tyndareus. When Perieres died she married Oebaulus and became the first widow to ever remarry. Their children were Arene, Hippocoon and Peirene. She was buried in the market place at Argos close to the grave of the head of Medusa. *See also* Andromeda; Perseus.

Gorgyra (Greek)
She is the possible wife of the river god Acheron (q.v.).

Gorias (Celtic)
The Tuatha de Danann came from four cities. When they left

www.ebook3000.com

Gorias, en route to Ireland, they brought with them the treasure known as Lugh's Lance. The other three cities are Falias, Finias, and Murias. *See also* Tuatha de Danann.

Gortys (Greek)
He is the son of Rhadamanthus and Alcmene (qq.v.).

Gosh (Persia) *see* Dervaspa.

Gosirsa (China) *see* Niu-Y'ou.

Gotama (India) *see* Buddha; Gautama.

Gotterdammerung (German) *see* Ragnarok.

Gou (Fon People, Africa)
Also known as: *Ge, Ogun.*
God of the moon. Son of Mawu and one of the triad of Gou, Mawu, and Lisa. Lisa in her feminine form is the mother of Gou. Gou may be linked with Gu who is the god who supplied weapons and cutting edges and who is a thunder god. *See also* Gu; Lisa; Ogun.

Gouri (India) *see* Gauri.

Govannan (Celtic) *see* Don.

Govannon *Gobannon* (British)
Also known as: *Goibniu* (Celtic).
Govannon is the British equivalent of the Celtic god of smiths, Goibniu (q.v.).

Govinda *Govind* (India)
Herdsman or "Giver of Enlightenment." *See also* Krishna.

Gowree (India) *see* Devi.

Gozanze-Myoo (Buddhist; Japan)
Also known as: *Trailokya-Vijaya-Raja, Trailokyavijaya.*
Gozanze-Myoo is one of the five Godai-Myoo (Five Great Kings). He is an incarnation and an aspect of Akshobhya, the Dhyani Buddha, and some say Ashuku. As a protector of the Buddhist world, Gozanze-Myoo manifests the wishes of Buddha and protects the Buddhist world from its enemies. He lives in the region of the east. Gozanze-Myoo is depicted as a fierce, grotesque deity. He has four faces, a center eye, and bristles for hair. His eight arms, two joined at breast height, hold an assortment of attributes. In his left hands he has a stick, bow and lance. In his right hands he holds a sword, arrow, and a thunderbolt. His right foot is firmly planted on Jizaiten (also known as Mahesvara) and his left foot is lightly touching the hand of Umahi (also known as Uma), the wife of Jizaiten. *See also* Akshobhya; Dai Itoku-Myoo; Fudo-myoo; Godai-Myoo; Gundari-Myoo; Kongo-Yasha-Myoo; Trailokyavijaya; Uma.

Gozu Tenno *Gozu-Tenwo* (Buddhist; Japan)
Also known as: *Buto.*
Gozu Tenno is considered a deity of foreign import to Japan. Originally, he might have been the Chinese ox-headed deity named Niu Y'ou (Niu-t'ou). During the Middle Ages, Susanowo was considered a god of the plague and because of purification rituals, he was confused with Gozu Tenno. He is depicted with the head of an ox. *See also* Buto (A); Niu-Y'ou; Susanowo.

Gozu-Tenwo (Japan) *see* Gozu Tenno.

Grace (Greek) *see* Graces.

Graces *Grace, Graeae, Gratiae* (Latin)
Also known as: *Charites.*
Good spirits who represented grace in giving, gratitude in receiving and grace in behavior. In early mythology the Graces were known as the Charites. The number of Graces varies but Hesiod indicated they were three in number, daughters of Zeus and Eurynome, or Zeus and Euphrosyne, or Zeus and Aphrodite, or Dionysus and Aphrodite, or Helius and Aegle. Though their parentage is questionable, they are generally said to be the children of Zeus and Eurynome. They were Euphrosyne (joy, festivity), Aglaea (radiant, splendor) and Thalia (the flowering, rejoicing). Homer, in the *Iliad*, adds Charis and Pasithea to the group and some say Charis was Grace herself. It is possible that Aglaea and Charis are one and the same deity. One of the Graces, possibly Aglaea or Charis, was said to be the mate of the fire god Hephaistos. They are known by the Greeks as Charites and by the Romans as Gratiae (there is a difference of opinion as to identifying the Roman Gratiae with the Graces and Charites) and are usually shown as Aphrodite's attendants, although it said that they also attended Apollo, Dionysus, Eros, and their half-sisters, the Muses. Their other half-sisters are the Horae (Hours). The people of Athens worshiped two of the Graces, Auxo ("increaser") and Hegemone ("leader"), and the Spartans, led by the founder of Sparta, king Lacedaemon, worshiped Cleta ("sound") and Phaenna ("brightness"). They were also worshiped at Boeotian Orchomenus in the form of stones that were evidently meteorites. The Graces spread happiness and harmony wherever they traveled and often provided entertainment at events on Mount Olympus. In what is known as their traditional attitude, they are three, standing naked, each with a shoulder draped over the other, the middle one facing the opposite way. They are often shown nude and dancing in a circle or partially clothed, holding hands. In ancient times, they were depicted in long tunics and crowns. The Graces are said to represent the rays of the sun. Gratiae. Compare to Eumenides. *See also* Aglaia (A); Anchises; Aphrodite; Charites; Helius; Hephaistos; Horae; Kathirat (Syria, Ugarit); Muses; Phorcys.

Gradivus (Roman)
Epithet of Mars (q.v.). *See also* Ares; Silvanus.

Graeae (Greek) *see* Graiae.

Graha (India)
They are evil male and female spirits who live in lakes. They cause eclipses of the moon and disease and are especially dangerous to children under the age of sixteen.

Grahapati *Grhapati* (Lord of the House) (India)
An aspect of Agni personifying the hearth fire. *See also* Agni.

Graiae *Graeae* (Greek)
The Graiae, Deino, Enyo and Pephredo, are the three daughters of Phorcys and Ceto. Sometimes they are found guarding the cavern of the Gorgons. They were born looking very old, ugly, and haggard. They shared one eye and one tooth between them. Their siblings are Echnidna, Ladon, Scylla and the Gorgons. *See also* Gorgons; Medusa; Perseus.

Grainme *Grainne* (Celtic)
Engaged to Finn, she fell in love with his friend Diarmait, the son of Corc. *See also* Finn.

Gram (Teutonic)
Also known as: *Balmung.*
Deified object. Mythical sword of Sigurd. *See also* Sigurd.

Gramadevata (India) *see* Gramadeveta.

Gramadeveta *Gramadevata, Ganv-devata* (pre–Aryan, Brahmanic; India)
Also known as: *Amma* (singular), *Ammanavaru* (plural; Mysore, India), *Dih, Dihwar, Ganv-devi, Gramdevati, Maramma* (Mysore), *Mariamma* (Mysore), *Thakurani* (Orissa, India).
They are guardian deities who are also known as household goddess and village deities. In some places, they are known as goddesses of smallpox or cholera. Although generally female, there are male Gramadevetas. All unusual events are attributed to their activities. As spirits of good and bad, who have various functions, they must be propitiated with offerings of rice, flowers, fruit, liquor, pigeons, goats, milk, camphor, and or incense. Hanuman is considered a Gramadeveta, as are Vishnu, Brahma, Aiyanar, Bhairon, Gansam Deo, and Mariamma. In some areas, the Gramadeveta are now considered to be avatars of Shiva and Vishnu. *See also* Bhairon; Brahma; Hanuman; Mariamma; Vishnu.

Gramanis (India) Fiends and goblins. *See also* Devas.

Gramdevati (India) *see* Gramadeveta.

Gramnnos *Gramnos, Grannos* (Gaulish, Celtic)
He is an ancient god of mineral springs. *See also* Borvo.

Gramnos (Celtic) *see* Gramnnos.

Grandfather Fire (Mexico) *see* Tatevali.

Grandmother (Maya) First woman to have sex. *See also* Ch'en.

Grandmother Growth (Mexico) *see* Takotsi Nakawe.

Grandmother of the Garudas (India) *see* Garudas; Kasyapa; Tamra.

Grandmother Toad (Huron People, North America) *see* Ketq Skwaye.

Grannos (Celtic) *see* Gramnnos.

Gratiae *Graeae, Graiae* (Greek) *see* Graiae.

Gration (Greek) *see* Giants.

Grdhra-Kuta (Japan) *see* Ryojusen.

Great Black Belt (Japan) *see* Daikoku.

Great Father (A) (Pawnee People, North America) *see* Tirawa.

Great Father (B) (Arawak People, South America) *see* Ifilici Wacinaci.

Great Hare (Native American) *see* Gitche; Michabo; Nanabozho.

Great Mother (A) (Greek) *see* Agdistis.

Great Mother (B) (Welsh) *see* Matronae; Modron.

Great Power (Pawnee People, North America) *see* Tirawa.

Great Rainbow Snake (Australia)
Creator. Some of the many names given this deity are Kunmanggur, Galeru, Ungur, Wonungur, Worombi, Wonambi, Wollunqua, Yurlunggur, Julunggul, Langal, Muit, Yero, Taipan, Mindi, Karia. He is usually shown with a large red knife.

Great Snapping Turtle (Fox People, North America) *see* Medi Kenagg.

Great Spider (Akoma, Koshairis People, North America) *see* Iatiku.

Great Spirit (Choctaw People, North America) *see* Aba.

Great Spirit of the Winds (Native North American People) *see* Ga-Oh.

Greek (Homeric)—Creation Legend *see* Oceanus; Pontus.

Greek (Olympian)—Creation Legend *see* Aegaeon; Gaea.

Greek (Orphic)—Creation Legend *see* Phanes.

Greek (Pelasgian)—Creation Legend *see* Cronus.

Green Taras (Tibet) *see* Amoghasiddhi; Arya Tara.

Grerr (Teutonic) *see* Freyja.

Grhapati (India) *see* Agni.

Grid (Teutonic)
Giantess wife of Odin. Her son, Vidar, slew Fenrir the wolf. Grid assisted Thor by lending him her magic gloves, girdle and staff to defend himself against the giant Geirod (q.v.). *See also* Fenrir; Odin.

Griffin (Scythia) *see* Gryphon.

Griffon (Scythia) *see* Gryphon.

Grihadevatas (India) *see* Devis.

Grimhild (Teutonic) *see* Sigurd.

Grimmir *Grimmr* (Norse; Teutonic), *Grimner, Grimnik*
Also known as: *Geirod, Odin.*
This is the name Odin assumed when he visited the hall of Geirod. He is generally shown with his face partially covered with a hood. *See also* Geirod; Odin.

Grimnikr (Teutonic) *see* Grimmir; Odin.

Grimnir (Teutonic) *see* Grimmir.

Grismadevi (Sumer)
Also known as: *Dbyar-Gyi-Rgyalmo* (Tibet).
Goddess of the seasons. She is red in color and shown with an animal head.

Grith (Teutonic)
She is the giant wife of Geirod, the giant, who tried to kill Thor.

Gritta (Teutonic) *see* Odin.

Gro-bdog (Buddhist; Tibet)
Also known as: *Di-do.*
Storm deities. Ten demon knife carriers.

Groa (Teutonic)
A sorceress, Groa was known for her medical skills and her abilities to use spells and incantations. When Sif was unsuc-

www.ebook3000.com

cessful in removing a stone fragment from Thor's forehead, she sent for Groa. On the verge of success, she became excited when Thor told her that she might once again see her lost child Orvandil. Her excitement caused her to forget where she had paused in her incantations. As a result, the stone remained in Thor's forehead. She is the wife of Aurvandil and mother of Svipdag. *See also* Aurvandil.

Grogopa (Greek) *see* Gorgopa.

Gromovit *Gromovnik* (Serbian)
Thunder or harvest deity. The Christians renamed him St. Iliya Gromovnik. *See also* Perun.

Gronw Pebyr (Celtic) *see* Blodeuwedd; Llew Llaw Gyffes.

Grudyen (Celtic)
He is the son of Muryel, and one of the seven survivors of the battle between Bran and Matholwch. *See also* Bran.

Grydat (Teutonic) *see* Odin.

Gryffon (Scythia) *see* Gryphon.

Gryphon *Griffin, Griffon, Gryffon* (Scythia)
Deified animal. These strong and vigilant beasts are transporters of deities. They destroy those who try to steal. They have the head of an eagle, the body of a lion and enormous wings. In ancient times they were associated with Nergal.

Gsin-rje gsed (Tibet) *see* Yama Kings; Yamantaka.

Gu *Gua* (Fon People, Africa)
He is a thunder god, and god of farming. Gu is the patron of blacksmiths. He gave the people all their tools and weapons. He is possibly the same or similar to Ge and Ogun. *See also* Gua.

Guabancex (Taino People, Haiti)
Goddess of storms, water, rain and wind. Her messengers are Coatrischie and Guantauva. Coatrischie collects water from the mountains. Some say these two are deities of darkness and light. In some versions, they have slightly different names: Coatrischie and Guatauva, who are also deities of darkness and light. One version associates her with Iermaogauacar, Apito, and Zuimaco. All are said to be mothers of Iocauna and Guamaonocon. *See also* Atabei; Iocauna.

Guabonito (Haiti; South America)
Spirit or sea nymph. She taught the medicine man Guagugiana how to use amulets of stones and gold. *See also* Orehu.

Guacarapita (Antilles, Haiti) *see* Atabei; Iella; Iocauna.

Guacas (Inca People, Peru) *see* Haukas.

Guachimines (Inca People, Peru) *see* Apocatequil; Guamansuri.

Gualicho (Patagonian People, South America)
An evil spirit.

Guamansuri (Inca People, Peru)
The first mortal, he was the father of the twins, Apocatequil and Piguero, posthumously. After seducing the sister of the Guachimines, he was murdered by them. *See also* Apocatequil.

Guamaonocon (Haiti, Taino People, Antilles)
Also known as: *Attabeira, Iocauna, Jocakuvague, Maorocon, Maorocoti, Vague, Yocahu.*
High god. "Father sky." Supreme being. His mother has five names. They are Attabeira, Mamona, Gaucarapita, Iella, and Guimazoa. According to legend the people pray to spirits called Zemes rather than directly to these deities. The Zemes are believed to be intermediaries who transmit the prayers of the people to the gods. There is a version where Guamaonocon is called by two names, Guamaonocon and Iocauna. Iocauna is sometimes referred to as a yucca spirit. *See also* Atabei; Iella; Iocauna; Zemes.

Guana (Africa) *see* Gamab.

Guantauva (Haiti) *see* Guabancex.

Guardian of the Fetus (Roman) *see* Alemona.

Guata (Teutonic) *see* Othin; Wotan.

Guatauva (Antilles) *see* Atabei; Guabancex.

Guayarakunny (Patagonian People, South America)
He is the creator of the world and the lord of the dead. Guayarakunny let men and beasts out of the underground caverns. The horns of the beasts frightened the people. They shut the caverns trapping all black cattle. Men and beasts return to the underground caverns after death.

Guaymi People, Costa Rica — Creation Legend *see* Nancomala

Gucumatz *Gukumatz* (Maya, Guatemala; Quiche People, Central America)
God of civilization. God of agriculture. A sky god, and a wind and rain deity, Gucumatz is also a god of farming and domestic life and is able to assume the shapes of many different animals. Gucumatz resembles Quetzalcoatl in many respects, and like the Aztec god, he was represented as a feathered serpent. He is primarily a Guatemalan deity. In the Mayan version, Gucumatz is one of thirteen creator deities. He is a shape changer and the son of the Sun and Moon. In some versions Gucumatz appears to be a co-creator with Huracan. In this same version three names are mentioned, Chipi-Caculha, Raxa-Caculha and Caculha Huracan. The first two may be thought of as the first men, while the third may be an aspect of Huracan. In the Quiche tradition, the gods Gucumatz, Tepeu, and Huracan created the ancestors of the Quiche people from maize. They were known as the Four Balams who were the gods of the north, south, east and west. Their names are Balam-Quitze (Smiling Tiger), Balam-Agab (Night Tiger), Iqi-Balam (Moon Tiger), and Mahucatah (Famous Name). Originally the Balams had the ability to see great distances. Nothing was hidden from them. Their creators became jealous. They blew mist over the eyes of the Balams leaving them with ordinary sight. The Quiche also had a jaguar god named Balam. *See also* Huracan; Kukulcan; Popol-Vuh; Tepeu.

Gudatrigakwitl (Wishosk People, North America)
A creator god. He first created fog, then realizing no one would be able to see his creation of men, changed the fog into all the beings on earth.

Gudrun *Grimhild, Gutrune, Krimhild* (Norse; Teutonic)
In the "Volsung Cycle," Gudrun is the daughter of Krimhild

and the mate of Siegfried. In the *Nibelungenlied*, she is known as Gutrune, the sister of Gunther (also known as Gunnar). In the third "Saga" she is known as Grimhild (or by the alternate spelling Krimhild). *See also* Sigurd.

Guecubu (Araucanian People, Chile)
An evil deity, his name means, "The Wanderer Without." *See also* Akanet.

Gueggiahora (Brazil)
Supreme being. Not worshiped as such, but said to be invisible and dwelling above the stars.

Guener (Irish) *see* Gwen.

Guesa (Chibcha People, South America)
Deified mortal. A sacrificial victim who was brought up for the sole purpose of being given to the god Bochica. He is shown as a boy with one eye, four ears and a long tail.

Guga (India)
Guga ia a serpent god sometimes shown with a human head.

Gugal (Babylonia) *see* Marduk.

Guha (India) *see* Karttikeya.

Guhkin-Banda (Sumer) The god and patron of goldsmiths.

Guhyaka (India)
Cavemen and treasure-keepers for Kuvera (q.v.).

Guimazoa (Antilles; Haiti) *see* Atabei; Iocauna; Zemes.

Guinevere *Gwynhwyvar* (British) *see* Arthur.

Gukumatz (Maya People, Yucatan) *see* Gucumatz.

Gukup Cakix (Maya People, Yucatan)
Also known as: *Vukub-Cakix.*
Evil deity. A giant. Husband of Chimalmat. Father of Zipacna and Caprakan. He pretended to be both sun and moon, but this vain, cruel, and clumsy deity was found out and punished by Hunahpu and Ixbalanque. *See also* Caprakan.

Gul-shes (Hittite) *see* Ullikummis.

Gula (Akkadian, Babylonia, Sumer)
Also known as: *Gatamdug, Gula-Bau, Ninhursag, Ninki.*
Mother or earth goddess. Goddess of vital heat. Defender of homes. Gula is a goddess who brings both illness and good health. She was believed, along with Nin-Karrak, to be the daughter of Anu. Some say she was the sister of Enlil. In some localities, Gula is said to be the wolf of Ninurta. A dog was her symbol. Under the name Mah or Belit-ili, Gula was a goddess of medicine. She is one of the brides of Samas. Gatamdug, a wise mother goddess, who was known for her ability to interpret dreams, eventually assimilated into Gula. She is shown seated and accompanied by a dog. Gula's emblem is the eight rayed orb. Compare her to Aa. She is possibly female counterpart of Damu (Tammuz). Gula is identified with the mother goddess, Mah (Belit-ili). She is sometimes identified with Ninmah, Ninki, Ninhursag, Ninurta and Aruru. *See also* Bau; Mah (B); Ninkarrak.

Gullfaxi *Goldfax* (Norse; Teutonic)
Also known as: *Gold Mane.*
Deified animal. He is the horse of the giant Hrungnir. The giant lost a race against Odin who rode the eight-legged steed, Sleipnir.

Gullin-Bursti *Gullinborst, Gullinbursti* (Norse; Teutonic)
Also known as: *Golden Bristled, Slidrugtanni.*
Magic boar. It was created by the dwarfs Brock and Sindri on direction of Loki, and given to Frey by Loki. In another version, this was the golden boar made for Loki to give to Freyr. It was made by the two dwarfs, Brokk and Eitri. *See also* Brock; Eitri; Loki; Sindri.

Gullinborst (Teutonic) *see* Gullin-Bursti.

Gullinbursti (Teutonic) *see* Gullin-Bursti.

Gullinkambi *Gullinkambe* (Norse; Teutonic)
Also known as: *Golden Comb.*
Deified bird. This cock will warn of the coming of Ragnarok. It will wake the Einherjar in Valhalla. Gullinkambi perches on the topmost branch of Yggdrasil and wakens the gods each morning.

Gulltoppr (Teutonic)
Heimdall's golden-maned horse. *See also* Heimdall.

Gullveig *Gollveig, Gulveig, Golveig-Heid, Gulveig-Hoder;* (Norse; Teutonic)
Also known as: *Angerboda, Angerbodha, Aurboda, East Wind Hag, Heid, Heidr, Ljod, Midgard, Orboda, Volva (the).*
Aspect. Evil goddess. Probably a form of Freyja. Her name means "Gold Might." One of the Vanir who was burned three times by the Aesir. She entered Asgard demanding reparation for an injury, was killed three times, yet lived. In another version she was a goddess of evil and ruler of Iarnvid. She is called the mother of the Varns. Although she is sometimes called an aspect of Freyja, some say she was an attendant of this deity. In one version she is the counterpart and ally of Loki. An evil, crafty, prophesying goddess, this giant caused misfortunes, sickness and death. She was pierced by spears, and burned in flames three times, but lives on. All but a part of her heart was destroyed. Loki found and swallowed it. Since the heart contained her evil soul, he became twice as evil. There are tales that she was the mother of werewolves, who infest the earth and murder men. Called the East Wind Hag, she is said by some to be the mother of Fenrir, Hel, Jormungandr, and the Midgard Serpent. In some versions, Jormungandr was the Midgard serpent. Another name she calls herself is Ljod. She is associated with Freyja. *See also* Aesir; Angerboda; Fenrir; Hel; Jotuns; Loki; Midgard; Vanir.

Gulsa Goddesses *Gulses Goddesses* (Hittite)
In some renditions, the Gulsa goddesses assisted the mother goddess Hannahannas in her search for Telepinus (q.v.).

Gulu (Uganda, Africa)
A possible name for Heaven. The first man, Kintu, was supposed to have come from Gulu to earth along with his brothers (not named, possibly Kaikuzi), and married a woman named Nambi. In one version Gulu is the father of Walumbe. *See also* Kaikuzi; Kintu.

Gulveig (Teutonic) *see* Gullveig.

www.ebook3000.com

Gulweig-Hoder (Teutonic) *see* Angerboda; Gullveig.

Gumshea (Assyro-Babylonian) *see* Ishtar.

Gun (Fon People, Africa)
God of iron, war, and rain. Twin of Xevioso, and eldest son of Mahu and Lisa. *See also* Vodu.

Gunab (Africa) *see* Gamab.

Gunarh (Northwest Coast, Native North Americans)
Also known as: *Killer Whale.* Deified animal. Killer whale.

Gunarhnesengyet (Tlingit People, North America)
A great hunter hero.

Gundari-Myoo (Buddhist; Japan)
Also known as: *Amrita Kundika, Amrite Kundalin, Hosho, Nampo Gundari Yasha.*
Gundari-Myoo distributes celestial nectar to poor humans. He is one of the five myoo and a manifestation of Hosho. He is usually standing on a lotus with one foot raised. He is shown with three eyes, bristly hair and red body with eight arms. *See also* Dai Itoku-Myoo; Fudo-myoo.

Gundhary (India) *see* Gandhari.

Gundlad (Teutonic) *see* Gunnlod.

Gungner (Teutonic) *see* Gungnir.

Gungnir *Gungner* (Norse; Teutonic)
Magic spear of Odin. Gungnir was given to Odin by Loki. It was manufactured by the dwarf Brock or Sindri. In another version, on the day Odin exchanged his eye for the gift of memory, he commemorated the event by breaking a branch from the Yggdrasil tree and fashioned his beloved spear, Gungnir. *See also* Loki; Mimir.

Gunnar (Teutonic) *see* Gunther.

Gunnlod *Gonlad, Gonlod, Gundlad* (Norse; Teutonic)
Goddess and guardian of the mead of poetry. She is one of the wives of Odin and the mother of Bragi, the god of poetry, and Skadi and the nine giantesses who were the mothers of Heimdall. Some say Gunnlod was the daughter of the giant Sattung. She was in charge of the three jars of inspiration called Bodn, Odrorir and Son, which Odin stole from her. *See also* Heimdall; Odin.

Gunnolth (Teutonic) *see* Odin.

Gunnthra (Teutonic) *see* Elivagar.

Gunther *Gunnar* (Teutonic) *see* Gudrun.

Gupta-Chara (India) *see* Bala-Rama.

Gur (Middle Eastern) *see* Bohu.

Guruhi (Gambia, Africa)
Evil deity. Worshiping this deity gave humans great power, but the god poisoned and tortured his opponents. He is represented as a stool on which stood an iron ball. Possibly the ball was originally a meteorite. He is similar to Famien.

Gushkinbanda (Babylon)
One of the gods created by Ea (q.v.).

Gutrune (Teutonic) *see* Gudrun.

Gwakko-Bosatsu (Japan)
Also known as: *Chandra-Prabha* (Sanskrit).
Moon deity. He is a companion of Nikko-bosatsu (an aspect of the sun). Shown as a youth, he has three knots in his long hair and is seated on a red lotus. His body is yellow and he holds a lotus-bud and a blue lotus in his left and right hands.

Gwawl (Celtic)
Deified mortal. Gwawl is a suitor of Rhiannon who was unsuccessful against his rival, Pwyll.

Gwen *Guener* (Irish)
Goddess of smiles. Sister of Jou and Sadurn. *See also* Venus.

Gwern (Celtic) *see* Bran; Branwen; Ogyrvan.

Gwidion (Celtic) *see* Gwydion.

Gwinn (Celtic; British)
Also known as: *Annwn.*
Underworld deity. One of the early Celtic gods of the underworld and ruler of the souls of slain warriors. The son of Lludd, he is the hunter of wicked souls. Since he abducted his sister Creudilad, he must now fight for her, forever. *See also* Achren; Annwn; Creudilad.

Gwri (Celtic) *see* Pryderi; Rhiannon.

Gwydion *Gwidion* (Celtic)
Gwydion, the god of civilization and arts is the son of Don the Enchanter and the brother of Gilfaethwy. A talented bard, Gwydion is also skilled in the arts, magic and battle. He gained entry into the court of King Pryderi. After mesmerizing the king with his poetry he demanded his prized pigs in payment. Pryderi refused. Gwydion tempted him with the offer of an exchange, the pigs for twelve magnificent horses and twelve purebred hounds. Pryderi accepted. The next day his acquisitions disappeared the same way they had appeared — by magic. The king had been swindled. Pryderi and his men pursued the villains, caught up with them, and a battle ensued. Gwydion killed Pryderi, and his brother Gilfaethwy raped Goewin, the virgin foot holder of their uncle, Math. Ostracized and without shelter, the brothers finally gave themselves up to Math. He turned Gwydion into various animal forms and under these guises the bard fathered numerous offspring. Their punishment lasted for three years. When released, Gwydion offered his sister, Arianrhod, as Math's new virgin foot holder, even though she wasn't a virgin. She failed the virginity test and subsequently gave birth to twin sons, Dylan and Llew. When Math found out that she was not a virgin, he threw Dylan into the sea where he became a water god. Gwydion was able to save Llew. He tricked his sister into naming him Llew Llaw Gyffes (Llew of the Skillful Hand) whom Gwydion raised as his own child. April Fool's Day originated with Gwydion as a result of the tricks he used to have his sister's "guise" removed from Llew. Llew's new name was Llew Llaw Gyffes. In earlier legends of Gwydion, his brother is Amathaon, and his mother is Anu. Amathaon, perhaps a patron of agriculture, fought with Gwydion against Arawn, the god of the underworld. He is similar to Wodan and the equivalent of Ogma (Ireland). *See also* Amathaon; Anu (A); Arianrhod; Blodeuwedd; Llew Llaw Gyffes; Math; Pryderi.

Gwyn Gohoyw (Celtic) *see* Pryderi.

Gwynhwyvar (British) *see* Arthur.

Gyane (Greek) *see* Aeolus (B).

Gyas (Greek)
He is the son of Melampus and brother of Cisseus. *See also* Melamous.

Gyges (A) (Greek)
One of the Hecatonchires. *See also* Chaos; Gaea; Hecatonchires.

Gyges (B) (Greek) A king of Lydia.

Gyhldeptis *Gyhledeptis* (Eskimo)
Also known as: *Hanging Hair.*
Princess. Vegetation spirit. She was responsible for destroying the dangerous whirlpool named Keagyihl Depguesk.

Gyhledeptis (Eskimo) *see* Gyhldeptis.

H

Ha (China) *see* Men Shen.

Ha-Mori (Japan)
God of leaves. Generally found with Ku-ku-no-chi, who is god of boles of trees. *See also* Kaya-no-hime-no-kami; Ku-ku-no-chi.

Ha-nui-o-rangi (Polynesia)
He is one of the sons of Rangi and Poko-ha-rua-te-po (qq.v.).

Ha-Sert (Egypt) *see* Aaru.

Ha-Tsiang (China) *see* Ha; Heng.

Ha Wen Neyu (Iroquois People, North America) Great Spirit.

Ha-Yama-Tsu-Mi (Japan)
God of the lower mountain slopes. *See also* O-Yama-Tsu-Mi; Sengen.

Hab'al *Habal, Hobal* (Arabia)
Possibly rain or fate deity. May have originally been called Ha-B'al (the lord) and later confused with Abel, the son of Adam. His consorts are Allat and Al-ozzah. Hab'al is said to have replaced the Arabic Khalasa. He is generally shown as a statue of red stone holding seven headless arrows in a gold right hand. The arrows were for divination purposes. He is sometimes shown as an old man with a long beard. Hab'al is said to have been destroyed by Mohammad.

Habal (Arabic) *see* Hab'al.

Habetrot (England) Goddess of spinning and healing.

Habil (Persian) *see* Abel.

Habl (Hebrew) *see* Abel.

Habone (Danish) *see* Fulla.

Hacavitz (Maya People, Yucatan) *see* Xumucane.

Hacha'kyum *Hachakyom* (Maya People, Yucatan)
God of real people. Hacha'kyum planted stars by sprinkling sand in the sky.

Hachakyom (Maya People, Yucatan) *see* Hacha'kyum.

Hachiman (Buddhist, Shinto; Japan)
Also known as: *God with Eight Banners (The), Hachiman Daibosatsu, Hachiman Taro, Yahata.*
War deity. He is a Shinto god of war, later adopted by the Buddhists. Hachiman is thought to be a deified mortal who was the Emperor Ojin, and son of the Empress Jingo. He is usually shown mounted on a horse and carrying a bow.

Hackeberg (Teutonic) *see* Odin.

Hactcin (Jicarilla Apache People, North America)
The Hactcin have always existed. They were the first beings. The Hactcin created the world, the underworld, and the sky. In another version, the Hactcin, children of the earth and sky, lived in the underworld. Their leader, Black Hactcin, created animals.

Ha'dad (Middle Eastern) *see* Hadad.

Hadad *Ha'dad, Haddad* (Phoenician, Semite, Syrian)
Also known as: *Adad, Addu, Aleyn-Baal, Baal, Martu* (Amorite), Rimmon.
Storm God. Originally, Hadad was a Syrian deity but in cuneiform text he was called Addu, who was a chief deity. Later, he was known as Rimmon, a thunder god of air and storm. He is said by some to be the son of Dagon. In one version, his mother/wife is Asherah. In another, he was said to be the father of the fate goddess Seimia. He possibly came from an ancient king who was an enemy of Solomon. The Syrians knew him as a god of lightning, rain, and fertility. The Nabataens worshiped Hadad as a thunder god. In later times he appeared in their cul-

www.ebook3000.com

3. Proceed in the same way, breathing in progressively through the bones of the forearms, upper arms, scapulae, collarbone, sternum and ribs. You may feel a different sensation as you breathe in each area; in some areas the feeling is cool, in others warm or tingling, depending on the bone structure and the quality of the marrow.
4. Inhale and exhale in the same way through the toes, feet and legs; then, in a step-by-step progression, inhale up through the calf bones, thighbones, pelvis, coccyx and sacrum, and up the spinal column to the C-7 vertebrae.
5. Finally breathe in through the arms and legs simultaneously. Combine their energy as it flows up past C-7 and up through the neck and skull. Breathe in this way for at least nine breaths. Conclude by collecting energy at the navel.

Marrow Washing

You can wash your bone marrow with earth force, heavenly force or with cosmic force. This energy helps to cleanse and rejuvenate the bone marrow.

Heavenly Force Marrow Washing with Violet Light

1. Men place the left palm on the top of the head, and cover it with the right palm. Be aware of your 'Personal Star' (star that appears in your mind's eye and is located above your crown), above. Slightly press the palms and spiral in the clockwise direction, spiralling from the front to the right ear, to the back and the left ear 9 times; rest and feel the increased Chi pressure in the crown. Do 3 sets.
2. Women place the right palm on the top of the head and cover it with the left palm. Be aware of your Personal Star above you. Press the palms lightly and spiral in a counterclockwise direction, spiralling from the front to the left ear, to the back and the right ear 9 times; rest and feel the increased Chi pressure in crown. Do 3 sets.
3. Face your palms towards Heaven and feel that you are scooping a galactic Chi ball from above. This Chi ball contains the North Star (Violet) and the Big Dipper (Red). See the dipper fill with violet/red energy. Imagine you reach out your arms to hold the dipper handle and pour the violet/red liquid over your crown. It will feel like there is a numbness descending. Your palms face down to your crown and pour the whole galaxy onto your crown. You may perceive this energy as violet amethyst and red light frequencies. Smile.

4. Guide this sensation down into your skull, deep into your brain, cervical vertebrae, sternum, thoracic vertebrae, lumbar vertebrae and down through your legs. Feel it penetrating and enlivening your bones, deep into the bone marrow, washing, cleansing, energizing. This 'liquid-like' Chi spills all the way down to your feet. Feel it connecting with the earth through the soles of your feet; be aware of the bubbling springs in the feet (the K1 points of the kidney meridian) breathing and pulsating.
5. Touch your navel with the fingers of both hands. Focus on the door of life, and let the fire activate in the Tan Tien and kidneys. Chi will rise up to the brain.

ture under the guise of Zeus. Hadad resembled Reseph in his thunder god guise. Some say he is identical with Balmarcodes. *See also* Adad (A); Aleyn-Baal; Baal; Shaushka.

Haddad (Babylon) *see* Adad; Hadad.

Hades (Greek, Egypt)
Also known as: *Ades, Aides, Ais, Aldoneus, Charun* (Etruscan), *Dis, Duzakh* (Persia), *Dzokh* (Armenia), *Orcus, Pepi* (Egypt), *Pluto* (Roman), *Pluton, Tartarus.*
God of death. Giver of fertility. King of the Underworld. Hades is the son of Cronus the Titan god of the world and time and Rhea the mother of the gods. His siblings are Demeter, Hera, Hestia, Poseidon and Zeus. As a newborn, his father swallowed Hades, but Zeus was able to rescue him. Hades, Poseidon and Zeus shared as rulers of the universe. Hades made his home in Erebus, a realm never touched by light. Later, he abducted the goddess Persephone and forced her to become his spouse. He did show some compassion when her mother Demeter was overcome by grief. He told Persephone that she could leave the underworld if she had not eaten anything while there. Unfortunately, she had eaten the seeds of a pomegranate, so Hades decided to let her leave the abode of the dead for four or six months a year. Like a robber or thief, Hades dons his helmet of darkness that allows him invisibility and takes or snatches people from life. Their souls are whisked away for a fee by the boatman Charon to the dark, gloomy realm of Hades. Upon crossing the river Styx they are greeted by the horrifying three-headed guard dog, Cerberus. There are many caves and caverns to wind through before reaching the judges who will decide the soul's fate. The judges are Minos, Rhadamanthus, Aeacus, and Triptolemus. They weigh the good and bad deeds by placing them on the scales of Themis, the blindfolded, impartial goddess of justice. If the good outweighs the bad, the spirit is allowed to move to the Elysian Fields, if the reverse, the spirit is condemned to suffer in the fires of Tartarus. Other deities who make their home in Hades are the Furies and Hecate. In the Armenian Old Testament Hades is called Dzokh which came from the Persian Duzakh (Hell). The same document uses the word *ouydn* (Aidonoeus) for the ruler of this hell. Hades is similar to the Egyptian Anubis, and Hades as Hell compares to the Egyptian Tuat. Compare Hades also to the Aztec Mictlan. Possibly the same as the Persian Santaramet. For Hades as a place of retribution, *see* Ixion, Sisyphus, and Tantalus. *See also* Aeacus; Cerberus; Charon; Cronus; Dis; Elysian Fields; Erebus; Gehenna; Hell; Minos; Persephone; Rhadamanthys; Rhea; Serapis; Styx; Tartarus; Themis.

Hadhayos (Persia) *see* Srishok.

Hadui (Iroquois People, North America)
This god of disease is a hunchback dwarf. According to legend he gave the secret of medicine, cure and the use of tobacco to Yoskeha (q.v.).

Hae-Sun (Korea) Sun goddess.

Haemon (A) (Greek)
His parents are Creon and Anioche or Eurydice. He died with his love, Antigone. *See also* Antigone; Eurydice (C).

Haemon (B) (Greek) He is the son of Thoas.

Haemus (Greek)
He is the son of Boreas, the north wind, and Oreithyia (who was raped by Boreas). He married the nymph, Rhodope. They called themselves Zeus and Hera and were subsequently turned into mountains. *See also* Boreas; Zetes.

Hafaza (Islamic)
The Hafaza are guardian angels who protect good souls after death.

Hafgan (Celtic) *see* Arawn; Pwyll.

Haftoreng (Persia) *see* Hapto-iringa.

Hag (Teutonic) *see* Jotuns.

Hagar (Hebrew) *see* Hajar (Islamic).

Hahai Wugti (Hopi People, North America)
The Spider Woman.

Hahgwehdiyu and Hahgwehdaetgah (Iroquois People, North America) *see* Taweskare and Yoskeha.

Hai (Hebrew) *see* Aai (Egypt); Ai.

Ha'iaka (Hawaii) *see* Pele.

Haidar (Persia) *see* Ali.

Haimavati (India) "Of the Himalayas." *See also* Parvati.

Haio Hwa Tha *Hayowentha, Hiawatha* (Mohawk People, North America)
God of law. Chief and Great Lawgiver.

Haitsi-Aibeb (Hottentot People, Africa) *see* Heitsi-Eibib.

Haiwa (Arabic) *see* Eve.

Hajar (Islamic) *Hagar* (Hebrew)
She is the Egyptian slave mistress or wife of Ibrahim. *See also* Zam Zam.

Hakahotu (Polynesia) *see* Fakahotu.

Hakaiki (Polynesia)
Hakaiki is one of a triad with Atea and Ono. *See also* Atea.

Hakea (Hawaii, Oceania) Goddess of the dead.

Haku (Japan) *see* Fuji.

Hala (India) The sacred ploughshare of Bala-Rama (q.v.).

Hala-Bhrit (India) *see* Bala-Rama.

Hala-Yudha (India) *see* Bala-Rama.

Halayudha (India) *see* Bala-Rama.

Haldja (Finnish) *see* Domovoj.

Halia (Greek)
Sea-woman. Halia is the daughter of Pontus, Poseidon or Uranus and Thalassa. She is the sister of the Telchines (q.v.).

Halirrhothius (A) (Greek)
He is the son of the sea god Poseidon and Euryte, the daugh-

ter of Hippodamas and wife of Porthaon. Halirrhothius raped Alcippe and was murdered by her father, Ares. Ares was the first man tried for murder. *See also* Alcippe; Ares; Hippodamas.

Halirrhothius (B) (Greek)
He is the son of Perieres and Gorgophone (q.v.).

Halitta (Arabic) *see* Alilat.

Hall of Many Seats (Teutonic) *see* Sessymir.

Hall of the Slain (Teutonic) *see* Valhalla.

Hallat (Sumer) *see* Allat.

Hallow Hills (Celtic) *see* Tuatha De Danann.

Hallows of Ireland (Celtic) *see* Manannan Mac Llyr; Tuatha De Danann.

Halmus (Greek)
The son of Sisyphus and Merope, he was the king of Boeotian Orchomenus. *See also* Chryse; Eteocles; Glaucus; Merope; Sisyphus.

Haltia (Finland)
Haltia is the name for the tutelary genius of each person. *See also* Domovoj.

Halys (Greek)
He is the river god son of Oceanus and Tethys. He courted Sinope, but was unsuccessful. *See also* Rivers; Sinope.

Hamadrades (Greek) *see* Hamadryads.

Hamadryad (Greek) *see* Hamadryads.

Hamadryads *Hamadryad, Hamadryades* (Greek)
Also known as: *Dryades, Dryads.*
Hamadryads were originally spirits of oak trees and later along with dryads became spirits of trees in general. Unlike the dryad, the life of the hamadryad lives in the tree and dies with the tree. The nymphs of fruit trees are known as maliades. Hamadryads are usually depicted as half-woman, half-tree. For other classifications of nymphs, *see* Nymphs. *See also* Dryads.

Hambaris *Hambarus* (Armenian but probably originally from Persia)
Also known as: *Jushkapariks, Pais, Vushkapariks.*
A type of Chimaera or spirit. They appear as mortal men who live and die, although they assume different forms, including the feminine. The Hambaris take up residence in deserted houses. They are mentioned in the Armenian version of the Christian Bible along with the Jushkapariks and Devs. In one version the Jushkaparik or Vushkaparik is similar to the Pairika, who was a female Dev (a Persian concept). The Hambaris sometimes appear as half-animal. *See* Chimaera; Devs.

Hambarus (Armenian) *see* Hambaris.

Hamedicu (Huron People, North America) High God.

Hamestagan *Hamistakan* (Persia)
This is an intermediate place between heaven and hell. Souls who have been judged to have performed an equal amount of good and bad during life wait here until the restoration of the world. The only punishment in Hamestagan is suffering from being hot or cold. *See also* Chinvat Bridge.

Hamhit (Egypt) *see* Poseidon.

Hamingja *Haminja* (Teutonic)
Goddess of fortune. She also acts as a guardian spirit. Hamingja stays with the mortal she chooses for life. Hamingja is particularly lucky for a child born with a caul (piece of membrane that surrounds a fetus and sometimes covers its head at birth). She is possibly one of the Lars. *See also* Fylgukona.

Haminja (Norway) *see* Hamingja.

Hammon (Egypt) *see* Amen.

Hammurabi *Khammurabi* (Babylonian)
Also known as: *Amraphel.*
Deified mortal. He is an ancient king who was said to have founded Babylon. He claimed to have been created by Dagon. *See also* Dagon; Marduk.

Hamsa (India) *see* Hansa.

Hamsapadika *Hamsavati* (India)
First wife of Dushyanta. *See also* Bharta (B).

Han-chung Li (China) *see* Arhats.

Han Chung-Li (China)
Also known as: *Chung-Li.*
One of the Eight Immortals. What little is known about him is that he was the master of Lu Tung-Pin and possibly Chang Kuo-lao. He is shown as a careless, corpulent old man. Han Chung-Li is dressed in a great mantle and he waves a feather fan. He is associated with Han Hsiang-Tzu. *See also* Arhats; Chung-Li-Ch'uan; Eight Immortals; Lu Tung-pin.

Han Hsaing-tzu (China) *see* Ho-hsien-ku.

Han Hsiang-Tzu *Han Siang-Tsi* (China)
One of the Eight Immortals (Pa Kung). He is the nephew of the great poet, Han Yu. The uncle indicated that his nephew had magical power, so he was possibly a god of magicians. He is shown as a boy with his hair tied in two small knots on either side of his head, carrying either a bouquet of flowers or a basket of peaches. He is associated with Lu Tung-Pin and Han Chung-Li. *See also* Eight Immortals.

Han Siang-Tsi (China) *see* Han-Hsiang-Tzu.

Hanan Cuzco (Inca People, Peru) *see* Tahuantin Suyu Kapac.

Hanata (Middle Eastern)
Ishtar as a warrior (q.v.). *See also* Anat.

Hanghepi Wi (Dakota People, North America)
Moon of the Night.

Hanhau (Maya People, Yucatan)
Also known as: *Ahpuch, Yum Cimil.*
Lord of death. He is the ruler of the cold underworld, Mitnal. *See also* Ahpuch; Mictlan; Mitnal.

Hani-Yasu-No-Kami (Japan) Goddess of clay and earth. *See also* Taki-Tsu-Hiko.

www.ebook3000.com

Haniyama-Himi (Japan) *see* Haniyasu-Bime-No-Kami.

Haniyasu-Bime-No-Kami (Japan)
Also known as: *Haniyama-Himi.*

Goddess of clay. She is one of the daughters of Izanami and the sister/wife of Pani-yasu-biko-no-kami. Haniyasu was created from Izanami's excrement. Other deities who came from the same source were Pani-yasu-biko-no-kami and Pani-yasu-bime-no-kami. She is probably the same as Toyo-uke-hime-no-himi (q.v.).

Haniyasu-Hime-No-Kami (Japan) *see* Izanagi.

Hannahannas (Hittite)
This mother goddess is associated with Telepinus and the Gulsa goddesses (qq.v.).

Hanpa (Sumer)
God of demons. Father of Pazuzu and lord of all demons. *See also* Pazuzu.

Hansa *Hamsa* (Hindu; India)
Originally a sacred goose, later a swan, Hansa became Brahma's mount. Hansa was sent by Shiva and Vishnu to awaken him to creative work. The ambrosia-filled gold or silver eggs laid by Hansa represent the sun and moon. Some say that it was Shiva in the form of Hansa who awakened Brahma. *See also* Brahma; Shiva; Vishnu.

Hanuman *Huniman, Hunooman* (Hindu; India)
Hanuman the flying monkey god is a healer, pharmacologist, grammarian, poet, warrior and builder. He is an extremely virile deity although he is completely chaste. He plays a prominent role in the *Ramayana.* Hanuman is the son of the wind god Vayu and the monkey queen, Angara. Dasaratha, Rama's father, held a ceremony to ensure that he would be granted sons. Each of his three wives received a cake. When Kaikeyi, the youngest wife, received her cake last she became highly agitated. Out of nowhere, a kite appeared and whisked her cake away. Angara, an Apsarases cursed to live as a monkey, who was the mate of the monster Kesari, was in the forest praying for a son. The kite found Vayu, who gave the cake to Angara. Suddenly, Shiva appeared and instructed her to eat the sweet. From the dessert, Hanuman was created to assist Vishnu in his avatar as Rama. Born with a ravenous appetite, his mother could not satisfy him. The sun appeared to the baby monkey like a piece of fruit. When he leapt after it, the sun in its chariot kept ahead of him. Before he knew it, Hanuman found himself in Indra's celestial territory. The great god whacked him with his thunderbolt and Hanuman fell to earth. Indra's action infuriated Vayu and he entered the deities' intestines and gave them all upset stomachs. To gain relief, Indra apologized to Vayu and then made Hanuman immortal. A loyal and faithful servant to Rama, he became the general in the army of the monkey king Sugriva, who attacked Lanka (Ceylon). In this capacity, he was the supervisor who oversaw the monkeys and bears as they built Rama's bridge from India to Sri Lanka. He killed Kalanemi and fought many battles against the Gandharvas and Rakshasas. Renowned for his intellect, his knowledge of homeopathic medicines was used to restore the wounded to health. When the king of the demons, Ravana, abducted Rama's mate, Sita, Hanuman assisted in her rescue. In size, he can appear as a giant, or as small as a thumb. He is worshiped by women who want children and by wrestlers. Eternally youthful, Hanuman is sometimes red or sometimes gold or yellow with a red face, a booming voice and an endless tail. In Nepal his images are usually covered with vermilion mixed with mustard oil and he is often dressed in a red cloth with a red or golden umbrella over his head. The tale of Rama and Hanuman is comparable to the story of Indra and the ape Vrishakapi. *See also* Angara; Apsarases; Bhima (A); Bhishma; Gandharvas; Gramadeveta; Indra; Jambavan; Kaliya (an incarnation of Kalanemi); Rakshasas; Rama; Ravana; Sugriva.

Haokah (Sioux People, North America)
Two-horned, meteor-throwing thunder god. His expression depicts half-cheer, half-grief. Haokah used the wind to beat the thunder drum. He cried when happy and laughed when sad. He also felt heat as cold and cold as heat.

Haoma *Homa* (Indo-Iranian)
Also known as: *Ephedra, Gaokerena, Sarcostemmaacidum, Soma, White Haoma, White Hom.*

This sacred plant of life when pressed yields a powerful stimulant said to give strength to men and gods. It was brought to the sacred mountain, Hara Berezaiti, by an eagle. In its natural state Vohu Manah gave it healing qualities. The first four men who pressed the sour milky juice of the haoma plant each received the boon of a great son: Vivanghvant had Yima, Athwya had Thraetaona, Thrita had Keresaspa and Pourushas had Zoroaster. In its supra-terrestrial form it is called White Haoma, also known as Gaokerena, and has within itself the seeds of all plant life. Haoma is known as the purifier of the Place of the Sacred Fire. Haoma has hallucinatory properties and is known to have inspired warriors and poets. It bestows religious insight, and gives husbands and children to women. It imparts immortality and can renovate the universe. Haoma is used in a lengthy ritual as part of the *Yasna* (sacred book) sacrifice. Incantations are used during the ritual to drive away evil and prepare for the coming of good. Though the forces of evil attempt to destroy the tree by forming a lizard, it is protected by ten *kar* (fish) who never stop swimming around it. Deified, Haoma is the son of Ahura Mazda (q.v.). Compare Hoama to Soma (Vedic), the Amrita (Hindu), Ambrosia (Greek), and Yggdrasil (Teutonic). *See also* Gandarewa; Thrita; Tree of Many Seeds; Vohu Manah; Yazatas; Yima.

Haoshyangha and Tahmouras (Persian) *see* Hushang.

Hap (A) (Egypt) Another name for Apis (q.v.).

Hap (B) (Egypt)
A variant spelling for Hapi, the god of the Nile.

Hapi *Hap* (Egypt)
Hap, the god of the Nile, lived under the rocks in a cave, guarded by snakes, near the First Cataract at Aswan. He is shown as a fat man (a sign of prosperity) with the breasts of a woman (some say one pendant breast is shown), which indicate his powers of fertility. Hap holds two plants, the papyrus and the lotus, or two vases, from which he pours water. He is also depicted carrying a tray of food. *See also* Tchabu.

Hapi-Ankh (Egypt) *see* Apis (A).

Hapi-Asar (Egypt) *see* Serapis.

Hapikern (Maya)
Hapikern is the evil serpent god who is the constant opponent of Nohochacyum, the creator (q.v.).

Hapinunu (Aymara, Quechua People, South America)
Flying female night spirits who catch people with their long pendulant breasts.

Hapto-iringa *Haftoreng, Haptok Ring* (Zoroastrianism; Persia)
Ursa Major. Hapto-iringa, the Great Bear, is chieftain of the north quarter of the sky. *See also* Aktar (The); Tishtrya; Yazatas.

Haptok Ring (Persia) *see* Hapto-iringa.

Hapy (A) (Egypt)
Hapy is one of the four sons and is shown with either a dog's head or an ape's head. His function was as a funerary deity in charge of protecting the small intestines (some say the lungs). The brothers were depicted on the urns used to store the organs of mummies. The other three brothers are Amset, Tuamutef, and Qebhsneuf. Associated with the four gods are the goddesses Nephthys, Neith, Isis, and Serquet.

Hapy (B) (Egypt) *see* Hapi.

Hapy-Wet (Egypt)
River god. God of the Nile in Heaven. When united with the sun god, Ra, Hapy-Wet is a form of the god Khnemu.

Har (A) (Teutonic)
"The High One," an alternate name for Odin.

Har (B) (Teutonic) One of the Dwarfs (q.v.).

Har (C) (Egypt) *see* Horus.

Har-End-Yotef (Egypt) *see* Horus.

Har-Pa-Neb-Taui (Egypt) *see* Horus.

Har-Sopdu (Egypt) *see* Sopdu.

Hara (Vedic; India)
"Universe Destroyer." This is another name for Rudra or Shiva (qq.v.). Harihara is the name for the deity formed by the combination of Shiva and Vishnu (qq.v.). *See also* Harihara.

Hara Berezaiti (Indo-Iranian)
This is a sacred mountain in the center of the earth. Roughly translated it means "Peak of the Law." *See also* Haoma.

Hara Gauri (Nepal) *see* Ardhanariswara.

Haraiti, Mount (Persian) *see* Hariati.

Harakhtes (Egypt)
Also known as: *Harakhte, Herakhty.*
The name is the Greek rendering, and means "Horus of the Horizon." Harakhtes represents the sun on its daily course. In time, Harakhtes became so closely associated with Ra that their characteristics and powers were inseparable, and Ra was known as Ra Harakhte or Ra Horaete. Harakhtes is depicted as a falcon. *See also* Horus; Khepri.

Harakhty (Egypt) *see* Ra-Harakhte.

Harates (Greek) *see* Aeneas.

Harbard (Teutonic)
This is the name Odin used while in disguise when he crossed the waters in a ferry. During the crossing, Harbard and Thor both bragged of their exploits. *See also* Odin; Thor.

Harendotes (Greek, Egypt)
Also known as: *Har-End-Yotef, Hartomes, Horus.*
Aspect of Horus. The name the Greeks gave Horus after he avenged his father, Osiris, by taking up arms against Set. *See also* Hartomes; Horus.

Hari (India) *see* Vishnu.

Hari-Hara (India) *see* Hara.

Hariati, Mount *Haraiti, Mount* (Persian, Iranian)
The site of the home of Ahura Mazda, which is situated on the highest peak. The home has one thousand pillars and is lit in and out by stars. Ahura Mazda is carried in a chariot drawn by four white horses with golden feet when he leaves the premises. *See also* Ahura Mazda; Alburz (Mount); Chinvat Bridge; Sraosha.

Harihara (Hindu; India)
Harihara represents the great gods Vishnu and Shiva as one. Vishnu appeared as a beautiful woman named Mohini. Shiva took one look at her and fell in love. Upon embracing her, he merged as one with her. At that moment, Vishnu assumed his "normal" form. In other interpretations, said to have developed in the ninth century A.D., Harihara has the combined attributes of Vishnu and Shiva. Shiva is the right side of the body, and Vishnu the left. The merging of the two great gods resulted from an attempt to reconcile the differences of the feudal lords who worshipped Shiva and Devi, and the followers of Krishna as the incarnation of Vishnu. The latter devotees were the smaller landowners. *See also* Shiva; Vishnu.

Harinagamesi *Harinaigameshin* (India)
A Brahmanic deer-headed fertility deity. *See also* Mahavira.

Harinaigameshin (India) *see* Harinagamesi.

Harini (India) *see* Apsarases.

Haripriya (India) *see* Lakshmi.

Harita (India) Divine Horses. *See also* Indra.

Hariti
Also known as: *Kishibojin* (Japan), *Men Brayut* (Bali), *Nanda* (Buddhist; India).
The goddess of smallpox and fecundity, Hariti, an ogress, is the mother of the Yakshas. Her name means "one who steals." She is the mate of Panchika and she either gave birth to or devoured five hundred demon children. In some accounts, she had five hundred healthy sons. Kuvera is also said to be her mate. She fed on human flesh and carried away a child daily. One of her sons, Pingala, was hidden by Buddha to teach her a lesson. This act made her realize the suffering that she had caused others and she was converted by Buddha. Her name was changed to Nanda, meaning "joy," and she then became the pro-

www.ebook3000.com

tector of all children. She is shown seated, with unkempt hair, and a child or cornucopia in her hand. *See also* Buddha; Kishimojin (Japan); Kuan Yin (China); Sitala; Yaksha and Yakshini.

Harits, The (India) Indra's Horses. *See also* Indra.

Harlot, The (Hebrew) *see* Lilith.

Harmachis (Egypt) *see* Horus; Ra-Harakhte; Sphinx.

Harmakis (Egypt) *see* Ra-Harakhte; Sphinx.

Harmonia (A) (Greek)
Also known as: *Hermione, Hermoine.*
Harmonia is the daughter of Ares and Aphrodite. In some versions of this myth she is said to be the daughter of Zeus and Electra, or a daughter of Atlas. As the offspring of Ares and Aphrodite, her siblings are Phobos, the god of panic; Pallor, the god of terror; Deimos, sometimes known as the god of dread; Enyo, goddess of war; Eros, the god of love; and Anteros, the god of passion. Harmonia married the sun hero Cadmus. Their children are Polydorus; Agave, who murdered her husband and went insane; Autonoe, who was also driven insane for torturing Semele; Ino, who murdered her children; and Semele, who died when Zeus revealed himself to her in his ethereal glory. When Harmonia and Cadmus were married the gods attended their wedding. The jealous fire god and smith, Hephaistos, who was the husband of Aphrodite, created a necklace and a veil or a robe as a wedding gift for Harmonia. The necklace was said to bring disaster upon all who wore it. It did. Their daughters endured horrendous tragedies. Finally Harmonia and her brilliant husband Cadmus were changed into snakes, or some say lions, by Ares and retired to the tranquil Elysian Fields, also known as the Islands of the Blessed. As snakes, Harmonia and Cadmus were depicted as black with blue spots. Harmonia is not to be confused with Harmonia, daughter of Menelaus and Helen. *See also* Anteros; Aphrodite; Ares; Cadmus; Hephaistos; Semele.

Harmonia (B) (Greek) *see* Helen; Semele.

Harmothoe *Harmathoe* (Greek)
Harmothoe and her husband, Panareus, were killed by the great god Zeus. She is the mother of Aedon, Cleothera and Merope. *See also* Aedon; Merope.

Haroeris (Egypt)
Also known as: *Hor Merti, Horkhenti Irti.*
A name by which Horus was called, the Greek form of Har Wer, and Egyptian name meaning "Horus the Elder" or "the Great."

Harops (Egypt) *see* Harpies.

Harpakhrad (Egypt)
An alternate name for Horus (q.v.). *See also* Banebdedet; Harpokrates.

Harpies *Harpiae, Harpy* (Greek)
Also known as: *The Hounds of Zeus, The Snatchers.*
Storm goddesses. Homer only named one Harpie, Podarge (also known as Celaeno), meaning "blackness," and Hesiod wrote of two, Kalaino, (also known as Aello, Aellopuus), meaning "howler," and Ocypetes, meaning "rapid." Their parents are Thaumas and the Oceanid Electra. In other myths their parents are said to be Poseidon and Gaea or Typhon, god of the storm winds and the sea monster Echida. As the daughters of Thaumas and Electra, their sister is Iris, the messenger of the gods. Podarge, impregnated by the West Wind, who is known as Zephyrus, or some say the North Wind, Boreas, gave birth to Achilles' famous horses, Xanthus and Balius. The Harpies earned their name "The Snatchers" when it was said that Hades had them bring living beings to him who were unwilling to die. It was also believed that the Harpies and other female bird-like creatures were ghosts who might snatch away mortals at whim. They also had a reputation for devouring corpses. Under the direction of the great Zeus they earned the name "The Hounds of Zeus" by "hounding" the ancient, blind soothsayer, king Phineus of Salmydessus, in Thrace. Zeus' problem with him was that he insisted upon revealing the future to mortals. Every time Phineus would sit down to eat, the Harpies would swoop down and steal his food, leaving excrement on the plate and a terrible stench behind as they flew off. Near death by starvation or suicide, the poor man was rescued by the Argonauts Zetes and Calais, sons of the North Wind, Boreas, and brothers of Cleopatra. In some legends, the Harpies are killed by the men and in others it is said they bargained with Iris or Hermes, who agreed to allow the Harpies to live if they would leave Phineus alone. The Harpies then retired to their cave on Mount Dicte in Crete. They are sometimes shown as vultures, or depicted as bird-like creatures with female heads, long claws and wings. The Harpies are similar to the Egyptian evil winds called the Harops which bring flies and locusts. They are also similar to Greek Cataclothes who were spinners of fate. *See also* Phineus for more details of his life. To compare to wind deities *see* Aegeon; Aello; Aeolus; Boreas; Eurus; Notus; Zephyrus; Zetes. *See also* Chimaera; Gorgons; Keres; Oceanids.

Harpina (Greek)
She is possibly the mother of Oenomaus by Alxion or Ares. *See also* Ares; Oenamnaus.

Harpokrates (Greek)
Also known as: *Harpakhrad, Heru-P-Khart, Heru-Pa-Khret.*
A name given to the child Horus by the Greeks, who looked upon him as the god of silence since he was depicted with his finger to his mouth. Generally shown nude with a sidelock of youth and the Double Crown. One hand touches his lips. Sometimes shown as a child, or a baby on his mother's knee. *See also* Horus.

Harpy (Greek) *see* Harpies.

Harpyiae (Greek) *see* Harpies.

Harsaphes *Arsaphes* (Greek)
Also known as: *Hershef* (Egypt).
A god of fertility and water, he was portrayed as ram-headed, he is the Greek form of the Egyptian Hershef. The chief center of his worship was at Heracleopolis Magna (The Great City of Heracles). He is identified with the Greek Hershef, the predynastic Egyptian Amon, and the Greek Heracles. *See also* Hershef.

Harsiese (Greek) *see* Horus.

Harsiesis (Greek)
Also known as: *Hor-Sa-Iset* (Egypt).
A Greek epithet of Horus, called Hor-sa-iset by the Egyptians, meaning "Horus, son of Isis," the infant who avenged his father, Osiris. He was conceived after his mother, Isis, had magically had intercourse with the dead body of Osiris. He is shown as hawk-headed, carrying instruments of death.

Hartomes (Egypt)
An epithet of Horus, meaning the "Lancer." He was depicted in bas-reliefs in the sanctuary at Edfu using his lance against his enemies, the armies of Set. *See also* Harendotes; Horus.

Haru-Yama-no-Kasumi-Onoko (Japan)
God of spring. Younger brother of Aki-Yama-no-Shitabi-onoko. He is the lover of Izushio-tome.

Haruspices (Etruria)
Deity of foretelling. An individual haruspex foretells events by interpreting abnormal meteorological events, unusual growths and births of deformed humans and animals.

Harut (Middle East; Islamic)
Harut is one of the two fallen angels. The other is Marut (q.v.).

Hasibwari (Melanesia, Solomon Islands) *see* Hatuibwari.

Hasisu (Phoenician) *see* Kusor.

Hasteseyalti *Hastseyalti* (Apache, Navajo, Papago People, North America)
Also known as: *Yebitsai, Yepitsai.*
Maternal Grandfather of the Gods, the Talking God, and creator. He belongs to a group of household and nature deities known as the Yei (q.v).

Hasteshogan *Hastsehogan* (Apache, Navajo, Papago People, North America)
Also known as: *Hastseltsi, Red Lord.*
God of racing. Known as the Red Lord, Hasteshogan is also a god of the evening and the west. He is also a household deity who belongs to a group of household and nature gods known as the Yei (q.v.). *See also* Ganaskidi; Hastseyalti.

Hastsehogan (Native North American) *see* Hasteshogan.

Hastseltsi (Native North American) *see* Hasteshogan.

Hastseoltoi (Apache, Navajo, Papago People, North America)
Goddess of hunting. Wife of war god.

Hastseyalti (Native North American People) *see* Hasteseyalti.

Hastsezini (Apache, Navajo, Papago, Pueblo People, North America)
A fire god. Called the "Black Lord." Originally four mysterious beings appeared before the first Pueblo people who were called Kisani. These four beings were Bitsis Lakai, Bitsis Dotli'z, Bitsis Litsoi and Bitsis Lizi'n. Bitsis Lakai was like the Navaho Hasteseyalti; Bitsis Dotli'z was like To'nenili, and Bitsis Lizi'n was like Hastesezini. The four mysterious gods created the first man and woman, Atsi Hastin and Aste Estsan.

Hastshehogan (Navajo People, North America) *see* Hasteshogan; Yei.

Hastsheyalti (Navajo People, North America) *see* Hasteseyalti; Yei.

Hat-Hor (Egypt) *see* Hathor.

Hat-Mehit (Egypt)
Dolphin goddess, wife of Ba-nab-djet, the ram of Mendes. *See also* Hathor; Neith.

Hathor *Athor, Athyr, Hat-hor* (Egypt, possibly Mesopotamia), *Hawthor.*
Also known as: *Hat-Mehit.*
Goddess of love, mirth and joy. Goddess of the sky and sun. Possibly a fertility goddess. Mortuary goddess. Hathor (hat-hor) means the "House of Horus." She protected infants and consoled the dead. In earlier times, as the sky goddess, she was regarded as the mother of the sun god, Horus, until she was replaced by Isis. It is thought that Hathor was given a bovine form because the concept of the sky as a cow was widespread in the Delta. In an ancient myth Hathor was said to have raised the young sun-god to heaven by means of her horns. She was known as "Hathor of the Horizon" and her animal was the wild cow. In later periods she was regarded as the solar eye. The sistrum, a musical rattle, was her attribute and fetish. There is reference to her as the mother of Ihy. The goddess Qadesh is thought to be an aspect of Hathor. Hathor was usually depicted in human form wearing a sun-disc flanked by cow's horns on her head. She was also represented as a cow or with the head or horns of a cow, and has been shown with two long ringlets similar to the style of Asherah. As the seven Hathors, they resemble the Fates and are possibly the same as Sekhet, or Bast. She could be associated with Bes. The ancient goddess Apt may be a form of Hathor. Also identified with Hathor is the goddess Ament. Another form of Hathor was the mother goddess Hat-Mehit, counterpart of Ba-neb-Tettu. She has been associated with Asherah and the Greeks identified her with Aphrodite. *See also* Amenhotep; Ament; Amentet; Amun; Astarte; Bes; Hat-Mehit; Horus; Isis; Ninhursag; Nut; Qadesh; Sekhmet.

Hati (Norse; Teutonic)
Also known as: *Gamr, Garm, Garme, Hati Hrodvitnisson, Maanegarm, Mana-garm, Manigarm* (Moon-hound), *Maragarme, Skoll.*
One of two gigantic wolves, in some myths known as werewolves, Hati is the brother of Skoll, and the son of Hrodvitnir. Skoll pursues the sun and Hati is always after the moon. Hati is also known as Garm, the watchdog of the dead, who is stationed at the entrance of Hel's domain. In some versions, the wolf Fenrir is called the father of Hati and Skoll. Hati and Skoll are known as the Varns. *See also* Fenrir; Garm; Ragnarok; Skoll.

Hati Hrodvitnisson (Teutonic) *see* Hati.

Hatmehit (Egypt) *see* Hat-Mehit; Neith.

Hatra (Mesopotamia) *see* Ba'al Shamin.

Hatuibwari *Hasibwari* (Melanesia, Solomon Islands)
Serpent deity. Supreme god. Creator god. He formed a woman from red clay and a man from the woman's rib. Hatuibwari is a winged serpent with a man's head and breasts of a woman.

www.ebook3000.com

Hau (Egypt) *see* Akeneh.

Hauillepenyi (Araucanian People, Chile)
This god of fog looks like a sheep with a calf's head and a seal's tail.

Haukas *Guacas* (Peru) Ancient sun deity.

Haumea (Hawaii)
(Hawaii; Maori People, New Zealand; Tahiti)
Also known as: *Haumea-ka-hanau-wawa* (Haumea giving birth noisily), *Ka-haka-ya-koko* (The Place of Blood), *Kamehaikana, Lau-mihi* (because she gathered crabs and seaweed), *Papa, Papa-hanau-moku* (Papa Giving Birth to Islands).

"Tree of Changing Leaves." Goddess of Childbirth. Goddess of Death. Mother Goddess. Mother of Pele. Sister of Kane and Kanaloa. This goddess introduced natural childbirth. Her own children were born from different parts of her body and were said to be "strange noisy creatures." Wildflowers were in her care but she could withhold their growth in times of need. Haumea, who had the power to transform herself from aged to young, and from young to aged, had many sons. When her oldest son came of age, Haumea died and was reborn so that she could marry him. In time, he died. Haumea again died and was reborn so that she could marry her youngest son. Later, she again died so that she could marry her great grandson. In all, she had six rebirths. Haumea owned an orchard with magical trees that gave the owner whatever he or she wanted. She gave some of her trees to earth children. She also had a spectacular fish tree. The tree had to be placed in the ocean for its fruits to become fish. She gave the tree to one of her sons who placed it in the sea (at that time the waters were without fish). He became the first fisher. His problem was that he was very greedy. Wanting all he could get, he shook the tree with such force that the fish fell from tree and swam away from him, instead of falling into his hands. That is why today one must fish for fish. Haumea also has the ability to disappear into trees. Once, when her husband was being chased for sacrifice, she grabbed him and they both entered into a tree for safety. *See also* Papa; Pele.

Haumia (Polynesia) *see* Haumia-Tikitiki; Hema; Hina; Tawhaki.

Haumia-Tikitiki (Polynesia)
Also known as: *Haumia.*

God of wild or uncultivated plants. He is the son of the sky god, Rangi, and mother earth, Papa. For a list of siblings, *see* Rangi. He is associated with Tawhiri, Tane, Tangaroa, and Tu. *See also* Haumea; Papa; Po; Rongo.

Haur (Teutonic) *see* Dwarfs.

Haurvatat and Ameretat
Also known as: *Khurdad and Amardad* (Pahlavi dialect), *Khurdadh, Khordadh* (Zoroastrian; Persia).

Associated with water and vegetation, these feminine deities are always together. Haurvatat is the goddess of health and Ameretat is the goddess of immortality. As Amesha Spentas they give wealth and herds of cattle. Their opponents are Hunger and Thirst. *See also* Ameshas Spenta; Daevas.

Havai (Polynesia) *see* Avaiki.

Havaiki (Polynesia) *see* Avaiki.

Havamal (Teutonic) *see* Fjalar; Loki.

Havfru *Havfrue* (Finno-Ugric)
Also known as: *Akkruva, Avfruvva.*

Goddess of fish and fishers. Protector of fishers. Havfru is often friendly to people. When a storm is eminent, she can be seen. She is a mermaid, half-fish and half-woman. The male version is bearded. Havfru is probably the same as Havfrue of the Danes. She is possibly the female counterpart of merman, Havmand, of the Danes.

Havgan (Celtic) *see* Arawn; Pwyll.

Havmand (Danish) *see* Havfru.

Hawaii — Creation Legend *see* Kane.

Hawaiki (Polynesia) *see* Avaiki.

Haweniyo (Iroquois People, North America)
Creator deity. Little known.

Hawiyah (Islam)
This is the seventh section in the Islamic Hell. Hawiyah is a bottomless pit reserved for hypocrites. *See also* Islamic Hell.

Hawwa (Babylonian) *see* Eve.

Hay Tau (Phoenician) *see* Adonis; Osiris.

Haya (Babylonian)
"Goddess of Direction." This is one of the titles of the goddess Ninlil (q.v.).

Haya-aki-tsu-hime (Japan) *see* Haya-akitsu-hime-no-kami.

Haya-akihiko-no-kami (Japan) *see* Haya-akitsu-hime-no-kami.

Haya-akitsu-hime-no-kami *Haya-Aki-Tsu-Hime* (Shinto; Japan)
Ruler of the Seas. Haya-akitsu-hime-no-kami (Rapid-Autumn-Princess Deity) is the daughter of Izanagi and Izanami and the sister/wife of Paya-aki-tu-piko-no-kami (also known as Haya-akihiko-no-kami, Rapid-Autumn-Lad-Deity). As the ruler of the turbulent seas she swallows all sins and catastrophes cast into the sea. Haya-akitsu-hime-no-kami was born after the creation of the eight islands of Japan. Haya-akitsu-hime-no-kami is one of the children of Izanagi and Izanami created to populate the terrain and become deities (kami) of the natural phenomena. There were thirty deities created during this time, gods of the seasons, the sea, earth, trees, winds, mountains, valleys and fire. Her brother/husband was the ruler of rivers. In some interpretations, they are the parents of the water, mountain, tree and wind deities and grandparents of fertility, fire, land and bird deities. Later, when Izanagi returned from Yomi (hell), other sea deities were created as he scrubbed the toxins from his body. The ruler of fish and all sea creatures, O-wata-tsu-mi, is the most prominent of the group. During periodical purification rituals, Se-oritsu-hime (Lady-Who-Descends-the-Rapids) is called upon to absolve followers of offenses. The heavenly offenses committed against the earth include pollution, removing water pipes, filling irrigation channels and sowing seed repeatedly. The earthly offenses include offenses committed in sexual relationships, such as bestiality,

the cutting of dead bodies, incest and leprosy. Haya-akitsu-hime-no-kami is also invoked. The god Ibukido-nushi (Breath-Blowing-Lord) blows the offenses to the goddess Haya-sasura-hime (Swift-Banishment-Lady), who lives in Yomi (hell). *See also* Izanagi and Izanami; Kaya-no-hime-no-kami (Ruler of the Grassy Plain); O-wata-tsu-mi.

Haya-ji (Shinto; Japan)
Also known as: *Haya-Tsu-muji-no-Kami.*
Whirlwind deity. Haya-ji is an ancient Shinto deity. When Ame-no-Wakahiko was killed by an arrow, the lamentations of his wife, Shita-teru-hime were heard in the heavens. The sympathetic sun goddess Amaterasu had Haya-ji take the body of Ame-no-Wakahiko back to earth for the funeral. In a variation of this myth, the gods sent the parents of Shita-teru-hime to earth for his funeral. In the Ryobu-Shinto tradition, Haya-ji is shown as an ugly man under the shape of a devil carrying a large bag across his shoulders from which he squeezes wind. For other early Shinto wind deities, *see* Amaterasu; Fu-jin; Shina-tsu-hiko. For additional details about Ame-no-Wakahiko *see* Ame no-oshido-mimi.

Haya-Sasura-Hime (Japan) *see* Haya-akitsu-hime-no-kami.

Haya-Tsu-muji-no-Kami (Japan) *see* Haya-ji.

Hayagriva (India)
Also known as: *Vishnu.*
"The horse-necked" god of learning, Hayagriva, is an aspect of Vishnu. As Hayagriva, his consort is the lion-headed goddess Shakti, Cha-dog-ma (also known as Vajra Shringkhala or Shringhala), who is associated with love. Hayagriva and Cha-dog-ma are the Door-Keepers of the West in the Bardo World. *See also* Ankusha; Shakti; Vajrapani; Vishnu; Yamantaka.

Hayasya (Buddhist; India) The Divine Mare.

Hayk *Hayik* (Ancient Armenia)
Also known as: *Hay.*
Sky-god. Culture hero. Possibly a god of wine and vegetation. Hayk, a culture-hero, overthrew Bel (also called Nimrod). Hayk is the father of Armenak, also a culture-hero and grandfather of Cadmus. He is a giant with curly hair, bright smiling eyes and a strong arm. Armenak may have been associated with the Teutonic hero Irmin and the Vedic Aryaman (qq.v.). *See also* Armenak.

Hayowentha (Native North American) *see* Haio Hwa Tha.

Hea (Chaldean) *see* Ea.

Heart of Heaven (Quiche People, Guatemala) *see* Huracan.

Heavenly Herdsman (Japan) *see* Kengiu.

Heavenly Spinster (China) *see* Chin Nu.

Hebat (Hittite) *see* Hepat.

Hebdomad (Gnostic; Chaldea, Egypt, Syria)
High gods. Sabaoth is one of the seven Hebdomad or Ogdoad deities coming indirectly from Sophia. *See also* Ogdoad; Sabaoth.

Hebe (Greek)
Also known as: *Ganumedes, Ganymeda, Juventas* (Roman).
Goddess of eternal youth. Hebe is the daughter of Zeus and Hera, sister of Ares, wife of Heracles and mother of Alexiares and Aniketos. She was a cupbearer to the gods until she indecently exposed herself. Ganymede replaced her. She restores youth and vigor by supplying Ambrosia and because of this she is sometimes called Ganymede. Iolaus restored Hebe's youth. *See also* Ares; Eos; Ganymede; Hera; Heracles; Juventas; Zephyrus.

Hecab (Greek) This is another name for Hecuba.

Hecate *Hekate* (Greek)
Also known as: *Aktiophi, Artemis* (possible aspect), *Brimo, Crantaeis* (possibly), *Diana, Enodia* (wayside goddess), *Proserpina, Selene* (possible aspect), *Trioditis* (goddess of the meeting of roads).
Underworld goddess. Goddess of night and darkness. Queen of ghosts. Queen of shades. Controller of the hidden things of nature. Possibly a moon goddess. Hecate is either the daughter of the Titan Perses and Asteria or Zeus and Asteria or Zeus and Demeter. Hecate presides over birth, life, death, streets and gates. Her priestess is Medea to whom she taught the art of magic. Hecate, often depicted with a torch, was only worshiped at night by torchlight. Dogs and black lambs were offered to her as sacrifices. She is sometimes shown as a triple statue at crossroads who has with her a pack of hounds. Sometimes she is shown with three heads: a dog, horse, and lion. Hecate is often confused with Artemis. She is similar if not the same as the Indian Ekata. Hecate is associated with Persephone and Pluto. Some think she was an aspect of both Selene and Artemis. The name Brimo was used for Hecate as well as for Persephone, Rhea and Demeter. Hecate as an epithet was used by Luna, Diana, and Persephone. *See also* Artemis; Demeter; Diana; Leto; Persephone; Rhea.

Hecaterus (Greek)
He is the possible father of the Curetes and the Satyrs. *See also* Curetes; Satyrs.

Hecatoncheires (Greek) *see* Hecatonchires.

Hecatoncheiroi (Greek) *see* Hecatonchires.

Hecatonchires *Hecatoncheires, Hecatontocheiroi, Hekatoncheires* (Greek)
Also known as: *Centimani, The Hundred-handed.*
Guardians. Hesiod wrote that the Hecatonchires are the three sons of Gaea (Earth) and Uranus (Sky). They are Briareus (also spelled Obriareus, and also called Aegaeon), Cotus (Cottus) and Gyes (Gyas or Gyges). Giants, each had fifty heads and one hundred arms. Their father was jealous of their great strength and hid them within their mother which filled her with pain. She tried to convince her youngest son, Cronus, to castrate Uranus. Instead, Cronus kept the giants imprisoned in Tartarus. She was more fortunate with Zeus. She convinced him to release her sons so that they could assist him in his battle with the Titans. When they had done so, he returned them to Tartarus and gave them the duties of watching over the Titan prisoners. Briareus was given leave by Thetis to once again assist Zeus in a squabble with opponents but he was returned to the

www.ebook3000.com

dark section of the Underworld when his mission was accomplished. The monstrous siblings of the Hecatonchires are the Giants, the Cyclopes, and Typhoeus. *See also* Cronus; Cyclopes; Enceladus; Gaea; Giants; Hades; Tartarus; Typhon (A); Uranus.

Hecatontocheiroi (Greek) *see* Hecatonchires.

Hector (Greek)
He is the youngest son of Priam and Hecuba. He was killed by Achilles in the Trojan War. *See also* Achilles; Cassandra.

Hecuba *Hecab* (Greek)
After Troy fell, Hecuba was given to Odysseus as a slave. The sons of Polymnestor killed her youngest son, Polydorus. Seeking revenge, Hecuba blinded and killed the men. She was changed into a dog. *See also* Cassandra; Hector; Polydorus.

Hedj-Wer (Egypt) *see* Ape.

Heelios (Greek) *see* Helius.

Hefaidd Hen (Celtic) *see* Rhiannon.

Hefedha (Arabic)
Protector deity. Little known but this deity deters danger.

Hegal (Babylonia) *see* Marduk.

Hegemone (Greek) *see* Charities; Graces.

Heh *Hehu* (Egypt)
Also known as: *Hehet, Neheh.*
God of the immeasurable. God of eternity. He was part of the Ogdoad and by some accounts he mated with Hehut. Heh in numbers denotes a million. He is shown with the head of a frog and is also depicted kneeling and holding a notched palm rib in his hands. Heh was later identified with Shu. *See also* Maa-Nefert-ra; Neheh; Ogdoad.

Hehet (Egypt)
High god. One of the gods in the Pyramid Texts. *See also* Amun; Heh.

Hehuah (Christian, Hebrew) *see* Jehovah.

Hehui *Hehu* (Egypt)
High god. One of the eight ancient gods mentioned with Amen in the Pyramid Texts. In one version he is mated with Hehut. He has the head of a frog. Hehui is probably the same as Heh (q.v.). *See also* Amun.

Hehut (Egypt) *see* Maa-nefert-ra.

Heid (Teutonic) *see* Freyja; Gulveig.

Heidr (Teutonic) *see* Gulveig.

Heidrun (Teutonic)
Deified animal. Either Odin's or Valfather's she-goat. This animal feeds on the leaves and twigs of Lerad, Yggdrasil's topmost branch. Heidrun furnishes the food for the dead warriors in Valhalla. Heidrun is similar to Saehrimnir, the boar, who is also food for the gods. *See also* Saehrimnir; Valhalla; Yggdrasil.

Heilyn (Celtic)
He is the son of Gwynn the ancient, and one of the survivors of the battle between Bran and Matholwch. *See also* Bran.

Heimdall *Heimdal, Heimdallr* (Norse; Teutonic)
Also known as: *Heimdal-Rig, Rig.*
One of the Aesir. God who was the son of nine mothers, or brother of nine sisters. Some versions give the name of the father as Odin and the names of the mothers as Angeyja, Atla, Eistla, Eyrgjafa, Gjalp, Greip, Ind, Jarnsaxa, and Ulfrun. He visited three women, and had three different children. He is the watchman of the gods and guard of the bridge. He is the owner of the horn, Gjall, which can be heard all over the world. Heimdall is the only god who lived for a time among mortals. After he assumed the name Rig, he and a mortal woman produced Jarl. He may be the son of Odin. Heimdall needs very little sleep and can see a hundred miles, hear the grass grow and wool growing on sheep. The following is a list of the three women and their children. The race of Thralls: Edda the mate of Ai. By Heimdall she had Thrall who in turn married Thir (the drudge). Their sons are Fjosnir, Klur, Hriem, Kreggi, Kefsir, Fulnir, Drumb, Digraldi, Drott Leggjaldi, Lut and Hosvir. Their daughters are Drumba, Kumba, Okkvinkalfa, Arinnefja, Ambott, Eikintjasna, Ysjarughpja and Tronubeina. The race of Peasants: Amma the mate of Afi. From Heimdall she had Karl who married Snor. Their sons are Hal, Dreng, Hold, Thegn, Smit, Breid, Bondi, Bundinskeggi, Bui, Boddi, Brattskegg and Segg. The daughters are Snt, Brud, Svanni, Svarri, Sprakki, Fljod, Sprund, Vif, Feima, and Ristil. Heimdall's third woman was Mothir, the mate of Fathir. From Mothir, Heimdall had Jarl, who married Erna. Their children are the sons Bur, Barn, Jod, Athal, Arvi, Nid, Nidjung, Svein, Kund and Kon. The daughters are not named in legend; however, Heimdall's mothers are the daughters of Aegir and Ran. Heimdall has gold teeth so is known as "Gold Tooth." When Balder died, Heimdall rode Gulltoppr, his horse with the golden mane, to the funeral. Heimdall's home is called Himinbjorg. *See also* Aegir; Aesir; Balder; Freyja; Gjall; Gunlodd; Odin; Ran; Thor.

Heitsi-Eibib *Haitsi-aibeb* (Hottentot People, Africa)
Also known as: *Tsui-goab.*
Sorcerer god. Magician. He is the offspring of a cow or a virgin who ate a magic herb. A shape-shifter, Heitsi-Eibib eats special grass. He is the spirit of the bush and the hero of hunters. He dies and is reborn. His enemy is Gaunab (q.v.). *See also* Gaunab; Tsui'goab.

Hek (Egypt) *see* Heka.

Heka *Hek, Hekau, Hyk* (Egypt)
Serpent. God of magic. This serpent is mentioned in the magical formulae of Unas, King of the Fifth Dynasty. It is sometimes identified with Shu. *See also* Akeneh.

Hekate (Greek) *see* Hecate.

Hekatoncheires (Greek) *see* Hecatonchires.

Hekau (Egypt) *see* Heka.

Heke-Heke-I-Papa (Polynesia)
Earth goddess. One of the wives of Rangi. Of the many children of these two, the most well-known is Tama-nui-rangi. *See also* Rangi.

Heket *Hekt, Heqet, Heqt, Heqtit, Hequet* (Egypt)
The goddess who attends births. Heket attends Ra as he is

born again each morning. Along with other deities, she assists in forming children in the womb and presiding over births as a midwife. She is shown as a woman with the head of a frog. Sometimes, she is depicted as a frog at the end of a phallus. Heket is associated with Isis. She was the assistant to the goddess in bringing Osiris back to life. Heket is the female complement of Khnum, the ram-headed god. In some interpretations, she is known as his mother. *See also* Isis; Khnum.

Hekret (Egypt) *see* Akeneh.

Hekt (Egypt) *see* Heket.

Hel (Norse; Teutonic)

Also known as: *Hela, Hella, Urd, Urth.*

Goddess of the underworld. There is some confusion as who was really the deity of the underworld. Some say it is Odin. Hel, Hella, Hellawisi, Hellewite, Hellia, Helviti, Halvete, Helvede are the various names for the Underworld or "Place of Punishment." Hel is the daughter of Loki, and sister of Fenrir and Ifing. Hel's plate is called Hunger; her knife, Famine or Starvation; her bed was Sick Bed or Disease; and the bedhangings, Glimmering Misfortune or Misery. Hel is said to be the same as Helheim, one of the nine worlds of the dead. She is a woman whose upper body is alive and her lower body is half-dead and rotting. *See also* Balder; Garm; Gullveig; Hades; Hati; Hermod; Loki; Nifl-heim; Urd.

Hela (Teutonic) *see* Hel.

Helblindi (Teutonic)

He is the son of Farbuti, and brother of Loki. Helblindi is also a name given to Odin. *See also* Farbuti; Loki; Odin.

Heleius *Heleus* (Greek)

He is the son of Perseus and Andromeda. He ruled the Taphian Islands with Cephalus. *See also* Andromeda; Gorgophone; Perseus.

Helen (Greek)

Also known as: *Helen of Troy.*

Queen of Sparta. Helen is the daughter of Zeus and Leda or Nemesis. Her mortal step-father is Tyndareus. She is the half-sister of the Dioscuri (Castor and Pollux) and the sister of Clytemnestra. Early in life she was abducted by Theseus, the king of Athens and rescued by the Dioscuri. Renowned for her beauty, and pursued by various suitors, she chose Menelaus, but either eloped with or was abducted by Paris, a rich Trojan prince. This created the havoc that was said to have initiated the Trojan War. After his death she married Deiphobus, spent a number of years in Egypt and returned to Sparta with Menelaus after the fall of Troy. It is said that Menelaus originally wanted to kill her but melted at the sight of her beauty. Helen and Menelaus have a daughter, Hermione, and sons, Aethiolas and Maraphius. According to other sources, their children are Hermione, Pleisthenes and possibly Nicostratus. She also had three sons by Paris: Bunomus, Aganus and Idaeus, and a daughter, Helen. These sons are said to have died as infants under a collapsed roof in Troy. Helen is also the mother of Iphigeneia as a result of her relationship with Theseus. There are many versions of her death but it is likely that she was hung by the maids of Argive Polyxo who were avenging the death of Tlepolemus at Troy. *See also* Acamas (A); Agamemnon; Ajax the Greater; Castor and Pollux; Hesione; Leda; Menelaus; Nemesis; Paris; Tyndareus.

Heleus (Greek)

He is the son of Andromeda and Perseus. His siblings are Alcaeus, Electryon, Gorgophone, Mestor, Perses and Sthenelus. *See also* Andromeda; Gorgophone; Paris; Perses.

Helheim (Teutonic) *see* Hel; Hell.

Heliades *Heliaads, Heliads* (Greek)

Deities of light. The Heliades are the daughters of the sun god Helius and the Oceanid, Clymene, and the sisters of Phaethon. Their names are Aegiale (also known as Phoebe), Aegle and Aetheria. They were changed into poplar trees and their tears became amber. The sons of Helius by Rhode are also called Heliades. A group of intelligent men, known for their interest in astrology, they are Actis, Candalus, Cecaphus, Macar, Ochimus, Triopas. *See also* Aegle (A); Clymene; Helius; Oceanids.

Helicaon (Greek)

He is the son of Antenor and Theano. *See also* Acamas (B); Agenor; Antenor; Archelous; Glaucus; Laodamas.

Helice (Greek)

She is the daughter of the king of Aegialus and wife of the king of Athens, Ion. *See also* Zeus.

Helios (Greek) *see* Helius; Sebek.

Helius *Heelios* (Ancient Greek), *Helios* (Greek; Roman)

Also known as: *Acamas* ("Untiring"), *Hyperion, Panderces* ("All-seeing"), *Sol* (Roman), *Terpimbrotos* ("He Who Makes Mortals Rejoice").

Sun god. Helius is the son of Hyperion and Theia. His siblings are the goddess of dawn, Eos, and the moon goddess, Selene. He married Perse and became the father of Perses, who is known for his brutality; Pasiphae, who by a bull became the mother of Minos; Aeetes, the cruel king of Colchis; and Circe, the sorceress. He is also thought to be the father of the Graces, by Aegle and the father of the Heliades, by other women. He may be the father of Aex, the Corybantes, and Augeias. He is also said to be the father of Achelous, by Gaea. He was loved by the nymph, Axibia. When Zeus apportioned the world, he neglected to give Helius a section. To keep him happy, the great god gave him the island of Rhodes. He drove a four or nine horse chariot named Quadriga through the sky during the day, accompanied by Eos. The names of his horses are Aethon, Astrope, Bronte, Chronos, Eous, Lampon, Phaeton, Phlegon, Pyroeis. Each night Helius returned from west to east on the river Oceanus, transported in a golden cup. Loyal to his children, he allowed his son Phaethon to borrow the sun chariot one day and it ended in disaster. He would take Circe and Aeetes on his rounds and he once loaned the chariot to his granddaughter Medea. Helius loaned the golden cup to Heracles twice; once for his journey to Erytheia and again in his search for the Garden of Hesperides. The giant Orion was healed of blindness by Helius. Aphrodite, furious at the all-seeing Helius for telling her husband that she was having an affair with Ares, got even by having him fall in love with the daughter of king

www.ebook3000.com

6. Move your hands down touching your femur bones; feel your hands penetrate into the bone and into the bone marrow. Feel like an electric shock or a tingling moving all the way down through the bones of the leg and down to the soles of your feet.
7. Slowly move your fingers down touching the bone and into bone marrow and extend yourself down past the earth to touch the galaxy on the other side. Raise your sacrum and picture yellow light coming up from the earth and the other side of the galaxy; focus on the Lower Tan Tien and feel it fill with Chi. Do this three times. Go back down to the squatting position.



Fig. 2.4 *Galaxies Spiral Star and the Direction of Spiral*

8. Place the palms face down to the earth and be aware of the galaxy and the yellow light; make three to six circles to gather the Chi below. Gather the yellow Chi; touch your heels and feel the yellow Chi flowing up the leg bones. Feel the bubbling of your bones like an electric current running up through the feet, tibia and fibula, femur, pelvis, and spine. While touching your bone and bone marrow with your fingers, slide your hands up along the back of your legs; slowly come all the way up to touch the coccyx and the sacrum. Concentrate on your sexual center so the energy will flow and spread out to the sexual organs. Go back to the navel and gather the Chi into your Tan Tien.

Orchamus, Leucothoe. He had to disguise himself to gain entry to her bedroom. A former love, the spiteful Clytie, inflamed with jealousy, told the king who punished his daughter by burying her alive. Overwhelmed with grief, Helius transformed her into a frankincense bush. The spurned lover died and became the flower, heliotrope, who turns its head to follow the sun each day. Some say the Colossus of Rhodes was a depiction of his form. Helius is also shown with a halo of rays and the attribute of a crocodile in his hand. Helius is often confused with his father, the Titan sun god, Hyperion. For additional offspring of Helius *see* Heliades. Compare Helius to the god of light, Apollo, to the Norse god, Sol, the Hindu sun god, Surya, the Slavonic god Dazbog, and the Roman Sol. *See also* Aeetes; Aegipan; Aegis; Aegle; Alcyoneus; Aphrodite; Ares; Clytie; Eos; Graces; Heliades; Medea; Oceanids; Orion; Pasiphae; Phaethon; Sebek; Selene.

Hell *Hel, Nifl-heim* (Teutonic from the root word Hel or Hol, possibly)

Also known as: *Amenti* (Egyptian), *Duzakh* (Persian), *Dzokh* (Armenian), *Gehenna* (Hebrew), *Hades* (Greek), *Irkalia* (Babylonian), *Kigal* (Akkadian), *Santaramet* (Iranian), *Sheol* (Hebrew), *Spenta Armaiti, Spentaramet, Tartarus.*

Underworld. Many versions of Hell describe it as being somewhere underground or below the earth. The Egyptians say it was Amenti with pits of flame and demons. The Norse say the Yggdrasil tree had its roots buried in Hell. The Akkadians call it Kigal. The Babylonians call it Irkalia. To some it is a place of the dead and of no return while some say it is just a stopover region. In traditional Western literature, the angel of Hell is Nasargiel. He oversees the torture of sinners. *See also* Amentet; Elysian Field; Gehenna; Hades; Hel; Helheim; Irkalla; Nifl-heim; Sheol; Spenta Armaiti; Spentaramet; Tartarus.

Hella (Teutonic) *see* Hel.

Helle (Greek)

Helle is the daughter of Athamas and Nepele, and the sister of Phrixus. The sister and brother escaped on the ram with the Golden Fleece. *See also* Golden Fleece; Ino; Nephele; Phrixus.

Hellen (Greek)

A Hero. King of Phthia. Hellen gave his name to the Hellenes, the Greek race. He is the son of Deucalion and Pyrrha, or possibly Zeus and Dorippe, or Prometheus and Clymene. With the nymph Orseis they are the parents of Dorus, Xuthus, and Aeolus. He is the grandfather of Ion and Achaeus. *See also* Achaeus; Aegimius; Aeolus; Deucalion; Ion; Xuthus.

Heloha (Choctaw People, North America)

The female Thunderbird.

Helunus (Greek) *see* Cassandra.

Hema (Polynesia)

He is the son of Kaitangata and Whaitiri, the cannibal goddess. His sibling is Punga. (In Hawaii, Kaitangata's wife is Hina-who-worked-in-the-moon and Hema's mother is the moon goddess Mahina.) Hema married the goddess Urutonga ("South-West"). They had two (some say three) children, Tawhaki, the god of thunder and good health, and Kariki. When Hema inadvertently trespassed on the land of the goblins, he was put to death. His sons took revenge for his demise. *See* Haumea; Tawhaki.

Hemera (Greek)

"Day." She is the daughter of Erebus, who is the personification of the darkness of the Underworld, and Nyx, the personification of night. Her union with Cephalus, the son of the messenger of the gods, Hermes, and Herse, the personification of the dew, produced Phaethon, who was kidnapped by Aphrodite to watch over her shrine. *See also* Aither; Erebus; Hermes; Herse; Nemesis; Nox; Phaethon.

Hemsut (Egypt)

Deity of protection. *Deity of destiny. Hemsut appears as the* female counterpart of the "ka" (creative and preserving power of life). Hemsut wears an emblem and headdress of the shield. Above the shield are two crossed arrows. *See also* Ka.

Hemth (Egypt) *see* Akeneh.

Heneb (Egypt)

The god of grain and other land products, Heneb is the competitor of Osiris.

Heng (Huron People, North America)

Also known as: *De Hi No, Thunder.*

God of Thunder. Male fertility spirit. He is one of seven brothers, all atmospheric deities. *See also* Tsentsa; Yoskeha.

Heng and Ha (Buddhist; China)

Also known as: *Heng Ha Er Tsiang, Indra, Snorter and Puffer, Vajrapani.*

Heng and Ha are two forms of the Buddhist god Vajrapani, a name assumed by Indra when he was the bodyguard of Gautama. General Puffer is called Ha-Tsiang. General Snorter is called Heng-Tsiang. Heng is also known as Cheng Lung. *See also* Men Shen.

Heng-Ha-erh-Chiang *Heng Ha Er Tsiang* (China) *see* Heng and Ha; Men-shen.

Heng-O (China) *see* Chang-O.

Heng-Tsiang (China) *see* Heng and Ha.

Henga (Osage People, North America)

Deified bird. Sacred Eagle.

Henir (Norse; Teutonic) *Hoener, Hoeni, Hoenir, Hone, Honer, Honir.*

Also known as: *We* (possibly) or *Willi* (possibly).

"God of Silence." One of the triad, with brothers Odin and Lodur, or part of the trinity of Odin, Loki and Henir. Henir, was taken hostage to the Vanir in exchange for Niord. Known as the "God of Silence," he never spoke unless prompted by Mimir (also known as Memory). In some versions, Henir is part of the group that created the world from Ymir's body. *See also* Aesir; Loki; Midgard; Mimir; Odin; Ymir.

Henkhisesui (Egypt)

Wind deity. God of the east wind, shown as a snake-headed man with four wings.

Henmemet (Egypt) Lesser deities.

Heno (Iroquois People, North America) *see* Adekagagwaa; Hino.

Hentiu (Egypt)
Spirits of the twelfth sector of Tuat, the Henitiu are forms of Osiris.

Hentiu and Antiu (Egypt) *see* Antiu; Hentiu.

Hepa (Egypt) *see* Ap-taui.

Hepat *Hebat, Hepit* (Hittite, Hurrian)
Also known as: *Hepatu, Wurusemu.*
Hepat, the Hurrian goddess of beauty, fertility, and royalty, is the wife of the Teshub, the weather god. She is possibly the mother of Sharruma (also known as Sharma). In later times, she merged with the Hittite sun goddess, Wurusemu. She is shown standing on a lion or a panther, well-dressed, wearing a crown, jewels and ornate shoes. She was driven from her temple by Ullikummis (q.v.). *See also* Arinna; Teshub.

Hepatu (Hittite) *see* Hepat.

Hephaestus (Greek) *see* Hephaistos.

Hephaistos *Hephaestus* (Greek)
Also known as: *Mulciber, Ptah* (Egypt), *Vulcan* (Roman).
Divine artisan. Patron of crafts. Lord of artificers. Hephaistos is the son of Zeus and Hera, or by Hera by autogenesis. His siblings are the god of war, Ares, the nymph, Arge, the goddess of strife, Discordia, Eleithyia, and Hebe, the goddess of eternal youth. Hephaistos is thought to have married either the youngest of the Graces, Aglaea, or the goddess of love, Aphrodite. He fathered the half-serpent Erichthonius either alone or with Athenia, Gaea or Attis; the Argonaut Palaemon by Lernus' wife; and possibly the outlaw Periphetes by Anticleia. He is also the father of Olenus, who was later turned to stone, and Tullius, the sixth king of Rome, by Ocrisia, a Roman slave. With Aetna he fathered the twin male Palici volcanoes although some feel they were the sons of Zeus and Thalia. He was also the father of Cerycon, king of Eleusis. In one version of his life, he was abused, rejected, and thrown out of heaven as a newborn by Hera because of his deformed legs. He landed in the Oceanus where he was rescued and raised by the Oceanid Eurynome and Thetis of the silver feet. In another version, Zeus threw him from heaven because of his deformity and he landed on the island of Lemnos where he was raised by the Sintians. He became an artisan in metal and created many fine and useful items. Pandora, the first female known to man was his creation. He also enabled Athena to issue forth from the head of Zeus by splitting it open with his hammer. His hot metal pellets killed the giant Mimas, he forged Achilles' magic armor, Heracles' magic shield, weapons for Aeneas and possibly fastened Prometheus to a cliff by chains to fulfill a request for Zeus. Multi-faceted, he designed Harmonia's necklace which is fatal to all who wear it, and built many beautiful palaces for the gods of Olympia. Hephaistos was helped in his craft by the dwarfs Sileni and Satyrs, the Cyclopes who did the heavy work, and his personal assistant and some say his son, the dwarf, Cedalion. Despite his abusive beginnings and the fact that he was unable to use his legs in the usual way, he used his upper body and his mind to create and to contribute to others. Hephaistos is sometimes shown as a stunted, bearded man, holding a hammer. He is sometimes shown with a conical hat. He is identified with but not the same as the Roman Vulcan. *See* Ares for information about Ares' affair with Hephaistos' wife Aphrodite. Compare Hephaistos to the Vedic Tvastri, the Slavonic Dazbog, the Celtic Goibniu, and the Egyptian Ptah. *See also* Acamas (D); Achilles; Aeetes; Aegis; Aeneas; Aglaia; Anteros; Ariadne; Athena; Cedalion; Credne; Curetes; Eurynome; Gaea; Graces; Harmonia (A); Hera; Mimas; Orion; Pandora; Prometheus; Ptah; Rivers; Stymphalian Birds; Thetis; Vulcan.

Hepit (Hurrian) *see* Hepat.

Hept-Shet (Egypt) *see* Assessors.

Heptet (Egypt)
Deity of death. This goddess assisted in the resurrection of Osiris. She has the body of a woman with the head of a bearded snake. On her head she wears a pair of horns surmounted by a solar disk, the Atef crown, and uraei with disks and horns. In each hand she holds a knife. *See also* Osiris.

Heqet (Egypt) *see* Heket.

Heqt (Egypt) *see* Heket.

Heqtit (Egypt) *see* Heket.

Hequet (Egypt) *see* Heket.

Her-Ba (Egypt) *see* Aai.

Her-Hequi (Egypt)
High gods. One of four deities in the fifth sector of Tuat.

Her-Pest (Egypt)
A form of the god Horus as victor over the great "male hippopotamus," the symbol of the god Set (Seth). *See also* Horus.

Her-T (Egypt) *see* Anhur; Hathor.

Her-Tchema (Egypt) *see* Horus.

Her-tesu-f (Egypt) *see* Ab-esh-imy-duat.

Her-Thertu (Egypt) *see* Tcheser-tep-f.

Hera *Here* (Greek)
Also known as: *Antheia* (Flowering One), *Argeia* (Argive Hera), *Juno* (Roman), *Karphophoros, Kourotrophos.*
Sky goddess. Queen of heaven. Goddess of women. Goddess of childbirth. Goddess of marriage. Goddess of wild things. Hera is the daughter of Cronus and Rhea. Her siblings are Demeter, Hades, Hestia, Poseidon, and Zeus. Zeus disguised himself as a cuckoo and seduced his sister. She became a jealous, exacting spouse. Hera visited severe vengeance upon the numerous females with whom her philandering mate Zeus became enamored, as well as upon their offspring. She became the mother of Ares, Arge, Discordia, Ilythia, Hebe, and Hephaistos. Typhon might also be her son. Hera's nurse is Euboea, her favorite handmaiden is Iris. Her attendants are the Charites and Horae. During the Trojan War she was on the side of the Greeks and assisted the Argonauts on numerous occasions. The name Antheia is used for Hera in her form as an adolescent. As an earth mother, goddess of wild things and child-rearer, she was known as Karpophoros. Hera's sacred fruits are the apple

www.ebook3000.com

and pomegranate. Her sacred birds are the cuckoo, goose, and peacock. Hera is shown as a regal matron wearing a crown. She is calm in appearance and her eyes are wide-opened. *See also* Ares; Charities; Cronus; Demeter; Hades; Hephaistos; Horea; Medea; Jason; Juno; Poseidon; Zeus.

Heracles (A) *Herakles* (Roman) *Hercules* (Latin); (Greek).

Also known as: *Alcides* (name given at birth), *Criophorus, Melkarth* (Carthage), *Melqart, Monoecus.*

Hero. Heracles, the son of Zeus and Alemene (Alcmene), or Zeus and Alkmena, became the greatest of Greek heros, despite the obstacles he had to overcome. Hera, jealous of his birth by Zeus and a mortal woman, took her hostilities out on Heracles. Renowned for his strength, he strangled two serpents, which Hera had sent to destroy him, while he was still in the cradle. Zeus wanted him to live in the world and gain knowledge of the human condition so that the gods would have a greater understanding of mortals. He was known as Herakles or Hercules by the Romans, and Melqart by the Carthaginians. Driven mad by Hera, he accidentally killed his own children and his wife, Megara, daughter of Creon. On recovering he was so stricken with grief that he exiled himself and went to consult the oracle of Apollo at Delphi. He was commanded to serve Eurystheus for twelve years. During that period he performed twelve labors. The gods assisted him in his tasks, and he carried them out successfully. **1.** Slaying the Nemean lion with his own hands. He was called Alcides after wearing the pelt of this lion. **2.** To destroy the nine, or as some say, seven-headed Lernaean hydra which had ravaged the country of Lernae near Argos. The middle head was immortal and for every head lopped off by Heracles, two grew in its place. With the assistance of Iolaus, he burned away the heads and buried the immortal head under a great rock. He shot it with poisoned arrows and the wounds became incurable. **3.** To capture the Arcadian or Cerynean stag which had golden horns and brazen hoofs. **4.** To capture the Erymanthian boar in a net and carry him to Mycenae. Along the way he fought with the Centaurs, killing many of them and wounding his old friend Chirion, who died. **5.** To clean the Augean stables which held three thousand oxen belonging to King Augeas of Elis. They had not been cleaned for thirty years and Heracles had to clean them in one day if he wanted the reward of one-tenth of the cattle. He accomplished this by turning the rivers Alpheus and Penus through the stables. Augeas then refused him the reward, and at a later time Hercules killed him. **6.** To kill the Stymphalian birds which belonged to Ares and which had brazen claws and beaks. They used their feathers as arrows and preyed upon humans. **7.** To capture the wild bull of Crete which King Minos of Crete had begged as a sacrifice from Poseidon. **8.** To capture the man-eating mares of Diomedes, who fed his horses with human flesh. **9.** To obtain the girdle of Hippolyte, queen of the Amazons, by making war on the Amazons and slaying Hippolyte. **10.** To capture the oxen of Geryon. While there he erected the mountains in Spain and Africa, known as the Pillars of Hercules. **11.** To fetch the three Golden Apples from the Garden of the Hesperides by sending Atlas to get them while he held up the heavens. **12.** To bring Cerberus, the three-headed dog of Hades, to the Upperworld. Heracles was also known for his eight deeds: **1.** Beating Antaeus in a fight. **2.** Rescuing Alcestis from the Underworld. **3.** Traveling as an Argonaut. **4.** Rescuing Hesione. **5.** Acting as a servant to Omphale. **6.** Stealing the sacred tripos of Delphi after Apollo refused him purification. **7.** The sacking of Troy. **8.** His twelve labors. After performing the twelve labors Heracles was free from service to Eurystheus and returned to Thebes. He married Deianira, daughter of Oeneus of Calydon. When Nessus, a centaur, tried to abduct her, Heracles shot him with a poisoned arrow. The dying Nessus told Deianira to keep his blood since it would always preserve her husbands's love. Later, fearing that she was being supplanted by Iole, Deianira sent Heracles a garment soaked in the blood of Nessus, which poisoned him. After his death he was taken to Olympus, given immortality, and married Hera's daughter, Hebe. He was honored after his death with the task of guarding the Gates of Olympia. Heracles was characterized by brains, brawn, gluttony, drunkenness and sexual prowess. Although he slew many mythical monsters, he also drained swamps, built roads, and served the people. His earthiness and humor made him appealing to the common person. The name Criophorus (one who carries a ram) was given to Heracles after he carried a ram around the town three times to save the people of Tanagra from the plague. Compare Heracles to Krishna (India) and Arjuna (India). *See also* Abderus; Acca Larentia; Admete; Admetus; Aegimius; Aeneas; Agrius (A); Alcyoneus; Alpheus; Amazons; Antaeus; Ares; Calydonia Boar Hunt; Enceladus; Eos; Eurydice (C); Giants; Harsaphne; Helius; Hephaistos; Hera; Hesione; Hesperides; Hylas; Jason; Medea; Nereus; Pelops; Sarpedon (B); Scylla; Stymphalian Birds; Zetes.

Heracles (B) (Greek)

He is a Dactyl, who is the son of the nymph Anchiale or Rhea, the mother of the gods.

Herakhty (Egypt) *see* Harakhtes.

Herakles (Greek) *see* Heracles.

Heraktes (Egypt) *see* Ra-Harakhte.

Herb-Quelling (Japan) *see* Kusanagi.

Hercules (Greek) *see* Heracles.

Herdesuf (Greek) *see* Horus.

Herecgunina (Algonquin, Chippewa, Cree, Nascopie People, North America)

The power of evil.

Herfadir (Teutonic) *see* Odin.

Herhkhty (Greek) *see* Horus.

Heri-Seru (Egypt) *see* Assessors.

Herishef (Egypt) *see* Arsaphes.

Herjan (Teutonic)

This name, meaning "God of Battles," is an alternate name for Odin.

Herkeios (Greek) Zeus as the protector of the home.

Hermakhis (Egypt)

This is a title used for Horus. It means "Horus on the Horizon."

Hermanubis (Greek)
Also known as: *Anubis, Heru-em-Anpu* (Greek).
Aspect of Anubis. This name is used for the god Anubis in connection with his role as conductor of the souls of the dead, a function he shared in common with the Greek god Hermes. He is shown as a jackal-headed man, the same as Anubis (q.v.).

Hermaphroditos (Greek) *see* Hermaphroditus.

Hermaphroditus *Hermaphroditos* (Greek)
Also known as: *Atlantiades, Atlantius.*
Minor deity. Born as Atlantiades, the son of Hermes and Aphrodite was renowned for his beauty. His father had numerous children by other women but had long desired the goddess Aphrodite. She wasn't remotely interested in him until the great god Zeus intervened. He had his eagle swoop down and steal one of her slippers while she was bathing in the Achelous river. The eagle was instructed to deliver it to Her-me's home in the Egyptian city of Amythaonia. In return for the slipper, Aphrodite would have to satisfy Hermes' longing for her. She did, and of this union Atlantiades was born. (In some myths, a man named Anaplades and not Hermes played this role.) When Atlantiades was fifteen, the nymph Salmacis began to pursue him. An innocent, he rebuffed her advances, which infuriated her. When she spied him bathing in a fountain she jumped in and clung tightly to him while she prayed to the gods that they be united forever. Her prayers were answered in an unusual way. Atlantiades and Salmacis became one person physically sharing male and female attributes and he/she became known as Hermaphroditus. In another version of this myth it is said that whoever bathed in the fountain would lust after a person of the same sex. Compare Hermaphroditus to Hylas. *See also* Aphrodite; Hermes.

Hermeias (Greek) *see* Hermes.

Hermes *Hermeias* (Greek)
Also known as: *Agoneus* (Greek), *Mercury* (Roman), *Mercurius* (Roman), *Turms* (Etruscan).
Messenger of the gods. Hermes is the versatile god of commerce, and patron of travelers, shepherds, traders, and robbers. Early Egyptologists thought of him as a god of knowledge, and the Egyptians called him Mercury, Sebku or Sebek. In his aspect of Agoneus he is the patron of gymnastic exercises. He is the son of Zeus and Maia, and brother of Apollo. He fathered Autolycus, Cephalus, Ceryx, Myrtilus, and possibly Pan. His various loves are Herse, Deianeira (Persephone) and Penelope. A talented god, he is the inventor of the lyre and the pipes of Pan (both musical instruments). Hermes exchanged the pipes of Pan for the golden rod Apollo used to herd cattle. This rod became the caduceus which was Hermes' emblem. Many of his exploits turn upon thievery or mischief. He wears a winged cap and has wings attached to his ankles, enabling him to travel from place to place with the speed of the wind. He was originally a god of stones, stoneheaps, and boundaries. He was first shown as a mature bearded athlete. Later, he was depicted as a younger athlete carrying a caduceus and wearing winged sandals and a winged helmet. As Mercury his sacred animals are the goat, cock and the tortoise. The Greek people identified Hermes with the Egyptian god Thoth. *See also* Abderus; Acacallis; Aegisthus; Aether; Agraulos; Amphion; Ares; Argus (B); Autolycus; Calypso; Evander (A); Evander (B); Fates; Harpies; Hermaphroditus; Ino; Mercury (B); Oenamaus; Orion; Pelops; Perseus; Sebek; Semele; Thoth; Typhon (A); Zetes.

Hermin (Teutonic) *see* Irmin.

Hermione (A) (Greek)
She is also known as Harmonia. *See also* Harmonia (A).

Hermione (B) (Greek)
She is the daughter of Menelaus and Helen of Troy. *See also* Helen.

Hermitten (Tupi-Guarani People, Brazil)
In one of the Creation Legends, Hermitten and his two brothers, Coem and Krimen, escaped the Deluge by hiding in caves, or by climbing trees. In the legend, Guaracy, the sun, is the creator of all animals. The other creator gods are Jacy the moon, who created plant life, and Peruda who was concerned with human reproduction. *See also* Tawendore.

Hermod *Hermodr* (Norse; Teutonic)
The son of Odin, Hermod is a wind and war god. He acts as a messenger between the deities. When Balder suddenly died, Hermod volunteered to ride Odin's horse, Sleipnir, into the realm of Hel to search for him. He was unsuccessful in bringing Balder back from Helheim. He did bring the ring Draupnir back with him to give to Odin. Hermod and Bragi welcome dead war heroes into Valhalla. *See also* Balder; Bragi; Draupnir; Frigg; Hel; Odin; Sleipnir; Valhalla.

Hermoder (Teutonic) *see* Aesir.

Hero (Greek)
Hero is one of the Aphrodite's priestesses. Leander fell in love with her. Every night he swam across the Hellespont to see her. One night he drowned. Stricken with grief, the beautiful Hero drowned herself. *See also* Rivers.

Herok'a (Algonkian, Chippewa, Cree, Nascopie People, North America)
They are earth spirits known as "Those without Horns."

Herovit *Jarovit* (Slavic) God of the army.

Herse (Greek) "The Dew"
Herse is the daughter of Cecrops or Acteus and Agraulos. Her relationship with the messenger of the gods, Hermes, produced Cephalus and Ceryx. *See also* Agraulos; Cephalus; Ceryx; Hermes.

Hershef (Egypt)
Also known as: *Arsaphes* (Greek), *Harsaphes* (Egypt).
Known as "Terrible Face," this ram-headed god, adopted by the Greeks and known as Arsaphes or Harsaphes, was worshiped at Heracleopolis Magna. *See also* Harsaphes.

Hert-ketit-s (Egypt)
Underworld deity.
A lion-headed goddess, she presides over the pit Hatet, in the eleventh sector of Tuat. She belches fire on the wretched

www.ebook3000.com

creatures who are then hacked to pieces by a large knife which she holds in both hands.

Hert-Nemmat-Set (Egypt)
Underworld deity.
A woman fiend in the fourth pit of the eleventh sector of Tuat who punishes the shadows and heads of the damned.

Hert-sefu-s (Egypt)
Underworld deity.
A woman fiend in the fifth pit of the eleventh sector of Tuat who does the same as Hert-Nemmat-Set.

Hertha *Nertha* (Norse; Teutonic)
Also known as: *Aertha, Aerth.*
Mother of the gods. Goddess of agriculture. She is specially worshiped at Shrove-tide when ploughs are carried in procession. *See also* Bertha; Nerthus.

Hertyr (Teutonic) *see* Odin.

Heru (Egypt)
A Hawk God. Probably an aspect of Horus. *See also* Aai; Ashenu; Horus; Unas.

Heru-ap-sheta-taui (Egypt) *see* Jupiter.

Heru-em-akbet (Egypt) *see* Harmachis; Sphinx.

Heru-em-Anpu (Egypt) *see* Hermanubis.

Heru Khent an Maa (Egypt) *see* Horus.

Heru-Khu (Egypt)
Also known as: *Heru-Khuti.*
Sun deity. One of four deities in the fifth sector of Tuat. Replaced by Amen and Amen-Ra. *See also* Mars.

Heru Khutti (Egypt) *see* Horus.

Heru Murti (Egypt) *see* Horus.

Heru-P-Khart (Egypt) *see* Harpokrates.

Heru-pa-kaut (Egypt)
Great Mother. She is the mother and counterpart of her son Ba-neb-tettu, the creator god. She is depicted with a fish, the symbol of plenty and fecundity, on her head.

Heru-Pa-Khret (Egypt) *see* Harpokrates.

Heru Sam Taui (Egypt) *see* Horus.

Heru-tuati (Egypt) *see* Ab-ta.

Heru Ur (Egypt) *see* Horus.

Heruka (Buddhist; Tibet)
Heruka is one of the numerous deities that emanated from Akshobhya. Also called the Great Heruka, he represents compassion, and his sakti, Nairatma, personifies knowledge. The worship of Heruka is said to confer Buddhahood on the worshipper. His mate in Bardo is Buddha Krotishaurima (the Mighty Wrathful Mother). Heruka appears with her on the Eighth Day in Bardo. She is embracing him, her right hand is clinging to his neck and with her left hand she is putting a blood-filled red shell to his mouth. Heruka is dark brown, with three heads, six hands and four feet. His middle face is dark brown, the right one is white and the left, red. He has nine eyes and protruding teeth. His hair is reddish-yellow. He wears garlands of severed heads and skulls, a tiger skin and snake ornaments. *See also* Akshobhya; Herukas; Shakti; Vajrapani.

Herukabuddhas (Tibet) *see* Herukas.

Herukas *Herukabuddhas* (Buddhist, Lamaism; Tibet)
The Herukas have three heads and six arms and represent the wrathful form of masculine energy and are known as knowledge-holding deities. The Herukas and their saktis are the manifestations of the Dhyanibuddhas and their saktis. Some say that the energy of Heruka manifests the wrathful manifestation of the Herukas who also have a peaceful manifestation. The Herukas are Kamaheruka, who is green; Ratnaheruka, who is yellow; Padmaheruka, who is red; Vairocana, white or a reddish-brown hue; and Vajraheruka, who is blue. *See also* Dhyanibuddhas; Heruka; Ratnasambhava.

Herunub (Egypt) *see* Horus.

Herusmatauy *Ahy* (Egypt)
He is the son of Horus of Edfu and Hathor.

Hery-sha-duat (Egypt)
Underworld deity. He is in charge of the fields of Tuat. He has nine sekhtiu (field laborers) to do the work.

Heryan (Teutonic) *see* Odin.

Hes (Egypt) *see* Bast; Horus.

Hesahet (Egypt) *see* Hesat.

Hesaret (Egypt) *see* Hesat.

Hesat (Egypt)
Also known as: *Hesahet, Hesaret.*
Deified animal. This divine cow nurses the children of the deities. She is reputed to be the mother of the Mnevis bull.

Hesione (Greek)
Hesione is the daughter of Laomedon, the king of Ilium, and Strymo, the daughter of the river god Scamander. Hesione's siblings are Astioche, Cilla, Hicetaon, Clytius, Priam, Lampus, and Tithonus. The third wife of Telamon, the king of Salamis, she became the mother of Teucer. One of Heracles' eight deeds was to rescue Hesione from the belly of a whale, or a similar near death experience. Her father had reneged on a promise to Poseidon who had sent a sea monster to plunder the land. An oracle told him that to save the land, he would have to sacrifice his daughter. As the oracle was about to be fulfilled, Heracles came upon the scene. He promised to rescue Hesione if Laomedon would give him two beautiful horses that had been gifts from Zeus. He did so. Heracles rescued Hesione but Laomedon again reneged in paying his debts. Heracles left to gather six ships full of warriors and he returned to Ilium. In retaliation, he ravaged the city and killed all of Laomedon's sons except Priam. He also abducted the beautiful Hesione and gave her to his friend Telemon. This occurred long before the Trojan War. At a later time, Hesione's nephew Paris went to Greece on the pretext of bringing his aunt back to her homeland. He went off course to Sparta, fell in love with Helen, and triggered the events

which led to the Trojan War. Not to be confused with Hesione who was perhaps married to Nauplius, or Hesione (also known as Asia or Axiothea), the wife of Prometheus. *See also* Astioche; Heracles; Priam; Scamander; Telemon.

Hespere (Greek)
One of the Hesperides, she is the possible daughter of Atlas and Pleione. *See also* Atlas; Hesperides; Pleione.

Hespereia *Hespere* (Greek) *see* Hespere.

Hesperia (Greek) *see* Hesperides.

Hesperides (Greek)
Also known as: *Daughters of the Evening, Hesperia.*
Guardians. The Hesperides are the daughters of Nyx and Erebus or Phorcys and Ceto or Atlas and Hesperis or Zeus and Themis. The number of Hesperides varies from three to seven. Names attributed to the deities are Aegle, Hespere, Erytheis, Arethusa, Hesperusa and Hespereia. The Hesperides, who loved to sing, and the hundred-headed dragon or serpent, Ladon, were appointed to guard the trees which bore the Golden Apples. When Hera married Zeus the apples were a gift from Gaea, who personifies the earth. The treasured apples were stolen by Heracles or by Atlas on behalf of Heracles and the Ladon was slain by Heracles. The Hesperides transmuted themselves into trees and in this form were helpful in directing the Argonauts to a spring in the desert created by Heracles. Athena recovered the sacred fruit in Eurystheus and returned it to the garden. In another version of this myth, it is the Garden of Hesperides where the four daughters of Hesperos (Vesperus), who became the Evening Star, sing while watching the tree of Golden Apples which is guarded by Ladon. The Garden of Hesperides has been compared to the Garden of Eden. *See also* Atalanta; Calypso; Golden Bough; Golden Fleece.

Hesperis (Greek)
She is the daughter of Hesperos and spouse of Atlas. *See also* Atlas; Hesperides.

Hesperos (Greek) *see* Hesperides.

Hesperus (Greek) *see* Hesperides.

Hesperusa (Greek) *see* Hesperides.

Hest (Egypt) Another name for Isis.

Hestia *Histia* (Greek) Also known as: *Vesta* (Latin).
Goddess of fire. Guardian of home and hearth. Hestia is the daughter of Cronus and Rhea and sister of Zeus, Poseidon, Hera, Hades and Demeter. She vowed to remain a virgin even though she had marriage offers from her brother Poseidon and the god Apollo. It is said that Hestia remained aloof from the squabbles on Mount Olympus, and was the representative of the public hearth in the city as well as in private homes. Hestia was the first deity to build a house. She is personified by the life-giving hearth fire. In a purifying ritual used by her worshipers, a virgin walks around the farm holding a cock in her hands to ward off weeds and injurious insects. Her emblem is fire. Compare Hestia to the Japanese goddess of fire, Fuji, and Agni of India. *See also* Apollo; Cronus; Demeter; Hades; Hera; Poseidon; Rhea; Vesta (Roman).

Hesus (Gaul) *see* Esus.

Het-Hert (Egypt) An alternate spelling for Hathor (q.v.).

Hetch-Abehu (Egypt) *see* Assessors.

Hetchuti (Egypt) *see* Aai.

Hetemet-bau (Egypt) *see* Aaru.

Hetet-sept (Egypt) *see* Aani.

Hetmehit (Egypt) *see* Banebdedet.

Hettsui-no-kami (Japan) *see* Inari.

Heumac (Mexico) *see* Quetzalcoatl.

Heve (Babylonian) *see* Eve.

Heveidd Hen (Celtic) *see* Rhiannon.

Heviosso (Africa) *see* Xevioso.

Hey-Tau (Egypt) *see* Adonis.

Heybajra (Buddhist) *see* Lhamo.

Heyoka (Dakota People, North America)
A group of deities known as the Oppositres.

Hgnss (Teutonic) *see* Freyja.

Hiawatha (Mohawk People, North America) *see* Haio Hwa Tha.

Hiceton (Greek)
He is the son of Laomedon and Strymo. Hiceton advised the Trojans to return Helen of Troy to Menelaus so that a war would not develop. *See also* Helen; Laomedon; Menelaus; Strymo.

Hidimba (India) *see* Bhima (A).

Hidimbaa (India) *see* Bhima (A).

Hieromneme (Greek)
Her father is the river god, Simoeis, and her sister is Astyoche. *See also* Anchises; Astyoche; Simoeis.

Higona (San Cristobal) *see* Figonas.

Hiisi (Finnish)
In early times, Hiisi was a sacred grove and its spirit. Later Hiisi became a forest demon who became the devil. Hiisi and cohorts, Lempo and Paha, directed the axe which cut Vainamoinen. Lempo turned the blade, Paha directed the blow, and Hiisi pushed it through the veins. In another version, Hiisi is identical with Lempo, and he is a love deity. *See also* Kalevala; Vainamoinen.

Hika-po-loa (Hawaii)
In later times, this ancient god was worshiped as the three gods, Kane, Ku, and Lono (q.v.).

Hikawa-hime (Japan) *see* Kushi-nada-hime.

Hiko-hohodemi-no-mikoto (Japan) *see* Hikohohodemi.

Hikoboshi (Japan) *see* Kengiu.

www.ebook3000.com

Hikohohodemi *Hoho-demi, Hohodemi, Hiko-hohodemi-no-mikoto* (Shinto; Japan)

Also known as: *Hoori, Ho-wori.*

Hikohohodemi (Prince-Fire-Subside), is the great-grandson of the sun goddess Amaterasu. His parents are Ninigi (Prosperity Man) and Kono-Hana-Sakuya-Hime (Blossoms-of-the-Trees-Blooming-Princess). In early recordings of this myth, Hikohohodemi's two brothers are mentioned, Hoderi and Hosuseri (Prince-Fire-Flash), also known as Ho-no-Susori. Later writing refers to one brother, Hosuseri. Hikohohodemi became a hunter and Hosuseri took up fishing. They did well in their chosen fields but for some reason decided to switch occupations for a time. The experiment was not successful. Hosuseri returned the bow and arrows to his brother and asked him to return his fishing equipment. Hikohohodemi had lost Hosuseri's fishhook, so he substituted a different hook, made from three parts of his sword. Hosuseri refused the substitute, as his original hook had magical qualities that allowed him to reel in large quantities of fish. The brothers quarreled. Grief-stricken, Hikohohodemi, weeping at the seashore, was found by the god Shiho-tsuchi. He suggested that Hikohohodemi visit the bottom of the sea and implore the assistance of the great sea god O-Wata-Tsu-Mi in his search for his brother's hook. Hikohohodemi made the journey and fell in love with the god's daughter, Toyo-Tama-Bime (Abundant-Pearl-Princess) and forgot his quest for the missing hook. They married and he stayed in the luxurious palace of the sea god for three years. Remorse overcame him when he remembered the reason for his trip. O-Wata-Tsu-Mi called an assembly of all the fish in the sea. One fish sent word that she could not attend due to illness. Her name is the "Red Woman" in one tradition and in another "The Kuchime" (mouth-female). Messengers were sent to assist her to the meeting. The magic hook, caught in her throat, was causing her illness. O-Wata-Tsu-Mi gave his son-in-law the hook along with a set of instructions to follow when he returned the hook to his brother Hosuseri. He also gave him two jewels that controlled the tides, the Kangi (Tide Ebbing Jewel) and the Mangi (Tide Flowing Jewel). Hikohohodemi mounted the back of a monster shark for the trip to Japan to return the fishhook to his brother. Toyo-Tama-Bime and O-Wata-Tsu-Mi have been depicted in combination human and dragon form. For the continuation of his adventure from this point, *see* Hosuseri. For information about his relationship with his wife, *see* Toya-Tama-Bime. For details of the birth of Hikohohodemi and his brothers, *see* Ninigi. For details about the undersea palace and other sea deities, *see* O-wata-tsu-mi. *See also* Hoderi; Sengen.

Hikuleo (Tongan People, Polynesia)

Goddess of Pulotu (the underworld).

Hildisvini (Teutonic) *see* Ottar.

Hill of Healing (Teutonic) *see* Lyfjaberg.

Himavan (India) *see* Ganga.

Himavat (India) "Owner of Snow." *See also* Ganga; Parvati.

Himavati (India) *see* Kali.

Himeropa (Greek)

A siren. She is the daughter of Achelous and Calliope, Melpomene, Terpsichore or Sterope. *See also* Achelous; Calliope; Sirens.

Hina (A) (Oceanic)

Also known as: *Hina-Hau-One* (Earth-formed maiden), *Hina-Keha* (Bright Lady), *Hina-Titama* (Dawn-maiden), *Hina-uri, Hine, Hine-nui-te-po, Hine-Te-Ngaru-Moana* (Lady-of-the-Ocean-Waves), *Hooho, Ina, Sina.*

Goddess of Darkness. Goddess of death. Dawn-maiden. Patron of travelers. Patron of arts and crafts. Goddess of the Moon. Hina was created by the god Kane to be his wife. In that role her name is Hine-Hau-One. She is also known as "Hine-the-mitigator-of-many-things," indicating her multi-functional roles. Hina became the goddess of darkness when she discovered that her father had committed insist with her under the guise of being her husband. She is closely associated with the moon and as Goddess of the Moon in her full phases, she is known as Hina-keha. She is also known by this name as a goddess of childbirth. When she is in her fish form she is known as Hine-Te-Ngaru-Moana. For an additional myth, *see* Tangaroa. *See also* Hine-nui-te-po; Ku and Hina.

Hina (B) (Polynesia) *see* Hine.

Hina-arauriki (Oceanic)

She is the wife of Turi-a-faumea. *See also* Faumea.

Hina-famed-in-story (Hawaii)

Skilled as a practitioner of magic, she was the sister/wife of Tiki (q.v.).

Hina-opuhala-koa (Hawaii)

Goddess of coral and spiny creatures of the sea. She can appear as a woman or as a coral reef. *See also* Ku and Hina.

Hina-ula-ohia (Hawaii)

Goddess of the ohia-lehua forest. In her home on the northern side of Oahu, we find her as the mate of Ku-ka-ohia-laka, the god of canoe builders, and mother of the voyager, Ka-ulu. On Maui she is the spouse of the god of lightning, Kaha'i, and mother of the god of comets, Wahieloa, and grandmother of the goddess of the dance, Laka. In her shape as the sacred ohia tree, she protects and shelters Hi'i-lawe, the child of Kakea, and Kaholo and also the daughter of Po-kahi, Lau-ka-ieie. *See also* Hina (A); Laka.

Hindu — Creation Legend *see* Brahma; Kurma; Shiva.

Hine-ahu-one *Hine-Hau-One* ("Earth formed Maiden"), (New Zealand; Polynesia)

Also known as: *Hina, Hina-Titama* ("Dawn Maiden"), *Hine, Hine-nui-te-po.*

First mother. After Tane had tried many times to make his mother Papa become his wife and as many times she refused but sent him to other females, he finally found Hine-ahu-one. This goddess gave birth to Tikitohua who became the ancestor of birds. Then she conceived Tiki-kapakapa, the first human child of Tane. In some versions she is sister-wife of Maui or created by Tane. *See also* Hine-tu-a-maunga; Papa; Tane.

Hine-nui-te-po (Polynesia)

Also known as: *Hine, Hine-ahu-one, Hine-hau-one, Hine-i-tau-ira.*

Goddess of the night. Goddess of the underworld. She is the ruler of all ten levels of the afterworld, although some say she only rules the upper four. Her father is Tane. Tane created Hine or, as some say, Hine-i-tau-ira (the first woman), from sand and clay, then had intercourse with her. When she realized what he had done, she fled to the underworld in shame. There she became Hine-Nui-Te-Po, the "Goddess of Night." In another rendition, she was created by Tane in the same manner but she was called Hine-hau-one and they had a child named Hine-titama who was the dawn maiden. She is described in some tales as having red eyes, sharp teeth, the body of a man, hair like seaweed and a mouth like a barracuda. *See also* Hina; Miru; Rohe; Tane.

Hine-tu-a-maunga (New Zealand; Polynesia)
Possibly a goddess of water or reptiles. In his second attempt to have his mother Papa as his wife, she refused again and sent him to Hine-tu-a-maunga (the mountain maid) to take as a wife. She conceived but instead of a child she brought forth rusty water and reptiles. *See also* Hine-ahu-one; Hine-nui-te-po; Mumuhango; Papa; Rangahore; Tane.

Hi'iaka *Hi'iaka-i-ka-poli-o-Pele* (Hawaii)
Supreme patroness of the hula. Sister of the goddess of fire and the goddess of dance, Pele. All chants for hula ceremonies are named under Hi'iaka, even those dedicated to Ku and Hina, the ancestral couple. Hi'iaka is the dear friend of the dancer Hopoe. *See also* Ku and Hina; Laka; Pele.

Hinlil (Assyria, Babylonia) Goddess of crops and grain.

Hino *Heno, Hinu, Hinun* (Iroquois People, North America)
Also known as: *The Thunderer.*
Sky and thunder god. Hino is the husband of the Rainbow and guardian of the Heavens. He is beneficial to humans but doesn't like them invading his domain. Among his many assistants are Oshadagea, the Dew Eagle, and Keneu, the Golden Eagle. Some say his brother is the West Wind. Hino's opponent is a great serpent. *See also* Adekagagwaa.

Hi'ona (San Cristobal) *see* Figonas.

Hinu (Iroquois People, North America) *see* Adekagagwaa; Hino.

Hinu-ua (Polynesia) *see* Atea.

Hinun (Iroquois People, North America) *see* Hino.

Hiordis (Teutonic) *see* Hjordis.

Hippasus (A) (Greek)
He is the father of Actor, the Argonaut. *See also* Actor (C).

Hippasus (B) (Greek)
Leucippe, the daughter of Minyas, is his mother (q.v.).

Hippe (Greek)
Hippe is the daughter of Cheiron and the mother of Melanippe. *See also* Aeolus (A); Aeolus (B); Cheiron; Melanippe.

Hippocoon (A) (Greek)
King of Sparta. He is the son of Oebaulus, king of Sparta, and Gorgophone, the widow of Oebalus' brother, Perieres, or Bateia. When Hippocoon refused to purify Heracles after he killed Iphitus, Heracles killed Hippocoon and his twelve sons. *See also* Gorgophone.

Hippocoon (B) (Greek)
He was the companion of Aeneas when he travelled to Italy.

Hippocrene (Greek)
Hippocrene, a deified fountain dedicated to the Muses, is located at the foot of Mount Helicon. It began to flow when the ground was struck by the hoofs of the winged horse, Pegasus. *See also* Muses; Pegasus.

Hippodamas (Greek) *see* Calydonian Boar Hunt.

Hippodameis (Greek) *see* Anchises.

Hippodamia (A) *Hippodameia* (Greek)
She is the daughter of Adrestus, the King of Argo, or Butes and Amphithea. Her siblings are Aegialeia, Aegialeus, Argeia, Cyanippus and Deipyle. She is the spouse of Peirithous and mother of Polypoetes. At her wedding a violent fight erupted between the Lapiths and the Centaurs. *See also* Adrestus; Centaurs; Cyanippus; Peirithous; Polypoetes.

Hippodamia (B) (Greek)
She is the daughter of Oenomaus and Evarte (who is the daughter of Acrisius and Eurydice). Her brother is Leucippus, who was killed when he dressed as a girl in an attempt to become acquainted with Daphne. Hippodamia became the spouse of Pelops, the king of Lydia and Pisa in Elis. She is the mother of Alcathous, Astydameia, Atreus, Chrysippus, Copreus, Lysidice, Nicippe, Pittheus, Thyestes and Troezen. Hippodamia had many suitors. Her father decided to hold a chariot race and give the winner the prize of his daughter. Hippodamia had other plans. She bribed the charioteer Myrtilus to fix the race so the winner would be Pelops. Hippodamia killed herself after murdering Chrysippus, thought to be the son of Pelops by Axioche or Astyoche. In other renditions it is offered Chrysippus' his half-brothers Atreus and Thyestes were responsible for the murder. *See also* Atreus; Chrysippus; Eurydice (C); Oenamaus; Pelops.

Hippodamia (C)
She is the daughter of Anchises, the king of Dardania who after being struck by Zeus' thunderbolt limped for the rest of his life. She is the sister of Aeneas and Lyrus (his father is Anchises but his mother is Aphrodite). Hippodamia is the wife of the valiant Alcathous, the son of Aesyetes, who was killed by Idomeneus in the Trojan War.

Hippodamus (Greek)
His parents are Agenor, the son of Pleuron and Xanthippe, and Epicasta, the daughter of Calydon and Aeolia.

Hippolochus (A) (Greek)
He is the son of Bellerophon and Philonoe and the father of Glaucus. *See also* Bellerophon; Glaucus.

Hippolochus (B) (Greek)

Hippolyte (A) (Greek)
Queen of the Amazons. She is the daughter of the god of war, Ares, and Otrera the Amazon queen. Her siblings are Antiope (Melanippe) and Penthesileia. She could be the mother of Hippolytus. One of Heracles' labors (his ninth) was to retrieve Hippolyte's magic girdle. It had been given to her by Ares. It is thought that after losing it, Hippolyte either died of a broken

www.ebook3000.com

heart, or was murdered by Heracles. *See also* Acastus; Admete; Amazons; Ares; Frejya (Norse); Hippolytus (A); Penthesileia.

Hippolyte (B) (Greek)
Hippolyte is the daughter of Creteus. Her siblings are Amythaon, Pheres, and Promachus. She could have been the wife of Acastus. Hippolyte was attracted to Pelus but he rejected her advances. The spurned women lied to Acastus and said that Peleus had attempted to seduce her (*see* Acastus for details). There is a possibility that Peleus murdered Acastus. *See also* Acastus; Admete; Ares; Amazons; Peleus; Promachus.

Hippolytus (A) (Greek)
Also known as: *Auriga* ("The Charioteer" constellation), *Virbius.*
Deified mortal. He is the son of Theseus and possibly the Amazon queen Hippolyte. Phaedra, the daughter of Minos, the king of Crete, married Theseus, the hero king of Athens. Married or not, Phaedra was attracted to and fell in love with Hippolytus. He rebuffed her advances. She went to her husband and claimed that Hippolytus had attempted to seduce her. Theseus believed his spouse. Hippolytus had to flee the husband's wrath. Poseidon's sea-calves interrupted his flight, turned over his chariot, and caused his demise. When he reached heaven he was supposed to become the constellation Auriga. Instead, through Artemis' efforts he became the deity Virbius. *See also* Acamas (A); Adonis; Giants; Hippolyte (A); Phaedra.

Hippolytus (B) (Greek)
He is the giant son of the earth personified, Gaea. His giant siblings are Agrius, Alcyoneus (who stole the sun Helios' cattle), Gration (killed by Heracles during the battle of the Giants and the gods), Mimas (killed in the same battle), Polybotes (buried by the sea god Poseidon), Porphyrion (the leader of the Giants, killed by Heracles in the battle) and Thoon (killed in the same battle as his brothers). Hermes, the messenger of the gods, wearing his hat of invisibility, killed Hippolytus in the same war of the Giants and the gods. *See also* Agrius; Alyconeus; Gaea; Giants; Helios; Hermes; Polybotes; Poseidon.

Hippomachus (Greek)
His father is the militant Trojan, Antimachus, and his siblings are Hippolochus and Peisander.

Hippomedon (Greek)
One of the Seven against Thebes. He is the father of Polydorus by Evanippe. *See also* Adrestus; Evanippe; Polydorus.

Hippomenes (Greek)
He is the son or possibly the father of Megareus and Iphinoe. Either Hippomenes or Melanion married Atalanta of Boeotia, the daughter of King Schoeneus.

Hippona (Greek)
Goddess of horses.

Hipponoos (A) (Greek) *Hipponous, Hipponus* (Greek)
Another name for Bellerophon (q.v.).

Hipponoos (B) (Greek) He is the son of Priam.

Hipponoos (C) (Greek)
He was the last Trojan killed by Achilles before Achilles died.

Hipponoos (D) (Greek)
Astynome is his wife and Capaneus and Periboea, his children.

Hipponus (Greek) *see* Hipponoos.

Hippopotamus *see* Her-Tchema; Horus.

Hippotades (Greek)
This is an epithet for Aeolus, the god of the winds (q.v.).

Hiranya-kasipu *Hiranya Kasyapu, Hiranyakashipu, Ravana* (Brahmanic, Hindu; India)
Hiranya-kasipu, "gold eye," is a giant king of the demon Daityas and chief of the Asuras. He held a boon of invulnerability granted to him by Brahma. He was the brother of Hiranyaksha, the demon who drowned the earth. According to some, Hiranya-kasipu set himself up as the sole object of worship, in place of the gods, but his son Prahlada remained a fervent supporter of Vishnu, and all his father's attempts to do away with him were in vain. In disbelief at Prahlada's claim that Vishnu was omnipresent, Hiranya-kasipu kicked a pillar with his foot. When the pillar fell, Nara-Simha, the lion-headed human who was the fourth avatar of the god, appeared and tore him to pieces. Hiranya-kasipu's mate is Mahallika, who according to some sources is the daughter of Prahlada. His demon-serpent son, Hrada, who practiced austerities, was known for stealing people's sacrifices from the gods. Vishnu was sent by the gods to lure him and his cohort demon friends away from the light of the Veda to the darkness of ignorance. *See also* Asuras; Brahma; Daityas; Diti; Hiranyaksa; Kalanemi; Mandodari; Nara-Simha; Prahlada; Ravana; Vamana; Vishnu.

Hiranyagarbha *Brahma, Narayana* (Vedic, Brahmanic; India)
He is the creator god of the heavens, earth, all that lives, and all the waters, including Rasa, the mythological river that encircles the earth and the atmosphere. His name literally means "Golden Germ." In one legend, he is the golden egg produced by the primal waters. From this egg the creator god Prajapati was born. In other legends Hiranyagarbha is formed in the first egg, and becomes the first male, Brahma (q.v.). *See also* Brahma; Pani (B); Prajapati.

Hiranyakashipu (India) *see* Hiranya-kasipu.

Hiranyaksa *Hiranyakasipu, Hiranyaksha* (Brahmanic, Hindu; India)
A Daitya. A giant demon who was helped by Brahma's strength and a protecting boon until he became ruler of the universe by toppling Indra from his throne, driving the gods from the heavens, and drowning the earth. Hiranyaksa, who was Ravana's first incarnation, was vulnerable only to the boar. In time, he was destroyed by the boar Varaha, Vishnu's avatar. *See also* Daityas; Diti; Hiranya-Kasipu; Ravana; Varaha.

Hiranyaksha (India) *see* Hiranyaksa.

Hiranyapura (India)
The city of the Daityas, Hiranyapura is sometimes located beneath the ocean. Other times, it breaks free and moves under the earth or sails through the air. *See also* Daityas.

Hiribi (Mesopotamia) *see* Hiribi.

Hirihbi (Mesopotamia; Syria, Ugarit)
He is referred to as a god of summer in some myths and a Sumerian king in other myths. *See also* Nikkal; Yarikh.

Hirnakess (India) A giant. *See also* Varaha.

Hiro (Polynesia, Tahiti)
Afterworld deity. In charge of the underworld of the Areoi priests. Similar to Urutaetae.

Hirugo (Japan) *see* Hiruko.

Hiruko *Hirugo* (Shinto as Hiruko, Buddhist as Ebisu; Japan)
Also known as: *Ebisu.*
Solar deity and god of the health of children. The background of Hiruko (meaning child leech) is debatable. In some traditions, he is the oldest child of Izanagi and Izanami and was born in the shape of a jellyfish. This would make him the first god (kami) born through intercourse. He would also be the brother of the great sun goddess Amaterasu, the moon ruler Tsuki-Yomi, and the storm god Susanawo. At birth, his parents were displeased with his form, so they placed him in a raft and let him drift away. His raft beached at Ebisu Shore, thus he became known as Ebisu. He was deaf and unable to hear the summons for the other deities to assemble and was the only deity not in attendance. Other scholars feel that Hiruko was a sun god who was ignored for political reasons by the followers of Amaterasu. In this capacity, he is the grandson of Amaterasu and the brother of Ninigi. In later interpretations as Ebisu, he was known as a god of fishermen. His father was Daikoku, the god of labor. Both became deities of the Shichi Fukujin (seven Japanese deities of happiness). *See also* Ebisu; Izanagi and Izanami; Ninigi; Shichi Fukujin; Tsuki-Yomi.

Hisa-me (Japan) *see* Shiko Me; Yomi.

Hisakitaimisi (Cree People, North America)
The Controller of Life.

Hischen (Maya People, Yucatan) *see* Chibirias; Icona.

Hiscilla (Greek)
She is the daughter of Myrmidon, the wife of Triopas and the mother of Erysichthon, Iphimedeia, Messene and Phorbas. *See also* Iphimedeia (A); Triopas.

Histia (Greek) *see* Hestia.

Hitchi (Hitchiti People, North America)
Deified plant. The first tobacco plant.

Hiuke (Norse; Teutonic)
Also known as: *Yuke.*
A moon god. Waxing moon. Hiuke, the waxing moon and Bil, the waning moon, always accompany Mani, the moon, on his rounds. *See also* Mani.

Hiyoyoa (New Guinea)
Land of the dead. Said to be ruled by Tumudurere and his wives and children.

hJamdpal (Tibet) *see* Manjusri.

hJig-rTen-Gsum-Rgyal (Tibet) *see* Trailokyavijaya.

Hjordis *Hiordis* (Teutonic)
In some myths, she is the second wife of Sigmund, the son of Volsung. He disposed of his first wife, Borghild, for killing his first son, Sinfiotli. Hjordis is a young princess daughter of Englimi, the King of the Islands. One of her suitors was king Lygni of the Hundling race. When she agreed to marry old Sigmund, Lygni declared war on Sigmund. Sigmund fought well but Odin interfered and shattered the sword Sigmund had pulled from the tree trunk. The defenseless Sigmund was wounded to the death by his enemies. Hjordis hid from Lygni, who wanted to claim her, and tried to save Sigmund. Sigmund knew it was Odin who indirectly killed him and all he wanted was for Hjordis to gather up the shattered sword and save the fragments. Hjordis and her maid were saved by Alf. Some say she became the wife of Alf and later bore a son, Sigurd. *See also* Alf; Borghild; Sigi; Sigmund; Sigurd.

Hkum Yeng (Burma)
A nat (spirit) who guards the villages of the Wa of Burma. He was propitiated by human heads from head-hunting excursions. *See also* Nats.

Hlamo *Hlamos* (Tibet) *see* Ganda; Shakti; Tara (B).

Hler (Teutonic) Underworld deity. *See also* Oegir; Ymir.

Hlidskialf (Teutonic) *see* Hlidskjalf.

Hlidskjalf *Hlidskialf, Hlithkjalf, Lidskialf, Lidskjalf* (Teutonic)
This is the throne where Odin sits when he surveys the world. *See also* Gladsheim; Odin; Sovabek; Valaskjalf.

Hlin *Hlina* (Teutonic)
The tears of mourners are kissed away by Hlin, the goddess of consolation. Hlin is also the second attendant of Frigga. *See also* Frigga; Fulla.

Hlithkjalf (Teutonic) *see* Hlidskjalf.

Hlodr (Teutonic) *see* Lodur; Loki.

Hlodyn (Teutonic)
This giant woman is sometimes known as the mother of Thor (q.v.). She is also known as Jord.

Hlooyn (Teutonic) *see* Jord.

Hlora (Teutonic) *see* Thor.

Hloride (Teutonic) *see* Thor.

Hloridi (Teutonic) *see* Thor.

Hlorrida (Teutonic) *see* Thor

Hlorridi (Teutonic) *see* Thor.

Hmin Nat (Burma)
This is a demon who causes intermittent fevers in travelers. The Hmin Nat also drives mortals insane. *See also* Hkum Yeng; Nats.

Hngss (Teutonic) *see* Freyja; Hnossa.

Hnikar (Teutonic) *see* Odin.

Hnitbjorg (Norse; Teutonic)
This is the mountain home of the giant Sattung where he hid the mead of poetry made from Kvasir's blood. He is associated with Fjlar and Galar. *See also* Sattung.

www.ebook3000.com



Fig. 2.5 *Hands circle to gather Earth Chi.*

Microcosmic Orbit

The Microcosmic Orbit Meditation awakens, circulates and directs Chi through the ‘Governing Channel’, which ascends from the base of the spine up to the head and the ‘Functional’ or ‘Conception Channel’, which runs from the tip of the tongue down the middle of the torso to the perineum. Dedicated practice of this ancient esoteric method eliminates stress and nervous tension, energizes the internal organs, restores health to damaged tissue and builds a strong sense of personal well being.

The Microcosmic Orbit is the foundation of Cosmic Healing Chi Kung practice. Each new practice is dependent upon the high quality of your meditations and your ability to perfect the Microcosmic Orbit. In order to master Cosmic Chi Kung, one must practice meditation daily. The meditations in the Microcosmic Orbit also strengthen the ‘Original Chi’ and teach you the basics of circulating Chi. They allow the palms, the soles of the feet, the mideyebrow point and the crown to open. These specific locations are the major points where energy can be absorbed, condensed and transformed into fresh new life force.

● **1.** Focus on the Lower Tan Tien (the area where the Original Chi is stored, between the navel, kidneys and sexual organs). Feel the pulsing in this area, observe whether this area feels tense or relaxed, cool or warm, expansive or contracting. Notice any sensations of Chi: tingling, heat, expansiveness, pulsing, electric or magnetic sensations. Allow these to grow and expand. Then let this energy flow out to the Navel Center.

Hnos (Teutonic) *see* Hnossa.

Hnoss (Teutonic) *see* Hnossa.

Hnossa *Hngss Hnos, Hnoss,* (Teutonic) *see* Aesir; Freyja.

Ho-deri (Japan) *see* Hoderi.

Ho-hsien-ku *Ho-sien-ku* (China)
Also known as: *Damsel Ho, Kasenko* (Japan)
She is the only female in the group known as the Eight Immortals. Ho-hsien-ku went to heaven during daylight hours. A mortal damsel known in Taoist belief as Ho was said to have gone to heaven during daylight hours. One of the Eight Immortals, the god of barbers, Lu Tung-pin gave Ho-hsien-ku the peach of immortality. As Kasenko, she feeds on mother of pearls. Ho-hsien-ku is shown as an elaborately dressed woman with a lotus on her shoulder. Sometimes she is depicted as a girl wearing a lotus flower on her shoulder or with a Chinese lute. She is generally shown with Han Hsaing-tzu. *See also* Arhats; Eight Immortals; Lu Tung- pin.

Ho-masubi (Japan) *see* Kagu-tsuchi.

Ho-no-suri (Japan) *see* Hosuseri.

Ho-no-susori (Japan) *see* Hikohohodemi; Hoderi.

Ho Po (China)
Also known as: *Nine Songs.*
One of the nine heroes. God of the Yellow River. *See also* Nine Songs.

Ho Shen (China) God of Fire. *See also* Tsao Shen.

Ho-sien-ku (China) *see* Ho-hsien-ku.

Ho-suseri (Japan) *see* Hosuseri.

Ho-wori (Japan) *see* Hikohohodemi.

Hoa (Chaldean) *see* Aa; Aos; Ea.

Hoakils (Tierra del Fuego)
Hoakils is a spirit who grants power to the Yakamouch (shaman). *See also* Yakamouch.

Hoard Thoughts (Japan)
The universe was in darkness until Hoard Thoughts came up with a successful plan to woo the sun goddess, Amaterasu, from her cave. *See also* Amaterasu.

Hobal (Arabic, Indo-Persian) *see* Abel; Hab'al.

Hobnel (Maya People, Yucatan) *see* Hobnil.

Hobnil *Hobnel* (Maya People, Yucatan)
This food god and god of plenty, is one of a triad with Chac Mol and Ah-Kluic. *See also* Chac Mol.

Hocereu Wahira (Algonquin, Chippewa, Cree, Nascopi People, North America).
Disease-Bringer.

Hod (Teutonic) *see* Hodur; Odin.

Hod-Dpag-Med (Tibet) *see* Amida; Amitabha.

Hodar (Teutonic) *see* Hodur.

Hodd-Dropnir (Teutonic) *see* Mimir.

Hodd-Mimer (Teutonic) *see* Mimir.

Hoddmimir's Wood (Teutonic) *see* Yggdrasil.

Hoddrofnir (Teutonic) *see* Mimir.

Hoder (Teutonic) *see* Hodur.

Hoderi *Ho-deri* (Shinto; Japan)
Also known as: *Ho-no-susori.*
Hoderi is the son of Kono-Hana-Sakuya-Hime (Blossoms-of-the-Trees-Blooming-Princess) and Ninigi (Prosperity Man). His brothers are Hikohohodemi (Prince-Fire-Subside) and Hosuseri (Prince-Fire-Flash). In some early renditions the three brothers are referred to as triplets. In later myths, Hoderi was not included as one of Kono-Hana-Sakuya-Hime's sons. When the tales involve Hosuseri and Hikohohodemi they are called twins. Sometimes, Hosuseri is called the elder son. For details surrounding his birth, *see* Ninigi. In the Ninigi version, the three children are born at the same time. *See also* Hikohohodemi; Hosueri; Sengen.

Hodir (Teutonic) *see* Hodur.

Hodr (Teutonic) *see* Hodur.

Hodsrun (Tibet) *see* Kasyapa (B).

Hodur *Hod, Hodar, Hoder, Hodhr, Hodir, Hodr, Hotherus.* (Norse; Teutonic)
Also known as: *Bjorno-hoder.*
God of darkness. God of winter. The blind god of darkness and winter, Hodur accidentally killed Balder with an arrow made of mistletoe. The accident was instigated by the trickster Loki. In turn, in an act of revenge, Hodur was killed by Vali. (With innocent, pure Balder alive, evil could not prevail.) Hodur is one of the 13 major deities in the mythology of the "Eddas." The other deities are Odin, Thor, Njord, Freyja, Balder, Tyr, Heimdal, Bragi, Forseti, Vidar, Vali and Ull. Hodur will return at Ragnarok, the destruction of the universe. *See also* Balder; Boe; Ragnarok; Vali (A).

Hoener (Teutonic) *see* Henir; Loki.

Hoenir (Teutonic) *see* Henir.

Hofud (Teutonic)
This sword, used by Heimdall, is one of the treasures of the Aesir. *See also* Aesir; Heimdall.

Hofvarpir (Teutonic) *see* Gna.

Hofvarpnir (Teutonic) *see* Gna.

Hogni (Teutonic) *see* Sigrun.

Hoho-Demi (Japan) *see* Hikohohodemi.

Hohodemi (Japan) *see* Hikohohodemi.

Hoita (Mandan Indians, North America)
Spirit. Name for Spotted Eagle.

Hokewingla (Dakota Indian) The Turtle-man in the moon.

Holda *Holla, Hulda, Hulle* (Norse; Teutonic)
Also known as: *Frau Holle, Frau Venus.*

Goddess of weather. Probably the same as Frigga. In this case Holda is the dispenser of gifts and controllor of weather. She gave flax to mortals and taught them how to use it. This goddess lived in a cave and was then known as Frau Venus. She is ugly and long toothed, with long, shaggy hair. In her role as an evil deity, she is opposed by Bertha (q.v.). *See also* Frigga.

Holdja (Estonia) *see* Domovoi.

Holla (Teutonic) *see* Holda.

Holle (Teutonic) *see* Holda.

Holler (Teutonic) *see* Ull.

Homa *Haoma* (India)
A sacred drink similar to Soma, thought by some to be a dark beer or a port wine. *See also* Haoma; Soma.

Hometeuli (Mexico)
Creator. Known as the "First Cause," he created the universe. His residence is called Homeyoco (also known as Homeiocan) and is the place of the Trinity whose word created Cipatonal and Xumio, gods who lived before the deluge. *See also* Ciptonal.

Homosubi (Japan) *see* Kagu-tsuchi.

Homshuk (Maya) *see* Chalucas.

Homunculus (Greek)
Spirit. A tiny man, with miraculous power, he was manufactured rather than born. *See also* Dwarfs.

Homusubi (Japan) *see* Kagutsuchi.

Hone (Teutonic) *see* Henir.

Honga (Osage People, North America)
The Honga are earth people who live below the ground.

Honir (Teutonic) *see* Henir.

Honochenokeh (Iroquois People, North America)
Spirits of goodwill. Invisible Helpers.

Hoodmimir's Wood (Teutonic) *see* Ragnarok.

Hoof-Tosser (Teutonic) *see* Gna.

Hooho (South Sea Islands) *see* Hina.

Hoori (Japan) *see* Hikohohodemi.

Hopleus (Greek)
He is the son of Poseidon and Canace. For the names of siblings, *see* Canace.

Hor (Greek) *see* Horus.

Hor Bebdetite (Egypt) *see* Behdety; Horus.

Hor Behdetite (Egypt) *see* Behdety.

Hor Merti (Egypt) *see* Haroeris.

Hor-Nubti (Egypt) *see* Horus.

Hor-Sa-Iset (Egypt) *see* Harsiesis.

Hora-Galles *Tora-Galles* (Lapp) Thunder god.

Horae *Horai* (Greek)
Also known as: *Carpo, Dike, Eirene, Eunomia, Karpo, Thallo.*
Goddess of the seasons. These three sisters, Dike (justice), Eirene (peace) and Eunomia (lawfulness), are the daughters of Zeus and Themis. Their siblings are Astraea, the goddess of justice (also known as Dike), and the deities of destiny, the Moirai. As well as supervising the Olympic Games, the Horae guard the entrance to heaven and to Olympus. They are also Hera's attendants. *See also* Aristaeus; Hera, Moirai.

Horaematawy (Egypt) *see* Horus.

Horaios (Gnostic)
One of the seven ruling spirits created by the god Ophiomorphus, the serpent son of Ialdabaoth. They are called the Archons. *See also* Archons.

Horakhti (Egypt) *see* Horus.

Horakhty (Egypt) *see* Horus.

Horchia (Chaldea) *see* Aretia.

Horea (Egypt) She is the wife of Seth.

Horkhenti Irti (Egypt) *see* Haroeris.

Hormazu (Zoroastrian; Persia)
One of the alternative names for Ahura Mazda.

Hormerti (Egypt) *see* Horus.

Hormothoe (Greek) *see* Harmothoe.

Hormusda (Mongol) *see* Asuras (India).

Horn (Teutonic) *see* Aesir; Freyja.

Horn of Victory (India) *see* Shankha.

Hornbori (Teutonic) *see* Dwarfs.

Horomazes (Greek) *see* Ahura Mazda.

Horos (Greek) *see* Horus.

Horse-Face (China) *see* Ma-Mien; Nui-Y'ou.

Horseface (China) *see* Ma-Mien.

Horses of the Aesir (Teutonic) *see* Animals.

Horta (Etruscan) She is a goddess of agriculture.

Horus *Haroeris* (Greek), *Horos* (Egypt, Greek)
Also known as: *Aroueris, Aten, Har, Harocrates, Harpokrates* (Son of Horus), *Herdesuf, Herhkhty, Hermakhis* ("Horus on the Horizon"), *Heru Khent an Maa, Heru Khuti, Heru Murti, Herunub, Heru Sam Taui, Heru Ur, Hor, Horakhti, Hyperion* (Greek).
"Harpooner." A solar and sky-god. He is also a falcon god who protects the earth with his wings. Called Hor by the Egyptians and Horos by the Greeks, but known by the Latin form of his name, Horus is the son or sometimes the brother of Osiris and Isis. Isis, in the form of a hawk, is said to have conceived Horus as she fluttered above her husband's corpse in the swamps. He was called Harpokrates as a youth. Worshiped in different ways and places, he is always represented as a falcon or falcon-headed. Horus is one of the principle Egyptian deities.

www.ebook3000.com

The living king is always regarded as Horus incarnate. Horus is known by various other names. Her-tchema as a hippopotamus, Horaematawy, Horakhty, Hormerti, Hor-Nubti, Heru, Horus-Aah, Horus-Behdety, Horus Khenty En Maatyu, Heru-Pa-Khret, Har-End-Yotef, Har-Pa-Neb-Taui (the blind Horus) and many others. The cult of Horus originated either at Behdet or Nekhen. Behdet was located in the Western Delta near Imarut. In Behdet, Horus was presented as a war-like god with the head of a hawk (or falcon) who carried bows and arrows and was known as Horus of Behdet. In predynastic Nekhen, on the west bank of the Nile, the chief god was Nekheny ("the Nekhenite"), a falcon who wears two long plumes on his head. He later assimilated with Horus, who became Horus Nekhenite. Horus is the father of Imsety who was given androgynous features and was represented in the Middle Kingdom as a beardless man with the yellow skin color of a woman. Khenty-Khet, the crocodile god at Athribis, assumed the form and nature of Horus. Horus waged war against the murderers of his father (the forces of darkness). His uncle Seth, one of the villains, in the form of a black pig, injured Horus' eye. The "Eye of Horus" fought the enemies of light and was seen as fire. One of Horus' eyes is seen as the sun and the other as the moon. In another myth, Horus battles the hippopotamuses and crocodiles of Seth in defense of the sun god Ra. Seth rips out the eye of Horus. He retalitates by yanking off Seth's testicles, forcing him to return his eye. After the Fifth Dynasty, Horus was overtaken by the sun-god Ra. The falcon Horus is the emblem of royal authority. As a young man, Horus is shown with a side-lock of hair and his finger to his mouth. The spear of Horus is a weapon blessed by the goddess Neith and used by royalty. Replicas of the spear were often placed with the dead as protection en route to the next world. Horus is associated with Apollo. Compare Horus to the Vedic deities, Indra and Vishnu. *See also* Aamu; Ab-ta; Amen; Ament; Aten; Atum; Banebdedt; Bast; Bes; Hapy (A); Harakhtes; Harendotes; Harpokrates; Harsaphe; Harsiesis; Hartomes; Hathor; Her-Pest; Hera; Isis; Khenty-Khet; Min; Neith; Osiris; Qebhsneuf; Ra; Set; Sopdu; Thoth.

Horus-Aah (Egypt) *see* Horus.

Horus-Behdety (Egypt) *see* Horus.

Horus Khenty En Maatyu (Egypt) *see* Horus.

Horus-Pa-Kret (Egypt) *see* Horus.

Hoshang and Takhmoruw (Iranian, Persian)
Also known as: *Haoshyangha and Tahmouras, Husheng and Tamuras, Husheng and Tamurath.*

Hoshang is the grandson of Mashya and Mashyoi, the son of Siyamek and the father of Takhmoruw. Siyamek was killed by an evil Div (demon). Determined to avenge his father's death, Hoshang slayed two-thirds of the world's demons and proceeded to establish a peaceable kingdom. The art of blacksmithing is attributed to Hoshang. He also invented the axe, saw and hoe. He discovered a method to distribute water to fertilize the fields. He domesticated animals and made clothing from the hides of wild animals. His son, Takhmoruw, succeeded him after his death. (In the Avestic tradition, Takhmoruw, called Takhma Urupi, is not the son of Hoshang, but is his successor. In earlier texts, Takhmoruw is known as the son of Vivanghvant and a brother of Yima.) He taught his people to weave and spin. He cast a spell on the evil Ahriman, changed him into a horse and rode him around the world, some say for thirty years. While he was on tour, the evil Divs revolted. Takhmoruw returned with a massive club, and with the assistance of the good Divs, engaged in a short but dramatic battle. Takhmoruw tied up two-thirds of his enemies by magical means, hit the rest of them over the head with his club and tied them together. They begged for their lives and in return promised the king that they would teach him a beneficial art. He relented in order to learn their secret. They in turn taught him how to write and he became a learned man. Takhmoruw is also known as the "jailer of demons" (div-band). In other legends, Hoshang is known as the grandson of Gaya Maretan (q.v.). *See also* Ahriman; Daevas; Mashya; Yima (also known as a first king).

Hosho-Nyorai (Japan)
The Buddha of goodness and beauty, he is also known as Ratnasambhava (q.v.).

Hosuseri *Ho-no-suri, Ho-suseri* (Shinto; Japan)
Also known as: *Ho-deri.*

Fisherman. Hosuseri (Prince-Fire-Flash) is the great grandson of the sun goddess Amaterasu. His parents are Ninigi (Prosperity Man) and Kono-Hana-Sakuya-Hime (Blossoms-of-the-Trees-Blooming-Princess). His brothers in early records are Hoderi and Hikohohodemi (Prince-Fire-Subside). Later myths generally do not mention Hoderi. Hosuseri was a famed fisherman and Hikohohodemi was a hunter. They decided to exchange occupations for a time. The experiment did not work to their advantage. Hosuseri returned his brother's bow and arrows. Hikohohodemi had lost his brother's magic fishhook. He broke his sword into three pieces and fashioned imitations. They were not acceptable to Hosuseri, for his magic fishhook had allowed him to catch large quantities of fish. The brothers quarreled, and Hikohohodemi was remorseful. A series of events led him on a lengthy undersea quest for the fishhook. Three years later, with the assistance of the sea god O-Wata-Tsu-Mi, the hook was retrieved. Hikohohodemi returned to the upperworld (Japan) to return it to his brother. The sea god had given Hikohohodemi two jewels that controlled the tides, known as the Kangi (Tide-Ebbing-Jewel) and Mangi (Tide-Flowing-Jewel). O-Wata-Tsu-Mi had advised Hikohohodemi that if his brother became angry and tried to attack him, to use the Mangi to swell the waters and drown him. He cautioned that if Hosuseri repented, he should use the Kangi to repeal the tide. Hosuseri was not satisfied. His rice fields had failed because his brother kept them flooded with the Mangi and Hikohohodemi's fields had prospered. Jealous, he continued to badger his brother. Finally, to cease the strife, Hikohohodemi utilized the Mangi and caused the waters to cover his brother completely. When Hosuseri promised to pay homage to his brother, Hikohohodemi used the Kangi to allow the tide to ebb and gave his brother his freedom. Kangi and Mangi symbolize divine authority and life force. For details about his inauspicious birth, *see* Ninigi. For details about the retrieval of the magic fishhook, *see* Hikohohodemi. *See also* Amaterasu; Hoderi; O-Wata-Tsu-Mi; Sengen; Toyo-Tama-Bime.

Hotar (India) "The Invoker." *See also* Agni.

Hotei *Hotei-Osho* (Buddhist; Japan)
Also known as: *Pusa.*
Hotei is one of the Shichi Fukujin (seven deities of happiness). A fat god of laughter and happiness, he often carries a bag of treasures which he bestows on those who never worry about troubles. He is of Chinese origin. Pusa is a common European appellation for Hotei. Hotei is usually shown with a large naked stomach, bald headed and with large ear lobes (symbol of omniscience). He holds a hand-screen and a large sack, and is often in the company of children. To the Zen believers, Hotei is depicted as a happy wandering monk who represents the carefree life of one who has found peace through the study of Zen. Comparable to Miroku-Bosatsu, the Japanese future Buddha, Pou-tai, the Chinese god of contentment, Mi-Lo Fu, the Chinese future Buddha, and Maitreya, the Sanskrit fourth or coming Buddha. *See also* Shichi Fukujin.

Hotei-Osho (Japan) *see* Hotei.

Hoth (Teutonic) *see* Loki.

Hothbrod (Teutonic) *see* Miming.

Hotherus (Teutonic) *see* Hodur.

Hotoru *Hoturu* (Pawnee People, North America)
Deified bird. Spotted Eagle Spirit. Sometimes, he is called a god of winds.

Hotu-papa (Polynesia) This is another name for Papa (q.v.).

Hotua Poro (Samoan) *see* Incubus (Medieval Europe).

Hou-Chi *Hou Ji, Hou-Tse* (China)
Also known as: *Prince Millet.*
Harvest deity. A hero of royal birth, Hou-Chi taught the Chinese people the principles of farming and became one of the immortals. Hou-Chi is considered to be the founder of the dynasty of Chou, which began in about the twelfth century B.C.E., the time of the beginning of the large feudal estates. He was believed to have been a miraculously born descendant of Huang Ti. Generally this deity was worshiped by peasants. Some say Celestial Prince Liu replaced Hou-tsi who was then either a god of soil or crops. He is depicted as an old man with millet stalks growing from his head. Hou-Chi was usurped by Liu (Celestial Prince Liu). *See also* Shen Nung (who resembles Hou-Chi).

Hou Ji (China) *see* Hou-Chi.

Hou-T'u
Also known as: *Hou-T'u nai nai* (China).
God of the soil. Earth mother. Her name was Hou-t'u nai nai before she was transformed into a goddess. Hou-T'u is probably the same as T'u-ti Shen (q.v.).

Hou-T'u Shen (China) *see* T'u-Ti Shen.

Hound of Culann (Celtic) *see* Cuchulain.

Hounds of Zeus (Greek) *see* Harpies.

Houris *Houri* (Islamic; India.)
Also known as: *Hurani* (Persia), *Huriyeh* (Arabic).
Heavenly maidens similar to the Apsaras. They welcome slain heroes back from battle as do the Valkyries of the Norse. The Houris resemble white clouds. Compare them to the Valkyries and Apsaras.

Hours (Greek) *see* Horae.

How-Chu (China) God of the Air.

hPhags-skyes-po (Tibet) *see* Virudhaka.

hPhren-ba-ma (Tibet) *see* Mala.

Hra-f-ha-f (Egypt) *see* Assessors.

Hrada (India) *see* Hiranya-kasipu.

Hraesveglur (Teutonic)
He is a giant known as the Guardian of the Gates.

Hraesvelgr *Hrae-Svelger, Hraesvelg, Hraesvelgur* (Teutonic; Norse)
Also known as: *Jonakr* (possibly).
Winter god. Dressed in eagle plumes, Hraesvelgr the corpse-swallower directs the icy winds of Vasud to cause discomfort for mortals. He is possibly the same as Jonakr (q.v.). *See also* Vasud.

Hrafna (Teutonic) *see* Odin.

Hreidmar (Teutonic)
Also known as: *Hreithmarr, Reidmar.*
Magician. Hreidmar, also called King of the Dwarf Folk, is the peasant father of Ottar, who had been changed into an otter, Fafnir, Regin and three daughters. He is associated with Odin. *See also* Andarvi; Ottar; Regin.

Hreithmarr (Teutonic) *see* Reidmar.

Hreshtak (Armenian) Angels. *See also* Aramazd.

Hrid (Teutonic) *see* Elivagar.

Hrim-Faxi *Hrimfaxe* (Teutonic) *see* Aarvak; Alsvid; Dagr; Norns.

Hrim-Thurs *Hrimthursar* (Teutonic) *see* Bergelmir; Ymir.

Hrimfaxe (Teutonic) *see* Hrim-Faxi.

Hrimthursar (Teutonic) *see* Hrim-Thurs.

Hringhorn *Hringhorni, Ringhorn* (Teutonic)
Hringhorn is Balder's large ship, which was later used as his funeral pyre. The female giant Hyrrokin launched Hringhorn for Balder's funeral. *See also* Balder.

Hringhorni (Teutonic) *see* Hringhorn.

Hrodvitnir (Teutonic) *see* Fenrir; Hati; Skoll.

Hropt (Teutonic) *see* Odin.

Hrotik (Armenian) *see* Fravashi.

Hrsikesa (India) Lord of Senses. *See also* Krishna.

Hrungnir (Teutonic)
He is one of the giants who was slain by Thor. Hrungnir has a head and heart of stone, and is armed with a stone shield and a whetstone. Part of the whetstone is still buried in Thor's head. *See also* Thor.

www.ebook3000.com

Hsaing Chun (China)
He is the god of the waterways of Hsiang (Hunan) and one of the nine creator gods. *See also* Nine Songs.

Hsi-Ho (China)
Also known as: *Water Mother.*
Mother of the suns. Wife of Ti-suin. In ancient mythology there are ten suns and twelve moons. Hsi-ho controls the time each sun has a turn in lighting the world. There is a great tree in the Valley of the Lake which is the abode of the suns. While one climbs to the top to light the world, the others wait in the branches. Her worship is similar to that of Aphrodite or Venus.

Hsi-Hua (China)
Official residence for female fairies. This abode is under the control of the Fairy Queen, Hsi Wang Mu (q.v.). *See also* Hung-hua.

Hsi-Ling Shih (China) *see* Sien-tsan.

Hsi T'ien (China) *see* Amida.

Hsi-Wang-Mu *Hsi Wang Mu, Si Wang Mu* (China)
Also known as: *Wang Mu Niang-niang.*
Underworld deity. Goddess of Epidemics. Goddess of plague and pestilence. She is the Royal Mother of the Western Paradise. She possesses the Peaches of Immortality and governs the forces of plague and calamity. The list of the Immortals is kept by Hsi-Wang-Mu. Her residence is within a mountain of jade. Sometimes she is identified with Wang mu niang-niang (Lady Wang or Queen Mother Wang), the keeper of the Peaches of Immortality. In this manifestation, she is a tiger-toothed woman with a leopard's tail, who lives in a jade mountain to the west of Kun-Lun and rules over spirits of evil, sending plague and affliction to mankind. Later, as consort of Tung Wang Kung or as some say, Yu-ti, she resided with the Jade Emperor in the palace on Kun-Lun. Hsi-Wang-Mu is described as a gracious, young, and beautiful sovereign, the Queen of the West, and co-ruler along with Tung Wang Kung over San Hsien Shan (Isles of the Blest). One of her depictions is that of the tiger toothed woman. Another depiction shows her as a beautiful and gracious lady, sometimes winged, sometimes not. She corresponds in some respect to Ament the Egyptian goddess. *See also* K'un-lun; Shen t'ao; Wang-Mu-Niang Niang; Xi Wang Mu.

Hsiang Chun (China)
Hero deity of waterways. One of the Nine Heroes. He is god of the waterways of Hsiang (Hunan province). *See also* Hsiang Fu-jen; Nine Songs.

Hsiang Fu-Jen (China)
Two sisters who are part of the Nine Heroes. The sisters' names are Wo Huang and Nu Ying. *See also* Hsiang Chun; Nine Songs.

Hsing Shen (China) God of the Road.

Hsuan-T'ien Shang-Ti (China)
Deity of water. Supreme Lord of the Dark Heaven. He is sometimes called upon to remove demons and evil spirits. Like the god Kuan-ti, he also punishes evil doers. Hsuan-T'ien Shang-Ti is shown as a giant with naked feet, dressed in a black robe with a gold breast plate. He stands on a turtle which is surrounded by a snake. *See also* Cheng Wu; Kuan-ti.

Htamenmas *Pharmen-pa* (Tibet)
These animal and bird-headed goddesses are found in the Bardo World on the twelfth and thirteenth day holding skeletons and corpses. *See also* Kerimas.

Hu Ching-Te (China)
God of doors. One of the generals who has been deified as a god of the outer doors. He is usually paired with Ts'in Shu-pao, who is also a general. The two deities replaced Shen-t'u and Yu-lu. In another version, it is Ch'in Shu-pao and Yu ch'ih Ching-te who are the guards of the doors. Usually each deity is represented as a leaf on one-half of the outer door. *See also* Men-shen; Shen-t'u.

Hu-Shen (China)
Hail storms are averted by propitiating this local god.

Hu Sia (Egypt)
Also known as: *Hu and Sia; Saa.*
Hu is the god of sense of taste and also of the divine food on which gods and mortals feed. He is the force of creative will. Hu is said to have been born from the drops of blood from Ra when he mutilated his penis. In another version of this myth, it is related that Hu and Sia came into being from the drops of blood which fell when the great sun god Ra was circumcised. Hu appears at the Creation in the Boat of the Sun. Later, he appears at the Judgment of the Dead. Hu is portrayed as a human with a sign of his name above his head. *See also* Ra; Sia (who may be the same as Hu).

Hua Hsien (China) Goddess of flowers.

Huaaiti (Egypt) *see* Aai.

Huacas (Chincha People, Colombia)
Also known as: *Yamanamca Intanamca.*
Spirits or idols. One group of huacas is named Yananamca Intanamca. The Yananamca were destroyed by another huacas named Huallallo Caruincho who was apparently evil. He was called Lord and instructed the women to have only two children, one of which was to be sacrificed for him to eat. He in turn was overthrown by a hero deity named Pariacaca (q.v.). *See also* Coniraya Viracocha.

Huahuantli *The Striped One* (Aztec; Mexico)
An alternate name for Teoyaoimquit (q.v.).

Huaillepenyi (Araucanian People, Chile)
God of fog. He creates deformed children. Huaillepenyi lives on the banks of any watercourse. He is shown as a ewe with the head of a calf and tail of a seal.

Huallallo Caruincho (Andean, Peru)
Huallallo is an evil lord who ate the children sacrificed to him. *See also* Coniraya; Huacas.

Huan-T'ien Shang-ti (China) *see* Shang-ti.

Huana Cauri (Inca) *see* Tahuantin Suyu Kapac.

Huang, The (China)
Deity of good omen. As a male phoenix bird it is called Feng and the female is called Huang. The bird is said to sit only on the site of buried treasure.

Huang-Lao (China)
He is the first man, or creature created by the mixing of Yin and Yang. Huang-Lao was called "The Gold Colored One." He taught mortals the skills needed to exist on earth. *See also* P'an-Ku.

Huang-Ti *Huang Ti* (China)
Also known as: "Yellow Emperor." Inventor of the compass. Originator of bronze casting. His mother is Fu-Pao, a brilliant woman who bore him by miraculous conception and gave birth after being pregnant for two years. Huang-Ti's wife is Hsi-Ling Shih, who introduced the culture of silkworms. Hun-Tun is his son. One of his descendants is Hou Chi, a grain deity. *See also* Hou-chi; Hsi-Ling Shih; Hun-Tun.

Huang T'ien (China)
Also known as: *Shang Ti.*
Huang T'ien is the imperial heaven ruled by Huang T'ien Shang Ti. He rides on the back of a tortoise encircled by a serpent in the dark heaven or northern sky. *See also* Shang Ti.

Huang T'ien Shang Ti (China) *see* Shang Ti; Yu Huang.

Huasi-Camayac (South America) *see* Conopa.

Huasi-Camayoc (South America) *see* Conopa.

Hubaba (Middle Eastern) *see* Khumbaba.

Hubal (Persian)
He was the tutelary deity of Mecca until the advent of Islam, when his likeness was destroyed.

Hubar (Babylon)
Also known as: *Tiamat*
As Hubar, Tiamat is the personification of the underworld river of the same name. *See also* Tiamat.

Huchi Fuchi (Japan)
Goddess of fire. She is possibly a deity of the early inhabitants of Japan known as the Ainos.

Huecuvus (Araucanian People, Chile, South America)
The Huecuvus are shape-changing spirits of evil under the command of Pillan (q.v.).

Huehuecoyotl (Mexico) *see* Coxcoxtli; Xochipilli.

Huehueteotl (Aztec, Olmec; Mexico)
Also known as: *Old God, Xiuhtecuhtli.*
A fire god, he might have been the earliest deity discovered from the Teotihuacan period. It is quite possible that Huehueteotl was a volcano deity since this region is volcanic. Apparently worshiped for many centuries, he is shown as an old man sitting with his head bowed. The head and shoulders support an incense bowl. The name Huehueteotl is used sometimes for the Aztec god Xiuhtecuhtli (q.v.).

Huehuetonacacipactli (Aztec; Mexico)
Also known as: *Cipactli, Coxcoxtli*
Fish god. "Old Fish God of our Flesh." *See also* Cipactli; Coxcoxtli.

Huemac Possibly *Hueymac* (Aztec, Toltec People, Mexico)
Also known as: *Quetzalcoatl* (possibly).
God of earthquakes. Astrologer. In some myths Huemac rules with Quetzalcoatl, and in others he is an aspect of Quetzalcoatl. It is said that he was an astrologer priest and the first of the nine rulers. He died at the age of three hundred during the reign of the second ruler (or era). Huemac was said to have compiled a book of history and prophecy, and founded the city of Tollan. *See* Legend of the Four Suns; Topiltzin.

Hueymac (Mexico) *see* Huemac.

Hueytecpatl (Aztec People, Mexico)
Possibly a god of fire. He is associated with the flint stone and is one of the original quadruplets. *See also* Hueytonantzin.

Hueytonantzin (Aztec People, Mexico)
Mother goddess. She is the mother of the Lords of the Four Directions: Hueytecpatl, Ixuin, Nanacatltzatzi and Tentemic. Hueytonantzin was sacrificed each morning by her sons. *See also* Ixmacane.

Hugh (Celtic) *see* Aed.

Hugi (Norse; Teutonic)
Also known as: *Thought.*
Giant. Hugi outran Thor's human servant Thialfi in a race in Utgard-Loki's domain. The reason Thialfi could not beat him was because he was the embodiment of thought. *See also* Loki.

Hugin (Teutonic) *see* Huginn.

Huginn *Hugin* (Teutonic)
Huginn, "The News Gatherer," is one of Odin's ravens. *See also* Munin; Odin.

Huh and Hauhet (Egypt)
High gods. Huh (frog headed) and Hauhet (serpent headed) gods. Huh was the male and Hauhet the female. They are part of the Ogdoad, the eight gods who created the world. *See also* Ogdoad.

Huichilobos (Aztec) *see* Huitzilopochtli.

Huitzilo-Mexitli (Aztec) *see* Huitzilopochtli.

Huitzilo-Poktli (Aztec) *see* Huitzilopochtli.

Huitzilopochtli *Huitzilo-Poktli, Huitzilopoktli, Uitzilopochtli* (Aztec; Mexico)
Also known as: *Blue Tezcatlipoca, Curicaveri, Huichilobos* (name give by the Spanish), *Huitzilo-Mexitli, Hummingbird Left Hand, Mexitli, Mextli, Mixcoatl, Otontecutli, Tenochtitlan, Tezcatlipoca, Xocotl.*
Chief of the Aztec pantheon. God of war. Storm deity. God of lightning. Protector of travelers. Associated with the sun and fire. His name means "Hummingbird on the Left." The Aztecs were living in caves when they came upon a likeness of Huitzilopochtli. He became their leader; they saw themselves as children of the sun, and followed his directions. Often he led them in the form of a hummingbird. When he commanded that they leave Aztlan, their island home, they did. In time a number of followers split off and followed Huitzilopochtli's sister Malinalxochitl, a powerful woman who had amazing control over scorpions, snakes and spiders. Huitzilopochtli continued his way and led his people on an arduous journey lasting

www.ebook3000.com

generations from Aztlan to Coatepec (Hill of the Serpent). It was here that he was reborn. Huitzilopochtli's mother Coatlicue was sweeping the temple one day when she tucked feathers into her blouse. When she finished her task and went to remove the feathers, they were gone. She knew she was pregnant. This divine impregnation was the god's beginning of his rebirth. His sister Coyolxauhqui and his 400 brothers known as the Centzon Huitznahuas, embarrassed and infuriated because of their mother's pregnancy, decided to murder her. They laid in wait and when she approached they decapitated the woman. Huitzilopochtli leaped from his mother fully grown and dressed in warrior's gear, flourishing Xiuhcoatl. In retaliation for their brutal act he dismembered his sister and killed all but a few of his brothers. His image was usually depicted in wood rather than stone. He is shown with a tuft of blue-green hummingbird feathers on his head, a golden tiara, a spear in his right hand and a shield in his left. He is often shown holding the smoking mirror common to Tezcatlipoca. Other depictions show him with hummingbird feathers on his left, holding a stick shaped like a snake. He is also depicted as being covered with gems, gold and pearls. His face is frequently painted with yellow and blue stripes, and he wears a black mask decorated with stars around his eyes. Human sacrifices were frequently made to Huitzilopochtli. According to some, various other tribal gods, such as Curicaveri (Tarascan), Mixcoatl (Chichimec), Otontecutli or Xocotl (Tepanec and Otomi people) are similar or identical with Huitzilopochtli. *See also* Centzon Huitznahuas; Chimalmat; Coatlicue; Coyolxauhqui; Hueytonantzin; Legend of the Four Suns; Otontecutli; Tezcatlipoca.

Huitzilopoktli (Aztec) *see* Huitzilopochtli.

Huitziton (Aztec) *see* Huitzilopochtli.

Huitznahua (Aztec)
High gods. The Huitznahua are the remaining brothers of the war god Huitzilopochtli who were defeated but not deposed during the power struggle between the war god and his unfortunate sister, Malinalxochitl. *See also* Huitzilopochtli.

Huixtocihuatl (Aztec) *see* Uixtochihuatl.

Hulda (Teutonic) *see* Holda.

Huldra (Teutonic) *see* Bertha; Holda.

Huliamma (India)
She is one of the Mutyalamma goddesses who are deities of the household. Huliamma is a tiger goddess. *See also* Mutyalamma.

Hulle (Teutonic) *see* Holda.

Hum-ba (Middle Eastern) *see* Khumbaba.

Humbaba (Middle Eastern) *see* Khumbaba.

Humhum (Middle Eastern) *see* Khumbaba.

Hummingbird Left Hand (Aztec People, Mexico) *see* Huitzilopochtli.

Hun-Apu (Quiche People, Guatemala) *see* Hun-cane.

Hun-cane *Huncame* (Quiche People, Guatemala)
Hun-Cane and Vukubcame were co-lords of the cavern world of Xibalba. Hun-Cane and Vukubcame were destroyed by Hun-Apu and Xbalanque after they murdered Hunhun-Apu and Vuub-Hunapu. *See also* Xibalba.

Hun-Tun *Hun Tun* (China)
God of chaos. The personification of chaos, a mythical emperor-god who held sway prior to the active forces, Yin and Yang. The emperor of the north (Hu) and the emperor of the south (Shu) met in the territory of Hun-Tun. Unfortunately, Hun-Tun lacked the necessary orifices for seeing, hearing and smelling. Because of his hospitality, Shu and Hu bored holes at the rate of one a day to give him orifices. On the seventh day, when they drilled the last hole, Hun-Tun died and at the same time the world was created. Sometimes Hun-Tun is the wicked son of Huang Ti. *See also* Shu-hu.

Hunab Ku (Maya) *see* Hunab-ku.

Hunab-Ku *Hunab Ku* (Maya People, Yucatan)
Also known as: *Kinebahan* ("Mouth and Eyes of the Sun").
Invisible Supreme God. Hunab-Ku is the great god without form, the chief of the Mayan pantheon. He is the father of Itzamna, and the spouse of the goddess of weaving Ixazalvoh (q.v.). Hunab-Ku is analogous to the Aztec god Ometeotl. *See also* Itzamna; Ometeotl.

Hunabku (Maya) *see* Hunab-Ku.

Hunahpu and Ixbalanque *Hun-Ahpu* (Maya People, Yucatan)
Also known as: *Alom, Cajolom, Hun-Ahpu and Xbalanque, Hunahpuguch, Hunahpuutiu, Qaholom.*
Demi-god. God of the hunt. Son of Hun Hunahpu and Xquiq. Twin brother of Ixbalanque ("little jaguar"), both born by miraculous birth. The twins have two other brothers, the talented monkey artisans, Hun Batz and Hun Chuen. Hun Batz and Hun Chuen caused their younger twin brothers a lot of grief. Years later when the twins were older and fed up with their brothers' constant abuse, they lured them into a tree with no escape. Hun Batz and Hun Chuen became monkeys. He and his brother attacked the great imposter of the sun, Gukup Cakix. During the battle, the evil giant pulled and ripped off Hunahpu's arm. With the help of an elderly couple, perhaps their grandparents, they punished Gukup, and Hunahpu retrieved his arm. The two brothers next destroyed two other evil beings, the sons of Gukup Cakix, Zipacna and Cabracan, a destroyer of mountains. The task was not easy. It demanded plotting, planning, and scheming, but the wins were successful. Next the hero twins set out to avenge the deaths of their father Hun Hunahpu and his twin, their uncle Vukub Aphu. They set out for the underworld and once there endured a series of trials and tribulations before achieving their goal. The brothers were then able to turn themselves to the task of creation. *See also* Alom; Camazotz; Caprakan; Gukup Cakix; Hunahpu-Guch; Qaholom; Zipacna.

Hunahpu-Guch *Hunahpuguch* (Maya)
Also known as: *Alom.*
Creator. Originally Alom (or Atonatiuh) of the four creator regents. He changed his name during the third attempt to create

men. *See also* Legend of the Four Suns. The name Hunahpu may be associated with both Hunahpu-guch and Hunahpu-utiu. There is a separate legend regarding Hunahpu (q.v.).

Hunahpuguch (Maya) *see* Alom; Hunahpu.

Hunbatz (Maya) *see* Hunhun-Ahpu; Xquiq.

Huncame (Quiche People, Guatemala) *see* Hun-cane.

Hunchouen (Central America) *see* Hunapu; Xquiq.

Hundred-Handed (Greek)

This is another name for the Hecatonchires (q.v.).

Hunhun-Ahpu and Vukub-Ahpu

Hunhun-Ahpu and Vukub-Ahpu had been lured to the underworld by the Xibalba people to compete in a ball game. The twin brothers lost the game and were sacrificed. Hun-hun-Ahpu's head was taken and hung from a barren calabash tree (likely as a warning to others). The tree began to grow fruit immediately. The story of the unusual tree spread rapidly. It attracted a young woman who went to have a look at it. Hun-hun-Ahpu's head spoke to her and enticed her to receive his saliva. Miraculously, she became pregnant with and gave birth to the hero twins Hunahpu and Ixbalanque (q.v).

Huniman (India) *see* Hanuman.

Hunooman (India) *see* Hanuman.

H'uraru (Pawnee People, North America)

Also known as: *Atira.*

Mother earth. Creator of all things. Earth spirit.

Hypnos (Greek) This is a name of Somnus, the god of sleep.

Hura-Kan (Central, South America) *see* Huracan.

Huracan *Huracan Hura-Kan, Hurakan, Hurucan, Hurukan* (Maya, Quiche People, Guatemala)

Also known as: *Caculha Huracan*, *Heart of Heaven* (Quiche), *Hurn.*

God of hurricanes; of summer storms; of whirlwinds. God of terror. Huracan and Gucumatz created all things including mortals who were originally formed from wood. The mortals displeased the gods so they decided to try again. This time the gods used maize to create men and formed women for the men. Huracan developed fire and gave it to mortals. Others believe the original creators are Gucumatz and Tepeu or Gucumatz and Qabauil. Huracan was especially revered in Guatemala. He is associated with the Aztec god Quetzalcoatl, and also with Gucumatz and Tepeu (qq.v). Huracan is associated with the Aztec god, Quetzalcoatl. *See also* Gucumatz; Quetzalcoatl; Tepeu.

Hurakan (Central, South America) *see* Huracan.

Hurani (Persia) *see* Houris.

Huriyeh (Arabic) *see* Houris.

Hurn (Central, South America) *see* Huracan.

Hurucan (Central, South America) *see* Huracan.

Huruing Wuhti (Hopi People, North America)

After creating everything else, this male/female deity made men and women out of clay. In other myths of the Hopi Creation Legend, Huruing Wuhti are two mother goddesses. In some Hopi tales they are known as survivors of the Deluge and mothers of the ancestors of the tribe. Ragno, an old mother goddess, assisted the women during times of difficulty. Ragno is also a figure in the Pomo Indian Creation Legend. *See also* Ragno.

Hurukan (Central, South America) *see* Huracan.

Husbishag (Assyro-Babylonian)

Underworld goddess. She is the keeper of records of the time of death of individuals. Her spouse is the evil spirit, Namtar (q.v.).

Husheng (Iranian, Persian) *see* Hoshang.

Husheng and Tamuras (Persian) *see* Hushang and Takhmoruw.

Husheng and Tamurath (Persian) *see* Hushang and Takhmoruw.

Hutameh (Islam)

This is the third section in the Islamic Hell known as Daru el-Bawar. It is reserved for people of the Jewish faith. *See also* Islamic Hell.

Hutchaiui (Egypt)

Weather god. God of the west wind. He is depicted as ram-headed with four wings, or as a ram-headed beetle.

Huti Watsi Ya (Huron People, North America) The Pleiades.

Huve (Bushmen of Africa)

Also known as: *Huveane.*

Supreme God. After creating heaven and earth, Huve hammered some pegs into the sky and climbed back to heaven, removing the pegs as he climbed. He is possibly the same as Huveane of the Basuto people.

Huveane (Basuto People, Africa)

Creator. After creating heaven and earth, mortals caused Huveane great distress. He hammered pegs into the sky, climbed up them, removing them from below as he climbed higher and higher. Soon he was lost from sight and has not been seen since that time.

Huythaka (Columbia, South America) *see* Bochica; Chia; Cuchaviva.

Huzruwauqti (Pueblo People, North America)

Goddess of hard material. Her abode is located in the western home of the sun.

Hvar (Chaldean) *see* Hvare-khshaeta.

Hvaranah (Persia) *see* Khvarenanh.

Hvare-khshaeta *Hvarekhshaeta, Hvar* (Chaldean, Persian)

"The Brilliant Sun." In some legends he is one of the Yazatas and is known as the eye of Ahura Mazda. In Chaldean astrology he is associated with Tishtrya, known as the Dog Star, Mah the moon, and Anahita. He rides across the sky in a chariot drawn by swift horses. *See also* Ahura Mazda; Ameshas Spenta; Anahita; Tishtrya; Yazatas.

Hvarekhshaeta (Chaldean) *see* Hvare-khshaeta.

Hveheuteotl (Aztec) *see* Xiuhtecuhtli.

www.ebook3000.com

Hvergelmir *Hvergelmer, Vergelmir* (Teutonic)
Also known as: *Kvergjelme, Odraerir.*

This is an ever-flowing spring, well, or cauldron beginning under one root of Yggdrasil in the world called Nifl-heim. From Hvergelmir flowed ten, eleven, or twelve rivers known as the Elivagar. These streams hardened into ice blocks. *See also* Elivagar; Nifl-heim; Odraerir; Yggdrasil.

Hyacinth (Greek) *see* Hyacinthos.

Hyacinthos *Hyacinth, Hyacinthus, Hyakinthos* (Greek)
Deified mortal. Spring deity. Hyacinthos is the son of Pierus and the Muse Cleio, or Amyclas and Diomede. An extremely beautiful youth, loved by Apollo and Zephyrus, he was accidentally killed when Zephyrus, also known as the West Wind, blew Apollo's discus from its course. In another version, it was Phoebus who threw the discus and when Hyacinthos rushed to pick it up it bounced back and struck him in the face. From his blood sprang the hyacinth or in some legends, the lily. Three great goddesses, Aphrodite, Artemis and Athena, carried him to heaven. *See also* Aphrodite; Apollo; Artemis; Athena; Clytia; Muses; Zephyrus.

Hyacinthus (Greek) *see* Hyacinthos.

Hyades (Greek)
The Hyades are the five, or some say seven, daughters of Atlas and Pleione, Atlas and Aethra, or Oceanus and Tethys. Their siblings are Calypso, Hyas, the Hesperides and the Pleiades. *See also* Atlas; Calypso; Hesperides; Hyas; Naiads; Pleiades.

Hyagnis (Armenian, Greek)
Possibly a lightning god. Father of Marsyas-Masses. Some say Marsyas is a tribal variety of Hyagnis and Hyagnis is the Greek form of Vahagn. *See also* Marsyas; Vahagn.

Hyakinthos (Greek) *see* Hyacinthos.

Hyas (Greek)
He is the son of Atlas and Pleione. His siblings are Calypso, the Hyades, the Hesperides and the Pleiades. *See also* Atlas; Calypso; Hesperides; Hyades; Pleiades.

Hydra, Lernean (Greek)
Demon of draught and darkness. A nine-headed monster, Hydra is the son of Typhon and Echidna. For each head cut off, two would grow in its place unless the wound was cauterized. One of his nine heads is immortal. To fulfill his second labor, Heracles had to kill the Hydra. He burned away eight of its heads and buried the ninth under a rock. The Hydra caused Heracles' death. *See also* Cerberus; Chimaera; Crommyonian Sow; Echidna; Heracles; Iolaus; Sphinx; Typhon.

Hygeia *Hygea, Hygieia* (Greek)
Also known as: *Salus.*

Goddess of health. She is the daughter of the great healer, Asclepius, and Epione, the daughter of Merops. Her siblings are Acesis, Aegle, Iaso, Janiscus, Machaon, Panacea, and Podalirius. Hygeia is shown with a serpent drinking from a jar she is holding. *See also* Acesis; Aegle; Asclepius; Merops.

Hyk (Egypt) *see* Heka.

Hylas (Greek)
Deified mortal.

Hylas is the son of Theodamas, the king of the Dryopes, and the nymph Menodice, who is the daughter of the giant hunter, Orion. Heracles came upon Theodamas in his field and demanded either an oxen or a plough from him. When the king refused his request, Heracles, looking for an excuse to war with the Dryopes, murdered him and abducted the beautiful youth Hylas. He took the young man aboard the Argos as his attendant and lover. One day, while the ship was beached, Hylas went to draw water at a spring. Dryope and the nymphs of Pegae spied him. Entranced by his beauty, they lured him into the water. When an all night search party found only his water pitcher, Heracles went wild with despair. It is said that in his sorrow, Heracles made the waves sound his loved one's name as they pounded against the shore. Hylas was never heard from again. *See also* Argonauts; Hermaphroditus; Naiads; Nereids; Orion; Scylla; Sirens.

Hyllus (Greek)
He is the son of Heracles and Deianeira or Melite. *See also* Aegimius; Heracles.

Hylonome (Greek)
A centaur. She is the daughter of Ixion and Nephele. *See also* Ixion; Nephele.

Hymen (Greek)
Also known as: *Hymenaeus.*

God of marriage. A minor deity. Hymen may have been the son of Apollo and the muse Urania or a son of Dionysus and Urania, or Dionysus and Aphrodite. In some myths he is said to have been one of Aphrodite's attendants. The most romantic myth is that he was a poor musician who pined after a young woman who was forbidden to marry him because of his status. Pirates abducted the couple and sailed away with them. On board the ship, Hymen played enchanting music on his lyre and put the crew to sleep. Once asleep he threw them all overboard, and sailed the vessel back to Athens. Not only was he hailed as a hero, he was able to marry the woman of his dreams and sing at his own wedding. The song he sang was used thereafter at other nuptials and became known as the "hymenael." *See also* Dionysus.

Hymenaeus (Greek) *see* Hymen.

Hymir *Hymer* (Norse; Teutonic)
The sea giant Hymir is the son of Fornjot, and brother of Aegir. He became the father of Tyr. He is associated with Thor, who took Hymir's magic cauldron, used for brewing ale. Hymir also accompanied Thor on his fishing trip to hook the Midgard Serpent. *See also* Aegir; Fornjot; Midgard Serpent; Thor.

Hypate (Greek)
A Delphic Muse who personifies the high string of the lyre. Her sisters are Mese, the middle string, and Nete, the low string.

Hyperbius (Greek)
He is one of the fifty sons of Aegyptus. *See also* Adrestus; Aegyptus; Eteocles.

Hyperenor (A) (Greek)
He is one of the Sparti, the people who sprang from the soil when Cadmus sowed the teeth of the dragon. *See also* Cadmus; Chthonius; Echion.

Hyperenor (B) (Greek) Poseidon and Alcyone are his parents.

Hyperion (Greek)
Sun god. One of the Titans, son of Uranus and Gaea. His wife is his sister, Theia. Sometimes it is said that his wife is Euryphaessa. Hyperion is the father of Helios, the sun god, Selene, the moon goddess, and Eos, goddess of the dawn. He is depicted as a handsome man. Hyperion is sometimes confused with Helios (q.v.). *See also* Gaea; Oceanids; Uranus.

Hypermnestra (A) *Hypermestra* (Greek)
She is the eldest of the fifty daughters of Danaus. She refused to follow her father's instructions to all his daughters — to kill their husbands on their communal wedding night. She would not murder her husband, Lynceus, because he spared her virginity. She was tried and acquitted by the Argive judges. Later, she became the mother of Abas. After death, Hypermnestra, Lynceus and Aba were all buried in the same tomb at Argos. *See also* Danaus.

Hypermnestra (B) (Greek)
She is the daughter of Thestius and Eurythemis.

Hypnos *Hypnus* (Greek)
Also known as: *Somnus.*
God of sleep. His parents are Nyx and Erebus; his siblings: Aether, Cer, Dreams, Hemera, Momus, Moros, Nemesis and Thantos. Pasithea, one of the Charities, became his wife. Their children are Morpheus and the Dreams. *See also* Aether; Erebus; Keres; Morpheus; Nemesis; Nox; Sarpedon (B); Somnus.

Hypnus (Greek) *see* Hypnos.

Hyposouranios (Phoenician)
The giant son of Fire, Hyposouranios was the first to build towns. His brother Ousoos was the first to make garments from skins. *See also* Fire; Ousoos.

Hupseus (Greek)
King of the Lapiths. He is the son of Peneius and Creusa. His children are Astyagyia, Cyrene, Stilbe and Themisto. *See also* Creusa; Cyrene; Themisto.

Hypsipyle (Greek)
Queen of Lemnos. She is the mother of several children by Jason, the Argonaut. When the women of her father Thoas' kingdom attempted to kill him, Hypsipyle saved him. She was exiled to Lemnos. *See also* Jason.

Hyrieus (Greek)
King of Hyria. He is the son of Poseidon or Lycus and Alcyone. It is possible that Orion is his son. *See also* Orion.

Hyrmina (Greek)
She is the daughter of Epeius and Anaxiroe and the spouse of Phorbas. *See also* Actor (B).

Hyrrokin (Norse; Teutonic)
She is the female giant who at Odin's request, launched Balder's ship Hringhorn when he died. Because she performed this act without help, Thor became so angry that he tried to kill her. *See also* Balder; Hringhorn; Odin; Thor.

I

I (A) (China)
Also known as: *Excellent Archer.*
He is the god of bowmen. I shot down all but one of the ten suns because they heated the earth so much. He is the spouse of the moon goddess, Chang-o.

I (B) (Maya)
The goddess I is a water goddess who may be the same as Chalchiuhtlicue (q.v.).

I-Em-Hetep (Egypt) *see* Imhotep.

I Kaggen (Africa) *see* Cagn.

I-shi-ko-ri-do-me (Japan) *see* Ishikoridome-no-Mikato.

I-ti (China)
God of wine. I-ti is a former mortal who invented wine making. He is associated with Tu K'ang, the god of distillers.

Iacchus (A) (Greek)
Epithet of Bacchus. *See also* Bacchus; Dionysus.

Iacchus (B) (Greek)
He is the son of Demeter, Dionysus or Persephone.

Iaeuo (Greek) *see* Iao.

Iaevo (Hebrew) *see* Jehovah; Yahweh.

Iah (Egypt) (Hebrew) *see* Aa; Aah; Jehovah.

Iahweh (Chaldea) *see* Sabazios.

Iai (Egyptian) *see* Aah.

Iakchos (Greek) *see* Dionysus.

Ial (India)
Also known as: *Hari Hara-putra* (Vishnu, son of Shiva), *Ier.*
Son of a god. He is said by some to be a son of Shiva by Mohina (feminine Vishnu). *See also* Vishnu.

Ialdabaoth (Ophites; post–Christian Gnostics)
Spirit creator. One of seven ruling spirits created by the god

www.ebook3000.com

🔵 **2.** Use your intention (mind-eye-heart power) to spiral in the navel point guiding and moving the Chi. Let the energy flow down to the sexual center (Ovarian or Sperm Palace).

🔵 **3.** Move the energy from the sexual center to the perineum and down to the soles of the feet.

🔵 **4.** Draw the energy up from the soles to the perineum and to the sacrum.

🔥 **5.** Draw the energy up from the sacrum to the Door of Life (the point in the spine opposite the navel).

🔥 **6.** Draw the energy up to the mid-spine point (the T-11 vertebrae).

🔥 **7.** Draw the energy up to the base of the skull (Jade Pillow).

🔥 **8.** Draw the energy up to the crown.

🔥 **9.** Move the energy down from the crown to the mideyebrow point.

🔥 **10.** Touch the tip of your tongue to your upper palate, press and release a few times; then lightly touch the palate, sensing the electric or tingling feeling in the tip of the tongue. Move the energy down from the mideyebrow to where the tip of your tongue and palate meet.

🔵 **11.** Move the energy down from the palate through your tongue to the throat center.

🔵 **12.** Move the energy down from the throat to the heart center.

🔵 **13.** Bring the energy down from the heart to the solar plexus and feel a small sun shining out.

🔵 **14.** Bring the energy back down to the navel.

🔥 **15.** Continue to circulate your energy through this entire sequence of points, at least nine times. Once the pathways are open, you can let your energy flow continuously like a river of energy without needing to stop at each point.

🔥 **16.** Conclude when you wish by collecting energy at the navel.

Men: Cover your navel with both palms, left hand over right. Collect and mentally spiral the energy outward from the navel 36 times clockwise, and then inward 24 times counterclockwise.

Women: Cover your navel with both palms, right hand over left. Collect and mentally spiral the energy outward from the navel 36 times counterclockwise, and then inward 24 times clockwise. *For details of this practice see the book, "Awaken Healing Light", by Mantak Chia.*

Ophiomorphus, the serpent son of Ialdabaoth. The first spirit is possibly Adonaeus or Adonai; the second, Ialdabaoth; third, Iao; fourth, Sabaoth; fifth, Astaphaios; sixth, Ailaios; seventh, Horaios. In some renditions, Ialdabaoth (conceived by Sophia) is the first ruler. *See also* Abraxas; Archons; Iao; Sophia.

Ialmenus (Greek)
An Argonaut. Co-ruler of Orchomenus with his brother Asclaphus. He is the son of Ares and Astyoche. Ialmenus and Asclaphus were both suitors of Helen of Troy. The brothers took thirty ships to Troy. *See also* Ares; Argonauts; Asclepius.

Ianus (Roman) *see* Janus.

Iao (Gnostic)
Also known as: *Iaeuo.*
Aspect or name for Yahweh or Jehovah. One of the Archons. Part of an invocation by an Hellenistic priest indicates this might be a god similar in nature to Yahweh; i.e., "I invoke thee.... Demon of Demons, God of Gods, The Lord of Spirits, the unwandering Æon, *Iao ouêi* [Jehovah?] hearken unto my voice... ." *See also* Abraxas; Jehovah; Yahweh; Zeus.

Iapetus *Iapetos* (Greek)
A Titan. He is the giant son of Uranus and Gaea. His siblings are Cronus, Pallas, Oceanus and the Titans. He married Clymene, one of the numerous ocean nymphs who are the daughters of Oceanus. Iapetus has four gigantic sons: Atlas, Menoetius, Prometheus (Forethought) and Epimetheus (Afterthought). *See also* Atlas; Clymene; Cronus; Epimetheus; Gaea; Prometheus; Uranus.

Iarnsaxa *Jarnsaxa* (Norse; Teutonic)
Also known as: *Iron Dirk, Sif* (possibly).
She is the giant mistress of Thor and mother of Magni, and in some renditions, Modi, and possibly Sif. She is not a member of the Asynjor. When he was three years old, Magni lifted the foot of the giant Hrungnir from the leg of Thor. *See also* Magni; Modi; Sif (B).

Iasion (Greek)
His parents are Zeus and Electra. Dardanus, his brother, is favored by Zeus. His children by Demeter are Philomelus, who invented the wagon, and Plutus, the god of agricultural riches. *See also* Dardanus; Demeter; Eirene, Electra.

Iaso (Greek)
Goddess of healing. Her name means "cure." She is the daughter of the great physician Asclepius and Epione, the daughter of Merops. Her siblings are Acesis, Aegle, Hygeia, Janiscus, Machaon, Panacea and Podalirius. *See also* Asclepius; Merops.

Iasus (A) (Greek)
He is the son of Lycurgus, the king of Arcadia, and Cleophyle or Eurynome. His wife is Clymene and their daughter is Atalanta. His siblings are Amphidamas, Ancaeus and Epochus. *See also* Atalanta; Clymene; Inachus.

Iasus (B) (Greek)
Son of Rhea and Anchiale. One of the Dactyli. *See also* Dactyli; Rhea.

Iasus (C) (Greek)
King of Argos. His parents are Argus Panoptes and Ecbasus or Triopas and Ismene. His siblings are Agenor and Pelasgus.

Iasus (D) (Greek) Aeneas killed Iasus during the Trojan War.

Iath (Celtic) *see* Eire.

Iatiju (Acoma People, North America)
Parent of the Katsinas who are food and rain deities. *See also* Pishumi; Shk.

Iatik (Native American) *see* Iatiku; Nautsiti.

Iatiku and Nautsiti *Iatik* (Akoma, Koshairis People, North America)
Creators. They are sisters who created man. The sisters were made by Iatik in some versions and in other versions it was the Great Spider (Sus'istinako) who created them. Iatiku is sometimes referred to as a corn mother.

Iaw (Hebrew) *see* Jehovah.

Ib (Egypt) *see* Ab.

Ibe Dji (Yoruba People, Africa)
The likeness of Ibe Dji is only involved in the ceremonies that commemorate the deaths of twin sisters.

Iblis *Eblis* (Islamic)
The Prince of Darkness. Chief of the Jinn. Originally he was the angel Azazel. *See also* Azazel; Jin; Satan.

Ibmel (Finno-Ugric) *see* Jumala.

Iboroquiamio (Orinoco People, South America)
Devil. Little known, but greatly feared deity.

Ibrahim (Islamic) *see* Abram.

Ibraoth (Middle East) *see* Sabaoth.

Ibukido-Nushi (Japan) "Breath-Blowing-Lord." *See also* Haya-akitsu-hime-no-kami.

Icarius (A) (Greek)
He is the son of Perieres and Gorgophone or Oebaulus and Bateia, the Naiad. *See also* Gorgophone; Hippocoon.

Icarius (B) (Greek)
This farmer taught other farmers how to grow grapes and produce wine as originally taught by Dionysus. One day, during a festival, the drunken farmers beat Icarius to death. Icarius and his daughter, Erigone, the harvest goddess, became the constellation Bootes (some say Erigone is the constellation, Virgo). *See also* Dionysus; Erigone.

Icarus (Greek)
In an attempt to escape from King Minos, Daedalus made wings held together by wax. His son, Icarus, flew too close to the sun and was killed. His body washed up on the island of Icaria. *See also* Daedalus; Minos.

Icheiri (Carib People, Antilles)
Spirits. Each cabin has a altar where food offerings are laid out for the Icheiri. They are generally thought of as intermediaries between humans and the celestial powers. There is a deity named Yris involved with the Icheiri. *See also* Lares; Penates.

Ichiki-Shima-Hime (Japan) *see* Benten.

Ichikishima-Hime-no-Mikoto (Japan) *see* Three Goddesses of Munakata.

Icona (Maya People, Yucatan)
Also known as: *Jesus*.
Creator. According to legends, the Spanish Christianized the people but the Mayans converted the Christian Jesus to Icona. Icona created all things and he and his wife, who is a virgin named Chibirias or Hischen, had a son named Bacab. The rest of the legend is similar to the crucifixion story of the Biblical God, Jesus, and the Holy Ghost. The Holy Ghost is called Echuac or Ekchuah. *See also* Christ; Jesus.

Ictinike (Sioux People, North America)
Known as the "Father of Lies," Ictinike was exiled from heaven by his sun god father.

Id (Aztec)
God of fire. This god of fire, both creative and destructive, holds a position of seniority among the gods. His dwelling place is the North Star.

Ida (A) (India) *see* Ida (B); Manu.

Ida (B) *Adda, Idavita, Ila* (India)
An earth goddess, goddess of devotion, speech and vital air, Ida is the daughter and perhaps spouse of Vaisavata. She is also called the instructor of Vaisavata, spouse of Budha, mother of Kuvera. *See also* Budha; Kuvera; Vaisavata.

Ida (C) (Greek)
She is the daughter of Corybas, spouse of Lycastus, and mother of Minos. *See also* Minos.

Ida (D) (Greek)
She is the daughter of Melisseus. She and her sister, Adrastia, fed Zeus when he was an infant in Crete. *See also* Adrastia; Amaltheia; Zeus.

Ida-Ten (Zen; Japan)
Also known as: *Wei-to* (China).
From a revelation of a Chinese monk, Tao Hsuan (also spelled Tao-Suan). Ida-Ten is the god who protects monasteries. Guardian of the law. He is regarded as having miraculous speed. Formerly, he was known as General Wei, who as a mortal was the first to be put in charge of protecting Buddhism and monks. Ida-Ten is depicted as a handsome young man wearing a Chinese-type helmet, breastplate, and holding a sword. He is associated with a demon named Sokushikki.

Idaea (A) (Greek)
She is one of the daughters of Dardanus (q.v.).

Idaea (B) (Greek) Idaea is an epithet of Rhea (q.v.).

Idaea (C) (Greek) She is the second wife of Phineus (q.v.).

Idaeus (Greek)
A herald for the Trojans. When Priam went to pick up his son Hector's body, Idaeus was his driver. *See also* Hector; Helen; Priam.

Idakru (Japan)
Idakru is sometimes referred to as a son of Susanowo, the Ruler of the Ocean and Mysterious Things. *See also* Susanowo.

Idas (A) (Greek)
An Argonaut. Member of the Calydonia Boar Hunt. His parents are Aphareus and Arene or Poseidon and Arene. His siblings are Lynceus and Peisus. The two women in his life were abducted. Phoebe was abducted by Castor and Polydeuces. Marpessa was abducted by Apollo.

Idas (B) (Greek)
Also known as: *Acesidas*.
Idas is one of the Dactyli. One of his siblings is Heracles. *See also* Dactyli; Heracles.

Idavida *Ida* (India)
Idavida is the mother of the demon dwarf, Kuvera (q.v.).

Idavold (Teutonic) *see* Idawold.

Idavolir (Teutonic) *see* Idawold.

Idavoll (Teutonic) *see* Idawold.

Idawold *Idavold, Idavoll, Idavolir, Ithavoll* (Norse; Teutonic)
Place of the gods. Asgard is located on the Plain of Idawold. It is also the location of Odin's palace, and Vingolf, the palace of the goddesses. Gladsheim is located in Idawold. *See also* Asgard; Gladsheim; Vingolf.

Iddahedu (Babylon) *see* Nabu.

Ide (Northwest Coast Native North Americans) *see* Adee.

Idem-Kuguza (Finnish) *see* Orin-Murt.

Idi (Native North American People) *see* Adee.

Idim-Kuguza (Finnish) *see* Orin-Murt.

Idlirvirissong *Irdlirvirisissong* (Eskimo)
Sky deity. Demonic cousin of the Sun. In some versions she is the cousin of Aningan, the moon god. She is depicted as a clown. *See also* Alignak; Sedna.

Idmon (A) (Greek)
He is the son of Abas and Asteria or Cyrene, or Apollo and Asteria or Cyrene. *See also* Argonauts.

Idmon (B) (Greek)
He is one of the fifty sons of Aegyptus (q.v.).

Idmon (C) (Greek)
Arachne, the weaver, who hung herself and was turned into a spider by Athena, is his daughter.

Idomene (Greek)
She is the daughter of Pheres and Periclymene. Her siblings are Admetus, Lycurgus and Periopis. Her marriage to Amythao resulted in the births of Aeolia, Bias, Melampus and Perimele. *See also* Abas (A); Admetus; Aeolia; Melampus; Pheres.

Idomeneus (Greek)
King of Crete. He is the son of Deucalion, the brother of Crete, the husband of Medea and the father of a son, Idamante.

Idun *Iduna, Idunn, Idunna, Idhunn, Ithun, Y'dun* (Norse; Teutonic)
Idun, an Asynjor, is the goddess who guards the golden apples of eternal life for the gods. The Aesir needed the apples for their strength and health. Idun is the wife of Bragi, the god of poetry. Her brother is the giant Thjasse-Volund. When Loki

www.ebook3000.com

was abducted by the giant Thiassi, he gained his release by promising to give Idun to him. Loki wooed Idun by telling her he knew where she could find better apples. They went into the woods together and Idun was taken by Thiassi. Without their apples, the Aesir grew old and dissipated. They threatened to punish Loki if he did not return Idun. Using Freyja's magic cloak, he flew into Thiassi's territory and rescued Idun. Thiassi chased them to the edge of Asgard, where he was killed by the Aesir. *See also* Aesir; Asynjor; Bragi; Loki; Sol (B); Thiassi.

Idyia *Eidyia* (Greek)
She is the daughter of Oceanus and Tethys, the spouse of Aeetes and the mother of Absyrtus and Medea. *See also* Absyrtus; Aeetes; Medea; Oceanus; Tethys.

Ie (Hebrew, Christian) *see* Jehovah.

Iegad (Pelew Islands)
Sun deity. The god who brought light to earth.

Iella (Antilles)
Mother goddess. Mother of the dual god Iocauna and Gaumaonocon. In legend she is a supreme being with five names. The other four names are Atabei, Mamona, Guacarapita, and Guimazoa. In another list, four names are given: Atabei; Gaumaonocan; Iocauna; Zemes.

Iemhetep (Egypt) *see* Imhotep.

Iermaogauacar (Antilles) *see* Iocauna.

Iesous (Greek) *see* Jesus.

Iesu (Hebrew) *see* Jesus.

Ieu (Hebrew) *see* Jehovah.

Ieui (Hebrew) *see* Jehovah.

Ifa (Yoruba People, Africa)
Also known as: *Fa* (Fon People), *Ifa-Eschu* (possibly), *Orunmila.*
God of wisdom and knowledge. Fire god. The name Ifa refers to the deity and to his oracle. There are conflicting legends pertaining to Ifa's origins. Some say that he came to earth with other deities at the beginning of time. His wisdom was necessary to establish order in the world. In early days, before the great division between heaven and earth, Ifa traveled frequently to consult with the supreme deity, Olodumare. One day on earth a family squabble developed and one of his eight children insulted him. He journeyed back to the celestial realm to live. His permanent departure left the earth in chaos and confusion. Food was scarce, disease was rampant and women became barren. The children were sent to beg their father's forgiveness. After an arduous trip they finally found Ifa ensconsed under a palm tree in heaven and he refused to budge. He gave his children each a kit containing sixteen palm nuts to be used for communication and divination. Through these tools he conveyed the desires of mortals to the deities and the will of the deities to the mortals. Ifa is also connected to Eshu. Eshu collected and read palm nuts from a miraculous palm tree, which was Ifa, thus satisfying the hunger of the gods. Sometimes Eshu is the servant of Ifa, to whom he is forced to surrender the art of divination; sometimes it is Ifa who has the art, and Eshu forces Ifa to give him part of the knowledge. Eschu loves to test the character of people. Ifa, also known as a fire god, was worshiped under the emblem of the palm nut with sixteen stones, each stone had three or four eyes likely similar to the kits he gave his children. *See also* Eshu; Fa (A); Olodumare; Orunmila; Shango.

Ifgdrasil (Teutonic) *see* Yggdrasil.

Ifilici Wacinaci (Arawak People, South America)
Also known as: *Great Father, Wa Cinaci, Wa Murreta Kwonci.*
Probably a creator or culture hero. He may be the same as Wa Cinaci and Wa Murreta Kwonci. These names seem to mean "Maker" or "Great Father."

Ifing (Teutonic)
Ifing is a stream or river on the broad Plain of Idawold in Asgard in the upper sky where Odin set up his council. The water in this stream never froze. This is where Odin gathered together the twelve gods known as the Aesir and the twenty-four goddesses known as the Asynjor, to make a pact of harmony. Weapons and tools are made in Ifing. Ifing separates the realms between the giants and the gods. *See also* Aesir; Asgard; Asynjor.

Ifrit (Arabic) *see* Afrit.

Ifrits (Middle Eastern) *see* Jin.

Igaluk (Eskimo)
Sun deity. Alaskan name of the god of the Moon.

Iggdrasil (Teutonic) *see* Yggdrasil.

Igigi (Babylonian; Mesopotamia)
The Igigi, assistants to the chief of the gods, Anu, and other high gods, are the spirits of heaven who appear as stars. They are called upon before battles. With the Annunaki, they are the hosts of heaven and earth. Some writers do not differentiate between the Igigi and Annunaki. Others specify that the Annunaki are the spirits of earth. The Igigi and Anunnaki are the offspring of Anshar and Kishar, and Ellil (generally called Enlil) was their ruler. In other renditions, Ishtar is their leader. Marduk created the Anunnaki. *See also* Anshar; Anu; Anunaki; Apsu; Enlil; Ishtar; Kishar; Marduk.

Igirit (Hebrew) Ruler of Demons. *See also* Agrat Bat Mahalat.

Ignerna (British) *see* Arthur.

Ignis (Teutonic, Roman)
Deity of fire. Son of Manus, the mythical father of the Teutons. Associated with the Caberi and Vulcan (qq.v.).

Iha-haga-hime (Japan) *see* Kaya-No-Hime-No-Kami; Ninigi.

Iha-naga-himi (Japan) *see* Iwa-naga-hime.

Iha-no-hime (Japan)
Goddess of prosperity and long life. She is the very jealous wife of Nintoku.

Iha-tsutsu No Wo (Japan) *see* Izanami.

Ihasutsu-nome (Japan) *see* Izanami.

Ihi (Egypt)
Also known as: *Ahi.*

"The Sistrum Player." Deity of music. He is the son of Hathor and Horus. The sistrum is the musical instrument that is sacred to Hathor. *See also* Sistrum.

Ihi-yori-hiko (Japan)
Fertility deity. One of the four faces of Futa-na Island.

Ihoiho (Polynesia Society Islands)
Creator. Creator god who was followed by Timo-taata.

Ihuitimal (Toltec People, Mexico) *see* Mixcoatl.

Ihy (Egypt) *see* Hathor.

Ijaksit-Khoton (Siberia) *see* Ajysyt.

Ika-tere (Polynesia)
Father of fish. Brother of Tu-te-wehi and son of Tangaroa. *See also* Tangaroa; Tu-te-wehi.

Ikiti-simapine-no Mikoto *Ikiti-sima-pime-no-mikoto* (Japan) *see* Amaterasu; Three Goddesses of Munakata.

Iksion (Greek) *see* Ixion.

Ikto (Sioux People, North America)
He is the inventor of speech for mortals.

Iku-tu-pikone-nomikoto (Japan) *see* Amaterasu.

Il (Ugarit) *see* El.

Ila (A) (India) *see* Sarasvati.

Ila (B) (India) *see* Ida.

Ilabrat *Ili-abrat* (Babylonia, Sumer)
Also known as: *Ninsubur, Papsukkal, Papukkal.*
Ilabrat is the messenger sent by Anu to inquire why the south wind stopped blowing. This relates to the legend of Adapa breaking the wings of the southwest wind she-demon, Shutu. Some say he is shown with a staff or wand in his right hand. He is sometimes identified with Ninsubur. *See also* Adapa; Ninsubur; Papsukkal; Tammuz.

Ilah (Ugarit) *see* El.

Ilaheva (South Pacific)
The earth goddess spouse of the sky god Eitumatupua (q.v.).

Ilamatecuhtli *Ilamatecutli* (Aztec People, Mexico)
Also known as: *Old Mother, Tonantzin.*
This is a name for Tonantzin. In this form, Ilamatecutli is represented as the Earth Toad. She is a mother goddess, corn goddess, fertility goddess and the lord of the thirteenth hour of the day. The Earth Toad is shown swallowing a stone knife. *See also* Lord of the Day Hours; Tonantzin.

Ilancue *Ilancueitl* (Aztec People, Mexico)
Also known as: *The Old Woman.*
First goddess or Earth goddess. She is the wife, possibly first wife, of Ixtacmixcoatl. They are the ancestors of the People of Mexico. *See also* Chimalmatl; Ixtacmixcoatl.

Ilancueitl (Aztec) *see* Ilancue.

Ilat *Alilat* (Arabic)
She is an early mother goddess who has been likened to Aphrodite. *See also* Alilat.

Ilavida (India)
Ilavida is the mother of Kuvera and the spouse of Vishravas (q.v.).

Ildebaoth (Gnostic) *see* Abraxas.

Ile-gbigbona (Africa) *see* Sonponno.

Ile-titu (Africa) *see* Sonponno.

Ilem (Slavic) *see* Ilmarinen.

Ilhallubu (Babylon) *see* Adad.

Ili-abrat (Sumer) *see* Ilabrat.

Ilias (Arab) *see* Elijah.

Ilinbongasum (Saora People, India)
God of the rainbow. *See also* Adununkisum.

Ilithyia (Greek) *see* Ilythia.

Ilithyiae (Greek) *see* Ilythia.

Illa (Haiti) *see* Atabei.

Illa Ticci *Illa Tici* (Peru) *see* Viricocha.

Illillos (Sumer) *see* Enlil.

Illinus (Babylon) *see* Aus; Belus (B).

Illiyun (Islamic)
The seventh stage in Islamic Paradise. This is where the register of good deeds is kept.

Illuyankas (Hittite)
The storm god killed this giant serpent with the help of the goddess Inaras. She enlisted the assistance of a mortal named Hupasiyas. He agreed to aid her only if she slept with him, which she did to accomplish her goal. *See also* Inaras.

Illyrius (Greek)
He is the son of Cadmus and Harmonia. His siblings are Agave, Autonoe, Ino, Polydorus and Semele. *See also* Ino; Semele.

Ilma (Slavonic, Finnish)
God of the air. He is the father of Luonnotar who was the mother of Vainamoinen who in turn was a creator. Other references call Luonnotar the creator and the daughter of Ilma. *See also* Ilmarinen.

Ilmaka (Himyarite People, South Arabia)
War deity. Called the smiter.

Ilmaqah *Ilmuqah* (Semitic) Moon god. *See also* Allah; Elohim.

Ilmarinen *Ilmaris, Ismaroinen* (Finnish, Lithuanian, Slavic)
Also known as: *Ilem, Ilma, Inmar, Jen, Jumala, Jumla, Sangke.*
Smith god. Ilmarinen is the son of Ilmatar. He is the brother of Vainamoinen and Lemminkainen. His wife is Kildisin, the daughter of the sorcerer Pohja. Ilmarinen forged the sun. He also forged the magic mill known as Sampo with the point of a swan's feathers, milk from a sterile cow, a grain of barley and the wool of a ewe. There are stories about Ilmarinen and his brothers attempting to steal the Sampo and while doing so,

www.ebook3000.com

breaking it. In later versions of his myth we find that his spouse Kildisin has merged into Virgin Mary. Ilmarinen is associated with the hero, Vainamoinen. Compare Ilmarinen to the Vedic god Tvastri, and the Celtic god Goibniu. *See also* Ilma; Ilmatar; Jumala; Kalevala; Pohja; Sampo.

Ilmaris (Finland) *see* Ilmarinen.

Ilmatar (Finland)
Creator. Hero. This androgynous goddess (sometimes known as a hero) is the daughter of the god of air Ilma, mother of the creator of the sun Ilmarinen, the magician, Lem*minikainen* and the god of music Vainamoinen. In her female form she is a creator of all. (In some myths, Luonnotar is the mother of Vainomoinen.) *See also* Ilmarinen; Lemminikainen; Luonnotar; Vainamoinen.

Ilu (Ugarit) *see* El.

Ilumarru (Babylon) *see* Adad.

Ilus (A) (Greek) He is the son of Dardanus and Bateia (qq.v.).

Ilus (B) *Iulus* (Greek)
Also known as: *Ascanius*
He is the son of Aeneas and Creusa. His name links him with Ilium (Troy). It also links him with the Julian family of Julius Caesar and Caesar Augustus. *See also* Aeneas; Creusa.

Ilus (C) (Greek) Mermerus, the son of Pheres, is his father.

Ilus (D) (Greek)
The wrestler. Fourth king of Troy. His parents are Tros and Callirrhoe. His siblings are Assaracus, Cleopatra and Ganymede. He married Eurydice and became the father of Laomedon and Themiste. Ilus won fifty young men, fifty young women and a cow in the wrestling division of the Phrygian Games. Zeus gave Ilus the Palladium. A prophet told him to build a city on the spot where his cow would lay down. He named the city Ilion which was later changed to Troy. *See also* Anchises; Callirrhoe; Eurydice (C); Ganymede; Theano.

Ilyas (Islamic) *see* Elijah.

Ilyasin (Islamic) *see* Elijah.

Ilythia (Greek) *see* Eileithyia.

Im (Akkadian, Babylonian) God of storms. *See also* Rimmon.

Imana (Warundi People, Africa)
Supreme being. Chief of the Ancestral Spirits of the race.

Imaymana Viracocha (Inca)
Imaymana Viracocha is the son of the creator, Viracocha, and brother of Tocapo Viracocha. Viracocha sent his sons out to visit the people after the Great Deluge and the Creation. The brothers were to ensure that the people were still following the commandments they had been given. As they travelled, they named the different varieties of trees, bushes, plants, fruits, flowers and told the people which could be eaten or which would have curative powers and which varities were dangerous to their health. *See also* Manco Capac; Viracocha.

Imberombera (Australia)
Another name for the mother goddess, Waramurungundja (q.v.).

Imbrogeneis (Greek) *see* Curetes; Telchines.

Iment (Egypt) *see* Ament; Amenti.

Imgig (Sumer) *see* Zu.

Imhetep (Egypt) *see* Imhotep.

Imhotep *I-em-hetep, Iemhetep, Imhetep* (Egypt)
Also known as: *Imuthes* (Greek).
Deified mortal. God of learning, medicine and wisdom. God of builders. Imhotep was the architect of the Step Pyramid at Sakkara and an official of the pharaoh Zoser in the Third Dynasty. He was one of the few Egyptian mortals to obtain deification which in his case occurred two thousand years after his death. Memphis was the seat of his worship. Some say he was the scribe of Thoth. He is identified with the Greek Asclepius. *See also* Amenhotep, son of Hapu.

Imhursag (Sumer) *see* Ishkur.

Imi Kashiki No Mikoto (Japan) *see* Ama-no-minaka-nushi.

Immer (Sumer) *see* Ishkur.

Imra *Amra* (Kafir People, Afghanistan)
Also known as: *Dagun, Yamri.*
Supreme deity. Little known name for the supreme god by the Kafir people.

Imseti (Egypt) *see* Mesta.

Imsety (Egypt) *see* Horus.

Imuit (Egypt)
Deified object. Actually a fetish of one of the early gods, or possibly the name of one of the ancient deities. It is associated with Anubis and Osiris.

Imuthes (Greek) *see* Imhotep.

Imy-Hemef (Egypt)
"Dweller in His Flame." This serpent is fifty feet long. He lives on top of Bakhau, the Mountain of Sunrise.

In (Japan) *see* Yo.

In-shushinak (Elamite) *see* Adad.

Ina (Polynesia)
Also known as: *Hina, Hine, Sina.*
Heroine. Her spouse is Tinirau, and her sister, Rupe (also known as Ru). She has two children whose names are not mentioned. She is likely the same as Hina (q.v.). *See also* Tinirau.

Ina-gami Furu-kushi-nada-hime (Japan) *see* Kushi-nada-hime.

Ina-Init (Philippine)
Sun god. He is the husband of Aponbolinayen.

Inachus (Greek)
Also known as: *Inaclius.*
River god. In some myths Inachus is the son of Oceanus and Tethys, a river god of the river Inachus and the first king of Argos. In other versions, he is not a deity, but is the first king of Argos, who named the chief river of Argos after himself. As

the son of Oceanus and Tethys, he married his sister, the ash nymph Melia and they became the parents of Phoroneus and Aegialeus and a daughter, Io. Others say that Io's father was Iasus and that Argia was the mother of Io and Phoroneus. It is said that when Hera and Poseidon were quarrelling over who should receive the Argolis, Zeus intervened and asked the river gods Inachus, Cephissus and Asterion to make the decision. They decided in favor of Hera. This infuriated Poseidon who in retaliation dried up their river beds permitting them water only after the rains. Inachus was the first to worship Hera and his daughter Io became her priestess. It is said that the goddess Athena as Pallas Athena bathed in the waters of Inachus every year to restore her virginity. Hera also conducted a similar ritual in a spring known as Canathus. To compare to other river deities, *see* Achelous; Acheron; Alpheus; Asopus; Cephissus; Cocytus. *See also* Apsyrtus; Argus (B); Hera; Io; Meliae; Oceanids; Oceanus; Rivers; Tethys.

Inaclius (Greek) *see* Inachus.

Inadjet (Egypt) *see* Buto (A).

Inagami-Hime (Japan) *see* Kushi-nada-hime.

Inagi-Utasunhi (Cherokee People, North America)
Evil deity. The Dark Twin, a wild boy.

Inanna (A) (Sumer)
Also known as: *Annis, Ishtar* (Babylonian), *Tamar* (Hebrew).
Inanna, an earth goddess, grain goddess, goddess of date groves, and a goddess of wine and love, is also known as Queen of Battles. She is probably the daughter of Ningal, who is the wife of Nana. Inanna's sisters are Nanshe, Ninisinna, Ninmug, Nidaba, and Ereshkigal, and perhaps Anunit. Her brothers are Utu and probably Shamash. After the dilemma of making a choice between the shepherd god Dumuzi and the farmer god Enkidu, she decided to wed Dumuzi, although Utu thought that Enkidu would make the better mate. In some renditions, Inanna preferred Enkidu but Dumuzi was determined to wed her. During the summer month of either July or August, Inanna decided to travel to see her sister Ereshkigal, the Queen of the Underworld. In some versions of this myth, her reason for the descent is not clear. Other interpretations explain that she wanted to attend the last rites for Gulgallana, the husband of Ereshkigal. Before her departure, she instructed her vizar, Ninshubur, that if she did not return in three days, he should begin mourning rites for her. Further, she told him to inform the high gods, Enlil, Nanna and Enki, of her whereabouts and have them intercede on her behalf so that she would not be put to death. She had to pass through a series of seven gates. Neti, the gatekeeper, asked her why she was visiting the place of no return. After her explanation, he instructed her to leave a piece of clothing at each gate, as was the custom. Naked, she finally reached her sister and the seven judges, known as the Anunnaki. She was turned into a corpse and hung on a stake. She was informed that there was only one way out of the underworld: one could return to the upperworld if a substitute was provided. In the meantime, the three days had passed and Ninshubur approached the gods as he was instructed to do by Inanna. Enlil and Nana did not want to be involved. Enki performed magical rites and created two creatures from his fingernail. They went into the underworld and sprinkled her corpse sixty times with the water and food of life. Revived, Inanna was allowed to leave accompanied by demons who were to return with her substitute. The demons claimed several substitutes whom Inanna refused to allow be taken: the vizar Ninshubur, Shara the god of Umma, and Latarak the god of Badtibira. Grateful for being spared, they humbled themselves before Inanna. Inanna and the demons traveled on to Dumuzi's domicile in Erech where he reigned as king. He was not at all upset that his wife had been in the underworld. Enraged, that he was not in mourning for her she instructed the demons to take him as her substitute. Later, relenting, she was able to make arrangements that Dumuzi and his sister Gestinanna would each spend six months in the underworld. In another myth about this ambitious goddess, she wanted the benefits of civilization to be conferred on the people in her city of Erech. Not only would it prosper the community, it would enhance her image politically. To accomplish this goal, she had to acquire the "Me," or decrees of civilization, which are similar to the Tablets of Destiny. The Me were in the custody of the god Enki in the Sumerian Eridu. She traveled to his domain in her ship, the *Boat of Heaven.* When she arrived, she was invited to join Enki at a banquet. Smitten by her, and later inebriated, he gave her the precious Me. She loaded over one hundred tablets on her *Boat of Heaven* and set sail for the voyage home. In the meantime, Enki, now sober, was informed by his messenger Isimud that he had given the tablets to Inanna. Upset, he sent Isimud and a group of sea monsters after the ship. When they reached Inanna, Isimud attempted to retrieve the tablets through civilized verbal communication. Inanna, determined not to relinquish her treasures, became furious that Enki had broken his word. She had Ninshubur rescue her, the tablets, and the ship. This was not to be the end of story. Enki was as determined to get his tablets back as Inanna was to keep them. Despite numerous additional onslaughts from the sea monsters, in the end, the victorious Inanna arrived in her port with her precious cargo, the Me. The ritual practices of Inanna and the Babylonian Ishtar were similar. Inanna was preceded by Belili (q.v.). Inanna has attributes similar to those of Ninhursag (q.v.). She is also identified with the Hebrew goddess Tamar. *See also* Anunnaki; Anunit; Dumuzi; Enki; Enkidu; Enlil; Ereshkigal; Gestinanna; Innini; Ishtar; Nana; Nanshe; Nidaba; Ninedinna; Ninsun; Shamash; Utu.

Inanna (B) (Babylonian)
Known as the "Mistress of Heaven," she is a mother goddess.

Inapatua (Australia) *see* Inapertwa.

Inapertwa *Inapatua* (Aborigine People, Australia)
Creators. The first rudimentary humans or incomplete men. Their form was indistinct, consisting of rounded shapes. The two highest gods (unnamed) came down and separated the various parts to make human beings. *See also* Numbakulla.

Inar (Hittite)
Destroyer of serpents. Inar once killed a great serpent and its family by feeding them so much food they could not get back in their holes.

Inaras (Hittite)
This goddess promised to sleep with the hero Hupasiyas if

www.ebook3000.com

he would kill the dragon Illuyankas and his offspring. Hupasiyas, with the help of the thunder god, killed the dragon, and Inaras kept her promise. *See also* Illuyankas.

Inari *Inari-m'yojim* (Japan)

Also known as: *Uka-no-kami, Httsui-no-kami*

Deity of rice, property and prosperity. Patron of swordsmiths and tradespersons. As Httsui-no-kami, deity of kitchen. An androgynous deity, Inari is also portrayed as goddess and often referred to as a vixen. As the goddess she is depicted as a fox and is often worshiped as a fox. Inari is associated with fire and smith-craft. As the god, he is depicted as a bearded old man with his attendants and messengers, two foxes. He is also shown sitting on a sack of rice or balanced on the back of a fox and holding two bags of rice. Inari's messenger is Kitsune, a bewitching fox, who is also the guardian of the rice crop. Geishas and prostitutes are sometimes spoken of as kitsune (foxes). The fox, of great magical importance in Japan, was feared for its malice. Depression and insanity are often attributed to the fox-spirit. In China, the fox is known as a sly companion of fairies. On the first day of the Horse (Hatsu-uma) in February, a major festival was held and Inari was a deity honored. On November 8, another festival, known as the Festival of the Goddess of the Kitchen Range, or the Feast of Bellows (Fuigo Matsuri) was held in Inari's honor. Here she is known as Httsui-no-kami. Other kitchen deities include Oki-Tsu-Hiko, Oki-Tsu-Hime and Kamado-no-kami. On this day, fires were lit to honor numerous deities, including Inari. The Romans had a goddess of ovens known as Fornax. The oven is a mother-symbol connected with food-producing and food-giving. The workings of witches and magic are connected with the kitchen and include the range, the oven or the hearth. The principal temple erected in honor of Inari is at Fushimi, near Kyoto. Inari is associated with and sometimes confused with Uke-mochi, the food goddess. *See also* Vesta.

Inari-m'yojim (Japan) *see* Inari.

Inca — Creation Legend (Peru) *see* Apocatequil; Coniraya; Irma; Mama Occlo; Mancho Capac; Pacari; Viracocha.

Incubi (Medieval European) *see* Incubus; Succubus.

Incubus *Incubi* (plural), *Succubus* (female) (Medieval European)

A supernatural being neither wholly good nor wholly evil. Known as the demon lover, an incubus fathered Merlin, Arthur's counselor. They are male spirits of evil dreams and nightmares. During the Middle Ages, it was believed that the incubus had intercourse with sleeping women. Unexplained pregnancies could conveniently be attributed to a virgin birth, and blamed on the incubus. Often the birth of twins, or babies born with birth defects were said to be the children of an incubus. These demons are often handsome, though smelly, with cloven feet. The incubus is comparable to the Celtic Dusii and Samoan Hotua Poro. *See also* Bhutas (Hindu); Demons; Jinn (Medieval Europe); Satyrs (Greek); Succubus.

Inda (India) *see* Indra.

Indech, King (Celtic) *see* Domnu.

Indra (Buddhist, Hindu, Vedic; India)

Also known as: *Aindri, Inda* (Buddhist), *Indra-nag, Indrani, Lord of the Gods and Destroyer of Their Enemies, Mahendra, Pakasasana, Parjanya* (Rain-bringer, name used in later myths), *Puramdara, Sahasramuska* (Thousand Testicled One), *Sakra, Satakratu, Skambha* (Support), *Taishaku* (Japan), *Vajrapani, Vritrahan* (Slayer of Vritra), *Vritrahana, Vrtrahanna.*

Indra is variously known as a supreme deity, a storm god and god of the atmosphere. In Vedic accounts, Indra is the son of the sky god Dyaus and the earth goddess Prithivi. Born from his mother's side, he was hidden and ignored at birth. His parents and the gods thought that his arrival would upset the universe and perhaps lead them to their doom. Hiding him was not the answer, for he made himself known from his earliest days. The chief of the Vedic gods, he is called the Mighty Lord of the Thunderbolt, Cloud-gatherer, and the Sender of Rain and its Fertility. In Hindu accounts, Indra is the son of Dyaus and Nistigri. It is also said the Mother of All Gods, Aditi, is either the mother of or the attendant to Indra. Some say his father was Tvashtri, the artisan deity who created the indestructible vajra. Energetic and impulsive, Indra was addicted to soma. It is possible that his first drink of the intoxicating nectar came from his mother's breast. Fortified by the beverage, he took his father's vajra (thunderbolt) and set out to battle the demons who plagued the land (*see also* Varcin). His consort is the jealous, lascivious Indrani, his son, Sitragupta. In some renditions, he is the twin brother of Agni. In one myth, he was ripped to pieces and reassembled by the gods. They were unable to find his penis and had to attach the member of a ram to Indra. He overcame the serpent Vritra with the advice and aid of Vishnu and fought against other demons. His home, Swarga (Vaijayanta), located between heaven and earth on Mount Meru was filled with dancers and musicians. His servants were demigods known as the Vasus. With Agni and Surya, he formed a triad of the major Vedic gods. Many Vedic hymns are in honor of Indra. He is the king of the gods, god of storms, slayer of demons, destroyer of fortresses and compeller of clouds. He befriended the outcast, the weak and the oppressed. After Indra killed the darkness and drought dragon, Vritra, he was looked upon with favor by the gods. Indra's assistants are the Maruts, subordinate, warrior-like storm gods who drink soma to fortify themselves for battle. Not always ethical, he was a treacherous fighter and could be unfair. A swaggering war god, he flew across the sky in his solar chariot wielding a thunderbolt. Yet, he exhibited human traits. The thunderbolt he used as a weapon was also used to bring the dead to life. Although he is a god, his conquests were not always accomplished alone. Often other deities intervened on his behalf. Indra is invoked to send rain during times of drought. He is often depicted with the vajra (thunderbolt) in his right hand and a bow in the other, or with a second pair of arms, holding lances. He is fair-complexioned, with ruddy cheeks, a red beard and shoulder length golden hair. He rides a horse and is depicted with his driver, Matali, in a flaming chariot drawn by two tawny horses with flowing tails and manes. Sometimes the horses are gold and red and are known as the Harits. Indra is symbolized by the bull. One of his symbols is the owl, indicating power. His vajra (thunderbolt) is the symbol of divine or mystic energy. It also symbolizes the male principle and the axis of the universe. His other weapons are the bow, net and hook (anka). It is said that Indra's long arms spanned the skies. In later times, he was depicted with a dog (*see* Yama). As a cattle-raider, he is associated with the horse and the bull. (The cattle are the clouds.) He is shown seated on his four-tusked elephant named Airavata (rain cloud). Airavata sprang from the churning sea of milk when the universe was created. Indra carries the elephant goad (lightning) and the vajra (thunder). He is sometimes depicted with seven arms holding a diadem, discus (chakra), elephant goad (ankusa), prayer beads, sickle, axe (tanka) and thunderbolt. Indra is said to be the personification of the great summer monsoon of north India. The Vedic horse is the symbol of the breath (Prana). To yoga practitioners, Indra's two horses can represent inhalation and exhalation. His chariot can symbolize the inner practice of yoga. Indra symbolizes the awakened life-force in yoga practice. The slaying of the dragon and the release of the seven rivers, symbolizes Indra as the pure life force that destroys the negative energy of disease and ignorance. Soma represents the fruit of the sacred tree or tree of knowledge. The magic arts, taught by Indra, are known as Indrajala. Another deity by the name of Indra is part of the Daeva group of deities. In ancient Persian mythology, Indra was a minor deity, known as Andra, a Daevas (evil spirit) who opposed Asha Vahista. (*See also* Devas.) As Andra, he waits on the bridge named Cinvat and heaves souls into hell. Indra is somewhat like Thor, the thunderer of Norse religion, and the Roman god of war, Mars (q.v.). As Indra-nag, he is depicted as a crowned king with a bow, attended by the serpent Nagas. Indra is equated with Varuna, who some say was ousted by Indra. In the Buddhist tradition, Indra is known as Inda and is subservient to Buddha. *See also* Kurma and Lokapalas regarding Airavata. Compare Indra with Horus (Egypt), Tiamat (Babylonia), and Verethraghna (Persian). Compare to Uranus and Cronus (Greek). *See also* Aditi; Adityas; Agastya; Ahalya; Arjuna; Asuras; Asvins; Bali (A); Bhishma; Brihaspati; Daityas; Deva (A), Deva (B); Dikpalas; Diti; Dyaus; Gandharvas; Garuda; Hanuman; Heng and Ha; Hiranyaksa; Indrani; Kamadhenu; Karna; Karttikeya; Krishna; Kunti; Loka; Lokapalas; Maruts; Meru Mountain; Mitra; Nagas and Nagis; Pandavas; Parjanyi; Parvati; Pramloka; Prithiva; Ratri; Ravana; Ribhus (The); Sakra; Samantabhadra; Shiva; Skambha; Soma; Surabhi; Surya; Surya-Bai; Swarga; Tvashtri; Ushas; Vach; Varuna; Vasus; Veda (The); Visvakarma; Vritra; Yama.

Indra-nag (India) *see* Indra.

Indrajala (India) Magic Arts. *See also* Indra.

Indrajit (India) Conqueror of Indra. *See also* Ravana.

Indranee (India) *see* Indrani.

Indrani *Indranee* (Nindu, Vedic; India)

Also known as: *Aindra, Aindri, Paulomi-vallabha* (Lover of Paulomi), *Saci, Saki* (Sanskrit), *Shakrani* (Sanskrit).

Indrani, the goddess of sexual pleasure, is the daughter of Puloman and is a reflection of her husband Indra. She is a highly sexual, eternally youthful, jealous, war-like woman. When Indra appeared to be spending too much time with the ape Vrishakapi, Indrani cast her burning eyes on him and he was filled with lust for her. Indra appeared and drove the ape away. Later, Indra was caught by Vrishakapi in a comprising situation with Vrishakapi's wife. In time, Indra and Vrishakapi rekindled their friendship. Indrani had good reason for her jealousy. Her mate had a passion for women, particularly married women. He had another affair with the first woman created by Brahma, Ahalya, who was the wife of his teacher, Gautama. Indra and Indrani had a son, Sitragupta. Indrani owns the Kalpa, also known as the Parijata Tree. It is kept in Swarga, the celestial dwelling place of Indrani and Indra. Swarga is located between heaven and earth on Mount Meru. If the elderly gaze upon the magic wishing tree, they are reinvigorated. Other records indicate that Indrani was either married to or was the lover of Paulomi. Indrani is portrayed as a beautiful and sensual fair-complexioned woman. Compare Indrani to Lakshmi and the Greek Venus. Compare the Parijata Tree to Soma and Amrita (q.v.). *See also* Ahalya; Indra; Meru Mountain; Parijata; Ribhus; Satyabhama (third wife of Krishna); Swarga.

Indraprastha (India)

Celestial palace. *See also* Pandavas; Visvakarma.

Inet (Egypt) *see* Aai.

Ingi (Teutonic) *see* Dwarfs.

Ingnersuit (Eskimo) *see* Inue; Tornaq.

Ingui-Frey (Teutonic) *see* Freyr.

Ingun (Teutonic) *see* Freyr.

Ingunar-Frey (Teutonic) *see* Freyr.

Ingvi-Frey (Teutonic) *see* Freyr.

Ini-Herit (Egypt)

Also known as: *Onuris* (male).

Goddess of mediators, diplomats, statesmen and conciliators. When the goddess Tefnut became angry and bore the sun away, it was Ini-Herit who sought after her, calmed her and returned the sun to the sky.

Ininguru (Australian)

Goddesses of women. Possibly healing deities. Associated with the secret fertility rites of women. They travel across the desert to participate in the rites, and then return to the sky. They do appear now and then to see what is going on.

Inle (Yoruba People, Africa) *see* Olodumare.

Inmar (Finland) *see* Ilmarinen.

Innini (Sumer)

Also known as: *Inanna, Ninanna, Ninhursag, Ninki, Ninsinna, Nintud.*

Mother goddess. Although known in various aspects and different names, most say she was created by Anu and is his female counterpart. *See also* Astarte; Belit-ili; Dumuzi; Ereshkigal; Inanna; Ishtar; Ninhursag; Ninki; Nintud.

Innua (Eskimo) *see* Manitou.

Ino (Greek)

Also known as: *Leucothea, Mater Matuta* (Roman), *The White Goddess.*

Ino is the daughter of Cadmus of Thebes and Harmonia.

www.ebook3000.com

Her siblings are Agave, Autonoe, Illyrius, Polydorus and Semele. She married Athamas and became the mother of Learchus and Melicertes and the stepmother of Helle and Phrixus (their natural mother was Nephele). Ino and her sisters, Agave and Autonoe, spread rumors that Zeus was not the father of their dead sister's son, Dionysus. Nonetheless, Hermes persuaded her to raise Dionysus as a female to outwit the jealous Hera. Suffering from divine madness, Ino helped her sister Agave rip her son Pentheus to pieces. She also attempted to murder her stepchildren but they were able to escape on a winged golden ram. Hera was able to drive Ino and her husband insane and they killed their own children. Dionysus survived this madness because Zeus had Hermes take him to the nymphs of Nysa who resided on a mountainside near Helicon and there he stayed, possibly in the form of a lamb until manhood. In another version of her story, Ino was insanely jealous of Nephele, Athamas' first wife, and she took it out on her stepchildren by treating them cruelly. She fled to the sea with Athamas in pursuit and in a moment of madness she dove into the water with Melicertes. It is said that the Nereids accepted them as one of their own and Ino became the goddess Leucothea and Melicertes became Palaemon. As sea deities they came to the aid of sailors in distress and it is said that Leucothea once saved Odysseus from death. *See also* Dionysus; Harmonia (A); Mater Matuta; Nephele; Persephone; Portunus; Semele.

Inti *Intu* (Inca People, Peru)
Also known as: *Apu-Punchau.*

Inti or Apu-Punchau is the Peruvian name for the sun. In some legends, Inti is the sun god, father of Choun (also known as Viracocha), Pachacamac and Manco Capac. Other versions name him the brother/husband of Mama Quilla. Inti crosses the sky daily and plunges into the western sea. After swimming under the earth he reappears each morning. Eclipses are caused by his anger. He is depicted as a human with a bright face surrounded by rays and flames. Children and animals were sacrificed to Inti, Pachacamac, and Viracocha annually at a festival in their honor. In some legends he is associated with Tutujanawin (q.v.). *See also* Mama Quilla; Manco Capac; Pachacamac; Tupan; Virococha.

Intu (Inca People, Peru) *see* Inti.

Inua (Eskimo) *see* Manitou; Tornaq.

Inuat (Eskimo)
Also known as: *Inua, Inue, Tornaq.*

The spirit or doppelganger (sometimes called the "owner") of all living creatures, and everything in nature has this spirit, including non-living things. They live on after the death of the individual. Normally they are invisible, but sometimes can be seen as a light or fire, especially associated with foretelling death. *See also* Orenda; Tornaq.

Inue (Eskimo) *see* Inuat.

Io (A) (Greek)
Also known as: *Ida.*

Priestess of Hera. Cow goddess. Princess of Argus and daughter of Inachus (Inakhos). She was loved by Zeus who, to allay the suspicions of Hera, transformed her into a heifer. Hera was aware of the change and had the hundred-eyed Argus watch her. When Zeus had Argus killed by Hermes, Hera tormented Io with a gadfly, which drove her from place to place until she reached the Nile, where she recovered her human form and bore a son, Epaphus, by Zeus. The Greeks identified her with Isis. *See also* Adrastia; Apis (A); Apsyrtus; Golden Fleece.

Io (B) (Maori People, New Zealand; Polynesian)
Also known as: *Iho-Iho, Io-Mataaho, Io-Matua, Io-Matua-Te-Kora, Io-Nui, Io-Taketake, Io-Te-Toi-O-Nga-Rangi, Io-Te-Wananga, Io-Te-Whiwhi, Kore-Te-Whiwhia, Te-lo-Mate* (The God of Death), *Te-Io-Ora* (The Living God).

Supreme Being. All things flow from Io. The original creator, himself uncreated, he retains for himself the spirit and the life and the form. There is nothing outside or beyond him, and with him is the power of life, of death, and of godship. It is Io who selected Tane, the god of forests, to receive his secret knowledge. *See also* Papa; Rangi; Tane.

Io-Mataaho (Polynesia) *see* Io (B)

Io-Matua (Polynesia) *see* Io (B).

Io-Matua-Te-Kora (Polynesia) *see* Io (B).

Io-Nui (Polynesian) *see* Io (B).

Io-Taketake (Polynesia) *see* Io (B).

Io-Te-Toi-O-Nga-Rangi (Polynesia) *see* Io (B).

Io-Te-Wananga (Polynesia) *see* Io (B).

Io-Te-Whiwhi (Polynesia) *see* Io (B).

Iobates (Greek)
Also known as: *Amphianax.*

King of Lycia. He is the father of Philonoe and Stheneboea. When Bellerophon wanted to marry Stheneboea, Iobates sent him to fight the three-headed, fire-breathing Chimaera. When he safely returned, Iobates allowed him to marry Philonoe, not Stheneboea. *See also* Bellerophon; Chimaera; Proetus; Stheneboea.

Iocaste *Iokaste* (Greek) *see* Jocasta.

Iocauna (Taino People, Haiti)
Also known as: *Attabeira, Guamaonocon, Iermaogauacar.*

Supreme being. Iocauna is a supreme being known by two names, Iocauna and Guamaonocon. His mother has five names. They are usually listed as Iella, Atabei, Mamona, Guacarapita, and Guimazoa. In another list, four names are given: Atabei, Iermaogauacar, Apito, and Zuimaco. *See also* Atabei; Guamaonocon; Iella; Zemes.

Ioi (Chinook People, North America)
She is the sister of Blue-Jay (q.v.).

Iokaste (Greek) *see* Iocaste.

Ion (Greek)
Ion is the son of Apollo and Creusa (who was the wife of Xuthus). His is the brother of Janus, the Roman god of beginnings and endings. *See also* Achaeus; Creusa; Janus; Xuthus.

Iophossa *Chalciope* (Greek)
Another name for Chalciope, the daughter of Aeetes, king

of Colchis and Asterodeia. *See also* Aeetes; Asterodeia; Chalciope.

Iord (Scandinavian)
Goddess of earth. Daughter of Nott (Night).

Iormungandr (Teutonic) *see* Jormungandr.

Iouskeha (Native North American) *see* Ioskeha.

Iovialis (Roman) *see* Genius.

Iowahine (Hawaii)
First woman. Wife of Tiki. Both were formed from earth by Tane (q.v.).

Ipa Huaco (Inca) *see* Tahuantin Suyu Kapac.

Ipalnemoani *Ipalnemohuani* (Aztec People, Mexico)
Also known as: *Citlallatonac and Citalicue, Ometecutli and Omeciuatl, Tloque Nauaque, Tloquenahuaque, Tonacatecutli and Tonacaciutl.*
High god. One of the first Aztec gods. Called "He by Whom We Live," he was one of the unknown gods. In some versions, Ipalenemoani is a bisexual deity who is known by various names. *See also* Citlallatonac; Texcatlipoca; Tloque Nauaque; Tloquenahuaque; Tonacatecuhtli.

Ipalnemohuani (Aztec) *see* Ipalnemoni.

Iphianassa (A) (Greek)
She is the daughter of Proteus and Stheneboea (qq.v.). *See also* Iphinoe (A).

Iphianassa (B) (Greek) Another name for Iphigeneia.

Iphicles (Greek) *see* Argonauts; Eurydice (C).

Iphidamas (Greek) *see* Acamas (B).

Iphigenia *Iphigeneia* (Greek)
Also known as: *Chrysothemis, Iphianassa.*
Deified mortal. Daughter of Agamemnon and Clytemnestra. She was offered as a sacrifice to appease Artemis at the outbreak of the Trojan War. However, Artemis substituted her with a bear (some say a deer) and carried Iphigenia off to Tauris. She later became a priestess and saved the life of her brother Orestes when he was about to be sacrificed. Some say she is an aspect of Artemis and Helen. *See also* Achilles; Calchas; Orestes.

Iphimedeia (A) (Greek)
She is the daughter of Triopas, who is the son of Poseidon and Canace, and Hiscilla. Iphimedeia's siblings are Erysichthon, who sold his daughter into prostitution for food, and also descrated Demeter's grove, Messene, who married Polycaon, the first king of Messenia and Phorbas, the king of Thessaly, who fought Pelops (some say Phorbas is the son of Lapithus and Orsinome). Iphimedeia is the wife of her uncle, Aloeus and the lover of Poseidon. *See also* Aloeides; Aloeus; Erysichthon; Phorbas (A); Poseidon.

Iphimedeia (B) (Greek)
Her parents are Theseus, the hero king of Athens, and Helen of Troy. *See also* Helen; Theseus.

Iphinoe (A) (Greek)
She is the daughter of Proteus and Stheneboea or Anteia. Her siblings are Iphianassa, Megapenthes and Lysippe. The god of wine, Dionysus, or the goddess Hera, drove her insane. *See also* Anteia; Dionysus; Hera; Lysippe; Proetus.

Iphinoe (B) (Greek)
Her father is Nisus, the king of Megara. Erymede and Scylla are her siblings. She married Megareus and became the mother of Evaecheme, Evippus, Hippomenes and Timalcus. *See also* Erymede; Evippus; Hippomenes; Scylla.

Iphinoe (C) (Greek)
She is the daughter of Alcathous and Evaecheme. *See also* Alcathous; Iphinoe (B).

Iphitus (Greek)
An Argonaut. Iphitus is the son of Eurytus and Antiope. He was killed by Heracles. *See also* Antiope; Argonauts (Names of); Heracles.

Iphtimis (Greek) *see* Nefertum (Egypt).

Ipila (Melanesia)
Creator. He carved the first human from wood and brought it to life by painting the face with sago milk. Although he carved more humans at a later time, his first human, Nugu, was punished by Ipila and made to hold the earth on his shoulders. Compare Ipila to Atlas. *See also* Nugu.

Iqi-Balam (Maya) *see* Xumucane.

Ir-Kalla (Akkadian, Babylonia) *see* Irkalla.

Ira (A) (Sumer) *see* Irra; Nergal.

Ira (B) (India) *see* Kasyapa.

Ira-Waru (Polynesian) *see* Maui.

Iraj (Persian) *see* Airya.

Iraja (India) *see* Kama.

Iravat (India)
He is the son of Arjuna and Ulupi. *See also* Arjuna.

Irawaru (Oceanic) *see* Maui.

Irdlirvirisissong (Eskimo) *see* Idlirvirissong.

Irene (Greek)
Also known as: *Eirene, Pax.*
Goddess of peace. *See also* Eirene.

Irin Mage (Tupi-Guarani People, Brazil)
In one version of the Creation Myth, Irin Mage, a powerful magician, caused a deluge to extinguish the great fire caused by Monan, the creator god. In another myth, the brothers Tawenduare, the god of day, and Arikute, the god of night, are the heroes of the deluge. *See also* Arikute; Monan.

Irinyes (Greek) *see* Erinyes; Eumenides.

Iris (Greek)
Goddess of the rainbow. Messenger of the gods. Iris is the daughter of Thaumas and Electra and sister to the Harpies. As the messenger of the gods, particularly Hera and Zeus, the rainbow is her path. She is shown as a beautiful robed woman carrying a staff. Sometimes she has wings. *See also* Electra; Harpies; Thaumas.

www.ebook3000.com

Chapter III
Cosmic Chi Kung

Opening the Three Tan Tiens to the Six Directions

Introduction

Opening the Three Tan Tiens is a Chi Kung meditation that strengthens our connection to the universe, opening us up to the primordial force of the Cosmos and the energy within Nature. We are dynamically connected to the infinite. "As above, so below" is an echo of wisdom heard from sages and mystics throughout the ages. When we can connect to and absorb the energy that surrounds us, we are able to tap into the many splendors of the universe.

We exist because of the unique combination of the forces that are around and within us. The two main forces are electricity and magnetism. 'Bio-electro magnetism' is the western term for life force, and what the Tao refers to as Chi. For the last 5000 years, the Taoists have utilized this bio-electro-magnetic energy to enhance their way of life and establish a relationship with the universe. Bio signifies life, electro refers to the universal energies (yang) of the stars and planets and the magnetic force refers to the earth force (yin) or gravitational force present on all planets and stars. As we align ourselves with these forces, we become a conduit through which we can absorb and digest these energies through the body, mind and spirit establishing a direct connection with the universe. The Taoists recognized this connection and created the Chi Kung form of 'Opening the Three Tan Tiens to the Six Directions' to enhance our relationship to and our understanding of this connection.

Humans normally access bio-electro-magnetic energy through food and air. Plants take the universal energies of the sun and the magnetic energies of the earth and digest and transform them, thereby making these energies available to all living beings. Taoists believe that the food sources with the purest form of energy are the green leafy vegetables. These have taken sunlight directly into their cells. Rather than waiting until the energy in the universe is processed through plants, the Taoist goes directly to the source of this primordial energy. Through Chi Kung and meditation, the Taoists direct the energy of the universe precisely. Opening the Three Tan Tiens is a meditational Chi Kung exercise that focuses on how to directly tap into the source of energy all around us.

The Tao views human beings as lamps filled with fuel. Many people burn this fuel at very high intensity, without ever taking the time to replenish the oil in the lamp. Alcohol,

Irkalia (Babylonian) *see* Irkalla.

Irkalla *Ir-Kalla, Irkalia* (Babylon)
Underground or Hell. Counterpart of Island of the Blest. Land of "no return" beneath the earth. It is ruled by Nergal and his consort Ereshkigal. It is called the House of Dust and Darkness. Once entered, it can never be left. Some texts refer to Irkalla as an androgynous deity and as such a god or goddess of the underworld. *See also* Apsu; Dilmun; Hades; Hell.

Irkingu (Babylonia) *see* Marduk.

Irlek-Khan (Central Asia) *see* Erlik-Khan.

Irma (Inca People, Peru)
Also known as: *Pachacamac.*
He is a supreme deity who descended from the Sun and Moon. He quarrelled with Kon, a god of the Chimu people. After chasing the Chimu people into the sea he began a new race by creating three different eggs. A gold egg brought forth male nobles, a silver egg female nobles, and a copper for both sexes of the common people. Some mythologists say that Irma was probably a harvest god who was later renamed Pachacamac (q.v.).

Irmen (Teutonic) *see* Irmin.

Irmin *Ermine, Hermin, Irmen, Odin* (possibly); (Norse; Teutonic)
High god. Irmin was worshiped in parts of Germany. He may be the same as Odin. He uses a heavy chariot to ride the Milky Way which was called Irmin's Way. Compare Irmin to the Armenian Armenak. *See also* Odin.

Irnini (Babylonian) *see* Ishtar.

Iron Dirk (Teutonic) *see* Iarnsaxa.

Iroquois People — Creation Legends (North America) *see* Athensic; Enigorio and Enigohatgea; Itapalas.

Irra *Ira* (Assyro-Babylonian)
Also known as: *Gir, Girra, Nergal* (possibly).
Plague god. Underworld deity. God of pestilence. He is the cohort of An and he works for Nergal. *See also* Nergal.

Irsirra (Hurrite)
The son of Kumarbis. This spirit placed Ullikummis on Enlil's lap. *See also* Enlil; Kumbaris; Ullikummis.

Irus (A) (Greek)
Also known as: *Arnaeus.*
He was the attendant to Penelope's would-be lovers. Odysseus killed him in a boxing match. *See also* Odysseus; Penelope.

Irus (B) (Greek)
He is the son of Actor and Aegina. His siblings are Menoetius and Polymela. His children by Demonassa are Eurydamas and Eurytion. *See also* Eurydamas; Eurytion; Menoetius; Peleus; Polymela.

Isa (Hebrew) *see* Jesus.

Isakakate (Crow People, North America) *see* Isakawuate.

Isakawuate *Isakakate* (Crow People, North America)
Also known as: *Old Man Coyote, The Trickster.*
A trickster deity. Sometimes Isakawuate is the name used for the creator.

Isana (India)
"Ruler." A form of Shiva. *See also* Agni; Dikpalas; Shiva.

Isander (Greek)
His parents are Bellerophon, the son of Glaucus and Eurymede, and Philinoe, the daughter of Iobates. His siblings are Deidamia (who married Evander), Hippolochus (the father of Glaucus), and Laodamia (the wife of Sarpedon). *See also* Bellerophon; Evander; Glaucus; Sarpedon.

Isani (India) *see* Gauri.

Ischys (Greek)
He is the son of Elatus and Hippea. His siblings are Caenis and Polyphemus. He fell in love with Coronis but she was killed before their marriage. *See also* Caenis; Coronis; Polyphemus.

Isfenarmad (Persia) *see* Spenta Armaiti.

Ishi-kori-dome (Japan) *see* Ishikoridome-no-Mikoto.

Ishikoridome-no-mikoto *Ishi-kori-dome, I-shi-ko-ri-do-me* (Shinto, Japan)
Goddess of stone cutting and artisans. When the sun goddess Amaterasu withdrew into the depths of the cave named Ame-no-Iwato, darkness enveloped the earth. The deities convened and decided to commission the talented artisan Ishikoridome-no-mikoto to create a mirror that would entice Amaterasu from the cave. The goddess Ama-no-Uzume performed a frenzied dance known as the Karuga. The sun goddess, curious about the noise, peeked out of the cave, and attracted by her beautiful image in the mirror, was lured into the world. The darkness lifted and once again there was light. This famous mirror known as Kagami (also known as Yata-Kayami) became one of the three Insignia of the Throne. The goddess Ishikoridome-no-mikoto was later asked by Amaterasu to accompany her grandson Ninigi to earth when he took up his duties as the divine ruler of Japan. In Japan a mirror represents a woman's soul, knowledge, enchantment, history and principles. The mirror is an attribute of Amaterasu and Emma-O. The sacred mirror, Kagami is a symbol of purity. It is deposited in the goddesses' sanctuary at Ise. *See also* Ama-no-Uzume; Amaterasu.

Ishkhara (Babylonian, Hittite)
She is a goddess of love who is affiliated with Ishtar as a priestess. In another reference she is one of the deities who is called upon to listen to the believer (q.v.).

Ishkur *Iskur* (Akkadian, Hittite, Sumerian)
Also known as: *Adad, Enlil, Immer, Mer, Mermer, Mur.*
Wind god. Ishkur, who lives in the underworld known as Arallu, replaced Enlil as a god of the winds. In some renditions, he is known as a god of lightning who is the son of Enlil. He is sometimes identified with Adad and is possibly the same as Imhursag, the father of Ningirsu. *See also* Arallu; Enlil; Ningirsu.

Ishmael (Hebrew) *see* Ismail.

Ishtar *Istar* (Assyro-Babylonian; Akkadia, Chaldea, Semitic, Sidon, Sumer).

Also known as: *Absusu* (Sumerian), *Abtagigi* (She Who Sends Messages of Desire), *Agasaya, Ashtart, Ashtoreth, Athar* (Arabic), *Aya* (Babylonian), *Banitu* (possibly), *Belti* (Semite), *Bisi-Bisi, The Bride, Dilbar* (The War-provoking Evening Star), *Gamlat* (Babylonian), *Gumshea, Hanata* (Middle Eastern), *Inanna* (Sumerian), *Innini, Irnini* (possibly), *Kilili* (Queen of Harlots), *Meni* (possibly), *Minu-anni, Minu-ullu, Nin-kar-zi-da, Nin-khar-sagga, Nin-si-anna, Ninkarrak* (Sumerian), *Ninkasi, Ninlil* (Phoenician), *Sharis* (possibly an ancient name used by the Armenians), *Shaushka* (Hittite), *Shimti* (Akkadian; goddess of fate), *The Shrieker, Zanaru* (Lady of the Islands), *Zib* (evening star who stimulates sexual desire).

As a Babylonian goddess, Ishtar originally may have been a Sumerian or Akkadian goddess. A composite of numerous goddesses, she is generally thought to have originally been the earlier Sumerian goddess Inanna. Ishtar is a mother goddess, fertility goddess, the goddess of spring, a storm goddess, a warrior and goddess of war, a goddess of the hunt, a goddess of love, goddess of marriage and childbirth, goddess of fate, and a goddess who is the divine personification of the planet Venus. She is also an underworld deity. Her predominate aspects are as the mother goddess of compassion and the goddess of sex and war. She is invoked for protection against sickness and evil in her role as mother goddess. The sexual aspect of her persona is linked to the earth's fertility. She has a reputation for having numerous lovers who were killed when she was finished with them. As the daughter of Sin and sister of Shamash, the warlike side of her character is dominant. In her role as warrior, Ishtar rode into battle and sent the vanquished into the underworld. It is said that she once tore out the teeth of a lion. It is in this form that she was worshiped by the Assyrians, particularly at Nineveh and Erbil. She is the sister of the queen of the Underworld, Ereshkigal. Ishtar was worshiped at Uruk as the goddess of gentleness, love and desire. In this aspect, she is known as the daughter of the sky god Anu and the goddess Anat. Though not as violent, she was still demanding and had a bad temper. Ishtar's consort, and some say brother, is Tammuz, but she was also said to be the wife of Ashur, and the consort of many kings. In one of her numerous adventures, as Irnini, she was living in the huge Cedar Forest of the Amanus which were guarded by the giant Khumbaba. She had planned to build a table and chair from the wood of a huluppa tree that she had planted in her garden. Prevented from proceeding with her project by negative forces, Gilgamesh came to her aid. In return, she presented him with a magic drum and drumstick made from the huluppa tree. Their relationship was not always smooth. Ishtar once took revenge on Gilgamesh by sending a bull after him, when he spurned her advances. Enkidu saved Gilgamesh, but was rewarded for his bravery by being struck down with a fatal illness by Ishtar. In another tale, Tammuz was mortally wounded by a wild boar. He was cast into the underworld. Furious, she made a journey to the dark and dreary place. Aggressively she demanded entry and threatened to smash the doors down if refused. She also threatened to let the dead loose to wander among the living. The guardian of the gate gained permission from the ruler Ereshkigal to allow Ishtar through the gates. At each of the seven gates it was demanded that she leave an article of clothing or jewelry. Finally, naked, she appeared before the queen. In the meantime, the Upperworld mourned her absence. The vizier of the gods, Papsukaal, was tearing out his hair, and Shamash was in deep mourning. Her absence from the Upperworld caused the passions of all men and beasts to cease. The only way to return to normalcy was to persuade Ishtar to return. This, they knew, would be a difficult endeavor, as she would not consent to return without Tammuz. The great god, Ea, finally decided to create Asushunamir, a charming eunuch, to send to the Underworld to rescue Ishtar. With the use of magic incantations, which Ereshkigal could not resist, Ishtar was led from the Underworld by Namtar. She was part of the triad with Sin and Shamash. Ishtar as the goddess of love was irrestible. Her lovers were legion. Once tired of them, they were cast aside. When she descended to earth, she had a retinue of courtesans with her. Sacred prostitution formed part of her cult. Ishtar is identified with the Sumerian goddess Inanna and with Astarte of the Phoenicians and Babylonians. She has been identified with Ninlil. Ishtar corresponds to the Chaldean goddess Nintu (q.v.). Ishtar parallels the ancient Sumerian goddess Anunit in numerous ways (q.v.). The Hebrew goddess Tamar is equivalent to Ishtar. The Hittite goddess Shaushka is known as the Hurrian Ishtar. As Hanata, she is also a warrior. The Babylonian goddess Gamlat eventually assimilated into Ishtar, as did the Babylonian Aya (q.v.). The war goddess Agasya eventually became Ishtar as the sky warrior. The vegetation goddess Gumshea merged with Ishtar. Her titles of Minu-anni and Minu-ullu may link her with the Assyrian god or goddess, Meni (*see* Menu). Compare Ishtar to Isis (Egyptian), and the Inca goddess, Mama Allpa. Ishtar is depicted sometimes naked, with her hands clasping her breasts. Often she is bedecked in jewelry and has an elaborate hairstyle. She is also shown reclining, wearing a crowned crescent set with a shining stone on her head. Sometimes she is shown holding her symbol, the eight pointed star. In her battle stance, she carries a bow and is depicted standing on a chariot drawn by seven lions. The lion, bull, and dragon are Ishtar's emblems. The lion is her sacred animal and perhaps the dove. *See also* Abtagigi; Allat; Allatu; Anat; Anta; Anu (B); Arinna; Ashur; Astarte; Asushunamir; Atargatis; Athar (A); Aya; Belti; Boann (Celtic); Chemosh; Ea; Enki; Enkidu; Ereshkigal; Gilgamesh; Igigi; Inanna; Innini; Khumbaba; Kilili; Namtar; Ninkarrak; Ninkasi; Ninlil; Papsukaal; Ramman; Saltu; Sammuramat; Semiramis; Shamash; Sharis; Sin; Tammuz; Tiamat; Venus; Zerpanitum.

Ishum (Babylon) *see* Nergal.

Isimud (Sumer) *see* Inanna.

Isir (Babylon) *see* Tammuz.

Isis (Egypt; also worshiped in Pompeii, approx. 360 B.C.).

Also known as: *Ament, Ankhat* (Goddess of Land), *Anquat, Anquet* (Giver of Life), *Aset, Aust, Eset* (Giver of Life; Egyptian), *Hest, Isis Pharia* (Greek), *Kekhet* (Goddess of Harvest), *Khut* (Light Giver), *Methyer, Renenet* (Goddess of Food), *Satis* (Fertility), *Selene* (Greek), *Tcheft, Thenenet* (Power), *Usert* (Goddess of Tuat).

Patroness of loving wives and mothers. Goddess of the earth,

www.ebook3000.com

protector of the dead. The Greeks called her Isis Pharia, the protector of seaman. She assimilated the functions of many other goddesses. Known as "the cunning one," Isis is the daughter of Geb and Nut, the sister-wife of Osiris and the sister of Seth and Nephthys. She is the mother of Horus. When Osiris was treacherously slain and dismembered by Seth, Isis and her sister Nephthys wandered the universe searching for the parts of his body to restore him to life. Isis wanted the same power that Ra held and she knew everything but his secret name. She tricked Ra by sending a serpent to poison him with its bite and made him reveal his name. By doing so her powers became greater. Isis, Osiris, and Horus formed the powerful Egyptian trinity. She was the principal goddess of ancient Egypt and identified with the moon by Plutarch although the ancient Egyptians regarded her as the "Eye of Ra." Isis is said to typify the female side of civilization in its struggle with barbarism as Osiris embodies the male aspect. The *Book of Breathings* was said to have been written by Isis for her dead husband (*see also* Shu). She is represented by having a solar disk between the horns of a cow. Horus and Isis were depicted as falcons when they were later worshiped in Gebtu. Isis is identified with Hathor. She was worshiped in Rome and Greece, and came to be identified with the goddess Demeter. She is also identified with Venus (Roman), Astarte (Phoenicia), Ishtar (Babylon), Diana of Crete, Proserpine of Sicilians, and Minerva of Athens. Compare Isis to Ishtar (Assyro-Babylonian), Marduk (Babylonian, who also used magic), and Freyja (Teutonic). *See also* Ab; Ament; Anquet; Anubis; Apis (A); Astarte; Atum; Geb; Hapy (A); Harsiesis; Heket; Horus; Io; Nephthys; Osiris; Qebhsneuf; Ra; Ranenet; Satis; Selene; Selket; Serapis; Serius; Set; Sothis; Usert; Wadjet.

Isis Pharia (Greek) *see* Isis.

Isis-Sothis (Egypt) *see* Sirius; Sothis.

Iskrychi (Poland) *see* Domovoi (Russia).

Iskrzychi (Slavic) *see* Domovoj.

Iskur (Babylon) *see* Ishkur.

Islamic Hell (Stages of)
Known as Daru el-Bawar, the Islamic Hell is divided into seven stages:
First: Jahannam (similar to purgatory).
Second: Laza (reserved for Christians).
Third: Hutameh (a fiery place reserved for Jewish people).
Fourth: Sa'ir (reserved for Sabians).
Fifth: Saqar (a fiery place reserved for the Magi).
Sixth: Jahim (a hot fire of idol-worshipers).
Seventh: Hawiyah (a bottomless pit reserved for hypocrites).

Islamic Paradise (Stages of)
Known as Dar el-Jannah, Paradise is divided into eight stages:
First: Jannatu el-Khuld, known as "The Garden of Eternity," and symbolized by green or yellow coral.
Second: Daru el-Qarar, "The Dwelling of Peace," symbolized by white pearls.
Third: Daru el-Salam, known as "The Dwelling which Abideth," symbolized by green chrysolite.
Fourth: Jannatu el-Adn, "The Gardens of Perpetual Abode," symbolized by large pearls.
Fifth: Jannatu el-Ma'wa, "The Gardens of Refuge."
Sixth: Jannatu el-Na'im, "The Gardens of Delight," symbolized by white silver.
Seventh: Illiyun, where the register of good deeds is kept.
Eighth: Jannatu el-Firdaus, "The Gardens of Paradise," symbolized by red gold.

Island of Flame (Egypt) *see* Ogdoad.

Island of the Blessed (Greek)
On the western edge of Oceanus is the Island of the Blessed, an after-death land of happiness for those favored by the gods. *See also* Harmonia (A).

Ismail (Islamic) *Ishmael* (Hebrew)
The son of Hajar and Ibrahim. *See also* Zam Zam.

Ismaroinen (Slavic) *see* Ilmarinen.

Ismenius (Greek)
He is the father of Linus, the music teacher who taught Heracles, Orpheus and Thamyris how to play the lyre. *See also* Linus.

Ismenos (Greek)
His parents are Amphion and Niobe. One of five sons and six daughters, they were all, except one, murdered. The males were killed by Apollo and the females (except Chloris) were killed by the goddess of the hunt, Artemis. *See also* Amphion; Amyclas; Artemis; Chloris; Niobe

Ismenus (Greek)
He is the son of the river god Asopus and Metope. For the names of his siblings, *see* Asopus.

Isodaites (Greek) Another name for Dionysus.

Isong (Ekoi, and Ibibio People, West Africa)
Also known as: *Eka Obasi, Obasi Nsi.*
Goddess of fertility. She is called "The Tortoise-Shell Goddess."

Issitoq (Eskimo)
Also known as: *The Giant Eye.*
High god. The god who seeks out those who break the rules.

Istar (Assyro-Babylonian) *see* Ishtar.

Istaru (Assyria) *see* Astarte.

Istepahpah (Creek People, North America)
A devouring monster.

Istio (Teutonic)
Patriarchal deity. He is the son of Manus and the grandson of Tuisko.

Iswara (India) "Supreme Lord." *See also* Shiva.

Italapas (Chinook People, North America)
Also known as: *Coyote.*
In a Creation Legend, after the Deluge, Italapas ridded the

earth of water, and enabled mortals to begin a new life. He is also credited for establishing laws. *See also* Coyote.

Itchita (Yukut People, Siberia)
Tree goddess and healing deity. This goddess lives in birch trees. Her tiny assistants are spirits of grass and trees. They keep the spirits of sickness away from mortals.

Ith (Celtic) *see* Eire.

Ithavall (Teutonic) *see* Idawold.

Ithun (Teutonic) *see* Idun.

Iti (Egypt)
Also known as: *Ity.*
God of music. Son of the Bull of Ra and the goddess Hathor. He is also called the "Bull of Confusion." He is shown as a man with the double crown of Upper and Lower Egypt and the side-lock of youth.

Itoki (Nicaragua)
Creator deity. Great mother. Itoki is said to be a mother scorpion who dwells at the end of the Milky Way. She is responsible for sending the new souls of those recently born to their human life and she receives the souls of the newly dead. Her spouse is the great father Maisahana the founder of the Tauchca, Yusco, Sumo, and Ula people. Itoki is probably shown with many paps. *See also* Ituana; Maisahana.

Itom Ae (Yaqui People, South America)
Also known as: *Our Mother.*
Supreme Goddess. Not much known since this is a recent discovery.

Itsu-no-wo-ha-bari (Japan) *see* Ame-no-wo-ha-bari.

Ituana (Nicaragua) *see* Itoki.

Itylus (Greek)
He is the son of Zethus, the co-ruler of Thebes and Aedon, the "Nightingale." *See also* Aedon; Zethus.

Itys (Greek)
His parents are Tereus and Procne, who became a swallow after she accidentally killed Itys. *See also* Aedon; Procne.

Itza Mixcoatl (Mexico) *see* Mixcoatl.

Itzam-Kab-Ain (Maya People, Yucatan) *see* Ahmucen-Cab.

Itzama (Maya) *see* Itzama.

Itzamna *Itzmatul, Izamna* (Maya People, Yucatan)
Also known as: *Chichen Izta, Hunab Ku, Izamal, Izona, Kabil, Kabul, Kinich-ahau, Kinish-kakimo, Ytzmatul, Zamna.*
"Lizard House." Sky god. God of healing. God of drawing and letters. A chief god, he is the son of Hunab-Ku. He was the creator and father of both gods and men. He brought writing, and the use of maize and rubber. Squirrels were sacrificed and gifts were given to him. Itzamna kept the fields fertile for the people. Itzamna had the ability to restore the dead to life. He was sometimes called Kabul or Kabil. In some legends, he appears as a priest named Zamna. According to some writers, Zamna, Izamal, and Itzmatul are modifications of the name Itzamna. He is shown with a red hand, to which the ill pray for healing. Itzamna is sometimes identified with Quetzalcoatl, sometimes with Tlaloc, and sometimes with Tonacatecutli. *See also* Cain; Kinich Ahau; Quetzalcoatl; Tlaloc.

Itzcoliuhqui *Itztlacoliuhqui* (Aztec People, Mexico)
God of darkness. He is responsible for earthquakes, volcanic eruptions, and disasters. Some say he is a god of cold and dryness. He is possibly an aspect of Quetzalcoatl. Itzcoliuhqui is sometimes identified with Texcatlipoca. *See also* Pillan.

Itzcueye (Honduras, Nicaragua, Central America)
Earth goddess. *See also* Ilancue.

Itzcuinan (Mexico) *see* Xochiquetzal.

Itzli (Aztec People, Mexico)
Itzli is a stone knife god, who is the Lord of the Second Hour of the Night. He is identified with Texcatlipoca (q.v.). *See also* Lord of the Night Hours.

Itzmatul (Aztec, Maya) *see* Itzamna.

Itzpapalotl (Aztec; Mexico)
Also known as: *Cihuatcoatl, Obsidian Butterfly, Tonantzin.*

Itztlacoliuhqui (Aztec) *see* Itzcoliuhqui; Quetzalcoatl; Tezcatlipoca.

Itztli (Aztec People, Mexico)
Also known as: *Texcatlipoca.*
Stone knife god. He rules the Second Hour of the Night. Itztli is usually depicted with Chalchiuhtlicue and Tlazolteotl (qq.v.). *See also* Texcatlipoca; Tonatiuh.

Iuchar (Celtic) *see* Cian; Dana.

Iucharba (Celtic) *see* Cian.

Iucharbar (Celtic) *see* Dana.

Iulus (Greek)
Also known as: *Ascanius, Ilus.*
Iulus is the son of Aeneas and Creusa (qq.v.).

Iuno (Etruscan) *see* Juno.

Iuppiter (Roman) *see* Jupiter.

Iusaas *Iusas* (Egypt)
Also known as: *Iusaaset, Nebt-Hetep.*
First deity. In later Egyptian mythology, she was believed to be the wife of Atum. Another wife of Atum was Nebhet Hotep. Iusaas sometimes appears as the sole parent of the first divine couple Shu and Tefnut. Other times, Iusaas and Nebhet Hotep are merely female aspects of Tem, who is bisexual in some accounts. Nebhet Hotep seems to have been a double of Iusaas, and is sometimes called "Mistress of the Gods." Iusaas is shown as a woman holding a scepter in her right hand and the ankh, in her left. She wears a vulture headdress surmounted by a uraeus, and a disk between a pair of horns. *See also* Atum.

Iusaaset (Egypt) *see* Iusaas; Shu.

www.ebook3000.com

Iustitia (Roman)
Another spelling for Justitia, the goddess of justice.

Iuturna (Roman)
Another spelling for Juturna, the goddess of springs.

Iuwen (Egypt) *see* Osiris.

Ivaldi (Norse; Teutonic)
Smith gods. They are two dwarfs called the sons of Ivaldi who made the three treasures for the gods. The golden hair for Sif, the ship Skidbladnir for Freyr, and the spear Gungnir for Odin.

Iving (Norse; Teutonic)
Deified river. The river that never freezes, it divides Asgard from Jotunheim. *See also* Asgard; Jotunheim.

Iwa (Polynesia, Hawaii) *see* Kupua.

Iwa-naga-hime *Iha-naga-himi* (Japan)
Fate deity. "The Lady of Rock-Perpetuity," and ugly sister of Ko-no-hana-sakuya-hime. When Ninigi chose the better looking of the two women, Iwa decreed that mankind would be short-lived like the flowers.

Iwasu-hime-no-kami (Japan) *see* Izanami.

Iweridd (British, Cymric, Irish)
She is the earth goddess wife of Llyr and mother of Bran and Branwen. Her name means "Ireland." *See also* Bran; Branwen; Llyr.

Ix (Maya)
In some myths, Ix is one of the four Becabs. He represents the west. His color is black. *See also* Becabs.

Ix-chel (Maya)
Also known as: *Chibilias.*
Goddess of childbirth. She is responsible for the fecundity of women. Ix-chel is also considered a guardian and a deity of medicine. Some say she is the wife of Izamna and mother of the Becabs.

Ix Tub Tun (Maya)
No function shown, but may be a rain deity. Her legend is that she spits out precious stones. She is shown as a snake.

Ixazalvoh *Ixzaluoh* (Maya People, Yucatan)
Ixazalvoh is the inventor and goddess of weaving, the goddess of healing, childbirth, prophecy, and sexuality. In some renditions, she is the spouse of the sun god Kinich Ahau. In other versions she is the spouse of Hunab-Ku (q.v.). *See also* Hunab-Ku; Ixchel; Kinich Ahau.

Ixbalanque (Maya)
Brother of Hunahpu (q.v.). *See also* Gukup Cakix.

Ixchel (Maya)
She is the goddess of healing, childbirth, prophecy, sexuality and weaving. *See also* Ixazalvoh.

Ixcocauhqui (Nahuatl People, Central America; Mexico)
God of fire and destructive lightning.

Ixcuin (Aztec) *see* Ixmacane.

Ixcuina (Maya) Goddess of pleasure. *See also* Ixmacane.

Ixcuiname (Mexico) *see* Ixmacane.

Ixion (Greek)
Also known as: *Iksion.*
Deified mortal. King of the Lapithae of Thessaly. Ixion is the son of Antion and Perimela (Perimele). There is a possibility that his father was not Antion but Phlegyas or Ares. He was the king of the Lapiths of Thessaly and he was married to Dia, the daughter of Eioneus. Some think that Zeus was the father of their child, Peirithous. He is also the father of Amycus and the Centaurs by Nephele. Ixion promised his father-in-law a valuable gift when he married Dia but he was unable to keep his word. Eioneus decided to take two of Ixion's horses until he could fulfill his promise. Furious, Ixion arranged to pay the debt but when Eioneus arrived he threw him into a pit of fire and killed him. This act stunned the populace and the deities for it was said to be the first time that a mortal had murdered a family member. After a long period of repentance, he was summoned by Zeus to Mount Olympus and placed at the table of the gods. But Ixion, unappreciative of his host's hospitality, tried to seduce Hera, the wife of Zeus. Zeus created a cloud named Nephele in the form of Hera; and Ixion, believing it was the goddess, was caught in the act of making love to her. Zeus punished him by chaining him to a fiery wheel which never ceased turning, either in the sky or in later mythology in the Underworld. In fairness to Ixion, Homer, in the *Iliad* said that Zeus was in love with Ixion's wife, Dia. Compare to the punishment of Sisyphus and Tantalus. *See also* Abas (C); Hades; Nephele; Peirithous.

Ixmacane *Ixcuin, Ixcuina, Ixcuiname, Ixmucane, Xmucane* (Maya)
Also known as: *Bitol, Teteoinnan, Tlazolteotl.*
Creator. One of the original four regents who tried to create mankind. He was changed into two gods by the fabricating gods Ajtzak and Ajbit. Before the change, his name was Bitol. This was also the time when the only female joined the group. She had the double name of Chirakan-Ixmucane, which links her with the creation deities. In another version, she is spoken of as Ixcuiname (four faces or four sisters) who represents the four ages of women. One of these sisters is Ixcuina, who is a goddess of pleasure. *See also* Bitol; Hueytonantzin; Ixpiyacoc; Teteoinnan; Tlazolteotl.

Ixmucane (Mexico) *see* Ixmacane.

Ixpiyacoc *Xpiyacoc* (Maya)
Also known as: *Tzakol.*
Creator. At the third attempt at creating mankind, Tzakol (one of the four original regents) was split into two gods, one of which was Ixpiyacoc. He and Tzakol were joined by the fabricating gods, Ajtzak and Akbit. In another version, Tzakol, Bitol, Alom and Qaholom (Cajolom) changed their names to Ixpiyacoc, Ixmucane, Hunahpuguch and Hunahpuutiu, then joined Ajtzak and Ajbit and one female deity named Chirakan-Ixmucane. *See also* Cipactonal; Ixmacane; Oxomoco.

Ixtab (Maya People, Yucatan)
Goddess of death. She is known as a goddess of those who hang themselves. Ixtab is shown as a limp body with a loop around the neck. She is related to Ahpuch, Yum Cimil and Hanhau, who are all deities of death. *See also* Mitlan.

Ixtaccihuatl (Aztec People, Mexico)
Also known as: *White Woman.*
Ixtaccihuatl is a sacred volcano in central Mexico. She is worshipped for earth, water, rain, and vegetation. *See also* Tlaloc.

Ixtacihuatl (Aztec) *see* Ixtaccihuatl.

Ixtacmixcoatl (Aztec People, Mexico) *see* Mixcoatl.

Ixtlilton (Aztec People, Mexico)
"Little Black One."
He is one of a group with Xochipilli and Macuilxochitl. They might be brothers. Ixtlilton, a god of healing, health and medicine, is associated with the Centzon Totochtin (q.v.). In some renditions, he is a god of maize or dancing. Ixlilton is associated with Centzontotochtin. *See also* Texcatlipoca.

Ixtliltou (Aztec) *see* Texcatlipoca.

Ixzaluoh (Maya) *see* Ixazalvoh.

Iyatiku (Crow, Pueblo People, North America)
Mother goddess. Corn goddess. She was instrumental in bringing mortals to the surface from the bowels of the earth. She made a ladder from a fir tree and after a woodpecker bored a hole in the rock above, mortals were able to climb into the next world. There were four worlds: white, red, blue, and yellow. Iyatiku helped the mortals from the red world to the blue world.

Izamal (Maya) *see* Itzamna.

Izamna (Aztec) *see* Itzamna.

Izanagi and Izanami *Izana-gi and Izana-mi* (Shinto; Japan)
Izanagi (Male Who Invites) and Izanami (Female Who Invites) were created by the celestial deities to create earthly manifestations. Izanagi and Izanami are the last of the seventh generation of the first deities born from chaos. Their first creation was the deity Hirugo, whom they set adrift to fend for himself. They created the eight Japanese islands (other islands came into being later) and the deities to inhabit the lands. (*See also* Izanami.) The last god, Kagu-tsuchi, the god of fire, burned the goddess and caused Izanani great pain and distress. From her bodily expulsions, the goddess Moaning-River was created and Izanami died. According to the *Kojiki*, her inconsolable husband Izanagi, beheaded the child with Ame-no-wo-ha-bari (Heavenly Point Blade Extended), his sacred sword. Blood from his sword fell to the ground and created eight more gods and from the body issued eight deities representing the mountains. In the *Nihongi*, Izanagi cut the serpent into three pieces, and each became a god. The drops of blood from his sword created the gods Kura-okami (Dragon god of the valleys), Kura-yamatsumi (Lord of the dark mountains), Kura-mitsu-ha (Darkwater-snake or Valley-water-snake) and Taka-okami (Dragon-god residing on the mountains). In the *Kojiki*, these deities issued from the blood between Izanagi's fingers. Izanagi then descended into Yomi (hell) to beg Izanami to return with him. Reluctantly, because she had tasted the food of Yomi, she approached the god of Yomi with her husband's request. Izanagi ignored her plea not to follow her into the castle and there he found Izanami rotting and full of worms, guarded over by the soldiers of Yomi and eight Thunder gods. He threw three peaches at the soldiers and managed to block the entrance to Yomi with a huge rock. Izanami, angry that he hadn't listened to her, chased after him and found herself barricaded by the rock in Yomi. She was so angry she caused one thousand people to die every day. In retaliation, he gave birth to fifteen hundred people to thwart her. After all they had been through, Izanagi and Izanami decided to part ways. After escaping the darkness of Yomi, Izanagi went to the sea to cleanse himself. This process created the terrestrial deities: a daughter Amaterasu (Heaven Illumining Goddess), the Ruler of the Realm of Light on Heaven and Earth; and two sons: Tsuki-yomi (also spelled Tsukiyomi-no-Mikoto), the Moon Ruler and Ruler of the Night, and Takehaya Susanowo, the Valiant Swift Impetuous Hero, who is the Ruler of the Ocean and Mysterious Things. For the Shinto creation myth, *see* Ama-no-minaka-nushi. For their creations between Hirugo and Amaterasu, *see* Kami and Haya-akitsu-hime-no-kami. The legend of Izanagi is similar to Pan-Ku of the Chinese. Compare to Orpheus (Greek). For additional information about thunder gods, *see also* Take-mekazuchi. Izanagi created the first wind gods Shina-tsu-hiko, and O-Wata-Tsu-Mi. The peach, an attribute of Izanagi, symbolizes immortality and is used to ward off evil spirits and the plague. For more about the peach tree, *see* Yomi. *See also* Ame-no-wo-ha-bari; Hiruko; Izanami; Kaya-no-hime-no-kami; Kushi-nada-hime; Susanowa; Tsuki-Yomi; Yomi.

Izanami (Japan)
Also known as: *Izanami-no-kami.*
Creator. Izanami and Izanagi were given the function of creating the terrestrial deities. They were given a spear known as the "Celestial Jewel-spear." As they stood on Ama-no-ukihashi, the "floating bridge of heaven" (also known as "Heavenly Stairs" or "Heavenly Rock Boat"), they fished around until they found the sea. They stirred the thick primeval waters, drew up the spear, and from its tip the island of Onogoro was formed. The original deities who sprang from chaos built a home for the couple with a central pillar. Izanami and Izanagi became man and wife by circling the pillar three times and meeting one another face to face. The first deity they created was the "leech child" Hirugo. Next they created the eight islands of Japan, known as their children. Others islands came into existence later. Once the islands had been created Izanami and Izanagi gave birth to the inhabitants which were the physical features of the terrain and the natural phenomena such as earth, sea, winds, trees, mountains, valleys, plains, seasons and fire. Thirty deities representing these elements are said to have been born. This included the goddess Iwasu-hime-no-kami (possibly the sand); a goddess, Haya-akitsu-hime-no-kami (Ruler of the Seas); Kaya-no-hime-no-kami (Ruler of the Plains and Goddess of Fields and Meadows); Ogetsu-hime-no-kami (Great Food Princess Deity, who is also known as Ogetsu-hime and

www.ebook3000.com

Oho-ge-tsu-himi). They also gave birth to the sea gods, likely snakes or dragons, known as Wata-tsumi (sea children) and the Miszuchi (water fathers), which are described variously as four-legged dragons, horned deities and large water snakes. These deities were not individually named but were appealed to when rain was needed during arid periods. The birth of her son the fire god, Kagu-tsuchi, seared and scorched Izanami. As she lay dying, additional deities were born from the expulsions of her body. These included Kanayama-hime (Metal-Mountain Princess Deity) and her brother; Haniyasu-bime-no-kami, the earth goddess and goddess of clay and her brother; Izunome-no-kami (Hallowed-Woman Deity) and her brother; Mitsuha-nome (also known as Mitsu-ha no-me), a water goddess variously described as a water snake or a producer of water, and her brother. Kuramitsuha-no-kami (Valley-Water-Greens Deity) is sometimes included in this group; however, according to the *Nihongi* this deity is said to have come from the body of their son, the fire god Kagu-tsuchi. Nakisawame-no-kami (Weeping-Marsh Woman Deity), described as a goddess dwelling at the base of the trees in the foothills of Mount Kagu, was formed from the tears of Izanagi who wept for his dead wife. Also listed is Ihatsutsu-nome, the wife of Iha-tsutsu no wo and mother of the god Tutsu-nushi no Kami, although according to the *Nihongi*, she may be of the following generation. They have been depicted hovering over the "ocean of chaos" just before the creation of the island of Onogoro. Izanami is shown as a woman with long hair. In the translation of the *Nihongi* by Aston, she is shown with long hair, wearing an ornate robe and is facing Izanagi. Between them are two wagtails. The spear may be a phallic symbol. The pillar, a common symbol in many civilizations, is an object of honor in Japan. It is found in Shinto shrines and is known as Nakago no mibashira (Central August Pillar). The bridge, Ama-no-uki-hashi, is the connection between heaven and earth. In myth, the bridge collapsed into the sea one day as the gods were napping. From that time, it became necessary for the deities to have messengers travel back and forth. This bridge is also known as Ame-no-uki-hashi, Ama-no-hashadate, Ame-no-iha-fune, and Ukibashi. The bridge is symbolic of a transition from one state to another. Sometimes messengers are indicative of the union of heaven and earth. For additional details *see* Ama-no-minaka-nushi. *See also* Izanagi and Izanami for details of their relationship. *See also* Amaterasu; Ame-no-wo-ha-bari; Haya-akitsu-hime-no-kami; Kagu-Tsuchi; Kami; Kanayama-hime; Susanowo.

Izha (Indo-Iranian) Goddess of the sacrifice.

Izona (Maya) *see* Itzamna.

Iztac Ciuatl (Aztec) *see* Ixtaccihuatl.

Iztaccihuatl (Aztec) *see* Mixcoatl.

Iztacmixcoatl (Aztec) *see* Mixcoatl.

Izunome-no-kami (Japan) *see* Izanami.

J

Jaahannam (Arabic) The underworld. *See also* Gehenna.

Jabal (Sumer)
Patron of tents and flocks. *See also* Ea; Enki; Lumha.

Jacy (Tupi-Guarani People, Brazil)
Jacy is the moon, and the creator of plant life. *See also* Hermitten.

Jadapati (India) *see* Varuna.

Jade Emperor (China) *see* Yu Huang.

Jade Lady (China) *see* Yu Nu.

Jafnhar (Teutonic)
"Even as High," an alternate name for Odin.

Jagadgauri (India) Another name for Parvati (q.v.).

Jagadnatha (India) Another spelling for Jagannath (q.v.).

Jaganat (India) *see* Jagannath.

Jaganmatri (India)
"Mother of the World." *See also* Devi; Durga; Lakshmi.

Jagannath *Jagadnatha, Jaganat, Jagannath, Jaggurnath, Jayanat, Juggernaut*
Also known as: *Buddha, Krishna, Vishnu* (Hindu; India).

Jagannath, meaning "Lord of the World," is a title for Krishna, and a form of Krishna, who is worshiped for protection and removal of sins. One day, Krishna, in the form of an animal, was slain by a hunter. A pious king, Indradyumna, also known as Indrahumna, came upon his bones. Krishna instructed the king to have an image made of him and to place the bones inside. The great artisan Visvakarma agreed to create the idol, providing that the king would not look at it until it was finished. The impatient king kept pestering Visvakarma. Finally, after fifteen days he became so annoyed that he stopped his creation, leaving it without hands or feet. Some scholars believe that Jagannath was Buddha. During the festival of Snana-yantra, held in the month of Jyaishtha, the statue is bathed in milk.

During the following festival of Ratha-yatra, in the month of Ashadha (June-July), he is placed in his great car, accompanied by his brother Bala-Rama and his sister Jagannatha (also called Subhadra) and carried to his temple as part of a great procession. This ritual symbolizes regeneration. It is often said that worshipers dragging the car threw themselves under the wheels as an act of sacrifice. This is doubtful as the spilling of blood was considered a defilement. It is likely that the crushing crowds accidentally pushed believers under the car wheels. As Indradyumna retrieved the image before the hands and feet were completed, the statue is shown this way. The most primitive tribe in India, the Saora people, worship Jagannath as well as one hundred and twenty-six other deities. *See also* Bala-Rama; Buddha; Krishna; Subhadra; Vishnu; Visvakarma.

Jagannatha *Subhadra* (India) *see* Jagannath; Subhadra.

Jaggurnath (India) *see* Jagannath.

Jaguar God (Mexico; Aztec) *see* Tepeyollotl.

Jah (A) *Jeh* (Persia) *see* Jahi.

Jah (B) (Hebrew) *see* Jehovah.

Jahannam (Islam)
The first stage in Daru el-Bawar, the Islamic Hell (q.v.).

Jahi (Persia)
Also known as: *Jah* (Pahlavi dialect), *Jeh* (Pahlavi dialect).

She is the personification of female impurity in the *Avesta*. To defeat the evil that she has introduced into the world, the virgin Eredatfedhri is invoked. An evil harlot-demon, she aroused Angra Mainyu from his sleep and caused him to pour poison on the body of the first man, Gaya Maretan, which created world conflict. In the *Bundahishn* Jahi is the personification of sin. *See also* Ahura Mazda; Angra Mainyu; Drujs (female demons of deceit); Gaya Maretan.

Jahim (Islam)
The sixth stage in Daru el-Bawar, the Islamic Hell. It is reserved for idol-worshipers. *See also* Islamic Hell.

Jahve (Hebrew) *see* Jehovah.

Jahweh (Hebrew) *see* Jehovah.

Jaja (India) *see* Naga and Nagis.

Jakis (Japan) Malignant air spirits who cause illness.

Jala-Hastin (India) An aquatic spirit; a water-elephant.

Jala-Shayin (India) *see* Vishnu.

Jala-Turaga (India) An aquatic spirit; a water-horse.

Jaladhi-Ja (India) "Born in the Ocean." *See also* Lakshmi.

Jalandhara (India) *see* Asuras; Bali (B).

Jaldabaoth (Hebrew) *see* Jehovah.

Jalebha (India) An aquatic spirit, a water-elephant.

Jalpati (India) "Lord of the Waters." *See also* Varuna.

Jalu-Ketu (India) *see* Bhishma.

Jam (Persia) *see* Yima.

Jam-dbyans-mag-gi-rgyal-po (Tibet) *see* Manjusri.

Jam-pa-i-dbyans (Tibet) *see* Arpacanamanjusri.

Jam-pe-yang (Tibet) *see* Arpacanamanjusri.

Jam-pol (Tibet) *see* Manjusri.

Jam-yang-nge-gi-gya-po (Tibet) *see* Manjusri.

Jamadagni (India) *see* Parashur Rama; Rishi.

Jambavan *Jambavat* (Hindu; India)
Like Hanuman the monkey, Jambavan, king of the bears, was created by Vishnu to assist Rama, an avatar of Vishnu, in his fight against the evil demon Ravana. In return for his wise advise he was given the boon of being invulnerable to all except his father Vishnu. In the end, it was his father, in his avatar as Krishna, who killed him. For details about Jambavan's death, *see* Syamantaka the magic jewel. *See also* Hanuman; Krishna; Rama.

Jambavati (India)
Daughter of King of the Bears. *See also* Jambavan; Krishna; Syamantaka.

Jambha (Hindu; India) A demon killed by Vishnu.

Jambhala *Dsam-Bha-La* (Tibet), *Kuvera* (Sivaites) (Buddhist, Sivaites; India)
Jambhala, the god of wealth, walks on a person who vomits up jewels. He is an aspect of the protector of wealth, Kuvera. Jambhala is depicted as a golden corpulent young figure seated in Indian fashion. He holds a lemon (jambhara) and a mongoose (nakula). Another depiction of Jambhala shows him holding a trident and scepter, seated sideways on a horse dragon. Indonesian depictions often include him flanked by lions. The lemon's seeds are the seeds of the world. Compare Jambhala to god of the purse, Panchika. His Hindu counterpart is Kuvera. *See also* the goddess of wealth, Kurukulla.

Jambi (Africa) *see* Bumba.

Jambudvipa (Buddhist, Hindu; India)
Translated as Rose-appletree Island, Jambudvipa is the ancient mystical name for the continent of India. *See also* Meru Mountain.

Jamshid (Iranian)
The first Iranian mortal, Jamshid is the son of Vivanghvant, twin of a sister, Yimeh (also known as Yima), who was also his spouse, and brother of Spityura and Takma Urupa. *See also* Vivanghvant; Yima.

Jamuna River (India) Sacred River. *See also* Karna; Yami.

Jan *Jann* (Middle Eastern) *see* Jin.

Jana (Etruscan, Roman) Queen of Secrets. *See also* Janus.

Jana-Loka (India) *see* Loka.

Janaka (India) *see* Sita.

Janardana (India) *see* Vishnu.

www.ebook3000.com

Janguli (Buddhist; India)
An ancient serpent goddess who prevents and cures snakebites. She is depicted playing a musical instrument or playing with a snake. She wears a snake necklace and ear adornments depicting coiled cobras. Her colors are white and gold. *See also* Tara (B).

Jann (Islamic) *see* Jinn.

Jannatu el-Adn (Islamic)
Meaning the "Gardens of Perpetual Abode," and symbolized by large pearls, this is the fourth stage in Islamic Paradise (q.v.).

Jannatu el-Firdaus (Islamic)
Meaning "The Gardens of Paradise" and symbolized by red gold, this is the eighth stage in Islamic Paradise.

Jannatu el-Khuld (Islamic)
Meaning "Garden of Eternity" and symbolized by green or yellow, this is the first stage in Islamic Paradise (q.v.).

Jannatu el-Ma'wa (Islamic)
Meaning "The Gardens of Refuge," this is the fifth stage in Islamic Paradise (q.v.).

Jannatu el-Na'im (Islamic)
Meaning "The Gardens of Delight," and symbolized by white silver, this is the sixth stage in Islamic Paradise (q.v.).

Janus (Etruscan, Roman)
Also known as: *Bifrons, Deus Clavigerus, Dianus, Gaelestis, Ianus, Janus Pater.*
High god. God of beginning and end. God of gates. He is an ancient Roman divinity. The Etruscans called him the father of the twelve gods, whose twelve altars belonged to twelve months. His consort was Jana (queen of secrets). He was loved by the virgin hunter and goddess of thresholds and door-pivots, Cardea. Some of his attributes were later transferred by the Christians to Peter. He was the god of beginnings and entrances; therefore, the first month of the year was named after him, and gates and doorways were under his protection. His temple at Rome was open in time of war and closed in time of peace. It was closed three times in Rome's first 700 years. Janus is represented with two faces turned in opposite directions. Sometimes with three or four heads, or one old face and one young. *See also* Cardea.

Jao (Hebrew) *see* Jehovah.

Japan — Creation Legend *see* Ama-no-mimaka-rushi; Izanagi and Izanami

Japara (Aborigine People, Australia) *see* Purukupali.

Japhet *Japheth* (Armenian)
God of the north. He is one of the triad consisting of Zervan, Titan, and Japhet. They are called "Princes of the Land." Japhet may either be Saturn's brother Iapetus, or Shem of the Book of Genesis. In Hebrew tradition he was the eldest of Noah's three sons, born 100 years before the flood. Some say he is identical with Iapetus (Greek). *See also* Zurvan.

Jappan (Aztec) Another spelling for Yappan (q.v.).

Jar-Sub (Turkey)
Home of gods. Jar-Sub is the general term for universe, ruled over by seventeen lords of land and sea. The term can mean any place inhabited by master-spirits.

Jara (India) Flesh-eating female demon. *See also* Jara-Sandha.

Jara-Sandha *Jarasandha* (Hindu; India)
Jara-Sandha is the son of King Brihadratha ("Big Carriage") and his two wives. Each wife had given birth to half-babies on the same day and threw them into the forest. A flesh-eating demoness, Jara, put the remains together (likely for a meal) and Jara-Sandha was formed. His wails alerted his father who ran to his rescue. When Jara-Sandha became king of Magadha, he was forced from the throne by demon Kansa. He was also forced to give Kansa two of his daughters for wives. Jara-Sandha was present with his demon army the day Rukmini and Krishna's cousin Sisupala were almost married. Jara-Sandha and his cohort, the demon Kalayavana, became Krishna's nemesis after the death of Kansa. During one episode in Krishna's life, Jara-Sandha imprisoned twenty thousand rajas. Krishna, and his cousins Bhima and Arjuna, both Pandavas, set out to rescue them. Jara-Sandha, who was renowned for his remarkable strength, was eventually killed in the resulting combat by Bhima, who, on the advice of Krishna, split him in half in a battle that lasted twenty-seven days. *See also* Arjuna; Bhima; Kansa; Krishna; Pandavas; Sisupala.

Jarah (Ugarit) *see* Eterah.

Jaralez (Armenian) *see* Arlez.

Jaras (India) *see* Krishna.

Jarasandha (India) *see* Jarha-Sandha.

Jari (Teutonic) *see* Dwarfs.

Jarl (Teutonic) *see* Heimdall.

Jarnsaxa (Teutonic) *see* Iarnsaxa.

Jarovit (Slavic) *see* Herovit.

Jashar (Middle East) *see* Adad (A).

Jason (Greek)
Also known as: *Diomedes.*
Leader of the Argonaut Expedition. Member of the Calydonia Boar Hunt. Jason (original name Diomedes) is the grandson of Aeolus, the son of Aeson (the Aeolian king of Iolcos), and Alcimede and the brother of Promachus. He is the father of Mermerus, Pheres, Alcimenes, Argus, Eriopis, Medeius, Thessalus, and Tisandrus, possibly by Medea. He is also the father of Euneus, Thoas and either Deipylus or Nebrophonus by Hypsipyle, queen of Lemnos. When Jason's uncle, Pelias, usurped the throne, his mother smuggled Jason, the rightful heir, to safety. She entrusted him to the care of Cheiron, the centaur, who changed Diomedes' name to Jason and reared him in a cave on Mount Pelion. When Jason turned twenty-one he made his way back to Iolcos to regain his father's kingdom. En route he stopped to help an old woman cross a stream and he lost a sandal. He never knew that the crone was Hera in disguise but she never forgot his kindness and remained his lifelong ally. Previously, an oracle was revealed to Pelias warning him to beware of a man wearing one sandle. When Jason arrived wearing one sandal, Pelias decided to send him on a seemingly

impossible venture to search for the Golden Fleece. The handsome young adventurer gathered together a renowned group of male and female heroes to assist him, including Peleus, the twins Castor and Polydeuces, and Atalanta, goddess of the hunt. Argos built the ship called the Argo and Orpheus joined them to sing and keep up their spirits. At one point, Heracles joined them for a short time to aid them in overcoming the numerous obstacles they encountered on their voyage. For details of these adventures *see* the Argonauts. When they finally reached Colchis, Jason met his preordained love, Medea, who assisted him with her magical powers in the next phase of his quest. *See* Medea for this portion of his life. In the end, Jason died alone and lonely. As he sat under the prow of the rotting Argo, it fell and killed him. Some myths say that he died by his own hand. There is also the possibility that he killed Aeetes, the father of Medea. *See also* Admetus; Aeetes; Apis; Apsyrtus; Argonauts; Argus (C); Calydonia Boar Hunt; Golden Fleece; Medea; Pheres (A); Phrixus; Sirens.

Jassuju (India) *see* Shuznaghu; Zumiang-nui.

Jatavedas (India) *see* Agni.

Jatayu (India)
He is the king of the eagles and son of Garuda (q.v.).

Javerzaharses (Armenian)
Nymphs. They are possibly female Kaches who were thought of as spirits of weddings, singing and rejoicing. They are also spirits of welfare, marriage and childbirth. The Javerzaharses are sometimes found on the river banks, prairies, and near the pines. *See also* Kaches; Torch.

Jayadratha (India) *see* Bhima (A).

Jayanat (India) *see* Jagannath.

Jeggua (Yoruba People, Africa)
Jeggua is the goddess of purity and virginity. *See also* Olodumare.

Jeh (Persia) *see* Jah.

Jehova (Hebrew) *see* Jehovah.

Jehovah *Jehova* (Hebrew)
Also known as: *Ahiah, Hehuah, Iah, Iao, Iaw, Ie, Ieu, Ieui, Jah, Jahve, Jahweh, Jaldabaoth, Jao, Jhvh, Jhwh, Jod-heh-vav-heh', Yahowah, Yahu, Yahveh, Yahweh, Yaw, Yehoveh, Yhwh.*
Supreme god. Originally a god of wrath. Generally pronounced Adonai or Elohim by the early Jewish people since the true name of the supreme being was never uttered. A creator deity, he made the earth, and all it contains in six days and established the seventh day as the sabbath. He created the first male and female, Adam and Eve. He appeared to only Abraham, Isaac, Jacob, and Moses in early versions of scripture. It is possible that Jehovah began as a deity of the vine. His symbols are a seven-branched candlestick or a hand emerging from a cloud. His only opponent was the serpent. When Jehovah appeared as a mortal on earth, he was known as Jesus. *See also* Jesus; Yahveh.

Jemdekhen (India) *see* Parashur Rama.

Jemshid (Persia) *see* Yima.

Jen (Finland) *see* Ilmarinen.

Jerah (Ugarit) *see* Elohim; Eterah.

Jeshodha (India) *see* Yasoda.

Jeshu (Hebrew) *see* Jesus.

Jesu (Hebrew) *see* Jesus.

Jesus (Hebrew)
Also known as: *Christ, Cristos, Iesous* (a corruption of the Hebrew Yehoshu'a, a common Jewish name; Greek), *Iesu, Isa, Jeshu, Jesu, Khrestos* (Greek), *Logos, Yesha.*
The Messiah. "Anointed One." Deified mortal. Very few historical records remain about his existence in the period associated with him, but one of the military aides of Moses was named Jehoshua, which was shortened to Jeshua. The Greeks replaced the "sh" sound with "s" which gave the name "Jesus." This name is mentioned several times in the original Greek New Testament, but various versions say he was the eldest of five sons of Joseph and Mary and in the biblical version he was divinely born of Mary, wife of Joseph, a carpenter. Early Coptic text (Pistis Sophia) tells of Jesus praying to his father by addressing him by various magical names: Aeeiouo, Iao, Aoi, and others. In another passage, Jesus addresses his god in the following names and words: Iao Iouo, Aoi, Oia, and others. It is believed by followers that Jesus is the supreme being in earthly form. *See also* Christ; Jehovah; Logos.

Jhoting (India)
This is the spirit of a dead lower caste Hindu who died dissatisfied. Jhoting is also the ghost of a dead man who never married and did not have relatives.

JHVH (*Jod-heh-vav-heh*) (Hebrew) *see* Jehovah; Yahweh.

JHWH (Hebrew) *see* Jehovah; Yahweh.

Jibb-Jang-Sangne (Dhammai People, India)
Jibb-Jange-Sangne and her brother, Sujang-Gnoi-Rise, are the mountain children of the sky god, Jongsuli-Young-Jongbu, and the earth goddess, Subbu-Khai-Thung. Their siblings, who were born as frogs, are Lujjuphu and Jassuju. *See also* Shuznaghu.

Jibril (Islamic) *see* Gabriel.

Jiburili (Arabic) *see* Gabriel.

Jicarilla Apache People — Creation Legend (North America) *see* Hactein.

Jig-ten-sum-gyal (Tibet) *see* Trailokyavijaya.

Jigoku (Buddhist; Japan).
Hell or Underworld. Jigoku is composed of eight hot sections known as To-Kwatsu and eight freezing sections known as Abuda. There are also sixteen sub hells, and four hells called Kimpen Jigoku. In Hell, an immense mirror reflects and exposes the crimes of the naked soul as it kneels before the table of three judges. The three judges are Kagu-hana, a decapitated head (nose); Emma-O, who sits in the middle; and Miru-me, also a decapitated head (eyes). When the sins have been weighed, the sinner is condemned to the appropriate hell. This fate can be avoided by the prayers of the living. Next, a Bodhisattva delivers the soul from the evils of hell and the transgressor is reborn in Paradise or on earth. There is a hell called Kodoku-jigoku which appears more like a spirit than a proper hell. Born a

www.ebook3000.com

drugs, tobacco and promiscuity all quicken the depletion of this fuel. The Taoist exercises strive to continually refuel the energy within. The Taoist recognizes that we are limited in our nature as human beings, unless we connect the sources of energy within the universe, thereby becoming infinite. So, within the limitations of our human nature, we constantly fill ourselves with the unlimited abundance of energy around us.

Through their internal quest, the Taoists discovered a doorway to the universe. The more we open our internal energy, the more we are capable of connecting to the forces of energy around us.

Human beings have amazing potential and capabilities. We are unique creatures in the way we use our minds and hands. Look at the world around you, the skyscrapers, the architecture, computers, technology and the myriad creations of man. All have come about through the combination of the mind with the hands. In the Tao practice, we use the mind and the hands, in both Chi Kung and meditation, to connect to the forces of the universe. We use the mind to project a pattern of energy into the universe, to connect to the force, and to bring this energy back into the body.

The mind can travel millions of light years in a few moments. Taoists discovered the unlimited potential of the human mind. If you picture something in your mind; an ocean, a sunset or a mountain, you automatically connect with that image. The mind can take you anywhere you imagine. With the proper training you can connect to the energy of nature and the universe and project your Chi to combine with it, drawing these forces into the body. The hands are called the touching force, and like antennae they can transmit the frequencies and vibrations from space. With the mind and the hands, each of us can journey into the boundless energy of the universe.

Relaxation, Letting Go, Surrender and Ego

In some religions and spiritual paths, there is a great emphasis on surrender and letting go. This is actually a form of relaxation. Taoist practices emphasize relaxation, letting go, and emptiness. When a person is relaxed, the muscles are open, the breathing is soft, and the energy can flow through the channels of the body. There is no resistance and no fighting. This allows the creative and higher forces to flow into us.

Most religions have a similar process. To contact the higher self and the higher forces, one needs to let go and surrender in order to reach the level where one can be in contact and become one with the higher forces. Through the surrender of control, one opens up and touches the forces of nature. However, if you continue to surrender and let go, you will lose the energy you have sent out. In the long term, this will gradually drain you. The force will suck the energy out of you, rather than help you to bring the energy into yourself. To avoid this, at the moment that one is in touch with the higher forces, one again becomes aware of oneself and his or her own energy. One is then able to project his or her own thoughts, intentions and patterns into the force, integrating the outer with the doubling or tripling inner energies. You can bring this force back to your place, your house and into yourself.

prince who became a beggar monk, Kuya, through his writings and paintings, and Genshin, also known as Eshin Sozu, were well known for their dissertations on the ghastliness of hell. Depictions of the horrors of hell, pits of flame and ice, were common on screens toward the end of the Heian culture (late eighth and early ninth centuries). Compare Jioku to Hades (Greek), Tartarus (Greek), Tuat (Egypt), Yomi (Japan). For a complete description of the chief judge, *see* Emma-O; Oni. *See also* Gokuraku Jodo; Hell.

Jigs-Byed (Tibet) *see* Bhairava.

Jikoku (Japan) *see* Jikoku-Ten.

Jikoku-Ten *Jikoku, Jikokuten* (Buddhist; Japan)

"Land-bearer." Jikoku-Ten is one of the four Shi Tenno. Known as the four kings, these deities protect the four corners. Jikoku-Ten functions as the guardian of the east and protects his section from evil demons. Should a demon attempt to cross his path, he will be trampled. The four guards all wear uniforms and have ferocious facial expressions. Jikoku-Ten is depicted with a small container and holds a sword in his left hand. *See also* Bishamon-ten; Dhartarastra; Komoku-ten; Nio; Shi Tenno; Zocho-ten.

Jikokuten (Japan) *see* Jikoku-Ten.

Jimmu Tenno *Jimmu Tennu* (Shinto; Japan)

Also known as: *Kamu-yamato-ihare-biko, Kama-yamato-iware-biko, Toyo-mike-nu, Waka-mi-ke-nu-no-mikoto.*

First Emperor. Warrior. Conquerer. First Japanese demigod who was a human hero. Jimmu Tenno, the first emperor and founder of the Imperial Line of Japan, was born Kama-Yamato-Iware-Biko (also called Waka-mi-ke-nu-no-mikoto). He acquired the name Jimmu Tenno posthumously. He is the son of the sea princess Tama-Yori-Bime (Spirit-Medium-Princess, also known as Jewel-Good Princess) and her nephew Ama-tu-Piko-nagisa-take-U-gaya-puki-apezu-no-mikoto. Her nephew is the son of her sister Toyo-Tama-Bime (Lady Abundance Jewel) and Hikohohodemi (Prince-Fire-Subside). He was the youngest of four sons. In legend, Jimmu Tenno ascended the throne in the year 660 B.C.E. His seat of power was Yamoto in Honshu. He was said to have lived one hundred and twenty-seven or one hundred and thirty-seven years. In one myth, Jimmu and his brothers were attempting to bring peace to the land. They were guided by a three-legged, golden crow, which was eight feet long. It had been sent to them from the celestial realm. Jimmu had a sacred cross-sword and a fire-striker. To quell the raging storm his brothers jumped overboard. Tenno, the official title of the Emperor, has been kept to the present. It is thought to have been a word first used by Prince Shotoku when communicating with China. The name Jimmu means "son-of-heaven." Mythology and history entwined called the mythical Jimmu Tenno (Sun of Heaven) a great-grandson of the sun goddess Amaterasu. All following emperors dated from him and thus were called divine. In 1946, the emperor Hirohito renounced his divinity. The crow with three legs drawn within a solar disk is an early Chinese imperial emblem that represented the active life of the Emperor, his Yang. The three legs within the disk represent the main phases of the sun throughout the day: dawn, noon and dusk. The crow as messenger is also a common symbol. The sun goddess Amaterasu has a crow as her messenger. It is also said that the crow symbolizes the isolation of the individual who lives on a higher plane. *See* Ama-no-minaka-nushi for the Shinto creation myth. *See* Amaterasu for details of divine emperors. *See also* Hikohohodemi; Ninigi; Toyo-Tama-bime.

Jimmu Tennu (Japan) *see* Jimmu Tenno.

Jina (India) *see* Buddha; Mahavira.

Jinimin (Aborigine People, Australia)

Also known as: *Jesus.*

He has black and white skin and will be the one who will give back the country to the original people.

Jinn *Jin* (Arabia, India, Indochina, Persia)

Also known as: *Ajnan* (Male), *and Jinniyah* (Feminine; Islamic), *Div, Djinn, Genie, Genii, Ghaddar* (pre–Islamic), *Ghul* (pre–Islamic), *Ifrits, Jann, Jinniyeh, Junun* (plural; Islamic), *Marid, Nar, Nara, Qutrub* (pre–Islamic), *Se'irim, Shaitan.*

Demons of evil and good. They live on the mountain Kaf and are ruled by King Suleyman or as some say, Azazel. Made of fire, they live, die and give birth much as humans do. However, they are extremely long-lived. Along with a sense of humor, they have supernatural powers. It is said that the Jinn assisted in the construction of pyramids. There are good and bad Jinn. They can appear as human. In the Arabic tradition, the plural is Jinn, the feminine Jinniyah, and the singular, Jinni. There are five types of Jinn: the Jann who have the least amount of power; the Jinn, usually evil; the Shaitan, who are usually imps or devils; the terrible Ifrit; and the Marid, who are the most evil and the most powerful. The leader and chief of the Jinn is Iblis. Usually the Jinn are invisible, but they can appear in any animal or human form. They frequently appear as snakes. In Persia a similar demon is called the Jann. Described as half-wolf, half-hyena. Jinn corresponds to Rephaim. There are many of these demons in all religions. The most common names are Divs, Damrukh Nara, Shelan Nara, Mardash Nara, Kahmaraj, Nara, Al, Akwan, Jann, Tarnush. *See also* Afreet; Al; Apsarases; Bhutas; Dalhan; Demons; Dusii; Genii; Iblis; Incubus; Lokapalas; Nagas; Rakshasas; Satyrs (Greek); Yakshas.

Jinniyeh (Middle Eastern) *see* Jin.

Jitoku (Japan) *see* Samantabhadra.

Jivaro People — Creation Legend (Andes, South America) *see* Cupara.

Jizaiten (Tibet) *see* Trailokyavijaya.

Jizo (Japan) *see* Jizo-Bosatsu.

Jizo-Bosatsu (Buddhist; Japan)

Also known as: *Jizo, Kshitigarbha* (India), *Ti-tsang Wang-p'u-sa* (China).

A god of mercy, and guardian of those in need, Jizo-Bosatsu will assist believers on all levels of existence. He protects the souls of little children and is propitiated by pregnant women and travelers. He carries a staff with six jingling rings that warn of his approach in case he should inadvertently step on a living creature. His statue is placed at crossroads. He is shown seated, bearing a jewel that grants wishes (the Cintamani) in his ring hand, and a staff in his left hand. *See also* Kshitigarbha; Ti-tsang; Yama Kings.

Jjuko (Bugand, Bantu People; Africa)
The spirit for fixing things. *See also* Balubaale; Kibuuka.

Joagh (Africa) Another spelling for Jocasta.

Joagh (Africa) *see* Juck.

Joca-Huva (Haiti) Sky god and possible son of Atabei (q.v.).

Jocakuvague (Antilles Islands, Haiti) *see* Guamaonocon.

Jocasta *Jocaste* (Greek)
Also known as: *Epicaste* (Homeric), *Iocaste, Iokaste.*
Deified mortal. Jocasta is the daughter of Menoeceus, the sister of Hipponome and Creon, and the wife of Laius and mother/wife of Oedipus. When Oedipus was older, the mother and son met. They did not recognize one another. A relationship ensued. She became the mother by Oedipus of the sons Eteocles and Polynices and daughters Antigone and Ismene. When she discovered that Oedipus was her son, she hung herself. Oedipus blinded himself. *See also* Antigone; Oedipus.

Jocaste (Greek) *see* Jocasta.

Jodo (Japan)
Also known as: *Ching-tu* (China).
Jodo is a heavenly western paradise ruled by Amita. It is similar to Kun-lun mountain. *See also* Ching-Tu.

Jogaoh (Iroquois People, North America)
The Jogaoh are fairy or dwarf people similar to the Pukwudjies of the Objiwa. There are three types: the Gahonga who inhabit rivers and rocks, the Gandayah who are in charge of grains, fruits and fish, and the Ohdowas who live underground. Their job is to keep control of the monsters who inhabit the underworld. *See also* Gahonga; Ohdowas; Pukwudjies.

Joghi (Africa) *see* Juck.

Jok (Acholi People, Africa) Juck.

Joli-Torem (Vogul People, Siberia)
Creator. His sister, Num, was the director of the the work involved in creation.

Jomali (Teutonic) *see* Jumala.

Jonakr (Teutonic)
Also known as: *Hraesvelgr.*
God of winter. Husband of Gudrun and father of Erp, Hamdir and Sorli. Possibly the same as another Winter God named Hraesvelgr (q.v.). *See also* Gudrun.

Jongsuli-Young-Jongbu (Dhammai People, India)
The sky god, Jongsuli-Young-Jongbu, and his earth goddess sister, Subbu-khai-Thung, were the first born children of Shuznaghu and Zumiang-nui, who existed above in a place where neither sky nor earth existed. The children were swallowed by the worm, Phangnalomang, and later rescued by another sibling. Upon release, Jongsuli-Young-Jongbu became the sky and his sister, Subbu-khai-Thung, became the earth. Together, they gave birth to the god Sujang-Gnoi-Rise and the goddess Jibb-Jang-Sangne, who became mountains. They also had a son, Lujjuphu, and daughter, Jassuju, who were born as frogs. The frogs mated and gave birth to the first mortals, Abugupham-Bumo and Anoi-Diggan-Juje. *See also* Shuznaghu.

Joogi (Africa) *see* Juck.

Jord *Jordh* (Norse; Teutonic)
Also known as: *Fjorgyn, Hlodyn, Jord Nerthus, Jorth.* (May be feminine version of *Njord* [also called *Erda*].)
Earth mother, or earth goddess. She is the mother of the human, Mannus. *See also* Aesir; Annar; Frigga; Odin; Thor.

Jordegumma (Swedish) *see* Madderakka (Lapp).

Jormungandr *Iormungandr* (Norse; Teutonic)
Also known as: *Midgard Serpent, Midgardsormen.*
Serpent. Jormungandr laid at the root of the tree of life, Yggdrasil, before Odin cast him into the sea. He is the offspring of Gulveig (or Loki) and brother of Fenrir and Hel. Jormungandr became so large he encircled the earth biting his own tail. He was killed by Thor, who in turn was drowned by the serpent's venom. *See also* Angerboda; Fenrir; Gullveig; Loki; Midgard; Nagilfar.

Jorojin *Ju-rojin, Jui, Jurojin* (Buddhist; Japan)
Jorojin, one of the Shichi Fukujin (seven deities of happiness), is the white-bearded god of longevity, wisdom and good luck. His origins stem from China. He is the controller of good health. Jorojin enjoyed drinking sake but was never considered a drunkard. A short god, he is accompanied variously by a tortoise, crane, or a black deer, all representing a happy old age. He sometimes appears dressed as a scholar, wearing a headdress and is also depicted leaning on a long staff. Sometimes he is holding a stick with a book on top. The book represents the life limit of every individual on earth. In Japan the crane is called *tsuru* and is a royal bird, symbolizing valor and loyalty. The deer is symbolic of Buddha's teachings and is one of the forms in which Buddha was born. In Japan the tortoise is the symbol of longevity (combined with the peach it signifies immortality). *See also* Fukurokujin; Shichi Fukujin.

Jorth (Teutonic) *see* Jord.

Jotun-heim *Jotunheim, Jotunnheim* (Teutonic; Norse)
Also known as: *Utgard.*
This is the snowy land of the giants who are known as Jotuns. The major city in Jotun-heim is Utgard. Jotun-heim is the home of Bergelmir, the only frost giant to survive the war between Odin and his family. Jotun-heim is one of the nine worlds which has a root of the Yggdrasil extending into it. In one myth the Jotuns were so cruel to mortals that the Aesir used the giant Ymir's eyebrows to make a great wall around the land of mortals, Midgard. *See also* Aesir; Baugi; Bergelmir; Jotuns; Midgard; Mimir; Odin; Utgard; Yggdrasil; Ymir.

Jotunnheim (Teutonic) *see* Jotun-heim.

Jotuns (Teutonic)
Also known as: *Jotun.*
These hostile ice giants were conquered by Odin. Three of the giants were female or perhaps one female giant born three times. Their names are Aurboda, Gullveig (also known as Gulvieg-Hoder), and Hag. They reside in Jotun-heim (q.v.). *See also* Gullveig; Mani (A); Odin; Thor; Utgard.

www.ebook3000.com

Joukahainen (Finland) *see* Vainomoinen.

Jouskeha (Native North American) *see* Ioskeha.

Jove (Etruscan, Roman)
Also known as: *Jupiter, Vediovis.*
Thunder god. Jove is another name for Jupiter. He is the Roman equivalent of Jehovah and Zeus. *See also* Jupiter; Mercury (A); Zeus.

Jubal (Sumer) Patron of music. *See also* Ea; Enki; Lumha.

Juck (Shilluk People, Africa)
Also known as: *Juok.*
Creator god. Although he created the world, he does not direct it. He is a very impersonal deity who is present in all things. In the beginning, he created the white man from white sand, the brown man from Nile mud, and the black man from black earth. *See also* Nyikang.

Juemel (Finno-Ugric, Slavic) *see* Jumala.

Juggernaut (India) *see* Jagannath.

Juichimen (Buddhist) God of mercy. *See also* Kuan Yin.

Juji-Yama (Japan) *see* Fuji.

Jukkui Ajayo (Inca People, South America)
Also known as: *Pipisao.*
Life force. It is believed this deity is a type of spirit responsible for the health of the body and mind. It leaves at night during sleep, but appears in dreams. It must return before the body awakens. If forced away by shock, the body is exposed to illness. *See also* Pachamama.

Juksakka (Lapp)
Goddess of birth. She had the primary function of changing the girl child into a boy child while still in the womb. Daughter of Maderakka.

Jukurokujin (Japan) *see* Fukurokujin.

Julunggul *Julunggl* (Maori People, Australia, New Zealand)
Rainbow snake (q.v.).

Jumala (Finno-Ugric, Slavic)
Also known as: *Ibmel, Ilmarinen, Jomali* (Teutonic), *Jemel, Jumla, Jumo, Mader-atcha, Ukko.*
Supreme god. God of the sky and thunder. God who decides how long mortals will live. He lives in the highest story of heaven in a house glistening with gold and silver. He has seven sons, and many assistant spirits who have wings. The Norse call him Jomali. Jumala was later replaced by Ukko. He is associated with Sangke. *See also* Ilmarinen; Ukko; Vainomoinen.

Jumla (Finno-Ugric, Slavic) *see* Jumala.

Jumna *Yami* (Hindu; India)
She is the goddess of the river of the same name (earlier known as Yamuna River), and the spouse of Varuna. Vasudeva crossed the Jumna when carrying the infant Krishna. *See also* Varuna; Yami.

Jumo (Finno-Ugric, Slavic) *see* Jumala.

Juno (Roman; may have been assimilated from the Etruscan deity Uni or Iuno)
Also known as: *Hera* (Greek), *Iuno* (Etruscan), *Juno Caelestis, Juno Lucina* (goddess of childbirth) *Juno Moneta* (goddess of finance), *Saturnia* (daughter of Saturn).
Goddess of marriage. Protector of women and of childbirth. Goddess of finance. Goddess of war. Originally, Juno was the goddess of the moon. Later, she assimilated to the Greek Hera. She is the daughter of Saturn and the wife of Jupiter. They are the parents of Mars. When Gaul assaulted Rome, her geese gave her warning and she saved the city. Her various epithets are Cinxia, Domiduca, Huga, Jugalis, Matrona, Pronuba, Unxia, Curitis (Quiritis), Lucina, Moneta, Regina, Sosphita, and Virginensis. Juno, the bitter enemy of Semele, was said to have struck Semele's son, the wine and fertility deity, Bacchus, with madness. Her sacred animal is the goat, and her sacred fruit, the fig. Juno's festival date is July 7. She is often shown as a stately woman holding a scepter with a bird on top in one hand and pomegranate in the other. She is associated with Jupiter and Minerva. *See also* Bacchus; Cupra; Hera; Semele; Tanit.

Juno Caelestis (Carthage) *see* Tanit.

Junun (Islamic) *see* Jinn.

Juok (Africa) *see* Juck.

Jupiter (The planet) *see* Brihaspati; Eurynome (A); Marduk; Tara (A).

Jupiter *Iuppiter, Juppiter.* (Roman; may have been a Syrian deity); (Jupiter of Doliche)
Also known as: *Heru-ap-sheta-taui* (Egypt), *Jove* (Etruscan), *Tina* (Etruscan), *Vediovis* (an early name), *Vedius, Vejovis* ("Little Jupiter"), *Zeus* (Greek).
Probably a war-god or fertility god. Air god. One of a triad of high gods; the other two are Mars and Quirinus. Jupiter was also part of the triad which included the goddesses Juno and Minerva. Different versions say he was son of Cronus and Rhea. Some say he was brother/husband of Juno. Some say he was husband of Antiope and father of Amphion and Zethus. Other consorts were Dione, Themis, and Europa. By Europa he was father of Minos, Rhadamanthus and Sarpedon. He was brother of Neptune, Pluto, Vesta, Ceres and Juno. In some legends his attendants were Victoria or Nice (Nike), Fama (goddess of flame), Fortuna, Hebe, or Juventas and Mercury. Jupiter was later assimilated to the Greek god Zeus. He was worshiped as Jupiter Feretrius (the smiter), Jupiter Elicius (lightning attractor), and Optimus Maximus (The Best and Greatest). He was first worshiped as a stone (Jupiter Lapis) when he came from Latium. He was worshiped by the Romans as a god of soldiers. He was called a patron of ironworkers. Oak trees were sacred to Jupiter. The name Vejovis, or Vedius, was used for Jupiter when he appeared without his thunder. Most legends of Jupiter parallel those of Zeus (q.v.). Compare to the Norse gods, Odin, Thor, and the Germanic Thunar. *See also* Aegis (Greek); Cronus; Dyaus (India); Jove; Juno; Mercury (A); Tina; Titans.

Jupiter-Ammon (Egypt) *see* Amen (B).

Jupiter Ammon (Greek) *see* Amen (B).

Jurapari *Jurupari* (Brazil)
Divine Protector. Guardian of tribal and family mores.

Jurasmat (Latvia)
"Mother of the Sea." High goddess. She follows mortals from birth to death. The other Lativian goddess who do the same are Laima (childbirth), Delka (the newborn), Laukamat (fields), Mezamat (wood), Lopemat (cattle), Darzamat (gardens), and Vejamat (winds).

Jurojin (Japan) *see* Jorajin; Shichi Fukujin.

Jurupari (Brazil) *see* Jurapari.

Jushkapariks (Armenian) *see* Hambaris.

Justice (Greek) An epithet of Themis, the goddess of justice.

Justice (Greek) Goddesses of justice. *See also* Dike, Themis.

Justice (Roman)
Goddesses of justice. *See also* Astraea, Justitia.

Justitia *Iustitia* (Roman)
Goddess of justice. She presides with Jupiter at a cult started by Augustus. Justitia is shown blindfolded, holding scales and a sword.

Juterna *Diuturna, Iuturna, Juturna* (Roman)
Goddess of healing springs, ponds, and rivers. In early times she was known as Diuturna. Her parents are Daunus and Venilia, and her brother is Turnus, the king of Rutulia. By Janus, she became the mother of Fontus. Jupiter seduced her, and later in compensation, he deified her. *See also* Janus; Jupiter.

Juturna (Roman) *see* Juterna.

Juventas (Roman)
Goddess of eternal youth. Patron goddess of the youth of Rome. She is similar to the goddess Hebe of the Greeks and is a symbol of the glory of Rome. *See also* Hebe; Jupiter.

Jvalamukha (India) *see* Amrtakundali.

Jwok (Africa) *see* Juck.

Jyotsna (India) Goddess of Twilight. *See also* Ratri.

K

K (Maya)
The god K is a wind god thought to be a form of Chac Mol (q.v.) *See also* "B."

Ka (Egypt)
The soul. Ka is created in mortals at the time of birth. The deity Khnum or an assistant made the mortal body on a potter's wheel and at the same time his or her double, Ka, was created. Ka stays within the mortal until the time of death when it splits into two and becomes a bird called the Akh. The bird flies into the Afterlife and becomes the Ka, or double of the mortal once again. Then the Ba, a human-headed bird, remains on earth in the body left behind by the Akh. In essence, Ka is the energy of every living thing. *See also* Ab; Ba; Fa.

Ka-Hemhem (Egypt)
Guardian. A lion god appearing in the sixth sector of Tuat.

Ka-onohi *Ka-onohi-o-ka-la* (Hawaii)
Conductor of the souls of dead chiefs. *See also* Lo-lupe.

Ka-onohi-o-ka-la (Hawaii) *see* Ka-onohi.

Kaang (Bushmen People, Africa)
Also known as: *Kho, Khy, Thora.*
The supreme god. As Thora, his adversary is Gawa, leader of the spirits of the dead who dwell in the sky. Sometimes Kaang is confused with Cagn. *See also* Cagn; Gawa.

Kaare (Norse; Teutonic)
Wind or storm giant. He is the son of Fornjotnr, the storm personified, the father of Iokul, the icicle personified, and the grandfather of Snaer, the snow personified. *See also* Fornjotnr.

Kaba *Kava* (Finno-Ugric, Russian)
Also known as: *Chuvash (Russian).*
Spirit of fate or providence. Father of the messenger, Puleh. The Russians call Kaba, Chuvash. *See also* Fates (Greek); Puleh.

Kabandha (Hindu; India)
Kabandha was a giant demon, the son of Devi Sri. During a fight with Indra, Indra's thunderbolt hit him and left him as a monster. As he wandered the forest he encountered Rama and begged him to destroy his body. From his ashes he was reborn as a good Gandharva. The appreciative demon assisted Rama in his fight against the demon king Ravana and his troops. He also advised Rama to become the friend of Sugriva, the king of the monkeys. He is headless with a large mouth and sharp teeth in his belly. His one large eye is centered in his breast. Legless, he moves around on eight arms. *See also* Gandharvas; Rama; Ravana; Sugriva.

Kabeiroi (Greek) Another spelling for Caberi (q.v.).

Kabibonokka (Algonquin People, North America) *see* Manibozho.

www.ebook3000.com

Kabil (A) *Kabul* (Maya) *see* Itzamna.

Kabil (B) (Arab, Persian) *see* Cain.

Kabirs (Greek) *see* Caberi.

Kabo Mandalat (Polynesia, New Zealand)
Demon of disease. This female spirit causes elephantiasis. She is depicted as a large hermit crab with legs like coconut trees.

Kaboi (Boliva, Brazil)
Possibly a bird deity. He is an ancient god who led his people from the lower world by a bird call.

Kabonian *Kaboniyan* (Tinguian People, Philippine Islands)
Culture Hero. Kabonian lives either in the sky or near Patok in a cave. In the first times he married a Tinguian woman. He gave the people rice and sugar cane and taught them to plant and reap. He also instructed the people how to perform ceremonies. Another important lesson he offered was how to rid themselves of evil spirits. Kabonian also entered the body of a woman to show her how to cure illness. Sometimes he is above the greatest of the deities, Kadaklan, in stature, and sometimes equal to him. *See also* Kadaklan.

Kaboniyan (Tinguian People, Philippine Islands) *see* Kabonian.

Kabta (Sumer) The god of bricks. *See also* Enki.

Kabun (Algonquin People, North America) *see* Kabibonokka; Manibozho.

Kacha (India) *see* Brihaspati.

Kaches (Armenian)
Similar to the Devs, the gluttonous, musical Kaches are benevolent spirits, and helpers of their god. They might be wind spirits. Compare the Kaches to Kobolds. *See also* Devs; Javerzaharses.

Kachinas (Zuni People, North America)
Kachinas are spirits of the dead who participate in the dancing and ceremonies along with the living. Their abode is at the bottom of a lake in an empty desert. They are generally represented as dolls.

Kachpikh (Tierra del Fuego)
Also known as: *Wild People.*
Evil spirits. These invisible spirits hate humans and can cause death and disease. They live in the forest or in caves.

Kadaklan (Tinguian People, Philippine Islands)
Creator. Kadaklan is not personalized. He is acknowledged as the creator of the earth, moon, stars, and sun. His wife is Agemem, and his two sons are Adam and Balujen. The sons and his dog Kimat, who is lightning, must see the Kadaklan's commands are obeyed. During storms Kadaklan amuses himself with his drum, which is the thunder. *See also* Kaboniyan.

Kadesh (Egypt) *see* Min; Qadesh.

Kadi (Sumer)
Kadi, the goddess of justice of Der, is a derivative of Kishar.

Kadomas (Tibet) *see* Dakinis.

Kadru (India)
The daughter of Daksha, mate of Kasyapa, mother of Nagas and Nagis, a daughter Manasa, and sons Sesha and Kapila. *See also* Daksha; Garuda; Gauri; Kasyapa; Manasa; Nagas and Nagis; Sesha.

Kafisi (Melanesia)
Creator goddess, she is the sister of Bunosi (q.v.).

Kagami (Japan) *see* Amaterasu.

Kagoro (Baziba People, Africa)
Kagoro is one of four sons of the father of gods, Wamara. His three brothers are Mugasha, god of water, Kazoba, god of the sun and moon, and Ryangombe, god of cattle.

Kaggen (Africa) *see* Cagn.

Kagu-Hana (Japan) *see* Jigoku.

Kagu-Tsuchi *Kagu-tsuchi, Kagu-Tsughi, Kagu-Zuchi, Kagutsuchi* (Shinto; Japan)
Also known as: *Ho-Masubi, Homusubi.*
Kagu-Tsuchi, the god of fire, is the son of Izanagi and Izanami. His birth scorched his mother and caused her death. The angry father drew his sacred sword and killed him. In the *Kojiki,* he is beheaded and in the *Nihongi* he is chopped into three pieces by Izanagi. Each dead body part created a deity and other deities sprang from his splattered blood. Kura-okami, Kura-yama-tsumi and Taka-Okami are other deities who were created during this episode. Some sources say that a total of eight deities were created from his death. Prayers are offered to Kagu-Tsuchi under the name of Ho-Masubi, who is known as the god who causes fire. In the Ryobu-Shinto tradition, Ho-Masubi is the god of Mount Atago. To protect one against fire, amulets of the wild boar were worn. The talisman of the wild boar was also used as protection against snakes in Japan. Complicated ceremonies were held to appease the fire god and to ensure the safety of dwellings from the devastation of fire. Kiri-Bi fire (pure fire) was obtained by the friction of pieces of Hinoki wood or by striking a hard stone with steel. The Emperor's food was prepared over Kiri-Bi fire and Shinto priests used it in their homes. The faithful had access to Kiri-Bi fire on New Year's day. It was obtained from the priests and carefully carried home. The home hearth would be lit from Kiri-Bi fire and the protection from fire would last throughout the year. Geishas and prostitutes could have Kiri-Bi fire struck over their heads to give them protection as they carried out their professional activities. For information about the *Kojiki,* the *Nihongi* and the Shinto creation myth, *see* Ama-no-minaka-nushi. One of Kagu-tsuchi's brothers is O-Yama-Tsu-Mi, the chief god and lord of the mountains. *See also* Atago-Gongen; Izanagi and Izanami; Kanayama-hime; Kura-okami; O-Yama-Tsu-Mi; Sengen.

Kagu-Tsughi (Japan) *see* Kagu-Tsuchi.

Kagu-Zuchi (Japan) *see* Kagu-tsuchi.

Kaguhana (Japan)
This deity locates those who do evil deeds. According to some he is shown on one side of Emma-O.

Kagura (Japan) *see* Amaterasu.

Kagutsuchi (Japan) *see* Atago-Gongen; Kagu-tsuchi.

Kah (Egypt) *see* Ba.

Kaha'i (Hawaii) God of lightning. *See also* Kariki; Tawhaki.

Kaharon (Greek) *see* Charon.

Kahil (Arabic) *see* Shahar.

Kahukura (Maori People, Polynesia)
God of war. Kahukura is a sacred deity of the early Maori people. His symbol is the rainbow.

Kai (Egypt)
One of the forms of Osiris in the sixth sector of Tuat.

Kai-n-Tiku-Aba (Samoa People, South Sea Islands)
"Tree of Many Branches." This sacred tree grows from the back of the father of the gods, Na Atibu. A man, known as Koura-Abi, who had a destructive disorder, came along and deliberately broke the tree down. The broken tree caused many people to be disruptive and even violent. The people scattered and sadness and sorrow became their companions. *See also* Nareau.

Kai-Tangata (Hawaii, Polynesia, New Jealand) *see* Kaitangata

Kaiaimunu (Melanesia)
The Kaiaimunu are powerful spirits who have individual names. Some legends say the Kaiaimunu were given to the tribe by Iko (also spelled Hido, Sido) a culture hero. The Kaiaimunu are generally made with wicker frames and depicted as monsters.

Kaikeyi (India)
One of Dasaratha's wives, she is the mother of Bharata. *See also* Bharata (A); Hanuman; Rama.

Kailasa (India)
Located on the sacred Mount Meru, Kailasa is the city of the gods Shiva, Kuvera, and Ganesha. *See also* Ganesha; Kuvera; Meru Mountain; Shiva.

Kaimai and Trentren (Araucana People, South America)
Two serpents who made the seas rise in a great flood to prove they had fantastic magic powers.

Kain (Hebrew, Moslem) *see* Cain.

Kaitabha (India) A giant demon. *See also* Durga; Kali.

Kaitangata *Kai-Tangata, Kattangata* (Polynesia)
Also known as: "*Man Eater.*"
Warrior deity. He is known for his prowess as a fighter. His wife is Whaitari, the cannibal chieftain from the sky, although a Hawaiian tale fashions the story differently, casting Hina-who-worked-in-the-moon as the wife of Kaitangata. They had two children, a son, Hema, and a daughter, Punga. Hema became the father of two sons, Tawhaki and Kariki. *See also* Hema; Tawhaki; Whaitari.

Kaizuki (Burganda People, Africa)
In some versions Kaizuki is the brother of Death. He is associated with the legend of Kintu, Gulu and Nambi.

Kaka-Guia (Africa) *see* Nyami.

Kakasians (Scythian) *see* Amazons.

Kakemono (Japan)
Carpenter gods. Kakemono of Fukurakuju is one of the seven gods of luck. He has a high domed head.

Kako (Greek, Roman) *see* Cacus, the fire-breathing giant.

Kala *Black Demon, Kala-Shiva* (Brahman, Hindu; India)
Kala is the god of time, death and destruction. When the universe is reborn after each destruction this deity insures that only those who are wise are not reborn but live on with him. He is usually identified with Shiva but sometimes with Yama, Brahma or Vishnu. Kala is also a name for Shiva as the spouse of Kali. *See also* Durga; Kali; Shiva; Yama.

Kala-Siva (India)
Double-sexed God of Time or Death. *See also* Kala; Shiva.

Kalacakra (Buddhist; Nepal, India)
Kalacakra turns the wheel of life. As Kalacakra is the title of a work in a division of the Kangyur, it is possible that Kalacakra is a personification of that work. He is usually depicted with four heads, each with three eyes. He has either twelve or twenty-four arms and two legs. His color is dark blue and he wears a tiger skin. He is always shown stepping to the left on two prostrate figures. The figure under his right foot holds a bow and arrow and the other figure holds a trident and the khatvanga (magic wand).

Kalachi (India) Yama's palace. *See also* Yama.

Kalaino *Celaeno* (Greek) *see* Harpies; Podarge.

Kalaipahoa (Hawaii, Polynesia)
Tree deity. She is the goddess who enters and poisons trees. Her two sisters, Kapo and Pua, are also poison trees.

Kalais *Calais* (Greek)
Another spelling for the wind god, Calais (q.v.).

Kalaka (India) *see* Daksha; Danavas.

Kalamahakala (India) *see* Mahakala.

Kalanemi (Hindu; India)
Kalanemi is the Rakshasa grandson of Hiranya-Kasipu, son of Virochana and nephew of the demon Ravana. His evil ways were extinguished when Vishnu killed him, but he was reincarnated as Kansa and Kaliya. *See also* Hiranya-kasipu; Kaliya; Kansa; Rakshasas; Ravana; Virochana.

Kalaratri (India)
This is a being created by Devi who was unsuccessful in his battle against the demons. *See also* Durga (B).

Kalasi-Suti (India) Son of a Jar. *See also* Agastya.

Kalayavana (India) A demon. *See also* Krishna.

Kalee (India) *see* Devi.

Kalevala *Kalewala* (Finnish)
The Kalevala, meaning "The Land of Heroes," is one of the world's great epics. Written in 1835, by Elias Lönnrot, it is a col-

www.ebook3000.com

lection of Finnish myths, legends and romances. It portrays Finland's superiority over Lapland, and the adventures of the deified heroes of Ilmatar. *See also* Ilmarinem; Leshy; Sampo.

Kali (Hindu; India)

Also known as: *Bairavi* (The Terrible), *Bhavani, Bhima-Devi* (Terrifying Goddess), *Black Mother, Camunda, Candi, Chamunda, Chandika* (The Burning or Fierce), *Chinnamastica, Devi, Devi-Kali, Durga, Himavati, Kali-Ma* (Black Mother), *Kalika, Kamakshi, Karali* (Terrible), *Karna-Moti* (With Pearls in Her Ears), *Khadga Jogini, Khadga Yogini, Krittivasas* (Clad in Hide), *Kumari, Maha-Kali* (Mighty Time), *Mahakalee* (The Great Black One), *Mahamya, Menakshi, Nitya-Kali* (Endless Time), *Parvati, Raksha-Kali* (Guardian Kali), *Rudrani, Sati, Shmashana-Kali* (Kali of the Burning Ground), *Shyama-Kali* (The Black One), *Syama* (Black), *Tara, Uma* (Light), *Vajrajogini.*

Kali the warrior goddess is also the goddess of fertility and time, the goddess of mysteries, and the goddess of destruction and death. She is generally thought to be an aspect of the great mother goddess Devi. Other scholars believe that she is a goddess in her own right and not an aspect or incarnation of prior goddesses. Initially, Kali was a minor goddess in Hindu mythology. She appeared with a noose to lead away the dead after the Kauravas raided the sleeping Pandavas in the battle at Kuruksetra. Devi, who is frequently referred to as Durga, overcame the demons Kaitabha and Madhu who were born of Vishnu during his cosmic sleep. Later, the demon brothers Sumbha and Nisumbha took over the celestial kingdom and ruled over the deities. The gods called upon Durga to subdue the evil spirits. She appeared to them in the form of the beautiful and composed goddess Parvati and assured the worried deities that she would handle the situation. Equipped with weapons supplied by the gods, she marched into battle as Durga, to confront the demons Canda and Munda. When she saw them approaching, her wrathful form overcame her. Furious, she furrowed her brow and Kali emerged in all her terrible magnificence. She leapt into the fight, armed with her sword and noose, decapitated the demons and presented their heads to Durga as a gift. Durga called upon Kali again when she confronted the nearly invincible Raktabija (also spelled Ratavija). Every time Durga pierced him with her sword, demons from his blood emerged in his likeness. Kali sprung into being again and solved the problem by opening her gigantic mouth and swallowing the despicable creatures. Next, she sucked the blood from Raktabija gaping wounds and killed him. And so, the heavens were once again free from evil. Kali, the goddess of fertility and time, is the personification of the opposing forces of creation and destruction. When Kali danced with Shiva her frenzy overtook them and the earth shook with their rhythm. As Shyama-Kali she allocates boons and dispels fear. As a protector, she is known as Raksha-Kali and is called upon in times of epidemics and natural disasters. Shamashana-Kali embodies the power of destruction. Kali is the patron goddess of the infamous Hindu Thugs also known as Thags or phansigar (strangler), an organization of murderers who were bound by vows of secret murder in the service of Kali. The goddess bares a slight resemblance to the earlier goddess of the night Ratri, the sister of the dawn goddess Ushas. She more closely resembles Nirriti the Vedic demon. The differences are that Nirriti is presented clothed, with golden hair, and Kali, the female warrior is black. Nirriti's popularity waned as Kali's emerged. Both goddesses are associated with death and sorrow. Kottavei, a goddess of war who appears in the Tamil pantheon, corresponds with Kali. She is known as a sorceress who feeds on carnage. Kali's attendants are the Dakinis, female demons who feed on flesh and blood. In one depiction, a young Dakini is shown in a crouching position, with a vessel on her head. Kali is depicted as a skeleton type black or dark blue naked figure bedecked with skulls and serpents. Her eyes are red, and her tongue protrudes from her blood-smeared face. She wears earrings made of corpses, a garland of severed heads, and a girdle composed of severed hands. She has ten hands, each holding weapons. In a Tantric depiction, she is shown with a necklace of heads; in her two right hands, she holds the sword and the scissors of death. In her left hands, a bowl of food and the lotus of generation. In art, she is also shown dancing on Shiva's body, swinging a sword in one hand and his head in the other hand. She is often seen standing with one foot on the leg and the other on the chest of Shiva. Sometimes she is shown feeding on the entrails of her victims. A ritual thought by worshipers to fulfill desires and receive special powers is to invoke Kali by repeating some of her other names: Sati, Rudrani, Parvati, Chinnamastica, Kamakshi, Umak Menakshi, Himavati and Kumari. Her festival Durga Puja is celebrated in the autumn. Since the prohibition of human sacrifice, goats instead of human heads are presented as an offering to the goddess. Kali symbolizes the productivity of Nature. Her color is yellow and she is associated with the number five. Compare the awesome Kali to the irresistible Krishna. Compare Kali to Isis (Egypt). Kali and Durga resemble the goddess of smallpox, Sitala (q.v.). *See also* Agni; Bhavani; Dakinis; Devi; Devis; Durga; Gauri; Kala; Karttikeya; Kauravas; Khadga Jogini; Kumari; Lhamo (Tibet); Nirriti; Pandavas; Parvati; Ratri; Shiva; Tara; Ugra; Vishnu.

Kali-Durga (India) *see* Devi.

Kali-Ma (India) *see* Kali.

Kalia (Greek)

Goddess of vice. She tried to divert Heracles' attention from his studies with Cheiron, the immortal Centaur. *See also* Centaur; Cheiron; Heracles.

Kalika (India) *see* Devi; Karttikeya.

Kalinda-Kanya (India) *see* Yami.

Kalindi (India)

She is the daughter of Surya and wife of Krishna. *See also* Krishna.

Kaliya (Hindu; India)

Also known as: *Kalanemi* (an incarnation), *Kansa* (an incarnation).

Kaliya, an incarnation of Kalanemi, is a five-headed serpent who is depicted vomiting fire and smoke. His lives in the river Yamuna. It was from the river that he emerged to ravage the surroundings. As a child, Krishna dove from a tree into the water and the splash set the tree on fire. Kaliya and his troop of serpent demons attacked the young god, encoiled him and nearly killed him. Bala-Rama reminded Krishna that he was a god. Krishna then used his divine energy, overcame the serpent and danced on his head until he was left powerless. Krishna ousted him from his home and sent him to the sea but gave him his word that the Garuda, the enemy of serpents would not annihilate him. *See also* Bala-Rama; Garuda; Hanuman; Kalanemi; Kansa; Krishna.

Kaliyuga (Hindu; India)
Part of the Kalpa cycle, Kaliyuga is the present age, known as "the age of iron." It began just over 5,000 years ago and will last for 400,000, some say 432,000 more years. It is the age of degeneration and is called the worst of the four great periods of world history. Virtue is becoming non-existent and mortals await the coming of Kalki the destroyer. Kalki is the tenth incarnation of Vishnu. He will arrive on his white horse to restore order to the world. Before he arrives there will be a drought lasting one hundred years, and seven suns will appear which will remove the last of the water. Fire will consume the earth, then twelve years of rain will submerge the world. Brahma will return at this point and the cycle will start again. *See also* Dwaparayuga; Kalki; Kalpa; Mahakala; Tretayuga; Vishnu.

Kalki *Kalkin* (Hindu, India)
Kalki is the tenth, future and final avatar of Vishnu. As Kalki, his mother is Awejsirdenee, the wife of Bishenjun. Upon his return he will appear as a giant man with a white horse's head, wielding a flaming sword, astride a white horse riding through the sky. His purpose will be to end evil and wickedness in the world. His appearance will take place at the end of our age, which is known as the iron age. When he arrives the wicked will be destroyed and the world will be created anew to enter an age of advancement. The day of Kalki's arrival is called the day of Pralaya. On this day Shiva will dance on the disintegrated world and Vishnu will sleep so that the world will be born anew. Compare Kalki to the Buddhist Maitreya. *See also* Kaliyuga; Shiva; Vishnu.

Kalkin (India) *see* Kalki.

Kallin-Kallin (Australia) "Chicken Hawk" *see* Yalungur.

Kalliope (Greek) *see* Calliope.

Kalma (Finnish)
Kalma, the goddess of death, is an underworld deity. Her companion is a monstrous animal who seizes and devours humans. Her name means "corpse odor." In other versions, Kalma is a male, known as a god of tombs. *See also* Kalevala; Manala.

Kalmashapada, King (India) *see* Parashara.

Kaloafu (Polynesia)
Kaloafu is one of the foster parents of Eel (Tuna). The other was Tuehie. Tuna was the lover of Hina. *See also* Hina; Tuna.

Kalpa *Brahma-Kapla* (Hindu; India)
This is a sub-cycle of Mahapralaya. One day in the life of Brahma is equal to 4,320 million years, or according to some, 4 billion human years. At this time Brahma awakens and three worlds are created: heavens, middle, and lower regions. The Kalpa is divided into 1,000 Great Ages (Mahayugas). Each Mahayuga is further divided into the four ages or Yugas: Krita, Treta, Dwaparayuga, and Kaliyuga. In Jain mythology, Kalpa is one of the two uppermost levels of the universe; Kalpathitha is the other. In Kalpa, there are sixteen heavens known as Devalokas. Each Devaloka has a name and its own inhabitants. In Kalpathitha there are fourteen abodes for the gods. Indrani, the wife of Indra, is the owner of the magic Kalpa Tree also known as the Parijata Tree. It is kept in Swarga, the celestial dwelling place of Indrani and Indra. If the elderly gaze upon this tree, they will regain their vigor. *See also* Dwaparayuga; Indrani; Kaliyuga; Kalpa; Mahapralaya; Parijata; Sesha.

Kalratri (Nepal) *see* Vajravarahi.

Kalseru (Australia) *see* Rainbow serpent.

Kalumba (Africa) *see* Kalunga.

Kalunga (Angola, Luba People, Zaire, Africa)
Also known as: *Kalumba, Kalunga-Ngombe.*
Kalunga is a god of death or a place of the dead. In a Luba tale he also appears as a Supreme Being. He created mankind, then realized Life and Death were coming along the road. He instructed a goat and a dog to guard the path. The dog fell asleep while on watch and allowed Death to enter. In Bahai, Brazil, Kalunga was known as a god of the sea, one of the gods in a pantheon of African deities worshiped by the Congo-Angola followers.

Kalunga-Ngombe (Africa) *see* Kalunga.

Kalupso (Greek) *see* Calypso.

Kalura (Australia)
Possibly a rain god or one who is associated with spirit children.

Kalypso (Greek) *see* Calypso.

Kam-Pala (India) *see* Bala-Rama.

Kama (A) (Buddhist, Hindu, Vedic; India)
Also known as: *Cama Ananga* (Bodiless), *Iraja* (Born in Water), *Kama Deva, Kamadeva, Pradyumna* (an avatar), *Rupastra* (Weapon of Beauty), *Samantaka* (Destroyer of Peace), *Samsara-Guru* (Teacher of the World), *Smara* (Memory).
The Vedas proclaim Kama as a supreme god and creator, who sprang from the cosmic waters. His first emanation was desire and his second, the power to achieve desire. He created Nara (waters) and threw a seed into them which became a golden egg. From this egg came Narayana, who is an aspect of Brahma, or the son of Krishna. When Brahma was acknowledged as the supreme god, it was said that Kama sprang from his heart. As a creative moral force he is said to be the son of Sraddha, the goddess of faith, and Dharma, the god of justice and virtue. In later times, as the god of sexual desire and love, his parents are Vishnu and Mayadevi (delusion), or Vishnu and the goddess of beauty and fortune, Lakshmi. His mate is Rati, the goddess of desire and passion. A reluctant Kama, painted green, was sent on a mission by the gods to rouse Shiva from his meditations, which had been ongoing for centuries. Irritated at being disturbed, Shiva turned Kama to ashes with the fire from his third eye. During this period, the earth was dry and arid. Unsettled, Shiva, who had been stung by Kama's

www.ebook3000.com

arrow, was unable to return to his meditations until he married Parvati. The gods approached Shiva and requested that Kama, the god of love and sport, be returned to the world. He was restored as Pradyumna, the son of Krishna and Rukmini and was reunited with Rati. The beautiful, eternally youthful Kama rides on a parrot called Kameri, the wisest of all birds, or a peacock, the symbol of impatient desire. He carries a bow strung with bees, and five arrows pointed with flowers: the lotus, mango, asoka, muli and karunga, all emblems of desire. The blossoms of the damanaka tree which are associated with spring worship, are offered to Kama. His symbol is Makara, the monster fish, who is Varuna's vehicle. He is king of the love nymphs, the Aspara's, who dance around him. One nymph carries his red banner, bearing the emblem of Makara. Kama's adjunct is Vasanta, the deity who presides over the flower season, spring. Kama (love) ensures that creation in the universe will never cease. Kama is equated with the creative aspect of Agni (q.v.). He sometimes appears as an aspect of the Buddhist god of temptation and death, Mara (q.v.). Compare Kama to the Greek Eros. *See also* Asparases; Brahma; Dharma; Krishna; Lakshmi; Makara; Naryana; Parvati; Pradyuma; Priti; Rati; Shiva; Sraddha; Tapati; Vach; Vishnu.

Kama (B) (Hawaii, Polynesia)
High god. He is a powerful tutelar deity of all the islands.

Kama Deva (India) *see* Kama (A).

Kama-Dhenu (India) *see* Kamadhenu.

Kama-Yama-Hiko (Japan)
God of mountain minerals. *See also* O-Yama-Tsu-Mi; Sengen.

Kama-Yamato-Iware-Biko (Japan) *see* Jimmu Tenno.

Kamadeva (India) *see* Kama (A).

Kamadhenu *Camdhen, Kama-Dhenu, Kamdhain, Kamdhen, Kamdhenu* (Hindu; India)
Also known as: *Nandini, Savala, Surabhi.*

Kamadhenu, the "Cow of Desires," or the "Wish Cow," is one of the miraculous treasures churned from the sea by the gods. She has the ability to fulfill all wishes. In the form of a cow she belonged to Indra and to the sage Vasishtha. Kamadhenu produced the warriors who fought against the god of war, Arjuna. *See also* Parashur Rama for additional mythology. *See also* Kurma regarding the churning of the sea. Compare Kamadhenu to Audhumla (Teutonic). *See also* Arjuna; Nandi; Surabhi; Vasistha.

Kamado-No-Kami (Japan) *see* Inari.

Kamaheruka (Tibet) *see* Herukas.

Kamak (Iranian)
Drought demon. This gigantic bird holds back rain with its large wings. It was killed by Keresaspa (q.v.).

Kamakshi (India) *see* Devi.

Kamala (India) *see* Lakshmi.

Kamapua'a (Hawaii)
Also known as: *Kamapuaa.*

"The Great Boar." "Hog-child." Creator. He is the grandson of Kamaunua-niho (also spelled Ka-mau-nui, Kamaunu) the female sorcerer who was married to Humu (also spelled Aumu). In one of his numerous myths, he is newly born on the northern coast of Oahu. His older brother, Kahiki-honua-kele, tries to throw him away. His mother fresh from her purification bath finds him lying on her skirt in the form of a baby pig. His brother takes the infant pig to his grandmother's house. She recognizes her kupua grandson and raises him until he becomes of age. In another tale, Kamapua'a used his great snout to push up the earth from the bottom of the sea. This allowed the gods and people a place to live and land to cultivate. A protector of the gods and people, he was frequently in battle with their enemies. Kamapua'a also used his snout to dig wells. He was one of the many suitors of the great fire goddess, Pele. Initially, Pele looked upon him with disdain. However, in a contest, Kamapua'a won against his opponents by extinguishing all Pele's fires with mud. So it was that Kamapua'a and Pele were wed. He is described as a half-man and half-hog, but he is also a shape-changer. He covers the bristles on his back while in human form, often as a tall, handsome man, with sparkling eyes, by wearing a long cloak. Kamapua'a is also able to change himself into a fish or into plant life. *See also* Pele.

Kamapuaa (Polynesia, Hawaii) *see* Kamapua'a.

Kambel (Melanesia)
Sky deity and creator. Possibly a god of fire. Kambel cut down a palm tree which released humans.

Kamdhain (India) *see* Kamadhenu.

Kamdhen (India) *see* Kamadhenu.

Kamdhenu (India) *see* Kamadhenu.

Kame and Keri (Bacairi People, South America)
First men. They are twin brothers who after the Deluge became the creators of mankind, making men out of reeds. In another version, they created animals from a tree trunk. Kame and Keri stole balls of feathers from a vulture to make the sun and moon.

Kameri (India) Sacred parrot. *See also* Kama (A).

Kamehaikana (Hawaii)
Kamehaikana is the goddess Haumea's name when she is in human form. *See also* Haumea.

Kami (Japan, Egypt)
Also known as: *Ama, Chi-haya-buru, Kamit.*

Supreme force. Kami was created by Izanagi (Male Who Invites) and Izanami (Female Who Invites). Izanagi and Izanami were created by the triad produced from chaos. Their function was to create earthly manifestations. Their first creation was the Japanese archipelago followed by the creation of kami, followed by the divine rulers of the world. Kami represents all things produced. Kami is applied to all things from the lowest to the highest form of life, including the forces of nature. Kami means "beings more highly placed" and applies to everything that is revered. In the Shinto beliefs, all nature is venerated. By approximately C.E. 200 the religion of Shinto ("Way of the Gods") established that the Imperial Family had descended from the sun goddess Amaterasu. This gave the emperor kami. He was not worshiped as a deity but the unquestionable religious position of the Imperial Line was thereafter called sacred. This lasted until 1946 when the emperor Hirohito renounced his divinity. Deities and spirits were also known as kami, though not all were worshiped. There are two groups of kami: those of heaven, Ama-Tsu-Kami and those of earth, Kuni-Tsu-Kami. In time, almost everything in nature and every locality had its kami, or spirit which were honored by shrines and sanctuaries. In early times Ama and Kuni (heaven and earth) were linked by stairs or some say a bridge called Ama-no-hashidate. This allowed the gods to communicate with earth by way of messengers. Some traditions say that kami was an early name for Egypt. For the Shinto creation myth, *see* Ama-no-minaka-nushi. Kami generally corresponds to the two souls of the gods. In some traditions, it corresponds to the gods and powerful mortals and in others the two souls exist in gods and mortals. The gentle, kind and happy one is nigi-mi-tama and the rough or violent one is ara-mi-tama. The opposite of Ama (heaven) was the underworld or kingdom of the dead called Yomi-tsu-kuni (land of darkness) or Ne-no-kuni (land of roots) or Soko-no-kuni (deep land). *See* Ama-tsu-kami for details of Ama (heaven). *See* Yomi for details about the underworld. For additional names applied to the bridge Ama-no-hashidate, *see* Izanagi.

Kami-mi-musubi (Japan) *see* Kami-mimusubi.

Kami-Mimusubi (Shinto, Japan)

Also known as: *Kami-mi-musubi* (Divine or Mysterious-producing), *Kami-musubi-mi-oya-no-mikoto, Kami-musubi-no-kami, Kamu-musubi.*

Mother goddess. Kami-mimusubi and her male counterpart Taka-Mimusubi are considered the secondary couple who followed the triad who sprung from primeval chaos. Her daughters are Yorodzu-hime (Taku-hata chi-hata hime), and probably Mi-ho-tsu hime. Her son is Suku-Na-Biko, who became the chief of the medicine deities. Another son may have been Omohi-kane no kami. When she heard the appeals of Okuni-nushino-mikoto's mother when he was killed, she returned him to life as a handsome young man. Kami-Mimusubi collected the seeds produced by the food goddess Ogetsu-hime-no-kami and used them for nutritional purposes. (Ogetsu-hime-no-kami is also known as Ogetsu-hime and Oho-ge-tsu-himi.)

In some traditions, Kami-Mimusubi represents Kami Romi. For information, *see* Ama-no-minaka-nushi. This listing will also give information regarding the Shinto creation myth and the *Kojiki.* Kami-Mimusubi is listed in the *Kojiki* as the third of the "Five Deities." Compare this myth to Amaterasu, who used goods produced by Ukemochi to produce a food supply. *See also* Okuni-Nushino-Mikoto; Suku-Na-Biko; Taka-Mimusubi; Ukemochi.

Kami-Musubi (Japan) *see* Kami-mimusubi.

Kami-musubi-mi-oya-no-mikoto (Japan) *see* Kami-mimusubi.

Kami-musubi-no-kami (Japan) *see* Kami-mimusubi.

Kami-nari (Japan) *see* Raijin; Take-mi-kazuchi.

Kami-rogi (Japan) *see* Ama-no-minaka-nushi.

Kami-romi (Japan) *see* Ama-no-minaka-nushi; Kami Mimusubi.

Kamiizanaginarisan (Japan) *see* Kami-Nari.

Kaminari Sama (Japan) *see* Raiden.

Kamit (Japan) *see* Kami.

Kammapa (Sesuto People, Africa)

The monster Kammapa devoured all mortals except one old woman. She gave birth to a child without the help of a man. She named the child Lituolene, who was born as an adult. In attempting to kill the monster, Lituolene was swallowed, and once inside he cut the monster open and released all the humans.

Kammus (Moabite) *see* Chemosh.

Kamo-hoalii (Polynesia, Hawaii) *see* Kamohoali'i.

Kamohoali'i (Polynesia, Hawaii)

Also known as: *Kamo-hoalii, King Moho.*

God of steam (vapor). Kamohoali'i is the son of the goddess of childbirth, Haumea. His sisters are Pele, the angry volcano goddess of Hawaii, and Hi'iaka. *See also* Pele.

Kamrusepas (Mesopotamia)

This goddess of magic and healing sent a bee to awaken Telepinus with its sting. He is the god of agriculture, fertility, and youth who had disappeared and brought all life to a standstill. Her actions were to remind him of his duty and to bring back the sun and life to mortals. *See also* Telepinus.

Kamsa (India) *see* Kansa.

Kamu-mimusbi (Japan) *see* Ama-no-minaka-nushi.

Kamu-mimusubi (Japan) *see* Ama-no-minaka-nushi.

Kamu-musubi (Japan) *see* Kami-mimusubi.

Kamu-yamato-ihare-biko (Japan) *see* Jimmu Tenno.

Kamus (Moabite) *see* Chemosh.

Kan-Xib-Yui (Maya People, Yucatan) *see* Ahmucen-Cab.

Kana (Hawaii, Polynesia)

Hero. Kupua (demi-god). Many of his legends tell us of his adventures as he traveled from island to island battling the evil Kupua. Often his impish brother Niheu (Sand Crab) accompanies him. Kana, born as a rope, is very, very tall. He can step from one island to another even though they may be 70 miles apart. He is variously known as the son of Hina and Hakalanileo, Ku and Uli. Uli is sometimes his grandmother who raised him. One of Kana's most famous deeds was to travel to the entrance of the underworld to restore the stolen sun to his people. *See also* Ku; Kupua; Uli.

Kana-yama-biko-no-kami (Japan)

"Metal Mountain Prince Deity." *See also* Kanayama-hime; O-Yama-Tsu-Mi; Sengen.

Kana-yama-hime (Japan) *see* Kanayama-hime.

www.ebook3000.com

One must remain open and empty while using one's intentions, mind and Chi to draw the energy into oneself. What might initially appear to be a paradox is reformed as one does the practice and learns how to be empty and open and to simultaneously retain enough consciousness to draw the force into oneself.

Mind, Organs and Sexual Organs

It seems that some people are disconnected from themselves and from their sexual organs. The mind and organs are therefore separate. Taoism believes that the mind, body and spirit must work together. The results depend on a person's practice.

Brain

The brain can access and generate the higher forces, but storing this energy in the brain itself is not easy. We need to train the brain to increase its ability and capacity to store energy. The brain energy, when increased to a certain level, can enable more synapses to grow, and can help turn protein into brain cells. The Tao believes that with training and practice, one can learn to grow more brain and nerve cells, as well as increase the number of synapses in the central nervous system.

Organs of the Body

The organs can also generate energy, but much less than the sexual organs and the brain. They also have a much greater capacity to store and transform energy.

Sexual Organs

The Tao discovered that the sexual organs are the only organs that can generate a significant amount of sexual energy (life force). However, the sexual organs cannot store the energy efficiently. When too much energy is generated, considerable amounts have to be dumped out. And this is the best energy that one has. It is the ‘creative’ energy.

Three Tan Tiens

The Three Tan Tiens can also store energy, transform it and supply it to the brain, spinal cord, sexual organs and other organs.

The aim of Taoist basic training is to integrate the brain, sexual organs and other organs into one system. If the brain generates too much energy, it can store the energy in the organs. The excess sexual energy can also be stored in the organs and the three Tan Tiens. If the brain generates too much of the higher forces and we are unable to store this energy, we have to throw it away. It is like preparing food for one hundred people, when only one person is eating. The rest gets thrown away. In the same way,

Kanaima (Arawak People, New Guinea) *see* Kenaima; Makonaima.

Kanakamuni (India) *see* Manushi-Buddhas.

Kanaloa (Hawaii, Polynesia)
Also known as: *Milu, Tangaroa*
God of the Underworld. God of the Squid. Teacher of magic. After earth was separated from heaven, Kanaloa became the leader of the first group of spirits placed on earth. It is said that the spirits had been "spit out" by the gods. Kanaloa led them in a rebellion but they were defeated and thrown into the underworld. People who are associated with canoes invoke Kanaloa and Kane. Kanaloa is called upon for the safe sailing of the canoe and Kane for canoe building. Kanaloa and Kane are also connected with fish ponds. There are numerous legends about the adventures of Kanaloa and Kane as they traveled throughout the islands establishing water springs and making certain that the springs were kept clean. Kanaloa appears in the shape of an octopus. *See also* Kane; Miru; Tanaoa; Tangaroa.

Kanati and Selu (Cherokee People, North America)
The First Ancestors. The male, Kanati, and the female, Selu, were the first of the Cherokee people.

Kanayama-Hime (Japan)
Also known as: *Kana-yama-hime.*
Goddess of Metal. Kanayama-hime (Metal-Mountain Princess Deity) was created from the vomit of her mother, Izanami. Izanami had been seared and scorched by the birth of Kanayama-hime's brother, the fire god Kagu-tsuchi, and was deathly ill. Eight deities were born from her bodily emissions during this time. Kanayama-hime's brother/husband was Kana-yama-biko-no-kami (Metal-Mountain Prince Deity). *See* Sengen for other mountain deities. *See also* Izanami.

Kandu (India) *see* Pramloma.

Kane (Hawaii, Polynesia)
Also known as: *Kane-Hekili* ("Thunderer"), *Tane.*
God of Procreation. God of the Sea. In the first era, before heaven and earth, Kane dwelled alone in the darkness. Light was created in the second era. This is when the gods Ku and Lono, with Kane, created the earth and all that is on it. In the third era, they create man and woman, Kumu-honua (Earth Beginning) and Lalo-honua (Earth Below). In the fourth era, Kane, who had been living on earth, returned to live in heaven. The man, who had broken Kane's law, was then made immortal. In another rendition, Kane, Ku and Lono came out of po (night). They created three heavens. Kane's dwelling was the uppermost heaven, Ku's heaven came next and Lono's dwelling was in the lowest heaven. Then the gods fashioned the earth. Kane made the sun, moon and stars and placed them in the space between heaven and earth. He made the ocean salt. An image of man was formed from the earth, the head out of white clay brought from the north, south, east and west seas. Man's body came from red earth mixed with spittle. Man was formed after the image of Kane with Ku as the worker and Lono as the general assistant. Kane and Ku spat into his nostrils, Lono into his mouth and he became a living being. This first man is named Ke-li'i-ku-honua. He was given a splendid garden to live in and a wife, who was created from his right side. Her name is Ke-ola-Ku-honua (or Lalo-hano). In ancient times, the three gods were worshiped as one under the name of Hika-po-loa. Kane is known as "the organizer." Kane is comparable to, and some say the same as, the Polynesian god Tane (q.v.). In Hawaiian mythology Kane is the father of the Goddess of Hawaii, Hi'i-aka (q.v.). As a culture god, Kane's name is often coupled with Kanaloa, god of the squid. *See also* Kanaloa; Ku; Ku-ka-ohia-laka; Lono.

Kane-Hekili (Hawaii, Polynesia) "Thunderer." *See also* Kane.

Kane Hoalani (Hawaii, Polynesia)
Also known as: *Kane Milohai.*
This ancient god, who is the father of Pele, owns a miraculous sea-shell. If the shell is placed on the ocean waves it turns into a spectacular sailing ship that will float the owner to any destination required almost immediately. *See also* Kane; Pele.

Kane-Kahili (Hawaii, Polynesia) One of the volcano deities.

Kaneapua (Hawaii, Polynesia)
Fish god. Healer. Brother of the goddess Pele, Kaneapua and his brother Aukele-nui-aiku brought the first coconuts to Hawaii. They are planted at Kahaualea and Kalapana in the Puna district of the island. The akuhekuhe fish is one of Kaneapua's forms. *See also* Kupua-Huluena; Kuula; Laeapua; Pele.

Kangi and Mangi, The (Japan) *see* Hikohohodemi; Hosuseri; O-Wata-Tsu-Mi.

Ka'nini (Aborigine People, Australia)
Spirit of the "Great Mother from the Water."

Kannon (Buddhist; Japan)
Also known as: *Avalokitesvara, Bato Kannon, Fuku-kensaku Kannon, Ju-ichimen Kannon, Jundei Kannon, Kannon Bosatsu, Kuan Yin, Nyo-i-rin Kannon, Senju Kannon, Sho Kannon.*
Goddess of mercy. She is one of the Bodhisattvas. Kannon Bosatsu is generally associated with Amida. *See also* Amida; Kuan Yin.

Kannuck *Kanook* (Haida, Kwakiutl, Tlingit, Tsimshian People; North America)
Deified animal. Deity of darkness. The Wolf Spirit. Brother of Yehi. Kanook controls the waters and his brother, Yehi, is a spirit of light.

Kanook (Native North American) *see* Kannuck.

Kanro-O (Japan) *see* Amida.

Kansa *Kamsa* (Hindu; India)
Also known as: *Kalanemi* (an incarnation), *Kaliya* (an incarnation), *Kenss.*
During the second age of the world, Kansa, an asura (demon), was born as the son of Queen Pavanarekha and King Ugrasena. His real father is Drumalika, a demon, who assumed Ugrasena's form and raped Pavanareka. Their kingdom, Mathura, is an agricultural area and the populace is described as peace-loving. Eventually, Kansa deposed Ugrasena and ruled as a tyrannical king who oppressed his subjects. When he heard that his cousin Devaki would give birth to a son who would kill him, he murdered her sons and issued an order to have all male infants slaughtered. Devaki's infants Krishna and Bala-Rama

were spared through a ruse. Krishna was raised in the forest by the cowherds Yasoda and her mate Nanda. The goddess Devi transformed herself into the infant daughter of Yasoda and Nanda and told Kansa that Krishna had escaped and therefore Kansa would be made powerless. Kansa became the archenemy of Krishna and deployed multitudes of demons to obstruct him during his lifetime. The last plan he devised was to have Akrura, the head of his court, invite Krishna to Mathura for a sacrifice in honor of Shiva. He arranged to have Chanura, a wrestler, at the gates to overcome him. His backup plan was to have a huge elephant trample Krishna to death. What he did not know was that Akrura was a devotee of Krishna who went straight to Krishna and divulged the plan. A great brawl ensued with Krishna and Bala-Rama slaying Kansa and his eight brothers. *See also* Asuras; Bala-Rama; Devaki; Devi; Drumalika; Jara-Sandha; Kaliya; Krishna; Sisupala; Yadavas.

Kanthaka *(India)* Prince Gautama's horse. *See also* Buddha.

Kantoki-No-Ki (Japan)
Deified trees. Any tree struck by lightning is called Kantoki-No-Ki, which means "trees cloven by the god." They are never cut down.

Kanwa (India) *see* Shakuntala.

Kanya-Kumari (India) *see* Kumari; Shakti.

Kanzuras, Mount (Hittite, Hurrian) *see* Kumbaris.

Kapala (India) "Skull." *See also* Shiva.

Kapila (India) *see* Kadru; Manasa; Sagara.

Kapisha (India) Mother of the Pishachas (q.v.).

Kapohoikahiola (Hawaii, Samoa)
God of explosions. One of the volcano deities.

Kappa (Japan)
Water monster. River god. Kappa the dwarf was born from the mortals who had drowned in Japanese rivers. He has magic powers used to draw people, particularly children, to him. Like the evil Oni, he also rapes women. Since he is very polite, one can escape his clutches by bowing low to him. When he returns the bow, all the water leaks out from the hole in his head and he is rendered impotent. Although evil, he has a reputation for teaching mortals how to set broken bones and is also a trustworthy creature. If he compromises with a mortal, he will keep his end of the contract even to his own detriment. In some renditions Kappa is used in the plural. Kappa or the Kappa live in rivers, ponds or lakes and are vampires, feeding on their prey through the anus. Aside from blood, they like cucumbers and can be placated by tossing the vegetable into their dwelling places. Some think they originated with the early, semi-nomadic Ainu people. The mouths of streams and rivers have a deity known as Minato-no-kami. Kappa resembles a monkey without fur. Sometimes he is shown with fish scales or a tortoise shell instead of skin and is about the size of a small child. He is yellow-green, with an indentation on the top of his head. He is also depicted with the head of a monkey, body of a tortoise and legs and arms of a frog. *See also* Gaki; Oni; Shiko-me; Tengu.

Kapua (Hawaii) *see* Kupua.

Kara (Teutonic) *see* Valkyries.

Karala (India) "The Formidable." *See also* Durga; Parvati.

Karali (India) *see* Kali; Durga.

Kardama (India) *see* Varuna.

Karei *Kari* (Semang People, Malay Peninsula; Andaman Islands).
Creator. God of storms and thunder. Giver of souls. Recorder. Judge. His companion is Ple. He punishes wrong-doers for sins such as mocking tame or helpless animals, killing sacred birds, killing the sacred black wasp, and being too familiar with one's mother-in-law. When angry, he causes thunder. To atone, the sinner must gash shins, mix blood with water and toss it to the sky while calling out "Stop, stop."

Kari (Teutonic) Lord of the storm giants. *See also* Aegir; Ymir.

Karia (Australia) *see* Rainbow Snake.

Kariki *Karihi* (New Zealand, Hawaii, Polynesia)
Also known as: *Aliki* (Hawaii), *Kaha'i.*
Culture hero. He is the brother of Tawhaki, who is called the god of thunder by the Maori People, and son of Hema and the goddess Urutonga. His grandparents are Kattangata and the cannibal chieftain, Whaitiri. Kariki and his brother are involved in many adventures together as they search for their father who had been abducted by goblins, beaten to a pulp and thrown into a pit. *See also* Hema; Kaha'i; Tane; Tangaloa; Tawhaki; Whaitiri.

Karisini (India) *see* Lakshmi.

Karitay (Tamil People, India)
"Dark Mother." An ancient goddess of the forest who feeds demons from her beggar's bowl. *See also* Aiyai.

Kariteimo (Japan) *see* Kishimojin.

Karkotaka (India) *see* Nagas.

Karl (Norse; Teutonic)
God of Peasants. Karl is the son of Amma by Heimdall. He is the husband of Snor. He is the founder of the race of peasants. *See also* Heimdall.

Karlafberge (Teutonic) *see* Odin.

Karliki (Slavic)
The Karliki are various classes of spirits. *See also* Domovoi; Lyshie.

Karma Dakinis (India) *see* Dakinis.

Karma-Heruka (Tibet) *see* Karma-Krotishaurima.

Karma-Krotishaurima (Tibet)
She is found with her spouse Karma-Heruka in the Bardo World on the twelfth day. *See also* Padma Krotishaurima; Ratna Krotishaurima; Shakti.

Karma-Sakshi (India) "Witness of Deeds." *See also* Surya.

Karna (Hindu; India)
Also known as: *Anga-Raja, Radheya, Vasusena.*
The sage Durvasas gave Kunti a secret charm by which she

www.ebook3000.com

could become pregnant by the god that she loved over all others. The result was the virgin birth of Karna, the son of Kunti and the sun god Surya. He was born in a full coat of brilliant armor. Ashamed of his birth, Kunti abandoned the baby on the banks of the Jamuna River. Yami, the goddess of the river, gave him to the Ganges River and its goddess, Ganga. She arranged that Radha and her spouse, the charioteer Nandana (also called Shatananda), would find him and raise him. Indra was fascinated by the shining armor of the sun-child. In exchange for the armor, Indra gave him his magic spear. Karna gained immense strength from the weapon and became a great warrior. He was made the king of Anga (now Bengal), by Duryodhana. He was one of the contestants for the hand of Draupadi and although he won the event, she rejected him. Distressed, he joined her enemies, the Kauravas. During the war of the *Mahabharata* he killed Ghatotkacha and was later killed by Arjuna. After his death, Arjuna learned that Karna was his half-brother, the oldest son of his mother. His mother gave birth to other children by various gods but always remained virginal through the power of the sage, Durvasas. *See also* Arjuna; Bhima (A); Duryodhana; Ganga; Indra; Kauravas; Kunti; Radha; Surya; Yami.

Karna-Moti (India) "With Pearls in Her Ears." *See also* Kali.

Karora (Gurra People, Australia)

Supreme deity. Karora was born in darkness at the bottom of Ilbalintja (a dry pond or lake). After he left, the pond became filled with the juice of honeysuckle buds. He was the creator of many sons. In one myth, the sons injure the wallaby (Tjenterama) who became the first ancestor of the race. Karora is still asleep in Ilbalintja.

Karpios (Greek) *see* Dionysus.

Karpo *Carpo* (Greek) *see* Carpo.

Karpophoros *Kourotrophos* (Greek) *see* Hera.

Karsnik (Slavic) *see* Krsnik.

Kartavirya (India)

King with a Thousand Arms. *See also* Parashur Rama.

Kartika (India) *see* Karttikeya.

Kartikeya (India) *see* Karttikeya.

Karttekeya (India) *see* Karttikeya.

Karttikeya *Karttekeya, Kartika, Kartikeya* (Vedic, Hindu; India)

Also known as: *Agneya* (Son of Agni), *Ganga-ja* (Born from the Ganges), *Gangeya, Guha* (Secret), *Kumara, Mahasena, Scanda, Scanda, Sena-pati* (Army Commander), *Skanda, Subramanya.*

Karttikeya, the god of war and bravery and patron of thieves, in late Vedic myth was given life expressly to slay the demons who plagued the gods. There are numerous myths relating to his origins. We are told of Indra coming upon the beautiful Devasena when he was in the forest. The horse demon Keshin was about to rape her but fled when he saw Indra with his vajra (thunderbolt). Devasena asked Indra to find her a mate and protector. Noting that her name meant "Divine Array," he felt that a warrior would be most suitable for her. He decided that Karttikeya would be appropriate. Strengthened by a mate with this auspicious name, this couple could lead the gods. In a variation of this story, Indra took Devasena to heaven to meet Brahma. Brahma decided that the god of fire Agni would be an appropriate mate for her. They became the parents of Karttikeya. In another version, when the gods were plagued by a demon, Shiva created six children by the flame of his third eye to combat it. His mate Parvati clasped them too tightly one day, and their bodies merged into one, but they retained six heads. He is also known as the son of Agni and the goddess of the river Ganges, Ganga. He was raised by the six Krittika sisters who received him from the Ganga. They all wanted to nurse him, so he developed six heads. Suaha, one of Daksha's numerous daughters, may have been his mother when she mated in disguise with Agni. He is also called the son of Daksha's daughter Parvati and Shiva, and the brother of Ganesha. He competed with Ganesha, the learned elephant god, for the hands of the goddesses of success, Siddhi and Buddhi, and Ganesha emerged the victor. Two goddesses, Bhadrakali and Kalika, who belonged to a group known collectively as the Matris or Divine Mothers, became Karttikeya's companions. They accompanied him when he went to slay the demon Taraka. These goddesses speak different languages, have different complexions, and wear various outfits. They live in trees, caves, crossroads, mountains and cremation grounds. (Kali was said to have belonged to this group.) In other renditions, Taraka was slain by Rama and Lakshmana. Karttikeya is depicted holding a bow and arrow as he rides Paravani, his peacock. Sometimes he is shown with six faces. Karrtikeya is identified with the planet Mars. He may have been derived from an ancient war god named Muruhan. Karttikeya is sometimes said to be the spouse of the goddess Shashthi (q.v.). *See also* Agni; Asuras; Bana; Bhisma; Brahma; Daksha; Devi; Ganesha; Ganga; Indra; Kali; Parvati; Rama; Taraka; Vach; Visvakarma.

Karu (Greek) *see* Car.

Karus (Greek) *see* Car.

Kasa-Nagi (Japan) *see* Susanowo.

Kasa Sona (Melanesia)

First beings. These deities were on earth long before mankind and were born with the sun.

Kasandra (Greek) *see* Cassandra.

Kasenko (Japan) *see* Ho-hsien-ku.

Kashijotem (Japan) *see* Kichijo-Ten.

Kashiko-ne No Mikoto (Japan) *see* Ama-no-minaka-nushi.

Kashyapa (India) *see* Kasyapa.

Kasin (Mayan) *see* Nohochacyum.

Kassandra (Greek) *see* Cassandra.

Kastiatsi (Acoma People, North America)

The Rainbow. *See also* Katsinas; Shruistha.

Kastor and Polydeukes (Greek) *see* Castor.

Kasyapa (A) *Kashyapa* (Brahmanic, Hindu; India)

Also known as: *Kasyapa Marica, Kesava.*

Kasyapa is the progenitor of all living things on earth. Mating with the self-formed goddess Aditi, they became the parents of the Adityas and the god Vivasvat. The *Vishnu Purana* states that Vishnu is also their son. He mated with Danu, the daughter of Daksha, and her sisters: Ira, the mother of earthly vegetation; Surasa; Diti, with whom he was the father of the Daityas; and Surabhi the cow goddess. With Vinata the underworld goddess he became the father of the Garudas. With Kadru, another of Danu's sisters, he became the father of the Serpent Race, known as the Nagas and Nagis. According to some renditions, he married all thirteen of Daksha's daughters. He was also the mate of the grandmother of the Garudas Tamra, and Sumati, the daughter of Vinata. He had another daughter, Saudamani, and was also the father of the Pisashas, Rakshasas and Yakshas. Kasyapa is one of the seven great rishis (sages) and an arch-priest for Rama. Kasyapa is sometimes identified with Prajapati (q.v.). *See also* Aditi; Agni; Andhaka; Aruna; Asuras; Daityas; Daksha; Diti; Gandharvas; Garuda; Gauri; Kadru; Krodha; Manasa; Marichi (B); Nagas and Nagis; Pisasha; Rakshasas; Rishi; Sagara; Sumati; Surabhi; Vishnu.

Kasyapa (B) (Buddhist; India)

Also known as: *Hodsrun* (Tibet), *O-sung* (Tibet).

Known as the luminous protector, Kasyapa is the third Manushi-Buddha who lived on earth for 20,000 years preceding Gautama Buddha. *See also* Manushi-Buddhas.

Kathar (Ugarit)

Also known as: *Kathar the Clever.*

God of architects, artisans, and weapon makers. Kathar built the palace of Baal. Kathar is identified with Hephaistos (q.v.).

Kathar-Wa-Hasis (Ugarit) *see* Khasis.

Kathirat, The (Syria, Ugarit)

They are known as the wise goddesses and have been compared to the Greek Graces (q.v.). They are depicted as swallows who are associated with maternity. *See also* Yarikh.

Katkochila (Wintun People, North America)

In the Creation Legend, Katkochila set fire to the earth after someone stole his magic flute. A great flood doused the fire.

Katonda (Luganda People, Africa)

Creator. This is a creator god. His name was used by the Christians and Muslims for their god.

Katsinas (Acoma People, North America)

Also known as: *Katcinas.*

Rain and food deities. Younger children of Iatiju, with powers to bring rain and food. Probably the same as Katcinas of the Pueblo People. *See also* Iatiju; Kastiatsi; Mayochina; Pishumi; Shk; Shruistha; Tsichtinaka; Uchtsita.

Kattangata (Polynesia) *see* Kaitangata

Katyayani (Southern India)

This goddess uses a tiger as her vehicle. The tiger's skin is used by worshipers of Shiva and by sannyasins.

Kauhausibware (San Cristobal)

Creator. Similar to Kafisi.

Kaukabhta (Syrian) *see* Astarte.

Kaukas (Lithuanian) *see* Krukis.

Kaukis (Prussia) Household dwarf spirits.

Kaukomielli (Finnish) *see* Ahti; Lemminikainen.

Kaulu (Hawaii, Polynesia)

Also known as: *Kana.*

Voyager. Trickster. God of cultivated foods. Kaulu is one of three brothers, one evil, one good. Born on Oahu, he is the youngest son of Ku-ka-ohia-laka and Hina-ula-ohia. His older brother, Kamano, threatened that Kaulu would die upon birth. Fearing to take human form, Kaulu chose to be born in the form of a rope. Another brother, Kaeha (or Kaholeha), put him on a shelf and cared for him. Kaeha was taken to the sky lands of Kane and Kanaloa. Kaulu went in search of him. The obstacles were many, but because of his two exceptionally strong hands, he was able to overcome them. When strong waves presented themselves, he broke them up. (As a result, we now have surf.) His troubles were far from behind him when he reached Kaeha. He had to trick and deceive the gods and the chief of sharks, Ku-kama-ulu-nui-akea (or Kalake'e-nui-a-a-Kane), who had swallowed Kaeha. When Kaulu finally retrieved his brother, they returned to Papakolea in Moanalua. Kaula went to Kapalama where he killed the goddess of fertility and guardian of cultivated plants, Haumea, and on to Kailua, where he killed Lono-ka-eho, who had eight foreheads and ruled the north side of Oahu, and his dog, Kuilioloa. In another adventure under the guise of a small weakly man, he was told by the gods Kane and Kanaloa to take all he could from their vegetable plot. *See* Kana, who was also born in the shape of a rope. *See also* Haumea; Hina-ula-ohia; Kupua; Kupua-Huluena.

Kauravas, The *Kurus.* (Hindu; India)

In the *Mahabharata*, the Kauravas are despicable scoundrels who are the enemies of their cousins, the five noble Pandavas. The Kauravas are the one hundred sons of the blind king Dhritarashtra and Gandhari. The eldest son, Duryodhana, became the leader of the Kauravas in the great war of the *Mahabharata*. When Dhritarashtra was offered the gift of sight by a magician, he refused because he did not want to see his people killed. In one episode, the Kauravas and Pandavas fought for possession of his kingdom. A public contest of strength was held between the cousins. Arjuna, a Pandava, was the winner who received the princess Draupadi as a prize. She became the wife of the five Pandavas. A gambling match took place and the Kauravas defeated the Pandavas by cheating and drove them into exile. It took thirteen years for the Pandaras to overcome the Kauravas. The Kauravas are also called Kurus, after their ancestor, Kuru. The Kauravas symbolize the forces of darkness, draught or winter, and the Pandavas symbolize fertility and growth. *See also* Arjuna; Bala-Rama; Bhishma; Duryodhana; Kali; Karna; Kunti; Pandavas; Tapati.

Kausalya (India) *see* Rama.

Kaushalya (India) Mother of Rama. *See also* Rama.

Kausiki (India) *see* Durga.

Kaustubha (India)

Vishnu's sacred jewel. *See also* Kurma; Vishnu.

www.ebook3000.com

Kauveri (India) *see* Kuvera.

Kauyumari (Huichol People, Mexico)
Also known as: *Wolf.*
Trickster deity. Most of the tales about this deity show him as a foil of the Moon. The Moon causes him a great deal of trouble such as having him cut down a honey tree only to find the honey turned to stones or lifting the tail of a donkey which is supposed to shower him with coins, but instead showered him with manure. There are many other tales of this deity and in some he appears to be involved in legends of creation. He is also said to be one of the survivors (along with a dog) of the flood caused by the earth mother, Nakawe.

Kava (A) (Iran, Persia)
Mythical smith deity. He and King Faridun were responsible for the capture and imprisonment of the evil Zahhak. *See also* Faridun; Zahhak.

Kava (B) (Finno-Ugric) *see* Kaba.

Kawa-no-kami (Japan)
River god. Although most important rivers have their own deities, Kawa-no-Kami is said to be king of all.

Kawelo (Polynesia, Hawaii) A trickster spirit. *See also* Kupua.

Kaya-no-hime-no-kami *Kaya-no-mi-oya-no-kami, Kaya-nu-himi, Kayanu-hime-no-kami* (Shinto; Japan)
Also known as: *Ko-no-hana-sakuya-hime* (Lady-who-makes-the-trees-bloom), *Nu-zuchi, Nuzuchi.*
"Ruler of the Grassy Plains." Vegetation goddess. Goddess of herbs. Protector of fields and meadows. Kaya-no-hime-no-kami is the daughter of Izanagi and Izanami. She became the wife of Opo-yama-tu-mi-no-kami and the mother of four daughters and four sons who were of the third earthly generation. As the daughter of Izanagi and Izanami, she was created after the eight islands of Japan. Other inhabitants created were the deities of the wind, sea, seasons, trees, mountains, valleys and fire. She is called one of the separated spirits of the goddess of food, Toyo-uke-bime, and the god of the boles of trees Kuku-no-shi (Kukunochi-no-kami). As Kuku-no-shi, this deity is associated with the god who protects the leaves of the trees, Ha-mori, and the god of the soul of the tree, Ko-dama (the Echo). One of her daughters, Kono-Hana-Sakuya-Hime (Blossoms-of-the-Trees-Blooming-Princess) married Ninigi (Prosperity Man). Kaya-no-hime-no-kami is associated with the goddess of fields, No-no-kami. The deification of vegetation is to encourage the regeneration of life and is connected with fertility and fecundity. Herbs are indicative of nature and health and are connected to food. As a symbol of natural forces, they can be medicinal or poisonous. In many civilizations, the tree is a manifestation of life. In Japan it was believed that trees were endowed with speech, known as the echo. The echo, Ko-dama, is the soul of the tree. *See also* Haya-akitsu-hime-no-kami (goddess of the sea); Izanagi and Izanami; Kuku-no-shi; Ninigi; O-yama-Tsu-Mi; Sengen (goddess of Mount Fuji); Toyo-uke-hime-no-himi; Ukemochi (goddess of food).

Kaya-no-mi-oya-no-kami (Japan) *see* Kaya-no-hime-no-kami.

Kaya-nu-himi (Japan) *see* Kaya-no-hime-no-kami.

Kayanu-hime-no-kami (Japan) *see* Kaya-no-hime-no-kami.

Kayumarth (Persia) *see* Gaya Maretan.

Kayurankuba (Zulu People, Africa) Storm spirit.

Kazoba (Baziba People, Africa)
Kazoba is the god of the sun and moon. His father is the father of gods, Wamara. He has three brothers: Kagoro; Mugasha, the god of water; and Ryangombe, the god of cattle.

K'daai Maqsin (Yakut People, Siberia)
Also known as: *Kudai-Bakshy.*
Spirit of blacksmiths. This underworld deity gives blacksmiths their skill. In some renditions, K'daai Maqsin is the name of the afterworld for the souls of blacksmiths.

Keagyihl Depguesk (Native North American)
The spirit of the whirlpool.

Keb (Egypt) *see* Geb.

Kebehsenuf (Egypt) *see* Qebhsneuf.

Kebehut (Egypt)
Goddess of freshness. Daughter of Anubis. *See also* Anubis.

Kebhsnauf (Egypt) *see* Qebhsneuf.

Keckamanetowa (Fox People, North America)
Also known as: *Ketchimanetowa.*
Deified animal. The Gentle Manitou. In some versions this is also the name of a creator.

Ked *Ket* (Celtic)
Also known as: *Annis.*
Malevolent deity. An evil mother goddess, she hides in caves or under rocks. She tries to catch children to suck their blood.

Keelut (Eskimo)
Evil spirit. Depicted as a hairless dog, this spirit who lives in the earth.

Kefi (Egypt) Kefi is a guardian of the tenth sector of Tuat.

Kehkeh (Egypt) *see* Aani; Utennu apes.

Kei-Kung (China, Taoist)
Also known as: *Lie-kung, T'ien-chu.*
Thunder god. Husband of T'ien Mu. *See also* Lie-kung; T'ien Mu.

Kek (Egypt)
Also known as: *Emen, Keku, Kekui.*
God of Darkness. He is the husband or mate of Kekut (Keket). Kek is probably a male version of Keket.

Keket *Kekuit* (Egypt)
Goddess of Darkness. Another name for Isis. One of the deities mentioned in the Pyramid Texts. She is the wife or mate of Kek or Kekui. *See also* Amun; Kekui.

Kekhet (Egypt) *see* Isis.

Kekri (Finno-Ugric)
Cattle deity. Kekri increase the number of cattle.

Keku (Egypt) *see* Kek.

Kekui (Egypt) *see* Kek.

Kekuit (Egypt) *see* Keket; Kekui.

Kelpie *Kelpy* (Scotland)

This one-eyed, ill-tempered water-sprite lurks in lakes, rivers and the sea. He rushes to his victims with a terrible roar, snatches them and drags them beneath the surface. In another version of this myth, he appears in the form of a horse on the banks of a river and intices travelers to mount him. Once mounted, he takes his rider into the deep water to drown. He is sometimes referred to as a god of lakes and rivers.

Kelpy (Scotland) *see* Kelpie.

Kematef (Egypt) *see* Amen (B).

Kemosh (Moabite) *see* Chemosh.

Kenaima *Kanaima* (Orinoco region, South America)

Also known as: *Orehu, Yauahu* (Arawak People).

The Kenaima are generally considered as greatly feared spirits of human origin. They are both malevolent and vengeful. The exception is the Orehu, water-sprites who appear as mermaids. They can be benevolent at times. The Yauhahu are usually the familiars of shamans or medicine men. The Kenaima usually appear in animal form. *See also* Makonaima; Orehu.

Kenemti (Egypt) *see* Assessors.

Keneu (Iroquois People, North America)

Also known as: *Kineun.*

Deified bird. This golden eagle assists Hino, the Thunderbird. In the legends of the Menominee Indians he is called Kineun. *See also* Hino.

K'eng-san-ku (China)

Also known as: *San-ku, Tsi-ku, Ts'iku.*

Deity of the Privy. Originally, she was a deified mortal named Lady Ts'i. She was killed by Lady Ts'ao by being thrown into privy-pit. She is usually shown as a large ladle with the bowl forming the head with a human face. Twigs and cloth make up her body.

Kengiu (Japan)

Also known as: *Ch'ien Niu* (China), *Ching Yuh* (Korea), *Hikoboshi.*

Cattle god. Known as the "Heavenly Herdsman," Kengiu was romantically involved with the weaver Shokujo (q.v.). *See also* Chin Nu (China); Shokujo.

Kenken-Wer (Egypt)

"The Great Cackler," a name for Geb (q.v.).

Kenos (Tierra del Fuego)

First man. Kenos was sent to Earth by the supreme god and told to bring order to the world. He fashioned male and female organs from peat, and from them, created mortals, the first of which was the ancestor of the Onas. He returned to the sky to become a constellation.

Keoloewa (Hawaii)

Ancient sorcery god. His image is made of wood dressed in native tapa, with the head and neck of wicker-work covered with red feathers to make it look like a birdskin. He wears a native helmet hung with human hair. His mouth is large and distended. This figure was placed in the inner room of the temple at the left of the door, with an altar before it. *See also* Uli.

Kenss (India) *see* Kansa.

Kent Sehet (Egypt) *see* Anubis.

Kentauros (Greek) *see* Centaurs.

Kentaurs (Greek) *see* Centaurs.

Ker (A) (Greek) *see* Keres.

Ker (B) (Pelasgian) Another spelling for Car or Q're, the solar god of ancient Syria.

Ker-Neter (Egypt) *see* Aaru; Ament; Amentet.

Kerberos (Greek) *see* Cerberus.

Kere Nyaa (Africa)

Home of a god. The mountain called Mount Kenya. This was the resting place of the god who made the first people. He created three sons: Kamba, Masai and Kikuyu. These were the founders of the three races by the same names.

Keremet (Russia)

Possibly a god of harvest. A powerful, mischievous god. His spouse is the Earthwife goddess Mukylcin.

Keres (Greek)

Also known as: *Cer, Ker.*

Death Spirits. The Keres were grim spirits who carried the dead to their fate. Often quoted in plural, they were said to be the daughters of Nyx and the sisters of Moros (doom), Momus, Hypnos, Dreams, Aether, Nemesis, Charon and Thanatos. They embodied the inevitability of death and are identified with the Fates (bringers of death). Their function and appearance is similar to the Erinyes although in general they lacked the retributive qualities of the Erinyes. *See also* Erinyes; Fates; Harpies.

Keresaspa (Zoroastrian; Persian)

Also known as: *Garshasp, Sama Keresaspa Naire-manah* (name in early times).

As he is a heroic warrior and not a god, Zoroastrians do not worship him. He is the son of Thrita and as Sama he became the grandfather of Rustam and, as Nariman, the great grandfather of Rustam. He captured Yima's Khvarenanh (glory) which gave him the strength to rid the earth of many demons. He killed Gandarewa (also known as Kundrav), the dragon of the cosmic ocean Vourukasha, as well as Srvara, Vareshava, Pitaona, Arezo-shamana, the sons of Nivika and of Dashtayani, the nine sons of Pathana, Snavidhka, the nine sons of Hitaspa and the murderer of his brother Urvakhshaya. When he originally died, Keresaspa's soul was not admitted to Garotman (heaven). It was thought that he lacked respect for fire and that he had little interest in religion. Khnathaiti, a witch whom he wed, was said to have robbed him of his spiritual interests. After lengthy petitioning by Zoroaster, the angels, and the animals, he gained entry. When the monster Azhi Dahaka breaks free from Mount Demavand at world's end, he will create demonic

www.ebook3000.com

havoc in the world. Keresaspa will be resurrected to kill the monster. With his magic club, he will also slay Angra Mainyu, who represents evil creation, and Druji who represents falsehood. Keresaspa will thus save the earth. He is depicted as a youthful warrior with sidelocks. *See also* Angra Mainyu; Gandarewa; Kamak; Srvara; Yima.

Keri and Kame (Bacairi People, South America) *see* Kame and Keri.

Keridwen *Ceridwen, Cerridwen, Kerridwen* (British, Celtic, Welsh)
An early British fertility goddess, Keridwen evolved into a goddess of poets and a goddess of inspiration and knowledge. A shape changer, her abode is in an underwater Elysium. She is the daughter of Ogyren, the mate of Tegid Voel, and the mother of three children. Her daughter Creirwy was a very beautiful child and her son Avagdu was extremely ugly. Keridwen developed a magic potion for her son that would ensure inspiration when drunk. She used six plants to develop the potion which was placed in Amen, the magic cauldron. The process took a year and a day. Gwion Bach was placed in charge of stirring the brew. One day, three drops splashed on his fingers. He sucked his fingers to stop the pain and was immediately possessed of all knowledge. He stole the cauldron and ran away. Keridwen pursued him. He changed into a hare to escape her. She changed into a greyhound. He then became a fish and she became an otter. He became a bird, and she became a hawk. Finally he became a kernel of corn. She became a hen and swallowed him. From the kernel of corn, she became pregnant. The child she gave birth to became Taliesin, the most famous of bards. Keridwen is the equivalent to Irish Bridget.

Kerimas (Tibet)
Also known as: *Keyuri.*
These goddesses, also known as the Eight Wrathful Ones, appear in human form in the Bardo World on the twelfth and thirteenth day. They haunt cemeteries and cremation grounds. Each one carries a different part of the human body. *See also* Htamenmas.

Kerkios (Greek) *see* Castor.

Kerlaug (Teutonic) *see* Kerlaung.

Kerlaung *Kerlaug, Kerlogar* (Norse; Teutonic)
Rivers of the dead crossed by the bridge Bifrost. Thor must swim or walk across these rivers as his weight would not be sustained by the bridge Bifrost. *See also* Bifrost; Thor.

Kerlogar (Teutonic) *see* Kerlaung.

Kerres (Roman) *see* Ceres.

Kerridwen (Celtic) *see* Keridwen.

Kerub (Roman, Semite) *see* Cherub.

Kerwan and Katcina Mana (Hopi People, North America)
Maize deities. The Sprouting Maize Spirits.

Kesare (India) *see* Kesari.

Kesari *Kesare* (India)
He is the monster husband of the monkey queen Angara. *See also* Hanuman.

Kesava (India)
"Having Fine Hair." Another name for Kasyapa (q.v.). *See also* Daksha; Kasyapa (A); Krishna; Vishnu.

Keshi (India) *see* Keshin.

Keshin *Keshi, Kesin* (India)
A horse-shaped demon. *See also* Karttikeya; Krishna.

Kesin (India) *see* Keshin.

Kesini (India)
She is the daughter of Vidharba, mother of Asamanjas and one of the spouses of Sagara (q.v.).

Kessiepeia (Greek) *see* Cassiopeia.

Ket (Celtic) *see* Ked.

Ketchimanetowa (Fox People, North America)
Supreme god. The Great Spirit.

Ketq Skwaye (Huron People, North America)
Also known as: *Grandmother Toad.*
She is a creator goddess.

Kettu *Kittu* (Babylonian)
Deity of justice and truth. He is the son of Shamash and brother of Misor (q.v.).

Ketuiti (Egypt) *see* Aai.

Keturah (Hebrew) *see* Abram.

Keuakepo (Hawaii, Polynesia)
God of fire. One of the volcano deities. He brings the night rain, or rain of fire.

Kewawkgu (Algonquin People, North America)
A tribe of powerful magicians. *See also* Gluskap.

Keyuri (Tibet) *see* Kerimas.

Kha (Egypt) *see* Ba.

Kha-a (Egypt)
Underworld deity. He is an archer in the tenth sector of Tuat.

Khadau and Mamaldi (Amur People, Siberia)
First mortal. They are the first humans, or parents of the first shamans. They are also masters of the underworld or creators. After Mamaldi created the continent of Asia she was killed by her husband. Khadau continued to create shamans, but his wife gave them souls.

Khadga Jogini *Khadja Jogina, Khadga Yogini* (Buddhist; Tibet)
Also known as: *Blue Tara, Kali, Ugra Tara, Vajrajogini, Vajra Tara.*
Khadga Jogini as the Blue Tara is the most important of the three fierce Manifestations of Tara (Blue, Yellow, Red). She is short and fat with round, red eyes. Her forked tongue protrudes through her teeth. She is draped in a tiger skin, wreathed with human skulls, has four to twenty-four arms and dances on human corpses. *See also* Agni; Kali; Tara.

Khadga Yogini (India) *see* Khadga Jogini.

Khadhomas (India) *see* Dakinis.

Khadja Jogina (Tibet) *see* Khadga Jogini.

Khadomas *Khahdoma* (Tibet)
The Khadomas, fairy-like female goddesses, are particularly helpful, when called upon, by followers of Yoga. One of the Khadomas is the goddess Yeshe-Khahdoma, who wears a tiara. *See also* Dakinis; Remati.

Khados (Tibet)
The chief of the Khados is Sangye Khado also known as Buddha Dakini. *See also* Dakinis.

Khahdoma (Tibet) *see* Khadomas.

Khaibit (Egypt)
Shadow of a man, similar to Ka and Ba. Able to move about freely when separated from the body. *See also* Ba; Ka.

Khaldi (Armenian, Iranian)
Also known as: *Bag-Mashtu* (possibly), *Bag-Mazda.*
Supreme God. Khaldi is an ancient supreme or moon deity of the Armenian Urartian population who called themselves Khaldians. This god was associated with a weather or storm god called Theispas and a sun-god called Artinis. All might have been derived from the Babylonian deities or conversely the Babylonians might have developed their triad of Sin, Shamas and Ramman from these gods. Some think Khaldi was identified with Bag-Mashtu (also known as Bag-Mazda) who was a sky god that later became the Iranian Ahura Mazda. *See also* Ahura Mazda; Artinis; Bag-Mashtu; Khaldi; Sin; Theispas.

Khalil (Arabic, Hebrew) *see* Abram.

Khalisah (Arabic) Goddess of Purity.

Khammurabi (Babylon) *see* Hammurabi; Marduk.

Khandro (India) *see* Sarasvati.

Khandros (India) *see* Dakinis.

Khang Fei (China) *see* Chang Fei.

Khar (Iranian) *see* Khara (A).

Khara (A) *Khar* (Iranian)
Khara is a gigiantic three-legged ass with two normally situated eyes, two eyes on the top of his head and two eyes on his hump. He has nine mouths, and one horn. He stands in the cosmic ocean Vourukasha and assists in world management. His sharp eyes enable him to overcome evil. *See also* Vourukasha.

Khara (B) (India) *see* Nikasha; Shurpanaka.

Kharchheri (Buddhist; Nepal)
Also known as: *Avalokitesvara, Six Syllabled Lokeswara.*
Kharchheri, the deity of wisdom and knowledge, is an aspect of Avalokitesvara known as the Six Syllabled Lokeswara. The six syllables are "OM MANI PADME HUM," which is constantly chanted by devotees. White in color, Kharchheri is four-armed and wears many ornaments. He carries the rosary in his right hand and a full blown lotus in the left. The other two hands are raised to his chest in the gesture of prayer holding the jewel, the symbol of knowledge. *See also* Avalokitesvara.

Khasa (India)
Possibly one of Daksha's sixty daughters and possibly the mother of the Rakshasas (q.v.).

Khatwanga (India) Shiva's Sacred Club. *See also* Shiva.

Khaya (India) *see* Chhaya.

Khebieso (Ewe People of Dahomey Group, Africa)
Also known as: *So*
God of lightning. *See also* Bo.

Kheiron (Greek) *see* Cheiron.

Khema (Hebrew) *see* Af (C).

Khemi (Egypt) *see* Assessors.

Khen-pa (Tibet)
Dressed in white garments, he has white hair and rides a white dog. Khen-pa controls the sky demons. *See also* Khon-ma.

Khenemu-Shu (Egypt) *see* Shu.

Khensu *Khonsu* (Egypt)
Also known as: *Aa, Chespisichis* (Greek), *Chons, Chunus, Khensu-Nefer-Hetep, Khensu-Pa-Khart, Khensu-Ra, Khons, Khons Hor, Khuns.*
An early moon god of healing and regeneration, Khensu is considered to be the divine child of Amen and Mut. His name means "traveler," and he crosses heaven as the moon-god. He was well known as a healer during the reign of Ptolemy IV. He may be a form of Amen and Ptah. He is represented as a young man in the form of a mummy with bound legs bearing the moon's disc and crescent on his head. He is also represented as wearing a crescent moon and disk surmounting a skullcap. In later periods he is shown standing on crocodiles. He is associated with Thoth (q.v.). *See also* Aa; Aah; Amen (B); Ptah; Thoth.

Khensu-Nefer-Hetep (Egypt) *see* Khensu.

Khensu-Pa-Khart (Egypt) *see* Khensu.

Khensu-Ra (Egypt) *see* Khensu.

Khenti-Amentet (Egypt) *see* Amentet; Osiris.

Khenti Amenti *Khentamenti, Khentamentiu* (Egypt)
Also known as: *Ophois, Up-uaut.*
Underworld deity. He is a wolf-god of Abydos with whom Osiris was sometimes identified in his capacity as Ruler of the Dead. The name, meaning "Ruler of the West," may have been given to Upuaut in connection with his worship as lord of the dead, especially at Abydos. He is described as jackal-headed. Khenti is sometimes identified with Ophios, Upuaut, and Osiris. *See also* Osiris; Up-uaut.

Khenti-Amenti (Egypt) *see* Aai.

Khenti-qerer (Egypt) *see* Aai.

Khentimentiu (Egypt)
God of destiny. The god who rules the destiny of the dead.

www.ebook3000.com

Khenty-Amentiu (Egypt) *see* Ap-uat.

Khenty-Khet (Egypt) *see* Horus.

Khepera (Egypt) *see* Khepri.

Kheperi (Egypt) *see* Aai; Khepri.

Khepi (Egypt) *see* Aai.

Kheprer (Egypt) *see* Aai.

Khepri *Chepera, Khepera, Kheprer, Kheperi, Khoprer* (Egypt)
Also known as: *Chafura.*
Creator. Khepri is one of the gods of the "Ennead." He was believed to have been born of Nunu. Khepri is identified with Ra as the morning sun, born again each day. He is often depicted with the face of a scarab, or with a scarab surmounting his head, a symbol, as was the sun, of creation and rebirth and everlasting life. He is one of the original creation gods and is said to be self-created, since he copulated with his own shadow. From his semen came Shu and Tefnut. In one version, Khepri is the creator of Nun. Harakhtes is also a winged beetle-god representing the morning sun. Khepri is usually shown as a human with the head of a scarab-beetle. The sun beetle was a popular amulet, a symbol of new life thought to give light and warmth. It was often placed in the tomb with the deceased. *See also* Ab; Ab-ta; Amen (B); Harakhtes; Khepera; Nun; Ptah; Shu; Tefnut.

Kher-Aha (Egypt) *see* Aaru.

Khert Neter (Egypt)
Also known as: *Tuat.*
Another title for Tuat, the underworld. *See also* Tuat.

Khesef-haa-heseq-neha-hra (Egypt)
Underworld. The name of the Seventh Hour of Tuat. This is the hidden abode of Osiris. The name of the city he passes through is called Tephet-shetat, and the names of the serpents and deities are Mehen, Neh-har, Ab-she, Serqet, Her-tesu-f; the goddesses: Temtith, Tenity, Nakity and Hetemitet. Also mentioned are Ankh-aru-tehefau, Ankhtith, Hekenth, Af-Tem and the crocodile, Ab-sha-am-Tuat. *See also* Tuat.

Khesfu (Egypt)
God who carries a spear in the Tenth Sector of Tuat.

Khetaka The sacred club of Bala-Rama (q.v.).

Kheti (Egypt)
A large serpent in the eight sector of Tuat, Kheti belches fire to punish those who have gone against the rites with Osiris. On his back stand seven gods. *See also* Osiris; Tuat.

Khetrpal (India) *see* Bhumiya.

Khi-Dimme-Azaga (Babylonia)
Mother goddess. She is possibly the daughter of Ea. Some say she is identical with Belit-Sheri. *See also* Ea.

Khnem-Renit (Egypt) *see* Ap-taui.

Khnemiu (Egypt)
The Khnemiu are four deities wearing red crowns, found in the Eleventh Sector of Tuat.

Khnemu (Egypt) *see* Khnum.

Khnoumis (Greek, Egypt) *see* Khnum.

Khnum (Egypt)
Also known as: *Amen-khum, Amun-kneph, Chnemu, Chnoumes, Chnoumis, Cnuphis, Ef, Khnemu, Khnoumis* (Greek), *Khnumu, Kneph, Knephis, Knepth, Kueph.*
Creator deity. At Elephantine, Khnum was called "Lord of Elephantine" and "the maker of heaven and earth and the underworld, and of water and of the mountains." He fashioned men out of clay on a potter's wheel and breathed life into them. As the "Father of Fathers" and the "Mother of Mothers," he assisted Heket, the birth goddess, at births. He was also regarded as protector of the source of the Nile. He had three consorts: Heket, Anukis and Satis. Khnum was part of a triad with Anukis and Satis. In another version his wives were Anqet and Satet and he was said to guard the waters coming from the lower world. Khnum could also be addressed as Neith (the goddess), thus acknowledging his feminine side. Khnemu represented the gods of the four elements: earth, air, fire, and water. He is depicted as a ram or with a ram's head (some say as a serpent's head). He has been represented with four heads. Khnum later merged with the god Min. *See also* Aani; Abu; Anubis; Heket; Min; Neith; Ptah; Satis.

Khnumu (Egypt) *see* Khnum.

Kho (Bushmen; Africa) *see* Kaang.

Kho-Dumo-Dumo (Basuto People, Africa)
Evil demon. He swallowed everything on earth but missed one woman. This woman had a son named Ditaolane who killed the demon and released all it ate. Ditaolane became chief and eventually allowed himself to be killed. At death his heart changed into a bird and flew away.

Khoda (Persia) Supreme spirit.

Kholumolumo (Bantu People, Africa)
Monster cannibal that eats everybody and everything.

Khon-ma (Tibet)
Also known as "*Old Mother.*"
She is in charge of the earth demons. Her face has eight wrinkles, she wears yellow robes, carries a golden noose, and rides on a ram. Her counterpart is Khen-pa (q.v.).

Khons (Egypt) *see* Aah; Khensu; Thoth.

Khons Hor (Egypt) *see* Khensu.

Khonsu (Egypt) *see* Khensu.

Khonus (Egypt) *see* Khensu.

Khonvum (Pygmy People, Africa)
Supreme deity. He is the supreme god, worshiped as a sky god, who controls celestial phenomena. He resurrects the sun each morning by throwing broken pieces of the stars at it. He carries a bow made of two serpents that become the rainbow.

Khoprer (Egypt) *see* Khepri.

Khordadh (Persia) *see* Ameratat; Haurvatat.

Khoromozitel (Slavic)
Also known as: *Domovik, Domovoi, Uboze.*
Domestic deities. This is possibly another name for the Domovoi (q.v.).

Khors (Slavic)
He is the god of health and hunting who is depicted in the form of a stallion. Khors is associated with Dazbog and Perun (qq.v.).

Khosadam (Siberia)
Evil deity. She is the wife of the high god Ec. After she was driven out of heaven for being unfaithful to Ec, she became a devourer of souls.

Khoser-et-Hasis (Ugarit)
Also known as: *Bn-Ym.*
He is the son of the sea. *See also* Bod-Baal.

Khoton (Yakut People, Siberia) *see* Khotun.

Khotun *Khoton* (Yakut People, Siberia)
Also known as: *Kubai-khotun.*
Khotun is the goddess of birth and nourisher of people. She lives in a lake of milk, although some say that she lives in the Zambu tree. The milk from her large breasts are the origin of the Milky Way. *See also* Ajysit.

Khou *Khu* (Egypt)
God of light. Khou is similar to the Ka or Ba which is the essence of the soul. Khou is depicted as a crested bird. *See also* Ka.

Khovaki (Tungus People, Siberia)
Also known as: *Savaki.*
Either creator god or spirits that protect shamans.

Khrestos (Greek) *see* Jesus.

Khristos (Greek) *see* Christ.

Khronos (Greek) *see* Cronus.

Khshasthra Vairya *Khashthra* (Zoroastrian; Persia)
Also known as: *Shahrevar, Shahriver* (Pahlavi dialect).
An Amesha Spentas, Khshasthra Vairya is a god of metal and protector of the poor and weak. He personifies Ahura Mazda's sovereignty and his triumph over evil on earth. His opponent is the arch-demon Sauru. In the court of heaven his associates are Mithra, Asman, and Aniran. He is associated with the stream of molten metal that will test all men at the end of the world. Through Ahura Mazda, Khshasthra allots the final rewards and punishments to the dead. His flower is the royal basil. *See also* Ahura Mazda; Amesha Spentas; Daevas; Sauru; Shahapet; Vohu Manah; Yazatas.

Khshathrapati (Persia) *see* Shahapet.

Khu (Egypt) *see* Ba; Bia; Khou.

Khudjana (Africa) *see* Ribimbi.

Khulater (Siberia) Ruler of the dead.

Khumbaba *Hubaba, Humbaba* (Akkadia, Babylon, Sumer)
Also known as: *Hum-ba, Humhum, Huwawa.*
Monster. Wicked demon. A monster and lord of the Mountain of Cedars (Lebanons), also known as the Cedar Forest of the Amanus. After Enkidu dreamed he was hurled into the underworld, Gilgamesh made offerings to the god Shamash, who told him to overcome Khumbaba, the giant of the cedar forest. The two friends made the long journey and succeeded in their task. Khumbaba is said to have had breath like a hurricane and a voice like a storm. A giant, he took the shape of a dragon who spits fire. One of the local deities of the Elamites was named Humba or Hubaba and was said to be an earth god. Connected to Tammuz. Ishtar, as the goddess Irnini, lived in the forest for a time. *See also* Gilgamesh; Ishtar.

Khumban (Sumer)
High god. Husband of Kiririsha. He is a god of Elam who corresponds to the Babylonian god Marduk.

Khun (China, Mongol)
A white dragon horse who is a protector against demons. *See also* Kun (B).

Khun-Lun (China) *see* Kun-Lun.

Khuno (Peru)
God of storm and snow. A certain group of Indians set fire to a forest in order to clear the land for crops. The smoke from the fire offended Khuno and he sent down terrible rain and hail, destroying their villages and some of the land. When it was over the people found a plant with bright green leaves which they put in their mouths to stay their hunger. This was the beginning of the use of the cacao plant.

Khuns (Egypt) *see* Khensu.

Khuran-Nojon (Buriat)
Rain god. He owns nine barrels of rain. When he opens one barrel it rains for three days.

Khurdad and Amardad (Persia) *see* Ameratat; Haurvatat.

Khurdadh (Persia) *see* Ameratat; Haurvatat.

Khuri Edzhin (Buriat)
God of music. Deity of musical instruments who teaches mortals the art of music.

Khusor (Semite) God of navigation and of incantations.

Khut (Egypt) *see* Isis.

Khuzwane (Lovedu People, Africa)
Creator. Little is known about Khuzwane, but he left his footprints on the rocks.

Khvarenanh *Hvaranah, Khwarenah* (Persia)
Often called "Glory" and literally meaning "light or luster," the Khvarenanh is the substance that makes gods and mortals powerful, and influences the planets. It is found in cosmic space, the sea, milk, or the reeds. *See also* Ba; Ka; Yima.

Khy (Bushmen, Africa) *see* Kaang.

Khyati (India) *see* Lakshmi.

Ki (Chaldea, Sumer)
Also known as: *Kishar* (the Earth).

www.ebook3000.com

when too much sexual energy is produced and there is no place to store it, it is wasted. We do not have enough of this energy to be able to waste it. We have a limited amount of energy and of time.

Some practices just deal with the spirit and ignore the body and the sexual energy. These practices can generate a lot of energy, but when one is not connected to the organs, it cannot be stored anywhere. One will end up draining oneself. Some people practice sitting quietly, emptying the mind, with the whole body relaxed and calm, but very little energy is actually generated. When one gets deep into the practice, some people find it hard to come back to society, because they have no energy and their mind power does not work well. These people have to depend on others to support them.

In the Universal Tao, we are learning to create a sacred and holy temple within ourselves. With the simple practice of smiling to all the organs, we can integrate our bodies, minds and spirits. They are no longer separate. The sexual practice connects the mind with the sexual organs and the brain. The separation between these parts of ourselves is bridged and a synergy is created.

The Taoist practice provides us with the resources to extend beyond the realm of our senses. By tapping into our internal resources and channeling the energy around us, we can perceive much more than the senses normally report to the mind. We want to extend our perception from the limited perspective of the sociologically conditioned senses to the unlimited awareness of the universe. For example, our senses tell us that the earth is flat, that we are stationary, and that heaven is above us. In reality, the earth is a sphere hurtling through space at thousands of miles per hour and the heavens are above, below and beyond the earth in every direction. The goal of the Three Tan Tiens is to connect with the forces from the six directions - above, below, left, right, front and back - and draw all these forces into the body. Eventually, with practice one can draw upon many different energies and use them as needed, thereby giving form to the formless energy that is abundant in nature.

Opening the Three Tan Tiens

Opening the Three Tan Tiens to the Six Directions is just another one of the many resources the Taoist practitioner uses to connect with the universe. The practice combines the power of the mind with the extension of Chi. This combination allows our personal consciousness to directly connect to the patterns and matrices of energy in the universe. When we put our thoughts into the web of the universe, we transform the electromagnetic energy into a force that is accessible to us. The combination of mind power and energy is what allows us to establish a relationship to these creative forces and the high sources of energy.

The earth, personified as the goddess Ki, is the daughter of Nammu and the mother of Enlil, and possibly the goddess Damkina. *See also* An; Damkina; Enlil; Kishar; Nammu; Ninhursag; Ninki; Ninmu (A).

Ki-gulla (Babylon) *see* Kulla.

Ki-No-Mata-No-Kami (Japan) *see* Kappa.

Kian (Celtic) *see* Cian.

Kianto (Maya) God of foreigners and diseases.

Kiara (Africa) *see* Mbamba.

Kibalso (Africa) *see* Kibuuka.

Kibu (Melanesian)
Kibu, the land of the dead, is an island located in the west.

Kibuka (India) Aryan war god.

Kibuuka *Kibuka* (Bantu, Buganda People, Africa)
Also known as: *Kibalso.*
Storm spirit. Founder of the Buganda. A spirit who some say was formerly a human king. One of the Balubaale, he is the brother of the great god Mukasa. Compare Kibuuka to the Yoruba deity Shango. *See also* Balubaale; Mukasa.

Kichigonai (Quiche People, Guatemala)
Deity of light. Creator of the day.

Kichijo-Ten (Japan)
Also known as: *Kashijotem.*
Goddess of good fortune. Goddess of beauty. She is sister of Bishamon and the rival of the jealous Benten. Kichijo-Ten is usually shown holding the sacred gem in her left hand. *See also* Benten; Bishamon.

Kicva (Celtic) *see* Pryderi.

Kiehtan (Massachusetts People, North America)
Supreme Being. *See also* Gitchi.

Kien Niu (China) *see* Chin Nu.

Kien t'an (China) *see* Chang.

Kigal *Ki Gal* (Akkadian) *see* Hell.

Kigatilik (Eskimo) A Fanged Demon.

Kihe-Wahine (Hawaii) Goddess of demons and lizards.

Kiho (Tuamotuan Archipelago; Polynesia)
Also known as: *Kiho Tumu.*
A supreme god, Kiho dwells beneath the foundations of Avaiki. Though he created all things, he does not have a mate. *See also* Atea; Avaiki; Io; Po; Rua.

Ki'i (Hawaii) *see* Tiki.

Kii (Polynesia) *see* Tiki.

Kikimora *Kikimoras* (Slavic)
Also known as: *Mora.*
Part of the Domovoi spirit group, this household deity is said to live in the cellar or in the ovens. She helps around the house, but she dislikes laziness and will break items and spoil food if the house isn't kept clean. She can also disturb sleeping people. Kikimora is ageless and is depicted with chicken's legs and a long nose. In some legends, she is the wife of Domovoi. *See also* Domovoi; Zduh.

Kiku-jido (Japan)
He is an eternal youth and god of the chrysanthemum. *See also* Sennins.

Kikuyu (Africa) *see* Gikuyu; Kere Nyaa.

Kildisin (Finnish, Slavic)
Goddess of birth. Wife of Ilmarinen. Daughter of the sorcerer Pohja. She is prayed to by those who desire children. *See also* Ilmarinen.

Kili (Teutonic) *see* Dwarfs.

Kilili (Assyria, Babylon)
Also known as: *Absusu, Abtagigi, Ishtar.*
Deity of Harlots. One of the Babylonian and Assyrian aspects of Ishtar as queen of the harlots. Her title means "One who Leans Out," or "Queen of the Windows." Some say she is an evil spirit. She is similar to the Sumerian Abtagigi and Absusu. *See also* Abtagigi; Ishtar.

Killer Whale (Northwest Coast Native North Americans) *see* Gunarh.

Kilyikhama (Brazil, Peru)
This is the name of a class of demons. One Kilyikhama is a boy who has lights on each side of his head. Another is called the "White Kilyikhama." He rides and whistles in his little boat in the swamps. One Kilyikhama is the most dangerous of all. He is described as being very tall and thin, with eyes that look like balls of fire. His very appearance signifies instant death. The Kilyikhama ride on the Milky Way in the form of white birds. They wait for the right moment to descend into the bodies of men. Another demon of this class is called Aphangak who are ghosts of men. Little is known of their characteristics although they are greatly feared. *See also* Demons.

Kimat (Tinguian People, Philippine Islands)
Kimat is the lightning personified as the dog of the creator Kadaklan (q.v.).

Kimbu-Sangtung (Dhammai People, India)
Kimbu-Sangtung is one of the children of the first mortals, the brother and sister, Abugupham-Bumo and Anoi-Diggan-Juje. *See also* Shuznaghu.

Kimpen Jigoku (Japan) *see* Jigoku.

Kimpurushas, The (India)
These spirits are followers and servers of Kuvera (q.v.).

Kinebahan (Maya) *see* Hunab-ku.

King Moho (Polynesia, Hawaii) *see* Kamohoali'i.

King Yama (India) *see* Yama; Yama Kings.

Kingmingoarkulluk (Eskimo)
This diminutive Eskimo is a benevolent land spirit who sings when approached by humans.

Kings of Hell (China) *see* Diamond Kings; Kshitigarbha.

Kings of Tara (Irish) *see* Banbha.

Kingu *Kingugu* (Babylon, Sumer)

Chief of monsters. Battle leader for Tiamat. One of the sons of Apsu, the primeval sea god of fresh water and Tiamat, the dragon personification of the salt sea. He is sometimes called husband-son of Tiamat. Tiamat made Kingu commander of the monsters she created to form an army that would free Apsu from the captivity imposed upon him by Ea. She endowed Kingu with the "Tablet of Destinies," which Marduk retrieved after overcoming him. In some versions, Marduk bound him in the underworld and took the tablets of fate, after which he burned Kingu and used his blood to create man. The "Tablet of Destinies" was said to be placed on Kingu's head or breast by Tiamat. When Marduk gained possession of the tablet, he placed it on his breast. The tablet may be an amulet. *See also* Apsu; Ea; Marduk; Tiamat.

Kinharigan (Dasun People, Borneo)

Creator. He and his wife, Munsumundok, killed one of their children and planted the pieces. From these came plants and animals to feed mankind.

Kinich Ahau (Maya People, Yucatan)

Also known as: *Kinish-Kakimo.*

Sun god. God of healing and medicine. Husband of the goddess of weaving, Ixazalvoh. His name means "the Lord of the Face of the Sun." Kinich Ahau may be the same as the Maya god "G" (q.v.). *See also* Itzamna; Ixazalvoh.

Kinilau (Polynesia) *see* Tinirau.

Kinish-Kakimo (Mexico) *see* Itzamna.

Kinkini-Dhari (Tibet)

Also known as: *Til-bu-ma* (Tibet).

This Shakti is the serpent-headed Door-Keeper of the North, along with her spouse, Amritahari, in the Bardo World. They are associated with stern justice. *See also* Ankusha; Cha-dog-ma; Shakti; Zhag-pa-ma.

Kinma (Babylon) *see* Marduk.

Kinnaras, The (India)

They are the horse-headed male musicians in Kuvera's heaven. *See also* Kuvera.

Kintu (Africa)

First man. Kintu was found by the sons of heaven (in some versions heaven is called Gulu) and their sister Nambi. He and Nambi became the ancestors of the human race. *See also* Gulu; Ngai.

Kipu-Tytto (Finnish)

Goddess of illness. Daughter of Tuonetar and Tuoni. She lives in Tounela (hell). *See also* Manala; Tounela.

Kiririsha (Sumer)

Queen of the gods. A goddess of Elam who is the wife of the high god Khumban.

Kirke (Greek) *see* Circe.

Kirnis (Slavic) God of ripening cherries. *See also* Lawkapatim.

Kiron (Greek) *see* Cheiron.

Kisani (Navaho People, North America) *see* Atse Estsan; Atse Hastin.

Kishar *Kissare* (Assyro-Babylonian)

Also known as: *Ki* (the Earth).

"Whole Earth." Mother goddess. She is the sister and wife of Anshar, by whom she was the mother of Anu and Ea. Her parents are Lahmu and Lahamu (according to others, Tiamat and Apsu). When associated with Nergal, Kishar is one of the watchmen of Ereshkigal. It is not known if this representation is male or female. The names Anshar and Kishar mean "host of heaven," and "host of earth." She is probably a winged dragon like her parents. Kishar is associated with Anshar as a pair of deities. She is similar to the Greek Lache and Lachos. *See also* Anu (B); Apsu; Ea; Igig; Kadi; Lahamu and Lahmu; Tiamat.

Kishibojin (Japan) *see* Kishimojin.

Kishijoten (Japan) *see* Bishamon.

Kishimogin (Japan) *see* Kishimojin.

Kishimojin *Kishimo-jin, Kishibojin* (originally from India, on to China and later Japan)

Also known as: *Hariti, Kariteimo.*

Demon goddess. Goddess of children. Kishimojin was a demon goddess who devoured children in the town of Rajagriba while Buddha Sakyamuni lived there. He promised her that if she maintained her peaceful aspect, he would insure that the villagers would leave offerings for her. The once evil demon became a protector of children and women in childbirth. She is shown seated, surrounded by children, or standing and holding a baby. Sometimes she holds the Flower of Happiness in her hand. *See also* Hariti; Sakyamuni; Sitala.

Kisimbi (Congo, Africa) *see* Nymphs.

Kisin (Maya) *see* Nohochacyum.

Kissare (A) (Assyro-Babylonia) *see* Kishar.

Kissare (B) (Babylonian Creation Legend of Damascisu) *see* Anu (C); Belus (B).

Kistna (India) *see* Krishna.

Kitchaka (India) *see* Bhima (A).

Kitchi Manito (Native North American) *see* Kitshi Manito.

Kitcki Manitou (Algonquian and Sioux People, North America) *see* Kitshi Manito.

Kitimil and Magigi (Pelew Islands)

First people. Only known as the survivors of the deluge.

Kitshi Manito *Gitchee Manitou, Gitchy Monedo, Kitcki Manitou* (Algonquian, Chippewa, Oglala, Sioux People, North America)

Also known as: *Gitche, Tanka, Wakan, Wakonda.*

Supreme beneficial spirit. He is opposed by Mitshi-Manitou (Mudje-Monedo), a bad spirit. *See also* Gitche; Tirawa; Wakonda.

www.ebook3000.com

Kittu (Sumer) The personification of justice. *See also* Kettu.

Kiun (Hebrew) *see* Chiun; Rephaim.

Kivutar (Finnish)
Goddess of disease. Daughter of the Tuoni and Queen of the Underworld, Tuonetar. Sister of Loviatar, Kipu-Tytto, Kivutar, and Vammater. They live in the underworld known as Manala (q.v.). *See also* Tuonetar; Tuoni.

Kiyamat-Saus (Finnish) *see* Kiyamat-Tora.

Kiyamat-Tora (Finnish)
Also known as: *Tamek-Vui, Touni.*
He is a prince or judge of the dead who is assisted by Kiyamat-saus.

Kkhrafstras (Persia)
Evil spirit. This creature, who is linked with decay and corpses, lives on dead matter.

Kla (Ashanti People, Africa)
Also known as: *Sisa.*
Goddess of goodness. Her counterpart, the male Kla, is the essence of evil. The Kla survives death and is then called Sisa. The name is both male and female.

Klehanoai (Navaho People, North America)
Also known as: *Bekotshidi.*
Moon carrier. He is the husband of Yolkai Estsan. He lives in the east. *See also* Ahsonnutli; Yolkai Estsan.

Klotho (Greek) *see* Clotho.

Knaritja (Aborigine People, Australia)
Great Father or Eternal Youth. His skin is "reddish," and he is emu-footed. His wives have dog feet.

Kneph (Egypt) *see* Khnum.

Knosu (Egypt) *see* Aah.

Ko-Dama (Japan) *see* Kay-no-hime-no-kami.

Ko-no-hana-sakuya-hime (Japan) *see* Kaya-no-hime-no-kami.

Kobine (Oceanic) *see* Nareau.

Kobolds (Teutonic)
Originally, Kobold was a dwarf miner in Teutonic myth. Later, Kobolds were known in German myth as benevolent earth spirits who usually haunt houses. Compare Kobolds to Kaches.

Kodoku-Jigoku (Japan) *see* Jigoku.

Koevasi (Melanesian)
Creator. She is a snake goddess who is the ancestor of all the people of Florida Island in the Solomons. Similar to Kafisi (q.v.).

Kohin (Australia) *see* Baiame.

Koin (Australia) *see* Baiame.

Kojiki, The (Japan) *see* Ama-no-minaka-nushi.

Kojin *Kojin-Sama* (Japan)
This androgynous kitchen deity always keeps the kitchen stocked with food.

Kokko (Zuni People, North America)
Spirits. The Kokko, a group of deities led by Koloowisi, appeared in human form. *See also* Palulukon.

Kokuzo-Bosatsu *Kokuzo* (Buddhist; Japan)
Also known as: *Akasagarbha.*
The deity Kokuzo-Bosatsu possesses the virtues of wisdom and compassion; indestructible, without beginning and without end. He is shown seated on a lotus which in turn is placed on a lion. In his hands, he carries a lance and a jewel.

Kokytus (Greek) *see* Cocytus.

Koloowisi (Hopi, Zuni People, North America)
Also known as: *Palulukon* (Hopi).
He is the chief of a group of rain and lightning spirits called Kokko by the Zuni. *See also* Palulukon.

Kolpia (Phoenician)
He is the wind who is the spouse of Baau and father of Aion and Protogonos in the "Creation Legend of Philo Byblos." Baau may be the same as the Babylonian goddess Ba'u. Aion (meaning "life") and Protogonos were the first to discover edible fruits. They became the parents of Genos and Genea, the first to worship the sun. Genos and Genea were the parents of Light, Fire and Flame. *See also* Air (A) for the Phoenician Creation Myth of Damascisu; Fire.

Kombu (Bantu People, Africa) Either a spirit or a creator god.

Komoku (Japan) *see* Komoku-ten.

Komoku-ten *Komoku* (Buddhist; Japan)
Also known as: *Virupaksha* (India)
Komoku-ten ("Wide-gazing") is one of the four Shi Tenno guardian kings. In some renditions he is the guardian of the west and in others the south. He is shown holding a lance or brush in his hand and in his other hand he holds the sheath of his sword, or his hand is on his hip. *See also* Bishamon-Ten; Jikoku-Ten; Nio; Shi Tenno; Virupaksha; Zocho-Ten.

Komorkis (Blackfoot People, North America)
The moon goddess. *See also* Apisirahts.

Kompira (India) *see* Kuvera.

Kompira-Daigongen (India) *see* Kuvera.

Kon (A) (Teutonic) *see* Heimdall.

Kon (B) (Chimu People, South America) *see* Irma.

Kondoy (Mixe People, Mexico) *see* Chalucas.

Kongara-Doji (Japan) *see* Fudo-Myoo.

Kongo-Yasha-Myoo (Buddhist) Japan
Also known as: *Vajra-Yaksha* (Sanskrit).
Guardian. A Godai-Myoo. Kongo-Yasha-Myoo is one the Five Great Kings, known as the Godai-Myoo. They are incarnations and manifestations of the five great Buddhas and the protectors of Buddhism. Kongo-Yasha-Myoo is the wrathful incarnation of Fuku who is also known as Amoghasiddhi and Amoghavajra in Sanskrit. Kongo-Yasha-Myoo is depicted with three heads, bristling hair and six arms. He stands on two lotus blossoms with his left leg raised and is surrounded by flames.

His front head has five eyes. He is the only deity with this distinguishing feature. In his lowest right hand, he holds an arrow. In the right hand near his breast, he holds the vajra (thunderbolt) and in his uplifted third hand, a sword. In his left hands he holds a wheel, bow and bell. He is also shown with one head and four arms. *See also* Amoghasiddhi; Dai Itoku-Myoo; Fudo-Myoo; Godai-Myoo; Gozanze-Myoo; Gundari-Myoo; Shi Tenno.

Kongorikishi (India) *see* Vajrapani.

Konjo (China) *see* Tara (B).

Konkara (Japan) *see* Fudo-Myoo.

Kono-Hana-Sakuya-Hime (Japan) *see* Hikohohodemi; Hoderi; Hosuseri; Ninigi; Sengen; Toyo-Tama-Bime.

Konohana-Chiru-Hime (Japan) *see* Kushi-nada-hime.

Koo-chul-inn (Celtic) *see* Cuchulain.

Koodjidnuk (Eskimo)

Spirit of healing. A good spirit who came from creation as a large bird with a hooked beak, a black head, and a white body.

Koppa-Tengu (Buddhist; Japan)

The Koppa-Tengu, goblins who have mouths like beaks and bodies with small wings, are the inferiors of the Tengu (q.v.).

Kooshelta (India) *see* Rama.

Kooshelya (India) *see* Rama.

Kootamoinen (Finnish) Another name for Kun, the moon.

Koran *Qur'an* (Islamic)

The sacred text of Islam, known as the *Koran*, is divided into 114 chapters, or suras. Revered as the word of God, the *Koran* is said to have been dictated to Muhammad by the archangel Gabriel. The *Koran* is accepted as the foundation of Islamic law, religion, culture, and politics. *See also* Muhammad.

Kore (Greek)

Kore is an epithet of Persephone. *See also* Demeter; Persephone.

Kore-Te-Whiwhia (Polynesia) *see* Io (B).

Korka-kuzo (Finno-Ugric) *see* Domovoi; Dvorovoi.

Korka-murt (Finno-Ugric) *see* Domovoi; Dvorovoi.

Korobona (Arawak People; Carib)

A great female warrior and culture heroine, Korobona is said to have been seduced by a water demon. In the Carib Creation Legend, the first Carib was born as a result of their union. *See also* Mama Nono.

Korraval (Tamil People, India)

Korraval, the goddess of victory, is the wife of Silappadikaram, the name used for Bala-Rama by the Tamil People. *See also* Silappadikaram.

Korred (Celtic) Fairies. *See also* Korriganes.

Korriganes (Celtic)

Fairies. It is generally said that there are nine Korriganes. They are shape changers who are spirits of the wind. They can cause death with their breath, but can also cure diseases and heal wounds. The Korriganes are less than two feet high and have long hair. They usually wear a white veil.

Korubantes (Greek) *see* Corybantes.

Korybantes (Greek) *see* Corybantes.

Koshchei (Slavic)

Immortal evil snake. This serpent carries off princesses and the mother or wife of the hero. He is killed by a magic death-egg thrown or broken by the hero.

Koshi (Japan)

An eight-headed dragon. *See also* Kushi-nada-hime; Susanow.

Koshin (Japan)

Also known as: *Koshin-Sama.*

Road deities. Monkey gods. In some versions, Koshin is a god of the roads. In others this is the collective name of the three monkeys who portray see, speak, and hear no evil. The individual names are Mizaru, Kikazaru, and Iwazaru.

Kotan-Shorai (Japan) *see* Buto (B); Susanowo.

Kotari (India) *see* Devi.

Kothar and Khasis *Kathar, Kathar the Clever, Kathar-Wa-Hasis, Kothar-u-Khasis* (Ugarit)

They are two gods of architects, artisans, and weapon makers. Sometimes they are referred to as one deity, Kothar-u-Khasis. The magic weapons "Yagrush" (Chaser) and "Aymur" (Driver) were made by Kothar-u-Khasis, as was Baal's abode. Once while attending a feast at the home of King Danel, the king noticed Kothar's bow and arrows. King Danel persuaded him to give them to him. He in turn gave them to his son, Aqhat. When the goddess Anath saw the weapons, she coveted them. She offered Aqhat a large amount of gold and silver, but he would not part with his prized possessions. He even refused the gift of immortality from her. Anath devised a plan and sought and obtained permission from the great god El to implement it. She changed the minor deity Yatpan into a vulture and asked him to fly over Aqhat while he was eating, knock him over, and fly off with the bow and arrows. Unfortunately, Yatpan killed Aqhat and carried off the bow which subsequently was lost. Anath mourned Aqhat's death which had caused famine to fall over the earth. She promised to return him to life if he would give her the bow and arrows, so that she could return once again make the earth fertile. Aqhat's sister, Paghat (sometimes called Pughat), and her father the king attempted many measures to restore fertility, to no avail. The famine lasted for seven years. When they heard the news of Aqhat's death, Danel vowed vengence. His prayers to Baal were answered and he was permitted to examine all the vultures to see which one killed his son. Paghat had designed her own plan. Unbeknown to her, she employed her brother's murderer, Yatpan to help her find the killer. During this period, Danel found the remains of his son in the stomach of the mother of the vultures, Sumul. After cursing three cities in the area where his beloved son died, he returned home and mourned for seven years. Compare Kothar to Hephaistos (Greek). *See also* Anath; Baal; El; Yam-Nahar.

www.ebook3000.com

Kothar-u-Khasis (Ugarit) *see* Khasis; Kothar.

Koti (Creek People, North America)
Animal spirit. A water-frog, a helpful spirit.

Koto-Shiro-Nushi (Japan)
Okuni-Nushino-Mikoto, who is one of the Shichi Fukujin (seven gods of happiness), could be the father of Koto-Shiro-Nushi. *See also* Okuni-Nushino-Mikoto; Take-Minakata.

Kotoshironushi-No-Mikoto (Japan) *see* Ebisu.

Kottavei (India)
A goddess of war, Kottavei feeds on carnage. *See also* Kali.

Kottos (Greek) *see* Cottus; Hecatoncheires.

Kou-Hun-Shih-Che (China) *see* Wu-Ch'ang.

Kouretes (Greek) *Korubantes* (Crete) *see* Curetes; Telchines.

Kouros (Greek) *see* Curetes.

Kourotrophos (Greek) *see* Karpophoros.

Kox (Aztec) *see* Coxcoxtli.

Kozoba (Baziba People, Africa)
God of the sun and moon. He is the son of the father of the gods, Wamara, and the father of Hangi. *See also* Wamara.

Krakuchanda (India) *see* Manushi-Buddhas.

Kratos (Greek)
"Power." He is the son of the Titan, Pallas and the Oceanid, Styx. His siblings are Bia ("Force"), Nike ("Victory") and Zelos ("Zeal"). *See also* Nike; Pallas; Styx.

Kravyad (India) "Flesh Eater." *See also* Agni.

Kresnik (Slavic) *see* Krsnik.

Kricco (Slavic)
God of fruits of the fields. *See also* Lawkapatim.

Krimen (Tupi-Guarani People, Brazil) *see* Hermitten.

Krimhild (Teutonic) *see* Gudrun.

Kripa (India)
He is the husband of Drona and the father of Ashvatthaman. *See also* Duryodhana.

Krishna *Kistna, Kristna, Krsna* (Hindu, Vaishnava; India)
Also known as: *Acyuta* (Immovable), *Arisudana* (Slayer of Enemies), *Gopel* (The Cowherd), *Gopinath* (The Lord of Cowherds), *Govind, Govinda* (Herdsman or Giver of Enlightenment), *Hrsikesa* (Lord of the Senses), *Janardana* (Liberator of Men), *Juggernaut* (Lord of the World), *Kesava* (Having Fine Hair), *Madhava* (Husband of Laksmi), *Madhusudana* (Slayer of Madhu), *Mathuranath* (Lord of Muttra), *Vasudeva, Yadava* (Descendent of Yadu).

Krishna, the eighth avatar of Vishnu, is known as a god of vegetation, love, and erotic delight. Vishnu assumed the form of Krishna to overcome Kansa, the tyrannical king of Mathura. The *Mahabharata*, the main source for Krishna's legend, records that Vishnu plucked two hairs from his head, one white and one black. The strands were placed in the wombs of Rohini, and Devaki. Rohini bore Balarama from the white hair and Devaki gave birth to Krishna from the black hair. According to the *Purana*, the sage Narada told Devaki's uncle Kansa that her son would kill him. Kansa then put Devaki's six children to death. Balarama, the seventh was transferred to the womb of Rohini, the second wife of Vasudeva, and she subsequently gave birth to Krishna. He was born in Vrindavana, a wood in Vraja. Krishna was exchanged for the newborn daughter of the cowherd Nanda. In time Kansa discovered the truth and on numerous occasions tried to kill Krishna. As a child, Krishna was spontaneous and impetuous, a little rascal. He loved sweets and butter and would steal them whenever he could. Obedient when near his mother, once out of her sight, he was constantly getting into mischief. During his youthful period, his playfulness continued. He loved sports and flirting with the cowgirls (*gopis*). Kansa, his evil uncle, continued to send his retinue of monstrous demons to kill Krishna. Putana, the demon daughter of the demon king Bali, arrived disguised as a beautiful woman. She attempted to suckle Krishna with her poison-filled breasts. Krishna sucked the life from her. Sakta-Sura flew in and tried to crush Krishna but was crushed by him. Trinavarta, the "Whirlwind," blew in and swept up the young god. Krishna increased his weight and held on to his neck until he was so heavy that the exhausted demon fell to the ground and shattered. Other demons followed: Vatsasura, the female demon in the shape of a cow; Bakasura disguised as a raven (or some say a giant crane); Aghasura, the younger brother of Putana; and Batasura, in the form of a huge snake. All were killed by the young god. Dhenuka appeared in the form of a giant ass, and was killed by Bala-Rama. The demon bull-fiend Arishta (also called Arista) was so powerful that his movement shook the earth. He attempted to crush Krishna, but ended up being choked to death. Krishna had a major battle with the many-headed serpent Kaliya. The serpent had been polluting the waters, stealing the cows, and preventing the women from fetching water. Kansa had the monster in a position of defeat but when Kaliya's fish-tailed wives begged the god to spare him, he consented on the condition that he remain in the sea and he was warned that he would be destroyed by the serpent-eagle Garuda, if he ever appeared on land. Indra, overcome by jealousy of the popular god, tried to destroy mortals by sending floods. To protect the cowherds and the cattle, Krishna held Govardhana mountain for seven days with his little finger. In time, Indra's anger turned to admiration for the strong, determined young god, who had become a friend and the charioteer for his son, Arjuna. Krishna's action-filled adventures were far from over. He killed Kansa's father-in-law Jarasandha and brother Sunaman. He carried off the daughter of the king of the Gandharvas, conquered Saubha, the city of the Daityas, and overcame Varuna. He killed Panchajana and confiscated his conch shell, stole the magic Parijata tree from Swarga, Indra's heaven, and planted it in his celestial home Dvarka (meaning "City of Gates"). He took Agni's fiery discus (chakra) and with Arjuna's help, he burned the Khandava forest. Krishna's travails were not over. Next came the demon Keshin in the shape of a horse. Krishna thrust his fist down the beast's throat and caused him to explode. Kuvalayapida, the demon, appeared in the shape of an elephant. Other demons harassed him, notably Shankha-Sura and Kalayavana. Krishna's consort during this period was

Radha, an incarnation of the goddess Lakshmi, who was the faithful wife of Vishnu. During the battle between the Pandavas and the Kauravas, Krishna fought with Arjuna and his army fought on the other side with Duryodhana because Krishna was related to both sides. Rukmini, who was Krishna's wife, and also an avatar of Lakshmi, had a son who was an avatar of Kama the god of love. They named him Pradyumna. The demon Sambara abducted the child and he was raised by Sambara's spouse or housekeeper, Mayadevi. When Pradyumna grew older, his son, Aniruddha, was abducted by the Usha, a Daitya. Krishna arrived on the scene with Pradyumna and Bala-Rama. They engaged in a ferocious battle with Usha's father Bana and his troops of Daityas. Krishna and company emerged the victors and his grandson was rescued. Krishna also killed Kansa and then went to the lower regions to retrieve his six brothers, killed before his birth. The hunter Jaras mistook Krishna for a deer and accidentally shot him in his only vulnerable spot, his heel. Krishna's jewelled abode of Dvarka disappeared under water seven days after he died. Pradyumna was killed during a brawl in Dvarka and Bala-Rama died under a tree. During his lifetime, the irresistible Krishna married Kalindi and Madri, the daughters of the sun god Surya; Jambavati, the daughter of Jambavan, king of the bears; and Satyabhama, the daughter of Satrajit. His wrathful wife was Bhama. The *Purana* gives Krishna 16,100 wives and 180,000 sons. Krishna's companion was Yudhishthira, the eldest of the five Pandavas. In the Vedic tradition, Krishna gave the *Bhagavad Gita* to Arjuna to encourage him on the battlefield in his fight for truth. Krishna's period marks the end of the Vedic era. Krishna is generally shown with black skin, symbolizing wisdom and eternity and sometimes with four arms, possibly denoting the four directions. He is also shown in slate-blue color, often wrestling with a serpent or playing his flute, which is known as "Call-of-the-Infinite." The sound of his music is irresistible to all who hear it. He is traditionally shown clothed in a jewelled sari with a high conical crown. His consort Radha is red or pink in color. During the first full moon of spring, Phalguna (February-March), a celebration known popularly as the Holi festival celebrates Krishna's life as a cowherd. Colored water and powders are offered to Krishna and Radha. The Rasa and the Hallisa dances celebrate Krishna's life. Krishna-Janmashtami is the celebration of Krishna's birthday. He was born at midnight on the eighth day of the dark fortnight of Bhadrapada (August-September). A twenty-four hour fast is observed. Temples are decorated in his honor, bells are rung and conches blown. Another ceremony, Jhulanayatra, known as the Ceremony of Swinging the Lord Krishna, is held during the eleventh to the fifteenth days of the bright fortnight of Sravana (July-August). Krishna killed the serpent Kaliya by dancing on his head and trampling him to death, symbolizing the triumph of good over evil. Krishna's weight is the weight of the earth. His mantra is "*Om Namo Bhagavate Vasudevaya.*" His numerous wives represent the stars. Pradyumna represents love and Aniruddha, egotism. The hunter Jaras represents cold or old age. The demoness Putana is depicted as about fifteen feet tall. Krishna is associated with the tamala tree. It has dark bark and dark leaves and is an object of veneration by Vaishnava devotees. For Kansa's background *see* Drumalika. Compare Krishna's vulnerability to the vulnerability of Achilles. Compare Krishna to Heracles and Osiris. *See also* Aditi; Arjuna; Bala-Rama; Bali; Bana; Bhima (A); Daityas; Devaki; Devi; Drumalika; Duryodhana; Gopis; Jambavan; Juggernaut; Kama (A); Kansa; Lakshmi; Pandavas; Parijata; Parikshit; Pradyumna; Radha; Sankhasura; Satyabhama; Sisupala; Soma; Subhadra; Swarga; Syamantaka; Vishnu; Visvakarma; Yadavas.

Krishna Dwaipayana (India) *see* Vyasa.

Kristna (India) *see* Krishna.

Krita (Hindu; India)
Also known as: *Kritayuga.*

Part of the cycle of Kalpa, Krita is the golden age which lasts 1,728,000 years. Virtue is 100 percent, and Dharma, god of justice and duty, walks on four legs and is colored white. *See also* Dwaparayuga; Kalpa.

Kritanta (India) The god of death. *See also* Yama.

Kritayuga (India) *see* Krita.

Krittika Sisters *Kirteka* (India) *see* Karttikeya; Rishi; Vasistha.

Krittikas (India) *see* Vasistha.

Krittivasas (India) "Clad in Hide." *See also* Kali.

K'ro-bo-mi-gyo-ba (Tibet; Japan) *see* Acala.

Krodha (India)

Her name means "anger." She is the daughter of Daksha, the spouse of Kasyapa, and the mother of all four-footed predators and birds of prey. *See also* Bhutas; Daksha; Kasyapa; Shiva.

Kronos (Greek) *see* Cronus.

Krotishaurima, Buddha (Tibet) *see* Heruka.

Krsanu (India) "The Archer." *See also* Soma.

Krsna (India) *see* Krishna.

Krsnik *Karsnik, Kresnik* (Slavic)

Protector deity. A benevolent god, he protects the family from werewolves and vampires. He battles Vlkodlak, the werewolf.

Krukis (Slavic)
Also known as: *Kaukas* (Lithuanian), *Pukys.*

Household spirits. The Krukis along with Peseias are protectors of domestic animals. The Krukis were also the patrons of blacksmiths. They are part of the Domovoi group (q.v.).

Kruth, The (Cambodia) *see* Garuda (India).

Ksama (India) *see* Lakshmi.

Kshiti-Apsarases (India) *see* Apsarases.

Kshiti-garbha (Central Asia) *see* Kshitigarbha.

Kshitigarbha *Ksitgarbha, Kshiti-garbha* (India; Buddhist; Central Asia)
Also known as: *Jizo* (Japan), *Ti-Tsang* (China), *Ti-Tsang Wang-P'u-sa* (China).

Kshitigarbha was not known in Indian Buddhism and Lamaism. Throughout Central Asia (beginning in China), he was a an old god of the earth representing fertility and growth, a Bodhisattva, and a patron of travelers. He regulates the six

www.ebook3000.com

paths *(gati)* taken by the souls of mortals, deities, animals, demons, and asuras after being judged by the ten Kings of Hell. In paintings by Yueyen-Kwang, the ten kings are depicted clustered around Kshitigarbha. Kshitigarbha's head is shaved and sometimes he wears a wreath or a traveler's shawl. In his right hand he carries a ringed stick known as a *Khakkara,* and in his left hand, a pearl known as *Cintamani,* the wish-granting gem. The Cintamani is also the emblem of Mahakala, Ratnapani, Ratnasambhava, and Samantabhadra. He is related to the air god, Akasagarbha. Kshitigarbha is similar to the chief of the Yama Kings (q.v.), and the same as Jizo Bosatsu of Japan (q.v.). *See also* Akshobhya; Chu-kiang; Dhyanibodhisattvas; Pien-ch'eng; Ratnapani; Ratnasambhava; Samantabhadra; Sung Ti; Ti-Tsang; Wu Kuan; Yama Kings; Yen-lo.

Ksitigarbha (Central Asia) *see* Kshitigarbha.

Ktesios (Greek) Zeus as the guardian of property.

Ku and Hina (Hawaii)
Ku, the first male creative force, and Hina, the first female creative force, are invoked as inclusive of the total ancestral line, past, present and future. Ku presides over all male deities and Hina presides over all female deities. Ku as Master of the Universe is called Ku-Kau-Akahi (Ku Standing Alone). Many of the early gods were given Ku names. A few examples: Ku as god of the forest would be Ku-moku-hali'i (Ku spreading over the land), Ku-olono-wao (Ku of the deep forest). Ku as god of war would be Ku-nui-akea (Ku the supreme one), Ku-kaili-moku (Ku snatcher of land). Ku is a god of war and a sorcery god. *See also* Hi'iaka; Hika-po-loa; Hina; Kane; Ku-ka-ohia-laka; Ku-mauna; Lono.

K'u-ch'u K'iao (China)
Also known as: *Bridge of Pain.*
Underworld bridge. Once the soul is given the Broth of Oblivion by Lady Meng (Meng-p'o) they must cross this bridge where they are confronted by two demons. *See also* Meng (A); Ti-yu.

Ku Gods (Hawaii) *see* Ku and Hina.

Ku-ka-ohia-laka (Hawaii)
God of the hula dance. God of canoe builders. He is the husband of Hina-ula-ohia (q.v.). In the temples he is depicted as a feather god and worshipped with Kanaloa, Kane, Ku-nui-akea and Lono. *See also* Hiiaka; Laka (A).

Ku-Kali-Moku *Kukalikimoku* (Hawaii, Polynesia)
God of war. God of sorcery. He is the most famous of the Ku gods. His cries are heard over the deafening sounds of battle. Ku-Kali-Moku was also the most famous god of sorcery, until the advent of Ka-lei-pahoa, the sorcery god of Molokai. Ku-Kali-Moku is shown with a head of blood-red bird feathers. Upon his head, he wears a Roman-type helmet. *See also* Ku and Hina; Uli.

Ku-Kau-Akahi (Hawaii)
Ku, the first male creative force, is called Ku-Kau-Akahi ("Ku Standing Alone"), as the Master of the Universe. *See also* Ku and Hina; Ku Gods.

Ku-mauna (Hawaii)
Ku of the Mountain. He is one of the forest gods who was banished by the goddess of fire Pele, for refusing to destroy prince Lohiau when she asked him to do so. He was overcome in her fire and died. Later, he was worshipped as a local rain god.

Ku-ula-kai (Hawaii)
God of abundance in the sea. He is one of the gods of fishers, and some say the chief of all the gods of the sea. He built the first fishpond. At death, he bequeathed the objects he used to control the fish to his son Aiai. He also taught him how to address the gods and how to set up fish altars. The four objects were Pahiaku-kahuoi, a decoy stick, Leho-ula, a cowry, Manai-a-ka-lani, a hook and a stone called Kuula. When dropped into the pond this stone drew fish. Many myths involve Ku-ula-kai and his son Aiai. *See also* Ku and Hina.

Ku-waha-ilo (Hawaii)
One of the conductors of the souls of dead chiefs. *See also* Lo-lupe.

Kua Tsi-i (China) God of happiness. *See also* Fu-Shen.

Kuai (Arawak People, Amazon, Brazil)
Hero and fertility spirit. Very little is said of this deity except he was considered to be the one who introduced the mask dances. He still dances in the sky-world. Kuai is possibly related to the Katchinas of the Zuni and Pueblo Indians.

Kuan Jung (China) *see* Kuan-Ti.

Kuan-Ti (China)
Also known as: *Kuan Jung, Kuan Yu.*
A war hero who became a personal god of war, Kuan-Ti had been a loyal and faithful general and scholar named Chang-sheng, Shou-chang or Yun-chang (Yen Ch'ang). He was raised to the status of a god after his death. As a patron of the people, he protected them by preventing rather than making war. Kuan-Ti predicts the future for his followers. He sometimes plays the part of a judge who is called upon to punish those who do evil to others. In this case he sends his attendant, Shou-t'sang, to give out the punishment. Kuan-Ti is said to have a son named Kuan P'ing. In some versions he is also a god of literature. As Kuan or Kuan Yu he was associated with Liu Pei and Chang Fei, all were warriors and according to some were from eight to nine feet tall. He is said to have been one of three generals of the Han dynasty who swore brotherhood. He is depicted with a red face and green clothing. Sometimes he is shown as a giant nine feet high with a beard two feet long. He is usually carrying weapons and is sometimes on horseback. His festival day is May 13. His name is similar to the Buddhist goddess of mercy, Kuan Yin. *See also* Hsuan-T'ien Shang Ti.

Kuan-yin (China) *see* Kuan Yin.

Kuan Yin *Kuan-yin, Kwan-yin* (China)
Also known as: *Avalokitesvara* (India), *Juichimen, Kannon* (Japan), *Kwan-she-yin, Kwannon, Nyo-i-rin Kwan-on* (Male), *Po-i Ta-shi, Sung-tzu-niang-niang.*

She is the goddess of mercy and fecundity, protector of women, bringer of rain, and savior of sailors. Her titles are The All Merciful, Bodatsu, Bodhisattva, Buddha, The Divine Voice of the Soul, Goddess of Fertility, Goddess of Mercy and Knowledge, Great Bodhisattva, The Melodious Voice, The Merciful Mother, The Mother, Of the Hundred Hands, The Prostitute, The Saviouress, The Triple, Wife and Daughter. Some say that she was originally an Indian Bodhisattva known as Avalokitesvara, or, some say, the Buddhist god of mercy, Juichimen. She was clearly masculine and portrayed with a fine line mustache. She parallels the goddess Vach (India). She was also said to have eleven heads and was called Sung-Tzu-Naing-Naing. Kuan Yin is possibly a form of Kunti or Parvati. In some legends, she is a goddess of prostitutes, also called public girls. Kuan Yin is generally clad in a white dress and holding a lotus flower, or, seated on a lotus and carrying a child. Her different aspects are shown in different dress and with two, four, six, and as many as a thousand arms. Some think she is a form or aspect of Tara (B) (q.v.). *See also* Avalokitesvara; Hariti; Nijuhachi-bushu; P'an Chin-Lien; Parvati, Ti-Sang.

Kuan Yu (China) *see* Kuan-Ti.

Kuang Mu (China) *see* Mo-li Hung.

Kubaba (Kish)
Deified mortal. Mother of Puzur-Sin, first king of the Fourth Dynasty of Kish. The goddess herself, a former barmaid, reigned as queen of the Third Dynasty for 100 years.

Kubebe (Greek) *see* Dionysus.

Kubele (Greek) *see* Cybele.

Kubera (India) *see* Kuvera.

Kubira (India) *see* Kuvera.

Kudai (Siberia) A Sky God. *See also* Ameshas Spenta.

Kudai Bai-ulgon (Altaic, Tartars) *see* Bai Ulgan.

Kudai-Baksy (Siberia) *see* K'daai Maqsin.

K'uei-Hsing *K'uei-Sing, Kuei-Sing* (China)
The god of examinations. He fulfills an important function as assistant to the god of literature, Wen Ch'ang (Wen-ti). Although very ugly, he is well liked, since it was he who selects the successful examination candidate. He is usually depicted standing on a turtle. When turned down by the emperor because of his appearance, K'uei-Hsing attempted to drown himself. The turtle Ao rescued him. He carries a bushel basket to measure the talents of the candidates presented to Tung Wang Kung (also known as Yu-ti), the Jade Emperor. The bushel basket represents his function as a god of the constellation Big Dipper. The Chinese call the Big Dipper "Bushel." K'uei-Hsing is associated with Wen Ch'ang.

Kuei-Hui (China)
Kuei-Hui is a bottomless pit in the Eastern Sea into which all the waters of this world and of the Han flow. Mortals call the Han the Milky Way. The Five Islands of the Immortals once floated in the Kuei-Hui but a giant sank two of them. The other three islands are lost. *See also* Milky Way.

Kueph (Egypt) *see* Khnum.

Kuetzal-Koatl (Mexico) *see* Quetzalcoatl.

Kuhu (India)
She is the moon goddess daughter of Angiras and possibly the sister of Agni.

Kui (Maori) This blind storm goddess eats human flesh.

Kujaku-Myoo (Japan)
Also known as: *Mahamayuri.*
Protector from calamity. An aspect of a Bodhisattva. Kujaku-Myoo is one of the more gentle myoo who dwells in the Tushita heaven. Shown seated on an eight-petalled lotus, usually with four arms, holding a flower, fruit and a peacock feather, Kujaku-Myoo has a white body and wears white transparent garments.

Kujum-Chantu (Thompson People, Pacific Northwest, North America)
The Earth. Creator deity. She is seen as the whole earth. The first humans lived on her fat belly. Because she worried about the humans falling off she died of her own accord and the valley of her chest became the area where the Apa-Tanis live. Her eyes became the sun and moon and from her mouth came Kujum-Popi, who directed the sun and moon to shine. *See also* Kujum-Popi.

Kujum-Popi (Thompson People, Pacific Northwest, North America)
Born from the mouth of Kujum-Chantu (earth), this deity created or sent the sun and moon into the sky. *See also* Kujum-Chantu.

Kukalikimoku (Hawaii, Polynesia) *see* Ku-Kali-Moku.

Kuko-no-shi (Japan) *see* O-Wata-Tsu-Mi.

Kuksu (Maidu, Pomo People, North America)
In the Maidu legends, Kuksu, a culture hero, is the first man. The Pomos call him the elder brother of the creator god Marumda. *See also* Marumba; Ragno.

Kuku-no-shi *Ku-ku-no-shi* (Shinto, Japan)
Also known as: *Kukunochi-no-kami* (possibly).
God of mountains. God of the boles of trees. One of the children of Izanami and Izanazi. Kuku-no-shi is the brother of Oho-wata-tsu-mi, Shima-Tsu-Hiko, and Oho-yama-tsu-mi. In some traditions, the food goddess Toyo-uke-hime-no-himi separated herself into the god Kuku-no-shi and the goddess of grasses and herbs, Kaya-no-hime-no-kami. *See also* Ha-mori; Izanami and Izanagi; Kaya-no-hime-no-kami; Toyo-uke-hime-no-himi.

Kukulcan *Cuculcan* (Maya People, Yucatan)
Also known as: *Cezalcouati, Gucumatz, Quetzalcoatl.*
Patron of artisans. Inventor. An early serpent god, Kukulcan is the Mayan form of the Mexican god, Quetzalcoatl. It is said that he instituted a system of laws, and numerous inventions, among them the calendar. His place of worship was the city of Quirigua. *See also* Gucumatz; Quetzalcoatl.

Kul (Finnish)
Also known as: *Kul-Uasa, Vasa, Vodyanoi, Vodyanoy.*

www.ebook3000.com

Nymphs. The Kul are selfish water sprites who dislike sharing their fish with mortals. They also inflict sickness on mortals. *See also* Vodyanoi.

Kulla (Babylon)
God of temples. Anu or Ea created this god to restore temples.

Kulmu (Etruscan)
God of tombs. He is shown with shears and torches.

Kumara (India) *see* Karttikeya.

Kumarbis *Kumbari* (Hurrian)
Kumarbis, a sky god and weather god, became the father of the gods by castrating and swallowing his father's testicles. (Anus, his father, had achieved his position by ousting his father Alalus from the throne.) Anus told Kumarbis that he had swallowed three mighty gods: the river god Aranzahas, Tashmishu, who may have been a rain god, and a god whose name cannot be deciphered from ancient tablets, but who is thought to be a storm god. Kumarbis spit them out on Mount Kanzuras. Kumarbis plotted to create a rival storm god. He fathered the god Ullikummis after having union with a rock three miles long, according to some myths. Others say that how the birth came about is unclear. Ullikummis grew to monstrous proportions and assisted his father in his struggle against the storm, thunder, and rain god Teshub, who was also the son of Kumarbis, and his brother Tashmishu. Eventually, Kumarbis was deposed by Teshub. *See also* Alalus; Anu (B); Anus; Teshub; Ullikummis.

Kumari (Hindu, India)
Also known as: *Devi, Kali, Kanya-Kumari* (Daughter-virgin).

Kumari, meaning "the maiden," is a virgin goddess worshiped by virginal, young women. She is called the "Living Goddess." Kumari is an aspect of Devi and Kali (qq.v.).

Kumbari (Hittite, Hurrian) *see* Kumarbis.

Kumbhakara *Kumbhakarna* (India)
Kumbhakara is a giant monster who sleeps for six months and wakes up for a day. Nikasha is thought by some to be the mother of Kumbhakara; Ravana; Khara; Vibhishana, a good natured demon; and a daughter, Shurpanaka, who is a giant she-demon. *See also* Kuvera; Nikasha; Ravana; Shurpanaka; Vishravas.

Kumbhakarna (India) *see* Kumbhakara.

Kumbhandas (India) *see* Dhartarastra.

Kummiya (Hittite, Hurrite)
He is the storm god who battled Ullikummis (q.v.).

Kumudavati (India) *see* Kumunda.

Kumund (India) Elephant guard. *See also* Lokapalas.

Kumunda (India) *see* Dikpalas; Nagas and Nagis; Rama.

Kumush (Modoc People, North America)
A creator god. After the world was destroyed, he returned to the land of the dead with his daughter, who was also dead. Kumush wearied of dancing with spirits at night who became skeletons by day, and taking a basket of bones, he returned to earth and created a new race of people. He is described as being a beautiful blue color.

Kun (A) (Peru) God of the Desert.

Kun (B) *Khun* (China, Mongol)
The Sovereign God turned to Kun for help following a devastating, lasting flood. In very remote times the world was flooded. Kun worked nine years in an attempt to dam the water. He was not successful. The price he paid for his labors was high. Either Yao or Shun, his successor, executed Kun. They ordered his son Yu to carry on with his father's work. Yu stole soil that had magical properties from the Lord. The soil known as the "swelling mold" kept swelling in size. He hoped it would hold the water back. It did not. The Lord, enraged with Yu for stealing the "swelling mold," had him executed in a dark place without sun in the north, known as Feather Mountain. Yu's body lay for three years without decomposing. Eventually someone came along and sliced his stomach open. His son Yu emerged. Later Yu had a son named Ch'i (q.v.). Kun is possibly the same as Khun of the Mongols, a white dragon horse that was a protector against demons. Kun is associated with Fu-hsi. There are many legends based on Kun's experiences. In some of them, Kun is successful in his attempts to close the dam, and is rewarded with the throne. Often, it is said that Kun was born from a stone that had been split open, and he turned into a bear.

Kun (C) (Finnish)
Also known as: *Kootamoinen.*
A god who is the moon.

K'un-Lun (China) *see* Kun-Lun.

Kun-Lun Mountain *K'un-Lun, Khun-Lun* (China)
Also known as: *Ching-Tu.*

The Lord of the Sky's capital on Earth. The mountain abode of the celestial lords. The Queen Mother, Hsi Wang Mu, cultivates and keeps the Peaches of Immortality on Kun-Lun Mountain. She acts as a hostess when the feasts of immortality are given for the gods. Her husband Tung-wang-kung and the other immortals also live on Kun-Lun Mountain. Kun-Lun is located in the extreme west, extending to the heights of the sky and depths of the earth. It is the dwelling place on earth of the Lord of the Sky, Tung Wang Kung. In later mythology, it took on the features and quality of a heavenly paradise. Kun-Lun is probably the same as Jodo of the Japanese people. *See also* Feng-tu; Hsi Wang Mu; Nu Kua; Tiyu; Yama Kings.

Kun-Rig (India) *see* Vairocana.

Kunapipi (Australia) *see* Waramurungundja.

Kunapipi-Kalwadi-Kadjara (Australia) *see* Ngaljod; Rainbow Snake; Waramurungundja.

Kund (Teutonic) *see* Heimdall.

Kundalini (India)
Also known as: *Bhujangi* (Serpent).

She is the Supreme Power in the body, located at the base of the spinal column, in the area called the lowest chakra or bodily center. She has the form of a coiled and sleeping serpent and is often represented coiled around a lingam (the phallus as a mystical object).

Kundrav (Persian) *see* Gandarewa.

Kung Kung (China)
A dragon or horned monster who struck down the pillars of the firmament with his head, causing tremendous earthquakes and the resulting great Deluge when the vault of heaven collapsed and fell.

Kuni-no Sa-tsuchi No Mikoto (Japan) *see* Ama-no-minaka-nushi.

Kuni-toko-tachi-no-mikoto (Japan) *see* Ama-no-minaka-nushi.

Kuni-Tsu-Kami (Shinto; Japan)
Earthly deities. Kuni-Tsu-Kami is the name given to earth deities. These deities lived on the islands of Japan. They could go to Ama (heaven) and the gods of heaven, known as Ama-tsu-kami could also move to earth. The Ama in heaven could only find out what was happening on earth if a messenger came to the celestial realm with news. These deities could see into the future without the use of divination. For the Shinto creation myth, *see* Ama-no-minaka-nushi. *See also* Kami.

Kunmanggur (Australia) *see* Rainbow Snake.

Kunti *Pritha* (Hindu; India)
Queen Kunti, also known as Pritha, is the daughter of a nymph and King Sura of Mathura. She is the sister of Vasudeva and the wife of Pandu. When she was very young, the sage Durvasas granted her the opportunity to bed with five gods. She chose four and permitted Madri, Pandu's other wife, to choose the fifth deity for herself. As a result of Kunti's activities, she became the virgin mother of a son Karna by the sun god Surya and three of the Pandavas: Yudhisthira, by Dharma; Bhima, by Vayu; and Arjuna, by Indra. Karna was born in full armor. Kunti, worried about the wrath of the community, hid the child in the river Aswa. He was cared for by a series of foster river-goddesses, including Yami and Ganga, who saw that he was discovered. Nandana, the charioteer to the blind King Dhritarashtra, raised him. When Indra saw his shining armor, he traded it for a spear that never missed. It was Karna who first fell in love with and was rejected by the beautiful goddess Draupadi because of his lowly station in life. A spirited woman, she was the daughter of the king of the Panchalas. Later, she was won as a prize by Arjuna at an archery contest. At Kunti's insistence, she became the shared wife of the Pandavas. In some versions, it was Karna who won Draupadi and then was rejected by her. Angered, Karna joined the enemies of the Pandavas, the Kauravas, and fought against his half-brothers. He killed Ghatotkacha but later was killed by Arjuna. After his death, the Pandavas discovered that Karna was their brother. Indra invited Kunti and her family to reside in his celestial city, Swarga. *See also* Bhima (A); Dharma; Gandhari; Indra; Karna; Kauravas; Krishna; Pandavas; Prithivi; Radha; Surya; Swarga; Vishnu; Yudhisthira.

Kuntu-bzang-mo (Tibet) *Samanta-Bhadra* (India)
Divine Mother and Shakti, she is the mate of Samantabhadra (q.v.). *See also* Shakti.

Kuo Shang (China)
One of the nine heroes. Kuo Shang appears as thick, dark clouds.

Kupala (Slavic)
Water deity. Goddess of joy. Primarily a goddess of water, Kupala was also worshiped in fire rites. She is involved in magic and healing herbs. Kupala is shown as a straw figure dressed in a woman's gown and adorned with ribbons and jewelry. Sometimes she has wooden arms. Similar in nature to Yarilo (q.v.).

Kupua *Kapua* (Hawaii; Polynesia)
Trickster spirits. Demi-gods. Shape-changers. The Kupua are born in non-human form, either as an egg or a plant, although there are exceptions. Someone, often a maternal grandparent, recognizes the Kupua's divinity and raises him. He is gifted, intelligent, and has a huge appetite. In Kupua stories, we are often told that the kupua has been offered the daughters of the chief as gifts. Then the kupua is sent off to overcome a dangerous hellion who is petrifying the land. Kupuas are known under various names. Kawelo is a spear-thrower and fisher; Iwa is a master thief; Ono is a fisher who was born as an egg; Kana, born in the shape of a rope, was brought up by his grandmother, Uli. Maui is classed as a kupua. *See also* Kamapua'a; Kana; Ku; Kupua-Huluena; Mafuike; Uli.

Kupua-Huluena (Hawaii)
He is a well known kupua who is credited for bringing vegetable foods to the islands. *See also* Kanea; Kaneapua; Kaulu; Kupua.

Kur (Sumerian)
Underworld deity. He is a monster who throws stones. He is the villain who is depicted as the empty place between the sea and the earth's crust. In some legends, he carries Inanna to the underworld. He is associated with Inanna and possibly with Ninurta.

Kura-Mitsu-Ha (Japan)
"Dark Water Snake." Kura-Mitsu-Ha and his brothers, Kura-yama-tsumi and Kuru-okami, were born from the blood of their brother, the fire god Kagutsuchi, when he was killed by their father, Izanagi. *See also* Izanagi and Izanami; Kagutsuchi; Kura-Okami; Taki-tsu-hiko.

Kura-Okami (Shinto) Japan
Rain and snow god. Weather deity. In the *Nihongi* (*Chronicles of Japan*), Kura-Okami was created from the blood of the upper part of a sacred sword belonging to Izanagi when he killed his son, the fire god Kagu-tsuchi. Two other deities born at the same time are Kura-yama-tsumi (Lord of the Dark Mountains) and Kura-mitsu-ha (Dark-water-snake). In another section of this document, the deity Taka-Okami (Dragon-god-residing-on-the-mountains) was born from the pieces of the Kagu-tsuchi's body. In the *Kojiki*, Kura-Okami, Kura-yama-tsumi and Kura-mitsu-ha were created from the blood that leaked between Izanagi's fingers when he killed Kagu-tsuchi. Kura-Okami (Dragon god of the valleys) is said to be a snake or dragon god who controls the rain and snow. Kura-Okami is shown as a dragon or serpent. For the Shinto creation myth and information about the *Kojiki* and the *Nihongi*; *see* Ama-no-minaka-nushi. *See also* Izanagi and Izanami; Taka-okami; Taki-tsu-hiko.

www.ebook3000.com

Three Tan Tiens

Once we make the connection with the forces of energy in the universe, we then want to be able to store this energy in the body. Energy is like money, if you are making a million dollars a year and spend a million dollars, you have nothing left to use in the future. That is the way we live and use our energy in our society. We are spending more energy than we are saving and we are living on borrowed energy, paying very high interest. Our credit will run out very soon.

In the Tao practice, we store energy in the Three Tan Tiens. The Three Tan Tiens are the reservoirs of energy within us.



Fig. 3.1 *The* ***Upper Tan Tien*** *is in the brain (the* ***Crystal Room****, third ventricle), and when it is full of energy, the capacity of the brain increases. We store our spiritual intelligence, the mind here. All the Tan Tiens have both yin and yang within them. In nature, the yin and yang are present in all things. Day (yang) turns into the sunset, which turns to night (yin). It is very important to feel the qualities of yin within yang and yang with yin (sunrise/sunset). One quality does not exist without the other. They are inseparable qualities of the same force.*



Fig. 3.2 *The* ***Heart*** *Center Tan Tien, between the two nipples, is the* ***Middle Tan Tien****. It is associated with the fire element. Yet, within fire there is always water. The original spirit (Shen) is stored here.*



Fig. 3.3 *The lower abdomen at the* ***Navel*** *is like an empty universe, or ocean. We want to feel a universe of energy in the* ***Lower Tan Tien****. Within this universe or ocean, there is a fire, like a volcano under the ocean; 'fire under water'.*

The Three Tan Tiens refer to the three reservoirs of energy within the body. These reservoirs are places where we can store, transform and collect energy. The reservoirs are the source of energy that flows through the body. The meridians are rivers of energy fed by these reservoirs. The goal of Opening the Three Tan Tiens is to continually fill and replenish the energy of the Three Tan Tiens. When we are connected to the Tao, life ceases to be a struggle. Through the observation of nature, the Taoists learned to flow with the stream of energy and connect to forces in the universe.

In these practices, we use a variety of hand movements and body postures to open to the energy around us. We draw the energy from the six directions into the body, activate the three fires, open the Three Tan Tiens and circulate this energy in the Microcosmic Orbit.

Kura-Yama-Tsumi (Japan)
"Lord of the Dark Mountains." *See also* Izanagi and Izanami; Kura-okami; Taki-tsu-hiko.

Kuramitsuha-no-kami (Japan) *see* Izanami.

Kurangara (Aborigine People, Australia)
Spirits. The Kurangara have long flexible limbs forked on the ends. They are usually depicted with a long muzzle, and exaggerated genitals.

Kuretes (Greek) *see* Curetes.

Kurke (Prussia; Slavic)
Also known as: *Curche.*
Deity of agriculture. Also the name of a weevil. A cult prayed to Kurke to control this weevil.

Kurma (Brahmanic, Hindu; India)
Kurma the tortoise is the second avatar of Vishnu. When the gods were losing their strength after a Rishi laid a curse on Indra, Vishnu took charge. He instructed the Daevas to join with the Asuras to churn the sea of milk, using Mount Mandara as the churning stick, and Vasuki king of the snakes and Seshu the endless serpent as the churning rope. The endeavor took a thousand years. The reason for this action was to bring to the surface all solid objects including the miraculous cup containing soma which had been lost during the Great Deluge. Soma, the beverage of immortality would revitalize the deities. Vasuki consented to assist only if he would be given a share of soma. The rapid motion and the weight of the churn threatened the sea and the earth below. Only Vishnu, assuming the form of Kurma the giant tortoise could save them. He dove to the bottom of the ocean to serve as a base for Mount Mandara. The efforts of the gods on one side of the churn and the demons on the other, at last, brought forth from the churning the treasures of the Vedic tribes lost in the Deluge. During these efforts, Vasuki vomited up halahala, a poison also called Visha, which emitted toxic fumes that could have killed everything, including the gods and demons. Shiva, who was watching over the project, caught the poison and swallowed it. The only ill-effect he suffered was a scalded gullet, which left a bluish trace, the result of his mate strangling him to save him. This incident gave him the surname Nilakantha (blue-throat). When Dhanvantari, the physician of the gods, rose from the sea, he held the cup of soma in his hands. After Vishnu retrieved it from the asuras, the gods were restored to their former vitality and sovereign authority. In the *Satapatha Brahmana*, Kurma is an avatar of Prajapati. Some records indicate that many of Prajapati's exploits were tranferred to Vishnu. Numerous treasures were churned from the sea. Soma, mentioned above, was the first item; the divine physician was next, followed by the goddess of beauty, Lakshmi; Sura, the goddess of wine; Chandra, the moon; Rambha, the beautiful Asparas nymph; Uchchaihsravas, the moon-colored horse; Vishnu's jewel, the Kaustubha; the magic tree, Parijata; Kamadhenu, the miraculous cow; Airavata, Indra's milk-white elephant; Shankha, a large shell, and the warrior who could blow it; Dhanus, the bow that always struck its target; Visha, a substance that could be healing or poisonous; the god Dhanvantari, who is said by some to hold a cup of sparkling soma in his hand; and Varuni, queen of Varuna and goddess of spiritous liquor. The number of items retrieved varies from fourteen to thousands, as does the sequence of the item retrieved. Some of the treasures caused battles between demons and gods and others saved countries. *See also* Amrita; Apsarases; Asuras; Chandra; Daevas; Indra; Kamadhenu; Lakshmi; Matsya; Parijata; Prajapati; Rambha; Savarbhanu; Sesha; Shiva; Soma; Surabhi; Varaha; Vasuki; Vishnu.

Kuru (India)
Kuru is the common ancestor of the Kauravas and their cousins the Pandavas. *See also* Kauravas; Pandavas; Tapati.

Kuruksetra, Battle of (India) *see* Kali; Pandavas.

Kurukshetra (Hindu; India)
The sacred battlefield where the *Mahabharata* war was fought.

Kurukulla (Buddhist; East Asian)
Also known as: *Red Tara.*
Goddess of wealth. She is reddish in color and has four arms. The upper two arms are in a threatening position and the lower arms in a soothing position. *See also* Jambhala; Kuvera; Tara (B).

Kururumany (Arawak People, South America)
Creator. Kururumany is the husband of Kulimina. He created males and she created females. He returned to earth one day to check on his creation and found the people corrupt. As punishment he deprived them of immortality and left various serpents, lizards and vermin behind to make their life uncomfortable. In other legends, Kururumany has two wives. One wife is Emisiwaddo, who is possibly connected with ants, and the other wife is Wurekaddo, who is only known as one who works in the dark. There is mention of a higher god than Kururumany named Aluberi or Amalivaca, but little is known about these deities other than they may be tricksters. *See also* Makonaima; Purrunaminari.

Kurwaichin (Polish, Slavic)
Deity of animals. His primary duty is to watch over the lambs, while Kremara takes care of pigs. He is similar to Makosh, who took care of small domestic animals; to Walgino, who took care of cattle; and Zosim, who was in charge of bees. Another god who takes care of pigs is Priparchis.

Kusanagi (Japan)
Also known as: *Ame-no-murokumo-no-tsurugi* (Sword-of-black-clouded-heavens), *Herb-Quelling.*
Deified object. The Kusanagi is the remarkable sword Susanowo drew from the tail of an eight-headed serpent he slaughtered after his arrival in Izumo province. He gave the sword to his sister Amaterasu, who gave it to her grandson, Ninigi, when she sent him to reign on earth. She also gave him the other two treasures, the jewel and the mirror. The Kusanagi is known as the famous Herb-Quelling and is one of the three symbols of imperial sovereignty. The name Herb-Quelling originated from the period when the sword was in the possession of the warrior Yamato-Takeru. When he was ambushed, he was able to cut down burning bushes with the weapon. The divine sword is the symbol of courage. Compare Kusanagi to the sword Ame-no-wo-ha-bari. The Kusanagi is comparable to the

Arthurian Excalibur, the magic sword of King Arthur. For details about the Excalibur, *see* Vivian. *See also* Ame-no-wo-ha-bari for additional sword symbolism. For details of the three sacred treasures, *see* Amaterasu; Kushi-nada-hime; Ninigi; Susanowo.

Kusha (India)
Kusha is the son of Rama and Sita, the twin brother of Lava, the spouse of Kumudavati, and the father of Kushamba. *See also* Kumunda; Rama; Sita.

Kushi-nada-hime *Kushinada-Hime* (Wondrous Inada Princess); (Shinto; Japan)
Also known as: *Ina-Gami Furu-Kushi-Nada-Hime* (True-hair-touching-princess), *Inagami-Hime.*
Rice goddess. Kushi-nada-hime is the youngest of eight daughters. Her parents are Asi-na-duti, an earthly deity, and Tenazuchi-no-kami (Hand-Stroking-Elder). Every year an eight-headed snake from the Koshi district would slither into Izumo and feast upon one of the young women. When Susanowo, the son of Izanagi, arrived in the area, the parents of Kushi-nada-hime told him of their travails. Kushi-nada-hime was their only daughter alive, and the snake was due for his annual visit. Susanowo had a solution. He changed the young woman into a comb and stuck it into his hair. He filled eight bowls with saki and waited. Koshi, the snake, arrived and was bewitched by the aroma wafting up from the bowls. Each head lapped up the rice wine and the inebriated snake fell off to sleep. Susanowo, ready to take advantage of the situation, chopped the greedy villain into pieces. To his delight, he found a remarkable sword in the middle of the snake's tail. He presented the weapon to his sister, the sun goddess Amaterasu. It later became known as Kusanagi. Susanowo, ready to settle down, married Kushi-nada-hime. He built her a wedding palace and composed what is known as the oldest Japanese poem. They became the parents of Okuni-Nushino-Mikoto, who became Lord of Izumo. The *Kojiki* lists six generations of the descendants of Kushi-nada-hime. The female deities, their fathers, husbands and children are Konohana-chiru-hime (Blossoms-of-the-Trees Falling-Princess). Her father was Opo-yama-tu-mi-no-kami. She married Ya-sima-zinumi-no-kami and was the mother of a son, Pupa-no-modi-kunusunu-no-kami. Hikawa-hime, daughter of the wife of Okami-no-kami, married Pupa-no-modi-kunusunu-no-kami and had a son, Puka-buti-no-midu-yare-pana-no-kami. Amenotsudoe-chine-no-kami married Puka-buti-no-midu-yare-pana-no-kami and became the parents of a son, Omidu-nu-no-kami. Futemimi-no-kami, the daughter of Punoduno-no-kami, married Omidu-nu-no-kami and became the mother of a son, Ame-no-puya-kinu-no-kami. Sashikuni-waka-hime, the daughter of Sasi-kuni-opo-no-kami, married Ame-no-puya-kinu-no-kami and became the mother of Okuninushi (Okuni-Nushino-Mikoto) and eighty other sons. The snake and sword are frequently a part of the myths of Susanowo. In early Japan, the thunder god was a snake. The comb could signify male dominance or masculinity. For details about the sword, *see* Kusanagi; for details about the hero's life and the sacred treasures, *see* Susanowo; for his early life, *see* Izanagi; for his relationship with his sister, *see* Amaterasu. For information about the Shinto creation myth, the *Kojiki*, and the *Nihongi*, *see* Ama-no-minaka-nushi. *See also* Izanagi and Izanami; Okuni-Nushino-Mikoto.

Kushinada-hime (Japan) *see* Kushi-nada-hime.

Kusor (Phoenician)
God of the seasons. God of divination. God of mechanical devices. Inventor. God of sailors (possibly). Kusor and his brother, Hasisu, were involved in the construction of windows in the temple of Baal. The god Aleyn did not want windows, so they installed a skylight instead. Kusor was in charge of letting rain fall on earth through the skylight. As god of mechanical devices, he invented the fishing boat, fishing hook, fishing lines, navigation and iron-working. Kusor and Hasisu are sometimes known as one god, Kusor-Hasisu. He is identified with the Greek Hephaistos.

Kusug (Assyro-Babylonia) *see* Ea.

Kuu (Finnish)
Kuu is the name for the moon. Her daughter was named Kuutar.

Kuula (Hawaii, Polynesia)
God of the sea. God of fishing. His counterpart is Aiaiakuula, the goddess of fishers. *See also* Kaneapua.

Kuvalayapida (India) A demon. *See also* Krishna.

Kuvanna (India) A Yakshini. *See also* Yaksha.

Kuvera *Kubera, Kubira* (Hindu, Brahmanic, Buddhist, Vedic; India)
Also known as: *Dhana-Pati* (Lord of Wealth), *Dhanada* (Giving Wealth), *Kompira* (Tibet), *Kompira-Daigongen* (Tibet), *Namu-tho-se-ser-chhen* (Tibet), *Namu-Zozusen, Nara-Raja* (King of Men), *Ratna-Garbha* (Jewel-Belly), *rNam-t'os-sras-gsir-ch'en* (Tibet), *Takshaka, Vaisravana.*
Kuvera, known as the chief of evil beings during the Vedic period was elevated to the position of god of wealth and lord of treasures of the earth by the Hindus. He is the hideous dwarf son of Visravas and Idavida (Ida), and is considered by some to be an aspect of Shiva. He inherited Sri Lanka from his father but was ousted by his evil half-brother Ravana. Kuvera owns the earth's gold, silver and jewels. Pushpaka, the flying chariot was a gift to Kuvera from Brahma. This magic vehicle, devised by the divine architect Visvakarma, could contain a whole city. Kuvera moved into the palace of Lanka, also built by Visvakarma for the Rakshasas. They had deserted it when they were expecting an attack by Vishnu. Later, when the situation had settled, they decided they wanted their city of wealth back. The daughter of one of their leaders was sent to seduce Kuvera's father. From that union, the demon Ravana and two sons were born, the monster Kumbhakarna and Vibhishana, the good-natured demon. Kuverva was driven from his home along with the Gandharvas, Rakshasa, Kimpurushas and Yakshas. They settled in Alaka, the wealthiest city in the universe, located in the Himalayas. In other interpretations, his home was in a superb palace in Kailasa or on Mount Meru. On Mount Mandara, he maintains a beautiful garden known as Chaitraratha. Kuvera is chief of the Yakshas and Guhyakas and the ruler of the North; the location of the mineral rich mountains. His attendants are known as the Kinnaras and his chief attendant is Manibhadra (also known as Manivara). Kuvera's mates are Yakshi, Charvi or Kauveri, a Danava, the daughter of Mura, and Rambha, who

www.ebook3000.com

was also sexually involved with Ravana. He has three sons and a daughter, Minakshi (also called Minakshidevi), the "fish-eyed goddess." Minakshi and her husband Sundara are thought by some to be incarnations of Parvati and Shiva. Minakshi and Minakshidevi are sometimes included as a name for the mother goddess Devi. He is also said to have mated with Hariti, who gave birth to five hundred demons. Kuvera is usually accompanied by two fiends, Yaksha and Yakshi. White in color, he is shown as a fat dwarf with three legs, eight teeth and one eye. He is also seen as a pot-bellied, ugly, black, heavily jewelled man, sitting cross-legged and holding a purse. In some depictions, he is golden-yellow, astride a white lion with a green mane, holding the banner of victory in his right hand and the mongoose under his left arm. His daughter Minakshi is described as having lustrous eyes and a beauty that subdued all earthly and heavenly beings. She had three breasts, but when she met Shiva, one of her breasts disappeared. Kuvera is a fertility deity, god of wealth, tutelary household spirit, protector of sailors and god of the dead. He has a jar of honey that revitalizes the elderly, restores sight to the blind and ensures immortality to all tasters. His non-tantric symbol is the caitya (*see* Stupa). The Kinnaras are musicians as well as Kuvera's attendants. They have human bodies and horses' heads and are said to have been born at the same time as the Yakshas. For Kumbhakarna and Vibhishana, *see* Ravana. Kuvera is associated with the goddess of wealth Kurukulla. (*See also* Panchika, god of the purse.) *See also* Abheda; Brahma; Devi; Dikpalas; Gandharvas; Hariti; Ida (B); Jambhala; Lokapalas; Maitreya; Mandara Mountains; Parvati; Rakshasas; Rama; Rambha; Ravana; Shiva; Takshaka; Virudhaka; Visvakarma; Yaksha and Yakshini.

Kvasir *Kvaser* (Teutonic)
A wise giant, Kvasir was killed by the dwarfs Fjalar and Galar. His blood, when mixed with honey, and distilled in the magic cauldron Odherir, became the source of an intoxicating beverage that gave wisdom and inspiration to poets. Odin favored this drink. In some accounts, Kvasir was created from the spittle of the Aesir and the Vanir. Compare Kvasir to Soma (India). *See also* Aesir; Baugi; Dwarfs; Odraerir; Vanir.

Kvergjelme (Teutonic) *see* Hvergelmir; Nifl-heim.

Kwammang-a (Bushmen, Africa)
Creator of the moon. He is sometimes described as grandson of Cagn. Cagn made Eland from Kwammang-a's discarded shoe. Eland was killed by Kwammang-a, and when he burst the gall the fluid blinded him. He wiped his eyes with a feather, which he then threw into the sky. It became the moon. Some call Kwammang-a a rainbow lord. Associated with Cagn (q.v.).

Kwan-on (Japan) *see* Kuan Yin.

Kwan-she-yin (China) *see* Kuan Yin.

Kwangiden *Kwangiten* (Japan)
Protector deity and god of good fortune. In Buddhist mythology the two devas Ganapati and Vinayaka are joined to become the Japanese Kwangiden. Kwangiden is shown in several forms, but usually as elephants when male and female deities. In male form he is sometimes shown as a man with a human body and an elephant's head. Normally he has four hands and four legs. Sometimes he is shown with two or six arms.

Kwangiten (Japan) *see* Kwangiden.

Kwannon (Japan) *see* Kannon; Kuan Yin.

Kwarenah (Persia) *see* Khvarenanh.

Kwetzal-Koatl (Mexico) *see* Quetzalcoatl.

Kwoth (Dinka, Neur People, Africa)
Also known as: *Kuth* (plural).
These spirits, known singularly as Kwoth, are divided into those above (kuth nhail) and those below (kuth piny).

Ky-Klopes (Greek) *see* Cyclops.

Kyala (Nyakyusa People, Tanzania)
Sky god. He was promoted from a local god to chief god, then to supreme god. At that time he was no longer worshiped, being too far above for petty worries of mortals.

Kybebe (Greek) *see* Cybele.

Kybele (Hittite) *see* Cybele.

Kyklopes (Greek) *see* Cyclops.

Kypris (Greek) *see* Aphrodite.

Kyrene (Greek)
Another spelling for Cyrene, the nymph queen of Libya.

Kyrgys-Khan (Altaic, Tartars)
With his brother Sary-Khan, he is a god of happiness. They are the grandsons of Bai Ulgan (q.v.).

L

L (Maya)
Aspects of known as: *"The Old Black God."*
He is shown toothless, with black paint covering one-half of his face. L may be the same as the Aztec Tepeyollotl (q.v.).

La Strega (Roman) *see* Befana.

La Vecchia (Roman) *see* Befana.

La'a Maomao (Polynesian) God of winds.

Labartu (Assyrian)
They are female demons who live in marshes and mountains. At one time it was thought that they kidnapped children. Later, they were considered benevolent. *See also* Lamassu.

Labosum (Saora People, India)
This earth god is offered rice and wine when a new home is built. He is implored to keep ants from eating the wood. Adununkisum, the sun god, is then offered a mango leaf filled with rice to keep the house safe from fire. *See also* Adununkisum.

Labyrinth (Greek)
The Labyrinth was built by Daedalus for king Minos to contain the Minotaur. *See also* Daedalus; Minos; Minotaur.

Lacedaemon (Greek)
Founder and king of Sparta. He is the son of Zeus and Taygete (q.v.).

Lachesis (Greek)
"Caster of Lots." She is one of the Fates (q.v.).

Lachmu (Babylon)
Also known as: *Lache.*
Deity of darkness. He is the husband of Lachama (Lachos). Some say Lachmu and Lachama are the parents of Anshar and Kishar. *See also* Anshar; Apsu; Kishar; Tiamat.

Lada (Romanian, Slavic)
Goddess of spring. Lado is the sun god spouse of Lada. In later times, Lada was venerated as an aspect of the Virgin Mary and was worshiped during the Christmas season.

Lado (Slavic) Husband of Lada (q.v.).

Ladon (A) (Greek)
Ladon, the son of Oceanus and Tethys, is the god of the river Ladon. *See also* Oceanus; Rivers; Tethys.

Ladon (B) (Greek) He traveled with Aeneas from Troy to Italy.

Ladon (C) (Greek) The name of a dog belonging to Actaeon.

Ladon (D) (Greek)
He is the hundred-headed and hundred-voiced dragon son of Phorcys and Ceto, or possibly Typhon and Echidna. Ladon and the Hesperides protected the garden where the Golden Apples were kept. When Heracles came to get the apples, he killed Ladon. Ladon became the constellation Draco. *See also* Ceto; Echidna; Evander (A); Heracles; Hesperides; Medusa; Phorcys; Typhon.

Ladru (Irish) *see* Cessair.

Lady Meng *Lady Ming* (China)
Goddess of Hell. *See also* Meng (A).

Lady of Heaven (Middle Eastern) *see* Anat.

Lady of Kazailu (Mesopotamia) *see* Martu.

Lady of Ninab (Mesopotamia) *see* Martu.

Lady of Sati (Egypt) *see* Anoukis; Anquet.

Lady of the Bed (China) *see* Ch'uang-Mu.

Lady of the Lake (Arthurian) *see* Vivien.

Laeapua (Hawaii, Polynesia)
God of fishers. He is the local god of Lanai who is associated with Kaneapua, who is also a god of fishers.

Laeding *Leding* (Teutonic)
Fenrir was first bound by a chain called Laeding, made of strong iron links. The second chain was called Dromi. The last and strongest chain was named Gleipnir. *See also* Fenrir; Gleipnir.

Laerad (Teutonic) *see* Ledrad.

Laertes (Greek)
King of Ithaca. Argonaut. Member of the Calydonia Boar Hunt. He is the son of Arceisius and Chalcomedusa, or Cephalus and Procis. He married Anticleia who may have already been pregnant by Sisyphus. His children are possibly Odysseus and Ctiemene. Laertes was one of Penelope's suitors. *See also* Anticleia (A); Argonauts; Sisyphus.

Laga (Teutonic) *see* Odin; Saga.

Lagamal (Sumer)
Son of a god. A deity of Elam who was believed to be the son of Ea.

Lagi (Polynesian) *see* Rangi.

Lahamu and Lahmu *Lachama and Lachmu, Lakhamu and Lakhmu.*
Also known as: *Asakku* (Assyro-Babylonian).
The dragons Lahamu and Lahmu were the first forms of life created by Apsu and Tiamat. Lahamu is the female, and Lahmu is the male. From their union, Anshar and Kishar were created. Lahamu is invoked when a building is completed. They are described as "hairy," or "muddy." They have three pairs of curls and are naked except for a triple sash. *See also* Anshar; Apsu; Kishar; Marduk; Tiamat.

Lahar (Sumer)
Created by Enlil (Ea in Babylonian mythology) and sent to earth by Enki, Lahar is the god of cattle. *See also* Ashnan; Ea; Enki; Enlil.

Lahmu *Lakhmu* (Assyro-Babylonia) *see* Lahamu.

Laima (Latvia)
Goddess of childbirth. Laima is one of the deities who accompany Latvians from birth to death.

Laius *Laios* (Greek)
King of Thebes. He is the son of Labdacus (who is the son of Polydorus and Ncyteis). Laius married Jocasta (also known as Epicasta), the daughter of Menoeceus. He is the father of Oedipus. *See also* Jocasta; Oedipus; Polydorus.

Lajnan (Micronesia) *see* Rigi.

Laka (A) (Hawaii)
Laka, the goddess of the wildwood, is the sister of Lono (q.v.).

www.ebook3000.com

Laka (B) (Hawaii) He is the ancestor of the Menehune people.

Lakchos (Greek) *see* Bacchus.

Lakemba (Polynesia) *see* Lothia; Miru.

Lakhamu *Lakhmu* (Sumer)

Huge serpents, the first deities to be born of Apsu and Tiamat. They in turn gave birth to Anshar and Kishar. *See also* Lahmu.

Lakhamu and Lakhmu (Assyro-Babylonian) *see* Lahamu.

Lakhe (Babylon) *see* Belus (B).

Lakhmu (Babylon) *see* Lahamu.

Lakhus (Babylon) *see* Belus (B).

Lakshmana (India)

He is the son of King Dasartha and Queen Sumitra, twin of brother Shatrughna, and faithful brother of Rama. *See also* Agastya; Bharata (A); Karttikeya; Rama; Ravana.

Lakshmi *Laksmi, Laxmi* (Buddhist, Jain, Hindu; India)

Also known as: *Devi Sri* (Noble Goddess), *Dharani* (an avatar), *Haripriya* (Beloved of Vishnu), *Jaganmatri* (Mother of the World), *Jaladhi-Ja* (Born in the Ocean), *Kamala* (an avatar), *Karisini* (One Possessing Dung), *Ksama* (Earth), *Lala, Luttchmeen, Mama Lakshmi, Matrirupa* (Mother of All Living Things), *Padma* (Lotus Goddess), *Phra Naret* (Siam), *Radha* (Lotus goddess), *Rohini* (an avatar), *Rukmini* (an avatar), *Shakti, Shri, Sita* (an avatar), *Sree, Sri, Varahini* (an avatar), *Vriddhi* (Goddess of Growth).

In early times, (pre–Vedic) Lakshmi was an earth goddess. Later, in the *Rig-Veda* she is known as Sri and Lakshmi. In the *Ramayana* she is a beautiful goddess of fortune and prosperity, one of the treasures born of the churning of the sea of milk. She emerged holding a lotus and proceeded to bestow blessings upon the universe. The deities were dazzled by her brilliance, and each one wanted her for a partner. She decided upon Vishnu as her mate, and in each of his ten avatars she is there as her avatar to join him in his activities. Her avatars as Vishnu's mate are Kamala or Padma, mate of Vamana (Vishnu's dwarf avatar); Dharani (meaning the Earth), mate of Parashur Rama; Sita, mate of Rama; Varahini, mate of Varaha; Radha, mate of Krishna; and some say Rukmini, another of Krishna's consorts. In some tales, Vishnu and Lakshmi are the parents of the god of love, Kama, and the goddess Tisnavati. In the *Purana*, Lakshmi is the daughter of Brighu and Khyati. Prior to her relationship with Vishnu, she was the consort of Agni and the mother of the three Agnis (fires). Lakshmi is a culmination of the aspects of the three great goddesses of Indian rivers, Ganga, Yamuna and Sarasvati. She is one of a Hindu Triad with Sarasvati and Devi. In this representation, she is known as the Red Goddess. As Karisini, she is the fertility goddess who gives soil, crops and animals. In some areas, aside from being the goddess of glory and prosperity, she is the goddess of rice. She is known to people who fish for a living as Empress of the Sea. Sacrifices are made to her for a good catch and a safe journey home. Lakshmi is approached by the faithful who desire children, fame, fortune, health, horses, cows, and by men who desire sons. She is also a favorite goddess of business people. She does not have temples, but is worshiped in the home. Lakshmi, the symbol of Vishnu's creative energy, is usually depicted seated and holding a pink or blue lotus. In some depictions, she has four hands; two hands are in the protective gesture (abhaya mudra), and in her other hands, she holds a mirror and a vermillion pot. Shown beautifully dressed, she is often accompanied by two dwarfs. She is also depicted seated or standing on her symbol, the lotus. Her complexion is golden and she sometimes has two arms. She is associated with the elephant, especially the white elephant known as Sri-gaja, who symbolizes rain and fertility. In Buddhist art, she is shown with two elephants. Her vehicle is the owl. This could be because the owl feeds on rodents which damage crops. As her companion, she is able to keep watch over owls and ensure agricultural prosperity. Lakshmi appears on the Parijata tree as a flower. A winter festival is held for Lakshmi and Kali, called Diwali (feast of lamps). During this period, the new moon in late October or early November (Kartik), bankers and merchants count their wealth. In Nepal an annual celebration takes place on the new moon night in November to celebrate Lakshmi. As the goddess of growth and charity, she is also celebrated on the Friday before the full moon in Sravana (July-August), in a festival known as Lakshmi-Vrata. In Sanskrit, the word lakshana means a "lucky sign," and the word laksha, "a luck mark." In the *Rig-Veda*, the word Lakshmi is used for "good luck." In the *Atharva Veda* there are two Lakshmis, one for good and one for bad luck. The Hindu reverence for the cow is based on the worship of Lakshmi, the beautiful goddess of material and spiritual prosperity. Lakshmi is comparable to Kishijoten, sister of Bishamon (Japan) (q.v.). She is also comparable to Vasundhara. Compare Lakshmi to Indrani and the Greek Venus. The Greeks compared Lakshmi to Artemis (q.v.). Lakshmi may be the same as or is associated with Ardhanariswara (q.v.) Sometimes, Lakshmi is said to have assisted Soma (q.v.). For other treasures retrieved from the churning of the sea of milk, *see* Kurma. *See also* Agni; Andhaka; Brighus; Devi; Ganga; Garuda; Kama (A); Krishna; Kurma (the tortoise avatar of Vishnu); Parashur Rama; Parijata Tree; Radha; Rama; Sarasvati; Shakti; Sisupala (regarding Rukmini); Sita; Soma; Sri; Tulasi; Vaikuntha; Vamana; Varaha; Varuna; Vishnu; Yami.

Lakshmi-Vrata (India) Festival. *See also* Lakshmi.

Laksmi (India) *see* Lakshmi.

Lala (Etruscan) *see* Diana; Lakshmi.

Lamashtu (Middle Eastern) *see* Anat; Lamassu.

Lamassu *Lamashtu, Lamastu, Lammea* (Babylonia, Hebrew, Sumer)

Also known as: *Labartu, Labasi, Lamme* (Sumerian).

Demoness. Forerunner of Lilith. She is probably a child-slaying demon similar to Lilith of the early Hebrews. Originally Lamassu was the Sumerian deity Lamme. She is said to be the daughter of the god of heaven, Anu. She attacks pregnant women and children. The mere mention of her name can strike terror in people. She has a violent temper and when she is on a rampage she will chase domestic animals and accost them with her bare hands. She can slide in and out of houses at will, terrifying the inhabitants. She might be shown as a winged animal.

She has also been depicted standing on the back of a wild ass, a serpent in each hand and suckling a wild pig and a jackal. Some say that she resembles a leopard and has the face of a lion. She is shown with wild hair and bare breasts. *See also* Abyzy; Labartu; Lamia; Lilith; Sedu.

Lambodara (India) *see* Ganesha.

Lamech (Sumer) *see* Lumha.

Lamhfhada (Celtic, Irish, Welsh) *see* Lugh.

Lamia (A) *Lamma, Lamiae* (Greek)
Lamia, the daughter of Belus and possibly Libya. She fell madly in love with the great god, Zeus. The ever-jealous Hera turned Lamia into a snake with the head and breasts of a woman. Hera killed all but one of Lamia's children. This drove Lamia insane. When she saw a child in its mother's arms she would seize the infant, tear it to pieces and devour it. She terrorized people until she was slain, possibly by Eurybatus, the son of Euphemus. *See also* Alcyoneus; Hera; Lamassu; Scylla; Sirens; Zeus.

Lamia (B) (Greek)
Lamia, the daughter of the sea god Poseidon, and Zeus are the parents of Sibyl Herophile.

Lamia (C) (Greek)
She was the monster of Crissan who roamed the land killing and eating humans at random. This ended when the Delphic Oracle recommended that mortals be sacrificed to her. The first person chosen was Alcyoneus, who with his brother Porphyrion were the strongest of the Giants. Before Alcyoneus was devoured, Eurybatus killed her.

Lamia (D) (Greek)
Lamia is a god who was worshipped at Eleusis.

Lamiae (Akkadian, Greek) *see* Lamia.

Lamis (Greek) *see* Agenor (A).

Lamma (Akkadian, Greek) *see* Lamia.

Lamme (Sumer) *see* Lamassu.

Lampethus *Lampetie* (Greek)
One of the Heliades, daughter of Helios or Apollo and Neaera. Lampethus and her sister, Phaethusa, were so devastated at the death of their half-brother Phaethon that they were turned into poplar trees and shed tears of amber. *See also* Aegle (A); Heliades; Helius; Phaethon (A).

Lampetie (Greek)
Another spelling for Lampethus, one of the Heliades (q.v.).

Lampon (Greek) *see* Helius.

Lampus (Greek)
He is the son of the king of Troy, Laomedon, and Leucippe, Placia or Strymo. *See also* Astyoche; Hesione; Priam.

Lamus (Greek)
His parents are Heracles and the queen of Lydia, Omphale. Heracles was Omphale's slave for three years. Lamus' siblings are Agelaos and Alcaeus. *See also* Heracles; Omphale.

Lan-ts'ai-ho (China)
Patron of Gardeners. *See also* Arhats; Eight Immortals.

Land of the Setting Sun (Egypt) *see* Ament.

Land of Women (Irish) *see* Tir na mBan.

Langal (Australia) *see* Rainbow Snake.

Langali (India) *see* Bala-Rama.

Langi (Polynesian) *see* Rangi.

Langit (Polynesian) *see* Rangi.

Lao-Tien-Yeh (China) *see* Yu Huang.

Lao-Tzu (Taoism; China) *Lao Tzu*
Also known as: *Shen Pao, T'ai-Shang Lao-chun.*
High god. Lao-Tzu is said by some to have lived in the first part of the 6th century B.C.E. and is thought to be the founder of Taoism. Other scholars debate his existence. In the Taoist tradition, Lao-Tzu became an immortal after death. He appeared in spirit form to Zhang Dao Ling about two centuries later and gave him the authority to establish the dogma and tenets of *Tao jiao,* or religious Taoism. His movement was known as the "Way of the Celestial Masters" *(Tien Shi).* Lao-Tzu is the ruler of the third heaven (T'ai Ch'ing) and the teacher of kings and emperors. Once a mortal named Laotse or Lao Tze, he was later deified as Shen Pao and was associated with the San Ch'ing (The Pure Ones). In some versions he was connected with Confucius. He is possibly the same as Cheou-lao, the god of longevity. *See* Chang Tao-ling regarding the founders of existing Taoism. *See also* Shang Ch'ing; T'ai Ch'ing; Yu Ch'ing.

Laocoon (A) (Greek)
He is the son of the Trojan seer, Antenor, and a priestess of Athena, Theano. For the names of his siblings, *see* Theano. *See also* Acamas (B); Argonauts, Laodamas (A).

Laocoon (B) (Greek)
The son of Capys and Themiste, who is also the cousin of Capys, Laocoon is the brother of Anchises and husband of Antiope. *See also* Anchises; Antiope.

Laocoon (C) (Greek)
An Argonaut, Laocoon, the son of Oeneus, sailed on the Argo to protect his half-brother Meleager (q.v.).

Laocoon (D) (Greek)
The son of Priam and Hecuba, he was the Trojan priest of Apollo and the sea god Poseidon. It was Laocoon who warned his colleagues that there were soldiers in the Wooden Horse. *See also* Priam.

Laodamas (A) (Greek)
He is the son of the Trojan seer Antenor and Theano, who was a priestess of Athena at Troy and who also founded Padua after the fall of Troy. For a list of his siblings, *see* Theano. *See also* Acamas (B); Apsyrtus; Laocoon (A).

Laodamia (A) (Greek)
She is the daughter of Bellerophon and Philonoe. Her hus-

www.ebook3000.com

band (who may be her son by Zeus) is Sarpedon, and their child is Evander. *See also* Bellerophon; Evander (B); Sarpedon (A); Sarpedon (B).

Laodamia (B) (Greek)
She is the daughter of Acastus, the Argonaut king of Iolcus, and Astydameia, the daughter of Pelops and Hippodameia. Her siblings are Sterope and Sthenele. She has brothers who are unnamed. *See also* Acastus; Sterope; Sthenele.

Laodice (A) (Greek)
Also known as: *Electra.*
She is the daughter of Agamemnon and Clytemnestra. Her siblings are Chrysothemis, Iphigeneia and Orestes. *See also* Acamas (A); Agamemnon; Electra.

Laodice (B) (Greek)
The daughter of Priam and Hecuba. After the fall of Troy, she was swallowed by the earth. *See also* Hecuba; Priam.

Laodice (C) (Greek)
Cinyras, the king of Paphos in Cyprus, is her father.

Laomedon (Greek)
King of Troy. He is the son of Ilus, the wrestler and the fourth king of Troy and Eurydice. Laomedon contracted with Apollo and Poseidon to build the walls of Troy. When they had finished the project, Laomedon refused to pay them. The two gods sent a sea monster after him. Laomedon bribed Heracles to kill it. Again, Laomedon refused to pay for the services rendered. Furious, Heracles sent eighteen ships to Troy. Laomedon and all his sons except Priam were killed. *See also* Astyoche; Eurydice (C); Hesione; Poseidon; Priam.

Lapithae *Lapiths* (Greek)
The Lapithae were Thessalians ruled by Peirithous. They were constantly fighting with the Centaurs. *See also* Centaurs; Hippodamia (A).

Laphystios (Greek) *see* Dionysus.

Lara (A) (Roman)
Also known as: *Mania.*
Evil deity. A nymph. Mother of the Manes. She was too talkative so her tongue was cut out by Jupiter. *See also* Manes; Mania.

Lara (B) (Greek)
She is the wife of the messenger of the gods, Hermes, and the mother of the household gods, the Lares, according to some sources.

Larentia (Roman) *see* Acca Larentia.

Lares *Lars* (Etruscan, Roman, Greek)
Also known as: *Lar* (Singular), *Penates.*
Ancestor spirits. Gods of the home. The Lares are two ancient Etruscan gods, embraced by the Romans. Originally, they were thought to be spirits of the field. In later times, they represented deified spirits of ancestors, and their function was to shield descendants against harm. Each state had Lares and each household kept a Lar, likely in the form of a statue. Lares were orignally found in fields and later at intersections. The Lar of the household was acknowledged upon departure from and arrival to the home, and at meals. Their queen may have been the earth or mother goddess, Acca Larentia. She was either the wife of Carutius or Faustulus and in either case was the nurse of Romulus and Remus. The household Lar is often depicted as a young man holding a drinking horn and cup. Their sacred animal is the dog. Some say the parents of the Lares are Hermes and Lara. Compare the Lares to Domovoi. *See also* Acca Larentia; Lupa; Romulus.

Larunda (Greek) *see* Muses.

Larvae (Roman)
This is another name for the ghosts known as Lemures (q.v.).

Lasema *Lasya, Sgeg-mo-ma* (Tibet)
Goddess of beauty. *See also* Akshobhya; Mamaki; Ratnasambhava.

Lasthenes (Greek)
He helped Eteocles defend the city of Thebes along with the Thebans, Actor, Hyperbius, Melanippus, Megareus, and Polyphontes. *See also* Adrestus; Eteocles; Melanippus.

Lasya (Tibet) *see* Lasema.

Lat (A) (Egypt) *see* Leto.

Lat (B) (Arabic) *see* Allat.

Latarak, God of Badtibira (Sumer) *see* Inanna.

Latmikaik (Pelew Islands, Micronesia)
Latmikaik, a sea goddess, rose from the waves. She brought forth fish, which built a tower that became earth. With her husband Tpereakl, she shared in governing the earth. She had two sons and it is possible mankind resulted from the joining of these to fish.

Latona (Roman)
She is the Greek Leto. *See also* Diana; Leto; Sekhmet.

Laufey (Teutonic)
Laufey is the giant mother of Loki and possible spouse of Farbauti. *See also* Loki.

Laukamat (Latvia)
Birth and death goddess. Goddess of fields. She accompanies Latvians from birth to death. *See also* Laima.

Laukosargas (Prussia)
God of fields and grain. He is similar to Lawkapatim (Polish).

Laume (A) (Prussia)
Goddesses of protection. They, along with Kaukis (small dwarfs and gnomes) protect the home. *See also* Kaukis.

Laume (B) (Lithuanian)
A supernatural hag, Laume rides around in her iron wagon, carrying a whip. She was once caught stealing from Perun's garden. *See also* Perun.

Laurin (Teutonic) *see* Andvari.

Lausus (A) (Greek)
"Scorner of the Gods." Lausus was a close friend of the Lord of Darkness, Turnus. He was killed by Aeneas. *See also* Abas (A); Aeneas; Turnus.

Lausus (B) (Greek) He is the brother of Rhea Silvia.

Lava (India) *see* Kusha.

Lavania (Greek) *see* Aeneas; Turnus.

Laverna (Roman) Goddess of thieves.

Lawgiver of Society (Nigeria; Africa) *see* Ala (B).

Lawkapatim (Polish, Slavic)

Field spirit. Her primary job is to preside over the tilling of the field. She is similar to Datan and Tawals and the Slavic gods, Kricco (fruits of the field) and Kirnis (god of ripening cherries). *See also* Datan; Laukosargas.

Laxmi (India) Another spelling for Lakshmi.

Laza (Islam)

The second stage in Daru el-Bawar, the Islamic Hell, Laza is reserved for Christians. *See also* Islamic Hell.

Learchus (Greek)

He is the son of Athamas and Ino. His father accidentally killed him. *See also* Ino.

Lebe (Dogon People, Africa)

One of the first people. Lebe is the oldest of the eight ancestors who came from heaven. He represented "word" or "speech." In a complex legend Lebe died or was swallowed by the seventh ancestor (a snake), but "word" remained as stones, so, in a sense, Lebe or language is represented by a stone. Lebe is associated with the Nummo spirits (q.v.).

Leda (Greek)

Her parents are Thestius and Eurythemis. Three of her siblings are Althaea, Hypermnestra and Plexippus. Leda's mortal husband is King Tyndareus, by whom she had Clytemnestra and Castor. She is the mother of Helen and Polydeuces by Zeus. For details to compare to other women who were seduced by Zeus in other forms: *see* Aegina; Antiope; Danae; Europa. *See also* Althea; Castor; Helen; Nemesis.

Leding (Teutonic) *see* Laeding.

Ledrad *Laerad* (Teutonic)

The upper bough of the Yggdrasil tree (q.v.).

Legba (Dahomey, Fon People, Africa)

Also known as: *Eschu.*

An individual's personal god, a god of the crossroads, and a trickster. The Legba statue represents the master of the house and placed in front of him are pots, which are members of his family. Numerous myths revolve around Legba. It is said that in the beginning Legba lived on earth with his supreme god. He only did what he was instructed to do by his god. When he did something harmful to fulfill his orders, the people blamed him, and eventually came to hate him. Finally, Legba approached his god and asked why the people should hate him as he was only fulfilling god's will? God responded that the ruler of a kingdom should be acknowledged and thanked for all good and his servants for all that is bad. This may be why Legba is sometimes considered to be a devil. In some versions Legba is a messenger of the twin deities, Mawu and Leza (Lisa), and generally associated with Eshu, Fa, and the thunder god Heviosso. Legba is shaped like a mound of clay with a molded phallus and covered with protective cover of thatch. *See also* Eshu; Fa (A); Leza.

Legend of the Four Suns (Aztec)

Also known as: *Legend of the Five Suns.*

First earths. There are several versions of this legend. **1.** There were four eras before our own. The first era, known as Nahui Ocelotl, ruled by Tezcatlipoca, was called Tiger Sun, which lasted 676 years. Then inhabitants of the planet Earth were eaten by tigers and the sun vanished. The second sun (Nahui Ehecatl), ruled by Quetzalcoatl, was called the "Four Wind." At the end of 364 years mortals were swept away by fierce winds and the survivors changed into monkeys. The third sun, Nahui Quiahuitl, ruled by Tlaloc, was called "Four Rain." At the end of 312 years a terrible fire shower destroyed most of mankind, and all remaining mortals were changed into birds. The Fourth Sun, Nahui Atl, ruled by the goddess Chalchihuitlicue, was destroyed by a great flood after 676 years, and only a man and a women survived. The Fifth Sun, which is our current era, is called Nahui Ollin, or 4 Motion. Ruled by Xiuhtecuhth, it will end in earthquakes. **2.** The name of the First Sun is Chalchuihutonatiuh; the Second Sun, Tletonatiuh; the Third Sun, Yohualtonatiuh; and the Fourth Sun, Ehecatonatiuh. **3.** The names of the regents of the suns are Atonatiuh, the First Age; Tlalchitonatiuh, the Second Age; Ehcatonatiuh, the Third Age; and Tlatonatiuh, the fourth age. In this legend Quetzalcoatl appeared in the third sun age. **4.** In this version, Tonacatecutli and Tonacaciuatl dwell in the thirteenth heaven. Four gods are born from them: Camaxtli, Tezcatlipoca, Quetzalcoatl, and Huitzilopochtli. From them came Oxomoco and Cipactonal (first man and woman). They created Mictlantecutli and Mictlanciuatl to be in charge of hell. Their next creation was Cipactli, a sea monster they used to shape the earth, and Tlaloctecutli and his wife Chalchiuhtlicue to have dominion over the sea. Oxomoco and Cipactonal had a son who married a woman formed from a hair of the goddess Xochiquetzal. This pair created a half sun which gave so little light the gods made another half sun which became Tezcatlipoca. In another version the various deities were named: Quetzalcoatl, Atonatiuh, Ocelotonatiuh, Quiyauhtonatiuh and Ecatonatiuh. The ancient belief of the people of Yucatan also has four ages of the world. Saiyamkoob were the first people who lived in darkness. They were followed by the Tsolob, who were destroyed by flood, then followed the Mayan civilization. *See also* Atonatiuh; Chicomoztoc; Nata; Tlazolteotl.

Lei-Kung (China)

Also known as: *My Lord Thunder.*

The god of thunder. Lei-Kung carries out punishment against the guilty who have escaped the law or whose crime was not discovered. At times, he solicits the aid of humans, rewarding them for furthering his work. He is depicted as an ugly man with claws and wings and a blue body, wearing nothing but a loin cloth and carrying a mallet. At his side hang his drums. He is associated with Tien Mu (Mother Lightning) Yu-tzu (Master of Rain), Yun-t'ung (Cloud God), and Feng-po (God of Winds). Sometimes Feng-po is replaced by the goddess Feng-p'o-p'o (Goddess of Winds). *See also* Kei-Kung.

Leipt (Teutonic) *see* Elivagar.

www.ebook3000.com

Leiriope (Greek)
The river god Cephissus and Leiriope are the parents of the beautiful, vain god, Narcissus. *See also* Cephissus; Narcissus.

Leische (Russian)
Spirit of the woods. He is worshiped in a circle of birch trees. One must face east and bend down and look between the legs and call for Uncle Leische to grant a wish or bargain for the soul.

Lelex (A) (Greek)
King of Megara. He is the son of the sea god, Poseidon, and Libya. His brothers are the twins, Agenor, the king of Phoenicia, and Belus, king of the Egyptians. *See also* Agenor (A); Belus (B).

Lemminikainen (Finnish)
Also known as: *Ahti, Ahto, Kaukomielli.*
Magician. His mother is the goddess, Ilmater, who is also a magician. He is the hero brother of Vainamoinen and Ilmarinen. In an attempt to kill a swan he was thrown into a river and drowned. His mother restored him to life. In another version of the myth, he is the consort of Wellamo or Vellamo. They live deep under the sea in a place called Ahtoia. He is holder of the treasure Sampo. Some say Lemminikainen bore the epithet Ahti so he could be both god and hero. *See also* Ahti; Ilmarinen; Louhi; Vainomoinen.

Lempo (Finnish) *see* Hiisi.

Lemures (Roman)
Also known as: *Larvae, Remuria.*
Spirits of the dead. They are evil spirits who return to wreak mischief and terror among the living. One of the Lemures is said to be the ghost of Remus.

Lenaeus (Greek)
"He of the Winepress." An epithet of Dionysus (q.v.).

Leodegrance (Celtic) Another name for Bran (q.v.).

Leodocus (Greek)
He is the Argonaut son of Bias, king of Argos, and Pero. For a list of siblings, *see* Pero.

Leprechaun *Lepracaun, Leprachaun, Leprecawn, Leprechawn, Lubrican* (Celtic, Irish)
Spirit. A small fairy who goes around looking like an old man. Leprechauns are known for their fine leather work; the shoes they craft are among the finest known. It is said that a leprechaun will divulge the location of his life savings if captured by the commanding glare of a mortal gaze. However, when bullied and threatened by thieves, leprechauns can be disagreeable. They are associated with the Cluricaune, who haunt cellars. *See also* Dana; Dwarfs.

Ler (Celtic) *see* LLyr.

Lerad (Teutonic)
Deified tree. The Lerad is topmost branch of the Yggdrasil tree. *See also* Yggdrasil.

Lernus (Greek)
He is the possible father of the Argonaut Palaemon. *See also* Hephaistos.

Leshacikha (Slavic)
She is the wife of the forest-dwelling shape changer, Leshy.

Leshonki (Slavic)
They are the children of Leshy and Leshacikha.

Leshy *Leshies* (plural), *Lesiy, Lesiye, Lyeshy, Lesovik* (Slavic)
Also known as: *Miehts-Hozjin.*
Forest faun or satyr. A shape changer of the wild areas. Some say he is the offspring of a mortal woman and a demon. Although not evil, he enjoys misdirecting mortals and kidnapping young women. He wears his shoes on the wrong feet. Leshy is the protector of all birds and animals in the forest. His protector is a bear. Humans can thwart him by putting their clothes on backwards. Leshy has a wife called Leshacikha and children known as the Leshonki. His shape is human, but his blood and skin tone are blue and he does not have a shadow. His eyes and beard are green. Often he appears like the devil, with horns, goat's feet and finger-claws. He is similar in nature to the field spirits known as Polevik (q.v.). *See also* Domovoi; Kalevala.

Lesiy (Slavic) *see* Leshy.

Lesovik (Slavic) *see* Leshy.

Lethe (Greek)
Deified river. This river, one of five in Hades, is known as the river of forgetfulness. When the soul travels this river all pain and anguish from the past is forgotten. The soul is prepared from this trip to enter the etheral Elysian Fields. The name of the river's nymph is also Lethe, the daughter of Eris (strife). The other four rivers in Hades are Acheron, the river of woe; Cocytus, the river of wailing; Phlegethon, the river of fire, and Styx. *See also* Acheron; Cocytus; Elysian Fields; Eris; Hades; Styx; Tartarus.

Leto (Greek)
Also known as: *Lat* (Egypt), *Latona* (Roman).
Goddess of light. Leto is the daughter of Ceos and Phoebe, sister of Asteria and mother by Zeus of the twins Apollo (the sun) and Artemis (the moon goddess and goddess of the hunt). Leto is identified by the Romans as Latona or Queen Lat and by the Egyptians as Lat, a fertility goddess of the date-nut and olive. Persecuted by the jealous Hera, who sent the serpent Python to harass her, she wandered the land searching for a safe place to give birth. Hera kept the goddess of birth, Ilythia, away from Leto, who suffered horribly for nine days. Iris, the messenger of the gods was able to locate Ilythia and guide her to Leto who had finally found solace on the desolate rock called Delos, which floated on water and was tossed about by waves. This rock was really Asteria, Leto's sister, who had resisted the sexual overtures of Zeus and was turned into a quail and then a rock. Even here Leto had to promise that with the birth of Apollo the land would become fertile and worshippers would come from afar to honor the birth of the sun deity. Now Zeus, who had originally abandoned Leto because of his fear of Hera, came forth in appreciation and anchored Delos to the floor of the sea. Poseidon has also been credited with this deed. Out of deference to Hera, who swore that Leto would not give birth where the sun shone, he erected a dome over the rock and four pillars that reached the bottom of the sea. Other myths are easier

on Zeus. They say that he altered Leto's appearance from a woman to a quail, which allowed her to escape Hera's wrath and fly to Delos. Leto was also called the personification of darkness. Niobe, the wife of Amphion, the king of Thebes, and the mother of fourteen children made facetious remarks to Leto for only having two children and further insulted her by saying that her female child, Artemis, was masculine and her male child, Apollo was feminine. Enraged, Leto sent Apollo to murder the sons of Niobe and Artemis to murder the woman's daughters. Apollo spared Amyclas and Artemis spared Meliboea. *See also* Aeneas; Amphion; Apollo; Artemis; Ceos; Hera; Ilythia; Iris; Niobe; Zeus.

Leucippe (A) (Greek)

The daughters of Minyas, Leucippe, Alcithoe and Arsippe were driven insane by Dionysus when they refused to honor him. While in a music-induced frenzy, the three sisters killed Hippasus, Leucippe's son. *See also* Alcithoe; Calchas; Dionysus; Minyas.

Leucippe (B) (Greek)

She is the daughter of Thestor and Megara.

Leucippus (A) (Greek)

He is the son of Oenomaus and Evarete and the brother of Hippodameia. *See also* Gorgophone; Hippodameia (B); Oenamaus.

Leucippus (B) (Greek)

His parents are Perieres and Gorgophone. *See also* Borus; Gorgophone; Icarius.

Leucopeus (Greek) *see* Calydonian Boar Hunt.

Leucosia (Greek) One of the Sirens (q.v.).

Leucothea (Greek)

Also known as: *Ino, Mater Matuta, White Goddess.*

Leucothea is the name given to Ino by the Nereids after she drowned and was made into a sea goddess. *See also* Ino; Nereids.

Leucothoe (Greek)

She is the daughter of the king of Persia, Orchamus, and Eurynome. Her father buried her alive when he heard about her love affair with Apollo. She turned into a frankincense bush. *See also* Apollo; Clytia; Eurynome; Helius.

Leviathan (Gnostic; Babylon, Ugarit.)

Also known as: *Livyathan* (Hebrew), *Nakhash, Rahabh, Tannin.*

This serpent was slain by Gabriel with the assistance of Yahweh. Gabriel made a tent from the skin of Leviathan to cover the walls of Jerusalem. Compare Leviathan to Tiamat and Mot. In some renditions, Leviathan is the same as the dragon Lotan (meaning "covering") of the Ugarites, who was slain by Baal. *See also* Apepi; Rahabh.

Leza *Lisa* (Bantu People, Africa)

Also known as: *Chilenga, Lubumba, Reza, Rezha.*

High god. Leza is generally thought of as being a god of lightning or rain. It seems that different names denote different functions of this god. The name may supersede Mpambe, Chiuta, and the early Leza of the Yaos of Africa. Some say Leza is a goddess and as such is either the wife or mother of Mawu. Some also say she is one of a triad along with Mawu and Ge. When associated with Mawu she is an androgynous deity called Mawu-Lisa. In some versions both Leza and Mawu are the twins of Nana Buluku who was the female creator of everything. Leza is shown as chameleon. *See also* Lisa; Mahu.

Lha-mo (Tibet) *see* Dakinis.

Lhamo *Lha Mo* (Buddhist, Hindu; India)

Lhamo, a defender goddess is an important goddess to the Tibetans. She is often found in a corner behind a curtain in monasteries. The only feminine divinity of the Dharma Palas (Eight Terrible Ones), and the only defender goddess of the Mahayana school. She was outfitted with weapons by the gods. To determine the fate of mortals, she has two die given to her by Heybajra. Brahma gave her a peacock feather fan and Vishnu gave her a lion which she wears in her right ear. In her left ear hangs a serpent, given to her by Nanda, the serpent. Vajrapani gave her a hammer. Other gods presented her with a mule covered by the skin of a demon, with reins of venomous serpents. Lhamo is depicted seated side-saddle on her mule. Her expression is fierce and she has a third eye. Covered in a tiger skin, she wears a long garland of heads. In her right hand, which is raised, she carries a scepter and in her left, a skull cup which is held at her breast. *See also* Brahma; Kali; Nanda, Vajrapani; Vishnu.

Li (China) *see* T'ieh-Kuai.

Li Hun (China)

Hero or god of ceremonies. One of the nine heroes, Li Hun is worshiped as a god of ceremonies. *See also* T'ieh-kuai Li.

Li T'ieh-Kuai (China) *see* T'ieh-Kuai.

Lia Fail (Celtic)

Deified object. The Stone of Destiny. It was brought to Ireland by the Tuatha De Danann and was placed at the Hill of Tara. Upon this stone are crowned the kings of Ireland. The voice of the stone will groan its mighty approval when a worthy king rides across it. It will remain silent if the ruler is unworthy.

Liaksit (Yakut People, Siberia)

Another spelling for Ajysyt, goddess of childbirth and domestic animals.

Libanza (Upotos People, Congo, Africa)

Evil deity. Supreme god. He is probably associated with the moon, since he allowed the moon to die only twice each month, but because mortals did not obey his wishes they had to die permanently.

Liber (Roman)

Also known as: *Bacchus.*

Fertility god. Liber is the Roman equivalent of the Greek god of wine, Bacchus. He is the husband of Libera, goddess of wine, who is identified with the Greek Persephone. Liber and Libera are worshiped with Ceres. *See also* Agdistis; Bacchus; Dionysus.

Liber Pater (Roman) *see* Dionysus.

www.ebook3000.com

Combined Practice

Warm - Up Exercises

Rotating the Sacrum

Rotating the sacrum is an excellent exercise to open the lower back and activate the spinal cord. Place one hand over the sacrum and the other over the pubic bone. Rotate the sacrum in a circle, 36 times in each direction. This movement activates the sacral pump.





Spinal Cord Breathing

Inhale and expand the chest, arms bent at the elbows and extended to the sides of the body. Exhale, tuck the tailbone under you and round the back, bringing the elbows toward one another in front of the chest. Smile. Inhale, expand the chest, tuck the chin in toward the throat, push the chin back and raise the crown and bring the arms out to the sides. Repeat this back and forth movement 36 times. This movement activates the cranial and sacral pumps, and loosens all the joints in the spine.

Libera (Roman) Goddess of wine. She is the wife of Liber.

Libertas (Roman) Goddess of liberty.

Libitina (Roman)
Goddess of death. Underworld goddess. She is worshiped in a similar way to Persephone.

Libya (Greek)
Libya is the daughter of the son of Zeus and Io, Epaphus, and Memphis, the daughter of the river god, Nile. She married Triton, the son of the sea god Poseidon, and Amphitrite, goddess of the sea. Libya is the mother of Lelex and by Poseidon, the twins Agenor and Belus. There is a possibility that she is the mother of Lamia by her son, Belus. *See also* Agenor (A); Belus; Lamia; Lelex.

Lidskialf (Teutonic) *see* Hlidskjalf.

Lidskjalf (Teutonic) *see* Hlidskjalf.

Lie-Kung (China) *see* Kei-Kung

Lif (Norse; Teutonic)
Also known as: *Life.*
Lif is the mortal who will survive after Ragnarok by hiding in the tree of life, Yggdrasil. He will father the new race of humans. His mate is Lifthrasir (meaning "eager for life"). In some versions of this myth, Lif is female and Lifthrasir is male. *See also* Ragnarok; Yggdrasil.

Life (Teutonic) *see* Lif.

Lifthrasir (Teutonic) *see* Lif; Ragnarok.

Ligeia (Greek)
She is the daughter of Achelous and Calliope and is one of the Sirens. *See also* Sirens.

Light (Phoenician) *see* Kolpia.

Light Bearer, The (India) *see* Ushas.

Lightning Man (Australia) *see* Mamaragan.

Ligoapup (Micronesia) *see* Ligobund.

Ligobund (Micronesia, Caroline Islands)
Also known as: *Luk.*
He is a creator god who made earth habitable, then gave birth to three children who were the first humans. In another rendition of this myth, it was Luk who did this, and it was his daughter (Ligoapup) and her daughter's son (who was made from the rib of this son) who married Ligoapup and started the human race. Another version tells that Ligoapup bore a girl first, then from her arm came a boy and from her eye another boy, then from her other eye another girl. In some versions Luk is thought to be the highest deity, and his wife is Inoaeman. He is also said to have a sister named Rat. Some legends say he is the lord of all who are evil and deceitful. Possibly Ligoapup is the same as Ligoububfanu from the island of Truk. She is the wife of Anulap and a creator deity. *See also* Ligoububfanu; Luk; Nareau; Yelafaz.

Ligoububfanu (Island of Truk, Micronesia)
Creator. The wife of Anulap who was possibly a creator also. Similar to, or may be the same as, Ligoapup of the Caroline Islands. *See also* Ligobund.

Likho (Slavic)
"Evil One." She has one eye and is the personification of evil. *See also* Lyeshy.

Liknites (Greek) *see* Dionysus.

Lil (Sumerian) *see* Enlil.

Lilavati (India) "Charming Woman." *See also* Devi.

Lilis (Hebrew) *see* Lilith.

Lilith *Lillity* (Hebrew)
Also known as: *Ailo, The Harlot, Lilis, Queen of the Demons.*
First woman. Queen of demons. As the first wife of Adam, she was rejected because she was not quite human. The ancient Hebrew people said that she refused to submit to Adam. She learned the sacred name "Yahveh" and therefore received wings and flew to Paradise. Her curse was that every child she had would die in infancy. After she tried to kill herself, the supreme god gave her power over all infants until they were eight days old, unless they were protected by the angels Sanoi, Sansenoi, and Sanmangalaph. In order to protect their new children, the early Hebrews hung an amulet around the child's neck, with "Sen, Sam, San," written on it. She has special power over illegitimate children, and she catches youths with her kisses. She is similar in nature to the Sumerian demon Alu under the guise of Ailo. She is also similar to the Babylonian deity Lamashtu. The word "lil" means a spirit of the same kind as the afreets (unclean spirits) of the Arabic People of the present day. Lillity, a feminine form, is a female evil spirit with the habits of a vampire in the demonology of the Jewish People. These gods or spirits rule the world of the night, darkness and evil and are hostile to humans. The only protection from them is through the use of magic spells and incantations. *See also* Agrat Bat Mahalat; Alu; Gallu; Gelu; Lilu.

Lilithu (Sumer, Baylonia) *see* Lilu.

Lilitu (Sumer, Babylonia) *see* Lilu.

Lilli (Sumer, Babylonia) *see* Lilu.

Lillith (Akkadian) *see* Lamassu; Lilith.

Lillity (Semite) see Lilith.

Lillu (Babylonia, Sumer) *see* Lilu.

Lilu *Lilithu, Lilitu, Lilli* (Babylon, Sumer)
Also known as: *Lilith* (possibly).
Demon. This spirit of lasciviousness entices women in their sleep. He is the counterpart of Lilli and may be related to Lilith of the Hebrews. Lilu is associated with the Babylonian demons Alu, Gallu, Lamashtu, Utukku.

Limnades (Greek)
The Limnades are dangerous nymphs who reside in lakes and swamps. *See also* Naiads.

Ling-Pao T'ien-Tsun (China)
Also known as: *Tao Chun.*
High god. Ruler of T'ai Ch'ing, the second heaven of the San

Ch'ing, Ling-Pao is the Guardian of the Sacred Books and the god of keeping time. *See also* San Ch'ing; Yu Ch'ing.

Lingodbhava (India) *see* Shiva.

Linus (Greek)
He is the son of Ismenius. Heracles, Orpheus and Thamyris were taught to play the lyre by Linus. Heracles, in a rage, killed his teacher with the lyre. *See also* Heracles; Orpheus.

Liomarar (Island of Yap, Micronesia)
Creator deity. She threw sand to create the island of Ulithi. Her daughter, Lorop, had three sons, one of whom is Motikitik (q.v.).

Lion with the Steady Hand (Celtic) *see* Llew Llaw Gyffes.

Liosalfar (Teutonic) *see* Alfar.

Lipaurus (Greek)
He is the father of Cyane who married Aeolus and became the mother of six sons and six daughters who married each other. *See also* Aeolus (B).

Lir (Irish)
Also known as: *Llyr* (Wales)
Lir is a well known local sea god who lived on the coast of Antrim. One of his children (by Penardun) who became notable is Manannan (Manawydan Ap Llyr). He is also the father of Bran by Iweridd. Some say that he is the father of Creiddylad or Cordelia. *See also* Creiddylad; Llyr; Manannan Mac Llyr.

Lisa *Leza, Lissa* (Dahomey, Fon People, Africa)
Also known as: *Chilenga, Mawa-Lisa* (androgynous), *Mawu, Mawu-Lisa, Reza, Rezha.*
Sky deities. Twins born to Nana Buluku. Lisa, the male, is god of the sun, sky and power, and is called the Chameleon. Mawu, the female is goddess of earth, moon and fertility. In some aspects this is an androgynous deity known as Mawu-Lisa. In male form, Mawu was a creator and part of the trinity Lisa, Ge, and Mawu. In another version Lisa is a mother goddess whose sons were Mawu (the sun) and Gou (the moon). *See also* Leza; Mahou.

Lit (Teutonic) *see* Dwarfs.

Little Cat (Egypt) *see* Bast.

Liu-Hai (China)
God of wealth. Liu-Hai is shown as a boy holding a string of gold cash over his head. A large tree-footed, money-distributing toad is biting the string.

Liu Pei (China) God of basket makers and straw shoe makers.

Livyathan (Hebrew) *see* Leviathan.

Ljod (Teutonic) *see* Angerboda; Gullveig.

Ljosalfaheim (Teutonic) *see* Alfheim.

Llampallec (Andean) *see* Naymlap.

Llaw Erent (Celtic) *see* Llud.

Llaw Gyffes (Celtic) *see* Llew Llaw Gyffes.

Llawerein (British) *see* Llud.

Llediaith (Celtic) *see* Llyr.

Lleu (Celtic) *see* Llew Llaw Gyffes.

Lleu Llaw Gyffes (Celtic) *see* Llew Llaw Gyffes; Lugh.

Llew (Celtic) *see* Arianrhod.

Llew Llaw Gyffes *Lleu Llaw Gyffes* (Celtic)
Also known as: *Llaw Gyffes, Lleu, Llew, Lugus.*
Llew Llaw Gyffes, a sun deity and corn divinity, is the son of Arianrhod and possibly her brother, Gwydion. His twin brother, Dylan, was thrown into the sea by Arianrhod or his uncle Math, where he became a sea deity. Gwydion saved Llew, disguised him as a shoemaker and raised him. Arianrhod placed a "guise" on her son which ruled that he would never have a name, a mortal wife, nor weapons. Gwydion, through the use of trickery was able to revoke the "guise." Gwydion and Math made a beautiful wife for Llew Llaw Gyffes from a tree and an assortment of blossoms. Her name is Blodeuwedd. She was born without a soul and soon betrayed her husband by sleeping with the lord of darkness, Gronw Pebyr. In order to kill her husband she had to trick him into revealing the secret of his vulnerability. He was only vulnerable when he had one foot on a cauldron, the other on a buck (or billy-goat), with his hair tied to an oak branch. In other versions, the setup is similar but the spear used to kill him had to be forged on a specific day a year before death. The scene was finally set and Gronw Pebyr aimed the weapon and struck Llew Llaw Gyffes in the groin. His hair tied to the oak branch saved him from touching the ground. He turned into an eagle. Gwydion tended his wound and with his magic returned the man to his mortal form. Llew Llaw Gyffes returned to his home and killed Gronw Pebyr. In other renditions, Llew Llaw's vulnerable spot, like Achilles, is his heel. Llew Llaw means "Lion with the Steady Hand." He is associated with the eagle. Compare Llew to the Irish Lugh. *See also* Arianhod; Blodeuwedd; Gwydion; Math.

Llud *Lud, Ludd* (British)
Also known as: *Argetlam* (Celtic; "The Silver Handed"), *Ereint, Llaw Erent* (Gaul), *Llawerein* (British; "The Silver Handed"), *Llud Llaw, Nodens, Nuada, Nud, Nudd* (Welsh).
The city of London was named in honor of the river god Llud. The city's original name was Caer Ludd, and the temple of Llud was atop Ludgate Hill. It is thought by some researchers that Llud displaced the earlier goddess of the Thames, Tamesis. Llud has an artificial silver hand. Compare Llud to Nuada.

Llud Llaw (Celtic) *see* Llud; Nuada.

Llwch Lleu (Celtic, Irish, Welsh) *see* Lugh.

Llyr *Ler* (Wales), *Lir* (Irish)
Also known as: *Llediaith, Llyr Marini.*
Llyr is the same as the Irish sea god, Lir. *See also* Bran; Branwen; Manwydan Ap Llyr.

Lmahuika (Polynesia)
Underworld deity. This goddess rules the edges of the underworld. She may be same as Locha, Lothia, and Miru.

Lmylitta (Babylon) Goddess of fertility. Goddess of childbirth.

www.ebook3000.com

Lnyiko (Cameroon)
God of divination. He is the son of Nyokon and Mfan who was driven from heaven by his father.

Lo Ching Hsin or T'ien Pao (China) *see* Yu Ch'ing; Yuanshih T'ien-Tsun.

Lo-lupe (Hawaii)
Also known as: *Olo-pue, Ololupe.*
God of Maui. Conductor of the souls of dead chiefs. He is invoked in the rite of deification of the dead and resurrection of the dead. Warriors greatly fear this god. Lo-lupe is depicted in the form of a lupe (kite) shaped like a sting ray. Other conductors of the souls of dead chiefs are Ka-onohi, also called Ka-onohi-o-ka-la (the eyeball of the sun) and Ku-waha-ilo (Ku of the maggot-dripping mouth). *See also* Ku and Hina.

Loa (Polynesia, Marshall Islands)
Creator. Loa created everything with the aid of a seagull who wove the dome of heaven.

Locana (India)
"Buddha Eye." *See also* Akshobhya; Dhyani Buddhas; Maitreya.

Locha (Polynesia) *see* Lmahuika; Lothia; Miru.

Lodar (Teutonic) *see* Loki.

Lodbrok (Teutonic) *see* Ragnar Lodbrog.

Lodder (Teutonic) *see* Loki.

Lodur (Teutonic) *see* Loki.

Lofn (Norse; Teutonic)
Goddess of love. Some say she is the goddess who smiles on illicit unions and sparks passionate love. Others say her task is to remove obstacles from the path of lovers. In some versions, she is an attendant of Frigg. *See also* Frigg.

Loge (Teutonic) *see* Logi.

Logh (Celtic) *see* Aesar (B).

Logi *Loge* (Norse, Finnish; Teutonic)
Also known as: *Flames.*
He is the giant fire god who beat Loki in an eating match in the court of Utgard-Loki. Logi is identified with Loki (q.v.).

Logos (Egypt, Alexandria)
Also known as: *Jesus.*
Gnostic version of the son of god. Aspect of Jesus. Arius of Alexandria attempted to revive Sabellianism about 318 C.E. He said that god's son, Logos, created the world. Logos is generally regarded as meaning "reason." Logos is associated with Sophia (reason and wisdom). *See also* Jesus; Sarasvati.

Loha-Mukha (India)
A race of iron-faced male cannibals who each have one leg.

Loka (Buddhist, Hindu; India).
In Tibetan Buddhism, Loka is one of the three divisions of the universe. In Hinduism, there are three or seven Lokas, heaven, earth and hell, often called Tri-Loka (Triloka), and Sapta-Loka, the seven-world universe. There is mention of an eight-world universe and also detailed descriptions that mention fourteen Lokas, seven that rise above the earth and seven that descend from the earth. The seven worlds of Sapta-Loka are the earth known as Bhur-Loka; the abode of the Munis and Siddhas, located between the earth and the sun and known as Bhuvar-Loka; Indra's heaven, located between the sun and the pole-star, known as Swarga or Svar-Loka; the abode of Bhrigus and other saints, Marar-Loka; the abode of Brahma's children, Jana-Loka; the abode of the Vairajas (also known as Vairagis), the ascetics, known as Tapa-Loka and Pitri-Loka; Brahma's abode, known as Satya-Loka, where he resides with other immortals. Other realms are Soma-Loka, the abode of the moon and planets, Gandharva-Loka for heavenly spirits, Rakshasa-Loka for demons and Pishacha-Loka for imps. The Lokaloka mountains, located beyond the farthest of the seven seas, divides the visible world from the infinite darkness beyond. *See also* Gandharvas; Meru Mountain; Naraka (B); Pretas; Swarga; Vaikuntha; Yama.

Lokaloka Mountains (India) *see* Loka.

Lokamatri (India) *see* Gauri.

Lokanatha (India) *see* Samantabhadra.

Lokapalas, The (Brahmanic, Buddhist, Hindu, Vedic; India)
Also known as: *Great Kings,* (Buddhist), *Jig-rten-skyon* (Tibet).
This is a name given to the Vedic deities who became protective spirits under Brahmanism. They are the guardians of the eight quarters of the world. In the Buddhist world, they live around Meru Mountain and guard the entrance to the Buddhist paradise of Sukhavati. The Lokapalas are also known as the eight Hindu gods and their elephants. They guard the eight main points of the compass. Indra and his elephant Airavata (in the *Ramayana,* "Virupaksha") guard the east. Yama and his elephant Vamana (in the *Ramayana,* "Mahapadma") guard the south. Agni and his elephant Pundarika guard the southeast. Sometimes Kuverva is substituted for Agni. Surya or Nirriti and the elephant Kumuda guard the southwest. Varuna and his elephant Anjana (in the *Ramayana,* "Saumanasa") guard the west. Vayu and his elephant Pushpa-danta guard the northwest. Kubera and Savabhauma (in the *Ramayana,* "Himapandara") guard the north and either Soma or Prithiva or Shiva and Supratika guard the northeast. The demon Ravana claims that he is the guardian of the fifth world, the center. Compare the Lokapalas to the male guardians of the gates of Bardo, *see also* Amrtakundali. *See also* Agni; Chakravala (Buddhist Universe); Dhartarastra (regarding the Four Great Kings); Dikpalas; Gandharvas; Ganesha; Indra; Niritti; Prithiva; Ravana; Shiva; Soma; Sukhavati (Paradise); Surya; Takshaka; Varuna; Vasuki; Vayu; Virudhaka; Virupaksha; Yama.

Loke (Teutonic) *see* Fjalar; Loki.

Lokeswar (Nepal) *see* Lokeswara.

Lokeswara *Lokeswar* (Buddhist; Nepal, India)
Also known as: *Avalokitesvara.*
Lord of the world. There are said to be one hundred and eight forms of Lokeswara, who is a form of Avalokitesvara. This form was assumed when the Buddhist pantheon incorporated

Shiva. One form is Chintamani Lokeswara, the Lokeswara of the wishing gem, who is said to dispense jewels and wealth to his devotees. Chintamani is richly ornamented. He wears a sacred thread of jewels and earrings and a full blown lotus at each shoulder. *See also* Avalokitesvara; Shimhanada Lokeshara; Sristikanta Lokeswara.

Loki (Norse; Teutonic)

Also known as: *Fjalar, Loder, Lodur, Loke, Lokkju, Lopter, Lopti, Sagloki, Suttung, Thok* (possibly), *Utgard-Loki.*

In some legends Loki appears evil and in others a faithful ally of Odin and other gods. He is known as a culture hero, and one of the Aesir. In other myths, he is a fire and strife demon, and a trickster. As Utgard-Loke, he was first conceived a fire demon, who also caused earthquakes and optical illusions. He may also have originated as a giant, though other myths indicate he was related to the dwarfs. He is said to be the father of Neri (Norine). In some myths Loki has a brother named Byleipt, Byleipter, or Byleist, although Loki was called Lopter at the time. In some versions, as Loder, he was the brother of Odin and Hoener. His mother is Laufey and his father Farbauti, who is also known as the father of Bleifstr, and Helblindi (a name given to Odin). He became the god of strife and the spirit of evil, possibly because he swallowed the half-burned heart of Gullveig. Myth has it that after doing so, he gave birth to the wolf Fenrir, the Nithog serpent and Hel, mistress of the underworld, all considered monsters. He caused the death of Balder by convincing the blind Hoth to throw mistletoe at him, the only thing said to have been able to kill him. Balder would have been allowed to leave Hel if every living thing would weep for him. When Loki heard of this edict, he took on the form of a woman and became the one exception and would not weep for him. He is said to have originally obtained Thor's hammer from the dwarfs and is also credited with the invention of the fishing net. Once, in the form of a mare he enticed away the horse of the giant who was building the walls of Asgarth in order to make him break his contract. In this legend he gives birth to Othin's eight-legged horse, Sleipnir. He has been called the Sly One, the Trickster, the Shape Changer, and the Sky Traveler and is said to have flown around in Freyja's falcon feathers. He was finally chained to a rock, where a serpent dripped venom on him and where he is to remain until the Twilight of the Gods (also known as Ragnarok). His wife, Sigyu stays with him and catches the poison in a dish. In the holocaust at the end of the world, Loki will lead the forces of Midgard. Midgard is the part of the world inhabited by men, imagined as a fortress encircled by a huge serpent, built by the gods around the middle region of the universe. *See also* Aeigir; Aesir; Balder; Fafni; Farbuti; Fenrir; Fjalar; Fornjotnr; Freyja; Gullin-Bursti; Gullveig; Gungnir; Heimdall; Hel; Helblindi; Henir; Huehuecoyotl (Aztec); Hugi; Idun; Jormungandr; Logi; Midgard; Neri; Nott; Odin; Ragnarok; Ran; Thok; Thor; Vili; Ymir.

Lola (India) Goddess of fortune.

Lone Man (Native North American) *see* Maninga.

Longo Rongo-Ma-Tane (Polynesia) *see* Lono; Rongo.

Loni (Teutonic) *see* Dwarfs.

Lono (Polynesia, Hawaii)

Also known as: *Longo Rongo-Ma-Tane, Ono, Rongo*

God of thunder, rain and darkness. God of fertility. God of agriculture. God of singing (in the Marquesas). One of the triad with Kane and Ku. He is associated with cloud signs and the phenomena of storms. He is offered first fruits in Polynesia. His sister is Laka, the goddess of the wildwood. In Hawaiian mythology the tale is told that one day, Lono came down to a rainbow in search of a wife. He found her and they lived happily together until he heard that she had been unfaithful. He beat her to death. Later, he felt very sorry that he had killed her. To assuage his heaviness of heart, he initiated games and feasts in her honor. Lono climbed into his canoe (filled with provisions) and sailed away, promising to return one day with a bountiful island. So it was that it became a tradition to hold an annual festival of five days full of feasts, processions, fun and sports. In a variation, Lono sent his two brothers from island to island in search of a wife for him. They came upon a beautiful woman known as Ka-iki-lani who lived with the birds in a breadfruit grove. Lono descended on a rainbow and took her as a wife. She became the goddess Ka-iki-lani-ali'i-o-Puna. They lived a blissful life and often surfed together. An earth chief made love to Lono's woman and the pardisical environment was destroyed. Infuriated, he beat her to death even though she proclaimed her innocence. In this rendition, as in the prior one, he feels sorry, initiates games in her honor, hops into a canoe and sails away. Prayers are offered to Lono for rain, abundant crops, or escape from illness and travails. His symbol is a straight wooden post ten to fifteen feet long with approximately a ten-inch circumference. It is topped by a knob, which some say represents a bird. Near the top a cross-piece about sixteen feet long is tied. Feather wreaths hang from it and at each end lengthy streamers of white tapa cloth hang. This representation is called Lono-makua (Father Lono). Lono is identified with Rongo (q.v.). *See also* Hika-po-loa; Hina-ula-ohia; Kane; Ku.

Lopamudra (India) *see* Agastya.

Lopemat (Latvia) Creator and goddess of cattle.

Lopter (Teutonic) *see* Loki.

Lord Nose (Aztec) *see* Yacatecuhti.

Lord of Elephantine (Egypt) *see* Khnum.

Lord of the Bed (China) *see* Ch'uang-Kung.

Lord of the Dance (India) *see* Nataraja.

Lord of the Gallows (Teutonic) A title for Odin.

Lord of the Land of Tehennu (Egypt) *see* Ash.

Lord of the Land of the Olive Tree (Egypt) *see* Ash.

Lord of the Magic Tooth (Maya) *see* Ahau-Chamahez.

Lord of the Regent of Death (Mexico) *see* Miclantecutl.

Lord of the Winds (China) *see* Yu Shih.

Lords of the Day Hours (Aztec)

The hours of day and night are ruled by gods. There are thirteen Lords of the Day. The Lords of the Day are (1) Xiuhte-

www.ebook3000.com

cuhtli, (2) Tlaltecuhtli, (3) Chalchihuitlicue, (4) Tonatiuh, (5) Tlazolteotl, (6) Teoyaoimquit, (7) Xochipilli, (8) Tlaloc, (9) Quetzalcoatl, (10) Tezcatlipoca, (11) Mictlantecuhtli, (12) Tlauixcalpantecuhtli, and (13) Ilamatecuhtli. *See also* Lords of the Night Hours, and individual deities listed.

Lords of the Night Hours (Aztec)
There are nine Lords of the Night Hours. They are (1) Xiuhtecuhtli, (2) Itzli, (3) Piltzintecutli, (4) Cinteotl, (5) Mictlancihuatl, (6) Chalchihuitlicue, (7) Tlazolteotl, (8) Tepeyollotl, and (9) Tlaloc. *See also* Lords of the Day Hours, and individual deities listed.

Lorop (Micronesia)
She is the daughter of the creator, Liomarar. Lorop has three sons, one of whom is Motikitik, the hero god. *See also* Lowa; Motikitik.

Lorride (Teutonic) *see* Thor.

Lorridi (Teutonic) *see* Thor.

Lotan (Ugarit) *see* Baal; Leviathan.

Lothia (Loyalty Islands, Polynesia.)
Also known as: *Lakemba, Locha.*
Deity of the afterworld. Lothis is the goddess who rules the afterworlds. She might be same as Miru, or Lmahuika. *See also* Hiro; Miru; Rohe; Urutaetae.

Lothurr (Teutonic) "The Fighter." *See also* Thor.

Loucetius (British, Celtic) *see* Cocidius; Tuetates.

Louhi (Finnish; Lapland)
Goddess of evil. Louhi is a sorceress who rules the land of Pohja. According to some she bargained with Vainamoinen the magician and musician to exchange the talisman sampo for her daughter. She reneged on her bargain and allowed her daughter to marry the smith Ilmarinen, who made the magic sampo. In the Lapland version of this tale, she is the mistress of Pohjoa the sorcerer and a goddess of fog and wind. *See also* Lemminkainen; Pohja; Sampo; Vainomoinen.

Louquo (Carib People)
First man. He came down from the sky and after creating humans from his body, returned to heaven.

Loviatar (Finnish)
Goddess of disease. She is the wife of the wind and mother of nine monsters of disease. She is the daughter of the Lord of Tuonela (the underworld), who is also the god of death, Tuoni, and Tuonetar, and the sister of Kivuatar, Kipu-Tytto and Vammater. They live in Manala. Loviatar is described as having a large face and wrinkled skin. *See also* Manala; Tuonela; Tuonetar; Tuoni.

Lowa (Micronesia)
Creator god. It is not certain whether Lowa came from the sky or the sea. He created the Marshall Islands by emitting the sound "Mmmm." The first humans, a boy and a girl, issued forth from a blood blister on his leg. *See also* Lorop; Tangaloa.

Loxias (Egypt) *see* Apollo.

Loz (Babylon)
With Nergal and Ninmug he ruled Meslam, the underworld. *See also* Nergal.

Lu-Hsing (China)
The god of salaries. Born mortal, Lu-Hsing was deified and given immortality. He is associated with the gods of happiness and long life. His symbol is the deer, Lu, on which he is often mounted.

Lu-ma *Gita, Ghirdhima* (Tibet)
Goddess of music and song. *See also* Gita.

Lu Pan *Lupan* (China)
God of carpenters. His two wives are the goddesses of lacquer-workers. One wife is red and the other wife is black. Once, Lu Pan made a wooden falcon that was able to fly.

Lu Tung-Pin *Lu-Tung-Pin* (China)
Also known as: *Ancestor Lo, Lu Tsu, Lu Yen.*
One of the Eight Immortals. God of Barbers. In many legends about Lu Tung-Pin, he plays the role of punishing the wicked and rewarding the good. In some versions, as Ancestor Lo he is a god of barbers. Lo is either a substitute for Lu-Tung-Pin or an addition. Ancestor Lo is credited for shaving the head of an emperor whose skin was sensitive. He is usually shown as a young man in robes, carrying a fly-chaser and a sword. *See also* Arhats; Eight Immortals; Han Chung-Li; Ho-hsien-ku.

Lubrican (Celtic) *see* Leprechaun.

Lubukhanlung (Dhammai People; India)
Lubukhanlung, Sangso-Dungso and Kimbu-Sangtung are the children of the first mortals, Abugupham-Bumo and Anoi-Diggan-Juje. Their grandparents are the brother and sister frogs, Lujjuphu and Jassuju. *See also* Shuznaghu.

Lubumba (Africa) *see* Leza.

Luchta (Irish) *see* Credne.

Luchtaine (Irish) *see* Credne; Goibniu.

Lucifer (Latin)
Name of the morning star. The name is also used for Satan. Luciferians are fallen angels. *See also* Kanaloa; Satan.

Lucina (Greek, Roman)
Also known as: *Juno.*
This goddess of light is Juno. As Lucina she presides over the birth of children. *See also* Diana; Eileithyia; Juno.

Lud *Ludd* (Celtic) *see* Llud; Nuada.

Ludd (Celtic) *see* Don; Lud.

Ludjatako (Creek People, North America)
Deified animal. The Giant Turtle.

Lug (Celtic) *see* Lugh.

Lug Lonnbemnech (Celtic) *see* Lugh.

Lugal-Banda *Lugalbanda* (Sumer)
He was the god and shepherd king of Uruk, where he was worshipped for over a thousand years. Some say he was the third king of Uruk after the Deluge. One of his tasks was to protect

Gilgamesh. The adventures of Lugal-Banda are similar to those of Gilgamesh. He was said to have conquered the Dragon Zu. Lugal-Banda is possibly the same as Lugalmeslam. *See also* Gilgamesh; Zu.

Lugalabdubur (Babylonia) *see* Marduk.

Lugaldimmerankia (Babylonia) *see* Marduk.

Lugaldurmah (Babylonia) *see* Marduk.

Lugallanna (Babylonia) *see* Marduk.

Lugalmeslam (Sumer) *see* Nergal.

Lugalugga (Babylonia) *see* Marduk.

Lugas (Celtic, Irish, Welsh) *see* Lugh.

Lugeilan (Caroline Islands)

God of knowledge. Son of Aluelop (also known as Luk). First teacher of mortals. He taught the arts of tattooing and hairdressing. He also taught people how to cultivate crops.

Lugh *Lug* (Celtic, Irish, Welsh)

Also known as: *Find* ("Fair-haired One"), *Lamhfhada* ("of the Long Arm"), *Lleu Llaw Gyffes, Llwch Llawwynnawc* (Welsh), *Lug Lonnbemnech* (Many Blows), *Lug Samildanach* ("Many-skilled"), *Lugas.*

God of sorcery, poetry, history, and carpenters. Solar deity. Lugh "of the many skills" is the grandson of the Tuatha De Danann Dia'necht and also the grandson of the Fomosian Balor, whom he eventually killed. He is the son of Cian, a Tuatha De Danann, and the Fomorian moon goddess, Etlinn. He is also the brother of Dagda and the divine father of the hero Cu Chulain. He was raised by the sea god, Manannan Mac Llyr. Lugh is the custodian of the magic spear, one of the four talismans of the Tuatha De Dananns. The spear has a mind of its own, and it strikes the enemy of its own will. Along with the spear, when in battle, Lugh wears a helmet and carries a shield that magically protects him from being wounded. Lugh was the first person to engage in battle on horseback. He rides a horse named Enbarr, a gift from his foster father. Lug appeared at King Nuada's court with a company of fairies and offered to assist the Tuatha De Danann's in their battle to overcome the evil giants, the Fomorians. As one had to have a skill to be a Tuatha De Danann, he was admitted only after he recited his talents and accomplishments. It followed that he led the group to victory in the Second Battle of Magh Tuiredh, and after the death of Nuada he became the king of the Tuatha De Danann. In some versions of this story, Nuada relinquishes the throne to Lugh prior to the battle. Constantly fighting darkness, he avenged his father Cian's death and also killed his demonic grandfather Balor, using a slingshot. Lugh is depicted as a handsome, youthful, athletic man and is associated with the eagle, his horse, Enbarr, and his dog, Failinis. Lugh is thought by some to be the Romano-British Mercury. He is equivalent to the Welsh Lleu Llaw Gyffes. Lugh is associated with Arianrhod. Compare Lugh to Odin and Varuna. *See also* Balor; Bress; Cailleach Bheare; Cian; Cu Chulain; Dagda; Dia'necht; Manannan Mac Llyr; Mercury (A); Mercury (B); Tuatha De Danann.

Lugus (Gaul, Celtic)

Llew Llaw Gyffes was known as Lugus in Lyons. His festival Lugnasad, was held on the first of August. *See also* Llew Llaw Gyffes.

Lujjuphu (India) *see* Shuznaghu; Zumiang-nui.

Luk (Caroline Islands, Micronesia)

Also known as: *Lugeilan, Luke-Lang, Lukelang, Lukelong, Yelafath, Yelafaz.*

Creator god of all things. God of knowledge. His wife is either Inoaeman or Ligoapup, who could also be his sister. His son by one of the women is Olifat. Luk took trees and plants from heaven and set them on the barren earth. He also taught mortals to cultivate crops. Luk is particularly associated with the coconut palm. *See* Ligobund; Lukelong; Nareau; Olifat; Yelafaz.

Luke-Lang (Micronesia) *see* Luk.

Lukea (Greek) *see* Artemis.

Lukelang (Micronesia) *see* Luk.

Lukelong (Micronesia)

The goddess Lukelong existed in the beginning. She created the heavens and then the earth. *See also* Luk.

Lullu (Babylon) First Man. *See also* Mami.

Lumauig (Oceanic) *see* Maui.

Lumha (Sumer)

Also known as: *Ea, Enki, Lamech.*

Patron of singers. Under the name of Enki, Lumha is the father of Jabal, the patron of tents and flocks, Jubal, patron of music, and Tubal-cain, patron of the forge. *See also* Ea; Enki.

Lumimu-Ut (Oceanic)

Creator. At first there was only the ocean and a rock. From the rock came a crane, then a female deity who was created from the sweat of this crane. From a place called "Original Land" she took two handfuls of earth. She spread it on the rock and created the world. Then she created plants and trees. From her union with the wind she conceived a son, and through incest with this son she bore all the gods. The Samoan and Melenesian legends have a similar story of everything coming from a stone, and the belief that gods and men were born from incest between mother and son. *See also* Tane.

Luna (Roman)

Also known as: *Artemis.*

Goddess of the moon. *See also* Artemis; Selene.

Lung (China)

Also known as: *Lung-Wang.*

Serpent dragon and one of the Ssu-ling. It can become invisible or change color and size. Lung is usually shown bearded, his head with horns, a scaly body, and claws. Sometimes he is shown as a human. Lung could be part of, or the same as, the Dragon Kings (q.v.). He is similar to the Nagas (q.v.).

Lung-Wang (China) *see* Dragon Kings; Lung.

Luojatar (Finnish) *see* Luonnotar.

Luonnotar *Luojatar* (Finnish)

Also known as: *Synnytar.*

www.ebook3000.com

Nature deity. She is the daughter of Ilma, god of the air. Luonnotar created earth and the heavens from the eggs of a duck. One half of the eggs became the earth, the other half, the heavens. The yolks became the sun and the whites the moon. Her son Vainamoinen remained in her womb until he became bored, thirty years later. She has two other sons, Ilmarinen and Lemminkainen. *See also* Ilma; Vainamoinen.

Lupa (Roman)
Also known as: *Acca Larentia.*
Lupa, meaning "wolf," is a nickname for the goddess Acca Laurentia (q.v.).

Lupan (China) *see* Lu Pan.

Lusin (Armenian)
This is an ancient name for the Armenian moon goddess.

Luttchmeen (India) *see* Lakshmi.

Lycaon (Greek)
King of Arcadia. His parents are Pelasgus and either Meliboea or Cyllene. His siblings are Maenalus, Nyctimus, Pallas, and forty-six other brothers. *See also* Acamas (B); Maenalus.

Lycaste (Greek)
She is the daughter of the last king of Troy, Priam, and the wife of the Argonaut Polydamas.

Lycastus (Greek)
He is the grandson of Zeus and Europa. His parents are Minos, king of Crete, and Pasiphae, who mated with a bull and became the mother of the Minotaur. His siblings are Acacallis, Androgeus, Ariadne, Catreus, Deucalion, Eurydale, Glaucus, Phaedra and Xenodice. Lycastus wed Ida. Some say Lycastus' son Minos II was really the son of Lycastus' father Minos. *See also* Acacallis; Ariadne; Minos; Pasiphae.

Lycean (Egypt) *see* Apollo.

Lycius (Greek) This is an epithet of Apollo, the wolf god.

Lycotherses (Greek)
King of Illyria. He was the second wife of Agave, who murdered him so her father Cadmus could take over the throne. *See also* Agave; Cadmus.

Lycrus (Greek)
He is the son of the renowned warrior Abas. *See also* Abas (A); Anchises.

Lycurgus (A) *Lycus* (Greek)
He is the son of Pheres and Periclymene (Clymene). His maternal grandfather, Minyas, was said to have built the first treasury. His siblings are Admetus, Idomene, Lycurgus, and Periopis. Lycurgus was resurrected after death by Asclepius. *See also* Admetus; Ino; Minyas.

Lycurgus (B) (Greek)
King of Arcadia. For lineage details *see also* Iasus (A).

Lycurgus (C) (Greek)
He is the son of Heracles and Praxithea, one of the fifty daughters of Thespius. Forty-eight of Praxithea's sisters slept with Heracles in one night.

Lycurgus (D) (Greek)
King of the Edonians of Thrace. His great enemy was Dionysus. When he refused to give him shelter, the great god Zeus blinded him and drove him insane. In his insanity, Lycurgus committed several atrocities. He killed his son, attempted to rape his mother, and cut off his own legs. The cause of his death is unknown. He might have killed himself, or he was thrown to the wild animals.

Lycurgus (E) (Greek)
He is the son of Pronax and brother of Amphithea.

Lycurgus (F) (Greek) An Athenian orator.

Lycus (A) (Greek)
King of Thebes. He is the possible son of Poseidon and Celaeno, and the husband of Dirce. *See also* Amphion; Antiope; Epopeus; Zetes.

Lycus (B) (Greek)
One of the fifty sons of Aegyptus. *See also* Aegyptus; Danaids.

Lycus (C) (Greek) He is the Centaur son of Ixion and Nephele.

Lycus (D) (Greek) King of Libya. His daughter is Callirrhoe.

Lycus (E) (Greek) He is the son of Ares.

Lyeshy *Lyeshie* (Slavic) *see* Leshy.

Lyfjaberg (Norse; Teutonic)
Also known as: *Hill of Healing.*
Hill of healing. Every woman who climbs this hill will be cured. It is also the hill where Menglad rules with her attendants. Her hall is called Lyr.

Lykeious (Greek) *see* Apollo.

Lynceus (Greek)
A son of Aegyptus, whose life was saved by his wife Hypermnestra when her sisters murdered all his brothers. He became king of Argos. *See also* Abas (A); Aegyptus; Argonauts; Danaus; Perseus.

Lyngvi (Norse; Teutonic)
The island on Lake Amsvartnir where Fenrir is bound and waiting for Ragnarok. *See also* Fenrir; Ragnarok.

Lysippe (A) (Greek)
She is one of the fifty daughters of Thespius.

Lysippe (B) (Greek)
Her parents are Proetus and Stheneboea or Anteia. She married Melampus. *See also* Proetus; Melampus.

Lyr (Irish) *see* Manannan Mac Llyr.

Lyrus (Greek) *see* Aeneas.

Lysianassa (Greek)
Her father is Polybus, the son of the messenger of the gods, Hermes, and Chthonophyle. *See also* Adrestus; Hermes; Polybus.

Lysidice (Greek)
Her parents are Pelops and Hippodameia. She became the

mother of Hippothoe by Mestor, the son of Andromeda and Perseus. *See also* Pelops.

Lysimache (Greek)
Lysimache is the daughter of Abas. She is the possible wife of Talaus, the Argonaut. *See also* Abas (B); Adrestus.

M

M (Maya)
He is the god of travelers who corresponds to Yacatecuhtli (q.v.).

Ma-Bellon (Roman) *see* Arinna.

Ma-Hina (Hawaii) *see* Hina.

Ma-Mien *Mamien, Ma-Vien* (China)
Also known as: *Asvamuttakha* (India), *Bach-Ma* (Indo-China), *Horse-Face.*
"Horse-Face." Protector deity. With his companion Niu-t'ou, meaning "Ox-head," he conducts people to hell. Ch'eng-Huang, the god of walls and ditches, controlled Ma-Mien. In some versions of this myth it is the two Wu-ch'ang who conduct the souls to hell. (*See* Wu-ch'ang.) In some versions Ma'mien and Niu-t'ou are demons. Ma-Mien is shown in the form of a white horse. He is opposed by the Door Guards. *See also* Men Shen; Niu-Y'ou; Yama Kings.

Ma-Mo (Tibet)
Female disease spirits who are often the spouses of malignant demons.

Ma-Negoategeh *Ma Negoategeh* (Iroquois People, North America)
Evil deity called the "The Evil Twin."

Ma-Ngee (Africa) *see* Ngewo-wa.

Ma-p'am-pa (Tibet) *see* Ajita.

Ma-Riko-Riko (Maori)
First woman. She was created by Arohi-rohi (Mirage) from the warmth of the sun.

Ma-tshiktshiki (Oceanic) *see* Maui.

Ma-Tsu (China) *see* Ma-zu

Ma-tsu-p'o (China) *see* T'ien-hou.

Ma-vien (China) *see* Ma-mien.

Ma-Zu (China)
Also known as: *Ma-Tsu.*
Goddess of fishermen and sailors. Ma-zu began her life as a devout young woman in the eleventh century C.E. She is still popular in Hong Kong and Taiwan.

Maa (A) (Egypt) *see* Ap-Taui.

Maa (B) (Egypt) *see* Maat.

Maa-an-f (Egypt) *see* Assessors.

Maa-Nefert-Ra (Egypt)
The name of the Twelfth Hour of Tuat. The city is called Khepert-kekui-khaat-mest and the pylon Then-neteru. This place is where the god is reborn in the form of Khepera, Nu, Nut, Hehu and Hehut. The deities mentioned are Ka-en-Ankh-neteru, Af, and Amkhiu. The god is accompanied by twelve unnamed goddesses and twelve gods who praise Ra. Other gods mentioned are Hehu, Hehut, Nehui, Ni, Nesmekhef, Nu, Nuth. *See also* Tuat.

Maa-thet-f (Egypt) *see* Aaru.

Maa-uat (Egypt) *see* Aai.

Maahes (of Nubian origin; Egypt)
This lion-headed god who was worshiped in Egypt, may be the son of Ra and Bast. He is shown as a lion or lion-headed man.

Maan-Emoinen (Finnish) *see* Rauni.

Maanda (Africa) *see* Ngewo-wa.

Maanegarm (Teutonic) *see* Hati.

Maat (Egypt)
Also known as: *Maa, Maet, Maht, Mat, Maut.*
Goddess of truth and justice. Weigher of souls. Maat is the daughter of the sun god Ra and the female counterpart and perhaps wife of Thoth. When Ra created the world, he brought truth and justice, in the embodiment of Maat, to mortals. As well as being the regulator of the path of the sun, she represents the order which rules the worlds through balance. The foundation of Egyptian religion was based on the necessity of practicing Maat to preserve truth, justice and social order. Maat led the dead souls to the Hall of Judgement to appear before Osiris. Her symbol is the feather, used to counterbalance the hearts of the departed. In her hall there are forty-two judges or assessors (regarded as priests), each of whom the dead must convince that he or she is "maaty" and has not committed any one of forty-two unacceptable acts. Maat's opinion is taken into consideration in making the decisions. The god Anubis places the

www.ebook3000.com

departed one's heart on one pan of the scale and the feather on the other pan. Next, the god Thoth reads the verdict while the monster Amit stands in attendance ready to chew up the hearts of the guilty. This is not the end of the ordeal for the departed soul. The next step is to name the parts of the door which open into the region of the blessed, followed by other questions. Maat is shown in human form wearing a headdress with an ostrich plume. She is also depicted with a feather taking the place of her head. The feather of Maat symbolizes truth. Maat is associated with Amen-Ra. *See also* Aati; Ament; Amentet; Amit; Anubis; Apet; Mafdet; Negative Confession; Osiris; Ra; Thoth.

Maati (Egypt) *see* Aati.

Maati-f-em-tes (Egypt) *see* Assessors.

Maaty (Egypt) *see* Aati.

Mab (Celtic) *See* Maeve.
Mabinogion, the (Celtic). *See also* Arianrhod.

Mabon (British, Celtic, Irish, Welsh)
Also known as: *Mabonagrain, Mabuz, Maponos* (Wales).
God of music. Possibly a god of hunters. Mabon, "the divine youth," is the son of the river-goddess Modron. The tale is told that he was kidnapped from his mother when he was three days old. It took many adventures before his rescuers found him (inside a salmon) and released him from the Otherworld. *See also* Angus; Matrone.

Mabonagrain (Celtic) *see* Mabon.

Mabuz (Celtic) *see* Mabon.

Mac Cecht (Irish) *see* Banbha.

Mac Cuill (Irish) *see* Banbha.

Mac Greine (Irish) *see* Banbha.

Mac Ind Og (Celtic, Irish) *see* Angus.

Mac Oc (Celtic) An alternate name for Angus (q.v.).

Mac Og (Celtic, Irish) *see* Angus.

Macar (Greek) *see* Aeolus (A); Heliades.

Macareus (Greek)
He is one of six brothers and seven sisters who are the children of Aeolus of Magnesia, who was the ancestor of the Aeolians and Enaret. Macareus committed suicide after having an incestuous relationship with his sister Canace. *See also* Canace (for the names of his other siblings).

Macha (Celtic)
Fertility goddess and goddess of war. Macha is an early fertility-goddess of Ireland, the eponym of Ulster's capital. She is also a warrior-goddess, who paralyzed the enemy troops because they made fun of her. Macha is comparable to Epona and Rhiannon. She is associated with the Morrigan. *See also* Epona; Mab; Morrigan; Rhiannon.

Machaon (Greek)
He was a surgeon and a co-ruler of parts of Thessaly. His parents are the healer Asclepius and Epione, the daughter of Meropes. His siblings are Acesis, Aegle, Hygieia, Iaso, Janiscus, Panacea, and Podalirius. He married Anticleia and became the father of Alexanor, Gorgasus and Nichomachus. He was one of Helen of Troy's numerous suitors. Machaon fought and died in the Trojan War. *See also* Asclepius; Helen; Hygieia.

Machchael *Marocael* (Taino Indians; Antilles)
Guardian. He watches the entrance of the cave where the first people emerged. Once he was late in returning to the cave and was turned into a stone. *See also* Marocael.

Machulas (Aymara People, South America) *see* Achachilas.

Macris (Greek)
She is the daughter of Aristaeus, the instructor of bee-keepers, and Autonoe and the sister of Actaeon. When Dionysus was hiding in a cave to escape his mother's murderous wrath, Macris brought him honey (likely from her father's hives) to eat. *See also* Actaeon; Aristaeus; Dionysus.

Macuilxochitl (Aztec; Mexico)
Also known as: *Five Blossoms, Xochipilli.*
Deity of music and dancing. One of the attendants of the high gods. The name is a synonym of Xochipilli (q.v.).

Mada (Hindu; India)
Mada is the demonic monster god of drunkenness or intoxication. Mada is also the god of liquor, women, dice, and hunting. In the *Mahabharata*, it is written that the Asvin twins rejuvenated the aged and wealthy sage Chyavana. Chyavana was the son of Bhrigu. He married the youthful Sukanya, the daughter of Saryata, and rued his aging physique. Delighted with his newfound youth, he told the Asvin twins of a soma get-together in the heavens, hosted by the gods. They decided to attend but were barred from entering by Indra because of their humble origins. It was said that the twins spent too much time with mortals to be pure. Chyavana decided to make a sacrifice to the Asvins and infuriated Indra. Armed with a thunderbolt and a mountain Indra proceeded to attack Chyavana. Chyavana conjured up the monster Mada, who was powerful enough to swallow the universe and the heavens. Indra yielded and permitted the Asvins to imbibe soma with the other deities. Mada symbolizes thought. *See also* Asvins; Soma.

Madderakka (Lapp)
Also known as: *Jordegumma* (Swedish).
Goddess of women. Goddess of childbirth. Creator of the infant. She is the mother of three daughters, Juksakka, Sarakka and Uksakka.

Mader-Akka (Finnish) *see* Akka.

Maderakka (Lapp) *see* Juksakka.

Madhava (India)
Husband of Laksmi. *See also* Krishna; Vishnu.

Madhu (India)
An extremely evil demon. Madhu and his followers were slain by the gods. Their marrow or "meda" covered the earth, who has since been called Medini. *See also* Durga; Kali.

Madhupriya (India)
"Friend of the Wine." *See also* Bala-Rama.

Madhusudana (India) Slayer of Madhu. *See also* Krishna.

Madhyama (India) *see* Vach.

Madira (India) "Of Spiritous Liquour." *See also* Devi.

Madivi *Mandavi* (India) *see* Bharata.

Madri (India)

She is the mother of two of the Pandu Princes, the twins Nakula and Sahadeva. *See also* Asvins; Krishna; Kunti; Pandavas.

Maeander (Greek)

River god. His parents are Oceanus and Tethys (qq.v.). *See also* Rivers.

Maenads (Greek)

Also known as: *Bacchae, Bacchantes, Bassarides.*

Possibly storm spirits. Female followers of Dionysus. He inspired them to ecstatic frenzy and they carried out his orgiastic rites. The first Maenads were the Nymphs. The Maenads are depicted naked or wearing thin veils. Wreaths of ivy crown their heads. They carry a two handled urn. Sometimes they are playing a flute or tambourine as they frenetically dance. In some versions they are attendants of Bacchus (q.v.). *See also* Dionysus.

Maenalus (A) (Greek) Father of Atalanta.

Maenalus (B) (Greek) Pan's sacred mountain in Arcadia.

Maenalus (C) (Greek)

The oldest of the fifty sons of the king of Arcadia, Lycaon. He made the mistake of serving the great god Zeus human flesh. Zeus hurled a thunderbolt at him and he died. Not to be confused with Lycaon, also an Arcadian king, who deliberately cut his son to pieces and offered him as a sacrifice to Zeus.

Maenawr Penardd (Celtic)

Fertility god. Magician. He owns a magic rod and a carrion eating sow. The sow is said to be Keridwen in disguise.

Maeoe (Celtic) *see* Maeve.

Maet (Egypt) *see* Maat.

Maeve *Meave, Mave* (Celtic)

Also known as: *Maeoe, Meadhbh, Mebhdh, Medb.*

Goddess of war. Originally, Maeve was the goddess of Ireland's sovereignty, the goddess of Tara, the island's magical center. In later versions, she was demoted in myth, as Irish culture changed under Christian influence, to an ordinary mortal queen. The original was definitely not a queen. Her name meant in Celtic "intoxication" or "drunken woman." Legend says she ran faster than horses, slept with innumerable kings whom she discarded, and carried birds and animals across her shoulders and arms. Maeve is the central figure of the most important remaining old Irish epic, the *Tain Bo Cuillaigne*, or *Cattle Raid of Cooley*. After comparing possessions with her consort, King Aillil (Ethal Anbual), she found he had a magic bull which she did not possess. She used her army to steal the magic bull of Cooley. After a great battle with the hero Cuchulain, she finally took the bull, but it in turn had to fight with Aillil's bull and they tore each other to pieces. *See also* Cuchulain; Mab.

Mafdet (Egypt)

Mafdet was worshipped in the earliest times as a goddess of judicial authority. Her name also stood for an apparatus used for executions. It was a pole, curved at the top with a coil of rope around the shaft and a projecting blade. Mafdet is also known as a snake fighter. She is represented as a feline predator and is shown running up the execution pole. In the Late New Kingdom she is shown in scenes from the judgment hall of the beyond. *See also* Maat.

Mafuike (Polynesian)

God or goddess of the underworld and of fire. One of the ancestors of Maui who tricked her into giving him her fingers which he quenched in a stream. In her anger she set the world on fire but Maui called on rain, sleet and snow to put it out. *See also* Kupua; Maui.

Magatama (Japan)

The Magatama are curved ornamental jewels belonging to the goddess of light, Amaterasu. They are one of the three insignia depicting Imperial power. The jewels symbolize the benevolence of the sun goddess' soul. *See also* Mi-kura-tana-no-kami; Susanowo.

Magh Tuiredh First Battle of (Celtic) *see* Credne.

Maghayanti (India) A Krittika sister. *See also* Rishi.

Magic Thunderbolt (India) *see* Tvashtri; Vajra.

Magna Mater (Greek)

Magna Mater, "Mother of the Gods," is an epithet for Rhea. *See also* Cybele; Rhea.

Magnes (Greek)

Magnes, the son of Aeolus and Enarete, was a human magnet, the nails in his shoes caused his feet to become magnetized to the ground. *See also* Aeolus (A); Argus (E).

Magnesia (Greek) *see* Canace.

Magni *Magne* (Norse; Teutonic)

Also known as: *Might, Thrud.*

God of strength. Son of Thor and the giantess Iarnsaxa, he lifted the giant Hrungnir's foot from his father when he was only three nights old. He and his brother Modi will inherit the hammer Mjollnir after Ragnarok. *See also* Iarnsaxa; Mjollnir; Modi; Ragnarok; Thor.

Mah (A) (Persia) *see* Ameshas Spentas; Hvare-khshaeta; Yazatas.

Mah (B) (Persian, Semitic, Sumerian, Akkadian, Chaldean)

Also known as: *Aruru, Belit-Ili, Gula, Mama, Mami* (Sumerian), *Ninmah.*

God of the moon. Queen of gods. Creation goddess. Assistant to Vohu Manah of the Amesha Spentas. Mah has been given the task of regulating time and tide. In her Semitic role of Belit-ili she is a deity of animals. As Mah or the Akkadian goddess Mami she is credited with creating seven women and seven men from clay and blood. As Gula, she is a goddess of medicine. In her creation role she is thought of as being Aruru. Mah is possibly androgynous since some versions call this deity a god. In Chaldean astrology, she is associated Hvare-Khshaeta, the sun;

www.ebook3000.com

Shaking

Shake the whole body loose, especially the joints, by bouncing up and down on the heels. Let all the joints open and relax. Also, shake the testicles and the breasts loose. This will open the sexual energy (the yin electric) and you do this on back as well.

The yin and yang are the negative and positive electric forces in the universe. The heart produces impulses (the yang electric) and the adrenal glands produce the adrenal hormone to stimulate the heart to beat. Of all the hormones inside us, this is the one that gives the vital force to our life.

When we concentrate on the sexual organs, the heart and the mind, we can make the yin and the yang electricity combine.




Point of Lymphatic drainage into the Vena
Direction of Lymphatic flow

Fig. 3.4 *Whole Body shaking and Lymphatic System*

True Breath - Skin Breathing

We exist because of the physical food and the unique combination of forces that surround us. The daily requirement of calories is about 6,000 units, while we only get 2,000 calories from food. The other 4,000 calories come from the forces around, above and below us. These forces that surround us are electricity, magnetism, cosmic particle energy, light, sound and heat. If we don't know how to absorb and transform this cosmic food, we need to depend on others to supply us. We then need to ask a priest, monk or holy person to give us our daily spiritual food.

The Taoists discovered that we can learn to absorb these surrounding and universal energies through the skin and the major energy centers. Absorbing energy through the skin is called the True Breath. This powerful energetic technique requires the Inner Smile and relaxation. The more one can relax, the more the body and the skin can open to the energy around us. The practice allows one to extend the mind, to touch the force and to draw that energy back into the body.

Tishtrya, the Dog Star; and Anahita, who is associated with the planet Venus. In later times, the Roman goddess of war, Bellona became known as Mah-Bellona. Mah is sometimes identified with Ninlil. She was associated with Anu after the flood. *See also* Aruru; Belit; Bellona; Ninmah; Tishtrya.

Mah Asruna (India) *see* Avalokitesvara.

Mah-Bellona (Roman) *see* Bellona.

Maha Isvari (India) "Great Potentate." *See also* Devi.

Maha-Kali (India) *see* Kali.

Maha-Maya (India) *see* Devi.

Maha-Pita (India) "The Great Father." *See also* Brahma.

Maha Sambara (Nepal) *see* Sambara (A).

Maha-Vairochana Tathagata (India) *see* Dainichi-nyorai.

Mahabharata (Hindu; India)

The *Mahabharata* is a long epic poem about the struggle between the Pandavas and their cousins the Kauravas (qq.v.).

Mahachandrarosana (Nepal) *see* Chandamaharoshana.

Mahadeo (India) *see* Parvati.

Mahadeva (India)

"Great God"; a praise name for Rudra-Shiva. *See also* Rudra; Shiva.

Mahagauri (India) *see* Gauri.

Mahakala (Hindu, Buddhist; India, Tibet)

Also known as: *Dharmapala Kalamahakala, Dharmapala Sitamahakala, Shiva.*

Mahakala is a title used for Shiva as the god of irrevocable time. In this aspect, Shiva is shown with an axe in one hand and a human body in the other hand. The Buddhist use this as a title for the deities Dharmapala Kalamahakala and Dharmapala Sitamahakala, the black and white protector spirits. In Tibet, Mahakala, the "Power of Devoring Time," keeps evil away. He wears a fierce expression on his face, a knife in his headdress and in one hand he holds a skull formed into a cup that is full of blood. *See also* Shiva.

Mahakalee (India) "The Great Black One." *See also* Devi; Kali.

Mahakali (India) *see* Devi; Gauri.

Mahakaruna (India) *see* Avalokitesvara.

Mahalaxmi (Hindu; India)

Mahalaxmi is an aspect of the mother goddess Durga. She is one of eight mother goddesses who rides a lion and carries many weapons, though she is not a menacing figure. Seated on her lion, she is shown with sixteen arms, carrying assorted weapons, as well as a book, rosary, bell and lotus. *See also* Durga.

Mahallika (India) *see* Hiranya-kasipu.

Mahamaya (India) *see* Maya (A).

Mahamayuri (Japan) *see* Kujako-Myoo.

Mahamya (India) *see* Kali.

Mahapadma (India) *see* Lokapalas.

Mahaprajapati (India) *see* Prajapati (B).

Mahapralaya (Hindu; India)

Mahapralaya is the complete cycle of universal time as represented by the one hundred year life of Brahma. At the end of this time, the entire universe, including Brahma and all the other gods, is destroyed in the Great Cataclysm (Mahapralaya). Following Mahapralya there will be one hundred years of chaos, then another Brahma is born, along with a new cycle. *See also* Kaliyuga; Kalpa.

Maharajni (India) "Great Queen." *See also* Devi.

Mahasena (India) *see* Karttikeya.

Mahasiddhas (Buddhist; India)

Tantric saints. *See also* Padma Sambhav; Samantabhadra.

Mahasthamaprapta (Nepal)

She is a Dhyanibodhisattva who is often seen standing to the right of an important deity with her colleagues, Akasagarbha, Avalokitesvara, Kshitigarbha, Mahasthamaprapta, Maitreya, Manjusri, Sarvanivaranaveskambhin, Trailokyavijaya. Vajrapani or Samantabhadra are sometimes substituted for one of the eight Dhyanibodhisattvas. *See also* Dhyanibodhisattvas; Samantabhadra.

Mahavira (Jains; India)

Also known as: *Jina, Vardhamana.*

The Mahavira, meaning "Great Man," was the twenty-fourth and last tirthankara ("keeper of the fords") of the Jains. He left his celestial abode to live on earth to alleviate human suffering. He chose to be an embryo in the womb of Devananda, the wife of Rishabhadatta, a Brahman who lived at Kundapura. Devananda was given fourteen (some say sixteen) favorable signs in a dream. The omens were an elephant, a bull, a lion, the goddess Sri, a garland, the moon, the ocean, a celestial abode, jewelry, a banner, a vase, a lake of full of lotuses, and an eternal flame. Her delighted husband was certain that this was an indication that their son would be a great Brahman scholar and religious leader. Sakra, the king of gods in Heaven had different plans. He decided that it would be more favorable for Mahavira to be the son of a Kshatriya. He ordered the gods' messenger and leader of the heavenly infantry, Harinagamesi, meaning "the-Man-with-the-antelope's-head," to transfer the embroyo from Devananda's womb to the womb of Trisala (also known as Priyakarini), the wife of the Kshatriya Siddhartha. Now she was given the fourteen signs that Devananda had received. From that time they enjoyed good fortune in all aspects of their lives. Twenty-five hundred and niney years ago, the child was born and given the name Vardhamana, meaning "he-who-grows, he-who-develops." He grew up as a prince in Bihar and married Yasoda. They became the parents of a daughter Riyadarshana (also known as Priyadarsana). (The Digambaras, a magor Jain group, do not believe that he ever married.) Vardhamana's parents, who were followers of the twenty-third Jain savior Lord Parsva's doctrine, decided to leave the world and did so by starving themselves to death. Vardhamana, in his thirtieth year, was granted permission by his brothers and authorities of the kingdom to give away his wealth. He spent the next twelve years as an ascetic and gained enlightenment. At this time he became Jina, the Victor. As Jina he taught for thirty years. His followers were known as Jainas or Jains after their master. He formed them into four groups: monks, nuns, laymen and laywomen. The number of disciples is given as fourteen thousand in some documents and in others forty-two hundred. At the end of this period, he was "kevalin" (omniscient) and he was ready to die. He had himself carried to a hall brightened by heavenly light, and was placed on a throne of diamonds. He preached for many hours and in the still of the night, when his followers had fallen asleep, he died. The year was 485 B.C.E. Many lamps were lit, but his soul had already departed for heaven. This incident is commemorated by the Jains in a festival known as Divali. *See also* Buddha; Sakra; Siddhartha.

Mahayogi (India) "Great Yogi." *See also* Shiva.

Mahayuga (India) *see* Dwaparayuga.

Mahendra (India) *see* Indra.

Mahesvara (India)
"Great Lord." *See also* Shiva; Trailokyavijaya; Uma.

Mahi (India) Mother of the planet Mars. *See also* Bhumi.

Mahina (Hawaii) *see* Hina.

Mahisa (India) *see* Mahisasura.

Mahisasura (India) "Buffalo Monster." *See also* Devi; Durga.

Mahisha (India) *see* Mahisasura.

Mahishamardini (India) *see* Durga.

Mahlaima (India) *see* Mala.

Maho Penekheka (Mandan)
The Evil Power. *See also* Maho Peneta.

Maho Peneta (Mandan) The Great Spirit.

Mahomet (Turkish) *see* Mohammed.

Mahou (Dahomey People; Africa) *see* Mahu.

Mahre and Mahrianag (Ancient Persian)
Adam and Eve. *See also* Adam.

Mahrkusha (Iranian, Persian)
"Destroyer." The demon who will destroy all mortals by frost and snow. *See also* Yima.

Maht (Egypt) *see* Maat.

Mahu *Mawu* (Dahomey, Fon People; Africa)
Also known as: *Mawa, Sogbu.*

Mahu is the daughter of Nana Buluku, and twin sister of the male deity Lisa. She is the mother of Dan. A creator goddess, she is associated with the sun and the moon. Mahu was transported by the great serpent Aido Hwedo as she moved around creating the earth and mortals. She is known as the mother or the twin sister of Lisa in some myths. As a male deity of metal working Mawu is also called Gu, which is also the name of the metal used in making swords. Either she or Nana Buluku is the creator. Sometimes a part of a trinity with the chameleon god Lisa and Ge the moon god. Some writers say Mawu is the chief creator deity of the Dahomey people, but still associated with Lisa and Ge. In this same version Mawu is called the father of Lisa or that Lisa was the mate of Mawu. She is considered androgynous when linked with Lisa as Mawu-Lisa. In this relationship, Lisa a male deity is associated with the sun and Mawu is the sky god and chief of all deities. *See also* Agbe; Aido Hwedo; Leza; Mahu.

Mai (Turkey) *see* Umai.

Maia (A) (Roman)
Dawn goddess. Goddess of fertility. Plant goddess. Maia, an ancient Roman goddess of fertility, could have been the consort of Vulcan. The consort of the Romano-British deity Mercury was known as Maia, as was the goddess worshipped in Rome with Mercury. Maia is associated with Fauna, the goddess of animals, farming and nature. *See also* Mercury (A); Mercury (B).

Maia (B) (Greek)
Maia is one of the Pleiades, the seven daughters of the Greek god Atlas and Pleione (also known as Aethra). She is the mother of the messenger of the gods, Hermes, by Zeus. *See also* Calypso; Pleiades.

Maia (B) (India) *see* Maya (A).

Maidere (Tartar) *see* Maitreya.

Maijunga (Aborigine People, Australia)
God of the Southeast Wind. *See also* Bara.

Mainda (India) Monkey Child. *See also* Asvins.

Maira Ata *Maira* (Tupi-Guarani People, Brazil)
Also known as: *Sommay.*

Culture hero. He was able to predict the future with the help of spirits. His children are the twins Ariconte and Timondonar. Some say only one son was Maira Ata's and the other was the son of a mortal named Sarigoys. The story is that the twins had to pass tests before Maira Ata recognized them as his sons. Ariconte and Timondonar opposed one another. During an argument, Timondonar stamped his foot on the ground and caused the great deluge. The only survivors were Timondonar, Ariconte and their wives. *See also* Ariconte; Maire-Monan.

Maire-Monan (Tupinambas People, Brazil)
Also known as: *Transformer.*

Culture hero and teacher. Maire-Monan came after Monan, who was the creator of mankind. Maire-Monan had the power to change men and animals into other forms in order to punish them for misdeeds. He taught men governing and agriculture. Men killed him because of his changes. He is probably the same as Maira Ata since the legends are similar. *See also* Ariconte; Maira Ata.

Maisahana (Nicaragua, Central America)
Great father or first man. Maisahana and his wife Itoki were the first people. They were the founders of the Mosquito, Tuachca, Yusco, Sumo and Ulua people. There is no indication that Maisahana and Itoki were worshiped as deities. *See also* Itoki.

Mait' Carrefour (Haitian)
God of crossroads and moon deity. He is the brother of

www.ebook3000.com

Ghede (Baron Samedi) and possibly came from the Kalfu Indian religion. Some say he is a patron of magicians. Mait' Carrefour is generally shown with his arms in a cross-like position. *See also* Ghede.

Maitreya (Buddhist; India)
Also known as: *Ajita, Byamspa* (Tibet), *Champ-pa* (Tibet), *Maidere* (Tartar), *Metteya, Mi-Lo Fu* (China), *Miroku-Bosatsu* (Japan).

Known as the loving one, Maitreya is the fourth and future Buddha. His given name is Ajita. He resides in Tushita heaven and is expected to appear on earth in human form four thousand years after the disappearance of Gautama Buddha. In some traditions, it is said that it will be five thousand years after Gautama Buddha's disappearance that Maitreya will appear. He is also worshiped as a Dhyanibodhisattva. He is the only Bodhisattva worshiped by the Hinayanist and the Mahayanist Buddhists. In Bardo, the Tibetan Buddhism after-death state, Maitreya appears with Akshobhya and his sakti Locana. Maitreya is sometimes depicted standing, adorned with ornaments and holding a lotus stalk in his right hand. If he is represented seated as a Buddha, his legs are either interlocked or dangling. His color is yellow and sometimes his images bear the figures of the Dhyani Buddhas. His vahanas (vehicles) are the lion, or the lion throne, or the symbol of divine wisdom, a white elephant. His emblem is the caitya (the stupa that holds sacred relics). Compare Maitreya to the Kalki (Hindu) and Hotei (Japan). *See also* Abheda; Ajita; Akshobhya; Buddha; Dhyani Buddhas; Dhyanibodhisattvas; Kuvera; Manushi-Buddhas; Mi-Lo Fu; Miroku-Bosatsu; Samantabhadra; Stupa; Tushita; Vairocana.

Makali (Hindu; India) *see* Parvati.

Makanaima (Arawak People; New Guinea) *see* Makonaima.

Makara (Hindu; India)
Makara is a sea monster known as the mount of Varuna, the symbol of Kama (the god of love), and the vehicle of Ganga. A source of life and death, Makara dispenses the water of life to the good and death to the evil. Makara carries a priceless pearl in his mouth. If a man is courageous enough to retrieve it, it is assured that the woman of his dreams will fall in love with him. In early Indian art, the Makara resembled a crocodile. It evolved into a composite fish elephant and is depicted variously as a dolphin, a crab, a crocodile or a shark. In Central Java, it usually has a monster's head, gaping jaws, large teeth, and an elephant's trunk. Sometimes another mythical animal emerges from the trunk, and from its jaws, figures of deities, lions, or birds emerge. The Makaras are associated with darkness and water. In the Hindu zodiac, Makara represents Capricorn. *See also* Ganga; Kama (A); Varuna.

Makara Sisters (Aborigine People, Australia)
Deified birds. Originally the Makara Sisters were Emu women, but because of the unwelcome advances of the Dingo men called the Wanjin, they flew away. To capture them the Dingo men set fire to their hiding place, a fire which ruined the Makara's wings, but because they had to step so high over the flames their legs became elongated. Now the Emu cannot fly, but they can outrun people. The Emu are beautiful women with long, honey colored hair, and bodies covered with icicles. The icicles falling from their bodies cause frost in late winter. Sometimes the Maraka sisters are called the Seven Sisters and are compared to the Pleiades.

Makemake (Easter Islands, Hawaii)
Patron of the Bird Cult. Makemake is a local god of the Hawaiians who took the place of Tane. He drove the birds to an island to protect them from egg stealers. There are indications that Makemake was later adopted by the Easter Island People. Makemake possibly developed from the Tahitians' giant bird who swallows mortals, named Matu-'u-ta'u-ta'ua.

Makh (Hittite) *see* Ullikummis.

Makila (Pomo People, North America)
Father of Dasan (q.v.).

Makkal (Middle Eastern) *see* Moloch.

Makonaima *Makanaima, Makunaima* (Arawak People, New Guinea; Caribbean; South America)
Also known as: *Kanaima, Kenaima.*

One who works in the night. His work is done under the darkness of night. In early times, all creatures could speak and all lived in harmony. At that time, his son, Sigu, ruled over all animals. Makonaima created a tree bearing many fruits, but Sigu (who is an apparent trickster) cut down the tree. The stump of the tree was filled with fish of every kind, but for some reason the stump began to overflow. Capped by Makonaima with a basket, the flow was stopped. A monkey (also a trickster) removed the basket and a deluge followed. Makonaima saved the animals by placing some in a cave and others in a tree. At daybreak the waters had receded, but the animals were completely changed. Thus began our present world. In another tale, Makonaima, a creator, is the twin brother of Manape. He pulled down the "Tree of Life" against the opposition of the rodent, Agouti. This brought about the flood that destroyed mankind. After the tree had fallen, it spread plants all over the earth. Makonaima appears to belong to a class of avengers known as Kenaima (q.v.). He is possibly analogous to Wakanda and Manito. *See also* Aimon Kondi; Kururumany.

Makunaima (Caribbean, South America) *see* Makonaima.

Mala (India) *see* Ratnasambhava.

Malah (Babylonia) *see* Marduk.

Mali (Australia) "The Bat" *see* Gidja.

Malik (Sumer) *see* Nergal.

Malinalxochitl (Aztec)
She is the sister of Huitzilopochtli (q.v.).

Malsum (Algonquin People, North America)
The Destructive Force. He is the brother of Gluskap.

Mama (Sumer) *see* Ama; Mah (B); Mami.

Mama Allpa (Inca; Peru)
An Incan earth deity and goddess of the harvest. Mama Allpa is known as the "great nourisher of mankind." The Carib earth-goddess, Mama Nono, is comparable to Mama Allpa, as are

Artemis and Ishtar. Mama Allpa is described as having numerous breasts. *See also* Artemis; Ishtar; Mama Nono.

Mama Cocha (Inca; Peru)
Also known as: *Mother Sea.*
Mother goddess. Sea Mother. Mama Cocha is the sister and wife of Viracocha, the creator of mortals. She is a goddess of rain and of water, associated especially with Lake Titicaca. Fishers worship her. *See also* Copacati; Mama Pacha.

Mama Cora (Inca; Peru)
Corn goddess. She is the daughter of Pirrhua. *See also* Manco Capac; Pirrhua.

Mama Coya (Inca) *see* Tahuantin Suyu Kapac.

Mama Huaco (Inca) *see* Ayar Aucca.

Mama Ipacura (Inca) *see* Ayar Cachi.

Mama Lakshmi (India) *see* Lakshmi.

Mama Nono (Carib People, Antilles)
She was the earth mother goddess of this now extinct tribe. Korobona was another female figure known as a cultural heroine, and mother of the first Carib. *See also* Korobona; Mama Allpa.

Mama Occlo *Mama Ocllo* (Inca; Peru)
Also known as: *Mama Oella, Mama Ogllo.*
First woman. She is the sister and wife of Manco Capac who made the trek with him in search of Cuzco. Mama Occlo instructed the Inca women in the domestic arts. *See also* Manco Capac; Viracocha.

Mama Ocllo (Inca) *see* Mama Occlo.

Mama Oella (Inca) *see* Mama Occlo.

Mama Ogllo (Inca) *see* Mama Occlo.

Mama Oullo Huaca (Inca) *see* Mama Occlo.

Mama Pacha (Inca) *see* Pachamama.

Mama Quilla (Inca; Peru)
Moon goddess. Inti, the sun, is her brother/husband. With the exception of Venus, the planets and stars were her attendants. As the moon goddess of the ancient Peruvians, she presided over the births of children. Mama Quilla was represented as a disk of silver with the face of a human. She is associated with Cuycha the rainbow, Catequil the thunder god, and Chasca, the planet Venus. Mama Quilla is comparable to the Roman goddess Diana. *See also* Cuycha; Inti.

Mama Raua (Inca; Peru) *see* Ayar Uchu.

Mama Zara *Zaramama* (Inca; Peru)
Grain Mother. She is an ancient corn or grain goddess.

Mamaki (Buddhist; Tibet)
Known as the shakti of Akshobhya, Ratnasambhava and Vajrasatwa, this goddess is a Dhyanibuddhasaktis. She appears in the Second Day in Bardo embracing Vajrasatwa, attended by the female Bohisattvas Lasema and Pushpema, and the male Bodhisattvas Say-nying-po and Champ-pa. Her asana (position) is lalita; one leg pendant sometimes supported by a lotus and the other leg in the position of a Buddha. Her mudras are varanda, also called vara, the gift bestowing mudra; the arm is pendant, all fingers extended downward, and the palm turned outward, and vitarka, which signifies argument; the arm is bent, all fingers extend upward, except the index finger which touches the tip of the thumb, with the palm turned outward. She is shown holding three mayurapiccha (peacock feathers) at shoulder level. Her color is yellow. Her emblems are the kapala (human skull cap), karttrika (chopper), mayurapichha (peacock feather), and ratna (jewel). *See also* Akshobhya; Dhyani Buddhas; Maitreya; Ratnasambhava; Shakti; Tara (B); Vajrapani; Vajrasatwa.

Mamaldi (Siberia) *see* Khadau.

Mamandabari (Aborigine People; Australia)
They are important Dreamtime spirits who rose out of the ground. Sometimes they are said to be two brothers or a father and son. They are responsible for teaching various rituals.

Mamaragan (Aborigine People, Australia)
Also known as: *Lightning Man.*
Storm god. He lives at the bottom of a waterhole in the dry season and rides the top of thunder clouds in the wet season. The Lightning Man is shown with stone axes on his joints. He is similar to Daramulun.

Mama'sa'a (Fox People, North America) The First Man.

Mamers (Roman) *see* Mars.

Mami (Akkadian, Babylon, Chaldea, Sumer)
Also known as: *Ama, Aruru, Mah, Mama.*
Mother goddess. She is variously called the Mother-Womb, the Bearing One, the Mother Goddess, the Creator of Destiny, The Creator of Mankind, the Mistress of All the Gods. Goddess of childbirth. The goddess who, according to the beliefs held at Eridu, molded man out of clay, softened by the blood from a god slain by Ea. Mami aided mothers in childbirth. In the *Poem of Creation*, Mami created the first man, whose name was Lullu. *See also* Ama (A); Aruru; Mah (B).

Mami-Ngata (Aborigine People; Australia) *see* Bunjil.

Mamien (China) *see* Ma-Mien.

Mammitu (Assyro-Babylonian).
Also known as: *Mammetu, Mammetum.*
Mammitu plots the destiny of the newborn child's life. She also decrees the fate and future of men.

Mamona (Antilles) *see* Atabei; Iella; Iocauna.

Mamu (Aborigine People; Australia)
Spirit animal. Mamu is a large spirit Dingo who captures and eats the spirit of any child who wanders away from camp. *See also* Mopaditis.

Man Eater (Polynesia) *see* Kaitangata.

Man-la (India) *see* Bhaishajyaguru.

Mana-garm (Teutonic) *see* Hati.

Mana-heim *Manheim, Mannheim* (Teutonic)
Also known as: *Midgard.*

www.ebook3000.com

Mana-heim is the part of Midgard inhabited by human beings (rather than giants or dwarfs). Some do not differentiate between Mana-heim and Midgard (q.v.).

Manabozho (Native North American) *see* Nanabozho.

Manabush (Algonquin People, North America) *see* Nanabozho.

Manaf (Arabic)
This ancient god, called by some a sun god, was caressed by women, except during their menses, when it was forbidden.

Manala (Finnish)
Also known as: *Tounela, Tuomela.*
The underworld. It is inhabited by giants of various races as well as those mortals who are dead and awaiting rebirth. The giants know quite a bit about medicine and can often provide remedies for illnesses. The inhabitants of Toumela have as their queen, Tuonetar, who has as her husband, Tuoni. Their daughters, who are described as very ugly, included Kipu-Tytto (goddess of illness) and Loviatar (source of evil and goddess of disease), who in turn is the mother of nine monsters of sickness. There is also Kivutar and Vammatar, who are goddesses of disease, and finally the god of death, Kalma. The giants are associated with Vainamoinen. *See also* Hell; Kalma; Kipu-Tytto; Kivutar; Loviatar; Tuonetar; Tuoni.

Manannan (Irish) *see* Manannan Mac Llyr.

Manannan Mac Lir (Irish) *see* Manannan Mac Llyr.

Manannan Mac Llyr *Manannan Mac Lir* (Celtic, Irish)
Also known as: *Manannan, Manawydan Ap Llyr* (Celtic) *Manawyddan.*
Manannan Mac Llyr is a sea god, god of the capes of the sea, god of storms and waves, god of fishers, god of war and shape changer. He is the son of Lyr. He married Fand who was later given to Cuchulain. In time she was returned to her husband. To insure that the lovers would never meet again, he shook his magic cloak between them. He became the father of Mongan by Caintigerna, the wife of Fiachna. This was accomplished by one of his favorite pastimes; he assumed the form of her husband and climbed into bed with her. Aside from frolicking with women, he also had serious responsibilities. An ancient deity, he prepared the Sidhe for the Tuatha de Danann. He was the guardian of the Blessed Islands and the guardian of the Hallows. With Pryderi, the son of the goddess Rhiannon, he was also the guardian of the Grail. His life was made easier with a ship that could follow his command without sails; a cloak that made him invisible; a helmet that consisted of flames; and a sword that could not be swayed from its mark. It was said that he fed the Tuatha De Danann pigs for food. The pigs constantly came to life cooked and ready to be eaten the next day. Manannan Mac Llyr became the foster father of the great deity Lugh, whom he received in payment from Lugh's father, Cian. He was also the foster father of numerous other deities. The Blessed Islands have been identified with the Isle of Man and the Isle of Arran. One of Manannan's consorts may have been Aoife, the woman warrior or perhaps another woman with the same name. She was punished and changed into a crane for stealing the secret alphabet of knowledge from the deities. Her intent was honorable. She intended to give it to mortals. She used her new shape to her advantage and made a bag from her skin, which she used to hold the alphabet and accomplish her mission. Not to be confused with Manawydan Ap Llyr (Manawyddan), the stepfather of Pryderi. Manannan and Manawyddan have common attributes. *See also* Aine; Aoife (B); Cian; Cuchulain; Fand; Lugh; Tuatha de Danann.

Manasa *Manassa.* (Hindu; India).
Also known as: *Manasa-Devi, Shakti, Vaishnavi* (wife of Vishnu).
Manasa, the snake goddess, is the daughter of Kadru and Kasyapa and sister of Sesha, Kapila, and the Nagis and Nagas. The Shivalas, followers of Shiva, maintain that Shiva is her father. With Shiva, her mother is said to be Gauri. She is a demanding goddess and anyone who encounters her cannot turn away from her. A wealthy merchant named Chand had been given certain powers by Shiva because of his devotion. Manasa was angry and demanded that Chand worship her. When he refused, she made his life hell on earth. First, she ripped up his prize garden. Next she appeared to him in the form of an enticing young woman and promised to marry him if he would transfer his powers to her. Beguiled, he did as asked. She transformed herself back into her goddess form and demanded his worship. He thought that the fatal attraction was over and again, he refused. Furious, she set out to make life impossible for him. His garden was once more uprooted, she bit his six sons to death, and his ships containing all his wealth were sunk. He was left stranded on a desert island and almost starved to death. Still, he would not give in to her demands. He survived and eventually made his way home and attempted to rebuild his life. Manasa had not forgotten him. Although he had taken elaborate precautions to protect himself from her, she still managed to harass him. He married and had a son, Lakshmindra. His son married Behula and on his wedding night, a snake slipped into the bed and bit him to death. The new bride put her husband's body on a raft and sailed the rivers for six months hoping that a doctor would be able to revive him. Eventually, she came upon a washerwoman who led her to Manasa. Lakshmindra was restored to life only on the condition that Chand be made to worship her. The couple journeyed home and related Manasa's proposition. Finally, on the eleventh day of the second half of the moon, Chand relented and worshiped the serpent goddess. The Shivalas believe that the worship of cobras will keep them safe. Manasa is invoked for protection against snakebites. She is known to inspire women, and those who are sterile invoke her for fertility. During worship, Manasa and her serpent family are appeased by various items, including milk. She is a protector of animals, and is also worshiped by hunters. Compare Manasa to Gauri. *See also* Devi; Kadru; Kasyapa; Nagas and Nagis; Sesha; Shakti; Shiva; Takshaka; Vishnu.

Manasa-Devi (India) *see* Manasa.

Manasa-Putra (India) "Brain Born." *See also* Rishi.

Manasi (India) *see* Asparases.

Manassa (India) *see* Manasa.

Manat (Arabic) *see* Menat.

Manawddan (Irish) *see* Manannan Mac Llyr.

Manawydan Ap Llyr *Manawyddan, Manawydan Son of Llyr* (Celtic)

Also known as: *Manannan Mac Llyr* (Celtic, Welsh).

Deified mortal. Manawydan Ap Llyr, frequently referred to as Manawyddan, is the son Llyr. He was one of seven survivors who took Bran's head to London. Manawydan was the second husband of the goddess Rhiannon and the stepfather of Pryderi. He was known as a teacher, craftsman, and a dependable man who was always able to make a living. A bright and cunning individual, he rescued Rhiannon and Pryderi from a magic castle. Manawydan Ap Llyr is often called the Welsh counterpart of Manannan Mac Llyr and has attributes similar to Pwyll. *See also* Bran; Branwen; Pryderi; Rhiannon.

Manawydan Son of Llyr (Celtic) *see* Manawydan Ap Llyr.

Manawyddan (Celtic) *see* Manawydan Ap Llyr.

Manco Capac *Manco-Capac, Manco, Manko-Kapak* (Inca; Peru)

Also known as: *Ayar Manco, Pirrhua-Manco, Tahuantin Suyu Kapac.*

Solar god. Teacher of religion, agriculture, weaving and civilization. In the beginning, Manco Capac and his three older brothers, all children of Inti, the sun, emerged from the Paccari-Tambo (Inn of Origin) caves. The eldest son proclaimed the earth belonged to him. Manco Capac was so furious that he trapped his brother in a cave and sealed it with huge boulders. He also pushed his second eldest brother over a precipice. While falling to his death, he was changed to stone. The acts were witnessed by the remaining brother, who decided that the best thing for him to do was to flee. He was never heard from again. Manco Capac went on to establish the city of Cuzco, where he was worshiped as the Son of the Sun. In another version of the origins of the Incas, caves are again the point of emergence. The three caves are the same name as in the previous myth, Paccari-tambo or sometimes Tambotocco (Place of the Hole). In the beginning, four brothers and four sisters emerged from the middle cave. Their names and numbers vary from myth to myth. While searching for habitable land for a settlement, one of the brothers, Ayar Cachi, incurred the wrath of his siblings. A strong, boastful, show-off, Ayar was finally tricked into returning to the Cave of Origin under the pretext of gathering items they had left behind. Once inside, his brothers on the outside sealed the wall so he could not escape. The brothers set up temporary housing at Tambu Quiru and while there were visited by the spirit of Ayar Cachi, the brother sealed in the cave. He persuaded them to proceed on their journey and to found the city of Cuzco. Ayar Cachi stayed behind on Huanacauri, a hill. There he turned himself into stone where he became the object of veneration for a later Inca cult. (In another rendition, it was another brother, Ayar Uchu, who after teaching Manco Capac certain rituals, turned himself into stone.) In a variation, the sun god felt compassion for mortals who were at that time living in a barbaric state. He sent his son, Manco Capac and his daughter, Mama Ocllo, to earth to instruct the mortals in the ways of civilized living. They traveled many miles before they found a place where the long golden rod they were carrying could be buried in the earth. When they finally reached a place where the earth accepted the rod, it was Cuzco. Over time they gained the native people's confidence and taught them the art of civilization. They also established the worship of the sun. Manco Capac is associated with Pachacamac. *See* Tahuauntin Suyu Kapac for another version. *See also* Mama Occlo; Pachacamac; Viracocha.

Mandara Mountain (Hindu; India).

A sacred mountain range in the Himalayas, Mandara mountain is the home of Durga. It was this mountain that was used as a pole in the churning of the ocean of milk. *See also* Deva (A); Durga; Kuvera; Loka; Meru Mountain.

Mandavi (India) *see* Madivi.

Mandishire (Siberia) *see* Manjusri.

Mandodari (Hindu; India)

The daughter of Maya the architect, Mandodari is the eldest wife of Ravana and also the wife of his brother Bihishan. Some say that she is a later avatar of the Daitya Hiranya-kasipu. *See also* Hiranya-kasipu; Maya (C); Ravana.

Mane (Teutonic) *see* Nat.

Manes (Roman)

Spirits of the dead. *See also* Dis; Dis Pater; Orcus; Pitri; Pluto.

Mangadevatas (India) *see* Devis.

Mangaia Island — Creation Legend (Polynesia) *see* Vari (A).

Mangala (A) (India) "The Auspicious One." *See also* Devi.

Mangala (B) (Mande People, Africa)

Creator. Supreme being. Mangala created seeds and mankind from an egg. He also created Pemba and Faro as the twins. *See also* Faro; Pemba.

Mangi and Kangi, The (Japan) *see* Hikohohodemi; Hosuseri; O-Wata-Tsu-Mi.

Manheim (Teutonic) *see* Mana-heim.

Mani (A) *(Mane)* (Teutonic)

Mani, the moon, and Sol, the sun, are the offspring of the giant, Mundilfari. *See also* Aarvak; Muspells-heim; Odin; Sol (B).

Mani (B) (Brazil, South America)

Food deity. There are several versions relating to this god. Most appear to be connected with the advent of missionaries. In one, the "Good Spirit" came down and introduced the plant manioc to the people and taught them how to prepare it as a food. He didn't teach them how to reproduce the plant. Later, a young virgin was seduced by a young man who was really a metamorphosed version of Manioc. The daughter of this union led the people, and showed them how to plant and cultivate manioc. In another version it was a pale son who was born from the union and he was named Mani; but he died without any signs of sickness after one year. He was buried and a odd plant grew on his grave. Because birds became intoxicated after eating the fruit from the plant, the people opened the grave and found the manioc root which they called Mani-oka. In other versions Mani lived to a ripe old age, teaching the people many things. Among the most important was the method of planting and using the manioc root. *See also* Tupan.

www.ebook3000.com

Mani (C) (Polynesia)
Mani is accompanied on her rounds by the waxing moon, Hiuki, and the waning moon, Bil. Mani is able to bring the god of darkness, Tangaroa, back to life by shaking his hands in a coconut shell. *See also* Tangaroa.

Mani (D) *Manes* (Manichaeism; Babylon)
Mani, a native of Babylonia, took up his cause in approximately C.E. 242. His beliefs were combined with Zoroastrianism, the dualism of Mazdaism and the Gnostic tradition borrowed from Christians of John the Bapist and the Mandaeans. The combination formed the basis for his dualistic religious philosophy. He was the self-proclaimed highest spokesperson of Christ. The Christians denounced Manichaeism as a heresy.

Mania *Maniae* (Etruscan, Greek)
Goddess of the dead. The Greeks called her "Daughter of Night." She was thought to be responsible for causing moonsickness. In ancient days, children were sacrificed to her. In Etruscan mythology she is an underworld deity and consort of Mantus. *See also* Lara.

Manibozho (Indian People, North America) *see* Nanabozho.

Manigarm (Teutonic) *see* Hati.

Manik (Maya People, Yucatan)
Manik is the god of sacrifice. He is similar to Xipe Totec (q.v.)

Maninga (Mandan)
Water spirit. The Flood Spirit. Lone Man defeated Maninga but Maninga later returned and made the water rise. Lone Man planted a sacred cedar tree then had his people build a high stockade of willow planks, which was called the Great Canoe. When the water started to overflow the walls Lone Man threw precious shells that were favorites of Maninga. The deity caused the water to recede to pick up the shells and the people created a magic turtle drum which drove Maninga away forever.

Manitou *Mandio, Manito* (Native North American People; various groups)
Also known as: *The Great Spirit or Manitos.*
Supreme deity. The spirit or spirits that rule all things. The masters of life. In one version Gitche-Manito means a good spirit and Matche-Manito is a bad spirit. Similar to the Eskimo Inuat. Manitou is similar to the Iroquois Orenda. *See also* Gitche.

Manju Bara (India) *see* Manjusri.

Manjughosa (India) *see* Manjusri.

Manjughsha (India) *see* Manjusri.

Manjunghose (India) *see* Manjusri.

Manjushree (India) *see* Manjusri.

Manjushri (India) *see* Manjusri.

Manjusri *Manjushree, Manjushri* (Buddhist; India, Tibet)
Also known as: *Arpacanamanjusri, Dharmacakra* (Soft-voiced Lord of Speech; one of four manifestations), *hJamdpal* (Tibet), *Jam-dbyans-mag-gi-rgyal-po* (Tibet), *Jam-pol* (Tibet), *Jam-yang-nge-gi-gya-po* (Tibet), *Mandishire* (Siberia), *Manju Bara, Manjughosa* (Pleasant Voice), *Manjughsha, Megh Sambara* (Nepal), *Monju* (Japan), *Monju-Bosatsu* (Japan), *rNam-snan-mnon-byan* (Tibet), *Siddhaikaviramanjughos* (White One with Soft Voice; a manifestation), *Simhanadamanjusri* (Lion-voiced Charming Splendor; a manifestation), *Tiksnamanjusri* (Charming Splendor; a manifestation), *Vagisvara, Vagiswara, Vajrahara, Varanga, Wen-shu* (China), *Yamantaka* (Manjusri's fierce form), *Yamari* (Foe of Yama).
Manjusri, the god of learning, speech, science, and wisdom, was born from a lotus, without parents. In Sanskrit, his name means "Great Fortune" or "Deep Virtue." At birth, a tortoise sprang from his face. He lived on Mount Panchashirsha (five peaks) in the Himalayas. Manjusri arrived in the area riding on his lion and with one swipe of his sword drained the water of Lake Nagavasa which filled the valley. In some traditions he is considered to be the founder of culture and learning in Nepal. Others venerate him as the founder of the universe and the god of agriculture. They dedicate the first day of the year to him. One of the Dhyanibodhisattvas, he forms a triad with Avalokitesvara and Vajradhara. He is single, but is often involved with the wives of his Hindu friends, Vishnu and Brahma. He is portrayed as yellow, or of a golden hue, sometimes seated in a posture of teaching. He is generally shown sitting on a blue lion surrounded by clouds representing ignorance. He holds either a lotus, a sword or a book in his hands. His delusion-cutting sword, known as the "Sword of Wisdom," indicates the ability to obliterate the clouds of ignorance. Sometimes he bears small figures of the Dhyani Buddhas in his hair. He also appears in a feminine appearance. In Japan, Manjursri is paired with Fugen-Bosatsu (in Sanskrit, Samantabhadra). He is shown seated on a lotus and riding an elephant. In his fierce form as Yamantaka or Yamari, he celebrates his victory over the demon of death, Yama. He has three or six faces and mutiple hands; he carries a sword, thunderbolt, axe and noose and is usually shown with a necklace of skulls. Megh Sambara, who is the angry aspect of Manjusri in Nepal, is known as the god of protection against enemies. He is depicted with a buffalo head and is in the company of a female. *See also* Arpacanamanjusri; Avalokitesvara; Brahma; Dhyani Buddhas; Dhyanibodhisattvas; Monju-Bosatsu; Prajnaparamita; Samantabhadra; Sambara; Sarasvati; Vishnu; Yamantaka.

Manko-Kapak (Inca) *see* Manco Capac.

Manmatha (India) This is Vishnu as the god of love (q.v.).

Mannheim (Teutonic) *see* Mana-heim.

Manru (Babylonia) *see* Marduk.

Mantchu-Muchangu (Shongo People, Africa)
God of dressmakers. He taught humans how to make clothes and cover their bodies.

Mantis People — Creation Legend (Bushman Group, South Africa) *see* Cagn.

Mantius (Greek) *see* Abas (B).

Mantradevatas (India) *see* Devis.

Mantus (Etruscan) *see* Mania.

Manu (Hindu; India)
Manu is one of fourteen patriarchs. Each patriach ruled or

will rule the world for one period of its history. Each period of time, known as a Manvantara or Manu interval, is equal to 4,320,000 years. Each interval is named for its own Manu and ends with a great flood. We are now considered to be in the seventh interval and the Manu for this period is Vaivasvata, the son of the sun god Vivasvat. The first Manu, "The Intelligent," who emanated from Brahma was Svayam-bhuva and as Brahma's son was the progenitor of mortals. His wife, Satarupa, emanated from the goddess of knowledge Sarasvati. Svayam-bhuva was the father of the ten Prajapatis and the seven, and later ten Maharishis. Svayam-bhuva created the *Manu-sanhita*, the Book of Hindu Laws. In the *Satapatha Brahmana*, it is said that Manu came upon a small fish on the bottom of his wash bowl. The fish begged to be saved and in return promised to save Manu from certain destruction when the Great Deluge flooded the land. Manu saved the fish until it grew so large that it had to be taken to the ocean. That day, the fish instructed Manu to build a ship. When the flood arrived, Manu boarded the ship and was towed around for years by the fish. Finally, Manu and the ship arrived on Mount Himalaya. When the waters subsided, everything on earth had perished except for Manu. Manu offered a sacrifice of whey, cream and ghee (the sacrificial melted butter), and was given a woman, who was called his daughter. Manu turned himself into a bull to avoid the act of incest. Ida, his daughter turned herself into a she-goat and Manu turned into a he-goat. This went on until the earth was populated with animals. Manu is one of "the seven sages" who shine in Saptarshi (the Great Bear constellation). A similar myth is told in the *Mahabharata* involving the seventh Manu, Vaivasvata, and Matsya, the fish avatar of Vishnu. For details, *see* Matsya. Compare to the creation myth of Brahma. *See also* Daksha; Pishachas; Prajapati; Rishi; Sanja; Sarasvati; Varaha; Vasistha; Vishnu; Vivasvat.

Manuai (Admiralty Islands)
He is the first man, who created woman from the trunk of a tree, mated with her and became the founder of the people. *See also* Takaro.

Manusha-Rakshasis (Hindu; India)
Female demons in human form. *See also* Rakshasas.

Manushcithra (Persia) *see* Faridun.

Manushi-Buddhas *Manusibuddha* (Buddhist; India)
The Manushi-Buddhas appear in the form of a human to live on earth and teach the doctrine of Buddha. The seven Manushi-Buddhas are Vipasyin, Siokhi, Vishvabhu, Krakuchanda, Kanakamuni, Kasyapa and Sakyamuni (Gautama). The last four belong to our present Kalpa. (A Kalpa is four billion human years and is the same as one day for Brahma.) In another list, five Manushi-Buddhas are given: Krakuchandra, Kanakamuni, Kasyapa, Sakyamuni, and Maitreya, the future Buddha. Another reference lists seven: Dipankara, Vipasyin, Sikhin, Visvabhu, Krakuchanda, Kanakamuni, and Kasyapa with Maitreya, the eighth and future Buddha. They are Buddhas of compassion and are depicted wearing monastic garments and have bare heads and usually long-lobed ears. *See also* Dhyani Buddhas; Dipankara; Kasyapa (B); Maitreya; Sakyamuni; Samantabhadra; Vajrapani.

Manusibuddha (India) *see* Manushi-Buddhas.

Manyu (Persia) *see* Angra Mainyu.

Manzan Gormo (Burait)
Mother goddess. Said to have created the Milky Way from her excess milk. *See also* Ajysyt; Khotun; Milky Way.

Maorocon (Antilles) *see* Guamaonocon; Iocauna.

Maorocoti (Antilles) *see* Guamaonocon; Iocauna.

Maou (Africa) *see* Mahou.

Maponos (Wales) *see* Mabon.

Mar (Aborigine People, Australia)
Also known as: *The Cockatoo-man.*
Fire deity. He was the only one who knew how to make fire until little bird-man Takkanna stole the secret. A fight developed and all were changed into birds and Takkanna became the robin, his red feathers reminding all that he had given fire to the people.

Mara *Namuci* (Buddhist, Lamaist; Hindu; India)
Mara, the god of lightning, seduction, temptation, physical love and death, was the father of three beautiful daughters known as the Lust goddess, the Thirst goddess and the Delight goddess. Mara sent them to distract Buddha from his meditations as he sat under the Bo Tree. Their sensual dances failed to sway the devout Buddha. Mara hurled mountains at Buddha and they were transformed into flowers and celestial chariots. Mara is the ruler of the sphere of the pleasures of sense and the commander of an army of demons. His function is to delay the coming and preaching of the Law. Said to be homeless, Mara wanders the earth to catch the souls of the dying. His demons are described as having grimacing faces, and distorted bodies, some with a second face in their stomachs. They are shown on foot or riding elephants brandishing various weapons. Mara is sometimes depicted as a vulture. In the Hindu tradition, Mara personifies evil and death. Mara is the same as the Hindu death demon Mrtyu. Compare Mara to Garuda (Hindu). *See also* Akshobhya; Buddha; Kama.

Marakayikas (Japan) Also known as: *Ma.* Goblins.

Maramma (India) *see* Gramadeveta; Mariamma.

Marapa (Melanesia)
Afterworld. Some Solomon islanders believe that those with idle souls become the nests of white ants. All the dead can become ghosts in human or animal form.

Maraphius (Greek) *see* Helen.

Marar-Loka (India) *see* Loka.

Marareus (Greek) *see* Aeolus (A).

Mararisvan (Hindu; India)
Lightning and thunder deity. The messenger of Vivasvant. The one who brought fire to mortals.

Marassa (Haitian)
They are twins gods who are likely harvest deities. *See also* Lisa.

www.ebook3000.com

Marathonian Bull (Greek)
As his seventh labor, Heracles had to capture this bull who had ravaged the land. It was finally killed by Theseus. *See also* Heracles; Theseus.

Marawa (Melanesia)
Death god. After Qat created mortals, Marawa tried to follow suit by fabricating humans from a tree. He breathed life into them, but instead of burying them for three days like Qat, he covered them for seven days. They were badly decomposed. As a result man lost immortality. Marawa is a malicious opponent of Qat (q.v.).

Marcra Shee (Irish) *see* Sheehogue.

Mardall (Teutonic) *see* Freyja.

Mardoll (Teutonic)
"Shining One Over the Sea," Mardoll is another name for Freyja (q.v.). *See also* Aesir.

Marduk *Aleyn-Baal, Amaruduk, Asar, Asarri, Ashur* (Assyrian), *Bel Marduk, Belos, Enlil* (Sumeria), *Merodach;* (Akkadia, Assyria, Babylonia, Sumer)
Also known as: *Addu, Agaku, Agilma, Aranunna, Asaru, Asaruali, Asarualim Nunna, Asaruludu, Asharu, Barashakushu, Bel Matati, Dumuduku, Enbilulu, Epadun, Exizkur, Gibil, Gil, Gilma, Gishnumunab, Gugal, Hegal, Irkingu, Kinma, Lugalabdubur, Lugaldimmerankia, Lugaldurmah, Lugallanna, Lugalugga, Malah, Manru, Marukka, Marutukku, Mummu, Namtillaku, Nari, Nebiru, Papalguenna, Shazu, Sirsir, Suhgurim, Suhrim, Tuku, Tut, Zahgurim, Zahrim, Ziku, Zisi, Ziukkinna, Zulum.* (The preceeding forty-nine names are from the "Hymn of the Fifty Names of Marduk.")
King of the gods, supreme god, and god of storm and lightning, Marduk was also known as a sun god, fertility god and patron god of Babylon, which he founded. He is the son of Enki, or Ea and Ninki, or Ea and Damkina. Some say that Marduk was born of Apsu, the Ocean. With the goddess Zerpanitum, he became the father of Nabu, the god of speech and language. Marduk who had invincible courage, became lord and ruler of the gods, a reward for fighting Tiamat and her assistants; a viper, a dragon and the Lahamu. When the moon god Sin was threatened by evil spirits, it was Marduk who fought off his oppressors and routed them, restoring Sin's light. The goddess of evil, Tiamat, arranged a campaign to have her followers of darkness, led by her son Kingu, attack the gods. The deities found out about it and endowed Marduk with the abilities of a magic cloak and the abilities of a magician. The talking cloak gave instructions to Marduk on how to appear and disappear. The deities, impressed to find that Marduk's words were powerful gave him the sceptre, throne and the magic weapon to slay Tiamat. (His father, Ea had killed Apsu with the aid of magic incantations.) After slaying the monster Tiamat, Marduk secured the Tablets of Destiny from the demon Kingu (some say Zu). He used one-half of the skin or body of Tiamat to cover the earth. In other accounts, half of Tiamat's body was placed above the earth as the sky. He kept the sky in place with bars and charged guards with the responsibility of not letting Tiamat's waters escape. Marduk became the chief god of the Babylonian pantheon, and took on the characteristics of Enlil, as well as the attributes and functions of other gods. Marduk constructed Esharra (patterned after Apsu, Ea's abode) as an abode for the great gods. When Marduk went to battle Ea, aside from his magic weapons, he carried an amulet in the form of an eye in his mouth, and herbs in one hand to ward off evil influences. His next step in the creation of the universe was to establish the order of the months according to the moon's changes. From this came the calendar. He also instituted the three celestial ways. In the northern heavens was the way of Enlil, Anu in the zenith, and Ea in the south. The celestial order was under the charge of the planet Jupiter. Next came the creation of mortals to service the gods. Ea suggested that this be done by slaying the demon Kingu and using his blood to fashion the mortals. In other accounts he created mortals with the aid of the goddess Aruru, from clay. Marduk's temple, Esagila was built for him by the gods as a token of their appreciation. Officially he had fifty great names, received by proclamation by command of Anu. Marduk, as Merodach was also the mate of the Chaldaea, Sumer goddess of compassion, Shala. He was often called Bel-Marduk, god of Accad and Sumer after Hammurabi came into power. Some say the word amour came from Amaruduk which was an early form of Marduk. In his role of Tammuz, Marduk later disappeared, according to some research. Marduk is said to be the same as Telepinus, the son of Teshub of the Hattic people. Marduk is the same as Bel of the Babylonian and Assyrian religion (q.v.). Compare Marduk's myth to the myth of Yam-Nahar (Ugaritic). *See also* Aleyin; Anu (B); Anunnaki; Apsu; Aruru; Ashur; Damkina; Ea; Enki; Enlil; Igigi; Isis (Egyptian, who also used magic); Kingu; Lahamu; Nabu; Nebo; Nimrod; Ninki; Rahabh; Sin; Telepinus; Tiamat; Zerpanitum; Zi; Zu.

Mare Goddess (Celtic) *see* Rhiannon.

Maree (Celtic)
Also known as: *Mari* (Crete), *Mouri.*
Maree, the goddess of wells, trees and stones was worshiped in ancient Scotland. There is a record of an ancient goddess of the same name from the Minoan people who was a mother deity. It is remotely possible they are connected. *See also* Mari (India).

Margarme (Teutonic) *see* Hati.

Mari (Hindu; India)
Mari is the goddess of death and diseases found in valleys, or hills. She is worshiped by the Koramas of India and is said to be the same as the Great Mother, Devi. The Koramas also worship Shiva and Vishnu and venerate holy stones, trees and isolated areas, where they believe demons and spirits dwell. Mari is depicted with four hands, holding a trident, skull, rope and a drum. She is possibly the same as the ancient goddess of Crete with the same name. *See also* Bhavani; Devi; Maree (Celtic); Shiva; Vishnu.

Mariamma *Maramma, Marimata* (Gramadeveta) (India)
The goddess of smallpox, and other diseases. It is thought by some researchers that she is not an ancient deity and may have been named after the Virgin Mary. However, there is a group of ancient deities, the Gramadeveta, who are known in Mysore as Mariamma and Maramma. *See also* Gramadeveta.

Marica (Roman)
The name for the Greek sorceress, Circe (q.v.).

Marichi (A) *Marici, Marishi.* (Buddhistic Hinduism; India)
Also known as: *O-zer-chem-ma* (Tibet), *Tou Mu* (China), *Ushas.*

She is the ray of dawn comparable to the Hindu Ushas except that Marichi is frightening. Some say she that she is a terrible goddess who emanates from Vairocana. Others feel that she is a forerunner of Vairocana. In some references she is called the mother of Gautama Buddha. She is portrayed with three faces, one is a boar's snout, and a frontal eye. She has ten threatening arms, her head is crowned with skulls and wreathed in flame. She is depicted variously with a hook, thunderbolt, a bow and arrow, a needle and a cord. Her car is drawn by seven pigs. Marichi is usually accompanied by Rahu, the demon of eclipses and ruler of meteors. *See also* Buddha; Chandi; Marishi-ten (Japan); Maya (A); Tou Mu (China); Ushas; Vairocana.

Marichi (B) (Hindu; India)
The son of Brahma and the father of Kasyapa, Marichi was the chief of the Maruts and a Rishis. *See also* Brahma; Kasyapa (A); Maruts; Rishi.

Marid (Arabic) *see* Jin.

Marimata (India) *see* Gramadeveta; Mariamma.

Marinette (Haitian)
Earth goddess. Wife of Ti-Jean Petro. *See also* Ti-Jean Petro.

Maris (Greek) *see* Ares.

Marisha *Marsha* (Hindu, India)
An Asparasa and goddess of the dew, she is the daughter of the Pramlocha, spouse of Prachetas (Prachetases) and mother of Daksha. *See also* Asparases; Daksha; Pramloka; Urvasi.

Marishi-Ten (Japan)
Also known as: *Marichi-Bosatsu, Marichi-Deva.*

God or Goddess of warriors. Goddess of first light. She is invisible and rules the light that appears in the sky before the sun. She guards warriors against the weapons of their enemies. In some versions Marishi-Ten is a male with the same attributes. She is depicted either standing or sitting on one or seven galloping boars. She has two, six or eight arms and holds various weapons including a bow and a sword. Her image was often found on warrior's helmets. Marishi-Ten wears a costume of a Chinese lady and holds a fan. Compare her to Ushas the Vedic goddess of dawn and Eos, the Greek goddess of dawn. *See also* Aurora; Marichi (A).

Marocael (Taino People, Antilles) *see* Cacibagiagua; Machchael.

Marri (Babylon) *see* Adad; Mari.

Marru (Babylon) *see* Adad.

Marruni (Melanesia)
Creator. Earthquake deity. Called the "earthquake." He cut pieces from his tail to create people and creatures of the land. Has a human body ending in a snake's tail. Similar to Bunosi (q.v.).

Mars (Roman)
Also known as: *Ares* (Greek), *Heru-khuti,* (Egypt), *Mamers, Mavors* (Roman).

God of war. God of agriculture. God of prophecy. Patron of husbandmen. Patron god of the city of Florence. Mars is one of a triad of high gods with Jupiter and Quirinus. He is the son of the weather god, Jupiter, and Juno, the goddess of marriage, or Juno and a mystical flower, or Juno alone. His spouse was the minor goddess Nerio. Mars became the father of Romulus and Remus by Rhea Silvia, and the father of Amor by Venus. His sacred shield, the Ancile, was guarded by his priests, the Salii. His sacred bird is the vulture. As the god of prophecy he is attended by Picus, the woodpecker. In time, Mars assimilated to the Greek god Ares, but unlike his counterpart, was extremely popular. Compare Mars to the Vedic Indra, and Norse Thor. *See* Ana-Purna; Ares, Discordia; Esus; Picus; Silvanus. Compare Mars to the Vedic Indra and the Norse Thor. *See also* Ana-Purna; Ares; Discordia; Esus; Silvanus.

Mars the planet (Greek) *see* Eurynome (A).

Marsalai (Melanesia)
Malevolent guardian spirits of the hunting grounds, they inhabit rocks, pools, and holes. The Marsalai are dangerous to child-bearing women and can cause miscarriages and stillbirths. They can also cause earthquakes, winds, landslides and floods. These spirits are generally depicted as a striped or two-headed snake or lizard.

Marsyas (Asia Minor, Greek)
Also known as: *Marsyas-Masses* (Armenian).

River deity. Son of Hyagnis, the lightning god. A Seleni (woodland satyr) who was flayed to death by Apollo for playing one of Athena's cast-off flutes. As Marsyas-Masses he is also a flute-playing river god. He is probably shown as a satyr. He could be a tribal god similar to Hyagnis, then changed to Vahagn by the Phrygians. *See also* Hyagnis; Vahagn.

Marsyas-Masses (Armenian) *see* Marsyas.

Martanda *Marttanda Savita, Surya, Vivasvan, Vivasvant, Vivasvat* (The Bright One); (Brahman; India)
Martanda, one of the Adityas and the eighth son of Aditi, emerged from an egg as a shapeless lump. His mother took one look at him and threw him away. The divine moulder took the compound and created the god Martanda. The excessive material fell to earth and became elephants. In early times, Martanda was an attribute of the sun, and later became a sun god. Some legends indicate he was the forerunner of Vishnu and Pushan. Martanda, the personification of the setting sun, daily crosses the sky. His chariots are drawn by seven red or white horses. *See also* Aditi; Adityas; Varuna; Vivasvat. He is associated or identified with Vishnu and Pushan (qq.v.).

Marttanda (India) *see* Martanda.

Martu (Mesopotamia; Sumer)
A relatively minor god. He is associated with the god Numushda (god of the city, Kazailu). His wife is the daughter of this god. The daughter is unnamed, but is referred to as the Lady of Ninab, or the Lady of Kazailu. There was a tribe of nomadic Semites living to the west of Sumer, who were called the Martus.

www.ebook3000.com

Daily Practice: Opening, Connecting and Activating Chi Within and Cosmic Charging

Paradoxically, in order to project ourselves out into the immensity of the galaxies and the universe to gather limitless resources of Cosmic Chi for healing, we must take the first steps of the journey within ourselves. In order to 'go out', we must first 'go in'. The vehicle for this magical journey is powered by our ability to relax in mind and body. As we physically relax and let go of muscular and emotional tensions and joint and bone structures we gain access to the inner realms by turning on our very special subtle smile. It opens the pathways of the parasympathetic nervous system. This helps us to reduce the out flowing habits of our senses so that we can be more alert in sensing our inner universe.

This simple process of 'going in' enables us to develop our internal skills so as to safely 'go out' to the universe.

Practice

Relax and Let go - Smile to Connect with the Universe Within

Smile to mideyebrow, eyebrows, eyes, mouth, jaw, tongue, lips, cheeks, ears, shoulders, ribcage and brain. Let the relaxed sensations and the 'Observer Mind' (Upper Brain) sink down into the Lower Tan Tien.

1. Smile to the mideyebrow. Relax and let go. Smile to the eyebrows and let them grow long to the sides. Lower these relaxed sensations down to the Tan Tien.



Fig. 3.5 *Smile and Relax to the Mideyebrow and think of the eyebrows growing long.*

Martummere (Australia) *see* Nurrundere.

Maru (North Island Maori, Polynesia)
Also known as: *Tu Matauenga.*
Commander of the Heavenly Hosts. War God. On the South Island, Maru is known as Tu Matauenga. Maru is called upon by war leaders to be with them during battle and to ensure that they will emerge as victors. He has a huge fire that is used to burn the demons he has vanquished.

Marukka (Babylon) *see* Marduk.

Marumda (Pomo People, North America)
With his brother Kuksu, Marumda created the world. First they attempted to destroy their creation by fire and then by water. They were rescued by the mother goddess Ragno (q.v.). *See also* Kuksu.

Marunogere (Melanesia)
God of females. He created the first female sex organs by boring holes into women.

Marut (India) *see* Vayu.

Maruta (India) *see* Vayu.

Maruts (Vedic, Hindu; India)
Also known as: *Rudras, Rudriyas, Sons of Rudra.*
The fast-flying Maruts, storm spirits, gods of the hurricane and warriors are the sons of Rudra and Prisni, the cow goddess, who is also known as the goddess of the dark season. Some sources name the goddess Diti, also known as Danu, the mother of the giant Daityas, as the mother of the Maruts. The Maruts were all born at the same time in the form of a lump. Rudra-Shiva took the lump and shaped it into the attractive youths. In other renditions, Shiva as a bull, fathered them with Prithivi, who was in the shape of a cow. They were said to have been separated in the womb by Indra. Vayu the wind god is another deity named as the father of the Maruts. Rodasi, the wife of Rudra is a companion of the Maruts. She frequently rides in their chariot across the sky. They are known as cohorts of the war gods and constant companions of the storm god Indra. They are usually numbered at forty-nine but some sources say there are twenty-one Maruts. In the *Rig-Veda*, there are said to be twenty-seven, or one hundred and eighty Maruts. Their weapons are used to penetrate the cloud-cattle and cloud-rocks, releasing torrents of rain. In some accounts, they assisted Indra in his battles with the dragon Vritra. The Maruts are companions and allies of Indra and they reflect his personality. Storm gods, they ride on whirlwinds, flashing lightning and creating thunderous sounds. They incorporate playful and war-like aspects at the same time. In ancient texts, they are known as the Rudras and were considered duplicates of Rudra, the god of the dead. In later times, when Rudra became a celestial being, the Maruts became gods of the atmosphere. The Maruts are depicted as gay youths and alternately fearsome warriors. They wear bright skins, golden helmets and breastplates. Their ankles and wrists are adorned with gold bracelets. Cleanliness is important to the Maruts. They delight in scrubbing one another clean. Their weapons are bows, arrows, axes and gleaming spears. They ride in a golden-wheeled chariot drawn by three deer. Maruts is not to be confused with the singular Marut or Maruta which refers to Vayu. Compare the Maruts to the Greek Curetes. *See also* Aditi; Adityas; Daityas; Devi; Diti; Indra; Marichi (B); Prithivi; Ribhus (the); Rudra; Swarga; Varuna; Vasus; Vayu; Vedas (the).

Marutukku (Babylon) *see* Marduk.

Marzyana *Marzann* (Slavic)
Earth mother or grain goddess. She is identified with Ceres. *See also* Datan.

Masa-katu-a-katu-kati-paya-pi-ame-no-oso-po-mimi-no-mikoto (Japan) *see* Amaterasu.

Masaka-yama-tsu-mi (Japan)
God of the steep mountain slopes. *See also* Naka-Yama-Tsu-Mi; O-Yama-Tsu-Mi; Sengen.

Masan (Hindu; India)
Deity of disease. Masan comes from the ashes of the funeral pyre and causes illness in children by throwing ashes over them. He is sometimes shown as a child or a bear and is generally black in color.

Masauwu (Hopi People, North America)
God of death. Some say he is a god of fire and war.

Masaya (Aztec People; Nicaragua)
Underworld goddess. She rules the volcanos and causes earthquakes. Bad souls go to her domain. She shares the underground with Mictanteot.

Masewi and Oyoyewi (Acoma People, North America)
War Spirits. The Twins. For other Acoma deities, see Iatiju; Kastiatsi; Katsinas; Pishumi; Shk; Shruistha.

Mashkhith (Hebrew) *see* Af (C).

Mashtu (Babylon)
She is the goddess of the moon, brother of Mashu, and daughter of Nannar.

Mashu (Babylon)
Moon god. Brother of Mashtu the goddess of the moon. Both are children of Nannar. Some say they resemble Hyuki and Bil of the Teutonics. See Nana (B).

Mashya and Mashyoi *Masha and Mashyoi* (Persia, India, Iran)
First humans. They are the two humans who were from the seed of Gaya Maretan. They in turn gave birth to Fravak and Fravakain and Siyamek and Siyameki (sometimes called Siyakmak and Nashak). They are the ancestors of the human race. Mashya and Mashyoi grew up under the form of a tree. (The Greek Corybantes were born as trees; Attis was born from an almond tree and Adonis from a myrtle tree.) Their mythology is comparable to legend of Adam and Eve. *See also* Ahura Mazda; Angra Mainyu; Drujs; Gaya Maretan; Hushang.

Masli (India) *see* Parvati.

Maslum (Algonquin People, North America) *see* Gluskap.

Massim-Biambe (Mundang People; Africa)
Creator deity. The son of Phebele (male principle) and Mebeli (female principle) received the soul (tchi) and life from

Massim-Biambe. This son was called Man. Since Massim-Biambe is invisible he can only be contacted through objects called Grigris.

Mat (Egypt) *see* Maat.

Matali (India) Indra's celestial chariot driver. *See also* Indra.

Matarisvan *Atharvan* (India)

A demigod, Matarisvan is the author of the fourth Veda. He is sometimes listed as a Rishi. *See also* Agni; Rishi.

Mater Matuta (Roman)

Also known as: *Leucothea* (Greek).

Goddess of birth. Mater Matuta is said to be a dawn goddess also known as the Greek Leucothea, the White Goddess, a goddess of the sea. She began her life of tragedy as Ino, the daughter of Cadmus and Harmonia. *See also* Cadmus; Dionysus; Harmonia; Hera; Ino; Semele.

Mater Turrita (Greek) *see* Cybele.

Math (Celtic)

Also known as: *Math Hen* (old math or ancient), *Math Mathonwy* (Welsh).

God of sorcery. Benevolent deity. Shape shifter. Math is an ancestor of the House of Don, the son of the sky deity Mathonwy and the brother of the goddess Don. He is the uncle of Arianrhod, Gwydion and Gilvaethwy. A skilled magician, he taught his art to his nephew Gwydion. It is said that he was so sensitive that he could hear the slightest sounds of the world. Math's feet were extremely important for they held the key to his vulnerable spot, perhaps in his heel. When he wasn't in battle it was necessary for him to have a footholder. This task, considered an important position, entailed having his feet held in the lap of a virgin female. When his footholder, Goewin, was raped by his nephew Gilvaethwy, he married her in an attempt to eradicate her shame. He was known for his beneficence to those who had suffered and his fairness in meting out punishment without being vindictive. Compare Math to Dagda. *See also* Arianhrod; Don; Gwydion; Llew Llaw Gyffes.

Math Hen (Celtic) *see* Math.

Math Mathonwy (Celtic) *see* Math.

Matholwch (Celtic) *see* Bran; Branwen.

Matholwych (Celtic) *see* Bran; Branwen.

Mathuranath (India) Lord of Muttra. *See also* Krishna.

Matuka (Polynesia)

He is the giant cannibal killed by Rata, the hero-god. *See also* Rata.

Mati-Syra-Zemlya (Russian, Slavic)

Also known as: *Mother Earth Moist.*

Earth goddess. The ancient Slavic People and Russians worshiped Earth as a divinity. She was possibly a deity of foretelling the future or a deity of justice.

Matlalcueje (Aztec; Mexico)

Rain goddess. Companion of Chalchiuhtlicue.

Ma't'outt Naing (China) *see* Ts'an Nu.

Matri Mother (India) *see* Devi.

Matrikas (India) *see* Ganda.

Matris, The (India) *see* Ganda; Karttikeya; Shakti.

Matrona (Celtic) River goddess. *See also* Sequana.

Matronae (Celtic)

Also known as: *Matres, Matres Britanne* (Roman), *Modron.*

Mother goddesses. They are the three mother-goddesses who oversee fertility. The Matronae are lovers of peace, tranquility and children. In one version the Romans gave them the name Matres and considered them goddesses of fate. In another version Modron was the wife of Urien who was an underworld deity. She was also the mother of Mabon. As Modron, the Welsh "Great Mother," she is comparable to Dana. *See also* Mabon.

Matrs (India) Female Demons. *See also* Ganda.

Matsya (Hindu; India)

Matsya the fish is thought by many to be the first avatar of Vishnu. However, in the *Bhagavata-Purana*, Matsya is the tenth incarnation of twenty-two. He came as tiny fish into the hands of Manu Vaivasvata, the seventh Manu. Matsya begged to be allowed to live, and promised Vaivasvata in return to save him from the impending Great Deluge. Matsya grew so swiftly that Vaivasvata thought he would be happier in the ocean. Once in his natural surroundings, Matsya was able to give instructions to Vaivasvat for building the ship to save himself. On board was the seed of all plant life and pair of all living creatures. When the flood came, only a great horned fish, Matsya, the avatar of Vishnu, could be seen. Manu Vaivasvata moored his ship on Matsya's horn and was saved. Vishnu, in his form as Matsya is credited with teaching Manu the law. A Manu (Father) is one of fourteen patriarchs, each of whom was a ruler of the earth for one period of its history. The first Manu, an emanation of Brahma was Svayam-bhuva. In another episode, Brahma is asleep during a period of universal chaos. The sacred Veda slips from his mouth, and the demon Hayagriva absconds with it. Matsya comes to the rescue, slays the demon and restores the Veda. In a later version of this myth, recorded in the *Mahabharata*, the fish responds that he is Brahma Prajapati, the creator of the Brahmanas. Some researchers liken Vaivasvata to Noah. This myth, recorded in the *Mahabharata*, is similar and often confused with the myth from the *Satapatha Brahmana*. For details, see Manu. *See also* Kurma (Vishnu's avatar as a tortoise); Prajapati; Vasuki; Vishnu.

Matsyendranatha (Nepal)

He is a "god-saint" who brought salvation to Nepal. Identified with Avalokitesvara, his followers practice a blend of Buddhism, Hinduism and popular religion. He is propitiated as the god of salvation and rain.

Matu-'u-ta'u-ta'ua (Tahiti)

A giant bird that swallows men. *See also* Makemake.

Maturang (Oceanic)

He is the possible son of the creator spider god, Nareau (q.v.).

www.ebook3000.com

Mau (A) (Egypt)
Meaning "mew," Mau is an alternate name for the fire and cat goddess Bast (q.v.).

Mau (B) (Oceanic) *see* Maui.

Mau-aa (Egypt) *see* Aai.

Maudgalyayana (India)
He is the equivalent to the Chinese Mu-lien, who is the assistant to Ti-tsang-wang-pu-sa, the god of mercy.

Maui *Mowee* (Polynesia, New Zealand, Samoa, Hawaii, New Hebrides).
Also known as: *Amoshashiki, Ma-tshiktshiki, Mau, Maui-tikitiki, Maui-tukituki, Milu, Mosigsig, Motikitik* (Micronesia), *Rupe, Tiitii* (Samoa).
Sun god, later a culture hero. Inventor of fishing and sailing ropes. Inventor of the fish basket. Inventor of kite-flying and dart-throwing. Creator of the dog. A Kupua (trickster spirit). Son of Mahuika or Ta-ranga, and Ru. The number of brothers he has depends on the legend. Sometimes he does not any siblings. Other times he has three, four or six brothers. In the Maori tradition, his father is Makea-Tutara, the chief of the underworld and his mother is Taranga. Within this family structure he is the youngest and ugliest of five sons. His brothers are Maui-Taha, Maui-Roto, Maui-Pae, and Maui-Whao. It happened that Maui came into the world prematurely as his mother was walking along the beach. His body had not yet taken form. She wrapped him with her hair and put him into the sea. Sea fairies came upon him and nursed and cared for him, until a terrible storm came along and routed him from his hiding place in the kelp. He was thrown back onto the beach. An ancestor, Tama-Rangi, happened upon him and through his tales and songs of Maui's people awakened him to life. Maui then began his travels and eventually found his family. His adventures were many as befits a culture hero. Once, deciding that the days were too short and the nights too long, he starved his grandmother to death so he could have her magic jawbone. Maui used the jawbone to beat the sun into slowing its daily travels. The benefit for mortals was longer hours of light for work. He also used the magic jawbone as a hook for fishing. On one ocassion, his catch was a huge fish. He instructed his brothers not to touch it until he returned from giving thanks. They ignored his request and cut the fish raggedly in two sections. It jerked and squirmed and threw itself around. The fish was the island of New Zealand. Maui, who was mortal because his father forgot to bestow immortality upon him, also controlled the winds and arranged the stars. Many tales illustrate how he managed to get fire. Usually it was by trickery, fighting for it, or stealing it. Often the goddess of fire, Nahui-Ike, who resided in the Underworld is the individual who is tricked into giving him fire. The fire went from him as a gift to his people. There was a time when Maui was highly perturbed with his wife for not feeding him on time. She was involved romantically with someone named Ri. Maui turned Ri into a dog. It could have been avoided if he had been fed on time. There are myths where Maui's brother-in-law Ira-waru was changed into a dog. In this instance Maui has a sister, Hina-uri. Some call him the eight-headed Maui. He was variously known as Maui-of-a-thousand-tricks, Maui-tupua-tupa, Maui-the-wise, Maui-tikiti-ki-a-Taranga, Tama-nui-a-te-ra. Maui is associated with Atea, Ru, Tane, and Hina. He was said to have defeated Tuna. Sometimes Maui is associated with Mokoroa the shark, and he is even said to be the son of Tangaroa. Sometimes he is similar to Lumauig, Matuarang, and Qat. Many of the feats credited to Maui also appear in legends of Tangaroa. Maui is likened to the Greek Ulysses (q.v.) *See* Hina; Kupua; Mafuike; Motikitik; Nareau; Qat; Tuna.

Maui-tikitiki (Polynesian) *see* Maui; Motikitik.

Maui-tukituki (Polynesia) *see* Maui.

Mauna (Native North American People) "The Earth Maker."

Maut (Egypt) *see* Apet; Maat.

Mauti (Egypt) *see* Aai.

Mave (Celtic) *see* Maeve.

Mavors (Roman) *see* Mars.

Mawa-Lisa (Africa) *see* Lisa.

Mawu (Africa) *see* Mahu.

Mawu-Lisa (Africa) *see* Lisa.

Maya (A) *Maia* (Buddhist; India)
Also known as: *Mahamaya, Mayadevi, Shakti.*
Maya was the spouse of Rajah Suddhodana (sometimes called Sedowdhen or Siddown). He was the chief officer of the Sakyas, a small Aryan tribe. They lived in Kapilavastu, the capital of Shakya, about one hundred miles northeast of Benares and thirty to forty miles south of the Himalayas. Maya was chosen as the mother of Gautama Buddha. The Bodhisattva appeared in a dream, entering her womb (or right side) in the form of a pure white, six tusked elephant. It was predicted that the child's destiny would lead him to the life of an ascetic or universal ruler. After his birth a huge ceremony was held to name him. Eighty thousand relatives, and one hundred and eight Brahmins attended. Gautama had one hundred godmothers. Maya died of joy seven days after her son's birth and he was raised by her sister Prajapati. When he renounced the world to live as a monk, Gautama became known as Sakyamuni and Siddartha. Maya is generally depicted as lying on her left side. Sometimes she is shown sitting on a lotus. Two elephants sprinkle her from waterpots they hold with their trunks. Marichi is also said to be the mother of Siddartha. In Ceylon, the goddess Avany is known as the mother of Sakyamuni. For additional details of Gautama's birth see Buddha. *See also* Indra; Kadru; Lokapalas; Marichi (A); Maya (B); Nagas; Sakyamuni; Sesha; Shakti; Sri.

Maya (B) (Hindu; India)
Also known as: *The Goddess of Fantasy, The Goddess of Illusion, Maya-Devi* (Powerful Goddess), *Maha-Maya, The Universal Mother, The Universal Shakti.*
The daughter of Anrita and Adharma, Maya is the spouse of Brahma and the mother of a daughter, Sumaya. In later times, she was identified with Kali-Durga. *See also* Adharma; Anrita; Maya (A).

Maya (C) (Hindu; India)
He is the father of Mandodari who married the demon Ravana. Maya, an architect, built a palace for the Pandavas. *See also* Mandodari; Pandavas; Ravana.

Maya People — Creation Legend (Yucatan) *see* Ahmucen-Cab; Ajtzak; Xumucane.

Mayadevi (A) *Mayavati* (India)
Mother/wife of Pradyuma, she is identified with Rati. *See also* Kama (A); Krishna; Pradyuma; Rati.

Mayadevi (B) (India) *see* Maya (A).

Mayauel *Mayahuel* (Nahua People, Aztec People, Mexico)
Goddess of pulque and childbirth. A mortal woman, Mayauel discovered the intoxicant pulque from a mouse who was drinking from an agave plant. Her discovery led to her deification. In another version she was a many-breasted goddess who was transformed into the maguey (agave) plant becaused of her fruitfulness. Some legends say she suckles a fish. The agave plant is regarded as the Tree of Life by the Nahua people. It is believed that Xolotl nursed the first man and woman created by the Aztec gods from its milk. Mayauel is sometimes shown sitting on a cactus plant with a looped cord to show that she helped women in childbirth. Night is her special time. Mayauel is possibly shown as a white fox or coyote. She is frequently depicted with four hundred breasts, seated on or in front of the agave plant. Mayauel is sometimes associated with Quetzalcoatl. *See also* Xolotl.

Mayavati (India) *see* Mayadevi (A).

Mayochina (Acoma People, North America)
Deity of summer. The Summer Spirit. For other Acoma deities, *see* Katsinas.

Mayon (Tamil People, India)
He is an ancient god comparable to Krishna.

Mba (Babua People, Eastern Sudan) *see* Bele.

Mbamba *Mbambe, Mpambe* (Wakonde People, Africa)
Also known as: *Kiara.*
A supreme god, Mbamba lives above the sky. He is associated with Leza and Nyambe who represent the sun. Mbamba is shown in human form and is white and shining.

Mbambe (Africa) *see* Mbamba.

Mbir (Guarayu People, South America)
Also known as: *Miracucha.*
Creator. Mbir is a worm, generally shown in human form, who created and shaped the world. He could be the same as Mbere, the creator god of the Fans.

Me (Sumer) *see* Nabu.

Me-phem-pa (Tibet) *see* Ajita.

Me-tog-ma (Tibet) *see* Pushpema.

Meabel (Celtic) *see* Dagda.

Meadhbh (Celtic) *see* Maeve.

Meave (Celtic) *see* Maeve.

Mechaneus (Greek) "Manager and Contriver." An epithet of Zeus.

Mecisteus (Greek)
One of the Seven Against Thebes. His parents are Talaus and Lysimache or Lysianassa. His son is Euryalus. Mecisteus was killed by Melanippus. *See also* Adrestus; Astynome; Pronax.

Mecurius (Roman) *see* Hermes; Mercury (A).

Mede (Greek)
Mede is another name for Periboea, the wife of Icarius and the mother of Penelope.

Medb (Celtic) *see* Maeve.

Medea *Medeia, Medeias, Medeius, Medus* (Greek)
Sorceress. Medea is the daughter of Aeetes and Eidyia, sister of Absyrtus and half-sister of Chalciope. A sorceress, taught by her aunt Circe, she could use her powers for good or evil. Jason of Ioclus, the handsome leader of the Argonauts, arrived in Colchis in quest of the Golden Feece. Medea met him and fell in love. Unknown to her, this arrangement had been preordained by the goddesses Hera and Athene, who had personal agendas. King Aeetes agreed to relinquish the Golden Feece under seemingly impossible conditions. Medea agreed to assist Jason in his quest if he promised to take her with him on the Argos and marry her. He swore to do so. Medea used her powers to lull the dragon who guarded the fleece so that Jason could steal it and then fled Colchis with him. King Aeetes, who never intended to part with the fleece threatened to burn the Argos and massacre the crew and he set out in pursuit of them. Under false pretenses, Medea arranged a secret meeting with her brother Apsyrtus, who met her on an island where he was killed, chopped up and thrown into the sea. (*See* Apsyrtus.) Medea and Jason moved to Corinth, had sons (Alcimedes, Argus, Eriopis, Medeius, Mermerus, Pheres, Thessalus and Tisandrus) and lived quietly for ten years. The Golden Fleece was hung in the temple of Zeus at Orchomenus. The ambitious Jason, renowned for his early adventures, accomplished only because of Medea's powers, decided to divorce her and marry Glauce (also called Creseusa and Creusa), the daughter of the King of Corinth. Infuriated, Medea made Glauce a magnificent wedding gown. When she tried it on it burned her flesh away and she died in agony. Her father also perished while trying to save her. Medea also killed her sons (except possibly Thessalus), either out of revenge or to save them from living in exile. Again, accounts of her adventures differ; she was said to have had two sons whom she murdered. She escaped from Corinth on a sky-borne chariot driven by two dragons, a gift from her grandfather, Helius. She fled to Thebes hoping for protection from Heracles, whom she cured from the insanity that caused him to kill his children. He was too involved with his labors to be of help so she went on to Athens. The aging King Aegeus promised her protection if she would give him the children he had been denied. He did have a son, Theseus, but at the time he was unaware of his existence. He married Medea and they had a son, Medus (Medeias, Medeius). Eventually, Theseus turned up at the court. Medea, fearful that he would claim the throne tried to have him killed. (*See* Theseus.) Aegeus discovered that Theseus was his first son, and it was he who convinced his father to exile Medea. (See Medus). According to some renditions, after her death Medea became a consort of Achilles in the Elysian Fields. Others say that she was worshipped as a goddess.

www.ebook3000.com

See also Aeetes; Apsyrtus; Argonauts; Ariadne; Golden Fleece; Helius; Jason; Medus; Pheres (A); Theseus.

Medecolin (Algonquin People, North America)
A sorcerer. *See also* Gluskap.

Medeias *Medeius, Medus* (Greek)
He is the son of Jason or Aegeus and Medea. *See also* Medea; Medus; Pheres (A).

Medeius (Greek) *see* Medea; Medus.

Medha (India)
She is possibly one of Daksha's daughters and the spouse of Dharma. *See also* Daksha; Dharma.

Medi Kenaga (Fox People, North America)
Deified animal. The Great Snapping Turtle.

Medica (Roman)
An epithet of the goddess Minerva as the patroness of physicians.

Medicine Buddhas (Buddhist; Tibet)
Also known as: *Abheda, Mi-che-pa* (Tibet), *Mi-p'yed* (Tibet).
The Medicine Buddhas are usually found in two groups, one of eight and one of nine, seated in a meditative pose. They wear monastic robes without ornanments. They wear the sign of insight on their foreheads (urna), their hair is styled in a high chignon (usnisa), the symbol of supernatural wisdom, and they usually have long ear lobes. *See also* Abheda.

Medini (India) Mother of the planet Mars. *See also* Bhumi.

Medus (Greek)
Also known as: *Medea, Medeias, Medeius.*
Medus is thought to be the son of Medea and Aegeus, king of Athens. Hesiod claimed that Jason was Medus' father and that Cheiron raised him. After Medea attempted to murder Theseus, whom she suspected would inherit the throne, she and Medus were driven from Athens and went to Colchis. Aeetes, her father the former king of Colchis, was by some accounts killed by his brother Perses. Perses had been warned that a descendent of Aeëtes would seek revenge, so when he heard of the arrival of Medus he imprisoned him. Medea, impersonating an ancient priestess promised to end the plague in the area if she could have Medus to use in her sacrifical rites. Perses agreed and was slaughtered by the sword of Medea given to Medus, thus avenging his grandfather. Other accounts say that it was Medea who killed her father Perses. Medus went on to conquer the land to the east and named it Media although some believe that Medea named it in honor of herself. *See also* Aeetes; Medea; Perses.

Medusa (Greek)
Also known as: *Medousa.*
A Gorgon. Medusa is the daughter of Phorcys and Ceto. Her lover, who is possibly her husband, Poseidon, is the father of her children, Pegasus and Chrysaor. She is also to be the mother of Caca and Cacus by Vulcan. Her siblings are Echiodna, Euryae, Stheno, Scylla, Ladon and the Graiae. The goddess Athene, enraged that she had slept with Poseidon in one of her temples, changed the once beautiful Medusa into a Gorgon monster. Perseus, jealous of her affair with Poseidon, decapitated her. Some think that Athene guided his sword. From the blood of her body her twin sons, Pegasus the winged horse and Chrysaor the warrior-giant, were born fully grown. Not only did Athene wear Medusa's head in the center of her aegis but she is said to have given two vials of Medusa's blood to Asclepius the healer. With the blood from her left side he was said to be able to raise the dead and with the blood from her right side he could destroy instantly. Other myths say that she divided the blood and Asclepius used his share to save people while Athene used her share to kill and instigate wars. Medusa's gaze turned men to stone and her blood populated the Libyan desert with snakes. Her body was buried in the marketplace of Argos. As a Gorgon, Medusa is depicted with wings, glaring eyes, huge teeth, a protruding tongue, and claws. Her hair is full of serpents. *See also* Aegis; Athene; Caca; Ceto; Chrysaor; Gorgons; Graiae; Oceanids; Pegasus; Perseus; Poseidon; Scylla; Vesta.

Megaera *Megaira* (Greek)
One of the three Furies. She is the daughter of Gaea. Her siblings are Alecto and Tisiphone (qq.v.) *See also* Calchas; Erinyes; Eumenides; Eurydice; Furies; Heracles.

Megaira (Greek) *see* Megaera.

Megara (A) (Greek)
Megara is the daughter of the king of Thebes, Creon, and Anioche or Eurydice. Her siblings are Enioche, Haemon, Menoeceus and Pyrrha. She married Heracles. *See also* Creon; Pyrrha.

Megareus (Greek)
Ruler of a portion of Boeotia. He married Iphinoe and became the father of Evaecheme, Evippus, Hippomenes and Timalcus. *See also* Adrestus; Evippus; Hippomenes.

Megh Sambara (Nepal) *see* Manjusri.

Megin-giord *Megingiord* (Norse; Teutonic)
Also known as: *Megingjardir.*
This is Thor's magic belt. His strength is doubled when he wears Megin-giord.

Megingiord (Teutonic) *see* Megin-giord.

Megingjardir (Teutonic) *see* Megin-giord.

Meh-Urt (Egypt) *see* Amen (B).

Mehen (Egypt)
Mehen, a great serpent deity, is responsible for protecting Ra from the monster Apophis on his journey to Tuat. Mehen is mentioned in the First Division (First Hour) of Tuat, in the Seventh Hour, and in the Eighth Hour. The gods pulled the sun boat of Ra at Mehen's command. When the sun god is depicted traveling across the night sky he appears with a cabin around him and the serpent coiled protectively around the cabin. She is mentioned as a serpent goddess in the ancient "Hymn to Amen-Ra." *See also* Ab-esh-imy-duat; Akeneh; Apepi; Apophis; Nekhbet; Shepes.

Mehendra (India) *see* Indra.

Mehit (Egypt)
Supreme goddess. Mehit, the wife of Anhur, is identified

with Tefnut. She is depicted with the head of a lioness. *See also* Anat; Anhur.

Mehu (Philippines) *see* Finuweigh.

Mehueret (Egypt) *see* Neith.

Meiden (Lithuania) God of animals and forests.

Meido (Japan) *see* Yomi.

Meilanion (Greek) *see* Melanion.

Meili (Teutonic) *see* Odin.

Meilichios (Greek)
Meilichios is the name of Zeus when he is in serpent form.

Meion (Greek) He could be the father of Cybele (q.v.).

Mekel (Sumer) *see* Nergal.

Melampus (Greek)
A talented mortal who could speak to and understand animals, Melampus became known as the greatest of all prophets. He was unable to cure Iphinoe, a follower of Bacchus, the Greek god of wine, of insanity. Her sister, Lysippe, became the wife of Melampus. His children are Abas, Antiphates and Mantius. *See also* Abas (B); Argonauts; Bacchus; Iphinoe; Lysippe; Proetus.

Melanesia — Creation Legend *see* Agunua.

Melanion (Greek)
His father is Amphidamas and his brother is Antimache. Either Melanion or Hippomenes married Atalanta. When Melanion and Atalanta were caught having sex in a sacred place they were turned into lions. *See also* Atalanta; Hippomenes.

Melanippe (A) (Greek)
Also known as: *Arne*
Her parents are Aeolus, the son of Hellen, and Hippe, the daughter of Cheiron, the immortal Centaur. Her children by Poseidon, Aeolus II and Boeotus were taken from her by Aeolus, when they were very young. Aeolus also blinded Melanippe. Initially they were cared for by a cowherd, but later they were adoped by Theano, the wife of Metapontus, who already had two sons. The four young men fought and Theano's sons were killed by Melanippe's sons. Her heart heavy with grief, Theano committed suicide. Poseidon cured Melanippe's sight and she married Metapontus. *See also* Aeolus (B); Ares; Arne; Theano.

Melanippe (B) (Greek)
This is another name for the Amazon queen, Antiope.

Melanippus (A) (Greek)
He is the son of Astacus of Thebes. *See also* Acamas (A); Adrestus.

Melanippus (B) (Greek) The son of Ares.

Melas (Greek)
Melas is the son of Licymnius and Perimede and the brother of Argeius and Oeonus. While assisting Heracles in a fight against Eurytas, he was killed. It was Eurytas who taught Heracles to use a bow. When Eurytas would not give Heracles his wife Antiope, Heracles killed him. *See also* Calydonian Boar Hunt; Eurytus; Phrixus.

Melatha (Choctaw People, North America)
Deified animal. Male Lightning Bird.

Meleager (Greek)
He is the Argonaut son of Ares or Oeneus and Althea. He married Cleopatra, the daughter of Idas, and became the father of Polydora. It was Meleager who killed the Calydonian Boar. When the Curettes attacked the Calydonians, Meleager was killed. The goddess of the hunt, Artemis, changed him into a guinea-fowl. *See also* Aeetes; Althea; Ares; Argonauts; Artemis; Calydonian Boar Hunt.

Melech (Middle Eastern) *see* Moloch.

Melekh (Middle Eastern) *see* Moloch.

Melesians (Irish) *see* Amergin.

Melete (Greek)
Melete is the Boeotian muse of practice. Her sisters are Aoide, the muse of song, and Mneme, the muse of memory. *See also* Gaea; Mneme; Uranus.

Melgart (Carthage) *see* Heracles.

Melia (Greek)
She is the daughter of Oceanus and Tethys. She is the sister/wife of Inachus and the mother of Aegialeus, Io and Phoroneus. She became the mother of Ismenius by Apollo. *See also* Apsyrtus; Inachus; Io; Meliae; Oceanus; Tethys.

Meliae (Greek)
Ash nymphs. The Meliae, nymphs of manna ash trees, the Giants and the Erinyes sprang from the blood of the castrated Uranus. The ash tree is said to be a sacred tree which was originally used in rain-making ceremonies. The Three Fates dispensed justice under the ash tree and it is said to be one of the goddesses of retribution's (Nemesis') seasonal disguises. One of the meliae, Melia married her brother, the river god Inachus, and became the mother of Phoroneus the first king of Argos; Aegialeus, who some think was the founder of Sicyon; and Io, who was changed into a cow. She may have been the mother of Mycene (eponym of Mycenae). Some say Melia is the daughter of Oceanus and that Argia is the mother of Phoroneus and Io. *See also* Aegialeus; Erinyes; Eumenides; Fates; Gaea; Giants; Inachus; Io; Mycene; Nemesis; Phoroneus; Uranus.

Meliboea (A) (Greek)
Also known as: *Chloris.*
She is the daughter of Amphion and Niobe. Artemis, goddess of the hunt, spared her life and killed her five sisters. Apollo killed her five brothers, sparing Amyclas, according to some. *See also* Amphion; Amyclas; Apollo; Artemis; Chloris; Leto; Niobe.

Meliboea (B) (Greek)
She is the Oceanid daughter of Oceanus and Tethys. Her marriage to the king of Arcadia, Pelasgus, produced a son, Lycaon. *See also* Lycaon; Oceanus; Tethys.

Melicertes (Greek)
Also known as: *Palaemon, Portunas, Portus.*
God of ports and harbors. Melicertes is the son of Athamas and Ino. His mother drowned him and he became the god Palaemon. *See also* Athamas; Ino; Melkart; Palaemon; Portus; Sisyphus.

www.ebook3000.com

Melie (Greek) *see* Amycus.

Melissa (Greek)
Melissa is the daughter of Melissus, the king of Crete. With her sister Amalthea she nursed the infant Zeus. *See also* Adrastia; Amalthea.

Melisseus (Greek)
He is the father of Adrastia and Ida, the nursemaids of the infant Zeus. *See also* Adrastia.

Melissus (Greek)
King of Crete. He is the father of Amalthea and Melissa, the nursemaids of the infant Zeus.

Melkart *Melcarth, Melkarth, Melqart, Melquart* (Ammonite, Phoenicia, Tyre)
Also known as: *Aleyn-baal, Baal, Melicertes, Milcom, Moloch, Palaemon, Palaimon, Palamon.*

Originally a solar deity, but later became god of travelers, sailors, and of the city of Tyre. Melkart, like the phoenix, is regenerated by fire. He is associated with both Baal and the Greek Heracles. Some Greek versions say Melkart's father was named Demarus, the son of Uranus who married his sister and mother, Ashtart (Astarte). Some writers say the Greeks adopted this god and gave him the name Melicertes or Palaemon. As Melicertes, he was the son of Athamas and Ino. Later he became the sea god Palaemon. He was also said to be an opponent of Yahveh. He is sometimes shown carrying an axe or spear in one hand and a shield in the other. He is also shown riding a sea horse. The Egyptians show him with the head of a gazelle. There are those who say he is identical with Moloch. Compare him to the Greek fire god and smith, Hephaistos. *See also* Agrius (A); Aleyn-Baal; Astarte; Attis; Heracles; Tammuz.

Melkarth (Carthage) *see* Heracles; Melkart.

Melpomene (Greek)
Muse of Tragedy. Her name means "singing." She sang mourning songs for dead poets and people of accomplishment. One of the nine Muses, Melpomene is the daughter of Zeus and Mnemosyne (Memory). With Achelous, the river god, she became the mother of the Sirens. She is usually shown with a tragic mask, the buskin (a laced half boot with thick soles worn by actors in Greek and Roman tragedies), sometimes with a lyre or scroll and wearing a crown of leaves. *See* Achelous; Mnemosyne; Muses; Sirens; Zeus.

Melquart (Canaan) *see* Astarte; Melkart.

Memnon (Egypt, then to the Greeks)
King of Ethiopia. He is the son of Tithonus (who was turned into a grasshopper when he grew old) and the goddess of the dawn, Eos. Memnon killed Antilochus, a close friend of Achilles during the Trojan War. Achilles in turn killed Memnon. In fact, he died many times and in many places. Zeus made him one of the Immortals. Hephaistos made his bright armor. Birds (souls) flew from his funeral pyre. Memnon is also a name of one of the gigantic statues of Amenophis III located in Thebes. *See also* Antilochus; Eos; Hephaistos; Priam.

Memphis (Greek)
Her grandparents are Oceanus and Tethys, her father is the river god Nile and her sister is Anchinoe. Memphis married Epaphus, king of Egypt and became the mother of Libya and Lysianassa. *See also* Agenor (A); Apis (A); Libya; Nile.

Memphis Triad (Egypt)
This triad consists of Ptah, Sekhmet, and Imhotep. Sometimes Nefertum replaces one of the three gods.

Men *Min* (Egypt)
Aspect of Khem. He is shown with a thyrsus in his right hand and a pine cone in the left. *See also* Min.

Men Brayut (Bali) *see* Hariti.

Men Shen *Men-Shen* (Buddhist; China)
Also known as: *Ch'en Ch'i, Ch'in Ch'iung, Cheng Lung, Ha, Heng, Heng-Ha-erh-Chiang, Hu Ching-te, Shu Yu and Yu Lei, Snorter and Blower, T'ai-Tsung, T'ien Wang.*

Door guards. Men Shen is the collective name for door guards in early mythology. Shen-t'u and Yu-lu were the right and left deities. One has a red face, the other is black. These were later replaced by Yu-ch'ih Ching-te and Ch'in Shu-pao, who were deified mortals. They were replaced with Heng-Ha-erh-Chiang (Sniffing and Puffing Generals) or T'ien Wang (The Heavenly Kings). It is the job of the door guards to be certain all papers are in order when Ox-head (Niu-t'ou or Gosirsa) and Horse-face (Ma-mien) or the Wu-ch'ang (Mr. White and Mr. Black) come to conduct the souls to hell. In one version the names of two mortal marshals in the military are given. These are Cheng Lung and Ch'en Ch'i, later to become known as Heng (Cheng Lung) and Ha (Ch'en Ch'i) or "Snorter and Blower" respectively. They are generally shown in military garments, holding weapons. The door guards are associated with the Jade Emperor. Sometimes a third door guard is associated with them. He is known as Wei Cheng. *See also* Celestial Kings; Heng and Ha; Ma-Mien; Shen-T'u.

Men-Ur (Egypt)
Deified animal. A sacred bull of Memphis. *See also* Mnevis.

Men-urt (Egypt) *see* Amen (B).

Mena (A) (India) Mother of Parvati. *See also* Devi; Parvati.

Mena (B) (Roman)
She is the goddess of menstruation who presides over the months.

Menaka (Hindu; India)
An Asparasa who was sent by the gods to interrupt the spiritual practices of the maharishi Vishvamitra. *See also* Asparases; Marisha; Urvasi.

Menakshi (India) *see* Devi.

Menat *Manat* (Arabic)
This goddess of destiny was venerated in northern Arabia. Followers prayed to her for rain and for victory over enemies. She is associated with Allat and Al-Uza (qq.v.). *See also* Gad; Menu; Unsas.

Mendean Triad (Egypt)
The triad of Banebdedet, Hermehit, and Harpakhrad. *See also* Banebdedet.

Mendes (Egypt)
Sacred animal. A ram in whose form Osiris was sometimes incarnated. The ram is a symbol of virility.

Mene (Greek) Another name for Selene, goddess of the moon.

Menelaus (Greek)
Menelaus, the king of Sparta is the son of Atreus and Aerope. His siblings are Agamemnon and possibly Pleisthenes and Cleolla. With the assistance of Odysseus, he married Helen of Troy. Menelaus was in the Wooden Horse. He never died but went directly to the Eden-like Elysian Fields. *See also* Agamemnon; Elysian Fields; Helen.

Menerva (Etruscan) *see* Minerva.

Menestratus (Greek)
He saved his lover Cleostratus from being eaten by the dragon who appeared every year in Thespiae.

Menesthius (Greek)
He is the son of the river god Spercheius, and Polydora. His mother and her husband Borus raised him.

Menfra (Roman) *see* Minerva.

Meng (A) *Meng-P'o, Meng-Po Niang-Niang* (China)
Also known as: *Lady Meng, Lady Ming.*
Guardian. She prepares the broth of oblivion (Mi-Hung-T'ang) for those who return from judgment. She lives just outside of hell. After she gives souls the broth they must cross K'u-ch'u k'iao (the Bridge of Pain). *See also* Ti-yu; Yama Kings.

Meng (B) (Celtic) *see* Dagda.

Meng-T'ien (China)
God of the writing brush. He is a mortal from the military who was deified for inventing the writing brush. *See also* Ts'ai Lun; Ts'ai Shen.

Menglad *Menglod* (Norse; Teutonic)
Also known as: *Freyja.*
Goddess of healing. Her home is on Lyfjaberg, the hill of healing. In the form of Menglod she is said to be a spouse of Svipdag. She is possibly a form of Freyja.

Meni (Babylon) *see* Menu.

Mennon (Teutonic) *see* Thor.

Menodice (Greek)
She is the daughter of Orion and the mother of Hylas. *See also* Hylas; Orion.

Menoeceus (A) (Greek)
He is the father of Creon, Hipponome and Jocasta.

Menoeceus (B) (Greek)
He is the son of Creon and Anioche or Eurydice.

Menoetius (A) (Greek)
He is the son of Iapetos and Clymene or Asia. His siblings are Atlas, Epimethius ad Prometheus. During the battle between the Giants and the gods, Menoetius was torpedoed into Tartarus by one of the great god Zeus' thunderbolts. *See also* Abderus; Epimethius; Iapetus; Oceanids.

Menoetius (B) (Greek)
An Argonaut. His parents are Actor and Aegina. He married either Sthenele or Periopis and became the father of the hero, Patroclus. *See also* Actor; Aegina; Patroclus.

Menra (Roman) *see* Minerva.

Menrfa (Etruscan) *see* Minerva.

Menrva (Etruscan) *see* Minerva.

Menthe *Mentha, Mintha* (Greek)
Menthe, a nymph of the river Cocytus in the underworld, was the secret lover of Hades until Demeter found out about the affair. Either Demeter or Persephone beat Menthe brutally and changed her to dust. From Menthe as dust came the mint plant. *See also* Cocytus; Demeter; Hades; Persephone.

Menthu (Egypt, Greek) *see* Buchis.

Mentu (Egypt, Greek) *see* Buchis.

Menu *Meni* (Chaldean) (Assyro-Babylonian, Chaldean)
Menu is variously called a mother goddess, a goddess of fate, and a goddess of good luck. She is also known as Meni, the Babylonian goddess of love. Some say that Menu is male, and that he is a moon deity. Menu may be associated with Gadda (q.v.), and possibly is the same deity Manat (q.v.). *See also* Ishtar; Min.

Menuis (Egypt) *see* Ra.

Menur (Egypt, Greek) *see* Mnevis.

Mer (Babylon, Sumer) *see* Ishkur; Rimmon.

Mer-en-aaui-f (Egypt) *see* Ap-taui.

Mer-ur (Greek) *see* Apis.

Mercurius (Gallo-Roman) *see* Mercury (B).

Mercury (A) (Roman)
Aspects or known as: *Mercurius, Vialis* (Roman)
The protector of roads, and travelers, the deity of commerce, patron of merchants, thieves, scoundrels, and astronomers, Mercury is also the messenger of the gods.

He is the Roman version of the Greek Hermes. He was worshipped in Rome (approx. 495 B.C.) along with a goddess who appears to be Hermes' mother, Maia (also known as Rosmerta), the daughter of Atlas. The Latin poet Ovid, who wrote of Mercury's friendship and adventures with the god Jupiter, described him as a humorous and shrewd deity. Mercury's original name has not been discovered but many believe him to be the Irish Lugh. The name of Vialis was used because Mercury presided over the making of roads. Mercury is shown as a youthful male standing on tip-toe, wearing a winged hat and winged sandals. He is also depicted with coins or a purse and sometimes with a golden chain. This depiction is almost identical to the description of Hermes, except that Hermes is not shown with a purse. His attributes are the sword, chalice and harp. The cock was his sacred bird and the tortoise and goat were his sacred animals. His symbol was the four-horned serpent (quadricornutus serpens). He was often depicted holding a caduceus (a staff with two serpents entwined), and a purse. The staff is his attribute

www.ebook3000.com

as it is for Asclepius, Dionysus and Hermes. He also appears in Gaulish dress, bearded, with his sacred animals, the cock, goat and tortoise. *See also* Hermes; Lugh (guardians of roads and travelers). *See also* Acca Larentia; Esus; Pitho.

Mercury (B) The planet. *See also* Budha (India); Eurynome A (Greek).

Meriones (Greek) *see* Acamas (B).

Merlin (British) *see* Arthur; Vivien.

Mermer (Sumer) *see* Ishkur.

Mermerus (A) (Greek)
Mermerus was well known for his ability to concoct poison. He is the son of Pheres (q.v.).

Mermerus (B) (Greek)
His parents are Jason the Argonaut and Medea, the seer and magician. *See also* Jason; Medea.

Merodach (Babylon) *see* Marduk.

Merope (A) (Greek)
Another name for Eriboea (q.v.). *See also* Aepytus; Oceanids; Orion; Pleiades; Sisyphus.

Merope (B) (Greek)
She is the daughter of Erechtheus, the 6th or 7th king of Athens.

Merope (C) (Greek)
One of the Pleiades. She is the daughter of Atlas and Pleione. Because she married the mortal Sisyphus, she is not visible in the night sky. *See also* Alcyone; Atlas; Electra; Pleiades; Pleione.

Merope (D) (Greek)
Also known as *Clytie.*
She is the daughter of Pandareus and Harmothoe. When the great god, Zeus, killed her parents, she and her sister, Cleothera were raised by Athena. When the Harpies kidnapped the sisters, they were forced to be servants to the Erinyes. *See also* Athena; Erinyes; Harmothoe; Harpies.

Merops (A) (Greek)
King of Percote. His father is also known as Merops. Merops, the younger, became the father of Arisbe, Adrastus, Amphius and Cleite. He taught Aesacus how to interpret dreams. *See also* Aesacus; Cleite; Oceanids.

Merops (B) (Greek) He is the husband of Clymene.

Merops (C) (Greek)
He traveled with Aeneas from Troy to Italy.

Mers (Greek) *see* Ares.

Mertseger (Egypt)
Also known as: *Mert-sekert, Merseger.*
Funerary goddess. This Theban goddess, who represents silence, is closely associated with Osiris. Mertseger is the Greek name of the Egyptian snake goddess, Mert-sekert. She is depicted as a snake with the head of a woman, often surmounted by the solar disk, or with the head of a vulture and a snake on either side of her human head.

Meru Mountain (Brahmanic, Hindu, Jain, Buddhist; India)
Also known as: *Deva-Parvata, Kailasa* (Buddhist), *Ratnasanu, Sumeru.*
The sacred mountain of Mount Meru is placed in the Himalaya range. A mystical range, the cosmic center is both interior and exterior. It has three luminous peaks each composed of gold, silver and iron. Often called the golden mountain, it is located on the round, flat, continent of Jambudvipa, known as the world's center, where the cities of the gods are located. Mountains, separated by oceans, surround Mount Meru, which acts as a pivot for the three worlds. The sun, moon, stars, and all heavenly bodies revolve around it. Meru is Brahma's heaven (known as Brahmapura), and home to numerous other deities. Indra's heaven, Swarga (or third heaven), is located on the summit, which is said to be 84,000 *yojanas* (leagues) high. His site, built by the divine architect Tvashtri, is portable and can be moved anywhere. Vishnu's paradisical Vaikuntha is on its slopes. The Gandharvas reside in the foothills and demons live in the valleys. The Buddhist religion has a similar mountain called Kailasa. Meru is the center of the world lotus and the axis of the human spinal column. Jambudvipa, the ancient esoteric name for India, is located around Meru. Meru corresponds to the Mt. Olympus of the Greek mythology. Mount Mandara, which became the home of the earth goddess Durga, is another sacred mountain. *See also* Bhishma; Brahma; Durga; Indra; Indrani; Kurma (Vishnu's avatar as a tortoise); Loka; Patala; Swarga; Tvashtri; Vaikuntha; Visvakarma.

Merur (Egypt) *see* Ra.

Merwer the Bull (Egypt) The sacred animal of Atum (q.v.).

Mese (Greek)
One of the Delphic Muses, she personifies the middle string of the lyre. Her sisters are Hypate, the high string, and Nete, the low string.

Mesede (Melanesian)
God of archery. When his bow is drawn it causes fire. He is associated with the goddess Abere.

Meshkhent (Egypt) Another spelling for Meskhenit.

Meshlamthea (Greek) *see* Neral (Sumer).

Meskhenit *Meshkhenet, Meskhent, possibly Meshkhent* (Egypt)
Also known as: *Hathor*
Goddess of childbirth. Meskhenit determines the "ka" of the child while still in the womb. At birth, she determines the infant's destiny. Four Meskhenits appear as servants of Isis in the circle of Abydine gods. Meskhenit is identified with the birth brick, which is used for squatting when the woman is about to give birth. According to the *Rind Papyrus,* Thoth carved the time of one's death into birth bricks. Meskhenit is identified with Hathor in her role of mother goddess. She is sometimes shown as a woman with a headdress of palm-shoots or as a brick with a woman's head. *See* Isis; Ka.

Meskhti (Egypt) *see* Ap-taui.

Meslam (A) (Babylon)
This is another name for Aralu, the underworld.

Meslam (B) (Egypt) *see* Amset.

Mesperit-Arat-Maatu (Egypt)
The name of the Sixth Hour of Tuat. *See also* Osiris; Tuat.

Messene (Greek)
She is the daughter of Triopas and Hiscilla, and the wife of the first king of Messenia, Polycaon. *See also* Hiscilla; Iphimedeia; Triopas.

Messibizi (Algonquin People, North America) *see* Michabo.

Messon (Algonquin People, North America) *see* Michabo.

Messou (Native North American) *see* Nanabozho.

Mesta (Egypt) *see* Amset.

Mestha (Egypt) *see* Amset.

Mesti (Egypt) *see* Amset.

Mestor (Greek) *see* Andromeda; Gorgophone.

Metapontus (Greek)
He might be the son of Aeolus and brother of Melanippe. Theano had two sons when Metapontus married her. He assumed they were his children. They had two more sons before he found out that the first two children were not his. He killed Theano and her two sons. (Theano founded Padua after the fall of Troy.) *See also* Theano.

Metharme (Greek)
She is Pygmalion's daughter. *See also* Adonis; Pygmalion.

Methyer (Egypt) *see* Isis.

Metidice (Greek)
He is one of Adrestus' children. *See also* Adrestus.

Metis (Greek)
Metis is the daughter of Oceanus and Tethys and the first wife of the great god Zeus. When she became pregnant with their daughter, the goddess Athena, Zeus swallowed her. He was fearful that a second child would be a son more powerful than he. Athena was born from Zeus' brain, through his head. Metis was known for her infinite wisdom. It is said that she knew more than all the gods. *See also* Athena; Cronus; Eurynome (A); Oceanids; Zeus.

Metope (Greek)
She is the wife of the river god Asopus, and the mother of twenty daughters and three sons. For a partial list of their names, *see* Pelasgus (B). *See also* Aegina; Antiope; Asopus; Rivers.

Metropator (Gnostic) *see* Demiurge.

Metrope (Greek) *see* Phaethon.

Metteya (India) *see* Maitreya.

Metu-khut-f (Egypt) *see* Aai.

Metztli (Aztec) *see* Meztli.

Meuler (Araucanian People, Chile)
Wind god.
God of all winds, waterspouts and typhoons. He is represented as a lizard who is disappearing underground.

Mexitli *Mextli* (Aztec) *see* Huitzilopochtli.

Mezamat (Latvia) Goddess of Forests.

Mezavirs (Latvia)
Also known as: *Mezadevs.*
God of Forests. Probably the same as Mezamat.

Meztli Metztli (Aztec; Mexico)
Also known as: *Coyolxauhqui, Tecciztecatl* (Male), *Yohualticitl* (the Lady of the Night).
Moon goddess. Goddess of darkness. Agricultural goddess. Meztli was burned in flames, symbolic of the consuming of night and the birth of the light of day. Meztli is the same as the Yohualticitl. *See also* Coyolxauhqui; Tecciztecatl; Tezcatlipoca; Yohualticitl.

Mi-che-pa (Tibet) *see* Abheda; Medicine Buddhas.

Mi-Ho-Tsu Hime (Japan) *see* Kami-Mimusubi.

Mi-Hung-T'ang (China)
Also known as: *Broth of Oblivion, Mi-Hun-T'ang.*
Broth of oblivion. Lady Meng gives the broth to all mortals who pass through the doors of hell. The drink causes them to forget their past.

Mi-Kura-Tana-no-Kami (Japan)
The sun goddess Amaterasu's sacred jewels. *See also* Amaterasu; Susanowo.

Mi-Li (China) *see* Mi-Lo Fu.

Mi-Lo Fu
Also known as: *Ajita* (the invincible), *Byamspa* (Tibet), *Chem-pa* (Tibet), *Maitreya* (India), *Mi-Li, Miroku-Bosatsu* (Japan), *Pou-T'ai* (China); (Buddhist; China)
He is the last teacher and savior of our world period. In India he is known as Maitreya and in Japan, Miroku-Bosatsu. He is pictured as a fat, jovial figure with a mountainous stomach. Mi-Lo Fu is comparable to the Pou-tai (Chinese). Compare him to Hotei (Japan). *See also* Ajita; Maitreya; Miroku-Bosatsu.

Mi-Oya-no-Kami (Japan) *see* Fuji.

Mi-p'yed (Tibet) *see* Abheda; Medicine Buddhas.

Miach (Celtic)
He is the physician son of Dia'necht, and the brother of Airmid. *See also* Airmid; Dia'necht.

Michabo (Algonquin People, North America)
Also known as: *Giant Rabbit, Great Hare, Messibizi, Messon, Missabos, Missiwabun.*
Supreme deity. Creator of the human race. He was a shape changer who created man by mating with a muskrat. One of his messengers is Gijigouai. In some versions his opponent is Kabun, his father. In other versions, it is his brother Chokanipok who is his opponent. *See also* Kitcki Manitou; Nanabozho.

Miclantecutli *Mictlantecutli, Mictlantecuhtli* (Mexico, Aztec)
Also known as: *Acolnauactl, Tzontemoc.*
Lord of Chicunauhmictlan, the region of Death. Lord of the eleventh hour of the day. Patron of the north. Miclantecutli cares for the souls that arrive in his domain. His spouse is

www.ebook3000.com

2. Smile to the eyes: relax the eyes and feel how nice and cool they are. Let the eyes draw back in their sockets and start to sink down to the chest and gradually down to the abdomen, the home of your ‘feeling and awareness mind’.



Fig. 3.6 *Smile and relax the eyes, sink into the eye sockets and gradually feel the eyes dropping down into the Abdomen.*

3. Relax the two broad muscles extending from the outer portions of the upper lips across the cheekbones, and lightly smile feeling their connection to the upper front of the ears. Gradually feel the ears growing ‘long’, up and down. Feel the ears grow all the way down and connect to the kidneys.





Fig. 3.7 *Smile to the Ears and listen to the Kidneys.*

Miclancihuatl, the goddess of death and lord of the fifth hour of the night. The couple live in a windowless house in Chicunauhmictlan. Quetzalcoatl and his twin brother, Xolotl, stole the bones of the previous generation from him. In anger, Miclantecutli sent quails in pursuit, but the two managed to get away with the bones. (The bones fell and broke during the escape. These broken bones became a race of mortals of various heights and weights.) Miclantecutli's symbol is the skeleton god of the dead. He appears as a skelton of bleached bones splattered with blood spots. Often he is decorated with owl feathers, and head adornments and banners made from paper. He wears a neck piece of extruded eyeballs. *See also* "A"; Chicunauhmictlan; Legend of the Four Suns, Lords of the Day Hours; Lords of the Night Hours; Omeyocan; Quetzalcoatl.

Micronesia — Creation Legend *see* Areop-Enap; Nareau.

Mictanteot (Aztec People, Nicaragua)
Underworld deity. God of the underground where dead souls go. Good souls go to join Tamagostad and Zipaltonal. One of the major gods of the underground is Masaya the goddess of volcanos. Similar to Mictlantecuhtli (Mexico). *See also* Masaya.

Mictecacihuatl (Aztec People, Mexico) *see* Mictecaciuatl.

Mictlantecutli (Aztec) See Micantecutli.

Mictlantecuhtli (Aztec) see Miclantecutli.

Miclancihuatl (Aztec)
Lady of the Region of Death. See also Miclantecutli.

Mictlan (Aztec)
A commonly used abbreviation for Chicunauhmictlan.

Micux (Natchez People, North America)
A heroine. The human daughter of a cannibal spirit.

Mid-gard (Teutonic) *see* Midgard.

Midas (Greek)
King of Phrygia. Discoverer of white and black lead. His parents are Gordius of the "Gordian Knot" fame and Cybele. King Midas entertained Silenus, the king of Nysa, and in return Silenus gave him the "golden touch." One day as he bathed in the river Pactolus he lost his touch. He is shown with the ears of an ass, given to him by Apollo. *See also* Cybele; Gordius.

Middle Earth (Teutonic) *see* Midgard.

Mider *Midir, Mithr.*
Also known as: *Aileili* (Celtic).
A chief god of the underworld. He is the son of Dagda and Boann and the brother of Angus. Mider was raised as the foster son of Manannan mac Lir. When he grew up, he in turn fostered Angus of the Brugh. Mider owned a magic cauldron that was stolen from him by Chchulainn. He had two abodes. He lived in a castle on the Isle of Man where he kept three exceptional cows and a magic cauldron. The castle was guarded by three cranes. Whenever a stranger passed, the cranes would croak loudly. His other residence was at the sidh (burial mound) of Bri Leith (in County Longford). As Aileili, he is Etain's lover. *See* Angus; Blathnat; Boann; Etain (A).

Midewiwin (Algonquin People, North America)
Sacred dance. It is the "Great Medicine Dance" which guards the tribe in matters of safety, health and wealth. The Chippewa Indians used the name for their society of shamans.

Midgaard (Teutonic) *see* Midgard.

Midgard *Mid-gard, Midgaard, Midgarth* (Norse; Teutonic)
Also known as: *Mana-heim, Middle Earth.*
Midgard is the earth, the abode of man; it is one of the nine worlds of Norse mythology. Midgard, meaning middle abode, is located halfway between Nifl-heim and Muspells-heim. Midgard was fashioned from the body of the evil frost giant Ymir who was slain by Odin, Vili, and Ve. The skull of Ymir became the vault of heaven over Midgard. The four corners of heaven were held up by four strong dwarfs, one stationed in each corner: Nordri, Sudri, Austri, and Westri. The light for Midgard was supplied by sparks from Muspells-heim. The sun and moon were also created from this source. Ymir's flesh became the land, his blood the sea, his bone the mountains, and his hair the trees. Ymir's eyebrows were used to encircle Midgard to protect it from the evil Giants. Jormungandr, also known as the Midgard Serpent, encircles the whole earth. Midgard is where Odin, Vili and Ve, or in some versions Odin, Henir, and Loki found the ash and elm trees or two blocks of wood from which they manufactured the first man and woman, Ask and Embla. Odin gave them souls, Henir gave them motion and senses, and Loki gave them blood and complexions. After Midgard was created, other gods came to assist Bor's sons in fashioning a dwelling place for the gods. It is known as Asgard (q.v.). *See also* Asgard; Ask; Bor; Dwarfs; Gullveig; Henir; Jormungandr; Jotun-heim; Loki; Mana-heim; Muspells-heim; Nifl-heim; Odin; Sudri; Ve; Vili; Westri; Yggdrasil; Ymir.

Midgard Serpent (Teutonic) *see* Jormungandr; Midgard.

Midgardsormen (Teutonic) *see* Jormungandr.

Midgarth (Teutonic) *see* Midgard.

Midir (Celtic, Irish) *see* Mider.

Miehts-Hozjin (Lapp) *see* Leshy.

Mielikki (Lapp)
Forest spirit. He is the husband of Tapio and possibly a god of hunters. *See also* Tapio.

Mig-mi-bzan (Tibet) *see* Virupaksha.

Might (Teutonic) *see* Magni; Thrud.

Mighty Striker, The (Celtic) *see* Sucellos.

Mihir (Persia) *see* Mitra.

Mihr (Armenian; Iranian)
Also known as: *Mithra.*
Probably a god of light, air, war, and contracts. Possibly an underworld or fire deity. Although called the son of Aramazd and brother of Anahit and Nane, he seems to have been a different god than Mithra. He was of the triad of Aramazd and Anahit of the Armenians. In Persia, he was said to represent the sun and was a child of Ormazd. Later, he was replaced by the god Vahagn. As god of fire he was associated with Hephaistos of the Greeks. *See also* Anahita; Aramazd; Mithra; Vahagn.

Mihtajan (Persian) Mithra's festival. *See also* Mitra.

Mii-no-kami (Japan) *see* Kappa.

Mikak'e (Osage People, North America)
Star deities. The Star People.

Mikal (Middle Eastern) *see* Moloch.

Mikura-Tana-no-kami (Japan) *see* Amaterasu.

Milanion (Greek) *see* Melanion.

Milaraspa *Mila-Raspa* (Buddhist)
Born early in the twelfth century, Milaraspa spent his life wandering through Tibet converting people to Buddhism. He was a mendicant poet who is said to have written over one hundred thousand poems. Milaraspa is depicted as seated on a lotus petal covered with a gazelle skin. He has short, curly hair, holds his right hand behind his ear as though listening to something. In his left hand he holds a begging bowl.

Milcom (Middle Eastern) *see* Moloch.

Milesians (Irish) *see* Amergin; Tuatha De Danann.

Miletus (Greek)
He is the son of Apollo and possibly Acacallis. He loved Sarpedon, the son of the great god, Zeus. *See also* Acacallis; Minos; Sarpedon (A).

Milk (Gilyak People, Siberia) Devils.

Milky Way *see* Breathmaker (North America); Chin Nu (China); Irmin (Teutonic); Itoki (Japan); Ituna (Central America); Khotun (Siberia); Kilyikhama (South America); Kuei-Hui (China); Manzan Gormo (Middle Eastern); Muludaianinis (Australia); Vahagn (Armenia).

Milomaki (Amazon People, Brazil)
Food deity. According to myth, a little boy came from the sun and was gifted with a voice that charmed all the people. They called him Milomake or Son of Milo. In the legend, shortly after hearing the boy sing the people ate some fish that killed many of them. Thinking the boy was the cause of the deaths, they killed and burned him. From his ashes came a long blade of grass which quickly developed into a giant Paziuba palm. The men make flutes from this palm which they play when the fruit is ripe. Only men can play or look on the flutes for women and children will die if they so much as glimpse the instrument. He could be related to Tupan.

Milu (Oceanic) *see* Maui.

Mim (Teutonic) *see* Mimir.

Mimar (Teutonic) *see* Mimir.

Mimas (Greek) *see* Ares; Giants; Hephaistos.

Mime (Teutonic) *see* Mimir.

Mimer-Nidhad (Teutonic) *see* Mimir.

Mimi *Mini* (Aborigine People, Australia)
Spirits. These spirits are responsible for teaching the people to paint. They are usually shown dancing, fighting, running, or hunting. Their bones are so brittle they refuse to go out in the wind. Their diet consists of people and yams.

Miming (Teutonic)
In a Danish version, drawn from Norse sources, regarding the death of Balder, it is necessary for Hodur to gain possession of Miming's sword to wound Balder. Miming is a forest troll who is the son of Hothbrod, and the foster son of Gevar. In the same version, Hodur is not a blind god, but a god distinguished for his strength and prowess. In another version, Miming's sword was creted by the clever smith Volund for his son Heime. *See also* Balder; Hodur; Volund.

Mimir *Mim, Mimar, Mime, Mimer-Nidhad* (Norse; Teutonic)
Also known as: *Baugreginn Jotunn* (King of the Gold Rings), *Hodd-Dropnir, Hodd-Mimer* (Treasure-Mimer), *Hoddrofnir* (The Treasure-dropping One), *Naddgofugr*.
Chief of smiths. God of prophecy and wisdom, god of waters, ponds, and a god of knowledge, the giant Mimir is sometimes called a water demon. He is the keeper of the well of wisdom which also mirrors the future. Mimir's Well flows from the root of the tree of life, Yggdrasil in Jotun-heim. Mimir drinks from the well daily. When the war between the Aesir and the Vanir ended, Henir and Mimir were given to the Vanir as hostages. Henir, a handsome man was thought to be chieftain material and was given a position of leadership in Vanaheim. When the Vanir realized that Henir was incompetent without Mimir, they killed Mimir and sent his head to the Aesir. Odin embalmed the head and used his magic to cause the head to talk. Mimir's talking head was able to answer Odin's questions and tell him secrets of life that were hidden from others. Odin asked Mimir for a drink of the magic beverage from his spring or well. Mimir agreed but demanded in return one of Odin's eyes, which Mimir later used as a cup. Odin never regretted exchanging his eye for wisdom. He was also given the ability to see the future which saddened him. In commeration of that day, Odin broke a branch from the Yggdrasil tree and created his cherished spear Gungnir. Odin's eye may symbolize the all-seeing sun, which sinks into the sea in the evening and from which the "keeper of the sea" appears to be drinking at sunrise. Mimir is the son of Ymir and was formed from the sweat from under Ymir's left arm. Mimir is Odin's uncle, and Bolthorn's brother. Compare Mimir's story to the tale of the Celtic god Bran. *See also* Aesir; Bestla; Bolthorn; Gungnir; Henir; Jotun-heim; Mimir's Well; Odin; Vanaheim; Vanir; Yggdrasil.

Mimir's Well (Norse; Teutonic)
Well of wisdom. The god Mimir is in charge of the magic spring of wisdom that bubbles up from the root of the Yggdrasil tree. Odin gave an eye for a drink from this well. Mimir's head was cut from his body by the Vanir gods, but was restored to life by Odin. It still protects the well. *See also* Mimir; Odin; Yggdrasil.

Min *Men, Menu, Minub* (Egypt)
Also known as: *Amen* (possibly), Amsu.
God of fertility, vegetation, procreation. God of those who travel in the desert. God of hunters and miners. One of the most ancient gods of Egypt, he was called Min of Koptos. The original gods of this area, Rahes and Min, were depicted as falcons. It appears that Min replaced this god and may have been associated with the Canaanite/Phoenician deity of war, Reshep. Both had the same consort who was the Syrian goddess of love,

www.ebook3000.com

Quadesh. The cult of Min celebrated the god's festival at harvest time by sacrificing a white bull. He is variously shown as an ithyphallic bearded man, a storm god wielding thunderbolts, a bull, and later as a falcon when he became identified with Horus the Elder as a sky god. He was worshipped in the form of a sacred white bull. Lettuce (considered an aphrodisiac) was one of his most important attributes and was offered to him during ceremonies and is shown with him in many reliefs. He is also depicted in human form with his legs tight together, an erect phallus, a club or stick above his arm, which was raised stiffly with his hand extended to one side, wearing a skullcap with two plumes and two streamers hanging down the back. His personal fetish represented the cigar-shaped cuttle-fish. He is identified with Amen-Ra and with the Greek god Pan. *See also* Aahes; Amen (B); Amsu; Khnu; Nephthys; Quadesh; Reshep.

Min-Amen (Egypt) *see* Amsu.

Minabozho (Algonquin People, North America)
Sea deity. He is the god who fell into the sea and caused it to overflow.

Minakshi (India) "Fish-Eyed." *See also* Devi; Kuvera.

Minakshidevi (India) *see* Devi; Kuvera.

Minato-no-kami (Japan) *see* Kappa.

Mindi (Australia) *see* Rainbow Snake.

Minerva *Menerva, Menrfa, Menrva* (Etruscan, later, Roman)
Also known as: *Athena* (Greek), *Medica*.
Keeper of the city of Rome. Goddess of war. Patroness of physicians. Goddess of intellectual activity, particularly schools. Goddess of wisdom. Patroness of arts and crafts. Patron and goddess of craftspeople. She is the daughter of Jupiter and one of the triad of Jupiter, Juno and Minerva. She has the same qualities as the Irish Brigit and may be the same as the Celtic Belisama. Minerva's sacred animal is the antelope. Thought to be a prophetic animal, its eyes are associated with sharpness of vision. *See also* Aegis; Ana-Purna; Athena; Bellerophon; Brigantia; Brigit; Cupra; Isis; Juno; Tina.

Minga Bengale (Shongon People, Africa)
God of hunters. God who taught humans how to make nets.

Minibozho (Native North American) *see* Nanabozho.

Minipat (Africa) see Muluku.

Minos (Greek)
King of Crete. Law-giver. Shipbuilder. Minos is the son of Zeus and Europa and the brother of Rhadamanthys and Sarpedon. Rhadamanthys was the king of Crete before Minos. His brother Sarpedon went into exile when Minos became the ruler. Minos married Pasiphae the daughter of Helius. He is the father of Acacallis, Androgeus, Ariadne, Catreus, Deucalion, Euryale, Glaucus, Lycastus, Phaedra and Xenodice. Europa married Asterius, the childless king of Crete who adopted her sons by Zeus: Minos, Sarpedon and Rhadamanthys. Upon his death the brothers quarreled either over the estate or over the love of a beautiful young man named Miletus or Atymnius. When the young man declared his preference for Sarpedon, Minos drove his brothers from the kingdom. To quell other rivals and to illustrate his divine heritage he prayed to Poseidon to send him a bull which he promised to sacrifice. Poseidon honored his desires and sent a stunning beast up from the sea. When Minos saw it, he couldn't bear to part with it and nefariously sacrificed a substitute. Enraged, Poseidon decided to follow through with a bullish plan. At this time, Minos was married to Pasiphae, the moon goddess. They had a large family: Catreus, who was killed accidentally; Deucalion, the Argonaut; Androgeus, the Panathenaic athlete who was killed by the Marathonian bull; Acacallis, who, pregnant by Apollo, was banished to Libya by her father; Glaucus, who as a baby drowned in a large jug of honey; Ariadne, who fell in love with Theseus and helped him escape from the Labyrinth; Phaedra, who married Theseus and eventually committed suicide; and Xenodice. Poseidon with the assistance of the well known inventor and craftsperson Daedalus arranged to have Pasiphae fall in love with the bull that Minos would not sacrifice. The result of this union was the monstrous deity of darkness, Minotaur, a half-human, half-bull creature. Minos took care of the situation and continued to look after his kingdom. He was a well-liked monarch who established laws handed down by Zeus. His wife grew weary of his multitudinous affairs, detailed in another section. His exact cause of death is not certain but it has been said that Minos was killed by the daughters of King Cocalus of Camicus who drowned him in boiling water. After death he became a judge in the Underworld along with his brother Rhadamanthys and Aeacus who was a son of Zeus and the king of Aegina. For details of the impact that Minotaur had on the lives of Athenians, *see* Minotaur. For details of Minos' extramarital affairs, *see* Britomaris. Some researchers write that Minos as judge of the underworld was not the Minos described above. They name him the son of Lycastus and Ida or sometimes the son of the other Minos. The judges who sit with him in the underworld are Rhadamanthys and Sarpedon. *See also* Acacallis; Aeacus; Aegis; Europa; Helius; Orion; Pasiphae; Perse; Rhadamanthys; Sarpedon (A); Styx; Theseus.

Minotaur *Minotaurus* (Greek)
Also known as: *Asterion, Asterios, Asterius.*
Deified animal. Deity of darkness. Minotaur, meaning Bull of Minos, was the half-bull, half-human creature who was the offspring of Pasiphae, the wife of Minos, and a bull. His name was Asterius, meaning "star," but he is usually called the Minotaur. Minos had the inventor Daedalus construct the famous Labrinyth to contain and hide the monster. Minos felt that Aegeus, the king of Athens, was responsible for the death of his son Androgeus and in retribution he demanded that seven young men and seven young women, all Athenians, be sacrificed to the beast annually or every nine years in some versions of the myth. Theseus the hero, always looking for a stupendous obstacle to overcome, decided to conquer the Minotuar. Ariadne, the daughter of Minos, had seen Theseus and fallen in love with him. She knew that if he entered the Labrinyth it would be a one way path to certain doom. She approached Daedalus the builder of the maze for assistance. It was decided that Theseus would take a large ball of twine and tie one end of it to the entrance of the Labrinyth and unwind it as he made his way to the beast. When he found Minotaur, he beat him to death with his fists, followed the twine back to the entrance and exited to

safety. In other versions of this legend, this beast was the offspring of Europa, the mother of Minos. Depicted as either a monster or bull with the head of a man or vice versa. *See also* Aeetes; Daedalus; Minos; Pasiphae; Theseus.

Minotaurus (Greek) *see* Minotaur.

Mintha *Minthe* (Greek)
Other spellings for Menthe, the nymph of the Cocytus river in Tartarus, the underworld. *See also* Menthe.

Minthe (Greek) *see* Menthe.

Minu (Egypt) *see* Min.

Minu-anni (Assyro-Babylonian) *see* Ishtar.

Minucihr (Persia) *see* Faridun.

Minyas (Greek)
Minyas built the first treasury. He is the maternal grandfather of Admetus and the son of Aeolus, Chryses or Poseidon. He is the father of Alcithoe, Arsippe, Clymene, Leucippe and Periclymene. His daughters Alcithoe, Arsippe and Leucippe were driven mad by Dionysus and turned into bats. *See also* Admetus; Dionysus.

Minyas, The (Greek)
They are the daughters of Minyas. *See also* Admetus; Argonauts.

Miolnir (Teutonic) *see* Mjollnir.

Mir (Sumer) *see* Ishkur.

Mirabichi (Ottawa People, North America) God of the water.

Mirage (New Zealand) *see* Arohi-rohi.

Miralad *Miralaidj* (Australia) *see* Djanggawuls.

Miralaidj (Australia) *see* Miralad.

Miroku-Bosatsu *Maitreya* (India), *Mi-Li* (China); (Buddhist; Japan)
Miroku-Bosatsu is the future Buddha who lives in the Tosotsa-Ten (heaven). He will come down to earth 5,670 million years after the entry of the Buddha into Nirvana. He is shown standing on one foot with the other on his left knee, and his right hand on his chin. Sometimes he is depicted standing or seated on a lotus and sometimes he is shown sitting. *See also* Arrida; Maitreya; Mi-Lo-Fu; Tushita.

Mirsi (Sumer) *see* Mirsu.

Mirsu *Mirsi* (Sumer)
Also known as: *Tammuz.*
After creating gods of the sea, Anu created land gods. As a land god, Mirsu was the god of irrigation. Mirsu is also a title of Tammuz (q.v.). *See also* Anu.

Miru (A) (Polynesia)
Also known as: *Locha, Lothia.*
Goddess of the underworld. She shares her responsibilities with Hakea of Hawaii, Lothia or Lakemba of Loyalty Island, or Locha of the same island. Some say Miru ruled only the last three of ten levels of the afterworld. Demonic in the worst sense of the word, she seduces men to drunkenness on her "kava" which she stocks abundantly in her cellar. Next she cooks her victims in her large, eternally lit oven. When the bodies are ready, she eats the souls. *See also* Hine-nui-te-po; La'i-la'i; Lmahuika; Rohe.

Miru (B) (Polynesia)
Miru, the god of the dead, collects souls in his cave. Large lizards, who are nourished by the flies in the underworld, are his servants.

Miru-me (Japan) *see* Jigoku.

Misambwa (Luganda People, Africa)
They are spirits connected with the clan and with natural objects. The Misambwa may be related to Massim-Biambe of the Mundang people of the Congo. *See also* Massim-Biambe.

Misca (Aztec People, Nicaragua)
God of traders. Misca shared in creation with Ecalchot, Ciaga, Quiateot, Chiquinau, and Vizetot. All were ruled by Tamagostad and Zipaltonal. *See also* Chiquinau; Ciaga; Ecalchot; Quiateot; Vizetot.

Misharu (Sumer)
Also known as: *Misor.*
This deity of law and order could be the same as Misor.

Misor (Semite, Phoenician)
Also known as: *Misharu.*
Creator of salt. Culture hero. Misor may be the god of the autumn sun. He is sometimes referred to as a god of righteousness. Misor is usually mentioned in connection with Sydyk. He could be indirectly related to Kettu and Misharu. *See* Sedeq; Sydyk; Zatik.

Misrakesi (India) *see* Asparases.

Missabos (Algonquin People, North America) *see* Michabo.

Missiwabun (Algonquin People, North America) *see* Michabo.

Mistelteinn (Teutonic)
In some myths, this is the magic weapon used to kill Balder (q.v.).

Mistress of all the Gods (Middle Eastern) *see* Mami.

Mistress of Heaven (A) (Middle Eastern) *see* Nane.

Mistress of Heaven (B) (Babylonia) *see* Inanna (B).

Mistress of the Gods (Middle Eastern) *see* Anat.

Miszuchi (Japan) *see* Izanami.

Mit (Egypt) *see* Nut.

Mithr (Celt) *see* Mider.

Mithra (Persia) *see* Mitra.

Mithras (Roman) *see* Mitra.

Mitnal (Maya People, Yucatan)
Underworld or hell. Ruled by Hanhau or Ahpuch. Mitnal is sometimes identified with Mictlan, the Aztec underworld. *See also* Hanhau; Ixtab.

www.ebook3000.com

Mitoshi-no-kami *Mitosh-no-kami, Mitoshino* (Japan)

The god of the harvest. He is sometimes known as a deity of food. He is probably the same as Miketsu-oho-kami.

Mitra *Mithra, Mithras* (Roman); (Aryan, Mazdean, Mithric, Hindu, Vedic, Zoroastrian; Babylonia, India, Persia, Greece, Rome)

Also known as: *Dharmaraha* (India), *Mihir* (Persia), *Mihr* (Pahlavi dialect), *Shamash, Surya* (India), *Yama* (India).

Sun god. Fertility god. Corn god. Mitra is a Babylonian sun and fertility deity and known as an aspect of Shamash. As a Vedic sun god and a Hindu solar deity, Mitra, one of the Adityas, is represented as ruler of the day and Varuna, the moon, as ruler of the night. He is the son of the self-formed goddess Aditi. His siblings are Varuna, Aryaman, Indra, Savitri, Bhaga, Ansa, Vivasvat, Daksha and perhaps Surya. Mitra is one of the triad with Varuna and Aryaman, or some say Agni (fire), and Vayu (wind), or a dyad with Varuna. In the latter instance he is co-guardian (with Varuna) of the laws by which the universe is maintained and nature is made fruitful. He guards over contracts and friendships and Varuna presides over oaths. Together they are known as "supporters of justice." As an aspect of Yama he rules over departed souls. The goddess Danu is sometimes said to be the mate of Mitra-Varuna. Some ancient texts identify Mitra as a sky-goddess. Dharmaraha is said to be a form of Mitra. In some legends, Mitra is identified as the joint father of Agastya, with Varuna by the Apsarasa Urvasi. In pre–Zoroastrian times, he was the giver and guardian of cattle, and a god of light who personified loyalty and obedience. In Zoroastrianism, Mitra is known as Mithra. Mithra, with Sraosha and Rashnu are the judges of dead souls on Chinvat Bridge. In Zoroastrianism, Mithra was armed with a knife and a torch when he was born from a rock in the sphere between heaven and hell. His birth was witnessed by shepherds and the Magi. All animals and herbs were born from the blood of the primeval ox, known as Geusha Urvan that Mithra attacked and killed. This ox went to heaven where it remained as the protector of animals. Bulls were sacrificed to Mithra as part of covenants or pacts between two nations. Thus, he is known as the god of the contract. He is the protector of truth and the enemy of lies. After the death of Zoroastra, Mithra and Anahita were incorporated into Zoroastrianism along with the concept of astralism, possibly by the Magi. Mithra's feast, Mihrajan, takes place on approximately September 7 and lasts for six days. His birthday is December 25. He is one of twenty-eight Izeds (spirits, or angels) surrounding the throne of Ahura Mazda. He has ten thousand eyes and ears, is all-seeing, all-hearing, and never sleeps. Nothing escapes his notice. He watches over family life, and detests the darkness of lies and deceptions. His chariot is drawn by four horses. Mithra is generally shown with a dog, serpent and crow. The dog is his venerated companion. He is also depicted as a lion-headed man with a serpent twined around his body, standing on a globe. India adopted Mithra as Mitra and in later times, he was worshiped in Rome as the patron of soldiers and merchants. Reliefs of a young god attired in a Persian costume and wearing a conical hat were found in Mithraic sanctuaries which are known singularly as the Mithraeum. He is kneeling on a bull and plunging a dagger into its neck. The bull's genitals are being attacked by a scorpion, a serpent drinks the blood and a dog springs from the wound. Ears of wheat emerge from the bull's tail. The bull represents the life force. The scorpion implies the lower world defeating its life-giving purpose. The serpent symbolizes the earth made fertile by sacrificial blood. The Mithraeum was generally found in a cave but if one was not available it was built in a subterranean crypt. At one end a relief was fashioned showing Mithra killing a bull. The Mithraic Mysteries excluded women but permitted men from all economic stratas to become members. Though prevalent in Greece, it was far more popular in Rome where it was established in approximately 67 B.C.E. The worship of Mithra in Rome became extremely important and was valued for its mystery and its ethical system. A depiction known as the Vatican Mithra shows him killing the bull with the assistance of the dog, serpent and a scorpion. Mithra's sacred animals are the ox, bull, cock, and lion. The raven is his sacred bird and the sunflower his sacred flower. The violet is consecrated to Mithra. In the Mithraic doctrine, he was often worshiped in caves. Cakes and the sacred Haoma beverage were offered to him. In the Mazdean legends, the supreme being, Ahura Mazda created Mithra to assist him in battle against his twin brother, Angra Mainyu, the personification of darkness and evil. Mithra, as the male principle, brought forth the moon and the sun, from his light and heat. He also brought forth the female principle in the form of the goddess of waters, Anahita. *See also* Aditi; Adityas; Adon; Agastya; Agni; Ahura Mazda; Alburz (Mount); Anahita; Angra Mainyu; Aryaman; Bhaga; Chinvat Bridge; Daksha; Danu; Haoma; Indra; Mihr; Parvati; Rashnu; Savitri (A); Shamash; Sraosha; Surya; Urvasi; Varuna; Vasistha; Vayu; Vivasvat; Yama; Yazatas; Yima.

Mitshi-Manitou *Mudje-Monedo* (Chippewa People, North America)

Evil spirit. He is the opponent of Kitshi Manito (q.v.).

Mitsu-ha No-me (Japan) *see* Izanami.

Mitsuha-nome (Japan) *see* Izanami.

Mixcoatl *Mixkotl* (Aztec, Huejotzingo People, Tlaxcalan People; Mexico)

Also known as: *Camaxtli* (known by this name as principal god of the Huejotzingo and Tlaxcal people), *Huitzilopochtli, Iztac Mixcoatl, Red Tezcatlipoca, Totepeuh.*

"Cloud Serpent." God of hunting. Associated with war and fire. Identified with the stars. Mixcoatl is the son of Tonacatecuhtli and Tonacacihuatl. He has three siblings. He is the father of 400 sons known as the Centzon Huitznahua. Mixcoatl became the father of Quetzalcoatl with one of the five females he created to service the sun. Once, Tezcatlipoca assumed Mixcoatl's identity. As Tezcatlipoca-Mixcoatl he brought fire to mortals. Mixcoatl's festival, Quecholli (the "small bird"), takes place during the first 18 days of November. A male and a female were sacrificed to him. It was the time to produce and service weapons for war. Mixcoatl wears a black mask, sometimes with white dots symbolizing stars surrounding it. The god of the Morning Star, Tlahuizcalpantecuhtli also wears the same eye gear. Mixcoatl's body is painted with red and white stripes. He is sometimes shown with a bow and arrow and a basket to carry his hunter's catch. *See also* Camaxtli; Huitzilopochtli; Quetzalcoatl; Tezcatlipoca.

Mixkotl (Mexico) *see* Mixcoatl.

Miysis (Egypt) God of the slaughter. *See also* Bast.

Mizimu (Luganda People, Africa)
Also known as: *Muzimu.*
Spirits of the dead.

Mjollnir *Miolnir, Mjolnir* (Norse; Teutonic)
Deified object. Magic hammer of Thor. Regardless of distance, the hammer always returns to the hand of Thor. The hammer is so red-hot, Thor wears the magic glove or gauntlet, Iarn-greiper, to hold it. It was made by the dwarfs Brokk and Eitri.

Mka-gro-ma (Tibet) *see* Dakinis.

Mkah Hgroma (Buddhist; Tibet)
Blessings and esoterical knowledge are the boons received from believers in Mkah Hgroma, who is a type of mother goddess. She is similar to the Hindu dakinis (q.v.).

Mmoatia (Twi People, Africa)
Also known as: *Aboatia* (singular).
Spirits. The Mmoatia are little people of the forest, or "fairies."

Mmokos (Slavic)
Also known as: *Mokusa.*
Goddess of sheep. Goddess of those who spin wool.

Mnemosyne (Greek)
Goddess of memory. She is the Titan daughter of Uranus and Gaea, and mother, by Zeus, of the Muses, goddesses of the arts. *See also* Ceos; Cronus; Gaea; Melpomene; Muses; Themis.

Mneuis (Egypt) *see* Mnevis.

Mnevis *Mneuis* (Egypt)
Also known as: *Menur, Mer-ur, Wer-mer.*
Sacred bull. He is the sun god Ra, incarnated as a bull. He is depicted as a black bull with the sun-disk between the horns. *See also* Apis (A); Buchis; Osiris.

Mo-hi-hai (China) God of water.

Mo-li (China) *see* Tien-Wang.

Mo-li-chi (China) *see* Chandi; Tou Mu.

Mo-li Ch'ing (Buddhist; China)
Also known as: *Tseng Chang.*
Protector deity. God of happiness. One of the Diamond Kings (Ssu Ta Chin-kang). Mo-li Ch'ing is the brother of Mo-li Hung, Mo-li Hai and Mo-li Shou. He can create wind, smoke or serpents. This god is twenty-four feet tall with a beard like copper wire. He wears a jade ring on his finger, carries a spear and a magic sword. *See also* Mo-li Hai; Mo-li Hung; Mo-li Shou; Ssu Ta Chin-kang.

Mo-li Hai (China)
Protector deity. God of happiness. Brother of Mo-li Ch'ing, Mo-li Hung and Mo-li Shou. One of the Diamond Kings. He is probably a storm or weather deity. Mo-li Hai is shown holding a four-string guitar. *See also* Diamond Kings; Ssu Ta Chin-kang.

Mo-li Hung (China)
Also known as: *Kuang Mu.*
Protector deity. God of happiness. One of the Diamond Kings (Ssu Ta Chin-kang). Brother of Mo-li Ch'ing, Mo-li Hai and Mo-li Shou. He can cause darkness with his magic umbrella. When he turns it upside down it produces storms, thunder, wind, and earthquakes. Mo-li Hung is shown holding an umbrella. *See also* Ssu Ta Chin-kang.

Mo-li Shou (China)
Also known as: *Ch'ih Kuo.*
Protector deity. God of happiness. One of the Diamond Kings. Brother of Mo-li Ch'ing, Mo-li Hung, and Mo-li Hai. This deity is in charge of an animal that is similar to a white rat. When turned loose from the panther-skin bag which keeps him in check, he turns into a white winged elephant that devours men. Mo-li Shou also can bring forth a snake or other man-eating creatures. He is shown with two whips and a bag made of panther skin. *See also* Diamond Kings; Ssu Ta Chin-kang.

Moaalii (Hawaii, Polynesia)
Moaalii is a local shark god of Molokai and Oahu. He is similar to Ukanipo.

Mode (Teutonic) *see* Modi.

Modgud (Norse; Teutonic)
Guardian. She is the woman who guards the bridge over the river Gjoll in Jotunheim.

Modi *Mode* (Norse; Teutonic)
God of wrath or courage. Wind deity. Son of Thor and the giant female Iarnsaxa. Modi and his brother Magni will inherit the hammer Mjollnir after Ragnarok. *See also* Iarnsaxa; Magni; Mjollnir; Ragnarok; Thor.

Modron (Welsh) "Great Mother." *See also* Matronae.

Modsogner *Modsognir* (Norse; Teutonic)
Also known as: *Mimir* (possibly).
Creator of dwarfs. Chief of all artists. Modsogner is one of the dwarf creator gods who existed before creation. He was assisted in the task of creating dwarfs resembling man, by Durin. Some say Modsogner and the rest of the dwarfs were created by Odin and his brothers from the maggots found in the flesh of Ymir. There is reference to Modsogner as an aspect of Mimir. *See also* Durin; Mimir; Ymir.

Moerae (Greek) *see* Moirai.

Moertholl (Teutonic) *see* Freyja; Moertholl.

Mohammed *Muhammad* (Arabic), *Mahomet* (Turkish).
Also known as: *al-Amin* ("Honest"; Islamic).
The son of Abd-allah and Amina and the grandson of Abd-el-Muttalib, Mohammed was born in Mecca in Common Era (A.D.) 570 and died in 632. Some say that his birth date is not certain and place it between 568 and 572. His father died before his birth. During his teens, he was known as al-Amin. He is the last of the divine messengers sent to warn mortals. Married several times, his first wife, a widow fifteen years his senior, was Khadija. During their happy marriage of twenty years, they had two (some say three) sons who died and four daughters, Zainab,

www.ebook3000.com

Ruqaiyah, Umm Kulthum, and Fatimah. Mohammed is the founder of Islam and the author of the *Koran*, the *Hadith* and the *Sirah*. The Word of God was revealed to Mohammed through the Angel Jibril (also: Gabriel). His message appealed to people of the lower socio-economic strata and posed a threat to the ruling classes. He was accused of being insane, being possessed by evil spirits and of being a magician. Mohammed and his small band of followers were persecuted incessantly. In the year 620, Mohammed had a vision that became known as the "Night Journey" or "Ascension." On the winged horse Burag, guided by Jibril, he was taken from the Ka'ba at Mecca to the Temple in Jerusalem. He climbed the ladder of light to the foot of the heavenly throne. In the world, conditions grew worse for him. Eventually he left Mecca and went to Yathrib, later known as Medina. Mohammed's flight in 622, known as the Hegira (or hijra), marks the beginning of the Islamic calendar. The majority of the Medinans accepted Islam. The Jewish colony resisted his message and numerous battles resulted. It was during this period that the jihad or "holy war" was born. His armies were victorious throughout the area and when they returned to Mecca peaceful arrangements were made with his former enemies. A few years later, feeling that death was eminent, the Prophet led ninety thousand believers into Mecca. On sacred Mount Arafat, where Adam and Eve had met, Mohammed gave his final sermon. It was accompanied by rites still practiced by muslims. The prophet's favorite fruit was the date. Mohammed denounced the characterization of Jesus as the Son of God, but referred to him as another prophet. *See also* Abraham; Gabriel; Jesus; Koran.

Mohini (India) She is the female incarnation of Vishnu.

Moira (Roman) Goddess of fate. *See also* Eumenides; Fates.

Moirae (Greek) *see* Moirai.

Moirai *Moerae, Moira, Moirae* (Greek)
Also known as: *Atropos, Fates* (Roman), *Parcae* (Roman).
Deities of destiny. Clotho (the spinner), Lachesis (the caster of lots), and Atropos (the unbending) are the three daughters of Zeus and Themis. They control the actions and destinies of mortals. They were known to the Romans as the Fates. (In an ancient Babylonian legend the Moira were seven goddesses of fate.) The Moirai are depicted as three old women, one with a distaff, one with a spindle, and one with shears. *See also* Eumenides; Fates; Fortuna; Themis; Tyche.

Moiragetes (Greek)
As guides of the Moirai, Apollo and Zeus are known as the Moiragetes. *See also* Fates; Moirai.

Mokusa (Slavic)
Another name for Mmokos the goddess of sheep.

Molc (Middle Eastern) *see* Moloch.

Molech (Middle Eastern) *see* Moloch.

Molione (Greek)
She is the wife of Actor and the mother of Eurytus and Cteatus, possibly by the sea god, Poseidon. *See also* Actor (B).

Molionides *Molionidae* (Greek)
The twin sons, who were possibly joined, of Actor and Molione. Their names are Cteatus and Eurytus. *See also* Actor (B).

Moloch *Malik, Melech, Melekh, Molc, Molech, Mollac, Molloch, Molokh, Mulac* (Ammonite, Canaanite, Semite)
Also known as: *Agni, Makkal, Mikal, Milcom.*
This ancient sun god represents the negative aspects of the sun's heat in some renditions. He was thought to bring plagues. At one time, followers assuaged him by the sacrifice of newborn children. The Canaanites thought of Moloch as a god of wealth. His name probably came from the word "melech" which means "king." In Hebrew writings the term "bosheth" (meaning shame) was used as a reference to an idol, but when the diacritical marks were inserted Melech became Molech, then Moloch. *See also* Agni; Nergal; Yahweh.

Molokh (Middle Eastern) *see* Moloch.

Molpe (Greek) She is one of the Sirens (q.v.).

Molus (Greek)
Molus is the son of Ares, who is the only son of Zeus and Hera, and Demonice, the daughter of Agenor and Epicasta, or possibly Alcippe. *See also* Ares.

Mommu (Assyro-Babylonian) *see* Mummu.

Momo (A) (Hopi People, North American)
Deified insect. The Honeybee.

Momo (B) (Celtic) *see* Eire.

Momona (Antilles) *see* Atabei.

Momus (Greek)
The Fault-finder. God of ridicule. He is the son of Nox and Erebus and the brother of Aether, Cer, Charon, Dreams, Hemera, Hypnos, Moros, Nemesis and Thanatos. Momus' big mouth, always spewing sarcastic and ridiculing remarks, had him ousted from Olympus. He also made sarcastic remarks to the god of fire, Hephaestus, and the goddess of love, Aphrodite. *See also* Erebus; Keres; Nox.

Monan (Tupi-Guarani People, Brazil)
Also known as: *Maire-Monan.*
An ancient creator god, Monan created mortals. He later attempted the destruction of the world by fire as punishment for their evil ways, but a great flood saved it. He was later replaced by Maire-Monan (q.v.). *See also* Ariconte; Irin Mage.

Mondamin (Chippewa People, North America)
Corn Spirit. *See also* Nokomis; Onatah.

Moneta (Roman) *see* Juno.

Mongan (Irish) *see* Manannan Mac Llyr.

Monju (Japan) *see* Monju-Bosatsu.

Monju-Bosatsu *Monju.*
Also known as: *Manjusri* (Buddhist; India; Japan)
A very popular deity of old Japan, he is a deity of education, enlightenment and transcendental wisdom. Among the Bodhisattvas he is paired with Fugen. He is shown seated on a lotus supported on a lion, or sometimes cross-legged and sometimes with one leg on the ground. He often has a scroll in one hand

and a scepter in the other. Sometimes he is depicted with a sword in his hand which is used to cut down the obstacles of enlightenment. Monju-Bosatsu is said to be identical to the Manjusri (India). *See also* Amida; Bodhisattva; Manjusri; Samantabhadra.

Mono (Japan) *see* Oni.

Monoecus (Greek) An epithet of Heracles.

Monogenes (Gnostic) *see* Nous.

Mont (Egypt)
Also known as: *Menthu, Mentu, Month.*
A war god of Thebes. He lived in Hermonthis in Upper Egypt. For a short time, he was adopted by Amon and Mut and called their son. Some writers say he was a supreme deity until demoted by the god Amun or Antum. In some versions, in his aspect of Mentu or Menthu, he was the god of the rising sun. Mont is depicted as falcon-headed or sometimes as a bull-headed man. *See also* Amen; Buchis; Menthu.

Month (Egypt) *see* Mont.

Moon-hound (Norse; Teutonic) *see* Hati.

Mopaditis (Aborigine People, Australia)
Spirits of the dead. They look like people but no one ever sees them. They are invisible by day, white in the light of the moon, and black when it is dark.

Mopsus (A) (Greek)
He was a well known seer who won a contest against Calchas to see who was the better prophet. *See also* Calchas.

Mopsus (B) (Greek)
He is the Argonaut son of the seer, Ampycus, and Chloris. Mopsus was also present on the Calydonian Boar Hunt. He died from a snake bite in Libya.

Mora (Slavic) *see* Kikimora.

Morave (Melanesian) *see* Abere.

Mordred (Arthurian) *see* Adder.

Morgan Le Fay (British, Celt) *see* Arthur; Morrigu.

Morganes (Celtic, Welsh)
Also known as: *Morgan, Morgens* (British).
Female water spirits. Mermaids. In the singular form, Morganes is a lake spirit who is possibly connected with Morgan Le Fay.

Morirai (Greek) *see* Eumenides.

Morityama (Acoma People, North America)
The Spring Spirit. See also Katsinas; Mayochina.

Morkul-Kua-Luan (Aborigine People, Australia)
Known as the "Spirit of the Long Grass," Morkul-Kua-Luan is probably a food spirit. He is shown with half-closed eyelids and a beak-like nose.

Mormyrus Kannume (Egypt) *see* Oxyrhynchus.

Morning Star (Pawnee People, North America) *see* Tirawa.

Moros (Greek)
Goddess of destiny. Moros is the daughter of Nox and Erebus. She is not a well known deity but is thought to have been invisible and all-controlling. *See* Erebus and Nox for the names of her siblings. *See also* Aether; Keres; Oneiroi.

Morpheus (Roman)
God of dreams. He is the son of Somnus or Hypnos. Morpheus has 999 brothers. His uncle is the god of death, Thanatos. Morpheus, one of the Oneiroi, who represent dreams, is generally represented a chubby, winged child, holding poppies in his hand. *See also* Hypnos; Somnus; Thanatos.

Morrigan (British, Celt) *see* Morrigu.

Morrigu (Arthurian)
Also known as: *Badb Catha* (possibly), *Macha, Morgan Le Fay, The Morrigan, Morrigu-Morrigan, Nemain.*
"Great Queen." Goddess of war. Queen of ghosts. Possibly a sea deity. Morrigu is known as the forerunner of Morgan Le Fay. She dwells in Avalon along with King Arthur. Morrigu is sometimes called Arthur's sister. She has eight sisters. Others say she is mistress of Guingamore, wife of Uriens (king of Gore), and mistress of Sir Accolon. In one version, she is one of the forms of Badb, and one of a triad with Macha and Nemain, who are also cruel goddesses of war. This triad is often called Morrigu. Unable to charm the hero Cuchulain, her passion soon turned to hatred. A shape-changer, she used the identity of an eel, a wolf, and a red-eared heifer to attack him when he was extremely vulnerable fighting off other enemies. His injuries were severe and Badb also wore war wounds from the encounter. Later, as he was walking along a road, he encountered an old woman milking her cow. He begged for a drink. When he finished the beverage, he bestowed his blessing upon the woman. A short time passed and he realized that the woman was Morrigu, in disguise. His blessings had healed her. Morrigu can appear as a seductive young woman, or as a lame, swarthy hag with a big mouth. *See also* Badb Catha; Banbha; Cuchulain; Dagda; Macha; Nemain.

Mors (Roman)
Also known as: *Thanatos.*
God of death. Mors is the personification of death. *See also* Somnus.

Morta (Roman)
Morta is an epithet of Parca, the goddess of childbirth. *See also* Parca.

Moschel (Latvia) God of cows.

Mosigsig (Oceanic) *see* Maui.

Mot (Ugarit)
God of the netherworld. God of the season of crops or god of aridity and death. He dies by the scythe at the hands of Anat at harvest time and is reborn in spring. From the works of Philo, Mot was produced from a self-created being called Desire. This "breath" was sometimes thought to be slime or other rotting water-based substances. From it came the germs that were the origin of everything. Baal or Aleyin, the son of Baal, was Mot's opponent. Some say Mot is El's favorite son. Once, Mot devoured Baal and was forced to regurgitate the god by Baal's

www.ebook3000.com

sister Anat with the aid of Shapash. He is sometimes confused with the god Yam. Deities associated with Mot are the dragon Tannin and the serpent Loran. *See also* Anat; Asherah; Astarte; Baal; Yamm.

Mother Earth (Greek) *see* Chaos.

Mother Earth Moist (Russian, Slavic) *see* Mati-Syra-Zemlya.

Mother of All Things (Pawnee People, North America) *see* Tirawa.

Mother of the Mind (Maya) *see* Alaghom Naom.

Mother Scorpion (Central America) *see* Ituana.

Mother Sea (Inca) *see* Mama Cocha.

Mother Womb (Middle Eastern) *see* Mami.

Mothir (Norse; Teutonic)
Goddess of the nobly born. Heimdall as Rig slept between Fathir and Mothir and from his union with Mothir was born Jarl. *See also* Heimdall; Jarl.

Motikitik (Micronesia)
Creator. He is the son of Lorop. There are similarites between him and the Polynesian deities Maui-tikitiki, Motikitik, and the Melanesian god Maui.

Mountains (Greek) Goddess of mountains. *See also* Gaea.

Mouri (Celtic) *see* Maree.

Mowee (Oceanic) *see* Maui.

Moymis (Babylon) *see* Belus (B).

Mpambe (Africa) *see* Mbamba.

Mridani (India) *see* Devi.

Mrigavyadha (India) "Piercer of Deer." *See also* Rudra.

Mritya (India) "Death." *See also* Yama.

Mrtyu (Hindu; India)
Also known as: *Mara* (Buddhist).
Mrtyu is a death demon and the messenger of Yama, the god of death. *See also* Mara; Yama.

Mtanga (Africa) *see* Mulungu.

Mu-King (China)
Also known as: *Mu Kung, Yu Huang.*
He is the god and ruler of the immortals. Mu King was the first living creation, born of primeval vapor. He is the same as Yu Huang.

Mu Kung (China) *see* Mu-king.

Mucalinda (Buddhist; India) *see* Muchilinda.

Muchilinda *Mucalinda* (Buddhist; India)
Muchilinda is a Naga serpent king who protected Buddha by making a seat from his body for the master and protecting him with his hood. *See also* Buddha; Nagas.

Mudhead (Hopi People, North America) The clown. *see* Tehabi.

Mudungkala (Aborigine People, Australia)
She is a blind creator goddess who rose from the ground long before the creation of hills and before there was sunrise. Mudungkala brought forth three children, a boy and two girls, and they became the first people.

Mueragbuto (New Hebrides) *see* Takaro.

Mugasha (Baziba People, Africa)
God of water. He is the son of Wamara, the father of gods.

Muhammad (Arabic) *see* Mohammed.

Muit (Australia) *see* Rainbow Snake.

Mukasa (A) (Bantu People, Uganda, Africa)
Supreme deity. Oracle. This deity is the "spirit of the lake." He is also the spirit of plenty and fertility. His symbol is a stone pillar. He was senior among the Balubaale (*see* Baluballe). The people of Uganda people call him the highest god of all the pantheon. Mukasa is said to be son of one of the higher gods, possibly Musisi, the earthquake god. His mortal mother is Nambubi. In some legends, Mukasa has three wives. *See also* Balubaale; Bumba; Gulu; Katonda; Kibuuka; Kintu.

Mukasa (B) (Vedic; India)
Mukasa is a kind and peaceful god of plenty.

Mukunda (Buddhist; India) Goddess of the Drum.

Mukuru (Africa) *see* Omumborombonga.

Mul-lil (Akkadian, Semitic) *see* Adar (B).

Mulac (Middle Eastern) *see* Moloch.

Mulciber the Smelter (Roman) Epithet of Vulcan. *See also* Hephaistos; Vulcan.

Muliebris (Etruscan, Roman) *see* Fortuna.

Mulius (Greek)
Mulius, the husband of Agamede, was killed in the Trojan War by Achilles or Nestor. *See also* Actor (C); Nestor; Poseidon.

Muludaianinis (Aborigine People, Australia)
Gods of sleep. Muludaianinis are the women whose men had affairs with other men's wives. This caused a fight and all of them went into the sky. The men became the Milky Way and the women the stars. At dusk the Muludaianinis men travel across the sky to visit their wives. When they are finished they wipe the perspiration from their bodies. It falls onto mortals below and makes them sleepy.

Muluku (Macouas People, Africa)
Chief creator deity. After Muluku made the earth he dug two holes and from these brought forth a man and a woman. Because the two were too stupid to use the tools he supplied, he took the tails from two monkeys (who knew how to use the tools) and placed them on the humans. This made monkeys human and humans monkeys. His opposition is Minipa.

Mulungu (Yao People, Malawi; East Africa)
Also known as: *Mtanga, Umlungu* (Zulu).
Supreme god. Mulungu could be a name for the white man, or just a name for the white man's god. He may be a forerun-

ner of Mpambe, Chiuta, and Leza. He caught two tiny people in his fish net and created the human race from them. In some legends, he went to heaven on a spider's web. Mulungu may also be the same as Mtanga of the Yao People. *See also* Leza; Unkulunkulu.

Mumham (Celtic) *see* Eire.

Mummu (Assyro-Babylonian; Sumer)
Mummu personifies the waves of the ocean, created from the union of Apsu and Tiamat. In Babylonian mythology, Mummu is Apsu's vizier. Tiamat and Apsu consulted with him when the younger gods became so rowdy they wanted to destroy them. Tiamat had second thoughts, but Mummu and Apsu devised a plan. Somehow, the gods caught wind of the scheme, and the wise Ea decided upon a counter-move. After casting a spell on Apsu, he killed him. He bound Mummu up and put a cord through his nose. Ea then constructed a sacred chamber where he could rest in peace. It was in this chamber that Marduk was born. *See also* Apsu; Marduk.

Mummu-Tiamat (Sumer) *see* Tiamat.

Mumuhango (Polynesia)
The ancestor of Tane. Tane wanted to create a woman for a mate and asked his mother Papa to be his wife. She refused and sent him to Mumuhango. The result of his union with Mumuhango was a tree, not a woman. *See also* Hine-tu-a-maunga; Papa; Tane.

Munda (India) A Demon. *See also* Chunda (B); Durga; Kali.

Mundilfari *Mundilfaer, Mundilfore, Mundilare* (Norse)
He is the giant father of Mani, the moon, and Sol, the sun. *See also* Mani; Sol.

Munga Munga (Oceania) *see* Mungamunga.

Mungamunga *Munga Munga* (Aborigine People, Australia)
Goddesses of women. They are generally shown as a pair of fairy-like creatures who are associated with secret fertility rites of women. They are attractive goddesses who are sometimes invisible.

Mungan-Ngaua (Aborigine People, Australia)
Mungan-Ngaua lived on earth a long time ago. He taught the secret rites of an initiation ceremony. His son, Tundum, conducted the first rites. Tundum and his wife were turned into porpoises after a cosmic cataclysm in which almost the whole human race perished.

Mungu *Mungo* (Giryama People, Africa)
Rain deity. Among the Pygmies, Mungu is a creator god who sometimes seems to be a first ancestor and sometimes a culture hero. He may have five or six other names. Mungu is the possessor of the totality of mana. A goat and chicken are offered in sacrifice to him.

Muni (India) *see* Gandharvas.

Muninn and Huginn (Norse; Teutonic)
Also known as: *Memory and Thought.*
Deified birds. Information gatherers. Muninn and Huginn are Odin's ravens. They perch on his shoulders until morning when they head out for the world. At nightfall, they return and report the world news to Odin. *See also* Odin.

Munis (India) Sages. *See also* Brahma; Loka.

Munitus (Greek)
He is the son of Acamas and Laodice. *See also* Acamas (A).

Munon (Teutonic) *see* Thor.

Munsumundok (Borneo) *see* Kinharigan.

Muntalog (Indonisian) *see* Wigan.

Muntu (Egypt) *see* Buchis.

Mur (Sumer) *see* Ishkur.

Murtaza (Persia) *see* Ali (B).

Muruhan (India) *see* Karttikeya.

Muryoju (Japan) *see* Amida; Dnichi-nyorai.

Muryoka (Japan) *see* Amida.

Musa (Africa) Spirit of the forest. Protector of hunters.

Musala (India) The sacred pestle of Bala-Rama (q.v.)

Musagetes (Greek)
An epithet of Apollo as the patron of the Muses.

Musali (India) *see* Bala-Rama.

Musellsheim (Teutonic) *see* Muspells-heim.

Muses (A) (Greek)
Spirits of inspiration. The nine Camenae Muses are the daughters of Zeus and Mnemosyne (Memory). Their names are Clio, also spelled Cleio (the personification of history), Euterpe (lyric poetry), Thalia (comedy), Melpomene (tragedy), Terpsichore (choral dance and song), Erato (erotic poetry), Polyhymnia, also spelled Polymnia (religious poetry and sound), Urania (astronomy), and Calliope (epic poetry). The talented and inspiring group sang for deities and mortals at weddings, funerals, and other commemorative occasions. The Muses were companions of Apollo in his aspect as Apollo Musagetes, the god of music. *See also* Aloeides; Fates; Graces; Hyacintos; Melpomene; Sirens.

Muses (B) (Greek)
The Boeotian Muses are the three daughters of Uranus and Gaea. They are Aoide, the muse of song; Melete, the muse of practice; Mneme, the muse of memory.

Muses (C) (Greek)
The Delphic Muses are the personifications of the high, middle and low strings of the lyre. Their names are Hypate, Mese and Nete. They were discovered by the youthful giants Otus and Ephialtes on Mount Helicon.

Muses (D) (Vedic; India) They are Bharati, Ila and Sarasvati.

Mushdamma (Sumer) "The Great Builder." *See also* Enki.

Muspel (Teutonic) *see* Muspells-heim.

Muspelheim (Teutonic) *see* Muspells-heim.

www.ebook3000.com

4. Open your mouth and relax your jaw, separating the upper and lower teeth. Feel the jaw relax. Once the jaw relaxes the shoulders will relax and drop down. Continue to feel the jaw relax until you feel the saliva start to come out. Relax down to the rib cage. Feel the rib cage drop down, softening all the joints, relaxing down to the Lower Tan Tien. Let the tongue relax back in the mouth. Feel the tongue start to drop down into the throat to the chest and all the way down to the navel sinking the 'floating' sensation down to the Lower Tan Tien.
5. Smile to the shoulders and relax until you feel the shoulders drop and the rib cage relax.



Fig. 3.8 *Relax the Jaw; and the Shoulders and Tongue will relax down to Lower Tan Tien.*

6. Lightly close the lips, but keep the teeth slightly separated. Physically begin a child-like smile with the corners of the mouth gently uplifted and the outer edges of the eyes softly crinkled up. Breathe through your nose.
7. Smile into the brain and empty the upper (observing) mind down to the Tan Tien.
8. Become aware of your inner universe as a big empty space. Keep on sinking – sinking down, into the darkness of your empty space. Keep sinking and experience the vastness until you get closer and closer to the center, the 'original force.' Stay relaxed and alert so as to be able to see one dot of light. It becomes a galaxy spiraling inside you.

   Do the above practice several times until you become familiar and comfortable with it.



Fig. 3.9 *Bring the Senses down to the Tan Tien.*

Muspellheim (Teutonic) *see* Muspells-heim.

Muspells-heim *Muspelheim, Muspellheim, Muspellsheim* (Norse; Teutonic)

Also known as: *Muspel.*

Located in the southern section of the primeval abyss known as Ginnunga-gap, Muspells-heim is the world of elemental fire. From the rivers of Muspells-heim flowed waters of bitter poison which in time became solid masses that filled a vast central space. The ice from Nifl-heim, located in the north of Ginnunga-gap rolled down into contact with these deposits and formed thick coatings of hoar-frost. The warm air of Muspells-heim blew in and melted the hoar-frost. The continual action of cold and heat, and according to some, the will of the powerful Allfather, created Ymir (also called Orgelmir), the first ice giant. Muspells-heim is guarded by the flame giant Surtr. In some myths it was Surtr's flaming sword that melted the hoar-frost. *See also* Aarvak; Austri; Ginnunga-gap; Mani; Midgard; Nifl-heim; Surtr; Svalin; Ve; Vigrid; Vili; Ymir.

Musso Koroni *Mousso Koroni* (Bambara and Mande People, Africa)

Also known as: *Koundye.*

Goddess of disorder. She is the wife of Pemba and daughter of the Voice of the Void. In the Mande stories, she is the twin of Pemba. She came to earth in the ark. *See also* Faro; Mangala.

Mut *Muut* (Egypt)

Mother goddess. Queen of heaven. Goddess of feminine arts. Mut is the wife of Ammon, Amon, Amun or Amenand. She is the mother of Khensu. Mut could be an androgynous deity, since she was believed to have both male and female reproductive organs. She is depicted as a lioness or vulture headed. One depiction shows her with a phallus. She is also represented as a woman wearing a vulture skin on her head with the Upper Egyptian crown on top. Mut is the counterpart of Amen-Ra. She is identified with Bast and Sekhmet. *See also* Adonis; Amen; Ament; Ammon; Bast; Khensu; Khonso; Nut; Sekhmet.

Muta (Roman) Muta is the goddess of silence. *See also* Lares; Larunda.

Mutuhei (Polynesia) *see* Atea; Tanaoa.

Mutunus (Roman)

Also known as: *Priapus* (Greek).

Deity of flocks and fruitfulness. He is similar to the son of Dionysus and Aphrodite, Priapus, the fertility god.

Mutyalamma (India)

House deities. The pearl goddesses. They are Chinnintamma, the goddess who is head of the house; Callalamma, who presides over the buttermilk; Yaparamma, who presides over business transactions; Gangamma, the water-goddess. There is Balamma, who presides over household carts; Huliamma, the tiger goddess; and one more widely worshipped, Ankamma, the goddess of cholera, or sometimes of disease in general. These goddesses are from a small village on the east coast in the Telugu country. Some villages have goddesses that are called by no special name, but simply, Uramma or Gramadeveta, meaning "village-goddess" or Peddamma, meaning "Great Mother." The suffix "amma" indicates "feminine."

Muy'ingwa (Hopi People, North America)

Underworld deity. He is the god who gave the Indians maize.

Muyscaya People — Creation Legend (South America) *see* Chimini-Pagus.

Mwambu and Sela (Kenya, Africa)

First man and woman. God created them so his new sun had people to shine upon.

Mycene (Greek)

She is the daughter of Inachus and Meliae. *See also* Meliae.

Myersyats (Slavic)

The moon personified as a goddess. *See also* Dazbog.

Myesyats (Russian, Slavic)

The moon. Two versions of Myesyats are told. In one Myesyats is the wife of Sun (Dazhbog) and when they fight an earthquake results. In another it is the Sun who is the wife and Myesyats is the husband and their children the stars. The sun is also called Dazhbog in Slavic mythology.

Mygdon (Greek)

He is the son of Poseidon and Melie and the brother of Amycus. Mygdon became the King of Phrygia. *See also* Amycus.

Mylitta (Babylon, Chaldean)

Also known as: *Belit.*

Goddess of fertility and childbirth. She is the same as Belit. *See also* Ashtoreth; Astarte.

Mylitti (Assyro-Babylonia) *see* Belit.

Myo-Ken (Japan) *see* Amatsu-Mikaboshi.

Myrmidons (Greek)

They are the Thessalian people who were allies of Achilles during the Trojan War. *See also* Aeacus; Aegina.

Myrrha (Greek)

Also known as: *Smyra.*

Myrrha is the daughter of the king of Paphos, Cinyras, in Cyprus and Cenchreis. Some say she was the daughter of the king of Assyria, Theias. Aphrodite was angry with Myrrha either because her mother boasted that the young woman was more beautiful than Aphrodite, or possibly because Myrrha did not honor the great goddess properly. Aphrodite punished her by giving her incestous feelings for her father. When he was intoxicated, Myrrha slept with him for twelve nights and as a result became pregnant. When her father found out, he chased after her with a sword. She prayed to the gods to make her invisible so he could not harm her. They changed her into a myrrh tree and it is said that her tears became the gum from the tree. Cinyras killed himself. Nine months later, the infant Adonis emerged from the split tree. *See also* Adonis.

Myrtilus (Greek)

He is the son of Hermes and Clytie. *See also* Hippodameia; Oenamaus; Pelops; Sisyphus.

Mysinger *Mysing* (Iceland)

Sea deity. According to legend he commanded Fenja and Menja to grind out salt or ice from Frothi's Mill (also known as the World mill) in order to hold up his ship. Unfortunately no one told them to stop, so they are still grinding out ice.

N

N (Maya)
God of the end of the year.

Na-Arean (Micronesia) *see* Nareau.

Na Atibu (Oceanic)
This is another name for the first human, De Babou. *See also* Nareau.

Na-naki-me (Japan) *see* Ame no-Oshido-Mimi.

Na Reau (Micronesia) *see* Nareau.

Na Rena (Micronesia) *see* Rigi; Riiki.

Naaki (Finnish)
Water spirit. A dangerous shape changer who pulls people under the water. He is one of the attendants of Ahti (q.v.).

Naarayan (India) *see* Narayana (A).

Naareau (Gilbert Islands) *see* Nareau.

Nabu *Nebo* (Mesopotamia)
Also known as: *Nabug, Tigranes* (Iranian).
Nabu, the son of Marduk, is the god of wisdom, intelligence, and justice, the patron of writers and writing, and a messenger and scribe of the gods. The "Tablets of Fate" were in his charge, and he inscribed the judgments made by the gods. He was Bel's messenger. His vessel is a ship named Iddahedu. Nabu is the spouse of Tashmetrum (Tashmetu), or in some versions, either Nisaba (goddess of the harvest) or Nana. He was thought of by some worshipers as a higher god than Marduk. His temple was at Borsippa (the site was later assigned to the Tower of Babel). Nabu may have originally been the ancient Sumerian deity known as Me, or Sa, or even more ancient, the gods Ur and Dubbisag. Nabu is said to be the same as the angel Pravuil or Vretil of the Hebrews. He is represented, as is Marduk, with a dragon and also with the tools of engraving. His counterpart is the grain goddess, Nidaba. In some legends Nabu is connected with Dilmun (q.v.). Compare Nabu to Thoth (Egypt). *See also* Nana; Nebo; Nisaba (A); Nusku; Puleh; Sin; Tablets of Fate; Tashmetrum; Tiur (Armenian).

Nabudi Women (Aborigine People, Australia)
Evil, malicious spirits, the Nabudi Women send invisible barbs into people who travel alone and make them ill.

Nabug (Assyrian) *see* Nabu.

Nachash *Nchsh* (Hebrew)
Serpent. Nachash is said by mystics to be the serpent who tempted Eve. He is similar to the Naga and Nagis (India).

Nacht (Teutonic) *see* Nott.

Nacon (Maya People, Yucatan) War god.

Naddgofugr (Teutonic) An alternate name for Mimir.

Nadi-Devata (Buddhist; India) River goddess.

Nadija (India) *see* Bhishma.

Nadimmud (Babylon) *see* Ea; Enki; Nudimmud.

Nag (India) *see* Naga Naga Knaya.

Naga Knaya (India)
They are the daughters of the Naga Naga Knaya.

Naga Naga Knaya *Nag* (Buddhist, Hindu; India)
The Naga Naga Knaya are the part-human, part-serpent guardians of the law of Buddha. They are rain deities, guardians of the water and guardians of wealth. A priceless jewel is carried in their foreheads or throats. Their daughters are known as Naga Knayas. Two Naga kings, Nanda and Upananda, were said to have given Buddha, in his mortal form as Gautama, his first bath. Buddha's almsbowl was a gift from the Nagas. Another version of the Naga mythology states that the Hindu gods Indra and Brahma received their first baths from the Nagas. One Naga king is Virupaksha, one of the Four Great Kings who guard the entrance to the Buddhist paradise of Sukhavati. The upper portion of the Naga Naga Knaya is human and the lower part is a snake. The Naga serpents are represented as two entwined serpents, symbolic of chthonic transcendence. As guardians, their images represent the life force and are often found at the portals of Buddhist and Hindu shrines. Regarding the Four Great Kings, *see* Dhartarastra. *See also* Brahma; Buddha; Chakravala (Buddhist Paradise); Indra; Nagas and Nagis (the); Sukhavati; Virudhaka; Virupaksha.

Naga-pasa (India) Brahma's arrow.

Naga-Teka (India) Snake Killer. *See also* Garuda.

Nagarjuna (India) *see* Abheda; Dainichi-nyorai; Stupa.

Nagas and Nagis (Hindu, Jain; India)
Also known as: *Bhogavati* (for Nagis), *Bhogini* (for Nagis), *Bhujagas, Jaja, Nagas and Naginis, Nagas and Nagunis, Nagnis, Naia, Naja, Naje, Pannagas, Uragas.*
The Nagas and Nagis, a race of serpents, were the one thousand sons and daughters of Kadru (the daughter of Daksha) and her mate, the sage Kasyapa. Minor deities, their purpose was to populate Patalas (the underworld) where they live in luxurious palaces. The females are always well dressed and known to be clever. When they appear as nymphs, mortal men fall in love and sometimes marry them. Some of their daughters appear as beautiful women, such as Ulupi, who became the mate of Arjuna. Padmavati is a Nagi queen who was the mate

www.ebook3000.com

of Dharanendra. Sesha, Vasuki, and Ananta are well known Nagas. The Nagas harm mortals only when they are mistreated. Although their venom is deadly, they also carry the elixir of life and immortality. The Naga kings are Takshaka (his mate is Manasa) and Vasuki. Vishnu sleeps on a bed provided by the body of the Naga Sesha while the three, five, seven or nine hooded heads of this snake give him shade. The giant bird-like Garudas, their mortal enemies, enjoying feeding on them. The Nagas are associated with weather, particularly rain and in times of drought pictures of the Nagas are worshiped. In later Hindu times, Karkotaka was known as the king of the Nagas who control weather. The Pancha-muke, a five-faced Naga, spreads his five hoods over many gods. Another Naga king, Paravataksha, lived under a lake shaded by a holy tree. His sword caused earthquakes and his roar caused thunder. The Nagas and Nagis are often shown in three forms: fully human with snakes on the heads and necks; the upper body in human form with the lower region in snake form or as common snakes. The Nagas carry a precious jewel in their heads. The cobra Capella is called a Naga and elephants are often referred to as Nagas because of their long trunks. An historical dynasty of kings in India were known as the Naga-Dwipa. *See also* Arjuna; Bhutas; Daksha; Kadru; Kasyapa; Kumunda; Manasa; Muchilinda; Naga Naga Knaya; Sarpas; Sarpis; Sesha; Takshaka; Vajrapani; Vasuki; Vishnu; Vrita.

Nagelfare (Teutonic) *see* Nagilfar.

Nagilfar *Naglfar, Naglefar, Naglefare, Naglfari* (Norse; Teutonic)
Ship of death. This ship was manufactured from nail parings of the dead whose relatives neglected to pare the nails before the deceased was laid to rest. Iormungandr (the Midgard snake) will create a giant wave that will release the ship from its mooring in the outer regions of Nifl-heim. Piloted by Loki, it will set sail for the conflict of Ragnarok.

Naglefar (Teutonic) *see* Nagilfar.

Naglefare (Teutonic) *see* Nagilfar.

Naglefari (Teutonic) *see* Nagilfar.

Naglfar (Teutonic) *see* Nagilfar.

Naglfari (Teutonic) *see* Nagilfar.

Nagnis (India) *see* Nagas.

Nagua (Aztec) *see* Nahual.

Nagual (Native North American) *see* Nagua.

Nah-Hunte (Sumer)
Sun-god. The sun-god of the Elamites, he was also a deity of law and order and of light.

Nahochacyumchac (Maya) *see* Nohochacyum.

Nahual (Aztec)
Also known as: *Nagua, Nagual, Nahual.*
The Nagual is a person's personal spirit. It accompanies one through life. The Nagual is generally in the form of a bird or beast which makes it presence known in various ways. *See also* Ba; Ka.

Nahualpilli (Aztec) *see* Tlaloc.

Nai (Egypt) *see* Akeneh.

Nai-nai Niang-niang (China) *see* Sheng mu; T'ien Hou.

Nai-nai-miao (China)
Goddess of children. The devotees of Nai-nai-miao pray to become pregnant. She is generally associated with Sheng mu and is related to T'u-shan.

Nai-No-Kami (Japan) *see* Take-mi-kazuchi.

Naia (India) *see* Nagas.

Naiades (Greek) *see* Naiads.

Naiads (Greek)
Also known as: *Naiades.*
Water deities. Healers. The Naiads are divine but not immortal, fresh-water nymphs, who live in brooks, fountains and lakes. They are the daughters of Zeus or daughters of Oceanus and Tethys. Healers, they are the attendants of Athena and nurses of Adonis, Dionysus, and Zeus. (In another tradition, it is the Hyades who nursed Dionysus.) The ever youthful and lovely nymphs had the gift of prophecy and lived on the food of the gods, ambrosia. According to the Greek philosopher Plutarch (C.E. 46?–120?), nymphs never lived over nine thousand six hundred and twenty years. Generally kind, they could be menacing as in the case of the Russian nymphs known as the Rusalki. Other types of nymphs are the Crenae and Pegae who live in springs, the Potamids who live in rivers and streams and the Limnads who live in stagnant waters. Other nymphs are Cassotis and Castalia of Parnassus, and Hago, the ruler of a fountain on Mount Lycaeus. *See also* Aganippe; Calypso; Daemon; Hylas; Nereids; Nymphs; Oceanids; Rusalki.

Naids (Greek) *see* Nymphs.

Naiga-Mesha (India) *see* Nejamesha.

Nairatma (Tibet) *see* Heruka.

Nairitya *Nairrita* (Nepal)
God of Dread. *See also* Dikpalas; Rakshasas.

Nairrita (India) *see* Nairitya.

Nairriti (India) *see* Devi.

Nairyosangha (Iranian)
God of fire. Messenger of Ahura Mazda. Devotees bring Nairyosangha offerings for sacrifice. He is similar to the Narasamsa.

Naivedya (India) *see* Nidhema.

Naja (India) *see* Nagas.

Najade (Slavic) Water nymphs.

Naje (India) *see* Nagas.

Nak (Egypt)
Serpent. He is an ancient serpent fiend who was defeated by Amen-Ra who is mentioned with another fiend called Sebau.

Nakawe (Mexico) Earth Mother. *See also* Kauyumari.

Naka-yama-tsu-mi (Japan)
God of mountain slopes. One of the eight sons of Ho-Masubi. See Sengen for other mountain deities. *See also* Ho-Masubi; O-Yama-Tsu-Mi; Sengen.

Nakhash (Semite) *see* Rahabh.

Nakime (Japan) *see* Ame no-Oshido-Mimi.

Nakisawame-no-kami (Japan) *see* Izanagi.

Nakiu-Menat (Egypt) *see* Aai.

Nakshatras (India) *see* Vasus.

Nakula (India)
He is the fourth of the Pandu Princes and the twin of Sahadeva. *See also* Asvins; Madri; Pandavas.

Nakula and Sahadeva (India) *see* Asvins.

Nala (India) The Ape. *See also* Visvakarma.

Nam-kha-ing-kya-wang-chug-ma (Tibet)
Also known as: *Akasha Dhatu Isvari.*
"Divine Mother of Infinite Space." *See also* Shakti; Vairocana.

Nam-tho-se-ser-chhen (Tibet) *see* Kuvera.

Namandjolk (Aborigine People, Australia)
He is a malevolent spirit being.

Namarakains (Aborigine People, Australia)
Arnhem Land. They are evil spirits who steal the spirits of sick people.

Namargon (Aborigine People, Australia)
Also known as: *Lightning Man.*
Storm spirit. Husband of Barginj. He is responsible for storms and thunder. He uses his head, knees and elbows to strike the clouds and produce lightning. Namargon is depicted with stone axes emerging from his head.

Namasangiti (Buddhist; Tibet).
Also known as: *Vairocana.*
Namasangiti is an emanation of Vairocana and is thought to be the deification of the Namasangiti literature of the Buddhist pantheon. Namasangiti, white in color, sits in the meditative pose on the lotus with his eyes half-closed and a smile on his face. He has one head, twelve arms and wears numerous ornaments. Namasangiti is associated with Prajnaparamita (q.v.). *See also* Vairocana.

Namcui (India) *see* Mara.

Namios (Greek) *see* Apollo.

Nammu (Chaldea, Sumer)
Also known as: *Aruru, Ki, Ningal, Ninhursag, Ninmah, Nintu.*
In Sumerian cosmogony, Nammu is the eternal primeval sea; the mother of all the gods and the one who gave birth to heaven personified as the god An, and earth, who is personified as the goddess Ki. Their union created the air god Enlil, which made Nammu his grandmother. Enlil separated from An and Ki (heaven and earth), and the universe was created as heaven and earth separated by air. In one myth, Nammu is depicted as the mother of the god of wisdom, Enki. As he slept in the deep, the other gods, who expected his help, were clamoring for food. They complained to the mother goddess Nammu who roused him. He instructed Nammu and her daughter Ninmah, the goddess of birth, to create mortals. They would be fashioned from clay for one purpose. Their existence would free the gods from working. The mortals would till the fields and grow the food. Enki was delighted with this innovation and decided to give a banquet to celebrate. Enki and Ninmah drank too much and became inebriated. Ninmah took clay from "over the abyss," and fashioned six types of mortals. Only two are clearly defined. One is a barren woman and the other a eunuch. Enki decided that the fate of the eunuch would be to stand before the king. He then proceeded to create a physically and mentally deficient mortal. When he saw his creation, he asked Ninmah to do something for the pathetic being. There was nothing that she could do. Angry, she cursed Enki for his creation. Compare Nammu to the Assyro-Babylonian goddess Tiamat. *See also* An; Aruru; Ea; Enki; Enlil; Ki; Ningal; Ninhursag; Ninlil; Ninmah; Ninmu; Nintu.

Nampo Gundari Yasha (Japan) *see* Gundari-Myoo.

Namtar (Assyro-Babylonian, Sumer)
Also known as: *Namtaru.*
Chief of seven devils. Evil spirit. He brings plagues to mortals and carries out the destructive plans of Nergal. Namtar has sixty plagues under his control. His spouse is Husbishag, the record-keeper who records the fate of all in the kingdom of Arallu. Namtar acts as the messenger of Ereshkigal. When Ishtar sought Tammuz in the underworld, Namtar was ordered to strike her with a disease. He restored her to health upon her release. *See also* Arallu; Ereshkigal; Husbishag; Ishtar; Nergal.

Namtaru (Sumer) *see* Namtar.

Namtillaku (Babylonia) *see* Marduk.

Namu-tho-se-ser-chhen (Tibet) *see* Kuvera.

Namu-Zozusen (India) *see* Kuvera.

Nana (Greek)
She is the daughter of Sangarius and the mother of Attis. *See also* Agdistis; Attis; Sangarius.

Nana *Nina* (Akkadia, Sumer)
Also known as: *Anna-Nin, Belit-Sheri* (possibly).
Mother goddess. She is the sister of Tammuz and wife of Nabu. Some say she is a moon goddess, or goddess of flocks and rivers. *See also* Anahita; Belit-Sheri; Nanai; Ningal; Ninsun.

Nana Buluku (Fon People, Africa; Haiti).
Supreme deity. God of herbs and medicine. Father of twins Mahu and Leza. He could be androgynous as some renditions refer to Nana Buluku as the primordial mother of the twins. *See also* Lisa; Mahu.

Nanabojo (Native North American) *see* Nanabozho.

Nanaboojoo (Native North American) *see* Nanabozho.

Nanabozho *Nanabojo, Nanaboojoo* (Algonquin, Chippewa, Cree, Fox, Memomin, Ojibwas, Ottawa, Potawatomi, Sauk People, North America)

www.ebook3000.com

Also known as: *Great Hare, Kabibonokka, Manabhozho, Manaboojoo, Manabozho, Manabush, Messou, Michabo, Minibozho, Winabojo, Wolverine.*

Trickster. Transformer. Cultural hero. The myths about Nanabozho abound. He takes many forms among Native North Americans. In the Potawatomi tradition he is the eldest of quadruplets. Nanabozho and the second eldest, a boy, have human form. The third brother is a magician of reknown and a White Hare. The youngest quadruplet, Flint, killed their mother at birth. When Nanabozho grew up, he in turn killed Flint. Nanabozho lived with his second brother, until the jealous supernaturals drowned him. This caused Nanabozho to war against the supernaturals. They tried to assuage Nanabozho by initiating him into Midewiwin, the sacred medicine society. His drowned brother returned and was sent to preside over dead souls. The Cree and Ojibway tell of Nanabozho searching for his brother. When he locates him running with a pack of wolves, he joins him. The brothers shared many adventures. Eventually, Nanabozho is sent from the pack with one wolf as a companion. The companion is seized by underwater beings, and rescued by Nanabozho. A deluge followed, but Nanabozho was able to escape on a raft. Muskrat dived from the raft to take a small piece of earth so that Nanabozho could recreate the world. In another myth, as a creator god he flooded the universe to put out the fire started by his enemies. From the mud, he formed the earth and mortals. Nanabozho taught his creation how to survive. In the Algonquin tradition, he is one of five gods. The other four gods are Kabibonokka (north wind), Kabun (west wind), Shawano (south wind), and Wabun (east wind). He is said to live on an island named Michilimakinak. He has a brother, Chibiabos, and a grandmother, Nokomis (similar to Kitchki Manitou). In other myths, he is a creator god who placed four beneficial spirits at the four corners of the heavens. Their fuction is to hold up the heavens and contribute to the happiness of the human race. In one rendition, the four spirits are his brothers Shawano, Kabun, Kabibonokka, and Wabun. In the Algonquin legend Kabibonokka was god of the north. The other brothers are Shawano (south), Kabun (west), and Wabun (east). In the Algonquin creation legend, Manibozho is known as a culture hero, though some say he is a sun god. He was hunting when the great lake flooded and the world was covered with water. He sought safety on a mountain. Before descending, he sent a raven, a muskrat, and an otter to ensure the waters had receded. Known as the "Great Hare," he married the muskrat and became the ancestor of the tribe. In most legends these deities were born from the earth mother, who died giving them life. Though many names are used by the different Native North Americans for Nanabozho, the similarity of the legends may indicate it is the same deity.

Nanahuatzin *Nanauatzin* (Aztec People, Mexico)

Deity of light. This pimple-faced little god was chosen to be the light of the world. Although the world existed, there was no sunshine. The god Tecciztecatl offered his service, but even though he offered splendid tribute, he was unsuccessful. Little Nanahuatzin had little to give, so he threw himself into the sacred fire and was chosen to be the sun. *See also* Meztli, Tecciztecatl, Yohualticitl.

Nanai (Japan) *see* Ame no-Oshido-Mimi; Nana (Babylon)

Nanan-Bouclou (Africa; Haiti) *see* Nana Buluku.

Nanauatzin (Mexico) *see* Nanahuatzin.

Nancomala (Guaymi People, Costa Rica)

As the great flood ebbed, Nancomala came upon the water maiden Rutbe. They became the parents of the Sun and Moon, who were the twin ancestors of humans.

Nanda (A) *Nund* (India) *see* Devaki; Devi; Kansa.

Nanda (B) (India) *see* Lhamo; Naga Naga Knaya.

Nanda (C) (India) Protector of children. *See also* Hariti.

Nandaka (India) Vishnu's divine bow. *See also* Vishnu.

Nandana *Shatananda* (India) *see* Karna; Kunti.

Nandi (Hindu; India)

Nandi, the white bull, is Shiva's mount and guardian of all four-footed animals. He is also the guardian of Shiva's temples. He is the calf of the Cow of Plenty, Surabhi. The Rishi, Vasistha owned him. Nandi's form is most often seen lying down at the entrance or inside of the temple. His testicles, symbolizing the source of life, are touched by followers as they enter the place of worship. *See also* Badari; Kamadhenu; Nandini; Shiva; Vasistha.

Nandini (India)

She is the female aspect of Shiva's bull Nandi. Nandini is a wish-fulfilling cow. *See also* Kamadhenu; Nandi.

Nandisha (Hindu; India)

Also known as: *Shiva.*

Nandisha, a dwarf with a monkey face, is an aspect of Shiva. He confronted the demon Ravana in Skanda's forest. Ravana ridiculed and taunted him. Nandisha warned the demon that he would be killed by monkey-faced beings. Incredulous, Ravana lifted a mountain to throw at the dwarf. Nandisha put his toe in the mountain and crushed the demon's hands. Ravana had to spend the next thousand years singing hymns of praise to Shiva in order to placate the god. *See also* Ravana; Shiva; Skanda.

Nandisvara (India) *see* Shiva.

Nane (Armenia, Babylonia, Sumer)

Also known as: *Anahita, Hanea, Nana.*

Goddess of the Evening Star. Mistress of Heaven. Originally a goddess of the Sumerians, it is likely that she is the same as Nana. Some say she was the daughter of Aramazd. Later, Nane was identified with Athene and Nana. *See also* Anahita; Athene; Ishtar; Nana.

Nang-sal-ma (Tibet) *see* Aloka.

Nanih Waiya (Choctaw People, North America)

First place or creator. The name means "Bending Hill" or the place of emergence. At a later date used as name for the Christian creator.

Nanna (A) (Norse; Teutonic)

Moon goddess. Nanna is the wife of Balder and the mother of Forseti. She saw her husband killed by the mistletoe thrown by Hoder. Overcome, she threw herself on his funeral pyre. *See also* Balder; Hoder; Forseti.

Nanna (B) *Nannar* (Assyro-Babylonia)
Also known as: *Sin.*
Moon god and god of divination and astronomy. The moon god of the Sumerians, he is the counterpart of the Babylonian god Sin. Nanna is worshiped in the form of an elderly man. His symbol is the crescent. *See also* Mashu; Sin.

Nannan (Celtic) *see* Eire.

Nannar (A) (Babylonia)
She is a moon goddess and the twin sister of Shamash (q.v.).

Nannar (B) (Sumer) *see* Nanna (B).

Nanook (Eskimo)
Also known as: *Nanuq.*
The Bear. The Pleiades.

Nanshe (Sumer)
A goddess of the waters of springs who had the ability to interpret the dreams sent by Zaqar. A daughter of Ea, she was, like her father, worshiped at Eridu and at Lagash, where a yearly festival was held in her honor.

Nantosuelta *Nantosvelta* (Celtic)
Also known as: *Winding River.*
Fertility goddess. Nantosuelta, a Gaulish fertility goddess, is the consort of Sucellos (Silvanus in southern Gaul). She is frequently shown with Sucellos and is often seen holding a pole topped by the replica of a small house (perhaps a bird house). The goddess is accompanied by a raven. *See also* Silvanus; Sucellos.

Nanu (Celtic) *see* Anu (B); Eire.

Nanuq (Eskimo) *see* Nanook.

Naonghaithya (Persia) *see* Naonhaithya.

Naonhaithya *Naonghaithya, Naosihaithya* (Persia)
A Zoroastrian archdemon. *See also* Daevas; Darvands.

Naosihaithya (Persia) *see* Naonhaithya.

Napaeae (Greek)
They are shy but merry nymphs who live in wooded areas and are often found as members of Artemis' entourage. *See also* Artemis; Nymphs.

Napi (Blackfoot People, North America)
During a great disaster, Napi, the founder of the tribe, led his people to the safety of Nina Stahu, a great cave. *See also* Apisirahts.

Na'pi (Blackfoot People, North America)
Also known as: *Old Man.*
Creator deity. A god who created man and woman from clay.

Nar Nara (Pakistan) *see* Jin.

Nara (India) *see* Narayana (A); Nari.

Nara-Raja (India) *see* Kuvera.

Nara-Simbha (India) *see* Nara-Simha.

Nara-Simha *Nara-Simbha, Narashinha, Narasimba, Narasimbha, Narasinha* (Man-Lion) (Brahmanic, Hindu; India)
Also known as: *Nara simhavatara.*
Nara-Simha is the fourth avatar of Vishnu. The tyrant Haranya-kasipu, who is one of the Daityas (demons), was furious when his son Prahlada refused to worship him and instead declared his belief that Vishnu was the only true god. Brahma had given immunity from harm to Haranya-kasipu. There were a few provisions. He could not be killed by day or night, by animal or man, nor could he be killed inside or outside of his home. When his son would not obey him Haranya-kasipu cursed and kicked a pillar and challenged Vishnu to come forth if he was truly omniscient and omnipresent. Vishnu appeared as Nara-Simha the half-man, half-lion and ripped his adversary to pieces. Haranya-kasipu was killed between day and night, at dusk, neither in nor out, but in his doorway, and not by an animal nor a man but by a half-beast, half-man. Prahlada took over his father's position, but reigned with kindness and wisdom. His grandson was the demon Bali who left Sutala in Patala, a region under the world by Vishnu. Nara-Simha is described as red, with a thick bristling mane dripping blood. He wears a garland made from the entrails of his enemy. This myth appears to be symbolic of the struggle between light and darkness. *See also* Bali; Daityas; Hiranya-kasipu; Matsya; Prahlada; Vamana (Vishnu's avatar as a dwarf); Varaha (Vishnu's avatar as a boar); Vishnu.

Narada (Hindu; India)
Also known as: *Brahma-deva.*
A rishi (sage), Narada sprang from Brahma's forehead. He did not get along well with Daksha, so Daksha decreed that Narada would be born from one of his daughters. This happened and the father was Brahma. As only gods are born twice of the same father, Narada became Brahma-Deva. Narada, a friend of Krishna, invented the lute and taught the Gandharvas to play it. *See also* Brahma; Daksha; Gandharvas; Pradyuma.

Narah (India) *see* Narayana (A).

Naraka (A) *Narakasur, Naraka-asura* (Hindu; India)
A vile and powerful giant demon, Naraka was king of Pragiyotisha. The personification of darkness, he conquered all the kings on earth and became an arch enemy of the gods. He stole Aditi's earrings and wore them himself in his fortress castle. He took Indra's canopy and abducted sixteen thousand one hundred young women from earth and the celestial realm. In the form of an elephant he raped the daughter of the divine architect Visvakarma. Krishna went after him with a vengeance. He battled the demon and his army, including Muru, the five-headed demon, and his seven sons. After defeating Naraka, the palace was open to reveal countless treasures and the female prisoners. When Krishna saw the young women, it was love at first sight. He whisked them off to his heavenly abode and married them. *See also* Aditi; Sita; Vasundara; Yama.

Naraka (B)
Also known as: *Dmyal-wa, Naraloka* (Tibet); (Buddhist, Hindu; India).
The lowest Hindu world, where the wicked are punished

www.ebook3000.com

after death. The home of goblins and sorcerers, it has twenty-eight divisions. (*See* Patala). In the Buddhist tradition, it is one of the six paths or conditions of existence and is also called Nara. The six conditions are divided into eight classes: birth, old age, sickness, death, misfortunes and punishments, offensive objects and sensations, separation from loved ones, ungratified wishes, and the struggle for existence. *See also* Loka.

Naraloka (India) *see* Naraka (B).

Narasamsa (India)
"Praise of Men," a title of Agni. *See also* Agni.

Narashinha (India) *see* Nara-Simha.

Narasimba (India) *see* Nara-Simha.

Narasimbha (India) *see* Nara-Simha.

Narasimhavatara(India) *see* Nara-Simha.

Narasinha *Man-Lion* (India) *see* Nara-Simha.

Narayana (A) *Nara, Narah, Naarayan, Satya-Narayana, Satyapir* (Hindu; India)
A thousand-eyed being greater than Brahma, Narayana is the creator, preserver and destroyer of worlds. He is the eternal male who bore even Brahma in his indestructible body. He lay for ages on the primeval waters, known as Nara, floating on a banyan leaf while sucking his toe. When he decided to create everything from his body, speech was born from his mouth, the Vedas from his body, amirita from his tongue, the firmament from his nose, heaven and sun from his eyes, temples from his ears, clouds and rain from his hair, lightning from his beard, rocks from his nails, and mountains from his bones. His toe-sucking position symbolizes eternity. In another version he created Purusha. As Satya-Narayana he was originally Satyapir, the combination Hindu and Muslim deity. Satya-Narayana is worshiped once a month at dusk. Among his elaborate offerings is a delicacy made with sugar, flour, milk, and banana. Narayana is also a name that became associated with Buddha in later times. Compare Narayana to Purusha. *See also* Brahma; Kama; Naryana (B); Parvati; Vishnu.

Narayana (B) (Hindu, Muslim; India)
Also known as: *Vishnu.*
Narayana, "Moving Waters," is an epithet of Vishnu. When Brahma began creating the world, he awakened Vishnu, who was asleep on the serpent Sesha on the ocean's floor. When Narayana is used as a mystic name of Vishnu, it recalls Purusha. *See also* Brahma; Narayana (A); Purusha; Sesha; Vishnu.

Narayana (C) (Hindu; India)
He is a Rishi, the son of the deity Dharma and Ahimsa. He practiced his penance with an intensity that alarmed the gods. *See also* Dharma; Rishi.

Narayana (D) (Hindu; India)
The son of the first man, Nara, who is identified with Vishnu. *See also* Narayana (A); Narayana (E); Nari (B); Vishnu.

Narayana (E) (Hindu; India) An epithet for Brahma.

Narcissus (Greek)
Deified mortal. A beautiful youth, he is the son of the river god Cephissus and the nymph Leiriope. To avenge Narcissus' rebuff of the nymph Echo's love, Aphrodite, who regarded the incident as a rebuke to herself, caused Narcissus to become enamored of his own reflection in the waters of a stream. Unable to embrace or kiss the image, he pined away until he was changed into a flower, the narcissus. *See also* Aphrodite; Cephissus; Echo.

Nare (Teutonic) *see* Narve.

Nareau *Na Reau, Naareau, Nareua, Narleau, Naruau, Nauru* (Oceanic)
Also known as: *Areop-Enap, Na-Arean, Tekikinto, Tekikitea, Tekitekite.*
Spider. Creator-trickster god. Nareau and his daughter Kobine came from Te Bo Ma, the primeval darkness, and Te Maki (meaning "Cleaving Together") and created heaven and earth. Next, they created the first humans, De Babou and De Ai (also known as Na Atibu and Te-Po-ma-Te-Maki). Riiki the eel or Rigi the worm, who are sometimes credited with the creation of all, perhaps assisted Nareau. Nareau sent De Babou and De Ai with instructions to tend the earth. They disobeyed his orders not to have offspring and gave birth to the sun, moon, and sea. Because they pleaded for forgiveness he allowed them to remain and they began the human race. Some say Nareau has a son named Maturang who fished upland to form the islands. Nareau is possibly the same as Tabakea, the turtle, who was called "the Father of All Things." Nareau, who is shown as a spider is somewhat similar to Qat. *See* Riiki and Rigi for a different creation story. *See also* Areop-Enap; Kai-n-Tiku-Aba; Ligobund; Luk; Lukelong, Qat; Yelefaz.

Narfe (Teutonic) *see* Narve.

Narfi (Teutonic) *see* Narve.

Nari (A) (Teutonic) *see* Narve.

Nari (B) (India)
Nari is the "Mother of the Earth," the primordial woman, spouse of Nara and, according to some, the mother of Viraj. *See also* Viraj.

Nari (C) (Babylonia) *see* Marduk.

Narleau (Gilbert Islands) *see* Nareau.

Naru (Teutonic) *see* Narve.

Naru-kami (Japan)
Also known as: *Kami-nari.*
God of thunder. Same as Kami-nari. Symbolizes thunder and lightning. *See also* Kami-nari.

Naruau (Gilbert Islands) *see* Nareau.

Narve *Nare, Narfe, Narfi, Nari, Narvi* (Norse; Teutonic)
He is the son of Loki and his third wife, the loving, faithful Sigyn. His brother, Vali, was named after the Vali who avenged Balder. The gods turned Vali into a wolf expressly to rip Narve's body apart. His intestines were used by the gods to tie up his father. *See also* Loki; Sigyn; Vali.

Narvi (Teutonic) *see* Narve.

Nasamon (Greek)
Nasamon is the grandson of Apollo and Acacallis and the

son of the Libyan chieftain Amphithemis (also known as Garamas) and Tritonis. His brother is Caphaurus, also known as Cephalion. *See also* Acacallis.

Nasargiel (Hebrew) A fallen angel who rules in Hell.

Nasatyas and Dasra (India)
The "Wonder Workers," Nasatyas and Dasra are the twin healing deities known as the Asvins. In later times, the Asvins declined in mythological status and became the Zoroastrian archdemon Naonghaithya. *See also* Asvins.

Nasilele (Zambia, Africa)
Moon goddess. Wife or mate of Nambi or Nyambe. *See also* Nyambe.

Nasrah (Arabic) The Hewer.

Nastrond (Norse; Teutonic)
Also known as: *Shore of Corpses.*
Underground. In this section of Hel the dragon Nidhod gnaws on the corpses of evil doers. *See also* Hel; Nidhod.

Nasu (Zoroaster; Persia)
This female demon, one of the Drujs, is able to enter a corpse in the shape of a fly. The glance of a dog is able to drive her away, in a funeral rite known as sag-did ("dog-sight"). Should she invade a living body, a nine day purification ceremony known as Barashnum will rid the person of her impurities. *See also* Angra Mainyu; Drujs.

Nat (A) (Greek) *see* Sol (B).

Nat (B) (Teutonic) *see* Nott.

Nat-thami (Burma)
They are the eleven maiden nats (spirits) who guard eleven royal umbrellas in Mandalay. *See also* Nats.

Nata and Nena (Aztec People, Mexico)
Survivors of the flood. Nata and Nena were warned by Tezcatlipoca about a coming flood. They took refuge in a hollowed log. Tezcatlipoca warned them not to eat anything except a single ear of maize. They disobeyed the god and ate roasted fish they had caught. Tezcatlipoca punished them by changing the fish into dogs. Similar to tale of Noah and that of Coxcox and Xochiquetzal (q.v.). Nata and Nena are associated with Citlallatonac (q.v.). *See also* Legend of the Four Suns; Tezcatlipoca.

Natagai (Mongol)
Also known as: *Nogat.*
A little food is placed in the mouths of these images at each meal. They are considered gods of prosperity and weather. They preside over earth, house, cattle and corn. The images are generally made of felt material. They are possibly the same as the health deity, Tangri (Mongol). *See also* Ahura Mazda (Persian); Tangri.

Nataraja *Nataraja Siva* (Hindu; India)
Also known as: *Natesha* (Lord of the Dance), *Shiva*, *Sudalaiyadi* (Dancer of the Burning Ground).
Nataraja, the master of rhythm and dancing, is an emanation of Shiva. His cosmic dance, Nadanta, consists of five movements: creation, preservation, destruction, reincarnation or illusion, and nirvana. Separately, these movements represent the activities of Brahma, Vishnu, Rudra, Mahashvara and Sadashiva. Nadanta is performed in the golden hall of Chidambaram in the center of the universe. When Shiva dances, a halo surrounds his head and legions of spirits surround him. He plays his own drum, Damaru, and as he whirls he keeps the stars and planets in orbit. His dance symbolizes the constant movement of the universe. When he dances in cemeteries, the unclean spirits heed his call and are brought into his circle of power. The serpent Sesha saw Shiva's performance and was so enthralled that he renounced his life style in hope of seeing it again. When attacked by the demon Muyalaka, Shiva pressed his toe on him and broke his back as he continued his cosmic dance. Shiva invented the Tandava dance to please "Uma" the mother. Another dancer in Shiva's court is Tandu the god of dancing. Shiva, shown with his right leg raised in dance, is known as Natesha. *See also* Sesha; Shiva; Uma.

Natesha (India) "Lord of the Dance." *See also* Nataraja; Shiva.

Nats (Buddhist; Burma)
Spirits of air, sky, earth, forest, hills, rivers, streams, wind, and rain, nats are also household ghosts and ghosts of cultivated fields. Agricultural nats are known as Saba-Leippya. *See also* Hkum Yeng; Hmin Nat; Nat-thami; Sa-bdag (Tibet); Thein.

Natu-no-me-no-kami (Japan) *see* Ukemochi.

Natu-taka-mi-no-kami (Japan) *see* Ukemochi.

Nature (Greek) *see* Chaos.

Nau (Egypt) *see* Nut.

Nau and Naut (Egypt) *see* Nau and Nen.

Nau and Nen (Egypt)
Also known as: *Nau and Naut, Nau-Shesma* (possibly).
Probably creator deities. Nau, the monster serpent, has seven serpents on his seven necks. He is usually associated with his consort, Nen, but little is known about either except that they are mentioned in the Pyramid Texts along with Amen and Ament. Nau and Nen may be one deity with dual names. *See also* Amen.

Nauholin (Aztec)
Sun god. Nauholin was worshiped by Early Aztec warriors or knights.

Nauisithous (Greek)
He is the son of the sea god, Poseidon, and Periboea. It was Nauisithous who purified Heracles after he murdered his children. *See also* Calypso; Heracles; Nauplius; Poseidon.

Naunet (Egypt) *see* Ogdoad (the); Ptah.

Nauplius (A) (Greek)
Astromoner, sailor. He is the husband of Clymene.

Nauplius (B) (Greek)
Nauplius is the son of Poseidon and Amymone and the half-brother of Nauisithous. He is a sailor and a navigator. *See also* Argonauts; Hesione; Poseidon.

Nauroz (Persian) A Persian festival. *See also* Yima.

Nauru (Gilbert Islands) *see* Nareau.

www.ebook3000.com

Nausinous (Greek)
He is the son of Odysseus and Calypso. Nausinous and Nausithous share the same mother, Calypso, who was brokenhearted when Odysseus left her. *See also* Calypso; Odysseus.

Nav (Slavic)
Spirits. Spirits of mortals who died tragically and too soon.

Nava-ratri (India) Hindu Festival. *See also* Durga-puja.

Navagrahas (Nepal) *see* Dikpalas.

Navasard (Armenian)
Navasard is a New Year's celebration in honor of Aramazd (q.v.).

Nayanezgani and Thobadzistshini (Navajo People, North America)
Also known as: *Atseatsan and Atseatsine* (possibly).
Culture heroes. Possibly sun and sea deities. Slayers of the Alien gods and Child of the Waters. They cleaned the world of the man-devouring giants, except those of cold, hunger, old age, and poverty. *See also* Anaye.

Naymlap (Andean People, South America)
Also known as: *Llampallec.*
Supreme deity. Possibly a sea deity. Legend indicates that he was either a mortal chieftain or a deity of great renown. Long ago Naymlap and his wife, Ceterni, and a group of assistants came from the north. These people reigned for a long time, then given wings by his power, rose to the sky and disappeared. His followers attempted in vain to search for him but he left no trace except for an idol carved from green stone, which they called Llampallec. Naymlap was followed by Cium, who perished of hunger in a below ground chamber. According to myth he wanted to appear immortal. After nine different kings, the king named Tempellec followed and attempted to move the statue, but a demon who appeared as a beautiful woman seduced him. Shortly after this it began to rain for thirty days, followed by a severe famine. Tempellec's people threw him into the sea and he was followed by a change in the form of government. The original group of people who came with Naymlap were Pitazofi (a trumpeter), Ninocolla (warden of the throne), Ninagentue (cup-bearer), Fongasigde (spreader of shell dust on the water), Ochocalo (head of the food preparing), Xam (in charge of face paints), and Llapchilulli (in charge of vestments and plumes).

Nazi (Semitic, Sumerian)
One of the goddesses created by Ninhursag. In one version, Nazi is a deity who heals the phallus. *See also* Ninhursag.

Nchsh (Hebrew) *see* Nachash.

Ndengei *Ndengi* (Fiji Islands)
Creator. He is the divine serpent god with stone flesh who hatched mortals from a bird's egg. His son, Rokomoutu, is also a creator, but only of land. In one story, Ndengei hatched two eggs, one a boy and one a girl. They became the ancestors of the human race. In a different rendition, a great bird laid the two eggs which were hatched by Ndengi. One became a boy, the other a girl. He is also a god and judge of the underworld. It is difficult for the soul to reach him, as the way is barred by a giant wielding an axe. If the soul is wounded, it cannot appear in the place of judgment. Whenever Ndengei turns over, there are earthquakes. *See also* Figonas; Kafisi.

Ndengi (Fiji Islands) *see* Ndengei.

Ndjambi Karunga (Herero People, Southwest Africa)
He is the omnipresent supreme being known for his kindness.

Ndrianahary (Africa) *see* Ndriananhary.

Ndriananahary *'Ndriananahary, 'Ndrianahary* (Madagascar, Africa)
Supreme deity. He sent his son, Ataokoloinona, to earth to see if it was suitable for inhabitation. The son never returned, so he sent his servants who are dead people to search for him, but they never returned to earth. *See also* Andriamanitra.

Ne (Egypt)
One of the principal gods mentioned in the Pyramid Texts.

Ne No Kuni (Japan) *see* Ne-No-Kuni.

Ne-No-Kuni (Japan) *see* Yomi.

Naenia (Roman) Goddess of funerals.

Neaera (A) (Greek)
She is the wife of Strymon, the Thracian river god, and the mother of Evadne. *See also* Argus (A); Strymon.

Neaera (B) (Greek)
She is one of the six daughters of Amphion and Niobe.

Neb-Abui (Egypt) *see* Assessors.

Neb-baui (Egypt) *see* Aai.

Neb-Hrau (Egypt) *see* Assessors.

Neb-Maat (Egypt) *see* Assessors.

Neb-senku (Egypt) *see* Aai.

Neb-Ti (Egypt) *see* Nephthys.

Neba-per-em-khetkhet (Egypt) *see* Assessors.

Nebhet Hotep (Egypt) *see* Nebt-Hetep.

Nebiru (Babylon) *see* Marduk.

Nebmerutef (Egypt)
Deity of writing. A scribe, he was inspired by Thoth, the patron god of writing and record keeping.

Nebo (Hebrew, Sumer)
Also known as: *Ak, Marduk, Merodach* (Akkadian).
Nebo is a name for Marduk when he is the "God of Trading." In this form he is also called a teacher and writer. As Ak, he has traits similar to Mercury in that he is called a messenger and a recording angel. *See also* Marduk; Nabu; Namtar.

Nebrophonus (Greek)
He is possibly the son of Jason and Hypsipyle. *See also* Jason.

Nebt-het (Egypt) *see* Aai.

Nebt-Hetep (Egypt) *see* Iusaas.

Nebt-Hetep *Nebhet Hotep* (Egypt) *see* Atum; Iusaas.

Nebt Ushau (Egypt)
Nebt Ushau is the name of the Eighth Hour of Tuat. The name of the pylon guarding the entrance is Aha-en-urt-nef. The city Osiris passes through at this hour is Tebat-neteru-s. Only gods and spirits who have been mummified and buried appropriately occupy this place. Four ram forms of the god Tathenen guard Osiris. The other gods mentioned during this section of the sun god's trip are Affi, Aranbfi, Ba-neteru, Horus, Isis, Ka-Amentet, Khatri, Khepera, Nut, Osiris, Rem-neteru, Seb, Sebeq-hra, Shu, Ta, Tefnut, and Tem. The doors in the Circle, Shesheta, are Hetemet-khemiu, Tes-aha-Ta-thenen, Tesermen-ta, Tes-khem-baiu, Tes-neb-terer, Tes-sekhem-aru, Tes-sept-nestu, Tes-sheta-em-thehen-neteru, Tes-sma-kekui. *See also* Tuat.

Nebthet (Egypt) *see* Nephthys.

Nechtan (Celtic, Irish) *see* Boann.

Neda (Greek)
Neda was one of the infant Zeus' nurses. *See also* Zeus.

Nedu (Sumer) *see* Arallu.

Nef-em-baiu (Egypt) *see* Aai.

Nefer Hor (Egypt) A son of the god Thoth.

Nefer-Tem (Egypt) *see* Assessors.

Nefertem (Egypt) *see* Nefertum.

Nefertum *Nefer-Tem, Nefertem* (Egypt)
Also known as: *Iphtimis* (Greek), *Horus.*
God of the sun. God of perfumes. Nefertum is the son of Ptah and Sakhmet. He is one of the triad of Memphis which is composed of Ptah, Sakhmet and Nefertum. Nefertum and Horus (child of the sun) united to become a single entity. He is sometimes shown with a lion's head or as a youth seated on a lotus blossom. He wears a crown of either a lotus with two feathers or with one lotus alone. He is often depicted standing on a recumbent lion. One of his attributes is a saber. Nefertum is identified with Thoth and Horus. *See also* Ptah; Sekhmet.

Negafok (Eskimo) The cold weather spirit.

Negative Confession (Egypt)
Negative Confession is a rite that takes place before the Weighing of the Heart. There are forty-two Negative Confessions from the Eighteenth Dynasty. They are **1.** I have not done iniquity. **2.** I have not robbed with violence. **3.** I have not done violence to any man. **4.** I have not committed theft. **5.** I have slain neither man nor woman. **6.** I have not made light the bushel. **7.** I have not acted deceitfully. **8.** I have not purloined the things which belong to God. **9.** I have not uttered falsehood. **10.** I have not carried off goods by force. **11.** I have not uttered vile or evil words. **12.** I have not carried off food by force. **13.** I have not acted deceitfully. **14.** I have not lost my temper and become angry. **15.** I have invaded no man's land. **16.** I have not slaughtered animals which are the possessions of God. **17.** I have not laid waste the lands which have been ploughed. **18.** I have not pried into matters to make mischief. **19.** I have not set my mouth in motion against any man. **20.** I have not given way to wrath without due cause. **21.** I have not committed fornication, and I have not committed sodomy. **22.** I have not polluted myself. **23.** I have not lain with the wife of a man. **24.** I have not made any man to be afraid. **25.** I have not made my speech to burn with anger. **26.** I have not made myself deaf unto the words of right and truth. **27.** I have not made another person to weep. **28.** I have not uttered blasphemies. **29.** I have not acted with violence. **30.** I have not acted without due consideration. **31.** I have not pierced my skin, and I have not taken vengeance on the gods. **32.** I have not multiplied my speech beyond what should be said. **33.** I have not committed fraud, and I have not looked upon evil. **34.** I have never uttered curses against the king. **35.** I have not fouled running water. **36.** I have not exalted my speech. **37.** I have not uttered curses against God. **38.** I have not behaved with insolence. **39.** I have not been guilty of favoritism. **40.** I have not increased my wealth except by means of such things as are mine own possessions. **41.** I have not uttered curses against that which belongeth to God and is with me. **42.** I have not thought scorn of the god of the city. (This list was compiled from the reference book *Who's Who in Egyptian Mythology*, by Anthony S. Mercatante.) *See also* Amit; Maat; Osiris; Thoth.

Negoogunogumbar (Pygmy People, Africa)
He is a monster ogre who swallows children.

Neha-Bra (Egypt) *see* Serqet.

Neha-Hau (Egypt) *see* Assessors.

Neha-Hra (Egypt) *see* Ab-esh-imy-duat.

Nehallennia (Norse)
Goddess of plenty. She is a local deity who appears to be connected with the sea or with sailors. According to some she was a deity worshiped only on Walcheren Island in the North Sea. The cornucopia is her symbol.

Neheb-Kau (Egypt) *see* Assessors; Nut.

Neheb-Nefert (Egypt) *see* Assessors.

Nehebkau *Neheb-kau* (Egypt)
Serpent deity. Mother goddess. She is one of the principal deities mentioned in the Pyramid Texts. Nehebkau is generally thought of as an underworld deity. In some versions this goddess is associated with food. She is shown as a serpent with human legs.

Neheh (Egypt)
Also known as: *Heh.*
Deity of eternity. This god is the personification of eternity, representing unending time and a long, happy life. He is shown as a squatting man carrying a symbol of life and wearing a curved reed on his head. *See also* Heh.

Nehelennia (Teutonic)
Fertility goddess. Nehelennia is depicted standing on a boat. *See also* Nerthus.

Nehesu (Egypt) *see* Aamu.

Nehi (Egypt) *see* Aai.

Nehmauit (Egypt)
A wife of Thoth. Her name means "Uprooter of Evil."

www.ebook3000.com

Tan Tien Consciousness: Second Brain

Already terms have been used like ‘upper mind’, ‘feeling and awareness mind’ in the abdomen and lower ‘Tan Tien’. In the next phase of practice, the ‘conscious mind of the heart’ is introduced. For those readers who have not been updated on the scientific and medical revelations of the recent era about a ‘second’ and ‘third’ brain, we offer the following information.

Along with this, there is the long-standing Taoist practice of cultivating and training consciousness in the Three Tan Tiens, especially the Lower Tan Tien. There is my own experience in participating in brain wave measurements and ‘brain energy potential’ research in recent years. The combination of all these areas of knowledge and experience in our time, makes Cosmic Healing practices accessible for our minds while also being very ‘down to earth.’ Now let’s talk about the Lower Tan Tien.

In addition to its importance as the control center for the mechanics of the physical structure of the body, the Lower Tan Tien also houses a treasure of even more far-reaching significance. It has been a well-kept secret in the western world, as well as in most of the rest of the world: our Second Brain. Most of us who have had Taoist training in Chi Kung, Tai Chi, various Chi meditations or healing practices have often heard the reminder, ‘Be aware of your Tan Tien.’ But, do most people really ‘get’ the meaning of the injunction to always be conscious of the Tan Tien? Probably not. Further, do we use our Second Brain as much as we can? Definitely not.

In western terms, do we actually understand “Be aware of your Tan Tien” as being a way to train consciousness and awareness, like educating a brain in the abdominal area, in our Tan Tien? Probably not. Throughout the world, there are institutions to train the brain in the head. That is good. But, what about training the ‘second brain’ in the abdominal area? I didn’t think of it exactly like that in western terms, either, even though that is exactly what I have been doing all of my life in my Taoist training and teaching.

Personal Revelation

Suddenly I came to understand a few things which are so simple and so important, and that’s what I am going to share with you. It started in 1994 in Los Angeles when a clinical psychologist there, Dr. Rhonda Jessum, wanted to start testing me. I agreed to do the testing, but the machines at that time didn’t tell me much. However, it was discovered that when I did the Inner Smile meditation, my brain waves went down dramatically – but at the same time, my ‘beta’ waves increased to a very high level. That means the waves showed that I could be driving a car, but that my brain should have been resting and sleeping. So the researchers said, “Hey, how did you do that?” I didn’t understand either – because it was not clear to me either.



Fig. 3.10 *First and Second Brains are linked.*

Neht (Egypt)
One of the principal gods mentioned in the Pyramid Texts.

Neit (Egypt) *see* Neith.

Neiterogob (Masai People, Africa) Goddess of Earth.

Neith *Neit* (Egypt)
Also known as: *Mehueret* (her name as the Celestial Cow), *Net, Nit, Nut, Nyt, Pallas Athene* (Greek), *Tehenut* (the Libyan).
Mother of the gods. Goddess of hunting. Mistress of the cow. Sky goddess. Warrior goddess. Mortuary goddess. Protector of the city of Sais (capital of Egypt in the seventh century A.D.). Protector of marriage. Weaver. Patron deity of the arts of domestic life. Arbitrator. In early times she was worshiped as two crossed arrows either on a shield or an animal skin. Later, she had the attributes of a woman. She wore a crown and held a bow and arrows. Later still, she appeared with her attribute, the weaver's shuttle. Around the 7th century C.E. she became the mother of the gods, and a sky goddess. Neith existed before the beginning and it was she as Mehueret, the Celestial Cow, who gave birth to the sky. Renowned for her skills and her wisdom, she was the weaver of the world. When conflict arose between Horus and Set over the vacancy left by Osiris' death, the god called upon Neith to act as the arbitrator. She is shown with Isis offering bread and water to the dead when they reach the otherworld. She is often seen with Selket, the goddess who protects the canopic vase holding the intestines of the dead. Neith is one of the deities who welcomes the dead at the gates of the otherworld. Sometimes she is replaced by Ament, Hathor, Maat, or Nut. When Osiris died, she watched over his coffin with Isis, Nephthys, and Selket. The practice of placing weapons around funeral biers in ancient times may have been connected to her. It was said that mummy wrappings were the gifts of Neith and they allowed the dead to partake of her divine powers. Neith dwells in Acacia. She is often depicted with a shield and arrows or with a bow and arrows. Sometimes as a cow with stars on its belly. The Nile perch was sacred to Neith. The goddess Hatmehit wore a fish (perhaps a dolphin) on her head and was revered as the "first of the fishes." As personification of the sky, she could be identified with Nut. Neith is the female counterpart of Anubis. She is identified with the Greek Athena. Sometimes, Neith is called the mother of Ra. Her association is with Khnum, Sobek and Amunet, Thoth and Horus. Her name is associated with the hunting goddess, Sais. *See also* Ament; Amentet; Anubis; Athena; Chaos; Hathor; Hapy (A); Horus; Khnum; Nut; Selket; Set.

Nejamesha (Jains; India)
Also known as: *Naiga-Mesha, Nemeso.*
God of children. He has wings and the head of a goat.

Nekhbet (Egypt)
Also known as: *Eileithya* (Greek), *Nekhebet, Nekhebit.*
Goddess guardian of Upper Egypt. Her epithet is "she who binds the nine bows." The Greeks called her Eileithya (the city of Eileithyiaspolis) and as such was the goddess of childbirth.

Known as the vulture goddess, Nekhbet became a national goddess and represented Upper Egypt. Lower Egypt was represented by Wadjet of Buto (also known as Edjo), the snake goddess. The vulture and the snake represented the two halves of the country. Symbols of the animals became embodiments of the two crowns and the two uraei surrounding the solar disc were often thought of as Nekhbet and Wadjet. Nekhbet is also one of the principal deities mentioned in the Pyramid Texts. She is depicted as a serpent or a vulture protecting the pharaoh as she hovers over his head with her wings outstretched or as a woman wearing a vulture skin over her head. Nekhbet is the counterpart of Buto. *See also* Wadjet.

Nekhebet (Egypt) *see* Nekhbet.

Nekhen (Egypt) *see* Assessors.

Nekheny (Egypt) *see* Horus.

Nekhibit (Egypt) *see* Nekhbet.

Neleus (Greek)
King of Pylos. Neleus is the son of the sea god, Poseidon, and Tyro, who was the second wife of Cretheus, the founder and first king of Iolcus. Neleus is the twin of a brother, Pelias. The twins were abandoned at birth and raised by a keeper of horses. Pelias carried the imprint of a hoof on his face from being kicked by a horse when he was an infant. Pelias usurped Neleus from the throne to prevent Aeson, the eldest son of Cretheus and Tyro, from becoming king. Neleus married Chloris and became the father of twelve sons. He refused to purify Heracles after he murdered Iphitus during a bout of insanity. Angry, Heracles killed all Neleus' sons, except Nestor. *See also* Cretheus; Iphitus; Heracles; Pelias; Pyro.

Nemain *Neamhan, Neman* (Celtic)
Goddess of panic. War goddess. Might be same as Morrigu Morrigan. Possibly part of the triad of Neman, Morrigu and Macha that made up Badb. *See also* Badb; Morrigu.

Neman (Celtic) *see* Nemain.

Nemcatacoa (Chibcha People, Bogata, South America)
God of weavers and dyers. His history is similar to the rainbow god Chuchaviva. Both of these deities have the unusual task of guarding drunkards. *See also* Chuchaviva.

Nemeds (Irish) *see* Banbha; Tuatha De Danann.

Nemesco (India) *see* Nejamesha.

Nemesis (Greek, Persian)
Also known as: *Adrasteia.*
Goddess of retributive justice. Nymph-goddess. Nemesis, the daughter of Erebus and Nox, who relentlessly meted out just punishment to evildoers, lawbreakers, the proud and haughty, is known as Daughter of the Night. She was also known and worshipped as the beautiful daughter of Oceanus because as the nymph-goddess with the apple-bough she was also the sea-born Aphrodite, sister of the Erinyes. It is possible that her Greek origin transpired when the Persians, conquered after invading Greece, left behind a block of marble from which the Greeks carved a statue of Nemesis. It is said that in attempting to avoid Zeus, she changed herself into a goose but failed to escape when Zeus became a swan. Her egg, hatched by Leda, became Helen of Troy (the cause of the Trojan War). She has been shown as a regal woman seated in a chariot drawn by griffons. (The griffon was the symbol of retributive justice.) The

ash tree was one of Nemesis' seasonal disguises. She is also depicted with an apple-bough in one hand, and a wheel in the other, wearing a silver crown embellished with stags. *See also* Adrastia; Aether; Erebus; Eumenides; Helen; Keres; Meliae; Nox.

Nemeso (India) *see* Nejamesha.

Nemo-kuni (Japan) *see* Yomi.

Nemon (Celtic)
Also known as: *Nemontana.*
She is a war goddess who served under Morrigu (q.v.).

Nempterequeteva (Chibcha People, Bogata South America) *see* Bochica.

Nemquetcha (Muyscaya People, South America) *see* Chia.

Nemquetheba (Chibcha People, Bogata, South America) *see* Bochica.

Nen (Egypt) *see* Nau; Nen.

Nenaunir *'Nenaunir.* (Masai People, Africa)
An evil storm god, Nenaunir is in opposition to Ngai. He may be linked to a flood myth about the rainbow swallowing the earth. The Masai attacked the rainbow and forced it to give back the earth. *See also* Ngai.

'Nenaunir (Masai People, Africa) *see* Nenaunir.

Neno-Katatsu-kuni *Ne-no-kuni* (Japan)
"Land of Roots." Another name for Yomi, the underworld realm of the dead. *See also* Yomi.

Neolya (Russia) *see* Dolya.

Nephele (Greek; possibly Semitic)
Zeus created a cloud named Nephele to look like Hera. Ixion, the king of the Lapiths of Thessaly, embraced her cloud form and they became the parents of the Centaurs and Amycus. She married Athamas and became the mother of Phrixus and Helle. Athamas' second wife, Ino, was so jealous of Nephele that she attempted to murder Phrixos and Helle. They were able to escape her fury on a winged golden ram. *See also* Abas (C); Athamas; Ino; Ixion; Phrixus.

Nephthys *Nephythys* (Egypt)
Also known as: *Nebthet, Neb-Ti.*
Goddess of the dead. Mistress of the palace. Guardian (with Hapy) of embalmed lungs. She is the daughter of Geb (the earth) and Nut (the sky). She was the wife of her brother Set the god of thunder. Commitment did not stop her from getting her other brother Osiris intoxicated and then seducing him. Anubis, the god of embalming was the son of their union. When Set murdered Osiris, she left him. With Isis, another protector of the dead, the goddesses embalmed Osiris. To mourn Osiris, they turned themselves into kites. Nephthys and Isis are shown with winged arms. Nephthys is the female counterpart of Set and Min. *See also* Anubis; Atum; Geb; Hapy (A); Isis; Nut; Osiris; Selket; Set.

Nephythys (Egypt) *see* Nephthys.

Nepra (Egypt) God of corn. *See also* Tchabu.

Nepri (Egypt) *see* Renenet.

Nept-Uns (Roman) *see* Neptune.

Neptune (Roman)
Also known as: *Nethunus* (possibly Etruscan), *Poseidon* (Greek).
God of the waters. Husband of Salacia, goddess of streams. *See also* Aello; Harpies; Poseidon.

Neptunus (Roman) *see* Neptune.

Nereides (Greek) *see* Nereids.

Nereids *Nereides* (Greek)
Nymphs of the sea and ocean. Shape shifters. The Nereids are the fifty daughters of Nereus and Doris. The Greek authors Homer, Hesiod, Hyginus and Apollodorus all named them, but the number of Nereids and their names were not in accord. Actaea, Agave, Doto, Dynamene, Galateia, Panope (Panopae in Hyginus' list), Pherusa, Speio, and Thetis are in all four recordings. Other Nereids who developed individual myths are Ceto (also called the daughter of Oceanus and Gaea), Amphitrite and Doris. They were said to dwell at the bottom of the Mediterranean with Nereus and they could be the prototypes of the mermaid. Kind to sailors, they assisted the Argonauts as they navigated their ship past Charybdis and Scylla, who guarded the entrance to the straits of Messina. The beautiful, gentle nymphs are attendants of the sea-goddess Thetis. *See* Naiads, the deities of lakes and fountains, for comparison to other water deities. *See also* Acis; Amphitrite; Andromeda; Ceto; Charybdis; Doris; Hylas; Irra; Nereus; Nymphs; Reshep; Scylla; Thetis.

Nereus (Greek)
Also known as: *Phorcus, Phorcys, Phorkus, Phorkys, Proteus.*
Sea god. Shape shifter. Nereus is a sea divinity, son of Oceanus and Gaea, or Pontus and Gaea. His siblings are the "fair-faced" Ceto; the sea god Phorcys; Thaumas, also a sea god; Eurybia, the "flint-hearted;" and Crius. He married the sea goddess Doris, with whom he had fifty daughters, called the Nereids. Nereus, known as "the old man of the sea," was a shape shifter, gifted with prophecy and lived in the Aegean Sea. He was captured by Heracles who forced him to disclose the location of the Garden of Hesperides. Nereus, like most sea gods, is depicted with seaweed for hair. *See also* Actaea; Amphitrite; Ceto; Doris; Gaea; Nereids; Oceanus; Thaumas.

Nergal *Nirgalu* (Assyro-Babylonia, Phoenicia, Sumer; possibly of Egyptian origin).
Also known as: *Enmesarra, Gira, Girra, Ira, Irra, Lugalmeslam, Malik, Mekel, Meshlamthea, Reshef, Reshep.*
God of the underworld. Lord of fires. Supreme ruler and judge of Arallu, the land of the dead. God of midsummer sun, war, pestilence, the chase, and a protector deity. He is also a god of flocks and foaling. In earlier myths, he was a god of war. He is the brother and counterpart of Ninurta. Nergal led a company of evil spirits (possibly seven gods) who were ruled by Narudu, into the underworld, forcing its queen, Ereshkigal, to marry him and appoint him sovereign of her kingdom as the price of peace. In the form of Irra, his messenger is Ishum. He is associated with Marduk and is sometimes identified with Shamash. Nergal's attribute is a sword or the head of a lion. He

www.ebook3000.com

is possibly shown as a winged lion. *See also* Allatu; Arallu; Ereshkigal; Irra; Naruda; Ninurta; Satan.

Neri (Norse; Teutonic)
Also known as: *Norine.*
He is the ruddy faced sky or morning god, who is the son of Loki and Nott (qq.v.).

Nerig (Babylon) *see* Ninib.

Nerivik *Nerrivik* (Eskimo People, Greenland)
Also known as: *Arnarquagssaq, Sedna.*
Sea goddess. Nerivik was a mortal woman who was snatched up by a petral (sea-bird). Her relatives attempted to save her but were also attacked so they threw her into the sea. She grabbed the side of their boat and they chopped off her fingers. The fingers became seals and whales. Nerivik sank to the sea's floor, was transformed into a sea goddess and became the ruler of the food for the living and ruler of the souls of the dead. She is guarded by a ferocious dog. She is sometimes called the "Food Dish." Nerivk is comparable to Sedna (q.v.) *See also* Adlivun, the home of Sedna.

Nerrivik (Greenland) *see* Nerivik.

Nerta (Egypt) *see* Ap-taui.

Nertha (Teutonic) *see* Nerthus.

Nerthus *Nertha* (Norse; Teutonic)
Also known as: *Hertha, Iron Lady* (German), *Njord, Terra Mater* (Roman).
A goddess of water, fertility, death and peace. Earth deity. She is the sister or wife of Njord. As a deity of death and fertility, the Teutons carried Nerthus around on a wagon to fertilize the fields. Her symbol is a boat. *See also* Bertha; Hertha; Njord.

Nesaru (Arikara People)
"The Power Above." Supreme deity. He created Mother Corn from an ear of corn. She led the people from the underworld to the light of day.

Nesert (Egypt)
One of the principal gods mentioned in the Pyramid Texts.

Nesr (Arabic) Vulture God.

Nesreca (Serbian) *see* Sreca.

Nessus (Greek)
His parents are Ixion and Nephele. A Centaur, he attempted to rape Deianeira and was slain by her husband, Heracles. The blood and semen of Nessus, left on his coat and given to Heracles by Deianeira caused his death. After death, Nessus became the ferryman of the river Evenus, in the underworld. *See also* Centaur; Deianeira; Heracles; Ixion; Nephele.

Nestor (Greek)
King of Pylos for three generations. He was possibly married to Anaxibia. A wise and honorable man, Nestor had ninety ships that sailed to the Trojan War. Remarkably, they all returned safely. *See also* Antilochus; Eurydice.

Nesu (Sumer) *see* Aruru; Ninhursag.

Net (Egypt) *see* Amen (B); Ament; Neith.

Netch-baiu (Egypt) *see* Aai.

Netchesti (Egypt) *see* Aai.

Nete (Greek)
One of the Delphic Muses, she personifies the low string of the lyre. Her sisters are Hypate, the high string, and Mese, the middle string. *See also* Muses (Delphic).

Neter (Egypt)
Also known as: *Neteri, Netra, Nutar.*
The Neter is a sacred symbol in the form of an axe. It is one of the earliest representations of a divinity. There is argument as to its meaning, but some think that it means divine, strong, or mighty.

Neter-Khertet (Egypt) *see* Tuat.

Neter Mut (Egypt)
Also known as: *Theotokos* (Christian).
Aspect of Isis. A very old and common title of Isis. The Christian Fathers translated this name as Theotokos, or Mother of God. *See also* Isis.

Neter-Ta (Egypt)
Heaven. In an old document or hymn to Amen-Ra, Neter-Ta is described as the Divine Land.

Neteri (Egypt) *see* Neter.

Netetthap (Egypt)
One of the principal gods mentioned in the Pyramid Texts.

Nethert (Egypt) *see* Aai.

Neti (Sumer) *see* Arallu; Inanna.

Netra (Egypt) *see* Neter.

Neuri (Slavic)
The Neuri are a race of sorcerers who change into wolves for several days once each year. They are possibly connected with the name Vlkodlak which was the vampire or werewolf.

Ng Ai (Africa) *see* Ngai.

'Ng Ai (Masai People, Africa) *see* Ngai.

Nga (Yurak People, Siberia) God of the underworld and death.

Ngahue (Polynesia, New Zealand)
Afterworld deity. He is probably the head of the underworld as is Tawhaki. Ngahue is similar to the Tahitian, Hiro and Urutaetae.

Ngai *Ng Ai, 'Ng Ai, 'Ngai* (Masai Group; Kikuya People, East Africa)
He is a High God, the creator of all things. His abode is in the sky but when he visits earth, always invisible, he stays in the mountains. His visits are made to achieve a general overview of his people. He distributes rewards and punishments as he deems necessary. He is called upon during times of disasters, and prayed to during rites of passage, and special functions, such as marriage. He is also known as a sky god, and god of rain and clouds. Ngai found the first mortal Dorobo, or Kintu.

With the first mortal, he found an elephant and a serpent. Ngai places a guardian angel beside every man to defend him against dangers. Ngai's opponent is the evil deity Nenaunir (q.v.). *See also* Kintu.

'Ngai (Masai People, Africa) *see* Ngai.

Ngakola (Banda People, Africa)
Creator. Brother of Tere. He breathed life into mortals. *See also* Tere.

Ngalijod (Australia) see Rainbow Serpent.

Ngaore (Polynesia, New Zealand)
Goddess of grass (probably). Tane tried for a fourth time to make his mother Papa become his wife, but she again refused and sent him to Ngaore (meaning "tender one"). Instead of children, his new wife conceived rush type grasses. After many other attempts, Tane finally found a wife who would bear a human child. She was Hine-ahu-one (q.v.). *See also* Hine-ahu-one; Mumahango; Papa; Rangahore; Tane.

Ngaru (Mangaia Island, Polynesia)
A culture hero, Ngaru caused a deluge to keep the female demon Miru from cooking him. He also overcame the sky demon Amaite-Rangi. *See also* Miru.

Ngewo (Africa) *see* Ngewo-wa.

Ngewo-Wa *Ngewo* (Mende People; West Africa)
Also known as: *Maanda, Ma-Ngee.*
Creator of everything. He was called by the humans he created Maanda (grandfather), Ma-ngee (grandfather-take-it) and Ngee-wolo-nga wa-le (grandfather-take-it-is-spread-wide). The first name was given him because he gave humans whatever they asked for. The second name was given him after he disappeared.

Ngunyari (Australia) *see* Walangala.

Ngurunderi (Australia) *see* Bunjil; Daramulun; Nurrundere.

Ngurvilu (Araucanian People, Chile)
God of water, lakes, and seas. He is the cause of boat and swimming accidents. Ngurvilu is shown in the form of a cat with a long claw on the end of its tail.

Ngworekara (Fan People, Africa)
An evil demon king, he rules over the kingdom of evil spirits who were souls of the dead. Ngworekara and his spirits are depicted with dirty ears, droopy noses resembling elephant trunks and, long straggly hair.

Nhangs (Armenian, Persian)
Evil river spirits. They can appear as women, mermaids, seals, crocodiles and even sea monsters. They drag swimmers under water and drown them. *See also* Devs.

Ni (Inca People, Peru)
Also known as: *Ocean.*
Sea deity. Little is known about Ni, but he or she was worshiped as a provider of fish. *See also* Si; Vis.

Nibelung *Nibelungen, Niblungs, Niflungar, Niflungs* (Norse; Teutonic)
High gods. Nibelung is the brother of Schilbung. They were slain by Siegfried with the sword Balmung. In the plural, the Nieblungs are dwarfs who came from a land of mist where Giuki and Grimhild ruled. The rulers have three sons: Gunnar, Hogni, Guttorm, and one daughter, Gudrun. *See also* Dwarfs; Gudrun; Siegried; Sigurd.

Nibelungen (Teutonic) *see* Nibelung.

Niblungs (Teutonic) *see* Nibelung.

Nicahtagah (Maya) *see* Xumucane.

Nice (Greek) *see* Nike.

Nichan (Gros-Ventre Group of Algonquin People, North America)
He is a creator god who first destroyed the world by fire and later water. *See also* Gluskap; Manibozho.

Nicippe (Greek)
Also known as: *Amphibia.*
Her parents are Pelops and Hippodameia. She married Sthenelus and had three children: Alcino, Eurystheus and Medusa (not to be confused with the Gorgon, Medusa). See Hippodameia (B) for the names of Nicippe's siblings. *See also* Pelops.

Nick (Teutonic) *see* Nix.

Nicor (Teutonic)
They are malignant water monsters who drown people. *See also* Nixie.

Nicostratus (Greek)
Helen of Troy was driven from Sparta by Nicostratus and his brother, Megapenthes, when the king of Troy, Menelaus, died. *See also* Menelaus; Helen.

Nidaba (Babylon)
Corn goddess. Counterpart of Nabu. In old legends she was, like Nabu, a patron of letters. Nidaba is associated with Adad and Enlil. Some believe she was a form of Ishtar. She is depicted with serpents springing from her shoulders. *See also* Nabu.

Niddhogge (Teutonic) *see* Nidhod.

Nidhema *Naivedya Sal-za-ma* (Tibet) *see* Amoghasiddhi.

Nidhod (Teutonic)
Also known as: *Niddhogge, Nidhogg, Nidhoggr, Nidhug, Nighhoggr, Nithogg.*
A winged dragon, Nidhod flies around Nifelhel. He is one of several monsters who try to injure the roots of the world-tree, Yggdrasil. Nidhod chews on the corpses of evil people. *See also* Nastrond; Yggdrasil.

Nidhogg (Teutonic) *see* Nidhod.

Nidhoggr (Teutonic) *see* Nidhod.

Nidhug (Teutonic) *see* Nidhod.

Nidim (Assyro-Babylonia) *see* Ea.

Nidra (India)
She is the goddess of sleep, and the daughter of Brahma.

www.ebook3000.com

Nifelheim (Teutonic) *see* Nifl-heim.

Nif'fleheim (Teutonic) *see* Nifl-heim.

Nifl-heim *Nif'fleheim, Nifelheim, Nifhel, Niflheim, Nivlheim.* (Norse; Teutonic)
Also known as: *Hel, Hell, Realm of the Mist.*
Nifl-heim, the world of mist, ice and darkness, is situated in the north section of Ginnunga-gap, the primeval abyss. Within Nifl-heim is a spring known as Hvergelmir (also called Kvergjelme). From the spring ten, eleven, or twelve rivers known collectively as the Elivagar flowed and turned to ice by the cold wind from Ginnunga-gap. The goddess Hel became the queen of Nifl-heim where the tree of life, Yggdrasil tree, has roots. Nifl-heim is known in some myths as the lowest of nine worlds and the abode of those who die of old age or disease. *See also* Bifrost; Elivagar; Ginnunga-gap; Gleipnir; Hel; Hell; Hvergelmir; Midgard; Muspells-heim; Surtr; Yggdrasil; Ymir.

Niflheim (Teutonic) *see* Nifl-heim.

Niflhel (Teutonic) *see* Nifl-heim.

Niflung (Teutonic) *see* Nibelung.

Niflungar (Teutonic) *see* Nibelung.

Niflungs (Teutonic) *see* Nibelung.

Nig (Teutonic) *see* Nix.

Nighhoggr (Teutonic) *see* Nidhod.

Night (A) (Greek) *see* Chaos; Fates; Nyx.

Night (B) (Norse; Teutonic)
Goddess of night. Daughter of Narvi. Mother of Day. She rides her horse around the world. *See also* Nott.

Night Gods (Aztec) *see* Lords of the Night Hours.

Night Journey (Islamic) *see* Mohammed.

Nightingale (Greek) *see* Aedon.

Nigi-mi-tama (Japan) *see* Susanowo.

Nigishzida (Mesopotamia) *see* Anu (B).

Nihongi, The (Japan) *see* Ama-no-minaka-nushi.

Nii-no-ama (Japan) *see* Suitengu.

Nijuhachi-bushu (Japan)
Protectors. They are the servants of the goddess of peace, Kuan-Yin. Twenty-seven of the servants' names are Hibakara-o, Sanshi-taisho, Mansen-o, Kompira-O, Karura-o, Kinnara-o, Konshiki-kujaku, Komoku-ten, Kendatsuba, Konda-o, Gob-ujo, Misshakukongo, Bishamon-ten, Daibon-ten, Teishaku-ten, Toho-ten, Zocho-ten, Shakara-o, Magora-o, Nandaryu-o, Daibenszit-ten, Makeshura, Shimmo-ten, Naraen, Basosennin, Mawara-ten, and Manzenshao.

Nik (Teutonic) *see* Nix.

Nikasha (India)
She is thought by some to be the mother of Ravana, Khara, Vibhishana, Kumbhakarna and a daughter, Shurpanaka. *See also* Kuvera; Ravana.

Nike *Nice* (Greek)
Also known as: *Athena, Victoria* (Roman).
Goddess of victory. Nike is the daughter of the river nymph Styx and the Titan, Pallas. Her sisters are Bia, the personification of violence or force, Zelus, jealousy or zeal, and Cratus, strength. As Nice, not to be confused with Nice, mother of Nicodromus, or Athena as Athena Nice. She is shown as a winged woman holding a wreath. She is also depicted raising a trophy or leading the horses of heroes. *See also* Pallas; Styx.

Nikkal (Mesopotamia)
Goddess of the fruits of summer. Some think that she is the youngest of the Kathirat (q.v.). *See also* Yarik.

Nila Tara (India) *see* Tara (B)

Nila-Vastra (India) *see* Bala-Rama.

Nilakantha (India) "Blue Throat." *See also* Shiva.

Nilavarahi (Nepal) *see* Varahi.

Nile (Greek)
He is the river god son of Oceanus and Tethys. His children are Anchinoe, who married Belus, king of the Nile and Memphis, who married Epaphus, king of Egypt. *See also* Agenor (A); Anchinoe; Belus; Epaphus.

Nimah (Sumer) *see* Ninmu (A).

Nimrod (Hebrew)
Early deified king of Babel. Nimrod, grandson of Ham and son of Cush, is generally thought of as the first mortal ruler of the world. He is sometimes identified with Marduk. Nimrod ordered the building of the Tower of Babel. *See also* Marduk.

Nimsimug (Babylon)
She is the daughter of Enki and Ninmu. Her daughter is the goddess Utto by her father, Enki.

Nimue (Arthurian) *see* Vivien.

Nimurta (Sumer) *see* Ninurta.

Nin-Ib (Akkadia, Assyro-Babylonia, Sumer)
Also known as: *Adar, Nerig, Nin-ib, Nineb, Ninurta, Nirig, Reshep.*
God of spring sun and morning sun. He is usually shown as an eagle. *See also* Adar; Ninib; Ninurta.

Nin-Ip (Babylon) *see* Ninib.

Nin-kar-zi-da (Assyro-Babylonia) *see* Ishtar.

Nin-karrak (Assyro-Babylonia) *see* Ninkarrak.

Nin-khar-sagga (Assyro-Babylonia) *see* Ishtar.

Nin-kharak (Assyro-Babylonia) *see* Ninkarrak.

Nin-Khursag (Sumer) *see* Ninhursag.

Nin-Ki (Sumer) *see* Ninki.

Nin-Lil (Semitic) *see* Adar; Ninlil.

Nin-si-anna (Assyro-Babylonia) *see* Ishtar.

Nin-Si-Anna (Middle Eastern) *see* Ishtar.

Nina (A) (Mexico) *see* Xochiquetzal.

Nina (B) (Sumer)
Also known as: *Ninetta, Ninevah.*
Mistress of the Goddesses. Nini is a local goddess. She is a daughter of Ea and goddess of the city of the same name, later called Ninevah. She uttered oracular responses from the temple at Nina, dedicated to her brother Ninurta. Her sister is the architect goddess, Nisaba. With Imhursag, she became the mother of a son, Ningirsu. *See also* Belit-sheri; Ea; Ishtar; Nana.

Ninagal (Assyro-Babylonia) *see* Ea.

Ninanna (Babylonia) *see* Innini; Nintud.

Ninatta and Kulitta (Babylonia)
They are goddesses of music who are Ishtar's attendants.

Ninazu (Sumer)
Sun god. He is the grandfather and possible father of Tammuz.

Ninbubu (Assyro-Babylonia) *see* Ea.

Nindubarra (Assyro-Babylonia) *see* Ea.

Nindulla (Semitic) One of the deities created by Ninhursag.

Nindurra (Sumer) *see* Ninkurra.

Nine Songs, The (China)
Creators. **1.** Tung Huang T'ai I was worshiped as the Eastern Emperor. **2.** Yun Chung Chun, god of the clouds. **3.** Hsaing Chun, god of the waterways of Hsiang (Hunan). **4.** Hsiang Fu-Jen, two daughters of Emperor Yao, Wo Huang, the older, and Nu Ying, the younger. **5.** Ssu Ming, arbiter of life and death, protector of virtue and enemy of evil. **6.** Tung Chun, god of the sun rising in the East. **7.** Ho Po, god of the Yellow River. **8.** Shui Shen, god of the fishes. **9.** Yu Po, Feng I and Shui I, gods of the waters. *See also* Dragon Kings; Ho Po; Yu Shih.

Nineb (Babylon) *see* Ninib.

Ninedinna (Babylon)
She is the Goddess of the Records of the Dead. She may be the same as the Sumerian goddess Ninisinna, a sister goddess of Inanna (q.v.).

Nineishizda (Sumer, Babylon) *see* Ningishzida.

Ninella (Assyro-Babylonian) *see* Damkina.

Ninetta (Sumer) *see* Nina.

Ninevah (Sumer) *see* Nina.

Ningal (Semitic, Sumer, Babylon)
Also known as: *Aruru, Ninhursag, Ninmah, Nintu.*
Sun goddess. She is the wife of Sin, and mother of Shamash. Ningal is identified with the Summerian goddess, Ki. *See also* Aruru; Ianna; Nammu; Nana; Ninhursag; Ninlil; Ninmah; Nintu.

Ningirda (Sumer) *see* Ereshkigal.

Ningirsu (Sumer)
Also known as: *En-Mersi, Ninurta* (possibly).
Deity of irrigation and fecundity. God of the city of Lugash. He is the son/husband of Bau. In later times, he became a war god. Ningirsu is shown as a goat, a lion-headed eagle, or a lion with a branch in his front paws. Possibly he is the same as Ninurta (q.v.). He may be an aspect of Tammuz.

Ningishzida (Babylon, Sumer)
Also known as: *Nineishizda, Unummuzida.*
Guardian or tree god. Created by Anu. Some say he is the father of Tammuz, with whom he guarded the gate of Anu's dwelling place. The mother of Tammuz is either Etuda or Ereshkigal. The Sumerians called Ningishzida a companion of Tammuz. In one poem he seems to be connected with Arallu, the underworld. This is substantiated by his mother being a ruler of Arallu. The title Unummuzida may be one of Tammuz or possibly a completely different deity. He could be an aspect of Eshmun or Tammuz. He is associated with Adapa. Ningishzida is represented as bearded and with a serpent springing from each shoulder. *See also* Arallu; Tammuz.

Ningizzida (Sumer) *see* Gizidu.

Ningursu (Sumer) *see* Ningirsu; Ninurta.

Ningyo (Japan)
Mermaid spirit. Ningyo, sometimes seen by earthly eyes, has long hair and the body of a fish. Pearls are said to be her tears. A woman who eats the mermaid spirit's flesh gains perpetual youth and beauty.

Ninharsag (Sumer) *see* Ninhursag.

Ninhursag *Nin-Khursag, Ninharsag, Ninkhursag.* (Sumer, Accad)
Also known as: *Aruru, Bau, Belit, Belit-Illi, Belitis, Ga-tum-dug, Gula, Innini, Ki, Nammu, Ningal, Ninkarrak, Ninki, Ninlil, Ninmah, Nintu, Ninurta.*
Earth goddess. Mother goddess. Fertility goddess.
As Ninhursag, she is called Earth Mother, queen of the cosmic mountain and queen who gives birth. As wife or sister of Enlil, she created the deities Nindulla, Ninsu-utud, Ninkasi, Nazi, Dazima, Nintil and Enshagme. She created men from clay. In one legend she is the mother of Egime and Lil (also called Nesu). In another legend, as the wife of the water god Enki, she became the mother of Ninmu, the plant goddess, the grandmother of Ninkurru and the great grandmother of Uttu the goddess of plants. She is also worshiped under the name of Ninlil. *See also* Aruru; Belit; Beltis; Damkina; Enki; Enlil; Ga-Tum-Dug; Gula; Innini; Ki; Namma; Nammu; Ningal; Ninki; Ninlil; Ninmah; Ninmu; Ninti (one of the eight healing goddesses created by Ninhursag to heal the eight areas of disease in Enki); Nintu; Ninurt; Uttu.

Niniane (Arthurian) *see* Vivien.

Ninib (A) (Japan) *see* Ninigi.

Ninib (B) (Sumer) *see* Ninurta.

Ninigi (Shinto; Japan)
Also known as: *Ninib, Ninigi-no-mikoto* (The Heavenly Grandchild), *Piko-po-no-ninigi.*
God of prosperity. Founder of the imperial house. Ninigi's full name translated is His-Augustness-Heaven-Plenty-Earth-Plenty-Heaven's-Sun-Height-Prince-Rice-Ear-Ruddy-Plenty.

www.ebook3000.com

Ninigi, also known as Prosperity Man, was sent to earth by his grandmother, the sun goddess Amaterasu, and other deities to become the divine ruler of Japan. He replaced Okuni-nushino-mikoto's sons. To insure strong leadership, Amaterasu gave Ninigi the three symbols of power. In later years, the items, a mirror, jewels and a sword, became the Imperial emblems of power. Ninigi settled in a palace on Cape Kasasa in the province of Hyuga. He met and married a woman noted for her beauty, Kono-Hana-Sakuya-Hime (Blossoms-of-the-Trees-Blooming-Princess), also known as Sakuya-hime. She is the daughter of the mountain god O-Yama-Tsu-Mi (also spelled Opo-yama-tu-mi-no-kami) and Kaya-no-hime-no-kami (meaning Ruler of the Grassy Plains) and the sister of Iha-haga-hime. The princess is an ancestor of the Emperor Jimmu Tenno. Ninigi, a jealous husband did not believe that she was faithful to him because she conceived the night of their wedding. His attitude infuriated her. She built a muro, a small dwelling without doors, and at the moment of birth, she set fire to it. She told Ninigi that if she were not telling the truth, the child would die. As the flames soared around her, she gave birth to three sons, Hoderi, Hosuseri and Hikohohodemi. The new mother and children emerged unharmed from the inferno. Later writing mentions only two sons, Hosuseri and Hikohohodemi. Ninigi's wife Kono-Hana-Sakuya-Hime had a divine rice field named Sanada. From her rice she made "heavenly" sweet sake, according to the early Shinto recordings in the *Nihongi.* She initiated the annual festival which was later known as Nihi-nahe (also nihi-name) celebrated November 23rd. On this day the season's new rice was offered to the gods and to the Emperor. When her sons were born she severed their umbilical cords using a bamboo knife. Bamboo represents courage and steadfastness and is considered a lucky symbol. Cherry trees surround the shrine dedicated to Kona-Hana-Sakuya-Hime, O-Yami-Tsu-Mi and Iha-haga-hime. O-Yama-Tsu-Mi is venerated as Father Mountain and Iha-haga-hime as Rock Princess. For events prior to Ninigi's descent to earth, *see* Izanagi. For details of the sacred treasures, *see* Susanowo. *See also* Ama-no-Uzume; Amaterasu; Ame-no-Oshido-Mimi; Hikohohodemi; Hiruko; Hosuseri; Ishikoridome-no-Mikoto; Kaya-no-hime-no-kami; Kusanagi (the sacred sword); Okuni-Nushino-Mikoto; Sengen; Susanowo; Take-mi-kazuchi; Toyo-Tama-Bime.

Ninigi-no-mikoto (Japan) *see* Ninigi.

Ninigiku (Sumer)

Also known as: *Ea.*

This name, meaning "King of the Sacred Eye," was given to Ea because of his omniscience and wisdom.

Ninildu (Babylon) God of construction. *See also* Ea.

Nininni (Babylon) *see* Nintud.

Ninisinna (Sumer) *see* Inanna; Ninedinna.

Ninkarrak *Nin-karrak, Nin-kharak, Ninkarraka* (Assyro-Babylonia, Sumer)

Also known as: *Gula* (possibly), *Ishtar, Ninhursag, Ninki.*

Babylonian and Sumerian goddess of medicine and healing, Ninkarrak nursed sick humans. She is the daughter of Anu, sister of Gibal, the fire-god, and is sometimes given the role as the consort of Ninurta. The dog, as a protector of homes is associated with her. Ninkarrak is also an epithet of Ishtar (q.v.). *See also* Adapa; Anu; Daminka (B); Gula; Ninhursag; Ninki.

Ninkarraka (Assyro-Babylonia) *see* Ninkarrak.

Ninkasi (Semite)

God of the vine. Ninkasi is one of the deities created by Ninhursag. He is sometimes shown as a goddess. She (or he) helped Lugalbanda or Ninurta in rescuing the "Tablets of Fate" from the nest of Zu. Ninkasi is similar to Dionysus.

Ninkhursag (Sumer) *see* Ninhursag.

Ninki *Nin-Ki* (Sumer)

Also known as: *Bau, Belit-Illi, Belitis, Damgalnunna, Damkina, Ga-Tum-Dug, Gashan-Ki, Gula, Innini, Ki, Ninhursag, Ninkarrak, Ninlil, Ninmah, Ninmu, Nintu.*

It is possible that she is a goddess of fresh water and one of Enki's wives. She was honored at the funeral ceremony for Gilgamesh. *See also* Beltis; Damkina; Ea; Enki; Gula; Ki; Marduk; Ninhursag; Ninkarrak; Ninlil; Ninmah; Ninmu (A); Nintu.

Ninkilim (Sumer) *see* Ninurta.

Ninkurra *Nindurra* (Sumer) *see* Enki; Ninmu; Uttu.

Ninlil (Assyro-Babylonian; Sumer)

Also known as: *Beltis, Haya* ("Goddess of Direction"), *Ninhursag, Ninki, Ninlilla, Nisaba.*

Ninlil is a mother goddess, air goddess, goddess of fertility, and goddess of sailors. She is the daughter of Nunbarshegunu, a goddess said to have lived in Nippur before the creation of mortals. Known as the Sumerian virgin mother, Ninlil was considered to be Enlil's consort or sister/wife. In one interpretation of this myth, Ninlil was raped by sky god Enlil as she was sailing. He was condemned by a council of gods to live in the underworld for his despicable deed. In another version, Ninlil deliberately disobeys her mother and bathes by the river so that Enlil will see her. In yet another variation, it is her mother, Nunbarshegunu, who is determined to arrange a marriage between Ninlil and Enlil. In both versions, the result is similar. He seduces the goddess and leaves her. She follows him and although he keeps turning up in disguise, they are again intimate. On the boat that is crossing the river to the underworld, she submits to him once more, and their child Nanna (also known as Sin) is conceived. She fell so deeply in love with him that she followed him to the underworld. The gods decided that she had to postpone this trip until she gave birth as the child was to be Nanna the moon god and they didn't want him born under the earth. After Nanna's birth, he was left in heaven and Ninlil descended to join Enlil. They had three more children who were minor underworld deities. In some renditions, the three children are born first. They are the substitutes who must be left in the underworld so that Nanna may be born in heaven. Ninlil and Enlil became the grandparents of Nanna's offspring by Ningal, who is the sun god Utu. Ninlil assisted Enlil in bestowing kingship on earthly monarchs. She was one of a trinity with Anu and Ea. This myth may be connected with an early belief in the impregnating powers of water. *See also* Anu; Aruru; Beltis; Ea; Enlil; Ishtar; Nammu; Nanna (B); Ningal; Ninhursag; Ninki; Nisaba; Utu.

Ninlilla (Assyro-Babylonian) *see* Ninlil.

Ninma (Sumer) *see* Ninmu.

Ninmah (Middle Eastern) *see* Mah (B).

Ninmah (Sumer)

Also known as: *Aruru, Mah, Ningal, Ninhursag, Ninki, Ninmu.*

Ninmah is one of the most important aspects of the goddess Mah. Mah has forty-one other names and aspects. *See also* Aruru; Mah (B); Nammu; Ningal; Ninhursag; Ninki; Ninmu; Nintu.

Ninmu *Ninma* (Sumerian)

Also known as: *Ki, Ninki, Ninmah, Ninsar.*

Ninmu the goddess of plants is the daughter of the water god Enki and the goddess Ninhursag. Through incest with Enki, she became the mother of Ninkurra. Ninkurra later mated with her grandfather Enki, and Uttu, the goddess of plants, was born. In a variation of this myth, Nintu and Enki became the parents of Ninmu and Ninkurra. Enki committed incest with Ninkurra and became the father of Uttu goddess of plants. There is a possibility that Ninmu is also a sea goddess. She is associated with the Sumerian goddess, Nammu (q.v.) and identified with the goddess Ki (q.v.). *See also* Enki; Ninhursag; Ninki; Ninmah; Uttu.

Ninmug (Sumer) *see* Inanna.

Ninsar (Sumer) *see* Ea; Ninmu.

Ninshubur (Sumer) *see* Inanna.

Ninsinna (Babylon) *see* Innini; Nintud.

Ninsu-Utud (Akkadian, Babylonian, Sumerian)

Goddess of Healing. She is one of the deities created by Ninhursag. One of her specialities is to heal aching teeth. Ninsu-Utud is the spouse of Ninazu. *See also* Ninhursag.

Ninsubur (Akkadian, Babylonian, Sumerian)

Also known as: *Ilabrat, Ili-Abrat, Ninurta, Papsukkal.*

Messenger. In one legend Ishtar sent Ninsubur to get a description of her rival Saltu. The name is also an early title of Ninurta. Ninsubur is identified with Papsukkal and Ilabrat, who are also messengers. *See also* Ilabrat; Ninurta; Papsukkal; Tammuz.

Ninsun (Chaldea, Sumer)

Also known as: *Situr.*

She is the goddess of the city of Uruk and mother of the multi-talented goddess Gestinanna and the shepherd god Dumuzi. She may also be the mother of the hero Gilgamesh. Depicted as a cow, she was considered omniscient. She is identified with Aruru. *See also* Dumuzi; Gestinanna; Gilgamesh.

Ninth Division of Tuat (Egypt)

This division of Tuat is guarded by the monster serpent Ab-ta (q.v.).

Ninti (Sumer)

She is one of the eight goddesses of healing who was created by Ninhursag to heal corresponding diseased parts of Enki's body. Her specific healing area was the rib. *See also* Enki; Ninhursag.

Nintil (Akkadian, Babylonian, Sumerian)

One of the goddesses created by Ninhursag. *See also* Ninhursag.

Nintu (Sumerian)

She is a mother goddess and goddess of birth who corresponds to Ninhursag and Ishtar (qq.v.). She also parallels Mami, Aruru and Ninmah. She is linked with Enki in some myths. *See also* Enki; Nammu; Ningal; Ninhursag; Ninki; Ninmu; Nintud.

Nintud *Innini, Ninanna, Nininni, Ninsinna, Nintu* (Akkadia, Babylon, Sumer)

Also known as: *Belit, Belit-Ilani.*

Earth goddess. Goddess of childbirth. Possibly the sister of Enlil. As Innini she is a mother goddess who was created by Anu. Her children are Nergal and Ninurta. In her form of Nintud her husband/son was Dumuzi (Tammuz). *See also* Aruru; Belit; Belit-ili; Belit-Illi; Ereshkigal; Innini; Ishtar; Ki; Nammu; Ningal; Ninhursag; Ninki; Ninmah; Nintu; Nintud.

Nintue *see* Aruru

Ninurash (Sumer) *see* Ninurta.

Ninurta *Nimurta* (Akkadia, Canaan, Sumer)

Also known as: *Ennammasht, Ningirsu, Ninhursag, Ninib, Ninkilim, Ninsubur, Ninurash.*

War god. Irrigation god. Patron of hunters. Fertility deity. God of copper and coppersmiths. South Wind personified. The son of Enlil, and Belet-Ili. In some myths his mother is the earth goddess Ninman. There is reference to the pig being sacred to Ninurta and thus he had two other titles, Ennammasht (lord of swine) and Ninkilim, who was killed by a wild boar. The name Ninsubur was an early title of Ninurta although Ninsubur was a god in his own right. In one Sumerian myth, Ninurta instructed by his weapon, Sharur, destroys the underworld demon Asag. The Kur waters rose up and prevented irrigation waters from reaching the fields. A famine followed, but Ninurta was able to circumvent its severity by constructing a great wall made from piles of rocks in front of Sumer and over the Kur. He then directed the waters back into the Tigris. His mother, Ninmah came to visit and was made queen of the stone mound and given the name Ninhursag. Ninurta's symbol is an eagle. He is sometimes shown as lion-headed. He is associated with Ningursu. Ninhursag was possibly Ki, queen of the cosmic mountain, fertility and earth goddess (Sumerian). *See also* Abu; Ningursu; Ninhursag; Ninkasi; Ninsubur.

Ninzadim (Assyro-Babylonia) *see* Ea.

Nio (Buddhist; Japan)

Protectors of Buddhism. Guardian deities. The Nio are spirits who prevent evil from entering monasteries. Their functions include the protection of children and prevention of theft. They receive offerings of straw sandals from followers. The Nio, considered minor deities, were originally derived from Hinduism and incorporated into the Buddhist pantheon. The Nio are represented as two statues of Vajrapani. They are usually red in color and draped in simple garments. Two Nio exist at the right and left of the portals at Great South Gate of Todai-ji. They were carved in 1203 by Unkei and Kaikei. They are twenty-six feet high and although discolored, the pigment reveals red skin, brown hands and multi-colored garments. There is a glaring expression on their faces and they have muscular bodies. *See also* Bishamon-Ten; Jikoko-Ten; Komoku-Ten; Shi Tenno; Zocho-Ten.

www.ebook3000.com

Niobe (A) (Greek)
Niobe is the daughter of Tantalus and Dione and the sister of Pelops and Broteas. Her intense pride in her children was the cause of their destruction. Because she had seven sons and seven daughters, she boasted of her superiority to the goddess Leto who had only two children, her twins Apollo and Artemis. To punish her arrogance, Apollo killed all of Niobe's sons and her husband Amphion, and Artemis killed all her daughters. In other versions one son, Amyclas, and one daughter, Meliboea, were spared. Niobe wept until she was transformed into marble from which streamed incessant tears. Euripides and Apollodorus place the number of her children as fourteen, seven daughters and seven sons. Sappho said there were eighteen; Homer said twelve; Hesiod, twenty; and Herodotus wrote that she had only four children. *See also* Aedon; Amphion; Apollo; Argus (A); Artemis; Leto; Pelops; Satyrs; Tantalus (A); Zethus.

Niobe (B) (Greek)
First mortal woman to be loved by a deity. Niobe is the daughter of Phoroneus, the first king of Argos, and either Cerdo known as Cerdo the wise, Peitho, possibly the goddess of persuasion, or Teledice. Her siblings are Car, the king of Megara (his mother was likely Cerdo), and Apis, the ruler of Apia, who was killed by Telchis and Thelxion. Niobe and Zeus are the parents of Typhon, Pelasgus, Argus and Osiris. *See also* Apis (B); Car; Niobe (A).

Niord (Teutonic) *see* Aegir; Njord.

Niparaya (Pericu People, Native North American)
Supreme deity. Husband of Amayicoyondi and father of three sons, Quaayayp (man), Acaragui, and although the other is not named, he may be Wac or Tupuran. The children were likely virgin births as Niparaya did not have sexual relations with his wife and he does not have a visible body. The Pericu People had only a few deities associated with Niparaya. Cucumunic, who created the moon, and Puratabui, who created the stars.

Nipin and Pipoun (Algonquin, Montagnais People, North America)
Also known as: *Nipinoukhe and Pipounoukhe.*
They are the spirits of summer and winter who divide the world between themselves. Nipin brings the heat of summer and the beauty of the world, but when he changes places each year with Pipoun, then winter returns, and so returns the cold and bitterness of this season. Nipin might be the same as the god Niparaya of the Pericu People.

Nipinoukhe and Pipounoukhe *see* Nipin and Pipoun.

Nir-Jara (India) *see* Amrita.

Nirba (Akkadian)
He is a creator deity and a god of harvest.

Nireus (Greek)
The sea god Poseidon and Canace are his parents. *See also* Aloeus; Canace; Epopeus.

Nirgalu (Babylon) *see* Nergal.

Nirig (Babylon) *see* Ninib.

Nirrita (India) *see* Nirriti; Rakshasas.

Nirriti (Hindu, Vedic; India)
Nirriti, the daughter of Surabhi, the cow goddess and goddess of plenty, protects the weary, down-trodden, and those born into crime as long as they are ethical. She is presented as elderly, tired and emaciated. Dressed in black, her hand is always out to receive alms. Her name means "misery." In other depictions, she is the Vedic goddess of death and spouse of Nirrita, the guardian deity of the Southwest. She is the mother of the Rakshasis and Rakshasas. *See also* Kali; Lokapalas; Rakshasas; Surabhi.

Nirruti (India)
Mentioned in the *Rig-Veda*, the god Nirruti is depicted on a lion surrounded by Rakshasas and nymphs. *See also* Rakshasas.

Nirvana (India)
Heaven. A place of perfect rest. Some believe the name means death. *See also* Aaru; Amida; Elysian Fields.

Nisaba (A) (Sumer)
Goddess of architecture. Patron of letters. *See also* Nabu; Nina (B); Ninlil.

Nishatha (India) Son of Bala-Rama (q.v.).

Nisis *Nisus* (Greek)
Deified mortal. He is the king of Megara, whose lock of purple hair (on which his life and fortune depended) was snipped off by his daughter, Scylla, and presented to King Minos, with whom she had fallen deeply in love. Nisus was transformed into a sea eagle, and his daughter into a sea bird.

Nisroch (Assyrian)
Possibly a sky god. May be the same as Nisr-uku, an eagle-headed deity of the Assyrians. Possibly associated with Anu.

Nissyen (Celtic) *see* Bran.

Nistigri (India) *see* Indra.

Nisumbha (India) A Demon. *See also* Durga; Kali.

Nisus (Greek) *see* Nisis.

Nit (A) (Egypt) *see* Neith.

Nit (B) *Niti* (India) *see* Devaki.

Nitatui (India) A Krittika sister. *See also* Rishi.

Nithog (Teutonic) *see* Loki.

Nithogg (Teutonic) *see* Nidhod.

Niti (India) *see* Devaki.

Niti-ghosha (India) *see* Brihaspati.

Nitwatakawaca (India)
The indestructible demon. *See also* Arjuna.

Nitya-Kali (India) *see* Kali.

Niu (Egypt) *see* Amen (B).

Niu-T'ou (China) *see* Niu-y'ou.

Niu-Y'ou *Niu-t'ou* (Buddhist; China).

Also known as: *Gozu Tenno* (possibly Japan), *Horse-Face, Ox-Face, Ox-Head.*

He is one of the T'u-ti, gods of place. With his companion Ma-Mien, he is the assistant to the Yama kings and Ch'eng-Huang, the god of walls and ditches. Niu-Y'ou and Ma-Mien are the deities who retrieve the souls for the Yama Kings, although in some versions, it is the two Wu-ch'ang who pick up the souls. Niu-Y'ou may have been imported to Japan where he is known as Gozu Tenno. He is opposed by the Door Guards. *See also* Goganze-Myoo (Japan); Gozu Tenno (Japan); Ma-Mien; Yama Kings.

Nivlheim (Teutonic) *see* Nifl-heim.

Nixe (Teutonic) *see* Nixie.

Nixie *Necar, Necks, Nick, Nig, Nik, Nixe, Nixie, Nixy, Nokel,* (Teutonic)

Also known as: *Stromkarls.*

Lesser water divinities. The Nixie belong to a group of kind, loving male water spirits along with the Stromkarls and the Necks. The female water spirits are the Undine. The Undine, Necks, Nixie and Stromkarls sometimes leave the water to attend village dances. The only way they can be detected is by seeing the damp hem of their clothing. They are described with fish tails. They often sit by the water combing each other's long green or blonde hair or playing the harp and singing. The Undines also have green teeth. *See* Nugal.

Nixy (Teutonic) *see* Nixie.

Njord *Niord, Njorth* (Norse; Teutonic)

Also known as: *Nordur.*

Originally a Vanir, this giant is the god of riches, dispenser of wealth, and a fertility, harvest, fire, and weather god. When called upon by those at sea he assures good fortune. He brings on sunset by quenching the fires of day. When the war between the Vanir and the Aesir ended, and a treaty was being agreed upon, each race gave hostages to the other. Njord and his son Frey were given to the Aesirs. In exchange, the Aesirs gave Odin's brother Henir and the wise Mimir to the Vanir. Njord became one of the main gods of the Aesir. Njord met and married Skadi, the beautiful, giant daughter of Thiassi. In some accounts Skadi is the mother of Frey. In other accounts she is called the stepmother of Frey and Freyja. Njord's first spouse was the earth goddess Nerthus who may also be his sister. Njord, the personification of summer, loved his home, Noatun, which is near the sea. His spouse Skadi, who personifies winter, preferred the mountains. She tried to live with him part of the time. It did not work out, so she left him to return to the mountains. One of the strange tales of Njord was that he was Saturnus, the father of Jupiter, Neptunus, and Plutus. Jupiter wasn't satisfied with the gift of heaven from the god Saturnus and made war on him. Saturnus hid in Italy and changed his name to Njord. Njord is depicted as a handsome man dressed in a short green tunic. Sometimes he wears a crown of seaweed and shells. He is also shown wearing a brown brimmed hat decorated with eagle or heron feathers. *See also* Aesir; Balder; Freyja; Jord; Nerthus; Skadi; Vanir.

Njorth (Teutonic) *see* Njord.

Nkosi Yama'kosi (Ndebele People, Zimbabwe, Africa)

Supreme being. This name applies to both a god and to leading mortals.

Nkulnkulu (Africa) *see* Unkulunkulu.

No-no-kami (Japan) *see* Kaya-no-hime-no-kami.

Noah (Hebrew)

Hero. Survivor of the deluge. According to legend, he was the second founder of the human race and his original name was Menachem. He was saved from a great flood by building an ark of gopher wood and sheltering his family and a pair of every living thing. Some versions say they lived in the ark for forty days and nights and other versions say the flood lasted a year. *See also* Abram; Cessair.

Noatun (Norse; Teutonic) Dwelling place of Njord in Asgard.

Nodens (Celtic) *see* Llud.

Nodotus (Roman) Roman god of knots in the straw.

Noesarnak (Eskimo People)

One must carefully approach Noesarnak, the land spirit. She is depicted as a woman with spindly legs who is dressed in deer skins and carries a deer skin mask.

Nogamain *Nogomain* (Aborigine People, Australia)

Creator. He is described the same as Djamar, but he, like Atnatu, made himself out of nothing. He doesn't have any family according to some. According to others, he has a wife and son, who is described as a hunting spear. Nogamain is sometimes called the man in the moon. He was possibly replaced by Kunmanggur and Kukpi by other tribes. *See also* Djamar.

Nogat (Mongol) *see* Natagai.

Nogomain (Australia) *see* Nogamain.

Nohochacyum (Maya People, Yucatan)

Also known as: *Kasin, Nahochacyumchac, Nukuchyumchakob.*

"Grandfather." God of creation. Opponent of the evil god Hapikern. He is the son of two flowers and brother of the gods Yantho, meaning "good"; Usukun, meaning "bad"; and Uyitzin, meaning "neutral." They are associated with Xamaniqinqu, "the spirit of the north," and Kisin, "the earthquake." Nohochacyum is a single great father and chief god. His servants are the spirits of the east, ruled by Usukun, thunder, and the constellations. At the end of the world he will wrap the serpent Hapikern around his body who will draw people to him to be killed. *See also* Usukun; Xamaniqinqu; Yumchakob.

Nokel (Saxon) *see* Nixie (Teutonic).

Noken (Teutonic) *see* Nugal.

Nokomis (Algonquian People, North America)

Also known as: *Ethinoha, Grandmother* (Iroquois), *Wenonah.*

Earth Mother or Earth Goddess. Her daughter is the corn spirit, Onatah. She is the grandmother of Nanabozho. In one legend, Nokomis fell to earth and became Wenonah, the wife of Hiawatha. *See also* Mondamin; Nanabozho.

Nommo (Dogon People, Sudan, Africa)

Also known as: *Nummo.*

www.ebook3000.com



Fig. 3.11 *Second Brain*

Twin gods. The supreme god, Amma, fertilized earth with rain and produced the twins, Nommo, a male and female. They are heavenly blacksmiths, who created copper. The first fire was stolen from them. They are generally thought of as water or spirits of water. *See also* Amma (A); Yuragu.

Nomus (Greek) *see* Aristaeus.

Noncomala (Central America)
Supreme deity. In this story Noncomala was angry at the local province of Guaymi so he flooded it. Nubu, another local god, held on to the seed of man, which he expelled during his dreams. Once his anger abated, he planted the seeds. From the good seeds came man and woman and from the bad seeds came monkeys. *See also* Nubu.

Nona (Tahiti)
Also known as: *Haumea* (Hawaii)
Ancestor of the Tafa'i People. She is comparable to Haumea, the Hawaiian goddess of childbirth and cultivated plants. *See also* Haumea.

Nono *Nona* (Greek) She is one of the three Fates (q.v.).

Nootaikok (Eskimo)
He is the spirit of icebergs and possibly a god of seals.

Nor (Teutonic) *see* Aarvak; Nordri; Norvi.

Nordi (Teutonic) *see* Aarvak; Austri.

Nordre (Teutonic) *see* Nordri.

Nordri *Nordre* (Norse; Teutonic)
He is one of four dwarfs who support the heavenly vault (made from the skull of Ymir) on their shoulders. The others are Sudri, Austri, and Westri. From their names came the North, South, East and West.

Nordur (Teutonic) *see* Njord.

Norea (Coptic)
One of the first mortals, she is the sister of Seth and wife of Noah.

Norine (Teutonic) *see* Neri.

Norn (Teutonic) *see* Norns.

Nornir (Teutonic) *see* Norns.

Norns (Norse; Teutonic)
Also known as: *Nornir.*
Goddesses of destiny. There are a number of Norns both good and evil. The three prominent goddesses are Urd (fate), Skuld (personification of the future), and Verdandi (necessity). They reside under and care for Yggdrasil, the tree of life, near Urd's well. The Norns control the unchanging universal laws and the fate of mortals and the Aesirs. Urd and Verdandi were beneficial, but Skuld was said to undo the good work of the other two. The Norns didn't appear until the end of the Golden Age. Their main purpose was to weave the web of fate. The Norns dress themselves in swan plumage from the two swans they care for in the waters from Urd's Well. Compare the Norns to the Fates. *See also* Aesir; Fylgia; Urd's Well; Yggdrasil.

Norse — Creation Legend *see* Ginnunga-gap.

North Wind (Greek) *see* Boreas; Chaos; Eurynome (A).

Norve (Teutonic) *see* Norvi.

Norvi (Norse; Teutonic)
Also known as: *Narvi, Nor, Norve.*
Norvi is the giant father of Nott (Night) and the ancestor of the Norns. *See also* Norns; Nox.

Notos *Notus* (Greek)
Also known as: *Auster, South West Wind.*
He is the son of Astraeus and Eos. *See also* Astraeus; Boreas; Eos; Notus.

Nott (Norse; Teutonic)
Also known as: *Nacht, Nat.*
Nott, the goddess of night, is the daughter of the giant Norvi (or some say Mimer) and sister of Dagr (day). She rides in a dark chariot drawn by the sable horse, Hrim-faxi. The mane of the horse drips dew and hoarfrost onto the earth below. She has been married three times. Her first husband was Naglfari, with whom she had a son, Aud. Her second husband was Annar, with whom she had a daughter, Jord, and her third husband was Dellinger (Delling), by whom she had a son, Dag. *See also* Aarvak; Dag; Nat (B); Night.

Notus Notos (Greek)
Also known as: *Auster, South West Wind.*
God of wind. Notus, the son of the Astraeus (the starry sky) and Eos the goddess of dawn, is called the South West Wind. He is the dispenser of rain and of sudden and heavy showers. His siblings are Boreas (North Wind), Zephyrus (West Wind) and Eurus (South East Wind). Notus is generally shown as an old grey haired man with a gloomy face. His head is covered with clouds, he has dark wings and wears sable. Compare Notus to Fu-jin (Japan). *See also* Boreas; Chimaera; Eos; Zephyrus.

Nous (Valentinus sect, Post-Christian Gnostics)
Also known as: *Monogenes.*
First deity. Nous (possibly with mate, Sige) was the first perfect being who came from the Unknowable Father. Because he was too great to act directly, he and his partner Aletheia produced the perfect number of offspring: Logos and Zoe and their children, Bythios, Mixis, Ageratos, Henosis, Autophyes, Hedone, Akinetos, Synerasis, Monogenes, and Macaria who acted in his place. Logos and Zoe, in turn, produced another set that consisted of an imperfect number of aeons: Anthropos and Ecclesia, Paracletos and Pistis, Patricos and Elpis, Metricos and Agape, Ecclesiasticus and Macariotes, Theletas and Sophia. The offspring acted on matter in place of Nous. *See also* Dionysus.

Nox (Greek)
Also known as: *Nyx.*
Nox, the goddess of night, is pictured as a "Great Black Bird," the Greek personification of Night, who was born out of the primordial Chaos. From her egg came Eros and from her shell Oranos and Gaia (Heaven and Earth), who are called the parents of the Titans. In another myth, she is the daughter of Chaos and the wife of her brother Erebus. She became the mother of Thanatos (Death), Moros (Destiny), Hypnos also known as

Somnus (god of sleep), Momus the fault finder, Nemesis (goddess of retributive justice), Aether (Sky) and Hemera (Day), Oneiroi (Dreams), Cer (goddess of violent death), Charon (ferryman of the dead) and possibly Hesperides and Old Age. She has also been identified as the mother of Fraus (divinity of treachery) by Orcus (Pluto). She is represented as winged, or sitting on a chariot, clothed in black, surrounded by stars. For the development of creation on earth at this time, *see* Cronus. Compare Nox to the Vedic goddess of the night, Ratri. *See also* Aether; Aither; Erebus; Fates; Furies; Keres; Nemesis.

Nu (Egypt)

Water deity. This god and his counterpart goddess, Nut, were water deities and the most ancient gods of the Egyptians. They are part of a company of gods, usually four pairs called Paut. *See also* Hehu; Hehut; Kekui; Kekuit; Kerh; Kerhet. Others say the eight gods were Ament, Nu, Nut, Hehui, Hehet, Kekui, Keket, and Hathor. As mentioned in the "Papyrus of Nesi-Khensu," Nu appears to be a deity of time or possibly a god of potters. He is also mentioned in relationship with Khensu. In the Chinese mythology the name is associated with Chih Nu. Nu is the counterpart of the goddess Nut. He is associated with Amen. Sometimes, he is identified with Hapi. *See also* Aai.

Nu-Kua *Nu Kua* (China)

Also known as: *Nu Wa Naing Naing.*

Creator of the human race. Nu-kua is the wife and sister of the renowned sage Fu-hsi and mother of the ten spirits. Her recipe for creating mortals began with yellow mud. She dipped a rope into the mud and then trailed the rope around; the drops that dripped from the rope became men and women. In another rendition, like many other creators she fashioned mortals from lumps of clay. When evil giants set fire and flame loose upon the world, Nu-Kua restored everything by replacing the overturned poles of the world with the feet of a giant turtle which repaired the widespread damage that came after the catastrophic flood and fire. She also melted stones of five colors to repair a rip in the sky. In some versions her name has two parts. Nu was the brother and Kua the sister, and they were the first human pair. She is shown as a woman from the waist up, and a dragon's tail below. She holds a pair of compasses. *See also* Fu-hsi; Kun-Lun Mountain.

Nu Wa Naing Naing (China) *see* Nu-Kua.

Nu-Zuchi (Japan) *see* Kaya-no-hime-no-kami.

Nuada *Nuadhu* (Celtic)

Also known as: *Argetlam* ("the Silver Handed"), *Llud, Llud Llaw Ereint, Lud, Nuada Argentlam, Nuadha Airgedlamh, Nud Nodens.*

Nuada is the chief of the Tuatha de Danann who lost his hand or arm in battle. The hand or arm was replaced by one of silver created the smith and healer, Dia'necht. Compare Nuada to the British Llud, the Vedic and Hindu deity Savitri, and to the Norse deity Odin. *See also* Airmid; Bress; Credne; Dagda; Dia'necht; Llud; Lugh; Tuatha De Danann.

Nuada Argentlam (Celtic) *see* Nuada.

Nuadha Airgedlamh (Celtic) *see* Nuada.

Nuadhu (Celtic) *see* Nuada.

Nuba (Sudan)

Sky god. Nuba sent the god Su to earth down a bamboo-shoot with some peas. Su dropped some on the way which struck the drum he was supposed to have beaten for Nuba to bring him up. Nuba pulled up the bamboo, causing Su to fall and break his leg. *See also* Wantu Su.

Nubti (Egypt)

Also known as: *Set.*

Epithet of Set. Known as the "Golden One," he shoots his arrows at the noon-day sun.

Nud (Celtic) *see* Llud; Nuada.

Nud Nodens (Celtic) *see* Nuada.

Nudd (Celtic) *see* Llud.

Nudimmud *Nadimmud* (Babylon)

Also known as: *Ea, Enki.*

Creator. Nudimmud, as Ea, created the Apsu-Ocean, and some say, the other gods. He is the son of Anu and one of a triad with Anshar and Kishar. *See also* Apsu.

Nuga (Melanesia)

Creator. A great crocodile, Nuga created rivers by the lashing of his tail. He is associated with the creator Ipila (q.v.).

Nugal (Teutonic)

Also known as: *Noken.*

Deified animal. Nugal is a dapple-grey horse or a brown ass. He uses his fiery tail to lead people astray. Nugal is often associated with the Nixies. *See also* Nixie.

Nuit (Egypt) *see* Amunet.

Nujalik (Eskimo)

Goddess of the land-hunt.

Nuktelios (Greek) *see* Dionysus.

Nukuchyumchakob (Maya) *see* Nohochacyum; Yumchakob.

Nuliajuk (Netsilik Eskimo People)

She is the mistress of land and sea and the mother of animals. Her power gives her the ability to cause storms and to make animals visible or invisible. She rules through spirits. One spirit is responsible for recording the violations of taboos. When she was a young human female, she was grossly abused. Once while on the sea, her knuckle joints were cut off one by one. They fell to the bottom and became sea animals. She sank to the bottom and became the mother of the sea animals. There are numerous variations of this myth. Nuliajuk is comparable to Sedna (q.v.).

Num (Samoyd)

Also known as: *Ec* (Yenisei), *Num-torem, Numi-torem, Torum* (Ugrain).

Supreme god. The Vogul people say he lives in the seventh heaven which contains the water of life. The sun and moon are his eyes. In some myths, he is a thunder or sky god. *See also* Ec;

Numbakulla (Aborigine People, Australia)

First deity (both plural and singular). Born out of nothing

www.ebook3000.com

or always existing. He, or as some say, these two created everything. After inserting a pole into the earth, Numbakulla climbed it and left the planet forever. In some renditions, Numbakulla created humans from amorphous creatures from Inapatua (q.v.).

Nummo (Africa) *see* Nommo.

Numokh Mukana (Mandan) The First Man.

Numphe (Greek) *see* Nymphs.

Nun (Egypt) *see* Atum; Khepri; Nu; Ptah; Ptah.

Nun and Naunet (Nunet) Egypt. *See also* Nun.

Nunam-shua (Eskimo People, Pacific Region)
She is the owner of all the land animals, and mistress of land and mountain forests. She wears a coat made of the furs of all animals and beams with radiant light. *See also* Sedna.

Nunbarshegunu (Assyro-Babylonian) *see* Ninlil.

Nund (India) *see* Nanda.

Nunet (Naunet) (Egypt) *see* Nun.

Nunu (Egypt) *see* Khepri; Nun; Thoth.

Nunyunuwi (Cherokee People, North America)
His name means "dressed in stone." He is a destructive cannibal spirit.

Nurelli (Aborgine People, Australia)
High god. According to myth this deity created all things. Once he completed the task he gave men laws then returned to the sky. His story is related to Bunjil's story.

Nurra (Assyro-Babylonia) *see* Ea.

Nurrundere *Nurundere, Nurunderi* (Aborigine People, Australia)
Also known as: *Baiame, Bunjil, Daramulun, Martummere, Ngurunderi, Pun-gel.*
Creator gods. Some say it was Nurelli who created everything. Others say Bunjil, Daramulun, or Mungan-ngaua were the supreme creators. In one version, Nurrundere is a culture hero who taught crafts and skills. In most versions of his myths, Nurrundere left for Wyrra-warre, the sky.

Nurunderi (Australia) *see* Martummere; Nurrundere.

Nusku (Assyro-Babylonian, Sumer)
A messenger of the gods, Nusku is also the god of fire, light, and civilization. He is referred to variously as the first born of Enlil, the moon god Sin, or Anu. He was known to have burned sacrificial offerings to the gods. Nusku is the minister and vizier of Enlil, and he sometimes acted as a god of justice. His symbol is the lamp. He is equated with Nabu and Gabil (qq.v.). *See also* Anu; Enlil; Nabu; Sin.

Nusmatlizaix (Bella-Coola People, North America)
Deified bird. When the world was first populated, the rivers and people were imprisoned in the cave called Nusmatlizaix. A huge rock barred the entrance. The Eagle was unable to break in, but the Raven succeeded and freed the human race.

Nut (Egypt)
Goddess of the sky. Nut is one of the Ennead, a group of eight deities. She is the child of Shu, dryness, and Tefnut, water. Her male counterpart or husband is Nu. She is the mother, by her brother, Geb, of Osiris, Isis, Seth and Nephthys. It was Nut, in the form of a cow, who called Ra to the heavens where Nut became the support of the sky. In the *Book of the Dead*, there is a reference that Nut is the mother and Seth the father of Osiris. Nut was caught being unfaithful by her husband. He cursed her so that she could only give birth on the days which were not on the calendar. Nut sought counsel from Thoth. In a board game with the moon god, Thoth won a part of each day which amounted to five days during which Nut could give birth. This was the mythical origin of the five additional days which the Egyptians annually inserted at the end of every year in order to establish harmony between lunar and standard time. During these five days Orsiris was born on the first, the elder Horus on the second, Set (Typhon) on the third, Isis on the fourth and Nephthys on the fifth day. According to Heliopolitan theology Nut was the mistress of the heavenly bodies which were said to be all her children who entered her mouth and emerged from her womb. She was called "the female pig who eats her piglets." It is said that as the mother of the sun-god Re, she swallowed him in the evening and gave birth again in the morning. She is represented bearing a vase on her head, and is usually depicted with her hands and feet planted on the earth and her body arching up to form the vault of heaven. She is sometimes shown with the head of a uraeus topped with a disk, and with the head of a cat. Nut is also shown as a woman bearing a vase of water on her head. She is also represented as a suckling sow. The sycamore tree was a manifestation of Nut. The leaves shielded the dead Osiris and the branches were said to have restored his soul. She was comparable to the Greek god Rhea. She was also comparable to Hathor in that both were cow-goddesses. She has been identified with Hathor, Mut, Nit and Neith. The Greeks compared Nut and Seb to Cronus and Rhea. She is mentioned as a form of the goddess Neheb-Kau and counterpart of the serpent god Nau. *See also* Aai; Ament; Amentet; Amun; Atum; Ennead (the); Hathor; Isis; Nephtys; Osiris; Ra; Sopdu; Thoth.

Nutapa (South America) *see* Dyai.

Nutar (Egypt) *see* Neter.

Nu'umea (Polynesia)
Heaven. Goddess of uncultivated plants. As a goddess, she is the wife of Wakea. She was killed when Kaulu tossed her into the net of Maoleha. Nu'umea is associated with the trickster Kaulu. *See also* Haumea; Wakea.

Nux (Greek) *see* Nix; Nox.

Nuzuchi (Japan) *see* Kaya-no-hime-no-kami.

Nyalic (Africa) *see* Nyalitch.

Nyalitch (Dinka People, Africa)
Also known as: *Nyalic.*
Supreme god. Lord of spirits. God of sky and rain. See also Abuk.

Nyambe (Nigeria, Africa)
Also known as: *Bumba, Nyambi.*

Nyambe is the sun as a supreme deity. He punishes those who try to climb up and kill him. Once, when Nyambi lived among mortals, he gave them a magic tree which would give them immortality. The mortals treated Nyambe with disrespect. He pulled up the tree and disappeared. In a tale from Zambezi, Nyambe is the spouse of Nasilele, who appears to be a moon goddess. Nyambe is used as a name for the Supreme Being in the western tropics of Africa. It may be the same as Nyame. *See also* Bumba.

Nyambi (Africa) *see* Nyambe.

Nyame *Nyami* (Ashanti, Twi People, Africa)
Also known as: *Kaka-Guia, Nyame and Asase, Onyame.*
Androgynous Creator. Funerary deity. Possibly a storm god or goddess. Father and mother god. As a goddess, she is Nyame or Nana or Nyankoipon (Ashanti, Africa). Her husband is Asase Yaa, god of rain, wind, sun, moon, night and sleep. Nyame's female name-day is Thursday. To open a new field or to dig a grave one must have her permission. As Kaka-Guia he was considered a male deity and a funerary god who brought souls to the supreme deity. In the Mande version Nyame is the vital force and is associated with Pemba and Faro. Sometimes Nyame is personified as the moon. Nyame is similar to or the same as Nyankopong. *See also* Abonsam; Asase Yaa; Nyambe.

Nyame and Asase (Africa) *see* Nyame.

Nyamia (Africa) *see* Nyamia Ama.

Nyamia Ama (Senegal, Africa)
Also known as: *Nyamia.*
Storm deity. Nyamia Ama, often called an invisible sky god, controls storms, rain and lightning. He is said to be a white child with large ears. Nyamia Ama is associated with Evua (the sun), Kaka-Guia (god of the soul) and Guruhi (god of evil). *See also* Nyame.

Nyankopon (Africa) *see* Nyankopong.

Nyankopon Kweku (Africa) *see* Nyankopong.

Nyankopong (Ashanti People, Africa)
Also known as: *Nyankopon, Nyankopon Kweku, Onyankopon, Onyankopong.*
Nyankopong once lived on earth, but moved to the sky because an old woman kept hitting him with her pestle as she pounded grain. Similar to Nyame, he may be her forerunner. *See also* Nyame.

Nyasaye (Maragoli People, Kenya, Africa)
He is the chief of spirits and is generally shown as a pole surrounded by a pile of stones.

Nyceteus (Greek)
Nyceteus is the son of the sea god, Poseidon, and Celaeno. He is also referred to as the son of Chtonius or Hyrieus and Clonia. When he found that his daughter Antiope was pregnant by Zeus, he committed suicide. *See also* Antiope.

Nyctimene (Greek)
Raped by her father, Epopeus, the king of Lesbos, she was subsequently changed into an owl by Athene.

Nyikang (Shilluck People, Africa)
Deified ancestor. God of agriculture. God of rain. He instituted the tradition of marriage between siblings, and ritual murder. Ancestor god of the Shilluck, who is the intermediary between the people and Juck. Nyikang is believed to be either the father of Omara (the first man) or the descendant of the first cow, or crocodile. He created his subjects by changing wild animals to people, or he fished men out of the water, or brought them out of a calabash. Although he dies by strangling himself or disappears in a whirlwind, he always returns. He must, or the Shilluck people will all die. *See also* Juck.

Nyktelios (Greek) *see* Dionysus.

Nymphs *Numphe*
Also known as: *Aegle* (the name of more than one nymph); (Greek)
Spirits. Nymphs are attractive female divinities who inhabit certain objects or places in nature. The Oceanids and Nereids are the sea nymphs: Naiads are fresh-water nymphs of fountains and lakes; Dryads and Hamadryads are tree nymphs; and the Oreades are mountain nymphs. The worship of nymphs was extensive and their places of worship were usually situated near springs, woods or caves. There are also dangerous water nymphs, known as Bisimbi, in the Congo (Africa). They live at the mouths of rivers, and in wells or ponds and are thought to be spirits of the dead. These nymphs are made of water and can only be seen at dawn rising like wisps of dew. Nymphs represent different aspects of nature. They are usually depicted as young, beautiful, often naked and promiscuous. *See also* Aegle; Dryads; Naiads; Napaeae; Nereids; Oceanids.

Nyokon (Cameroon People, Africa)
Supreme god. His first son, Nyiko, the spider of divination, became the lover of his mother, Mfam. Nyokon drove him away. Nyiko still holds the secrets of divination of his father.

Nyx (Greek) *see* Nox.

Nzambi (Bantu People, Africa)
Also known as: *Mpungu, Nzambi, Nzame.*
Androgynous creator deity. Supreme god, and invisible god of creation. He created the first man, Fam, who became vain, so Nzambi buried him in a hole, but Fam still caused mankind misfortune. Nzambi then created a second man, Sekume. Sekume created a wife from a tree (Mbongwe) and they became the ancestors of the human race. Nzambi came down to earth and fell in love with Mboya, a mortal girl, and had a son, Bingo, who has a legend of his own. As Nzambi Mpungu this deity is a goddess who had several other legends. *See also* Bingo; Bumba; Nzame.

Nzambi Mpungu (Africa) *see* Nzambi.

Nzame (Fon People, Africa)
Also known as: *Nzambi.*
High god. Nzame has many wives and three sons, Whiteman, Blackman, and Gorilla. He is probably the same as Nzambi although the legends differ. *See also* Nzambi.

Nzamgi (Bakongo People, Lower Congo, Africa)
He is the supreme god, creator of all things. Inaccessible, he is not worshiped. Nzamgi intervenes in the creation of every child. Those who violate his laws are punished.

www.ebook3000.com

O

O-kuni-Nushi (Japan) *see* Okuni-nushino-Mikoto.

O-mi-t'o Fo (China) *see* Amida.

O-pa-me (Tibet) *see* Amida.

O-sung (Tibet) *see* Kasyapa (B).

O-Wata-Tsu-Mi *Oho-Wata-Tsu-Mi, O-Wata-Tsumi* (Shinto; Japan)

Also known as: *Shio-zuchi* (Old Man of the Tide).

God of the sea. Ruler of all sea creatures. When Izanagi stepped into the great sea to cleanse himself of the pollutants of Yomi (hell), numerous sea deities were created. Among them are O-Wata-Tsu-Mi, the ruler of fish and all sea creatures; Shima-Tsu-Hiko, god of the wind; Kuko-no-shi, god of the trees; and Oho-yama-tsu-mi, god of the mountains. O-Wata-Tsu-Mi is considered the most important god of the group. Another sea god is Shiho-tsuchi. O-Wata-Tsu-Mi lives in a palace with his family on the sea floor. The palace has a great gateway flanked by towers of coral. The curved, sloping roof is made of lapis lazuli tiles. A huge cassia tree with fanning branches grows in front of one of the towers. The interior exudes wealth. Inside, there are rugs of sealskin and silk. Delicacies from the eight corners of the sea are served at meals. O-Wata-Tsu-Mi has two messengers, a monster shark and a crocodile. Hikohohodemi, the son of Ninigi, once stayed with O-Wata-Tsu-Mi for three years while looking for his brother's fishhook. He married the sea god's daughter Toya-Tama-bime and O-Wata-Tsu-Mi gave him two jewels of the tides known as Kangi (Tide Ebbing Jewel) and Mangi (Tide Flowing Jewel). With the advent of Ryobu-Shinto, a new sea god was created, named Sui-tengo, who is associated with the Hindu god Varuna. Sui-tengo is the protector of sailors and sick children. Sui-tengo is depicted in the shape of a woman holding a child in her arms. The woman represents Nii-no-ama and her grandson, the infant Emperor Antoku. Antoku and his nurse drowned in Dan Bay near Shimonoseki in the year 1185. O-Wata-Tsu-Mi and Toya-Tama-bime are depicted as a combination of human and dragon form. *See also* Haya-akitsu-hime-no-kami; Hikohohodemi; Hosuseri; Izanagi and Izanami; Toyo-Tama-Bime; Yomi.

O-Wata-Tsumi (Japan) *see* O-Wata-Tsu-Mi.

O-Yama-Tsu-Mi (Japan)

Chief god and lord of the mountains. He is appealed to before trees are cut down, particularly trees used to construct temples. He is the brother of the fire god, Kagu-tscuhi. His wife is Kaya-no-hime-no-kami (Ruler of the Grassy Plains). One of their daughters, Kono-Hana-Sakuya-Hime (Blossoms-of-the-Trees-Blooming-Princess) is the wife of Ninigi and the mother of Hoderi. *See also* Hoderi; Ninigi; Sengen.

O-zer-chem-ma (Tibet) *see* Marichi (A).

Oado (Persia) Kushana wind god.

Oak of Mughna (Celtic) *see* Abellio.

Oak of Two Greens (Celtic) *see* Dagda.

Oannes *Onnes, On* (Babylonian, Chaldean, Sumerian, Greek)

Also known as: *Aos, Dagon, Ea* (Semitic).

Earth deity. Oannes is the Greek name for Ea, the god of wisdom, who taught agriculture, irrigation and shipbuilding to the Babylonians. In Sumerian myth, Oannes came from the sea to bestow knowledge of the arts, sciences, and culture upon the people. At the end of each day, he returned to the sea. He is depicted as half-fish, half-man monster, or goat. In Syrian myth, his mate is the sea goddess Ataryatis Derketo (also known as Atargatis), and he is the father of Semiramis, who became the Queen of Babylon. *See also* Aa; Aeacus; Aos; Atargatis; Ea; Poseidon; Semiramis.

Oarion (Greek) *see* Orion.

Oath (Teutonic) *see* Var.

Oba (A) (Yoruba People, Africa)

River goddess. Goddess of wisdom and culture. Oba is Shango's favorite of his three wives. He won her from his brother, Ogun. An excellent cook, she followed her sister Oschun's advice and cut off her own ear and put in the soup she was cooking for him, in order to assure herself of her husband's affection. When he found the flesh, he became angry and sent her away. She became the river Niger. *See also* Ogun; Olodumare; Shango.

Oba (B) (Africa)

He is the traditional king of the Edo People.

Oba-Orun (Yoruba People, Africa) *see* Olodumare.

Obagat (Pelew Islands)

Creator deity. Wanted to give mankind immortality, but Rail gave them disease and death instead. Possibly the same as Lukeland (q.v.).

Obasi Nsi (West Africa) *see* Isong.

Obassi (Africa) *see* Obassi Osaw.

Obassi Osaw *Obassi* (Hausa People of the Niger, Africa)

Creator diety or high god. He gave mortals everything but fire which had been stolen by a boy.

Obastet (Egypt) *see* Bast.

Obatala (Yoruba People, Africa)

Also known as: *Orish-nla, Orish-oko, Orisha-ijaye, Orisha-ogiyan, Orisha-popo.*

First creation of the supreme being, Olodumare. His original name was Orish-nla. Sky god or earth deity. God of peace and order, representative of purity and law. Protector of town entrances. He is known as the sculptor god because he shapes babies while in they are in the womb. He makes barren women fertile. Obatala is asked by other deities to intervene on their behalf to Olodumare. His lineage varies; he is the son of Olodumare (who is also known as Olorun), the supreme being, and Olokun, the sea. His brother is Oduduwa. Or, he is the son of Oduduwa and brother/husband of Yemoja. Or, he is the father of Aganju and Yemoja who gave birth to Orungan who impregnated his mother. His mother gave birth to Dada, Schango, Ogun, Ochossi and Schankpannan. Obatala is the god of the north. Sometimes he is known as the master of the sky. We are also told that he was sent down to the waters by Olodumare to fashion earth. He drank some palm wine and was unable to finish his task. His replacement was Oduduwa. Obatala, who loves cleanliness, is depicted as an elderly man with white hair, dressed in white robes, in white surroundings. Sometimes he is accompanied by his spouse, Yemoja. For the Yoruba creation myths, *see* Oduduwa, Orish-nla and Olodumare. *See also* Aganju; Ogun; Shango; Yemoja.

Obe (Africa) *see* Obi.

Obeah (Africa) *see* Obi.

Oberon (Anglo-Franco) *see* Alfheim.

Obi (Africa; West Indies)
Also known as: *Obe, Obeah.*

Obi is a form of witchcraft which is often used for antisocial behavior. However, in the hands of the proper person, it can be a powerful source of good.

Obosom (Africa) see Abosam.

Obriareus (Greek)

He is one of the Hecatonchires. Known to mortals as Aegaeon and to the gods as Obriareus, he is also known as Briareus. *See also* Aegaeon; Hecatonchires.

Obsidian Butterfly (Aztec) *see* Itzpapalotl.

Obtala (Yoruba People, Africa) *see* Orish-nla; Shango.

Ocaleia (Greek)

Ocaleia is the wife of Abas and the mother of the twins Acrisius and Protetus. *See also* Abas; Acrisius; Proetus.

Ocean (Greek) *see* Oceanus.

Oceanic — Creation Legend *see* Areop-Enap; Lukelong; Lumimu-Ut; Nareau; Riiki.

Oceanides (Greek) *see* Oceanids.

Oceanids *Oceanides* (Greek)

Nymphs. Guardians of youth. The Oceanids are the children of Oceanus and Tethys. They have three thousand sons known as the Rivers and three thousand daughters known as the Oceanids. Not all lived in the sea. Some had the gift of prophecy and others were shape changers. The eldest daughter, Styx, is the only offspring who is a river deity. Metis is a goddess of wisdom and prudence. Europa and Asia became land masses, and Calypso is an island nymph. Doris became the mother of fifty daughters, nymphs known as the Nereids. Eidyia (Idyia) married Aeetes, king of Colchis. Electra with Thaumas became parents of the Harpies and Iris. Callirrhoe and Medusa's son Chrysaor became the parents of a three-headed creature named Geryon. Perseis (Perse) became the mother of Circe, Pasiphae, Aeetes and possibly Perses. Clymene became the mother of Menoetius, Prometheus, Epimetheus and Atlas, according to Hesiod. Ovid called her the mother of Phaethon by Helius, though she was married to the king of Egypt, Merops. The Heliades are her children. To compare to other water deities, *see* Achelous; Naiads; Nereids; Rivers; Sirens; Styx. *See also* Achelous; Alpheus; Asopus; Cephissus; Chrysaor; Clytia; Cocytus; Europa; Harpies; Heliades; Inachus; Nymphs; Oceanus; Titans.

Oceanus *Okeanos* (Greek)
Also known as: *Ocean.*

A Titan and a sea deity. Oceanus is the lord of Ocean, the unending river that encircles the world, including the rivers of Hades. He is one of the Titans, son of Uranus and Gaea, brother of Cronus, and the brother and husband of Tethys. He is the god of all waters, including those of the underworld and a contributor to the formation of the universe. He is the father of three thousand river gods, known as Rivers, and three thousand water nymphs, known as Oceanids, as well as various other children. Oceanus is sometimes referred to as the father of Triptolemus, the prince of Eleusis. He may be the father of Acmon and Passalus by Theia. Oceanus and Gaea are also the parents of Crius, Eurybia, Nereus, Phorcys and Thaumas. He is also said to be the father of Thetis, Eurynome and Perse. Either Oceanus, Apollo or Perses is the father of Cariclo, the wife of Cheiron. Oceanus and Tethys raised their sister Rhea's daughter Hera. In old age, Oceanus' tide came in with the advent of the Olympians reign and he was replaced by Poseidon. In the Pelasgian creation myth, Oceanus and Tethys were the rulers of the planet Venus. (*See* Eurynome.) Oceanus is depicted reclining with an oar and sea animals. *See* Oceanids and Rivers for additonal names of his children. Compare Oceanus to the Assyro-Babylonian, Apsu. *See also* Achelous; Aeetes; Alpheus; Amphitrite; Apsyrtus; Asopus; Cephissus; Ceto; Chaos; Clytia; Cocytus; Cronus; Eurynome (A); Gaea; Inachus; Meliae; Naiads; Nemesis; Nereids; Nereus; Pontus; Poseidon; Rhea; Styx; Themis.

Ocelotonatiuh (Mexico) *see* Legend of the Four Suns.

Ocepta *Ocypete* (Greek) She is one of the Harpies (q.v.).

Ochimus (Greek)

He is one of the Heliades and the father of Cydippe. *See also* Heliades.

Ochren (Celtic) *see* Achren.

Ochun (Africa) see Oschun.

Ocirvani and Tsagan-Sukuty (Mongol)

Ocirvani and Tsagan-Sukuty descended from heaven to the Primordial Ocean. Tsagan-Sukuty was asked by Ocirvani to dive to the depths and return with mud. They spread the mud over a turtle and fell asleep. Sulmus, the deity of evil, tried to drown the two gods, but everytime he rolled over them the earth expanded.

www.ebook3000.com

Ockabewis (Chippewa People, North America)
Messenger of the gods. Teacher of mankind.

Ocleia (Greek) *see* Aglaia.

Ocrisia (Greek)
She was a Roman slave who was the mistress of Hephaistos (q.v.).

Octli (Aztec People, Mexico)
Also known as: *Centzontotochtin.*
Gods of intoxicating drink. A general name for pulque deities. *See also* Centzon Totochtin; Colhuatzincatl; Ometochtli; Patecatl; Texcatzoncatl.

Ocypete (Greek) She is one of the Harpies (q.v.).

Od (Norse; Teutonic)
Also known as: *Oder, Odin, Odnir, Odur, Othur, Svipdag.*
Some say Od is Freyja's lost husband, while others say it is another name for Odin. *See also* Freyja.

Od-Dpag-Med (Tibet) *see* Amitabha.

Od-Hroerir (Teutonic) *see* Odraerir.

Oddua (Africa) *see* Oduduwa.

Odem (Hebrew) *see* Adam.

Oder (Teutonic) *see* Od or Odin.

Odherir (Teutonic) *see* Odraerir.

Odhinn (Teutonic) *see* Odin.

Odhroerir (Teutonic) *see* Odraerir.

Odin *Odhinn, Othin, Othinn, Othinus, Ouvin, Votan, Votan, Wodan, Wode, Wodemus, Woden, Wodhen, Wodin, Wotam, Woutan, Wuotan* (Norse; Teutonic)
Also known as: *Allfather, Baleyg* ("One with Flaming Eyes"), *Biblindi, Bileyg* ("One with Evasive Eyes"), *Bilflindi, Bolverk* ("Evil- Doer"), *Bolverkin, Breit-Hut, (*"Chooser of the Slain"), *Farma-Tyr, Fjolnir, Gagnrad* ("He Who Determines Victories"), *Galgavaldyr, Gangler, Gaut* ("The Creator") *God of Hanged Men, God of Ravens, Grimmr, Grimnikr, Grimnir, Habard, Hackeberg, Hakoi-berent, Hanga-tyr, Har* ("The High One"), *Harbard, Helblindi, Herfadir, Herjan* ("God of Battles"), *Her-tyr, Heryan, Hnikar, Hrafna, Hropt, Jafnhar* ("Even as High"), *Karlafberge, Lord of the Gallows, Od* (possibly), *Odr, Omi, Oski, Rafnagud, Roptatyr, Sidhottr, Sigfadir* ("The Father of Battle or of Victory"), *Sigtyr, Skidskegg, Thudr, Uggerus, Vafud, Vale, Valfadir, Valfather, Valkjosandi* (Scandinavian), *Vegtam, Vidforull, Wild Huntsman, Woden, Ygg* ("The Awful"), *Yggr.*

There are many legends associated with Odin, the supreme deity, and god of war, intelligence, and poetry. Odin so thirsted after knowledge that he sacrificed an eye to his uncle, the giant Mimir, for a drink of the beverage of wisdom from Mimir's Well. Considered to be the wisest of all deities, other gods sought advice from him. One of his abodes, named Gladsheim, is located in Asgard. From his throne, known as Hlidskialf, in Valaskjalf, Odin is able to see and know all throughout the world. His dietary habits are sparse; at his banquets he drinks only wine. The meat set before him is given to his wolves, Geri and Freki. A handsome man, his sexual appetite is robust. Some say he is a polygamist. Among his spouses are Jord, Frigga, Rind, Saga, Grid, Gunnlod, and Skadi. Some say he had only two wives, Gritta and Grydat, but numerous affairs with mortal women, female giants, and supernatural beings. In an ancient legend, Odin's sons are named Weldegg, Beldegg, Sigi, Skiold, Saeming, and Yngvi. They are reputed to have been mortal kings. In another ancient legend, Odin and Frigga have seven sons who are said to have founded the Anglo-Saxon heptarchy. Yet another rendering couples Odin with Jord, with whom he had a son Thor, with Frigg a son Balder, with Grid a son Vidar, with Rind a son Vali, and other sons Heimdal, Hod, Bragi, Tyr, Meili, and Hermod. Odin is known as a magical sovereign with a vast knowledge of the runes, a magical method of divination, later used in the formation of an alphabet. The runes gave him the power to kill enemies, cure illness, and compel women to sleep with him. His magical powers give him the ability to assume many guises. He prefers the identity of the traveler so that he can wander the earth observing the actions of people. His ravens, Huginn, who personifies thought, and Muninn, who personifies memory, lift from their perches on his shoulders each day and fly to various places in the universe. When they return they tell Odin of all they have seen. Odin travels wherever he desires on his eight-footed horse, Sleipner, the fastest horse in the world. In one legend, Odin appeared to the giant Gunnolth in the form of a snake and spent three nights with her. During this time, she gave him a few drinks of the beverage of poets, Odraerir. Odin also bragged that he had slept with seven sisters. As a warrior, he encourages his men to fight like dogs and wolves. Two warriors, Sigmund and Sinfjotli, are characterized as werewolves. The cult of the berserkir, warriors dedicated to Odin, dressed in wolf or bear skins fight like wild animals. In some legends, Odin is thought of as a horse and horses were sacrificed to him. Odin is also thought of as a death demon in Teutonic folklore. He told Aun or On, the king of Sweden, that he could live as long as he sacrificed one of his sons every ninth year. The king followed the instructions but when it came to his tenth son the Swedes would not allow him to be sacrificed, so the king died and is said to be buried in Upsala. There is an interesting myth that tells of Odin being exiled by the other gods who were unhappy with his transgressions. They provided a substitute, the crafty wizard Oller who ruled for ten years and was expelled from his throne when Odin returned. Oller moved to Sweden and was slain as he attempted to rebuild his fortunes. In one myth Odin is known as the god of wisdom, agriculture, poetry and war. He is the god of death and battle, originally one of three brothers born of Bor at the beginning of time. In that version the three created a man and woman, Ask and Embla, from two trees. Odin gave them breath and life, his brother Vili gave them understanding, and his other brother Ve gave the warmth and human characteristics. In another version, it is Odin who created the progenitors of the human race and all living things including the first mortals, Ask and Embla. His brothers are Vili and Ve. Odin's sons with Frigga are Balder, Hodur, a blind god, and Boe. Boe is sometimes called his son by Rind. Odin had Boe kill the slayer of his father, Balder. Other sons of Odin are Ty, Brage, and possibly Heimdall and Vidar. In legends of Thor, Odin was said to be his father and Jord or Fjorgyn, his mother. Odin is also thought of as a death demon in Teutonic folklore. Wednesday in the English and Scandinavian language comes from Odin's name. He collects fallen warriors known as einherjar. They will assist him in the foretold battle of Ragnarok at the end of time. Men were hung as sacrifices to Odin. Odin voluntarily hung himself from the tree of life, Yggdrasil, for nine nights without food or beverage. By carefully observing everything around him, he noticed magic runes beneath him. With great effort he was able to lift them, and was immediately set free. He was rejuvenated by his experience of self-sacrifice. Odin is pictured as a grey-bearded, one-eyed man in a blue cloak and a broad-brimmed hat who usually carries his magic spear, Gungnir, and wears the ring Draupnir. His symbol is the eagle, and sometimes the wolf, or raven. In most versions, his two ravens, Huginn and Muninn, are perched on his shoulders, and his two wolves, Geri and Freki, lay at his feet. In nearly every respect Odin is similar to Jupiter (Roman) and Zeus (Greek). Odin is the same as the Wodan (German). Compare Odin to Nuada (Celtic), Lugh (Celtic), Savitri (Hindu), Varuna (Hindu) and Esus (Gaul). *See also* Aesir; Ask; Audhumla; Balder; Baugi; Bergelmir; Bestla; Boe; Bor; Buri; Embla; Frigga; Gladsheim; Grid; Gunnlod; Harbard; Heimdall; Helblindi; Hermod; Hlidskjalf; Hoder; Huginn; Jord; Jotun-heim; Jotuns; Loki; Mimir; Mimir's Well; Muninn; Odraerir; Ragnarok; Rind; Saeming; Saga; Sigi; Sigmund; Sinfjotli; Skadi; Sleipnir; Sokvabek; Ull; Ve; Vidar; Vili; Yggdrasil; Ymir.

Odnir (Teutonic) *see* Od or Odin.

Odraerir *Od-Hroerir, Odherir, Odhroerir, Odrerer, Odrorir, Odrovir, Othrevir, Othroerir* (Norse; Teutonic)

Also known as: *Eldhrimir* ("Firefrost"), *Hvergelmer, Hvergelmir.*

Odraerir is one of the vessels of magic mead. In this myth the gods created the god of wisdom, Kvasir, from their saliva. Two dwarfs, Fjalar and Galar, slew him and drained his blood into three vessels. Two of the vessels were crocks named Son and Boden. The third vessel was the kettle named Odraerir. They mixed the blood with honey, and anyone who sipped from this mixture became a great poet and singer. After killing the giant Gilling and his wife, Fjalar and Galar were captured by Gilling's brother Sattung. In return for their lives they traded the mixture to Sattung who put it in charge of his daughter, Gunnlod. In some myths, Odraerir is guarded by Bolthorn's son. Odin in one of his adventures found the magic mead and drank all three vessels, thus becoming the greatest of all poets and singers. In his haste to empty all he had taken Odin emptied his mouth into a vessel the people of Asgard prepared, but spilled a few drops. This allowed the mortals who lapped it up the great power of poetry. Odraerir was called Eldhrimir when it was used to boil the flesh of the wild boar. *See also* Baugi; Bolthor; Fjalar; Gilling; Gunnlod; Hvergelmir; Kvasir; Niflheim; Odin; Sattung; Son (A).

Odrerer (Teutonic) *see* Odraerir.

Odrorir (Teutonic) *see* Odraerir.

Odrovir (Teutonic) *see* Odraerir.

Odu-Duwa (Africa) *see* Oduduwa.

Odudua (Africa) *see* Oduduwa.

Oduduwa *Odudua, Odu-Duwa* (Yoruba People, Africa)

Androgynous earth deity. "Self-existent ruler who created all beings." Often Oduduwa is known as the goddess wife of Obatala. Together they are credited as the creators of earth. Sometimes it is Obatala who created mother earth from his spouse Oduduwa. Oduduwa has a son, Ogun, who became a renowned warrior. Creator of dry land. King of Ife. In some creation myths, Oduduwa was sent to finish the job of creation after Obtala fell into a drunken sleep. Some say Oduduawa as a god is the father of Aganju and Yemaja. In another version his son is Oranyan. In a version of the creation myths of the Yoruba people, Olodumare, the supreme being created the earth from a celestial gaseous mass. It was formed in what became known as the cities of Oyo, Ife and Ibadan in Nigeria. The first divine spirit who was created, known as an Orisha, was Oduduwa. He was given the spirit of Olodumare and could act as Olodumare. He was the highest authority on earth and the foremost ruler. He filled a deep abyss with gasses left from the creation of the earth and created water. From water the next Orisha was formed in the likeness of Oduduwa and as Oduduwa but with opposite qualities. Yembo, the mother of water followed and became the spouse of Oduduwa. From Yembo all the waters of the world were created. The marriage of Oduduwa and Yembo represented the union of the sea and the earth. From this union came the creation of other Orishas. For other versions of the creation myth of the Yorubas, *see* Orish-nla and Olodumare. *See also* Ajanju; Ife; Obtala.

Odur (Teutonic) *see* Od; Odin.

Odysseus (Greek)

Also known as: *Ulixes* (Latin), *Ulysses* (Roman).

Deified mortal. Son of Laertes or possibly Sisyphus, and Anticleia. King of Ithaca Husband of Penelope. The wiliest of the Greek leaders at Troy, he was the inventor of the wooden horse. His wanderings on the way home from Troy, which form the subject of Homer's *Odyssey*, lasted twenty years. Finally he reached home and killed the suitors by whom Penelope had been surrounded during his absence. Achaemenides, a companion of Odysseus, was abandoned by him in Sicily and saved by Aeneas. *See also* Aeneas; Aeolus (B); Ajax the Greater; Ajax the Lesser; Anticleia (A); Argus (F); Calypso; Ino; Sirens; Sisyphus.

Oebaulus (Greek)

King of Sparta. He is the husband of Gorgophone, who was first married to his brother, Perieres. She was the first Greek woman to remarry. *See also* Gorgophone.

Oedipus *Oidipous, Oidipodes* (Greek)

Deified mortal. King of Thebes. Son of Laius (Laios) and Jocasta, who, fulfilling a prophesy of the oracle at Delphi, unwittingly killed his father and married his mother. Laius, attempting to thwart Fate, ordered his infant son to be killed. Jocasta had the child carried to Mount Cithaeron where he was raised by a shepherd. Unaware of his lineage, he killed a stranger who turned out to be his father on the road to Thebes years later. He was rewarded with the hand of his mother, the Queen of Thebes, for ridding the city of the dangerous Sphinx by guess-

www.ebook3000.com

ing its riddle. When she discovered her son's identity, Jocasta committed suicide and Oedipus, tormented by the Erinyes, blinded himself. He left Thebes with his daughter Antigone, and died at Colonus near Athens comforted by the hero Theseus. *See also* Adrestus; Antigone; Eteocles; Jocasta; Polyneices; Theseus.

Oegir (Teutonic)
Also known as: *Hler.*
Sea deity. Consort of Ran (the robber, or tempest). As Hler, he is the ruler of the underworld. Hler and Ran raised up the fierce waves called Kolga. Hler's consort is the goddess Hela. *See also* Hel.

Oegishailm (Norse; Teutonic)
Magic Helmet. Helmet of darkness worn by Fafnir.

Oenamaus *Oenomaus* (Greek)
Oenamaus is the son of Ares or Alxion by Harpina, who is the daughter of the river god Asopus, or possibly the Pleiad Asterope. In some traditions, Asterope is the wife of Oenamaus and not his mother. He married Evarete, the daughter of Acrisius, and became the father of Hippodamia and Leucippus, who dressed as a female to befriend Daphne and was killed by her friends. Oenamaus, the king of Pisa, was told by an oracle that he would be killed by his future son-in-law. In order to negate the prophecy he devised chariot races offering Hippodamia as the prize. Certain that he would never be defeated because he had been given a pair of winged horses and special armor by his father Ares, he was able to eliminate twelve or thirteen suitors who lost the races and their lives in the treacherous contest. Each participant was instructed to take Hippodamia in his chariot and dash off toward Corinth. If Oenamaus overtook him, he was beheaded and his head was nailed to the palace door. Pelops, the son of Tantalus, had heard of Hippodamia's great beauty and of her father's wealth. Determined to emerge the victor, he prayed to Poseidon for guidance and he became friendly with Myrtilus, a son of Hermes, who was in charge of maintaining Oenamaus' chariot. Pelops bribed the man by offering him a night in bed with Hippodamia and half the kingdom if he would leave the linchpin out of the king's chariot wheel. Some writer's believe that Hippodamia bribed Myrtilus, who was said to be in love with her. Pelops emerged the victor of the race when the wheel of the king's chariot flew off and he was hurled to the ground. As he was dying, Oenamaus cursed Myrtilus for betraying him and declared that his once trusted assistant would die at the hands of his new friend, Pelops. *See also* Acrisius; Ares; Daphne; Hippodamia (A); Leucippus; Pelops.

Oenarus (Greek) *see* Ariadne.

Oeneus (A) (Greek)
He is the son of the god of war, Ares, and Demonice or possibly Alcippe. His siblings are Evenus, Molus, Pylus and Testius. *See also* Alcippe; Ares.

Oeneus (B) (Greek)
King of Calydon. Oeneus is the son of Porthaon and Euryte. His siblings are Alcathous, Agrius, Melas, Sterope and Leucopeus. His first marriage was to his niece, Althea. He was the father of Deianeira, Gorge (who was later turned into a guinea fowl by Artemis) and Toxeus. Some say Meleager is also his child. Althea felt responsible for the death of Meleager, so she hung herself. After Althaea's suicide, Oeneus married Periboea. Their children are Olenias, Perimede and Tydeus (some say he is the son of Oeneus' daughter Gorge). Oeneus has a son, Laocoon, by a member of his household staff. It was the custom of the land owners to pay homage to the goddess of hunting, Artemis. Oeneus forgot to pay his dues. The infuriated goddess sent the Calydonia Boar to plunder his land. Oeneus killed Toxeus for jumping a ditch that was to protect Calydon. Oeneus was also killed, possibly by his brother Agrius' sons. *See also* Althea; Ares; Artemis; Athena; Calydonian Boar Hunt; Heracles; Laocoon; Meleager; Periboea.

Oengus (Celtic, Irish) *see* Angus; Dwyn.

Oengus of the Bruigh (Celtic, Irish) *see* Angus.

Oenomaus (Greek) *see* Oenamaus.

Oenone *Oinone* (Greek)
Oenone is the daughter of the river god Cebren. A nymph, she married Paris, who later abandoned her for Helen. Oenone and Paris had two children, Corythus and Daphnis. Corythus either found his father in bed with Helen and killed him or Paris killed his son because the young man fell in love with Helen. Oenone attempted a reconcilation, but was not successful. Though she had the gift of healing, she could not heal her inner anguish. When Paris, wounded in battle at Troy, appealed to her to heal him, she refused. Stricken with remorse, she acquiesced but it was too late. He died. She hung herself. *See also* Helen; Nymphs; Paris.

Oenopion (Greek)
He is the son of Dionysus and Ariadne or Theseus and Ariadne. Dionysus taught him the art of cultivating the vine. He married the nymph Helice and became the father of a daughter, Merope, and several sons. When Orion raped Merope, Oenopion blinded him. *See also* Ariadne; Dionysus; Merope; Orion; Pleiades; Theseus.

Ogdoad, The (Egypt)
Also known as: *Island of Flame, Primordial Hill.*
Heaven. The "Island of Flame" or "Primordial Hill" was the first body to appear. Upon it, in turn, appeared an Ogdoad of eight divinities who created Atum. They are Nun and Naunet (also spelled Nunet), god and goddess of the ocean; Heh and Hehet (also called Huh and Huker), god and goddess of the immeasurable who created the sun; Kek and Keket (also called Kuk and Kuket), god and goddess of darkness which enables the sun to shine; Amun and Amunet (also called Nui and Nuit), god and goddess of mystery who are made of air and, as Nui and Nuit, invisible. The head of this pantheon is Thoth, who found the ancient deities instated in Khemenu, "the town of eight," along with Wenet, the goddess-hare and a baboon. It is said that the great sun god Ra rested there when he rose for the first time. The male halves of the Ogdoad were frog-headed and the female halves were serpent-headed. *See also* Amen; Ament; Ennead; Hebdomad; Huh and Hauhet; Isle of the Blessed; Thoth; Wenet.

Ogetsu-Hime *Ogetsu-Hime-No-Kami* (Japan) *see* Izanami; Kami-Mimusubi; Ukemochi.

Oggun (Yoruba People, Africa) *see* Ogun.

Ogham (Celtic) *see* Ogma.

Ogma (Celtic, Gaul, Irish)
Also known as: *Ogham, Ogmios.*

Deity of eloquence and language. When he spoke, Ogma wore a lion skin. He had fine gold chains attached to his tongue. The gold chains indicated the gift of speech was precious. *See also* Boann; Dagda.

Ogmios (Celtic) *see* Ogma.

Ogoni (Slavic) God of Fire. *See also* Agni.

Ogoun (Africa, Haitian) *see* Obatala; Ogun.

Ogrigwabibikwa (Pygmy People, Africa)
Dwarf shape changer. A dwarf who changes into a reptile.

Ogue (Yoruba People, Africa) *see* Olodumare.

Ogun *Oggun* (Dahomey, Yoruba People, Africa; Caribbean; Central America; South America)
Also known as: *Gu* (African), *Ogoun* (Haitian).

God of iron. God of warriors, surgery (including circumcision). God of hunting. God of blacksmiths, goldsmiths and butchers. In some traditions Ogun is the second son of Oddua and Yembo. He came into the world from a volcano as it was erupting and brought with him the ability to forge weapons and tools. He has a warlike nature, and a persona that demands respect. Presently, he is popular with hunters and owners of cars and trucks. In the past, humans were sacrificed to him, now he is offered dogs in some areas. In early times, when the earth was a marsh, Ogun came from the celestial realm on a spider's web to hunt. Later, when the supreme deity Odolumare had the Orishas organize the earth, Ogun was the only one with an iron machete. He cut through the impenetrable thorn bushes and made access easier for the deities. His reward was a crown. He preferred the life of the warrior and hunter and left to live alone on a hilltop where he could pursue his passions. After many years, he returned wearing unacceptable blood stained clothing and was refused entry by the gods. Ogun made new clothing from the bark of a palm tree and found another place to live. In the Voodoo belief he is associated with rum. He is sometimes associated with the Haitian goddess Erzulie. Ogun is comparable to the Fon deity of metal, Gou. *See also* Aganju; Oba (A); Obatala; Yemoja.

Ogyges (Greek)
King of Athens. His parents are Poseidon and Gaea. Antaeus and Charybdis are his siblings. He married Thebe. *See also* Antaeus; Charybdis; Thebe.

Ogyrvan (Celtic)
Ogyrvan is a magic cauldron. It is also listed as one of the treasures of Britain. Another magic cauldron listed as one of the treasures of Britain is Gwigawd.

Oh-Kuni-Nushi (Japan) *see* Okuni-Nushino-Mikoto.

Oh-kuninushi (Japan) *see* Okuni-Nushino-Mikoto.

Oh-magatsumi (Japan) *see* Okuni-Nushino-Mikoto; Susanowo.

Oh-Yama-Tsumi (Japan) *see* Fuji.

Ohdowas (Iroquois People, North America)
Evil spirits.

They are dwarfs who live underground and control all the monsters. *See also* Dwarfs (Teutonic); Gahongas; Gandayaks; Jogaoh.

Oho-ge-tsu-himi (Japan) *see* Ogetsu-hime-no-kami.

Oho-hiru-me No Muchi (Japan) *see* Amaterasu.

Oho-iwa Dai-myo-jin (Japan)
Also known as: *Oiwa Daimyojin*

"Great God of the Rock." *See also* Taki-Tsu-Hiko.

Oho-Kuni-Nushi-No-Kami (Japan) *see* Okuni-Nushino-Mikoto.

Oho-to-mahe No Mikoto (Japan) *see* Ama-no-minakanushi.

Oho-to-nochi No Mikoto (Japan) *see* Ama-no-minakanushi.

Oho-yama-tsu-mi (Japan) *see* O-Wata-Tsu-Mi.

Ohonamochi (Japan) *see* Taki-Tsu-Hiko.

Ohouris (Egypt) *see* Anhur.

Ohoyo Osh Chishba (Choctaw People, North America)
Deity of corn. Her name means "Unknown Woman," the name of the Corn Mother.

Ohrmazd *Ormuzd* (Persia)
Also known as: *Ahura Mazda.*

The first creator. He created the Immortals, followed by the Yazatas, followed by everything else. He is both mother and father of all. *See also* Ahura Mazda.

Oidipodes (Greek) *see* Oedipus.

Oidipous (Greek) *see* Oedipus.

Oileus (Greek)
Oileus, the king of Locris, is an Argonaut. He married Eriopis and became the father of Ajax the Lesser. At one time, Oileus and Apollo were lovers. *See also* Ajax the Lesser; Argonauts.

Oinone (Greek) *see* Oinone.

Oiwa Daimyojin (Japan)
Another name for the "Great God of the Rock," Oho-iwa Dai-myo-jin. *See also* Taki-Tsu-Hiko.

Okami-no-kami (Japan)
She is a descendant of the rice goddess, Kushi-nada-hime (q.v.).

Oke (Yoruba People, Africa) *see* Olodumare.

Oke Hede (Mandan) Evil deity. The Evil Twin.

Okeanos (Greek) *see* Oceanus.

www.ebook3000.com

After that, I was invited to start testing in Europe by the Institute for Applied Biocybernetics and Feedback Research. My name is becoming known there because I teach in Europe a lot. One of the biggest institutes for training top athletes in Europe is in Vienna. They developed an instrument that can measure the brain's potential energy, which represents all the energy in the body. The doctors also said that this proves to the west that Chi exists, there is energy and a life force running in the body. That instrument picks it up in the brain and indicates how much potential brain energy you have. It also determines how much energy you have for the whole day and how much of that energy is for mental clarity and body power. They use these instruments to measure the athletes.

The study measures brainwave frequencies during four practices.



Fig. 3.12
Cosmic Inner Smile



Fig. 3.13
Cosmic Orbit

Fig. 3.14
Six Healing Sounds



Fig 3.15
Orgasmic Upward Draw



***Fig. 3.16** Alpha and Theta Waves increasing during the Cosmic Inner Smile Meditation.*

***Fig. 3.17** Ultraslow Brain potentials measurement while in Vienna.*

Oki (Huron People, North America) *see* Orenda.

Oki-tsu-hiko (Japan)
Kitchen god. *See also* Ch'an Tzu-fang (China); Inari; Tsao Chun (China); Tsao Wang (China).

Oki-tsu-hime (Japan)
Kitchen god. *See also* Ch'an Tzu-fang (China) Inari; Tsao Chun (China); Tsao Wang (China).

Okikurumi (Ainu People, Japan)
Also known as: (Male) *Aeoina Kamui, Ainu-rak-kur, Pon Okikurumi.*

Sea goddess. Androgynous deity. Husband of Turesh. When the world was new and too hot for people to walk, Okikurumi did their fishing for them, sending his wife to deliver his catch. One Ainu disobeyed the order that none should see her face and caught her by the hand. Immediately, she turned into a sea monster. As punishment, Okikurumi no longer fished for the people. That is why the Ainu are very poor. In some legends, Okikurumi is the first man and was born from the goddess Chikisani and a sun god. *See also* Chikisanti; Fuji.

Okitsushima-Hime-no-Mikoto (Japan) *see* Three Goddesses of Munakata.

Oklatabashih (Choctaw People, North America)
First woman. Her name means "Mourner of the People." She is the survivor of the Flood.

Oko (Yoruba People, Africa)
Oko, the god of agriculture, is the son of Yembo.

Okolner (Norse; Teutonic)
Home of deities. A hall named Brimer in Okolner is where the giants will convene to consume ale after the end of the world known as Ragnarok.

Oku-Thor (Norse; Teutonic)
Also known as: *Thor.*

Oku-Thor is the name used for Thor when he journeys in thunderstorms.

Okuni-Nushino-Mikoto (Shinto; Japan)
Also known as: *O-Kuni-Nushi, Oh-Kuninushi, Oho-Kuni-Nushi-No-Kami, Okuninushi, Yachihoko-no-Kami* (God of Eight Thousand Spears).

God of medicine and sorcery. One of the Shichi Fukujin (seven gods of happiness). Storm god. God of marriage. God of wealth. God of fishing. God of sericulture. Okuni-Nushino-Mikoto (Great Land Master) is said in most legends to be the son of the Valiant Swift Impetuous Hero, Susanowo, and Kushi-nada-hime. Okuni-Nushino-Mikoto, his father and brothers are the rulers of Izumo. They are the rulers of mysterious and evil happenings. His father, also a storm god, can be gentle and kind or wild and unruly. He is either the chief or an associate of the spirits of the underworld. Okuni-Nushino-Mikoto, as a medicine man and sorcerer works for the welfare of the people. His close associate is the dwarf god Suku-na-biko (Small Prince of Renown), who is the chief of the medicine men. One of Okuni-Nushino-Mikoto's eighty brothers is Oh-Magatsumi (Great Evil-doer). During times of natural disasters and pestilence, the people directed their prayers to these deities. The logic was that one appealed to the instigators of evil to avert evil. When Susanowo descended into Yami (hell), Okuni-Nushino-Mikoto took over as the ruler of Izumo. In this capacity, he is the overseer of the ghosts of old rulers, known as Ujikami. Some say that his overlord was the evil deity Ama-tsu-mika-hoshi. Okuni hated suffering, so he prevented evil spirits from injuring mortals. Once he came upon the skinned hare of Inaba who was in great pain. The brothers of Okuni-Nushino-Mikoto had advised the hare to bathe in the salty sea and dry his body in the wind. This procedure intensified his misery. Okuni-Nushino-Mikoto prescribed a fresh water dip and a roll in the sedge. Sedge is a type of plant similar to grass but the stems are solid rather than hollow. The procedure cured the hare and in thanks he offered Okuni-Nushino-Mikoto the princess Yakami, which enraged Okuni's brothers. Through various underhanded methods, they killed him. His mother appealed to the goddess Kami-Musubi, who returned her son to life as a strong, young man. To protect him from the wrath of his jealous brothers, he was sent to Susanowo's realm in the underworld. In his new location, he met and fell in love with Suseri-Hime, the daughter of Susanowo. He abducted her, a bow and arrow, a sword and a harp, all prized possessions of his benefactor. He was captured and sentenced to numerous labors. In this myth he was duped by his brothers and burned to death by a hot, rolling stone. It was not to be his end. He was reborn as a beautiful youth and named Yachihoko-no-Kami. It is said that he rode a bronze horse once a year and all who saw him turned into dogs. In time, Ninigi, the grandson of his aunt, the sun goddess Amaterasu, overthrew him and took over the throne. In some versions, Okuni-Nushino-Mikoto was the son-in-law and successor, rather than the son of Susanowo. Other renditions say that it was Onamuji, the brother of Okuni-Nushino-Mikoto, who was forcibly removed from the throne. Okuni-Nushino-Mikoto has a daughter named Shita-teru-Hime who married Ame-no-Wakahiko, the renowned warrior god. He may have been the father of two sons, Koto-shiro-nushi and Take-minakata. With Daikoku, Okuni-Nushino-Mikoto became one of the Shichi Fukujin (Seven Gods of Happiness), representing wealth. In some traditions, Okuni-Nushino-Mikoto is said to worship the deity Omiwa. *See* Kushi-nada-hime for alternate lineage. *See also* Amaterasu; Ame-no-Oshido-Mimi; Daikoku; Kami-Mimusubi; Kushi-nada-hime; Ninigi; Shi Tenno; Shichi Fukujin; Suku-na-biko; Susanowo; Take-mi-kazuchi; Yomi.

Okuninushi (Japan) *see* Okuni-Nushino-Mikoto.

Ol-Okun (Africa) *see* Olukun.

Ol-Orun (Yoruba People, Africa) *see* Olodumare.

Ola'li (Maidu People, North America) *see* Coyote.

Old Age (Greek) *see* Nox.

Old Black God, The (Maya) *see* "L."

Old Coyote (Mexico) *see* Huehuecoyotl.

Old God (Mexico) *see* Huehueteotl.

Old Woman Earth (Ashanti People, Africa) *see* Asase Yaa.

Oldherir (Teutonic) *see* Odraeirir.

Olelbis (Wintun People, North America)
Also known as: *Earth-Maker.*
Creator deity. The god Olelbis lives with two old women. His home is in Olelpanti in a beautiful sweat-house that grew until it was the largest paradise and most beautiful place in the world. When the world was destroyed by a great fire, Olelbis called upon Kahit (the wind) and Mem Loimis (the waters) to put out the fires. After, he restored the earth and created a new race of people. He is similar to Taikomol of the Yuki tribe, Yimantuwinyai of the Hupa and K'mukamtch of the Klamath People.

Olelpanti (Wintun People, North America)
Olelpanti, the home of the god Olelbis, is described as being on the upper side of the highest place. *See also* Olelbis.

Olenias (Greek) *see* Calydonian Boar Hunt.

Olenus (Greek)
He is the brother of the divine artisan, Hephaistos (q.v.).

Oler *Oller, Uller* (Norse; Teutonic)
Another name for Ull, the god of winter (q.v.).

Olifat *Olofat* (Caroline Islands; Micronesia)
Also known as: *Iolofath, Obagat, Orofat, Wolphat, Yelafath.*
Trickster deity. Messenger. Son of the god Luk and a mortal female. He emerged as an adult from his mother's skull. Olifat traveled between heaven and earth. He is a trickster god, who waged war on the other gods. Once he was put to death but his father revived him. Olifat became the messenger between Luk and mortals, and brought fire to them. In some legends it is Olifat who decreed that mankind would not be immortal. He is similar to Nareau, and is associated with Luk (qq.v.).

Oller (Teutonic) *see* Odin; Oler; Ull.

Ollerus (Teutonic) *see* Ull

Oloddumare (Yoruba People, Africa) *see* Olodumare.

Olode (Africa) *see* Sonponno.

Olodumare *Oloddumare* (Yoruba People, Africa)
Also known as: *Olofi, Olofin-Orun* (Supreme King), *Olorun* (Lord of Heaven or Owner of Heaven).
Creator deity. Olodumare, the supreme deity of the Yoruba, is the creator of everything in heaven and on earth. Born of the primordial heaven Olokun, he is the highest deity in the Yoruba pantheon. Olodumare knows the innermost thoughts and feelings of all mortals. He is said to be an impartial god who controls the destiny of each individual. Other deities in the pantheon are known as Orishas (spirits, also called divine beings) and are generally identified with, or are manifestations of, the forces of nature and patrons of occupations. Orishas have the power to be in different places at the same time. Orishas according to rank following Olodumare are Obatala, who represents purity and law; Eleggua, the ruler of all paths and opportunities in life; Ogun (also called Oggun), deity of iron; Oshosi, the hunter and judge; Ozun or Osun, the communicator; Asogguano, who represents epidemics and health matters; Orisha-Oko, Dada, the goddess of the brain and its senses; Ogue, Oke, Inle, Meyi, Argayu, the sun deity and god of the desert; Shango, the thunder deity; Jeggua, the goddess of purity and virginity; Oba, the goddess of wisdom and culture; Oya, the goddess of the air we breathe and the deity of water; Yemaya, who represents salt water; Orula and Oshun, who represents sweet water. The priests in the Yoruba religion are considered prophetic and act as intermediaries between mortals and the orishas. Some tradionalists think that Olodumare is one of a trinity rather than the supreme deity of the Yoruba. Some also say he created men, but others say it was Orisha-Nla (also spelled Orishanla, the great orisha), or that Olodumare and Orisha-Nla are one and the same being. Another opinion is that the female deity Oduduwa was the creator. In the United States, the names Olodumare, Olorun or Olofi are used by followers of the Yoruba faith. Symbols or images of Olodumare are not made, nor are temples dedicated to him, though prayers are offered to him and thanks given to him for every part of life and existence. It is said that Olodumare's favorite color is white. Some scholars treat the name Olorun as a vulgarization of Olodumare. The creation myths of the Yoruba vary in different locales. For two versions, *see* Oduduaw and Orish-nla. *See also* Eshu; Ifa; Ogun; Olorun; Orish-nla; Oschun; Shango.

Olofad (Micronesia) *see* Olifat.

Olofat (Micronesia) *see* Olifat.

Olofi (Yoruba People, Africa) *see* Olodumare.

Olofin-Orun (Yoruba People, Africa) *see* Olodumare.

Olokun *Ol-Okun* (Benin, Yoruba People, Nigeria, Africa)
"Owner of the Sea." "Lord of the Great Waters." "Lord of the Undertow." God of wealth and commerce. Provider of children. Olokun is the son of Osanobua, the creator god, or one of the children of Aganju and Yemaya. He is the father of the sky god, Olorun (also known as Olodumare). (Others say that Olorun and Olokun are rivals not relatives and that Olorun created the world and mortals.) He is the primeval sea and it is from him that the supreme deity Olodumare came forth. Olokun's splendid palace is underwater. He is a cultured god who loves beauty in all its forms. His wife, Yemaya, the goddess of salt water, represents the surface of water. More women worship him than men. Sailors pray to him for safety on their journeys. His attendants are both human and fish-like. Olokun is depicted as having mudfish as legs. In another depiction, he wears a cylindrical hat, a ceremonial apron covers his pants and he is bare-footed. *See also* Olodumare; Olorun; Orunmila.

Olorun (Benin, Yoruba People, Africa)
Also known as: *Olodumare.*
"Owner." Sky god. Creator of the world and mortals. *See also* Olodumare; Olokun.

Olu-Igbo (Africa)
Jungle deity. Owner of the bush and jungle.

Oluksak (Eskimo)
A god of lakes, he lives on the banks of the water. Only an Angakok (shaman) can talk to him.

Olumbe (Africa)
Also known as: *Orumbe.*
A god of death. Ruler of the kingdom of the dead, Magombe. Similar to the Basumbwa people's god of death named Lufu or Lirufu.

www.ebook3000.com

Olusi (Yoruba People, Africa) *see* Eshu.

Oluwa (Yoruna People, Africa) *see* Olodumare.

Olympian Creation Myth (Greek) *see* Aegaeon; Gaea.

Olympus (Greek)
Home of the gods. A lofty mountain on the border between Macedonia and Thessaly, which is the abode of the gods.

Omacatl (Aztec People, Mexico)
Also known as: *Two Reeds*
God of festivity and joy. Omacatl was worshiped primarily by the rich. At his festivites bountiful feasts and orgies were offered. He is represented as a black and white squatting figure. On his head he wears a paper coronet. Around his shoulders hangs a flower-fringed cloak. He carries a spectre, a symbol of royalty. *See also* Tezcatlipoca.

Ometecutli and Omeciuatl (Aztec, Toltec People, Mexico)
Also known as: *Ometeotl, Tonacatecutli and Tonacaciuatl* ("Lord and Lady of our Flesh").
"Lords of Duality." "Lords of the Two Sexes." They are the father and mother of mortals and have existed from the beginning. As a bisexual deity the names represent the supreme god Ometeotl. They dwell in Omeyocan and from there the souls of babes are assigned their role in life and sent to the surface of earth. They are identified with the ancestral couple, Cipactonal and Oxomoco. *See also* Ipalnemoani; Ometeotl; Tloque Nahuaque; Tonacaciutl.

Ometeotl *Ometeuctli, Ometecuhtli, Omeciuatl* (Aztec, Toltec People, Mexico)
Also known as: *Ometecutli and Omeciuatl, Tloque Nahuaque.*
"Two God." Ruler of Omeyocan, the "Place of Duality." Supreme being and creator of the universe. Ometeotl as Ometecutli and Omecuiatl is the embodiment of two persons, both god and goddess, representing dualistic, opposite forces within one deity. Ometeotl corresponds to Hunab-ku, the principal god of the Maya People. *See also* Citlanlinicue; Hunab-ku; Quetzalcoatl; Tloque Nahuaque.

Omeyocan (Aztec People, Mexico)
Home of the gods. Dwelling place of Ometeotl. The souls of babies are kept in Omeyocan until given to the mortal world. *See also* Chicunauhmictlan.

Omi (Teutonic) *see* Odin.

Omi-tsu-nu (Japan)
Earth deity. "Beach-Field-Master." Grandson of Susanowo, the storm god. He enlarged the country by tying a rope to various places and having the people pull on it.

Omicle (Phoenician) *see* Air (A); Aura.

Omidu-nu-no-kami (Japan) *see* Kushi-nada-hime.

Omito (China) *see* Amida.

Omit'o-fo (China) *see* Amida.

Omito-Fu (China) *see* Amida; O'Mi-To-Fu.

Omiwa (Japan) *see* Okuni-Nushino-Mikoto; Suku-Na-Biko.

Omohi-kane No Kami (Japan) *see* Kami-Mimusubi.

Omorka *Omoroka* (Babylon, Chaldea)
Supreme deity. Moon or sea goddess. In one version this ruler was cut in two by Bel and one half became the sky, the other the earth. Some say she is identical with Tiamat (q.v.). *See also* Bel.

Omoroka (Babylon) *see* Omorka.

Omphale (Greek)
Omphale, the queen of Lydia, made Heracles her slave for three years. They had three children, Agelaos, Alceus and Lamus.

Omumbo-Rombonga (Africa) *see* Omumborombonga.

Omumborombonga *Omumbo-Rombonga* (Herero People, Africa)
Also known as: *Mukuru.*
Deified object. The sacred tree of life from which everything sprang. The people of the district called it Mukuru or Father Mukuru. Some versions associated this deity with Cagn (q.v.).

On (Chaldea) *see* Oannes.

Ona (Tierra del Fuego) *see* Alakaluf.

Onamuji (Japan) *see* Okuni-nushino-mikoto; Susanowo; Take-mi-kazuchi.

Onar (Teutonic) *see* Anar.

Onatah (Iroquois) *see* Onatha.

Onatha *Onatah* (Iroquois People, North America)
Goddess of wheat. She is the daughter of Eithinoha, who was called "Our Mother." Abducted by a demon of the underworld, Onatha was rescued by the sun.

Oneiroi (Greek)
The Oneiroi are the children of the god of sleep, Hypnos, or Nox, the personification of night. They represent dreams. *See also* Dreams; Ereus; Hypnos; Nox.

Oneus (Greek)
A wine connoisseur, Oneus is the host of the gods and celebrities. *See also* Calydonian Boar Hunt.

Oni (Buddhist; Japan)
Devils. These devils, often giant size, can fly. They have been known to be comic, cruel, malicious and lecherous. The function of the Oni of hell is to hunt down, capture and deliver the souls of the accused to the judges in Jigoku via a flaming chariot. The earth Oni are shape changers and can become a living being or an inanimate object. There are invisible Oni who whistle, speak or sing. The Oni who dress in red are responsible for diseases and epidemics. Some say the ancient name for these demons was Shiko-Me and Mono, and that they possibly came from China or India. Like the Kappa, the Oni have a reputation for raping women. These colorful demons are red or green with heads of oxen or horses if they are the Oni of hell. The earth Oni can be pink, blue, red, or grey in color. They have horns and sometimes three eyes, three toes and three fingers. Sometimes they carry a mallet or an iron spiked rod, and wear a loin

cloth of tiger skin. They are similar to the Gaki demons. *See also* Kappa; Shiko-Me; Tengu.

Oni-tsu-nu (Japan) *see* Susanowo.

Onlar (Turkey) *see* Cin.

Onnes (Chaldea) *see* Oannes.

Onnophris (Egypt) *see* Onophris.

Ono (Hawaii; Polynesia)

Also known as: *Lono* (Hawaii), *Rongo* (Marquesas).

Ono is the son of the god of darkness, Tanaoa, and brother of Atea, the god of light. In some myths, Ono is a Kupua (trickster spirit) and fisher, born of an egg. He is one of a triad with Atea and Hakaiki. In the Marquesas, Ono as Rongo is a patron of singing. He is also associated with cultivated foods. *See also* Atea; Kupua; Rongo.

Onoophris (Egypt) *see* Aa Nefer.

Onophris (Egypt)

Also known as: *Onnophris, Onuphis, Osiris, Unnefer.*

Onophris, meaning "Good One," is a name for Osiris as god-ruler of Egypt. *See also* Osiris; Unnefer.

Onoruame (Tarahumara People, South America)

Also known as: *Our Father.*

Supreme deity. Nothing known at present. Recent discovery.

Onouris (Egypt) *see* Anhur.

Onuphis (Egypt) *see* Aa Nefer; Buchis; Onophris.

Onuris (Egypt) *see* Anhur; Ini-herit.

Onyame (Akan People, Africa)

Another spelling for Nyame.

Onyankopon *Onyankopong* (Ashanti People, Africa) *see* Nyankopong.

Onyankopong (Africa) *see* Nyankopong.

Ooyarrauyamitok (Eskimo)

A food deity. Ooyarrauyamitok sometimes resides on earth and sometimes in heaven. He can help humans procure meat.

Ope (Norse; Teutonic) Demon of torture or hysteria.

Opet (Egypt) *see* Apet; Taueret.

Ophiomorphus (Gnostic)

He is the creator serpent god, who is the son of Ialdabaoth. *See also* Archons; Horaios.

Ophion (Greek)

At one time, Ophion, the Titan, ruled Olympus with his wife, Eurynome. He was unseated from the throne and thrown into the sea or the underworld by Cronus, the god of the world, and his sister/wife Rhea, the mother of the gods. *See also* Chaos; Cronus; Eurynome (A); Rhea.

Ophois (Egypt) *see* Ap-aut; Khenti Amenti.

Ophois Wepwawet (Egypt) *see* Ap-uat.

Opian Menoetius (Greek) *see* Abderus.

Opis (Greek)

Opis is an attendant of the goddess of hunting, Artemis. *See also* Orion; Rhea.

Opita (Haiti)

The Opita are spirits of the dead who once peopled the world. They live on the island of Coaibai. They only go out at night. If you fight with an Opita, you will die.

Opo (Ashanti People, Africa)

Spirit of the ocean. A child of Nyame.

Opo-Kuni-Nusi (Japan) *see* Three Goddesses of Munakata.

Opo-yama-tu-mi-no-kami (Japan) *see* Kushi-nada-hime; Segan.

Opochtli (Aztec)

He is the god who presides over the catching of birds and fish.

Ops (Roman)

Also known as: *Rhea.*

Harvest deity. Originally, Ops was an ancient goddess of plenty who was replaced by Rhea. *See also* Cybele; Eire (Celtic); Rhea.

Oranos (Greek) *see* Nox.

Oratal (Greek) *see* Bacchus.

Orboda (Teutonic) *see* Gulveig.

Orchomenus (Greek)

He is the father of Elara, who with Zeus became the parents of the giant Tityus. Tityus was killed by either Zeus or Apollo and Artemis after he attempted to rape Leto. *See also* Apollo; Artemis; Leto; Tityus.

Orcus (Roman) *see* Dis Pater; Hades; Nox; Pluto.

Oreades (Greek) *see* Oreads.

Oreads *Oreades* (Greek)

Mountain nymphs. Oreads are the nymphs who inhabit caves and mountains. Pan, who was raised by nymphs after his mother abandoned him, enjoyed frolicking with the lithe spirits. When the goddess Artemis goes hunting, the Oreads are her attendants. They are shown as graceful women dressed in hunting costume. *See also* Artemis; Echo; Nymphs.

Orehu (Arawak People, South America)

Evil spirits. Nymphs. The Orehu are similar to mermaids who drag men and their canoes down to the bottom of rivers and lakes. In one legend they appeared to be beneficial since they gave a medicine man some unusual power. They are similar to the Yauhahu, and the Haitian Guabonito.

Oreithyia (Greek)

Oreithyia is the daughter of Erechtheus and Praxithea. She is the mother of the twins Calais and Zetes, Chione (who threw her son Eumpolus into the ocean), Cleopatra (who married Phineus), and Haemus (who was changed into a mountain). Boreas, the north wind carried Oreithyia away and raped her. *See also* Boreas; Calais; Zetes.

www.ebook3000.com

Orenda (Iroquois People, North America)
Also known as: *Otgon, Otkon.*
Supernatural force. The in-dwelling spirit of all things. The opposite spirit is Otgon, thought to be "bad magic." *See also* Inuat; Manitou; Oki; Wakanda.

Orendil (Teutonic) *see* Aurvandil.

Orestes (Greek)
Deified mortal. Orestes is the son of Agamemnon and Clytemnestra. He killed his mother and her lover, Aegisthus, to avenge their murder of his father. Thereafter, he was hunted by the Furies and fled from country to country. When, by Apollo's command, he submitted to trial before the Areopagus at Athens, he was acquitted and returned to Argos to ascend the throne. His spouse is Hermoine (q.v.). *See also* Aegisthus; Agamemnon; Eumenides.

Orgelmir (Teutonic) *see* Ymir.

Ori-hime (Japan) *see* Amatsu-Mikaboshi.

Orihime (Japan) *see* Amatsu-Mikaboshi.

Orin-Murt (Finnish)
Also known as: *Idem-Kuguza.*
Barn spirit. Considered a spirit of the threshing barn.

Orion *Oarion, Urion* (Greek)
Hunter. Constellation. Orion, a famous giant and hunter, was the son of the sea god Poseidon or Hyrieus, king of Hyria, and Euryale, the daughter of Minos. He became the father of the nymph Menodice. In a later account of his birth it is said that Hyrieus, king of Thrace or of Boeotian Hyria, who had been a gracious host to Poseidon, Hermes, and Zeus, was asked by the gods how they could repay him. He asked for a child. They urinated on the hide of a bull and buried it. After nine months, Orion grew up on the spot and was named Urion by his father. Orion married Side, who bragged that she was more beautiful then Hera. It is possible that this did not sit well with the jealous goddess, for Side died young and was sent to the Underworld. Orion met Merope, the daughter of Oenopion, king of Chios, and asked for her hand in marriage. As the price of betrothal Oenopion set the task, which Orion quickly accomplished, of clearing his island of wild beasts. Impatient, Orion did not wait for the wedding, he raped his fiancée and reaped the wrath of her father, who blinded him and threw him out on the beach. Orion, who had the power to walk on water, found his way to Lemnos. Out of pity, the god of fire and metalworking, Hephaistos, offered him the services of his servant, the dwarf Cedalion, who mounted on the shoulders of the giant guided him to the sun where his eyesight was restored by the sun god Helius (some say Apollo). His eyesight restored but his judgement still cloudy, he chased the daughters of Atlas, the Pleiades and possibly their mother, Pleione (whom he didn't recognize as his great grandmother), around for years until they became exhausted. To give them relief, Zeus placed them among the stars. Orion and his dog Sirius joined the moon goddess Artemis for the more traditional type of hunting. Old habits die hard; it is said that she shot him either for raping her or her attendant Opis, or out of jealousy because he slept with Eos, the goddess of dawn. In another less dramatic version, he was stung by a monster scorpion sent by the goddess Gaea (earth) and died. After death Orion became the brightest constellation in the sky along with Sirius, his faithful dog. *See also* Acacallis; Artemis; Helius; Hephaistos; Hylas; Pasiphae; Pleiades.

Orish-nla Orishanla (Yoruba People, Africa)
Also known as: *Obtala.*
Creator. The Yorubas have many rich creation myths that vary from locale to locale. Orish-nla was an Orisha (divine being), some say the first created by the supreme deity, Olodumare. He was sent to what became the city of Ife. He received a little earth in a snail shell, a hen with five toes and a pigeon. With this cache he was instructed to reorganize the primeval watery mass that was to become the earth. The birds scratched the earth, the hen scattered the dirt, and the earth spread out. In other versions, the Orisha Orunmila was with him and together they created the physical nature of the planet. Other Orishas joined them, rain began to fall and the creation of mortals followed. In a variation, Orisha-Nla was instructed to create mortals and the Olodumare would give them life. In an important variation of the creation myth pertaining to Orish-nla, he was sent to earth to create. Instead he fell into a drunken sleep from ingesting palm wine. The Orisha Oduduwa came from the celestial realm to investigate and upon seeing Orish-nla's condition, he fulfilled the creation command. This rendition explains why the followers of Orish-nla are forbidden to drink palm wine. In a variation of this myth, it is not Oduduwa who is the divine messenger but a chameleon. He gave Eshu, his servant of long standing, the gift of a plot of land to develop. The servant, himself a god of fate, was jealous and wicked and hated his function as a caregiver. He placed a huge boulder on a hill overlooking the land. When Orish-nla stopped by to see how the garden was growing, the wicked servant pushed the boulder over the ledge. It fractured Orish-nla into many pieces. The Orisha Orunmila collected the parts of Orish-nla's body and distributed them to different locations. It is said that Orish-nla had one wife. At some point, Orish-nla became the Orisha Obatala. This may be because at one time the name Orish-nla encompassed all Orishas. *See also* Obatala. Like Olodumare, Orish-nla favors the color white. He also likes snails cooked in butter. The distribution of his body parts indicates that his spirit is found in all living things. After the distribution of his body parts, the number of Orishas (gods), became four hundred and one, considered to be a sacred number to the Yoruba people. The number of Orishas in the pantheon varies with other sources, there are said to be up to twelve hundred. The chameleon as the divine messenger is also used in the myths of the Bantu and Pygmies. To compare to other creation myths of the Yoruba, *see* Olodumare. *See also* Eshu; Fa (A); Obatala.

Orish-Oke (Yoruba People, Africa) *see* Olodumare.

Orish-Oko *Possibly Orish-oke* (Yoruba People, Africa)
God of agriculture, patron of farmers.

Orisha-Oko (Yoruba People, Africa) *see* Olodumare.

Orishanla (Africa) *see* Orish-nla.

Orishas (Yoruba People, Africa) Divine spirits. *See also* Obatala; Oduduwa; Olodumare; Orish-nla; Orunmila.

Orithyia (Greek) *see* Orethyia.

Orko (Basque) God of thunderstorms.

Ormazd (Iranian) *see* Ahura Mazda.

Ormet (Norse; Teutonic)
The dead must cross this river in Helheim. *See also* Hel; Thor.

Ormizd (Armenian) *see* Aramazd.

Ormuz (Iranian) *see* Ahura Mazda.

Ormuzd *Ormazd, Ormuz* (Persia) *see* Ahura Mazda.

Ornytion (Greek)
He is the son of Sisyphus and Merope. *See also* Sisyphus.

Oro (Polynesia, Tahiti)
Also known as: *Oro-of-the-laid-down-spear.*
God of War. Oro was worshiped as one of the gods of the Polynesian priests or entertainers called Ka'ioi or Arioi. Some say he is a god of the afterworld. In the Maori version he is a peace god and the son of Ta'aroa. He is similar to Urutaetae and Hiro of the Areoi people of Tahiti. Oro is sometimes associated with the god Tane. *See also* Roma-Tane; Ta'aroa; Tane.

Orokannar (Africa) *see* Amagandar.

Oromazez (Iranian) *see* Ahura Mazda.

Oromila (Benin People, Africa)
He is a spirit of divination who might be same as Orunmila of the Yoruba People.

Oromuco (Aztec) *see* Omeciutal; Oxomoco; Xmucane.

Orpheus (Greek)
A famous lyrist, he is the son of Apollo and the musical Muse Calliope, and husband of Eurydice. He received his lyre from Apollo and played upon it so exquisitely that all things, animate and inanimate, were charmed. He is one of the heroes of the Argonaut expedition. His music enabled his shipmates to avoid being lured by the enchanting voices of the evil serpents known as the Sirens and thus they avoided certain death. On her wedding day, Eurydice, the new wife of Orpheus, was trying to escape the romantic overtures of Aristaeus, the beekeeper, said by some to be her husband's half-brother. A swarm of his bees chased her and she was bitten by a snake and died. Orpheus followed her to Hades and begged Pluto to allow her to accompany him back to earth. His request would be granted, he was told, if he would not look at his new bride until the borders of Hades had been passed. The temptation was too great. He looked — and lost her forever. In grief for her he spurned the Thracian women, who became incensed and tore him to pieces during the celebration of Dionysus. Compare Orpheus to Izanagi and Izanami (Japan). *See also* Adonis; Aeneas; Aristaeus; Cerberus; Eurydice (A); Hymen; Jason; Muses; Sirens.

Orphne (Greek)
She is called by some, the wife of Acheron. *See also* Acheron.

Orry (Celtic) *see* Ouri.

Orseis (Greek)
She is the nymph wife of Hellen. *See also* Aegimius; Aeolus (A).

Orsilochus (Greek)
Alpheus, the river god, is his father. *See also* Alpheus.

Ort (Finnish)
Also known as: *Urt.*
The name of the soul.

Ortheis (Greek) *see* Aeolus (A).

Orthrus (Greek) *see* Typhon (A).

Orula (Africa) *see* Olodumare.

Orumbe (Africa) *see* Olumbe.

Orun-Mi-La (Africa) *see* Orunmila.

Orunmila *Orun-Mi-La* ("Heaven Knows Who to Save"), (Yoruba People, Africa)
Also known as: *Fa,* (The Sky Knows Who Will Prosper), *Gbaye-Gborun* (He Who Lives on Earth and in Heaven), *Ifa.*
Sky deity. God of the oracle. God of knowledge. Messenger of the gods. God of healers. Orunmila is the eldest son of Olorun. A creation myth applied to Orunmila is similar to one told about Orish-nla. Orunmila received soil in a snail shell, a hen and a pigeon and was ordered to go to a primeval mass and create earth. In a variation, he assisted Orish-nla in creating the physical nature of the earth. A deity of divination, he served as the intercessor between the gods and mortals. As a divine messenger, knowledgeable of all languages on earth, he used a rope to commute between heaven and earth. He decided to stay in heaven but had to return to earth when Olokun, the Owner of the Sea, created havoc and made the planet uninhabitable. As Ifa, he is a physician who taught the use of herbs, attended women giving birth, and set up health clinics in many areas. While dwelling on earth, he chose sixteen disciples to study his methods of healing. His favorite food is the rat. For Orunmila's role in creation, *see* Orish-nla. Compare to the Yoruba creation myth pertaining to Oduduwa. *See also* Ifa for another aspect of his life. The Fon people of Dahomey call a similar deity Fa. Orunmila is similar to the Greek Hermes. *See also* Olokun; Olorun; Orish-nla.

Orvandel (Teutonic) *see* Aurvandil.

Osanyin (Africa)
God of curative medicine and divining.

Oschun *Oshan, Oshun* (Yoruba People, Africa)
Queen of the Sweet Water. Lady of Charity. Goddess of the river Osun. Goddess of food. She is the daughter of Oba Jumu and Oba Do. She is one of Shango's mates. Together they had human children. Their descendants still live along the river banks. Oschun is turned to in times of need. She will provide what is needed, and make the way a little easier. In later times, Oschun became popular in Cuba and Trinidad. *See* Oba (A); Olodumare; Shango.

Oshadagea (Iroquois People, North America)
God of the West. He fights the fire demons who destroy vegetation by flying with a load of water on his back and dropping it on the crops. He is known sometimes as the assistant to Hino.

Oshadi-Pati (India) Supervisor of Herbs. *See also* Soma.

www.ebook3000.com

Oshan (Africa) *see* Oschun.

Oshosi (Yoruba People, Africa)
He is known as the hunter and the judge. *See also* Olodumare.

Oshun (Africa) *see* Shango.

Osiris (Egypt)
Also known as: *Af-Osiris, An, Anzety, Apis, Asar, Asartait* ("The Swathed One"), *Asir, Asiri, Ausar* ("Highest of All Powers"), *Ausiri, Bull of the West, Iuwen, Onnophris, Onophris, Ptah-Sokar-Osiris, Uasir, Unnefer, Wennefer* ("The Eternally Good Being").

Osiris is one of the chief Egyptian gods and the first king of the Nile. He is the son of Seb and Nut. His siblings are Elder Horus, Set (also known as Typhon), Isis, and Nephthys. He married his sister Isis and became the father of Horus. He was given rule of the earth by his father. His station allowed him to civilize mortals by giving them laws, agriculture and religion. He also introduced viticulture and received the name Wennefer ("the eternally good being"). His wife Isis discovered wheat and barley growing wild and he introduced cultivation to the people. His vegetable aspect is symbolized by corn and many effigies made of corn husks and corn-stuffed images bandaged like mummies have been located. Osiris is thought to have been the first mummy. Like the corn, he was first trodden in the earth (burial), then rested in the dark and the new seed germinated (resurrection). Osiris was also a tree spirit. In the hall of Osiris at Denderah, the coffin containing the hawk-headed mummy of Osiris is depicted as enclosed within a tree. He is also known as "God of the Flood" and the Nile was called the "efflux of Osiris." In his aspect as a moon god he was known as Iuwen. He was referred to as a ram god. He was regularly identified with the bull of Apis of Memphis and the bull Mnevis of Heliopolis. His name may mean "place of the eye" which would correspond to his written sign. In early times, Osiris merged with Anedjti, the royal god of Bursiris. Osiris adapted his insignia of the rule, crook and flail. The phoenix, although the "ba" of Ra, the sun god, is also a manifestion of Osiris according to the *Book of the Dead*. The phallus, another manifestation attributed to the dead Osiris, is a symbol of the life forces overcoming death. Osiris's brother Set (the power of darkness and evil) was so jealous of his brother's attributes that he murdered him. The method employed varies from myth to myth. In one tale, Set enticed Osiris into a wooden box and threw him into the water where he was washed up by the sea at Byblos and discovered by Isis. She placed his remains in a coffin that Set tore open and then ripped his body into fourteen parts. Isis searched for him and wherever she found a remnant of his body, she built a shrine. (*See* Isis.) In another version of his death, Set assumed the shape of a wild boar and ripped Osiris limb to limb. A variation of this tale has Set hunting a boar and coming across the mangled body of his brother. Yet another version gives Set an accomplice, Thot. They trap Osiris, tear his body to pieces and throw him into the water. After death, Osiris became Lord of the Underworld and Judge of the Dead. He represents the sun who is overcome by night but who rises again the next morning. Reincarnated he was known as Apis. After the beginning of the Middle Kingdom all transfigured dead became Osiris, who is a symbol of resurrection. His mythical resurrection was ascribed to Anubis' knowledge of embalming, to Isis who gave him breath by flapping her wings above him and Horus who gave him the eye of Horus (gouged out by Set). Under Osiris the Egyptians were persuaded to give up cannibalism. He taught them farming, the pleasures of music and framed a legal code for them. The major cult shrine was at Abydos where an important temple was erected by Seti I in the Nineteenth Dynasty. The Greeks associated him with Dionysus and Hades. He is usually shown as a man with a beard, bound around with the clothes used in mummification but with his two hands free enough to hold a shepherd's crook and a whip, both of them symbols of authority. Osiris is sometimes joined with other gods, and depending on the god he wears a different costume. For example, Osiris-Aah is portrayed with a crescent moon or full moon on his head. The color of his skin is depicted as white (like mummy wrappings), black (the realm of the dead) or green (resurrection). There are over one hundred and fifty names or aspects of Osiris; i.e., Af-Osiris, an aspect of Osiris meaning the "flesh of Osiris." He is named Iuwen in his aspect as moon-god. Osiris is associated with Adonis (Greek), Eshmun (Phoenicia), and Tammuz (Babylon). *See also* Aani; Aaru; Aati; Ab-esh-imyduat; Adonis; Ament; Amentet; Anubis; Apis (A); Apis (B); Atum; Dionysus; Horus; Isis; Mnevis; Niobe (B); Onophris; Serapis; Set; Styx (Greek); Typhon (A); Wenenu.

Osiris-Apis (Egypt) *see* Apis (A); Serapis.

Osiris-Hapi (Egypt) *see* Apis (A).

Oski (Teutonic) *see* Odin.

Osorapis (Egypt) *see* Apis (A); Serapis.

Ossa (Greek)
Ossa is a sacred mountain in Thessaly, upon which the Giants piled Mount Pelion in order to climb to the heavens. *See also* Olympus.

Ostra (Teutonic) *see* Eastre.

Osun (Africa) *see* Oschun.

Ot (Mongolia)
She is a fire queen and goddess of marriage who is associated with Umai (q.v.).

Otafuku (Japan) *see* Ame-no-uzume.

Oter (Teutonic) *see* Ottar.

Otgon (Iroquois People, North America) *see* Orenda.

Othin (Teutonic) *see* Odin.

Othinn (Teutonic) *see* Odin.

Othinus (Teutonic) *see* Odin.

Othrevir (Teutonic) *see* Odraerir.

Othroerir (Teutonic) *see* Odraerir.

Othur (Teutonic) *see* Od or Odin.

Oti (Africa) *see* Cagn.

Otkon (Iroquois People, North America) *see* Orenda.

Otontecutli (Aztec) *see* Huitzilopochtli; Xocotl.

Otos (Phoenician) *see* Air (A); Aura.

Otr (Teutonic) *see* Ottar.

Otrera (Greek)
Otrera was one of the Amazon queens. She married Ares and became the mother of Antiope, Hippolyte and Penthesileia. *See also* Antiope, Ares; Hippolyte.

Otshirvani (Central Asia)
In this myth, the creator god Otshirvani and his assistant, Chagan-Shukuty, came down from heaven. They saw a turtle (some say frog) diving in the water. Otshirvani caught the turtle and placed it on its back. Shukuty dove in and brought up some earth from the bottom. The earth was placed on the turtle's stomach. Shulmus, the devil, climbed on the stomach with them in order to drown them. Otshirvani, trying to escape, caused the earth to increase to its present size. *See also* Vajrapani (India).

Ottar *Oter, Otr, Ottarr, Otter* (Norse; Teutonic)
Sea deity. Son of Hreidmar and brother of Fafnir and Regin. A fisherman, he changed into an otter. He was murdered by Loki. *See also* Andarvi; Fafnir; Hreidmar; Sigurd.

Ottarr (Teutonic) *see* Ottar.

Otter (Teutonic) *see* Ottar.

Otua (Polynesia) *see* Atea.

Otus (Greek)
Otus and his twin brother, Ephialtes, are known as the Aloeides. They are the sons of the sea god Poseidon or possibly Aloeus and Iphimedeia. Otus was the first to worship the Muses. *See also* Aloeides; Muses.

Oulapatou (Tierra del Fuego)
Also known as: *Wild Men of the West.*
The Oulapatou are dangerous spirits of the dead. They are invisible except when cutting the throats of sleeping people and eating their limbs. Although invisible most of the time, they are able to imitate the sounds of birds and animals. The Oulapatou are generally thought of as the dead who return to earth as evil spirits. *See also* Taquatu.

Oulomos (Phoenician)
Born by Ether and Air, he produced Chousorus, according to the Creation Legend of Mochus. *See also* Air (C).

Ouranos (Greek) *see* Uranus.

Ourea (Greek) *see* Gaea.

Ouri (Celtic)
Also known as: *Orry.*
An early sun god.

Ousoos (Phoenician)
He was the first to use skins for garments. His brother Hyposouranios was the first to build towns. *See also* Fire.

Ouvin (Teutonic) *see* Odin.

Ovinnik (Slavic)
Barn spirits. The Ovinnik are mischief-making spirits who live in barns. They have been known to set barns on fire. If there is a large, ragged black cat wandering around the property, it is likely an Ovinnik. They are one of the Domovoi spirits and are similar to the Bannik. *See also* Bannik; Domovoi.

Ox-Face (China) *see* Niu-Y'ou.

Ox-Head (China) *see* Ma-Mien; Men Shen; Niu-Y'ou.

Oxlus (Greek)
He is the son of Ares and Protogeneia. *See also* Ares.

Oxomoco *Oromuco, Oxomuco* (Aztec People, Mexico)
Also known as: *Piltzintecutli* (probably), *Xmucane* (Maya).
First man. Oxomoco and his wife, Cipactonal, were created by the four first gods. These gods were Camaxtli, Tezcatlipoca, Quetzalcoatl and Huitzilopochtli. The son of Oxomoco and Cipactonal married a woman made from the hair of the goddess Xochiquetzal. In some legends of the Hopi and Zuni Indians, Tamagostad and Cipattoval are identical with Oxomoco and Cipactonal. In some Mayan legends Oxomoco and Cipactonal are similar to Xpiyacoc and Xmucane. *See also* Camaxtli; Cipactonal; Legend of the Four Suns; Tamagostad; Xmucane.

Oxomuco (Aztec) *see* Omeciutal; Oxomoco.

Oxyrhynchus (Egypt)
Also known as: *Mormyrus Kannume.*
Deified fish. The Oxyrhynchus was worshipped in the Egyptian city of the same name and renounced in other sections as it was the fish said to have eaten the phallus of Osiris after he was chopped to pieces by the evil god Set. *See also* Osiris; Set.

Oya (Yoruba People, Africa)
Goddess of violent rainstorms. Chief wife of the three wives of Shango. The others are Oschun and Oba. Shen, her husband, disappeared, she turned into the River Niger. *See also* Olodumare; Oschun; Shango.

Ozun (Yoruba People, Africa) "The Communicator." *See also* Olodumare.

www.ebook3000.com

P

Pa (China)
Goddess of Drought. *See also* Huang Ti.

Pa-cha *Pa Ch'a* (China)
Pa-cha is a local god who is a protector against locusts. He began life as a mortal who became a general under the name of Liu Meng-tsaing-kun or Liu T'ai-wei. After death he was deified. Pa-cha is shown as a soldier with an eagle's beak or as a man with a bird's beak and feet, wearing a petticoat. He has unusually long fingernails.

Pa Hsien (China)
Also known as: *Eight Immortals, Pa Kung.*
See also Eight Immortals.

Pa Kung (China) *see* Pa Hsien.

Pa-yama-to-no-kami (Japan) *see* Ukemochi.

Pacari (Inca People, Peru)
The four brothers and sisters who founded the four religions of Peru are said to have come from Pacari, the Cave of Refuge. The first brother was Pachacamac, the second unnamed, the third was Viracocha, and Manco Capac was the fourth. In another version of this myth, two brothers, Apocatequil and Piguerao, with the help of Atagucho, cut their way out of the cave. *See also* Apocatequil; Inca Creation Legends.

Paccari Tampu (Inca People, Peru)
House of the gods. The House of the Dawn. It is a cave south of Cuzco on the Vilcamija River where Manco Capac and his brothers first appeared on earth.

Pachacamac *Pacha-Camak* (Pre-Inca, later incorporated into Inca)
Also known as: *Pacharurac* (Maker), *Viracocha* (possibly).
Supreme god. Creator. Earth god. All things emanate from Pachacamac. He is the son of the sun, Inti, and brother of Manco Capac and Viracocha. His spouse is the earth mother Pachamama. His greatest rival is Viracocha ("Foam of the Lake"). Pachacamac has the attributes of a culture hero, for he taught useful arts and crafts to the people. He is affiliated with Coniraya (q.v.). *See also* Bachue; Manco Capac; Pacari; Pachayachachic.

Pacharurac (Peru) *see* Pachacamac.

Pachayachachic (Peru)
Creator and possible director of the universe. He was brought into being in the later Inca times. *See also* Pachacamac.

Pachamama *Pacha-Mama* (Pre-Inca, Peru)
Earth mother. Some call her the wife of Pachacamac and others the wife of the sun god, Inti. Animals, particularly llamas were offered to her as sacrifice. Pachamama is still worshipped in Peru, where some identify her with the Christian Virgin Mary. *See also* Pachacamac.

Padma (India) Lotus Goddess. *See also* Lakshmi.

Padma Dakinis (India) *see* Dakinis.

Padma Krotishaurima (Tibet)
She is found in the Bardo World on the eleventh day offering a red shell full of blood to Padmaheruka (q.v.). *See also* Karma-krotishaurima; Ratna Krotishaurima; Shakti.

Padma-pam (India) *see* Padmapani.

Padma Sambhav (Tibet) *see* Samantabhadra.

Padmaheruka (Tibet) *see* Herukas; Padma Krotishaurima.

Padmapani *Padma-pam* (India)
An epithet of Avalokitesvara.

Padmavati (India) *see* Nagas and Nagis.

Paeon (A) (Greek)
He is the son of Nestor and Eurydice. One of his siblings is Antilochus (q.v.).

Paeon (B) (Greek) Another name for Apollo's son Asclepius.

Paeon (C) (Greek)
Possibly a son of Poseidon and Helle. Brother of Edonus. They are part of the Edoni tribe.

Pagoda (Buddhist) *see* Bishamon; Diakoku; Stupa.

P'ags-skyes-po (Tibet) *see* Virudhaka.

Pah (Pawnee People, North America)
He is the moon god spouse of Shakura, the sun, and father of one child. He was placed in the west by the creator god, Tirawa (q.v.).

Paha (Finnish) *see* Hiisi.

Pahulu (Hawaii)
An ancient goddess of sorcery who ruled Lanai, Molokai and a sect of Maui.

Pai (Egypt)
Guardian. He guards the twelfth sector of Tuat.

Pai Mu-tan (China)
Also known as: *White Peony.*
A courtesan, Pai Mu-tan is called upon to distract practicing ascetics. She fell in love with Lu Tung-pin, who accompanied her to the bridge leading to Paradise. As "White Peony,"

she is the symbol of wealth, honor, love and female beauty. *See also* Apsarases (India); Pramlocha (India).

Paia (Polynesia) *see* Rangi.

Pairikas *Pairika* (Zoroastrian; Persia)
Also known as: *Paris.*
These female demons are spirits of seduction who cast spells on everything. They are known to cause shooting stars and meteors. They are the counterparts of the Yata. *See also* Ameshas Spenta; Angra Mainyu; Drujs; Yata.

Pairimaiti (Persia) *see* Spenta Armaiti.

Pais (Armenia) *see* Hambaris.

Paisacha (India) *see* Pishachas.

Pakadringa (Aborigine People, Melville Island, Australia)
A thunder god. He was the son of Quork-quork. He, along with Tomituka, the monsoon rain goddess, and Bumerali, live in Tuniruna, the upperworld, during the dry season, but at the end of the season they travel together. Tomituka brings the rain, Bumerali brings lightning, and Pakadringa brings thunder. Some say it is Bumerali's voice that makes the thunder. *See also* Tomituka.

Pakasasana (India) *see* Indra.

Pakhet (Egypt) *see* Sekhmet.

Pakheth (Egypt) *see* Pakht.

Pakht *Pakheth* (Egypt)
Also known as: *Bast.*
Pakht, a goddess with the head of a lioness, is identified with Bast. She guards the entrance to dwellings and tombs. *See also* Bast.

Palaechthon (Greek)
He is the son of the earth, Gaea. He became the father of the king of Argos, Pelasgus.

Palaemon (Roman)
Also known as: *Melicertes* (Greek), *Portunus* (Latin).
Palaemon is the Roman god of ports and harbors. The Isthmian Games were founded in his honor. He could be connected with Janus, the god of beginnings and endings. *See also* Melkart.

Pales (Roman)
Pales is an ancient rustic god (he is both male and female), who may have been a god of cattle. He is possibly connected with the Greek Palikoi, who are twin sons of Zeus and Thalia (qq.v.). There is also a pastoral goddess named Pales. Each spring during her celebration, known as Parilia, fires of straw were lit and people passed through them to be purified.

Palici (Greek)
The Palici are the twin male Sicilian volcanoes born from the bowels of the earth. Their parents are said to be either Zeus and his daughter Thalia, or Hephaistos and Aetna. *See also* Hephaistos; Thalia.

Palladium (Greek)
Deified object. The Palladium is a wooden image of Pallas Athene at Troy, on which the safety of the city depended. (Some say it was a metal image.) It was stolen by Odysseus, the king of Ithaca, and Diomedes, the king of Aetolia, and rescued by Aeneas, known as the founder of the Roman race.

Pallantia (Greek)
Her parents are Evander (also known as Evandrus) and Deidamia, the daughter of Bellerophon and Philonoe. Her siblings are Pallas, the founder of the Pallanteum in Italy, Roma and Sarpedon II. Her son by Heracles was named after her brother, Pallas. *See also* Deidamia; Evander; Pallas; Sarpedon (B).

Pallas (A) (Greek) An epithet of Athene (q.v.).

Pallas (B) (Greek)
He is the giant son of Uranus and Gaea who was skinned alive by Athena during the battle of the gods and Giants. *See also* Athena; Gaea; Giants; Uranus.

Pallas (C) (Greek)
Evander and Deidamia are his parents. His siblings are Pallantia, Roma and Sarpedon. He was associated with Aeneas. *See also* Aeneas; Evander (B); Pallantia; Sarpedon (B).

Pallas (D) (Greek)
The son of Crius and Eurybia, his siblings are Astraeus and Perses. His marriage to the Oceanid, Styx, the ruler of the underworld river, produced Bia, Kratos, Nike and Zelos. *See also* Astraeus; Crius; Nike; Styx.

Pallas (E) (Greek)
Heracles and Pallantia are his parents.

Pallas (F) (Greek)
He is the son of Lycaon and Cyllene. He became the father of Chryse (q.v.).

Pallas (G) (Greek)
His father is Megamedes and his children are possibly Eos, Helios, and Selene.

Pallas (H) (Greek)
The daughter of Triton (who is the son of Posedion and Amphitrite), she was accidentally killed by her friend the goddess of war, Athena.

Pallas Athena (Greek) *see* Pallas.

Pallas Athene (Greek) *see* Pallas.

Pallor (Greek)
Pallor, the god of terror, is the son of the god of war, Ares, and his sister, the goddess of love, Aphrodite. His siblings are Anteros, the god of passion; Deimos, the god of fear; Enyo, the goddess of war; Eros, the god of love; Harmonia, who was later turned into a snake by her father; and Phobos, the god of fear and terror. *See also* Anteros; Ares; Deimos; Eros; Harmonia (A); Phobos.

Palmyra (Mesopotamia) *see* Ba'al Shamin.

Palta (Greek) *see* Rhea.

Paltar (Teutonic) *see* Balder.

Palulop (Micronesia)
God of Navigators. God of knowledge. In some myths, he

www.ebook3000.com



Fig. 3.18 A. *Altering dominance of alpha and theta waves during the Cosmic Orbit Meditation.* ***B.*** *Cosmic Healing Sounds Meditation, results in increases in alpha and theta frequencies. There are minimal beta brainwaves; the brain reaches a state of stillness and internal focus.* ***C.*** *Orgasmic Upward Draw Meditation increases the levels of alpha and theta.*



Fig. 3.19 *Left and Right Brain Charts*

It's interesting because the energy I have been describing in my teaching is exactly what they were measuring during their testing. So I went there and did the measurements with them. I just did the Inner Smile, smiling into my abdomen. They picked up these readings very quickly and said, "Your brain waves are going lower, lower and resting – and you are nearly in the sleeping state." At the same time, the muscle tension is the son of Alulei. He is the father of Rongerik and Rongelapanp or Alulei. He is also said to be the father of Big Rong, Little Rong, and Faravai. *See also* Alulei; Rongerik.

Palulukon (Hopi People, North America)
He is the Great Serpent, considered the master of rain and lightning. Palulukon is the same as Koloowisi of the Zuni People. *See also* Kokko.

Pamola (Algonquin People, North America)
He is an evil spirit of the night. *See also* Gluskap.

Pamphylus (Greek)
Aegimius, the king of the Dorians, is his father and his brother is Dymas, the Trojan who disguised himself as a Greek during the Trojan War. *See also* Aegimius.

Pan (Greek)
Also known as: *Aegipan, Consentes, Faunus* (Roman).

The god of woods, fields, and wildlife. God of flocks. Patron of hunters, shepherds. Inventor of the panpipes (syrinx). Pan's parents are Hermes and Dryope or Hermes and Penelope, or Zeus and Callisto, or Zeus and Hybris, or Apollo and a wood nymph. Pan was abandoned by his mother and raised by nymphs. He was very fond of music, enjoyed dancing with the nymphs and mischievously frightening people who walked through forests at night. When Hermes took Pan to Olympus, the gods were pleased with his delightful music and impish countenance. He is represented as having two small horns, a flat nose, and the lower limbs of a goat. He is often depicted wearing the ears of an ass, an emblem of acute perception. Apollo gave the ears of an ass to Midas for enjoying Pan's music. In this instance, it was to ridicule the king. Compare Pan to Bacchus and Silenus to whom the ass was a sacred animal. The Greeks identify him with the Egyptian god Ba-neb-djet, also a ram-god. Pan is sometimes confused with the Satyrs. *See also* Acis; Aegipan; Aegis; Evander (A); Min; Silvanus.

P'an Chin-Lien *P'an Kin-Lien* (China)
She is a goddess of fornication and patroness of prostitutes. When she was a young widow, her brother-in-law caught her with her lover and killed him. In other legends she is a mortal widow killed by her father because of her bad habits. After death, she was deified. *See also* Hariti; Kuan Yin.

P'an Kin-Lien (China) *see* P'an Chin-Lien.

Pan-Ku (Chinese) *see* Chaos.

P'an Ku (Taoist; China)
Also known as: *Yuan-shih T'ien-wang.*

P'an Ku is sometimes called the creator of the universe, which he formed with a hammer and chisel. His creation took eighteen thousand years. Each day he grew six feet taller than the day before. When his project was completed, he died so that creation could live. He is called the giant who became the world. His voice is thunder, his breath the wind and his tears (some say his blood), the rivers. His limbs are the four quarters of the world, the soil was formed from his flesh, and the constellations from his beard. Herbs and trees were produced from his skin and teeth. His bones and marrow gave us precious stones, metals and rocks. His perspiration produced the rain. Insects crawling across his body became mortals. In other variations, he is said to have been born in the egg of chaos. It is also said that he was born from Yin and Yang, the dual forces of nature. He is described as having a body four times the size of that of an ordinary mortal. Two horns project from his head, and two tusks from his upper jaw. His body is thickly covered with hair. He is also depicted as a small man, dressed in bearskin or leaves. He holds a hammer in his right hand and a chisel in his left hand (sometimes the tools are reversed). Sometimes he holds the moon in one hand and the sun in the other hand. He is often shown with a dragon, unicorn, phoenix and tortoise. In some legends, he is depicted with the body of a serpent and the head of a dragon. *See also* Adam; Adhibuddha; Buddha; Gaya Maretan; Purusha; Ymir.

P'an-T'ao *Fan T'ao* (China)
Also known as: *Shen-T'ao.*

Divine fruit. The P'an-T'ao are the peaches of the orchard of heaven (Huang t'ien) that ripened only once in three thousand years and bestowed immortality. To the Chinese, the peach became the symbol of long life, as did the tortoise. There is some confusion whether the peaches or the tree that bears them are named P'an-T'ao or Shen-T'ao. These peaches were the property of Queen Mother Hsi Wang Mu (Wang-mu-niang-niang) and Yu-huan-shang-Ti (the Jade Emperor). *See also* Hsi-Wang-Mu.

Panacea (Greek)
She is the goddess of health, daughter of Asclepius and Epione. *See also* Asclepius.

Pancasirsha, Mount *Pancaskiki, Mount* (Nepal) *see* Manjusri.

Panch Buddhas (Nepal) *see* Dhyani Buddhas.

Pancha-muke (India) *see* Nagas.

Panchajana (India)
Panchajana was originally a sea demon who lived in a conch shell under the ocean. He kidnapped Sandipani's son. Krishna, infuriated, dove into the water, killed him, and took his shell to use as a trumpet. When the horn is blown sinners are annihilated. During ceremonies a small shell, the symbol of Krishna's conch shell, is used to pour holy water over the image of Krishna. Worshipers often have an image of the conch shell branded on their arms. *See also* Krishna.

Panchali (India)
Another name for Draupadi (q.v.).

Panchashirsha, Mount *Pancaskika, Pancasirsha* (Nepal) *see* Manjusri.

Panchika (Buddhist; India)
He is the son of the ogress Hariti, and possibly Kuvera, the chief of the Yakshas. In Nepal, Panchika is known as the god of the purse. He is depicted with Hariti and his symbol is the pike. Panchika is similar to Jambhala and Kuvera (qq.v.). *See also* Hariti; Yaksha.

Pandara *Pandaravasani* (Buddhist; India)
Pandara, known as the "White-clad One," is the sakti (consort) of Amitabha. In an ancient legend, it is said that Pandara wore clothing made of stone, which could only be cleaned by fire. She is depicted as a beautiful woman, wearing flowers in

her hair, many ornaments, holding two lotus flowers and seated on a lotus. She symbolizes the all-consuming essence of fire which is also purifying and leads to compassion. Her color is rose, her position (asana) is lalitasana (one leg pendant, the other in the position of a Buddha). Her emblems are the cakra (Buddhist wheel), kapala (altar object), padma (lotus), and utpala (blue lotus). Her mudras are varada (her arm pendant with fingers and palm extended outward) and vitarka (her arm bent, fingers extended upward, except the index finger, which touches the tip of the thumb, the palm outward). The varada signifies gift-bestowing or charity and the vitarka signifies argument. *See also* Amitabha; Dhyani Buddhas.

Pandaravasani *Pandaravasini* (Tibet) (India) *see* Avalokitesvara; Pandara.

Pandareus (Greek)
The son of Merops of Miletus and a nymph, Pandareus became the king of Miletus in Crete. He married Harmothoe and became the father of Aedon, who became a nightingale after trying to commit suicide and Cleothera and Merope, who were kidnapped by the bird-like monster sisters the Harpies and forced to serve the Erinyes. Pandareus and Merope were killed by Zeus after stealing the statue of a golden dog made by Hephaistos, the god of fire. *See also* Aedon; Cleothera; Merope; Zethus.

Pandavas, The (Hindu; India)
The noble Pandavas were the heirs of Pandu, the son of Ambalika and Vyasa. Fertility gods and guardians of crops, they were born of virgin birth by their mothers, Kunti (also known as Pritha) and Madri. The eldest Pandava, Yudhisthira, the son of the god Dharma, known for his integrity, is Krishna's companion. The others are Bhima, a fiery-tempered giant, the son of the wind god Vayu; Arjuna, the son of Indra, known as chivalrous; and Nakula and Sahadeva, wise and beautiful twins who are the sons of the Asvins. The Pandavas shared the beautiful goddess Draupadi as their wife. When they were exiled for thirteen years by the Kauravas, who represent the winter or drought, the earth was not fertile. The struggle between the Pandavas and their jealous cousins, the one hundred Kauravas, is known as the "Great Battle of Kurukseta." It lasted eighteen days and is described in the *Mahabharata*. The five Pandavas are symbolic of the five senses and the five elements. *See also* Arjuna; Asvins; Bala-Rama; Bharadvaja; Bhima (A); Bhishma; Brihaspati; Dharma; Duryodhana; Indra; Jara-Sandha; Kali; Kauravas; Krishna; Kunti; Madri; Maya (C); Pandu; Satyavati; Tapati; Visvakarma; Vyasa; Yudhisthira.

Panderces (Greek) "All-seeing." *See also* Helius.

Pandora (Greek)
First woman. Zeus, enraged at the theft of the celestial fire by Prometheus, had Hephaistos, the god of fire, mould a woman from clay whose beauty would cause strife among the human race. The gods gave her various gifts: charm, beauty, the art of healing, eloquence, skills in woman's work and the ability to sing. In one myth, Zeus gave her the beautiful box and forbade her to open it. Her curiosity overcame her and when she opened it every human ill and plague escaped into the world, leaving only "hope" (Elpis) in the box. Another myth states that Epimetheus had the box in his house and Pandora found it when they married, opened it against his warnings and all human sorrows and sufferings were let loose except hope. "Pandora's Box," therefore, has come to mean something that appears valuable, but is, in truth, a curse. There is a parallel to the story of the Vedic deity Vishnu (q.v.) *See also* Epimetheus; Hephaistos.

Pandrosos *Pandrosus* (Greek)
She is the daughter of Acteus and Agraulos or Cecrops and Agraulos. Her siblings are Agraulos, Erysichthon and Herse. *See also* Acteus; Agraulos.

Pandu (India) *see* Arjuna; Bhishma; Duryodhana; Kunti; Pandavas; Vyasa.

Panhellenius (Greek)
"God of all Greeks." An epithet of Zeus.

Pani *Panis* (Hindu; India)
The Pani are devious aerial dwarf demons who live on the other side of the River Rasa and are Indra's enemies. They inspire foolish acts and encourage slander and disbelief. Compare the Pani to the Darbas and the Pishachas. *See also* Hiranyagarbha.

Pannagas (India) *see* Nagas; Nagis.

Panopae (Greek) *see* Nereids.

Panope (Greek)
Panope is one the the fifty daughters, known as the Nereids, of Nereus and Doris. *See also* Doris; Nereids; Nereus.

Panpati (India) *see* Ganesha.

Panther, The (Iroquois People, North America) *see* Dajoji.

Papa (A) *Fakahotu, Hakahotu, Papa-tu-a-nuku, Tu-metua.* (Polynesia; New Zealand)
First goddess. Goddess of earth and fertility. The female element. Opposite of Te Tumu. Her spouse is Wakea, Vatea or Rangi. Her origins vary in different myths. With Rangi, the sky as her spouse, we find them so entwined that light cannot shine through their entities. The gods, highly annoyed, talked of killing them. Finally, Rongo, Tangaroa, Haumia, and Tu tried to pry them apart, but were not successful. Papa and Rangi's son, Tane, after great effort, was able to separate his parents. Another son, Tawhiri, the god of winds, worried that his parents would be injured, created storms in an attempt to stop Tane. The storms created havoc and many creatures from the sea fled to the swamps. Tangaroa lost many of his subjects. This caused a rift between the brothers who have been enemies since that time. In another legend Papa is the goddess Tu-metua, who is the daughter of Timatekore (Tima-te-kore), and his wife Tamaiti-ngava-ringavari. Papa is the consort of Vatea. They had five children: Tangaroa, Rongo, Tonga-iti, Tangiia, and Tane. In another version, a sky god named Rehua was one of the sons of Rangi and Papa. In one legend Papa-tu-a-nuku (who was probably Papa) was the unfaithful wife of Tangaroa. She had a alliance with Rangi which resulted in a fight between Tangaroa and Rangi. *See* Adam; Maui; Rangi; Tangaroa; Tawhaki; Vatea.

Papa (B) (Mexico) *see* Topiltzin.

Papa-Tu-Anuku (Polynesia) *see* Papa (A).

www.ebook3000.com

Papa-tu-a-nuku (Polynesia)
Earth deity. One of the wives of Rangi. Their children are Rehua, Tane, Paia, Tu, Rongo and Ru. One version relates that Papa-tu-a-nuku was the wife of Tangaroa. She left him for Rangi, which caused a fight between the two gods. *See also* Rangi.

Papalguenna (Babylonia) *see* Marduk.

Papsukkal *Papukkal, Papsukal* (Mesopotamia)
He is the chief minister of the gods of heaven. *See also* Ilabrat; Ishtar; Ninsubur; Tammuz.

Papukkal (Sumer) *see* Papsukkal.

Paqok (Mexico) *see* Shtabai.

Par (Egypt)
Par is a form of the god Amen-Ra, called the "Lord of the Phallus," "Lofty of Plumes," and "Lord of Transformation, whose Skins are Manifold," The goddess Sekh-met-Bast-Ra is the female counterpart of Par. She is the "Phallus Goddess." *See also* Amen.

Para (India) *see* Vach.

Parae (Greek) *see* Fates.

Parameshthin Prajapatya (India) *see* Agni; Indra; Prajapati; Soma.

Parashara (Brahmanic, Hindu, India)
He is a Brahmin, a Rishi (arch-priest) and poet, son of Adrisyanti and King Kalmashapada who turned into the demon, Shaktar. Parashara later became the spouse of Satyavati and as a result of embracing her, the father of Vyasa. A section of the Himalayas was burnt when he performed a sacrifice. *See also* Satyavati; Rishi; Vyasa.

Parashur Rama *Parasu-Rama, Parasuraman, Purrishram, Pursurama* (Brahmanic, Hindu, India)
"Rama with an Axe." Parashur Rama is the sixth avatar of Vishnu. In this avatar, he returned to earth in human form as a Brahmin, the youngest of the five sons of the sage Jamadagni (also known as Jemdekhen) and Renuka (also spelled Runeeka). The Kshatriyas, a class of warriors, had gained power in the world. The gods felt that the power should be placed in the hands of the priests instead of the warriors and possibly the Vaishya, who were farmers, merchants, and tradespeople. The rationale was that learned men would provide an honest and peaceful environment. They dispatched Vishnu to earth as Parashur Rama to rectify the problem. Parashur Rama was taught the art of weaponry by Shiva, who gave him the battle axe known as Parashu. Parashur Rama in turn instructed Arjuna how to use weapons. Jamadagni and Renuka entertained the king with a thousand arms, Kartavirya. When he left their dwelling, he helped himself to a calf. This was not an ordinary calf. It was Kamadhenu, the Cow of Plenty, who could grant all desires. Parashu Rama killed the king and the king's sons in turn killed Jamadagni. Incensed, Parashur Rama eliminated all Kshatriyas from the earth. At a later time, the sea god Varuna gave Parashur Rama a tract of land that had previously been under water. Parashur Rama called it Malabara and opened it for settlement to all the Brahmins. In another legend, Parashur Rama is disguised as a monk. Indra had left his cow, Kamadhenu, the Cow of Plenty, in the care of the monks to keep the Kshatriyas from abducting her. Parashur Rama took care of the threat by killing the enemies. Their dead bodies cluttered the earth, leaving no room for the Brahmin. Parashur Rama appealed to Varuna who agreed to give him as much land as his arrow could cover when shot from his bow. Yama overheard this discussion and took the shape of an ant so he could nibble at the bow and insure that the arrow would not cover an extensive territory. His plot worked. Parashur's arrow merely glided to Malabara. Originally Parashur Rama was not an avatar of Vishnu. He did, however, have Vishnu's bow. His wife was Dharani, the Earth. In time, he was incorporated as one of the less important avatars of Vishnu. Compare the ant myth to a similar myth pertaining to Vishnu's death (q.v.) *See also* Kamadhenu; Lakshmi; Vamana (Vishnu's avatar as a dwarf); Vishnu; Yama.

Parasu-Pani (India) *see* Bhavani.

Parasu-Rama (India) *see* Parashur Rama.

Parasurama (India) *see* Parashur Rama.

Parasuraman (India) *see* Parashur Rama.

Paravani (India) Sacred peacock. *See also* Karttikeya.

Paravataksha (India) *see* Naga.

Parbati (India) *see* Devi; Parvati.

Parca (Roman)
Also known as: *Morta.*
Parca is the goddess of childbirth. She is one of the Parcae. *See also* Fates.

Parcae (Roman)
Roman name for the Fates. *See also* Fates; Moirai; Parca.

Parganya (India) *see* Parjanya.

Pariacaca (Inca People, Peru)
Creator deity. He was one of five eggs hatched by a falcon. Pariacaca was the creator while the other four eggs became the four winds. Later, all became men. *See also* Coniraya; Huacas; Pacha-Camac; Yananamca Intanamca.

Pariae (Greek) "Ancient Ones." *See also* Fates; Graces.

Parijata Tree *Kalpa Tree, World Tree* (Hindu; India)
The Parijata Tree is the Hindu tree of the universe. It is owned by Indrani, the wife of Indra, and is planted in Swarga, the celestial dwelling place of Indrani and Indra. The Parijata Tree was found at the bottom of the Ocean of Milk when the waters were churned. At one point, Krishna's wife demanded it for herself. A battle issued between Krishna and Indra and Krishna emerged the victor. The Parijata was taken to Dvarka until Krishna died and it was returned to Indrani, though some say that Krishna returned it of his own accord. Swarga is located between heaven and earth on Mount Meru. If the elderly gaze upon the magic wishing tree, they are reinvigorated. The Parijata Tree is said to yield all objects of desire. *See also* Andhaka; Indra; Indrani; Krishna; Kurma, Lakshmi; Satyabhama; Swarga.

Parikshit (Hindu, India)
The king of Hastinapura and patron of poetry, Parikshit is the grandson of the warrior Arjuna and the son of Abhimanya and Uttara. He was killed before birth by Ashvatthaman and brought back to life by Krishna. *See also* Abhimanya; Arjuna; Ashvatthaman; Krishna.

Paris (A) (Greek)
He is the second son of the king of Troy, Priam, and his queen, Hecuba (daughter of the Trojan river god, Cebren). His siblings are Aesacus, Cassandra, Creusa, Deiphobus, Hector, Helenus, Polyxena and Troilus. Paris mated with the water nymph Oenone and they became the parents of two boys, Corythus and Daphnis. When Hecuba was pregnant with Paris, she had a terrible nightmare about giving birth to a firebrand that destroyed Troy. When Paris was born Priam forced his chief herdsman, Agelaus, to take the infant to Mount Ida and to leave him there exposed and alone. He was suckled by a she-bear for five days. Agelaus returned to rescue the baby and to raise him as his own son. Later, Paris reconciled with his birth parents. During his youth, he became an excellent herdsman, archer, and musician. A handsome man, he had also developed an eye for beauty. During the marriage festivities for Peleus and Thetis, the goddess of discord Eris arrived in an angry mood. She was the only deity not invited to the affair. She tossed a golden apple bearing the inscription "For the Fairest" among the guests. Three beauties claimed it: Aphrodite, Athene, and Hera. Paris was called upon to decide which goddess was "the fairest." He choose Aphrodite. Athene and Hera were furious with him. He abducted Helen from the event and took off for Greece. When he refused to return Helen, the Greeks marched against Troy, and so the Trojan War began. When Troy was captured Paris was hit by a poisoned arrow belonging to Heracles, but shot by Philoctetes. Wounded, he returned to his wife Oenone to be healed. Understandably, she rejected him and departed. Overcome with guilt, she returned to find him dead. She hanged herself. *See* Atalanta who was also exposed and suckled by a she-bear. *See also* Achilles; Agamemnon; Ajax the Greater; Cassandra; Eris; Helen; Hesione.

Paris (B) (Persia) *see* Pairikas.

Parjanya *Parganya, Parjanya-vata* (Rain and Wind); (Vedic; India)
Parjanya, an Aditya, is the third on the list of the twelve names or forms of the sun god Surya. He may have been the husband of the earth goddess Prithiva. Parjanya abides in the clouds and with his rays sends water to earth. He could be the same as Perkunis (Armenian) and Perun (Slavonic). *See also* Adityas; Indra; Prithiva; Soma; Surya; Varuna.

Parjanya-vata (India) *see* Parjanya.

Parnasavari (India) *see* Tara.

Parnassus (Greek)
Deified mountain. A mountain in Phocis, dedicated to Apollo, Dionysus and the Muses.

Parthenia (Greek) An epithet of the virgin goddesses Artemis, Athena and Hestia.

Parthenopaeus (Greek) *see* Adrestus; Ares.

Parthenos (Greek) *see* Athena.

Partholanians (Irish) *see* Partholon.

Partholon *Partholan* (Irish)
Master of all crafts. Partholon, the leader of his people, the Partholanians, arrived in Ireland via Spain. They encountered the Fomorians, an evil race of giants. *See also* Banbha; Beltine; Cessair.

Partholonians (Irish) *see* Partholon.

Parusha (India) *see* Purusha.

Parvata (India) *see* Parvati.

Parvati *Parbati, Parvata, Parwati, Purbutty* (Hindu; India)
Also known as: *Adrija* (Mountain-born); *Ama; Amba* (Mother); *Ambika* (Mother); *Bagavati; Bhairavi* (Terrible); *Bhavani; Bhowani; Devi; Durga* (Inaccessible); *Gauri* (The Yellow); *Girija* (Mountain-born); *Haimavati* (Of the Himalayas); *Jagadgauri; Karala; Kausiki* (She of the Sheath); *Makali; Minakshi; Minakshidevi; Sali Kanya* (Mountain Maiden); *Sati* (Virtuous); *Skandaganani* (Mother of Skanda); *Uma* (Light).

Parvati, the mountain goddess, is an aspect of the great mother goddess Devi. As Parvati, the daughter of Mena, who is married to Himavat, the god of the Himalayans, she is known as the great virgin. She is the sister of the goddess Ganga, who is the personification of the sacred river Ganges. Parvati's relationship with Shiva followed Shiva's relationship with Sati. When Sati died, the gods wanted Shiva to remarry and decided that Sati should return as Parvati. Shiva was a practicing ascetic so absorbed in his practice that he never noticed the beautiful young woman. After several years, the gods sent the god of love, Kama, to intervene. He struck the chord of desire within Shiva, but Shiva, annoyed at the interruption, reduced him to ashes with his third eye. He was later returned to life. It took several years before Shiva acted on his passions. During this period, Parvati engaged in asceticism and continued to hope that their relationship would be consummated. Finally, she married Shiva and many more years passed before she became the mother of Karttikeya, the god of war and patron of thieves, and Ganesha, the elephant god of wisdom. In some legends, Karttikeya's mother is said to be Ganga and Ganesha's status is also disputed. Shiva had an ongoing feud with his former father-in-law, Sati's father, Daksha. Parvati noticed from her home on Mount Kailasa that Daksha was holding festivities to celebrate a great sacrifice in honor of Vishnu. Once again, he had neglected to invite Shiva. When Parvati informed her husband, the *Mahabharata* tells us that he became so furious that he rushed to the scene of the activities and caused an uproar that made the whole universe shake. In his rage, he attacked the gods. He knocked out Pushan's teeth and blinded Bhaga. He struck Narayana with his trident and Brahma had to intervene. In the *Puranas*, we are told that when Shiva found out that he had not been invited to the sacrifice, he was so livid that he created a terrifying being called Virabhadra, the monster of destruction. He also created thousands of similar demigods whom he dispatched to the air. During the ensuing melee, nature was in chaos. Indra was trampled, Yama's staff was broken, the goddess of literature, Sarasvati had her nose cut off, Mitra was blinded, Agni's hands were cut off and Chandra was badly beaten. Finally, Daksha admit-

www.ebook3000.com

ted Shiva was the supreme god, or Vishnu, who had Shiva by the throat, forced Shiva to acknowledge Vishnu's supremacy. Parvati and Shiva spent many harmonious periods together but they also had their share of marital woes. Once while Shiva was pontificating on the Veda, she fell asleep. Enraged, he threw her out of heaven and she spent some time on earth as the human daughter of a fisherman. He also had a bad habit of intruding on her bath, even though she had made her desire for privacy clear to him. (*See* Ganesha.) Parvati was also Shiva's consort or wife as Devi, and other aspects of Devi: Sati, Durga, Gauri, Kali and possibly as Bishen and Mahadeo. In the Bengali tradition, as Kali, she is the mother of Brahma, Shiva and Vishnu. Parvati is usually shown holding weapons in her ten hands. Her animal is the lion and she is associated with music. This mountain goddess is associated with Annapurna mountain, as is the goddess of daily bread, Ana-Purna (q.v.). For Minakshi, *see* Kuvera. *See also* Agni; Andhaka; Ardhanapriswara; Asuras; Avalokitesvara; Bhavani; Brahma; Daksha; Devi; Devis; Durga; Ganesha; Gauri; Indra; Kali; Kama (A); Karttikeya; Mitra; Pushan; Ratri; Rudra; Sarasvati; Sati (A); Shiva; Trailokyavijaya; Uma; Virabhadra; Vishnu.

Parwati (India) *see* Devi; Parvati.

Pasa (India) *see* Amrtakundali.

Pashadhari (India, Tibet) *see* Ankusha; Zhag-pa-ma.

Pasht (Egypt) *see* Bast.

Pashupa (India) *see* Shiva.

Pashupati (A) (India) *see* Pasupati.

Pashupati (B) (Nepal)
Also known as: *Gu-lang* (Tibet).
This goddess is propitiated by mothers of children, particularly in Tibet.

Pashupati (C) (India)
"Lord Protector of Animals." *See also* Shiva.

Pashyanti (India) *see* Vach.

Pasi (India) *see* Varuna.

Pasiphae (Greek)
She is the daughter of Helios and Perse. Her siblings are Aeetes, Circe and Perses. She married Minos and became the mother of Acacallis, Androgeus, Ariadne, Catreus, Deucalion, Eryale, Glaucus, Lycastus, Phaedra and Xenodice. In the form of a cow, built for her by Daedalus, she slept with a bull and became the mother of the Minotaur. (Some writings call Pasiphae the daughter of Callirrhoe and Chrysaor.) *See also* Acacallis; Aeetes; Ariadne; Daedalus; Deucalion; Helios; Minos; Minotaur; Oceanids; Orion; Perses.

Pasithea (A) (Greek)
One of the Graces, Pasithea married Hypnos (sleep) and became the mother of Morpheus. *See also* Graces.

Pasithea (B) (Greek)
A Nereid, she is the daughter of Nereus and Doris.

Passalus (Greek)
One of the Cercopes, who are two-tailed gnomes, Passalus is the son of Oceanus and Theia. *See also* Oceanus.

Patagonian People — Creation Legend (South America) *see* Guayarakunny.

Pasupata *Pinka* (India) Shiva's Sacred Trident. *See also* Pinka.

Pasupati *Pashupati* (India)
Also known as: *Shiva.*
Shiva as "Lord Protector of Animals" is known as Pasupati. He is described as the five-faced herdsman who wanders through the forests naked. *See also* Prajapati; Rudra; Shiva.

Patala *Patalas* (Hindu; India)
This is the lowest region of the underworld, lying beneath Mount Meru. Patala is 70,000 yojanas below the earth. It is the dwelling place of the semi-divine Asuras, which includes the Daityas, Danavas and Yakshas and is guarded by the Nagas. Vishnu left Patala to Bali, the grandson of Prahlada and great-grandson of the demon Hiranya-Kasipu. It is also the collective name for the seven (sometimes eight) infernal regions. Beneath Patala are the hells and the serpent Sesha who holds the world upon his hood. The beauty of Patala equals that of the seven upper regions. *See also* Arjuna; Asuras; Bali; Daityas; Gandharvas; Loka; Meru Mountain; Nagas and Nagis; Nara Simha (Vishnu's avatar as half-male); Naraka; Prahlada; Sagara; Sesha; Vamana (Vishnu's avatar as a dwarf); Vasuki; Vishnu.

Patalas (India) The Underworld. *See also* Patala.

Patecatl (Aztec People, Mexico)
Pulque deity. He is one of the Centzon Totochtin group (four hundred rabbits who are the gods of inebriation) and discoverer of the peyote plant from which liquor is made. He is probably a son of Cinteotl. In some legends, he is the husband of Mayahuel. *See also* Centzon Huitznahuas; Centzon Totochtin; Colhuatzincatl; Mayahuel.

Pathalavati (India) *see* Durga.

Patol (Gnostic) *see* Alaghom Naom.

Patroclus (Greek)
He is the son of Menoetius (the son of Actor and Aegina) and Periopis or Sthenele. During the Trojan War, he was a leader, along with Achilles, of the Myrmidons. The two heroes were close friends. When Patroclus died his bones were mixed with the bones of Achilles. The funeral games of Patroclus were held in his honor. *See also* Abderus; Achilles; Actor (A); Ajax the Lesser; Sarpedon (B).

Paulomi-Vallabha (India) Lover of Paulomi. *See also* Indrani.

Pautiwa (Hopi People, North America) The Sun.

Pav (India) *see* Agni.

Pavaka (India) *see* Agni.

Pavamana (India) *see* Agni.

Pavana (India) *see* Vayu.

Pavanareka, Queen (India) *see* Kansa; Yadavas.

Pax (Roman)
Also known as: *Eirene, Irene.*
Goddess of peace. *See also* Eirene; Plutus.

Paya-aki-tu-piko-no-kami (Japan)
Also known as: *Haya-akihiko-no-kami.*

"Rapid-Autumn-Lad-Deity." *See also* Haya-akitsu-hime-no-kami.

Payatamu (Zuni People, North America)
Deity of flowers. When he plays his flute, flowers bloom and butterflies follow him. *See also* Pan.

Payetome (Brazil, South America)
He is a white-bearded agriculture deity.

Paynal *Painal, Paynalton* (Aztec People, Mexico)
Also known as: *Huitzilopochtli.*
Paynal is the name of the of Huitzilopochtli's stand-in rather than substitute or impersonator at many of his festivals and when he spends part of the year in Hades. He wears Huitzilopochtli's attributes during these periods. Paynal is sometimes considered a messenger. *See also* Huitzilopochtli.

Pazuzu (Sumer)
Wind deity. Pazuzu is the son of Hanpa, the king of evil demon spirits. Pazuzu rages like a whirlwind bringing disease to mortals. He has four wings, a half-human, half-animal head, with ram's horns and his hind feet are talons. His body is covered with scales or feathers. He has the tail of a scorpion and his phallus terminates in a snake's head. *See also* Hanpa.

Peaches of Immortality (China) *see* Hsi-Wang-Mu; Kun-Lun Mountains; P'an-T'ao; Wang-Mu-Niang-Niang.

Pedaeus (Greek)
Pedaeus is the son of Atenor and an unknown woman. For a list of his siblings, *see* Atenor. He was raised by his father's wife, Theano. *See also* Acamas (B).

Pedsi and Pehor (Egypt)
Pedsi and Pehor were Egyptian brothers who drowned in Nubia and were deified in the Late Period. They became the focus of an important local cult. They may have been buried in a concealed chamber in a small temple at Dendur. This temple has been reconstructed in the Metropolitan Museum of Art in New York. Unlike Greece, the deification of mortals was rare in Egypt. *See also* Amenhetep; Imhoteph.

Pegae (Greek)
The nymph, Pegae, fell in love with Hylas, the Argonaut. She sacrificed him by drowning him. *See also* Hylas; Naiads.

Pegasos (Greek) *see* Pegasus.

Pegasus *Pegasos* (Greek; earlier, Assyrian, Hittite)
Also known as: *Pegasus of the Wells.*
Deified animal. Pegasus is the winged horse offspring of the sea foam of Poseidon and the blood of his mother Medusa. Medusa, pregnant by Poseidon, was beheaded by her husband Perseus. Pegasus and his brother, the warrior Chrysaor, were said to have sprung from her neck fully grown. Favored by the Muses, he stamped his hoof and produced the sacred Hippocrene spring on Mount Helicon and the Hippocrene spring at Troezen. Pegasus played a prime role in the tribulations of Bellerophon. Pegasus was stung by the gadfly sent by Zeus and it sent Bellerophon reeling. Pegasus continued to Olympus where he carried thunderbolts for Zeus. He was also said to be the steed of Eos and Athene. Pegasus is shown as a winged white horse. The Hippocrene Well means the "Horse's Well" and was horse-shaped. The name Pegasus means "springs of water." The foot of the horse is said to represent the penis and the horseshoe the vagina. The hoof as a life-creating symbol symbolized the reproductive organs of the male and female. *See also* Aarvak; Bellerophon; Chimaera; Eos; Gorgons; Medusa.

Pehor and Pedsi (Egypt) *see* Pedsi.

Pei-Chi-Chen (China) *see* Cheng Wu.

Peiras (Greek)
Some think there is a possibility that Peiras is the father of the eternally youthful, mortal monster Echidna by Styx, the river goddess. *See also* Argus (A); Echidna; Styx.

Peirene (A) (Greek) She is the daughter of Gorgophone.

Peirene (B) (Greek) Her father is the river god, Achelous.

Peirithous (Greek)
King of the Lapiths. Member of the Calydonian Boar Hunt. His parents are Ixion or Zeus and the Lapith, Dia. Hippodameia is his wife and the golden-haired Polypoets is their son. After an attempt to kidnap Persephone, Peirithous was sent to Hades for eternity. *See also* Calydonian Boar Hunt; Ixion; Persephone.

Peisander (Greek)
He is the son of the Trojan Antimachus and the brother of Hippomachus.

Peisidice (Greek)
She married Myrmidon and became the mother of Actor, Antiphus and Eupolemeia. For a list of her thirteen siblings *see* Canace. *See also* Aeolus (A); Antilochus.

Peisinoe (Greek) She is one of the three Sirens (q.v.).

Peisistratus (Greek)
He is the son of Nestor and Eurydice or possibly Anaxibia. *See also* Antilochus; Perseus; Polycaste.

Peitho (Greek)
Peitho is the goddess of persuasion. Her parents are the messenger of the gods, Hermes, and the goddess of love, Aphrodite. *See also* Aphrodite; Car; Hermes; Niobe (B).

Pekoi (Hawaii) A trickster deity. *See also* Kapua.

Pelasgian Creation Myth (Greek) *see* Eurynome (A); Pelasgus (A).

Pelasgus (A) (Greek)
First mortal. In the Pelasgian creation myth, Pelasgus was the first mortal, who rose up from the Arcadian soil and taught his followers, the Pelasgians, how to build huts, how to nourish themselves with acorns and clothe themselves with sheep or pig-skin clothing. *See also* Eurynome (A).

Pelasgus (B) (Greek)
He is the son of the river god, Asopus, and Metope. His two brothers are Ismenus and Pelagon. He has twenty sisters, some of whom are Aegina, Antiope, Chalcis, Salamis, and Thebe. *See also* Aegina; Asopus.

Pelasgus (C) (Greek)
First king of Arcadia. He is the son of Zeus and Niobe (said

www.ebook3000.com

to be the first mortal to be loved by a god) or Gaea (Earth). His siblings are Argus, who was the first son of Zeus' by a mortal; Isis; Typhon; Osiris (Serapis), who married his sister Isis and was murdered by Typhon. He married Cyllene and was the father of Lyacaon who was his successor to the throne. *See also* Argus (A); Asopus; Eurynome (A); Niobe (B); Typhon.

Pelasgus (D) (Greek)

His parents are Triopas and Sois. His siblings are Agenor, Iasus and Xanthus. Pelasgus built a temple dedicated to Demeter at Argos. He reinforced the city and renamed it Larissa, after his daughter.

Pelasgus (E) (Greek)

His parents are the sea god Poseidon and Larissa (the daughter of Pelasgus). *See also* Pelasgus (D).

Pele (Hawaiian, Polynesian)

Also known as: *Ai-laau* (Wood Eater), *Hina-ai-ka-malama* (her name as a woman on earth), *Hina-hanaia-i-ka-malama* (the Women who Worked in the Moon), *Ka-ula-o-ke-ahi* (The Redness of the Fire), *Pele-ai-honua* (Eater of the Land), *Pele-honua-mea* (Pele of the Sacred Earth), *Pele-Ulu* (possibly).

Mother goddess. Fire Goddess. Goddess of the Kilauea volcano. Goddess of Dance. Pele, the goddess of the Kilauea volcano on Hawaii, erupts when she is angry. She is the daughter of Moemoe (Moemoe-a-aulii) and Haumea. She has seven brothers and five sisters, or five brothers and seven sisters. One sister, whom she tucked under her armpit in her travels, is Hi'i-aka-i-ka-poli-o-Pele (in the armpit of Pele) who was born in the shape of an egg. There are several versions of her arrival in Hawaii: she was expelled from her distant homeland; she was driven to the island by a flood; she was driven out of Kahiki (Tahiti) by her sister; she went in search of her brother Kamohoali'i; or that she simply loved to travel. It is said that she caused the flood when sea water poured from her head while searching for the husband who deserted her. One of her forms is as the goddess Pele-ulu. Pele travels with the great gods Ku and Lono and some minor deities including her friend Hopoe. She is comparable to the goddess of fire or the underground of the Maoris, Pare or Parewhenua-mea. She is associated with the god of hogs, Kamapaua'a. Pele's myths revolve around her establishment of a home at the volcano and sending for her lover Lohiau to share her home. Compare to Fuji (Japan), Agni (India), Hestia (Greek), Vesta (Roman). *See also* Haumea; Kamohoali'i.

Pele-Ulu (Hawaii) One of the forms of Pele (q.v.).

Peleus (Greek)

King of Myrmidons. An Argonaut. Member of the Calydonian Boar Hunt. Owner of a sword made by the fire god, Hephaistos. Peleus is the son of Aeacus, who was the king of Aegina (and after death a judge of the dead in Hades), and Endeis the daughter of Cheiron and Chariclo (the daughter of Apollo). Peleus is the brother of Telamon and half-brother of Phocus. Phocus was murdered by Peleus and Telamon. Actor absolved and purified Peleus of the murder, gave him one-third of his kingdom, and either Antigone or Polymela for a spouse. (Some say Polymela was his daughter.) Astydameia, the daughter of Pelops and Hippodameia, fell in love with Peleus. When he rejected her advances she went to Polymela with a fabricated story. Polymela was so devasted that she hung herself. (Peleus might have murdered her and cut her body to pieces in retaliation.) After Polymela died Peleus married Thetis (daughter of Nereus and Doris). (Zeus wanted to be Thetis' lover but heard the prophesy that the son of Thetis would be more illustrious than his father, so he gave her to Peleus.) At their wedding, the goddess Eris rolled the Golden Apple. They became the parents of Achilles. *See also* Acastus; Achilles; Actor (A); Aeacus; Aegina; Argonauts; Calydonia Boar Hunt; Creteus; Eris; Hephaistos; Hippolyte (B); Jason; Paris.

Pelias (Greek)

Pelias, the king of Iolcus, is the son of the sea god Poseidon and Tyro, who was married to her uncle Cretheus. Pelias is the twin brother of Neleus. Abandoned by his mother at birth, he carried an imprint on his face from a horse who had kicked him. He usurped his brother's throne and prevented Aeson, the eldest son of Cretheus and Tyro, who was next in line, from becoming king. *See also* Admetus; Cretheus; Jason; Neleus.

Pelion (Greek)

Deified mountain. Mount Pelion is located in Central Magnesia in Thessaly. In their wars against the gods, the Giants placed Mount Pelion on Mount Ossa in order to scale the heavens with greater ease. The Centaur, Cheiron, reared a number of Greek princes in his cave on this mountain. It was on Mount Pelion that Acastus attempted to have Peleus killed. Material to build the Argos came from the wooded range. *See also* Acastus; Argos; Cheiron; Giants; Peleus.

Pelios (Greek) *see* Acastus.

Pelopia (Greek) *see* Aegisthus; Ares.

Peloponnesus (Greek) A peninsula in southern Greece. *See also* Achaeus.

Pelops (Greek)

Descendant of the gods. Deified mortal. Pelops is the son of the king of Sipylus, Tantalus, and Dione (the daughter of Atlas) or possibly one of the other Pleiades. Pelops siblings are Broteas and Niobe. Broteas carved his mother's image in a rock and when he wouldn't do the same for Artemis, she drove him insane and he burned himself to death. Niobe was eventually turned to stone. Through nefarious maneuvers Pelops married Hippodamia, the daughter of Oenamaus. Pelops fathered numerous children: Alcathous, the Megarian king; Astydameia, who was chopped to death by Peleus; Atreus, king of Mycenae; Copreus, who was killed by Heracles; Lysidice; Nicippe, also known as Amphibia, who married Sthenelus; Pittheus, the king of Troezen; Thyestes, the king of Mycenae who raped his brother Atreus' wife, Aerope; Troezen, who co-ruled Troezen with Pittheus; and possibly Epidaurus and the robber Sceiron (Sciron). He was also the father of Chrysippus by either Astyoche or Axioche. Chrysippus was murdered by his half-brothers, Atreus and Thyestes, or by his stepmother Hippodamia. Pelops had an unusual beginning in life. His father, Tantalus, chopped him up and served him as a meal to the deities. All but the goddess of agriculture, Demeter, realized what Tantalus had done. Demeter ate Pelops' left shoulder. The gods restored the infant to life and Demeter gave him an ivory shoulder. He was so beautiful that the sea god, Poseidon, fell in love with him and took him to Olympus. In time, he was returned to earth, some say because of his father's crimes. When he married Hippodamia he became the king of Pisa and proceeded to acquire surrounding areas as well. Under the pretense of friendship he became acquainted with King Stymphalus of Arcadia and then brutally murdered him to procure his land. Before his marriage, he had made promises to Myrtilus, a son of Hermes, that he did not intend to keep. Myrtilus kept reminding him of his debt which included the privilege of sleeping with Hippodamia for one night and half of the kingdom. Finally, Pelops killed Myrtilus by throwing him into the water, possibly near Elis harbor. This act manifested a curse put on Myrtilus by Oenamaus as he was dying. Now, as Myrtilus saw his death fast approaching, he cursed the house of Pelops. Some say that Pelops murdered Myrtilus the same day that Pelops won Hippodamia's hand. In the end it was thought that Pelops realized his wife and or his sons were guilty of murdering Chrysippus and she either committed suicide or went to live with her sons. Nothing is known about Pelop's death although his great-grandson, Heracles, established a shrine in his name at Olympia. (Not to be confused with Pelops, the twin of Teledamas, children of Cassandra and Agamemnon who were murdered as infants or Pelops the son of Amphion and Niobe.) For the devious method employed by Pelops to win Hippodamia's hand, *see also* Argus (A); Astydameia; Demeter; Eurydice (C); Hippodamia (A); Oenomaus; Tantalus (A).

Pelus (Greek) *see* Actor.

Pemba *Pembu, Pembo* (West Africa)
Supreme being or creator. He was born from the Cosmic Egg but found the world was incomplete so Pemba returned to retrieve seeds from the egg. Those seeds were impure, so Pemba's twin, Faro, was sacrificed to purify the earth. In another version, as Pembo, he is a god of water, agriculture, and wisdom. He is the son of the Voice of the Void, husband of Musso Koroni. *See also* Faro; Mangala (B).

Penates (Etruscan, Roman)
Gods of the household. The Penates are usually in groups of two or three. They were honored at mealtimes by families as gods of storerooms. They are shown most often in a dancing attitude. These gods share the hearth with Vesta and the Lar. The Romans connected them with the Terminalia and Janus. *See also* Lares; Janus.

Peneius (Greek)
Peneius is the river god son of Oceanus and Tethys. *See also* Oceanus; Rivers; Tethys.

Peneleos (Greek) *see* Argonauts.

Penelope (Greek)
Deified mortal. Wife of Odysseus. She was besieged by more than a hundred suitors during her husband's absence at Troy. She firmly believed that Odysseus would return and therefore delayed a decision as long as possible. Finally she promised to make a choice when she had completed a certain robe which she was then weaving. By undoing at night what she had woven during the day, she was able to put off the suitors until Odysseus returned. *See also* Calypso; Odysseus.

Peneus (Greek)
River deity. A river god in Thessaly and father of the nymph Daphne, who was pursued by Apollo.

Penglai (Taoist, China)
A magic island, home of immortal beings who possess the secrets of eternal life.

Penthesileia (Greek)
Queen of the Amazons. She is the daughter of Ares and Otrera and the sister of Antiope (also known as Melanippe) and Hippolyte. An ally of the Trojans, she was killed at Troy by Achilles (q.v.). *See also* Amazons; Ares; Antiope; Hippolyte (A).

Pentheus (Greek)
King of Thebes. His grandfather is Cadmus, who introduced the alphabet to the people. His parents are Echion, who is one of the Sparti, and Agave. Pentheus was ripped to pieces by his mother and his aunts. For details, *see* Agave, Ino. *See also* Cadmus.

Peparethus (Greek)
He is the son of Dionysus and Ariadne. *See also* Ariadne; Dionysus.

Pepi (Egypt) *see* Apep; Apepi; Apophis; Hades; Rahabh; Tiamat.

Per Uadjit (Egypt) *see* Uatchet.

Percht (Teutonic) *see* Bertha.

Perchta (Teutonic) *see* Bertha.

Perdix (A) (Greek)
Also known as: *Calus, Talus.*
Inventor. He is the son of Perdix. Perdix worked as an assistant to his uncle, Daedalus. Daedalus, jealous of his nephew's inventions, murdered him.

Perdix (B) (Greek)
She is the mother of Perdix (A) and sister of Daedalus and Sicyon.

Pereplut (Slavic) Goddess of drink and changing fortunes.

Pereus (Greek)
He is the son of Elatus and Laodice and the father of Neaera, the wife of Aleus.

Peri (Persia)
The Peri are beautiful, good spirits who guide mortals to the Land of the Blessed. They are opponents of the evil daevas.

Perialces (Greek)
He is possibly the son of the king of Argos, Bias, and his wife, Pero. *See also* Pero.

Periboea (A–F) (Greek)
(A) Daughter of Hipponous, second wife of Oeneus. Mother of Tydeus. (B) Sometimes known as Merope. Spouse of Polybus of Corinth. Foster mother of Oedipus. (C) Daughter of Alcathous and Euaechme or Pyrgo. Second wife of Telamon.

www.ebook3000.com

Mother of Ajax. She rejected the love of Minos. (D) Mother of Nausithous by Poseidon. (E) Mother of Pelagon by Axius. (F) Periboea who is also known as Asterodia, Dorodoche and Mede. She is the spouse of Icarius. Some of her children are Iphthime, Penelope and Perileus.

Periclymenus (A) (Greek)
He is the shape-changer son of Neleus and Chloris. *See also* Argonauts; Chloris; Neleus.

Periclymenus (B) (Greek)
The sea god Poseidon is his father. His mother is Chloris.

Perieres (Greek)
King of Messenia. His parents are Aeolus and Enarete. He has six brothers and seven sisters. For a list of their names *see* Canace. *See also* Enarete; Gorgophone.

Perigune (Greek)
She is the daughter of Sinis and the mother of Melanippus by Theseus. *See also* Acamas (A).

Perikionios (Greek) *see* Dionysus.

Perimede (A) (Greek)
She is the daughter of the king of Calydon, Oneneus. *See also* Calydonian Boar Hunt; Jason.

Perimede (B) (Greek)
Her parents are Oeneus and Periboea. She married Phoenix.

Perimede (C) (Greek) Her sister is Amphitryon (q.v.).

Perimela (Greek) She is the mother of Ixion (q.v.).

Perimele (A) (Greek)
Her parents are Admetus and Alcestis. Some say she is the mother of Magnes. *See also* Alcestis; Admetus; Magnes.

Perimele (B) (Greek)
Perimele is one of six daughters of Aeolus and Enarete. She has seven brothers. For a list of their names, *see* Canace. Achelous seduced Perimele. Two children were born of the affair, Hippodamas and Orestes. Her furious father threw her into the sea. Poseidon changed her into an island. *See also* Achelous; Aeolus (A); Aeolus (B); Hippodamas; Orestes; Poseidon.

Periopis (Greek)
She is the daughter of Pheres and Periclymene. Her siblings are Admetus, Idomene and Lycurgus. *See also* Admetus; Pheres.

Periphetes (Greek)
Also known as *Corynetes.* He had a bad leg and carried a club to kill travellers. *See also* Anticleia (D); Hephaistos.

Perit (Egypt)
Afterworld deity. One of twelve goddesses in the ninth sector of Tuat. She utters words of power causing the life and strength to arise in Osiris. The other goddesses are Aat-aatet, Aat-khu, Hent-nut-s, Nebt-mat, Nebt-setau, Nebt-shat, Nebt-shef-shefet, Netert-en-khentet-Ra, Sekhet-metu, Shemat-khy (or khu), and Tesert-ant.

Perkaunas (Lithuanian) *see* Perkunis; Perun.

Perkuna Tete (Armenian, Lithuanian)
Thunder and lightning goddess. She bathes the sun at the end of the day. *See also* Perkunis.

Perkunas (Armenian) *see* Perkunis.

Perkunis *Perkunas, Pehrkon, Perkun, Perkuns* (Armenian, Lithuanian, Slavic)
Also known as: *Armat, Erkir.*
God of heaven and thunderstorms. Weather deity. The names Perkunas, Erkir, or Armat of the ancient Armenians are associated with the earth. Perkunis and Erkir may be a female version of one of these gods. In another version the Lithuanians had a goddess of thunder and lightning. Her name was Perkuna Tete. Oak trees were holy to Perkunis and when Christian missionaries cut them down the people complained that their forest deities were being destroyed. During times of draught animal sacrifices were made to Perkunis deep in the woods. Perkunis resembles Zeus. Compare Perkunis to Parjanya (India). *See also* Jupiter; Perun; Thor.

Permessus (Greek) *see* Aganippe (A).

Pero (Greek)
Pero is the beautiful daughter of Neleus and Chloris. She married Bias, the king of Argos, and became the mother of the Argonaut Areius; the Argonaut Leodocus; Talaus, also an Argonaut. She could also be the mother of a daughter, Alphesiboea, and another son, Perialces.

Peron (Slavic) *see* Perun; Pyerun.

Peroun (Slavic) *see* Perun.

Perse *Perseis* (Greek)
She is the Oceanid daughter of Oceanus and Tethys. Some of her siblings' names are Clymene, Doris, Electra, Meliboea, and Proteus. She has numerous other siblings who are rivers, streams, and fountains. Perse married Helius and became the mother of Aeetes, Circe, Pasiphae, and Perses. *See also* Aeetes; Circe; Electra; Helius; Minos; Oceanids; Oceanus; Pasiphae.

Perseis (Greek) Another spelling for Perse.

Persephone *Persephassa, Proserpina* (Roman), *Proserpine* (Roman); (Greek; possibly from Asia)
Also known as: *Brimo, Core, Despoina* (Arcadian) *Kore, Proserpina* (Roman).
Goddess of corn and the underworld. Daughter of Demeter and Zeus, commonly referred to as Kore or Core. Hades carried her off and married her in the lower world. (*See* Demeter.) Persephone could not leave Hades permanently since she had eaten a pomegranate in the lower world. They struck a compromise by which Persephone would spend one-third of the year with Hades and two-thirds with Demeter. Now when Persephone is in Hades, the earth is barren; when she is with Demeter, the earth blossoms. The name Brimo is also used for Demeter, Hecate, and Rhea. Her attributes are the bat, the narcissus and the pomegranate. Some legends associate her with Adonis. *See also* Admetus; Adonis; Baubo; Cocytus; Demeter; Hades; Hecate; Rhea; Sirens; Styx; Zeus.

Perses (A–D) (Greek)
(A) Son of Perseus and Andromeda. (B) Son of Helios and Perse. (C) Son of Crius and Eurybia, siblings Astraeus and Pallas, spouse of Asteria, father of Hecate. (D) Possibly the father of Chariclo.

Perseus (Greek)
Also known as: *Eurymedon* (Called this name by his mother, *Pterseus.*)

Perseus is the grandson of Acrisius, son of Zeus and Danae (Dahana) and husband of Andromeda, or possibly Persika or Aurigena. Raised by Polydectes, king of Seriphos, he was sent by him to fetch the head of Medusa. Guided by the deities Athene and Hermes, he stole the single eye and tooth shared by the Graiae, sisters of the Gorgons, which he refused to return until they directed him to the nymphs who had the magic helmet, wallet, and winged sandals of Hades. The exchange was made and he was also given a mirror from Athene and a sickle from Hermes. He found the Gorgons and used the mirror to look at Medusa while he beheaded her, for it was said if a man looked directly at her, he would turn to stone. He placed the head in the wallet, the helmet which made him invisible on his head, and fled. (For a variation of this myth *see* Medusa.) In some versions of this myth he is said to have stopped at the palace of the Titan Atlas to rest. His reception was not hospitable so he turned Atlas into a mountain (Mount Atlas). This portion of the myth is in dispute because Atlas is alive generations later in other tales. He then flew on to Chemmis in Egypt to visit his ancestors, Danaus and Lynceus. (During Herodotus' day these were the only Egyptians to worship Perseus.) As he passed over the Ethiopian colony of Joppa, on the coast of Syria, he saw Andromeda, a naked damsel in distress and rescued her from a sea-monster. He stayed with her for a time and they had a son, Perses. (*See* Andromeda.) He returned to Seriphos to find his mother a fugitive from Polydectes. He rescued her by turning Polydectes and his court to stone with the head of Medusa. He then made Dictys (the seaman who originally rescued him when he was an infant) the king of Seriphos. His battles over, he returned the weapons to Hermes and gave the head of Medusa to Athene and set sail for Argos with his mother, his wife, and some say, a party of Cyclopes. He convinced his grandfather Acrisius that he was not seeking revenge for his ill-treatment of him and his mother when he was born. During a celebration in honor of his return (according to other sources the funeral games of the father of Tentamides of Larissa), he threw a discus (said to be his invention), and accidentally killed Acrisius thus fulfilling the oracle which had haunted Acrisius for so many years. Perseus is said to have traded the kingdom of Argos for Tiryns where he established the city of Mycenae and fortified Midea with the assistance of the Cyclopes who built walls around both cities. After death, Athene had Perseus and Andromeda placed among the stars. It has also been written that Dionysus came to Argos to punish Perseus who retaliated by inflicting madness on the women of Argive who then began to devour their children. Perseus realized his mistake and placated Dionysus by dedicating a temple to him. This tale is similar to the story related about Perseus' grandfather's twin brother, Proetus. For details of Perseus' birth *see* Acrisius. *See also* Aegis; Antilochus; Athene; Chrysaor; Danae; Dionysus; Medusa; Pegasus.

Pertunda (Roman)
Goddess of marriage.

Perun *Peron, Peroun, Piorun, Pyerun* (Polish, Russian, Slavic)
Also known as: *Perkunas* (Armenian).

War God. God of thunder. Lord of the universe. His weapon is the thunderbolt. It is thought by some that Perun may be the same or associated with the Vedic god Parjanya who in turn was an aspect of Indra. He was the chief deity of the warrior class. It is said that at Novgorod an image of Perun in the likeness of a man stood with a thunder-stone in his hand. Elsewhere, a fire of oak wood burned in his honor and if it went out the attendant paid with his life. He was invoked by early Russian monarchs before going to war. He is shown with three heads surrounded by flames. He is similar to Zeus, Jupiter and Thor. Analogous to Svantovit (q.v.). Compare to Parjanya (India). *See also* Dazbog; Gromovit; Khors; Perkuna Tree; Perkunis; Volos.

Pesedjet (Egypt) *see* Ennead of Heliopolis.

Peseias (Slavic)
Protectors of domestic animals. *See also* Krukis.

Pesthi (Egypt)
Afterworld deity. An archer in the tenth sector of Tuat.

Petesuchos (Egypt) *see* Sebek.

Petra (Egypt)
Afterworld deity. A god in the eleventh sector of Tuat. He has a disk on his head and stretches his arms to keep apart the wings of the serpent Tchet-s.

Phae (Greek)
She is the daughter of the destructive whirlwind, Typhon, and the monster, Echidna.

Phaedra (Greek)
Phaedra is the daughter of Minos and Pasiphae and the second wife of Theseus. She has a step-son, Hippolytus, and two children, Acamas and Demophoon. Phaedra ended her life by suicide. *See also* Acacallis; Acamas (A); Adonis; Ariadne; Demophoon; Minos; Pasiphae; Theseus.

Phaenna (Greek) *see* Graces.

Phaethon (A) (Greek)
Sun deity. Phaethon is the son of Helius (the sun) and the Oceanid, Clymene. He could be the son of Clymenus by Metrope, which would make him the grandson of Helius. In an effort to prove that Helius was his father he drove the sun chariot Quadriga through the sky for one day. It was his last day. He lost control of the horses and was flung from the vehicle into the Eridanus river and became a swan. His grief-stricken sisters, the Heliades, were transformed into poplar trees. Others say that he was killed by Zeus when he drove his father's chariot too close to earth and almost set the world on fire. Some consider Phaethon the constellation Aurigia, known as the Charioteer. *See also* Aegle (A); Apsyrtus; Eos; Heliades; Helius; Oceanids; Phaethusa; Rivers.

Phaethon (B) (Greek) Another name for the Argonaut Absyrtus, king of Colchis. *See also* Aither.

Phaethon (C) (Greek)
He is the son of Cephalus, (the son of Deion and Diomede) and the goddess of dawn, Eos, or Tithonus, the brother of Phaethon and Eos. Aphrodite kidnapped him to be a guard at her shrine.

www.ebook3000.com

was very low, the heartbeat was very low and the skin resistance was very low. After that, I surged the energy up to the brain and they started to see that the energy actually charged up there. When we are thinking, worrying or feeling anger, shame or guilt – the energy level in the brain actually decreases, and the brain doesn't get charged up. They were quite amazed, and said, "Hey, this is what we're looking for!"

They asked me what I was doing. I said, "I'm smiling to my abdomen." They kept on talking to me and asking me questions. They discovered that this brain (in the head) was not very active at all, meaning that there was not much activity in the brain. It was still in a very light resting state. But, how could I answer their questions? They said, "Hey, look! Master Chia is talking to us in his sleep. How can he talk to us in his sleep?"

After that, I said, "Oh, I understand now." Because, throughout the whole practice of the Tao is the injunction, 'train the second brain in order to use the second brain.' It took the westerners a long time to understand that. So, when the article about the 'Hidden Brain in the Gut' came out in The New York Times,[1] I started to understand that. You can be miserable; you can be happy; you can feel all kinds of feelings. But according to this article, they had also discovered that this brain in the gut, the enteric nervous system, can do a lot of functions. It says that this gut brain can send and receive impulses; it can record experience and respond to emotions. So, it is like a brain. In this article, they had only discovered that the large intestine and the small intestines have the same neurons as the brain cells. After that article, a new book, *The Second Brain,* was published.[2]

Now in medical science, I might add, they have begun to discover consciousness in the heart. They found that the heart can record a whole event, and it has its own brain. Dr. Paul Pearsall has written a new book, called *The Heart's Code*.[3] They have found that people who have a heart transplant actually get the emotions of the donor. They actually experience whatever the donor experienced. One of the cases is that of a girl who was brutally killed, and they didn't know who killed her. But, the heart was OK; so, it was transplanted into another girl. After that, the girl started to get nightmares and described somebody killing her. Then she described how the killer looked. Finally, the mother took the girl to a psychiatrist, and he in turn contacted the police. The girl gave the police an exact description and a police artist drew a likeness of the killer. With the information provided by the girl, the police were able to go and arrest the man. Afterwards, when confronted with clear details of the crime, the man confessed that he was indeed guilty of this crime. So, from that experience, medical scientists and others came to realize that the heart can record all of an event and remember it.



Fig. 3.20 *Heart's Code*

---

[1] "Complex and Hidden Brain in the Gut Makes Stomachaches and Butterflies," The New York Times, section C1, Tuesday, January 23, 1996

[2] Gershon, Michael. *The Second Brain* (New York: Harper Collins Publishers Inc., 1998).

[3] Pearsall, Paul, Ph.D. *The Heart's Code* (New York: Broadway Books, 1998)

Phaethusa (Greek)
She is a Heliad. The death of her half-brother, Phaethon, grieved her so deeply that she turned into a poplar tree. *See also* Aegle (A); Heliades.

Phaland (Teutonic) *see* Volund.

Phalerus (Greek) One of the Argonauts (q.v.).

Phallus Goddess (Egypt) *see* Par.

Phan-Ku (China) *see* Chaos.

Phanes (Greek)
Also known as: *Ericepauis; Eros; Fan; Phanes-Dionysus; Protogenus Phaethon; Protogonos.*

Orphic Creation Legend. Light or the god of light. In the Orphic creation myth, the awesome goddess, black-winged Night was impregnated by Wind and laid a silver egg protected by the womb of darkness. From this egg, Eros, known as Phanes, emerged and created the earth, sky, sun and moon. He lived in a cave with Night, who called him Protogenus Phaethon, and Ericepauis. She represented herself to him as the triad of Night, Order, and Justice. Before the cave sat the goddess Rhea, who beat on a drum so that mortals would heed the oracles of the triple-goddess who ruled the universe. In time, her scepter was passed to Uranus. Although the name Eros is associated with Phanes it is not the god of love, but rather is influenced by the mystical doctrine of love. Double-sexed, with four heads, golden wings and the heads of a ram, bull, snake and lion. Compare to the Pelasgian creation myth, *see* Cronus. Compare to the Homeric creation myth, *see* Oceanus; Pontus. Compare to Olympian creation myth *see* Aegaeon; Gaea. To compare to Hesiod's creation myth, see Pontus. *See also* Chaos; Eurynome (A); Gaea.

Phanesphoebe (Greek) *see* Rhea.

Phangnalomang (Dhammai People, India)
Phangnalomang is the worm who devoured the earth goddess Subbu-Khai-Thung and her brother, the sky god, Jongsuli-Young-Jongbu. For details, *see* Shuznaghu.

Phanus (Greek)
Phanus is the Argonaut son of the god of wine, Dionysus, and possibly Ariadne. *See also* Argonauts; Ariadne; Dionysus.

Pharmen-ma (Tibet) *see* Htamenmas.

Pheme (Greek)
Also known as: *Fama* (Roman).
Goddess of rumors.

Pheres (A) (Greek)
He is the son of the Argonaut Jason and Medea, the priestess of Hecate. His siblings are Alcimenes and Thessalus, who are twins; Argus, who was murdered, possibly by his mother; a sister, Eriopis; Medeias, who was exiled from Athens; Mermerus, who was possibly killed by his mother; Tisandrus. He was either killed by Medea when he was a child, or he was stoned to death by the Corinthians. *See also* Jason; Medea.

Pheres (B) (Greek) He is the father of Antigone, the wife of Cometes (q.v.).

Pheres (C) (Greek)
His son is Mermerus who was known for his poison-making abilities.

Pherusa (Greek)
She is one of the fifty daughters of Nereus and Doris, known as the Nereids.

Philandros (Greek) *see* Acacallis.

Philomelus (Greek)
Inventor of the wagon. His parents are Iasion and Demeter and his brother is Plutus, the god of agricultural riches. *See also* Demeter; Eirene; Plutus.

Philemon (Greek)
Philemon and his wife of many years, Baucis, were kind to Zeus and Hermes. They received special boons from the gods. At the end of their lives, Philemon was changed into an oak tree and Baucis was changed into a linden tree. *See also* Baucis.

Philinoe (A) (Greek)
She is the daughter of Iobates, the king of Lycia, and the wife of Bellerophon, who originally wanted to marry Philinoe's sister, Stheneboea. *See also* Anticleia; Bellerophon; Stheneboae.

Philinoe (B) (Greek)
Her parents are Tyndareus, the king of Sparta, and Leda. Her siblings are the Dioscuri (known as the "Gemini Twins"), Phoebe, Timandra (there is a possibility that Phoebe and Timandra are the same person), Clytemnestra and their half-sister Helen of Troy. *See also* Clytemnestra; Dioscuri; Helen; Leda.

Philippines — Creation Legend *see* Finuweigh.

Philyra (Greek)
Philyra is one of the many daughters of Oceanus and Tethys. She changed into a horse to mate with Cronus who was also in horse form. The union produced Cheiron, the immortal Centaur. *See also* Cheiron; Cronus.

Phineus (A) (Greek)
Soothsayer. Phineus is the son of the king of Tyre, Agenor and Telephassa or Argiope. His siblings are Cadmus, Europa, Phoenix, Cilix, Demodoce, Electra, Thasus and possibly Argus. He is also said to be the son of Agenor's son Phoenix, or, of Poseidon. He is a blind soothsayer and the king of Salmydessus, in Thrace. In some legends it is said that Zeus blinded him and sent the Harpies to constantly punish him for revealing the future to mortals. Other legends say that Poseidon blinded him for telling Phrixus which route to take to Colchis or Phrixus' sons the best way to reach Greece. Yet other versions say that the North Wind, Boreas, and the Argonauts blinded him because he had blinded his sons who were Boreas' grandsons. Phineus' first marriage was to Cleopatra, the daughter of Boreas and Oreithyia. They had two children who may have been Pandion and Plexippus. His second marriage was to Idaea, the daughter of king Dardanus of the Scythians. They also had two children, Mariandynus and Thynius. Idaea told Phineus that his sons by Cleopatra had raped her. Enraged, he blinded and tortured them. The Argonauts rescued the men and convinced them not to kill their step-mother. Instead, she was sent back to her father, who sentenced her to death for her apparent untruths. In variations of this myth, it is Cleopatra's brothers,

Zetes and Calais, who save Phineus from the Harpies. Or another version is that the Harpies swooped him up and carried him to the land of the Scythians, his second wife Idaea's father's territory. *See also* Aello; Boreas; Calchas; Harpies; Zetes.

Phineus (B) (Greek)
Coward. Phineus is thought to be the son of Belus, king of the Egyptians, and Anchinoe, a daughter of the Nile. His siblings are Cepheus, king of Ethiopia; Aegyptus, king of Egypt; Danaus, king of Libya; and a sister, Thronia. He was engaged to his niece, princess Andromeda, the daughter of king Cepheus. She was chained to a rock and about to be devoured by a sea monster and Phineus would not attempt to rescue her. Perseus killed him, turned him to stone, rescued the maiden and married her. *See also* Agenor (A); Andromeda; Perseus.

Phlegethon (Greek)
Phlegethon is the river of fire in the underworld, Hades. There are four other rivers in Hades: Acheron, the river of woe; Cocytus, the river of wailing; Lethe, the river of forgetfulness; Styx *see* Acheron; Cocytus; Lethe; Tartarus; Styx.

Phlegon (Greek) *see* Helius.

Phlegyas (Greek)
He was the king of Orchomenus, who was suceeded by Chryses. His parents are Ares and Chryse, or Ares and Dotis. His children are Coronis and possibly Ixion. Enraged when his daughter was raped by Apollo, he burned down the great god's temple at Delphi. In retaliation, Apollo murdered Phlegyas, sent him to the underworld, Hades, and hung a large stone over his head. (Some say he was killed by Lycus and Nycteus.) *See also* Apollo; Ares; Chryse; Coronis; Hades; Ixion.

Phobos (A) (Greek)
God of fear and terror. He is the son of Ares and Aphrodite. For a list of his siblings *see* Anteros. *See also* Ares; Harmonia (A).

Phobos (B) (Greek)
Phobos (meaning terror) is one of the four horses belonging to Ares. The other three horses are Aithon (meaning fire), Conabos (meaning tumult), Phlogios (meaning flame).

Phocus (A) (Greek)
He is the son of either Ornytion, who is the son of Sisyphus and Merope or the sea god Poseidon. His brother is Thoas. After curing Antiope of insanity, he married her. *See also* Antiope; Merope; Poseidon; Sisyphus.

Phocus (B) (Greek)
Phocus is the Argonaut son of Caeneus and brother of Priasus, who were also Argonauts.

Phocus (C) (Greek)
The son of Aeacus and Psamathe, he married Endeis, the daughter of the Centaur, Cheiron, and Chariclo and became the father of Crisus, Naubolus and Panopaeus. He was murdered by his half-brother, Peleus, his brother, Telamon, and his wife Endeis.

Phoebe (A) (Greek)
Phoebe is an epithet of the moon goddess, Artemis.

Phoebe (B) (Greek)
Phoebe, the Titan, is the daughter of Gaea and Uranus. She is sister/spouse of Coeus and the mother of Asteria and Leto. Her grandchildren are Artemis and Apollo. Her epithet is Phoebus (meaning, shining).

Phoebe (C) (Greek)
Phoebe is a half-sister to Helen and sister to the Dioscuri and Clytemnestra.

Phoebe (D) (Greek)
She was engaged to Lynceus, kidnapped by Polydeuces and married Castor.

Phoebe (E) (Greek) A Heliad, she is also known as Aegiale.

Phoebus (Roman)
Aspects or known as: *Apollo, The Bright One.*
Sun god. Phoebus was the Roman title for Apollo. He was the son of Jupiter and Latona and the brother of Diana. Apollo was not originally a sun deity but a god of medicine, music, and prophecy. In the 5th century B.C.E. he was adopted by the Romans, who hoped that his influence would help the people avert the plague. The healing rays of the sun could be considered a symbol for Apollo as Phoebus. *See also* Apollo.

Phoenician — Creation Legend (from Philos Bybios) *see* Aer; Arura; Baau (B); Chaos; Dagon (B).

Phoenix (A) *Phenix, Phoinix* (Egypt)
The Phoenix bird, the symbol of immortality, lives for five hundred years, burns in its nest, becomes ashes and is reborn, in a continuous cycle. The bird eventually ended up in Phoenicia, which was said to have been named for him. The Phoenix is possibly the same as Bennu Bird of the Egyptians (q.v.).

Phoenix (B) (Greek)
King of the Dolopians. He is the son of Amyntor and Cleobule. When his father found out that Phoenix had seduced his (the father's) concubine, he blinded him. Peleus asked Cheiron to restore his sight. *See also* Cheiron; Peleus.

Phoenix (C) (Greek) He is a lieutenant who served Achilles.

Phoenix (D) (Greek)
He may be the father of Adonis by Alphesiboea.

Phoenix (E) (Greek)
Phoenix, the son of Agenor, may be the same as Phoenix (D). *See also* Agenor (A).

Phorbas (A) (Greek)
King of Thessaly. He is either the son of Lapithus and Orsinome and brother of Periphas, or the son of Triopas and Hiscilla and brother of Erysichthon, Iphimedeia and Messene. Phorbas is the father of Actor, Augeias and possibly Tiphys. (Tiphys, the pilot of the Argo, could be the son of Hagnias.) Phorbas fought Pelops. *See also* Actor (B); Iphimedeia (A); Pelops; Tiphys.

Phorbas (B) (Greek)
A renowned boxer, Phorbas was killed by Apollo.

Phorbas (C) (Greek)
Phorbas was the lover of the god Hermes. He was a cattle rancher who led the Phrygians against the Greeks in the Trojan War. *See also* Apollo; Hermes.

www.ebook3000.com

Phorbas (D) (Greek)
The son of Argus, he later became the king of Argolis.

Phorbus (Greek)
The father of Pronoe who married Aetolus, his grandchildren are Calydon and Pleuron.

Phorcys (Greek)
Also known as: *The Old Man of the Sea.*

Phorcys, an ancient sea god, is the son of Pontus (Sea) and Gaea (Earth). His siblings are Ceto (Keto), Nereus, Thaumas, Crius, and Eurybia. Married to his sister, the sea monster Ceto, he became the father of monstrous serpent Ladon, the Gorgons, and Graiae. Ladon has also been said to be the offspring of Typhon and Echidne or self-conceived by Gaea. He was also the father of the nymph Thoosa by an unknown woman. Thoosa is the mother of the famous Cyclops, Polyphemus, by Poseidon. Phorcys may have been the father of the barking monster Scylla, by Ceto, Crataeis or Hecate and was possibly the father of monster Echidna and the Hesperides. *See also* Ceto; Cyclops; Gaea; Hesperides; Medusa; Nereus; Oceanus; Polyphemus (B); Pontus; Skylla.

Phorkos (Greek) *see* Sirens.

Phoroneus (Greek)
First king of Argos. Inventor of fire. Oracular hero. Phoroneus is the son of the river god Inachus and the ash nymph Melia and the brother of Aegialeus and Io. In some legends, Argia is said to be his mother as well as the mother of his sister, Io. He married either Laodice, Peitho or Cerdo and was the father of Niobe, Apis and Car. Niobe, who was the first mortal woman whom Zeus loved, became the mother of twelve children, eleven of whom were murdered. Phoroneus' son, Apis, by the nymph Teledice (Cinna) was killed by Telchis and Thelxion. Car became the king of Megara and inaugurated the worship of the goddess of agriculture, Demeter, in his kingdom. Phoroneus was the first person to bring a group of people together and form a marketplace. He was also the first to erect an alter to Hera in Argolis although his father Inachus was said to be the first to worship the goddess. The Argives claimed that he was the first to discover the use of fire and bring it to mortals and not Prometheus as claimed by other mythologists. They also credit Phoroneus with making Hera's armor. After death Phoroneus was retired to the Elysian Islands. Compare to the metal and bronze smith, Hephaistos. Phoroneus is said to be the counterpart of the Celtic Bran. *See also* Apis (B); Apsyrtus; Argus (A); Car; Curetes; Hera; Inachus; Meliae; Niobe (B); Prometheus.

Phra (Egypt) *see* Re.

Phra In Suen (Siam) *see* Shiva.

Phra Narai (Siam) *see* Vishnu.

Phra Naret (Siam) *see* Lakshmi.

Phra Noreai-Narayana (Cambodia) *see* Vishnu.

Phrixos (Greek) *see* Phrixus.

Phrixus *Phrixos, Phryxus* (Greek)
Deified mortal. Phrixus is the son of Athamas and Nephele, who with his sister, Helle, escaped from their wicked stepmother Ino on the back of a winged, golden ram and flew to Colchis. Only Phrixus survived. He married Chalciope, the daughter of Aeetes, the cruel king of Colchis, and became the father of Argus (who convinced Aeetes to give the Golden Fleece to Jason), Cytissorus (who helped the Argonauts capture the Golden Fleece), Melas, Phrontis and some writers mention Presbon. In some accounts, Phrixus lived a long and happy life and others say that his father-in-law Aeetes killed him to protect himself, having learned from an oracle that he would die by the hands of a foreigner. *See also* Aeetes; Argus (D); Athamas; Golden Fleece; Ino; Jason; Nephele.

Phrontis (Greek)
He is the brother of the deified mortal Phrixus (q.v.).

Phryxus (Greek) *see* Phrixus.

Phtha (Egypt) *see* Ptah.

Phuca (Celtic) *see* Puck.

Phuphlans (Etruscan) *see* Bacchus; Fuflans.

Phyag-na-rdo-rje (Tibet) *see* Vajrapani.

Phyag-na-rin-chen (Tibet) *see* Ratnasambhava.

Phyderi (Celtic) *see* Pryderi.

Phylacides (Greek) *see* Acacallis.

Phylacus (Greek)
Phylacus, the former king of Phylace, is the son of Deion and Diomede. He wed Clymene, the daughter of Catreus, the partial ruler of Crete, and became the father of Alcimede, who became the mother of the hero and Argonaut Jason and Iphiclus, also an Argonaut. *See also* Actor; Clymene; Diomede.

Phyllis (Greek)
Phyllis is the daughter of one of the kings of Thrace: Lycurgus, Phyleus or Sithon. She married Demophoon and had an affair with Acamas. For details, *see* Acamas (A).

Phylodameia (Greek) *see* Danaus.

Phylomache (Greek)
Phylomache is the daughter of Amphion and Niobe. *See also* Acastus; Amphion; Niobe.

Phyrra (Greek) *see* Eurydice.

Phytalmios (Greek) *see* Dionysus.

Phyxios (Greek) God of Escape. An epithet of Zeus.

Pi-hia Yuan-kun (China) *see* Sheng-mu.

Pi-hsia-yuan-chun (China) *Pi-hsia*
Also known as: *Kuan Yin* (Buddhist), *Princess of the Streaked Clouds, Shen Mu, Sheng-mu, Yuan-kun.*

Goddess of childbirth and women with children. She had two attendants, one who brought children, the other ensured good eyesight for them. She is the daughter of the Great Emperor of the Eastern Peak, Tung Huang T'ai I. Pi-hsia-yuan-chun is shown as a woman wearing a headdress adorned with the wide-winged birds. Pi-hsia-yuan-chun is indirectly associated with the Jade Emperor (Yu-ti). She is the same as the Buddhist deity, Kuan Yin. *See also* Tung Huang T'ai I.

P'i-Lu-Cha-Na (China)
P'i-Lu-Cha-Na is a god of light who is the same as Vairocana (q.v.). *See also* Vajrasatwa.

Pi-yusha (India) *see* Amrita.

Picus (Roman)
Demigod. Prophet. His parents are the god of agriculture, Saturn, and the nymph Venilia or Sterculus, the King of Latium (who is often identified with Saturn) and Venilia. Some say he is the twin of the ancient god of agriculture Pilumnus. The women in Picus' life are Pomona, the goddess of fruit trees and gardens, and the nymph Canens. Circe, the sorcerer with the wonderful hair fell madly in love with Picus. When he rejected her, she turned him into a woodpecker. Canens searched for him for six days. Grief-stricken when she could not find him, she dissolved in her own tears and died. Picus is the companion of Mars in his role as god of prophecy. Picus could be an aspect of Saturn. *See also* Circe; Fanus; Mars; Saturn.

Pidray *Pidrai* (Canaan, Syria, Ugarit)
She is the daughter and perhaps wife of the god of rains, Baal, and the sister of two sisters, Tallai and Arsai. Her name means "mist," and she is a nature goddess who symbolizes light. Her sister Tallai symbolizes dew and rain, and Arsai symbolizes the earth. *See also* Baal.

Pien-ch'eng (Central Asia)
One of the Ten Kings of Hell. Supervised by King P'ing-teng Tushi, he beats the guilty souls. *See also* Kshitigarbha.

Pierus (Greek) *see* Muses.

Piko-po-no-ninigi (Japan) *see* Ninigi.

Pillan *Pilan* (Araucanian People, Chile, South America)
Weather god. Thunder god. After death, tribal chiefs, assuming the form of volcanoes, were met by Pillan. Pillan's activities cause lightning and earthquakes. Pillan has many spirits of evil, known as Huecuvus, under his command, who bring drought, disease, and other disasters to mortals. The Huecuvus are shape changers. The other spirits under Pillan are the Cherruve, who look like snakes with human heads. *See also* Auchimalgen.

Piltzintecutli *Piltzintecuhtli-Tonatiuh* (Mexico, Aztec)
Also known as: *Oxomoco* (probably).
He married a woman who was made from one of the hairs of the goddess, Xochiquetzal. (This legend is the same as that attributed to Oxomoco.) Some say he was connected with Tonatiuh Metztli and Tezcatlipoca. His hair is golden. During festivals he is represented by young men climbing poles in contests. Piltzintecutli is the planet Mercury. *See also* Legend of the Four Suns; Oxomoco; Tonatiuh; Xochipilli; Xochiquetzal.

Pilumnus (Roman) Ancient god of agriculture. *See also* Picus.

Pinaka (India) Shiva's sacred bow.

Pinau (Inca) *see* Ayar Auca; Manco-Capac; Tahuauntin Suyu Kapac.

Ping-ten Tush (Central Asia) *see* Kshitigarbha; Peen-Ch'eng.

Pinga (Caribou Eskimo People, North America)
She is the guardian of animals, the goddess of souls, guardian of the souls of the living, and a healing deity. She instructs the moon-god Alignak when to return the souls of the dead to earth to be reborn. *See also* Alignak; Sedna.

Pingala (India) *see* Hariti.

Pinka *Pasupata* (India)
Pinka is Shiva's sacred trident which symbolizes his primary functions of creation, preservation, and destruction. *See also* Shiva.

Piorun (Slavic) *see* Peron; Perun.

Pipisao (South America) *see* Jukki Ajayo.

Pirrhua-Manco (Peru) *see* Manco Capac.

Pisakas (India) *see* Pishachas.

Pisasha (India) *see* Pishachas.

Pishacha-Loka (India) *see* Loka.

Pishachakis (India) *see* Pishachas.

Pishachas *Paisacha, Pisakas, Pisasha, Pishachakis* (female), *Pishachi* (female); (Brahmanic, Hindu; India)
Also known as: *Pishags* (Celtic).
The Pishachas are vicious, flesh-eating demons who are usually found hanging around burial grounds. The males are known to seize sleeping, drugged or insane women, which results in illegitimate births. Manu condemned these acts. These bloodthirsty monsters are believed to be the souls of mortals who have died violent or untimely deaths. Others say they emanate from Shiva in his angry form as Rudra. In the *Mahabharata*, they were created by drops of water from Brahma and they live in Northern India. The demon Pishacha, a daughter of Daksha, is the mother of the Pishachas and Pishachis. These demons, like the Apsaras, who originally haunted rivers and holy pools, are described as pious. The Asapishachikis are female demons who are another kind of Pishachis (female Pishachas). The Pishachas are similar to the Rakshasas but more malevolent. *See also* Apsarases; Bhutas; Darbas; Dasyus; Panis; Pratas; Rudra.

Pishachi (India) *see* Pishachas.

Pishags (Celtic) *see* Pishachas (India).

Pishumi (Acoma People, North America)
The Spirit of disease. *See also* Katsinas; Mayochina.

Pisinoe (Greek) *see* Sirens.

Pistis Sophia
(Post-Christian Gnostic. Possible remnants of worshipers associated with Marcion and Valentinus)
Also known as: *Pistis, Sophia.*
Supreme deity. Known as the "Virgin of Light," Sophia resembles the characteristics of the Asiatic goddess Astarte or the Greek Aphrodite. The doctrine of the Gnostics differs from Christian doctrine in many ways, particularly in their concepts of the life and death of Jesus. Pistis Sophia appears to follow a great deal of the Egyptian beliefs. Their version of heaven con-

www.ebook3000.com

sists of a series of spheres, one above the other. Hell follows that of the Egyptian Tuat in that there are halls with governors corresponding to the travels of Osiris through Tuat. The governors are Enkhthonin, Kharakhar, Arkharokh, Akhrokhar, Markhour, Lamehamor, Lonkhar, Arkheokh, Xarmarokh, Rhokhar, and Khremaor.

Pitamaha (India) "Grandfather." *See also* Brahma.

Pitar (India) *see* Pitri; Prajapati.

Pitri-Loka (India) *see* Loka.

Pitripati (India) *see* Yama.

Pitris (Hindu; India)
Also known as: *Pitar.*
Semi-deified, the Pitris are the souls of ancestral spirits. The living give offerings to insure that the Pitris will reside in paradise with their ruler Yama. Svadha ("Sacrifice") is their mother. Compare Pitris to Fravashi; Manes. *See also* Daksha; Prajapati.

Pitriyana (India) Path of the Fathers. *See also* Yama.

Pittheus (Greek)
King of Troezen. He is the son of Pelops and Hippodameia, the father of Aethra and the grandfather of Theseus. For a list of his siblings, *see* Pelops. *See also* Hippodameia; Theseus.

Piye-Tao (Mexico) *see* Coqui-Xee.

Place of Reeds (Aztec People, Mexico) *see* Aztlan.

Plain of Two Mists (Celtic) *see* Achren.

Plains of Ida (Teutonic) *see* Gladsheim.

Plat-eye (West Indies)
An evil spirit or ghost that often appears in the shape of a dog with captivating eyes that can envelope the victim. Sometimes only eyes are visible and the longer you stare at them the larger they become. The Plat-eye is usually seen on the night of the new moon.

Pleaser of Brethern (Egypt) *see* Qebhsneuf.

Pleiades (Greek)
Deified mortals. They are the seven daughters of Atlas and Pleione or Atlas and Aethra, who being pursued by Orion, appealed to the gods for help. Zeus transformed them into doves and placed them among the stars. Their sisters were the Hyades. One of the Hyades, Sterope, disappeared after marrying a mortal. The other Pleiades are Alcyone, Celaeno, Electra, Merope, Maia and Taygeta and possibly Calypso. *See also* Calypso; Maia; Merope; Orion; Pelops.

Pleione (Greek)
Also known as: *Aethra* (Greek).
She is the Oceanid daughter of Oceanus and Tethys. *See also* Calypso; Orion; Pleiades.

Pleisthenes (Greek) *see* Agamemnon; Helen.

Pleuron (Greek)
Pleuron is the son of Aetolus, the king of Elis, and Pronoe. His brother is Calydon (who married Aeolia). Pleuron and Xanthippe married and became the parents of Agenor (who married Epicaste) and three other children.

Plexippus (Greek) *see* Althea.

Plouton (Greek) *see* Pluton.

Pluto (A) *Plutos* (Greek)
Also known as: *Dis Pater* (Roman), *Hades* (Greek), *Mantu* (Etruscan), *Orcus* (Roman), *Pluton* (Giver of Wealth).
Underworld deity. The taciturn brother of Zeus, who placed him in charge of all the Lower World. Zeus gave him the scepter of Tartarus. *See also* Cerberus; Dis Pater; Fabruus; Hades; Serapis.

Pluto (B) (Greek)
Pluto is the daughter of Cronus, lover of Zeus and mother of Tantalus.

Plutodotes (Greek) *see* Dionysus.

Pluton *Plouton* (Greek)
An epithet of Hades as the "Giver of Wealth."

Plutus (Greek)
Also known as: *Plouton, Ploutos.*
God of agricultural abundance. He is the son of Iasion and Demeter. The goddess of peace, Pax, raised him. He was blinded by Zeus for bestowing his gifts on good and noble mortals only. Since that time his gifts are distributed indiscriminately. *See also* Demeter; Eirene.

Pneuma (Egypt) *see* Shu.

Po (Samoan; Oceanic)
Also known as: *Ao-Pouri.*
Pre-existent darkness. Po is the son of Ilu (the Firmament) and Mamao (Space). Po's sister/mate is Ao (day). With Ao, Po created two children, Rangima (Bright Sky) and Rangiuri (Night Sky). Together Po's parents were the sky. Tagaloa the Ocean god (known in Polynesia as Tangaroa) placed high rocks in strategic positions to hold the sky in place. *See also* Ta'aroa.

Po-i Ta-shi (China) *see* Kuan Yin.

Podarge (Greek)
Also known as: *Celaeno* ("blackness").
Podarge is one of the Harpies and the mother, by Boreas, the north wind, of Achilles' immortal steeds, Xanthus and Balius. Her parents are Thaumas and Electra. Her siblings are Aello and Ocypetes. *See also* Aello; Celaeno; Harpies; Xanthus; Zephyrus.

Poeas (Greek) One of the Argonauts.

Pohja *Pohjola* (Finland)
Located beyond a great whirlpool, north of Finland in the Arctic Ocean, Pohja is the home of the dead. It is ruled by Louhi, the evil sorceress. *See also* Ilmarinen; Louhi; Vainomoinen.

Pohjola (Finland) *see* Pohja.

Poko-ha-rua-te-po (Polynesia)
Night wind. One of the wives of Rangi. Their children are Ha-nui-o-rangi, Ta-whiri-ma-tea, and many wind deities. *See also* Rangi.

Pole Star (Pawnee People, North America) *see* Tirawa.

Polevik (Russian, Slavic)
Also known as: *Polevoi, Polevoy.*

Spirit of the field. If you are drunk and fall asleep in a field, a Polevik may attack and murder you. A Polevik is usually dressed in white. He may have grass in place of hair. He could appear as a dwarf with two different color eyes. The female version may be Poludnitsa, who is not as vicious. Sometimes shown in white. *See also* Leshy.

Polias (Greek) *see* Athena.

Pollux (Roman)
Pollux is the Roman name for the Greek Polydeuces. *See also* Castor; Dioscures; Leda; Polydeuces.

Polotu (Polynesia, The Tongan people)
The Underworld. Ruled by the goddess, Hikuleo.

Poludnitsa (Russian, Slavic)
Also known as: *Polednica, Poludnica, Prez-Poludnica.*

Goddess of the fields. Although she is probably related to the Polevik, she is not a murderer. Like the Leshy, she loves to misguide travelers. She particularly likes to make children get lost in corn fields. Poludnitsa is described as a lovely woman dressed in white.

Polybotes (Greek)
He is a giant son of Gaea, who is associated with the sea god, Poseidon. *See also* Gaea; Giants.

Polybus (A) (Greek)
His parents are Antenor and Theano. *See also* Acamas (B); Argus (C).

Polybus (B) (Greek)
He is the son of the messenger of the gods, Hermes. He married Periboea.

Polybus (C) (Greek)
King of Corinth. Polybus is the son of the sun god Helios. He married Merope. Oedipus is his foster child. *See also* Helios; Merope; Oedipus.

Polycaste (Greek)
She is the youngest sister of Antilochus (q.v.).

Polycaon (Greek)
First king of Messenia. He is the husband of Messene (q.v.). *See also* Iphimedeia (A).

Polydamas (Greek)
Polydamas is the son of Antenor and Theano. An Argonaut, he married Lycaste, the daughter of Priam, the last king of Troy. Father and son were accused of being traitors in the Trojan War. *See also* Acamas (B); Antenor; Priam; Theano.

Polydectes (Greek)
Polydectes is the son of the human magnet, Magnes, and a Naiad (fountain and spring spirits). The fisherman who turned king, Dictys, is his only sibling. Polydectes was supposed to be guarding Danae and her son, Perseus. He attempted to rape Danae but was stopped by Dictys. His life ended when he was turned to stone by Perseus. *See also* Acamas (B); Acrisius; Dictys; Perseus.

Polydeuces (Greek)
Also known as: *Pollux* (Roman).

One of the Dioscuri. His famous parents are Zeus and Leda and his sister is Helen of Troy. Polydeuces is the famous warrior brother (some say friend) of Castor. *See also* Amycus (A); Argonauts; Castor; Helen; Jason; Leda; Zeus.

Polydora (A) (Greek)
Polydora is the daughter of the Argonaut who killed the Calydonian Boar, Meleager, and Cleopatra, the daughter of Idas and Marpessa. *See also* Meleager.

Polydora (B) (Greek)
Her parents are Peleus and Antigone or Peleus and Polymela. Achilles is her half-brother.

Polydore (Greek)
She is one of the fifty daughters of Danaus, forty-nine of whom murdered their husbands on their joint wedding night. Her husband was Dryops. *See also* Danaus.

Polydorus (A) (Greek)
He is the son of the king of Thebes, Cadmus, and Harmonia. His parents were turned into beautiful snakes. *See also* Cadmus; Harmonia (A); Ino.

Polydorus (B) (Greek)
His parents are Priam and Laothoe or Priam and Hecuba. He could not participate in the Trojan War because of his youth. Instead, he was given a treasure to transport to Polymnester, the king of Thrace. The king murdered Polydorus for the treasure. Hecuba in turn, killed Deipylus, the son of Polymnester and Ilione (the daughter of Priam and Hecuba and is the woman who raised her brother Polydorus), and blinded Polymnester. *See also* Hecuba; Priam.

Polyeidus (Greek)
Polyeidus is a prophet. He once died and was brought back to life by Glaucus, the son of Minos. *See also* Acacallis; Bellerophon; Glaucus; Pasiphae.

Polyhymnia *Polymnia* (Greek)
She is the Muse of song. *See also* Muses.

Polyidus (Greek) *see* Polyeidus.

Polymede (Greek)
She is the daughter of the thief Autolycus and the mother of the Argonaut hero Jason (q.v.).

Polymela (A) (Greek)
Polymela, the daughter of Actor and Aegina, committed suicide when she thought her husband, Peleus, had abandoned her. *See also* Actor; Peleus.

Polymele (B) (Greek)
She is the daughter of Peleus and Polymela. *See also* Jason; Polymela.

Polymnia (Greek)
Another spelling for the Muse of song, Polyhymnia.

Polynices *Polyneices* (Greek) *see* Polynices.

Polynesia — Creation Legend *see* Ta'aroa; Vari (A); Vatea.

Polynices (Greek)
Polynices is the son of Oedipus and Jocasta (some say Eury-

www.ebook3000.com

ganeia could be his mother). He agreed with his brother, Eteocles, to be the king of Thebes on alternate years. Eteocles reneged on the agreement. The brothers fought and killed each other. Their deaths caused Adrestus to lead the Seven Against Thebes. *See also* Adrestus; Antigone; Eteocles; Oedipus.

Polypheme (Greek) *see* Jason.

Polyphemus (A) (Greek)
Giant. He is the one-eyed giant son of Poseidon and nymph Thoosa (some say the son of Uranus and Gaea) and most renowned of the Cyclops. He rivaled Acis for the affections of Galatea. When she rebuffed his overtures, he killed Acis. He captured Odysseus and twelve members of his crew, and ate two crew members a day. The remaining crew members were able to escape, after Odysseus blinded Polyphemus, by tying themselves to the underside of goats and sheep. He lived on the island of Sicily. *See also* Acis; Cyclops; Odysseus; Phorcys; Poseidon.

Polyphemus (B) (Greek)
First king of Cius in Mysia. He is the Argonaut son of Elatus of Arcadia and Hippea. His siblings are Caenis (who was born female and changed her sex to male) and Ischys, the lover of Coronis (the Thessalian princess who was unfaithful and who was subsequently killed). Polyphemus fought against the Centaurs but was later abandoned by his colleagues, the Argonauts, because he was an old man. *See also* Argonauts; Caenis; Centaurs; Coronis; Polyphemus.

Polyphontes (Greek)
He was one of the Thebans defending the city against the Seven Against Thebes. His colleagues were Actor, Hyperbius, Lasthenes, Melanippus, and Megareus. *See also* Adrestus; Megareus; Melanippus.

Polypoets (A) (Greek)
He is the blonde son of Peirithous and Hippodameia. With Leonteus, he took forty ships to the Trojan War. He was also the winner of the iron ball throwing contest at the funeral games of Patroclus. *See also* Hippodameia (B).

Polypoets (B) (Greek) His parents are Apollo and Phthia.

Polypoets (C) (Greek)
He is the son of Odysseus and Callidice.

Polytechus (Greek) *see* Aedon.

Polyxena (Greek) *see* Achilles; Cassandra.

Polyxo (A) (Greek)
She could be the mother of Deipylus (q.v.) *See also* Antiope.

Polyxo (B) (Greek)
She is the wife of Nycteus and the possible mother of Antiope.

Polyxo (C) (Greek) One of Apollo's priestesses.

Pomona (Roman)
Goddess of fruit trees and orchards. She was pursued by many suitors, including Vertumun, the god of the season. She rejected all of them. Vertumun disguised himself, returned to her and was accepted as her husband. Pomono's sacred month is September. She is comparable to the goddess of plenty, Ophs (q.v.).

Pon Okikurumi (Japan) *see* Okikurumi.

Pontos (Greek) *see* Pontus.

Pontus *Pontos* (Greek)
Also known as: *Oceanus.*
Sea deity. According to Hesiod, Pontus (the sea), Uranus (Sky), and Ourea (Hills) were created by Gaea (Earth) when time began. He is without personal attributes and is thought to be a personification of the vastness and deepness of the sea. Pontus and his mother Gaea became the parents of the sea monster Ceto, Crius, and the sea gods Nereus, Eurybia, Thaumas and Phorcys. These offspring are also attributed to Oceanus and Gaea. *See also* Ceto; Chaos; Gaea; Nereus; Oceanus.

Popol-Vuh (Maya)
"The Collection of Written Leaves." This early book compiles myths, including the creation myth, psuedo-history and later pure history of the Quiche People. It is a source of the names of many of the Mayan deities. Among the creator gods mentioned are Ajbit, Ajtzak, Alom, Bitol, Cabaguil, Chirakan-Ixmucane, Gukumatz, Hunahpu-guch, Hunahpu-utiu, Ixmucane, Ixpiyacoc, Qaholom, Tepeu, and Tzakol. Each of these deities have their own entry.

Porphyrion (Greek)
He is one of the giant sons of Uranus and Gaea. He died at the hands of Heracles. *See also* Alcyoneus; *Giants.*

Porthaon (Greek)
First king of Calydon. He is the son of Agenor and Epicaste and the father of Alcathous, Agrius, Melas, Oeneus and Sterope by Euryte. *See also* Agrius; Oeneus; Calydonian Boar Hunt; Sterope.

Portunus (Roman)
Also known as: *Melicertes* (Greek), *Palaemon.*
Portunus is the Latin name for the Roman god of harbors and ports, Palaemon.

Porus (Roman) God of plenty.

Poseidon (Greek; possibly Indo-European origin)
Also known as: *Aegeus, Genethlios, Hippios, Neptune, Neptunius* (Roman), *Neptuns* (Etruscan).
Poseidon is the Greek god of the sea. God of rivers (in Thessaly). Patron of horse racing. One of the twelve great Olympians. Poseidon is the son of Cronus and Rhea, brother of Zeus, Hades, Hera and Hestia. Swallowed at birth by his father, he was later set free by Zeus. Zeus, Hades and Poseidon drew lots and Poseidon received the sea as his domain. He took up residence in a palace in the depths of the Aegean Sea. Daily Poseidon rides through the ocean in a chariot led by sea-horses. Called the patron of horse racing, he is said to have created the horse by a blow of his trident on a rock. In classical times, Poseidon was known as Hippios, taken from *hippo,* meaning "horse." In his horse form he coupled with Demeter in her form as a mare and created many horses as offspring. The Romans called him Neptune. As Neptune he is the husband of Salacia (goddess of salt water), who was similar to Amphitrite. He was thought to have

ruled the earth but was replaced by Zeus. Don was one of the twelve great Olympians. In one myth, Laomedon asked Poseidon to assist in building the walls of Troy, and later refused to pay him. In retaliation, Poseidon sent a sea monster to devour Laomedon's daughter, but it was killed by Heracles. He desperately wanted the privilege of naming the city as did Athene. After arguing over it, they agreed that the one who could bestow the most useful gift upon the city would have the right to name it. Poseidon struck his trident into the ground and a well of water appeared (another myth says a horse appeared) but Athene summoned the olive tree to spring from the ground. She won the contest. He was an ally of the Greeks in the Trojan War. Like Zeus, he had many lovers and offspring. One of his lovers was Agamede, the wife of a sterile husband, Mulius. Agamede and Poseidon had three sons: Actor, Belus and Dictys. He is usually depicted seated in a chariot as he is drawn across the sea by horses, holding a trident in his hand (used for creating earthquakes). On his head sits a crown of marine shells and aquatic plants. An attribute of Poseidon is the destructive whirlwind, which twirls around to the left. (A whirlwind which twirls to the right has a quiet center.) The great fish Ceto was sacred to Poseidon. Some say Aegeus is a form of Poseidon. For a list of his offspring by his spouse Amphitrite (q.v.) Compare Poseidon to Sedna (Eskimo People). Compare to Varuna (India). *See also* Actor (B); Actor (C); Aegis; Aello; Aeolus (A), Aeolus (B), Agenor (A); Ajax the Lesser; Aloeides; Althea; Amycus (A); Andromeda; Antaeus; Ares; Athene; Bellerophon; Belus; Calydonia Boar Hunt; Ceto, Cronus, Curettes; Dictys; Europa; Eurydice (C); Gaea; Golden Fleece; Harpies; Hestia; Inachus; Lamia; Medusa; Minos; Oannes; Oceanus; Oenamaus; Orion; Paeon (E); Pasiphae; Pegasus; Pelasgus; Pelias, Pelops; Periboea (E); Periclymenus (B); Perimele (B); Phineus (A); Phocus (A); Phorcys; Polybotes; Polyphemus; Sarpedon (B); Scylla.

Poshaiyangkyo (Zuni People, North America)
Father of all Medicine. First Man.

Postverta *Postvorta* (Roman)
Also known as: *Carmenta, Carmentis.*
She is the goddess of the past and a prophet. Her sister, Antevorta (the future), is also a prophet. At one time, the sisters were one. Postverta is also the goddess of women's ailments and childbirth. *See also* Antevorta; Carmentis.

Postvorta (Roman) *see* Postverta.

Potamids *Potameides* (Greek)
The Potamids are nymphs who live in fountains, springs and rivers. *See also* Naiads; Napaeae; Nymphs; Oceanids; Oreades.

Potos (Phoenician) *see* Air (A); Aura.

Pou-Tai (China) *see* Hotei (Japan); Mi-Lo Fu.

Poudan (German) *see* Odin.

Pourushas (Persian) *see* Haoma.

Prabhasa (India) *see* Vasus.

Pradyumna (Hindu; India)
Also known as: *Kama* (an earlier avatar).
Sambara, the draught demon, abducted Pradyumna, the week old son of Rukmini and Krishna, and threw him into the water where he was swallowed by a fish. Sambara's housekeeper, Mayadevi, found the child inside the fish and raised him. In some renditions, the sage Narada, upon seeing the infant, informed Mayadevi that he was a god. In other accounts, it is said that when he was of age, Mayadevi told him that she was not his real mother and that she loved him. An affair ensued, they killed Sambara, and Pradyumna whisked her off to Dvarka, his father Krishna's celestial kingdom. They became the parents of Aniruddha. Pradyumna came to his end in a drunken brawl and returned to life once again as Kama. Mayadevi is an avatar of Ratri, Kama's love in his earlier life as Pradyuma, god of love. *See also* Aniruddha; Dvarka; Kama (A); Krishna; Mayadevi; Narada; Ratri; Rukmini; Sisupala (one of Krishna's demon enemies).

Prah Prohm (Cambodian) *see* Brahma.

Prahlada (Hindu; India)
Prahlada is the son of the demon king, Hiranya-kasipu. To his father's chagrin, Prahlada was devoted to the god Vishnu. This devotion caused consternation and anger to the evil demon Hirany-kasipu, who tried to kill his son and failed. Vishnu, in his avatar as Nara-Simha, the half-man, half-lion, finally killed Prahlada's father. Vishnu left the region of Patala to Prahlada, who was a kind and just king. He became the grandfather of the virtuous king of Mahabalipura, Bali. *See also* Bali (B); Daityas; Hiranya-kasipu; Nara-Simha; Patala; Vamana (Vishnu's avatar as a dwarf); Vishnu.

Prajapati (A) *Dhata, Dhatr, Pasupati* (Lord of Cattle), *Pitar, Pitri, Rudra* (Vedic, Brahmanic, Hindu; India)
In the *Rig-Veda X*, Prajapati (the Golden Embryo) is the supreme god, and creator of all. As the creator and the life force of all the gods he is the first of all gods. In the *Satapatha Brahmana*, Prajapati is produced in the form of a golden egg. When he burst from the egg, the gods Agni, Indra, Soma and Parameshthin Prajapatya were created from his breath. From his downward breath the Asuras were created, bringing forth darkness. From the tears he wiped away came the air, from the tears that fell into the primordial waters came the earth, and the tears he wiped upward became the sky. He then created all else. In one version he was created from the primeval waters and was born in one year, and said to have a life span of one thousand years. From his first words came the seasons and the worlds. He is said to have created the Asuras. By Ushas, the goddess of the dawn, he was the father of Rudra, the storm and wind deity. Prajapati's epithet "Lord of Creation" or "Lord of Creatures" was used for Brahma and occasionally Indra. The son of Brahma, Manu, was later given this title as were the seven archpriests known as Rishis: Angiris, Bhrigu, Narada, Daksha, Kasyapa, Visvamitra and Vasishtha. Prajapati worshiped the lingam and drove the chariot of Rudra in the form of Arjuna. Prajapati is associated with and possibly the same as the god Visvakarma. *See also* Agni; Arjuna; Asuras; Brahma; Brighus; Brihaspati; Daksha; Hiranyagarbha; Indra; Kama; Kasyapa; Krishna; Kurma; Manu; Purusha; Rama; Rishi; Rudra; Sarasvati; Skambha; Soma; Surya; Vach.

Prajapati (B)
Also known as: *Mahaprajapati* (India)
She is the sister of Maya, and Siddartha's aunt.

www.ebook3000.com

Prajapatis (India)
The Prajapatis are the children of Brahma who were created from his mind. They are usually considered to be the same as the Rishis and Manus. *See also* Manu; Rishi.

Prajna (India) *see* Prajnaparamita.

Prajnaparamita *Prajna* (Buddhist; India)
Also known as: *Ses-rab-kyi-pha-rol-ta-phyin-pa* (Tibet). Prajnaparamita, the goddess of knowledge and transcendental wisdom, is usually associated with Manjusri. In some versions, the effigy of Akshobhya resides inside her gown. The teachings of Prajnaparamita formed the foundations of Mahayana Buddhism. Her color is white or yellow and she is shown seated on a lotus making the gesture of teaching, sometimes holding a book or a pink lotus. Her emblems are the Buddhist rosary known as a mala, a Buddhist non-tantric symbol called the pustaka, which is made of long palm leaves, and tied with a string, and utpala, a blue lotus. In an East Java Andes site carving, she is seated on a round lotus cushion. Her hands are in the dharmacakra-mudra (raised in front of her chest). This position symbolizes the "Turning of the Wheel of the Law." A lotus stalk rises from the pedestal, and winds around her left shoulder. On the top of the lotus flower rests a book, the *Sutra of Transcendental Wisdom*. She wears a profusion of numerous necklaces and bracelets and a conical headdress. The lower part of her body is covered with a patterned *kain*. In other depictions she is shown with four arms. *See also* Akshobhya; Manjusri; Namasangiti; Sarasvati.

Prakriti (Brahmanic, Hindu; India)
She is the mother of Brahma as the personification of nature. *See also* Purusha; Shakti.

Pralamba (Hindu; India)
Pralamba is an Asura who in the shape of a giant elephant was killed by Bala-Rama. *See also* Asuras; Bala-Rama.

Pramadvara (Hindu; India)
Pramadvara is the wife of Ruru, a giant Danava (q.v.).

Pramantha (India) Hindu fire god.

Pramati (India) *see* Agni.

Pramlocha (India) *see* Pramloka.

Pramloka *Pramlocha* (Hindu; India)
Pramloka, an Asparasa, was sent by Indra or Kama to distract the sage Kandu from his practice. She became pregnant and gave birth to the goddess of dew, Marisha. After being with Pramloka for nine hundred and seven years, six months and three days, which seemed like one day to Kandu, she left him. Pramloka spent the rest of her time swinging from tree to tree as a tree nymph. *See also* Asparases; Indra; Kama (A); Marisha.

Pramzimas (Lithuania)
Supreme deity. Pramzimas sent the giants Wandu (the wind) and Wejas (the water) to destroy mankind because of its wickedness. There were still a few pious mortals living, so he repented and saved them in a nut shell.

Prasena (India) *see* Syamantaka.

Prasetas (India) "Supremely Wise." *See also* Varuna.

Prasni (India)
Prasni is a cow goddess who is known as the "Goddess of the Dark Season." *See also* Maruts.

Prasuti (India)
She is the daughter of Manu who married Daksha, the early Vedic god. *See also* Daksha.

Pratas (India) *see* Pishachas.

Pratyusha (India) *see* Vasus.

Pravuil (Hebrew) *see* Nabu.

Praxidice (Greek)
Goddess of justice. *See also* Dike; Themis.

Praxithea (A) (Greek)
She is one of the fifty daughters of Thespius. She and forty-eight of her sisters slept with Heracles in one night. Praxithea became the mother of Lycurgus as a result of her union with Heracles. One sister remained a virgin.

Praxithea (B) (Greek)
Erichtonius is her husband and Pandion, the king of Athens who died heartbroken when his daughters turned into birds, is her son.

Precht (Teutonic) *see* Bertha.

Preng-ta-ma (Tibet) *see* Mala.

Presbon (Greek)
Presbon is the son of Phrixus (who is the son of Athamas and Nephele) and Chalciope (the daughter of Aeetes, the king of Colchis and the nymph Asterodeia). Presbon is the father of Clymenus, who became the king of Boeotia. *See also* Phrixus.

Preta-Loka (India) *see* Loka; Pretas.

Preta-Raja (India) King of the Ghosts. *See also* Yama.

Pretas *Yi-dvag* (Tibet); (Hindu, Buddhist; India, Tibet)
The Pretas, spirits of dead persons, often called hungry ghosts, inhabit Preta-Loka, the realm of tortured spirits also known as the ghost world. They committed wrongful deeds in a former life and have been sentenced to the circle of perpetual hunger. The Pretas are sometimes said to be goblins who travel in groups and who haunt graveyards. Comparable to the Gaki (Japan). *See also* Bhutas; Loka; Yaksha; Yakshinis.

Priam (Greek)
Also known as: *Podarces*.
"Ransomed." The father of fifty sons, and twelve daughters (some say he had fifty daughters), he was the last king of Troy. Too aged to fight during the Trojan War, he was killed by Pyrrhus. *See also* Acamas (A); Achilles; Amazons; Cassandra; Hesione.

Priamus (Teutonic) *see* Thor.

Priapos (Greek) *see* Priapus.

Priapus (Greek)
Also known as: *Fecundus, Mutunus, Priapos.*

Fertility god. God of fruitfulness. God of gardens, bees, vines, sheep and goats. Priapus is the son of Dionysus and Aphrodite, although some say his father is Hermes. Despite the beauty of his parents, he was born ugly and deformed. He became obsessed with Lotis, the daughter of Poseidon. He chased her until she was changed into a lotus tree. Priapus is identified with Hermes and Pan. His sacrificial animal is the lamb. Statues of Priapus are usually made of red painted wood. He is shown with unusually large sexual organs. *See also* Adonis.

Priapus (B) (Greek)
He is the son of Caeneus and brother of Phocus. The three men are Argonauts.

Primigenia (Etruscan, Roman) *see* Fortuna.

Primordial Hill (Egypt) *see* Ogdoad, The.

Prince Cataract (Japan) *see* Taki-tsu-hiko.

Prince Millet (China) *see* Ho-Chi.

Prishni (India) *see* Prisni.

Prisni *Prishni* (India)
She is the Cow Goddess also known as the Goddess of the Dark Season. *See also* Maruts; Rudra.

Pritha (A) (India)
Mother of the Pandavas. *See also* Kunti; Pandavas.

Pritha (B) (India) *see* Kunti; Prithiva.

Prithi (India) *see* Prithiva.

Prithiva (Hindu, Vedic; India) *Pritha, Prithi, Prithive, Prithivi,* (Earth), *Prthivi.*
Also known as: *Dyaus-Pita* (Sky Father), *Dyaus-Pitri, Dyava-Matar* (Earth Mother), *Dyavaprithivi, Dyavaprthivi* (Sky and Earth).

In the Vedas, Prithiva, the earth and personification of fertility, is the wife of Dyaus (heaven or the sky) and the mother of the great storm god Indra and Agni, the god of fire. Her daughters are the goddess of dawn Ushas and Ratri. She may have been the daughter or wife of the sage Prithu, and possibly the wife of the rain god Parjanya. When Indra was born miraculously from her side, the heavens and earth shook in fear. Prithiva and the other gods were also frightened. Fearing that Indra would be the harbinger of great changes in the divine order and possibly the cause of their destruction, Prithiva hid him away and ignored him. Prithiva and Dyaus were invoked separately or as a couple known as Dyavaprithivi. (*See* above for variations of the name.) They are thought of as the parents of the gods and of mortals. The Vedic gods, considered close to nature, are represented by astronomical bodies and the weather. They are divided into gods of the sky, gods of the atmosphere and gods of the earth. Examples of sky gods are Mitra and Varuna; gods of the atmosphere, Indra and the Maruts; gods of the earth, Agni and Soma. It is thought by some writers that Prithiva was either male or androgynous. In this case, she would be addressed or invoked by the name Dyaus-Pita (Sky-Father). Prithiva is depicted as a cow and Dyaus as a bull. In Vedic cosmology, heaven and earth represent a dual world, known as Rodasi. Between heaven and earth is Antariksha, the atmosphere, where gods and demons struggle for supremacy. Apas, the celestial waters, lay beyond Antariksha, as does the Sun world, Swar. The great heaven of the gods is known as Rochana. Prithiva is associated with the solid state of matter. Her colors are orange-red and yellow. In some traditions, her color is yellow and her symbol is a yellow square. Prithiva corresponds closely to the earth goddess Bhumi (also known as Bhu, Bhumidevi, Bhu-devi), said to be a wife of Vishnu (q.v.). She is comparable to the sow and earth goddess Sukarapreyasi. Compare to Gaea (Greek). *See also* Agni; Devas (A); Dharti Mai Parjanya; Dyaus; Indra; Kunti (also known as Pritha); Lokapalas; Maruts; Ratri; Soma; Ushas; Varuna.

Prithive (India) *see* Prithiva.

Prithivi (India) *see* Prithiva.

Prithu (India) *see* Prithiva.

Priti (India)
She is thought to be one of Daksha's daughters and is one of the spouses of the god of love, Kama. *See also* Daksha; Kama; Rati; Vishnu.

Priyadarsana *Riyadarshana* (India) *see* Mahavira.

Prodromes (Greek)
After death, the twins Zetes and Calais, sons of the north wind, Boreas, and the river nymph Oreithyia, were turned into the Prodromes, winds from the northeast. *See also* Zetes.

Proetus (Greek)
Proetus is the son of either Abas and Aglaia or Ocaleia, and he was the twin brother of Acrisius. Proetus and Acrisius began quarrelling before birth. Abas gave his sons the kingdom of Argos but during a bitter dispute Acrisius expelled Proetus, who fled to Lycia and married the daughter of Iobates, Antea (also called Stheneboea). With the assistance of Iobates, during a bitter battle at Epidaurus, Proetus regained his share of Argos. Shields were thought to have been used for the first time during this conflict. The goddess Hera was said to have cast a spell causing insanity on Proetus' daughters, Lysippe, Iphinoe and Iphianassa. The infliction was passed to the other women of the kingdom. Proetus offered Melampus, a Messenian seer, a large portion of his kingdom to cure them. He sent a group of strong men who created loud noises and chased the women to Sicyon. During the chase all the women were healed except Iphinoe who died. Proetus' wife fell in love with Bellerophon, who had come to Proetus to be purified, but he declined her advances. Scorned, she told Proetus that Bellerophon had attempted to seduce her and demanded that her honor be defended. Proetus had Bellerophon deliver a sealed letter to Iobates asking him to slay Bellerophon. *See also* Abas (A); Acrisius; Aglaia; Aristaeus; Bellerophon; Danae; Iobates; Iphinoe; Lysippe; Melampus; Perseus; Stheneboea.

Promachus (Greek)
His parents are Aeson and Alcimede (or possibly Polymede). He is the brother of Jason, the Argonaut, who was killed by Pelias, the king of Iolcus. *See also* Jason; Hippolyte (B); Pelias.

Prometheus (Greek)
Creator. Seer. Inventor of architecture, astronomy, medi-

www.ebook3000.com



The Lower Brain consumes less energy and can do a lot of daily work, like send and receive impulse records and experience and respond to emotions. When you lower down the Upper Mind, it will also lower the blood pressure and anxiety.



Fig. 3.21 *Abdomen has it own Brain: the Awareness Mind.*

On the second page of the Times' article, it says that even the large intestine is loaded with neurons. The question was posed, 'Can it learn?' But I say, "Hey, this goes back to 4,700 years of the Tao practice, which says: Train all the organs; train them how to do different things." You can rest the head brain when you're not using it – and use the brain in the gut. Why is it so important? Because the head brain is a 'monkey mind' riddled with doubt, shame, guilt and a suspicious mind. It is always thinking. Worrying, figuring things out things, head trips – it just keeps on, all the time. To be a God, you must let go of the past and empty the mind. Now we are in the information age; anything flits in – we think. Just one word flits in and we start an entire string of thought. When somebody says one bad word to you, you can think and figure it out for three days and three nights. 'How am I going to get revenge?
How am I going to get revenge?'

Scientists have discovered that when people worry too much, thinking, planning, etc., this brain actually uses up a lot of energy. Depending on the type of person– some people are very physical types who use very little brain energy, but their physical body consumes a lot of energy. However, most people think and think and think. So the scientists give an approximation, by way of a percentage. This is just a number for comparison, not an exact number. They say that this brain in the head can use up to 80% of the body's energy. So, what happens is you have only 20% left for the organs.



Fig. 3.22 *Cross-section of the neurons in the Large Intestine.*

According to the information about the brain in the gut, they have discovered that the brain in the head and the brain in the gut can do some similar jobs. For example, this brain in the gut is the emotional and the feeling brain. In the west you have the exprescine, writing, metal-work. He is the Titan son of Iapetos and Clymene (also known as Asia) or Gaea and brother of Atlas and Epimetheus, (some say Menoetius). His wife is Hesione, though others say she was Pandora or Pyrrha. Hesione or Pronoea became the mother of his son Deucalion. This son and his wife Pyrrha survived the great nine day Deluge that extinguished all others on the earth. Prometheus stole sacrificial fire from the heavens to give to mortals. When Zeus found out, he chained Prometheus to a rock on Mount Caucassus. Daily, an eagle or a vulture would stop by and feed on his liver, which fortunately regenerated. Finally, Heracles rescued him. In other renditions, Prometheus stole the fire from the hearth of Zeus, or the workshop of Hephaistos, or from the fiery chariot of the sun. He is sometimes credited as being the artist who shaped men and beasts from clay. According to Hesiod, Clymene was the mother of Prometheus, Menoetius, Epimetheus and Atlas. *See also* Achaeus; Aeolus (A); Deucalion; Epimetheus; Hephaistos; Oceanids; Pandora; Themis.

Pronax (Greek)
He is the son of Talaus and the father of Amphithea and Lycurgus. *See also* Adrestus; Amphithea; Talaus (for a list of siblings).

Prontis (Greek) *see* Phrixus.

Proserpina *Proserpine* (Roman)
Also known as: *Persephone* (Greek).
Queen of the underworld. *See also* Demeter; Hecate; Isis (Egypt); Persephone.

Proserpine (Egypt) *see* Proserpina.

Proteus (A) (Greek)
King of Egypt. He was the second husband of Psamathe and the father of Cabeiro, Theoclymenus and Theonoe. There is a possibility that he is the same as Proteus, known as the Old Man of the Sea.

Proteus (B) (Greek)
Old Man of the Sea. His parents are Oceanus and Tethys. He is a prophet and shape-changer who herded sheep for Poseidon.

Protogeneia (A) (Greek)
She is the daughter of Aeolia and Calydon. *See also* Aeolus (A); Ares.

Protogeneia (B) (Greek)
Deucalion and Pyrrha are her parents. She became the mother of Opus by Zeus.

Protogonos (A) (Greek) *see* Phanes.

Protogonos (B) (Phoenician) *see* Kolpia.

Prthivi (India) *see* Prithiva.

Pryderi (Celtic)
Also known as: *Phyderi.*
Originally a fertility lord. Later, ruler of the dead. Pryderi began life as Gwri, the son of Rhiannon and Pwyll. When he was an infant, he was grabbed from his cradle by an otherworldly monstrous claw. The household staff made it appear as though his mother was responsible. She was severely punished. One evening as Teirnyon Furf Liant was attending his mare who was about to give birth, the same claw attempted to snatch the foal. Teirnyon was able to drive it away. Pryderi, hiding in the stable, cried out to Teirnyon. The man saved the child and raised him as his own. In later years, he realized that the young man looked like his natural father and so returned him to his birth parents. Eventually, he married Cigfa (Kicva), the daughter of Gwyn Gohoyw. One day while hunting with his stepfather he managed to get stuck to a golden bowl and was spirited-away to the Otherworld. In a variation of this myth, he is with his mother and they enter a magic castle and are both trapped. In each case, his stepfather, Mananwydan ap Llyr, an ingenious man, rescues him. Pryderi also accompanied the giant Bran when he went to rescue his sister Branwen. He was one of the seven who survived the battle. Gwydion, the son of Don the Enchanter, stole Pryderi's pigs. A fight followed and the thief killed Pryderi who then became a lord of the Underworld. Compare to Zeus and Romulus, both taken from their mothers as infants (as was Moses). *See also* Gwydion; Mananwydan ap Llyr; Rhiannon.

Psamathe (Greek)
Psamathe is the Nereid daughter of Nereus and Doris. She changed the amorous Aeacus, king of Aegin and son of Zeus, into a seal when he would not stop pursuing her. They had a child, Phocus. Aeacus died and became a judge in the otherworld. Psamathe remarried Proteus, the king of Egypt. *See also* Aeacus; Phocus; Proteus.

Psedjet (Egypt) *see* Ennead, The.

Psyche (Greek)
Psyche is a nymph who personifies the human soul and immortality. Eros, the god of love, married her. He visited her nightly, concealing his features from her and leaving before dawn. Contriving to see him, she lighted her lamp one night and was enraptured by his beauty. When he was awakened by a drop of oil which fell on his face from the lamp, he fled, and she wandered in search of him. The goddess of love, Aphrodite, was furiously jealous and tried to thwart the lovers. Eros' prayers to the gods were answered and Psyche ultimately joined him on Mount Olympus. Compare Psyche to the Indian Urvasi. *See also* Aphrodite; Eros.

Ptah *Phtha, Pthah* (Egypt)
Also known as: *Naunet, Nun.*
Ptah was known as "the Ancient One." He is the son of Nun, husband of Sekhmet and the father of Nefertem. At Memphis, he coalesced with Ta-tanen and Sokar. Ptah was an important god, and his name was sometimes combined with other gods. Ptah-Osiris, Ptah-Seker, Ptah-Seker-Osiris, Ptah-Seker-Tem, Ptah-Hap, Ptah-Nun, and Ptah-Tatenn (or Tenen). One of the Triad of Memphis which consisted of Ptah, Sakhmet and Nefertum. His masculine aspect was Nun, and Naunet was his female aspect. The invention of the arts are attributed to him. In the Pyramid Age he was a creator god. His creative power was said to have been manifested in every heartbeat and every word. Like Khnum he was said to have created all beings on a potter's wheel. In the Late Period, he became a composite deity, Ptah-Sokar-Osiris, having incorporated the nature of *Osiris* and

Sokar. Short of stature, he is often mistaken for a child. He is sometimes shown as a bearded man with a tight cap and garments with the Menat (weight) hanging from the back of his neck. Depictions of the Late Period often show him with female breasts and he has been represented as a standing mummiform figure with tall plumes on his head. His holds a scepter. Compare Ptah to Hephaistos (Greek). *See also* Apis (A); Astarte; Khnum; Khonsu; Naunet; Nun; Osiris; Sekhmet.

Ptah-il-Uthra (Gnostic) *see* Abathur.

Ptah-Sokar-Osiris (Egypt) *see* Osiris; Ptah; Sokar.

Ptous (Greek)
He is the brother of Athamas and Themisto (qq.v.)

P'u-hien (China) *see* Samantabhadra.

P'u-hsien (China)
Also known as: *Pushan.*
The name P'u-hsien was given to the Vedic sun-god Pushan in Chinese mythology. *See also* Kuan-yin; Pushan; Ta-Shih-Chih.

Pu-sa (China) *see* Bodhisattvas.

Puchan (India) *see* Pushan.

Puck (Celtic)
Also known as: *Phouka, Phuca Pwakas, Pwalso.*
A spirit. The Irish Phuca is an evil spirit who appears as a demon horse. The British Puck is a mischievous elf. The Pwakas are good natured trolls. All analogous to the Pixy or Fairy.

Pueblo People — Creation Legend (North America) *see* Awonawilona; Sussitanako.

Pueo-nui-akea (Hawaii)
Owl god. Guardian. He is an owl god who brings life to the souls who are wandering on the plains.

Puka-buti-no-midu-yare-pana-no-kami (Japan) *see* Kushi-nada-hime.

Pukkeenegak (Eskimo People, North America)
Goddess of childbirth and clothing. Pukkeenegak procures food for her worshipers. She appears with her face tattooed, big boots on her feet, clad in a pretty dress.

Pukku (Babylon)
The sacred drum given to Gilgamesh by Ishtar.

Pukwudjies (Ojibwa People, North America)
Fairy people who inhabit the forests.

Pukys (Slavic) *see* Krukis.

Pulah (Finnish) *see* Puleh.

Pulastya (India)
He is the grandfather of the demon Ravana. *See also* Rakshasas; Ravana.

Puleh *Pulah* (Finno-Ugric, Russian)
Messenger. Puleh is the son of the writer of fate, Kaba. He is similar to Nabu and Thoth. *See also* Kaba.

Pulinda and Pulini (India)
Children of Kuvanna the Yakshini. *See also* Yakshini.

Puloma (India) *see* Daksha; Danavas.

Puloman (India) *see* Indra.

Pun-Gel (Australia) *see* Bunjil.

Puna (Polynesia) *see* Tii Tokerau.

Punchau (Inca People, Peru)
He is a sun god who is depicted as a warrior armed with darts. He is comparable to Epunamun (Araucanian).

Pund-Jel (Australia) *see* Pundgel.

Pundarika (India) *see* Dikpals; Lokapalas.

Punoduno-no-kami (Japan) *see* Kushi-nada-hime.

Punyajana (India) "Friendly Folk." *See also* Yaksha; Yakshini.

Pupa-no-modi-kunusunu-no-kami (Japan) *see* Kushi-nada-hime.

Puramdara (India) *see* Indra.

Purandhi (India) Goddess of Plenty.

Purbutty (India) *see* Devi; Parvati.

Puripais (Greek) *see* Dionysus.

Purohita (India)
The family priest of the gods. *See also* Brihaspati.

Purrishram (India) *see* Parashur Rama.

Purrunaminari (Maipuri, Orinoco People, South America)
Creator deity. According to myth Taparimarru, the wife of Purrunaminari bore a son named Sisiri by virgin birth. Purrunaminari has the title of "He Created Men." *See also* Kururumany.

Purukupali (Aborigine People, Australia)
Creator god and god of death. Angered because his wife Bima had allowed his son Jinini to die, he beat her and her lover, Japara. With Jinini, he walked into a whirlpool to die. He decreed that all must die because of this incident. Japara partially escaped the decree by changing himself into the moon. The scars of the beating he received still show on his face. He still has to die for three days, but is returned to life each month. For another version of the moon myth, *see* Alinda.

Purusa (India) *see* Purusha.

Purusha *Parusha, Purusa* (Brahmanic, Vedic; India)
Also known as *Ambika, Brahma, Viraj.*
In the Vedic tradition, Purusha, the "Primal Man," is a cosmic giant with a thousand heads who was sacrificed by the gods to create the universe. His heads became the sky, his feet the earth, his navel the air. His limbs produced mortals. Later, in the Brahmanic tradition, Purusha, meaning "person," was known as the first man and was the physical manifestation of Brahma. After floating on the primeval waters for a thousand years, he broke out of the golden cosmic egg. Fearful and lonely, the lord of the universe divided himself into a male and female half and created Ambika (also known as Viraj) and proceeded to create offspring. Next in the form of a pair of cattle, they created cattle and the cattle created offspring. The same steps were followed to create all living creatures in the universe. He

www.ebook3000.com

destroyed all sins by fire. Purusha is described as having a thousand eyes and a thousand feet which encompass the earth on every side. Symbolically, Purusha lives in the heart of every individual and Purusha fills the cosmos. Purusha represents the male force which is opposed to but unites with Prakriti, the female force (Nature), to form creation. Purusha as the grand sacrifice, who was sacrificed by the gods to create the world, stresses the importance of sacrifice as a creative event. Compare Purusha to Narayana. This creation myth is from the *Rig-Veda X*. For another creation myth from the same source, *see* Prajapati. *See also* Adam; Adhibuddha; Brahma; Buddha; Narayana (B); P'an Ku (China); Sarasvati.

Purvachitti (India) *see* Apsarases.

Purvadevatas (India) *see* Devis.

Pusa (European) *see* Hotei (Japan).

Pusait (Lithuania, Prussia)
Spirit. Pusait is a wood spirit who hides under lilac-bushes. Little dwarfs called "kaukis," bring him food from the house.

Pusan (India) *see* Pushan.

Pushan *Puchan, Pusan* (Hindu; India)
He is the son of Aditi and lover of his sister, the sun goddess Surya. A solar deity, Pushan was known in later times as an Aditya. A god of growth, he is the restorer of what is lost, guardian of roads and of cattle, and guardian of the dead. He presides over love and marriages and protects travelers. Known as a wonder-worker, Pushan motivates, invigorates and provides abundance, including food for all living things. He was the discoverer of soma, the elixir of the gods, according to some renditions and the husband of Rohini. He drives a chariot drawn by male goats, carries a golden lance, awl or goad. Because he does not have teeth (they were kicked out by Shiva), he eats offerings of mush. Pushan shares traits similar to the Asvin twins (q.v.). Compare to Thor (Norse) and Dagda (Celtic). *See also* Aditi; Adityas; Daksha; Martanda; Parvati; Savitri (A); Soma; Surya.

Pushpa (India) *see* Pushpema.

Pushpa-danta *Pushpadanta* (India)
Elephant guardian of the northwest. *See also* Dikpalas; Lokapalas; Vayu.

Pushpadanta (Nepal) *see* Pushpa-danta.

Pushpaka (India)
The celestial chariot. *See also* Kuvera; Ravana.

Pushpema *Me-tog-ma* (Tibet), *Pushpa* (India)
She is a goddess personifying blossoms. *See also* Mamaki.

Puspa (Tibet) *see* Akshobhya.

Putan (Micronesia)
Putan and his sister created everything from parts of their bodies. Some say it was Putan who instructed his sister to create everything from his body after he died.

Putana (India)
A fifteen foot female demon with poisonous breasts. She is the daughter of Bali and sister of Bana. *See also* Bali (B); Bana; Krishna.

Pwalso (Celtic) *see* Puck.

Pwyll (Celtic)
Also known as: *Pwyll Pen Annwn* (Welsh).
Pwyll, who inadvertently insulted Arawn, the ruler of Annwn, the underworld, changed bodies with him for a year. During this period, he overcame Arawn's enemy, Hafgan, and was rewarded with the title "Lord of Annwn." In a lengthy epic, Pwyll married Rhiannon, a fertility goddess. They had a son originally named Gwri, later known as Pryderi. Tragedy visited their home and life changed drastically for the happy couple. Regarding his marriage to Rhiannon, *see* Rhiannon. For information about the relationship between Pwyll and Arawn, *see* Arawn. *See also* Achren; Annwvyn; Pryderi.

Pwyll Pen Annwn (Celtic) *see* Pwyll.

P'yag-na-rdo-rje (Tibet) *see* Vajrapani.

Pyerun (Slavic, Russian, Polish) *see* Perun.

Pygmalion (Greek)
Sculptor. King of Cyprus. Although Pygmalion was a misogynist, he created the statue of a beautiful woman and fell in love with it. Aphrodite took pity on him for the way he loved the statue, named Galatea, so she gave it life and they became parents of a son Paphos. Pygmalion also has a daughter, Metharme.

Pylades (Greek)
He is the son of Strophius and Anaxibia. He married Electra (also known as Laodice), the daughter of Agamemnon and Clytemnestra, and became the father of Medon and Strophius II. *See also* Aegisthus.

Pylus (Greek)
Pylus is the son of the god of war, Ares, and Demonice, who is the daughter of Agenor and Epicasta. *See also* Ares.

Pyracmon (Greek) *see* Acamas (D); Cyclops.

Pyrene (Greek)
Pyrene could be the mother of Cygnus by Ares (q.v.).

Pyriphlegethon (Greek) *see* Phlegethon.

Pyroeis (Greek) *see* Helius.

Pyrrha (A) (Greek)
Achilles was named Pyrrha when he lived as a woman. *See also* Achilles; Deucalion; Epimetheus.

Pyrrha (B) (Greek)
Pyrrha was the first woman. She is the daughter of Epimetheus and Pandora. *See also* Epimetheus.

Pyrshak-Khan (Altaic, Tartars) *see* Bai Ulgan.

Pythagoras (Greek) *see* Abaris.

Pythia (Greek) *see* Artemis.

Python (Greek)
Python is the famous serpent of the cave of Mount Parnassus, slain by Apollo. *See also* Apollo; Leto.

Q

Qabauil (Central, South America) *see* Huracan.

Qadesh *Kadesh, Quedesh, Qetesh* (Hittite, Semitic)
Aspects or known as: *Hathor* (Egypt), *Qadishtu, Qodshu.*
Fertility goddess. Goddess of love. She was the consort of Amurru (Reshef). She is thought to be of Syrian origin and as Kadesh, *the ancient* Hittite goddess, she is an aspect of Astarte and is known as the patroness of prostitutes and the holy one. Sacred prostitution rites were carried out in her cult. As the Egyptian Qetesh, she is depicted nude, holding flowers, standing on the back of a lion, sometimes facing the viewer. As Qadesh (the "holy"), called Anat, she is shown naked, standing on a lion and holding a weapon, between the Egyptian fertility god, Min, and the Canaanite god Resheph. Qadesh is comparable to the Persian Anahita and the Phoenician Anat (who is also called Quadesh). *See also* Aleyin; Allat (patroness of prostitutes); Amurru; Anahita; Anat; Astarte; Hathor; Min; Resheph.

Qadishtu (Egypt) *see* Qadesh.

Qaholom (Maya People, Yucatan) *Cajolom*
Also known as: *Hunahpu, Hunahpuutiu.*
Creator. One of the four original regents who created earth. At the time of the third creation attempt, he was made into two gods, Qaholom and Hunahpu. They were joined by the fabricating gods Ajtzak and Ajbit. *See also* Alom; Hunahpu; Popol-Vuh.

Qahootze (British Columbia, Native North American)
A supreme deity.

Qamaits (Bella Coola People of North America)
Also known as: *"Afraid-of-nothing," "Our Woman."*
Sky deity. A goddess of one of the upper heavens. Some think she is a goddess of war. She rarely visits earth and when she does sickness and death result. The Bella Coola pray to her subservient gods, Senx (the sun, called "Our Father") and Alkuntam, who created man.

Qasavara (Melanesia)
Evil spirit. Spirit opponent of Qat. A cannibal ogre who kills and stores Qat's brothers in a chest. Qat burns Qasavara in his home, and revives his brothers by blowing through a reed in their mouths. *See also* Qat.

Qat (Melanesia)
Also known as: *Quat* (New Hebrides).
A creator spirit. He created three men and three women from a tree, then hid them for three days. He gave them life by dancing and drum beating. In another tale, he created men from clay and women from plaited fronds of sago-palms. He is also credited with creating various animals and purchasing night from I'Qong (Night) who also taught him how to make dawn. His evil counterpart is Marawa. Qat has eleven brothers all named Tangaro. In some tales Qat is opposed by his brothers. In some it is Marawa who is his opposition. Some feel Qat is the counterpart of the Polynesian deity, Maui. More likely he is closer to Nareau. *See also* Marawa; Maui.

Qeb (Egypt) *Geb, Keb.*
Also known as: *Qebeb, Qebk, Seb.*
High god. He is the husband of Nut and father of Isis, Nephthys, Osiris, and Set. Qeb is known as the "Great Cackler" who laid the solar egg. He is shown with the head of a goose. The Greeks identified Qeb with Cronus. *See also* Isis; Nephtys; Osiris; Set.

Qebehsennuf (Egypt) *see* Qebhsneuf.

Qebh-sennuf (Egypt) *see* Qebhsneuf.

Qebhet (Egypt)
Also known as: *Qebhut.*
Qebhet, the goddess of cool water, is the daughter of Anubis.

Qebhsnauf (Egypt) *see* Qebhsneuf.

Qebhsneuf *Kebehsenuf, Kebhsnauf, Qebehsennuf, Qebehsenuf, Qebh-sennuf, Qebhsnauf, Qebsnuf* (Egypt)
He is one of four divine sons of Horus and Isis. A hawk-headed god, he guarded the intestines, specifically the liver and gall bladder, in the Canopic vases. He was also the guardian of the west. His name means "Pleaser of Brethren." *See also* Amset; Hapy (A); Horus; Isis; Tuamutef.

Qebhut (Egypt) *see* Qebhet.

Qebsnuf (Egypt) *see* Qebhsneuf.

Qebui (Egypt)
God of the north wind. He is shown as a four-headed ram with four wings, or as a man with four ram heads.

Qeften (Egypt) *see* Aani.

Qererti (Egypt) *see* Aai.

Qerhet (Egypt)
Goddess of nomes. She is a serpent goddess, who is the patron of the eight nomes of Lower Egypt.

Qerti (Egypt) *see* Assessors.

Qetesh (Egypt) *see* Qadesh.

Qodshu (Egypt) *see* Qadesh.

Q're (Pelasgian)
Another spelling for Car, the ancient solar god of Syria. *See also* Car.

www.ebook3000.com

Qu-ba (Egypt) *see* Aai.

Quaayayp (Pericu People, Native North American)
Also known as: *Man.*
Teacher. Son of Niparaya and Amayicoyondi. Brother of Acaragui. Known as a great teacher who had many servants. It is said that he was murdered. Although dead, he still bleeds. He doesn't speak so an owl speaks for him. Quaayayp is opposed by Wac or Tupuran, who was evil.

Quadriga (Greek)
Quadriga is the name of the chariot driven by Helios, the sun, as he traverses the sky daily. *See also* Helios; Phaethon.

Quajaip (Mexico)
Also known as: *Possibly Metipa.*
Culture hero. Little information, but may have been a Christianized version of Jesus, since he was killed by the people and a wreath of thorns was placed on his head. May be related to another dying deity named Metipa.

Quakuinahaba (Mojave People, Native North America) *see* Cathen.

Quartiana (Roman) *see* Febris.

Quechua People — Creation Legend (Bolivia, Souther America) *see* Dohitt.

Quedesh (Egypt) *see* Qadesh.

Queen of Battles (Sumer) *see* Inanna (A).

Queen of the Dead (Nigeria; Africa) *see* Ala (B).

Queen Mother of the West (China) *see* Hsi Wang Mu.

Queen Mother Wang (China) *see* Wang-mu-niang-naing.

Quetzal-Coatl (Mexico) *see* Quetzalcoatl.

Quetzal-Cohuatl (Mexico) *see* Quetzalcoatl.

Quetzal-Koatl (Mexico) *see* Quetzalcoatl.

Quetzalcoatl *Kuetzal-Koatl, Kwetzal-Koatl, Quetzal-Coatl, Quetzal-Cohuatl, Quetzal-Koatl,* (Mexico, Aztec, Toltec, Maya)
Also known as: *Ce Acatl Quetzalcoatl* "One-reed Quetzalcoatl," *Ehecatl, Itztlacoliuhqui, Kukulcan* (Maya), *Omecutli-Omeciuatl, Ometecutli, Quetzalcoatl-Ehecatl, Quetzalcoatl-Xolotl, Tlahuizcalpantecuhtli, Tlauixcalpantecuhtli, Tohil-Heumac, Yolcuatl.*
"Feathered Serpent." Supreme deity. God of air, clouds and wind. God of medicine and the healing arts. God of fertility and wealth. God of thieves. God of gambling. God of fishermen. Messenger of the gods. Patron of farmers, planters, gardeners and others who work with the soil. Patron of stone engravers and cutters and of builders. Patron of gold and silversmiths and of all who work with metal. Inventor of books and writing. Inventor of the calendar. Of Toltec origin, he is the son of Ometecuhtli and Omeciuatl. Quetzalcoatl and Xolotl, his raggedy-eared dog and double and sometimes called his twin, journeyed down to the underworld, known as Mictlan, to steal the bones of mortals from a previous generation. Although Mictlantecutli, "Lord of the Sojourn of the Dead," sent quails to pursue them, Quetzalcoatl and Xolotl succeeded in their task. He sprinkled his own blood on the bones to create the present generation. The Toltec People believed that Quetzalcoatl was sent to earth by the supreme god to be an earthly king. He was a decent ruler until he fell under the spell of a witch goddess. Tezcatlipoca, in his form of the Blue Hummingbird, Huitzilopochtli, was the instigator of this scenario. He would later become the patron of the Aztecs. The witch had under her control a magic mushroom. It was given in beverage form to the king, who innocently drank it. He became highly intoxicated. While in this state, he had sex with the witch, breaking a sacred tradition. His only choice was to leave Mexico. He took his dwarfs and other creatures who would die on the journey and sadly departed. Quetzalcoatl reached the sea coast, embarked in a raft made of serpent skins and sailed toward the sunrise. The fire of the rising sun ignited his raft. His heart arose from his body and joined the sun. It can still be seen shining in a solar eclipse. This event took place on C.E. July 16, 750, according to a painting in the ancient Mexican sacred book, *Codex Vindobonensis Mexic.1.* Nine Toltec rulers followed the first ruler, each called Quetzalcoatl. Quetzalcoatl is linked to Venus as the Morning Star. His double, or twin, Xolotl is the Evening Star. Quetzalcoatl is offered fruit and flowers. He is sometimes represented as a serpent clothed in the green feathers of the quetzal bird. Sometimes he appears as an aged bearded man with fair or black hair, large eyes and a high forehead. He is dressed in a long robe. *See also* Ehecatl; Huemac; Kukulcan; Legend of the Four Suns; Ometecuhtli; Tezcatlipoca; Xolotl.

Quetzalpetlatl (Mexico) *see* Quetzalcoatl.

Quiateot (Aztec People, Nicaragua)
Rain god. He belongs to a group of creation deities ruled by Tamagostad and Zipaltonal. Quiateot is associated with Ecalchot, Ciaga, Quiateot, Misca, Chiquinau and Vizetot. *See also* Chiquinau; Ciaga; Oxomoco.

Quiche People — Creation Legend (Guatemala) *see* Gucumatz.

Quilaztli (Aztec) *see* Cihuatcoatl.

Quinametzim (Tlaxcala, Toltec People, Mexico)
Giants. The Quinametzim are giants who inhabited the earth in the distant past, as mortals count it, and warred against mortals. According to legend, these giants ruled the second of four or five worlds (or eras). Their era is called the Sun of the Earth. When the human races of the Olmecs and Xicalancas ruled the third world called the Wind Sun, they completely destroyed the rest of the giants. At this time, the gods Quetzalcoatl or Huemac came into being. When the humans refused to obey the god's teachings the world was destroyed by high winds and the people were turned into monkeys. *See also* Legend of the Four Suns; Sun of Fire; Tloque Nahaque.

Quineuhyan (Aztec)
Emergence myth. *See also* Chicomoztoc)

Quinkan (Australian Aborigines)
Underground spirits. Dangerous and powerful spirits living in caves and crevices.

Quires (Gallo-Roman) *see* Silvanus.

Quirinus (Roman)
Also known as: *Mars, Romulus, The Spear God.*
Initially, Quirinus was an independent god worshipped by Sabine settlers on Quirinal Hill. He had a priest, the Flamen

Quirinalis. His spouse was Horta Auirini or the spouse of Romulus, Hersilia. It is possible that the Sabines borrowed Quirinus from one of the Roman names for Mars. Eventually, in the later period of the Republic, Quirinus merged into Mars. When Romulus was referred to as a god, the name Quirinus was used. Quirinus is also an epithet of Mars. Quirinus is the name of either an associate of Bellona's, or a spouse, or son. *See also* Mars.

Quiyauhtonatiuh (Mexico) *see* Legend of the Four Suns.

Quork-quork (Aborigine People, Australia)
He is the father of the thunder god, Pakadringa (q.v.).

Qur'an (Islamic) *see* Koran.

Qutrub (pre–Islamic) *see* Jin.

R

Ra *Re* (Egypt)
Also known as: *Atchet* (his female aspect), *Atum, Khepra, Phra.*

God of the sun. King of gods and mortals. In the beginning, Ra was alone, embraced by Nun, the primeval waters, protected only by a lotus. He impregnated himself and bore the air, Shu, and the moisture, Tefnut, by spitting them out of his mouth. Shu and Tefnut came together and the earth, Geb, and the sky, Nut, were born. Geb and Nut mated and produced Osiris, Isis, Set, and Nepthys. They became the nine major deities of Egypt. Collectively, with Ra at the helm as the principal deity known as Ra-Horakte, they are known as the Ennead of Heliopolis. The world came into being when Nut, transforming herself into a cow, transported Ra to the heavens on her back, and he received the title of "Lord and Creator of the World." Ra, as the sun, travels across the sky in his bark boat which he changes in the morning and evening. In the morning he boards his morning boat, Matet, and then as a falcon-headed man wearing the coiled cobra and the sun disk (uraeus) he boards his evening boat, Semktet (also called Mesektet), for his trip through the rivers of the Underworld. Ra created mortals from his tears. In time, seeing that his mortals were deceitful and unfaithful, he ordered the goddess Hathor to rid the earth of them. She was so enthusiastic about her task that only after major efforts he was able to get her to cease and desist. When Ra's eye (the sun) began to wander and could not be found at night, he sent either Anhur or Thoth to retrieve it. What they found was that the sun's place at night had been taken over by the moon. An uproar ensued that did not quiet down until Ra found suitable places and times for his eye and the moon. Many times we find Ra's name attached to another god. This gives the priest additional power. At one time, there were as many as seventy-five forms of Ra. Ra's cult symbol is the obelisk. His personal symbol is the sun. He is depicted as a hawk-headed mortal, wearing the sun's disk and uraeus, holding a scepter with a grey-hound's head. As Khepra, Ra is a dung beetle (q.v.) Additional myths pertaining to Ra are found under Isis and Nut. *See also* Aani; Amen; Astarte; Aten; Atum; Hapi; Horus.

Ra-ateni (Egypt) *see* Aai.

Ra-Harakhte (Egypt)
Also known as: *Harakhty, Harmachis* (Greek), *Heraktes, Ra-Horakhty.*

Supreme deity. Ra-Harakhte is a composite name given to the sun as ruler of Egypt and chief of the gods of Heliopolis. His name means "Horus of the Horizon." He is shown with the head of a falcon and wearing the solar disk wreathed by the Uraeus. The Greeks know him as Harmachis. *See also* Horus.

Ra-Heru-Khuti (Egypt) *see* Aaru.

Ra-Horakhty (Egypt) *see* Ra-Harakhte.

Ra-Jin (Japan)
Spirit of weather. This spirit of the thunder and wind is similar to the Oni. He has a round frame behind his back, on which are fastened small drums.

Ra-Tem (Egypt) *see* Atum; Sopdu.

Raashiel (Semitic) Earth god.

Rabisu (Mesopotamia; Babylonian)
A Mesopotamian demon who appears in nightmares; a Babylonian ghost who set bodies on end.

Rada (Haitian People, Dahomey origin, Africa)
Rada is the name for a pantheon of Haitian deities of the *vodun* cult. Other Haitian pantheons are the Petro, Congo, and Ibo gods. *See also* Agbe.

Radha (Hindu; India)
Also known as: *Lakshmi.*

Radha, an avatar of Lakshmi, is celebrated in Indian poetry and art as the pretty cowgirl who pined for Krishna while he danced and flirted with other women. The women, known as gopi or cowgirls, were irresistibly drawn to Krishna by the strains of his flute. Their dance, known as the "Rasalia" or play of delight, lasted for six months. Their spouses, known as the gopa or cowboys, were left behind while the women frolicked. The men were not jealous for they did not realize the passage of time or the absence of their mates. After a period of extensive foreplay Radha and Krishna finally fulfilled their love for

www.ebook3000.com

one another. Their union, as man and wife, represents the world coming into existence. Radha is associated with the earth and the west. She is not to be confused with Radha the wife of Adhiratha (Dhritarashtra's charioteer), who adopted Karna, the son of Kunti and Surya. *See also* Karna; Krishna; Kunti; Lakshmi; Surya; Vishnu; Yami.

Radheya (India) *see* Karna.

Rafnagud (Teutonic) *see* Odin.

Rafu-sen (Japan) Goddess of the plum blossom.

Raga (India) A musical melody personified as a deity.

Raga-Vidyaraja (India) *see* Aizen-Myoo (Japan).

Ragnar Lodbrog (Norse; Teutonic)
Sun hero. It is possible that he was a mortal named Ragnar. He killed the winter serpents and was given the name Lodbrog. Ragnar was the husband of Thora, who died. He married Aslog and became father of Ingvar and Ubbe, who were mortal men. According to the tale, he could only be killed by a viper.

Ragnarok *Ragnarokr* (Norse; Teutonic; Icelandic)
Also known as: *Gotterdammerung* (German), *Twilight of the Gods.*

Ragnarok is the apocalyptic final battle between the gods and the giants, involving all creation. It is the world's end when all life will be destroyed, including the gods. The nine worlds will be submerged. After the war, two humans named Lif and Lifthrasir will emerge from Hoodmimir's Wood. They will propagate the new human race. According to Norse myth, Ragnarok is the day when Loki and his followers will break their bonds and meet the gods for their final battle. All will be killed and there will be total destruction followed by regeneration. A new earth will arise, peopled by sons of Odin, Thor, Balder, and Hodur. They will live in harmony with mortals in the new world created by Alfadur (All Father). Compare Ragnarok to Armageddon. *See also* Balder; Fenrir; Garm; Hati; Hodur; Lif; Loki; Nagilfar; Odin; Skoll; Thor; Vigrid.

Ragnarokr (Teutonic) *see* Ragnarok.

Ragno (Hopi, Maidu, Pomo People, North America)
An old mother goddess, Ragno appears in the Pomo Indian Creation Legend associated with the brothers Kuksu and Marumda (qq.v.). In the Hopi Creation Legend, she is associated with the Huruing Wuhti (q.v.). *See also* Marumda.

Rahabh (Semitic)
Also known as: *Nakhash, Tannin.*

Serpent. The early Hebrews believed in a monster nature serpent called Rahabh, Tannin or Nakhash. God (Yahweh) was called on to "break the heads of Leviathan and of the dragons in the waters." He was created on the fifth day of the week of creation, and was killed by Gabriel with the assistance of Yahweh. *See also* Leviathan; Pepi.

Rahes *see* Min.

Rahu *Bhangi* (Cambodia; Hindu; India)
Originally a Daitya, this monster demon, known as "The Grasper," causes eclipses by eating the sun. He is the son of Simhika, one of Daksha's numerous daughters. Jealous of the gods who were drinking the elixir, soma, he changed himself into a god to join them. While Vishnu was creating the world, he seized the elixir and drank enough to fill a river. Surya the sun and Soma the moon were watching, and they told Vishnu. He threw his discus named Sudarshana at him and sliced off his head. His body fell to earth with the force of an earthquake but his head remained alive. It devours the moon monthly and the sun occasionally. He is depicted with a dragon's head, four arms and a tail like a comet. His chariot, drawn by eight black horses (representing night clouds), carries him through the sky. He gained immortality by drinking the sacred soma. Followers worship him by walking over hot cinders. He can be frightened away by bathing in holy waters during an eclipse, by the piercing cries of female bathers, the sounds of the conch shell, and devotional songs. *See also* Daityas; Daksha; Marichi; Savarbhanu (for a variation of this myth); Soma; Sudarshana; Surya.

Rahula (A) (Buddhist; Nepal).
Rahula is known as the Dharma Protector and is said to have arisen from the land of fire and infinite ferocity. He is grey, has nine heads, four arms and one thousand flaming eyes.

Rahula (B) Son of Gautama and Yasodhara. *See also* Buddha.

Raiden *Raijin, Kaminari Sama* (Japan)
This demon god of thunder likes to nibble on navels. The goddess Uzume caught him in her bath. He has claws and usually carries a string of drums. The only protection from him is to hide under a mosquito net. *See also* Take-mi-kazuchi.

Raijin (Japan) *see* Raiden.

Rainbow Snake *Great Rainbow Snake* (Australia)
Also known as: *Angamunggi, Galeru, Julunggul, Kalseru, Karia, Kunapapi Langal, Kunmanggur, Mindi, Muit, Ngaljod* (female), *Taipan, Ungud, Wollunka, Wollunqua, Wonambi, Wonungur, Worombi, Yero, Yurlunggur.*

Sky deity. He shaped the land and produced spirit children. The Rainbow Snake is sometimes identified as a mother goddess, sometimes a god, sometimes both. As Kunmanggur, he is associated with Tjinimin, the Bat.

Raja of Kasi (India) *see* Bhishma.

Rajarishis (India) *see* Rishi.

Rajyadidevatas (India) *see* Devis.

Raka (Polynesia) *see* Raki.

Raki *Raka* (Polynesia; Maori People, New Zealand)
Also known as: *Rangi.*

High god or creator. Storm deity. Most of the legend of Tane and Raki is similar to that related in Rangi. The only difference is that Tane decided to clothe Raki with stars, but they only made Raki look good at night. Some think the sun and moon were Rangi or Raki's children and later placed for eyes in the sky. In some versions of this mythology, Raka (trouble) presided over the basket of winds which he received from Vari-ma-tetakere. She also gave him the land called Moana-Irakau. *See also* Rangi; Vatea.

Raksasa (India) *see* Rakshasas.

Raksha-Kali (India) *see* Kali.

Rakshas (India) *see* Rakshasas.

Rakshasa-Loka (India) *see* Loka.

Rakshasas, The *Manusha-Rakshasis* (female demons in human form), *Raksasa, Rakshas, Rakshasi* (female Rakshasa), *Yakshas* (Hindu; India)

The Rakshasas, semi-divine evil spirits, are the foes of gods and mortals. They have magic powers and can take on any form at will. According to the *Ramayana*, they were created from Brahma's foot to protect the primeval waters. Their king was the demon Ravana. In other sources, they are said to be descendants of the sage Pulastya or the children of Nirriti, the Vedic goddess of death and guardian of the southwest, and her mate Nirrita, or the children of Khasa, who may have been one of Daksha's sixty daughters. As shape changers, they can appear as animals, especially dogs, vultures and owls. When the monkey god Hanuman went to their home in Sri Lanka in search of Sita, he saw that they came in every conceivable shape and form. They can appear as monstrous humans, old women or beautiful men and women. Their colors are yellow, green, or blue. Their eyes are usually vertical slits and they have matted hair and large bellies. Their fingers are set on backwards and they each have five feet. Their diet is made up of human flesh and food that has been sneezed on or contaminated by insects. If touched by their poisonous fingernails one can die. They love to hang out in cemeteries, destroy sacrifices and enter humans through their food, causing illness and insanity. Occasionally, a Rakshasas can be kindly. Vibhishana, the younger brother of Ravana, is an example. His character and behavior were unacceptable to Ravana, so he exiled him. Vibhishana went on to join Rama and became the viceroy of Lanka. Visvakarma, the divine architect, built the dwelling place of the Rakshasas. A Rakshasa known as Nairitya, the god of dread, was transformed into a guardian deity of the eight directions. His post was the southwest. A ninth century sculpture from Central Java thought to be Nairitya shows a man seated on a rectangular pedestal with the right leg folded on top of the left. He is dressed in a loincloth and wears a high headdress and elaborate jewelry. His hair is long and falls over his shoulder. He carries a sword with a curved blade in his right hand, which rests on his right knee. His left hand is placed on the right foot and he holds a small oval shield. His heavenly status is indicated by a pointed, petal-shaped halo. In a later depiction, he is seated on his mount, a bhuta (demon). Many Rakshasas were cruel humans in their previous life. If one is frightened or pestered by a Rakshasas, address it as "Uncle" and it will disappear. They represent the forces of evil and the human aspects of greed, deceit, lust and violence. *See also* Agastya; Agni; Asuras; Bhima (A); Bhutas; Brahma; Daitya; Hanuman; Kalanemi; Kasyapa; Kuvera; Nirriti; Pishachas; Rama; Ravana; Sita; Vasistha; Visvakarma; Vritra; Yaksha.

Rakshasi (India) *see* Rakshasas.

Rakshodhidevatas (India) *see* Devis.

Raktabija (India) A Demon. *See also* Kali.

Raluvhimba (Venda People, Northern Transvaal, South Africa)

The Supreme Being. Creator of All. Raluvhimba is offered prayers and sacrifices particularly during times of drought.

Rama (Hindu; India)

Also known as: *Rama-candra* ("The Embodiment of Righteousness"), *Rama-Chandra, Ramachandra, Vishnu.*

Ramachandra, often called Rama, was the Prince of Ayodhya and the seventh avatar of Vishnu. His mission in this form was to defeat the giant demon Ravana and to teach morals by setting an example. Rama, the eldest son of King Dasaratha (also known as Dasarata) and Kaushalya (also spelled Kausalya and Kooshelya) and grandson of Aja of the Solar Race. He was born as a result of Dasaratha performing a "horse sacrifice" known as the Ashvamedha. After the sacrifice, Dasaratha's three wives, Kausalya, Kaikeyi and Sumitra, spent the following night next to the beast's carcass as part of a rite thought to impart the animals potent fertility spirit to them. Vishnu appeared to Dasaratha in his celestial form after the sacrifice and gave him a nectar, a divine essence of itself, to be shared among the women. Kausalya received half and the other women each received a quarter of the total amount. Sumitra divided her portion into two. Kausalya gave birth to Rama, Kaikeyi to Bharata, and the youngest wife Sumitra gave birth to the twins, Lakshmana and Satrughna. Each son had within him the percentage of Vishnu's essence equal to the amount of nectar ingested by his mother. Kaikeyi, the second wife of Dasaratha and the mother of Rama's half-brother Bharata, wanted Rama exiled for fourteen years and wanted her son to become the king. Dasaratha had promised to fulfill any wish for his wife and it was with great pain that he told his dear son Rama of the agreement. Rama, his wife Sita, and his brother Lakshmana, abiding by Dasaratha's wish, went into exile. Sita was then abducted by the evil giant Ravana, king of the island of Lanka. Rama enlisted the assistance of the flying monkey gods Hanuman, Sugriva, and their troops to rescue her. Eventually, he returned to his home to reign but his life was fraught with struggles against Ravana and the demon Rakshasas. Throughout his life, Rama remained courageous and virtuous. The *Ramayana*, an epic poem divided into seven books, thought to have been composed in the third century by Valmiki, recounts the episodes of Rama's life. It is said that the reading of the *Ramayana* will remove all sins. Another famous epic, known as the *Tulsi Das*, written by Tulasi Dasa, servant of Lakshmi, in the late medieval Hindi period (1541–1605), also celebrates his life. Lakshmana, a partial representation of Vishnu represents perfect loyalty. Sita, an avatar of Sri, a wife of Vishnu, represents female purity and fidelity. Her name means "furrow," and symbolizes the fertile earth. Rama, thought also to be a vegetation deity, symbolizes the fertilizing function of the sky. Ravana represents evil and Lanka represents Ceylon. The Ashvamedha or "horse sacrifice" was a ritual performed by ancient Vedic kings. They sacrificed the finest stallion in hopes of producing a son. The queen was then required to spend the night next to the dead beast and to perform certain sexual rites. Of all the domestic animals, the horse was the most honored. It was believed that if a ruler would sacrifice a hundred stallions, he would become ruler of the world. In later times, the rites were modified. The horse was symbolically used during the ritual and then released to roam for a year. If the horse was found in another king's

www.ebook3000.com

domain, the king would either accept that the horse's owner was his superior, or he would fight. The following year the horse was sacrificed. Under cover of the horse's robe, the queen would perform ritual acts thought to endow her with the animal's fertility power. The horse was then offered to the Lord of Creation, Prajapati. Kausalya is described as a virtuous woman; Kaikeyi, as young, beautiful, and proud; and Sumitra is said to have been sweet and loving. The story of Rama and Hanuman is similar to the story of Indra and the ape Vrishakapi. *See also* Agastya; Ahalya; Bali (A); Ganesha; Hanuman; Indra; Jambavan; Karttikeya; Kasyapa; Kumunda (regarding Kusha; another of Rama's sons by Sita); Kuvera; Lakshmi; Parashu Rama; Prajapati; Rakshasas; Ravana; Sampati; Sita; Soma; Sugriva; Vishnu; Visvakarma.

Rama-candra (India) *see* Rama.

Rama-Chandra (India) *see* Rama; Vishnu.

Ramachandra (India) *see* Rama.

Rambha (Hindu; India)
The most beautiful of the Asparas, with an amiable disposition, Rambha is the spouse of Kuvera, who was raped by the demon Ravana. She was one of the treasures rescued by Kurma (Vishnu's avatar as a tortoise) from the Churning of the Ocean of Milk. Indra sent her to tempt the ascetic Visvamitra who did not submit to temptation but turned her into a stone. *See also* Apsarases; Kurma; Kuvera; Ravana; Rishi.

Ramiriqui (Muzo People, Colombia)
Ramiriqui and his nephew, Sogamozo, created men and women. Men were created with yellow clay and women from an herb. Later Ramiriqui became the sun and Sogamozo became the moon.

Ramman (Armenia)
Also known as: *Adad.*
Weather or storm god. One of the early triad of Khaldi, Theispas and Artinis. He could be a forerunner of one of the Babylonian triads, Sin, Shamas, and Ramman. *See also* Adad; Khaldi.

Rammanu (Sumer) *see* Adad.

Rammon (Sumer) *see* Adad.

Rampanohitaolana *Rampanahoditra, Rampanaohozatra, Rampanaora see* Rampanelombelona.

Rampanelombelona (Madagascar).
Creator deities. Five of the Zanahary gods who created mortals.

Ran (Norse; Teutonic)
Ran, the goddess of the sea, is the mate of the sea deity, Aegir. She pulls drowning men down with her net. She is the mother of nine daughters who represent the waves. One of her daughters is the water goddess Angeyja. *See also* Aegir.

Ranan (Egypt) *see* Renenet.

Ranga-Hore (Polynesia) *see* Rangahore.

Rangahore *Ranga-Hore* (Polynesia, New Zealand)
She is probably a goddess of stones. In the third attempt by Tane to make his mother Papa his wife she refused again an sent him to his ancestor Rangahore to be his wife. This woman conceived stones instead of a child. *See also* Hine-ahu-one; Hine-tu-a-maunga; Ngaore; Papa; Tane.

Rangda (Bali; India)
Rangda is a goddess of fertility connected with paddy fields. She is depicted with large breasts and with flames spewing from her mouth. She is also known as a witch.

Rangi (Polynesia; New Zealand)
Also known as: *Atea, Atea Rangi, Raki, Rangi-Nui, Te Tumu.*
Rangi is the sky god father/spouse of Papa, mother earth. In the darkness before anything began, known as Ao-pouri, beings called Po (representing the Primeval Void) wanted to create light. In some versions, these beings were the children of Rangi and Papa, while other versions say they were offspring of Po. (*See also* Po for description of the children.) The children argued about tearing Rangi and Papa apart, killing them if necessary, to make light and darkness. Finally, the god of forests, Tane, succeeded in separating the two, and found hidden, the human race. His brother, the storm god Tawhiri, was extremely upset at the separation of his parents. He acted out by creating upheavals from hurricanes and storms, uprooting his brother Tane's forests. He established his power by dominating the authority of the sky. Another brother, the god of war, Tu, did not want to submit to the power of Tawhiri. A struggle ensued between the brothers which signified the beginning of warfare. The islands of the Pacific Ocean were formed by their struggle. In the meantime, Tangaroa set the sun and moon in place and created the first woman, Hine. Hine and Tane united and created the children, who were the first Polynesian people. Tane, who symbolized fish of all species assigned Rongo the position of the god of cultivated food, Haumia-tikitiki the god of wild food, Tawhiri-ma-tea the god of winds and storms, and Tu-matauenga the god of man. In another version of this myth, Rangi is replaced by Raki and the brothers are named Tane, Takaroa, Paia and Rehua. In this scenario, it is Tane and Paia who lifted Rangi from Papa. In another version, Rua and a group of night and day gods assisted him in raising the heavens. According to some legends, Rangi had a series of other spouses and children. Four of the six wives mentioned are Poko-ha-rua-te-po, Papa-tu-a-nuku, Heke-heke-i-papa, Hotu-papa and the fifth and sixth are not described. Most of the children of these unions of Rangi and his various wives are listed as gods and goddesses in their own right. A brother, Akatauire, the husband of Ruange, is mentioned in some myths as a co-ruler, with Rangi, of Mangaia island. Rangi was known as Atea Rangi by Tuomotuans. *See also* Atea; Heke-heki-i-papa; Hotu-papa; Papa (A); Po; Poko-ha-rua-te-po; Raki; Rehua; Rongo; Rua; Tane; Tangaroa; Tawhiri-ma-tea; Tu; Tu-matauenga; Vatea.

Rangi-Nui (Polynesia) *see* Rangi.

Rangidimaola (Madagascar)
A jester deity. He was summoned by Zanahary to be the companion of his son Razanajanahary. When Rangidimaola became vain and offensive, Zanahary sent him to earth as punishment. Razanajanahary visited his friend and gave him three pieces of wood, which Rangidimaola sculpted into human form. Razanajanahary then breathed life into them.

Ranno (Egypt) *see* Renenet.

Raphael (Semitic) God of air.

Rapithwin (Zoroastrian; Persia)
God of the noon day heat and of the summer months. When the demon of winter arrives, Rapithwin retreats below the earth and keeps the subterranean waters warm so plants and trees do not die. In Zoroastrian teaching, Ahura Mazda performed the sacrifice that resulted in the creation of the world, during Rapithwin's time of day. When the time of the renovation of the world occurs, it will also take place during Rapithwin's time of day. *See also* Ahura Mazda; Tishtrya; Yazatas.

Rasa (Brahmanic, Vedic; India)
The Rasa is the mythological river that encompasses the earth and the atmosphere. *See also* Hiranyagarbha; Pani (B).

Rashnu *Rasn* (Pahlavi dialect), *Rasnu* (Zoroastrian; Persia)
Along with Mithra and Sraosha, the angel Rashnu passes judgment of the souls of the dead on Chinvat Bridge. He holds the golden scales. *See also* Ahura Mazda; Ameshas Spenta; Chinvat Bridge; Mithra; Sraosha; Yazatas.

Rasoalao (Madagascar)
Underworld deity. She is one of two daughters of a Vazimba woman (one of the dead). The other daughter is Ravola. Before the mother died she bequeathed the gift of wild animals to the oldest daughter, Rasoalao, and to the younger daughter, Ravola, the tame animals.

Rat (Egypt)
Also known as: *Rat-Taiut.*
She is called "Mother of Gods." She could be the wife of the sun god Ra, or perhaps the name Rat is a feminized version of Ra's name. She is sometimes shown wearing a headdress of a disk with horns and the uraeus and sometimes with two feathers on the disk.

Rat-Taiut (Egypt) *see* Rat.

Rata (Polynesia)
Also known as: *Laka, Ratu-nui.*
Hero-god. As Laka he is the grandson of Tawhaki. In some legends, he is the son of Tokerau and Wahieroa. He is the possible son of the eel-woman Faumea. The tales of Rata are sometimes confused with those of Tawhaki and of Hina. Rata is credited with killing the cannibal giant Matuku. *See also* Faumea.

Ratana Sambhav (Buddhist; Nepal) *see* Dhyani Buddhas.

Ratatosk (Norse; Teutonic)
Also known as: *Ratatpslr.*
Deified animal. Ratatosk is the rabbit or squirrel who runs up and down the Yggdrasil tree promoting strife between the eagle on top and the serpent, Nidhogg, at the roots. *See also* Nidhogg; Yggdrasil.

Ratatpslr (Teutonic) *see* Ratatosk.

Ratavija (India) A Demon. *See also* Kali.

Ratha-yatra (India)
A festival for Krishna in his form as Jagannath, "The Lord of the World."

Rati (Hindu; India)
Also known as: *Maydevi*; *Mayavati* (Deceiver).
She is the soul mate of the god of love, Kama. When he was consumed by Shiva's third eye, she appealed to Parvati to use her influence to have him restored to life. Her request was fulfilled and he was incarnated as Pradyumna. As Mayadevi, she protected him as he grew up in this incarnation. *See also* Brahma; Kama; Parvati; Pradyuma; Priti; Shiva; Vishnu.

Ratna Dakinins (India) *see* Dakinis.

Ratna-Garbha (India) "Jewel-Belly." *See also* Kuvera.

Ratna Krotishaurima (Tibet)
This goddess, who also has the title Shakti, is found in the Bardo World on the tenth day, offering Ratnaheruka a red shell filled with blood. *See also* Karma-Krotishaurima; Padma Krotishaurima, Ratnaherukca; Shakti.

Ratnaheruka (India) *see* Herukas; Ratna Krotishaurima, Ratnasambhava.

Ratnapani (India) *see* Dhyani Buddhas; Dhyanibodhisattvas; Kshitigarbha; Ratnasambhava, Samantabhadra, Vajrapani.

Ratnasambhava (Buddhist; India)
Also known as: *Chak-na-rin-chhen* (Tibet), *Hosho-Nyorai* (Japan), *Phyag-na-rin-chen* (Tibet), *Ratna Sambhav* ("Born of a Jewel"), *Ratnaheruka* (Yellow Heruka Buddha), *Ratnapani, Rin-chen-bhyun-idan* (Tibet).
Ratnasambhava, the Buddha of goodness and beauty, is the third of the Dhyani Buddhas or Buddhas of Meditation. The central figure of the Ratna family, Ratnasambhava symbolizes wealth and dignity and the cosmic element of sensation. His negative aspect is the exploitation of wealth, and in Nepal, the embodiment of slander. His female counterpart is Mamaki, who is also said to be the consort of Akshobhya and Vajrasatwa. Ratnasambhava is accompanied by two female bodhisattvas on the third day in Bardo. The goddesses are Mala, the goddess of ornamentation, and Dhupa, the goddess who carries incense. Mala is also known as hPhren-ba-ma (Tibet), Preng-Ta-Ma and Mahlaima. Dhupa is also known as Dhupema, Dug-Po-Ma and bDug-spos-ma (Tibet). She is one of the Eight Mothers of Buddhism. Bardo, the Tibetan Buddhism after-death state, is considered the place of transition between death and rebirth. Ratnasambhava, yellow in color, always faces the south. He is seated in the gift-bestowing position (varada mudra). His symbols are the pearl (cintamani) and ghanta (bell). The horse throne is his vehicle. It represents intelligence and beauty of form. His yellow color symbolizes the wealth or fertility of the earth. The pearl or wish-fulfilling gem, which he always wears, indicates the absence of poverty. The pearl (cintamani) is also the symbol for an object used as a point of concentration when meditating. Ratnasambhava is also depicted embracing Mamaki. She symbolizes the water required as fertilizer by the earth. She is also depicted in the lalita asana (one leg pendant, often supported by a lotus. Her mudras (poses) are varanda and vitarka. The varada is the gift-bestowing gesture. The arm is pendant, all fingers are extended downward, and the palm is extended outward. The vitarka signifies argument. The arm is bent, the index finger touches the tip of the thumb, the other fingers extend upward. The goddess Mala brings out the beauty

www.ebook3000.com

sions, 'I feel you from my gut' and 'I have a gut feeling about something.' Why do people mention a gut feeling? Obviously people have some feeling in their gut. It's very interesting that the whole Tao practice is feeling, awareness and consciousness – using this gut to feel, to be aware, and to be conscious.

You can rest, relax the brain in the head by using the 'brain in the gut.' This is the first step. The first thing we learn in the Tao is to forgive and let go. When we keep on remembering past negative emotions, we will stop seeing the truth. To let go of the past is to empty the mind and use the abdominal mind, the awareness and consciousness. Here's an interesting point in the way of the Tao: This gut brain can do a lot of simple functions that are similar to the functions of the brain in the head. This is a feeling and awareness type of functioning similar to many of our 'right brain' functions. However, we need to use the brain in the head in order to perform complex functions such as reasoning, making plans and making complex calculations. For rational functions, we need to use the brain in the head for the 'left brain' functions.



For our daily life of consciousness, awareness and feeling, we can use either the brain in the gut or the brain in the head. When we use the upper brain less, it will become charged with more energy and its power will be increased – and more power will be available to the body. That is why we say in Taoism, that we have to train the brain in the gut, so that we can use it when the brain in the head is resting. When the head brain is resting, it can be recharged: brain repair and maintenance occurs. Also, it can grow new brain cells. With more charging we have more power for creativity or whatever we want to use it for. If we like, we can use it to develop our higher spiritual nature.

Fig. 3.23 *When you are not using the Upper Brain allow it to rest by sending it down to the Lower Tan Tien.*

The simple thing is, that for the same job that the head brain or the gut brain can do, the head brain charges you eighty dollars. The gut brain only charges you twenty dollars. So, which one do you want to use? No, of course we are not that silly to use this overpriced person for the same work. But when we come to our own actual life, we don't know how to do it. We always use this mind, this high-priced brain. To add to this, we continue using it and using it, until the brain energy is completely consumed – no more energy. When you get to a certain level the brain is empty. These brain energy measurements are not only for indicating mental energy levels, they also represent energy conditions for the whole body and spiritual energy.

Whenever I smile down, the brain waves go lower and lower very quickly – and the transformed energy from the Tan Tien and organs charges up the brain in the head! Just by flexing the facial muscles into the mode we use with a genuine smile, we can produce the effects on the nervous system that normally goes with the natural spontaof the earth. Peaceful in demeanor, she is usually depicted dancing (arhaparyankasana). Mala has two or four arms and holds a Buddhist rosary. Dhupa represents clean air and space for vegetation to grow and waters to run clearly. Dhupa is also shown dancing, has two or four arms and holds an incense vase. *See also* Amrtakundali; Dhyani Buddhas; Herukas; Hosho-Nyorai; Kshitigarbha; Mamaki; Vairocana; Vajrapani; Vajrasatwa.

Ratnasanu (India)
Sacred Mountain. *See also* Meru Mountain.

Ratri *Ratridevi* (Hindu, Vedic; India)
Ratri is the benevolent goddess of the starlit night, darkness and sexual passion. She is the daughter of the earth goddess Prithiva and the sister of the dawn goddess Ushas, the fire god Agni and the storm god Indra. She may have been the spouse of Dyaus, who is also the husband of Prithiva. Although Ratri is said to have given birth to beings of darkness, she is not to be feared. She is invoked for protection against robbers and other perils of the night. Ratri is associated with the goddesses of twilight, Jyotsna and Sandhya, and the twin Asvins. When Ratri, dressed in dark clothes adorned with gleaming stars, retires, her sister Ushas, the goddess of dawn returns. She is depicted as a beautiful woman, sometimes shaking a cymbal. Compare to the Greek goddess of the night, Nox. *See also* Agni; Asvins; Dyaus; Indra; Prithiva, Sandhya.

Ratridevi (India) Goddess of the Night. *See also* Kali; Ushas.

Ratu-nui (Oceanic) *see* Faumea; Rata.

Rau (Egypt)
Afterworld deity. Rau carries a spear in the tenth sector of Taut.

Rauni (Finnish)
Also known as: *Akka, Maan-Emoinen.*
Thunder god. Rauni and his wife are deities of fertility. Some writers say Ukko was a supreme god and Rauni or Akka was his wife. One version uses the name Maan-Emoinen in place of Rauni and calls her an earth goddess. In this version she is the consort of Jumala or Ukko. Rauni is the wife of the thunder-god Ukko of the Finns. The Lapps have a goddess named Ravdna to whom they sacrifice reindeer as they do to the thundergod. Analogous to Freyr and Freyja. *See also* Jumala; Ukko.

Ravana (Hindu; India)
Also known as: *Hiranyaksha, Hiranyakshipu, Indrajit* (Conqueror of Indra), *Sisupala.*
Ravana, a giant demon, was king of the Rakshasas in the island kingdom of Lanka. Given a protective boon by Brahma for the austerities he practiced over thousands of years, Ravana could not be killed by the gods, demons or Gandharvas. He was only vulnerable to men and beasts. He had three incarnations as Vishnu's archenemy, the first, in the form of Hiranyaksha; the second, Ravana; and the third, Sisupala. He is the grandson of Pulastya and the son of Visravas and a Rakshasi. (Some say his mother was Nikasha.) His sister is the she-demon giant Shurpanaka meaning "she who has nails like winnowing baskets," who acted as a spy for her brother. He has two brothers and a half-brother, the dwarf god of wealth, Kuvera. His brother Kumbhakarna is a giant monster who would sleep for six months and wake up for a day. The younger brother, Vibhishana, although a demon, is of good character, much to Ravana's displeasure. After being exiled by Ravana, he was invited to join forces with Rama and eventually became the viceroy of Lanka. His eldest wife was the slender-waisted Mandodari who also mated with Bibhishan, said by some to be Ravana's brother. Ravana's mistress Rambha was also sexually involved with his half-brother Kuvera. A formidable, flying foe, able to assume any form, he could create tremendous storms, break mountains in half, and with his hands stop the sun and the moon. Even the great god Indra was unable to overcome him. Ravana overtook Swarga, Indra's heaven, captured Indra and made him a lowly servant. He was in good company; the great god Agni was the cook, Varuna the water carrier, and Vayu the sweeper. Ravana seized Lanka from his brother Kuvera and forced him to supply money. In desperation, the gods approached Vishnu for assistance in overcoming the demon. Vishnu came to earth as Rama to battle the evil and havoc personified as Ravana. One of Ravana's despicable actions was raping women. In the forest of Dandaka, Sita, her husband Rama and his faithful brother Lakshmana were living in exile. The demon Ravana dressed as a priest, made his way to the hermitage and attempted to seduce Sita. When she rejected him, he abducted her and carried her to Lanka. Rama organized Sugriva and Hanuman and their troops of monkeys and bears who were created by the gods to assist in overcoming Ravana. After building a bridge to Lanka they engaged in many battles. The lengthy attacks ended when Rama shot an arrow created by Brahma and given to him by the sage Agastya, through Ravana's chest. The arrow flew into the ocean, purified itself and returned to Rama. So it was that the creator who had protected evil incarnate ultimately destroyed it by his creation. Ravana is depicted with ten heads, twenty arms, copper color eyes and long, sharp teeth. In some carvings he is shown as a human being. His mount is the flying chariot Puspaka, which he confiscated from Kuvera. His attributes when disguised as a priest are a gourd on a strap, and a jingling staff known as a khakkhara in Sanskrit. *See also* Agastya; Agni; Bali (A); Brahma; Daityas; Gandharvas; Hanuman; Hiranya-kasipu; Hiranyaksha; Indra; Kalanemi; Kuvera; Lokapalas; Mandodari; Maya (C); Nandisha; Nikasha; Rakshasas; Rama; Rambha; Sampati; Shurpanaka; Sisupala; Sita; Sugriva; Swarga; Varuna; Vayu; Vishnu.

Raven (North American Indian) *see* Yehl.

Ravola (Madagascar) *see* Rasoalao.

Razanajanahary (Madagascar) *see* Rangidimaola.

Razeka (Arabic) Tribal god of food.

Rbhus (India) *see* Ribhus (The).

rDorge-sems-dpa (Tibet) *see* Vajrasatwa.

rDorje-P'ag-mo (Tibet) *see* Dorje Phagmo.

Re (Egypt) *see* Ra.
Realm of the Mist (Teutonic) *see* Nifl-heim.

Red Lord (A) (Native North American) *see* Hastseltsi.

Red Lord (B) (China) *see* Ch'i-ti, and Shang Ti.

Red Man (Cherokee People) *see* Asgaya Gigagei.

Red Woman (Cherokee People) *see* Asgaya Gigagei.

Rediyas (Semitic) God of water.

Regin *Reginn* (Norse; Teutonic)
Regin is probably a god of wisdom or a celestial smith, though some say he is a god of sowing and reaping. Known as a master smith, Regin taught Sigurd the art of the warrior. Regin is the youngest son of Hreidmar, the king of the dwarfs. His other sons are Fafnir and Otter. In the end, Regin was killed by Sigurd. He is usually shown with a forge. *See also* Fafnir; Sigurd.

Reginn (Teutonic) *see* Regin.

Rehua (Polynesia) *see* Maui; Rangi.

Reia (Greek) *see* Rhea.

Reidi-Tyr (Teutonic) *see* Tyr.

Reidmar (Teutonic) *see* Hreidmar.

Rekhi (Egypt) *see* Aai.

Rem (Egypt)
God of weeping. Rem is the personification of the sun god Ra's tears. His name means "to weep."

Remati (Tibet)
This tutelary goddess is chosen by certain yogis because she is associated with Tantric secret doctrines. *See also* Yeshe-Khahdoma.

Remi (Egypt)
God of fish. Known as the "Fish God." Remi is sometimes identified with the god Rem. *See also* Aai.

Remphan (Hebrew) *see* Rephaim.

Remus (Roman) *see* Romulas and Remus.

Renen (Egypt) *see* Renenet.

Renenet (Egypt)
Also known as: *Ernutet, Isis, Ranan, Ranno, Renen, Renenit, Renenutet, Thermuthis.*

Goddess of children. Goddess of fertility and the harvest. Lady of the granaries and fertile land. Renenet feeds the newborn infant and names her. She will attend her when she is judged after death. One of the months of the Egyptian calendar is named for Renenet. As Renenet, Isis is the goddess of the harvest. As Thermuthis, offerings are made to her when the corn is harvested and the grapes are pressed. She is portrayed sometimes as lion or snake-headed. She is also depicted as being crowned with the uraeus and with two ostrich feathers. As Renenet, she is also shown carrying Nepri, the young god of corn. Renenet has some of the same functions as Shai (q.v.). She is associated with Meshkhent (q.v.). *See also* Isis.

Renenit (Egypt) *see* Renenet.

Renenutet (Egypt) *see* Renenet.

Renniu (Egypt)
Afterworld deities. Four bearded gods in the eleventh sector of Tuat.

Renpet (Egypt)
Renpet is the goddess of the eternity of time. She is a deity of the springtime of life and of the early calendar. She is shown wearing a long palmshoot curving above her head.

Renuka (India) *see* Parashur Rama.

Rephaim *Rephan, Rephain, Remphan* (Hebrew)
Also known as: *Anakim, Chiun, Kiun.*

Giants. Old Testament ghosts of darkness or giant demons of Canaan. Two well-known giants are Goliath and Og. Some think they represent the souls of the dead in Sheol. Rephaim is probably the same as Remphan, who is the Satan of the ancient Israelites. Some say Chiun (a goddess of plenty) is also the name of an idol worshiped in ancient times. *See also* Chiun; Jinny.

Rephain (Hebrew) *see* Rephaim.

Rerek (Egypt)
Aspect of Set. Rerek is a form of the monster serpent taken by the god Set to oppose the sun god Ra from appearing daily in the East. Rerek is identified with Apophis.

Rerit (Egypt) *see* Taueret.

Rerir (Norse; Teutonic)
Rerir, who is probably a drought aspect of the sun, is the grandson of Odin and the son of Sigi. Rerir desperately wanted a son. Frigga (Freyja) sent her messenger Gna (or Liod, Ljod) with a miraculous apple which she dropped in his lap. He and his unnamed wife ate the apple and in due time their beautiful son, Volsung, was born. Shortly afterward Rerir and his wife died. *See also* Volsung.

Rert (Egypt) *see* Taueret.

Rerti (Egypt) *see* Assessors.

Rertu (Egypt) *see* Taueret.

Reshef (Syrian) *see* Reshep.

Reshep *Reshef, Resheph, Reshepu, Reshpu* (Egyptian)
Also known as: *Aleyin, Apollo, Nergal* (Babylonia), *Ninib.*

As an Egyptian deity, Reshep is a warrior god and is the same as the Semitic Aleyin/Amurru. He is depicted with a crown of gazelle horns, carrying a shield, spear and a club. *See also* Aleyin; Amurru; Min; Nergal; Qadesh.

Resheph (Babylonia) *see* Reshep.

Reshepu (Babylonia) *see* Reshep.

Reshpu (Babylonian) *see* Reshep.

Rest-F (Egypt) *see* Ap-taui.

Revanta (India) *see* Sanja.

Revati (India) Wife of Bala-Rama (q.v.)

Reza (Africa) *see* Leza, and Lisa.

Rhadamanthus *Rhadamanthys* (Greek)
The great god of thunder, Zeus, in the form of a white bull, had intercourse with Europa, the daughter of Agenor, and Rhadamanthus and his brothers Minos and Sarpedon were conceived. He married the widow Alcmene after the death of her

www.ebook3000.com

husband Amphitryon, who was killed fighting Erginus, the king of Boeotian Orchomenus. The ruler of Crete, Rhadamanthus was ousted from the throne by his brother Minos. Rhadamanthus married Alcmene and became the father of Erythus and Gortys. A lover of justice on earth, at death he was appointed one of the three judges of the dead in Hades along with Aeacus and Minos. In the Cretan tradition, Rhadamanthus is known as the son of Phaestus. For more information on his early family life, *see* Minos; Sarpedon (A). *See also* Aeacus; Europa; Styx.

Rhadamanthys (Greek) *see* Rhadamanthus.

Rhea (Greek)
Also known as: *Acrea, Bona Dea, Brimo, Cybele, Idaea, Magna Mater, Opis, Ops, Reia, Tellus, Tera, Titaea.*

Rhea is the oldest Greek goddess historically connected to the earth. She is known as the daughter of Phanesphobe, and wife of Cronus, who is also her brother. Other legends write that she is the daughter of Uranus and Gaea and mother of Zeus, Demeter, Hades, Hera, Hestia, and Poseidon. A syncretistic goddess, she was worshiped by many names, and had as many different attributes as she had adherents. She is well known for saving the life of Zeus by substituting a stone for him at birth which Cronus swallowed thinking it was Zeus. Rhea was particularly popular in Phrygia as Cybele, where she was regarded as a goddess of forest and wild animals. As the protectress of civic commerce she wore a symbolic castellated crown. Sacred dances were held in her honor in forests and on mountains, by her priest, the Corybantes. In the Pelasgian creation myth, Rhea and Cronus were the rulers of the planet Saturn. The name Brimo is used for Rhea as well as Demeter, Hecate and Persephone. She is shown in a carriage drawn by lions. *See also* Acamas (A); Adrastia; Cocytus; Corybantes; Cronus; Cybele; Demeter; Eurynome (A); Gaea; Hecate; Hestia; Nut; Oceanus; Ops; Persephone; Zeus.

Rhea-Silvia (Gallo-Roman) *see* Silvanus.

Rhene (Greek) *see* Ajax the Lesser.

Rhiannon (Gaul, Celtic)
Also known as: *Mare Goddess.*

Deity of horses. Moon goddess. Rhiannon is the daughter of Hefaidd Hen, Lord of the Underworld. Pwyll glimpsed Rhiannon galloping on her white mare. Entranced, he attempted to follow her but was unable to match her speed. He asked her father for her hand in marriage but was manipulated into making it possible for her former love to wed her. Rhiannon devised a way for Pwyll to outsmart them and the lovers were married. In time, they had a son, Gwri, later called Pryderi. Tragedy struck one night as the infant lay sleeping. Otherworld forces snatched him away. His nurses and attendants, fearful of being blamed, killed puppies and smeared the blood on Rhiannon's face while she was asleep. Rhiannon was found guilty of devouring her son. Her punishment was to carry every visitor to the court on her back (like a horse) and tell them of her wickedness. Years later Pryderi was returned by Teyron and Rhiannon was acquitted. When her husband died she married Manawyddan. Her tribulations were not over. She followed her son to an otherworldly castle where he became stuck to a golden bowl. Perhaps in an attempt to aid him, she also became stuck. Mother and son served a lengthy term in the Otherworld until Manawyddan was able to devise a plan to set them free. Her magic birds awoke the dead and put the living to sleep. In a number of sculptures, Rhiannon is accompanied by birds. The magic birds of Rhiannon sang to the beheaded Bran's head so he would not realize the passing of time. Compare Rhiannon to the Arthurian Vivien. Rhiannon is thought to be a later version of the great Celtic fertility queen, Rigatona. She is comparable to the continental "Horse Goddess," Epona, and has the attributes of the Greek goddess, Despoina. For information about Pryderi's absence, *see* Pryderi. *See also* Despoina; Epona; Manawydan Ap Llyr; Pryderi; Pwyll; Rhiannon.

Rhibus (India) *see* Ribhu.

Rhind (Teutonic) *see* Rind.

Rhode (Greek)
Rhode is the daughter of the sea god, Poseidon, and the sea goddess, Amphitrite. *See also* Amphitrite.

Rhodope (Greek)
Rhodope is the nymph who married Haemus. They called themselves Zeus and Hera and were changed into mountains. *See also* Haemus.

Ri (Akkadian) Goddess of light or water.

Ribhu (India) *see* Ribhus (The).

Ribhuksan (India) *see* Ribhus (The).

Ribhus, The *Rbhus* (Vedic; India)
Arbhu (in early times), *Rbhus, Rhibus, Ribhu* (singular), *Ribhuksan.*

Initially, Ribhus was an early Vedic sun deity. Later he became a wind deity and still later he became one of three artisan elf deities, known collectively as the Ribhus. The Ribhus, also called Ribhuksan, are Vaja and Vibhvan (also called Vibhu). They are the sons of Indra and the goddess of the morning light, Saranyu, who is the daughter of Tvashtri. In some legends, they are the sons of Sudhanvan, the "good archer." The Ribhus, artisan elves, learned their skills from their grandfather, Tvashtri. Cosmic chariots and horses for Indra and other deities were created by the Ribhus. They improved upon Tvashtri's creation of the miraculous bowl that held soma by making it into four cups. Their innovation made Tvashtri jealous and caused him to hide himself. The magic cow of plenty that could bestow all blessings was accredited to the Ribhus' skills. Elderly parents were revitalized by their powers. They assisted Indra in creating and holding up the heavens in some renditions. They made grass, herbs, and passages for streams. Renowned for their kindness, occasionally they engaged in overt rivalry with their grandfather Tvashtri. These actions may have reflected the animosity between Indra and Tvashtri during certain periods. Presented in human form, therefore of humble origins, they were refused entry into heaven. After death they were recognized for their magical contributions to the gods and their powers over nature and were granted immortality. As a creator, Indra is sometimes called a Ribhu. As a group, the Ribhus appear as stars or rays of the sun. The Adityas, Maruts and Vasus are depicted in the same manner. Sudhanvan the archer is thought to represent the sun's rays. The magic cow symbolizes a cloud. The horses and chariots are the winds and sun. The four cups represent the four quarters of the moon. The elderly parents are the sky and the earth. Compare to Indrani's Kalpa Tree. Compare the Ribhus to the Asvins. *See also* Adityas; Indra; Maruts; Saranyu; Tvastri; Vasus.

Rig (Norse; Teutonic)
Also known as: *Heimdall, Riger, Rigir.*
Aspect of Heimdall. This is the name of the god Heimdall when he created the three races of men. He is generally shown as a stately old man. *See* Heimdall.

Rig-Veda (India) An ancient book of creation myths.

Rigatona (Celtic) *see* Rhiannon.

Riger (Teutonic) *see* Rig.

Rigi (Micronesia) *see* Riiki and Rigi.

Rigir (Teutonic) *see* Rig.

Riiki and Rigi (Micronesia)
Also known as: *Lajnan* (Female), *Na Rena.*
Creators. Either of two eels or worms who raised the sky on the orders of Nareau. There are several versions of this worm, eel, or grub. In one Rigi helped Yelafaz raise the upper half of a mussel shell. In another, Rigi was a butterfly that helped Tabuerik separate the heavens from the earth. One strange version from the Marshall Island area is that Rigi or Na Rena came out of a rock. *See also* Lukelong; Nareau; Yelafaz.

Rima (Inca People, Peru)
Also known as: *Rimac.*
War god. Little information is available about Rima. He was called "He Who Speaks" and was consulted by chiefs before going into battle. He could be an oracle. *See also* Pachacamac.

Rimmon (Assyro-Babylonia)
Also known as: *Adad Rammon, Barku* (Syrian), *Mer* (Akkadian), *Tessub* (Cassite).
God of storm and lightning. He is similar to Adad, Adonis, Teshub. He is identified with Hadad or Addad. *See also* Hadad.

Rin-chen-bhyun-idan (Tibet) *see* Ratnasambhava.

Rind (Norse; Teutonic)
Also known as: *Rhind, Rinda, Rindar, Rinde.*
The giant goddess, Rind is the personification of the hard and frozen earth. She is the mistress or one of the wives of Odin and mother of Vali. *See also* Boe; Odin.

Rinda (Teutonic) *see* Odin; Rind.

Rindar (Teutonic) *see* Rind.

Rinde (Teutonic) *see* Rind.

Ringesum (Saora People, India)
God of the wind. *See also* Adununkisum.

Ringhorn (Teutonic) *see* Hringhorn.

Ringing Horn (Teutonic) *see* Gjall.

Ririt (Egypt) *see* Taueret.

Rishi *Rishis* (plural), *Rsi, Rshis.* (Brahmanic, Hindu, Vedic; India)
Also known as: *Angiras, Angiris, Prajapatis, Saptarshi* (collective title).
The Rishis were born from Brahma's mind. These sages, poets and priests preserved and handed down the knowledge imparted from the Vedas (sacred Sanskrit scriptures). The names and number of Rishis varies depending on the tradition. Some say there are seven and others ten or fourteen Rishis. The oldest list of seven rishis includes Atri, Bharadvaja, Gautama, Jamadagni, Kasyapa, Vasistha and Visvamitra. Together, the seven Rishis form the constellation of the Great Bear. A more common list includes Agastya, Angiras, Atri, Bhrigu, Kasyapa, Vasistha and Visvamitra. Matarisvan, said to be the author of the fourth Veda (also known as Atharvan, and is sometimes listed as a Rishi), brought the fire god, Agni, to a semi-divine patriarchal Rishi, named Angiras. His duties were to act as priest of the gods and lord of the sacrifice. He was a poet, astronomer and law-giver. In some accounts, he is said to be the son of Agni's daughter, Agneyi. Other renditions call him the father of Agni, Brihaspati and Utathya. Another patriarch mentioned is Manasa-Putra. There are three classes of Rishis, the Rishis of the gods, known as Devarishis, the priestly sages known as Brahmarishis, and the Rishis of royal origin known as Rajarishis. The spouses of the seven Rishis are known as the Krittika sisters, six of whom became the Pleiades. As the nurses of Karttikeya, only six sisters are usually mentioned. The seventh is sometimes mentioned as being a small star, dark or hidden near the Great Bear. The list of their names varies. One list mentions Abrayanti, Amba, Arundhati, Chupunika, Dula, Maghayanti, Nitatui, and Varshayanti. The Rishis are said to be the most visible stars of Ursa Major. *See also* Agastya; Agni; Brahma; Brighus; Brihaspati; Daksha; Karttikeya; Kasyapa (A); Kurma (Vishnu's avatar as a tortoise); Marichi (B); Manu; Narayana (C); Prajapati; Rambha (regarding Visamitra); Surabhi; Vasistha, Vedas; Visvakarma.

Rishis (India) *see* Rishi.

Rishtu (Assyro-Babylonian) *see* Apsu.

Rissalka (Slavic) *see* Rusalki.

Rivers (A) (Greek)
River deities. Guardians of youth. Oceanus and Tethys were reputed to have had three thousand daughters, known as the Oceanids, and three thousand sons, known as the Rivers. Some of the River deities are Achelous, the oldest and most famous, a shape changer and father of the Sirens; Acheron, whose heritage is attributed to Oceanus as his father and either Tethys, Gaea or Demeter as his mother; Alpheus, famous for his pursuit of Arethusa; Asopus, who attempted to rescue the kidnapped Aegina; Asterion, who helped Inachus and Cephissus judge between Poseidon and Hera to see who would be the patron deity of Argos; Achelous (Axius), the healing river deity who cured Alcmeon of insanity; Cebren, father of Oenone, Paris' first wife; Caecinus, possibly the father of Euthymus, the Olympic boxer who fought the ghost Hero to death; Cephissus, thought to be the father of Narcissus; Cocytus, deity of a river

www.ebook3000.com

in Hades said to flow with tears of the dead; Crimisus, the father of Acestes; Eridanus, the deity of a mythical river which could be the Po (Phaethon was said to have fallen from the sky into this river, leaving a lingering noxious odor which the Argonauts were able to smell some time later as they passed the area); and Halys, an unsuccessful contender in his pursuit of the virgin Sinope. Inachus was one of the referees asked to decide whether Hera or Poseidon should have possession of the Argolis. Ladon is noted for its beauty; the deity may be the father of the nymph Daphne, who disliked men, and Metope, who married her uncle Asopus; his brother Peneius has also been called their father. Other river deities include Maeander, the circuitous river and the deity Maeander, the father of Samia who married the king of the island Samos; Scamander, who became infuriated when Achilles filled his river, also named Scamander, with the bodies of dead Trojans and flooded the plain. In retaliation, the fire god Hephaistos dried the river. *See also* Achelous; Acheron; Acestes; Aegina; Alpheus; Cephissus; Cocytus; Hephaistos; Inachus; Oceanids; Oceanus; Phaethon; Pontus; Sinope.

Rivers (B) Sacred rivers of India. *See also* Byas; Ganga; Yami.
Rivers of Hvergelmir in Nifl-heim (Teutonic) *see* Elivagar.

Riyadarshana (India) *see* Mahavira.

rNam-parsnon-sras (Tibet) *see* Vairocana.

rNam-snan-mnon-byan (Tibet) *see* Manjusri.

rNam-t'os-sras-gsir-ch'en (Tibet) *see* Kuvera.

Robigus (Roman)
God of rust or mildew. A red or rust colored dog was sacrificed to Robigus, every April.

Robur (Celtic) Oak tree god. *See also* Abellio.

Rock-Sene (Gambia, Africa)
High god. Rock-Sene is generally considered the creator of the sun and moon and also a deity of the harvest and of thunderstorms. He is both kind and destructive.

Rod and Rozanitsa (Slavic)
Deities supplanted by Perun. *See also* Perun.

Rodasi (India)
She is the spouse of the storm god Rudra. *See also* Maruts; Rudra.

Rodu (Sumer) God of fruitfulness.

Rogo-tumu-here (Oceanic)
Also known as: *Rogo*.
Demon octopus. He once abducted Tangaroa's daughter-in-law while she was surfing. Tangaroa rushed to the rescue in his canoe. After a bitter struggle, Tangaroa overcame the octopus and saved his daughter-in-law. *See also* Faumea.

Rohe (Polynesia; New Zealand)
Along with Hine-nui-te-po, Rohe ruled the afterworld. He rules three of the ten levels. *See also* Hine-nui-te-po; Miru.

Rohini (India) *see* Bala-Rama; Krishna; Pushan; Rudra; Soma.

Roma *Rome* (Greek)
Goddess of war. Roma (meaning strength), the eponym of Rome, is the daughter of Evander and Deidamia. Her siblings are Pallas, Pallantia, Sarpedon and possibly Dyne (meaning power). She is depicted as a tall woman with a noble air about her. She wears a helmet and a long robe and resembles Athena. *See also* Evander (B); Sarpedon (B).

Roma-Tane (Polynesia)
God of Paradise. He was worshiped by the Arioi, who were priests or entertainers on the islands around Tahiti. *See also* Oro; Tane.

Romulus and Remus (Roman, assimilated to Greek)
Also known as: (Romulus) *Quirinus*.
Culture heroes. They are twin brothers who are the sons of Mars and the vestal virgin Sylvia (Rhea Silvia). Their mother, condemned to be buried alive, set the twins adrift on the Tiber. They were rescued and suckled by a she-wolf. Later Romulus killed Remus and founded the city of Rome, which he named after himself, and became its first king. Builders from Etruria were called to construct the city. They taught him the written rules and sacred ceremonies to be observed. A round pit was dug where the Court of Assembly now stands. Each worker brought along a small piece of earth from his area. It was thrown into the pit along with symbolic fruits of the earth. With a plow drawn by a bull and a cow, Romulus drew the boundary of the city in a circle. Romulus also killed King Acron after the rape of the Sabine women. The pit was called the "mundus," which also means "cosmos." It was covered by a huge stone known as the "soul stone." It is said that on certain days the stone was removed and the spirits of the dead rose from the center of the pit. Rome was known as the square city, yet is was built in a circular shape. Many refer to this design as an architectural mandala. Compare to other infants taken from mothers. Pryderi; Rhea Silvia; Zeus.

Rona (Polynesia)
"Tide Controller." She is the daughter of Tangaroa, the sea god. One night as she carried a bucket of water home to her children, clouds had slipped across her path, making the way dark. Rona slipped and hurt her foot against a root. Annoyed, she said unkind things about the moon. The moon overheard her and put a curse on the Maori People. Today, one can see Rona on the moon. When Rona upsets her bucket, it rains.

Rongerik and Rongelap (Marshall Islands)
Heros. They are two brothers who are a part of the family of Palulop. *See also* Palulop.

Rongo (Polynesia)
Also known as: *Lono* (Hawaii), *Lono Rongo-Ma-Tane, Ono, Orongo, Rono.*
God of cultivated food. He is also called a god of night. He is the twin brother of Tangaroa or Haumia-tikitiki and the son of Papa and Tangaloa or Vatea, depending on the legend. In one version, as the child of Papa and Vatea, he is known as the brother of Tangaroa, Tonga-iti, Tangiia, and Tane. Other versions say he is known as the son of Rangi and Papa and the brother of Haumia. He was known as Ono in the Marquesas and Lono in Hawaii. In one myth, he descends on a rainbow to find a mortal wife. In a Mangaia Island myth, Rongo, an underworld war god is the son of Papa-Tu-Anuku (often called Papa),

the great mother of the gods, and Vatea. With his mother's help, his twin brother Tangaroa was driven from his position as king of the island, and Rongo took his place. Later, the island was submerged after a natural disaster. Eventually it surfaced along with a new king called Rangi who said he was the grandson of Rongo. *See also* Haumia; Hotu-papa; Lono; Papa (A); Po; Rangi; Tangaroa; Tane; Tawhiri; Tu; Vari (A); Vatea.

Rono (Polynesia) *see* Rongo.

Roptatyr (Teutonic) An alternate name for Odin.

Rose-Apple Land (India) *see* Jambudvipa.

Roskva (Norse; Teutonic)

Roskva, a servant girl and her brother, Thialfi, were given to Thor by a peasant in payment for a mischievous deed of Loki. Little is said of Roskva, but Thialfi lost a race with Hugi in one of Thor's adventures. Some say Roskva is the daughter of Orvandel.

Rosmerta (Gallo-Roman) *see* Mercury (B).

Rshis (India) *see* Rishi.

Rsi (India) *see* Rishi.

Ru (Polynesia) *see* Rua; Rupe.

Ru-piny (Africa) *see* Woko.

Rua (Polynesia)

Also known as: *Ru, Rua-Haka, Rua-Haku.*

God of the ocean. God of craftsmen. Rua is the Abyss who brought forth the octopus Tumu-ra'i-feuna that held heaven (Atea) and earth together causing darkness. It is Rua who caused the great flood because a fisherman's hook became entangled in his hair. Even though angry, Rua forgave the fisherman but took revenge by flooding the world. Only the fisherman, a friend, a hog, a dog, and several hens were allowed to live until the waters returned to the proper level. Rua is possibly the same as the ocean deity, Tinirau. Rua might be the same as Ruahatu of Tahiti. *See also* Tinirau.

Rua-Haka (Polynesia) *see* Rua.

Ruad Ro-Fhessa (Celtic) *see* Dagda.

Ruad Rofhesa (Celtic) *see* Dagda.

Ruadan (Irish) *see* Brigit.

Ruange (Polynesia) *see* Rangi.

Rudra (Brahmanic, Hindu, Vedic; India).

Also known as: *Araga* ("the burning midsummer sun"), *Bhutapati* (Prince of Demons), *Mahadeva* ("Great God;" a praise name for Rudra-Shiva), *Mrigavyadha* (Piercer of the Deer), *Pasupati* (Lord of Cattle), *Prajapati, Siva, Tryambaka* (Three-Mothered or Three-Eyed).

Rudra is the deity of storms and winds, the divine physician, lord of cattle and wildlife, lord of song and sacrifices, God of the dead and the underworld, and the deity of robbers and beggars. An early Vedic god, he is the son of the goddess of dawn Ushas and Prajapati. Rudra is the father of the Maruts, also known as Rudras by the cow goddess Prisni or perhaps Rodasi or Diti. His other consorts are Rudrani, the cruel goddess of bloody sacrifices, also known as Devi-Uma-Kali; Ambika, an aspect of Devi; Durga also an aspect of Devi; Parvati, another aspect of Devi; Uma Haimavati and Suaha, the daughter of Daksha. His spouse Sati, known as the virtuous wife, committed suicide when Rudra died. Suaha is also called the wife of Agni and perhaps the mother of Karttikeya. In the *Rig-Veda*, Rudra is portrayed as compassionate and generous. Later, in the *Brahmanas*, with Rudrani, the storm goddess who spreads disease and death, as his wife, he is a grotesque and dreadful god. Known as the "God of Storms" and the "Lord of Time and Death," he is the red god of storms, winds and mountains. He is also a deity of the dead and a demon skilled in archery, who brought disease with his arrows. When appeased, he is a healer and creator of life, and protector of god of cattle and wild life. Under the name Mrigavyadha (piercer of the deer), he wounded Prajapati who had committed incest with his daughter, Rohini, who changed herself into a gazelle or deer. To save himself from Rudra's wrath, Prajapati promised he would make Rudra king of animals, which is how Rudra became known as Pasupati "Lord of Cattle." There are other records indicating that the Mother of the Gods, Aditi, is the mother of the Rudras. In later times, in the Puranas, Brahma was sacrificing to the fire made from his own effulgence. He wiped perspiration from his forehead with a piece of wood and cut himself. A drop of blood fell into the fire. From the blood, by the will of Shiva, sprang Rudra, who separated himself into eleven beings. Rudra chose not to adore Brahma but instead sought Shiva. In his terrible aspect, Rudra is described as a wild tempered, murderous man, with a swarthy build, who spits like a beast. He rides a boar, and shoots the arrows of disease and death at mortals and gods alike. He is also described as having a red face and a blue neck. Sometimes he is shown with red hair. His animal is the mole and his home, the crossroads. In his beneficent aspect he is thought to be as dazzling as the sun. He is also depicted with brown skin and braided hair. His name, Tryambaka, is used when accompanied by the three mother-goddesses and indicates descent from three mothers which may symbolize the triple division of the universe, or the mystical third eye. When he emerged from Brahma's blood, he had five heads, ten hands, and fifteen eyes. For remedial purposes he used cow urine and possibly leeches. For other Vedic healers, *see also* Agni, Asvins, Diti, Indra, Soma. (Of this group, Rudra is the only one who did not partake of soma.) Compare Rudra to the Greeks Hermes and Typhon. Rudra shares the characteristics of Agni (q.v.). *See also* Aditi; Brahma; Brihaspati; Daksha; Devi; Diti; Durga; Kasyapa; Maruts; Parvati; Pishachas; Sati (A); Shiva; Ushas; Vajrapani; Vedas.

Rudra-Shiva (India) *see* Agni; Rudra; Shiva.

Rudrani (India)

Goddess of bloody sacrifices. *See also* Devi; Kali; Rudra.

Rudriyas (India)

They are the sons of Rudra (q.v.). *See also* Maruts.

Rugevit (Slavic)

Also known as: *Rugievit.*

God of war. He has seven faces, wears a bull's head on his

www.ebook3000.com

chest and a swan with spread wings on his curly hair. He is similar to Radigast, Svantovit and Yarovit.

Rugievit (Slavic) *see* Rugevit.

Ruha D'qudsha (Mandean Gnostic)

Rukma (India) Brother of Rukmini. *See also* Sisupala.

Rukmini (India)
Mother of Bhadracharu by Krishna. *See also* Jara-Sandha; Kama (A); Krishna; Lakshmi; Satyabhama; Sisupala.

Ruma (India) Queen of the Apes. *See also* Sugriva.

Rumar (India) *see* Aruna.

Rumia (Polynesian)
Rumia is the shell that existed in the primeval darkness known as Po. The inner shell of Rumia is known as Timi-iti. Within Timi-iti is Ra'a-ti, the place where the supreme god, Ta'aroa created himself. *See also* Po; Ta'aroa.

Rumina (Roman) She is the goddess of nursing mothers.

Rumor (Greek)
The spreader of rumors, she is the last daughter of mother earth, Gaea.

Runeeka (India) *see* Parashur Rama.

Runes (Norse; Teutonic)
The Runes is a system of writing said to be invented by Odin. It was reputed he cut the magic writing on the teeth of his horse, Sleipnir, with the sword Gungnir. Odin had the gift of wisdom and runes. As a talisman it is used for protection. Today, the Runes are used as a method to foretell the future.

Rupastra (India) *see* Kama.

Rupe (Polynesia)
Also known as: *Ru.*
He is the winged hero, brother of Hina. *See also* Hina; Maui.

Ruqaiyah (Islamic) *see* Mohammed.

Ruru (India) "Hound." *See also* Shiva.

Rusa (Semitic) *see* Allat.

Rusalkas (Slavic)
Rusalki, Rusalky, Rissalka (singular).
Also known as: *Vili.*
Winged female spirits of the water and woodland. In some myths, the Rusalkas are the spirits of women who die before marriage and then become water sprites. In other myths, they are the unbaptized souls of dead children, or the spirit of any mortal youth who died by drowning. The Rusalkas possess eternal youth, have beautiful voices and unusual powers. Rusalkas in the south are soft and gentle, those in the north are frigid and stern. In summer they reside in forests and in winter they live in water. Some believe the Rusalkas live in certain green trees which some believe are the homes of the dead. The Rusalkas sometimes send storms and rain. They can be charming allies or harmful enemies. In their beautiful form, they have a reputation for enticing men to succumb to them and then they drag them into the sea. They hate absinthe, so if one holds a leaf of it in one hand the Rusalkas can be overcome or defeated. They have long green hair which enables them to tickle mortals to death. They are shown as beautiful maidens or very ugly, pallid young women with dishevelled hair. Compare to the Greek Naiads and Sirens. *See also* Nymphs for Greek classes of nymphs.

Rusalki (Russia) *see* Rusalkas.

Russalka (Russia) *see* Rusalkas.

Rustam (Persia)
Deified king. He is the father of Zal who exposed his son on a mountain top where the vulture Simurgh rescued him. The legend of Rustam, Sam, and Zal is a long tale of the various kings of ancient Persia. *See also* Sam; Simurgh; Zal.

Rutali, The (Greek) *see* Evander (B).

Rutbe (Guaymi People, Costa Rica) *see* Nancomala.

Ruwa (Kilimanjaro, Djaga People, Africa)
Supreme deity. He broke open the pot which held mortals prisoners. Ruwa then planted a yam called Ukaho which was forbidden to all humans. In a tale similar to Adam and Eve, the mortals ate the yam which made them vulnerable to disease.

Ryangombe (Baziba People, Africa)
God of cattle. Ryangombe is the son of Wamara, the father of gods (q.v.).

Ryojusen (Japan)
Also known as: *Grdhra-Kuta.*
Japanese Buddhist heaven.

Ryu-Wo (Buddhist; Japan)
Also known as: *Ryujin.*
King of dragons. Sea king. Ryu-Wo is the dragon king of the Ryujins, and the guardian of Buddhas's religion. Ryu-wo has a human body, though he wears a serpent on his crown. His retainers are serpents, fish and other marine monsters.

Ryujin (Japan) *see* Ryu-wo.

S

Sa (A) (Egypt)
Life Preserver for travelers on the river. The hippopotamus goddess, Tauret, is shown standing upright with her hand on the life preserver, Sa, which is made of papyrus. *See also* Tauret.

Sa (B) (Sumer) Ancient Sumerian god. *See also* Nabu.

Sa-bdag (Tibet)
The Sa-bdag are spirits known as earth-movers who live in soil, lakes, springs, and houses. The image of the local Sa-bdag is placed inside the outer gateway. It is offered wine and bloody sacrifices. *See also* Nats (Burma).

Sa-Yori-Bime-No-Mikoto (Japan) *see* Amaterasu; Three Goddesses of Munakata.

Saa (Egypt) *see* Sia.

Saa-Set (Egypt)
Serpent in afterworld. Huge serpent that stands on his tail. He is in the first sector of Tuat. *See also* Akeneh.

Saba-Leippya (Burma)
Agricultural nats (spirits). *See also* Nats.

Sabala (India) "Heavenly Hound." *See also* Yama.

Sabaoth (Chaldea, Syria)
Also known as: *Iahweh Sabaoth, Iao-sabaoth, Ibraoth, Lord Sabaoth, Sabaoth the Adamas.*
Possibly an underworld deity. Archon and ruler of the fifth sphere. One of the seven Hebdomad or Ogdoad deities coming indirectly from Sophia. Sabaoth is the grandson of Ialdabaoth and the son of Ialdabaoth. He is the guard of the gate called Portal of Life which opens into the lower zone of heaven. There are Gnostic texts that associate Sabaoth with the god Osoronnophris who might have been an Egyptian deity during the time of Moses. He has a chariot with a four-faced cherub and angels. *See also* Archons; Barbelo; Ialdabaoth; Ogdoad; Pistis Sophia; Tuat.

Sabaoth Adamas (Gnostics) *see* Adamas.

Sabazios (Gnostic) *see* Sabizios.

Sabazius (Greek)
Sabazius is an epithet of Dionysus (q.v.). *See also* Cybele.

Sabines (Gallo-Roman) *see* Silvanus.

Sabitu (Babylon)
This goddess rules the land along the sea of death. *See also* Siduri.

Sabizios (Armenia, Chaldea, Phrygia, Syria, Thrace)
Also known as: *Iahweh Sabaoth* (possibly), *Sabazios, Zagreus.*
Sabizios is possibly a serpent creator deity or a serpent god of the underworld. He might have been one of the deities of the Valentinus Gnostic sect. Sabizios is sometimes associated with the goddess Barbelo who was said to be his mother. He is is also identified with Jehovah. Some say he was worshiped under the name of Zagreus by the Thracians and Phrygians. *See also* Barbelo; Ialdabaoth; Sabaoth.

Sacharis (Egypt) *see* Seker.

Sachi (India) *see* Sagara.

Saci (India) *see* Indra; Indrani.

Sacontala (India) *see* Shakuntala.

Sacred Tooth (Buddhist)
The tooth of Guatama Buddha which is enshrined in Kandy, Sri Lanka.

Sacti (India) *see* Shakti.

Sacy-Perere (Brazil) Happy forest spirits.

Sa'd (Arabic) *see* Allat.

Sadurn (Irish) She is the sister of Gwen, the goddess of smiles.

Sadwes (Persia) *see* Hapto-iringa.

Sae-no-Kami (Japan)
God of roads. *See also* Chimata-no-Kami; Sanzu-no-Kawa.

Saehrimni (Teutonic) *see* Saehrimnir.

Saehrimnir *Saehrimni* (Teutonic)
Saehrimnir is the divine boar who daily is killed, boiled by the cook, Andhrimnir, in the cauldron Eldhrimnir. He provides the food for the gods. No matter how much is eaten at each meal, the supply never runs out. Each morning the boar comes to life again.

Saeming (Teutonic) *see* Odin; Seming; Thor.

Saena (Persia) *see* Simurgh.

Saga (Teutonic)
Also known as: *Laga.*
Goddess of history, legend and song. She is one of the wives and daily drinking partner of Odin. He visits her in the crystal hall of Sokvabek. *See also* Odin.

Sagar (Islam)
A fiery place reserved for the Magi in the fifth section of the Islamic Hell (q.v.).

Sagara (Hindu; India)
The grandson of Bahu, and son of Sachi, the king of Ayodhya, Sagara spent seven years in his mother's womb before birth. His father, driven from his throne by the Haihayas, died

www.ebook3000.com

in exile in the jungle before he was born. When Sagara was old enough, Aurva, the sage, gave him a magic weapon known as the Agneyastra that allowed him to exterminate most of his father's enemies and reclaim the throne. Aurva's powers allowed Sagara's spouse Sumati, the daughter of Kasyapa, to give birth to sixty thousand sons. His other spouse, Kesini, the daughter of Vidharba had one son, Asamanjas. This son was troubled and Sagara eventually abandoned him. The other sixty thousand sons also had behavioral problems. The gods complained to the great god Vishnu and the sage Kapila about their behavior. During his thirty thousand year reign he constantly attempted to bring the Ganges River down from the celestial realm, without success. In an attempt to usurp Indra, he decided to perform the horse sacrifice to signify his claim to universal dominion. When Indra caught wind of the plan, he assumed the disguise of a demon and drove the horse to the underworld. Infuriated, Sagara sent his sixty thousand sons, who had been responsible for guarding it, in search of the animal. They dug a deep pit and ended in Patala, the underworld, where they found the horse and Kapila. When they accused the sage of stealing their father's horse, he reduced them to ashes with the powerful rays of his eyes. Anshumat, the son of Asamanjas and the grandson of Sagara searched for his uncles. Eventually he came upon their ashes, Kapila, and the horse in the pit. This huge hole was named Sagara which means "ocean." Kapila told Anshumat that his uncles could only be purified by the waters that ran through Vishnu's feet. He did permit the grandson to return the horse to Sagara. It was the grandson of Anshumat, Bhagiratha, who dug the bed for the river of heaven that cleanses the sins of all sinners, the Ganges. Her waters reached the underworld and purified the ashes of Sagara's sons so that they could enter Swarga. *See also* Ganga; Kasyapa (A); Patala; Sumati; Swarga; Vishnu.

Sagbata (Dahomey, Fon People, Africa)
Smallpox deity. Associated with the god Dan, they are a group of four Vudus, consisting of Sagbata, the earth god who spread smallpox among mortals; Xevioso, god of thunder; Gun, god of iron; Avlekete (also known as Agbe), god of the sea. Sagbata is thought by some to be the son of Mawu. *See also* Agbe; Mawu; Vodu; Xevioso.

Sahadeva (India)
He is a Pandu prince and the twin of Nakula. *See also* Asvins; Madri; Pandavas.

Sahaganya (India) *see* Apsarases.

Sahar (Middle Eastern) *see* Elohim.

Sahasrabhuja (Buddhist; Nepal)
Sahasrabhuja is an aspect of Avalokitesvara. He has eleven heads and one thousand arms. The basic image of Avalokitesvara is depicted with eleven heads and eight arms. The other arms form a mandala and are sometimes marked with eyes. The eleventh head at the top is said to be that of his parent, Tathagata. The heads have a peaceful countenance with the exception of the tenth head which looks angry. His main hands are held against his chest; the upper hands hold the rosary and the full blown lotus. The other four hands display a jewel on the right and a pot and bow and arrow on the left. *See also* Amoghapasa Lokeswar; Avalokitesvara; Tathagata.

Sahasramuska (India)
Thousand Testicled One. *See also* Indra.

Saho-yama-hime (Japan) The goddess of spring.

Sai-no-Kami (Japan) *see* Sanzu-no-kawa.

St. Bridget (Celtic) *see* Brigantia; Brigit.

Saint Brigit (Irish) *see* Brigit.

St. George *see* Anat; Anhur.

Sa'ir (Islam)
This is the fourth state in the Islamic Hell. It is reserved for Sabians (people from Saba, an ancient Arab state).

Sais (Egypt) *see* Neith.

Saites (Greek) *see* Sapi.

Saiva (Lapp) Protective Deity.

Saiyamkoob (Maya People, Yucatan)
Also known as: *The Adjusters.*
First people. Dwarfs built the now ruined cities in total darkness long before there was light from the sun. At that time a living bloody rope came from the sky and brought them food. Once the sun appeared the people turned to stone. The rope was cut or broken and it divided the earth and sky. At this time a flood visited earth and destroyed the people. The second people, known as the Tsolob (The Offenders), were also destroyed by flood. The Maya lived in the third world and they were also destroyed by a flood. The present world is an admixture of all the races of the Yucatan. There was no indication of how this world will end. *See also* Legend of the Four Suns.

Sak (Egypt)
Composite animal. The Sak is an animal with the front of a lion, the rear part a horse, the head of a hawk, and a tail that terminates in a lotus-like flower. She is shown with a collar around her neck and with bars and stripes on her body, which has eight breasts.

Saka-no-mi-wo-no-kami (Japan)
God of the mountain slope. *See also* Naka-Yama-Tsu-Mi; Sengen.

Sakarabru (Guinea, Africa)
God of darkness. God of medicine, justice and retribution. Sakarabru, represented as a ball of maize, can be a demon or a healer. He appears during the changes of seasons and the new moon.

Sakhmis (Egypt) *see* Sekhmet.

Saki (India) *see* Indrani.

Sakko (India) *see* Sakra.

Sakra *Sakko* (Buddhist, Jain; India)
Sakra is the divine spirit who received Buddha (Brahma) in a golden bowl at birth. He is the chief Deva, and when Buddha was born, he ordered ten thousand sankhas to be blown. The shank or conch shell *(Concha Veneris)*, was used as a "sounder" to drive away demons. He is referred to as one of the twelve Adityas. In the Jain tradition, Sakra, the "King of Gods in

Heaven," decided that the fetus of Mahavira should be transferred from the womb of Devananda to the womb of Trisala. The name Sakra is also an epithet for Indra and a name for India. *See also* Adityas; Buddha; Indra; Mahavira.

Sakta-Sura (India) A demon. *See also* Krishna.

Sakti (India) *see* Shakti.

Saktis (Hindu) *see* Astamatrikas.

Sakunadevatas (India) *see* Devis.

Sakuni (India) A demon. *See also* Duryodhana.

Sakuntala (India) *see* Apsarases.

Sakya-t'ub-pa-dam-g-Nas-brtan (Tibet) *see* Sakyamuni.

Sakyamuni (Buddhist; India)

Also known as: *Buddha, Gautama, Gotama, Sakya-t'ub-pa-dam-g-Nas-brtan* (Tibet), *Sha-kya-tup-pa* (Tibet), *Shih-chia-mou-ni* (China), *Siddartha* (He Who Has Fulfilled the Object of His Earthly Coming), Tathagata.

Born Siddartha, son of Maya by divine birth, he became the monk Gautama, also called Sakyamuni, when he renounced the world. He was a member of the Sakya tribe belonging to the Gautama clan. Sakyamuni means "the sage of the Sakya tribe." He is the third Buddha and the fourth Manushi-Buddha, lord of the present world cycle. His asana (position) is dhyana (meditative). He sits on a red lotus. His mudras (positions) are dhyana bhumisparsa (the right arm pendant over the right knee with the hand and palm inward with all fingers touching the lotus throne), dharmacakra (the left hand covering the right hand against the breast), or varada (arm pendant, fingers extended outward and palm turned outward), or vitarka (arm bent, palm outward and all fingers extended upward, except the index finger which touches the tip of the thumb). His mount is a lion throne and his color is gold. His emblem is a patra (begging bowl). *See also* Akshobhya; Buddha; Kishimojin; Manushi-Buddhas; Maya; Samantabhadra; Vajrapani.

Salachia (Roman) *see* Salacia.

Salacia *Salachia* (Roman)

Also known as: *Amphitrite* (Greek).

Goddess of salt water and springs. *See also* Amphitrite; Neptune; Nereids; Poseidon.

Salagrama (Hindu; India)

The Salagrama are small rounded stones that symbolize the living presence of Vishnu. They are the objects of daily worship. Their river-worn shell is flint-like ammonite and they are different colors but generally black. They have one or more holes in the side. They are usually found in the Gandaki River, one of the tributaries of the Ganges.

Salamis (Greek)

She is the daughter of Asopus and Metope and sister to twenty-one siblings. Salamis was once kidnapped by Poseidon. *See also* Aegina; Asopus; Metope; Pelasgus; Thebe.

Salema and Sakia (Arabic)

Gods of rain and of health. Sakia is an ancient Arab god who was worshiped as the provider of rain and Salema is a health provider.

Sali Kanya (India) Mountain Maiden. *See also* Parvati.

Salii (Roman)

They are the priests of Mars who guard his sacred shield, called the Anchile.

Salkis (Egypt) *see* Selket; Serqet.

Salm (Persia) *see* Cairima.

Salmacis (Greek)

Salmacis is the name of the nymph of the fountain of the same name. All men who drink from its waters become effeminate. *See also* Hermaphroditus.

Salmon (Babylon) *see* Saramana.

Salmoneus (Greek)

King of Elis. His parents are Aeolus and Enarete. They have seven sons and seven daughters. (For a list of their names, *see* Enarete.) Salmoneus' wife Alcidice died giving birth to a daughter, Tyro. His next wife, Sidero, imprisoned Tyro, but she was rescued by her sons, Neleus and Pelias. Sisyphus threw Salmoneus out of Thessaly. When he started imitating thunder and lightning, it did not strike the great god Zeus as humorous. He killed Salmoneus and sent him to the underworld. *See also* Aeolus (A); Canace; Enarete; Sisyphus.

Salmoxis (Greek) *see* Bacchus; Dionysus.

Saltu (Babylon)

This deity of discord was created by Ea as an opponent or rival of Ishtar. *See also* Ea; Ishtar.

Salus (Roman)

Goddess of health, prosperity, and public welfare.

Sam (Persia)

High god. Deified King. Sam exposed his son Zal on a mountain top where the vulture Simurgh rescued him. *See also* Rustam; Simurgh.

Samana (India) The Leveller. *See also* Yama.

Samanta-Bhadra (India) *see* Samantabhadra.

Samantabhadra (Buddhist; India) *Samanta-Bhadra*

Also known as: *Fugen Bosatsu* (Japan), *Fugen En-myo* ("Indestructible Existence," Japan), *Jitoku* (Japan), *Lokanatha, P'u-hein* (China), *Zuntu-zang-po* (Tibet).

Samantabhadra, the deity of universal goodness and happiness, is one of the five Buddhist creators of the universe. The other four are Avalokitesvara, Ratnapani, Vajrapani, and Visvapani. Samantabhadra is the head of one of the three groups of boddhisattvas. Each group contains sixteen boddhisattvas. The other two groups are lead by Buddha Maitreya (Future Buddha). Samantabhadra is a member of a group of eight Buddhas known as Dhyanibodhisattva. The other Buddhas in this group are Akasagarbha, Avalokitesvara, Kshitigarbha, Mahasthamaprapta, Maitreya, Manjusri, Sarvanivaranaveskambhin, and Trailokyavijaya. Sometimes Samantabhadra or Vajrapani substitute for one of the eight. The Dhyanibodhisattva evolved from the meditations of the Dhyani Buddhas. The mortal manifestations of the Dhyanibodhisattva are known as Manushi-Buddhas. They come as teachers and live on earth for a short

www.ebook3000.com

neous feeling. We can actually make ourselves relaxed and happy by taking advantage of this built-in human mechanism. It's natural. Just do it! Learning to smile down to the abdominal area and maintain the awareness of the relaxed, smiling sensation in the Tan Tien is the first step in training the *Second Brain!* Think about it: Pure awareness and consciousness can change attitudes and emotions carried in the DNA.

Remember: Number 1: "Empty your mind down to the Tan Tien, and fill the Tan Tien with Chi." An axiom in the Tao is, where the mind goes the Chi follows. And, Number 2: "When your mind is empty, it will be filled!" This means that when the organs have extra energy, the extra organ energy will rise up and fill the brain with Chi.



***Fig. 3.24** When the mind is empty, transformed energy from all the organs can charge the brain with Chi.*

Practice

Three Minds into One: 'Yi' Power

Smile into your heart. Lower the Observation Mind, then the Heart Mind down to the Tan Tien. With the Feeling/Awareness Mind, Spiral the three minds into one.

1. Smile into your heart. Make it feel soft. Feel love. Feel joy. Feel happy and feel compassion in your heart. Feel the heart spiral.
2. Spiral in the upper mind. Lower your upper mind, the observation mind, down to the Tan Tien in your navel area.
3. Turn the consciousness in your heart, activated by your love and softness, down to your Tan Tien.
4. Combine the upper and middle minds with the energy of the feeling/awareness mind of the entire nervous system – the Second Brain in the abdomen. Merge the three minds into one mind by spiraling their energy, blending them together as one in the Tan Tien.

When the three minds merge into one they become the 'Yi' power, the three-mind power – activate the spiraling at the mideyebrow, crown and the soles of your feet – expand to the universe in six directions: up, down, front, back, left and right. Once you get it, the Yi, we will start to activate the six directions and the three fires.


Mideyebrow
Make the Heart feel soft
Heart
Three Minds into One Yi Mind Power
A.
B.
Crown

***Fig. 3.25** **A.** The Heart softens like a rose blossoming.*

***B.** Spiral the Upper Tan Tien into the Lowest Tan Tien and Three Mind 'Yi' Power.*

period. Samantabhadra's consort is Dharmavajra. In Tibet, in the Red Cap sect, known as Mying-ma-pa, Samantabhadra is the same as Adibuddha. The Red Cap tradition was founded in the ninth century C.E. by Padma Sambhav. An ancient guru, and perfected being, he is the most important of the Mahsiddhas (Tantric saints). In Tibet, the wife of Samantabhadra is the goddess Kuntu-bzang-mo, the Divine Mother. In Japan, Samantabhadra is known as Fugen Bosatsu and he is considered one of the most important boddhisattvas. Fugen Bosatsu, also called Jitoku, personifies wisdom, compassion, cordiality and constancy. He is known as the "Sweeper of Pine Needles." Fugen is paired with Manjursi among the boddhisattvas. Fugen, the god of compassion and bestower of longevity, understands the motives and actions of all mortals. He is often shown wearing a crown, seated on a lotus with his legs crossed. In his left hand he holds a lotus surmounted by a sword surrounded by flames. His right hand is slightly raised, the palm turned outward and the fingers stretched outward, except the fourth and fifth fingers, which are bent. He is also depicted with multiple arms. In one depiction he has twenty arms, each holding an object. As a youth he is shown seated on a lotus, sometimes holding a manuscript. The lotus is upheld by one or more elephants, the symbol of longevity. Samantabhadra is depicted as blue or green. He is shown nude, without ornaments with and without his consort Dharmavajra. His mudra is vajrahumkara (his wrists are crossed at the breast and he is holding ghanta and vajra, a bell with a thunderbolt handle), the symbol of the supreme and eternal Buddha. A vajra is also the thunderbolt of Indra. In his form of Lokanatha, he is yellow, carries the jewel on a lotus and makes the gesture of charity known as the varada mudra. The arm is pendant, all fingers extended downward and the palm turned outward. As Lokanatha he is known as the assistant of Avalokitesvara. *See also* Adibuddha; Amrtakundali; Avalokitesvara; Dam-c'an-r-do-rje-legs-pa; Dhyani Buddhas; Dhyanibodhisattvas; Kshitigarbha; Kunto-Bzang-mo; Maitreya; Manjusri; Manushi-Buddhas; Sakyamuni; Trailokyavijaya; Vajrapani.

Samantaka (India) *see* Kama (A).

Samantamukha (Buddhist; Nepal)
Samantamukha is a manifestation of Avalokiteswara. Known as the "All Pitying One" or the "All Sided One," he looks in all directions to protect all creatures. His numerous heads and eyes enable him to concentrate on the most auspicious way to redeem mortals. The three tiers of heads indicate that he looks down on the three worlds: the world of desire, the world of form and the world of non-form. He is shown with eleven heads on three tiers, eleven brains and twenty-two eyes. *See also* Avalokitesvara.

Samantapancaka (India)
Brahma's sacred altar. *See also* Brahma.

Samas (Northern Semitic) Sun god. *See also* Sams; Shamash.

Samavurti (India) The Impartial Judge. *See also* Yama.

Samaya-Tara (India) *see* Amoghasiddhi.

Samba (India) *see* Krishna.

Sambara (A) *Shambara* (India)
Draught demon. *See also* Krishna; Pradyuma.

Sambara (B) (Buddhist; Nepal)
Also known as: *Chakra Sambara, The Great Defender.*
Maha Sambara, the deity of supreme bliss, has seventeen heads in five rows, four in each row and one at the top. All his faces have bulging eyes, gaping mouths and fangs. He has two sets of seventeen and eighteen arms, for a total of seventy arms. He has four primary arms which hold the goddess of bliss, Vajravarahi (Nepal). Each of his feet has six toes and he stands in the alidh asana posture (stepping to the left with the right leg straight and the left leg bent). He is also described with twelve arms and four heads, each with three eyes. He holds various symbolic objects and is shown embracing Vajrabarahi. Sambara is used in spiritual exercises; meditation and yoga practices. *See also* Chakra Sambara; Dorje Phogmo (for Vajravarhi); Pradyuma; Varahi.

Sambo-kojin (Japan)
Kitchen god, with three faces and two pairs of hands.

Samdhya (India) Goddess of Twilight. *See also* Ratri.

Samdya (India) *see* Sandhya.

Samgna (India) *see* Sanja.

Samhitas, The (India)
The Samhitas is the name given to the four sacred books: the *Rig-Veda, Sama-Veda, Yajur-Veda, Atharva-Veda,* of the Vedas that are generally considered to form a unit.

Samia (Greek)
She is the daughter of the river god Maeander and the wife of of the Argonaut, king of Samos, Ancaeus. *See also* Ancaeus; Maeander; Rivers.

Samildanach (Celtic) *see* Lugh.

Samjuna (India) *see* Sanja.

Sammunus (Roman)
Probably an epithet of Hades (q.v.). *See also* Tina.

Sammuramat (Armenia)
Also known as: *Ishtar, Semiramis* (Syria).
See Atargatis; Ishtar; Semiramis; Sharis.

Samnati (India) *see* Devaki.

Sampati (Hindu; India)
The son of Garuda and the assistant to Rama, Sampati is a gigantic speaking eagle. He was instrumental in locating Rama's spouse, Sita, who had been abducted by the evil demon, Ravana. *See also* Garuda; Rama; Ravana; Sita.

Sampo (Finland)
Sampo is the magic mill that grinds out prosperity. It is held by a wicked giant, and there are many battles over its possession. It was forged by Ilmarinen. *See also* Louhi; Vainamoinen.

Sampo-Kwojin (Japan) *see* Susanowo.

Sampsa Bellervoinen (Finland)
God of the sowing season. He flees to the North each year and must be brought back.

Sams (Southern Semite)
She is a sun goddess who is equal to the Northern Semite sun god Samas. She is also comparable to Allat (q.v.).

Samsara-Guru (India) *see* Kama (A).

Samvarana (India) *see* Tapati.

San Ch'ing *Sang Ch'ing* (Taoism; China)
Also known as: *The Three Heavens.*
The residence of the three supreme gods. The first heaven, located in the Jade Mountain, is called Yu Ch'ing and is ruled by Yuan-shih T'ien-tsun, or Lo Ching Hsin or T'ien Pao depending on the source. Both gods are the source of all truth. The second heaven is called Shang Ch'ing and is ruled by Ling-pao T'ien-tsun or Tao Chun. He is in charge of the sacred books. The third heaven is called T'ai Ch'ing which is ruled by *Lao Tzu. He* is also called Shen Pao, T'ai-shang Lao-chun or Cheou-Lao, and is considered the teacher of emperors and kings and a god of longevity. Comparable to the Buddhist three heavens. *See also* Ling-Pao T'ien-Tsun; San Hsien Shan; San Kuan; San Yuan; T'ai Shang San Kuan.

San Hsien Shan (China)
Also known as: *San Kuan.*
Home of the gods. "The Three Isles of the Blest" (P'eng-lai, Fang-chang, and Ying-chou) are the most desirable residence for the Immortals. (*See* Chiu Kung.) This is the location of the Peach Tree of Immortality (P'an-T'ao or Shen-T'ao). A similar heaven is called San Ch'ing (Three Pure Ones) and San Kuan (Three Agents) (q.v.) Similar to the Taoist San Ch'ing.

San Kiai Kung (China) *see* San Kuan.

San-ku (China) *see* K'eng-san-ku.

San Kuan (Taoist; China)
Also known as: *San Kiai Kung* (Lords of the Three Worlds), *San Kuan Ta Ti* (Three Great Emperor Agents), *San Yuan* (Three Origins), *T'ai Shang San Kuan* (Three Supreme Agents).
Spirits. The San Kuan are the three agents who rule over heaven, earth and water. The Agent of Heaven is T'ien-kuan. He is a god of happiness. The Agent of Water, Shui-kuan, wards off misfortune. Ti-kuan is the Agent of Earth and grants remission of sins. They are usually shown sitting or standing together holding tablets in their hands. Sometimes only T'ien-kuan is shown. He is standing and holding an unfolded scroll in his hands. The Three Agents are similar to the Japanese Shichi Fukujin. *See also* San Ch'ing.

San Kuan Ta Ti (China) *see* San Kuan.

San Yuan (China) *see* San Kuan.

Sandacos (Greek, Persia)
Sandacos, said to be the father of Adonis, the Greek god of love, is a local god of the city of Celenderis. He could be the same as Sedeq (q.v.).

Sandakos (Phoenician) *see* Adonis.

Sandhya *Samdhya* (Hindu; India)
Sandhya, originally a nature goddess and later a goddess of twilight, is said to be the shy daughter of Brahma. Once when drunk and in the form of a stag, Brahma had incestuous desires and chased her through the sky. He was apprehended by Shiva, who cut his head off with a bow and arrow. From that time, it is said that Brahma paid homage to Shiva. Sandhya is also the period that precedes a Yuga, one of the four Hindu ages of the world. The four ages are Krita, Treta, Dvapara and Kali. Sandhyavandona was originally the Hindu morning and evening prayer (twilight worship). *See also* Brahma; Ratri; Shiva.

Sandili (India) Possibly the mother of Agni or Brahma.

Sang-gyeman-gyila-beduryr-o-chi-gyal-po (Tibet) *see* Bhaishajyaguru.

Sangarius (Greek)
He is one of the river god sons Oceanus and Tethys and the father of Nana. His grandson is Attis. He could be the father of Hecuba by Metope. *See also* Attis.

Sangay Chanma (Tibet) *see* Shakti.

Sangke (Slavic) *see* Ilmarinen.

Sango (Africa) *see* Shango.

Sangreal (Greek) *see* Holy Grail.

Sangso-Dungso (Dhammai People, India)
Sangso-Dungso, Kimbu-Sangtung and Lubukhanlung are the children of the first mortals, the brother and sister, Abugupham-Bumo and Anoi-Diggan-Juje. Their grandparents are the brother and sister frogs, Lujjuphu and Jassuju. *See also* Shuznaghu.

Sangye Khado *Buddha Dakini* (Tibet) *see* Khados.

Sanhara (India) "Destruction." *See also* Shiva.

Saning Sari (East Indies, Java, Sumatra) "Mother of Rice."

Sanja *Samgna, Samjna, Samjuna, Sanjna* (India)
In Puranic mythology, Sanja is the daughter of Visvakarma, the sister of the goddess Barhishmati, and the spouse of the sun, Surya. In some renditions, they became the parents of Manu and the twins, Yama and Yami. When she could no longer endure Surya's brilliance, she had her assistant, (some say her sister) Chhaya or "Shade" take her place and she transformed herself into a mare and galloped off into the forest. After a time, Surya discovered that his mate had disappeared. He became a stallion, and when he found her they came together sexually and became the parents of the Asvin twins and Revanta. After this reconciliation, they lived together for a time as horses but eventually returned to human form. In order to make her living conditions at home more tolerable, she had her father shave away an eighth of Surya's rays. In some renditions, Sanja is said to be the spouse of Soma (q.v.). The mythology of Sanja and Saranyu are similar and they are often considered to be the same deity. *See also* Asvins; Manu; Saranyu, Surya; Tapai; Visvakarma; Yama.

Sankara (India) Healer. *See also* Shiva.

Sankashana (India) *see* Bala-Rama.

Sankhasura (Hindu; India)
Sankhasura was a Yaksha (demon) in the employ of Kansa,

www.ebook3000.com

Krishna's archenemy. One night when Krishna and his half-brother Bala-Rama were frolicking with the cowgirls, Sankhasura mingled among them and attacked some of the women. When Krishna heard their screams, he pursued the demon and beheaded him. *See also* Bala-Rama; Krishna; Yaksha.

Santanu (India) *see* Bhishma.

Santaramet (Iranian, Persian)

Santaramet is a type of hell referred to in the Armenian Old Testament. The inhabitants are evil spirits called Santarametakans. Santaramet is also the name of an ancient Armenian goddess of the underworld, who was the Persian Spenta Armaiti (q.v.). *See also* Dzokh; Hades; Hell; Spantaramet.

Sanumati (India) *see* Apsarases.

Sanzu-no-kawa (Japan)

Also known as: *Chimata-no-kami* (singular), *Sai-no-kami, Yachimata-hiko* (singular).

Divine river. Deities of the roads and highways. "The River of Three Routes." The soul must go to one of three places, toward the hells, toward the beast life, or toward the realm of the "hungry ghosts." There are judges on all three roads where the soul is examined. Other names associated with the Sanzu-no-kawa: Chimata-no-kami, the god of the road; Yachimata-hiko, god of countless roads. The deities were created by Izanagi to protect travellers. Possibly the collective name of the judges is Sai-No-Kami. *See also* Chimata-no-kami.

Sapi (Egypt)

Also known as: *Saites* (Greek).

Afterworld deity. In the fifth nome in the Nome-Lists the name is associated with the goddess Nit or Neith.

Sapling (North America) *see* Yoskeha.

Sapta-Loka (India) *see* Loka.

Saptarshi (India) The seven Rishis. *See also* Rishi.

Saptungtongsum (Saora People, India)

The god of dancing. *See also* Adununkisum; Krishna.

Sar-Akha (Finnish) *see* Akha.

Sarah *Sarai* (Hebrew) *see* Abram.

Sarai (Hebrew) *see* Abram.

Sarama (India) Heavenly Hound. *See also* Yama.

Saramana (Assyro-Babylonia)

Also known as: *Salmon, Selamanes, Shulmanu, Sulman.*

He is a war god shown with a battle axe. Saramana is sometimes identified with Reshep.

Sarameya (India) Heavenly Hound. *See also* Yama.

Saranya (India) *see* Saranyu.

Saranyu *Saranya, Sharanyu* (Vedic, Hindu; India)

Saranyu, goddess of the clouds and morning light, is the daughter of the sun Tvashtri, possibly the twin sister of a brother Trisiras, the spouse of Vivasvat and perhaps the mother of the twins Yami and Yama, the Asvin twins and the artisan elves known as the Ribhus. She lived up to her name, which means the "fleet running one." Shortly after a magnificent wedding, attended by all the gods in the world, she disappeared. Her husband's brilliance had become unbearable. She was gracious enough to create a look-alike, Sarvana, to stay behind in her place. In time, when Vivasvat realized what had happened, he went to find her. What he found was his spouse disguised as a mare. They agreed to a reconciliation under the conditions that he would have some of his brightness shaved away so that she could have a little shade in her life. Her father performed the operation and she helped him reshape the shavings from his rays into weapons for the gods. Compare Saranyu to Sanja. Saranyu corresponds with dawn goddesses Aurora (Roman); Ausera (Lithuanian); Aya (Chaldean); Eos (Greek); Ushas; Zorya Utrennyaya (Slavic). *See also* Asvins; Ribhus; Trisiras; Tvashtri; Visvakarma; Vivasvat; Yama; Yami.

Sarapis (Egypt, Greek) *see* Serapis.

Sarasvati *Saraswati* (Buddhist; Chinese)

Also known as: *Arya Sarasvati* (Tibet), *Benten* (Japan), *Brahmani, Brahmi, Dakini Ye-she-tsho-gyal* (Victorious One of the Ocean of Wisdom), *Gayatri* (Singer), *Khandro, Logos* (The Word), *Prajnaparamita, Satarupa* (She of a Thousand Shapes), *Savitri, Shata-et, Shata-Rupa, Vac, Vach, Vach-Sarasvati, Vajravina, Viraj, Yang-Chen.*

Originally, Sarasvati was the Vedic goddess of the Sarasvati river and was associated with fertility and prosperity. Her holy waters flowed west from the Himalayas into the sea. The sage Utathya cursed the waters when Varuna stole his spouse and now the river water ends in the desert. Later, Sarasvati became the goddess of speech, learning, the cultural arts and science. She is credited with bringing the Sanskrit language to the people. In some traditions, it is believed that she discovered soma, the elixir of the gods. Sarasvati was born of Brahma's self, and it was for her love that he created the world. She was his daughter and became his spouse. Sarasvati, Lakshmi and Ganga were also mates of Vishnu. The strife in their relationship caused him to suggest that she marry Brahma. One day when she was to play a role in a sacrificial function Brahma sent word for her. She replied that she was involved with her grooming and that he could wait. Angry, he decided not to wait. He married a second wife, the goddess Gayatri. Incensed with his actions, she cursed him and declared that he should only be worshiped once a year. Sarasvati is known as the "White Goddess" when she is one of a trimurti with the goddesses Lakshmi and Devi. She is one of the goddesses of the Jaina pantheon along with Lakshmi and the Apsarases. As Satarupa, she is the mother of Manu Svayam-bhuva, the first Manu. She is considered the female aspect of Viraj created from the substance of Purusha or Prajapati. The three Vedic muses are the goddesses Bharati, Ila and Sarasvati. In the Buddhist pantheon, Sarasvati is the goddess of poetry and music and the spouse of Manjusri Jampal, the god of learning. Sarasvati is shown as beautiful and graceful young woman often smiling, white in color, wearing a crescent moon on her brow. She has two or four arms and is usually shown holding a book, a lyre or a drum, a rosary, and a lotus. Sometimes she holds a container of Soma and the Vidya, emblem of knowledge. Her mount is the peacock, which is shown with its tail spread. She is also depicted seated on a swan and sometimes on a lotus petal. Sarasvati is also shown as an attendant or consort of the fire god, Agni. As Vajravina, she holds a stringed instrument known as the vina, in her right hand. As Arya Sarasvati, she is bright red in color and has three faces, six arms and an aggressive attitude. Sarasvati merged with the goddess of highest wisdom, Prajnaparamita (Prajna), and is shown with three eyes, the moon in her crown, holding a book and a lotus. Sarasvati's festival, Dawat Puja, or "worship of the inkstand," is held in the month of Magh (January-February). On her day, the only writing instrument that may be used is a pencil. Following the festival, new pens and ink must be used. In Bengal, followers worship pens, ink and account books in her honor. Twigs and blossoms of the mango tree are among offerings given to this goddess. Offerings to Sarasvati cleanse the liar immediately. Sarasvati is intellectually compatible with Vach, the goddess of sound and almost identical to the goddess Benten of Japan. *See also* Agni; Andhaka; Apsarases; Brahma; Dakini Yeshe-tsho-gyal; Devi; Ganga; Lakshmi; Logos; Manu; Parvati; Prajnaparamita; Savitri; Shakti; Soma; Sri; Varuna; Vishnu; Yami.

Saraswati (India) *see* Sarasvati.

Sarbanda (Babylon, Syria) A goddess of war or the bow.

Sarika (India) *see* Durga.

Sarna Burhi (India) Bengali tree goddess.

Sarnga (India)
Sarnga is Vishnu's divine bow. *See also* Vishnu.

Sarpanit (Assyro-Babylonian) *see* Zerpanitum.

Sarpas and Sarpis (India)
They are semi-divine serpents who dwell in heaven, in the air, on earth, and in the lower regions. Unlike the Nagas and Nagis, they do not walk or run.

Sarpedon (A) (Greek)
King of Lycia. Sarpedon is the son of Zeus and Europa. His siblings are Minos and Rhadamanthus. He was raised by Asterius, the king of Crete who had married Europa. Later he married Laodamia and was the father of Evander. As a youth he was exiled from Crete with Rhadamanthus by his brother Minos when Minos found out that a beautiful young man, either Miletus or Atymnius was in love with Sarpedon. His son Evander married Deidamia, the daughter of Bellerophon, and inherited his father's kingdom. In some legends they became the parents of Sarpedon named after Evander's father. In other legends, both Sarpedon (A) and Sarpedon (B) are thought to be the same man. Sarpedon's brothers Minos and Rhadamanthus became judges in the underworld after death. *See also* Asterius; Europa; Evander; Minos; Rhadamanthus; Sarpedon (B); Zeus.

Sarpedon (B) (Greek)
Warrior. Sarpedon was the son of Zeus and Laodamia, daughter of Bellerophon, or of Evander and Deidamia. As the son of Evander and Deidamia his siblings were Pallas who was later killed by Turnus, Roma (the eponym of Rome) and Pallantia (the eponym of the Palatine Hill, the highest of the seven hills of Rome). As the son of Zeus and Laodamia he was a brave warrior who commanded the Lycian troops and was slain by Patroclus. His dear friend Glaucus could not bear to see the Achaeans desecrate his body, nor could the dead man's father, Zeus. He sent Apollo to purify the corpse and had Hypnos (Sleep) and Thanatos (Death) transport it to Lycia for burial. Sarpedon is thought to represent the creeping light of heaven. In later traditions, Sarpedon is named as one of the sons of Zeus and Europa. There was another Sarpedon who was thought to be the son of Poseidon who was killed by Heracles for torturing visitors to his home. *See also* Evander (B); Glaucus; Sarpedon (A).

Sarume, The (Japan) *see* Ama-no-Uzume.

Saruta-Biko-No-Kami (Japan) *see* Ama-no-Uzume.

Saruto-Biko (Japan) *see* Ama-no-Uzume.

Sarva (India) The Destroyer. *See also* Agni; Shiva.

Sarvaga (India) *see* Bhima (A).

Sarvamangala (India)
"Universally Auspicious." *See also* Devi.

Sarvana (India) *see* Saranyu.

Sarvani (India) *see* Devi; Tapati.

Sarvanivaranaveskambhin (India) *see* Amoghasiddhi; Dhyanibodhisattvas; Samantabhadra.

Sarvanivaranviskambin (India) *see* Amoghasiddhi.

Sarvari (India) Water goddess.

Sarvavasini (India) *see* Devi.

Sary-Khan (Altaic, Tartars)
A god of happiness. *See also* Bai Ulgan.

Saryata (India) *see* Mada; Sukanya.

Sasabonsam (Africa)
An evil spirit. He lurks in the branches of the trees and jerks up unwary travelers by hooking his toes under their armpits. His legs are long and can be uncurled to go longer; his feet point backward. He has a pointed beard and horns and has thin lips. His arms are outstretched, and skinny wings, like those of a flying fox, join his arms to his legs.

Sashikuni-waka-hime (Japan) *see* Kushi-nada-hime.

Sasi-kuni-opo-no-kami (Japan) *see* Kushi-nada-hime.

Sasilekha (India) *see* Apsarases.

Sata-rupa (India) *see* Vach.

Satakratu (India) *see* Indra.

Satan *Sathanas, Sathan* (Akkadia, Babylon, Sumer, Persia)
Also known as: *Arya Sarasvati, Belial, Charun, Devil, Eblis, Iblis; Irra* (possibly, Babylon), *Nergal.*

Underworld deity of evil. Satan is possibly Irra of the Babylonia pantheon. He is one of the demons recognized by Jesus. In one version of his mythology, he is the twin brother of the archangel Michael and ruler of the evil deities, Azazel, Beelzebub, Belial, Chemos, Dagon, Moloch, Rimmon and Thammuz. In one description he is depicted (as Charun), with horse-ears and a hooked nose, his flesh is blue as if decaying, and he carries

www.ebook3000.com

a mallet to strike down his victims. Charun is believed to have influenced the medieval concept of Satan. Satan is similar in nature to Lilith. *See also* Azazel; Charon; Devil; Nergal.

Satarupa (India) *see* Sarasvati; Shiva; Manu.

Satavaesa (Zoroastrian; Persia)
An unidentified star or constellation and one of the Yazatas (q.v.).

Satet (Egypt) *see* Khnum; Satis.

Sathan (Babylon) *see* Satan.

Sathanas (Babylon) *see* Satan.

Sati (A) *Ambika, Amvika, Devi, Parvati, Suttee, Uma* (Brahmanic, Hindu; India)
Sati, one of the numerous daughters of Daksha, is an early aspect of the great mother goddess Devi. As Sati, the "good wife," she committed suicide by burning herself to death when her mate Shiva in his aspect as Rudra the storm god was killed. Sati is depicted with a calm face and dressed in a girdle and necklace. She is also shown with a child on her knee. The practice of burning a wife on her husband's funeral pyre is known as sati or suttee. *See also* Ardhanariswara; Daksha; Devi; Durga; Kali; Parvati; Rudra; Satis (Egypt); Shiva; Uma.

Sati (B) (Egypt) *see* Satis.

Sati, Queen (C) (India)
Queen Sati is the mate of the Brahmin and Maharishi King Visvamitra.

Satis (Egypt)
Also known as: *Isis, Isis-Satis, Isis-Sothis, Satet, Sati, Satis.*
River deity. Satis was the first wife of the creator god, Khnum. An archer-goddess, she assisted her spouse in protecting the upper Nile and the Cataracts. Arrows were the symbols of the swiftness of the Nile's course. Satis presented water to the deceased for purification. When Khnum identified with the sun god Ra, Satis became the "eye of Ra." She is sometimes confused with Satet. She is depicted in human form wearing on her head the white crown of the South with two horns and holding a bow and arrow. There is a similarity between Satis and the Hindu goddess Sati. She is sometimes identified with the goddess Ament. There is a possibility that as Sati she is a form of Isis (q.v.). *See also* Anukis; Khnum; Sati (A).

Satrajit (India)
A Yadava. *See also* Satrajit; Satyabhama; Yadava.

Satrughna (India) *see* Rama.

Sattung *Suttung* (Norse; Teutonic)
Also known as: *Fjalar, Loki, Utgard-Loke.*
Sattung is the giant son of Gilling or Surtr. He is the brother of Baugi and the father of Gunlodd. Sattung captured the Mead of Poetry from the two dwarfs, Galar and Fjalar, but lost it to Odin in his guise of Bolverk. *See also* Fjalar; Kvasir.

Saturn *Saturnus* (Roman)
Also known as: *Cronus* (Greek), *Heru-ka-pet, Heru-p-ka* (Egypt).
God of agriculture. God of workers and the vine. Responsible for prosperity and abundance. His spouse is Ops and they are the parents of Jupiter. Saturn is also the father of Juno and Picus by the nymph Venilia and possibly Sterculus, the king of Latium. Once the ruler of the world, he was removed from his position by his son Jupiter. *See also* Cronus; Jupiter; Ops; Steruclus.

Saturn the Planet (Greek) *see* Eurynome (A).

Saturnus (Roman) *see* Saturn.

Satya-Loka (India) *see* Loka.

Satya-Narayana (India) *see* Narayana (A).

Satyabhama (Hindu; India)
Satyabhama, the daughter of Satrajit, is generally thought to be Krishna's third wife. She claimed that a jewel that once belonged to her father was rightfully hers. When Satyabhama heard that Krishna had given his other wife, the beautiful goddess Rukmini, a flower from the magic Parijata Tree, she became indignant and demanded that he bring her the whole tree. Krishna went to Svarga, Indra's celestial dwelling place, with Aditi's earrings (Indra's mother) and Indra's canopy and requested the tree. When Indra refused to oblige him, Krishna uprooted the tree and left, pursued by Indra and his forces. Krishna kept the tree for a year and then willingly returned it to Indra. Krishna was involved with Jambavan, the King of the Bears who had a precious jewel that belonged to Krishna. *See also* Indrani; Jambavan; Krishna; Parijata Tree; Syamantaka.

Satyapir (India) *see* Narayana.

Satyavan (India) "Possessing Truth." *See also* Savitri (B).

Satyavati (Brahmanic, Hindu; India)
Satyavati, meaning "the Truthful One," is the daughter of the Asparasa Adrika who lived in the shape of a fish and the king of Chedi, the mate of the rishi Parasara, and the mother of a son Vyasa. At a later time, she became the mate of king Shantanu of Hastinapura, the mother of two more sons, Chitrangada and Vichitravirya, and the grandmother of the Pandavas. *See also* Asparases; Bhishma; Pandavas; Parashara; Vyasa.

Satyrs (Greek)
Also known as: *Fauns.*
Deities of the woodland. The Satyrs, woodland deities, are descendants of Hecaterus and Apis, Niobe or Car. They were addicted to sensual pleasure and associated with the worship of Dionysus and Bacchus. They loved and overindulged in the "nectar of the gods," music, dancing and frolicking with women. When the Satyrs age, they are known as the Sileni. The Satyrs are ruled by Silenus, the king of Nysa, an expert musician, who resembled the Satyrs in appearance. The Satyrs are depicted as ugly, with a pug-nose, goat ears, budding horns and a short tail. *See also* Bacchus; Bhut (India); Corybantes; Dionysus; Hephaistos; Incubus (Medieval Europe); Jinn; Silenus.

Saubhadra (India) *see* Abhimanyu.

Saudamani (India) *see* Apsarases; Kasyapa; Yakshini; Yaska.

Saumanasa (India) *see* Lokapalas.

Saunanda (India) The sacred club of Bala-Rama (q.v.).

Saurasa (Hindu, India)
A giant female Rakshasa, Saurasa opened her mouth to swallow the monkey general Hanuman as he flew through the air. He had enlarged himself to the size of a mountain but when she caught him, he reduced himself to the size of a thumb. Once he was inside of her, he enlarged himself again, she burst open and he escaped. *See also* Hanuman; Rakshasa.

Sauromatai (Scythian) *see* Amazons.

Sauru (Zoroastrianism; Persia)
Sauru is the arch-demon who personifies the mismanagement of government and inebriation. He opposes Khshasthra Vairya (q.v.). *See also* Daevas; Darvands.

Savabhauma (India) *see* Lokapalas.

Savaki (Siberia) *see* Khovaki.

Savala (India) *see* Kamadhenu.

Savarbhanu (Hindu; India)
He began life as a Daitya with four arms and a tail. When soma, the elixir of the gods was being passed around, at the churning of the sea of milk, he slipped between Surya and Chandra and managed to gulp a portion. He was apprehended by Vishnu who sliced him in two with his discus, Sudarshana. The powerful effects of the soma gave each part immortality and Savarbhanu became Ketu and Rahu and was placed in the stellar sphere. Ketu appears as a dragon's tail carried through the sky in a chariot drawn by eight swift red horses. The dragon-headed Rahu rides in a chariot drawn by eight black horses. He despises the sun and the moon and is constantly pursuing them. Occasionally, he catches the planets and an eclipse occurs. *See also* Chandra; Daitya; Kurma (regarding the Churning of the Sea of Milk); Rahu (for a variation of this myth); Soma; Sudarshana; Surya.

Savita (India) *see* Martanda; Sita; Vivasvat.

Savitar (India) *see* Savitri (A).

Savitr (India) *see* Savitri (A).

Savitri (A) *Savitar, Savitr* (Heaven), *Surya, Vach, Vach-Sarasvati* (Vedic, Hindu; India)
Originally, Savitri and Vivasvat were attributes or names of the sun. Later, they became deities. Savitri is the son of Aditi and one of the Adityas. He became the king of heaven, the giver of life, the father of the sun goddess Surya and possibly the Asvins. He is represented by universal movement, seen in the course of the sun and the motion of the winds and seas. Known as the "Generator," "The Stimulator," "The Inspirer" and "The Life-giver," it is Savitri who calls for the night to approach. Savitri dispels disease and give mortals longevity and gods immortality, for he puts all to rest. He is invoked for the remission of sins. Savitri has golden eyes, hands and tongue. As the personification of the rising and setting sun, he rides through the heavens in a chariot drawn by glittering horses with white hoofs. In sacrifices, he cut off his hand but the attendant priests restored it. His hand represents the sun's rays and the new hand is the lights of dawn. In the Hindu tradition, if the mantra of the *Gayatri* (a sacred text of the Vedas) is chanted upon rising, the magical powers of the text are exercised on behalf of the reciter. The mantra "Om" is the basis of the *Gayatri.* Savitri is an aspect Surya, the sun god, and was later identified with Vishnu, whom he most resembles. In the *Upanishads,* Savitri appears as Purusha, "The Golden Person." Compare him to the Norse god Odin's lost eye and the Celtic deity Nuada's silver hand. *See also* Aditi; Adityas; Asvins; Daksha; Mitra; Pushan; Sarasvati; Savitri (B); Surya (A); Surya (B); Vach; Varuna; Vishnu; Vivasvat.

Savitri (B) *Deva-Kanya* (Hindu; India)
Savitri, the daughter of Asvapati, choose the exiled prince Satyavan to be her husband. She was not thwarted by the warnings of the court sages that her loved one only had one year to live. The year passed and the god of death, Yama appeared to escort Satyavan to the land of the dead. Savitri followed them until her feet bled. She pleaded with Yama to release her spouse. Impressed by her willingness to follow her mate to death's doorstep, the god agreed to allow Satyavan to return to her so that they could have many children together. Savitri is a name applied to many goddesses and is a common female name. A celebration is observed yearly by women in honor of Savitri, who did not allow death to conquer love. Savitri as a sun goddess could represent the sun and her husband the setting or dying sun. Another Savitri was the daughter of the sun and the wife of Brahma. Compare Savitri to the Greek goddess Alcestis. *See also* Sarasvati; Savitri (A); Yama.

Say-nying-po (Tibet) *see* Mamaki.

Sayori-bime-no-mikoto (Japan) *see* Three Goddesses of Munakata.

Scamander (Greek)
Also known as: *Xanthus.*
River god. His parents are Oceanus and Tethys. During the Trojan War, he assisted the Trojans, who were fighting with the Greeks, by flooding his river. He is the maternal grandfather of Cilla (q.v.). *See also:* Callirrhoe; Hesione; Rivers.

Scamandrus (Greek) *see* Rivers.

Scanda (India) *see* Skanda.

Scarab (Egypt)
Deified insect. A representation of a beetle, the sacred symbol of everlasting, eternal transformation and of immortality. The scarab is associated with the god Khepri and was often used as a seal, or an amulet worn for protection against evil. *See also* Amulet.

Scarphe (Greek) *see* Jason.

Scathach (Celtic)
Goddess of the sky. Sorceress. *See also* Aoife.

Sceiron (A) (Greek)
He is the son of Pelops or Poseidon who was killed by Theseus. *See also* Pelops.

Sceiron (B)
Sceiron is the northwest wind. His parents are the Titan, Astraeus and Eos, the goddess of dawn.

www.ebook3000.com

Schoeneus (Greek)
He is the king of a section of Boeotia. His parents are Athamas and Themisto. *See also* Atalanta; Athamas.

Scrat (Teutonic) Wood demon. *See also* Dus (Celtic).

Scylla *Skylla* (Greek)
Sea-monster. Although her lineage is murky, the legends of Scylla are clear. She was either the daughter of Phorcys and Hecate or Phorcys and Crataeis, or Typhon and Echidna, or Poseidon. In other legends, she is the daughter of the queen of Libya, Lamia, whom Zeus adored. When the jealous Amphitrite found out about Scylla's affair with Poseidon she had the enchantress Circe turn the beautiful nymph into a sea-monster. In another version, Circe, angry that Scylla would not respond to the romantic overtures of Glaucus, poured poison into her bathing pond. Scylla stepped in to cleanse herself and turned into a monster. The jealousy of another woman also created havoc in Lamia's life. Scylla and Charybdis harassed sailors in the Straits of Messina; it was impossible to avoid the danger of one without encountering the other. When Heracles was navigating his oxen through the straits of Sicily, Scylla reached out, grabbed one of the animals and gorged herself. Incensed, he killed her. Phorcys, her father, was able to revive her. Little is known about Charybdis except through the writing of Homer. He tells us that she lived in the sea under a rock on which a fig tree grew. She swallowed the angry waves of the sea three times a day and then regurgitated them. He called her the daughter of Poseidon and the Earth (Gaea). He wrote that the angry Heracles hurled a thunderbolt at her when she stole his oxen and thus changed her into a sea monster. Scylla barked like a dog and had twelve feet, six necks and six heads, each with three rows of teeth. *See also* Calypso; Ceto; Circe; Giants; Gorgons; Hylas; Lamia; Medusa; Nereids; Poseidon; Sirens.

Se-oritsu-hime (Japan)
Lady-Who-Descends-the-Rapids. *See also* Haya-akitsu-hime-no-kami.

Seb (Egypt) *see* Aai; Geb; Nut.

Sebak (Egypt) *see* Sebek.

Sebek *Sebak, Sebeq, Sebku Sobek* (Egypt, Greek)
Also known as: *Helios* (Greek), *Petesuchos, Sebek-Hetep, Sobk, Sobk-Re, Suchos, Sukhos* (Greek).
Sebek was a local god at the city of Arsinoe (called Crocodilopolis by the Greeks), in Faiyum. He was an early fertility god and later a god of death. A crocodile, believed to be the incarnation of a god, he is a protector of reptiles. Sebek prevents decay of the body in the tomb and provides speech and sight to the dead. He is associated with the pharaohs of the Thirteenth Dynasty. He is depicted as a crocodile or a crocodile-headed man. As Helios (Greek) he is depicted with a halo of rays and the attribute of a crocodile in his hand. There are depictions of crocodiles which carry a falcon's head adorned with the double crown indicating the relationship between Suchos and Horus. In the *Book of the Dead*, Sebek assists in the birth of Horus. *See also* Horus; Sukhos (Greek).

Sebek-Hetep (Egypt) *see* Sebek.

Sebeq (Egypt) *see* Sebek.

Sebi (Egypt)
Sebi is a monster serpent who guards the entrance to the twelfth sector of Tuat.

Sebuit-nebt-uaa-khesfet-sebau-em-pert-f (Egypt)
Afterworld name. The name of the Eleventh Hour of Tuat. The city of Re-qerert-apt-khat which Osiris passes through has the pylon Sekhen-tuatiu. The deities who accompany the god or soul on the journey are Fa, Ermenu, Athpi, Netru, Shepu, Reta, Amu, Ama, Shetu, Sekhenu, Semsem, Mehni, Sem-shet, Sem-Nebt-het, four forms of Neith, Aper-hra-neb-tchetta, Tepui, Shetu, Tchet-s, Petra, Temu, Shetu, Nebt-ankhiu, Nebt-khu, Nert, and Hent-neteru. There are pits in this place. They are Hatet, guarded by Hert-ketit-s; another unnamed pit guarded by Hert-Hantua; another guarded by Nekenit; and two others guarded by Hert-Nemmat-Set and Hert-sefu-s. Three other goddesses are included in this journey: Pesi, Rekhit, Her-sha-s, and Sait and another god, Her-ut-f. *See also* Tuat.

Sechmet (Egypt) *see* Sekhmet.

Sedeq (Ancient Hebrew; Canaan; Persian; Syrian.)
Also known as: *Melchi-sedeq, Sydyk.*
Sun deity. Sedeq, a chief deity of the Palestinians, is the father of the seven Kabirs (great gods). He is usually associated with the god Misharu and called Melchi-sedeq. Under the names of Sydyk and Misor, they are the sons of Shamash and as culture heros, are the discoverers of salt. *See also* Misor; Zatik.

Sedit (Wintun People) *see* Coyote.

Sedna (Eskimo People)
Also known as: *Ai-willi-ay-o, Arnaknagsak, Arnarquagssaq, Avilayoq, Nerivik, Nerrivik.*
Sea goddess. Mother of all sea creatures. Sedna is the daughter of Anguta or Angusta. In one myth, Sedna fell in and out of love with a bird spirit. During her father's attempt at rescuing her from the spirit he became frightened and threw her from the boat. She tried to climb back in and he cut off parts of her hand which became seals and other sea creatures. There are many variations on this theme. Another myth tells us that her nameless parents were giants. She had a voracious appetite and one night began nibbling on her mother and father. Horrified, they managed to throw her into the sea. She clung to the side of the boat and they chopped off her fingers which turned into sea creatures. She sank to the bottom, set up housekeeping, and became the ruler of all sea creatures and the dictator of storms. The Angakok (shaman) would visit her in a trance. He was received by the ruler in a luxurious tent in Adlivun under the sea furnished with the skins of various sea animals. The great lady would watch him dance and amuse her and then would give him a message for the people, generally regarding the food supply; if it was to be abundant they should stay, if sparse, they should move on. The toxic matter thrown into the sea (representing sins) tangles her hair. Her hair also tangles when land and sea meat are cooked together. Hunters who do not hunt with respect for the hunted caused her terrible pain. When Sedna is treated with honor, gentleness and honesty she provides food for humans, hence is called the "Food Dish." She is also called the "Great Sea Mother." It is Sedna who initiated taboos. She particularly dislikes dirty women. When a taboo is broken, she

takes the women's sewing articles and covers over the seals, so that they cannot be hunted. The shaman is called to bring her to him with his magic songs. When she possesses him, other men hold him tightly. During this period, the men are able to confess all breaches of taboos. Her hair becomes smooth again and she returns to her home in the sea. Her lights are turned up, the storms subside, and the animals are once again free to be hunted. However, the hunters must wait for four days before proceeding with the hunt. During this period, women do not sew. In some descriptions, Sedna is fat, hideous, and ill-tempered. She is also depicted as a giant with one eye. In another description, her hands are like seal's flippers. She is the counterpart of the Pacific Eskimo goddess Nunam-shua (q.v.), and comparable to Nerivik. Compare Sedna to the Greek sea god, Poseidon. *See also* Adlivun; Anguta; Aningan; Nerivik; Tornaq.

Sedrat (Arabic)
Deified tree. Sedrat is the lotus tree that stands on the right-hand side of the throne of Ali. Countless angels rest in the shade of this tree and two rivers run from its roots.

Sedu *Shedu* (Babylon, Semitic, Hebrew)
Also known as: *Alad.*
Benevolent, obtuse demons. Door or gateway guardians (possibly). They are shown as winged animals, probably cows or bulls. Associated with the Lamassu. *See also* Lamassu.

Seeta (India) *see* Sita.

Sefer (Egypt)
Deified animal. A animal with the winged body of a lion and the head of an eagle.

Sefkhet-Aabut (Egypt) *see* Seshat.

Seger (Egypt) *see* Seker.

Segesta (Greek)
Segesta is a nymph and the possible mother by the river god, Crimisus, of the Trojan War hero, Acestes. *See also* Acestes.

Segetia (Roman)
Also known as: *Tutilina.*
Agricultural deity. Corn deity. Segetia protects the fruits and vegetables of the harvest. In some locales, she specifically protected the grown corn. Segetia may be an aspect of Ops and is comparable to the Greek goddess of corn, Seia. The difference is that Seia protects the corn before it sprouts.

Segomo (Celtic)
Another name for the god of war, Cocidius (q.v.).

Sehetch-khatu (Egypt) *see* Aai.

Seia (Greek)
Corn deity. Goddess of corn before it sprouts. *See also* Ops; Segetia.

Seilenos (Greek) *see* Silenus.

Seiren (Greek) *see* Sirens.

Se'irim (Middle Eastern) *see* Jin.

Seitaka Doji *Seit Ka-doji* (Japan)
He is the servant and messenger of Fudo-myoo. In one hand, he holds a stick. *See also* Fudo-myoo.

Sekem Taui (Egypt) *see* Ap-uat.

Seker (Egypt)
Also known as: *Sacharis, Seger, Socharis, Sokar, Sokare, Sokaris.*
Early god of vegetation. Deity of the necropolis of Memphis. He is closely affiliated with Osiris. Seker is shown as a seated hawk-headed man holding sovereignty emblems in his outstretched hand. He is sometimes shown with the head of man holding a knife in each hand. *See also* Amentet; Osiris; Ptah.

Sekhait (Egypt) *see* Sekhmet.

Sekhauit (Egypt) *see* Sekhmet.

Sekhautet (Egypt) *see* Sekhmet.

Sekhem (Egypt) The soul or vital power. *See also* Sekhmet.

Sekhem Em Pet (Egypt)
Also known as: *Anubis.*
Sekhem Em Pet is the name for the god Anubis as a son of Osiris. *See also* Sekhem Taui.

Sekhem-hra (Egypt) *see* Aai.

Sekhem Taui (Egypt)
Also known as: *Anubis.*
Sekhem Taui is another name for the god Anubis as a form of his father, Osiris.

Sekhemus (Egypt)
Afterworld deity. The name of the Fourth Hour of Tuat. The boat of Ra arrives at the Circle called Ankhet-kheperu (*see* Aat) which has a pylon called Ament-sthau. Ra is guided along the hidden path called Re-stau and the winding road of the Ammehet to the land of Seker, which is filled with fearsome snakes. Along the way Osiris is merged with Seker and becomes Osiris Seker. Re-stau has three doors called Mates-sma-ta, Metesneheh, and Metes-mau-at. Osiris Seker passes through the door guarded by the goddess Am-mut who consumes souls with fire from her mouth. Thoth and Horus go in front of Osiris and they pass through the serpents, Hetch-nau, Seker, Amen, Hekent, Menmenu, Neheb-kau and the scorpion Ankhet. *See also* Taut.

Sekhen-ba (Egypt) *see* Aai.

Sekheper-khati (Egypt) *see* Aai.

Sekher-remu (Egypt) *see* Aaru.

Sekhet (Egypt) *see* Bast; Hathor; Ra; Sekhmet.

Sekhet-aaru (Egypt) *see* Aaru.

Sekhet-hetep (Egypt) *see* Aaru.

Sekhmet (Egypt) *Sakhmet, Sechmet, Sekhem*
Also known as: *Bast, Mut, Sekhait, Sekhauit, Sekhautet, Sekhem-bast-ra, Sekhet.*
Warrior goddess. Goddess of childbirth, fire, heat. Punisher of mortals for sins. Protector of the righteous (in later times). Sekmet was created by Ra from the fire in his eyes to punish mortals for their sins. Sekhmet became the wife of Ptah, though often described as his mother, and mother of Nefertem. Together they made up the Memphite Triad. Her name means

www.ebook3000.com

the "Mighty One" and she is known to spread terror. She is a fearless warrior who uses arrows. The hot desert winds are her breath and a fiery glow emanates from her body. Sekhmet, the negative aspect of Bast, is well known for her knowledge of magic and sorcery. The local goddess Mut merged with Sekhmet when Thebes became the royal residence. She is depicted with the head of a lioness or as a lioness. She is also shown with a solar disk, crowned with the poisonous uraeus-serpent. As Sekhem-bast-ra she is worshiped with Bast and Ra as a compound deity. In this form, she is the consort of Ptah-seker-ausar. Sekhmet is identified with Hathor who took the shape of a lioness and did battle for Ra against those mortals who were rebellious against him. She is also identified with Mut and Pakhet. The Greeks called her Sakhmis, Latona, and Artemis. *See also* Bast; Mut; Sakhmet; Ra.

Sekhmet-Bast-Ra (Egypt)
Strange deity portrayed as a male head on the body of a woman with a phallus.

Selamanes (Babylon) *see* Saramana.

Selene *Selena, Selina* (Greek)
Also known as: *Artemis, Diana, Mene, Luna* (Roman), *Phoebe.*

Goddess of the moon. Selene is the daughter of Hyperion or Pallas and Euryphaessa or Theia. Her siblings are the sun god Helius and the goddess of dawn, Eos. Selene had a long term affair with a beautiful, younger man, Endymion. She kept him in a somnolent state and every night paid him a visit. Over time, she had fifty daughters by Endymion. With Zeus she had three children, Pandia, Ersa and Nemea. The shepherd god Pan turned himself into a white ram and had sex with her. A very beautiful goddess, sometimes shown with wings, she rides across the skies in a chariot pulled by two white steeds. *See also* Artemis; Diana; Eos; Helius; Isis.

Selk (Egypt) *see* Selket.

Selket (Egypt) see Serqet.

Selkis (Greek) *see* Selket.

Selkit (Egypt) *see* Selket.

Selqet (Egypt) *see* Selket.

Selquet (Egypt) *see* Selket.

Selsabil (Islamic)
Water the flavor of ginger flows from this fountain in Paradise.

Semaahut (Egypt) *see* Aai.

Semele (Greek)
Also known as: *Thyone.*

Semele is the daughter of the king of Thebes, Cadmus, and Harmonia. Her siblings are Agave, who later murdered her husband and went insane and then murdered her son; Autonoe, who was driven insane for her treatment of Semele; Ino, who raised Dionysus and later went insane; and two brothers, Illyrius and Polydorus. Semele was loved by Zeus and became the mother of Dionysus. The jealous Hera appeared to Semele in the form of Beroe, her nurse, and persuaded her rival to ask Zeus to appear to her in all the splendor of his divinity. Semele, unable to endure the brilliance of Zeus in his divine form, was burnt to ashes, but Hermes rescued her unborn child Dionysus, and sewed him into the thigh of Zeus from which he was later born. Her jealous sisters, Autonoe, Ino and Agave, spread vicious rumors about Semele and were punished throughout their lives by Zeus or Dionysus. In another version of this legend, Persephone was the mother of Dionysus and he was snatched away and eaten by the Titans. Zeus saved the child's heart and served it to Semele in a drink from which she became pregnant. In later years, Dionysus went to the underworld, Hades, and took Semele to Mount Olympus where she became immortal under the name of Thyone. Some think Semele (or Persian Zamin) was Zemelo, an ancient earth goddess of the Phrygians. The Greeks identified her with the mother of the Egyptian Osiris. *See also* Actaeon; Bagos Papaios; Cadmus; Dionysus; Hera; Ino; Juno.

Semi (Egypt)
Deified object. Semi is a large winged uraeus standing on its tail. It is found in the tenth sector of Tuat.

Semiramis (Assyria)
Also known as: *Sammuramat.*

A goddess of love and war, she is the daughter of Ataryatis Derketo of Ascalon, the Syrian fish goddess (also known as Atargatis), and Oannes the god of wisdom. Ishtar's dove fed her as a newborn until she was found by the shepherd Simmos, who raised her. She wed Menon, who was a general of King Ninus of Assyria. After his death, she married Ninus and became the Queen of Babylon. After his death, she became the ruler of Assyria. She led mighty war campaigns against Persia, Egypt, Libya and Ethiopia, and conquered the eastern world. She was also noted for building Babylon and its famed hanging gardens. *See also* Atargatis; Oannes.

Semit-her-abt-uaa-s (Egypt)
The name of the Fifth hour of Tuat. Osiris must pass through Semit-her-abt-uaa-s, the capitol city of Seker. The pylon and circle of the city are called Aha-neteru and Ament, respectively. Within the city are the souls called Baiu amu Tuat who are hidden beings. The boat of Osiris is towed by seven gods and seven goddesses, and he is accompanied by the gods Her-khu, Anhetep, Her-hequi, and Hetch-met. *See also* Tuat.

Sena (India) *see* Karttikeya.

Sena-pati (India) *see* Karttikeya.

Senenahemthet (Egypt)
Serpent demon. It is mentioned in a magical formula of *Unas*, a king of the Fifth Dynasty. *See also* Akeneh.

Sengen (Japan)
Also known as: *Asama, Kono-hana-sakuya-hime* (The Princess Who Makes the Blossoms of the Trees to Flower), *Sengen-Sama.*

The goddess of Mount Fujiyama. Although many shrines have been dedicated to Sengen, an important one has been established on the summit of the sacred Mount Fuji. Pilgrimages are made to her sanctuary during the summer months and worshipers honor the rising sun. Based on this practice, there could be a connection between Sengen and the sun goddess Amaterasu. In her role the similarity between the short lives of mortals and the short lives of blossoms is illustrated. (*See* Sakuya-hime.) Many shrines are erected on mountains, as they are considered sacred. Additional mountain deities are O-Yama-Tsu-Mi, chief god and lord of the mountains. This deity was appealed to before trees were cut down, particularly trees used to construct temples. He was born from the blood of his brother, the fire god Kagu-tsuchi. O-Yama-Tsu-Mi married Kaya-no-Hime-no-Kami (Ruler of the Grassy Plains). One of their daughters, Kono-Hana-Sakuya-Hime (Blossoms-of-the-Trees-Blooming-Princess), married Ninigi and became the mother of Hoderi, Hosuser and Hikohohodemi. Other mountain deities are Naka-Yama-Tsu-Mi and Saka-no-Mi-Wo-no-Kami, gods of the mountain slopes; Masaka-Yama-Tsu-Mi, god of the steep mountain slopes; Ha-Yama-Tsu-Mi, god of the lower mountain slopes; Shigi-Yama-Tsu-Mi, god of the mountain foot; Kama-Yama-Hiko, god of mountain minerals; the goddess Kanayama-hime (Metal Mountain Deity); her brother Kana-yama-biko-no-kami (Metal Mountain Prince Deity). *See also* Amaterasu; Fuji; Hikohohodemi; Hoderi; Hosuseri; Izanagi; Izanami; Kagu-Tsuchi; Kanayama-hime; Kaya-no-Hime-no-Kami; Ninigi; O-Yama-Tsu-Mi.

Sengen-Sama (Japan) *see* Sengen.

Senk-hra (Egypt) *see* Aai.

Senki (Egypt) *see* Aai.

Sennins *Sennin* (Japan)
Also known as: *Weiwobo.*

Sometimes known as one god, sometimes as more than one god with various attributes. High god. Tobo-saku. Known variously as the "Prime Man of the East," and Weiwobo, the "Queen Mother of the West." The Prime Man of the East is an old man who never grows any older. His immortality is symbolized by a peach in his hand. The Queen Mother lives on a plateau, close to Heaven, far to the west of China. Rafu-sen is the female deity of the plum-blossom. Kinko Sennin rides on a pure white crane and plays his harp while flying through the air. Kiku-jido, deity of the Chrysanthemum, is an eternal boy who lives somewhere in the mountains. Most of the Sennins are shown as a man seated on a chair with a staff in his hand. *See also* Izanagi (for peach symbolism).

Senx (Bella Coola People, North America)
The sun. Senx is called "Our Father." *See also* Alkuntam.

Sepa (Egypt) *see* Centipede.

Sepes (Egypt)
A deity who lives in the persea tree at Heliopolis.

Sept (Egypt) *see* Aaru.

Septu (Egypt) *see* Sopdu.

Seqeq (Egypt) *see* Sebek.

Sequana (Gallo-Roman)
Sequana, an early deity, is the river and earth goddess of the Seine and its valleys. Relics from her sanctuary were found in marshes near the source of the Seine River. Her sanctuary was thought to be a healing center, based on the found objects, which included human and animal figures, torsos, heads, limbs, and internal organs. The items may have been offerings to the deity. During her festival, the Celts pulled an image of a duck with a berry in its bill along the river. Other Celtic river goddesses are Belisama, Clutoida of the Clyde, Devona of the Devon, Matrona of the Marne, and Verbeia of the Wharfe. *See also* Belisama.

Sequinek *Seqinek* (Eskimo)
Aspect. Another name for God of the sun.

Ser-Kheru (Egypt) *see* Assessors.

Seraa (Egypt) *see* Aai.

Serafili (Muslim) *see* Gabriel.

Seraphim (Hebrew) *see* Angels.

Serapis *Sarapis* (Greek)
Also known as: *Apis, Asar-Apis, Asar-Hap, Asar-Hapi, Asarhap, Hapi-Asar, Osiris-Apis, Usur-Api.*

The Greeks derived the name Serapis from a combination of Osiris-Apis. During the Ptolemaic period Serapis was the Egyptian state god under the Greek rulers. In Greece, Serapis, a god of the underworld, was worshiped as god of the Ptolemies in the Serapeum temple in Alexandria. It was in Alexandria that the funeral cult of the dead bull was celebrated. Many of the myths attached to Serapis are similar to those of Osiris because in Memphis, Serapis was confused with Osorapis (Osiris Apis), the Greek name for Apis, and was worshiped with Osorapis. Serapis is shown as a bull-headed man wearing the solar disk and the uraeus between his horns. He is also shown wearing a corn modius on his head. In Greece and Rome he was usually represented as a figure similar to Pluto or Hades. Serapis is sometimes identified with Zeus, Asclepius, and Dionysus. *See also* Amentet; Apis (A); Argus (A); Onophris.

Serekhi (Egypt) *see* Assessors.

Serpent Lady (Aztec People, Mexico)
A name for Coatlicue. She is also variously called the Serpent Petticoated and Serpent Skirt. *See also* Coatlicue.

Serpents (Egypt)
Also known as: *Dragons.*

Sacred magical formulae. In the text of *Unas*, there are a series of short magical formulae, many directed against serpents. The following serpents are included: Ufa, Nai, Heka, Hekret, Setcheh, Akeneh, Amen, Hau, Antaf, Tcheser-tep, Thethu, Hemth, and Senenahemthet. The Nagas, Azi-dahak, Ahji are a few of the serpents of India. Kou-lung is a serpent from China. Even in Christianity St. George had his dragon.

Serqet *Selket, Selqet, Selquet Serket* (Egypt)
Also known as: *Salkis.*

Underworld deity. Protector of the dead and living. Scorpion goddess. With her winged arms widespread, she protects the mummy and guards the canopic jars containing the viscera. With the goddesses Neith, Isis and Nepthys, Serqet, the daughter of the sun god Ra, watches over the body of Osiris. During the Seventh Hour of Ra's journey to Tuat, Serquet confronts, seizes, and ties up the evil serpent, Neha-bra, who attempts to

www.ebook3000.com

Activating the Six Directions and the Three Fires

This powerful energetic technique allows one to extend the mind, to touch the force, and to draw that energy back into the body.

The Six Directions teaches you how to expand your mind and Chi for receiving healing power. By practicing the Six Directions daily you will increase your healing and cosmic power. Turn your mind and Chi into the cosmos, multiply them and draw them back.

Direction Below

When you achieve the three minds into one mind begin expanding into the Six Directions; press your hands down and start with the low direction. Picture yourself standing on the earth and you expand yourself very far away – deep down into the earth, very, very deep down into the earth. Your hands become very long; your feet become very long — they go all the way down into the earth and out past it into the galaxy below on the other side.

Push. When you push, connect with the galaxy below — pull and think about your Tan Tien filling with Chi. Push and pull. Push and pull. Fill your Tan Tien with Chi.



A. ***B.*** ***C.***

Fig. 3.26 A. *Hands expand through the earth and to the galaxy below.* ***B.*** *Hands push forward and pull back.* ***C.*** *Smile to the primordial Chi from the universe back to the Lower Tan Tien and fill the Tan Tien with Chi.*

prevent Ra's boat from moving ahead. Serquet is depicted as a woman with a scorpion on her head and also as scorpion with the head of a woman. She is a companion of Isis and once sent seven of her scorpions to protect Isis from Set. She also protected Qebhsenuef. Worshipers of Serqet will never feel the scorpion's sting. *See also* Ab-esh-imy-duat; Hapy (A); Isis; Neith; Nephthys; Tuat.

Serqi (Egypt) *see* Aai.

Ses-rab-kyi-pha-rol-ta-phyin-pa (Tibet) *see* Prajmaparamita.

Sesa (India) *see* Sesha.

Sesha *Sesa, Sesha, Seshu, Shesha* (Brahmanic, Hindu; India)
Also known as: *Ananta* (Endless), *Anata, Anata-Sesha, Sesanaga, Virupaksha.*
Sesha, the world serpent, and Vasuki, one of the three kings of the Nagas, were used by the gods as a rope, in the churning of the Ocean of Milk. Sesha forms the couch where Vishnu rests on the primal sea. With his thousand hooded heads, he provides shade for his master. He is one of the Nagas kings who rule in Patala, the underworld. He is the son of Kasyapa and Kadru and the brother of Manasa. Sesha came into being when he sprang from the mouth of Bala-Rama as he was dying. His name, given to him by Brahma, means "eternal." Earthquakes are caused when he moves one of his heads. At the end of each kalpa (1,000 ages), he destroys the world with fire. Sometimes he is represented as a man in the form of Bala-Rama. As a serpent, he is depicted with a thousand heads, dressed in purple, and holding a plow and pestle. He symbolizes Time. Sesha is sometimes identified with Vrita. *See also* Bala-Rama; Kadru; Kalpa; Kurma (for churning of the ocean of milk); Manasa; Nagas and Nagis; Narayana (B); Nataraja; Patala; Vasuki; Virupaksha; Vishnu; Vrita.

Seshat (Egypt)
Also known as: *Sefkhet-Aabut, Sesheta.*
Deity of builders. Goddess of writing. Seshat is closely linked to Thoth as the patroness of writing and literature and the recorder of historical events. She is a helpmate to Thoth in his work and is the wife most often mentioned in connection with him. Her epithet is "She Who Is Foremost in the House of Books." She is also known as "Lady Builder." Seshat is a deity of the stars and to builders by aiding them in the stellar alignment of new structures, especially temples. She is depicted wearing a crescent and star with two plumes on her head or a headdress resembling a seven-pointed star crowned by a bow or a crescent. She usually wears a panther skin over her dress and holds a palm leaf in her hand. *See also* Sefkhet-Aabut; Thoth.

Sesheta (Egypt) *see* Sefkhet-Aabut; Seshat.

Seshetai (Egypt) *see* Aai.

Seshmu (Egypt)
God of perfume. Perfume deity and provider. Seshmu is mentioned from the Old Kingdom onward as the god of perfume and a provider, perhaps of material goods. Fragrance, aside from the olfactory advantages, was said to be infused with the power for immortality.

Seshu (India) *see* Sesha.

Sesi (Egypt) see Aai.

Sessrumnir (Norse; Teutonic)
Sessrumnir is the hall of the goddess Freyja in Asgard. *See also* Asgard.

Sessrymner (Teutonic) *see* Freyja.

Set *Seth, Seti, Sut* (Egypt)
Also known as: *Sutekh, Typhon.*
God of evil and darkness. Weather deity. Known as a born plotter. Set is the son of Geb and Nut, brother of Osiris, Isis and brother/husband of Nephthys. Sometimes he is known as the father of Anubis. In ancient times, he was the patron deity of Lower Egypt. When Upper Egypt overtook Lower Egypt, he became known as the god of darkness and the evil opponent of his nephew, Horus. During the Hyksos period he was worshipped as the chief god. During the Nineteenth and Twentieth Dynasties Set was known as a benevolent god who restrained the forces of the desert. He was the patron of the Ramessides. His good standing did not last long and by the Twenty-first Dynasty, he was once again the god of evil. He was insanely jealous of his brother Osiris, and numerous myths relate how he slaughtered him. In one tale, he tricked his brother Osiris by having a chest made that could only fit Osiris. When Osiris got in the chest, it was sealed and tossed into the Nile. The chest was found by Isis, but later came back to Set, who cut Osiris' body to pieces. Isis found all of the body except the penis and scrotum and restored Osiris to life. Set was slain in vengeance by Horus and thrown into the desert to live forever. Set is represented as having a hyena-like body, the muzzle being pointed and the ears high and square. In his aspect as Akherkh, he is a griffin-like animal. Set is represented as darkness and has been compared to a destructive, cruel sea, while Osiris, his direct opposite, is compared to light and the river Nile for his life-giving attributes. Set has many animal aspects: the antelope, donkey, ass, crocodile, and sow. The ass, often thought of as slow and stubborn, was an insignia of Set. It symbolized lust and cruelty. In Greece, as an animal sacred to Silenus and Bacchus, it represents wisdom and prophetic powers. Set is identified by the Greeks as Typhon. *See also* Ab-ta; Akherkh; Anat; Atum; Bast; Horus; Isis; Osiris; Seth; Sopdu; Typhon (A).

Set-Hra (Egypt)
A monster serpent who guards the entrance to the eighth sector of Tuat.

Set-Kesu (Egypt) *see* Assessors.

Set-Qesu (Egypt) "Crusher of Bones." A demon.

Seta-Ta (Egypt)
Guardian. Seta-Ta is a mummified god standing at the end of the corridor in the fourth sector of Tuat.

Setana (Celtic) *see* Cuchulain.

Setanta (Celtic) *see* Cuchulain.

Setcha (Egypt)
Setcha is an animal having the body of a leopard and the head and neck of a serpent.

Setcheh (Egypt)
Serpent demon used in the magical formula of *Unas.*

Setchet (Egypt) *see* Akeneh.

Setem (Egypt)
God of hearing. He is depicted with an ear above his head.

Seth (Egypt) *see* Set.

Setheniu-Tep (Egypt)
Afterworld deities. Four divine beings wearing white crowns found in the eleventh sector of Tuat.

Sethu (Egypt)
Also known as: *Setu.*
Sethu is a monster serpent god who guards the entrance to the tenth sector of Tuat. He carries a spear.

Seti (Egypt) *see* Set.

Setu (Egypt) *see* Sethu.

Seven Against Thebes (Greek)
They attempted to conquer the city of Thebes, unsuccessfully. Their sons, the Epigoni, successfully made the same attempt on the city of seven gates, ten years later. For details *see also* Adrestus.

Seven Generation Deities, The (Japan) *see* Ama-no-minaka-nushi.

Seven Snakes (Aztec)
A name for the maize goddess, Chicomecoatl.

Sgeg-mo-ma (Tibet) *see* Lasema.

Sgrib-pa-rnam-sel (Tibet) *see* Amoghasiddhi.

sGrol-mas (Tibet) *see* Tara.

Sha (Egypt)
Sha is a deified composite animal who has long square ears and a tail that looks like an arrow. It resembles the animal of the god of evil and darkness, Set.

Sha-kya-tup-pa (Tibet) *see* Sakyamuni.

Shadrapha (Phoenicia)
Also known as: *Shed the healer.*
God of Healing.

Shahapet (Armenian, Iranian, Slavic)
Also known as: *Khshathrapati, Shavod, Shoithrapaiti, Shvaz, Zd.*
Known as an Armenian lord of the land, he appears as a man or a serpent. He is a good spirit, unless he is angered. When found in houses, he is called Shavod, and is known as a lazy household guardian. On the last day of February he is forced out of the house to take up his duties in the field. The householders bang on the walls of the houses with old clothes, sticks and bags to arouse him. As a spirit of graveyards or fields, he is known as Shavz. Shahapet, Shvod, and Shavz are used in combination to frighten children. Similar to Iranian Khshathrapati. *See also* Shvaz; Shvod.

Shahar and Shalim (Canaan, Syria)
Also known as: *Ab, Amm, Kahil, Wadd, Warah.*
"The Gracious God." Twins sons of El. Shahar ("dawn") is the god of dawn, and Shalim ("peace") the god of sunset. South Arabians had many names for the moon god: Warah (the Wanderer), Kahil (the Old One), Wadd (the Loving) and Ilmuqah, which has no meaning, but may follow in the same vein as Ab (father) or Amm (ancestor or uncle) Associated with the Canaanite Shemesh, a sun god, and Yareah, god of the moon. *See also* Alilah; El; Elohim; Il; Ilah.

Shahpet (Armenian) *see* Shvaz.

Shahr (Mesopotamia) see Ba'al Shamin.

Shahrevar *Shahriver* (Persia) *see* Khshasthra Vairya.

Shahriver (Persia) *see* Shahrevar.

Shai (Egypt)
Also known as: *Shait.*
"Fate." The god Shai accompanies each human from birth to death, decreeing the course of his life, and appearing with the soul of the dead when it is tried and judged before Osiris. Sometimes Shai is coupled with the goddess Renenet ("Fortune"). She stands near the pillar of Balance where the dead are judged. *See also* Aai; Osiris; Renenet.

Shait (Egypt) *see* Shai.

Shaitan *Shetan* (Islamic)
An evil spirit. In the Arabic tradition, Shaitan are one of five types of Jin. *See also* Azazel; Devil; Jin.

Shakrani (India) *see* Indrani.

Shaktar (India)
The demon who was originally King Kalmashapada. *See also* Parashara.

Shakti *Sacti, Sakti* (Pre-Vedic, Hindu, Saktism, Tantraism, Tantric Buddhism, Mahayana Buddhism; India)
Also known as: *Aditi, Asa Poorna, Buddha Krotishaurima* (Tibet), *Cha-dog-ma* (Tibet), *Chak-yu-ma* (Tibet), *Devi, Durga, Gokarmo, Hlamos, Kanya-Kumari* (Daughter-virgin), *Kunto-bzang-mo* (Tibet), *Lakshmi, Mamaki* (Tibet), *Manasa, Matris (the), Maya, Nam-kha-ing-kya-wang-chug-ma* (Tibet), *Padma Krotishhaurima* (Tibet), *Prakriti, Ratna Krotishaurima* (Tibet), *Sangyay Chanma* (Tibet), *Sarasvati, Til-bu-ma* (Tibet), *Varuni, Yasodhara.*
Shakti is the Mother Goddess. She personifies the creative and destructive aspects of Divine Power. The Mother Goddess has come into the world in many forms to destroy evil and strengthen good. In the *Tantra,* there is one Universal Power, one Supreme Being, the Divine Mother. From herself, she created herself and her male aspect. In Hindu and Budhhist traditions, she is the consort of the god and represents his female aspect. Each member of the Hindu Trimurti has his Shakti. Shakti is also an epithet for many Indian and Tibetan goddesses. *See also* Ankusha; Devi; Durga; Ganesha; Hayagriva; Heruka; Kinkini-Dhari; Kuntu-bzang-mo; Lakshmi; Mamaki; Maya (A); Purusha (regarding Prakriti); Ratna Krotishaurima; Soma; Vairocana; Vilva (sacred tree); Zhag-pa-ma.

Shakuntala *Sakuntala Sacontala* (Hindu; India)
Raised by the sage Kanwa, this nymph became the mate of Dushyanta and mother of Bharata (q.v.).

www.ebook3000.com

Shakura (Pawnee People, North America) *see* Pah; Tirawa.

Shakuru (Pawnee People, North America)
Also known as: *Atius, Atius Tirawa.*

High god. Shakuru is the messenger between earth and the sky spirit, Tirawa. Some say he is a god of health and strength. *See also* Atius Tirawa.

Shal-za-ma (Tibet) *see* Nidhema.

Shala (Chaldea, Sumer)
An ancient Sumerian goddess of compassion, Shala was later included in the Chaldean Pantheon. She is the consort of Adad, or some say Marduk as Merodach, Dumuzi and Ramman. *See also* Dumuzi; Marduk; Ramman.

Shalem (Canaan, Syria) *see* Shahar and Shalim.

Shamas (Babylon) *see* Shamash.

Shamash *Chemosh, Shamas, Shemesh* (Mesopotamia) *Shamshu, Samsu or Sham-shu* (Arabia), *Chemosh, Shemesh.* (Probably of Sumerian origin, then adopted by the Akkadian people along with the entire Sumerian pantheon.)

Also known as: *Babbar, Shahan* (possibly), *Shullat, Utu* (possibly).

Sun god. In the regions of Sippar and Larsa, a god of divination. Possibly a deity of fire under the name of Shahan and a god of prophecy. Shamash is the son of Sin the moon god, or some say Enlil. He is the twin brother/spouse of the passionate goddess Ishtar. (Some say Aya is his spouse.) He is the father of Kittum ("truth") and Mesharum ("justice"). Originally a Semitic deity, Shamash was brought to Mesopotamia by the Akkadians. With his father, Sin, the moon-god, and his twin sister, Ishtar, Shamash forms an important triad. Elsewhere, he is one of a Babylonian triad with Sin (the moon) and Ramman (weather god). Shamash has the ability to deliver oracular responses of prophecy. His chief sanctuary was in Babylon, and he was also worshiped, possibly as Utu or Babbar at Sippar and Larsa or Ellasar. Scorpion men open his vast palace door every morning. (He lives in the mountains somewhere in the east.) His driver Bunene waits in the chariot for Shamash armed with his saw to mount the vehicle. They set out on their daily journey. At day's end they enter through another vast door in the mountains of the west and travel through the earth to their starting place. The sun and moon were represented by a crescent and disk by the South Arabians from the ninth to second century. His Sumerian counterpart is Utu. Shamash is associated with Gilgamesh. *See also* Aa, Aah, Ba'al Shamin; Mithra; Mitra; Shamash; Sin.

Shamashana-Kali (India) *see* Kali.

Shambara (India) *see* Sambara.

Shamshu (*Samsu*) (Arabic) *see* Shamash.

Shan Kuei (China)
Demon of the mountains. One of the nine heroes.

Shang Ch'ing *San Ch'ing* (China)
Supreme god of the "Superior Heaven." *See also* Lao-tien-yeh; San Ch'ing; Yu-huang-shang-ti.

Shang-di *Shang-ti* (China)
Ruler on High. Shang-di is the highest god of the Shang dynasty. He was later equated with Tian and was important in state rituals.

Shang Ti (China) *Shang-Ti*
Also known as: *Huan-T'ien Shang-Ti, Huang-Ti, Ti.*

Supreme god. Shang dynasty. The ancients knew him as the "Lord of the Dark Heaven," who was supreme over five deities. Each god had a sector of the sky. Ts'ing-ti, called the Green Lord, was in charge of the East. Ch'i-ti was over the South and was called the Red Lord. The god of the West was Po-ti, who was called the White Lord. Huan-ti, god of the North, was called the Dark Lord and the Center was under the rule of the Yellow Lord, Huang-ti. Shang Ti is represented as a man ten feet tall, surrounded with a halo, his long hair hanging over his back, generally clothed in a black robe. He is sometimes depicted as sitting on the back of a tortoise which is circled by a serpent. *See also* Chen Tsung; Huang T'ien; Lao-tien-yeh; T'ien; Yu-huang-shang-ti.

Shango (Yoruba People, Africa)
Earth god. God of thunder and lightning. Storm god. God of the east. God of war. God of justice and fairness. Shango is the earth born son of Obtala and brother of Ogun. He was the mortal king of Oya as well as a doctor who lived in a palace with several wives, including Oya, Oshun and Oba. His wife Oya had the reputation for being a very fierce woman who had an abundant beard. Shango had a bad temper and when he was angry he could kill by breathing fire. However, his wives apparently caused him great despair, for he committed suicide by hanging and now rules from the celestial realm. There, he acts as a god of justice. He punishes liars, thieves and those who work sorcery for negative means. The axe, representing the thunderbolt, is his weapon. When alive he carried a double-headed axe of stone said to have fallen from heaven. His altar is a three-forked tree that contains a basin with stones that also fell from heaven. In early days, if lightning caused fire, it was not extinguished even if a dwelling was burning because of the fear one had that Shango might retaliate. When Shango disappeared, his wife Oya changed into the river Niger. Shango is depicted with a double-headed axe similar to Thor's hammer. Shango represents thunder and the sound of thunder is said to be his bellowing. His sacred animal is the ram, and he is often shown with a ram's head and horns. From early times the Yorubas have been renowned for their bronze casting and their stone carving. Carved figures representing the Shango cult wore the double-axe insignia, often on the head or carried in their hands with a ram's head carved on the top. The Ashanti storm god is their supreme deity, Nyame. The Dinka People have the deity Deng, who has the aspects of a storm god. The Buganda war god Kibuka has storm god characteristics. Compare Shango to Zeus and Ammon-Ra. *See also* Ifa; Oba; Obtala; Olodumare; Oschun; Oya.

Shani (India) *see* Tapati.

Shankha-sura (India) A demon. *See also* Krishna.

Shantanu (India) King of Hastinapura. *See also* Vyasa.

Shap (Syria, Ugarit) *see* Shaphash.

Shaph (Ugarit) see Shaphash.

Shaphash *Shap, Shapsh* (Syria, Ugarit)
She is the sun goddess often called "Torch of the Gods," who helped Anath bind and carry the body of Baal to the top of Mount Tsaphon. There she assisted in his burial and the accompanying feast. Later, when he was resurrected but could not be found, Shaphash went to find him. She was successful and Baal once again sat on the throne in Zaphon. A fight took place between Baal and Mot. Shaphash arrived on the scene, separated them, intimidated Mot, and paved the way for a reconciliation. *See also* Anath; Baal; Mot.

Shapsh (Syria, Ugarit) *see* Shapash.

Shar (Sumer) *see* Anshar.

Shara (Armenian) God of food. Son of Armais.

Shara of Umma (Sumer) *see* Inanna; Shara.

Sharabha (India) *see* Shiva.

Sharanyu (India) *see* Saranyu.

Sharira (Buddhist) *see* Stupa.

Sharis (Urartian People of Armenia)
Mother goddess. She could be the forerunner of Ishtar as some of the Babylonian deities migrated to Armenia. Some place Sharis in the same category as Sammuramat, a name that is an epithet of Ishtar. There may even be some relation to the Armenian goddess, Semiramis.

Sharma (Hittite, Hurrian) *see* Sharruma.

Sharruma *Sharma* (Hittite, Hurrian) *see* Hepat.

Shasnli *Shakanli* (Choctaw People, North America)
Animal monster.

Shasti (A) (Bengal, India)
A protector of children, known as the Mother-Sixth, Shasti is worshiped on the infant's sixth day of life. Sometimes she is worshiped with Karttikeya as her spouse and she is considered to be his Divine Army. Shasti is depicted as riding a cat. She could be an aspect of Uma.

Shasti (B) (Hindu; India)
Shasti is the female form of the elephant-headed god, Ganesha.

Shastradevatas (India) *see* Devis.

Shata-Rupa (India) *see* Sarasvati.

Shatananda *Nandana* (India) Karna.

Shatarupa (India) "She of a Thousand Forms." *See also* Vach.

Shatrughna (India) Twin brother of Lakshmana (q.v.).

Shaumya (India) *see* Shiva.

Shaushga (Hurrian, Hittite) *see* Shaushka.

Shaushka *Shaushga* (Hurrian, Hittite)
Known as the Hittite Ishtar, Shaushka is the sister of three brothers, Teshub, Tashmishu and Hadad the storm god. Ishtar's name is usually used in the texts of the period in place of her own name. *See also* Ishtar; Teshub.

Shavod (Slavic) *see* Shahapet.

Shawano (Algonquin) *see* Manibozho.

Shaya (India) *see* Chhaya.

Shazau (Babylonia) *see* Marduk.

She-Chi *She, She-Tse* (China, Taoist)
Also known as: *Thu, Tu.*
Spirits of earth and grain, respectively. Possibly a single spirit with the same attributes. Also called gods of soil and crops. According to some this deity was originally an official under the rule of the Yellow Emperor.

She-Tse (China) *see* She-Chi.

Shedu (Babylon) *see* Sedu.

Sheehogue and Deenee Shee (Irish. Called the "Gods of the Earth" in the *Book of Armagh*)
Also known as: *Marcra Shee* (fairy cavalcade), *Slooa-shee* (fairy host).
Fairies. The Sheehogue and Deenee Shee are fallen angels, not good enough to be saved, but not bad enough to be lost. At one time, they were the giants of the Tuatha De Danann, but became smaller as they were no longer worshiped. Among them are the Pookas and Fir Darrigs, who are bad fairies. The other fairies are mischievous, but not bad. Sheehogue (sidheog) is singular, Deenee Shee (daoine sidhe) is plural. *See also* Banshee; Leprechaun; Tuatha De Dannan.

Shehbui (Egypt)
Shehbui, the god of the south wind, is portrayed as a lion-headed man with four wings.

Shelartish (Urartian People, Armenia)
Shelartish is possibly a local god or one of the less important moon deities. He is associated with the goddess Sharis. There is a possibility that he was part of an early Urartian pantheon along with either Khaldi and Theispas or Shamas and Ramman.

Shelf of the Slain (Teutonic; Norse) *see* Valaskjalf.

Shelva (Toltec People, Mexico)
Shelva is the giant who escaped the Great Deluge by climbing the mountain belonging to the god of water. When the waters subsided, Shelva built the pyramid of Cholula.

Shemerthi (Egypt)
God of bowmen. He is an archer god in the tenth sector of Tuat.

Shemesh (Mesopotamia)
Sun god. Little known deity, but he might have been a twin of Yareah who was a moon deity. He is associated with Shahar and Shalem who are deities of dawn and sunset. *See also* Shahar and Shalem; Shamash.

Shemsu Heru (Egypt)
They are lesser deities who are the assistants to the god Horus. They also aid the dead.

www.ebook3000.com

Shemti (Egypt) *see* Ab-ta.

Shen Nung (China) *see* Shen-nung.

Shen-Nung *Shen Nung* (China)
God of Agriculture. Deified mortal. Shen-Nung's son is the spirit of grain, Chu. Shen-Nung, the emperor of the third millennium B.C.E., brought the skills of agriculture to his people. After his death he was deified.

Shen Shu (China) *see* Shen-T'u.

Shen-T'ao (China) *see* P'an-T'ao.

Shen-T'u (Taoist; China)
Also known as: *Men-Shen, Shen Shu.*
Guardian. They are the original door guards of the early Chinese. Along with Yu-Lu and Shen Shu (or Shu Yu) the two gods guard the gates to hell. They were later replaced by the Sniffing General and the Puffing General. Men Shen is the collective name for the door gods. *See also* Hu Ching-te; Men Shen; Ts'in Shu-pao.

Sheng-Mu *Sheng-mu* (Taoist; China)
Also known as: *Nai-nai Niang-niang, Pi-Hia Yuan-Kun, T'ai-Shan Niang-Niang, T'ien-Hou.*
Mother goddess. Goddess of women and children. Her family name is Ch'en. Sheng-Mu is the daughter of T'aiyuehtati, the Emperor of the Eastern Peak. She is the wife of Mao Ying. She is a personal god (one who did great deeds during her lifetime). The daughter of a fisherman, she has the ability to cast out demons. She is the patron of farmers and fishers as she used her gift to aid them during her lifetime. She died at twenty-one. She keeps two of the demons she tamed with her. They act as messengers. Sheng Mu is shown wearing a headdress made of three birds with outspread wings. She is usually associated with the goddess of healing, Sung-tsi niang-niang (q.v.).

Shennda Boaldyn (Isle of Man) *see* Beltine.

Sheol (Hebrew)
Also known as: *Hell.*
Underworld. The grave or dwelling place of the dead. A place of darkness. The early Israelites pictured Sheol as a dim, underground world where all the souls of the dead were sent. It is a place without torture, but Sheol is also without joy. Sheol is similar to Arallu, Gehenna, Hades, Hell and Tuat.

Shepes (Egypt)
Aspect of Thoth. Shepes is a form of the god Thoth who appears in the seventh sector of Tuat. He is depicted seated with three headless figures, enemies of Osiris, kneeling before him. Their hearts have been ripped out and their bodies chopped up. There are other interesting figures in various positions around him: the god Af-Asar, the serpent Ankhtith, Hekenth the lion-headed goddess, and three hawks wearing double crowns on their human heads. The god Af-Tem sits regally nearby on a serpent shaped like a throne. Horus, whom Shepes in the form of Thoth once cured, also appears during this period with a retinue of gods and the goddesses of the twelve hours. *See also* Abesh-imy-duat (for other supportive members and enemies of this hour); Horus; Thoth.

Shepi (Egypt) *see* Aai.

Shesat Maket Neb-s (Egypt)
Afterworld deity. The name of the second hour of the night in Tuat. Osiris or the dead pass through the country called "Urnes" using the boat of Ra, proceeded by four other boats. The gods who minister to the dead in the second hour are Isis, Khnemu, Seb, Thoth, Afu, Ketuit-ten-ba, Kherp-hu-khefti, Heru-Tuat, Seben-hisq-qhaibit, Benth (two ape gods), Aana, Horus-Set, Mest-en-Asar, Met-en-Asar, Sesenet-khu. Following are the seven goddesses: Mest-tcheses, Amam-mitu, Hertuaiu, Sekhet of Thebes, Amet-tcheru, Ament-nefert, Nit-tep-Ament. Then there are Nebui, Besabes-uaa, Nepr, Tepu, Hetch-a, Ab, Nepen, Ar-ast-neter, Amu-aa, Heru-khabit, Anubis, Osiris-Unnerfer, Khui, Horus and Set, Hen-Heru, Hun, Hatchetchu, Nehr, Makhi, Renpti, Afu, and Fa-trau. *See also* Tuat.

Shesemtet (Egypt)
She is the lion-headed sky goddess consort or wife of Shesemu.

Shesemu *Shesmu* (Egypt)
Underworld or afterworld deity. God of the wine press. Shesemu is the lord of the last hour of the night and consort or husband of Shesemtet. As the god of the wine press he pushes the head of transgressors into the wine press and crushes their skulls. He is shown as a human with lion or ox head. *See also* Tcheser-tep-f; Tuat; Unas.

Shesera (Egypt)
Afterworld deity. A god that appears in the tenth sector of Tuat. He is depicted armed with arrows and with a solar disk for a head.

Shesha (India) *see* Sesha.

Shesmu (Egypt) *see* Shesemu.

Shesshes (Egypt) *see* Ab-ta.

Shet-Kheru (Egypt) *see* Assessors.

Sheta-Ab (Egypt)
Guardian of the sixth sector of Tuat. His name means "Secret heart."

Shetan (Islamic) *see* Shaitan.

Shetu (Egypt)
A serpent monster. He has the unusual ability to disappear into his own body when Ra ceases to speak. He appears in the eleventh sector of Tuat.

Shi-pa Lo-han *see* Arhats.

Shi Tenno, The *Shitenno* (Buddhist; Japan)
Guardians. The Shi Tenno, said to be five hundred years old, are guardians of the four cardinal points of the compass. They function as protectors of the world against the demons. Their names and directions are often given as guardian of the north, Bishamon, also known as Tamon; of the south, Zocho; of the west, Komoku; and of the east, Jikoku. Another list gives the north to Bishamon; the south to Komoku; the east to Jikoku; and the west to Zocho. The Shi Tenno are often located at temple gates to ward off evil spirits. The Nio serve a similar function. These and other guardian figures are known as Kongo Rikishi,

or the strong men who hold the thunderbolt. The guardian figures are often depicted as "foreigners" with long curly hair, bulging eyes and fierce expressions on their faces. *See also* Bishamon; Godai-myoo; Jikoku-Ten; Konko-Yasha-Myoo; Nio; Shichi Fukujin.

Shi-tien Yen-wang (China) A name for the ten Yama Kings (q.v.).

Shi-wang (China) *see* Yama Kings.

Shichi Fukujin, The (Buddhist; Japan)

The Shichi Fukujin are the seven deities of luck, a group of six gods and one goddess. Their names are Benten the goddess of love; Bishamon the god of war; Daikoku the god of prosperity; Ebisu the god of workers and fishing; Fukurokujin the god of health and longevity; Hotei the god of good luck and generosity; Jorojin the god of wisdom. These deities have come together from different origins. Benten, as Benzaiten and Bishamonten (a male and female), is originally Hindu. Fukurokujin, Jorogin and Hotei are of Chinese origin. The name Pusa is a common European rendition for Hotei. The healer and sorcerer, Okuni-Nushino-Mikoto combined with Daikoku, became one of the Shichi Fukujin or Seven Gods of Happiness in later mythology. The images of the Shichi Fukujin were worn as charms. Benten is shown with a lute; Bishamon holds a weapon with an ax-like blade and a steel spike mounted on the end of a long shaft (similar to a halberd); Daikoku holds a mallet and sits on two rice bales; Ebisu holds a fishing rod and a plate of fish; Fukurokujin is depicted with a stork, a cane and a book of fate; Hotei has a large belly, a big smile and holds a bag containing desirable items; Jorojin is accompanied by a deer. Bishamon was also one of the guardians of the four points of the compass known as the Shi Tenno. *See also* names of individual deities for additional information and various spellings of names. *See also* Hiruko; Okuni-Nushino-Mikoto.

Shidure (Sumer) *see* Siduri.

Shidurri (Sumer) *see* Siduri.

Shigi-yama-tsu-mi (Japan)

God of the mountainfoot. *See also* O-Yama-Tsu-Mi; Sengen.

Shih-chia-mou-ni (China) *see* Sakyamuni.

Shiho-Tsuchi (Japan) *see* Hikohodemi; O-Wata-Tsu-Mi.

Shiko-Me *Shikome* (Terrible Woman); (Japan)

Also known as: *Gogo-me, Gogome, Hisa-me, Hisame, Yomo-tsu-shiko-me* (Ugly-Female-of-the-World-of-the-Dead).

Devils. Evil female spirits. Storm deities. The Shiko-Me are grotesque, evil, female deities who reside in Yomi, the underworld. Izanami was chased by a crowd of these demons along with eight attendant thunder demons and fifteen hundred assistant devils, as he fled from Yomi. Some say the Shiko-Me were an early form of the devil deities, the Oni. *See also* Gaki; Izanagi; Izanami; Kappa; Oni; Tengu; Yomi.

Shikome (Japan) *see* Shiko-me.

Shilup (Choctaw People) *see* Shilup Chito Osh.

Shilup Chito Osh (Choctaw People, North America)

Also known as: *Shilup.*

The Great Spirit or the name of a ghost.

Shima-tsu-hiko (Japan) *see* O-wata-tsu-mi.

Shimhanada Lokeswara (Buddhist; India)

Healer. Shimhanada Lokeswara is an aspect of Avalokitesvara and is regarded by the Mahayanist Buddhist as a healer of all diseases. He appears in many forms which vary slightly from one another. Shimhanada Lokeswara is depicted with a white complexion, three eyes, and a crown of matted hair (Jatamukuta). He wears a tiger skin and sits on a lion. A white trident with a white snake wrapped around is held in his right hand. In his left hand, he holds a burning sword on a lotus. *See also* Avalokitesvara; Lokeswara.

Shimmei (Japan)

Shimmei is a name used for the goddess Amaterasu, who is a sun goddess, the founder of sericulture, the guardian of agriculture, the deity of peace and order and the ancestor of the ruling family. *See also* Amaterasu.

Shimti (Akkadian) Goddess of Fate. *See also* Ishtar.

Shin-je-she-chi-chyil-khor (Tibet) *see* Yamantaka.

Shina-to-be (Japan) *see* Shina-tsu-hiko.

Shina-tsu-hiko (Shinto) Japan

Wind god. Shina-tsu-hiko and Shine-tsu-hiko (Shina-to-be) were born of Izanagi's breath. They hold up the sky and fill the void between heaven and earth. They are the superiors of the minor wind deities Tatsuta-hiko and the goddess Tatsutsa-hime. Prayers are offered to Shina-tsu-hiko, Shine-tsu-hiko, Tatsuta-hiko and Tatsutsa-hime when a plentiful harvest is desired. These deities are also invoked by fishermen and sailors. Amulets are worn to protect believers from the ill-effects of the wind and protection against storms. Tasuta-hiko and Tatsutsa-hime are named after the sanctuary where they are worshiped. *See also* Amaterasu; Fu-jin (god of winds); Haya-ji (whirlwind deity); Izanagi.

Shine-tsu-hiko (Japan) *see* Shina-tsu-hiko.

Shining One, The (Greek) *see* Aglaia.

Shinto Creation Myth (Japan) *see* Ama-no-minaka-nushi.

Shio-Zuchi (Japan)

"Old Man of the Tide." Shio-Zuchi is another name for the god of the sea and ruler of all sea creatures, O-Wata-Tsu-Mi (q.v.).

Shiri-Kume-na-Nawa (Japan)

"Don't Retreat-Rope." This rope was tied across the entrance to the cave known as Ame-no-Iwato, where the light of the world, personified as the goddess Amaterasu, had sequestered herself. *See also* Amaterasu.

Shishupala (India) *see* Sisupala.

Shita-teru-Hime (Japan)

She is the daughter of Okuni-Nushino-Mikoto, the god of medicine and sorcery. Ame-no-Oshido-Mimi, the son of the

www.ebook3000.com

sun goddess, Amaterasu, fell in love with her. *See also* Ame-no-Oshido-Mimi; Haya-ji; Okuni-Nushino-Mikoto.

Shitala (India) *see* Sitala.

Shitenno *Shi Tenno* (Japan)
Guardians. The four guardian kings. Zocho (in India, known as Virudhaka), Jikoku (in India, known as Dhritarashtra), Komoku (in India, known as Virupaksha) and Tamon (in India, known as Vaisramana). They protect the East, West, North and South regions of the sky. The Shitenno are assisted by eight generals, who are also protecting deities. *See also* individual gods.

Shiu-Mu Naing-Naing (China)
Water mother. *See also* Hsi-Ho and T'ien-Hou.

Shiva *Siva* (Hindu; India).
Also known as: *Ananda* (Joy, Happiness), *Ardhanari-Ishvara* (The Lord Who Is Both Male and Female), *Ardhanariswara* (Nepal), *Asitanga* (With Black Limbs), *Badari* (Lord of Badari Shrine), *Baidya-isvar, Bhaga* (The Divine), *Bhadra Vira, Bhairab, Bhairava* (The Destroyer), *Bhutesvara* (Lord of Spirits and Demons), *Dakshina-Murti* (Facing South), *Digambara* (Clothed in Space, Dressed in Air), *Garudi* (Shiva's secret form as female bird of prey), *Hara* (Universe Destroyer), *Isana, Iswara* (Supreme Lord), *Kala-Siva* (Double-sexed god of time or death), *Kapala* (Skull), *Krodha* (Anger), *Mahadeva* ("Great God," a praise name for Rudra-Shiva), *Mahakala* (God of Irrevocable Time), *Mahayogi* (Great Yogi), *Maheshvara* (Great Lord), *Nandisha* (Lord of Nandi), *Nandisvara, Nataraja Siva* (King of the Dance), *Nataraja* (Cosmic Dancer), *Nilakantha* (Blue Throat), *Panchamukhi-Maruti, Pashupa, Pashupati, Pasupati* (Lord Protector of Animals), *Phra In Suen* (Siam), *Rudra* (Storm), *Ruru* (Hound), *Sanja, Sankara* (Healer), *Sarva* (The Destroyer), *Sanhara* (Destruction), *Sharabha, Shaumya* (a peaceful aspect), *Sudalaiyadi* (Dancer of the Burning Ground), *Sundara, Sundareshwar, Syama* (Black), *Tryambaka* (Three-mothered or Three-eyed), *Unmatta* (Raging), *Vaidya-nath* (Lord of the Knowing Ones or Lord of the Physicians), *Virabhadra* (Monster of Destruction), *Vishvanatha, Visnanatha* (Vishna's name as the presiding deity of the sacred city of Benares); (Brahmanic, Hindu, Vira-Shaivaisma, Vedic; India)

Shiva has one thousand and eight names and epithets. He is a creator god, moon god of the mountains, god of agriculture, fertility god, lord of the cosmic dance, god of the arts and learning, god of truth, god of luck, god of the rivers, god of the forests, god of death, of yoga, of cremation grounds, and the lingam. He was a god of a primitive Hindu religion, later adopted into the Brahmanic pantheon. In this capacity, he embraced the destructive qualities of his Vedic predecessor Rudra, the storm god of the *Rig-Veda*. Shiva's attributes are truth, energy, and darkness. It is said that he does not have incarnations, although some followers declare that he has twenty-eight. His celestial abode is Kailasa where the faithful hope to arrive after death. Shiva stands beneath the sacred river Ganges which flows from the Himalayas in great torrents. The water flows through his matted hair and divides into the seven holy rivers of India. Frequently he is called upon to assist other gods in their fight against evil. During the Churning of the Ocean of Milk, when the serpent demon Vasuki was used as a churning rope, he vomited poison. The toxin threatened pollution of the ocean and the death of the other deities. Shiva quickly caught the noxious spill in his throat. His wife Parvati sprang to his aid and strangled him to keep him from swallowing it. He survived and was left with the legacy of a blue throat. Shiva has eight terrifying aspects: Asitanga, Bhairava, Kapala, Krodha, Rudra, Ruru, Sanhara, and Unmatta. His consorts are aspects of the Great Mother Goddess Devi who appears as Gauri, Sati, Parvati, Uma, Durga and Kali. He is the third member of the Hindu Trinity and he represents the destroyer but has aspects of regeneration. The other two members are Brahma, who represents the principle of creation, and Vishnu, who is the preserver. As Ardhanari, Shiva represents Shiva with Parvati or Durga and is both male and female. Agni is identified with Shiva as Rudra-Shiva, his destructive aspect. The followers of Shiva maintain that Brahma created the universe and was outside of the universe. He was awakened by Shiva, in the form of Hansa the goose. From Brahma's head sprang Angira (memory), from his breast Dharma (very loosely translated as "the ultimate conduct of all things"), from his body, mind and matter. He then proceeded to divide his body in half, the right half being Manu, the first perfect man, and the left half female, Satarupa, who is Maya or "illusion." In the *Mahabharata*, it is written that Krishna worshiped Shiva. The Buddhist Shingon sect consider Fudo-Myoo an aspect of Shiva. Shiva, as the ascetic, is often depicted with white matted hair, and an ash-smeared body. He is seated on the skin of a tiger, elephant or deer, covered by a snake canopy. This position symbolizes that he has overcome aggression and greed. On each side of his third eye he has three horizontal gold stripes, known as *tiku*, his caste mark. (Vishnu has three converging vertical strokes). Around Shiva's blue neck, he wears prayer beads, and the writhing cobra Vasuki. The crescent moon is depicted on his forehead, the symbol of the sovereignty given to him at the Churning of the Ocean. His mount, the white bull Nandi, is nearby and his son with the elephant head, Ganesha, is at his feet. Nandi, the guardian of all quadrupeds, provides the music for the dance of Shiva Nataraja known as the Tandava. Nandi's symbol is the crescent moon and his consort is Nandini, the cow who could fulfill all desires. The elephant symbolizes strength, power, wisdom and knowledge. Shiva's emblems are the lingam (phallus) and the footprint. Worship of the lingam celebrates his creative power. He usually has four faces, three eyes and ten arms. He rules with his eastward face, rejoices with his northward face, delights in all creation with his westward face, and with his southward face he shows his angry and destructive side. Shiva is also shown with five faces, three eyes and four arms, wearing snakes as ornaments and a string of skulls around his neck. Sharabha is a form of Shiva who appears as a black monster with eight legs and tusks and long claws. He lives in the Himalayas and is said to be over a hundred miles in length. As the god of music, Shiva Nataraja has his hourglass drum and frequently a stringed instrument known as the *vina*. He is sometimes pictured as a type of Dionysus or a Bacchus, drunk with wine and dancing madly on the mountains. As Bhutesvara, he dances in Smashana, the cemetery where the dead bodies are purified. He wears a necklace of skulls, and is garlanded with serpents. In Smashana, visitors must avoid the Vetala, an evil spirit who sneaks into corpses and makes them act like zombies who commit unspeakable crimes. In other depictions Shiva carries a trident named Pasupata or Pinaka, created by the divine smith, Visvakarma, a bow named Ajagava (some call the bow Pinaka), an arrow, and a noose. He also has a club with a skull on the end named Khatwanga. His other attributes are the elephant and the rat. His sacred plant is the Asoka ("Calotropis Gigantea"). The Bilva (sacred fruit) and the Nirgundi, a three-leaved plant, are also his emblems. The leaves of the sacred Vilva (bel) tree are used in cermonial worship of Shiva and Shakti. Red China roses are essential in worshiping Shiva. In his manifestation as Nandisvara, he is shown in a ca. 9th century sculpture from Central Java as a slender prince dressed in royal attire, guarding the entrance to a shrine. He wears a crossed sacred thread, two girdles and two sashes, tied at the hip. His head, slightly inclined, is framed by an oval halo. His face shows a three-quarter profile. Behind his right shoulder is his traditional attribute, a trident. As Ardhanari-Isvara, he is represented with one female breast, depicting his male and female nature. During the moon-month Phalaguna the wedding of Shiva and Parvati is celebrated with a feast known as Shivaratri. Shiva represents the totality of all being and he aids all who worship him. If his name is repeated with devotion, faith and concentration, the heart is cleansed from sin and in rebirth the worshiper will live a happy life. *See also* Kurma regarding Shiva as Nilakanth. Compare Shiva and Nandi to Ptah and Apis (Egypt). Shiva corresponds to Vishnu (q.v.). Compare to the creation myth of Brahma. *See also* Andhaka; Ardhanariswara; Arjuna; Badari; Baidya-nath; Bana; Banalingas (sacred stones); Bhaga; Bhairab; Bhairava; Brighus; Daksha; Dakshina-Murti; Devi; Durga; Fudo-Myoo (Japan); Gramadeveta; Hanuman; Hara; Indra; Kala; Kali; Kalki; Kama (A); Krishna; Kuvera; Lokapalas; Mahakala; Manasa; Manu; Meru Mountain; Nandi; Nandisha; Nataraja; Panchamukhi-Maruti; Parashur Rama; Parvati; Pasupati; Pinka; Pushan; Ratri; Rudra; Sandhya; Saranyu; Sati (A); Sitala; Soma; Tara (A); Trailokyavijaya; Vasuki; Virabhadra; Visvakarma; Vritra; Yaksha and Yakshini.

Shivaratri (India) Celebration Feast. *See also* Shiva.

Shiwanni and Shiwanokia (Zuni People, North America)
When Awonawilona created clouds and the air, the sky deities, Shiwanni and his wife Shiwanokia, decided to be creative. Shiwanni spit on his hand, slapped it, and formed yucca suds. His floating suds became the stars and constellations. Shiwanokia's suds fell to earth and became Awitelin Tsita, the Earth Mother. *See also* Awitelin Tsita; Awonawilona.

Shk *Shakak* (Acoma People, North America)
The Winter Spirit. *See also* Iatiju.

Shoden (Japan) *see* Ganesha (India).

Shoithrapaiti (Slavic) *see* Shahapet.

Shojo (Japan)
The Shojo are denizens of the deep, who look something like orangutangs. They are merry deities and as they drink heavily, they are known as gods of sake, a rice wine. Their faces are red, and they have long red hair. They carry a dipper and wear gaudy dresses of red and gold.

Shokujo (Japan) *see* Amatsu-Mikaboshi.

Shony (Celtic) *see* Son.

Shore of Corpses (Teutonic) *see* Nastrond.

Shou (Egypt) *see* Shu.

Shou-hsing *Shou-Sing, Shouhsing* (China)
Also known as: *Lao-Jen, Nan-Chi, Shou-Lao.*
Shou-hsing is the god of long life, wealth and happiness. He is highly revered for his power to give mortals the gift of longevity. He records the destined date of a person's death, but could sometimes be persuaded, by honor and sacrifice, to alter his figures favorably. He is closely connected with the god of long life and salaries Lu-hsing (or Lu-sing) and the god of happiness Tsu-hsing, who were often depicted with him. This group is known as Fu-shou-lu. Shou-hsing is also known as Nan-chi lao-jen or Shou-lao (Old Man of the Southern Pole). Shou-hsing is generally depicted carrying a staff and holding a peach of immortality. He is an old white-bearded man with a bulbous bald head who is sometimes shown with a turtle or stork. Shou-hsing is part of a triad with Fu-hsing and Lu-hsing. He is associated with the god of happiness, Fu Shen, and the god of wealth and happiness, Ts'ai Shen.

Shou-lao (China)
Old Man of the Southern Pole. *See also* Shou-hsing.

Shou-Shen (China) *see* Shou-hsing.

Shou-Sing (China) *see* Shou-hsing.

Shou-Ts'ang (China)
Servant deity. Shou-Ts'ang executed justice on the orders of Kuan-Ti. He was also the squire and groom for the god of war.

Shouhsing (China) *see* Shou-hsing.

Shraddha (India) *see* Sraddha.

Shri (India) *see* Sri.

Shru (India) *see* Sri.

Shruisthia (Acoma People, India) The Autumn Spirit.

Shu *Shou* (Egypt at Nay-ta-hut; Libyan)
Also known as: *God of Air.*
God of atmosphere. God of dry winds. Shu and his sister/wife Tefnut were the first couple of the *Ennead* of Heliopolis. When his father Ra (the sun) ordered Shu to separate Geb and Nut from their embrace so light could come through, he did so. He held Nut up to form the sky. After the reign of Ra, Shu became the ruler of the world until he was overtaken by Apep's children. Weakened by the melee he gave the throne up in favor of Geb. The heavenly hosts threw a major farewell party that lasted for nine days. When it was over, Shu graciously retired to heaven. Shu and Tefnut were known as the "Twin Lion Gods." Overall, Shu personified the atmosphere which divides the sky from the earth. The goddess Isis wrote a book entitled *Book of Breathings* for her dead husband Osiris. It was concerned with the necessity of breathing in the underworld, of living after death. To do so, the deceased had to identify with the god Shu. Shu is usually depicted with one or more ostrich (or feather) plumes on his head and sometimes as the support of the vault of heaven. Shu's name means "dry," "empty." *See*

www.ebook3000.com

also Aai; Amun; Anat; Anhur; Geb; Heh; Isis; Khepri; Khnemu; Ra; Seb; Tefnut.

Shu-Hu (China)
Lightning. Shu, the northern god, and Hu, the southern god, created the world from the body of Chaos (Hun-tun). After the creation of the world, their names were combined and became the lightning that struck Chaos and allowed the world to emerge. *See also* Hun-tun.

Shu Yu and Yu Lei (China) *see* Men Shen.

Shualu (Babylon) *see* Aralu.

Shui Chun (China) *see* Shui Shen.

Shui I (China)
God of the waters. *See also* Nine Songs; Shui Shen.

Shui Jung (China)
Also known as: *Ch'eng Huang.*
As Shui Jung, he is one of the Pa Cha (Eight Spirits). As Ch'eng Huang, he is the god of walls and ditches. *See also* Ch'eng Huang.

Shui-kuan (China)
Also known as: *Shui Shen.*
Water deity. He belongs to the triad known as San Kuan. They are the Three Supreme Agents, or Three Origins. With Shui-kuan is T'ien-Kuan, the agent of heaven, and Ti-Kuan, the agent of earth. It is Shui-Kuan's job to defend men from evil. He rides his horse through water and is followed by fish. He is identical with Shui Shen. *See also* Nine Songs; San Kuan.

Shui Shen (China)
Also known as: *Shui Chun, Shui I, Shui-kuan.*
God of the waters. He is one of the Nine Songs, the nine creator gods. Shui Shen is similar to Yo Po and identical with Feng I. *See also* Nine Songs; Shui-Kuan.

Shukra *Sukra* (India) *see* Asuras; Brighus; Brihaspati.

Shullat (Sumer) *see* Shamash.

Shulmanu (Babylon) *see* Saramana.

Shura (Japan)
The Shura, male reincarnations of warriors who died in battle, are furious spirits who live in the sky where they fight one another.

Shurpanaka *Surpanaka* (India)
Shurpanaka is a Rakshasi (giant female demon) who is probably the daughter of Nikasha and sister of Ravana, Kumbhakarna, Khara, and Bihishan. *See also* Nikasha; Ravana.

Shutu (Mesopotamia)
South West Wind demoness. *See also* Ilabrat.

Shuznaghu and Zumiang-nui (Dhammai People, Northeast India)
Shuzanghu and Zumiang-nui lived above in a place were neither sky nor earth existed. Zumiang-nui gave birth to the earth goddess Subbu-Khai-Thung and the sky god Jongsuli-Young-Jongbu. The children fell from their space and were swallowed by the worm Phangnalomang. Zumiang-nui had another child and the worm came to devour it. Shuzanghu trapped him, split his stomach open and rescued his children who took their positions as the earth and the sky. They united and gave birth to the goddess Jibb-Jang-Sangne and the god Sujang-Gnoi-Rise, who became mountains, followed by a son, Lujjuphu, and daughter, Jassuju, who were born as frogs. In turn, they mated and gave birth to the first mortals, Abugupham-Bumo and Anoi-Diggan-Juje. They became the parents of Lubukhanlung, Sangso-Dungso and Kimbu-Sangtung. Abugupham-Bumo and Anoi-Diggan-Juje are described as being covered with hair. *See also* Agni; Brahma; Prajapati; Purusha.

Shvaz (Armenian)
Also known as: *Shahpet.*
Shvaz is a spirit or ghost of the fields who appears in the spring of the year. He may be identified with Shahapet (q.v.). *See also* Shvod.

Shveta Tara (India) "White Tara." *See also* Tara (B).

Shvod (Armenian)
This house guardian appears to mortals once yearly. He is beneficent unless he is angered. He may be related to Shahapet (q.v.). *See also* Shvaz.

Shyama-Kali (India) "The Black One." *See also* Kali.

Si-Wang-Mu (China)
Si-Wang-Mu is a name for Hsi-Wang-Mu, the goddess of epidemics, plagues and pestilence. *See also* Hsi-Wang-Mu.

Sia (Egypt)
Also known as: *Saa.*
God of the sense of touch or feeling, and of knowledge and understanding. Sia was born from the drops of blood that flowed when the sun god Ra mutilated his penis. He was subsequently invoked as a protector of the genitals of the deceased. Sia also is one of the gods who watch the heart of the deceased being weighed at the great judgment. *See also* Hu; Ra.

Sia People — Creation Legend (North America) *see* Sussistinnako

Sibhol (Celtic) *see* Eire.

Sibu (Andean People, Peru)
Creator. Sibu created rocks on which a monster bat defecated. From this material sprang trees and grasses. The bat could travel to the underworld (Nopatkuo) where he fed on the blood of Benu, the earth. Benu is the daughter of Namaitami who in turn is the daughter of Namasia. When the inhabitants of the underworld found out what the bat was doing they made a snare that cut the monster in half. Sibu healed the bat but required it to always keep its head down so its innards would not fall out. Now, the bat must always stay in this position. There are other stories about Sibu, one of which involves a flood myth. *See also* Sura (A).

Sibyl (Greek)
Also known as: *Sibylla, Sibylle, Sif.*
Prophet. There are numerous women in ancient mythology from various civilizations known as Sibyl. They are almost all prophets who also act as intermediaries between mortals and the gods. The original Sibyl is thought to be the Greek Sibyl,

daughter of Dardanus and Neso. When Apollo asked her what she wanted, she asked to live as many years as the number of grains of sand she held in her hand. But she forgot to ask for youth and consequently shrivelled to a tiny size. When children asked her, "Sibyl, what do you want?" she could only answer with the words, "I want to die." *See also* Amaltheia; Golden Bough; Sif.

Sibyl Herophile (Greek) *see* Lamia.

Sibylla *Sibyl* (Greek) *see* Sibyl.

Sibyls (Greek)
Deified mortals. Women with the gift of prophecy who interceded with the gods on behalf of human supplicants. The Sibyls are usually very young or very old. They reside in and around caves. *See also* Sibyl.

Sibzianna (Babylonian) *see* Tammuz.

Siddhaikaviramanjughos (India) *see* Manjusri.

Siddhartha *Siddartha* (Buddhist, Jain; India)
Also known as: *Buddha.*
Siddhartha is the father of Mahavira. Siddhartha is an epithet for Buddha and a praise name for saints. The name is also used to depict one who has accomplished total enlightenment and self-control, or who has accomplished his reason for being on earth. *See also* Buddha; Mahvira; Sakyamuni.

Siddhas, The (Hindu, Jain; India)
Also known as: *Siddhanganas* (male), *Siddhanjanas* (female).
The Siddhas, demi-gods with great occult powers, reside in eternal bliss in Sidda-Sila, a region above the Kalpas in the zenith of the universe. There are 88,000 holy beings, all manifestations of Vishnu. *See also* Loka.

Siddhi (India)
Goddess of success. *See also* Ganesha; Karttikeya.

Side (Greek) *see* Orion.

Sidero (Greek)
"The Iron One." She is the second wife of Salmoneus and stepmother of Tyro. Tyro's twin sons, Neleus and Pelias, rescued their mother when Sidero had her imprisoned, and then murdered Sidero. *See also* Cretheus; Salmoneus.

Sidhe, The (Celtic) *see* Tuatha De Danann.

Sidhi-Data (India) *see* Ganesh.

Sidhottr (Norse; Teutonic) *see* Odin.

Sido (Melanesian)
Also known as: *Hido, Iko.*
Hero god. He is a trickster and shape changer. His wife is Sagaru. In death he planted crops to feed the souls of the dead.

Siduri *Shidure, Shidurri, Siduru* (Assyro-Babylonian)
Also known as: *Ishtar, Siduri-Sabitu.*
Sea deity. She is described as a beautiful goddess who lives by the sea in the midst of a beautiful garden strewn with gems. When she could not deter Gilgamesh from his desire to find Uta-Napishtim, Siduri directed him to elicit the help of Urshanabi. Siduri is shown as a serpent. Others describe Siduri as a veiled barmaid who is a manifestation of Ishtar. Her home is on the seashore not far from the Land of Life where the deified mortal Utnapishtim lives. *See also* Ishtar; Sabitu; Utnapishtim.

Siduri-Sabitu (Sumer) *see* Siduri.

Siduru (Sumer) *see* Siduri.

Sie-king T'ai (China)
Magic mirror. Sie-king T'ai is the mirror used by Ts'en-kuang to judge the dead before he assigns them to one of the ten hells of Ti-yu. *See also* Ti-yu; Ts'en-kuang-wang.

Siegfried (Teutonic) *see* Sigurd.

Sien-tsan (China)
Also known as: *Hsi-ling Shih.*
Goddess of weaving silk. The goddess and patroness of the art of silk cultivation. In her mortal life, she had been the wife of the emperor Shen-Nung, who was also deified. There is a similar version where Hsi-Ling Shih was the wife of Huang-ti and introduced the silk worm to the Japanese. *See also* Huang-ti; Toyo-Uke-Hime-no-Himi; Ts'an Nu.

Sieroji Zemele (Lithuania) *see* Zemina.

Sif (A) (Greek) Sif is an alternate name for Sibyl.

Sif (B) (Teutonic; Norse)
Sif is the wife of the thunder god, Thor. Her golden hair, cut off by Loki, was replaced by hair spun from gold by the dwarfs. She is the mother of Lorride and a daughter, Thrud. Sif is the owner of the jewel-dropping ring, Draupnir. *See also* Iarnsaxa; Sibyl; Thor; Thrud.

Sig-Tyr (Teutonic) *see* Tyr.

Sige (A) (Teutonic) *see* Sigi.

Sige (B) (Sumer) *see* Zi

Sigfadir (Teutonic) *see* Odin.

Siggeir (Norse; Teutonic)
Siggeir is possibly a lord of darkness. He is the husband of Signy, who is the daughter of Volsung. *See also* Sigmund; Signy; Sinfiolti.

Sigi (Norse; Teutonic)
Also known as: *Sige.*
Deified mortal. King of Franconia. Sigi is one of the sons of Odin. He is the father of Rerir and grandfather of Volsung. He is usually depicted as a wolf. *See also* Odin; Volsung; Zi (Babylon).

Sigidi (Africa) *see* Eshu.

Sigird (Teutonic) *see* Sigurd.

Sigmund (Norse; Teutonic)
Sun hero. Sigmund is the eldest of the ten sons of Volsung and Liod. With his twin sister Signy they were the parents of Sinfiotli (Sinfjotli). Sigmund's first wife Borghild murdered Sinfiotli. His second wife Hiordis is the mother of Sigurd. Sigmund furnished swords to the fallen warriors in Valhalla. He, alone, was able to pull Gram, the magic sword, from the oak tree where Odin had thrust it. Siggeir, the husband of Sigmund's sister Signy, was so jealous of Sigmund's ownership of the Gram the sword that he had all the Volsungs slain. Only Sigmund escaped and hid in a cave. After a long series of events Sigmund

www.ebook3000.com

1. Stand, feet together. Put you hands down, parallel to the ground. Expand your hands very far away and your mind very far away smiling into the ground. Continue expanding your hands, feet and your mind very far away beyond the earth below. Go down through the galaxy, way beyond to the primordial force. It's just like you are extending all the way to the primordial force before 30 million years ago.
2. Push, moving the hands forward six inches only.
3. Pull, moving the hands back by the sides. Think about your Tan Tien – Chi coming to the primordial force in your Tan Tien. Smile to your Tan Tien, dark, deep and vast.
4. Push: touch the primordial force in the universe.



A. ***B.*** ***C.***

Fig. 3.27 A. *Be aware of the universe in front.*
B. *Expand your hands very big and long to the universe in front.*
C. *Hold the fire ball to activate the Tan Tien Fire.*

5. Pull back to your Tan Tien the dark primordial forces with your hands.

Push and pull: It's just like you go to an empty space – vast. Then you come back to your Tan Tien – also empty, just like the primordial condition before anything existed. That is where all the forces come from. Push and pull 3 – 9 times.

Front Direction and Tan Tien Fire

Next, be aware of the front direction; a huge fireball appears in front of you.

and Sinfiotli avenged the deaths of the Volsungs, but Signy perished in the flames that killed Siggeir. *See* also Arthur; Odin; Signy; Volsung; Volsung Saga.

Sigmund and Sinfjotli (Teutonic) *see* Odin.

Signy (Norse; Teutonic)
Dawn goddess. She is the only daughter of Volsung and Liod. Her brother, Sigmund, is the eldest of ten brothers. With Sigmund she became the mother of Sinfiotli. Signy and her son killed Siggeir (her former husband) to avenge the death of Volsung. *See also* Sigmund; Volsung.

Sigoo (Arawak People, New Guinea)
Sigoo took the animals and birds to the high mountains so that they could survive the Great Flood.

Sigrdrifa (Teutonic) *see* Brynhild.

Sigrun (Teutonic)
Also known as: *Kara.*
She is the daughter of Hogni. Sigrun was reincarnated as Kara, who is one of the Valkyries (q.v.).

Sigtyr (Teutonic) *see* Odin.

Sigu (Arawak People, New Guinea)
Ruler of the animals. *See also* Makonaima.

Siguna (Teutonic) *see* Sigyn.

Sigurd (Norse; Teutonic)
Also known as: *Siegfried, Sigird.*
He is the handsome hero of the Volsunga saga. He was born after his father Sigmund's death. His mother, Sigmund's second wife, was Hiordis. Sigurd, encouraged by Regin, killed Fafnir so he could have the treasures stolen from Andarvi. Sigurd was in love with a Valkyrie woman, Brynhild. He went to Giuki's kingdom, the land of the Nibelungs. Grimhild, the wife of Giuki, gave Sigurd a magic love potion. He completely forgot his longing for Brynhild and fell in love with Gudrun, the daughter of Giuki and Grimhild, whom he married. Later, Sigurd went to Brynhild and wooed her for his brother-in-law Gunnar. Later still, Brynhild, understandably jealous, played a role in having Sigurd murdered. *See also* Andarvi; Fafnir; Sigmund.

Sigyn (Norse; Teutonic)
Also known as: *Siguna.*
Earth goddess. Sigyn sits by her husband Loki's side collecting the poison that drips on his face. This is his punishment for misdeeds. She will stay with him until Ragnarok. Sigyn is the mother of Narve and Vali. *See also* Loki; Narve; Ragnarok; Vali.

Sigyu (Teutonic) *see* Loki.

Sikhin (India) *see* Manushi-Buddhas.

Silappadikaram (Tamil People, India)
Bala-Rama is worshipped under this name by the Tamil people. His spouse is the goddess of victory, Korraval. *See also* Bala-Rama.

Silas (Roman) *see* Silvanus.

Silenus *Seilenos, Seilenoi, Selenus* (Greek)
Also known as: *Seilenus* (plural), *Sileni* (plural).
King of Nysa. A jovial old deity, Silenus, a talented musician, has the gift of prophecy. He is a companion, teacher and protector of Dionysus. He also appears as a guardian of the drunken Bacchus. Silenus is the son of either the shepherd god Pan, or Hermes, the messenger of the gods, or the earth mother goddess, Gaea, and possibly the father of the Centaur Pholus by an ash nymph. Silenus killed the monster Enceladus during the war against the Giants. Woodland gods known as Sileni gave king Midas the "golden touch." Silenus is depicted as a burly intoxicated old man riding an ass or with the ears of an ass. The Sileni are often confused with the Satyrs. Both were represented as animals, either horses or goats. *See also* Bacchus; Enceladus; Hephaistos; Midas; Satyrs.

Silik-mulu-khi (Akkadian)
The god of light and protector of mortals, Silik-mulu-khi is the son of Ea. *See also* Ea.

Silili (Babylon, Chaldea)
The Divine Mare; she is the mother of all horses.

Silvanus *Sylvanus* (Roman)
Also known as: *Callirius* (Woodland King), *Gradivus, Quirinus, Silas, Sylvan.*
Agricultural god. Silvanus, the protector of farmers in the Narbonnaise (southern Gaul) area, is affiliated with the ancient earth goddess Aeracura and was once thought of as a god of war. One of his consorts was the Celtic goddess Nantosuelta. His consort Rhea-Silvia is a priestess of Vesta. Their offspring, the Sabines, are also called Quires. Silvanus is depicted with a scythe or a mallet with his foot resting on a cask. It is thought that his animal is the stag. He is the same as the Celtic hammer or thunder god Sucellos. He is also identified with the vegetation god, Sylvain. He is sometimes identified with Mars and sometimes with Pan. *See also* Aeracura; Cernunnos; Nantosuelta; Sucellos; Vesta.

Simbi (Haitian)
Also known as: *Simbi en Deux Eaux.*
God of fresh water, rain and magicians. He is shown in snake form.

Simbi en Deux Eaux (Haitian) *see* Simbi.

Simhanadamanjusri (India) *see* Manjusri.

Simharatha (India) *see* Durga.

Simhika (India)
She is one of Daksha's daughters and the mother of Rahu. *See also* Daksha; Rahu.

Simoeis (Greek)
He is the son of Oceanus and Tethys and the father of Astyoche and Hieromneme. *See also* Astyoche.

Simurgh (Persia)
Also known as: *Garuda* (India), *Saena.*
Simurgh is the vulture who saved Zal, the father of Rustam. He gave Zal one of his feathers and told him to throw it into a fire whenever he needed help. Compare Simurgh to Garuda (India). *See also* Rustam; Sam.

Sin *Sinu* (Sumer, Babylon, Akkadian)
Also known as: *Nanna, Nannar.*

Moon god. Sin, the early god of the moon, is the son of Enlil and husband of Ningal, father of Nusku. He has the reputation of being a wise god who shared his wisdom with other deities every month. Marduk placed Sin in charge of marking monthly time by his waxing and waning. With his light, his enemies, the evil beings, could be watched. When the Utukku (spirits) with Ishtar and Shamash extinguished his light, Marduk came to the rescue and battled the attackers. He was successful in bringing back the light from the eclipse. Sin is known as Nanna in Sumer, where he was worshiped in the form of an elderly man. His symbol is a crescent. He is also believed to be the father of Nusku. *See also* Enlil; Ishtar; Marduk; Nanna; Ningal.

Sin-Nanna (Babylon) God of the Moon. *See also* Sin.

Sina (Polynesia) *see* Ina.

Sindre (Teutonic) *see* Sindri.

Sindri (Norse; Teutonic)
Also known as: *Sindre.*

Master smith. The dwarf Sindri resides in his palace located in a hall in the Nida mountains. He and his brother Brokk and perhaps others are known as the Sons of Ivaldi. The mischievous Loki had cut off all of Thor's faithful wife Sif's golden hair. Enraged, Thor said he was going to crush Loki to death. Loki, a trickster, was able to talk his way out of the situation by promising to have hair for Sif made of gold that would grow like her own hair. He went to the Sons of Ivaldi. They fufilled Loki's promise and at the same time fashioned the ship Skidbladnir and the magic spear, Gungir. Loki put his head on the block and made a wager with Brokk that Sindri would not be able to fashion three other items as precious as the hair, ship and spear. Sindri and Brokk set about their task. Sindri placed a hog in the forge and instructed Brokk to blow the bellows without stopping until he returned. Meanwhile, a pesky fly kept annoying Brokk. He ignored it even when it settled on his neck. When he lifted the hog from the forge it had turned into a boar with golden thistles. The boar came to be known as Gullin-Bursti. He kept on working. When Sindri returned he lifted the magic gold ring Draupnir from the forge. Next Sindri laid iron in the forge and instructed Brokk to keep the bellows blowing or the work would be ruined. The pesky fly was still flitting around. This time it landed between Brokk's eyes and stung him. It was so bad that blood poured down his face and blinded him. At that point, Sindri returned, reached into the forge and took out Mjollnir the magic hammer. He sent Brokk off go to Asgard to collect the payment of Loki's head to settle the wager. Settled in their places of judgment, the Aesir decided that Odin, Thor and Frey were to judge between Loki and Brokk. Loki gave Odin the spear, Thor the golden hair, and Frey the magic ship. Brokk gave Odin the magic ring, Frey the golden boar, and Thor the magic hammer. The Aesir decided that Brokk had won the wager. Loki wanted to reclaim his head, but Brokk would not hear of it. Loki, wearing his magic shoes, took giant steps over land and sea. Brokk asked Thor to assist him. He did and Loki was apprehended. The dwarf was ready to chop off Loki's head when Loki said the wager was for his head only and not his neck. Not to be thwarted, Brokk sewed together Loki's lips. The name Sindri is also the hall with the red roof in the world to come after Ragnarok. *See also* Dvalin; Loki; Odin; Ragnarok; Sif; Svart-alfa-heim; Thor.

Sinfiotli (Norse; Teutonic)
Also known as: *Sinfjotle, Sinfjotli.*

A werewolf. He is the son of Sigmund and his sister Signy, and half-brother of Siggeir. Sigmund and Sinfiotli in werewolf guise murdered people and when there were not any candidates available, they attacked one another. Sinfiotli was killed, but was brought back to life and together they avenged the death of the Volsungs. Sinfiotli also helped his mother murder Siggeir. *See also* Siggeir; Sigmund; Signy; Volsung.

Sinfjotle (Teutonic) *see* Sinfiotli.

Sinfjotli (Teutonic) *see* Sinfiotli.

Sinfjotli and Sigmund (Teutonic) *see* Odin.

Singhini (Nepal) Female guardian demon.

Sinilau (Polynesia) *see* Tinirau.

Sinivali (Hindu; India)

Goddess of fecundity and easy birth. Sinivali is thought to be one of Vishnu's spouses. *See also* Dharti Mai; Vishnu.

Sinon (Greek)

Sinon, the son of Sisyphus and Anticleia (the daughter of Autolycus and wife of Laertes), was a Greek spy during the Trojan War. He could be the brother of Odysseus. *See also* Sisyphus.

Sinope (Greek)

Virgin deity. Sinope, the daughter of Asopus, was whisked off by Zeus, who promised to grant her any wish if she would submit to his ardent advances. Her wish was to remain a virgin and according to most myths, her wish was granted despite the pursuits of Apollo, the river-god Halys, and Zeus. She lived on an island, happy with her solitude. Diodorus Siculus claimed that Apollo finally deflowered her and that she became the mother of Syrus. *See also* Amentet; Apollo; Asopus.

Sintians, The (Greek)

In some myths, Hephaistos was raised by the Sintians on the island of Lemnos. *See also* Hephaistos.

Sinu (Sumer) *see* Sin.

Sio Calako (Hopi People, North America) A giant.

Sio Humis (Hopi People, North America) The Rain Spirit.

Siokhi (India) *see* Manushi-Buddhas.

Sioux People — Creation Legend *see* Wakataka.

Sipendarmidh (Persia) *see* Spenta Armaiti.

Sippara (Egypt) *see* Aah.

Sipylus (Greek) *see* Aedon.

Sirat (Islamic)

The Sirat is the bridge that spans hell, known as Daru el-Bawar. It is similar to the Zoroastrian Chinvat Bridge (q.v.).

Sirdu (Chaldean) *see* Aa.

www.ebook3000.com

Sirens *Seiren, Syren* (Greek)

The Sirens are evil nymphs who lived on various islands off the coast of southern Italy. The islands named are Cape Pelorus, the Isle of Anthemusa, Capri, and the Siren Islands. They are the daughters of the river god Achelous and the muse of tragedy, Melpomene or Terpsichore, the muse of dance. Other writers name Achelous the father and Calliope, the muse of poetry, or Sterope (also known as Asterope) as their mother. They have also been called the daughters of the ancient sea god Phorkos and the sisters of the demon Skulla. Homer named two Sirens but other writers say there were three, four or eight. Their names are given variously as Leucosia, Ligeia and Parthenope, or Aglaopheme (meaning brilliant voice), Aglaope, Molpe (meaning song), and Thelxiepeia (meaning enchanting words), or Himeropa and Peisinoe (Pisinoe), meaning the persuasive. The Sirens once witnessed Persephone being raped by Hades. Intent upon revenge, they were given wings by Zeus. In another legend, it is related that Aphrodite punished them with strange bodies because they never fell in love. Their greatest love was for their perceived talent. They challenged the Muses to a musical competition and lost. The Muses' crowning glory is the tiaras they made from the Siren's feathers. Their melodious voices enchanted sailors and lured them to their deaths. The only mortals known to survive the dangerous route past their island was Jason and the crew of the Argos, who had taken great precautions, and at another time, Odysseus. When Odysseus sailed by their island unscathed, the Sirens felt their loss of power and flung themselves to their deaths. Represented as birds with wings and the head and breasts of a woman. Compare the Sirens to the Russian Rusalki and Russalka. *See also* Achelous; Aello; Calydonian Bear Hunt; Fates; Gorgons; Graiae; Harpies; Hylas; Jason; Lamia; Muses; Odysseus; Orpheus; Scylla.

Siris (Assyro-Babylonia) *see* Ea; Zu.

Sirius (Egypt)

Also known as: *Sirius the Dog-star, Sothis.*

Sirius, known as the brightest star, marked the beginning of the sacred Egyptian year. The Egyptians called it Sothis and considered it the star of Isis. Visible just before sunrise about the time of the summer solstice, Sirius signified the beginning of the sacred Egyptian year. In female form, Sothis represented the goddess of love and life, who comes to wake her lover from the dead. *See also* Aktar; Hapto-iringa; Isis; Orion; Tishtrya; Sothis.

Sirona *Dirona* (Gaul, Celtic) *see* Borvo.

Sirrida (Chaldean) *see* Aa.

Sirrush (Sumer)

Sirrus, who has four feet and long legs with talons on his hind paws, is a dragon sacred to Marduk. The long neck of his scaly body ends in a large-eyed snake-head with straight vertical horns and a split tongue darting forward.

Sirsir (Babylonia) *see* Marduk.

Sirsootee (India) *see* Devi.

Sisa (Ashanti People, Africa) *see* Kla.

Sistrum (Egypt)

Sacred object. The Sistrum is a rattle used in the worship of Isis, Hathor, and Min. It is usually depicted as having a handle with the top shaped like the head of Hathor with cow's ears, and a horseshoe-shaped metal frame with loose cross-bars that rattle when shaken. Sometimes there were metal disks along the strings. The sound frightened away demons. *See also* Ihi.

Sisupala *Shishupala* (Hindu; India)

Also known as: *Ravana.*

Sisupala, the King of Chedi, is the third avatar of the demon Ravana. When he was an infant, Krishna was visiting and noticed his deformities. He took the child on his knees, and his third eye and two extra arms disappeared. Sisupala's hatred of Krishna grew into an obsession and he could barely sleep without thinking about him. In later years, he was engaged to Rukmini, the daughter of the King of Vidarbha, Bhishmaka. The engagement and impending wedding were arranged by her brother Rukma, who was a friend of the evil Kansa, who had been killed by Krishna. Rukmini, an avatar of the goddess Lakshmi, was in love with Krishna. She wrote to him and begged to be rescued from the ceremony. He arrived on the scene and pulled her into his chariot and they sped away pursued by Sisupala, Jara-Sandha and Rukma. Rukma tried to kill Krishna, but was apprehended by Krishna's half-brother Bala-Rama. Rukmini interceded for him and her brother was spared. Krishna ensconced her in his celestial dwelling place, Dvarka, and in time they produced ten sons, including Pradyumna, and a daughter, Charumati. Sisupala, who never forgave Krishna for interfering with his relationship with Rukmini, harassed him whenever he had the opportunity. Krishna tolerated him because he had promised Sisupala's mother that he would forgive him a hundred wrongs. On the hundred and first incident, Krishna threw Sudarsana, his magic discus, at him and split him in half. His soul burst into flame, bowed before Krishna and was absorbed into his feet. The discus Sudarsana is formed like a wheel with an extremely sharp edge. It lives in the sky and by rotation comes to Vishnu's hand. It emits fire sparks and lightning and can burn down cities. Vishnu and his avatars used it in battle to slay demons. *See also* Bala-Rama; Jara-Sandha; Krishna; Lakshmi; Pradyuma; Ravana.

Sisyphos (Greek) *see* Sisyphus.

Sisyphus *Sisyphos* (Greek)

The underworld deity Sisyphus is the son of Aeolus and Enarete. He became the king of Corinth and married the Pleiad Merope and became the father of Thersander, Glaucus, known as Glaucus of Corinth, Halmus (Almus) the king of Boeotian Orchomenus, and Ornytion. Sisyphus discovered that the renowned thief Autolycus was responsible for stealing his cattle. In retribution, he seduced Autolycus' daughter Anticleia, who was married to Laertes, and he became the father of Sinon and possibly Odysseus. Sisyphus and his brother Salmoneus despised one another and Sisyphus wanted him killed. He consulted an oracle and following the advice he had an affair with his brother's daughter, Tyro. They had two sons but when she learned about the oracle, she felt that Sisyphus hated his brother more then he loved her, so she murdered the children. Sisyphus discovered the dead bodies and falsely accused Salomoneus of the deaths and had him expelled from Thessaly. It is felt that Sisyphus committed a heinous act at this time and was condemned to Hades to roll a huge rock uphill which, upon reaching the top, always rolled to the bottom. Some think that Zeus, angry with Sisyphus for divulging that he had abducted Aegina, the daughter of Asopus, ordered Hades to punish him. When Sisyphus reached Tartarus, he managed to manipulate Hades into allowing him to return to the world, and promised that he would return. He broke his promise and had to be dragged back by Hermes. Sisyphus, known as a cunning and avaricious man, also had another side. He discovered the dead body of his nephew Melicertes on the Isthmus of Corinth, which had been brought ashore by a dolphin. He buried him at that location and founded the Isthmian games in his honor. His son Glaucus was murdered by Pelops and his ghost was known as Myrtilus. For the genealogy of Sisyphus, *see* Aeolus (A). Sisyphus is similar to Ixion. For another explanation for his severe punishment in Hades, *see* Aegina. Compare his punishment to that of Ixion and Tantalus. *See also* Anticleia (A); Asopus; Autolycus (A); Bellerophon; Canace; Erinyes; Hades; Pelops; Salomoneus.

Sita *Seeta* (Hindu; India)

Also known as: *Bhumija, Lakshmi.*

Sita is described in some renditions as self-formed as a seed furrow in the soil. In this form she is known as Bhumija and is said to have sprung from the earth where she was discovered by King Videha while he was ploughing. Other legends proclaim that she is either the daughter of the earth Bhumi or the earth goddess and goddess of wealth Vasundhara and sister of her brother Naraka. A beautiful sister, Urmila, the daughter of Janaka, is also mentioned. In another version, she is the daughter of Savita who personifies the sun and the lover of Soma the moon. Sita is a fertility goddess and goddess of agriculture. She is an incarnation of Lakshmi who follows Lakshmi's incarnation as Dharani. Sita was extremely beautiful and attracted many suitors. A competition was held to see who would have the privilege of being her mate. The winner of the event had to bend the bow that Shiva had been given by Janaka. Rama, Vishnu's seventh avatar, was the victor as was predestined. Sita followed him into the forest when he was exiled. One day, while Rama was hunting, Sita was abducted by the demon Ravana and carried off to Sri Lanka. He tried to seduce her but she resisted his overtures. A battle to gain her back developed and she was rescued by Rama, his devoted brother Lakshmana and Hanuman and his troop of monkeys. Rama would not believe that Sita did not have sex with Ravana. Finally, in desperation to prove herself, she threw herself onto a burning pyre. The god of fire Agni knew that she was pure and did not burn her. Still her spouse did not believe her. He insisted that she go off to live in the forest even though he knew that she was carrying his child. She lived with the sage Valmika and gave birth to twin sons, Kusha and Lava. When the children were about fifteen Rama first saw them and knew instantly that they were his children. He wanted his family back, but Sita, who was heartbroken, returned to the womb of the earth, her birth place. Sita symbolizes the resourceful earth and the pure and faithful spouse. *See also* Agastya; Bharata (A); Bhu-Devi; Bhumi (regarding Bhumija); Hanuman; Kusha; Lakshmi; Rama; Ravana; Sampati; Soma; Sugriva; Vasundara.

Sitala *Shitala, Sitla* (Hindu; India)

Sitala is the black goddess of smallpox. She was thrown out of Shiva's paradise, Kailasa, for throwing her gold necklace at the great god, which gave him ulcers. Kicked by a cow, she cursed all cows to lives of heavy labor. Her curse gave all cows one teat for the calf, one for the gods, one for the king, and one for the owner. It was further decreed that the animal's hide would be used for shoes and drums. She also cursed the mango tree, causing it to be devoured by insects and used for burning the dead. Sitala, who dispenses and cures smallpox, is invoked for protection against the disease. She has eight faces studded with eyes and teeth like boar's tusks. Her hair is made of peacock feathers and two elephants hang from her ears. In her hands are a sword, dagger, trident, cup, wheel, rope and an ape. Her clothes are serpents. She is also depicted wearing red robes, carrying reeds to chastise her victims and riding an ass. The milk from an ass is thought to be a cure for smallpox. Sitala is worshiped in spring and summer and during times of illness. During this time, the patient is surrounded by neem leaves. She is sometimes identified with Devi in her aspects of Durga and Kali (q.v.). *See also* Hariti; Kishimojin (Japan); Shiva.

Sitamahakala (India) *see* Mahakala.

Sitatapatraparajita (Tibet) *see* Avalokitesvara; Gdug-dkar-chan-ma; Tara (B).

Sitatara (India) *see* Tara (B).

Sith (Teutonic)

Harvest deity. One of the wives of Orvandel. Mother of Ull and stepmother of Svipdag. Legend says she prepared the food of wisdom from the fat of three serpents.

Sitla (India) *see* Sitala.

Siton (Phoenician)

An alternate name for Dagon. *See also* Dagon (B).

Sitragupta (India) Son of Indra. *See also* Indra.

Sittung (Teutonic) *see* Fjalar.

Situr (Sumerian) *see* Ninsun.

Siudleratuin (Inuit, Eskimo) Spirits of the dead.

Siva (India) *see* Shiva.

Siyamek (Persian) *see* Hushang; Takhmoruw.

Sjofn (Teutonic)

She is a messenger goddess who inspires human passion. Sjofn is also an attendant of Frigga.

Skad (Teutonic) *see* Odin.

Skade (Teutonic) *see* Skadi.

Skadhi (Teutonic) *see* Skadi.

Skadi (Norse; Teutonic)

Also known as: *Skade, Skadhi, Skathi.*

Goddess of winter. Goddess of the chase (possibly). Skadi is the daughter of Hrim-thurs or Thiassi. Because of the death of Thiassi, the gods allowed her to choose a husband from the gods. Blindfolded, she could only see the gods' feet. She wanted to be the wife of Balder but her blind choice was Niord. For a time, she spent part of the year with Niord and part of the year

www.ebook3000.com

in her wintery home. Later, the two separated and she became the wife of Odin. They had a son, Saeming, who became the first king of Norway. Later still, she married the winter god, Uller. Some say Freyja was her daughter. Skadi was the one who fastened a serpent over Loki's head so venom dripped on his face, but Loki's wife Sigyn held a cup to catch the venom. When she had to take a moment to empty the cup, the venom caused Loki such pain that his agonized movements caused earthquakes. Skadi wears silvery armor, a short white hunting dress, white fur leggings, broad snowshoes and holds a spear and arrows. She is usually accompanied by wolves or dogs. *See also* Balder; Loki; Njord; Sigyn.

Skambha (Hindu; India)
"The Supporter." Skambha is an axis deity who sustains the worlds. He is sometimes identified with Brahma. Skambha is also an epithet of Agni, Indra and Soma.

Skanda *Scanda* (Hindu; India)
Skanda is another name for the war god Karttikeya (q.v.). *See also* Bana; Devi; Durga; Kumara; Nandisha; Visvakarma.

Skandaganani (India) *see* Parvati.

Skandas, The Five (Buddhist)
The five cosmic elements. *See also* Dhyani Buddhas.

Skathi (Teutonic) *see* Skadi.

Skidbladner (Teutonic) *see* Skidbladnir.

Skidbladnir *Skidbladner* (Norse; Teutonic)
Skidbladnir is Frey's ship. It can be folded like a napkin and put into a pocket. It was presented to Frey by Loki. The ship was probably fashioned by a dwarf, either Brokk, Ivaldi or Sindri.

Skidskegg (Teutonic) *see* Odin.

Skin-Faxi (Norse; Teutonic)
Also known as: *Skinfaxe, Skinfaxi.*
Skin-Faxi is the steed who draws the chariot of Dag through the heavens. His name means "shining mane." *See also* Dag; Hrim Faxi.

Skinfaxi (Teutonic) *see* Skin-faxi.

Skiold (Teutonic) *see* Odin.

Skirner (Teutonic) *see* Skirnir.

Skirnir *Skirner* (Norse; Teutonic)
Also known as: *Shining.*
Skirnir is the messenger of Freyr who won the giantess Gerda for him. He was awarded Frey's magic sword.

Skjold (Teutonic) *see* Thor.

Skogsfru (Scandinavian)
A woodswoman, Skogsfru is considered unlucky to hunters because she lures them away from their fires in the forests.

Skoll (Norse; Teutonic)
Skoll, a giant wolf, may be a god of eclipses and sunsets. Skoll pursues the sun daily, and will swallow it before Ragnarok. His brother, the more forbidding of the two, is the giant wolf Hati. He pursues the moon. Skoll is thought by some to be the son of Hrodvitnir. Others say he is the son of the wolf Fenrir. Skoll and Hati are known as the Varns. *See also* Fenrir; Hati; Ragnarok.

Skoyo *Soyoko* (Hopi, Sia People, North America)
The Devouring Monsters. The Hopi Indians call them Soyoko.

Skrymer (Teutonic) *see* Skrymir.

Skrymir *Skrymer* (Norse; Teutonic)
Also known as: *Utgard-Loke, Utgard-Loki.*
Giant. Thor, Loki and Thialfi were traveling through the forest en route to Utgard, the land of the giants. They met the giant Skrymir who joined them. Over the days as they moved along, the giant placed them in strange conditions. At one point, angry and frustrated, Thor attempted to kill him with his magic hammer Mjollnir, but could not. The giant would not die. Later they discovered that Skrymir was Utgard-Loki who is Loki in disguise using his magic powers. *See also* Loki.

Skuld (Teutonic) *see* Norns.

Skulla (Greek) *see* Sirens.

Sky (Greek) *see* Chaos; Gaea.

Skyamsen (Tlingit) Thunderbird.

Skyites (Greek) *see* Dionysus.

Skylla (Greek) *see* Scylla.

Sleipner (Teutonic) *see* Sleipner.

Sleipnir (Norse; Teutonic)
Also known as: *Sleipner.*
Odin's horse. Sleipnir is the offspring of Svadilfari and the trickster of Asgard, Loki, who had taken the shape of a mare to consummate the union. The eight-footed Sleipnir has supernatural strength. When Balder died, Hermod (Odin's son) rode Sleipnir to Hel to try to gain his release. *See* Asgard; Balder; Hel; Loki; Odin; Runes.

Slid (Norse; Teutonic)
Deified river. Slid is one of the rivers or streams coming from Hel. It consists of nothing but water and naked swords or daggers and spears. *See also* Hel; Hvergeilmir.

Slidrugtanni (Teutonic) *see* Gullin-Bursti.

Slooa-Shee (Irish) *see* Sheehogue.

Smaj (Serbia)
Protector of the Serbian nation. These divinities resemble winged male mortals and have been known to shoot fire while flying.

Smara (India) "Memory." *See also* Kama (A).

Smashana (India)
Smashana is the cemetery where dead bodies are burnt for purification. *See also* Shiva.

Smok (Slavonic) *see* Zmek.

Smyra (Greek) *see* Myrra.

Smyrna (Greek) *see* Adonis; Myrrha.

Snana-yantra (India) Festival for Jagannath (q.v.).

Snatchers, The (Greek) *see* Harpies.

Snor (Teutonic) *see* Heimdall

Snorta (Teutonic) *see* Snotra.

Snorter and Blower (China) *see* Heng and Ha; Men Shen.

Snorter and Puffer (China) *see* Heng and Ha; Men Shen.

Snotra (Norse; Teutonic)
Also known as: *Snorta.*
She is the goddess of virtue and knowledge and Frigga's attendant. *See also* Frigga.

So (Ewe People, Dahomey, Africa) *see* Khebieso.

Sobek (Egypt) *see* Neith; Sebek.

Sobk (Egypt) *see* Sebek.

Sochos (Egypt) *see* Sebek.

Sogamozo (Colombia) *see* Ramiriqui.

Sogbo (Dahomey People, Africa)
Sogbo, also known as Mahu, the earth and fertility goddess, is the mother of the god, Agbe, whom she placed in charge of world affairs. *See also* Agbe; Mahu.

Sojobo (Japan) *see* Tengu (The).

Sois (Greek)
Sois is the wife of Triopas and the mother of Pelasgus. *See also* Pelasgus (D).

Sokar *Sokari, Sokaris* (Egypt) *see* Seker.

Sokare (Egypt) *see* Seker.

Sokari *Seker* (Egypt) *see* Osiris.

Sokaris (Egypt) *see* Seker.

Sokkvabek (Teutonic) *see* Sokvabek.

Soko-no-kuni (Japan)
"Deep Land." Another name for Yomi, the underworld realm of the dead. *See also* Yomi.

Sokotsu-kuni (Japan)
"Bottom Land." Another name for Yomi, the underworld realm of the dead. *See also* Yomi.

Sokushikki (Japan)
Sokushikki is a demon who is associated with the protector of monasteries, Ida-Ten. *See also* Ida-Ten.

Sokvabek *Sokkvabek* (Norse; Teutonic)
The home of the gods. Odin and Saga met at Sokvabek daily to drink the waters of the river. *See also* Breidablik; Gladsheim; Hlidskjalf; Odin; Saga.

Sol (A) (Roman)
Also known as: *Helius* (Greek).
Sol is the Roman god of the sun, identified with the Greek god, Helius. *See also* Helius; Sol (B).

Sol (B) (Norse; Teutonic)
Also known as: *Nat, Sun.*
Sol and Mani are the giant children of Mundilfari. He named Mani after the moon, and Sol after the sun. (The orbs had been newly created.) Sol, the sun maid, is the spouse of Glaur (glow). Sol and Mani were transferred to the sky where they daily accompany their horses through the heavenly course. Sol is protected from the sun's hot rays by the magic cooling shield Svalin. *See* Aarvak; Idun; Nott, Sol (A).

Solal (Caroline Islands)
Ancient deity. Supreme being. Solal, the oldest of gods, planted a tree on the rock from which the world is made. He climbed the tree, and halfway up he created earth, then he climbed to the top where he created the sky for the dwelling place of his brother, Aluelop.

Solang (Micronesia)
God of canoe builders or carpenters. He appeared to Longorik in the shape of a bird and with the assistance of the ants, helped him build the first canoe. He is associated with Alulei (q.v.).

Solomon (Semite) *see* Chemosh.

Solymi (Greek) *see* Bellerophon.

Solymians (Greek)
The Solymians are Lycian warriors who fought Bellerophon and lost. *See also* Bellerophon.

Soma (Hindu, Vedic; India; Persia)
Also known as: *Amrit* (Water of Immortality), *Amrita, Chandra, Haoma* (Persian), *Indu* (The Moon), *Oshadhi-pati* (Supervisor of Herbs), *Skambha* (Support), *Soma Pavamana* (Self-Purifying Soma), *Syenabhrita* (Eagle-borne).
In the Vedic texts, Soma is coupled with Agni. With the rise of Hinduism, and the advent of the deities Vishnu, Shiva, Shakti and later, Krishna, the stature of Soma and Agni fell to a lower rung. The deity Soma is a moon god, a god of the flowing waters, a god of inspiration, ecstasy and riches. In later times, he became a god of herbs and healing. Soma means "The Joyous One." Soma, the beverage of the gods, is a sacred plant and the juice extracted from it gives strength, wisdom, and immortality to those who drink it. The moon is said to contain this celestial nectar, which reputedly also grew on earth. In one legend, the archer Krsanu shot at the eagle that carried Soma. A feather from the bird fell to earth and created the growth of the plant; Soma the god is the personification of soma juice. He took various shapes, and shared many of Indra's characteristics. Many myths surround the origins of soma the golden nectar and Soma the deity. Some feel that Soma is Indra and that it was Indra who discovered soma in the Himalayas; yet other versions claim the goddess Sarasvati found Soma in the Himalayas and brought it to the other deities. Other myths are Indra first tasted soma from his mother's breast; the goddess of waters Vach, who was one of Indra's wives, gave soma to the half-bird, half-man, celestial spirits known as the Gandharvas. Later, they were charged with caring for the plant. Other vari-

www.ebook3000.com

ations are that Soma is the son of Parjanya; Soma is the son of the sage Atri (the son of Brahma) and Anasuya; Soma married the Vedic maiden of the sun, Surya. He had twenty-seven wives, who are the daughters of Daksha. When he ignored all the women except Rohini, his father-in-law placed a curse on him. Soma was afflicted with leprosy, and when he lost strength, so did all earthly creatures. When Daksha lifted the curse, he declared that Soma's realm, the moon, would wax and wane each month. Rohini (Red Cow or Red Deer) is also known as the wife of the moon god Chandra. A goddess named Diksha, about whom little is known, is also mentioned as a wife of Soma. The etymology of her name is roughly, "solemn preparation." In later times Soma was known as the embodiment of the moon. Later still, he became known as a god of herbs and healing. It is thought that medicinal herbs derive their healing properties from the ambrosia, Soma. Without leaves or branches, the beverage was produced by crushing the stem. The yellow juice of the plant and the sound it made as it passed through the sieve represent thunder and lightning. The resulting liquid, described as being the color of golden nectar, symbolizes the rain, or in other interpretations, semen. The beverage also symbolizes liberation, inspiration, and immortal life. Soma the plant had a real and a mythical existence. It was used in ritual ceremonies. Soma the deity has been described as a celestial bull, a bird, and a giant of the waters. He is also depicted as a youth, brown, active and wise, adorned in gold. The twenty-seven daughters of Daksha represent the twenty-seven lunar stations. Soma's symbol is a silver crescent. He rides through the heaven in Indra's three-wheeled chariot pulled by ten brilliant white horses, the steeds of Vayu (the wind). His celestial bow, later owned by Arjuna, is named Gandiva. Soma and fire were the two major *Rig-Veda* sacrifices. The goddess Amritika, a celestial being, is mentioned as the goddess who poured soma, the intoxicant, love potion, or hallucinogen. She represents the feminine as a vehicle of transformation. The moon, known as Shasha, means "hare," which explains why the hare is considered by some to be a moon deity. Soma the beverage is similar to the Indo-Iranian Haoma, the ambrosia of the Greeks, and Manna of the Israelites. Varuna is referred to as the keeper of Soma. His daughter by Varunari is Varuni, the goddess of spirituous liquor. Soma is comparable to the Greek Dionysus (q.v.). Soma and the Sumerian deity Tammuz are said to be counterparts as each is associated with the waning and waxing of the moon. The renowned imbibers of Soma are Indra and Agni (q.v.). Sometimes the goddess Lakshmi (q.v.) assists Soma. Compare Soma to the Parijata Tree kept by Indrani. For other healing deities, *see* Asvins; Rudra. *See also* Arjuna; Brihaspati; Chandra; Daksha; Gandharvas; Garuda; Hoama; Kurma (Vishnu's avatar as a tortoise); Loka; Lokapalas; Prithiva; Rahu; Savarbhanu; Sita; Skambha; Surya; Surya-Bia; Tara (A); Vach; Varuna; Vasus; Yama.

Soma-Loka (India) *see* Loka.

Somavati (India) Moon Goddess. *See also* Soma.

Sombol-Burkan (Buryat)
As he rested on the Primordial Ocean, Somboi-Burkan, a creator god, asked a water bird to dive to its depths. The bird returned with mud from which the god created the earth. In a variation of this myth, Sombol-Burkan created man from the same substance.

Somin-Shorai (Japan) *see* Buto (B); Fuji.

Somnus (Roman)
Also known as: *Hupnos, Hypnos* (Greek), *Hypnus* (Greek).
Roman god of sleep. Father of one thousand sons. He wears black garments covered with golden stars. A crown of poppies adorns his head. In his hand, he holds a goblet of poppy juice. Some say has wings. *See also* Erebus; Hypnos; Nox.

Somo (Buddhist) *see* Tara (A).

Son (A) (Norse; Teutonic)
Also known as: *Blood.*
Deified object. One of the jars that holds the mead of poetry brewed from Kvasir's blood. *See also* Kvasir.

Son (B) (Celtic)
Also known as: *Shony.*
Sea god. He is offered whiskey for good fishing and kelp. He is superseded by Brain-uil (St. Brendan).

Son of Self (India) *see* Agni; Tanunapat.

Son of Svarog (Slavic) "Son of the Sky." *See also* Dazbog.

Sonponno (Africa)
Also known as: *Ile-Gbigbona, Ile-Titu, Olode.*
Deity of smallpox and related diseases. He is also called Olode (Owner of the Public), Ile-Gbigbona (Hot Ground), and Ile-Titu (Cold Ground).

Sons of Mil (Irish) *see* Amergin.

Soora (India) *see* Sura (B).

Sopd (Egypt) *see* Sopdu.

Sopdu *Septu, Sopd* (Egypt)
Also known as: *Har-Sopdu.*
Earth deity. God of the frontier. Sopdu is one of the gods of the four quarters of the earth, along with Horus, Set, and Thoth. When the goddess Nut, in the form of a cow, was on her way to heaven with Ra-Tem on her back, her legs began to shake. The gods of the four quarters were called to steady her. Each god took one of her legs, and the god Shu supported her belly. In the Pyramid Texts, Sopdu is mentioned in connection with the teeth of the deceased. His link to Horus in the Middle Kingdom led to the name Har-Sopdu in the New Kingdom. He is depicted as a crouching falcon. In human form he is shown with a crown of two falcon feathers and a shemset girdle. *See also* Horus; Nut; Set; Thoth.

Soped (Egypt)
God of the roads. A hawk-headed god who protected the roadway that led out of Lower Egypt.

Sophax (Greek) *see* Antaeus.

Sophia (Gnostic) *see* Pistis Sophia.

Sophia-Prunikos (Gnostic)
One of the Aeons, Sophia-Prunikos, who personifies wisdom, is the mother of Ialdabaoth. She is similar to Ennoia. *See also* Alaghom Naom Tzentel; Barbelo; Ennoia; Pistis Sophia.

Sopt (Egypt)
Spirit of the twilight or light of dawn. As Horus-Sopt he is the light of dawn.

Soramus (Roman) Roman name for Apollo.

Soteira (Greek)
An epithet of Athena, Artemis and Persephone. *See also* Athena.

Soter (Greek) "Father and Savior of Man." An epithet of Zeus.

Sothis (Egypt)
Also known as: *Isis-Sothis, Sirius.*
Sothis is the female form, deified as a goddess, of the dog star Sirius. The name Sothis is the Greek form of the Egyptian word for Sirius. She was later associated with Isis. Sothis is depicted as a woman with a star on her head and is also portrayed as a large dog. Shown riding side-saddle on the dog, she is known as Isis-Sothis. Sothis was frequently represented among the Greeks and Romans as a cow. *See also* Isis; Sirius.

Sotshirvani (Siberia) *see* Vajrapani.

South West Wind (Greek) *see* Notus.

Soyoko *Skoyo* (Hopi, Sia People, North America)
Soyoko is the generic name for monsters. The Sia Indians call them Skoyo.

Spantaramet *Spentaramet* (Armenian, Iranian, Persian)
Also known as: *Amesha Spentas, Santaramet, Spenta Armaiti.*
A goddess of vineyards, Spantaramet is similar in aspect to the Persian Spenta Armaiti, and Dionysos of the Greeks. She was possibly known as Santaramet by the Armenians but later they used the name of Aramazd in her place. The name Santaramet was then associated with the underworld. The evil spirits who dwell in Santaramet are called Santarametakans. *See also* Amesha Spentas; Dionysos; Hades; Hell; Santaramet; Spenta Armaiti.

Sparte (Greek) *see* Acrisius; Sparti.

Sparti *Sparte* (Greek)
Also known as: *Sown-men.*
The Sparti are dragon-men who sprouted from the dragon's teeth which were planted in mother earth by Cadmus (q.v.).

Spear of Lugh, The (Celtic) *see* Tuatha De Danann.

Speio (Greek)
A Nereid, Speio is one of the fifty daughters of Nereus and Doris. *See also* Doris; Nereids; Nereus.

Spenishta (Iran)
One of the five sacred fires. It burns before Ormazd and eats but does not drink. *See also* Ahura Mazda.

Spenjaghrya (Iran)
A demon, Spenjaghrya represented winter or darkness. He was slain by Vazishta who represents lightning.

Spenta Armaiti (Zoroastrian; Persia)
Also known as: *Armaita, Armaiti, Armati, Asfandarmad, Isfenarmad, Santaramet, Sipendarmidh, Spantaramet* (Armenia), *Spendarmad* ("Bounty").
An Ameshas Spenta, she is the daughter of Ahura Mazda and sits at his left hand. Known as the guardian of the earth, and keeper of the vineyards, she is the personification of faithful obedience, religious harmony and worship. She also ensures pasture for cattle. Robbers, evil men and irreverent wives distress her. The archdemons opposed to Spenta Armaiti are Taromaiti, who personifies presumption, and Pairimaiti, who personifies crooked-mindedness. She appeared to Zoroaster visibly. In ancient Armenia, she was known as Spantaramet, the goddess of the underworld. *See also* Ahura Mazda; Ameshas Spenta; Asvins (India); Daevas; Gaya Maretan; Hell; Spantaramet; Zoroaster.

Spentaramet (Persia) *see* Spantaramet; Spenta Armaiti.

Spercheius (Greek)
River god. His parents are Oceanus and Tethys. He became the father of Menesthius by Polydora. Menesthius saved his lover, Cleostratus, from being eaten by the dragon who attacked Thespiae once a year.

Sphinx (Greek, Egypt, Asia Minor)
Also known as: *Harmachis, Harmakis, Heru-em-akbet.*
The Egyptian Sphinx is a spirit guardian of entrances. The most famous is known as Sesheps. A sphinx represents vigilance and is often depicted as a devourer. It can appear as a ram-headed lion, a hawk-headed lion and human-headed lion. The sphinx was often created from stone and shown in a crouched position, wearing the headdress of a pharaoh. The Greek Sphinx is the daughter of Typhon and Echnidna, or Orthus and Chimaera. Her siblings are the Caucasian Eagle, Cerberus, Chimaera, Crommyonian Sow, Hydra, Orthus, Nemean Lion, and an assortment of vultures. She guarded the road on the way to Thebes and asked all those who passed to solve a riddle. The riddle was "What goes on four feet, on two feet, and on three?" She killed those who failed to answer the question correctly. When Oedipus finally solved her riddle, she killed herself. The answer to the riddle is Man. The mortal as a child crawls, as an adult, walks upright and in old age is supported by a cane. The Greek Sphinx is depicted with the upper part as a female, her torso part dog, the tail of a snake, wings of a bird, and lion paws. She spoke in a human voice. Greek sphinxes are either female or androgynous and are winged. Iconographically, the sphinx is often said to be the female equivalent of the Centaur. The difference is the sphinx is depicted immobile and the centaur in movement. Sphinxes all like riddles. *See also* Cerberus; Chimaera; Eurydice (C); Sesheps; Typhon (A).

Spider Woman (Zuni People, North America) *see* Ahayuta Achi.

Spiniensis (Roman)
Agricultural deity. A god who helped clear a field of thorns.

Spinning Damsel *Weaver Damsel* (China) *see* Chin Nu.

Spirit of the Long Grass (Australia) *see* Morkul-Kua-Luan.

Spor (Slavic) The spirit of growth.

Sraddeheva (India) *see* Yama.

www.ebook3000.com

Sraddha *Shraddha* (Hindu; India)
Sraddha, the goddess of faith, is the mate of the god of justice Dharma and the mother of the god of love, Kama. Sraddha is also a sacred word meaning faith, belief or trust and a practice of giving a meal to the deceased. *See also* Dharma; Kama.

Sraddhadeva (India) God of Funeral Directors. *See also* Yama.

Sraosh (India)
Also known as: *Srosh.*
Messenger. God of obedience and devotion. A mediator or divine messenger between gods and mortals. Usually combined with Mithra and Rashnu as guardian angels. They will be judges of the otherworld. *See also* Amshaspands; Fravashis; Mithra; Rashnu; Yazatas.

Sraosha *Sros* (Pahlavi dialect); (Zoroastrianism; Persia)
With Mithra and Rashnu, Sraosha ("the obedient") greets the soul at death and presides over judgment of the soul. He conveys prayers to heaven, feeds the poor, and is the destroyer of evil. His opponents are Aeshma, the embodiment of fury, and the leader of the demons, Angra Mainyu. The guardian angel of the world, he lives on the highest peak of Mount Hariati in a self-lit house with a thousand pillars. Four horses with golden feet draw his chariot. *See also* Aeshma; Ameshas Spenta; Angra Mainyu; Chinvat Bridge; Daevas; Hariati (Mount); Mitra; Rashnu; Yazatas.

Sreca (Serbia)
The genius of good fate, Sreca is the opposite of Nesreca, the genius of evil fate. *See also* Dola; Dolya.

Sri *Shri, Shru* (Hindu; India)
Sri is the name of Lakshmi when she was incarnated as the wife of Rama, an avatar of Vishnu. In Northern India, the coconut is sacred to her. It is called Sriphala, or fruit of Sri. Her mount is a white elephant named Sri-gaja. *See also* Lakshmi; Sarasvati. She is comparable to Kishijoten, sister of Bishamon (q.v.) (Japan).

Sri Dewi (Javanese) Goddess of Rice.

Sri-gaja (India) The white elephant of Sri (q.v.)

Srin-po (Tibet) Ghouls or vampires the color of raw flesh.

Sringatpadini (India) A Yakshini (q.v.).

Srinmo (Tibet)
Female demon of death.

Sriphala (India) The sacred coconut of Sri (q.v.).

Srishok *Hadhayos* (Persia)
Mortals rode the back of this heavenly bull to pass from the central portion of earth, Khwanirath, to the surrounding six portions, the Keshvars. Srishok will be the last animal offered in sacrifice at the renovation of the world. Because of his importance, he is protected by Gopatshah, the half-man, half-ox. *See also* Vourukasha.

Sristikanta Lokeswara (Buddhist; Nepal)
An aspect of Avalokitesvara, he is depicted with one face, two arms and stands on a lotus. Amitabha appears over his head. His right hand is held in the gesture of charity (varada) and his left hand is placed near his navel. Numerous four-armed gods emanate from his body. *See also* Amitabha; Avalokitesvara; Lokeswara.

Srnkhala (India) *see* Amrtakundali.

Srosh (Persia) *see* Sraosh.

Srvara (Persia)
This horned dragon had teeth as long as an arm, eyes as large as three wheels, huge ears and a horn as high as the evil Dahhak. Keresaspa jumped onto his back and stayed there for a half-day until he finally clubbed him to death. *See also* Gandarewa; Keresaspa.

sSin-rje-gsed-kyi-dkyil-kor (Tibet) *see* Yamantaka.

Ssu Ling (China)
Four spiritual animals. Ch'i-lin or Pai Hu, the unicorn, is the chief of the animals; the Phoenix, Feng-huang or Chu Ch'ieh, is the chief of all birds; the tortoise, Kuei Shen, is the chief of all mollusks; the dragon, Lung, is the chief of all scaly animals. *See also* Kuei Shen.

Ssu Ming (China)
Arbiter of life and death, and protector of virtue. One of the Nine Heroes. He is divided into two beings and is sometimes confused with Shang T'ai and Wen Ch'ang. *See also* Nine Songs.

Ssu Ta Chin-kang (Buddhist; China)
Also known as: *Diamond Kings of Heaven, Kings of Hell, T'ien-wang.*
The Ssu Ta Chin-kang are four brothers, protector deities who are gods of happiness. Their names are Mo-li Ch'ing or Tseng Chang; Mo-li Hung or Kuang Mu; Mo-li Hai or To Wen; and Mo-li Shore or Ch'ih Kuo. They represent "pure, vast, sea, and age." Generally, they are considered to be mortal generals who were deified. *See also* Diamond Kings; Mo-li Ch'ing; Mo-li Hai; Mo-li Hung; Mo-li Shou.

Staphylus (A) (Greek)
An Argonaut. He is the son of Dionysus and Ariadne or Theseus and the husband of Chrysothemis and Ariadne. *See also* Argonauts; Ariadne.

Stellar Goddess (China) *see* Chin Nu.

Stenele (Greek) *see* Danaus.

Sterculius (Roman) *see* Stercutius.

Stercutius (Roman)
Also known as: *Sterculius.*
Agricultural deity. His father is Fanus, the inventor of herding, hunting and husbandry, and he is the possible father of Picus, the prophet who was turned into a woodpecker by the goddess Circe. Stercutius oversees the manicuring of the fields. He invented many agricultural tools and was the first to use manure. *See also* Acis; Fanus; Picus.

Sterope (A) (Greek)
She is the daughter of Acastus, the King of Iolcus and son of Pelias and Astydameia or perhaps Hippolyte. She is the sister of Laodamia and Sthenele.

Sterope (B) (Greek)
Also known as: *Asterope.*
She is the Pleiad daughter of Atlas who was turned into stone and Pleione (also known as Aethra). Her siblings are Alcyone, Celaeno, Electra, Maia, Merope and Taygete. She is either the wife or mother of Oenomaus.

Sterope (C) (Greek)
She is the daughter of the King of Tegea and Argonaut, Cepheus, and the sister of Aerope and possibly Echemus.

Sterope (D) (Greek)
She is the daughter of Porthaon, the first king of Calydon and Eurtye, the daughter of Hippodamas. Her siblings are Agrius, Alcathous, Melas, Oeneus and Leucopeus. She could be the mother of the Sirens.

Steropes (Greek)
"Lightning."
He is the Cyclops son of Uranus and Gaea, brother of Arges and Brontes. *See also* Acamas (D); Aegaeon; Cyclops; Gaea.

Sthalidevatas (India) *see* Devis.

Stheneboea
Also known as: *Antea* (Greek)
She is the daughter of Iobates (also known as Amphianax), the King of Lycia and the sister of Philonoe. Stheneboea married Proetus and became the mother of Iphinoe, Iphianassa, Lysippe and Megapenthes. Bellerophon made it clear that he wanted Stheneboea as his wife. Her father, Iobates, sent him to fight Chimaera, the fire-snouting three-headed daughter of Echidna and Typhon. After slaying Chimaera, Bellerophon returned and was given the hand of Stheneboea's sister, Philonoe. Stheneboea was in so in love with Bellerophon that she committed suicide. *See also* Antea; Bellerophon; Iobates; Proetus.

Sthenelaus (A) (Greek)
He is the son of Actor who was killed while fighting the Amazons with Heracles.

Sthenelaus (B) (Greek)
He is the son of Androgeus, the famous athlete who is the son of Minos and Pasiphae. His brother is Alcaeus, King of Thasos, with whom he shared the throne.

Sthenelaus (C) (Greek)
His parents are Capaneus and Evadne. He was one of Helen of Troy's numerous suitors.

Sthenelaus (D) (Greek)
He is the son of Perseus (who is the son of Zeus) and the beautiful Andromeda. His siblings are Alcaeus, Gorgophone, Heleus, Mestor, Perses and Electryon. *See also* Alcaeus; Andromeda; Electryon; Gorgophone; Heleus; Mestor; Perses; Perseus.

Sthenele (Greek)
She is the daughter of Acastus, who is the King of Iolcus, and Astydameia, who is the daughter of Pelops and Hippodameia. Her siblings are Laodamia and Sterope. She wed Menoetius, the son of Actor and Aegina, and became the mother of Patroclus who was a close friend of Achilles with whom he shares burial grounds on White Island. *See also* Acastus; Laodamia; Patroclus; Stercutius; Sterope (A).

Stheno (Greek)
Stheno is one of the Gorgons. *See also* Gorgons; Medusa.

Stone of Fal (Celtic) *see* Tuatha De Danann.

Stratius (Greek)
He is the son of Nestor and Eurydice, or possibly Anaxibia. His siblings are Antilochus, Artetus, Echephron, Paeon, Peisidice, Peisistratus, Perseus, Polycaste and Thrasymedes. *See also* Antilochus; Nestor; Perseus.

Straw Mirror (Mexico) *see* Texcatzoncatl.

Strenia (Roman)
Goddess of fruits. She presides over New Year festivals. Strenia corresponds to the goddess of health, Salus.

Stribog (Slavic)
God of the wind. Slavic mythology has several gods of the wind and storms which may be related. They are Dogoda the west wind, Varpulis, the noise of the storm, and Erisvorsh, the deity of the holy tempest. They are all related to Perun (q.v.). *See also* Varpulis.

Stromkarl (A) (Sweden)
Fresh water spirit.

Stromkarl (B) (Norway)
"River Man." He is a talented musician who is a spirit of a waterfall. If a white kid or black lamb is sacrificed to him on a Thursday, he will teach the believer one of the eleven tunes he knows. If the student dares to play the eleventh tune, men, women, infants, cups, plates, chairs and tables must dance wildly.

Strymon (Greek)
River god. His parents are Oceanus and Tethys. He is the father of Evandne. *See also* Argus (A); Hesione.

Stupa (Buddhist)
Also known as: *Caitya, Dagoba, Pagoda, Sharira, Tope.*
A chief symbol of Buddhism, the stupa is a mound that is found in many forms and ranges from the size of an amulet to several hundred feet. A sacred object, it is revered because it is thought to preserve relics of Gautama Buddha. The sacred Indian world mountain Sumeru is known as a Stupa. When covering the remains of other Buddhas or holy men it is called sharira. It is known as a tope when it is erected as a memorial to a priest. *See also* Abheda; Amida; Buddha; Kuvera; Maitreya (the stupa is his emblem); Nagarjuna; Yamai.

Stymphalian Birds (Greek)
As his sixth labor, Heracles had to rid the Stymphalian lake in Arcadia of these birds. They were able to wound all who approached them with their arrow-like feathers. Hephaistos, the god of fire, made a bronze rattle that Athene gave to Heracles. The sound frightened the birds away. They flew to the island of Ares in the Euxine Sea, and it was there that the Argonauts encountered them. *See also* Athene; Hephaistos; Heracles.

www.ebook3000.com

Open your palms: scoop up the Chi, scoop up the fire. Bring the fire into your Tan Tien. Activate the Tan Tien Fire.

1. You start with a small dot of light inside you. Expand your awareness smiling to the universe in front of you.
2. Become aware of a big fireball in front of you. Fell your hand become bigger and longer. Scoop up the fireball. You may close your eyes to help your inner sensing.
3. Use the fireball to light the fire in your Tan Tien. Feel the fire burning in the darkness, the 'fire burning under the sea.'



Fig. 3.28 *Smile to the Burning Fire.*

Back Direction and Kidney Fire

Be aware of the back of the Tan Tien, the Door of Life and the back or rear direction. Extend your mind very far away to the 'back'. Scoop up the fire and light up your 'Kidney Fire'.



Fig. 3.29 *Be aware of the back direction, move the arms toward the back of the universe and scoop up the universal fire.*

Stymphalus (Greek)
King of Arcadia. The son of Laodice. Stymphalus was killed by Pelops. *See also* Aeacus; Laodice; Pelops.

Styx (Greek)
River deity. A Titan, the nymph Styx is the daughter of Oceanus and Tethys or Uranus and Gaea. She married the Titan Pallas, the son of Crius and Eurybia. They became the parents of Zelus (Zelos), meaning jealousy or zeal; Nike, meaning victory; Cratus (Kratos), meaning strength; and Bia, meaning force or violence. Their offsprings exhibited the attributes of Zeus. In some renditions of this legend it is thought that Styx was the mother of Persephone by Zeus, though it is usually Demeter who is named as her mother. When Zeus rebelled against Cronus and was attacked by the Titans, Styx deserted her brothers and with her children became one of the first deities to assist the great god. In gratitude, Zeus gave her the river Tartarus which bordered the lower regions of the underworld. She also ruled over her river, the Styx, one of the rivers of the underworld that separates the boundaries of the world between the living and the dead. It flows around the infernal regions nine times. The supreme judge Minos and his associates, Rhadamanthus and Aeacus, were located on the far bank of the Styx. Charon, the ferryman, also took dead souls across this river as he did on other rivers of the Underworld. Zeus agreed that all important oaths uttered by the Immortals would be sworn on the waters of the Styx. The messenger of the gods, Iris, would fly down to Tartarus for a vial of water from the river and return it to the oath sayer to drink, thus making the oath sacred. If the oath was broken, the person would go into a coma for one to nine years depending on the version of the myth. If the oath sayer regained consciousness and still did not abide by the oath, he or she was expelled from the company of the Olympians forever. It is said that when Hera swore by Styx from the peaks of Olympus, she could touch the earth with one hand and with the other could reach the seas. Thetis plunged her son Achilles into the Styx at birth to make him invulnerable. Only his heel remained dry. The mythology of the Styx is said to have originated in Egypt and legend has it that Isis buried Osiris on its banks. *See also* Acheron; Cocytus; Gaea; Golden Bough; Hades; Lethe; Mino; Oceanids; Oceanus; Rhadamanthus; Tartarus; Tethys; Uranus; Zeus.

Suaha *Suada, Svaha, Swaha* (Hindu; India)
Also known as: *Agnayi.*
Suaha is one of the numerous daughters of the early Vedic god, Daksha. He gave Suaha to Agni to be his wife. She is also reputed to be one of the wives or consorts of the great god of winds and storms, Rudra. *See* Agni; Daksha; Karttikeya; Rudra.

Suadela (Roman) *see* Aphrodite.

Suasuthur (Teutonic) *see* Summer.

Subbu-Khai-Thung (Dhammai People, India)
She is the earth goddess daughter of Shuznagu and Zumiang-nui who existed before the sky and earth. Her sky god brother, Jongsuli-Young-Jongbu, was born at the same time. The children were swallowed by the worm Phangnalomang. For details, *see also* Shuznaghu.

Subhadra *Jagannatha* (Hindu; India)
She is the daughter of Vasudeva and Devaki, sister and spouse of Arjuna and mother of Abhimanyu (also known as Saubhadra) by Krishna. *See also* Abhimanyu; Arjuna; Devaki; Krishna.

Subramanya (India) *see* Karttikeya.

Succubus *Succuba* (Middle Ages)
The Succubus is a female demon from the class of demons known as Incubi. The Succubus comes to men in the night. When the male awakens, the proper prayers must be recited to prevent pregnancy from the union, for if children are produced they are considered demonic. *See also* Incubus.

Sucellos (Celtic)
Also known as: *The Good Striker, The Mighty Striker.*
God of death. God of fertility. Thunder god. Known as Silvanus in southern Gaul, Sucellos is a charitable underworld deity who is thought by some to be connected with Dis Pater and has been equated with Cernunnos. His consort is the fertility goddess, Nantosuelta. Sucellos is shown as a heavy-set man, with long hair and a beard, wearing a long, belted tunic, sometimes with tights and sometimes bare-legged. He holds a long-handled mallet in one hand (indicating creativity) and a drinking vessel (fertility) in the other. He is frequently shown with Nantosuelta and is often accompanied by a dog. Compare Sucellos to Thor and Dagda. *See also* Cernunnos; Dis Pater; Nantosuelta; Silvanus.

Suchos (Egypt) *see* Sebek.

Suci (India) *see* Agni.

Sudalaiyadi (India)
"Dancer of the Burning Ground." *See also* Nataraja; Shiva.

Sudarsana (India) *see* Sudarshana.

Sudarshana *Sudarsana* (Hindu; India).
Sudarshana, Vishnu's magic discus, lives in the sky. Shaped like a wheel with edges sharp enough to cut off the heads of demons and tops of mountains, it spits fire and causes lightning. Sudarshana always returns to Vishnu. *See also* Rahu; Savarbhanu; Sisupala.

Suddhodana, Rajah (India)
Putative father of Gautama Buddha (q.v.).

Sudhanvan (India) "The Good Archer." *See also* Ribhus.

Sudjaje (Slavic) Goddesses of destiny.

Sudre (Teutonic) *see* Sudri.

Sudri *Sudre* (Norse; Teutonic)
Sudri is one of the four dwarfs who supported the heaven's vault, made from the skull of Ymir, on their shoulders. His name became South. The other dwarves are Nordri, Austri and Westri. *See also* Aarvak; Dwarfs; Nordri; Ymir.

Sudyumna (India) Son of Vaivasvata (q.v.).

Suetiva (Colombia) *see* Chia.

Suffete (Ugarit)
A beast who is the Lord of the River. *See also* Bod-Baal.

Sugriva *Sukrip* (Hindu; India)
The son of Surya, Sugriva was the honorable ruler of the Vanavasas, who are forest dwellers. His powerful half-brother

Bali ousted him from his throne. He did not regain his position until Rama killed Bali. In return, Sugriva, his commander-in-chief Hanuman, and his army of monkeys aided Rama in his battle against the demon Ravana and the rescue of Rama's mate, Sita. Sugriva is the spouse of Ruma, Queen of the Apes. *See also* Bali (A); Hanuman; Kabandha; Rama; Ravana; Sita; Surya; Tara (A); Yadavas.

Suhgurim (Babylon) *see* Marduk.

Suhiji-Ne No Mikoto (Japan) *see* Ama-no-minaka-nushi.

Suhiji-ni No Mikoto (Japan) *see* Ama-no-minaka-nushi.

Suhrim (Babylonia) *see* Marduk.

Sui-tengo *Suitengu* (Japan)

Suitengo is the protector of sailors and sick children. She is depicted in the shape of a woman holding a child in her arms. *See also* O-Wata-Tsu-Mi.

Suilap (Altaic, Tartars) *see* Bai Ulgan.

Suitengu (Japan) *see* O-Wata-Tsu-Mi; Sui-tengu.

Sujang-Gnoi-Rise (Dhammai People, India)

He is the mountain son of Shuznaghu and Zumiang-nui. His siblings are a sister, Jibb-Jang-Sangne, who is also a mountain; another sister, Jassuju, and a brother, Lujjuphu, who were born as frogs. *See also* Shuznaghu.

Sukan-Bikona (Japan) *see* Suku-na-Biko.

Sukana-Biko (Japan) *see* Susanowo.

Sukanthi (India) *see* Apsarases.

Sukanya (India)

She is the daughter of Saryata and wife of Chyavana. *See also* Mada.

Sukapreyasi (India)

Sow and earth goddess. *See also* Prithiva; Varaha.

Sukarasya (Buddhist; India) The Divine Cow.

Sukati (Egypt)

Afterworld deity. A minor god found in Tuat. If the deceased is able to recite a certain formula and keep it secret from the god, he is allowed to drink from the deepest and purest part of the celestial stream, and eventually to become "like one of the stars in the heavens."

Sukhavati (Buddhist; India)

Also known as: *Go-Kuraku-Jodo* (Japan), *The Happy Realm of Sukhavati, Hsi T'ien* (China), *Red Western Realm of Happiness, Si-Fang Ki-Lo Shi-Kiai, Ts'ing-tsing T'u.*

Sukhavati is the western paradise of Amitabha. A place of perfection located an incalculable distance from earth, this is where the soul is invited to be born again. The blessed are surrounded by jewel-laden trees, beautiful gardens and serene waters. They bathe in water that is always the right temperature, without fear of drowning. Apparel is provided to the specifications of the blessed. One need only think of the food, aroma, and music most loved and it is provided. Apsarases (nymphs) attend every need. In Sukhavati, souls are conceived in lotus hearts. The soul develops and is nourished by the teachings of Buddha. The flowers ripen by the rays (fingers) of Buddha and the soul comes forth. It is in Sukhavati that the souls are judged. The bad souls are judged by Ch'eng-huang and the good souls by Kuan-yin. After judging they are sent to Tung-yo ta-ti who is called the Emperor of the Eastern Peak. Sukhavati is generally represented by a square structure of bamboo covered by sheets of paper. *See also* Amida; Amitabha; Apsarases; Chakravala (Buddhist Universe); Dhartarastra (Guardian in the Heaven of the Four Great Kings); Gokuraku; Lokapalas; Naga Knaya; Tushita; Yidak.

Sukhos (Egypt) *see* Sebek.

Suko (Dahomey People, Africa) Supreme god.

Sukra (India) *see* Shukra.

Sukrip (India) *see* Sugriva.

Suku-na-Biko *Sukan-bikona, Sukuna-biko, Sukuna-bikona, Sukuna-biko-na-no-kami* (Shinto; Japan).

Chief of medicine deities. Suka-na-Biko (Small Prince of Renown) is the dwarf son of the goddess Kami-Mimusubi. When Okuni-Nushino-Mikoto was murdered by his brothers, Kami-Mimusubi was called upon by his mother and she resurrected the woman's son. Suku-na-Biko mysteriously arrived by boat to assist Okuni-Nushino-Mikoto, the son of Susanowo, in establishing his kingdom. Suku-na-Biko is a medicine god who wears moth wings with small feathers. One day he climbed a millet plant when it was ripe. His weight made the plant bend and he was flung to the heavens, where he remains to this day. Okuni-Nushino-Mikoto, who acutely felt the loss of his colleague, called out to the heavens in despair. A blinding light appeared over the sea and a voice announced itself as the protecting deity and instructed the distraught man to worship him on Mount Mimoro. His name was Omiwa. For additional details *see* Kami-Mimusubi; Okuni-Nushino-Mikoto.

Sukuna-biko (Japan) *see* Suku-na-Biko.

Sukuna-biko-na-no-kami (Japan) *see* Suku-na-Biko.

Sukuna-bikona (Japan) *see* Suku-na-Biko.

Sul (Celtic, British) Goddess of warm springs.

Sulman (Babylon) *see* Saramana.

Sulmus (Mongol)

Deity of evil. *See also* Ocirvani; Tsagan-Sukuty.

Sulochana (India) A Yakshini. *See also* Yaska.

Sumati (India)

Sumati is the daughter of Vinata and Kasyapa and the mate of Sagara. She gave birth to a giant gourd containing sixty thousand sons. *See also* Garuda; Kasyapa; Sagara.

Sumatra — Creation Legend *see* Batara Guru.

Sumaya (India) *see* Maya (C).

Sumbha (India) A demon. *See also* Durga; Kali.

Sumeru (India)

Sacred Mountain. *See also* Meru Mountain; Stupa.

Sumitra (India) A Yakshini. *See also* Rama; Yaska.

www.ebook3000.com

Summano (Etruscan) *see* Uranus.

Summer (Teutonic)
God of the Season. Descendent of Svasud and one of the rulers of the seasons. The god Summer is the enemy of Winter. *See also* Winter.

Summer Spirit (Acoma People) *see* Mayochina.

Sumul (Ugarit) Mother of the Vultures. *See also* Khasis; Kothar.

Sumuqan (Assyro-Babylonian)
"King of the Mountain." Sumuqan is a cattle god who lives in Ereshkigal's court in the underword. *See also* Enki; Ereshkigal.

Sumur (Central Asia) The world mountain. *See also* Abyrga.

Sun (Norse; Teutonic)
Also known as: *Sol.*
The sun. Sun is the daughter of Mundilfari. She drives the sun on its course through the heavens. *See also* Helius; Mundifari; Ra; Surya.

Sun Hou-tzu (China)
Ruler of the monkeys. Sun Hou-tzu is a monkey or a fairy who carries a magic wand. When he was taken in chains, to the land of the dead, Sun Hou-tzu found and tore up the page on which his name was recorded, stating he was no longer subject to death. The king, Yen-Lo-Wang, conceded to his declaration.

Sun-pin (China)
Sun-pin is the mortal who invented shoes to cover his feet after his toes were cut off in a war.

Sunaman (India) *see* Krishna.

Sunda (India) *see* Arjuna.

Sundara (India) *see* Kuvera; Shiva.

Sundareshwar (India) *see* Shiva.

Sung Chiang *Sung Kiang* (China)
God of thieves. Once a renowned bandit, Sung Chiang was later deified. The more ancient mortal bandit named Chi is also worshiped as another god of thieves.

Sung Kiang (China) *see* Sung Chiang.

Sung Ti (Buddhist; Central Asia)
Sung Ti is one of the Kings of Hell who after the sinners are judged guilty, tortures them with hot water and fire. *See also* Kshitigarbha.

Sung-tsi (China) *see* Avalokitesvara; Kuan-yin.

Sung-tsi Kuan-yin (China) *see* Avalokitesvara; Kuan-yin.

Sung-tsi Niang-niang (China) *see* Sung-tzu Naing-naing.

Sung-tzu-Naing-naing *Sung-tsi Niang-niang* (China)
Goddess of Fecundity and Healing. Goddess of newborn children. She likes incense, firecrackers and rattles. She is one of six deities who are in the train of Sheng mu. Sung-tzu Naing-naing is shown with an infant in her arms. She is usually associated with Sheng mu.

Sung-tzu-niang-niang (China) *see* Kuan Yin.

Sunstone, The (India) *see* Syamantaka.

Suntra (Hindu; India) Fertility goddess.

Supai (India) *see* Supay (A).

Supai (Inca) *see* Supay (B).

Suparnas (Hindu, India)
Winged supernatural beings who dwell in the Simbali forest under the rule of Garuda. They are invoked at the daily presentation of water to deceased ancestors. *See also* Garuda.

Supay (A) (India) God of air.

Supay (B) (Collao, Inca People, Peru)
Also known as: *Supai.*
God of the dead. Evil spirit. Lord of minerals. Supay rules over those spirits that did not go to the Land of the Sun and are confined within the dark earth. Supay demanded human sacrifices, especially children, to populate his kingdom. He has the ability to transform himself into an animal and to make animal sounds. He can also appear as a charming mortal and when the confidence of his victim has been won he is said to enter the body and cause epilepsy or madness. Silver can be transformed to gold by this god of the dead. Supay, who emits a sulfuric odor, is sometimes depicted with a lion's body, ram's horns, and tiger's teeth. *See also* Anchancho; Ekkekko.

Support (Polynesia) *see* Tango.

Suprabha (India) *see* Arjuna.

Supratika (India) *see* Dikpalas; Lokapalas.

Sura (A) (Andean People, Peru)
Supreme deity. Maize seed was given to Sura by Sibu, another supreme god. While planting the seed it was stolen by Jaburu who is an evil god. Given a cup of chocolate by Sibu, Jaburu swelled so much he blew up. The seed was then returned to Sura.

Sura (B) *Soora* (India) Goddess of Wine. *See also* Kurma.

Surabhi (Dravidian, Hindu; India)
Known as "the fragrant one," Surabhi the cow goddess and goddess of plenty is one of Daksha's daughters. Born from the churning of the ocean, she descended to earth with Indra. Later she became one of the mates of the sage Kasyapa and the mother of cows, buffaloes and the goddess Nirritti. She symbolizes Nature's productive power and is closely connected with "Cow of Desire," Kamadhenu. She is associated with the Rishi (q.v.). *See also* Daksha; Indra; Kamadhenu; Kasyapa; Kurma; Nirritti.

Surabhidatta (India) *see* Apsarases.

Suradevi (India) Goddess of wine and spirits.

Surapamsula (India) *see* Apsarases.

Suras (Persian) *see* Aditi.

Surasa (India) *see* Kasyapa.

Suris (Persian) *see* Aditi.

Surisi (India) *see* Devi.

Surisvari (India) "Divine Lady." *See also* Devi.

Surpanaka (India) *see* Shurpanaka.

Surt (Teutonic) *see* Surtr.

Surter (Teutonic) *see* Surtr.

Surtr (Norse; Teutonic)
Also known as: *Black Surt, Surt, Surter, Surtur.*

Fire god. Surtr is a flame giant who guards Muspells-heim (Muspell). His sword sent sparks which partially melted the great ice-blocks coming from the streams of the Elivagar. He is the father of Sattung (or Glaur) and grandfather of Gunlodd. At the apocalyptic final battle of Ragnarok, Surtr will lead his band consisting of army of Hel, Liki, Garm, Fenris and Iormungandr against the Aesir and Vanas. Surtr will kill Frey and proceed to end the world with his fiery sword. *See also* Audhumbla; Elivagar; Fjalar; Ginnunga-gap; Gunlodd; Hvergelmir; Sattung; Sol; Vigrid.

Surtur (Teutonic) *see* Surtr.

Surya *Surja* (Brahmanic, Hindu, Vedic; India)
Also known as: *Dina-Kara* (Day-Maker), *Divine Vivifier, Karma-Sakshi* (Witness of Deeds), *Surya-Bai* (female aspect of Surya), *Surya Narayana* (Surya's title as a divine incarnation of Vishnu).

Surya, the sun god and god of fate, is variously described as one of three sons of Dyaus, or the son of Aditi or Brahma. In early times, as the son of Dyaus, he was one of a triad, with his brothers, Indra and Agni. He was also a part of a triad with Agni and Vayu. As the power of the sun, in a fixed universe, he is the god of everything, both moving and static. He removes darkness, heats the world, and is the nourisher and stimulator of mortals. His light cures darkness, leprosy, and poverty. He became the husband of Sanja, who is the daughter of the divine artificer, Visvakarma. Surya is also represented as the father, husband or lover of the beautiful Ushas, goddess of the dawn. As in the mythology of Vivasvat, Surya married and was later left alone by his mate, who could not tolerate his dazzling light. Surya's spouse Sanja, the daughter of Visvakarma, bore three children before her departure. She arranged for the shade goddess Chhaya to take her place. In some renditions, the substitute mate is Aswini who is said to be the mother of the Asvin twins. It was several years before Surya realized that Chhaya was not his wife. In the form of a stallion, he searched for and found Sanja, who had disguised herself as a mare. They were reunited only after her father shaved away an eighth of his rays. Surya is called the father of the Asvin in some legends and the father of the twins Yama and Yami in other renditions (as is *Vivasvat*) or the father of both sets of twins. He is the father of the goddesses Kalindi and Madri who became wives of Krishna. The goddess Kunti, also known as Pritha, chose Surya as one of her five lovers. Surya is said to be the source of amrita which he passes to Soma the moon god to dispense to the gods. As with Soma, a hostile atmosphere exists between Surya and the demon Rahu, who sometimes swallows him. In the Purana, Surya is celebrated as the supreme soul in all the Vedas. He is given names and epithets corresponding to the major deities; Indra, Dhata (or Dhatr, a synonym of Prajapati) known as the Creator of All Things, Parjanya, Tvashtri, Pushan, Aryama, Vivasvat, Vishnu, Ansuman (who keeps the vital organs functioning properly), Varuna, and Mitra. The deities Savitri and Vivasvat were absorbed by and became aspects of Surya. This god was widely worshiped during the Vedic and Puranic periods. He is often referred to as the eye of Varuna (the moon) and Mitra (the sun). As a fate deity, Surya sees all and notes all. He bestows immortality on the gods and presides over the length of a mortal's life. He is invoked to cure illness and to eradicate evil spirits, for his radiance destroys darkness. Surya is depicted as a goat or horse, sometimes as an eagle in flight, or as a short or legless man. He is also shown as a dark red man with three eyes and four arms. Two of his hands hold water-lilies, the third is in an attitude of blessing, and the fourth is shown in an attitude of encouragement. He is sometimes shown with gleaming, golden hair and arms, riding in a golden chariot drawn by seven red mares, or one mare with seven heads. This could represent the seven constituent colors of the sun's rays. He is preceded by his twin sons, the Asvins, who ride in a golden chariot. Surya's symbol was the swastika, which during this period was a symbol of generosity. Rahu swallowing Surya is the sun darkened by an eclipse. Orthodox Brahmans repeat the Gayatri mantra three times a day, to receive the sun god's blessing. The sun is praised in the form of Brahma in the morning, Vishnu at noon, and Shiva in the evening. For the Hindus, the celebration worship day for the sun god is on the seventh day after the new moon in the month which corresponds to January-February (Magha). Red lotuses are used during the worshiping of Surya. Compare Surya to Helius (Greek) and Sun (Teutonic). *See also* Adityas; Agastya; Agni; Aruna; Asvins; Bali; Brahma; Ganesha; Indra; Krishna; Lockapalas; Martanda; Mithra; Mitra; Parjanya; Prajapati; Pushan; Radha; Rahu; Sanja; Savarbhanu; Savatri; Soma; Sugriva; Surya-Bai; Syamantaka; Tapati; Urvasi; Ushas; Varuna; Vasistha; Vedas (The); Vishnu; Visvakarma; Vivasvat.

Surya-Bai *Savitri, Surya* (Male aspect of Surya-Bai); (Vedic, Hindu; India)

Surya-Bai, the sun goddess, is the female representative of the sun. She is the daughter of the sun god Savitri. Surya is the wife of Soma the moon god. In some legends she appears as the spouse of the twin gods of light, the Ashvins. She has been called the lover of the moon god Chandra. In Vedic mythology, as Surya-Savitri, representing the sun at winter solstice, she is the wife of Pushan and the Asvins. Surya is depicted in a three-wheeled car accompanied by the Asvins. This group of three, in their three-wheeled car, symbolizes the morning, noon and evening light. As Surya Savitri, the goddess represents the dawn. There is a connection between Surya-Bai and the Persian fire goddess Anahita (q.v.). *See also* Asvins; Chandra; Savitri (B); Soma; Surja; Surya; Ushas.

Surya Narayana (India) "Moving in Waters." *See also* Surya.

Suryabhauma (Nepal) *see* Dikpalas.

Suryi (India) *see* Yami.

Susa-no-wo (Japan) *see* Susanowo.

Susa-noo (Japan) *see* Susanowo.

www.ebook3000.com

Susano (Japan) *see* Susanowo.

Susano-o-no-Mikoto (Japan) *see* Susanowo.

Susanoo (Japan) *see* Susanowo.

Susanowo *Susa-no-wo, Susano, Susanoo, Susa-noo* (Shinto; Japan)

Also known as: *Atago-Gongen, Buto, Susano-o-no-Mikoto* (His Brave Swift Impetuous Male Augustness), *Taka-haya-susa-no-wo, Take, Takehaya Susanowo.*

God of water. God of storms. God of the sea. God of forests. Ruler of the ocean and mysterious things. God of love and marriage (in later times). Susanowo is one of a trinity with Amaterasu and Tsuki-yomi. He is the son of Izanagi (Male Who Invites) and Izanami (Female Who Invites). His sister Amaterasu is the sun goddess and ruler of the light in Ama (heaven) and on earth. The moon god and ruler of the night, Tsuki-yomi, is his brother. Susanowo is variously called Swift-Impetuous-Deity, the Impetuous Male, and the Valiant Swift Impetuous Hero. When Izanagi escaped from Yumi (hell) where he had unsuccessfully attempted to persuade Izanami to return with him, he felt tainted by death's grasp. He plunged into the powerful sea to cleanse himself of the pollutants that had adhered to his being. From his discarded clothing, the dirt and grime of the underworld was released into the water. This act liberated many evil spirits from the darkness to the light. He threw in his stick and the God-set-up-at-the-crossroads was created. When he cleansed his body, two deities who created ills were produced. To counterbalance their manifestations, he created two deities to set the ills right. He then dove into the sea and all the sea deities were created. When he washed his left eye, his daughter, the beautiful sun goddess Amaterasu, came forth. From his right eye, her brother, the moon god, Tsuki-yomi was born. When he washed his nose, Susanowo was created. Izanami gave them definite realms and functions. Amaterasu was to be the sun goddess and ruler of the realm of light on heaven and earth. Tsuki-yomi was the moon ruler and ruler of the night. To Susanow, Izanami gave the domain of the ocean and other mysterious things. The sun goddess and the moon goddess followed their father's command and took up their duties. Susanow alone was recalcitrant. He insisted that he wanted to be with his mother Izanami, who was now the genius of death in the underworld. Finally, his father drove him away. Before departing, he went to bid his sister Amaterasu farewell. En route to the celestial sphere he caused a major uproar. Mountains shook and the earth groaned and quaked in upheaval. The alarmed sun goddess, fearing a confrontation, prepared her bow and arrows. Susanow assured her that his visit was without malice. To prove his intent, he suggested that they each create children. The sun goddess took her brother's sword and broke it. She masticated the three pieces, blew a mist from her mouth and created three goddesses. The storm god asked Amaterasu for Mi-kura-tana-no-kami, her strand of jewels. He split them between his teeth, blew a mist from his mouth and created five male deities. Amaterasu decided that these were her children as they had evolved from her jewels. Excited with his accomplishments he lost control. A rampage evolved and destruction ensued. He roared through the land and obliterated the rice fields and irrigation systems his sister had developed. He sullied the sacred observances of the rules of purity that she had instituted by piling excrement in her sacred places. Unwilling or unable to deal with his unexpected outburst, Amaterasu secreted herself in a cave and the world was immersed in darkness. (*See* Amaterasu.) For his impetuousness he was punished by the gods. His beard was shaved, his nails were ripped from his fingers and toes and he was ousted from heaven. When Susanowo was controlled by Ara-mi-tama, his wicked soul, his nature was evil. When Nigi-mi-tama, his beneficent soul, was in charge, Susanowo was gentle and kind. On one occasion, the life of the rice goddess Kushi-nada-hime was endangered. The eight-headed dragon Koshi was making his annual visit and she was his next victim. Susanowo tricked the monster and chopped him into pieces. Susanowo and Kushi-nada-hime were married. He gave the sword Kusanagi that came from the tail of the dragon to his sister Amaterasu. Susanowo is the father of Okuni-Nushino-Mikoto (Great Land Master). His son is a healer and sorcerer, who works for the welfare of the people. It is often said that he is the only descendant of Susanowo. In other traditions, another son is mentioned: Oh-Magatsumi (Great Evil-doer), who was the source of all evils. Idakru is also mentioned as a son. Oni-tsu-nu is said to be the grandson of Susanowo. In one legend, Susanowo, dressed in rags, made his way to the home of a wealthy man, Kotan-Shorai. It was a wild and stormy night and the Susanowo asked for lodging. Kotan-Shorai, who did not recognize him, refused him entry. Susanowo chopped the inhospitable man into five pieces and offered him as a sacrifice. This complicated deity was eventually banished to the place of exile, Izumo. There, with his sons, they ruled the land and continued to rebel against the solar deities for a time. In the province of Izumo, as an ancestor of the Izumo tribe, Susanowo was reputed to have planted the forests on the coasts of Korea. He also created the mountains on the southern side of Japan (in the province of Kii). These remarkable locations sprang from the hairs on his head and beard. As instruments for mysterious and sometimes evil happenings, Susanowo was thought to be the chief of spirits in Yomi-tsu-kuni (land of darkness) or the underworld. Susanowo, Oh-Magatsumi, Okuni-Nushino-Mikoto and Suku-Na-Biko (the chief of the medicine men) were called upon by the Izumo followers whenever disease ravaged the land or a major disaster occurred. Susanowo's attribute is the ox. The killing of the dragon is an aspect of Susanowo as a warrior. The myths of Susanowo are related primarily to water, thunder and the snake. In early Japan, the snake was considered the god of Thunder. The sword, known as Kasanagi, a symbol of courage, is one of the three insignia depicting Imperial power. (*See* Kasanagi.) A mirror known as Kagami, also called Yata-Kayami, the symbol of purity, is another insignia. The third of the insignia is the curved ornamental jewels that symbolize the benevolence of the soul of the sun goddess Amaterasu. The jewels is known as Magatama. It is thought that originally they came from the claws of a tiger or the tusk of a boar. The Chinese believed that the claws of a tiger or the tusks of a boar possessed magical qualities. The Magatama however is characteristically Japanese. Kotan-Shorai literally means inhospitable. *See also* Buto (B). In many ancient cultures, to be inhospitable to friends, strangers and in some cases enemies was a grievous infraction of social mores and sometimes a crime. (*See* Fuji.)

For the Shinto creation myth, *see* Taka-mi-musubi. Susanowo might be the same as Shina-Tsu-Hiko. He is identified with Buto, Emma-O, Sampo-Kwojin and Tsuki-yomi. Other personifications of the warrior are Futsu-nushi (Sharp-Cutting-Lord) and Take-mika-zuchi (Valiant-August-Thunder). These gods, following the command of the sun goddess, went to vanquish the unruly deities in Izumo. For the return of the world from darkness to light, *see* Amaterasu; Hiruko; Izanagi and Izanami; Okuni-Nushino-Mikoto; Yomi. Compare Susanowo to Andromeda who was saved from the sea monster by Perseus (Greek). The tale of Susanowo and Kotan-Shorai is comparable to the myth of Buto, the ox-headed king, who is an aspect of Susanowo. *See also* Atago-Gongen; Buto (B); Kushi-nada-hime; Ninigi (who became the ruler following Okuni-Nushino-Mikoto's sons); Suku-Na-Biko; Three Goddesses of Munakata; Ukemochi.

Suseri-bime (Japan) *see* Okuni-Nushino-Mikoto.

Suseri-hime (Japan) *see* Okuni-Nushino-Mikoto.

Susetka (Russia) *see* Domovoi.

Sus'istinako *Great Spider* (Akoma, Koshairis People, North America). *See also* Iatiku; Sussistinnako.

Sussistinnako (Sia People, North America)

First creature. The Great Spider Sussistinnako was the first of all living creatures. It was not until he shook his magic rattle and sang that the other living creatures came forth. He created two women: Utset (mother of Indians), and Nowutset (parent of other men). Another version says he created the two women from the east and west points of the lower world. The cosmogony of the Sia is similar to that of the Navajo.

Sussitanako (Keres, Pueblo People, North America)

Sussitanako, the spider woman, created her daughters Ut Set and Nau Ut Set from her singing as she spun. Ut Set became the Mother of the Pueblo people and Nau Ut Set became the mother of all other people. From turquoise, abalone and natural colored rocks, her goddess daughters created the moon and the sun.

Sut (A) (Islamic)

He is the demon of lies. His father is Iblis and his brothers are Awar, Dasim, Tir and Zalambur. *See also* Azazel.

Sut (B) (Muslim) Lord of lies. Son of Eblis.

Sutalidihi (Cherokee People, North America)

The sun. Sutalidihi is the name given to the sun, Unelanuhi.

Sutekh (Egypt) *see* Set.

Suttee *(India) see* Sati (A).

Suttung (Teutonic) *see* Loki; Sattung.

Sutty (India) *see* Devi.

Suvetar (Finnish)

Goddess of the South Winds. She heals with honey dropped from clouds.

Suvinenge (Dahomey People, Africa)

Suvinenge is a messenger between sky and earth. He has the body of a vulture with a bald man's head.

Svadha (India) *see* Pitri.

Svadilfare (Norse; Teutonic)

Also known as: *Svadilfari.*

Deified animal. Svadilfare belongs to the giant who offered to build the wall around Asgard if given the goddess Freyja. The god Loki, in mare form, lured Svadilfari away from his work of hauling stones. From Loki's union with Freyja the great stallion Sleipner was born. The wall was unfinished so Freya was saved. *See also* Loki.

Svadilfari (Teutonic) *see* Svadilfare.

Svafnir (Teutonic) *see* Odin.

Svaha (India) *see* Suaha.

Svald (Teutonic) *see* Idun.

Svalin (Norse; Teutonic)

Svalin is a cooling shield made by the gods to protect the horses who draw the sun chariot, Aarvak and Alsvid. *See also* Aarvak; Alsvid; Muspells-heim; Sol (B).

Svanhild (Teutonic) *see* Swanhild.

Svantevit (Slavic) *see* Svantovit; Svetovid.

Svantovit *Svantevit* (Slavic)

Giant warrior god. God of plenty. Local deity. Svantovit is called the father of the sun and fire. His white horse was used for divination by the priests in later times. He is generally shown holding a bull's horn in his right hand. Hanging beside him are a sword, saddle and bridle. He is similar to the war-gods Rugievit, Yarovit, or Radigast. He is analogous to Pyerun (q.v.). *See also* Svetovid.

Svantrovit (Slavic) *see* Svetovid.

Svar-Loka (India) *see* Loka.

Svarga (India) *see* Swarga.

Svarof (Slavic) God of fire.

Svarog (Slavic)

Also known as: *Svarozits.*

God of the atmosphere, or high god. Svarog is the father of Dazhbog (the sun) and Svarogich (fire). He is identified with Perun (q.v.).

Svarozic (Slavic)

Svarozic is an ancient god of fire. He is the son of Svarog (q.v.).

Svarozits (Slavic) *see* Svarog.

Svart-Alfa-Heim (Teutonic)

Also known as: *Alfar, Svartalfaheim.*

Home of the evil spirits. When Ymir was killed, a host of maggot-like creatures were breeding in Ymir's flesh. These creatures became Dwarfs, Gnomes, Kobolds, and Trolls. Because of their evil ways they were sent down to Svartalfaheim, the underground home of the black dwarfs, where they must remain. If they come forth during the day they will be turned to stone. It is reputed these creatures have a great store of gold, silver and precious gems. Their opposite creatures are Fairies and Elves who are good and reside in Alf-heim (Alfheim). *See also* Ymir.

www.ebook3000.com

Svartalfaheim (Teutonic) *see* Svart-Alfa-Heim.

Svart-Alfar (Norse; Teutonic)
Also known as: *Svartalfar.*
Dwarfs. Maggot-like creatures who came from the flesh of Ymir. They were pictured as black dwarfs or dark elves. They had to stay underground or be turned to stone. They were intelligent and knew the past and future. Homely, dark-complexioned beings with green eyes, large heads, short legs, and crow's feet. *See also* Svartalfaheim.

Svartalfar (Teutonic) *see* Svart-Alfar.

Svasud *Svosud* (Norse; Teutonic)
Also known as: *Svasuthr.*
Possibly a god of the summer sun. He is the giant father of Summer. *See also* Summer; Vasud.

Svasuthr (Teutonic) *see* Svasud.

Svayam-Bhuva (India)
The First Manu. *See also* Manu; Matsya.

Svetovid (Slavic)
Also known as: *Svantevit, Svantovit, Svantrovit.*
Chief of the gods. God of fate, fertility and war. He is possibly the same as Svasud (Teutonic). *See also* Svantovit.

Sviagod (Teutonic) *see* Freyr.

Sviagris (Scaldic)
The Scaldic name for the goddess Freyja's necklace, Brisingamen.

Svipdag (Teutonic) *see* Odin or Od.

Svipday (Teutonic) *see* Aesir.

Svosud (Teutonic) *see* Svasud.

Swaha (India) *see* Suada.

Swanhild (Teutonic; Norse)
Also known as: *Svanhild.*
She is the daughter of Sigurd and Gudrun. After Sigurd's death she married Jormunrek (Ermenrich). When Swanhild was accused of adultery with her stepson, Randwer, Jormunrek had Randwer hanged and Swanhild trampled to death by horses. Swanhild was so beautiful the horses could not trample her without a cover over her. She was avenged by Sorli and Hamdir (two of the three sons of Gudrun) who cut off the hands and feet of Ermenrich. Odin (in his one-eyed form) interfered before they killed him, but bystanders still stoned him to death. *See also* Gudrun; Odin; Sigurd.

Swarga *Svarga, Svarga Loka* (Hindu; India)
Vaijayanta, Indra's celestial home and its great city, Amaravati, which means "Full of Ambrosia," is located on the sacred Meru Mountain. It was built by the architect of the gods, Tvashtri. Swarga, guarded by the white elephant Airavata, is a portable dwelling place and can be moved anywhere. It is here that the faithful await their next birth on earth. Indra presides over Swarga accompanied by his wife, Indrani. The Maruts and other major deities attend their needs. The Apsarases and Gandharvas provide entertainment. The healing twin deities, the Asvins, are the physicians of Swarga. In this capacity they are known as Nasatya collectively or sometimes Dasra and Nasatya. *See also* Amaravati; Andhaka; Apsarases; Arjuna; Asvins; Indra; Indrani; Krishna; Kunti; Loka; Maruts; Meru Mountain; Parijata; Ravana; Sagara; Tvashtri; Vaikuntha; Visvakarma; Yama.

Swayambhu (Nepal) *see* Adibuddha.

Swetavarahi (Nepal) *see* Varahi.

Sword of Nuada, The (Celtic) *see* Tuatha De Danann.

Syama (India)
"The Heavenly Hound." *See also* Kali; Shiva; Yama.

Syamantaka (Hindu; India)
A magic jewel also known as the Sunstone, Syamantaka protected its owner from all harm providing the owner was of good character. If the wearer was evil, it brought evil and ultimately destruction to the person. Each day, this stone produced eight loads of gold. Surya, the sun god, originally gave the jewel to the Yadava, Satrajit, as a gift for his dedicated worship. Krishna coveted it and was riled when Satrajit refused his request. Satrajit's brother Prasena borrowed the jewel one day when he went hunting. Although he was immortal, he was wicked and when he was attacked by a lion, it swallowed the gem and killed him. Krishna was a prime suspect when Satrajit found that Syamantaka was missing. However, Jambavan, the king of the bears, saw the incident from his home in a cave. He killed the lion and secured Syamantaka. In defense of his honor, Krishna set out to find out what had happened to the jewel. His detective work led him to Jambavan. A lengthy and vicious battle followed in the cave. After seven days, Krishna's party assumed the worst and they returned to his celestial home, Dvarka, with news of his death. Back in the cave, the great god was still engaged in combat with Jambavan that lasted for another fourteen days. Finally, Krishna struck a mortal blow to the giant bear. Jambavan realized before death that his battle had been with a god. He turned the jewel over to the conqueror, begged for forgiveness, and gave Krishna his daughter Jambavati as a spouse. Krishna returned the jewel to its rightful owner, Satrajit. Grateful for Krishna's honorable behavior, Satrajit gave Krishna his daughter Satyabhama. He did not retain ownership of the Sunstone for long. He was murdered and Syamantaka was stolen. For some reason, the thief gave the jewel to Krishna's uncle Akrura. Unaware of this transaction, Krishna and Bala-Rama set out, found the culprit and murdered him. But he did not have the jewel. Bala-Rama, who loved Krishna, was convinced that he had stolen the jewel and his accusation led to a serious rift in their friendship. Uncle Akrura finally admitted that he was in possession of Syamantaka. Krishna, Bala-Rama and Satyabhama each claimed ownership but in the end, Akrura was allowed to keep it. *See also* Bala-Rama; Jambavan; Krishna; Surya; Syamantaka; Yadavas.

Syamatara (India) *see* Tara.

Syavana (India) *see* Mada.

Sydycos (Phoenicia) *see* Sydyk.

Sydyk (Phoenicia, Syria, Greek, Babylon)
Also known as: *Sedeq, Sydycos.*

High god. He is the father of the seven or eight Kabirs (Cabiri) who were "great gods," and of Eshmun (Asclepius). He might be related to the Syrian hero-god Sandacos. He could be one of the Phoenician twin deities Sydyk and Misor. *See also* Astronoe; Cabiri; Sedeq.

Syenabhrita (India) "Eagle-Borne." *See also* Soma.

Syenovik (Russian) *see* Domovoi.

Syga-Tojon (Yakut) *see* Ulu Tojon.

Sylain (Gallo-Roman) *see* Silvanus.

Sylg (Teutonic) *see* Elivagar.

Sylvan (Roman) *see* Silvanus.

Sylvanus (Roman) *see* Silvanus.

Symaetis (Greek) *see* Acis.

Symoethis (Greek) *see* Acis.

Syn (Norse; Teutonic)
Also known as: *Synia.*
Goddess of tribunals and trials. Syn is Frigga's attendant. She guards the door of Frigg, and acts for defendants at trials.

Synia (Teutonic) *see* Syn.

Synnytar (Finland) *see* Luonnotar.

Syr (Teutonic) *see* Freyja.

Syren (Greek) *see* Sirens.

Syrus (Greek) *see* Sinope.

T

Ta (Egypt) *see* Ba.

Ta-Djesant (Egypt) *see* Tuat.

Ta-Fan (China)
Ta-Fan is the same as the god Brahma (India).

Ta-Ret (Egypt) *see* Assessors.

Ta-Sent-Nefert (Egypt)
She is the wife of Haroeris, who is a form of Horus. Ta-Sent-Nefert was worshipped with their son P-neb-taui.

Ta-Shih-Chih (China) *see* Tammuz (q.v.).

Ta-Shih-Chih (Buddhist; China)
A Dhyanibodhisattva. Ta-Shih-Chih is the same as the goddess Mahasthamaprapta (Nepal). She is a companion of the goddess of peace, Kuan-yin; the god of learning, Wen-shu; the god of happiness, P'u-hsien. *See also* Dhyanibodhisattvas; Manjusri; Pushan; Samantabhadra.

Ta-Tanen (Egypt) *see* Tanunen.

Ta-Tchesert (Egypt) *see* Tuat.

Ta-urt (Egypt) *see* Taueret.

Ta-uz (Babylonian) Festival Assessors.

Ta'aroa *Taaroa* (Polynesia)
Also known as: *Tangaroa, Te Temu, Tii-Maaraatai.*
Supreme deity. Creator. In the beginning, Ta'aroa developed himself. He existed in Fa'a-ti, the place within the shell named Timi-iti. The outer portion of this shell, named Rumia, existed before creation, in a primeval void of darkness named Po. Eons passed before Ta'aroa slipped from his shell. He was alone. He proceeded to create a new shell for himself and retreated once again. Time passed. Finally, Ta'aroa used the new shell for a foundation and the original one for the top of the sky. He identified himself as the "Source," Te Tumu, the creator of all things. Ta'aora's spine became a mountain ridge, his vitals, the clouds, his arms and legs, the earth. The enormous effort he used to create the universe caused a vast amount of perspiration to accumulate, from which the oceans were created. He also created the god Atea, the light, who in turn began all life. Ta'aroa is associated with Tumu-ra'ifeuna (the Great Octopus). *See also* Atea; Io (B); Maui; Tane; Tangaroa; Po.

Taaroa (Polynesian) *see* Ta'aroa.

Taaroa Kanaloa (Hawaii) *see* Tanaoa (Polynesia).

Taatoa (Oceanic) *see* Tangaroa.

Tabakea (Oceanic)
"The Turtle." He is called the "Father of All Things." *See also* Nareau.

Tablets of Fate (Sumer)
Also known as: *Dup Shimati.*
The destiny of the world is written on the sacred Tablets of Fate. They were called Dup Shimati. The god who had the tablets in his possession became all-powerful. They were given to Kingu to mark his power.

Tabu-Eriki (Polynesian) *see* Tabuerik.

Tabuerik *Tabu-Eriki* (Oceanic)
Creator deity. In legends similar to those of Yelafaz, Nareau

www.ebook3000.com

and Lukelang made Tabuerik, the lightning and thunder god, who in the form of a bird had Rigi, a butterfly who flew around and separated heaven from earth. *See also* Lukelang; Nareau; Riiki; Tangaroa; Yelafaz.

Tacatecutli (Aztec People, Mexico)
God of merchants and adventurers. Tacatecutli opened the way for the other gods. He also opened paths for the imperial armies.

Tachen (Polynesia) *see* Take (B)

Tacita (Roman) Deity of silence.

Tafa'i (Polynesia; Tahiti) *see* Tawhaki.

Tages (Etruscan)
Tages, a small demon who is the son or grandson of Jove, rose from a ploughed furrow and immediately began to predict the future and the signs sent from the gods. He was the first of the Etruscan prophets.

Taguacipa *Taquacipa* (Inca)
"The Deceiver." An evil deity, Taguacipa is in opposition to Viracocha. He undoes the good that Viracocha creates. *See also* Pachacamac; Viracocha.

Tahuantin Suyu Kapac (Inca People, Peru)
Also known as: *Ayar Aucca, Ayar Manco, Ayar Uchu, Ayars, Colla, Cusco Huanca, Hanan Cuzco, Huana Cauri, Manco-Capac, Urin Cuzco.*
Earth gods. The Tahuantin Suyu Kapac are four brothers who are sons of the Sun. Ayar Cachi (also known as Colla) is ruler of the east, Ayar Aucca (also known as Pinau) is ruler of the south, Ayar Manco (also known as Manco) is ruler of the north and Ayar Uchu (also known as Tocay) is ruler of the west. They are similar to Becabs and Acatl. *See also* Acatl; Becabs; Manco-Capac; Texcatzoncatl; Viracocha.

T'ai Ch'ing (China) *see* Ling-Pao T'ien-Tsun; San Ch'ing.

T'ai Ching (China) *see* Yu-Huan-Shang-Ti.

T'ai I (China) *see* T'ai Shan.

T'ai Shan (China)
Also known as: *T'ai-yo Ta-to, T'aiyo Tato, Tung Huang T'ai I.*
God of life. God of fate. God of destiny. God of death. The Great Emperor of the Eastern Peak, the god of T'ai-shan, a mountain in northern China, delegated by the Jade Emperor, Tung Wang Kung, to oversee the lives and activities of mortals and all creatures on earth. He determined the course of men's lives, assisted by a large bureaucracy to handle the details, records, and statistics. In time, T'ai Shan assumed control over life and death. A large splendid temple for this god is in Peking. He is known under different names in other legends. He is said to be the father of Sheng-mu.

T'ai-Shan Niang-Niang (China) *see* Sheng-mu.

T'ai Shang San Kuan (China) *see* San Kuan.

T'ai-Tsung (China) *see* Men shen.

T'ai-yo Ta-to (China) *see* T'ai shan.

Tailtiu (Celtic)
She is the earth goddess wife of Eochaid mac Eire, the king of the Fir Bholg.

Tain Bo Cuailnge (Celtic) Welsh divine bulls.

Taipan (Australia) *see* Rainbow Snake.

Taishaku (Japan)
Taishaku is the Japanese name of the Vedic god Indra.

Tait (Egypt)
Goddess of linen weaving. She is associated with Isis and the swathing of Osiris' body for burial.

T'aiyo Tato (China)
T'aiyo Tato is another name for T'ai Shan, the god of fate, destiny, life and death. *See also* T'ai Shan.

Tajikaroo (Japan) "Prince Mighty Power." *See also* Amaterasu.

Taka-haya-susa-no-wo (Japan) *see* Susanowo.

Taka-Mimusubi *Takami-Musubi, Taka-mi-Musubi* (Shinto; Japan)
Creator deity. Taka-Mimusubi (High Producing) and Kami-Mimusubi (Divine or Mysterious Producing) are the secondary deities who formed the triad that sprang from Chaos. The head of the triad is Ama-no-minaka-nushi, the Eternal Land Ruler. In some traditions, Taka-Mimusubi represents Kami-rogi, the Divine Male, and Kami-Mimusubi represents the Divine Female, Kami-romi. *See* Ama-no-minaka-nushi for the Shinto creation myth. *See also* Amaterasu; Kami-Mimusubi.

Taka-okami (Japan)
Taka-okami is a rain god who dwells in the mountains. *See also* Izanagi; Izanami; Kagu-tsuchi; Kura-okami; Taki-tsu-hiko.

Taka-pime-no-mikoto (Japan)
She is the daughter of one of the Three Goddesses of Munakata, Takiri-bime-no-mikoto, who is also known as Okitsushima-hime-no-mikoto (Mist-Princess-Godddess) and possibly Opo-kuni-nusi. Her brother is Adi-siki-taka-pikone-no-kami. *See also* Three Goddesses of Munakata.

Takama-no-hara (Japan)
Also known as: *Ama.*
Heaven. Takama-no-hara (abode of the gods) is often called Ama (heaven). The ruler of Ama is the radiant sun goddess Amaterasu. Ama is described as a beautiful spot with terrain the same as Japan's and geographically not far away. In early times a bridge named Ama-no-hasidate connected earth to Ama (heaven). This allowed the deities to move back and forth with ease. One day, as the gods were napping, the bridge collapsed. Now there are the celestial deities, known as Ama-tsu-kami, who reside in Takama-no-hara or Ama, and the earthly deities, known as Kuni-tsu-kami, who reside on the islands of Japan. The deities are not confined to their locales. There are times when the Takama-no-hara will settle on earth and the Kuni-tsu-kami will move to the celestial realm. However, the heavenly deities do not know what is transpiring on earth unless news is brought to them by messenger. The opposite of

Takama-no-hara or Ama is Yomi, the underworld realm. *See also* Ama-no-minaka-nushi; Amaterasu; Yomi.

Takami-Musubi (Shinto) Japan. *See also* Taka-Mimusubi.

Takaro (New Hebrides) *see* Tangaroa.

Take (A) (Japan) *see* Susanowo; Take-mi-kazuchi.

Take (B) (Polynesia)
Also known as: *Tachen.*
Take is the point below Vari in the creation tale. It is the stem of the coconut (Avaiki) which is the universe. The god Tamaa was said to have planted the first coconut tree. Take is also a general term the Polynesians use for god. *See also* Avaiki; Vari.

Take-mi-kazuchi *Take-mika-zuchi, Take-mikazuchi* (Shinto, Japan)
The great general Take-mi-kazuchi (Valiant August Thunder) was appointed by the sun goddess Amaterasu and other deities to travel to earth on a mission. He was given a companion for his journey, the god of fire, also known as the genius of weapons, Futsu-nushi (Sharp Cutting Lord). The task of the thunder deity and the fire deity was to force the submission and abdication of Onamuji, or some say, Okuni-Nushino-Mikoto from the throne of Izumo province. It had been decided that Ninigi, the grandson of Amaterasu, was to be the new ruler. Take-mi-kazuchi's brother, Aji-suki-takahikone, was also a thunder deity. As an infant, he had to be carried up and down a ladder and put in a boat that sailed around the islands to subdue his screaming and hollering. He later became the father of the rain god Taki-tsu-hiko (Prince Cataract). Another god widely worshiped was Kami-Nari, also known as Raiden, the god of rolling thunder. An earthquake god appeared in later times (approximately C.E. 599) named Nai-no-kami. The boat and the ladder represent the connection of thunder between heaven and earth. An earthquake could be depicted as thunder under the earth. Kami-Nari is described as having horns on his head and tusks in his wide mouth. A tree split by lightning was venerated and could not be cut down. *See also* Amaterasu; Izanagi; Ninigi; Okuni-Nushino-Mikoto; Raiden; Susanowo; Taki-tsu-hiko.

Take-mi-musubi (Japan) *see* Takami-musubi.

Take-mika-zuchi (Japan) *see* Take-mi-kazuchi.

Take-mikazuchi (Japan) *see* Take-mi-kazuchi.

Take-Minakata (Japan)
It is possible that Okuni-Nushino-Mikoto, who is one of the Shichi Fukujin (seven gods of happiness), is the father of Take-Minakata and Koto-shiro-nushi. If so, they would have a sister, Shita-teru-Hime, who married Ame-no-Wakahiko, the renowned warrior god. *See also* Okuni-Nushino-Mikoto.

Takehaya Susanowo (Japan) *see* Susanowo.

Takemiskazuchi no Mikoto (Japan)
He is a warrior god represented by the deer.

Takhma Urupi (Persia) *see* Hoshang.

Takhmoruw (Persia) *see* Hoshang.

Taki-mi-Mushubi (Japan) *see* Ame-no-Oshido-Mimi; Taka-Mimusubi.

Taki-tsu-hiko (Shinto; Japan)
Also known as: *Prince Cataract.*
God of waterfalls. Taki-tsu-hiko, the son of the thunder god Aji-suki-takahikone and nephew of the thunder god Take-mi-kazuchi, dwells on the mountains and is the god of waterfalls. West of the Kaminabi mountain there is a stone that became the soul of Taki-tsu-hiko. Taka-okami, a rain deity, also dwells in the mountains. In some renditions, he also produces snow. Another rain god, who produces snow and dwells in valleys, is Kura-okami (dragon god of the valleys). Kura-okami and his two brothers, Kura-yama-tsumi and Kura-mitsu-ha, were born from the blood of their brother, the fire god Kagu-tsuchi, when he was slaughtered by their father Izanagi. Another deity, Oho-iwa Dai-myo-jin also known as Oiwa Daimyojin, was known as the great god of the rock. There is also a goddess of clay and earth known as Hani-Yasu-no-Kami and a god of earth, Ohonamochi. Taki-tsu-hiko was said to be in the shape of a rock. Prayers are sent to him for rain in times of drought. In some depictions the deities appear as serpents or dragons. *See* Kura-okami for details of his origins. In early times, red, black or white horses were sacrificed to bring rain and red horses to stop rain. *See also* Take-mi-kazuchi.

Takiri-bime-no-Mikoto (Japan) *see* Amaterasu; Three Goddesses of Munakata.

Takitsu-hime-no-Mikoto (Japan) *see* Three Goddesses of Munakata.

Takitu-pime-no-Mikoto (Japan) *see* Three Goddesses of Munakata. *See also* Amaterasu.

Takkanna (Australia) *see* Mar.

Takoroa (Polynesia) *see* Rangi.

Takotsi Nakawe (Huichol People, Mexico)
Also known as: *Grandmother Growth.*
Earth goddess. Agricultural goddess. Takotsi Nakawe is the giver of long life. She is the mother of the armadillo, peccary and bear.

Takshaka *Kuvera, Vaisravana* (Hindu; India)
Takshaka is the king of the serpents known as Nagas and Nagis. He and the other serpents were instrumental in protecting the other gods and mortals. They forbid spiritual truths to those not worthy and grant them to the deserving ones. The sage Astika, son of the serpent goddess Manasa, intervened to save Takshaka from death. Injury or death from a snake bite can be avoided if the person remembers to utter Astika's name when bitten. *See also* Kuvera; Lokapalas; Manasa; Nagas; Yakshas.

Taku-hata Chi-hata Hime (Japan) see Ama-no-minaka-nushi; Kami-Mimusubi.

Takuskanskan (Dakota People, North America)
"The Moving God" who is the wind and a trickster.

Talaus (Greek)
Talaus is the Argonaut son of the king of Argos, Bias, and

www.ebook3000.com

1. Expand your awareness all the way to the back. Move the arms toward the universe behind you.
2. Touch the universe; scoop up the fire. Activate the Kidney Fire. Maintain your awareness in the Tan Tien and expand smiling out to the universe. The energetic spiral glows in the Tan Tien. Spiral in the heart, spiral in your crown and spiral in the universe.

Heart Fire

Raise your hands up under your armpits, and feel yourself holding the two fireballs. Touch the heart by extending the fingers energetically in from the sides; feel your hands extending into your heart and very far away. Activate the Heart Fire.



Fig. 3.30 *Activate the Heart Fire.*

1. Move your hands up under your armpits and extend your fingers deep into your heart and very far away.
2. Tan Tien and the Universe: you are connecting to the 'charger,' charging more fire into yourself.
3. Feel your heart soft in the center as you smile down. Feel the warmth of the fire energy of love, joy and happiness in the heart.
4. You feel the connection with the unconditional love in the universe as you keep your heart consciousness in your Tan Tien and extend your awareness out to the universe.

Pero, who is the daughter of Neleus and Chloris. His children are Adrestus, who became the king of Argos, the leader of the Seven against Thebes and the leader of the Epigoni; Aristomachus, Astynome, Eriphyle, Hippomedan, Mecisteus, Metidice, Parthenopaeus and Pronax. *See also* Abas (B); Adrestus; Bias.

Taliesin (British) *see* Amergin; Bran.

Talisman

A talisman is an object usually engraved with figures and generally worn as a charm. The talisman is thought by believers to possess magical powers. *See also* Ab; Benten; Buto; Ilmarinen; Kagu-tsuchi; Runes; Tuatha De Danann; Vainamoinen.

Tallai (Canaan, Syria, Ugarit)

She is the daughter of Baal who symbolizes dew and rain. Her sisters are Arsai, who symbolizes the earth, and Pidray, a nature goddess who symbolizes light.

Talus *Talos* (Greek)

Talus is the son of Perdix and the brother of Daedalus, the inventor. Jealousy led him to kill his brother Daedalus. He was then turned into a partridge by the goddess of the hunt, Athena. *See also* Daedalus.

Tama-Yori-Bime (Japan) *see* Jimmu Tenno; Toyo-Tama-Bime.

Tamagostad (Aztec People, Nicaragua)

Also known as: Possibly *Oxomoco.*

Creator. He is the husband of Zipaltonal (also known as Cipattonal). They are the ruling deities of Ecalchot, the wind god; Ciaga, the water god; Quiateot, the rain god; Misca, the god of traders; Vizetot, the god of famine. The gods were part of creation. They live in the heaven of good souls. Some writers say Tamagostad and Zipaltonal or Cipattonal are the same as Oxomoco and Cipactonal. On the other side of heaven is the realm of Mictanteot ruled by the goddess of volcanoes, Masaya. *See also* Oxomoco.

Tamanduare (Tupi-Guarani People, Brazil) *see* Timondonar.

Tamar (Hebrew)

She is equivalent to Ishtar (q.v.). *See also* Inanna.

Tamats (Mexico)

Also known as: *Elder Brother.*

God of wind and air. He is a messenger of the gods and the conqueror of the underworld people. A shape changer deity, he sometimes appears as a wolf, a deer or even a pine tree.

Tamazcalteci (Aztec)

A name for Cihuatcoatl and Tonantzin. *See also* Tonantzin.

Tamek-Vui (Finnish) *see* Kiyamat-Tora.

Tamendonar (Tupi-Guarani People, Brazil) *see* Timondonar.

Tammus (Greek) *see* Harpies.

Tammuz (Assyro-Babylonia)

Also known as: *Ab-u, Adonai, Damu-zi-abzu* (Tammuz of the Abyss), *Dao, Daonus* (the instructor of agricultural arts), *Dumuzi, Enlil* (sometimes), *Es-u, Isir, Sibzianna* (shepherd and hunter), *Tamoza, Thammuz.*

Possibly a tree god, originally. Vegetation god. God of the spring sun. God of crops. Tammuz is the son of Ningishzida and Etuda. He is the brother/lover of Ishtar in their youth. Tammuz became the ruler of Uruk. The mythology of Tammuz and Ishtar is closely related to the earlier mythology of the Sumerian Dumuzi and Inanna. A major difference occurs when Dumuzi descends into the underworld: it is because an angry Inanna allowed the demons to take him there as her substitute. In the Tammuz tale, a grieving Ishtar attempted to rescue Tammuz from his descent into the underworld. More aggressive than her earlier counterpart, Inanna, Ishtar threatened to let the dead free to terrorize the living if she was not allowed to enter the underworld. When she was admitted, she did not return immediately. Papsukkal, the vizier of the great gods, earlier made it clear what would happen if Ishtar did not return to the upperworld. He appealed to Ea for her release. Ea created the eunuch Asushunamir to enter the lower realm to persuade Ereshkigal, ruler of the underworld and sister of Ishtar, to give him the life-water bag. He charmed the goddess, who then ordered her vizier Namtar to give him the bag. During the yearly summer solstice, it was Ishtar who had Tammuz torn to pieces and thrown into the sea. His absence caused a barren earth, and her grief. Finally, Ishtar agreed that Tammuz would spend six months of the year in Arallu (the underworld) with her sister Ereshkigal, who was the queen of the region, and six months with her (Ishtar) in the upperworld. In the end, with his father Ningishzida, he guarded the gate of Anu, in the city of the gods. His festival is the Ta-uz. Sometimes he appears in goat form. The cock is sacred to Tammuz. Compare to: Aa, Abu, Adon, Adonis, Angus, Cybele, Asushunamir and Gula. Tammuz is known as the counterpart of the Vedic deity Soma (q.v.). Both deities are associated with the waxing and waning of the moon. As a harvest god, Tammuz died each winter and was reborn each spring. Compare the agricultural myth of Tammuz to the Hittite god Telepinus. Compare to Boann and Dagda (Celtic). Tammuz is associated with Adonis (Greek), Eshmun (Phoenicia), and Osiris (Egypt). *See also* Aa; Anu (B); Arallu; Damkina; Dumuzi; Ea; Enlil; Inanna; Ishtar; Marduk; Mirsu; Namtar; Ningishzida; Papsukkal.

Tamoanchan (Aztec People, Mexico)

Paradisiacal place of origin. It was to the mythical city of Tamoanchan that Quetzalcoatl brought the "precious bones" from which the first men were made by Quetzalcoatl, and the goddess Quilaztli. This is the place of origin of the "Mother of the Deities," Teteoinnan. Itzpapalotl, the "Obsidian Butterfly," is a goddess of Tamoanchan. Tamoanchan is represented by a tree in blossom emitting blood. *See also* Ciuateteo; Itzpapalotl.

Tamon (Japan) *see* Bishamon.

Tamon-Tenno (Japan) *see* Bishamon.

Tamontennu (Japan) *see* Bishamon.

Tamoza (Babylonian) *see* Tammuz.

Tamra (India)

Grandmother of the Garudas. *See also* Garudas; Kasyapa.

Tan (Egypt) *see* Ament; Amentet; Amenti.

Tanabata Hime (Japan) *see* Amatsu-Mikaboshi.

Tanabata Tsume (Japan) *see* Amatsu-Mikaboshi.

Tanaoa (Polynesia)
Also known as: *Taaroa Kanaloa* (Hawaii), *Tangaroa.*
A god of darkness or hell, or a god of thunder. He came from Chaos and produced Ono. In another version of his legends, he and Mutuhei (darkness and silence) ruled Po, the primeval abyss. Atea, the god of light, is in constant opposition to Tanaoa. *See also* Atea; Ono; Qat; Rangi; Ta'aroa; Tangaloa.

Tandu (Hindu; India)
Tandu is one of Shiva's principal attendants. He is primarily a teacher of mimicry and dancing.

Tane (New Zealand, Polynesia)
Also known as: *Kane* (Hawaii), *Tane, Tane-mahuta, Tawhiri, Tawhiri-ma-tane, Ti'i.*
Creator. God of forests and creatures of the forest. Tane is the son of Rangi, the sky father, and Papa who is mother earth. His siblings are Olo, Oro (or Koro), and some say Tu. Others say Rangi and Papa were his children, and that he was the god of darkness or the underworld. Still others say his children were twin boys (Tonga-iti and Tangi-ia) and that his consort was Tangia. Some say his wife was Hine (Hine-hau-one) who later became Po, the goddess of darkness. Tane and the goddess Vatea produced the triad of Tangaroa, Rongo, and Tane or the pair Tangaroa and Tiki. In one myth, we find Tane, after many trials with various female deities that gave unsatisfactory results, mating with Hine-ahu-one, who gave birth to the egg, known as Tikitohua, that resulted in the bird ancestor of all birds. Her next child was Tiki-kapakapa who was the mother of the first human child. Another legend relates that when Tane went to heaven, he left the rainbow as a reminder of his presence on earth. Man was created from red earth and the spittle of Kane. He was also said to be part of the triad of Ku and Lono. The three breathed life into man and made woman from his bones. The name they gave man was Tiki or Tiki-aw-a-ha and the woman Iowahine. One other version tells of Tane shaping a woman out of earth and mating with her, producing Hine-itau-ira with whom he also mated. When she found out he was her father she killed herself and went to the underworld where she became Hine-nui-te-po, the great goddess of the night (q.v.). Tane is sometimes associated with the war god Oro. Compare to Kane (Hawaii). *See also* Hine; Maui; Papa; Rangi; Ta'aroa; Tawhiri-ma-tane; Tu.

Tane-mahuta (Polynesia) *see* Tane; Tawhiri-ma-tea.

Tanen (Egypt) *see* Tanunen.

Tangaloa (Polynesia, Samoa)
Also known as: *Lowa, Tangaroa.*
Pre-existent creator. Sea god. He lived in the Void with his messenger, the bird Tulli. Tulli flew over the vast expanse of waters searching for a place to rest. Tangaloa threw down a rock which became one of the Samoan Islands, Manu'a. Tangaloa created other islands, including Tonga and Fijii. Tulli complained that he needed shade on the islands, so Tangaloa sent the "Peopling Vine." It was from this plant that the first man was made. In another version, Tangalo was born from his mother's head or he came from the Po (The Void). His sons were Vaka (Laka) and Ahu (Tupo). Called "god on high" he was the deity of fair-haired people, and light and plenty. He is a god who re-created the earth after it was destroyed by the flood. Elsewhere, we read of Tangaloa as a messenger between the high gods; Tama-poulialamafoa (King of Heaven), Tangaloa-eiki (Celestial Chief), Tangaloa-tufuga (Celestial Artisan), and Tangaloa-atu-logo-logo (Celestial Messenger). In this case he created the earth on orders from those above. In one of the Samoan legends there was a great flood that covered the earth. Only two mortals (Seve and Pouniu) temporarily saved themselves by swimming. Tangaloa saw their plight and sent two men down with hooks. They drew Samoa from under the sea for the mortals' refuge. Tangaloa is also credited for raising the sky. *See* Tangaroa, Timo-taata, Ihoiho, Taaroa and Tiki, all creator gods of Polynesia and the surrounding islands. The deity, Lowa of the Marshall Islands, may have been a cognate of Tangaloa. *See also* Laka; Po; Qat; Takaro; Tane; Tangeroa; Qat.

Tangara (Greek)
She is the daughter of Enarete and Aeolus of Magnesia, who is the son of Hellen and Ortheis. *See also* Aeolus (A); Canace; Enarete; Salmoneus.

Tangaroa (Polynesia, Samoa, Tahiti, Society Islands, Marquesas, New Zealand)
Also known as: *Kanaloa, Taaroa, Tabu-eriki, Tabu-Eriki, Tanaoa, Tangaloa, Ta'oroa, Te Temu, Tonga-iti, Tongaiti, Upao, Vahu.*
Creator. God of the ocean and of fishers. God of house builders and carpenters. One myth tells of this deity creating earth by throwing rocks into the sky, or throwing a rock from heaven to earth; the other version is that he created earth by breaking the primordial egg into two halves which become earth and sky. A third version said that he was son of Rangi and Papa (or Vatea and Papa), and brother of Rongo, and god of fish and reptiles. Also the father of Tu-te-wehi (Tu-te-wanawana) and Ika-tere, whose mother was Punga. In some legends Rangi and Papa were once known as a pair, Kane and Kanaloa. One story associates him with a maiden named Vinmara, who in turn resembles the Malaysian sky maiden, Widadari. The name Vinmara might be associated with the Sanskrit Vindhyadara. In one legend Papa (Papa-tu-a-nuku) was the wife of Tangaroa, but was unfaithful and went to Rangi for solace. This caused a fight between Rangi and Tangaroa. Tangaroa is sometimes confused with Tane. He is possibly related to Roma-Tane, the Polynesian god of paradise. He is similar in some respects to Qat of Melanesia and to Tagaro and Takaro. *See also* Faumea; Maui; Tane; Tangaroa.

Tangere (Tartars of the Volga) *see* Tangri.

Tango (Polynesia)
Also known as: *Support.*
One of the children of Vari-ma-te-takere, the great mother. His land is called Enua-kura. *See also* Vatea.

Tangri (Altaic)
Also known as: *Tangere* (Tartars of the Volga), *Tengeri* (Buryats), *Tengri* (Mongols and Kalmyks), *Tingir* (Beltirs).

www.ebook3000.com

This celestial, omniscient god was not worshipped in temples. It is generally thought that he was not represented in the form of a statue. He was offered prayers and sacrifices. All natural disasters were thought to be signs of his discontent. Later, the Mongols and Buryats referred to numerous gods by the name Tangeri. The Tangeri were gods who ate the fruits of the World Tree. *See also* Bai Ulgan.

Tanit *Tanith* (Carthage, Phoenicia)
Also known as: *Caelestis, Juno Caelestis, Tlanit Pene Baal.*
A celestial or lunar goddess. Tanit is the wife or consort of Baal Hammon. She is identified by some with Juno Caelestis (Juno) of the Romans. Her symbol is a circle inside a crescent supported by a blunt cone, similar to Hathor's symbol. She is sometimes linked with Ishtar, Ashtart and Astarte. Sometimes, she is associated with Artemis.

Tanith (Carthage) Chief goddess of Carthage.

Tanka (Oglala People, North America) *see* Kitcki Manitou.

Tanngniostr (Teutonic) *see* Tanngnost.

Tanngnost (Norse; Teutonic)
Also known as: *Tanngniostr, Tooth Grinder.*
Deified animal. Tanngnost is one of the two goats who pull Thor's chariot. The other goat is named Tanngrisni.

Tanngrisni (Norse; Teutonic)
Also known as: *Gat Tooth, Tanngrisnr.*
Deified animal. One of the goats that pulls Thor's chariot. The other is called Tanngnost.

Tanngrisnr (Teutonic) *see* Tanngrisni.

Tannin (Semite) *see* Leviathan; Rahabh.

Tano (Ashanti People, Africa)
God of rivers and thunder. Tano is the son of Asase Ya and Nyame. His brother and rival is Bia. He is often described as being an antelope when he is associated with his opponent, Death. *See also* Abosom; Asase Yaa; Bia; Nyame.

Tantalus (A) *Tantalos* (Greek)
Sun deity. Tantalus, king of Lydia, is the son of Zeus and Pluto. He married Dione and became the father of Pelops, Niobe and Broteas. A wealthy king, he had a banquet for the deities and decided that he would test their powers and reveal a few of their secrets. He cut his infant Pelops into pieces and served him for dinner. All but Demeter realized what he had done. His angry father punished him in Tartarus, the lowest region of the underworld, with a raging thirst for eternity. Standing under a loaded fruit tree in water up to his chin, Tantalus could never quite either grasp the fruit or drink from the water. Compare his punishment to the punishment of Sisyphus and Ixion. *See also* Amphion; Demeter; Erinyes; Niobe; Oenamaus; Pelops; Tantalus (B).

Tantalus (B) (Greek)
Also known as: *Tantalos.*
Tantalus is the son of Amphion and Niobe.

Tantalus (C) (Greek) He is the son of Thyestes and Aerope.

Tantalus (D) (Greek)
He was married to Clytemnestra and was killed by Agamemnon. Tantalus (C) and (D) are different versions of the same person. *See also* Aerope; Agamemnon; Clytemnestra.

Tanunapat (India) "Son of Self." *See also* Agni.

Tanunen (Egypt)
Also known as: *Ta-tanen, Tanen, Tathenen, Tenen, Tetenen.*
Local god of Memphis. Tanunen is sometimes identified with Ptah, who has a human form and wears two ostrich feathers and two ram's horns on his head. He could be an aspect of Ptah as an earth god. *See also* Ptah.

Tao (China)
Tao is the universal energy and primeval cosmic force. *See also* T'ien.

Tao Chun (China) *see* Ling-Pao T'ien-Tsun.

Ta'oroa (Polynesia) *see* Tangaroa.

Tapa-Loka (India) *see* Loka.

Tapati (Hindu; India)
Tapati, meaning "The Hot One," is the daughter of Chhaya the shade, and Surya the sun. Surya did not know that his wife Sanja had left him and had used Chhaya as a substitute wife. A lovely golden colored nymph, Tapati lived in the celestial realms. She has two brothers, Shani and Savarni. Her father arranged that king Samvarana would get lost in the forest and seemingly come upon Tapati accidentally and fall in love with her. The events transpired accordingly with help from the love god Kama. Tapati, however, vanished when the king spoke to her of his romantic feelings. Thoroughly smitten, he went in search of his heart's desire. She appeared to him in a vision and told him that she could not be his mate without her father's permission. He worshipped the sun for twelve days before his request was granted. Surya had a sage escort his daughter to earth and she married the king. Leaving his kingdom behind, he took his bride to the mountain forests where they lived for twelve happy years. While away, anarchy spread throughout his realm and the couple was forced to return to restore harmony. Tapati and Samvarana were the parents of Kuru, an ancestor of the Pandavas and Kauravas. *See also* Kama; Kauravas; Pandavas; Sanja; Surya.

Tapio (Finnish)
Called the "Golden King," he is a woodland lord. His family is composed of his wife, Mielikki, and children Nyyrikki and Tuulikki. His home is called Tapiola. Tapio is an old man with a brown beard, wearing a high hat of fir cones and a coat of tree moss.

Taqiacopa (Inca) *see* Taguacipa; Virococha.

Taquatu (Tierra del Fuego)
Also known as: *Yaccy-Ma* (possibly).
Taquatu is an invisible giant spirit. He travels in his canoe over the water and in the air. If you are idle and not alert, he could take you aboard his canoe and carry you far from home. *See also* Yaccy-Ma.

Tar-Ata (Middle Eastern)
Tar-Ata is a name for the goddess Atargatis (q.v.).

Tara (A) (Brahmanic, Hindu; India)
Also known as: *Kali, Taraka.*

Tara, a stellar deity, is the mate of Brihaspati who represents Jupiter, or Soma (the moon), and the mother of Buddha (Mercury). In some legends, she married her brother Sugriva. She is a furious destroyer and slayer of evil beings. On one occasion, the god Soma (the moon), intoxicated with power, abducted Tara (the star). Brihaspati, a learned man who instructed the gods, attempted to rescue his wife unsuccessfully. Soma would not relinquish the goddess even when instructed to do so by the great Brahma. A war, known as the Tarakamaya, erupted with Tara leading the gods and Soma the demons. In some interpretations, Brihaspati formed the party of the gods and fought against Soma. During this encounter, Shiva slashed Soma's face in half with a trident. The goddess appealed to Brahma for assistance and finally Soma gave his captive her freedom. Pregnant, she returned to her husband. He refused to accept her until after the child was born. A miraculous birth occurred immediately. The male infant was so beautiful that Soma and Brihaspati both claimed to be the father. Brahma asked the goddess who was the father of the child and she replied that it was Soma. Soma, as the lord of constellations, embraced his son and named him Buddha. Buddha later became the founder of the lunar dynasties. (This Buddha is not Gautama, the great Buddha of the Buddhist tradition.) Tara is not to be confused with Rama's monkey general's wife of the same name. Tara is a gracious and lovely figure, but when she is depicted as an aspect of Kali, the wife of Shiva, she appears as a dark goddess wearing skulls. *See also* Brahma; Brihaspati; Kali; Shiva; Soma; Sugriva.

Tara (B) (Buddhist, Jainist, Lamaist; Country of origin, India)
Also known as: *Bhrkuti* (Yellow Tara), *Bribsun* (Green Tara), *Dol Jyang* (Green Tara, Tibet), *Dolma* (Tibet), *Ekajata* (Blue Tara), *Hlamo* (Tibet), *Janguli, Konjo* (White Dolma, China), *Kurukulla* (Red Tara), *Kwan-Yin* (China), *Mamaki, Nila Tara* (Blue Tara), *Parnasavari, sGrol-mas* (Tibet), *Shveta Tara* (White Tara), *Sitatara, Syamatara* (Green Tara), *Tara-Amba, Tara-Dharani, Tara Utpala* (Green Tara), *Tara White* (Nepal), *Taraka, Wen-Ch'en* (White Tara, China).

In early times, Tara, a stellar goddess, was invoked for safe passage across the seas. Later she became the protector of all mortals as they crossed the ocean of existence. She is the destroyer of fears, remover of obstacles and bestower of boons. She is the wife and female counterpart of Avalokitesvara in his role as the Savior from the Eight Perils. As Tara White and Tara Green she is the spouse of Avalokitesvara and shares his qualities. She is the three-eyed goddess of daytime depicted with a wheel on her chest, playing a lute. She is usually shown seated but occasionally, she is in a standing or dancing position, dressed and crowned like a boddhisattva. As Tara White and Tara Green she is kind and gentle. As Tara Yellow, Red and Blue she is threatening. Tara was born from tears which fell from Avalokitesvra's eye as he gazed with pity upon the suffering world. As Tara Utpala (Green Tara), she helps her believers through the night. Utpala is the most popular aspect of Tara in Tibet. Sometimes she is shown with a rosary and a book. Often her right hand is in the varada mudra which is the charity pose, with the arm pendant and all fingers extended outward. Her left hand is in the vitarka or argument mudra with the arm bent and all fingers extended upward, except the index finger, which touches the tip of the thumb. Sorrow is relieved in her aspect as Tara-Dharani. As Tara-Amba she represents the "Mother." As Nila Tara she is the consort of Akshobhya, the second Dhyani Buddha. She holds a half-closed water-lily or lotus, often blue, in her left hand. As the consort of Amoghasiddhi her mount is a roaring lion and her emblems are the kapal and visvavajra. Tara has one hundred and eight names. She is comparable to Kuan Yin (China). Princess Konjo was one of two princesses who are thought to have introduced Buddhism to China. She is said to be an incarnation of the White Dolma and is named Wen-Ch'en. She married the King of Tibet, Srong-btsangombo (also spelled Srong-tsan-gampo). *See also* Amoghasiddhi; Avalokitesvara; Chandamaharoshana; Dhyani Buddhas; Khadga Jogina; Vairocana.

Tara (C) (India) *see* Bali (A).

Tara-Amba (India) *see* Tara (B)

Tara-Dharani (India) *see* Tara (B).

Tara Utpala (India) *see* Tara (B)

Tara White (Nepal) *see* Tara (B).

Taraka (India)
Taraka is a she-demon who lives in a forest near the Ganges River. She feasts upon travelers. *See also* Karttikeya; Tara (B).

Tarakamaya *Taraka-Maya* (India)
A divine war. *See also* Brihaspati; Tara (A).

Taramis (Celtic) *see* Taranis.

Taranga (Polynesia)
Taranga is the mother of the trickster-god, Maui. When he was an infant, she cradled him in a top-knot of her hair. *See also* Maui; Tu-matauenga.

Taranis *Taramis* (Celtic)
"The Thunderer." God of thunderstorms. The enemies of Taranis were put in a cage and burned according to one source. It is thought that this may be an exaggeration, although it has been said that this ritual was practiced by the Gauls in the first century B.C.E. The attribute of Taranis is the wheel. *See also* Esus; Jupiter; Odin.

Tarapaca (Peru) *see* Virocochа.

Taraxhippos (Greek)
Taraxhippos is the name of the ghost of Glaucus of Corinth. *See also* Glaucus.

Tareya-Wagon (Mohawk People, North America)
Supreme deity. The god who liberated the Kaniengehaga, better known as the Mohawks, from confinement beneath the surface of the earth. He then led them to the Valley of the Mohawk on the surface of the planet.

Tarhuhyiawahku (Iroquois People, North America)
High god. Name of the giant holder of the heavens.

Tari-penu (India) *see* Bura-penu.

www.ebook3000.com

Tarik (Persian)
Tarik is one of the evil demons created by Ahriman to be his assistant. *See also* Darvands.

Tariki (India) "Delivering." *See also* Devi.

Taromaiti (Persia) *see* Spenta Armaiti.

Tartaros (Greek) *see* Tartarus.

Tartarus *Tartaros, Tartus* (Greek)
Also known as: *Erebus, Hades, Hell.*
Underworld. Tartarus, the final stop for the souls of wicked mortals, is the deepest part of the underworld, a dark and abysmal place often referred to as Hades' kingdom. It is surrounded by black rivers, a bronze fence and iron gates. The guards are either the Hecantonchires, who are three giants, each with fifty heads and one hundred arms, or Cerberus, the multiheaded dog who never sleeps. Originally Tartarus was a prison for gods who had been ousted from Olympus and many Titans who were the enemies of Zeus ended up in this hell. One must cross the rivers Acheron, Cocytus, Phlegethon, Lethe and Styx under the employ of Charon, the ancient ferryman, to reach this destination. There are several points of entry to the final stop: Epirus, Heraclea Pontica, and Colonus. Erebus, also a place where souls go to die, is frequently used as a synonym for Tartarus. The personification of Tartarus, also known as Tartarus, was born out of Chaos, as were Gaea (the earth personified) and Eros (love personified). By his sister Gaea, Tartarus became the father of Typhoeus and possibly the immortal monster Echidna. Compare Tartarus to Jigoku and Yomi (Japan) and Tuat (Egypt). *See also* Acheron; Aither; Cerberus; Charon; Cocytus; Dis; Enceladus; Erebus; Gaea; Hades; Hecatonchires; Hell; Lethe; Phlegethon; Pluto; Styx; Typhon (A).

Tartus (Greek) *see* Tartarus.

Tarutius (Etruscan) The wealthy spouse of Acca Larentia.

Tashmetrum (Sumer)
Goddess of writing. She is the wife of Nabu, the god of writing.

Tashmetum *Tashmetu* (Sumer) *see* Nabu.

Tashmishu *Tasmisu, Tasmisus* (Hurrian, Hittite) *see* Shaushka; Teshub.

Tasmisu (Hurrian, Hittite) *see* Tashmishu.

Tasmisus (Hurrian, Hittite) *see* Tashmishu.

Tathagata (Nepal) *see* Buddha; Dhyani Buddhas; Nyorai; Sahasrabhuja; Sakyamuni.

Tathagata Mahavairokana (India) *see* Dainichi-nyorai.

Tathenen (Egypt) *see* Tanunen.

Tatjenen (Egypt)
Tatjenen is an early god of the Memphite region who was later identified with Ptah of Memphis. He is shown as a bearded man wearing a crown with two feathers and a solar disc above a pair of ram's horns. *See also* Ptah.

Tatsuta-Hiko (Japan) *see* Tatsuta-Hime.

Tatunen (Egypt)
"One, the Maker of Mankind." Creator. Tatunen is the same as Tanen (q.v.).

Tatzitzebe (Choco People, Columbia, South America)
High god. *See also* Caragabi.

Taueret *Ta-urt, Tueris* (Egypt)
Also known as: *Apet, Opet, Rerit, Rert, Rertu, Ririt, Theoris* (Greek), *Tuart.*
Hippopotamus Goddess. Goddess and Protector of Childbirth. Goddess of Vengeance. Underworld Goddess. Protector women and their offspring during their infancy. During the New Empire worship of Taueret was so popular in Thebes that children were named after her. Her images were found in many homes. She is portrayed as a hippopotamus with large udders who is standing upright on her hind feet. One hand is on the Sa (life preserver). As the goddess of vengeance, she has the body of a hippopotamus and the head of a lioness. She brandishes a dagger. Sometimes she carries a huge crocodile with open jaws on her shoulders. Taueret is associated with Bes (q.v.) *See also* Apet; Sa; Theoris.

Taurt (Egypt) *see* Taueret; Theoris.

Tauru (Persia) *see* Taurvi.

Taurvi *Tauru* (Zoroastrian; Persia)
The archdemons Taurvi and Zairishi are the opponents of the goddesses Haurvatat and Ameretat. *See also* Daevas; Haurvatat; Zairishi.

Taus (Middle Eastern) *see* Azazel.

Tauthe (Babylonia) *see* Apsu; Belus (C); Tiamat.

Tawals (Polish) *see* Datan; Lawkapatim.

Tawendonare (Brazil) *see* Tawenduare.

Tawenduare *Tawendonare* (Tupi-Guarani People, Brazil)
God of daylight. Tawenduare is the constant foe of his brother Arikute, god of night and always the victor in their struggle. *See also* Arikute.

Taweskare (North America) *see* Yoskeha and Taweskare.

Tawhaki (Hawaii, Polynesia, New Zealand)
Also known as: *Kaha'i* (Hawaii), *Tafa'i* (Tahiti).
Maori god of thunder and lightning. Tawhaki is the grandson of the fighter Kaitangata and the cannibal chieftain from the sky, Whaitiri. He is the son of Hema and a goddess. His brother is Kariki (known as Aliki in Hawaii). Many stories of Tawhaki revolve around the adventures he shares with Kariki as they search for their father. Hema had been abducted by the goblins, beaten unmercifully and thrown into a pit for trespassing on their property. Tawhaki and his wife are the parents of Wahieroa, who in turn had a son, Rata. Tawhaki caused the great flood either by stamping on the floor of heaven which cracked allowing the waters to flood the earth, or by causing his mother's excessive weeping by his actions. Another version says Tawhaki caused the flood as revenge on an attempt to kill him. There is a version that tells of Tawhaki and his brother searching for their father, Hema, in the sky where they ran into

Whaitiri, the cannibal cheiftain, who is his grandmother in many myths. Kariki was killed by falling from the spider web that leads to heaven. Some versions say Tawhaki found his wife in the upperworld and stayed there as a deity of lightning. Others say he brought his wife (unnamed) to earth where she bore him a son, Wahieroa, who in turn married and fathered Rata. In a mixed up tale, Wahieroa was killed by Matuku (a cannibal giant) before Rata was born. There are numerous comments about the attractive, gleaming red skin of Tawhaki. He was irresistible to women. He is sometimes shown as bird. His exploits are similar to those of Maui and Tane. In Maori myth, Tawhaki is the youngest son of the goddess Urutonga ("South West") and Hema. *See also* Kaitangata; Rata; Wahieroa.

Tawhiri (Polynesia) *see* Tane; Tawhiri-ma-tea.

Tawhiri-ma-tane (Polynesia) *see* Tawhiri-ma-tea.

Tawhiri-ma-tea *Tawhiri-ma-tane* (Polynesia)
Also known as: *Tane, Tawhiri.*

A god of winds, hurricanes and storms, he is the son of Rangi, the sky father, and mother earth, Papa. His brothers are Tu and Tane. He opposed the separation of his parents, Rangi and Papa, by Tane, to create the world. To show his displeasure, Tawhiri caused huge storms and vicious whirlwinds which destoyed his brother Tane's forests. This in turn caused the perpetual war between Tane and Tangaroa. Tawhiri-ma-tea might have caused the destroying deluge. He is the father of thirteen children, two who are strong winds and eleven who are clouds. Some of the children's names are A-Kahiwahiwa (Fiery Black Clouds), Ao-Kanapanapa (Glowing Red Clouds), Ao-Nui (Dense Clouds), Ao-Pakakina (Wildly Drifting Clouds), Ao-Potango (Dark Heavy Clouds), Ao-Pouri (Dark Clouds), Ao-Roa (Thick Clouds), Ao-Takawe (Scurrying Clouds), Ao-Whetuma (Fiery Clouds), Apu-Hua (Fierce Squalls) and Apu-Matangi (Whirlwind). *See also* Ao-Pouri; Ao-Toto; Papa; Rangi; Tane; Tangaroa.

Tawiscara *Taweskare, Tawiskaro, Tawiskorong* (Huron, Iroquois People, North America) *see* Yoskeha and Taweskare.

Tawiskaro (North America) *see* Yoskeha and Taweskare.

Tawiskorong (North America) *see* Yoskeha and Taweskare.

Taygete (Greek)
She is one of the Pleiades and one of the great god Zeus' innumerable lovers. From their union, she had a son, Lacedaemon (q.v.). *See also* Pleiades.

Tchabu (Egypt)
Tchabu, the god of drink, is mentioned in a hymn to Hapi, the god of the Nile, along with the god of corn, Nepra and Ptah.
See also Hapi; Ptah.

Tcheft (Egypt)
Tcheft is a title for the goddess Isis as the goddess of food that is offered to the gods.

Tchemtch-hat (Egypt) *see* Aai.

Tcheser-Tep *Teheser-Tep-f* (Egypt)
A serpent demon mentioned in the magical formula of Unas. *See also* Assessors; Shesemu; Shesmu.

Tchet-s (Egypt)
A winged monster serpent in the eleventh sector of Tuat. Probably the same as Tcheser-Tep.

Tcolawitze (Hopi People, North America)
Either a god of fire or fire itself.

Te-aka-ia-oe (Polynensia) *see* Avaiki; Vatea.

Te-manava-roa (Polynesia) *see* Avaiki; Vatea.

Te-Po-ma-Te-Maki (Oceanic)
This is another name for one of the first people. *See also* De Babou and De Ai; Nareau.

Te-tangaengae (Polynesia) *see* Avaiki; Vatea.

Te Tumu *Te Temu* (Polynesia) *see* Rangi; Ta'aroa; Tangaroa.

Te-vaerua (Polynesia) *see* Avaiki; Vatea.

Tebati (Egypt) *see* Aai.

Tebi (Egypt) A name given to one of the solar gods.

Tecciztecatl *Teccuciztecatl, Tecuciztecatl* (Aztec People, Mexico)
Also known as: *Coyolxauhqui, Meztli* (Female or Male), *Tezcatlipoca, Yohualticitl* (the Lady of the Night).

Moon god. Tecciztecatl offered to light the sun, but because of fear of the sacred fire refused to enter the flames. Nanahuatzin entered the flames and became the sun. Because of Tecciztecatl's cowardice the gods threw a rabbit into the moon and thus Teccizteca1 became the moon. He is shown as an old man with butterfly wings. He is the same as Meztli. Tecciztecatl was replaced by the goddess Coyolxauhqui. *See also* Coxcoxtli; Coyolxauhqui; Meztli; Nanahuatzin; Yohualticitl.

Teccuciztecatl (Mexico) *see* Tecciztecatl.

Tecmassa (Greek)
Tecmassa was either the wife or mistress of Ajax the Greater.

Tecpatl (Aztec People, Mexico)
God of the north. One of four year-bearers or year gods. Tecpatl is in charge of region of the north, and of the destiny of the person who is in this point of space and time. The other year gods are Acatl, Tochtli and Calli. *See also* Acatl; Calli; Tochtli.

Tectamus (Greek)
King of Crete. He is the brother of the king of the Dorians, Aegimius, and the father of Asterius. (Some say Minos and Pasiphae are Asterius' parents.) *See also* Aegimius.

Tecuciztecatl (Aztec) *see* Tecciztecatl.

Tecumbalam (Central America) *see* Xecotcovach.

Tefenet (Egypt) *see* Tefnut.

Tefnut *Tefenet* (Egypt)
Goddess of rain, dew and mist. She is the daughter of Atum, the sister-consort of Shu and the mother of Geb and Nut. Shu and Tefnut were the first couple of the Ennead of Heliopolis. Tefnut is depicted as a woman with a lioness' head or as a lioness. Tefnut and Shu were created by the self-copulation of

www.ebook3000.com

the sun god Ra or Tem, or were born from his spittle. After Thoth criticized her for having abandoned Egypt and leaving the country desolate, she wept great tears, but her tears soon turned to anger. She changed into a ferocious, bloodthirsty lioness, and her mane smoked with fire as her face glowed like the sun. She roamed drenched in the blood of her enemies. Shu and Tefnut may be associated with the underworld. Tefnut is represented as a lioness or lioness-headed. Sometimes, she is seen in human form wearing a sun's disk encircled by a cobra on her head. In Buto, Tefnut and Shu were worshipped in the form of flamingo-like children (symbolic for the sun and moon). She is identified with Nehemauit, Menhit, Sekhet, Apsit, Khepri, Ra, Atum, Anat, Amun, Aai, Anhur and Shu. *See also* Atum; Ennead; Geb.

Tegeates (Greek)
He was the lover of Acacallis and is possibly the father of Cydon. *See also* Acacallis.

Tehabi (Hopi People, North America)
"Mudhead, the Clown." Trickster deity.

Teharonhiawagon (North America) *see* Yoskeha.

Tehenut (Egypt) *see* Neith.

Teheser-Tep-f *Tcheser-Tep, Tcheser-Tep-f.* (Egypt)
A deified being or possibly a god. He is one of the forty-two judges in the Hall of Maati. He examined the bodies of the dead gods after they were captured by Am-kehun. If they were found fit, the bodies were bound by Her-thertu and their throats were cut and intestines removed by the god Khensu, then Shesemu butchered and cooked them for the deified king Unas. *See also* Unas.

Tehuti (Egypt)
Also known as: *Aah Tehuti, Djehuty, Thoth.*
"The Measurer." Tehuti is a title of Thoth. As Tehuti, he has the power to grant life to the deceased for millions of years. *See also* Aah; Ape; Thoth.

Teiresias (Greek) Another spelling for Tiresias, the great seer.

Teirnyon Furf Liant (Celtic) *see* Pryderi.

Teka-Hra (Egypt)
A monster serpent who guards the entrance to the Fifth Division or Fifth Hour of Tuat. *See also* Aau.

Tekhi (Egypt)
Tekhi is the goddess of the first month of the year. In some cases she is considered the female counterpart of Thoth. She is shown wearing a pair of high feathers.

Tekikinto (Micronesia) Another name for Nareau.

Tekikitea (Micronesia) *see* Nareau.

Tekitekite (Micronesia) *see* Nareau.

Tekkeitsertok (Eskimo People)
God of earth. He is a high hunting god who owns all the deer.

Telamon (Greek)
King of Salamis. An Argonaut. Member of the Calydonia Boar Hunt. He is the son of the king of Aegina, Aeacus, and Creusa (some say Endeis, who is the daughter of Cheiron and Chariclo). His brother is Peleus and his half-brother is Phocus. Telamon had three wives: Glauce, who burned to death at her wedding; Periboea, who went to Greece as a sacrifice for the Minotaur; and Hesione, who was rescued from a whale's stomach by Heracles. *See also* Aeacus; Ajax the Greater; Glauce; Hesione; Peleus; Periboea; Phocus.

Telavel (Lithuania)
The god of smiths and iron, Telavel, forged the sun and put it in the sky.

Telchines (Greek, Crete, Boeotia; Phoenicia)
Also known as: *Korubantes* (Crete) *Kouretes.*
Sorcerers. Rain-bringers. The Telchines are sons of the sea god, Poseidon, and Thalassa or possibly sons born from the blood of Uranus. Some of their names are Antaeus, Lycus, Megalesius, and Ormenos. They have five other brothers and a sister, the sea-woman Halia. When they mixed water from the River Styx with sulphur they ruined the harvest and killed the flocks. They are similar to the Caberi (q.v.). *See also* Corybantes; Dactyls; Poseidon; Styx.

Telchis *Telchin* (Greek)
With Thelxion, seized the throne of Apis. *See also* Apis (B); Niobe (B).

Teledamas (Greek)
Teledamas is the twin brother of Pelops. Their parents are Agamemnon and Cassandra. *See also* Agamemnon; Cassandra; Pelops.

Teledice (Greek)
She is the possible mother of Apis, Car and Niobe. *See also* Car; Niobe (B).

Teledyne (Greek) *see* Apis (B).

Telegonus (Greek)
He is the son of Odysseus and Circe. His siblings are Ardeas (who was later changed into a heron), Agrius and perhaps Latinius. Telemachus is his half-brother. Unknowingly, Telegonus killed his father Odysseus. Later, he married Penelope, his father's wife. He is not to be confused with Telegonus the spouse of Io, or Telegonus the son of Proteus. *See also* Calypso; Circe; Odysseus; Telemachus.

Telemachus (Greek)
He is the son of Odysseus and Penelope. His half-brother is Telegonus. Odysseus had disappeared from Troy for twenty years. During a part of that period Telemachus was taught by Athena. When old enough he left in search of his father. He met up with him in Eumaeus' hut. The three men killed all of Penelope's suitors. Telemachus also killed his father's consort, the sorcerer Circe, and then he fled to Italy. *See also* Calypso; Odysseus; Penelope; Telegonus.

Telephassa (Greek)
Also known as: *Argiope* (possibly).
She is the spouse of king Agenor and the mother of Cadmus, Cilix, Demodoce, Europa, Phineus, Phoenix, Thasus and possibly Argus. She went with her sons in search of Europa, who

had been kidnapped. There is a possibility that Telephassa and Argiope are two different women. *See also* Agenor (A); Europa.

Telepinus *Telepinu* (Hittite)
Also known as: *Marduk* (possibly).
Telepinus, the son of Teshub, is the god of youth, agriculture, and fertility. Occasionally he would leave the area. His absence created numerous difficulties. The land would become blighted and famine would abound. Angry one day, he disappeared again. Finding him was imperative. Hannahannas, the queen of heaven, sent a bee to search for him. The bee found him asleep in a meadow and stung him. He was so infuriated that he destroyed everything around him. The queen sent an eagle to return him to her. With the assistance of beautiful young women (possibly the Gulsa goddesses), the goddess of healing Kamrusepas, who brought along sesame and nectar, he was cleansed of his negativity. Then all good things were restored to earth. Compare to the Ugaritic Baal. *See also* Kamrusepas; Marduk; Teshub.

Telexiepeia (Greek) *see* Sirens.

Telipinu (Hittite) *see* Telepinus; Teshub

Telkhis (Greek) *see* Apis (B)

Tellus (Roman)
Also known as: *Gaea* (Greek); *Tellus Mater.*
Earth goddess. A pregnant cow was sacrificed to her. Associated with Pales. *See also* Gaea; Rhea.

Tellus Mater (Roman) *see* Tellus.

Telpochtli (Mexico) *see* Texcatlipoca.

Tem (Egypt) *see* Khepri.

Tem-Asar (Egypt) *see* Atum.

Tem-Sep (Egypt) *see* Assessors.

Temazcalteci (Mexico) *see* Ciuacoatl; Tonantzin.

Temt (Egypt)
Creator goddess. Little known ancient deity who is associated with or counterpart of the creator god, Tem.

Temtemtch (Egypt) *see* Aai.

Temu (Egypt)
Also known as: *Atem, Atmu, Atum, Tem, Tum.*
Sun deity. He either replaced Amen, or he is a form of Amen and Amen-Ra. *See also* Amen; Atem; Ra.

Tenages (Greek)
He is one of the Heliades and reputed to be the smartest. *See also* Heliades.

Tenazuchi-no-kami (Japan)
"Hand-Stroking-Elder." Asi-na-duti, an earthly deity, and Tenazuchi-no-kami are the parents of the rice goddess, Kushi-nada-hime, who is the youngest of eight daughters. *See also* Kushi-nada-hime.

Tenen (Egypt) *see* Tanunen.

Tengere Kaira Kan (Altaic, Tartars)
"Compassionate Heavenly Lord." *See also* Bai Ulgan.

Tengeri (Buryats) *see* Tangri.

Tengri (Kalmyks, Mongol People) *see* Tangri.

Tengu, The (Buddhist; Japan)
Spirits. Minor deities. Goblins. The Tengu are playful and sometimes evil spirits who live in the treetops, especially among the mountains. They hatch from eggs and live in colonies with a leader. The leader, Sojobo, is served by a messenger Tengu. Sojobo wears red robes and a small coronet and carries a fan made of feathers in his right hand. He has a large, aquiline nose and wears a fierce expression. His inferiors, known as Koppa-tengu, have mouths like beaks and bodies with small wings. The Tengu like to play tricks but do not like to be tricked. They are responsible for volcanoes and bad storms. The Tengu are thought to be reincarnated spirits of arrogant, malevolent people, particularly priests or warriors. These demons are depicted as small, bird-like men. They are sometimes shown wearing cloaks of feathers or leaves. The Tengu messenger is dressed in leaves. The aquiline nose is said to be a symbol of pride. Compare the Tenju to the Oni and Kappa. *See also* Gaki; Shiko-me.

Tenochtitlan (Mexico) *see* Huitzilopochtli.

Tenshodaijin (Japan)
A name for the goddess of light, Amaterasu (q.v.). *See also* Ama-Terasu-o-mi-kami.

Tenshoko-dagin (Japan) *see* Amaterasu.

Tenshoko-Daijin (Japan) *see* Amaterasu.

Tenshokokdaijin (Japan) *see* Amaterasu.

Tent-Baiu (Egypt)
The name of the Third Hour in Tuat. The gods of the country the souls pass through are called "Hidden Souls," and the Field (country?) is called Net-neb-ua-kheper-autu, mastered by the god Khatra. The boat of Ra is preceded by three other boats containing the nine forms of Osiris. *See also* Tuat.

Tentamides (Greek)
During a celebration in honor of his return (according to other sources the event was the funeral games of the father of Tentamides of Larissa), Perseus threw a discus (said to be his invention) and accidentally killed Acrisius. *See also* Perseus.

Tentit-uhesqet-khat-ab (Egypt)
The name of the Tenth Hour of Tuat. The region Osiris passes through is called Akert and the city is called Metchet-qat-utebu which has the pylon Aa-kheperu-mes-aru. The serpents mentioned are Thes-hrau and Ankh-ta. The gods who are identified in this hour are Tepthera, Shesera, Temau, Utu, Setu, Rau, Khesfu, Nekenu, Pesthi, Shemerthi, Thesu, and Kha-a. There is also mentioned the living beetle, P-ankhi, two additional serpents, Menenui, and the goddesses Netheth and Kenat, and Seftit. Eight more gods called Ermenui, Neb-aqet, Tua-khu, Her-she-taiu, Sem-Heru, Tua-Heru, Khenti-ast-f, and Khenti-ment are met on the journey of Osiris through this realm. *See also* Tuat.

Teoti-Husn (Mexico) *see* Teotihuancan.

Teotihuacan (Mexico) *see* Teotihuancan.

www.ebook3000.com

Teotihuancan *Teotihuacan* (Aztec People, Mexico)
Also known as: *Teoti-Husn.*

"City of the Gods." Sacred city. Although an actual city, mythically, it is the place where the gods met to create the fifth and final sun. The fifth sun is now, our present age. It is called Nahui Ollin, meaning four motion. Nahui Ollin is ruled by the sun god Tonatiuh or some say Xiuhtecuhth. The largest of the ancient cities, Teotihuancan is the site of the great pyramids of Mexico. Originally inhabited by the Nahua-speaking people around 400 B.C.E., the Toltecs invaded and ransacked the area in about C.E. 650. The Temple of Quetzalcoatl, the Pyramid of the Moon and the Pyramid of the Sun are located in Teotihuancan.

Teoyaoimquit *Teoyaomiqui* (Aztec People, Mexico)
Also known as: *Huahuantli* ("Striped One").

He is the god of warriors who die in battle. Teoyaoimquit is also the Lord of the Sixth Hour of the Day. *See also* Huahuantli; Lords of the Day Hours; Tepeyollotl.

Tep-tu-f (Egypt) *see* Anubis.

Tepen (Egypt)
A monster serpent in the Fifth Sector of Tuat. He carries offerings made by the living to the hawk-headed god, Seker. *See also* Seker; Tuat.

Tepeu (Maya People, Yucatan)
Creator. One of the seven regents, or gods that created everything. The council of seven solar gods decided to change the existing vegetation world and made several attempts. Tepeu is generally found with Gucumatz and Hurakan. *See also* Gucumatz; Huracan; Ixmucane; Ixpiyacoc.

Tepeyollotl *Tepeyolohtli* (Aztec, Zapotec People, Mexico)
Also known as: *Jaguar God, Teoyaoimquit, Tlaltecutli.*

His name means "Heart of the Mountains." He is the Lord of the eighth hour of the night. He is described as the spotted jaguar monster who leaps out to seize the declining sun. He is also called Tlaltecutli, the "Lord of the Earth," and the "Toad with Gaping Jaws." Tepeyollotl is probably the same as Mictlantecutli. *See also* Legend of the Four Suns; "L"; Lords of the Night Hours; Teoyaoimquit; Tlaltecutli.

Tepeyolohtli (Mexico) *see* Tepeyollotl.

Tepi (Egypt)
This monster serpent has four human heads, four breasts, and four pairs of human arms and legs. It is found in the Ninth Sector of Tuat. *See also* Ab-ta; Tepui.

Tepictoton (Aztec People, Mexico)
The Tepictoton are mountain dwarfs who are protectors of mountains. They might be related to the underground caverns called Tepeyollotl.

Tepoztecatl (Aztec People, Mexico)
Tepoztecatl is a local deity of Tepoztlan, who was born of a virgin.

Tepui (Egypt)
Afterworld deity. A two-headed god who appears in the eleventh sector of Tuat.

Ter (Egypt)
This two-headed monster serpent is found in the Fifth Sector of Taut.

Tera (Greek) *see* Rhea.

Tera, Mount (Persia) *see* Alburz (Mount).

Terah (Middle Eastern) *see* Elohim.

Teraphim *Teraph* (Hebrew)
The Teraphim are small household gods who provide protection for the family members. These gods are connected with ancestors.

Tere (Banda People, Africa)
Sky deity. Brother of Ngakola. His task is to take animals and seeds to earth. Once, he dropped the basket, releasing the contents of life-giving water. He chased the animals and the ones he caught became the domestic animals; the ones who got away are now the wild animals.

Tereus (Greek)
Deified mortal. According to different legends, Tereus either cut out his wife Procne's tongue and married her sister, Philomela, or he dishonored Philomela and cut out her tongue so that she might not reveal his misdeed. In any case, the sisters communicated with each other and Procne killed her son Itys and served up his flesh to Tereus out of revenge. When the sisters fled, pursued by Tereus, the gods changed all three into birds; Procne, a swallow; Philomela, a nightingale; and Tereus, a hawk. *See also* Aedon; Ares; Boreas.

Terminus (Roman)
Guardian. A lesser god of the Romans. Terminus is a boundary god who guards the edges of property. A stone dedicated to him was oiled and covered with plants, then placed in a hole which had been hallowed with the blood of a victim, usually a pig or lamb.

Terminalius (Greek)
"Protector of Boundaries." An epithet of Zeus. *See also* Terminus.

Terpimbrotos (Greek) *see* Helius.

Terpsichore (Greek)
One of the Muses. Terpsichore, goddess of dance, is usually seen wearing a crown of laurel and carrying a lyre. *See also* Muses; Sirens.

Terra (Roman)
Also known as: *Gaea* (Greek), *Tellus, Titaea.*
Goddess of the earth. *See also* Aello; Gaea; Harpies.

Tertiana (Roman) *see* Febris.

Teshub (Hittite)
God of rain and thunderstorms. King of gods. His brother is Tashmishu. His consort is Khepan, or Hepit. (Hepit's sister is Shoushka the Hurrian goddess of sexuality and marriage.) Teshub is the owner of the storm bulls Sheri and Khurri. Kumarbi slept with a rock and created a giant stone son, Ullikummi, to kill Teshup. Teshub and Tashmishu fought valiantly to overcome Ullikummi. Finally the great god Ea came to the rescue and with the giant who holds up the earth, Upelluri, they emerged the victors. A relief from the New Empire

shows Teshub in the form of a bull. This is the only case in the Hittite pantheon in which an animal stood for a god. In other representations he is standing on a bull or bulls pull his chariot. Teshub has also been depicted carrying a single ax. *See also* Adad; Ea; Hepit; Telipinu.

Tessub (Cassite) *see* Rimmon (Babylon).

Tet *Djed* (Egypt)
The symbol of Osiris. It is usually an amulet that represents stability or durability. It is similar in nature to Thet (Djet) which was the girdle, buckle or knot of Isis.

Tetenen (Egypt) *see* Tanunen.

Teteoinnan (Aztec People, Mexico)
"Mother of the Deities." An earth goddess. *See also* Ciuacoatl; Huitzilopochtli; Tlazolteutl; Tonantzin.

Tethus (Greek) *see* Tethys.

Tethys *Tethus* (Greek)
Rhea (the earth personified) took her daughter Hera (also earth) to Tethys to be cared for, since without water earth cannot exist. In the Pelasgian creation myth Tethys and Oceanus were the rulers of the planet Venus. Tethys is the Titaness daughter of Uranus and Gaea who married her brother, Oceanus. *See also* Achelous; Acheron; Alpheus; Amphitrite; Apsyrtus; Asopus; Calypso; Cephissus; Clytia; Cocytus; Cronus; Eurynome (A); Gaea; Hera; Inachus; Naiads; Oceanids; Oceanus; Styx; Themis.

Tetzcotzingo (Aztec People, Central Mexico)
Also known as: *Bald Rock.*
Sacred place. Worship takes place at Tetzcotzingo for rain, water, earth, and vegetation.

Teu (Teutonic) *see* Tyr.

Teucer (Greek)
He is the founder of the city of Salamis. His parents are Telamon and Hesione. Ajax is his half-brother. *See also* Ajax the Greater; Cinyras; Hesione.

Teuhie (Polynesia)
Creator. Teuhie is one of the foster parents of Eel (also known as Tuna) who was lover of Hina. The other parent was Kaloafu. *See also* Hina.

Teutamias (Greek) King of Larissa. *See also* Danae.

Teutates (Celtic)
Supreme deity. The human sacrifices to this god were killed by having the victim plunged headlong into a vat.

Tezcatlipoca *Tezcatepuca, Texcatlipoca, Tezcatlipo'ca* (Mexico, Aztec, Toltec)
Also known as: *Camaxte, Camaxtli, Chalchiuhtotolin, Huitzilopochtli, Ipalnemoani* (Lord of the Near and the Nigh), *Itzlacoliuhqui, Ixtliltou, Iztli, Iztli-Tezcatlipoca* (Stone Knife God of the Underworld), *Metztli* (moon god), *Moquequeloa, Moyocoyani* (Maker of Himself), *Omacatl, Telpochtli* (Lord of Festivities and Banquets), *Tepeyollotl* (Heart of the Mountain), *Tezcatlipoca, Titlacauan* (He who is closest to the shoulder), *Tloque Nauaque, Toueyo, Xipe Totec, Yaotl, Yoalli Ehecatl* (Night Wind), *Yaotl* (The Enemy).
"Smoking Mirror." Supreme deity. Sun god. God of darkness. Foremost recipient of human sacrifice. Giver and taker of life. Bringer of fortune and misfortune. Patron of rulers. Protector of warriors. God of the north. God of fate and punitive justice. God of cold. God of darkness. Patron of sorcerers, magicians, and thieves. Patron of Trecena 1 Ocelotl in the Tonalamatl (Aztec calendar). Shape-changer. Representative of the sun in the four directions of the Universe. Tezcatlipoca, the foremost of the gods, is the son of Ometeotl and his spouse who is also himself, Omecihuatl. His brothers are Huitzilopochtli, Quetzalcoatl and Xipe Totec. With the advent of their births the cycle of birth and death, creation and destruction was put into motion. Before humans were created, Tezcatlipoca put out his gargantuan foot to tempt the Earth Monster also known as Cipactli, the great crocodile, to come up from the primordial waters. Earth Monster rose up and snapped off his foot. In retaliation, Tezcatlipoca ripped off her jaw. Earth Monster would never again sink into the waters. From that day she became the earth. It was on her back that all humans were created and to this day live. In place of his missing foot, Tezcatlipoca wears a dark obsidian mirror. His obsidian mirror reflects the future. It also allows him to see everything, including what is within the hearts of mortals. (Later, one of Tezcatlipoca's favorite disguises was that of a turkey wearing a mirror in place of his amputated foot.) Many myths relate the constant struggle between Tezcatlipoca and Quetzalcoatl. As Tezcatlipoca is an imperfect god, he is never able to approach the Pole Star, home of the omnipotent, omniscient great dual god, his father, Ometeotl. Instead he is relegated to hopping around on one foot leaving the tracks that make up the Great Bear constellation. He is depicted with his obsidian mirrors and broad bands of yellow and black across his face. He is one of gods of the "Four Eras or Four Suns." He was the god of the First Sun called Nahui Ocelotl, "four tiger." This sun lasted 676 years, then all men perished, devoured by tigers. In this role he is depicted dressed in a tiger skin. *See* Legend of the Four Suns for more information about this period. *See also* Camaxtli; Chimalmat; Citlallatonac; Coxcoxtli; Ehecatl; Huitzilopochtli; Ipalnemoani; Itzcoliuhqui; Quetzalcoatl.

Texcatzoncatl *Tezcatzontecatl* (Aztec; Mexico)
"Straw Mirror." God of drunkards. Pulque deity. Flower god. He is one of the group of brothers called Centzon Totochtin (q.v.). *See also* Cinteotl.

Teyron (Celtic) *see* Rhiannon.

Tez-Katli-Poka (Aztec) *see* Tezcatlipoca.

Tezcatepuca (Aztec) *see* Tezcatlipoca.

Tezcatlipo'ca (Aztec) *see* Tezcatlipoca.

Tezcatzontecatl (Mexico) *see* Texcatzoncatl.

Tgorem (Ugarit)
Also known as: *Num, Torum.*
God of the sky, of order and balance. *See also* Ec; Num.

Thakurani (India) *see* Gramadeveta.

Thalassa (Greek)
Also known as: *Dione.*

www.ebook3000.com

Sacred Fire *(Chi Fire)*

Connect the Three Fires to combine into one Fire: *Heart to Kidneys to Navel to Heart*.



Fig. 3.31 *Connect the Three Fires and Sacred Fire.*

1. Move your hands together in front of your heart. Hold your hands together in front near the heart and feel the fire burning in there. Connect the Heart Fire to the Kidney Fire, the Kidney Fire to the Tan Tien Fire and back up to your heart; connecting them as one triangular Sacred Fire, circulating the Chi at 1,000 revolutions per minute, 10,000 R.P.M, 30,000 R.P.M and 60,000 R.P.M, doubling or tripling their collective power.

Open the Third Eye

Now, extend your hands out to the front, very far away – pushing, pushing, pushing. Push. Turn your palms inward, and extend your middle fingers inward toward your third eye. Picture a crack in the middle of your forehead, and pull the crack open. Feel the light from the heavens opening it and feel the light from the heavens shining into your brain.

1. Open your palms. Open your eyes, dimming the eyes. Look to the universe. Extend your hands to the front, palms vertical. Extend the arms from the scapulas. Smile and touch the universe.
2. Turn your palms inward and extend your middle fingers inward toward your third eye.

Thalassa is the goddess of the sea, personified. She is the mother of the Telchines and Halia. The father is possibly the sea god, Poseidon. *See also* Curetes; Telechines.

Thalath (Babylonia) *see* Belus (B).

Thalestris (Greek) *see* Amazons.

Thalia (A) (Greek)
"Rejoicing." Her parents are the illustrious Zeus and Themis the Titan, who is the personification of order and justice. Her siblings are Aglaea, Pasithea and Euphrosyne. By her father Zeus, she became the mother of the Sicilian twin volcanoes known as the Palici. (Others say that Hephaistos and Aetna are their parents.) Thalia is one of the Graces. *See also* Graces; Hephaistos; Palici.

Thalia (B) (Greek)
One of the nine Muses, Thalia is the muse of comedy. She is the daughter of Zeus and Mnemosyne, the personification of Memory. She carries the mask of comedy and a shepherd's staff. *See also* Corybantes; Muses.

Thalia (C) (Greek)
One of the fifty mermaids known as the Nereids (q.v.).

Thallo (Greek)
One of the Horae (goddesses of the seasons). Thallo is the personification of spring. She is the daughter of Zeus and Themis. Her sister, Carpo, the personification of autumn, is worshipped with her. *See also* Carpo; Horae.

Thaloc (Aztec) *see* Poseidon (Greek).

Thammuz (Babylonian) *see* Tammuz.

Thanantos (Greek) *see* Keres.

Thanatos *Thantos* (Greek)
Also known as: *Mors* (Roman); *Paean.*
God of death. Thanatos is the son of Nox and Erebus and brother of Hypnos. He sent those he struck with his sword to the realm of Hades. Thanatos is depicted as a winged or black-robed man carrying a sword. *See also* Aether; Erebus; Mors; Nemesis; Nox; Sarpedon (B).

Thantos (Greek) *see* Thanatos.

Thasus (Greek)
Thasus is the son of Agenor and Telephassa. *See also* Agenor (A).

Thauk (Teutonic) *see* Thok.

Thaukt (Teutonic) *see* Thok.

Thaumas (Greek)
Sea god. Thaumas is the son of Oceanus and Gaea or Pontus and Gaea. He married his half-sister Electra, the daughter of Oceanus and Tethys. *See also* Aello; Gaea; Harpies; Nereus; Oceanids; Oceanus; Phorcys.

Theano (Greek)
Theano is the daughter of the king of Thrace, Cisseus. It was Theano who gave the Palladium to Diomedes and Odysseus. She also founded Padua after the fall of Troy. She married Antenor. Her children are Acamas, Agenor, Archelous, Coon, Crino, Demoleon, Iphidamas, Laodamas, Polybus, Glaucus, Helicaon, Laocoon, Lycaon and Polydamas. She also had two children by Metapontus, who killed her and two of her sons when he discovered that they were not his children. *See also* Agenor; Antenor; Diomedes; Metapontus; Odysseus; Polybus.

Theb-ka (Egypt) *see* Anhur.

Thebe (A) (Greek)
She is the daughter of Asopus, the river god, and Metope who was also the daughter of one of the river gods, either Ladon or Peneius. Thebe was abducted by Zeus. *See also* Antaeus; Asopus; Ladon; Zethus.

Thebe (B) (Greek)
She is the daughter of Zeus and the spouse of Ogyges.

Thegn (Teutonic) *see* Heimdall.

Theia (A) *Thia* (Greek)
She is the daughter of the Centaur Cheiron, who was raped by Aeolus. The sea god Poseidon changed her into Evippe, a mare. She became the mother of a foal named Melanippe, who changed into a girl. *See also* Aeolus; Cheiron; Poseidon.

Theia (B) (Greek) The daughter of Memnon.

Theia (C) (Greek)
She is the Titan daughter of Uranus and Gaea, sister spouse of her brother Hyperion, and the mother of Helius, Eos, and Selene. *See also* Cronus; Eos; Eurynome (A); Gaea; Helius; Hyperion; Oceanids; Oceanus.

Thein (Burma)
Rain nats (spirits) who live in the stars. When engaged in fights, they cause thunder and lightning. When rain is needed, the people hold a formal tug-of-war in an attempt to rouse the Thein. *See also* Nats.

Theiodamas (Greek) *see* Hydras.

Theispas (Urartian People, Armenia)
A weather or storm god. One of the triad of deities worshiped by the early Urartians. The other gods were Khaldi who was the supreme or moon deity, and Artinis the sun-god. All may have been forerunners of the Babylonian triad of Sin, Shamas and Ramman. *See also* Artinis.

Thelxiepeia (Greek) She is one of the Sirens (q.v.).

Thelxion (Greek)
Thelxion and Telchin wrenched the throne from Apis. *See also* Apis (B); Cassandra; Niobe (B).

Themehu (Egypt) *see* Aamu.

Themis *Themiste* (Greek)
Also known as: *Ananke.*
Goddess of law and justice. The Titan Themis is the daughter of Uranus and Gaea and the sister of the Titans and the Giants. When the Oceanid Metis, the first wife of Zeus (Hesiodic tradition), was swallowed by Zeus, Themis married the great god. She became the mother of the Moirae (Fates), the Horae (Seasons), Astraea (Justice) and possibly Prometheus

(Forethought) and Clymene. The original goddess of prophecy, she originated the Delphic Oracle and presented it to Zeus as a birthday present. A brilliant deity, advisor and inventor, she personified justice and order. Themis, Ocean, Tethys, Hyperion, Mnemosyne, Iapetus (because of his sons Atlas and Prometheus) were deities from the group known as the Elder Gods. These Titans were not ousted when Zeus toppled Cronus and the Olympians came into power. They were only reduced to a lower rung on the heavenly ladder. In the Pelasgian creation myth, Themis and Eurymedon are the deities who ruled the planet Jupiter. Themis is depicted carrying a cornucopia and scales. Compare Themis to Ananke. *See also* Atlas; Cronus; Dike; Eurynome (C); Evander (B); Fates; Gaea; Giants; Hesperides; Horae; Hyperion; Metis; Mnemosyne; Moirae; Ocean; Prometheus; Tethys; Titans; Uranus; Zeus.

Themiste (Greek)

Themiste is the daughter of Ilus and Eurydice and the sister of Laomedon. Her children are Anchises and Laocoon. *See also* Anchises; Laocoon; Laomedon.

Themisto (Greek)

The daughter of Hypseus, her siblings are Astyagyia, Cyrene, Stilbe and her husband is Athamas. (She was his third wife.) Her children are Erythrius, Leucon, Ptous and Schoeneus. When Themisto found that she had killed her own sons instead of the *sons of Athamas* and Ino, she committed suicide. *See also* Athamas; Ino.

Then-Aru (Egypt) *see* Aai.

Thenemi (Egypt) *see* Assessors.

Thenenet (Greek) *see* Isis.

Theno (Greek) *see* Acamas (B).

Thenti (Egypt) *see* Aai.

Theonoe (A) (Greek)

Also known as: *Eidothea.*

She is the daughter of Thestor and Megara. Her siblings are Alcmaon, Calchas and Leucippe. *See also* Alcmaon; Calchas.

Theonoe (B) (Greek)

Proteus and the Nereid Psamathe, the daughter of Nereus and Doris, are her parents. Her siblings are Cabeiro and Theoclymenus. *See also* Doris; Nereids; Proteus.

Theophane (Greek)

The beautiful Theophane was kidnapped by Poseidon and she became the mother of the ram who was born with the Golden Fleece. *See also* Golden Fleece; Poseidon.

Theoris *Thoeris* (Egypt, Greek)

Also known as: *Taurt.*

The goddess of women in childbirth and protector of babies, Theoris was called the "Great." She presided over toilet rites. She is sometimes identified with Hathor and is the female counterpart of Bes. She is shown as a female hippopotamus squatting on her haunches. Since the Archaic Period, she is depicted as standing upright with human arms and legs. She held either the attribute of the "sa" (a symbol of protection) or the ankh or a torch as attributes. Her image was often attached to beds and headrests. *See also* Bes; Hathor; Taueret.

Thermuthis (Egypt) *see* Renenet.

Thessalus (A) (Greek)

King of Thessaly. His parents are Heracles and Chalciope. His two sons took thirty ships to the Trojan War. *See also* Pheres (A).

Thessalus (B) (Greek)

His parents are Jason and Medea. For a list of his siblings, see Pheres (A). *See also* Jason; Medea.

Thestius (A) (Greek)

If his father was Ares, he is the possible father of Althea, Hypermnestra, Plexippus and several others. *See also* Althea; Ares.

Thestius (B) (Greek)

His son, Calydon, accidentally killed him.

Thestor (Greek)

Thestor is the son of Apollo or possibly Idmon. He married Megara and became the father of Alcmaon, Calchas, Leucippe and Thenoe. *See also* Calchas.

Theta-enen (Egypt) *see* Aai.

Thethu (Egypt)

A serpent demon mentioned in a magical formula of Unas. *See also* Akeneh.

Thetis (Greek)

Thetis "of the silver feet" is the daughter of Nereus and Doris. Hera raised her. Thetis' sisters are the Nereids. She had been wooed by Zeus and Poseidon until they heard an oracle announce that if Thetis had a son, he would be greater than his father. So, they dropped her in a hurry and forced her to marry Peleus. The goddess of strife, Eris, rolled the Golden Apple at her wedding. When her son Achilles was born, she dipped him in the Styx river to make him invulnerable. She was holding him by the heel and of course, that became his only vulnerable spot. *See also* Achilles; Doris; Eris; Peleus; Styx.

Thevadas (India) *see* Devis.

Thia (Greek) *see* Theia.

Thialfi *Thjalfi* (Norse; Teutonic)

Also known as: *Swift Runner.*

Lightning deity. Brother of Roskva and servant of Thor. Thialfi, encouraged by Loki, broke one of the magic bones of Thor's goat and because of this the peasant family gave their daughter and son to Thor as servants. Associated with Skrymir. Thialfi was beaten in a race with Hugi. *See also* Roskva.

Thiassi *Thjasse, Thjazi, Thiazi* (Norse; Teutonic)

Also known as: *Voland.*

Storm giant. Thiassi is the son of Ivalde and Greip and brother of Egil and possibly Idun. Idun is the guardian of the magic apples which Thiassi coveted to give him back his youth. Idun was finally restored to Valhalla by Loki. Thiassi was killed and burned by the Aesir. *See also* Idun.

Thiazi (Teutonic) *see* Thiassi.

Thing (Iceland. Norse; Teutonic)

Also known as: *Thingstead, Ting.*

www.ebook3000.com

The Thing is an assembly of the gods where matters of importance were discussed.

Thingstead (Teutonic) *see* Thing.

Thingsus (Teutonic) *see* Tyr; Ziv.

Thir (Teutonic) *see* Heimdall; Thor.

Thixo (Ponda, Xhosa People, Africa)
Also known as: *Dxui* (Bushmen), *Tsui'* (Hottentot).
Creator god. For details, *see* Tsui'goab.

Thjalfi (Teutonic) *see* Thialfi.

Thjasse (Teutonic) *see* Thiassi.

Thjazi (Teutonic) *see* Thiassi.

Tho-Ag *The Eternal Mother* (Tibet) *see* Aditi.

Tho-Og *The Eternal Mother* (Tibet) *see* Aditi.

Thoas (A) (Greek)
The son of Dionysus or Theseus and Ariadne. When the Lymnian women went insane and killed their spouses, he was the only survivor.

Thoas (B) (Greek)
Also known as: *Deiplus.*
He is the son of Jason and Hypsipyle. He was about to sacrifice Orestes and Pylades when Iphigeneia rescued them. *See also* Jason; Orestes; Pylades.

Thoas (C) (Greek)
King of Aetolia. Thoas was one of Helen's many suitors. He took forty ships to Troy. He was in the Wooden Horse.

Thoas (D) (Greek)
He was killed by Menelaus in the Trojan War.

Thoas (E) (Greek)
He is the giant son of Uranus and Gaea, killed by the Fates.

Thoas (F) (Greek) Aeneas' companion. *See also* Aeneas.

Thoas (G) (Greek)
He is the son of Ornytion, who is the son of Sisyphus and Merope. His brother is Phocus. *See also* Merope; Ornytion; Phocus; Sisyphus.

Thobadzistshini *Thobadestchin* (Navajo People)
He is either the son of Yolkai Estsan or Estanatlehi. *See also* Anaye; Atseatsine.

Thoeris (Greek) *see* Theoris.

Thok (Norse; Teutonic)
Also known as: *Loki* (possibly), *Thauk, Thaukt, Thokk.*
This female giant, representing darkness, is likely an aspect of the trickster fire god Loki. She was the only one who refused to weep for Balder after his death. This prevented him from returning to earth from Hel. *See also* Balder; Loki.

Thokk (Teutonic) *see* Thok.

Thomagata (Chibcha People, Columbia)
Also known as: *Fomagata.*
Thunder deity. Opponent of the sun god Bochicha. Thomagata, an evil deity, with one eye, four ears and a long tail, turns men into animals.

Thomagostad (Niquiran People, Nicaragua)
Chief deity. He lives with his consort, Zipaltonal, in the east. Thomagostad and Zipaltonal created everything.

Thonenli (Navajo People, North America)
He is a water god who belongs to a group of household and nature deities, known as the Yei (q.v.). *See also* Ganaskid.

Thoon (Greek)
Thoon is the giant son of the earth, personified as Gaea. *See also* Giants; Hippolytus (B).

Thoosa (Greek)
Thoosa is the mother of the one-eyed Cyclops, Polyphemus, by the sea god, Poseidon. *See also* Phorcys; Polyphemus.

Thor *Thur, Tor, Tror* (Norse; Teutonic)
Also known as: *Akethor* (a corruption of Ukko-Thor), *Aku-Thor, Donar, Einridi, Finnish, Hloride, Hloridi, Hlorrida, Hlorridi, Lorridi, Lothurr* ("The Fighter"), *Thunaer, Thunar, Thunaraz, Thunor, Vingthor.*
God of thunder and lightning. Protector. God of fertility. God of the sky. God of the household. Thor follows Odin as a principal deity in the Norse pantheon. He is Odin's son by Jord or Fjorgyn, or Munon with one of Priamus' daughters, or his mother could be the giant Hlodyn. As a protector who watches over mortals he is always in battle with the wild forces of natures personified by the giant Jotuns. Thunder and lightning are his primary ways of gaining attention. Even his chariot produces its own thunder as it rolls through the skies pulled by the great god's goats Tanngnjost and Tanngrisni. When Thor is holding the reins he is known as Riding-Thor. These goats are amazing animals. Thor, who has to have a voracious appetite because of his size and the energy he expels, kills and eats the goats constantly. As long as he wraps their bones in their hides, they come back to life and are ready to cook and eat again. He is the spouse of the beautiful, blonde Sif. Their children are Modi and Throd (Thrud), or according to some Lorride and Thrud. He is also the father of Magni by the giant Jarnsaxa (Iarnsaxa) and according to other sources, Lorride, or Magni and Modi. Other male children said to be Thor's sons are Veggdegg, Beldegg (another name for Balder), Skjold, Saeming, and Yngve. Thor resides in Bilskirnir, a 540 room palace located in Thrudheim. He owns a few magnificent, magical objects: a hammer called Mjollnir that never misses its target and always returns to him; a pair of iron gauntlets called Iarngreiper to grasp his hammer; and a belt of strength called Megin-giord. Some say that he killed his foster-mother and father, Vingnir and Hlora, then took possession of the kingdom of Thracia. He assumed the names Vingthor and Hlorridi after his foster parents. Thor is the only god who cannot use the bridge Bifrost because of the heat he generates. It did not bother him as he found short cuts to reach the meeting place of the gods at Yggdrasil. As a god of the peasants and a household god his likeness was carved on the master of the household's chair. Thor is always more interested in deeds of strength than in craftsmanship. Thor is described as burly, red-headed, immensely strong, with blazing eyes and a beard. Like Odin, he wears a broad-brimmed hat. He is often

depicted holding his hammer Mjollnir in his hand. Thursday is named after this god (Thunar's Day). As Donar his symbol is the swastika. He resembles the Greek Zeus and Roman Jupiter. Compare Thor to the Celtic god Sucellos, the Yoruba deity, Shango, the Indian gods Indra and Pushan and the Celtic god Dagda. *See also* Aegir; Aesir; Alviss; Ares; Asgard; Balder; Bifrost; Brisingamen; Donar; Heimdall; Hrungnir; Jord; Jotuns; Loki; Magni; Midgard; Mjollnir; Modi; Ragnarok; Saeming; Sif (A); Thialfi; Thrall; Thrud; Thrudheim; Thunor.

Thora (A) (Norse; Teutonic)
Thora, the daughter of Hakon (or possibly Heroth), wife of Elf (or Ragnar Lodbrog), gave refuge to Gudrun and her daughter Svanhild in Denmark for seven and a half years. *See also* Elf.

Thora (B) (Africa) *see* Kaang.

Thot (Egypt) *see* Osiris.

Thoth *Thouth* (Egypt)
Also known as: *Aah, Aah-te-huti, Aah Tehuti, Djehuti, Tehuti, Thout, Thouti, Zehuti.*
God of wisdom, time, astromony, music, magic, medicine, drawing, writing, surveying. Messenger and secretary of the gods. Author of 42 books. He was the protector of Horus (he cured him from scorpion poison) who later followed him as ruler. Thoth attempted to revive Osiris when he had been pulled apart. His followers claim that he creates by sound. The sound of his voice caused the birth of the early deities of Nun by the sound of his voice. The baboon was incorporated into Thoth's cult and became an aspect of his being. When he was sent to retrieve Tefnut, Ra's estranged daughter, he and Shu were disguised as baboons. Thoth is represented as either an ibis or an ibis-headed man, or as a baboon, and sometimes with the head of a dog. His attributes are often a writing palette or a palm leaf. The Greeks identified Thoth with Hermes, and he was also known as Aah. When Thoth was god of the city of Hermopolis, he was either a baboon or an ibis; in Khnum, he was a he-goat, in Memphis, a bull. Thoth's female counterpart is Seshat. *See also* Aah; Aani; Amenhotep; Amit; Maat; Neith; Nut; Osiris; Sopdu.

Thott (Egypt) *see* Aani.

Thoueris (Greek) *see* Theoris.

Thout (Egypt) *see* Thoth.

Thouth (Egypt) *see* Thoth.

Thouti (Egypt) *see* Thoth.

Thraell (Teutonic) *see* Thrall.

Thraetana (Persian) *see* Thraetaona.

Thraetaona (Persian) *see* Ahura Mazda; Haoma; Thrita.

Thrall (Norse; Teutonic)
Also known as: *Thraell.*
Founder of the race of Serfs. He is the son of Heimdall and Edda. Heimdall spent three days in the hut with Rig and Edda and somehow Edda bore Thrall. There are some who say Thrall is the brother of Churl and Jarl. Thrall's wife is Thyr, the drudge. They had ten sons and ten daughters. Thrall has a dark complexion and is heavy set. *See also* Heimdall.

Thrasymedes (Greek)
He is the son of Nestor and Anaxibia or Eurydice. For the names of his siblings, *see* Stratius. *See also* Antilochus.

Thrbadestchin (Navajo People, North America)
A creator god. Son of Estanatlehi.

Three Emperors (China) *see* Fu-Hsi.

Three Goddesses of Munakata (Shinto; Japan)
Daughters of Amaterasu. The three goddesses of Munakata were born of the mist of the sun goddess Amaterasu's breath. Their names and affiliations follow. Takiri-bime-no-mikoto, also known as Okitsushima-hime-no-mikoto (Mist-Princess-Goddess), is thought to have married Opo-kuni-nusi. She is the mother of a daughter, Taka-pime-no-mikoto, and a son, Adi-siki-taka-pikone-no-kami. The second goddess of Munakata is Ichikishima-hime-no-mikoto (variant spellings, Ikiti-simapime-no-mikoto, Ikiti-sima-pime-no-mikoto), also known as Sayori-bime-no-mikoto (variant spelling, Sa-yori-bime-no-mikoto). The third goddess of Munakata is Takitsu-hime-no-mikoto (variant spelling, Takitu-pime-no-mikoto) (Seething-Water-Princess-Goddess). These goddesses are recorded in the *Kojiki* and the *Nihongi* and are included among the Hachi-o-jo or "Eight Rulers." The three goddesses of Munakata are described by Susanowo as graceful maidens. For the Shinto creation myth and additional details about the *Kojiki* and *Nihongi*, *see* Ama-no-minaka-nushi. *See also* Amaterasu; Susanowo.

Three Legged Ass (Persia)
The Three Legged Ass is a benevolent deity of disease and pests. He has three feet, six eyes, nine mouths, two ears and a horn. He is as big as a mountain and each foot covers as much ground as a thousand sheep. His task is to destroy the worst disease and pests.

Three Norns, The (Scandinavia) *see* Eumenides.

Thrita (Persian)
Also known as: *Faridun* (name in later times), *Thraetana, Thraetaona, Thrita Athwya, Trita Aptya.*
As Thrita he is the healer and preparer of haoma and the one who drives away serious illness and death from mortals. Thrita was the third man who prepared haoma for the corporeal world. (His name means third.) His prayers to Ahura Mazda brought all the healing plants that grow round the Gaokerena tree in Vourukasha, the cosmic ocean. As Thraetaona (Faridun in the later texts), he is a healer and a victorious warrior. He battled the three-headed, three-jawed, six-eyed mighty dragon, Azhi Dahaka. He is called upon to relieve itches, fevers, incontinency, and to keep evil people away. These discomforts are all attributed to the power of Azhi-Dahak. Thrita defeated the dragon with his club but could not slay him. When he finally took a sword and stabbed the evil dragon, a multitude of horrible creatures crept from his loathsome body. Fearful of the world being filled with such vile creatures as snakes, toads, scorpions, lizards, tortoises, and frogs, Thrita refrained from cutting the monster to pieces. Instead he bound and imprisoned him in Mount Demavand, where to this day he causes earthquakes. It is said that mortals will one day regret Thrita's action. It is Thraetaona who seized Yima's "khvarenanh" (his glory) when it left his

www.ebook3000.com

body and then became the ruler of Yima's realm. He divided the kingdom between his sons Airya, Cairima, and Tura. In other legends, Thrita is represented as the father of Thraetaona. Thrita is killed by Azhi Dahaka (who represents frost). Thraetaona avenges his father's death by tying Azhi Dahaka to Mount Demavend. Traetasona sometimes reveals himself in the shape of a vulture. *See also* Ahura Mazda; Gaokerna Tree; Haoma; Kava; Trita (India); Vourukasha; Yima; Zahhak.

Thronia (Greek)
Thronia is the daughter of Belus, the king of the Egyptians, and Anchinoe, the daughter of the river god Nile. *See also* Agenor (A); Danaus.

Thrud (Teutonic)
Also known as: *Might.*
Thrud is the giant daughter of Thor and Sif and the sister of Lorride. Her lover was the dwarf, Alvis, who was petrified by sunlight because he failed to prove his mental powers to Thor. *See also* Magni; Thor.

Thrud-Heim (Teutonic) *see* Thrudheim.

Thrud-Vang (Teutonic) *see* Thrudheim.

Thrudgelmer (Teutonic) *see* Thrudgelmir.

Thrudgelmir *Thrudgelmer* (Norse; Teutonic)
Thrudgelmir, a six-headed frost giant, was born from the feet of Ymir. In turn, Thrudgelmir bore the giant Bergelmir, father of all frost giants. *See also* Bergelmir; Ymir.

Thrudheim *Thrud-Heim* (Norse; Teutonic)
Also known as: *Thrud-Vang, Thrudheimr, Thrudvangr, Thrudvarg.*
Home of gods. Thor's home in Asgard. Thor's mansion in Thrudheim is named Bilskirnir.

Thrudheimr (Teutonic) *see* Thrudheim.

Thrudvangr (Teutonic) *see* Thrudheim.

Thrudvarg (Teutonic) *see* Thrudheim.

Thrym (Teutonic)
Also known as: *Thrymr.*
Thrym is the frost giant who stole Thor's hammer. He was killed by Thor. Sometimes called the King of the Frost Giants. *See also* Loki.

Thrymr (Teutonic) *see* Thrym.

Thu (China) *see* She-chi.

Thunaer (Teutonic) *see* Thor.

Thunar (Teutonic) *see* Thor; Thunor.

Thunaraz (Teutonic) *see* Thor.

Thuner (Teutonic) *see* Thunor.

Thunor (Norse; Teutonic)
Also known as: *Thor, Thunar, Thuner.*
A Germanic sky god, Thunor is similar to Jupiter of the Romans. His symbols are the great oaks of central and western Europe. The name Thunor is one of Thor's alternate names. Thunor may have been the forerunner of Thor. Some say Thunor is Thor (q.v.). *See also* Jupiter.

Thunor (Teutonic) *see* Thor.

Thunupa (Inca People, Peru)
Also known as: *Virococha.*
High god. Thunupa's legends are similar to the legends of Virococha. Thunupa has one unique tale. He is said to have arrived from the north with five unnamed disciples. With the advent of Christianity, a cross was added to his back in his depictions. *See also* Virococha.

Thuremlin (Australia) *see* Baiame; Duramulun.

Thviti (Norse; Teutonic)
Thviti is the black boulder where Fenrir the wolf was chained by the fetter, Gleipnir (also called Gelgia). The gods pulled the end of Gleipnir through Gioll, the rock, and fastened it to Thviti. *See also* Fenrir; Gleipnir.

Thyestes (Greek)
He is the son of Pelops and the brother of Atreus. *See also* Aegisthus; Atreus; Pelops.

Thyia (A) (Greek)
Thyia is the daughter of the river god, Cephissus, or possibly Castalius. She had a child by Apollo. *See also* Cephissus.

Thyia (B) (Greek)
She is the daughter of Deucalion, the king of Perae, and his cousin Pyrrha, who is the daughter of Epimetheus and Pandora. Thyia and her father survived the Great Deluge.

Thyone (A) (Greek)
Thyone is the name given to Semele when she was deified. *See also* Semele.

Thyone (B) (Greek)
Thyone is one of the women who are said to be the mother of Dionysus.

Thyoneus (Greek) Another name for Dionysus.

Ti-Jean Petro (Haitian)
He is the serpent son of Dan Petro. His wife is the Haitian earth goddess, Marinette. Ti-Jean Petro likes to climb posts or trees. *See also* Marinette.

Ti-Kuan (Taoist; China)
Also known as: *San Kuan.*
God of forgiveness. Ti-Kuan, who has the power to forgive sins, is one of the Agents of Earth. He is one of the triad Shui-Kuan and T'ien-Kuan.

Ti-mu (China) *see* Ti-ya.

Ti-shih (China)
Ti-shih is the Chinese equivalent of the god Indra of India.

Ti-tsang-wang-pu-sa (Buddhist; China)
Also known as: *Jizo-Bosatsu* (Japan), *Kshitigarbha* (Central Asia), *Maudgalyayana* (India), Ti-tsang, Yu-ming Kio-shi.
Underworld deity. God of mercy. Ti-tsang was appointed by Buddha Sakyamuni with the job description of protecting the

souls of those sent to the underworld, deciding who can be reincarnated and delivering souls to paradise (Si-fang ki-lo shi-kiai or Tsing-tsing t'u), the abode of Amitabha, and the task of emptying all the hells. He preaches to the damned and must remain in hell until the last soul is saved. He can assume any one of six forms or all of them at the same time. Ti-tsang is usually shown in the dress of the Chinese bonzes with a crown on his head. Sometimes he has two assistants, one of whom is Mulien, known as Maudgalyayana in India. He is sometimes worshiped along with Amitabha. In some instances, Ti-tsang-wang-pu-sa is shown as a smiling monk, robed, with a halo about his body and head; he carries the pearl of light and the staff with metal rings, which tinkle at his approach. For information about the underworld, *see* Ti-yu. *See also* Amitabha; Ch'eng-huang; Jizo-Bosatsu; Kshitigarbha; Kuan Yin; Tung-yo ta-ti; Yama Kings.

Ti-ya (China)

Also known as: *Ti-mu.*

Earth mother and goddess of children. Her title is Ancestress of the World.

Ti-yu (China)

Also known as: *Kings of Hell.*

Ti-yu is the home of the ten Yama Kings. They are judges of the dead. There are ten levels or hells in Ti-yu which are ruled by various kings. The first and chief of the rest is Yen-lo Wang or Yen-Wang, but he was replaced by Ts-in-kuang-wang. He receives the dead and decides where they go by placing them in front of the mirror Sie-king T'ai. After this they are taken to Wang-si ch'eng, who is in charge of those who die by accident. Various versions say they either can or cannot return. The second hell consists of sixteen sub-hells and is ruled by Ch'u-kiang wang (Ch'u Chiang). He decides the punishment of the go-betweens in the process of marriage rites. The third hell is ruled by Sung-ti, who punishes those mandarins who behaved badly to their superiors. The fourth hell, under Wu-kuan wang, is where those who are miserly are punished. The fifth hell is ruled by King Yama or Yen-lo Wang, who judges those who commit the worst sins: killing, destruction of sacred books, etc. King Piench'eng is in charge of the sixth hell. He punishes those guilty of sacrilege or who curse other gods. The seventh hell is ruled by T'ai-shan kun wang (King of the Eastern Peak), who punishes those who desecrate graves, use or eat human flesh, or sell their wives to be slaves. The eighth hell has King of P'ing-teng in charge. He punishes those who fail to be pious. The ninth hell is ruled by King of Tu-shi, who punishes those who read or write obscene material, and the tenth hell is ruled by Chuan-lun-wang, who turns the Wheel of transmigration. He decides where the soul will be placed in the future life. In a sense he is a god of reincarnation. He also takes the soul to Meng'p'o niang-niang, who gives them the broth of oblivion. *See also* K'u-ch'u K'iao.

Tiamat *Tihamtu* (Assyro-Babylonian; Chaldea, Semite)

Also known as: *Baau* (beneficent form), *Bis-Bis, Hubar, Mummu-Tiamat, Omorca, Omoroka, Tamtu, Tauthe, Tehom, Thalass, Thalatth, Thamte, Thlavatth, Tiawath, Tisalat, Ummukhubar.*

The goddess of the primeval sea, visualized as a dragon and representing the forces of chaos and evil, Tiamat is the salt water personified, the counterpart of Apsu, the sweet water. The gods and the world were born of Apsu and Tiamat. She is described as being 300 miles long, with a mouth 10 feet wide. Her circumference was 100 feet and she moved with undulations six miles high. In her own image she created multitudes of offspring. She is also credited with populating the earth with hornets, scorpions, spiders, apes, vultures, and hyenas. Her conflict with Marduk became aggressive when her mate, Apsu, was killed. Placing her son, Kingu, in command of the zoomorphic beings she had created, she went into battle against Marduk. She armed her group with horrific weapons and was assisted by the gods of the night sky and the star gods. Marduk slaughtered Tiamat, and made half her body the firmament, half the earth, and with her blood the sea was formed. Tiamat as Hubar is the personification of the underworld river, Hubar. She is depicted as a winged seven-headed dragon with a scaly body, and claws. Tiamat is similar to Apepi (Apep) of the Egyptians, and the Egyptian goddess Ta-Urt. She corresponds to the Greek Thalassa as a sea goddess and the Greek Hydra and Pistris as a dragon. Compare Tiamat to the dragon-slayer Indra (India). There may be a connection between Tiamat in her aspect as Bis-Bis, and Ishtar in her aspect as Bisi-Bisi. Tiamat and Yam parallel Zeus as rain providers. *See also* Apsu; Bau; Chaos; Damkina; Ea; Enlil; Ishtar; Kishar; Lahamu; Marduk; Nammu (Sumerian primeval sea personified as a mother goddess).

Tiamuni (Acoma People, North America)

The First Man. *See also* Katsinas; Mayoching; Tsichtinaka.

Tianquiztli (Aztec People, Mexico)

"Marketplace." The Pleiades were known as Tianquiztli to the Aztec People. *See also* Tlauixcalpantecuhtli.

Ticholtsodi (Navajo People, North America)

Water monster. *See also* Tonenili.

T'ie-kuai (China) *see* T'ie-Kuai Li.

T'ieh-Kuai Li *T'ie-kuai Li* (China)

Also known as: *Li, Li T'ieh-kuai.*

Deity of beggars. He is one of the Eight Immortals, who is sometimes called "Li with the Iron Crutch." T'ieh-Kuai Li lost his body after his servant cremated it too soon. His soul was placed in the body of a beggar who had died of hunger. He is shown as a beggar leaning on a crutch and carrying a large calabash on his back. T'ieh-Kuai Li is associated with Lao-tzu and Wang-kiu. *See also* Arhats; Eight Immortals; Pa-hsien.

Tieholtsodi (Navajo People, North America) Water Monster.

Tien *T'ien* (China)

Also known as: *Thien, Tian, Ti'in, Yu Huang.*

High god. Heaven. God of the Vault of Heaven. In some interpretations, Tien is the supreme god of the early Zhou people. Tien ("Heaven") is the supreme god, superior to ancestors and other gods. It was necessary for rulers to have and to hold Heaven's approval which could be lost if they were cruel or unfair. As heaven, Tien consists of Li (the active principle), Li (the mover), Ki (matter). Heaven is also known as the Chinese imperial heaven, Huang T'ien, where the ruler is Huang T'ien Shang Ti. Tien is often shown with a large round head. *See also* Yin and Yang.

www.ebook3000.com

T'ien-chu (China) *see* Kei-kung.

T'ien-Hou (China) *see* Sheng-mu.

Tien-Hou (China) *see* T'ien Hou.

T'ien Hou *Tien-Hou* (China)
Also known as: *Ch'uan Hou* (Goddess of Streams), *Ma-tsu-p'o, Nai-nai Niang-niang, Sheng-Mu, T'ien-Shang.*

Protector of merchants and ships. T'ien Hou is a sea goddess, although many say she was a deity of navigators. Once, as a mortal girl, she found that her four brothers were at sea, each on a different ship. She fell into a faint. After she was revived and three brothers came back safely, they told her it was the vision of their sister appearing to them that saved them from the dangers of a tempest each one had met. The brother who did not return had not seen his sister, because she had been brought out of her faint before she could reach him. In later mythology, she was given the title of "Empress of Heaven." Sometimes she is shown seated on a lotus, sometimes on a throne, sometimes on a cloud or on the waves. She holds either a tablet or scepter. T'ien Hou usually wears a long robe with a girdle and has a bonnet on her head. A variation of her name is Ch'uan Hou, goddess of streams. She is generally paired with An-kung, a god of sailors. *See also* An-kung; Hsi-Ho; Shengmu; Shiu-mu niang niang.

T'ien-Kuan (China) *see* San Kuan.

Tien-Kuan *T'ien-Kuan* (Taoist; China)
God of happiness. The Agent of Heaven, a god with the power to bestow happiness and well-being. One of a triad with Ti-Kuan and Shui-kuan. On special family occasions and before the performance in a theater, Tien-Kuan appears dressed in the robes of a mandarin and carrying a scroll filled with good wishes for those present. *See also* San Kuan.

Tien Mu *Tien-mu* (China)
Goddess of lightning. She works with Lei-Kung, the thunder god. She uses mirrors to produce flashes of lightning. Tien Mu is possibly the wife of Lei-Kung (also called Kei-Kung). She is associated with the Feng-Po, Jade Emperor, the Dragon King, Yu-Tzu and Yun-T'ung. Tien Mu is shown standing on a cloud holding two mirrors above her head. *See also* Kei-Kung.

T'ien Pao (China) *see* Cheng Wu; Yu Ch'ing.

T'ien-Shang (China) *see* T'ien Hou.

T'ien Tsu (China) The father of husbandry.

T'ien-Wang (China) *see* Men Shen; Ssu ta Chin-kang.

Tien-Wang (Buddhist; China)
Also known as: *Mo-Li.*

Deities of the doors. The door deities are four brothers who are guardians of the four directions. Their symbols are a sword, a guitar, an umbrella and a marten (animal) which they use to control the elements. They are the same as Vaisravana, Virudhaka, Virupasa and Dhrtarastra of India. *See also* Men Shen; Ssu Ta Chin-Kang; Ts'in Shu-Pao.

Tigranes (Iranian) *see* Nabu.

Tigris (Mesopotamia)
The sky god Anu poured the Tigris river from a great water pot. In another myth, Anu impregnated Kumbaris with the Tigris after being castrated by him. *See also* Anu (B).

Tii (Polynesia) *see* Atea; Tane; Tii-Maaraatai; Tiki.

Tii-Maaraatai (Polynesia)
Also known as: *Ta'aroa, Tane, Tii, Tiki.*

The mortal form of the creator god, Ta'aroa. He is the first man, considered evil. He was created by Ta'aroa from earth, and he was clothed in sand. A wife, named Hina, was created for Tii-Maaraatai. A white heron is associated with him. *See also* Atea; Hina; Ta'aroa; Tane; Tiki.

Tii-Tapu (Polynesia) *see* Atea; Tiki.

Tii-Tokerau (Polynesia)
Also known as: *Tahiti Tokerau.*

The goddess Tii-Tokerau was blinded and held prisoner by the god Puna. He also murdered her husband, Wahieroa. The great hero-god Rata rescued his mother, Tii-Tokerau. *See also* Rata.

Ti'in (China) *see* Tien.

Tiitii (Samoa) *see* Maui.

Tijuskeha (North America) *see* Ioskeha.

Tiki (Marquesas, Society Islands; Maori People, New Zealand)
Also known as: *Ki'i* (Hawaii), *Ti'i, Tii.*

Creator. The Maori replaced Tane with Tiki, and made him the husband of Hine. Once thought of as the first man, he is an artisan and messenger of Tane and represents virility. The Maori people called Tane's reproductive power and penis Tiki, while others used Tiki, Ti'i or Ki'i as the name for a separate deity. In Hawaiian mythology, Tiki is the husband/brother of Hina-famed-in-story, who was adept at using magic. When Tiki fell seriously ill, Hina-famed-in-story tried her magic and it did not work. Tiki succumbed and with him all mankind. *See also* Ihoiho; Tane; Tangaroa; Ti'i.

Tiki-Kapakapa (Polynesia, New Zealand) *see* Tikitohau.

Tikitohua (Polynesia, New Zealand)
First bird. In his last attempt to have a human child, Tane took Hine-ahu-one as his wife. First she gave birth to an egg that became Tikitohau, the ancestor of all birds. Then she gave birth to Tiki-kapakapa who was the first female human. *See also* Hine-ahu-one; Papa; Tane.

Tiksnamanjusri (India)
"Charming Splendor." A manifestation of Manjusri, the god of learning, speech, science and wisdom. *See also* Manjusri.

Til-bu-ma (Tibet)
Til-bu-ma is another name for Kinkini-Dhari, the serpent-headed door-keeper of the north.

Tilo (Baranga People, Africa; Mozambique)
Tilo, the storm god, is present in every rain storm. His voice is heard as the thunder. This god is connected with all that is mysterious in the universe.

Tilottama (India) A Nymph. *See also* Arjuna.

Timirau (Polynesia) *see* Tinirau.

Timi-iti (Polynesia)

In the beginning, Ta'aroa, the supreme deity, developed himself. He existed in Fa'a-ti, the place within the shell named Timi-*iti*. The outer portion of this shell, named Rumia, existed before creation, in a primeval void of darkness named Po. *See also* Ta'aroa.

Timo-Taata (Polynesia)

Creator god. Second to Ihoiho. *See also* Ihoiho.

Timondonar *Tamendonar, Tamanduare* (Tupi-Guarani People, Brazil) *see* Ariconte.

Tina *Tinia* (Etruscan)

He is the chief god of the people. With the goddess of wisdom, Minerva, and Cupra, the goddess of fertility, he is a member of the Great Triad. He is represented as a thunderbolt. As chief god, he has three thunderbolts and Minerva and Cupra have one each. Tina, Uni and Minerva became the Capitoline Triad, imposed on the Romans to replace Jupiter, Mars and Quirinus. Tina exhibits traits similar to the great Zeus. Some say he is identified with the Roman Summanus. An authority calls Summanus an epithet, "probably of Hades, referring to his power over the night sky." *See also* Cupra; Minerva.

Ting (Teutonic) *see* Thing.

Tinga (Greek) *see* Antaeus.

Tingir (Beltirs) *see* Tangri.

Tinia (Etruscan) *see* Tina.

Tinilau (Polynesia) *see* Tinirau.

Tinirau *Timirau, Tinilau* (Polynesia)

Also known as: *Kinilau, Sinilau.*

God of the Ocean. King of fish. Tinirau is generally thought of as the lover of Hina or Ina, as she is called in some cases. He lived on Motu-tapu or Vavau (the sacred islands). Motu-tapu was given to him by the great goddess, Vari-ma-te-takere. Tinirau has two forms and two faces. One form was human, the other was fish-like. *See also* Hina; Ina; Maui; Ru; Rupe; Vatea.

Tiphys (Greek)

Until his death, Tiphys, the son of Hagnias or Phorbas and Hyrmina, was the pilot of the Argos. The subsequent pilot was Ancaeus. *See also* Actor (B); Argonauts.

Tir (Iranian, Persian)

This demon of fatal accidents is the son of Iblis and the brother of Awar, Dasim, Sut, and Zalambur. *See also* Azazel; Tishtrya; Tiur.

Tir na-nog *Tir na n'og* (Celtic) *see* Tuatha De Danann.

Tirawa (Pawnee People, North America)

Also known as: *Atius Tirawa, Shakura, Tirawa Atius.*

A creator deity known as the Great Power or the Great Father, Tirawa lives in heaven with his wife Atira. He is in charge of the other gods. Knowledgeable about astrology, he placed Shakuru, the sun, in the heavens to give daylight, and Pah, the moon, for light in the evening. He set the Evening Star who was called Mother of All Things, the Morning Star (a soldier god) to guard the east, the Pole Star for the north and the Death Star for the south. Tirawa then placed four other stars as supports for the sky. He is also the god of good buffalo hunting. Some think of him as a god of thunder or a god of the sun. In the Creation Legend, Tirawa attempted to destroy the world by fire, but it was extinguished by a great deluge. *See also* Kitshi Manito; Pah; Wakonda.

Tirawa Atius (Pawnee Indian) *see* Tirawa.

Tiresias *Teiresias* (Greek)

Deified mortal. A Theban whom the gods blinded. In compensation for the loss of his sight, they gave him the power of prophecy. Tiresias is associated with Athena.

Tisandrus (Greek)

He is the son of Jason, the Argonaut, and Medea. *See also* Jason; Medea; Pheres (A).

Tishtrya *Tir* (Chaldean, Persian)

A yazata (celestial being), Tishtrya is in constant battle with the life destroying demon of drought, Apaosha. Tishtrya is Sirius, the dog-star, and a god of rain. In the *Bundahish* (q.v.), he is said to be the primeval producer of all water. In the "Yashts" (Zoroastrian hymns to divine spirits), he is shown as the continual source of water, the protector of Aryan lands, the lord of all stars, the giver of children and the victor over sorcerers. He produced the first rain at the creation. Each raindrop became as big as a bowl so the earth was covered to the height of a man. From the rains, the cosmic ocean Vourukasha was formed. When prayers reach him during droughts, he descends to Vourukasha as a white horse with golden ears to battle Apaosha, who appears as a dark horse. When he is able to overcome the demon, Vourukasha boils over. The vapors rise and are blown to earth. In one battle with Apaosha, he was losing ground. Ahura Mazda heard Tishtrya's cries of despair and offered prayers and sacrifices on his behalf. This gave him the strength of ten horses, ten camels, ten bulls, ten mountains and ten rivers and he overcame Apaosha, and the waters flowed freely. The fourth month of the year, June-July, is dedicated to him. During the first ten days of this period, he is said to take the form of a fifteen-year-old male, an age thought to be ideal in Persian thought. In the second ten days he takes the form of a bull and in the third, the form of a horse. It was in these forms that he created Vourukasha. In Chaldean astrology, Tishtrya as the dog-star is venerated with Hvare-Khshaeta, the sun; Mah, the moon; and Anahita, who was identified with the planet Venus. Tishtrya is depicted as a bull with golden horns or as a beautiful young man of about fifteen years of age. In this form, he is appealed to by believers for male children and wealth. Sometimes he is depicted in female form. *See also* Ahura Mazda; Aktar (The); Anahita; Apaosha; Bundahish; Hapto-iringa; Hvare-Khshaeta; Mah; Rapithwin; Sirius; Tir; Vourukasha (B); Yazatas.

Tisiphone (Greek)

Vengeance. One of the three Erinyes, Tisiphone wreaks vengeance on the evil. Her sisters are Alecto and Megaera. *See also* Erinyes; Eumenides.

www.ebook3000.com

Titae-Aretia (Greek) *see* Aretia.

Titaea (Greek)
An epithet of Gaea, goddess of the earth, and Rhea, mother of the gods (qq.v.).

Titaea Magna (Greek) *see* Aretia.

Titania (Anglo-Franco) *see* Alfheim.

Titans (Greek)
Giants. The Titans, who preceded the Olympian gods, are the giant, half-man, half-snake children of the god of the sky, Uranus, and the earth mother, Gaea (who are the offspring of Nox, meaning night). The Giants waged a ten year war with Zeus in which they were ultimately conquered and imprisoned in a cavern near the underworld, known as Tartarus. The Giants names are Agrius, Alcyoneus, Aloeus, Anax, Anteaus, Clytius, Cyclops, Enceladus, Epihialtes, Gration, Hecatonchires, Hippolytus, Mimas, Pallas, Polybotes, Porphyrion, Rhoetus, Thoas, Thoon and Tityus. The Cyclopes are the one-eyed monster giants: Arges, Brontes, and Steropes (some add Geraestus and Acmonides). The Hecatonchires, Briareus, Cottus and Gyges, are each equipped with 50 heads and 100 hands. *See also* Cyclopes; Gaea; Hecatonchires; Nox; Themis.

Tithonus (Greek)
Deified mortal. Son of Laomedon and brother of Priam, for whom his wife, Eos, secured immortality. Because she forgot to ask also for eternal youth, he continued to grow older until Eos changed him into a grasshopper. *See also* Eos; Priam.

Titlacauan (Mexico, Aztec) An aspect of Tezcatlipoca (q.v.).

Tityos (Greek) *see* Tityus.

Tityus *Tityos* (Greek)
A Euboeoan giant, Tityus is the son of Gaea (the earth) or Zeus and Elara (the daughter of Orchomenus). After Tityus attempted to rape Leto, who is the mother of Apollo and Artemis, he was killed either by Zeus or Apollo and Artemis. He was sent to Tartarus, the underworld, where his regenerating liver is ripped apart and eaten daily by vultures. *See also* Apollo; Artemis; Giants; Tartarus; Zeus.

Tiu (German) Name for Zeus.

Tiur (Armenia; Possibly Babylon, Persia, or Iran)
Also known as: *Tir* (Iranian).
The scribe of Aramazd who writes what Aramazd dictates about the events of each human life. He is probably a deity of writing and eloquence. Tiur is identified with the Greek Apollo, the prophet god of healing and music, and as a writer, Tiur is also identified with Nabu of the Babylonians and Hermes of the Greeks. *See also* Aramazd.

Tiw (Teutonic) *see* Tyr.

Tiwaz (Teutonic) *see* Tyr.

Tjausul and Othale (Teutonic) Deities of restlessness.

Tjikantja Brothers (Aborigine People, Australia)
Creators. Sky gods who created all things on earth.

Tjinimin the Bat (Australia) *see* Rainbow Snake.

Tlacauepan (Aztec, Mexico)
Magician. Tlacauepan is the younger brother of Tezcatlipoca (who is also Huitzilopochtli) and Titlacauan. Skilled magicians and adversaries of Quetzalcoatl, they tried to drive Quetzalcoatl from power.

Tlachgo (Celtic) *see* Eire.

Tlacht (Celtic) *see* Eire.

Tlahuitzin (Aztec) *see* Yappan.

Tlahuizcalpantecuhtli (Mexico) *see* Tlauixcalpantecuhtli.

Tlaloc (Aztec People, Mexico)
Also known as: *Atonatiuh, Chac* (Mayan) *Cocijo* (Zapotec), *Dzaui* (Mixtec), *Muye* (Otomi), *Nahualpilli, Tohil* (Quiche of Guatemala).
Tlaloc is the god of thunder, rain, moisture, and mountains. He is one of the four sons of Ometecuhtli and Omeciuatl. He was worshiped as a creator god in Mexico before the Aztecs conquered the region. He lived in the mountains with the goddesses of grain. His mate, who is sometimes called his sister, is Chalchihuitlicue, the "Emerald Lady." The rain gods known as the Tlalocs are his children. Huixtocihuatl, the goddess of salt, is his eldest sister. Infants and children were sacrificed to Tlaloc. He is the god of the south, and was the ruler of the sun of the third universe, which was consumed by fire. Tlaloc is also the lord of the eighth hour of the day and the ninth hour of the night. In some renditions of myths involving Tlaloc he is known as the husband of the flower-goddess Xochiquetzal. His home is in Tlalocan. Tlaloc is depicted with a mask of serpents similar to that of Quetzalcoatl, except Quetzalcoatl has only one serpent. His incense is the smell of burning rubber. Some of the legends attributed to Tlaloc are similar to those of Quetzalcoatl (q.v.). *See also* Atonatiuh; Chalchiuhtlicue; Choc Mol; Huitzilopochtli; Iztac Ciuatl; Lords of the Day Hours; Lords of the Night Hours; Ometecuhtli; Quetzalcoatl; Tezcatlipoca; Tlalocan; Tlaloques.

Tlalocan (Mexico, Aztec)
Also known as: *Mount Tlaloc, The Place of Tlaloc.*
Abode of the Rain God. In the Postclassic period, Tlaloc lived in magnificently decorated mountain caves. By the time of the Conquest, he had moved up to the fourth level of the upperworld, known as Tlalocan, where he lives with his consort, Chalchihuitlicue, and remains the ruler.

His tenants are all dead souls who died in the water, including flood water or a disease associated with water; the souls of dead Dwarfs; and souls of everyone who lived with a handicap. Tlalocan is a tranquil place, a place of abundance. The air is filled with the scent of flowers and the music of song is always heard in the background. All souls in Tlalocan stay for four years before they return to earth. *See also* Ciuateteo; Xolotl.

Tlalocs *Tlaloques* (Aztec)
Minor rain gods who are the children of Tlacoc (q.v.).

Tlaloques (Aztec) *see* Tlaloc.

Tlaltecuhtli *Tlaltecutli, Tlatecutli* (Aztec People, Mexico)
Also known as: *Coatlicue, Earth Lord or Earth Lady.*
The name of this giant monster, who looks like a crocodile,

indicates the male gender although most depictions indicate the female gender. Once, when the earth was covered in water from the Great Deluge that had destroyed the fourth age, Tlaltecuhtli was swimming around looking for flesh to eat. Quetzalcoatl and his companion, Tezcatlipoca, changed themselves into serpents and dove into the waters. They grabbed Tlaltecuhtli and ripped her in half. To please the gods they threw one half to the sky and it became the heavens and the stars. The other half became the surface of the earth. Other gods came to earth to comfort her. Tlaltecuhtli cried during the first night for the hearts of men to eat. Fruit would not console her unless it was sprinkled with the blood of men. She is one of the thirteen Companions of the Day who preside over the daylight hours. She is invoked by midwives when infant warriors threaten to kill the mother. Prayers to Tezcatlipoca often invoked Tlaltecuhtli as the sun. Tlaltecuhtli is usually represented with claws at the elbows and knees, a full-face death's head at the back, and skulls and crossbones at the sides. Often she is depicted as a crouching figure in the the birth position, head upturned with a grinning mask, her mouth open showing flint blades. On her back there is the symbol of a skull. Sometimes she is represented as a toad swallowing a stone knife. Under the name Tlatecutli she is a form of Cihuacoatl or Tonantzin. She is associated with Tonatiuh and Tlaleutli. Tlaltecuhtli is a variant of Coatlicue. *See also* Chalchiuhtlicue; Mictlantecutli; Tepeyollotl.

Tlaltecutli (Aztec) *see* Tlaltecuhtli.

Tlanit Pene Baal (Carthage) *see* Tanit.

Tlanuwa (Cherokee Indian)

Deified bird. The Great Hawk, a magic bird. Tlanuwa is the same name the Natchez call their magical bird with metal feathers.

Tlaoque (Mexico) *see* Tlaloc.

Tlapallan (Aztec People, Mexico)

The Bright Land. Quetzalcoatl went to Tlapallan when he was driven out by the evil magicians. *See also* Quetzalcoatl.

Tlatecutli (Aztec) *see* Tlaltecuhtli.

Tlauixcalpantecuhtli *Tlahuizcalpantecuhtli* (Aztec People, Mexico)

Also known as: *Quetzalcoatl, Venus.*

"Lord of the House of Dawn." Lord of the twelfth hour of the day. When the sun (personified as Huitzilopochtli) was in a particular position in the sky in relation to the position of Venus, the planet (which is Tlauixcalpantecuhtli) and Tianquiztli (the Pleiades), special rituals took place. Tlauixcalpantecuhtli is an aspect of Quetzalcoatl. *See also* Acatl.

Tlazolteotl (Mexico) *see* Tlazolteutl.

Tlazolteutl *Tlazolteutl-Ixcuina, Tlazolteotl* (Aztec People, Mexico)

Also known as: *Ixcuiname, Teteoinan, Teteoinnan, Toci.*

"Sacred Filth Eater." "Lady of Witches."

Moon Goddess. Earth Goddess. Goddess of Excrement. Goddess of Purification, and Curing. Goddess of Love and Fertility. Goddess of Childbirth. Lifegiver. Forgiver of Sins. Goddess of Sexual Pleasure. Patron of Gambling. Great Spinner of Thread and Weaver of the Fabric of Life. One of the nine Lords of the Night Hours. Patron of the Day Ocelotl, and the Trecena 1 Ollin in the Tonalamatl (Aztec calendar). Once in a lifetime, confession could be given to a priest. This act was usually delayed until it was thought that age would nullify temptation. The "sinner" would appear before the priest and list all misdeeds. Wrong-doing would include disobeying the gods, deviating from the sexual mores of the community, cowardice during battle, and neglect of sacrifices. Offerings were made to the gods, and absolution was granted by Tlazolteutl's priest. If the confession was honest, Tlazolteutl would absorb the sins of the confessor, and purify the soul. Tlazolteutl could bring tranquility to the home and bestow fertility. Paradoxically, it is Tlazolteutl who tempted Quetzalcoatl. She is the power behind all magic in the Aztec world. Cinteotl, god of corn, is her son; another child is the eternally young Xochiquetzal. (Xochiquetzal was used by the gods to test the virtue of the aesthetic Yappan. Yappan succumbed to her beauty and was killed by the demon Yaotl.) As Tlazolteutl she appears nude, riding on a broom. She wears a horned headdress with a crescent moon and she holds a red snake. She also has a crescent moon decoration on her nose. Sometimes the area around her mouth is painted black. Tlazolteutl represents the planet Venus. She is often depicted wearing a flayed human skin (which represents her ties with the fertility and renewal of spring). As Ixcuiname, she is the spouse of Mictlantecuhtli, the lord of the underworld. Tlazolteutl is associated with her daughter Xochiquetzal, Toci the patron of midwives, and she is affiliated with Mayahuel, the goddess of maguey. *See also* Chalchiuhtlicue; Itztli; Ixcuiname; Ixmacane; Legend of the Four Suns; Lords of the Day Hours; Lords of the Night Hours; Mayahuel; Quetzalcoatl; Tlahuizcalpantecuhtli; Toci; Yappan; Xipe Totec; Xochiquetzal.

Tlazolteotl (Mexico) A variant spelling for Tlazolteutl.

Tlehanoai (Apache, Navajo, Papago People, North America)

"Carrier of the Night." A moon god.

Tlenamaw (Haida, Kwakiutl, Tlingit, Tsimshian People, North America)

Dragon. A monstrous dragon.

Tlepolemus (Greek) *see* Helen.

Tletonatiuh (Aztec)

Also known as: *Tonatiuh.*

The sun. Men were sacrificed so their blood would nourish Tletonatiuh. He is usually associated with Tlaltecutli, Huitzilopochtli and Tezcatlipoca in sacrifice. *See also* Huitzilopochtli; Legend of the Four Suns; Mictlan; Mictlantecutli; Tezcatlica; Tlaltecutli.

Tloquenahuaque *Tloque Nahuaque, Tloque Nauaque* (Aztec; Toltec People, Mexico)

Also known as: *Chicomexochit, Citalicue, Citlallatonac, Ipalnemoani* ("He Who Is Very Near"), *Ipalnemohuani, Omeciuatl, Ometecutli, Tonacaciutl, Tonacatecutli.*

"Lord of all Existence." High god or creator. Ancient Toltec god. The unknown god, creator of all things. Tloquenahuaque ruled the first of four or five worlds, known as the "water sun." After 1716 years it was destroyed by floods and lightning. He created the first man and the first woman. Other than a nine

www.ebook3000.com

3. Picture a crack in the middle of your forehead and let the heavenly light shine into the brain; pull the crack open and let the light reflect into the organs.
4. Close the third eye. Again, open. Pull: open-close-open. And, close. With the third eye open, the light from the heavens shines into your brain and reflects down to all your organs. Open and close the third eye 3 - 9 times.



Fig. 3.32 *Look as you smile into the Universe in front of you.*



A. **B.**

Fig. 3.33 A. *The Middle of the Finger hooks into the third eye and reflects down into the Organs.* **B.** *Pull open the Third Eye; let heaven open and shine its light into the Brain.*

story building erected in his honor, there are no depictions or statues of Tloquenahuaque. *See also* Ipalnemoani.

To-Kabinana and To-Karvuvu (New Hebrides, Polynesia)
First humans. In legend a being (god) drew figures of men on the ground and sprinkled them with his blood. They came to life as To-Kabinana and To-Karvuvu. To-Kabinana climbed a coconut tree and threw down two yellow nuts which burst on impact and changed into two women. To-Karvuvu did the same but his changed into ugly women. In some various versions the two first men exchanged or stole coconuts from each other and caused the differences in dark and light races of people. In some tales one of the two is credited with creating death, and teaching the art of fire, building houses and other benefits of mankind. Some of the tales are similar to those of Qat (q.v.).

To-Kwatsu (Japan) *see* Jigoku.

To-Matauenga (Polynesia)
Supreme god. Son of Rangi and Papa. God of man. *See also* Rangi.

Toafa (Samoa) *see* Foge and Toafa.

Tobadzistsini (Apache, Navajo, Papago People, North America)
War god. Child of the Waterfall, a war spirit.

Tobardasum (Saora People, India) God of the banyan tree.

To'bilhaski'di (Navajo Indians)
The first world. At the east was a place called Tan, the south a place called Nahodoola and west, a place called Lokatsosakad. In the east at Essalai where was located Leyahogan whose chief was Tieholtsodi. The chief of the south was Thaltlahale and the chief of the west was Tsal. The chief of the north was Idni'dslkai. In the west was a place called Tse'-Iitsibehogan where lived the twelve first people: Holatsi Dilyi'le who were dark ants; Holatsi Litsi, red ants; Tanilai, dragon flies; Tsaltsa, yellow beetles; Wointli'zi, hard beetles; Tse'yoali, stone-carrier beetles; Kinli'zin, black beetles; Maitsan, coyote-dung beetles; Tsapani, bats; Totso', white faced beetles; Wonistsidi, locusts; and Wonistsidikai, white locusts.

Tocay (Peru) *see* Manco Capac; Tahuantin Suyu Kapac.

Tochtli (Aztec)
God of the south. One of four year-bearers or year gods. Tochtli is in charge of the south region. He is god of those people who reside in that space and time. There is some disagreement as to which god was in charge of the North. Various writers place Tecpatl and Texcatlipoca in this function. *See also* Acatl; Calli; Tecpatl.

Toci (Aztec People, Mexico)
Mother goddess of the earth and curing. She was also identified with war. *See also* Tlazolteutl.

Todote (Samoyed of Siberia) God of evil and death.

Tohil (Mexico) *see* Quetzalcoatl; Tlaloc; Xumucane.

Tohil-Heumac (Mexico) *see* Quetzalcoatl.

Tokakami (Mexico)
God of death. Described as black and blood-smeared who come from the underworld to devour the Indians.

Tokay (Inca) *see* Ayar Uchi; Manco Capac; Viracocha.

Tokelau *Tokelo* (Polynesia)
Also known as: *Tui-Tokelo.*
Supreme deity. Similar to Ta'aroa (q.v.)

Tokelo (Polynesia) *see* Tokelau.

Tolocan (Aztec People, Mexico) Home of the gods.

Toma (Tibet)
Also known as: *Vajra-Yogini.*
Toma is a wrathful goddess associated with Yogic rites. Her followers are instructed to visualize her red in color, with three eyes, dancing nude, except for symbolic ornaments. She is an aspect of Vajra-Yogini (q.v.). *See also* Dorje-Naljorma.

Tominagatoo (Warrau People, South America)
Also known as: *Kononatoo.*
Possibly a creator. No function shown. Both names indicate a great father figure, but not necessarily a god.

Tomituka (Aborigine People, Australia)
Monsoon rain goddess. *See also* Pakadringa.

Tonacacihuatl (Aztec People, Mexico)
She is the wife of Tonacatecuhtli. *See also* Chicomecoatl; Omeciutal; Ometecutli; Tonacatecuhtli.

Tonacaciuatl (Mexico) *see* Tonacacihuatl; Xochiquetzal.

Tonacaciutl (Mexico) *see* Omeciutal.

Tonacajoha (Mexico) *see* Cinteotl.

Tonacatecuhtli *Tonacatecutli* (Male), *Tonacacihuatl or Tonacaciutl* (Female); (Aztec People, Mexico)
Also known as: *Chicomexochit, Chicomexochitl, Omeciutal, Ometecutli.*
Creator and food giver. Tonacatecuhtli separated the waters from the heaven and was the first Lord of the World. He is usually considered a bisexual deity and is known under various names. In most cases he is paired with Tonacaciutl, who is the female principle. He is shown with a crown filled with grain. He is the same as Ometecuhtli (q.v.). *See also* Huitzilopochtli; Ipalnemoani; Ometecuhtli.

Tonacatecutli and Tonacaciutl (Aztec, Toltec People, Mexico)
Also known as: *Citlallatonac and Citalicue, Lord and Lady of Our Flesh, Lord and Lady of Our Sustenance.*
Male/female version of Tloque Nahuaque. Some say these two represent a single deity as a divine pair. In some versions they gave birth to red Tezcatlipoca (Xipe Totec or Camaxtli), black Tezcatlipoca, white Tezcatlipoca or Quetzalcoatl; blue Tezcatlipoca; Huitzilopochtli. *See also* Citalicue; Citlallatonac; Tloque Nahuaque; Tloquenahuaque.

Tonantzin (Aztec People, Mexico)
Also known as: *Cihuacoatl, Ciuacoatl, Coatlicue, Ilamatecutli, Itzpapalotl, Tamazcalteci, Teteoinnan, Tlatecutli.*
The Mother Goddess. Earth goddess. Her best known name was Ciuacoatl, but her titles, Old Goddess, Obsidian Butterfly, and Grandmother of the Sweat-Bath, and Mother of the Gods indicate she was worshiped in many ways, but primarily she

was regarded as an earth deity. In her various roles she is represented as a toad swallowing a knife or a deer. *See also* Ciuacoatl; Coatlicue.

Tonapa (Peru) A name for Virocecha, the teacher of the world.

Tonatiuh *Tonatiuhichan* (Aztec People, Mexico)
Also known as: *Piltzintecutli.*
War or sun god. An ancient sun-god and god of warriors. His home, the House of the Sun, was the home of the warriors. Tonatiuh was fed and cooled by human sacrifice. Each day he was raised to the zenith by warriors, and in the evening, women who died in childbirth lowered him to the darkness of the underworld. Tonatiuh was also known as Piltzintecutli. Those who die in his service are rewarded with eternal life. He is also said to be the ruler of fate. In one version Tonatiuhichan is a type of heaven where warriors who died in battle became Quauteca (eagle's companion) and went to this eastern paradise. Others who die go either to Tlalocan (Tlaloc's home) or to Mictlan. Tonatiuh is depicted as the sun in the center of the Aztec calendar. Associated with Meztli (the dawn) and Tlahuizcalpantecuhtli. *See also* Tezcatlipoca.

To'nenile *Tonenili* (Apache, Navajo, Papago People, North America)
"Water Sprinkler." To'nenile ia a rain god and trickster. He is shown carrying a water pot. It is To'nenile who saved the people from Ticholtsodi, the water monster.

Tonenili (North America) *see* To'nenile.

Tonga-Iti (Polynesia) *see* Tangaroa.

Tongaiti (Polynesia) *see* Tangaroa.

Tootega (Eskimo)
Deity of boats. She is able to walk on water. She lives in a stone house on an island. Said to look like a little old woman.

Tooth Grinder (Norse) *see* Tanngnost; Thor.

Tope (A) (Norse) Deity of insanity.

Tope (B) (Buddhist) *see* Stupa.

Topielce (Slavic) Spirits who dwell in lake water.

Topiltzin *Toplitzin-Quetzalcoatl* (Toltec) (Mexico)
Also known as: *Ce Actl, Hueymac* (Aztec) *Papa, Xipe.*
Probably a deified mortal. Some versions claim this was the name of the priest who performed the actual slaying of the victim of sacrifice. He is shown with a red beard turning slightly white. *See also* Mixcoatl; Xipe Totec.

Toplitzin-Quetzalcoatl (Mexico) *see* Topiltzin

Tora-Galles (Lapp) *see* Hora-Galles.

Torch (Indo-European, Armenian)
Also known as: *Torx.*
Demons. Mythical demon of gigantic or dwarfish size. Usually benevolent, but sometimes a mischievous, spiteful genie. He falls into the same class as both the Telchines and Cyclopes. This group of spirits were often referred to as blacksmiths. Similar to the Telchines and Cyclopes of Greece.

Tore (Pygmy of Africa)
God of thunderstorms. Some pygmies seized fire and ran off with it while Tore pursued them on his swing, up to the sky and down to the valley, in vain. He returned home to find his mother dead. As punishment he decreed that men should also die. Tore is interchangeable with mythical animals. Also known as lord of the dead.

Torgarsoak (Eskimo) *see* Tornarsuk.

Tornait (Eskimo) *see* Tornaq.

Tornaq (Eskimo)
Also known as: *Innua, Inua, Inuat, Tornait, Torngak.*
Spirit. A spirit being, the familiar of a shaman (Angakok). The Tornaq is called the owner or in-dweller of everything in nature. Normally invisible, but as Tornait they are helpers or guardians and sometimes appear as a light or fire prior to the death of someone. They are ruled by Tornarsuk, who is sometimes called the Great Tornak. *See also* Ingnersuit (Cliff Inua); Inua; Sedna; Umiarissat (Sea Inua).

Tornaq (Eskimo) *see* Inuat.

Tornarsuk (Inuit; Eskimo)
Also known as: *Tornatik or Tornarsuk* (Greenland), *Torngarsoak* (Labrador), *Torngasoak, Tungrangayak* (Alaska).
Ruling spirit. A higher spirit than the Tornaq. Generally thought of as the ruler of the Tornaq. Known in Alaska as Tungrangayak. Variously depicted as bear, a tall man with one arm, a tiny figure, and some say he is invisible. Some say his body is covered with eyes. Some say he is a sea monster or a large white bear. Same as Torngak, Tornaq and Tungrangayak.

Tortali (New Hebrides)
Sun deity. Tortali, the god of the sun and day, discovered his wife, Avin (a mortal), was having an affair with Ul, master of the moon and night. Tortali drove her from the garden and ever since, women had the menstrual cycle and had to work in the earth for food.

Tortoise Shell Goddess (West Africa) *see* Isong.

Toru (Polynesian)
He is the god of the deep ocean. His function is to paint fish and seashells.

Torum (Ugarit) *see* Ec; Num; Tgorem.

Torx (Indo-European, Armenian) *see* Torch.

Tos-khan (Altaic, Tartars) *see* Bai Ulgan.

Tosotsu-Ten *Tosotsa-Ten* (Japan)
Also known as: *Ryojusen, Tushita.*
Tosotsu-Ten is the Japanese Buddhist "Heaven of Contentment" situated somewhere high in the sky. *See also* Gokuraku; Jodo; Miroku-Bosatsu; Ryojusen; Tushita.

Totates (Celtic) *see* Teutates.

Totepeuh (Mexico) *see* Mixcoatl.

www.ebook3000.com

Tou Mu (China)
Also known as: *Chandi* (India), *Marichi* (India), *Mo-li-chi.*
Supreme goddess. The goddess of the North Star. Known as the "Bushel Mother," she is the mother of nine sons, who were the earliest of earthly rulers. Her palace is the center of the stellar system, and all other stars revolve around it. Tou Mu holds sway over life and death, but she is beneficent and sympathetic in the use of her power. She writes down the time of the life and death of mortals and in this she is a goddess of destiny. She is depicted with three eyes and eighteen arms, holding weapons, the solar and lunar disks, a dragon's head, and five chariots in her hands. *See also* Chandi; Marichi (A).

Tou-Shen (China)
Goddess of disease. One of the Tao-shi or Ministry of Epidemics and a goddess of smallpox. She is said to punish those guilty of infanticide. Associated with Sha-shen. *See also* Chen-shen.

Tounela *Tuomela* (Finland) *see* Kipu-Tytto; Manala.

Touni (Finnish) *see* Kiyamat-Tora.

Toxeus (Greek)
Oeneus, the king of Calydon, and his niece, Althea, who later hanged herself, are the parents of Toxeus. He is the brother of Gorge, who, some think, was changed into a guinea fowl by the goddess of the hunt, Artemis. Toxeus is the half-brother of Deianeira, who commited suicide after accidentally killing Heracles (Deianeira was also turned into a guinea fowl after death by Artemis), and Meleager, the Argonaut and slayer of the Calydonian Boar. Meleager was also turned into a guinea fowl by Artemis. *See also* Althea; Artemis; Calydonian Boar Hunt; Deianeira; Meleager.

Toyo-kumu-no Mikoto (Japan)
"Rich Form Plain of Augustness." *See also* Ama-no-minaka-nushi.

Toyo-mike-nu (Japan) *see* Jimmu Tenno.

Toyo-Tama-Bime *Toyo-Tama-Bime-No-Mikoto, Toyo-Tama-Hime, Toyotama* (Shinto; Japan).
Sea goddess. Princess. Toya-Tama-Bime (Abundant Pearl Princess also called Lady Abundant Jewel) is the daughter of the ocean god O-Wata-Tsu-Mi. Her younger sister is Princess Tama-Yori-Bime (Jewel-Goodness-Princess or perhaps Spirit-Medium-Princess). They live in a castle on the bottom of the sea. She married Hikohohodemi (Prince Fire Subside), the son of Ninigi (Prosperity Man) and Kono-Hana-Sakuya-Hime (Blossoms-of-the-Trees-Blooming-Princess). She met her husband when he came to the ocean's depths in search of his brother Hosuseri's magic fishing hook. He was so happy with his new wife that he forgot his original intent. Three years later when he remembered, he was full of remorse. The magic hook was retrieved and O-Wata-Tsu-Mi gave him instructions to follow when he returned it to Hosuseri. He left for the upperworld (Japan) and was gone for a long time. Toyo-Tama-Bime, who was pregnant, decided to join her husband. She took her younger sister, Tama-Yori-Bime, on the journey. They settled in a small hut by the edge of the shore. When the time came to give birth, she warned her husband not to follow her into the hut. His curiosity prevailed and he spied on her through a window. Horrified, he saw that she had assumed the shape of a mammoth sea crocodile. The princess was deeply offended by her husband's actions. After the birth of her son, Amatupiko-Pikonagisa (Ama-tu-Piko-nasgisa-take-U-gaya-puki-apezu-no-mikoto), she gave the child to her sister and returned to her father's home. In later years, Tami-Yori-Bime married her nephew Amatupiko-Pikonagisa. They became the parents of the first emperor of Japan, Waka-mi-ke-nu-no-mikoto, also known as Toyo-mike-nu and posthumously given the name of Jimmu Tenno. Toyo-Tama-Bime and her father, O-Wata-Tsu-Mi, are represented in a combination of human and dragon form. For a description of their undersea castle, *see* O-Wata-Tsu-Mi. *See* Hikohohodemi for the early relationship of Hikohohodemi and Toyo-Tama-Bime and for details about the magic hook and Hikohohodemi's relationship with Hosuseri. For the events that transpired when he returned the magic fishhook to his brother, *see also* Amaterasu; Haya-akitsu-hime-no-kami (goddess of the sea); Hosuseri; Jimmu Tenno; O-Wata-Tsu-Mi.

Toyo-Tama-Bime-No-Mikoto (Japan) *see* Toya-Tama-Bime.

Toyo-Tama-Hime (Japan) *see* Toyo-Tama-Bime.

Toyo-Uke-Bime (Japan) *see* Amaterasu; Ukemochi.

Toyo-Uke-Hime (Japan) *see* Amaterasu; Ukemochi.

Toyo-Uke-Hime-No-Himi (Japan) *see* Amaterasu. *See also* Ukemochi.

Toyo-Uke-No-Kami (Japan) *see* Amaterasu; Ukemochi.

Toyotama (Japan) *see* Toyo-Tama-Bime.

Tpereakl (Pelew Islands)
Tpereakl is the wife of the sky god, Latmikaik. Typereakl lived in the sea where she gave birth to two sons and all fish. The fish built a tower which became the earth, and mankind was the result of the mating of gods and fish.

Traetaona (Persia) *see* Yima.

Trailokaya (Tibet) *see* Trailokyavijaya.

Trailokya-Vijaya-Raja (Tibet) *see* Trailokyavijaya.

Trailokyavijaya *Trailokya-Vijaya-Raja* (Buddhistic Hinduism, Tibetan Tantrism)
Also known as: *Akshobhya, Gozanze-Myoo* (Japan), *hJig-rTen-gsum-rgyal* (Tibet), *Jig-ten-sum-gyal* (Tibet).
Trailokyavijaya, a Dhyanibodhisattva, is the lord of the three Buddhist worlds known as Trailokaya. Trailokayavijaya corresponds to the Japanese Gozanze-Myoo, one of the Godai-Myoo (Five Great Kings), who are the protectors of Buddhism. He is thought to be a terrible aspect of Akshobhya. A grotesque figure, Trailokyavijaya has bristling hair, four faces, a forehead eye, and eight arms. He holds a bell, sword, hook and arrow in right hands and a discus, bow and noose in the left hands. He is shown with his right foot on Parvati, the Hindu great virgin goddess, who is one of Shiva's consorts, and his left foot on Mahesvara, the spouse of the goddess Uma, who is an incarnation of Parvati. In some depictions, he is shown trampling on

Shiva's head. His emblem is the ghanta (bell). *See also* Dhyanibodhisattvas; Godai-Myoo; Gozanze-Myoo; Parvati; Shiva; Uma.

Trambaka (India) *see* Shiva.

Tree of Many Seeds (Persia)
Two trees stand in Vourukasha, the cosmic ocean; the Tree of Many Seeds, from which all trees derive, and the Gaokerena tree, which will provide the elixir of immortality for all mortals at the renovation of the universe. In its branches lives the great Saena bird. When it beats its wings it breaks the branches, scattering the seeds which are then carried over the earth in the wind and the rain. *See also* Alburz (Mount); Haoma; Vourukasha.

Treta (India) *see* Tretayuga.

Tretayuga *Treta* (Hindu; India)
Part of the Kalpa cycle, Tretayuga lasts 1,296,000 years. In this cycle the god Dharma has only three legs and is red in color. Virtue is one-quarter less than perfect during this period. *See also* Dharma; Dwaparayuga; Kaliyuga; Kalpa.

Tri-Loka (India) *see* Triloka.

Triad, Capitoline (Roman) *see* Tinia.

Triad of Deities (Egypt) *see* Amum-Mut-Khons; Horus-Hathor-Harsomtus (Horus the Younger); Khnum-Anukis-Satis; Osiris-Isis-Horus (Harpocrates); Ptah-Sekhmet-Nefertem.

Triad of Elephantine (Egyptian) *see* Anukis.

Triambika (Hindu; India)
Wife of Rudra-Shiva. *See also* Devi; Rudra; Shiva.

Triloka (India) The Three Worlds. *See also* Bali (B); Loka.

Trimurti Trinity (Hindu; India)
The Hindu Trimurti consists of Brahma the creator, Vishnu the preserver and Shiva the destroyer. The symbol of this trinity is a,u,m, (pronounced om). Lakshmi, Sarasvati and Devi form a Trimurti of goddesses.

Trinavarta (India) Whirlwind, the Demon. *See also* Krishna.

Triopas (A) (Greek)
A Heliad. King of Rhodes. He is the son of the sun god, Helios and Rhode. *See also* Heliades; Helios.

Triopas (B) (Greek)
King of Thessaly. His parents are Poseidon and Canace. For the names of his siblings, *see* Canace. He married Hiscilla and became the father of Erysichthon, Iphimedeia and Phorbas. *See also* Erysichthon; Iphimedeia (A).

Triopas (C) (Greek)
He is the father of Pelasgus by Sois. *See also* Pelasgus (D).

Tripada (India) God of fever, usually malaria.

Triptolemus (Greek) *see* Abas (C); Demeter; Oceanus.

Trisala (India)
Also known as: *Priyakarini.*
The embryo of Mahavira ("Great Man") was transferred from the womb of Devananda to the womb of Trisala. She is the wife of the Kshatriya, Siddhartha. *See also* Mahavira.

Trishna *Trisna* (India)
She is the sister of the god of love, Kama, and daughter of Lakshmi. *See also* Kama; Lakshmi.

Trisiras (Hindu; India)
Possibly a three-headed water god. Trita, Aptya and Indra killed Trisiras and set his cows free. Some say Indra stole the cows. It was Trisiras' father, Tvashtri Tvastar, who forged Indra's bolt. Some say that Trisiras and Indra are half-brothers, and that Indra killed Tvastar. Trisiras is sometimes referred to as the twin of the goddess of the morning light Saranyu, and the son of Tvashtri. He is sometimes associated with the serpent Visvarupa, who is the son of Tvashtri. *See also* Saranyu; Tvashtri.

Trita Aptya *Thrita* (Hindu; India. Persian)
Trita is the slayer of the serpent Visvarupa. An air, water, lightning, moon, and storm god, he brought fire to earth in the form of lightning and prepared the elixir of the gods, soma. Not to be confused with Tretayuga of the Kalpa cycle. Comparable to the Iranian Thrita (q.v.). This myth is sometimes attributed to Agni or Indra. *See also* Agni; Indra; Soma; Trisiras; Varuna.

Tritogeneia (A) *Trigoneia, Tritonis* (Greek)
She is the daughter of Aeolus and some say the wife of Minyas, who was wealthy enough to build his own treasure house. *See also* Aeolus; Minyas.

Tritogeneia (B) (Greek)
Tritogeneia is a surname used for Athena.

Triton (Greek)
Also known as: *Tritons.*
Sea deity. A divinity of the sea, Triton is a son of Poseidon and Amphitrite or Kelaino. He makes the roaring of the ocean by blowing thorough his shell. Triton is human with fish tails for legs. He could be connected with the trident of Poseidon. He is also connected with the Muses. *See also* Amphitrite.

Tritonis (Greek)
She is the wife of Amphithemis. *See also* Acacallis.

Trivia (Roman) Trivia is the Latin equivalent of Artemis (q.v.). *See also* Diana.

Troezen (Greek)
Troezen is the son of Pelops and Hippodameia. *See also* Pelops.

Tronubeina (Teutonic) *see* Heimdall.

Tros (A) (Greek)
His parents are the wealthy king of Dardania, Erichthonius, and Astyoche. He is married to Callirrhoe. They are the parents of Assaracus, Cleopatra, Ganymede and Ilus. When Ganymede was kidnapped, he received two immortal horses from Zeus and a golden vine from Hephaistos. *See also* Callirrhoe; Cleopatra; Erichthonius; Ganymede; Hephaistos.

Tros (B) (Greek)
The son of Alastor, Tros was killed by Achilles in the Trojan War.

www.ebook3000.com

Tryambaka (India)
"Three-Mothered" or "Three-Eyed." *See also* Agni; Rudra; Shiva.

Tsagan-Sukuty (Mongol) *see* Ocirvani.

Ts'ai Lun (China)
God of stationers. Inventor of paper. Ts'ai is associated with Meng-T'ien, who made the first brush for writing, and Ts'ang Chieh, who invented writing.

Ts'ai Shen *Ts'shen Yeh* (China)
God of wealth. God of happiness. The widely venerated god of wealth. His birthday, which falls on the fifth day of the first month of the Chinese year, is celebrated with sacrifice and special acts of honor. The most common mortal identified with this deity was Chao Kung-ming although there were others. Ts'ai Shen owns a casket that holds an inexhaustible supply of gold. He is associated with Tseng-fu-ts'ai-shen, god of happiness, and Pi Kan, a deified mortal. *See also* Fu Shen; Shou Hsing.

Tsalu (Cherokee People, North America)
Tobacco. A name given to the tobacco plant by the Cherokees. It may or may not be a deity.

Ts'an Nu (China)
Also known as: *Ma't'ou Naing* (Lady with a Horse's Head).
Goddess of silkworms. Ts'an Nu, the goddess of silkworms, is the second-rank wife of the Jade Emperor. She is shown wrapped in a horse's skin.

Ts'ana-Pa (Tibet) "White Brahma." *See also* Brahma.

Ts'ang Chien (China)
Ts'ang Chien is the inventor of writing. He is associated with Meng T'ien, who invented the first brush for writing, and Ts'ai Lun, who invented paper. *See also* Meng T'ien; Ts'ai Lun.

Ts'ang Kie (China) *see* Ts'ang Chien.

Tsao Chun (China)
God of fire or furnace or hearth. *See also* Chung-liu; Tsao Shen; Tsao-Wang.

Tsao-kuo-chia *Ts'ao Kuo-kiu* (China)
He is usually found with Ho-hsien-ku, the only female in the group known as the "Eight Immortals." In some legends, he is the brother of an empress in the Sung dynasty. Tsao-kuo-chia is shown dressed in imperial robes, wearing a bonnet and holding a tablet. *See also* Arhats; Eight Immortals; Ho-hsien-ku.

Ts'ao Kuo-Kiu (China) *see* Tsao-kuo-chia.

Tsao Shen (China)
Also known as: *Chung-Liu, Tsao Chun, Tsao Wang, Tse Shen.*
Kitchen god. Prince of the Furnace. God of the Hearth. He was also known as Ch'an Tzu-fang, but in this form, dressed in yellow garments and having unkempt hair, he wasn't very popular. There is some confusion about Tsao Shen, Tsao Chun, Tsao-wang, and Ch'an Tzu-fang, since they were all gods of fire or furnace/hearth. The term Tsao can be used as furnace or stove. Associated with the Jade Emperor. Sometimes found with Oki-Tsu-Hiko and Oki-Tsu-Hime, both kitchen gods. *See also* Ho Shen.

Tsao-wang (China)
Also known as: *Tsao Chun, Tsao Shen.*
God of the Hearth. The hearth god, who resides in the home, near the hearth, keeps watch over the family. He makes his report before Tung Wang Kung, the Jade Emperor, when he appears once a year in heaven. He is assisted in his task by his wife, Tsao-wang nai-nai. When Tsao-wang has left the house on his mission to the Jade Emperor, the family offers sacrifice, and firecrackers are set off to guide his path. His way home is again indicated by firecrackers, and he is welcomed with sacrifice. He usually appears as an old man with a white beard sitting in an armchair with his wife beside him.

Tsaphon, Mount (Ugarit) *see* Zaphon.

Tse Shen (China) *see* Tsao Shen.

Tsects (North American Indian, Haida, Kwakiutl, Tlingit, Tsimshian)
Good spirit. Grandmother white mouse and a friendly spirit.

Ts'en-kuang (China) *see* Kshitigarbha.

Tseng Chang (China) *see* Mo-Li Ch'ing.

Tsentsa (Huron People, North America)
The good Creator-Twin. *See also* Heng.

Tseurima (India, Tibet) Cemetery goddess.

Tshindi (Navajo People, North America) *see* Anaye.

Ts'i-fu-shen (China)
Gods of happiness. Seven gods who give happiness.

Tsi-ku *Ts'iku* (China) *see* K'eng-san-ku.

Tsi-zhui (Osage People, North America)
Sky gods. The Tsi-zhui are known as the "Sky People."

Tsichtinaka (Acoma People, North America)
Guide. The guide of mankind during the emergence.

Ts'in-kuang-wang *Ts'en Kuang, Ts'kuang-wang* (China)
High god. Ts'in-kuang-wang replaced Yen-lo wang (also known as Yen-wang) as the chief of Ti-yu, the Chinese hell. He is the first god to see the dead. It is his function to receive the deceased and place them in front of the mirror known as Sie-king t'ai, which shows their history. After this he decides on which level of hell the soul is to be placed. *See also* Ti-yu.

Ts'in Shu-pao (China)
God of the doorway. He is usually paired with Hu King-te. Once they were generals of the T'ang Emperor. These two deities replaced Shen-t'u and Yu-lu. Ts'in Shu-pao is shown as a leaf on one half of the outer door of the residence. Hu King-te is represented as a leaf on the other half. *See also* Hu King-te; Shen-t'u.

Ts'kuang-wang (China) *see* Ts'in-kuan-wang.

Tsmok (Russia) *see* Domovoj; Zmek (Slavic).

Tsoede (Sudan) God of canoe builders, smiths, and fertility.

Tsotsil (Navajo People, North America)
Deified mountain. Magical boundary mountain.

Tsui'goab *Tsui'*(Hottentot People, Africa)
Also known as: *Dxui* (Bushmen), *Thixo* (Pondo, Xhosa People), *Tsui-Goab, Tsui-Goam, Tsuni Goam.*

Supreme god. Sky god. God of rain, storms and thunder. He fought and killed the evil being Gaunab (chief of the dead) and received a wound in his knee which gave him his name. Tsui'goab made the first man and woman or the rocks where they emerged. He is similar to or the same as Dxui of the Bushmen and Thixo of Xhosa and Ponda people of Africa. He may be the same as Haitsi-aibeb or Gurikhoisib. *See also* Gaunab; Heitsi-Eibib.

Tsui-Goam (Africa) *see* Tsui-Goab.

Tsuikiyomi (Japan) *see* Tsuikiyomi-no-mikoto.

Tsuki-Yomi (Shinto) Japan
Also known as: *Tsuikiyomi Mikoto, Tsuikiyomi-no-Mikoto.*

Tsuki-Yomi, god of the moon, and ruler of the night, was the son of Izanagi (Male who Invites) and Izanami (Female who Invites). He was born when Izanagi washed his right eye as he bathed in the sea following his return from Yumi, the world of the dead. Tsuki-Yomi, assigned the role of god of the moon and ruler of the night, played a minor role in Shinto mythology compared to two of his most famous siblings. His sister was the beautiful sun goddess Amaterasu and his brother Susanowo was the sea, thunder, rain and fertility god. Amaterasu was created from her father's left eye and Susanowo was born when his father washed his nose or sneezed. When smallpox was widespread, adherents appealed to Tsuki-Yomi for protection. For the Shinto creation myth, *see* Ama-no-minaka-nushi; Amaterasu; Hiurko; Izanagi and Izanami; Susanowo; Ukemochi.

Tsuikiyomi Mikoto (Japan) *see* Tsuki-Yomi.

Tsukiyomi-no-Mikoto (Japan) *see* Tsuki-Yomi.

Tsuni Goam (Africa) *see* Tsui'goab.

Ttlaya (Fox People, North America) A ghost.

Tu (Hawaii, New Zealand, Polynesia)
Also known as: *Ku* (Hawaiian), *Tu-matauenga, Tu-metua, Tu-of-the-angry-face.*

War god. Rangi is the sky father of Tu and Papa is the earth mother of Tu. When Rangi and Papa were cleaved together as sky and earth, they had already created Tane, Tangoroa, Tu, Rongo, Haumia and Tawhiri, who were within their warm embrace. There did not seem to be a way for the children to separate the parents. The children became restless in their cramped quarters. Tu suggested that they kill Rangi and Papa. Following their parents' separation, the brothers deserted Tu. His anger led him to catch the birds in Tane's forests, net the fish in Tangaroas' waters and pull from the ground the cultivated and uncultivated plants, which were the children of his brothers Tane and Haumia. In the Society Islands, legends replaced Tu with Oro, the son of and assistant to the creator, Ta'aroa. Known in Hawaii as Ku, he is the founder of the Ku family of war gods. He accepted human sacrifices. *See also* Ku and Hina; Papa; Rangi; Rongo; Ta'aroa; Tangoroa; Tawhiri; Tu-metua.

Tu-ka-nguha (Polynesia) *see* Tu-matauenga.

Tu-ka-taua (Polynesia) *see* Tu-matauenga.

Tu K'ang (China)
God of distillers. He is probably a mortal who discovered alcohol. Tu K'ang is generally associated with I-ti, the god of wine.

Tu-kariri (Polynesia) *see* Tu-matauenga.

Tu-mata-what-iti (Polynesia) *see* Tu-matauenga.

Tu-matauenga *Tu-ma-tauenga* (Polynesia)
Also known as: *Maru* (South Island of Maori), *Tu, Tu-ka-nguha, Tu-ka-taua, Tu-kariri, Tu-mata-what-iti, Tu-whake-ticke-tangata.*

God of War. An aspect of the god of war, Tu. Tu-matauenga is his name on the North Island; to the Maori of the South Island he is known as Maru. *See also* Maru; Maui; Papa; Po; Rangi.

Tu-Metua (Polynesia)
Also known as: *Tu, Tu-Papa, Tumateanaoa.*

Mother goddess. Papa is the goddess Tu-metua who is the daughter of Timatekore (Tima-te-kore) and his wife Tamaiti-ngava-ringavari. Papa is the consort of Vatea. They had five children: Tangaroa, Rongo, Tonga-iti, Tangiia, and Tane. In another legend, Tu-Metua is the sixth and final child of the great mother goddess Vari-ma-te-takere who created her from a bit of her right side. The mother gave Tu-Metua the land called Te-enua-te-ki which is located at the very bottom of Avaiki. She is sometimes linked with her nephew, Tangaroa. *See also* Papa; Rangi; Tangaroa; Vatea.

Tu-nui-ka-re (Oceanic) see Faumea.

Tu-Papa (Polynesia) *see* Tu-Metua.

Tu-qu-aat (Egypt) *see* Aaru.

Tu-te-wanawana (Polynesia) *see* Tu-te-wehi.

Tu-te-wehi (Polynesia)
Also known as: *Tu-te-wanawana.*

Father of reptiles. *See also* Ika-tere; Po; Tangaroa.

T'u-Ti (China) *see* T'u-ti Lao-Yeh.

T'u-Ti Lao-Yeh (China)
Also known as: *T'u-Ti.*

Deified mortal. This name is usually given to a high official after death, placing him in the category of a local god. Anyone could be made a T'u-Ti Lao-Yeh after death, but the position was not stable. Failure to avert one disaster meant the individual lost his divine status and a replacement was brought in immediately.

T'u-Ti Shen (China)
Also known as: *Hou-T'u Shen.*

Patron god of the soil. God of the Place. God of Walls and Moats. *See also* Hou-Tu.

Tu-whake-ticke-tangata (Polynesia) *see* Tu-matauenga.

Tua-heru (Egypt) *see* Ap-taui.

Tuamutef (Egypt)
Also known as: *Duamutef.*

www.ebook3000.com

Tuamutef, a jackal-headed god, is one of the four divine sons of Horus and Isis. He is the guardian of the east, and the Canopic guardian of the stomach. His brothers are Amset, Hapi, and Qebhsneuf. *See also* Amset; Hapy (A); Horus; Isis; Qebhsneuf.

Tuart Rert (Egypt) *see* Taueret.

Tuat (Egypt)

Also known as: *Duat, Khert Neter, Neter-khertet, Ta-Djesant, Ta-tchesert, Twet.*

The underworld or otherworld. Divided into twelve sectors or nomes, each of which has its own demons or ordeals that the deceased must pass in order to be worthy of life with Osiris. Sometimes the place is called Ta-djesant, Ta-tchesert, Neterkhertet, or Khert Neter. A river flows through this underworld realm into twelve sections. The gates separating the twelve sections (fields) are guarded with serpents and demons. Ta, the sun god, must know the names of the these monsters to secure passage. Reference is made to seven arrets or circles within the divisions. These arrets are guarded by a doorkeeper, watcher, and herald. The first by Sekhet-hra-asht-aru, Semetu, and Hukheru; the second by Tun-pehti, Seqet-hra, and Sabes; the third by Am-haut-ent-peh-fi, Res-hra, and Uaau; the fourth by Khesef-hra-ash-kheru, Res-ab, and Neteqa-hr-khesef-atu; the fifth by Ankh-em-fentu, Ashebu, and Teb-her-kehaat; the sixth by Aken-tau-k-ha-kheru, An-her, and Metes-hra-ari-she; the seventh by Metes-sen, Aa-kheru, and Khesef-hra-khemiu. All the other entrances are guarded by a serpent god and a host of other gods. The first division, or first hour, is the entrance which is guarded by the serpent, Saa-Set. The second division is guarded by Mehen. The third division (Tent-Baiu) is guarded by the serpent and arch-fiend Apepi. The fourth division is guarded by Tchetbi (possibly Tekhi). The fifth division is guarded by Teka-hra. The sixth division is guarded by Maa-ab. The seventh division is guarded by Akhan-maati. The eighth division is guarded by Set-hra. The ninth division is guarded by Ab-ta. The tenth division (known as Tentit-uhesqet-khat-ab) is guarded by the serpent, Sethu. The eleventh division is guarded by Am-net-f, and the twelfth division is guarded by Sebi. There are twenty-one pylons in Tuat, but only ten have the names of the guards. These are Neri or Nerau, Mes-Peh or Mes-Ptah, Ertat-Sebanqa or Beq, Nekau or Hu-tepa, Henti-requ or Ertahen-er-reqau, Semamti or Samti, Akenti or Am-Nit, Khu-tchet-f or Netchses, Tchesef or Kau-tchet-f, Sekhen-ur whose name was not changed as the others were at a later date. Compare Tuat to Tartarus (Greek), Yomi and Jigoku (Japan). *See also* Aaru; Aati; Aau; Ab; Amentet Antiu; Arkharokh; Elysian Fields; Gehenna; Hentiu; Sekhet-Aarru (the domain of Osiris).

Tuatet-maket-neb-s (Egypt)

Afterworld. The name of the Ninth Hour of Tuat. Osiris passes through the city of Bes-aru which has the pylon Sa-Akeb. The deities mentioned are Akhem-sek-f, Akhem-urt-f, Akhemhemi-f, Akhem-khemes-f, Khen-unnut-f, Hapti-ta-f, Hetepuaa, Neter-neteru, Teha-Tuat, Tepi, Muti-khenti-Tuat, Nestikhenti-Tuat, Nebt-au-khent-Tuat, Nehata, Teba, Ariti, Menkhet, Hebs, Nebti, Asti-neter, Asti-paut, Hetemet-khu, Neb-pat, Temtu, Men-a, Perit, Shemat-khu, Nebt-shat, Nebt-shef-shefet, Aat-aatet, Nebt-setau, Hent-nut-s, Nebt-mat, Tesert-ant, Aat-khu, Sekhet-metu, Netert-en-khentet-Ra and Her-shetauti. *See also* Tuat.

Tuatha De Danann *Tuatha de Danaan, Tuatha-Dedanan* (Celtic)

The Tuatha De Danann are a legendary race of gods, sometimes called "the Children of Don" (or Dan, Dana, Danann), who inhabited Ireland. They are the descendants of Nemed who came to the island from Greece. Skilled in the art of magic, they brought four talismans with them known as the "Hallows of Ireland." The Hallows are the Stone of Fal, the Sword of Nuada, the Lance of Lugh and the Cauldron of the Dagda. They defeated the evil giants, the Fomorians, who had defeated the original race, the Firbolgs. The Tuatha De Dananns were in turn defeated by the Milesians, who were ancestors of the Gaels. It is said that the agreement was made to divide the country into two sections. The upper section was for the Gaels and the Tuatha would retreat to the other section, or Otherworld, also known as Tir na n'og, or the Sidhe or Hollow Hills. The chief female deity of the Tuatha De Danann is the goddess Dana and one of the chief male deities is Dagda who is also known as the "Good God," because of his wisdom and skills. Their queengoddess is Banbha. The symbols of the Tuatha De Danann are the stone, sword (or spear), lance and cauldron. It is said in some myths that the Tuatha De Danann and their treasures came from four cities: Gorias in the east, the origin of Lugh's lance; Falias in the north, which yielded the Stone of Destiny; Finias in the south, the origin of the sword or spear of Nuada; and Murias the city of the west (which later sank beneath the seas) is the origin of Undry, Dagda's magic cauldron. *See also* Amergin; Anu (A); Banbha; Beltine; Bress; Brigit; Cesair; Cian; Curoi Mac Daire; Dagda; Dana; Dia'necht; Domnu; Goibniu; Lugh; Manannan Mac Llyr; Nuada.

Tuatha-Dedanan (Celtic) *see* Tuatha De Danann.

Tuati (Egypt) *see* Aai.

Tubal-Cain (Sumer) Patron of the forge. *See also* Lumha.

Tucana People — Creation Legend (Amazon, South America) *see* Dyai.

Tuchita (India) *see* Tushita.

Tucupacha (Tarascan People, Mexico)

Tucupacha created heaven and earth, then created men and women from clay. After they melted in water, he created them again in cinders and metals. Apparently disappointed with his creations he caused a flood but saved a priest (Texpi) and his wife and some seeds and animals.

Tues (Greek) *see* Ares.

Tueris (Egypt) *see* Taueret.

Tuetates *Totates* (Gaul)

Also known as: *Alborix, Caturix, Loucetius, Rigisamos.*

God of war.

Tug'ny'gat (Eskimo People) *see* Tungat.

Tui-tokelo (Polynesia) *see* Tokelau.

Tuil (Kamchatka Peninsula, Siberia)

God of earthquakes. He rides his sleigh beneath the earth.

Tuil can be convinced to go elsewhere with his sleigh by poking holes in the ground with a very sharp stick of the proper length.

Tuirenn, Children of (Celtic) *see* Cian.

Tuku (Babylonia) *see* Marduk.

Tulasi (India)
The leaves of this sacred plant are used for the ceremonial worship of Shiva. Thought to remove all evils, it is sinful to break its branches. The juice of its leaves is said to have a curative effect. The goddess of plants who bears the same name is identified with Lakshmi (q.v.). *See also* Vilva.

Tule (Zande People, Siberia)
Water and trickster deity. He is the counterpart of Tere. *See also* Bele; Tere.

Tuleyone People — Creation Legend (North America) *see* Olle.

Tuli (Polynesia)
Messenger bird. Tangaloa sent Tuli to earth to establish land. After Tuli complained of lack of shade trees, Tangaloa gave Tuli a vine known as the "Peopling Vine," from which came humans. *See also* Tangaloa.

Tullius (Greek)
King of Rome. He is the son of Hephaistos and Ocrisia. *See also* Hephaistos.

Tulungusaq (Eskimo)
First creature. The first entity to appear was the Swallow. She showed Tulungusaq the clay soil at the bottom of a great abyss, which he uses to disguise himself as a Crow, and to create everything living.

Tum (Egypt)
Also known as: *Atum, Tem.*
Sun deity. He existed before creation. God of the setting sun, Tum presides over darkness. Some say he is the father of Ra who was born without a mother. His mate is possibly Akusaa, goddess of sunset. *See also* Atum; Tem.

Tumateanaoa (Polynesia) *see* Tu-metua.

Tumburu (India) *see* Gandharvas.

Tuminikar (Taruma People, Guiana)
Culture hero. He is a good deity whose twin brother, Duid, is a trickster god who causes worries for men.

Tumuteanaoa (Polynesia)
Also known as: *Echo.*
She is a child of the goddess Vari-ma-te-takere, who created her from a piece of her left side. This was Vari's fourth child, and the goddess gave her the land called Te-parai-tea. *See also* Vari.

Tun Huang T'ai (China) *see* Tung Huang T'ai I.

Tun Huang T'ai I (China) *see* Tung Huang T'ai I.

Tuna (Tongan People, Polynesia)
Also known as: *The Eel.*
God of trees. Tuna, the foster son of Kaloafu and Teuhie, was the spouse or lover of Hina. Hina grew tired of the relationship and left him. Finding a replacement lover was difficult as everyone was frightened of Tuna. Soon, the great hero-god Maui came along and was immensely attracted to Hina. Tuna and Maui engaged in a spectacular fight resulting in Tuna being chopped up in pieces. His head was planted and from it the first coconut tree sprouted. *See also* Hina; Maui.

Tung-Ak (Mongol)
God of managers and chiefs. Tung-Ak controls minor spirits.

Tung Chun (China)
Tung Chun, the god of the sun rising in the east, is also one of the nine heroes. Nine Songs.

Tung-Hua (China)
Tung-Hua is the official residence of male fairies. Tung Wang, also known as Tung Wang Kung, is in charge of Tung-Hua. *See also* Hsi-hua.

Tung Huang T'ai I (China)
Also known as: *T'ai Shan, T'ai-yueh-ta-ti, Tung-yueh-ta-te.*
Eastern Emperor. Great Emperor of the Eastern Peak. One of the nine heroes. Tung Huang T'ai I was placed in his position by the Jade Emperor. He is the protector of men and animals and he attends to the prosperity of both. His daughter, Pi-hsia-yuan-chung-mu, is a protector of children and goddess of birth. *See also* Nine Songs; Pi-hsia-yuan-chung-mu; T'ai shan.

Tung Wang Kung (China) *see* Yu Huang.

Tung-yo ta-ti (Buddhist)
After the judging, dead souls are sent to Tung-yo ta-ti, who is called the Emperor of the Eastern Peak. *See also* Sukhavati; Tung Huang T'ai I.

Tunkan Ingan (Dakota People, North America) Sex god.

Tuonela (Finnish)
Tuonela is the underworld ruled by Tuoni, the god of death. A beautiful black swan swimming on a black river protects the kingdom. *See also* Manala; Tuonetar.

Tuonetar (Finnish)
Queen of the underworld. She is the wife of Tuoni who is the king of the land of the dead, known as Tuonela. *See also* Kivutar; Loviatar; Manala; Tuoni; Vammatar.

Tuoni (Finnish)
God of the underworld. Lord of Tuonela, the underworld, he is the husband of Tuonetar and father of some vicious daughters and equally vicious sons. *See also* Kivutar; Kiyamat-Tora; Lemminkainen; Loviatar; Manala; Vainamoinen; Vammatar.

Tupan (Guarani, Tupinamba People, Brazil)
Also known as: *St. Thomas, Thunder, Toupan, Tumpa, Tupa, Tupi.*
God of thunder and lightning. Tupan is acknowledged as a god but is not worshiped. He is the son of the hero Nanderevusu and his wife, Nandecy. Whenever he visits his mother he causes storms; the creaking of his boat makes thunder. Tupan is a stocky young man with wavy hair. *See also* Milomaki.

www.ebook3000.com

Tupi (Brazil) *see* Tupan.

Tura (Persia) *see* Thrita.

Turachogue (Chibcha People, South America) *see* Bachue.

Turan (Etruscan)
Love goddess. She is associated with the moon goddess Zirna (q.v.).

Turi-a-faumea (Oceanic)
Turi-a-faumea is the son of the eel-woman, Faumea (q.v.).

Turms (Etruscan) *see* Hermes.

Turnus (Greek)
Turnus, the king of Rutuli, fought against the Trojans in the Trojan War. He fled Troy and went to Italy. In a battle with one of the three leaders of the Dardanians, Aeneas, Turnus was killed and sent to the underworld. Aeneas later married Lavina, the daughter of Turnus. *See also* Abas (A); Actor (C); Aeneas; Evander (B).

Turquoise Man-woman *see* Ahsonnutli.

Tushita *Tuchita, Tosotsa-Ten* (Buddhist; Japan).
The heaven for contented souls. Tushita is one of the twenty-four Buddhist heavens. It is the abode of Maitreya, the coming Buddha. Gautama Buddha resided in Tushita when he chose Maya as his mortal mother. Bodhisattvas are reborn in this realm before they become Buddhas. Each term of residence in Tushita is four hundred Tushita years. One Tushita day is four hundred years on earth. *See also* Buddha; Maitreya; Miroku-Bosatsu; Ryojusen; Sukhavati.

Tushna (Greek) *see* Apollo.

Tushnamatay (Persia) Goddess of meditation.

Tut (Babylon) *see* Marduk.

Tutates (Celtic) *see* Teutates.

Tute-Mute-Anaoa (Polynesia) *see* Vari (A).

Tuto-Tamu (Japan)
Tuto-Tamu is one of the gods who convinced the great goddess of light, Amaterasu, to leave her cave and restore light to the world. *See also* Amaterasu.

Tutruica (Choco People, Columbia, South America)
The rival of the creator, Caragabi (q.v.).

Tutsu-nushi No Kami (Japan)
Iha-tsutsu no wo and Ihatsutsu-nome are the parents of the god Tutsu-nushi No Kami. They are early generation deities in the creation legend. They are depicted hovering over the "Ocean of Chaos" just before the creation of the island of Onogoro. *See also* Izanami.

Tutu-F (Egypt) *see* Assessors.

Tvaksh-tri (India) *see* Tvashtri.

Tvashta (India) *see* Tvashtri.

Tvashtar (India) *see* Tvashtri.

Tvashtr (India) *see* Tvashtri.

Tvashtri (India)
Also known as: *Tvaksh-tri, Tvashta, Tvashtar, Tvashtr, Twashtar* (Sanskrit; Form Fashioner), *Twashtri, Visvakarma.* (Vedic; India)
Tvashtri, the divine artisan, architect and god of war, is the son of the sky god Dyaus. He is the father of the goddess of morning light, Saranyu, and the serpent Visvarupa. In some renditions he appears as the father of Indra, and in other legends, he is Indra's brother. Tvashtri is the creator of the magic thunderbolt known as the Vajra. He made thunderbolts as weapons for Indra and other deities. Another unique creation was the magic bowl that never emptied of soma, the ambrosia of the gods. Indra fortified himself with soma frequently, particularly before his battles with the serpent Vritra. Tvashtri taught his grandchildren, known as the Ribhus, their skills. In early times, his power was far-reaching and he was considered a creator god who gave life to all forms of creation, including heaven and earth. He created fire in the form of the god Agni. His far-reaching powers allowed him to form the men and women who were destined to marry, while they were still in the womb. During this period, Indra killed Tvashtri's son, Visvarupa, and Tvashtri and Indra became enemies. Some writers say Visvarupa was the same as Tvashtri. He could be the grandfather of Yama. He is said to be the father-in-law of Vayu, the god of wind. In later times, Tvashtri was known as Visvakarma. The vajra (vadjra), an important symbol to many Vedic, Hindu and Buddhist deities, is from the Sanskrit and means diamond and is usually translated as thunderbolt. It is a symbol of divine or mystic energy. It also symbolizes the male principle and the universal axis. It is usually represented in the form of a club or hammer, sometimes as weapon that looks like a discus with a hole in the middle. Compare Tvashtri to the Greek smith, Hephaistos, the Roman Vulcan, the Slavic Ilmarinen, and the Celtic Goibniu. *See also* Dyaus; Indra; Meru Mountain; Ribhus (The); Saranyu; Surya; Swarga; Vayu; Visvakarma; Yama; Yami.

Tviti (Teutonic) *see* Gleipnir.

Twashtar (India) *see* Tvashtri.

Twashtri (India) *see* Tvashtri.

Twet (Egypt) *see* Tuat.

Twilight of the Gods (Teutonic)
Another name for Ragnarok (q.v.).

Two Lady (Mexico) *see* Omeciutal; Ometecuhtli.

Two Lord (Mexico) *see* Omeciutatl; Ometecuhtli.

Twrch Trwyth (Celtic) *see* Cian.

Ty (Teutonic) *see* Odin; Tyr.

Tyche (Greek)
Also known as: *Tyche Agathe.*
The mate of Agathos Diamon, Tyche is a mother goddess and the goddess of fate. She is usually depicted winged, wearing a turreted crown and carrying a scepter. She is also shown standing on a ball or wheel or steering a wheel, wearing a blindfold. Compare Tyche to Fortuna, Allatu, and Astarte. *See also* Agathos Daimom; Allat; Fates.

Tydeus (Greek)
One of the Seven Against Thebes. He is the son of Oeneus and Gorge, or possibly Periboea. He married Deipyle and became the father of Diomedes, who became the king of Aetolia and who was deified after his death. Tydeus did not make out as well as his son. Near death, he killed his killer, Melanippus, and ate his brains. His actions did not sit well with the goddess Athena, who would not save his life, nor would she deify him. *See also* Calydonian Boar Hunt; Diomedes; Melanippus; Seven Against Thebes.

Tydus (Greek) *see* Adrestus.

Tyko (Greek) *see* Sisyphus.

Tyndareus (Greek)
Deified mortal. Husband of Leda and father of Clytemnestra and Castor; also king of Sparta. *See also* Agamemnon; Gorgophone; Helen; Leda.

Typheon (Greek) *see* Typhon (A).

Typhoeus (Greek) *see* Typhon (A).

Typhon (A) *Typhaon, Typheon* (Greek)
Also known as: *Typhoeus.*
Typhon, the demon of the whirlwind and a volcano deity, is the monster son of Typhoeus, who is a son of Tartarus and Gaea (Earth). As a son of Typhoeus, his aunt was the half-nymph, half-serpent Echidna. (Typhon and Typhoeus are often mistaken for the same person.) Typhon is the father by Echidna of a monstrous brood of offspring: the Crommyonian Sow, the Caucasian Eagle, Cerberus, the two-headed dog Orthus (Orthrus), Chimaera, the Nemean lion, the Vultures and the Sphinx. When the gods saw Typhon heading for Olympus, they fled to Egypt and transformed themselves into various animals. The great god Zeus remained behind. To allow the monster to take over Olympus was to allow him to become master of the world. A mighty battle ensued and at one point, Typhon felled his opponent, cut the muscles of his hands and feet, hid him in a cave and secreted his sinews under a bearskin, charging the dragon Delphyne to guard them. Hermes and Aegipan were able to regain them and restore them to Zeus' body. Zeus returned to Olympus for a new supply of thunderbolts and again engaged in battle with Typhon. The Fates entered the scene and tricked the monster into eating mortal food to weaken him. In the next bloody battle, Zeus the victor flung his enemy into the deepest region of the underworld, Tartarus. He is described as a giant monster having a hundred dragon heads, each shooting flames from mouth, eyes, and nostrils, and uttering blood curdling screams at the same time. Compare Typhon to the Vedic deity Indra's victory over the serpent Vrita, and to the Egyptian Set and Osiris. *See also* Aegipan; Cerberus; Enceladus; Gaea; Hecatonchires; Hydra; Phorcys; Scylla; Set; Tartarus; Zeus.

Typhon (B) *Typheon, Tyhaon* (Greek)
Typhon is the son of Zeus and the mortal Niobe. His siblings are Argus, Osiris and Pelasgus. *See also* Aello; Agrus (A); Niobe (B); Pelasgus.

Tyr (Norse; Teutonic)
Also known as: *Reidi-tyr, Sig-tyr, Teu, Thingsus, Tiw, Tiwaz, Ty, Tyw, Zio, Ziu, Ziv, Ziw.*
Sky god. As Tiwaz (German) he is a god of battle who is associated with Mars by the Romans. He is the god of law and order and one who holds up the universe. He is also known as a god of the sky and of battle. He is either the son of Odin or Hymir. Some say Tyr was the son of Frigga by Odin and brother of Balder and Hermod. Tyr was the only brave one to fasten the fetter around the neck of Fenrir, the wolf, and lost his hand because Fenrir was mistrustful of the strength of the binding called Gleipnir. He is associated with the Valkyries. As Thingsus, Ziv is God of Assembly. *See also* Fenrir; Thing; Ziu.

Tyro (Greek)
The daughter of Salmoneus and Alcidice, she married her uncle (who was also her stepfather), Cretheus. Her children are Aeson, Amythaon, Pheres, and Promachus. A liason with the sea god Poseidon produced twin sons, Neleus, the king of Pyros, and Pelias, the king of Iolcus. *See also* Crethus; Neleus; Pelias; Salmoneus; Sisyphus.

Tyt (Egypt) *see* Ab.

Tyw (Teutonic) *see* Tyr.

Tzakol (Maya People, Yucatan) *see* Ixpiyacoc.

Tzakor (Maya People, Yucatan)
Creator. One of the four regents who attempted to create mankind. *See also* Ixpiyac (Xpiyacoc).

Tzinteotl (Aztec)
Also known as: Possibly *Xochiquetzal.*
Goddess of maize. Little known of her history, but she is probably related to Xilonen. *See also* Cinteotl; Xilonen.

Tzitzimime (Aztec People, Mexico)
Star demons. They are called "Monsters Descending from Above."

Tzontemoc (Mexico) *see* Mictlantecutli.

www.ebook3000.com

Front Direction: Push/Pull Master Practice

Now, turn your palms, pushing out. Push. Pull. This is the master practice that is imperative for successful completion. When you first start practicing you should do it at least one hundred times and increase up to 200 times. Push and pull. When you push, you feel your hands extended very far away – very long – reach the sky. Touch the universe.



1. Push: Extend your arms and hands to the front, palms vertical. Extend the arms from the scapulas.
   Expand: smiling, smiling, touching the universe – touching the force, touching the Cosmic Chi.

Fig. 3.34
Master practice:
Touch the Universe.



2. Pull: Draw the Chi back to you from the universe. Moving the arms from the scapulas, draw the hands toward your body in a horizontal position, drawing the Chi into the body.

Fig. 3.35 *'Drawing' Universal Chi - feel your Tan Tien and fill it with Chi.*

U

Uadjit (Egypt) *see* Buto (Greek); Uatchet.

Uaj (Slavic) God of the earth.

Uajet (Egypt) *see* Buto (A); Uatchet.

Uajyt (Egypt) *see* Uatchet.

Uamemti (Egypt) *see* Assessors.

Uasir (Egypt) *see* Osiris.

Uatch-Nes (Egypt) *see* Assessors.

Uatchet (Egypt)
Also known as: *Buto, Per Uadjit* (The Dwelling Place of Uadjit), *Uajyt, Uatchit, Uatchura, Uazet, Uto.*

Cobra goddess. Protector and guardian of royalty. Uatchet assisted Isis in hiding the infant Horus in the swamps. Uatchet is shown with wings and the red crown of Lower Egypt is on her head. She is mentioned in one of the old hymns along with Amen-Ra, Nekhebet and Mehen. *See also* Buto (A); Nekhbet; Wadjet.

Uatchit (Egypt) *see* Buto; Uatchet.

Uatchura (Egypt) *see* Buto (A); Uatchet.

Uazai (Egypt) *see* Buto (A); Uatchet.

Uazet (Egypt) *see* Uatchet.

Ubelluris (Hittite)
This mountain god carries the edge of the western sky on his shoulders.

Uben (Egypt) *see* Aai.

Uboze (Slavic) *see* Khoromozitel.

Uc-Zip (Maya)
Underworld deity. Uc-Zip announces the Vision Serpent when he emerges from Xibalba, the underworld.

Uchchaih-sravas (India) Sacred Horse. *See also* Kurma.

Uchtsiti (Acoma People, North America)
"Nothing Lacking." Uchtsiti is the "Father of the Gods."

Udar (Teutonic)
Udar, the son of Nott, is a water god. *See also* Nott.

Uddushunamir (Assyro-Babylonian) *see* Asushunamir.

Udumbara (India) "Man of the Ficus Tree." *See also* Yama.

Udzume (Japan) *see* Ama No Uzume.

Ueuecoyotl (Mexico, Aztec, Otomi)
Also known as: *Coyote* or *Old Coyote.*

God of fecundity. Trickster deity. He is the manifestation of unacceptable impulses. Some sources believe the name Xolotl was borrowed from Ueuecoyotl. He is also confused with Xolotl. Ueuecoyotl is generally considered the same as the North American Coyote (q.v.).

Ufa (Egypt)
Ufa is a serpent mentioned with Akeneh, the serpent demon, and other serpents in the text of *Unas*, a king in the fifth dynasty. This text describes magical methods to destroy serpents and barbarous beasts.

Ugar (Ugaric)
Ugar is one of Baal's messengers. *See also* Baal.

Uggerus (Teutonic) A name for Odin (q.v.).

Ugra (India) "Dread." *See also* Agni.

Ugra Tara (Buddhist; Tibet)
A dreadful manifestion of the goddess Khadga Jogina (q.v.).

Ugrasena, King (India)
The demon Drumalika assumed the body of King Ugrasena and raped his wife, Queen Pavanarekha. She became pregnant and gave birth to the demon Kansa. For additional details, *see* Kansa. *See also* Yadavas.

Uhiji-ni No Mikoto (Japan)
"Mud Earth." One of the third "generation" of deities to spring from Chaos. *See also* Ama-no-minaka-nushi.

Uhlanga (Africa)
Uhlanga is another name for the supreme god, Unkulunkulu (q.v.).

Uhumakaikai (Hawaii, Polynesia)
Local evil shark or fish gods of Kauai.

Uiracocha (Inca) *see* Virococha.

Uitzilopochtli (Aztec) *see* Huitzilopochtli.

Uitztlampa (Mexico, Aztec)
Also known as: *Place of Thorns.*

The mountain refuge of the brothers of Huitzilopochtli who escaped his wrath. *See also* Coatlicue; Huitzilopochtli.

Uixtochihuatl *Huixtocihuatl, Uixtociuatl* (Aztec People, Mexico)
She is the goddess of salt, and considered to be the eldest sister of Tlaloc. She is also known as the sister of the rain gods. Uixtochihuatl is sometimes identified as one of the wives of Tezcatlipoca. *See also* Atlantonan; Tlaloc; Xilonen; Xochiquetzal.

Uixtociuatl (Mexico) *see* Uixtochihuatl.

Uja-Jin (Japan)
Uja-Jin is an obsure deity who is associated with Benten, the sea goddess of good luck. *See also* Benten.

Ujikami (Japan)
The Ujikami are the ghosts of old rulers. *See also* Okuni-Nushino-Mikoto.

Uka-no-kami (Japan)
Uka-no-kami is another name for the androgynous deity of rice and good luck, Inari (q.v.).

Ukanipo (Hawaii) Great shark god of Hawaii. *See also* Moaalii.

Uke-mochi (Japan) *see* Ukemochi.

Uke-mochi-no-kami (Japan) *see* Ukemochi.

Ukemochi *Uke-mochi, Uki-mochi* (Japan)
Also known as: *Ogetsu-hime-no-kami* (Great-Food-Princess), *Toyo-uke-bime* (Princess-of-Rich-Food) *Toyo-uke-hime* (Plentiful-Food-August), *Toyo-uke-hime-no-hime, Toyo-uke-hime-no-himi, Toyo-uke-no-kami* (Abundance-Bounty-Goddess), *Uke-mochi-no-kami, Ukemochi-no-kami, Waka-uke-nomi* (Young-Woman-with-Food).

Goddess of food. Goddess of sustenance. Domestic deity. Ukemochi (Food-Possessing-Goddess) produced the food that the sun goddess Amaterasu used as seeds to grow in the fields she developed and irrigated. The ancient records of the *Nihongi* and the *Kojiki* vary in the interpretation of this myth. The *Nihongi* records that the sun goddess Amaterasu sent her brother Tsuki-yomi to visit Ukemochi. In the *Kojiki*, it is her brother Susanowo who is sent on the mission. The following myth, based on the *Nihongi*, is generally thought to be the most original rendition. Tsuki-yomi was sent to earth to see that Ukemochi was performing her duties. While being hospitable, she opened her mouth while facing the field, and boiled rice streamed from it. As she faced the sea, she regurgitated fish and edible seaweed. When she faced the wooded hills, game of various kinds came forth. Tsuki-yomi did not appreciate this banquet. He killed her. Death did not stop the food goddess from being productive. The ox and the horse emerged from her head, silkworms from her eyebrows, millet grew from her forehead, rice from her stomach, and wheat and beans from her genitals. Amaterasu, upset by her brother's actions, separated from him. The name Ogetsu-hime-no-kami may be another name for Ukemochi but it is not certain as the *Kojiki* is not clear about the name. It refers to Ogetsu-hime-no-kami as Ukemochi and also names a separate entity Ukemochi. The name is used as another name of the land of Apa. It also refers to Ogetsu-hime-no-kami as the wife of Pa-yama-to-no-kami, who is said to be the husband of Ukemochi. As wife and mother Ukemochi had eight children. Three of her daughters were Waka-sana-me-no-kami, Natu-taka-mi-no-kami (also known as Natu-no-me-no-kami) and Aki-bime-no-kami. Ukemochi may be the same as Waka-Uke-Nomi (Young-Woman-with-Food). She may be the same as Toyo-Uke-Bimi (Princess-of-Rich-Food) and Toyo-uke-no-kami (Abundance-Bounty-Goddess). Toyo-uke-no-kami was known as companion of the sun goddess Amaterasu. Ukemochi is often confused with the god of rice Inari, who is often presented as a goddess. Ukemochi represents kindness, nourishment and the maternal cord. Rice is considered an emblem of happiness and nourishment. Seaweed signifies joyousness. Fish represent abundance, wisdom, generative power and woman. In some Asian cultures bones of the fish are thrown back into the sea so the fish can return to life for the next fishing season. The ox toils for others and is a symbol of agriculture. Wheat is also a symbol of agriculture. The horse symbolizes creativity and endurance. In Japan, beans, as well as being nourishing, were used to dispel evil spirits. (In ancient Greece and Rome, one could spit beans to expel ghosts.) Ise, the principal shrine dedicated to Amaterasu, has reserved the outer shrine for worship of Ukemochi. For information about the *Nihongi*, the *Kojiki* and the Shinto creation story, *see* Ama-no-minaka-nushi. Compare Ukemochi to Kami-mimusubi, who collected the seeds produced by Ogetsu-hime-no-kami. *See also* Amaterasu; Inari; Kaya-no-hime-no-kami (goddess of herbs).

Ukemochi-no-kami *see* Toyo-uke-hime-no-hime; Ukemochi.

Ukhukh (Egypt)
Local deity. He was worshiped near the site of modern Meir. His symbol is a staff decorated with two feathers and two serpents.

Uki-Mochi (Japan) *see* Ukemochi.

Ukibashi (Japan) *see* Izanami.

Ukko (Finnish)
Also known as: *Jumala.*
God of air. God of thunderstorms. Ukko replaced the sky and thunder god Jumala. He created fire when he struck his sword against his fingernail. Ukko is associated Vainamoinen and Ilmarinen. *See also* Ilmarinen; Jumala; Thor.

Ukko-Thor (Finnish) *see* Thor; Ukko.

Uksakka (Lapp)
Door goddess. Uksakka lives under the door. Her function is to protect the newborn and the owners of the house. She is similar to Dorr-Karing of the Swedish people.

Uktena (Cherokee People, North America)
The Great Water Serpent. *See also* Ukteni; Unktehi.

Ukteni (Natchez People, North America) Magical water snake.

Ul (New Hebrides) Spirit of moon and night. *See also* Tortali.

Ulgan (Siberia) Supreme god of heaven.

Uli (Hawaii, Polynesia)
Sorcery goddess. She is the most commonly invoked sorcery deity in Hawaii. Uli, Maka-ku-koae, the god who brings madness, and Alae-a-Hina, the goddess who had the secret of fire, are invoked to bring death to an enemy. *See also* Keoloewa; Ku-Kali-Moku; Kupua.

Ull (Norse; Teutonic)
Also known as: *Auler, Holler* (German), *Oller, Ollerus, Uller, Ullerus, Ullr, Wuldor* (Anglo-saxon).

www.ebook3000.com

God of winter. God of skiing. God of archery. Major god. Ull, Hod, Vali and Vidar are the four major gods in Norse mythology. In the mythology of the *Eddas*, Ull is one of twelve major deities. The others are Odin, Thor, Njord, Frey, Balder, Tyr, Heimda, Bragi, Forseti, Hod, Vidar and Vali. Ull is an excellent skier and archer. His mother is the beautiful, golden-haired protector of homes, Sif, and his stepfather is Thor. His natural father is unknown. Ull resides in Ydalir (Valley of Rain). *See also* Holler; Skadi.

Uller (Teutonic) *see* Ull.

Ullerus (Teutonic) *see* Ull.

Ulligarra (Sumer)
One of the two first ancestors of mankind. The other was Zalgarra. They were born from the blood of the gods known as Lamga. *See also* Cosmology of Assur.

Ullikummi (Hittite, Hurrian) *see* Ullikummis.

Ullikummis *Ullikummi* (Hittite, Hurrite)
His father, Kumbaris, had Ullikummis created specifically to oppose the gods. After being born he was first placed on the lap of Kumarbis by the goddesses Gul-shes and Makh, then placed on the right shoulder of Upelluris, the giant who sustained the world. Ullikummis' body, made of dioritic stone, grew to immense proportions. By the fifteenth day he stood in the sea, so tall, the sea only reached his belt. He grew to a height of 9,000 leagues with a girth of 9,000 leagues. As his height reached to the heavens, the other gods feared him. After he decided to destroy humanity and the storm god Kummiya, the other gods defeated him. They were helped by the great god Ea who weakened Ullikummis to the point where he could be overtaken. *See also* Alalus; Anus; Ea; Hepat; Kumarbis; Teshub; Upelluris.

Ullr (Teutonic) *see* Ull.

Ullur (Teutonic) *see* Aesir.

Ulmuka (India) Son of Bala-Rama (q.v.).

Ulu Tojon (Yakut People, Siberia)
Also known as: *Arsan-Duolai, Arson Duolai, Syga-Tojon.*
Creator. God of thunder and lightning. He is called the "stranger" or "white creator." Ulu Tojon is from the third heaven. He rules the underworld and the Abaasy. Mortals received fire from him. He is possibly the same as Arson Duolai (q.v.) *See also* Abassy.

Ulupi (India)
A Nagi serpent princess. *See also* Arjuna; Nagas and Nagis.

Ulysses (Roman) Ulysses is the Roman equivalent to Odysseus.

Uma (Hindu; India)
Also known as: *Devi, Parvati*
Uma is an aspect of the great goddess Devi and her name means "Light" as she personifies light and beauty. She is depicted with a golden skin and is attributed with inspiring the gods with love. Parvati was reborn as Uma. In one legend, Uma is the wife of the god Mahesvara. They had three thousand children; the eldest son was Vinayaka. *See also* Daksha; Devi; Devis; Durga; Gozanze-Myoo; Kali; Parvati; Sati (A); Shashthi; Shiva; Trailokyavijaya.

Uma Haimavati (India) *see* Rudra.

Umai (Mongol, Turkey)
Also known as: *Mai, Ymai.*
Fire deity. Although a fire god or goddess to the Mongols, she is a Goddess of Fire in the sense of household use to the Turks. If her flame should be extinguished, so would that of the Turk family. Umai is possibly the same as Ummu of the Assyrians. *See also* Akha; Ot.

Umhlanga (Africa) *see* Unkulunkulu.

Umiarissat (Eskimo) *see* Inuat; Inue.

Umina (Ecuador)
God of medicine. He is represented by a large emerald.

Umlungu (Africa) *see* Mulungu.

Umm Kulthum (Islamic) *see* Mohammed.

Umunmutamku (Assyro-Babylonia)
The Great God, Ea, created Umunmutamku and Umunmutamnag as deities to present offerings to other gods. *See also* Ea.

Unas (Egypt)
Also known as: *Ashem, Sekhem, Unis.*
A god who eats other gods. The gods were snared by Amkehuu, and after an examination for fitness by Tcheser-tep-f, they were bound by Her-thertu and the god Khensu cut their throats and took out their intestines. Next, they were butchered and cooked by Shesemu. Unas ate their words, power and spirits. He ate the largest and finest at daybreak, the smaller ones at sunset, and the smallest for his evening meal. The old and worn out gods were rejected and used for fuel in his furnace. The result of his eating the gods was that he changed into Sekhem and Ashem. *See also* Shesemu.

Undines (Teutonic) Female water spirits. *See also* Nixie.

Undry (Celtic) *see* Dagda.

Unelanuhi (Cherokee People, North America)
Also known as: *Aghyu Gugu*
Unelanuhi is a sun goddess.

Ung (Egypt)
Ung is a god who is sometimes called "Son of the Solar Deity." He is a messenger of the gods. He is identified with Osiris and Shu.

Ungud (Aborigine People, Australia)
Also known as: *Rainbow Serpent, Wongar.*
Ungud is a bi-sexual snake god. He caused rain after Wallanganda threw water on the earth. He is possibly the same as Wuraka (q.v.). *See also* Rainbow Snake.

Unis (Egypt) *see* Unas.

Universal Egg (Greek) *see* Eurynome (A).

Universal Mother (India) *see* Maya (B).

Universal Shakti (India) *see* Maya (B).

Univirae (Etruscan, Roman) *see* Fortuna.

Unkulunkulu (Kaffir, Zulu People, Africa)

Also known as: *Nkulnkulu, Uhlanga, Umhlanga.*

Supreme deity. Son of Unvelingange, creator of civilization. Unkulunkulu's impatience is indirectly responsible for death because he couldn't wait for the message of creation to be spread among mortals. He chose the messenger. Another version from the Zulu people of Africa places Unkulunkulu as a creator god or a place of beginning. Other authorities state that Unkulunkulu was the first man. The name is associated with a reed or reed bed. He is similar to Mulungu and Ribimbi.

Unmatta (India) "Raging." *See also* Shiva.

Unnefer (Egypt)

Also known as: *Onnophris, Osiris, Unnofre, Wenen-nefer, Wenenefer.*

Unnefer is one of the titles applied to Osiris, meaning "he who is continually happy," in his role as god of resurrection. *See also* Onophris.

Unnet (Egypt) *see* Wenut.

Unnofre (Egypt) *see* Unnefer.

Unsas, The (Arabic)

A triad of powerful goddesses known as Al-Uza, Menat and Allat (also known as Lat, Uzza and Manat). *See also* Allat; Al-Uza.

Unt (Egypt) *see* Aaru.

Untunktahe (Dakota People, North America)

With Waukheon, the thunderbird, Untunktahe, the water god, is a primary deity.

Unummuzida (Sumer) *see* Ningishzida.

Unvelingange (Kaffir)

First god. The god who existed before anything else.

Upamanya (India)

His eyesight was restored by the twin deities of healing, the Asvins (q.v.).

Upananda (India)

Nanda and Upananda, two Naga kings, gave Buddha in his mortal form as Gautama his first bath. *See also* Naga Naga Knaya.

Upao (Polynesia)

Upao is a name for the creator god of the ocean and of fishers, Tangaroa.

Upasunda (India)

Upasunda and Sunda are two of the Asura brothers, who are constantly in conflict with the gods. *See also* Arjuna; Asuras.

Upelluri (Hittite) *see* Upelluris.

Upelluris *Upelluri* (Hittite, Hurrite)

The Isirra deities placed Ullikummis on the shoulders of this giant, so he could grow to immense proportions and oppose the gods. Like Atlas, Upelluris carried the world on his shoulders. *See also* Atlas; Ullikummis.

Upset (Egypt)

Upset is often identified with Isis and other goddesses worshipped at Philae.

Upshukina (Sumer)

Home of gods. In the great hall the gods meet to hold council. The Igigi held a banquet there and gave Marduk full powers as king and Ruler of the World. *See also* Igigi; Marduk.

Upuaut (Egypt) *see* Khenti Amenti.

Ur (Sumer)

He is an ancient Mesopotamian god, thought by some to be Nabu. *See also* Nabu.

Ur-Nammu (Sumer)

Originally the king of the city of Lagash, this tall, thin ruler was later deified.

Ur-Shanabi (Babylon) *see* Urshanabi.

Urshanabi (Babylon)

He is the sailor who takes dead souls across the Sea of Hades. *See also* Gilgamesh.

Ura (Assyro-Babylonia) A demon of pestilence.

Uraeus (Egypt)

Divine cobra. A flame-breathing asp who protects the sun god Ra by destroying his foes. Ra is sometimes depicted wearing on his head the disk of the sun surrounded by the uraeus, a symbol of royalty and power. Uraeus is the divine snake, a cobra, identified with the goddess Buto of Lower Egypt. It appears in the headdresses or crowns of many gods and goddesses of Egypt. It is said to spit fire at anyone who is an enemy of the gods or who invades the tombs of the dead.

Uragas (India) *see* Nagas and Nagis.

Urania (Greek)

Urania is the Muse of astronomy and astrology. She is the mother of Hymenaeus by Dionysus and the possible mother of the poet and musician, Linus. Urania is depicted with a globe and a pair of compasses. *See also* Hymen; Linus; Muses; Uranie.

Uranus (Greek)

Also known as: *Caelus, Coelus* (Roman), *Ouranos, Summano* (Etruscan).

Sky god. Most ancient of deities. His father is sometimes said to be Aether (Air). His mother and later his wife is Gaea (earth). He is the father of the Cyclopes, Hecatonchires and Titans. He sequestered his children by lock and key. Cronus, however, was able to castrate him and throw his genitals into the sea. From his genitals the goddess Aphrodite was created and rose from the sea. From his semen and blood the Erinyes, Giants and Meliae were born. The Telchines and Halia are possibly his children by Thalassa, personification of the sea. Compare Uranus to Varuna (India) and Indra (India). *See also* Aegaeon; Aether; Alcyoneus; Ceos; Chaos; Cronus; Cybele; Demeter; Enceladus;

www.ebook3000.com

Erinyes; Gaea; Giants; Hecatonchires; Meliae; Muses; Oceanus; Styx; Telechine; Theia (C); Themis; Thoas (E); Titans.

Urcaguary (Peru) *see* Urcaguay.

Urcaguay *Urcaguary* (Inca People, Peru)
He is a god of the underground and guardian of the underground treasures. Urcaguay is shown as a large snake with the head of a deer with little gold chains on the tail.

Urd *Urdh, Urdhr, Urdur* (Norse; Teutonic)
Also known as: *Urpr, Urth, Wurd, Wyrd* (Anglo-Saxon).
Goddess of destiny. One of the Norns. The better known of the numerous Norns are Urd, Verdandi and Skuld. There are both good and evil Norns. They oversee the destiny of all mortals and gods. At every birth, one of the Norns is present. They reside beneath the Tree of Life, Yggdrasil, next to Urd's Well. The gods assemble at this location. Some say Urd is the chief of the Norns and the daughter of Mimir. She is shown looking back. *See* Fates; Hel; Mimer; Mimer's Well; Norns; Odin; Yggdrasil.

Urdh (Teutonic) *see* Urd.

Urdhr (Teutonic) *see* Urd.

Urdur (Teutonic) *see* Urd.

Urien (Celtic)
Urien is one of the names for Bran's decapitated head. *See also* Bran.

Urin Cuzco (Inca)
Urin Cuzco is another name for Tahuantin Suyu Kapac, the four brothers who are the sons of the sun and the first people. *See also* Tahuantin Suyu Kapac.

Urion (Greek) *see* Orion.

Uris (Greek)
Uris is one of the attendants of Artemis, the moon goddess and goddess of hunting. Some say that Uris was possibly the lover of the hunter Orion (q.v.).

Urja (India)
Urja is one of Daksha's daughters. *See also* Daksha; Vasistha.

Urmila (India)
She is described as a beautiful sister of Sita, the goddess of fertility and agriculture. *See also* Sita.

Urpihuachac (Andean People, Peru)
Urpihuachac was the lucky recipient of the few fish in the world, a gift from the creator of all things, Coniraya (q.v.). *See also* Viracocha.

Urpr (Teutonic) *see* Urd.

Urshanabi *Ur-Shanabi* (Babylonia)
Urshanabi is the sailor who steered the ark built by Utnapishtim, during the great Deluge. *See also* Gilgamesh; Utnapishtim.

Urshiu (Egypt) *see* Aai.

Urt (A) (Egypt)
Also known as: *Osiris.*
Urt is one of the four earthly forms of Osiris in the sixth sector of Tuat.

Urt (B) (Finnish) *see* Ort.

Urth (Teutonic)
Urth is a name for the goddess of the underworld, Hel (q.v.).

Uruasi (India) *see* Urvasi.

Uruki (India) *see* Urvasi.

Urun Ai Toyon (Yakuts)
The god of the seventh heaven, who does only good, but can bring punishment.

Urutaetae (Polynesia, Tahiti)
God of the underworld (afterworld). Some say Urutaetae presides as the head of the underworld. *See also* Hiro.

Urutonga (Maori People, New Zealand)
"South West." In Maori mythology, she is the goddess wife of Hema and the mother Tawhaki and Kariki. *See also* Hema; Tawhaki.

Urvashi (India) *see* Urvasi.

Urvasi *Uruki, Uruasi, Urvashi* (Vedic, Hindu; India)
Goddess of success in love. An Apsaras. She is the daughter of the sage Naranarayana. The power that he acquired from his rigorous austerities alarmed the gods. They sent a beautiful nymph to distract him. When he saw her, he was not disturbed. He put a flower on his thigh and from it Urvasi, even more alluring than the nymph, blossomed. Her father sent her to the celestial realm where she created a major disturbance among the deities for they all wanted her for a mate. Varuna and Surya (sometimes Mitra) both loved her at the same time. She aroused them so that their sperm fell to the ground. It was collected in a jar of water and from it Agastya was born in the shape of a beautiful fish. She is also known as the mother of Vasishtha by Mithra or Varuna, or some say Agni. In other legends, she is the spouse of the mortal king Pururavas, the gleaming one, who is an aspect of the sun and the founder of the lunar dynasty. When a flash of lightning revealed her husband's brilliance, it was more than she could endure. Urvasi vanished into the water, and became a naiad with a fish tail. Distraught, Pururavas searched everywhere for her and finally found her on the last day of the year. In a slight variation of this tale, she lived with the king on the condition that she never wanted to see him naked. He forgot and when she came upon him without clothing, she was filled with disgust and fled. He promised her that if she returned he would give up his throne for her and become an erotic dancer. She is one of the few Apsarases with her own mythology. Her earthly counterpart is the swan or the lotus. Compare Urvasi to the Greek Psyche and Daphne. *See also* Agastya; Apsarases; Manaka; Marisha; Mitra; Varuna; Vasihtha.

Usanas (India) *see* Brihaspati.

Usekht-Nemmat (Egypt) *see* Assessors.

Usert (Egypt) *see* Isis.

Usha (India)
She is the demon daughter of Bana. *See also* Bana; Daityas; Krishna.

Ushas *Dyotana* (The Light-Bearer), *Marichi, Marishi, Usas* (Vedic, Hindu; India)

Ushas, goddess of the dawn, is the daughter of the earth goddess Prithiva and the sky god Dyaus. Her siblings are Agni the fire god, Ratri the night goddess (also known as Ratridevi), Varuna the king of the universe, Bhaga the god of prosperity and probably Indra the god of the heavens. Ushas may be the sister of the Adityas. She is the mother of the storm god Rudra and possibly the twin healing deities, the Asvins. If not their mother she is a close friend. Ratri and Ushas are reputed to be joint mothers of the sun god Surya. Others say she is the lover, bride or daughter of Surya. Chandra the moon god is also her husband. Their marriage can never be consummated, as the moon and the sun are constantly in pursuit of one another. Eternally youthful, she brings age to mortals. She is also a fertility goddess and a goddess of poetry. In some renditions, it is said that she was created by Indra. There is an ancient Vedic goddess named Asva who was called "The Dawn" and "The Mare." She closely corresponds to the goddess of dawn Ushas. Holding a bow and arrow, Ushas is depicted draped in the gentle colors of dawn, crossing the eastern sky in a vehicle drawn by red cows. As a fertility goddess, she is shown with three heads; one head is a pig's head, the symbol of fecundity. Seven pigs draw her vehicle. Ushas, the beautiful dawn goddess, is a source of delight to all living creatures. It is said that Marichi, who is a Buddhist goddess, is Ushas in her fierce form. In this aspect she is shown with an eye in her forehead, three faces, ten arms, her head crowned with skulls and wreathed in flame. Compare Ushas to the Greek goddess of dawn, Eos. *See also* Adityas; Agni; Asvins; Aurora; Bhaga; Chandra; Dyaus; Indra; Marichi (A); Marichi-ten; Prithiva; Ratri; Rudra; Saranyu; Surya; Varuna.

Ushemet Hatu Khefti Ra (Egypt)

Underworld time. The name of the first hour of Tuat. The dead (Af) make their journey along the river of Tuat in the Sektet boat. With them are Ap-uat, Sa, Heru-Hekenu, Nehes, Hu (the double of Shu, and the captain and lady of the boat). *See also* Tuat.

Ushnishavijaya (Buddhist; India)

This goddess abolishes fear and is also considered a goddess of charity. Her attributes are Buddha on the lotus, a bow and arrow, a noose and a water-pot. She is shown with three faces and eight arms.

Ushodevatas (India) *see* Devis.

Usma (Babylon)

He is one of the attendants of the great god, Ea. It is possible that he is a god of the sea. Usma is shown as two-faced.

Usukun (Maya People, Yucatan)

Evil deity. He is one of the brothers of Hapikern. Usukun hates mankind. His assistant is Kisin, the earthquake. Usukun is associated with Nohochacyum.

Usur-Apa (Egypt) *see* Serapis.

Usur-Api (Egypt) *see* Serapis.

Uta-Napishtim (Babylon) *see* Utnapishtim.

Uta-Napistim (Babylon) *see* Utnapishtim.

Utanapishtim (Babylon) *see* Utnapishtim.

Utnapishtim *Ut-Napishtim* (Babylon)

Also known as: *Uta-Napishtim, Ziusudra* (Sumerian).

A mortal who was deified. When the gods sent the Deluge, Utnapishtim built an ark and saved himself, his family and the beasts who inhabit the earth. The sailor who steered the craft was Urshanabi. Enlil the storm god made Utnapishtim immortal. It was Utnapishtim who Gilgamesh consulted in his search for immortality. Utnapishtim gave Gilgamesh a plant to eat for this purpose. *See also* Ea; Enlil; Gilgamesh; Siduri; Ziusudra.

Utathya (India) *see* Rishi; Sarasvati.

Utennu Apes (Egypt) *see* Aani.

Utet (Egypt) The heron god.

Utgard (Teutonic)

Also known as: *Jotunheim.*

Realm of the giants. Utgard is the home of Skrymir located in Jotunheim. Utgard-Loki may be the ruler. *See also* Fjalar; Utgard-Loki.

Utgard-Loki *Utgard-Loke* (Teutonic)

Also known as: *Loki, Skrymir.*

Giant. Utgard-Loki is the nemesis of Thor. As Loki he rules Utgard, the home of the giants in Jotunheim. For additional details of the shape-changer, *see* Loki. *See also* Fjalar; Skrymir.

Uther Ben (Celtic)

One of the names given to Bran's decapitated head. It means "Wonderful Head."

Uther Pendragon (Celtic)

One of the several names given to Bran's decapitated head. *See also* Arthur; Bran.

Uthra (Gnostic) *see* Abathur.

Uto (Egypt) *see* Uatchet.

Utsanati (Cherokee People, North America)

Rattlesnake, helper of man.

Utset and Bowutset (Sia People, India) The First Mothers.

Uttara (India)

Abhimanya and Uttara are the parents of Parikshit, the king of Hastinapura and patron of poetry. His grandfather is the warrior, Arjuna. *See also* Abhimanya; Parikshit.

Uttu (Sumer)

She is the goddess of clothing, earth, plants, and general vegetation. One of her responsibilities is weaving cloth and making clothing. Her mother, Ninkurra, is the daughter of Ninsar and Enki. Ninsar is the daughter of Ninhursag and Enki. Enki had an incestuous relationship with his daughter Ninsar and Ninkurra was born. He did the same with his granddaughter, Ninkurra, and Uttu was born. He tried to molest Uttu but her great grandmother Ninhursag intervened. *See also* Enki; Ninhursag; Ninkurra; Ninmu.

www.ebook3000.com

Utu (Sumer)
Also known as: *Babbar.*
He is the counterpart of the Babylonian god Shamash. The brother of Inanna, he wanted her to marry the farmer god Enkidu rather than the shepherd god Dumuzi. He is connected with legislation and justice. In some myths he is the moon god, son of Enlil and the goddess Ninlil. *See also* Babbar; Dumuzi; Enkidu; Enlil; Inanna; Ninlil; Shamash.

Utu-Rekhit (Egypt) *see* Assessors.

Utukki (Assyro-Babylonian)
The Utukki are the seven evil demons created from the union of Anu and Antu. Their siblings are the underworld gods, known as the Anunnaki. *See also* Anat; Antu; Anu.

Utukku (Sumer)
The Utukku are the genies who are spirits holding a position subordinate to that of the gods. Those called the Edimmu were forces of evil; the Shedu, forces of good. *See also* Edimmu; Shedu; Utukki.

Uuodan (German) *see* Odin.

Uyitzin (Maya People, Yucatan)
Benevolent deity. He is one of three brothers of Nohochacyu, the creator, who is the enemy of the evil Nohochacyum (q.v.).

Uyungsum (Saora People, India) *see* Adununkisum.

Uzzah (Arabic) *see* Al-Uza.

V

Vac (India) see Sarasvati.

Vach Vac, Vacha (Brahmanic, Hindu; India)
Also known as: *Bak, Madhyama, Para, Pashyanti, Sata-rupa, Savitri (A), Shatarupa* (She of the Thousand Forms), *Vaikhari.*
A charming, seductive and mysterious goddess, Vach, meaning "voice," was originally known as the goddess of thunder. Later, she became known as the goddess of knowledge and speech. All intelligent beings were created through Vach by Prajapati. In the Vedas, Vach is called the "melodious four-uddered cow." Her milk sustains all and her udders sustain the four quarters of the universe. She is variously known as the spouse of Indra, the bull As (meaning breath) and possibly Vata (the wind). In one legend, Vach, as one of Indra's wives and goddess of waters, gave the nectar of the gods Soma to the Gandharvas. As Sata-rupa she is an aspect of the female half of Brahma and the daughter of Kama (love). She is sometimes represented as a cow. She is similar in some aspects to the goddess Sarasvati and in some legends she is referred to as Sarasvati's mother. Vach corresponds to Diti and Aditi and closely parallels Kwan-Yin. *See also* Aditi; Brahma; Brihaspati; Indra; Kama; Karttikeya; Prajapati; Soma.

Vach-Sarasvati (India) *see* Sarasvati.

Vacha (India) *see* Vach.

Vacuna (Roman)
Vacuna is a Sabine goddess, often said to be the same as the Roman goddess of victory, Victoria. She is identified with Ceres, Diana, Minerva or Venus. *See also* Victoria.

Vadaba (India) *see* Vadava.

Vadava *Badava, Vadaba* (India)
This mare goddess is also a being of flame, with a horse's head, who licks up water, and causes clouds and rain. *See also* Asvins; Vivasvat.

Vadjra (India) *see* Vajra.

Vafthrudni (Teutonic) *see* Vafthrudnir.

Vafthrudnir (Teutonic)
Also known as: *Vafthrudni.*
Frost Giant. Possibly a god of riddles. A giant of great intelligence, Vafthrudnir matched wits with Odin who used the name Gangrad supplied by Frigga. The stakes were that the loser would also lose his head. Odin won, but it is not known if the giant lost his head.

Vafud (Teutonic) A name for Odin. *See also* Odin.

Vaghan (Tierra del Fuego)
Vaghan is another name for the supreme deity, Alakaluf.

Vagisvara *Vagiswara* (India) A name for Manjusri (q.v.).

Vagiswara (India) *see* Vagisvara.

Vague (Antilles Islands, Haiti)
Another name for the supreme being, Guamaonocon.

Vah (Persian) *see* Vahran; Verethraghna.

Vahagn (Armenia)
"Dragon Killer." God of fire. One of a triad with Aramazd and Anahit. This triad is similar to the Persian Auramazda, Anahita, and Mithra. Vahagn was once a rival of *Ba'al Shamin* and Mihr, both sun-gods. He had been accused of stealing straw

and the wife of Ba'al Shamin. He used the straw to form the Milky Way. Vahagn might be the same as the Armenian storm god known as Dsovean. (Both gods were sea-born.) There is even a possibility of him being preceded by the pre–Vedic Vrtrahan. Vahagn's consort is sometimes said to be love goddess Arusyak ("Little Bride"). Vahagn bears some similarity to the fire god Agni. *See also* Anahit; Aramazd; Astaik; Ba'al Shamim; Dsovean.

Vahran (Persian)

Vahran is the name for Verethraghna, the genius of victory, in the Pahlavi dialect. *See also* Verethraghna.

Vahu (Polynesia)

A name for Tangaroa, the creator god. *See also* Tangaroa.

Vaidya-nath (India)

"Lord of the Knowing Ones," or "Lord of Physicians." *See also* Shiva.

Vaijayanta (India) Indra's palace. *See also* Indra; Swarga.

Vaikhari (India)

A name for Vach, the goddess of knowledge and speech. *See also* Vach.

Vaikuntha *Vaijayanta* (Hindu; India)

Vishnu's celestial abode is a city of gold and jeweled palaces. It is located on Mount Meru and has a circumference of 80,000 miles. The river Ganges, sometimes said to have its origin in Vishnu's foot, runs through his kingdom. Blue, red and white lotuses bloom in the five surrounding pools. Vishnu and his wife, the goddess of beauty Lakshmi, radiate like the sun as they sit amid the white lotuses. *See also* Amaravati; Lakshmi; Loka; Meru Mountain; Swarga; Vishnu.

Vainamoinen *Wainamoinen* (Finland)

Vainamoinen, the hero, god of music, magician and the enchanter, invented the zither. According to some legends Vainamoinen is the brother of Lemminkainen and Ilmarinen. When he plays his instrument he quiets the elements and all wild animals. Vainamoinen remained in his mother Luonnotar's womb until he became bored, thirty years later. He married the daughter of the evil sorcerer Louhi, the Lady of Pohja (also spelled Pohjola). Vainamoinen had the smith god, Ilmarinen, manufacture the talisman known as Sampo. Joukahainen promised Vainamoinen that he could marry his sister, Aino. Repulsed by the thought of marriage to the elderly man she ran away, fell into the sea and became a water spirit. Vainamoinen is the same as the Estonian god of music, Vanemuine. Forged from magic metals, Sampo is a mill that grinds out grain, salt and even gold upon demand. It represents a source of prosperity. *See also* Aino; Hiisi; Ilmarinen; Ilmatar; Jumala; Lemminkainen; Louhi; Luonnotar; Pohja; Sampo.

Vairagis *Vairajas* (India) *see* Loka.

Vairajas (India) *see* Vairagis.

Vairocana *Vairochana* (Buddhist; India, Nepal); (Ryobu-Shinto; Japan)

Also known as: *Dainichi Nyorai* (Japan), *Kun-Rig, Marichi* (possibly), *P'i-Lu-Cha-Na* (China), *rNam-parsnon-sras* (Tibet).

Vairocana is the fourth of the five contemplative Buddhas, known as the Dhyani Buddhas, except in Nepal, where he is placed as the first contemplative Buddha. The Buddha of compassion, his consort (shakti) is Vajradhatvisvari, known as the Queen of Vajra Space. Other references name his consort as the Shakti Nam-kha-ing-kya-wang-chug-ma, the Divine Mother of Infinite Space, also known as Akasha Dhatu Ishvari. He is a pious Buddha who respects law and the scriptures. He is the master of the temple and its contents. Vairochana represents the cosmic element of form known as rupa and he presides over the autumn season. In the mandala of the five tathagatas (also known as five families), Vairocana is placed in the center of the first tathagata. In this position, he represents the basic poison of confusion and also its opposite, the reversal of ignorance. Akshobhya, the ruler of the Vajra family, is the second tathagata, who generally appears in the eastern side of the mandala, at the bottom. In some texts, he appears in the center with Vairochana. The poison of the Vajra family is hatred. The hatred is transmuted into wisdom. On the southern side of the mandala is Ratnasambhava (the jewel bearer), ruler of the ratna family. The ratna is the jewel which grants all desires. The poison of the ratna family is pride resulting from the possession of riches. The antidote is the wisdom of equality and equanimity. In the five tathagatas mandala, Amitabha is placed above, in the west. His family, the padma (lotus), symbolizes desire and passion. The antidote is discrimination, which provides coolness and detachment. The passion is transformed into compassion. On the northern side (the right) is Amoghasiddhi who represents the karma family (meaning action). It is symbolized by the sword or the double Vajra (thunderbolt). The poison of the karma family is the energy of envy and some say confrontation (sanskara). The antidote is wisdom which accomplishes all actions. Sanskara is also refinement, erudition and education. In China, Vairocana is known as P'i-Lu-Cha-Na and is considered a god of light. Vairocana's color is blue and sometimes white. (His attributes are sometimes alternated with the attributes of Aksobhya.) He is seated in a meditative position (dhyana) with his two hands held against his chest, the tips of the fingers united. This mudra (pose) signifies preaching and turning the wheel of the law. It is also the mudra of Gautama and Maitreya. Vairocana's mount is the lion, sometimes depicted as a dragon. His emblems are the wheel (chakra) and bell (ghanta). Without form (rupa) there cannot be individual existence. Autumn represents the disintegration of forms. Vairocana is often depicted in the meditative pose, white in color with four faces, holding an eight-spoked wheel. This pose indicates that he is both the center and everywhere. The wheel represents transcending the concepts of direction and time. In the Ryobu-Shinto tradition, the Shinto sun goddess Amaterasu is Vairocana. *See also* Akshobhya; Amaterasu; Amrtakundali; Buddha; Dainichi-Nyorai; Dhyani Buddhas; Fudo-Myoo; Herukas; Marichi (A); Namasangiti; Ratnasambhava; Shakti; Tara (B); Vajrasatwa.

Vairochana (India) *see* Vairocana.

Vairochi (India)

Vairochi is another name for the demon with a thousand arms, Bana (q.v.)

www.ebook3000.com

Vaishnavi (India) Wife of Vishnu. *See also* Devi; Manasa.

Vaisravana (India)
Vaisravana is another name for the giant snake Vasuki, who is one of the three rulers of the Nagas in Patala, the underworld. *See also* Kuvera; Nagas; Patala; Takshaka; Vasuki.

Vaitarani (India) Hindu river of death. *See also* Yama.

Vaivasvata (India)
"Son of Vivasvat." Vaivasvata is the Manu for the seventh and present world cycle. Vaivasvata was the pilot of the ship that was tied to the horn of the great fish, Matsya, who is an avatar of Vishnu, during the great flood. Ida, an earth goddess and goddess of speech and vital air, is the daughter and possible wife of Vaivasvata. She is also called the instructor of Vaivasvata. *See also* Ida (B); Manu; Matsya; Vasuki; Vishnu; Yama.

Vaja (India)
Vaja and his brother Vibhan (also called Vibhu) are known as the Ribhus. They are the sons of Indra and the goddess of the morning light Saranyu, who is the daughter of Tvashtri. In some legends, they are the sons of Sudhanvan, the "good archer." The Ribhus, artisan elves, learned their skills from their grandfather, Tvashtri. For additional details, *see* Ribhus (The).

Vajra (India) Magic Thunderbolt. *See also* Tvashtri; Vairocana.

Vajra Dakinis (India) *see* Dakinis.

Vajra-Pani (India; Sanskrit) *see* Vajrapani.

Vajra-shringhala *Vajra-shringkhala* (Tibet)
Vajra-shringhala is found in the Bardo World on the Sixth Day. For a list of her companions, *see* Ankusha. *See also* Cha-dog-ma.

Vajra Tara (India)
Another name for Tara. *See also* Khadga Jogina; Tara.

Vajra-Varahi (Tibet) *see* Varahi.

Vajra-Yogini (Tibet)
Also known as: *Dorje-Naljorma; Toma.*
She is a Tantric goddess. For details, *see* Dorje-Naljorma; Toma.

Vajrabarahi (India)
Another name for Dorje Phogmo, the Thunderbolt Sow. *See also* Dorje Phogmo; Sambara (B); Varahi.

Vajradhara *Adibuddha* (Buddhist; Nepal)
Vajradhara, an aspect of Adibuddha, is presented in a single form and in yabyum (male, female). In single form he is decorated with jewels and sits in an attitude of meditation (vajraparyanka), with the thunderbolt or wand that destroys ignorance (the vajra) in the right hand and the bell (ghanta) in his left hand. His two hands are crossed against his chest. In yabyum, his form is the same except that he embraces his female counterpart. Vajradhara and Vajrasawta are sometimes confused with one another. *See also* Adibuddha; Vajrasawta.

Vajradhatvisvari (Nepal)
"Queen of Vajra Space." Vajradhatvisvari is the consort of Vairocana, the fourth of the five contemplative Buddhas. *See also* Dhyani Buddhas; Vairocana.

Vajradhupa (Buddhist; India) Goddess of Incense.

Vajradipa (India)
Another name for the goddess of the lamp,Vajraloka.

Vajragandha (Buddhist; India) Goddess of Fragrance.

Vajragiti (Buddhist; India) Goddess of Song.

Vajrahara (India)
Vajrahara is another name for Manjusri, the god of learning, speech, science, and wisdom (q.v.).

Vajraheruka (Tibet) *see* Herukas.

Vajrajogini (India) *see* Kali; Khadga Jogini.

Vajraloka *Vajradipa* (Buddhist; India) Goddess of the Lamp.

Vajranga (Buddhist; India) Another name for Manjusri (q.v.).

Vajranrtya (Buddhist; India)
Goddess of the Exuberant Dance.

Vajrapani *Vajra-Pani* (Buddhist, Hindu; India)
Also known as: *Acala, Acaryavajrapani, Bodhisattva Chakdor* (Tibet), *Hayagriva* (Horse-Necked), *Heruka, Phyag-nardorje* (Bearing the Dorge in Hand; Tibet), *P'yag-na-rdo-rje* (Tibet), *Sakyamuni, Sotshirvani* (Siberia).
"Wielder of the Thunderbolt." Vajrapani is a Dhyanibodhisattva and the second of the five Buddhist creators of the universe. The other Dhyanibodhisattvas are Avalokitesvara, Ratnapani, Samantabhadra and Visvapani. Vajrapani is the spiritual son of Dhyani Buddha Akshobhya and his shaki (consort) Mamaki. Vajrapani means the vajra-holder. Vajra means thunderbolt. The thunderbolt is the symbol of extraordinary mystical power and divine energy. It also denotes the male principle, and the axis of the universe. Vajrapani's realm is "The Realm of Those of Long Hair." It is his paradise and not a Buddha Realm. He is known as the clearer of obstructions. In legend, he manifested himself as Hayagriva to subjugate the wrathful deity, Rudra, known as "The God of Storms" and "The Lord of Time and Death." Vajrapani as Hayagriva has a horse's head and is red in color. He entered Rudra's body through his anus. Rudra acknowledged the domination and offered himself as a throne to Vajrapani. Rudra's costume and attributes were transmuted into the Heruka Buddha costume. As a rain god, Vajrapani protects the nagas (serpents), who bring the rain from the garuda birds. Acala and Acaryavajrapani are manifestations of Vajrapani. In an early incarnation, Vajrapani was Sakyamuni, who is the third Buddha and the fourth Manushi-Buddha. Vajrapani as Vajrapani, and in his manifestations as the Supreme Heruka or Hayagriva, is an exorciser of evil spirits. He is a Dharmapala one of the hideous giants who are the Protectors of Religion in Buddhist tradition. Vajrapani, white in color, holds the vajra and the lotus. He is often depicted with a naked upper body. Vajrapani appears in the Gandharva (also

called Gandhara) sculptures as a Zeus, Eros, Pan, Heracles or a Dionysus. The Gandharva school was of Greek influence and represented Buddha standing. In the mixed Hindu-Buddhist tradition, Vajrapani is the same as Indra (q.v.). *See also* Akshobhya; Amoghasiddhi; Avalokitesvara; Buddha; Dhyanibodhisattvas; Heng and Ha; Heruka; Indra; Lhamo; Mamaki; Manushi-Buddhas; Nagas; Otshirvani; Samantabhadra.

Vajraraga (Buddhist; India) God of love.

Vajrasattva (India) *see* Vajrasatwa.

Vajrasattvamika (Nepal)
She is the consort of Vajrasatwa and the mother of the Bodhisattva, Ghantapani (q.v.).

Vajrasatwa *Vajrasawta* (Buddhist; Nepal)
Also known as: *Dhyani Buddha, Dorje-sem-pa* (Tibet), *P'i-lu-cha-na* (China), *rDorje-sems-dpa* (Tibet), *Vajra-sattva, Vajrasattva, Vajrassattvamika* (Nepal).

"Courageous Thunderbolt Soul." Vajrasatwa is regarded by Nepali Buddhists as the priest of the five contemplative Buddhas, known as the Dhyani Buddhas. Independent shrines are dedicated to Vajrasatwa and his worship is always performed in secret for those initiated into the mysteries of Vajrayana. *Vajrasatwa* is worshiped as Adibuddha by the Red Cap sect in Tibet. Sometimes Vajrasatwa is included as a sixth Dhyani Buddha. His consort is Vajrasattvatmika and their son is the Bodhisattva Ghantapani. Vajrasatwa is represented in two forms, single and yab-yum. Yab means the "honorable father" and yum means the "honorable mother." The combined word means father in company of or the embrace of mother. Vajrasatwa, white in color, wears ornaments and a crown upon his head. Like the other Dhyani Buddhas, he sits cross-legged in a meditative pose. He carries the vajra and ghanta (bell) in his right hand with his palm upwards against his chest. His left hand rests upon his left thigh or in his lap. Vajrasatwa originates from the syllable HUM. *See also* Akshobhya; Amitabha; Amoghasiddhi; Amrtakundali; Dainichi-nyorai; Dhyani Buddhas; Mamaki; Ratnasambhava; Vairocana; Vajradhara.

Vajravarahi (Tibet) *see* Varahi.

Vajravina (India)
A name for the goddess of speech and learning, Sarasvati (q.v.).

Vajrayana (Nepal) *see* Chakra Sambara; Sambara.

Vaka (India)
Vaka is a demon killed by the ferocious Pandava, Bhima. *See also* Bhima (A).

Vakea (Polynesia) *see* Vatea.

Valaskjalf (Norse; Teutonic)
Also known as: *Shelf of the Slain.*

Home of the gods. Valaskjalf is one of the mansions of Odin, in Asgard. In Valaskjalf, he sits on his throne named Hlidskjalf and he rests his feet on a footstool of gold, as he surveys the world. Valaskjalf contains furniture and utensils of silver and gold manufactured by the gods. *See also* Asgard; Hlidskjalf; Valhalla; Vali (C).

Vale (Teutonic) *see* Boe; Odin; Vali.

Valetudo (Italy) Health and victory goddess.

Valfadir (Teutonic) *see* Odin.

Valfather (Teutonic)
Also known as: *Allfather.*

Valfather is an aspect or another name for Odin. *See also* Odin.

Valhal (Teutonic) *see* Valhalla.

Valhalla *Valhal, Walhalla* (Norse; Teutonic)
Also known as: *Hall of the Slain.*

Home of the gods. A great hall, the beautiful dwelling place of Odin and the other Scandinavian gods. Odin feasted in this temple of immortality daily on wine and boar's meat with all his chosen slain warriors who had fallen in battle. Some say he never ate, but subsisted on mead alone. Valhalla had five hundred and forty doors wide enough to allow eight hundred warriors to enter abreast. A boar's head and an eagle were above the principal gate. The walls of the building were fashioned of spears and the roof was made of golden shields. Compare to Amaravati. *See also* Valaskjalf.

Vali (Norse; Teutonic)
Also known as: *Ali (A), Beav, Bous, Vale, Voli.*

Possibly a god of vegetation and god of archery, Vali is the son of Odin by his third wife Rinda (also called Rind). Vali was born and reached full stature in one day and killed Hodur in revenge for the death of his half-brother Baldur (Balder). Vali will survive Ragnarok. Possibly the same Vali is the son of Loki and Sigyn and brother of Nari or Narvi. This Vali was turned into a wolf by the gods. He is usually shown as an archer. *See also* Odin.

Valkjosandi *Chooser of the Slain* (Teutonic) *see* Odin.

Valkyr (Teutonic) *see* Valkyrie.

Valkyrie *Valkyr, Valkyries* (Plural), *Valkyrja, Valkyrs, Walkure, Walkyrie* (Teutonic)
Also known as: *Alaisiagae.*

Goddesses of fate. Odin sent the beautiful Valkyries into battle to decide who would survive, and who would die. There are two classes of Valkyrie: the celestial, and the half-mortal, half-divine group. The latter group often lives among mortals for a time. Later, they return to Odin in Valhalla. When not on duty as goddesses of fate, they served as cup-bearers to Odin and the fallen heroes. Some of the goddesses serve in menial positions. They ride around on their horses in groups of three. The number of Valkyries, however, varies widely. A few of the better known Valkyries are Gundul, Hild, Lokk, Mist, Skogul, and Skuld. The Valkyries are closely related to the Norns (q.v.). They are similar to the Celtic Morrigan.

Valkyrja (Teutonic) *see* Valkyrie.

Valkyrs (Teutonic) *see* Valkyrie.

Valland (Teutonic) *see* Volund.

Vamana *Vamen, Vamena* (Hindu; India)
Also known as: *Bamun Owtar* (Vamana Avatar).

www.ebook3000.com

Pull. Think and smile to your Tan Tien. Push, very far away to the universe. Pull. Push: Smile, relax, and let go, touching the sky, touching the universe.



Fig. 3.36
Let go - Push and Touch the Universe, do it 6, 9 or 18 times.

Left and Right Directions

Now, move your hands to the left and right directions. Pull the Universal energy in. Push; touch the universe. Pull; think about your Tan Tien. Push – all the way, touching-touching-touching the universe.



1. Move your extended hands from the front horizon to the left and right sides.

Fig. 3.37 *Touch the Universe Left and Right.*

Vamana, a dwarf, is the fifth avatar of Vishnu. He returned to earth as the son of Kasyapa and Aditi. Another reference records that Vamana was the son of Kusht and Arwut and that he lived one thousand years. The gods had requested that he rid heaven and earth of the giant demon Bali, who was a Daitya. Bali was not evil but he had developed into a powerful ruler of the three worlds. Vamana approached King Bali under the pretense of being a poor man in need of land. He finally talked the king into giving him as much land as he could cover in three steps. Because of his diminutive size, the king agreed to his request. Vamana then grew into his omnipresent size and covered the entire earth with his first step, and the heavens with his second step. His third step could have encompassed the lower worlds but he decided to give a section of Patala to Bali. Bali is the grandson of Prahlada and the great-grandson of Hiranya-kasipu, who were involved with Vishnu during his avatar as the half-male, half-lion named Nara-Simha. Bali the demon represents darkness and the gods represent light. *See also* Daityas; Dikpalas; Hiranya-kasipu; Lakshmi; Lokapalas; Nara-Simha (Vishnu's avatar as half-man, half-lion); Parashur Rama; Patala; Prahlada; Vishnu.

Vamen (India) *see* Vamana.

Vamena (India) *see* Vamana.

Vammatar (Finnish)
Goddess of disease. Daughter of Tuoni and Tuonetar. Sister of Loviatar, Kipu-Tytto, and Kivutar. They live in Tuonela. *See also* Tuonetar.

Vamsa (Buddhist; India) Goddess of the Flute.

Vanadevatas (India) *see* Devis.

Vanadis (Teutonic)
Vanadis is another name for Freya given to her because she came from the Vanir race. As Vanadis she was worshiped in Disir at Uppsala. She is a member of a group of goddesses called Disir. The Disir were known for their concern for the good of the home and family. *See also* Aesir; Disir; Frejya; Vanir.

Vanagods (Teutonic)
The sea and wind gods, also referred to as Vanas (q.v.). *See also* Vanir.

Vanaheim (Norse; Teutonic)
Home of the gods. Home of the Vanir who were later integrated with the Aesir.

Vanant (Zoroastrian; Persia)
An unidentified star or constellation, and a Yazata (q.v.).

Vanas (Teutonic) see Vanir.

Vanavasas (India)
The Vanavasas are forest dwellers ruled over by Sugriva, the brother of Bali. *See also* Sugriva.

Vandya (India) A Yakshini. *See also* Yaksha and Yakshini.

Vanemuine (Estonian)
He is a god of music who is the same as the Finnish Vainamoinen (q.v.).

Vaner (Teutonic) *see* Vanas; Vanir.

Vanir (Norse; Teutonic)
Also known as: *Vanagods, Vaner, Vanir.*
Race of fertility gods. The Vanir, a peace-loving group who lived in Vanaheim, watched over the fruits of earth and all living things. The Aesir and the Vanir were constantly at odds with one another. Finally the two races were able to negotiate a peace treaty. As well as exchanging hostages, the Vanir were at last admitted to Asgard, the celestial home of the Aesir. *See also* Aesir; Asgard; Njord (re: terms of the hostage exchange); Frejya; Vanaheim.

Var (Teutonic) *see* Vor.

Vara (Teutonic) *see* Vor.

Varaha (Hindu; India) *Varaha-Avatara, Varahavatar.*
Also known as: *Vishnu.*
Varaha, the wild boar, is the third avatar of Vishnu. He assumed this form to drive the demon Hiranyaksha from power. After the Great Deluge, as he searched for the earth, he found that Hiranyaksha had hidden the earth under water. A battle lasting a thousand years ensued. Varaha emerged the victor and brought the planet to the surface again. In another rendition, Varaha overthrew the evil giant Hirnakess (or possibly Hiranyaksha) thought to be a Daitya, who attempted to keep him from his mission. He reached to the ocean's depths and rescued the earth goddess Bhumidevi. The tusks of Varaha supported her and enabled her to bear the weight of her creation. Lakshmi is his wife once again, in her avatar as Varahini. Sukapreyasi the sow goddess also appears as his wife during this period. In another rendition of this tale, the world is overpopulated. Varaha has to lift it with one tusk from time to time. The shift causes earthquakes, which keep the population in check. The wild boar is an earth symbol. *See also* Daityas; Hiranya-Kasipu (regarding Hiranyaksha); Kurma (the tortoise avatar of Vishnu); Lakshmi; Manu; Matsya (the fish avatar of Vishnu); Nara-Simha (Vishnu's avatar as half-man, half-lion); Vishnu.

Varaha-Avatara (India) *see* Varaha; Vishnu.

Varahavatar (India) *see* Varaha.

Varahi (Buddhist; Nepal)
The Varahi protect temples and buildings. Four Varahi protect the four corners of Kathmandu Valley in Nepal. They are Vajravarahi (also known as Dorje Phagmo), who is red and protects the livestock in the western quarter of the Kathmandu valley in Nepal; Nilavarahi, who is blue and protects the east; Swetavarahi, white, guards the south; and Dhumbarahi, grey, guards the north and is said to protect the valley from cholera. Vajravarahi is also known as the goddess of pleasure. As well as the embodiment of pleasure, she is the essence of five types of knowledge. Vajravarahi has two arms, one head with disheveled hair, three eyes, and is depicted nude. On her head she wears a garland of heads said to be wet from the blood she drinks. She is shown standing on the gods Bhiarav and Kalratri. In her right hand she holds the vajra, which is the thunderbolt or diamond that destroys ignorance. *See also* Dakinis; Dikpalas; Dorje Phagmo; Sambara.

Varahini (India)
An avatar of the beautiful goddess, Lakshmi (q.v.). *See also* Varaha.

Varanga (India)
A name for Manjusri, the god of speech and learning. *See also* Manjusri.

Varcin (Hindu; India)
A demon hostile to mortals who was overcome by Indra.

Vardhamana (India)
A name for the "Great Man," Mahavira (q.v.).

Varegan (Persian, Iranian) *see* Vareghna.

Vareghna *Varegan, Varengan* (Persian, Iranian)
The raven form of the god of war and victory, Verethraghna (q.v.).

Varengan (Iranian, Persian) *see* Vareghna.

Vari (A) (Indonesia, Polynesia)
Also known as: *Atea, Vari-Ma-Te-Takere, Wakea.*

In some accounts, Vari is the self existent being who lives at the bottom of the coconut shell called Avaiki, the land of the dead. (Avaiki, meaning "mud," was said to be the source of all life.) Below Vari is Take, the root of the universe. In another version of this myth, Vari-Ma-Te-Takere is the mother of Vatea, Tinirau, Tango, Tu-Mute-Anaoa, Raka, and Tu-metua. In still another version, she is the great mother goddess Vari-Ma-Te-Takere who plucked the gods and men from her left side. Parts of her body were distributed to Tinirau, Tango, Te-paraitea, and Raka. From her right side she plucked Tu-metua. In the Polynesian island of Mangaia's Creation Legend, Vari's daughter Vatea rules the underworld. Vari is the grandmother of the sky god Tangaroa, and the god of the underworld, Rongo. *See also* Atea; Avaiki; Raki; Tangaroa; Tango; Tinirau; Tu-Metua; Vari (A); Vatea.

Vari (B) (India) "Fair Faced." *See also* Devi.

Vari-Ma-Te-Takere (Polynesia) *see* Vari (A).

Varpulis (Slavic)
Wind god. Varpulis causes the noise of storms. He belongs to a group of wind gods who are associated with Perun. Varpulis is equated with Erisvorsh. He is possibly related to Stribog, the god of winter, and Dogoda, the west wind. *See also* Perun; Stribog.

Varshayanti (India) A Krittika sister. *See also* Rishi.

Varuna (Brahmanic, Buddhist, Hindu, Vedic; India; Persia)
Also known as: *Ahura Mazda* (Persia), *Amburaja, Jadapati, Jalpati* (Lord of the Waters), *Pasi, Prasetas* (Supremely Wise), *The Aditya* (Eternal Celestial Light), *Trita, Yadahpati* (Lord of the Living Beings in Water).

In early times, Varuna was the universal monarch and the guardian of cosmic law. He created the three worlds: the heavens, earth, and the air between them. He was all-seeing and a judge of the actions of mortals. His name means "the coverer," meaning the sky. He was the son of the sun goddess Aditi. His siblings were Mitra, Aryaman, Indra, Savitri, Bhaga, Ansa and Martanda (Vivasvat), and a sister, the goddess of dawn, Ushas. Later, he fell to the ranks of a secondary deity. He was a Dyad with the Vedic solar deity Mitra. As Mitra and Varuna (Mitra-Varuna), the sun and the moon, they are always present to guard and witness all actions and events. Endowed with magical powers, they understood the powers of certain devas (gods) and demons. Mitra-Varuna, the divine two-in-one, is coupled with the goddess Danu. He is part of a triad with Mitra and Aryaman. He is also one of the Vedic triad with Mitra and Agni (Divine Father, Divine Son and Holy Spirit). His early name was Asura (Lord), which is the same word as Ahura in the Parsi language. As ruler of the western direction, his domain included the Arabian sea. In Persia, he became Ahura Mazda, the Wise-Lord of the *Avesta*. In Vedic hymns he has a Hebraic quality, resembling the Yahweh of the Old Testament. His Sanskrit name means "sky" and in later times he was the head of the pantheon of Indo-European gods (the Adityas), who represent the military power of the gods. World order was maintained by their use of magical powers. In the *Mahabharata*, Varuna is the son of Kardama. He mated with the nymph Urvasi, and they had a son, the sage Vasistha, who was born from her soul. Varuna's kingdom is Sukha (happiness), located on Pushpa-giri (flower-mountain). In other versions, his wife is Gauri or Varunani, the goddess of wine, and his consorts are Ganges and Jumna. With Varunani a daughter, Varuni, was born, who is known as the Goddess of Spirituous Liquor. Varuna presides over the care of the sacrificial ambrosia, Soma, which is stored in the moon. There is a possibility that Varuna and the goddess Lakshmi were married. In some traditions, Varuna was usurped by Indra. When that happened, Varuna was relegated to the role of one of the Asuras (demons) and was removed from the celestial realm to the bottom of the ocean. He still retained his power, for in Indian mythology, gods and demons are of equal strength. Other scholars say that Indra reestablished the rule of Varuna. Indra and Varuna are often invoked together as a dual deity, as are Mitra and Varuna. Varuna is considered a Vedic rain god, as are Indra, the Maruts and Parjanya. He is often associated as lord of the dead with Yama, who was the first man to die. In later times he became known as the receiver of souls who died by drowning, and as guardian of the night. In the Buddhist tradition, Varuna emanated from the belly of the Dhyani Buddha, Avalokitesvara (The Lord Gifted with Complete Enlightenment). Varuna is depicted as white skinned, with a thousand eyes and four arms. Draped in a golden mantle, he sits on a throne. In later times he was shown riding a sea monster, half-crocodile, half-bird, known as Makara (q.v.). He holds a noose or lasso to snare non-believers. The lasso noose also indicates his function as a judge. The noose, often called "The Noose of Varuna" is called the Naga-pasa, or "snake noose," from which the wicked cannot escape. The god of death Yama (q.v.) also casts a noose over his candidates. Astovidad, the Persian demon of death, is another deity who uses a noose to perform his duties. Varuna also holds a container of gems which symbolize fertility. The horse is Varuna's sacred animal. Varuna also appears as Capricornus. In this form, he has the head and forelegs of an antelope and the body and tail of a fish. This is the same emblem as the Babylonian god Ea. Repentance for sins is granted at a festival known as Varunapragh. Compare Varuna to Uranus, Poseidon (Greek), Odin (Teutonic) and Lugh

www.ebook3000.com

(Celtic). Varuna is associated with the Japanese sea deity Suitengu (q.v.). Varuna is sometimes confused with Indra and Agni. Trita is an aspect of Indra and Agni. Varuna is often identified with the god of ecstasy, Soma (q.v.) *See also* Aditi; Adityas; Asuras; Avalokitesvara; Brihaspati; Daityas; Dipkalas; Diti; Krishna; Lokapalas; Mitra; Parashur Rama (Vishnu's avatar as a dwarf); Ravana; Soma; Surya; Urvasi; Ushas; Vasistha; Vedas (The); Yama.

Varunani (India) *see* Varuni.

Varuni *Varunani* (India)
Also known as: *Shakti.*
(India) Goddess of Spirituous Liquor. *See also* Gauri; Kurma; Shakti; Soma; Varuna.

Vasa (Finnish) *see* Kul.

Vasanta (India)
The Deity of Blossoming Flowers. *See also* Kama.

Vasanta-Bandhu (Hindu; India)
"Friend of Spring," God of Love.

Vashita (Hindu; India) Goddess of Discipline.

Vashti (Semitic)
A little known Elamite goddess. Possibly associated with Varuna.

Vasishta (India) *see* Vasistha.

Vasistha *Vasishtha* (Brahmanic, Hindu, Vedic; India)
Also known as: *Adi.*
"Most Wealthy." Vasistha is the son of Varuna or some say Surya or Mitra. He was born from his mother Urvasi's soul. He is one of the seven Rishis who are divine sages, poets, and prophets, and one of the ten Prajapatis, the ten beings created by Brahma or by Manu who were assigned to carry out specific tasks in the creation of the world. A solar deity, and pupil of Agni, he composed the *Rig-Veda* hymns. He once owned the miraculous "Cow of Desires," Kamadhenu. The goddess Arundhati, thought to be one of the seven Krittikas, is Vasistha's wife. There is a possibility that she was the mother of seven or one hundred sons. In one legend, Vasistha is said to have had a hundred sons who were all murdered by a Rakshasa who devoured them. Grief-stricken, he attempted suicide several times but was unsuccessful. He threw himself from a high mountain but the rocks below turned soft. He walked into a burning forest but the flames would not burn him. He jumped from a ship and was washed ashore. Finally, he tied his hands and threw himself into a river. The river Byas untied him and moved him safely to the shore. The Byas is still called "the Untier." Later, he wed Urja, a daughter of Daksha, and they had seven sons. Adi, an incarnation of Vasistha, is a demon who can take the shape of a bird or a snake. *See also* Agni; Brahma; Daksha; Kamadhenu; Kasyapa; Manu; Mitra; Nandi; Parashur Rama; Prajapati; Rakshasa; Rishi; Surya; Urvasi; Varuna; Vishnu.

Vasu (India) *see* Vasus.

Vasu Deva (India) *see* Vasudeva.

Vasud (Teutonic)
Icy Wind. He is the father of Vindsual who is the father of Winter (god of winter). These winds were set in motion by the giant Hraesvelgr. *See also* Hraesvelgr; Winter.

Vasudeva *Vasu Deva* (India)
The Universal Spirit. *See also* Bala-Rama; Brahma; Devaki; Kunti.

Vasuki *Vaisravana* (Hindu; India)
This gigantic snake is one of the three rulers of the Nagas in Patala. He served as a rope for the gods to churn the sea of milk and again for Vaivasvata to moor his ship to the horn of Matsya (the fish avatar of Vishnu) during the great flood. He is the ruler of the West and the snakes he rules are gods of the rains and of prosperity who can assume human shape. He is often identified with Vishnu's snake, Sesha. In some renditions, Sesha and Vasuki were both tied around Mount Mandara to serve as ropes for Kasyapa when he churned the ocean of milk. Vasuki sent Garuda a serpent a day to eat, to avoid having the Nagas annihilated. Vasuki is usually depicted in human form wearing the crest of a serpent. *See also* Devas (A); Garuda; Kurma (Vishnu's avatar as a tortoise); Lokapalas; Matsya; Nagas and Nagis; Patala; Sesha; Shiva; Vishnu; Yaksha and Yakshini.

Vasundhara (Buddhist, Hindu; India)
Vasundhara, an earth goddess and goddess of wealth, is the mother of the goddess of agriculture, Sita, and a son, Naraka. Vasundhara is the Buddhist counterpart of the Hindu Lakshmi. Vasundhara has four hands and holds a sheaf of paddy, a full vase, and jewels. She has three faces with different complexions. The right face is brown, the middle face is yellow and her left face is reddish. She is also shown as a six-armed crowned goddess in a dancing pose. Four of her hands hold symbols of abundance. Two of her hands are held in the varada (gift-giving) mudra. This gesture shows the arms pendant, all fingers extended downward and the palms facing outward. Vasundhara symbolizes the earth. She is honored to prevent poverty. *See also* Amoghapasa Lokeswara; Lakshmi; Sita.

Vasus, The (Vedic; India)
The Vasus are a group of seven, eight or nine demi-gods, children of Aditi, who are the attendants of Indra. Their names are Vasu (wealth), Apa (water), Anala (fire), Dhara (earth), Dhurva (the pole-star), Prabhasa (dawn), Pratyusha, (light), and Soma (moon). Anila (wind) is added in some descriptions. Chandra the moon god is sometimes included in the group of eight attendants to Indra. Nakshatras, meaning "stars," is sometimes included as one of the attendants. Groups of Vedic gods, like the Adityas, Maruts, Ribhus and Vasus, often are represented as rays of the sun, as stars or as constellations. The Vasus are symbols and personifications of natural phenomena. *See also* Aditi; Adityas; Chandra; Ganga; Indra; Maruts; Ribhus.

Vasusena (India)
A name for Karna, the great warrior, born of miraculous birth. *See also* Karna.

Vata (Iran) The god of the winds. *See also* Vayu.

Vatea *Vakea* (Polynesia)
Also known as: *Atea, Avatea.*
Vatea is known as the first man and the father of gods and mortals. In one version of this myth, Vatea was half-man and

half-fish. He came from the demon woman Vari-Ma-Te-Takere (Vari). She in turn came from Avaiki, the lowest part of the shell which is the universe. In another version, Vatea and Tangaroa argued about who was the first born of Papa. To settle the dispute Papa was cut in two and Vatea took the upper half and threw it into the sky where it become the sun. Tangaroa left the lower half of Papa on the ground until it was drained of blood and decomposing. Then he threw it into the sky where it became the pale moon. Vatea was given the land named Te'-papa-rairai or Te enua marama o Vatea by the great goddess, Vari-Ma-Te-Takere. In still another version, Vatea is the lover and wife of Papa. In the Mangaia Islands, Vatea is the husband of Papa, and the father of Rongo and Tangaroa. Papa influenced him to favor his son Rongo and disown Tangaroa. The other demons in *Avaiki* were Te-aka-ia-oe, Te-tangaengae or Te-vaerua, and Te-manava-roa. Some say one eye of Vatea was like a fish and the other like a human, others say one eye is the sun and the other eye the moon. Vatea's brothers are Tinirau, Tango, Raki, and Tumuteanaoa. (Some myths refer to Tumuteanaoa as a female.) There is another child of Vari, named Tu-metua (Tu), who was the principal god or goddess of the Polynesian people. Tu was also thought to be the aunt of Tangaroa. In some legends, Tumateanaoa or Tu-metua is the wife of Vatea and she was really named Papa. *See also* Atea; Avaiki; Papa (A); Raki; Rangi; Rongo; Tu-metua; Tumuteanaoa; Vari (A).

Vatsasura (India) A female cow demon. *See also* Krishna.

Vayu (Indo-Iranian, Persian, Vedic; India)

Also known as: *Marut, Maruta, Pavana* (Purifying), *Vata*.

Vayu, a nature deity, god of breath, life, air and wind, is said to have been created by the breath of Purusha. As he was created by breath, so does his breath give life to god and mortals. In early times, he was one of a triad with Agni and Surya. Later, Indra supplanted him in the triad. He is the father of the monkey-god Hanuman and of the Pandava, Bhima. His father-in-law is the artisan god Tvashtri. Vayu brings life in the rain clouds and death in the storm. He makes the dawn and lightning appear. Usually gentle, he does have a violent aspect. Angry with Indra, he broke off the peak of the sacred Mount Meru and it became Sri Lanka. He is considered by some to be one of the Maruts (storm gods) and by others to be one of the Vasus who were the attendants of Indra. In the Hindu tradition, with his elephant Pushpa-danta, he is also the guardian of the west. In Persia, Ahura Mazda (the creator), who rules in the light above, and Angra Mainyu (the devil), who rules in the darkness below, offer sacrifice to Vayu, who rules in the void between heaven and hell. Vayu is an assistant of Vohu Manah of the Amesha Spentas. Vayu helps the souls of just mortals surmount any obstacles during the journey they must make after death. Prayers are offered to Vayu in times of danger for he is capable of moving as the wind, swiftly through both worlds. In the Zoroastrian tradition, Vayu is a Yazata (celestial being). He is described as a fearsome broad-breasted warrior wearing the raiment of warfare, and carrying a sharp spear and weapons made of gold. He is also shown in antelope form with a thousand eyes. This symbolizes his swiftness and his ability to be all-seeing. He may be seen driving a carriage pulled by red and purple steeds or in a chariot drawn by two red horses as the storm god Indra's charioteer. He is also shown in a gold chariot, which touches the sky and is drawn by a thousand horses, or in a chariot drawn by three deer. His mount is the deer and his symbol the wheel. Vayu relates to Prana (the breath) and to the practice of Pranayama (breath control). Other nature gods are Tvashtri (the Thunderbolt), Parjanya (the Rain), Apa (the Waters), and Prithivi (the Earth). *See also* Agni; Ahura Mazda; Ameshas Spenta (Persian); Angra Mainyu; Dikpalas; Hanuman; Indra; Kunti; Lokapalas; Maruts; Mitra; Pandavas; Ravana; Soma; Vasus; Vedas (The); Vohu Manah (Persian); Yazatas (Persian).

Vazimba (Madagascar)

Spirit. Mother of Rasoalao and Ravola. Spirits of the dead. *See also* Rasoalao; Ravola.

Vazishta (Iranian)

Vazishta, who represents lightning, killed the demon Spenjaghrya, who represents darkness or winter.

Ve *We* (Norse; Teutonic)

He is the son of Bor and Bestla, and the brother of Odin and Vili. Ve helped create the first man and woman, Ask and Embla, from two trees. They were given senses, expression, and speech. Odin specifically gave them breath. Ve gave them color and body temperature. Vili gave them understanding. They also created the celestial bodies by employing the sparks that flew out of Muspells-heim. With his brothers, Ve killed the giant Ymir. Some identify Ve with Henir (q.v.). *See also* Ask; Audhumla; Bestla; Bor; Embla; Henir; Midgard; Muspells-heim; Odin; Vili; Ymir.

Vedams, The (India) *see* Vedas, The.

Vedas, The *Vedams, The* (Divine Knowledge); (Vedic, Hindu; India)

In the sacred Sanskrit scriptures known as the Vedas, there are four books called the Samhitas: the *Rig-Veda* or *Book of Hymns*, with 1,028 hymns (associated with speech); the *Soma-Veda* or *Book of Songs* (associated with song), a book of chants, mantras, and tunes; the *Yajur-Veda* or *Book of Liturgical Formulae* (associated with expression), sacrificial formulas, prayers, and explanatory material; the *Atharva-Veda* or *Book of Magic Formulae* (associated with emotion), charms and spells and the making of the shastra (law). The Rishis (divine sages, poets and teachers) preserved and handed down the knowledge imparted by the Vedas. The Vedic hymns created the first Hindu mythology. These hymns were addressed to the Vedic gods: Agni (fire), Indra (thunder), Surya (sun), Vayu (wind), Aditi (earth), Varuna (rain and sea), the Ashvins (healers) and Dyaus-piter (father of light). The feared deities are Yama (death), Vrita (drought), Rudra (storm), and the Maruts (whirlwinds). *See also* Agni; Ashvins; Indra; Maruts; Rishis; Rudra; Surya; Vrita; Yama.

Vedavyasa (India) *see* Vyasa.

Vedfolnir (Teutonic) The falcon of the Yggdrasil Tree (q.v.).

Vedic Creation Legend *see* Purusha.

Vediovis (Etruscan, Roman) An early name for Jove (q.v.). *See also* Jove; Jupiter.

Vedius (Roman) *see* Jupiter; Vejovis.

www.ebook3000.com

Vega (Persia) The constellation.

Veggdegg (Teutonic) *see* Thor

Vegtam (Teutonic) *see* Odin.

Vejamat (Latvia) Goddess of the wind.

Vejovis *Vedius* (Roman)
"Little Jupiter." An epithet of Jupiter when he appears without his thunder. The name Vedius is also used under these circumstances.

Vele (Prussia) Spirits of water and the woods.

Veles (Russia) The patron of flocks and harvests. *See also* Volos.

Velint (Teutonic) *see* Volund.

Vema (India) Goddess of sexual love.

Vemacitra (India)
"Splendid Robe." He is the sage of jealous gods. *See also* Amrtakundali.

Venus (A) (Roman)
Also known as: *Acidalia, Anahit* (Armenia), *Anahita* (Persia), *Aphrodite* (Greek), *Bennu-asar, Pi-neter-tauau* (Egypt), *Verticordia.*

Goddess of love and beauty. Mother of Amor by Mars. She is the Roman Aphrodite. Veneralia, her festival, takes place April 1 and August 19. August 19 is also the festival date for Jupiter. Some say Venus is the daughter of Jupiter and Dione, and that she is the mother of Aeneas and Pitho, the goddess of persuasion (by Mercury). *See also* Aphrodite (Greek); Astarte (Phoenician); Anahit (Armenia); Anahita (Persia); Ishtar (Babylon); Isis (Egypt).

Venus (B) The planet. *See also* Anahita (Chaldean); Brihaspati (India); Eurynome (A) (Greek); Ishtar (Babylonia); Tishtrya (Chaldean); Tlahuizcalpantecuhtli (Aztec); Xolotl (Aztec).

Verbeia (Celtic) River goddess. *See also* Sequana.

Verdandi (Teutonic)
Spirits. One of three Norns (goddesses of destiny) who decide the fates of men.

Verethraghna (Persia)
Also known as: *Bahram* (name in later times), *Bairam, Vah, Vahagn* (Armenian), *Vahran* (Pahlavi dialect), *Varegan, Vareghna, Varengan.*

Born in the ocean, he is the chief of the fravashis and the genius of victory. He overcame the dragon Azhi Dahaka, who symbolizes darkness and drought, and tied him to Mount Demavand. His name means "Victory Over Adverse Attack." Some writers describe him as a personification of aggressiveness and the irresistible force of victory and proclaim that he did not kill monsters or dragons. He is depicted as the victor over evilness in mortals and demons, and the administrator of punishment. He has ten incarnations: that of a strong wind which brings health and strength and carries the glory of Ahura Mazda; a golden-horned bull representing rays; a white horse with golden trappings; a youth of the ideal age of fifteen; a burden-bearing camel, shown sharp-toothed and stamping forward, who represents a fertile cloud; a sharp-toothed boar who can kill at one stroke; a swift bird named Vareghna (possibly a raven); a wild ram; a fighting buck; and a man holding a sword with a golden blade (representing the hero). In his boar form, he accompanied Mithra. As a god of war, he is popular with soldiers. In later times, he was known as Bahram, the protector of travelers. Verethraghna is comparable in the Hindu god Indra who as Vritrahan constantly fought to overcome Vrita the drought demon. *See also* Azhi Dahaka; Azurha Mazda; Fravashi; Mithra; Vareghna.

Vergelmir Well (Teutonic)
An alternate spelling for Hvergelmir Well (q.v.).

Vergil *Virgil* (Greek) *see* Styx.

Vertimnus (Roman)
Also known as: *Vertumnus, Vortumnus.*

God of buying and selling. God of the changing seasons. God of gardens. He is the shape changer god who seduced Pomona, the goddess of fruit trees and orchards.

Vesna (Slavic) Goddess of spring.

Vesper (Greek)
Also known as: *Hesperus* (Greek).

Vesper is Venus as the Evening Star. *See also* Eos; Venus.

Vesperus (Greek) *see* Hesperides.

Vessavana (Buddhist, Cambodia)
Lord of benevolent demons. An amulet of this deity is often placed on a child's bed for protection.

Vesta (Roman, Greek)
Also known as: *Caca, Hestia, Prisca.*

The Roman Vesta, who is the Greek Hestia, is the virgin goddess of fire and the guardian of home and hearth. She was worshipped in every household. Her other function was to intervene to save the innocent. Her handmaidens, known as priestesses, are called Vestal Virgins or the King's Daughters and were treated as their names implied. It was the sacred obligation of the Vestal Virgins to keep the holy fires burning upon the royal hearth. Their term of service was thirty years and upon completion they had the option of returning to secular life. If their chastity was violated, they died a horrible death by being buried alive. Vesta's animal was the ass and her symbol the flame. A festival in honor of Vesta and known as the Vestalia was held on the ninth of June. Another Roman goddess, known as Fornax, the deity of ovens, is comparable to Vesta. A festival in honor of Fornax, known as Fornacalia, was celebrated in February. The oven is considered a mother symbol. For additional details, *see* Inari (Japan). The ancient Roman goddess Caca was replaced by Vesta. Vesta is etymologically connected with the Greek Hestia (q.v.). Compare Vesta to Agni (India), Fuji (Japan), Inari (Japan) and Pele (Hawaii). *See also* Silvanus.

Vetala (Hindu; India)
"Ghoul." An evil spirit who dwells in Smashana, Vetala is also known as the guardian of Deccan villages. In human form he is shown with his hands and feet turned backwards and hair that stands on end. He lives in a stone smeared with red paint

or in one of the stones in the prehistoric stone circles scattered around the hills. He haunts cemeteries and animates dead bodies. He is often portrayed as a mischievous demon who likes to play practical jokes. *See also* Durga; Shiva.

Vetanda (India)
"Like an Elephant." An epithet of Durga (q.v.).

Vialis (Roman) An epithet of Mercury (q.v.).

Viaroacocha (Inca) *see* Virococha.

Vibhishana (India)
A variant spelling of Vihishana, one of the eclectic members of the demon family of Visravas.

Vibhu (India) An alternate spelling for Ribhus (q.v.).

Vibhvan (India)
He is the artisan elf brother of Vaja and Ribhus, who collectively are known as the Ribhus (q.v.).

Vibishana (India) *see* Vihishana.

Vichitravirya (India)
He is the half-brother of the demigod poet, Vyasa (q.v.).

Victoria (Sabine, Roman)
Also known as: *Nike* (Greek), *Vacuna* (Sabine).
Originally Victoria was an early agricultural goddess who became the Sabine goddess of frivolity known as Vacuna. The Romans worshiped her as a goddess of war and victory and identified her with Bellona. *See also* Bellona; Nike.

Vid (Teutonic)
Vid is one of the eleven or twelve rivers springing from the well in Nifl-heim, known as Hvergelmir. The ice on the rivers created the clay giant Ymir. *See also* Elivagar.

Vidar *Vidor* (Norse; Teutonic)
Also known as: *Vidor, Vitharr*
"God of Few Words." God of peace. He is the son of Odin and the giant Grid. After Odin, he is the strongest of the gods. Vidar is the personification of the primeval forest. He lives in Landvidi, often shortened to Vidi. A tall, handsome man, he is depicted in his armor, carrying a broad-bladed sword and wearing a great iron or leather shoe. His shoe will be pushed against Fenrir the wolf's throat during the Twilight of the Gods, Ragnarok. *See also* Fenrir; Odin; Ragnarok; Vali.

Vidarbha (India) *see* Vidharba.

Vidforull (Teutonic) An epithet of Odin (q.v.).

Vidharba *Vidarbha* (India)
Vidharba is the father of Kesini, one of Sagara's wives. She is the mother of an emotionally disturbed son, Asamanjas, whom Sagara abandoned. *See also* Sagara.

Vidor (Scandinavian)
God of silence who walks on water and in the air. He is the same as the Norse Vidar (q.v.).

Vidura (India)
An incarnation of Dharma who as Vidura was the son of a maid and Vyasa. *See also* Dharma; Vyasa.

Vidyadevis (Jain; India) Goddesses of knowledge.

Vidyadhara *Bijadari, Wijadari* (Hindu; India)
The benevolent demigods Vidyadhara are shape changers who often appear as swan-maidens. They often take on human form and marry mortals. In the regions between earth and sky, they maintain their own kingdom. They supplanted the Yakshas and are analogues of the Melanesian swan maidens, the Vinmara. The Vidyadhara are not to be confused with the Vidyadhari, who are Hindu nymphs known to charm travelers. They live in ponds, on riverbanks and in woods. Swans are known as the preachers of gospels in the courts of kings. *See also* Kasyapa; Visvakarma; Yaksha.

Vidyadhari (India)
Wood and water nymphs. *See also* Vidyadhara.

Vigaya (India) "Victorious." *See also* Devi.

Vigona (San Cristobal)
Vigona is a variant spelling for the serpent-shaped creator spirits, Figonas.

Vigrid (Norse; Teutonic)
Also known as: *Battle Shaker.*
Vigrid is the plain in Asgard where the final battle known as Ragnarok, between the sons of Muspell and the forces of Surtr, will take place. *See also* Asgard; Muspells-heim; Ragnarok; Surtr.

Vihishana *Bibhishan, Vibishana, Vibhishana, Vihishana* (India)
He is the good-natured monster demon son of Visravas. His brothers are Kumbhakarna, Kuvera and Ravana. *See also* Kuvera; Nikasha; Rakshasas; Ravana; Vishravas.

Vii (Serbian) God of lightning.

Vijaya (India)
"The Victorious Guardian." He is the spouse of the goddess Ankusha (q.v.). *See also* Amrtakundali; Yaksha and Yakshini; Yamantaka.

Vijayasri (India) Goddess of victory.

Vikathikarala (India) "Fearful." An epithet of Durga (q.v.).

Vikrama (India) An epithet of Vishnu.

Vikramaditya (India) An epithet of Vishnu.

Vila (Slavic)
Also known as: *Russalka* (Russian).
Spirits of the forests, clouds and mountains. The eternally youthful Vila protects national heroes and are capable of calling forth whirlwinds, hailstorms and rain. They are long-haired and winged and are quite beautiful. *See also* Russalka.

Vile (Teutonic) *see* Vili.

Vili *Vile* (Norse; Teutonic)
First members of the race of Aesir. Vili is the brother of Odin and Ve. With his brothers, he helped create the first man and woman, Ask and Embla, from two trees. They were given senses, expression, and speech. Odin specifically gave them breath, Ve

www.ebook3000.com

gave them color and body temperature. Vili gave them understanding. From Ask and Embla all mortals were born. The brothers also created the celestial bodies from the sparks that flew out of Muspells-heim. Some say Vili later assimilated with Loki (q.v.). *See also* Ask; Audhumla; Bestla; Bor; Embla; Midgard; Muspells-heim; Odin; Ve; Ymir.

Vilin (Sumer)
The Vilin are malicious, attractive, female spirits who can change shape at will.

Vilva *Bel* (India)
The leaves of this sacred tree are used for the ceremonial worship of Shiva and Shakti. It is forbidden to break its branches. During the Durga-puga festival, Durga is invoked on a twig of this tree (q.v.). *See also* Durga; Tulasi.

Vinata (India)
"Mother of Eagles." She is the daughter of Daksha, the spouse of Kasyapa and the mother of Garuda. *See also* Daksha; Garuda; Kasyapa; Sumati.

Vinayaka (India)
"God of Difficulties." An epithet of Ganesha (q.v.). *See also* Uma.

Vindhyavali (Hindu; India)
She is the wife of Bali and the mother of Bana (also called Vairochi), the demon with a thousand arms, and a demon daughter, Putana, known for her poisonous breasts. *See also* Bali (B); Putana.

Vindhyavarini (India)
"Dwelling in the Vindhya Mountains." *See also* Devi.

Vindhyavasini (India) *see* Devi.

Vindsual (Teutonic)
Also known as: *Vindsval.*
Icy wind. He is the son of the icy wind, Vasud, and father of Winter, the enemy of Summer. *See also* Hraesvelgr; Winter.

Vindsval (Teutonic) *see* Vindsual.

Vingnir (Teutonic)
He is the foster father of Thor (q.v.). *See also* Vingthor.

Vingolf (Teutonic)
Vingolf is the sanctuary of Frigga and her goddesses. *See also* Gladsheim.

Vingthor (Teutonic)
Vingthor is the name Thor assumed from his foster father, Vingnir. *See also* Thor.

Vinmara (Melanesian) Swan-maidens. *See also* Vidyadhara.

Vipasyin (India) One of the seven Manushi-Buddhas (q.v.).

Virabhadra (India)
This monster of destruction, who is an emanation of Shiva, is a gigantic demon with a thousand eyes, arms and feet and enormous tusks. He killed Yajna while Daksha performed the first sacrifice. He also blinded Bhaga, knocked out Pushan's teeth, and beheaded Daksha. *See also* Bhaga; Daksha; Parvati; Shiva; Yajna.

Viracocha (Inca People; Peru) *see* Virococha.

Viraj (India)
Also known as: *Ambika, Purusha, Prajapati.*
According to some, Viraj is the child of Nari, the "Mother of the Earth," the primordial woman, who is the spouse of Nara. In other renditions, Purusha broke out of the golden cosmic egg after floating on the primeval waters for a thousand years. Fearful and lonely, the lord of the universe divided himself into a male and female half and created Ambika (also known as Viraj). *See also* Nari; Prajapati; Purusha; Sarasvati.

Virbius (Greek)
Also known as: *Auriga* ("The Charioteer" constellation), *Hippolytus.*
Hippolytus, the son of Theseus and Hippolyte, was named Virbius when he was deified after death. *See also* Hippolytus.

Virochana (India)
Virochana is the demon son of Prahalada, father of Bali and Kalanemi. *See also* Bali (B); Kalanemi; Prahalada.

Virococha *Uira-Cocha, Uiracocha, Viaracocha, Viracocha* (Inca People, Peru)
Also known as: *Arunaua, Choun, Con Ticci Viracocha, Con Ticci Viracocha Pachayachachic, Coniraya Viracocha, Illa Tici Viracocha* (Peru), *Manco Capac, Pachacamac, Taapac, Tarapaca, Thunupa, Ticci Viracocha, Tonapa, Tuapaca, Vicchaycamayoc, Viracocharapacha Yachipachan.*
"Sea Foam." Supreme god. God of law. Teacher of the world. He sculpted in stone all the races of men and his work can still be seen today. He is the god of water and growing things, the creator and spirit of life. Like Pachacamac, Viracocha antedated the Incas in Peru and was taken by them as one of their gods. He lived in the depths of Lake Titicaca. He is the creator of the sun, moon, and stars and was lord of thunder, lightning and rain. His father is the Sun and his brothers are Pachacamac and Manco Capac. His sister and wife is Mama Cocha, also a deity of the water. Children and animals were sacrificed to him. His servants or assistants are named Tonapa and Tarapaca. Somehow, Virococha, who is without flesh and bones, has a beard, wears the sun as his crown and carries a thunderbolt. He also has a reputation of being a swift runner. Sometimes, Virococha wanders the earth as a beggar. Some say Virococha's opponent was named Taguacipa. *See also* Bochica; Coniraya; Manco Capac; Pachacamac; Rimac; Thunupa.

Virtus (Roman) God of male courage.

Virudaka (India) *see* Virudhaka.

Virudhaka *Virudaka* (Buddhist; India)
Also known as: *hPhags-skyes-po* (Tibet), *P'ags-Skyes-po, Zocho-ten* (Japan).
A Lokapalas and one of the Four Great Kings, Virudhaka is the King of the South, and lord of the giant demons and gnomes known as the Kumbhandas. He holds a sword and an elephant head skin. His color is blue. For a description of the abode of the Four Great Kings, *see* Dhartarastra, for the Buddhist Universe, *see* Chakravala. *See also* Kuvera; Lokapalas; Naga Naga Knaya; Virupaksha; Yakshas; Zocho-ten.

Virupaksha (Buddhist; India)
Also known as: *Komoku-ten* (Japan), *Mig-mi-bzan* (Tibet).

A Lokapala, he is the Lord of the Nagas in the west. His color is red. He holds a serpent, jewel and a receptacle. *See also* Dhartarastra; Komoku-ten; Lokapalas; Naga Naga Knaya; Sesha; Virudhaka.

Vis (Inca)
Also known as: *Earth.*
Harvest god. *See also* Ni; Si.

Vishapa (Armenian)
"Whose Saliva Is Poison." Vishap is an epithet of the evil dragon, Azi Dahaka, who is determined to wipe mortals from the earth. *See also* Azi Dahaka.

Vishnu *Primeval Being, Lord of the Universe, Lord Creator and Generator of All, Lord of Sacred Wisdom, Lord of Waters, World Maintainer.* (Brahmanic, Hindu, Jain, Vaishnava, Vedic; India)
Also known as: *Achyuta, Aditi, Ananta* (Eternal), *Ananta-Shayana* (Sleeping on Ananta), *Badari* (Lord of Badari), *Buddha* (his ninth avatar), *Hara, Hari* (The Sun), *Hayagriva, Jala-Shayin* (Sleeping on the Water), *Janardana, Jagannath, Kalki, Kalkin* (his tenth and future avatar), *Kesava, Krishna* (his eighth avatar), *Kurma* (his second avatar as a tortoise), *Manmatha, Madhava, Matsya* (his first avatar as a fish), *Mohini* (feminine incarnation), *Nara-Simbha,* (his fourth avatar as a Man-Lion), *Narasimba, Narasimbha, Narasinha, Narayana* (Protector of Men), *Parasu-Rama, Parashur Rama* (his sixth avatar as Rama with an ax), *Parasurama, Phra Narai* (Siam), *Phra Noreai-Narayana* (Cambodia), *Rama, Rama-candra, Rama-Chandra,* (his seventh avatar as the gentle hero), *Ramachandra, Surya-Narayana* (Moving in the Waters), *Vamana* (Vishnu's fifth avatar as a dwarf), *Varaha, Varaha-Avatara, Varahavatar,* (his third avatar as a boar), *Vikrama, Vikramaditya, Yajnesvara.*

Vishnu is variously known as the god of blue water, a sun god, a god of love, and later as a protector of worlds and conqueror of demons. In the Vedic period, Vishnu was a minor deity who was occasionally associated with Indra. In the *Rig-Veda,* a hymn to Vishnu celebrates his three strides. Two steps are visible to mortals and the third step is beyond sight and the bird's flight. With these steps, he brought into being the earth, the air and heaven. He is called the "All-pervader," the "Wide-stepper" and the preserver. This feat is also performed by Vamana who is the fifth avatar of Vishnu (in the form of a dwarf) in Brahmanic mythology. The Vedics believed in personal immortality. The good went to heaven or the world of Vishnu and others to the domain of Yama (although Yama was also thought of as the ruler of all departed spirits). During the Brahmanic period Vishnu rose in status and became the second member of the Hindu Trimurti (triad) along with Brahma the Creator and Shiva the Destroyer. In this representation, he is self-existent and embodies all good and mercy. His numerous avatars are enacted in order to overcome evil in the world and each avatar carries its own tale. He appears in human or supernatural form. Vishnu also appears in amsavataras or partial incarnations. This method permits him to invest a portion of himself to two or more men at once, with varying degrees of power. In his non-avatar form, he was childless and had a divided male-female essence. The male essence descended into Rama and Krishna and the female essence into Sita and Radha. When Vishnu is in an avatar form, his wife, the beautiful goddess Lakshmi, often appears in another form with the same or another name. Vishnu is the husband or possible son of Aditi. His father is the sun god Vaivasvata. In the Bengali tradition, the Great Mother Devi as an avatar named Kali is his mother. He is also named as the husband of the earth goddess Bhu (also spelled Bhumi and Bhumidevi). Vishnu and Lakshmi reside in his heaven named Vaikuntha, an abode made of gold and precious stones, where he watches over the universe. In another rendition, Vishnu was married to Sarasvati. Their union was so unhappy that Vishnu suggested that she marry Brahma, which she attempted to do. The goddess of the Ganges, Ganga, was also his wife, Shiva's wife, and the spouse of several other deities. Manasa, also known as Manasa-devi was the wife of Vishnu and Shiva. Another wife was Sinivali, the goddess of fecundity, easy birth and goddess of the day of the new moon. Vishnu absorbed all the sun gods into himself as Surya-Narayana. In an attempt to obtain perfection, the other deities offered a sacrifice. Vishnu, who ended the ritual before the other gods, became the most powerful and the most perfect. This displeased the gods, so they decided to murder him. They approached but could not attack, for he was upright on his feet, his head resting on his bow. It was decided that an army of ants would be employed to carry out the plan. The ants gnawed on the string of his bow until it sprang back and decapitated Vishnu. The great god's power was seized by his murderers and divided into three parts, which became the three principal phases of sacrifice. Followers of Vishnu are known as Vaishnavas. Ten Avatars of Vishnu according to the *Bhagavad Gita*: **1.** Matsya or Fish. **2.** Kurma or Tortoise. **3.** Varaha (Varahavatar) or Boar. **4.** Nara-Simbha or Man-Lion. **5.** Vamana or Dwarf. **6.** Parashur Rama. **7.** Rama, also called Ramachandra, the gentle Rama hero of the *Ramayana.* **8.** Krishna. **9.** Buddha. **10.** Kalki, his future avatar with a white horse head. The first five avatars are mythological, the next three heroic, the ninth religious, the tenth to come. In the *Bhagavata Purana,* twenty-two avatars are mentioned and it is stated that the avatars of Vishnu are innumerable. Rama (also known as Ramachandra) and Krishna are Vishnu's two most popular aspects. He is often represented holding a mace, conch shell (his traditional emblem), wheel or sun disk (chakra), and a Padma (lotus) in each of his four hands, and with blue skin, and clothed in yellow. On his breast he wears the Kaustubha jewel, symbolizing the sun and the calf mark (vatsa). His disk was forged by Visvakarma from the shavings of the sun god Surya. In later times, he is shown riding the half-man, half-bird, Garuda. His other vehicle is an eight-wheeled chariot (symbolizing the eight directions). It is drawn by demons (representing blazing heat). He is also depicted reclining on a couch formed by the seven-headed serpent Sesha, whose length is endless. His seven raised heads provide shade. Once Vishnu appeared in his "real" form to Arjuna, one of the Pandava brothers whom Vishnu as Parashur Rama instructed in the art of military skills. This "real" form depicted hundreds of bodies, heads and arms and was said to be a terrifying sight. In the Vedic tradition, Vishnu is the manifestation of solar energy. His three steps are manifestations of light in the form of the sun, lightning and fire. They can also be interpreted as the three phases of the sun: sunrise, noon and sunset. His divine sword is named Nandaka and his bow Sarnga. Another of

www.ebook3000.com

Vishnu's symbols is the knot, which symbolizes life without beginning and without end. In the Vedic tradition there are three earths corresponding to three heavens. One earth, the fourth, is called Bhumi. She is described by some as the mother of Mars. Later, in the Tantric and Puranic periods of Hinduism (about C.E. 500–1500), Vishnu is identified with the lion. The pipal tree, a type of fig tree, is regarded as a representation of Vishnu. Throbbing pain in eyes and arms and also nightmares can be removed by sprinkling the sacred tree with water while reciting a prayer. In the Hindu tradition, in the Vaikuntha heaven, Vishnu is seated on white lotus flowers. His wife Lakshmi is seated to his right. Another common depiction is Vishnu reclining in a state of deep meditation on Shesha, who has one thousand cobra heads. A lotus rises up from his navel which is partly covered by the world-ocean. Brahma, also in deep meditation, is seated on the lotus. In the *Bhagavad Gita*, Yajna or sacrifice is said to be Vishnu. As Vishnu-Narayana, he is associated with the primordial waters and represents the creative principle from which universes emerge and into which they are reassimilated. The setting sun represents Vishnu dying. As Manmatha, Vishnu is the god of love who carries bows and arrows and is associated with Priti and Rati. As Hayagriva, Vishnu is depicted with a horse's head and is known as the god of learning. Lakshmi, who was originally worshiped through the sacred fire, symbolizes the abundance that comes through fire. Lakshmi and Bhumidevi are always represented with a blue or pink lotus in their hands. Vishnu is the central deity of worship in the Vaishnava tradition. Vishnu shares characteristics with Indra and Prajapati (q.v.). Vishnu is associated with Indra in relation to Vritra (q.v.). *See* Vivasvat, who is thought by some to be the forerunner of Vishnu. The sun god Savitri closely resembles Vishnu (q.v.). Compare to the Greek deities, Apollo and Zeus, the Egyptian Horus and the Norse Thor. *See* Pandora for a parallel myth. *See* Narayana who is said to be an aspect of Vishnu. The goddess Bhumi closely corresponds to Prithivi and some feel they are two forms of the same goddess. *See also* Aditi; Adityas; Agastya; Agni; Ahalya; Amrita; Andhaka; Arjuna; Asura; Badari; Bala-Rama; Bali (B); Bhumi; Brahma; Brighus; Buddha; Deva (A); Devaki; Devi; Dharti Mai (also known as Bhu Devi); Durga; Gandharvas; Ganesha; Ganga; Garuda; Gramadeveta; Hansa; Hara; Hiranya-Kasipu (regarding Hiranyaksha) Rama; Jagannath; Kali; Kaliyuga; Kalki; Kama (A); Kasyapa; Krishna; Kurma; Kuvera; Lakshmi; Manjusri (Buddhist); Manu; Mari; Matsya; Nagas and Nagis; Nara-Simha; Narayana (A); Narayana (B); Narayana (D); Parashur Rama; Patala; Prahlada; Prithivi; Priti; Rahu; Rati; Ravana; Sagara; Salagramas (stone representing Vishnu); Saranyu; Sarasvati; Sesha; Shiva; Siddhas; Sita (for details about Vaivasvata); Surya; Tulasi (sacred plant); Vaikuntha; Vamana; Varaha; Vasuki; Visvakarma; Yajna; Yama.

Vishvabhu (India) *see* Manushi-Buddhas.

Vishvakarman (India) *see* Visvakarma.

Vishvanatha (India) "Lord of All." *See also* Shiva.

Visnanatha (India)
Visnanatha is Shiva's name as the presiding deity of the sacred city of Benares.

Visnu (India) *see* Vishnu.

Vispala (India)
Vispala is one of the patients of the healing twin deities, known as the Asvins. The brothers fitted Vispala with an iron leg. *See also* Asvins.

Visravas (India)
The son of Pulastya, father of Kuvera with Ilavida and with a Rakshasi, three sons, Ravana, Kumbhakarna and Vibishana. *See also* Kuvera; Ravana.

Visva-Karma (India) *see* Visvakarma.

Visva-Krit (India) *see* Visvakarma.

Visvakarma *Tvashtri, Vishvakarman, Visva-Karma, Visva-Krit, Viswakarman* (Buddhist, Hindu, Vedic; India)
Originally, the name Visvakarma was an epithet used for gods of great power, such as Indra or Surya. In early times, Visvakarma was known as Tvashtri. Later, known as Visvakarma, he was the divine architect and divine smith for gods and demons. Beyond the understanding of mortals, he produced heavens and earths. In the post–Vedic period he was known as the divine architect. Visvakarma created the universe from an unknown tree and was responsible for the maintenance of his creation. He built the paradisiacal city of Amaravati in Swarga, and Vaijayanta, Indra's palace on Mount Meru. Krishna employed him to design his divine abode Dwarka in one night, and he built the dwelling place for the Rakshasas, Sri Lanka. He was also the architect for the assembly hall of Yudhisthira, *and* Chandrapura, city of the king of the Vidyadharas. Indraprastha, the palace of the Pandavas, was also his creation. He was a Rishi, one of the seven (some say fourteen) sages born from Brahma's brain. He designed the bridge to Lanka for Rama (one of the three avatars of Vishnu), and generated the ape Nala who acted as chief engineer and supervisor for the construction crew of monkeys who built the bridge. Indra's fabulous horses were produced by Visvakarma and he constructed the chariots of the gods. When his daughter Sanja was unable to stand the dazzling brightness of her mate, Surya the sun, he shaved off one eighth of his rays. With the shavings Visvakarma gave Nala material for his work on the bridge and forged metal to make weapons for the gods. He also forged Shiva's trident and Karttikeya's spear, and Vishnu's discus. Visvakarma is said to be all-seeing, with faces, eyes and arms on all sides. In the middle provinces of India, festivals were held four times yearly in Visvakarma's honor. During these periods, their book on architecture and their tools of the trade are revered. Visvakarma is also honored for introducing sacrifice and then giving the example by sacrificing himself. Visvakarma is sometimes identified with Indra, Tvashtri and Brahma and sometimes confused with Tvashtri. The confusion may stem from early times when Visvakarma was known as Tvashtri. Visvakarma is also confused with Vivasvat and is identified with Prajapati. *See also* Amaravati; Brahma; Chakravala the Buddhist Universe; Indra; Jagannath; Karttikeya; Krishna; Kuvera; Meru mountain; Pandavas; Rakshasas; Rama; Rishi; Sanja; Shiva; Surya; Swarga; Tvashtri; Vidyadhara; Vishnu; Vivasvat; Yadavas.

Visvamitra (India)
He is a Rishi. The names and numbers of the Rishis varies.

words and deeds. At death, he greets mortals and leads them to the highest heaven. Vohu Manah also protects domestic animals. He is particularly opposed to the demon Aka Manah (Vile Thoughts or Discord), and the demons Aeshma (Wrath), and Az (Wrong Mindedness). When he was thirty years old, Zarathustra Spitama, known as Zoroaster, the founder of Zoroastrianism, had a vision of Vohu Manah. He appeared to him as an angel nine times the size of a man, and proclaimed that Zoroaster would become the prophet of Ahura Mazda, the one true god. *See also* Ahura Mazda; Aka Manah; Ameshas Spenta; Asha Vahista; Az; Daevas; Haoma; Kshasthra Vairya; Vayu; Zoroaster.

Vohu Mano (Persia) *see* Vohu Manah.

Voice of the Void (Bambara People, Africa)

Creator spirits. They are primordial spirits who created everything. Pemba created women; Faro, the water. There was constant strife between Pemba, who was good, and his wife, Musso Koroni, who was evil. Faro gave mortals agriculture. *See also* Musso Koroni; Pemba.

Vol *Vola, Volla* (Norse; Teutonic) *see* Fulla.

Voland (Teutonic) *see* Valland; Volund.

Volcano Woman (North Pacific Coast People, North America)

Volcano Woman is another name for the mountain spirit Dzelarhons.

Voli (Teutonic) *see* Vali.

Volkun (Serbian, Slavic)

Another name for the werewolf, Vlkodlak.

Volla (Norse; Teutonic) *see* Vol.

Volos (Slavic)

Also known as: *Veles, Vyelyes.*

Volos is the god of cattle and commerce, the protector of the herds and flocks. The Christians later absorbed him into their religion as St. Blaise, or St. Vlas. Because he was worshiped by warriors he might have been considered a god of war at one time. The only physical description of him is that he had curly hair. He is identified with Pyerun (q.v.).

Volsung (Norse; Teutonic)

Volsung is the son of Rerir and one of the grandsons of Sigi, Odin's son. His mate is Liod. They had ten sons (Sigmund is the eldest) and a daughter, Signy. Signy's husband Siggeir murdered Volsung. The name Volsung is used for all members of Volsung's family. *See also* Odin; Sigmund.

Volsunga Saga, The (Teutonic; Norse)

The Volsunga Saga originated in 13th century Iceland. They are the stories of the gods, goddesses, heroes of the Volsungs. The main Volsung character is Sigurd, son of Sigmund and Hiordis. Others in the Volsunga Saga cast are Bryhild, Hiordis, Gudrun and Gunnar. *See also* Sigmund; Volsung.

Voltan (Maya) God of Earth.

Voltumna (Etruscan) Mother goddess.

Volturnus (Roman) God of the river Tiber.

Volund *Foland, Phaland, Valland, Velint, Voland,* (Norse; Teutonic)

Also known as: *Wayland, Weland, Wieland, Woland.*

Deity of smiths. The brothers Egil, Slagfinn and Volund lived with three Valkyries: Olrun, Alvit, and Svanhvit. After nine years the Valkyries left. Egil and Slagfinn followed and were lost. Voland stayed behind and, being a smith, copied the ring Alvit had given him. He made seven hundred duplicate rings, one of which King Nidud (who captured Volund) gave to his daughter Bodvild. In a clever ruse Volund escaped after killing all of Nidud's family. Volund went to Alfheim where he manufactured suits of impenetrable armor, the swords Balmung and Joyeuse, and was also said to have fashioned Miming for his son Heime.

Volundr (Teutonic) *see* Weland.

Voluptas (Roman)

Voluptas is the goddess of sexual delight. She is the daughter of Cupid and Psyche.

Volva, The (Teutonic)

The Volva is a name used for the evil goddess Gullveig.

Vor (Norse; Teutonic)

Also known as: *Frigga* (possibly), Var, Vara.

"Vow." Goddess of faith. Vor, an attendant of Frigga, is a goddess from whom nothing can be hidden. She is a goddess of marriage and contracts. She punishes those who do not keep their vows. *See also* Frigga.

Vortumnus (Roman) *see* Vertimnus.

Votan (A) (Teutonic) *see* Odin.

Votan (B) (Yucatan, Mayan)

Also known as: *Heart of the People.*

Culture hero, first man, or god. Votan descended from Imos (a genie or guardian of the days), and traveled on subterranean roads going beneath the Earth and ending at the roots of the sky. His successor was Canam-Lum (Serpent of the Earth). Votan appears to be the same as Quetzalcoatl, or similar. He is associated with Palenque, Zamna, Itzamna and Kukulcan.

Vourukasha (A) (Indo-Iranian and Hindu)

The sea godfather of Apam Napat ("Grandson of the Waters"), who was born on a cloud and who loved Anahita (q.v.).

Vourukasha (B) (Persian)

Vourukasha is the boundless ocean, so wide that it contains a thousand lakes, and the springs of the water goddess Anahita. Rain created by the god Tishtrya formed the waters of Vourukasha. From it the world is supplied with water. In the midst of Vourukasha stands Gaokerna the sacred plant and The Tree of Many Seeds. After the cosmic ocean was created, twenty-three seas followed; three great seas, and twenty smaller seas. Two rivers ran through the earth, one from north to west and the other from north to east. They ran over the edge of the world and their waters mingled with Vourukasha. The rains caused the earth to split into seven pieces. One half of the land mass is known as Khwanirath, and the surrounding six portions are the Keshvars. Passage from one portion to the other was impossible except by riding on the back of Srishok, or Hadhayos, the heavenly bull. Vourukasha is watched over by the fantastic half-

www.ebook3000.com

2. Pull Tan Tien: Smile to your Tan Tien. Keep smiling to your Tan Tien.
3. Push to both sides. Expand all the way, smiling and touching the universe.

   Push/Pull: touching, touching the universe drawing the Chi smile energy into you from both sides.

   Do 3-6 times.



Fig. 3.38 *Pull: Just feel about your Tan Tien.*

Direction Above

Turn your palms up to the universe. Scoop up the Chi. Pour the Chi over your crown, and touch your crown. Project the Chi all the way down to the perineum and down through the earth to the universe below. Tan Tien and universe; always feel your Tan Tien spiraling, heart spiraling, crown spiraling and the universe around you spiraling.



Fig. 3.39 A. *Raise the hands above the crown and feel it extend up to heaven.*
B. *Feel that the hands are big and long and that the bones are hollow. Fill and pack the bones with Chi.*

Visvamitra is listed on the oldest list of seven rishis which includes Atri, Bharadvaja, Gautama, Jamadagni, Kasyapa and Vasistha. Together, the seven Rishis form the constellation of the Great Bear. *See also* Rishi.

Visvapani (Buddhist; India) A Dhyanibodhisattva (q.v.).

Visvapani is one of the five Buddhist creators of the universe. The other four are Avalokitesvara, Ratnapani, Samantabhadra, Vajrapani. *See also* Dhyani Buddhas; Samantabhadra; Vajrapani.

Visvarupa (India)

Visvarupa is the serpent son of Tvashtri. He is associated with Trisiras, the three-headed water god. *See also* Ahi; Trisiras; Tvashtri.

Visvavasu (India) *see* Vivasvat.

Viswakarman (India) *see* Visvakarma.

Vitharr (Teutonic) *see* Vidar.

Vivanghat (Persian) *see* Vivanghvant.

Vivanghvant *Vivanghat* (Persian)

"The Vivifier." *See also* Haoma; Hoshang; Jamshid.

Vivasvan (India) *see* Martanda; Vivasvat.

Vivasvant (India)

"The Bright One." *See also* Martanda; Vivasvat.

Vivasvat *Visvavasu, Vivasvan, Vivasvant* (Vedic; India)

Also known as: *Martanda, Marttanda, Savita, Surya.*

Vivasvat, also known as Martanda, emerged from an egg as an unformed lump. His mother, the "Mother of the Worlds," Aditi, took one look at him and hurled him into the heavens. The divine artificer Tvashtri molded the lump into Vivasvat the sun god. The excessive material fell to earth and became elephants. Vivasvat, an Aditya, was the eighth son born to Aditi. An extravagant wedding took place when Vivasvat married Saranyu, the goddess of morning light, who was the daughter of Tvashtri. The extensive guest list included the whole world and every deity. Eventually, the couple became the parents of twins, a son Yama and a daughter Yami who became the parents of all mortals. Saranyu found it difficult staying with Vivasvat because of his brightness. She assumed the shape of a mare and disappeared. Vadava (also spelled Vadaba) the mare goddess was formed in her likeness to take her place. She bore the twin healing deities, known as the Asvins. When Vivasvat realized that a clone of his wife was with him, he assumed the form of a horse and galloped off in search of his original bride. He found her and they reunited. In later times, Vivasvat and Saranyu became aspects of the chief sun god, Surya. Often the mythology of Vivasvat is attributed to Surya, as in time Surya absorbed Vivasvat and Savitri. Vivasvat crosses the sky daily, in a chariot drawn by seven red or white horses. Vivasvat's son Vaivasvata is the seventh and present Manu of the earth. *See* Manu; Matsya. For Vivasvat's siblings, *see* Aditi. *See also* Adityas; Asvins; Kasyapa; Martanda; Mitra; Saranyu; Surya; Tvashtri; Visvakarma; Yama; Yami.

Vivian (Arthurian) *see* Vivien.

Vivien *Vivian, Vivienne* (Arthurian)

Also known as: *Anatis, Dame du Lac, Ellen Douglas, Lady of the Lake, Nimue, Niniane, Rhiannon* (Possibly).

Lake goddess. Water nymph. Sorceress. Vivian, an enchantress, accorded the Excalibur sword to King Arthur. She was the mistress of Merlin the magician and prophet, and lived in a palace in the middle of a magic lake. In early times, as Niniane (in the writing of Malory), she imprisoned the same Merlin in a rock or a tree. In other traditions, Vivien is the same as Nimue, the daughter of Dinas, who seduced the older Merlin under the pretext of wanting to know how to build a tower out of air. He succumbed to her charms at a high price. He was imprisoned in her edifice, a walless tower, and died. Vivien as Ellen Douglas is from a poem by Scott and in Cabel's Jurgen she is called Anatis. It is thought that Vivien is an aspect of Rhiannon, the Cymric goddess. Vivien and the aspects of Vivien are the goddess personified. Her emblems are the sword and fish. *See also* Arthur; Rhiannon.

Vivienne (Arthurian) *see* Vivien.

Vizetot (Nicaragua)

God of famine. Vizetot is one of the creation deities who are ruled by Tamagostad and Zipaltonal. He is associated with Ecalchot, Ciaga, Quiateot, Misca, and Chiquinau.

Vjofn (Teutonic)

Goddess of love and peace. She is an attendant of Frigga. Her job is to maintain peace among mortals and to reconcile quarrels.

Vlkodlak *Vrkolak, Vukodlak* (Serbian, Slavic)

Also known as: *Volkum.*

Vlkodlak is a Slavic man who can turn into a werewolf. In Serbia, Vlkodlak is the spirit of the hungry wolf who causes eclipses of the sun and moon.

Voden (German) *see* Odin.

Vodu (Dahomey, Fon People, Africa)

Supreme beings. Masters of the divisions of nature. Sagbata, the earth god; Xevioso, the thunder god; Gun, the god of iron; Avlekete or Agbe, god of the sea. They are associated with Legba (q.v.) Some versions claim the vodu is the power, the force of a cult. *See also* Olodumare; Xevioso.

Vodyanoi *Vodyany* (Slavic, Russian)

Also known as: *Vodyany-Ye.*

"Grandfather." Water sprites. These immortal shape changers are very dangerous. They lure people to the water and drag them in to become their slaves. They keep their souls and allow the bodies to float to the top. Some of the Vodyanoi have a human face, paws in place of hands, long horns, eyes that glow and large toes. Others are men with red eyes, very long noses and black skin. A diverse group, other Vodyanoi are old men with green hair and beards. They can be depicted as a fish or a tree trunk with wings. The Vodyanoi can be propitiated by sacrificing a black pig. *See also* Kul.

Vodyanoy (Finnish) *see* Kul; Vodyanoi.

Vodyany-Ye (Slavic) *see* Vodyanoi.

Vohu Mana (Persia) *see* Vohu Manah.

Vohu Manah *Vohu Mana, Vohu Mano* (Zoroastrian; Persia)

Also known as: *Bahman* (Pahlavi dialect).

An Amesha Spentas, he is the advisor of Ahura Mazda and sits at his right hand. He keeps a daily record of men's thoughts, man, half-ox Gopatshah. *See also* Alburz (Mount); Anahita; Angra Mainyu; Gandarewa; Khara (A); Simburgh; Thrita; Tishtrya; Tree of Many Seeds.

Vretil (Hebrew) *see* Nabu.

Vrihaspati (India) *see* Tara.

Vrikdevatas (India) *see* Devis.

Vrikodara (India) "Wolf's Belly." *See also* Bhima (A).

Vrikshakas (India) *see* Apsarases.

Vrinda (India) *see* Asuras.

Vrishakapayi (India) Wife of Vrishakapi (q.v.).

Vrishakapi (India) The Ape. *See also* Hanuman; Indrani.

Vrita *Vrtra* (The Covering); (Hindu, Vedic; India)
Vrita the archdemon, serpent of darkness and draught, is an Asura. He is the offspring of the goddess Danu and is called a Danava. A Danava is a descendant of Danu or something having the character of Danu. Danavas became known as subordinates of Vrita. In later times, Danavas were called Rakshas and sometimes Vritas or Daitya or Adityas. The Adityas represent good and are hostile to the Danavas. In a variation of Vrita's origins, it is said that he was manifested by the father of a youth killed by Indra. The young man had three heads, one for studying, one for eating and one for watching. Indra was extremely jealous of the peaceful, studious youth. He tried unsuccessfully to distract him from his meditations and studies. Finally, Indra was so enraged that he hurled a thunderbolt at him and cut off his heads. Vita, a huge dragon or serpent, emerged and swallowed Indra's cows which were the rain clouds. He also blocked the seven great rivers of India with his ninety-nine coils or by lapping up the water. He terrified all the deities except Indra. With the advice and possible aid of Vishnu, or some say, Krishna, and enough soma to fortify him, he set out to slay the dragon. His method, either drowning him in a great mass of foam that emanated from his belly or attacking him with his magic thunderbolt, was successful. The hideous corpse frightened the courageous god and he leapt over the rivers that sprang free when Vrita's coils were removed. Upon Vrita's belly, his mother, who was slain in the battle, lay dead. His brave action caught the attention of the gods, and from that time, they were at Indra's side whenever he needed assistance. Vrita's name means the "Enemy" or the "Enveloper." There are variations of this myth, and Indra always emerges the victor. Vrita is depicted as strong and wily. Darkness symbolizes the pain and misery caused by drought. The seven great rivers are said by some to be the seven planets. Danu means "bondage" and Vrita, as a Danava and the offspring of Danu, therefore personifies restraint. Vrita is comparable to the celestial Egyptian snake, Ahi. Compare Vrita to Typhon (Greek). *See also* Adityas; Agastya; Asuras; Drukh; Indra; Maruts; Nagas and Nagis; Rakshasas; Sesha; Shiva; Soma; Tvashtri; Varuna; Vedas (The).

Vritra (India) *see* Vrita.

Vritrahan *Vritrahana, Vrtrahanna* (India)
Slayer of Vrita. *See also* Indra.

Vritrahana (India) *see* Vritrahan.

Vrkolak (Serbian, Slavic) *see* Vlkodlak.

Vrou-elde (Germanic) *see* Bertha.

Vrtra (India) *see* Vrita.

Vrtrahanna (India) *see* Vritrahan.

Vukodlak (Serbian, Slavic) *see* Vlkodlak.

Vukub-Ahpu (Maya) *see* Hunhun-Ahpu.

Vukub-Cakix (Maya People, Yucatan)
Sun and Moon deity. According to the "Popul Vuh," Vukub-Cakix was the first of the giants of one of the ages of the earth. He had two sons, Zipacna and Cabrakan. Vukub-Cakix owned a fruit tree which was for his food. The two brothers Hunahpu and Xbalanque hid in the branches and shot this giant with a poisoned arrow. The giant tore off one of Hunahpu's arms, which his wife, Chimalmat, proceeded to roast on a spit. Disguising themselves as physicians the two brothers managed to convince Vukub-Cakix that his teeth were causing him trouble and substituted maize for the emeralds that were his real teeth. The transplant robbed the giant of his power and soon killed him. After recovering, both brothers went on to their next adventures where they killed Zipacna and Cabrakan. *See also* Hunahpu; Xbalanque; Xibalba.

Vukubcame *Vukub-Came* (Quiche People, Guatemala)
One of the Lords of the Underworld. *See also* Hun-cane; Xibalba.

Vulcan *Vulcanus* (Roman)
Also known as: *Hephaistos* (Greek), *Mulciber the Smelter.*
God of Fire. God of metal working. Patron of iron workers. Vulcan might have been the husband of Maia (Maiestas). With Medusa, he had two children, Caca, the goddess of latrines, and Cacus, the fire-breathing giant. His festival, Vulcania, was held outside of the city on August 23. Small fish were thrown into fire to assuage him. He is similar to, and identified with, the Greek god Hephaistos. Compare to the Vedic deity Tvastri and the Celtic Goibniu. *See also* Caca; Hephaistos; Maia; Medusa.

Vulcania (Roman)
Festivals held in honor of Vulcan, celebrated August 23.

Vulcanus (Roman) *see* Vulcan.

Vultures (Greek)
They are the children of Typhon and Echidna. *See also* Typhon (A).

Vushkapariks (Armenia)
The Vushkapariks are spirits similar to the Pairikas (q.v.). *See also* Hambaris.

Vuub-Hunapu (Guatelmala) *see* Hun-cane.

Vyaghrini (Nepal) Female guardian demon.

Vyasa (Hindu; India)
Also known as: *Krishna Dwaipayana, Vedavyasa.*
Vyasa, the demigod son of the sage Parashara and the water nymph Satyavati, lived as a hermit in the forest. He became the poet of some of the books of the *Mahabharata.* His half-broth-

www.ebook3000.com

ers by King Shantanu of Hastinapura, Chitrangada and Vichitravirya, died leaving their widows childless. Satyavati asked Vyasa to impregnate his sisters-in-law, Ambika and Ambalika. He agreed, but they were not overjoyed when they saw his appearance. They were expecting the handsome Bhishma, not a wild-looking man with long, matted hair. Ambika could not bear to open her eyes, so her son Dhritarashtra was born blind. Ambalika was so frightened that the color drained from her face. Her son was the pale Pandu. These births were not deemed successful by Satyavati and she insisted that Ambika and Vyasa make another attempt. The thought horrified Ambika and although she consented, she substituted her maid as Vyasa's partner. The maid gave birth to Vidura who was an incarnation of Dharma. *See also* Bhishma; Brihaspati; Dhritarashtra; Ganesha; Pandavas; Parashara; Satyavati.

Vyelyes (Slavic) *see* Volos.

W

Wa (China)
Little is known about the divine woman, Wa, who, according to Chinese writings in the first century C.E., "produced ten thousand beings through metamorphosis."

Wa Cinaci (Arawak People, South America) *see* Ifilici Wacinaci.

Wa Murreta Kwonci (Arawak People, South America) *see* Ifilici Wacinaci.

Wabun (North America) *see* Manibozho.

Wadd (Arabic)
"The Loving." Wadd is a name used for the twin sons of El, Shahar, the god of dawn, and Shalim, the god of sunset. *See also* Shahar.

Wadjet (Egypt)
"Green One." Wadjet is the Goddess of Buto and the national goddess of Lower Egypt. She symbolizes the forces of growth. She is a fire-spitting serpent who is also known as the "Eye of Re." Wadjet is the most important serpent-deity. The uraeus, her sacred animal, is said to have wound herself around the king's diadem. Wadjet's counterpart is Nekhbet of Upper Egypt. She is sometimes seen with a leonine head topped by the solar disc and uraeus. *See also* Buto (Greek); Isis; Nekhbet; Uatchet.

Wagilag Sisters (Australia) *see* Wawalag Sisters.

Wahieroa (Oceanic)
Wahieroa is the mortal son of Tawhaki and a goddess. His grandparents are Hema and a goddess. His paternal uncle is Kariki. Wahieroa and his wife are the parents of Rata. Like his father and grandfather, Wahieroa was captured and killed (in his case, by a flying monster, named Matu'u-ta'u-ta'uo, although in some stories, it is a shark named Matuku tago-tago who bites off his head). As in generations past, Rata set out to avenge his father's death. His adventures comprise an exciting and enduring saga. Finally, Rata encounters Matuku, the shark. He rips open the shark's belly and finds his father's head. Other body parts were found in the stomachs of Matuku's monster associates. Rata went on to rescue his mother, Puna, and to restore her eyesight. Mother, son and father's body parts went home together. *See also* Kariki; Rata; Tawhaki.

Wailing River (Greek)
Wailing River is a name used for the Cocytus river. As a river, the Cocytus is a tributary of the River of Sadness, the Acheron in Epirus. The souls of the dead not buried wander along the banks of the Cocytus where they will wail and groan for one hundred years after death. For the names of other rivers in the Underworld, *see* Cocytus. *See also* Charon.

Wainamoinen (Finland) *see* Vainomoinen.

Waka (Galla People, Ethiopia, Africa)
Waka will bring the needed rain, if the right devotee asks.

Waka-hiru-me *Wakahirume* (Japan)
The sun goddess, Amaterasu, thought highly of her weaving maiden, Waka-hiru-me. When Amaterasu's brother, the volatile Susanowo, threw a skinned colt through the roof of the "Heavenly Weaving Wall," Waka-hiru-me was so frightened that she fell onto her shuttle and punctured her vagina. Her death infuriated the sun goddess, who sealed herself into the cave known as Ame-no-Iwato (Sky-Rock-Cave) and withdrew the light of the world. *See also* Amaterasu; Amatsu-Mikaboshi.

Waka-mi-ke-nu-no-mikoto (Japan)
Jimmu Tenno, the first emperor and founder of the Imperial Line of Japan, was born Kama-Yamato-Iware-Biko but was also called Waka-mi-ke-nu-no-mikoto. He acquired the name Jimmu Tenno posthumously. *See also* Jimmu Tenno.

Waka-sana-me-no-kami (Japan)
A name for the goddess of food, Ukemochi (q.v.).

Waka-uke-nomi (Japan)
"Young woman with food." Another name for the goddess of food, Ukemochi (q.v.).

Wakahirume (Japan) *see* Waka-hiru-me.

Wakan (Oglala People, North America)
Another name for the supreme spirit, Kitshi Manito.

Wakan-Tanka (Dakota, Sioux People, North America)
Assembly of gods. The Wakan-Tanka is a collective unity of the gods which has tremendous power. It is similar to a gathering of world leaders, but far more effective. It is necessary to be of the right mind before calling on these gods. To quote a priest of the Dakotas, "It is not fitting that a man should suddenly go out and make a request of Wakan-Tanka." *See also* Kitshi Manito.

Wakanda (North American) *see* Wakonda.

Wakataka (Sioux People, North America)
Wakataka, the creator god, made the earth, the parents of the Sioux people, all fur animals that swim and all animals that hunt for food.

Wakcexi *Waktcexi* (Algonquin, Chippewa, Cree, Nascopie People, North America)
A water monster.

Wakea (Polynesia) *see* Vari (A).

Wakonda *Wakanda* (Osage, Omaha, Sioux and Dakota Indian, North America)
Wakonda is the power above; a supreme invisible being who created everything. Among the Nebraska Omaha People, Wakanda stands for the mysterious life power embodied in all natural forces and creatures, as well as in man. Compare to Tirawa of the Pawnee Indians. *See also* Kitshi Manito.

Wakonyingo (Pygmy or Wachaga People, Africa)
The Wakonyingo are dwarf spirits or elves who live at the peak of Kilimanjaro. They have their own ladders to climb to heaven. Though they are small of stature, their heads are so large that they carry a horn to call for help if they start to lose their balance.

Waktcexi (North American) *see* Wakcexi.

Wala (Fox People, North America) The Dawn.

Walangada (Aborigine People, Australia)
Walangada is one of the law-giving spirits who live in caves. *See also* Wondjina.

Walangala (Aborigine People, Australia)
He is a god of culture and social institutions. He is similar to Wallanganda, but Walangala did not create anything. If people do not follow the proper procedures, he will send floods. Walangala is associated with the maker of bull-roarers, Nyunyari. *See also* Ungud; Wallanganda.

Walhalla (Teutonic) *see* Valhalla.

Walkure (Teutonic) *see* Valkyrie.

Walkyrie (Teutonic) *see* Valkyrie.

Wallanganda (Aborigine People, Australia)
Wallanganda and Ungud created everything. They could be associated with the Wawalag sisters. *See also* Ungud.

Walumbe (Vedic; India)
Walumbe is mentioned in the *Rig-Veda* (approximately 1500 B.C.E.), as the god of death.

Wamara (Baziba People, Africa)
Father of gods. He has four sons: Kagoro; Mugasha, god of water; Kazoba, god of the sun and moon; and Ryangombe, god of cattle.

Wandjina (Aborigine People, Australia)
Ancestral spirits. When a Wandjina completes his task, he turns himself into a picture, which contains his spirit and power. According to Worora People, in eastern Australia, Wandjinas are giant human beings who came out of the sea. They created the world, spirit children and animals. In caves, they are painted as large figures with no mouths. The bodies are striped and dotted red, yellow, black and pale blue. The Worora repainted the Wandjinas as part of a ceremony to increase the number of animals. This ritual probably originated in Melanesia.

Wang (China)
The Jade Emperor Yu Huang's guardian of the palace door, Wang was also called upon to drive away evil spirits. *See also* Yu Huang.

Wang-chugmas *Wangchugmas* (Buddhist; Tibet)
There are twenty-eight of Wang-chugmas, who are bird and animal-headed goddesses. They appear in the Bardo World. *See also* Amrtakundali.

Wang-Mu-Niang-Niang (China)
Also known as: *Hsi-Wang-Mu, Lady Wang, Queen Mother Wang.*
Guardian. She is a beautiful young woman, who is the keeper of the peaches of immortality (known as P'an-T'ao or Shen-T'ao). Her husband is the Jade Emperor, or Yu-Huang-Shang-Ti. Wang-Mu-Niang-Niang is depicted in ceremonial dress, sometimes alone, sometimes with female attendants or with a peacock. *See also* Hsi Wang Mu.

Wantu Su (Africa; Sudan)
Creator. Wantu Su wanted to send gifts down to earth for humans, so he had his son, Wantu, slide down a rope and announce his arrival by drum-beating. A crow hit the drum which broke and scattered all the creatures of earth.

Warah (Arabic) *see* Shahar.

Waramurungundja *Waramurungundju* (Aborigine People, Australia)
Also known as: *Imberombera, Kunapipi.*
Mother goddess. She came out of the sea and from her body she produced children, animals and plants. She established the language for each group of people. *See also* Nuba; Wuraka.

Warana (Australia) *see* Wondjina; Yalungur.

Wasicong (Dakota People, North America)
Protective spirit.

Wata-tsu-mi (Japan) *see* O-wata-tsu-mi.

Watatsumi (Japan) *see* O-wata-tsu-mi.

Watchdog of Chulain (Celtic) *see* Cuchulain.

Water Mother (China) *see* Hsi-Ho.

www.ebook3000.com

Water Nymphs (Greek) *see* Naiads.

Wati and Kutjara (Aborigine People, Australia)
Also known as: *Two-Men.*

Spirits. Wati and Kutjara are ancestral spirits who gave men the ceremonial instruments that keep them in contact with the "Dreaming." They circumcised each other and the older brother gave his sister to his younger brother.

Waukheon (Dakota People, North America)
Waukheon is the thunder bird god. He and the water god, Untunktahe, are principal deities.

Wauwalak Sisters (Australia) *see* Wawalag Sisters.

Wawalag Sisters (Aborigine People, Australia)
Also known as: *Wagilag, Wauwalak, or Wawilak Sisters.*

Possibly fertility deities. They are generally associated with Yurlunggur and possibly Julunggul, Muit, Mumuna, Kunapipi. In legend one sister is pure and the other is not. Sometimes, they are identified with the Mungamunga girls who are said to be the daughters of Kunapipi. *See also* Djanggawuls; Rainbow Snake.

Wawalug (Australia) *see* Wawalag Sisters.

Wawilak Sisters (Australia) *see* Wawalag Sisters.

Waxcpini Xedera (Algonquian, Chippewa, Cree, Nascopie People, North America)
The Great Spirit.

Wayland the Smith (Teutonic)
Ruler of the dark elves. *See also* Alfar; Elves; Freyja.

We (A) (Kasena People, Africa)
Supreme god. This deity left earth because an old woman sliced bits from him for her stew pot.

We (B) (Teutonic) *see* Ve.

Weaver Damsel (China) *see* Chin Nu; Spinner Damsel.

Weendigo (North America) *see* Windigo.

Wehtiko (North America) *see* Windigo.

Wei-to *Wei-t'o* (China)
Also known as: *Bodhisattva, Celestial General Wei.*

Underworld deity. Overlord of all Hells. Guardian of the entrance. Chief of thirty-two generals who are subjects of the Four Kings. Wei-to is shown in armor including the helmet of a general. He is usually leaning with both hands on a club. Wei-to is the same as the Buddhist, Veda. He is identified with the Yaksha, Vajrapani. *See also* Ida-Ten.

Weiwobo (Japan)
Also known as: *Queen Mother of the West.*

One of the Sennins. Weiwobo, the Queen Mother, lives on a plateau, close to heaven, far to the west of China. *See also* Sennins.

Weland (Teutonic) see Wayland.

Weldegg (Teutonic) *see* Odin

Well of Urd (Teutonic) *see* Urd.

Wen Ch'ang (China)
Also known as: *Wen Ch'ang Ti Chun, Wen-ch'ang Ti-kun, Wen-chang-ta-ti, Wen-ti.*

God of literature. An ancient god, he is the emperor of literature, an honor bestowed on him by Tung Wang Kung (Yu-ti), the Jade Emperor, after he had lived a number of active, eventful lives. His original name as a mortal was Chang Ya, who was born during the T'ang dynasty. Another name given him was Chang Ya Tzu, and the dates of his life were either around C.E. 265–316 or some say C.E. 900–1280. In both cases he was killed during a fight. Wen Ch'ang is depicted in the blue dress of a mandarin and is usually seated, with a scepter in his hand. Sometimes only a tablet represents this god. Sometimes he is shown riding a white horse. His symbol is the crane. The god of examinations, K'uei-Hsing (Kuei-sing), was his helper. Another of his helpers is called "Red Jacket or Red Coat" (Chu I). In some versions his helpers are Hsuan T'ung-tzu and Ti-mu or T'ien-lung and Ti-ya. He is often confused with Tzu T'ung and K'uei-Hsing. *See also* Confucius.

Wen-chang-ta-ti (China) *see* Wen Ch'ang.

Wen Ch'ang Ti Chun (China) *see* Wen Ch'ang.

Wen-ch'ang Ti-kun (China) *see* Wen Ch'ang.

Wen-Ch'en (China) *see* Tara (B).

Wen-shu (China)
Wen-shu is the same as Manjusri, the god of learning. *See also* Manjusri; Dhyanibodhisattvas.

Wen-ti (China)
God of scholars. He is the same as Wen Ch'ang. *See also* Wen Ch'ang.

Wenen-Nefer (Egypt) *see* Unnefer.

Wenenefer (Egypt) *see* Unnefer.

Wenenut (Egypt)
Deified rabbit-headed goddess. Wenenut is the female counterpart of the hare-headed god, Wenenu. In some texts, Wenenu is identified as a form of Osiris. She is depicted with a knife in each hand, although she is also seen with the ankh and a scepter. *See also* Osiris.

Wenut (Egypt)
Also known as: *Unnet.*

Goddess of the hours. Shown as a woman with a star upon her head.

Wep-Rehewh (Egypt)
Also known as: *Thoth.*

"Judge of the Two Opponent Gods," Wep-Rehewh is an aspect of Thoth which refers to Thoth's role as judge in the strife between the gods Horus and Set for control of Egypt.

Weres *Urs* (Egypt) *see* Ab.

Weret Hekau (Egypt) The goddess of magic.

West, The (Egypt) *see* Ament; Amenti.

West Wind (Greek) The god Zephyrus is the West Wind.

Westre (Teutonic) *see* Westri.

Westri *Westre* (Norse; Teutonic)
Westri is one of the dwarfs who supports the heavens made from the skull of Ymir. His name is synonymous with South. His colleagues are Nordi, Sudri and Austri. *See also* Aarvak; Nordri.

Whaitiri *Whatitari, Whatitiri* (Maori People, Polynesia)
Cannibal chieftainess. Sky deity. Inventor of the latrine. She came down from the sky and married Kaitangata. They had two children, Hema and Punga. In several tales, Whaitiri, an evil woman, went blind and returned to the sky. In a Maori tale, Kaitangata complained constantly about the mess his children made and the smell of their excrement. Whaitiri invented the toilet, left the family behind and went to her home in the sky. *See also* Hema; Kaitangata; Tawhaki.

Whatitiri (Polynesia) *see* Whaitiri.

Whenua (Polynesia) Another name for Papa (q.v.).

Whisky Jack (North America) *see* Wisagatcak.

White Goddess, The (Greek)
The White Goddess is a name given to Leucothea, the sea goddess (known as Ino before deification) the by the Nereids. *See also* Ino; Nereids.

White Haoma (Persia) *see* Haoma.

White Hom (Persia) *see* Haoma.

Whitigo (North America) *see* Windigo.

Whitiko (North America) *see* Windigo.

Wieland (Teutonic) *see* Volund; Weland.

Wigan (Ifugao People, Philippines)
Also known as: *Muntalog.*
Wigan and her brother, Bugan, were survivors of the great deluge. Considered deities by some, there are many tales of how they created the human race. The god above them, Maknongan or Mumbonang, forgave their sin of incest in order to reinhabit the earth. Their first son was Kabigat. *See also* Huginn.

Wijadari (India)
Benevolent demigods. *See also* Vidyadhara.

Wild Huntsman (Teutonic) A title for Odin.

Wild Men of the West (Tierra del Fuego) *see* Oulapatou.

Wilobo (Africa)
Wilobo, his brother Woko and Wilobo's son Ru-piny are the deities who fix things. *See also* Jok; Woko.

Wilolane (Zuni People, North America) The Lightning.

Wimpe (Algonquin People, North America)
This sorcerer, involved in a contest with Gluskap, grew taller than the pine forest. Gluskap, the power of good, grew even taller and defeated him. *See also* Gluskap.

Winabojo (North America) *see* Nanabozho.

Windigo (Algonquin, Chippewas, Ojibwa People, North America)
Also known as: *Weendigo, Wehtiko, Whitiko, Witigo.*
Evil giants. The Windigo are a race of giant cannibals who prey upon human beings in the winter when food is scarce. These creatures have twisted mouths, emaciated bodies and hearts of ice. They emit a series of eerie whistles and also roar loudly. The only known way to destroy a Windigo is to hack it to pieces and burn it to melt its heart.

Wintua People — Creation Legend (North America) *see* Katochild.

Wisagatcak *Wisakedjak, Whiskey Jack* (Cree Indian People of Canada)
When Wisagatcak attempted to catch one of the large beavers who lived at the beginning of the world, he failed. The beavers used magic against him and caused water to cover the land. Wisagatcak made a raft. Many varieties of animals climbed aboard. After a time, a muskrat dove into the water looking for land. He drowned. A raven flew about in search of land, without luck. Wisagatcak with the help of a wolf magically made a ball of moss which turned into earth. It spread across the whole world and rested on water.

Wisakedjak (North America) *see* Wisagatcak.

Witana (Aborigine People, Australia)
A creator being. He made the gorges, cliffs, and water-holes. He also established the rites of initiation of male children into manhood. He made a cut in each arm. From one arm came blood which became red ocher, and from the other black blood came out which turned into reefs of black pigment. These colors are used in initiation ceremonies.

Witigo (North America) *see* Windigo.

Wlenenu (Egypt)
"Opener of the Ways." Wlenenu is a deified animal who is a door god. He is a battle god who appears on one of the four sacred standards of Pharaoh. His female counterpart is Wenenut. Wlenenu is sometimes identified as a form of Osiris. *See also* Wepwawet.

Wodan *Wode, Wodemus, Woden, Wodhen, Wodin, Wotan* (Germanic)
Wodan is a later form of Odin (q.v.).

Wode (Germanic) *see* Bertha; Wodan.

Wodemus (Germanic) *see* Wodan.

Woden (Germanic) *see* Wodan.

Wodhen (Germanic) *see* Wodan.

Wodin (Germanic) *see* Wodan.

Woko (Acholi People, Africa)
The deity Woko, his brother Wilobo, and Wilobo's son Rupiny are called upon when things go wrong. They are "fixer-uppers." The family is related to the Joks. *See also* Jok.

Woland (Teutonic) *see* Volund.

Wollunka *Wollunqua* (Aborigine People, Australia)
Also known as: *Rainbow Snake.*
A snake god. He was a snake so large he could travel for miles and his tail would still be in the waterhole he left. His companion is a mortal named Mumumanugara who was supposed to have come from the great snake's body. *See also* Rainbow Snake.

www.ebook3000.com

Wollunqua (Australia) *see* Wollunka.

Wolverine (North America) *see* Nanabozho.

Wonaambi (Australia) *see* Rainbow Snake.

Wondjina (Aborigine People, Australia)
Also known as: *Djunggun, Walangada, Warana.*
Spirits. The Wondjina are the spirits of the sky and rain. The Rainbow Serpent (Galeru, Kaleru, Galaru, Ungur) is a Wondjina. They live in caves and are the law givers. Other Wondjinas are Warana the Eaglehawk, Wodoi the Rock Pigeon and Djunggun the Owl. Another Wondjina is an unidentified deity named Walangada. They are depicted on their sides with their heads haloed. The Wondjina do not have mouths and their eyes and noses are joined. *See also* Gidja; Rainbow Snake.

Wongar (Australia) *see* Ungud.

Wonungur (Australia) *see* Rainbow Snake.

Worombi (Australia) *see* Rainbow Snake.

Wotan (Germanic) *see* Wodan.

Woutan (Teutonic) *see* Odin.

Wowta (Warrau People, Guyana)
An evil frog-woman. *See also* Abore.

Woyengi (Ijo People, Nigeria, Africa).
Mother, Creator goddess.

Wu-Ch'ang (China)
Also known as: *Kou-hun-shih-che, Mr. Black, Mr. White.*
Messengers. The Wu-Ch'ang are the gods who conduct the souls to hell. It is the two Wu-Ch'ang rather than Ox-head (Niu-t'ou) and Horse-face (Ma-mien) who are in charge. One of the Wu-Ch'ang is black and the other is white. They are called Mr. White and Mr. Black. The Wu-Ch'ang are dressed in black or white robes. A rope hangs around their necks and they wear tall pointed hats. Both gods have their tongues hanging out. They are opposed by the Door Guards. *See also* Ma-mien; Niu-t'ou; Yama Kings.

Wu Kuan (Central Asia)
One of the Kings of Hell. He presides over punishments that are dispensed by the Yakshas. *See also* Kshitigarbha; Yakshas.

Wuhuu (Waranjui People, Africa)
Wuhuu is a name for Heaven or the "World Above." The ruler of Wuhuu is Ruwa, Mrule, Mrile, or Nrile. Some say Mrule is different from the others and that he is associated with the Masai people.

Wulbari (Krachi People, Africa)
Supreme deity. Wulbari once dwelled on top of mother earth, but it became too crowded so he left for heaven. He is associated with the spider Anansi. Wulbari's legends are similar to the god Nyankopon (q.v.).

Wuldor (Teutonic) *see* Ull.

Wulgis (Aborigine People, Australia)
Spirits of dead medicine men. The Wulgis take a possible candidate and conduct him to the sky many times. This is where he learns the secrets of magic and healing. The Wulgis are often consulted by medicine men to help in healing the sick.

Wuni (Dagamba People, Africa)
Supreme god. In old times, men did not die but were slaves forever. They wanted to be free so they sent Dog and Goat to ask Wuni to free them. Because Goat confused the message and said men wanted to die, Wuni made the arrangements. This legend is similar to Kalumba's legend.

Wuotan (German) *see* Odin.

Wuraka (Aborigine People, Australia)
Probably a god of procreation. He is the companion of the mother creator, Imberombera. His penis was so heavy he wore it around his neck. *See also* Waramurungundja.

Wurd (Anglo-Saxon) *see* Urd.

Wuriupranili (Aborigine People, Australia)
The Sun Woman. Wuriupranili is a sun goddess who travels across the sky carrying her flaming torch of bark. She paints the sunset colors in the sky. *See also* Ilara; Tuniruna; Yuwuku.

Wurusemu (Hittite) Sun goddess. *See also* Arinna; Hepat.

Wyrd (Anglo-Saxon) *see* Urd.

Wyrra-Warre (Australian aborigines)
The sky or sky god.

X

Xamaniqinqu (Maya People, Yucatan)
God of the north. His brother is the creator god, Nohoyum (q.v.). *See also* Hapikern; Uyitzin; Yantho.

Xanthippe (Greek)
She is the daughter of Dorus (who is the son of Apollo and Phthia). She married Pleuron and became the mother of Agenor and three other children. *See also* Agenor; Dorus; Pleuron.

Xanthos (Greek) *see* Xanthus.

Xanthus (A) (Greek) *Xanthos*

Achilles' immortal horses, Xanthus and Balius, have the power of speech. They are the offspring of the west wind Zephyrus, and the Harpy Podarge. *See also* Achilles; Harpies; Oceanus; Zephyrus.

Xanthus (B) (Greek)
"Yellow." Another name for Scamander (q.v.).

Xbalanque *Xbalemque* (Maya People, Yucatan) *see* Hunahpu; Vukub-Cakix.

Xecotcovach (Maya People, Yucatan)
Demon bird. After the gods created mankind from various materials they decided their work was not sufficient so destroyed what they created by a flood. Other demons helped in the destruction. Xecotcovach devoured their eyes. Camalotz cut off their heads. Cotzbalam ate their flesh, and Tucumbalam smashed their sinews and bones. Mankind was not destroyed, but those who were left were changed into monkeys. Most of the legends come from the "Popul Vuh." *See also* Alom; Bitol; Camalotz; Cotzbalam.

Xelhua (Aztec People, Mexico)
He is a giant who survived the Great Deluge. *See also* Atonatiuh; Legend of the Four Suns; Nata and Nena; Tlazolteotl.

Xenodice (Greek)
Xenodice is the daughter of the wealthy Minos and Pasiphae (the daughter of the sun god, Helius). *See also* Acacallis; Ariadne; Minos; Pasiphae.

Xevioso (Fon People, Africa)
Also known as: *Heviosso.*
God of thunder. Xevioso is the son of Mahu and Lisa and the twin of Gun. At one time he was offered human sacrifices. Associated with Legba. *See also* Legba; Vodu.

Xi Wang Mu *Xi Wang-Mu* (Taoist; China)
Also known as: *Hsi-Wang-Mu, Queen Mother of the West.*
Xi Wang Mu is a powerful goddess who reigns over a paradise in the west. Her believers are promised immortality. *See also* Hsi-Wang-Mu.

Xib Chac (Yucatan)
The name for the rain god who is commonly called Chac (q.v.).

Xibalba *Xibalha* (Maya People, Yucatan; Quiche People, Guatemala)
"Place of Fright." The underworld realm of the dead. The Celestial Monster dives into Xibalba with the mortal soul on its back. The soul must confront the Lord of Death, and other obnoxious creatures such as the God of Zero, and the Vision Serpent. The Hero Twins, Hunahpu and Xbalanque, once descended into the depths of Xibalba to take control of this land by means of defeating the creatures in a series of ball games. The lords of Xibalba are Hun-Came, meaning "One Death," and Vukub-Cakix, meaning Seven Deaths. In the mythology of the Quiche People, Xibalba is a region of phantoms. Xibalba is the equivalent of Hades (Greek). Compare to Hades. *See also* Hell; Hun-cane; Hunahpu.

Xilonen (Aztec People, Mexico)
Also known as: *Chalchiuhcihuatl, Chicomecoatl, Princess of the Unripe Maize.*
Goddess of maize. Fertility goddess. Protector of the home. When the early corn appeared and turned green, it took on divine form and was Xilonen, the counterpart of the god Cinteotl. Households kept a basket in front of the maize bin which held five ears of dried corn. It was formed into and dressed as a woman. This represented Xilonen. She is sometimes identified as a wife of Tezcatlipoca. Extremely pretty, Xilonen is depicted seated primly with bare breasts. In her hands she holds fresh maize cobs. Her festival is in July when the maize turns ripe. The feasts feature maize, gruel and tamales. *See also* Atlantonan; Chicomecoatl; Cinteotl; Tzinteotl; Uixtochihuatl; Xochiquetzal.

Xipe (Aztec) *see* Xipe Totec.

Xipe Itzpapalotl (Aztec People, Mexico)
Also known as: *Camaxtle.*
Agricultural or star goddess. Little known but she is designated Obsidian Knife Butterfly.

Xipe Totec *Xipe* (Aztec, Mixtec, Nahua, Zapotec People, Mexico)
Also known as: *Camaxtle, Camaxtli, God 7 Rain* (Mixtec people), *Nanautzin, Red Tezcatlipoca, Yopi.*
"Our Flayed Lord." Vegetation Deity (particularly of seeds). God of suffering. God of spring. God of renewal. Healer of eye ailments. God of flowers. Patron of goldsmiths and jewellers. God of the sunset. Patron of gladiatorial combat. Xipe is identified with suffering and sacrifice, particularly gladiator sacrifice. Xipe is one of the four sons of Ometeotl and Omecihuatl. His brothers are Tezcatlipoca, Quetzalcoatl and Huitzilopochtli. Quetzalcoatl and Huitzilopochtli were charged with creating the earth, other gods, and people. When Xipe and his brothers were born the universal cycle of creation and destruction was put in motion. As the Red Tezcatlipoca, Xipe is the brother of the Blue, Black and White Tezcatlipoca and Quetzalcoatl.

During the year, soldiers captured young gladiators and held them captive until Xipe's feast, known as Tlacaxipehualiztli (meaning, "Flaying of the Men"). At the time of the Conquest the festival took place March 6–March 25. Numerous references indicate that the festival went on many days longer than scheduled. The gladiators were flayed (skinned) alive and offered for sacrifice. Their skins were worn by impersonators, who were usually the captors of the victims. Some say the flayed skins were considered holy.

The four cardinal points are associated with the four sons of the supreme dual god: Quetzalcoatl, Xipe Totec, Camaxtli, and Huitzilopochtli. They are also connected with the Four Suns which preceded our world and ended in destruction. Xipe is similar to the Mayan god of sacrifice, and patron of the day Manik. As god of the sunset, Xipe is associated with the west and wears the eagle down of sacrifice on his robe. He is generally depicted as a human inside the flayed skin of another man. Vertical stripes run from his forehead to chin, running over or broken by the eyes. The puckered flayed skin usually displays an incision where the heart was removed; the penis is absent.

www.ebook3000.com

The flayed skin is elaborately tied on at the back. *See also* Camaxtli; Coatlicue; Tezcatlipoca; Topiltzin.

Xiuhcoatl (Aztec People, Mexico)
Xiuhcoatl is the serpent that Huitzilopochtli used as a weapon to kill his sister, Coyolxauhqui. *See also* Coyolxauhqui.

Xiuhtecuhtli (Aztec People, Mexico)
Also known as: *Huehueteotl, Xiuhtecutli.*
"Turquois Lord." God of fire. God of time. One of five gods who rule the suns: Tezcatlipoca, god of the north and first sun; Quetzalcoatl, god of the west, and the second sun; Tlaloc, god of the south and the third sun; Chalchihuitlicue, goddess of the east and fourth sun; and Xiuhtecuhtli, god of fire. Xiuhtecuhtli is the god of the present day sun. This is the fifth and last sun known as "nahui ollin" (four earthquake) which will end in earthquakes and fire. He lives in Chicunauhmictlan (abbreviated Mictlan), the underworld, with Mictlantecutli and Mictlanciuatl. *See also* Huehueteotl; Hueytonantzin; Huitzilopochtli; Legend of the Four Suns; Tezcatlipoca.

Xiuhtecutli (Mexico) *see* Xiuhtecuhtli.

Xmucane (Yucatan) *see* Ocomoco.

Xochipilli *Cinteotl* (Aztec People, Mexico)
Also known as: *Flower Lord, Flower Prince, Huehuecoyotl.*
God of flowers. God of sport. God of dance. God of games. God of beauty. God of love. God of youth. Husband (others say twin and husband) of the eternally young Xochiquetzal. His father is Cinteotl. Xochipilli is one of the brothers of the Centzon Totchtin (q.v.). He is associated with Patecatl. Some say his consort was the female form of Pilzintecutli. *See also* Centzon Totochtin; Huehuecoyotl; Macuilxochtl; Xochiquetzal.

Xochiquetal (Aztec People, Mexico) *see* Cinteotl.

Xochiquetzal Xochiquetzalli (Aztec, Toltec People, Mexico)
Also known as: *Itzcuinan, Nina, Tonacaciuatl, Xochipilli.*
"Flower Quetzal." "Flower of the Rich Plume." Flower deity. Patroness of unmarried women. Patroness of weavers. Guardian of childbirth. Guardian of the new mother. She is the goddess of flowers and love, daughter of Tlazolteutl, wife of Tlaloc or as some say, Coxcoxtli (Coxcox) They survived on Colhuacan mountain. Their children, who could not speak, were given the gift of speech by a dove (some say it was a pigeon) and spoke a multiplicity of tongues, each unintelligible to the others. Tezcatlipoca fell in love with Xochiquetzal, taking her from the rain-god. (Some say it was Nina and her husband, Nala, who escaped the flood in a hollowed out tree.) In some versions, Xochiquetzal, Xilonen, Atlantonan, and Uixtociuatl are wives of Tezcatlipoca. In other versions, Xochiquetzal is identical with Tonacaciuatl and is the consort of Tonacatecutli. She lives in Xochitlicacan, Itzeecayan, or Tamoanchan. Some say she is the patroness of unmarried women who went to the battleground with warriors. Another story indicates that one of the hairs of Xochiquetzal was made into the wife of the first man who was either Oxomoco or Piltzintecutli (qq.v.) One of her aspects is that of Itzcuinan who was a goddess of childbirth and sexual pleasure. The marigold is the favorite flower of Xochiquetzal. *See also* Tezcatlipoca; Tlaloc; Tonacaciuatl; Tzinteotl; Xilonen.

Xochiquetzalli (Mexico) *see* Xochiquetzal.

Xochitl (Mexico, Toltec, Aztec)
Probably a goddess of Pulque. According to some sources Xochitl appeared about the same time as Tezcatlipoca and Huitzilopochtli. Although not particularly recorded as creating Pulque, the intoxicating drink became popular during her time. There were many deities of the ancient Maya, Aztecs, and Toltecs who were said to have created Pulque. There is indication she was a mortal and the wife of one of the early kings. *See also* Colhuatzincatl; Mayauel; Patecatl; Texcatzoncatl.

Xocotl (Aztec) *see* Huitzilopochtli; Otontecutli.

Xolotl (Aztec People, Mexico)
God of monsters. God of magicians. Dispenser of bad luck. God of twins. God of double ears of maize. Twin brother of Quetzalcoatl. As the god of magicians, he has the power to assume different shapes. Xolotl represents the evening star, the planet Venus. His Quetzalcoatl is the morning star. Xolotl is the god of the game, play-ball. Xolotl, in the form of a dog, accompanies the souls and the sun during their journey into the realm of paradise and down to the underworld. In dog form, he is also the companion of Quetzalcoatl. According to some, Xolotl may have been a deified leader or chieftain of a group of people called the Chicimecs. This legend indicates he had a son named Nopaltzin who in turn had a son named Tlohtzin. Xolotl is described as being deformed with both feet pointing backward. Sometimes, he is depicted as a dog. He is identified with deformity and illness. He is similar to Coyote and Ueuecoyotl. *See also* Ciuateteo; Mayauel; Miclantecutli; Quetzalcoatl.

Xpiyacoc (Maya) *see* Hunhun-Ahpu; Ixpiyacoc; Vukub-Ahpu; Xmucane.

Xquiq (Maya People, Yucatan)
Creator mother. Xquiq became the mother of Hunahpu and Xbalanque from Hunhun-Ahpu's spittle when his head was on a fruit tree in the underworld. *See also* Hunahpu; Hunhun-Ahpu; Vukub Hunahpu; Xbalanque.

Xubchasgagua (Colombia)
Xubchasgagua is another name for the moon goddess, Chia (q.v.).

Xue (South America)
Xue is a name for the supreme creator and law-giver, Bochica (q.v.).

Xumucane (Maya People, Yucatan)
Creator. According to myth the gods created men from white and yellow maize while Xumacane made the broth that gave the humans life. The first people were named Balam-Quitze, who was the head of his clan and whose god was Tohil, Balam-Agab whose god was Avilix, Mahucutah whose god was Hacavitz, and Iqi-Balam whose god was Nicahtagah. Although they were like gods, the gods were not pleased, so they clouded the mortal's vision to make them just human beings. *See also* Cipactonal; Gucumatz; Hunhun-Ahpu; Ocomoco; Vukub-Ahpu; Xpiyacoc.

Xuthus (Greek)
Xuthus is the son of Hellen, the king of Phthia, and the nymph, Ortheis. His siblings are Aeolus, who married Enarete and Dorus. Creusa (who was raped by Apollo) became his wife.

Their children are Achaeus, Diomede, Ion and possibly Dorus. *See also* Achaeus; Aeolus (A).

Xvarenah (Persia) *see* Khvarenanh.

Y

Ya-sima-zinumi-no-kami (Japan)

He is the husband of Konohana-chiru-hime (Blossoms-of-the-Trees-Falling-Princess). They are the parents of a son, Pupa-no-modi-kunusunu-no-kami. Konohana-chiru-hime is the descendant of Kushi-nada-hime, the rice goddess. *See also* Kushi-nada-hime.

Yacatecuhtli (Aztec People, Mexico)

Also known as: *Lord Nose.*

"He Who Goes Before." Yacatecuhtli is the god of commerce and traveling traders. He is shown as a bundle of staves. *See also* "M" (the Mayan god of travelers).

Yaccy-Ma (Tierra del Fuego)

Also known as: Possibly the same as *Taquatu* (q.v.).

Evil spirit. Yaccy-Ma is responsible for all evil deeds. His opposition is Yerri Yuppon, a giant black man, who is called upon in times of danger. *See also* Taquatu.

Yachihoko-no Kami (Japan)

"God of Eight Thousand Spears." Yachihoko-no Kami is a name for Okuni-Nushino-Mikoto, the god of medicine and sorcery.

Yachimata-Hiko (Japan)

God of the road. He and his female counterpart, Yachimato-hime, guard the cross-roads or as some say, all roads.

Yachimato-Himi (Japan) *see* Yachimata-Hiko.

Yadahpati (India)

"Lord of the Living Beings in Water." *See also* Varuna.

Yadavas (India)

The Yadavas are the Aryan descendants of King Yadu. Krishna is thought by some to have been born into this dynasty. When he became weary of battling demons, he assigned the divine architect Visvakarma the task of building a new kingdom. Upon completion, he led the Yadavas to their new home, the fortress city of Dvarka. Their first king was Ugrasena and the queen was his spouse Pavanarekha, the mother of the demon Kansa. Many Yadavas perished in the great flood but the survivors became the ancestors of kings. *See also* Jambavan; Kansa; Krishna; Syamantaka; Visvakarma.

Yagrush (Ugarit) A magic weapon. *See also* Khasis; Kothar.

Yahata (Buddhist, Shinto; Japan)

Yahata is another name for the god of war, Hachiman (q.v.).

Yahu (Semite) *see* Yahweh.

Yahveh (Hebrew) *see* Yahweh.

Yahweh *Yahveh* (Semite, Hebrew, Canaanite, Christian)

Also known as: *Elohim, Iaeuo, Iao, Jehova, Jehovah, Jhvh, Jhwh, Ya-w, Yaho, Yahu, Yahwe, Yahweh Elohim, Yau, Yaw, Yeuo, Yhvh, Yhwh.*

Supreme god. He is said to be an extremely jealous god who cannot tolerate the presence of other divinities. In the thirteenth century B.C.E. the Israelites overran the Canaanite cities. Their god Yahweh is obscure, but some think he may have been connected with the moon, since desert nomads travel by night and orient themselves by the moon. Yahweh may have been a weather god, which links him with Baal. His original name, Elohim, had first meant a collection of sacred or divine beings. Early Christian writers thought the diacritical marks placed under the consonants YHWH or JHVH by the ancient Hebrews indicated vowel sounds, but used the vowels for Adonai which ended up as the name Jehovah. Most scholars believe the correct pronunciation is Yahveh. There is a version where Yahweh is referred to as an Arabian volcanic god. In the first two chapters of Genesis in the Old Testament, two creation myths are presented. In the first chapter, the original state of the universe is watery chaos. The creator god Elohim divided creation into six separate periods, each belonging to one day. The order of creation is: Light; the firmament and heaven; the dry land (earth), separation of earth from the sea, vegetation; the celestial bodies; birds and fish; animals, and male and female together. In the second chapter of Genesis, in the beginning, the universe is waterless waste. Yahweh Elohim created man out of dust, the Garden of Eden, all trees, including the Tree of Life, and the Tree of the Knowledge of Good and Evil, animals and birds, and woman created from man. Recent discoveries indicate the goddess Ashura may have been the wife or consort of the Canaanite or Semitic god Yahweh. Remotely connected with Baal, Yam, Marduk and Tiamat. Possibly associated with Anat as her consort. *See also* Ashura; Varuna (India).

Yajna (Hindu; India)

When Daksha performed the first sacrifice, Yajna, a demigod

www.ebook3000.com

Raise your hands up to the universe and expand your hands as big as the universe - feel the Chi charge into your bones.

Scoop and gather the energy turning the body three times to the left and three times the right drawing the smiling energy.



Fig.3.40 *Scoop up the Universal Chi and pour it over the head.*

Open the Spine

1. Touch the back-crown point. Pour the Chi all over your crown. Think of your soles so that you feel like there is a waterfall of Chi flowing from your crown all the way down to your soles. Feel your finger grow long and the Chi penetrate down through your spine to the coccyx. Leave the fingers touchng the back of the crown, to maintain the energetic connection with the coccyx.



Spine

Fig. 3.41 *Feel your fingers growing long, all the way down to the coccyx.*

with a deer's head, was killed by Virabhadra. *See also* Daksha; Virabhadra; Vishnu.

Yajnesvara (India) *see* Vishnu.

Yakami, Princess (Japan)

The princess was offered to Okuni-Nushino-Mikoto, a medicine man and a sorcerer (among numerous other attributes), as a gift from the skinned hare of Inaba for healing him. *See also* Okuni-Nushino-Mikoto.

Yakamouch (Tierra del Fuego)

Yakamouch is a shaman similar to the Eskimo Angakok. While the Angakok can speak to Sedna, the Yakamouch converses with a being called Aiapakal and they gain their power from a spirit named Hoakils. The Yakamouch can be either a man or woman (usually old) and can be recognized by their hair which is covered by a grey or white clay. The Yakamouch can cure or cause disease or death and are able to control the weather. Other than their hair style, they look like any other human. *See also* Angakok.

Yakho (India) *see* Yaksha and Yakshini.

Yakka (India) *see* Yaksha and Yakshini.

Yaksa (India) *see* Yaksha and Yakshini.

Yaksha and Yakshini (Hindu; India)

Also known as: *Agnimukha* (Fire-Face), *Ashvamukhi* (Horse-face, applies to female Yakshinis in half-woman, half-horse form), *Punyajana* (Friendly Folk), *Supporters of the Houses, Yakho, Yakka, Yaksa, Yakshas* (masculine plural), *Yakshinis* (feminine plural).

The Yakshas and Yakshinis are minor deities of the air, forest, and trees. Shape changers, they are attendants who accompany their king, Kuvera the god of wealth. When Kuvera wants to travel the Yakshas carry him through the sky. These deities are usually good and are considered harmless but they can be wicked. They are ferocious guardians of their master's gates and are known as protectors of good. As shape changers they can appear in any form. Yakshini is the female counterpart of Yaksha. She lives in the forest and appears in a seductive female form who smiles invitingly at unsuspecting travelers, who will then lose their way. Once, a Yakshini led Prince Vijaya and his men away from their trail in the forest. She immobilized them but could not devour them because they were protected by special charms. The prince followed her deep into the forest. When she turned around, she appeared as a beautiful woman named Kuvanna. She agreed to release his men only if he married her. He did and they had two children, Pulinda and Pulindi. Eventually, Vijaya, who had slain many demons, became king. The Yakshinis are also known to be ferocious and have been known to devour children. Some of the Yakshinis are Vandya, Sumitra, Sringatpadini (who produces horns and changes men into animals), Sulochana, and Saudamani. A type of Yakshas known as Agnimukha live in hell. They torture sinners with their blazing red faces, hands and feet. The Yakshas can appear as handsome men but sometimes appear as ugly, black dwarfs with distended stomachs. Yakshinis are often found carved on temple pillars as sensual women with accentuated hips. One depiction shows a Yakshini grasping the branch of a tree while giving the trunk a gentle kick. The kick is thought to make the tree burst into blossom. Other carvings show them clinging to mango trees like acrobats. The swelling curves of their bodies are said to suggest the fertility of tropical nature. Chakrisvari, a Yakshini with sixteen arms, is represented with the Yaksha Gaumuh in a Jaina temple at Palitana as the guardian of the main entrance. Sometimes the Yakshinis are depicted as half-woman, half-horse. In this form they are known as Ashvamukhi ("Horse-face"). The Yakshas were supplanted by the Vidyadhara (q.v.) The Yakshas and Yakshinis are comparable to the Greek fauns and satyrs. *See also* Bhima (A); Dikpala; Hariti; Kuvera; Panchika; Pretas; Rakshasas; Shiva; Takshaka; Vasuki; Vijaya; Virudaka; Wu Kuan.

Yakshi (India) *see* Kuvera.

Yakshinis (India)

Nature and Air Deities. *See also* Yaksha and Yakshini.

Yakushi-Nyorai *Yakushi-Rurikwo-Nyorai* (Japan)

Also known as: *Bhaishajyaguru* (Sanskrit).

He is a divine physician who governs the land of Joruri in the East. Humans are protected against disease by him. He has twelve generals called Yakushi juni shinsho. *See also* Dainichi-nyorai.

Yakushi-Rurikwo-Nyorai (Japan) *see* Yakushi-Noyorai.

Yalungur (Australia)

Also known as: *Eagle Hawk, Warana.*

Gidja, the moon god, made the first woman by castrating Yalungur, Eagle Hawk.

For a different rendition see Gidja.

Yam (Ugarit) *see* Yam-Nahar.

Yam-Nahar (Ugarit)

Also known as: *Yam, Yamm.*

The son of the Father of the Gods, El, and brother of the god of fertility, Baal, Yam-Nahar is the god of the seas and rivers. Yam-Nahar demanded that the gods turn Baal over to his messengers. Frightened of Yam-Nahar, the gods bowed their heads. El, who favored his son Yam-Nahar, promised to turn Baal over to his messengers. Baal shamed the gods for being frightened of Yam-Nahar and attacked his brother's messengers. He was restrained by Anat and Astoreth. The god Kothar-u-Khasis gave Baal two magic weapons, known as "Yagrush" (Chaser) and "Aymur" (Driver), to use against Yam-Nahar. Baal managed to subdue Yam-Nahar and was about to kill him when he was restrained by Astoreth. In celebration of his victory, Baal's sister Anat in her aspect as a goddess of war arranged a massive feast. Dressed in her festive finery, she closed the palace doors on Mount Zaphon, and murdered all of Baal's enemies. It is said that she waded in blood up to her knees and hung the heads and hands of the dead on her body. Yam-Nahar represents the waters in their hostile aspect. Baal represents the waters as rain that fertilizes the earth. Compare this myth to the Mesopotamian myth of Marduk and Tiamat (qq.v.). *See also* Anath; Baal; El; Kothar and Khasis.

Yama (Brahmanic, Hindu, Vedic; India; Buddhist; Tibet).

Also known as: *Antaka* (Antiquity or He Who Ends Life), *Asu-niti, Chos-Rgyal Phyi-Sgrub* (Tibetan Buddhist), *Dandadhara* (Club-bearer), *Dharmaraha, Dharmaraja* (King of Virtue), *Kala* (Time), *King Yama* (Tibet), *Kritanta, Mitra, Mritya* (Death), *Pitripati* (Lord of the Fathers), *Preta-Raja* (King of Ghosts), *Samana* (The Leveller), *Samavurti* (The Impartial Judge), *Sraddeheva, Sraddhadeva* (God of Funeral Ceremonies), *Udumbara* (the Man of the Ficus Tree), *Vaivasvata* (Son of Vivasvat), *Yen-lo* (Central Asia).

In Vedic literature, Yama was the first man. He is considered an immortal who chose a mortal destiny. He is also described as a deified hero and the first man to die. In the Vedas Yama's kingdom is for good souls. In the Puranas, it is also a place for wicked souls. Yama, Soma and Varuna are the rulers of Pitriyana, the Vedic Path of the Fathers. Yama and his twin sister Yami are the children of Vivasvat, the rising sun, and Saranyu, the daughter of Tvashtri. In the Hindu tradition, Yama is the king of the dead. Later, as Dharmaraha, who was a form of Mitra and associated with Varuna, he became the judge of dead souls. Yama and Yami are the first man and woman and the founders of the human race. When Yama died, his soul traveled the path to the otherworld in the southern section of the upper sky and arrived in the Land of the Dead. He became the guardian of the south. His city is known as Yamapura and his palace is Yamasadana also known as Kalachi. The bloody river Vaitarani flows between this region and the land of the living. All souls must cross this water. Yama has two four-eyed, striped dogs with broad noses, Syama (also spelled Sarameya), the "courser," and Sabala (also called Svanau) the "hound." They are the offspring of Indra's heavenly dog Sarama ("Quick"). Some scholars believe that the dogs are Indra and Agni. Their duties are to guard the otherworld path and act as messengers as they visit dying souls. Sometimes an owl or a pigeon takes over their duties. Yama's ever vigilant messengers of death are known as the Yama-dutas. The emissaries lasso the spirit with a noose and deliver it to Yamapura. The trip from earth to the land of the dead takes four hours and forty minutes and cremation cannot take place until that time has passed. All humans will follow the same route after death, known as the "Path of the Fathers," or the "Path of the Manes" (Pitris, in Sanskrit). Yama and Varuna are the judges of the dead souls. (In later mythological times, Varuna became the lord of the ocean and had his own heaven.) In the Land of the Dead, Chitragupta the accountant produced a list of the mortal's deeds. This register is known as the Agrasandhani. A judgment, always fair, is handed down. The spirit is hurried back to the place of cremation where it feeds on oblations and receives a new body. The new body is led to Swarga (heaven) or to one of twenty-one hells, known as Naraka. If the destination is heaven, the faithful will be given the sacred beverage of the gods, Soma, to make them immortal. If the soul is headed to hell, the realm of darkness, known as Put, it must travel two hundred leagues a day through inconceivable tortures. Two of Yama's associates are the Vedic god Nirrita who is the guardian of the southwest, and Nirriti the goddess of decay. In the Buddhist tradition in China and Tibet, Yama became King Yama of the Ten Hells. In later times, Agni, representing the fire of the funeral pyre, presided over the "Path of the Fathers." Yama is depicted with a bull's head, a third eye and a crown of skulls. He stands to the right of a bull and under the bull is a woman. In another depiction, he appears similar but is naked except for a belt of heads and many jewels. As the judge of the dead he is shown riding a buffalo. He is green in color, often with a flower in his hair. He wears red clothing, and holds a noose and a club. He is also depicted as heavy set, with a greenish complexion, riding a black thunder horse. Around the first of November a festival known as Yama-dyitya is held in honor of Yama and Yami. The dog Syama, which means "black," is also a name given to Shiva. The first of the eight stages of yoga is called Yama. Yama corresponds to Varuna, who also uses a noose to capture the wicked. Compare to Manu, who is sometimes called Yama's twin; together they are known as the twin fathers of the human race. Yama corresponds to Yima (Persian). Compare to Osiris (Egypt), and Emma-O (Japan). *See also* Savitri (B) for a myth pertaining to Yama. Yama is sometimes identified with Kala, the god of time (q.v.). Compare Yama's dogs to Cerberus (Greek). *See also* Agni; Daksha; Dharma; Dikpalas; Indra; Lokapalas; Mara; Mrtyu; Parashur Rama; Parvati; Sanja; Saranyu; Shiva; Soma; Surya; Swarga; Tvashtri; Varuna; Vedas (The); Vishnu; Vivasvat; Yama Kings; Yamantaka; Yami.

Yama-Dutas (India) Messengers of death. *See also* Yama.

Yama-Dyitya (India)

Festival for Yama and Yami. *See also* Yama.

Yama-Isvara (India) *see* Yami.

Yama Kings, The (Buddhist; China, Tibet)

Also known as: *Shi-tien Yen-wang, Shi-wang.*

The ten kings, known as the Yama Kings, sit as rulers and judges of the ten courts of Ti-yu (Hell). Each king has jurisdiction over the punishment of distinct and clearly outlined crimes committed during the offender's life. The kings live in the chief town of Ti-yu, Feng-tu. The principal Yama King or King Yama, who some say is Yeng-Wang-Yeh (others say he was dismissed by the Jade Emperor), reviews the deeds of the newly arrived souls and determines whether he or one of the other judges will carry out punishment, basing his decision on the type and severity of the crime, whether it be sacrilege, arson, dishonesty, murder, or lying. It is the province of the tenth judge to determine whether the soul is to be reborn in the form of a human or an animal. The virtuous souls and those without blame may return to life on earth almost at once or may achieve a place among the immortals. Several versions give different categories to the functions of these judges. The deities who are sent to retrieve the souls of the dead are Ox-Head (Niu-t'ou) and Horse-Face (also known as Ma Mien). They are opposed by the door guards. In Tibet Yama or Gsin-rje gsed is a god of the dead. Yamantaka conquered death. The Yama Kings are generally shown in imperial dress garments with a roll of paper in front of them. The Yama Kings correspond to the Indian Bodhisattva Kshitigarbha and the Chinese Ti-tsang (q.v.). The opposite of hell is the Kun-lun Mountain (q.v.). *See also* Feng-tu; Kshitigarbha; Ma-Mien; Niu-t'ou; Ti-tsang-wang-pu-sa; Ti-yu; Yamataka; Yen-wang.

Yama-no-Kami (Japan)

Also known as: *Yama-no-Shinbo.*

Goddess of the hunt. Goddess of the forest. Goddess of agriculture. Goddess of vegetation.

www.ebook3000.com

Yama-Tsu-Mi (Japan) *see* O-Yama-Tsu-Mi.

Yama-Uba (Japan)
The Yama-Uba are evil female demons. They are possibly the same as Yuki-onna (the snow woman).

Yamai (Koli People, India)
She is a form of the Great Mother worshiped by people who fish. Newborns are shown her form which is represented as a stupa daubed with red clay. Goats are sacrificed to her yearly. *See also* Stupa.

Yamantaka *Yamantakha* (Buddhistic Hinduism; India, Tibet)
Also known as: *Dai Itoku-Myoo* (Japan), *Gsin-rje gsed* (Tibet), *Manjusri, Shin-je-she-chi-chyil-khor* (Tibet), *sSin-rje-gsed-kyi-dkyil-kor* (Tibet), *Yamari* (Foe of Yama).
Yamantaka, the Destroyer of Death, is the ferocious aspect of the deity Manjusri. He conquered the demon king Yama and exiled him to the infernal regions. Yamantaka is one of the four male guardians of the doors in Bardo. He guards the south gate. The other three male guardians are Armtakundali, the Coil of Nectar, Vijaya, the Victorious and Hayagriva, the Horse-necked, who is Vishnu as the god of learning, depicted with a horse's head. Yamantaka is the fierce form of Manjusri. His consort is Yamantakasakti, also a doorkeeper on the south gate. His consort is also referred to as Zhag-pa-ma, who is also known as Pashadhari, a sow-headed goddess. Yamantaka is depicted with the head of a bull, with a third eye and wearing a crown of skulls. His colors are black, blue or red. He has two arms and carries a karttrika (chopper) in his right hand and a kapala (human skull cup) in his left. He wears a belt of heads and is shown stepping to the right. He is usually accompanied by birds and demons. In paintings he is shown to have nine heads, sixteen feet, and thirty-four arms holding all the *Tantra* symbols. He is often green in color with flaming eyes. *See also* Armtakundali, for other deities, who appear with Yamantaka in Bardo on the sixth day. *See also* Ankusha; Dai Itoku-Myoo (Japan); Manjusri; Vishnu; Yama; Yima (Persian); Zhag-pa-ma.

Yamantakasakti (Tibet) *see* Yamantaka.

Yamantakha (Tibet) *see* Yamantaka.

Yamapura (India) City of the dead. *See also* Yama.

Yamari (India) *see* Dai Itoku-Myoo; Manjusri; Yamantaka.

Yamasadana (India) Yama's palace. *See also* Yama.

Yami (Hindu, Vedic; India)
Also known as: *Goddess of the River Yamuna, The Jumna, Kalinda-Kanya, Suryi, Yama-isvara, Yamuna.*
Yami is the twin sister and wife of the god of death Yama and the daughter of Vivasvat, the sun god, and Saranyu. They are described as the first couple and parents of the first human beings. She is identified with the sacred river Jumna, formerly called Yamuna. As the river Jumna, she protected the baby Karna and arranged for the goddess Radha to look after him. Bala-Rama is thought to have diverted her waters to irrigate the land. In one description, Yami has a swine's head. *See also* Bala-Rama; Ganga; Jumna; Karna; Kunti; Radha; Saranyu; Sarasvati; Vivasvat; Yama.

Yamma-Raja (Japan) *see* Emma-O.

Yamri (Afghanistan) *see* Imra.

Yamuna (India) *see* Yami.

Yan Tachu (Zuni People, North America)
Creator. Yan Tachu was created by Awonawilona and in turn he created mankind along with his wife, Tsita.

Yananamca Intanamca (Andean People, Peru)
Also known as: *Huacas.*
Spirits. The Yamanamca Intanamca are a group of spirits who walked upright and belonged to a group known as the Huacas. They were destroyed by a Huaca by the name of Huallallo Caruincho, who was evil. He was called Lord and instructed the women to have only two children. One of the children had to be sacrificed for him to eat. Huallallo Caruincho in turn was overthrown by a hero deity named Pariacaca (q.v.). *See also* Coniraya; Huacas; Viracocha.

Yanari (Japan) Goblin of earthquakes.

Yanauluha (Zuni People, North America)
The First Priest.

Yang (China) *see* Yin and Yang.

Yang-Chen (Buddhist, China)
Goddess of teaching and learning. Protector of sacred books. *See also* Sarasvati.

Yang Ch'eng (China)
Also known as: *Star of Happiness.*
God of happiness. He was once an official or mandarin who was quite small. Now he is worshiped as a deity. *See also* Shousing.

Yang Ching (China)
The goat god appealed to for protection against wild animals. He wears a goatskin and has a goat's head.

Yang Ki-Sheng (China) *see* Ch'eng Huang.

Yang-Ku (China) *see* Yang-Wu.

Yang-Wu *Yang-Ku* (China)
Yang-Wu is a valley in the east where the ten suns and their mother lived. Every day, each in turn, corresponding to one hour of the day, the suns crossed the sky, each one in his own chariot with the mother the charioteer, to a mountain in the west. Once, when all ten suns once appeared together, the Excellent Archer, Yi, took his magic bow and brought down all but one of the suns, saving the earth from the overpowering heat. *See also* Yi.

Yangombi (Bantu People, Africa) God of creation.

Yansan (Yoruban People, Africa) Wind deity.

Yantho (Maya) *see* Nohochacyum.

Yao (China)
God of writing. He authored works about regulating floods and binding rivers to their banks.

Yao-Shih Fu (China)
God of healing and sex change. He is the same as Buddhist god, Bhaishajyaguru.

Yaotl (Aztec, Toltec People, Mexico)
Also known as: *Texcatlipoca, Tezcatlipoca.*

"The Enemy." Yaotl spied on the ascetic, Yappan, until he caught him in a compromising position with the eternally young and beautiful goddess Xochiquetzal. Yaotl beheaded Yappan and the gods changed the fallen ascetic into a scorpion. *See also* Xochiquetzal; Yappan.

Yappan (Toltec People, Mexico)
Also known as: *Jappan.*

Deified mortal. Yappan was an ascetic mortal who wanted to win the favor of the gods. Leaving the world behind, he moved to the top of a huge rock and lived as a hermit. The gods, suspicious of Yappan, sent numerous women to seduce him. He did not bite the bait. So, Yaotl was sent to spy on him. In the meantime, the goddess Xochiquetzal decided to entice him. Yappan came down from his rock to help her climb up. He was lured into her net. After her conquest, she left him. Yaotl, who was privy to the episode, beheaded him. The gods turned Yappan into a scorpion, doomed to life under a rock instead of on top of a rock. Yappan's wife, Tlahuitzin, was also killed by Yaotl and changed into another variety of scorpion. *See also* Tlazolteutl; Yaotl.

Yaparamma (India)
She is one of the Mutalamma goddesses who are deities of the household. Yaparamma presides over business transactions. *See also* Mutalamma.

Yareah (Canaanite)
Moon god. He is worshiped with Shemesh, the deity of the sun. They are similar to Shahar and Shalem who are deities of dawn and sunset.

Yarikh (Mesopotamia; Syria, Ugarit)
Yarikh, the moon god, is the mate of the goddess of fruits of the earth, Nikkal. She is the daughter of Hiribi, the god of summer, and thought to be the youngest of the wise goddesses known as the Kathirat. When they married, the Kathirat provided all the necessities for the wedding. *See also* Baal; Kathirat.

Yarilo (Slavic)
God of love. He is generally thought to be connected with spring sown corn. Most legends associate him with carnal love. Yarilo is depicted as a young handsome man dressed in white. He carries flowers and sheaves of corn, is barefoot and rides a white horse. Sometimes he is shown with phallic attributes. Similar in some respects to Kupala (q.v.).

Yarovit (Slavic) God of victory.

Yasha (Nepal) *see* Dikpalas.

Yashts *Yasts* (Zoroastrian)
Hymns to the divine spirits, the Yashts form the Khorda-*Avesta. See also* Avesta; Bundahish; Tishtrya; Yazatas.

Yasoda (A) *Jesodha* (India)
Yasoda and Nanda, poor cowherds, were the parents of eight children. When their eighth child, a female, was born, Krishna and the gods replaced her with Krishna, as a newborn, to avoid the wrath of the evil Kansa. Yasoda and Nanda's daughter was assumed to be the child of Vasuveta and Devaki. For details, *see* Devaki; Devi; Kansa.

Yasoda (B) (India) Wife of Mahavira (q.v.).

Yasodhara (India) *see* Buddha; Shakti.

Yasts (Zoroastrian) *see* Yashts.

Yata *Yatis, Yatu, Yatus* (Zoroastrian; Persia)
Male counterparts of the Pairikas, the Yata are demon magicians and sorcerers who are the friends of the spirits of evil. Their chief is Akhtya. Compare to Daevas. *See also* Amesha Spentas; Angra Mainyu; Druj; Pairikas.

Yata-Kayami (Japan) *see* Amaterasu; Kagami.

Yatagarasu *Yata-Garasu* (Shinto, Japan)
Yatagarasu is the sacred crow of the sun-goddess Amaterasu. This tale corresponds to that of Yang-Wu in Chinese mythology. *See also* Amaterasu.

Yatis (Persia) *see* Yata.

Yatpan (Ugarit) *see* Khasis and Kothar.

Yatu (Persia, India)
A race of demons who take the shape of vultures or dogs. *See also* Yata.

Yatudhanis (India)
Female goblins and fiends who are associated with the sun. *See also* Devas (A).

Yatus (Persia)
Another spelling for Yata. *See also* Ameshas Spenta; Angra Mainyu; Yata.

Yau (Semite) *see* Yahweh.

Yauhahu (New Guinea) *see* Kenaima.

Yavishta (India) *see* Agni.

Yaw (Canaan)
The Hebrew people attached Babylonian myths to Yaw. *See also* Yahweh.

Yaya-Zakurai (Japan) Cherry tree goddess.

Yayu (India) God of air.

Yazatas (Zoroastrian; Persia)
Also known as: *Yajata* (Sanskrit), *Yazata* (singular), *Yazdan* (New Persian), *Zyed.*

"Adorable Ones." The Yazatas rank below Ahura Mazda and the Ameshas Spenta in the celestial realm. They are said to be innumerable; however, only about forty are mentioned in Zoroastrian texts. Of this number, the three most popular Yazatas are Sraosha, the guardian of humanity; his sister Ashi Vanguhi, the rewarder of good deeds; and Mithra. They are expressions of Ahura Mazda, and their duty is to transmit his will to mortals. They are divided into two classes: the spiritual, who personify truth and victory; and the material who are the guardian spirits of the elements, heaven, the planets, and stars. Other Yazatas are Anahita, Haoma, Atar, Verethraghna, Rapithwin, Apo, Hvarekhshaeta, Mah, Tishtrya, Hapto-iringa,

www.ebook3000.com

Satavaesa, Vanant, Dervaspa, Rashnu, Vayu, Tishtryas, and the twelve Akhtar or constellations. It is said that Ormazd was the first celestial Yazata while Zoroaster (the founder of the Zoroastrians) was the first terrestrial Yazata. The Yazata is also a part of the soul. It is created by Ormazd before a human's birth, and remains in the realm of the immaterial during life and survives death. The Yazatas are associated with the Fravashis (q.v.). *See also* Aeshma; Ahura Mazda; Akhtar (The); Ameshas Spenta; Asha Vahishta; Atar; Chinvat Bridge; Dervaspa; Haoma; Khshasthra Vairya; Mithra; Tishtrya; Vayu; Zoroaster.

Yazdan (Persia) *see* Ameshas Spenta; Yazatas.

Ydaler (Teutonic) *see* Ydalir.

Ydalir *Ydaler* (Teutonic) The abode of Ull (q.v.).

Y'den (Teutonic) *see* Idun.

Yeba Ka (Apache, Navajo, Papago People, North America)
Male leader of the gods.

Yebaad (Apache, Navajo, Papago People, North America)
Female leader of the gods. Female counterpart of Yeba Ka. *See also* Yeba Ka.

Yebitsai (North America) *see* Yebitshai.

Yebitshai (North America) *see* Yei.

Yebitshai *Yebitsai, Yepitsai* (North America) *see* Hasteseyalti; and Yei.

Yehl (Athapascan, Haida, Kwakiutl, Tlingit, Tsimshian People, North America)
Also known as: *Yetl.*
A name for the sacred bird, often called the Great Raven. Yehl is a demiurge and a trickster. In some myths, he is in the form of a crane. An Athapascan myth tells of Yehl the raven raising the earth from the waters after the great deluge. He became their ancestor and taught the people the uses of fire.

Yei (Navajo People, North America)
Also known as: *Yeibechi, Yeibichai.*
Household or nature spirits. A group of deities that can be classified as household or nature spirits. They are beneficial to mankind, and are opponents of the Anaye and Tshindi who are generally thought of as being evil. The Yei consist of Ganaskidi (harvest god), Thonenli (water god), Hastseyalti or Yebitshai (Yebitsai) (Maternal Grandfather of the gods and god of the east and dawn), and Hastshehogan (house god and god of the evening and the west). The highest of all is Estsanatlehi, a goddess of youth who grows old, then transforms herself into a girl again. Two brothers, Nayanezgani and Thobadzistshini, are worshiped as the destroyers of the Anaye. *See also* Anaye; Estsanatlehi; Ganaskidi; Hasteseyalti.

Yeibechi *Yeibichai* (North America) *see* Yei.

Yeibichai (North America) *see* Yei.

Yeitso (Navajo People, North America)
The Sun's child, a giant.

Yelafaz *Yelafath* (Yap People, Marshall Islands, Micronesia)
Also known as: *Luk.*
A creator deity. A huge tree hung from the sky, its roots touching the sea. A woman was born in this tree. Yelafaz gave her sand which she threw on the sea and thus created the earth. *See also* Lukelang.

Yellow Book of Lecan (Celtic) *see* Amergin.

Yemahya (Africa, Caribbean, Central America)
God of the deep sea.

Yemanja (Brazil)
Also known as: *Yemoja.*
Goddess of the sea. On New Year's Eve, at midnight, those who love Yemanja go to a beach and light a candle in her name. Then, little boats constructed of flowers are set adrift on the waves. If they are taken out to the sea by Yemanja, a good year will come. If they are refused and thrown back onto the sand, it will be a bad year. *See also* Yemoja.

Yemaya (Yoruba People, Africa)
Goddess of salt water. Goddess of the surface of the ocean. She is the wife of Olokun. *See also* Olodumare; Olokun.

Yembo (Africa) *see* Oduduwas.

Yemma (Japan) *see* Emma-O.

Yemoja *Yemaja, Yemanja, Yemaya* (Cuba), *Yemonja*; (Yoruba People, Africa)
Mother of the gods. Yoruban goddess of the Ogun river and sometimes known as Ogun's wife. She is sometimes called the goddess of rivers and fish. In some legends, she is the wife of Aganju. Worship of Yemoja was carried to Cuba and Brazil (where she is known as Yemanja or Yemaya). *See also* Obatala; Ogun; Yemanja.

Yemonja (Africa) *see* Yemoja.

Yemowo (Africa) *see* Obatala.

Yen Kung (China)
Weather god. He has the power to calm winds and waves.

Yen-lo Wang (China) *see* Yen-Wang.

Yen-Wang (China)
Also known as: *Yen-lo Wang, Yen-Wang-Yeh.*
Underworld deity. The god of the world of the dead, the chief of the Yama Kings. Yen-Wang controls the manner and time of death and decides the destiny of the souls of the dead, determining the shape, human or animal, those who return to earth will take, selecting those who will receive immortality and judging the punishments for the wicked. One version says Yen-Wang was dismissed by the Jade Emperor as chief of the underworld because he was too merciful. His replacement was Ts-in-kuang-wang. Yen-Wang corresponds to the Bodhisattva Kshitigarbha. (The chief of hell is Ti-tsang Wang-p'u-sa.) *See also* Kshitigarbha; Ts-in-kuang-wang; Yama Kings; Yen-lo Wang.

Yepitsai (North America) *see* Yebitshai.

Yero (Australia) *see* Rainbow Snake.

Yerri Yuppon (Tierra del Fuego) *see* Yaccy-Ma.

Yeshe-Khahdoma (Tibet) *see* Khadomas.

Yeshu (Hebrew) *see* Jesus.

Yetl (North American Indian) *see* Yehl.

Yeuo (Semite) *see* Yahweh.

Yew of Ross (Celtic) *see* Abellio.

Ygdrasil (Teutonic) *see* Yggdrasil.

Ygdrasili (Teutonic) *see* Yggdrasil.

Ygg (Teutonic) *see* Odin.

Yggdrasil *Iggdrasil, Ygdrasil, Yggr-drasill, Ygdrasili*; (Norse; Teutonic)

Also known as: *Ashyggr-drasil, Hoddmimir's Wood, Laerad, Ledrad.*

The ash tree Yggdrasil is the sacred tree of life, the universal tree. Yggdrasil's branches spread across the universe. It connects and shelters all the worlds. It has three roots: one is among the Aesir where Urd's Well, named after the wisest of the three goddess of Fate, is located. It is here that the gods and the Aesir have their principal meeting place. Another root is in the land of the giants, Jotun-heim, near Mimir's Well, the well of wisdom. The third root is deep in Nifl-heim, the underworld, where the Hvergelmir well is located. Here the dreaded serpent Nidhod constantly gnaws at Yggdrasil's roots. Yggdrasil was created by the All-Father after Odin and his colleagues established Midgard. An eagle perches on Lerad, the topmost bough of the sacred tree. Between his eyes Vedfolnir the falcon sits watching all. In some myths it is the golden cock, Gullinkambi, who watches. Always green, the tree provides food for Odin's goat Heidrun, who provides Odin's warriors with milk. The stags Dain, Dvalin, Duneyr, and Durathor nibble at the new buds and drip honeydew or water on the earth for all the rivers. The tree also has another occupant, a squirrel or rabbit named Ratatosk who constantly attempts to cause strife between the dragon and the eagle. The three goddesses of destiny known as the Norns are responsible for taking care of Yggdrasil. They sprinkle it with sacred waters from Urd's fountain. Heimdall's horn Gjall is hidden under one of Yggdrasil's roots. Compare Yggdrasil to the myth of the serpent Abyrga of Central Asia. *See also* Aesir; Alfheim; Ask; Dain; Davalin; Gjall; Gullinkambi; Haoma (Persian); Heidrun; Hvergelmir; Jotun-heim; Lif; Midgard; Mimir; Mimir's Well; Nidhod; Nifl-heim; Norns; Odin; Ratatosk; Urd; Verdandi; Ymir.

Yggr (Teutonic) *see* Odin.

Yggr-drasill (Teutonic) *see* Yggdrasil.

Y H V H (Hebrew) *see* Yahweh.

Y H W H (Hebrew) *see* Yahweh.

Yi (China)

Also known as: *Excellent Archer.*

Probably a sun god. Yi is the husband of Chang-o. There were once ten suns in the sky. When the excessive heat threatened the earth, Yi used his magic bow, given to him by emperor Ti-suin, to shoot down nine of the suns. This is why we have only one sun. In one version Si-wang-mu, who was the queen of the immortals, gave him the drink of immortality, but Yi's wife stole it. The drink allowed her to fly, but because Yi interfered she only drank part so was unable to fly to heaven. Stopping half-way she became a goddess of the moon, while Ye went all the way and became a sun deity. *See also* Yang-Wu.

Yi-dvag (Tibet) *see* Pretas.

Yidak (Buddhist; India)

Yidak is the spirit world of thirst and hunger. One is relegated to this world after death if during life it was necessary to always have the upper hand. These spirits have distended stomachs and suffer from colic. The water they drink turns to fire. The Yidak have long, thin necks and small mouths. *See also* Chakravala; Sukhavati.

Yim (Persian) *see* Yimi.

Yima (Indo-Iranian, Persian)

Also known as: *Jam, Jamshid* (later form of the name), *Jemshid, Yim, Yima Khshaeta, Yimi.*

Yima is the divine aspect of Jamshid, the first Iranian mortal. Known as the first king, he ruled the earth for a thousand years. During this golden period, the earth was plentiful and peaceful. As hunger, illness, cold, heat, and death did not exist, the population increased and Yima had to enlarge the world three different times. At the end of his reign, the world was twice as large as it was in the beginning. Yima is the creator of three fires: Burzhin Mitro, Frobak and Gushasp. When Yima was warned by the creator, Ahura Mazda, that Mahrkusha would send three wretched winters that would encompass the world, he built a Vara (cavern) to ensure the continuity of the earth's population. Here he placed the best of men, animals, and plants. Unfortunately, Yima had a dark side. He broke Zoroaster's law by bribing men with ox flesh in one rendition, and in another by lying and delighting in his lies. Three different times his lies caused his Khvarenanh (spirit or glory) to fly from him in the form of a bird. The first time, Mithra caught it; the second time, Traetaona; and the third, Keresaspa. In some renditions, at this point, he was seized by Azhi Dahaka. He either died by his brother Spityura's hand or was killed by the evil Azhi Dahaka in the form of a mortal named Zahhak, who took over his kingdom. In later times, Yima was known as a builder. As a cultural hero, he taught men to lay foundations and mold bricks. Yima initiated the Persian festival, Nauroz. In a variation of this myth, Yima is the first man, son of Vivanghvant or Yama. He lived in a Vara where he endured a horrible winter. Ahura Mazda sent a bird with the message that he was to leave the Vara and till the earth. The Vara, made of kneaded clay, was two miles long and two miles wide. It had only one window that was self-luminous, and one door which was sealed up. Within it he had all the seeds necessary to proceed with his mission. In addition, he was given a ring and a dagger by Ahura Mazda. During his 900 winters on earth, he filled it with people, birds and animals in a 600-year span. He then expanded the earth three times during the next three years by one-third its size each time. His reign was a golden period; people were happy living under the *Avesta* (law) of Ahura Mazda, and they lived for 150 years. Takhmoruw and Hoshang are also known as first kings in Persian mythology. According to some Yima's father was Takhmoruw who was the son of Husheng, who was son of Siyamek, who was son of Gayomort. In this case, Yima

www.ebook3000.com

was not the first mortal. He was, however, the first immortal to chose mortality. Compare to Ymir (Teutonic). *See also* Ahura Mazda; Azhi Dahaka; Drujs; Haoma; Hoshang and Takhmoruw; Jamshid; Keresapa; Khvarenanh; Mahrkusha; Mithra; Thrita; Vivanghvant; Yama.

Yimak (Iranian) *see* Yimeh.

Yimaka (Iranian) *see* Yimeh.

Yimeh (Iranian)
Also known as: *Yimak, Yimaka.*
Creator. Wife of Yima, and, like him, she is a creator of the human race. *See also* Yima.

Yimi (Persian) *see* Yimi.

Yin and Yang (China)
Creators. Yin and Yang are the two ethers that came from the dividing of the original cell of primeval chaos, Ch'i. Yin is female, dark, negative and of the earth, and symbolized by a divided or broken line. Yang is male, bright, positive and of the heavens, and is symbolized by an unbroken line. Yin came to be identified with demons; Yang, to represent the gods. Yin and Yang are the foundation of the doctrine of dualism, in which alternating and opposing forces brought about the creation of the universe, Yin forming the earth and Yang the sky. Yin and Yang shaped the fundamental nature of all living things. In one version Yin and Yang became mixed and this resulted in the creation of man. This first man was named Huang-lao. Corresponds to In and Yo of the Japanese people. *See also* Chaos; Tien.

Yinewumana (Pueblo People, North America)
Goddess of Gems.

Yiyantsinni (Navaho, Pueblo, and Iroquois People, North America)
The Yiyantsinni are twelve men who hold up the sun or the heavens with their poles. *See also* Atseatsan and Atseatsine.

Ylg (Teutonic) *see* Elivagar.

Ymai (Turkey) *see* Umai.

Ymer (Teutonic) *see* Ymir.

Ymir *Ymer* (Norse; Teutonic)
Also known as: *Augelmir, Aurgelmir, Aurgenimir, Fornjotnr, Hrim-Thurs* (Ice Giant), *Hrimthursar, Orgelmir, Yme.*
The first of the supreme gods, Ymir is an evil frost giant. He was created in Ginnunga-gap, a vast place of emptiness, at the beginning of the universe. Created from the mist of ice rime of Nifl-heim when it encountered and was melted by the warmth from Muspells-heim, the land of fire, he was called a Hrim-Thurs (ice-giant). Ymir was nourished by the divine cow, Audhumla, who was formed from the drips of ice before he came into existence. While Ymir rested, a man and a woman came from the sweat from under his left armpit, and a son from the union of one of his legs to the other. After the birth of the son and daughter, Ymir produced a six-headed giant named Thrudgelmir from his feet. Thrudgelmir in turn brought forth the giant Bergelmir who was the producer of all the evil frost giants. After being killed by Odin and his family, Ymir's flesh was turned into the garden Midgard which had a hedge surrounding it made from Ymir's eyebrows. Ymir's blood or sweat formed the ocean surrounding Midgard. His bones were the hills, his teeth the cliffs, his hair the trees and vegetation and his skull became heaven along with his brains which became the clouds. In another myth, it is Fornjotnr rather than Ymir who produced the first gods. Fornjotnr had three sons, Hler, Kari and Loki. It is also said that the tree Yggdrasil grew from his body. In one version, the first man was named Buri. With his sister/spouse, they had a son Bor who in turn had three sons, Odin, Vili, and Ve. From them came the Aesir (gods). There is a version that relates that when Ymir was killed the blood inundated the earth. Only a man and woman survived and from them a new race of giants descended. In the same version Ymir's flesh crawled with maggots which the gods gave wits and human appearance, and they turned into dwarfs. Compare Ymir to Yima (Indo-Iranian). *See also* Aesir; Ask; Audhumla; Bergelmir; Bestla; Buri; Dwarfs; Elivagar; Embla; Fornjotnr; Ginnunga-gap; Jotun-heim; Loki; Midgard; Mimir; Muspells-heim; Nifl-heim; Odin; Thrudgelmir; Ve; Vili; Westri; Yggdrasil.

Ynakhsyt (Yakut People, Siberia) Goddess of cattle.

Ynawc (Celtic)
Ynawc is one of the seven survivors of the battle between Bran and Matholwch. *See also* Bran.

Yngri (Teutonic) *see* Freyr.

Yngve (Teutonic) *see* Thor.

Yngvi (Teutonic) *see* Odin.

Yo and In (Japan)
The female and male principles, analogous to the Chinese Yin and Yang, of the egg of chaos that split to form the earth and heavens. *See also* Izanagi; Yin and Yang.

Yo-Elat (Ugarit) *see* Anath-Yahu

Yo Po (China) Fish god. *See also* Nine Songs; Shui Shen.

Yo-shi-wang Fo (China) *see* Yo-wang.

Yo-wang *Yo-shi-wang Fo* (Buddhist; China)
God of healing and medicines.

Yoalli (Mexico) *see* Texcatlipoca.

Yoalliehecatl (Mexico) *see* Teczatlipoca.

Yoamaxtli (Mexico) *see* Camaxtli.

Yocahu (Antilles Islands) *see* Guamaonocon.

Yocahuguama (Antilles) *see* Iocauna.

Yoga-Siddha (India)
The Monkey Queen. *See also* Visvakarma.

Yogini (Hindu; India)
One of the eight female demon servants of the goddess Durga (q.v.)

Yogisvari (India) "Adept in Yoga." *See also* Devi.

Yohual-Tecuhtin (Aztec People, Mexico)
Lords of the night. Ten deities who determine the fate of men.

Yohaulticetl (Anahauac People, Mexico)
Also known as: *Metztli, Tecciztecatl.*
"The Lady of the Night." Goddess of night. Guardian of babies. She is also the moon god, Tecciztecatl, who is also known as Meztli. *See also* Coyolxauhqui; Metzli; Tecciztecatl.

Yohualtonatiuh (Aztec) *see* Legend of the Four Suns.

Yolaikaiason (North America) *see* Atseatsan and Atseatsine.

Yolcuatl (Mexico) *see* Quetzalcoatl.

Yolkai Estsan (Navajo People, North America)
Also known as: *Yolaikaiason.*
Water goddess. Yolkai Estsan was created from a white shell. She is the sister of Estsanatlehi, the wife of the moon carrier, Klehanoai, and the mother of Thobadzistshini. *See also* Ataentsic; Klehanoai.

Yomanua-Borna (Antilles)
He is a rain god with two assistants, who has a shrine in a cavern.

Yomi (Shinto; Japan)
Also known as: *Meido, Ne-no-kuni* (Land of Roots), *Neno-katatsu-kuni, Soko-no-kuni* (Deep Land), *Sokotsu-kuni* (Bottom Land), *Yomi-no-kuni, Yomi-no-yo, Yomi-tsu-kuni* (Land of Darkness), *Yomotsukuni* (Land of Gloom).
Underworld. Yomi is the realm of the dead, a bottomless chasm and kingdom of darkness lying below the earth. It is reached from the edge of the sea or by a twisting, downhill road that leads to a subterranean level. The populace of Komi, rich, poor, good and bad, appear to lead lives similar to their mortal existence; they eat, have homes and move around. Punishment and rewards are not a part of this dark world. Once one eats the food cooked in Yomi then he or she is incorporated into the underworld realm. The grotesque female inhabitants of Yomi are known as Yomo-tsu-shiko-me (ugly-female-of-the-world-of-the-dead), also known as Shiko-Me. In some versions, Yomi is ruled by Tsuikiyomi-no-Mikoto, who is often called Tsuki-yomi. Tsuki-yomi is the ruler of the moon and the ruler of the night. It is also said that Yomo-tsu-kuni is the god of the realm of the dead. Yomi is referenced in the legend of Izanagi and Izanami and Okuni-nushi and Susanowo. Izanami (Female Who Invites) became the ruler of death and ills in Yomi after her death. The Peach Tree of Life grows on the border of Yomi. The peach is a symbol of the mother-goddess. Izanagi threw three peaches at his pursuers in Yomi. (The Chinese also have a gigantic sacred Peach Tree.) According to some, Yomi is possibly derived from Yama as other names associated with Yama or Yomi are deities of the underworld. The opposite of Yomi is Ama (heaven). Compare to Jigoku (Buddhist), Tuat (Egypt), Tartarus and Hades (Greek). *See also* Izanagi and Izanami; Kami; O-Wata-Tsu-Mi; Okuni-Nushino-Mikoto; Shiko-Me; Susanowo; Yomo-tsu-kami.

Yomi-no-kuni (Japan) *see* Yomi.

Yomi-no-yo (Japan) *see* Yomi.

Yomo-tsu-kami (Japan)
God of the dead. Possibly a male version of Yomo-tsu-shiko-me. *See also* Soko-no-kuni; Yomi.

Yomi-tsu-kuni *Yomotsukuni* (Japan)
"Land of Darkness." "Land of Gloom." *See also* Yomi.

Yomo-tsu-shiko-me (Japan)
"Ugly-female-of-the-world-of-the-dead." She is a resident of the underworld realm of the dead, Yomi. *See also* Shiko-Me; Yomi.

Yomotsukuni (Japan) *see* Yomi-tsu-kuni.

Yondung Halmoni (Korea)
Ancient wind goddess. She is given rice cakes during her celebrations in shamanic rituals.

Yorodzu-Hime (Japan) *see* Kami-Mimusubi.

Yoskeha and Taweskare *Yoskeha and Tawisara, Yoskeha and Tawiscara*; (Huron, Iroquois People, North America)
Also known as: *Hahgwehdiyu and Hahgwehdaetgah, Sapling and Flint, Yoskeha and Teharaonhiawagon.*
In an Iroquois version of this myth, Yoskeha and Taweskare are the twins of the mother goddess Ataentsic (also spelled Ataensic). The twins, bitter enemies, caused their mother's death. Ataentsic, who created the sun and moon from Taweskare (Flint), cast Yoskeha (Sapling) out for not telling the truth about who caused her death. Flint became a trickster and maker of malevolent beings and spirit of winter. In some versions, Ataentsic is their grandmother. In another version Yoskeha, known as Teharaonhia-wakon, still a sapling, changed himself into a youth each time he grew old. For a different version of this myth, *see* Taweskare. *See also* Ataentsic; Hadui.

Yoyolche (Aztec People, Mexico)
These evil demons live underground. When they walk at night they shake the house with their giant steps. *See also* Kisin; Yumchakob.

Yryn-ai-tojon (Siberia) *see* Yryn-aja-tojon.

Yryn-aja-tojon (Siberia)
Also known as: *Yryn-ai-tojon.*
Supreme deity. He is the white lord who created earth by challenging Satan to bring a piece of earth from the bottom of the sea. Yryn sat on this piece of earth and Satan stretched it to force him off. The more he stretched the larger the earth became. *See also* Ullu Tojon.

Ytzmatul (Maya) *see* Itzamna.

Yu-Ch'iang (China)
God of the sea wind. He is responsible for great storms. Depictions show him with a human face and the body of a bird. Sometimes two green serpents hang from his ears and two more cling to his feet. Yu-Ch'iang is also shown with the body of a fish. He rides on two dragons.

Yu-Ch'ih Ching-Te (China) *see* Men-shen.

Yu Ch'ing (Taoist; China)
Also known as: *Lo Ching Hsin, T'ien Pao, Yu Huang, Yuan-shih T'ien-tsun.*
Supreme deity. God of the "Jade Heaven." In some versions this is one of three heavens called San Ch'ing. Yu Ch'ing is either the first heaven or the ruler of the first heaven. *See also* Ling-Pao T'ien-Tsun; Shang Ch'ing.

www.ebook3000.com

Yu-Huan-Shang-Ti (Taoist; China)
Also known as: *August Personage of Jade, August Supreme Emperor of Jade, Father Heaven, Huang T'ien Shang Ti, Jade Emperor, The Jade God, Lao-tien-heh, Lao-tien-yeh, Mu Kung, T'ai Ching, T'ien, Tien, Yu Ch'ing, Yu'ti.*
"The August Supreme Emperor of Jade." Emperor of the gods. God of purity. God of nature. Creator deity. Yu-Huang-Shang-Ti, the son of Pao Yu and Ching Te, lives on the highest level of heaven with his wife, the Queen Mother Wang (also known as Wang-mu-niang-niang and Hsi Wang Mu). All lesser gods in his court report to Yu-Huan-Shang-Ti about human activities. The emperor created mortals from clay. The clay figures were put out to dry but rain came and some of the figures were damaged. The damaged figures constitute the sick who live on earth; the healthy mortals are the clay figures that he saved. The door to his palace is guarded by Wang. According to Taoist tradition, as Yuan-shih T'ien-tsun, his agents are Tsao Chun and Lei Tsu. Yu-Huan-Shang-Ti is part of a triad of three deities from heaven (known as Ta-lo or San Ch'ing). The first member of the triad is Yuan-shi T'ien-tsun or Lo Ching Hsin or T'ien Pao. The second is Yu-Huang or Ling-pao T'ien-Tsun, and the third is Kin-k'ue Yu-chen T'ien-tsun or Lao Tzu. He is depicted seated on a throne, wearing the formal robes and headdress of a Chinese emperor. *See also* Si-wang-mu; Yu Ch'ing; Yuan-shih T'ien-tsun.

Yu-K'ien (China) *see* Ch'eng Huang.

Yu-Lu (China)
Door god. Guardian of the left side of the door. His brother, Shen-T'u, guards the right side. These two deities have been replaced by Ts'in Shu-pao and Hu King-te. Like most deities these were formerly mortals, in this case generals of the army of the T'ang Emperor. One has a red face, the other black. *See also* Celestial Kings; Men-shen; Shen-T'u.

Yu-ming Kio-shi (China) *see* Ti-tsang.

Yu Nu (China)
Also known as: *Jade Lady, T'ien Hsien Yu Nu Pi Hsia Yuan Chu* (First Lord of the Blue Sky, Heavenly Fairy, Jade Lady).
Goddess of rain. Yu Nu is the daughter of Tung Hai (Eastern Sea) and wife of Hsi Hai (Western Sea). She brings rain during periods of drought.

Yu Po (China)
Water deity. One of the Nine Songs. Similar to Shui Shen. *See also* Nine Songs.

Yu Shih (China)
Lord of the Winds. Yu Shih is a rain god, who has the gift of magic, and lives in K'un Lun Mountain. He walks through water without getting wet and fire without being burned. He is shown standing on a cloud pouring rain from a water can. He may be the same as Yu-Tzu (q.v.). *See also* Nine Songs; Yu Huang; Yu Nu.

Yu-ti (China) *see* Yu Huang.

Yu-tzu (China)
Also known as: *Master of Rain.*
God of rain. Yu-tzu carries rain in a ceramic pot and distributes it with his sword. He is generally found with Tien Mu (lightning) and Lei-kung, the thunder god. Possibly same as Yu-Shih.

Yuan Shi (China) *see* Chen Wu.

Yuan-Shih T'ien-Tsun (Taoist, China)
Also known as: *The First Cause, Lo Ching Hsin, Yu Ch'ing.*
The Highest God. Invisible and immortal, he existed before creation. Some say he was part of a triad of high deities. Others say he is the highest of the high deities. He appears to have been replaced by Yu Huang. Yuan-Shih is associated with Tsao Chun (kitchen god) and Lei Tsu (thunder god) and Yu Ch'ing.

Yuan-shih T'ien-wang (China) *see* P'an Ku.

Yuddhisthira (India) *see* Yudhisthira.

Yudhishthira (India) *see* Yudhisthira.

Yudhisthira *Yuddhisthira, Yudhishthira* (India)
The son of Kunti and the god of justice, Dharma. *See also* Arjuna; Bhima (A); Brahma; Dharma; Duryodhana; Krishna; Kunti; Pandavas; Visvakarma.

Yuga (India) *see* Dwaparayuga.

Yuke (Norse; Teutonic) *see* Hiuke.

Yuki-onne (Japan) *see* Yukionna

Yukionna *Yuki-onne* (Japan)
Goddess of winter. Snow Woman. A ghastly, ghostly white spirit. Her custom is to appear in snowstorms and lull men to sleep and to death. She is young and has a beautiful body and a seemingly nice disposition, but she kills her husbands.

Yul-khor-bsrun (Tibet) *see* Dhartarastra.

Yum Caax *Yum Kaax* (Maya People, Yucatan)
Also known as: *Ghanan.*
The god of maize, coca and agriculture. Yum Caax is a handsome young deity. He is honored at planting and harvest time, particularly for coca and maize. The dried leaves of the coca, when masticated, create a state of euphoria. It was known as the "divine plant" by the Incas and was used by the ruling class. The coca plant has been revered by many groups. The leaves are used for purification or to ward off evil spirits. It has also been used to heal wounds, stomach problems and intestinal disorders. Maize is often a symbol of fertility and sustenance. *See also* Cinteotl.

Yum Chung Chun (China)
The god of the clouds. One of the nine heroes. *See also* Nine Songs.

Yum Cimil (Maya People, Yucatan)
Death god. Lord of the underworld. *See also* Hanhau.

Yum Kaax (Mexico) *see* Yum Caax.

Yumbalamob (Maya People, Yucatan)
Protectors. The ancient Yumbalamob are deities who protect Christians. They reside in the first heaven above the earth. The legend is similar to that of Tezcatlipoca in that they guard entrances and crossroads. *See also* Tezcatlipoca.

Yumchakob (Maya People, Mexico)
Also known as: *Nukuchyumchakob.*
Yumchakob is an ancient white-haired god who is fond of smoking. He produces rain and protects mortals. Yumchakob resides in the sixth of seven heavens which is ruled by the Christian god El Gran Dios, who might be Kukulcan. Kukulcan also has white hair and likes to smoke. Compare the Yumchakob to the Chacs. *See also* Kisin; Nohochacyum.

Yun Chung Chun (China)
God of clouds. One of the Nine Songs. *See also* Nine Songs.

Yun-T'ung (China)
Also known as: *Little Boy of the Clouds.*
God of clouds. Generally found with Lei-kung, Yu-tzu and Feng-po.

Yuncemil (Maya) *see* Acat; Becabs.

Yurlunggur or Julunggul (Australia) *see* Rainbow Snake.

Yurupari (Brazil, Tupiian people)
Demons. Some people say Yurupareu is a generic term for all evil demons or spirits. Others say Yurupari is god, spirit or ogre of the forest.

Yu'ti (China) *see* Yu Huang.

Yzamna (Maya) *see* Itzamna.

Z

Zababa *(Kish)* Supreme god of gods.

Zabba (Hurrite) God of war.

Zabel (Ugarit) The Lord of the Sea. *See also* Bod-Baal.

Zaden (Armenia)
Also known as: *Zatik.*
God or goddess of Fishermen. Little known deity during the reign of Queen Sathenik of Albania, about 190 B.C.E. May have been a representative of Ishtar. *See also* Zatik.

Zagreus (Greek)
Zagreus is the son of the great god, Zeus, and Persephone, goddess of the underworld. *See also* Dionysus; Sabizios.

Zaguaguaya *Zaquaguayu* (Guarayo People, South America) *see* Abaangui.

Zahgurim (Babylonia)
Zahgurim is a name for Marduk taken from the "Hymn of Fifty Names of Marduk." *See also* Marduk.

Zahhak *Zohak* (Middle Eastern) *see* Zohak.

Zahrim (Babylonia)
Zahrim is a name for Marduk taken from the "Hymn of Fifty Names of Marduk." *See also* Marduk.

Zainab (Islamic)
Zainab is one of the four daughters of Mohammed by his first wife, Khadija. Her sisters are Fatima, Ruqaiyah and Umm Kulthum. Mohammed and Khadija also had two (others say three) sons. *See also* Fatima; Mohammed.

Zairisha *Zari* (Persia)
The archdemons Zairisha and Taurvi degrade men, lead them to failure and cause old age. They are in opposition to the goddess of health, Haurvatat, and the goddess of immortality, Ameretat. *See also* Ameretat; Daevas; Haurvatat.

Zal (Persia)
Hero and deified king. The long legend of Zal depicts him as the father of the hero Rustam. He has adventures similar to those of Hercules. In one of the stories Zal is rescued by the vulture Simurgh, who also saves him in later times from his enemy, Isfandiyar. The bird also heals the wounds of Zal and his horse, Rakhsh.

Zalambur (Islamic)
The son of Iblis, and brother of Awar, Dasim, Sut, and Tir, Zalambur is the demon of dishonesty in business. *See also* Azazel.

Zalgarra (Sumer)
One of the two first ancestors of mankind. The other was Elligarra. *See also* Cosmology of Assur.

Zalmoxis *Salmoxis* (Greek)
Also known as: *Dionysus* (possibly), *Gebelzeizis.*
Zalmoxis is known as a Thracian god. At death's doorsteps, his followers asked him for immortality. Zalmoxis is possibly an epithet of Dionysus. *See also* Bacchus; Dionysus.

Zaltu (Assyro-Babylonia)
Zaltu is a goddess of strife who was created by Ea to complement Ishtar.

Zam-Armatay (Persia) She is an earth goddess.

Zam Zam *Zem Zem* (Islamic)
The prophet Ibrahim abandoned his son Ismail (also called Ishmael) and the child's mother Hajar (also called Hagar), who was his Egyptian slave, in Mecca. Hajar was left with a few dates

www.ebook3000.com

Turn ‘Three Minds into One Mind’ at the Lower Tan Tien, and expand the awareness to the universe. Let yourself be charged by the universe.



Like you are back in the womb.

Tan Tien is like a battery.

Fig. 3.42 *Universe charges Tan Tien power.*

Beware of the Tan Tien and spiral it like universal energy in motion. Feel the heart center spiraling and the crown spiraling. Be aware of the universe spiraling above, below, front, back, left and right. Let all of the sick energy and the negative forces leave the body and go down into the ground for Mother Earth to recycle. Extend the Chi from above, all the way down through the earth and the universe below.



Fig. 3.43 *Be aware of the Lower Tan Tien, Heart Center and Crown spiraling. Feel the Universe is spiraling and charging the Three Tan Tiens.*

and a small amount of water. In her search for more water, she traveled the hilly terrain between Safa and Marwah seven times until she came upon the sacred well Zam Zam. Pilgrims to Mecca still follow her route. *See also* Abram.

Zamama (Babylonian)
Corn, sun, and war deity. He subdued the eagle (storm) with his weapon, Sharur (cyclone). He was later identified with Marduk. *See also* Marduk.

Zamba (Cameroons, Africa)
Creator. He created the earth and made it his residence. He has four sons: N'Kokon, Otukut, Ngi, and Wo. He is probably the same as Zambi.

Zambi (Angola, Africa)
Supreme being. He lives in the sky and is connected with a flood legend. He is the supreme judge of the dead. Zambi may be the same or similar to Zamba (q.v.)

Zamin (Persian)
Some think that Zamin and the Greek Semele are Zemelo, an ancient earth goddess of the Phrygians. *See also* Semele.

Zamna (Yucatan) *see* Itzamna.

Zanaharibe (Madagascar) *see* Zanahary.

Zanahary (Madagascar)
Also known as: *Andriamanitra, Zanaharibe.*
Supreme god. Zanaharibe is supreme over the Zanahary hierarchy. There are many Zanahary deities, both good and bad, and they all were instrumental in creating earth and mankind.

Zanaru (Assyro-Babylonian)
An name for Ishtar, meaning "Lady of the Islands."

Zandagahih (Zoroastrian; Persia)
Zandagahih is another name for the "Bundahish," an important Zoroastrian work. For details *see* Bundahish.

Zaphon, Mount *Tsaphon* (Ugaritic)
Sacred Mountain. *See also* Baal; Yam-Nahar.

Zapotec Quetzalcoatl (Mexico) *see* Coqui-Xee.

Zaqar *Zakar* (Babylonia, Sumer)
Also known as: *Dzakar.*
Zaqar, the god Sin's messenger, brings messages from the god, to mortals through dreams.

Zaramama (Peru) Grain Mother. *See also* Mama Zara.

Zarathustra Spitama (Persia) A name for Zoroaster (q.v.).

Zari (Persia) *see* Daevas.

Zarik (Persia)
Zarik is one of the evil spirits created by Ahriman to be his assistant. *See also* Darvands.

Zarpandit (Assyro-Babylonian) *see* Zerpanitum.

Zarpanit (Assyro-Babylonian) *see* Zerpanitum.

Zarvan-akarana (Persian) *see* Zurvan.

Zarya (Slavic) *see* Zorya.

Zatik (Armenia)
Also known as: *Zaden.*
Little known god or goddess of vegetation. Probably a misspelling of the Iberian god of fishermen named "Zaden." Possibly associated in some way with Ishtar. Some say Zaden may have been a representative of Ishtar. In some versions Zatik appears related to the Palestinian god Sedeq or possibly the Babylonian sons of the god Shamash who were called Kettu and Misharu. These were later identified as Sydyk and Misor. *See also* Zaden.

Zcernoboch (Slavic) *see* Chernobog.

Zcernoch (Slavic) *see* Chernobog.

Zd (Slavic) *see* Shahpet.

Zduh *Zduhacz* (Slavic)
Zduh is the soul or spirit that leaves the body of a sleeping person or animal at night. During its travels, it engages in battles and could be killed. *See also* Domovoi; Kikimora.

Zduhacz (Slavic) *see* Zduh.

Zehuti (Egypt) *see* Djehuti Orzehuti; Thoth.

Zelos *Zelus* (Greek)
"Zeal." "Jealousy." Zelos is the son of the Titan Pallas and the Oceanid Styx. *See also* Styx.

Zelus (Greek) *see* Zelos.

Zem Zem (Islamic) *see* Zam Zam.

Zemelo (Phrygian)
Zemelo is an ancient earth goddess thought by some to be the fore-runner of the Greek Semele. *See also* Semele.

Zemes *Zems, Zemi, Zemis* (North America, South America)
Spirits. Believed to be intermediaries between the people and their god. This god can be considered both singular and plural. The people pray to the Zemes for rain or sun and in some versions the Zemes help lessen pain for women during the birth process. *See also* Guamaonocon; Iella; Iocauna.

Zemina *Sieroji Zemele, Zemyna, Zemynele* (Lithuania)
An earth goddess, she is the source of all life. Particular attention is given to her at the birth of each child. She is associated with plant life, particularly the spruce, oak, and linden trees.

Zempat (Prussian) God of earth and cattle.

Zemyna (Lithuania) *see* Zemina.

Zemynele (Lithuania) *see* Zemina.

Zend (Persia)
A translation and exposition of the *Avesta* in a form of Middle Persian used in Zoroastrian literature of the 3rd to 10th centuries, known as Pahlavi.

Zend-Aves'ta The *Avesta* together with the Zend.

Zeniari (Japan)
A name for Benten, goddess of the sea and goddess of good luck. *See also* Benten.

Zephyr (Greek) *see* Zephyrus.

Zephyros (Greek) *see* Zephyrus.

Zephyrus *Zephyr, Zephyros;* (Greek)

Also known as: *Caurus, Favonius* (Roman), *West Wind.*

God of the west wind. Zephyrus is the son of Astraeus (starry night) and Eos, goddess of dawn. He is the mild and gentle West Wind who resides in a cave in Thrace with his brother and close companion, Boreas, the North Wind. Their siblings are Notus, the south wind, and Eurus, the southeast wind. Zephyrus and his mate, the athlete Chloris, also known as Flora, have a son, Carpus (fruit). He is also the father of Achilles' immortal horses, Xanthus and Balius, by the Harpy Podarge. Zephyrus is held responsible by some writers for his jealousy and the subsequent death of the beautiful young man, Hyacinthos, who adored Apollo and was turned into a hyacinth or a lily. Zephyrus, who began life as a wild wind and deity, turned mellow over the years and is described as mild and gentle with flowers in his lap. He is comparable to the Roman Favonius. Compare to Fu-jin (Japan). *See also* Aeolus; Boreas; Chimaera; Chloris; Eos; Harpies; Hyacinthos.

Zeraili (Africa) *see* Azazel.

Zerbanit (Assyro-Babylonia) *see* Zerpanitum.

Zerbanitu (Assyro-Babylonia) *see* Zerpanitum.

Zerpanitum (Assyro-Babylonia)

Also known as: *Beltiya, Gamsu, Sarpanit, Zarpandit, Zarpanit, Zerbanitu, Zirbanit.*

Mother goddess. Creator and destroyer. In early times, Zerpanitum was depicted as pregnant and was worshipped as the moon rose. She may be the same as or an aspect of Ishtar and Beltis. Gamsu, a Chaldean sea goddess, eventually assimilated with Zerpanitum. *See also* Beltis; Gasmu; Ishtar.

Zervan (Persia) *see* Zurvan.

Zetes and Calais (Greek)

Also known as: *Boreadae, Boreades, Prodromes.*

Zetes and his twin Calais are the sons of Boreas (also known as Aquilo), the north wind, and the river nymph Oreithyia, who is the daughter of Erechtheus and Praxithea. Their siblings are Cleopatra, Haemus and Chione. The twins have wings that sprouted when they reached puberty although it is also said that their father presented the wings to them before they sailed on the Argo. Zetes and Calais are credited with saving the life of their brother-in-law, the old and starving king Phineus of Thrace, who had been beset by the wretched winged creatures, the Harpies. In some versions of this myth, the twins chased the monster birds through the sky and, unable to capture them, died of exhaustion. A more popular rendition is that they pursued their prey to the islands of Strophades and were told by either Hermes or Iris to desist with the promise that the Harpies would not trouble Phineus again. Some say it was their sister, Cleopatra, the wife of Phineus, whom they rescued. In one tale, Phineus imprisoned Cleopatra and her children because of the jealousy of another of Phineus' wives. They met their fate through Heracles who had heard that the twins were responsible for encouraging their shipmates to abandon him in Mysia. As the twins were en route home from the funeral games of Pelias, Heracles killed them with his bow and arrows at Tenos. After death the twins became the Prodromes or winds from the northeast. When Boreas the north wind blew, one of the two pillars marking their graves would sway. Zetes and Calais have purple wings or purple hair. Compare to storm deities; Chimaera; Harpies. *See also* Argonauts; Boreas; Phineus.

Zethus (Greek)

Zethus is the son of Zeus and Antiope and the twin brother of Amphion. Abandoned at birth, he later married either Thebe or Aedon, the daughter of Pandareus, and became the father of Itylus. Zethus shared the kingship of Thebes with his brother, Amphion. Although they were opposites in many ways, the twins appeared to share their duties well. Zethus was known for his agricultural abilities and his brother for his musical abilities. Aedon accidentally killed their son, Itylus, and she turned into a nightingale. It is said that Zethus died of a broken heart. *See* Antiope for details of his mother's life and his birth. For additional information about his relationship with his brother, *see* Amphion; Thebe. *See* Aedon for details about the death of Itylus.

Zeus (Greek)

Also known as: *Amen* (Egyptian), *Ammon* (Egyptian), Basileus (the king), *Beelsamin* (Early Phoenician), *Deipatyros* (Illyrians), *Dyaus Pitar* (Aryan), *Gamelios* (God of Marriage), *Herkeios* (Protector of the Home), *Jove* (Roman), *Jupiter* (Roman), *Ktesios* (Guardian of Property), *Mechaneus* (manager and contriver), *Meilichios* (Zeus in Serpent Form), *Moiragete* (guide of the Moirae), *Panhellenius* (God of all Greeks), *Phyxios* (God of Escape), *Soter* (Father and Savior of Man), Terminalius (protector of boundaries), *Tiu* (German), *Zeus Chthonios* (God of Earth and Fertility).

Father of gods and men, god of the sky, and lord of Olympus, where he resides, Zeus is founder of the Olympian dynasty. Connected with the upper air, he is the god of all that is high, including mountain tops, eagles, oaks and thunderstorms. He was brought up in a cave on Mount Ida to be safe from his father, Cronus, the god of the world and time, who had swallowed his other children. Rhea, the mother of the gods and Zeus' mother, left him in the care of a nurse on Crete. The name of the nurse who hid the baby is given variously as Neda, Helice, Aega, Cynosura, Adrastea, Ida or Adamanthea. Zeus' siblings are Hades, the king of the underworld; Hera, the queen of heaven, whom Zeus seduced in the form of a cuckoo or a hummingbird; Hestia, the virginal goddess of the hearth; Poseidon, god of the sea; Demeter (also known as Ceres), the goddess of agriculture, who was also seduced by Zeus. Cronus had bound the one-eyed, monsters known as the Cyclopes. Zeus liberated them, and was rewarded by them with the gift of thunder and lightning. His thunderbolts were forged by the talented smith Hephaistos. The Cyclopes were invaluable assistants to Zeus as he traveled his path to become the leader of the gods. Using his thunder and lightning as weapons he conquered the race of giants known as the Titans (who are the siblings of the Cyclopes and the Hecatonchires). Zeus turned them upon the goddess of the earth Gaea, whom he deposed from her throne after a struggle with Typhoeus, the son of Gaea and Tartarus (who was born from Chaos). With the help of the Cyclopes (others say it was his mother Rhea and his first wife Metis, a daughter of Oceanus

www.ebook3000.com

and Tethys, who helped him) he defeated Cronus and the other Titans and thus became master of the world. He gave the sea to his brother Poseidon to rule and the underworld to his other brother, Hades, reserving the heavens for himself. Zeus successfully fought two battles to keep his throne. One engagement was with the screaming monster whirlwind, Typhon, who has a hundred dragon heads that shoot flames from his nostrils and eyes. The other battle was with the most powerful of the giants, Enceladus. Both opponents had been sent by Gaea to punish Zeus. As Metis, the first wife of Zeus, was residing in his stomach, he married again. His second wife, the Titan Themis, the personification of order and justice, gave birth to daughters who are the seasons, personified as the Horae; the goddess of fate, personified as the Moirae; and the goddess of justice, Astraea. Another mate of Zeus was the Oceanid Eurynome, who gave birth to the Graces and personifies beauty and grace. By his sister, Demeter, Zeus fathered Persephone, goddess of the underworld. Persephone later succumbed to her father in the form of a snake and gave birth to Zagreus. The other child of Persephone and Zeus is Dionysus, who as an embroyo was swallowed by Zeus and placed in the body of Semele. Other wives and mistresses included Mnemosyne, the personification of memory and the mother of the Muses; Leto, a Titan, who became the mother of Apollo and Artemis; Hera, whom Zeus seduced in the form of a cuckoo or hummingbird and who gave birth to Ares, Hebe, Eileithyia, and possibly the god of fire, Hephaistos. It is generally agreed that his sister Hera is his important mate.

By Dione he was the father of the goddess of love Aphrodite (possibly). His affairs with mortal women produced more children. Disguised as Amphitryon, the spouse of Alcmene, she bore him Hercules. With Danae he fathered Perseus. Disguised as a white bull he kidnapped and had sex with Europa. She birthed Minos, Rhadamanthus, and Sarpedon. With Io he became the father of Epaphus. Disguised as a swan he seduced Leda. She hatched Castor and Pollux and Helen. He is also the father of Arcas by Callisto. Some of his other lovers were Aegina, Calliope, Carme, Electra, Eos, Eris, Laodamia, Leda, Niobe, Pandora, Selene, Semele, Styx, Tethys, Thalassa and Thymbris.

The ancient Persians called the sky Zeus. They climbed the highest peaks to offer sacrifices to Zeus. The Olympic Games were held every four years on Mt. Olympus in his honor. Zeus was possibly worshiped as early as 1500 B.C.E. Worshiped all over Greece, his principal shrines were at Dodona and Olympia. Zeus possesses the goatskin shield known as the aegis. His sacred bird is the eagle. Zeus is usually depicted seated on a throne, with thunderbolts in one hand and a scepter of cypress in the other, wearing a wreath of olive or myrtle. Most legends of Zeus parallel those of Jupiter (Roman). Compare Zeus to Dyaus (India); the Vedic god Vishnu; the Norse gods Odin, and Thor. *See also* Acrisius; Adrastia; Adrestus; Aegina; Aegipan; Aeolus (A); Aeolus (B); Agdistis; Aglaia; Amaltheia; Amen (A); Amen (B); Anchises; Antiope; Apis (A); Ares; Argus (A); Argus (C); Artemis; Asopus; Astrae; Atalanta; Bellerophon; Calypso; Chaos; Cian; Corybantes; Cronus; Cybele; Cyclops; Danae; Enceladus; Eris; Eurynome; Fates; Graces; Harmonia (A); Harpies; Hecatonchires; Hephaistos; Hermaphroditus; Hesperides; Hestia; Horae; Ino; Ixion; Lamia; Leto; Metis; Minos; Moirae; Muses; Naiads; Nephele; Niobe (B); Oceanus; Orion; Persephone; Perseus; Phineus; Poseidon; Rhadamantus; Rhea; Sarpedon (A); Sarpedon (B); Semele; Serapis; Sinope; Sisyphus; Styx; Tartarus; Tethys; Themis; Titans; Typhon.

Zhag-pa-ma (Tibet)
Also known as: *Pashadhari* (India).
This sow-headed goddess, associated with fondness, is a Shakti, and with her mate, Yamantaka, is the Door-Keeper of the South. Her other name, Pashadhari, indicates that she is a noose-bearer. *See also* Kinkini-Dhari; Shakti; Yamantaka.

Zhal-zas-ma (Tibet) *see* Amoghasiddhi.

Zi (Sumer)
Also known as: *Sige, Ziku.*
Spirits. As the ancient spirits, the Zi, became important, they were given new names. In general, they are controlling life spirits of everything in nature. Sometimes, Zi is singular and known as a goddess of life. Ziku is one of the names bestowed upon Marduk by Anu. *See also* Marduk; Sigi; Ti.

Ziapsu (Sumer) *see* Dumuzi.

Zib (Babylonia)
Zib is Ishtar as the evening star who generates desire. *See also* Ishtar.

Zigarun (Akkadia) *see* Apsu.

Ziku (Sumer, Babyloni) *see* Marduk; Zi.

Zima (Slavic) Mother Winter.

Zin (Nigeria, Africa)
Also known as: *Zin-Kibaru.*
Water spirits. The Zin, who are depicted as dragons, are associated with musical instruments. The Zin were possibly adapted from the Islamic Jinn. *See also* Zinkibaru.

Zin-Kibaru (Africa) *see* Zinkibaru.

Zinkibaru *Zin-Kibaru* (Songhoi, Africa)
Also known as: *Zin.*
A djinn, Zinkibaru is the blind Master of Fish.

Zio (Teutonic) *see* Tyr.

Zipacna (Guatemala, Central America)
Deity of the dawn. Every morning, Zipacna slays four hundred stars. Every evening, Hunahpu restores the stars to the sky. *See also* Gukup Cakix; Hunahpu; Ixbalanque.

Zipaltonal (Nicaragua)
Creator. Zipaltonal and her husband, Tamagostad, created earth and everything on it. Good souls go to them in their heaven. Bad souls go to Mictlantecuhtli (q.v.). *See also* Masaya.

Zirna (Etruscan)
She is a moon goddess who is depicted with a half moon hanging from her neck. Her companion is the love goddess Turan.

Zisa (German) *see* Cisa.

Zisi (Babylonia) *see* Marduk.

Ziu (Teutonic)
Also known as: *Mars, Othin* (possibly).
Ziu is thought to be the original father and sky god among the Teutonic People. He is identified with sun symbols, the circle, the wheel, the swastika. The Romans identified Ziu as Mars. *See also* Tyr; Zeus.

Ziukkinna (Babylonia) *see* Marduk.

Ziusudra (Sumer)
Also known as: *Utnapishtim* (Babylonia).
He is the pious king of Sippar, a mortal who was instructed by Enki to build a boat to save himself and others, along with some animals, from the great flood. In later times in Babylonian mythology, Ziusudra was known as Utnapishtim. *See also* Ea; Enki; Gilgamesh; Noah; Urshanabi; Utnapishtim.

Ziv (Teutonic)
Also known as: *Thingsus, Tyr.*
God of Assembly. *See also* Tyr.

Ziva (Slavic)
Also known as: *Siva, Zywie* (Polish).
Goddess of life.

Zivena *Vitzcatl* (Aztec People, Mexico) Highest heaven.

Ziw (Norse) *see* Tyr.

Ziz *Ziv* (Hebrew)
Ziz, an ancient giant bird, devours vegetation.

Zleja (Lithuania) Goddess of high day. *See also* Breksta.

Zluidni (Slavic) Malicious fairies.

Zmek (Slavic)
Also known as: *Cmok, Smok.*
Zmek, a guardian angel, has as his symbol the snake or serpent. *See also* Tsmok.

Zocho (Japan) *see* Zocho-Ten.

Zocho-ten (Buddhist; Japan)
Also known as: *Virudhaka, Zocho.*
Zocho-ten is one of the four heavenly kings known as Shi Tenno. As a guardian of the four directions, established to ward off evil spirits, he is responsible for the south in some versions and the west in others. He is known as the destroyer of evil, dispenser of good and a god of growth. Zocho-ten is shown dressed as a soldier, wearing a ferocious expression and holding a sword and a shield. Compare to the Nio guards (q.v.). *See also* Bishamon-Ten; Jikoku-Ten; Komoku-Ten; Shi Tenno; Virudhaka (India).

Zohak *Zahak, Zahhak* (India, Iran, Persia)
Deified mortal. Demon. Said to be the incarnation of the druj, Azhi Dahaka. Not originally evil, he came under the spell of Ahriman (Angra Mainyu) and later vanquished (or killed) Jemshid (another name for Yima). Zohak introduced meat to the people who were always vegetarians. The demon Zohak was later defeated and chained to a mountain by Feridun. In some interpretations, Zohak, the drought demon, was slain by Thraetaona. Zohak is not a pleasant sight. He has serpents growing from his shoulders. *See also* Azhi Dahaka; Yima.

Zonget (Siberia)
Zonget is the ancient goddess of hunting and ruler of all bird and animal life and ruler of all who hunt.

Zoroaster (Persia)
Also known as: *Ardusht, Mazdayasni-Zaroshtis, Zarathustra Spitama.*
He is said by some to have been born c. 590 B.C.E. Others place his birth at various points between 1000 and 600 B.C.E. Conceived by a ray of light that entered his mother's bosom, he was born of a virgin birth. It is said that he laughed at birth. His mother is Dughda (also known as Dughdhova), and his putative father is Pourushaspa. A light hero and prophet, Zoroaster had three wives, three sons, and three daughters. Yima's Khvarenanh (Glory) was transferred to him. The Ameshas Spenta appeared to him with revelations. Ahura Mazda revealed the path of truth to him on Mount Elburz and he founded Zoroastrianism. His rule of moral conduct is good thought, good word, and good action. During his life on earth, he performed many miracles, and endured temptation by the arch-demon Angra Mainyu. Eventually slain by demons, Zoroaster descended to the underworld and three days later ascended to heaven. He left his sperm in Lake Kasu where it is preserved. It is guarded by 99,999 Fravashis. Every millennium for three millenniums, a virgin bathing in the lake will receive his sperm and give birth to a savior. The first savior will be Aushedar who is known as the developer of righteousness. The second savior will be Aushedar-mah and the third savior, Soshyant. *See also* Ahura Mazda; Amesha Spentas; Angra Mainyu; Avesta; Fravashi; Haoma; Khvarenanh; Spenta Armaiti; Vohu Manah; Yazatas; Yima.

Zoroastrian — Creation Legend *see* Ahura Mazda.

Zorya, The (Slavic)
Also known as: *Aurora,* (Greek, Roman), *Zarya* (Slavic).
Guardians. Dawn goddesses. The Zorya are two or three goddesses who guard the universe. They are either Zvezda Dennitsa or Zorya Utrennyaya, the morning star, and Zvezda Vechernyaya, the evening star, and the midnight Zorya. They keep watch over the hound chained to the constellation of the Little Bear for if the chain should break it would be the end of the world. In some legends Dennitsa replaces the Sun as wife of Myesyats (moon). Dennitsa is almost equal to the greatest gods. The Zorya are the same as the Auroras. *See also* Perun.

Zorys, The Two (Serbian) *see* Auroras, The Two.

Zotzilaha Chimalman (Maya)
He is a bat god who is the same as Camazotz (q.v.).

Zu (Mesopotamia)
Also known as: *Anzu, Imgig.*
A minor deity, and perhaps an underworld god, Zu is the son of the bird goddess Siris. He lived with his wife and children, and worked as the valet of Ellil, the supreme god. Zu stole the Tablets of Fate from Ellil while he was washing. Ea, god of the earth and waters, persuaded the goddess of the womb, Belet-Ili, to conceive and deliver a divine hero who could overcome Zu. Ninurta was born, and fulfilled his destiny by recovering the Tablets of Fate. In another record of this myth, we are told that the gods were dismayed when the theft occurred but none volunteered to pursue Zu. Finally, Lugalbanda, the father of

www.ebook3000.com

Gilgamesh, undertook the task and killed Zu. In yet another record, *The Hymn of Ashurbanipal*, it is said that Marduk crushed Zu's skull. Zu and Siris are described as enormous birds who breathe fire and water. Zu is also depicted as a lion-headed eagle. *See also* Ea; Marduk.

Zulu People — Creation Legend (Africa) *see* Unkulunkulu.

Zulum (Babylonia) *see* Marduk.

Zumiang-nui (India) *see* Shuzanghu.

Zuni People — Creation Legend (North America) *see* Awonawilona; Shiwanni and Shiwanokia.

Zunto-zang-po (Tibet) *see* Samantabhadra.

Zurvan (Zurvanites; Persia)

Also known as: *Zarvan-akarana, Zervan* (this spelling is from a later sect of Zoroastrians), *Zrvan Akarana.*

Before the creation of heaven and earth, Zurvan, generally believed to mean "boundless time," existed alone. Androgynous, Zurvan desired a son. After offering sacrifices for a thousand years, Zurvan doubted that his desire would be fulfilled. In this moment of doubt, twins were conceived, Ohramazd and Ahriman. Ohramazd represented the fulfillment of his desire (all good), and Ahriman represented his doubt (evil). In Armenia, Zervan, Titan, and Japhet were worshiped, possibly the same as Shem, Ham, and Japhet of the Book of Genesis. Zurvanism is thought by some to be pre–Zoroastrian. The myths of the Zurvanites were incorporated into Zoroastrianism. *See also* Ahura Mazda; Angira Mainyu; Japhet.

Zvezda Dennitsa (Slavic)

Goddess of the Morning Star. According to some she and her sister represent the planet Venus. This goddess tends the horses of the sun. She may be linked with Zorya. *See also* Zvezda Vechernyaya.

Zvezda Vechernyaya (Slavic)

Goddess of the Evening Star. Sister of Zvezda Dennitsa. Possibly a moon deity.

Zvoruna (Lithuania) Goddess of the hunt and of animals.

Zyed (Persia) *see* Yazatas.

Zywie (Polish) *see* Ziva.

www.ebook3000.com

BIBLIOGRAPHY

Aldington, Richard and Delano Ames, trans. *Larousse Encyclopedia of Mythology*, 3rd impression. London: Paul Hamlyn, 1960.

Allen, Louis A. *Time Before Morning: Art and Myth of the Australian Aborigines.* New York: Crowell, 1975.

Altizer, Thomas J. J. *Truth, Myth, and Symbol.* Englewood Cliffs, NJ: Prentice-Hall, 1962.

Andersen, Johannes Carl. *Myths and Legends of the Polynesians.* New York: Farrar and Rinehart, 1931.

Andrews, Lynn V. *Windhorse Woman: A Marriage of Spirit.* New York: Warner Books, 1989.

Anton, Ferdinand. *Ancient Mexican Art.* London: Thames and Hudson, 1969.

Arnott, Kathleen. *African Myths and Legends, retold by Kathleen Arnott.* New York: Walck, 1963.

Asimov, Isaac. *Asimov's Guide to the Bible, The Old Testament.* New York: Equinox Books, Published by Avon Books, a division of the Hearst Corp., 1971.

Bachofen, J. J. *Myth, Religion, & Mother Right.* Bollingen Series LXXXIV, Princeton, NJ: Princeton University Press, 1973.

Balin, Peter. *The Flight of Feathered Serpent.* Venice, CA: Wisdom Garden Books, 1978.

Barbeau, Marius. *Huron and Wyandot Mythology; with an Appendix Containing Earlier Published Records, by C. M. Barbeau.* Ottawa: Goverment Printing Bureau, 1915.

Baumgartner, Anne S. *Ye Gods!* New Jersey: Lyle Stuart Inc., 1984.

Beck, Mary Giraudo. *Heroes and Heroines: Tlingit-Haida Legend.* Anchorage: Alaska Northwest Books, 1989.

Beckwith, Martha. *Hawaiian Mythology.* Honolulu: University of Hawaii Press, 1970.

Bell, Robert, E. *Women of Classical Mythology: A Biographical Dictionary.* Santa Barbara, CA: ABC-CLIO, 1991.

Bierhorst, John. *Mythology of South America.* New York: William Morrow and Company Inc., 1350 Avenue of the Americas, 1988.

_____. *The Mythology of Mexico and Central America.* New York: William Morrow and Company, 1990.

_____. *The Mythology of North America.* New York: William Morrow and Company, 1985.

Birch, Cyril. *Chinese Myths and Fantasies.* London: Oxford University Press, 1961.

Blackwell, Thomas. *Letters Concerning Mythology.* (The Printer or distributor may be J. Oswald, whose advertisement appears on the last page.) DNB attributes the printing to Andrew Millar, London, c. 1748.

Branston, Brian. *Lost Gods of England.* England: Oxford University Press, 1974.

Bratton, Fred Gladstone. *Myths and Legends of the Ancient Near East.* New York: Crowell, 1970.

Bray, Frank Chapin. *Bray's University Dictionary of Mythology.* New York: Thomas Y. Crowell Co., 1964.

Briggs, Katharine. *An Encyclopedia of Fairies.* New York: Pantheon Books, 1976.

Brinton, Daniel Garrison. *American Hero-Myths: A Study in the Native Religions of the Western Continent.* Philadelphia: H. C. Watts, 1882.

_____. *Religions for Primitive Peoples.* New York; London: G. P. Putnam's Sons, 1897.

Brock, Sebastian P. *The Syriac Vewsion of the Pseudo-Nonnos Mythological Scholia.* England: Cambridge University Press, 1971.

Bruce S., Roberto D. *Lacandon Dream Symbolism: Dream Symbolism and Interpretation Among the Lacandon Mayas of Chiapas, Mexico.* 2 vols. Mexico: Ediciónes Euroamericanas, 1975–79.

Brundage, Burr Cartwright. *The Fifth Sun: Aztec Gods, Aztec World.* Austin: University of Texas Press, 1979.

Bryant, Page. *The Aquarian Guide to Native American Mythol-*

ogy. London, England: The Aquarian Press, an Imprint of Harper Collins, 1991.

Budge, E. A. Wallis. *Amulets & Superstitions.* New York: Dover Publications, 1978.

_____. *The Gods of the Egyptians.* Volumes I and II. New York: Dover Publications, 1969.

Bulfinch, Thomas. *Bulfinch's Mythology, Illustrated Edition.* New York: Avenel Books, 1978.

Burland, C. A. *The Gods of Mexico.* New York: Putnam, 1967.

Burland, Cottie. *North American Indian Mythology.* New York: Tudor Publishing Company, 1965.

Campbell, Joseph. *Creative Mythology: The Masks of God.* New York: Penguin Books Ltd., 1968.

_____. *Occidental Mythology: The Masks of God.* New York: Penguin Books Ltd., 1976.

_____. *Oriental Mythology: The Masks of God.* New York: Penguin Books Ltd., 1976.

_____. *Primitive Mythology, The Masks of God.* New York: Penguin Books Ltd., 1976.

_____, with Bill Moyers. *The Power of Myth.* New York: Anchor Book, 1991.

Carrasco, David. *Quetzalcoatl and the Irony of Empire: Myths and Prophecies in the Aztec Tradition.* Chicago: University of Chicago Press, 1982.

Caso, Alfonso. *The Aztecs: People of the Sun.* Norman: University of Oklahoma, 1958.

Cassirer, Ernst. *Philosophie der Symbolischen Formen.* English, *The Philosophy of Symbolic Forms.* Translated by Ralph Manheim. 3 vols. New Haven: Yale University Press, 1953–57.

Cavendish, Richard, ed. *Man, Myth and Magic: The Illustrated Encyclopedia of Mythology, Religion and the Unknown.* Marshall Cavendish, 1983.

Ceram, C. W. *Gods, Graves, & Scholars: The Story of Archaeology.* Translated from the German by E. B. Garside and Sophie Wilkins. (Second, revised and substantially enlarged edition.) A Borzoi Book. Alfred A. New York: Knopf, 1968.

Chamberlain, Basil Hall. *The Language, Mythology, and Geographical Nomenclature of Japan Viewed in the Light of Aino Studies.* Toyko: Imperial University, 1887.

Chant, Joy. *The High Kings.* Toronto; New York: Bantam, 1983.

Christie, Anthony. *Chinese Mythology.* New York: Peter Bedrick Books, 1983.

Cirlot, J. E. *A Dictionary of Symbols.* (Translated from the Spanish) New York: Routledge & Kegan Paul (English translation). Published by Philosophical Library, 1962.

Clark, R. T. Rundle. *Myth and Symbol in Ancient Egypt.* London: Thames and Hudson Ltd, 1959.

Coffer, William E. *Spirits of the Sacred Mountains: Creation Stories of the American Indians.* New York: Van Nostrand Reinhold Co., 1978.

Conger, Jean. *The Velvet Paw: A History of Cats in Life, Mythology, and Art.* New York: I. Obolensky, 1963.

Conrad, Jack Randolph. *The Horn and the Sword: The History of the Bull as Symbol of Power and Fertility.* New York: Dutton, 1975.

Conway, Moncure Daniel. *Demonology and Devil-lore.* London: Chatto, 1879.

Coomaraswamy, Anadad K. & Sister Nivedita. *Myths of the Hindus & Buddhists.* New York: Dover Publications Inc., 1967.

Coyajee, Sir Jehanigir Cooverjee. *Cults & Legends of Ancient Iran & China.* Fort Bombay: J. B. Karani's Sons, 1936.

Craigie, Sir William A. *The Religion of Ancient Scandinavia.* Freeport, NY: Books for Libraries Press, 1969.

Cross, Frank Moore. *Canaanite Myth and Hebrew Epic: Essays in the History of the Religion of Israel.* Cambridge, MA: Harvard University Press, 1973.

Cushing, Frank Hamilton. *Outlines of Zuni Creation Myths.* New York: AMS Press, 1976.

Davidson, H. R. Ellis. *Gods and Myths of Northern Europe.* New York: Penguin Books Ltd., 1975.

Delphian Course, The. *The Delphian Society.* Indiana: W.B. Conkey Co., 1913.

Deren, Mary. *Divine Horsemen: The Living Gods of Haiti.* London; New York: Thames and Hudson, 1953.

Diner, Helen. *Mothers and Amazons.* New York: Doubleday Anchor, 1938.

Diop, Cheikh Anta. *The African Origin of Civilization, Myth or Reality.* Edited and translated by Mercer Cook. Chicago, IL: Lawrence Hill Books, 1974.

Dixon, Roland Burrage. *Oceanic Mythology.* Boston: Marshall Jones Company, 1916.

Dunne, John S., C.S.C. *The City of the Gods: A Study in Myth and Mortality.* New York: The Macmillan Company; London: Collier-Macmillan Limited, 1965.

Duran, Fray Diego (a translation). *Book of the Gods and Rites and the Ancient Calendar.* Norman: University of Oklahoma Press, 1971.

Durdin-Robertson, Lawrence. *God the Mother.* Wexford, Ireland: Cesara Publications, Redmond Print.

_____. *The Goddesses of Chaldea, Syria and Egypt.* Dublin, Ireland: Cesara Publications, 1975.

_____. *The Goddesses of India, Tibet, China, and Japan.* Dublin, Ireland: Cesara Publications, 1976.

Dwight, M. A. *Grecian and Roman Mythology.* New York: A.S. Barnes & Co., 1856.

Ecun, Oba. *Ita Mythology of the Yoruba Religion.* Miami, FL: Obaecun Books, 1989.

Edda (the younger). Selections. The Prose Edda of Snorri Sturluson: Tales from Norse Mythology. Introduced by Sigurdur Nordal; Selected and Translated by Jean I. Young. Berkeley: University of California Press, 1954.

www.ebook3000.com

Eisner, Robert. *The Road to Daulis: Psychoanalysis, Psychology, and Classical Mythology.* Syracuse, NY: Syracuse University Press, 1987.

Eliade, Mircea. *Australian Religions: An Introduction.* Ithaca and London: Cornell University Press, 1973.

_____. *Gods, Goddesses, and Myths of Creation.* New York: Harper & Row, Publishers, Inc., 1974.

Elmendorf, William Welcome. *Structure of Twana Culture.* New York: Garland Pub. Inc., 1974.

Evslin, Bernard. *Gods Demigods and Demons.* New York: Scholastic Book Services, 1975.

_____, and Hoopes. *Heros and Monsters of Greek Myth.* New York: Scholastic Book Services, Fourwinds Press, 1967.

Farnell, Lewis Richard. *Greece and Babylon: A Comparative Sketch of Mesopotamian, Anatolian and Hellenic Religions.* Edinburgh: T. & T. Clark, 1911.

Farugi, Isma'il Ragial, ed., David E. Sopher, map ed. *Historical Atlas of the Religions of the World.* New York: Macmillan Publishing Co., Inc., 1974.

Feibleman, James K. *Understanding Oriental Philosophy.* New York: A Mentor Book, New American Library, 1976.

Fell, Barry. *America B.C.* New York: Pocket Books, Simon & Schuster, Inc., 1989.

Fiske, John. *Myths and Myth-makers: Old Tales and Superstitions Interpreted by Comparative Mythology.* Boston: Houghton, 1900.

Flornoy, Bertram. *The World of the Inca.* (Translated from the original French, *L'Aventure Inca,* by Winifred Bradford.) New York: The Vanguard Press, 1956.

Fontein, Jan. *The Sculpture of Indonesia.* Washington, DC: National Gallery of Art, 1990.

Frawley, David. *Gods, Sages and Kings, Vedic Secrets of Ancient Civilization.* Salt Lake City, Utah: Passage Press (a division of Morson Publishing), 1991.

Frazer, Sir James George. *The Golden Bough: A Study in Magic and Religion.* New York: Abridged Edition, Collier Books, Macmillan Publishing Company, 1963.

_____. Edited and with notes and foreword by Dr. Theodor H. Gaster. *The New Golden Bough: A New Abridgment of the Classic Work.* New York: Criterion Books, 1959.

Furlong, J. G. R. *Encyclopedia of Religions.* 3 vols. New York: University Books Inc., 1964.

_____. *Faiths of Man.* 3 vols. New York: University Books Inc., 1964.

Gardner, Ernest Arthur. *Religion and Art in Ancient Greece.* London and New York: Harper & Brothers, 1910.

Gardner, Robert L. *The Rainbow Serpent: Bridge to Consciousness.* Toronto: Inner City Books, 1990.

Gaster, Theodor H. *The Oldest Stories in the World.* Boston, IL: Beacon Press, 1952.

_____. *Translations of Ancient Near Eastern Dramatic Texts.* New York: Schuman, 1950.

Gifford, Douglas. *Warriors, Gods & Sprits from Central & South American Mythology.* New York: Schocken Books; Vancouver (B. C.): Douglas & McIntyre, 1983.

Glueck, Nelson. *Deities and Dolphins; The Story of the Nabataeans.* New York: Farrar, Straus and Giroux, 1965.

Goldsmith, Elizabeth Edwards. *Life Symbols as Related to Sex Symbolism: A brief study into the origin and significance of certain symbols which have been found in all civilisations.* N.Y. and London: Pitnam's Sons, 1924.

Goodrich, Norma Lorre. *Ancient Myths.* New York: Meridian, 1994.

_____. *Priestesses.* New York: HarperPerennial, 1990.

Graves, Robert. *The Greek Myths.* 2 vols. New York: Penguin Books, 1985.

_____. *The White Goddess* New York: The Noonday Press, Farrar, Straus and Giroux, 1989.

Gray, John. *Near Eastern Mythology.* New York: Peter Bedrick Books, 1982.

Gray, Louis Herbert, ed. *The Mythology of All Races.* XIII vols. George Foot Moore, consulting editor. Boston: Marshall Jones Company, 1916–32.

Great Religions of Modern Man. 6 vols. New York: George Braziller Publisher, 1961.

Greenway, John. *The Primitive Reader.* Hatboro, PA: Folklore Associates, 1965.

Grey, Sir George. *Polynesian Mythology and Ancient Traditional History of the Maori as told by their Priests and Chiefs.* New York: Taplinger Pub. Co., 1970.

Grimm, Jacob. *Teutonic Mythology.* 3 vols. Translated from the 4th ed., by James Steven Stallybrass. London: G. Bell, 1883–1888.

Guerber, H.A. *The Norseman.* New York: Avenel Books, 1985.

Hamilton, Edith. *Mythology, Timeless Tales of Gods and Heroes.* New York: New American Library, 1969.

Hawkes, Jacquetta. *Man and the Sun.* New York: Random House, 1962.

Hays, H. R. *In the Beginnings.* New York: G. P. Putman's Sons, 1963.

Henderson, Joseph L. and Maud Oaks. *The Wisdom of the Serpent.* Canada: Ambassador Books, 1963.

Hewitt, James Francis Katherinus. *History and Chronology of the Myth-Making Age.* London: J. Parker, 1901.

Highwater, Jamake. *Myth and Sexuality.* New York: NAL Books, 1990.

Hinnells, John R. *Persian Mythology.* London; New York: Hamlyn, 1973.

Hodges, Margaret. *The Other World: Myths of the Celts.* New York: Farrar, Straus and Giroux, 1973.

Hooke, S. H. *Babylonian and Assyrian Religion.* Norman: University of Oklahoma Press, 1963.

Hopfe, Lewis M. *Religions of the World.* Canada: Collier Macmillan Canada, Ltd., 1979.

Horn, Siegfried H., Ph.D. *Seventh Day Adventist Bible Dictionary.* No. 1 of 8 vols. Washington, DC: Review and Herald Publishing Association, 1960.

Hospital, Clifford. *The Righteous Demon: A Study of Bali.* Vancouver: University of British Columbia Press, 1984.

Hultkrantz, Ake. *The Religions of the American Indians.* Translated by Monica Setterwall. Berkeley: University of California Press, 1980.

Hveberg, Harald. *Of Gods and Giants, Norse Mythology.* Translated by Pat Shaw Iversen. Norway: Johan Grundt Tanum Forlag, Office of Cultural Relations, Norwegian Ministry of Foreign Affairs, 4th edition, 1969.

Ions, Veronica. *Indian Mythology.* New York: Paul Hamlyn Publishers, 1968.

James, Edwin Oliver. *Myth and Ritual in the Ancient Near East: An Archeological and Documentary Study.* New York: Praeger, 1958.

James, William. *The Varieties of Religious Experience.* New York: Mentor Books, the New American Library, 1958.

Janson, H. W. *History of Art.* New York: Harry N. Abrams, Inc., 1977.

Jayne, Walter Addison. *The Healing Gods of Ancient Civilizations.* New Haven: Yale University Press, 1925.

Jaynes, Julian. *The Origins of Unconsciousness in the Breakdown of the Bicameral Mind.* Boston, MA: Houghton Mifflin Company, 1976.

Jenness, Diamond. *Indians of Canada.* Canada: Diamond Press, Ministry of Supply and Supplies, 1989.

Jobes, Gertrude. *Dictionary of Mythology, Folklore and Symbols.* 2 vols. New York: Scarecrow Press Inc., 1962.

Jorgensen, Joseph G. *The Sun Dance Religion: Power for the Powerless.* Chicago: University of Chicago Press, 1972.

Jung, Carl G. *Analytical Psychology, Its Theory and Practice (The Tavistock Lectures).* New York: Vintage Books, A Division of Random House, 1970.

_____. *Memories, Dreams, Reflections.* Recorded and Edited by Aniela Jaffe, Translated from the German by Richard and Clara Winston. New York: Vintage Books, a Division of Random House, 1965.

_____. *Symbols of Transformation: An Analysis of the Prelude to a Case of Schizophrenia.* Translated by R. F. C. Hull. Princeton, N.J.: Bollingen Series XX, Second Edition, Princeton University Press, 1976.

_____. *Two Essays on Analytical Psychology.* Translated by R. F. C. Hull. Cleveland Ohio: Meridian Book, The World Publishing Company, 1961.

_____, and M. L. von Franz, Joseph L. Henderson, Jolande Jacobi, Aniela Jaffé. *Man and His Symbols.* Garden City, NY: Doubleday & Company, 1964.

Kalakaua, His Majesty. *Legends and Myths of Hawaii: The Fables and Folk-Lore of a Strange People.* Rutland, VT: Charles Tuttle Co., 1979.

Karanitz, David. *Who's Who in Greek and Roman Mythology.* New York: Clarkson N. Potter, Inc., Publishers, 1975–76.

Keeler, Clyde E. *Secrets of the Cuna Earthmother: A Comparative Study of Ancient Religions.* New York: Exposition Press, Inc., 1960.

Keightley, Thomas. *Mythology of Ancient Greece and Italy.* New York: D. Appleton and Company, 1836.

Kellett, E. *The Story of Myths.* New York: Harcourt, 1927.

King, L. W. *Babylonian Religion and Mythology.* New York: AMS Press, 1976.

King, Noel Q. *Religions of Africa: A Pilgrimage Into Traditional Religions.* New York: Harper & Row, Publishers, 1970.

Kinsley, David R. *The Sword and the Flute, Kali and Krsna, Dark Visions of the Terrible and the Sublime in Hindu Mythology.* Berkeley and Los Angeles: University of California Press, 1975.

Knappert, Jan. *The Aquarian Guide to African Mythology.* Wellingborough, Northamptonshire, England: Aquarian Press, Thorsons Publishing Group, 1990.

_____. *An Encyclopedia of Myth and Legend, Indian Mythology.* Hammersmith, London, England: Aquarian Press, Thorsons Publishing Group, 1991.

_____. *An Encyclopedia of Myth and Legend, Pacific Mythology.* Hammersmith, London, England: Aquarian Press/Thorsons Publishing Group, 1992.

Korean Folklore. Edited by the Korean National Commission for Unesco, Pace International Research, U.S.A. Korea: The Si-Sa-Yong-O-Sa Publishers, Inc., 1983.

Kramer, Samuel Noah. *Mythologies of the Ancient World.* Edited and with an introduction by Samuel Noah Kramer. Garden City, NY: Anchor Books, Doubleday & Company, Inc., 1961.

La Barre, Weston. *The Ghost Dance, Origins of Religion.* Garden City, NY: Doubleday & Company, Inc., 1970.

Larousse World Mythology. New York: Prometheus Press, 1965.

Larson, Geral James, ed. *Myth in Indo-European Antiquity.* Coedited by C. Scott Littleton and Jaan Puhvel. Berkeley: University of California Press, 1974.

Larue, Gerald A. *Ancient Myth and Modern Man.* Englewood Cliffs, NJ: Prentice Hall, 1975.

Leach, Edmund, ed. *The Structural Study of Myth and Totemism.* London: Tavistock Publications, 1967.

Leach, Maria, ed. *Funk & Wagnalls Standard Dictionary of Folklore Mythology & Legend.* New York: Funk & Wagnalls, 1949.

Leon-Portilla, Miguel, ed. *Native Mesoamerican Spirituality: Ancient Myths, Discourses, Stories, Doctrines, Hymns, Poems from the Aztec, Yucatec, Quiche-Maya and Other Sacred Traditions.* New York: Paulist Press, 1980.

Leonard, W. E. *Gilgamish.* New York: Viking Press, 1934.

Lessa, William A. *Tales from Ulithi Atoll, Oceanic Folklore.* Berkeley: University of California, 1961.

Lin, Hsu-tien. *The Nature and Characteristics of Chinese Myths*

www.ebook3000.com

Open the Middle Channel and Perineum

1. Move to the mid-crown point. Touch the point and project your fingers inwards; go deeper, deeper through the middle of your body down to the perineum. Focus on the perineum. Feel the Chi from the universe flow into your perineum. Look for one dot of light. Look into the darkness, the vast darkness, the immense darkness; this is the primordial force, a cloudy moving force. Look for a dot of light at the perineum and extend your awareness all the way down through the ground and the universe below.



***Fig. 3.44** Move the Hands to the Middle of the Crown and feel the Fingers Penetrate to the Perineum.*



When finished opening to the Six Directions and igniting the Three Fires, gather the Chi in the center and bring this expanded awareness into the healing session.

and Legends. Singapore: Dept. of Chinese Studies, National University of Singapore, 1983.

Long, Charles H. *Alpha: The Myths of Creation.* New York: George Braziller, 1963.

Lopez Lujan, Leonardo. *The Offerings of the Templo Mayor of Tenochtitlan.* Translated by Bernard R. Ortiz de Montellano and Thelma Ortiz de Montellano. Niwot: University of Colorado, 1994.

Lukker, Manfred. *The Gods and Symbols of Ancient Egypt.* London, England: Thames and Hudson, 1980.

MacCana, Proinsias. *Celtic Mythology.* Middlesex, England: The Hamlyn Publishing Group, 1975.

McConnel, Ursula. *Myths of the Munkan.* Carleton: Victoria: Melbourne University Press, 1957.

MacKenzie, Donald A. *China and Japan.* London, England: Studio Editions Ltd., Princess House, 1986.

Majupuria, Trilok Chandra. *Sacred and Symbolic Animals of Nepal: Animals in the Art, Culture, Myths and Legends of the Hindus and Buddhists.* Kathmandu: Sahayogi Prakashan, 1977.

Malinowski, Bronislaw. *Myth in Primitive Psychology.* New York: Norton, 1926.

_____. *Sex, Culture, and Myth.* New York, Harcourt, Brace & World, 1962.

Marriott, Alice Lee. *Plains Indian Mythology.* New York: Crowell, 1975.

Martin, Richard P., ed. *Bulfinch's Mythology. The Age of Fable, the Age of Chivalry, Legends of Charlemagne.* HarperCollins, 1991.

Masaharu, Anesaki. *History of Japanese Religion.* Rutland, VT: Charles E. Tuttle Company, 1975.

Mason, J. Alden. *The Ancient Civilizations of Peru.* Middlesex, England: Penguin Books Ltd., 1968.

Massey, Gerald. *Ancient Egypt, the Light of the World.* 2 vols. California: Mokelume Hill, Reprint 1988.

Matthew, John & Caitlin. *British & Irish Mythology.* London: Aquarian Press, Thorson Publishing Group, 1988.

Mercatante, Anthony S. *Who's Who in Egyptian Mythology.* New York: Clarkson N. Potter, Inc. Publishers, 1978.

Miller, Mary and Karl Taube. *The Gods and Symbols of Ancient Mexico and the Maya.* London: Thomas and Hudson Ltd., 1993.

Modder, Ralph P. *Chinese Temple Festivals, Origins and Religious Beliefs.* Hong Kong: South China Morning Post, 1983.

Mohanty, Sri Mangala Prasad. "Saora Tribals." *Hinduism Today,* March 1995. Pg. 1.

Monaghan, Patricia. *The Book of Goddesses & Heroines.* St. Paul, MN: Llewellyn Publications, 1990.

Morgan, Harry Titterton. *Chinese Symbols and Superstitions.* South Pasadena CA: P.D. and Ione Perkins, 1942.

Mortensen, Karl Andreas. *A Handbook of Norse Mythology.* Ann Arbor, MI: University Microfilms, 1971.

Mountford, Charles Pearcy. *Aboriginal Conception Beliefs.* Melbourne: Hyland House, 1981.

_____. *The Dawn of Time.* Australia: Rigby Press, 1974.

_____. *The Dreamtime.* Australia: Rigby Press, 1974.

_____. *The First Sunrise.* Australia: Rigby Press, 1974.

Munsterberg, Hugo. *The Arts of Japan: An Illustrated History.* Rutland, VT: Charles E. Tuttle Company, 1981.

Myerhoff, Barbara G. *Peyote Hunt: The Sacred Journey of the Huichol Indians.* Ithaca, NY: Cornell University Press, 1974.

Neumann, Erich. *The Great Mother; An Analysis of the Archetype.* Translated by Ralph Manheim. Princeton, NJ: Princeton University Press, 1963.

Noel, Ruth S. *The Mythology of Middle-earth.* Boston: Houghton Mifflin, 1977.

Okpewho, Isidore. *Myth in Africa: A Study of Its Aesthetic and Cultural Relevance.* New York: Cambridge University Press, 1983.

Olcott, William Tyler. *Sun Lore of All Ages: A Collection of Myths and Legends Concerning the Sun and Its Worship.* New York: Putnam, 1914.

Osborne, Harold. *South American Mythology.* New York: Peter Bedrick Books, 1983.

Otto, Walter Friedrich. *Dionysos, Mythos und Kultus.* English: *Dionysus, Myth and Cult.* Translated by Robert B. Palmer. Bloomington: Indiana University Press, 1965.

Overmyer, Daniel L. *Religions of China: The World as a Living System.* New York: Harper and Row Publishers, 1986.

Pagels, Elaine. *The Gnostic Gospels.* New York: Vintage Books, 1979.

Palmer, Robin. *Centaurs, Sirens, and Other Classical Creatures: A Dictionary, Tales and Verse from Greek & Roman.* New York: H. Z. Walck, 1969.

Parrinder, Geoffrey. *African Mythology.* Middlesex, England: The Hamlyn Publishing Group, 1967.

_____, ed. *World Religions: From Ancient History to the Present.* Facts on File, 1984.

The Pawnee: Mythology (Part 1). Collected under the Auspices of the Carnegie Institution of Washington, by George A. Dorsey. Washington: Carnegie Institution of Washington, 1906.

Payne, Robert. *The World of Art.* New York: Doubleday & Company, Inc., 1972.

Perry, John Weir. *Roots of Renewal in Myth and Madness.* San Francisco: Jossey-Bass, 1976.

Petrankos, Basil. *Ephor of Antiquities in Attica.* Athens, Greece: National Museum, Clio Editions, 1981.

Piggot, Juliet. *Japanese Mythology.* New York: The Hamlyn Publishing Group, 1975.

Platt, Rutherford H. (Jr.), ed. *The Forgotten Books of Eden.* New York: Bell Publishing Company, 1980.

Poetical Prose Quotations, Mythology. Watford, England: Reference Library. The Greycaine Book Manufacturing Company Limited, c. early 1800s.

Poignant, Roslyn. *Oceanic Mythology.* London, England: Paul Hamblyn Limited, 1967.

Polome, Edgar C. *Old Norse Literature and Mythology: A Symposium.* Austin: University of Texas Press, 1969.

Popol Vuh: The Great Mythological Book of the Ancient Maya. Translated by Ralph Nelson. Boston: Houghton Mifflin, 1976.

Popol Vuh: The Sacred Book of the Ancient Quiche Maya. English version by Delia Goetzand Sylvanus G. Morley from the Spanish translation by Adrian Recinos. Norman: University of Oklahoma Press, 1950.

Portillo, Jose Lopes, Demetrio Sodi, Fernando Diaz Infante. *Quetzalcoatl, in Myth, Archeology, and Art.* New York: Continuum, 1982.

Puhvel, Jaan. *Comparative Mythology.* Baltimore and London: The Johns Hopkins University Press. 1987.

Radhakrishnan, Sarvepalli, and Charles A. Moore, eds. *A Sourcebook in Indian Philosophy.* Princeton, NJ: Princeton University Press, 1967.

Reed, A. W. *Myths and Legends of Australia.* New York: Taplinger Publishing Co., 1973.

Rees, Alwyn D., and Brinley Ree. *Celtic Heritage: Ancient Tradition in Ireland and Wales.* New York: Grove Press, 1961.

Ringgren, Helmer. *Religions of the Ancient Near East.* Translated by John Sturdy. Philadelphia, PA: The Westminster Press, 1973.

Rinpoche, Guru, according to Karma Lingpa. *The Tibetan Book of the Dead. The Great Liberation through Hearing in Bardo.* Commentary by Francesca Fremantle and Chögyam Trungpa. Boulder, CO: Shambhala Publications, 1975.

Roberts, Ainslie. *The Dreamtime Book: Australian Aboriginal Myths in Paintings.* Adelaide, Australia: Rigby, 1973.

Robinson, Roland E. *The Feathered Serpent: The mythological genesis and recreative ritual of the aboriginal tribes of the Northern Territory of Australia.* Sydney: Edwards & Shaw, 1956.

Rose, H. J. *A Handbook of Greek Mythology.* New York: E. P. Dutton & Co., Inc., 1959.

Ross, Anne, Ph.D. *Druids, Gods, and Heroes from Celtic Mythology.* New York: Schocken, 1986.

Rowland, Beryl. *Animals with Human Faces, A Guide to Animal Symbolism.* Knoxville, Tennessee: The University of Tennessee Press, 1973.

Roys, Ralph L. *The Books of Chilam Balam of Chumayel.* Norman: University of Oklahoma Press, 1967.

Russell, Bertrand. *History of Western Philosophy and Its Connection with Political and Social Circumstances from the Earliest Time to the Present Day.* England: George Allen & Unwin Ltd., Ruskin House, 1965.

Rutherford, Ward. *Celtic Mythology.* Northamptonshire, England: Aquarian Press, Thorsons Publishing Group, 1987.

Rydberg, Viktor, Ph.D. *Teutonic Mythology, Gods and Goddesses of the Northland, Volume II.* London, England: Norrcena Society, 1906.

Sanders, Tao Tao Liu. *Dragons, Gods & Spirits from Chinese Mythology.* New York: Schocken Books, 1983.

Schafer, Edward H. *The Divine Woman; Dragon Ladies and Rain Maidens in T'ang Literature.* Berkeley: University of California Press, 1973.

Scherer, Margaret Roseman. *The Legends of Troy in Art and Literature.* New York: Phaidon Press for the Metropolitan Museum of Art, 1963.

Shapiro, Max S. & Rhoda A. Hendricks. *Mythologies of the World.* New York: Doubleday & Co., 1979.

Short Description of Gods, Goddesses and Ritual Objects of Buddhism and Hinduism in Nepal. Nepal: OM Printers, 1989.

Shryock, John Knight. *The Temples of Anking and Their Cults: A Study of Modern Chinese Religion.* New York: AMS Press, 1973.

Smith, Homer W. *Man and His Gods.* New York: Grossett's Universal Library, Grossett & Dunlap, 1957.

Spence, Lewis. *Mexico and Peru, Myths and Legends.* England: Thomas Y. Crowell Company, 1920.

______. *Myths & Legends of Babylonia & Assyria.* Detroit: Gale Research Co., 1975.

______. *The Outlines of Mythology.* London, England: Watts & Company, 1949.

______. *The Popol Vuh: The Mythic and Heroic Sagas of the Kiches of Central America.* New York: AMS Press, 1972.

Sproul, Barbara C. *Primal Myths, Creating the World.* San Francisco: Harper & Row Publishers, 1979.

Squire, Charles. *Celtic Myth and Legend: Poetry & Romance.* Hollywood, CA: Newcastle Publishing Co., 1975.

Stace, W. T. *Mysticism & Philosophy.* Los Angeles, CA: Jeremy P. Tarcher, Inc., 1960.

Stapleton, Michael. *The Illustrated Dictionary of Greek and Roman Mythology.* New York: Peter Bedrick Books, 1986.

Thomas, Lawson E. *Religions of Africa.* San Francisco: Harper & Row, Publishers, 1984.

Townsend, Richard F. *The Aztecs.* London, England. Thames & Hudson Ltd., 1992.

Tripp, Edward. *The Meridian Handbook of Classical Mythology.* New York: A Meridian Book, New American Library, 1970.

Turnbull, Stephen R. *The Book of the Samurai: The Warrior Class of Japan.* New York: Gallery Books, An Imprint of W. H. Smith, Publishers, 1982.

Vaillant, C. R. *Aztecs of Mexico.* New York: Pelican Book–Penguin Books, 1966.

Velikovsky, Immanuel. *Oedipus and Akhnaton: Myth and History.* Garden City, NY: Doubleday, 1960.

Vermaseren, M. J. *The Legend of Attis in Greek and Roman Art.* Leiden, The Netherlands: E. J. Brill, 1966.

Visser, Marinus Willem de. *The Dragon in China and Japan.* Amsterdam: J. Muller, 1913.

Waddell, Laurence Austine. *The Buddhism of Tibet. Tibetan*

www.ebook3000.com

Buddhism, with its Mystic Cults, Symbolism and Mythology, and in its relation to Indian Buddhism. New York: Dover Publications, 1972.

Walker, Barbara G. *The Woman's Encyclopedia of Myths and Secrets.* San Francisco: Harper and Row, 1983.

Warren, Elizabeth. *Heroes, Monsters, and Other Worlds from Russian Mythology.* New York: Schocken Books, 1985.

Watterson, Barbara. *The Gods of Ancient Egypt.* New York: Facts on File Publications, 1984.

Watts, Alan W. *The Two Hands of God.* New York: George Braziller, 1963.

Weigle, Marta. *Spiders and Spinsters: Women and Mythology.* Albuquerque: University of New Mexico Press, 1982.

Werner, E. T. C. *Myths and Legends of China.* London: G. G. Harrop, 1922; reprinted Singapore: G. Brash, 1984.

Williamson, Robert Wood. *Religion and Social Organization in Central Polynesia.* New York: AMS Press, 1977.

Wolf, Eric *Sons of the Shaking Earth.* Illinois: University of Chicago Press, 1959.

Wolkstein, Diane and Samuel Kramer. *Inanna.* London, England: Rider and Co., 1983.

Woodcock, P. G. *Dictionary of Mythology.* New York: Philosophical Library, 1953.

Yumoto, John M. *The Samurai Sword, a Handbook.* Rutland, VT: Charles E. Tuttle Company, 1985.

Zimmer, Heirick Robert. *The Art of Indian Asia: Its Mythology and Transformations.* 2 vols. New York: Pantheon Books, 1955.

www.ebook3000.com

INDEX

A 3
Aa 3, 60, 198, 268, 451
Aa Sekhemu 4
Aaai 4
Aaan 4
Aaapef 61, 63
Aabdju 60
Aah 3, 464
Aah-Djuhty 3
Aah Tehuti 3, 457, 464
Aah Te-huti 3
Aah-Tehuti 3
Aah-te-huti 464
Aai 3, 4, 5, 44, 457
Aai Gods 3
Aaiu-f-em-kha-nef 60
Aakebi 4
Aa-kheperu-mes-aru 458
Aa-kheru 477
Aalu 4
Aamu 4
Aana 4, 425
Aana-tuati 4
Aani 4
Aaru 4
Aarvak 4, 38, 446
Aa-Sekhemu 4
Aat 4
Aat-aatet 379, 477
Aati 5, 75
Aatiu 4
Aat-khu 379, 477
Aats 4
Aat-shefsheft 3, 5
Aau 5
Ab 5, 422, 425
Aba 6
Abaangui and Zaguaguaya 6
Abaasy 6, 123, 483
Ababinili 6
Abac 14
Abaeus 62
Abaia 6
Abaios 62
Abakan-Khan 6
Abanathabla 8
Abans 6
Abantes 12, 121, 165
Abantiades 6
Abantias 142
Abaris 6
Abas 6, 12, 25, 67, 121, 137, 142, 230, 232, 297, 298, 316, 356, 390
Abasoms 7
Abasy 6, 70, 123
Abathur 6
Abatwa 6
Abd-allah 326
Abde'ra 7
Abd-el-Muttalib 326
Abderus 6
Abdu and Inet 9
Abel 7, 13, 113, 200
Abellio 7
Abelus 7
Abeona 7
Abere 7, 319
Aberewa 72
Ab-esh-imy-duat 5, 33
Abheda 7, 315
Abhijnaraja 7
Abhimanya 374, 486
Abhimanyu 7, 69, 441
Abiku 7
Abil 7
Abjaja 7, 105
Abjayoni 105
Ablathanabla 8
Aboatia 326
Abokas 7
Abonsam 7
Abore 7
Aborigine People 7, 36, 81, 84, 89, 92, 101, 143, 146, 154, 158, 170, 187, 236, 251, 261, 273, 281, 302, 303, 304, 308, 322, 328, 329, 330, 332, 334, 350, 352, 353, 370, 392, 395, 396, 469, 471, 483, 504, 505, 506, 507
Abosom 7
Abou 8
Abracadabra 8
Abraham 8, 250
Abram 8
Ab-ramu 8
Abrasax 8, 65
Abraxas 8, 93
Abrayanti 404
Abruel 184
Ab-sha-am-tuat 5, 269
Ab-She 5, 33, 269
Absusu 8, 242, 271
Absyrtus 8, 18, 121, 233, 314, 380
Ab-ta 4, 5, 348, 477
Abtagigi 8, 242, 271
Abtu and Ant 9
Abu Talib 36
Ab-u 451
Abu 8, 451
Abuda 250
Abugupham-Bumo 9, 55, 252, 271, 295, 412, 429
Abuk 9, 85, 146
Abuk and Inet 9
abundance 11, 27, 29, 41, 107, 142, 149, 221, 277, 329, 340, 364, 385, 387, 390, 392, 405, 443, 446, 473, 482
Abundant Pearl Princess 473
Abundantia 183
Abundia 183
Abu-Turab 36
Abydine 319
Abydos 54, 60, 268, 367
Abyrga 9, 516
Abyss 164, 185, 191
Abyssinia 73
Abyzu 9
Abzu 63
Acacallis 9, 52, 62, 68, 137, 145, 192, 297, 322, 323, 337, 375, 457
acacia 85, 341
Academia 9
Academus 9
Acala 9, 121, 489
Acalle 9
Acamas 9, 10, 21, 23, 56, 137, 152, 165, 192, 210, 330, 380, 461
Acan 10
Acantha 62
Acantun 94
Acara 9
Acaragui 349, 395
Acarnan 113
Acaryavajrapani 489
Acastus 10, 51, 76, 219, 287, 377, 439, 440
Acasus 67
Acat 10
Acatl 10, 449, 456
Acca 10, 297
Acca Larentia 10, 32, 178, 180, 287, 297, 455
Acca Laurentia 10
Accad 346
Accadians 32, 158
Acco 10
Accolon 328
Acersecomes 62
Acesidas 10, 232
Acesis 72, 229, 231, 299
Acesta 10
Acestes 10, 134, 163, 405, 418
Acestis 10
Acetes 12
Achachilas 11, 183
Achaea 11, 21, 414
Achaemenians 50
Achaemenides 358
Achaeus 11, 152, 211, 510
Achalanatha 182
Achamoth 11
Achates 11
Ach-Chazu 28
Acheloos 11
Achelous 11, 113, 114, 132, 210, 217, 291, 317, 376, 379, 404, 433
Acherbas 151
Acheren 11
Acheron 11, 12, 72, 123, 131, 194, 289, 366, 382, 404, 455, 503
Acherusia 11
Achilles 11, 12, 18, 21, 31, 34, 35, 42, 57, 75, 91, 113, 123, 137, 145, 152, 167, 173, 192, 205, 209, 212, 219, 292, 314, 317, 329, 331, 375, 377, 378, 382, 385, 386, 393, 440, 462, 474, 508, 522
Achilleus 11
Achiyalatopa 12
Acholi 506
Achomawi 134
Achren 12
Achtaroth 73
Achtoret 73
Achyuta 498
Acidalia 61, 495
Acis 12, 137, 157, 177, 185, 387
Acmon 117, 138, 356
Acolnauactl 320
Acoma 231, 263, 264, 311, 328, 384, 428, 466, 475, 481
Acotzentli 12
Acraea 61, 403
Acrisius 6, 12, 25, 67, 91, 121, 142, 151, 174, 176, 218, 356, 359, 380, 390, 458
Acron 405
Acropolis 26, 170
Actaea 342
Actaeon 13, 68, 69, 70, 83, 112, 123, 284, 299
Actaeus 26, 214, 372
Actor 13, 17, 19, 67, 76, 118, 135, 145, 152, 162, 175, 218, 241, 287, 318, 327, 376, 377, 382, 386, 387, 388, 440
Acuecueyotl 13, 120
Acyuta 275
Adad 13, 15, 87, 168, 200, 241, 344, 399, 404, 423
Adad Rammon 404
Adad-Ea 13
Adam 7, 13, 14, 39, 113, 162, 166, 176, 250, 255, 302, 311, 327, 407; and Balujen 14; and Eve 102
Ad-ama 13
Adamah 13
Adamanthea 522
Adan 16
Adapa 14, 15, 58, 162, 176, 192, 234, 346
Adar 14, 78, 345
Adargyns 13, 14
Adda 232
Addad 13, 404

Addanari 14
Adda-Nari 14
Addane 14
Addephagia 14
Adder 14, 171
Addittee 15
Addu 13, 14, 15, 200, 309
Ade 13
Adee 15
Adekagagwaa 15
Aden 16
Adena 6
Adept in Yoga 148, 517
Ades 201
Adharma 15, 55, 105, 313
Adhaya mudra 153
Adhibudda 15
Adhidevatas 148
Adhiratha 397
Adi 15, 493
Adibuddha 15, 150, 411, 489, 490
Adi-Pati 186
Adi-siki-taka-pikone-no-kami 15, 449, 464
Adit 15
Aditi 15, 26, 71, 141, 147, 148, 237, 264, 310, 325, 393, 406, 415, 416, 422, 444, 487, 491, 492, 493, 494, 498, 500
Adityas 15, 16, 45, 71, 98, 140, 149, 185, 264, 310, 325, 374, 393, 409, 416, 486, 492, 493, 500
Adjusters 409
Adlet 16
Adlinden 16
Adliparmiut 16
Adlivun 16, 417
Admeta 16
Ad'meta 16
Admete 16
Ad'metos 16
Admetus 16, 35, 62, 67, 173, 232, 297, 324, 379
Admiralty Islands 308
Adn 16
Adon 16, 75, 79, 451
Adonaeus 65, 231
Adonai 16, 65, 75, 231, 250, 451
Adonaios 16
Adonay 16
Adonia 16, 17
Adonis 16, 17, 54, 61, 113, 117, 129, 153, 158, 172, 331, 333, 367, 379, 382, 404, 412, 451
Adorable Ones 514
Adrastea 17, 522
Adrasteia 17, 341
Adrastia 17, 40, 232, 317
Adrastos 17
Adrastus 17, 19, 64, 130, 136, 145, 175, 319
Adrestea 17
Adrestus 17, 19, 47, 175, 218, 320, 387, 451
Adrija 374
Adrisyanti 373
Adrola 63
Adsullata 17
Adu Ogyinae 17
Adununkisum 17, 284
adventurers 449
Aeacides 17, 18
Aeacus 12, 17, 18, 19, 174, 201, 323, 377, 382, 391, 403, 441, 457
Aeaea 18, 129, 130
Aeaucus 17
Aebh 18, 60
Aeculapius 72
Aed 18, 60
Aedh 18
Aedon 18, 205, 244, 372
Aeeiouo 18, 250
Aeeta 18
Aeetes 18, 64, 67, 76, 129, 130, 194, 210, 233, 239, 250, 314, 315, 356, 375, 379, 383, 389
Aega 20, 23, 522
Aegaeon 18, 19, 184, 356
Aege 19
Aegean Sea 35, 342, 387
Aegeon 18, 125
Aeger 19
Aegeria 163
Aegeus 18, 20, 22, 314, 315, 323, 387, 388
Aegiale 19, 20, 382
Aegialeia 17, 19, 47, 57, 132, 136, 152, 218
Aegialeius 19, 64
Aegialeus 17, 19, 47, 64, 136, 218, 236, 316, 383
Aegialus 11
Aegimius 19, 156, 371, 456
Aegin 391
Aegina 13, 17, 18, 19, 74, 241, 318, 376, 377, 386, 404, 434, 440, 457, 523
Aegipan 19, 145, 371, 480
Aegir 19, 180, 209, 229, 399
Aegis 19, 20, 40, 93, 177
aegis 93
Aegisthus 20, 81, 116, 165, 365
Aegle 20, 25, 66, 72, 169, 195, 210, 216, 229, 231, 299, 354
Aegyptus 20, 25, 49, 142, 143, 175, 229, 232, 297, 382
Aeife 18, 60, 103
Aeithlius 21
Aello 20, 125, 385
Aellopuus 20
Aeneas 6, 10, 20, 21, 49, 51, 61, 119, 151, 157, 173, 176, 212, 218, 231, 235, 244, 284, 287, 319, 358, 370, 463, 479, 495
Aeneas Silvia 21
Aenetus 13, 118, 145, 152
Aeneus 20, 131
Aengus 54
Aeoina Kamui 361
Aeolia 21, 218, 232, 391
Aeolus 20, 21, 39, 69, 79, 104, 115, 125, 133, 134, 136, 145, 156, 166, 174, 182, 211, 219, 249, 292, 299, 300, 316, 320, 324, 379, 410, 433, 452, 461, 474
Aeolus II 70, 316
Aeonius 138
Aeons 21, 351, 437
Aepytus 21, 192
Aer 22
Aeracura 22, 153, 431
Aerolith 22
Aeron 22
Aerope 22, 23, 66, 81, 118, 131, 318, 377, 440, 453
Aeropus 22, 66
Aerth 215
Aertha 215
Aes Sidhe 142
Aesacus 76, 130, 145, 319, 374
Aesar 22
Aeschylus 62
Aesculapius 72, 172
Aeshma 22, 138, 501
Aeshma-deva 74
Aesir 19, 22, 71, 72, 77, 90, 104, 105, 192, 198, 209, 221, 232, 233, 252, 283, 294, 350, 432, 444, 462, 491, 496, 516, 517
Aesm 22
Aeson 16, 35, 67, 249, 341, 390, 480
Aesus 22
Aesyetes 218
Aether 22, 118, 122, 135, 170, 230, 266, 327, 352, 484
Aetheria 20, 22
Aetholides 22, 174
Aethon 210
Aethra 23, 229, 385, 440
Aethre 22
Aethusa 66
Aetna 12, 23, 167, 212, 370
Aetolia 67, 152, 370, 463, 480
Aetolis 136
Aetolus 21, 62, 114, 165, 383, 385
Aex 19, 20, 23, 210
Af 23
Afa 23
Af-Asar 425
Afau 23
Affi 340
Affreet 23
Afghanistan 34, 235
Afi 23, 46, 209
Af-Osiris 23, 367
Afraid-of-nothing 394
Afreet 23, 291
Africa 6, 7, 9, 17, 23, 24, 27, 29, 30, 33, 34, 40, 46, 50, 67, 72, 74, 78, 84, 85, 86, 87, 89, 91, 95, 101, 102, 103, 105, 112, 120, 122, 127, 128, 132, 133, 138, 142, 146, 155, 160, 163, 165, 172, 176, 177, 184, 185, 188, 190, 191, 193, 195, 197, 198, 199, 209, 213, 228, 231, 233, 235, 250, 252, 253, 255, 256, 258, 260, 264, 265, 266, 268, 269, 270, 271, 272, 273, 275, 283, 288, 290, 292, 302, 306, 307, 311, 314, 323, 324, 326, 329, 330, 331, 334, 338, 339, 340, 341, 342, 343, 344, 350, 353, 354, 355, 356, 358, 360, 361, 362, 363, 364, 365, 366, 367, 368, 378, 396, 405, 407, 409, 414, 423, 436, 437, 442, 446, 453, 459, 463, 467, 472, 476, 481, 484, 500, 501, 503, 504, 506, 507, 508, 513, 515, 521, 523; deserts 93
Afrit 23
Af-Tem 269, 425
afterworld 220, 295, 308, 343, 366, 417
Afu 23, 425
Ag 23, 25
Agaku 309
Agamede 13, 329, 388
Agamemnon 12, 23, 51, 56, 81, 113, 116, 127, 128, 129, 130, 165, 240, 287, 318, 365, 378, 393, 453, 457
Aga-mi-ketsu-no-Kami 23
Aganippe 12, 20, 23, 142, 143
Aganju 23, 356, 358, 362, 515
Agapae 24
Agape 21, 24, 351
Agas Xenas Xena 24
Agasaya 24, 242
Agassou 24
Agastya 24, 160, 325, 404, 485
Agatha 24
Agathadeamon 24
Agatho-demon 93
Agathodiamon 24
Agathos Diamon 24, 479
Agave 24, 83, 88, 112, 205, 234, 239, 297, 342, 378, 419
Agbe 24, 85, 436, 500
Agdistis 24, 81, 136
Agdo 24
Agdos 24, 136
age of the universe 21
Agelaos 286, 363
Agelaus 374
Agemem 255
Agemo 24
Agenor 10, 21, 24, 25, 52, 56, 66, 67, 96, 97, 112, 129, 146, 165, 174, 192, 218, 231, 289, 291, 327, 377, 381, 382, 385, 387, 393, 402, 457, 461, 507
Agent of Heaven 467
Agents of Earth 465
Ageratos 21, 351
Aghasura 275
Aghyu Gugu 25, 483
Agilma 309
Aglaea 20, 25, 195, 212, 461
Aglaia 6, 12, 25, 390
Aglaopheme 433
Aglauros 26
Aglaurus 26
Aglaus 81
Agloolik 25
Agnar 25, 189
Agnayi 26, 441
Agne 25
Agnen 25, 68
Agneya 25, 263
Agneyastra 25, 409
Agneyi 25, 404
Agni 15, 25, 26, 53, 60, 77, 78, 99, 100, 135, 141, 149, 152, 160, 187, 195, 216, 237, 259, 263, 275, 278, 285, 293, 325, 327, 374, 377, 388, 390, 401, 404, 406, 412, 414, 434, 435, 436, 437, 444, 474, 479, 485, 486, 488, 492, 493, 494, 512
Agni Yavishta 25
Agnimukha 26, 511
Agnis 25, 285
Agoneus 214
Agoni (Slavic) 25
Agothyathik 85
Agras 26
Agrasandhani 26, 512
Agrat Bat Mahalat 26
Agraulos 26, 35, 214, 372
Agraulus 26, 66
Agreaskoui 66
Agreus 26, 27, 69
agriculture 26, 40, 41, 43, 62, 69, 71, 85, 88, 93, 94, 99, 103, 104, 113, 117, 119, 120, 124, 125, 128, 142, 167, 177, 197, 218, 224, 270, 275, 281, 287, 294, 310, 320, 328, 354, 361, 365, 378, 384, 385, 402, 411, 415, 415, 424, 425, 427, 431, 450, 451, 458, 485, 496, 519
Agri-manios 53
Agriskoue 66
Agrius 26, 27, 114, 130, 178, 190, 219, 359, 387, 440, 457, 469
Agro-manyus 53
Agros 27, 164
Agrotes 26, 27
Agroueros 27
Agu 27
Aguieus 62
Aguilo 64, 104
Agunua 27
Agusaya 27
Agwe 27, 172
Agweta 27
Agyieus 62
Agyieyus 62
Ah 3, 75
Ah Puch 28
Aha 98
Aha-en-urt-nef 340
Ahalya 27, 238
Ahana 80
Aha-neteru 419
Ahans 77
Aharman 53
Ahat 27, 43
Ahau-Chamahez 27
Ahayuta Achi 27, 156
Ahet 27
Ahhazu 28, 146

www.ebook3000.com

Ah-hetep 27
Ahi 28, 85, 143, 233
Ahiah 250
Ahimsa 337
Ahi-Mu 28, 75
Ahit 27
Ahji 420
Ahkinshok 28
Ah-Kiuic 27
Ah-Kluic 120, 221
Ahkushtal 28
Ahmakiq 28
Ahmes-Nefertari 44
Ahmucen-Cab 28
Ahoeitu 28, 164
Ahpuch 28, 202, 246, 324
Ahpuch Yum Cimil 28
Ahrenkonigin 28
Ahriman 30, 32, 52, 53, 65, 71, 138, 143, 157, 455, 521, 524, 525
Ahrimanes 28, 53, 71
Ahsonnutli 28, 81
Ahti 28, 289, 332
Ahto 28, 289
Ahtoia 28, 289
Ahu 28, 452
Ahuehuete 28
Ahura 28
Ahura Mazda 28, 29, 33, 45, 50, 53, 65, 77, 78, 86, 89, 179, 180, 188, 189, 203, 204, 222, 228, 268, 270, 325, 333, 360, 400, 438, 464, 468, 492, 494, 500, 501, 514, 516, 524
Ah-uuc-chek-nale 28
Ahy 215
Ahzi Dahaka 157
Ai 3, 29, 160, 209
Aiai 29, 277
Aiaiakuula 29, 282
Aiakos 17
Aiapakal 29, 511
Aias 31
Aibheaog 29
Aida-Wedo 29, 141
Aides 131, 135, 201
Aidne 29
Aido Hwedo 29, 302
Aidoneus 16
Aife 60
Aigamuchab 30
Aighistos 20
Aigina 19
Aigi'pan 19
Aigis 20
Aigisthus 20
Aigle 20
Ai-laau 377
Ailaios 231
Ailaiosastaphaios 65
Ailanthus 30
Aileili 321
Ailiah 37
Aillen 30
Aillil 300
Ailo 291
Ailoaios 75
Aimon Kondi 30
Aindra 238
Aindri 69, 237, 238
Aine 30, 58, 142
Aineias 20
Aino 488
Ainos 226
Ainu 125, 262, 361
Ainu-rak-kur 361
Ainus 182
Aion 21, 273; and Protogonos 88
Aior-pata 42
Aipaloovik 30
Air 30, 368
air/atmosphere 22, 36, 127, 135, 154, 135, 168, 181, 224, 232, 234, 237, 248, 253, 321, 347, 395, 400, 428, 443, 446, 451, 474, 482, 514
Airavarta 30
Airavata 30, 152, 238, 281, 293
Airawata 30
Aireskoi 66
Aireskouy 66
Airmed 151
Airmid 30, 151, 320
Airo-pata 42
Airya 465
Airyano 30
Ais 149, 201
Aisar 22
Aither 31
Aithon 382
Aithre 22
Aithuia 79, 80
Aitvaras 31, 155
Aiwel 85
Aiwil Longar 85
Ai-willi-ay-o 417
Aiyai 31
Aiyanar 196
Aizen Myo-O 31
Aizen-Myoo 31, 193
Aizenmyo-o 31
Aizenmyo-wo 31
Aja Ekapada 31
Aja 31, 85, 398
Ajagava 31, 428
Ajatar 31
Ajattara 31
Ajax 31, 67, 162, 192, 379
Ajax the Greater 10, 31, 170, 175, 456
Ajax the Lesser 31, 116, 171, 360
Ajbit 31, 127, 245, 387, 394
Aji-suki-takahikone 450
Ajita 32, 303, 320
Ajnan 251
Ajorsum 32
Ajtzak 32, 127, 245, 387, 394
Ajy-khoton 32
Ajysit 32
Ajysyt 32, 290
Ak 339
Aka 32, 33
Aka Manah 32, 138, 501
Aka Mano 143
Akadja 105
A-Kahiwahiwa 3, 456
Aka-Kanet 32
Akalo 32
Aka-Manah 32
Akamas 9
Akan 364
Akanchob 33
Akanet 32
Akar 32
akasa 91
Akasagarbha 32, 150, 273, 277, 301, 410
Akasha Dhatu Ishvari 488
Akasha Dhatu Isvari 334
Akatauire 399
Ake 60
Akebiu 32
Akeneh 32, 61, 420, 481
Aken-tau-k-ha-kheru 477
Akenti 477
Aker 32
Akert 458
Akeru 32
Akesi 4
Akethor 463
Akewa 32
Akh 32, 86, 254
Akha 32
Akhan-maati 477
Akhekh 33
Akhem-hemi-f 477
Akhem-khemes-f 477
Akhem-Sek 33
Akhem-sek-f 477
Akhem-urt-f 477
Akhen 5, 33
Akhenaten 33
Akhenaton 79
Akherkh 421
Akhet-nen-tha 33
Akhmiu 4
Akhrokhar 385
Akhtar 33, 515
Akhtya 33, 514
Aki-bime-no-kami 482
Akinetos 351
Aki-Yama no Shitabi-onoko 33, 206
Akka 33, 401
Akkadia 13, 14, 27, 36, 49, 58, 63, 65, 73, 81, 93, 95, 139, 161, 167, 170, 198, 211, 235, 241, 242, 270, 300, 304, 309, 334, 339, 345, 348, 349, 404, 414, 426, 431, 432
Akkruva 33, 207
Aklemia 14
Akna 33
Akoma 446
Akoman 32
Ako-Mano 32
Akongo 33, 46
Akrura 33, 262, 447
Aksak 33
Akselloak 33
Akshobhya 33, 84, 99, 121, 150, 195, 215, 303, 304, 389, 400, 454, 473, 488, 489
Akshyobhya 33
Aksobhya 33
Aktiophi 170, 208
Aku 27
Akua 79
akuhekuhe fish 261
Akuj 34
Akupara 34
Akusaa 34, 478
Aku-Thor 463
Akwan 146, 251
Akycha 34
Al 34, 38, 146, 164, 251
Al Ussa 34
Ala 34, 36, 37
Alad 418
Alae-a-Hina 482
Alaghom Naom 34
Alaghom Naum 34
Alah 37
Alaisiagae 34, 490
Alaka 34, 282
Alakaluf 34, 487
Alakh 34
Alalus 34
Alambusha 63
al-Amin 326
Alan 34
Alaska 472
Alastor 34, 474
Alat 37
Alator 131
Alatuir 34
Albania 520
Alberich 52
Albion 48
Albiorix 34, 131
Alborix 477
Albors, Mount 34
Albunea 34
Alburz, Mount 34, 35, 126
Alcaeus 35, 52, 194, 286, 440
Alcathous 35, 81, 114, 218, 240, 359, 377, 378, 387, 440
Alcemene 35
Alcestis 16, 35, 51, 173, 213, 379
Alceus 363
Alcides 213
Alcidice 410, 480
Alcimede 35, 67, 249, 383, 390
Alcimenes 35, 171, 249, 381
Alcino 344
Alcinoe 165
Alcinous 66
Alcippe 35, 66, 138, 176, 202, 327, 359
Alcis 35
Alcithoe 35, 290, 324
Alcmaon 113, 462
Alcmene 172, 175, 195, 402, 403, 523
Alcmeon 113, 404
alcohol 98, 148, 299, 300, 357, 493
Alcyone 21, 39, 115, 165, 166, 192, 230, 385, 440
Alcyoneus 35, 56, 184, 190, 219, 286, 469
alder 114
Aldoneus 201
ale 229
Ale 34
Alebrewer 19
Alecto 35, 171, 183, 315, 468
Aleion 35, 36
Alektro 35
Alemene 213
Alemona 35
Aletes 20
Aletheia 21, 351
Aleus 118, 378
Aleus the Arcadian 67
Alevin 16
Alexander 36
Alexander the Great 194
Alexandra 116
Alexandria 293, 420
Alexanor 299
Alexiares 208
Aleyin 36, 51, 328, 402
Aleyn 36, 282
Aleyn-Baal 36, 86, 87, 95, 200, 309, 317
Alf 36, 160
Alfadur 397
Alfar 36, 160, 166, 446
Alfar Lios 160
Alfheim 36
Alf-heim 36, 446
Alfhild 36
Alfrigg 36, 98, 181
Algelaos 35
Algonkian 214
Algonquian 160, 192, 272, 350, 505
Algonquin 78, 191, 193, 213, 221, 267, 303, 315, 320, 321, 323, 334, 335, 349, 371, 504, 506
Algue 32
Al-Hasan 36
Ali 36, 418, 490
Ali ibn 36
Alidat 73
Alien Gods 51
Alignak 36, 384
Aliki 262
Alilah 36, 37
Alilat 36, 61, 234
Alilta 36
Alinda 36, 392
Alitta 61
Alittu 73
Aliyan 36
Alka 32
Alkmena 213
Alkuntam 37, 394
All 25, 26
All Merciful, The 278
All Pitying One 411
All Sided One 411
Allah 14, 36, 37, 85, 164
Allat 34, 36, 37, 51, 64, 170, 200, 242, 317, 412, 484
Al-Lat 37
Allath 37
Allatu 37, 170, 479
All-Caring 67
All-Devouring 82
Allecto 35
alligator 28
Alloprosallos 65
All-pervader 498
All-pervading Circle 48
All-seeing 210, 372
almond trees 9, 10, 27
almonds 24, 81
alms dish 106
Aloadae 37
Aloeidae 37
Aloeides 37, 368

Aloeus 37, 115, 162, 169, 170, 190, 240, 368, 469
Aloka 84
Alom 37, 227, 245, 387
Aloros 38
Al-ozzah 200
Alpanu 69
alphabet 112, 116, 176, 178
Alphaeus 38
Alphee 38
Alpheios 38
Alpheius 38
Alpheous 38
Alphesiboea 16, 379, 382
Alpheus 11, 38, 66, 213, 366, 404
Alphito 38
Alrinach 38
Als 38
Alsvid 5, 38, 446
Alsvider 5, 38
Alsvinn 38
Alswid 38
Altaic 89, 283, 414, 452, 458
Althaea 38, 114, 145, 153, 288
Althaemenes 9, 131
Althaia 38
Althea 38, 66, 175, 194, 316, 359, 462, 473
Altjira 38
Alu 28, 38, 146, 291
Aluberi 281
Aluelop 296, 436
Alukah 170
Alulei 38, 371, 436
Alulim 38
Aluluei 38
Alulus 59
Aluqa 39
Al-Uza 34, 37, 317, 484
Al-Uzza 34
Al'uzzah 34
Alvheim 36
Alvis 39, 160, 465
Alviss 39
Alvit 501
Alxion 205, 359
Am 43, 61
Am Ut 58
Ama 39, 40, 46, 164, 177, 259, 260, 280, 304, 374, 417, 445, 449, 450, 518
Amaethon 40
Amagandar 40
Amahraspands 45, 48
Amairgen 45
Amairgin 45
Amaite-Rangi 40, 344
Amaleus 18
Amalivaca 40, 281
Amalthaea 40
Amalthea 40, 132, 317
Amaltheia 11, 17, 19, 20, 40, 132
Amam 46
Amamet 46
Amamet the Devourer 46
Amam-Mitu 40, 425
Amam-ta 4
Aman 43, 61
Amanki 41, 167
Ama-no-hashadate 247
Ama-no-hasidate 449
Ama-no-kagaseo 42
Ama-no-minaka-nushi 39, 42, 280, 449
Ama-no-minakanushi-no-Kami 39
Ama-No-Oshido-Mimi 41, 43
Ama-no-sagu-me 43
Ama-no-uki-hashi 246, 247
Ama-no-Uzume 40, 41, 241
Amanus 270
Amaravati 41, 63, 447, 490, 499
Amardad 45, 207
Amarna Heresy 33
amaru 168
Amaruduk 309
Amaterasu 23, 39, 40, 41, 42, 43, 46, 140, 181, 208, 217, 220, 221, 223, 241, 246, 251, 260, 281, 282, 300, 320, 347, 361, 420, 426, 427, 445, 449, 450, 458, 464, 476, 479, 482, 488, 503, 514
Ama-terasu Ohmi-Kami 39, 41
Amaterasu-Oho-hiru-me 41
Ama-terasu-Oho-hiru-me No Mikoto 41
Amaterasu-Oho-mi-Kami 41
Amaterasu-omi-gami 41
Ama-terasu-o-mi-Kami 41
Amathaon 40, 42, 58, 199
Amathaounta 42
Amathaunta 42
Amatheon 42
Amathusia 61
Ama-tsu-Kami 39, 40, 260, 449
Amatsu-Mikaboshi 42
Ama-tsu-mika-hoshi 361
Amatsu-Otome 42
Amatupiko-Pikonagisa 473
Ama-tu-Piko-nagisa-take-U-gaya-puki-apezu-no-mikoto 251
Ama-Tu-Pikone-no-mikoto 41
Ama-Waka-Hiko 43
Amayicoyondi 42, 349, 395
Amazon region 160, 277, 322, 368
Amazons 16, 42, 57, 60, 96, 174, 218, 281, 316, 368, 378, 440
Amba 42, 374, 404
Ambalika 372, 503
amber 20
Am-beseku 75
Ambi 42
Ambika 42, 148, 150, 158, 374, 392, 406, 415, 497, 503
Ambologera 61
Ambott 209
ambrosia 40, 41, 42, 193, 208, 437, 447
Amburaja 492
Amchimalghen 42
Amehetp 44
Amen 32, 33, 43, 49, 61, 209, 215, 267, 268, 322, 338, 352, 418, 420, 458, 522
Amenand 331
Amenet 43, 44
Amen-ha 4
Amenhetep 44
Amenhetep III 44
Amenhotep I 44
Amenhotep III 33, 44
Amenhotep IV 33, 79
Amenhotep, Son of Hapu 44
Ameni 4
Amen-khat 4
Amen-khum 269
Ame-no-Hohi 43
Ame-no-iha-fune 247
Ame-no-Iwato 241, 426, 503
Ame-no-Iwato 40, 41
Ame-no-minaka-nushi 39
Ame-no-murokumo-no-tsurugi 281
Ame-no-Oshido-Mimi 43
Amenophis 44
Amenophis I 44, 41
Amenophis III 317
Ame-no-puya-kinu-no-kami 282
Ame-no-tajikara-wo 41
Amenotsudoe-chine-no-kami 282
Ame-no-uki-hashi 247
Ame-no-Uzume-no-Mikoto 40, 41
Ame-no-Wakahiko 43, 208, 361, 450
Ame-no-wo-ha-ba 246
Ame-no-wo-ha-bari 43, 281
Amen-Ra 43, 44, 49, 54, 61, 81, 82, 215, 299, 323, 331, 333, 343, 373, 458, 481
Ament 4, 43, 44, 206, 225, 242, 338, 341, 352, 415, 419
Amentet 4, 44
Amentet-nefert 4
Amenthes 44
Amenti 4, 44, 211
Ament-Nefert 44, 425
Ament-ra 44
Ament-sthau 418
Amen-ur 43
Amererat 45
Ameretat 45, 48, 138, 455, 520
Amergin 45, 92, 135
Amesha 28
Amesha Spentas 16, 22, 45, 48, 73, 78, 148, 157, 190, 207, 270, 300, 438, 494, 500, 514, 524
Amesho Spends 45
Ameshospends 45, 48
Amet-tcheru 45, 425
Amhairghin 45
Am-haut-ent-peh-fi 477
Am-henth-f 44
Amida 42, 45, 46, 48, 139, 261
Amidas 45
Ami-Hemf 45
Amina 326
amirita 337
Amisodaurus 125
Amit 46, 299
Amita 42, 45, 252
Amitabha 45, 46, 48, 84, 150, 371, 439, 442, 466
Amitayus 45, 46
A-mi-t'o-fo 45
Amitolane 46
Amitra-Dhara 48
Am-kehun 457
Am-kehuu 483
Am-khaibetu 75
Amm 46, 422
Amma 23, 46, 196, 209, 262, 351
Amma-Ana-Ki 161
Ammanavaru 196
Ammehet 4, 418
Ammi-Seshet 46
Am-Mit 39, 46
Ammon 43, 331, 522
Ammonite 317, 327
Ammonium 43
Ammon-Ra 423
Am-mut 39, 418
Ammut 46
Am-net-f 477
Amoghapasa Lokeswar 46, 84
Amogha-Siddhi 47
Amoghasiddhi 47, 48, 84, 150, 185, 273
Amoghasiddi 47
Amoghavajra 47, 273
Amon 43, 205, 328, 331
Amonet 44
Amon-ra 43
Amor 47, 171, 310, 495
Amorite 13, 200
Amoshashiki 313
Amphianax 47, 56, 239
Amphiaraus 17, 67
Amphibia 47, 344, 377
Amphictyon 147
Amphidamas 231, 316
Amphion 47, 49, 57, 76, 127, 182, 243, 253, 290, 316, 339, 349, 383, 453, 522
Amphione 113
Amphissus 62, 157
Amphithea 17, 19, 47, 56, 64, 83, 145, 218, 297, 391
Amphithemis 9, 62, 187, 338, 474
Amphitrite 47, 48, 97, 291, 342, 387, 388, 403, 410, 417, 474
Amphitryon 12, 35, 118, 121, 165, 379, 403, 523
Amphius 130, 319
Amphoterus 113
Ampithea 136
Ampithemis 115
Ampycus 67, 328
Amra 235
Amraphel 202
Amrata 48
Amrit 436
Amrita 42, 48, 121, 436
Amrita Kundika 199
Amrita Surabki 48
Amritahari 55, 272
Amrita-Kumbha 48
Amrite Kundalin 199
Amritika 48, 437
Amrta 48
Amrtakundali 48
amsavataras 498
Am-senf 75
Amset 48, 204, 477
Amseth 48
Amshashpands 45, 48
Amshaspands 48
Amshaspends 45
Am-Sit 48
Amsu 44, 48, 49, 322
Amsu-Amen 48, 49
Amsvartner 49, 178
Amu 177, 417
Amu-Aa 49, 425
amulets 14, 49, 62, 197
Amulisu 10
Amum 43
Amun 43, 328, 331, 359, 457
Amunet 44, 46, 49, 341, 359
Amun-kneph 269
Amun-Min 43
Amun-re 43
Amur 267
Amurru 36
Amvika 148, 415
Amvika Devi 42
Amyclae 116
Amyclas 47, 49, 152, 229, 290, 316, 349
Amycus 245, 331, 342
Amykos 49
Amymone 49, 143, 338
Amyntor 76, 382
Amythao 232
Amythaon 21, 219, 480
Amythaonia 214
An 49, 58, 59, 82, 160, 168, 241, 334, 367
Ana 39, 49, 51, 58, 142
Ana Nse Kukuroko 50
An-Aareretef 49
Anadyomene 61
An-a-f 49, 75
Anahauac 518
Anahit 50, 65, 73, 75, 321, 487, 495
Anahita 50, 60, 65, 228, 301, 325, 335, 394, 444, 468, 487, 495, 501, 514
Anahite 50
Anait 50
Anaitis 50
Anakhai 50
Anakim 402
Anala 25, 493
Anamaqkiu 50
Anan 164
Ananda 50, 427
Ananga 50
Ananke 50, 461, 462

www.ebook3000.com

Ananse 50
Anansi 50, 507
Ananta 50, 333, 421, 498
Ananta-Shayana 50, 498
Anaplades 214
Anapurna 50
Ana-purna 50
Anar 50
An-Aretf 49
Anasuya 437
Anat 36, 49, 51, 75, 242, 328, 329, 394, 457, 510, 511
Anata 51, 421
Anata-Sesha 421
Anath 49, 51, 55, 86, 87, 142, 274
Anatha 51
Anath-yahu 51, 73
Anatis 500
Anatu 49, 51, 55
Anax 190, 469
Anaxibia 10, 23, 35, 51, 57, 66, 81, 130, 162, 343, 376, 393, 440, 464
Anaxiroe 230
Anaxo 35
Anaye 51, 515
Ancaeus 231, 411, 468
Ancestor Lo 295
Ancestral Spirits 235
Ancestress of the World 466
Anchancho 51, 164
Anchiale 138, 213, 231
Anchile 51, 410
Anchinoe 20, 25, 96, 142, 317, 345, 382, 465
Anchises 10, 20, 51, 61, 81, 157, 175, 218, 286, 462
Ancient Lord 186
Ancient One 391
Ancient Ones 373
Ancient Persian 302
Ancient Spider 65
Ancient Sun deity 207
Ancile 51, 310
Ancus Martius 10
Andaman Islands 262
Andarta 52
Andarvi 431
Ander 52, 143
Andes 11, 136, 164, 225, 339, 429, 443, 485, 513
Andhaka 154
Andhaka 52
Andhrimner 52
Andhrimnir 52, 164, 408
Andra 52, 238
Andreus 118, 173
Andriamanitra 521; and Andrianahary 52
Andrianahary 52
Andrimne 52
Androgeus 9, 18, 35, 52, 68, 192, 297, 323, 375, 440
androgyny 123
Andromeda 25, 35, 52, 68, 116, 118, 165, 194, 298, 379, 380, 382, 440
Androphonos 61
Anduruna 52, 64
Andvare 52
Andvari 52, 160
Andvarinaut 52
Ane 34
Anedjti 367
Anga 263
Angada 91
Angajan 53
Angakok 16, 362, 417, 511
Angamunggi 397
Angana 53, 63
Angara 203, 267
Anga-Raja 262
angels 6, 23, 53, 63, 74, 85, 86, 179, 180
anger 276, 427
Angerboda 53, 198
Angerbodha 53, 198
Angerona 53, 119
Angeronalia 53
Angervadil 53
Angeyja 53, 209
Angira 427
Angiras 26, 141, 278, 404
Angirasa 53
Angiris 388, 404
Angita 129
Angitia 53
angler 162
Anglo-Saxons 155, 169, 482, 485
Angoi 53
Angola 258, 521
Angpetu 53
Angra Mainyu 15, 22, 28, 29, 53, 71, 83, 85, 138, 148, 157, 189, 248, 267, 325, 439, 494, 524
Angrboda 53, 178
Angrbodha 53
Angro Mainyus 53
Angry Spirit 53
Anguissance 65
Angurvadel 53
Angus 54, 103, 139, 158, 173, 299, 321, 451
Angus Mac Og 54, 113
Angus Od 54
Angus of the Brugh 54, 321
Angusta 54, 417
Anguta 54, 417
Anhefta 4, 5, 54
An-her 44, 54, 477
Anher 49, 54
Anhert 54
An-hetep 419
An-hetep-f 49, 75
Anhir 54
Anhoret 54
An-Hur 49, 54
Anhur 49, 54, 66, 315, 396, 457
Anhur-Shu 54
Ani 54
Aniketos 208
Anila 493
animal skins 98
animal spirit 275
animals, deities of 119, 124, 290, 316, 375, 388, 427
Animiki 54
Aningan 36, 232
Anioch 54
Anioche 167, 201, 315, 318
Aniran 270
Aniruddha 91, 276, 388
Anit 54
Anith 164
Anitsutsa 55
Anius 62
Anjana 293
Anjanma 152
Anjea 55
Ank 55
Ankamma 55, 331
ankh 51, 55, 244
Ankh-aru-tehefau 269
Ankhat 242
Ankh-em-fentu 477
Ankhet 418
Ankhet-kheperu 418
Ankhi 55
Ankh-ta 458
Ankhtith 269, 425
Ankt 55
An-Kung 50, 467
Ankus 55, 186
Ankusa 48
Ankusha 55, 496
An-mut-f 50
Anna 25, 97
Anna Perenna 50
Annancy 50
Anna-nin 51, 334
Annapurna 50, 375
Anna-Purna 50
Annar 50, 55, 160, 351
Annfwn 12, 55
Anningan 36
Annis 236, 265
Annu 81
Annunaki 59, 233
Annuthat 51
Annwn 12, 55, 199, 393
Annwvyn 12
Anobret 135
Anoi-Diggan-Juje 9, 55, 252, 271, 295, 412, 429
Anointed One 250
Anonach 164
Anos 58
Anouke 55
Anouris 54
Anpao 55
Anpu 58
An-pu 58
Anqet 59, 269
Anquat 242
Anquet 55, 59, 165, 242
Anrita 55, 313
Anro-mainyus 53
Ansa 15, 325, 492
Anshar 55, 58, 59, 63, 73, 161, 184, 233, 272, 284, 285, 352
Anshumat 409
Anshur 55, 73
Ansuman 56, 444
Anta 50, 51, 55, 56
Antaeus 35, 56, 184, 190, 213, 360, 457
Antaf 32, 61, 420
Antaka 56, 511
Antares 204
Antariksha 56, 390
Antauges 56, 152
An-tcher-f 50
Antea 56, 96, 390, 440
Anteaus 469
Anteia 96, 240, 297
antelope 33, 58, 106, 112, 121
Antenor 10, 25, 56, 135, 146, 192, 286, 386, 461
Antero 56
Anteros 56, 61, 66, 145, 168, 171, 205, 370
Antetu 56
Antevorta 56, 388
Anthat 56
Anthedon 192
Antheia 56, 61, 212
Antheias 173
Antheti 4
Antheus 152
anthills 6
Anthios 152
Anthony S. Mercatante 340
Anthropos 21, 351
Anti 56
Antianeira 162, 172, 175
Anticleia 56, 57, 83, 212, 299, 358, 432
Antigone 13, 57, 67, 76, 132, 173, 175, 201, 252, 359, 377, 381, 386
Antikleia 56
Antilebanon 86
Antilles 78, 177, 197, 231, 233, 299, 304, 487, 518
Antilochus 51, 57, 317, 369, 386, 440
Antimache 16, 316
Antimachus 57, 219, 376
Antion 57, 245
Antiope 47, 57, 58, 66, 146, 153, 169, 175, 218, 240, 253, 316, 354, 368, 376, 378, 382, 387, 522
Antiphates 6, 316
Antiphus 112, 376
Antit 51
Antiu and Hentiu 58
Antoku 355
Antrim 292
ants 6, 18
Antu 58, 487
Antum 51, 58, 328
Anu 13, 14, 30, 42, 49, 51, 55, 58, 59, 63, 83, 94, 97, 142, 161, 162, 164, 167, 168, 184, 191, 198, 199, 233, 234, 238, 242, 272, 279, 285, 301, 324, 346, 347, 349, 353, 451, 467, 487, 523
Anubis 58, 60, 93, 201, 214, 235, 265, 298, 341, 342, 367, 394, 418, 421, 425
Anuket 55, 59
Anukis 55, 59, 269
Anukisuas 59
Anukit 59
Anulap 59, 291
Anum 49, 58
Anumati 59
Anunaki 59
Anungite 59
Anunit 59, 236, 242
Anunitum 59
Anunnaki 51, 58, 59, 236, 487
Anus 34, 59, 279
Anu's Way 168
Anush 59
Anzety 59, 367
Anzu 524
Ao 59, 278, 385
Ao Ch'in 156
Ao Jun 156
Ao Kuang 156
Ao Shun 156
Aobh 18
Aodh 18
Aoi 60, 250
Aoide 60, 316, 330
Aoife 18, 60, 103, 305
Ao-Kanapanapa 59, 456
Aokeu 60
Ao-Marama 59
Ao-Nui 59, 456
Ao-Pakarea 59
Ao-Potango 59, 456
Ao-Pouri 59, 60, 385, 399, 456
Ao-Roa 456
Aos 3, 60, 161, 355
Ao-Takawe 456
Ao-Toto 60
Ao-Whetuma 60, 456
Ap 4, 60, 61, 63
Apa 482, 493, 494
Apache 184, 206, 470, 471, 472, 515
Apam Napat 60, 501
Apaosha 60, 468
Apap 61, 63
Apas 91, 390
Apason 63, 96
Apa-Tanis 278
Apaturia 61
Ape 4, 60, 91, 334, 502
Apemosyne 131
Apep 61, 63, 428
Apepi 4, 5, 61, 63, 466, 477
Aper-hra-neb-tchetta 417
Aper-ta 4, 61
apes 4, 91, 407
Apet 64, 455
Aphacitis 61
Aphangak 61, 271
Aphareus 67, 105, 194, 232
Apheliotes 174
Aphidnae 116
Aphrodite 8, 12, 16, 17, 20, 25, 31, 36, 37, 51, 56, 61, 64, 66, 68, 73, 74, 75, 78, 97, 112, 113, 122, 137, 145, 152, 153, 157, 168, 169, 171, 172, 178, 184, 185, 192, 195, 205, 206, 211, 212, 214, 225, 229, 234, 331, 337, 341, 370, 374, 380, 382, 384, 390, 391, 393, 433, 484, 495, 523
Aphrodite Genetrix 61
Aphrodite Nymphia 61
Aphrodite Pandemos 61
Aphrodite Porne 61
Aphrodite Urania 61
Aphson 63
Api 61
Apia 62, 349

Apis 61, 62, 203, 349, 367, 383, 415, 420, 428, 457, 461
Apisirahts 62
Apit 62
Apito 197, 239
Aplu 62
Apo 62, 514
Apocatequil 62, 197, 369
Apochquiahuayan 62, 125
Apoconallotl 120
Apocryphal 14
Apollo 6, 9, 12, 16, 18, 19, 20, 22, 31, 37, 47, 49, 62, 66, 67, 69, 70, 72, 95, 105, 112, 113, 116, 117, 127, 129, 131, 133, 134, 137, 138, 139, 143, 145, 156, 157, 169, 171, 175, 176, 195, 211, 213, 214, 216, 223, 229, 232, 239, 286, 287, 289, 290, 297, 310, 316, 321, 322, 327, 330, 337, 349, 356, 364, 365, 366, 369, 371, 374, 377, 378, 382, 387, 393, 402, 414, 430, 432, 438, 462, 465, 469, 499, 507, 523
Apollo Musagetes 330
Apollodorus 63, 342, 349
Apollon 62
Apollonius Rhondius 64
Aponbolinayen 235
Apophis 3, 61, 63, 315, 402
Apopophis 63
Apostles 103
Apotrophia 61
Apoyan Ta'chu 84
Apoyan Tachu 84
Apple of Discord 79
apple tree 7
apples 20, 176, 213; *see also* golden apples
April 61
April Fool's Day 199
Apsaras 53, 63, 187, 224, 384, 485
Apsarases 41, 63, 147, 186, 203, 413, 442, 447
Apsit 457
Apsu 55, 63, 97, 142, 161, 167, 272, 284, 285, 309, 330, 466
Apsu-Ocean 352
Apsyrtos 64
Apsyrtus 18, 64, 314
Apt 43, 44, 64, 206
Ap-Taui 60
Apt-ent-khet 4
Apt-ent-qahu 4
Apt-net 4
Aptu 64
Aptya 474
Apu 4, 5, 64
Ap-Uat 60, 486
Apu-Hau 64, 456
Apu-Matangi 64, 456
Apu-Punchau 239
Apzu 63
Apzu-Rishtu 64
Aqas-Xena-Xenas 24
Aqhat 274
Aquarius 187
Aquila 64
Aquilo 64, 105, 133
Ara Tiotio 64, 84
Ara 64
Arabia 8, 37, 46, 97, 142, 159, 166, 169, 200, 234, 251, 423
Arabic 7, 8, 13, 14, 23, 34, 36, 37, 39, 53, 73, 74, 79, 80, 85, 87, 88, 141, 143, 163, 165, 176, 184, 189, 209, 224, 234, 242, 247, 305, 317, 326, 338, 343, 401, 410, 418, 484
Arabs 5, 8, 14
Arabus 64, 116
Arachne 64, 232
Aracynthias 61
Araethyrea 153
Arafat, Mount 327
Araga 64, 406
Arak 64
Aralez 69
Arallu 37, 59, 64, 65, 95, 170, 241, 334, 342, 346, 425
Aralu 64, 319
Aram 69, 87
Aramaean 14, 15
Aramaic 78, 166
Aramati 65
Aramazd 65, 153, 321, 335, 339, 438, 469, 487
Aramean 13
Ara-mi-tama 64, 260, 445
Aranbfi 340
Aranunna 309
Aranzahas 279
Ar-Ast-Neter 64, 425
Araucana 32, 42, 82, 124, 127, 170, 198, 207, 225, 226, 256, 320, 344, 384
Arawak People 30, 233, 266, 274, 277, 281, 303, 364, 431
Arawn 12, 42, 65, 199, 393
Arazu 65, 161
Arbhu 403
Arbidihist 73
arbitration 58, 92
Arcadia 21, 22, 38, 67, 113, 116, 131, 175, 176, 231, 297, 300, 376, 378, 379, 387, 440, 441
Arcas 113, 523
Arceisius 284
Archaic Period 60
Archander 11
archangels 14, 48, 53, 184
Archelous 10, 21, 56, 192, 461
archers/archery 62, 230, 267, 276, 319, 415, 424, 441, 483, 490, 513, 516
architects/architecture 44, 264, 274, 349
Architekes 11
Archons 14, 65, 93, 222, 231, 408
Arctic Ocean 385
Ardabahisht 73
Ardeas 130, 457
Ardevi Sura Anahita 50
Ardhanari 65
Ardhanari-Ishavara 65
Ardhanari-Ishvara 65, 427
Ardhanariswara 65, 285, 427
ardhaparyankasana 185
Ardhapayanka 71
Ardi-bahisht 73
Ardusht 524
Ardvi Vaxsha 65
Areia 61
Areius 65, 379
Arekoi 66
Aremata-Popoa 65
Aremata-Rorua 65
Arene 65, 194, 232
Areoi 220, 366
Areopagus 365
Areop-Enap 65, 337
Ares 17, 22, 35, 37, 38, 54, 56, 57, 61, 65, 66, 72, 79, 114, 127, 133, 137, 145, 152, 157, 163, 165, 168, 171, 176, 202, 205, 208, 212, 213, 218, 231, 245, 297, 310, 316, 327, 359, 368, 378, 382, 393, 440, 462, 523
Areskoui 66
Arete 66, 153
Arethusa 38, 66, 216, 404
Aretia 66
Aretus 57, 66
Arezo-shamana 266
Arezur 126
Arezur ridge 35
Argalus 152
Arganthone 66
Argayu 67, 362
Arge 24, 66, 165, 212
Arge Woyo 24
Argeia 17, 19, 47, 67, 136, 212, 218
Argeius 316
Argennis 61
Argentina 32
Arges 18, 137, 184, 440, 469
Argestes 182
Argetlam 292, 352
Argia 236, 316
Argiope 25, 67, 112, 129, 174, 381, 457, 458
Argives 67, 143, 212, 230, 383
Argo 170, 218, 286, 468
Argolis 236, 383, 405
Argonauts 8, 9, 10, 13, 16, 23, 31, 35, 38, 49, 57, 65, 66, 67, 72, 76, 83, 112, 113, 114, 115, 118, 133, 137, 145, 147, 152, 162, 172, 174, 175, 189, 192, 205, 212, 213, 216, 218, 230, 231, 232, 240, 249, 287, 289, 297, 298, 314, 316, 318, 328, 342, 360, 366, 376, 377, 379, 380, 381, 382, 383, 385, 386, 387, 390, 411, 440, 450, 457, 468, 473
Argos 6, 10, 12, 17, 19, 21, 49, 62, 64, 65, 67, 68, 112, 130, 132, 142, 152, 175, 176, 213, 229, 235, 289, 314, 315, 316, 349, 365, 370, 377, 378, 379, 380, 383, 390, 404, 433, 450, 451
Argunua 27
Argus 18, 25, 62, 67, 68, 121, 134, 162, 169, 171, 176, 239, 249, 349, 377, 381, 383, 457, 480
Argus of the Hundred Eyes 67
Argus Panoptes 67, 231
arhats 7, 32, 68
Arhhanariswara 65
Ariadne 118, 152, 192, 297, 323, 359, 375, 378, 381, 439, 463
Ariadne 9, 39, 52, 68
Arianrhod 39, 58, 68, 102, 125, 142, 155, 199, 292, 296, 312
Arianrod 68
Ariconte 68, 302
Aricoute 68
Aridella 68
aridity 244, 328
Ari-em-ab-f 75
Aries 194
Ari-hes-nefer 68
Arikara People 343
Arikute 68, 240, 455
Arinitti 69
Arinna 69
Arinnefja 209
Arioi 366, 405
Arion 17, 119, 146, 184
Arisbe 130, 171, 319
Arishta 69, 275
Aristaeus 13, 62, 69, 83, 137, 174, 299, 366
Aristaios 69
Aristomachus 17, 451
Arisudana 69, 275
Arit 5, 477
Arius 293
Arjuna 7, 69, 88, 98, 100, 186, 213, 240, 249, 259, 263, 264, 275, 276, 280, 332, 372, 374, 388, 437, 441, 486, 498
Arjuni 69
Arjunis 69
ark 21, 64, 119, 124, 147, 331
Ark of the Covenant 139
Arkate 69
Arkharokh 385
Arkheokh 385
Arlez 69
armadillo 450
Armageddon 397
Armais 424
Armaita 438
Armaiti 438
Armat 379
Armati 438
Armen 86
Armenak 69, 208, 241
Armenia 29, 38, 59, 64, 65, 69, 71, 73, 75, 87, 88, 139, 149, 157, 180, 181, 201, 202, 208, 211, 229, 242, 249, 250, 255, 268, 297, 310, 321, 335, 339, 344, 379, 380, 399, 408, 411, 413, 422, 424, 429, 438, 469, 472, 487, 495, 498, 502, 520, 521
Armenius 64
armor 11, 96
Armtakundali 513
army 214, 263
Arnaeus 69, 241
Arnaknagsak 417
Arnamentia 69
Arnarquagssaq 343, 417
Arne 21, 69, 104, 115, 166, 316
Arngrim 98
Arnhem Land 154, 334
Aroe 143
Arohi-rohi 70, 298
Arotrios 139
Aroueris 222
Arpacana 70
Arpacanamanjusri 70, 307
Arralu 170
Arrets 70
arrow 106, 221
Arsai 70, 384, 451
Arsan Duolai 70, 483
Arsaphes 70, 205, 214
Arsi Basum 70
Arsiei 189
Arsinoe 62, 72, 171, 417
Arsippe 290, 324
Arson Duolai 6, 70, 483
art 98
Arta 73
Artemis 13, 16, 21, 23, 37, 38, 42, 47, 49, 62, 66, 68, 70, 78, 97, 113, 114, 115, 127, 133, 145, 151, 208, 229, 240, 243, 285, 289, 290, 296, 304, 316, 336, 349, 359, 364, 365, 374, 377, 382, 419, 438, 453, 469, 473, 474, 485, 523
Artemis Calliste 70, 114
Artemis Caria 70
Artemis Caryatis 70
Artemis Laphria 70
Artemis of Ephesus 70
Artemis the Fairest 70
Artetus 440
Arthur 14, 55, 65, 70, 84, 179, 237, 282, 328, 500
Artimpaasa 71
Artinis 71, 268, 399, 461
Artio 71
artisans 150, 160, 241, 264, 274
arts 199, 427
Artus 70
Aruna 71, 187
Arunaua 497
Arundhati 71, 404, 493
Arunta 38
Arupa Lokas 120
Arura 22
Aruru 71, 167, 191, 300, 304, 309, 334, 346, 348
Arushi 71
Arusyak 75, 488
Arvak 4
Arvakr 4
Arvi 209
Arwut 491
Arya 182, 325, 510
Arya Sarasvati 413, 414

www.ebook3000.com

Tan Tien and the Universe

The expression, 'Tan Tien and the Universe', is a reminder to feel your Tan Tien, heart, mideyebrow and crown spiraling and that you are connected to the universe spiraling in the six directions around you.

1. Establish a Complete Location

You will use your Yi, the three-mind power, repeatedly to recharge your Chi for various purposes. You recharge by connecting to the Universal Chi in the six directions of the universe simultaneously. When you charge a particular area or direct Chi into the body to a particular point, you first establish a connection point for the Chi by placing the hand or fingers at an appropriate location on the surface. This is like giving a location for the Chi to go to. Once the location is established and the Chi starts to go there, leave your hands there.

Then you move your attention to where you want the Chi to go in the body. Feel the Chi connected to and charging the intended location.

2. Charge Tan Tien from Universe

When the location connection is established, be aware of your Tan Tien, heart center, mideyebrow and crown spiraling. Be sure that the conscious mind of the heart is lowered to the Tan Tien and the awareness mind of the abdomen is connected to the mideyebrow crown and out to the universe. Feel them connected to the spiraling energy in the six directions of the universe. Let the universe charge your Tan Tien.

3. Don't Stop at the Location

With your focus in the Tan Tien, the Chi will go from there to the 'location' indicated by your hands and then to the intended location in the body. Don't let Chi stop there, however.

4. Direct Chi out the Opposite Side to Universe

Direct your attention to guide the Chi flow through the body and out the opposite side. You want to clear out any blockages and prevent any others from accumulating. You also want to release sick energy and negative forces down into the earth. Let the Universal Chi flow out through the universe and beyond.

Arya Tara 71
Aryama 444
Aryaman 15, 71, 208, 325, 492
Aryan trinity 71
Aryong-Jong 71
As 487
Asa 37, 73
Asa Poorna 422
Asae Yaa 72
Asag 71, 348
Asaheim 72
Asakku 284
Asama 419
Asamanjas 267, 409, 496
asana 185, 304
Asani 25, 26
Asapishachikis 71, 384
Asar 22, 71, 309, 367
Asar-Apis 420
Asarhap 420
Asar-Hap 61, 420
Asar-Hapi 61, 420
Asari 22, 71, 161
Asarri 71, 309
Asartait 367
Asaru 309
Asaruali 309
Asarualim Nunna 309
Asaruludu 309
A'sas 22
Asase 354
Asase Efua 72
Asase Ya 8, 50, 72, 101, 453
Asase Yaa 354
Asbet 72
Ascalaphus 66, 67, 72
Ascalon 419
Ascanius 21, 72, 235, 244
Ascension 327
Asclaphus 231
Asclepius 11, 20, 62, 72, 88, 115, 123, 133, 137, 171, 172, 178, 229, 231, 235, 297, 299, 315, 319, 369, 371, 420
Asdar 73
Asdrestus 17
Aser 73
Aset 242
Asfandarmad 438
Asgard 22, 36, 72, 102, 180, 192, 198, 233, 245, 357, 421, 432, 446, 465, 490, 496
Asgarth 294
Asgaya Gigagei 72
Ash 72
Ash nymphs 236, 316
Ash of Uisnech 7
ash tree 74, 341, 516
Asha 73
Asha Vahishta 45, 48, 73, 78, 138, 238
Ashadha 248
Ashanti People 7, 17, 50, 72, 101, 273, 354, 364, 453
Asharu 309
Ashdar 73, 75, 80
Ashdod 139
Ashebu 477
Ashem 73, 483
Ashemu 73
Ashen 73
Asher 73
Ashera 51, 73
Asherah 73, 75, 86, 87, 200, 206
Asherat 13, 73
Asherat of the Sea 164
Asheratian 75, 79
Ashertu 73
ashes 108, 258
Ash-hrau 72
Ashi Vanguhi 514
A-shih 32
Ashima 42
Ashipu 184
Ashir 73
Ashmadia 74
Ashmun 172
Ashnan 73, 161, 167, 168
Ashrapa 73, 140
Ashshur 73
Ashtar 73, 87, 146
Ashtareth 73, 75
Ashtaroth 75, 122
Ashtart 75, 242, 317, 453
Ashtoreth 73, 75, 242
Ashuku 193, 195
Ashur 55, 73, 242, 309
Ashura 74
Ashurbanipal 74
Ash-Vahishta 73
Ashvamedha 398
Ashvamukhi 74, 511
Ashvatthaman 156, 159, 275, 374
Ashvins 77, 494
Ashwins 77
Ashyggr-drasil 516
Asia 70, 74, 80, 88, 89, 169, 174, 194, 281, 318, 356, 379; *see also* Central Asia
Asia Minor 24, 50, 56, 69, 136, 310, 438
Asiaq 74
Asi-na-duti 282, 458
Asir 71, 367
Asirat 73
Asiri 367
Asirtu 73
Asitanga 74, 427
Ask 74, 166, 321, 358, 496, 497
Askefruer 74
Asken 74
Asklepios 72
Askr 74
Aslog 397
Asman 270
Asmegir 139, 145
Asmegir Citadel 74
Asmodeus 14, 22, 74
Asogguano 74, 362
Asoka 74, 259, 428
Asopia 169, 170
Asopus 11, 19, 57, 74, 130, 243, 320, 359, 376, 404, 405, 410, 432, 434, 461
asp 484
Asparas 281, 399
Asparasa 310, 317, 389
Asparasa Adrika 415
Aspelenie 74
Asrael 14
Asrafel 184
Asrapa 140
Asraphel 14
Asratu 73
Asri 74
ass 51, 74, 77, 88, 166, 268, 321, 352, 371, 464
Assamese People 97
Assara Mazaas 74
Assarac 74
Assaracus 51, 113, 235, 474
assembly 480, 524
Assessors 28, 49, 75
Asset 4
Asshur 55, 73
Assir 73
Assorors 55
Assoros 55
Assorus 97
Assur 22, 71, 73, 95, 133
Assuras 77
Assyria 8, 13, 22, 32, 37, 49, 51, 59, 64, 71, 73, 74, 85, 95, 124, 184, 218, 271, 284, 309, 331, 349, 376, 419
Assyro-Babylonia 32, 37, 55, 58, 59, 63, 64, 71, 75, 77, 79, 95, 142, 143, 161, 167, 168, 188, 190, 228, 241, 242, 272, 304, 318, 330, 334, 336, 342, 345, 347, 353, 404, 413, 430, 443, 451, 466, 483, 484, 487, 520, 521, 522
Ast 4, 75
Astacus 316
Astaik 75, 87
Astamatrikas 75
Astanpheus 75
Astaphaeus 75
Astaphaios 65, 75, 231
Astar 73, 75
Astarete 75
Astart 75
Astarte 16, 37, 51, 61, 73, 75, 95, 96, 123, 139, 243, 384, 394, 453, 479
Astartu 75
Aste Estsan 206
Asten 4
Aster paeus 75
Astereth 73
Asteria 62, 67, 75, 118, 143, 208, 232, 289, 379, 382
Asteric 66
Asterie 80, 152
Asterion 57, 67, 76, 132, 236, 323, 404
Asterios 323
Asterius 174, 323, 414, 456
Asterius 76
Asterodeia 18, 64, 76, 121, 240, 389
Asterodia 379
Asterope 66, 76, 359, 440
Asteropeia 13, 118, 145, 152
Astert 73
Asthertet 76
Asthoreth 75
Asti 76
Astik 75
Astika 76, 450
Asti-neter 477
Astioche 76, 143, 215
Asti-paut 477
Astirati 73
Aston 247
Astoreth 75, 511
Astovidad 76, 492
Astraea 76, 151, 222, 461, 523
Astraeus 76, 104, 105, 135, 169, 174, 351, 370, 379, 416, 522
astralism 325
Astrerodeia 76
Astronoe 72, 76, 137, 172
astronomy 110, 336, 464, 484
Astrope 76, 210
Astyagyia 230, 462
Astydameia 10, 76, 145, 218, 287, 377, 439, 440
Astydameis 81
Astynome 17, 76, 114, 115, 127, 219, 451
Astyoche 13, 51, 72, 76, 130, 171, 216, 218, 231, 377, 431, 474
Asu 26
Asuka 42
Asu-niti 512
Asur 73
Asura 22, 28, 86, 261, 389, 484, 502
Asuras 15, 77, 100, 105, 138, 140, 146, 147, 219, 281, 375, 388, 492
Asuris 15, 77
Asus 22
Asushunamir 77, 242, 451
Asushu-Namir 77, 170
Asu-su-namir 77
Asva 77
Asvaghosa 77
Asvamedha 77
Asvamuttakha 298
Asvapati 416
Asvin 393, 412, 413, 444
Asvina 158
Asvinau 77
Asvins 72, 77, 100, 143, 146, 160, 299, 338, 372, 401, 404, 416, 447, 484, 499, 500
Aswa 280
Aswan 203
Aswini 444
Asyngur 77
Asynja 77
Asynje 77
Asynjor 22, 77, 101, 180, 231, 232, 233
Asynjur 72
Asynor 94
Asyut 60
Ata 78
Atabei 78, 233, 239, 252
Atabyrius 38
Ataensic 78
Ataentsic 78, 518
Ataeusic 78
Atago, Mount 78, 255
Atago-Gongen 78, 445
Atago-Sama 78
Atagucho 369
Atahocan 78
Ataksak 78
Atalanta 38, 66, 67, 78, 114, 117, 219, 231, 250, 300, 316
Atalante 78
Atanea 78
Atanua 78
Atanzah 58
Ataokoloinona 78, 339
Atar 14, 78, 514
Atarate 78
Atargate 78
Atargatis 78, 79, 139, 453
Atarsh 78
Ataryatis 78
Ataryatis Derketo 78, 79, 355, 419
Atchet 396
Ate 79, 171
Atea 79, 201, 313, 364, 399, 452, 492, 493
Atea Rangi 79, 399
Atef crown 70, 75, 212
At-Em 78
Atem 81, 458
Aten 33, 79, 222
Atenor 376
Atergatis 78
Athal 209
Athamantia 79
Athamas 21, 79, 115, 166, 172, 211, 239, 288, 316, 317, 342, 383, 389, 392, 417, 462
Athapascan 515
Athar 79, 242
Atharate 78
Atharva Veda 285, 411, 494
Atharvan 312
Athena 10, 20, 25, 31, 36, 39, 51, 56, 64, 79, 116, 118, 119, 133, 135, 152, 167, 169, 170, 171, 194, 229, 232, 286, 310, 319, 320, 323, 333, 341, 345, 370, 374, 405, 438, 451, 468, 474, 480
Athenaa 79
Athenaia 79
Athene 9, 17, 20, 67, 70, 79, 80, 83, 96, 105, 142, 194, 236, 314, 315, 335, 354, 370, 374, 376, 380, 388, 440
Athenia 212
Athens 9, 11, 21, 52, 56, 57, 67, 80, 104, 118, 135, 138, 146, 170, 171, 174, 219, 240, 297, 314, 315, 319, 323, 359, 360, 365, 389
Athensic 80
Atheret 80
Athirat 51, 80, 164
Athirat the Merciful 80
Athor 206
Athpi 177, 417
Athrar 73
Athtar 73, 75
Athtar 80
Athwya 203
Athyr 206
Atira 228, 468
Atius Tirawa 423, 468
Atius 423

Atla 209
Atlacamini 80, 120
Atlantiades 214
Atlantius 214
Atlas 47, 66, 80, 114, 131, 133, 139, 152, 165, 169, 172, 173, 175, 205, 213, 216, 229, 231, 302, 318, 319, 356, 365, 377, 380, 385, 391, 440, 484
Atlatonan 81
Atmu 81, 458
Atnatu 81, 350
Atola 28
Aton 79
Atonatiuh 81, 288, 469
Atos 24
Atrahasis 58
Atreidae 23
Atreus 20, 23, 81, 218, 318, 377, 465
Atri 81, 404, 437, 500
Atropos 38, 81, 130, 327
Atroposy 177
Atru-she-en-nesert-f-em-shet 4
Atse Estsan 81
Atse Hastin 81
Atseatsan 81, 339
Atseatsine 81, 339
Atsi Hastin 206
Attabeira 78, 197, 239
Attes 81
Attica 9, 26, 97, 113
Attis 24, 52, 54, 81, 136, 137, 158, 212, 334, 412
Attus 81
Atu 4
Atua 79, 81
Atugan 81
Atum 43, 79, 81, 97, 244, 319, 359, 396, 456, 457, 458, 478
Atum-Ra 81
Atum-Re 81
Atumu 81
Atunua 79
Atus 81
Atvins 77
Atymnius 82, 116, 323, 414
Atys 24, 81
Au Sept 82
Auai 4, 82
Aucca 449
Auchimalgen 82
Aud 82, 351
Audhumla 82, 517
Audjal 82
Audr 82
Audumla 82
Auga-nur 24
Auge 70
Augeas 13, 213
Augeian stables 38, 66, 213
Augeias 13, 67, 210, 382
Augelmir 517
Augmentative Immortals 29
Augralids 26
Augusel 65
August Personage of Jade 519
August Supreme Emperor of Jade 519
Augustus 254
Aukar 4, 82
Aukele-nui-aiku 261
Aukert 82
Aulanerk 82
Auler 482
AUM 15
Aumakua 82
Aumanil 82
Aun 82, 358
Aunaauif 60
Aunua 179
Aura 30, 76, 82, 169
Auraka 82
Auramazda 28, 487
Aurboda 164, 190, 198, 252
Aurentil 83
Aurgelmir 82, 517
Aurgenimir 517
Auriga 219, 497
Aurigena 380
Aurigia 380
Aurora 80, 83, 85, 133, 169, 174, 184, 413, 524
Auroras 83
Aurva 83, 409
Aurvandil 83, 197
Aus 83, 97
Ausaas 83
Ausar 367
Ausera 83, 413
Aushedar 83
Aushedar-mah 83
Ausiri 367
Auspicious One 148, 306
Ausrine 83
Aust 242
Auster 351
Austi 83, 160
Australia 36, 38, 55, 64, 81, 84, 89, 91, 92, 101, 143, 146, 154, 158, 170, 172, 187, 191, 193, 235, 236, 238, 251, 253, 258, 261, 263, 273, 281, 302, 303, 304, 308, 322, 328, 329, 330, 332, 334, 350, 352, 353, 370, 392, 395, 396, 397, 469, 471, 483, 504, 505, 506, 507, 511
Austre 83
Austri 83, 321, 351, 441, 506
Austria 28
Autak 83, 85
Authades 83
Autolycus 56, 83, 127, 145, 214, 386
Autonoe 13, 24, 69, 83, 112, 234, 239, 299, 419
Autophyes 21, 351
Autu 79
Autumn 116
Autychus 62, 69, 137
Auxo 195
Avagdu 83, 134, 267
Avaggdu 83
Avaiki 83, 271, 492, 494
Avallach 83
Avallon 83
Avalokitesvara 45, 46, 83, 103, 122, 150, 261, 268, 277, 278, 293, 301, 307, 312, 369, 409, 410, 426, 439, 454, 489, 492, 500
Avalokiteswara 83, 411
Avalokit-Isvara 83
Avalon 71, 84, 328
Avanc 14
Avany 84, 313
Avasta 516
avatars 84, 285
Avatara 84
Avatea 493
Aventina 151
Aventine Hill 151
Avesta 50, 84, 85, 180, 188, 248, 492, 521
Avfruvva 33, 207
Avici 120
Avilayoq 417
Avilion 83, 84
Avilix 509
Avin 472
Avlekete 85, 409, 500
Awahili 84
Awar 84, 85, 446, 468, 520
Awejsirdenee 258
Awful, The 357
Awhiowhio 64, 84
Awitelin Tsita 84, 428
Awitelin Ts'ta 84
Awo-kashiki-ne no mikoto 39
Awonawilona 84, 513
Awonawilone 84
Awun 84
Awwaw 84
axes 26, 86, 103, 108, 120, 155, 191, 223, 343, 498
Axibia 210
Axioche 76, 218, 377
Axius 379
Aya 85, 242, 413
Aya-kashiki no Mikoto 39
Aya-Kashiko-ne no Mikoto 39
Ayar 449
Ayar Aucca 449
Ayar Cachi 306, 449
Ayar Manco 306
Ayar Uchu 306, 449
Ayars 449
Ayida 85
Aylekete 85
Ayllu 85
Aymara People 11, 204
Aymur 85, 274, 511
ayn 51
Ayodhya 85, 398, 408
Aywil 9, 85
Az 85, 501
Azacca 85
Azai-Dahaka 85
Azapane 95
Azariel 85
Azazel 85, 231, 251, 414
Azazil 85
Azdahak 59, 85
Aze 85
Azhdak 85
Azhi 85
Azhi Dahaka 28, 53, 83, 85, 86, 98, 185, 266, 465, 495, 516, 524
Azhi-Dahak 464
Azi 28, 85
Azi Dahaka 78, 85
Azi-dahak 85, 420
Aziza 86
Azrael 14, 53, 86
Azrua 86, 179
Aztecs 10, 12, 13, 28, 62, 80, 81, 86, 113, 114, 118, 120, 122, 125, 129, 130, 131, 132, 133, 163, 180, 194, 225, 226, 227, 228, 232, 234, 240, 244, 246, 249, 288, 294, 295, 299, 303, 311, 312, 314, 320, 321, 324, 325, 333, 335, 338, 357, 363, 364, 368, 375, 376, 384, 395, 420, 422, 449, 451, 456, 459, 460, 466, 469, 470, 471, 472, 480, 508, 509, 510, 514, 517, 518, 524
Aztlan 86, 226, 227
Azur 22, 71, 73

B 86, 120
ba 367
Ba 5, 86, 254, 268, 270
Ba Neb Tetet 92
Ba Xian 163
Baal 13, 22, 36, 51, 59, 70, 75, 86, 87, 93, 103, 164, 165, 200, 274, 282, 290, 317, 328, 384, 424, 451, 458, 481, 510, 511
Ba'al 36, 86, 165
Baal Dagon 139
Baal Enet Mahartet 87
Ba'al Gad 184
Ba'al Hammon 87
Baal Hammon 36, 87, 453
Ba'al Lebanon 86, 87
Baal of Arvad 139
Baal of Mt. Lebanon 13
Ba'al of the Earth 36
Ba'al of Tyre 86
Baal Sapon 87
Ba'al Shamin 75, 86, 87, 487, 488
Ba'al Tsaphon 86
Baalat 87
Ba'alat 87, 95
Baalath 87, 96
Baalim 75, 86
Ba'alim 86
Baalith 95
Baal-Peor 123
Baalsamame 13, 86
Baalshamin 36
Baal-Sutekh 51
Baalti 87, 96
Baaltis 87
Baalzebub 87
Ba'al-zebub 36, 86, 87
Ba'al-zebul 87
Baau 88, 93, 104, 273, 466
Bab 88
Baba Jaga 88
Baba Yaga 88, 98
Baba 88
Babas 88
Babbar 49, 88, 423, 487
Babel 345
Babhru-Vahana 88
Babo 94
baboon god 60
Babru-Vahana 88
Babusum 88
Babylon 17, 27, 59, 62, 73, 85, 158, 161, 170, 172, 187, 199, 202, 226, 241, 243, 270, 271, 272, 279, 284, 290, 291, 292, 295, 296, 304, 307, 311, 319, 331, 344, 345, 346, 347, 352, 363, 392, 408, 410, 414, 418, 419, 431, 432, 447, 469, 484, 486
Babylonia 8, 13, 14, 22, 28, 36, 37, 38, 49, 55, 58, 61, 63, 71, 80, 83, 85, 86, 92, 93, 94, 95, 96, 122, 139, 144, 152, 158, 168, 172, 173, 176, 185, 192, 198, 202, 207, 211, 218, 233, 234, 235, 236, 241, 242, 267, 268, 269, 285, 309, 325, 335, 346, 348, 355, 396, 402, 448, 485, 520, 521, 523, 524
Babylonia-Assyria 13
Bacab 232
Bacabab 94
Bacairi 259
Bacchae 300
Bacchantes 300
Bacchus 24, 88, 98, 130, 152, 153, 159, 182, 230, 253, 290, 300, 316, 371, 415, 421, 427, 431
Bacchus Dionysus 72
Bach-Ma 298
Bachue 88
Backlum 10, 89
Badari 89, 427, 498
Badava 487
Badb 89, 103, 328, 341
Badb Catha 89, 93, 117, 328
Badessy 89
Badhbh 89
Badjang 90
Badtibira 236
Baduh 89
Baduhenna 89
Baeldaeg 90
Bafur 160
Bagadjimbiri 89
Bagavati 374
Bag-Mashtu 89, 268
Bag-Mazda 28, 89, 268
Bagos Papaios 89
Bahai 258
Bahamas 124
Bahman 500
Bahram 89, 495
Bahu 93, 104, 408
Bai Ulgan 89, 283
Baiame 89, 143, 158, 353
Baidya-isvar 427
Baidya-Nath 89
Baidya-nith 89
Baime 143
Bairam 89, 495
Bairavi 89, 257
Baiu amu Tuat 419
Bai-Ylgon 89
Baiyuhibi 89

www.ebook3000.com

Baj Bajaniai 89
Bajanai 89
Bajang 90
Bak 487
Bakairi People 176
Bakasura 90, 275
Bakchos 88
Bakhau 45, 61, 235
Bakkhos 88
Bakongo 354
Bal 86
Bala-Bhadra 90
Bala-Deva 90
Bala-Hadra 90
Balam-Agab 197, 509
Balamma 90, 331
Balam-Quitze 197, 509
Balams 90
Balan 95
Balandhara 99
Balarama 90, 275
Bala-Rama 90, 91, 99, 147, 201, 248, 258, 261, 262, 269, 274, 276, 330, 349, 389, 413, 415, 421, 447, 483, 513
Balbog 90, 91
Bald Rock 460
Baldag 90
Balder 22, 74, 90, 91, 104, 180, 181, 209, 214, 221, 224, 230, 294, 322, 324, 335, 337, 357, 397, 435, 463, 480, 483
Baldr 90
Baldur 90, 490
Baleyg 91, 357
Bali 91, 140, 204, 275, 336, 375, 388, 393, 399, 442, 491, 497
Balin 91, 95
Balius 91, 205, 385, 508, 522
Balmarcodes 91, 201
Balmung 91, 196, 344, 501
Baloi 91
Balor 12, 91, 129, 296
Bal'or 91
Balsamem 13, 86, 87
Balsamin 87
Balshameme 13, 86, 87
Balshamin 13
Balshamin 87
Baltein 96
Baltis 91
Balubaale 91, 271, 329
Balujen 255
Baly 91
Bambara 331, 501
Bambha 139
bamboo 102
Bamun Owtar 91, 490
Bana 91, 276, 393, 485, 488, 497
Ba-nab-djet 206
Banaded 92
Banalingas 92
banana 27
Banana 92
Banba 92
Banbha 45, 92
Banda 344, 459
Baneb Djedet 92
Banebdedet 92, 317
Ba-neb-djet 371
Ba-neb-Tettu 206, 215
Ba-neteru 340
Banitu 242
Banka-Mundi 92
banners 200
Bannik 92, 155, 368
banquets 20, 460
Banshee 92, 115
Ban'shee 92
banshees 89, 105
Banshie 92
Bansith 92
Ban'sith 92
Bantu Iyala 84
Bantu People 91, 102, 252, 269, 271, 273, 290, 329, 354, 365, 513
banyan 63, 92, 109, 337, 471
Baobhan Sith 92
baptism 98
Bar 14
Bara 92
Ba-Ra 4
Baragulla 92
Baranga 467
Barashakushu 309
Barashnum 338
Barbelo 83, 93, 408
barbers 221, 295
Bardad 13
Bardo 47, 48, 55, 84, 185, 215, 272, 293, 303, 304, 369, 513
Bardo World 208, 225, 262, 267, 400, 489, 504
bards 105
Barginj 334
Barhishmati 412
Barku 404
Barley 38
Barn 209, 368
Baron Cimetiere 93, 190
Baron La Croix 93, 190
Baron Piquant 93, 190
Baron Samedi 190
Barshamina 86
Bas 93, 98
basil 270
Basileus 93, 522
Basilisk 93
baskets 93, 292
Basosennin 345
Basque 366
Bassareus 93, 152
Bassarides 93, 300
Bast 70, 93, 98, 206, 298, 313, 331, 370, 418, 419
Basti 75
Basumbwa 362
Basuto 91, 228, 269
Bata 93
Batara Guru 93
Batasura 275
Ba-tau 86
Bateia 93, 218, 231, 235
Bath 4, 5, 92
Bathos 21
Bati Khan 93
Bato Kannon 45, 93, 261
Bato-kwannon 45
bats 114, 182, 191, 524
battle 56, 75, 80, 103, 108, 213, 236, 357, 358, 480
battle ax 51
Battle of Camlan 14
Battle of Moytura 89, 91
Battle of the Mahabharata 100
Battle of the Trees 42
Battle Raven 89, 93
Battle Shaker 93, 496
Bau 104, 184, 346, 347
Ba'u 273
Bau Ba'u 93
Baubo 94
Baucis 94, 381
Baugi 22, 94, 415
Baugreginn Jotunn 322
Bayl 95
Baze 79
Baziba 255, 265, 275, 329, 407, 504
bDug-spos-ma 400
Bea 248
Beach-Field-Master 363
Bealtuinn 96
Bean Si 92
Beann 97
Bean-Nighe 92
Bean-Sidhe 92
Beanu 97
Bear Shirts 98
beard 98, 111
Bearing One 304
Bearing the Dorge in Hand 489
bears 36, 52, 71, 113, 114, 124, 184, 193
beauty 98, 102, 106, 107, 110, 172, 212, 271, 287, 495, 509
Beav 490
beavers 506
Bebryces 49
Becab 28, 94
Becabs 10, 28, 33, 89, 94, 120, 126, 245, 449
bed 128
Beda 22, 94
beech tree 7, 177
beekeeping 69, 94
Beelsamin 522
Beelzebub 87, 414
Beelzebul 87
beer 193, 222
bees 28, 100, 137, 148, 390
beetles 5, 33, 43, 416
Befana 94, 98
Begelmir 95
begging-bowl 48
beginnings and endings 249
Begochiddy 95
Behdet 95, 223
Behdety 95
Behula 305
Bekotshidi 95, 273
Bel 13, 36, 86, 95, 96, 105, 142, 168, 309, 332, 363, 497
Bel Marduk 309
Bel Matati 309
Belatucador 131
Belatucadros 95
Belbogh 90
Beldeg 90
Beldegg 90, 357, 463
Bele 95
Belenos 95, 105
Belenus 95
Beletersetim 95
Belet-Ili 524
Belet-ili 71
Beli 58, 68, 155, 180
Belial 95, 148, 414
Belili 87, 95, 236
Belinus 95, 96, 105
Belisama 95, 323, 420
Belit 73, 87, 95, 142, 331, 346, 348
Belit-Ilani 95, 348
Belit-Ile 95
Belit-Ili 71, 95, 300
Belit-ili Gula 198
Belit-Illi 95, 346, 347
Belitis 95, 96, 346, 347
Belit-Seri 95
Belit-Sheri 95, 269, 334
Belit-tseri 95
Bella Coola People 37, 353, 394, 420
Bellerophon 95, 125, 145, 192, 218, 219, 239, 241, 286, 370, 376, 381, 390, 414, 436, 440
Bellerphontes 95
Bellerus 96
Bellin 95
Bellona 96, 168, 301, 396, 496
Bellonarii 96
bells 7, 133, 194
Bel-Marduk 95
Belos 309
Beloved of Vishnu 285
below the ground 222
Belshim 13, 86, 87
Beltaine 96
Beltan 96
Beltane 96
Belti 96, 242
Beltine 96
Beltirs 452
Beltis 87, 95, 96, 347, 522
Beltis-Allat 37
Beltiya 522
Beltu 87, 96
Belu 86
Belus 13, 20, 25, 83, 86, 96, 97, 142, 151, 286, 289, 291, 345, 382, 388, 465
Ben Edar Hill 173
Benares 99, 120, 313, 499
Bending Hill 335
Bendis 97
Bene Elohim 53
Benen 97
benevolent spirits 69
Bengal 424
Bengali tree goddess 414
Benin 362, 366
Benjaiten 97
Bennu 97, 382
Bennu-asar 495
Bensai-Ten 97
Bentakumari 97
Benten 61, 97, 271, 413, 414, 426, 482, 521
Bentet 4
Bentet apes 4
Benth 425
Benthesicyme 48, 97, 126
Benu 82, 97, 429
Benzai-Ten 97
Benzaiten 97, 426
Benzai-Tennyo 97
Ber 13
Berchta 98
Berecynthus, Mount 97
Berecyntia 97, 136
Bergelmer 97
Bergelmir 97, 104, 252, 465, 517
Berkta 98
Berling 36, 97, 181
Berne 71
Beroe 17, 61, 419
Beroea 17
Berosus 96
Berserker 98
Berserkir 98, 357
Berserks 98
Berserksgangr 98
Bertha 98
Bes 93, 98, 160, 206, 455, 462
Besabes-uaa 425
Besam 98
Bes-aru 477
Beset 98
Besi 98
Besi-shemti, 4
Besla 98
Bestla 98, 104, 494
Besu 98
Bet 93
Beteshu 61
Betsune Yeneca 98
Bettla 98
Betylus 139
Bevarash 86, 98
Beyla 98
Bhadra 89
Bhadra Vira 89, 427
Bhadracharu 407
Bhadrakali 158, 263
Bhadrapada 276
Bhadri-Nath 89
Bhaga 15, 98, 141, 325, 374, 427, 486, 492, 497
Bhagavad Gita 276, 498, 499
Bhagavad-Gita 69, 98
Bhagavadgita 98
Bhagavata 99
Bhagavata Purana 99, 498
Bhagavata-Purana 312
Bhagiratha 99, 186, 187, 409
Bhairab 99, 427
Bhairava 99, 427
Bhairavi 99, 148, 374
Bhairoba 99
Bhairon 99, 196
Bhaisajyaguru 46, 99
Bhaishajyaguru 99, 511, 513
Bhama 99, 276
Bhandra 89
Bhandrakali 89
Bhangi 397
B'haq Ziva 6

Bharadvaja 99, 156, 404, 500
Bharadwaja 99
Bharata 99, 398, 422
Bharatha 99
Bharati 99, 330, 413
Bharawaya 99
Bhargavi 99, 148
Bharundas 99
Bhava 25, 26, 99
Bhavani 99, 148, 257, 374
Bhava-Siva 141
Bhawani 99
Bherri 112
Bhiarav 491
Bhima 34, 63, 90, 99, 100, 158, 159, 249, 280, 372, 490, 494
Bhima-Devi 100, 257
Bhima-sena 99
Bh*imsen* 99
Bhimul Pen 99
Bhishma 100, 187, 503
Bhishmaka 100, 433
Bhogavati 332
Bhogini 332
Bhowanee 99, 148
Bhowani 99, 148, 374
Bhradrakali 100
Bhramara 100, 148
Bhrgu 100
Bhrigu 100, 299, 388, 404
Bhrigu Collection 100
Bhrigus 77, 83, 100, 293
Bhrkuti 454
Bhu 100
Bhu-Devi 100
Bhudevi 100, 149
Bhujagas 332
Bhujangi 279
Bhujyu 77, 101
Bhumi 101, 390, 434, 499
Bhumidevi 491, 499
Bhumija 101, 434
Bhumiya 101
Bhur-Loka 293
bhusparsa mudra 33
Bhuta 141
Bhutanayaki 101
Bhuta-nayaki 148
Bhutapati 101
Bhutas 101
Bhutesa 186
Bhutesvara 101, 427
Bhuvana-Matri 148
Bhuvanisvari 148
Bhuvar-Loka 293
Bia 86, 101, 275, 345, 370, 441, 453
Biaame 143
Biadice 134
Biamban 89, 101, 143
Biambun 101
B-lame 89
Bias 21, 35, 51, 65, 232, 289, 378, 379, 450
Bibhishan 401, 496
Bible 123, 124, 162, 202
Biblindi 357
Bifrons 249
Bifrost 72, 101, 267, 463
Bifur 101, 160
Big Dipper 278
Big Rong 38, 371
Bihar 301
Bihishan 306, 429
Bijadari 496
Bil 22, 101, 220, 307, 311
Bila 101
Bildjiwararoju 154
Bile 58, 102
Bileyg 102, 357
Bilflindi 357
Biliomagus 7
Bilskirnir 102, 463, 465
Bilva 102, 428
Bima 392
Bimbogami 102
Bimbo-Gami 102
Binded 92
Bingo 102, 354
Binzuku 102
Binzuru 102
Bir 13
birch trees 289; bark 193
birds 33, 71, 97, 99, 103, 112, 144, 158, 172, 173, 187, 193, 224, 225, 255, 266, 269, 270, 303, 317, 505, 515
Birqu 13
Birque 13
Birral 89
Birren 119
Birs 74
birth 28, 33, 68, 70, 116, 122, 146, 207, 253, 270, 271, 287, 312, 319, 348, 432; *see also* childbirth
Birushana 140
Bis-Bis 466
Bishamon 97, 102, 271, 285, 425, 426
Bishamon-Ten 102
Bishamonten 102, 426
Bishamon-ten 345
Bishamon-tenno 102
Bishen 148, 188, 375
Bishenjun 258
Bish-nat 99, 102
Bisi-Bisi 242
Bisimbi 354
Bistones 152
Bisu 98
Biswarupa 102
Bith and Birren 102
Bith 119
Bithynia 94
Bitje 102
Bitol 37, 102, 245, 387
Bitsis Dotli'z 81, 206
Bitsis Lakai 81, 206
Bitsis Litsoi 81, 206
Bitsis Lizi'n 81, 206
Bivar-asp 85
Bjelbog 90
Bjorno-hoder 221
Bjort 164
Black 148, 257, 427
Black Agnes 102
Black Annis 58, 102, 112
Black Demon 256
Black Hactcin 103, 200
Black Lord 206
Black Mother 257
Black One 61, 257, 429
Black Surt 444
blackbird 126
Blackfeet People 62
Blackfoot 273, 336
Blackman 354
blackness 205, 385
blacksmiths 36, 97, 105, 107, 159, 164, 195, 197, 223, 234, 245, 265, 276, 360, 457, 475
Blathine 103
Blathnat 103, 136
Bleifstr 294
Bleik 164
Blessed Islands 305
Blessed Isles 166
Blessed Ones 48
Blid 164
blindness 98, 100, 221, 223
Blissful Realm of Lotuses 48
bLo-bzan-chos-kyi-rgyal-mtsan 46
Blodeuwedd 103, 292
Blodughofi 181
blood 73, 99, 140, 225, 437
Blue Jay 24, 103, 239
Blue Tara 267, 454
Blue Throat 345, 427
Bn-Ym 270
Bo 103
Bo Tree 308
Boand 103
Boann 103, 139, 321, 451
Boannan 103
boars 10, 11, 16, 17, 38, 52, 70, 105, 114, 130, 151, 164, 181, 194, 198, 219, 498
Boat of Heaven 236
boats 27, 343, 472
Bochica 103, 124, 126, 128, 135, 180, 198, 509
Bochicha 103, 463
Bod the Red 103
Bodatsu 278
Bodb 18, 54, 103, 139
Bodb Dearg 60, 103
Bodb Derg 103
Bod-Baal 103
Boddhisattvas 103, 454
Boddi 23, 209
Boden 104, 358
Bodhidharma 77
Bodhisattvas 45, 47, 103, 84, 99, 103, 109, 120, 156, 250, 261, 276, 278, 303, 313, 479, 489, 505
Bodiless 258
Bodisats 103
Bodisatvas 103
Bodn 104, 199
Bodvild 501
Boe 104, 358
Boeotia 67, 74, 78, 127, 219, 315, 389, 417, 457
Boeotian Hyria 365
Boeotian Muses 330
Boeotian Orchomenus 131, 170, 173, 195
Boeotus 21, 70, 104, 316
Boetis 19, 104
Bogata 341
Bogatyr 104
Bogatyri 104
Bogu 104
Bohu 93, 104
Boi 112
boils 107
Bokika 103
Bolina 62
Boliva 255
Bolivia 11
Bolmso 98
Bolon-ti-Ku 28
Bolon-tsac-cab 28
Bolthorn 98, 104, 322, 358
Bolverk 94, 104, 357, 415
Bolverkin 357
Bolverkr 104
Bombay 99
Bombor 101, 160
Bomersum 104
Bomong 104
Bona Dea 104, 137, 177, 178, 403
Bondi 23, 209
bones 451
Bong 104
Bonus Eventus 104
Book of Armagh 424
Book of Breathings 243, 428
Book of Genesis 249, 525
Book of Hymns 494
Book of Liturgical Formulae 494
Book of Magic Formulae 494
Book of Songs 494
Book of the Dead 4, 5, 63, 353, 417
Bookkeeper of Heaven 190
bookkeeping 69
books 87
boomerang 101
Bootes 171, 231
Bor 82, 98, 104, 358, 494
Borea 125
Boreadae 104
Boreades 104, 113, 522
Boreas 64, 67, 76, 91, 104, 113, 122, 126, 130, 133, 169, 174, 175, 182, 201, 205, 351, 364, 381, 385, 390, 522
Borghild 220, 430
Bormanus 105
Bormo 105
Born from a Lotus 7, 105
Born from the Ganges 187, 263
Born in the Ocean 248, 285
Born in Water 258
Born of a Jewel 400
Born of Daksha 141, 148
Borneo 53, 272
Borr 104
Borsippa 332
Borus 105, 194, 318
Borve 105
Borvo 105
Bosheth 93, 327
Boshintoi 105
Bosom Friend 71
Bossu 105
bo-tree 109
Bottom Land 436, 518
Boulaia 105
boundaries 122, 128, 459
Bounty 438
Bous 490
Bouyan 34, 105
Bov 103
Boverkin 104
bow 108, 122, 149, 186, 223, 269; *see also* archery
Bowutset 486
box tree 7, 111
boxer 175
Boy-god of love 47
Boyne River 103
Bozaloshtsh 105
Braesia 129
Brage 105
Bragi 22, 105, 199, 214, 232, 357, 483
Brahma 15, 24, 26, 52, 63, 65, 77, 81, 100, 105, 129, 141, 148, 186, 187, 196, 203, 219, 238, 256, 258, 263, 282, 293, 301, 307, 308, 312, 319, 332, 336, 337, 338, 344, 374, 375, 384, 388, 389, 392, 398, 401, 404, 406, 412, 413, 416, 421, 427, 435, 444, 448, 454, 474, 493, 498, 499
Brahma Prajapati 312
Brahma-deva 336
Brahma-Kapla 258
Brahmaloka 105
Brahmanas 141, 186, 312, 406
Brahmanaspati 26
Brahmani 148, 413
Brahmans 15, 25, 77, 91, 100, 105, 148, 186, 187, 196, 219, 256, 264, 281, 282, 293, 310, 319, 336, 373, 384, 388, 389, 392, 400, 404, 406, 415, 421, 427, 444, 454, 487, 492, 493, 498, 511
Brahmarishis 404
Brahmi 413
Brahmin 77
Brahmins 313
brain 138
Brain-uil 437
Bralbral 154
Bralgu 154
Bran 125, 176, 179, 193, 197, 209, 245, 289, 292, 306, 322, 383, 391, 485, 486, 517
Branwen 125, 176, 245, 391
Brattskegg 23, 209
bravery 263
braziers 134
Brazil 25, 61, 68, 136, 198, 214, 240, 247, 254, 255, 258, 271, 277, 302, 306, 322, 327, 376, 408, 455, 478, 515, 520
bread 14, 50
Bread and Water of Life 58
breastplate 107
breasts 270
breath 22, 78, 231, 494
Brechta 98

www.ebook3000.com

Breg 139
Breid 23, 209
Breidablik 90
Breit-Hut 357
Bres 130
Bress 139, 151
Brhaspati 25, 26
Bri 19
Bri Leith 321
Brian 129, 142
Briareus 18, 184, 208, 356, 469
Bribsun 454
bricks *see* masonry
Bride, The 85, 242
bridge 432
Bridge of Pain 277
Bridget 267
Brigantia 112
Bright 100
Bright and Fair 139
Bright Lady 217
Bright Land 470
Bright One 121, 147, 310, 382, 500
Brighu 285
Brigit 97, 103, 139, 142, 323
Brihadratha 249
Brihaspati 454
Brilliant Male 42
Brilliant Sun 228
Brimer 361
Brimo 146, 208, 379, 403
Briseis 12, 113
Brising Necklace 98
Brisingamen 159, 447
Brisinga-men 42
Britain 14, 36, 40, 43, 69, 70, 83, 95, 102, 112, 115, 125, 131, 133, 134, 142, 155, 176, 193, 195, 200, 245, 267, 292, 299, 328, 442
British Columbia 394
Britomartis 151
Brock 159, 198, 199, 432, 435
Brokk 156, 160, 164, 326, 432
Bromius 152
Bronte 210
Brontes 10, 18, 137, 184, 440, 469
broom 88, 148
Broteas 152, 349, 377, 453
Broth of Oblivion 277, 318, 320
Brud 23, 209
Brugh na Boinne 54
Bruigh na Boinne 139
Brut 193
Bryhild 501
Brynhild 431
Bsrahmanic 27
Buan 103
Buan-Ann 58
Buarainech 91
Bubastis 93
Buddha 15, 42, 99, 102, 120, 182, 223, 238, 247, 252, 278, 303, 304, 308, 324, 329, 332, 409, 410, 411, 430, 454, 486, 498
Buddha Amida 182
Buddha Dakinis 141, 268
Buddha Eye 33, 293
Buddha Krotishaurima 215, 422
Buddha Maitreya 410
Buddha of Immeasurable Life Duration 45
Buddha of Immeasurable Light 45
Buddha Sakyamuni 272, 465
Buddhas 103, 140, 193
Buddhasaktis 156
Buddhi 186, 263
Buddhism 7, 9, 15, 31, 32, 33, 41, 45, 46, 47, 48, 63, 68, 70, 77, 78, 83, 97, 99, 102, 103, 105, 117, 120, 121, 123, 124, 126, 128, 139, 140, 141, 147, 148, 149, 150, 151, 152, 153, 156, 162, 163, 166, 182, 183, 185, 188, 193, 195, 196, 199, 200, 204, 211, 215, 220, 224, 237, 249, 250, 251, 253, 256, 258, 261, 264, 267, 268, 273, 274, 281, 282, 285, 290, 293, 301, 303, 304, 307, 308, 313, 315, 317, 319, 322, 324, 326, 329, 332, 334, 338, 348, 350, 363, 371, 389, 397, 407, 408, 409, 410, 411, 413, 422, 425, 426, 430, 435, 439, 440, 442, 448, 454, 458, 465, 467, 478, 479, 481, 486, 488, 489, 490, 491, 492, 493, 495, 497, 499, 500, 504, 510, 511, 513, 516, 517, 524
Buddhistic Hinduism 310
buffalo 77, 158
Buffalo Monster 302
Bugan 506
Bugand 252
Buganda 271
Bui 112, 209
builders 235
Bulaia 79
bull 11, 13, 26, 50, 55, 57, 61, 62, 70, 73, 75, 81, 87, 88, 93, 106, 109, 147, 158, 164, 173, 191, 213, 317, 323, 325, 449
Bull of Amentet 61
Bull of Confusion 244
Bull of Minos 323
Bull of Ra 244
Bull of the Marathon 52
Bull of the Underworld 61
Bull of the West 367
Bull-fiend 69
Bumba 353
Bumerali 370
Bundahish 85, 189, 468, 521
Bundahishn 248
Bundinskeggi 209
Bunene 423
Bunjil 89, 143, 353
Bunosi 255, 310
Bur 209
Burait 32, 308
Burganda 256
Buri 82, 98, 104, 517
burial 123
Buriat 270
Burma 220, 338, 408, 461
Burning 158, 257
Bursiris 367
Buryat People 172, 437, 452, 453
Burzhin Mitro 516
bushel basket 278
Bushel Mother 473
Bushmen 112, 160, 190, 228, 254, 283, 476
Busiris 59
butchers 122, 177, 360
Butes 61, 67, 170, 218
Buto 195, 341, 445, 446, 457, 481, 484, 503
buttermilk 113
Buxenus 7
Byamee 89
Byamspa 303, 320
Byanu 97
Byas 493
Byblos 87, 91, 367
Byelobog 91
Byggvir 98
Byju-Nath 89
Byleipt 294
Byleipter 294
Byleist 294
byliny 104
Bythios 21, 351

Caanan 8
Cabaguil 387
Cabeiro 391, 462
Caberi 137, 233, 254, 457
Cabiri 138
Cabiria 119
Cabracan 227
Cabrakan 502
Caca 112, 315, 495, 502
cacao 164, 270
Cacce-Olmai 112
Cacia 112
cactus 122
Caculha Huracan 197, 228
Cacus 112, 315
Cadmus 13, 24, 25, 69, 83, 112, 130, 162, 165, 166, 208, 229, 234, 238, 297, 312, 378, 381, 386, 419, 438, 457
caduceus 318
Caecinus 112, 404
Caelestis 453
Caelus 484
Caeneus 67, 112, 133, 382, 390
Caenis 112, 241, 387
Caenus 67
Caer Ibormeith 54
Caer Ludd 292
Caesar 153
Caesar Augustus 235
Cagn 112, 132, 133, 190, 254, 283, 363
Cailleach 150
Cailleach Bheare 112, 114
Cailleach Bherri 112
Cailleach Bheur 14, 112
Cailleach Mor 112
Cailleach ny Groamagh 112
Cain 13, 14, 113
Caintigerna 305
Caipre 173
Cairima 465
Caitya 440
caitya 7, 283, 303
Cajolom 227, 394
Cakra-samvara 156
Caksusi 63
calabash tree 228
Calaeno 62
Calais 67, 104, 113, 126, 205, 256, 364, 382, 390, 522
Calakomanas 113
calamity 278
Calchas 11, 23, 35, 113, 462
calendar 268, 278
California 134
Callalamma 113, 331
Calli 10, 113, 456
Callidice 387
Calliope 11, 17, 62, 67, 113, 133, 217, 291, 330, 366, 433, 523
Callipygos 61
Callirius 431
Callirrhoe 11, 113, 119, 127, 130, 152, 162, 187, 190, 235, 297, 356, 474
Callirrhoe
Calliste 113
Callisto 113, 371, 523
Call-of-the-Infinite 276
Cally Berry 112, 114
Calumniator, The 85
Calus 378
Calyce 21, 114, 115, 166
Calydon 17, 21, 27, 38, 67, 70, 114, 131, 213, 218, 359, 379, 383, 385, 387, 391, 440, 462, 473
Calydonia 10, 11, 16, 38, 66, 70
Calydonian Boar 114, 116, 135, 162, 232, 249, 284, 316, 328, 359, 376, 377, 386, 457, 473
Calydons 114
Calypso 66, 80, 114, 173, 229, 339, 356, 385
Cama Ananga 258
Camalotz 114, 508
Camaxte 460
Camaxtle 125, 508
Camaxtli 114, 288, 325, 368, 460, 508
Camazotz 114, 524
Cambodia 64, 105, 187, 397, 495, 498
Camdhen 259
Cameiro 115
Camena 180
Camenae 114, 116, 163
Camenae Muses 330
Cameroon 293, 354
Cameroons 521
Camicus 138, 323
Campe 115
Camulos 115
Camulus 115, 131
Camunda 257
Canaan 8, 13, 36, 51, 70, 73, 74, 75, 80, 87, 123, 139, 164, 170, 184, 327, 348, 384, 402, 417, 422, 451, 510, 514
Canace 21, 37, 57, 115, 133, 134, 166, 169, 222, 240, 299, 349, 474
Canada 16, 37, 506
canals 167
Canam-Lum 501
Canathus 236
Canda 115, 158, 257
Candelifera 115
Candi 257
Candra 121
Candramas 121
Canens 384
cannibalism 30, 37, 101, 141, 172, 269, 293
canoes 30
Canola 115
Canopus 24, 115
Canthus 67, 115
Cantul-ti-Ku 28, 94
Caoineag 92, 115
Caointeach 92, 115
canoes 277, 436, 475
Caolainn 112
Capaneus 17, 76, 115, 219, 440
Cape Kasasa 347
Cape Pelorus 433
Capella 333
capes 305
Caphaurus 9, 115, 118, 338
Capitoline Triad 468
Cappadocian 97
Capra 19
Caprakan 115, 198
Capri 433
Capricorn 19, 40, 303
Capricornus 492
Capys 51, 286
Car 62, 115, 119, 136, 266, 349, 383, 394, 415, 457
Caragabi 115, 479
Caratus 101
Cardea 115, 249
Caria 115
Carian pirates 96
Carib 231, 274, 295, 304
Caribbean Sea 122, 303, 360, 515
Caribo 139
Caribou Eskimo 384
Cariclo 123, 356
Caridwen 116
Carius 115
Carlin 112, 116
Carme 523
Carmenta 114, 116, 176, 388
Carmentis 116, 388
Carna 116
Caroline 82
Caroline Islands 291, 296, 362, 436
carpentry 38, 256, 295, 436, 452
Carpo 116, 222, 461
Carpus 127
Carrier of the Night 470

Carthage 25, 36, 72, 75, 87, 151, 172, 213, 453
Carutius 10, 180, 287
Caryatids 70
Caryatis 115
Carys 115
Cascade of Andvari 52
Cascus 112
Cashel 162
Cassandra 20, 23, 31, 62, 116, 145, 374, 378, 457
cassia tree 355
Cassiepeia 116
Cassiopea 116
Cassiopeia 52, 64, 82, 116, 118
Cassite 404
Cassotis 333
Castalia 62, 113, 333
Castalius 118
Caster of Lots 284
Castor 9, 35, 67, 116, 136, 153, 232, 250, 288, 382, 386, 480, 523; and Pollus/Pollux 116
castration 49, 132, 135
Caswallwan 102, 117
cat 43, 93, 102, 111, 313
Cataclothes 205
Catamitus 117, 187
Cataracts 59, 415
Catequil 117, 136, 304
Catha 117
Cathbad 135
Cathena 117
Catreus 9, 52, 68, 131, 192, 297, 323, 375, 383
Cattegat 19
cattle 11, 13, 15, 16, 25, 26, 30, 32, 42, 50, 55, 57, 61, 62, 69, 70, 73, 75, 82, 87, 89, 105, 107, 110, 112, 129, 142, 147, 151, 206, 207, 209, 215, 239, 259, 265, 266, 284, 328, 335, 348, 353, 370, 388, 389, 390, 406, 407, 434, 442, 443, 487, 493, 501, 517, 521
Cattle Raid of Cooley 300
Caturix 477
Cauac 94
Caucasians 16, 117, 125, 162, 438, 480
Caucassus, Mount 391
caul 202
cauldrons 43, 65, 106, 360, 477
Caurus 522
Cauth Bodva 89, 117
Cave of Origin 306
Cave of Refuge 62
caves 62, 102, 104, 114, 136, 177, 222, 306
Cavillaca 132
Ce Acatl Quetzalcoatl 395
Ce Actl 472
Ceacht 117, 139
Cearas 117
Ceasar 119
Ceatus 13
Cebren 76, 359, 404
Cecrops 26, 184, 214, 372
Cedalion 117, 160, 212, 365
cedar tree 270, 307
Celaeno 20, 117, 143, 165, 297, 354, 385, 440
Celenderis 412
Celestial Cow 341
Celestial Dog 122
Celestial Garden 120
Celestial General Wei 505
Celestial Jewel-spear 246
Celestial Kings 117
Celestial Mandarin 123
Celestial Master 122
Celestial Monster 508
Celestial Prince Liu 224
Celestial Toad 117, 122
Celeus 6, 117
Celmis 117, 138
Celts 7, 12, 14, 17, 18, 22, 29, 30, 34, 40, 42, 45, 52, 54, 55, 58, 65, 68, 70, 71, 73, 83, 84, 89, 91, 92, 95, 96, 97, 102, 103, 105, 112, 115, 116, 117, 119, 129, 130, 131, 132, 133, 134, 135, 136, 137, 139, 141, 142, 144, 145, 151, 153, 155, 157, 158, 159, 160, 164, 166, 173, 176, 177, 179, 180, 193, 194, 195, 196, 197, 199, 209, 265, 267, 274, 289, 290, 292, 296, 299, 300, 305, 306, 309, 312, 320, 321, 328, 336, 341, 342, 352, 360, 384, 391, 392, 393, 403, 405, 416, 418, 420, 441, 442, 449, 454, 460, 477, 485, 486, 495, 517
cemeteries 58, 60, 101, 108, 110, 143, 267, 435, 475
Cenchreis 16, 117, 129, 331
Cengus 54
Cenn Cruaich 117
Centauras 117
Centauroi 117
Centaurs 6, 13, 21, 27, 69, 72, 112, 117, 135, 157, 175, 213, 218, 229, 245, 249, 257, 287, 297, 316, 342, 343, 377, 381, 382, 387, 431, 438, 461
Centaurus 62, 117
Centeal 129
Centeotl 129, 146
Centimani 19, 118, 208
Centipede 118
Central America 90, 122, 127, 128, 197, 244, 245, 302, 351, 360, 515, 523
Central Asia 9, 45, 171, 187, 276, 368, 384, 443, 465, 507, 512
Centzon Huitznahuas 131, 133, 227, 325
Centzon Mimixcoa 118
Centzon Totochtin 118, 132, 246, 375, 460
Centzon-Huitznahuas 118
Centzonhuitznauac 118
Centzontotochtin 357
Centzonuitznaua 118
Ceos 118, 184, 289
Cephalion 9, 115, 118
Cephalus 13, 26, 31, 67, 118, 119, 145, 152, 169, 211, 214, 284, 380
Cepheus 20, 25, 52, 67, 116, 118, 142, 382, 440
Cephissus 11, 76, 118, 173, 236, 289, 337, 404, 465
Cer 22, 118, 122, 170, 230, 266, 327, 352
Ceramus 68, 118, 152
Cerberus 72, 113, 119, 125, 162, 201, 213, 438, 455, 480
Cercaphus 118
Cercopes 119, 375
Cercyon 119
Cerdo 115, 119, 349, 383
ceremonies 290
Ceres 94, 119, 125, 146, 151, 253, 290, 311, 487
Ceridwen 267
Cerklicing 119
Cermait 119
Cernobog 124
Cernunnos 119, 441
Cernunnus 119
Cerridwen 267
Cerycon 212
Cerynean stag 213
Ceryx 26, 118, 119, 174, 214
Cesair 119
Cesar 119
Cesara 119
Cesarea 119
Cessair 92, 102, 119
Ceterni 339
Ceteus 113
Cethe 119, 151
Ceto 119, 135, 162, 168, 174, 184, 194, 195, 216, 284, 315, 342, 383, 387, 388
Cexochitl 129
Ceylon 84, 313, 398
Cezalcouati 278
Cghene 120
Chaabu 159
Chaac 120
Chaam 10, 89
Chac 27, 86, 120, 121, 469, 508
Chac Mol 221, 254
Chacamita 164
Chaco People 33
Chacs 94, 120, 520
Chadanta 120
Cha-dog-ma 120, 208, 422
Chafura 269
Chagan-Shukuty 368
Chahuru 120
chain 178
Chaitraratha 120, 282
Chakdor 489
Chak-na-rin-chhen 400
Chakra 120, 158, 186
Chakra Sambara 120, 411
Chakra-Raja 186
Chakravala 120, 149
Chakrisvari 120, 511
Chak-yu-ma 55, 422
Chala 120
Chalchihuitli'cue 120
Chalchihuitlicue 120, 288, 295, 469, 509
Chalchihuitzli 125
Chalchiuhcihuatl 508
Chalchiuhcueye 120
Chalchiuhtlicue 13, 80, 120, 121, 230, 244, 288, 312
Chalchiuhtotolin 460
Chalchuihutonatiuh 288
Chalciope 18, 76, 121, 239, 314, 383, 389, 462
Chalcipe 67
Chalcis 376
Chalcodon 6, 12, 121, 165
Chalcomedusa 284
Chalcon 121
Chaldaea 188, 309
Chaldea 5, 8, 10, 37, 50, 51, 66, 71, 73, 85, 139, 161, 185, 191, 208, 228, 242, 270, 300, 304, 318, 331, 334, 348, 355, 363, 408, 423, 431, 466, 468
Chalean 60
Chalmecatciuatl 121
Chalucas 121
Cham 63
Chamacoco 172
chameleon 24, 290, 292
Champ-pa 303, 304
Chamunda 121, 158, 257
Ch'an line 77
Ch'an Tzu-fang 120, 475
Chand 305
Chanda 158
Chanda Maharoshana 121
Chandamaharoshana 9, 121
Chandi 121, 148, 158, 473
Chandika 121, 158, 257
Chandra 121, 281, 374, 416, 436, 437, 486, 493
Chandrakanta 121
Chandraprabha 121
Chandra-Prabha 199
Chandrapura 499
Chang 121, 122
Chang Fei 177, 277
Chang Fei Khang Fei 122
Chang Hsien 121
Chang Kung 121
Chang Kuo-lao 163, 202
Chang Tao-ling 122
Chang Tung-Ch'ang 123
Chang Ya 505
Chang Ya Tzu 505
Chang Yuang-Hsiao 121
changelings 159
Chang-Kuo-Lao 68, 122
Chang-O 117, 122, 230, 516
Chango 122
Chang-sheng 277
Ch'ang-Sheng T'u-Ti 122
Chang-Sien 121
Chantico 122
Chanura 262
Chao Kung-ming 475
Chaos 22, 30, 42, 55, 63, 122, 135, 170, 171, 175, 184, 227, 351, 429, 452, 455, 481
Chaquen 122
Char 149
Chariclo 377, 379, 382
chariots 50, 106, 170
charioteers 71, 98, 109, 219, 497
Charis 20, 25, 195
Charites 195
Charities 212, 230
charity 486
charm 49
Charming Splendor 467
Charming Woman 148, 291
Charon 11, 22, 118, 122, 123, 131, 170, 191, 194, 201, 266, 327, 352, 455
Charumati 123, 433
Charun 123, 201, 414, 415
Charvi 282
Charybdis 48, 56, 184, 342, 360, 417
Chasca 123, 304
chastity 102
Chaun-lun 146
Chavah 176
Chavva 176
Chchulainn 321
Chebeldei 6, 123
Chedi 415, 433
cheer 14
Cheiron 10, 11, 13, 17, 21, 69, 72, 117, 123, 135, 218, 249, 257, 315, 316, 356, 377, 381, 382, 461
Chelidon 18
Chelovek 155
Chemchuevi 134
Chemmis 380
Chemos 414
Chemosh 123, 423
Chem-pa 320
Ch'en 123
Ch'en Ch'i 317
Chen Jen 123
Chen Resic 84
Chen Wu 123
Ch'eng Huang 123, 350, 429, 442
Cheng Lung 211, 317
Cheng Wu 123
Ch'eng-huang shen 123
Chenrezig 123, 124
Chenrgzi 123
Cheou-Lao 286, 412
Chepera 269
Cherakan-Ixmmucane 127
Cheresi 84
Chernobog 119, 124
Cherokee People 6, 25, 55, 72, 84, 190, 236, 261, 353, 446, 470, 475, 482, 483, 486
Cherruve 124, 384
cherries/cherry trees 272, 514
Cherubim 53, 124
Chespisichis 268
Chhaya 124, 444, 453
Chhwaskamini 124
Ch'i 122, 124, 279, 517
Chi 124, 443
Chia 124, 509
Chibcha 88, 122, 126, 135, 180, 198, 341, 463
Chibchachum 124
Chibchacum 103, 124
Chibecha 103

www.ebook3000.com

Chibiabos 127, 335
Chibilias 245
Chibirias 232
Chichen Izta 244
Chichimees 114
Chicimecs 114, 509
Chickasaw People 6
Chickcharney 124
Chicken Hawk 511
Chicomecoatl 125, 422, 508
Chicomexochit 125, 470, 471
Chicomexochitl 471
Chicomoztoc 125, 129
Chiconamictlan 125
Chiconauapan 125
Chicuna 125
Chicunauhmictlan 125, 320, 321
Chidambaram 338
Chie 124
Chief of Heaven 78
Ch'ien Niu 126, 266
Ch-Ien Niu 120
Ch'ien-T'ang 125
Ch'ih Kuo 125, 326, 439
Chih Neu 126
Chih Nu 126, 352
Ch'ih Yeo 125
Chi-haya-buru 259
Chih-Nii 120, 126
Chih-Wen 125
Chikisani 361
Chikisanti 125
Chilam 120
Child of the Waters 51
childbirth 32, 33, 50, 66, 78, 94, 95, 98, 99, 107, 115, 125, 129, 135, 151, 163, 207, 212, 217, 242, 245, 250, 253, 284, 292, 299, 304, 314, 319, 328, 331, 341, 348, 373, 383, 388, 418, 455, 462, 470; *see also* birth
children 98, 102, 111, 224, 225, 272, 333, 341, 402, 425, 466
Children of Don 68, 125, 155, 477
Children of Llyr 125
Children of the Earth 136, 189
children of the rain 136
Chile 32, 82, 124, 127, 170, 198, 207, 225, 226, 320, 344, 384
Chilenga 290, 292
Chilidanope 137
Ch'i-Lin 124, 439
Chimaera 19, 96, 125, 162, 174, 202, 239, 438, 440, 480, 522
Chimaira 125
Chimalman 125
Chimalmat 115, 198, 502
Chimalmatl 125
Chimata-no-Kami 126, 413
Chimera 125
Chiminagagua 126
Chiminagua 126
Chimini-Pagus 126
Chiminiquagua 126
Chiminizagagua 103, 126
Chimu 241
Chin 10, 126
Chin Chia 126, 128
Ch'in Ch'iung 317
Chin Nu 126
Ch'in Shu-pao 225, 317
China 30, 32, 45, 50, 59, 68, 84, 102, 103, 117, 120, 121, 122, 123, 124, 125, 126, 127, 128, 132, 149, 151, 156, 163, 170, 177, 178, 181, 182, 183, 202, 211, 221, 224, 225, 226, 227, 230, 232, 251, 252, 265, 266, 270, 272, 276, 277, 278, 279, 280, 284, 286, 288, 290, 291, 292, 295, 296, 298, 303, 307, 310, 317, 318, 320, 324, 326, 329, 333, 346, 350, 352, 363, 369, 371, 378, 383, 384, 392, 410, 412, 413, 423, 424, 425, 426, 427, 428, 429, 430, 439, 442, 443, 448, 449, 453, 454, 465, 466, 467, 473, 475, 476, 478, 488, 490, 503, 504, 505, 507, 508, 512, 513, 515, 516, 517, 518, 519, 520
Chincha 225
Chinese Ti-tsang 512
Ching Te 519
Ching Yuh 266
Ching-Tu 126, 252, 279
Chinnamastica 148, 257
Chinnigchinich 126
Chinnintamma 126, 331
Chinook People 24, 103, 239, 243
Chintamani Lokeswara 294
Chinta-Mani 129
Chinvat 45
Chinvat Bridge 22, 52, 126, 325, 400, 432
Chinvat Peretu 126
Chione 9, 62, 83, 97, 104, 113, 126, 174, 364, 522
Chios 365
Chipiapoos 127
Chipi-Caculha 197
Chippewa People 98, 154, 160, 192, 213, 214, 221, 272, 321, 325, 327, 334, 357, 504, 505, 506
Chiquinau 127, 129, 162, 324, 395, 500
Chirakan-Ixmucane 127, 245, 387
Chirion 213
Chiron 12, 123
Chiruwi 127
Chi-Sheng Sien-Shi 132
Ch'i-ti 423
Chitragupta 512
Chitrangada 88, 415, 503
Chitra-ratha 186
Chiu I 127
Chiu Kung 127
Chiun 402
Chiuta 290, 330
Chiutcoatl 129
Ch'i-You 124
Chlevnik 127, 155
Chloris 47, 49, 65, 67, 127, 180, 316, 328, 341, 379, 451, 522
Chnemu 269
Chnoumes 269
Chnoumis 269
Choco 115, 455, 479
Choctaw People 6, 211, 316, 335, 360, 361, 424, 426
Chokaniok 320
cholera 196, 491
Cholula 424
Chonchonyi 127
Chons 268
Chonsu 127
Chooser of the Slain 357
Choreb 124
Chos-Rgyal 512
Choun 239, 497
Chousorus 368
Christ 153, 250, 307
Christianity 8, 14, 172, 510
Christmas 284
Chronos 22, 127, 135, 210
chrysanthemum 271, 420
Chrysaor 113, 127, 162, 190, 315, 356, 376
Chryse 66, 127, 132, 370, 382
Chryseis 23, 127
Chryses 23, 127, 128, 324, 382
Chrysippe 143
Chrysippus 76, 81, 128, 218, 377, 378
Chrysogeneia 128
chrysolite 143
Chrysorthe 62, 133
Chrysothemis 23, 128, 165, 240, 287, 439
Chthon 128, 184
Chthonian 173
Chthonophyle 297
Chtonius 354
Chu 128, 425
Ch'u Chiang 128
Chu Ch'ieh 439
Chu I 126, 128
Chu Jung 128
Ch'uan Hou 467
Ch'uang-Kung 128
Ch'uang-Mu 128
Chuan-Lun 128
Chuan-Lun Wang 128
Chuan-lun-wang 466
Chuchaviva 135, 341
Chuchulain 135
Chu-kiang 128, 146
Ch'u-kiang wang 466
Chukum 128
Chukwu 128
Chunda 128
Chung-Li 202
Chung-Li-Ch'uan 128
Chung-Liu 128, 475
Chunus 268
Chupunika 128, 404
Churl 464
Chuvalete 128
Chuvash 254
Chwezi 128
Chyana Lokas 120
Chyavana 77, 100, 299, 442
Ciaga 127, 128, 162, 324, 395, 451, 500
Cian 119, 129, 130, 151, 296, 305
Cibola 125, 129
Cigfa 391
Cihauteto 129
Cihuacoatl 129, 470, 471
Cihuatcoatl 129, 451
Cilix 25, 112, 129, 165, 381, 457
Cilla 129, 215, 416
Cin 129
Cinni 129
Cintamani 129, 277
Cinteotl 129, 132, 295, 375, 508, 509
Cinvat 126, 238
Cinxia 253
Cinyras 16, 117, 129, 287, 331
Cipactli 129, 131, 226, 460
Cipactonal 288, 363, 368, 451
Cipatonal 222
Cipattoval 368
Cirape 129, 134
Circe 18, 27, 53, 114, 129, 192, 210, 310, 314, 356, 375, 379, 384, 417, 439, 457
Circle 340
circumcision 8
Cisa 130
Cisseus 200, 461
Cissos 152
Citalicue 130, 470
Cit-Bolon-Tum 130
Cithaeron, Mount 358
cities 79, 86, 123, 172
Citlalicue 133
Citlallatonac 125, 133, 338, 470; and Citalicue 240, 471
City of the Gods 41, 459
Ciuacoatl 129, 471
Cium 339
Cius 387
civilization 197, 199
Ciza 130
Clad in Hide 257
Clad with the Quarters 148
clay 110, 202, 203
Cleio 130, 229
Cleite 130, 143, 319
Cleitus 104, 130
Cleobule 76, 382
Cleodora 130, 143
Cleolla 23, 130, 318
Cleone 74, 130
Cleopatra 38, 104, 113, 126, 130, 143, 205, 235, 316, 364, 381, 386, 474, 522
Cleophyle 231
Cleostratus 130, 318, 438
Cleothera 115, 205, 319, 372
Cleta 195
Clio 130, 330
Cloaca Maxima 130
Cloacina 130
Clonia 354
cloth spinning 126, 200, 326
clothing 223, 392, 486
Clotho 68, 81, 130, 177, 327
Clothru 130
clouds 36, 89, 106, 117, 181, 237, 325, 343, 383, 395, 413, 519, 520
clown 232, 329
clubs 99, 100, 223, 267, 268, 269, 512
Cluracan 130
Cluricanes 130, 158
Cluricaune 130, 289
Clutoida 131, 420
Clyde 131, 420
Clymene 8, 16, 19, 20, 22, 35, 62, 67, 78, 80, 118, 131, 147, 151, 169, 211, 231, 318, 319, 324, 356, 379, 380, 383, 391, 462
Clymenus 131, 170, 175, 380, 389
Clytemnestra 20, 23, 116, 128, 165, 240, 287, 288, 365, 381, 382, 393, 453, 480
Clytia 131
Clytie 131, 211, 319, 331
Clytius 58, 175, 190, 215, 469
Cmok 524
Cnidia 61
Cnossus 68, 138
Cnuphis 269
Coaibai 364
coal 94
coast 81
Coatepec 131, 227
Coatlicue 118, 125, 131, 133, 227, 420, 469, 471
Coatrischie 78, 131, 197
cobra 111, 481
coca 519
Cocalus 138, 323
Cocidius 115, 131, 418
Cocijo 469
Cockatoo-man 308
cocks 31, 41, 43, 66, 172, 179, 198, 216, 318
coconut palm 296
coconut trees 255
coconuts 27, 83, 261, 307, 439, 450
Cocytus 11, 131, 289, 318, 324, 382, 404, 455, 503
Codex Vindobonensis Mexic.1 395
Coeculus 112
Coel 115
Coelus 484
Coem 214
Coeranus 6
Coeus 75, 118, 135, 175, 382
coffer 183
coffin 111
Cogaz 112, 132, 190
Coil of Nectar 48, 513
coins 123, 154
Colchis 8, 18, 64, 67, 76, 121, 137, 194, 210, 240,

250, 315, 356, 380, 381, 383, 389
Cold 51, 244, 460
Cole 115
Colhuacan 132, 133
Colhuatzincatl 118, 132
Colias 61
Colla 449
Collao 164, 443
Collao 51
Collection of Written Leaves, The 387
Colombia 88, 103, 115, 124, 128, 225, 399, 455, 463, 479, 509
Colonus 57, 359, 455
Colophon 18, 64
Colossus of Rhodes 211
Comana 66, 127, 132
Combalus 132
Cometes 19, 57, 67, 76, 132, 381
commerce 116, 339, 362, 495, 501, 510
Communicator, The 368
Companions of the Day 470
compasses 226, 352
compassion 423, 458
Comus 130
Comyria 115, 136
Con Ticci Viracocha 497
Con Ticci Viracocha Pachayachachic 497
Conabos 382
Conaire the Great 139
conch shells 48, 158, 186
Conchobar 130, 135, 144
Condates 131
Confucianism 132
Confucius 132, 286
Congo 290, 324, 354, 396
Congo-Angola 258
Coniraya 132, 369, 485
Coniraya Viracocha 132, 497
Conlaoch 60
Conn 60
Connla's 103
Conopa 132
conquerors 43, 158, 188, 401
consciousness 33, 77
Consentes 371
consolation 220
constellation 266
construction 347
Consus 132
contracts 321, 501
Controller of Life 220
cooking 181
cooks 52
Coon 10, 56, 192, 461
Copacati 132
copper 348
Copreus 81, 218, 377
Copts 18, 60, 351
Coqui-Cilla 132
Coqui-Xee 132
Cora 128
coral reef 217
Corb 132
Corc 196
Corcyra 74
Cordelia 292
Core 379
Corinth 19, 74, 96, 115, 135, 314, 359, 378, 381, 386, 433, 454
Coritiacus 131
corn 62, 116, 119, 121, 125, 139, 146, 152, 185, 231, 234, 304, 325, 327, 342, 344, 360, 379, 418, 521; *see also* maize
Cornu Copiae 132
cornucopia 11, 22, 37, 40, 132, 159, 180, 205, 340, 462
Corona 62
Corona Borealis 68
Coroneus 133
Coronis 62, 72, 132, 133, 169, 241, 382, 387
Coronus 19, 67, 133
corpses 58, 157, 185, 224, 225, 258, 267, 273
Corus 133
Corybantes 113, 133, 136, 137, 210, 403
Corybas 133, 137, 232
Corynetes 133, 379
Corythus 359, 374
Cosmic Dancer 427
Cosmic Egg 22, 378, 392, 497
Cosmocrator 133
Costa Rica 335
Coti 112, 133, 190
Cottus 133, 184, 469
Cottus 18
Cottys 133
Cotus 133, 208
Cotys 113
Cotzbalam 114, 133, 508
Couatlicue 131
Courageous Thunderbolt Soul 490
Couretes 136
Courtesans 61
courtyard spirits 159
Coventina 133
Covering, The 502
Covetina 133
cowboys 396
cowgirls 194, 396
cowherds 120, 126, 194, 275
cows and associated deities *see* cattle
Coxcos 133
Coxcox 129, 133, 338
Cox-cox 133
Coxcoxtli 129, 133, 226, 509
Coyolxauhqui 118, 131, 133, 194, 227, 320, 456, 509
Coyote 133, 134, 241, 243, 481, 509
Cozaana 132
crafts and craftsmen 65, 103, 406
Cranaus 135
crane 296
Crantaeis 208
Crantor 76
Crataeis 383, 417
Cratus 101, 345, 441
creativity 144
creators/creation 4, 6, 7, 8, 9, 13, 14, 17, 18, 20, 22, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 37, 39, 40, 42, 43, 44, 46, 48, 49, 50, 52, 53, 54, 55, 58, 59, 62, 63, 65, 66, 70, 71, 72, 73, 74, 75, 77, 78, 80, 81, 82, 83, 84, 85, 88, 89, 90, 92, 93, 94, 96, 97, 98, 100, 102, 103, 104, 105, 106, 107, 108, 110, 111, 112, 114, 115, 120, 121, 122, 125, 126, 127, 129, 132, 133, 134, 135, 138, 139, 141, 143, 144, 146, 148, 151, 152, 154, 158, 159, 160, 160, 161, 167, 168, 170, 171, 172, 175, 177, 179, 180, 181, 182, 184, 187, 188, 189, 190, 191, 193, 197, 198, 199, 200, 202, 203, 204, 205, 206, 207, 207, 210, 211, 212, 214, 215, 216, 217, 218, 219, 222, 225, 226, 227, 228, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 244, 245, 246, 247, 248, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 263, 264, 265, 266, 267, 269, 270, 271, 272, 273, 274, 278, 279, 280, 281, 282, 283, 284, 288, 290, 291, 292, 293, 295, 296, 297, 298, 300, 302, 303, 304, 306, 307, 308, 309, 310, 311, 312, 314, 320, 321, 322, 324, 325, 326, 327, 329, 330, 331, 334, 335, 336, 337, 338, 339, 342, 343, 344, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 362, 363, 364, 365, 366, 368, 369, 371, 372, 373, 374, 376, 378, 381, 384, 385, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 403, 404, 405, 406, 407, 408, 410, 413, 415, 417, 418, 422, 427, 428, 429, 436, 437, 438, 445, 446, 448, 449, 450, 451, 452, 455, 456, 458, 459, 460, 462, 463, 464, 466, 467, 468, 469, 470, 471, 474, 475, 476, 477, 478, 479, 482, 483, 484, 485, 486, 487, 488, 491, 492, 493, 494, 496, 497, 498, 499, 500, 501, 504, 506, 507, 508, 509, 510, 513, 515, 516, 517, 518, 519, 520, 521, 523, 525
Credne 134, 138, 151, 193
Cree 213, 214, 220, 221, 334, 335, 504, 505, 506
Creek 6, 172, 243, 275, 295
Creiddylad 134, 292
Creidhne 134
Creidiylad 134
Creidne 134
Creirwy 134, 267
Crenae 333
Creon 17, 54, 57, 66, 134, 165, 167, 175, 201, 213, 252, 315, 318
Creseusa 134
Cresphontes 21
Cressida 113
Crete 9, 10, 17, 19, 40, 67, 68, 76, 131, 136, 151, 152, 163, 174, 205, 213, 219, 232, 297, 309, 317, 323, 372, 383, 403, 414, 456, 457
Creteus 219
Cretheus 19, 21, 115, 134, 166, 341, 377, 480
Creudilad 134
Creudylad 134
Creusa 11, 21, 62, 116, 134, 143, 145, 152, 156, 192, 230, 235, 239, 244, 374, 457
Criasus 67, 176
Crimisus 10, 134, 163, 405, 418
Crino 10, 56, 135, 461
Criophorus 213
Crios 135
Crissa 174
Crissan 286
Cristobal 496
Cristos 250
Crisus 51, 76, 382
Crius 75, 76, 135, 152, 174, 175, 184, 342, 356, 370, 379, 383, 387, 441
Crnobog 135
Crnoglav 135
crock 104
crocodiles 4, 5, 7, 43, 46, 129, 131, 189, 211, 223, 268, 269, 303, 352, 417, 473
Crom-Eocha 139
Crommyonian Sow 125, 135, 162, 438, 480
Cronos 119, 135
Cronus 17, 26, 61, 72, 91, 114, 117, 123, 131, 133, 135, 136, 139, 146, 166, 175, 184, 189, 201, 208, 212, 216, 231, 253, 353, 356, 364, 381, 385, 387, 394, 403, 415, 441, 462, 484, 522, 523
crook 59
crops *see* agriculture
crossroads 126, 129, 208, 302
Crow 135
Crow People 129, 134, 241, 246
crown 99, 107, 111
crows 41, 89, 133, 183, 478, 514
crozier 78
Crusher of Bones 421
crutch 163
crying 27, 32, 402
Cteatus 135, 327
Ctesippus 76, 145
Ctesylla 61
Ctiemene 284
Cu 119, 135, 151
Cu Chulain 135, 296
Cuba 366, 515
Cuchavira 135
Cuchaviva 103, 124
Cuchu'lainn 135
Cuchulain 103, 135, 148, 177, 300, 305, 328
Cuchulainn 60, 135, 136, 144, 166, 179
Cuchu'linn 135
Cuchullin 135
cuckoo 212, 213
Cuculcan 278
Cucumunic 349
Culain 135
Culann 135
culture 102, 107, 355, 504
culture heroes/heroines 6, 7, 8, 27, 32, 40, 58, 60, 64, 68, 143, 193, 208, 233, 255, 256, 261, 262, 274, 278, 294, 302, 313, 324, 330, 335, 339, 344, 353, 369, 395, 405, 478, 501
Cumae 194
Cumaean Sibyl 40, 194
Cumhal 115, 179
Cupara 136
Cupid 47, 137, 171, 501
Cupido 47
Cupra 136, 468
Curaj Mama 164
Curche 281
Curetes 17, 38, 70, 114, 115, 133, 136, 208, 311
Curettes 316
Curicaveri 114, 226, 227
curing 470, 471
Curitis 253
Curoi 103
Curoi Mac Daire 136
curse 100
Curupira 136
Cusco Huanca 449
Cush 345
Cuycha 117, 136, 304
Cuzco 136, 304, 306, 369
Cyane 21, 136, 292
Cyanippus 17, 19, 47, 136, 218
Cybebe 136
Cybele 24, 52, 69, 78, 81, 97, 133, 136, 137, 158, 194, 316, 321, 403, 451
Cybelle 136
Cyble 181
Cyclops/Cyclopes 6, 18, 62, 115, 135, 137, 138, 184, 209, 212, 380, 383, 387, 440, 463, 469, 472, 484, 522
cyclotes 10
Cycnus 62, 66, 137, 393
Cydippe 356
Cydon 9, 137, 457

www.ebook3000.com

Cyena 187
Cyene 187
Cyhiraeth 137
Cylarabes 132
Cyllene 127, 297, 370, 377
Cymodoce 137
Cymothoe 137
Cymric 68, 105, 245
Cynortas 152
Cynosura 137, 522
Cynthia 70, 137, 151
Cynthius 62, 137
Cynthius, Mount 62, 137
Cyparissus 62
Cypria 61
Cyprus 9, 10, 61, 287, 331, 393
Cyprys 16
Cyrene 62, 66, 67, 69, 137, 152, 230, 232, 283, 462
Cyrus 129
Cythera 61, 137
Cythereia 137
Cytissorus 121, 137, 383
Czarnobog 124

Da 138
Daauke 142
Dabaiba 138
Dab-Iha 138
Dabog 144
Da-Bog 144
Dactls 138
Dactyli 10, 117, 134, 138, 213, 231, 232
Dada 138, 356, 362
Dadu 13
Dadzbog 144
Daedalion 9, 138
Daedalus 68, 138, 231, 284, 323, 375, 378, 451
Daeira 152
Daemons 138
Dae-Soon 138
Daeva 138, 238
Daevas 53, 138, 147, 238, 281, 514
Dag 82, 138, 139, 351, 435
Dagamba 507
Dagan 139
Daganoweda 139
Dagda 18, 54, 58, 92, 103, 117, 139, 142, 296, 312, 321, 441, 451, 464, 477
Dagde 139
Daghda 139
Daghdae 139
Daghdae-Cearas 139
Daghdha 139
Dagini 140
Dagoba 440
Dagodevos 139
Dagon 82, 139, 200, 202, 355, 414, 434
Dagr 138, 139, 145, 351
Daguaun 139
Dagun 139, 235
Daguna 139
Dahak 139
Dahaka 464
Dahana 142
Dahhak 85
Dahomeans 172
Dahomey 24, 29, 85, 86, 89, 103, 138, 139, 176, 193, 268, 288, 292, 302, 360, 366, 396, 409, 436, 442, 446, 500
Dahomey People 7, 23, 27, 105
Dai Itoku-Myoo 45, 139, 140, 193, 513
Daibenszit-ten 345
Daibon-ten 345
Daikoku Sama 150
Daikoku 150, 162, 220, 361, 426
Daikoku Ten 150
Daimon 138, 146
Daimones 138
Dain 101, 140, 160, 516
Dainachi Nyorai 42
Dainachi Nyori 140
Dainichi Nyorai 193, 488
Dainichi-nyorai 46, 140, 182
Daityas 24, 69, 140, 146, 153, 154, 219, 275, 276, 306, 311, 336, 375, 397, 416, 491
Daiva 138, 147
Dajdbog 144
Dajoji 140
Dakas 140
Dakinis 140, 156, 257, 326, 413
Dakis 140
Dakota People 53, 55, 202, 216, 221, 450, 484, 504, 505
Daksha 15, 89, 101, 141, 143, 147, 148, 149, 153, 187, 255, 263, 264, 268, 276, 310, 315, 325, 336, 374, 388, 389, 390, 406, 415, 431, 437, 441, 485, 493, 497, 510
Dakshaja 141, 148
Dakshina 148
Dakshina-Murti 141, 427
Daktuloi 138
Dalhan 141
damanaka tree 141, 259
Damaras 188
Damaru 141, 338
Damascius 30, 63, 82, 83, 96
Damavand, Mount 53
Damballah 141, 172
Damballah-Wedo 141
Dam-c’an-r-do-rje-legs-pa 141
Dam-chen-dr-je-le-pa, Dor-le 141
Dame du Lac 500
Dames Vertes 141
Damgalnunna 347
Damia 141
Damke 142
Dam-ki 142
Damkina 63, 142, 161, 188, 271, 309, 347
Damku 142
Damnameneus 117, 138
Damona 105, 142
Damrukh Nara 146, 251
Damsel Ho 221
Damu 158
Damu-zi-abzu 451
Dan 142, 302, 409
Dan Ayido Hwedo 142
Dan Bay 355
Dan Petro 142, 465
Dana 30, 58, 142, 155, 184, 312
Danae 6, 12, 129, 142, 380, 386
Danai 142, 143
Danaidae 142
Danaide 134
Danaid(e)s 25, 49, 75, 117, 130, 142, 143, 170, 174, 175
Danaus 6, 11, 20, 25, 49, 75, 117, 130, 142, 143, 174, 175, 230, 380, 382, 386
Danavas 77, 140, 141, 143, 146, 282, 375, 389, 502
Danavis 143
Dancer of the Burning Ground 338, 427, 441
dancing 63, 91, 98, 133, 138, 180, 338, 377, 413, 427, 489, 509
Dandadhara 512
Dandaka 401
Dane 176
Dane Hills of Leicestershire 58
Danel 274
Danes 74, 183, 207
Dangis People 101
Danh 142
Daniel 143, 184
Danil 143
Daniyal 143
Dante Hills 102
Danu 15, 28, 58, 68, 139, 142, 143, 155, 264, 311, 325, 492, 502
Danube 64
Danus 80
Dao 451
Daonus 451
Daphne 62, 143, 218, 359, 378, 405, 485
Daphnis 64, 359, 374
Dar al 16
Dar el-Jannah 143, 243
Darago 143
Daramulum 158
Daramulun 89, 143, 304, 353
Darawigal 89, 143
Darbas 143, 372
Dardania 10, 20, 21, 51, 105, 171, 218, 474, 479
Dardanos 165
Dardanus 93, 165, 171, 231, 232, 235, 381, 430
Dardunus 136
Darius I 29
Dark Elves 154, 505
Dark Heavy Clouds 59
Dark Mother 262
Dark One 61
Dark Season 389, 390
Dark Twin 236
Dark Water Snake 280
Dark Waters 93
darkness 6, 20, 22, 29, 56, 59, 61, 107, 110, 170, 180, 208, 217, 221, 223, 244, 249, 265, 284, 287, 294, 320, 401, 409, 421, 452, 460
Darramulum 143
darts 100
Daru el-Bawar 228, 243, 248, 288, 432
Daru el-Qarar 143, 243
Daru el-Salam 143, 243
Darvands 143
Darwands 143, 144
Darzamat 144, 254
Dasan 144, 303
Dasara 187
Dasarata 144
Dasaratha 99, 144, 203, 256, 398
Dasartha 285
Dascylus 49
Dasharatha 144
Dashtayani 266
Dasim Sut 84
Dasim 85, 144, 446, 468, 520
Dasra 77, 338, 447; and Nasatya 144
Dasun 272
Dasyus 144
Datan 144, 288
date-nut 289
dates 236, 327
Dattoli 24
Dauce 83, 97
Daughter of Night 307, 341
Daughters of the Evening 216
Dauke 142
Daunus 254
Dauthe 142
Davalin 159
Davkina 142
Dawat Puja 144, 414
Dawkina 142
dawn 56, 57, 66, 71, 76, 77, 78, 79, 80, 83, 85, 98, 104, 107, 123, 130, 169, 190, 217, 302, 310, 312, 422, 422, 431, 470, 486, 524
Day 139, 211, 345
Day-Maker 152, 444
daytime 28, 107, 138, 139, 294, 454, 455, 472, 524
Dazbog 144, 211, 212, 270
Dazhbod 144
Dazh-Bog 144
Dazhbog 83, 144, 331, 446
Dazibogu 144
Dazima 144, 346
Dbyar-Gyi-Rgyalmo 196
dDe-mch-og-dpal-kor-lo-dom-pa 156
De Ai 144, 337
De Babou 144, 332, 337
De Danaan 103
De Hi No 211
Dea Syria 78
dead 7, 34, 43, 50, 54, 55, 58, 70, 88, 93, 95, 98, 99, 100, 106, 108, 110, 125, 127, 128, 131, 135, 171, 178, 187, 190, 197, 201, 225, 266, 268, 270, 283, 307, 324, 342, 395, 406, 443, 515, 518; records of 346
Deae Matres 144
Dealer of Death 62
Dealgnaid 96
Dearg 18
death 3, 14, 28, 35, 36, 53, 56, 62, 71, 76, 78, 79, 80, 82, 85, 86, 89, 92, 95, 99, 100, 105, 114, 118, 123, 126, 139, 158, 194, 201, 207, 212, 217, 239, 246, 256, 257, 258, 266, 291, 308, 309, 311, 320, 321, 328, 329, 333, 343, 349, 358, 362, 392, 406, 417, 427, 441, 449, 453, 461, 471, 504, 511, 512, 519
death-egg 274
Debabou 144
Debee 148
Deber 144
Deccan 495
Deceiver 400, 449
Deceleia 9
deception 53
Dech’tire 135, 144
Dechterecul 144
Dechtire 144
Deduska 155
Decima 178
Deduska Domovoy 155
Dedusky Domovik 155
Dee 145
Deep Land 436, 518
Deep Virtue 307
Deepavati 153
deer 37
defender goddess 290
Deformation 34
Deganiwada 139, 154
degeneration 258
Deianeira 38, 145, 214, 229, 343, 359, 473
Deianira 11, 38, 114, 145, 153, 213
Deidameia 11, 76, 96, 145, 176, 241, 370, 405, 414
Deidre 179
Deileon 145
Deimachus 21, 145
Deimos 56, 61, 66, 145, 168, 171, 205, 370
Deimus 145
Deino 195
Deion 13, 21, 115, 118, 145, 152, 166, 383
Deion the Phocian 67
Deione 9, 145
Deipatyros 522
Deiphobe 40
Deiphobus 116, 145, 374
Deiplus 463
Deipyle 17, 19, 47, 136, 145, 152, 218, 480
Deipylus 145, 249, 386, 387
Deivi 145
Dejanira 11, 145

Dekla 145
Delia 61, 70, 145
Deliades 96, 145, 192
Delight goddess 308
Delius 62
Delivering 148, 455
Delka 145, 254
Delling 74, 139, 145
Dellinger 145, 351
Delos 62, 137, 289, 290
Delphi 213, 358, 382
Delphic Muses 229, 319, 330, 343
Delphic Oracle 20, 143, 286, 462
Delphin 47
Delphos 62
Delphus 62
Delphyne 145, 480
Delta 206
deluge *see* flood
Dema 145
Demarus 317
Demavand, Mount 85, 86, 267, 464, 495
Demavend, Mount 465
Dem-chho-pal-khor-lo-dom-pa 156
Demeter 6, 11, 24, 72, 94, 115, 119, 135, 137, 146, 147, 152, 156, 172, 201, 208, 212, 216, 230, 231, 240, 243, 318, 377, 378, 379, 381, 383, 385, 387, 403, 404, 441, 453, 522, 523
Demiurge 146
Demne 179
Demo 40
Demodice 134
Demodoce 112, 165, 381, 457
Demogorgon 146
Demoleon 10, 56, 146, 192, 461
Demon Destroyer 28
Demonassa 174, 241
Demonice 146, 176, 327, 359, 393
Demonice 35, 66
demons 4, 7, 9, 14, 15, 22, 26, 28, 31, 32, 34, 38, 39, 40, 45, 46, 52, 53, 54, 60, 61, 65, 71, 73, 74, 76, 77, 83, 84, 85, 87, 90, 91, 95, 99, 100, 101, 102, 103, 110, 114, 115, 120, 133, 136, 138, 140, 141, 144, 146, 154, 156, 157, 159, 160, 166, 167, 184, 185, 186, 196, 203, 211, 216, 219, 223, 225, 229, 248, 249, 251, 256, 259, 266, 267, 268, 269, 270, 271, 272, 274, 282, 284, 291, 299, 330, 349, 370, 371, 372, 423, 427
Demophile 40
Demophon 6, 117, 146, 156
Demophoon 9, 10, 23, 146, 165, 380, 383
Denderah 367
Dendrites 146, 152
Dendur 376
Deng 85, 146
Deng-dit 146
Denmark 464
Dense Clouds 59
Deo 146, 147
Deohako 147
Deophontes 95
Deopul 148
Der 255
Derceto 78
Derketo 78, 82
Dervaspa 147, 515
Descendent of Yadu 275
desert 67, 85, 93, 279, 322
Desire 22, 242, 328
Despoena 61
Despoina 379, 403
destiny 177, 211, 268, 327, 328, 351, 441, 449, 485
Destroyer of Death 513
destruction/destroyers 15, 20, 22, 26, 78, 84, 99, 105, 204, 256, 257, 258, 302, 303, 412, 427, 513
Deucalion 9, 21, 52, 68, 147, 192, 211, 232, 297, 323, 375, 391, 465
Deus Clavigerus 249
Dev 147, 202
Deva 148, 409
Devak 147
Devaka 147
Deva-Kanya 416
Deva-Kanyakas 148
Devaki 15, 63, 90, 147, 261, 275, 441, 514
Devalokas 258
Deva-Matri 15, 147
Devananda 301, 410, 474
Deva-Parvata 147, 319
Devapura 41
Devarishis 404
Devas 138, 143, 147
Devasena 263
Devee 148
Devera 148
Devi 42, 50, 65, 99, 121, 147, 148, 158, 159, 188, 204, 256, 257, 262, 279, 283, 285, 309, 374, 375, 406, 413, 415, 422, 427, 434, 474, 483, 498
Devi Sri 254, 285
Devi-Kali 257
devils 14, 31, 38, 88, 98, 133, 148, 166, 172, 216, 231, 288, 289, 363, 414
Devis, The 148
Devi-Uma 99, 148
Devi-Uma-Kali 148
Devon 420
Devona 420
Devorgilla 148
devotion 25, 45, 65, 100, 107, 232, 439
Devourer of Amenti 46
Devs 138, 149, 202, 255
dew 214, 310, 456
Dew Eagle 218
Deywuckee 147
Dhammai 9, 55, 250, 252, 271, 295, 381, 412, 429, 441, 442
Dhammapada, The 149
Dhanada 149, 282
Dhana-Pati 282
Dhanus 149, 281
Dhanvantari 149, 281
Dhara 493
Dharanendra 333
Dharani 285, 373, 434
Dharini 149
Dharma 141, 149, 159, 258, 276, 280, 315, 337, 427, 439, 474, 496, 503, 519
Dharma Palas 290
Dharma Protector 397
Dharmacakra 149, 307
dharmacakra-mudra 389
Dharmadhvaja 46
Dharmapala Kalamahakala 301
Dharmapala Sitamahakala 301
Dharmapala 149, 156, 489
Dharmaraha 325, 512
Dharmaraja 48, 149, 512
Dharmavajra 411
Dhartarastra 149
Dharti Mai 149
Dharti Mata 149
Dhata 388, 444
Dhatr 149, 388
Dhatri 15, 149
Dhenuka 149, 275
Dhisana 149
Dhritarashtra 100, 146, 150, 159, 185, 264, 280, 503
Dhriti 147
Dhrtarastra 117, 467
Dhruvasinha 48
Dhumakety 25
Dhumbarahi 491
Dhupa 400
Dhupema 400
Dhurva 493
dhyana 104, 410
dhyana mudra 150
Dhyani Buddhas 33, 45, 46, 47, 48, 150, 195, 303, 307, 400, 410, 454, 488, 490, 492
Dhyanibodhisattvas 32, 84, 150, 301, 303, 307, 410, 448, 473, 489, 500
Dhyanibuddhas 150, 215
Dhyanibuddhasaktis 150, 304
Dia 22, 68, 150, 245, 376
Dia Griene 150
Diabolos 148
Diabul 148
diadem 109, 148, 238
Diakoku 150
dialect 22
Diamond Kings 151, 326
Diamond Kings of Heaven 439
Dian Cecht 151
Diana 17, 70, 78, 137, 145, 151, 152, 163, 189, 208, 304, 382, 419, 487
Diana of Crete 243
Diancecht 151
Dianchecht 151
Dia'necht 30, 119, 129, 134, 135, 151, 173, 296, 320, 352
Dianus 249
Diarmait 151, 179, 196
Diarmuid 17
Diaus 160
Diban 144
dice *see* gambling
Dice 151
Dicte, Mount 205
Dictyanna 70, 151
Dictynna 70, 151
Dictys 12, 13, 151, 380, 386, 388
Di-do 196
Dido 21, 25, 97, 151, 165
Didon 151
Didone 151
difficulties 186, 497
Digambara 427
Digambari 148
Digdevatas 148
Dig-Gaja 152
Digraldi 209
Dih 196
Dihwar 196
Dii Di 151
Diing 9, 85, 146
Dik 152
Dike 76, 151, 152, 222
Dikpalas 152
Diksha 437
Diktynna 70
Dilbar 152, 242
Dilga 89
Diligina 59
Dilipa 186
Dilmum 167
Dilmun 59, 152, 162, 168, 332
Dina-Kara 152, 444
Dinas 500
Dindyme 136
Dindymene 136
Dindymus 136
Dinga-dit 146
Dingo 304
Dingos 89
Dinija 152
Dinka People 9, 85, 146, 283, 353
Diomede 11, 13, 118, 145, 152, 229, 383, 510
Diomedes 6, 10, 19, 27, 57, 66, 113, 130, 132, 137, 145, 152, 166, 192, 213, 249, 370, 461, 480
Dionae 152
Dionaea 61
Dione 38, 61, 80, 139, 152, 175, 253, 349, 377, 453, 460, 495, 523
Dionusos 152
Dionysos 152, 438
Dionysus 17, 24, 38, 57, 61, 65, 67, 68, 82, 83, 88, 93, 117, 133, 145, 146, 152, 153, 159, 190, 195, 229, 230, 231, 239, 240, 289, 290, 297, 300, 319, 331, 333, 359, 366, 367, 374, 378, 380, 381, 390, 408, 415, 419, 420, 427, 431, 437, 439, 463, 465, 484, 490, 520
Dionysys 118
Dioscures 116, 153
Dioscuri 9, 10, 23, 67, 116, 153, 381, 382, 386
Dioskouroi 77
Dipamkara 153
Dipankar 153
Dipankara 153, 308
diplomats 238
Dirae 183
Dirce 57, 153, 297
direction(s) 207, 226, 347
Dirima 36
Dirona 105
dirt 179
Dis 153, 201
Dis Pater 22, 153, 178, 385, 441
disaster 90
discipline 493
Discord 153, 171, 172
Discordia 66, 79, 153, 165, 171, 212
disease 14, 28, 38, 51, 53, 55, 58, 74, 111, 184, 195, 201, 210, 221, 255, 271, 273, 295, 309, 311, 345, 384, 416, 473, 491
Disir 153, 491
disorder 331
Dispater 153
distaff 327
distillers 476
Ditaolane 269
ditches 429
Dithrambos 153
Dithyrambos 152, 153
Diti 15, 52, 140, 153, 311, 406, 487
Diubhal 148
Diuturna 254
Div 146, 251
Divali 154, 302
Divalia 53
Diver Bird 79
Diveriks 154
divination 282, 293, 336, 423
Divine Array 263
Divine Lady 148, 444
Divine Land 343
Divine Mare 431
Divine Mother of Infinite Space 334, 488
Divine Mothers 263
Divine Vivifier 444
divining 366
Divji Moz 154
Divo Napata 77
Divs 138, 148, 251
Divya-ratna 129
Diwali 154, 285
Diwata Magbabaya 154
Djadek 155
Djaga 407
Djamar 154, 350
Djanggau 154
Djanggawuls 154
Djed 154, 460
Djehut 154
Djehuti 464
Djehuti Orzehuti 154

www.ebook3000.com

Open the Three Tan Tiens

Move your hands down to the mideyebrow. Touch the mideyebrow.
We are going to open the three Tan Tiens, starting with the Upper Tan Tien.

Upper Tan Tien - Mideyebrow

1. Recharge. Remember: Tan Tien – heart consciousness in, awareness out. Spiral – Tan Tien, heart, third eye and crown. Universe – six directions spiraling.



Fig. 3.45 *Raise hands and charge with Universal Chi.*

Djehuty 457
Djeneta 154
Djigona 154
Djigonasee 139
Djigonsa 154
djinn 251, 523
Djunggun 507
Djunggun the Owl 507
Djunkgao 154
Dmyal-wa 336
Dockalfar 36, 154
Doda 154
Dodol 154
Dodola 154
Dodona 523
Dog Star 228, 301
Dogdha 139
Dogoda 154, 440, 492
Dogon 46, 288, 350
dogs 4, 16, 17, 66, 69, 72, 99, 125, 170, 172, 177, 179, 206, 209, 258, 265, 268, 287, 313, 338, 347, 385, 507, 509, 514
Doh 154
Dohit 154
Dohitt 154
Dol Jyang 454
Dola 155
Dolgthvari 160
dolls 255
Dolma 47, 155, 454
Dolopes 11
Dolopians 67, 382
dolphins 48, 79, 206
Dolya 155
Domania 155
Domfe 155
Domiduca 253
Domnu 155
Domovik 159, 270
Domovikha 155
Domovoi 92, 127, 159, 270, 271, 276, 287, 368
Domovoj 155, 159
Domovoy 155, 159
Domovui 155, 159
Don 58, 68, 102, 142, 199, 388
Don the Enchanter 391
Donar 463, 464
donkey 80, 122
Donn 12
Donu 142
Don-yod-grub-pa 47
Don-yo-dup-pa 47
Doorga 148
doors 55, 128, 152, 153, 275, 298, 350, 475, 482, 506, 507, 512, 519
Dori 160
Dorians 19, 21, 371, 456
Dorippe 211
Doris 47, 119, 131, 137, 155, 160, 185, 342, 356, 372, 379, 381, 391, 438, 462
dorje 156
Dorje Phagmo 156
Dorje Phogmo 489
Dorje-Naljorma 155, 489
Dorje-phe-mo 156
Dorje-sem-pa 490
Dorobo 343
Dorodoche 379
Dorr-Karing 156, 482
Dorus 11, 19, 21, 62, 152, 156, 211, 507, 509, 510
Doso 146, 156
Dotis 66, 382
Doto 156, 342
Double Crown 205
Dousares 159
doves 61, 133, 175, 385
downlooking deity 84
Drac 156
Draco 284
dragons 20, 28, 31, 51, 53, 55, 67, 73, 78, 88, 93, 97, 112, 115, 125, 128, 130, 140, 143, 145, 156, 162, 177, 178, 185, 229, 266, 270, 272, 274, 280, 284, 290, 296, 314, 344, 407, 420, 466, 467, 470, 487, 488, 502, 518
drama 152
Drauga 148
Drauga 53
Draughts 60
Draupadi 69, 100, 159, 263, 264, 280, 371, 372
Draupner 156
Draupnir 52, 156, 160, 164, 214, 358, 430
Dravidians 99, 144, 148, 443
drawing 244, 464
Drayads 157
dread 25, 26, 145, 333, 481
dreams 110, 122, 143, 156, 174, 230, 266, 327, 328, 505
Dreng 209
Drepanum 10
dressmakers 307
Dri-chab-ma 185
Dri-chha-ma 47, 185
drink 108, 378, 456
Dromi 156, 178, 192, 284
Drona 99, 100, 156, 159, 275
Dropper 156
Drott Leggjaldi 209
Droudje 157
drought 20, 114, 188, 259, 369
drowning 266
Druantia 157
Drugas 53
Druge 157
drugs 98
Druids 6, 7, 14, 22, 45, 96, 129
Druj 53, 148
Druji 267
Drujs 53, 157, 338
Drukh 157
drums 7, 99, 141, 329
Drumalika 157, 261, 481
Drumb 209
Drumba 209
drunkenness 118, 135, 299, 300, 460; *see also* alcohol; intoxication
Drvaspa 147
Dryades 157, 202
Dryads 170, 174, 202, 354
Dryas 12, 66, 157, 175
Dryh Basy 157
dryness *see* aridity
Dryope 62, 157, 175, 371
Dryopes 229
Dryopian 67
Dryops 157, 386
Dsam-Bha-La 248
Dsovean 157, 488
Dsovinar 157
duality 363
Duamutef 476
Duat 477
Dubbisag 332
Dubh Lacha 157
duck 134
Dufr 160
Dughda 157, 524
Dughdhova 157
Dug-Po-Ma 400
Duhsasana 100
Duibhal 148
Duid 478
Dula 158, 404
Dulachan 158
Dumah 189
Dumazu 158
Dumuduku 309
Dumu-e-zi 158
Dumunzi 158
Dumu-zi 158
Dumuzi 54, 81, 137, 158, 167, 190, 236, 348, 423, 451, 487
Dumuziabzu 158
Dumuziapsu 158
Dumuzida 158
Duneyr 140, 160, 516
dung 285
Dunga 158, 161
Dup Shimate 158
Dup Shimati 158, 448
Duramulun 158
Durathor 516
Durathror 140, 160
Dur-Europas 87
Durga 89, 128, 148, 159, 188, 257, 301, 306, 319, 374, 375, 406, 422, 427, 434, 496, 497, 517
Durga Mahisasuramardini 158
Durga Puja 257
Durga Purga 159
Durga-Kali 121
Durga-puga 497
Durga-puja 158
Durin 159, 160
Durinn 159
Duroydhana 185
Duruge 157
Durugh 148
Durva-grass 186
Durvasas 262, 263, 280
Duryodhana 90, 99, 100, 150, 159, 263, 264, 276
Dus 159
Dusares 159
Dushyanta 99, 202, 422
Dusii 159, 237
Dussasana 185
Dusura 159
Duwel 148
Duzakh 201, 211
Dvalin 36, 98, 140, 159, 160, 181, 516
Dvalinn 159
Dvapara 412
Dvarapala 159
Dvarka 90, 159, 275, 276, 373, 388, 433, 447, 510
Dvergar 159
Dvivida 77, 159
Dvorovoi 155, 159
Dwaparayuga 159, 258
dwarfs 14, 36, 47, 52, 55, 74, 83, 91, 97, 98, 101, 108, 117, 139, 140, 145, 155, 156, 159, 164, 166, 181, 183, 184, 185, 186, 191, 192, 198, 199, 201, 204, 212, 224, 232, 245, 252, 262, 264, 273, 282, 285, 326, 335, 351, 360, 372, 393, 446, 469, 498
Dwarka 499
Dwarpara 159
Dweller in His Flame 45, 235
Dwumwem 160
Dwyn 160
Dxui 160, 463, 476
Dyad 492
Dyai 160
Dyanysos 152
Dyaus 25, 77, 147, 160, 237, 390, 401, 479, 486, 523
Dyaus Pitar 522
Dyaus-Pita 160, 390
Dyaus-Pitar 160
Dyaus-piter 494
Dyaus-Pitri 390
Dyava-Matar 160, 390
Dyavan 160
Dyava-Prithivi 160
Dyavaprithivi 390
Dyavaprthivi 390
Dyavo 160
dyers 341
Dyeus 160
Dyhu 160
Dylan 68, 160, 199
Dymas 19, 160, 371
Dyna 145, 176
Dynamene 160, 342
dynasty of Chou 224
Dyne 176, 405
Dyotana 160, 486
Dyu 160
Dzakar 521
Dzalarhons 160
Dzaui 469
Dzelarhons 501
Dzhe Manito 160, 192
Dzokh 201, 211

E 161
Ea 13, 14, 27, 55, 58, 60, 63, 77, 84, 92, 94, 139, 142, 158, 161, 162, 167, 170, 176, 188, 191, 199, 211, 242, 269, 272, 279, 284, 296, 304, 309, 330, 336, 346, 347, 352, 355, 410, 451, 459, 483, 486, 492, 520
Eabani 167
Eadna 164
Eadon 161
Eagle Hawk 191, 511
eagles 15, 25, 47, 64, 73, 79, 84, 162, 187, 188, 191, 197, 211, 221, 224, 250, 266, 292, 296, 349, 353, 358, 411, 436, 448, 497, 525
Ealur 161
Eanna 161
Earl Fitzgerald 30
Earl of Wind 178
Early Waker 4, 38
earrings 15
ears 186
earth deities 22, 26, 32, 36, 38, 44, 46, 51, 66, 70, 71, 73, 81, 82, 97, 98, 99, 100, 106, 107, 108, 109, 110, 111, 119, 128, 129, 131, 136, 139, 142, 149, 152, 160, 161, 167, 168, 184, 189, 198, 209, 217, 224, 232, 234, 236, 240, 242, 244, 245, 252, 276, 284, 285, 292, 310, 312, 313, 333, 341, 346, 348, 350, 362, 369, 372, 390, 423, 424, 431, 436, 437, 441, 442, 449, 450, 457, 458, 459, 460, 469, 470, 471, 481, 486, 493, 498, 501, 520, 521, 522
earthquakes 19, 29, 36, 71, 93, 103, 115, 124, 226, 310, 339, 477, 513
East 121, 423, 478
East Indies 412
East Wind 53, 174, 198
Easter Islands 303
Eastern Emperor 346, 478
Eastern Sea 278
Eastre 161, 169
Easy-Rice-Field-of-Heaven 41
Eater of the Dead 46
Eater of the Land 377
Eaters of Souls 58
eating and drinking 14
Eaynnes 171, 173
Ebhlenn 162
Ebhlinne 162
Ebisu 162, 220, 426
Ebisu Shore 220
Eblis 85, 148, 231, 414, 446
Ec 162, 270, 352
Ecalchot 127, 129, 162, 324, 395, 451, 500
Ecatonatiuh 288
Ecbasus 25, 67, 162, 176, 231
Ecclesia 21, 351
Ecclesiasticus 21, 351
Echauc 27
Echecles 13, 162, 173
Echedemus 9
Echemus 22, 118, 440
Echephron 57, 162, 440
Echida 20, 162, 205
Echidna 67, 113, 117, 119,

125, 127, 135, 162, 184, 190, 194, 229, 284, 376, 380, 383, 417, 440, 455, 480, 502
Echidne 383
Echiodna 162, 315
Echion 24, 67, 162, 172, 175, 378
Echis 162
Echnidna 195, 438
Echo 70, 162, 184, 265, 337, 478
Echua 10, 164
Echuac 232
eclipses
eclipses 36, 195, 435
Ecmar 103
ecstasy 152, 436
Ecuador 483
Edda 29, 209, 464
Eddas 180, 221, 483
Eden 152, 162
Edfu 95, 206, 215
Edie 13
Edimmu 162, 487
Edo 172, 355
Edom 13
Edoni 369
Edonians 157, 297
Edonus 369
Edusa 162
eels 6, 178, 258, 460, 478
Eeriboea 162
Eeyeekalduk 162, 163
Ef 269
Efe 163
Efnissien 176
Efrit 163
Egeria 114, 163
Egesta 10, 134, 163
eggs 15, 43, 78, 105, 116, 122, 141, 169, 203, 241, 280, 297, 306, 310, 339, 351, 364, 371, 373, 467, 517; *see also* Cosmic Egg; golden egg
Egil 83, 462, 501
Egilorvandel 83
Egime 346
Egis 20
Egypt 3, 4, 5, 8, 9, 14, 16, 17, 20, 22, 23, 25, 27, 28, 32, 33, 34, 36, 39, 40, 42, 43, 44, 45, 46, 48, 49, 50, 51, 53, 54, 55, 56, 58, 59, 60, 61, 62, 63, 64, 68, 70, 71, 72, 73, 74, 75, 78, 79, 81, 82, 83, 86, 87, 88, 92, 93, 95, 96, 97, 98, 101, 102, 118, 123, 127, 130, 135, 142, 143, 146, 152, 154, 160, 165, 168, 169, 176, 177, 184, 189, 201, 203, 204, 205, 206, 208, 209, 211, 212, 214, 215, 216, 222, 225, 226, 228, 233, 235, 238, 242, 253, 254, 256, 259, 265, 266, 267, 268, 269, 270, 289, 293, 298, 300, 313, 315, 317, 318, 319, 320, 322, 326, 328, 331, 333, 338, 339, 340, 341, 342, 345, 348, 352, 353, 356, 359, 364, 367, 368, 369, 370, 373, 376, 379, 380, 382, 391, 394, 396, 400, 401, 402, 408, 409, 413, 415, 416, 417, 418, 419, 420, 421, 422, 424, 425, 433, 437, 438, 441, 442, 448, 449, 453, 455, 456, 457, 458, 459, 460, 462, 464, 465, 476, 477, 478, 480, 481, 482, 483, 484, 485, 486, 495, 503, 505
Ehat 27
Ehcatonatiuh 288
Ehecatl 163, 395
Ehecatl-Quetzalcoatl 163
Ehecatonatiuh 288
Ehet 27
Eidothea 462
Eidyia 18, 64, 233, 314, 356
Eight Immortals 68, 122, 163, 202, 221, 295, 466, 475
Eight Mothers of Buddhism 400
Eight Perils 454
Eight Rulers 464
Eight Spirits 123
Eight Wrathful Ones 267
Eikinskjaudi 160
Eikintjasna 209
Eil 164
Eilatus 21
Eileithya 341
Eileithyia 61, 66, 163, 523
Eilton 160
Eilythia 163
Einheriar 164, 192
Einherjar 164, 198, 358
Einridi 463
Eioneus 164, 245
Eir 22, 164
Eira 164
Eire 22, 164
Eirean 164
Eirene 151, 164, 222, 240, 375
Eirin 164
Eirinn 164
Eistla 209
Eithinoha 164, 363
Eitri 156, 164, 198, 326
Eitumatupua 28, 164, 234
Eka 148
Eka Obasi 243
Ekadanta 186
Ekadzati 164
Ekajata 156, 454
Ekako 164
Ekalgina 59
Ekata 208
Ekchuah 164, 176, 232
Ekeko 164
Ekhi 32
Ekkekko 164
Ekki 33
Ekoi 243
Ekron 87
E-Kur 168
El 27, 36, 37, 51, 73, 80, 86, 87, 164, 165, 166, 173, 274, 328, 422, 503, 511
El Gran Dios 520
Eladu 139
Elagabalus 86
Elah 164
Elam 270, 272, 284
Elamite goddess 493
Elamites 270, 333
Eland 283
Elara 165, 364, 469
Elare 165
Elat 164, 165
Elatha 139
Elatus 112, 241, 378, 387
Elbegast 52
Elbes 166
Elburz, Mount 524
Elcmar 54, 103
Elcmhaire 54, 103
Elder Brother 451
Elder Gods 462
Elder Horus 367
elder tree 166
Eldhrimir 358
Eldhrimnir 164, 408
Eldir 20
Eldrimne 52
Electra 20, 23, 112, 128, 165, 173, 205, 231, 240, 287, 356, 379, 381, 385, 393, 440, 523
Electryon 35, 52, 165, 194, 440
Eleggua 165, 362
Eleio 165
Eleithyia 165, 212
Eleius 165
Elektra 165
elephantiasis 255
Elephantine 8
Elephantine Triad 55, 59, 165
Elephantis 8
elephants 30, 33, 55, 109, 158, 186, 187, 194, 248
Elephenor 9, 165
Eleusinian Mysteries 117, 146, 152, 174
Eleusis 6, 117, 119, 146, 152, 174, 212, 286, 356
Eleutherios 152
Eleuthia 163
Elias Lönnrot 256
Elijah 165
Elimmu 146
Elioun 164
Elis 21, 38, 67, 114, 165, 213, 218, 378, 385, 410
Elish'a 165
Elisha 165
Elissa 151, 165
Elivagar 165, 229, 345, 444
Elixir of Life 48
Eljudnir 166
el-Khudr 165
Ellasar 423
Ellat 37
El-Lat 37
Ellen Douglas 500
Elli 166
Elligarra 520
Ellil 168, 191, 233
elm trees 125, 166
Eloah 164
Eloaios 166
Elohim 164, 166, 250, 510
Elom 166
eloquence 105, 186
Elpis 21, 351
elves 77, 109, 130, 158, 160, 166, 392, 446, 464
Elyon 164, 166
Elysian Fields 60, 166, 201, 205, 289, 314, 318
Elysian Islands 383
Elysium 166
Emader-Akka 33
Emathion 166, 169
Embla 74, 166, 321, 358, 496, 497
embalming 58
Emen 265
Emer 60, 135, 166
Emerald Lady 120
emergence myths 132
Emesa 165
Emisiwaddo 281
Emla 166
Emma 166
Emma-Hoo 166
Emma-O 140, 166, 241, 250, 255, 446
Emma-Sama 166
Emola 166
Emperor of the Eastern Peak 425, 442
Empousae 166
Empress of Heaven 467
Empusa 166
emu 38, 273, 303
Emut 16
Enaret 39, 115, 299
Enarete 79, 134, 145, 166, 174, 300, 379, 410, 433, 452, 509
Enarte 69
Enbarr 296
Enbilulu 167, 309
Enceladus 49, 80, 167, 190, 431, 469
Enchantress 129
Endeis 17, 123, 377, 382
Endil 160
Endless 421
Endless Time 257
Endymion 62, 143, 151, 419
Enemy, The 460, 502, 514
Enemy of the sun 61
En-ge 14
Engidu 167
England *see* Britain
Englimi 220
Engur 161, 167
Engus 54
Enigorio and Enigohatgea 167
Eniocha 54
Enioche 54, 167, 175, 315
Enkhthonin 385
Enki 41, 49, 73, 142, 152, 161, 167, 168, 236, 284, 296, 309, 334, 346, 347, 348, 352, 486, 524
Enkidu 71, 158, 167, 191, 236, 487
Enki-Ea 161
Enkimdu 167
Enkita 167
Enlightener 153
Enlightener of the Darkness 156
enlightenment 103, 109, 195, 275
Enlil 13, 49, 55, 58, 59, 71, 94, 95, 139, 161, 168, 198, 241, 271, 284, 309, 334, 344, 347, 353, 423, 451, 486, 487
En-lil 168
En-Mersi 346
Enmesarra 168, 342
Enmesharra 168
Ennammasht 348
Ennead 81, 168, 189, 269, 353, 428, 456
Ennead of Heliopolis 396
Ennmeshara 168
Ennoia 168, 437
Ennugi 168
Ennuki 59
Ennyo 168
Enoch 113
Enodia 168, 208
Enshag 152
Enshagme 168, 346
Entuti 4
Enua-kura 452
Enualios 65
Enulios 168
Enuma Elish 49, 168
Enveloper 502
Enyalius 65, 168
Enyo 96, 145, 168, 171, 195, 205, 370
Eo 136
Eochaid mac Eire 449
Eochaid Ollathair 139
Eochail Lethderg 18
Eogabal 30
Eoghana 164
Eon 21
Eopuco 28
Eos 66, 76, 80, 83, 85, 104, 118, 130, 166, 169, 175, 210, 230, 310, 317, 351, 365, 370, 376, 380, 413, 416, 419, 461, 469, 486, 522, 523
Eosphorus 169
Eostre 161, 169
Eous 210
Epadun 309
Epaphos 62
Epaphus 25, 61, 136, 169, 239, 291, 317, 345, 523
Epeius 20, 169, 230
Ephedra 203
Ephialtes 37, 66, 169, 190, 330, 368
Ephyra 96, 192
Ephyraea 169
Epi 160
epic poetry 113
Epicasta 146, 218, 327, 393
Epicaste 252, 387
Epidaetia 61
Epidaurus 67, 169, 176, 377, 390
epidemics 74, 225, 429
Epigoni 17, 19, 64, 67, 115, 152, 169, 174, 422, 451
Epihialtes 469
epilepsy 15

www.ebook3000.com

Epimedes 138
Epimetheus 80, 131, 169, 231, 356, 372, 391, 393, 465
Epimethius 318
Epione 72, 231, 299, 371
Epiphania 94
Epiphanius 24
Epiphany 94
Epirus 131, 455
Epistrophus 176
Epitragia 61
Epitymbria 61
Epius 169
Epochus 231
Epona 146, 169, 299, 403
Epo'na 169
Epopeus 37, 57, 115, 133, 153, 169, 170, 354
Epunamun 170, 392
Eq'eq'o 164
Er 64
Erathipa 170
Erato 143, 170, 330
Erbil 242
Erebus 22, 31, 118, 122, 156, 170, 171, 177, 201, 211, 216, 230, 327, 328, 341, 351, 455, 461
Erech 170, 191, 236
Erechtheus 105, 130, 134, 170, 319, 364, 522
Eredatfedhri 170, 248
Ereint 292
Erelim 53
Eres 66
Erescheigal 170
Ereshkigal 37, 64, 77, 95, 170, 236, 241, 242, 272, 334, 342, 346, 451
Ergea 117
Erginus 67, 131, 170, 403
Erh-Lang 170
Eriboea 31, 170, 171, 319
Eribotes 115
Ericepauis 381
Erichthonius 26, 76, 105, 130, 170, 171, 184, 212, 474
Erichtonius 93, 170, 171, 389
Eridanus 171, 380, 405
Eridu 14, 59, 152, 161, 167, 171, 176, 236, 336
Erigone 20, 171, 231
Erinn 142
Erinnyes 35, 79, 171, 173, 178, 184, 266, 316, 319, 341, 359, 372, 468, 484
Erinnys 171
Erinyes 171, 173, 183
Eriopis 31, 62, 171, 249, 360, 381
Eriphyle 17, 451
Eris 14, 66, 79, 80, 153, 171, 289, 374, 377, 462, 523
Erishkegal 170
Eriskigal 49, 170
Erisvorsh 171, 440, 492
Eriu 45, 139, 164
Erkir 379
Er-Lang 170
Erlik-Khan 171
Erlin 171
Ermenrich 447
Ermen-ta 4, 5, 54
Ermenu 177, 417
Ermenui 458
Ermine 241
Erna 209
Ernutet 402
Eros 17, 31, 47, 56, 61, 66, 122, 145, 168, 171, 172, 184, 195, 205, 259, 351, 370, 381, 391, 455, 490
Erp 252
Erqigdlit 16
Errato 170
Ersa 419
Ertat-Sebanqa 477
Erui 92
Erulus 172, 176
Eruncha 172
Eryale 375
Erycina 61
Erymanthian boar 213
Erymede 240
Erysichthon 26, 172, 220, 240, 372, 382, 474
Erytheis 172, 216
Erythia 66, 190
Erythrius 79, 172, 462
Erythrus 172
Erythus 403
Erytus 174
Eryx 10, 61
Erzulie 172, 360
Esagil 172
Esagila 172
Esagilla 59
Esar 22
Esaugeteh Emissee 172
Esbani 71
escape 383, 522
Eschetewuarha 172
Eschu 288
Esculapius 72
Esege Malan 172
Eset 242
Esharra 172, 309
Eshmoun 172
Eshmun 17, 72, 75, 76, 123, 172, 346, 367, 448, 451
Eshu 172, 176, 233, 288, 365
Eskimo People 16, 25, 30, 33, 34, 36, 54, 74, 78, 82, 162, 200, 232, 233, 239, 243, 265, 271, 274, 307, 336, 340, 343, 350, 351, 352, 353, 362, 364, 392, 417, 420, 434, 457, 472, 478; *see also* Inuit
Esmoun 172
Esmounos 172
Esmun 172
Essalai 471
Ess-eorradh 73
Essus 71
Estanatlehi 173, 463, 464
Estiu 173
Estonia 29, 33, 155, 491
Estsanatlehi 173, 515, 518
Esu 172
Es-u 451
Esus 173, 358
Etain 54, 173, 321
Etan 151, 173
Etana 173
Eteocles 17, 57, 118, 173, 175, 252, 287, 387
Eteoclus 173, 176
Eterah 166, 173
Eternal Celestial Light 492
Eternal Land Ruler 39, 449
Eternally Good Being 367
eternity 49, 209, 340, 402
Ether 22, 30, 124, 368
Ethinoha 350
Ethiopia 59, 88, 116, 118, 169, 317, 382, 419, 503
Ethlinn 129
Ethne 68, 130
Ethona 80
etimmu 64
Etlinn 296
Etruria 206, 405; *see also* Etruscans
Etruscans 10, 53, 62, 69, 117, 119, 123, 136, 151, 178, 179, 180, 182, 201, 214, 222, 248, 249, 253, 279, 287, 307, 323, 342, 378, 385, 387, 449, 455, 468, 479, 484, 494, 501, 523
Etua 79
Etuda 346, 451
Euaechme 378
Euboea 9, 12, 67, 121, 165, 212
Euboeoa 62, 469
Eudora 173
Eudorus 173
Euios 152
Eumaeus 457
Eumelas 35
Eumelus 16, 173
Eumenides 171, 173, 183
Eumolpus 97, 117, 126, 174
Eunaomia 174
Euneus 174, 249
Eunomia 151, 174, 222
eunuchs 77, 79
Euonyme 61
Eupalamus 138
Euphemus 67, 174, 286
Euphrates 167
Euphrosyne 25, 174, 195, 461
Euplios 61
Eupolemeia 67, 376
Eupolemia 23, 174
Eurgyes 52
Euripides 349
Europa 17, 19, 25, 49, 76, 112, 165, 174, 253, 297, 323, 324, 356, 381, 402, 414, 457
Europe 38
Eurtye 440
Eurus 125, 133, 169, 174, 351, 522
Euryae 174, 315
Euryale 9, 52, 174, 192, 323, 365
Euryalus 67, 174, 314
Eurybatus 174, 286
Eurybia 75, 76, 135, 174, 184, 342, 356, 370, 379, 383, 387, 441
Eurycyda 165
Eurydale 68, 194, 297
Eurydamas 67, 174, 241
Eurydice 12, 35, 51, 54, 57, 69, 131, 142, 143, 162, 167, 174, 175, 176, 201, 218, 235, 287, 315, 318, 366, 369, 376, 440, 462, 464
Euryganeia 57, 173, 175, 387
Eurymede 96, 145, 175, 192, 241
Eurymedon 175, 380, 462
Eurynome 17, 20, 25, 74, 96, 104, 122, 174, 175, 195, 212, 231, 290, 356, 364
Euryphaessa 175, 230, 419
Eurysaces 31, 175
Eurystheus 16, 79, 119, 213, 216, 344
Eurytas 175, 316
Euryte 27, 35, 114, 201, 359, 387
Eurythemis 38, 175, 230, 288
Eurytion 57, 175, 241
Eurytus 13, 58, 135, 157, 175, 190, 240, 327
Euterpe 175, 330
Euthymus 175, 404
Euxine Sea 440
Eva 176
Evadne 21, 62, 67, 115, 134, 162, 169, 173, 175, 176, 339, 440
Evaecheme 240, 315
Evaki 176
Evander 145, 176, 241, 287, 370, 405, 414
Evandne 440
Evandrus 176
Evanippe 219
Evarete 12, 176, 290, 359
Evarte 218
Eve 7, 13, 14, 162, 176, 250, 302, 311, 327, 332, 407
Even as High 247, 357
evening 206
Evening Star 24, 152, 216, 242, 335, 495, 525
Evenissyen 176
Evenus 66, 146, 176, 343, 359
Everest, Mount 188
evergreen tree 154
evil 30, 35, 42, 51, 53, 91, 98, 104, 124, 129, 140, 143, 146, 148, 180, 187, 188, 197, 198, 204, 213, 222, 225, 267, 269, 270, 291, 295, 298, 302, 340, 357, 360, 421, 471
Evippe 173, 461
Evippus 240, 315
Evita 176
Evnissyen 176
Evua 354
ewe 225, 268
Ewe People 103
examinations 278, 505
Excalibur 282, 500
Excalibur 70
excrement 470
Exizkur 309
explosions 262
Eye of Ra 243, 415
Eye of Re 503
eyes 93, 102, 223, 243, 268, 367; gold 219; sacred 161, 347
Eyfura 98
Eyr 164
Eyra 164
Eyrgjafa 209
Ezuab 176

F 164, 176
Fa 176, 177, 233, 288, 366, 417
Fa'ahotu 79
Fa-akh 4
Fa'a-ti 177, 448, 468
Fachea 177
Facing South 141, 427
Fafner 177
Fafnir 52, 177, 224, 359, 368, 402, 431
Fagus 7, 177
Failinis 296
Fair Faced 148, 492
Fair-haired One 179, 296
fairies 127, 140, 160, 173, 179, 225, 252, 268, 274, 289, 326, 392, 424, 446, 524
faith 439, 501
faithful spirit 184
Faiyum 417
Fakahotu 177, 372
Fal 160
falcons 79, 114, 204, 222, 223
Falias 177, 195, 477
Fam 354
Fama 253, 381
Famien 177, 199
family life 61
famine 52, 71, 210, 500
Fan K'uai 177
Fan K'uei 177
Fan T'ao 371
Fand 177, 305
fans 26, 314, 344, 381
fantasy 313
Fanus 177, 178, 439
Fa-pet 4
Far Darter 62
Far East 45
Faraguvaol 177
Faravai 371
Farbauti 177, 287, 294
Farbuti 19, 177, 180
Faridun 86, 177, 265, 464
Farma-Tyr 357
farming *see* agriculture
Faro 177, 306, 354, 378, 501
fasces 86
fashion 98
fat 224
Fata 177
fate 34, 37, 98, 130, 145, 155, 176, 180, 242, 312, 318, 327, 426, 444, 447,

449, 460, 479, 490; *see also* destiny
Fates 16, 27, 38, 81, 177, 178, 206, 266, 284, 316, 327, 351, 358, 373, 422, 463, 480
father deities 5, 8, 29, 37, 38, 84, 88, 103, 139, 144, 160, 191, 192, 197, 232, 331, 354, 357, 364, 390, 420, 438, 448, 481, 490, 511, 516, 519
Fathir 329
Fatima 520
Fatimah 36, 327
Fa-trau 425
Fatua 104
Fatum 177
Fatu-Titi 79
Fault-finder 327
Faumea 178, 400, 479
Fauna Fatua 104
Fauna 12, 104, 157, 177, 178, 302
fauns 289, 415, 511
Faunus 104, 177, 371
Faustulus 10, 178, 287
Favnu 69
Favonius 178, 522
Favonus 178
Fawn 184
fear 98, 145, 228, 370, 382
Feast of Bellows 237
Feather Mountain 279
feathers 12, 44, 58, 197, 266, 277, 395
Febris 178
February 178
Februus 178
fecundity *see* fertility
Fecundus 389
Feima 209
Female Energy of All Good 156
femininity 177, 311, 331
Female Who Invites 246
Feng 225
Feng Huang 178
Feng I 346, 429
Feng Po 178
Feng P'o P'o 178
Feng Po-Po 178
Feng Shih 178
Feng-huang 439
Feng-po 288, 467, 520
Feng-P'o-P'o 178, 288
Feng-Tu 178, 512
Fenians 179
Fenja 331
Fenne 30
Fenrer 178
Fenrir 49, 53, 140, 156, 178, 192, 196, 198, 206, 210, 252, 284, 294, 297, 435, 465, 496
Fenris 178, 180, 444, 480
Fensalir 181
Fenti 75
Feonia 172
Fergus 135
Fergus Mac Roig 179
Fergus Mac Roy 179
Feridun 524
Feronia 176, 179, 180
ferrymen 56, 122
fertility 17, 24, 26, 30, 41, 46, 50, 58, 68, 69, 70, 73, 75, 78, 86, 87, 88, 94, 95, 104, 107, 111, 119, 122, 127, 130, 136, 139, 144, 148, 152, 154, 155, 156, 160, 164, 170, 172, 173, 176, 177, 178, 179, 180, 181, 186, 188, 189, 200, 204, 205, 206, 212, 234, 238, 242, 243, 253, 257, 267, 278, 285, 289, 290, 292, 294, 299, 300, 302, 309, 322, 325, 331, 336, 340, 343, 346, 347, 372, 390, 391, 394, 395, 399, 402, 417, 427, 432, 434, 441, 443, 443, 447, 458, 463, 470, 475, 481, 485, 486, 491, 508, 522
festivals 16, 96, 237
festivity 363
fetish gods 24
feud 108
fevers 178, 220
Fiachna 305
Fiachra 60
ficus tree 481, 512
Fides 179
fields 99, 287, 288, 371, 386
Fiery Black Clouds 3
Fiery Clouds 60
Fifth Dynasty 209
figs/fig trees 63, 253
Fighter 295, 463
Figonas 179, 496
Fihrist 86, 179
Fiji Islands 339
Fijii 452
Fili 160
Fimafeng 20
Fimbulthul 165
Fimila 22
finance 253
Find 179, 296
Fingal 179
fingers 138
Finias 179, 195, 477
Finland 26, 28, 33, 56, 155, 202, 216, 234, 235, 256, 258, 271, 272, 273, 274, 278, 279, 282, 289, 293, 295, 296, 305, 332, 365, 366, 385, 401, 411, 446, 453, 463, 478, 482, 488, 491
Finn 115, 151, 179, 196
Finn Mac Cool 179
Finn Mac Coul 179
Finn Og mac Cumhail 179
Finno-Ugric 33, 155, 159, 191, 207, 253, 254, 265, 392
Fintan 119
Finuweigh 179
Fionn 179
Fi'onn Mac Cumhal 179
Fionnuala 60
Fiorgyn 180, 181
Fiorvin 181
Fir Bholg 179, 449
Fir Darrigs 424
fir tree 73, 81, 157, 246
Firbolgs 92, 139, 179, 477
fire 9, 24, 26, 29, 43, 53, 71, 78, 97, 100, 110, 111, 117, 120, 122, 127, 128, 135, 136, 155, 172, 177, 178, 179, 180, 181, 182, 184, 192, 206, 216, 221, 226, 232, 233, 243, 245, 255, 257, 259, 267, 269, 270, 278, 289, 292, 293, 302, 311, 331, 333, 347, 353, 360, 367, 377, 389, 399, 402, 418, 432, 443, 444, 446, 456, 475, 483, 485, 487, 495, 502, 509, 511
Firefrost 358
firesides 102
Firishtak 179
Firistak 65, 179
First Cause 519
first man 39, 133, 134, 177, 266, 296
first mortal 267
First Savior 83
first woman 134, 176
First World Cycle 153
fish/fishing/fishermen 6, 9, 19, 25, 28, 29, 59, 82, 106, 107, 108, 112, 120, 125, 129, 132, 139, 148, 162, 177, 185, 207, 215, 223, 226, 261, 277, 282, 284, 298, 305, 361, 402, 481, 498, 515, 520, 523
fishhook 217, 223
fishing nets 151
Fith 160
Five Awesome Divinities 193
Five Blossoms 299
Five Deities 260
Five Dhyani Buddhas 45
Five Great Kings 33, 195, 273
Five Great Ones with the Powerful Roar 193
Five Islands of the Immortals 278
Five Kings 193
Five Orders of Dakinis 140
Five Suns 288
Fjalar 104, 160, 179, 191, 283, 294, 358, 415
Fjlar 220
Fjolnir 357
Fjorgyn 22, 161, 180, 252, 358, 463
Fjorgynn 180
Fjorm 165
Fjosnir 209
Flame 179
Flamen 395
Flames of Wisdom 155
flies 87
Flint 335, 518
Fljod 209
Floating Bridge of Heaven 43
flocks 334, 342, 371
flood 6, 13, 21, 28, 30, 50, 59, 60, 68, 71, 74, 80, 81, 94, 97, 102, 103, 110, 114, 119, 133, 143, 144, 147, 168, 172, 191, 214, 222, 228, 235, 240, 243, 256, 259, 264, 272, 280, 281, 295, 302, 308, 312, 335, 338, 344, 350, 361, 367, 391, 424, 431, 465, 470, 485, 491, 506, 508, 515
Flora 127, 180, 522
Floralia 180
Florence 310
Florida Island 273
flowers 33, 38, 103, 119, 123, 127, 131, 180, 212, 225, 272, 376, 393, 419, 493, 508, 509
flutes 80, 163, 491
Fly 87
fly-whisk 95
foaling 342
Foe of Yama 307, 513
fog 89, 197, 207, 225, 295
Foland 501
folk-heroes 69
Fomagata 180, 463
Fomonians 132
Fomorians 91, 92, 134, 139, 151, 155, 180, 193, 374, 477
Fomors 180
Fomosians 296
Fon 85, 142, 195, 197, 199, 233, 288, 292, 302, 334, 354, 366, 409, 500, 508
Fongasigde 339
Fons 115, 180
Fontinalia 115
Fontus 254
food 14, 23, 50, 108, 221, 225, 242, 343, 363, 366, 401, 417, 424, 456, 482, 503; cultivated 264, 405; rich 482
foot-races 128
foreigners 271
foresight 13, 163
forests 34, 74, 86, 89, 110, 124, 151, 163, 216, 262, 277, 284, 316, 320, 321, 371, 393, 427, 431, 445, 452, 512
foretelling 206
forge 111
forgetfulness 289
forgiveness 15, 465
Forjotnro 180
forked tongue 267
Form Fashioner 479
Formidable, The 158, 262
Formonians 89
Formosa 84
Fornacalia 495
Fornax 237, 495
fornication 371; *see also* sex
Fornjot 180, 229
Fornjotnr 180, 254, 517
Fornjotr 180
Fors 180
Forsete 180
Forseti 22, 90, 180, 336, 483
Fortuna 180, 253, 479
fortune 24, 74, 102, 120, 184, 202, 283, 285, 294
Forum 130
Fotia 45, 92
fountains 66, 153, 157, 218
Four Balams 197
Four Branches 68
Four Eras 460
Four Great Kings 332, 497
Four Hundred, The 118
Four Hundred Northerners 118, 180
Four Hundred Rabbits 118
Four Hundred Southerners 118
Four Kings 505
Four Rain 288
Four Suns 28, 288, 508
Four Wind 288
Four Wind Gods 94
fourth earth 101
Fourth Month 128
fowl 149
foxes 150, 237, 265, 267, 304, 315, 334, 504
fragrance 443, 489
Fraig 181
France 36, 141, 156
Franconia 430
frankincense bush 290
Fratres Arvales 10, 180
Frau Berchta 98
Frau Gode 98
Frau Holle 221
Frau Venus 221
Frau Wode 98
Fraus 180, 352
Fravahar 180
Fravak 311
Fravakain 311
Fravar 180
Fravartin 180, 181
Fravashi 180, 181, 385
Fravashis 181, 495, 515, 524
Frea 181
Frejya 98, 153, 183
Freke 181
Freki 181, 190, 357
freshness 265
Frey 22, 181, 198, 350, 432, 435, 444, 483
Frey'a 181
Freya 181, 491
Freyja 22, 42, 53, 97, 159, 181, 198, 233, 243, 294, 309, 318, 350, 357, 421, 435, 446, 447
Freyr 22, 36, 98, 101, 160, 166, 181, 190, 245
Fria 181
Fricco 181
Frid 164
Fridthjof 53
Friend of Spring 493
Friend of the Wine 90, 299
Friendly Folk 392, 511
Friga 181
Frigg 22, 181, 189, 193, 293, 448
Frigga 22, 25, 72, 90, 98, 105, 161, 164, 180, 181, 183, 192, 220, 222, 357,

www.ebook3000.com

402, 434, 436, 448, 480, 487, 497, 500, 501
Frija 181
Frimla 22
Fro 181
Frobak 516
frogs 43, 55, 131, 209, 226, 275, 507
frontier 437
frost 11, 104
Frost Giants 465
Frost Mane 4
Frosti 160
Frothi's Mill 331
frowning 99
frozen earth 190
fruit 7, 22, 26, 32, 48, 99, 119, 144, 345, 440
fruit trees 387
Frygga 181
Fu Chiao 132
Fu Hsi 181
Fu Shen 182, 428
Fu Sing 182
Fuchi 182
Fudo 182
Fudo-Myoo 140, 182, 193, 418
Fufluns 182
Fugen 327
Fugen Bosatsu 182, 307, 410, 411
Fugen En-myo 410
Fugi-San 182
Fu-Hsi 181, 182, 279, 352
Fu-Hsing 182
Fuji 11, 26, 182, 216, 377
Fuji, Mount 419
Fujiama, Mount 182
Fujin 105, 182
Fu-Jin 182, 351
Fujiyama, Mount 419
Fukiyi 182
Fuko 193
Fuku 47, 183, 273
Fuku-kensaku Kannon 261
Fukurakuju 256
Fukurokujin 183, 426
Fukurokuju 183
Fuku-Roku-Ju 183
Fulgora 183
Fulla 183
Fulla 22
Fulnir 209
Fundin 160
funerals 224, 319, 339, 439, 512
Fu-Pao 226
Furiae 171, 173, 183
Furies 79, 171, 173, 183, 201, 315, 365
furnace 120, 475
Fu-Shen 182
Fushimi 237
Fu-shou-lu 428
Futa-na Island 234
Futemimi-no-kami 282
Futo no Yasumuro 39
Futsu-Nushi 183, 446, 450
future 56, 116
Fylgia 183
Fylgja 183
Fylgjur 183
Fylgukona 183
G 183, 272
Gabil 184, 190, 353
Gabriel 8, 14, 53, 184, 274, 290, 397
Gad 184
Gadda 318
gadfly 96
Gaea 11, 18, 20, 27, 31, 35, 37, 56, 67, 80, 116, 118, 119, 122, 128, 135, 136, 137, 142, 143, 146, 152, 162, 167, 170, 171, 174, 184, 190, 194, 205, 208, 210, 212, 216, 219, 230, 231, 315, 326, 330, 342, 356, 360, 365, 370, 377, 382, 383, 386, 387, 390, 391, 403, 404, 407, 431, 440, 441, 455, 458, 459, 460, 461, 463, 469, 480, 484, 522
Gaelestis 249
Gaels 45, 84, 92, 95, 96, 112, 115, 477
Gaga 184
Ga-Gaah 183, 184
Gagnrad 184, 357
Ga-Gorib 188
Gahe 184
Gahongas 160, 184, 252
Gaia 184, 351
gaiety 98
Gajana 186
Gajanana 186
Gajendra 186
Gajomartan 188
Gaki 146, 184, 364, 389
Galan-Mai 96
Galar and Fjalar 415
Galar 104, 160, 191, 220, 283, 358
Galaru 507
Galatea 12, 137, 185, 387, 393
Galateia 342
Galeru 196, 397, 507
Galgavaldyr 357
Galla 503
Galli 133, 137
Gallo-Roman 420
gallows 357
Gallu 146, 185, 291
Gama 185
Gamab 188
Gamagu 188
Gamati 185, 188
Gambia 199, 405
gambling 28, 299, 395
Gamelios 185, 522
games 509
Gamlat 242
Gamr 187, 206
Gamsu 185, 522
Ganadevatas 185
Ganapati 185, 186, 283
Gana-Pati 186
Ganas 185, 186
Ganaskidi 185, 515
Ganda 47, 185
Gandaki River 410
Gandalf 160
Gandarewa 185, 186, 266
Gandayahs 184, 252
Gandayaks 185
Gandevi 69, 186
Gandha 185
Gandhara 148, 185
Gandhari 150, 185, 264
Gandharva-Loka 293
Gandharvas 63, 117, 146, 147, 149, 185, 186, 203, 254, 275, 282, 319, 336, 401, 436, 447, 487, 489, 490
Gandharvis 186
Gandhema 47, 185
Gandiva 69, 186, 437
Ganesa 186
Ganesh 186
Ganesha 148, 185, 186, 256, 263, 374, 424, 427, 497
Ganesha-Chaturthi 186
Ganga 63, 77, 148, 186, 187, 263, 280, 285, 303, 374, 413, 498
Gangadhara 187
Ganga-ja 187, 263
Gangamma 187, 331
Ganges River 63, 89, 99, 186, 187, 263, 374, 409, 410, 427, 454, 488, 492, 498
Gangeya 100, 263
Gangler 357
Gangrad 487
Gansam Deo 196
Ganumedes 187, 208
Ganv-devata 196
Ganv-devi 196
Ganymeda 187, 208
Ganymede 11, 64, 113, 117, 187, 208, 235, 474
Ganzir 64, 170
Ga-oh 15, 140, 183, 184
Gaoh 183
Gaokerena tree 53, 203, 474
Gaokerna 501
Gapn 87
Garamas 9, 187
Garang 9
Garbhadhatu 140
Garden of Eden 14, 162, 510
Garden of Eternity 249
Garden of Hesperides 40, 194, 210, 213, 216, 342
garden of paradise 152
gardens 9, 144, 390, 495
Gardens of Delight 249
Gardens of Paradise 249
Gardens of Perpetual Abode 249
Gardens of Refuge 249
Gari 190
Garide 9, 187
Garita 187
Garitari 187
Garkain 187
Garm 187, 206, 444
Garme 187, 206
Garnr 187
Garshasp 266
Garuda 47, 71, 187, 188, 250, 258, 275, 308, 411, 431, 443, 493, 497, 498
Garudas 146, 264, 333
Garudas Tamra 264
Garudi 188, 427
Gashanki 142
Gashan-Ki 347
Gasmu 142, 188
Gat Tooth 453
Gatamdug 188, 198
gates 249
Ga-Tum-Dug 184, 346, 347
Gau 7
Gaucarapita 197
Gaul 7, 71, 89, 97, 105, 136, 142, 153, 169, 173, 193, 196, 253, 292, 296, 360, 403, 454, 477
Gaumaonocan 233
Gaumaonocon 233
Gaumuh 511
Gaumukh 188
Gauna 188
Gaunab 188, 209, 476
Gauri 148, 158, 188, 305, 374, 375, 427, 492
Gauri-Sankar 188
Gaut 188, 357
Gautama 27, 45, 211, 238, 262, 332, 397, 404, 410, 484, 488, 500
Gautama Buddha 77, 149, 153, 264, 303, 310, 313, 440, 441, 479
Gavampati 188
Gavidjeen 129
Gawa 188, 254
Gaya 158, 188
Gaya Maretan 29, 53, 188, 189, 223, 248, 311
Gayatri 189, 413, 416, 444
Gayomart 188, 189
Gayomort 188, 516
gazelle 158, 317
Gbaye-Gborun 366
Ge Hinnom 189
Ge 69, 139, 184, 195, 197, 292
Gea 184, 189
Geb 81, 135, 168, 184, 189, 243, 266, 342, 353, 394, 396, 421, 428, 456
Gebal 27, 136
Gebaliah 136
Gebelzeizis 520
Gebtu 243
geese 30, 43, 106, 203, 341
Gefion 22, 189
Gefjon 181, 189
Gefn 181
Gegenees 189
Gegeneis 136, 189
Gehenna 23, 189, 211, 425
Geinos 27
Geirod 189, 196
Geirrod 25, 189
Geirrothr 189
geise 68, 292
Geishas 237, 255
Gekka-O 189
Gelanor 142, 189
Gelgia 192
Gelgja 178, 192
Gello 185
Gelou 185
Gemini 77, 90, 116, 153
gems 517
Gendenwitha 189, 190
Genea 179, 190, 273
General Wei 232
Generator 416
Genesis 49, 162, 510
Genethlios 387
Genetyllis 61
genie 162
Genie 251
Genii 23, 85, 138, 148, 180, 181, 190, 251
Genos 179, 273
Genshin 45, 251
Gentle Manitou 265
gentleness 242
Geoffrey of Monmouth 70
Gerd 22, 190
Gerda 190, 435
Gerdhr 190
Gerdr 190
Gere 190
Geri 181, 190, 357
Germany 98, 130, 138, 241, 343, 397, 482, 506, 522
Gerold 30
Gerold Iarla 30
Gerra 184, 190
Gersimi 181
Geruthus 189
Geryon 112, 113, 127, 162, 190, 213, 356
Geshtinnanna 190
Gestinanna 158, 190, 236
Geto 96
Geuh Urvan 190
Geusha Urvan 325
Gevar 322
Gewi 112, 132, 190
Geyaguga 190
Ghaddar 251
Ghanan 519
ghanta 46, 47, 48, 474
Ghantapani 490
Ghar-Jenti 190
Ghatotkacha 99, 263, 280
Ghede 85, 93, 190, 303
Ghee 25, 26, 190, 308
Ghineh 17
Ghirdhima 295
ghosts 101, 168, 184, 208, 512
ghouls 158, 495
Gi 184
Giallar Horn 192
Giallarhorn 101
Giane 190
giants 8, 9, 12, 18, 19, 27, 35, 37, 49, 51, 53, 56, 62, 66, 80, 82, 89, 92, 97, 99, 104, 106, 107, 108, 109, 110, 112, 113, 137, 140, 149, 154, 167, 171, 179, 180, 183, 184, 189, 190, 191, 193, 196, 198, 203, 208, 209, 212, 219, 220, 224, 225, 226, 230, 233, 243, 254, 256, 262, 270, 283, 286, 295, 320, 367, 404, 432, 484
Gibal 347
Gibil 184, 309
Gidja 191, 511
Gid-Kuzo 191
gigim 64

Gijigouai 191, 320
Gikuyu 191
Gil 309
Gilbert and Nauru Islands 65
Gilfaethwy 199
Gilgamas 191
Gilgames 191
Gilgamesh 13, 64, 71, 98, 152, 167, 191, 242, 270, 296, 347, 348, 392, 423, 430, 486, 525
Gilgamish 191
Gilgamos 191
Gilling 191, 358, 415
Gilma 309
Gilou 185
Gilvaethwy 312
Gimle 191
Gimli 191
Ginnar 160
Ginnungagap 191
Ginnunga-gap 82, 191, 331, 345, 517
Gioll 193, 465
Gir 241
Gira 342
Girau 184
girdle 16
Girija 192, 374
Girl of T'u 124
Girra 241, 342
Girru 192
Giryama 330
Gishgimmash 191
Gishnumunab 309
Gishzida 192
Gita 84, 295
Gitche 160, 192, 272
Gitche Manitou 192
Gitchee Manito 192
Gitchee Manitou 272
Gitche-Manito 307
Gitchy Monedo 272
Giuki 344, 431
Gizdubar 191
Gizida 14
Gizidu 161
Gjall 192, 209, 516
Gjallar 192
Gjallarhorn 192
Gjalp 209
Gjol 192, 193
Gjoll 165, 178, 193, 326
Gladsheim Castle 72
Glads-heim 192
Gladsheim 192, 232, 357
Glasir 192
Glasisvellir 189
Glasnir 192
Glastonbury 84
Glauce 134, 143, 192, 314, 457
Glaucus 9, 10, 52, 56, 68, 95, 130, 145, 192, 218, 241, 297, 323, 375, 386, 414, 417, 433, 434, 454, 461
Glaucus of Corinth 192
Glauk-Opis 79
Glaur 436
Gleipnir 156, 178, 192, 284, 465, 480
Glepnir 101
Gleti 193
Glias 64
Glimmering Misfortune 210
Glispa 193
Glitnir 180
Gloin 160
Glooscap 193
Glooskap 193
Glorious Realm 48
glory 78, 270
gloves, magic 196
Glowing Red Clouds 59
Glunen 193
Glusgahbe 193
Gluskap 193, 303, 506
Gna 22, 193, 402
Gnaa 193
gnomes 119, 166, 446
Gnostics 6, 8, 9, 11, 14, 21, 34, 48, 65, 75, 83, 86, 93, 113, 133, 146, 166, 168, 179, 208, 222, 230, 290, 307, 351, 364, 384, 437
Gnowee 193
Go Dai Myo-o 193
goats 19, 31, 40, 88, 125, 132, 143, 153, 161, 253, 318, 390, 507, 513
Gobannon 195
goblins 101, 109, 158, 196, 211, 274, 513, 514
Gobujo 345
God 8, 14, 191, 397
God of Few Words 496
God 7 Rain 508
Godai-Myoo 33, 140, 182, 193, 195, 273, 473
Godaison 193
Godavari 187
Gode 98
god-eating god 32
god-saint 312
God-set-up-at-the-crossroads 445
God-Who-Hoards-Thoughts 43
Goemmason 139, 140
Goewin 199, 312
Gog and Magog 193
Gogome 426
Gogo-me 426
Gogopa 79, 80
Gohone 15
Goibhniu 193
Goibniu 134, 193, 195, 212, 235, 479, 502
Gokarmo 422
Gokuraku 193
Gokuraku Jodo 193
Go-Kuraku-Jodo 442
Gokuraku-Jodo 45
gold 20
Gold Colored One 226
Gold Mane 198
Gold Might 198
Gold Rings 322
Gold Tooth 209
golden apples 20, 80, 171, 172, 194, 213, 216, 284, 377, 462
golden armor 11
Golden Bells 133, 194
golden boar 181
Golden Bough 194
Golden Bristled 198
golden calf 38
Golden Comb 198
Golden Eagle 218
golden egg 219, 258, 388
Golden Embryo 388
Golden Fleece 64, 67, 137, 184, 194, 211, 250, 314, 383, 462
Golden Germ 219
Golden Hall 42
Golden King 453
Golden Lady 148, 188
Golden Mountain 89
Golden One 352
Golden Person 416
Golden Ram 194
golden saddle 96
golden shower 12
golden touch 321
Goldfax 198
goldsmiths 360
Golgi 17
Golgos 17, 61
Goliath 402
Gollveig 198
Golveig-Heid 198
Gondemar 52
Gondul 181
Gonlad 199
Gonlod 199
Good and Rewarding God 87
Good Creation 29
good deeds, register of 234
good faith 179
Good God 477
Good Mind 45
Good One 364
Good Power 45
Good Spirit 25, 160, 306
Good Striker 441
goodness 273
gopa 396
Gopatshah 194, 439, 502
Gopel 194, 275
gopi 396
Gopinath 194, 275
Gopis 194
Gor 194
Gordian Knot 194
Gordius 136, 194, 321
Gore 194
Gorgasus 299
Gorge 38, 114, 194, 359, 473, 480
Gorgo 194
Gorgons 119, 174, 194, 195, 315, 380, 383, 440
Gorgopa 194
Gorgophone 52, 65, 93, 105, 194, 202, 218, 231, 290, 358, 376, 440
Gorgyra 11, 72
Gorgyra 194
Gorias 194, 195, 477
Gorilla 354
Gortys 195, 403
Gosh 147, 189
Gotama 410
Gotterdammerung 397
Gou 195, 292, 360
Goub 188
Gouri 188
Govannon 40, 155, 193, 195
Govardhana 275
Govind 34, 195, 275
Gowree 148
Gowrie 188
Gozanze-Myoo 33, 193, 195, 473
Gozu Tenno 195, 350
Gozu-Tenwo 195
Grace 195
Graces 20, 25, 51, 118, 173, 174, 175, 195, 210, 212, 264, 375, 461, 523
Gracious God 422
Gradivus 66, 195, 431
Graeae 194, 195
Graha 195
Grahapati 25, 195
Graiae 119, 168, 194, 195, 315, 380, 383
Grail 305
grain 15, 26, 38, 119, 128, 132, 211, 218, 236, 287, 304, 305, 311, 521
Grainme 179, 196
Grainne 196
Gram 91, 196, 430
Gramadevata 196
Gramadeveta 196, 309, 331
Gramadevetas 196
Gramanis 147, 196
Gramdevati 196
Gramnnos 105, 196
Gramnos 196
grandfather deities 23, 29, 105, 206, 350, 385, 500
grandmother deities 46, 123, 196, 267, 350, 450, 471
Grandson of Waters 60, 501
Grannos 196
Grasper, The 397
grass 6, 328, 344
grasshoppers 6
Gratiae 195
Gration 190, 219, 469
graves 91, 146
graveyards *see* cemeteries
Grdhra-Kuta 407
Great Ancaeus 67
Great Archon 65
Great Baal 86
Great Battle of Kurukseta 372
Great Bear 204, 404, 460, 500
Great Black Belt Deity 150
Great Black Bird 351
great black man 81
Great Black One 148, 257, 301
Great Boar 259
Great Bodhisattva 278
Great Builder 330
Great Cackler 189, 266, 394
Great Canoe 307
Great Cataclysm 301
Great Defender, The 411
Great Diamond Sow 156
great egg 189
Great Emperor of the Eastern Peak 383, 449, 478
Great Father 105, 139, 233, 301, 468
Great Forefather 83
Great Fortune 307
Great God 301, 406, 427
Great God of the Rock 360
Great God of Thebes 43
Great Hare 192, 320, 335
Great Hawk 470
Great Heruka 215
Great Illuminator 140
Great Kings 293
Great Land Master 361
Great Lord 302, 427
Great Man 301, 474, 492
Great Medicine Dance 321
Great Mistress of the Day 41
Great Mother 136, 148, 309, 312, 326, 513
Great Mother from the Water 261
Great Mountain 13
Great Mountains of the East 168
great nourisher of mankind 303
Great Oasis 44
Great Potentate 148, 301
Great Power 468
Great Queen 148, 301, 328
Great Rainbow Snake 196, 397
Great Sea Mother 417
Great Serpent 371
Great Snapping Turtle 315
Great South Gate of Todai-ji 348
Great Spider Sussistinnako 446
Great Spider 231, 446
Great Spirit 6, 15, 66, 78, 139, 154, 172, 192, 200, 302, 307, 426, 505
Great Spirit of the Winds 183
Great Sun Buddha 140
Great Tornak 472
Great Triad 468
Great Unseen One 83
Great Water Serpent 482
Great White One 60
Great Yogi 427
Greater Ennead 168
Great-Food-Princess 482
Greece 6, 8, 9, 10, 11, 12, 13, 14, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 31, 34, 35, 36, 37, 38, 39, 40, 42, 43, 44, 47, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 72, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 88, 89, 91, 92, 93, 94, 95, 96, 97, 101, 104, 105, 112, 113, 114, 115, 116, 118, 119, 121, 122, 123, 125, 126, 127, 128, 129,

www.ebook3000.com

130, 131, 132, 133, 134, 135, 136, 137, 138, 141, 142, 143, 145, 146, 147, 150, 151, 152, 153, 156, 157, 159, 160, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 173, 174, 175, 176, 177, 179, 180, 184, 185, 187, 189, 190, 192, 194, 195, 200, 201, 202, 206, 208, 209, 210, 211, 212, 213, 214, 216, 218, 219, 220, 222, 228, 229, 230, 231, 232, 235, 238, 239, 240, 241, 243, 244, 245, 249, 250, 252, 253, 254, 256, 257, 266, 268, 269, 274, 275, 277, 283, 284, 286, 287, 289, 290, 291, 292, 295, 297, 298, 299, 300, 302, 307, 309, 312, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 327, 328, 329, 330, 331, 333, 334, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 349, 351, 354, 355, 356, 357, 358, 359, 360, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 385, 386, 387, 388, 389, 390, 391, 392, 393, 395, 396, 403, 405, 407, 408, 410, 411, 412, 414, 415, 416, 417, 418, 419, 420, 422, 429, 430, 431, 432, 433, 436, 437, 438, 440, 441, 447, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 468, 469, 473, 474, 477, 478, 479, 480, 484, 485, 495, 497, 502, 503, 506, 507, 508, 509, 520, 522, 524
Green Ladies 141
Green One 503
Green Tara 454
Green Taras 47, 71
Greenland 16, 343, 472
Greip 209, 462
Grendel 180
Grerr 36, 98, 181
Grhapati 25, 26, 195
Grid 196, 357, 496
griffin 33, 197
Griffon 197
griffons 341
Grigris 177, 312
Grihadevatas 148
Grimhild 197, 198, 344, 431
Grimmir 196
Grimmr 196, 357
Grimner 189, 196
Grimnik 196
Grimnikr 357
Grimnir 189, 357
Grismadevi 196
Grith 196
Gritta 357
Groa 83, 196, 197
Gro-bdog 196
Grogopa 79, 194
Gromovit 197
Gromovnik 197
Gronw Pebyr 103, 292
Gros-Ventre Group of Algonquin 344
groves 151, 216
growth 285, 393
Grudyen 197
Grydat 357
Gryffon 197
Gryphon 197
Gryton 67
Gsin-rje gsed 512, 513
Gu 195, 197, 302, 360
Gua 197
Guabancex 197
Guabanex 78
Guabonito 197, 364
Guacarapita 78, 233, 239
Guacas 207
Guachimines 62, 197
Guagugiana 197
Guaire 162
Gualicho 197
Guamansuri 62, 197
Guamaonocon 197, 239, 487
Guantauva 197
Guaracy 214
Guarani 478
Guarayo People 6
Guarayu 314
guardians 28, 32, 35, 48, 58, 64, 70, 82, 88, 99, 102, 103, 117, 122, 147, 172, 181, 201, 216, 224, 257, 292
Guatama Buddha 408
Guatauva 78
Guatemala 197, 227, 228, 271, 502, 508, 523
Guayarakunny 197
Guaymi 335, 351
Gucumatz 197, 228, 278, 459
Gudatrigakwitl 197
Gudrun 197, 252, 344, 447, 464, 501
Guecubu 32, 198
Gueggiahora 198
Guener 199
Guesa 198
Guga 198
Gugal 309
Guha 263
Guhkin-Banda 198
Guhyaka 198, 282
Guiana 478
Guimazoa 78, 197, 233, 239
Guinea 7, 177, 409
guinea fowl 38, 114, 145
Guinevere 70
Guingamore 328
Gukumatz 197, 387
Gukup 227
Gukup Cakix 198, 227
Gukup Kakix 115
Gula 3, 58, 93, 94, 188, 198, 300, 346, 347, 451
Gula-Bau 158, 198
Gu-lang 375
Gulgallana 236
Gullfaxi 198
Gullinborst 198
Gullinbursti 164, 198
Gullin-Bursti 181, 198, 432
Gullinkambe 198
Gullinkambi 198, 516
Gulltoppr 198, 209
Gullveig 198, 252, 294, 501
Gulsa Goddesses 198, 203, 458
Gulses Goddesses 198
Gul-shes 483
Gulu 198, 256, 272
Gulveig 198, 252
Gulveig-Hoder 178, 198
Gumshea 242
Gun 199, 409, 500, 508
Gunab 188
Gunarh 199
Gunarhnesengyet 199
Gundari-Myoo 32, 48, 193, 199
Gundhary 185
Gundlad 199
Gundul 490
Gung 186
Gunga 186
Gungir 432
Gungner 199
Gungnir 159, 199, 245, 322, 358, 407
Gunlodd 415, 444
Gunnar 344, 431, 501
Gunnlod 199, 357, 358
Gunnolth 357
Gunnthra 165
Gupta-Chara 90
Gur 93, 104
Gurikhoisib 476
Gurra 263
guru 100
Guruhi 199, 354
Gushasp 516
Gushkinbanda 161, 199
Gutrune 197, 198
Guttorm 344
Guyana 7, 507
Gwakko-Bosatsu 199
Gwawl 199
Gwen 199
Gwern 176
Gwidion 199
Gwigawd 360
Gwinn 199
Gwion Bach 267
Gwri 391, 393, 403
Gwydion 40, 42, 58, 68, 103, 125, 155, 199, 292, 312, 391
Gwyn 134
Gwyn Gohoyw 391
Gwynn 209
Gwyrthur 134
Gyane 21
Gyas 200
Gyes 208
Gyges 18, 184, 200, 469
Gyhldeptis 200
Gyhledeptis 200
Gylfi 189
Gymer 190
Gymir 19, 180
Gyogi 41
Ha 211, 317
Ha Wen Neyu 200
Hab'al 200
Ha-B'al 200
Habal 200
Habard 357
Habel 7
Habetrot 200
Habil 7
Habl 7
Habone 183
Hacavitz 509
Hachakyom 200
Hacha'kyum 200
Hachiman 200, 510
Hachiman Daibosatsu 200
Hachiman Taro 200
Hachi-o-jo or 464
Hackeberg 357
Hactcin 200
Hadad 13, 36, 79, 86, 91, 200, 201, 404, 424
Ha'dad 200
Haddad 13, 200
Hadding 83
Hades 4, 11, 18, 19, 72, 94, 123, 135, 136, 137, 138, 146, 153, 170, 171, 174, 191, 201, 205, 211, 212, 213, 216, 251, 289, 318, 356, 366, 367, 376, 377, 379, 382, 385, 387, 403, 411, 419, 420, 425, 433, 434, 455, 461, 468, 508, 518
Hadhayos 439, 501
Hadith 327
Hadui 201
Haemon 54, 57, 201, 315
Haemus 104, 113, 126, 201, 364, 403, 522
Haemus, Mount 69
Hae-Sun 201
Hafaza 201
Hafgan 65, 393
Haftoreng 204
Hag of Beare 112
Hagar 8, 201
Hagnias 67, 468
Hago 333
hags 102, 112, 155, 252, 287, 328
Hahai Wugti 201
Hahgwediyu 183
Hahgwehdaetgah 147, 518
Hahgwehdiyu 518
Hai 4, 29
Haida 15, 160, 261, 470, 475, 515
Haidar 36
Haihayas 408
hail 105, 225
Haimavati 201, 374
Haio Hwa Tha 201
hair 108, 267, 275, 282
Haiti 24, 27, 29, 78, 85, 89, 93, 105, 131, 141, 142, 172, 190, 197, 252, 302, 308, 310, 334, 360, 364, 396, 431, 465, 487
Haitsi-aibeb 209, 476
Haiwa 14, 176
Hajar 201, 243, 520
Hakahotu 177, 372
Hakaiki 79, 201, 364
Hakalanileo 260
Hakea 201, 324
Hakoi-berent 357
Hakon 464
Haku, Mount 182
Hal 209
Hala 90, 201
Hala-Bhrit 90
halahala 281
Halayudha 90
Hala-Yudha 90
halcyon 18
Haldja 155
half-mortal 490
Halia 201, 457, 461, 484
Halieus 27
Halirrhothius 66, 201, 202
Halitta 36
Hall of Judgment 46, 58, 298
Hall of Maati 75, 457
Hall of the dead 166
Hall of the Slain 490
Hallat 37
Hallisa 276
Hallowmas 116
Hallows 305
Hallows of Ireland 477
Halmus 127, 192, 202, 433
halo 102
Haltia 155, 202
Halvete 210
Halys 202, 405, 432
Ham 345, 525
Hamadryad 202
Hamadryades 202
Hamadryads 157, 202, 354
Hambaris 202
Hambarus 202
Hamdir 252, 447
Hamedicu 202
Hamestagan 202
Hamingja 183, 202
Hamingjur 183
Haminja 202
Hamistakan 202
hammer 108, 123, 153
Hammon 43
Hammurabi 202, 309
Ha-Mori 200, 265
Hamsa 203
Hamsapadika 202
Hamsavati 202
Hamskerpir 193
Han Chung-Li 68, 202
Han Hsiang-tzu 202, 221
Han Siang-tsi 68, 163, 202
Han 177, 278
Han Yu 202
Hanan Cuzco 449
Hanata 51, 202, 242
Han-chung Li 163
handicrafts 80
Handmaiden 98
Hand-Stroking-Elder 458
Hanea 335
Hanga-tyr 357
hanged men 193, 357
Hanghepi Wi 202
Hangi 275
Hanging Hair 200
Hanhau 28, 202, 246, 324

Haniyama-Himi 203
Haniyasu-Bime-No-Kami 203, 247
Hani-Yasu-No-Kami 202, 450
Hannahannas 198, 203, 458
Hanpa 203, 376
Hansa 203
Ha-nui-o-rangi 200, 385
Hanuman 53, 99, 196, 203, 248, 398, 399, 401, 416, 434, 442
Haokah 203
Haoma 185, 203, 222, 325, 436, 437, 464, 514
Haoshyangha 223
Hap 4, 61, 203
Hapi 60, 61, 203, 352, 456, 477
Hapi-Ankh 61
Hapi-Asar 420
Hapikern 204, 350, 486
Hapinunu 204
happiness 40, 50, 97, 102, 150, 182, 183, 224, 277, 283, 326, 414, 426, 427, 428, 439, 475, 513
Happy Realm of Sukhavati 442
Hapti-ta-f 477
Hapto-iringa 33, 204, 514
Haptok Ring 204
Hapu 44
Hapy 48, 204
Hapy-Wet 204
Har 160, 204, 222, 357
Har Wer 205
Hara 204, 427, 498
Hara Berezaiti 203, 204
Hara Gauri 65
Haraiti, Mount 204
Harakhte 204
Harakhtes 83, 204, 269
Harakhty 396
Haranya-kasipu 336
Harbard 204, 357
harbors 316, 370, 387
hard material 228
Harendotes 204
Har-End-Yotef 204
Hari 498
Hari Hara-putra 230
Hariati, Mount 204, 439
Harihara 204
Harinagamesi 204
Harinaigameshin 204
Harini 63
Haripriya 285
Hariti 146, 204, 272, 283, 371
Harits 205, 237
harlots 8, 75, 242, 248, 271, 291
Harmachis 396, 438
Harmakis 438
Harmathoe 205
Harmonia 24, 56, 61, 66, 83, 112, 145, 168, 171, 205, 212, 214, 234, 238, 312, 370, 386
Harmothoe 18, 131, 205, 319, 372
Harocrates 222
Haroeris 205, 222, 448
Harops 205
harp 105, 115
Harpakhrad 92, 205, 317
Harpiae 205
Harpies 19, 20, 21, 47, 113, 117, 125, 165, 174, 205, 319, 356, 357, 381, 382, 385, 522
Harpina 66, 205, 359
Harpokrates 205, 222
Harpooner 222
Harpy 91, 205, 508
Harsaphes 44, 205, 214
Harsiesis 206
Har-Sopdu 437
Hartomes 204, 206
Haruspices 206
Harut 206
Haru-Yama-No-Kasumi-Onoko 206
Haru-Yama-no-Kasumio-noko 33
harvest 16, 28, 32, 33, 95, 104, 130, 171, 197, 224, 241, 242, 266, 303, 308, 325, 349, 364, 402, 451, 495, 498
Hasan 36
Ha-sert 4
Hashmalim 53
Hasibwari 206
Hasisu 282
Hassan 36
Hastehogan 81
Hasteseyalti 206
Hastesezini 206
Hasteshogan 206
Hasteyalti 81
Hastinapura 7, 374, 415, 423, 486, 503
Hastsehogan 206
Hastseltsi 206
Hastseoltoi 206
Hastseyalti 206, 515
Hastsezini 206
Hastshehogan 515
Hatai Wugti 84
Hatchetchu 425
Hatet 214, 417
Hat-hor 206
Hathor 50, 54, 61, 73, 75, 76, 86, 87, 93, 95, 98, 206, 215, 216, 234, 243, 244, 319, 341, 352, 353, 394, 396, 419, 433, 453; and Imhotep 44
Hathor of the Horizon 206
Hati 178, 206, 435
Hati Hrodvitnisson 206
Hat-Mehit 206
Hatmehit 341
Hatra 87
hatred 35, 85
Ha-Tsiang 211
Hattic 309
Hatuibwari 179, 206
Hau 32, 61, 420
Haufey 180
Hauhet 226
Hau-hra 61
Hauillepenyi 207
Haukas 207
Haumea 178, 207, 259, 260, 264, 351, 377
Haumea-ka-hanau-wawa 207
Haumia 207, 372, 405, 476
Haumia-Tikitiki 60, 207, 399, 405
Haur 160
Haurvatat 45, 48, 138, 455, 520; and Ameretat 207
Havai 83
Havaiki 83
Havamal 179
Havfru 33, 207
Havfrue 207
Havmand 207
Hawaii 29, 82, 165, 201, 207, 216, 217, 218, 240, 254, 256, 259, 260, 261, 262, 264, 265, 266, 267, 271, 277, 280, 282, 284, 293, 294, 303, 313, 326, 351, 364, 369, 376, 377, 392, 405, 452, 455, 467, 476, 481, 482
Hawaiki 83
Haweniyo 207
Hawiyah 207
hawks 4, 5, 43, 44, 73, 86, 97, 138, 215
Hawthor 206
Hawwa 176
Hay 208
Haya 207, 347
Hayas 149
Haya-akihiko-no-kami 375
Haya-Aki-Tsu-Hime 207
Haya-akitsu-hime-no-kami 207, 208, 246
Hayagriva 55, 208, 312, 489, 498, 499, 513
Hayagriva the Horse-Necked 48
Haya-ji 182, 208
Ha-Yama-Tsu-Mi 200, 420
Haya-sasura-hime 208
Hayik 208
Hayk 69, 208
Hayowentha 201
Hay-Tau 17, 86
hazel tree 91
Hea 161
headaches 15
healing 44, 53, 62, 72, 99, 102, 107, 116, 135, 162, 164, 172, 200, 231, 244, 245, 246, 260, 268, 272, 318, 347, 348, 366, 412, 422, 427, 436, 443, 513, 517; *see also* medicine
health 24, 45, 141, 149, 172, 177, 207, 220, 229, 246, 270, 371, 410, 490
hearing 422
heart 116
Heart of Heaven 228
Heart of the Mountains 459, 460
Heart of the People 501
hearth 107, 111, 120, 182, 195, 475
heat 135, 198, 400, 418
Heaven 58, 59, 84, 102, 110, 126, 171, 193, 198, 212, 221, 222, 225, 343, 349, 362, 379, 410, 416, 423
Heaven Knows Who to Save 366
Heaven of Contentment 472
Heaven of Sakra 120
Heaven of the Four Great Kings 120, 149
Heaven of the Thirty-three Divinities 120
Heaven-great-shining-Kami 41
Heavenly Alarming Female 40, 41
Heavenly Central Lord 39, 42
Heavenly Fairy 519
Heavenly Grandchild 346
Heavenly Herdsman 266
Heavenly Hosts 311
Heavenly Hound 408, 413, 447
Heavenly Weaving Wall 503
Heavenly-Point-Blade-Extended 43
Hebat 212
Hebdomad 208, 408
Hebe 66, 163, 165, 187, 208, 212, 213, 253, 254, 523
Hebel 7
Hebrews 7, 8, 13, 16, 22, 23, 26, 38, 39, 53, 61, 74, 75, 85, 86, 87, 93, 95, 162, 165, 166, 176, 184, 189, 201, 211, 236, 243, 250, 285, 290, 291, 332, 338, 339, 345, 350, 402, 417, 418, 425, 451, 459, 510, 524
Hebs 477
Hebt 44
Hecab 208, 209
Hecaerge 61
Hecantonchires 455
Hecat 70
Hecate 8, 23, 70, 94, 97, 118, 151, 166, 168, 170, 201, 208, 379, 381, 383, 403, 417
Hecaterus 136, 208, 415
Hecateus 6
hecatomb 141
Hecatoncheires 19, 115, 135, 208
Hecatoncheiroi 190
Hecatonchires 118, 133, 200, 208, 209, 228, 356, 469, 484
Hecatontocheiroi 208
Hector 12, 116, 145, 209, 232, 374
Hecuba 62, 116, 134, 145, 208, 209, 286, 287, 374, 386, 412
Hedj-wer 60
Hedone 351
Heelios 210
Hefaidd Hen 403
Hefedha 209
Hegal 309
Hegemone 195
Hegira 327
Heh 209, 340, 359
Hehet 209, 352, 359
Hehu 209, 298
Hehuah 250
Hehui 209, 352
Hehut 209, 298
Heian 251
Heid 198
Heidr 198
Heidrun 209, 516
heifers 50, 151
Hei-lao-ye 123
Heilyn 209
Heimda 483
Heimdal 19, 22, 209, 357
Heimdall 22, 23, 29, 46, 53, 91, 101, 181, 192, 198, 209, 221, 262, 329, 404, 464
Heimdallr 209
Heimdal-Rig 209
Heime 322, 501
Heitsi-Eibib 188, 209
Hek 209
Heka 32, 61, 209, 420
Hekate 208
Hekatoncheires 208
Hekau 209
Heke-Heke-I-Papa 209, 399
Hekent 418
Hekenth 269, 425
Heket 209, 269
Hekret 32, 61, 420
Hekt 209
Hel 53, 90, 166, 180, 187, 198, 206, 210, 211, 214, 252, 294, 338, 345, 435, 444, 463, 485
Hela 210, 359
Helblindi 177, 210, 294, 357
Heleius 194, 210
Helen of Troy 9, 10, 12, 23, 31, 57, 72, 116, 129, 145, 165, 205, 210, 214, 215, 216, 231, 240, 288, 299, 318, 341, 344, 359, 374, 381, 382, 386, 440, 463, 523
Helena 168
Helenus 116, 145, 374
Heleus 52, 210, 440
Helheim 210, 214, 366
Heliaads 210
Heliades 19, 20, 22, 118, 210, 286, 356, 380, 381, 382, 458, 474
Heliads 210
Helicaon 10, 56, 210, 461
Helice 210, 359, 522
Helicon, Mount 23, 87, 218, 239, 330, 376
Heliopolis 54, 62, 81, 168, 367, 420, 428, 456
Helios 11, 18, 19, 20, 22, 62, 129, 210, 230, 286, 370, 375, 379, 386, 395, 417, 474
heliotrope 131, 211
Helius 11, 19, 20, 35, 66,

www.ebook3000.com

76, 127, 131, 144, 166, 169, 170, 175, 195, 210, 211, 314, 323, 356, 365, 379, 380, 419, 436, 444, 461, 508
Hell 52, 56, 126, 128, 166, 178, 207, 211, 228, 241, 243, 248, 250, 284, 324, 345, 385, 409, 425, 452, 455, 505
Hella 210
Hellawisi 210
Helle 79, 194, 211, 239, 342, 369, 383
Hellen 11, 19, 20, 21, 147, 156, 211, 316, 366, 452, 509
Hellenes 211
Hellespont 194, 214
Hellewite 210
Hellia 210
Helmet of darkness 359
Heloha 211
Helvede 210
Helviti 210
Hema 211, 256, 262, 455, 456, 485, 503, 506
Hemera 22, 31, 61, 118, 122, 170, 211, 230, 327, 352
Hemhemti 61
Hemsut 211
Hem-taiu 61
Hemth 32, 61, 420
Heneb 211
Heng 211, 317; and Ha 211
Heng Ha Er Tsiang 211
Henga 211
Heng-Ha-erh-Chiang 317
Heng-O 122
Heng-Tsiang 211
Hen-Heru 425
Henir 22, 211, 321, 350
Henkhisesui 211
Henmemet 211
Heno 218
Henosis 21, 351
Henti-requ 477
Hentiu 212
Hent-neteru 417
Hent-nut-s 379, 477
Hepa 60
Hepat 69, 212
Hepatu 212
Hephaestus 25, 57, 67, 80, 101, 136, 138, 163, 171, 212, 327, 474
Hephaistos 12, 18, 20, 21, 26, 56, 61, 66, 68, 117, 119, 137, 165, 170, 184, 195, 205, 212, 264, 274, 317, 321, 357, 362, 365, 370, 372, 377, 383, 391, 392, 405, 432, 440, 478, 479, 502, 522
Hepit 212, 459
Heptet 212
Hept-shet 75
Heqet 209
Heqt 209
Heqtit 209
Hequet 209
Hera 6, 16, 19, 21, 35, 56, 57, 61, 64, 66, 67, 76, 117, 127, 135, 146, 152, 162, 163, 165, 171, 201, 208, 212, 213, 216, 222, 236, 239, 245, 249, 253, 286, 289, 290, 314, 327, 342, 356, 365, 374, 383, 387, 390, 403, 405, 419, 441, 462, 523
Heraclea Pontica 455
Heracleopolis Magna 205, 214
Heracles 6, 7, 10, 16, 19, 27, 35, 38, 42, 52, 56, 57, 58, 66, 67, 69, 70, 76, 79, 80, 112, 113, 114, 119, 121, 123, 127, 133, 137, 138, 145, 152, 162, 167, 169, 171, 175, 190, 194, 205, 208, 210, 213, 215, 216, 218, 219, 229, 232, 240, 243, 250, 257, 286, 287, 292, 297, 309, 314, 316, 317, 328, 338, 341, 342, 343, 363, 374, 377, 378, 387, 388, 389, 391, 440, 457, 462, 473, 490; *see also* Hercules
Heracules 370
Heraean Games 127
Herakhty 204
Herakleopolis 70, 82
Herakles 213
Heraktes 396
Heramba 186
herb lore 30
Her-ba 4
herbs 53, 104, 265, 281, 334, 366, 436
Hercules 11, 213, 520, 523; *see also* Heracles
Herdesuf 222
Herdsman 275
Here 212, 460
Herecgunina 213
Herero 339, 363
Herfadir 357
Her-Hequi 212, 419
Herhkhty 222
Heri-seru 75
Herishef 70
Herjan 213, 357
Herkeios 213, 522
Her-khu 419
Hermakhis 213, 222
Hermanubis 58, 59, 214
hermaphroditic deities 61, 214, 256, 427
Hermaphroditos 214
Hermaphroditus 61, 214
Herme 386
Hermehit 317
Hermeias 214
Hermes 6, 9, 19, 20, 23, 47, 61, 64, 66, 67, 72, 80, 83, 88, 94, 114, 116, 118, 119, 127, 128, 137, 145, 146, 157, 162, 171, 172, 173, 174, 175, 176, 205, 211, 214, 219, 239, 287, 297, 302, 318, 319, 331, 359, 365, 366, 371, 376, 378, 380, 381, 382, 390, 406, 419, 431, 434, 464, 469, 480, 522
Hermin 241
Hermione 205, 214
hermit 99
hermit crab 255
Hermitten 214
Hermod 90, 105, 181, 214, 357, 435, 480
Hermoder 22
Hermodr 214
Hermoine 56, 205, 365
Hermonthis 328
Hermopolis 62, 464
Hero 214, 225, 404
Herodotus 36, 349
heroes 31, 224, 266, 295, 296, 400, 430
Herok'a 214
herons 97, 486
Herophile 40, 286
Herophilus 61
hero's moon 136
Herovit 214
Her-Pest 212
Herse 26, 118, 119, 211, 214, 372
Her-sha-s 417
Hershef 70, 205, 214
Her-she-taiu 458
Her-she-tauti 477
Hersilia 396
Hersione 52
Her-tesu-f 269
Hertha 215, 343
Hert-Hantua 417
Her-thertu 457, 483
Hert-ketit-s 214, 417
Hert-Nemmat-Set 215, 417
Hert-sefu-s 215, 417
Her-tuaiu 425
Hertyr 357
Heru 4, 73, 215, 222
Heru-ap-sheta-taui 253
Heru-em-akbet 438
Heru-em-Anpu 214
Heru-Hekenu 486
Herui 49
Heruka 33, 47, 215, 489
Heruka Buddha 47
Herukabuddhas 215
Heru-ka-pet 415
Herukas 215
Heru-khabit 425
Heru-Khu 215
Heru-Khuti 215
Heru-pa-kaut 215
Heru-Pa-Khret 205
Heru-p-ka 415
Heru-P-Khart 205
Herusmatauy 215
Her-ut-f 417
Heru-Tuat 425
Heru-tuati 4, 5
Heryan 357
Hery-sha-duat 215
Hes 93
Hesahet 215
Hesaret 215
Hesat 215
He-She 84
Hesiod 31, 80, 118, 122, 137, 177, 195, 205, 208, 315, 342, 349, 356, 387, 391
Hesione 74, 147, 213, 215, 216, 391, 457, 460
Hespere 216
Hespereia 216
Hesperia 66, 216
Hesperides 20, 66, 78, 80, 114, 172, 173, 216, 229, 284, 352, 383
Hesperis 216
Hesperos 216
Hesperus 76, 169, 495
Hesperusa 216
Hest 216, 242
Hestia 135, 146, 201, 212, 216, 374, 377, 387, 403, 495
Hestia 26
Hesus 173
Hetch-a 425
Hetch-abehu 75
Hetch-met 419
Hetch-nau 418
Hetchuti 4
Hetemet-bau 4
Hetemet-khemiu 340
Hetemet-khu 477
Hetemitet 269
Hetep-uaa 477
Hetet-sept 4
Het-Hert 216
Hetmehit 92
Hettsui-no-kami 237
Heve 176
Heviosso 288, 508
Hewer 338
Heybajra 290
Heyoka 216
Hey-Tau 16
Heyvajra 120
Hiawatha 139, 201, 350
Hibakara-o 345
Hicetaon 215
Hiceton 216
Hidden One 43
Hidden Souls 458
Hidimba 99
Hido 430
H'ien-hou 50
Hierapolis 70
Hieromneme 51, 216, 431
high gods/goddesses 49, 86, 172, 179, 192, 197, 202, 208, 209, 212, 249, 291, 343, 344, 353, 355, 405, 420, 423, 446, 448, 454, 455, 465, 466, 475
High One, The 204, 357
High Producing 41
High, Powerful, Undefiled One 50
Highest God 519
Highest of All Powers 367
Higona 179
Hi'iaka 218, 260
Hi'iaka-i-ka-poli-o-Pele 218, 377
Hi'i-lawe 217
Hiisi 216
Hika-po-loa 216, 261
Hikawa-hime 282
Hikoboshi 266
Hikohohodemi 217, 221, 223, 251, 347, 355, 420, 473
Hiko-hohodemi-no-mikoto 217
Hikuleo 217, 386
Hild 490
Hill of Healing 297
Hill of Tara 290
Himalaya, Mount 308
Himalayas 34, 69, 186, 201, 282, 306, 307, 313, 319, 373, 374, 413, 427, 436
Himavat 186, 217, 374
Himavati 257
Himeropa 217
Himinbjorg 209
Himyarite 234
Hina 79, 178, 217, 218, 235, 260, 277, 313, 400, 407, 460, 467, 468, 478
Hina-ai-ka-malama 377
Hina-arauriki 178, 217
Hina-famed-in-story 217, 467
Hina-hanaia-i-ka-malama 377
Hina-Hau-One 217
Hina-Keha 217
Hina-opuhala-koa 217
Hina-Titama 217
Hina-ula-ohia 217, 277
Hina-ulu-ohia 264
Hina-uri 217, 313
Hina-who-worked-in-the-moon 256
Hinayanist 303
Hinduism 7, 14, 15, 24, 25, 27, 31, 34, 41, 42, 48, 50, 52, 53, 60, 63, 65, 69, 71, 75, 77, 78, 84, 89, 90, 91, 92, 97, 98, 99, 100, 101, 102, 105, 120, 121, 129, 140, 141, 143, 144, 147, 148, 149, 153, 157, 158, 159, 160, 185, 186, 187, 188, 203, 204, 211, 219, 237, 247, 248, 249, 253, 256, 257, 258, 259, 263, 264, 275, 276, 279, 280, 281, 282, 285, 290, 293, 299, 301, 303, 305, 306, 308, 309, 311, 314, 319, 325, 329, 332, 335, 336, 337, 338, 349, 372, 373, 374, 385, 388, 390, 393, 396, 397, 398, 399, 401, 404, 406, 408, 410, 412, 415, 416, 421, 422, 427, 433, 434, 435, 436, 439, 441, 443, 444, 447, 450, 452, 453, 454, 474, 483, 485, 486, 487, 488, 492, 493, 494, 495, 497, 498, 499, 502, 511; Lakshmi 493; Triad 285; Trimurti 422, 498
Hine 217, 218, 235, 399, 452, 467
Hine-ahu-one 217, 344, 452, 467
Hine-Hau-One 217, 218
Hine-i-tau-ira 217, 218
Hine-itau-ira 452

Hine-nui-te-po 217, 218, 405, 452
Hine-Te-Ngaru-moana 217
Hine-titama 218
Hine-tu-a-maunga 218
hinges 116
Hinlil 218
Hino 15, 218, 266, 366
Hinoki 255
Hinu 218
Hinun 218
Hi'ona 179
Hiordis 220, 430, 431, 501
Hippalcimus 67, 76, 104
Hippasus 13, 218, 290
Hippe 21, 69, 218, 316
Hippea 241, 387
Hippios 387
Hippocoon 93, 145, 194, 218
Hippocrene Well 376
Hippocrene 218, 376
Hippodamas 114, 202, 379, 440
Hippodameia 17, 19, 47, 61, 76, 81, 112, 127, 136, 164, 175, 176, 218, 287, 290, 297, 344, 376, 377, 385, 387, 440, 474
Hippodameis 51
Hippodamia 35, 218, 359, 378
Hippodamus 146, 218
Hippolochus 57, 96, 145, 192, 218, 219, 241
Hippolyta 57
Hippolyte 10, 16, 42, 57, 66, 181, 213, 218, 219, 368, 378, 439, 497
Hippolytus 9, 17, 57, 190, 218, 219, 380, 469, 497
Hippolytus 9, 17, 57
Hippomachus 57, 219, 376
Hippomedan 451
Hippomedon 17, 219
Hippomenes 78, 219, 240, 315, 316
Hippona 219
Hipponome 35, 252, 318
Hipponoos 95, 219
Hipponous 76, 95, 115, 219, 378
Hipponus 219
hippopotamus 46, 223, 408, 455, 462
Hippotades 21, 219
Hippotes 134, 163
Hippothoe 51, 298
Hiranya 219
Hiranyagarbha 105, 219
Hiranyakashipu 219, 256
Hiranya-kasipu 140, 154, 219, 306, 375, 388, 491
Hiranyakasipu 219
Hiranyaksa 219
Hiranyaksha 140, 154, 219, 401, 491
Hiranyakshipu 401
Hiranyapura 140, 219
Hiribi 514
Hirihbi 220
Hirnakess 491
Hiro 220, 343, 366
Hirohito 251, 260
Hirugo 162, 220, 246
Hiruko 41, 162, 220
Hisakitaimisi 220
Hisame 426
Hisa-me 426
Hischen 232
Hiscilla 172, 220, 240, 320, 382, 474
Histia 216
history 130, 408
Hitaspa 266
Hitchi 220
Hitchiti 6, 220
Hittie 78
Hittites 34, 58, 59, 62, 69, 73, 87, 167, 191, 198, 203, 212, 234, 236, 241, 242, 279, 376, 394, 424, 458, 459, 481, 483, 484, 507
Hiuke 220
Hiuki 101, 307
Hiyoyoa 220
hJamdpal 307
Hjordis 220
Hjuki 101
Hkum Yeng 220
Hlamo 454
Hlamos 185, 422
Hler 19, 180, 220, 359, 517
Hlesey 19
Hlidskialf 181, 220, 357
Hlidskjalf 220, 490
Hlif 164
Hlifthrasa 164
Hlin 220
Hlina 220
Hlithkjalf 220
Hlodyn 220, 252, 463
Hlora 463
Hloride 463
Hloridi 463
Hlorrida 463
Hlorridi 463
Hmin Nat 220
Hnikar 357
Hnitbjorg 220
Hnoss 181
Hnossa 22
Ho 221
Ho Po 221, 346
Ho Shen 221
Hoa 60, 161
Hoakils 29, 221, 511
Hoard Thoughts 41, 221
Hobal 7, 62, 200
Hobnel 27, 120, 221
Hobnil 221
Hocereu Wahira 221
Hod 221, 357, 483
Hodar 221
Hodd-Dropnir 322
Hodd-Mimer 322
Hoddmimir's Wood 516
Hod-dpag-med 45
Hoddrofnir 322
Hoder 221, 336
Hoderi 217, 221, 223, 347, 355, 420
Ho-deri 221, 223
Hodhr 221
Hodir 221
Hodr 221
Hodsrun 264
Hodur 22, 90, 104, 221, 322, 358, 397
hoe 223
Hoener 211, 294
Hoeni 211
Hoenir 211
Hofud 221
Hofvarpir 193
Hog-child 259
Hogni 344, 431
Hohodemi 217
Hoho-demi 217
Ho-hsien-ku 68, 221, 475
Hoita 221
Hokewingla 221
Hol 211
Holatsi Dilyi'le 471
Holatsi Litsi 471
Hold 98, 209
Holda 98, 181, 221
Holdja 155
Holla 221
Holland 98
Holler 482
Hollow Hills 477
Holy Bible 162
Holy Ghost 232
Holy Grail 70
Homa 203, 222
Ho-Masubi 255, 334
Home of the Dead 125
Homeiocan 222
Homer 11, 25, 38, 96, 105, 137, 175, 195, 245, 252, 342, 349, 358, 417, 433
Hometeuli 222
Homeyoco 222
Homshuk 121
Homunculus 222
Homusubi 255
Honduras 244
Hone 211
Honer 211
Honest 326
honey 77, 119, 265
Honeybee 327
honey-cake 119
Hong Kong 298
Honga 222
Honir 211
Honochenokeh 222
honor 100
Ho-no-suri 223
Ho-no-susori 221
Honshu 251
Hoodmimir's Wood 397
Hooho 217
Hoori 217
Hopewell 6
Hopi 113, 201, 228, 267, 273, 311, 327, 329, 331, 368, 371, 397, 432, 435, 438, 456, 457; creation legend 228, 397
Hopleus 37, 115, 169, 222
Hopoe 218, 377
Hor 222
Hor Beditite 95
Hor Merti 205
Horae 69, 76, 116, 151, 164, 174, 195, 212, 222, 461, 523
Hora-Galles 222
Horai 222
Horaios 65, 75, 222, 231
Horakhti 222
Horchia 66
Horea 222
Horkhenti Irti 205
Hormazu 28, 222
Hormothoe 18
Hormusda 77
Horn of Plenty 132
Hornbori 160
horned owls 114
horns 11, 13, 22, 95, 108, 124, 181, 184, 214, 268
Horomazes 28
Horos 222
Hor-Sa-Iset 206
Horse-Face 74, 123, 298, 317, 350, 507, 511, 512
Horse-Necked 208, 489
horses 6, 50, 56, 74, 77, 95, 105, 109, 123, 127, 169, 208, 219, 223, 248, 266, 267, 403, 431, 475, 487, 489
Horta 222
Horta Auirini 396
Horus 4, 44, 48, 62, 63, 79, 92, 93, 95, 98, 168, 204, 205, 206, 212, 213, 215, 222, 234, 243, 340, 341, 353, 394, 417, 418, 421, 424, 425, 437, 448, 464, 477, 481, 499, 505
Horus of the Horizon 204, 213, 396
Horus the Elder 205, 323
Horus-Set 425
Horus-Sopt 438
Horyu-ji 42
Hoshang 189, 223, 516
Hosho 193, 199
Hosho-Nyorai 223, 400
Ho-sien-ku 163, 221
hospitality 111
host of earth 272
Hosuser 420
Hosuseri 217, 221, 223, 347, 473
Ho-suseri 223
Hosvir 209
Hot One 453
Hot Springs 105
Hotar 25, 223
Hotei 224, 303, 320, 426
Hotei-Osho 224
Hoth 294
Hothbrod 322
Hotherus 221
Hotoru 224
Hottentot 30, 112, 132, 133, 188, 190, 209, 476
Hotua 159
Hotua Poro 237
Hotu-papa 224, 399
Hoturu 224
Hou Chi 226
Hou Ji 224
Hou-Chi 224
hougouns 89
Hound of Chulain 135
hounds 102, 129, 407, 427
Hounds of Zeus 205
Houri 224
Houris 224
House of Books 421
House of Don 312
House of Dust and Darkness 241
House of Horus 206
House of Recompense 16
House of Song 45
House of the Dawn 369
House of the Sun 472
household deities 55, 74, 126, 127, 132, 160, 195, 196, 227, 264, 270, 287, 378, 393, 459, 463
Hou-Tse 224
Hou-T'u 224
Hou-T'u nai nai 224
Hou-T'u Shen 476
How-Chu 224
Ho-wori 217
hPhags-skyes-po 497
hPhren-ba-ma 400
Hrada 219
Hraesveglur 224
Hraesvelg 224
Hrae-Svelger 224
Hraesvelgr 224, 252, 493
Hraesvelgur 224
Hra-f-ha-f 75
Hrafna 357
Hraudung 189
Hreidman 177
Hreidmar 52, 177, 224, 368, 402
Hreithmarr 224
Hreshtak 65
Hrid 165
Hriem 209
Hrim-faxi 4, 5, 38, 139, 351
Hrim-Thurs 97, 434, 517
Hrimthursar 517
Hringhorn 90, 224, 230
Hringhorni 224
Hrodvitnir 178, 206, 435
Hropt 357
Hrotik 180, 181
Hrsikesa 224, 275
Hrungnir 198, 224, 231, 300
Hsaing Chun 225, 346
Hsi Hai 519
Hsi T'ien 45, 442
Hsi Wang Mu 225, 279, 371, 519
Hsiang 225, 346
Hsiang Chun 225
Hsiang Fu-Jen 225, 346
Hsien Shan 127
Hsi-Ho 225
Hsi-Hua 225
Hsi-Ling Shih 226, 430
Hsing Shen 225
Hsi-Wang-Mu 225, 429, 504, 508
Hsuan T'ien Shang Ti 123
Hsuan T'ung-tzu 505
Hsuan-T'ien Shang-Ti 225
Htamenmas 225
Hu 227, 429, 486
Hu and Sia 225
Hu Ching-Te 225, 317
Hu Gadarn 14

www.ebook3000.com

2. Move your hands down and touch the mideyebrow. Feel your fingers grow very long (energetically) and penetrate all the way back to the base of the skull. Focus on the back. Remember: Tan Tien and the universe spiraling. With the spiraling, the Chi in the fingers will become hot. It will expand and penetrate out through the back of the head all the way to the universe behind.



Fig 3.46 *Fingers touch mideyebrow and penetrate to the back of the skull and the universe at the rear.*



Fig 3.47
Tan Tien and the Universe.

Hu King-te 475, 519
Hu Sia 225
Hua Hsien 225
Huaaiti 4
Huacas 225, 513
Huahuantli 225, 459
Huaillepenyi 225
Huallallo Caruincho 225, 513
Huana Cauri 449
Huanacauri 306
Huang 225
Huang Ti 224, 226, 227
Huang T'ien 226, 466
Huang T'ien Shang Ti 226, 466, 519
Huang-Lao 226, 517
Huang-Ti 125, 226, 423, 430
Huan-ti 423
Huan-T'ien Shang-Ti 423
Huasi-Camayoc 132
Hubaba 270
Hubal 226
Hubar 226, 466
Huchi Fuchi 182, 226
Huecuvus 226
Huehuecoyotl 509
Huehueteotl 226, 509
Huehuetonacacipactli 129, 226
Huejotzingo 325
Huemac 226, 395
Hueymac 226, 472
Hueytecpatl 226
Hueytonantzin 226
Huga 253
Hugh 18
Hugi 226, 406
Hugin 226
Huginn 226, 357
Huh and Hauhet 226
Huichaana 132
Huichilobos 226
Huichol 265, 450
Huitzilo-Mexitli 226
Huitzilopochtli 114, 118, 125, 131, 133, 226, 288, 303, 325, 368, 376, 395, 460, 470, 471, 481, 508, 509
Huitzilopoktli 226
Huitzilo-Poktli 226
Huitznahua 227
Huixtocihuatl 469, 481
Hu-kheru 477
hula 218, 277
Hulda 221
Huldra 98
Huliamma 227, 331
Hulle 221
Hum 33
human sacrifice 58, 95, 117, 143, 173, 460, 472
Humba 270
Hum-ba 270
Humbaba 270
Humhum 270
hummingbird 226
Humpbacks 185
Humu 259
Hun 425
Hun Batz 227
Hun Chuen 227
Hun Hunahpu 114, 227
Hun Tun 227
Hunab Ku 94, 227, 244
Hunab-Ku 227, 245, 363
Hunahpu 32, 115, 198, 228, 245, 394, 502, 508, 509, 523; and Ixbalanque 227
Hun-Ahpu 227
Hunahpuguch 37, 227, 245
Hunahpu-Guch 32, 127, 227, 228, 387
Hunahpuutiu 227, 245, 394
Hunahpu-utiu 127, 228, 387
Hunan 225
Hun-Apu 227
Huncame 227
Hun-Came 508
Hun-cane 227
Hundling 220
Hundred Character Tablet 163
Hundred-Handed 208, 228
hunger 51, 207, 210
Hunhun-Ahpu 228, 509
Hunhun-Apu 227
Huniman 203
Hunooman 203
Hunthaca 124
hunting 21, 27, 31, 42, 65, 66, 70, 78, 89, 92, 93, 108, 109, 114, 115, 199, 206, 217, 227, 242, 299, 321, 322, 323, 325, 330, 341, 342, 348, 352, 360, 434, 512, 524, 525
Hun-Tun 226, 227
Hupa 362
Hupasiyas 234, 236, 237
Hupnos 437
Hupseus 230
Huracan 197, 228
Huracan Hura-Kan 228
Hurakan 228, 459
H'uraru 228
Hurani 224
Huriyeh 224
Hurn 228
Huron 78, 139, 154, 164, 167, 183, 202, 211, 228, 267, 475, 518
Hurrian 34, 58, 212, 279, 424
hurricanes 3, 19, 131, 168, 228, 311, 456
Hurrites 59, 87, 241, 279, 483, 484, 520
Hurucan 228
Huruing Wuhti 228, 397
Hurukan 228
Husayn 36
Husband of Laksmi 275
Husbishag 228, 334
Hu-Shen 225
Husheng 223, 516
Hussein 36
Hutameh 228, 243
Hutchaiui 228
Huti Watsi Ya 228
Huve 228
Huveane 228
Huwawa 270
Huytaca 124
Huzruwauqti 228
Hvar 228
Hvaranah 270
Hvarekhshaeta 228, 514
Hvare-Khshaeta 228, 300, 468
Hvergelmer 229, 358
Hvergelmir 165, 229, 345, 358, 495, 496, 516
hyacinth 31, 130, 229
Hyacinthos 229, 522
Hyacinthus 62, 152, 229
Hyades 66, 80, 114, 133, 173, 229, 385
Hyagnis 229, 310
Hyakinthos 229
Hyas 66, 80, 114, 173, 229
Hybris 371
Hydra 49, 125, 162, 213, 229, 438, 466
Hygea 229
Hygeia 229, 231
Hygieia 72, 229, 299
Hyginus 342
Hyk 209
Hyksos 421
Hylas 67, 229, 318, 376
Hyllus 19, 145, 229
Hylonome 229
Hymen 61, 113, 152, 229
hymenael 229
Hymenaeus 164, 229, 484
Hymer 229
Hymir 229, 480
Hymn of Ashurbanipal 525
Hymn of Fifty Names of Marduk 309, 520
Hymn of the Curetes 136
Hymn to Amen-Ra 315
Hynos 22
Hypate 229, 319, 330, 343
Hyperbius 17, 229, 287, 387
Hyperboreans 6, 62
Hyperenor 229, 230
Hyperion 135, 169, 175, 184, 210, 211, 222, 230, 419, 461, 462
Hypermestra 230
Hypermnestra 38, 142, 143, 230, 288, 297, 462
Hypnos 118, 122, 156, 170, 228, 230, 266, 327, 328, 351, 363, 375, 414, 437, 461
Hypnus 230, 437
hypocrites 207
Hyposouranios 179, 230, 368
Hypseus 137, 462
Hypsipyle 145, 174, 230, 249, 339, 463
Hyrax 112, 190
Hyria 230, 365
Hyrieus 230, 354, 365
Hyrmina 13, 67, 230, 468
Hyrrokin 224, 230
Hyskos 51
hysteria 364
Hyuga 347
Hyuki 311
I 120, 230
I Kaggen 112
Iacchus 24, 88, 146, 152, 230
Iaeuo 231, 510
Iah 3, 250
Iahweh Sabaoth 408
Iakchos 152
Ial 230
Ialdabaoth 65, 75, 93, 222, 230, 231, 364, 408, 437
Ialemus 113
Ialmenus 66, 72, 231
Iamus 22, 62, 175
Ianus 249
Iao 8, 65, 75, 231, 250, 510
Iao Iouo 250
Iao-sabaoth 408
Iapetos 131, 231, 318, 391
Iapetus 80, 135, 169, 184, 231, 249, 462
Iarn-greiper 326
Iarngreiper 463
Iarnsaxa 231, 300, 326
Iarnvid 198
Iasion 146, 165, 231, 381, 385
Iaso 72, 229, 231, 299
Iason 165
Iasus 25, 78, 231, 236, 377
Iath 164
Iatiju 231, 264
Iatik 231
Iatiku and Nautsiti 231
Iaw 250
Ib 5
Ibadan 358
Ibe Dji 231
Ibibio 243
ibises 3, 4, 5
Iblis 14, 84, 85, 138, 144, 148, 231, 251, 446, 468, 520
Ibmel 253
Ibo People 34, 128, 396
Iboroquiamio 231
Ibrahim 8, 201, 243, 520
Ibraoth 408
Ibukido-Nushi 208, 231
Icaria 231
Icarius 93, 105, 171, 194, 231, 314, 379
Icarus 138, 231
ice 110
ice giants 252, 517
Iceland 183, 331, 462, 501
Icelandi 53
Icheiri 231
Ichiki-Shima-Hime 97
Ichikishima-Hime-no-Mikoto 231, 464
icicles 303
Icona 232
Ictinike 232
Id 232
Ida 17, 40, 232, 239, 297, 308, 317, 489, 522
Ida, Mount 17, 51, 137, 138, 194, 374, 522
Idaea 232, 381, 382, 403
Idaeus 232
Idakru 232, 445
Idalia 61
Idamante 232
Idas 67, 116, 130, 138, 232, 316, 386
Ida-Ten 232
Idavida 232, 282
Idavita 232
Idavold 232
Idavolir 232
Idavoll 232
Idavollen 72
Idawold 232
Iddahedu 332
Idem-Kuguza 365
Idhunn 232
Idi 15
Idika 148
Idlirvirissong 232
Idmon 64, 232, 462
Idni'dslkai 471
idol-worshipers 248
Idom 62, 67
Idomene 6, 16, 232, 297, 379
Idomeneus 218, 232
Idun 105, 232, 233, 462
Iduna 105, 232
Idunn 232
Idunna 232
Idurmer 139
Idyia 233
Ie 250
Iegad 233
Iella 78, 197, 233, 239
Iemhetep 235
I-em-hetep 235
Ier 230
Iermaogauacar 197, 239
Iesous 250
Iesu 250
Ieu 250
Ieui 250
Ifa 172, 176, 233, 366
Ifa-Eschu 233
Ifaluk 82
Ife 358, 365
Ifilici Wacinaci 233
Ifing 210, 233
Ifrits 23, 251
Ifugao 506
Igaluk 233
Igerna 70
Iggdrasil 516
Igigi 59, 63, 233, 484
Igirit 26
Ignis 233
ignorance 105
Iha-haga-hime 347
Iha-naga-himi 245
Iha-no-hime 233
Iha-tsutsu no wo 479
Ihatsutsu-nome 247, 479
Ihi 233
Ihi-yori-hiko 234
Ihoiho 234, 452, 468
Iho-Iho 239
Ihy 98, 206
Ijaksit 32
Ijo 507
Ika-tere 234
Ikhnaten 33
Ikhnaton 79
Ikiti-simapime-no-mikoto 41
Iko 256, 430
Iksion 245

Ikto 234
Iku-Tu-Pikone-nomikoto 41
Il 37, 164, 166
Ila 232, 330, 413
Ilabrat 14, 234, 348
Ilah 37, 164, 166
Ilaheva 28, 164, 234
Ilamatecuhtli 234, 295
Ilamatecutli 129, 234, 471
Ilancue 234
Ilancueitl 234
Ilat 234
Ilat 36, 37
Ilavida 234, 499
Ilbalintja 263
Ildebaoth 8
Ile-Gbigbona 437
Ilem 234
Ile-Titu 437
Ilhallubu 13
Ili-abrat 234, 348
Iliad, The 11, 245
Ilias 165
Ilinbongasum 234
Ilione 145
Ilios 165
Ilithyia 163
Ilium 215, 235
Illa 78
Illa Tici Viracocha 497
Illillos 168
Illinus 83, 97
Illiyun 234, 243
illness 14, 50, 58, 102, 140, 248, 272, 388
Illusion 148
Illuyankas 234, 237
Illyria 24, 112, 297
Illyrius 24, 83, 112, 234, 239, 419
Ilma 234, 235, 297
Ilmaka 234
Ilmaqah 166, 234
Ilmarinen 234, 235, 253, 271, 289, 295, 297, 411, 479, 482, 488
Ilmaris 234
Ilmatar 234, 235, 257
Ilmater 289
Ilmuqah 37, 234, 422
Ilos 139
Ilu 164, 385
Ilumarru 13
Ilus 51, 93, 113, 175, 235, 244, 287, 462, 474
illusion 313
Iluwir 13
Ilya-Muromyets 104
Ilyas 165
Ilyasin 165
Ilythia 289
Ilythiae 171
Im 235
Imana 235
Imarut 223
Imaymana Viracocha 235
Imberombera 235, 504
Imbrogeneis 136
Imenarete 165
Iment 44
Imgig 524
Imhetep 235
Imhotep 235, 317
Imhoteph 72
Imhursag 241, 346
Imi kashiki no Mikoto 39
Imi 13
Immaradus 174
immeasurability 209
Immer 241
immortality/immortals 16, 45, 48, 121, 122, 123, 128, 207, 221, 224, 225, 269, 317, 329, 382
Immovable 182, 275
Imos 501
Impartial Judge 411, 512
imps 99
Imra 235
Imseti 48
Imsety 223
Imuit 235
Imuthes 235
Imy-Hemef 235
In 517
Ina 217, 235, 468
Inaba 361
Inaccessible 148, 374
Inachus 19, 64, 67, 76, 235, 236, 239, 316, 331, 383, 404, 405
Inaclius 235
Ina-Gami Furu-Kushi-Nada-Hime 282
Inagami-Hime 282
Inagi-Utasunhi 236
Ina-Init 235
Inanna 58, 137, 158, 170, 236, 238, 242, 280, 346, 451, 487
Inapatua 236, 353
Inapertwa 236
Inar 236
Inaras 234, 236, 237
Inari 237, 482
Inari-m'yojim 237
Inca People 15, 62, 85, 117, 123, 132, 136, 138, 170, 197, 235, 239, 241, 253, 303, 304, 306, 344, 369, 373, 392, 404, 443, 449, 465, 485, 497, 498
incantations 100, 108
incense 107, 149, 489
incest 177
Incubi 237, 441
Incubus 159, 237
Ind 209
Inda 237, 238
Indech 155
Indestructible Existence 410
India 7, 9, 15, 17, 23, 24, 25, 26, 27, 28, 30, 31, 32, 33, 34, 41, 42, 45, 46, 47, 48, 50, 52, 53, 55, 56, 59, 61, 63, 64, 65, 69, 70, 71, 73, 74, 75, 76, 77, 81, 82, 83, 84, 85, 88, 89, 90, 91, 92, 93, 97, 98, 99, 100, 101, 102, 103, 104, 105, 113, 115, 120, 121, 123, 124, 126, 128, 129, 135, 138, 140, 141, 143, 144, 147, 148, 149, 152, 153, 154, 156, 157, 158, 159, 160, 164, 185, 186, 187, 188, 189, 190, 192, 194, 195, 196, 198, 201, 202, 203, 204, 205, 208, 217, 219, 222, 223, 224, 227, 230, 232, 234, 237, 238, 240, 241, 243, 248, 249, 250, 251, 253, 254, 255, 256, 257, 258, 259, 262, 263, 264, 267, 268, 271, 272, 273, 274, 275, 276, 278, 279, 280, 281, 282, 284, 285, 288, 290, 291, 293, 294, 295, 298, 299, 300, 301, 302, 303, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 317, 319, 320, 324, 325, 327, 329, 330, 331, 332, 334, 335, 336, 337, 338, 339, 341, 344, 345, 349, 363, 366, 369, 371, 372, 373, 374, 375, 381, 384, 385, 388, 389, 390, 392, 393, 396, 397, 398, 399, 400, 401, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 415, 416, 420, 421, 422, 424, 427, 429, 430, 431, 433, 434, 435, 436, 437, 439, 441, 442, 443, 444, 447, 448, 450, 451, 452, 453, 454, 465, 467, 471, 473, 474, 475, 478, 479, 481, 483, 484, 486, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 499, 500, 502, 504, 506, 510, 512, 513, 514, 516, 517, 519, 523, 524
Indochina 251, 298
Indo-European 387, 472
Indo-Iranian 60, 203, 204, 494, 501, 516
Indonesia 89, 99, 159, 492
Indra 15, 25, 27, 28, 30, 41, 48, 52, 55, 63, 69, 73, 77, 91, 121, 126, 135, 138, 139, 140, 147, 149, 152, 154, 160, 185, 188, 203, 205, 211, 219, 223, 237, 238, 254, 258, 259, 263, 275, 280, 281, 293, 299, 310, 311, 312, 319, 325, 332, 372, 374, 380, 388, 389, 390, 399, 401, 403, 409, 410, 415, 434, 435, 436, 443, 444, 447, 449, 464, 465, 466, 474, 479, 480, 484, 487, 488, 490, 492, 493, 494, 495, 498, 502, 512
Indradyumna 247, 248
Indrajala 238
Indrajit 401
Indra-nag 237, 238
Indranee 238
Indrani 237, 238, 258, 285, 373, 404, 437
Indraprastha 238
Indu 436
Indus River 187
Infatuation 79
infirmities 77
Ingi 160
Ingun 181
Ingunnar-Frey 181
Ingvi-Frey 181
Ini-Herit 238
Ininguru 238
Ininni 75
Inisfail 119
Inle 362
Inlil 63
Inmar 234
Innini 49, 158, 238, 242, 346, 347, 348
innocence 90
Innua 472
Ino 24, 79, 83, 112, 234, 238, 239, 288, 290, 312, 316, 317, 342, 383, 419, 462
Inoaeman 291, 296
insanity 15, 129
insects 98
inspiration 330, 416, 436
Instructor 123
intelligence 22, 82, 118, 168, 308, 332, 357
intestines 48
Inti 239, 304, 306, 369
intoxication 10, 300; *see also* alcohol; drunkenness
Intu 239
Inua 239, 472
Inuat 239, 307, 472
Inue 239
Inuit 434, 472; *see also* Eskimo People
invincibility 320
Invisible Supreme God 227
Invoker 25, 223
Io 17, 19, 42, 62, 64, 67, 152, 169, 236, 239, 291, 316, 383, 457, 523
Iobates 47, 56, 96, 125, 239, 241, 381, 390, 440
Iocaste 252
Iocauna 78, 197, 233, 239
Ioi 103, 239
Iokaste 252
Iokul 254
Iolaus 208, 213
Iolcos 249
Iolcus 10, 21, 35, 134, 287, 341, 377, 390, 439, 440, 480
Iole 58, 175, 213
Iolofath 362
Io-Mataaho 239
Io-Matua 239
Io-Matua-Te-Kora 239
Ion 11, 152, 211, 239, 510
Ionian Sea 114
Io-Nui 239
Iophossa 18, 121, 239
Iord 240
Iormungandr 53, 252, 333, 444
Ioskeha 167
Io-Taketake 239
Io-Te-Toi-O-Nga-Rangi 239
Io-Te-Wananga 239
Io-Te-Whiwhi 239
Iovialis 190
Iowahine 240, 452
Ipalnemoani 240, 460, 470
Ipalnemohuani 240, 470
Iphianassa 23, 35, 51, 128, 240, 390, 440
Iphicles 35, 118, 175
Iphiclus 35, 67, 383
Iphidamas 10, 56, 192, 461
Iphigeneia 23, 128, 240, 287, 463
Iphigenia 23, 113, 165, 240
Iphimedeia 37, 169, 220, 240, 368, 382, 474
Iphinoe 175, 219, 240, 315, 316, 390, 440
Iphis 175
Iphitus 58, 67, 175, 218, 240, 341
Iphthime 173, 379
Iphtimis 340
Ipila 240, 352
Iqi-Balam 197, 509
I'Qong 394
Ira 241, 342
Irad 113
Iraja 258
Iran 15, 28, 29, 30, 50, 85, 89, 204, 211, 223, 248, 259, 265, 268, 302, 311, 321, 332, 333, 413, 422, 438, 468, 469, 492, 493, 494, 517, 524
Iravat 69, 240
Ira-waru 313
Irdlirvirisissong 232
Ireland 14, 18, 22, 30, 45, 60, 65, 89, 91, 92, 96, 102, 103, 112, 114, 115, 117, 119, 129, 130, 134, 136, 142, 144, 148, 157, 161, 162, 166, 173, 176, 177, 179, 193, 195, 199, 245, 289, 290, 292, 296, 299, 305, 360, 374, 408, 424, 477
Irene 164, 240, 375
Irin Mage 240
Irinyes 171, 173
Iris 165, 171, 205, 240, 289, 356, 441, 522
Irkalia 211, 241
Irkalla 241
Ir-Kalla 241
Irkalla 64
Irkingu 309
Irlek-Khan 171
Irma 241
Irmen 241
Irmin 69, 208, 241
Irnini 242, 270
Irmin's Way 241
iron 6, 26, 105, 123, 182, 199, 360, 457
iron, age of 258
Iron Dirk 231
Iron Lady 343
Iron One 430
Iroquois People 15, 66,

www.ebook3000.com

78, 80, 81, 139, 140, 160, 164, 167, 183, 184, 185, 189, 200, 201, 207, 218, 222, 252, 266, 298, 360, 363, 365, 366, 454, 517, 518
Irra 241, 342, 414
irrigation 132, 168, 324, 348
Irsirra 241
Irus 13, 69, 174, 241
Isa 250
Isaac 250
Isakakate 241
Isakawuate 241
Isana 25, 26, 152, 241, 427
Isander 96, 145, 241
Isani 188
Ischys 112, 133, 241, 387
Ise 42, 482
Isfandiyar 520
Isfenarmad 438
Ishi-kori-dome 241
I-shi-ko-ri-do-me 241
Ishikoridome-no-Mikoto 40, 241
Ishim 53
Ishkhara 241
Ishkur 13, 168, 241
Ishmael 8, 243
Ishtar 8, 13, 27, 37, 51, 58, 59, 61, 65, 69, 73, 75, 77, 79, 80, 85, 94, 95, 96, 122, 123, 137, 152, 158, 167, 170, 191, 202, 233, 236, 241, 242, 243, 270, 271, 304, 334, 344, 346, 347, 392, 410, 419, 423, 424, 430, 432, 451, 453, 520, 521, 522, 523
Ishum 342
Isimud 236
Isir 451
Isirra 484
Isis 5, 14, 44, 49, 56, 58, 62, 70, 72, 73, 75, 81, 87, 146, 168, 181, 189, 204, 206, 210, 216, 222, 242, 257, 265, 319, 340, 341, 342, 343, 353, 367, 377, 394, 396, 402, 415, 420, 421, 425, 428, 433, 441, 449, 456, 460, 477, 481, 484
Isis Pharia 242, 243
Isis-Satis 415
Isis-Sothis 415, 438
Iskrychi 155
Iskrzychi 155
Iskur 13, 241
Islam 7, 8, 16, 36, 37, 84, 85, 89, 138, 143, 144, 148, 165, 201, 206, 207, 226, 228, 231, 234, 243, 248, 249, 251, 274, 288, 326, 408, 409, 419, 422, 432, 446, 520
Island of Flame 359
Island of the Blessed 243
Island of the Blest 241
Island of Truk 59, 291
Island of Yap 292
islands 154
Islands of the Blessed 135, 205
Isle of Anthemusa 433
Isle of Arran 305
Isle of Man 96, 112, 305, 321
Isles of the Blest 166
Isles of the West 142
Ismail 243, 520
Ismaroinen 234
Ismarus 174
Ismene 57, 173, 175, 231, 252
Ismenius 243, 292, 316
Ismenos 243
Ismenus 74, 243, 376
Isodaites 152, 243
Isoko 120
Isong 243
Israel 123, 139
Israfel 14, 53
Issa 62
Issac 8
Issitoq 243
Istar 73, 242
Istepahpah 243
Isthmian Games 370
Isthmus of Corinth 434
Istio 243
Iswara 188, 243, 427
Italapas 243
Italy 6, 21, 53, 116, 172, 176, 178, 218, 284, 319, 350, 457, 479, 490
Itchita 244
Ith 164
Ithaca 56, 284, 358, 370
Ithavoll 232
Ithun 232
I-ti 230, 476
Iti 244
Itoki 244, 302
Itom Ae 244
Itonus 104
Itsu-no-wo-ha-bari 43
Ity 244
Itylus 18, 244
Itys 18, 244, 459
Itzama 10
Itzam-kab-ain 28
Itzamna 94, 120, 227, 244, 501
Itzcoliuhqui 244
Itzcueye 244
Itzcuinan 509
Itzlacoliuhqui 460
Itzli 244, 295
Itzmatul 244
Itzpapalotl 129, 451, 471
Itztlacoliuhqui 244, 395
Itztli 244
Iubani 61
Iubau 61
Iuchar 129, 142
Iucharba 129
Iucharbar 142
Iulus 21, 72, 235, 244
Iuno 253
Iuppiter 253
Iusaas 81, 244
Iusaaset 244
Iusas 244
Iustitia 245, 254
Iuturna 245, 254
Iuwen 367
Ivald 159
Ivalde 435, 462
Ivaldi 245
Iving 245
Ivory Coast 101
Iwa 280
Iwa-naga-hime 245
Iwasu-hime-no-kami 246
Iwazaru 274
Iweridd 125, 245, 292
Ix 94, 245
Ix Tub Tun 245
Ixazalvoh 227, 245, 272
Ixbalanque 115, 198, 227, 228, 245
Ix-chel 245
Ixchel 94, 245
Ixcocauhqui 245
Ixcuin 245
Ixcuina 245
Ixcuiname 245, 470
Ixion 6, 57, 117, 133, 150, 229, 245, 297, 342, 343, 376, 379, 382, 434, 453
Ixmacane 245
Ixmucane 32, 102, 127, 245, 387
Ixpiyacoc 32, 127, 245, 387
Ixtab 246
Ixtaccihuatl 246
Ixtacihuatl 246
Ixtacmixcoatl 234, 246
Ixtlilton 246
Ixtliltou 460
Ixuin 226
Ixzaluoh 245
Iyatiku 246
Izamal 244
Izamna 244, 245
Izana-gi 246
Izanagi 39, 41, 43, 78, 182, 207, 220, 246, 247, 255, 259, 265, 280, 282, 355, 366, 413, 445, 450, 476, 518
Izana-mi 246
Izanami 41, 43, 78, 203, 207, 220, 246, 247, 255, 259, 261, 265, 278, 366, 426, 445, 476, 518
Izanami-no-kami 246
Izanazi 278
Izdubar 191
Izeds 325
Izona 244
Iztac Mixcoatl 325
Iztaccihuatl 121
Iztat Ix 34
Iztli 460
Iztli-Tezcatlipoca 460
Izumo 43, 281, 282, 361, 446, 450
Izunome-no-kami 247
Izushio-tome 206
Izuwo 41

Jaahannam 189, 247
Jabal 113, 247, 296
Jaburu 443
jackals 58, 60, 99, 268
Jacob 250
Jacy 214, 247
Jadapati 492
jade 121, 225
Jade Emperor 170, 278, 317, 384, 449, 467, 475, 478, 504, 505, 515, 519
Jade God 519
Jade Heaven 518
Jade Lady 519
Jade Mountain 412
Jafnhar 247, 357
Jagadgauri 247, 374
Jagadnatha 247
Jaganat 247
Jaganmata 188
Jaganmatri 148, 158, 247, 285
Jagannath 247, 400, 436, 498
Jagannatha 441
Jaggurnath 247
Jaguar God 459
Jah 248, 250
Jahannam 243, 248
Jahi 29, 53, 157, 189, 248
Jahim 243, 248
Jahve 250
Jahweh 250
Jain 121, 147, 148, 154, 285, 319, 332, 409, 430, 496, 498
Jaina pantheon 413
Jaina 511
Jainas 302
Jainism 454
Jains 301, 302, 341
Jaja 332
Jakis 248
Jaladhi-Ja 248, 285
Jala-Hastin 248
Jalandhara 77, 91
Jala-Shayin 498
Jala-Turaga 248
Jaldabaoth 250
Jalebha 248
Jalpati 248, 492
Jam 516
Jamadagni 373, 404, 500
Jambavan 248, 276, 415, 447
Jambavat 248
Jambavati 248, 276, 447
Jambha 248
Jambhala 248, 371
Jambudvipa 248, 319
Jam-dbyans-mag-gi-rgyal-po 307
Jam-pa-i-dbyans 70
Jam-pe-yang 70
Jam-pol 307
Jamshid 248, 516
Jamuna River 263
Jam-yang-nge-gi-gya-po 307
Jana 248, 249
Janaka 434
Jana-Loka 293
Janardana 275, 498
Janguli 249, 454
Janiscus 72, 229, 231, 299
Jann 146, 251
Janna 14
Jannatu el-Adn 243, 249
Jannatu el-Firdaus 243, 249
Jannatu el-Kh 249
Jannatu el-Khuld 243
Jannatu el-Ma'wa 243, 249
Jannatu el-Na'im 243, 249
Janus 55, 66, 115, 134, 239, 249, 370, 378
Janus Pater 249
Jao 250
Japan 11, 15, 23, 31, 32, 33, 39, 40, 41, 42, 43, 45, 47, 48, 61, 64, 78, 85, 94, 97, 102, 105, 125, 126, 132, 139, 140, 149, 150, 162, 166, 168, 182, 183, 184, 186, 189, 193, 195, 199, 200, 202, 203, 204, 206, 207, 208, 217, 220, 221, 223, 224, 226, 231, 232, 233, 234, 237, 241, 245, 246, 248, 250, 251, 252, 255, 256, 259, 260, 261, 262, 265, 266, 271, 272, 273, 274, 275, 276, 278, 280, 281, 282, 283, 300, 307, 310, 311, 320, 324, 325, 334, 337, 342, 345, 346, 347, 348, 350, 355, 360, 361, 363, 375, 396, 397, 400, 407, 408, 409, 411, 413, 414, 417, 418, 419, 420, 425, 426, 427, 428, 429, 436, 442, 445, 449, 450, 458, 464, 465, 472, 473, 476, 479, 481, 482, 488, 497, 503, 505, 510, 511, 512, 513, 514, 517, 518, 519, 524
Japara 392
Japhet 249, 525
Japheth 249
Jappan 249, 514
Jara 249
Jarah 173
Jaralez 69
Jaras 276
Jarasandha 157, 249, 275
Jara-Sandha 249, 433
Jari 160
Jarl 209, 329, 464
Jarnsaxa 209, 231, 463
Jarovit 214
Jar-Sub 249
Jashar 13
Jasius 138
Jason of Ioclus 314
Jason 10, 16, 18, 35, 64, 66, 67, 121, 123, 145, 171, 174, 230, 249, 315, 319, 339, 381, 383, 386, 390, 433, 462, 463, 468
Jassuju 9, 55, 250, 252, 295, 412, 442
Jatavedas 25
Jatayu 188, 250
Java 398, 412, 439
Javerzaharses 250
Jayadratha 100
Jayanat 247
Jealousy 521
Jeggua 250, 362
Jeh 248
Jehoshua 250
Jehova 510

Jehovah 36, 37, 146, 231, 250, 253, 408, 510
jellyfish 162, 220
Jemel 253
Jemshid 516, 524
Jen 234
Jerah 166, 173
Jerusalem 290, 327
Jeshu 250
Jeshua 250
Jesodha 514
Jesu 250
Jesus 18, 60, 232, 250, 251, 293, 327, 384, 395, 414
jewels 91, 97, 109, 264, 282, 400
Jhoting 250
Jhulanayatra 276
Jhvh 250, 510
JHVH 510
Jhwh 250, 510
Jibb-Jang-Sangne 250, 252, 429, 442
Jibril 36, 184, 327
Jiburili 184
Jicarilla Apache People 103, 200
Jigoku 166, 250, 363, 455, 518
Jig-rten-skyon 293
Jigs-Byed 99
jihad 327
Jikoku 251, 425, 427
Jikokuten 149, 251
Jikoku-Ten 251
Jimmu Tenno 39, 251, 473, 503
Jimmu Tennu 251
Jin 251, 422
Jina, the Victor 301, 302
Jingo, Empress 200
Jinimin 251
Jinn 146, 159, 231, 251, 523
Jinniyah 251
Jinniyeh 251
Jitoku 410
Jivaro Indian 136
Jizaiten 195
Jizo 78, 146, 251, 276
Jizo Bosatsu 277
Jizo-Bosatsu 251, 465
Jjord 181
Jjuko 252
jnana mudra 109
Joagh 252
Joca-Huva 78, 252
Jocakuvague 197
Jocasta 57, 173, 252, 318, 358, 359, 386
Jocaste 252
Jod 209
Jod-heh-vav-heh’ 250
Jodo 252, 279
Jodo 45
Jogaoh 252
John the Bapist 307
Joks 506
Joli-Torem 252
Jomali 253
Jonakr 224, 252
Jongsuli-Young-Jongbu 250, 252, 381, 429, 441
Joppa 52, 380
Jord Nerthus 252
Jord 22, 50, 82, 161, 180, 181, 220, 252, 351, 357, 463
Jordegumma 299
Jordh 252
Jormungandr 53, 198, 252, 321
Jormunrek 447
Jorojin 252, 426
Jorth 252
Joruri 511
Joseph 250
Jotun 252
Jotunheim 83, 94, 245, 252, 326, 486
Jotun-heim 97, 104, 252, 322, 516
Jotunnheim 252
Jotunnheim 72
Jotuns 183, 252, 463
Jou 199
Joukahainen 488
Jove 253, 449, 494, 522
joy 50, 78, 124, 174, 204, 206, 280, 363, 427, 436
Joyeuse 501
Jpd Ra 93
Jubal 296
Jubil 113
Juck 253, 354
Judaism 228
Judge of the Dead 367
Judge of the Two Opponent Gods 505
Judges 75
Judgment Day 53, 86
Judgment Hall 75, 300
judgments 95; register of 151
Jugalis 253
Juggernaut 247, 275
Jui 252
Juichimen 253, 277, 278
Ju-ichimen Kannon 261
Jui-k’ing fu-jen 122
Juji-Yama 182
Jukkui Ajayo 253
Juksakka 253, 299
Jukurokujin 183
Julian 235
Julius Caesar 235
Julunggl 253
Julunggul 196, 253, 397, 505
Jumala 33, 234, 253, 401, 482
Jumla 234, 253
Jumna 187, 253, 492, 513
Jumo 253
Jundei Kannon 261
Juno 80, 88, 151, 170, 177, 212, 253, 295, 310, 323, 415
Juno Caelestis 253, 453
Juno Lucina 253
Juno Moneta 253
Junun 251
Juok 253
Jupiter 20, 44, 80, 87, 88, 119, 151, 160, 253, 287, 309, 310, 318, 350, 358, 380, 382, 415, 454, 462, 464, 465, 468, 495, 522, 523
Jupiter Ammon 44, 87
Jupiter Elicius 253
Jupiter Feretrius 253
Jupiter-Ammon 43
Juppiter 253
Jurapari 254
Jurasmat 254
Jurgen 500
Jurojin 252
Ju-rojin 252
Jurupari 254
Jushkapariks 202
Justice 36, 50, 76, 151, 171, 180, 254, 255, 267, 273, 298, 300, 325, 332, 341, 353, 381, 389, 409, 423, 460, 461
Justitia 254
Juterna 254
Juturna 245, 254
Juventas 208, 253, 254
Jvalamukha 48
Jyaishtha 247
Jyeshtha 187
Jyotsna 254, 401

K 254
ka 4, 211, 319
Ka 86, 177, 254, 268, 270
Ka-Amentet 340
Kaang 112, 254
Kaare 254
Ka’ba 327
Kaba 254, 392
kaba karo 177
Kabandha 254
Kabeiroi 254
Kabibonokka 335
Kabil 113, 244
Kabiri 119
Kabirs 417, 448
Kabo Mandalat 255
Kaboi 255
Kabonian 255
Kaboniyan 255
Kabta 167, 255
Kabul 244
Kabun 320, 335
Kaches 250, 255
Kachinas 255
Kachpikh 255
Kadaklan 14, 255, 271
Kadesh 394
Kadi 255
Kadja Bossu 105
Kadomas 140
Kadru 187, 188, 255, 264, 305, 332, 421
Kaeha 264
Kaf 251
Kaffir 484
Kafir 235
Kafisi 179, 255, 264, 273
Kagami 40, 41, 241, 445
Kaggen 112
Kagoro 255, 265, 504
Kagu, Mount 247
Kagu-hana 250
Kaguhana 255
Kagura 41
Kagu-tsuchi 246, 247, 255, 261, 280, 355, 420, 450
Kagutsuchi 255, 280
Kagu-tsuchi no Kami 78
Kagu-Tsughi 255
Kagu-Zuchi 255
Kah 86
Kaha’i 217, 256, 262, 455
Kaharon 122
Kahaualea 261
Ka-Hemhem 254
Kahiki 377
Kahiki-honua-kele 259
Kahil 37, 422
Kahit 362
Kahmaraj 251
Kahmaraj Nara 146
Kahukura 256
Kai 256
Kaiaimunu 256
Kaikei 348
Kaikeyi 99, 203, 256, 398
Ka-iki-lani 294
Ka-iki-lani-ali’i-o-Puna 294
Kaikuzi 198
Kailasa 256, 282, 319, 427, 434
Kailasa, Mount 141, 185, 187
Kailua 264
Kaimai 256
Kain 113
Kai-n-Tiku-Aba 256
Ka’ioi 366
Kaitabha 158, 256, 257
Kaitangata 211, 256
Kai-Tangata 256
Kaizuki 256
Kaka-Guia 354
Kakasians 42
Kakea 217
Kakemono 256
Kakos 112
Kala 256, 512
Kala Bhairava 99
Kalacakra 256
Kalachi 512
Kalaino 205
Kalaipahoa 256
Kalais 256
Kalaka 141
Kalanemi 203, 256, 257, 261, 497
Kalapana 261
Kalaratri 159, 256
Kala-Shiva 256
Kalasi-Suta 24
Kalasi-Suti 256
Kala-Siva 256, 427
Kalayavana 249, 256, 275
Kalee 148
Ka-lei-pahoa 277
Kaleru 507
Kalevala 256
Kalewala 256
Kalfu 303
Kali 26, 99, 121, 140, 148, 158, 188, 257, 267, 279, 285, 375, 412, 427, 434, 454, 498
Kali of the Burning Ground 257
Kalia 257
Kali-Durga 148, 158, 313
Kalika 148, 257, 263
Kali-Ma 257
Kalinda-Kanya 513
Kalindi 257, 276, 444
Kalisto 113
Kaliya 256, 257, 261, 275, 276
Kaliyuga 159, 258
Kalki 258, 303, 498
Kalkin 258, 498
Kallin-kallin 511
Kalliope 113
Kalliste 70, 113
Kalma 258, 305
Kalmashapada 373, 422
Kalmyks 452
Kaloafu 258, 460, 478
Kalpa cycle 159, 258, 276, 308, 474
Kalpa tree 238, 258, 373, 404
Kalpas 430
Kalpathitha 258
Kalratri 491
Kalseru 397
Kalumba 258, 507
Kalunga 258
Kalunga-Ngombe 258
Kalura 258
Kama Deva 258
Kama 149, 172, 258, 259, 276, 285, 303, 374, 388, 389, 390, 400, 439, 453, 474, 487
Kamadeva 258
Kama-Dhenu 259
Kamadhenu 82, 259, 281, 373, 443, 493
Kamado-no-kami 237
Kamaheruka 215
Kamak 259
Kamakshi 148, 257
Kamala 285
Kamano 264
Kamapaua’a 377
Kamapua’a 259
Kamapuaa 259
Kamaunua-niho 259
Kama-Yama-Hiko 259, 420
Kama-yamato-iware-biko 251, 503
Kamba 266
Kambel 259
Kamchatka Peninsula 477
Kamdhain 259
Kamdhen 259
Kamdhenu 259
Kame 259
Kamehaikana 207, 259
Kameri 259
Kami 39, 40, 150, 162, 183, 259
Kami Romi 260
Kami-mi-musubi 260
Kami-Mimusubi 42, 260, 442, 449, 482
Kami-Musubi 361
Kami-musubi-mi-oya-no-mikoto 260
Kami-musubi-no-kami 260
Kaminabi 450

www.ebook3000.com

Kami-nari 337, 450
Kaminari Sama 397
Kami-rogi 39, 449
Kami-romi 39, 449
Kamit 259
Kammapa 260
Kammus 123
Kamohoali'i 260, 377
Kamo-hoalii 260
Kam-Pala 90
Kamrusepas 260, 458
Kamsa 261
Kamu-mimusbi 39
Kamu-mimusubi 39
Kamu-musubi 260
Kamus 123
Kamu-yamato-ihare-biko 251
Kana 260, 264
Kanaima 266, 303
Kanakamuni 308
Kanaloa 207, 261, 264, 277, 452
Kanati and Selu 261
Kana-yama-biko-no-kami 260, 261, 420
Kanayama-hime 247, 261, 420
Kana-yama-hime 261
Kandu 389
Kandy, Sri Lanka 408
Kane Hoalani 261
Kane Milohai 261
Kane 207, 216, 217, 261, 264, 277, 294, 452
Kaneapua 261, 284
Kane-Hekili 261
Kane-Kahili 261
Kangi 217, 223, 355
Kangyur 256
Kaniengehaga 454
Ka'nini 261
Kannon 261, 277
Kannon Bosatsu 261
Kannuck 261
Kanook 261
Kanro-o 45
Kansa 33, 77, 90, 147, 148, 157, 249, 256, 257, 261, 262, 275, 276, 412, 481, 514
Kanthaka 262
Kantoki-No-Ki 262
Kanwa 422
Kan-xib 28
Kanya-Kumari 279, 422
Kanzuras, Mount 279
Ka-onohi 254, 293
Ka-onohi-o-ka-la 254, 293
kapala 33, 141, 156, 304, 372
Kapala 262, 427
Kapalama 264
Kapila 255, 305, 409
Kapilavastu 313
Kapisha 262
Kapo 256
Kapohoikahiola 262
Kappa 262, 363, 458
Kapua 280
kar 203
Kara 431
Karala 158, 262, 374
Karali 158, 257
Karapans 53
Karau-anememti 61
Kardama 492
Karei 262
Kari 19, 180, 262, 517
Karia 196, 397
Karihi 262
Kariki 256, 262, 455, 456, 485, 503
Karisini 285
Karitay 262
Kariteimo 272
Karkotaka 333
Karl 23, 46, 262
Karlafberge 357
Karliki 155, 262
Karma 47
Karma Dakinis 141
Karma-Heruka 262
Karma-Krotishaurima 262
Karma-Sakshi 262, 444
Karna 100, 262, 263, 280, 397, 493
Karnak 44
Karna-Moti 257, 263
Karora 263
Karphophoros 212
Karpios 152
Karpo 222
Karsnik 276
Kartavirya 263, 373
Kartika 263
Kartikeya 263
Karttekeya 263
Karttikeya 26, 77, 148, 186, 187, 263, 374, 404, 406, 424, 435, 499
karttrika 304
Karu 115
karuga 40, 241
karunga 259
Karura-o 345
Karus 115
Kasa Sona 263
Kasandra 116
Kasena 505
Kasenko 221
Kashijotem 271
Kashiko-ne no Mikoto 39
Kashyapa 264
Kasi 99, 100
Kasin 350
Kastiatsi 263
Kastor and Polydeukes 116
Kasyapa 15, 26, 52, 71, 140, 141, 143, 153, 186, 187, 188, 255, 264, 267, 276, 305, 308, 310, 332, 388, 404, 409, 421, 442, 443, 491, 493, 497, 500
Kasyapa Marica 264
Kasyapu 219
Katchinas 277
Katcina Mana 267
Katcinas 264
Kathar 264, 274
Kathar the Clever 264, 274
Kathar-Wa-Hasis 274
Kathirat 264, 345, 514
Kathmandu 150, 491
Kathmandu Valley 491
Katkochila 264
Katonda 264
Katsinas 231, 264
Kattangata 256, 262, 455, 506
Katyayani 264
Kauai 481
Kaudi 134
Kauhausibware 264
Kaukabhta 73, 75
Kaukas 276
Kaukis 160, 264, 287, 393
Kaukomieli 28
Kaukomielli 289
Ka-ula-o-ke-ahi 377
Ka-ulu 217
Kaulu 264, 353
Kauravas 69, 90, 99, 100, 150, 159, 257, 263, 264, 276, 281, 301, 372, 453
Kausalya 398, 399
Kaushalya 264, 398
Kausiki 158, 374
Kaustubha 264, 281, 498
Kauveri 282
Kauyumari 265
Kava 177, 254, 265
kava 324
Kaveri River 46, 187
Kavis 53
Kawa-no-kami 265
Kawelo 265, 280
Kaya-no-hime-no-kami 246, 265, 278, 347, 355, 420
Kaya-no-mi-oya-no-kami 265
Kayanu-hime-no-kami 265
Kaya-nu-himi 265
Kayumarth 188, 189
Kazoba 255, 265, 504
K'daai Maqsin 265
Keagyihl Depguesk 200, 265
Keb 189, 394
Kebehsenuf 394
Kebehut 58, 265
Kebhsnauf 394
Keckamanetowa 265
Ked 265
Keelut 265
Kefi 265
Kefsir 209
Kegon 140
Kehkeh 4
Kei-Kung 265
Kek 265, 359
Keket 265, 352, 359
Kekhet 242
Kekri 265
Keku 265
Kekui 265, 352
Kekuit 265
Kekut 265
Kelaino 474
Ke-li'i-ku-honua 261
Kelpie 266
Kelpy 266
Kemataf 43
Kemosh 75, 123
Kenaima 266, 303
Kenat 458
Kendatsuba 345
Kenememti 61
Kenemti 75
Keneu 218, 266
Kengiu 266
K'eng-san-ku 266
Kenken-Wer 189, 266
Kenos 266
Kenss 261
Kentauros 117
Kentaurs 117
Kenya 34, 331, 354
Ke-ola-Ku-honua 261
Keoloewa 266
Ker 115, 266
Kerberos 119
kerchief 112
Kere Nyaa 266
Keremet 266
Keres 178, 266, 446
Keresaspa 53, 85, 185, 203, 259, 266, 439, 516
Keri 259
Keridwen 43, 83, 134, 267, 300
Kerimas 267
Kerlaug 101, 267
Kerlaung 267
Kerlogar 267
Ker-neter 4, 44
Kerres 119
Kerridwen 267
Kerub 124
Kerwan 267
Kesare 267
Kesari 53, 203, 267
Kesava 264, 267, 275, 498
Keshi 267
Keshin 263, 267
Keshvars 439, 501
Kesin 267
Kesini 267, 409, 496
Kessiepeia 116
Ket 265
Ketchimanetowa 265, 267
Ketq Skwaye 267
kettle 104
Kettu 267, 324
Ketu 416
Ketuiti 4
Ketuit-ten-ba 425
Keuakepo 267
kevalin 302
Kewawkgu 267
Kewawkqu 193
keys 153
Keyuri 267
Kha-a 267, 458
Khadau 267
Khadga Jogina 481
Khadga Jogini 257, 267
Khadga Yogini 257, 267
Khadhomas 140
Khadija 36, 326, 520
Khadja Jogina 267
Khadoma 156
Khadomas 140, 268
Khados 140, 268
Khahdoma 268
Khaibit 268
Khak-ab 61
Khakkara 277
Khalasa 200
Khaldi 29, 71, 268, 399, 424, 461
Khaldians 268
Khammurabi 202
Khandava forest 275
Khandro 413
Khandros 140
Khang Fei 177
Khan-ru 61
Khar 268
Khara 268, 279, 345, 429
Kharakhar 385
Kharchheri 268
Khasa 268, 398
Khashthra 270
Khasis 274
Khatra 458
Khatri 340
khatvanga 256
Khatwanga 268, 428
Khavah 13
Khaya 124
Khebieso 103, 268
Kheiron 123
Khem 317
Khema 23, 75
Khemenu 359
Khen-pa 268, 269
Khensu 3, 43, 268, 331, 352, 457, 483
Khensu-Nefer-Hetep 268
Khensu-Pa-Khart 268
Khensu-Ra 268
Khent Sehet 58
Khentamenti 268
Khentamentiu 268
Khenti Amenti 168, 268
Khenti-Amenti 4
Khenti-ast-f 458
Khenti-ment 458
Khentimentiu 268
Khenti-qerer 4
Khen-unnut-f 477
Khepan 459
Khepera 4, 269, 298, 340
Kheperi 4, 269
Khepert-kekui-khaat-mest 298
Khepi 4
Khepra 396
Kheprer 4, 269
Khepri 4, 5, 79, 81, 269, 416, 457
Kher-aha 4
Khermuti 61
Kherp-hu-khefti 425
Khersek-Shu 58
Khert Neter 269, 477
Khesef-haa-heseq-neha-hra 269
Khesef-hra 61
Khesef-hra-ash-kheru 477
Khesef-hra-khemiu 477
Khesfu 269, 458
Khetaka 90, 269
Kheti 269
Khi-Dimme-Azaga 269
Khnemiu 269
Khnem-renit 60
Khnemu 4, 44, 204, 269, 425
Khnoumis 269
Khnum 8, 55, 59, 165, 210, 254, 269, 341, 391, 415, 464
Khnumu 269
Kho 254

Khoda 269
Kho-Dumo-Dumo 269
Kholumolumo 269
Khond 92
Khon-ma 269
Khons 3, 268
Khons Hor 268
Khonsu 3, 268
Khonvum 269
Khoprer 269
Khordadh 207
Khoromozitel 155, 270
Khors 144, 270
Khosadam 270
Khoser-et-Hasis 103, 270
Khoton 270
Khotun 270
Khou 270
Khovaki 270
Khremaor 385
Khrestos 250
Khronos 135
Khshaeta 516
Khshasthra Vairya 45, 48, 138, 270, 416
Khshathrapati 422
Khu 86, 270
Khui 425
Khulater 270
Khumbaba 191, 242, 270
Khumban 270, 272
Khumbu-patas People 34
Khun 270, 279
Khun-Lun 279
Khuno 270
Khuns 268
Khuran-Nojon 270
Khurdad 48; and Amardad 207
Khurdadh 207
Khuri Edzhin 270
Khurri 459
Khusor 270
Khut 242
Khu-tchet-f 477
Khuzwane 270
Khvarenanh 266, 270, 464, 516
Khwanirath 439, 501
Khwarenah 270
Khy 254
Khyati 285
Ki 49, 71, 142, 168, 270, 271, 272, 334, 346, 347, 348, 466
Kian 129
Kianto 271
Kiara 314
Kibalso 271
Kibu 271
Kibuka 271, 423
Kibuuka 271
Kichigonai 271
Kichijo-Ten 97, 271
Kiehtan 271
Kien Niu 120, 126
Kien t’an 122
Kigal 211
Kigatilik 271
Kihe-Wahine 271
Kiho 83, 271
Kiho Tumu 271
Ki’i 467
Kikazaru 274
Kikimora 155, 271
Kikimoras 271
Kiku-jido 271, 420
Kikuya 343
Kikuyu 191, 266
Kilauea, Mount 377
Kildisin 234, 235, 271
Kili 160
Kilili 8, 242, 271
Kilimanjaro 407, 504
Killer Whale 199
Killing Mahisa 158
Kilyikhama 271
Kimat 255, 271
Kimbu-Sangtung 9, 271, 295, 412, 429
Kimi 40
Kimpen Jigoku 250
Kimpurushas 271, 282
Kin 183
Kinebahan 227
Kineun 266
Kingmingoarkulluk 271
Kings of Hell 151, 277, 439, 443, 466, 507
Kingu 63, 96, 161, 272, 309, 448, 466
Kingugu 272
Kinharigan 272
Kinich Ahau 183, 272
Kinich-ahau 244
Kinilau 468
Kinish-kakimo 244, 272
Kinkini-Dhari 55, 272, 467
Kinko Sennin 420
Kin-k’ue Yu-chen T’ien-tsun 519
Kinli’zin 471
Kinma 309
Kinnara-o 345
Kinnaras 272, 282
Kintu 198, 256, 272, 343
Kipu-Tytto 272, 273, 295, 305, 491
Kirata 69
Kiri-Bi fire 255
Kiririsha 270, 272
Kirke 129
Kirnis 272, 288
Kiron 123
Kisani 81, 206
Kish 278, 520
Kish Dynasty 173
Kishar 55, 58, 59, 63, 233, 255, 270, 272, 284, 285, 352
Kishibojin 204, 272
Kishijoten 102, 285
Kishimojin 146, 272
Kishimo-jin 272
kishru 58
Kisin 350, 486
Kissare 55, 97, 272
Kistna 275
Kitchaka 100
Kitchen deities 237, 361, 475
Kitcki Manitou 192, 272
kites 342
Kitimil 272
Kitshi Manito 192, 272, 325, 504
Kitshi 192
Kitsune 237
Kittu 85, 267, 273
Kittum 423
Kiun 402
Kivuatar 295
Kivutar 273, 305, 491
Kiyamat-saus 273
Kiyamat-Tora 273
Kkhrafstras 273
Kla 273
Klamath 362
Klehanoai 273, 518
Klotho 130
Klur 209
K’mukamtch 362
Knaritja 273
Kneph 8, 269
Knephis 269
Knepth 269
knives 12, 98, 177
Knossos 152
knots 350
Knower 25
knowledge 102, 109, 139, 185, 214, 233, 278, 296, 322, 366, 370, 389, 436, 487, 488, 494, 496
Kobine 337
Kobolds 255, 273, 446
Ko-dama 265
Kodoku-jigoku 250
Koevasi 273
Kohin 89
Koin 89
Kojiki 255, 260, 280, 464, 482
Kojiki 39, 40
Kojin 273
Kojin-Sama 273
Kokko 273
Kokuzo 273
Kokuzo-Bosatsu 32, 273
Kokytus 131
Kolga 359
Koli 513
Koloowisi 273, 371
Kolpia 30, 88, 122, 273
Kombu 273
Komi 518
Komoku 273, 425, 427
Komoku-ten 273, 345, 497
Komorkis 273
Kompira 282
Kompira-Daigongen 282
Kompira-O 345
Kon 209, 241
Konda-o 345
Kondo 42
Kondoy 121
Kongara-Doji 182
Kongo Rikishi 425
Kongo-Yasha-Myoo 193, 273
Konjo 454
Konkara 182
Konohana-chiru-hime 282, 510
Kono-Hana-Sakuya-Hime 217, 221, 223, 265, 347, 355, 420, 473
Ko-no-hana-sakuya-hime 245, 265
Kono-hana-sakuya-hime 419
Kononatoo 471
Konshiki-kujaku 345
Koo-chul-inn 135
Koodjidnuk 274
Kootamoinen 274, 279
Koppa-Tengu 274, 458
Koramas 99, 148, 309
Koran 14, 37, 53, 71, 113, 176, 274, 327
Kore 146, 274, 379
Korea 138, 201, 266
Kore-Persephone 146
Kore-Te-Whiwhia 239
Korka-kuzo 159
Korka-murt 159
Korobona 274, 304
Korraval 274, 431
Korriganes 274
Korubantes 136, 457
Korupira 136
Korwa 99
Korybantes 133, 136
Koshairis 231, 446
Koshchei 274
Koshi 274, 282, 445
Koshin 274
Koshin-Sama 274
Kotan-Shorai 445
Kotari 148
Kothar and Khasis 274
Kothar-u-Khasis 86, 274, 511
Koti 275
Koto-Shiro-Nushi 275, 361, 450
Kotoshironushi-No-Mikoto 162
Kottavei 257, 275
Kottos 133
Kou-hun-shih-che 507
Koundye 331
Koura-Abi 256
Kouretes 136, 457
Kourotrophos 212
Kox 133
Kozoba 275
Krachi 507
Krakuchanda 308
Krakuchandra 308
Kratos 275, 370
Kravyad 26
Kreggi 209
Kremara 281
Kresnik 276
Kricco 275
Krimen 214
Krimhild 197
Kripa 156, 159, 275
Krishna 15, 69, 91, 98, 123, 157, 194, 204, 213, 247, 248, 249, 253, 257, 258, 259, 261, 262, 275, 276, 285, 314, 336, 371, 372, 373, 374, 388, 396, 400, 407, 413, 415, 427, 433, 436, 441, 447, 498, 499, 502, 510, 514
Krishna Dwaipayana 502
Krishna-Janmashtami 276
Kristna 275
Krita 159, 258, 276, 412
Kritanta 512
Kritayuga 276
Krittika 42, 71, 128, 158, 263, 300, 349, 404, 492
Krittivasas 257
K’ro-bo-mi-gyo-ba 9
Krodha 101, 141, 276, 427
Kronos 135
Krsanu 276, 436
Krsna 275
Krsnik 276
Krukis 276
Kruth 187
Ksama 285
Kshatriyas 83, 146, 301, 373, 474
Kshiti-Apsarases 63
Kshitigarbha 32, 33, 150, 251, 276, 277, 301, 410, 465, 512, 515
Kshiti-garbha 276
Ksitgarbha 276
Ktesios 277, 522
Ku 216, 218, 260, 261, 294, 377, 452, 476; and Hina 277
Kua 352
Kua Tsi-i 277
Kuai 277
Kuan Jung 277
Kuan P’ing 277
Kuan Yin 84, 261, 277, 278, 383, 384, 454
Kuan Yu 277
Kuang Mu 326, 439
Kuang-jun 156
Kuang-li 156
Kuang-she 156
Kuang-te 156
Kuan-Ti 225, 277, 428
Kuan-yin 277, 345, 442, 448
Kubaba 278
Kubai-khotun 270
Kubebe 152
Kubele 136
Kubera 149, 282, 293
Kubira 146, 282
Kuchime 217
K’u-ch’u K’iao 277, 318
Kudai 45, 278
Kudai Bai-ulgon 89
Kudai-Bakshy 265
Kudnu 101
K’uei Hsing 126, 128
Kuei Shen 439
K’uei-Hsing 278, 505
Kuei-Hui 278
Kuei-Sing 278
K’uei-Sing 278, 505
K’ue-sing 128
Kueph 269
Kuetzal-Koatl 395
Kuhu 278
kuhuna 165
Kui 278
Kuilioloa 264
Kujaku-Myoo 193, 278
Kujum-Chantu 278
Kujum-Popi 278
Ku-kaili-moku 277
Kukalikimoku 277
Ku-Kali-Moku 277
Ku-kama-ulu-nui-akea 264
Ku-ka-ohia-laka 217, 264, 277
Ku-Kau-Akahi 277

www.ebook3000.com

Kuko-no-shi 355
Kukpi 350
Kuksu 278, 311, 397
Kukulcan 278, 395, 501, 520
Ku-ku-no-chi 200
Kukunochi-no-kami 278
Kuku-no-shi 265, 278
Ku-ku-no-shi 278
Kul 278, 279
Kulimina 281
Kulitta 346
Kulla 58, 161, 279
Kulmu 279
Kul-Uasa 278
Kumano-kusubi-no-mikoto 41
Kumara 186, 263
Kumarbi 49, 459
Kumarbis 241, 279, 483
Kumari 148, 257, 279
Ku-mauna 277
Kumba 209
Kumbari 279
Kumbaris 34, 58, 59, 467, 483
Kumbhakara 279
Kumbhakarna 279, 282, 345, 401, 429, 496, 499
Kumbhandas 146, 149, 497
Kummiya 279, 483
Ku-moku-hali‘i 277
Kumuda 152, 293
Kumudavati 282
Kumu-honua 261
Kumush 279
Kun 124, 274, 279
K’un Lun Mountain 519
Kunapipi 504, 505
Kunapapi Langal 397
Kund 209
Kundalini 140, 279
Kundapura 301
Kundrav 185, 266
Kung Kung 280
Kuni 260
Kuni no sa-tsuchi no Mikoto 39
Kuni-toko-tachi no mikoto 39
Kuni-Tsu-Kami 39, 40, 260, 280, 449
Kun-lu 252
K’un-Lun 279
Kun-Lun 225
Kun-Lun Mountain 126, 279, 512
Kunmanggur 196, 350, 397
Kun-Rig 488
Kunti 69, 99, 185, 263, 278, 280, 372, 397, 444, 519
Kuntu-bzang-mo 280, 411, 422
Ku-nui-akea 277
Kuo Shang 280
Ku-olono-wao 277
Kupala 280, 514
Kupua 260, 280, 313, 364
Kupua-Huluena 280
Kur 280, 348
Kura-mitsu-ha 246, 280, 450
Kuramitsuha-no-kami 247
Kurangara 281
Kura-okami 246, 255, 280, 450
Kura-yama-tsumi 246, 255, 280, 281, 450
Kurbantes 133
Kurgal 13
Kur-Gal 13
Kurke 281
Kurma 281, 399, 498
Kuru 281, 453
Kuruksetra 257
Kurukshetra 100, 281
Kurukulla 281, 454
Kurumba 155
Kuru-okami 280
Kururumany 281
Kurus 264
Kurwaichin 281
Kusanagi 43, 281, 282, 445
Kusha 282, 434
Kushamba 282
Kushana 355
Kushinada-Hime 282
Kushi-nada-hime 282, 360, 361, 445, 458, 510
Kusht 491
Kusor 282
Kusor-Hasisu 282
Kusug 161
kuth nhail 283
kuth piny 283
Kuth 283
Kutjara 505
Kuu 282
Kuula 277, 282
Ku-ula-kai 29, 277
Kuutar 282
Kuvalayapida 275, 282
Kuvanna 282, 392, 511
Kuvera 7, 146, 152, 198, 204, 232, 234, 248, 256, 271, 272, 282, 283, 371, 399, 401, 450, 496, 499, 511
Kuverva 293
Ku-waha-ilo 277, 293
Kuwarishiki no Amida 46
Kuya 45, 251
Ku-yu 117
Kvaser 283
Kvasir 94, 104, 220, 283, 358, 437
Kvergjelme 229
Kwakiutl 15, 261, 470, 475, 515
Kwammang-a 283
Kwangiden 283
Kwangiten 283
Kwannon 277
Kwan-she-yin 277
Kwan-Yin 277, 454, 487
Kweku 354
Kwetzal-Koatl 395
Kwoth 283
Kyala 283
Kybele 89, 136
Kyklopes 137
Ky-klopes 137
Kyklops 137
Kyoto 237
Kypris 61
Kyrene 283
Kyrgys-Khan 89, 283

L 283
La’a Maomao 284
Labartu 284, 285
Labasi 285
Labasu 28, 146
Labdacus 284
Labosum 284
Labrador 472
Labyrinth 9, 68, 138, 284, 323
Lacedaemon 12, 174, 195, 284, 456
Lachama 284; and Lachmu 284
Lache 272, 284
Lachesis 81, 130, 177, 284, 327
Lachmu 284
Lachos 272
Laconians 70
Lada 284
ladle 26, 148, 266
Lado 284
Ladon 119, 162, 176, 194, 195, 216, 284, 315, 383, 405, 461
Ladru 119
Lady Abundant Jewel 473
Lady Builder 421
Lady Godiva 169
Lady Meng 277, 284, 318
Lady Ming 284, 318
Lady Mother 32
Lady of Desolation 190
Lady of Earth 142
Lady of Heaven 51
Lady of Kazailu 310
Lady of Ninab 310
Lady of Rock-Perpetuity 245
Lady of the Bed 128
Lady of the Islands 242, 521
Lady of the Lake 500
Lady of the Night 320, 456, 518
Lady of the Vine 190
Lady of Wild Things 70
Lady of Witches 470
Lady Ts’ao 266
Lady Ts’i 266
Lady Wang 504
Lady-of-the-Ocean-Waves 217
Lady-Who-Descends-the-Rapids 417
Lady-who-makes-the-trees-bloom 265
Laeapua 284
Laeding 156, 178, 192, 284
Laerad 288, 516
Laertes 56, 67, 284, 358, 433
Laga 408
Lagamal 284
Lagash 184, 336, 484
Lahamu 63, 272, 309; and Lahmu 284
Lahar 73, 161, 167, 168, 284
Lahmu 63, 272, 284
Laima 254, 284
Laios 284
Laius 252, 284, 358
Lajnan 404
Laka 217, 284, 285, 294, 400
Lakchos 88
Lake Amsvartnir 297
lake goddess 132, 500
Lake Iguaque 88
Lake Kasu 524
Lake Kubera 100
Lake Llyon Llion 14
Lake Nagavasa 307
Lake Titicaca 132, 304, 497
Lake Xynias 67
Lakemba 295, 324
lakes 70, 114, 195, 266, 328, 329, 344, 362
Lakhame 55
Lakhamu 63, 285; and Lakhmu 284
Lakhe 97
Lakhmu 63, 284, 285
Lakhumu 55
Lakhus 97
Lakshmana 24, 99, 263, 285, 398, 424, 434
Lakshmi 26, 52, 70, 102, 238, 258, 276, 281, 285, 288, 396, 413, 422, 433, 434, 437, 439, 474, 478, 488, 491, 492, 493, 498
Lakshmindra 305
Lakshmi-Vrata 285
Laksmi 275, 285, 299
Lala 151, 285
lalita asana 400
lalitasana 372
Lalo-honua 261
Lamaism 140, 141, 215, 276, 308, 454
Lamashtu 28, 51, 285, 291
Lamassu 9, 285, 418
Lamastu 285
Lambakarna 186
lambs 107, 281
Lamech 113, 296
Lamehamor 385
lamentation 107
Lamga 133, 483
Lamhfhada 296
Lamia 38, 174, 286, 291, 417
Lamiae 166, 286
Lamma 286
Lamme 285
Lammea 285
lamps 489
Lampethus 20, 286
Lampetie 20, 286
Lampon 210
Lampus 169, 215, 286
Lamus 35, 286, 363
Lan Ts’ai-ho 163
Lanai 284, 369
Lancer 206
land gods 242, 249, 324
Land of Bliss 45
Land of Darkness 518
Land of Gloom 518
Land of Heroes 256
Land of Roots 342, 518
Land of the Big Women 150
Land of the Blessed 378
Land of the Dead 220, 271, 512
Land of the Setting Sun 44
Land of the Shades 58
Land of the Sun 443
land spirit 271
Land-bearer 251
Landvidi 496
Langal 196
Langali 90
Lanka 203, 282, 398, 401, 499
Lan-ts’ai-ho 286
Lan-Ts’ai-Ho 68
Lao Tzu 286, 412, 519
Laocoon 10, 38, 56
Laocoon 114, 175, 286, 359, 461, 462
Laodamas 10, 56, 64
Laodamas 173, 192, 286, 461
Laodameia (A) 286
Laodameia (B) 287
Laodameia 10, 76
Laodameia 96, 145, 176, 241, 414, 439, 440, 523
Laodice (A) 287
Laodice (B) 287
Laodice (C) 287
Laodice 146, 165, 330, 378, 383, 393, 441
Laodice 23
Laodocus 156
Laodocus 62
Laogore 129
Lao-Jen 428
Laomedon 129, 175, 215, 216, 235, 286, 287, 388, 462, 469
Laomedon 57, 76
Laothoe 386
Lao-tien-heh 519
Lao-tien-yeh 519
Lao-Tzu 286
Lao-tzu 466
Laphystios 152
Lapith 57, 67
Lapithae 245, 287
Lapiths 19, 112, 133, 218, 287, 342
Lapithú 19
Lapithus 62, 382
Lapland 257, 295
Lapp 32, 112, 222, 253, 299, 321, 409, 482
Lar 287, 378
Lara 287
Larentalia 10
Lares 138, 155, 287
Larissa 142, 377, 460
Lars 287
Larsa 88, 423
Larvae 287, 289
Lasema 287, 304
lash 96
Lasthenes 17, 287, 387
Lasya 33, 287
Lat 37, 289
Latarak 236

Latin 116, 195, 213, 216, 295, 358, 370
Latinius 457
Latinus 12, 130, 177
Latium 384, 415
Latmikaik 287, 473
Latona 62, 151, 287, 289, 382, 419
Latpon 164
latrine 506
Latvia 119, 144, 145, 254, 284, 287, 320, 328, 495
Laufey 177, 287, 294
laughter 224
Lau-ka-ieie 217
Laukamat 254, 287
Laukosargas 287
Laume 287
Lau-mihi 207
laurel tree 62, 143
laurel wreaths 143
Laurin 52
Lausus 287, 288
Lava 282, 434
Lavangi 63
Laverna 288
Lavina 479
Lavinia 21
law 50, 174, 177, 201, 461, 480, 497
lawgivers 34, 103
Lawkapatim 144, 287, 288
Laxmi 285, 288
Laza 243, 288
lead 96
Leader of Armies 66
Leander 214
Leaneira 152
Learchus 79, 239, 288
learning 105, 107, 208, 235, 307, 427, 467, 489, 490, 492, 499, 505, 513
leaves 200
Lebanon 86
Lebanons 270
Lebe 288
Leda 38, 116, 288, 341, 381, 386, 480, 523
Leding 284
Ledrad 288, 516
Leech 151
Legba 172, 176, 288
Leho-ula 277
Lei Tsu 519
Lei-Kung 288, 467, 519, 520
Leinster 18
Leipt 165
Leiriope 118, 289, 337
Leische 289
Lelantos 82
Lelegian of Samos 67
Lelex 25, 96, 289, 291
Lemminikainen 28, 235, 289
Lemminkainen 234, 297, 488
Lemnos 97, 157, 174, 212, 230, 249, 365, 432
lemon 248
Lempo 216
Lemures 287, 289
Lenaeus 152, 289
Lenaios 152
Leodegrance 289
Leodocus 289, 379
Leonteus 133, 387
leopard 17
Leophontes 95
leprechauns 130, 142, 289
Ler 18, 60, 292
Lerad 209, 289, 516
Lernae 213
Lernaean hydra 213
Lernus 212, 289
Lesbos 170, 354
Leshacikha 289
Leshies 289, 386
Leshonki 289
Lesiy 289
Lesiye 289
Lesovik 289
Lesser deities 211
Lesser Enneads 168
Lethe 11, 131, 289, 382, 455
Leto 21, 62, 70, 75, 118, 287, 289, 290, 349, 364, 382, 469, 523
letters 244
Lettuce 323
Leucippe 35, 113, 218, 286, 290, 324, 462
Leucippus 105, 143, 176, 194, 218, 290, 359
Leucon 79, 462
Leucopeus 114, 359, 440
Leucosia 11
Leucosia 290, 433
Leucothea 238, 239, 290, 312, 506
Leucothoe 131, 211, 290
Leveller 512
Level-Rice-Field-of-Heaven 41
Leviathan 14, 290
Leyahogan 471
Leza 288, 290, 292, 314, 330, 334
Lha Mo 290
Lha-mo 141
Lhamo 290
Li 466
Li Hun 290
Li Theh-kuai 163
Li T'ieh-kuai 466
Li with the Iron Crutch 466
Lia Fail 290
Liaksit 290
Libanja 33
Libanza 290
Liber 24, 88, 119, 152, 290, 291
Libera 119, 290, 291
Liberator of Men 275
Libertas 291
liberty 291
Libitina 291
Libya 9, 24, 43, 44, 56, 69, 96, 113, 137, 142, 283, 286, 289, 291, 297, 317, 323, 328, 341, 382, 417, 419, 428
licentiousness 118
Licymnius 316
Lidskialf 220
Lidskjalf 220
Lidskjalv 72
Lie-kung 265
Lif 291, 397
life 24, 55, 79, 81, 99, 139, 190, 192, 242, 253, 258, 291, 449, 524
Life-giver 416
Lifthrasir 291, 397
Ligeia 11, 291, 433
light 31, 51, 53, 60, 62, 70, 79, 107, 110, 111, 135, 148, 158, 179, 190, 257, 270, 289, 295, 321, 353, 374, 381, 384, 431, 458, 483, 488
Light Bearer 160, 486
Light Giver 242
Lightmaker 153
lightning 14, 25, 26, 31, 60, 62, 71, 87, 103, 117, 183, 200, 226, 229, 245, 256, 262, 268, 273, 290, 308, 309, 379, 404, 423, 440, 449, 455, 463, 467, 474, 478, 483, 496, 506
Lightning Bird 316
Lightning Man 304, 334
Ligoapup 291, 296
Ligobund 291
Ligoububfanu 59, 291
Likho 291
Liki 444
Liknites 152
Lil 168, 346
lilac-bushes 393
Lilavati 148, 291
Lilim 166
Lilis 291
Lilith 14, 28, 38, 148, 166, 285, 291, 415
Lilithu 291
Lilitu 146, 291
Lilli 291
Lillity 291
Lilu 28, 146, 291
lily 73, 229
Limenia 61
Limerick fairies 112
Limnades 291
Limnads 333
linden tree 94, 381
linen 449
Ling Hsu 125
lingam 43, 65, 100, 280
Ling-Pao 292
Ling-Pao T'ien-Tsun 291, 412, 519
Linos 182
Linus 62, 113, 243, 292, 484
Li'oa 32
Liod 430, 501
Liomarar 292, 295
lions 16, 20, 43, 46, 48, 72, 73, 93, 111, 125, 158, 184, 197, 292, 307, 316, 336
Lios Alfar 166
Liosalfar 36
Lipara 21
Liparus 21
Lipaurus 292
liquor *see* alcohol Lir 292
Lir 292
Lirufu 362
Lisa 24, 142, 195, 199, 290, 292, 302, 508
Lissa 292
Lit 160
Litai 79
literature 24, 128, 277, 505
Lithuania 31, 74, 83, 154, 234, 276, 287, 316, 379, 389, 393, 457, 521, 524, 525
Little Ancaeus 67
Little Bear 524
Little Black One 246
Little Boy of the Clouds 520
Little Bride 75
Little Coyote 129
Little Jupiter 253, 495
Little Rong 38, 371
Little Star 75
Lituolene 260
Liu Meng-tsaing-kun 369
Liu Pei 277, 292
Liu T'ai-wei 369
Liu-Hai 292
liver 48
Living God 239
Living Goddess 279
Livyathan 290
Lizard House 244
lizards 6, 53, 60, 93, 101, 176, 271
Ljod 53, 198
Ljosalfaheim 36
Llampallec 339
Llapchilulli 339
Llaw Erent 292
Llaw Gyffes 292
Llawerein 292
Llediaith 292
Lleu 292
Lleu Llaw Gyffes 292, 296
Llew 68, 103, 160, 199, 292
Llew Llaw 153
Llew Llaw Gyffes 292
Llud 40, 134, 292, 352
Llud Llaw 292
Llud Llaw Ereint 352
Lludd 199
Llwch Llawwynnawc 296
Llyr 134, 245, 292, 306
Llyr Marini 292
Lmahuika 292, 295
Lmylitta 292
Lnyiko 293
Lo Ching Hsin 412, 518, 519
Loa 293
Lob-sang-chho-chi-gyal-tshen 46
Locana 33, 150, 293, 303
Loch Gur 30
Locha 292, 295, 324
Locrian 67
Locris 31, 171, 360
locusts 369
Loder 294
Lodur 211, 294
Lofn 293
Lofty of Plumes 373
Loge 293
Logh 22
Logi 293
Logos 21, 250, 293, 351, 413
Loha-Mukha 293
Lohiau 277, 377
Loka 293
Lokamatri 188
Lokanatha 410
Lokapalas 146, 149, 293, 497, 498
Lokatsosakad 471
Loke 294
Lokeswar 293
Lokeswara 84, 293
Loki 19, 22, 52, 53, 90, 164, 177, 178, 179, 180, 181, 198, 199, 210, 211, 221, 233, 287, 293, 294, 321, 333, 337, 343, 368, 397, 406, 415, 430, 431, 432, 435, 446, 462, 463, 486, 490, 497, 517
Lokk 490
Lokkju 294
Lola 294
Lo-lupe 293
Lombodara 186
London 193, 306
Lone Man 307
Long Wave and Short Wave 65
longevity 45, 183, 233, 286, 412, 428
Longo Rongo-Ma-Tane 294
Longolap 38
Longorik 38, 436
Loni 160
Lonkhar 385
Lono 216, 261, 277, 284, 294, 364, 377, 405, 452
Lono Rongo-Ma-Tane 405
Lono-ka-eho 264
Lono-makua 294
Lopamudra 24
Lopemat 254
Lopter 294
Lopti 294
Loran 329
Lorop 292, 295, 329
Lorride 430, 463, 465
Lorridi 463
Lotan 290
Lother 130
Lothia 292, 295, 324
Lothurr 295, 463
Lotis 390
lotus 31, 46, 63, 77, 84, 100, 105, 106, 109, 150, 186, 193, 199, 203, 221, 259, 268, 273, 278, 285, 294, 301, 304, 307, 313, 319, 322, 324, 327, 340, 369, 372, 389, 390, 396, 409, 410, 411, 413, 414, 418, 442, 454, 486, 489, 499
Loucetius 131, 477
Louhi 295, 385, 488
Louquo 295
love 30, 31, 50, 54, 56, 61, 71, 75, 95, 97, 110, 122, 151, 160, 171, 178, 181, 206, 236, 242, 259, 275,

www.ebook3000.com

285, 293, 303, 307, 318, 370, 394, 419, 470, 474, 479, 490, 493, 495, 498, 499, 500, 503, 509, 514
Lovedu 270
Loviatar 273, 295, 305, 491
Lowa 295, 452
Lower Congo 354
Loxias 62
Loyalty Island 324
Loyalty Islands 295
Loz 295
Lu Ch'i 128
Lu Pan 295
Lu Tsu 295
Lu Tung-pin 163, 202, 221, 369
Lu Tung-Pin 202, 295
Lu Tung-pin 68
Lu Yen 295
Lu 295
Luba 258
Lubrican 289
Lubukanlung 9
Lubukhanlung 295, 412, 429
Lubumba 290
Luchta 134
Luchtaine 134, 193
Lucifer 148, 295
Lucina 163, 165, 253, 295
luck 97, 98, 102, 150, 164, 180, 183, 190, 271, 285, 318, 378, 427, 521
Lud 292, 352
Ludd 155, 292
Ludgate Hill 292
Ludjatako 295
Lufu 362
Lug 144, 296
Lug Lonnbemnech 296
Lug Samildanach 296
Lugalabdubur 309
Lugalbanda 191, 295, 347, 524
Lugal-Banda 295, 296
Lugaldimmerankia 309
Lugaldurmah 309
Lugallanna 309
Lugalmeslam 296, 342
Lugalugga 309
Luganda 264, 324, 326
Lugas 296
Lugash 346
Lugeilan 296
Lugh 60, 91, 112, 129, 135, 144, 151, 296, 305, 318, 358, 493
Lugh's Lance 195
Lugnasad 296
Lugus 292, 296
Lu-Hsing 295, 428
Lujjuphu 9, 55, 250, 252, 295, 412, 429, 442
Luk 291, 296, 362, 515
Lukea 70
Lukeland 355
Luke-Lang 296
Lukelang 296, 449
Lukelong 296
Lullu 296, 304
Luluwa 14
Lu-ma 295
Lumauig 313
Lumha 161, 167, 296
Lumimu-Ut 296
Luna 70, 151, 208, 296, 419
Lung 296
Lung-Wang 156, 296
Luojatar 296
Luonnotar 296, 488
Lupa 10, 297
Lupan 295
lupe 293
Lusin 297
lust 22, 74, 125, 308
Lut 209
lute 97
Luttchmeen 285
Lu-Tung-Pin 295
L'wal 146
Lyacaon 377
Lycaeus, Mount 333
Lycaon 10, 56, 113, 127, 297, 300, 316, 370, 461
Lycaste 297, 386
Lycastus 9, 52, 68, 192, 232, 297, 323, 375
Lycean 62
Lycia 56, 125, 239, 381, 390, 414, 436, 440
Lycius 297
Lycomedes 11, 62
Lycotherses 24, 297
Lycrus 6, 297
Lycurgus 16, 47, 157, 231, 232, 297, 379, 383, 389, 391
Lycus 49, 57, 113, 153, 169, 230, 297, 457
Lydia 35, 152, 200, 218, 286, 363, 453
Lyeshy 289
Lyfjaberg 164, 297, 318
Lygni 220
Lykeious 62
Lyktos 40
Lymnian 463
Lynceas 116
Lynceus 6, 67, 142, 143, 230, 232, 297, 380, 382
Lyngvi 297
Lyons 296
Lyr 297, 305
lyre 62, 116, 170, 214, 292, 330, 459
Lyrnessus 12
Lyrus 20, 51, 61, 218
Lysianassa 17, 76, 297, 314, 317
Lyside 133
Lysidice 81, 218, 297, 377
Lysimache 6, 76, 298, 314
Lysippe 6, 240, 297, 316, 390, 440

M 164, 298
Ma 89, 136, 148
Ma Negoategeh 298
Maa 60, 298
Maa-ab 477
Maa-an-f 75
Maahes 298
Maamba 89
Maanda 344
Maa-Nefert-Ra 298
Maanegarm 206
Maan-Emoinen 401
Maat 5, 43, 46, 298, 299, 341
Maa-thet-f 4
Maati-f-em-tes 75
Maaty 5
Maa-uat 4
Ma-Bellona 69
Mabinogion 68, 155
Mabon 54, 112, 299, 312
Mabonagrain 299
Mabuz 299
Mac Cecht 92
Mac Cuill 92
Mac Greine 92
Mac Ind Og 54
Mac Oc 54, 299
Mac Og 54
Macar 21, 119
Macareus 115, 166, 299
Macaria 21, 145, 351
Macariotes 351
Macedonia 363
Macha 299, 328
Machaon 57, 72, 229, 231, 299
Machchael 299
machete 360
machines and mechanical devices 282
Machulas 11
Macouas 329
Macris 13, 69, 83, 299
Macuilxochitl 246, 299
Mada 77, 299
Madagascar 52, 78, 339, 399, 400, 494, 521
Madavi 99
Madderakka 299
Maderakka 253
Mader-atcha 253
Madhava 275, 299, 498
Madhu 158, 257, 275, 299, 300
Madhupriya 90, 299
Madhusudana 275, 300
Madhyama 487
Madira 148, 300
Madri 77, 276, 280, 300, 372, 444
Madumda 134
Maeander 300, 405, 411
Maenads 300
Maenalus 78, 297, 300
Maenawr Penardd 300
Maeoe 300
Maera 171
Maet 298
Maeve 300
Mafdet 300
Mafuike 300
Mag Mell 177
Maga 144
Magadha 100, 157, 249
Magaera 183
Magatama 300, 445
Magh 414
Magh Tuiredh 134, 139, 296
Maghayanti 300, 404
Magi 325, 408
magic and magicians 27, 53, 65, 135, 154, 196, 199, 202, 209, 224, 260, 267, 296, 360, 431, 464, 505, 509
Magigi 272
Magna Mater 136, 300, 403
Magne 300
Magnes 21, 151, 164, 300, 379, 386
Magnesia 67, 115, 299, 377, 452
Magni 231, 300, 326, 463
Magog 193
Magombe 362
Magora-o 345
magpies 126
maguey 314
Mah 71, 198, 228, 300, 301, 304, 348, 468, 514
Maha Isvari 301
Maha Sambara 411
Mahabalipura 388
Mahabharata 77, 90, 98, 100, 141, 150, 159, 186, 187, 263, 264, 275, 281, 299, 301, 308, 312, 372, 374, 384, 427, 492, 502
Mahachandrarosana 9, 121
Mahadeo 375
Mahadeva 25, 26, 105, 301, 406, 427
Mahagauri 188
Maha-isvari 148
Mahakala 99, 277, 301, 427
Mahakalee 148, 257, 301
Mahakali 148, 188
Maha-Kali 257
Mahakaruna 84
Mahalaxmi 158, 301
Mahallika 219
Maha-Maya 148, 313
Mahamaya 313
Mahamayuri 278
Mahamya 257
Maha-Pita 105, 301
Mahaprajapati 388
Mahapralaya 258, 301
Maharajni 148, 301
Maharishis 308
Mahasena 263
Mahashvara 338
Mahasiddhas 301
Mahasthamaprapta 150, 301, 410, 448
Maha-Vairochana Tathagata 140
Mahavairokana 140
Mahavira 154, 301, 410, 430, 474, 492, 514
Mahayana 103, 290, 303, 389, 422
Mahayogi 427
Mahayugas 159, 258
Mah-Bellona 96, 301
Mahendra 237
Mahes 93
Maheshvara 427
Mahesvara 302, 473, 483
Mahi 101, 302
Mahisasura 148, 158, 302
Mahisha 121
Mahishamardini 158
Mahishasura 146
Mahlaima 400
Maho Penekheka 302
Maho Peneta 302
Mahomet 326
Mahre 13; and Mahrianag 302
Mahrianag 302
Mahrkusha 302, 516
Mahsiddhas 411
Maht 298
Mahu 24, 29, 142, 199, 302, 334, 436, 508
Mahucatah 197
Mahucutah 509
Mahuika 313
Mai 186, 483
Maia 104, 114, 165, 214, 302, 313, 318, 385, 440, 502
maidens 148, 279
Maidere 303
Maidu 133, 134, 278, 397
Maijunga 302
Mainda 77, 302
Maipuri 392
Maira 302
Maira Ata 68, 302
Maire-Monan 302, 327
Maisahana 244, 302
Mait' Carrefour 302, 303
Maitreya 7, 32, 33, 103, 104, 150, 224, 301, 303, 308, 320, 324, 410, 479, 488
Maitsan 471
maize 78, 113, 125, 129, 161, 197, 244, 246, 267, 331, 338, 409, 422, 443, 480, 508, 509, 519; *see also* agriculture; corn
Maka-ku-koae 482
Makali 374
Makanaima 303
Makara 187, 259, 303, 492
Makara Sisters 303
Makea-Tutara 313
Makemake 303
Makeshura 345
Makh 483
Makhi 425
Makila 144, 303
Makkal 327
Maknongan 506
Makonaima 303
Makosh 281
Makunaima 303
mala 389
Malabara 373
Malachim 53
Malah 309
Malawi 329
Malay Peninsula 262
Malaysia 7, 90
male children 121, 122
male courage 497
male Kla 273
male sexuality 89
Male Who Invites 246
Mali 191
Maliades 157, 202
Malik 327, 342
Malinalxochitl 226, 227, 303
Mallcu 164
mallet 288
Malsum 303

Mama 39, 300, 304
Mama Allpa 303
Mama Cocha 132, 304, 497
Mama Cora 304
Mama Lakshmi 285
Mama Nono 303, 304
Mama Occlo 136, 304
Mama Ocllo 304, 306
Mama Oella 304
Mama Ogllo 304
Mama Quilla 117, 136, 239, 304
Mama Zara 304
Mamaki 33, 150, 304, 400, 422, 454
Mamaldi 267
Mamandabari 304
Mamao 385
Mamaragan 304
Mama'sa'a 304
mambos 89
Mamers 310
Mami 39, 71, 300, 304, 348
Mamien 298
Ma-Mien 298, 350
Mammetu 304
Mammetum 304
Mammitu 304
Ma-Mo 298
Mamona 78, 197, 233, 239
Mamu 304
Man 312, 395
Man Eater 256
man in the moon 350
mana 330
Manabhozho 335
Manaboojoo 335
Manabozho 335
Manabush 335
Manaf 305
Mana-garm 206
managers and chiefs 314, 478
Mana-heim 304, 305, 321
Manai-a-ka-lani 277
Manala 273, 295, 305
Manannan 292, 305
Manannan Mac Lir 129, 305, 321
Manannan Mac Llyr 30, 129, 177, 296, 305, 306
Mananwydan ap Llyr 391
Manape 303
Manas 26
Manasa 76, 148, 188, 255, 305, 421, 422, 450, 498
Manasa-Devi 305
Manasa-Putra 404
Manasi 63
Manassa 305
Manat 317
Manawydan Ap Llyr 305, 306
Manawydan Son of Llyr 306
Manawyddan 125, 176, 305, 306, 403
Manco 306, 449
Manco Capac 239, 304, 306, 369, 497
Manco-Capac 306, 449
Manco-Capak 136
Mandaeans 307
Mandalay 338
Mandan 221, 302, 307, 353, 360
Mandara, Mount 147, 158, 281, 282, 306, 319
Mandavi 99
Mande 306, 331, 354
Mandio 307
Mandishire 307
Mandodari 306, 314, 401
Mane 306
Ma-Negoategeh 298
Manes 26, 113, 181, 287, 306, 307
Mangadevatas 148
Mangaia 79, 344, 399, 492
Mangaia Islands 40, 494
Mangala 148, 306
Ma-Ngee 344
Mangi 217, 223, 355
mango 259
Manheim 304
Mani 5, 101, 220, 306, 307, 330, 436
Mania 287, 307
Maniae 307
Manibhadra 282
Manicheism 28, 85, 307
Manigarm 206
Manik 307, 508
Maninga 307
manioc 136, 306
Mani-oka 306
Manito 303, 307
Manitos 307
Manitou 307
Manju Bara 307
Manjughosa 307
Manjughsha 307
Manjursi 411
Manjushree 307
Manjushri 307
Manjusri 70, 84, 103, 104, 150, 301, 307, 327, 328, 389, 410, 467, 487, 489, 492, 505, 513
Manjusri Jampal 413
Manko-Kapak 306
Man-la 99
Man-Lion 336
Manmatha 307, 498, 499
Manna 437
manna ash trees 316
Mannheim 72, 304
Mannus 252
Manru 309
Mansen-o 345
Man-slayer 61
Mantchu-Muchangu 307
Mantius 6, 130, 316
Mantradevatas 148
Mantu 385
Mantus 307
Manu Svayam-bhuva 413
Manu Vaivasvata 312
Manu 307, 308, 312, 388, 389, 427, 447, 489, 493, 512
Manu'a 452
Manuai 308
Manus 233, 243, 389
Manu-sanhita 308
Manusha-Rakshasis 308, 398
Manushcithra 177
Manushi-Buddhas 150, 264, 308, 410, 489, 497
Manusibuddha 308
Manvantara 308
Manyu 53
Manzan Gormo 308
Manzenshao 345
Mao Ying 425
Maoleha 353
Maori People 59, 70, 207, 239, 253, 256, 278, 298, 311, 377, 397, 405, 467, 476, 485, 506
Maorocon 197
Maorocoti 197
Ma-p'am-pa 32
Maponos 299
Mar 308
Mara 33, 259, 308, 329
Maragarme 206
Maragoli 354
Maramma 196, 309
Marapa 308
Marareus 21
Mararisvan 308
Marar-Loka 293
Marassa 308
Maratha 89
Marathon 169
Marathonian Bull 309, 323
Marawa 309, 394
Marcia 12
Marcion 384
Marcra Shee 424
Mardash Nara 146, 251
Mardoll 22, 181, 309
Marduk 13, 15, 36, 52, 55, 58, 59, 63, 71, 73, 95, 142, 143, 161, 166, 167, 168, 172, 233, 243, 270, 272, 309, 332, 339, 342, 345, 423, 432, 433, 458, 466, 484, 510, 511, 520, 521, 523, 525
Mare 77
Mare Goddess 403, 487
Maree 309
Marel 154
Marerewana 30
Mari 99, 148, 309
Mariamma 196, 309
Marian 39
Mariandyni 49
Mariandynus 381
Marianna 39
Marica 129, 177, 310
Marichi 310, 313, 473, 486, 488
Marichi-Bosatsu 310
Marichi-Deva 310
Marici 310
Marid 251
Ma-Riko-Riko 70, 298
Marimata 309
Marind-anim 145
Marinette 310, 465
Maris 66
Marisha 63, 310, 389
Marishi 310, 486
Marishi-Ten 310
marketplace 104, 466
Markhour 385
Marne 420
Marocael 299
Marpessa 130, 176, 232, 386
Marquesas 364, 405, 452, 467
Marri 13
marriage 23, 61, 71, 98, 121, 170, 185, 189, 212, 229, 242, 250, 253, 361, 367, 380, 445, 501, 522
Marru 13
Marruni 310
Mars 34, 47, 50, 51, 66, 95, 96, 101, 115, 123, 131, 151, 152, 153, 171, 173, 195, 238, 253, 263, 310, 315, 384, 395, 396, 405, 410, 468, 480, 495, 499, 524
Marsalai 310
Marsha 310
Marshall 515
Marshall Islands 38, 293, 295, 404, 405, 452
Marsyas 310
Marsyas-Masses 229, 310
Martanda 15, 310, 492, 500
Marttanda 500
Marttanda Savita 310
Martu 13, 200, 310
Martummere 353
Martus 310
Maru 311, 476
Marukka 309
Marumda 278, 311, 397
Marunogere 311
Marut 206, 494
Maruta 494
Maruts 66, 154, 182, 185, 237, 310, 311, 390, 406, 447, 492, 493, 494
Marutukku 309
Maruyama Okyo 185
Marwah 521
Mary 250
Marzann 144, 311
Marzyana 311
Masai 266, 341, 342, 343, 507
Masa-katu-a-katu-kati-paya-pi-Ame-no-oso-po-Mimi-no-mikoto 41
Masaka-yama-tsu-mi 311
Masaka-Yama-Tsu-Mi 420
Masan 311
Masauwu 311
Masaya 311, 321, 451
masculinity 148
Masewi and Oyoyewi 311
Masha and Mashyoi 311
Mashkhith 23
Mashoi 189
Mashtu 311
Mashu 311
Mashya 189, 223; and Mashyoi 311
Mashye 176
Mashyoi 223, 311
Maslum 193
masonry 255
Massachusetts 271
Massim-Biambe 311, 312, 324
Mat 298
Matali 237, 312
Matarisvan 25, 100, 312, 404
Matche-Manito 307
Mater 290
Mater Matuta 238, 312
Mater Turrita 136
maternity 75, 264, 407
Mates-sma-ta 418
Matet 396
Math 58, 68, 103, 139, 155, 199, 292, 312
Math Hen 312
Matholwch 176, 193, 197, 209, 517
Mathonwy 312
Mathura 147, 261, 262, 275, 280
Mathuranath 275, 312
Mati-Syra-Zemlya 312
Matlalcueje 312
Matres 312
Ma't'ou Naing 475
Matres Britanne 312
Matri 148
Matrikas 185
Matrirupa 285
Matris 185, 263, 422
Matrona 253, 312, 420
Matronae 312
Matrs 185
Ma-tshiktshiki 313
Ma-Tsu 298
Ma-tsu-p'o 467
Matsya 308, 312, 489, 493, 498
Matsyendranatha 312
Matu-'u-ta'u-ta'ua 303, 312
Matuarang 313
Matuka 312
Matuku 400, 456, 503
Maturang 312, 337
Matuta 290
Mau 313
Mau-aa 4
Maudgalyayana 313, 465, 466
Maui 79, 217, 280, 293, 300, 313, 329, 369, 394, 454, 456, 478
Maui-Pae 313
Maui-Roto 313
Maui-Taha 313
Maui-tikitiki 313, 329
Maui-tikiti-ki-a-Taranga 313
Maui-tukituki 313
Maui-tupua-tupa 313
Maui-Whao 313
Mauna 313
Mauretania 80
Maut 298
Mauti 4
Mave 300
Ma-Vien 298
Mavors 310
Mawa 302
Mawa-Lisa 292
Mawara-ten 345
Mawu 195, 288, 290, 292, 302, 409
Mawu-Lisa 290, 292
May 96

www.ebook3000.com

3. Picture your fingers like laser beams of Chi, 'Tan Tien and Universe': Feel your Tan Tien and the universe spiral and charge your fingers. Move your fingers out from the mideyebrow around the side of the head to the top of the ears. Your fingers are like lasers -cut-cut-cutting open your skull right in the middle, around to the top of the ear, cutting open your Upper Tan Tien. Cut and project your fingers long into the middle of your brain. Spiral your Tan Tien and the universe. Leave your fingers there. Concentrate on your Tan Tien spiraling – your heart, crown, the universe above, below, front, back left and right all spiraling. Your Tan Tien is a big empty space: primordial force; darkness. You can put so much Chi inside there! The Chi penetrates into your brain.



***Fig. 3.48** Move the fingers to the top of the ears. Feel them growing longer and cutting the skull open, penetrating into the brain.*

4. Move your hands all the way to the back, cutting to the back of the skull. Touch, and feel the Upper Tan Tien open.
5. Touch the base of your skull. Focus on the mid-eyebrow. Feel the Chi flow like a laser beam from back to front and out to the universe in front. Complete the opening process by moving the hands back around to the mideyebrow, cutting as you go.



***Fig. 3.49** Chi moves like a laser, penetrating from the mideyebrow at the front, to the back of skull.*

Maya 313, 314
Maya People 3, 10, 27, 28, 31, 32, 33, 37, 55, 86, 89, 94, 102, 114, 115, 120, 121, 123, 126, 127, 130, 133, 161, 164, 176, 183, 197, 198, 200, 202, 204, 221, 227, 228, 230, 232, 244, 245, 246, 254, 271, 272, 278, 283, 306, 307, 324, 332, 350, 363, 387, 388, 394, 395, 409, 410, 422, 459, 469, 479, 480, 481, 486, 487, 501, 502, 507, 508, 509, 519, 520, 524
Mayadevi 258, 276, 313, 314, 388
Mayahuel 314, 375, 470
Mayauel 314
Mayavati 314, 400
Maydevi 400
mayfly 144
Mayochina 314
Mayon 314
mayurapiccha 304
mayurapichha 304
Mazdaism 50, 53, 138, 307
Mazdayasni-Zaroshtis 524
Mazdean 325
Ma-Zu 298
Mba 95
Mbamba 314
Mbambe 314
Mbir 314
Mboya 102, 354
Me 236, 332
Meabel 139
mead 104, 358
mead of poetry *see* poetry
Meadhbh 300
Measurer 457
Meave 300
Mebet Hotep 81
Mebhdh 300
Mecca 226, 326, 520
Mechaneus 314, 522
Mechanitis 61
Mecionice 174
Mecisteus 17, 67, 174, 314, 451
Meciteus 17
meda 299
Medb 130, 300
Mede 314, 379
Medea 18, 35, 64, 68, 121, 171, 208, 210, 232, 233, 249, 250, 314, 315, 319, 381, 462, 468
Medecolin 193, 315
Medeia 314
Medeias 171, 314, 315, 381
Medeius 18
Medeius 249, 314, 315
Medha 315
Medi Kenaga 315
Media 86
mediators 238
Medica 315, 323
Medicine Buddhas 7, 315
medicine 27, 28, 62, 72, 94, 117, 126, 130, 151, 198, 201, 235, 246, 272, 300, 334, 347, 361, 366, 382, 395, 409, 426, 464, 483, 510, 513, 517; *see also* healing; health
medicine men 507
Medina 327
Medini 101, 299, 315
meditation 47, 104, 479
Mediterranean Sea 50, 342
Medon 165, 393
Medousa 315
Medus 18, 314, 315
Medusa 20, 118, 127, 190, 194, 315, 344, 356, 376, 380, 502
Megaera 171, 315, 468
Megaira 315
Megalesius 457
Megamedes 370
Megapenthes 240, 344, 440
Megara 35, 54, 113, 115, 175, 213, 240, 289, 290, 315, 349, 383, 462
Megareus 17, 219, 240, 287, 315, 387
Megaris 115
Megh Sambara 307
Megingiord 315
Megin-giord 315, 463
Megingjardir 315
Mehen 5, 177, 269, 315, 477, 481
Mehit 54, 315
Mehiyya-El 113
Mehni 177, 417
Mehu 179
Mehueret 341
Meiden 316
Meido 518
Meili 357
Meilichios 316, 522
Meion 136, 316
Meir 482
Mekel 342
Melaenis 61
Melampodes 142
Melampus 6, 67, 200, 232, 297, 316, 390
Melanesia 6, 7, 27, 206, 240, 255, 256, 259, 263, 271, 273, 308, 309, 310, 311, 319, 352, 394, 430, 452, 496, 497, 504
Melaneus 175
Melanion 78, 219, 316
Melanippe 21, 57, 66, 69, 104, 218, 316, 320, 461
Melanippus 9, 17, 287, 314, 316, 379, 387, 480
Melas 114, 121, 316, 359, 383, 387, 440
Melatha 316
Melcarth 317
Melchi-sedeq 417
Melchizidek 14
Meleager 18, 38, 66, 67, 114, 130, 286, 316, 359, 386, 473
Melech 327
Melekh 327
Melesians 45
Melete 60, 316, 330
Melia 19, 62, 64, 236, 316, 383
Meliae 171, 184, 316, 331, 484
Meliboea 127, 290, 297, 316, 349, 379
Melicertes 79, 239, 316, 317, 370, 387
Melie 49, 331
Melinaea 61
Melissa 17, 40, 317
Melisseus 17, 232, 317
Melissus 40, 317
Melite 229
Melkart 27, 36, 86, 317
Melkarth 213, 317
Melodious Voice 278
Melos 9, 146
Melpomene 11, 217, 317, 330, 433
Melqart 27, 123, 172, 213, 317
Melquart 75, 317
Melville Island 370
Mem Loimis 362
Memnon 57, 169, 317, 461
Memomin 334
memory 23, 149, 258, 326, 330, 435
Memphis 25, 61, 62, 169, 235, 291, 317, 340, 345, 367, 391, 418, 420, 453, 464
Memphis Triad 317, 391
Memphite Triad 418
Men 317, 322
Men Brayut 204
Men Shen 317
Mena 148, 317, 374
Men-a 477
Menachem 350
Menaka 317
Menaka 63
Menakshi 148, 257
Menalippe 123
Menat 34, 37, 317, 392, 484
Mende People 177, 344
Mendean Triad 92, 317
Mendes 206, 318
Mene 318, 419
Menehune 285
Menelaus 23, 51, 81, 116, 130, 145, 166, 205, 214, 216, 318, 344, 463
Menenui 458
Menerva 323
Menesthius 318, 438
Menestratus 130, 318
Meng 139, 318
Menglad 164, 181, 297, 318
Menglod 181, 318
Meng-P'o 318
Meng'p'o niang-niang 466
Meng-Po Niang-Niang 318
Meng-T'ien 318, 475
Menhit 457
Meni 178, 184, 242, 318
Menja 331
Menkhet 477
Menmenu 418
Menodice 229, 318, 365
Menoeceus 54, 66, 175, 252, 284, 315, 318
Menoetius 6, 13, 19, 80, 169, 231, 241, 318, 356, 375, 391, 440
Menominee People 50, 266
Menon 419
Menrfa 323
Menrva 323
Men-Shen 317, 425
menstruation 317
Mentha 318
Menthe 131, 318, 324
Menthu 328
Mentu 328
Menu 318, 322
Men-Ur 317
Menur 326
Me-phem-pa 32
Mer 13, 241, 404
Merchanitis 79
merchants 27, 150, 449
Merciful Mother 278
Mercurius 214, 318
Mercury 14, 47, 58, 59, 72, 88, 151, 173, 182, 214, 253, 296, 302, 318, 319, 339, 384, 496
Mercury Artaeus 71
mercy 251, 253, 261, 278, 313, 465
Merenaaui-f 60
Meriones 10
Merlin 70, 237, 500
mermaids 78, 175, 207, 266, 328, 342, 346, 364, 461
merman 207
Mermer 13, 241
Mermerus 171, 235, 249, 319, 381
Merodach 309, 339, 423
Merope 21, 131, 138, 165, 170, 192, 202, 205, 319, 359, 365, 366, 372, 378, 382, 385, 386, 433, 440, 463
Meropes 130, 299
Merops 72, 229, 231, 319, 356, 372
Merseger 319
Mersey River 95
Mertseger 319
Mert-sekert 319
Meru, Mount 24, 41, 100, 105, 120, 149, 186, 188, 237, 238, 256, 282, 293, 319, 373, 375, 447, 488, 494, 499
Mer-ur 326
Merwer the Bull 319
Merwer 81
Mese 229, 319, 330, 343
Mesede 7, 319
Mesharum 423
Meshkhenet 319
Meshkhent 319
Meshlamthea 342
Meskhenit 319
Meskhent 319
Meskhti 60
Meslam 48, 295, 319
Mesopotamia 3, 14, 37, 52, 73, 95, 104, 158, 191, 206, 220, 233, 260, 310, 332, 345, 373, 396, 423, 424, 429, 467, 514
Mes-Peh 477
Mesperit-Arat-Maatu 320
Messene 67, 116, 194, 220, 240, 320, 382, 386
messengers 6, 24, 53, 78, 124, 154, 172, 191, 214, 318, 357, 434
Messenia 21, 192, 240, 320, 379, 386
Messens 70
Messiah 165, 250
Messibizi 320
Messina 56, 342
Messon 320
Messou 335
Mest-en-Asar 425
Mestha 48
Mesti 48
Mestor 52, 194, 298, 440
Mestra 172
Mest-tcheses 425
metal 134, 261, 270
Metal Mountain Prince Deity 260
metal working 111, 502
metallurgy 138
Metal-Mountain Princess Deity 261
Metaneira 6, 117, 146
Metapontus 320, 461
Metchet-qat-utebu 458
Met-en-Asar 425
meteors 53
Metes-hra-ari-she 477
Metes-mau-at 418
Metes-neheh 418
Metes-sen 477
Metharme 16, 129, 320, 393
Methusha-El 113
Methyer 242
Metidice 17, 320, 451
Metion 138
Metipa 395
Me-tog-ma 393
Metope 57, 64, 74, 130, 243, 320, 376, 405, 410, 412, 461
Metricos 21, 351
Metropator 146
Metrope 380
Metteya 303
Metu-khut-f 4
Metzli 518
Metztli 320, 460, 518
Meuler 320
mew 313
Mexico 10, 12, 13, 28, 62, 81, 86, 103, 113, 114, 118, 120, 122, 125, 129, 130, 131, 132, 133, 146, 163, 180, 222, 225, 226, 234, 240, 244, 245, 246, 265, 299, 312, 314, 320, 325, 335, 338, 357, 363, 368, 375, 376, 384, 395, 420, 424, 449, 450, 451, 456, 459, 460, 466, 469, 470, 471, 472, 477, 481, 508,

509, 510, 514, 517, 518, 520, 524
Mexitli 226
Mextli 226
Meyi 362
Mezadevs 320
Mezamat 254, 320
Mezavirs 320
Meztli 320, 456, 472
Mfam 354
Mfan 293
Miach 30, 151, 320
Michabo 191, 320, 335
Michael 13, 14, 53, 414
Mi-che-pa 7, 315
Michilimakinak 335
Miclancihuatl 321
Miclantecutli 3, 320, 321
Micronesia 38, 59, 65, 287, 291, 292, 295, 296, 313, 329, 362, 370, 393, 404, 436, 515
Mictanteot 311, 321, 451
Mictlan 62, 125, 201, 321, 324, 395, 472
Mictlancihuatl 295
Mictlanciuatl 125, 288, 509
Mictlantecuhtli 125, 295, 320, 321, 470, 523
Mictlantecutli 125, 288, 320, 395, 459, 509
Micux 321
Mida 193
Midas 194, 321, 371, 431
middle abode 321
Middle Ages 237, 441
Middle Earth 321
Middle East 3, 16, 156, 202, 206, 242, 453
Middle Kingdom 223
Midea 380
Mider 54, 103, 136, 173, 321
Midewiwin 321, 335
Midgaard 321
Midgard 53, 72, 101, 198, 252, 294, 304, 305, 321, 516, 517
Mid-gard 321
Midgard Serpent 53, 198, 229, 252
Midgardsormen 53, 252
Midgarth 321
Midir 54, 139, 321
Midsummer Night 30
midwife 210
Miehts-Hozjin 289
Mielikki 321, 453
Might 300, 465
Mighty Lord of the Thunderbolt 237
Mighty One 419
Mighty One of Great Knowledge 139
Mighty Striker 441
Mighty Time 257
Mig-mi-bzan 497
Migonitis 61
Mihir 325
Mi-ho-tsu hime 260
Mihr 65, 321, 325, 487
Mihrajan 325
Mi-Hung-T'ang 320
Mi-Hun-T'ang 320
Mikak'e 322
Mikal 327
Mikula 104
Mi-Kura-Tana-no-Kami 41, 42, 320, 445
Milaraspa 322
Mila-Raspa 322
Milcom 317, 327
mildew 405
Milesians 45, 92, 477
Milesius 14
Miletus 9, 62, 67, 82, 145, 322, 323, 372, 414
Mi-Li 320, 324
milk 9, 107
Milk, Ocean of 48, 147, 399, 427
milkmaids 194
Milky Way 241, 244, 270, 271, 278, 308, 329, 488
mill 411
millet 224
Mi-Lo Fu 32, 224, 303, 320
Milomaki 322
Milu 261, 313
Mim 322
Mimar 322
Mimas 66, 190, 212, 219, 469
Mime 322
Mimer-Nidhad 322
Mimi 322
mimia reed 7
Miming 322, 501
Mimir 98, 104, 180, 192, 211, 322, 326, 332, 350, 357, 485
Mimir's Well 322, 357, 516
Mimoro, Mount 442
Min 269, 317, 322, 323, 342, 394, 433
Min of Koptos 322
Minabozho 323
Minakshi 148, 283, 374
Minakshidevi 148, 374
Min-Amen 48, 49
Minan 154
Minato-no-kami 262
Mindi 196, 397
mineral springs 196
minerals 259
Minerva 20, 50, 79, 80, 95, 136, 151, 181, 243, 253, 315, 323, 468, 487
Minga Bengale 323
Mini 322
Minibozho 335
mining 77, 273, 322
Minipa 329
Ministry of Epidemics 473
Minoans 166
Minos 9, 18, 20, 52, 57, 68, 76, 82, 116, 137, 138, 147, 152, 174, 192, 201, 210, 213, 219, 231, 232, 253, 284, 297, 323, 324, 349, 365, 375, 379, 380, 386, 402, 403, 414, 440, 441, 508, 523
Minos II 297
Minotaur 18, 52, 68, 76, 138, 284, 297, 323, 375, 457
Minotaurus 323
Mintha 318, 324
Minthe 324
Minu-anni 242
Minub 322
Minucihr 177
Minu-ullu 242
Minyans 67
Minyas 16, 35, 67, 128, 131, 218, 290, 297, 324, 474
Minyong People 104
Miolnir 326
Mi-oya-no-kami 182
Mi-p'yed 7, 315
Mirabichi 324
Miracucha 314
Mirage 70
Miralaid 154
Miroku-Bosatsu 224, 303, 320, 324
mirrors 98, 166
Mirsi 324
Mirsu 324
mirth 206
Miru 292, 295, 324, 344
Miru-me 166, 250
Misambwa 324
Misca 127, 129, 162, 324, 395, 451, 500
mischief 79, 266
misery 210, 349
misfortune 194, 210
Misharu 85, 324, 417
Misor 267, 324, 417, 448
Misrakesi 63
Missabos 320
Misshakukongo 345
Mississippi 6
Missiwabun 320
mist 18, 384, 401, 456, 490
Mistelteinn 90, 324
Mr. Black 123, 507
Mr. Golden Cuirass 126
Mr. Horse-face 123
Mr. Ox-face 123
Mr. Red Coat 128
Mr. Red Jacket 128
Mr. White 123, 507
mistletoe 90, 221, 336
Mistress of All the Gods 304
Mistress of Heaven 236
Mistress of Horses 76
Mistress of the Gods 51, 244
Mistress of the World 148
Mistress of Wild Things 152
Miszuchi 247
Mithr 321
Mithra 29, 35, 50, 126, 270, 321, 325, 400, 439, 485, 487, 495, 514
Mithraeum 325
Mithraic Mysteries 325
Mithras 325
Mithric 325
Mitnal 202, 324
Mitoshino 325
Mitoshi-no-kami 325
Mitosh-no-kami 325
Mitra 15, 24, 71, 325, 374, 390, 444, 492, 493, 512
Mitra-Varuna 143, 325, 492
Mitshi-Manitou 272, 325
Mitsuha-nome 247
Mixcoatl 86, 114, 121, 125, 129, 131, 226, 227, 325
Mixe 121
Mixis 21, 351
Mixkotl 325
Mixtec 132, 469, 508
Miysis 93, 326
Mizaru 274
Mizimu 326
Mjodvitnir 160
Mjollnir 164, 300, 326, 432, 435, 463, 464
Mjolnir 326
Mka-gro-ma 140
Mkah Hgroma 326
Mmoatia 326
Mmokos 326, 327
Mneme 60, 316, 330
Mnemosyne 113, 135, 170, 184, 317, 326, 330, 461, 462, 523
Mneuis 326
Mnevis 62, 326, 367; bull 215
Moaalii 326
Moabite 123
Moana-Irakau 397
Moanalua 264
Moaning-River 246
moats 476
Mochus 30
Mode 326
Modgud 326
Modi 231, 300, 326, 463
Modoc 279
Modron 142, 299, 312, 326
Modsogner 326
Modsognir 159, 326
Moemoe 377
Moerae 177, 327
Moertholl 181
Mohammed 34, 36, 53, 200, 326, 520
Mohawks 154, 201, 454
Mo-hi-hai 326
Mohina 230
Mohini 204, 327, 498
Moho, King 260
Moin 160
Moira 178, 327
Moirae 62, 178, 327, 461, 523
Moiragetes 62, 327, 522
Moirai 76, 81, 130, 173, 177, 222, 327
moisture 469
Mojave 117
Mokoroa 313
Mokusa 326, 327
Molc 327
Molech 327
Mo-Li 467
Mo-li Ch'ing 326, 439
Mo-li Hai 326, 439
Mo-li Hung 326, 439
Mo-li Shore 439
Mo-li Shou 326
Mo-li-chi 473
Molione 135, 175, 327
Moliones 13
Molionidae 327
Molionides 135, 327
Mollac 327
Molloch 327
Moloch 25, 317, 327, 414
Molokai 277, 326, 369
Molokh 327
Molpe 327
Molus 66, 146, 327, 359
Momo 164, 327
Momona 78
Momus 118, 170, 230, 266, 327, 352
Momus Moros 122
Monan 240, 302, 327
Mondamin 327
Moneta 253
Mongan 305
Mongolia 77, 367
Mongols 50, 81, 162, 270, 279, 338, 356, 442, 452, 453, 478, 483
mongoose 248, 283
Monju 307, 327
Monju-Bosatsu 307, 327, 328
monkeys 53, 70, 91, 99, 159, 191, 203, 262, 267, 274, 302, 443, 517
Mono 363
Monoecus 213, 328
Monoetius 131
Monogenes 21, 351
monsoons 92, 471
monsters 8, 9, 12, 14, 16, 18, 28, 46, 49, 51, 59, 64, 67, 77, 95, 102, 115, 117, 119, 125, 134, 162, 243, 267, 270, 272, 279, 280, 294, 299, 344, 424, 427, 466, 480, 509
Mont 43, 328
Montagnais 78, 349
Montezuma 134
Month 43, 328
Moombi 191
moon 27, 30, 36, 37, 40, 42, 43, 49, 52, 53, 59, 68, 70, 73, 77, 80, 82, 93, 95, 96, 97, 99, 101, 103, 106, 108, 110, 111, 119, 121, 122, 123, 124, 127, 133, 137, 138, 166, 173, 177, 191, 193, 194, 195, 199, 202, 206, 208, 217, 220, 221, 233, 234, 247, 253, 265, 268, 273, 274, 275, 278, 279, 282, 283, 290, 296, 297, 300, 304, 311, 320, 331, 334, 335, 336, 338, 350, 354, 363, 367, 369, 377, 382, 403, 419, 422, 427, 432, 436, 437, 453, 456, 460, 470, 474, 476, 482, 487, 509, 514, 523, 525
Moose 184
Mopaditis 328
Mopsus 67, 328
Mopus 113
Moquequeloa 460
Moqwais 50
Mora 271
Morai 64

www.ebook3000.com

Morave 7
Mordred 14, 70
Morgan Le Fay 70, 328
Morganes 328
Morgens 328
Morityama 328
Morkul-Kua-Luan 328
Mormyrus Kannume 368
morning 343, 413
Morning Star 62, 71, 128, 189, 190, 295, 325, 468, 525
Morning Venus God 62
Moros 22, 118, 230, 266, 327, 328, 351
Morpheus 230, 328, 375
Morpho 61
Morrigan 139, 299, 328
Morrigu 84, 89, 92, 328, 342
Morrigu Morrigan 341
Morrigu-Morrigan 328
Mors 328, 461
Morta 81, 328, 373
mortar and pestle 88
Mortuary goddess 206, 341
Moschel 328
Moses 153, 250, 408
Mosigsig 313
Mosotene 154
Mosquito 302
Most Grand 89
Most Royal 34
Mot 36, 51, 87, 164, 290, 328, 424
Mother Corn 343
Mother Earth 149, 170, 228
Mother Earth Moist 312
mother goddesses 10, 15, 22, 24, 32, 33, 34, 36, 37, 39, 42, 44, 50, 51, 56, 58, 59, 63, 71, 73, 75, 78, 84, 93, 96, 103, 104, 105, 112, 131, 138, 140, 148, 158, 164, 173, 185, 188, 190, 198, 203, 207, 217, 225, 226, 233, 234, 235, 236, 238, 242, 244, 246, 247, 254, 260, 265, 269, 272, 278, 285, 300, 304, 308, 312, 313, 318, 331, 334, 337, 340, 343, 346, 347, 348, 354, 363, 374, 377, 397, 400, 412, 422, 424, 425, 427, 460, 468, 471, 476, 479, 488, 497, 500, 501, 504, 515, 522, 523
Mothir 329
Motikitik 292, 295, 313, 329
Motu-tapu 468
Mounanchou 105
mountain ash 33
Mountaineer 148
mountains 45, 107, 112, 115, 127, 147, 159, 182, 188, 192, 200, 235, 270, 277, 278, 281, 311, 329, 334, 355, 364, 374, 406, 409, 426, 443, 469, 476, 481
Mouri 309
Mourner of the People 361
mouse-god 62
Mousso Koroni 331
Mowee 313
Moymis 97
Moyocoyani 460
Mozambique 467
Mpambe 290, 314, 330
Mpungu 354
Mridani 148
Mrigavyadha 329, 406
Mrile 507
Mritya 329, 512
Mrtyu 308, 329
Mrule 507
Mtanga 329, 330
Mu Kung 329, 519
Mucalinda 329
Muchilinda 329
Mud Earth 481
Mudhead 329, 457
Mudje-Monedo 325
mudras 33, 109, 140, 304
Mudungkala 329
Muenster 136
Mugasha 255, 265, 329, 504
Muhammad 274, 326
Muirne 179
Muit 196, 397, 505
Mukasa 271, 329
Mu-King 329
Mukunda 329
Mukuru 363
Mukylcin 266
Mulac 94, 327
Mulciber the Smelter 212, 329, 502
muli 259
Muliebris 180
Mu-lien 313, 466
Mulius 13, 329, 388
Mul-lil 14
Muludaianinis 329
Muluku 329
Mulungu 329
Mumbonang 506
Mumham 164
mummies 5, 58, 62, 86, 268, 367
Mummu 63, 161, 309, 330
Mummu-Tiamat 466
Mumuhango 330
Mumumanugara 506
Mumuna 505
Munakata 15, 231, 449, 464
Munda 128, 158, 257, 330
Mundang 311, 324
Mundilare 330
Mundilfaer 330
Mundilfari 306, 330, 436, 443
Mundilfore 330
Munga Munga 330
Mungamunga 330, 505
Mungan-Ngaua 330, 353
Munganngaua 89
Mungo 330
Mungu 330
Muni 186
Muninn and Huginn 330
Muninn 357
Munis 105, 293
Munitus 10, 330
Munon 463
Munster 30, 112
Munsumundok 272
Muntalog 506
Mur 241
Mura 282
Murdad 45, 48
murderers 20, 128, 266
Murias 195, 477
Murine 179
muro 347
Murtaza 36
Muru 336
Muruhan 263
Muryel 197
Muryoju 45, 46, 140
Muryoka 45
Muryoko 45
Musa 330
Musagetes 62, 330
Musala 90, 330
Musali 90
Muses 11, 13, 23, 25, 37, 62, 115, 130, 170, 175, 195, 218, 229, 317, 326, 330, 368, 374, 376, 386, 433, 459, 461, 474, 523
Mushdamma 167, 330
music and musicians 54, 62, 98, 234, 244, 270, 272, 295, 299, 346, 382, 413, 464, 488, 491
Musisi 329
muskrat 320
Muslims 7, 8, 36, 86, 113, 184, 337, 446; *see also* Islam
Muspel 331
Muspelheim 331
Muspell 101, 496
Muspellheim 331
Muspell-heim 494
Muspells-heim 191, 321, 331, 444, 497, 517
Muspellsheim 331
Muspells-heim 5
mussels 65
Musso Koroni 331, 378, 501
Mut 43, 44, 93, 268, 328, 331, 353, 418, 419
Muta 331
Mutalamma goddesses 514
Mutgo 151
Muti-khenti-Tuat 477
Muttra 275, 312
Mutuhei 452
Mutunus 331, 389
Mutyalamma 55, 227, 331
Mutyalammo goddesses 90, 113, 126, 187
Muut 331
Muyalaka 338
Muye 469
Muy'ingwa 331
Muyscaya People 103, 124, 126
Muzimu 326
Muzo 399
Mwambu and Sela 331
Mycenae 20, 23, 35, 81, 116, 130, 151, 165, 213, 377, 380
Mycene 331
Myersyats 144, 331
Myesyats 331, 524
Mygdalion 129
Mygdon 49, 331
Mying-ma-pa 411
Mylitta 73, 75, 95, 331
Mymidon 13
Mynes 176
Myo-ken 42
Myrina 174
Myrmidons 10, 11, 12, 13, 18, 19, 67, 76, 121, 174, 220, 331, 375, 376, 377
myrrh 16, 97, 331
Myrrha 16, 117, 129, 331
Myrtilus 214, 218, 331, 359, 378, 434
myrtle 61
Mysia 189, 387, 522
Mysing 331
Mysinger 331
Mysore 196, 309
mysteries 49, 257
myths 257

N 332
Na Atibu 144, 256, 332
Na Reau 337
Na Rena 404
Naa 24
Naaki 332
Naarayan 337
Na-Arean 337
Naareau 337
Nabataens 37, 200
Nabu 152, 309, 332, 334, 344, 353, 392, 455, 469, 484
Nabudi Women 332
Nabug 332
Nachash 332
Nacht 351
Nacon 332
Nadanta 338
Naddgofugr 322, 332
Nadi-Devata 332
Nadija 100
Nadimmud 161, 352
Naenia 339
Nag 332
Naga 69, 329, 332, 484
Naga Knaya 332
Naga Naga Knaya 332
Naga-Dwipa 333
Naga-pasa 332, 492
Nagarjuna 140
Nagas 146, 149, 156, 188, 238, 255, 264, 305, 333, 375, 420, 421, 450, 489, 493, 498; and Naginis 332; and Nagis 332, 414; and Nagunis 332
Naga-Teka 187, 332
Nagi serpent 483
Nagilfar 333
Nagis 255, 264, 305, 332, 450
Naglefar 333
Naglefare 333
Naglfar 333
Naglfari 82, 333, 351
Nagnis 332
Nagombe People 33
Nagua 333
Nagual 333
Nah-Hunte 333
Nahochacyumchac 350
Nahodoola 471
Nahua 314, 508
Nahual 333
Nahualpilli 469
Nahuatl 245
Nahui Atl 288
Nahui Ehecatl 288
Nahui Ocelotl 460
Nahui Ollin 288, 459, 509
Nahui 288
Nahui Quiahuitl 288
Nahuiatl 121
Nahui-Ike 313
Nai 32, 61, 180, 420
Naia 332
Naiades 333
Naiads 11, 23, 93, 132, 134, 151, 170, 231, 333, 354, 386, 407
Naiga-Mesha 341
Nain 101, 160
Nai-nai Niang-niang 425, 467
Nai-nai-miao 333
Nai-no-kami 450
Nairatma 215
Nairitya 152, 333, 398
Nairrita 333
Nairriti 148
Nairyosangha 333
Nais 192
Naivedya 47
Naja 332
Najade 333
Naje 332
Nak 333
Nakago no mibashira 247
Nakawe 265, 333
Naka-Yama-Tsu-Mi 334, 420
Nakhash 290, 397
Nakime 43
Nakisawame-no-kami 247
Nakity 269
Nakiu-menat 4
Nakshatras 493
Nakula 77, 300, 334, 409
Nal 177
Nala 28, 133, 334, 499
Nali 160
Namaitami 429
Namandjolk 334
Namarakains 334
Namargon 334
Namasangiti 334
Namasia 429
Nambi 198, 256, 272, 338
Nambubi 329
Namios 62
Nam-kha-ing-kya-wang-chug-ma 334, 422
Nammu 49, 71, 271, 334, 346, 348
Nam-parsnon-sras 488
Nampo Gundari Yasha 199

Namtar 146, 170, 228, 242, 334
Namtaru 37, 334
Namtillaku 309
Namuci 308
Namu-tho-se-ser-chhen 282
Namu-Zozusen 282
Nana 24, 75, 81, 95, 133, 236, 332, 334, 335, 354, 412
Nana Buluku 290, 292, 302, 334
Nana Nyankopon 8
Nanabojo 127, 334
Nanaboojoo 334
Nanabozho 334, 335, 350
Nanacatltzatzi 226
Nanahuatzin 335, 456
Nanaki 43
Na-naki-me 43
Nanauatzin 335
Nanautzin 508
Nan-Chi 428
Nancomala 335
Nanda 147, 148, 204, 262, 275, 290, 332, 335, 484, 514
Nandaka 335, 498
Nandana 263, 280
Nandaryu-o 345
Nandecy 478
Nanderevusu 478
Nandi 89, 335, 427, 428
Nandini 259, 335, 427
Nandisha 335, 427
Nandisvara 427
Nane 50, 65, 321, 335
Nang-sal-ma 84
Nanih Waiya 335
Nanna 22, 90, 168, 180, 236, 335, 336, 347, 432
Nannan 164
Nannar 311, 336, 432
Nanook 336
Nanshe 161, 236, 336
Nantosuelta 336, 431, 441
Nantosvelta 336
Nanu 58, 164
Nanuq 336
Naonghaithya 77, 336, 338
Naonhaithya 138, 336
Naosihaithya 336
Napaeae 336
Na'pi 336
Napi 336
Nar 101, 130, 146, 160, 251
Nara 42, 146, 251, 258, 337, 497
Nara simhavatara 336
Narada 275, 336, 388
Naraen 345
Narah 337
Naraka 15, 336, 434, 493, 512
Naraka-asura 336
Narakasur 336
Naraloka 336
Naranarayana 485
Nara-Raja 282
Narasamsa 25, 333, 337
Narashinha 336
Narasimba 336, 498
Narasimbha 336, 498
Nara-Simbha 336, 498
Nara-Simha 219, 336, 388, 491
Narasinha 336, 498
Narayana 105, 219, 258, 337, 374, 393, 498
Narbonnaise 431
Narcaeus 153
Narcissus 118, 162, 289, 337, 379, 404
Nare 337
Nareau 144, 312, 337, 362, 394, 404, 448
Nareua 337
Narfe 337
Narfi 337
Nari 309, 337, 490, 497
Nariman 266
Narleau 337
Narmada 92, 186, 187
Naruau 337
Narudu 342
Naru-kami 337
Narve 337
Narvi 337, 345, 351, 490
Nasamon 9, 115, 337
Nasargiel 211, 338
Nasatya 77, 447
Nasatyas 143, 338; and Dasra 338
Nascopi 221
Nascopie 213, 214, 504, 505
Nasilele 338, 354
Nasrah 338
Nastrond 338
Nasu 157, 338
Nat 145, 351, 436
Nata 133; and Nena 338
Natagai 338
Nataraja 338, 427
Nataraja Siva 338, 427
Natchez 6, 321, 470, 482
Natesha 338
Native North Americans 199, 265, 307, 313, 349, 394, 395
nats 220, 338
Natt 5
Nat-thami 338
nature 14, 70, 88, 133, 384, 519
Natu-taka-mi-no-kami 482
Nau 353; and Naut 338; and Nen 338
Nau Ut Set 446
Naubolus 67, 382
Nauholin 338
Nauisithous 114, 338
Naunet 353, 359, 391
Naupactus 62
Nauplius 49, 67, 216, 338
Nauroz 338, 516
Nauru 337
Nau-Shesma 338
Nausinous 114, 339
Nausithous 339, 379
Naut 338
nautilus 36
Nautsiti 231
Nav 339
Navaho 81, 134, 185, 273, 471, 517
Navajo People 51, 95, 173, 193, 206, 339, 446, 463, 464, 466, 470, 471, 472, 476, 515, 518
Nava-ratri 159, 339
Navasard 339
navigation 38, 270, 370
Nayanezgani 51, 173, 515; and Thobadzistshini 339
Naymlap 339
Nazi 339, 346
Nchsh 332
Ndebele 350
Ndengei 339
Ndengi 339
Ndjambi Karunga 339
'Ndrianahary 339
'Ndriananahary 339
Ndriananahary 52, 78, 339
Ne 339
Neaera 20, 67, 169, 176, 286, 339, 378
Neamhan 341
Neara 118
Neb-abui 75
Neba-per-em-khetkhet 75
Neb-aqet 458
Neb-baiu 4
Nebhet Hotep 244
Neb-hrau 75
Nebiru 309
Neb-Maat 75
Nebmerutef 339
Nebo 170, 332, 339
Neb-pat 477
nebris 153
Nebrophonus 249, 339
Neb-senku 4
Nebsent 75
Nebt Ushau 340
Nebt-ankhiu 417
Nebt-au-khent-Tuat 477
Nebthet 342
Nebt-het 4
Nebt-Hetep 81, 244
Neb-Ti 342
Nebti 477
Nebt-khu 417
Nebt-mat 379, 477
Nebt-setau 379, 477
Nebt-shat 379, 477
Nebt-shef-shefet 379, 477
Nebui 425
Necar 350
necklace 108
Necklace of the Brisings 36, 181
Necks 350
Necropolis 75, 118
nectar 40, 42, 48, 69
Neda 340, 522
Nedolya 155
Nedu 65
Nef-em-baiu 4
Nefer Hor 340
Nefertem 340, 391, 418
Nefer-Tem 75, 340
Nefertiti 33, 79
Nefertum 317, 340, 391
Negafok 340
Negative Confessions 46, 75, 340
Negoogunogumbar 340
Neha-bra 420
Neha-hau 75
Neha-hra 5
Nehallennia 340
Nehata 477
Nehebkau 340
Neheb-kau 75, 340, 353, 418
Neheb-nefert 75
Neheh 209, 340
Nehelennia 340
Nehemauit 457
Nehes 486
Nehesu 4
Neh-har 269
Nehi 4
Nehmauit 340
Nehr 425
Neht 341
Nehui 298
Neit 341
Neiterogob 341
Neith 80, 86, 88, 92, 122, 204, 269, 341, 353, 413, 417, 420
Nejamesha 341
Nekau 477
Nekenit 417
Nekenu 458
Nekhbet 341, 503
Nekhebet 341, 481
Nekhebit 341
Nekhen 75, 223
Nekheny 223
Neleus 21, 65, 127, 341, 377, 379, 410, 430, 451, 480
Nemain 328, 341
Neman 341
Nemcatacoa 341
Nemea 419
Nemean lion 162, 213, 438, 480
Nemed 477
Nemeds 92
Nemesis 17, 22, 118, 122, 170, 173, 230, 266, 327, 341, 342, 352
Nemeso 341
Nemi 163
Nemon 342
Nemontana 342
Nempterequeteva 103
Nemquetheba 103
Nen 338
Nena 338
'Nenaunir 342
Nenaunir 342, 344
Nencatacoa 135
Neno-Katatsu-kuni 342, 518
Ne-no-kuni 260, 342, 518
Neoptolemus 11
Nepal 9, 15, 33, 46, 47, 71, 83, 84, 99, 102, 120, 121, 124, 150, 152, 256, 268, 285, 301, 312, 333, 371, 375, 397, 409, 411, 427, 432, 439, 488, 490, 491, 502
Nepele 211
Nepen 425
Nephele 6, 79, 117, 194, 229, 239, 245, 297, 342, 343, 383, 389
Nephthys 58, 70, 72, 81, 168, 189, 204, 243, 341, 342, 353, 367, 394, 421
Nephythys 342
Nepr 425
Nepra 342, 456
Nepthys 396, 420
Neptune 151, 253, 342, 387
Neptunius 387
Neptuns 387
Neptunus 20, 205, 350
Nerau 477
Nereides 116, 239, 342
Nereids 12, 18, 47, 52, 119, 131, 134, 137, 155, 156, 160, 170, 173, 185, 290, 342, 354, 356, 372, 375, 381, 391, 461, 462, 506
Nereus 47, 119, 131, 135, 137, 143, 155, 160, 170, 174, 184, 185, 342, 356, 372, 381, 383, 387, 391, 438, 462
Nergal 37, 64, 148, 168, 191, 197, 241, 272, 295, 334, 342, 402, 414
Neri 294, 343, 477
Nerig 345
Nerio 310
Nerivik 343, 417, 418
Nerrivik 343, 417
Nert 417
Nerta 60
Nertha 215, 343
Nerthus 98, 343, 350
Nesaru 343
Nesert 343
Nesht 61
Nesmekhef 298
Neso 430
Nesr 343
Nesreca 439
Nessus 213, 343
Nesti-khenti-Tuat 477
Nestor 51, 57, 66, 162, 174, 329, 341, 343, 369, 376, 440, 464
Nesu 71
Net 43, 80, 91, 341
Netch-Baiu 4
Netchesti 4
Nete 229, 319, 330, 343
Neteqa-hr-khesef-atu 477
Neter 343
Neter Mut 343
Neteri 343
Neter-khertet 477
Neter-neteru 477
Neter-Ta 343
Netert-en-khentet-Ra 379, 477
Netetthap 343
Nethert 4
netherworld 328
Netheth 458
Nethunus 342
Neti 236
Net-neb-ua-kheper-autu 458
Netra 343
Netru 177, 417
nets 108

www.ebook3000.com

Netsilik Eskimo 352
Neur 283
Neuri 343
neuter 106
New Guinea 30, 145, 220, 303, 431
New Hebrides 313, 394, 471, 472, 482
New Kingdom 62
New Testament 95, 250
New Year 98
New Zealand 59, 64, 70, 84, 207, 217, 218, 239, 253, 255, 256, 262, 313, 343, 344, 372, 397, 399, 405, 452, 455, 467, 476, 485
newborn children 121, 145, 155, 443
News Gatherer 226
'Ng Ai 343
Ng Ai 343
Nga 343
Ngahue 343
'Ngai 343
Ngai 342, 343, 344
Ngakola 344, 459
Ngalaibal 158
Ngalalbal 143
Ngaljod 397
Ngaore 344
Ngaru 344
Ngee-wolo-nga wa-le 344
Ngewo 344
Ngewo-Wa 344
Ngi 521
Ngunung-ngunnut 191
Ngurunderi 143, 353
Ngurvilu 344
Ngworekara 344
Nhangs 344
Ni 298, 344
Nia-Jara 48
Nibelungen 344
Nibelungenlied 198
Nibelungs 160, 344, 431
Niblungs 344
Nicahtagah 509
Nicaragua 127, 128, 162, 244, 302, 311, 321, 324, 395, 451, 463, 500, 523
Nice 79, 253, 345
Nicerphoros 61
Nichan 344
Nichomachus 299
Nicippe 47, 81, 218, 344, 377
Nick 350
Nicodromus 345
Nicor 344
Nicostrata 116
Nicostratus 344
Nid 209
Nida 432
Nidaba 236, 332, 344
Niddhogge 344
Nidhema 47
Nidhod 338, 344, 516
Nidhogg 344, 400
Nidhoggr 344
Nidhug 344
Nidi 160
Nidim 161
Nidjung 209
Nidra 344
Nifelheim 345
Nifelhel 344
Nif'fleheim 345
Nifhel 345
Niflheim 101, 165, 345
Nifl-heim 191, 193, 211, 229, 321, 333, 345, 496, 516, 517
Niflungar 344
Niflungs 344
Nig 350
Niger 355, 368, 423
Nigeria 34, 84, 120, 353, 358, 362, 507, 523
Nighhoggr 344
Night 177, 345, 381
night 27, 68, 77, 82, 105, 116, 118, 125, 176, 177, 204, 208, 217, 218, 246, 295, 327, 345, 351, 381, 401, 405, 460, 518
nightingale 18, 244
nightmares 159; *see also* dreams
Nigi-mi-tama 64, 260, 445
Nigir 13
Nigishzida 58
Niheu 260
Nihi-nahe 347
Nihongi 39, 40, 42, 246, 247, 255, 280, 347, 464, 482
Nii-no-ama 355
Nijuhachi-bushu 345
Nik 350
Nikasha 279, 345, 429
Nike 79, 101, 275, 345, 370, 441, 496
Nikkal 345, 514
Nikko-bosatsu 199
Nila Tara 454
Nilakantha 281, 345, 427
Nilavarahi 491
Nila-Vastra 90
Nile 25, 59, 60, 63, 169, 203, 204, 223, 239, 253, 269, 291, 317, 341, 345, 367, 382, 415, 421, 456, 465
Nimgigri 13
Nimgirgirri 13
Nimrod 8, 345
Nimsimug 161, 345
Nimue 500
Nimurta 348
Nina 28, 133, 161, 334, 346, 509
Nina Stahu 336
Ninagal 161
Ninagentue 339
Ninanna 238, 348
Ninatta and Kulitta 346
Ninazu 170, 346, 348
Ninbubu 161
Nindu 238
Nindubarra 161
Nindulla 346
Nindurra 167
Nine Heroes 225, 439, 519
Nine Songs 221, 346, 478, 519, 520
Nineb 345
Ninedinna 346
Nineishizda 346
Ninella 142
Ninetta 346
Nineveh 242, 346
Ningal 71, 236, 334, 346, 348, 432
Ningirda 170
Ningirsu 94, 241, 346, 348
Ningishzida 170, 346, 451
Ningizzida 14, 73
Ningursu 348
Ningyo 346
Ninharsag 346
Ninhursag 49, 71, 93, 95, 142, 144, 152, 167, 168, 198, 238, 334, 339, 346, 347, 348
Niniane 500
Ninib 14
Nin-ib 14, 345
Ninib 94, 346, 348, 402
Ninigi 40, 41, 43, 217, 220, 221, 223, 241, 265, 281, 346, 355, 361, 420, 450
Ninigiku 161, 347
Ninigikug 161
Ninigi-no-mikoto 346
Ninildu 161, 347
Nininni 348
Ninisinna 236, 346
Ninkarrak 14, 58
Nin-karrak 184, 198, 347
Ninkarrak 242, 346, 347
Ninkarraka 347
Nin-kar-zi-da 242
Ninkasi 242, 346, 347
Nin-kharak 347
Nin-khar-sagga 242
Ninkhursag 346
Nin-Khursag 346
Nin-Ki 347
Ninki 93, 142, 161, 167, 198, 238, 309, 346, 347, 348
Ninkilim 348
Ninkurra 161, 167, 348, 486
Ninkurru 346
Nin-lil 14
Ninlil 55, 95, 168, 207, 242, 301, 346, 347, 487
Ninlilla 347
Ninma 348
Ninmah 71, 191, 300, 334, 346, 347, 348
Ninmu 167, 346, 347, 348
Ninmug 236, 295
Ninocolla 339
Ninsar 73, 161, 167, 348, 486
Ninshubur 236
Nin-si-anna 242
Ninsinna 238, 348
Ninsubur 234, 348
Ninsun 158, 190, 191, 348
Ninsu-Utud 346, 348
Ninth Division 3, 348
Ninth Hour 3
ninth wave 45
Ninti 348
Nintil 346, 348
Nintoku 233
Nintu 95, 167, 242, 334, 346, 347, 348
Nintud 95, 238, 348
Nintue 71
Ninurash 348
Ninurta 94, 168, 198, 280, 342, 345, 346, 347, 348, 524
Ninus 419
Ninzadim 161
Nio 348, 425, 524
Niobe 18, 47, 49, 62, 67, 113, 115, 127, 152, 243, 290, 316, 339, 349, 376, 377, 383, 415, 453, 457, 480, 523
Niord 211, 350, 434
Niparaya 349, 395
Nipin and Pipoun 349
Niping 101
Nipingr 160
Nipinoukhe and Pipounoukhe 349
Nippur 71, 168, 347
Niquiran 162, 463
Nirba 349
Nireus 37, 115, 169, 349
Nirgalu 342
Nirgundi 428
Nirig 345
Nirrita 349, 398, 512
Nirriti 257, 293, 349, 398, 512
Nirritti 443
Nirruti 349
Nirvana 45, 46, 84, 102, 103, 324, 349
Nisaba 73, 332, 346, 347, 349
Nishatha 349
Nisis 349
Nisroch 349
Nisr-uku 349
Nistigri 237
Nisumbha 128, 158, 257, 349
Nisus 240, 349
Nit 147, 341, 353, 413
Nitatui 349, 404
Nithog 294
Nithogg 344
Niti 147
Nit-tep-Ament 425
Nitwatakawaca 349
Nitya-Kali 257
Niu 43
Niu Y'ou 195
Niu-t'ou 350
Niu-Y'ou 350
Nivika 266
Nivlheim 345
Niwatakawaca 69
Nixe 350
Nixie 350, 352
Nixy 350
Njord 22, 181, 343, 350, 483
Njorth 350
N'Kokon 521
Nkosi Yama'kosi 350
Nkulnkulu 484
No dramas 41
Noah 74, 119, 133, 152, 312, 338, 350, 351
Noatun 350
nobility 329
Noble Goddess 285
Nodens 292
Nodotus 350
Noesarnak 350
Nogamain 350
Nogat 338
Nogomain 350
Nohochacyu 487
Nohochacyum 204, 350, 486
Nohoyum 507
Nokel 350
Noken 352
Nokomis 335, 350
Nome-Lists 413
nomes 49, 394
nomi 503
Nommo 350, 351
Nomus 69
Nona 178, 351
Noncomala 351
Nono 351
No-no-kami 265
noose 99
Noose of Varuna 492
Nootaikok 351
Nopaltzin 509
Nor 351
Nordi 506
Nordic 62
Nordre 351
Nordri 83, 160, 321, 351, 441
Nordur 350
Norea 351
Nori 101
Noricum 17
Norine 343
Norms 495
Nornir 351
Norns 36, 153, 183, 351, 516
Norse mythology 4, 19, 22, 23, 25, 29, 36, 38, 50, 52, 53, 72, 74, 82, 83, 90, 94, 95, 97, 98, 101, 102, 104, 139, 140, 145, 153, 156, 159, 161, 164, 165, 166, 177, 178, 179, 180, 181, 183, 184, 190, 191, 192, 196, 197, 198, 199, 206, 209, 210, 211, 214, 215, 220, 221, 224, 226, 229, 230, 231, 232, 241, 245, 252, 254, 262, 267, 291, 293, 294, 297, 300, 315, 318, 321, 326, 329, 330, 331, 333, 335, 337, 338, 340, 343, 344, 345, 350, 351, 357, 358, 359, 361, 362, 364, 366, 368, 397, 399, 400, 402, 404, 406, 407, 415, 421, 430, 431, 432, 435, 436, 437, 441, 443, 444, 446, 447, 448, 453, 462, 463, 464, 465, 480, 482, 485, 490, 491, 494, 496, 501, 506, 516, 517
North 86, 249, 429, 456, 460, 507
North America 6, 12, 15, 25, 27, 42, 51, 53, 54, 55, 59, 62, 66, 72, 74, 78, 80, 81, 84, 95, 98, 103, 113, 117, 120, 126, 127,

129, 133, 135, 139, 140, 144, 147, 154, 156, 160, 161, 164, 167, 172, 173, 183, 184, 185, 189, 190, 191, 192, 193, 197, 199, 200, 201, 202, 203, 206, 207, 211, 213, 214, 216, 218, 220, 221, 222, 224, 228, 231, 232, 234, 236, 239, 241, 243, 246, 252, 255, 261, 263, 264, 265, 266, 267, 271, 272, 273, 275, 278, 279, 295, 298, 303, 304, 311, 314, 315, 316, 320, 321, 322, 323, 324, 325, 327, 328, 329, 331, 334, 335, 336, 339, 344, 349, 353, 357, 360, 361, 362, 363, 365, 366, 369, 371, 376, 384, 388, 392, 394, 397, 420, 423, 424, 426, 428, 432, 435, 438, 446, 454, 456, 457, 463, 464, 466, 468, 470, 471, 472, 475, 476, 481, 482, 483, 484, 486, 501, 504, 505, 506, 513, 515, 517, 518, 521
North Pacific Coast People 501
North Pole 123
North Sea 340
North Star 232, 473
North Wind 64, 104, 394
Northern Ireland 112
Northern Island 112
northwest winds 92
Norve 351
Norvi 351
Norway 183, 435, 440; *see also* Norse mythology
nose 123, 179, 510
Nothing Lacking 481
Notos 351
Nott 5, 82, 139, 240, 343, 351, 481
Notus 76, 125, 133, 169, 174, 182, 351, 522
Nous 21, 351
Novgorod 380
Nowutset 446
Nox 170, 327, 328, 341, 351, 363, 401, 461
Nrile 507
Nu 4, 298, 352, 353
Nu Kua 352
Nu Wa Naing Naing 352
Nu Ying 225, 346
Nuada 30, 134, 139, 151, 179, 292, 296, 352, 358, 416
Nuada Argentlam 352
Nuadha Airgedlamh 352
Nuadhu 352
Nuba 352
Nubia 43, 55, 59, 98, 298, 376
Nubti 352
Nubu 351
Nud 292
Nud Nodens 352
Nudd 292
Nudimmud 63, 161, 167, 352
Nuga 352
Nugal 352
Nugu 240
Nui 359
Nuit 49, 359
Nujalik 352
Nuktelios 152
Nu-Kua 170, 352
Nukuchyumchakob 350, 520
Nuliajuk 352
Num 162, 252, 352, 460
Numa Pompilius 163
Numbakulla 352, 353
Numitor 10
Numi-torem 352
Nummo 350
Numokh Mukana 353
Numphe 354
Num-torem 352
Numushda 310
Nun 81, 97, 269, 359, 391, 396; and Naunet 353
Nunam-shua 353, 418
Nunbarshegunu 347
Nunbirdu 168
Nunet 353
Nunne Chaha 172
Nunu 269
Nunyunuwi 353
Nurelli 89, 353
Nurra 161
Nurrundere 89, 143, 353
nursing 95, 407
Nurundere 353
Nurunderi 353
Nusku 184, 353, 432
Nusmatlizaix 353
Nut 4, 81, 168, 243, 298, 340, 341, 342, 352, 353, 367, 394, 396, 421, 428, 437, 456
Nutapa 160
Nutar 343
Nuth 298
Nu'umea 353
Nuzuchi 265
Nu-zuchi 265
Nvard 64
Nxy 22
Nyakyusa 283
Nyalic 353
Nyalitch 9, 353
Nyambe 314, 338, 353, 354
Nyambi 353
Nyame 8, 50, 72, 101, 354, 364, 423, 453
Nyami 354
Nyamia 354
Nyamia Ama 354
Nyankoipon 354
Nyankopon 50, 354, 507
Nyankopong 354
Nyasaye 354
Nyceteus 57, 354
Nycteus 113, 387
Nyctimene 170, 354
Nyctimus 297
Nyi 160
Nyikang 354
Nyiko 354
Nyktelios 152
nymphs 17, 18, 19, 20, 23, 25, 42, 49, 63, 66, 67, 69, 70, 76, 77, 79, 88, 101, 103, 113, 114, 116, 117, 118, 119, 125, 130, 132, 136, 137, 138, 143, 157, 162, 163, 176, 177, 194, 197, 210, 213, 214, 224, 231, 239, 250, 279, 280, 287, 291, 300, 318, 324, 333, 336, 341, 342, 349, 354, 356, 364, 376, 388, 391, 468, 485
Nyo-i-rin Kannon 261
Nyo-i-rin Kwan-on 277
Nyokon 293, 354
Nyr 160
Nysa 239, 321, 415, 431
Nyt 341
Nyunyari 504
Nyx 22, 31, 118, 122, 156, 177, 211, 216, 230, 266, 351
Nyyrikki 453
Nzambi 354
Nzame 102, 354
Nzamgi 354

Oado 355
Oahu 217, 259, 264, 326
oak tree 7, 94, 102, 139, 157, 164, 194, 202, 253, 379, 381, 405
Oannes 60, 139, 161, 355, 419
Oarion 365
Oba 355, 362, 368, 423
Oba Do 366
Oba Jumu 366
Obagat 355, 362
Obasi Nsi 243
Obassi 355
Obassi Osaw 355
Obatala 355, 356, 358, 362, 365
Obe 356
Obeah 356
obedience 45, 439
Oberon 36, 52
Obi 356
Objiwa 252
obolus 123
Obosom 7
Obriareus 18, 19, 356
Obsidian Butterfly 471
Obsidian Knife Butterfly 508
Obtala 358, 365, 423
Ocaleia 6, 12, 25, 121, 356, 390
ocean 16, 19, 30, 36, 42, 47, 49, 82, 85, 97, 99, 103, 108, 111, 119, 155, 157, 160, 161, 165, 175, 178, 185, 188, 192, 197, 207, 217, 229, 232, 246, 254, 261, 270, 282, 287, 292, 304, 305, 312, 322, 342, 343, 344, 349, 355, 356, 361, 362, 371, 383, 387, 399, 406, 417, 426, 445, 452, 461, 462, 466, 468, 472, 473, 491, 501, 506, 511, 515, 518, 520, 521
Ocean, Churning of 63
Ocean of Chaos 479
Ocean of Milk 306, 373, 421
Oceania 201
Oceanic mythology 144, 178, 217, 296, 312, 332, 337, 385, 405, 448, 456, 479, 503
Oceanides 356
Oceanids 11, 23, 38, 61, 74, 113, 118, 127, 129, 131, 169, 174, 190, 205, 212, 275, 316, 354, 356, 370, 379, 380, 385, 404, 461, 521
Oceanus 11, 18, 38, 47, 64, 66, 74, 76, 80, 112, 113, 114, 118, 119, 131, 134, 135, 152, 155, 171, 174, 175, 184, 190, 202, 210, 212, 229, 231, 233, 235, 236, 243, 284, 300, 316, 317, 320, 333, 341, 342, 345, 356, 375, 378, 379, 381, 385, 387, 391, 404, 412, 416, 431, 438, 440, 441, 460, 461
Ocelotl 288, 470
Ocelotonatiuh 288
Ocepta 356
Ochimus 356
Ochocalo 339
Ochomenus 165
Ochossi 356
Ochren 12
Ocirvani and Tsagan-Sukuty 356
Ockabewis 357
Ocrisia 212, 357, 478
Octli 357
octopus 178, 261, 405
Ocypete 20, 356, 357
Ocypetes 205, 385
Ocyrrhoe 62, 123
Od 181, 357
Oddua 360
Odem 13
Oder 357
Odherir 283, 358
Odhinn 357
Odhroerir 358
Od-Hroerir 358
Odin 22, 25, 39, 72, 74, 82, 90, 91, 94, 97, 98, 102, 104, 105, 156, 159, 166, 173, 179, 180, 181, 183, 184, 188, 189, 190, 192, 193, 196, 198, 199, 204, 209, 210, 211, 213, 220, 224, 230, 232, 241, 245, 247, 252, 253, 283, 294, 296, 321, 322, 326, 330, 350, 352, 357, 397, 402, 404, 406, 407, 408, 415, 416, 430, 432, 435, 436, 463, 480, 481, 483, 487, 490, 492, 494, 496, 501, 506, 516, 517, 523
Odnir 357
Odolumare 360
Odr 181, 357
Odraerir 94, 104, 229, 357, 358
Odrerer 358
Odrorir 199, 358
Odrovir 358
Odudua 23, 358
Oduduwa 356, 358, 362, 365, 366
Odu-Duwa 358
Odur 357
Odysseus 11, 21, 27, 31, 56, 68, 83, 114, 130, 175, 209, 239, 241, 284, 339, 358, 370, 378, 387, 432, 433, 457, 461, 483
The Odyssey 358
Oeager 67
Oeagrus 113
Oebalus 65, 93, 194, 218, 231, 358
Oechalia 175
Oedipus 17, 57, 170, 173, 175, 252, 284, 358, 359, 378, 386, 438
Oegir 359
Oegishailm 359
Oenamaus 359, 377, 378
Oenarus 68
Oeneus 35, 38, 66, 70, 114, 145, 153, 194, 213, 286, 359, 378, 387, 440, 480
Oenghus 54
Oengus 54, 160
Oenomaus 35, 66, 114, 164, 176, 205, 218, 290, 359, 440
Oenone 18, 19, 359, 374, 404
Oenopia 18, 19
Oenopion 68, 152, 359, 365
Oeonus 316
o’erings 456
Og 402
Ogdoad 43, 44, 208, 226, 359, 408
Ogetsu-hime-no-kami 42, 246, 260, 482
Oggun 360
Ogham 360
Oglala 272, 504
Ogma 103, 139, 155, 173, 199, 360
Ogmios 360
Ogo 46
Ogoni 25, 360
Ogoun 172, 360
ogres 30, 204, 340, 371
Ogrigwabibikwa 360
Ogue 362
Ogun 24, 105, 195, 197, 355, 356, 358, 360, 362, 423, 515
Ogyges 56, 184, 360, 461
Ogygus 152
Ogyren 267
Ogyrvan 360
Ohdowas 184, 252, 360
ohia tree 217
ohia-lehua forest 217
Ohio 6
Oh-Kuninushi 361
Oh-Magatsumi 361, 445
Oho-hiru-me No Muchi 41

www.ebook3000.com

Oho-iwa Dai-myo-jin 360, 450
Oho-Kuni-Nushi-No-Kami 361
Ohonamochi 450
Oho-to mahe no Mikoto 39
Oho-to nochi no Mikoto 39
Oho-wata-tsu-mi 278, 355
Oho-yama-tsu-mi 278, 355
Ohoyo Osh Chishba 360
Ohramazd 525
Ohrmazd 28, 360
Ohthia 57
Oh-yama-tsumi 182
Oia 250
Oidipodes 358
Oidipous 358
Oileus 67, 360
Oinn 160
Oinone 359
Oisin 179
Oiwa Daimyojin 360
Ojibwas 334, 392, 506
Ojibway 54, 335
Ojin, Emperor 200
Okami-no-kami 282, 360
Oke 362
Oke Hede 360
Okeanos 356
Okikurumi 125, 361
Oki-Tsu-Hiko 237, 361, 475
Oki-Tsu-Hime 237, 361, 475
Okitsushima-hime-no-mikoto 449
Okkvinkalfa 209
Oklatabashih 361
Oko 361
Okolner 361
Okuninushi 282, 361
O-Kuni-Nushi 361
Okuni-nushi 518
Okuni-Nushino 450
Okuni-Nushino-Mikoto 43, 150, 260, 275, 282, 347, 361, 426, 442, 450, 510, 511
Oku-Thor 361
Ola'li 133, 134
old age 51, 166, 352
Old Book of Divinity 99
Old Coyote 481
Old God 226
Old Goddess 471
Old Man 336
Old Man of the Sea 342, 383, 391
Old Man of the Tide 355, 426
old math 312
Old Mother 234, 269
Old Testament 8, 16, 148, 201, 402, 413, 492, 510
Old Woman 234
Old Woman Earth 72
Old Woman's Grandchild 98
Olelbis 362
Olelpanti 362
Olenias 114, 359
Olenus 76, 212, 362
Oler 362
Olifat 296, 362
olive tree 72, 80
olives 289
Oller 358, 362, 482
Ollerus 482
Olmec 226
Olo 452
Oloddumare 362
Olode 437
Olodumare 172, 233, 356, 358, 362, 365
Olofat 362
Olofi 362
Olofin-Orun 362
Olokun 24, 356, 362, 366, 515
Ol-Okun 362
Ololupe 293
Olo-pue 293
Olorun 362, 366
Olrun 501
Olu-Igbo 362
Oluksak 362
Olumbe 362
Olus 172
Olympia, Gates of 213
Olympia, King of 131
Olympiad 80
Olympian creation myth 175, 184
Olympians 11, 61, 62, 66, 119, 135, 153, 462
Olympic Games 131, 222
Olympus, Mount 19, 25, 35, 116, 146, 175, 187, 190, 195, 213, 216, 222, 245, 319, 327, 363, 364, 371, 376, 378, 391, 419, 455, 480, 522, 523
Om 416
Om mani padme hum 268
Omacatl 363, 460
Omaha 504
Omara 354
Omecihuatl 114, 460, 508
Omeciuatl 240, 363, 469, 470
Omeciutal 471
Omecutli-Omeciuatl 395
omelets 31
Ometecuhtli 114, 363, 469
Ometecutli 395, 470, 471; and Omeciuatl 240, 363
Ometeotl 227, 363, 460, 508
Ometeuctli 363
Ometochtli 118
Omeyocan 125, 363
Omi 357
Omicle 30, 82
Omidu-nu-no-kami 282
Omi-tsu-nu 363
Omiwa 361, 442
omnipotence 47, 135, 181
omniscience 25, 39
Omohi-kane no kami 260
Omorca 466
Omorka 363
Omoroka 363, 466
Omo-taru no Mikoto 39
Omphale 35, 213, 286, 363
Omumborombonga 363
Omumbo-Rombonga 363
On 82, 355, 358
Ona 34
Onamuji 361, 450
Onar 50
Onas 266
Onatah 350, 363
Onatha 164, 363
One 148
One Possessing Dung 285
One, the Maker of Mankind 455
One Who Leans Out 271
One with Evasive Eyes 357
One with Flaming Eyes 91, 357
One-eyed Goddess of Wisdom 164
Oneiroi 118, 156, 170, 328, 352, 363
Oneneus 379
One-reed Quetzalcoatl 395
Oneus 363
Oni 146, 166, 262, 363, 396, 426, 458
Onlar 129
Onnes 355
Onnophris 364, 367, 484
Ono 79, 201, 280, 294, 364, 405, 452
Onogoro 246, 247, 479
Onondaga 154
Onophris 364, 367
Onoruame 364
Onouris 54
Onuphis 364
Onuris 54, 238
Onyame 354, 364
Onyankopon 354
Onyankopong 354
Oodeypoor 188
Ooyarrauyamitok 364
Ope 364
Opener of the Ways 60, 506
Opet 455
Ophannim 53
Ophiomorphus 65, 222, 231, 364
Ophion 122, 175, 364
Ophios 268
Ophites 14, 65, 75, 83, 230
Ophois 60, 268
Ophois Wepwawet 60
Ophs 387
Opis 364, 365, 403
Opita 364
Opo 364
Opochtli 364
Opo-kuni-nusi 449, 464
Opo-yama-tu-mi-no-kami 265, 282
Oppositres 216
Ops 132, 136, 164, 364, 403, 415, 418
Optimus Maximus 253
Opus 6, 391
or Soko-no-kuni 260
Oracle of Ammon 52
oracles 40, 92, 286, 366; *see also* Delphic Oracle
Oranos 351
Oranyan 358
oration 53
Orboda 198
Orchamus 131, 211, 290
orchards 387
Orchomenan 67
Orchomenus 66, 72, 118, 127, 133, 202, 231, 314, 364, 382, 403, 433
Orcus 153, 201, 352, 385
order 381, 460
Oreades 354, 364
Oreads 162, 364
Orehu 266, 364
Oreithyia 104, 113, 126, 130, 174, 201, 364, 381, 390, 522
Orenda 365
Orendil 83
Orestes 20, 23, 128, 165, 173, 240, 287, 365, 379, 463
organizer 261
organs 56
Orgelmir 517
Ori 160
Original Land 296
Orin-Murt 365
Orinoco People 40, 231, 392
Orinoco River 266
Orion 9, 70, 83, 117, 151, 210, 229, 230, 318, 359, 365, 385, 485
Orisha-ijaye 355
Orisha-Nla 362
Orishanla 365
Orisha-ogiyan 355
Orisha-Oko 362
Orisha-popo 355
Orishas 172, 358, 360, 362, 365
Orish-nla 172, 355, 356, 365, 366
Orish-oke 365
Orish-Oko 355, 365
Orissa 196
Orithyia 104
Orko 366
Ormazd 28, 45, 48, 180, 181, 438, 515
Ormenos 457
Ormet 366
Ormizd 65
Ormuz 28
Ormuzd 28, 360
Ornytion 192, 366, 382, 433, 463
Oro 366, 452
Orofat 362
Orokannar 40
Oromazez 28
Oromila 366
Oromuco 368
Orongo 405
Orotal 88
orphans 36
Orphe 72
Orpheus 17, 62, 67, 69, 113, 119, 174, 243, 250, 292, 366
Orphics 22, 122, 135, 381
Orphne 11, 72, 366
Orry 368
Orsedice 129
Orseis 19, 20, 21, 211, 366
Orsilochus 38, 366
Orsinome 382
Ort 366
Ortheis 19, 21, 156, 452, 509
Orthus 162, 438, 480
Ortygia 66, 114
Orula 362
Orumbe 362
Orungan 356
Orunjan 24
Orunmila 176, 233, 365, 366
Orun-Mi-La 366
Orvandel 83, 406, 434
Orvandil 197
Osage 211, 222, 322, 475, 504
Osanobua 362
Osanyin 366
Oscar 179
Oschun 366, 368
Oshadagea 218, 366
Oshadhi-pati 436
Oshadi-Pati 366
Oshan 366
Oshosi 362, 367
Oshun 362, 366, 423
Osiris 4, 5, 17, 22, 23, 40, 44, 45, 48, 49, 58, 59, 60, 61, 62, 64, 67, 70, 71, 81, 88, 97, 118, 152, 153, 154, 168, 172, 189, 204, 206, 210, 211, 212, 222, 235, 243, 256, 268, 269, 298, 318, 319, 340, 341, 342, 349, 353, 364, 367, 368, 377, 379, 385, 394, 396, 417, 418, 419, 420, 421, 422, 425, 428, 441, 449, 451, 458, 460, 464, 480, 483, 484, 485, 505, 506
Osiris-Aah 367
Osiris-Apis 61, 420
Osiris-Hapi 61
Osiris-Unnerfer 425
Oski 357
Osorapis 61
Osoronnophris 408
osprey 18
Ossa, Mount 367, 377
Ostra 161
ostrich 98
Osun 362, 366
O-sung 264
Ot 367
Otafuku 40
Oter 368
Otgon 365
Otherworld 98, 107, 299, 391, 403
Otherworld Tower of Initiation 68
Othin 294, 357, 524
Othinn 357
Othinus 357
Othrevir 358
Othroerir 358
Othur 357
Otkon 365
Otomi 114, 469, 481

Otontectli 114
Otontecutli 226, 227
Otos 82
Otr 52, 177, 368
Otrera 57, 66, 218, 368, 378
Otrere 66
Otshirvani 368
Ottar 98, 224, 368
Ottarr 368
Ottawa 324, 334
Otter 177, 368, 402
otters 50, 52, 224
Ottor 52
Otua 79
Otukut 521
Otus 37, 66, 169, 330, 368
Oulapatou 368
Oulomos 30, 368
Our Father 364, 420
Our Flayed Lord 508
Our Mother 244, 363
Our Woman 394
Ouranos 139, 183, 484
Ourea 122, 184, 387
Ouri 368
Ousoos 179, 230, 368
outrage 22
Ouvin 357
ouydn 201
Ovid 318, 356
Ovinnik 155, 368
O-Wata-Tsu-Mi 217, 223, 355, 426, 473
O-Wata-Tsumi 355
owl 79, 80, 103, 114, 124, 158, 237, 392
Owner 362
Owner of Heaven 362
Owner of Snow 217
Owner of the Days 28
Owner of the Sea 362, 366
ox 87, 140, 195
Ox-Face 123, 350
Ox-head 298, 317, 350, 507, 512
Oxlahun-ti-Ku 2
Oxlus 66, 368
Oxomoco 288, 363, 368, 384, 451, 509
Oxomuco 368
Oxyrhynchus 368
Oya 362, 368, 423
O-Yama-Tsu-Mi 347, 355, 420
oyise tree 120
Oyo 358
O-zer-chem-ma 310
Ozun 362, 368

Pa 369
Pa Ch'a 369
Pa Cha 123, 429
Pa Hsien 163, 369
Pa Kung 128, 163
Pacari 62, 369
Paccari Tampu 369
Paccari-Tambo 306
Pa-cha 369
Pachacamac 132, 239, 241, 306, 369, 497
Pacha-Camak 369
Pachamama 369
Pacha-Mama 369
Pacharurac 369
Pachayachachic 369
Pacific Coast People 103
Pacific Northwest 278
Pacific Region 28, 164, 234, 353
Pactolus 321
Padma 285, 369, 498
padma 372
Padma Dakinis 141
Padma Krotishaurima 369
Padma Krotishhaurima 422
Padma Sambhav 411
Padmaheruka 215, 369
Padma-pam 84, 369
Padmapami 84
Padmapani 84, 369
Padmasambhava 141
Padmavati 332
Padua 286, 461
Paean 62, 461
Paeon 57, 369, 440
Paghat 274
pagoda 102, 150
Pagoda 440
P'ags-Skyes-po 497
Pah 369, 468
Paha 216
Pahiaku-kahuoi 277
Pahlavi 22, 45, 53, 73, 180, 188, 207, 248, 270, 325, 400, 439, 495, 500, 521
Pahlavi Shahriver 45
Pahulu 369
Pai 369
Pai Hu 439
Pai Mu-tan 369
Paia 373, 399
pain 53
Painal 376
Pairikas 53, 157, 202, 370, 502, 514
Pais 202
Paisacha 384
Pakadringa 370, 396
Pakasasana 237
Pakhet 419
Pakheth 370
Pakhons 268
Pakht 370
Palaechthon 184, 370
Palaemon 67, 212, 239, 289, 316, 317, 370, 387
Palaimon 317
Palaiokastro 136
Palamon 317
Palatine, Mount 112
Pale One 90
Pale Red 158
Palenque 501
Pales 370, 458
Palestine 122
Pali 149
Palici 212, 370, 461
Palikoi 370
Palitana 511
Palladium 56, 146, 235, 370, 461
Pallanteum 176, 370
Pallantia 145, 176, 370, 405, 414
Pallas 76, 79, 80, 101, 113, 127, 135, 145, 174, 176, 190, 231, 275, 297, 345, 370, 379, 405, 419, 441, 469, 521
Pallas Athene 79, 236, 341, 370
Pallene 35
Pallor 56, 66, 145, 168, 171, 205, 370
palm nut 176, 233
palm tree 259
palm-shoots 319
Palmyra 87
Paltar 90
Palulop 38, 370, 405
Palulukon 273, 371
Pamola 193, 371
Pamphylus 19, 371
Pan 19, 20, 40, 88, 151, 157, 162, 176, 177, 182, 214, 300, 323, 364, 371, 390, 419, 431, 490
P'an Chin-Lien 371
P'an Kin-Lien 371
P'an Ku 371
P'an-T'ao 371
Panacea 72, 229, 231, 299, 371
Panaka 146
Panareus 205
Panathenaea 9, 52
Panch Buddhas 150
Panchajana 275, 371
Panchalas 280
Panchali 371
Pancha-muke 333
Panchamukhi-Maruti 427
Panchashirsha, Mount 307
Panchen Rimpoches 46
Panchika 146, 204, 248, 371
Pancratis 37
Pandara 45, 150, 371
Pandaravasani 371
Pandaravasini 84
Pandareus 18, 131, 319, 372, 522
Pandava 69, 490, 494, 498
Pandavas 90, 99, 100, 149, 150, 159, 249, 257, 264, 276, 280, 281, 301, 314, 372, 390, 415, 453, 499
Pandemos 61
Panderces 210, 372
Pandia 419
Pandion 170, 381, 389
Pandora 147, 169, 212, 372, 391, 393, 465, 523
Pandora's Box 80, 372
Pandrosos 372
Pandrosus 26, 372
Pandu 69, 77, 100, 159, 280, 300, 372, 409, 503
Pandu Princes 334
Panhellenius 372, 522
Pani 372
panic 341
Panis 146, 372
Pani-yasu-biko-no-kami 203
P-ankhi 458
Pannagas 332
Panopaeus 382
Panope 342, 372
Panopeus 20, 169
Panpati 186
panthers 24, 51, 128, 140, 151, 184
Pao Yu 519
Papa 59, 60, 79, 207, 217, 218, 224, 330, 344, 372, 399, 405, 452, 456, 471, 472, 476, 494, 506
Papa Giving Birth to Islands 207
Papago 206, 470, 471, 472, 515
Papa-hanau-moku 207
Papakolea 264
Papalguenna 309
Papa-tu-a-nuku 372, 373, 399
Paphia 61
Paphos 16, 61, 185, 287, 331, 393
Paphus 129
Paps of Anu 58
Papsukaal 242
Papsukal 373
Papsukkal 234, 348, 373, 451
Papukkal 234, 373
Papyrus of Nesi-Khensu 352
papyrus 44, 75, 87, 203, 408
Par 43, 373
Para 487
Paracletos 21, 351
Paradise 55, 86, 105, 121, 126, 143, 162, 234, 243, 249, 250, 291, 369, 405, 419
Parameshthin Prajapatya 25, 388
Parasara 415
Parashara 373, 502
Parashu 373
Parashur 498
Parashur Rama 69, 285, 373, 498
Parasu-Pani 99
Parasu-Rama 373, 498
Parasurama 498
Parasuraman 186, 373
Paravani 263, 373
Paravataksha 333
Parbati 148, 374
Parca 178, 328, 373
Parcae 177, 178, 327, 373
Pare 377
Parewhenua-mea 377
Parganya 374
Pariacaca 225, 373, 513
Pariae 373
Parijata tree 238, 258, 275, 281, 373, 415, 437
Parikshit 7, 374, 486
Parilia 370
Paris 10, 12, 23, 31, 36, 116, 145, 215, 359, 370, 374, 404
Parjanya 237, 374, 379, 380, 390, 437, 444, 492, 494
Parjanya-vata 374
Parnasavari 454
Parnassus 130
Parnassus, Mount 147, 333, 374, 393
Paros 35
parrots 59, 259
Parsva 301
Parthenia 78, 79, 374
Parthenon 80
Parthenopaeus 17, 38, 66, 451
Parthenope 11, 62, 433
Parthenos 70, 79
Partholan 374
Partholanians 92, 180, 374
Partholon 374
Parusha 392
Parvata 374
Parvati 50, 52, 77, 99, 148, 158, 185, 186, 187, 188, 247, 257, 259, 263, 278, 283, 317, 374, 375, 415, 427, 473, 474, 483
Parwati 148, 374
Pasa 48
Pashadhari 55, 513, 523
Pasht 93
Pashupa 427
Pashupati 119, 375, 427
Pashyanti 487
Pasi 492
Pasiphae 9, 18, 52, 68, 129, 137, 138, 147, 192, 210, 297, 323, 356, 375, 379, 380, 440, 508
Pasithea 25, 195, 230, 375, 461
Passalus 356, 375
passion 56
past 388
patures 62
Pasupata 375, 384, 428
Pasu-Pati 186
Pasupati 25, 375, 388, 406, 427
Patagonia 197
Patala 69, 77, 91, 140, 186, 187, 336, 375, 388, 409, 421, 489, 491, 493
Patalas 332, 375
Patecatl 375, 509
Path of the Fathers 512
Path of the Manes 512
Pathalavati 158
Pathana 266
Patok 255
Patol 34
patra 46
Patrae 70
Patricos 21, 351
Patroclus 6, 11, 12, 13, 31, 57, 167, 169, 318, 375, 387, 414, 440
Paulomi 238, 375
Paulomi-Vallabha 238, 375
Paut 352
Pav 25
Pavaka 25, 26
Pavamana 26
Pavana 494
Pavanarekha 157, 261, 481, 510
Pawnee 59, 120, 224, 228, 369, 423, 468
Pax 164, 240, 375, 385

www.ebook3000.com

Paya-aki-tu-piko-no-kami 207, 375
Pa-yama-to-no-kami 482
Payatamu 376
Payetome 376
Paynal 376
Paynalton 376
Paziuba palm 322
Pazuzu 203, 376
peace 143, 164, 240, 356, 366, 375, 422, 496, 500
Peach Tree of Immortality 412
Peach Tree of Life 518
peaches 246, 371
Peaches of Immortality 225, 279, 504
peacock 46, 67, 106, 148, 259, 263, 373
Peak of the Law 204
pearl goddesses 331
Pearl of Price 129
pearls 78, 143, 257, 263
peasants 23, 209, 262
peat 266
Pedaeus 10, 56, 376
Pedsi and Pehor 376
Pegae 229, 333, 376
Pegasos 376
Pegasus 96, 125, 127, 169, 218, 315, 376
Pegasus of the Wells 376
Pehrkon 379
Pei-chi Chen Chun 123
Peiras 67, 162, 176, 376
Peirene 74, 113, 194, 376
Peirithous 57, 157, 175, 218, 245, 287, 376, 387
Peisander 57, 219, 376
Peisidice 21, 51, 57, 115, 166, 174, 376, 440
Peisinoe 376
Peisistratus 57, 376, 440
Peisus 232
Peitho Suadela 61
Peitho 115, 349, 376, 383
Peking 449
Pekoi 376
Pelagia 61
Pelagon 75, 376, 379
Pelasgians 80, 122, 135, 152, 175, 266, 356, 376, 381, 394, 403, 460, 462
Pelasgus 67, 74, 175, 231, 297, 316, 349, 370, 376, 377, 436, 474, 480
Pele 26, 207, 218, 259, 260, 261, 277, 377
Pele of the Sacred Earth 377
Pele-ai-honua 377
Pele-honua-mea 377
Pele-Ulu 377
Peleus 10, 11, 12, 13, 18, 57, 67, 76, 166, 171, 250, 374, 377, 382, 386, 457
Pelew 272, 287, 355
Pelew Islands 233, 473
Pelias 16, 35, 51, 67, 192, 249, 341, 377, 390, 410, 430, 480, 522
Pelion, Mount 249, 367
Pelios 10
Pelopia 20, 51, 66, 137
Peloponnesus 10, 11, 19, 76, 169, 377
Pelops 18, 23, 35, 47, 67, 76, 81, 116, 128, 146, 152, 169, 175, 218, 287, 297, 344, 349, 359, 377, 378, 382, 385, 416, 434, 440, 441, 453, 457, 465, 474
Pelus 13, 219
Pemba 177, 306, 331, 354, 378, 501
Pembo 378
Pembu 378
Penardun 125
Penates 119, 138, 287, 378
Peneius 230, 378, 405, 461
Penelaus 76
Peneleos 67
Penelope 114, 174, 214, 241, 284, 314, 358, 371, 378, 379, 457
Peneus 378
Penglai 378
penis 225; *see also* phallus
Penobscot 193
Penthesileia 42, 66, 218, 368, 378
Pentheus 24, 88, 112, 162, 239, 378
Penus 213
Peopling Vine 478
Peparethus 68, 152, 378
Pephredo 195
Pepi 61, 201, 378
pepper 7
Per Uadjit 481
Perae 465
Percht 98
Perchta 98
Percote 130, 319
Perdix 138, 378
Peredur 14
Pereplut 378
Pereus 378
Perfect Ones 123
Perfect Order 45
perfume 185, 340, 421
Peri 378
Perialces 378
Periboea 31, 76, 82, 114, 170, 219, 314, 338, 359, 378, 379, 386, 457, 480
Periclymene 16, 67, 232, 297, 324, 379
Periclymenus 67, 379
Pericu 42, 349, 395
Perieres 21, 105, 115, 166, 194, 202, 218, 231, 290, 358, 379
Perigune 9, 379
Perikionios 152
Perileus 379
Perimede 114, 174, 316, 359, 379
Perimela 245, 379
Perimele 11, 16, 21, 35, 57, 115, 166, 173, 232, 379
Periopis 16, 232, 297, 318, 375, 379
Periphas 382
Periphetes 57, 133, 212, 379
Perit 379, 477
Perithous 112
Perkun 379
Perkuna Tete 379
Perkunas 379, 380
Perkunis 374, 379
Perkuns 379
Permessus 23
Pero 21, 65, 289, 378, 379, 451
Peron 380
Peroun 380
Perse 18, 76, 129, 210, 356, 375, 379
Persea Tree 63
Perseis 18, 356, 379
Persephassa 379
Persephone 14, 16, 17, 37, 72, 94, 97, 113, 131, 136, 146, 152, 194, 201, 208, 230, 274, 290, 291, 318, 376, 379, 391, 403, 419, 433, 438, 441, 520, 523
Perses 18, 52, 75, 130, 135, 174, 194, 208, 315, 356, 370, 375, 379, 380, 440
Perseus 6, 12, 20, 25, 35, 51, 52, 57, 80, 116, 127, 142, 151, 153, 165, 194, 298, 315, 376, 379, 380, 382, 386, 440, 458, 523
Persia 6, 7, 8, 13, 15, 16, 22, 25, 28, 32, 33, 34, 38, 45, 48, 50, 52, 53, 62, 65, 71, 73, 74, 76, 78, 83, 85, 86, 89, 98, 126, 131, 138, 139, 143, 144, 147, 157, 170, 176, 177, 179, 180, 181, 185, 187, 188, 190, 194, 201, 202, 204, 207, 211, 222, 223, 224, 226, 228, 248, 251, 265, 266, 269, 270, 273, 290, 300, 321, 325, 336, 338, 341, 344, 360, 370, 378, 400, 407, 410, 412, 413, 414, 415, 416, 417, 419, 431, 436, 438, 439, 455, 464, 468, 469, 474, 479, 487, 488, 491, 492, 494, 495, 500, 501, 514, 516, 520, 524, 525
Persika 380
Pertunda 380
Peru 61, 62, 123, 125, 132, 136, 138, 197, 207, 225, 239, 241, 270, 271, 279, 303, 304, 306, 344, 369, 373, 392, 404, 429, 443, 449, 465, 472, 485, 497, 513, 521
Peruda 214
Perun 144, 270, 287, 374, 380, 405, 440, 446, 492
Peseias 276, 380
Pesi 417
Pest god 144
Pesthi 380, 458
pestilence 28, 241, 382, 429, 484
Peter 249
Petesuchos 417
Petra 380, 417
petral 343
Petro 396
Petticoat of Blue Stones 120
Phae 380
Phaea 135
Phaeacians 66
Phaedra 9, 17, 52, 57, 68, 146, 192, 219, 297, 323, 375, 380
Phaenna 195
Phaenops 62
Phaestus 403
Phaethon 8, 20, 31, 64, 118, 169, 211, 286, 356, 380, 381, 405
Phaethusa 20, 286, 381
Phaeton 210
Phalaguna 428
Phaland 501
Phalerus 67, 381
Phalguna 276
phallus 108, 123, 126, 143, 210, 331, 373; *see also* penis
Phanes 22, 381
Phanes-Dionysus 381
Phanesphobe 403
Phangnalomang 252, 381, 429, 441
Phan-ku 122
Phanus 67, 68, 152, 381
Pharaoh 506
Pharmen-pa 225
Phasis 62
pheasant 43
Phebele 311
Phegeus 25
Pheme 381
Phenix 382
Pheonix 112
Pherae 16, 67
Pheres 16, 57, 67, 76, 171, 219, 232, 235, 249, 297, 319, 379, 381, 480
Pherusa 342, 381
Phibionites 24
Philae 484
Philammon 62
Philamon 127
Philandros 9
Philemon 94, 381
Philia 61
Philinoe 56, 96, 241, 381
Philippines 14, 34, 143, 154, 179, 235, 255, 271, 506
Philistia 52
Philo 328
Philo Byblos 30, 88, 122, 139, 273
Philoctetes 374
Philomela 170, 459
Philomelus 146, 231, 381
Philone 96
Philonoe 145, 218, 239, 286, 370, 440
Philyra 117, 123, 135, 381
Phineus 20, 25, 52, 112, 113, 165, 205, 232, 381, 382, 457, 522
Phlegethon 11, 131, 289, 382, 455
Phlegon 210
Phlegyas 66, 127, 133, 245, 382
Phlias 153
Phlogios 382
Phlogius 145
Phobe 75
Phobos 56, 66, 145, 168, 171, 205, 370, 382
Phocis 13, 21, 67, 118, 133, 145, 374
Phocus 13, 18, 112, 377, 382, 390, 391, 457, 463
Phoebe 20, 70, 80, 118, 135, 151, 175, 184, 289, 381, 382, 419
Phoebus 61, 62, 151, 229, 382
Phoebus Apollo 62
Phoenicia 13, 16, 17, 22, 25, 30, 35, 36, 37, 61, 73, 75, 76, 82, 86, 87, 88, 91, 93, 96, 97, 98, 122, 139, 164, 172, 174, 179, 190, 200, 230, 242, 243, 273, 282, 289, 317, 324, 342, 368, 382, 422, 434, 447, 453, 457, 522
Phoenix 11, 12, 16, 25, 76, 97, 165, 174, 178, 225, 317, 379, 381, 382, 457
Phoinix 382
Pholus 117
Phorbas 13, 67, 174, 220, 230, 240, 382, 383, 468, 474
Phorbus 114, 383
Phorcus 342
Phorcys 96, 119, 135, 162, 168, 174, 184, 194, 195, 216, 284, 315, 342, 356, 383, 387, 417
Phorkos 433
Phorkus 342
Phorkys 342
Phoronea 67
Phoroneus 19, 62, 64, 67, 115, 119, 136, 236, 316, 349, 383
Phosphorus 76
Phouka 392
Phra In Suen 427
Phra Narai 498
Phra Naret 285
Phra Noreai-Narayana 498
Phra 396
Phrixos 383
Phrixus 18, 67, 79, 121, 211, 239, 342, 381, 383, 389
Phrontis 121, 383
Phrygia 64, 69, 81, 88, 89, 93, 97, 133, 136, 138, 160, 235, 310, 321, 331, 403, 408, 419, 521
Phrygian Games 235
Phryxus 194, 383
Phtha 391
Phthia 21, 156, 211, 387, 507, 509
Phtia 62
Phuca Pwakas 392
Phyag-na-rdorje 489
Phyag-na-rin-chen 400
Phyderi 391
Phyi-Sgrub 512
Phylace 383
Phylacides 9

Phylacus 13, 35, 67, 118, 145, 152, 383
Phylas 76, 162
Phyleus 383
Phylisu 62
Phyllis 10, 146, 383
Phylodameia 143
Phylomache 10, 383
Physcoa 153
physicians 99, 149, 488
Phytalmios 152
Phyxios 383, 522
Pi Kan 475
Picus 177, 310, 384, 415, 439
Pidrai 384
Pidray 70, 384, 451
Pien-ch'eng 146, 384
Piench'eng 466
Piercer of the Deer 329, 406
Pierus 130, 164, 229
piety 89, 90
pigs 54, 65, 92, 110, 129, 136, 169, 223, 259, 353, 500
Piguerao 369
Piguero 62, 197
Pi-Hia Yuan-Kun 425
Pi-hsia 383
Pi-hsia-yuan-chun 383
Pi-hsia-yuan-chung-mu 478
pike 52
Piko-po-no-ninigi 346
Pilan 384
Pillan 124, 226, 384
pillars 14
Pillars of Heaven 94
Pillars of Hercules 213
Piltzintecutli 295, 368, 384, 472, 509
Piltzintecuhtli-Tonatiuh 384
P'i-Lu-Cha-Na 384, 488, 490
Pilumnus 384
Pinaka 384, 428
pine cone 317
pine tree 24, 81, 85, 171
Pi-neter-tauau 495
Pinga 384
Pingala 204
Pingo 74
P'ing-teng 466
P'ing-teng Tu-shi 146
P'ing-teng Tushi 384
Pinka 375, 384
Piorun 380
Pipes 214
Pipisao 253
Pipoun 349
Pirithous 150
Pirrhua 304
Pirrhua-Manco 306
Pisa 35, 114, 169, 218, 359, 378
Pisakas 384
Pisashas 264, 384
Pishachakis 384
Pishacha-Loka 293
Pishachas 262, 372, 384
Pishachi 384
Pishags 384
Pishumi 384
Pisidice 51
Pistis 21, 351, 384
Pistis Sophia 14, 83, 250, 384
Pistris 466
Pitamaha 105, 385
Pitane 22, 175
Pitaona 266
Pitar 385, 388
Pitazofi 339
Pitho 495
Pitri 388
Pitri-Loka 293
Pitripati 512
Pitris 141, 181, 385
Pitriyana 385, 512
Pittheus 22, 81, 218, 377, 385
Pixy 392
Piye-Tao 132
Pi-Yusha 48
Place of Blood 207
Place of Duality 363
Place of Fright 508
Place of the Eye 367
Place of the Sacred Fire 203
Place of Thorns 481
Place of Tlaloc 469
Placia 286
plague 111, 195, 225, 241, 334, 429
Plain of Idawold 232, 233
Plain of Two Mists 12
Plain to Heaven 41
plains 265
Plains of Ida 192
planet 319
planters 164
plants 45, 68, 110, 180, 182, 191, 207, 267, 302, 314, 348, 353, 478, 486; *see also* vegetation
Plat-eye 385
play-ball 509
Ple 262
Pleaides 466
Pleasant Voice 307
Pleaser of Brethren 394
pleasure 491
plebeians 151
Pleiad 359
Pleiades 55, 66, 80, 114, 117, 165, 168, 173, 228, 229, 302, 303, 319, 336, 365, 385, 404, 433, 440, 456
Pleione 23, 66, 80, 114, 133, 165, 172, 173, 216, 229, 302, 319, 365, 385, 440
Pleisthenes 23, 81, 130, 318
Plentiful-Food-August 41, 482
plenty *see* abundance
Pleuron 25, 218, 383, 385, 507
Plexippus 38, 175, 288, 381, 462
ploughers 90
ploughshare 90, 201
Plouton 146, 385
Ploutos 180, 385
plum-blossom 397, 420
Plural 71
Plutarch 243, 333
Pluto 153, 201, 208, 253, 366, 385, 420, 453
Plutodotes 152
Pluton 201, 385
Plutos 385
Plutus 146, 231, 350, 381, 385
P-neb-taui 448
Pni-yasu-bime-no-kami 203
Po 59, 177, 385, 399, 405, 407, 448, 452, 468
Po lao-ye 123
Podalirius 72, 123, 229, 231, 299
Podarces 389
Podarge 20, 91, 205, 385, 508, 522
Poeas 67, 385
Poem of Creation 304
Poenae 183
poets/poetry 24, 105, 107, 108, 116, 161, 170, 175, 177, 179, 199, 203, 220, 232, 267, 357, 413, 415, 437
Pohja 234, 271, 295, 385
Pohjoa 295
Pohjola 385
Po-i Ta-shi 277
poison 85, 140, 256, 319, 498
Po-kahi 217
Poko-ha-rua-te-po 200, 385, 399
Poland 144, 155, 281, 287, 288, 380
Pole Star 460
Polednica 386
poles 14
Polevik 289, 386
Polevoi 386
Polevoy 386
Polias 79
Pollux 9, 35, 116, 136, 153, 386, 523
Polotu 386
Poludnica 386
Poludnitsa 386
Polybotes 190, 219, 386, 469
Polybus 10, 56, 67, 170, 192, 297, 378, 386, 461
Polycaon 240, 320, 386
Polycaste 51, 57, 386, 440
Polydamas 10, 56, 297, 386, 461
Polydectes 12, 151, 380, 386
Polydeuces 49, 67, 116, 232, 250, 288, 382, 386
Polydeukes 116
Polydora 38, 57, 105, 130, 316, 318, 386, 438
Polydore 143, 157, 386
Polydorus 24, 83, 112, 205, 209, 219, 234, 239, 386, 419
Polyeidus 9, 96, 386
Polyhymnia 330, 386
Polymede 35, 83, 386
Polymela 13, 241, 377, 386
Polymele 162, 173, 386
Polymnestor 145, 209, 386
Polymnia 330, 386
Polyneices 17, 57, 173, 175, 252
Polynesia 3, 29, 38, 40, 59, 60, 64, 65, 78, 79, 81, 82, 83, 177, 200, 201, 207, 209, 211, 217, 218, 220, 224, 234, 235, 239, 255, 256, 258, 259, 260, 261, 262, 264, 265, 267, 271, 277, 280, 282, 284, 292, 293, 294, 295, 300, 307, 311, 312, 313, 324, 326, 330, 343, 344, 353, 364, 366, 372, 373, 377, 385, 386, 397, 399, 400, 405, 406, 407, 448, 450, 452, 454, 455, 456, 460, 467, 468, 471, 472, 476, 478, 481, 482, 484, 485, 488, 492, 493, 506
Polynesia Society Islands 234
Polynices 386
Polypheides 130
Polyphemus 12, 112, 137, 185, 241, 383, 387, 463
Polyphontes 17, 21, 287, 387
Polypoetes 62, 156, 218
Polypoets 376, 387
Polytechnus 18
Polyxena 12, 116, 145, 374
Polyxo 57, 145, 387
Poma 134
pomegranate 24, 146, 201, 213, 253, 379
Pomo People 144, 228, 278, 303, 311, 397
Pomona 180, 384, 387
Pompeii 242
Pon Okikurumi 125, 361
Ponda 160, 463
Pondo 476
ponds 254, 322
Pontia 61
Pontos 387
Pontus 119, 122, 184, 201, 342, 383, 387, 461
Pookas 424
poplar tree 20, 286, 381
Popoluca 121
Popol-Vuh 387
poppies 61
poppy seeds 119
Popul Vuh 502, 508
Poro 159
Porphyrion 35, 190, 219, 286, 387, 469
porpoises 330
Portal of Life 408
Porthaon 27, 35, 114, 146, 202, 359, 387, 440
ports 316, 370
Portunus 316, 370, 387
Porus 316, 387
Poseidon 11, 13, 18, 20, 21, 24, 31, 37, 38, 47, 48, 49, 52, 56, 57, 61, 66, 67, 69, 74, 76, 80, 96, 97, 104, 112, 114, 115, 116, 117, 119, 126, 127, 128, 130, 133, 135, 136, 137, 165, 169, 170, 174, 175, 190, 192, 194, 201, 205, 212, 213, 215, 222, 230, 232, 236, 240, 286, 287, 289, 291, 297, 315, 316, 323, 324, 327, 331, 338, 341, 342, 349, 354, 356, 359, 360, 365, 368, 369, 376, 377, 378, 379, 382, 383, 386, 387, 388, 390, 391, 403, 405, 416, 417, 418, 457, 461, 462, 463, 474, 480, 492, 522
Poshaiyangkyo 388
Possessing Truth 415
Postverta 56, 116, 388
Postvorta 388
Potameides 388
Potamids 333, 388
Potawatomi 127, 334, 335
Po-ti 423
Potok-Mikhailo-Ivanovich 104
Potos 30, 82, 122
potters 161
Pourushas 203
Pourushaspa 524
Pou-T'ai 320
Pou-tai 224
poverty 51, 102
power 242, 275, 292
Power Above 343
Power of Devoring Time 301
Powerful Goddess 313
Prabhasa 493
Prachetas 310
Pradyuma 314
Pradyumna 258, 259, 276, 388, 400, 433
Pragiyotisha 336
Prah Prohm 105
Prahalada 497
Prahlada 91, 140, 219, 336, 375, 388, 491
Praise of Men 25
Prajapati 25, 77, 105, 141, 219, 264, 281, 313, 388, 399, 406, 413, 487, 497, 499
Prajapatis 308, 389, 404, 493
Prajna 389
Prajnaparamita 334, 389, 413, 414
Prakriti 389, 393, 422
Pralamba 389
Pralaya 258
Pramadvara 389
Pramantha 389
Pramati 25
Pramlocha 63, 310, 389
Pramloka 389
Pramzimas 389
Prana 494
Pranayama 494
Prasena 447
Prasetas 492
Prasni 389
Prasuti 141, 389
Pratyusha 493
Pravuil 332
Praxidice 389

www.ebook3000.com

6. Recharge in the universe. Feel your bones and your arms are hollow. Fill and compact them with Chi.
7. Scoop the Universal Chi and pour it down over your crown and all the way down, down to the Middle Tan Tien.



Fig. 3.50
Recharge in the Universe, scoop and pour the Chi down to the Middle Tan Tien (Heart Center).

Middle Tan Tien - Heart Center - Conscious Mind

1. Move your hands all the way down to your heart center at the mid-sternum. Touch. Focus on the point opposite the heart, T5/T6, on the spine. Fingers 'long', Chi penetrates into your thymus gland. Light – golden light – penetrates into your thymus. Feel the Chi penetrate through your heart all the way through T5/T6 to the universe behind. 'Tan Tien and the Universe' also feel your Chi Fingers penetrate into the bone and bone marrow and spread out into your rib cage.



Fig 3.51 *Golden light enters the heart, thymus, bones and marrow; feel it penetrate to the universe at the rear.*

Praxithea 130, 297, 364, 389, 522
Praying Mantis 112
Precht 98
pregnancy 103
Preng-Ta-Ma 400
Presbon 121, 131, 383, 389
Preta 184
Preta-Loka 389
Preta-Raja 389, 512
pretas 120
Pretas 146, 389
Pre-Vedic 422
Prez-Poludnica 386
Priam 10, 12, 42, 57, 66, 116, 130, 134, 145, 157, 209, 215, 219, 232, 286, 287, 297, 374, 386, 389, 469
Priamus 463
Priapian Diana 70
Priapos 389
Priapus 61, 89, 331, 389, 390
Priasus 112, 382
priestesses 36
priests 6, 14, 24, 103, 108
Primal Man 392
Prime Man of the East 420
Primeval Being 498
Primeval Man 29
Primigenia 180
Primordial Hill 359
Primordial Ocean 356, 437
Prince Cataract 450
Prince Fire-Subside 217
Prince Mighty Power 41, 449
Prince Millet 224
Princess 508
Priparchis 281
Prisca 495
Prishni 390
Prisni 311, 390, 406
Pritha 100, 263, 280, 390, 444
Prithi 390
Prithiva 184, 293, 374, 390, 401, 486
Prithive 390
Prithivi 25, 101, 147, 237, 311, 390, 494, 499
Prithu 15, 390
Priti 390, 499
privy 266
Priyakarini 474
Procis 118, 284
Procleia 62
Procne 170, 244, 459
procreation 50, 261, 322, 507
Prodromes 390, 522
Proetus 6, 12, 25, 96, 121, 297, 390, 440
Promachus 35, 219, 249, 390, 480
Prometheus 11, 21, 80, 101, 123, 131, 147, 169, 211, 212, 216, 231, 318, 356, 372, 383, 390, 391, 461
Pronax 17, 47, 297, 391, 451
Pronoe 21, 114, 383, 385
Pronoea 147, 391
Pronuba 253
prophets/prophecy 13, 36, 56, 62, 100, 108, 114, 116, 165, 245, 310, 316, 322, 382, 386, 388, 423, 462
Proserpina 208, 379, 391
Proserpine 119, 243, 379, 391
Prosperity 45, 102, 164, 186, 233, 338, 410
Prosperity Man 347
prostitutes 255, 278, 394
protection 44, 211, 287
protectors 23, 27, 68, 69, 71, 107, 149, 209, 264, 342, 409, 459, 489, 498, 522
Protetus 356
Proteus 69, 142, 174, 240, 342, 379, 391, 457
Protogeneia 21, 147, 368, 391
Protogenus Phaethon 381
Protogonos 88, 273, 381
Proud God 83
providence 79, 119
Prthivi 390
Prussia 31, 145, 160, 264, 281, 287, 393, 495, 521
Pryderi 199, 305, 306, 391, 393, 403
psalmists 158, 161
Psamathe 18, 62, 382, 391, 462
pschent 82
Psedjet 168
pseudepigrapha 14
Psyche 391, 485, 501
Ptah 61, 72, 75, 212, 268, 317, 340, 391, 418, 428, 453, 455, 456
Ptah-Hap 391
Ptah-il-Uthra 6
Ptah-Nun 391
Ptah-Osiris 391
Ptah-Seker 391
Ptah-seker-ausar 419
Ptah-Seker-Osiris 391
Ptah-Seker-Tem 391
Ptah-Sokar-Osiris 367, 391
Ptah-Tatenn 391
Pterseus 380
Pthah 391
Ptolemy IV 268
Ptous 79, 392, 462
Pua 256
public speaking 97
Puchah 28
Puchan 393
Puck 392
Pueblo 81, 84, 228, 246, 264, 277, 446, 517
Pueo-nui-akea 392
Puffing 117
Puffing General 425
P'u-hein 410
P'u-hsien 392, 448
Puka-buti-no-midu-yare-pana-no-kami 282
Pukkeenegak 392
Pukku 392
Pukwudjies 252, 392
Pukys 276
Pulah 392
Pulastya 392, 398, 401, 499
Puleh 254, 392
Pulinda 511; and Pulini 392
Pulindi 511
Pulini 392
Puloma 100, 141
Puloman 238
Pulotu 217
pulque 118, 132, 314, 509
Puma 134
Puna 261, 467, 503
Punchau 170, 392
Pundarika 152, 293
Punga 211, 256, 452, 506
Pun-gel 353
Punia 29
Punoduno-no-kami 282
Punyajana 392, 511
Pupa-no-modi-kunusunu-no-kami 282, 510
Puphluns 182
Puramdara 237
Puranas 141, 194, 275, 276, 374, 406, 512
Purandhi 392
Puratabui 349
Purbutty 148, 374
purification and purity 25, 178, 250, 470, 494, 519
Puripais 152
Purohita 392
Purrishram 373
Purrunaminari 392
Pursurama 373
Purukupali 392
Pururavas 485
Purusa 392
Purusha 105, 337, 392, 393, 413, 416, 494, 497
Purvachitti 63
Purvadevatas 148
Pu-sa 103
Pusa 224, 426
Pusait 393
Pusan 393
Pushan 139, 141, 310, 374, 392, 393, 444, 464, 497
Pushpa 393
Pushpadanta 152, 393
Pushpa-danta 293, 393, 494
Pushpa-giri 492
Pushpaka 282, 393
Pushpema 304, 393
Puspa 33
Puspaka 401
pustaka 389
Put 512
Putan 393
Putana 91, 275, 276, 393, 497
Puzur-Sin 278
Pwalso 392
Pwyll 65, 199, 306, 391, 393, 403
Pwyll Pen Annwn 393
P'yag-na-rdo-rje 489
Pyerun 380, 446, 501
Pygmalion 25, 97, 129, 151, 185, 320, 393
Pygmies 163, 194, 330, 340, 360, 365, 472, 504
Pylades 20, 51, 165, 393, 463
pylons 4
Pylos 57, 174, 341, 343
Pylus 66, 67, 146, 359, 393
Pyracmon 10, 137
Pyramid Age 60
Pyramid of the Moon 459
Pyramid of the Sun 459
Pyramid Texts 23, 28, 32, 43, 44, 50, 58, 60, 61, 71, 72, 73, 74, 75, 118, 189, 209, 265, 338, 339, 340, 341, 343, 437
Pyrene 66, 137, 393
Pyrgo 378
Pyriphlegethon 11
Pyroeis 210
Pyros 480
Pyrrha 11, 54, 147, 169, 211, 315, 391, 393, 465
Pyrrhus 11, 145, 389
Pyrshak-khan 89
Pyrygian 89
Pythagora 22
Pythagoras 6
Pythia 70
Pythian games 128
Python 62, 289, 393

Qabauil 228
Qadesh 36, 51, 75, 206, 394
Qadishtu 75, 394
Qaholom 37, 227, 245, 387, 394
Qahootze 394
Qamaits 394
Qasavara 394
Qat 309, 313, 337, 394, 452, 471
Qeb 394
Qebeb 394
Qebehsennuf 394
Qebehsenuf 394
Qebhet 394
Qebh-sennuf 394
Qebhsenuef 421
Qebhsnauf 394
Qebhsneuf 48, 204, 394, 477
Qebhut 394
Qebk 394
Qebsnuf 394
Qebui 394
Qedeshet 75
Qeften 4
Qererti 4
Qerhet 394
Qerneru 61
Qerti 75
Qetesh 394
Qettu 61
Qodshu 394
Q're 115, 266, 394
Quaayayp 349, 395
Quadesh 51, 323, 394
Quadriga 76, 210, 380, 395
quadruplets 226
quail 75
Quajaip 395
Quakuinahaba 117
Quanzhen Taoism 163
Quartiana 178
quartz 143
Quat 394
Quauteca 472
Qu-ba 4
Quecholli 325
Quechua 154, 204
Quedesh 394
Queen Mother of the West 420, 505, 508
Queen Mother Wang 504, 519
Queen Tiy 33
Quetzalcoatl 114, 121, 125, 163, 197, 226, 228, 244, 278, 288, 295, 314, 321, 368, 395, 451, 459, 460, 469, 470, 471, 501, 509
Quetzal-Coatl 395
Quetzalcoatl-Ehecatl 395
Quetzalcoatl-Xolotl 395
Quetzal-Cohuatl 395
Quetzal-Koatl 395
Quiateot 127, 129, 162, 324, 395, 451, 500
Quiche People 90, 197, 227, 228, 271, 387, 469, 502, 508
Quilaztli 129, 451
Quinametzim 395
Quineuhyan 395
Quinkan 395
Quires 431
Quirigua 278
Quirinal Hill 395
Quirinalis 396
Quirinus 253, 310, 395, 396, 405, 431, 468
Quiyauhtonatiuh 288
Quork-quork 370, 396
Qur'an 274
Qutrub 251

Ra 3, 4, 5, 9, 23, 27, 32, 33, 44, 49, 54, 56, 58, 60, 61, 63, 70, 74, 75, 76, 79, 81, 82, 93, 168, 204, 209, 223, 225, 243, 269, 298, 315, 341, 353, 359, 367, 396, 400, 402, 415, 418, 419, 420, 421, 425, 428, 457, 458, 464, 478, 484
Ra-ateni 4
Ra'a-ti 407
rabbit 169, 320
rabbit-headed goddess 505
Rabisu 146, 396
racing 206
Rada 24, 141, 396
Radha 194, 263, 276, 285, 396, 498, 513
Radheya 262
radiance 20
Radigast 407, 446
Radsuithr 160
Radsvid 160
Rafnagud 357
raft 154
Rafu-sen 397
Raga 397
Raga-vidyaraja 31
Raging 427, 484
Ragnar Lodbrog 397

Ragnarok 90, 93, 164, 178, 179, 187, 191, 192, 198, 291, 297, 300, 326, 333, 358, 361, 397, 432, 435, 444, 479, 490, 496
Ragnarokr 397
Ragno 228, 311, 397
Raguel 74
Rahabh 61, 290, 397
Ra-Harakhte 79, 396
Ra-Heru-Khuti 4
Rahes 322
Ra-Horakhty 396
Ra-Horakte 95, 396
Rahu 310, 397, 416, 431, 444
Rahula 397
Raiden 397, 450
Raijin 397
Rail 355
rain 13, 36, 46, 47, 71, 87, 89, 94, 105, 120, 146, 154, 160, 197, 199, 200, 237, 245, 270, 277, 280, 290, 294, 304, 312, 343, 353, 354, 374, 395, 410, 431, 449, 456, 459, 469, 472, 476, 518, 519
Rainbow Bridge 101
Rainbow Serpent 483, 507
Rainbow Snake 253, 397, 506
rainbows 29, 46, 85, 110, 135, 136, 154, 188, 218, 234, 240, 256, 263, 269, 283
Rain-bringer 237
Raivata 90
Rajagriba 272
Rajah 441
Rajah Suddhodana 313
Rajarishis 404
rajas 249
Ra-Jin 396
Rajputana 188
Rajyadidevatas 148
Raka 397, 492
Rakhsh 520
Raki 397, 399, 494
Raksasa 398
Raksha-Kali 257
Rakshas 100, 398, 502
Rakshasa-Loka 293
Rakshasas 25, 26, 105, 140, 146, 203, 256, 264, 268, 282, 349, 384, 398, 401, 416, 499
Rakshasi 349, 398, 401, 429, 499
Rakshodhidevatas 148
Raktabija 257
Raluvhimba 398
ram 93, 269, 318
Rama 24, 27, 85, 99, 186, 203, 248, 254, 263, 264, 282, 285, 373, 398, 399, 411, 434, 439, 442, 454, 498, 499
Rama-candra 398, 498
Ramachandra 398, 498
Rama-Chandra 398, 498
Ramayana 63, 77, 187, 203, 285, 398
Rambha 63, 281, 283, 399
Rameses IV 93
Ramessides 421
Ramiriqui 399
Ramman 13, 71, 268, 399, 423, 424, 461
Rammanu 13
Rammon 13
Rampanelombelona 399
rams 4, 5, 7, 8, 18, 26, 27, 43
Ran 19, 209, 359, 399
Ranan 402
Randwer 447
Rangahore 399
Ranga-Hore 399
Rangda 399
Rangi 59, 60, 79, 200, 207, 209, 372, 373, 385, 397, 399, 405, 406, 452, 456, 471, 476
Rangidimaola 399
Rangima 385
Rangi-Nui 399
Rangiuri 385
Ranno 402
Ransomed 389
rape 100
Raphael 74, 400
Rapid-Autumn-Lad-Deity 376
Rapithwin 400, 514
Rasa 219, 276, 372, 400
Rasalia 396
rashness 79
Rashnu 126, 325, 400, 439, 515
Rasn 400
Rasnu 400
Rasoalao 400, 494
Rat 291, 400
Rata 312, 400, 455, 456, 467, 503
Rata 38
Ratatosk 400, 516
Ratatpslr 400
Ra-Tem 81, 437
Ratha-yatra 248, 400
Rati 258, 259, 314, 400, 499
ratna 304, 488
Ratna Dakinis 141
Ratna Krotishaurima 400, 422
Ratna Sambhav 400
Ratna-Garbha 282, 400
Ratnaheruka 215, 400
Ratnapani 150, 277, 400, 410, 489, 500
Ratnasambhava 48, 150, 223, 277, 304, 400, 488
Ratnasanu 319, 401
Ratri 25, 77, 257, 401, 486
Ratridevi 401
Rat-Taiut 400
Rattlesnake 134, 486
Ratu-nui 178, 400
Rau 401, 458
Rauni 33, 401
Ravana 91, 149, 203, 219, 248, 254, 256, 279, 282, 283, 293, 314, 335, 345, 392, 398, 399, 401, 411, 429, 433, 496, 499
Ravdna 401
ravens 62, 193, 330, 336, 353, 357, 358
Ravola 400, 494
Raxa-Caculha 197
Razanajanahary 399
Razeka 401
Rbhus 403
rDorje-P’ag-mo 156
rDorje-sems-dpa 490
Re 79, 396, 401
Realm of Accumulated Actions 47
Realm of Complete Joy 48
Realm of Light on Heaven and Earth 246
Realm of Perfected Actions 48
Realm of the Mist 345
Realm of Those of Long Hair 489
rebirth 169, 269
Recorder of Hell 190
Red Cap 411, 490
Red Emperor 128
Red Jacket or Red Coat 128, 505
Red Lord 206
Red Man 72
Red Tara 281, 454
Red Tezcatlipoca 325, 508
Red Western Realm of Happiness 442
Red Woman 72, 217
Rediyas 402
Redness of the Fire 377
regents 102
Regin 160, 177, 224, 368, 402, 431
Regina 253
Reginn 402
Rehua 372, 373, 399
Reia 403
Reidi-tyr 480
Reidmar 224
reincarnation 84
Rejoicing 461
Rekhi 4
Rekhit 417
Rekk 160
Rem 402
Remati 402
Remi 4, 402
Rem-neteru 340
Remphan 402
Remuria 289
Remus 10, 177, 287, 289, 310, 405
Renen 402
Renenet 242, 402, 422
Renenit 402
Renenutet 402
renewal 508
Renniu 402
Renpet 402
Renpti 425
Renuka 373
Rephaim 251, 402
Rephain 402
Rephan 402
reptiles 476
Re-qerert-apt-khat 417
Rerek 402
Rerir 193, 402, 430, 501
Rerit 455
Rert 455
Rerti 75
Rertu 455
Res-ab 477
Reshef 51, 342, 402
Reshep 62, 322, 342, 345, 402, 413
Resheph 36, 144, 394, 402
Reshepu 402
Reshpu 402
Res-hra 477
Re-stau 418
Rest-f 60
resurrection 484
Reta 177, 417
retribution 409
Revanta 412
Revati 90
revelry 88, 91, 152
Reza 290, 292
Rezha 290, 292
Rhadamanthus 172, 174, 201, 253, 402, 403, 414, 441, 523
Rhadamanthys 18, 76, 166, 323, 402
Rhadamantus 195
Rhea 9, 88, 97, 104, 119, 131, 133, 135, 136, 137, 138, 139, 146, 175, 184, 201, 208, 212, 213, 216, 231, 232, 253, 300, 353, 356, 364, 381, 387, 403, 460, 469, 522
Rhea Silvia 288, 310
Rhea-Silvia 431
Rhene 31
Rhesus 113
Rhiannon 169, 199, 299, 305, 391, 393, 403, 500
Rhibus 403
Rhind 404
Rhine Valley 22
Rhode 48, 403, 474
Rhodes 145, 210, 474
Rhodope 403
Rhodos 61
Rhoeo 62
Rhoetus 469
Rhokhar 385
Rhotetus 190
Ri 313
Ribhu 403
Ribhuksan 403
Ribhus 77, 403, 404, 413, 479, 489, 493, 496
ribs 13
rice 41, 97, 150, 237, 282, 412, 439
rice wine 64
Rich Form Plain of Augustness 473
riches *see* wealth
Rider of the Clouds 86
riddles 487
ridicule 327
Rig 29, 46, 209, 329, 404
Rigatona 403
Riger 404
righteousness 182, 324, 398
Rigi 65, 337, 404, 449
Rigir 404
Rigisamos 34, 131, 477
Rig-Veda 77, 285, 311, 349, 388, 393, 404, 406, 411, 427, 437, 493, 494, 498, 504
Riiki 337; and Rigi 404
Rima 404
Rimac 404
Rimmon 13, 200, 404, 414
Rin-chen-bhyun-idan 400
Rind 91, 104, 357, 404
Rind Papyrus 319
Rinda 404, 490
Rindar 404
Rinde 404
ring 52, 93, 95, 156
Ringesum 404
Ringhorn 224
Ringing Horn 192
Ririt 455
Rishabhadatta 301
Rishi Brihaspati 99
Rishis 24, 141, 264, 281, 310, 312, 335, 336, 337, 373, 388, 389, 404, 413, 443, 493, 494, 500
Rishtu 63
Rising from the Sea 61
Rissalka 407
Ristil 209
rituals 96, 108, 148
Riummon 13
River Man 440
River of Sadness 131, 503
River of Three Routes 413
rivers 11, 12, 33, 38, 49, 74, 76, 100, 101, 103, 104, 112, 114, 118, 125, 130, 131, 134, 138, 145, 171, 186, 204, 235, 253, 254, 262, 265, 266, 267, 289, 300, 310, 312, 332, 334, 344, 345, 355, 356, 387, 404, 412, 416, 427, 440, 441, 453, 457, 488, 495, 511, 515
Riyadarshana 301
rNam-snan-mnon-byan 307
rNam-t’os-sras-gsir-ch’en 282
roads 225, 408, 437, 510
Roarer 25, 26, 152
Robigus 180, 405
Robur 7, 405
Rochana 390
rocks *see* stone
Rock-Sene 405
Rod and Rozanitsa 405
Rodasi 311, 390, 405, 406
Rodu 405
Rogo 405
Rogo-tumu-here 178, 405
Rohe 405
Rohini 90, 121, 147, 275, 285, 393, 406, 437
Rokomoutu 339
Roma 176, 370, 405, 414
romances 257
Romania 284
Romans 80, 83, 86, 88, 94, 95, 96, 98, 104, 114, 115, 116, 117, 124, 127,

www.ebook3000.com

130, 132, 135, 136, 137, 138, 145, 146, 148, 151, 152, 153, 159, 162, 163, 164, 165, 168, 169, 171, 177, 178, 179, 180, 183, 184, 187, 190, 195, 201, 208, 210, 212, 213, 214, 233, 238, 245, 248, 249, 253, 254, 287, 289, 290, 291, 295, 296, 297, 302, 306, 310, 312, 315, 317, 318, 323, 325, 327, 328, 331, 339, 342, 343, 345, 350, 357, 358, 364, 370, 371, 373, 375, 378, 379, 380, 382, 384, 385, 386, 387, 388, 391, 395, 405, 407, 410, 411, 415, 418, 419, 431, 436, 437, 438, 440, 453, 458, 459, 461, 465, 480, 483, 484, 487, 494, 495, 496, 497, 501, 502, 522, 524
Roma-Tane 405, 452
Rome 6, 7, 10, 13, 14, 20, 22, 23, 32, 34, 35, 40, 44, 47, 50, 51, 53, 56, 58, 59, 61, 64, 66, 70, 78, 79, 112, 151, 176, 243, 325, 405, 478
Romulus 10, 177, 287, 310, 391, 395, 396; and Remus 405
Rona 405
Rongelap 405
Rongelapanp 371
Rongerik 371; and Rongelap 405
Rongo 60, 294, 364, 372, 373, 399, 405, 406, 452, 476, 492, 494
Rongo-ma-tane 60
Rono 405
Ro'o 79
rope 4, 260, 264
Roptatyr 357, 406
rosary 148, 301, 389, 401, 413, 454
Roscommon 112
Rose-appletree Island 248
roses 61
Roskva 83, 406, 462
Round Table 70
royalty 212
Royojusen 194
Rshis 404
Rsi 404
Rta 73
Ru 79, 313, 373, 406, 407
Rua 79, 399, 406
Ruad Ro-Fhessa 139
Rua-Haka 406
Rua-Haku 406
Ruahatu 406
Rudra 15, 25, 26, 42, 77, 100, 105, 141, 148, 204, 311, 338, 384, 388, 405, 406, 415, 427, 441, 486, 489, 494
Rudra Shiva 26
Rudrani 148, 257, 406
Rudras 185, 311, 406
Rudra-Shiva 148, 301, 311, 406, 474
Rudriyas 311, 406
Rugevit 406
Rugievit 406, 446
Ruh el Amin 184
Rukma 407, 433
Rukmini 100, 123, 249, 259, 276, 285, 388, 407, 415, 433
Ruler 241
rum 360
Ruma 407, 442
Rumar 71
Rumia 177, 407, 448, 468
Rumina 407
Rumor 184, 407
rumors 381, 407
Runes 407
Rupa 150
Rupastra 258
Rupe 235, 313, 407
Ru-piny 506
Ruqaiyah 327, 520
Ruru 389, 407, 427
Rusalkas 407
Rusalki 333, 407, 433
Rusalky 407
Russalka 433, 496
Russia 88, 92, 127, 155, 254, 266, 289, 312, 331, 380, 386, 392, 495, 496, 500
rust 405
Rustam 266, 407, 431, 520
rustic god 370
Rutali 21, 176
Rutbe 335
Rutra-Shiva 187
Rutuli 479
Rutulia 254
Ruwa 407, 507
Ryangombe 255, 265, 407, 504
Ryobu-Shinto 41, 182, 208, 255, 355, 488
Ryojusen 407, 472
Ryujins 407
Ryu-Wo 97, 407

Sa 98, 332, 408, 455, 462, 486
Saa 225, 429
Sa-Akeb 477
Saa-Set 408, 477
Saatet-ta 61
Sabak 165
Sabala 408, 512
Saba-Leippya 338, 408
Sabaoth 14, 65, 75, 93, 208, 231, 408
Sabazios 408
Sabazius 136, 137, 152, 408
Sa-bdag 408
Sabellianism 293
Sabes 477
Sabians 409
Sabines 431, 487, 496
Sabitu 408
Sabizios 408
Sacharis 418
Sachi 408
Saci 238
Sacontala 422
Sacred City 34, 136
Sacred Filth Eater 470
sacrifices 3, 25, 31, 53, 58, 71, 98, 114, 117, 153, 225, 307, 406; *see also* human sacrifice
Sacrificial Butter 190
Sacti 422
Sacy-Perere 408
Sad 37
Sadashiva 338
Sadb 179
Saddle Island 6
Sadhyas 185
Sadko 104
Sadurn 199, 408
Sadwes 204
Saehrimnir 52, 164, 209
Saehrimnir Saehrimni 408
Saeming 357, 435, 463
Saena 431, 474
Sae-no-Kami 126, 408
Saerimne 52
Safa 521
Saga 22, 357, 408, 436
Sagar 408
Sagara 99, 267, 408, 409, 442, 496
Sagaru 430
Sagbata 409, 500
sag-did 338
sages 44, 100, 108, 149, 308, 410
Sagloki 294
sago 240
Sahadeva 77, 300, 334, 409
Sahaganya 63
Sahar 166
Sahasrabhuja 84, 409
Sahasramuska 237, 409
Saho-yama-hime 409
sailing/sailors 21, 50, 108, 161, 282, 298, 347
Sai-No-Kami 413
Saint Befana 94
St. Blaise 501
Saint Brigit 96
St. Elias 165
St. George 54, 165, 420
St. Iliya Gromovnik 197
St. Michael 9
St. Patrick 18
St. Thomas 478
St. Vlas 501
saints 7
Sa'ir 243, 409
Sais 341
Sait 417
Saites 413
Saiva 409
Saiyamkoob 288, 409
Sak 409
Saka-no-mi-wo-no-kami 409, 420
Sakarabru 409
sake 252
Sakhmet 340, 391, 418
Sakhmis 419
Saki 238
Sakkara 235
Sakkhoras 191
Sakko 409
Sakra 237, 409, 410
Sakta-Sura 275, 410
Sakti 422
Saktis 33, 45, 75
Saktism 422
Sakunadevatas 148
Sakuni 159, 410
Sakuntala 422
Sakuya-hime 347
Sakya tribe 410
Sakyamuni 33, 84, 308, 313, 410, 489
Sakya-t'ub-pa-dam-g-Nas-brtan 410
Salachia 410
Salacia 47, 48, 342, 387, 410
Salagrama 410
Salamis 31, 74, 215, 376, 410, 457, 460
salaries 295
Salema and Sakia 410
Sali Kanya 374
Salii 51, 310, 410
saliva 85, 498
Salkis 420
Salmacis 214, 410
Salmon 413
Salmoneus 21, 115, 166, 410, 430, 480
Salmoxis 88, 520
Salmydessus 205, 381
Saltu 27, 348, 410
Salus 229, 410, 440
salt 481
saltwater 410, 515
Sam 407, 410
Sama 266
Sama Keresaspa Nairemanah 266
Samael 14
Samana 512
Samantabhadra 32, 48, 150, 277, 280, 301, 410, 411, 489, 500
Samanta-Bhadra 280, 410
Samantabhadri 48
Samantaka 258
Samantamukha 84, 411
Samantapancaka 411
Samas 37, 59, 198, 411, 412
Sama-Veda 411
Samavurti 411, 512
Samaya-Tara 47
Samba 90
Sambara 120, 276, 388, 411
Sambo-kojin 411
Samdhya 411, 412
Samgna 412
Samhitas 411, 494
Samia 405, 411
Samjna 150, 412
Samjuna 412
Sammunus 411
Sammuramat 411, 419, 424
Samnati 147
Samoa 23, 256, 262, 313, 385, 452
Samos 405, 411
Samothrace 97
Samoyd 352
Samoyed 471
Sampati 411
Sampo 28, 234, 289, 295, 411, 488
Sampo-Kwojin 446
Sampsa Bellervoinen 411
Sams 412
Samsara-Guru 258
Samsu 423
Samvarana 453
San Ch'ing 286, 291, 412, 423, 518
San Cristobal 179, 264
San Hsien Shan 225, 412
San Kiai Kung 412
San Kuan 412, 429, 465
San Kuan Ta Ti 412
San Yuan 412
Sanada 347
Sandacos 412, 448
sandal 34
Sandhya 401, 412
Sandili 412
Sandipani 371
Sandorcus 129
Sang Ch'ing 412
Sangarius 81, 334, 412
Sang-gyeman-gyila-beduryr-o-chi-gyal-po 99
Sangke 234, 253
Sangso-Dungso 9, 295, 412, 429
Sangyay Chanma 422
Sangye Khado 268
Sanhara 412, 427
Saning Sari 412
Sanja 77, 412, 413, 427, 444, 453, 499
Sanjna 412
Sankara 412, 427
Sankashana 90
sankhas 409
Sankhasura 412, 413
San-ku 266
Sanmangalaph 291
sannyasins 264
Sanoi 291
Sansenoi 291
Sanshi-taisho 345
Sanskara 47, 150, 488
Sanskrit 22, 24, 42, 45, 47, 86, 99, 120, 139, 140, 182, 199, 238, 273, 285, 307, 479, 511, 514
Santanu 100, 187
Santaramet 201, 211, 413, 438
Santarametakans 413
Sanumati 63
Sanzu-no-kawa 126, 413
Saora People 17, 32, 53, 70, 88, 104, 234, 248, 284, 404, 413, 471
Sapi 413
Sapling and Flint 518
Sappho 349
Sapta-Loka 293
Saptarshi 308, 404, 413
Saptungtongsum 413
Saqar 243
Sarah 8, 74
Sar-Akha 32
Sarakka 299
Sarama 413, 512
Saramana 413
Saramaya 182
Saranya 413
Saranyu 77, 83, 85, 403,

413, 474, 479, 489, 500, 512, 513
Sarapis 420
Sarasvati 26, 52, 61, 97, 99, 105, 140, 148, 187, 285, 308, 330, 374, 413, 414, 422, 474, 490, 498
Saraswati 26, 413
Sarbanda 414
Sarcostemmaacidum 203
Sardinia 190
Sarigoys 68, 302
Sarika 158
Sarna Burhi 414
Sarnga 414, 498
Saronic Gulf 118
Sarpanit 522
Sarpas and Sarpis 414
Sarpedon 76, 174, 176, 192, 253, 287, 322, 323, 370, 402, 405, 414, 523
Sarpedon II 145, 370
Saruta-biko 40
Sarva 25, 26, 414, 427
Sarvaga 99
Sarvamangala 148, 414
Sarvana 413
Sarvani 148
Sarvanivaranaveskambhin 47, 150, 301, 410
Sarvari 414
Sarvavasini 148
Saryata 299, 442
Sary-Khan 89, 283, 414
Sasabonsam 414
Sashikuni-waka-hime 282
Sasi-kuni-opo-no-kami 282
Sasilekha 63
Sassanians 28
Satakratu 257
Satan 85, 87, 95, 119, 125, 148, 295, 402, 414, 415, 518
Satapatha Brahmana 77, 281, 308, 312, 388
Satarupa 308, 413, 427
Sata-rupa 487
Satavaesa 33, 415, 515
Satet 269, 415
Sathan 148, 414
Sathanas 148, 414
Sathenik 520
Sati 141, 148, 158, 257, 374, 375, 406, 415, 427
Satis 55, 59, 165, 242, 269, 415
Satrajit 276, 415, 447
Satrughna 99, 398
Sattung 94, 199, 220, 358, 415, 444
Saturn 135, 177, 384, 403, 415
Saturnia 253
Saturnus 135, 350, 415
Satyabhama 276, 415, 447
Satya-Loka 293
Satya-Narayana 337
Satyapir 337
Satyavan 415, 416
Satyavati 100, 373, 415, 502, 503
satyrs 49, 57, 88, 133, 138, 159, 208, 212, 289, 371, 415, 511
Sau 61
Saubha 275
Saubhadra 7, 69
Saudamani 63, 264, 511
Sauk 334
Saunanda 415
Saurasa 416
Sauromatai 42
Sauru 138, 143, 270, 416
Savabhauma 293
Savaki 270
Savala 259
Savarbhanu 416
Savarni 453
Savioress 278
Savita 500
Savitar 416
Savitr 416
Savitri 15, 77, 141, 325, 352, 358, 413, 416, 444, 487, 492, 499, 500
Savus 17
saw 223
Saxons 20, 161
Say-nying-po 304
Sa-yori-bime-no-mikoto 41
Scaldic 447
Scamander 129, 130, 215, 405, 416, 508
Scanda 263, 435
Scandinavia 36, 98, 190, 240, 357, 435, 496
scarab 80, 269, 416
Scatbvach 135
Scathach 60, 416
Sceiron 377, 416
Sceolan 179
scepter 51
Schango 356
Schankpannan 356
Schilbung 344
Schoeneus 78, 79, 219, 417, 462
scholars 126, 132, 505
schools 223
science 24, 186, 307, 467, 489
scissors 38
Scorner of the Gods 287
scorpions 5, 244, 514
Scotia 61
Scotland 60, 65, 92, 112, 115, 116, 150, 266, 309
Scott 500
Scrat 159, 417
scribes 95, 186, 339
sculptor god 356
Scylla 56, 119, 130, 175, 194, 195, 240, 315, 342, 349, 383, 417
Scyros 11
Scythia 42, 65, 197, 381, 382
Sea Foam 497
Sea of Hades 191, 484
sea-crows 114
seagull 293
seals 351, 391
seashells 27, 261
seasons 174, 196, 222, 282, 443, 461, 495
Seb 4, 189, 340, 367, 394, 425
Sebak 417
Sebau 333
Sebek 417
Sebek-Hetep 417
Seben-hisq-qhaibit 425
Sebeq 417
Sebeq-hra 340
Sebi 417, 477
Sebku 417
Sebuit-nebt-uaa-khesfet-sebau-em-pert-f 417
Sebv-ent-seba 61
Sechmet 418
Second Savior 83
Secret heart 425
secrets 248, 263
Sedeq 412, 417, 447, 521
Sedit 133
Sedna 16, 36, 343, 388, 417, 418, 511
Sedrat 418
Sedu 185, 418
Seeland 189
Seer 62
Seeta 434
Sefer 418
Sefkhet-Aabut 421
Seftit 458
Seger 418
Segesta 10, 418
Segetia 418
Segg 209
Segomo 418
Sehetch-khatu 4
Seia 418
Seilenoi 431
Seilenos 431
Seilenus 431
Seimia 200
Seine 420
Seiren 433
S'eirim 148
Seit Ka-doji 418
Seitaka 182
Seitaka Doji 182, 418
Seker 418, 419, 459
Sekhait 418
Sekhauit 418
Sekhautet 418
Sekhem 56, 61, 73, 82, 418, 483
Sekhem Em Pet 58, 418
Sekhem Taui 60, 418
Sekhem-bast-ra 418, 419
Sekhem-hra 4, 61
Sekhemus 418
Sekhen-ba 4
Sekhen-tuatiu 417
Sekhenu 177, 417
Sekhen-ur 477
Sekheper-khati 4
Sekher-remu 4
Sekhet 93, 206, 418, 457
Sekhet Aaru 4
Sekhet of Thebes 425
Sekhet-hetep 4
Sekhet-hra-asht-aru 477
Sekhet-metu 379, 477
Sekhmet 93, 317, 331, 391, 418, 419
Sekh-met-Bast-Ra 373
Sekhmet-Bast-Ra 419
sekhtiu 215
Sektet 486
Sekume 354
Selamanes 413
Selena 419
Selene 70, 169, 175, 208, 210, 230, 242, 318, 370, 419, 461, 523
Seleni 310
Selenus 117, 431
self-creation 460
Self-Purifying Soma 436
Selina 419
Selket 341, 420
Selqet 420
Selquet 420
Selsabil 419
Selu 261
Semaahut 4
Semamti 477
Semang 262
Semele 13, 24, 83, 88, 89, 112, 152, 234, 239, 253, 419, 465, 521, 523
Semetu 477
Sem-Heru 458
Semi 419
Semiramis 64, 79, 355, 419, 424
Semites 8, 9, 14, 16, 24, 37, 50, 73, 74, 75, 82, 87, 88, 89, 96, 98, 113, 123, 136, 139, 144, 152, 162, 164, 176, 185, 200, 234, 242, 270, 300, 324, 327, 339, 342, 346, 347, 355, 394, 397, 400, 402, 411, 412, 418, 466, 493, 510
Semit-her-abt-uaa-s 419
Semktet 396
Sem-Nebt-het 417
Semsem 177, 417
Sem-shet 417
Sena-pati 263
Seneca 147, 183
Senegal 354
Senenahemthet 32, 61, 419, 420
Sengen 419
Sengen-Sama 182, 419
Senju Kannon 261
Senk-hra 4
Senki 4
Sennin 420
Sennins 420, 505
senses 138, 224, 275
Senx 37, 394, 420
Se-oritsu-hime 207, 417
Sep 58
Sepa 118
Sepes 420
Sept 4
Septu 437
Seqet-hra 477
Seqinek 420
Sequana 420
Sequinek 420
Seraa 4
Serafili 184
Seraphim 53
Serapis 61, 62, 72, 420
Serbia 83, 154, 155, 160, 197, 435, 439, 496, 500, 501
Serekhi 75
Serem-taui 61
serfs 29, 464
sericulture *see* silk and silkworms
Seriphos 380
Seriphus 12, 151
Serius 122
Serket 420
Ser-kheru 75
Serpent Lady 131, 420
Serpent Mountain 131
Serpent Petticoated 131, 420
Serpent Skirt 131, 420
Serpentarius 72
serpents see snakes
Serqet 5, 269, 420
Serqi 4
Serquet 204, 421
Sesa 421
Sesanaga 421
Sesenet-khu 425
Sesha 50, 90, 255, 305, 333, 337, 338, 375, 421, 493, 498
Seshat 421, 464
Sesheta 421
Seshetai 4
Seshmu 421
Seshu 90, 281, 421
Sesondowah 190
Ses-rab-kyi-pha-rol-ta-phyin-pa 389
Sessrumnir 181, 421
Sessrymner 181
Sesuto 260
Set 4, 32, 33, 51, 58, 81, 88, 92, 93, 148, 168, 189, 206, 212, 341, 342, 352, 367, 394, 396, 402, 421, 422, 425, 437, 480, 505
Setanta 135
Seta-Ta 421
Setcha 421
Setcheh 32, 61, 420, 422
Setem 422
Seth 56, 63, 75, 88, 222, 223, 243, 351, 353, 421
Setheniu-Tep 422
Set-Hra 421, 477
Sethu 422, 477
Seti 421
Seti I 4, 367
Set-kesu 75
Set-Qesu 421
Setu 422, 458
Seven Against Thebes 17, 19, 35, 76, 114, 115, 145, 169, 173, 176, 219, 314, 387, 422, 451, 480
Seven Deities of Good Fortune 97
Seven Generation Deities 39
Seven Gods of Creation 102
Seven Gods of Happiness 426
Seven Great Slayers of Monsters 95
Seven Sisters 303
Seven Snakes 125, 422
seventh heaven 485

www.ebook3000.com

sewers 111
sex 31, 33, 61, 75, 108, 123, 152, 196, 238, 245, 258, 275, 308, 401, 470, 478, 495, 501
sex change 99, 513
sexes 363
Sgeg-mo-ma 287
Sgrib-pa-rnam-sel 47
sGrol-mas 454
Sha 422
Shaddai 166
Shade 86, 124, 412
Shadow 268
Shadrapha 422
Shaft 128
Shahan 423
Shahapet 422, 429
Shahar 5, 37, 80, 164, 424, 503, 514; and Shalim 422
Shahpet 429
Shahr 87
Shahrevar 270
Shahriver 270
Shai 4, 422
Shait 422
Shaitan 85, 148, 251, 422
Shakak 428
Shakanli 424
Shakara-o 345
Shakrani 238
Shaktar 373, 422
Shakti 55, 148, 158, 186, 208, 285, 305, 313, 400, 422, 436, 493, 497, 523
Shakti Nam-kha-ing-kya-wang-chug-ma 488
Shakuntala 63, 99, 422
Shakura 369, 423, 468
Shakuru 468
Shakya 313
Sha-kya-tup-pa 410
Shala 13, 309, 423
Shalem 424, 514
Shalim 80, 164, 422, 503
shamans 16, 29, 64, 120, 221, 266, 270, 321
Shamas 268, 399, 423, 424, 461
Shamasa 71
Shamash 62, 73, 85, 87, 92, 123, 139, 236, 242, 267, 270, 325, 336, 342, 346, 417, 423, 432, 487, 521
Shambara 411
Shamdon 74
Shamhat 191
Shamshu 423
Sham-shu 423
Shan Kuei 423
Shang Ch'ing 412, 423
Shang T'ai 439
Shang Ti 226, 423
Shang-di 423
Shango 24, 146, 271, 355, 362, 366, 368, 423, 464
Shang-Ti 423
Shani 453
Shankha 281
Shankha-Sura 275, 423
Shankpanna 24
Shantanu 187, 415, 423, 503
Shap 424
Shapash 87, 329
shape changers 54, 63, 129, 267, 294, 413, 424, 487, 500
Shaphash 51, 424
Shapsh 424
Shar 55
Shara 236, 424
Sharabha 427
Sharanyu 413
Sharira 440
Sharis 242, 424
sharks 326, 482
Sharp-cutting Lord 183
Sharruma 212
Sharur 348, 521
Shasha 437
Sha-shen 473
Shashthi 263
Shasnli 424
Shasti 186, 424
Shastradevatas 148
Shata-et 413
Shata-Rupa 413
Shatarupa 424, 487
Shatrughna 285, 424
Shaumya 427
Shaushga 424
Shaushka 242
Shavod 422
Shawano 335
Shaya 124
Shazu 309
shears 327
sheath 374
She-Chi 424
Shed the healer 422
Shedim 14, 148
Shedu 418, 487
Sheehogue and Deenee Shee 424
sheep 31, 326, 327, 390
she-goat 209
Shehbui 424
Shelan Nara 146, 251
Shelartish 424
Shelf of the Slain 490
Shelva 424
Shem 249, 525
Shemat-khu 477
Shemat-khy 379
Shemerthi 424, 458
Shemesh 422, 423, 424, 514
Shemsu Heru 424
Shemti 4, 64
Shen 368
Shen Mu 383
Shen Nung 425
Shen Pao 286, 412
Shen Shu 425
Sheng mu 333, 443
Sheng-mu 383, 425, 449, 467
Shennda Boaldyn 96
Shen-Nung 124, 128, 425, 430
Shen-T'ao 371
Shen-t'u 117, 225, 317, 425, 519
Sheol 211, 402, 425
Shepes 425
shepherds 90, 158
Shepi 4
Shepu 177, 417
Sheri 459
Shesat Maket Neb-s 58, 425
Shesemtet 425
Shesemu 425, 457
Shesera 425, 458
Shesha 421, 499
Shesheta 340
Shesmu 425
Shesshes 4, 5
Sheta 61
Sheta-Ab 425
Shetan 148, 422
Shet-kheru 75
She-Tse 424
Shetu 177, 417, 425
Shi Tenno 251, 273, 425, 426, 427, 524
Shi'a sect 36
Shichi Fukujin 97, 102, 150, 162, 220, 224, 252, 275, 361, 412, 426, 450
Shidure 430
Shidurri 430
shield 20
Shigi-yama-tsu-mi 420, 426
Shih-chia-mou-ni 410
Shiho-tsuchi 217, 355
Shiko-Me 363, 426, 518
Shikome 426
Shilluck 354
Shilluk 253
Shilup 426
Shilup Chito Osh 426
Shima-Tsu-Hiko 278, 355
Shimhanada Lokeswara 426
Shimmei 41, 426
Shimmo-ten 345
Shimonoseki 355
Shimti 242, 426
Shinaland 182
Shina-tsu-hiko 426, 446
Shingon 45, 140, 182
Shining 77, 435
shining mane 435
Shining One 25, 62, 64, 90
Shining One Over the Sea 181, 309
Shining Ones 100
Shinshu 45
Shinto 31, 39, 40, 41, 42, 43, 46, 78, 140, 150, 162, 182, 183, 200, 207, 208, 217, 220, 221, 223, 241, 246, 247, 251, 255, 260, 265, 280, 282, 346, 347, 355, 361, 442, 445, 446, 449, 450, 464, 473, 476, 482, 510, 514, 518
Shio-Zuchi 355, 426
Shi-pa Lo-han 68
ships 108, 224, 333
shipwrecks 38
Shiri-kume-na-nawa 41, 426
Shishupala 433
Shitala 434
Shita-teru-Hime 43, 208, 361, 426, 450
Shi-Tenno 102
Shitenno 425, 427
Shi-tien Yen-wang 426, 512
Shiu-Mu Naing-Naing 427
Shiva 26, 50, 52, 65, 69, 74, 89, 91, 92, 98, 99, 100, 105, 119, 120, 141, 148, 158, 159, 182, 185, 187, 188, 196, 203, 204, 230, 241, 256, 259, 262, 263, 264, 268, 283, 293, 294, 301, 305, 309, 335, 338, 373, 374, 375, 384, 393, 400, 406, 415, 427, 434, 436, 452, 454, 473, 474, 478, 497, 499, 512
Shivalas 305
Shivaratri 428
Shiwanaokia 84
Shi-wang 512
Shiwanni 84; and Shiwanokia 428
Shiwanokia 84, 428
Shk 428
Shmashana-Kali 257
Sho Kannon 261
Shoden 186
Shoithrapaiti 422
Shojo 428
Shokujo 266
Shongo 307
Shongon 323
Shony 437
shooting stars 124
Shore of Corpses 338
Shotoku 251
Shou 428
Shou-chang 277
Shouhsing 428
Shou-hsing 428
Shou-Lao 428
Shou-Sing 428
Shou-t'sang 277
Shou-Ts'ang 428
Shraddha 439
Shri 285, 439
Shrieker 24, 242
Shrove-tide 215
Shru 439
Shu 4, 54, 79, 80, 81, 168, 189, 209, 227, 244, 269, 340, 353, 396, 428, 456, 457, 464, 483
Shu Yu 317
Shualu 64
Shu-Hu 429
Shui Chun 429
Shui I 346, 429
Shui Jung 123, 429
Shui Shen 346, 429, 519
Shui-kuan 412, 429, 465, 467
Shujaku 182
Shukra 77
Shullat 423
Shulmanu 413
Shulmus 368
Shun 279
Shura 429
Shurappak 59
Shurpanaka 279, 345, 401, 429
Shutu 14, 234, 429
Shuznaghu 252, 442; and Zumiang-nui 429
Shuznagu 441
Shvaz 422, 429
Shveta Tara 429, 454
Shvod 429
Shyama-Kali 257, 429
Si Wang Mu 225
Sia People 225, 429, 435, 438, 446, 486
Siam 285, 427, 498
Siamese twins 135
Siberia 6, 32, 45, 70, 81, 89, 105, 123, 144, 154, 162, 244, 252, 265, 267, 270, 278, 290, 343, 471, 477, 478, 482, 483, 489, 517, 518, 524
Sibhol 164
Sibu 429, 443
Sibyl 40, 119, 286, 429, 430
Sibylla 429
Sibylle 429
Sibylline oracles 40
Sibzianna 451
Sicily 10, 21, 137, 138, 358, 387, 417
Sick Bed 210
Sicyon 19, 57, 133, 169, 316, 378
Siddartha 313, 388, 410, 430
Sidda-Sila 430
Siddhaikaviramanjughos 307
Siddhanganas 430
Siddhanjanas 430
Siddhartha 301, 430, 474
Siddhas 293, 430
Siddhi 186, 263, 430
Side 365
Sidero 134, 410, 430
Sidh 18, 321
Sidhe 305, 477
Sidhi Data 186
Sidhottr 357
Sido 430
Sidon 24, 73, 242
Siduri 430
Siduri-Sabitu 430
Siduru 430
Siegfried 91, 198, 344, 431
Sie-king T'ai 430, 466, 475
Sien-tsan 430
Sieroji Zemele 521
Sif 22, 196, 231, 245, 429, 430, 432, 463, 465, 483
Si-Fang Ki-Lo Shi-Kiai 442
Sifuri 191
Sige 21, 430, 523
Sigfadir 357
Siggeir 430, 431, 432, 501
Sigi 357, 402, 430, 501
Sigidi 172
Sigird 431
Sigmund 357, 430, 431, 432
Signy 430, 431, 432, 501
Sigoo 431
Sigrun 431
Sigtyr 357
Sig-tyr 480
Sigu 303, 431
Siguna 431

Sigurd 52, 177, 196, 402, 431, 447
Sigyn 22, 337, 431, 435, 490
Sihu 134
Sikh 164
Sikhin 308
Sila 74
Silappadikaram 90, 274, 431
Silas 431
silence 205, 211, 331, 496
Sileni 212, 415, 431
Silenus 88, 98, 321, 371, 415, 421, 431
Silik-mulu-khi 431
Silili 431
silk and silkworms 41, 42, 361, 430, 475
Silvanus 22, 431, 441
silver feet 462
Silver Handed 292, 352
Silver Wheel 68
Silvius 21
Simbali 443
Simbi 431
Simbi En Deux Eaux 431
Simhanadamanjusri 307
Simharatha 158
Simhika 397, 431
Simmos 419
Simoeis 76, 216, 431
Simon Magus 8, 48, 168
Simurgh 187, 407, 410, 431, 520
sin 15, 53, 248
Sin 59, 71, 191, 242, 268, 309, 336, 346, 353, 399, 423, 432, 461, 521
Sina 217, 235
Sindre 432
Sindri 156, 159, 198, 199, 432, 435
Sinfiotli 220, 430, 431, 432
Sinfjotle 432
Sinfjotli 357, 432
Singhini 432
singing 294, 317
Sinilau 468
Sinis 379
Sinivali 432, 498
Sin-Nanna 432
Sinon 432, 433
Sinope 44, 74, 202, 405, 432
Sintians 212, 432
Sinu 432
Sio Calako 432
Sio Humis 432
Siokhi 308
Sioux 203, 232, 234, 272, 504
Sipae 67
Sipendarmidh 438
Sippar 59, 423, 524
Sipylus 18, 377
Sirah 327
Sirat 432
Sirdu 3
Siren Islands 433
Sirens 11, 113, 114, 217, 290, 291, 317, 327, 366, 376, 404, 407, 433, 440, 461
Siris 73, 161, 524, 525
Sirius 204, 365, 433, 438, 468
Sirona 105
Sirrida 3
Sirrush 433
Sirsir 309
Sirsootee 148, 188
Sisa 273
Sishanim 53
Sisiri 392
sistrum 93, 206, 234, 433
Sisupala 249, 401, 433
Sisyphos 433
Sisyphus 19, 21, 56, 74, 83, 95, 115, 166, 171, 192, 202, 245, 284, 319, 358, 366, 382, 410, 432, 433, 434, 453, 463
Sita 24, 99, 101, 203, 282, 285, 398, 401, 411, 434, 442, 485, 493, 498
Sitala 257, 434
Sitatapatraparajita 84
Sitatara 454
Sith 83, 434
Sithon 383
Sitla 434
Siton 139, 434
Sitragupta 237, 238, 434
Situr 348
Siudleratuin 434
Siut 60
Siva 406, 427, 524
Sivaites 248
Siwa 44
Si-Wang-Mu 429, 516
Six Syllabled Lokeswara 268
Siyamek 189, 223, 311, 516
Siyameki 311
Sjarr 160
Sjofn 434
Skade 434
Skadhi 434
Skadi 22, 199, 350, 357, 434, 435
Skambha 25, 237, 435, 436
Skanda 26, 91, 158, 263, 374, 435
Skandaganani 374
Skandar 160
Skandas, The Five 435
Skandhas 150
Skathi 434
skeletons 146
Skidbladner 435
Skidbladnir 159, 181, 245, 432, 435
Skidskegg 357
skiing 483
skills 107
Skinfaxe 435
Skin-faxi 139
Skinfaxi 435
Skiold 189, 357
Skirfir 160
Skirner 435
Skirnir 101, 435
Skjold 463
Skogsfru 435
Skogul 490
Skoll 178, 206, 435
Skoyo 435, 438
Skrymer 435
Skrymir 435, 462, 486
Skuld 351, 485, 490
Skulla 433
skulls 3, 99, 262, 427
sky 24, 35, 37, 38, 40, 42, 49, 54, 55, 58, 59, 61, 69, 79, 80, 87, 89, 104, 140, 141, 160, 164, 197, 206, 208, 212, 218, 222, 244, 252, 253, 268, 278, 279, 283, 292, 302, 323, 325, 341, 343, 349, 352, 353, 354, 356, 362, 390, 399, 416, 425, 437, 460, 463, 465, 469, 473, 475, 476, 480, 484, 492, 507
Sky Knows Who Will Prosper 366
Sky People 475
Sky Traveler 294
Skyamsen 435
Skye 60
Skylla 192, 417
Sky-Rock-Cave 41
Slagfinn 501
slaughter 22, 326
slaves 151, 209
Slavs 25, 34, 83, 88, 90, 92, 98, 104, 105, 124, 127, 135, 144, 154, 159, 160, 171, 194, 214, 234, 253, 262, 270, 271, 274, 275, 276, 280, 281, 284, 288, 289, 291, 311, 312, 326, 327, 331, 333, 339, 343, 360, 368, 378, 380, 386, 405, 406, 407, 422, 437, 438, 440, 441, 446, 447, 472, 481, 492, 495, 496, 500, 501, 514, 521, 523, 524, 525
Slayer of Enemies 69, 275
Slayer of Evil Spirits 25
Slayer of Madhu 275
Slayer of Rakshasas 25
Slayer of the Enemies 54
Slayer of Vritra 237
sleep 228, 230, 329, 334, 437
Sleeping on Ananta 498
Sleeping on the Water 498
Sleipner 357, 435, 446
Sleipnir 90, 214, 294, 407, 435
Slid 165, 435
Slidrugtanni 198
Slooa-shee 424
sloth 136
Sly One 294
Smaj 435
smallpox 196, 204, 309, 434, 473
Smara 258, 435
Smashana 427, 435, 495
smiling 128, 199
Smintheus 62
Smit 209
smiter 234
smiths *see* blacksmiths
Smok 524
Smoking Mirror 460
Smyra 16, 331
Snaer 254
snail 65
Snake Killer 187
snakes 3, 4, 5, 8, 9, 10, 11, 14, 16, 18, 27, 28, 29, 32, 33, 43, 45, 46, 47, 50, 53, 55, 58, 61, 62, 64, 69, 72, 73, 74, 81, 84, 85, 89, 90, 93, 97, 98, 99, 100, 102, 105, 110, 111, 112, 119, 122, 124, 125, 129, 138, 141, 142, 143, 174, 177, 179, 193, 194, 196, 197, 204, 206, 209, 222, 225, 226, 234, 235, 245, 249, 257, 264, 269, 273, 274, 278, 279, 285, 305, 319, 325, 332, 339, 364, 371, 393, 395, 397, 408, 414, 420, 422, 481, 483, 506, 508
Snana-yantra 436
snares 149
Snatchers 205
Snavidhka 266
Sniffing 117
Sniffing General 425
Snor 23, 209, 262
Snorta 436
Snorter 211
Snorter and Blower 317
Snorter and Puffer 211
Snotra 436
snow 36, 105, 133, 217, 280
Snt 209
So 268
Sobek 341, 417
Sobk 417
Sobk-Re 417
Socharis 418
social laws 103
Society Islands 452, 467
Sogamozo 399
Sogbo 24, 436
Sogbu 302
soil 113, 224, 424, 476
Sois 377, 436, 474
Sojobo 458
Sokar 391, 392, 418
Sokare 418
Sokaris 418
Sokkvabek 436
Soko-no-kuni 436, 518
Sokotsu-kuni 436, 518
Sokushikki 232, 436
Sokvabek 408, 436
Sol 5, 11, 38, 210, 211, 233, 306, 330, 436, 443
Solal 436
Solang 38, 436
Solar King 115
Solar Race 398
soldiers 102, 253
So'lla 134
Solomon 74, 123, 200
Solomon Islands 27, 32, 206, 273
solstices 53
Solymians 96, 436
soma 25, 48, 108, 121, 147, 149, 186, 188, 237, 299, 393, 397, 413, 474
Soma 25, 42, 69, 77, 121, 141, 186, 187, 203, 222, 281, 283, 285, 293, 388, 390, 412, 435, 436, 437, 444, 451, 454, 487, 492, 493, 512
Soma Pavamana 436
Soma-Loka 293
Somavati 437
Soma-Veda 494
Somboi-Burkan 437
Sombol-Burkan 437
Sommay 302
Somnus 170, 228, 230, 328, 352, 437
Son of a Jar 24, 256
Son of Agni 263
Son of Bile 117
Son of Ganga 100
Son of Milo 322
Son of Self 25, 453
Son of Svarog 144, 437
son of the sea 270
Son of the Sky 437
Son of the Solar Deity 483
Son of the Sun 306
Son of the Wave 160
Son of Vivasvat 489, 512
Son 43, 104, 199, 358, 437
song 386, 489
Song of the Divine One 98
Songhoi 155, 523
Songo 33
Son-of-hapu 44
son-of-heaven 251
Sonponno 437
Sons of Ivaldi 432
Sons of Mil 45
Sons of Rudra 311
Soora 443
Soothsayer 113
Sopd 437
Sopdu 437
Soped 437
Sophax 56
Sophia 8, 11, 21, 208, 231, 293, 351, 384, 408
Sopt 438
Sorama 146
Soramus 438
sorcerers and sorcery 18, 102, 129, 196, 209, 266, 277, 295, 296, 312, 315, 343, 361, 369, 426, 457, 482, 500, 510
Sorli 252, 447
sorrow 53
Soshyant 524
Sosphita 253
Soteira 79, 438
Soter 438, 522
Sothis 433, 438
Sotshirvani 489
souls 86, 124, 176, 177, 181, 254, 267, 270, 366, 384, 391
Source 448
Source of All Rivers 164
South 441, 469, 471, 497, 506
South Africa 398
South America 6, 33, 34, 40, 42, 51, 61, 82, 88, 103, 115, 122, 126, 135, 136, 154, 160, 164, 172, 176, 180, 197, 198, 204, 226, 231, 233, 244, 253, 256, 259, 266, 281, 303,

www.ebook3000.com

306, 314, 339, 341, 360, 364, 376, 384, 392, 455, 479, 509, 521
South Sea Islands 256
South Star 24, 115
South Wind 424, 446
Southeast Wind 302
Southwest 148, 485
Southwest Wind 351
Sovereign Chief 27
Sovereign God 279
sovereignty 92
sow 156, 300, 442, 489
Sown-men 438
Soyoko 435, 438
Spain 92, 213, 374
Spantaramet 438
Sparta 9, 12, 65, 67, 93, 215, 218, 284, 318, 344, 358, 381, 480
Sparte 12, 174, 438
Sparti 162, 229, 378, 438
spears 85, 102, 108, 199, 269, 296, 361, 395, 477, 510
speech 99, 106, 133, 149, 156, 232, 234, 307, 337, 467, 487, 488, 489, 490, 492
Speio 342, 438
spells 99
Spendarmad 438
Spenishta 438
Spenjaghrya 438, 494
Spenta Armaiti 45, 48, 138, 189, 211, 413, 438
Spentaramet 211, 438
Spentas 29
Spercheius 318, 438
Sphinx 4, 5, 125, 162, 170, 358, 438, 480
Spider Woman 84, 201
spiders 28, 50, 62, 64, 68
spindle 327
Spiniensis 438
Spinner 130
Spirit beings 91
Spirit Leader 148
Spirit of Apostasy 73
Spirit of New Fire 28
spirits 86, 111, 127, 138, 140, 143, 144, 147, 155, 185, 190, 222, 231, 262, 265
Spityura 248, 516
Splendid Robe 495
spoon 106
Spor 438
sport 509
Sprakki 209
springs 38, 48, 49, 66, 69, 95, 114, 133, 142, 245, 254, 336, 376, 410, 442
springtime 36, 50, 98, 107, 111, 116, 127, 134, 161, 169, 206, 242, 284, 328, 409, 495, 508
Sprund 209
squid 261
Squirrels 244
Sraddeheva 512
Sraddha 149, 258, 439
Sraddhadeva 439, 512
Sraosh 439
Sraosha 22, 45, 126, 138, 325, 400, 439, 514
Sravana 285
Sreca 155, 439
Sree 285
Sri 285, 301, 398, 439
Sri Dewi 439
Sri Lanka 203, 282, 398, 408, 434, 494, 499
Sri-gaja 439
Sringatpadini 439, 511
Srinmo 439
Srin-po 439
Sriphala 439
Srishok 439, 501
Sristikanta Lokeswara 439
Srnkhala 48
Srong-btsangombo 454
Sros 439
Srosh 439
Srvara 266, 439
sSin-rje-gsed-kyi-dkyil-kor 513
Ssu Ling 439
Ssu Ming 346, 439
Ssu Ta Chin-Kang 151, 439
Ssu-ling 178, 296
stags 13, 31, 79, 119, 151
stallion 270
Staphylus 67, 68, 152, 439
Star People 322
starlight 401
starling 106
Starry Night 104
stars 15, 42, 98, 108, 110, 118, 180, 200, 233, 323, 508, 513
Startassel 77
Starvation 210
state god 420
statesmen 238
stationers 475
steam 260
stellar goddess 454
Stenele 143
Step Pyramid 235
Sterculius 439
Sterculus 384, 415
Stercutius 439
Stercutus 12
Sterope 10, 76, 114, 118, 165, 217, 287, 359, 385, 387, 433, 439, 440
Steropes 10, 18, 137, 184, 440, 469
Sthalidevatas 148
Stheneboea 56, 96, 239, 240, 297, 381, 440
Sthenelaus 440
Sthenele 10, 76, 287, 318, 375, 439, 440
Sthenelus 35, 52, 115, 132, 194, 344, 377
Stheno 194, 315, 440
Stilbe 62, 230, 462
Stimulator 416
sting ray 293
stomach 48
stone 22, 33, 104, 109, 110, 124, 132, 224, 226, 241, 309, 353, 399
stone knife god 244, 460
Stone of Destiny 177, 290
Stone of Fal 477
stork 57, 183
storms 3, 13, 19, 20, 22, 23, 36, 58, 64, 66, 79, 80, 89, 111, 125, 154, 157, 167, 168, 180, 196, 197, 200, 205, 228, 235, 237, 242, 254, 262, 270, 271, 278, 279, 300, 304, 305, 309, 342, 354, 361, 368, 404, 406, 423, 427, 445, 456, 461, 467, 474, 510
Straits of Messina 417
strangulation 354
Stratius 57, 440, 464
straw 350
Straw Mirror 460
streams 107, 137, 467
La Strega 94
strength 98, 100, 300
Strenia 440
Stribog 144, 440, 492
strife 14, 153, 294, 520
Striped One 225, 459
Stromkarl 440
Stromkarls 350
Strophades 522
Strophius 393
Strophius I 51
Strophius II 165, 393
Strymo 76, 129, 215, 216, 286
Strymon 67, 113, 176, 339, 440
Stupa 7, 46, 440
Stymphalian Birds 213, 440
Stymphalus 18, 378, 441
Styx 11, 101, 123, 131, 162, 194, 201, 275, 289, 345, 356, 370, 376, 382, 441, 455, 457, 462, 521, 523
Su 352
Su Ch'e 122
Su Shi 122
Suada 25, 26, 441
Suadha 26
Suaha 141, 263, 406, 441
Sualtam 144
Sualtim 135
Subala 185
Subbu-Khai-Thung 250, 252, 381, 429, 441
Subhadra 69, 147, 441
Subramanya 263
success 186, 430, 485
Succuba 441
Succubus 237, 441
Sucellos 139, 336, 431, 441, 464
Suchos 417
Suci 26
Sudalaiyadi 338, 427, 441
Sudan 59, 95, 98, 350, 352, 475, 504
Sudarsana 433, 441
Sudarshana 397, 416, 441
Suddhodana 441
Sudhanvan 403, 404, 441, 489
Sudjaje 441
Sudre 441
Sudri 83, 160, 321, 351, 441, 506
Sudyumna 441
Suetiva 124
suffering 103, 508
Suffete 103, 441
Sugriva 91, 203, 254, 398, 401, 441, 442, 454, 491
Suhgurim 309
Suhiji-ni no Mikoto 39
Suhrim 309
suicide 9, 21, 56, 57, 66, 68, 75, 82, 90, 96, 113, 115, 129, 138, 145, 146, 175, 176, 299, 316, 323, 354, 359, 372, 378, 380, 386, 406, 415, 423, 440, 462, 493
Suilap 89
Sui-tengo 355, 442
Suitengu 442, 493
Sujang-Gnoi-Rise 250, 252, 429, 442
Suka-na-Biko 442
Sukan-bikona 442
Sukanthi 63
Sukanya 299, 442
Sukapreyasi 442, 491
Sukarapreyasi 390
Sukarasya 442
Sukati 442
Sukha 492
Sukhavati 45, 120, 149, 193, 293, 332, 442
Sukhos 417
Suko 442
Sukrip 441
Suku-na-biko 260, 361, 442
Sukuna-biko 442
Sukuna-bikona 442
Sukuna-biko-na-no-kami 442
Sul 442
Suleyman 251
Sulman 413
Sulmus 356, 442
Sulochana 442, 511
Sumati 187, 264, 409, 442
Sumatra 93, 412
Sumaya 313
Sumbha 128, 158, 257, 442
Sumer 3, 5, 8, 13, 26, 28, 34, 36, 37, 38, 39, 42, 49, 51, 55, 58, 59, 60, 63, 64, 65, 71, 73, 75, 86, 88, 92, 93, 95, 96, 104, 123, 133, 139, 144, 152, 158, 161, 162, 165, 167, 168, 168, 170, 171, 172, 176, 184, 185, 190, 192, 196, 198, 203, 220, 234, 236, 238, 241, 242, 247, 255, 270, 272, 273, 280, 284, 285, 291, 295, 296, 300, 304, 309, 310, 324, 330, 333, 334, 335, 336, 339, 342, 345, 346, 347, 349, 353, 355, 376, 405, 408, 414, 423, 432, 433, 455, 477, 483, 484, 486, 487, 497, 520, 521, 524
Sumerians *see* Sumer
Sumeru 319, 442
Sumitra 285, 398, 399, 511
Summano 484
Summanus 468
summer 220, 314, 443, 447
Sumo 244, 302
Sumul 274, 443
Sumuqan 167, 443
Sumur 9, 443
sun and horse goddess 173
sun boat 5
sun 5, 14, 24, 26, 32, 34, 41, 49, 53, 64, 67, 69, 71, 79, 84, 90, 95, 96, 99, 101, 103, 106, 107, 109, 110, 111, 117, 120, 123, 129, 131, 144, 159, 164, 168, 182, 183, 191, 193, 201, 204, 206, 210, 215, 220, 225, 227, 230, 232, 235, 239, 265, 269, 272, 275, 292, 305, 306, 309, 310, 313, 324, 325, 328, 333, 335, 338, 340, 342, 345, 346, 368, 382, 395, 396, 397, 411, 412, 420, 423, 424, 426, 430, 436, 443, 444, 447, 449, 451, 456, 460, 472, 478, 483, 498, 500, 503, 507, 514, 516
Sun Hou-tzu 443
Sun of Night 23
Sunaman 275
Sunda 69, 484
Sundara 283, 427
Sundareshwar 427
Sung Chiang 443
Sung Kiang 443
Sung Ti 146, 443
Sung-ti 466
Sung-tsi Niang-niang 443
Sung-Tzu-Naing-Naing 277, 278, 443
Sun-pin 443
sunrise 45, 235
sunset 34, 93, 422, 435, 508
Sunstone 447
Suntra 443
Supai 443
Suparnas 187, 443
Supay 51, 443
Superior Heaven 423
Support 237, 436, 452
Supporter 435
Supporters of the Houses 511
Suprabha 69
Supratika 152, 293
supreme deities 33, 34, 37, 39, 43, 46, 48, 65, 78, 84, 87, 120, 132, 164, 180, 197, 206, 228, 243, 253, 254, 267, 268, 269, 271, 272, 279, 283, 290, 307, 314, 329, 352, 354, 362, 369, 427, 442, 471, 473, 482, 507, 520, 521
Sura 77, 280, 281, 443
Surabhi 259, 335, 349, 443
Surabhidatta 63
Suradevi 443
Surapamsula 63
Suras 15, 274
surgery 299, 360
Suris 15

Surisi 148
Surisvari 148, 444
Surja 444
Surpanaka 429
Surt 444
Surter 444
Surtr 82, 179, 331, 415, 444, 496
Surtur 444
surveying 464
Surya 15, 24, 25, 26, 50, 71, 77, 105, 121, 160, 186, 211, 237, 257, 263, 276, 280, 293, 310, 325, 374, 393, 397, 416, 437, 441, 444, 447, 453, 485, 486, 493, 494, 498, 499, 500
Surya Narayana 444
Surya-Bai 444
Suryabhauma 152
Surya-Narayana 498
Suryi 513
Sus'istinako 446
Susanawo 220
Susano 445
Susanoo 445
Susa-noo 445
Susano-o-no-Mikoto 445
Susanow 64
Susanowo 41, 42, 78, 166, 183, 232, 281, 282, 361, 363, 442, 445, 464, 476, 482, 503, 518
Susa-no-wo 445
Suseri-Hime 361
Susetka 155
Sussistinnako 446
Sussitanako 446
sustenance 482
Sut 85, 421, 446, 468, 520
Sutala 336
Sutalidihi 446
Sutekh 421
sutras 149, 389
Suttee 415
Suttung 179, 191, 294, 415
Sutty 148
Sutur 101
Suvetar 446
Suvinenge 446
Svadha 385
Svadilfare 446
Svadilfari 446
Svaha 26, 441
Svald 233
Svalin 5, 436, 446
Svanhild 447, 464
Svanhvit 501
Svanni 209
Svantevit 446, 447
Svantovit 407, 446, 447
Svantrovit 447
Svarga 415, 447
Svarga Loka 447
Svar-Loka 293
Svarof 446
Svarog 446
Svarogich 446
Svarozic 446
Svarozits 446
Svarri 209
Svart Alfar 160, 166
Svart-Alfa-Heim 36, 160
Svartalfaheim 446
Svartalfar 447
Svart-Alfar 447
Svartheim 72
Svasud 443, 447
Svasuthr 451, 447
Svayam-bhuva 308, 312, 447
Svein 209
Svetovid 447
Sviagod 181
Sviagris 447
Svipdag 22, 83, 197, 318, 357, 434
Svol 165
Svosud 447
Svyatogor 104
Swaha 26, 441
swallows 18, 264, 478
swamp 111
swan 18, 54, 62, 103, 106, 110, 116, 137, 203, 341, 478
Swanhild 447
Swan-maidens 496, 497
Swar 390
Swarga 41, 69, 77, 185, 186, 237, 238, 258, 275, 293, 319, 373, 401, 409, 447, 499, 512
swastika 155, 444, 464, 524
Swathed One 367
Swayambhu 15
Sweden 156, 299, 358, 440
Sweeper of Pine Needles 411
swelling mold 279
Swetavarahi 491
Swift Heavenly Great Ears 43
Swift One 187
Swift Runner 462
swine 130; *see also* boar; pigs; sow
Swiss Alps 93
Switzerland 71
Sword of Nuada 477
Sword of Wisdom 307
swords 53, 97, 99, 106, 179, 221, 281
Syama 257, 427, 447, 512
Syamantaka 447
Syamatara 454
Syavana 100
Sychaeus 151
Sydycos 447
Sydyk 324, 417, 447, 448
Syenabhrita 436, 448
Syenovik 155
Syga Tojon 70, 483
Sykites 152
Sylg 165
Syllis 62
Sylvan 431
Sylvanus 431
Sylvia 405
Syn 448
Synerasis 21, 351
Synia 448
Synnytar 296
Syr 181
Syren 433
Syria 8, 13, 14, 16, 22, 24, 37, 43, 53, 58, 61, 70, 75, 80, 82, 86, 87, 93, 122, 132, 200, 208, 220, 264, 266, 380, 384, 404, 408, 414, 417, 422, 424, 447, 451, 514
Syria Dea 61
Syrus 432
Sythian 71
Szechwan 121

Ta 86, 340
Taapac 497
Taaroa 448, 452
Ta'aroa 177, 366, 407, 448, 467, 468, 471
Taaroa Kanaloa 452
Tabakea 337, 448
Tablet of Destinies 272
Tablets of Ashurbanipal 97
Tablets of Destiny 236, 309
Tablets of Fate 158, 332, 347, 448, 524
Tabuerik 404, 448, 449
Tabu-Eriki 448, 452
Tacatecutli 449
Tachen 450
Ta-Djesant 477
Taenarum 67
Tafa'i 351, 455
Ta-Fan 448
Tagaloa 385
Tages 449
Tagtug 152
Taguacipa 449, 497
Tahiti 207, 220, 312, 351, 366, 405, 406, 452, 455, 485
Tahiti Tokerau 467
Tahmouras 223
Tahmurath 146
Tahu 79
Tahuantin Suyu Kapac 10, 306, 449, 485
T'ai Ch'ing 291, 412
T'ai Shan 449, 478
T'ai Shang San Kuan 412
Taikomol 362
Tailtiu 449
Tain Bo Cuailnge 449
Tain Bo Cuillaigne 300
Taino Indians 78, 197, 239, 299
Taipan 196, 397
Taishaku 237, 449
T'ai-shan 449
T'ai-shan kun wang 466
T'ai-Shan Niang-Niang 425
T'ai-Shang Lao-chun 286, 412
Tait 449
T'ai-Tsung 317
Taiwan 298
T'ai-Yin Huang-Chun 122
T'aiyo Tato 449
T'ai-yo Ta-to 449
T'aiyuehtati 425
T'ai-yueh-ta-ti 478
Tajikaroo 41, 449
Taka-haya-susa-no-wo 445
Takama-no-hara 40, 449, 450
Taka-Mimusubi 39, 260, 449
Taka-mi-musubi 41, 446, 449
Takami-Musubi 449, 450
Taka-okami 246, 255, 280, 449, 450
Taka-pime-no-mikoto 449, 464
Takaroa 399
Take 83, 445, 450, 492
Takehaya Susanowo 39, 41, 246, 445
Take-mika-zuchi 446, 450
Take-mikazuchi 450
Take-mi-kazuchi 450
Take-minakata 361, 450
Takemiskazuchi no Mikoto 450
Takhmoruw 223, 516
Taki-mi-Mushubi 43
Takiri-bime-no-mikoto 41, 464
Taki-tsu-hiko 450
Takitsu-hime-no-mikoto 464
Takitu-pime-no-mikoto 41
Takkanna 308
Takma Urupa 248
Takotsi Nakawe 450
Takshaka 282, 333, 450
Takuskanskan 450
Talaus 6, 17, 76, 175, 298, 314, 379, 391, 450
Taliesin 45, 267
talisman 111, 451
Talking God 206
Tallai 70, 384, 451
Talos 138, 451
Talus 378, 451
Tamaa 450
Tamagostad 127, 129, 162, 321, 324, 368, 395, 451, 500, 523
Tamaiti-ngava-ringavari 372, 476
Tama-nui-a-te-ra 313
Tama-nui-rangi 209
Tama-poulialamafoa 452
Tamar 236, 242, 451
Tama-Rangi 313
Tamats 451
Tama-Yori-Bime 251, 473
Tamazcalteci 129, 451, 471
Tambotocco 306
Tambu Quiru 306
Tamek-Vui 273
Tamesis 292
Tamil 31, 90, 257, 262, 274, 314, 431
Tammuz 3, 14, 17, 54, 58, 65, 73, 75, 94, 95, 137, 142, 146, 158, 159, 170, 172, 192, 198, 242, 270, 324, 334, 346, 367, 437, 451
Tamoanchan 451
Tamon 102, 425, 427
Tamon-tenno 102
Tamontennu 102
Tamoza 451
Tamra 187, 451
Tamtu 466
Tamuras 223
Tamurath 223
Tan 44, 471
Tanagra 115, 213
Tanaoa 79, 364, 452
Tandava 427
Tandu 338, 452
Tane 79, 207, 217, 218, 239, 240, 261, 303, 313, 330, 344, 366, 372, 373, 397, 399, 405, 452, 456, 467, 476
Tane-mahuta 60, 452
Tanen 453, 455
T'ang Emperor 519
Tangaloa 405, 452, 478
Tangaloa-atu-logo-logo 452
Tangaloa-eiki 452
Tangaloa-tufuga 452
Tangara 21, 166, 452
Tangaro 394
Tangaroa 60, 79, 178, 207, 234, 261, 307, 313, 372, 373, 405, 406, 448, 452, 456, 484, 488, 492, 494
Tangere 452
Tangeri 453
Tangia 452
Tangiia 372, 405, 476
Tango 452, 492, 494
Tangri 338, 452
Tanilai 471
Tanit 75, 87, 453
Tanit Pene Ba'al 87
Tanith 453
Tanka 272
Tanngniostr 453
Tanngnjost 463
Tanngnost 453
Tanngrisni 453, 463
Tanngrisnr 453
Tannin 290, 329, 397
Tano 8, 101, 453
Tantalos 453
Tantalus 23, 47, 81, 152, 171, 245, 349, 359, 377, 453
Tantra 25, 422, 513
Tantraism 301, 422, 473, 489
Tantrayana 149
Tantric Buddhism 422
Tanunapat 25, 453
Tanunen 453
Tanzania 283
Tao 182, 453
Tao Chun 291, 412
Tao Hsuan 232
Tao jiao 286
Taoism 68, 121, 122, 123, 125, 156, 163, 221, 265, 286, 371, 378, 412, 424, 425, 465, 467, 508, 518, 519
Ta'oroa 452
Tao-shi 473
tapa 266
Tapa-Loka 293
Taparimarru 392
Tapati 453

www.ebook3000.com

Taphos 118
Tapio 321, 453
Tapiola 453
Taquacipa 449
Taquatu 453, 510
Tara 84, 91, 92, 124, 146, 150, 155, 257, 278, 300, 454, 489
Tara Utpala 454
Tara White 454
Tara-Amba 454
Tara-Dharani 454
Tarahumara 364
Taraka 263, 454
Tarakamaya 454
Taraka-Maya 454
Taramis 454
Taran 193
Ta-ranga 313
Taranga 313, 454
Taranis 454
Tarapaca 497
Tarascan 114, 477
Taraswin 187
Tar-Ata 78, 453
Taraxhippos 192, 454
Ta-ret 75
Tareya-Wagon 454
Tarhuhyiawahku 454
Tarik 143, 455
Tariki 148, 455
Tarnush 251
Tarshishim 53
Tartaros 455
Tartars 89, 283, 303, 414, 452, 458
Tartarus 31, 115, 122, 135, 143, 162, 167, 170, 184, 201, 208, 211, 251, 318, 324, 385, 434, 441, 455, 469, 477, 480, 518, 522
Tartus 455
Taruma 478
Tarutius 455
Ta-Sent-Nefert 448
Tashi Lama 46
Ta-Shih-Chih 448
Tashmetrum 332, 455
Tashmishu 279, 424, 459
taste 225
Ta-tanen 391, 453
Ta-tchesert 477
Tathagatas 46, 47, 140, 150, 410, 488
Tathenen 453
Tatjenen 455
Tatsuta-hiko 182, 426
Tatsutsa-hime 182, 426
Tattoo 10
Tatunen 455
Tatzitzebe 115, 455
Tauchca 244
Taueret 455
Tauret 408
Tauris 240
Ta-urt 455
Taurt 462
Ta-Urt 466
Tauru 48, 455
Taurvi 138, 455, 520
Taus 85
Taut 72
Tauthe 63, 96, 466
Ta-uz 448, 451
Tawals 288
Tawendonare 455
Tawenduare 240, 455
Ta-weret 98
Taweskare 518
Tawhaki 211, 256, 262, 343, 400, 455, 456, 485, 503
Tawhiri 60, 207, 372, 399, 452, 456, 476
Tawhiri-ma-tane 452, 456
Tawhiri-ma-tea 3, 59, 60, 64, 399, 456
Ta-whiri-ma-tea 385
Tawisara 518
Tawiscara 78, 167, 518
Taygeta 385
Taygete 165, 284, 440, 456
Tchabu 456
Tcheft 242, 456
Tchemtch-hat 4
Tchesef 477
Tcheser-tep 32, 61, 75, 420, 456, 457
Tcheser-tep-f 457, 483
Tchet-s 380, 417, 456
Tcolawitze 456
Te Bo Ma 337
Te enua marama o Vatea 494
Te Maki 337
Te Temu 448, 452
Te Tumu 79, 372, 399, 448
teachers/teaching 102, 108, 258, 513
Te-aka-ia-oe 83, 494
Teba 477
Tebati 4
Tebat-neteru-s 340
Teb-her-kehaat 477
Tebi 456
Tecciztecatl 133, 320, 335, 456, 518
Teccuciztecatl 456
Technites 27
Tecmassa 31, 456
Tecpatl 10, 456, 471
Tectamus 19, 156, 456
Tecuciztecatl 456
Te-enua-te-ki 476
Tefenet 456
Tefnut 4, 54, 81, 168, 189, 238, 244, 269, 316, 340, 353, 396, 428, 456, 457, 464
Tegea 67, 118, 440
Tegeates 9, 137, 457
Tegid Voel 267
Tehabi 457
Teharaonhia-wakon 518
Teharaonhiawagon 518
Teha-Tuat 477
Tehennu 72
Tehenut 341
Teheser-Tep-f 456, 457
Tehom 466
Tehuti 457, 464
Te-Io-Ora 239
Teiresias 457, 468
Teirnyon Furf Liant 391
Teishaku-ten 345
Teka-hra 5, 457, 477
Tekemiaau 5
Tekhi 457
Tekikinto 337
Tekikitea 337
Tekitekite 337
Tekkeitsertok 457
Telamon 18, 31, 35, 134, 162, 215, 377, 378, 382, 457, 460
Telavel 457
Telchin 457, 461
Telchines 138, 201, 457, 461, 472, 484
Telchis 62, 349, 383, 457
Teledamas 23, 116, 378, 457
Teledice 115, 349, 383, 457
Teledyne 62
Telegonus 114, 130, 457
Telemachus 114, 130, 457
Telemon 215
Telephassa 25, 67, 112, 129, 165, 174, 381, 457, 458, 461
Telepinu 458
Telepinus 198, 203, 260, 309, 451, 458
Tell el-Amarna 33
Tellus 184, 403, 458, 459
Tellus Mater 119, 458
Te-lo-Mate 239
Telpochtli 460
Telugu 331
Tem 4, 79, 81, 168, 244, 340, 457, 458, 478
Te-manava-roa 83, 494
Tem-Asar 81
Temau 458
Tempellec 339
tempests 105; *see also* storms
Temple Guardians 159
Temple of Jupiter 40
temples 279
temptation 109, 308
Tem-sep 75
Temt 458
Temtemtch 4
Temtith 269
Temtu 477
Temu 81, 417, 458
Ten Hells 512
Ten Kings of Hell 384
Tenages 458
Tenazuchi-no-kami 282, 458
Tendai 140
tenderness 56
Tenen 453
Tenes 62
Tengere Kaira Kan 89, 458
Tengeri 452
Tengri 452
Tengu 274, 458
Tenity 269
Tenno 251
Tenochtitlan 226
Tenos 522
Tenshodaijin 41
Ten-sho-dai-jin 41
Tenshodaijin 458
Tenshokodaijin 41
Tenshoko-daijin 41
Tentamides 458
Tent-Baiu 458
Tentemic 226
Tentit-uhesqet-khat-ab 458
tents 247
Teo-Kipaktli 133
Teotihuacan 459
Teotihuancan 459
Teoyaoimquit 225, 295, 459
Teoyaomiqui 459
Tepanec 114
Te'papa-rairai 494
Te-parai-tea 478
Te-paraitea 492
Tepen 459
Tepeu 197, 228, 387, 459
Tepeyollotl 283, 295, 459, 460
Tepeyolohtli 459
Tephet-shetat 269
Tepi 4, 5, 459, 477
Tepictoton 459
Te-Po-ma-Te-Maki 144, 456
Tepoztecatl 459
Tepoztlan 459
Tepthera 458
Tep-tu-f 58
Tepu 425
Tepui 417, 459
Ter 459
Tera 403
Tera, Mount 35, 126
Terah 8, 166, 173
Teraph 459
Teraphim 459
Tere 95, 344, 459, 478
Tereus 66, 104, 244, 459
Terminalia 378
Terminalius 459, 522
Terminus 459
Terpimbrotos 210
Terpsichore 11, 217, 330, 433, 459
Terra 11, 20, 183, 184, 205, 459
Terra Mater 343
Terrible 89, 99, 148, 257, 374
Terrible Face 214
Terrible Woman 426
Terrifying Goddess 100, 257
terror *see* fear
Tertiana 178
Tes-aha-Ta-thenen 340
Tes-ermen-ta 340
Tesert-ant 379, 477
Teshub 58, 212, 279, 309, 404, 424, 458, 459, 460
Tes-khem-baiu 340
Tes-neb-terer 340
Tes-sekhem-aru 340
Tes-sept-nestu 340
Tes-sheta-em-thehen-neteru 340
Tes-sma-kekui 340
Tessub 404
testicles 223, 237, 409
Testius 359
Tet 460
Teta 32
Te-tangaengae 83, 494
Tetenen 453
Teteoinan 470
Teteoinnan 129, 245, 451, 460, 470, 471
Tethus 165, 460
Tethys 11, 38, 47, 64, 74, 76, 80, 112, 114, 118, 131, 134, 135, 152, 155, 171, 174, 175, 184, 190, 202, 229, 233, 235, 236, 284, 300, 316, 317, 320, 333, 345, 356, 378, 379, 381, 385, 391, 404, 412, 416, 431, 438, 440, 441, 460, 461, 462, 523
Tethyus 113
Tetu 61
Tetzcotzingo 460
Teu 480
Teucer 31, 93, 215, 460
Teufel 148
Teuhie 460, 478
Teutamias 142, 460
Teutates 460
Teutons 19, 22, 23, 25, 29, 34, 35, 36, 38, 39, 41, 42, 46, 49, 50, 52, 53, 55, 66, 72, 74, 77, 82, 83, 89, 90, 91, 93, 94, 95, 97, 98, 101, 102, 104, 105, 139, 140, 145, 153, 154, 155, 156, 159, 161, 164, 165, 166, 177, 178, 179, 180, 181, 183, 184, 187, 188, 189, 190, 191, 192, 193, 196, 197, 198, 199, 202, 204, 206, 209, 210, 211, 213, 214, 215, 220, 221, 224, 226, 229, 230, 231, 232, 233, 241, 243, 245, 247, 252, 253, 254, 262, 267, 273, 283, 284, 287, 288, 289, 291, 293, 294, 295, 297, 300, 304, 306, 309, 311, 315, 318, 321, 322, 324, 326, 329, 330, 331, 332, 333, 335, 337, 338, 340, 343, 344, 345, 350, 351, 352, 357, 358, 359, 361, 362, 364, 366, 368, 397, 399, 400, 402, 404, 406, 407, 408, 415, 417, 421, 430, 431, 432, 434, 435, 436, 437, 441, 443, 444, 446, 447, 448, 453, 462, 463, 464, 465, 469, 479, 480, 481, 482, 483, 485, 486, 487, 490, 491, 493, 494, 495, 496, 497, 500, 501, 505, 506, 515, 516, 517, 524
Te-vaerua 83, 494
Texcatlipoca 125, 163, 244, 460, 471
Texcatzoncatl 118, 460
Text of Unas 32
Teyron 403
Tezcatepuca 460
Tezcatlipo'ca 460
Tezcatlipoca 81, 114, 133, 226, 288, 295, 338, 368, 384, 395, 456, 460, 469, 470, 471, 481, 508, 509, 519

Tezcatzontecatl 460
Tgorem 162, 460
Thags 257
Thakurani 196
Thalass 466
Thalassa 136, 201, 457, 460, 461, 466, 484, 523
Thalatth 466
Thalestris 42
Thalia 25, 133, 195, 212, 330, 370, 461
Thallo 116, 222, 461
Thaltlahale 471
Thames 292
Thammuz 414, 451
Thamte 466
Thamyris 243, 292
Thanatos 22, 118, 122, 170, 266, 327, 328, 351, 414, 461
Thantos 230, 461
Thasos 35, 440
Thasus 112, 165, 381, 457, 461
Thauk 463
Thaukt 463
Thaumacus 67
Thaumas 20, 135, 165, 174, 184, 205, 240, 342, 356, 383, 385, 387, 461
Thawab 16
Thea 123
Theano 10, 25, 56, 135, 146, 192, 286, 316, 320, 386, 461
Thebe 56, 74, 360, 376, 461
Thebes 12, 18, 24, 25, 33, 43, 44, 47, 54, 57, 66, 112, 131, 153, 167, 170, 173, 175, 238, 244, 284, 287, 290, 297, 314, 315, 316, 317, 328, 358, 359, 378, 386, 387, 419, 422, 438, 455, 522
Thegn 209
Theia 119, 135, 169, 175, 184, 210, 230, 356, 375, 419, 461
Theias 331
Thein 461
Theispas 71, 268, 399, 424, 461
Thekkr 160
Theletas 21, 351
Thelxiepeia 461
Thelxion 62, 349, 383, 457, 461
Themehu 4
Themis 50, 76, 81, 116, 130, 135, 151, 152, 164, 174, 177, 184, 201, 216, 222, 253, 254, 327, 461, 462, 523
Themiscyra 16
Themiste 51, 175, 235, 286, 461, 462
Themisto 79, 172, 230, 392, 417, 462
Then-aru 4
Thenemi 75
Thenenet 242
Then-neteru 298
Thenoe 462
Thenti 4
Theoclymenus 391, 462
Theodamas 229
Theonoe 35, 113, 391, 462
Theophane 194, 462
Theoris 455, 462
Theotokos 343
Thepla 38
Thermuthis 402
Thersander 192, 433
Thersites 27
Theseus 9, 20, 22, 23, 57, 68, 116, 119, 135, 146, 152, 176, 219, 240, 309, 314, 315, 323, 359, 379, 380, 385, 416, 439, 463, 497
Thes-hrau 458
Thespiae 130, 318, 438
Thespius 57, 174, 297, 389
Thesprotus 81
Thessalus 121, 171, 249, 381, 462
Thessaly 11, 21, 35, 57, 67, 79, 117, 132, 133, 240, 245, 287, 299, 342, 363, 367, 377, 378, 382, 410, 433, 462, 474
Thestius 38, 66, 67, 114, 146, 175, 230, 288
Thestor 35, 113, 290, 462
Thesu 458
Thet 460
Theta-enen 4
Thethu 61, 420, 462
Thetis 11, 12, 171, 208, 212, 342, 356, 374, 377, 441, 462
Thevadas 148
Thia 461
Thialfi 226, 406, 435, 462
Thiassi 180, 233, 350, 434, 462
Thiazi 462
Thien 466
thieves/theft 19, 71, 128, 204, 288, 395, 443
Thing 462, 463
Thingstead 462
Thingsus 480, 524
Thir 209
Thirst 207, 308
This 54
Thixo 160, 463, 476
Thjalfi 83, 462
Thjasse 462
Thjasse-Volund 233
Thjazi 462
Thjodvara 164
Thlavatth 466
Tho-ag 15
Thoas 27, 68, 152, 174, 178, 190, 201, 230, 249, 382, 463, 469
Thobadestchin 173, 463
Thobadzistshini 51, 339, 463, 515, 518
Thoeris 98, 462
Thok 90, 294, 463
Thokk 463
Thomagata 180, 463
Thomagostad 463
Thompson 278
Thonenli 463, 515
Tho-og 15
Thoon 190, 219, 463, 469
Thoosa 383, 387, 463
Thor 22, 39, 66, 83, 98, 101, 102, 139, 155, 166, 180, 189, 196, 197, 204, 220, 224, 226, 229, 230, 231, 238, 252, 253, 267, 294, 300, 310, 315, 326, 357, 361, 380, 397, 406, 423, 430, 432, 441, 453, 462, 463, 465, 483, 486, 497, 499, 523
Thora 254, 397, 464
Thorin 160
Thot 367
Thoth 3, 4, 43, 44, 48, 60, 76, 154, 168, 172, 214, 235, 299, 339, 340, 353, 359, 392, 396, 418, 421, 425, 437, 457, 464, 505
Thought 168, 226
Thousand Testicled One 237, 409
Thout 464
Thouth 464
Thouti 464
Thrace 6, 10, 17, 25, 65, 66, 97, 104, 146, 152, 157, 174, 176, 205, 297, 365, 381, 383, 386, 408, 461, 522
Thracia 463
Thraell 464
Thraetana 177, 464
Thraetaona 28, 85, 177, 203, 464, 465
Thrall 29, 464
Thralls 29, 209
Thrasymedes 57, 440, 464
Thrbadestchin 464
thread 68
Three Emperors 182
Three Goddesses of Munakata 449, 464
Three Great Emperor Agents 412
Three Heavens 412
Three Isles of the Blest 412
Three Legged Ass 464
Three Norms 174
Three Origins 412
Three Supreme Agents 412, 429
Three Tridynami 83
Three Worlds 148, 412, 474
Three-Eyed 25, 406, 475
Three-Mothered 25, 26, 406, 427, 475
thresholds 115
Thrita 177, 203, 266, 464, 474
Thrita Athwya 464
Throd 463
thrones 53, 106, 109, 220, 241
Thronia 20, 25, 142, 382, 465
Thror 160
Throttler 85
Thrud 39, 300, 430, 463, 465
Thrudgelmer 465
Thrudgelmir 97, 465, 517
Thrudheim 463, 465
Thrud-Heim 465
Thrudheimr 465
Thrud-Vang 465
Thrudvangr 465
Thrudvarg 465
Thrurinn 160
Thrym 180, 465
Thrymr 465
Thu 424
Thudr 357
Thugs 257
thumb 179
Thunaer 463
Thunar 253, 463, 465
Thunaraz 463
thunder 13, 14, 20, 24, 27, 29, 47, 54, 72, 85, 86, 87, 117, 136, 155, 160, 194, 197, 200, 203, 211, 218, 222, 253, 261, 262, 265, 288, 294, 337, 352, 370, 379, 380, 384, 396, 401, 423, 441, 452, 453, 454, 455, 463, 469, 478, 483, 487, 508
thunder drum 203
Thunderbird 211
thunderbolt 136, 489
Thunderbolt Sow 156, 489
thunderstorms 114, 366, 379, 454, 459, 472, 476, 482
Thuner 465
Thunor 463, 465
Thunupa 465, 497
Thur 463
Thuremlin 143, 158
Thursday 464
Thviti 193, 465
Thyestes 20, 81, 218, 377, 453, 465
Thyia 62, 118, 147, 465
Thymbris 523
Thynius 381
Thyone 152, 419, 465
Thyoneus 152, 465
Thyr 464
Thyria 62
thyrsus 153, 317
Ti 423
Tiahuanaco 132
Tiamat 52, 55, 61, 63, 64, 94, 122, 142, 143, 161, 226, 272, 284, 285, 290, 309, 330, 334, 363, 466, 510, 511
Tiamuni 466
Tian 423, 466
Tianquiztli 466
tiara 98
Tiawath 466
Tiber 405, 501
Tibet 7, 9, 15, 32, 33, 46, 47, 48, 55, 70, 84, 99, 105, 120, 123, 124, 138, 140, 141, 149, 155, 156, 164, 185, 196, 215, 225, 248, 262, 264, 267, 268, 269, 272, 280, 282, 287, 295, 298, 301, 303, 304, 307, 310, 315, 320, 326, 334, 336, 369, 375, 389, 393, 400, 402, 408, 410, 413, 439, 454, 473, 475, 481, 490, 497, 504, 511, 512, 513, 523
Ticci Viracocha 497
Ticholtsodi 466, 472
tides 36, 405
T’ieh-Kuai Li 68, 466
Tieholtsodi 134, 466, 471
T’ie-kuai Le 163
T’ie-kuai Li 466
T’ien 466, 519
Tien 466, 519
T’ien Hou 467
T’ien Hsien Yu Nu Pi Hsia Yuan Chu 519
T’ien K’ou 170
T’ien Kou 122
Tien Li 122
T’ien Mu 265
Tien Mu 288, 467, 519
T’ien Pao 123, 412, 518, 519
T’ien Wang 317
T’ien-chu 265
T’ien-Hou 425
T’ien-Kuan 412, 429, 465, 467
Tien-Kuan 467
T’ien-lung 505
Tien-Mu 178, 467
T’ien-Shang 467
T’ien-shih 122
T’ien-tsun 518
T’ien-wang 439
Tien-Wang 467
Tierra del Fuego 29, 34, 221, 255, 266, 368, 453, 487, 510, 511
tigers 55, 108, 178, 227, 264, 288
Tigranes 332
Tigris 58, 167, 348, 467
Tihamtu 466
Ti’i 452, 467
Tii 467
Tii-Maaraatai 448, 467
Ti’in 466
Tiitii 313
Tii-Tokerau 467
Ti-Jean Petro 310, 465
Tiki 217, 240, 452, 467
Tiki-aw-a-ha 452
Tiki-kapakapa 217, 452, 467
Tikitohua 217, 452, 467
Tiksnamanjusri 467
tiku 427
Ti-Kuan 412, 429, 465, 467
Til-bu-ma 272, 422, 467
Tilo 467
Tilottama 69, 468
Timalcus 240, 315
Timandra 381
Timatekore 476
Time 22, 135, 256, 257, 292, 406, 421, 427, 464, 505, 509, 512
Timi-iti 177, 407, 448, 468
Timirau 468
Timondonar 68, 302
Timo-taata 234, 452, 468
Ti-mu 466, 505
Tina 136, 253, 468
Ting 462
Tinga 56

www.ebook3000.com

Recharge and cut around to the Armpits

1. Recharge In the universe, pour Chi over the crown down through the body and lower your hands down to the heart center. Touch with the fingertips. Move your hands around under your armpits, extending the Chi like laser beams cutting open this Middle Tan Tien. Pause under the armpits as you send the Chi into the center.



Fig. 3.52 *Cut open the Middle Tan Tien by cutting around the armpits.*

2. Continue to move your hands around to your back at T5/T6, touch and send the Chi from back to front. Let the beam of Chi penetrate out through the heart center to the universe in front of you. Then, move the hands back around the sides to the front, cutting as you go.



Fig. 3.53 *Chi beam from T5/T6 penetrates to the Heart Center in front.*

Tingir 452
Tinguian People 14, 255, 271
Tinia 468
Tinilau 468
Tinirau 235, 406, 468, 492, 494
Tiphys 13, 67, 170, 382, 468
Tipperary 162
Tir 84, 85, 446, 468, 469, 520
Tir na n'og 477
Tirawa 369, 423, 468
Tirawa Atius 468
Tiresias 457, 468
tirthankara 301
Tiryns 67, 151, 380
Tisalat 466
Tisandrus 171, 249, 381, 468
Ti-shih 465
Tishtrya 33, 204, 228, 301, 468, 501, 514
Tishtryas 515
Tisiphone 171, 183, 315, 468
Tisnavati 285
Ti-suin 225, 516
Titaea 184, 403, 459, 469
Titaea Magna 66
Titae-Aretia 66
Titans 11, 19, 75, 76, 80, 101, 104, 116, 118, 123, 135, 174, 175, 184, 201, 208, 211, 230, 231, 249, 275, 326, 345, 351, 356, 364, 380, 382, 391, 416, 419, 441, 455, 461, 462, 469, 484, 521, 523, 525
Titania 36
Tithonus 118, 166, 169, 215, 317, 380, 469
Titlacauan 460, 469
Ti-tsang 276, 465, 466
Ti-Tsang Wang-P'u-sa 251, 276
Ti-tsang-wang-pu-sa 313, 465
Tityos 190, 469
Titysus 165
Tityus 62, 174, 364, 469
Tiu 522
Tiur 469
Tiw 480
Tiwaz 480
Ti-ya 466, 505
T'i-Yu 128
Ti-yu 430, 466, 475, 512
Tjausul and Othale 469
Tjikantja Brothers 469
Tjinimin 397
Tlacauepan 469
Tlacaxipehualiztli 508
Tlachgo 164
Tlacht 164
Tlahuitzin 514
Tlahuizcalpantecuhtli 395, 470, 472
Tlalchitonatiuh 288
Tlaleutli 470
Tlaloc 81, 120, 121, 244, 288, 295, 469, 481, 509
Tlaloc, Mount 469
Tlalocan 469, 472
Tlalocs 469
Tlaloctecutli 121, 288
Tlaloques 469
Tlaltecuhtli 129, 295, 469, 470
Tlaltecutli 459, 469
Tlanit Pene Baal 453
Tlanuwa 470
Tlapallan 470
Tlascalan People 114
Tlatecutli 129, 469, 471
Tlatonatiuh 288
Tlauixcalpantecuhtli 10, 295, 395, 470
Tlaxcala 325, 395
Tlazolteotl 121, 244, 245, 295, 470
Tlazolteutl 470, 509
Tlazolteutl-Ixcuina 470
Tlazoltoeotl 131
Tlehanoai 470
Tlenamaw 470
Tlepolemus 76, 145
Tletonatiuh 288, 470
Tlingit 15, 135, 199, 261, 435, 470, 475, 515
Tlohtzin 509
Tloque Nahuaque 363, 470, 471
Tloque Nauaque 240, 460, 470
Tloquenahuaque 240, 470, 471
To Wen 439
toads 234, 267, 459
Toba People 32
tobacco 136, 161, 201, 220, 475
Tobadzistsini 471
Tobardasum 471
To'bilhaski'di 471
Tobo-saku 420
Tocapo Virachocha 235
Tochthli 10
Tochtli 456, 471
Toci 129, 470, 471
Toda People 93
Todote 471
t'od-p'or 156
Tohil 469, 509
Tohil-Heumac 395
Toho-ten 345
toilets 183
To-Kabinana and To-Karvuvu 471
Tokakami 471
Tokelau 471
Tokelo 471
Tokerau 400
To-Kwatsu 250
Tollan 226
Tolocan 471
Toltecs 94, 125, 129, 226, 363, 395, 424, 459, 460, 470, 471, 472, 509, 514
Toma 155, 471, 489
To-Matauenga 471
tombs 61, 258, 279
Tominagatoo 471
Tominu 68
Tomituka 370, 471
Tonacacihuatl 114, 125, 325, 471
Tonacaciuatl 288, 363, 509
Tonacaciutl 240, 470, 471
Tonacajoha 129
Tonacatecuhth 114
Tonacatecuhtli 325, 471
Tonacatecutli 240, 244, 288, 363, 470; and Tonacaciutl 471
Tonantzin 129, 131, 234, 451, 470, 471
Tonapa 472, 497
Tonatiuh 295, 470, 472
Tonatiuh Metztli 384
Tonatiuhichan 472
To'nenile 472
To'nenili 206
Tonenili 472
Tonga 28, 164, 217, 386, 452, 478
Tonga-iti 372, 405, 452, 476
Tongaiti 452
Tootega 472
tooth 91, 186; magic 27; sacred 408
Tooth Grinder 453
Tope 440
Topielce 472
Topiltzin 472
Toplitzin-Quetzalcoatl 472
Tor 463
Tora-Galles 222
torch 26, 66, 163, 424, 507
Torch 472
Tore 472
torments 109
tornadoes 20, 64, 84, 114
Tornait 472
Tornaq 239, 472
Tornarsuk 472
Tornatik 472
Torngak 472
Torngarsoak 472
Torngasoak 472
Tortali 472
tortoises 34, 61, 183, 226, 243, 281, 498
torture 364
Toru 472
Torum 162, 352, 460
Torx 472
Tos-khan 89
Tosotsa-Ten 193, 324, 472, 479
Tosotsu-Ten 472
Totates 131, 477
Totepeuh 325
Totso' 471
Tou Mu 121, 310, 473
touch/feeling 429
Toueyo 460
Tounela 272, 305
Touni 273
Toupan 478
Tou-Shen 473
Tower of Babel 345
town 111
Toxeus 38, 114, 359, 473
Toya-Tama-bime 355
Toyo-kumu-no Mikoto 39, 473
Toyo-mike-nu 251, 473
Toyotama 473
Toyo-Tama-Bime 217, 251, 473
Toyo-Tama-Bime-No-Mikoto 473
Toyo-Tama-Hime 473
Toyo-uke-bime 265, 482
Toyo-Uke-Bimi 482
Toyo-uke-hime 41, 482
Toyo-uke-hime-no-hime 482
Toyo-uke-hime-no-himi 203, 278, 482
Toyo-uke-no-Kami 41, 482
Tpereakl 287, 473
traders 324
trades 183
trading *see* commerce
Traetaona 516
tragedy 317
tragelphus 70
Trailokaya 473
Trailokyavijaya 33, 150, 195, 301, 410, 473
Trailokya-Vijaya-Raja 195, 473
Trakshya 141
transformation 373
Transformer 302
Transvaal 398
travelers 7, 89, 111, 164
treachery 180
Treasure-dropping One 322
Treasure-Mimer 322
treasury 324
Trecen 1 Ollin 470
Trecena 1 Ocelotl 460
Tree of Changing Leaves 207
Tree of Life 9, 12, 28, 162, 165, 187, 303, 314, 485, 510, 516
Tree of Many Branches 256
Tree of Many Seeds 474, 501
tree of paradise 30
Tree of the Knowledge of Good and Evil 510
trees 63, 92, 95, 103, 109, 141, 146, 152, 177, 256, 262, 278, 309, 346, 451, 478
Trentren 256
Treta 258, 412, 474
Tretayuga 159, 474
Triad (Hindu) 285
trials 448
Triambika 148, 474
tricksters 129, 133, 172, 241, 294, 362
Tridandi 47
trident 48, 49, 99, 140, 384
Triganini 148
Trigoneia 474
Tri-Loka 293
Triloka 91, 474
Trimurti 105, 474
Trinavarta 275, 474
Trinidad 366
Trinity 474
Trioditis 208
Triopas 25, 37, 115, 169, 172, 220, 231, 240, 320, 377, 382, 436, 474
Triple 278
Triple Goddessess 107, 171
Triple Powers 83
triplets 221
tripos 213
Triptolemus 6, 117, 146, 201, 356
Tripura 146
Trisala 474
Trishna 474
Trisiras 413, 474, 500
Trisna 474
Trita 25, 26, 474, 492
Trita Aptya 464, 474
Tritogeneia 79, 474
Triton 48, 291, 370, 474
Tritonis 9, 115, 338, 474
Tritons 48, 474
Trivia 474
Troezen 81, 218, 376, 377, 385, 474
Troilus 62, 145, 374
Trojan Horse 113
Trojan War 113, 129, 130, 145, 146, 160, 171, 209, 212, 215, 216, 218, 231, 240, 299, 317, 329, 331, 343, 371, 374, 375, 382, 386, 387, 388, 389, 416, 418, 432, 462, 463, 474, 479
Trojans 93, 135, 160, 174, 232, 378, 479
trolls 98, 166, 446
Tronubeina 209
Trophonius 182
Tror 463
Tros 76, 113, 130, 171, 187, 235, 474
Troy 116, 127, 129, 135, 145, 152, 165, 169, 175, 176, 192, 213, 235, 284, 286, 287, 297, 319, 344, 358, 370, 374, 378, 386, 389, 461, 463; *see also* Trojan War; Trojans
Truk 59, 291
truth 14, 298, 427
Truthful One 415
Tryambaka 25, 26, 406, 427, 475
Tsagan-Sukuty 356
Ts'ai Lun 475
Ts'ai Shen 428, 475
Tsaltsa 471
Tsalu 475
Ts'an Nu 475
Ts'ana-Pa 105, 475
Ts'ang Chieh 475
Ts'ang Chien 475
Tsao Chun 475, 519
Ts'ao Kuo-kiu 163, 475
Tsao Shen 128, 475
Tsao Wang 475
Tsao-kuo-chia 68, 475
Tsao-wang 475
Tsapani 471
Tsaphon, Mount 424, 521
Tse Shen 475
Tsects 475
Tse'-Iitsibehogan 471
Tseng Chang 326, 439

Tseng-fu-ts'ai-shen 475
Ts'en Kuang 475
Ts'en-kuang 146, 430
Tsentsa 475
Tseurima 475
Tse'yoali 471
Tshindi 51, 475, 515
Tsichtinaka 475
Ts'i-fu-shen 475
Ts'iku 266
Tsi-ku 266
Tsimshian People 15, 261, 470, 475, 515
Ts'in Shu-pao 225, 475, 519
Ts'ing-ti 423
Ts'ing-tsing T'u 442
Ts'in-kuang-wang 475
Ts-in-kuang-wang 466, 515
Tsi-si 132
Tsita 513
Tsi-zhui 475
Ts'kuang-wang 475
Tsmok 155
Tsoede 475
Tsolob 288, 409
Tsotsil 476
Ts'shen Yeh 475
Tsu-hsing 428
Tsui' 476
Tsui 160
Tsui'goab 476
Tsui-goab 188, 209, 476
Tsui-Goam 476
Tsuikiyomi Mikoto 476
Tsuikiyomi-no-Mikoto 476, 518
Tsuki-yomi 41, 220, 246, 445, 446, 476, 482
Tsukiyomi-no-mikato 39
Tsukuba, Mount 182
Tsuni Goam 476
tsuru 252
Tu 207, 372, 373, 399, 424, 452, 456, 476
Tu K'ang 230, 476
Tu Matauenga 311
Tuachca 302
Tua-Heru 60, 458
Tua-khu 458
Tuamotu 79
Tuamotuan Archipelago 83, 271
Tuamutef 48, 204, 476, 477
Tuapaca 497
Tuart 455
Tuat 3, 4, 5, 27, 32, 33, 39, 44, 49, 54, 58, 60, 64, 97, 98, 102, 177, 201, 212, 215, 242, 251, 256, 265, 267, 269, 298, 315, 320, 340, 348, 369, 379, 380, 385, 402, 408, 417, 418, 419, 420, 422, 424, 425, 442, 455, 456, 457, 458, 459, 477, 485, 486, 518
Tuatet-maket-neb-s 477
Tuatha 103
Tuatha de Danaan 477
Tuatha De Danann 30, 45, 54, 58, 89, 92, 96, 125, 134, 136, 139, 142, 151, 155, 177, 179, 193, 194, 290, 296, 305, 352, 424, 477
Tuatha-Dedanan 477
Tuati 4
Tubal-Cain 74, 113, 296, 477
Tucana 160
Tuchita 479
Tucumbalam 114, 508
Tucupacha 477
Tuehie 258
Tueris 455
Tues 66
Tuesco 66
Tuetates 477
Tui 66
Tuil 477, 478
Tuirenn 129
Tuisko 243
Tui-Tokelo 471
Tu-ka-nguha 476
Tu-kariri 476
Tu-ka-taua 476
Tuku 309
Tul 95
Tulasi 478
Tule 478
Tuli 478
Tulli 452
Tullius 212, 478
Tulsi Das 398
Tulungusaq 478
Tum 81, 458, 478
Tu-matauenga 399, 476
Tu-ma-tauenga 476
Tu-matauenga 60
Tu-mata-what-iti 476
Tumateanaoa 476
Tumburu 186
tumeric 101
Tu-metua 372, 476, 492, 494
Tuminikar 478
Tumpa 478
Tumudurere 220
Tumu-ra'i-feuna 406
Tumu-ra'ifeuna 448
Tumuteanaoa 478, 494
Tu-Mute-Anaoa 492
Tun Huang T'ai I 346, 478
Tuna 313, 478
Tundum 330
Tung Chun 346, 478
Tung Hai 519
Tung Huang T'ai I 383, 449, 478
Tung Wang 478
Tung Wang Kung 126, 225, 278, 449, 475, 478, 505
Tung-Ak 478
Tung-Hua 478
Tungrangayak 472
Tungus 40, 270
Tung-wang-kung 279
Tung-yo ta-ti 442, 478
Tung-yueh-ta-te 478
Tuniruna 370
Tun-pehti 477
Tu-nui-ka-rere 178
Tu-of-the-angry-face 476
Tuomela 305
Tuonela 295, 305, 478, 491
Tuonetar 272, 273, 295, 305, 478, 491
Tuoni 272, 273, 295, 305, 478, 491
Tupa 478
Tupan 322, 478
Tu-Papa 476
Tupi 478
Tupi-Guarani People 68, 214, 240, 247, 302, 327, 455
Tupiian 520
Tupinamba People 25, 68, 302, 478
Tupuran 349, 395
Tu-qa-Aat 4
Tura 465
Turachogue 88
Turan 117, 479, 523
Turesh 361
Turi-a-faumea 178, 217, 479
Turkey 22, 32, 33, 129, 249, 326, 483
Turms 214
turnips 26, 62
Turnus 6, 21, 49, 176, 254, 287, 414, 479
Turquois Lord 509
turquoise 173
Turrupa 61
Tursa 28
turtles 221, 225, 295, 315, 448; *see also* tortoises
T'u-shan 333
Tu-shi 466
Tushita 278, 303, 472, 479
Tushna 62
Tushnamatay 479
tusks 26, 38, 109
Tut 309
Tutankhamen 79
Tutankhaten 79
Tu-te-wanawana 476
Tu-te-wehi 234, 476
T'u-ti 123, 350
T'u-Ti Lao-Yeh 476
T'u-ti Shen 224, 476
Tutilina 418
Tuto-Tamu 41, 479
Tutruica 115, 479
Tutsu-nushi no Kami 247, 479
Tutu-f 75
Tutujanawin 239
Tuulikki 453
Tu-whake-ticke-tangata 476
Tvaksh-tri 479
Tvashta 479
Tvashtar 479
Tvashtr 479
Tvashtri 237, 319, 403, 413, 444, 447, 479, 489, 494, 499, 500, 512
Tvashtri Tvastar 474
Tvastri 212, 235, 502
Twashtar 479
Twashtri 479
Twelve Mountains of Ebhlenn 162
Twenty-four Unseen Ones 83
Twet 477
Twi 326, 354
twilight 254, 411
Twilight of the Gods 294, 397, 479, 496
Twin Lion Gods 428
twins 57, 117, 509
Two God 363
Two Reeds 363
Two Zarys 83
Two-Men 505
Ty 480
Tyche 37, 75, 178, 180, 479
Tyche Agathe 24, 479
Tydeus 17, 27, 35, 114, 145, 152, 359, 378, 480
Tydides 152
Tydracus 116
Tydus 17
Tyedeus 38
Tyhaon 480
Tyndareus 23, 93, 105, 194, 288, 381, 480
Tyndaridae 153
Typhaon 480
Typheon 480
Typhoeus 19, 184, 209, 455, 480
Typhon 20, 67, 93, 117, 119, 125, 135, 167, 178, 205, 212, 229, 284, 349, 377, 380, 383, 406, 417, 421, 438, 440, 480, 502
typhoons 320; *see also* storms
Typhos 162
Tyr 22, 178, 181, 187, 229, 357, 480, 483, 524
Tyre 317, 381
Tyrfing 159
Tyrian 165
Tyro 134, 341, 377, 410, 430, 433, 480
Tyt 5
Tyw 480
Tzakol 37, 245, 387
Tzakor 480
Tzec 94
Tzinteotl 129, 480
Tzitzimime 480
Tzontemoc 320
Tzu T'ung 505

Uaau 477
Uadjit 481
Uai 61
Uaj 481
Uajyt 481
Uamemti 75
Uasir 367
Uatchet 481
Uatchit 481
Uatch-nes 75
Uatchura 481
Uazet 481
Ubbe 397
Ubelluris 481
Uben 4
Uboze 270
Uchchaih-sravas 281
Uchtsiti 481
Uc-Zip 481
Udar 481
Uddushunamir 77
Udumbara 481, 512
Udzume 40
Ueuecoyotl 133, 481, 509
Ufa 32, 420, 481
Uga-jin 97
Uganda 128, 198, 329
Ugar 87, 481
Ugaric 481
Ugarit 36, 70, 73, 75, 79, 80, 87, 103, 139, 164, 173, 220, 264, 270, 274, 290, 328, 384, 424, 441, 443, 451, 460, 510, 511, 514, 520
Ugaritic 85, 521
Uggerus 357, 481
Ugly-Female-of-the-World-of-the-Dead 426, 518
Ugra 25, 26, 481
Ugra Tara 267, 481
Ugrain 352
Ugrasena 90, 157, 261, 481, 510
Ugrian 162
Uhiji-ni No Mikoto 39, 481
Uhlanga 481, 484
Uhumakaikai 481
Uiracocha 497
Uira-Cocha 497
Uitzilopochtli 226
Uitzlampa 131, 481
Uixtochihuatl 81, 481
Uixtociuatl 481
Uja-Jin 482
Ujikami 361, 482
Ukaho 407
Ukanipo 326, 482
Uka-no-kami 237, 482
Ukemochi 42, 260, 482, 503
Uke-mochi 482
Ukemochi-no-Kami 23, 482
Uke-mochi-no-kami 482
Ukhukh 482
Ukibashi 247
Uki-mochi 482
Ukko 33, 253, 401, 482
Ukko-Thor 463
uko Cghene 120
Uksakka 299, 482
Uktena 482
Ukteni 482
Ul 482
Ula 244
Ulfrun 209
Ulgan 482
Uli 260, 280, 482
Ulithi 292
Ulixes 358
Ull 83, 362, 434, 482, 483, 515
Uller 362, 435, 482
Ullerus 482
Ulligarra 133, 483
Ullikummis 212, 241, 279, 459, 483, 484
Ullr 482
Ullur 22
Ulmuka 483
Ulster 135, 299

www.ebook3000.com

Ultimate Reality 149
Ulu Tojon 6, 70, 483
Ulua 302
Ulupi 69, 240, 332, 483
Ulysses 313, 358, 483
Uma 141, 148, 158, 257, 338, 374, 415, 424, 427, 473, 483
Uma Haimavati 406
Umahi 195
Umai 367, 483
Uma-Parvati 42
Umhlanga 484
Umina 483
Umlungu 329
Umm Kulthum 327, 520
Umma 236
Ummu 32, 483
Ummukhubar 466
Umunmutamku 161, 483
Umunmutamnag 161, 483
Unas 32, 60, 209, 419, 420, 422, 457, 462, 481, 483
Unbending 81
underground 111, 241, 321, 338, 485
undertow 362
underworld 3, 4, 14, 16, 17, 23, 28, 32, 33, 34, 37, 44, 45, 48, 49, 52, 58, 60, 62, 63, 64, 65, 69, 70, 72, 77, 80, 82, 83, 91, 95, 103, 105, 118, 119, 123, 129, 130, 132, 135, 140, 146, 153, 156, 158, 166, 168, 169, 170, 173, 175, 189, 191, 194, 199, 201, 208, 209, 210, 211, 214, 215, 217, 220, 225, 228, 236, 247, 250, 261, 267, 268, 269, 270, 273, 277, 280, 292, 300, 311, 313, 319, 321, 323, 324, 331, 340, 342, 343, 356, 359, 365, 367, 375, 379, 386, 391, 396, 403, 413, 441, 455, 485, 502
Undines 350, 483
Undry 139, 477
Unelanuhi 446, 483
Ung 483
Ungud 397, 483, 504
Ungur 196, 507
Uni 253, 468
unicorn 124, 439
Unis 483
United States 6, 24, 34, 46, 50
Universal Egg 175
Universal Man 25
Universal Mother 148, 313
Universal Shakti 313
Universally Auspicious 148, 414
Universe Destroyer 204, 427
Univirae 180
Unkei 348
Unknowable Father 351
Unknown Woman 360
Unkulunkulu 481, 484
Unmatta 427, 484
Unnefer 364, 367, 484
Unnet 505
Unnofre 484
Unnu 62
Unsas, The 484
Unsas 37
Unseen Ones 83
Unshorn 62
Unt 4
Unti 61
Untiring 210
Untunktahe 484, 505
Un-ug 113
Unummuzida 346
Unvelingange 484
Unxia 253
Upamanya 484
Upamanyu 77
Upananda 332, 484
Upanishads 416
Upao 452, 484
Upasunda 69, 484
Upelluri 459, 484
Upelluris 484
Upotos 290
Uppsala 491
Uprooter of Evil 340
Upsala 358
Upset 484
Upshukina 484
Upuaut 268
Up-uaut 268
Upuaut 60
Upwuat 60
Ur 8, 332, 484
Ura 484
uraei 33, 212
Uraeus 62, 244, 419, 484
Uragas 332
Ural-Altaic 171
Uramma 331
Urania 61, 229, 330, 484
Uranus 18, 22, 35, 37, 56, 61, 69, 80, 116, 118, 122, 135, 136, 137, 139, 146, 152, 167, 171, 184, 190, 201, 208, 230, 231, 316, 317, 326, 356, 370, 381, 382, 387, 403, 440, 441, 457, 460, 461, 463, 469, 484, 492
Urartians 71, 89, 268, 424, 461
Uras 14
Urcaguary 485
Urcaguay 485
Urd 210, 351, 485
Urd's Well 485, 516
Urdh 485
Urdhr 485
Urdur 485
Urien 312, 485
Uriens 328
Urin Cuzco 449, 485
Urion 365
Uris 485
Urja 485, 493
Urmila 434, 485
Ur-Nammu 484
Ur-nes 425
Urpihuachac 485
Urpi-huachacs 132
Urpr 485
Urs 5
Ursa Major 204, 404
Ursa Minor 137
Urshanabi 191, 430, 484, 485
Ur-Shanabi 485
Urshiu 4
Urt 366, 485
Urth 210, 485
Uruasi 485
Uruk 170, 191, 242, 295, 348, 451
Uruki 485
Urun Ai Toyon 485
Urutaetae 220, 343, 366, 485
Urutonga 211, 262, 456, 485
Urvakhshaya 266
Urvashi 485
Urvasi 24, 63, 325, 391, 485, 492, 493
Usas 486
Usekht-nemmat 75
Usert 242
Usha 85, 91, 276, 485
Ushas 25, 77, 83, 98, 121, 160, 169, 257, 310, 388, 390, 401, 406, 413, 444, 486, 492
Ushemet Hatu Khefti Ra 486
Ushnishavijaya 486
Ushodevatas 148
Usma 486
Usukun 350, 486
Usur-Api 420
Utanapishtim 191, 485, 486
Uta-Napishtim 430, 486
Utathya 413
Utennu 4
Utet 486
Utgard 252, 435, 486
Utgard-Loke 179, 294, 415, 435, 486
Utgard-Loki 166, 226, 293, 294, 435, 486
Uther Ben 486
Uther Pendragon 70, 486
Uthra 6
Utnapishtim 430, 524
Ut-Napishtim 13, 486
Uto 481
utpala 372, 389
Utsanati 486
Utset 446; and Bowutset 486
Uttara 7, 374, 486
Utto 345
Uttu 167, 346, 348, 486
Uttuka 146
Utu 158, 167, 236, 347, 423, 458, 487
Utukki 28, 51, 58, 59, 487
Utukku 162, 291, 432, 487
Utu-rekhit 75
Uyitzin 350, 487
Uyungsum 17
Uzume 40, 94, 397
Uzzah 34

Vac 413
Vach 278, 413, 414, 416, 436, 488
Vach Vac 487
Vacha 487
Vach-Sarasvati 413, 416
Vacuna 487, 496
Vadaba 77, 487
Vadava 487
Vaejo 30
Vafthrudni 487
Vafthrudnir 487
Vafud 357, 487
Vaghan 34, 487
Vagisvara 307, 487
Vagiswara 307, 487
Vague 197, 487
Vah 495
Vahagn 26, 75, 87, 157, 229, 310, 321, 487, 495
Vahran 488, 495
Vahu 452, 488
Vaidya-nath 427, 488
Vaijayanta 447, 488, 499
Vaikhari 487, 488
Vaikuntha 319, 488, 498, 499
Vainamoinen 216, 234, 235, 289, 295, 297, 305, 482, 488, 491
Vairajas 293
Vairocana 48, 150, 215, 310, 334, 384, 488
Vairochana 140, 182, 488
Vairochi 91, 488
Vairya 416
Vaisavata 232
Vaishnavism 275, 276, 498
Vaishnavi 148, 305, 489
Vaishvanara 141
Vaishwanara 25
Vaishya 373
Vaisravana 117, 149, 282, 450, 467, 489, 493
Vaitarani 489, 512
Vaivasvata 308, 312, 441, 489, 493, 498, 512
Vaja 403, 489, 496
Vajra 33, 46, 140, 141, 479, 488
vajra 91, 154, 182, 188, 237, 263
Vajra Space 488, 489
Vajra Tara 267, 489
Vajrabarahi 120, 156, 489
Vajradhara 307, 489
Vajradhatu 140
Vajradhatvisvari 150, 488, 489
Vajradhupa 489
Vajradipa 489
Vajragandha 489
Vajragiti 489
Vajrahara 307, 489
Vajraheruka 215
Vajrajogini 257, 267
Vajraloka 489
Vajranga 489
Vajranrtya 489
Vajrapani 9, 47, 103, 150, 211, 237, 290, 301, 348, 410, 489, 490, 500, 505
Vajra-Pani 489
Vajraraga 490
Vajrasattva 31, 48, 490
Vajra-sattva 490
Vajrasattvamika 490
Vajrasattvatmika 490
Vajrasatwa 140, 304, 400, 490
Vajrasawta 489, 490
Vajra-Shringhala 120, 489
Vajra-shringkhala 55
Vajrassattvamika 490
Vajra-Varahi 156
Vajravarahi 156, 411, 491
Vajravina 413, 414, 490
Vajra-Yaksha 273
Vajrayana Buddhism 120
Vajra-Yogini 155, 471, 489
Vaka 100, 452, 490
Vakea 493
Vala 146
Valaskjalf 192, 357, 490
Vale 104, 357, 490
Valentinus 65, 83, 384
Valentinus sect 351, 408
Valetudo 490
Valfadir 357
Valfather 209, 357, 490
Valhal 490
Valhalla 41, 72, 105, 164, 192, 198, 209, 214, 430, 462, 490
Vali 22, 91, 160, 337, 357, 404, 483, 490
Valiant August Thunder 450
Valiant Swift Impetuous Hero 41, 361
Valin 91
Valkjosandi 357
Valkyries 34, 153, 181, 224, 431, 480, 490
Valkyrja 490
Valkyrs 490
Valland 501
Valley of the Mohawk 454
Valley of Wajj 37
Valmika 434
Valmiki 398
Vamana 91, 152, 285, 293, 490, 491, 498
Vamen 490
Vamena 490
Vammatar 305, 491
Vammater 273, 295
vampires 101, 146, 276, 291
Vamsa 491
Vanadevatas 148
Vanadis 22, 181, 491
Vanagods 491
Vanaheim 19, 491
Vanant 33, 491, 515
Vanas 444, 491
Vanavasas 441, 491
Vandya 491
Vanemuine 491
Vaner 491
Vanir 22, 181, 198, 283, 322, 350, 491
Var 501
Vara 501, 516
varada 34, 153, 372
Varaha 285, 491, 498
Varaha-Avatara 491, 498
Varahavatar 491, 498
Varahi 491
Varahini 285, 491, 492
varanda 304
Varanga 307, 492
Varcin 492

Vardhamana 301, 492
Varegan 495
Vareghna 492, 495
Varengan 495
Vareshava 266
Vari 83, 148, 450, 492, 494
Vari-ma-te-takere 397, 452, 468, 476, 478
Vari-Ma-Te-Takere 492, 494
varja 140
Varns 178, 198, 206, 435
Varpulis 440, 492
Varshayanti 404, 492
Varuna 15, 24, 71, 77, 98, 149, 152, 153, 160, 238, 253, 259, 275, 281, 293, 296, 303, 325, 355, 358, 373, 388, 390, 401, 444, 484, 485, 486, 492, 493, 494, 512
Varunani 492, 493
Varunapragh 492
Varuni 281, 422, 492, 493
Vasa 278
Vasanta 259, 493
Vasanta-Bandhu 493
Vashita 493
Vashti 493
Vasishtha 259, 388, 485, 493
Vasistha 71, 335, 404, 492, 493, 500
Vasu 493
Vasu Deva 493
Vasud 224, 493, 497
Vasudeva 90, 147, 275, 280, 441, 493
Vasuki 146, 147, 281, 333, 421, 427, 489, 493
vasumdhara 91
Vasundhara 285, 434, 493
Vasus 15, 121, 185, 237, 493
Vasusena 262, 493
Vasuveta 514
Vata 487, 493, 494
Vatea 79, 372, 405, 406, 452, 476, 492, 493, 494
Vatsasura 275, 494
Vault of Heaven 466
Vavau 468
Vayu 15, 25, 99, 152, 182, 203, 280, 293, 311, 325, 372, 401, 437, 444, 479, 494, 515
Vazimba 400, 494
Vazishta 438, 494
Ve 74, 82, 98, 104, 321, 358, 494, 496, 517
La Vecchia 94
Veda 219, 312, 375, 505
Vedams 494
Vedana 150
Vedas 15, 25, 28, 31, 42, 48, 56, 63, 66, 77, 90, 99, 101, 121, 141, 144, 147, 148, 149, 160, 186, 189, 204, 219, 237, 238, 258, 263, 282, 293, 311, 325, 329, 337, 349, 374, 388, 390, 392, 400, 401, 403, 404, 406, 413, 416, 427, 436, 444, 479, 485, 486, 487, 492, 493, 494, 498, 499, 500, 502, 504, 511
Vedavyasa 502
Vedfolnir 494, 516
Vediovis 253, 494
Vedius 253, 495
Vega 204, 495
vegetables 15
vegetation 81, 114, 132, 158, 173, 208, 265, 275, 322, 353, 418, 451, 486, 490, 512, 521; *see also* plants
Veggdegg 463
Vegtam 357
Veigur 160
veils 168
Vejamat 254, 495
Vejovis 253, 495
Vele 495
Veles 495, 501
Velint 501
Vellamo 289
Vema 495
Vemacitra 48, 495
Venda 398
Veneralia 495
vengeance 183, 455
Venilia 254, 384, 415
Venus 21, 34, 47, 50, 61, 73, 75, 77, 80, 100, 123, 130, 151, 171, 225, 238, 242, 243, 304, 310, 356, 395, 460, 470, 487, 495, 525
Verbeia 420, 495
Verdandi 351, 485, 495
Verethraghna 89, 181, 488, 492, 495, 514
Vergelmir 229, 495
Verticordia 495
Vertimnus 495
Vertumnus 495
Vertumun 387
Vesna 495
Vesper 495
Vessavana 495
vest 90
Vesta 26, 151, 216, 253, 377, 378, 431, 495
Vestal Virgins 495
Vestalia 495
Vestri 160
Vetala 158, 427, 495
Vetanda 158, 496
Vetehinen 28
Vi 166
Vialis 318, 496
Viaracocha 497
Vibhan 489
Vibhishana 279, 282, 345, 398, 401, 496
Vibhu 496
Vibhvan 403, 496
Vibishana 496, 499
Vicchaycamayoc 497
vice 257
Vichitravirya 415, 496, 503
Victoria 79, 253, 345, 487, 496
Victorious Guardian 496
Victorious One of the Ocean of Wisdom 413
victory 79, 107, 148, 274, 345, 357, 490, 492, 495, 496, 514
Vid 165, 496
Vidar 22, 196, 357, 483, 496
Vidarbha 433, 496
Videha 434
Vidforull 357, 496
Vidharba 267, 409, 496
Vidi 496
Vidor 496
Vidura 496, 503
Vidya 413
Vidyadevis 496
Vidyadhara 496, 511
Vidyadhari 496
Vif 209
Vig 160
Vigaya 148, 496
Vigona 179, 496
Vigrid 93, 496
Vihishana 496
Vii 496
Vijaya 48, 55, 496, 511, 513
Vijayasri 496
Vijnana 33, 150
Vikathikarala 158, 496
Vikrama 496, 498
Vikramaditya 496, 498
Vila 496
Vilcamija River 369
Vile 496, 517
Vili 74, 82, 98, 104, 166, 321, 358, 407, 494, 496, 497
Vilin 497
vilva tree 158, 497
vina 414
Vinata 187, 188, 264, 442, 497
Vinayaka 186, 283, 483, 497
Vindalf 160
Vindhya Mountains 148, 497
Vindhyadara 452
Vindhyavali 497
Vindhyavarini 148, 497
Vindhyavasini 148, 497
Vindsual 493, 497
Vindsval 497
Vindya 24
vines 153, 159, 347, 390, 415
vineyards 438
Vingnir 463, 497
Vingolf 192, 232, 497
Vingolv 72
Vingthor 463, 497
Vinmara 496, 497
Vipasyin 308, 497
Vipunen 56
Virabhadra 98, 141, 374, 427, 497, 511
Viracocha 123, 235, 239, 304, 369, 449, 497
Viracocharapacha Yachipachan 497
Viraj 337, 392, 413, 497
Vira-Shaivaisma 427
Virata 69
Virbius 17, 219, 497
Virgin Mary 235, 284, 309, 369
Virgin of Light 384
Virginensis 253
virgins/virginity 70, 79, 109, 250, 279
Virgo 76, 171
Virochana 91, 256, 497
Virococha 465, 472, 497
virtue 66, 148, 149, 374, 436, 512
Virtus 497
Virudaka 497
Virudhaka 117, 149, 467, 497, 524
Virupaksha 117, 146, 149, 273, 332, 421, 497
Virupasa 467
Virvir 160
Vis 498
Visha 281
Vishapa 85, 498
Vishnu 15, 24, 25, 27, 50, 52, 62, 64, 71, 89, 98, 99, 100, 101, 105, 120, 141, 147, 148, 158, 186, 188, 196, 203, 204, 208, 219, 223, 230, 237, 247, 248, 256, 258, 264, 275, 276, 281, 285, 290, 307, 308, 309, 310, 312, 327, 333, 335, 336, 337, 338, 372, 373, 374, 375, 388, 390, 397, 398, 401, 409, 410, 413, 414, 416, 421, 430, 432, 434, 436, 439, 441, 444, 474, 489, 491, 496, 498, 499, 513, 523
Vishnu Purana 264
Vishnu-Narayana 499
Vishravas 234
Vishvabhu 308
Vishvakarman 499
Vishvamitra 317
Vishvanatha 427, 499
Vision Serpent 481, 508
Visnanatha 427, 499
Vispala 77, 499
Visravas 282, 401, 496, 499
Visvabhu 308
Visvadevas 185
Visvakarma 247, 282, 336, 388, 412, 428, 444, 479, 498, 499, 510
Visva-Karma 499
Visva-Krit 499
Visvamitra 388, 404, 415, 499, 500
Visvapani 150, 410, 489, 500
Visvarupa 28, 474, 479, 500
visvavajra 47
Visvavasu 186, 500
Viswakarman 499
vitarka 304, 372
Vitharr 496
Vithur 160
Vitzcatl 524
Vivanghat 500
Vivanghvant 203, 223, 248, 500
Vivasvan 310, 500
Vivasvant 308, 310, 500
Vivasvat 15, 77, 264, 308, 310, 325, 413, 416, 444, 500, 512, 513
Vivian 500
Vivien 403, 500
Vivienne 500
Vivifier 500
vixen 237
Vizetot 127, 129, 162, 324, 395, 451, 500
Vjofn 500
Vlkodlak 276, 343, 500, 501
Vodu 7, 85, 500
vodun 396
Vodyanoi 500
Vodyanoy 278
Vodyany 500
Vodyany-Ye 500
Vogul 252
Vohu Mana 500
Vohu Manah 22, 45, 138, 190, 203, 300, 494, 500, 501
Vohu Mano 48, 500
Voice of the Void 331, 378, 501
Void 29, 452
Vol 183
Vola 183
Voland 462, 501
volcanoes 19, 137, 143, 160, 226, 246, 261, 267, 377, 501, 510
Volga 104, 452
Voli 490
Volkh 104
Volkum 500
Volkun 501
Volla 183
Volos 501
Volsung 193, 197, 220, 402, 430, 501
Volsunga 431, 501
Volsungs 431
Voltan 501
Voltumna 501
Volturnus 501
Volund 501
Voluptas 501
Volva 198, 501
voodoo 105, 141, 172, 360
Vopdeva 99
Vor 501
Vortumnus 495
Votan 357, 501
Vourukasha 35, 53, 60, 185, 266, 268, 464, 468, 474, 501
Vow 501
Vraja 275
Vretil 332
Vriddhi 285
Vrikdevatas 148
Vrikodara 99, 502
Vrikshakas 63
Vrinda 77
Vrindavana 275
Vrishakapayi 502
Vrishakapi 203, 238, 399, 502
Vrita 28, 77, 237, 421, 480, 494, 502

www.ebook3000.com

Vritra 28, 143, 157, 237, 479, 502
Vritrahan 237, 502
Vritrahana 237, 502
Vrkolak 500
Vrou-elde 98
Vrtra 502
Vrtrahan 488
Vrtrahanna 237, 502
Vudus 409
Vukodlak 500
Vukub Aphu 227
Vukub Hunahpu 114
Vukub-Ahpu 228
Vukub-Cakix 198, 502, 508
Vukubcame 227, 502
Vukub-Came 502
Vulcan 137, 151, 193, 212, 233, 315, 329, 479, 502
Vulcania 502
Vulcanus 502
vultures 66, 72, 111, 125, 162, 308, 341, 343, 480, 502, 514
Vushkapariks 202, 502
Vuub-Hunapu 227
Vyaghrini 502
Vyasa 150, 186, 372, 373, 415, 496, 502
Vyelyes 501

Wa 220, 503
Wa Cinaci 233
Wa Murreta Kwonci 233
Wabun 335
Wac 349, 395
Wachaga 504
Wadd 37, 422, 503
Wadjet 503
Wadjet of Buto 341
Wagilag 505
Wahieloa 217
Wahieroa 400, 455, 456, 467, 503
Wailers 32
Wailing River 131, 503
Wainamoinen 56, 488
Waka 503
Wakahiru-Me 41
Wakahirume 503
Waka-hiru-me 503
Waka-mi-ke-nu-no-mikoto 251, 473, 503
Wakan 272, 504
Wakanda 303, 504
Wakan-Tanka 504
Waka-sana-me-no-kami 482, 503
Wakataka 504
Waka-Uke-Nomi 482
Wakcexi 504
Wakea 79, 353, 372, 492
Wakonda 272, 504
Wakonde 314
Wakonyingo 504
Waktcexi 504
Wala 504
Walangada 504, 507
Walcheren Island 340
Wales 12, 40, 68, 96, 103, 125, 142, 155, 176, 193, 267, 292, 296, 299, 306, 312, 326, 328, 393
Walgino 281
Walhalla 490
Wali 91
Walkure 490
Walkyrie 490
wallaby 263
Wallanganda 504
walls 429, 476
Walumbe 198, 504
Walutahanga 179
Wamara 255, 265, 275, 329, 407, 504
Wanand 204
Wanderer Without 32, 198
Wandjina 504
Wandu 389
Wang 504
Wang mu niang-niang 225
Wang-Chugmas 48, 504
Wangchugmas 504
Wang-kiu 466
Wang-Mu-Niang-Niang 504
Wang-mu-niang-niang 519
Wang-si ch'eng 466
Wanjin 303
Wantu Su 504
war 22, 28, 34, 36, 43, 54, 55, 66, 69, 75, 80, 89, 93, 95, 96, 97, 100, 102, 103, 104, 107, 108, 110, 114, 115, 117, 123, 124, 125, 131, 145, 150, 152, 168, 170, 173, 176, 177, 199, 200, 214, 226, 234, 242, 253, 256, 263, 271, 275, 277, 299, 300, 305, 310, 311, 321, 323, 328, 332, 341, 342, 346, 348, 357, 366, 370, 380, 394, 404, 405, 406, 413, 414, 418, 419, 423, 431, 447, 471, 472, 476, 477, 479, 492, 496, 510, 520
Warah 37, 422
Waramurungundja 235, 504
Waramurungundju 504
Warana 507, 511
Waranjui 507
War-provoking Evening Star 242
Warrau People 7, 507
warriors 6, 21, 31, 42, 43, 51, 55, 57, 60, 66, 69, 73, 75, 78, 98, 99, 109, 135, 143, 154, 158, 164, 173, 179, 202, 203, 242, 256, 257, 266, 267, 297, 310, 341, 357, 358, 360, 374, 402, 418, 446, 450, 459, 472
Warundi 235
Wasicong 504
wasp 262
Wata-tsumi 247
Watchdog of Chulain 135
Watchdog of Hades 119
watchdog of the dead 187
water 27, 28, 35, 36, 41, 48, 50, 53, 62, 64, 65, 78, 88, 92, 94, 97, 110, 120, 121, 125, 128, 142, 152, 155, 156, 161, 163, 167, 180, 187, 197, 205, 218, 223, 225, 230, 248, 266, 267, 274, 280, 304, 322, 324, 326, 329, 333, 337, 342, 343, 344, 347, 362, 366, 378, 392, 394, 402, 414, 427, 429, 431, 436, 444, 445, 466, 470, 472, 474, 481, 482, 484, 498, 518
Water of Immortality 48, 436
water-elephant 248
waterfalls 450, 471
water-frog 275
water-horse 248
waterspouts 320
waterways 225
Wati 505
Waukheon 484, 505
Wauwalak Sisters 505
waves 13, 19, 53, 82, 160, 217, 305
Wawalag Sisters 504, 505
Wawilak 505
Waxcpini Xedera 505
Way of the Celestial Masters 286
Wayland the Smith 36, 160, 166, 501, 505
wayside goddess 208
We 211, 494, 505
wealth 15, 102, 104, 149, 150, 152, 153, 248, 281, 282, 283, 292, 327, 350, 360, 361, 385, 386, 395, 428, 436, 475, 493
weaning 162
Weapon of Beauty 258
weapon makers 264, 274
weather 14, 36, 74, 114, 133, 156, 178, 222, 228, 268, 279, 338, 350, 384, 399, 510, 515
weaving and weavers 64, 94, 126, 223, 245, 341, 430, 449
wedjat-eye 5
Weendigo 506
weevil 281
Wehtiko 506
Wei Cheng 317
Weighing of the Heart 340
weights and measures 116
Wei-t'o 505
Wei-to 232, 505
Weiwobo 420, 505
Wejas 389
Weland 501
Weldegg 357
welfare 250
Well of wisdom 322
Wellamo 28, 289
wells 95, 107, 120, 142, 309
Wen Ch'ang 126, 128, 278, 439, 505
Wen Ch'ang Ti Chun 505
Wen Chung 132
Wen-chang-ta-ti 505
Wen-ch'ang ti-kun 128, 505
Wen-Ch'en 454
Wenenefer 484
Wenen-nefer 484
Wenenu 505
Wenenut 505, 506
Wenet 359
Wennefer 367
Wenonah 350
Wen-shu 307, 448, 505
Wen-ti 128, 505
Wenut 505
Wep-Rehewh 505
Wepwawet 60
Wera 98
Weres 5
Weret Hekau 505
werewolves 276, 500, 501
Wer-mer 326
west 206, 366, 471
West Indies 356, 385
West Wind 140, 154, 178, 218, 228, 505, 522
Western Paradise 45
Westre 506
Westri 83, 321, 351, 441, 506
Whaitiri 211, 256, 262, 455, 456, 506
whales 28, 82
Wharfe 420
Whatitari 506
Whatitiri 506
wheat 363
wheel 102, 109, 120, 186
wheel of life 256
Whenua 506
whirlpool 265
whirlwinds 20, 64, 84, 140, 208, 228, 474
Whiskey Jack 506
White Beauty 122
White Brahma 105, 475
White Dolma 454
White Goddess 10, 238, 290, 312, 413, 506
White Haoma 185, 203
white heron 467
White Hom 203
White Island 166, 440
White Kilyikhama 271
White Lady 98
White One with Soft Voice 307
White Peony 369
White Tara 429, 454
white Tezcatlipoca 471
White Woman 246
White-clad One 371
Whiteman 354
Whitiko 506
Who's Who in Egyptian Mythology 340
Whole Earth 272
Wi 53
Widadari 452
Wide Hearing 102
Wide-gazing 273
Wide-stepper 498
Wieland 501
Wielder of the Thunderbolt 489
Wife and Daughter 278
Wife of Brahma 148
Wife of Rudra 148
Wife of Rudra-Shiva 148
Wife of Shiva 148
Wife of Vishnu 148
Wigan 506
Wijadari 496, 506
Wild Huntsman 357, 506
Wild Men of the West 368
Wild People 255
wildflowers 207
wildlife 71, 212, 371
Wildly Drifting Clouds 59
Willi 211
Wilobo 506
Wilolane 506
Wimpe 193, 506
Winabojo 335
wind 3, 21, 22, 27, 28, 36, 43, 58, 83, 92, 94, 99, 100, 103, 141, 162, 163, 172, 178, 182, 184, 188, 197, 211, 214, 219, 224, 241, 254, 255, 273, 284, 295, 320, 351, 355, 374, 376, 381, 395, 404, 406, 426, 428, 440, 451, 456, 491, 492, 495, 518
Windigo 506
Winding River 336
windows 271
wine 10, 16, 88, 114, 130, 152, 153, 208, 222, 230, 231, 236, 289, 291, 381, 425, 443
wings 98
Winnebago 161
winter 33, 36, 77, 102, 107, 112, 133, 221, 224, 252, 264, 362, 428, 434, 443, 483, 493, 497, 519, 523
Wipunen 56
Wisagatcak 506
Wisakedjak 506
wisdom 5, 23, 24, 28, 34, 45, 46, 70, 108, 109, 119, 161, 163, 182, 183, 186, 233, 235, 264, 268, 307, 322, 323, 332, 355, 378, 389, 402, 464, 467, 489, 492, 498
Wish Cow 259
wish-granting gem 129
Wishosk 197
Witana 506
witchcraft 30, 53, 88, 356
With Black Limbs 427
With Pearls in Her Ears 257, 263
Witigo 506
Witness of Deeds 262, 444
wizard 42
Wlenenu 506
Wo 521
Wo Huang 225, 346
Wodan 90, 199, 357, 358, 506
Wode 98, 357, 506
Wodemus 357, 506
Woden 357, 506
Wodhen 357, 506
Wodin 357, 506
Wodoi the Rock Pigeon 507

Wointli'zi 471
Woko 506
Woland 501
Wollunka 397, 506
Wollunqua 196, 397, 506
Wolphat 362
Wolverine 335
wolves 60, 62, 99, 101, 178, 183, 190, 261, 265, 268, 297, 343, 358, 435, 490, 502
women 98, 212, 238, 277, 299, 330, 377, 388, 425, 462
Wonambi 196, 397
Wonder Workers 77, 144, 338
Wonderful Head 486
Wondjina 507
Wondrous Inada Princess 282
Wongar 483
Wonistsidi 471
Wonistsidikai 471
Wonungur 196, 397
Wood Eater 377
wood spirit 393
Wooden Horse 56, 169, 286, 318, 463
Woodland King 431
woodpeckers 18
wool 326
Word 413
Word of God 327
work 105
workers 415
World Above 507
world deities 87, 135, 181, 247, 275, 277, 293, 400, 470, 471, 499
World Gates 44
World Maintainer 498
world mountain 443
World of Forms 46, 140
World of Ideas 140
World Tree 373
worm 314
Worombi 196, 397
Worora People 504
Worship of the Inkstand 144
Wotam 357
Wotan 506
Wotjabaluk 193
Woutan 357
Wowta 7, 507
Woyengi 507
Woyo 24
wrath 22, 33, 250, 326
wrestlers 56, 235
writers 95
writing 181, 421, 455, 464, 513
writing brush 318
wrong-mindedness 85
Wu Kuan 146, 507
Wu Ti 182
Wu-ch'ang 317, 350, 507
Wuhuu 507
Wu-kuan wang 466
Wulbari 507
Wuldor 482
Wulgis 507
Wuni 507
Wuotan 357
Wuraka 483, 507
Wurd 485
Wurekaddo 281
Wuriupranili 507
Wurusemu 69, 212, 507
Wyrd 485
Wyrra-warre 353, 507

Xam 339
Xamaniqinqu 350, 507
Xanthian Plain 96
Xanthippe 25, 156, 218, 385, 507
Xanthos 507
Xanthus 12, 91, 205, 377, 385, 416, 507, 508, 522
Xarmarokh 385
Xbalanque 227, 502, 508
Xecotcovach 114, 508
Xelhua 508
Xenodice 9, 52, 68, 192, 297, 323, 375, 508
Xevioso 24, 199, 409, 500, 508
Xhosa 160, 463, 476
Xi Wang Mu 508
Xi Wang-Mu 508
Xib Chac 120, 508
Xibalba 114, 227, 228, 481, 508
Xibalha 508
Xilonen 81, 125, 480, 508
Xipe 472, 508
Xipe Itzpapalotl 508
Xipe Totec 307, 460, 508
Xiuhcoatl 118, 131, 227, 509
Xiuhtecuhth 288, 459
Xiuhtecuhtli 226, 295, 509
Xiuhte-cuhtli 295
Xiuhtecutli 125, 509
Xmucane 245, 368
Xochipilli 118, 246, 295, 299, 509
Xochiquetzal 81, 133, 288, 338, 368, 384, 469, 470, 480, 509, 514
Xochiquetzalli 509
Xochitl 509
Xocotl 114, 226, 227
Xolotl 134, 314, 321, 481, 509
Xpiyacoc 245, 368
Xquiq 227, 509
Xubchasgagua 124, 509
Xue 103, 509
Xumio 222
Xumucane 509
Xuthus 11, 21, 118, 134, 152, 156, 211, 509

yab-yum 490
Yacatecuhtli 298, 510
Yaccy-Ma 453, 510
Yachihoko-no Kami 510
Yachihoko-No-Kami 361
Yachimata-hiko 413, 510
Yachimato-hime 510
Yadahpati 492, 510
Yadavas 157, 275, 415, 510
Yadu 510
Yagrush 274, 510, 511
Yahata 200, 510
Yaho 510
Yahowah 250
Yahu 250, 510
Yahveh 8, 13, 87, 165, 250, 291, 317, 510
Yahwe 510
Yahweh 8, 14, 73, 74, 75, 79, 164, 231, 250, 290, 397, 492, 510
Yajata 514
Yajna 497, 499, 510
Yajnesvara 498
Yajur-Veda 411, 494
Yakami, Princess 361, 511
Yakamouch 29, 221, 511
Yakho 511
Yakka 511
Yaksas 149, 511
Yakshas 100, 105, 146, 188, 204, 264, 282, 283, 371, 375, 398, 412, 496, 505, 507, 511
Yakshi 282, 283
Yakshinis 120, 146, 282, 392, 439, 442, 511
Yakushi juni shinsho 511
Yakushi-Nyorai 511
Yakushi-Rurikwo-Nyorai 140, 511
Yakut People 6, 32, 70, 89, 265, 270, 290, 483, 485, 517
Yalungur 191, 511
Yam 329, 466, 510, 511
Yama 77, 141, 149, 152, 166, 256, 293, 307, 325, 329, 373, 374, 385, 412, 413, 416, 444, 466, 479, 492, 494, 498, 500, 511, 512, 513, 518
Yama Kings 178, 277, 350, 426, 466, 512, 515
Yama-Dutas 512
Yama-Dyitya 512
Yamagoshi no Amida 46
Yamai 513
Yama-isvara 513
Yamanamca Intanamca 225
Yama-no-Kami 512
Yama-no-Shinbo 512
Yamantaka 48, 55, 139, 307, 512, 513, 523
Yamantakasakti 513
Yamantakha 513
Yamapura 512, 513
Yama-Raja 166
Yamari 307, 513
Yamasadana 512, 513
Yamato-Takeru 281
Yama-Uba 513
Yami 77, 253, 263, 280, 361, 412, 413, 444, 500, 512, 513
Yamm 511
Yam-Nahar 86, 309, 511
Yamoto 251
Yamri 235
yams 27
Yamuna 90, 285, 513
Yan Tachu 513
Yananamca Intanamca 513
Yanari 513
Yanauluha 513
Yang 122, 124, 226, 227, 251, 371, 517
Yang Ch'eng 513
Yang Ching 513
yang force 156
Yang Ki-Sheng 123
Yang-Chen 413, 513
Yang-Ku 513
Yangombi 513
Yang-Wu 513, 514
Yank Ki-sheng 123
Yansan 513
Yantho 350
Yao 279, 346, 513
Yao dynasty 123
Yao People 290, 329, 330
Yao-Shih Fu 513
Yaotl 460, 514
Yap 515
Yaparamma 331, 514
Yappan 249, 470, 514
Yaqui 244
Yareah 422, 424, 514
Yarikh 514
Yarilo 280, 514
Yarovit 407, 446, 514
Yashts 468, 514
Ya-sima-zinumi-no-kami 282, 510
Yasna 203
Yasoda 147, 148, 262, 301, 514
Yasodhara 397, 422
Yasts 514
Yata 53, 157, 370, 514
Yata-Garasu 41, 514
Yatagarasu 514
Yata-Kayami 40, 41, 445
Yathrib 327
Yatis 514
Yatpan 274
Yatu 514
Yatudhanis 147, 514
Yatus 514
Yau 510
Yauahu 266
Yauhahu 364
Yavishta 25
Yaw 250, 510, 514
Ya-w 510
Yaya-Zakurai 514
Yayu 514
Yazatas 29, 50, 62, 73, 78, 147, 228, 360, 415, 468, 491, 494, 514
Yazdan 514
Ydaler 515
Ydalir 483, 515
Y'dun 232
year end 332
year gods 456
Yeba Ka 515
Yebaad 515
Yebitsai 206, 515
Yebitshai 515
Yebu 165
Yehi 261
Yehl 515
Yehoshu'a 250
Yehoveh 250
Yei 51, 173, 206, 463, 515
Yeibechi 515
Yeibichai 515
Yeitso 515
Yelafath 296, 362, 515
Yelafaz 296, 404, 448, 515
Yellow 374, 508
Yellow Book of Lecan 45
Yellow Emperor 226, 424
Yellow Heruka Buddha 400
Yellow River 221, 346
Yellow Tara 454
Yemahya 515
Yemaja 358, 515
Yemanja 515
Yemaya 362, 515
Yembo 358, 360, 361
Yemma 166
Yemoja 356, 515
Yemonja 515
Yen Kung 515
Yeng-Wang-Yeh 512
Yenisei 154, 162, 352
Yen-lo 146, 512
Yen-lo Wang 466, 475, 515
Yen-Lo-Wang 443
Yen-Wang 466, 515
Yen-Wang-Yeh 515
Yepitsai 206
Yero 196, 397
Yerri Yuppon 510
Yesha 250
Yeshe-Khahdoma 268
Ye-she-tsho-gyal 140, 413
Yetl 515
Yeuo 510
Yew of Ross 7
Ygdrasil 516
Ygdrasili 516
Ygg 357
Yggdrasil 9, 36, 74, 140, 192, 198, 199, 209, 211, 229, 252, 288, 289, 291, 322, 344, 345, 351, 358, 400, 463, 485, 494, 516, 517
Yggr 357
Yggr-drasill 516
Yhvh 510
Yhwh 250, 510
YHWH 16, 510
Yi 122, 513, 516
Yidak 516
Yi-dam 156
Yi-dvag 389
Yim 516
Yima 85, 139, 157, 203, 223, 266, 465, 512, 516, 517, 524
Yimak 517
Yimaka 517
Yimantuwinyai 362
Yimeh 248, 517
Yimi 516
Yin 122, 226, 227, 371; and Yang 124, 517
Yinewumana 517
Yingi 160
Yiyantsinni 81, 517
Ylg 165
Ymai 483
Yme 517
Ymer 517
Ymir 82, 83, 95, 97, 104,

www.ebook3000.com

165, 180, 211, 252, 321, 326, 331, 441, 446, 447, 465, 494, 496, 506, 517
Ynakhsyt 517
Ynawc 517
Yngri 181
Yngve 463
Yngvi 181, 357
Yo 517; and In 517
Yo Po 429
Yoalli Ehecatl 460
Yocahu 197
yoga 26, 140, 268
Yoga-Siddha 517
Yogic rites 471
Yogini 517
yogis 141
Yogisvari 148, 517
Yohaulticetl 518
Yohual-Tecuhtin 517
Yohualticitl 320, 456
Yohualtonatiuh 288
Yolaikaiason 28, 81, 518
Yolcuatl 395
Yolkai Estsan 173, 273, 463, 518
Yomanua-Borna 518
Yomi 207, 208, 246, 342, 355, 436, 450, 455, 518
Yomi-no-kuni 518
Yomi-no-yo 518
Yomi-tsu-kuni 260, 518
Yomo-tsu-kami 518
Yomotsukuni 518
Yomo-tsu-kuni 518
Yomo-tsu-shiko-me 426, 518
Yondung Halmoni 518
yoni 27
Yopi 508
Yorodzu-hime 260
Yoruba 23, 67, 74, 138, 146, 165, 172, 231, 233, 250, 355, 358, 360, 361, 362, 365, 366, 367, 368, 423, 513, 515
Yo-shi-wang Fo 517
Yoskeha 78, 201, 518; and Taweskare 518; and Tawisara 518; and Tawiscara 518; and Teharaonhiawagon 518
Young-Woman-with-Food 482, 503
youth 100, 173, 458, 509; eternal 42, 54, 187, 208, 254
Yo-wang 517
Yoyolche 518
Yris 231
Yryn-ai-tojon 518
Yryn-aja-tojon 518
Ysjarughpja 209
Ytzmatul 244
Yu 124
Yu ch'ih Ching-te 225
Yu Ch'ing 412, 518, 519
Yu Huang 126, 329, 466, 518
Yu Lei 317
Yu Nu 519
Yu Po 346, 519
Yu Shih 519
Yuan-kun 383
Yuan-shih 518
Yuan-shi T'ien-tsun 519
Yuan-Shih T'ien-Tsun 412, 519
Yuan-shih T'ien-wang 371
Yucatan 3, 10, 27, 28, 31, 32, 33, 114, 115, 120, 123, 126, 127, 130, 133, 176, 198, 200, 202, 221, 227, 232, 244, 245, 246, 272, 278, 288, 307, 324, 332, 350, 394, 409, 459, 480, 486, 487, 501, 502, 507, 508, 509, 519
yucca 197
Yu-Ch'iang 518
Yu-ch'ih Ching-te 317
Yuddhisthira 519
Yudhishthira 149, 276, 519
Yudhisthira 69, 99, 159, 280, 372, 499, 519
Yueh-Fu Ch'ang O 122
Yueyen-Kwang 277
Yugas 159, 258, 412
Yu-Huang 519
Yu-Huan-Shang-Ti 371, 519
Yuke 220
Yuki 362
Yu-K'ien 123
Yuki-onna 513
Yukionna 519
Yuki-onne 519
Yukut 244
Yul-khor-bsrun 149
Yu-Lu 117, 225, 317, 425, 519
Yum Caax 519
Yum Chung Chun 519
Yum Cimil 202, 246, 519
Yum Kaax 519
Yumbalamob 519
Yumchakob 520
Yumi 445
Yu-ming Kio-shi 465
Yun Chung Chun 346, 520
Yuncemil 10
Yun-chang 277
Yung-Ku Wang 123
Yun-T'ung 178, 288, 467, 520
Yurak 343
Yurlunggur 196, 397, 505
Yurupari 520
Yuryaku 23
Yusco 244, 302
Yu-Shih 519
Yu'ti 519
Yu-ti 126, 156
Yu-tzu 178, 288, 467, 519, 520

Zababa 520
Zabba 520
Zabel 103, 520
Zaden 520, 521
Zagreus 152, 408, 520
Zahak 524
Zahgurim 309, 520
Zahhak 85, 177, 265, 516
Zahrim 309, 520
Zainab 326, 520
Zaire 258
Zairicah 48
Zairicha 48
Zairisha 138, 520
Zairishi 455
Zakar 521
Zal 407, 410, 431, 520
Zalambur 84, 85, 446, 468, 520
Zalgarra 133, 483, 520
Zalmoxis 88, 520
Zaltu 520
Zam Zam 520, 521
Zamama 521
Zam-Armatay 520
Zamba 521
Zambezi 354
Zambi 521
Zambia 338
Zambu 270
Zamin 521
Zamna 244, 501
Zanaharibe 521
Zanahary 52, 399, 521
Zanaru 242, 521
Zandagahih 521
Zande 478
Zaphon, Mount 87, 511, 521
Zapotec 459, 469, 508
Zapotec Quetzalcoatl 132
Zaqar 336, 521
Zaramama 304, 521
Zarathustra Spitama 501, 521, 524
Zari 520
Zarik 143, 521
Zarpandit 522
Zarpanit 522
Zarvan-akarana 525
Zarya 83, 524
Zatik 520, 521
Zcernoboch 124
Zd 422
Zduh 521
Zduhacz 521
Zeal 521
Zebulon 87
Zehuti 154, 464
Zelos 101, 275, 370, 521
Zelus 345, 441, 521
Zem Zem 520
Zemelo 419, 521
Zemes 197, 233, 521
Zemi 521
Zemina 521
Zemis 177, 521
Zempat 521
Zems 521
Zemyna 521
Zemynele 521
Zen 224, 232
Zend 181, 521
Zend-Aves'ta 521
Zeniari 97, 521
Zephyr 182, 522
Zephyritis 61
Zephyros 522
Zephyrus 76, 125, 127, 133, 169, 174, 205, 229, 351, 505, 508, 522
Zeraili 85
Zerbanitu 522
zero 508
Zerpanitum 161, 188, 309, 522
Zervan 86, 249, 525
Zerynthia 61
Zetes 67, 104, 113, 125, 126, 205, 364, 382, 390; and Calais 522
Zethus 47, 57, 244, 253, 522
Zeu Pater 160
Zeus 12, 13, 16, 17, 19, 20, 21, 22, 25, 35, 37, 40, 44, 47, 51, 56, 57, 61, 62, 66, 67, 70, 72, 74, 76, 78, 79, 80, 81, 82, 94, 96, 101, 112, 113, 114, 115, 116, 129, 130, 132, 133, 135, 136, 137, 138, 139, 142, 145, 146, 150, 151, 152, 153, 160, 163, 164, 165, 167, 169, 170, 171, 174, 175, 177, 185, 187, 194, 195, 201, 205, 208, 211, 212, 213, 214, 216, 218, 222, 231, 232, 235, 239, 253, 277, 284, 286, 287, 288, 289, 290, 291, 297, 300, 302, 314, 316, 317, 318, 319, 320, 322, 323, 326, 327, 330, 333, 340, 341, 342, 349, 354, 358, 364, 365, 370, 371, 372, 376, 379, 380, 381, 383, 385, 386, 387, 388, 391, 402, 403, 410, 414, 417, 419, 420, 423, 432, 434, 438, 441, 453, 455, 456, 459, 461, 462, 464, 466, 468, 469, 474, 480, 490, 499, 520, 522, 523
Zeus Chthonios 522
Zeuxippe 170
Zeuxippus 62
Zhag-pa-ma 513, 523
Zhal-zas-ma 47
Zhang Dao Ling 286
Zhou 466
Zi 523
Ziapsu 158
Zib 242, 523
Zigarun 63
Ziku 309, 523
Zima 523
Zimbabwe 350
Zin 523
Zinkibaru 523
Zin-Kibaru 523
Zio 480
Zipacna 115, 198, 227, 502, 523
Zipaltonal 127, 129, 162, 321, 324, 395, 451, 463, 500, 523
Zirbanit 522
Zirna 479, 523
Zisa 130
Zisi 309
Ziu 480, 524
Ziukkinna 309
Ziusudra 59, 152, 167, 486, 524
Ziv 480, 524
Ziva 524
Zivena 524
Ziw 480
Ziz 524
Zleja 524
Zluidni 524
Zmek 524
Zocho 425, 427, 524
Zocho-ten 345, 497, 524
Zoe 21, 351
Zohak 85, 157, 524
Zonget 524
Zoque 121
Zoroaster 53, 84, 157, 203, 338, 438, 501, 515, 516, 521, 524
Zoroastra 325
Zoroastrianism 22, 28, 33, 45, 48, 53, 60, 65, 77, 78, 84, 85, 98, 138, 147, 180, 188, 204, 207, 222, 266, 270, 307, 325, 370, 400, 415, 416, 432, 438, 439, 455, 491, 500, 514, 521
Zorya Utrennyaya 83, 413, 524
Zorya Vechernyaya 83
Zoryas 83, 524, 525
Zoser 235
Zosim 281
Zotz 94
Zotzilaha Chimalman 524
Zrvan Akarana 525
Zu 296, 347, 524, 525
Zuhe 103
Zuimaco 197, 239
Zulu 329, 484
Zulum 309
Zumiang-nui 252, 429, 441, 442
Zuni People 12, 27, 28, 46, 84, 113, 134, 156, 255, 273, 277, 368, 371, 376, 388, 428, 506, 513, 525
Zuntu-zang-po 410
Zurvan 28, 29, 179, 525
Zurvanites 525
Zvezda Dennitsa 524, 525
Zvezda Vechernyaya 524, 525
Zvoruna 525
Zyed 514
Zywie 524

Cosmic Nutrition

Taoist Understanding, Lifestyle & Longevity


Fire
- Fire -
Wind
- Wood -
Earth
- Earth -
Greater Yin
Great Yin
Greatest Yin
Thunder
+ Wood +
Great Yang
- Earth +
Lesser Yin
- Metal -
Lake
Lesser Yang
Greatest Yang
Greater Yang
+ Earth +
Mountain
+ Metal +
Heaven
+ Water +
Water

Mantak Chia and W. U. Wei

Cosmic Nutrition

Taoist Understanding, Lifestyle & Longevity

Mantak Chia
and
W. U. Wei

Edited by
Colin Drown

Final Editing: Ted Ross

Computer Graphics: Hirunyathorn Punsan

Photographer: Sopitnapa Promnon

Design and Production: Suthisa Chaisarn

Illustrations: Udon Jandee

Project Manager: W.U. Wei

© North Star Trust

First published in 2011 by:

Universal Tao Publications
274/1 Moo 7, Luang Nua,
Doi Saket, Chiang Mai, 50220 Thailand
Tel (66)(53) 495-596 Fax (66)(53) 495-852
Email: universaltao@universal-tao.com

ISBN: 974-85401-3-8

Manufactured in Thailand
First Printing, 2011

All rights reserved. No part of this book may be used or reproduced in any manner whatsoever without the express written permission from the author except for brief quotations embodied in critical articles and reviews.

Lower Tan Tien - Navel - Awareness Mind

1. Recharge with Universal Chi. Tan Tien and Universe: Again, raise your hands and charge with the Chi into the universe. Your hands are very big, very long. The bones are hollow and compacted with compressed Universal Chi. Scoop the Chi from above and guide it down. Pour all the way down, down, down to the navel. Touch the navel, and focus on the Door of Life opposite on the spine between L2/L3. Touch and feel the Chi penetrate to the Door of Life Tan Tien and Universe. Feel the Chi penetrate through to the back and out to the universe behind.



A. ***B.***

Fig. 3.54 A. *Recharge the Lower Tan Tien and penetrate through to the Door of Life.*
B. *Raise the hands up to the universe and charge with Chi. Bring the power down to Tan Tien.*

2. Open this Lower Tan Tien the same way as for the Upper and Middle Tan Tiens. Charge more Chi into your hands, and let them be like lasers cutting it open. Cut around to the sides. Pause. The fingers of the left and right hands are very long, extended energetically inside. Cut and feel the energy penetrate into the center. Focus at Tan Tien and universe and feel more Chi.



Fig. 3.55 *'Cut' open the Lower Tan Tien with Laser Fingers.*

Table of Contents

Contents i
About the Authors xi
Acknowledgements xvii
Words of Caution xviii
Introduction xix

Chapter 1: Philosophy of Health.. 1
Healthy People make Healthy Nations 1
Health is your Natural Birthright 2
We are Truly a Civilized Nation 2
Physical Health 3
Emotional Health 4
Mental Health 4
Spiritual Health 4
Four Bodies into One 5
Toxemia, Drug Medication, ... 8
Cure of Disease and Germ Theory 8
Action of Disease 8
Drugtoxicity 9
Drugs Do Not Cure 10
Enervation Causes Toxemia 11
Acute and Chronic Disease 12
Crisis of Toxemia 12
Body Regenerates Itself 13
Germ Theory: Myth or Reality 14
Scientific Germ Discoveries 16
Truth about Germs 18
Germs are Necessary Beneficial to all Life 18
Germs do not cause Disease 19
Four Postulates 20
Germs vs Disease 22
Germ Theory Conclusions 23
American Death Ceremony 24
Take Charge of your Health 27

Chapter 2: Yin and Yang Principle..28
Force of the Universe 28
Eight Strands of the Brocade..30
Taoist Principles of Life within Yin and Yang 30
Unique Taoist Principles of Yin and Yang 31
Yin and Yang create Physical Change 32
Yin and Yang in Health and Longevity 32
Nature of Yin and Yang 33
Yin and Yang Characteristics..34
Yin and Yang in Food & Environment 35
Eat According to Seasons 37
Yin and Yang Scale 38
Cosmic Energy Vortex 40
Yin and Yang 40
Lifes Spiral Unfolds 41
Yin Yang Theory 41
Yin 42
Yang 43
Yang within Yin 43
Yin and Yang 44

Chapter 3: Great Physician Within...45
Fasting is Natural 45
Fasting Defined 46
Fear of Fasting or Starving 47
Experimental and Scientific Fasting 48
Animals and Fasting 49
Historical Fasting 51
What to Expect While Fasting 51
Long Fasts 53
Reasons for Fasting 55
Breaking a Fast 55
Fasting Recommendations 56
Summary of Fasting 57
Rejuvenating Power of Raw Juices 58
Juice Therapy Fasting 58
Eliminative Diet 59
Eliminative Crisis 60
Cleansing Foods 61
Feel Like a Million 62

Yin and Yang Juices 63
Daily Ration of Juice 63
Overcoming Constipation 64
Yin and Yang Constipation 65
Causes of Constipation 66
Detecting Constipation 68
Internal Bath 69
Flaxseed Cure for Colon Cleansing 70
Banana Diet for Intestinal Disorders 70
Other Laxative and Digestive Aid Foods 72
Intestinal Cleanse for Internal Health 72
Abdominal Lift 73
Exercises to Overcome Constipation 74

Chapter 4: Signs of Health and Disease 75
Self-Diagnosis 75
Four Phases of Oriental Diagnosis 76
Five Classes of Yin and Yang People 77
Facial Symptoms of Disease 78
Diagnose and Balance 80
Empty/Full and Yin/Yang Constitutions 80
Face, Hand and Body Diagnosis 82
Nose: 82
Face: 84
Mouth and Lips: 85
Eyes: 88
Eyebrows: 92
Ears: 93
Teeth: 94
Hands: 95
Fingers and Nails: 97
Nail Color: 99
Feet: 102
Hair: 103
Tongue: 104
Voice: 105
Urine: 106
General Body Symptoms 107
Vibrant Health and Human Beauty 107
Price of Health 109

Yin and Yang of Health 110
Yin and Yang of Illness 112
Excess and Deficiency 112
Yin and Yang Types 116
Theory in Practice 116

Chapter 5: Increase your Life Force 117
Twelve Keys to Good Health 117
Eat Only When Hungry 118
Proper Acid/Alkaline & Yin/Yang Balance 118
Masticate & Salivate your Food 120
Never Eat When Upset 120
Eat Food at Room Temperature 121
Cooked & Raw Foods Daily 121
Fasting or Eliminative Diet 121
Combine Food Properly 121
Avoid Close Work during Meals 122
Eat your Last Meal 4 Hours before Bedtime 122
Be Cheerful and Calm at Mealtime 123
Moderation is the Key to Health and Long Life 123
Happiness and Laughter are Medicines 124
Health Wisdom of Benjamin Franklin 125
Food Combining made Easy 125
Eight Food Combining Principles 126
Help for Weak Digestive Systems 127
Food Combining Groups 128
Million Dollar Minerals 128
Glamorous Minerals 130
Power of Minerals 131
Minerals and Richest Food Sources 132
Vitamins for Vitality 139
Natural Vitamins are Superior 139
Major Vitamins and their Food Sources 140
Vitamins and Mineral Food Supplements 143
Power of Enzymes 144
Protein Requirements 145
Protein and Amino Acid Metabolism 146
Proteins are not Fuel Foods 147
Worldwide Protein Research 148
Pritikin Diet Program 149

Dr. Paavo Airola on Protein 149
Protein and Calcium Metabolism 150
Russian Research on Protein 151
Excess Protein causes Cancer 152
Protein Reducing Diets 152
Scientific Consensus 153
Protein Requirements and Sources 153
Grams of Protein in Various Foods 154
Muscleman advocates Low Protein 155
Mayo Clinic Report 157
Protein vs Complex Carbohydrates 157
Vegetable Protein Superior 158
Important Protein Points 159
Carbohydrates and Sugars 160
Fruit Sugars 162
Fats 162
Free Fats are Harmful 164
Whole Food Supplements 165
Alfalfa (Liquid, Tablets or Powder) 166
Kelp and Seaweed 168
Nutritional Yeast 169
Miso 170
Soya sauce 170
Tofu 171
Beet Juice (Tablets or Powder) 171
Garlic 171
Balanced Mineral salt 171
Calcium (Carrot-Poxtoer) 172
Umeboshi (Salted) Plum 172
Spirulina Plankton 172
Herbs (Elixirs of Life) 173
Biblical Records 175
Herbs for Life, Health and Vitality 175
Drugs vs. Plant herbs 176
Health Aide Guide: 177

Chapter 6: Transformations of the Five Elements 178
and Yin/Yang Within 178
Five Elements in Life 178
Way of Yin and Yang 184

Wisdom increases Longevity 185
Transformations of the Five Elements 187
Liver & Gall Bladder Conditions 188
Heart & Small Intestines Conditions 189
Stomach, Spleen & Pancreas Conditions 190
Lungs & Large Intestines Conditions 191
Kidneys & Bladder Conditions 192
Using Herbs according to Five Elements 193
Diet and Longevity Secrets 195
Hidden Hunger 195
Nutritional Power 196
Confusion about Nutrition and Health 196
We are What We Eat 199
Locally Grown Foods for Optimum Health 200
Longevity Secrets of Centenarians 201
Live to be a Hundred 202
Vegetarianism vs Carnivorism 204
Scientific and Anatomical Basis of Vegetarianism 205
Meat is an Unnatural Substitute Food 207
Meat Eating may be Hazardous to your Sex 210
Choosing Your Own Diet 211
Alternative Vegetarian Protein Foods 212
Famous Vegetarian Personalities 213
Nerve Force Principle 213
Health Rating System 215
Level One 215
Level Two 215
Level Three 216
Level Four 216
Level Five 216
Six Formulas to increase your Nerve Force 217
Moderation: 217
Super Nutrition: 218
Correct Posture: 219
Lower Back Wall Exercise 220
Delsarte Hook 221
Daily Exercise: 221
Conserve Nerve Force Energy 223
Dead Still Paper Exercise: 224
Sufficient Rest and Sleep: 224

No-Exercise Super Beauty Treatment: 225
Rest and Sleep: 226
Mental and Emotional Poise: 226
Yin and Yang of Nutrition 228
Extremism versus Balance 228
Food Energetics 230
Center 232
Balancing Yin and Yang 233
Weight Problems 234
Flavors 235
Colors 236
Treatment 236
Underweight 237

Chapter 7: Effects of Yin/Yang with Acid/Alkaline 239
Acid and Alkaline pH 239
Acid-Alkaline Balance 240
Yin/Yang vs Acid/Alkaline Foods 241
Eat Foods in Season 244
Yin/Yang and Acid/Alkaline Conditions 245
Yin/Alkaline Condition Above 7.5pH 245
Yang/Acid Condition Below 6.5pH 247
Yin/Acid Condition Below 6.5pH 248
Acid/Alkaline in Yin Condition Neutral 7.0 pH 249
Yin/Yang in Acid Urine pH 6.5 or Below 249
Yin/Yang-Acid/Alkaline Neutral Urine 7.0 pH 250
True Teacher - The Tao 251
Balancing Body, Mind & Blood Chemistry 251
Effects of Various Diets on Mind and Body 253
Extreme Diets cause Imbalances 254
Sodium and Potassium Balance 256
You are What You Eat 257
Balancing the Life Cycle Triangle 257
Feminine and Masculine 258
Yin and Yang Dietary Guidelines 259
No Extremes 262
Eating Habits versus Making Changes 263
Maintaining Balance 266
Building a Strong Center 268

Chapter 8: Diet Fads, Junkfoodism to Extreme Yin & Yang..........269
Confusion Reigns Supreme..........269
Raw Foods vs Cooked Foods..........271
Food Crank..........272
Overcoming the Junk Food Syndrome..........272
Causes of Junkfoodism..........274
Flowing with the Tao and Yin/Yang Forces..........275
Flexibility is the Key to Yin and Yang Balance..........276
Overcoming the Junk Food Syndrome..........277
Extreme Yin and Yang Foods and Poisons..........280

Chapter 9: Tao Garden's Healing Meals..........302
Golden Nuggets of Nutrition..........302
Grains are Nourishing and Strengthening..........303
Whole Grains..........304
Beans and Legumes..........307
Germinated Seed and Nuts..........309
Miracle of Seed and Nut Germination..........310
Germinating Seeds and Nuts..........311
Enzyme Inhibitors in Unsoaked Seeds/Nuts..........312
Germinated and Blended Seed/Nut Milk..........313
Sprouts: Wonder Food..........313
Fruits for Beauty, Health and Longevity..........315
Eat Fruit Alone..........318
Vegetables: Rich in Chlorphyll..........319
Cultured Dairy Products..........320
General Dietary Principles..........322
Food Cooking..........323
Vital Keys to increase your Life Force..........324
Five Elements and Food..........326
Tao Garden's Organic Gardens..........328
Breakfast..........329
Lunch or Dinner Menu..........330
Mid-Afternoon Snack (If Hungry Only)..........330
Dinner (For Noon or Evening)..........330
Cold Weather Menu Samples..........331
Warm Weather Menu Samples..........332
Eating Habit Tips..........333
Prayer: Chi Charging your Food..........334

Tao Garden's Healing Recipes 335
Solar Light, Fresh Oxygen and Pure Water 352
Solar Time Clock 354
Vibratory Light Waves 355
Healing Ultra-Violet 356
Sunbathing 356
Scientific Solar Research 356
Summary Benefits of Sunlight 357
Fresh Outdoor Oxygen 358
Health Benefits of Deep Oxygen Breathing 359
Oxygen: Blood, Flexibility and Longevity 360
Training yourself to get More Oxygen 361
Water: Liquid of Life 361
Distilled and Mineral Water 362
Drink Only When Thirsty 363
Ancient and Modern 364
Metabolic Typing 364
Metabolic Types 365
Acid and Alkaline Balance 367
Creating Balance 367
Metabolic Groups 368
Dietary Recommendations 368

Chapter 10: Three Treasures of the Tao 371
Psychological Aspects of Yin and Yang 371
Balancing your Yin and Yang Forces 371
Yin Temperament 372
Yin and Yang manipulate each Other 374
Overcoming Temptations 374
Master the Yin and Yang World 375
Attitude changes with your Circumstances 377
Becoming a Free Individual 378
Harmonize your Life with the Tao 379
Marriage of Truth & Love (Yin & Yang) 379
Balancing Yin and Yang Qualities 380
Majesty of Inward Calmness 383
Cleansing Power of Forgiveness 383
Peace through Individual Freedom 384
Be Grateful: Live a Life of Cheerfulness 385
Positive Mental Attitude 385

Easy Way to Overcome Worry 388
Littleness of Humanity 389
Littleness of Time 390
Unconcer of the Future 390
Hurry, the Scourge of Humanity 391
Self-Reliance: Key To Success 392
Opportunities are Self-Made 393
Rely on Yourself 394
Happiness comes from Within 395
Unselfish Service: Key To Happiness 396
Honesty is the Best Policy 396
Right Action leads to Harmony 397
It is More Blessed to Give 398
Golden Stairs in the Tao 399
Law of Personal Magnetism and Attraction 400
Three Treasures of Tao 401
Kind Gentle Nature 401
Be Still and Listen 402
Love vs Power 403
Moderation and a Simple Life 404
Life is Simple 405
Thankful Humble Attitude 405
Be Thankful 406
Know Thyself First 407
Sympathy and Compassion Unlocks Hearts 408
Life is a Stage 409

Bibliography and Recommended Reading..411

Advertizing.. 416

3. Continue cutting to the Door of Life. Touch, and send the Chi from the Door of Life back to the navel and out to the universe in front.



Fig. 3.56 *'Cut' open the Door of Life and send Chi to the navel and universe in front.*

4. Move the hands back around the sides to the navel, extending the fingers and "cutting" the Tan Tien open as you go. Touch the navel: Tan Tien and the universe spiraling. Feel more Chi, and feel the Tan Tien open.

Activate Chi in the Bones of Hips, Legs and Sacrum

1. Now touch your pelvic bone by energetically extending your fingers from the front area near the hips to the back. Feel Chi penetrate into your pelvic bones: funny, laughing, happy bones.
2. Touch the femur bones. Tan Tien and universe. Charge the fingers. Also, feel the funny, happy, laughing vibration inside the bones and in the bone marrow. Be aware of the Three Tan Tiens. Spiral from the universe. Spiraling charging your Tan Tien. Charge your hands and your bones.



Fig. 3.57 *Touch the femurs - happy laughing bones!*

About the Authors

Mantak Chia

Master Mantak Chia

Master Mantak Chia is the creator of the Universal Healing Tao System and is the director of the Universal Healing Tao Center and Tao Garden Health Resort and Training Center in the beautiful northern countryside of Thailand. Since childhood he has been studying the Taoist approach to life. His mastery of this ancient knowledge, enhanced by his study of other disciplines, has resulted in the development of the Universal Healing Tao System which is now being taught throughout the world.

Mantak Chia was born in Thailand to Chinese parents in 1944. When he was six years old, Buddhist monks taught him how to sit and "still the mind." While still a grammar school student, he learned traditional Thai boxing. He was then taught Tai Chi Chuan by Master Lu, who soon introduced him to Aikido, Yoga and broader levels of Tai Chi.

Years later, when he was a student in Hong Kong excelling in track and field events, a senior classmate named Cheng Sue-Sue introduced him to his first esoteric teacher and Taoist Master, Master Yi Eng (I Yun). At this point, Master Chia began his studies of the Taoist way of life in earnest. He learned how to circulate energy through the Microcosmic Orbit and, through the practice of Fusion of the Five Elements, how to open the other Six Special Channels. As he studied Inner Alchemy further, he learned the Enlightenment of the Kan and Li, Sealing of the Five Senses, Congress of Heaven and Earth and Reunion of Heaven and Man. It was Master Yi Eng who authorized Master Chia to teach and heal.

When Mantak Chia was in his early twenties he studied with Master Meugi in Singapore, who taught him Kundalini, Taoist Yoga and the Buddha Palm. He was soon able to clear blockages to the flow of energy within his own body. He learned to pass the life force energy through his hands also, so that he could heal Master Meugi's patients. He then learned Chi Nei Tsang from Dr. Mui Yimwattana in Thailand.

A while later, he studied with Master Cheng Yao-Lun who taught him the Shao-Lin Method of Internal Power. He learned the closely guarded secret of the organs, glands and bone marrow exercise known as Bone Marrow Nei Kung and the exercise known as Strengthening and Renewal of the Tendons. Master Cheng Yao-Lun's system combined Thai boxing and Kung Fu. Master Chia also studied at this time with Master Pan Yu, whose system combined Taoist, Buddhist and Zen teachings. Master Pan Yu also taught him about the exchange of Yin and Yang power between men and women, and how to develop the Steel Body.

To understand the mechanisms behind healing energy better, Master Chia studied Western anatomy and medical science for two years. While pursuing his studies, he managed the Westetner Company.

Using his knowledge of Taoism, combined with the other disciplines, Master Chia began teaching the Universal Healing Tao System. He eventually trained other Instructors to communicate this knowledge and he established the Natural Healing Center in Thailand. Five years later, he decided to move to New York, where in 1979, he opened the Universal Healing Tao Center. During his years in America, Master Chia continued his studies in the Wu system of Tai Chi with Edward Yee in New York.

Since then, Master Chia has taught tens of thousands of students throughout the world. He has trained and certified over 1,500 instructors and practitioners from all over the world. Universal Healing Tao Centers, Chi Nei Tsang Institutes, Cosmic Healing Forums and Immortal Mountain Sanctuaries have opened in many locations in North America, Europe,South America, Asia, Africa and Australia.

In 1994, Master Chia moved back to Thailand, where he had begun construction of Tao Garden, the Universal Healing Tao Training Center in Chiang Mai.

Master Chia is a warm, friendly and helpful man who views himself primarily as a teacher. He presents the Universal Healing Tao System in a straightforward and practical manner, while always expanding his knowledge and approach to teaching. He uses a word processor for writing and is totally at ease with the latest computer technology.

Master Chia estimates that it will take fifty books to convey the full Universal Healing Tao System. In June 1990, at a dinner in San Francisco, Master Chia was honored by the International Congress of Chinese Medicine and Qi Gong (Chi Kung), who named him the Chi Kung Master of the Year. He is the first recipient of this annual award.

In December 2000, the Tao Garden Health Resort and Universal Healing Tao Training Center was completed with two Meditation Halls, two open air Simple Chi Kung Pavilions, indoor Tai Chi, Tao Tao Yin and Chi Nei Tsang Hall, Tai Chi Natural Swimming Pool, Pakua Center, Internal World Class Weight Lifting Hall and complete Eight Court Recreational Facilities.

In February 2002, the Immortal Tao practices were held at Tao Garden for the first time using the Dark Room technology creating a complete environment for the higher level Taoist practices.

In September 2003 Master Chia opened the Tao Garden Holistic Medical Spa using Western and Eastern Technology with Traditional Thai Massage, India Aveda Therapies and Chinese Chi

Nei Tsang Massage. The Spa is supervised by trained and certificated Medical Doctors, MDs with Holistic Degrees providing Colonic Therapy, Stem Cell Cancer Prevention and Natural Cancer Cure Treatments.

In March 2004 the Complete Holistic Mind, Body and Spirit Training was introduce at Tao Garden.

In July 2009 Master Chia introduced the Five Star Eight Forces Detox Spa with Saunas, Therapy Color Heated Pool, Jacuzzi, and Internal Massage Treatments. This was also introduced with Raw Food and Fasting Program with Organic Juice Bar.

In September 2010 the Universal Healing Tao Instructors celebrated thirty years of Master Chia's teaching with the Tao Congress at Tao Garden having over 200 instructors present for the celebration.

Master Mantak Chia has previously written and published these forty-three Universal Healing Tao books:

Awaken Healing Energy of the Tao 1983 - published by Aurora Press
Taoist Secrets of Love co-authored with Michael Winn 1984 - published by Aurora Press
Taoist Ways to Transform Stress into Vitality -1985
Chi Self-Massage: the Tao of Rejuvenation - 1986
Iron Shirt Chi Kung I - 1986
Healing Love Through the Tao - 1986
Bone Marrow Nei Kung - 1989
Fusion of the Five Elements I - 1990
Chi Nei Tsang: Internal Organ Chi Massage - 1990
Awaken Healing Light of the Tao - 1993
Inner Structure of Tai Chi - co-authored with Juan Li - 1996
Multi-Orgasmic Man - co-authored with Douglas Abrams 1996 - published by Harper Collins
Tao Yin - 1999
Chi Nei Tsang II - 2000
Multi-Orgasmic Couple - co-authored with Douglas Abrams 2000 - published by Harper Collins
Cosmic Healing I - 2001
Cosmic Healing II co-authored with Dirk Oellibrandt - 2001
Door of All Wonders co-authored with Tao Haung - 2001
Sexual Reflexology co-authored with W. U. Wei - 2002
Elixir Chi Kung - 2002

Tan Tien Chi Kung - 2002
Cosmic Fusion - 2002
Karsai Nei Tsang - 2003
Cosmic Orbit - 2003
Lesser Kan & Li - 2004
Cosmic Inner Smile - 2004
Cosmic Healing Sounds - 2004
A Touch of Sex - co-authored with Kris Deva North - 2005
Fusion of the Eight Psychic Channels - 2005
Wisdom Chi Kung - 2005
Multi-Orgasmic Woman - co-authored with Rachel Abrams 2005 - published by Rodale
Tendon Nei Kung - 2006
Living in the Tao - co-authored with W. U. Wei - 2007
Cosmic Vision - co-authored with Robert Lewanski - 2007
Universal World Link - 2008
Simple Chi Kung - co-authored with Lee Holden - 2008
Chi Cards - Book I - co-authored with W. U. Wei - 2008
Emerald River - co-authored with W. U. Wei - 2009
Cosmic Cleansing - co-authored with W. U. Wei - 2009
Emotional Wisdom - co-authored with Dena Saxer - 2010 - published by New World Library
Tai Chi Yang Style - co-authored with Andrew Jan - 2010
Taoist Medicine Wheel - co-authored with Kris Deva-North - 2010
Inner Alchemy from the Stars - co-authored with Christine Harkness-Giles- 2011
Tai Chi Wu Style - co-authored with Andrew Jan - 2011

Many of the books above are available in the following foreign languages editions:

http://www.universal-tao.com/publishers/index.html



W. U. Wei

Born after World War I, growing up in the Midwest area of the United States, trained in Catholicism; this student of the Tao started studying under Master Mantak Chia in the early 1980s and in the later 1980s became a Senior Instructor of the Universal Healing Tao (specializing on one on one training). In the early 1990s this Senior Instructor moved to Tao Garden, Thailand, and assisted Master Mantak Chia in building Tao Garden Taoist Training Center. For the next six years this student of the Tao travelled to over 30 countries teaching with Master Mantak Chia and serving as Marketing and Construction Coordinator for the Tao Garden. Upon completion of Tao Garden in December 2000 he became Project Manager (Winter) for the all Universal Tao Publications and products (coordinating the completion of an additional 35 titles). With the purchase of a mountain having four waterfalls in Southern Oregon, USA (late 1990s) this practitioner is presently (Summer) completing a Taoist Mountain Sanctuary for Personal Cultivation, Higher Level Practices and Ascension. The co-author of ***"Living in the Tao"***, the 360 Taoist poems from over 1,200 poems ***"Emerald River"*** expressing the feeling, essence and stillness of the Tao; and co-creator of the Universal Tao formula cards, "Chi Cards" (6 sets of over 240 formulas) & book form with Master Mantak Chia under the pen name the "The Professor - Master of Nothingness", the Myth that takes the Mystery out of Mysticism. William U. Wei also known as Wei Tzu is a pen name for this instructor so the instructor can remain anonymous and can continue to become a blade of grass in a field of grass.

Acknowledgments

The Universal Tao Publications staff involved in the preparation and production of ***Cosmic Nutrition - Taoist Understanding, Lifestyle & Longevity*** extend our gratitude to the many generations of Taoist Masters who have passed on their special lineage, in the form of an unbroken oral transmission, over thousands of years. We thank Taoist Master I Yun (Yi Eng) for his openness in transmitting the formulas of Taoist Inner Alchemy.

Thanks to Juan Li for the use of his beautiful and visionary paintings, illustrating Taoist esoteric practices.

We offer our eternal gratitude to our parents and teachers for their many gifts to us. Remembering them brings joy and satisfaction to our continued efforts in presenting the Universal Healing Tao System. For their gifts, we offer our eternal gratitude and love. As always, their contribution has been crucial in presenting the concepts and techniques of the Universal Healing Tao.

We wish to thank the thousands of unknown men and women of the Chinese healing arts who developed many of the methods and ideas presented in this book. We offer our gratitude to Bob Zuraw for sharing his kindness, healing techniques, inspiration and Taoist understandings without whom the book would not have come to be.

We wish to thank Bob Lewanski for his editorial work and writing contributions. We appreciate his research and great labor. We wish to thank Udon Jandee for his artisic contributions, as well as his ideas for the cover. As well as thanking our fellow Instructors, Colin Drown and Shashi Solluna, for their insightful contributions to the revised edition of various sections and proof reading of this book.

A special thanks goes to our ***Thai Production Team*** for their cover illustration and book design and layout: Hirunyathorn Punsan, Computer Graphics; Saysunee Yongyod, Photographer; Udon Jandee, Illustrator; and Saniem Chaisam, Production Designer.

Words of Caution

The practices described in this book have been used successfully for thousands of years by Taoists trained by personal instruction. Readers should not undertake the practice without receiving personal transmission and training from a certified instructor of the Universal Healing Tao, since certain of these practices, if done improperly, may cause injury or result in health problems. This book is intended to supplement individual training by the Universal Healing Tao and to serve as a reference guide for these practices. Anyone who undertakes these practices on the basis of this book alone, does so entirely at his or her own risk.

The meditations, practices and techniques described herein are **not** intended to be used as an alternative or substitute for professional medical treatment and care. If any readers are suffering from illnesses based on mental or emotional disorders, an appropriate professional health care practitioner or therapist should be consulted. Such problems should be corrected before you start training.

Neither the Universal Healing Tao nor its staff and instructors can be responsible for the consequences of any practice or misuse of the information contained in this book. If the reader undertakes any exercise without strictly following the instructions, notes and warnings, the responsibility must lie solely with the reader.

This book does not attempt to give any medical diagnosis, treatment, prescription, or remedial recommendation in relation to any human disease, ailment, suffering or physical condition whatsoever.

Introduction

The ancient sages and philosophers have long ago discovered the secret of regeneration. Man searches for outward cures when all the time the riddle of health lies within, by living in harmony with the natural laws of the universe.

From the health teachings passed down to our time has come the momentous discovery that the premature aging process which so quickly mars the human body is not Divinely caused; it is a chronic disease, caused by bad living habits.

Regarding aging as a disease or the breaking of natural health laws which create chronic conditions, it follows that the aging process must be subject to the universal law of cause and effect. To stop the symptoms of aging, which are sickness and decrepitude, remove the causes and the effects cannot come. At the present writing of the ancient secrets as laid down in this book, most, if not all the causes of aging and disease seem to have been clearly worked out. Most importantly of all, every one of these known causes is found to be preventable.

A fact long known to science is that the living tissue cells of our bodies are constantly wearing out and being replaced by new ones. The ancient sages, however, maintained that all human tissue is entirely renewed within seven years. If this is so, it means that every human body is actually a new body every seven years; and moreover, that if our bodies could be protected from the conditions which we know gradually bring about aging, they could live on indefinitely, barring accidents, in changeless youth and strength. By natural analogy it would appear that no human or other body could be expected to live forever, even if all the secrets of life were known to science. All things have a certain time during which they exist on the earth. If a man’s time to stay is over, he will have to die. But many die before their time is over, not by a visitation of Providence, but because they are ignorant of the laws controlling their nature.

Life could be indefinitely prolonged if the problem of intestinal auto-intoxication could be solved and the two hundred year man could be as a probable result of the science of the immediate future.

We must all learn from nature, our supreme teacher, and never subject ourselves to any fanatical, rigidly enforced one-sidedness.

Air, sun, water, food, exercise, fasting, sleep and relaxation are all necessary and natural rejuvenating factors, each of equal value, each complimented and completing the others. It is our everyday task and duty to make use of them, at the right time and place, so that our vitality be strengthened, our health promoted, our well-being increased, and our ability to work preserved until the end of our days. If we carry out nature's plan properly, we shall not meet with an early, unnatural end thrust upon us by illness; we shall rather fade away in old age, without pain or torment of death, like a candle extinguishedand find eternal peace.

Medical science as a body, however, is still skeptical about procedures designed to prolong youth or rejuvenate aging. But this need not be taken as discouraging. The history of medicine and science teems with records of organized opposition to new and revolutionary developments. The accepted medical and scientific attitude toward such things has always had and always will have three states: First, it ignores them. Secondly, it becomes sarcastic and irritated about them. Thirdly, it accepts them and forgets that it has not always done so. But this organized resistance to new things works also for the good, in that it warns and protects, so far as it can, the innocent citizen against licensed fraudulent doctors and other advertising quick cure con men. These dishonest quacks should not be mistaken for the honest health practitioner or decent doctor.

Let us be warned by the mistakes of our scientific past and try to be open-minded, but not credulous toward this ancient and up-to-date knowledge of prolonging youth, preventing disease and creating a state of super health; remembering that the present advancement of science admonishes us against defining limits to possible human longevity, and more and more supports the words of an anicent sage written two thousand years ago that man does not die; he kills himself.

Your future health depends upon your daily personal habits of eating, living and thinking today. Reflect upon this ancient wisdom: If you will pay the small price now in learning and disciplining your body, mind and spirit, you will soon come to experience the joy of living in its truest sense.

This comprehensive health program should serve a very useful purpose both in securing better nutrition for those in need of it, and as a practical philosophy for those seeking a better way of living.

3. Now we are going to slowly lower the sensation of Chi down through the bones to the earth. Opening up the sacrum. Move the hands down the legs as you bend down.
4. Lower yourself all the way down to the ground and sit on your feet. Move the Chi with your hands down to your toes, down through the earth and the universe below.



A. ***B.***

Fig. 3.58 A. *Sink the Chi into the earth.* ***B.*** *Lower and sink the mind and Chi down to the universe.*

5. Raise your sacrum up, keeping your hands at the toes. Smile to your Tan Tien and feel the Chi from the universe coming to fill the Three Tan Tiens. Opening up the sacrum.



Fig. 3.59
Raise the sacrum and smile to the Tan Tien.

This book can be heartily commended for both the old and young, rich and the poor. Ones station in life does not change their biological, emotional, mental and spiritual needs. In fact, success and happiness is almost guaranteed when a wholesome attitude toward health, nutrition and a more natural lifestyle is adopted.

In the following pages you will learn not only the ancient and modern secrets of prolonging youth, preventing disease, building health and superior nutrition, but also the philosophy behind wholesome living. The final section contains invaluable information on attaining inward calm for mental and spiritual happiness and success in life. This philosophy is a practical and positive method toward attaining peace of mind, emotional stability and a vibrant state of health. What you want in life it will seek you, but when it comes, it is up to you to seize it.

Awaiting you is a rare experience. You will find this book like a passport to a wonderful new style and attitude of life. It is strange that science has largely neglected studying those of advanced age. It would seem that if more were known about the habits of those who reach 100, physicians could better advise those of us aspiring to such an age. Common sense dictates that long life must be more than chance and happenstance. There must be a combination of factors which increase man's chances for living to an advanced age, and the sooner this formula becomes common knowledge, the longer many of us can hope to survive. To that extent do diet, exercise, outside interests, and family inheritance contribute to man's length of life. Governments have given many grants for studies on various aspects of health and aging. But to date there has never been a major study to discover what factors may have contributed to longevity of our eldest citizens.

Here in this enlightening, inspiring and informative book you will discover the formulas and secret teachings that have been taught through-out the ages. This book is destined to become a classic in its field. It bridges the gap between Eastern Philosophy and Western Science. For the first time, in one volume, you will be given specific step-by-step instructions of exactly what you can do, with complete confidence, to help yourself and your loved ones to a superior way of living-and build a long, useful, satisfying life of health, success and happiness far into advanced age.

This creative book thus treats ancient health teachings in a new light, and new ideas from a unique but authentic point of view. You cannot fail to be impressed by the sincerity, the bold directness, and the rare combination of simplicity and mastery of subject that the authors reveal as the result of years of experience, research, observation and practice in the natural health, new age psychology, spiritual and physical culture fields.

Persistent research and study into the vast mysteries of health, from all parts of the world, enables you to master any of your respective afflictions and you can accomplished it with the most gratifying results through correct nutrition. So can you, if you properly apply the physical, mental and spiritual teachings as set forth in this book. You will be introduced to proven principles, the personal application of which can literally transform your life for the better. With these safe teachings you can progress as far as you wish to go in regaining or maintaining superb health, beauty, strength and fitness.

And these Cosmic Nutrition secrets are all so simple and easy to follow. Every day that you apply these health teachings, you will build and improve your well-being. So why not start today, right now, and decide that you too can benefit by all of the wonderful restorative methods these authors reveal and discover for yourself what a dramatic transformation they will bring into your life.

Realize, health is a condition you have to personally earn for yourself. No one can do it for you. You must create your own conditions of health and physical fitness. Instead of merely treating disease, here are confidential disclosures showing you how to build the kind of magnificent health you are entitled to possess. However, in fairness to yourself, decide to apply these life principles faithfully, patiently, persistently and joyously. Stick to these advanced teachings with conviction. Believe and know that all will be well for you over a long and richly rewarding life. Because nothing else can pay you so well.

All the teachings in this tremendous volume have been fully endorsemented and complete approvaled through time tested understandings. And it is a genuine pleasure to unhesitatingly recommend that you adopt these Cosmic Nutrition rejuvenation teachings and make them a vital part of your life.

Decide to wisely join in this great, growing, popular, new, better and more satisfying way of living. Then let others marvel at the results you have achieved. May the Tao be with you and use the three greatest words in the English Language, ***“Do It Now!”***

Chapter 1

Philosophy of Health

Healthy People make Healthy Nations

When you been feeling below par with no energy, vitality, zest for living you wonder why. You are always tired throughout the day and you have to drag your weary, exhausted body out of bed mornings lacking that driving force during the day. You need ten cups of coffee to keep you going from morning until night and you are plagued with constant headaches, colds, aches, pains and sick nauseated feelings. We all have the desire to be healthy. Unfortunately, many people believe that they cannot live a life without disease, thinking a healthy, vibrant life is impossible, and give up in despair.

Approximately 2% of the people think logically for themselves, 8% of the people think when in pain and suffering and 90% would rather die than think. It is generally believed that sound health arises out of thin air, and that practically nothing can be done about it. With this apathetic public attitude toward personal health and physical fitness, is it any wonder why so few individuals radiate good health. There must be a cause for all of this suffering and disease. Observe closely what people are consuming in the name of food.

You will find them consuming tons of white sugar, white flour and it’s products, salt, oils, fried foods, canned foods, TV dinners, cakes, pop, candy, alcohol, meat, cigarettes, spices, drugs and chemically treated food in boxes and packages. Nothing more needs to be said.

Cancer and other degenerative diseases are steadily on the rise. Forty years ago one out of 17 died of cancer; in 1980, that ratio narrowed to one out of five. Volumes could be written on the decaying health of civilized nations, but it would only clutter up this book. Our primary purpose is to inspire and encourage people, not to discourage them.

The ancients speak of regeneration (renewing youth) by living in accordance with universal law, the Tao. The wise person of today will also maintain youthful health and prevent disease as taught by these ancient cultures.

Health is your Natural Birthright

The individual who is in excellent health has a smile on his face, while the sick person wears a frown. Good health carries with it poise, power self-confidence, courage and success. Poor health leads to irritability, weakness, lack of confidence, fear and failure.

Good health develops personal attractiveness, for nothing adds so much to the appearance of men or women as a wholesome condition of mind and body. The person who is well can concentrate upon their work and can keep at it day after day with no sense of fatigue, depression, or discouragement. The person in ill health works spasmodically and is unable to bring to their work that energy and enthusiasm that begets success and fortune.

We are Truly a Civilized Nation

Observing the overall health of Americans today, disease is on the increase. Mental and nervous disturbances, heart disease, TB, MS, diabetes, kidney and liver disease, cancer, blood disorders, poor eyesight, etc. are evidenced more than ever before.

The Americans lead the world in science and technology, but our average life-span is only 60 to 70 years, far below that of healthful living people. Sickness and suffering affect almost the entire population of this country. Billions are poured into disease research, new wonder drugs and hospitals yearly. The civilized nations are not becoming healthier, but disease on the increase.

Who are the truly civilized nations of the world? Are they the indus-trialized countries, or the Hunzas of Northern India, the Russian peasants of the Black Sea area, Watusi tribes of Africa, Bulgarian mountain dwellers, and certain American Indian villages right the United States?

These cultures have one thing in common; no disease. Their average life-span is at least 100 years, and many reach the age of 150 and over. Disease is totally unknown to them and they work and enjoy life until the day they die. They enjoy long life in absolute health and happiness; and death is very peaceful and quiet, void of all suffering or disease. These”primitives” are very robust and strong physically, mentally, morally and spiritually. Also non-existent in these cultures, are jails, hospitals, mental institutions, homo-sexuality, divorces and police or military force.

It is a proven fact that excellent physical, mental, emotional and spiritual health create a truly civilized nation. The ancient sages, philosophers and wisemen of antiquity lived to an advanced age, as they taught and practiced the following Universal Secrets and Principles of the Tao.

Physical Health

This requires a natural diet of pure wholesome foods that include a daily balance of proteins, fats, carbohydrates, vitamins, minerals, etc. (Organically grown if possible); sufficient exercise, i.e., jogging, swimming, yoga, weightlifting, chi kung, walking, massage, herbs, tai chi, breathing techniques, cycling, etc.; fresh outside air and sunshine daily; fasting when necessary; adequate sleep (at least eight hours); resting when tired; and drinking pure water (distilled, rain water, or spring water).

Developing good physical health requires several years, depending upon one's present physical condition. The wheels of nature grind ever so slowly, but nevertheless, surely. Time and healthful eating and living habits are the primary requirements in attaining good physical health. Remember: The human body, like all phenomena in nature, possesses the inherent power of self-regeneration when the conditions of healthful existence are adopted.



Fig.1.1 Four Body into One

Emotional Health

Emotional turmoil is the result of ill-health and confusion in the mental realm, brought about by overwork, lack of rest and sleep, jealousy, greed, hate, worry, fear, and a life of constant debauchery. People in a state of emotional confusion have little or no control in any department of their lives. They react in a negative way and become emotionally upset when the world around them is not catering to their every whim or desire. Emotional calmness under trying circumstances marks the person of dynamic health and personal magnetism. Good Emotional Health leads to lofty Spiritual Attainment.

Mental Health

Good Physical Health is a foundation for the development of sound Mental Health. The ancients teach us to remain calm and to refrain from hindering or interfering with another's life. Professor Chee Soo, a Chinese Taoist states:

"Do fish In the water complain that It Is cold or dirty? Of course not. Do they complain because the sea becomes rough, or envy or try to exploit each other? No. They live in harmony constantly, never envying or hating anything. Life for them is simply living ..." "The way to the spirit is through constant good thoughts and good deeds, now and every minute of each day, and through this way of life everything becomes an "open door" and the Tao becomes apparent to you In everything you do, and in every thought that passes through your head."

A calm mental attitude is necessary to carry us through the trials of everyday life. Living in harmony with the universal rhythm of life (moderation in every undertaking) produces a healthy mental state.

Spiritual Health

Here we have the culmination and synthesis of the first three characteristics of true health; Physical, Mental and Emotional. Spirituality can be developed only when all conditions, circumstances and difficulties in the game of life have been mastered. When all selfishness, greed, thoughts of hate, fear, anger, worry, anxiety are vanquished, it can then be said that you are on the road to Spirituality. A Spiritual person expresses total love to all people everywhere, whether they are good or bad, black or white, rich or poor, etc. They are unattached to worldly or material possessions, and are happy with or without these possessions. Happiness to them comes from realizing that "nothing in this world brings happiness except ***Peace of Mind***.

It is our human destiny to live in harmony with the order of the universe and attain good health, otherwise we attract mental and physical suffering and pain. Health cannot be purchased. It cannot be conferred by another. Health, happiness and a successfully abundant life cannot be voted in by a government legislature. Neither king, queen nor congress can guarantee the delivery of health, vitality and happiness to you. You must earn it through your own hour by hour, day by day efforts. Only then will you have learned the joy of living as taught by the ancients.

We urge all those who are interested in living a better life, to always keep an open mind and to constantly study, and to make improvements where necessary. This is the only way possible to arrive at any kind of scientific truth. We can learn something new every day if we have the desire to do so. Let us search together now and hopefully we will meet at the Golden Gates of Truth. Disease is an unnatural state to lone living a natural existence. To those who live unnaturally and surround themselves with artificial circumstances, disease is natural, for cause and effect decrees that normalcy shall generate normalcy and abnormality produce its kind. Hence all disease is seated in some shortcoming that opens the individual to such afflictions.

Four Bodies into One

If you look at a fan you can see its blades, when you start the fan up at the first speed, the blades are moving and you can see the blades. You turn the speed up the blades are moving faster but you can still barely see the blades. Then you turn it up to its highest speed and you cannot see the blades anymore. Are the blades still there? Yes. This is what happens with our first four bodies. They are just really one body with four different frequencies (Physical, Mental, Emotional and Spiritual). If you work on one body (frequency) you work on all of them at the same time.

Fan Still see Blades
Physical Body

Fan moving see blades
Mental Body

Fan moving faster Barely see blades
Emotional Body

Fan moving fastest, cannot see the blades
Spiritual Body

Fig.1.2 Four Frequencies of a Fan are the same as the Four Bodies: Physical Body, Emotional Body, Mental Body,Spiritual Body.

The physical body is the easiest to work with because it is in time and space and we can access it with our five senses which is the Taoist's approach. By working with the physical body through Cosmic Nutrition you are also healing and balancing the mental, emotional and spiritual bodies at the same time. We can also access our other bodies (Aethetric, Astral etc.) through further advance Taoist practices with our sixth and seventh senses (clairvoyance and telepathy) but again we work on all the bodies at the same time when we work on the physical body, because all the bodies are one body.

This is how the Taoist approach healing by first focusing on the physical body because it is the easiest connection.



Fig.1.3 Infinity Heavenly Realm - Yin and Yang Physical World

Toxemia, Drug Medication, Cure of Disease and Germ Theory

Oliver Wendell Holmes, M.D., that scholarly gentleman, who was far ahead of the medical world, so aptly voiced his verdict upon his own medical profession when he once stated;

“I firmly believe that, if the whole materia medica could be sunk to the bottom of the sea, it would be all the better for mankind and all the worse for the fishes,”

What is Toxemia? What is Disease? What is Cure? For the answers to these questions we have before us a book written by a medical doctor in 1926, entitled, “Toxemia Explained”, skillfully penned by Dr. J. H. Tilden, in which he defines Toxemia and Crisis of Toxemia. In the process of tissue building metabolism there Is cell building anabolism and cell destruction catabolism. The broken down tissue is toxic. In health when nerve energy is normal it is eliminated from the blood as fast as evolved. When nerve energy is dissipated from any cause physical or mental excitement or bad habits the body becomes enervated; when enervated, elimination is checked causing a retention of toxin in the blood or Toxemia. Of the action of drugs we know little; yet we put them into bodies about which we know less, to cure disease of which we know nothing at all.

Action of Disease

Disease in and of itself is a remedial process; a crisis of toxemia”; the end point of years of enervating habitspoor foods, overeating, alcohol, smoking, lack of exercise, stress, little sleep etc. The body continually strives to heal itself, and disease is the process of self-healing. The organism attempts to eliminate or discharge that which is harmful to it; these are the symptoms of disease, which are generally accompanied by our early warning system called pain. If pain is heeded and the proper natural therapy applied, including correct eating and health habits, disease and the symptoms of disease can be overcome.

Chemical drugs merely palliate the symptoms of disease; they impair the body’s self-healing process and drive the disease toxins deeper into the organs and tissues. Drugs produce “side effects”, which are very often far worse than the original toxic dis-

6. Lower down again. Lower the Chi down to the earth and the galaxy below.
7. Once more, raise your sacrum up, maintaining hand contact with your feet. Smile to your Tan Tien.
8. For the third time, lower down. Open your palms, gathering the Chi from the earth below. Gather and scoop the Chi.



Fig. 3.60 *Gather the Earth Chi.*

9. Touch your heels and feel your bones as you slowly rise up. Fill your bones with Chi as you guide it up with your hands.
10. Fill the bones in the upper legs as you move your hands up.



Fig. 3.61 A. *Fill the bones with Chi.* ***B.*** *Feel your fingers penetrate into the bones as you rise.*

ease. The side effects of drugs indicate that the body is using its vital energy in an attempt to eliminate the drug poison through the internal organs or other body parts. Medicines only relieve the “temporary” symptoms of disease, pain and distress; they do not overcome disease or improve one’s state of health and well-being.

Drugs do not possess the quality or power to act in a living organism; the living organism acts or reacts to any drug or poison in an attempt to expel it before it causes any possible internal damage. The key word here is living. The human body cell is a living intelligence, and as a unit of life it knows when it is being ill-treated or poisoned by dead and inert substances inimical to its existence. Thus, we observe the side effects of drugs when the living, acting body goes into action against them.

Dr. H. M. Shelton, a leading health researcher writes about the action of drugs: When a drug is vomited, this is an action, but it’s an action of the living organism and not of the lifeless drug. It Is absurd to write of the physiological actions of poisons: first, because they cannot act; and, second, because their presence always occasions pathological action. These so-called physiological effects of drugs are symptoms of disease. No pharmacologist, no pathologist, no physician will deny this. Dr. Anthony J. Sattilaro, who cured himself of cancer through diet, writes: If we can at least show that people can live better in their lifetimes, rather than suffering all the iatrogenic effects of the standard modalities that we have in Western medicine, I think we will have made a great contribution.

Drugtoxicity

Treating the sick with drugs only adds more to the existing toxemia within the body. It suppresses the healing power of the body. Drugs destroy red blood cells, cause anemia, and create a false illusion of being cured. The drugged patient returns again and again for stronger doses of medication and more experimental treatment. Remember: Health is built through everyday healthy eating and living habits. In addition, health can be restored by applying nature’s wholistic therapies, i.e., fasting, herbs, acupuncture, massage, sunshine, oxygen, hydrotherapy, exercise therapy etc.

Drugs Do Not Cure

The following statement is a universal law oi healing: Medicines do not heal or cure the body. The true cure lies in the removal of the causes of disease, and adopting rational and healthful living habits. When this path is followed, the body will then have the energy and power to regenerate, recuperate and heal itself. We then become free from the causes and symptoms of disease.

There are no instant cures for diseased living habits. The process of disease takes many years to develop, as does the return to health. Nature works her wonders ever so slowly. We can dis-cover new wonder-cures everyday, however, we can never escape from the natural law of cause and effect, or whatever we sow, so shall we reap. Disease is created by diseased habits; health is created by natural health habits and principles.



Fig. 1.4. Toxic Phycial, Emotional, Metal & Spiritual Bodies


RHEUMATISM
COLITIS
CATARRH
INDIGESTION
HEADACHES
NERVES
ARTHRITIS
TENSION
COLDS
PREMATURE OLD AGE
FATIGUE
CONSTIPATION
TOXEMIA
Branches
Trunk
Lowered Vitality
Abnormal Composition of Blood
Accumulation of Morbid Matter and Poisons in the System
Roots
IGNORANCE
INDIFFERENCE
MALNUTRITION
ENERVATION
The Soil
VIOLATION OF NATURES LAWS

Fig. 1.5. The Root causes of Impaired Health - Tree of Toxemia

Enervation Causes Toxemia

A thousand and one enervating habits of living are the primary causes of toxemia. Without proper and adequate nerve energy, our food is not digested and assimilated properly; cellular elimination and renewal is checked; metabolic wastes are retained in the system, causing toxemia; this leads to a crisis of toxemia, or what is commonly called a disease. Disease is a crisis of elimination by a system overloaded with toxic waste and auto generated poisons. A fast, rest in bed, and the giving-up of enervating habits, mental and physical, will allow nature to eliminate the accumulated toxin; then, if enervating habits are given up, and rational living habits adopted, health will come back to stay.

Acute and Chronic Disease

Acute diseases are short termed. Their symptoms are often violent, but only temporary. Acute symptoms indicate that the body possesses sufficient vital nerve force and energy to eliminate internal toxic conditions, such as colds, flus, mumps, measles, acne etc. On the other hand, chronic diseased conditions are of a more long standing nature, in which pathological degeneration of the cells, tissues and organs has taken place, i.e., cancer.

Suppressing acute symptoms of disease with drugs, if continued for many years, will result in chronic ailments. Acute disease symptoms should be allowed to run their course, without suppressing them with drugs. Acute symptoms turn into chronic pathology by suppressing them. Drugs create chronic disease by suppressing the natural channels of eliminationkidneys, bowels, lungs and skin.

The indiscriminate use of medication when the body is already diseased (toxic) is an unwise gesture. If the organism has the inherent power of self-healing, self-cleansing, and self-regeneration, what then is the purpose of inducing drug medication in an attempt to cure the sick? Answer: There is no return to health with such a practice. It is just a practice and nothing more. Human beings are the willing guineapigs to these drug experimenters. The cures may come and the cures may go, but the curing goes on forever. Also, the billions of dollars involved in the research and the sale of drugs, goes on forever.

This outmoded suppression and treatment does not stop the cause of sickness, cannot prevent further illness and it certainly plays no part in the building and maintenance of healthy cells and tissues. It is not the Creator's intention that man should live by the aid of crutches (drugs and other artificial remedies) or turn this planet into one vast hospital for the sick.

Crisis of Toxemia

Every so-called disease is a Crisis of Toxemia, which means that toxic matter has accumulated in the blood above the point of toleration, and the crisis, the so-called disease call it cold, flu, pneumonia, headache, or typhoid feveris a vicarious elimination. Nature is endeavoring to rid the body of toxin. Any treatment that obstructs this effort of elimination, baffles nature in her efforts at self-curing.

Drugs, feeding, fear, and continuing to work prevent elimination. A cold is driven into chronic catarrh; “flu” may be forced to take on an infected state; pneumonia may end fatally if secretions are checked by drugs; thyphold will be forced into a septic state and greatly prolonged, if the patient is not killed. Drugging pain of any kind checks elimination and prevents the human organism from cleaning house.

Cancer, tuberculosis, Bright’s disease, and all chronic diseases were once innocent colds “ameliorated” and which returned and were ameliorated again and again, each time accompanied by a greater constitutional enervation, and a greater constitutional toleration for toxin-poisoning, requiring a greater requisition of mucous membrane through which to eliminate the toxin.

To find the cause of cancer, start with colds and catarrh, and watch the pathology as It travels from irritation, catarrh, inflammation Induration, ulceratlon to cancer.

The proper way to study disease is to study health and every influence favorable or unfavorable to Its continuance. Disease Is perverted health. Any influence that lowers nerve-energy becomes disease-producing. Disease cannot be its own cause, neither can It be Its own cure, and certainly not its own prevention.

The treatment of disease is so simple that It staggers those who believe in drug curing. Heroic treatment is disease-building. Find in what way nerve-energy Is wasted, and stop it stop all nerve leaks. Then returning to normal Is a matter of time, in which nature attends to all repairs herself. And nature resents help medical officlousness.

Body Regenerates Itself

Western medicine too often tends to look at disease in small parts, forgetting that the whole body functions together as an entire unit. Instead of merely treating a particular symptom of disease, we must learn to look for the cause of disease, and eradicate it.

The real error arose when pharmacology and morphology (form and structure of living things) joined together to treat disease. An organ is treated with a drug, or an organ is transplanted. We are only temporarily palliating the symptoms of disease. The body functions as a whole, and will regenerate itself if properly cared for; it was never meant to be taken apart or artifically poisoned. The organs work in a system within the body to overcome disease, balance itself and regain a state of equilibrium. This is the thrust of holistic medicine. The germ theory of disease will be laughed at during the next century as the crowning piece of folly of the present.

Germ Theory: Myth or Reality

How did the Germ Theory begin? In the mid-seventeenth century, Leeuwenhoek and O. F. Muller studied and reported several forms of bacteria. Around 1830, Ehrenberg separated and grouped microbes into species and genera. Early investigations were badly handicapped by poor microscopes and the lack of understanding and accuracy.

Louis Pasteur became famous as a result of the controversial research he conducted on the germ theory of disease. He is known mostly for the Pasteur treatment of hydrophobia and pasteurization. Pasteur claimed the body was like a barrel of beer, and said, like beer, our bodies were at the mercy, or subject to invasion from germs and bacteria. He pronounced the Germ Theory of Disease, thusly: Each type of germ was responsible for creating its own specific type of disease or sickness. And diseases are due to an outside invasion of specific germ organisms.This theory was merely an announcement or conjecture by Pasteur, but it was, unfortunately, heralded as the final answer and great advancement in science, though the theory had absolutley no foundation in fact. If this theory were true, and proved scientifically, we should all be dead immediately by germ invasion.

Over a century later Dr. Robert O. Young discovered while working with dark field phase-contrast microscope (This high-powered microscope can magnify objects up to 28,000 times, enabling one to clearly view bacterial and fungal forms in exact detail in the blood.) that a dying cell revered back to a living cell when the internal environment of the cell changed from an acid statement to an alkaline state. He was so overwhelmed that he research all the data on the germ theory dating back over a 150 years and discovered that our bloodstream and the inside of your body (cells) have a landscape or terrain and in a disease state the body tissues to become too acidic. This imbalance sets the stage for chaos and disease based on the acid/alkaline balance in the terrain when the body is not getting the raw materials (nutrients) it needs for maintenance and repair to change the terrain back to normal. He concluded that germs are symptoms that are a result of thriving in an unbalanced terrain. Through Dr. Youngs research he discovered that Antoine Bechamp (1816-1908) a French Professor of Medical Chemistry and Pharmacy described the process of fermentation for what it is: a process of digestion by microscopic beings. He was the first to assert that the blood is not a liquid, but a flowing tissue and brought to the world in 1866 profound revelation that the granules were living ferments. He renamed them microzymas meaning small ferments as an independently living element within all living things, and is both the builder a recycler (Creative Cycle) and destroyer (Controlling Cycle) of organisms.In a state of health, the microzymas act harmoniously and fermentation occurs normally. But in the condition of disease, microzym become disturbed and change their form and function. Their function is a twofold and they are poised to recycle the physical body upon death into the earth (dust to dust). He referred to microzymas as the builders and destroyers of cells. Disease is a condition of our inner terrain and is not caused by attacking entities. This living particle of dust was first discovered by Professor Antoine Bechamp in 1864, and he found it to be physiologically imperishable and autonomously alive, meaning it have the ability to adapt to any circumstance while maintaining its purpose to enhance and organize life whether for the host or for itself. Bechamp stated that the microzyma was thoroughly impressionable and the only living entity capable of receiving and impression. These understandings of Bechamp and Young explaining the microzymas and the balancing of the pH factor (+ Yang & - Yin) confers with the all of the Taoist understandings of the Cosmic Dust Particulars(Star Dust) that give life to all beings and the balance of Yin and Yang in the body for health and well-being. In the morning at sunrise or in the evening at dust you can see them by squinting into the sun as shiny particulars giving life to all of the earth.

Pasteur himself, at a later date, proved the fallacy of the germ theory to his entire satisfaction despite his previously heralded announcement. However, since it departed from his first discovery, that germs cause disease, his new discovery was suppressed.

Pasteur stated that germs and bacteria are not the exact and primary cause of disease. He abandoned his earlier beliefs on the Germ Theory and became convinced that the germ was secondary and the disease came first. He said: The presence in the body of a pathogenic agent is not neces-sarily synonymous with infectious disease. Pasteur finally opened his eyes to the fundamental fact that germs and bacteria change their forms according to their environment. He realized the truth of these facts in the mid-1880's. However, the stage was set, the propaganda had already began, the lie perpetuated by the regulars, and the error, unfortunately, has continued up to the present day. Thus arose the foundations of the modern germ theory of disease, and in the midst of the wildest conjectures and the worst of logic, a nucleus effect was won, which has since grown and Is growing daily.

Scientific Germ Discoveries

The investigations of Cohn, Pasteur, Koch, Nageli, Kurth and others were totally overlooked: They proved that bacteria are affected by the medium in which they are cultivated. Not only are the forms modified, but also the physiological activity varies in degree and time. There is no question that certain bacteria are associated with specific diseases, but the big question science must face is: Are these germs the accompaniment of the disease or are they the cause of the diseased condition?

The idea that bacteria of a certain specific kind was the accompaniment of the disease was ruled out because it was found that in any particular disease the same type of bacteria was always found So, in order to satisfy a doubting public and furnish an answer to the question, What makes me sick? The medical profession answered germs, of course.

However, in view of the scientific research which has been cast aside by medicine, It is just as reasonable to assume that the maggots and flies found In a manure pile caused the manure pile as it is to assume that the various kinds of germs and bacteria, bacilli, or micro-organisms, by whatever name you may call them, found In a thoroughly filthy body poisoned with (bad) food, drugs, and bad habits, caused the condition of ill health.

Long ago it was demonstrated that the living tissues of a healthy body exert actions which are antagonistic to any of these parasitic invaders; and later bacteriological research shows that the mere admission of a germ or bacteria into an animal does not necessarily cause disease. With the claim by Dr. Rawlins that 2% of the people are diphtheria carriers, in other words, have diphtheria germs in their noses and throats, and yet have no diphtheria, how is the germ theory as the cause of disease correct?

We constantly breathe in some 14,000 germs and bacteria per hour. You cannot keep them out of your body; they are everywhere. Why, then do we not all have some form of disease? Why are some people immune to many diseases, and others susceptible?

It was proven many years ago by Dr. Bosenow of the Mayo Clinic that bacteria change their form according to the medium in which they live. For example, he was able to ‘reduce the pheumococcus (germ) to a streptococcus, and a streptococcus back to a staphylococcus,’ simply by changing the medium and environment in which they live. This is very important for you to under-stand, for it will liberate you from the fear that germs can cause a disease. People fear from lack of understanding; and when they understand that both health and disease are created by then-own living and eating habits, they will no longer fear the (ubiquitous) ever-present germ.

BONK
BING
HONK
VOOOM
HONK
WHAM
BAM
BEEP
HONK
CRASH
THUD
CLUNK
ZIPZIP
BOOM
THUD

Fig. 1.6. Learn to Live with Our Germs, they are our Friends

Truth about Germs

It is a scientifically known fact that: 1) Germs take on a form in accordance with their environment; and 2) So long as the internal environment and health of the body remains sound and vigo-rous, it will be completely immune; 3) Germs and bacteria are the lowest form of scavengers and they thrive and multiply in waste matter and filth within the system; 4) Disease germs and bacteria are not capable of affecting healthy living cells and tissues, for they do not have the strength or power to change or alter a higher living life form than themselves, i.e., germs only feed on the lifeless waste of an unhealthy and broken down condition of the body; 5) Bacteria are not the cause of disease, but may be considered as acces-sory factors or tertiary causes, analogous to the common garbage fly or vulture, who feed only when the refuse is placed in the garbage receptacle or an animal dies in the wild.

Germs are Necessary Beneficial to all Life

Microbes are spread throughout nature, are ubiquitous in fact. Human groups swarm with them. They are in the food we eat, the water we drink and the air we breathe. We are reared In an environment laden with them. We cannot escape them. We can destroy them only to a limited extent. We must accept them as one of the joys of life.

From the stand-point of Natural Science, germs cannot be regarded as the cause of disease, for if they were, we should all be victims of one or more germs at all times. Germs are saprophytes; that is, they live off dead inorganic matter. They are omnipresent scavengers in Nature's great laboratory, working over dead organic matter Into forms appropriate to the nourishment of growing vegetation. They are essential nitrifying agents in the soil. Without them, neither plant nor animal could long exist, and the earth would rapidly become encumbered with dead bodies. In the septic tank, sewage is reduced by them until it finally passes out pure water in which fish may live. From both, the esthetic and economic viewpoint, they are benefactors. They are friends of higher life. We live in a balanced and interdependent world, which Is too complex to ever fully understand, but our dependence upon the symbiotic support of germ life is, at least partly, known.

11. Feel your bones, and fill them with Chi all the way up to your coccyx. Touch your coccyx. Leave your fingers there, then be aware of the Chi and feel the Chi raising up to the Tan Tien and the universe. Feel it charge the fingers and the spine.
12. Come up to the sacrum. Feel the sacrum open. Focus at the Tan Tien and the universe.


A. **B.**

Fig. 3.62 A. *Bring the Chi to the Coccyx.*
B. *Move your hands up to the Sacrum and feel the Chi rise up to the Crown.*

13. Come up to the door of life, and then back to the navel. You may sit down to continue the next step in the Cosmic Healing Practice.



Fig. 3.63 *Bring the Chi to the Door of Life and let it penetrate to the Navel.*

Practice daily till you feel the Chi. Then you can apply this Chi to the Healing Sessions.

In the body, germs break up and consume dead and dying cells and discharges from the tissues. They perform the same function in the body that is ascribed to them everywhere else in nature. Viewed from this angle, they are purifying and beneficial agents.

Germs are really our best friends. All living matter and human health are totally and com-pletely dependent upon bacterial presence. They are fundamental to the existence of all higher organic life. The atmosphere has 4/5 nitrogen. The soil contains nitrogen fixing bacteria. No plant or animal can use nitrogen directly, with the sole exception of this soil bacteria, which converts nitrogen, with other elements, into nitrates and nitrites and thus develops material for the plant to develop protein. We obtain our nitrogen from the plants, and the plant gets it from the soil with the help of bacteria.

Scientific experiments have shown that when small animals were placed in completely germ free containers, they failed to develop normally; the intestinal tract became abnormal, liver deformed, lungs failed to develop properly and many deformities and ill-health followed. Bacteria is essential for normal development and health, for example, infants at birth are totally sterile, but in 24 hours there are millions of bacteria in the gastro-intestinal tract, which are necessary for the utilization of mother's milk.

Complete and adequate digestion of food is dependent upon a natural abundant supply of intestinal flora, which are referred to as bacterial enzymic activity. They are necessary for the breakdown, assimilation and absorption of all food material. When health Is normal the digestive secretions are sufficient protection against germs and parasites. Germs may cause putrefaction in a meal of lobsters when enervation prevents digestion; but when digestion is normal, the bacillus are utilized as food along with the lobster. Alt of the digestive juices are germicidal, and the normal digestion digests germs as readily as it does apples or bread.

Germs do not cause Disease

If germs are powerless against a healthy body, the logical preventative is the cultivation of health. If the body manufactures its own antiseptics and antitoxins, it should be supplied with the proper elements of sun, air, water, (natural) food, exercise, rest, etc., out of which to build these protective potencies, instead of being subjected to the present mad-house efforts to produce artificial immunity.

Pasteur said: “In a state of health the body is closed against the action of disease germs.” It is a mistake to single out one of the correlated factors that constitute cause and hold it responsible for pathology. Germs alone can no more pro-duce pathology than a seed alone can produce a tree. Just as a seed must have a fertile soil, moisture, air, water, warmth and sunshine, if it is to grow into a tree so the germ, if it is to add its complicating influence to an evolving pathology, must find certain essential conditions existing in the bodies of those it enters, before it can do the slightest harm. Normal nerve energy and pure blood in a word, good health are proof against germs of all kinds.

Impaired health provides the suitable soil in which germs thrive and grow. The soil is more important than the germ. Infection and degeneration can set in only when the soil is badly fertilized by inappropriate nutrition. Germs are imminent coagitators always secondary; a possible reinforcing or contingent cause, but never an exciting or primary cause.

A universal cause comes first; then the ferment, in the form of a germ, gaining access to the weakened tissues, takes on activity and attempts to assist the removal of undesirable material by liquifying it. The morbid material generated by this activity is more a by-product of the disintegrating tissue than a virulent poison resulting from bacterial maliciousness. Germ activity, in this view, is an outside accessory that facilitates the removal of auto-generated filth.” Germs “may complicate when there is a perversion of chemistry. But the germs of the so-called specific ‘diseases’ never take on specificity until the vitality of the different tissues is lowered and nutrition perverted because of dysemla the chemistry of the blood fails to supply the essential elements; then germs, previously innocent, take on virulency in keeping with the general enervation and systemic toxemia of the individual.

Four Postulates

Many years ago, the famous Dr. Koch, a bacteriologist, concluded, that the mere presence of a germ or bacteria in a cell, tissue, or organ is not adequate proof that it causes the disease, and he stated four requirements which must be met before any causal relationship between germs and disease are admitted:

1. Specific bacteria or germs must be found in every case of the disease.
2. Bacterium must never be discovered apart from the disease.
3. It should be possible to isolate the bacteria, culture them in a media and be capable of independent existence.
4. The introduction of a small amount of a pure germ culture should produce signs and symptoms of a specific disease in a healthy organism or body.

The Germ Theory, to be valid, must conform to all four requirements or postulates; all four postulates have been disproved, as demonstrated in the following explanations:

First Postulate: It is a scientifically known fact that specific bacteria are not found in every case of a specific disease. The well known physician, Sir Wm. Osier reported that the diph-theria bacillus is absent in 28 to 40 per cent of cases. According to Green's Medical Diagnosis: "Tubercule bacilli may be present early, more often late, or in rare instances be absent through-out." Koch's first condition is not fulfilled in tuberculosis, diphtheria, typhoid fever, pneu-monia or any other disease, because germs and bacteria are found in human and animal bodies which are healthy and free from the specific dis-ease, or diseases.

Second Postulate: The bacterium are found apart from the disease. It is a medically known fact that bacteria and germs are found in bodies, human and animal, which exhibit no signs and symptoms of any disease; proving beyond any doubt that the lowly innocent germ is not causing a disease. Healthy and disease free people of all ages, upon examination, will be found to harbour bacteria associated with many different diseases, yet, they do not have, have not had, and do not subsequently develop the 'diseases' these germs are supposed to cause. This second postulate holds not one bit of truth, and is rarely conformed to.

Third Postulate: Germs and bacteria are not capable of independent existence as they totally depend on the human or animal organism for their survival. If germs depend on the 'host organism' for survival, they cannot be considered as direct causes of disease, therefore, Koch's third postulate, just as the first two, fail to meet the 'acid test' of the germ theory of disease.

Fourth Postulate: Introducing germ cultures in a healthy body or organism does not produce signs and symptoms of the disease. The Bio-Chemical Society of Toronto conducted a number of very interesting experiments in which pure cultures of typhoid, diphtheria, pneumonia, tuberculosis and meningitis germs were consumed by the millions in food and drink by a group of volunteers. The results: no ill effects whatsoever. No diseased signs; tuberculosis germs were fed in water, milk, bread, cheese, butter and potatoes, meningitis germs were swabbed into the nostrils, tongues and ton-sils, diphtheria germs were taken in large doses, and the results of these tests showed absolutely no signs of disease. We have shown that fourth postulate that germs cause disease is a complete failure.

Germs vs Disease

If you have a particular disease, what should you do about It? You do not do anything about it. What you do, is you do something about the causes. That's most important. Find the causes of these various problems, and do some-thing about the causes. You do not do someting about the diseases. The disease represents the effort of resistance on the part of your body against the causes. It Is the causes of disease that bring about changes within the body; It is the causes of disease that bring about degeneration; it is the causes of disease that kill you, not the diseases. The disease Is the body's response, or its attempt to combat, overcome and destroy the causes. So, the disease is the process by which the body resists the causes of disease. Disease is the process of resistance, of action, of defense, remedial action, defensive action, or adaptive action.

As a patient's health status changes, bacteria found In the organism also change. Normal flora change into pathogenic as a result of a change of health. For example, a person in a hospital with normal or average bacteria flora in the body, after a cardiac arrest, within a matter of hours, the bacterial flora change and pathogenic bacteria are present. This indicates clearly that the person first develops the disease and then the bacteria change, pro-liferate, contribute perhaps, as secondary factors by elaborating their own toxins which the body has to deal with and in this way are associated with certain diseases, but not as causes.

Germs and bacteria are more In the nature of scaven-gers, more In the nature of organisms which are contributing positively to the remedial process i.e., by the breakdown of certain decomposed organic products; by the partial digestion of the body's degenerated tissue, because the bacteria themselves elaborate enzymes which digest tissue and the damaged and unhealthy tissue may be broken down by the bacterial enzymes, there-fore, they are acting to some extent as scavengers.

Obviously, we can do nothing about germs in the way of destroying them. If It were possible to destroy them, we would also destroy the rest of organic existence. Consequently, germs are our benefactors, they are neces-sary to life, to normal development; they are intimately associated with certain diseases, acting constructively on our behalf. We should try to understand the inter-relation-ships between micro-organisms and man, and not be forever in fear of them or chasing methods and mechanisms of destroying them. It is, Indeed, difficult to understand why a whole pro-fession has gone insane on the subject of bugs, to the utter neglect of those states of metabolism and nutrition which, when vitiated, constitute the universal cause of all disease.

The medical profession believes that the blood can be immunized. Normal blood does not need it, and the process lowers its resistance; and the victim of low resistance toxemia is further deteriorated by such treatment. An unreasoning way to rid the victim of germs and parasites Is to destroy them with germicides and parasiticides. After killing them off what is to be done about the habitat the patient? The belief that germs can be killed Inside the body is untenable, for any chemical that destroys micro-organisms also destroys the body. Even If medical men are still trying to kill venereal germs with drugs, the fact still remains that they damage their patients more than they do the germs. If I would live my life over again I would devote it to proving that germs seek their natural habitat diseased tissue rather than being the cause of diseased tissue; e.g,, mosquitos seek the stagnant water, but do not cause the pool to become stagnant.

Germ Theory Conclusions

The great fact remains that germs, bacteria and microbes are our best friends instead of our worst enemies. They are necessary in both health and diseased conditions; in health, as friendly bacterial ferments (enzymes) to necessitate the proper digestion and assimilation of foods; and in diseased conditions, by becoming active and assisting in the removal of undesirable material (dead cells, cellular wastes and filth) by liquifying it. Germ activity, in this view, is an outside accessory that facilitates the removal of autogenerated filth, which, if not released, will cause the dissolution of the body. With the filth go the germs. The search for ‘germs’ and ‘germ killers’ has lasted for over 100 years, and in all that time science has never found an anti-biotic, pill, or vaccine that would kill a germ that would not also kill the living body.

It is now known generally that the juices of a healthy body present far greater powers of immunity to all manner of germs than any anti-biotic that can be made. It would be more intelligent, instead of hunting for a magic pill, powder or medicine to kill off ‘germs’, to study the require-ments and conditions that bring about a state of health. By living in this “Super State of Health”, one need not worry about resisting noxious bacteria, for you will once and for all rid your (temple) body of the filthy soil that is required for the life and propagation of ‘germ scavengers’. For then, you and germs will be living together on friendly basis.

The entire philosophy of health is expressed in these words, Keep clean internally and externally, and learn to control and stay within the magnetic margins of your vitality and health. These health building suggestions, if followed faithfully, will reward one with superior health, vitality, energy and a zest for living far into advanced age. One will have no fear of germs, for through understanding they will gain knowledge, wisdom and the power to master the drama of life, including the lowly microbe. Neither ought you to attempt to cure the body without the soul; for the reason why the cure of many diseases is unknown to the physicians of Hellas is because they are ignorant of the whole, which ought to be studied also, for the part can never be well unless the whole is well.

American Death Ceremony

The death ceremony started as a crude ritual, back In the days of witchcraft. In recent years it has been developed Into a science. It usually takes from 10 to 15 years, however modern scientific advancements are shortening this period of time. It starts with one simple headache. When the one aspirin will no longer cover up the headache, take two.

After a few months, when two aspirin will no longer cover up the headache, you take one of the stronger compounds. By this time it becomes necessary to take something for the ulcers that have been caused by the aspirin. Now that you are taking two medicines, you have a good start. After a few months these medications will disrupt your liver function. If a good Infection develops, you can take some penicillin. Of course the penicillin will damage your red blood corpuscles and spleen so that you develop anemia. Another medication is then taken to cover up the anemia. By this time all of these medications will put such a strain on your kidneys they should break down. It is now time to take some antibiotics. When these destroy your natural resistance to disease, you can expect a general flare-up of all of your symptoms. The next step is to cover up all of these symptoms with sulfa drugs. When the kidneys finally plug up you can have them drained. Some poisons will build up in your system but you can keep going quite a while this way.

By now the medications will be so confused they will not know what they are supposed to be doing, but it does not really matter. If you have followed every step as directed you can now make an appointment with your undertaker. This game Is played by practically all Americans, except for the few ignorant souls who follow nature. Leave the drugs in the chemist's pot if you cannot heal yourself with nature's food.

Code of Health:

Balancing Yin & Yang Foods - Fasting or Eliminative Diet - Intestinal Cleanse - Sufficient Exercise - Stretching - Plenty of Fresh Air Exhaling Sufficiently - Proper Posture - Adequate Sunshine - Pure Water - Moderation - Correct Reading & Close Work - Self Control - Comfortable Clothing - Sufficient Rest & Sleep - Deep Breathing - Relaxation - Correct Eating - Acid & Alkaline Balance - Chewing Food Well - Personal Cleanliness - Knowing What You Want - Positive Thinking - Confidence - Compassion - Honesty - Eating Foods In Season & your Climate - Temperance in Habits - Eat only When Hungry & Thirsty - Cheerfulness - Thankfulness - Forgiveness & Love - Freedom - Meditation & Prayer



Fig. 1.7. Learn to Work with the Causes of Health

Causes of Disease:

Eating Extreme Yin & Yang Foods - Toxemia (From Enervating Habits) - Constipation Over or Lack of Exercise - Insufficient Stretching - Indoors Too Much - Insufficient Exhaling - Incorrect Posture - Lack of Sunshine or Over Exposure - Impure Water - Overwork - Incorrect Reading & Excessive Close Work - Nervousness - Lack of Self-Control - Restrictive Clothing - Insufficient Rest & Sleep - Working at Night - Tension & Worry - Malnutrition - Out of Acid/Alkaline Balance - Poor Personal Hygiene - Confusion - Fear & Doubt - Eating Foods Out of Season & your Climate - Using Prescription & Recretional Drugs or Alcohol - Overeating & Drinking - Self Righteousness - Discouragement - Self Pity - Fault Finding - Gloominess - Vengence & Hate

These are only a few of the basic causes of health and disease. Open your mind, for we can always learn more about life; ***Know Thyself***; keep the channels of your mind ever open for new causes. Remember: The mind is like a parachute; it functions only when open. Doctors cut, burn, dismember and torture the sick, and then demand of them an undeserved fee for such services.

Fig. 1.8. Learn to Work with the Causes of Disease

Take Charge of your Health

True understanding dispels fear. When we understand health and disease, in its whole form, we can no longer place the blame for our ill-health on the lowly germ or bacteria. We then look within for the answers to build our health force. No sane person wants to be ill; we all desire to be healthy and vibrant. It is tragic to witness loved ones in pain and suffering. Unfortunately, too few people understand or adhere to the natural laws that govern health and life. The ancients referred to sowing and reaping as karma or cause and effect. One may sow (cause) good karma by adhering diligently to the habits that create health. Conversely, one may also sow (cause) illness by ignoring the habits of natural health.

We can be the director of our destiny, captain of our soul and builder of our health if we pursue and practice the upward path as laid down thousands of years ago by the ancient masters. We recognize that the future of medicine is in prevention. Our idea is to give good nutritional and other advice so that people can keep themselves well and alive.

Chapter 2

Yin and Yang Principle

Force of the Universe

In ancient times human beings lived to over the age of a hundred. In our time, we are exhausted at the age of fifty. This is because of changes in circumstances, or is it that mankind is becoming negligent of the laws of nature.

Also in ancient times there were the so-called Spiritual Men: they mastered the Universe and controlled Yin and Yang. They breathed the essence of life (Cosmic Dust Particules), they were independent in preserving their spirit, and their muscles and flesh remained unchanged. Therefore they could enjoy a long life, just as there is no end for Heaven and Earth. All this was the result of their life In accordance with the Tao, the Right Way of Yin and Yang. This coming from profound statements were written some 5,000 years ago in the Huang Ti Nei Ching Su Wen (Yellow Emperor's Classic of Chinese Medicine), an ancient Chinese manuscripts on the subjects of health, healing and medicine.

The Oneness (Wu Chi) split and becomes two. These two are the poles and energies of yin and yang. They emerge continuously from this point within the expanse of infinity as a result of the endless movement within the primal sea. By their combination and interplay, the yin and the yang give rise to all the forms that inhabit the world of the relative universe. Thus, all antagonistic-complementary dualisms of the phenomenal world are but the two faces of the front and the back of one ultimate reality.

The secrets of health, life and longevity have been known and passed down from generation to generation by the ancient sages and wise men throughout history. The universal laws of Yin and Yang were formulated by the masters of the mysterious East. They observed all physical phenomena on earth as being duel in nature; that is, for every force, object or occurrence, there exists its opposite polarity.

Chapter IV

General Healing Session

The General Healing session practices are to be done with every student regardless of their age or health condition. These are for cleaning and strengthening the cells. Cells must be clean and strong to heal. The General Healing practices listed steps A-K are the most important part you must always do in every session. You can do this with one person or with many people at the same time. The following is a detailed decription of each of these steps. Become familar with them and they will flow easily one into the other.

A. Three Minds into One Mind

Smile down to the inner universe. Activate the heart consciousness and empty the mind and heart down to the LowerTan Tien, the Abdominal Brain. Gather the 'Yi' (mind-eye-heart power), combining three minds into one. Fill the Tan Tien with this Chi. Start to spiral. You are then ready to connect to the higher forces of Universal and Heavenly Chi. The Three Minds are the Upper, Middle and Lower, or three Tan Tiens. The Upper Mind is the one we have been closely related to most of our lives. It is the logical thinking, planning, calculating and worrying mind; it consumes 80% of our body's energy.
The key is to learn 'to releas the mind' by learning to sink the Chi to the Lower Tan Tien, whereby it can be used in synergy with the other two.

B. Activate the Six Directions

Activating the six directions is for opening the whole body, mind and soul to all of the Universal and Cosmic forces in all directions. We literally learn to draw in the Universal and Cosmic forces from all directions at the same time. This is important for healers so they are not using their own energy for healing but drawing on the limitless Universal forces.

Expand your awareness to connect to the universe and the Six Directions at the mideyebrow and crown; left, right, front, behind, above and below. Connect to the universe, collect and spiral the energy into your Lower Tan Tien.

C. Activate the Three Fires

Activate the Tan Tien, Kidney and Heart Fires to create a Sacred Fire Triangle. Move from the Tan Tien to the Heart, the Heart to the Kidneys and the Kidneys back to the Tan Tien.



Fig.2.1. Yin and Yang Principle (Cold & Hot)

In the food category, grains, eggs, meat, cooked foods are Yang; and fruits, vegetables, raw foods and juices are Yin. Yin is a centrifugal force in nature (cold, expansive, negative pole, alkaline, etc.). Yang is a centripetal force in nature (hot, contractive, positive pole and acid etc.).

The principles of Yin and Yang is not a fabricated theory or fad dietary practice of recent origin. The conception of Yin and Yang began with the conception of the universe and our physical world. It is the law of polarity or the law of opposites. Nothing exists except in relation to its opposites. To understand electricity, one must learn how to use positive and negative fields.

Yang is positive. Yin is negative. We would not know darkness (Yin) without light (Yang); heat (Yang), without cold (Yin); male (Yang), without female (Yin); hardness (Yang), without softness (Yin); and life (Yang), without death [Yin).

Although the forces of Yin and Yang are dual in nature, they proceed from, and are directed by one unifying force in the universe, known by various names such as God, the Tao, Brahmin, etc. It is a dualistic force emanating from one all-preyading power. There is only one presence and one power; and from that Supreme Power the relative duality of Yin and Yang flow.

The Yin and Yang Principle is relative in this constantly changing world. Nothing forever remains the same. No phenomena is purely Yin or purely Yang. Yin and Yang flow into each other like night and day, or inhaling and exhaling.

Eight Strands of the Brocade

History shows that the Chinese may have been direct descendants from the ancient sunken continents of Lumuria and Atlantis dating back some 12,000 to 25,000 years ago. The Chinese Taoists received the knowledge of the Yin and Yang Principle even before recorded history, stretching far back into antiquity. The Taoists sages teach us that the Principles of Yin and Yang have been passed down by highly spiritual beings called "Sons of Reflected Light" ages ago.

The Sons of Reflected Light brought to China the healing arts, known as the "Eight Strands of the Brocade", which consisted of eight principals of health as follows:

1. Diagnosis
2. Yin/Yang Diet and Exercise
3. Herbal Therapy
4. Hydrotherapy
5. Acupuncture
6. Acupressure
7. Massage
8. Meditation or the Way of Occulsion



Fig.2.2. Yang within Yin & Yin within Yang

Taoist Principles of Life within Yin and Yang

1. All Phenomena exist within Infinite Space.
2. All Phenomena are Interrelated.
3. All Phenomena are Relative.
4. Everything has Energy or Vibration.
5. Everything is in a Constant State of Change.

Unique Taoist Principles of Yin and Yang

Seven Principles of the Order of the Universe

1. All things are differentiated apparatus of One infinity.
2. Everything changes.
3. All antagonisms are complimentary.
4. There is nothing identical.
5. What has a front has a back.
6. The bigger the front, the bigger the back.
7. What has a beginning has an end.

Twelve Theorems of the Unifying Principle

1. One infinity differentiates itself into Yin and Yang which are the poles that come into operation when the infinite centrifugally arrives at the geometric point of bifurcation.
2. Yin and Yang result continuously from the infinite centrifugality.
3. Yin is centrifugal. Yang is centripetal. Yin and Yang together produce energy and all phenomena.
4. Yin attracts Yang. Yang attracts Yin.
5. Yin repels Yang. Yang repels Yin.
6. The force of attraction and repulsion is proportional to the difference of the Yin and Yang components. Yin and Yang combined in varying proportion produce energy and all phenomena.
7. All phenomena are ephemeral, constantly changing their constitution of Yin and Yang components.
8. Nothing is solely Yin or solely Yang. Everything involves polarity.
9. There is nothing neuter. Either Yin or Yang is in excess in every occurrence.
10. Large Yin attracts small Yang. Large Yang attracts small Yin.
11. At the extremes, Yin produces Yang and Yang produces Yin.
12. All physical forms and objects are Yang at the center and Yin at the surface.

Yin and Yang create Physical Change

Change in the physical realm is inevitable; it manifests itself in a dual nature Yin and Yang which is opposite yet complimentary. Neither one is absolute and the interplay between them is a constant giving and taking, like the ebb and flow of the ocean tides acting and reacting, day flowing into night, summer (Yang) slowly giving way to winter (Yin). Yin and Yang are created by the Universal Force, the Tao, which is without duality. Although Yin and Yang operate apart in outward phenomena, they are one within their natural core.

According to the Nei Ching:

"The Canon of Medicine provides us with many examples of this interchange between Yin and Yang and of the duality preserved within a single thing. The most concrete example of this duality Is man. As a male, man belongs to Yang; as a female, man belongs to Yin. Yet both, male and female, are products of two primary elements, hence both qualities are contained in both sexes. The Principle of Yin and Yang Is the basis of the entire universe. It Is the principle of everything in creation. It brings about the transformation to parenthood; it is the root and source of life and death. Heaven was created by an accumulation of Yang; the Earth was created by an accumulation of Yin. The ways of Yin and Yang are to the left and to the right. Water and fire are the symbols of Yin and Yang. Yin and Yang are the source of power and the beginning of everything in creation (Alpha and Omega). Yang ascends to Heaven; Yin descends to Earth. Hence the universe (Heaven and Earth) represents motion and rest, controlled by the wisdom of nature. Nature grants the power to beget and to grow, to harvest and to store, to finish and to begin anew.

Yin and Yang in Health and Longevity

Nei Ching continues:

"Everything in creation is covered by Heaven and supported by the Earth. When nothing has as yet come forth the Earth is called: the place where Yin dwells. It is also known as the Yin within the Yin. Yang supplies that which is upright, while Yin acts as a ruler of Yang. The affinity of Yin and Yang to each other was held to have a decisive influence upon man's health. Perfect harmony between the two primogenlal elements meant health; disharmony or undue preponderance of one element brought disease and death. But man is not helpessly exposed to the whims of Yin and Yang. Man had received the doctrine of the Tao as a means of maintaining perfect balance and to secure for himself health and long life.“

The Tao as used in this book does not represent the masculine or father image. It refers here to the Supreme Creative Force of the universe. The Tao is also referred to as the one, that creates the Yin and Yang, negative and positive, centrifugal and centripetal, alkaline and acid, electron and proton and the polar opposites which manifest on the physical plane, earth. Yin and Yang is the physical reality of the One Spiritual Force. Male/Yang and female/Yin are also physical opposites of the One Creative Universal Force. The I Ching states:

“The Yang and the Yin of the Universe are called Tao. This knowledge of the Tao and of the workings of Yin and Yang was considered even strong enough to counteract the effect of age”.

Thus, we find it said in the Nei Ching: “Those who have the true wisdom remain strong, while those who have no wisdom grow old and feeble. The official view of the Chinese Government regarding Yin and Yang states that it ‘contains an original, spontaneously dialectical, and simple materialistic doctrine; it is free of superstition; it approximates scientific formulation; and it represents a progressive way of thinking.

Nature of Yin and Yang

The nature of health and diet is intimately connected and interrelated to the universal laws and operations of Yin and Yang; it is an inescapable principle of life; a duality stemming from infinity itself and manefesting in the physical world of polar opposites.

With this understanding we need to know how can we personally use the laws of Yin and Yang in our daily lives and how can it affect our diet, health and mental make-up. The Ancient Mystery Schools teach what we have not been taught in our modern schools. The following general list of Yin and Yang classifications and attributes will help one to understand what the ancients taught and clarify one’s thinking on this most vast subject. Remember: The Yin and Yang Principle is the Law of Opposites in the Physical Realm. Study this chapter and subsequent ones to thoroughly acquaint yourself with the infinite variety and characteristics of Yin and Yang that abound in our midst.

Yin and Yang Characteristics

Yin	*(Its Opposite)*	*Yang*
Alkaline		*Acid*
Centrifugal		*Centripetal*
Negative		*Positive*
Potassium		*Sodium*
Cold		*Hot*
Moon		*Sun*
Water		*Fire*
Dark		*Light*
Night		*Day*
Moist		*Dry*
Fall & Winter		*Spring & Summer*
Female		*Male*
Rest		*Activity*
Vegetable		*Animal*
Expansion		*Contraction*
Outward Tendency		*Inward Tendency*
Narrow		*Wide*
Space		*Time*
Purple		*Red*
Soft		*Hard*
Mental		*Physical*
Periphery		*Center*
Earths Surface		*Earths Center*
Raw Food		*Cooked Food*
West & North		*East & South*
Sour, Sweet, Spicy		*Salty, Bitter*
Tall		*Short*
Slow		*Fast*
Passive		*Active*
Weak		*Strong*
Chronic Disease		*Acute Disease*
Even Numbers		*Odd Numbers*
Parasympathetic Nervous		*Sympathetic Nervous*
Catabolism		*Anabolism*
Fruitarian		*Carnivore*
Electron		*Proton*
Abdomen		*Back*

Yin	*(Its Opposite)*	*Yang*
Yin Organs		*Yang Organs*
Hollow		*Dense*
Absorption		*Blood Filled*
Discharge		*Regulators*
Store Energy		*Transport Energy*
Gall Bladder		*Liver*
Small Intestine		*Heart*
Stomach		*Spleen/Pancreas*
Large Intestine		*Lung*
Bladder		*Kidney*

Yin and Yang in Food & Environment

By studying and understanding the Yin and Yang foods and weather conditions we can know what to eat, how to eat, when to eat and how much to eat at any given time of the day or year.

Hot (Yang) climates produce expanded (Yin) fruits, vegetables, flowers and plants, with the aid of much rain which is Yin and expansive. This climate produces food that is large, watery, sweeter, with an abundance of the potassium element. These are cooling (Yin) foods eaten in Hot (Yang) weather. So, if you are down south or in the tropics, the natural tendency is to consume more of the Yin foods grown in that climate. These foods are also considered base forming or alkaline elements. The blood must maintain a slightly alkaline condition, 7.8 on the pH scale. If the blood becomes positively acid, one would die immediately.

Cold (Yin) climates produces more contracted (Yang) foods such as smaller grains, vegetables and fruits with less liquid within them. Cold climates require more warming foods in the diet, such as cooked grains, soups, bread, and other cooked foods. Foods grown in Northern climates contain an abundance of the sodium element (Yang), which is necessary to keep our body warm and contracted during the cold winter months. Yin juicy fruits and vegetables are also Alkaline. Yang foods, such as grains, eggs and meat are considered Acid forming. The key is to balance the Yin and Yang and the Acid/Alkaline in the diet.

Generally, eat more Yang foods during the Cold (Yin) winter, about 60 to 85 percent Yang and 10 to 30 percent Yin foods and reverse in summer.

In balancing the diet, one must learn to listen to that small inner voice within; or body intelligence, which instinctively instructs us as to the proper choice of foods in the varied environments. If one can tune-in to their true bodily needs, Yin and Yang balance can easily be achieved, resulting in superior health.

Yin is considered anything that grows large and fast in a short period of time. Any substance, for example, drugs, marijuana, medicine, sugar, alcohol are extremely Yin (expansive) and they tend to dissipate and expand the cells and tissues of the body and brain causing light-headedness or a spaced out feeling and lack of judgment.

Since Yin is centrifugal and expanding outward, it requires a great deal of Yang binding and contracting force to equalize the extreme expansion caused by excessive Yin foods and Ying mind-expanding substances.

Salt, time, heat and pressure create Yang conditions in nature and in food preparation. Salt preserves food and in the body it contracts (Yang) the cells and keeps them from expanding. Yang foods counteract Yin (expansion). We all need a balance of both Yin and Yang to maintain a healthy body chemistry.

Sun, heat and activity are Yang. The Moon, cold and rest are Yin. The sun and heat bring on summer outdoor activity. The air is magnetic and charged with Yang elements, which produce Yin summer fruits and vegetables. Cold weather is Yin, passive, tending toward indoor activity; it produces more Yang root, dense vegetables and grains, and smaller Yang fruits or none at all, as in the Arctic.

We are living in a universe of positive (Yang) and negative (Yin) magnetic energy fields, which continually vibrate at tremendous speeds and produce magnetic currents. These magnetic currents register on our brain in a color spectrum visible to the eye. The ultraviolet rays of the spectrum are Yin; and the infrared rays are Yang. From Yin to Yang in this order: violet, indigo, blue, green, yellow, brown, orange, and red.

Eat According to Seasons

The influence of food, climate and environment affects and intimately binds mankind to the inescapable natural laws of Yin and Yang. Cold weather creates an inner biologic need for warmth, fire and Yang foods. Hot or warm weather creates an inner biologic Yin need for Yin foods, which are cooling and refreshing, such as, more water, juicy fruits and vegetables.

An excessive consumption of cook Yang foods eaten in Yang hot weather overheats the body, blood and internal organs, resulting in extra heart beats, a rise in blood pressure, profuse sweating and fatigue. An excessive consumption of raw fruits, juices, liquids or raw vegetables eaten in Yin cold climates will automatically lower ones blood pressure, (due to expansion of vessels) thinning the blood, causing cold hands and feet and weakening the heart and circulatory system.

As the old saying goes, we are what we eat. The changing weather conditions can affect us in a detrimental way if we do not learn how to acclimate ourselves to the changing environment. Just as the weather changes, so must our diet change to meet the demands made upon it. If one lives in hot climates, less Yang foods should be eaten, including a moderate use of raw fruits and vegetables. To balance body chemistry in northern climates, eat more Yang quality grains, beans, seaweed, soups, stews, and less of the Yin fruits and vegetables.

In the food category, eggs, meat protein (lean part), salt and fish are extreme Yang foods; while all grains, legumes, peas, and seaweed are more balanced and healthfully Yang foods. Extreme Yin foods are sugar, alcohol, cow milk, ice cream, tropical fruits, drugs etc. (Refer to Yin and Yang food chart in another chapter). Balanced and healthy Yin foods are; apples, plums, peaches, pumpkin, most vegetables, most seeds and nuts etc.

Yin and Yang Scale



From Yin to Yang in this order:

1. **Drugs**
2. **Sugar**
3. **Oil**
4. **Cow Cheese**
5. **Ice Cream**
6. **Tropical Fruit**
7. **Fruit Juice**
8. **Baker's Yeast**
9. **Honey**
10. ***Fruit (In Season)**
11. ***Water**
12. **Nuts & Seeds**
13. **Nutritional Yeast**
14. ***Sea Vegetables**
15. ***Land Vegetables**
16. ***Beans**
17. ***Grains**
18. **Chicken**
19. **Fish**
20. **Miso**
21. **Lean Meat**
22. **Egg**
23. **Sea Salt**

*Staple foods to be used daily in season.

Fig.2.3. Yin and Yang Food Scale

Time, heat and salt will turn Yin vegetables more Yang. Cooked and salted Yang foods become more Yang. Raw eggs are not as Yang as cooked ones. Raw apples are more Yin than cooked ones. Sprouted grains are Yin; cooked and salted grains are more Yang. Dehydration yangizes food. Fats in meat, whole cow cheese, whole milk, cream cheese and ice cream are extremely Yin due to their high fat content. Foods should comprise the main part of ones diet. Consume miso, cold pressed vegetables oils and sea salt during cold weather to maintain internal balance and body warmth.

D. Linking Personal Stars, Energy Bodies and the Universe

World Link is a way for intelligent life force to return to the source; inwards and upwards. Become aware of the 'personal stars' above the crown and below the earth.We link with our own personal stars and then with the stars of each person in a group. This links the energy bodies of everyone in a group together. Start to spiral your energy and connect to other peoples' stars and energy bodies. Make a left spiraling pattern, progressing around the circle in a clockwise rotation. Link all of these stars together and form ***one large energy body.*** Each meditator will become an individual unit in an integrated communication link. A link between the earth and the universe.

E. Protective Circle and Chi Field

We create Chi Fields, Protective Animals and call the Eight Forces to protect the group from disturbances and psychic attacks. Raise your right (or leading) hand in the air and access the **'Sacred Fire'** of the universal cauldron. "Feel your fingers becoming big, long and hollow", as they reach into the Sacred Fire. The Chi will fill and pack your arm as you bring it down into your body. Use Yi-Power to create the **Sacred Fire Protective Circle.** The fire will purify and protect the circle. You can cast a circle around your community, house, room and body. This will create an energetic field of Chi around the whole room.

Then Create a **Chi Dome**. Invoke the 'guardian animals'; Blue Tortoise from the north, Red Pheasant from the south, Green Dragon from the east, White Tiger from the west, Yellow Phoenix from above and Black Tortoise from below.

Finally, activate the **Eight Elemental Forces of Nature and the Universe**. Call the forces of fire, water (ocean), thunder (lightning), lake (rain), earth, mountain, wind and heaven. Activate fire in the north, water in the south, lightning in the east, and rain in the west.

F. Chi (Sacred) Water Practice

Invoke the power of the Sacred, Chi or Holy Water practice to cleanse and heal the body's sick, toxic or negative energy. Make a request to receive healing energy and feel yourself touch a heavenly pool of sacred water energy. Feel the pool pouring down heavenly water to fill your arm.

Use the thumb and index finger to remove the sick energy from the cup, without touching the water. Talk to the sick cells. Let the sick energy return to the earth for recycling. Fill the water with your heart's compassion. Give the command: "This Sacred Water will give health, wealth and longevity". Cosmic Healing works on a cellular level. It is the water's 'job' to carry the message of the practice to all the cells, where it will remain. Drink the water in unison with the rest of the group.

It takes wisdom and intelligence to understand and apply the universal laws of Yin and Yang. The more it is applied, the more one is guided in life by the Tao. The ultimate key to this unifying principle is very simple. Moderation or adhering to the middle path in life and avoiding extremes in activity will automatically create a Yin and Yang balance, leading to harmony in body, happiness in mind and soul and success in life.



Fig.2.4. Yang Contracting & Force Yin Expending Force

Contracting centripetal force from the upper atmosphere toward the center of the earth produces the Yang-Male organism. Expending centrifugal forces from the center of the earth upwards, produces the Yin-Female organism.

Cosmic Energy Vortex

A clairvoyant's picture of the heart of the universe; the ultimate physical atom seen as a manifestation of pure light force spinning perpetually through itself interacting in the opposites of Yin and Yang.



Fig.2.5. Yin & Yang Cosmic Energy Vortex

Yin and Yang

From the interaction of the Subtle Origin in the Mysterious Mother and the balanced energy of Yin and Yang, all phenomena of life came forth. Yang energy is subtle and spiritual. It is positive and has action as its nature. Yin is coarse and physical and is referred to as earth. It is negative and receptiveness is its nature. Both energies are equal and support each other in perfect harmony.

Under the Law of Great Transformation, the energies are constantly changing, never static. Their movement in change is constant. Therefore, the future of a person has several possibilities, but nothing is certain, until the person makes it so.



Fig.2.6. Yin & Yang Life's Spiral

Lifes Spiral Unfolds

1. Infinity (Wu Chi), the Tao.
2. Yin and Yang - Relative World begins.
3. Energy, Emotion & Thought - Phenomenal World begins.
4. Fire, Pre-Atom - Material World formed.
5. World of Elements & Minerals is formed.
6. Vegetable Organic World begins.
7. Human Beings and Animal Kingdom begins.

Yin Yang Theory

Taoist Wisdom comes from observation of nature and her laws. By understanding nature's flows we can understand our own internal alchemy and also the dynamics of the universe. The microcosm reflects the macrocosm. The Taoist creation story is that Oneness, or Wu Chi, the source of all, manifests into this life of duality that we observe. Nature is a perfect manifestation of Wu Chi, and so we can learn a lot about life from observing, understanding and living according to nature's laws.

One of the first aspects of nature we can observe is duality: the existence of apparent opposites. For example, we see night and day; we can feel the difference between winter and summer; we experience both light and dark; we can feel warmth and coldness. These apparent opposites are not separate from one another, but are the same energy at different stages of a cycle. Thus we can observe the seasonal cycle taking us from the coldest part of winter through to the warmest part of summer and back again.

The Taoist s called these apparent opposites Yin and Yang. As a way of reminding us how they are not separate entities, but in continuous flow, they created a symbol called the Tai Chi, which shows this flow in its spiralling and dynamic nature. One dot of black appears on the white half and a white dot in the black half. This symbolises how even when we reach extreme Yang, there is Yin within in it, and vice versa.



Fig.2.7. Yin & Yang Opposites of the Universal

Yin

This describes the feminine principle of life and energy in its most contracted form. Winter, night time and dark moon are all examples of energy at its most contracted. In winter we feel to stay in more (we contract socially). At night time we sleep (we contract our activity levels). At dark moon we become introspective (we contract psychologically). When energy contracts it becomes solid: thus all things manifest and solid are described as Yin: the body, the blood, the earth etc.

Yang

This describes the masculine principle of life and energy in its most expanded form. Summer, day time and full moon are all examples of energy at its most expanded. In summer we feel lively and sociable. During the day time we are at our most active. At full moon we feel more inclined to go out and connect with others. When energy expands it becomes more intangible (just as when water is heated it becomes a gas). Thus all things that are less solid are described as Yang: the spirit, the chi, heaven etc.

Yang within Yin

As previously mentioned, the dot of white within the black is there to tell us that extreme Yin contains the seed of Yang, and vice versa. This part of the theory is often hard for people to understand. Once again, looking to Nature can help us to grasp this. In the middle of winter it is hard to see the seed of summer! Yet after mid-winter (Winter Solstice, December 21st) the days begin to get longer each day. This is the seed of summer.

We may describe a big crowd as Yang and a vast empty space in Nature as Yin. The crowd is sociable, the space is unsociable. And yet we can feel extremely lonely in the midst of a crowd. We can feel connected to the entire universe when we are alone in a vast part of Nature. This is another example of Yin within Yang (lonely in a crowd) and Yang within Yin (connected to all in vast space).

Because each opposite contains the seed of the other, when we push to an extreme, we find we suddenly shift to the opposite. Thus if we push something to extreme Yang, it will become Yin, and vice versa.

For example, when we are cold, we contract and become still; we can describe as Yin. In the summer we feel more flexible and active; described as Yang. But in extreme cold we begin to shiver, moving very, very fast extreme Yin has become Yang, in the hottest part of a hot summer we may simply lie motionless under a tree. Yang has turned to Yin.

Another example of the extremes is when we become a workaholic and work excessively hard (Yang), we may suddenly have a breakdown and develop fatigue (Yin). Likewise, people who are forced into a Yin state of not being able to be active, such as being confined into a small space, become very restless (Yang).

Yin and Yang

We can compare opposite pairs as Yin and Yang. However, it is important to remember that these opposites are not separate: they are one entity at different stages of its cycle, or Oneness reflected as two.

Yin	*Yang*
Night	*Day*
Winter	*Summer*
Dark Moon	*Full Moon*
Dark	*Light*
Introvert	*Extrovert*
Intuition	*Analysis*
Rest	*Activity*
Feminine	*Masculine*
Body	*Spirit*
Material	*Immaterial*
Contracted	*Expanded*

There can be a tendency to try to perceive Yin and Yang as being separate when we try to understand oriental theory through the dualistic modern mind: this leads automatically to judgment. We may try to choose between Yin and Yang, almost subconsciously, to decide which one is good and which one is bad. Our cultural bias tends to be towards labeling all Yin aspects as bad and Yang as good. The whole purpose of the Tao path is to transcend dualistic thought and to recognize that all of life is indeed One. Therefore, we need to be careful not to make judgments, but see how apparent opposites are simply different stages of the cycle, or reflections of the whole.

By observing Nature, we can begin to eliminate such judgements. When one has developed a deep relationship with Nature, one cannot choose between winter and summer or between sunset and sunrise. Rather we begin to embrace all and see it as one cycle that has different stages, Nature can teach us how to live in a harmonious way. Nature has no resistances to what is: the tree does not try to hold onto its leaves when autumn comes; the rock does not fight the ocean waves that break against it, but gently wears away. Thus we can learn to accept what is, and yet to walk our path: the path is The Way; it is the Tao.

Chapter 3

Great Physician Within

Fasting is Natural

The phenomenon of fasting is probably the least understood and the most abused health measure that has ever been used in the history of man. Understood and used with the proper knowledge of its processes, it is life saving and health promoting. Misunderstood and abused without thorough knowledge of its principles, it can be disease producing and death dealing.

To set the record straight, fasting or abstinence from food is an intimate part or process of every breathing life form, either plant or animal, (including human) that has ever existed since the beginning of Creation.

Just as we must all rest, mentally and physically from our daily activities, and give our bodies a chance to recharge its batteries through sleep, so must we allow our digestive and eliminative organs a rest (fast) from all food for the purpose of cleansing, purifying and revitalizing worn out cells, tissues, blood and all physiological functions.

There is nothing, mysterious, or occult about fasting. Although fasting has been used in various religious cults throughout history, it has not been generally recognized for its true value in the scientific care of the sick, the maintenance of health and the extension of life.

The word occult means secret. Fasting is an occult mystery only to those who have not taken the time to study it. And it will continue to be a mystery to all those who condemn it without first giving it a thorough investigation and fair trial.

A great sage once said: Condemnation before investigation, is the greatest bar to all knowledge. Let us not condemn the natural process of fasting, for it has been proven through scientific research and testing to be of true value in all states of health and disease. Abstinence is one of the best of all remedies and alone cures with out danger. Instead of using medicines, rather fast a day. Fasting is the royal road to internal purity.



Fig. 3.1. Great Healing Physician Within

Fasting Defined

Fasting is defined as a complete and total abstinence from all food, including juices, for a shorter or longer period of time for any number of purposes, i.e., illness, weight loss, etc.

It can be said that we all fast or abstain from all food during sleep and we customarily break-the-fast with the morning breakfast.

Everyone fasts in rest or sleep whether he knows it or not. Continual eating without periods of fasting would cause internal toxemia or food poisoning. However, nature dearly cares for us by taking away our hunger after a certain amount of food is consumed. It is a built-in safety valve, otherwise we would all die from gluttony.

Any food eaten in excess of bodily needs and natural hunger will cause a toxic overload in the system of undigested waste products (toxemia) within the cells and tissues. This in turn overworks the body's eliminative organs.

We can now detect the first state of the disease process; overworked organs of elimination, followed by toxemia or poisoned blood, and ending with pathology, disease and an early grave.

Fasting allows the eliminative organs to catch up on their work. The body is always striving to maintain a balance, and when it is given a physiologic rest, (fast), it will carry out its prime objective without the aid of drugs, medicines, or any other unnatural cures.

The cure of disease lies in preventing the cause of disease. There is no disease without a cause, and the causes are many, i.e., overeating wrong foods, alcohol, smoking, worry, fear, hate, overwork, lack of exercise, sunshine, rest and sleep.

Fear of Fasting or Starving

Fasting has been feared by many people, due to misinformation and fear tactics by the press, radio, and T.V., including the unwillingness or ignorance of the medical authorities to investigate and reveal the truth of the matter to the people.

The press has run articles telling of plane crash victims and survivors of other natural disasters, in which they survived for many days or weeks without food and medical help. Subsisting almost entirely on water, they come out of it with improved health, and freedom from previous disease conditions. These cases definitely substantiate the claim that the human body is inherently capable of surviving under adverse situations with no ill or adverse effects.

Hospital authorities believe that a patient will starve to death if not fed three square meals a day of the conventional over-cooked fare. Those who are supposed to know about our health and welfare are completely ignorant about the distinction between fasting and starving. Fasting and starvation are two completely different conditions. The first is beneficial and rejuvenating; the latter is destructive and death-dealing. Starvation begins where fasting leaves off.

Fasting is a process whereby the body exists on its stored reserves of fat, protein and minerals, until they are used up or exhausted. Then it is time to break the fast. To go beyond this point is starvation. Fasting does not use up the vital tissues or organs.

Starvation is a state or condition that goes beyond the stored reserves of fasting. It is a pathological skeletal condition which ends in death. Countless people have fasted with or without supervision for a variety of reasons from a few days to many weeks. The results of these fasts have been proven to be of utmost value in achieving superior health. There is no question but that scientific fasting eliminates the bodily poisons, adipose tissue, and breaks down destructive cells. If carried out properly and scientifically, the fast is a means of acquiring complete rejuvenation and vigorous, robust health.

Experimental and Scientific Fasting

It is unfortunate for the American people that the medical society, refuses to acknowledge, recognize, or teach the value of fasting as a natural form of correct care in sickness.

In European countries, fasting, juice diets and other natural therapeutic measures, are used by their best doctors in clinics and sanitariums. One such well-known clinic is the Buchinger Sanitarium in Bad Pyrmont, Germany, where over 70,000 fasts or juice fasts were conducted. In Australia, Dr. Alec Burton has conducted thousands of fasts at his Natural Hygiene resort for many years. In this country, Dr. H. M. Shelton has personally supervised over 30,000 fasts in his 50 years of practice in Texas. In Sweden, in the year of 1954 and again in 1964, Dr. Lennart Edren led a 300 mile walkathon while fasting. A total of 30 people started and finished the walk with no ill effects. All medical tests on the fast-walkers proved to be positive, with no adverse side effects. This experiment clearly proves that man is able to fast even under strenuous physical exertion.

Dr. Shelton writes about some interesting cases of feats of strength while fasting in Volume III of the Hygienic System, Chapter XVI. He states that Bernarn Macfadden, the Father of Physical Culture, held a fasting and strength contest in Madison Square Garden in 1903. After a 7 day fast, J. H. Waltering captured 1st place by winning the 50 yard dash in 6 minutes. A 6 minute mile in 1903 was considered quite fast at that time.

Even more fantastic was Mr. Gilman Low, a weight-lifter from Boston. In 15 seconds he lifted 500 lbs., 20 times, and in 20 seconds 900 lbs. twice. On the 7th day of his fast, he lifted in 19 seconds, 1 ton 22 times. All of this was closely observed by medical

G. Empty and Fill

The Empty and Fill technique is emptying the sick energy into the earth and filling with healing Cosmic Force Energy. Project your 'sword' hand (middle and index fingers) down to the ground. Project the hand 'very big and very long' and your feet 'very big and very long' - extended down to the ground. Now very slowly inhale, bring up the earth energy. Bring the energy up to your feet and into your bones. Let it enter all the bones, organs and cells. Feel it blending with all the sick energy. Turn your palm up, turn it back down again and exhale; let go of all the sick energy, the negative energy, the worries and burdens, all the way down into the earth. Repeat this three to nine times. Dig a hole and bury all the sick energy; tell it, "Do not come back; you will be happy down there." Smile.

H. Clean with Green Light

The Green light is for cleaning the cells. This is vitally important because the cells must be clean for healing. Green can help detoxify the toxic cells. Green Chi is mild and safe. Green Chi is used for cleansing, and as a decongestant for diseased parts. It 'loosens' the area. The light green Chi is used to break down dirty or diseased energy, like a detergent is used for washing clothes or dishes.

Afterwards, the cells will be rinsed with blue light, like clean water is used to rinse the detergent and residue from clothes or dishes.

When you carry out healing try to 'see' the cells enlarged and this green energy go in and blend with the dirty, black and cloudy energy. See it come out and let it go down to the earth. Dig a hole and bury it there. Tell it, "Don't come back. You will be happy down there". Become aware of the green light and spiral counter clockwise. Spiral down. Cleaning out the stress. Repeat as many times as you like, three times minimum.

I. Clean with Blue Light

Blue is like cold water; it has the yin power to dissolve all kinds of negative energy and sickness. It has an inhibiting effect. Blue yin energy is the opposite of red yang, which has a strengthening and stimulating effect.

Blue has a cooling effect; it can reduce pain and inflammation, and it can help blood clot. It stops bleeding and reduces fever. It can help to induce rest and sleep.

J. Charge with Violet Light

Charging with Violet light holds the highest healing energy. When the cells are clean they will absorb and hold the Violet light and the healing will take place. Luminous Violet has intelligence and can be programmed. The universe is full of violet light, especially the North Star and the Big Dipper. The color of the star of the higher self or soul, above the crown, is also violet. It is the color of Divine or Soul energy.

doctors. Mr. Low asserted that after a 15 day fast previously, he could have whipped his weight in wildcats. These feats were accomplished after 7 days without a bit of food.

Does this indicate a state of starvation, weakness or death? No. It simply means that the human body has a tremendous storehouse of reserve food material by which it sustains itself during periods of fasting or food shortage.

Dick Gregory, the famous black comedian, writer, and author of many books, one being on Natural Health and Vegetarian Nutrition, has undergone many fasts while engaged in long distance running (15 miles) non-stop.

We have personally gone on extended water fasts up to 2-4 weeks, and on watery fruit diets for up to 48 days, thus regaining our health and well-being. We do not recommend a fast or fruit diet for this length of time unless under proper supervision, or if you are well-versed in the procedure.

Animals and Fasting

We all can learn a lesson about fasting by observing the habits of wild and domestic animals. Animals will not eat when sick or wounded, but will retreat to a quiet location and rest, drinking only water until well.

It has been observed that some animals will consume a small amount of grass when sick. There is something in the grass and plant life that the animal craves when sick. The green chlorphyll supplies the missing elements or cleansing properties that are needed in sickness.

The household animal will recover of its own accord when left alone. It will let you know when it is ready to eat. It would be well for man to follow the same course of action as do all animals, that is, when sick, diseased or emotionally upset, take a physiological rest; abstain from all food, (fast), rest in bed, keep warm, quiet and drink only pure water as thirst demands until recovered. The humans are the only creature that eats at all hours of the night and day, and continues to do so when sick, diseased and emotionally upset.

They are the only living being that refuses to resort to fasting when sick. In their foolishness they partake of food and imbibes poisonous medications in a futile attempt to restore their sick body to health. Nothing adds to the fires of disease like drug treatment and forced feeding. This procedure has caused much suffering and agony, sending millions of unwary souls to an early grave.

All living organisms, from the one-celled amoeba to human, the highest form of intelligent life on earth are subject to the same Universal Natural Laws of Life and Existence, namely, the inherent qualities of self-healing, self-regeneration and self-rejuvenation.

It has been noted by research scientists that scores of insects and animals abstain from food from a few days to many months during the winter season. The breeding season of numerous lower animals is a period of fasting and resting. The silver salmon fasts for weeks while swimming hundreds of miles upstream to the spawning ground. The queen ant eats nothing until her eggs are hatched, and then the hatched workers finally bring her food. An incredible period of many weeks pass before she is again ready for food. The common earth worm has been kept alive for well over 15 generations in laboratory experiments because of the periodic fasts they underwent. It behooves every medical scientist and nutritional researcher to investigate the truths nature has to offer, and to use her natural principles for the benefit of all humankind.

Fig. 3.2. Fasting is Internal Resting.

Historical Fasting

Let us again remind our medical bretheren that the father of medicine, Hippocrates, recommended fasting in the care of the sick. He said, if a sick person is fed, one feeds the disease. On the other hand, if the sufferer is witheld from food the disease is fasted out.

All nations of antiquity followed the natural principles and methods of fasting and frugal eating as advocated by their great philosophers and sages: Socrates, Plato, Pliny, Senneca, Pythagores, Moses, Jesus, Budda, Mohammed, Galen, Benjamin Franklin, Thomas Edison, and many, many more.

Jesus reportedly fasted 40 days in the mountains, and thereafter could not be tempted by the devil. Likewise, Gandhi subjected himself to fasting and prayer frequently. Moses followed suit; fasted and prayed, and he decended from the mountains a wiser man.

In early Rome, certain drug doctors were not allowed to dispense their concoctions. The great Paracelsus once said that fasting is the greatest, the physician within, that heals us. Confucius, Buddha, Lao Tzu, Christ, Moses, and others fasted for internal purity and illumination.

By following the advice and example of these great men, you too can become disease free. There is nothing to fear, but fear itself, is an old adage that can be applied to the fear of fasting. Fear not for you will be guided by the Spirit of the Great Ones who have also tread the straight and narrow way.

What to Expect while Fasting

The first two or three days of the fast are the most difficult, especially for sick people. Because the faster has, for the first time in his life missed the accustomed stimulating meal. Like a drug addict, the food addict will go through two or three days of withdrawal symptoms. At this point of the fast, the tongue may become coated white and the breath may smell bad. There may be a foul taste in the mouth, and nausea, accompanied by dizziness upon arising, topped off by an empty feeling in the stomach. After three days these symptoms will usually disappear as the body's reserve forces will draw on themselves for nourishment.

These symptoms may also reappear as the fast progresses, as the elimination process continues. Near the end of the fast these unpleasant effects will subside and a feeling of well-being will take their place. It must be understood that the elimination of toxic material thrown out into the blood stream for expulsion is a necessary cleansing process.

If a crisis overtakes you during a fast, do not panic. Here are some crisis symptoms: feverishness or chills, due to toxic material being thrown into the blood stream for elimination; cramps, retention of urine, diarrhea, headaches, and insomnia are some of the temporary eliminative symptoms one may experience before reaching normal physiological balance and high level health. Fasters require plenty of rest, sleep, fresh air, sunshine and freedom from all stress to facilitate internal healing; this especially holds true for those weakened by a debilitating disease.

Many people prefer to drink warm water during a fast, and to place a ginger compress or hot water bottle on the stomach, intestines or bowels to attract blood to the area for healing.

It is amazing how a person’s hunger will vanish after the fifth day of fasting. In fact, the mere mention of food will sometimes cause nausea. As the reserve food supply within the body takes over the job of sustaining the body, other conditions are going on within to maintain a balance, i.e., the pulse rate slows down, the blood pressure decreases, and the stomach secretions are reduce. The eyes become brighter and the hearing becomes more acute. The blood cells increase in number.

As the fast nears completion, the symptoms of elimination will also disappear. The breath smells sweet. The foul taste and nausea are gone. The pulse rate, blood pressure, and temperature return to normal. The stomach secretions and hunger lacking before, now returns in full force. The mouth waters and there is a desire for the simplest of food.

There is a feeling of well-being and a new zest for living. The length of the fast cannot be determined before hand. Each case is unique and every person has different quantities of toxic poisons within them and various degrees of organic constitutional weaknesses. Nature will always indicate how long one should fast. Take it day by day.



Fig. 3.3. Short and Long Fasts in Nature

Long Fasts

Remember, one fast will never completely cleanse the body. It requires from one to three years of periodic fasting and correct eating to obtain a thorough cleansing and return to vibrant health.

One long fast may produce a clean, pink tongue, but this does not necessarily indicate a totally pure and cleansed body. When the tongue has become pink, it either indicates that the body is pure or that its reserve fuel supplies and vital force has been used up for cleansing during that particular fast.

Many times the faster will run out of energy and vitality well before the tongue clears up and becomes pink. In this case, it is imperative to break the fast and resume the feeding. Nothing is ever gained by trying to break records while fasting, at the expense of the recovery ability of the body. Fasting too much and too often can make a nervous wreck out of the strongest willed person, not to mention a sickly one.

Long fasts must be taken only under proper supervision by one who knows the procedure thoroughly. Remember: The sicker the body, the more crisis reaction it will have. Therefore, the necessity to be supervised by a competent health doctor. Most people can withstand a seven to ten day fast without supervision, provided some studying has been done on the subject. Between each fast maintain a well balanced diet, obtain sufficient exercise, sunshine, fresh air, rest and sleep and emotional poise.

Precautions in Fasting:

Fasting is most beneficial in acute diseases, but not in degenerative conditions. Acute disease is a violent or quick release of toxins in the system; it is a sign that the body has enough reserve vital power to discharge and eliminate the internal poisons and heal the organism. Chronic disease is a condition of long standing (degeneration) leaving an individual with weak vital healing power.

Degenerative diseases, such as cancer, diabetes, rheumatoid arthritis, Parkinsons disease, tuberculosis, heart disease and extreme malnutrition (anorexia nervosa), do not readily respond to long fasts. Other natural health and biological therapies are recommended to regain health and balance body and blood chemistry. Some of these therapies include: herbs, acupuncture, vitamin/mineral food supplements, balanced individual dietary measures, color and music therapy, hydrotherapy, corrective exercise movements, shiatsu massage, sunshine, sufficient rest and sleep, harmonious environment, and positive physical and mental conditions.

Dr. John Tilden, an early 1900's fasting physician, advocated only short fasts from 3 to 10 days for certain chronic diseases, and thereafter fed his patients only one meal per day until they recovered. He never advocated long exhausting fasts to completion, as he believed they were too depleting to the nervous system.

Consult a natural health or biologically oriented doctor in your area for a professional evaluation and consultation of your condition.

Reasons for Fasting

Fasting can be undertaken for many reasons:

1. For Body and Blood Cleansing
2. For Colds or Flu
3. When Mentally and Physically Fatigued
4. For Spiritual Development
5. For Rejuvenating Internal Glands and Hormones
6. For Losing Weight
7. To prevent Acute and Chronic Disease
8. To Feel and Look Better
9. To Eat Less and Save Money
10. To Lower Cholesterol Levels and Blood Pressure
11. To overcome Drugs, Smoking, Alcohol etc.
12. To overcome Stress and Sleep Better
13. To improve Digestion and Bowel Movements
14. To increase Mental and Physical Discipline

Addictions to stimulating foods will cause withdrawal symptoms. Stomach rumblings, headaches, nausea, weakness, fatigue, irritability, coated tongue are definite signs that one needs a fast; and afterwards, a change to a more wholesome, natural, non-stimulating dietary. The most sensible health policy one can follow is to eat only when truly hungry, which is indicated when the mouth waters, and there is a zest and relish for natural unstimulating food. If food is not relished at regular mealtimes, skip the meal and fast until true hunger returns.

Breaking a Fast

Extreme care should be taken in breaking a 5 to 10 day fast. The first day after the fast drink 4 ounces of apple or orange juice and 4 ounces of water, mixed; one glass every two hours. The second day eat fresh fruit according to hunger. The third day continue a well balanced diet. It is best to consume the fruit and vegetables grown in the region and climate where you live, i.e., apples, berries, peaches and cherries and winter vegetables in the northern region and oranges, grapefruits and melons in the southern region.



Fig. 3.4. Breaking the Fast

Fasting Recommendations

We do not recommend raw fooders or strict fruitarians to fast for any length of time; what is needed in these cases is a well balanced natural diet. These extreme alkaline diets are already naturally cleansing to the system, but are deficient in many nutrients that are necessary for tissue repair, healing and body-weight maintenance. Any further fasting in these cases will lead to disease and compound the problem.

The ancients teach that it is more beneficial to fast when ill or not hungry; all animals in nature follow this procedure. This is in conformity with the natural flow of life.

Many people attempt to set a scheduled day for fasting; but when their prearranged day arrives, they may find themselves hungry or in no mood to fast. Instead of heeding their inner psychological voice not to fast, they fast anyway. This is not a healthful practice, because the body is not in need or ready for a cleansing at that time; what one requires is wholesome food.

Many health enthusiasts believe the erroneous concept that fasting is a cure all; it is not. Fasting too long and too often, when one is not physiologically ready can lead to nervous exhaustion, anorexia, and may also lead to junk food binging. The former conditions can be fatal.

The best advice is to fast only when necessary, especially when hunger is not present, or when physically or emotionally exhausted. Missing a meal or two occasionally improves digestion, elimination, clears the mind, and increases health and longevity. Fasting in its proper time and need enables one to cleanse, heal and balance the body chemistry in a normal cycle.

Summary of Fasting

To sum up in a condensed version the benefits of fasting, we quote the leading advocate of fasting in America, Dr. H. M. Shelton:

1. Fasting does not cause the stomach to shrink up.
2. Fasting does not cause the walls of the stomach to grow together.
3. Fasting does not cause the digestive fluids of the stomach to turn upon it and digest the stomach.
4. Fasting does not paralyze the bowels.
5. Fasting does not impoverish the blood nor produce anemia.
6. Fasting does not produce acidosis.
7. Fasting does not cause the heart to weaken collapse.
8. Fasting does not produce malnutritional edema.
9. Fasting does not produce tuberculosis nor predispose to its development.
10. Fasting does not reduce resistance to disease.
11. Fasting does not injure the teeth.
12. Fasting does not injure the nervous system.
13. Fasting does not injure any of the vital organs.
14. Fasting does not injure the body's glands.
15. Fasting does not cause abnormal psychism.

On the Positive Side, Fasting does the following:

1. It gives the vital organs a complete rest.
2. It stops the intake of food, which may decompose in the intestines and poison the body.
3. It empties the digestive tract and disposes of putrefactive bacteria.
4. It gives the organs of elimination an opportunity to catch up with their work, and promotes elimination.
5. It reestablishes normal physiological chemistry and normal secretions.
6. It promotes the breaking down and absorption of exudates, deposits, diseased tissues, and abnormal growths.
7. It restores a youthful condition to the cells and tissues, and rejuvenates the body.
8. It permits the conservation and recanalization of energy.
9. It increases the powers of digestion assimilation.
10. It clears and strengthens the mind.
11. It improves function throughout the body.

Rejuvenating Power of Raw Juices

Natural science has rediscovered the regenerating and youthifying properties of raw foods and fasting as passed down throughout the ages from ancient teachings. In the days gone by, man was known to have lived to great ages in perfect health and vitality. Today, the European health clinics are utilizing the principles of this Secret Youth Formula in the form of Therapeutic Juice Fasting, including the use of fresh, raw fruit and vegetable juices, vegetable broths, youth giving herb teas and mineral waters.

Juice Therapy Fasting

In unhealthy, diseased, and acid/Yang conditions raw juice cleansing therapy is a beneficial alternative to the conventional water fast method. Both methods of fasting are useful and will rejuvenate and cleanse the body, however, a juice, vegetable broth and herb program will provide the demineralized and depleted body with the necessary elements as follows:

1. Live raw enzymes, trace mineral elements, vitamins & minerals.
2. Raw juices and broths act as remineralizers. They alkalize, purify and neutralize the acid-toxins and internal waste, as they are poured out into the blood system.

It has properties of other Chi colors. It has a rapid regenerating effect on damaged organs and nerves. Always use green and blue light before using violet. Violet light develops the crown center, the spiritual core. It is good for psychological ailments as well as for physical deficiencies.

K. Activate the Immune and Defense System

The body has various mechanisms which combine to provide protection and defense against illness and disease. These mechanisms enable the body to produce various cells and bodies which act against invading or unwanted substances. As soon as a foreign body is recognized, the immune system will be triggered and will act to provide the most efficient means of eliminating the danger and return the body to a balanced state of health. A strong and healthy body will have good resources to protect itself from negative or sick energy. The aim of these practices is to help you to realize the potential of true harmony within yourself. To activate the immune and defense system is to increase the production of red and white blood cells. To do this we activate the bone marrow and lymphatic system. Guide the student or whole group together in all of these steps. You will not lose energy by doing this. You will gain more energy because you are all connected together in the group power. The crucial part is to multiply your good intentions, Chi and virtue energy into the cosmos, making yourself and each person a direct line from the Universe. After you finish the General Healing session you can tailor the healing techniques in the next chapters to the individual's needs.

3. The blood-sugar level remains close to normal during a raw juice fast, while building up the alkaline reserves to neutralize the excessive acids in the tissues and blood.
4. The vitamins, minerals and enzymes are extremely necessary factors in supplying the life giving elements for the glands, organs, tissues and blood to increase the recovery ability and healing of the entire body.
5. Juices and liquids do not impair or tax the digestive process and are very effortlessly absorbed quickly into the blood stream, cells and tissues.
6. A juice faster does not experience much weakness or low energy lags during or after the fast, as many times occurs on a strict water fast.
7. The recovery rate after the juice fast, in many cases has been proven to be quicker and more stable. The beneficial results of the fast will be enhanced provided the person adopt a natural food & living lifestyle afterwards, as suggested in this book.
8. Raw fresh fruits and vegetables contain highly nutritive solar-energy electricity and enzymes, that operate to preserve and prolong the life of the living cells.

The morality of clean blood ought to be one of the first lessons taught us by our pastors and teachers. The physical is the substratum of the spiritual; and this fact ought to give to the food we eat, and the air we breathe, a transcendent significance.

Eliminative Diet

The Eliminative Diet consists of consuming only raw fruits, vegetables and juices, excluding proteins, fats and starches, and this list also includes the heavier acid forming fruits and vegetables such as, bananas, dates, dried fruits, potatoes, nuts, avocado, etc. Raw fruits, vegetables and juices are easy to digest and assimilate, thus enabling the remaining body energy to expend itself on self-healing and cleansing. If one consumes starch, fat, or protein foods during this cleansing diet, the healing process will be delayed. Heavier Yang/acid foods are more difficult to digest and take longer to be absorbed into the blood stream, therefore they should be avoided during a cleansing period.

The Eliminative Diet is a superb method of cleansing the body of internal impurities. A few days to a week on juicy fruits and vegetables, with sufficient rest, will allow the body to eliminate accumulated waste products, fatty deposits and excess weight. The best time for this type of Yin-Eliminative Diet is during hot summer months. One can expect to lose from 7 to 10 pounds of body weight and fat per week on this diet; it will also normalize blood cholesterol levels and lower high blood pressure.

Fig. 3.5. Cleansing Foods

Eliminative Crisis

Acute and chronic diseases can be attributed to the over-consumption of protein, fat and high-calorie processed starch foods. One should not be too concerned about eating high protein or other acid forming foods; the main concern here is internal cleanliness first, then afterwards a return to a wholesome nutritional program, which includes grains, legumes, vegetables, fruits, seeds and nuts (germinated), sprouts and a moderate amount of low-fat yogurt, buttermilk, cottage cheese (all raw), if you desire it.

During an Eliminative Diet one may experience varying degrees of aches, pains, headaches, diarrhea, dizziness, nausea, etc. Understand: These temporary symptoms are merely a cleansing process which are necessary before a healing can take place within and good health experienced.

These cleansing symptoms indicate that the organism is working to eliminate years of accumulated internal waste products. A crisis resulting from an Eliminative Diet or Fast is a physiologically preventative measure much less painful than the possibility of degenerative or chronic disease years later, i.e., cancer, heart disease, arthritis, etc.

Cleansing Foods

If you are an extremely busy person and do not have the time or inclination to go on a total fast for a few weeks at a Health Spa, then the Eliminative Diet and the Raw Juice Cleansing rejuvenation program is for you. The program consists of consuming only raw fruits and vegetables and their juices, to be eaten at mealtimes or at any other time during the day that you feel hungry. The following Raw Foods are excellent blood cleansers & purifiers.

Grapes
Nectarines
Watermelon
Grapefruit
Cherries
Papaya
Pears
Pineapples
Apples
Raspberries
Blackberries
Persimmons
Praches
Oranges
Plums
Blueberries
Cantaloupe
Tomatoes
Huckleberries
Cucumbers
Honeydew
Apricots (Fresh)
Mulberries
Strawberries

These foods may be used as disinfectors and mucous dissolvers in a salad consisting of tomatoes, cucumbers, green peppers and tender celery.
Onions
Radishes
Garlic
Lemon Juice
Leeks
Cayenne Pepper

The following vegetables are utilized more efficiently to cleanse the cells and tissues, build the blood and purify the internal organs. They must be freshly squeezed in a juice extractor and sipped slowly. Use carrot juice as a base, about five ounces, and add three ounces of any of the vegetables listed here:

Alfalfa
Dandelion
String Bean
Endive
Turnip
Cucumber
Spinach
Brussell Sprouts
Tomato
Cabbage
Lettuce
Squash
Parsley
Swiss Chard
Kale
Watercress
Kelp
Zucchini
Alfalfa
Potato
Asparagus
Sorrell
Beet
Parsnip
Carrot
Green Pepper
Celery

Feel Like a Million

You will be amazed at how much better you will look and feel after a fast or an eliminative diet, maybe even years younger. Without cleansing the body, one cannot possibly attain health. That is how important it is. Never eat when ill, instead rest in bed, drink distilled water when thirsty, have proper ventilation and warmth, and in a few days to a few weeks you will feel like a million.

Fasting and eliminative diets are the greatest means of cleansing the body, says Dr. J. H. Tilden, as it strengthens the nerves, aids digestion and helps to build a powerful organism.

Make up your mind that when your body requires a thorough internal house cleaning, to call on nature's maids in the form of the Water Fast, Raw Juice Cleansing or Eliminative Diet. Remember, your body must be clean before you will experience super health. Do not make a thousand excuses why you cannot begin on a sound health program. Only failures quit. The successful people in life are the ones who follow a truly logical and correct plan of living in harmony with Nature's Laws.

Fig. 3.6. Feel Like a Million in the Tao

Yin and Yang Juices

Yin and Yang refers to the potassium/sodium content of foods and juices. Basically, it involves using the food grown in the climate where you live. For instance, if you live in the North, you will obtain much better results if you consume the fruit and vegetable juices that are grown in that region; apple, pear, plum, berries, cherries, grapes, peaches, melons, carrots, beans (green), squash, celery, green pepper, cucumber, parsley, etc. These foods are grown in cold, (Yin), climates and they are classified as more Yang than tropical foods because of their higher sodium content. Northern (sodium/Yang) foods are more sustaining and warming in cold weather.

Yin, (potassium), foods are grown in hot Southern, (Yang), climates. Southerners can best utilize the foods grown in their region, such as, all citrus fruits, tomato, papaya, persimmons, mangoes, melons, peaches, berries and all vegetables grown in the South. These plant foods are high in potassium (Yin) and very cooling to the system, to withstand the hot weather.

Daily Ration of Juice

Juice is best taken on an empty stomach, or one half hour before a meal. The daily ration of vegetable juice should be from 4 to 6 ounces, unless you are on a juice cleansing program for a specified period of days, in which you can drink a quart or more per day. Any more than four to six ounces of vegetable juice on a daily basis may overwork the liver, causing yellow/orange skin, or what is known as carotene anemia. This is a result of the liver's inability to utilize vitamin A in large amounts. The darker races should observe the whites of the eyes for yellowness.

No more than four to six ounces of fruit juice should be taken daily. An excessive consumption of fruit juice overworks the kidneys and pancreas because of then concentrated sugar content, which depletes the adrenals and waterlogs the kidney/bladder organs. A healthy body produces only a small amount of insulin daily. An excessive intake of sweet juice will make the body produce excessive insulin and lead to hypoglycemia, (low blood sugar).

An excessive consumption of fruits and juices creates high alkalinity (Yin condition) in the system and overworks the adrenal glands in its effort to maintain the pH balance between 6.5 and 7.0 of the urine. This Yin condition decreases the hydrochloric acid in the stomach, thus lowering protein and calcium absorption. An eliminative diet or fast is not recommended for diabetics, hypoglycemics or other degenerative diseases.

Remember: Consume fruit in season only; but not excessively; more fruit can be eaten in the summer for Yin and Yang balance. Use good judgment in the choice and amount of raw foods at all times. A note to the seriously ill: Please consult a natural health practitioner or a competent doctor who thoroughly understands the process of fasting, natural healing, nutritional therapy and the Yin and Yang principle. A professional of this caliber can determine more accurately, through Oriental Diagnosis, Iridology, etc., what can be accomplished in one's individual case. Disease is nature's effort to get you well. Regain your health by living away disease. Hippocrates claimed that chronic disease came from auto-intoxication, ie., self-poisoning due to constipation. The deposits of accumulated waste in the colon release toxins which inflame the nerves producing rheumatism, neuralgia, melancholia, hysteria, exzema, acne, headaches, and many many other health problems. Hippocrates also taught the way to handle disease.

Overcoming Constipation

Constipation is a worldwide problem. However, it seems to be concentrated in the so called civilized Western nations to a greater extent. Constipation was known back in the time of Hippocrates, where certain days of the month were set aside for taking purgatives, enemas and emetics. It has grown to epidemic proportions especially in stress filled modern society where unnatural living habits are more prevalent, and tons of refined, processed and artificial junk foods and drugs are consumed daily. Constipation precedes most disease conditions. Constipation can be defined as the inability to evacuate the bowels; impacted colon; lack of intestinal strength and paristalsis activity; lack of complete bowel movement; improper stools and infrequent movements. There can also be constipation of the liver, kidneys and bladder because of a clogged condition from overeating.

Yin and Yang Constipation

Atonic constipation is a Yin condition; expanded colon and intestines. The symptoms of this disease are: lack of muscular tone in the colon and abdominal cavity; fallen and pushed out intestines with gas pockets and clogged fecal matter.

Clause: Overeating, excessive fruits, fats, liquids, sugars and other Yin foods to excess; excessive use of cathartics and improper and overuse of enemas.

Constipation is a disease of civilization. Wild men and wild animals do not suffer from this malady, which is perhaps responsible for more human misery and mental and moral disaster than any other single cause.

Spastic constipation is a Yang condition; the colon is constricted or tense and the fecal matter is evacuated in small lumps and stringy.

Cause: Excessive intake of meat, fish, fowl, eggs, white flour products and salt.



Atonic Constipation Spastic Constipation

Fig. 3.7. Colon in Atonic & Spastic Constipation

Constipation is virtually unknown in undeveloped and agricultural based countries. Compare the healthy normal colon with the abnormal diseased colon, and resolve to eat healthfully and perform internal exercises daily to maintain a normal colon and good health.



Fig. 3.8. Colon in Atonic & Spastic Constipation

The following are the Most Common causes of Constipation:

1. Constant Overeating and Improper Diet
2. Too many Food Combinations at Meals
3. Improper Mastication
4. Drinking with Meals (Excessively)
5. Eating when not Truly Hungry
6. Ignoring Nature's Call
7. Eating when Emotionally Upset, Angry or Tired
8. Eating too many Constipating Foods
9. Not Eating Enough Fresh Raw Foods
10. Lack of Abdominal Tone and Physical Fitness
11. Excessive Fruits, Liquids and Sugars
12. Excessive Meat, Eggs, White Flour Products and Salt

Causes of Constipation

1. Overeating bloats and overtaxes the digestive system and organs; and along with improper foods, makes the condition worse. An overloaded stomach cannot digest food properly and this mass of fermenting food coats up the walls of the intestines and colon, making it very difficult to evacuate waste matter. Internal secretions also fail to handle the excessive amount of food eaten.
2. Too many food combinations at one meal can easily upset the body and blood chemistry causing indigestion and toxemia. A mono-diet of just one food per meal, i.e., grapes or apples can do wonders in overcoming constipation.

3. Improper mastication overburdens the stomach and digestive organs. Food must be chewed into a semi-liquid state before the digestive system can handle it without trouble. Swallowing foods half chewed places all the work on the stomach and intestines causing blockages in the colon.
4. Excessive drinking with meals dilutes the digestive juices causing indigestion and constipation; it also hampers proper salivation of foods, which impedes digestion. If liquid is taken at a meal, simply sip slowly and mix with the saliva. The Chinese herbalists recommend a small cup of herb tea after meals to help cut any fat (vegetable or animal) eaten during the meal, and to aid digestion.
5. Eating when true hunger is not present is a burden to the stomach, internal secretions and intestines. True hunger is present when the mouth waters for wholesome unprocessed foods. Stomach pangs, pain or rumblings are all signs of indigestion and false appetite cravings. It is best to eat at regular hours, but if not hungry, skip that meal and wait until true hunger returns; or eat a light meal of fruit or vegetable broth.
6. Ignoring Nature's call to evacuate causes an accumulation of fecal matter in the lower bowel, making it insensitive to further movements. This directly leads to colitis, piles, colon prolapsus, auto-intoxication and constipation. No matter what you're doing at the time, always heed the call of nature.
7. Food is very poorly digested and assimilated when eaten in a state of emotional turmoil; the mouth becomes dry, saliva does not flow freely; stomach secretions stop or slow down and there is no real appetite; therefore, no nerve power t digest and utilize food properly, resulting in constipation. It is the same with fatigue; rest when tired. If you cannot sing or laugh before a mea skip it until you can.
8. Eating too many constipating foods, such as, meats, cheeses, nuts, white flour, white sugar, pastries, nut butters, oils, fatty foods, fried foods, too much popcorn and excessive use of lettuce or spinach raw, are direct causes and major constipating factors which leads to disease, if not counter-balanced by high fiber or anti-constipating foods, such as, whole grains, fruits, sprout: vegetables and juices, bens and yogurt.

9. Not eating a sufficient amount of fresh raw foods can cause constricted kidneys and liver and also hardening of fecal matter in the colon and bowels, which is a Yang condition. Lack of raw food deprives one of vitamins, minerals and enzymes necessary to the proper functioning of the digestive and eliminative system.
10. Lack of fitness, especially abdominal tone can cause prolapsus of the internal organs. The diaphragm muscles must be strengthened to build up tone and health in this area. Those who exercise daily (especially the abdominal region) rarely experience constipation. An overall exercise program also stimulates internal secretions, horones and organs.
11. Overeating of fruits, liquids, sugars etc. causes Atonic or Yin constipation.
12. An excessive intake of meat, eggs, white flour and salt causes Spastic or Yang constipation.

Detecting Constipation

Health and disease can be detected by observing the form and color of the feces. The stools should be firm and shaped like a banana or cigar, without odor; odor is a sign of internal stasis or constipation. Light colored feces are caused by an excess of raw fruits and vegetables. The normal feces should be medium brown; if they are dark or black, excessive animal products have been consumed, or there may be internal bleeding. Reddish feces are usually an indication of bleeding hemorrhoids. Greenish stools mean an overconsumption of Yin fruits and sweets. A baby's feces is yellow and soft. The feces should float; if not, excessive Yin foods, fruits, sugars and liquid have been eaten; also eating without thorough mastication and bad food combinations. When eating wholesome foods, thoroughly chewed and digested, the feces will be brown, firm and float on top.

Excessive salt consumption causes intestinal water absorption, which results in small and dry feces. Excessive use of dairy products, fruits, sugar and fats (all Yin), result in shapeless feces or diarrhea. The bowels should move after each meal. If you eat three meals per day, and have only one movement, you are constipated. In this case your body wastes are usually retained for two days or more. If you have small or scanty bowel movements three times per day, you are still constipated.

Practice

A. Three Minds into One Mind

1. Smile to the Inner Universe

Place your palms together in salutation, in front of your heart. Feel the Laogong points in your hands connect, creating an energy loop running from your heart through your arms and hands and back again.





A. ***B.***

Fig. 4.1 A. *Empty the mind down to the lower abdomen.*
B. *Activate the heart's compassion.*

2. Activate the Heart Compassion Energy

Smile to the heart and feel it softening. Feel love, joy, compassion and happiness. Smile down and empty the mind to the Tan Tien, the Abdominal Brain. Fill the Tan Tien with Chi and start to spiral. When the abdomen is warm, it is full of Chi. The Chi can then charge up to the brain.

Foul smelling stools are an unnatural and unhealthy condition, common to meat eaters only. Vegetarian gorillas and apes who are physiologically built like a human, have odorless stools, which are large and mushy. Their intestines and skin are free from parasites. Pin worms and parasites are always a sign of intestinal toxemia and constipation. More than 80 percent of all people have pin worm and many other types of worms. A diet of processed junk foods, meats, fried foods, sugar etc. will surely attract worms in your system.

Meat eaters invariably have bad smelling stool, along with a coated tongue and foul breath. In the case of the dog, tiger and lion and the meat-eater there are always to be found fragments of decaying flesh in the colon; while the colon of vegetarian animals like sheep, cow, deer and the nursing infant or flesh-abstainer, there is no decay or foul odors.

Internal Bath

A high enema of hot water 100°F will soften the deposits of the large intestine or colon and should be taken at least three days in succession to eliminate the hardened waste matter.

Fill your two quart enema bag with 1½ pints of water. Hang the bag 3 feet above the floor so that the pressure goes in slowly, without cramping, and allowing the water to penetrate the deep crevices. Lie on your back; draw knees up and relax the abdomen. Insert the regular 6 inch nozzle at the end of the tube, well-lubricated with vaseline, into the anal opening. Do not hurry the water into the colon; pinch the hose if necessary to avoid stomach cramps; discomfort will pass if done slowly. Now massage the stomach area with your hands for 1 or 2 minutes; next, get into a squatting position and expel the water and fecal matter. Repeat the above process again with warm water. Use cold water for the third enema; this tones-up the entire bowel area. Hold the second enema in for 10 or 15 minutes and pump the stomach in and out several times.

If you are extremely toxic, continue with 3 enemas per day for a three day period. You can never get all the waste out in one enema or in one day. Afterwards, use an enema when you have the flu, colds, sickness, fatigue or toxemia. It will work wonders for your health and well-being. You may also add lemon juice to your enema bag, or garlic and cayenne, to help cleanse the bowels.

Flaxseed Cure for Colon Cleansing

Cook or soak a handful of figs and prunes and blend them thoroughly; make enough to last a few days. Also add enough water to blender to allow for a liquid consistency. To 2 ounces of the fruit, add about 2 or 3 tablespoonsful of cleansed flaxseed, mixing it thoroughly. Eat this mixture after breakfast and before retiring at night. Flaxseed taken in this manner is tasteless and slides down easily. If the constipation is really stubborn, increase the flaxseed to six tablespoonsful per meal. This is necessary to cleanse the walls of the colon.

Flaxseed is not only lubricating, but healing and nourishing as well, as much of the oil is taken by the tissues. The flaxseed treatment to be effective requires that one drink enough water for the seeds to absorb the fluids in the intestines. This swells up and produces a slimy mass that not only cleanses the colon, but will in time restore the elasticity of the intestines with the resultant effect of a complete evacuation or bowel movement after each meal. Try this wonderful treatment and watch your health improve.

Use this treatment only to overcome constipation; never remain on it after the condition is corrected. Maintaining a wholesome diet, plus sufficient and proper internal exercises, will give one healthy and regular bowel movements indefinitely.

Banana Diet for Intestinal Disorders

Bananas are one of the best cures for most intestinal diseases. The gastro-intestinal tract, in terms of our personal health, is the most vital area in the body. Experts in autopsy state they have found that 60 to 80 percent of the colons examined have foreign matter, such as worms, accumulations of old feces-stones, and decaying undigested food residues. The average so-called healthy man of today is carrying continually within him, since childhood, several pounds of never eliminated feces. No wonder constipation is so prevalent today; it is a natural disorder. Poor intestinal health can easily lead to serious metabolic and organic complications.

However, do not lose hope; the mighty banana can rescue you from this internal disorder and restore intestinal fortitude. Fully ripened bananas contain powerful digestive enzymes that help digest other starches and sugars. In all intestinal disorders the body loses the ability to extract any nutriment from all types of carbohydrate foods.

Bananas are an excellent laxative food, which aid the tiny intestinal villi to expel old waste matter; they increase the absorbing surfaces of the entire gastro-intestinal tract. The mashed pulp of fully-ripened (brown speckled) bananas tremendously alters the internal chemistry of the digestive tract, restoring its ability to digest, absorb and totally assimilate complex carbohydrates, and other food elements.

When feeling bloated, no appetite, constipated, fatigued and cranky, try an exclusive banana eliminative diet for a day or two, or up to a week. Mashed ripe bananas are easier to absorb than a whole banana; they also taste like pudding. Mash them into a creamy pulp with a fork. Eat a bowl of this delicious banana pudding at your regular meal times, or when feeling hungry. Mash 3 to 5 bananas per meal, and eat as often as hungry.

For best results, eat no other food during the banana diet, except for pure water. We recommend this for occasional use only as an internal house cleansing. The whipped banana pulp diet feeds and helps to increase billions of friendly intestinal bacteria, or intestinal flora.



Fig. 3.9. Internal Bath

Other Laxative and Digestive Aid Foods

Apples: contain natural bulk, fruit fiber, iron, malic acid all acting to produce a healthy digestive tract.

Prunes: Rich in iron and potassium. Highly laxative & cleansing.

Pineapple: Contains bromelin, an excellent aid in protein digestion, and enzymic action. Helps to relieve Yang constipation.

Pears: Abundant in malic acid & kidney flushing action; beneficial in overcoming congested kidneys & impacted Yang colon.

Figs: Highly laxative due to its natural fiber, tiny seeds & fruit sugars feeding colon germs. High in iron, minerals & vitamins.

Whole Grains: High in B-complex vitamins, bulk (cellulose) and natural laxative qualities. Use grains in diet for superior health.

Intestinal Cleanse for Internal Health

Practice this Intestinal Program every Mornings:

1. Upon awakening in the morning perform from 10 to 15 sit-ups. Increase the number up to 20 as you become stronger.
2. Next, drink a glass of herb tea.
3. Now do some more abdominal exercises, such as, toe touching, side bends, pulling the stomach in and out. Try to pull the contents of the abdomen upwards, then force it downwards. Wiggle your insides, tossing them from side to side. Strive to control these vital muscles and make them work at will.
4. Continue the exercises until the need for a bowel movement, usually five or ten minutes will be enough.

Constipation is not overcome in a day or two; it takes time for the body to eliminate years of toxic wastes, and rebuild and strengthen itself. Relax and get plenty of rest, exercise, fresh air, sunshine and natural foods. Be persistent in performing the "Intestinal Cleanse" each morning. Within a couple days or weeks on this program you will experience normal and complete morning bowel movements. The key point to remember is to strengthen the entire abdominal cavity, i.e., diaphragm, stomach muscles and the internal organs. When these vital body parts are strengthened, you will vibrate with healthy personal attractiveness.

The Oriental belly dancers have excellent control of their abdominal muscles and diaphragm. Through their action of drawing in large quantities of fresh air and exercising, these girls have marvelous complexions, skin tone, sparkling bright eyes and the grace of a fawn. Include some abdominal exercises, hula or belly dancing movements in your morning routine; be imaginative. Never ignore the call of nature for bowel evacuation, whatever you may be doing during the day.

Abdominal Lift

Stand with feet apart, knees slightly bent and lean a little forward from the hips with the back straight. Inhale deeply and then exhale as much air as possible from the lungs. Next, pull in the abdominal muscles with a firm upward movement until a hollow appears under the rib cage. Hold this position for a few seconds; without inhaling, and then relax. Practice this Abdominal Lift on an empty stomach throughout the day, or preferably with the morning Intestinal Cleanse. This super exercise is great for the wasp-like waist appearance. It will provide your internal organs and intestinal canal freedom from unnecessary wastes, and keep the muscles and skin firm and youthful.

If these instructions are carried out regularly, one will receive the marvelous results of superior physical health and well-being. Drugs, laxatives, stomach and bowel remedies, along with their injurious side-effects, can be thrown out with the rest of the garbage!



Fig. 3.10. Abdominal Lift - Rolling the Abdominal Ball

Exercises to Overcome Constipation



Exercise #1: Stomach, intestines and chest strengthener. Rock the body to & fro on the abdomen for 30 to 60 seconds as shown. Also tones & trims the waist, hips, legs, arms, shoulders & back.



Exercise #2: Tones & strengthens the abdominal muscles, stomach, lower intestines & reduces the hips. Lie flat on the back, raise legs & sway the legs & hips from side to side. Repeat every day.



Exercise #3: Massages the stomach, intestines and internal organs; trims the waist and strengthen the chest and back. Spread feet 3 or 4 feet apart, knees bent. Inhale while stretching backward with arms overhead; while swinging forward and downward, exhale completely and vigorously. Repeat movement 6 to 8 times per day, especially mornings.

Chapter 4

Signs of Health and Disease

Self-Diagnosis

Many people really do not know what good health really is and what to look for it or what causes it and the lack of it. Many individuals honestly do not take the time and effort necessary to discover who and what they are or study deeply into the Universal Laws of health and life. It is almost a tragedy to hear people boastfully claim that they are in perfect health, when in the fact of visible diagnostic symptoms are the complete opposite.

Peopel do not see their skin pale and anemic. They do not see the body weak and fatigued after the least exertion or the complexion waxy, yellow or pimply. They do not look to see that their eyes are dull and listless or their eyesight failing requiring eyeglasses.They do not understand when their hearing is impaired or that they are plagued with insomnia, worry, hate, fear, nervousness, irritableness, pessimism and anger. These are signs and symptoms of failing health and diagnostic conditions of disease.

Physical diagnosis, according to the ancient Chinese and Japanese physicians is the observation of ones external condition, stemming from internal organic disorders.

We are living in a universe of law: cause and effect; yin and yang; positive and negative; acid and alkaline etc. Disease is an outcome (effect) of our daily eating and living habits (cause); and also our heredity, which is the effect of our ancestor’s living and eating habits. We all inherit constitutional weaknesses and strengths from our parents, our habits and nutrition since birth this makes us what we are today.

The causes of illness are many. There are no simple spontaneous causes or quick remedies. The human body is not attacked by disease; disease is the process of degeneration and the symptoms can easily be diagnosed on the face, body, hands, voice and nails etc. before chronic conditions develop. This is the just law of nature and no person can escape its consequences. We can however, live in relative harmony with the Tao or Nature and reap the benefits of good health.

Every body organ affects every other organ, which in turn affects the entire system and manifests itself in observable physical symptoms, which are diagnosable to the trained eye. The physical symptoms can often be diagnosed before a serious disease sets in. It is all in knowing how and what to look for that one can detect a malfunction in the body. This is due to the biological changes the body goes through under various conditions of health, disease and the aging process.

Our external physical conditions, for instance, voice, skin tone, hair, nails and daily vitality depend on the condition of our blood, skeletal, organ and nervous systems, which in turn depend on our total daily eating and living habits.

Four Phases of Oriental Diagnosis

1. ***Bo-Shin:*** The art of observational diagnosis, using the eyes to detect and observe im-balances in the face, hands, nails, posture, skin tone and color, eyes and general habits of living and eating.
2. ***Bun-Shin:*** The art of diagnosing by sounds, such as voice texture, tone, tempo, pitch and breathing.
3. ***Mon-Shin:*** Diagnosing by questioning a person about personal habits, diet, family history, employment problems and psychological tendencies.
4. ***Setsu-Shin:*** The art of touch diagnosis, for instance, acupressure, acupuncture points, pulse diagnosis, skin texture and sense of touch.

This chapter will cover mainly the art of (1) observational diagnosis; and briefly (2) the art of diagnosing by sounds/voice. These can assist one in discovering and overcoming many diagnosable conditions with some conscientious study and research. Diagnosing by questioning and touch require deeper technical research and study by doctors, health practitioners and others involved in clinical patient care.

In diagnosing people of the darker races, the symptoms and colors of health and disease are more detected on the nails, eyes, hair and mouth.



Fig. 4.1. Balance of Yin and Yang

Five Classes of Yin and Yang People

Each individual is born with a certain body type; a Yin or Yang constitution. In diagnosing, there are two factors to consider: inherited constitution, and the present health condition. The Yin and Yang principle is variable, and there are varying degrees of both Yin and Yang people. For example, on a scale from 1 to 10, 1 is Yang and Yin is 10, and 5 is balanced. Body conditions can be diagnosed in a general overall way; to diagnose accurately and precisely, each body organ and body part must be diagnosed separately. No person or phenomena is exclusively Yin or Yang. People are called Yin or Yang because one or the other of these forces dominate in the body; if one is % Yang and % Yin, they are considered Yang; the same with Yin, and vice-versa. We can alter our Yin or Yang condition by the way we eat and live.

There are five classifications of Yin and Yang conditions: Greater Yang and Lesser Yang, Greater Yin and Lesser Yin, and Healthy Balanced Yin and Yang. The balanced person does not exhibit extreme Yin or Yang symptoms. When one shows Greater Yin or Yang signs, they are referred to as Yin or Yang Full; when they show Lesser Yin or Yang signs, we refer to them as Empty Yin or Yang. This tells us how much vitality or energy a person possesses.

A Full or Empty Yang person is much more active; a Full or Empty Yin is less active and energetic. A Yin and Yang Healthy Balanced person is moderate in all activities; neither too slow or fast, but even-tempered in thought and action. This person can eat a wide variety of natural foods in moderation; his digestion, and internal organs function properly; good muscle tone; no constipation; transparent complexion, (glowing); eats seasonally, and never over-eats; performs internal and external exercises moderately daily and weekly; meditates daily; does not crave extreme Yin or Yang junk foods; neither underweight nor overweight; eats more Yang balanced foods in winter, with some Yin, more Yin in hot weather, with Yang foods; his or her attitude is gentle, kind, helpful, giving, loving and inspires those around him. He walks the middle path to truth, enlightenment, good deeds and wisdom ever listening to the Tao within for the secrets of the universe.



Fig. 4.2. Empty and Full Yin and Yang

Facial Symptoms of Disease

a. ***Cleft Chin:*** Strong Constitution and Amorous
b. ***Vertical Line between Eyebrows:*** Yang Liver
c. ***Horizontal Forehead Lines:*** Denotes Excess Intake of Liquids, Expanded Large Intestine and Kidneys
d. ***Broken and Uneven Forehead Lines:*** Small Intestine Disorders, Yin Condition
e. ***Cheeks Sunken In:*** Malnutrition, Poor Assimilation
f. ***Horizontal Line on Nose Bridge:*** Denotes Yang Liver Condition, Excessive Animal Foods
g. ***Swollen Area Above Upper Lip:*** Shows Expanded (Yin) Condition of Pancreas, Sex Glands, Spleen and Stomach
h. ***Cleft on Nose Lip:*** Heart and Circulatory Disease
i. ***Horizontal Line Above Upper Lip:*** Female Sex Gland and Organ Weakness
j. ***Bags under Eyes:*** Expanded (Yin) Kidneys
k. ***Puffy Half Circles (Bags) an Inch Below Eyes:*** Intestinal Toxemia and Weak Lungs

3. Combine the Three Minds into One



1. Turn Upper Mind to observation mind.
2. Turn consciousness (Middle Mind) down to Lower Tan Tien.
3. Combine three minds into one mind at the
   Lower Tan Tien (the Yi).
4. Manifest out at the mideyebrow.

Fig. 4.2 *'Three Minds into One'.*

B. Activate the Six Directions

Expand the awareness to connect to the universe and the Six Directions at the crown, mideyebrow, heart and Tan Tien.



Fig. 4.3 *Trust and believe - turn visualization into actualization.*



Fig. 4.3. Facial Symptoms of Disease

l. ***Spleen Area:*** Weak Stomach
m. ***Bladder Area:*** Lines indicate a Yin Bladder
n. ***Dark Blue under Eyes:*** Kidney, Bladder & Sexual Disorders
o. ***Swollen/Projecting Lower Lip:*** Intestinal Toxemia/Constipation
p. ***Stomach Area:*** Swollen, Cracked or Inflamed (Redness) indicates Stomach Disorders & Expanded (Yin) Condition.
q. ***Amativeness:*** Strong, Protruding Chin denotes Persistance and Determination, Amorous Nature
r. ***White under Iris:*** Sanpaku (Three-Whites) indicates Extreme Yin Condition in Body
s. ***Kidney Area:*** Ears Red or Swollen Snow Kidney Disorders
t. ***Wide Nostrils:*** Strong Lungs, Vitality
ta. ***Narrow Nostrile:*** Weak Lungs
u. ***Duodenum Area:*** Cracked or Swollen Corners indicates Diseased Duodenum
v. ***Pancreas Area:*** Red, Swollen or Veined denotes Pancreatic Disease
w. ***Double Chin:*** Denotes Excessive Cholesterol in System and Yin Condition
x. ***Pointed Ears:*** Excessive Meat (Yang) Intake & Disordered Eating
y. ***Sparse Eyebrows:*** Degenerative Condition and Weak Vitality
z. ***Hollow on Front of Ear:*** Poor Assimilation and Digestion

Diagnose and Balance Empty/Full and Yin/Yang Constitutions

Diagnosing Yang Full People:

Over-Energetic
Reddish Complexion
Yang Liver and Kidneys
High Blood Pressure
Enjoys Cold Weather
Eats Meat, Dairy, Salt & Eggs
Generally Constipated
Round, Fleshy Face, Wide Jaw
Positive & Aggressive
Works Hard & Heals Quickly
Over-Active Organs
Overweight, Strong Pulse
Heart Disorders
Strong Digestion and Appetite
Energetic and Strong Talk
Likes Drink or Alcohol
Circulatory Diseases
Needs Little Sleep
Fat-Strong Abdomen Muscles

Balancing Yang Full People:

In Extreme Yang Conditions: Induce Diarrhea, Sweating and Vomiting; this Diminishes Excess Energy in the Body. Less Yang People with Constipation: Avoid Vomiting and induce Diarrhea and Sweating.

Dietary Recommendations for Yang Full People:

Eat Less Cooked Food, more Raw Fruit and Vegetables, use much Less Salt, Tamari and Miso. Use thinner Broth Soups. Exercise and Sweat more. Use Watermelons, Grapefruit, Lemons, Celery, Parsley, Cucumber, Sprouts, Radishes, Greens etc.

Avoid: Fats, Cheese, Red Meat, Alcohol, Oils, Fried Foods, Ice Cream, Pastries. Drink more Liquid; Herb Teas. Herbs: Juniper Berries, Dandelion Leaf. Oregon Grape Root, Asparagus, Sage, Chaparral, Gravel Root.

Diagnosing Yang Empty People:

Over-Active, Energetic
Tan to Brown Skin
Kidney and Liver Trouble
Weaker Digestion and Appetite
Yang Constipation
Easily Fatigued,
Needs more Rest & Sleep
Takes Longer to Heal
Flat Abdomen & Firm Muscles
Slim to Underweight
More Athletic Prowess
Nervous Condition
Energetic Talk
Thin, Square or Bony Face
Tight Skin; Penetrating
Contracted Eyes
Positive and Aggressive
Moderate Drinker

Balancing Yang Empty People:

Must be kept Warm. Avoid Noise and Inharmonious Surrounding. Obtain sufficient Sleep and Rest. Dress Warm in Cold Weather. Extreme Yang Empty Conditions should eat more Yin-Quality Food.

Dietary Recommendations for Yang Empty People:

Eat less Salt, Miso, etc. Eat Softer Cooked Foods. Drink Moderate amount of Liquid. Eat Warm Foods. Eat more Cooked Vegetables. Eat Less Protein & Fat. Eat Fruits & Vegetables in Season. Chew Food 30 to 40 times.

Avoid: Fats, Meat, Cheese, Ice Cream, Alcohol, Oils, Ungerminated Seeds & Nuts & Citrus Fruits.

Herbs: Cammomile, Comfrey, Yarrow, Juniper Berry, Parsley Leaf, Dandelion Leaf, Alfalfa, Sage, Yam, Plantain and Chaparrel.

Diagnosing Yin Full People:

Underactive Thyroid
Cold Hands and Feet
Overweight
Poor Memory & Thinking
Weak Heart
Underactive Organs
Does not like Exercise
Overweight, Loose Flesh
Prolapsed Abdomen,
Falling Organs
Low Blood Pressure
Blue or Yellow Color
Yin Liver and Kidneys
Likes Warm Weather
Eats too much Sugar, Fat
Cold Drinks, Pastries
Round Fleshy Face
Bruises Easy
Menstrual Difficulties

Balancing Yin Full People:

Sweat to induce Harmony. Extreme Yin Full People should not Fast at all. Regularly eat Whole Cooked Grains & Vegetables. Needs Daily Exercise and Deep Breathing.

Dietary Recommendations for Yin Full People:

Less Salt, Less Liquid. Less Protein and Fat. Some Fresh Raw Fruits and Vegetables. Eat Slow, Chew Well. Warm Soup Broths. Avoid: Pastries, Ice Cream, Milk, Cheese, Coffee, Sugar Products, Ungerminated Nuts, etc.

Some Citrus is Good. Mushrooms, Potato, Radish, Lettuce. Herbs: Oatstraw, Horsetail, Watercress, Nettle, Marshmallow Root, Licorice, Garlic, Slippery Elm.

Diagnosing Yin Empty People:

Inactive, Low Energy
Can develop T.B.
Hypoglycemia
Poor Memory & Thinking
Cold Hands and Feet
Lack of Exercise
Likes Warm Weather
No Strength, Weak Muscles
Anemic and Pale Complexion
Poor Digestion and Assimilation
Hyperactive Thyroid
Weak Heart and Internal Organs
Yin Liver and Kidneys
Underweight, Thin
Eats too much Yin Food

Balancing Yin Empty People:

Needs to be given much Energy. Must live in Harmonious Surroundings. No Fasting. Keep Body Warm. Start with very light Internal Exercises and work up slowly to more Muscular Movements over several months.

Dietary Recommendations for Yin Empty People:

More Yang Food: Grains, Yang Beverages, Thick Vegetable & Grain Soups. Eat Slow, Chew Well.

Avoid: Yin Foods: Juices, Tropical Fruit, Ice Cream, Dairy Products, Slightly more Salt, Miso, or Tamari. Eat Less Liquid. Eat Less Raw Foods. Herbs: Same as Yin Full. Use Ginseng, Burdock.

Face, Hand and Body Diagnosis

Nose:

Long Thin Nostrils: Indicates weak lung power and less physical stamina. Excessive intake of sugars, fats, dairy and animal foods during the embryonic period. A person with long thin nostrils requires plenty of exercise, deep breathing, and outside fresh air. To help widen the nostrils, pull them apart and outward, this will open up the breathing channels, help sinus problems and increase this person's energy. Practice one minute daily.

Wide Nostrils: Indicates strong lung power and good physical vitality, strength and self-confidence. Wide nostril people make excellent athletes, good orators and are self reliant, and have unlimited energy to achieve success. This is due to their larger lung capacity, and ability to take in large quantities of oxygen, which feeds and sharpens the mind and imparts great energy.

Upturned Nose with Wide Nostrils: A sign of a strong yang constitution and physical aggression. This type of nose imparts one with initiative and a hopeful optimistic attitude. They are cheerful and amiable people with a desire to help others. They are also inquisitive, but they need encouragement to carry out their work.

Long Thin Bony Nose: A Yin Sign, more mentally inclined. The voice of a thin nosed person is generally high pitched. They are curious about life, nature and people; refined in manners. They are sharp and quick to perceive; inquisitive; they like details and sometimes overly analytical and judgmental. To balance this Yin personality, more whole grains and cooked vegetables are required. Deep breathing, outside fresh air, and vigorous exercise will strengthen this type of individual.

Red, Bulbous and Greasy Nose (Veins): Indicates high blood pressure, heart and liver disorders. Excessive alcohol, or sugar, fats and meat are the main cause. A swollen nose is a sign of an enlarged heart.

Cleft on the Tip of the Nose: Indicates heart or circulatory disorders. A dull ache in the nose indicates blood stagnation and heart trouble from eating rancid oils. A soft watery nose shows excessive intake of Yin foods and swollen heart. Sneezing is a discharge of excess Yin in the system, i.e., sugars, liquids, drugs etc.



Thin Nostrils **Upturned Nose** **Bony Nose**



Bulbus Nose **Wide Nostrils**

Fig. 4.4. Nose Diagnosis

Face:

Forward Bulging Forehead: Indicates inactive internal secretions and poor body circulation.

Hollow & Sunken Cheeks: Indicates weak lungs and digestive organs; improper nutrition or malnutrition; physical exhaustion and poor endurance. A hollow area in front of the ear opening denotes subnormal secretion of saliva and inefficient food assimilation.

Face Pimples Pimples: Indicates a consumption of extreme Yin foods, i.e., sugars, fats, tropical fruits, juices, pastries, candy, etc., in addition to an intake of extreme Yang foods, i.e., meat, eggs, fish, etc. Yin sweet foods eaten with Yang protein foods results in poor protein assimilation and is eliminated through the skin as eruptions. Intestinal toxemia, poor quality blood and constipation are usually present.

Red & White Spots or Habitual Red Flushed Face: Indicates heart disease, biliousness, fever and inflamations caused by extreme Yang and Yin foods such as animal protein, salt and sugar; disorderly eating. Blood becomes too thick to circulate through the body and results in stagnation and redness.

Orange or Yellow Skin: Shows liver, gall bladder, spleen and pancreas disorders. In vegetarians it indicates an excessive intake of raw vegetables and carrot juice. Sweets are contributing causes.

Green Skin: Indicates liver disease and possible cancer.

Pallor or Pale Face & Cheeks: Indicates weak glands, congested and inactive liver and anemia.

Thin, White Transparent Cheek: Shows weak glands, stomach, lungs and lack of energy. Tendency toward melancholy and introversion caused by poor quality food, weak assimilation, lack of oxygen and proper exercise, yin foods (sugar and sweets). Tendency to consumption and weak intestines.

White Patches: On face or body show liver and kidney disorders caused by excessive dairy foods, fats and sugars.

Veins and Blood Vessels: Showing at temples indicates heart, liver and gall bladder disease.

Cheeks with Veins: Indicates heart & stomach disorders due to gluttony, alcohol & disorderly eating.

Damp, Clammy & Excessive Perspiration: On face indicates extreme Yin and Yang food intake; heart and kidney disease.

Yellow, Waxy or Pasty Face: Shows liver, stomach and gall bladder trouble; dropsical condition of the fluid system caused by excessive fat and animal consumption and sugars.

Warts, Moles and Beauty Marks: Indicates excessive animal protein intake, fats & sugars. Liver & kidney disorders are indicated.
Double Chin: Sign of excessive cholesterol and fatty deposits throughout the system caused by fats, animal foods, salt and sugars; lack of exercise and natural foods.
Well-Developed Chin: Shows a strong heart inheritance, physical strength, and determination to succeed.
Small, Narrow & Receding Chin: Denotes less physical endurance/determination; heart functioning is not as strong as prominent chin caused by poor quality foods during pregnancy, especially calcium deficiency resulting in insufficient jaw formation.



Fig. 4.5. Face - Forward Bulging Forehead

Mouth and Lips:

Normal Nose/Mouth Relationship: Shows normal vertical and horizontal size of mouth. The mouth should be as wide as the outer edges of the nostrils. The mouth and lips are uppermost position of the digestive system, which ends in the anus. Conditions of the mouth and lips indicate deeper internal problems.
Balanced Mouth: Shows that the mother ate a balanced diet during the embryonic period. We inherit the effects of our mother's eating habits.
Pale or Red Lips: Indicates disorders in the stomach and intestines, for instance, compacted colon, constipation, indigestion. Extreme Yin or Yang foods cause internal disease and its symptoms to show up on the mouth and lips. Also show healthy and strong sex glands and hormones with well defined, long vertical crease from the upper lip to the base of the nose; wide horizontal area between the base of the nose and upper lip; and even heart-shaped lips.

Mouth Extended beyond Nostrils: Shows the mouth extending beyond the outer nostrils. It indicates the consumption of extreme Yang and Yin foods during pregnancy and early childhood. Any imbalances in diet cause imbalances in facial features. This condition can be normalized over a period of several years by balancing the diet and avoiding extremes.

Mouth Extended Horizontally and Vertically: Shows weaker internal organs. Generally a Yin or expanded internal condition from generations of Yin foods such as tropical fruits and vegetables, fats, sugar, fried foods, white flour etc. A return to proper eating will eventually contract (Yangize) the internal organs and normalize the exterior features.

Lips Higher Vertically: Indicates a weaker digestive system. Horizontally, the lips are Yang; balanced food was eaten during the mother's pregnancy; but the vertical height shows extreme Yin food during childhood. Also show weak sex glands with a lack of the vertical indentation, short distance between nose-base.

Upper Lip & Thin Pale Lips: Denotes weak internal glands, hormones and sexual powers.

Horizontal Crease Between Upper Lip & Nose-Base: Indicates malfunctioning sex glands.

Large, Loose, open Mouth and Lips: Indicates a Yin expanded stomach and colon; extreme Yin and Yang foods were eaten throughout life. It shows a generally rebellious and uncontrolled nature in mental and physical habits. Can be corrected by natural eating and living habits.

Closed, Evenly Set Mouth & Lips (Heart Shaped Lips): Shows a controlled mental and physical nature. These people direct their lives according to discipline and principle. Their eating habits are more balanced and they avoid extremes in living habits.

Wrinkles above the Lips: Indicate sexual and hormonal malfunctioning; also extreme Yang (dehydration) of body. Excessive intake of salt, spices, protein; insufficient raw foods and liquids.

Cracked Corners of the Mouth: Shows vitamin B-2 deficiency, digestive and stomach disorders caused by extreme Yang & Yin foods, such as animal protein, sugar and fats.

Cleft Pallet: Indicates excessive (Yin) sugars during pregnancy.

Sores on Lips: Indicates intestinal, stomach toxemia and general body congestion.

Tight Constricted Lips: Shows contraction of intestines & vagina.

Small Mouth: Shows much Yang energy & physical & mental vitality. Constant covering of the mouth shows overeating.

Swollen Upper Lip: Denotes stomach disorders; excessive Yin food intake.

Expanded Protruding Lower Lip: Indicates expanded and fallen intestines and constipation. A Yin condition from sugar, fat and excessive liquid intake.

Dry, Thin, Scaly & Mottled Appearance of Lower Lip: Indicates a disorder of the salivary glands.

Thin, Pale & Dry Upper Lip: Indicates weakness of reproductive system. If the upper lip is extremely short (weak spinal column).

Whiteness around Mouth & Pale Lips: Indicates anemia, poor circulation, blood stagnation and lack of expression caused by excessive intake of cheese, ice cream, milk (fats), sugar and high protein (animal).

Pink Lips (Caucasian): Indicates balanced nutrition, good circulation and health.

Darker Races: Observe the condition of the gums; they should be pink (good health). White gums show poor health and anemia.

Dark Lips (Causcasian): Shows liver, kidney and gall bladder trouble. Excessive bright red lips show high blood pressure, acute disease or infection, toxic liver and hemmorrhoids.

Purple Lips: Indicates blood stagnation, diseased heart and circulatory system.

Corners of Mouth Turned Down: Shows intestinal stasis & stomach disorders caused by Dairy foods, fats; cold food and drinks.



Normal Nose/Mouth Relationship

Mouth Extended Beyond Nostrils

Mouth Extended Horizontally & Vertically

Lips Higher Vertically

Fig. 4.6. Mouth & Lips Self-Diagnosis

Eyes:

Lower Sanpaku: Shows a condition of the eye known as Sanpaku or three whites eye whites are visible at the bottom and both sides of the iris. The iris is rolled up, leaving the white part of the eyeball exposed. This is a poor health sign. It indicates an extreme Yin or expanded condition of the brain, nerves, organs and body. In lower sanpaku, the higher the iris rises, the more one is beset with tragedy usually self-inflicted misfortune, accidents, problems in relationships with friends or loved ones etc. Sanpaku denotes a disorderly pattern of eating and living. Excessive amounts of fruits (tropical), juices, alcohol, sugars, fats, ice cream, dairy and fats; in addition to overworking, over exercising, malnutrition, lack of sleep and stress conditions will contribute to and cause sanpaku, and its attendent consequences.

Generally, people with this condition are fearful, suspicious and they lack physical and mental stamina. The criminal mind has also been shown to possess sanpaku. Famous people who possessed sanpaku before dying violently or tragically were: Ghandi, Caesar, the Kennedy brothers, Hitler, Martin Luther King, Elvis Presley and Freddie Printz (Chico and the Man). Many fashion models have varying degrees of sanpaku, due to strict crash weight-loss or starvation diets to maintain the modern skinny look.

A person showing signs of sanpaku is very often difficult to relate to and is skeptical of any help or advice. An honest person with upper sanpaku is more likely to be a victim of violence than a perpetrator. A return to whole foods, centered around grains, vegetables, legumes, seeds and seasonal fruit; including proper exercise, sufficient sleep, stress-free work, meditation and harmonious surroundings, can correct and improve ones overall health and center the iris.

Upper Sanpaku: Yang condition, especially of the liver, kidneys, and related internal organs. The iris is rolled-down in this condition and indicates a cruel nature, physical (Yang) aggressiveness, anger and a fighting character. This is usually caused by an intake of extreme Yang foods, such as animal protein. This person is easily provoked into anger or fighting, so be agreeable in his presence. Being vindictive and merciless, they often meet violent deaths.

Excessive Blinking: Body's attempt to expel excess Yin from the system. Babies blink one or two times per minute; their iris covers almost the entire eyewhite. We should blink no more than two to four times per minute the less the better indicating one in sound

C. Activate the Three Fires

1. Tan Tien Fire - Activate the Tan Tien Fire:

Smile down to the abdomen to create a burning stove near the lower lumbar and sacrum. Create a fire ball behind the navel, above the stove.

2. Kidney Fire - Activate the Kidney Fire:

Always retain awareness at the Tan Tien and keep it spiraling.

3. Heart Fire - Activate the Heart Fire:

Keep the heart soft and fill the heart with joy, love and happiness.



***Fig. 4.4 A.** Activate the Lower Tan Tien Fire.* ***B.** Activate the Kidney and Adrenal Fires.*
***C.** Activate the Heart Fire.*

4. Sacred Fire Triangle

The Sacred Fire Triangle has triple force. Make a triangle from kidneys to navel (Tan Tien). From the heart make the connection to the kidneys. Move from the Tan Tien up to the heart.

5. Cosmic Star and the Earth Star

At the moment of conception, the two forces yin and yang connect with such a force, then only fractions of a moment later, the two forces explode into nine different Energy Centers. Seven of them we find in the body and two of them outside the body, forming our personal stars.

health and in control of mind and body. In the animal realm, cats seldom blink; their eyes shine and glow in the dark; they are very independent and in total control of their actions. Humans can accomplish the same; but it may take many years of discipline in diet, health habits, exercise and meditation to attain superior health and control over one's nervous system and bodily functions.

Four White Sided Eye: It is usually accompanied by a bloodshot reddish hue, and is uncontrolled. There is usually a psychological problem or conflict in the person's life, accompanied often by a violent temper, outrage, oversensitiveness and assault. The individual's eating habits range from extreme Yin to Yang; starvation diets to gluttony.

Eyes Turned Inward: Shows a Yang or contracted iris; one that is turned inward toward the nose. It is a Yang condition, resulting in high blood pressure and heart problems. An excessive intake of meat, eggs, salt, eaten during the embryonic period or during early childhood. Balancing the diet can help to correct this condition.

Eyes Turned Outward: Shows a Yin or expanded condition of the eyeball; the liver, stomach and kidneys are also Yin. Cause: Excessive intake of Yin foods, i.e., sugars, sodas, ice cream, fats, tropical fruits, drugs and alcohol. The extreme of this condition may be prone to chronic disease. A Yin and Yang balanced diet can help correct this condition in due time.

Centered Normal Healthy Eyes: The upper and lower eyelids should touch the iris, with very little eye whites showing on the sides of the iris. The eye pupils should function properly in both light and darkness. Healthy eyes do not require glasses or contacts; neither do they squint or function poorly in close and distant vision; the sight is sharp and clear at all times; the eyes sparkle and the eye whites are clear.

Dark Eye Bags: Weak female organs and constricted (Yang) kidneys are indicated by a dark brown (half-circle) coloring under the eyes. Swelling, veined or dark blue under the eyes denotes kidney stones, gall stones, blood stagnation and anemia, caused by extreme Yin and Yang foods. Purple under eyes denotes adrenal exhaustion. Discolored puffy circles one to two inches below the eyes indicates lung disorders. A person with this condition is generally afflicted with diseases such as, lung cancer, tuberculosis, asthma and other respiratory disorders. Cause: tobacco smoke, sugar, high fat dairy products, (cheese, milk, butter) and a host of other extreme Yin and Yang junk foods.


Lower Sanpaku (Yin)
Upper Sanpaku (Yang)
Four White Sides
Eyes Turned Inward (Yang)
Eyes Turned Outward (Yin)
Normal Healthy Eye
Swollen Upper Eyelid
Dark Eye Bags
Bulging Eyes
Hollow Sunken Eyes
Glassy Eye

Fig. 4.7. Eye Self-Diagnosis

Swollen Upper Eyelid: Indicates gall bladder stones, heart and sexual manfunctioning. The swelling usually subsides when the stones pass. Cause: Sugar, fats & animal foods eaten to excess.
Bulging Eyes: Indicates lack of iodine in early childhood or embryonic period and thyroid disorder; also a Yin/expanded condition of organs. Excess intake of liquids and sugar.

Wide Staring Eyes: Indicates poor judgment, credulity, or if the expression is anxious, fear and apprehension. Orators & linguists have the full or convex eye. Fullness below the eye verbosity.
Puffiness or Bags under the Eyes: Indicates disease from dissipation; it is not the same as fullness. The eye foretells the truth when all the other features deceive us. When the eye says one thing and the tongue another, the practical man relies on the former.
Dark, Hollow, Sunken Eyes: Indicates extreme emaciation, deficiency of muscular development, nerve and physical exhaustion. Cause: Extremes in diet, starvation, or malnutrition.
Eyes with Light Blue: Indicates internal parasites & kidney trouble.
Scant Lower Eye Lashes: Deficiency in sexual glands & hormones.
Scant Upper Eye Lashes: Denotes (Yang) mental deficiency.
Itchy Eyes: Indicates liver malfunctioning and lung problems.
Hard Yellow Spots in Eye-Whites: Indicates worms in system.
Dry & Inflamed Eyeballs: Indicates an extreme Yang liver disorder and vitamin A deficiency.
Sties Growths on Eyelids: Shows an excessive intake of protein.
Pale, Colorless, White Eyelid (Upper & Lower): Denotes anemia; the eyelids should be pink in good health.
Yellow Eye Whites or Yellow Deposits in Eyes: Indicates excessive cholesterol in the system and liver and gall bladder blockage caused by excessive intake of fats, oils, fried foods, cheese, ice cream, milk, sugar and animal protein.
Entire Eye is Yellow: Jaundice is indicated. A Yin and Yang balanced diet can correct this situation in due time.
Bloodshot Eyes (Habitual): Indicates inflamed condition of the intestines and brain. The liver, gall bladder are affected. Eye strain, poor lighting, constant sun glare and late night reading can also cause bloodshot eyes caused by cheese, sugars, drugs, all fats, alcohol, dairy foods, animal foods etc. leading to chronic disease.
Dull, Lackluster Glassy Eye: The nervous system is under strain and pressure. Poor circulation, extremes in diet, hardened arteries and liver are indicated. A person with glassy eyes requires a complete change in diet and living habits. All drugs, alcohol, cigarettes, marijuana, overwork, excessive sex, stress and tension must be discontinued if a return to good health is desired. Also, meat, animal fats, dairy products, sugars, pastries, oils, etc., are causes of nerve disorders and consequently the dull glassy eyes.

Excessive Large Pupil: In daylight denotes nerve exhaustion and extremes in diet. It is a Yin, expanded condition of the kidneys, stomach, spleen intestines and bladder; adrenal weakness and brain expansion. Excessive intake of raw food (Yin). A balanced grain, vegetable, seeds and legume diet, including seasonal fruit should normalize the eye pupil in due time.

White Ring around the Iris: Indicates excessive intake of table salt, nerve weakness, poor circulation to brain, anemia and possible senility. Disordered eating, living and extremes in diet are contributing factors.



Slanting Intoward Nose

Slanting Down & Outward

Sparse Eyebrows

Connected Brows

Fig. 4.8. Eyebrow Self-Diagnosis

Eyebrows:

Eyes Slanting Intoward: Indicates Yang and aggressive nature caused by generations of animal food consumption.

Eyes Slanting Down & Outward: Shows a gentler & compassionate nature caused by vegetarian diet.

Sparse Eyebrows: Indicates a weakening health condition. Extremes in diet, such as excessive intake of sugars, liquids, fats, tropical fruits, juices; and animal foods. It shows weak life force, tendency to chronic disease and degeneration.

Connected Brows: Indicates strong life force, vitality, and artistic ability. It also shows generations of fatty animal food & dairy intake. The spleen, liver and pancreas are weakened by these foods.

Thick/Separated Brows: Shows superb health & long life potential.

High-Arched Brows: Denotes a person with a dramatic and creative flair, with the emphasis on active showmanship and leadership. Somewhat eccentric in character and mentality.

Ears:

Large Ears: Indicates strong inherited constitution; strong kidneys and adrenals showing are sign of health and longevity. Generations of basically vegetarian foods.

Thickness & Height in the Outer Upper Ear: Shows excellent blood circulation throughout the body and creative mental capacity; also the ability to accumulate and successfully handle finances and material possessions.

Large & Well Formed Inner Ear Area: Indicates good digestive and assimilation powers.

Fleshy & Thick Inner Ridge: Shows nerve force & inner strength.

Creased Ear Lobe: Shows heart disorders or diabetes.

Large Ear Lobe: Shows a healthy inherited constitution.

Small Ears & Lobes: Shows weak adrenals and small kidneys; generations of meat eating; energy generally low with little interest in mental pursuits. Small eared people should avoid excessive intake of animal protein, as their kidneys are unable to handle it.

Small Ears & Lobes: Shows a weak inherited constitution. Small eared people should emphasize whole grains, vegetables, soaked seeds and nuts, sprouts, fruits in season, with a minimum intake of protein foods. Cooked legumes should be eaten moderately. Sufficient rest, sleep and harmonious surroundings are recommended; exercise moderately, but never to exhaustion.



Large Ears **Ear Protruding**

Small Ears **Ear Close to Head**

Fig. 4.9. Ear Self-Diagnosis

Ears Protruding: Shows a Yin constitution. Impulsive & emotional activity. Mother ate too much Yin food during pregnancy.
Ears Close to Head: Indicates balance in mind and movement. Mother ate a more balanced Yin and Yang diet during pregnancy.
Ears High on Head: Indicates self-pride, egotistical nature, base instincts and material cravings and desires to excess. Mother ate excessively of animal foods & salt during embryonic period.
Ears Top Level with the Eye Corners: Indicates balanced mental and physical development.
Red Ears: Indicates a toxic, overworked kidney (Yang); excessive salt and protein. Spleen disease is indicated if the outer portion of the ear is red. Avoid extreme Yang foods.
Ear Wax: Sign of excessive intake of fats, oils, animal foods, and fried foods. It will not develop if these foods are not eaten.

Teeth:

Long Front Teeth: Indicates a Yin constitution. Short front teeth and ones that angle inward are Yang and indicate an uncontrolled character. Teeth that angle outward show a passive character.
Pointed Teeth: Excessive meat eating & other Yang foods over generations causes pointed teeth, especially the canines. The canine teeth will diminish in size as less meat is eaten over generations. Natural & orderly eating results in balanced & normal teeth.
Tooth Decay: Result of excessive intake of sugars, fats, animal foods, protein, liquids; and insufficient calcium from natural whole foods, such as grains, seaweeds, legumes, vegetables, seeds & fruits. Animal protein & sugar diminishes calcium absorption from other foods; calcium deficiency is the end result of tooth decay.
Crowding Teeth & Extra Teeth: Caused by extreme Yin & Yang foods during pregnancy.



Pointed Teeth

Fig. 4.10. Teeth Self-Diagnosis

Hands:

Swollen Kunckles & Fingers: Indicates expanded (Yin) kidneys, artheroscerosis and high blood pressure.

Bluish Wrist: Indicates sex gland weakness.

Reddish Palms with White Spots: Shows disorderly eating and poor blood circulation; excessive intake of animal protein and fats.

Bluish Palms: Denotes circulatory and heart trouble.

Dark Red Palm Heel: Indicates bladder & sexual disorders.

Yellow or Orange Palms: Indicates pancreas, spleen and liver disorders. Excessive intake of fats, raw greens or carrot juice are factors to be considered in causing this problem. In good health, the hands should be slightly pink and warm, dry and be firm, but not hard.

Hot, Moist & Red Hands: Indicates Yang congested liver & kidneys.Red hands are caused from excess Yang foods.

Cold, Clammy & Pale Hands: Indicates Yin expanded kidneys, bladder, stomach and intestines; weak nerves and anemia. Pale, cold hands are caused from excess Yin foods.

Flexible Fingers: If the health and blood circulation are normal, the four fingers should bend back 90° to the hand. This indicates a flexible mental and physical character, able to adapt to outward changing conditions; it shows healthy organs and good nerve and blood flow. A less than 90° backward bend indicates calcification or hardening of the bones, nerves, muscles, organs and reproductive system; a stubborn and unchangeable character usually accompanies inflexibility and hardening of the joints and muscles. The cause is from an excessive intake of sugars, salt, fats, oils, cheese and animal protein. Orderly eating can reverse this condition before terminal degeneration has set in. The less angle, more the hardening. Arthritic & painful joints show diseased kidneys.



Fig. 4.11. Flexible Wrist

Flexible Wrist: Should also have a 90° angle.

Raised Blood Vessels on the Back of the Hand: Indicates an excessive intake of Yin foods and a Yin kidney.

Trembling Fingers: Indicates weak nerves, nervousness and heart disorders.

Brown Spots on the Back of the Hands, Arms or Body: Denotes liver and gall bladder congestion; excessive intake of animal foods, dairy, fats and sugars.

Webbed Fingers: Indicates over-consumption of Yin foods and liquids during the embryonic period.

Wide Palm with Firm Flesh: Indicates strong inherited constitution with an active, aggressive nature & robust health (Yang).

Narrow Hand & Long Thin Fingers: Indicates sensitiveness, intellectual and artistic personality, and delicate health (Yin).

Round Bulge Appears on the Wrist: When the palm is pressed with the opposite thumb, above the wrist, the body is holding excessive liquids or sugar (Yin condition); the hands are usually moist.



Webbed Fingers **Wide Palm**



Narrow Hand **Round Bulge**

Fig. 4.12. Hand Self-Diagnosis

Fingers and Nails:

The nails are hard or clawlike extensions of the fingers; the fingers, in turn, are extensions of the entire nervous system; the nervous system is intricately connected to the brain, organs and every cell and tissue in the body. In acupuncture, these nerve pathways are known as merridians. If there is a blockage of circulation or stagnation of blood, or an excess of energy in any internal or external area of the body, this deficiency or excess can easily be detected & diagnosed in extremities (hands, nails, fingers & feet).

Visual Diagnosis: One who is trained in visual diagnosis can detect symptoms before they start to appear. One of the methods to do this is to look at the fingernails. For example, if the nail thickens noticeably it is one sign of circulatory weakness, lymph gland malfunction or blood diseases. When a fingernail has a tendency to become yellow, it may be an early sign of liver disease. Diabetes can be recognized by the gradual disappearance of the pink coloration of the nail.

Looking Glass: The fingernails are a looking glass or mirror, reflecting inner physiological conditions. Pink nails indicate good blood circulation to the fingertips showing blood flow through the mirror (nail). Lack of blood flow to the fingertips shows up as clear white nails, and is diagnosed as anemia. One can give an accurate prognoses and avert future health problems by reading and diagnosing the fingers and nails. Proper health measures and corrective eating and living habits can then be recommended to overcome the diagnosed symptoms. The entire hand can show past and more recent conditions of the individual, and it can indicate health or disease tendencies in the future or near future through prognoses.

Inflamed/Reddish Finger: Indicates acute or short term illness.

Hardened, Rigid & Chalky White Nails: Indicates severe and chronic or organic disease.

Wide-Short Fingers & Nails: Indicates a strong Yang constitution; practical, persistent, physically active and aggressive.

Long-Narrow Fingers & Nails: Indicates a Yin constitution; artistic, sensitive, imaginative, delicate;tendency to bronchial disorders.

Extremely Narrow Fingers & Nails: Denotes a delicate inherited constitution and less physical energy.

Finger/Organ Relationsdhip: The fingers are connected via nerves and merridians to body organs. The corresponding reflex finger/organ areas are listed as follows: thumb, lungs; first phallange, liver/large intestine; second phallange, circulatory system (heart governor) and sex glands; third phallange, kidneys (triple heater); fourth phallange, heart and small intestines.

Lack of Half-Moons: Indicates sodium/potassium imbalance; underactive thyroid gland; weak healing power in system; lack of circulation and low blood pressure. It is usually a Yin condition from an excessive intake of sugars, fats, juices and raw foods. Can also mean possible liver disorder. Indicates little or no physical exercise. It can also be caused by an excess of meat and salt.

Excessive Half-Moons: Half moons more than one quarter of the nail shows an over-active thyroid condition; tendency to excessive physical and mental activity and nervousness. An excessive intake of high potassium (Yin) foods can cause overdevelopment of the half-moons; however, in time the moons may disappear due to the extreme potassium/sodium imbalance and result in disease or poor health. Excessive half-moons can also mean high blood pressure. On the other hand, an excessive intake of sodium (Yang) foods may also cause the half-moons to disappear. Generally a lack of raw fruits and vegetables contribute to a Yang system. Regardless of age, the half-moons should always be present; if not, the important healing and beauty mineral element, potassium, will be missing, resulting in deficiency diseases. Yin, internal conditions change into Yang, and Yang ones change into Yin, (the process of biological transmutation) which is the natural order of Tao.

Healthy Half-Moon: A healthy half-moon should be no more than one-fourth of the nail, indicating potassium/sodium balance; vital healing power in the system; mental and physical energy and a balance between activity and rest. The Taoists teach that the normal sized half-moon indicates freedom from chronic disease and good health. The half-moon should show on all nails.

White Spots on Fingernails: Indicates zinc, pantothenic acid and calcium deficiency; poor protein absorption, pancreatic disorders and insulin deficiency; weak stomach acids and possible worms. Sugars and other excessive Yin foods and substances, such as drugs, chemicals, marijuana and alcohol neutralizes stomach acids causing calcium and mineral deficiencies. This also includes dairy products, honey, tropical fruits, sodas, cakes and candy. Nails take from 6 to 9 months to grow from bottom to top. One can determine, by the location of the white spot, the time of high Yin food intake, diseased organ and sugar in the blood stream. White spots can also mean kidney disease.



Fig. 4.5 Three Fires into One



Fig. 4.6 'Personal Star' Energy

The two personal stars are in fact energy centers connecting the aural field of each individual with the universal forces and the earth forces. In a way one can see the aim of Taoist Inner Alchemy in bringing these nine forces together, merging them into one force and thus enabling the return to the original force, the Wu Chi.

There is a star about six inches above your crown and another one about one to three feet below the soles of your feet. They are also known as the higher self, guidance, protector, adviser. These stars are our connection to the cosmic force, the universal force and the earth deep below us.

Always make sure your Tan Tien is warm and the sacrum and mideyebrow are breathing. Be aware of the crown breathing and see a star or a small sun above you. Be aware of the crown and feel a light beam extend out of the crown and make a connection to the star above you. Keep on breathing until you feel a strong connection. Feel how the star above you is exercising a strong pulling force on your crown. Once you feel this pull on your crown you will also feel a strong pull down from the earth. Be aware of the star above and the earth and universal force below you. Feel that both of them have a strong pull on you.

1. Reconfirm the star above you and the earth directly below you.
2. Fix the image of the North Star and the Big Dipper six to nine feet above your crown. See the cup of the Big Dipper filling with the violet light, which gathers Chi from the North Star and the universe.

Nail Color:

Pale & Chalky Nails: Indicates poor circulation, nerve exhaustion and possible stroke; anemia and poor iron and protein assimilation. Cause: Extreme Yin and Yang foods.

Green Nails: Denotes improper copper disposal and congenital liver ailment.

Bluish Nails: Indicates lack of oxygen and circulation to heart and heart disorder.

Tiny Red Dots under the Nails: Shows possible pin worms.

Transverse White Lines across Nails: Denotes fever, heart and kidney disease and malnutrition.

Biting Nails: Denotes intestinal and stomach problems and possible parasites in the body.

Red or Purple Hemorrhages under the Nails: Indicates an inflamed heart lining.

Soft Nails: Denotes calcium, vitamin, mineral and protein deficiency from an excess of sugars, dairy, fats and animal foods in the diet, weak will power and general fatigue.

Excessively Hard & Brittle Nails: Denotes anemia and hormonal imbalance.



Wide, Short Fingers **Long Narrow Fingers** **Lack of Half-Moons**



Excessive Half-Moons **Healthy Half-Moon** **White Spots**

Fig. 4.13. Nail Self-Diagnosis

Excessive Shiny Nails: Shows an overactive thyroid gland.
Excessive Red, Dark Blue or Purple Nails, Fingers & Swollen Hands: Shows heart and circulatory problems.
Triangle Shaped Nail: Indicates a weak inherited constitution and a ten-dency to nerve diseases, such as paralysis or palsy. This individual should watch his or her health, taking care to eat wholesome foods and obtaining proper sleep and exercise.
Short, Shrunk & Whithered Nail: Denotes a hypertensive nervous system and extreme malnutrition or malabsorption of food; extremes in diet during pregnancy or through early childhood; chronic disorders and critical & fault finding character.
Convex or Hour-Glass Nail: Denotes lung ailments, scrofula, dyspepsia and a possible Yang liver; excessive mucous and possible tendency to tuberculosis. A Yin lung condition from excessive intake of Yin foods.
Concave or Spoon-Shaped Nail: Shows tendency to infections, chronic anemia, possible hook worms, hyperthroidism and malnutrition; extremes in diet.



Triangle Shaped Nail Short Nail Hour-Glass Nail Spoon-Shaped Nail



Vertical Ridges Horizontal Ridges Round Bulging Nail

Fig. 4.14. Nail Color Self-Diagnosis

Anemia Test: One way of detecting anemia is by pressing any fingernail with the thumb; the nail will turn white from the thumb pressure; if after releasing the thumb pressure, the whiteness remains longer than a second, anemia is indicated. A pink color should show up immediately after releasing thumb pressure, indicating good blood circulation and absence of anemia.

Vertical Ridges: Denotes intestinal, liver & kidney disorders; circulation & skin impairment; poor protein & calcium absorption.

Ridges with Convex & White Chalky Nails: Denotes advanced chronic disease, such as stroke, cancer & hardened arteries.

Cracked & Split Nails: Calcium deficiency & weak sex glands.

Deep Horizontal Ridges: Indicates severe calcium and protein deficiency; acute illness; nerve exhaustion; anemia and psoriasis; extreme dietary eating patterns and changes in environment. For example, moving from north to south frequently and changing from Yang to Yin diets, or hinging on junk foods to Yang foods to fruitarian and raw foods/fasting and repeating the cycle over and over.

Round Bulging Nail: Denotes lung disorders; possible liver trouble and hardened arteries; this is a Yang sign.

Thick Raised Cuticle: Denotes an excessive intake of animal protein; extreme dietary changes, kidney and liver disorders.

Red or Bleeding Cuticle: Extreme condition of the above problems caused by excess Yin food intake.

Flat Nails: Indicates a weak lymphatic system, proneness to mumps, tonsils, appendicites, including other acute disorders. This is a Yin condition.

Square Nails: Indicates kidney disorders; excessive intake of animal protein or malabsorption of food.



Raised Cuticle

Flat Nails

Square Nails

Fig. 4.15. Nail Shape Self-Diagnosis

Feet:

Foot: Indicators of health or disease throughout the body. Certain symptoms in the feet signal trouble in the reflex body organs.

Athletes Foot: Sign of kidney problems caused from excessive animal protein intake.

Fallen Arches (Yin Condition): Indicates weak nerves.

Foul Smelling Feet: Sign of excess animal protein intake, liver & kidney disease.

Hard Callouses on Feet or Hands: Denotes excessive dairy products and animal protein in the diet.

Cracked Nails: Shows liver, kidney, spleen and pancreatic disease; excessive Yin and Yang foods.

Toes: Each Toes is connected to a body organ via Nerve Pathways (Merridians) as follows: Big Toe, Liver; 2nd Toe, Stomach; 3rd Toe, Bladder; 4th Toe, Gall Bladder; 5th Toe, Kidneys. Each toe can be massaged or pressed for one or two minutes to help improve the corresponding organ.

Hard, Whitered-Inflexible Toes/Nails: Denotes organic disorders.

Pain or Swelling in a Toe or the Feet: Indicates a disorder in the corresponding organ.



Fig. 4.16. Feet Self-Diagnosis with Five Vital Organs

Hair:

Premature Grey or White Hair: Sign of an excessive intake of Yang animal protein and Yin sweet foods. This indicates a liver, gall bladder and kidney malfunction. White haired people are generally more set in their ways, and it is hard for them to change and be more flexible.

Much Body Hair: Denotes a Yang inherited constitution and excessive animal protein consumption over generations.

Split Hair Ends: Indicates malfunctioning sex glands and hormones in both male and female. Excessive sugars, fats, and animal protein are the main cause of split ends. Poor hair circulation, overeating and lack of exercise are other contributing factors.

Dry Hair: Indicates liver, gall bladder, spleen and pancreatic disorders caused by fats, sugars, animal protein.

Oily Hair: Caused by excessive fats and oils in the diet.

Dandruff: Caused by excessive animal protein, fats, oils and sugars and kidney malfunction.

Hair Loss: Indicates internal organic disorders, especially from excessive animal protein, fats and sugars.

Hair Loss Front of Head: Caused by excessive Yin liquids, sugars, fruits, alcohol which lowers kidney & bladder functioning.

Hair Loss Top of Head: Indicates excessive animal protein. The lungs and large intestines are adversely affected.

Hair Loss Back of Head: Denotes excessive intake of chemicals, drugs, marijuana & medicine affecting liver & gall bladder.

Hair Loss Temples: Indicates excessive intake of drugs and sugar foods. The lungs and large intestines are affected.



Front Head Hair Loss

Top and Side Hair Loss

Fig. 4.17. Hair Self-Diagnosis

Tongue:

The tongue is an extension of the gastrointestinal track, which terminates in the anal canal. Any problems or disease symptoms on the tongue indicate disorders in the stomach, intestines and colon. Diseases can be diagnosed from the condition of the tongue. Any disorder in the *Middle of Tongue (Stomach); Sides of Tongue (Liver); Root of Tongue (Kidneys) & Tip of Tongue (Heart)*.

White/Yellow Color & Dry Coated Tongue: Indicates stomach fermentation, intestinal toxemia, liver and gall bladder disorders caused by excessive intake of dairy foods, fats, animal foods and overeating. A short water fast is indicated in this condition.

Green Tongue Color: Shows liver and kidney disorders.

Blue Tongue Color: Shows kidney and bladder trouble; disorderly eating. A balanced natural diet will balance the organs.

Violet Tongue Color: Shows liver & heart disease (Alcoholics).

Grey or Black Tongue Color: Indicates kidney and heart disease; black at the tongue base shows possible cancer.

Purple Tongue Color: Denotes sex and bladder disease.

Crease down the Middle of Tongue: Denotes intestinal disorders & vitamin B complex deficiency and extremes in diet.

Trembling Tongue: Shows a nerve condition & brain weakness.

Sties or Growths on Tongue: Indicates excessive intake of animal protein, kidney disease & a Yang heart. Also intestinal toxemia and constipation are generally indicated. Avoid over-eating, especially extreme Yang foods, meat, eggs, fish & salt & extreme Yin foods, i.e., ice cream, white sugar, pastries, alcohol & all fats.

Soft, Loose Tongue: Shows an expanded gastrointestinal system; excessive Yin foods.

Hard, Tense Tongue: Denotes excessive mucous in the system; animal foods, dairy, sugars and disorderly eating are indicated.



Line on Tongue

Sties on Tongue

Fig. 4.17. Tongue Self-Diagnosis

Voice:

Many diseases can be diagnosed from the sound and texture of the voice. The sound of the voice corresponds to inner physiological conditions. A crackling, hoarse voice always denotes degenerative disease of the sexual glands & hormones.

Voice Sounds: Designated into Yin and Yang as follows:

Yang	***Yin***
Strong Voice	Weak Voice
Low Pitch	High Pitch
Fast Speech	Slow Speech
Loudness	Softness
Dry Sound	Wet Sound
Tenseness	Looseness
Distinct Sound	Unclear Sound

Watery, Loose Voice, with Slow Speech: Indicates an excessive intake of (Yin) liquids, fruits and sugars. The result is kidney expansion, weakness and mucous.

Unclear & Weak Voice (Yin): Denotes lack of inner energy & vibrant health. For example, if one's health is poor, with low energy, the body lacks the force or vitality to express itself in a clear vibrant tone. Very sick people always speak quietly in a trembling tone.

Tense, Dry, Fast or High Pitched Voice: Indicates intestinal congestion, sexual degeneration, constipation; bladder, high blood pressure and circulatory trouble. Cause: Excessive intake of Yang foods, such as meat, eggs and salt contract the sex glands, kidney and liver, causing the person to shout or talk in a loud voice.

Fast Speech: Denotes an overactive heart; a Yang condition.

Stuttering: Indicates extremes in diet (heart & nervous conditions).

Voice Resonates: From various sections of the body; congestion and mucous can be detected according to location in the body. One can help to heal a congested section by making the sound of the designated vowel or letter for a minute or two, and focus the concentration on the area to be healed. For example, if one has sinus congestion, place the tongue on the upper palate and hum the sound "N" several minutes a day.

Magnetic Voice: A healthy voice is enjoyable to hear. It is neither too high or too low, but resonates and vibrates in a clear musical tone; this is the magnetic voice; it soothes and heals those who hear it. Consuming the balanced Yin and Yang foods and correcting the living habits will eventually improve ones voice.

Vibrant, Pleasant Voice: One must speak with an open throat and from deep down in the lower diaphragm-abdominal region.

Voice Exercise: Take a deep breath; open the mouth wide, and make the sound "AH" from the lower abdomen for five seconds, then stop. Inhale again and repeat for ten seconds and stop; continue in this manner up to 20, 30, 40 or 50 seconds, or as long as comfortable. Always start at the zero second mark and work up with five second intervals, i.e., 0-5, 0-5-10, 0-5-10-15 and so on. After a few weeks practice, of a minute or two per day, one can be up to 30 or 40 seconds non-stop, and the throat will then be opened and relaxed; the voice will be more vibrant and pleasant. If one reaches the sixty or seventy second mark while humming "AH" non-stop, they are on the way to developing a pure magnetic voice, one that others will gladly listen to. One may also practice this humming tone with the other body sounds M, N,, E, O, U.

Excessive & Confused Talking or Slow Talking: Indicates extremes in diet and excessive or disorderly eating. If one is not understood, it is because he does not understand himself due to inner physiological and psychological confusion and dietary imbalances. A healthy person speaks little, says much.

Strong, Clear Voice: Indicates healthy kidneys, liver, stomach, lungs, and strong sex power.

Weak, Trembling Voice: Denotes kidney & sex gland disorders.

Urine:

Dark Yellow or Brownish Color Urine with a pH under 6.5: Denotes a sluggish Yang liver and bile backed up in the blood caused by excessive intake of animal protein, fats, chemicals and sugar. The kidneys are constricted (Yang).

Light Colored or Clear Urine with a pH over 7.5: Denotes an expanded (Yin) kidney and liver caused by excessive intake of Yin foods; sugars, juices, alcohol, tropical fruits, liquids and raw foods.

Excessive Urination: Denotes expanded (Yin) kidneys caused from an excessive intake of Yin foods. Excessive urination with an excessive appetite, a glazed and furrowed tongue, diarrhea and loss of sexual and mental powers indicates a diabetic condition caused by diet too high in fats, sugars, animal protein, empty calories; excessive intake of Yin and Yang (extreme) foods.

Healthy Urine: Should be straw colored or the color of light beer, which will be 7.0 or balanced on the pH scale. This denotes a balanced Yin and Yang and Acid and Alkaline diet.

General Body Symptoms

Belching, heart burn, nausea, loss of appetite and dyspepsia are caused by an overloaded stomach, excessive fats, protein, oils and sugars in the diet. Toxemia and fermentation result from overeating, disorderly eating and various other enervating living habits. Constipation is usually present.

A swollen abdomen, itching about the anus and genitals and an offensive bad breath indicates pin worms or tape worms in the stomach or intestines, constipation and general body toxemia. Disorderly eating, overeating and extremes in diet are general causes of this condition. A pain in the lower back, in many cases, can be attributed to Yang (overworked) kidneys; the kidneys are located just above the right and left hip bone in the lower back region. An excessive intake of animal protein contracts (Yang) the kidneys and causes pain in the lower back.

An unlively, slow and mincing walk, when habitual, indicates premature nerve degeneration or senility. This can happen at any age, depending on the individual’s living and eating habits. One can be young, active and full of vitality at 80, or burned out and aged at 30 or 40; it all depends on the health habits and attitude of the individual. Constant colds, flu or sinus trouble is a definite indication of an excessive intake of fatty foods, cheeses, oils, fruits, liquids, sugars and animal protein. Excessive fruit eating can also lower stomach acids, depress kidney and lung activity and result in chronic mucous. Nuts, cheese, milk and fruits can cause colds and mucous just as fast as regular junk food.

Vibrant Health and Human Beauty

The idea of beauty of person is synonymous with that of health and a perfect organization. What an inspiration it is to see a truly robust and healthy man or women. A radiantly healthy man is always handsome; an energetic healthy woman is always beautiful.

They possess a magnetic charm that draws attention and compels admiration wherever they go. Beauty is but the reflection of wholeness, of health. Partial beauty, fading beauty, decaying beauty these are but expressions of partial, fading or decaying health.

An abundantly healthy individual is in perfect symmetry and proportion of body. The complexion glows and is free from blemishes, with the red blood shining through at the cheeks, fingers and toes. The hair sheens, is strong and full of life. The eyes are clear and sparkling, lips are rosy in color, the teeth pearly white, sound and even. An unmistakable look of confidence, courage, alertness, love and joy radiate upon the countenance. If you love beauty in body, mind and spirit, and desire it for yourself and for your offspring, there is only one way to attain it, and that way is to live in harmony with the laws of life.

If you possess most of these positive vibrant health qualities, you are living in accordance with natural law; if not, start on a rejuvenation health program today.

1. A healthy, normal appetite for natural wholesome foods.
2. Sound undisturbed sleep, and a zest for living upon rising mornings; free from fatigue.
3. Calm nerves, clear thinking and a steady magnetic gaze.
4. A clear, strong and musical voice in both sexes.
5. Hair that is strong, lustrous, plentiful and sheening; no dandruff or dryness.
6. A clear complexion, bright and glowing.
7. A firm, powerful and flexible grip.
8. A clear alert mind, with a good memory; no absent-mindedness or forget fulness.
9. Constructive and happy thoughts about yourself & others.
10. The attitude is confident, loving, cheerful & positive; a realist.
11. Perfect eyesight without glasses; eyes clear and sparkling; hearing perfect.
12. The tongue is pink & uncoated; the breath is sweet and clean.
13. No dark circles or puffiness under eyes.
14. A good sense of humor about yourself and others; a calm, peaceful nature.
15. A proper upright-posture & carriage; neither bent or inflexible.
16. Body weight proportionate to height and bone structure; neither thin or fat, but firm.
17. Body joints flexible & free from stiffness & calcium deposits.
18. You are taking total responsibility for all your actions, and circumstances.

3. **Reach up with your left hand, and hold on to the handle of the Big Dipper. Pour the violet light down to your personal star 4 to 6 inches above your head, in order to predigest the energy of the violet light. Then let it flow down to your crown, into the Upper Tan Tien, to be processed and flow down to the heart center (Middle Tan Tien) or to the back of the head down to C-7 (Cervical 7) and T-2 (Thoracic 2) and down to the palms.**

   In Taoism we consider that the North Star emits a violet light, which is regarded as the highest healing light and the Big Dipper as emitting a red light.

   You can do these meditations sitting, or standing in the Chi Kung posture. The standing position will support a stronger structure and provide a better connection with the earth.



Fig. 4.7 *The North Star, Big Dipper and Galaxy spiral above.*

4. Always remember to breathe in slowly so you can process the awareness of the Lower Tan Tien. Feel a suction, warmth (Chi) and continue to breathe in and be aware of the suction of the crown, North Star and Big Dipper above you.

19. Teeth are even and shiny white; gums do not bleed; no cavities and strong bite.
20. Muscles are firm, strong and smooth; an energetic springing step; athletic ability.
21. Internal organs and glands in their proper place and functioning healthfully.
22. No sensations of pain, pressure, swellings, soreness, tiredness, stress or indigestion.
23. Neither cold hands or feet; body temperature & blood pressure normal; pulse not too high or low but even & steady.
24. A grateful and thankful feeling for being alive, and appreciation for the things you now have.
25. You are orderly and precise in thought and action; neither hasty or plodding.
26. You are an independent thinker, free from dogmas, prejudices, and false notions.
27. You do follow organizations, groups, teachers or cults without question, failing to reason and thin about the truth of life by your own intelligence and creativity.
28. Your goal in life is to help other people; you are not self-centered and egocentric.
29. You do have plans and goals in life based on your own creativity and individuality.
30. You do know who you are, where you are going, and what is the purpose of your life.

Price of Health

Perfect Health is your natural right. The glossy hair, bright eyes, clear skin, active brain, steady nerves and happy disposition, together with the strength, vigor and unlimited energy of a truly healthy human being are all yours if you want them enough to pay the price. But these things cannot be purchased with money. They are not for sale in any store and cannot be found in boxes or bottles. They can be maintained or regained only one way and that is by carefully obeying the laws of nature every day. Health and beauty are born companions.

Yin and Yang of Health

In Taoist healing we are always looking at the balance between Yin and Yang as a measure of health. They say that when Yin and Yang finally separate, we have death. The Yin body returns to the Earth and the Yang spirit ascends to Heaven. Thus the work of a Taoist healer is to maintain a balance between Yin and Yang in order to preserve life. Healing is about becoming whole. In order to feel balanced and health, we have to have a flow between our Yin aspects and our Yang aspects.

Yin: Ability to stay calm; rejuvenation; detoxification; sleep.
Yang: Ability to take action; exercise; movement; zest for life.

If these are out of balance, then health problems may follow physical, mental or emotional. We can see this immediately by observing the extreme cases:

If one is excessively Yin without enough Yang, for example sitting at home on the couch all day watching TV, no exercise, no working soon enough one may suffer from overweight, fatigue and depression.

If one is excessively Yang without enough Yin, for example working long hours, spending time off working out fanatically in a gym, always rushing about and never resting sooner or later one may suffer from panic attacks, hyperactivity, sleeping problems and heart problems.

We must remember that Yin and Yang are not separate opposites: this is an over simplification of the Yin & Yang theory. Rather it is about flow. There is no problem to be busy, as long as one takes time to unwind and relax later. Likewise, there is no problem completely relaxing and being still, as long as one takes time to exercise and move later on.

Thus Yin and Yang do not have to be in balance at any one moment. But they must flow in a smooth and regular cycle for health to ensue. Just as night and day do not have to co-exist, they each have their time and flow one into the other in a smooth cycle.

In terms of health, there are some signs of imbalance that we are overly Yin (or do not have enough Yang), and others that we are overly Yang (or do not have enough Yin). Some imbalances are a result of our constitutional traits and others are due more to our lifestyle factors.

Here are some examples of symptoms that may indicate that we are becoming either overly Yin or overly Yang:

Overly Yin	***Overly Yang***
Excessively Cold	Excessively Hot
Deficient Chi	Excess Chi
Fatigued	Hyper
Weak	Rigid
Excess Fluids	Dryness in the Body
Low Blood Pressure	High Blood Pressure
Slow Respiratory Rate	Fast Respiratory Rate

Health is about harmony: smooth flow and overall balance. If we experience one of these symptoms (such as feeling cold) it is not necessarily a problem unless it is consistent and unbalanced. The more we connect to nature, the more we can see how we flow harmoniously with nature's cycles, For example, human beings naturally operate well when they are awake and active during the daytime and rest and sleep during the night. We are more comfortable if we stay in more during the winter months and spend more time in the outdoors during summer.

Thus, if you are very active during the day, this does not mean you have an overly Yang problem. But if it persists and you are unable to sleep well at night, then this indicates an imbalance, if you are cold during the winter, no problem, But if you continue to feel cold even in the summer months, there may be a deeper problem. Likewise, when we force our bodies out of harmony with nature for extended periods, we usually fall ill. A prime example is that of the night-shift worker. Even though a person may be sleeping a full 8 hours every day, if they always work at night then they are acting against the natural flow, it is not uncommon for night shift workers to begin to experience imbalances.

Yin & Yang theory gives us a model to understand health and illness that is dynamic. Many models of health make the mistake of using a static model: assuming that there is a point of good health to attain. For those seeking a static goal of health, this is very hard, indeed impossible. Our bodies are constantly changing and evolving, responding to the world around us. For example, our bodies tend to put on a little extra weight during colder months and become lighter in the summer. Thus if we are trying to stick to a single static weight, we are fighting against nature. The Oriental therapies give us a more fluid model, and yet a model with very clear ways of understanding our health and illness.

Yin and Yang of Illness

We can also view different illness in terms of Yin and Yang, though it must be remembered that this is only an approximation and does not apply to every case, in ancient times when Oriental Therapy was used, the names of diseases were often not known. A Chinese doctor would simply look at the symptoms and examine the person's energy to decide how to treat them. However, we can see that there are often similar patterns in particular diseases, and thus we can make an estimation of Yin & Yang imbalances. Always look at the individual's expression of the illness and their unique symptoms (such as heat, cold, weakness etc) before deciding.

Overly Yin	***Overly Yang***
Headaches (Front of Head)	Headaches (Back of Head)
Diabetes II	Syndrome X
Colitis	Duodenal Ulcers
Asthma	Gout
Hypothyroid	Hyperthyroid
Meningitis	Appendicitis

Excess and Deficiency

From the surface we may identify things as being overly Yin, Yang or balanced. However, in Chinese Medicinal Theory it was know that there are different underlying situations that can create each surface appearance.

An overly Yin situation may be caused by two possibilities:

1. Excess Yin
2. Deficient Yang

In other words, it may be that the person has built up an excess of Yin energies, habits or foods, or it may be that they do not have enough Yang qualities to balance their Yin. We can understand this by making simple charts to demonstrate. Balanced Yin and Yang would look like this:



Fig. 4.18. Balanced Yin & Yang

Yin may become excessive. This may be our constitutional tendency, or it may be of our behavior. For example, if we take too many cold watery foods and drinks which are Yin. It could be that we are in a very cold damp environment, and thus develop an excessively Yin situation. Therefore, there are a number of ways that we can develop too much Yin, which can be illustrated as so:



Fig. 4.19. Unbalanced Yin & Yang

The other scenario which looks externally the same is deficient Yang. This may be our constitution, or may develop out of our behaviors. For example, we may lose Yang when we avoid stimulating activities and sports. If we are lazy and sedentary, we may become deficient in Yang, or if we do not spend enough time with other people we can develop a deficiency. Deficient Yang may be illustrated as so:



Fig. 4.20. Unbalanced Yin & DeficientYang

Thus Excess Yin and Deficient Yang look externally the same, but under the surface there is a slightly different cause. Excess is always the result of too much of something (e.g. too many iced drinks) and deficiency a result of a lack (e.g. not enough exercise).



Fig. 4.21. Excess Yin & DeficientYang

The same can be found when we examine and overly Yang situation. This has two possibilities:

1. Excess Yang
2. Deficient Yin

It may be that the person has built up an excess of Yang energies, habits or foods, or it may be that they do not have enough Yin qualities to balance their Yang. An excess Yang situation may be constitutional, or it may be the result of too many Yang foods, exercises and habits. For example, if we eat too many rich and spicy foods then we can develop Excess Yang. It can be illustrated as so:



Fig. 4.22. Deficient Yin & Excess Yang

Deficient Yin maybe a constitution or we may develop it from not nourishing our Yin qualities. For example, if we do not take enough rest, do not take enough time alone and do not surrender into relaxing pasttimes we may develop a lack of Yin. This can be Illustrated as so:



Fig. 4.23. Lack of Yin & Excess Yang

Thus we can see that from the surface level, Excess Yang and Deficient Yin look the same, though they have different underlying patterns.



Fig. 4.24. Excess Yang & Deficient Yin

Therefore, in Oriental Theory, we distinguish between different underlying patterns so that we can understand the situation even deeper and know how to respond to it in an appropriate way.

Yin and Yang Types

Thus we can find two main different types: the Yin and the Yang. But when we look deeper we find four different subgroups. The following table shows the four different groups identified in Yin & Yang diagnostics:

	Overly Yang	***Overly Yin***
Yin Imbalances	Deficient Yin	Excess Yin
Yang Imbalances	Excess Yang	Deficient Yang

The external appearances are two groups: Overly Yang and Overly Yin. The internal imbalances may take four different forms, depending on whether it is a predominantly Yin imbalance or a predominantly Yang imbalance. Understanding our health problems from this perspective can help us to gain deeper insight into the nature of our issue, and of how to remedy it.

Theory in Practice

These theories are used directly in the practical application of Oriental Therapies. To a certain extent we can treat simply Overly Yin and Overly Yang situations the same, However, this deeper insight can give us even more understanding of the current imbalance and thus show us how we can treat the situation even more effectively. Oriental Therapy has many applications. Acupuncture, Chinese Herbs, Massage, Medical Qigong and Shiatsu are all based on the same theories.

However, the focus of this book will be on Nutritional Therapy. This can be used alone or combined with other treatments. Ancient Taoist theory is the foundation for two popular nutritional systems: Macrobiotics and Five Element Nutrition. Macrobiotics is concerned with the balance and harmony between Yin and Yang; whereas Five Element Nutrition looks with more details into the health of each organ system. Macrobiotics has been highly developed in Japanese culture, whereas Five Element Nutrition is more widespread in China. Both can be used alone or the systems can be integrated.

Chapter 5

Increase your Life Force

How to eat, when to eat, what to eat and where to eat are some of the basic questions people ask when starting a program of natural eating. We all should eat to live, not live to eat. An old Chinese proverb says: When feasts are spread the doctor rolls his pills. In fifty dishes lie a hundred ills. Most people today live to eat and they end up with enormous medical bills for all of their ills.

The three vital functions of food are to rebuild the living tissues; to supply energy; and to preserve a proper medium in which the biochemical processes of the body can take place.

We might add that the food must be in an assimilable form and that the combinations of food must be correct in order to insure perfect digestion. Otherwise, fermentation and gas will result from faulty combining. Here then are the rules of how to eat.

Twelve Keys to Good Health

1. Eat only when hungry stop before full.
2. Proper Acid and Alkaline and Yin and Yang balance.
3. Chew your food well mix thoroughly with saliva.
4. Refrain from eating when emotionally upset or physically exhausted.
5. Eat food at room temperature.
6. Use fresh natural organic raw and cooked foods daily.
7. Fasting or Eliminative Diet when necessary.
8. Combine food properly.
9. Refrain from close eye or brain work before, during, or after meals.
10. Consume your last meal at least three to four hours before bedtime.
11. Keep cheerful and calm at meals.
12. Follow the Law of Moderation (rhythm). Never overeat.

Eat Only When Hungry

Do not eat unless you have absolute hunger. True hunger is a mouth and throat sensation. The mouth waters when true hunger is present. True hunger is not stomach pangs or that empty feeling at the pit of the stomach. These symptoms are a form of addiction to highly seasoned and stimulating foods, such as meat products, coffee, salt, spices, and alcohol. When these foods are eaten they create withdrawal symptoms and the body again craves them with a burning desire. True hunger leaves the body in a relaxed state with no morbid cravings for junk foods. Eat only to satisfy hunger, no more. Hunger is the true spice of eating.

A completely full furnace smokes and will not readily burn. The stomach acts in the same manner; when completely full, it will not digest the excess load of food, but instead will ferment and putrify, poisoning the body and causing toxemia. A furnace not quite full will burn beautifully. The stomach, not quite full, will also burn (digest) beautifully. Overeating causes malnutrition. Surveys taken on individuals living past the age of 100, never fail to show that they are always moderate eaters. The glutton will never reach the age of 100. If you are not hungry at meal time or in the morning, skip that meal and you will enjoy your next meal. Eating three full meals a day, in most cases, overworks the digestion and internal organs. Listen to that small inner voice within you. It will tell you what to eat, how much to eat and when to eat; and you will seldom go wrong. Never eat between meals. Eat a meal, then do not eat again until you experience true hunger. Your stomach will thank you. To lengthen your life, lesson your meals. Who is strong? The ones that can conquer their bad habits.

Proper Acid/Alkaline & Yin/Yang Balance

Alkaline quality foods are classified as all watery type fruits, vegetables and their juices. To achieve Yin and Yang balance, simply consume the foods grown near or in the climate in which you live and in season. Use more cooked grains, legumes, vegetable stews and soups in the winter, and eat more raw food during the summer months.

D. Linking Personal Stars, Energy Bodies and the Universe

Be aware of your ‘personal stars’ above and below and connect to other peoples’ stars and energy bodies.

Three minds unite, one mind aware of the stars above you and a star below you. Connect these stars to the people around you. Think about the bright light above the crowns of other people. Start to spiral your energy to connect to each of them. Group all the stars into one energy body and connect all the way to the center of the universe.



Fig. 4.8 *World Link Meditation*

Alkaline Foods (General Percentages)

Summer	60% to 70%
Winter	25% to 35%
Fall	50% to 60%
Spring	50% to 60%

The Yin and Yang Balance is a different ratio and will be discussed in another Chapter. The foods falling into the Acid quality are all proteins, starches, fats and sugars, i.e., all nuts, seeds, cheeses, bread, potatoes, rice, oils, dried and sweet fruit, like dates, raisins, figs, bananas, etc.

Acid Foods (General Yearly Percentage)

Summer	30% to 40%
Winter	65% to 75%
Fall	40% to 50%
Spring	40% to 50%

Listen to your inner bodily needs; you may require more or less of the Acid foods at different times. All heavy type foods are acid forming and they show up acid on the pH urine scale. Also, eat sparingly of fats and sugary type foods, i.e., honey, dried fruits.

The human body requires just the right amount of proteins, starches, sugars, fats, minerals, vitamins and liquids. An excess or deficiency of any one food element, over a period of time, can cause acute, chronic or deficiency diseases, i.e., diabetes, cancer, obesity, high and low blood pressure, emaciation, hypoglycemia, schizophrenia etc. A balanced and moderate amount of all food elements, coupled with physical fitness, is the master key to good health, nutrition and longevity.

For example, too much protein damages the kidneys, ages the cells and tissues, pollutes the blood stream with uric acid and toxins. A deficiency of protein atrophys the kidneys, causes anemia, falling hair, emaciation, fatigue and mental depression.

An excess of starch injures the liver, causes nerve depletion, constipation, skin eruptions and mental fatigue. A deficiency of starch causes cold hands and feet, weight loss, a nervous and irritable condition, loss of energy and lack of body heat during cold weather.

All sugars eaten to excess impair the pancreas, kidneys and causes poor eyesight, falling hair, tooth decay, impotence, schizophrenia, paranoia and premature aging.

An excess of fat overworks the gall bladder and liver, and together with refined sugar raises the blood cholesterol. Fat is difficult to digest if eaten in excess of the bodily needs, and causes anemia, skin problems and obesity. A deficiency or an excess causes nerve disorders, falling hair, poor eyesight, lack of body heat and general fatigue.

Vitamins and minerals are essential in preventing various deficiencies and diseases. Lack of adequate vitamins and minerals has caused such deficiency as: beriberi, pellagra, rickets, scurvy and others. Severe mineral and vitamin depletion can be fatal An excess of minerals and vitamins can cause disease. Likewise, an excess of vitamin and mineral supplements in megadoes can be dangerous. Consult a competent health doctor of nutrition to advise you on their use.

Learn to listen to your inner bodily cravings for the proper amount of proteins, starches, sugars, fats, vitamins, and minerals; this will lead you to health and longevity.

Masticate & Salivate your Food

Indigestion is a universal malady. One of the main causes of stomach ailments is bolting food in a hurry. Nothing ages one faster than this pernicious habit. The stomach has no teeth to break up large particles of food. Nature has endowed man with a set of teeth to break down food into fine, almost liquid particles, so that the digestive enzymes and juices may easily mix with it. Sufficient mastication and salivation of all food, including liquids, insures healthy and thorough digestion and assimilation. Mastication allows us to enjoy and taste our food to the highest degree. Eating should be a pleasurable experience. Swallowing and hurried eating never allows one to really enjoy their meals. Adequate chewing enables one to eat less and to digest, assimilate and utilize their food better. Chew your food to a liquid then drink it, your stomach has no teeth; and also, chew your liquids.

Never Eat When Upset

Animals will not eat if wounded, sick, excited, frightened or maddened. Working under mental or physical strain will retard or suspend digestion. Never eat during a fever, as it will only feed the fires. Eating food when upset or under physical strain will cause faulty digestion and the result is toxemia. Eating under these adverse conditions slows down and impedes the peristaltic action of the stomach and its juices. The rule is then, when sick or in distress, stop eating until normal hunger returns. Rest, and a short fast will be the only remedies.

Eat Food at Room Temperature

Cold and hot food suspend digestion for some time. A great amount of body energy is wasted by this ill-habit. It is best to allow food and drink to reach room temperature before consuming it. In China one of the causes for failing to achieve longevity is considered to be the use of ice in food and drink.

Cooked & Raw Foods Daily

Eat according to season, climate and weather variations. Eat some cooked and raw food daily. Consuming only 100% cooked or 100% raw food exclusively is not conducive to vibrant health.

Consume more cooked grains, legumes and vegetables during the winter; and more raw foods during the summer.

Fasting or Eliminative Diet

A fast or an eliminative diet, when necessary is an excellent way to cleanse the body. Fast 3 to 5 days on distilled water with plenty of rest and fresh air, followed by a day of fruit. The eliminative diet of three days on watery fruits or vegetables or juices will bring superb health results. Refer to chapter on fasting and eliminative diet for more details. A temperate diet arms the body against all external accidents, so that they are not so easily hurt by the heat, cold or labor.

Combine Food Properly

The body and blood chemistry can easily be upset by continually consuming improper and incompatible food combinations, i.e., raw fruit with starch foods and fruit with animal protein are the most inharmonious combinations. See chapter on food combining.

Avoid Close Work during Meals

This is so important that it will add many years to your life. Oxygen is necessary to properly digest and assimilate the food eaten. Performing close work or reading or staying indoors after eating will hinder digestion and result in poor eyesight and other ills, because close work diverts the blood out of the stomach and into the head and brain area, causing a lack of blood for proper food digestion. After meals, go out into the open air and look into the distance. This will relax the entire nervous system resulting in improved digestion, assimilation and better health. Never lie down after eating, because the digestive juices do not flow freely in this position, and results in fermentation and gas. Too many people, including Health Culturists, are wearing glasses and weakening their eyes, because of the practice of not resting the brain and not getting fresh air after eating.

Eat your Last Meal 4 Hours before Bedtime

The body has the least amount of energy and vitality at night, which prevents the proper digestion and assimilation of foods eaten at a late hour. Good sound sleep is necessary for the repair of the cells, tissues and organs of the body. Eating a heavy meal at night before going to bed prevents the body from repairing and replenishing itself from the daily activities.

By evening, the body's energy has been mostly expended. Because of this low energy flow, the food consumed in the evening hours should be relatively light and easy to digest. After sunset, the ionic charge of the atmosphere drops, and the later one eats, the more likely the food is to be improperly digested. The last meal of the day should be taken on or before sunset. If you are hungry later in the evening, eat an apple or pear, or a few grapes and berries. Heavy food eaten before bedtime causes muscle twitching and cramps. Yellow and bilious skin can be attributed to this practice, as well as anemia and poor circulation.

This faulty habit weakens the vital organs and uses up a large amount of energy, causing a lack of good sound sleep. The best time to eat the heavier foods is earlier in the day, when the body has the vital energy to digest and assimilate the food properly. The average person does just the opposite; they eat a big meal just before bed time. No wonder there are so few magnetically healthy people around today. An abundance of energy can be yours when you learn to obey nature's laws.

Be Cheerful and Calm at Mealtime

Anger, hate, anxiety and worry stop digestion. At meal time keep calm and think about the lovely and beautiful things in life. Above all, enjoy your meal, and do not become a hypochondriac over your health or natural eating, learn the rules, practice them always, make them your habit, and then take up a worthwhile hobby or profession with the zest for living and doing.

These little secrets of correct eating may not seem like a big deal, and you may want to neglect them, but we can assure you they are very important for the maintenance and preservation of your health and happiness.

Moderation is the Key to Health and Long Life

Moderation is the natural law of temperance, not only in eating and drinking, but in sleeping, working, exercising, studying, meditation and all other activities. Overdoing anything in life tends to weaken ones vitality and physical powers. Excessive sleeping can make one sluggish, lazy and dull; the proper amount of sleep revitalizes and rejuvenates the body for daily activity. Excessive exercise, work or mental activity can lead to nerve and adrenal exhaustion, and the consequent loss of personal magnetism, vitality and health. If one lives within these magnetic margins (moderation) they can build a reserve energy supply to cope with any stress or heavy physical or mental emergency situation.

Moderation in all of the healthy activities and functions of life is the key to attaining vitality and good health. The ancients teach us that one cannot be moderate and attain good health and spiritual development by even the smallest use of drugs, alcohol, dope, sugar foods, smoking, lying, cheating, hate, anger, or swearing etc. Any amount of these negative habits in ones life are harmful to the spirutual and physical body and cause untold misery and suffering. They are contrary to the Tao and the order of the universe.

Sleep, activity and proper eating habits are the three most essential functions of life. When any one of these essentials are out of balance in some degree, one must suffer the consequences.

We learn through experience, and if we have suffered enough and learned our lessons well, we may alleviate our sickness and self-induced misery. Natural law will not be violated with impunity; the rich and poor are equal in respect to the Yin and Yang laws that govern physical life.

Remember these Suggestions on Moderation:

Eat only when hungry and stop before full.
Drink pure liquids when thirsty.
Rest or sleep when fatigued or exhausted.
Exercise daily, with moderation.
Cultivate cleanliness of body and mind.
Study and read when alert and willing.
Maintain a poised, confident, cheerful and thankful attitude.

Happiness and Laughter are Medicines

Chinese Taoist physicians say that the liver churns and exercises when we laugh. The liver circulation is quickened, the respirations are deeper and more profound, and we feel warmer all over. Mirth promotes digestion, while gloom and depression of spirits will produce dyspepsia and indigestion. He or she who is habitually joyful, calm and happy will generally possess good health. A philosopher once said that he would always trust one who whistled while working.

It is impossible to reach old age with a bad stomach. There is a great deal of truth in the statement that a good stomach is not affected by aggravations, sadness, or insults. All these emotions affect primarily the stomach. Of all man's functions that affect the body and soul together, laughter is the healthiest. Laughter aids digestion, circulation, sweating, and has a refreshing effect on the strength of all organs.

Cheerfullness and gladness are not only of value in preserving health, but they are of equal service as a remedy in disease. No one should visit a hospital who is gloomy or despondent; the patient will pick up the vibrations and feel more depressed and ill.

A calm, happy, and positive attitude lifts the soul and body, and inspires all who come in view of such a person. The longest lived and healthiest people throughout the world are always happy and full of inspiration and good cheer. Health is the most precious jewel and greatest possession upon earth.

Health Wisdom of Benjamin Franklin

To lengthen your life, lessen your meals. I saw few die of hunger; of eating, 100,000. Eat to live, and not live to eat. A full belly makes a dull brain. Hold your council before dinner; the full belly hates thinking as well as acting. He that never eats too much, will never be lazy. Eat few suppers, and you will need few medicines. Many dishes, many diseases; many medicines, few cures. Hunger is the best pickle. To live long it is necessary to live slowly. Wish not so much to live long, as to live well. Keep out of the sight of feasts of banquets as much as possible. If a man casually exceeds (overeats), let him fast the next meal, and all may be well again. A temperate diet frees from diseases and illnesses. Early to bed and early to rise, makes a man healthy, wealthy and wise. A sober diet makes a man vigorous; it preserves the memory and helps the understanding; it makes the body a fit tabernacle of the Lord to dwell in. Drink does not drown care, but waters it, and makes it grow faster. He is the best physician that knows the worthlessness of most medicines. Health is not lost by accident, not can it be repurchased at the drug store. It is lost by physiological errors, and can be regained only by erroring no more. Disease is nature's protest against a gross violation of her laws. The reward for service is more service.

Food Combining made Easy

You are what you eat is an old health saying that is only partly true. More importantly, you are what you digest, assimilate, absorb and utilize. Our total health depends, not only on what we eat, but how efficient our digestive and assimilative powers are. Understanding proper food combining can make a tremendous difference in our over-all health and well-being. It can even extend our lives far beyond the average, and slow down the aging process.

Most people consume food indiscriminately, that is, without regard to what happens to the incompatible food mixtures when they reach the stomach, i.e., gas, flatulence and indigestion. It is not necessary to get bogged down in strict unbending food combining rules in order to achieve good health. One need only apply a few important combining principles, as outlined here, to obtain excellent health benefits.

Eight Food Combining Principles

Most Important Food Combining Principles:

1. Salads should not be eaten before protein or starch (beans, grains), always with or after these foods. Food is digested much easier when eating from Yang foods to Yin ones. Protein and Yang foods require plenty of stomach hydrochloric acid for proper digestion. If one eats Yin salads, fruits or other light carbohydrate foods first, for which hydrochloric acid is not needed, and protein/ Yang foods are eaten last, the Yin foods will interfere with protein/ Yang food digestion because of diminished hydrochloric acid in the stomach. Therefore, when eating a grain/bean dish, cheese, yogurt etc., eat them before or with the vegetable salad, never after. One can alleviate much gas and indigestion by eating in this manner. The body secretes enzymes and hormones at all times on a healthy and well balanced diet: there is no need to eat salads first in the meal to supply any missing enzymes to digest protein or Yang foods.

2. Many foods, such as grains and beans contain both protein and starch, which are the principal foods of people worldwide. Eaten in moderation, protein and starch foods are not incompatible, as some erroneously believe. Complex carbohydrate foods, in fact, have a sparing effect on protein foods, thus saving the protein for its hormone and tissue building work. Complex carbohydrates, like grains, beans and root vegetables are energy and heat producers. If an insufficient amount of these are eaten with a protein, the protein is then used as a secondary source of energy and heat which requires extensive energy conversion and deprives protein of its main function hormone and tissue repair. Generations of healthy people have eaten protein and starch foods at the same meal. Nature produces a variety of protein and starch mixed foods, such as wheat, peas, beans, corn, buckwheat, potatoes, seeds, nuts, rye and all other grains.

3. Acid and sub-acid fruits combine fairwith pure protein foods, such as yogurt, cottage cheese, buttermilk, raw milk, eggs, etc. Milk always curdles as soon as it is mixed with the gastric juice, and this is a help rather than a hindrance to digestion, as it would leave the stomach too quickly if it remained in the fluid state. Fruit acids are mild compared to gastric secretions, therefore, they will not interfere with the digestion of a pure protein food eaten in moderation. This mixture can be eaten more in hot weather or tropical climates.

4. This is the most important food combining principle to follow! The worse combination of all is mixing acid or sub-acid fruits with starch foods, such as beans, bread, grains. The acids in the fruit impede starch digestion considerably, causing fermentation and gas. It is best to eat fruit alone. Stewed or baked fruit with a starch meal, however, will not cause any problems. Cooking fruits diminish their acids, and can be eaten occasionally with grains or other starch foods.

5. Avoid protein and sweet fruit or any other sweets, such as honey, sugar, corn syrup etc. Sweets inhibit stomach secretions (hydrochloric acid), and result in poor protein assimilation and digestion, along with fermentation and gas. Sweet fruits, such as melons, bananas and dates should be eaten on an empty stomach. You may eat fruit or melons in the morning, at least one-half hour before a protein or Yang food meal. Fruit for breakfast gives the stomach natural bulk and acts as an intestinal cleaner and eliminator.

6. Foods rich in fat, especially high fat cheeses, meats, nuts, milk, oils, butter, etc., inhibits the flow of gastric secretions, slows down digestion and delays the emptying of the stomach by several hours. If an excess of fatty foods are eaten at one meal, there will be digestive problems.

7. Avoid sulphur foods, such as onions, garlic, leeks, etc. at the same meals with sweet foods, such as fruits or honey. Stomach pains, gas, fermentation and indigestion can easily result from this poor combination.

8. The three most important points to remember are to: a) never overeat at mealtimes; b) eat only when truly hungry; and c) limit the combination and variety of foods at a meal 3 or 4 items per meal are sufficient for health and nourishment. Generally, the more foods that are mixed at one meal, the more digestive trouble one will have. Keep your meals simple, but delicious and nutritious. Eat to live, and not live to eat. With many dishes, comes many diseases.

Help for Weak Digestive Systems

Those with very weak digestive systems will benefit greatly by eating only 1 or 2 foods at a meal, thus lessening the burden on the entire digestive process. If you are sick, eat only one meal per day until your digestion is back to normal; it usually takes about one week to get back your normal digestion. The one meal per day plan can include cooked grains and vegetables in winter and a sub-acid fruit with the seed/nut milk or fruit alone; or cultured raw dairy products alone.

Food Combining Groups

Try to follow these simple food combining principles as much as possible but do not become a fanatic over the subject of food combining and nutrition. When visiting friends, relatives or restaurants, do not become a food combining crank by lecturing others on dietetics. Do not give advice unless asked, and then give just a little. Listen more and talk less no one likes a know-it-all. Extend the freedom onto others to do as they wish. Living by example is a far better teacher than excessive talking or preaching. Be careful of giving advice wise people do not need it, and fools will not heed it anyway.

The following is a list of food classifications and food combining groups, to be used at your own discretion, according to your individual needs and requirements. The food we eat is as important as the most potent medicine, even more so. For what we eat becomes part of us, part of our blood, our heart, our brain.

Million Dollar Minerals

Are you timid and shy? Do you constantly worry and show fear? Are you easily discouraged? Do you bite your nails? Are you anemic, weak, underweight or overweight? Are you a negative thinker? Is your memory poor? Why are some people serene, dynamic and vital? What makes certain women kissable at any age? Why is fear unknown to others? Why can some people sell snowballs in Alaska while others cannot sell water in a desert? Why can some men and women entice the fortunes of life to themselves? What is it? What is the secret of Super Health, Youth and Vitality?

The answer to these often asked questions lies in the powerful mineral elements that compose your body. You will learn all about these miraculous vital mineral elements how to use them harness them direct them and transform your life with their life giving power. These body elements must be raised through plant life, not given in drugs, to become yours. Most of us who study, work and read, are hungry for those tiny units of power the sixteen mineral elements.

1. Center Channel and Personal Star above


Soul, personal star or higher self
Upper Tan Tien (Upper Brain) is the Center of Observation.
Middle Tan Tien (Middle Mind) is the Center of Consciousness.
Lower Tan Tien (Lower Brain) is the Seat of Awareness.
Connect the Central Channel to the Upper and Lower Universe.

Fig. 4.9 *Connect Heaven to Earth using the Central Channel.*

2. Use Yi power to connect to your Personal Star above


Personal Star
Observation
Consciousness
Awareness
When the abdomen fills with Chi it will rise up and fill the upper brain. Connect to your personal star, six inches above your head.

Fig. 4.10 *Connect to your Personal Star Energy using 'Yi' Power.*

Group A: Proteins

Nuts & Seeds
Dairy
Beans & Peas
All Meat
Eggs

Group B: Starches

All Grains
Potatoes
Cauliflower
Pumpkin
Turnips
Carrots
Legumes
Chestnuts
All nuts
Beets
Parsnips
Bananas
Rutabaga
Bread

Group C: Fats

All Oils
Butter
Cream
Milk
Margarine
Avocado
Olives
Nuts
Cheese
Fat Meats

Group D: Acid Fruits

Orange
Pomegrante
Lime
Pineapple
Sour
Tomato
Grape
Lemon
Grapefruit
Sour Apple
Strawberry
Plum
Sour
Tangerines

Group E: Sub-Acid Fruits

Pear
Apple
Peaches
Blackberry
Raspberry
Nectarine
Papaya
Huckleberry
Grape
Guava
Quince
Blueberry
Figs
Plum
Apricot
Mango

Group F: Sweet Fruits

Fresh Raw

Bananas
Cantaloupe
Watermelon
Crenshaw
All Melons
Persimmons

Dried Fruit

Peach
Plum
Apricot
Pear
Apple
Pineapple
Figs
Dates
Raisins
Prunes

Group G: Non-Starchy Vegetables

Alfalfa
Garlic
Chard
Okra
Chicory
Celery
Sorrell
Leeks
Sweet Pepper
Asparagus
Zucchini
Squash
Bamboo Shoots
Eggplant
Cabbage
Artichoke
Broccoli
Fresh Peas
String Beans
Radish
Kale
Cucumbers
Brussel Sprouts
Water Chestnut
Escarole
Spinach
Mushrooms
Lettuce
Parsley
Watercress
Sprouts
Onions

How to Combine the Groups:

Group A and Group G: Good
Group A and Group D: Fair
Group B and Group C: Fair
Group A and Group F: Poor
Group D and Group E: Good
Group B and Group D: Poor
Group B and Group F: Poor
Group A and Group C: Fair
Group B and Group G: Good
Group A and Group E: Fair
Group C and Group G: Good
Group D and Group F: Poor
Group E and Group F: Good
Group B and Group E: Poor
Group A and Group B: Fair

Fig. 5.1. Food Combining Groups made Easy.

Glamorous Minerals

Charm your world with sulphur and iodine. Master your world with calcium and fluorin. Laugh with your world with silicon and potassium. Prosper in your world with manganese, iodine, calcium and phosphorus. Entertain and fascinate your world with sodium, magnesium, Iodine and chlorine. Love your world with iron, copper, phosphorous and potassium. Be self-confident in your world with all the powerful minerals which regulate our social, mental, health, business and esthetic life.

Many business executives have conquered their nerves and fatigue as well as other serious deficiencies by using all twelve of the body minerals. Some perpetually tired people may be hungry for only iodine, sulphur, phosphorus and manganese, to reenforce their vital system. Arthritic sufferers are hungry for sodium, chlorin, iodine and sulphur. Diabetics need sodium. Fearful, timid people need calcium, fluorin, iodine and oxygen, attracted to the body by the use of potassium. Those low in muscular power need Vitamin C with potassium, sodium and chlorin. Sad, melancholy and easily infected types need silicon, fluorin and iodine. Only a little lack brings disastrous consequences.

Through very small amounts of these precious elements are contained in the normal body, they have tremendously important work to do. The mineral elements work hand in hand with the glandular system. Nature placed these elements in the soil and not upon the drug shelf. More powerful than drugs in lasting nourishment, they provide the spark of life, the immunity against disease, the enthusiasm of youth, the endurance of health, the enchantment of well-being and calmness. To neglect them in our diet is to turn our face from bountiful supply in nature.

Only a tiny amount of copper, yet that mineral is like an electric dynamo charging complexion, hair, blood stream, and even the intestinal tract with an essence which enables other minerals to give forth their benefits. Copper, manganese and iron are an unbreakable corporation in the financial affairs of body chemistry. They are needed by tired mental workers, who are low in drive, energy and easily fatigued.

Phosphorus, calcium, silicon, and fluorin hunger are found in tuberculosis. Fluorin starvation means erratic characteristics, infections, premature aging and greying. Potassium hunger is found in those with no come back, no resilience of muscle, and those who suffer with intestinal atony. Sodium, chlorin and potassium assist assimilation and elimination. Sulphur, queen of enthusiasm, beauty and golden nerves, yet taken without balance, a Vesuvius of drying, scorching irritation. Magnesium and silicon, diplomats of optimism and poise, who never let one down. Iodine, the confidence artist, the clever, original life enjoyment chemical which turns back the clock toward youthful appearance and ambitions. You may combine iodine with any of the other minerals which you lack because it accelerates assimilation.

Power of Minerals

Minerals are found in small quantities within the body, about five percent, but they are vitally important to your health and well-being. They have very individual and distinct physiological functions to perform. They are necessary to the life process of plant, animal and man. These precious little minerals preserve our life, repair our tissues and bony structures. They impart firmness, form and grace to our body. Without them, our glands would stop functioning, because the glands maintain metabolism, secretions, digestion, mental activity and all physiological functions. The body fails to rebuild, repair and regenerate without an adequate supply of these dynamic little wonder-workers.

They give us vital electricity and magnetic power, ceaselessly working to recharge physical and mental batteries; and they carry the life sustaining oxygen to all parts of the body. They provide the spark of life and immunity against disease and poor health.

They are powerful neutralizers of toxins and wastes, purifying the blood and casting out of the system, uric acid and other poisons. They are the natural healers and give the body vital resistance and immunity against so-called germs of disease.

Raw fruit and vegetable juices contain the organic minerals the body can use. The cholrophyll found in the green coloring matter of plants, made into juice, is a superior storehouse of these vital mineral elements. They aid the body in producing and sustaining the supply of internal hormones, enzymes and secretions to keep you youthful and zestfully alive. They are necessary for the proper digestion and assimilation of proteins, starches and fats.

Our bodies are composed of these ***16 Mineral Elements***, primarily, plus over ***30 Other Trace Minerals:***

Iron
Silicon
Calcium
Phosphorus
Sulphur
Fluorine
Sodium
Magnesium
Chlorine
Iodine
Manganese
Potassium
Oxygen
Carbon
Nitrogen
Hydrogen

Our cells are constantly being used up and repaired daily, and this repair comes from within. Minerals and vitamins require daily replenishment. They supply the body through the bloodstream, therefore, the blood must contain and deliver all sixteen mineral elements that the body vitally needs and is composed of. Without all of the 16 elements, the body fails to function properly, hence sickness and poor health will follow. There are also over 30 trace mineral elements needed in small quantities by the body.

Wholesome, organic and natural foods adequately supply the body with minerals. However, if mostly unnatural and devitalized foods are eaten, only a small fraction of the requirements are supplied, resulting in severe mineral starvation and depletion, leading to ill-health, depression, fatigue and the common low-energy symptoms.

Minerals and Richest Food Sources

Iron (Blood Builder Mineral): It is an oxygen carrier in the blood and is found in the hemoglobin of the red blood corpuscles. Anemia cannot be present when the blood has a good supply of Iron flowing through it. Iron in the blood allows you to utilize the oxygen out of the air. The thyroid is considered the oxygen gland and iron helps the thyroid gland, along with the oxygen, to eliminate the cellular wastes, use them up, and make our foods in the body ready for blood assimilation. Iron imparts strength, vitality, courage, warmth, creativity and mental power. It gives you ambition to succeed and to be a live go-getter.

Inorganic Iron, as found in drugs, irritate the kidneys and cannot be assimilated by the body. Organic Iron, as found in natural foods, builds rich red blood. Anemic, pale, thin, depressed and sick people need large quantities of Iron from quality organic products. The lack of Iron brings on sleeplessness, irritability, neurasthenia, starvation, disease and unhappiness. If you want success, happiness and love to be a part of your life, use organic iron-rich foods.

Food Sources: Spinach, sorrel, lettuce, cherries, grapes, raw egg yolks, sunflower seeds, strawberries, asparagus, cucumbers, rye, goat cheese, blackberries, blueberries, apricots, lentils, currants, pomegranates, prunes, carrots, walnuts, figs, apples, wheat, pumpkins, tomatoes, radishes, cabbage, onions & chard.

Silicon (Optimism Mineral): It makes you happy, joyful and zippy. It builds the bones, hair, teeth, eyes, nails, eyesight and improves the complexion and is needed in the structural system, membranes and arterial walls. It brings beauty and firmness to the cells and tissues. Silicon is a good antiseptic, alkaline in composition. It is a great body toner and builds up body resistance. People plagued with sexual weakness, tumors, bad circulation, liver problems and constipation are in need of Silicon. Skins of fruits and vegetables and the outer coats of whole grain cereals are high in Silicon.

Food Sources: Whole wheat, seeds, oats, barley, figs, strawberries, apples, grapes, cherries, peaches, carrots, greens, walnuts, almonds, rye, onions, spinach, egg yolk, asparagus and lettuce.

Calcium (Will Power Mineral): It gives strength and durability and maintains the bone structure. It builds teeth, nails and steadies the nerves. It adds strength and firmness to the arteries and pulse. Calcium imparts endurance, will power, good memory, strong bones and teeth. It heals wounds and neutralizes toxic acids in the system. It is needed for concentration and strengthens the heart and courage. Calcium is destroyed in the body by white flour products, white sugar, candy, etc. It extends life and prolongs youth. Pregnant women need Calcium to produce healthy children and to maintain health. The infant will draw the Calcium from the mother's bones if she has a lack of it in her diet. Lack of Calcium brings on rotten teeth, rickets, anemia, weak & soft bones & diseased bodies. Calcium requires Vitamin D for proper assimilation.

Food Sources: Goat milk, egg yolk, Canadian wheat, kale, swiss cheese, buttermilk, green vegetables and juices, garlic, oats, lemons, oranges, berries, cabbage, dates, prunes, apricots, sesame and sunflower seeds and cauliflower.

Phosphorus (Brain and Nerve Building Mineral): Stimulates powerful mental thought and brain activity. It helps promote digestion, and better metabolism of carbohydrates and fats. Phosphorus works along with calcium as a bone builder, assisted by Vitamin D. The diet should consist of 2.5 calcium to 1 phosphorus to maintain a healthy ratio within the body. People eat too much phosphorus and consequently need to increase their intake of calcium.

Lack of this magic mineral will make you look old, but it maintains your youth if eaten daily. Lack of phosphorus can cause nerve and brain disorders, fatigue, weakness and poor elimination.

Food Sources: Almonds, rye, egg yolk, wheat bran, rice bran, goat cheese, turnips, soy beans, oats, barley, seeds, nuts, peas, beans, lentils, buckwheat, asparagus, yellow corn, parsnips, whey, cauliflower and kale.

Sulphur (Sex Appeal Mineral): It cleans, tones and purifies the system, feeds the nerves and gives life and beauty and an abundant growth of hair. Sulphur is associated with insulin, the hormone secreted by the pancreatic gland to properly digest carbohydrates. It throws out body impurities and promotes bile secretions, enabling the liver to utilize all food minerals. It promotes better bowel action and helps manufacture hormones for the generative system. It increases feelings and emotions. Lack of Sulphur produces dull brains, poor blood, lustreless hair, impotence, nervousness.

Food Sources: Cabbage, onions, garlic, radishes, raw egg yolk, asparagus, almonds, chestnuts, cauliflower, kale, brussel sprouts, pecans, mustard greens, broccoli, leeks, horseradish, string beans, endive, thyme and figs.

Sodium (Youth Mineral): It cleanses and sweetens the body. It builds the glands, ligaments and blood. Sodium neutralizes acidosis, helps digestion, overcomes fermentation. Prevents hardening of the arteries and joints. High strung people need this mineral in abundance. It improves good nature in the personality. Lack of Sodium results in catarrh and congestion and slows the mental processes. Depressed, discontented and downhearted people are usually deficient in it. Increase your Sodium intake and watch yourself become optimistic and contented.

Food Sources: Celery, carrots, asparagus, seeds, beets, pumpkin, squash, apples, cherries, egg yolk, berries, turnips, spinach, rice, goat cheese, black figs, string beans, oats, dandelions, whey, radish and goat milk.

Magnesium (Nerve Relaxer Mineral): This wonderful mineral calms and steadies the nerves, relieves mental fatigue. It helps keep the brain and emotions cool and calm. It relaxes the nerves and has a laxative effect. It is a sleep enhancer; calms irritatility and hot tempers. It helps overcome constipation and toxemia. Magnesium has recently been found to activate about 30 enzymes within the body and helps to metabolize protein, starch and fat. It also promotes vitamin and hormone activity. Lack of Magnesium leads to hysteria, nerve disorders, insanity, constipation and fainting spells. It protects against strontium 90 fallout in the air. City tap water (high in fluorides) will immobilize the usable magnesium in the body. Drink pure distilled water and be safe.

Food Sources: Nuts, seeds, whole grain foods, greens, peas, beans, almonds, apples, brown rice, goat milk, raw egg yolk, whole barley, black figs, walnuts, apricots, wheat, dandelion, garbanzo peas, pomegranates and corn.

Chlorine (Body Cleanser Mineral): It purifies, cleanses and cleans out body waste. It disinfects, freshens and sweetens the entire system; promotes joint agility and flexibility; cuts down fat and auto-intoxication. Lack of Chlorine may cause mucus, fear, anemia, depression, kidney problems, indigestion and no ambition to succeed.

Food Sources: Beets, red cabbage, cucumbers, spinach, radishes, sea salt, goat cheese and milk, carrots, egg yolk, lettuce, olives and pears.

Iodine (Thyroid Regulator Mineral): It normalizes the metabolism and protects the brain and nervous system from body toxins. It is a natural germicide, protecting, balancing and immunizing the internal system. Iodine nor-malizes the body weight through the function of the thyroid gland. The thyroid produces a horhome called thyroxin containing 65% iodine. Thyroxin controls the glandular secretions and the heat and energy production in the body. It helps digestion and assimilation. It slows aging and prolongs life. Iodine detoxifies the cells and tissues. Iodine regulates the cellular structures and the heart and circulatory system. It prevents goiter, loss of hair, brain fatigue, shyness, glandular problems, excitability and irregular pulse rate.

Food Sources: Sea kelp, dulse, irish moss, pineapple, brown rice, garlic, apples, raw egg yolk, strawberries, potato skin, watercress, sea foods, carrots, onions, tomatoes and artichokes.

Manganese (Nerve Controller Mineral): A thought coordinator, it increases mental and nerve force, quick recuperation and improves memory. It feeds the brain and nerves; and increases resistance to disease. It is the mineral controlling the emotions and affections, giving social poise, confidence and steady nerves. It also imparts to the body elasticity and fast recuperative ability. Lack of Manganese causes confusion and scatter-brained activity in work, studies and love. It can lead to nerve disorders if deficient too long.

Food Sources: Almonds, walnuts, endive, wintergreen, raw egg yolk, prunes, peppermint tea, parsley, pignolia nuts, rye meal, sun dried fruits and greens.

Potassium (Strengthen Mineral): It nourishes, gives health, strength and quick recuperative powers. It puts fire and zip into the body. It reduces pain and regulates the brain and body. It promotes elastic and supple muscles, and creates grace, beauty and good disposition. It helps to prevent constipation. It activates the liver and is alkaline to the body. It aids the tissues and internal secretions. Stress depletes the potassium in the body and this leads to an acid condition. People on the go need potassium. It helps to control temper. Get your share of this magic mineral daily.

Food Sources: Potato skin, almonds, parsley, watercress, carrots, berries, cherries, figs, grapes, lemons, olives, alfalfa, cucumber, dandelion, sage, dill, lettuce, peaches, oranges & tropical fruits.

Fluorine (Beautifier & Youth Mineral): It protects against sickness; knits bones, aids teeth enamel and strengthens tendons. As the youth element, it gives you strong mental powers and keeps you elastic. It works with calcium to build strong tooth enamel, bone structure, hair and elastic tissues. Fluorine is the rejuvenation mineral and helps to keep you young. It improves the eyes, hair and nails. The lack of fluorine causes premature old age, fear, hair loss, brain and body fatigue, tuberculosis, paralysis and a run down condition.

Food Sources: Raw goat milk/cheece, spinach, cress, garlic, oats, greens, beets, wheat, brussel sprouts, cabbage and cauliflower.

Oxygen (Life-Giving Mineral): Oxygen is primarily found in the air. Mountain and ocean air is the purest type available. City air is polluted and its oxygen is full of chemicals. Pure oxygen gives us brain and body stimulation. Oxygen comprises over half the body weight. Normal breathing is not enough. We must get out into the fresh air, exercise and expand our chest to its fullest capacity with the life-giving oxygen. Fresh oxygen helps to digest our food. It purifies and blood stream and cleans out the lungs. It is necessary for the metabolism and all processes of the body. Oxygen makes us happy, bouyant and fresh. Lack of it causes depression, anemia, low energy and a hopeless outlook on life.

Food Sources: Pure water, all fresh fruits, vegetables, juices, and pure outside air.

Carbon (Body Heater Mineral): One fifth of the body is composed of carbon. Only so much carbon is needed by the body. Too much can break down the liver and cause disease. Carbon is the fuel and heater to the body. Carbon is mostly found in fats, and they yield 4040 calories per pound, while carbohydrates furnish only 1820 calories per pound. Fats are composed of about 76 percent carbon, 12 percent hydrogen and 12 percent oxygen. After digestion, fats are absorbed and then oxidized to produce energy, carbon dioxide, and water. Eaten to excess, fats may be stored as body fat or converted into carbohydrate and stored as glycogen. Lack of carbon may cause coldness, forgetfulness, laziness, fear, brain deficiency and over all lack of energy. White flour products, white sugar, lard, fatty animal foods and fried foods are dangerous to life and health.

Food Sources: Rice bran, oats, corn, millet, cheese, butter, egg yolk, goat milk, avocado, pure vegetable oils, nuts, rye, wheat bran, barley, pecans, brazil nuts, walnuts, peanuts and coconuts.

Nitrogen (Muscle Builder Mineral): Nitrogen is mainly found in the form of protein, which is composed of carbon, oxygen, hydrogen, sulphur and nitrogen. Nitrogen furnishes building material to keep the cells and tissues together. In the construction of the protein molecules of plants, nitrogen is absorbed from the soil in soluble forms, as compounds of nitrates and ammonium salts, which are converted first into amino acids and then into protein. The body takes up this protein and converts it into amino acids for the promotion of growth, life, health and vitality. This is known as the Nitrogen Cycle, and all plant and animal life are dependent upon it for existence. The atmosphere is ¾ Nitrogen, with oxygen, carbon and hydrogen composing the rest of the ether. We could not breathe or live on 100% pure oxygen without the other three elements. Nitrogen keeps the oxygen from burning up in the body.

Food Sources: Nuts, seeds, legumes, milk, eggs, whole grains, cheese and all other foods high in protein.

Hydrogen (Cooling Mineral): Hydrogen maintains body coolness and body temperature. It is the youth mineral that helps to overcome inflammation and pain. It also flushes the inner organs of toxins and waste matter. It is involved in the nitrogen cycle of plants and animals. It is located in the atmosphere and fresh foods.

Food Sources: Fresh fruits and vegetables, lettuce, tomatoes, celery, juices, cucumber, water & all foods with a liquid content.

Trace Minerals: Copper, zinc, cobalt, selenium and the over 28 other trace minerals are found in very small quantities in the body. However, they are vitally important, and as necessary to your health and well-being as the other 16 Magic Minerals. These trace elements are found in all plant life.

Zinc: It is found in the hair, nails, bones, liver, skin, glands, kidneys and the prostrate gland. It increases blood production in weak areas. Wounds heal faster with zinc, and it can act as an antidote to certain poisons. Zinc deficiencies cause diabetes, retardation, schizophrenia, fatigue, infection, and poor skin. If you have white spots on your fingernails, you have a zinc deficiency.

Food Sources: Apricots, nutritional yeast, nuts, pumpkin and sunflower seeds, wheatgerm, egg yolk, soy beans, spinach and mushrooms.

Copper: It assists in forming rich red blood cells. It prevents anemia, builds the bones and circulator system. It heals the body, improves the hair and skin. Lack of Copper causes weakness, skin trouble, poor respiration, baldness and fatigue.

Food Sources: Nuts, raisins, molasses, soybeans, legumes, apricots, dark fruits and juices.

Cobalt: It is needed in small amounts only. It assists the absorption of B-12 in the body. It is contained in a variety of natural foods listed under the other minerals.

Selenium: Small amounts are needed. In functions similar to vitamin E in the system. It is located in small traces in sea water. It is contained in all natural foods.

Your food shall be your medicine, and your medicine shall be your food. Eat sparingly and defy the physician. The human is the most helpless creature on the face of the earth. When they come into existence they have to be taught everything which become their habits. But this is our salvation. If man is a creature of habits why not be a slave to good habits? We can reeducate ourselves and take control of our own destiny. Love does not dominate; it cultivates.

Natural Foods contain all the vitamins that have been discovered and will be discovered. Scurvy, pellagra, beriberi, and most all diseases are the result, partially at least, of vitamin deficiencies. Cheat the body of vitamin-rich food and you are on a disease-producing diet. Quality foods count, not quantity.

3. Connect your Personal Star to the Personal Star of each person

Connect your personal star to each person and then to the universe.

4. Create a Chi Body becoming the major connecting point. Counterclockwise spiral to connect each person's star into a larger group star.



Fig. 4.11 *Link with Each others Personal Stars.*



Fig. 4.12 *Connect into Group Star.*

5. Meditators become satellite links and create a group energy body.

The World Link meditations become an integrated communication link. They are linked to the earth and the universe. Spiral and connect each person's star together and group the energy into one energy body. This energy body becomes an integrated communication center for each person in the group. We can be connected, wherever we are. Each person can connect and become their own 'Center of the Universe'.



***Fig. 4.13** Form a Satellite Link and create a Group Energy Body.*

Vitamins for Vitality

Vitamins were discovered by Dr. Casmir Funk about 62 years ago. The word vitamin comes from the Latin word vita, which means life, and amins, meaning amino acids, which form the life substances of protoplasm or organic compounds, of which the growth and life of plants and animals depend. They are composed mainly of carbon, hydrogen, oxygen and nitrogen.

Actually, vitamins provide no heat, energy, or material for tissue building, however, they are vitally important for proper growth and good health. The minerals are the nutritional elements necessary for building and repairing cells and tissues. Vitamins are those atomically small sparks of food energy elements that carry on the process of metabolism; the activation, assimilation and utilization of minerals, fats, carbohydrates, trace elements and other nutritional factors in our food.

Vitamins keep the fires of life aglow. They secretly control the internal chemical process; converting food into blood, tissue and dynamic energy. The body needs vitamins from outside sources and they must be eaten daily, for it cannot store them.

Through the process of photosynthesis, (air, light and water), nature manufactures the organic vitamins, mineral salts, and enzymes through plant life; fruits, vegetables, seeds, nuts and sea vegetation. All earthly life forms are created and sustained by this process. Plant life is the number one source of nutriment for all beings and creatures on this planet.

Natural Vitamins are Superior

Nature makes no artificial substitutes for vitamins and minerals. No other substances can take their place in human and animal chemistry. We need them in abundance daily, in whole food form and in natural food supplement form to assure adequate and complete nutrition. The difference between synthetic and natural vitamins may be the difference between disease and health. Synthetic vitamins and minerals are inorganic chemical substances and cannot be utilized by the cells and tissues of the body. The chemist will never produce a single blade of grass, yet the body can assimilate and utilize that blade of grass, while rejecting the chemist's synthetic formula.

Scurvy, pellagra, beri-beri, rickets and similar diseases are caused by a vitamin starved body. When the body is lacking the essential vital nutrients, it will develop disease. Healthy bodies are built by quality foods, not quantity. Natural foods and natural food supplements will meet those needs to the fullest. Super Health will result with the intelligent use of them.

Major Vitamins and their Food Sources

Vitamin A *(Fat Soluble)*

It is destroyed by high heat in the presence of oxygen. It is stored in the fatty tissues for future use. Stress and strain will quickly use up Vitamin A. It builds resistance to colds, lung and sinus trouble. It is necessary for visual purple production and night vision. Increases growth and increases blood quality with the help of B complex, Vitamin C, D, E, F, Calcium, Phosphorus and Zinc. It helps conditions of acne, colds, allergies, eczema, diabetes, stress, and arthritis. Lack of this vitamin may cause night blindness, poor eyesight, rough skin, infections, dry hair and fatigue.

Food Sources: Alfalfa, green vegetables, carrots, tomatoes, apricots, cherries, egg yolk, papaya. RDA: 5,000 to 25,000 International Units daily. A glass of fresh carrot juice contains 9,000 to 12,000 units.

Vitamin B Complex *(Water Soluble)*

The B Complex family consists of the following B Vitamins: B1 (Thiamine), B2 (Riboflavin), B6 (Pyridoxine), B12 (Cobalamin), Biotine, Choline, Folic Acid, Inositol, Niacin (Niacinamide), Pantothenic Acid, Para-Aminobenzoic Acid and Pangamic Acid. The first three of these vitamins are the most important. They are stored in limited quantities in the body. They are active in enzyme production. They improve the digestive tract, skin, nerves, eyes and liver. They improve the absorption of food, and calm the nervous system. B Vitamins help metabolize fats, starches and proteins; reduce blood cholesterol; increase appetite; increase cell life; build rich red blood; prevent gray hair; promote sex hormone production; controls weight; maintains the sodium-potassium balance of the body and nerves; aids circulation of blood and lymph; improves friendly bacteria activity in digestive tract; helps depression, insomnia and fatigue; overcomes anemia, skin disorders, acne, dizziness, irritability, learning disabilities, weakness and hair loss and can help heart disease, gland and nerve disorders.

Food Sources: Nutritional Yeast, wheat germ, whole grains, egg yolks, brown rice, sunflower, pumpkin and sesame seeds, mushrooms, brown rice polishings, beans, buckwheat, lentils, peas, spinach, walnuts, goat milk, asparagus, tomatoes, green juices, berries, rye, wheat, almonds. These foods eaten in moderate daily quantities will supply all the B Complex required.

Vitamin C *(Water Soluble)*

This vitamin is destroyed by high heat, antibiotics, aspirin, tobacco, fever, stress, cortisone and other drugs. Essential for tissue respiration, improves appetite, builds capillary walls and connective tissue; gums, heart, skin, teeth and bones. Good for colds, shock and infection and tooth decay. Vitamin C works best with all vitamins and minerals, calcium, magnesium and bioflavo-noids. It improves anemia, bleeding gums, cavities, poor digestion and tissue damage.

Food Sources: Citrus fruits, all berries, green peppers, strawberries, tomatoes, currants, cress, cabbage, apples, green vegetable juices, papaya, melons, lettuce, peas and pineapple. It is not stored in the body and must be supplied daily. Fruits and vegetables eaten in season and grown locally will meet your daily vitamin C requirements. Rosehip powder can be used to supplement your diet with extra C.

Vitamin D *(Fat Soluble)*

Heat or oxidation does not affect this Vitamin. A limited amount of Vitamin D is stored in the body. The greatest source is from the sun; exposing the skin to the sunlight. The ultra-violet rays change the ergosterol in the skin into small amounts of Vitamin D. It helps the absorption of calcium and phosphorus. It is a good bone builder. It controls mineral metabolism. It favors good posture, bone growth and tooth development, fatigue, caries, nerve disorder, infections, poor skin tone, rickets and constipation.

Food Sources: Fruit and vegetables grown in the sunshine and their juices, butter, chlorophyl, goat milk and plenty of solar light. Crude mineral oil destroys Vitamin D in the body. Daily amount should be from 500 to 1,000 IU.

Vitamin E *(Tocopherol - Fat Soluble)*

It is not affected by heat or oxidation. The body stores a limited supply of Vitamin E. An adequate supply increases fertility, healthy skin and reduces abnormal hair growth on women. It is good for lactation, menstrual disorders, miscarriage and reproduction. Deficiencies of Vitamin E can cause sterility, loss of vitality and virility, lack of courage, pessimism and impaired mentality. It improves blood vessel and heart function. It builds the nerves and promotes the pituitary gland into activity. It helps to retard aging, controls blood cholesterol, tones muscles and nerves, keeps the blood from clotting, protects the lungs from pollution, increases male and female fertility and potency, and strengthens blood vessels, arteries and veins.

Food Sources: All whole grain foods, green vegetables, wheat germ, olive oil, corn, most fruits, cottage cheese, goat milk, soybeans, tomatoes, egg yolks and oats. Vitamin E is destroyed by birth control pills, tap water, crude mineral oil and hard fat. Vitamin E oil can be used topically for burns, wounds, warts and scars with good results.

Vitamin F *(Unsaturated Fatty Acids - Fat Soluble)*

Excessive heat destroys Vitamin F. Radiation and x-rays harm this vitamin in the body. It prevents stiff joints and hardened arteries. It controls blood cholesterol, improves blood pressure and glandular activity. It helps functioning of adrenal and thyroid glands. It calms the nerves and beautifies the skin. Lack of Vitamin F causes acne, gall stones, diarrhea, allergies, poor nails and hair, underweight and varicose veins. It makes for stunted growth, poor sexual development and loss of appetite.

Food Sources: Nutritional yeast, spinach, fruits, all seeds and nuts, egg yolks, wheat germ, olive oil, sunflower oil; whole grains, orange juice and root vegetables. Adequate supply from above foods should be eaten in moderation.

Vitamin K *(Menadione - Fat Soluble)*

X-rays, radiation, drugs, hard oils and fats destroy this vitamin. It improves the blood clotting system, and can be used for hemorrhages, menstrual problems and bruising. Lack of Vitamin K causes nosebleeds, diarrhea, tendency to hemorrhage and possible miscarriages.

Food Sources: Blackstrap molasses, yogurt, safflower oil, green juices and vegetables, oats, tomatoes, green peas, carrots, cauliflower and spinach. One to two milligrams per day are enough.

Vitamin P ***(Biof Lavonoids - Water Soluble)***

It is part of Vitamin C. It builds and maintains the blood, connective tissues, skin, gums, bones, teeth and capillary walls. Good for coldsores, colds and the flu.
Food Sources: Cherries, apricots, grapes, grapefruit, lemons, plums and the inner skins of most fruits. Same daily allowances as Vitamin C.

Vitamins and Mineral Food Supplements

1. ***Alfalfa Liquid, Powder or Tablets:*** Two teaspoonfuls or 3 to 5 tablets daily.
2. ***Nutritional Yeast:*** B-Complex and protein source. Two to four tablespoons daily.
3. ***Wheat Germ Oil or Flakes:*** Vitamin E, protein, B-complex, minerals. Must be fresh. Two to 4 tablespoons daily of flakes.
4. ***Sea Kelp or Dulse:*** High in iodine, trace minerals. Use in salads, cooking, eat 3 to 5 tablets, or 1 teaspoon daily.
5. ***Pure Rosehip Powder:*** High in vitamin C, bioflavonoids and enzymes. One teaspoon.
6. ***Pure Cold Pressed Vegetable Oils:*** High in unsaturated fatty acids. Use sesame, sunflower or safflower oils. No more than one tablespoon in summer and two in winter.
7. ***Rice Polishings:*** High in B-Complex vitamins and minerals. Two teaspoons daily.
8. ***Fresh Squeezed Vegetable Juices:*** Vitamins, minerals and enzymes. 4 to 8 ounces in summer - less in winter.
9. ***Spirulina Plankton:*** High in vitamins, minerals, enzymes and protein. Protects against radioactive agents. Two to four tablets, or two teaspoons daily.
10. ***Powdered Carrot Calcium (Dr. Bronner):*** High in Calcium and minerals. One teaspoon daily.

Vitamins seem to offer the kick to the minerals that enter our bodies. They are little invisible helpers ready to right every wrong that may come about in the complicated processes of building and maintaining a perfect body.

Power of Enzymes

All growing and living things, including the foods we eat, contain enzymes. Where we find minerals, vitamins, protein etc., we also find enzymes. Enzymes are tiny almost invisible ferments, which cannot even be seen by the strongest microscopes. They help us digest our food and keep the fires of metabolism alive in our system. Enzymes are contained in proteins and some vitamins. Enzymes require a protein carrier to charge us with health and vitality. In fact, if we eat raw food exclusively, i.e., raw fruits and vegetables, our enzyme activity will decrease. The body needs a certain amount of all natural elements to function properly and increase the enzymes in our system. When enzyme activity slows down, we age and slowly die. If enzyme activity is increased in the system, our health and longevity improves. Enzyme levels are generally low in cases of chronic disease.

Foods that lower enzyme activity: Fats, ungerminated seeds and nuts, nut butters, excess oils, alcohol, eggs, sugar, white flour and excess fruits. Overeating, which causes constipation and obesity also reduces internal enzymes. Foods and habits that increase enzyme activity: germinated or sprouted seeds, nuts and grains; fermented seeds, miso, tofu, tempeh, tamari, cultured products these foods contain aspergillus plant enzymes, the highest source of enzymes as yet discovered. Fasting when not hungry and obtaining sufficient exercise, sunshine and fresh air aid our enzyme production.

The body produces only two Enzymes Amylase and Protease, which digest carbohydrates and proteins. Without sufficient enzymes vitamins, minerals and hormones cannot carry on their activity. Biochemist and enzyme researcher, Dr. Edward Howell states: Enzymes are substances which make life possible. They are needed for every chemical reaction that occurs in our body. Enzymes may be the key factor in preventing chronic disease and extending the human lifespan. A balanced natural food diet with healthful living habits produces the ultimate results in superior health and longevity.

It is the opinion of those who best understand the physical system, that if the physical laws were strictly observed from generation to generation, there would be an end to the frightful diseases that cut life short, and make life a torment or a trial. The more you know the less you know but the more you become.

Perhaps the most predominant food fallacy is the high protein intake usually recommended. Protein in excess of our needs is not utilized by the body.

Protein Requirements

Where do you get your protein if you do not eat meat? How many times have vegetarians been asked this question throughout the history of nutrition? Why not ask how a cow produces milk and attains great size on vegetable matter; or where an elephant, gorilla and rhinoceros obtain their protein. Better yet, ask the vegetarian centenarians, worldwide, where their sources of protein come from.

There are people living in the mountains of Russia, Turkey, India, Northern Hunza, Iran and Poland who live over 100 years in good health. Their main diet consists of whole unprocessed grains, i.e., rye, wheat, oats, millet, buckwheat and rice; seeds, nuts, locally grown fruits, vegetables and raw cultured milk products. Their diet is basically high in natural complex carbohydrates and never high in protein. Their approximate protein intake ranges from 25 to 40 grams daily. People who subsist on these natural whole foods contract *no* disease of any kind. These centenarians work all day long in the fields and never experience fatigue as we know it. They are not protein deficient. Westerners are just protein hypochrondriacs. They know nothing of high protein or other fad diets. They exist healthfully and happily, and they are not skinny or fat, but firm, muscled, robust, and energetic. Did you ever see a fat native Chinese or Japanese who subsisted on their typical traditional diet who use meat mainly as a condoment in soups and vegetable stir fries. We have personally observed these tireless people subsist on a bowl of rice, beans and vegetables daily. Young Oriental women who did not look a day over 18 or 20, we discovered, were 35 and 40 years old, with youthful smooth skin and sparkling eyes to match. These people know nothing about protein. They simply radiate beauty and tranquility. They possess well-formed physiques, and maintain the same body weight throughout a long healthy life.

These are empirical (derived from observation without reliance on theory) facts, not based on personal opinions. These dietary patterns have been tried and tested for centuries. One only has to observe how the longed-lived people live and eat, and gently follow in their footsteps.

The nutritional skeptics of the West should take an example from these wise and healthy old people. Their diets, habits and cultures have been around long before America was discovered; and long before books and magazines were published on health and nutrition. We must remember that super markets, processed foods, drug companies, protein and other trendy diets are all modern inventions, not more than 60 to 80 years old; mere seconds in the history of the world.

Protein and Amino Acid Metabolism

Proteins, like carbohydrates and fats, are composed of carbon, hydrogen and oxygen, with the addition of nitrogen, sulphur and phosphorus. Plants can synthesize protein elements from the nitrates, ammonia in the soil and decomposing vegetable matter, along with water and carbon dioxide from the air. Therefore, humans are dependent upon plants for nitrogen-rich foods.

There are eight essential and fourteen non-essential amino acids necessary for growth. The essential ones are: isoleucine, leucine, lysine, methionine, phenylalanine, tryptophane, threonine, and valine. All 22 amino acids are necessary for health, however, the eight essential ones must be supplied in the diet daily. The fourteen other amino acids are alanine, arginine, aspartic acid, cystine, glutamic acid, glycine, histidine, hydro-xyglutamic acid, hydroxylsine, hydroxproline, norleucine, proline, serine, & tyrosine.

A good quality complete protein supplies all the essential eight amino acids for normal growth and health. Incomplete proteins are the ones that lack one or more of the eight essential amino acids, and can neither support normal growth or good health. Over fifty percent of our body is composed of protein including skeletal muscles, intestines, skin, ligaments, cartilage, eye, hair, nerve fibers, bones and blood. Protein is necessary for blood clotting; and produces hormones and all enzymes. Lack of sufficient protein can cause anemia, skin disorders, constipation and even death.

Protein is converted into amino acidswhich are the basic buildingblocks of our body. Protein is used to build the various body structures, for example, muscle protein is called myosin; connective tissue uses collagen protein; and hair is made up of keratin protein. An excess as well as a deficiency of protein can cause health problems. The residue of excess protein is converted into fat and carbohydrate which is highly toxic and disease producing.

To understand this it might be well to know something of the structure of an amino acid. As the name implies, the backbone of every amino acid is an amino (nitrogen) group, NH^2, and an acid(carboxyl) group, COOH, held together by a single carbon atom, To the carbon atom is also attached a chain of organic compounds (usually denoted as R) which give each amino acid its special characteristic. These individualizing chains are made up of carbon, nitrogen, hydrogen, oxygen and sometimes sulphur.

Hence the base of every amino acid looks like this:



$$NH^2 \qquad \overset{H}{\underset{R}{C}} \qquad COOH$$

Now, whenever the body cannot use an amino acid, the liver breaks it down into its various parts and uses the oxygen, hydrogen, and carbon atoms to form glucose or saturated fat. The rest, meaning the amino groups and sulphur groups it discards as ammonia and sulphuric acid. Get enough of those two elements in your system and you will be set up for all kinds of health disasters.

The ammonia (NH^3) is usualy taken care of by uniting with carbon dioxide which forms urea, a less nitrogenous substance which can be easily eliminated from the kidneys. An excess of ammonia can be converted into uric acid, however, which has the tendency to accumulate in the system and cause trouble. And sometimes the ammonia just remains as free NH^3. When there is a sufficient supply of minerals in the body, the acids, including sulphuric acid, combine with them and are eliminated as salts. Without enough minerals present, they get stuck in the body and clog up the functions of the cells. It is very important, therefore, to make sure that one’s protein intake meets the body’s needs, but no more. An excess of protein can create an excess of fat, raise the cholesterol level in the process, and fill the body with troublesome toxins.

Proteins are not Fuel Foods

Most recent research, worldwide, both scientific and empirical, shows more and more convincingly that our past beliefs in regard to high requirement of protein are outdated and incorrect, and that the actual daily need for protein in human nutrition Is far below that which has long been considered necessary.

The metabolism of proteins consumed In excess of the actual need leaves toxic residues of metabolic wastes in tissues, causes autotoxemia, over-acidity and nutritional deficiencies, accumulation of uric acid and purines in the tissues, intestinal putrefaction, can contribute to the development of our most common diseases such as arthritis, kidney damage, pyorrhea, schizophrenia, osteoporosis, atherosclerosis, heart disease, and cancer.

Proteins are among the most complex organic compounds found in nature. Proteins are used in the body for repair and replacement of worn out cells and tissues, but are not equally useful as fuel foods.

Carbohydrates and starchs are the primary fuel and energy supplying foods. Your need for protein can be drastically reduced by including in your diet complex carbohydrates such as, whole grains, legumes, peas, whole grain breads, whole grain noodles etc. These foods also contain an adequate supply of protein in the right proportion, especially when legumes and grains are combined at a meal.

Worldwide Protein Research

American health is declining. As a nation Americans are 21st in life expectancy, and 18th in infant mortality. They lead the world in cancer, heart disease, kidney disease, diabetes, osteoporosis, arthritis and hypoglycemia. Every cell in our body is built of protein, but that is not all we are built of. We are also 70% or more water with small amounts of minerals, vitamins etc. Proteins are needed for cell building and repair, enzyme and hormone synthesis, mineral metabolism. We need protein. But how much is too much?

Early European investigators advocated from 100 to 150 grams of proteins as a daily requirement. These erroneous figures were based on observation of what people were actually eating. Meat consumption was very high during the time of these investigations and it is easy to see how these scientists arrived at their conclusions. In the early nineteenth century conducted scientific tests on students and discovered that they could remain in nitrogen balance on less than a third of the amount of protein previously recommended and considered necessary. In fact, we have been made to believe that the more protein we consume, the better. We just could not get too much of it. Yet, the most recent worldwide research shows that the actual daily need of protein in human nutrition is far below that which has long been considered necessary.

E. Protective Circle and Chi Field

Raise your hand up and become aware of the ‘Sacred Fire’ in the universe. Feel that your fingers are very ‘big’, very ‘long’ and touch the fire. Bring the fire down. Make a circle around your community, your house, Tao Garden, the meditation hall and around your bodies. Create an energetic field of Chi around the whole room.

Sacred or Chi Fire
Connect and Receive Fire from the Universal Cauldron

1. Activate the Sacred Fire in the Universe

Be aware of yourself. Feel your arm and fingers ‘big’, ‘long’ and ‘hollow’. Reach to the universe to the Sacred Fire. Let the Sacred Fire fill and pack your arm.

2. Use Yi-Power to Create Sacred Fire Protective Circle



Use the Yi Power to draw the Sacred Fire Circle on the ground around your house, office and the room you work in.

A. ***B.***

Fig. 4.14 A. *Create a Group Energy Body.* ***B.*** *Sacred Fire ‘Protection’*

Pritikin Diet Program

The internationally renown Pritikin Nutrition Program recommends that we ingest no more than 15 or 16% of our total calories in protein. Anything over that amount and you go into negative mineral balance. Pritikin states: “For example, if you drank a quart and a half of milk per day, more calcium would be expelled through your urine than you take in. High protein diets change the body’s metabolism so that it must draw calcium from the bones to neutralize the acid conditions set up by amino acids and high protein, producing increased calcium and mineral excretion through the urine. Vegetarians always ask about getting enough protein. But I do not know any nutrition expert that can plan a diet of natural foods resulting in a protein deficiency, so long as you are not deficient in calories. You need only 6% of total calories in protein to maintain a positive nitrogen balance and it is practically impossible to get below 9% in ordinary diets. African Bantu women take in only 350 mg. of calcium per day. They bear nine children during their lifetime and breast feed them for two years. They never have a calcium deficiency, seldom break a bone, rarely lose a tooth. Their children grow up nice and strong. How can they do that on 350 mg. of calcium a day, When the American recommendation is 1200 mg. They are on a low protein diet that does not kick the calcium out of the body. In our country, those who can afford it are eating 20% of total calories in protein, which guaranties negative mineral balance, not only of calcium, but of magnesium, zinc and iron. It is all directly correlated to the amount of protein you eat”.

If you maintain your calories with whole grains, legumes, seeds, vegetables, fruits etc., you will obtain sufficient protein to keep you healthy. We are in total agreement with the food intake percentages of the Pritikin Diet: Fat intake is 5-10%, protein 10-15%, and complex carbohydrates, primarily unrefined.

Dr. Paavo Airola on Protein

Dr. Airola reports of a recent American research effort performed under the direction of Dr. Lennart Krook, showing that overeating meat leads to serious mineral imbalance, especially with respect to calcium and phosphorus. Dr. Airola goes on to report of another recent study conducted at the U. S. Army Medical Research and Nutrition Laboratory in Denver, Colorado, demonstrating that a high meat intake results in significant vitamin B6 losses. He adds that a high protein diet also causes severe deficiencies in magnesium, calcium, and niacin. Dr. Airola reports further of research conducted in Germany by Dr. Ph. Schwarz, of Frankfort University, and of those performed by the famous Swiss biochemist, Dr. Ralph Bircher, showing that the aging process is initiated by amyloid, a by-product of protein metabolism, which collects in connective tissues causing cellular and tissue degeneration. This process carried on throughout an entire organism seems to be the leading cause of premature aging.

Those peoples of the world who show the highest average life expectancy (Hunzas, Bulgarians Russians, Yucatan Indians, etc.) have traditionally subsisted on low protein diets, whereas those people who show the lowest life expectancy in the world of between 30 and 40 years (Eskimos, Lapplanders, etc.) have consumed large animal high protein diets.

Dr. Hindhede, in Protein and Nutrition; “a rich protein diet is a cause of various ailments, that luxurious habits especially overindulgence in meat, can give rise to various stomach, kidney and arthritical complaints, is reported by manifold experience. The office of the liver is to render harmless, by conversion Into urea, the ammonium, compounds which arise from the decomposition of animal protein in the intestines, and suggests that the ogran performs the same service in regard to various other waste products of metabolism. It is easy to conceive that the liver is to a certain degree composed of these poisonous products, but there are limits to the functional ability of the organ to render these poisons harmless, which may possibly explain some to the maladies from which those who indulge largely in meat suffer.”

Protein and Calcium Metabolism

A series of studies with young adults of both sexes show clearly that as protein intake is increased retention of bone calcium decreases. Researchers at the University of Wisconsin found that when the protein intake of young men was raised to 140 grams per day, the subjects proceeded to lose bone calcium at a rate which, if continued, would have left them no bones at all by their early 50’s. Not one subject failed to experience rapid bone deterioration, even though they took liberal amounts of calcium and their phosphorus intakes were kept artificially low. Studies with young women show that they too respond to high protein intake with marked bone erosion. It requires even lower protien intakes to effect the losses in women but this can be explained by their smaller body sizes. Young men had strong bone retention with protein intakes in the range of 50 grams per day. Unfortunately, young American adults are taking on the average as much as 100 grams of protein per day, suggests that our young may be experiencing rapid bone deterioration.

A build-up in blood urea Is associated with kidney failure and doctors in Italy, Hungary, Canada, Russia, and more recently in the U.S., report success in treating kidney patients with low protein diets. A Quebec physician, Dr. M. G. Bergerson, states that a low protein diet can be highly beneficial for kidney patients, even when they have reached the some stage. An Italian rsearcher reports patients with chronic kidney insufficiency can be rendered symptom free for years on a diet containing 20 grams of protein per day. A Russian group reports prolonged use of diets containing 18-24 grams of protein per day has netted good results with patients suffering from kidney insufficiency. The Russians have made extensive use of a potato diet for kidney patients and American researchers found plant proteins were far more effective than animal proteins in keeping blood urea levels down.

Russian Research on Protein

Dr. Uri Nikolayev is probably the most successful psychiatrist in history; the mentor of Moscow's prestigious Psychiatric Institute has cured thousands of desperately ill schizophrenics. What his technique does is rid the body of protein derivatives and other chemical abnormalities that Psychiatry Digest cites as the apparent cause of all forms of schizophrenia. His technique is of course, fasting. Fasting, it should be noted, Is the ultimate in low protien diets, low calorie diets, even protein-free low calorie diets, sharply curtail the excretion of protein wastes, only a fast can in the short run, at least, purge the body of the excesses of a lifetime. Dr. Nikolayev's treatment of fasting has received wide acclaim which it richly deserves. What has escaped attention is the second phase of his treatment, that is the treatment that follows a successful fast. For only with the adaption of a low-protein vegetarian diet are the results lasting, a return to a meat-based diet is a return to emotional stress.

Excess Protein causes Cancer

High protein intake is strongly linked to cancer. A Cornell researcher places the blame on ammonia. Ammonia, and possible other protein wastes, may indeed play roles in cancer, but protein partners cancer in a number of ways. High protein intake incites a cancer-like frenzy of activity at the cellular level. It weakens the body's capacity to resist cancer by weakening the liver, it stimulates the production of hormones involved in widespread hormone-dependent cancers, and it promotes the kind of growth on which cancer thrives.

High protein intake causes sharp increases in the rates of breakdown of existing protein and of synthesis of new protein at the cellular level. In the presence of adequate caloric intake the synthesis of new protein tends to exceed the breakdown of existing protein. The resulting protein build-up causes the cells to grow and divide. Rapid cell growth and rapid cell division are hallmarks of cancer. Tumors are the result of a concentration of frenzied protein synthesis and cell division at the site.

The rapid cell division that accompanies elevated protein intake begins as a general body phenomenon rather than being concentrated in on small region as It would with cancer. And finally, women should find this fact most convincing: High protein intake leads to increase production of estrogens (female sex hormones) in women; increased estrogen output tends to promote various female cancers.

Protein Reducing Diets

Most so-called reducing diets are harmful, and although damaged health. High protein diets and low or no carbohydrate diets are especially harmful. Severe restriction of carbohydrates with no restriction of fats and proteins may take weight off effectively, but can have the disastrous effect of causing irreparable damage to brain, nerve system and heart. A high protein diet, always popular with reducers, will admittedly help to reduce, but always with severe health damage as the result. Over indulgence in proteins is one of the prime causes of such dreaded diseases as arthritis, osteoporosis, heart disease and cancer.

Scientific Consensus

Perhaps the following fact will convince you more than anything else. The Food and Nutrition Board of the National Academy of Science, in collaboration with the World Health Organization, publishes every four years the Table of Recommended Daily Allowances of various nutrients. In the last two decades, they have lowered the daily recommendation for protein from 120 grams to only 46 grams. This was prompted by world-wide scientific consensus and a growing concern that an excess of protein in the diet, just like an excess of anything else, can be extremely harmful and can contribute to the development of biochemical and metabolic imbalances and diseases.

Protein Requirements and Sources

The protein requirements for each individual are totally different. Each person is unique in his nutritional needs, requiring certain foods for his own metabolism, glands and body structure. Hard and fast nutritional rules cannot be applied generally. Everyone must take a close look at themselves, and determine through self-diagnosis, habits and heredity, exactly what they require to improve their own health. No book can do this for you; a book can only be a guidepost to teach us universal principles, so that we may apply them to our own individual needs.

Generally, the protein intake for growing children is higher than for an elderly person. Pregnant women and nursing mothers may need a little extra supply of protein to provide nourishment for two organisms. The supply should only meet the demands of the body, and no more. Weight lifters and bodybuilders need more grams of good quality protein to make good the breakdown and loss of their cells and tissues.

You, as a unique organism, must determine what your protein requirements are on a day to day basis. Some days your inner voice or body intelligence will require that you consume additional amounts of natural protein, other days you will not feel the need for half that much protein. Stress conditions, exercise, hot and cold weather, sleep and rest, unforseen environmental factors, and human physical and physhological variables all play an extremely important role in your daily protein requirements.

Grams of Protein in Various Foods

	Seeds and Nuts	**Grams**
Filberts	½ cup	6
Almonds, Raw	½ cup	13
Brazil Nuts	½ cup	10
Cashews, Unsalted	½ cup	12
Pecans	½ cup	5
Sesame Seeds	½ cup	9
Sunflower Seeds	½ cup	12
Walnuts	½ cup	7
Pumpkin Seeds	½ cup	14
	Grains, Fruits and Vegetables	
Barley, Whole	½ cup	13
Buckwheat, Whole	¾ cup	12
Lima Beans, Cooked	1 cup	16
Kidney Beans	1 cup	15
Broccoli, Steamed	1 cup	6
Cauliflower	1 cup	3
Corn, Steamed	1 ear	3
Kale	1 cup	4
Lentils	1 cup	15
Peas, Steamed	1 cup	5
Peas, Split	½ cup	8
Potatoes, Baked	1 med	2
Squash, Winter	1 cup	4
Avocado	½	2
Apricots, Soaked	½ cup	4
Blackberries	1 cup	2
Dates, Soaked	1 cup	4
Prunes, Soaked	1 cup	3
Raisins, Soaked	½ cup	2
Wheat Bread	1 sl.	2
Corn Bread	1 sl.	3
Soy Flour, Powder	1 cup	39
Oatmeal	1 cup	5
Rice, Brown	1 cup	15
Rice Polish	½ cup	6
Wheat Germ	1 cup	17
Bean Soups	1 cup	8
Creamed Veg. Soups	1 cup	7
Nutritional Yeast	¼ cup	13
Nutritional Yeast	1 T	6
Soy Powder, Concentrate	1 T	12

	***Dairy-Animal**	
Raw Goat Milk	1 cup	8
Buttermilk	1 cup	9
Yogurt (Low Fat)	1 cup	8
Skim Milk	1 cup	8
Cottage Cheese	1 cup	35
Swiss Cheese	1 oz.	7
Egg	1	6
Skim Milk Cheese	1 oz.	8
Flesh	4 oz.	20

*Use these foods sparingly. Listed for clarity and information.

It should also be understood that under stress conditions and anemic conditions the body needs extra amounts of the entire B-Complex vitamines, and the best source of B-12, B-6, etc. is whole unprocessed grains: rice, rye, buckwheat, millet, wheat germ, and brewers yeast. For a calm disposition and steady nerves, grains, fruits, vegetables, seeds and nuts will provide the essential nutrients to overcome stress.

The most reliable indicator of protein need is our present overall health. Are we full of pep and energy? How about our skin, nails, hair and eyes? Is the skin smooth and clear? Are the nails without ridges, pink and smooth, with small half-moons at the base and are they free of white spots? Does the hair sheen and bounce with vitality? Do your eyes sparkle? Are they clear, without redness or yellowness? Is there dark circles under them? These are all self-diagnosing indicators of health and vitality of our organs. Also, is your digestion good? Are you always uncomfortable, bloated or experience gas after meals? Are you constipated? Is your elimination poor? Ask questions and experiment on yourself. No authority can decide for you what you need on any given day or hour. One must ultimately depend upon his own body wisdom to determine his or her own nutritional needs.

Muscleman advocates Low Protein

Vegetarian world champion bodybuilder, Bill Pearl (Mr. America, Mr. Universe), states quite emphatically that a growing bodybuilder simply does not need 300-400 grams of protein to reach his potential. Mr. Pearl believes that one can build health, strength and muscles on 50 to 70 grams of protein per day on a well balanced vegetarian diet. Beef is actually fairly low in protein, because once you remove all the fiber, water and uric acid from the prime steak, very little protein remains. Pearl has been a vegetarian since 1971 and has been pumping iron for 50 years. He is now near 80 years old and weighs well over 200 pounds of solid muscle with Herculean strength to match. He further says that there is absolutely no question that it Is possible to build a high-class physique and be a vegetarian at the same time. Vegetarian eating has had numerous positive effects on his body. His cholesterol gradually dropped down to a normal level of 198, and the blood pressure lowered. His pulse rate and other physiological processes are much better, and overall he is in better shape than he was 15 years ago.

One of the most dramatic changes has been in his uric acid levels. His uric acid is now down to zero, but before it was so sky high that every joint in his body ached. His uric acid was once so high that he could hardly move my hands. He actually thought he was getting arthritis. Now his energy levels are incredible, and he feels like a million dollars all of the time. His 33rd year of training starts in August (1979), and he definitely feel as good today as he did 30 years ago. There is nobody in his club, or anyone he have ever trained with, that he could not stay up with in a hard workout. His energy is greater that ever, and they do not need to knock off 15 cows a year to keep him fed.

The biggest change has been in his attitude toward himself and my fellow man. Perhaps this sounds crazy, but he is not as aggressive as he was in the past. There have been times in his life that he has wanted to go out and fight some guy for saying something to me. Or he would scream and holler, and really make an ass of himself. Now he catches himself smiling and trying to work out a problem. Vegetarianism has definitely had a mellowing effect on me. Once you are eating as a vegetarian, you cannot be swayed away from it by anyone, regardless of what he says. If a person offered him $50,000 to eat a steak, he would tell him to stick it in his pocket. What is the sense of making a commitment if you are not committed? He is a firm believer in sticking to convictions.

Mayo Clinic Report

According to Nutritionist, Dr. R. A. Nelson, of the Mayo Medical School: Animals fed high protein diets have increased urea production. Kidney hypertrophy occurs in animals on long term protein diets; more strikingly, if one kidney is removed, the degree of hypertrophy of the remaining kidney is directly related to the amount of protein ingested. High protein diets increase albumin and casts in animal urine. Rabbits on high protein diets develop nephritis, as do rats if the diet is continued long enough. Trout fed a low protein diet live twice as long as trout given a high protein diet.

Protein vs Complex Carbohydrates

An article appearing in Iron Man Magazine, Sept., 1978, entitled “Carbohydrates-No Villain”, written by Vince Gironda, body building champion, exercise and nutrition researcher, states: “I advocate a relatively low protein intake, about 45 grams per day. Too much protein creates a negative nitrogen balance which in turn leads to gout, sluggishness, and liver and kidney problems. The body cannot digest more than 20 grams per meal, and anything beyond that leads to problems. At least one meal per day should be carbohydrates in the form of vegetables or grains, thereby giving the body a protein break. Futhermore, it has been demonstrated repeatedly that protein combustion is not higher during heavy exercise than under resting conditions, while on the other hand the body uses carbohydrates stored first before it turns to other sources. Even after depleting the carbohydrate deposits, continued exercise does not hike protein needs significantly. According to my research, athletes performing strenuous, endurance tasks such as bodybuilding, and burning up 9,000 calories per day, show no noticeable increase in protein needs. If this all is not enough to turn your heads, Dr. Per-Olaf Astrand, a famous exercise physiologist in Sweden, performed a study which concluded that endurance tends to decrease as protein intake is elevated. He discovered that a high protein diet lowered endurance as well as reduced buildups in muscle carbohydrate, more than high carbohydrate diet. Experiments by Christensen and Hansen found that in heavy work such as powerllfting or bodybuilding, the major participant towards endurance was, once again, carbohydrates. Also, the subjects were able to perform three times longer on a carbohydrate diet than a protein or fat diet.

Probably the most asked question now is, if body building essentially is the tearing down and building up again of muscle tissue, then is not increased protein necessary for that process? The answer is no. A high protein intake even after a sustained injury, does not prevent a transient rise in nitrogen losses. Dr. Doris Callaway and a team of researchers found that animals fed three times as much protein as normal recovered no better than those on normal amount of protein. Now let us get one thing straight before we go any further. There is a quality difference between carbohydrates. Do not go out and load yourself up with candy and that type of junk carbohydrates. Carbohydrate loading with sugar is a mistake. Carbohydrates replace glycogen which the body stores and uses for energy. Sugar in any form leaches the stored glycogen from the liver and produces nervousness, irritability, fears, doubts, and various psychic changes in the personality. The major sources of carbohydrates should be from, as stated earlier, grains, and vegetables.

The protein contained in seeds and nuts, (soaked over night or germinated) all grains, all legumes, vegetables, sprouts, fruits; supplemented with nutritional yeast, soybean, tofu, soy powder, miso, and sea weed products are biologically superior, and pound for pound much cheaper than meat, eggs or dairy.

Vegetable Protein Superior

The animal cannot exist without the vegetal. The human body cannot digest inorganic substances or manufacture them from proteins, carbohydrates, vitamins or minerals, etc. The synthesizing and vitalizing of inorganic elements is a vegetal function. This process is called autotrophism. Only the vegetable kingdom can perform this phenomenon. Vegetables absorb inorganic elements and convert them into organic foods, which are very complicated in their composition and construction. This is a veritable miracle produced by the interworking of the forces of nature. Biologically speaking, we are children of the vegetal mother, and spring from the vegetal. Without vegetable life, no animal on the earth would survive. We depend upon vegetal products. Our hemoglobin is derived from chlorophyl. All vegetal foods are virgin materials for the purpose of maintaining or constructing our body. Neither meat nor animal products are pure virgin material for us. We must eat vegetables and their direct products. This is the biological principle and fundamental law: vegetables are the superior food.

3. Create a Chi Dome

Set up the 'guardian animals', Blue Tortoise in the north, Red Pheasant in the south, Green Dragon in the east, White Tiger in the west, Yellow Phoenix above and Black Tortoise below.


South
Fire-Li
Yang
Wind-Sun
Earth-Kun
Harmony
Thunder
Lightning
Chen
East
West
Lake-Tui
Rain
Mountain
Ken
Heaven
Chien
Water-Kan
Yin
North

Fig. 4.15 *Create and surround yourself with a Chi Dome and the Guardian Animals.*

Important Protein Points

1. Always go outside after eating, especially protein meals. Outdoor oxygen is absolutely necessary for normal protein assimilation and utilization.
2. Eat your protein meals earlier in the day if possible, but never over an hour after sunset. Daytime is for assimilation and digestion of foods. Night hours are for sleep & recuperation.
3. It is best to consume no more than 20 grams of protein at one meal. The body cannot utilize more than this at one time.
4. As a general percentage, the body requires from 30 to 60 grams of protein daily, depending on age, sex, activity, stress, sleep, weather, food quality and environment.
5. Eat the protein foods that your body can tolerate and easily digest and utilize. Consume only what agrees with your constitution and body intelligence. Meat, dairy and eggs are not absolutely necessary for protein requirements and health.
6. Legumes can be combined with grains and seeds to form complete and adequate proteins.
7. Junk food cravings are directly linked to protein deficiencies, incomplete dietary protein or poor protein utilization.
8. Germinated or soaked (overnight) seeds and nuts liquified in a blender will increase their quality and net protein utilization. Raw dried seeds and nuts, unsoaked or ungerminated are inferior foods and do not contain complete proteins.
9. An excess of protein in the diet, especially animal meat protein, including fish and poultry, leaves poisonous residues and uric acid in the system causing Yang disease symtoms, such as constricted (Yang) kidneys, high blood pressure, liver congestion, constipation, cancer etc.
10. The long lived people in many sections of the world (Russia, Hunzas, Bulgarians) consume a moderate amount of protein daily, and they remain in vibrant health and vitality past the 100 year mark. They are able to healthfully sustain themselves on a low protein diet because of their superior, pure organically grown food, pure fresh unpolluted air, clean fresh water, no stress and their joyous attitude. Their meat intake is almost nothing, and they consume mostly raw dairy products (fresh), grains, seeds, nuts, fruits and vegetables.

11. Americans consume more meat and other proteins than any other nation on earth, and they suffer from the most degenerative diseases known to humankind.
12. An excess or lack of protein in the diet can be a quick way to lose beauty, health and strength; you can develop unsightly facial wrinkles, hair loss, poor sight and hearing, underweight or overweight, premature aging, low blood sugar and many other disease symptoms. Listen to your inner body (voice) or intelligence for the proper amount you require daily. Only you can be the final judge.

Carbohydrates and Sugars

Carbohydrates are composed of carbon, hydrogen and oxygen. They are fuel, heat and energy producing foods. The main sources of carbohydrates are all grains, fruits, vegetbles, seeds, nuts, legumes, potatoes etc.

Starch foods begin digestion in the alkaline saliva of the mouth and are completed in the small intestine. For this reason, starches should be thoroughly masticated and insalivated in the mouth before swallowing. Starches are converted into dextrines and sugars, then into dextrose and glucose before entering the blood stream, where they are readily utilized and produce animal heat.

Cooked starch is acted upon by saliva and pancreatic juice very quickly; raw starch is not. Raw starch granules are surrounded by an envelope of cellulose, which the saliva penetrates very slowly; the same for pancreatic juice. The digestibility of starch (grains, legumes, potatoes etc.) depends upon the cooking. Improperly cooked or imperfectly chewed starch food pass mostly undigested into the feces. This is also true to poorly baked bread.

Glycogen like starch is insoluble. Hence, it is stored in the liver until needed for use; it is also stored in the muscles. Every cell in the body contains a small amount of glycogen. When fuel is needed, the glycogen is again transformed into sugar, dextrose, which nourishes the body. The body maintains its heat by the burning of glycogen. Muscular work is supported by the energy set free by the burning of glycogen just as the work of a steam engine is performed through the energy obtained from coal. When glycogen becomes exhausted, the bodily forces fail. The heart consumes glycogen with every beat. Without glycogen the heart could not beat and no muscle in the body could contract. The body contains about four percent glycogen. The greatest source of glycogen is found in natural foodstuffs, i,e., grains, vegetables, fruits, seeds, nuts, legumes etc.

When no starches or carbohydrates are eaten, the body makes glycogen by splitting the protein molecule. By this means, about half the weight of protein may be converted into glycogen. The other half of the protein is converted first into ammonia then into urea. The fuel value of protein is then only half its face value, and the body is taxed in the disposal of the large amount of poisonous waste. Consequently, protein is a very poor fuel food. In other words, carbohydrates are protein sparing, instead of the body converting protein into glucose for energy, it provides the heat, energy and fuel so that protein may be used for tissue building. Proteins are utilized more fully for tissue repair if some form of natural carbohydrate food is consumed at the same meal.



Fig. 5.1. Where our Energy Comes From.

Start with the intestines on the lower left hand corner. Here the starch, after being swallowed, is converted into glucose in the intestines, absorbed and carried by the blood stream to the liver, where it is converted into glycogen. When a muscle contracts it needs fuel so the glycogen is carried by a blood vessel from the liver to the muscle, converted again into glucose, mixed with oxygen from the lungs, and fired by insulin from the pancreas, producing energy.

Tea and coffee, both of which contain considerable amounts of tannic acid, prevents the action of saliva upon starch foods. Tea and coffee drinkers experience much gastric acidity and poor digestion and health.

Fruit Sugars

Natural fruit sugars are digested and absorbed into the blood stream within 30 to 60 minutes. The natural sugars contained in all fruits, dried fruits, honey, maple syrup etc., contain fructose, grape sugar, and levelose. Honey contains equal amounts of dextrose and levulose. Milk sugar contains lactose. Refined white sugar, commercial sugars, brown sugar, saccharine, (made from coal tar products), chemically treated sweets, ice cream, candy, cakes, pies and sodas are all devoid of vitamin and mineral elements, and create calcium loss, and cause conditions from anemia to schizophrenia. If you value you health, avoid these junk food refined sugars.

Natural sugars from fruit eaten in season (moderately) will satisfy your sweet tooth, and give the body wholesome minerals, vitamins and natural fiber/bulk for intestinal health. Eat more raw fruit in summer and sparingly in winter. Fruit is Yin and is high in potassium, needed for hot weather. The body does not require much Yin food in cold weather; but rather it needs more Yang foods, such as grains, legumes, miso, soups, steamed vegetables. Yin foods help to cool the body during hot weather. Yang foods warm the body during cold winter weather. We must learn how to change our diet according to seasonal changes. This is living in harmony with heaven and earth and gives us increased health and freedom.

Fats

Fats are called hydrocarbons because they produce oil when heated. Fats are used in the body as heat, energy and fuel. They are found in butter, cream, olive oil, seeds, nuts, avocado, cheese, milk, egg yolks and all oils. Fats are digested slowly, and remain in the liver and stomach longer, delaying hunger for quite some time. Fats differ from other foods in that they are stored in the body in almost unlimited amounts. Fat is somewhat of a reserve fuel that the body draws upon when the sugar stores are greatly reduced. A normal amount of fat is stored in the body to maintain body heat, protect and lubricate internal vital organs, and give a graceful contour and shape to muscles and skin. An over consumption of fatty foods will congest the liver and weaken the digestive organs. Fats are needed more in cold weather than hot to keep the body warm.

Cholesterol is a chemical component of oils and fats. The body forms fat from starch and sugar foods. If no natural fats are included in the diet, the body will produce fats from starch and sugar foods. It is best to take fat in small quantities giving the body a chance to manufacture its own fat. If a person's diet is aduquate in B vitamins, fresh fruits, grains, vegetables, seeds, nuts and soya products, he can produce all the lecithin and anti-cholesterol agents his body needs.

An excessive consumption of eggs, meat, cheese etc., can contribute to a rise in body cholesterol. Other cholesterol forming foods are: hydrogenated oils, margerine, butter and white flour, white sugar and salt. A small amount of natural fats eaten daily will maintain the body in good health and vitality. Remember, the body will produce its own fat if the diet is deficient in it.

Percentages of some fatty foods: Butter is nearly 90 to 100% fat. Nuts contain a large amount of fat 40% to 70%. Cream is from 25% to 40% fat. Avocados contain from 25% to 40% fat; the same as the ripe olive. The soy bean contains about 20% to 30% fat. Meat contains 40% to 50% fat. Regular cheese contains from 60% to 80% fat, except skim milk cheese. Eggs are 10% to 20% fat. Ice cream is very high in fat, from 70% to 90%, plus high in sugar. Vegetable oil is 80% to 90% fat. Natural foods, such as avocados, nuts and soybeans, because of their high fat content, should not be used excessively; they are not staple foods and should be eaten very sparingly.

The greatest cause of cholesterol build-up is a combination of two things: First, fatty foods, sugar foods, white flour, salt etc. Second, a lack of daily exercise and lack of fresh outdoor oxygen, and stressful conditions. To help overcome this, consume a low fat, low protein, and high natural carbohydrate diet, including: whole grains, low fat dairy, legumes, peas, seeds, fruits, vegetables, and obtain sufficient daily exercise, fresh air, sunshine and sleep. Avoid stress. Eventually, this diet will balance the internal organs and stabilize the mind and emotions. The body weight will also normalize itself, along with blood pressure, pulse rate and cholesterol levels. Exercise helps keep the blood stream flowing freely and the arteries free of cholesterol deposits.

Free Fats are Harmful

All extracted or refined oils, whether animal or vegetable are referred to as free fats or triglycerides; all of the bulk, fiber, vitamins, enzymes and minerals are removed from the food, and we no longer have a water soluble food. Even pure vegetable or nut oils are harmful, if taken to excess, especially if eaten in hot weather. A small amount, (one teaspoon per day) may be used in cold weather for body warmth. The body can obtain its fatty acids from whole foods such as, legumes, grains, and germinated seeds and nuts. The human system cannot properly handle extracted or fractionated free fatty oils in any form. These include: butter, cream, sour cream, peanut butter, nut butters, egg yolks, mayonnaise, margarine, lard, seed/nut oils, and vegetable oils. Pure vegetable oils are the least harmful, but should also be used sparingly.

Polyunsaturated fats can cause disease as well as saturated ones. Polyunsaturates do lower serum cholesterol levels in the blood; however, the cholesterol moves out of the blood and into the cells and tussues. These free fats then clog and block the oxygen carrying red blood cell from entering the tissues. Oxygen is thus reduced to the brain and body cells, which cause many internal disorders. All fats animal or vegetable if eaten beyond the needs of the body, can cause the following diseases; gallstones, diabetes, tumors, skin diseases, liver disorders, obesity, colitis, cancer, heart disease, lung disorders etc.

Human requirements for fatty foods are very low. We do not need an extra abundance of free fats in our diet; this only leads to ill health. Obtain your fats from whole foods in their natural state, and watch your health improve tremendously. When you realize that each body cell is a small battery, needing constant recharging through the food you eat, you will really begin to think about diet.

Fig. 5.2. Life starts with nature and blooms with Life.

Whole Food Supplements

Why cannot we obtain good nutrition from wholesome food in its natural state? We agree that under idea conditions, food supplements would not be needed. But what is considered ideal conditions? They are: 1.) All foods grown in rich, natural, organically fertilized soils year around. 2.) These organically grown foods should be available and raised in your locality. 3.) Living in a totally stress free, natural and unpolluted environment. Are you living in this naturally perfect environment? Are you obtaining all your food from such organically rich soil? Are you eating the organic food grown in your locality, not shipped from across the country? Are you living and working outdoors daily under natural lights, and without stress conditions? Do you spend hours each day in the outdoor atmosphere? Do you obtain suffcient exercise?

The majority of individuals cannot answer yes to most of the above questions: They can tremendously benefit from the daily use of natural whole food supplements and organic food concentrates, which furnish the missing organic minerals, vitamins and trace elements required by every cell of the body.

If one constantly craves junk foods, a dietary deficiency may be present and one may be severely in need of a balanced dietary program, plus whole food supplements. These nutrition rich food concentrates can help one to overcome the junk food syndrome and protect against any possible deficiencies from the use of commercially grown mineral poor foods.

Our first obligation to ourselves and our families should be to obtain the highest quality food grown locally, prepared in a nutritionally healthful manner and also, if conditions permit, to grow as many organic foods as possible in our own backyard garden. If we all had our own gardens on well mineralized fertile soil, vitamins might not be needed. If we ate foods that were not overprocessed and overmilled, the capsule might never have been invented. If we ate for nourishment rather than for palatability and if sixty times as much mineral values were not taken each year from the soil as are restored to it in fertilizer, and if in some households up to 77% of the mineral values were not lost or destroyed by heat and oxidation, we would not require the use of food supplements.

There are those who would have the Western public believe that present day foods are adequate in their vitamin and mineral content and that vitamin deficiency diseases and subclinical deficiencies are too rare to be a threat to public health. The majority of Americans are poorly nourished and consume nutritionally poor food. Hereditary factors also play an important part in your over-all health and nutritional needs. If your parents were in poor health and consumed mineral deficient foods, you may require more food supplements than a person who had parents with strong and healthy constitutions and ate mineral rich and nutritionally superior organic foods. One must judge their own nutritional needs and eat the whole foods and food supplements that fulfill the requirements of their totally individual body.

Food supplements should not be taken with the erroneous idea that they will give one Super Health while living on a diet of conventional calamity foods. They will, however, add some improvement to the conventional Western diet. It is true that food supplements would not be necessary if our food crops and top soil were rich in organic mineral elements, and all of our foods were grown on chemically free soils: unfortunately, these quality foods are a rarity, and as a result, most persons consume mineral deficient foods, causing malnutrition.

The following food supplements are some of the best known health aides to insure us of obtaining complete nutrition for superior health. Use them daily.

Alfalfa (Liquid, Tablets or Powder)

This amazing plant travels 24 feet into the soil and picks up the trace minerals that the average person is so lacking in. Alfalfa contains 8 essential enzymes, which help in the buildup of the internal bodily enzymes. Alfalfa closely approximates the blood hemoglobin, and is one of the most highly potent vitamin and mineral foods. It is rich in protein and contains every essential amino acid.

Many diseases are caused not only from excesses, but also from deficiencies of the necessary trace elements to maintain the body in proper chemical balance. If the body is not in balance, it can lead to a host of diseases from colds to cancer. Alfalfa grown on organic soil and made into liquid, tablet, powder or tea can be used with great benefit by all persons, healthy or sick.

The ancients knew its value, yet men forgot the ancient learning. For centuries sick farmers watched their cattle grow sleek and robust on alfalfa without the glimmer of an idea that this remarkable plant might help them. Even today, when food scientists cite the countless cases of benefits achieved by the use of alfalfa, the uninformed raise skeptical eyebrows. It may be a generation before most of our physicians and the general public wake up and grasp the truth about the place of alfalfa in human nutrition.

The same opinion was voiced by C. H. Burgess of the Michigan State Agricultural College, who said: "Rich in medicinal properties beneficial to the human race, the real value of alfalfa is but little known." But, with the passing years, the evidence that alfalfa has more total food minerals and trace elements than any other known plant that grows on land is beyond dispute. The famed farmer-writer, Louis Bromfield spoke of alfalfa's unique ability to tap the deep mineral richness of soil and to bring that richness upward to the sunlight and the air. The alfalfa root will reach down, in some instances, as much as 125 feet in order to do so.

Alfalfa is an excellent food; it improves digestion and a lagging appetite, as it is filled with several digestive enzymes:

Lipase Fat splitting enzyme.
Amylase acts upon starches.
Coagulase coagulates milk and clots the blood.
Emulsin acts upon sugar.
Invertase converts cane sugar into dextrose.
Peroxidase has an oxidizing effect on the blood.
Pectinase forms a vegetable jelly from a pectin substance.
Protase digests protein.

Alfalfa contains Vitamin U, an element that is an aid for peptic ulcers. It is a good diuretic and excellent regulator of the bowels. It has sufficient Vitamin D and phosphorus to build strong bones and teeth. Alfalfa has Vitamin K, flavones, growth and anti-stiffness factors. This remarkable product helps to prevent fatigue, and provides a perfect calcium-phosphorus ratio (2:1). The pure vegetarian or vegan, who uses no dairy products will be happy to know that alfalfa has .3 meg of Vitamin B-12 per 100 grams, and contains all essential amino acids.

Kelp and Seaweed

Kelp is a great source of iodine. Our soils are almost totally lacking in this very essential element. This is why certain sections of the country are known as goiter belts. Iodine is necessary for the proper functioning of the thyroid gland, which effects body growth, metabolism and over all health.

Hiziki and nori are also good seaweed products to include in salads, soups, or grain and bean dishes. Kelp and dulce are sea plants high in iron and copper, even more so than a pound of spinach or 7½ pounds of tomatoes. It contains more phosphorus than 1½ lbs. of carrots and more iodine in kelp than in oysters.

Scientific tests have shown that seaweed contains over thirty vital mineral elements and life sustaining organic substances that are absolutely necessary for a high state of health. The body loses these essential minerals daily, and they must be replaced by organic mineral-rich foods such as found in seaweed products. Here are a few of the major minerals and trace elements found in kelp:

Nitrogen helps to build and repair the body.
Iodine prevention against goiters.
Iron Blood Builder.
Copper together with iron builds the blood and helps the body to absorb oxygen.
Silicon helps to give beautiful sheen to the hair, nails and skin; prevents wrinkles and sagging skin.
Sodium helps to digest food, purifies the blood and prevents acidosis.
Sulphur builds the body cells.
Manganese builds the reproductive organs and is necessary for bone formation. It is a protective agent, especially for the heart, blood vessels, brain, and urinary passages.
Zinc helps prevent diabetes and prostate problems.

Kelp, dulce or other seaweed foods can be purchased in dried, powdered or liquid form. You can eat them whole, chew the kelp tablets, add the liquid to soups or sprinkle the powder over your favorite vegetable salads and grain meals. Kelp is a Yang food and can be consumed year around. Be sure to include kelp in your daily diet for better health and long life.

4. Activate the Eight Elemental Forces of Nature and the Universe

Activate all eight forces; wind, mountain, fire and thunder on the east. Earth, lake, water and heavenly power on the west.

Call the Eight Forces; fire, water (ocean), thunder (lightning), lake (rain), earth, mountain, wind, and heaven.


Fire-Li
Yang
Wind-Sun
South
Thunder
Lightning
Chen
East
West
Lake-Tui
Rain
Mountain
Ken
Heaven
Chien
North
Water-Kan
Yin

__Fig. 4.16__ Activate the Eight Forces.

Nutritional Yeast

Brewer's Yeast from beer breweries is a thing of the past. Yeast, as a supplement many years ago, was available only as a by-product of the beer vat. Today, it is no longer associated with the brewing industry, although many people still call it Brewer's Yeast. The correct name now is primary grown nutritional yeast.

A recent science writer once called the tiny yeast cell a terrific chemical factory for the manufacture of all the vitamins of the B complex. The yeast cell is a terrifically small unit of living matter, and similar to the cells of the human body. Many health authorities state that yeast contains more nutritional power than any other single food factor known to man. Yeast, as a food is grown without soil, takes up very little space in its growing process. Nutritional yeast has a very pleasant taste and is higher in nutritional value than the old time Brewer's Yeast.

The ancient Egyptians are said to have used yeast; and it has been used for baking, brewing and other uses throughout history. "Yeast is the smallest of all cultivated plants about l/4000th of an inch in diameter or about the size of a human blood corpuscle, as written in "The Complete Book of Food and Nutrition," edited by J. I. Rodale. Rodale continues:

The yeast plant stores enormous quantities of vitamins for its own use. These are then utilized as a food supplement by human beings, after the yeast plant is dried. Brewer's Yeast contains all the elements of the Vitamin B complex. It is also a rich source of complete protein. Brewer's Yeast contains 16 of the 20 amino acids forms of protein that are essential for the proper functioning of our bodies for longevity, for resistance to disease, for rebuilding tissues.

Nutritional yeast is reported to contain anti-aging and youth sustaining elements called nucleic acids RNA and DNA. Laboratory tests have shown that RNA and DNA protect mice and rats against lethal radiation doses. Yeast also contains the amino acids lysine and tryptophan, which may be missing from certain cereal and grain foods. Due to Its high natural B-Complex factors and minerals, it helps to build strong nerves and calmness under stress and other living conditions. A lack of the essential B Vitamins results in nerve disorders, irritability, depression, fatigue, skin problems, muscular weakness and underweight conditions. Nutritional yeast can put an end to the junkyism syndrome once and for all. It is rich in essential super food factors necessary for complete nutrition. It is one of nature's most complete and perfect foods. Yeast cakes used for baking bread should not be eaten raw, as they rob the body of B Vitamins.

Yeast is a miniature sprout of high nutritional value, and is dried in such a manner as to preserve its wealth of nutrients. Nutritional yeast can be used in soups, salads and other dishes to improve the nutritional value of foods. Yeast is also available in various concentrated forms in powder, flakes or tablets. Some people prefer to take yeast mixed in a glass of their favorite juice on an empty stomach, assuring quicker assimilation and no digestive interference with other foods. If yeast causes you gas, when eaten with other foods, try this method.

Miso

Miso is a dark paste made from fermented soybeans and other grains. The three types of miso are: Rome, made from soybeans and rice; Mugi, made of barley and soybeans and Hacho made soybeans only. Miso is aged from 3 to 18 months in wooden barrels, depending on the type. Hacho miso should be used more in winter due to its Yang quality. Mugi or Kome miso can be used moderately in the summer. Miso is a healthful salt substitute, which can be used in soups, bean and grain dishes, casseroles and wherever a salty flavor is required in cooking. Miso is one of the best sources of iron and vitamin B-12. Due to its fermented quality, miso builds up the intestinal flora & helps to overcome anemia.

Miso broth aids digestion and food absorption; it helps to alkalize the system, and balances the metabolism. It can be sipped slowly on cold winter days to keep one warm and cozy on the inside. Miso is also a protein source.

Soya Sauce

Soya sauce is a close kin to miso also fermented and made from soybeans with the addition of sea salt, wheat and water. It contains easily absorbed proteins, vitamins and minerals. Soya sauce can be used in soups, vegetable and grain dishes.

Tofu

Tofu is a soybean product with a consistency of farmer's or pot cheese. It is a very delicious, nutritious protein packed food. It can be used in soups, salads, sandwich spreads, grain, bean and vegetable stews. It contains vitamin B-12 and builds friendly intestinal bacteria, due to its fermented quality. Tofu is a highly concentrated food, containing all of the amino acids necessary for healthy growth.

Beet Juice *(Tablets or Powder)*

Beets are a powerful blood builder, with a high and easily assimilable iron content. It is used in diabetic disorders. Beets contain several digestive enzymes. Beets should be used only in small amounts because they may overwork the liver if over eaten.

Garlic

Garlic has been used successfully for high blood pressure, intestinal problems, colds, flus and lung disorders. Chinese herbalists caution against the use of garlic and sweets at the same time, as this mixture can cause nausea and indigestion. Garlic should not be used excessively every day, as the body will begin to emit a garlic odor in public, and one may chase away more than colds.

Garlic is also a powerful internal germicide and bactericide, keeping the system free from pathogenic or cancer causing agents. Garlic is used by all of the long lived people throughout the world.

Balanced Mineral Salt

This is a seasoning vegetable powder to be used in place of the salt shaker. It contains minerals and trace elements in balanced pro-portion, such as powdered soy beans, anise seed, calcium-magnesium phosophate, dulce, parsley, lecithin, vitamin C, rosehips, thyme and other dried vegetable ingredients. It can be used on all main dishesgrains, beans, vegetable stews, soups etc. It is very delicious and nutritious.

Calcium *(Carrot-Poxtoer)*

Calcium is one of the most important, but difficult to obtain foods in the dietary. This calcium supplement is made from pure fresh raw carrot juice, from high mineralized soil grown carrots dehydrated into a pure powdered concentrate and easily assimilable. Calcium is missing from almost all processed, canned and packaged super market foods. Calcium builds strong teeth, bones, hair, connective tissue and organic structures. One level teaspoonful of carrot-calcium supplies 1000 mgs. of pure calcium. The body requires from 800 - 1000 mgs. of this important element each day.

Umeboshi *(Salted)* Plum

Umeboshi Plums are pickled in salt for about two years, by an acid bacterial method. They have been used for centuries in Japan as a mainstay in cooking. They are used in main dishes, dressings and take the place of vinegar. They help to alkalize the system. Umeboshi Plums are used as remedies for stomach trouble, headaches and internal acidity; it aids the digestion and assimilation of food. It also helps in cases of dysentery and fatigue. They are especially delicious with rice and other grains.

Spirulina Plankton

Spirulina Plankton is a microalgae, like hijiki, nori and wakame. It grows in lakes and salt water, however, the best spirulina is said to come from fresh water ponds. The Aztecs ate spirulina over 400 years ago. They ate it with corn and millet. Spirulina is mass produced in two locations; from Lake Texcoco in Mexico and from Thailand. The nutrients in Spirulina are up to 95 percent digestible. Spirulina is twenty times as high in protein as soybeans, forty times as much as corn, 400 times as much as beef. Spirulina is low in the amino acid methionine, therefore, one should eat other grains, beans and seeds at the same meal or during the day to make up the loss. One tablespoon of spirulina contains:

6 to 7 Grams of Protein
35% of the RDA for Vitamin B1 - 25% of B2 - 6% of B3
90% of Carotene (Provitamin A)
10 % of Vitamin E
29% of Iron
(Small %) Trace Vitamins, Minerals and Enzymes

Spirulina Plankton is the most basic food in the whole food chain. It is a simple hydrocarbon made directly from photosynthesisthe interaction of sunlight and water. It is the most concentrated form of any known organic food; a complete protein containing 18 of the 22 known amino acids (the building blocks for living cells), including the eight essential amino acids. It contains the highest natural known source of Vitamin B-12, as well as many other vitamins, and all the cell salts and enzymes essential for body metabolism.

This new food from sunlight provides 4 times the protein power of beef 250% more Vitamin B-12 than liver 26 times the calcium of milk. Spirulina has incredibly long strings of amino acids of several kinds. The proteins of spirulina are 80-85% assimilated compared to 20% for beef protein. Spirulina is 65-71% protein; beef is about 18%. Spirulina contains the biologically active sugar rhamnose. The research on this effect was pioneered by Dr. Christopher Hills during his over 25 years of research into microalgae. Spirulina can be purchased in tablet, powder or liquid form. There is a new pasta on the market made with spirulina pastalina, a combination of wheat, soybeans and spirulina. It is delicious and highly nutritious. Spirulina is also helpful in removing radioactive agents and other pollutive metals from the body.

Herbs *(Elixirs of Life)*

“And God said, Behold, I have given you every herb yielding seed, which is upon the face of all the earthy and every tree, in which is the fruit of a tree yielding seed; to you it shall be for meat.” (Bible, Genesis-Chapter 1, Verses 29-31). Herbs are the true life-givers and healers of nature. Their use has become a lost art, but fortunately, they are gaining in popularity and usage by intelligent and advanced thinking physicians today. Herbs have been used since the beginning of time. The ancient Egyptians, Greeks, Lemurians and Chinese studied herbs systematically, and they respected the powerful rejuvenating qualities of nature’s healing plants.

Hippocrates, probably the first herbal physician to make an art of nature’s medicines, lived some 2,500 years ago. He is known as the Father of Medicine. Hippocrates believed in the powers of the human body to heal itself. And he used the constructive properties of herbs to facilitate the healing. He said: “The body has within itself the power to heal.”

About 1,500 A.D. Hohemhein began using inorganic chemicals to treat disease. He and the medical men that followed him believed that the body could be healed and purified chemically. They burned the books of Hippocrates and Galen, in public, for they wanted no competition from the natural methods of healing. Medical men wanted full power over the lives of sick people, to administer chemicals in place of herbs. Hohemhein was the first practitioner to give mercury as a medicine.

The true successors and pupils of Galen and Hippocrates are the herbal doctors of Great Britain. Hohemhien's successors are today's modern medical profession. The early Native Americans were well-versed in the use of herbs and plants. They were seldom sick, always full of vitality, stamina, endurance and fighting force. Our first colonists learned many things from the Native Americans; the use of herbs in the treatment of disease and maintaining vigorous health.



Fig. 5.3. Red Emperor, Shen-Neng, Patron Saint of Chinese Herbalism

Biblical Records

Moses taught the Israelites to subsist on natural simple foods and to use the herbs of the field for disease. The Good Book also instructs us to eat the fruit of the trees as nourishment and the leaves or herbs of nature for medicine. Paul recommended the consumption of herbs for fatigue and sickness.

The best Biblical argument for the use of natural foods and herbs is found in Gen. 1:29, which states: “And God said, Behold, I have given you every herb bearing seed, which is upon the face of all the earth, and every tree in which is the fruit of a tree yielding seed; to you it shall be for meat”. Leave your drugs in the chemises pot if you cannot heal the patient with food. He who for an ordinary cause resigns the fate of his patient to mercury (chemicals) is a vile enemy to the sick.

Herbs for Life, Health and Vitality

Hippocrates relied on the course of nature to restore health. He taught Moderation in all things. He had a working knowledge of over 400 various herbs. He was a true physician. Inter-estingly, the word physician is derived from physics, a Greek work for nature. So, Hippocrates was a doctor of nature. Nature has provided man with herbs in all parts of the world. Herbs are natural remedies; modern medicines are alkaloid chemicals taken from a plant and do not contain the health-building and restoring properties as herb teas used from the original plant. Medicines only relieve symptoms temporarily, while herbs and natural foods are more beneficial in the long run to restore and maintain health indefinitely. Given the proper care and nourishment, our bodies will remain free from disease.

Dr. Otto Mausert states that: “Chemistry of today has accomplished wonderful results in many ways, but all the laboratories in the world will never be able to supplant the remarkably fine process which takes place in the living cell. They will never successfully imitate the wonderful methods that Nature uses in performing its work in the plant, as well as in the human body.”

The great American inventor, Thomas A. Edison, once wrote: “Until man duplicates a blade of grass, Nature can laugh at his so-called scientific knowledge.”

Drugs vs. Plant Herbs

Herb teas assist nature in purifying the body, while chemical medicines squelch the symptoms and drive the disease deeper into the body, latrogenic diseases (drug induced) side-effects are far more harmful than the original sickness. This is the result of direct drug interference of the body's own natural healing powers.

Modern medical drugs are powerful-reacting chemical agents; most of them are Yin-expanding in action, while a few are Yang-contractive in quality. The Yin drugs spaces out or expands the brain and body cells, causing one to lose sight of reality, i.e., grogginess, loss of will and unclear thinking and perception. Hospitals and clinics are full of pickled brains and bodies. The list of drug induced diseases is growing every year. The AMA admits there is always a great risk in drugging a person. Chloromycetin, for example, is toxic to the blood producing system. About 20% of the drugs in vogue 20 years ago are now listed as harmful, yet many were considered wonder-drug discoveries.

Why is the average person very careful about the new car he buys? It must be perfect in every respect. The owner has it checked every few months to insure that it runs like new. He would not think of putting sand or water in the gas tank; No! The best grade of gas and oil must go into that car, and it must have the best possible main-tenance and care available at all costs. And the auto-mechanic must fix it right, or the owner does not pay him. Yet, the average person blindly accepts, without a word of objection, a dose of some medicine, tablet or drug, without thinking of what it might do to his or her body. Or more harmful serums and vaccines are injected into the bloodstream without a whimper or question as to what the substance is, or what value or harm it will do.

In his new book, "Herb Growing for Health," Dr. Donald Law writes: "The whole theory of botanic medicine is based upon the logical and simple practice of building up the human body to strengthen all the natural eliminating and healing processes. . ." "Botanic medicine does not seek to cure you by "killing off germs", it strengthens your natural func-tions of phagocyte production, (the little cells that eat up alien organisms invading your body); it strenghtens your liver and kidneys to do their clearing out functions better, and It makes defecation and perspiration function effeciently so as to expel the toxic matter you have acquired."

Another intelligent author, Dr. Otto Mausert, writing in his book, ‘‘Herbs for Health,’’ states: “Herbs contain the vital elements, vitamins and organic minerals that are deficient or lacking in the diseased body. They contain them in such a finely distributed and prepared state that they may be readily assimilated by the system and conveyed to the blood. Herbs also promote the elimination of waste matter and poisons from the system by simple, natural means. When correctly used, they support nature in the fight against disease.”

In the future, science promises to those races who will take advantage of the newer knowledge of nutrition, a larger stature, greater vigor, increased longevity and a higher level of cultural attainment. Those who travel go nowhere until they journey within. They who see are blind and see not, until they look within. They who seek the Tao, find not, until they know the Tao is within. Credo of a Taoist: Feel like a boy, act like a gentleman, speak like a saint, and work like a horse, because the journey is within.

Health Aide Guide:

Foods to Avoid	**Replacements**
Tea, Coffee, Alcohol, Sodas, Tap Water	*Herbal Teas*
Chocolate, Candy, Artificial Sweets	*Dried or Fresh Fruit, Honey*
Gelatin	*Agar*
Canned Bouillon, Meat Broths	*Vegetable Broth, Miso*
Cold Drinks, Sodas, Sugared Beverages	*Fresh Fruit & Vegetable Juice*
Tap Water	*Spring, Distilled or Pure Water*
Devitalized Commercial Sugared Cereals	*Whole Grain Cereals*
White Commercial Crackers & Snacks	*Rye Krisp, Corn & Wheat Chips*
White Bread	*100% Whole Wheat, Rye Breads*
Lard, Margarine, Butter	*Sesame, Tahini Sauce, Seed Butters*
White Vinegar, Wine Vinegar	*Lemon Juice, Apple Cider Vinegar*
Commercial Vegetable Oils	*Cold Pressed Olive & Sunflower Oils*
White Rice, White Flour Noodles	*Whole Brown Rice, Noodles & Pasta*
Cow Milk Cheeses & Other Dairy Foods	*Tofu, Soy Milk, Seed & Nut Milks*
Salted, Roasted Seeds & Nuts	*Raw Soaked Seeds & Nuts*
White Flour Pastries	*Whole Grain Baked Pastries*
Meat, Fish, Fowl, Eggs	*Seeds, Grains, Legumes, Nuts*
Common Salt, Pepper, Condiments	*Kelp, Dulce, Thyme, Parsley, Ginger*
Spices, Mustard, etc.	*Vegetable Seasoning, Tamari, Sea Salt*
Baking Powder	*Nutritional Yeast, Wheat Germ*
Pasteurized Cow's Milk & Cheeses	*Raw Cow's Milk, Yogurt & Goat Milk*
Food Thickening Agents (Eggs, Gelatin)	*Arrowroot, Agar, Seaweed*

Chapter 6

Transformations of the Five Elements and Yin/Yang Within

From the eternal Tao or creative force of the universe evolves Yin and Yang. The cycles of Yin and Yang produce the five elements of earth, which in turn produce all other physical phenomena: Wood, Fire, Earth, Metal (Air), and Water. The universe is the macrocosm of which humans are the microcosm and subject to the interplay of these five ancient forces. The five elements/transformations operate according to natural rhythms, i.e., seasonal changes, the moon's influence on agriculture and oceans, astrological changes, daily, monthly and yearly nutritional variations and variable psychological patterns.

The Theory of the Five Elements/Transformations is attributed to the Nei Ching, The Yellow Emperor's Classic of Internal Medicine, which dates back to the Chinese physician Chang Chuug-Ching in the second century A.D. Subsequent Chinese philosophers and physicians have since contributed material to the Nei Ching, which now contains twenty-four books.

Other groups of five elements include: The five Yin body organs, the five Yang organs, the five sense organs, the five tastes, the five planets, the five grains, the five directions, the five emotions etc.

Five Elements in Life

All biological forms are made up of these five elements, for life is a dynamic interplay of both heaven and earth Yin and Yang respectively. We may live a healthy and harmonious life by applying these universal principles to our everyday needs whether it be to overcome a disease, to use observational diagnostic procedures, to plant crops and to measure our everyday nutritional requirements.

Huang-Ti, the Yellow Emperor, is respectfully known as the father of Chinese Medicine. He is the author of the Huang-Ti-Nei-Ching Yellow Emperor's Classic of Internal Medicine written about 6,000 years ago.

In the next sections F,G,H,I are practices that are for cleaning the cells. The more you clean the cells the more the Cosmic Healing can take place.

F. Chi (Sacred) Water Practice

The Sacred Water practice (also known in the West as Holy Water) is to exercise the right of being the creators of the Cosmos. With strict and absolutely regular daily water intake to prevent the stresses and associated damages of dehydration, the chief conductor and supervisor of the body's well being – tryptophan and its neurotransmitter derivatives, serotonin, tryptamine and melatonin will be well positioned to regulate all functions. Regular daily walks will keep muscles well coordinated and correct any physiological processes that are established in the body as a result of anxiety or emotional stress.

A well hydrated and healthy skin needs water to constantly replace that which it loses to the outside environment. This then allows blood vessels to the face and the body to open up and provide necessary nourishment for exposed skin cells.

Science has discovered that even if we clean water through filtration processes, although it may look and taste alright, closer analysis using high powered microscopic technology, indicates that its cell structure is 'unclean'. Water, like humans, maintains the memory of its old 'self'. We store our 'memory' within our DNA; water stores its memory within its cells.

The world is about 70% water


You are about 70% water and remain so.
Thirst Center

Fig. 4.17 *Water is Life.*

Fig. 6.1. Huang-Ti, the Yellow Emperor

The Five Elements are not only expressed as physical reality fire, earth, metal (air), water and wood but are more intimately associated with the energy they express in their formation. These energy transformations are used in oriental diagnosis, massage, acupuncture, shiatsu, exercise therapy and dietary considerations.

Each of the Five Elements give birth to a corresponding food flavor; Wood creates the sour, Fire creates bitter, Earth creates sweet, Metal creates a hot (pungent) taste and Water creates a salty flavor. Each organ corresponds to one of the five different flavors and the body requires each of these flavors in a moderate amount daily. An excessive intake of one flavor will harm the associated organ and its corresponding one, i.e., an excessive intake of the sweet flavor injures the stomach/pancreas, the associated organs, and also harms the corresponding organ the Kidneys. The key is to balance the five flavors according to seasonal changes and inner biological needs on a day to day basis. If one consumes an excessive amount of salty foods, one will automatically desire or crave sweet foods to create a balance in the taste, which corresponds to an inner (organ) physiological need.


Burns to Become
(Fire)
Whose Ashes Decompose
Into the
(Earth)
Where Born and
Mined
(Metal)
Which Melts & Becomes
(Water)
Which Nourishes
Trees and Plants
(Wood)
Which
Creates
Creates
Creates
Creates
Creates
East
South
Center
West
North
Summer
Cultivate
Bitter
Fire
Heart
Speech
Joy
Spring
Sowing
Sour
Wood
Liver
Sight
Anger
Late Summer
Sweet
Earth
Spleen
Taste
Sympathy
Autumn
Harvest
Pungent Hot
Metal
Lungs
Smell
Grief
Water
Store
Salty
Water
Kidney
Hear
Fear
Penetrates
Melts
Extinguishes
Cuts
Cut Off by

Fig. 6.2. Five Element Relationships

The Nei Ching explains the five elements in various relationships as follows:

Five Fluid Secretions as connected with the Viscera:

Perspiration is connected with the Heart.
Mucus is connected with the Lungs.
Tears are connected with the Liver.
Saliva is connected with the Spleen.
Spittle is connected with the Kidneys.

Five Climates as they affect the Viscera:

Heat injures the Heart.
Cold/Dry injures the Lungs.
Wind injures the Liver.
Humidity injures the Spleen.
Dryness/Cold injures the Kidneys.

Controls exerted by the Viscera:

Heart controls the ***Pulse***.
Lungs control the ***Skin***.
Liver controls the ***Muscles***.
Spleen controls the ***Flesh***.
Kidneys control the ***Bones***.

Effect of the Flavors upon the body:

Excess of ***Salty*** flavor hardens the Pulse.
Excess of ***Bitter*** flavor withers the Skin.
Excess of ***Pungent*** flavor knots the Muscles.
Excess of ***Sour*** flavor toughens the Flesh.
Excess of ***Sweet*** flavor causes aches in the Bones.

Five Spiritual Resources as Controlled by the Viscera:

Liver controls the ***Soul***.
Heart controls the ***Spirit***.
Spleen controls the ***Ideas***.
Lungs control the ***Animal Spirit***.
Kidneys controls the ***Will Power***.

Effects of the Five Flavors:

Pungent flavor has a dispersing effect required in ***Fall***.
Sour flavor has a gathering effect required in ***Spring***.
Sweet flavor has a retarding effect required at ***All Times***.
Bitter flavor has a strengthening effect, required in ***Summer***.
Salty flavor has a softening effect, required in ***Winter***.

Injuries caused by Season's Climate following Next Season:

Injuries caused by the ***Cold of Winter*** cause a recurrence of the ***Illness in Spring***.
Injuries caused by the ***Wind of Spring*** make people unable to ***Retain Food in Summer***.
Injuries caused by the ***Heat of Summer*** cause intermittent ***Fever in Fall***.
Injuries caused by ***Humidity of Fall*** cause ***Cough in Winter.***

Five Organs and Body Relationships:

Heart is connected with the ***Pulse*** and rules over the kidneys.
Lungs are connected with the ***Skin*** and rule over the heart.
Liver is connected with the ***Muscles*** and rules over the lungs.
Spleen is connected with the ***Flesh*** and rules over the lungs.
Kidneys are connected with the ***Bones*** and rule over the spleen.

Five Nourishing Organ and Body Relationships:

The liver nourishes the muscles; the muscles strengthen the heart; the liver governs the eyes.

The heart nourishes the blood and the blood strengthens the stomach; the heart rules over the tongue.

The stomach nourishes the flesh; the flesh strengthens the lungs; the stomach rules over the mouth.

The lungs nourish the skin and the hair; the skin and the hair strengthen the kidneys; the lungs govern the nose.

The kidneys nourish the bones and the marrow; the bones and the marrow strengthen the liver; the kidneys rule over the ears.

Five Moods in Relation to the Organs and Daily Time Cycles:

People troubled with liver disorders appear mentally alert during the morning hours, are active and bright toward sundown and of quiet mind at midnight.

People troubled with heart disorders are mentally alert at noontime, active and bright at midnight & quiet in the early morning.

People troubled with spleen disorders are mentally alert just after sundown active and bright at sunrise, and are quiet during the afternoon.

People troubled with lung/respiratory disorders are mentally alert just before sundown active and bright at noon, and are quiet at midnight.

People troubled with kidney disorders are mentally alert at midnight, active and bright during the last days of the four seasons, and are most quiet before sundown.

Five Element Creation Cycle:

Wood burns to create ***Fire***.
Fire leaves behind ashes and compose into ***Earth***.
Earth which are created and mined and become ***Metal.***
Metal which if heated and melted become molten like ***Water***.
Water produces & nourishes trees, plants & ***Wood.***

Five Element Destruction Cycle *(Subjugation)*:

Wood is cut and felled by ***Metal***.
Fire is extinguished by ***Water***.
Earth is penetrated by ***Wood***.
Metal is dissolved or melted by ***Fire***.
Water is halted, absorbed and obstructed by ***Earth***.

Five Emotional to Oragn Relationships:

Anger is injurious to Liver, but ***Grief*** counteracts Anger.
Extra Joy is injurious to Heart, but ***Fear*** counteracts Joy.
Extra Sympathy is injurious to Stomach, but ***Anger*** counteracts Sympathy.
Extreme Grief is injurious to Lungs, but ***Joy*** counteracts grief.
Extreme Fear is injurious to Kidneys, but ***Sympathy*** overcome fear.

Five Food Tastes and their Corresponding Organs:

Excessive Salt injures the heart, and the pulse hardens, tears make their appearance and the complexion changes.

Excessive Bitter injures the lungs, and the skin becomes withered and the body hair falls out.

Excessive Pungent food injures the liver, and the muscles become knotty and the finger and toe nails wither and decay.

Excessive Sour food injures the spleen and stomach, and the flesh hardens and wrinkles and the skin becomes slack.

Excessive Sweet food injures the kidneys, and the bones ache and the hair on the head fall out.


Pulmonary Artery
Descending Vena Cava
Arch of the Aorta
Pulmonary Vein
Ascending Vena Cava
Heart
Aorta
Lung
Spleen
Liver
Doudenum
Stomach
Gall Bladder
Left Kidney
Right Kidney
Descending Conon
Accending Colon
Cecum
Appendix
Right Common Iliac Artery and Vein
Left Common Iliac Artery and Vein
Small Intestines
Rectum

Fig. 6.3. This diagram shows the general position of the 5 major organs of the trunk, in relation to each other. The method by which veins and arteries maintain circulation of the blood is shown also.

	Metal	**Water**	**Wood**	**Fire**	**Earth**
Tissues:	*Skin*	*Bones*	*Nerves*	*Blood*	*Muscles*
Bodies:	*Emotional*	*Dream*	*Mental*	*Spiritual*	*hysical*
Mental:	*Sensitivity*	*Creativity*	*Thinking*	*Intuition*	*ontaneity*
	Non-Judgmental	*Concept*	*Planning*	*Communication*	*Judgment*
	Discrimination	*Will Power*	*Strategy*	*Consciousness*	*Cleverness*
Function:	*Detoxification*	*Creation*	*Elimination*	*Circulation*	*Digestion*
Kingdom:	*Jester*	*Queen*	*General*	*King*	*Prime Minster*

Solar Calendar (Western) 13 Weeks-Lunar Calendar (Chinese) 13 Months or 13 Cycles:
Sunday-Sun; Monday-Moon; Tuesday-Fire; Wednesday-Water; Thursday-Wood; Friday-Metal; Saturday- Earth.

Controlling Cycle (Ko Cycle):
Fire Forges Metal - Metal Cuts Wood - Wood Roots Earth - Earth Dams Water - Water Puts Out Fire
Wood Covers Earth - Fire Melts Metal - Earth Contain Water - Metal Cuts Wood - Water Puts Out Fire.

Emotions: Anger Injures Liver - Sadness Controls Anger - Excess Joy Hurts Heart - Fear Controls Joy - Sadness Affects Lungs - Joy Controls Sadness - Fear Injures Kidneys - Thinking Controls Fear.

Way of Yin and Yang

Nei Ching says:
The sages did not overexert their bodies at physical labour and they did not overexert their minds by strenuous meditation. They were not concerned about anything, they regarded inner happiness and peace as fundamental, and contentment as highest acheivement. Their bodies could never be harmed and their mental faculties never be dissipated. Thus, they could reach the age of one hundred years or more.

Those who rebel against the basic rules of the universe sever their own roots and ruin their true selves. Yin and Yang, the two principles in nature, and the four seasons are the beginning and the end of everything and they are also the cause of life and death. Those who disobey the laws of the universe will give rise to calamities and visitations, while those who follow the laws of the universe remain free from dangerous illness, for they are the ones who have obtained the Tao, the Right Way.

Tao was practiced by the sages and admired by the ignorant people. Obedience to the laws of Yin and Yang means life; disobedience means death. The obedient ones will rule while the rebels will be in disorder and confusion. Anything contrary to harmony (with nature) is disobedience and means rebellion to nature.

Hence, the sages did not treat those who were already ill; they instructed those who were not yet ill. They did not want to rule those who were already rebellious; they guided those who were not yet rebellious. This is the meaning of the entire preceding discussion. To administer medicines to diseases which have already developed is comparable to the behavior of those persons who begin to dig a well after they have become thirsty, and of those who begin to cast weapons after they have already engaged in battle.

No matter whether people are rebellious or obedient, there is method and regularity in the workings of the four seasons and Yin and Yang. Everything is subject to their invariable rules and regulations, which govern the relationship between external and internal influences.

Wisdom increases Longevity

Nei Ching continues:

Those who have the true wisdon remain strong while those who have no knowledge and wisdom grow old and feeble. Therefore the people should share this wisdom and their names will become famous. Those who are wise inquire and search together, while those who are ignorant and stupid inquire and search apart from each other. Those who are stupid and ignorant do not exert themselves enough in the search for the Right Way, while those who are wise search beyond the natural limits.

Those who search beyond the natural limits will retain good hearing and clear vision, their bodies will remain light and strong, and although they grow old in what the mind can conceive and years they will remain able bodied and flourishing; and those who are able bodied can govern to great advantage. In their pleasures and joys they (sages) were dignified and tranquil. They followed their own desires and they never directed their will and ambition toward the protection of a purpose that was empty of meaning. Thus their allotted span of life was without limit, like Heaven and Earth.

Yang, the lucid element, ascends to heaven. Yin, the turbid element, returns to earth hence the universe (Heaven and Earth) represents motion and rest, controlled by the wisdom of nature (the Tao). Nature grants the power to beget and to grow, to harvest and to store, to finish and to begin anew. The Humankind of Virtues matched heaven when they cultivated their minds; they resembled the earth when they provided sufficient nourishment; and they were by the side of the people in the care of the five viscera.

The heavenly climate circulates within the lungs; the climate of the earth circulates within the throat; the wind circulates within the liver, thunder penetrates the heart; the air of a ravine penetrates the stomach; and the rain penetrates the kidneys. The six arteries generate streams; the bowels and the stomach generate the oceans; the nine orifices generate flowing water; and heaven and earth generate Yin and Yang (the two opposing principles).

The laws of nature are just, but terrible. There is no weak mercy in them. Cause and consequence are inseparable and inevitable. The elements have no forbearance. The fire burns, the water drowns, the air consumes, the earth buries. And perhaps it would be well for any race if the punishment of crimes against the laws of humans were as inevitable as the punishment of crimes against the laws of nature, were humankind as unerring in thier judgements as nature.

Fig. 6.4. What the mind can conceive and believe, the mind can achieve is inherited in the wisdom of the Tao.

Transformations of the Five Elements

	More Yang	Less Yang	Center Yin/Yang	Less Yin	More Yin
Five Elements:	Wood	Fire	Earth	Air	Water
Yang Organs:	Liver	Heart	Spleen/Pancreas	Lungs	Kidneys
Yin Organs:	Gall Bladder	S.Intestines	Stomach	L.Intestine	Bladder
Inner Anatomy:	Muscles	Blood Vessels	Flesh	Skin	Bones
Outer Anatomy:	Nails	Complexion	Breast/Lips	Hair/ Breath	Head Hair
Sense Organ:	Eyes	Tongue	Mouth	Nose	Ears
5 Senses:	Sight	Speech	Taste	Smell	Hearing
Body Fluids:	Tears	Sweat	Saliva	Mucous	Urine
Direction:	East	South	Center/Earth	West	North
Climate:	Windy	Hot	Humid	Dry	Cold
Seasons:	Spring	Summer	Late Summer	Autumn	Winter
5 Sounds:	Shouting	Laughing	Singing	Weeping	Groaning
5 Emotions:	Anger	Joy	Worry	Depression	Fear
Body Changes:	Control	Anxious	Sobbing/Belch	Coughing	Trembling
Creation:	Inspiration	Aspiration	Intellect	Dominance	Will
5 Functions:	Color	Odor	Taste	Voice	Fluid
Skin Color:	Blue/Grey	Red	Yellow/ Milky	Pale	Black/Dark
Daily Periods:	Morning	Noon	Afternoon	Evening	Night
Weather:	Crisp/Dry	Fog/Mist	Mellow	Snow	Ice/Frost
Planet:	Jupiter	Mars	Earth/ Saturn	Venus	Mercury
Monthly Cycle:	(+)Half-Moon	Full Moon	Hidden Moon	(-)Half-Moon	New Moon
Number:	8	7	5	9	6
Color:	Green	Red	Yellow	White	Black
Controler:	Spiritual	Soul	Mind	Ambition	Body Strength
Energy:	Upward	Active	Downward	Solidified	Floating
Examples:	Gas	Plasma	Condensation	Solid	Liquid
	Tree	Heat	Soil	Metal	Water
5 Tastes:	Sour	Bitter	Sweet	Pungent	Salty
Grains:	Wheat	Red Millet	Yellow Millet	Rice	Legumes
Fruits:	Apple/Plum	Berries	Dates/Olives	Melon	Citrus
Vegetables:	Leeks	Shallots	Mallow	Onions	Greens
Foods to Avoid:	Rancid, Oily	Burnt	Fragrant	Rotten	Putrid
Disease Areas:	Nerves	Viscera	Tongue	Upper Back	Cavities
Modalities:	Prayer	Healthy Habits	Herbals	Acupuncture	Heat Therapy

Fig. 6.5. Classification of the Five Elements and Transformations

Liver & Gall Bladder Conditions

General Toxicity Signs of Malfunctioning Yin or Yang Liver and Gall Bladder

Blockage of the Tear Ducts or Excessive Tears
Soft Ridged Nails
Poor Vision and Light Sensitivity
Bloodshot Eyes
Shouting and Anger
Weak Knees and Muscles
Fuzzy Thinking
Liver Pain (Under Right Rib Cage)

Symptoms of Yang (Contracted) Liver and Gall Bladder

Dizziness
Headaches
Red Eyes
Aversion to Heat
Impaired Hearing
Incomnia
Nosebleed
Cataracts
Irritability
Farsightedness

Symptoms of Yin (Expanded) Liver and Gall Bladder

Nausea
Poor appetite
Depression
Apprehension
Nearsightedness

Foods Discharge Toxins from Liver and Gall Bladder

Radishes
Potatoes
Lettuce
Mushrooms

Eaten Moderately Sour Foods Strengthen Liver and Gall Bladder

Grains	*Fruits*	*Vegetables*	
Wheat	Plums	Beets	Cabbage
Rye	Berries	Artichoke	Watercress
	Cherries	Celery	Burdock
	Apples	Leeks	Parsley

Liver and Gall Bladder are Weakened by an Excess of:

Fats, Butter, Dairy
Eggs and Vinegar
Nuts & Nut Butters
Sweets
Outdoor Wind
Overeating
All Rancid Fats & Oils
All Drugs
All Chemicals
Alcohol
Cold Drinks/Foods

These Herbs in Small Amounts Discharge Toxins from Liver/Gall Bladder

Burdock
Dandelion
Holy thistle
Golden Seal
Raspberry Leaf

These Yin Herbs Balance Yang Symptoms of Liver/Gall Bladder

Sage
Chaparral
Echinacea Root
Wild Yam
Oregon Grape

Yin Herbs Balance Yang Symptoms of Liver/Gall Bladder

Watercress
Garlic
Nettle
Slippery Elm
Licorice
Marshmallow

Mental Healthy Signs of Liver/Gall Bladder

Good Decisions and Ability to Make Plans
Confidence to achieve Success
Agreeable Personality and Disposition

1. *Excessive sour food injures the spleen and stomach, toughens and wrinkles the flesh, and the skin and lips become slack, and is balanced by a moderate amount of pungent food.*
2. *Excessive and/or lack of sour food injures the Liver and Gall Bladder.*
3. *Eat more steamed food during Spring to Strengthen Liver & Gall Bladder.*
4. *Anger is injurious to the Liver and Gall Bladder.*
5. *Excessive Running or Walking injures the Liver and Gall Bladder.*
6. *Excessive blowing wind injures the Liver and Gall Bladder.*
7. *A malfunctioning Liver and Gall Bladder causes Anger and Irritability.*
8. *A healthy Liver and Gall Bladder instills Peacefulness and Calmness.*

Fig. 6.6. Balancing Body Organs: Liver & Gall Bladder Conditions

The following three pages contain extracts from the book ‘The Message from Water’ by Masaru Emoto. It advises us that ‘water is telling us to take a closer look at ourselves - water is a mirror reflecting our mind.’

水からの伝言

After offering a prayer to the Fujiwara dam the message is reflected in the water.

When we project Chi and love into water and then freeze it; it will turn into a ‘regular’ and well structured crystal. If we project negative energy into water, the opposite will apply. Our projections will access the cellular level, clean out the polluted cells and reprogram those remaining with the essence of our affirmation.

When we project a nice, loving instruction or thought into water, like ‘let’s do it’ the water will pick up this vibration and restructure itself. If we project negativity into the water, like a command, ‘do it!’, the water will acknowledge this accordingly. When we look into a pond we see our image. If we drink a glass of negative image water its destructive energy will enter our system and attempt to multiply.



Chi and Love **Love-Appreciation**



Let’s do it **Do it!**

Fig. 4.18 *The Human Body consists of 70% Water.*

Heart & Small Intestines Conditions

General Toxicity Signs of Malfunctioning Yin or Yang Heart & Small Intestines

Swollen Nose and Hands
Cleft in Nose
Excessive Joy
Excessive Sweating or not at all
Excessive Laughing
Emotional Ups and Downs

Symptoms of Yang (Contracted) Heart and Small Intestines

Chest Constriction
Excess Perspiration
Dizziness
Stroke
Dry Palate
Back Pain
Laughing Fits
Little Talk

Symptoms of Yin (Expanded) Heart and Small Intestines

Shortness of Breath
Rambling Talk
Sorrowful and Listless
Sciatic and Lumbar Pains
Facial Pallor

Foods Discharge Toxins from Heart and Small Intestines

White Beans
Vegetables Oils
Seaweed
Beans

Eaten Moderately Sour Foods Strengthen Heart and Small Intestines

Grains	*Fruits*	*Vegetables*	
Red Millet	Apricots	White Beans	Pumpkin
Corn	Strawberries	Oils	Chickpea
Nuts	Cherries	Seaweed	Scallion
Almonds		Garlic	Burdock
		All Greens	

Heart and Small Intestines are Weakened by an Excess of:

Overdressing (Hot Clothing)
Burnt Food
Hot Drinks and Food
Excess Salt & Spice

These Herbs in Small Amounts Discharge Toxins from Heart/Small Intestines

Mint
Cayenne
Motherwort
Bayberry

These Yin Herbs Balance Yang Symptoms of Heart/Small Intestines

Black Cohosh
Caraway Seed

Yin Herbs Balance Yang Symptoms of Heart/Small Intestines

Borage
Gensing
Hawthorne Berry
Comfrey Root

Mental Healthy Signs of Heart/Small Intestines

Honesty and Integrity
Optimistic Personality
Poised in Mind and Body
Extends Love to Humanity and own Family

1 Excessive Bitter Food injures the lungs, whithers the skin, body hair falls out, stomach becomes congested, and is balanced by a moderate amount of Salty food.
2. Excessive and/or lack of Bitter foods injure the Heart and Small Intestines.
3. Eat more Raw food during Summer to Strengthen Heart & Small Intestines.
4. Excessive Joy and Excitement are injurious to the Heart & Small Intestines.
5. Excessive eye focusing, reading and close work weaken Heart & Eyesight.
6. Excessive Heat injures the Heart and Small intestines.
7. A malfunctioning Heart and Small Intestine causes Hysteria.
8. A healthy Heart and Small Intestine instills Happiness.

Fig. 6.7. Balancing Body Organs: Heart & Small Intestines Conditions

Stomach, Spleen & Pancreas Conditions

General Toxicity Signs of Malfunctioning Yin or Yang Stomach, Spleen & Pancreas

Ulcers
Drolling
Lack of Taste
Excess or Diminished Salavia
Vomiting
Heavy Limbs
Low Energy
Fatigue
Abdominal Pains
Mental Depression
A Sing-Song Voice
Obsession
Overweight
Intestinal Problems
Excessive Worry

Symptoms of Yang (Contracted) Stomach, Spleen and Pancreas

Watery Stools
Light Headedness
Flatulent Stomach
Constipation
Quarrelsome Moods
Sweet/Greasy Mouth Taste

Symptoms of Yin (Expanded) Stomach, Spleen and Pancreas

Indigestion
Heaviness
Emaciation
Diarrhea
Gastric Cramps
Nausea

Foods Discharge Toxins from Stomach, Spleen and Pancreas

Dark Greens
Herb Spices

Eaten Moderately Sour Foods Strengthen Stomach, Spleen and Pancreas

Grains	*Fruits*	*Vegetables*	
Yellow Millet	Dates	Squash	Dark Greens
	Olives	Parsnips	

Stomach, Spleen and Pancreas are Weakened by an Excess of:

Hot Food
Damp Clothing
Excessive Sweets
Eating too Fast-Overeating
Lack of Mastication
Damp Ground

These Herbs in Small Amounts Discharge Toxins from Stomach, Spleen/Pancreas

Ginger
Golden Seal
Gential
Juniperberry
Vervain

These Yin Herbs Balance Yang Symptoms of Stomach, Spleen/Pancreas

Lobelia
Fennel
Basil
Catnip

Yin Herbs Balance Yang Symptoms of Stomach, Spleen/Pancreas

Ginseng
Orange Peel
Fennel
Licorice

Mental Healthy Signs of Stomach, Spleen/Pancreas

Constructive Thinking and Action
Calm Disposition and Satisfaction
Sound Ideas and an Excellent Memory
Sympathetic Nature and a Balanced Critical Faculty

1. *Excessive sweet food injures the kidneys, causes hair loss, aching bones, and is balanced by a moderate amount of Sour food.*
2. *Excessive and/or lack of sweet food injures the Stomach, Spleen/Pancreas.*
3. *Eat more Stewed food during late summer to strengthen the Stomach, Spleen and Pancreas.*
4. *Extreme Sympathy, Moodiness and Worry is injurious to the Stomach, Spleen and Pancreas.*
5. *Prolonged Sitting weakens the Stomach, Spleen/Pancreas.*
6. *Excessive humidity (moisture) injures the Stomach, Spleen/Pancreas.*
7. *A malfunctioning Stomach, Spleen/Pancreas causes suspicion & mistrust.*
8. *A healthy Stomach, Spleen and Pancreas instills Trust.*

Fig. 6.8. Balancing Body Organs: Stomach, Spleen & Pancreas Conditions

Lungs & Large Intestines Conditions

General Toxicity Signs of Malfunctioning Yin or Yang Lungs & Large Intestines

Whimpering and Sorrow
Hemorrhoids
Sinus and Mucous Problems
Chest Congestion
Anguish and Helplessness
Bowel Difficulties

Symptoms of Yang (Contracted) Lungs and Large Intestines

Rapid and Deep Breath
Carcked Lips
Non-Productive Cough
Dry Rough Skin
Chest Pain

Symptoms of Yin (Expanded) Lungs and Large Intestines

Shallow Respiration
Shortness of Breath
Cold Hands and Feet
Never Thirsty
Drowsiness
Emaciation
Cramps
Loose Stools

Foods Discharge Toxins from Lungs Large Intestines

Green Peas
Cider Vinegar
Lemon
Tomato
Radish

Eaten Moderately Sour Foods Strengthen Lungs and Large Intestines

Grains	*Fruits*	*Vegetables*	
Rice	Peaches	Onion	Radish
Oats	Lemon	Comfrey	Cider Vinegar
Barley	Melons	Garlic	Hot Pepper
	Tomato	Green Pea	

Lungs and Large Intestines are Weakened by an Excess of:

Excess Fats
Excess Dairy
All Cold Foods
Under-Dressing in Cold Weather
All Cold Drinks
Excess Oils

These Herbs in Small Amounts Discharge Toxins from Lungs/Large Intestines

Horehound
Golden Seal
Wild Cherry Bark
Slippery Elm
Elecampagne

These Yin Herbs Balance Yang Symptoms of Lungs/Large Intestines

Pleurisy Root
Coltsfoot
Myrrh
Eucalyptus
Lobelia
Mullein
Garlic
Ginger

Yin Herbs Balance Yang Symptoms of Lungs/Large Intestines

Comfrey
Yarrow
Ohsa Root
Cayenne

Mental Healthy Signs of Lungs/Large Intestines

Physical Strength and Endurance
Good Mind and Body Rhythm
Harmonious Personality and Intuition
Buoyant Health and Vitality

1. *Excessive Pungent foods injure the liver, knot the muscles, slow the pulse and injure the spirit, and are balanced by a moderate amount of Bitter food.*
2. *Excessive and/or lack of Pungent food injures the Lungs/Large Intestines.*
3. *Eat more Baked foods during the Fall season to Strengthen the Lungs And Large Intestines.*
4. *Extreme Grief is injurious to the Lungs and Large Intestines.*
5. *Excessive lying down or sleeping weakens the Lungs/Large Intestines.*
6. *Excessive Dryness (Extreme Low Humidity) injures Lungs/Large Intestines.*
7. *Malfunctioning Lungs and Large Intestines causes Depression.*
8. *Healthy Lungs and Large Intestines instill Positiveness and Confidence.*

Fig. 6.9. Balancing Body Organs: Lungs & Large Intestines Conditions

Kidneys & Bladder Conditions

General Toxicity Signs of Malfunctioning Yin or Yang Kidneys & Bladder

Frequent Urination
Hair Loss
Arthritis
Scant Urination
Dandruff
Painful Joints
Poor Hearing
Weak Ankles
Backache
Moaning Sound
Sex Problems
General Fatigue

Symptoms of Yang (Contracted) Kidneys & Bladder

Dry Mouth
Excess Mucous
Fevers
Restlessness
Nymphomania
Painful Swelling
Cold Diseases
Perspiration after Eating

Symptoms of Yin (Expanded) Kidneys & Bladder

Soft Speech
Poor Memory
Impotence
Headaches
Ulcers
Fatigue
Weak Joints
Chills/Coldness
Swollen Legs
Indecisiveness

Foods Discharge Toxins from Kidneys & Bladder

Aduki Beans
Black Beans
Cider Vinegar
Oils (Vegetable)
Cirtus Fruit

Eaten Moderately Sour Foods Strengthen Kidneys & Bladder

Grains	*Fruits*	*Vegetables*	
Buckwheat	Grapes	Green Vegetables	Beans
	Grapefruit	Aduki Beans	Parsley
	Oranges	Black Beans	Seaweed
		Cauliflower	Cabbage
		Sea Salt	Miso

Kidneys & Bladder are Weakened by an Excess of:

Scalding Hot Food
Excess Sweets/Liquid
Scalding Hot Drinks
Drugs/Chemicals Alcohol
Excess Protein and Vinegar
Hot Clothing (Over-Dressing)

These Herbs in Small Amounts Discharge Toxins from Kidneys & Bladder

Raspberry Leaf
Plantain Leaf
Cleavers
Saw Palmetto
Nettles
Berries

These Yin Herbs Balance Yang Symptoms of Kidneys & Bladder

Juniper Berry
Parsley Leaf
Asparagus Root
Gravel Root
Myrrh
Dandelion

Yin Herbs Balance Yang Symptoms of Kidneys & Bladder

Oat Straw
Marshmallow Root
Horsetail

Mental Healthy Signs of Kidneys & Bladder

Excellent Concentration
Clear Beautiful Voice
Tenacious Will Power
Strong Sex Glands and Personal Magnetism

1. *Excessive Salty food injures the heart, causes high blood pressure, hardened pulse, and weak bones and is balanced by a moderate amount of Sweet food.*
2. *Excessive and/or lack of Salty food injures the Kidneys and Bladder.*
3. *Eat more Sauted Food during Winter to Strengthen the Kidneys/Bladder.*
4. *Extreme Fear and Moaning is injurious to the Kidneys and Bladder,*
5. *Prolonged Standing is harmful to the Kidneys and Bladder.*
6. *Excessive Cold Temperature injures the Kidneys and Bladder.*
7. *Malfunctioning Kidneys and Bladder cause Fear and Depression.*
8. *Healthy Kidneys and Bladder instill Courage and Fortitude.*

Fig. 6.10. Balancing Body Organs: Kidneys & Bladder Conditions

Using Herbs according to Five Elements

1. Use only the specific herb designated for a particular symptom or condition as explained in the Five Elements. Herbs should not be used indiscriminately without regard for their Yin or Yang qualities as is commonly practiced by most American herbalists. The Chinese Yin/Yang herbal system is far more accurate and scientific in their diagnosis, treatment and use of herbs.
2. Herbal teas are best utilized and assimilated on an empty stomach, in the morning, or before a meal. However, a small amount of tea may be used after a meal to help to assimilate fat eaten in the meal and aid digestion; no more than 2 to 4 ounces may be taken after meals, sipped slowly.
3. Herbal teas should be limited to one or two cups per day. An excess of an herb tea can cause a reverse condition or symptom in the body. The Chinese herbalists teach that what an herb can cure, it can cause the very same condition or problem, if it is taken in excess or the cause of the disorder is not stopped. For example, if one attempts to correct or balance Yang (contracted) constipation with a Yin herb, such as senna leaf tea, without removing the initial cause (overeating, white flour, salt, meat, dairy products etc.), the tea will help for a few days or weeks, temporarily, and the constipation will still remain a problem. If larger doses of senna leaf tea are taken to correct constipation, it will help for only short period of time, however, it will compound the problem by further weakening the intestines. The continuous use of laxatives, such as Senna leaf, in large doses, poisons and irritates the system. The body cures or heals itself; herbs are used only for remedial measures and to balance the organs and blood, provided the causes of the disorder are discontinued, and proper health and living habits are adopted. Herbs do not cure, they balance.

Another example: If one suffers from frequent or excessive urination, a Yin (expanded Kidney/Bladder) condition caused by an excessive consumption of liquids, fruits, juices, tropical fruits, melons, sugar etc. one or two cups per day of corn silk tea will help to constrict and strengthen the kidneys and bladder, and eventually correct the Yin condition, provided the above mentioned causes of the disorder are removed. Many herbalists today, recommend drinking large quantities of water, and using Yin herbs, i.e., parsley and Yin foods, i.e., cucumber and watermelon for kidney and bladder problems, without regard to whether the disorder is a Yin or Yang condition. If (Yin) parsley and Yin foods are used for Yin (expanded) kidneys and bladder, it will further weaken and expand them. Most herbs and herb teas should be used only to balance diseased conditions or symptoms. Discontinue their use after the health problem is overcome. Some herbs, such as alfalfa, dandelion, bancha, cinnamon, chicory, grain beverages, etc., can be consumed in small amounts (1 or 2 cups) daily for better health and enjoyment. Moderation in foods as well as herbs is the key to superior health.

4. Herbal teas should be used for short periods of time only (2 to 4 months); discontinue their use, or change to different herbs for your condition. Herbs are strong agents, and should not be used for too long a time, as the body will not respond or heal as quickly if used continually.

5. Yin herbal teas are used for Yang conditions and ailments, i.e., heavy meat, egg and salt consumers. Yang herbal teas are used for Yin condition, such as those who have been on a strict (Yin) raw food or fruitarian diet, or those eating excessively of fats and sugars, such as ice cream, cheese, sweets, donuts, soft drinks, etc.

6. Body Organs for the correct herbs used in balancing Yin or Yang diseased symptoms and for discharging toxins from the system. Use one or two herbs from the discharge toxins category; and one or two herbs from either the Yin or Yang category necessary for your specific symptoms or condition.

7. For specific disease conditions, herbs always remedy, correct and balance the system with optimum results when the cause or causes of disease (improper food, overeating, poor health habits, etc.) are eliminated and rational, healthful living and eating habits are adopted.

There is a delicious herb tea recipe is called Dr. Chang's Long Life Tea. It contains the following ingredients: Peppermint, Honeysuckle, Licorice, Ginseng, Cinnamon, Poria & Chrysanthemum.

Dr. Chang is trained in both Chinese and Western medicine, herbology, and acupuncture. He says this about herbs: "Herbs, like the regular foods, work by adjusting the flow of vital energy in the entire body of the human being. This is accomplished by increasing the energy where it is too low and lessening the energy where it is too high. When herbs are assimilated by the body their vitality is absorbed too. The herb's vitality passes through the pathways of energy (meridians) to reach the internal organs and to support and adjust them to their optimal functioning. The most useful purpose of herbs is the prevention of illness, rejuvenation and longevity. Everyone, whether sick or healthy, can benefit from herbs. A complete diet should include both regular foods and herbs. No one can obtain perfect health unless he has a complete diet program. Anyone who stops learning is older whether this happens at 20 or 80. Anyone who keeps on learning not only remains young but becomes constantly more valuable, regardless of physical capacity.

Diet and Longevity Secrets

The food question is infinitely the most important problem of the present day, and if properly dealt with must result in the disappearance of the vast bulk of disease, misery and death. Dr. Harvey W. Wiley, who was responsible for our pure food laws, joins Sir Arburhnot Lane, in saying that: “I believe I would not be far out of the way if I should say diet may be said to be a factor in every disease to which man is heir.”

Natural Science teaches us that we must eat for replenishment, drink for replenishment and breathe for replenishment. Nutritional replenishment means that we must put back into our body and blood what has been used up in the process of living. The ultimate purpose of blood circulation is to feed the hungry cells of your body, and this is accomplished by vitalizing and building a rich red blood stream through a balanced program of natural foods. This is the great Law of Life.

Hidden Hunger

Inadequate and incomplete nutrition along with poor food assimilation and lack of intestinal and muscular tone are some of the major initial causes why many individuals experience hidden hunger pangs or abnormal cravings, which compels them to constantly consume junk food. A well-balanced nutrition, exercise, fitness, and antistress program can help alleviate the problem in a short time. Natural whole food supplies in easily available form valuable elements that the human body is composed of, namely: vitamins, minerals, trace elements, enzymes, proteins, carbohydrates and fatty acids. The presence of these life sustaining components in their proper balance determines our state of health, vitality, and length of life. When any one of these natural elements become depleted or reduced below the body's requirements, that instant, health and vitality begin to diminish, and will continue to do so until disease appears. If the body's requirements are adequately met in every department, health will be the natural outcome.

Nutritional Power

Health minded individuals are becoming more concerned with nutrition power. Through the power of nutrition, the food we consume daily, we become physically and mentally what we are now and in the future. Food can build us into dynamos of health, strength and power or break us down into sick, weak and powerless individuals. The quality and not the quantity of foods is the determining factor in our overall health and well-being.

If civilized peoples do not use natural foods, if their food is changed from the condition in which nature supplies it, we have located at least one civilized habit that must tend towards body degeneration, organic strain and illness. Every human being knows that a building cannot be any more perfect than the materials used in its construction. Foods, just as they come from nature's hand, are capable of building perfect human bodies.

Confusion about Nutrition and Health

What is a proper diet of man? Is there one good diet that is good for everyone, everywhere, and will end all argument on what one should eat? One authority says to eat only fruits, nuts and vegetables; another says, eat only rice and no fruits. Still another advocates eating only fruit. One recommends a high protein diet, low fat diet. Some say to eat everything, because man is an omnivore. There are diets from each nation around the world, and we can take our pick. One author is against eating breakfast, another says to eat a big breakfast. One says to fast one day a week and another advises to fast 40 days at a time.

Here are a few national diets advocated by various authorities in the West:

Low Cholesterol
Weight Watcher's Diet
Orange Diet
High Carbo Diet
Low Protein Diet
Drinking Man's Diet
Eat All You Want Diet
Inches-Off Diet
Fruitarian Diet
High Fiber Diet
Air Force Diet
Grapefruit Diet
Low Carbo Diet
Save Your Life Diet
Rockerfeller Diet
No-Risk Diet
Milk Diet
Breatharian Diet
Policeman's Diet
Mucousless Diet
Grape Diet
High Protein Diet
Working Man's Diet
Mayo Diet
Diet Revolution
Bran Diet
Rice Diet

Some of these diets can be used for a limited period of time without harm in certain conditions, for instance, weight loss, lowering cholesterol, or for cleansing purposes, such as recommended in this book. However, there are no health or longevity advantages of living on any exclusive or extreme dietary fad or program beyond a few days or weeks. Superior health can only result from a balanced dietary program and proper living habits.

Is the meat diet the answer? What about the all fruit diet? And the grain only diet? Should I use food supplements? One groups says that honey, onions, garlic and grains are taboo. We have personally experimented with many of these diets, including the rice diet, high protein diet, fruitarian diet, vegetable, the cooked diet, the raw diet, the juice diet, the water diet, and yes, even the breatharian diet of only pure air. What is humans most optimum diet? What diet plan will impart superior nutrition and good health? As can be seen by the above diet statements and lists, confusion and contradiction is rampant in the health and nutrition field.

One thing is certain: Positive results in health and nutrition are of prime importance; not theory or speculation that look impressive on paper, but fail to produce healthy specimens in real life. In order to arrive at a logical and truthful conclusion, we must seek all the facts clinical and empirical that produce actual physical results, and not mere opinions and theories that do not produce positive, healthful results.

We must all learn to remain open minded in all of our research and study, investigating all sides of the issue before reaching answers or conclusions. The mind is like a parachute; it only functions when open. No one religion or philosophy has all the answers, but we can learn from them all. Unfortunately, all too often, we allow our own subjective ego's to obstruct our thinking and reasoning processes. Being human, we tend to hold on to our pet theories and opinions on health, diet and life, not opening our minds to a higher truth or superior method. When individual consciousness learns how to flow with the universal consciousness or natural law, one may easily discern the proper and true nature of health and life.

The ancient sage Buddha, during his earlier life, attempted to subsist on almost nothing, while fasting and praying in the mountains. One day he became enlightened, fled the mountains, and proclaimed to the masses, that fleeing society and depriving oneself of food and other necessities was not the answer to reach heaven or God. He revealed the answer to health, happiness and long life with one word: Moderation. Moderation in all the good and beneficial things of life. Moderation in diet, exercise, working, playing, sleeping, etc., is the answer to living a well-balanced and healthy life. Always keep this important point in mind when studying and practicing health and nutrition. To preserve health is a moral and religious duty, for health is the basis of all social virtues. We can no longer be useful when not well.



Fig. 6.11. Bodhidharma, the Ting Yun-peng, who came from India to China preaching a kind of Buddhism which ultimately evolved into Ch'an or Zen Buddhism. Courtesy of Field Museum of Natural History, Chicago.

Research has demonstrated that if we completely filter polluted water, using every process available, it will still maintain its old vibration and unstable structure. It will maintain memory in the same way that a computer does. We must therefore reprogram the cells with our intent.

If the water we drink contains too many pollutants and antioxidants it will eventually poison us.

As we can see from these pictures, there is an enormous difference between natural spring water and regular city water. It is now quite clear that if we program water so that it becomes, sacred, holy or Chi water, then it will have the power to remove all antioxidants and pollutants – all sickness. It will have the power to reprogram the water within our bodies, to carry the same pure structure.



Tokyo Tap Water **London Tap Water** **Paris Tap Water**



Under Ground Water in Northern Island, New Zealand **Buenos Aires, Argentina** **Spring Water of Saijo, Hiroshima Prefecture**

Fig. 4.19 *Healing or hurting?*

We are What We Eat

Improper or one sided nutriton can cause serious metabolic and chemical disorders that can take years to correct. For example, a heavy meat and protein diet is the cause of many diseases such as, kidney (contracted), arthritis, gout, premature aging and cancer tumors. Meat protein is extremely high in phosphorus, which can cause high calcium loss and bone cancer; it is deficient in almost all vitamins, minerals, enzymes and base elements. Meat can impart strength and power (Yang) for a short time, but it is not conducive to a healthy long life. Exclusive meat diets are extremely Yang and acid, resulting in very aggressive, hot-tempered, over-sexed and dictatorial characters. Grains, legumes, vegetables, seeds and fruit are superior sources of protein and biologically and more healthfully superior to meat protein. The exclusive cooked grain, legume and vegetable diet lacks the elements of raw food and potassium the beauty mineral. This diet usually leads to extreme underweight conditions or emaciation. Mentally, this diet produces Yang temperaments and organic contraction; fevers; sometimes uncompromising and arrogant. This diet lacks in sufficient raw fruits and vegetables, especially during summer weather; too much cooked food in hot weather; may lack sufficient protein and alkaline vitamins and minerals.

The Fruitarian Diet (watery fruit) is extremism on the alkaline side (yin) and will result in low blood pressure, poor circulation, cold feet and hands, anemia and nervousness. This last symptom is caused by a lack of sufficient proteins and grains which builds powerful nerve force in the body. Blood is not built by fruit alone, but by a combination of alkaline and acid food together. Mentally, the alkaline fruitarians tend to be over-critical. They whine and complain continually, feeling that no one is as moral or as perfect as themselves. They withdraw from society thinking that everyone else is headed for destruction.

The authors writing on fruitarianism, juicearianism, breatharianism and mucuslessarianism have not been able to live up to their own teachings. They live on the diet for a time, but nature always pulls them back to eat the heavier type of acid foods, i.e., protein, and carbohydrates. The reasoning is, that on some future day, when they have cleaned out every speck of mucus from the body, they will be ready to live on air. If Breatharianism were possible, it could be done only through divine intervention (grace) through Taoist practices, and not by consciously going to the extreme in any phase of life and living. There is an underlying truth to the vast sub-ject of health, diet and nutrition that must be considered before advocating a specific nutrition plan for anyone. Natural Law settles and answers the question as to what each of us shall eat in the following section. There is a natural affinity between natural foods and the human body. They share the earth as source, and the body so fed holds energies to be found in no other way. We call it health.

Locally Grown Foods for Optimum Health

Nature decides what foods we are to eat; and that decision is made according to the zone or region in which we live. In the cold frigid regions of the far north, fuel foods are required. Fruits, seeds and grains are very scarce in that region. The cold (Yin) temperatures require heavier and more Yang/Acid foods, such as cooked grains, legumes, miso, soups, stews etc. Generally, those living in a cold climate may consume a higher percentage of natural cooked starches and proteins and a small or moderate amount of raw foods and natural fats. On the other hand, as we travel south to the tropics, we need less fuel foods and more fresh fruits, vegetables and nuts. A high meat and fat diet, eaten in the south, would result in rapid decay and death. Hot weather is Yang and requires some summer grains and raw fruits and vegetables. A Yin fruit and vegetable diet in Alaska would cause a rapid loss of weight, extreme coldness to the bones and ultimate sickness.

The temperate zone produces a person with a well balanced spiritual, mental and physical nature. Here is where we find the greatest inventors and scientific advancement. Nature provides the greatest variety of foods in this region. While the south grows mostly Yin foods and citrus fruits, the temperate zone produces fruits and vegetables tending toward the Yang elements, for example, apples, peaches, beets and cherries. These Yang foods are higher in sodium, which is necessary for the temperate region. Tropical foods predominate in the element potassium, which is required to cool the body in the hot Yang climate.

There is little use in theorizing on the question of what we should eat. Nature simplifies the matter. For optimum health, consume foods grown within a 300 mile radius of where you live. Avoid foods shipped in from across the country or other countries. The red pepper, (cayenne), which grows so profusely in southern latitudes, is strongly magnetic (Yin), and the lemons, limes, oranges and tropical fruits abound in citric acid, which are assimilated and utilized easily by southern inhabitants. In the temperate region, the woods are overflowing with luscious ripe red berries, seeds and nuts, cucumbers, and nature has produced just the right kind of food that the humans and animals inhabiting that region require. Refer to the chapter on Yin & Yang balance for proper selection of foods.

Those living in a temperate climate, with a change of seasons winter, spring, summer and fall and the weather changing from hot to cold throughout the year, the diet must be adjusted to meet the environmental conditions to maintain nutritional balance and optimum health.

For instance, during the northern winters of the temperate zone, you will require more Yang and heavier foods such as, grains, wheat and rye bread, beans, peas, steamed vegetables and apples. Temperate summers require more cooling foods as found in this zone such as, cherries, peaches, plums, grapes, berries, melons, etc. The spring and fall diets will vary between the winter and summer ones. This is where one must become the final judge in the choice of foods they eat. Listen to the inner voice or feelings as to what the body requires of certain foods on any given day. Age, physical activity and stress conditions must also be considered as variables in an optimum selection of natural foods.

An occasional orange, pineapple juice or other tropical fruit eaten in the northern zones will do you no harm. Be moderate and use supreme judgment. Do not become a food fanatic or diet crank. Acid and Yang meat eaters can benefit more by eating some vegetable and fruit foods to balance their Yang characters. Vegetarians, who are mostly Yin and alkaline, would do better to eat more of the Yang natural foods, such as seeds, peas, grains, beans, miso, cooked vegetables, etc.

Longevity Secrets of Centenarians

The longest lived and healthiest people in the world live chiefly on the natural whole foods grown in their own region and climate. For example, the Bulgarian diet consists largely of whole rye and barley bread, sunflower seeds, vegetable soups; fermented foods such as, yogurt, sauerkraut, sourdough bread, soured milk, etc. They seldom eat meat. They consume goat or sheep milk and fresh raw honey. Bulgarians are mostly lacto-vegetarians. The Bulgarians boast of about 1,500 centenarians per million population, as contrasted to 100 or less persons over the century mark per million in the United States.

The Himalayan Hunzas consume a similar diet, with the addition of apricots, millet, buckwheat, mulberries, buttermilk, soups, fruits and vegetables. They work outside most of the day, getting sufficient exercise and oxygen to digest their food properly. They drink the highly mineralized water coming down from the majestic glaciers. They maintain a positive, happy attitude and youthful condition well into advanced age. Many Hunzas reach the age of one hundred years and beyond. The long lived Mexicans on the other hand, utilize the foods grown near them, such as: papayas, pineapple, corn, cornbread, beans, limes, lemons, oranges, red peppers, bananas, avocados, various vegetables and many herbs including damiana and sarsparilla. The Russians, living to a healthy advanced age, consume an abundance of garlic, onions, honey, pollen, buckwheat, sunflower seeds and oil, fermented lactic acid foods such as soured milks, sauerkraut, sourdough bread and pickles. Their foods are unprocessed. They eat very little meat and live an outdoor life.

Live to be a Hundred

1. Pure, whole, organic, natural foods.
2. Natural foods grown on rich humus black soil.
3. Clabbered goat milk products, fruits, vegetables, seeds, nuts and grains and very little or no meat.
4. Eating when hungry and only when hungry.
5. Eat and live in moderation.
6. Daily exercise outdoors; walking, running, gardening.
7. Centenarians always maintain a positive mental attitude.
8. A strong belief in a Supreme Guiding Force. They pray often, fast occasionally, live without fear and are serene and loving.
9. Most of these vibrant oldsters have developed and maintained perfect bodily postures, which is necessary for good circulation, nerve flow and superb health.
10. They live in an almost perfect environment with an altitude of about 4,000 feet, perfect for the heart, metabolism and thyroid. Sunshine and rain are abundant throughout the year

and food grows continuously. The atmosphere is brisk, bracing, energizing and pure. Never too cold or hot, but just right.

11. These healthy long lived people make their work their play and their play their work. They enjoy what they do and they love what they do.
12. They are never in a hurry or under stress, which is the greatest killer and life shortener of modern human.
13. Many of them avoid meat completely, do not smoke or drink alcohol.
14. They live by the cycles of the earth; early to bed when the sky darkens and up with the sun at the crack of dawn.
15. Most of them were married one or more times and have grandchildren and great grandchildren and enjoy being around young people.
16. Living at a 4,000 foot altitude, they have less gravitational pull on their bodies by climbing steep mountains. This insures good body circulation from the leg muscles to all parts of the body and brain.
17. They obtain an abundance of ultra-violet light from the sun daily. This light controls calcium, which are found in the long bones of the body that produce rich red new blood cells.
18. They drink the pure mountain glacier water and consume a variety of herb teas, such as, ginseng, peppermint, alfalfa, etc., and they drink only when thirsty.
19. The greatest secret of the centenarians is that they live a well-balanced life, mentally, physically, emotionally and spiritually.

Fig. 6.12. We squander health in search of wealth, we scheme and toil and save; then squander wealth in search of health. And all we get is a grave. We live and boast of what we own we die and only get a stone.

Vegetarianism vs Carnivorism

You may be surprised to learn that about one-half of the world's population is either totally Vegetarian or leaning in that direction. There are approximately eleven million Vegetarians in America today, and that number is growing fast. Many social and economic factors indicate that vegetable plant foods will account for as much as 90% of the United States food budget within ten years.

The current methods of food production, especially in the United States, is most uneconomical and wasteful. For example, eighteen million tons of vegetable protein are lost in feeding them to animals for the production of meat protein. If this vegetable plant food was fed directly to humans, it would meet 90% of the world's protein deficiency.

Nearly one-half of the United States harvested land is planted with crops to feed animals. The United States Department of Agriculture states that the billion people in developed countries use almost as much plant food as feed to produce animal protein as the two billion people in other countries use directly as food. Among other things, the meat industry may soon be using sterilized chicken manure as animal feed for the commercial market. In feeding vegetable foods to animals for meat, a 90% to 95% waste factor is involved. The cultivation of grains, vegetables, nuts and fruits can support a population eight times or more than that provided by the present wasteful system of feeding this food to animals first, then eating the animal.

We must not only provide superior nutrition for the people, but most importantly, save the land from exhaustion. Our cosmic spaceship (earth) is burning and smouldering with chemicals, inorganic fertilizers, fallout, industrial wastes and destructive poisons too numerous to mention. It is time for everyone to take some positive action and to demand that peace be given to our fields not only to save humans from malnutrition and disease, but consider a diet for the earth itself. Our world leaders are leading us like sheep, into mass suicide from the lack of true wisdom and deep insight. We must think of the generations and civilizations to come.

The Vegetarian philosophy is appealing to a growing number of people of all ages who desire a peaceful world now and for generations to come all over the globe. Youth is disillusioned with society. They have witnessed only war, insecurity, economic strife, chaos and corruption in all levels of government. Many of our young people are seeking only good and constructive change. The non-violent plan of eating, if embraced by mankind, would lead to world peace, as there would be no more killing; but it must start with each person. The whole Vegetarian Ideal will not only improve the individual, (the microcosm) but humanity as a total unit, (the macrocosm) and the entire environment.

Scientific and Anatomical Basis of Vegetarianism

All modern physiologists admit that flesh is not an essential part of the dietary of human beings. A well-selected vegetable diet is capable of producing the highest physical development. Prof. E. V. McCollum of John Hopkins University contributed his opinion of diet in the early nineteen hundreds, thusly: “I have not the slightest hesitation in saying that a vegetarian diet, is the most satisfactory type of diet that humans can take.”

Nothing is more easily demonstrated than animal meat being positively injurious in the highest degree, and that many of the diseases of our civilization are derived exclusively from its use. We will dispose of the meat question with the following incontrovertible scientific facts, which should be sufficient evidence that the practice is an acquired habit and wholly unnatural.

First: It is a universal fact that all animals that are naturally carnivorous are more active at night than in the daytime, and are of a nature which makes them positive at night and negative during the day. Man is more active in the daytime than at night by nature, and if he is carnivorous he furnishes an exception to the universal rule. Persons who consume large quantities of meat are rendered sleepy and dull during the day and are sleepless and nervous at night. Heavy meat eating usually accompanies the drinking of alcohol, along with spicy, fattening and other devitalized foods during a period of time in which the body requires sleep and recuperation from the daily activities.

Second: All animals that are naturally carnivorous perspire through the tongue and not through the skin. All naturally vegetarian animals perspire through the skin, as man does. Meat eaters have a feverish and disagreeable condition of the tongue, causing an unnatural thirst, which vegetarians do not experience.

Third: Man's anatomical structure is not adapted to a meat diet. His teeth are not adapted to tearing flesh and he has no claws to kill and rend his prey. His tooth structure is designed for biting and chewing grains, legumes, fruits, vegetables, seeds, nuts and other natural foods, as opposed to the carnivore who kills the animal and eats mostly inner organs, blood, guts, bones and lastly flesh.

Fourth: The perspiration and other forms of excreta thrown off from the bodies of meat eaters is exceedingly offensive, while that from vegetarian eaters is agreeable and less in quantity. Flies and mosquitos torment meat eaters, while vegetarians are comparatively immune. Vegetarians are seldom constipated, while meat eaters are almost universally so. Man secretes alkaline saliva, the carnivore secrets acid saliva.

Fifth: The carnivore stomach is small and round, as opposed to an oblong stomach of man, which has convolutions needed for the breakdown of fruits, grains and sweet tender vegetable foods. Man has an alimentary canal twelve times the length of his body. The carnivore canal is only three times the length of his body. The carnivore colon is smooth and short, which is necessary for the quick evacation of the putrefying flesh fare. The colon of man is long and convoluted for a more thorough digestion of the food from the plant kingdom.

Sixth: The consumption of meat renders the individual more ferocious and disagreeable in manner, less considerate of others, and more inclined to acts of brutality and selfishness, than to acts of kindness. In many cases, it produces the effect of continued irritation, nervousness, and sometimes results directly in insanity.

Seventh: When man attempts to comsume meat he literally poisons himself. Flesh foods begin to putrefy about one-fourth of the way down the intestinal canal, causing uric acid poisoning, ptomaines, chemicals, deadly hormones and the waste products from the animal's metabolism at the time of slaughter. Meat products in the human system over-stimulate the heart, causing it to beat up to 50% higher than average, which leads to high blood pressure.

Eighth: Man takes his liquid through sucking. All carnivores lap liquids with their tongue. Carnivores have large livers to handle the heavy meat consumption. Man's liver is small and not developed to handle a flesh diet. Flesh eating animals secrete ten times the hydrochloric acid into their stomachs, as do the vegetarian eaters. They require it for the breakdown of meat, bone, organs, sinews, feathers etc. Carnivorous animals eat mostly the inner organs of their prey in a raw state. The vultures, hyenias and other scavengers feast only on the left over muscle meat, after the tiger or lion has finished feasting on the best inner parts. Man falls into the scavenger category by consuming not raw muscle flesh, but aged, bacteria ridden and cooked flesh. Muscle meat is highly deficient in vitamins and minerals, and contains an excessive amount of phosphorus, which if eaten to excess throws off the calcium balance within the body. This phosphorus robs the bones and teeth of its valuable calcium and sets up uric acid crystals throughout the body joints, causing stiffness, pain and disease.

Ninth: Repeated experiments have proven that vegetarians excel over meat eaters in all tests of endurance and strength in both physical and mental labor and live longer lives. You do not need meat for heavy work. Prof. Voit of Munich discovered that, “heat and energy are almost exclusively created by carbohydrates.” Always keep in mind, however, that we must obtain a daily balance of natural proteins, carbohydrates, fats, vitamins and liquids. The gorilla, elephant, oxen, horse are tremendously strong, with great endurance, subsisting solely on vegetarian fare.

Tenth: Fruits, vegetables, grains and seeds repair and replenish the cells and tissues, whereas meat overstimulates and tears them down. Flesh food often causes a ravenous appetite, which nothing but more flesh can satisfy. Meat, being an extreme Yang substance, causes an internal craving for extreme Yin substances, i.e., sugar, alcohol, drugs, sodas etc. Extremes in diet cause extreme conditions or chronic diseases, i.e., leukemia, cancer etc.

Eleventh: Meat contains a high proportion of cholesterol (an important causative factor in thrombosis, high blood pressure etc.) with no lecithin (nature’s antidote) to balance it. (All vegetable proteins, on the other hand, contain lecithin to naturally counterbalance it).

Meat is an Unnatural Substitute Food

When thinking about vegetarianism especially the total kindmost people quite naturally ask what they can use in place of the various animal-source foods. It should be clearly understood that every one of these animal-source foods is already a substitute food: a perversion of the natural diet that is Ideally suited for the normal human body.

Vegans do, of course, advocate human milk given by a healthy mother direct to her own baby, as the ideal food in early infancy. Cow-milk formula is today finally being widely recognized as an inferior substitute for this. In cases where a mother has been unable to nurse her baby for whatever reason, or to supplement the mother's milk, various nuts, seed, and soya-based milks have been used with success. If we, as adults, bear in mind that milk, eggs, and meat are all in fact mere substitutes for our natural vegan foods, we will not be so concerned with searching for substitutes for substitutes items that look, smell, or taste like the barnyard/ slaughterhouse products we are so used to.

There are, of course, many vegetable-source replacements for the various animal products. But these are more in the nature of a dietary crutch to help one through the transition period, rather than a nutritional necessity. We should really learn what our natural foods are, and go on to build our diet up from these. So you want to be a vegetarian? We will help you all we can. But in the final analysis, we can only help you to help yourself. We are not just interested in getting someone off the animal flesh and substituting some over-cooked canned soyabeans. Are you still stuffing up on the junky white flour products? Sugar? White rice, Soda pop and stimulating cola drinks? Coffee? Do you smoke? Drink? Why do you?

But you are convinced. Now you want to know how to go about eating both ethically and healthfully. Generally, the first thing to go is meat. Makes no difference whether it is from a steer or a sheep; that of a pig may be worse for you; that of a chicken or fish is not so harmful from a cholesterol standpoint but Is likely to be worse in the matter of pollution. Ethically speaking, all are slaughter products, though you would have to kill many little fish or birds to equal the amount of meat taken from one larger animal. In any event, out goes the flesh: all of it. Calcium, protein, vitamins, minerals? Well, where do you suppose those animals got theirs? How is it that man uses the great big strong vegetarian animals around the world, for beasts of burden, for meat and milk, yet he thinks he must eat these things from them to obtain protein or some other nutriment? "Consider Mr. Elephant, with huge tusks and teeth and bones: whence come his calcium? Or the ox or the bullock, or the camel: where do they get their protein, with which to build their powerful muscles? How is the horse able to be strong and energetic? They are all total vegetarians. The vegetable kingdom Is, in point of fact, We can also use music to program a vibration into water. Classical music will create a vibration that synchronizes with our own health, whereas heavy metal music will have a tendency to 'shatter'!



"You make me sick", or "I will kill you".

You Fool



Heavy Metal Music

Thank you

Folk song of Celtic Region in UK

Healing Music

Fig. 4.20 *Power to heal or harm?*

Similarly, when we program our emotions regarding other people into water, the effects are the same. If we think negatively of someone, then the response will produce a bad vibration. If we think kind, loving thoughts then the structure will be like a beautiful crystal. If we love Mother Theresa and send this energy into the water, a wonderful crystalline structure will be created. Sick water can be transformed into healthy water. Healthy water can be transformed into sick water. The human body consists of 70% water. The key is your intent and your ability to believe that healing comes from the nature of your vibration. Always be open to receive.



Adolph Hitler

Mother Teresa

Dirty

Beautiful

Fig. 4.21 *Sick or saintly?*

the only natural first hand source of all the protein on this planet. Not one animal creates protein but by eating proteinous foods; none can synthesize calcium or other elements within the body; every one depends on the vegetable kingdom for the raw materials to restructure into its own particular type of make-up. No two types of animals have the same general protein type. But all vegetarian creatures can obtain their essential ammo acids (the building blocks of all proteins) from the vegetable proteins that are so abundantly and widely distributed in the world of plants.

Even the fang-and-claw predators, such as the dog and cat families, must obtain their protein from plants ultimately, though they take it second hand by eating vegetarian animals; but they pay a price in parasitic diseases and other problems associated with flesh-eating, even as humans do it they become dietary copycats and try to eat like a tiger or jackal. Truly man is the king of beasts, for his brutality exceeds them. Leonardo da Vinci stated, “We live by the death of others. We are burial places. I have since an early age abjured the use of meat, and the time will come when men will look upon the murder of animals as they now look upon the murder of men.”



Fig. 6.13.When feasts are spread the doctor rolls his pills.
In fifty dishes lie a hundred ills.

Meat Eating may be Hazardous to your Sex

The addition of chemicals and hormones to meat are causing sex gland problems. Experiments by Dr. F. Pottenger Jr. of Monrovia, California, have proven that the physical make up of men and women is changing. Men are looking and acting like women, and women are looking and acting like men. Hair is growing in abundance on the arms and legs of women. Men are becoming more feminine and weak physically, mentally and emotionally.

Another experiment was conducted in which a few chosen men and women were lined up facing a wall. Next, a number of doctors were invited to distinguish between the male and female from behind. These doctors had a great deal of trouble distinguishing the difference in gender. The men in this experiment had narrow shoulders and wide hips, which is a female characteristic, while the females had wide shoulders and narrow hips, which is a male characteristic. Have you ever seen synthetic female hormones at work? Did you know that a cow given a shot of DES (there are eight other lesser-known brand names) will abort her calf? A rancher years ago, found that he could chemically castrate young bulls with this small dosage. Any knowledgeable veterinarian will tell you that if a rooster is given DES daily eventually he will cease to crow and will begin to cluck like a hen when his tolerance level for female hormones has been breached. This last experiment could be viewed as unisex in the poultry yard as the rooster has been affected both mentally and physically. Roosters and, unfortunately, DES are both easily obtained. The French tests found that rats fed meat coming from steers fattened with the aid of DES were radically affected sexually impotence and sex reverses among male rats and cancer of the breasts and other female organs was produced in the female rats.

The Canadians banned DES as a result of the French tests, but no such luck for us. Is it simply because this nightmare was invented here that we must be the last to awaken from it? Why, after 20 years of flagrant use of synthetic female hormones in the cattle feeding industry do we find the chemical companies frantically pushing the new synthetic masculine hormones? Are the chemical companies (aided by an eye-closed attitude from the FDA) trying to cover up a tragic 20 year experiment with female hormones by forcing the American public to undergo mass hormonal therapy with the new masculine hormones? If so, how will the new experiment turn out? Why cannot we merely shut off all of these hormones rather than face the long ghastly transition which seems to be in store for us? The excessive consumption of hormon eladen meat products, in addition to a large intake of white sugar products, is one of the main causes of reversed sex roles today. This is certainly something each individual must seriously think about; and evaluate the effect of their dietary life styles and the socioeconomic impact it entails.

Choosing Your Own Diet

The question of whether to eat flesh products or not is strictly an individual matter. It depends on how far one desires to progress on the path to health and well-being. It has been scientifically proven that an excessive consumption of meat can easily lead to arthritis, gout, stomach, colon and bone cancer. We contend that overeating of any food item, either natural or unnatural, can cause a host of physical and mental diseasesfrom colds to cancer.

Certainly, we are not claiming that if one consumes a very moderate and limited amount of meat per week or day, that they will immediately drop dead from doing so. Almost everyone has eaten their share of meat before becoming a vegetarian; and they could not be coerced into giving up meat against their will. Each individual must accomplish this transition when they are physically and mentally ready.

We have researched and observed individuals and cultures worldwide and have discovered many healthy 100 year old plus people in both meat-eating and vegetarian categories. In both cases moderation in diet and personal habits seemed to be the key to their perspective longevity. In presenting this material to the public we are not attempting to be moralistic or dogmatic. Our main purpose here is to present the facts and scientific data as it is revealed to us. We do not personally partake of meat products through our own choosing for the following reasons: health, economics, spiritual, moral, ethical, ecological, aesthetic, scientific and humanitarian. Likewise, this decision should be based upon one's own deep study, contemplation and overall commitment to higher ideals; physically, mentally and spiritually. The reader must make that choice for himself or herself, and be given the freedom and love to do so.

Alternative Vegetarian Protein Foods

The following vegetarian foods are all high in protein, Vitamin B-12, iron, phosphorus etc. They are more nutritionally balanced than meat products, and are a safe, wholesome and healthful alternative to flesh.

Grains
Yogurt
Legumes
Raw Goat Milk
Nutritional Yeast
Seeds (Soaked)
Peas
Miso
Nuts (Soaked)
Soy milk
Buttermilk
Tofu

Many delicious recipes can be made with these foods without worrying about protein deficiencies or meat hormones. Eggs should be used sparingly, or rarely if at all. Use fertile eggs if you must have them.

Vital Statistics on why the Vegetarian Diet is Superior

1. Vegetarian food can feed the world ten times over and be better fed.
2. It is free from all hormones, antibiotics, drugs, chemicals and cancer causing agents.
3. It is free from trichina worms, parasites, food poisoning bacteria and uric acid.
4. It is high in vitamins, minerals, enzymes and other fresh raw food factors.
5. It supplies adequate proteins with complete amino acids for growth and health.
6. It maintains the arteries, internal organs, heart and body in a youthful condition.
7. It does not require the killing of animals for food and is free from animal diseases.
8. It makes one more kind, peaceful, gentle and loving to both animals and humans.
9. It is more economical individually and on a worldwide basis.
10. It gives one more endurance, strength, health and longevity.

Famous Vegetarian Personalities

As you can see from the list below, the vegetarian philosophy and way of life is not a passing fad. Vegetarianism is normal. Meat-eating is abnormal. This was the verdict of these scholarly people. The following is a partial list of the great men and women of history who because of their reverence for life avoided the eating of meat in their diet:

George Bernard Shaw
Mahatma Gandhi
Nietzsche
Albert Einstein
Maurice Materlinck
Sir Isaac Newton
St. Francis of Assisi
Edward Fitzgerald
Francois Voltaire
Paganini
Buddha
Pythagoras
Cicero
Plutarch
John Wesley
Lord Montgomery
Louisa May Alcott
Lucius Seneca
Socrates
Leonardo da Vinci
Prince Paul
Charles Darwin
Percy Shelley
William Blake
Richard Wagner
Edward Carpenter
Jesus Christ
Mohammed
Origen
Herodotus
Ovid
Scott Nearing
Lord Dowding
Vinoba Bhave
Count Tolstoy Plato
Albert Schweitzer
Aristotle
Troubetskoy
Henry David Thoreau
Horace Greeley
Ben Franklin
Bram well Booth
Arthur Shopenhauer
Krishna
Emerson
Diogenes
Porphyry
H. G. Wells
Dr. Ann Besant
Lady Dowding
Sir Stafford Cripps

Nerve Force Principle

Are you nervous, irritable and fidgety? Do you easily lose your temper? Do you entertain thoughts of fear and suspicion? How often do you take headache relieving drugs and medicines? Do you suffer from nervous butterflies, and do you constantly pity yourself? Are you sleeping soundly? Did you know that these lowly moods are the results of a depleted, destroyed and malnourished nervous system? These damaged and half-starved nerves impair digestion, cause headaches, mental anguish, heart disease, impotance, mental illness, nerve disorders and bring on a host of other physical ills. Poor nerve health and constant nerve leakage can destroy friendships and put an end to your lovelife and marriage. No matter how wealthy, influential or successful you are, if your nerves are jangled, starved and weak, you cannot be happy in life.

Nerve Force Principle will help create and build a healthy, strong and powerful nervous system; nerves of steel responding to your every command. Our super fast style of living, constantly rushing and on the go from morning until night, tends to drain and weaken nerve force and nerve energy faster than it can be recharged and energized. Nerve Force can be drained away quickly by these following nerve habits:

1. ***Immoderation:*** Overworking, over eating & over doing anything.
2. ***Poor Posture:*** Slouched sitting posture & bent standing posture.
3. ***Malnutrition:*** These foods are irritants to the nerves: coffee, alcohol, drugs, dope, salt, smoking, white flour foods, white sugar and sugared foods.
4. ***Lack of Proper Exercise:*** No daily exercise program and not getting enough pure outdoor oxygen after meals and throughout the day, results in sluggish nerve flow and poor nerve nourishment due to lack of adequate circulation of the blood to all body parts.
5. ***Insufficient Rest & Sleep:*** Lack of sufficient rest and sleep can result in rapid nerve loss and nervous disorders. No known remedy can rejuvenate a sleep and rest starved body. Proper sleep and rest is one of the quickest ways to restore lost nerve power.
6. ***Lack of Mental Poise:*** This is the result of immoderation, poor nutrition, lack of exercise, rest, and sleep. Emotionally unpoised people have the least nerve power and lead miserable and unhappy lives.

Every act of living uses up or drains away a certain amount of Nerve Force daily. The more Nerve Force we can accumulate within the system, the healthier, stronger, and younger we will remain. People who are constantly ill possess very low nerve force, and they deplete it faster than it can be replenished. To attain Five Level Nerve Health, we must conserve our energy and learn how to accumulate, recharge and rebuild our internal batteries to acquire powerful nerve force vitality.

Take care of your health; you have not right to neglect it, and thus become a burden to yourself, and perhaps to others. Let your food be simple; never eat too much; take exercise enough; be systematic in all things; if unwell, starve yourself until you are well again, and you may throw care to the winds, and physic to the dogs.

Health Rating System

Level One

Degenerative Disease: Cancer, rheumatoid arthritis, parkinson's disease, heart disorders, tuberculosis, multiple sclerosis, musular dystrophy, diabetes, colitis, blood disorders, nephritis, extreme fatigue etc. The individuals in this category have lost their health and vitality, and have very low nerve force energy. They suffer from every known degenerative disease.

The age of a person does not determine a health rating, for an individual can be anywhere from 1 to 90 or more years old. The health rating of a person depends on his daily health habits; if the habits are poor, he will climb no higher than the first level. One can be old at the age of 20, or young and healthy at the age of 100. Time or calendar years is not a prime factor in developing degenerative disease or Super Health. The fact is, that you can develop a a Super Health rating at any age if you persistently follow the teachings in this book.

Many young children born today of unhealthy, alcoholic, drug addicted and junk food eating parents are coming into this world with First Level health or degenerative diseases. Many are lucky to have average health, and very few children or adults are fortunate to be blessed with good health. The Frist Level person, however, can build his health to the Three or Four Level category, but they will have to follow the Five Level Formula very strictly.

Level Two

Poor Health: Asthma, eczema, psoriasis, sciatica, back problems and nerve disorders, hypoglycemia, mental problems, sexual impotence, frigidity, chronic fatigue, chronic visual and hearing problems etc. Second Level people generally have poor health, are constantly fatigued and lack energy. They suffer with chronic conditions such as, kidney, liver and organic problems that have not yet reached the degenerative state. The majority of this group are past the age of fifty, however, an increasing number of younger people have been developing these same chronic disease symptoms and therefore, fall into the Level Two category of poor health. Hospitals report that there are more cases of heart disease below the age of ten than above. This proves the fact that diseases are the result of habits and not chronological age. A poor constitution and poor health are either inherited from the parents or conditioned by poor eating and living habits early in life. They can, however be improved by following these formulas.

Level Three

Average Health: Poor eyesight and hearing; colds, flu, hay fever and sinus problems. Colds, flu, etc. are vital signs of internal elimination, which indicates that the body still has sufficient nerve force power to eliminate toxins and prevent degenerative conditions, such as arthritis, heart trouble, cancer etc. Suppressing acute (colds etc.) will eventually lead to chronic disease. This is the category of Average Health into which most Americans fall. Their nerve force energy runs from high to low on any given day. Many children are born today in the Third Level Health category, while many years ago they were born with Fifth Level Super Health because of better food and healthier environmental conditions.

Level Four

Good Health: People possess a great deal of energy and good health. They retire evenings only slightly fatigued and arise the following morning full of energy and nerve force, ready for a full day of activity and excitement. Fourth Level individuals possess normal sight, hearing, digestion, elimination and good organic health. Many people over the age of 20 do not possess a Level Four Rating. Their health begins to decline from age 20 to 30. Those possessing the Level Four Rating, over the age of 20, 30 or more are either living and eating properly, or were born of extremely healthy parents into a Fifth Level Health category.

Level Five

Super Health: It is the ultimate reward of those possessing a Fifth Level Rating. The individuals in this elite classification enjoy an abundance of vitality, nerve force and human energy mentally, physically, emotionally and spiritually and they know not what it is to be fatigued or worn out. This Super Health Level people are endowed with the following qualities: hair sheens, eyes sparkle, skin glows, teeth are glossy white, muscles are firm, the posture is perfect and they radiate a wealth of energy, confidence and happiness.

Level Five people retire evenings with a reserve of energy, and arise at the crack of dawn with a zest for living, ready to conquer the world. Their health is far above the norm, suffering neither digestive problems or organic disease, with excellent sight, hearing, sexual magnetism and clear voice. They are self-motivators, and great leaders in their perspective fields; setting high standards for the world to follow. To possess the Level Five Nerve Force Health Rating is a grand accomplishment in itself; and it is a very worthwhile goal for all to follow, for it would be the closest reality in developing Super Bionic men and women, endowed with superior spiritual, mental, emotional and physical health. This is indeed the goal of creation, for we are all born in the likeness and image of the Supreme Creator. It has been said that man was given the power to move mountains and to create miracles. That power is within you, controlled by the Tao within, to be used by you for good and constructive purposes. Like an old shoe that is worn down and needs new leather, so our brain and nerves need living natural food to restore their power.

Six Formulas to increase your Nerve Force

1. Moderation in all the Good Things of Life
2. Super Nutrition
3. Correct and Proper Posture
4. Adequate Daily Exercise
5. Sufficient Rest and Sleep
6. Mental and Emotional Poise

Moderation:

Moderation basically consists of this one key point: Expend no more energy beyond what has been accumulated each day. For example, by not going to extremes we will automatically maintain our reserve energy supply and enjoy excellent health. Overstepping our energy bounds can easily lead to nerve leaks, and consequent failing health. It is similar to saving money; if the bank account is overdrawn, there will be no funds in reserve to live on. Likewise with energy; the more energy one conserves, the more they will accumulate in the body, to be utilized for reserve and emergency purposes.

Powerful Nerve Force can never be built by going to extremes or immoderation in eating, working, studying, exercising, sleeping, reading, sexual indulgence, etc. Super Health will be an impossibility if one continually depletes, drains & destroys their nerve force.

Level One people possess very little Nerve Force, and if they are injured or wounded, they heal very slowly or not at all. Level Four or Five individuals possess an abundance of recuperative power and they heal very quickly. As you accumulate and hoard your energy. Nerve Force will eventually increase until the goal of Super Health is reached.

On the pathway to Super Health, one must learn how to regulate and conserve their own energy supply. You may accomplish this by adhering closely to the Law of Rhythm. The Law of Rhythm teaches one how to balance his life and practice moderation in all things. For example, when you've had enough to eat, your body rhythm alerts you by taking away hunger until more food is required; if we do not sleep or rest when tired or exhausted, we have ignored our body rhythm, and we may collapse from nerve exhaustion. Moderation is the key that unlocks the door to greater Nerve Force.

Super Nutrition:

To build powerful nerve force we need an abundance of essential nutrients in the form of vitamins, minerals, proteins, carbohydrates, trace minerals, enzymes and fats. However, the nerves must not only be fed, they must first be cleansed. A detoxification diet of three to five days or a short fast of a few days will help tremendously in cleansing the cells and tissues of the body for a more perfect and smooth nerve flow. Be sure to follow the cleansing period by eating highly nourishing foods. The following food minerals will rebuild, feed and protect the nerves. They are absolutely necessary in your quest for Super Health.

Calcium
Magnesium iron
Chlorine
Phosphorus
Iodine
Manganese
Sodium

It must be understood that to build powerful nerve force, one needs not only an abundance of minerals, vitamins and enzymes, but also adequate supply of complete protein and a sufficient amount of carbohydrates and fats.

A positive mental attitude will be transmitted into the cells of the water contained within our own body. We must consciously practice inner work until it becomes reflexive.


Abnormal
Normal
Abnormal Metabolism
Normal Metabolism
Complex Substrate
Complex Substrate
Soluble Products
Enzyme
Lack of Enzyme
Sufficient Enzyme
Protein Mutation
Protein Folding and Transporting
Ingestion of Indigestible Material

Fig. 4.22 *With the Power of the Sacred Water Abnormal Cells can be cured.*

Correct Posture:

Correct posture is a vitally important factor in restoring our Nerve Force vigor. A slumped back and shoulder position, while sitting or standing is a sure way of cutting off nerve supply from the spinal cord to the entire body.



Fig. 6.14. Correct Posture

A bent over, stooped position broadcasts to the world that life is too difficult to cope with; it is the appearance of a coward and makes one actually feel like one. You will never see or hear stooped over individuals singing happy days are here again, because it is contrary to their nature. Improper posture develops spinal curves, the adam's apple; it weakens the internal organs and forces out the pelvic joints, which is a major cause of prolapsed fallen organs. Poor posture can lead to headaches, backaches, tiredness and fatigue. Incorrect posture hinders good breathing, affects the digestion and is a prime cause of constipation.

The road to a perfect posture lies in the daily practice of sitting and standing as upright as we possibly can. Always sit with hips and back well against the back of a chair. While writing in a sitting position, bend from the hips, but do not round the back while doing so; this maintains the lumbar and sacral vertebrae in perfect alignment. Here is an excellent exercise to assist in developing a straight standing posture:


Nape Line
Jaw Line
Thigh Line
Both Buttocks Level
Horizontal Pelvis Straight Line Would Touch Chin, Chest Toes
Note Curve in Lower Back. Head Forward Flat Chest Dropped Pelvis Protruding Abdomen
Correct Posture
Incorrect Posture

Fig. 6.15. Correct Posture & Incorrect Posture

Lower Back Wall Exercise

Stand against a straight wall with the heels about two inches away from the base of the wall with the buttocks, shoulders and lower back all touching the wall. You should not be able to place a hand between the lower back and the wall. The idea of the exercise is to maintain an upright posture without the lower back curving inward and away from the wall. Move the lower hips inward and flatten them against the wall; this will remove the lower back curve and you should not be able to place your hand between it and the wall. It is this pocket between the wall and the lower back, that must be removed, that will ensure a straight posture.

Strive to relax in this exercise and remain free from strain and tension. The lower back should be flat and in line with the hips, and it should not curve inward in a sway back position. Practice this exercise for a few minutes two or three times a day and strive to maintain this correct posture daily. A perfect posture will allow the internal organs to remain in their proper place. Good posture enables the organs to function normally and the muscles to become firm and strong; you will be able to completely relax and become less fatigued while working. Here is another posture exercise that will help you to gain a perfect upright carriage.

Delsarte Hook

Imagine a fully expanded and suspended ballon. Think of the lungs as a large balloon and the chest as a collapsible aerodome, with the ribs as the rafters. The rafters must be lifted up completely away from the balloon. This is done by standing erect, then placing an imaginary hook where your breast bone is, and a pulley in the ceiling above you; then imagine yourself pulling the rope through the pulley, lifting up that portion of the anatomy (rib cage), which will leave the arms in a loose swing, shoulders relaxed back and down. The entire body will fall in proper alignment. In this correct posture you will be able to breathe easily and naturally. Always remember to keep the shoulders back and down and the chest out. Stand with the knees locked (abdomen and back flat). This is the correct standing posture. If you suffer from back problems consult a chiropractor and he will instruct you on the proper care and exercise of your spine and back.

A proper and correct posture will instill in you an attitude of courage and confidence that will be noticeable by all those around you. Proper posture insures excellent circulation throughout the body, which means greater nerve force, more energy and a higher health rating. An abundance of proper exercise tends towards the building up of an erect, well-propotioned body. The head, chest and shoulders should be held up. A flabby, clumsy, stooped body and a protruding abdomen detract greatly from the beauty and efficiency of the body.

Daily Exercise:

Proper daily exercise is as necessary to life as is food and nutrition. Exercise tones up the internal and external organs and muscles; it helps to circulate the nutrients to the nerves, muscles and vital organs. Exercises that leave one breathless are a great tonic to the body, inspiring us with courage, strength and confidence; it imparts a fresh feeling of energy and nerve power to every cell in our body. There is nothing like daily exercise to lift our spirits and set us on the path to Super Health. An adequate amount of daily exercise together with proper rest and sleep is vitally important in building powerful nerve force and energy. The best type of exercises are those that reach all the joints, spinal area and muscles of the body. The cells and tissues automatically go through a system of contraction and relaxing. When they contract they squeeze out their waste matter; when they relax they absorb their nutrients.

The Standing Spinal Twist and Stretch Stand with both feet on the floor, raise arms over head, lock fingers together, turn palms out, keep knees stiff and stretch forward as far as possible. After bending forward, return back to the erect position with the hands above the head; now bend backwards slowly and feel the muscles relaxing. Repeat the two movements five or six times. Next, with hands interlocked, stretch in a circular motion, bending in every direction from the hips; forward, backward and rotate all the vertebrae in their entire range of motion. Rotate six times each way. These exercises can be performed any time during the day when you need a quick energy boost, or if feeling sluggish.



Fig. 6.16. Standing Spinal Twist and Stretch Stand

Exercise #1: For waist reduction, stomach, liver and kidney stimulation. Swing the body in a complete circle 3 to 5 times in each direction. Inhale in upright position, and exhale slowly and com-pletely while making a wide circle as shown.

The cervical vertebrae is an area of much congestion and interference with blood flow and nerve energy to the eyes, ears and nasal cavities. This exercise will help to remove some of that congestion. Stretch head backward and forward as far as possible. Next, stretch it from side to side, attempting to lay it on each shoulder; then turn head from one side to the other, looking over each shoulder; next rotate the head in a circular motion, clockwise and counterwise six times. Stretch the muscles, then relax them. Repeat each exercise at least six times.

These joint type of exercises should be performed with other body parts as well; for example, one can twist, stretch, flex and rotate the shoulders, wrists, ankles, hips, knees, fingers, arms, etc. We can stimulate nerve and blood circulation to our face by squeezing, stretching and making face contortions; this will keep the face looking young and firm. The hands, feet and toes may be squeezed, rotated and stretched for better circulation. Stretching before arising in the morning is an excellent method of awakening our vital Nerve Force for the day ahead. All of these various circulation exercises are beneficial to all the organs, cells, blood and nerves of the body, building powerful nerve health.

Conserve Nerve Force Energy

Nerve energy and personal magnetism is conserved and accumulated within the body by the practice of controlling body movements and mo-tions. Constant fidgeting, excessive and nervous hand and leg motions while sitting, temper tantrums, constant talking and chattering and irritability must be controlled before we can attain the Level Five Rating.

All of these useless motions cause a serious, leakage of nerve energy away from the body. If this nerve energy were not squandered away in wasted motions and other immoderate habits, we could easily acquire a high degree of personal magnetism and health. It must be understood that our body may accumulate a certain amount of nerve energy daily and if we waste or deplete more than we receive, poor health will result. However, if we cease to squander our nerve energy away with useless and harmful motions, actions and immoderate habits, we will develop health, strength, energy and powerful nerve force.

While walking, relax and make all your movements smooth and easy; refrain from jerky motions and use only the muscles required for the task. It is best to sit down with both feet on the floor and in correct posture, relaxing without unnecessary motions. During the day, when time permits, lie down and relax in a dead still position for a few moments; it may be the refreshing lift you need. Here is an excellent nerve exercise that can help you gain self control and personal magnetism.

Dead Still Paper Exercise:

Take a standing position. Grasp a sheet of typing paper by the lower right hand corner between the thumb and first two fingers; hold it in front of your chest with the elbow away from the body. Next, locate a tiny spot or small point somewhere on a wall and hold the paper so that the upper opposite edge of the paper is in exact line with your eye and the spot on the wall. Control it in this position for fifteen seconds without any kind of shaking.

At first, the paper may uncontrollabley shake; but keep practicing it in spare moments and you will finally succeed in not moving in the slightest degree during the fifteen seconds. While performing this exercise do not cease breathing or eye blinking; just relax and be calm! This Dead Still Paper Exercise helps to control and stop nerve energy leakage and enables one to gain control of their body and mind. It forces the body and mind to concentrate and be still, while conserving and accumulating a supply of nerve force. It may take a few weeks to master this technique, but even-tually nervousness will vanish and relaxation and control follow. You will gain personal magnetism that will be noticed. If we constantly strived to be self-controlled, our vital nerve force energy and health can improve by leaps and bounds.

Sufficient Rest and Sleep:

Sleep and rest are vitally necessary to restore powerful nerve force in the body. It is during sleep that the body repairs itself; resting during the day recuperates the nerve energy lost during the daily activity. For sound sleep, your room should be well ventilated for the complete circulation of air. Fresh night vitalizes the body during sleep and prevents carbon monoxide poisoning from your own exhalation. However, the room temperature should be neither hot or cold.

For proper spinal nerve flow, the bed should be firm and not soft. Old worn out soft mattresses create spinal curvatures and impinge the nerves. Most people require from six to nine hours of sound sleep for the maintenance of health and repair of cells, tissues and nerves. Lack of sufficient rest and sleep is a prime cause of a drawn out haggard look, wrinkles, loss of vitality, poor memory, grouchiness and loss of beauty. Some people try to get by on only a few hours of sleep a night; others in their mad rush for wealth, fame and power, neglect proper rest and sleep. Nervous exhaustion is usually their reward.

It is generally believed that there is little harm in lying down or sleeping after meals, but this idea is entirely false. When you lie down or sleep after eating, the gastric juices do not flow readily. The main objective of sleep is to repair and replenish the nerves and tissues, but if we consume food directly before retiring at night, the body spends its energy on digestion instead of repair. The result will be a lack of vitality, health and strength. Because of poor elimination and repair, it can result in anemia. It is best to eat no later than three or four hours before going to sleep. If hungry at bedtime, a piece of fruit before retiring will do no harm as it is very quickly digested.

No-Exercise Super Beauty Treatment:

This Super Exercise is so simple that you expend absolutely no energy in performing it; all you do is lie down in bed and sleep! Sounds too easy does not it? Here is what you do before retiring to bed: Raise the foot end of your bed about two inches off the floor with a wooden block. Leave the bed in this raised position from now on. What does this simple exercise accomplish? It reverses the downward pull of gravity on facial muscles, skin and internal organs. When the lower part of the body is raised a few incher higher than the upper body while lying down, the blood stream gently courses down to the head stimulating the ductless glands to pour out their rejuvenating and beautifying juices to all parts of the face and body. This head lower sleeping position gives the vital organs an opportunity to fall back into their proper position, allowing them to function at peak effeciency to keep you young and vigorous.

The great eagle who lives to the age of two hundred and fifty years old usually flies with its head lower than its heart. In fact, all animals, to a certain degree, maintain their head lower than the heart. The ancient wise men knew the secrets of youth and longevity; they practiced yoga exercises daily, and obtained proper nutrition, rest, sleep etc. They slept with the foot end of their bed raised a few inches. After a few days you will become accustomed to this head lower position and begin to see and feel the results in better muscle tone, brighter complexion, smoother internal functions and firmer facial skin. Try this no-exercise health and beauty treatment and see and feel the results for yourself.

Rest and Sleep:

When fatigued and sleepy stop all activity, i.e., reading, watching television, etc. Retire to bed. Relax your muscles starting from the toes and loosening all body parts up to your head, feeling each body part relaxing in turn as you free it from tension. Think of your body as an extremely heavy weight sinking deeper and deeper into the mattress while relinquishing from your mind all thoughts of worry, anxiety and tension. Now fill your mind with beautiful and serene thoughts of love, happiness and peace. Spend a few minutes mentally forgiving everyone, and send these love, happiness and peace thoughts to the far corners of the world. By mentally blessing and forgiving the world, you send out healing energy which re-turns its blessings in health, success and sound sleep. Also, mentally picture yourself attaining your heart’s desires and success. These few sleeping secrets will help to give you a peaceful night’s rest. The next morning you will feel fit and ready to face the world with courage, confidence and love.

Mental and Emotional Poise:

The wisdom of the ancient sages passed down through the centuries have taught humans that mental poise or peace of mind is one of the greatest assests a person may possess. Freedom from worry is a vitally important factor in cleansing the mind and attaining Mental Poise. Why are people troubled with worry, anxiety and tension? Are your prolems so important that you worry yourself sick over them? Do you worry about a certain problem and then discover that the problem was hardly a problem at all? It was just our own lower mind entertaining thoughts of fear, failure and trouble. The sages tell us not to worry about the future; not to overly concern ourselves about employment, marriage, possessions, or losses. Do not trouble yourself about the future, but live the best you can in the present; this will insure our future success and happiness while giving us mental and emotional poise in life. Why does worry halt success and happiness? Worrying about the future or over trivial matters prevents us from accomplishing our best in the present; it stops us from doing the things we could and should do but fail to do, because of our incessant worry about the things we cannot do.

Dwelling on future desires will not bring happiness, but only anxiety and mental torment. Many people constantly dwell on some future desire, thinking that when they achieve their desires and goals, happiness will be guaranteed. This is generally not the case. For example, many people believe that they would be happy and contented as a president or executive of an organization. How many of these executives do you know are happy with their tremendous responsibilities? Happiness is a result of the right attitude of mind. If we have a negative attitude toward our present life and activities we will be unhappy; if we have a positive attitude toward life we will remain enthusiastic and enjoy our successes and achievements.

When we let go of the idea that we must have something to be happy, we automatically let go of envy, jealousy, revenge, hate, pride and in its place will appear true happiness and mental poise. We then become Master of our emotions. Perfect Mental Poise will open the inner door to our higher mind. This greater power will guide you to peace, health, harmony, happiness, success, a good marriage and true friends. The Supreme Architect knows your every need. To have faith is the highest high you may ever achieve. A mind brimming with faith and love is a tonic to the nerves and entire system. Perfect Mental Poise will regenerate your body which is a major step toward Super Health.

These Six Super Health Steps can lead you to happiness and success far beyond your highest expectations. As you gain in Super-Health and Nerve Force, you will become poised, emotionally balanced and in complete control of your life. You will have developed complete mastery in the drama and circumstances of your earthly existence.

Yin and Yang of Nutrition

It has long been understood that there is a link between the food that we eat and our health. The ancient Taoists developed a sophisticated understanding of health and wellness, including the use of herbs and food for rebalancing health.

These days we have a far more complex situation. This is due to several factors:

1. We have developed extremely sophisticated methods for the manufacture of food. There are huge numbers of highly processed and refined foods available to us that the ancient Taoists would never have dreamed of.
2. We travel more than our early ancestors. We expose ourselves to a wider variety of climates, seasons & food types.
3. Our farming systems have developed a huge range of chemicals, factory farming and modified food types that also affect our nutrition.
4. Our bodies are exposed to high levels of chemicals, pollutants, Pharmaceuticals and stress that our early ancestors would have had no experience of.

Thus we have to make adaptations in order to apply ancient principles to our modern situation. In the struggle to find the nutrition solution, the health world is not overwhelmed with theories and suggested diets. One year we are told to eat only raw food; the next year the high-protein diet is in. How on earth do we know which one to follow to restore our health to balance? What we need to look for is flexible Nutritional therapies that respond to each individual's needs.

Extremism versus Balance

In the modern world we have a habit of extremism. We are always trying to find the simple answer to solve all of our problems. The early Taoist models of thought show us that life does not operate in this way. Rather than trying to attain a single goal, life can be seen as a flow of energy. It is up to us to find harmony and balance within that flow.

For example, in modern thinking we may be tempted to try to aim to reach a perfect goal: perfect weight, perfect health, ideal levels of energy. However, if we stop and observe Nature we see that this is not reality, in reality, we flow between being tired to

Outline of Sacred Water Practice

Invoke the power of the Sacred Water practice to cleanse and heal the body's sick, toxic or negative energy. **If you are working with a group of people, direct your energy through the energy body overhead and into each person's star, as you guide them through the procedure**.

I. Hold a glass one quarter full of water in your left hand, folding the middle and the ring fingers into the center of the palm.

II. Hold the glass in front of your body as you point the 'Sword Fingers' of your right hand up to Heaven.

III. Make a request to receive healing energy and feel yourself touch a heavenly pool of sacred water energy. Feel the pool pouring down heavenly water to fill your arm.

IV. Place your fingers on the cup and ask:
Command 1: ***"Yin power and good fortune come from the east. Yin power please dissolve all negative energy, all sickness and bad fortune".*** Make a cross over the top of the cup.

V. Bring your arm down and point the sword fingers around the inner rim of the glass. Smile as you circle the fingers around the rim.
Command 2: ***"By my request. Please carry out the order now."*** Repeat this three times, charging the water with Yin Power. Project your thoughts into the water.

VI. Use the thumb and index finger to remove the sick energy from the cup, without touching the water. Do this three times. Talk to the sick cells. Tell them to listen to your command:
Command 3: ***"All sick cells please listen: Clear, clean and bright, this Sacred Water will take all the sickness away."***

VII. Repeat the order and visualize yourself removing the sick energy from the cells and giving it to Mother Earth for recycling.

VIII. Hold the cup with both hands near your heart.
Command 4: ***"This Sacred Water will give me/you health, wealth and longevity."***
Project love, joy, thankfulness, gratefulness, appreciation and the energy of compassion into the cup.

IX. The Sacred Water will carry the message of the practice to all the cells, where it will remain. If you are practicing in a group, drink the water in unison. If you are working with a student, pass them the glass to drink using both hands.

sleeping to wakefulness to high energy every day cycle. We are in constant flux. The result of trying to force our bodies towards an unnatural goal is that we push ourselves farther away from balance and harmony, A lot of modern illnesses that we see are a result of this disharmony.

Thus to improve our health, we need to start listening to our bodies, seeing where the imbalances lie and finding the ways to restore our own bodies into balance. Rather than just applying the same dietary therapy to all people, we need to find ways of observing and measuring Yin and Yang imbalances and then use dietary therapy to restore health. A lot of the current nutritional theories are based upon a movement in a single direction towards one extreme. For example:

Alkaline Theory: suggests that we all need to eat more alkaline-forming foods.
Raw Food Theory: suggests that we all need to eat only raw uncooked foods.
High Protein Diet: suggests that we all need to eat a high-protein, low-carb diet.
Vegetarianism: suggests that we all need to eliminate animal products from the diet.

These examples all work extremely well for some people, and books will be full of personal case histories to support the theory. The problem is, there is also a portion of the population for whom the diet does not work at all, and may even cause further illness. For example, cold and thin people may become very weak from the raw food diet; others will put on weight from eating a high protein diet. Oriental Nutritional Theory emphasizes the importance of choosing the right treatment for the right person. A complex system of diagnostics was developed, and is still in use today by many practitioners of Chinese Medicine.

One of the gifts of modern medicine has been its sophisticated diagnostic procedures. Therefore, we can use either system to enable us to choose the correct dietary therapy for each individual. Either way, we must choose a treatment based upon each unique person. To choose a diet without first diagnosing the person would be like taking a medicine without seeing what the illness was.

Food Energetics

The ancient systems of nutritional healing regarded different foods as having different energetic qualities. They did not have access to reductionist science, and thus did not know about micro-nutrients (minerals, vitamins etc). However, they did observe the different qualities of foods and the effects that they have on the people eating them.



Fig. 6.5. Energetics of a Tree

Just as Yin and Yang can be observed in a person’s energy, it can also be seen in a food, In food energetics, some foods are considered balancing: they do not have an extreme effect on energy, but maintain the center. Other foods have an expanding quality: they expand our Chi and make us feel lighter. Other foods have a contracting quality: they contract out Chi, making us feel more grounded. We can understand these qualities better by considering a tree. A tree has a stable centre: its trunk, it also has branches that reach upwards to Heaven and expand their energy out. In addition there are roots that sink deep into the Earth and contract the energy down.

We can use this model and apply it to different foods to understand their energetic qualities. If we look at food groups we find that the most expansive are the simple carbohydrates, which release their sugars very fast and thus rapidly lift our energy. Complex carbohydrates also give us energy, but released more slowly. Thus they are expansive, but less so. Fats and Proteins have a contractive effect. They build our body cells and have a grounding effect. Physiologically these food groups slow down the release of sugars in the diet, and thus help to regulate our blood-sugar levels. The denser the food, the more contractive it is. Thus meat is more contractive than beans and tofu.



Fig. 6.6. Tree Energetics of Simple Carbs Complex Carbs Fats Proteins

Some food are centering.those are the foods that are neither too sugary/refined nor too dense a protein/fat. These usually form the center of most ancient time-tested diets. Most diets from around the world will have both a protein and carbohydrate as the center. Commonly this will be a whole grain plus a bean.

Here are some examples:

County	***Protein***		***Carbohydrate***
India	Dahl	+	Rice
Mexico	Beans	+	Corn
Japan	Tofu	+	Rice
United Kingdom	Dairy	+	Potato
Europe	Cheese	+	Bread (wheat)
Middle East	Hummus	+	Bread

Centering foods are often a mixture of carbohydrates and proteins even within each food. For example, rice is thought of as a carbohydrate, but it does contain protein. Beans are often thought of as proteins, but they do contain carbohydrates. Such foods have a balancing and centering effect.

These foods create the core of the diet, and then other foods and flavours are used around these staples. Core foods help to maintain our sense of center. This is a very important principle in Taoism and Oriental Therapy.

Center

Our center is about staying balanced, if we only have extremes in our life, then we become pushed and pulled about by circumstances. For example, if we eat only expansive foods we may feel high, but ungrounded. The opposite is if we eat an excess of contractive foods then we may feel grounded, but depressed and heavy.

If we choose one extreme, we will soon crave the other. Thus we become a victim to our own feelings and cravings. We are constantly swinging from one extreme to the other, the energetic equivalent of manic-depressive. This is reflected in the habits of yo-yo dieting and detox-retox in which people swing from a diet or detox program into their old bad habits as a response.

In Oriental Therapy we seek to build a strong center. In Taoist Chi Kung (energy exercises) we put awareness to the Tan Tien area below the navel. This is the place where we try to store our Chi and build awareness. When we have more awareness in the center, then we are not so affected by outer circumstances. This gives us a gentle strength and stability. Building a strong center is an important aim. However, we also need to address any imbalances that occur and restore them, especially when we first start our practice.



Fig. 6.7. Center Force

Another time we may encounter strong imbalances is when we experience great change in our life, such as moving to a new country, travelling, changes in life circumstances and so on. The stronger our center is, the easier we will make such transitions. But we may also need to attend to adjusting our balance.

Balancing Yin and Yang

We have seen earlier how we can develop an overly Yin or Yang situation of imbalance. A simple way to apply Oriental Dietary therapy is to eat a little more of the foods that will rebalance us, until we feel harmonized again.

Overly Yin = Too Lethargic, Fatigued, Cold, Slow Pulse etc.

Overly Yang = Too Stressed, Busy, Hot, Fast Pulse etc.

Those who are too Yin can assist their body with the addition of a few more contractive foods. These will build strength and stamina. Thus a few more protein-rich foods and healthy fats (cold-pressed oils, nuts, seeds etc) can be added to the diet.

Those who are too Yang can assist their body by eating a few more expansive foods. Eating more vegetables will have a cooling and cleansing effect on the body, clearing excess heat. Whole grains will assist in the body's energy management.

If one becomes rebalanced from the diet, it may be wise to eat a more centering diet. We all have constitutional tendencies that mean that we will always benefit from eating more proteins or more carbohydrates (depending on our tendencies). Try to listen to your body as you adapt your diet to hear how it responds to different foods.

Situation	***Signs***	***Foods to Eat***
Overly Yin:	Cold, Weak, Tired, Too Moist	More Proteins/Fasts
Overly Yang:	Hot, Stressed, Hyper, Too Dry, Sleepless	More Carbs

This is about rebalancing: we do not want to move to another extreme. Therefore, just try gently altering your diet, rather than making sudden and dramatic changes. The body likes smoothness rather than suddenness.

Weight Problems

Weight problems are an increasing concern is modern healthcare. In 2005, the World Health Organization (WHO) estimated that 400 million adults were obese. In 1998 the US spent $78.5 billion on medical costs attributable to obesity. It appears that our modern consumerist society has a cost.

In Oriental Nutrition, not all overweight problems are seen as the same; and thus they are treated differently. Once again, we can use the Yin/Yang model to gain a clearer insight into differences. The overly Yang type of obesity is the result of a pattern of excess. Excess food, excess alcohol, rich and fatty foods all lead to an overweight pattern that is overly Yang. It can be identified by having characteristics such as: The body fat is solid and turgid; when pressed it has little give and feels full. There may be signs of heat. The person may be loud and impatient, or show other Yang characteristics.

On the other hand, the overly Yin type of obesity is the result of a pattern of deficiency. Deficiency of quality foods and nutrients, lack of exercise, yo-yo If these symptoms exist, then it can be wise to pay attention to the water content or moistness of the food that we eat. We can tell a lot about the moistening effects of a food juts by common sense and observation. If a food looks and tastes dry, then it usually is! if it appears moist, then it is.

Therefore foods that will dry up an overly Yin and excessively moist situation include lightly-cooked grains, foods without sauces, fish and meat. Foods that can moisturize an overly Yang and excessively dry situation include soups, sauces, fruits and water-rich vegetables.

Moistening	***Drying***
Soups, Sauces, Salads, Fruits	Dry Grains, Meat, Fish, Root Vegetables

Those who are excessively dry may choose to make a special moistening drink. Soaked psyllium husk or fiaxseeds (linseeds) soaked in water over night make a very moistening drink, or make a smoothie from yoghurt with seeds and fruit added.

Those with moistness and water retention may benefit from the addition of some diuretic herbal teas, such as roselle and nettle tea.

Flavors

In Oriental Therapy, different flavors have different energetic effects on the body. The sweet flavor has the most uplifting effect, whereas the salty flavor has a grounding effect. Blander-flavored foods have a more neutral effect.

Grounding	***Drying***
Salty	Sweet

Therefore, someone who has an overly Yin imbalance may want to reduce their intake of sweet foods. Someone with an overly Yang imbalance may want to reduce salty foods. The other flavors, bitter, sour and pungent, have varying effects on the body and are used to make fine tuned adjustments.

Colors

Color is energy; different colors are different wavelengths of energies. Thus the colors of our foods have an energetic effect on our being when we consume them. Brighter and lighter colors have an uplifting energetic effect. Darker and duller colors have a grounding effect. Therefore someone with an overly Yin imbalance may choose darker foods, such as meat, fish and beans. Someone with an overly Yang dieting and other inconsistent eating patterns all contribute to an overly Yin pattern, It may be accompanied by too much water in the body (water is Yin), leading to fluid retention and dampness, it can be identified by certain characteristics, including: The body fat is soft, flaccid and flabby; when pressed it gives way and feels empty. There may be signs of coldness. The person may be withdrawn and depressed, or shows other Yin characteristics.

Treatment

The overly Yang weight problem requires a treatment protocol that reduces excess Yang, and adds a little Yin. For example:

Fasting works well with this type of pattern as it quickly removes excess Yang.
The person can eat more cleansing and light foods: raw food, steamed vegetables, fruit and juices.
Protein and fat should be avoided.
Toxins must be eliminated: caffeine, tobacco, alcohol and drugs must be cut out, at least for the cleansing period.
Peace, quiet and tranquility need to be sought: this person will benefit enormously from walking alone in nature and taking up meditation. It is hard for them to lose weight without some level of relaxation.
Yang sports could be reduced, such as gym workouts. Yin exercise should be chosen such as yoga and Chi Kung.

Treatment for an overly Yin weight problem will be entirely different, as the whole situation is different. They need to make sure they are reducing excess Yin and adding a little Yang.

For example:

Sugars and fast-releasing carbohydrates should be eliminated, including fruit juices.

Fasting is unlikely to help with the weight problem, though it may reduce toxins and water. This type has to be careful because if they go without food this enhances the yo-yo dieting phenomenon, and their body's metabolism becomes even weaker.

Eating regularly is more important for these types. This helps to balance the blood sugar levels.

Increasing the levels of quality proteins and healthy fats can also help this type to lose weight. This means lean meats/fish and cold-pressed oils such as olive and flaxseed oil.

This person needs to add a little Yang exercise, such as running, dancing, jumping on a bouncer etc.

A little green tea can assist in stimulation of stagnant Chi and assist with weight loss.

These types are not gender dependent. However, a larger proportion of men will suffer from the overly Yang type of weight problem, whereas women are more prone to overly Yin weight problems. If you are trying to deal with a weight problem, try to assess where you are imbalanced in your life (e.g. not enough exercise, too much alcohol consumption) and seek balance.

Underweight

Being underweight is also an issue for some people. Even though our beauty magazines often exalt extreme thinness, it is often a sign of weakness and deficiency, and an underweight situation may not support vibrant health. Once again, we can distinguish between the overly Yang and Overly Yin underweight problems.

An overly Yang underweight problem would be a person who is overly active, nervous and jittery. They may be always moving or fidgeting and find it difficult to rest or be still. In order to gain weight, this type of person will need to eat more complex carbohydrates. They also have to rest and learn some form of relaxation. Deep breathing can be tremendously helpful. They need to avoid stimulants such as caffeine at all costs.

The overly Yin underweight situation is one in which a person is thin, quiet and fragile. They are likely to get cold to the core and feel as if they have weak bones. They may find it very difficult to socialize and to express themselves. To begin to gain weight and restore health, this person may need to eat quality proteins and fats (such as olive oil and flaxseed oil). It is important in the type of person that they eat very nourishing and high-quality foods, with an emphasis on warm and cooked foods.

It always takes longer to restore a deficiency pattern. An overly Yin underweight person is very deficient. Therefore, they will need to take a lot of time and dedication to rebalance their health.

Step I: Prepare the Hands and Arms to Receive the Universal Chi

Left Hand Position: Prepare to hold a cup or glass with the left hand by folding the ring and middle finger into the center of the palm. Hold the glass in front of the body.


A. **B.**

Fig. 4.23 A. *Fold Ring and Middle Fingers.* ***B.*** *Hold Glass in Front of Body.*

Step II: Prepare the Sword Hands to Receive the Universal Chi

Right Hand Position: Form the right hand into a 'sword hand' by folding the pinkie, ring fingers and thumb into the palm. Straighten and hold the index and middle fingers together and extend them upward.


Fig. 4.24 *Prepare to receive the Universal Chi.*

Chapter 7

Effects of Yin/Yang with Acid/Alkaline

Acid and Alkaline pH

The principle of Yin and Yang is the basis of the entire universe. It is the principle of everything in creation. It brings about the transformation to parenthood, it is the root and source of life and death especially with acid and alkaline balance.

In order to grasp the significance of acid and alkaline, one must first understand the meaning of pH. pH is a measure of hydrogen ion concentration in blood, urine and liquids, and is used as as symbol to indicate acidity and alkalinity. A pH of 7 is considered neutral, the measure of pure water. pH 7 is .0000001 gram atom of hydrogen ion per litre. The acid end of the pH scale is from 1 to 7, and 7 to 14 is the alkaline end.

Normal healthy skin can have a pH reading of from 4.5 to 6, or acid. Blood pH is slightly alkaline, from 7.3 to 7.8 on the scale and strives to maintain that reading at all times. Urine should range from 6.5 to 7.0 on the over-all average to insure good health. Urine measurements can fluctuate depending on the type of foods eaten beforehand. However, the urine should be slightly acid or neutral. Saliva is slightly alkaline. The stomach must maintain between 4.0 to 5.0 acidity to digest and breakdown protein foods. If the stomach loses its acidity somewhat, and tends towards neutrality or alkalinity, protein and calcium digestion, assimilation and absorption are lowered or decreased, resulting in indigestion and poor health. Mouth saliva, in good health, should be 7.1 pH.

It is not necessary to continually check your urine pH. It is more important to heed your inner voice or feelings as to what natural foods your body requires at any given time. Balance will be maintained by applying the universal yin/yang and acid/alkaline principles; the body will balance itself, and the urine analysis will be normal. Your health will improve tremendously by eating mainly locally grown natural foods in season. The Acid/Alkaline balance affects every phase of life; from diet, to thought, to weather, to sleep, and physical activity. Everything we do in life either creates acidity or alkalinity. To attain good health it is necessary to thoroughly understand the causes of acidity and alkalinity and apply this knowledge to our life.



Fig. 7.1. Alkalinity of the Blood

Acid-Alkaline Balance

As the Alkalinity Scale shows, the normal condition of the blood must be maintained slightly alkaline, between 7.22 to 7.35. Neutral blood would result in immediate death. A slightly alkaline blood and lymph is a requirement for health and long life. An acid condition of the body and its organs does not mean that the blood has become acid. Acidosis is not acid blood. If the blood were actually acid the body would immediately die from positive acidosis. Cells cannot live in an acid medium.

The body always maintains an alkaline reserve in order to neutralize acid elements. These alkaline reserves are called buffer salts, which are sodium, potassium, calcium and magnesium. These buffer salts maintain a balance between the alkalinity and acidity of the blood, which is normally 80% alkali and 20% acid. An excess of either acid or alkaline in the body is quickly neutralized by the buffer salts. An exclusive acid forming hi-protein or junk food diet, plus a lack of fresh fruit and vegetables will cause a deficiency of these salts, causing a drain on the alkaline reserves and irritation in the cells and tissues of the body, resulting in disease.

Overeating of alkaline foods will also cause a drain on the buffer salts in the cells to neutralize the over-alkalinity. The body expends much energy in overcoming or neutralizing either an over-alkaline or over-acid dietary. The key is to consume both acid-forming and alkaline-forming foods in balance daily, adjusted to seasonal weather conditions. The solvent watery type foods are (alkaline). The heavier type foods are (acid). These are alkaline foods: all watery type fruits, juices, and vegetables (non-starchy). The acid type foods are: all proteins, starches, seeds, nuts, cheeses, fats.

Acid/Alkaline Body Fluids

Body Fluid	***pH of Fluid***
Gastric Juice	1.2 - 3.0
Vaginal Fluid	3.5 - 4.5
Urine	4.6 - 8.0
Saliva	6.35 - 6.85
Blood	7.35 - 7.45
Semen	7.2 - 7.6
Cerebrospinal Fluid	7.4
Pancreatic Juice	7.1 - 8.2
Bile	7.6 - 8.6

Yin/Yang vs Acid/Alkaline Foods

Yin and Yang is generally believed to be the same as Acid and Alkaline; in actual application it is not. From a broad universal perspective, Yin is Alkaline and Yang is Acid; from the food standpoint, acid-forming elements are made up of sulphur, phosphorus and chlorine; alkaline-forming elements are made up of sodium, potassium, calcium, magnesium and iron. The Yin and Yang scale is more variable than the Acid-Alkaline scale, i.e., potassium and sodium are alkaline forming elements, yet potassium is Yin and sodium is Yang. For example, meat, grains, nuts and sugars are all considered acid-forming, yet meat and grains fall into the Yang Acid category, while nuts and sugar are classified as Yin/Acid. Simply stated; Yin and Yang is on a deeper, more universal scale than Acid and Alkaline.

Yin foods are also high in fat, such as nuts, dairy foods and avocados. Yin/Acid forming foods, like milk, sugar, nuts are high in phosphorus and sulphur, but are low in sodium. Yang/Acid forming foods, for example, rice, rye, eggs, fish are all high in phosphorus, sulphur and sodium.

Yin/Alkaline forming foods, for example, oranges, pineapples, tomatoes, are high in potassium, calcium and iron, but are low in phosphorus and sulphur. Yang/Alkaline forming foods in the form of cherries, berries, garlic, burdock root, ginseng, are high in sodium, but low in phosphorus and sulphur. Acid and alkaline are subject more exclusively to chemistry and food. Yin and Yang encompass all phenomena physical (food, biochemistry, etc.), mental, emotional and spiritual.

Acid Forming Elements	***Alkaline Forming Elements***
Sulphur	Sodium
Phosphorus	Potassium
Chlorine	Calcium
Magnesium	Iron

Acid/Alkaline is also on a sliding relative scale, i.e.,meat is highly acid, but it contains some alkaline elements, while apples are mostly alkaline, but contain a small amount of acid elements. Meat is on the Yang end of the scale, and fruit is on the Yin side.

Pure sugar and fats are always Yin. Pure starch and protein are always Yang. Pure sugar, fat starch, and protein are always Acid. Dairy fat is Yin and Acid. Watery fruits and vegetables are always Yin and Alkaline. Raw unsalted seeds and nuts are always Yin and Acid. Cooked grains, beans, eggs, meat, fish and chicken are always Yang and Acid. Yin foods cause expansion of the organs. Yang foods cause contraction of the organs. Consume only the proper quantity of protein, starches, fats and natural sugars that the body requires daily; realize that an excess or a deficiency of these foods can cause disease. Consume mostly whole grains, seeds, and beans from the Yang protein & starch category.

Seasonal Eating Percentages

Season	**Alkaline Foods**	**Acid Foods**
Summer	65%	35%
Fall	50%	50%
Winter	25%	75%
Spring	50%	50%
Very Hot	80%	20%
Very Cold	20%	80%

Note: These are only general percentages. Learn to listen to your inner physiological needs; eventually you will know the right amount, or whether you are eating too much or too little of the Acid or Alkaline foods. Study and learn how to balance foods.

Alkaline Foods Above 7.5PH +

Alkaline Forming Elements: *Sodium, Potassium, Calcium, Magnesium, Iron*

Yang Fruit	***Yang Vegetables***
Apple, Apricot, Berries,Cherry, Grape, Melons, Nectarine, Peach, Pear, Pomegranate	Burdock, Garlic, Dandelion, Ginseng, Onion, Leek, Radish, Watercress, Parsley, Endive,Alfalfa/Kelp-Dulse

Yang Foods: High in Sodium, Low in Potassium.
Yang/Alkaline Foods: High in Sodium, Low in Phorphorus and Sulphur

Yang Fruit	***Yang Vegetables***
Citrus Fruit, Guava, Mango, Papaya, Persimmon, Pineapple,Tomato, Plum	Celery, Cucumber, Cabbage, Sprouts, Sweet Pepper, Green Vegetables Spinach, Asparagus, Lettuce

Yin Foods: High in Potassium; Low in Sodium.
Yin/Alkaline Foods: High in Potassium, Calcium; Low in Phosphorus/Sulphur

Acid Foods Below 7.0 PH +

Acid Forming Elements: *Sulphur, Phosphorus and Chlorine*

Yin Protein	***Yin Fat***	***Yin Starch***
Avocado	Dairy Cow (N)	Banana (Unripe), Carob,
Dairy Cow (N)	Butter (N)	Potato (N), Prunes,
Nuts	Fatty Meat*	Dates, Raisins (N)
Seeds	Avocado, Nuts	Figs, Honey

Regular cheese, milk, nuts and avocado contain both fats and proteins.

Yin Foods: High in Potassium; Low in Sodium.
Yin/Acid Foods: High in Phosphorus and Sulphur; Low in Sodium.

Yang Protein	***Yang Starch***
Tofu and Miso	Carrot (N)
Goat Cheese (N)	Beet (N)
Beans	Beet (N)
Corn Goat Milk (N)	Rice
Olives	Barley
Rye	Oats
Nutritional Yeast	Millet
Buckwheat	Pumpkin (N)
Eggs*, Fish*,	Wheat
Fowl*, Meat*	Peas

Yang Foods: High in Sodium; low in potassium.
Yang/Acid Foods: High in sodium, phosphorus and sulphur.
(N) Neutral or 7.0 PH
* If you can stop these foods, do so.
+ PH taken from urine analysis.

Fig. 7.2. Food Chart Classification with Yin/Yang Designation

Eat Foods in Season

In arranging daily menus seasonal weather changes must be taken into account, especially if one lives in the northern or seasonal climates. Why is this so important? Because, as we men-tioned, cold weather is alkaline upon the body fluids, therefore, the body requires more acid foods to balance itself correctly.

During cold winter months consume more protein, natural starches and fats, and less alkaline foods to maintain internal balance. Use more raw food in summer and more cooked food in winter. Fall and Spring require generally 50% alkaline foods and 50% acid foods. In tropical zones or during summer in the north, 65% alkaline foods can be consumed, while acid food requirements can be lowered to 35%. If the temperature soars over 90 degrees use more seasonal fruits and vegetables, and less grains, beans and cooked food. By eating in this manner heat and cold will be more comfortable, mentally and physically. Hot weather reacts acid upon the body fluids. Vacationers in Mexico and other tropical zones generally blame their diarrhea and stomach upsets on the water. Eating rich, spicy acid foods, cold drinks and ice cream, creates extreme acidosis, digestive disorders and loose bowels.

Consuming excessive alkaline foods in cold weather will cause over-alkalinity within the body; (cold hands and feet, low blood pressure, diarrhea etc.). Excessive acid foods in hot weather will cause over acidity. Living and eating according to the universal principles of Yin and Yang, and Acid and Alkaline should be an enjoyable pleasure and experience for your creative imagination. It is a living, dynamic philosophy a guide, lighting our way to superior health and a well-balanced life style. These life principles should never become a strict, inflexible and austere ideology ruining all joy, happiness and pleasure in life.

Meat eaters and exclusive grain and cooked food eaters have an acid/yang urine pH from 5.0 to 6.0, indicating that the internal organs are working hard to maintain slight alkalinity in the blood. To overcome low pH in the system, consume a little more raw food, (fruits and vegetables in season). Many raw fooders, fruitarians and vegetarians usually have a high (7.3 to 8.0) urine pH, which is considered alkaline and yin. This can result in poor protein/calcium absorption and indigestion. High alkalinity in the stomach reduces its hydrochloric acid content causing the above problems. Balance must be maintained with additional cooked grains, legumes and vegetables. Purchase Nitrazine pH paper to check your urine and saliva readings occasionally.

Above 7.50 PH is an alkaline condition, which is taken from urine analysis. Below 6.5 are in an over-acid condition from urine analysis. Both of these conditions overtax the body causing it to become tired and weak. The body organs are always working to maintain the blood slightly alkaline, 7.22 to 7.35. Over acidity and over alkalinity will eventually break down the organs (disease) because of the immense strain upon them to maintain the blood in proper balance.

Yin/Yang and Acid/Alkaline Conditions

The type of food we eat places us in a definite category. These different categories are as follows: Yin/Alkaline, Yang/Acid, Yin/Acid, Acid/Alkaline balance in a Yin condition, Yin/Yang balance in an Acid condition, and lastly, Acid/Alkaline and Yin/Yang balance. Let us take a look at these different groups.

Yin/Alkaline Condition Above 7.5pH

A Yin-Alkaline condition of mind and body is caused by eating an excess of Yin/Alkaline foods, such as citrus fruits, tropical fruits, grapes, green vegetables, sprouts, onions, tomatoes and any other food that gives a pH reading of the urine more than 7.5. In the non-food category, all drugs, marijuana, alcohol, and soft drinks are Yin (expansive). If one consumes excessive amounts of Alkaline/Yin foods and not enough Acid/Yang foods, the urine pH will rise above 7.5 to 8.0 or more (Urine Scale Test). In this condition the system is deficient in protein, fats, sulfur, chlorine, grains and legumes.

Yin/Alkaline diets are excessively high in potassium. Potassium is an expansive (Yin) or centrifugal element. It expands cells, tissues and organs. If indulged in to excess, this diet can cause kidney expansion and weakness, resulting in over-urination and loss of sex and glandular hormones (testosterone). The kidneys are directly tied in with the entire glandular and reproductive systems. Weak kidneys and adrenals can diminish or stop the sex drive. In this condition the urine turns light in color, like water, with a 7.5 to 8.0 pH reading. The kidneys lose their contractile or yang power and become loose, unable to synthesize protein and filter out waste products.

Excessive consumption of raw vegetables, especially lettuce, carrots and carrot juice will cause liver congestion and yellow/ orange or muddy colored skin, (caucasions only) so prevalent in many raw fooders or vegetarians. The liver eliminates bile through the bile ducts, through the intestines and out with the stools. If the liver is sluggish, from improper foods or constipation, the bile will stagnate and flow into the blood, into the system and out to the skin as a carrot complexion.

An overworked or diseased liver has long ago been associated with a mental condition called melancholia. Melan refers to the skin, and dark bile reaches the skin from biliousness, and causes mental depression & melancholy, or a negative mental condition.

As a result of a Yin/Alkaline condition a person tends to suffer with low blood pressure, (expanded arteries and blood vessels) poor circulation, cold hands and feet, anemia, low blood sugar, diarrhea, asthma, impotence, Yin arthritis, mental and physical laziness, nervousness, schizophrenia, poor memory and loss of concentration.

Mentally, this condition causes fear, worry, anxiety, self-pity, irritability, criticalness and self-righteousness. Yin/Alkaline people are sus-picious, with their nerves on edge, and are therefore easily intimidated on the defensive, mentally and verbally. They attempt to make others perfect, instead of extending freedom to all. Usually unhappy themselves, they force their ideas or advice on others. Remember: These are extreme nutritionally affected psychological behavior patterns. There are variations of this type.

Yin/Alkaline people lose the ability to center (contract-Yang) their mind to a specific goal. With brain cells Yin and expanded, (confused thinking) they are unable to go within (one pointedness) to find peace and contentment.

Dietary Recommendations: A Yin/Alkaline diet is deficient in sulphur, phosphorus, cholrine acid forming minerals; beans, protein, B-complex, whole grains, sea vegetables etc. This deficiency many times leads to cravings and binging on Yang/Acid forming junk food, such as pizza, flesh foods, restaurant food etc. Or due to lack of B-vitamins and protein, (which maintain normal blood sugar levels) an excess of ice cream, cheese and other sugared foods are eaten. Diet lacks grains, beans, miso, cooked vegetables, sea vegetables; too much raw food in winter; not enough grains, beans etc. Diet lacks the pungent and salty taste according to the Five Elements.

Yang/Acid Condition Below 6.5pH

A Yang/Acid condition of mind and body is caused by consuming an excess of Yang/Acid foods such as: all meats, eggs, salt, fish, grains, nuts, fats, cheese, etc., and all other foods that gives one a urine pH reading of 6.5 or less.

Yang/Acid diets are excessively high in sodium. Sodium is a contractive (Yang) element. It contracts or restricts organs, tissues and cells. This type of diet causes kidney contraction or restric-tion, resulting in scanty urination, dark yellow or brownish and foamy urine.

Healthy urine is straw colored or of a light beer consistency. Dark urine indicates over-worked kidneys. The kidneys eventually shut down operation and the end result is Bright's disease. Diseased kidneys are unable to synthesize protein and fail to filter out normal body wastes and environmental toxins.

A Yang toxic liver backs up bile into the blood, making it dark or black, causing biliousness, mental depression and melancholia.

A person in a Yang/Acid condition exhibits aggressive energy-force. They have high blood pressure, ulcers, heart disorders, kidney disease, gout, bone disease, cancer etc. In physical diagnosis, their face and ears are reddish, veins in nose and cheeks, yellow eye whites, hot moist hands and feet, excessive sweating, farsightedness etc. This is an extreme Yang/Acid condition.

If the urine pH drops to 5.5 and below, the kidneys, liver, bladder, lungs, skin and other organs must operate under a heavy load to attempt to expel the excess acid toxins from the system, and to preserve and maintain the blood in its normal 7.5 pH a slightly alkaline condition. When the internal organs malfunction from overwork (overeating, toxins) disease is inevitable; if the blood pH falls to positive acidity, even slightly, death is certain.

The Yang/Acid person exhibits the following physical and mental traits: excessive sexual desire (irritated sex glands), menstrual disorders, hot temper, impatience, arrogance, possessiveness, dominance, hold grudges, exclusiveness, demand immediate attention, and in the extreme, dictatorial.

Mentally, these people are self-centered, egotistical and overbearing in manner and attitude. Unlike the Yin spaced out person, the Yang person is more centered in his concentration and mental activity. Their brain cells are more con-tracted (Yang and centered thinking) to a specific goal. They are not generally fearful or worrisome, like their Yin counterpart.

Dietary Recommendations: This diet is deficient in alkaline minerals: potassium, calcium, magnesium and iron. Also lacks raw foods, fruits, vegetables, seeds, grains, legumes, sea vegetables etc. Yang/Acid people crave many foods and substances, such as beer, wine, alcohol, coffee, mari-juana, tropical foods, potatoes, juices and all sugared foods all Yin and Alkaline, except for potatoes and sugar, which are Yin and Acid. This diet lacks seasonal fruit and vegetables eaten daily in moderation; too much meat, cooked foods and fats, especially in summer. According to the Five Element Taste Theory, this diet is too high in the salty, pungent and sweet taste, and sometimes deficient in the bitter and sour taste. Bitter: almonds, raw vegetables. Sour: apples, plums, yogurt, etc.

Yin/Acid Condition Below 6.5pH

A Yin/Acid condition is caused by consuming chiefly Yin (expansive) and Acid forming foods. For example, milk, cheese and ice cream are Yin because of their high fat (expansive) content, and Acid due to their Acid forming qualities, lowering body and urine pH below 6.5. All sugared foods, such as pies, cakes, donuts, soft drinks, candy etc., are Yin/Acid due to their high sugar and white flour content. All sugar is Yin (expansive), and all white flour products are Acid forming.

People falling in this category usually consume an excessive amount of devitalized junk food. Their urine pH is well below 6.5, and the blood and body is generally deficient in vitamins, minerals, trace elements, enzymes and quality protein. Yin/Acid individuals suffer from every known disease: Arthritis, diabetes, hypoglycemia, gout, obesity, kidney and liver disorders, lung and blood diseases, skin and sexual diseases, fatigue and all types of cancer.

Mentally, this condition produces weak willed individuals, lack of concentration and drive, low self-esteem; usually followers, allowing others to use them; do not think clearly for themselves; do not stand up for their personal rights; allowing others to think for them; duped by commercials and slick advertising, believing without questioning, what product to purchase or what alleged pain killers to use.

Step III: Fill your Arm with the Power of the Heavenly Pool

Sense the sword fingers and the arm as being 'long' and 'big' as you raise them towards Heaven. Sense that the middle of the arm is hollow and bottom is sealed at the shoulder. The mind's attention is focused on merging with the primordial Chi of the Universe, the energy of your thoughts will be multiplied.

As you make your request to the Universe, feel that you are touching a heavenly pool of Sacred Water Energy. Feel that the pool is pouring down like a waterfall to fill the arm. When it is full compact, compress the Sacred Energy into it as much as you can.



Fig. 4.25 *Touch the Heavenly Pool.*

A. ***B.***

Fig. 4.26 A. *Blessing Sacred Water in Russia.* ***B.*** *Opening the Third Eye in Russia.*

Acid/Alkaline in Yin Condition Neutral 7.0 pH

A Yin condition while maintaining an Acid/ Alkaline balance results from consuming an excess of Yin foods in both the Acid/ Alkaline categories, while at the same time eating the correct balance of Acid and Alkaline.

For example, this individual generally eats a large amount of tropical fruit: tomatoes, sprouts, cucumbers, raw greens, fruit and vegetable juices, which are all Yin and Alkaline; all high fat cheeses, milk, avocados, seeds, nuts, oils high in fat (Yin) and Acid forming; bananas, dates, figs, raisins, all dried fruit high in sugar (Yin) and Acid forming; and potatoes, yams, eggplant (Yin) and also Acid forming.

These people generally suffer with cold hands and feet, falling hair, skin disorders, colds, flus, fatigue, nervousness, low blood sugar (hypoglycemia), sexual impotence or frigidity.

Mentally, they tend to be docile, fearful, lack success drive, and express little faith; usually peaceful, but lazy. Recommendations: Diet too high in Potassium (Yin) element; deficient in Sodium (Yang) element; excessive tropical fruits and juices. Balancing the diet: Consume fruit in season and climate only more raw fruit and vegetables in summer, less in winter. Use more cooked grains, legumes, miso, sea vegetables and soups. Lacks sour, salty and pungent taste.

Yin/Yang in Acid Urine pH 6.5 or Below

An Acid condition while in Yin/Yang balance is caused by eating an excess of acid foods, while eating the right balance of Yin and Yang foods. This person generally eats a large amount of the following foods: All grains (rice, wheat, oats, etc., millet, beans, fish, cooked vegetables and soups, burdock, ginseng and beans; little or no raw food).

These people generally suffer physically with lung problems, occasional fevers, yang liver congestion, anemia and some skin disorders; usually underweight and at the extreme, emaciated. Body becomes too Acid. Mentally, they are sometimes arrogant, generally desire leadership and are too demanding. Recommendations: This diet is usually deficient in alkaline elements, such as potassium, iron and calcium. This deficiency sometimes leads to a craving for beer, coffee etc. If the diet is too strict, there may be occasional hinging on extreme Yin/Alkaline fruits, ice cream or other sweet foods or juices. This diet lacks seasonal fruit eaten daily in moderation; too little raw food, especially in summer. According to the Five Element Theory, this dietary condition lacks two of the five tastes sweet and sour. All five tastes must be balanced daily more or less according to the seasons, climate and region where one resides.

Yin/Yang-Acid/Alkaline Neutral Urine 7.0 pH

To acquire Yin/Yang and Acid-Alkaline balance, one should eat a sufficient amount of Acid and Alkaline foods, while balancing the Yin and Yang factors. In order to attain the correct balance, eat mostly the foods grown in your own climate.

In the south, some Yin fruits and vegetables can be eaten daily in moderation, balanced equally with natural Yang grains, legumes, sea vegetables, soups, land vegetables, etc. One who wishes to achieve balance in the North should not use tropical food to any great extent. In the main, their diet should consist of: grains, soups, legumes, seeds and nuts soaked or germinated, apples, pears, berries, burdock, low fat raw milk dairy (sparingly), miso, sea vegetables etc. Consume foods locally grown. Those who constantly have a neutral 6.5 to 7.2 pH urine reading are in Acid/Alkaline balance. A Yin/Yang balance is achieved by adhering closely to the above Yin and Yang balancing diet. This Yin/Yang diet will automatically place one in the proper Acid/Alkaline balance.

The healthiest and longest lived people throughout the world in Tibet, Russian mountains, China, Northern India, Iran, Turkey, etc. do not consume extreme Yin or Yang diets: neither all raw foods or all cooked foods. They eat a variety of natural foods (grains, legumes, vegetables, fruits, seeds, nuts, fermented and cultured dairy products, and meat very sparingly or not at all) grown in their own climate and environment eaten in season.

Those who attain this proper balance, obtain sufficient exercise and sleep, and live in accordance with the natural laws of life will achieve super health physically, mentally, emotionally and spiritually. These are the true compassionate teachers and leaders of the world; their judgment is always sound and useful.

True Teacher - The Tao

Humankind has always longed for a leader/teacher to ease his suffering. But what they really needs is enlightenment from within themselves. A healthy man or woman wants no followers and would never follow another person blindly. They are the true individualists, not carbon copies of another's mind. The true teachers of the world inspire others to great heights. Students learn to think for themselves under a true leader and teacher, and are taught to be responsible for their own actions. They inspire and always extend others the freedom to live their own life without interference. They are positive, happy, magnetic, calm, patient, understanding, loving, kind, and full of pep and energy, with a clear, sharp mind.

Balancing Body, Mind & Blood Chemistry

According to ancient Chinese Taoist health teachings written in "The Yellow Emperor's Classic of Internal Medicine" as the Five Elements and Transformation principle, there is no one perfect or ideal food to subsist on fruits and vegetables alone are too Yin/Alkaline; grains, beans and meat alone are too Yang/Acid. Extreme diets whether Yin or Yang are unbalanced diets, creating imbalances in mind and body chemistry.

A Yin/Alkaline diet can be used effectively as an eliminative or cleansing for a short period of time when necessary. All cleansing diets, fasting, juice diets, sprout/raw food diets can help tremendously to eliminate internal (Yang/Acid) toxins, poisons, overcome Yang constipation, Yang liver disorders, Yang kidney trouble etc., and balance body chemistry. They should be undertaken for this purpose only, and not as a regular dietary program.

The same dietary principal holds true for one who has become too Yin and Alkaline, from eating excessively of fruit, juices, sprouts, vegetables, liquids and all raw foods. One can create a balance in the system by discontinuing all raw foods for a few days or weeks, and consuming exclusively only grain-based products, legumes, cooked vegetables, miso, soups, sea vegetables, etc. These are natural Yang/Acid foods, which will help to bring an extreme Yin/Alkaline system back to balance. After internal balance has been achieved, one can then end this exclusive Yang/Acid diet and return to a properly balanced diet as stated in this chapter and in the following Food Chart.

Extreme Yin Foods:

High Sugar & Fat, White Sugar & Ice Cream, Fructose & Glucose, Margarine & Lard, Dope & Chemicals, Pop & Cold Drinks, Grapes, Cakes, Pies & Jams, Coffee & Alcohol, Baking Yeast & Spices, Chocolate & Candy

Natural Yin/Acid Foods:

Honey & Maple Syrup, Carob & Molasses, Dried Seeds & Nuts, Dried Fruit, Oils & Butter, Avocado & Mushrooms, Potatoes & Nut Butters, Milk & Cheese, Over-Eating

Yin/Alkaline Foods:

Tomatoes & Oranges, Grapefruit & Pineapple, Fresh Figs & Dates, All Juices, Tropical Fruits, Melons & Bananas, Eggplant

Balanced Food Category:

Yin/Alkaline Foods:

Fruits: Apples, Pears, Plums, All Berries, Cherries, Apricots, Pomegranate, Blueberry, Strawberry, Blackberry, Grapes.

Vegetables: Cabbage, Romain lettuce, Green pepper, Sprouts, Alfalfa, Squash, Carrot, Garlic, Onion, Celery, Leeks, Radishes, Sea Vegetables, Broccoli, Dandelion, Kale, Bib Lettuce,Artichokes, Brussels Sprouts, Cauliflower Okra, Swiss Chard, Cucumber, Endive Parsley, Endive Parsley, Mustard Greens, Watercress, Sorrel, Beet Tops, Turnip Greens, Turnip, Spinach, Tomatoes.

Yang/Acid Foods:

Seed/Nuts Soaked: Pumpkin, Sunflower, Sesame, Almonds, Walnuts, Pecans, Brazil.

Grains: Rice, Rye, Wheat, Corn, Buckwheat, Oats, Millet, Barley.

Beans & Peas: Lima, Pinto, Kidney, Aduki, Butter, Black & Tofu.

Dairy: Low Fat Yogurt, Buttermilk, Skim & Goat Milk (Sparingly).

Food Supplements:

Yin/Alkaline: Chlorophyll Liquid, Alfalfa Tablets, Spirulina, Garlic Pills.

Yang/Alkaline: Kelp, Dulse

Yin/Acid: Nutritional Yeast (Eat 90% or More of the Foods in this Balanced Food Section for Optimum Health)

Extreme Yang Foods (High Starch and Protein):

Yang/Acid: Meat, Fish, Fowl, Eggs, White Flour, Brunt Food, Skim Milk Cheese, High Salt Cheese and Cigarettes.

Yang/Alkaline*: Salt, Ginseng, Burdock, Miso and Tamari.

(*Note: Consume Yang/Alkaline foods in cold weather; and very sparingly in warm or hot climates).

Fig. 7.3. Yin/Yang and Acid/Alkaline Food Classification

Effects of Various Diets on Mind and Body

Grains, Legumes, Vegetables, Fruits, Sea Greens, Seeds, Nuts (Soaked) (More Raw Food in Hot Weather-More Cooked Food in Cold Weather): More healthful; physically and mentally balanced temperament. Generally free from illness and disease. Intuition, creativity nature well balanced and more developed.

Grains, Beans, Cooked Vegetables: Tendency to underweight or emaciation. This diet lacks raw food and sufficient potassium; may also lack protein and alkaline vitamins and minerals. Insufficient raw foods during hot weather may cause fevers, Yang temperaments and contracted organs; anemia present; arrogance.

Exclusive Raw Fruit, Vegetable, Juice and Nut Diet: Tendency toward possessiveness, nerve disorders, over sensitive, sentimental and emotional; critical temperament. Disease symptoms: Expanded (Yin) kidneys, intestines, bladder and colon; excessive urination, lung and respiratory weakness; weak digestion and sexual organs, glands and hormones.

Alcohol, Spices, Stimulants and Drugs: Emotional instability and insecurity; heart and blood pressure weakness; expanded kidneys and skin diseases. Disorders in the sex glands and hormones; excessive sexual desire; falling hair on front and sides of head. Poor creativity and confusion in the mental realm.

Meat, Fish, Salt and Eggs: Tendency to be more aggressive, stubborn and determined. More practical, mechanical and materially minded. Fast and sharp thinking mind and senses. Disease symptoms: Constricted (Yang) heart, high blood pressure, circulatory problems, Yang kidneys, liver and gastrointestinal tract (pain in these areas). Constricted constipation, cancerous growths and tumors; farsightedness; loss of hair on top and back of head.

Sugar Products, Honey, Dried Fruits, All Sweets: Mental instability and delusion, schizoid tendencies, nervous disposition, overweight, hypoglycemia, diabetes, skin disorders; expanded (Yin) digestive systems and disorders; weak kidneys and bladder; sexual weakness; liver and pancreatic disorders.

Dairy Foods (Cheese, Milk, Ice Cream): More docile, mentally dull and unresponsive; painful joints and lower back area. Disease symptoms: mucus condition, colds, flu, lung disorders, skin diseases, cysts, tumors, heart and circulation problems; liver, gallbladder, and spleen congestion and sexual difficulties; prone to cancer and growths. Anemia and fatigue are generally present.

A true, lasting and stable physical and mental healing, however must take place after the cleansing period on a well-balanced Yin/Yang and Acid/Alkaline diet. A well balanced diet is a definite requirement afterwards in order to strengthen and build cellular structures, increase normal hormone production, impart muscle tone, form and reconstruct blood and hemoglobin.

Exclusive fruitarian, juicearian or sproutarian diets, beyond a certain point of cleansing, generally fail to produce healthy results in balancing the body physically, chemically and mentally. Blood, bone and muscle are built by 16 mineral elements, several vitamin elements, plus the proper amount of protein, natural complex carbohydrates and fats. A balanced body chemistry is a prerequisite or necessary factor for internal healing and health maintenance.

Extreme Diets cause Imbalances

Raw fooders too often over-cleanse the body to a deficiency point, which leads directly to serious health disorders and emaciation. For example, an emaciated, bony physique is not Nature's plan for vibrant manhood and womanhood. Disorders of this type are contrary to natural law. Powerful magnetic nerve force and energy cannot be built on a diet of fruits, sprouts or cleansing diets alone. One has only to observe an emaciated, bony dog, cat or horse and see that it is not pleasant to look at; its grace, beauty and normal form is gone. The same principle holds true for men and women; they should possess a well proportioned physique, according to their height and bone structure with firm, well-formed and elastic muscles, which look pleasing to the eye.

An extreme raw food diet will create a hinging syndrome, which pulls one to consume large quantities of straight junk food or Yang or Acid victuals, such as grains, bread, potatoes, nuts, health food cakes and pies etc. In balance, these Yang/Acid foods are beneficial in moderation; however, the raw fooders believe that these natural Yang/Acid foods are poisons or mucous forming in the body, and therefore avoid them like the plague. They are constantly pulled towards these heavier Yang foods like a magnet to a bar of steel. Their conscious lower mind or will tells them to eat more and more Yin foods, while the subconscious mind constantly seeks equilibrium, and creates an insatiable craving to overeat Yang/Acid foods. Humans are an intimate part of nature's finer forces; it is the natural law or urge within humans that strives for eternal balance within the body; and it will not be denied by a scheming conscious lower mind.

This same principle of binging can be applied to any strict dieting program: for example, a strict grain and bean diet, which is too Yang and Acid will create an internal subconscious and physical craving (physiological need) or binging syndrome in which one consumes large quantities of Yin foods fruit, juices, vegetables, or Yin junk food, such as beer, coffee, ice cream or sweets.

Extreme Yin or Yang diets are much too rigid and create imbalances in body chemistry. Each causes its own kind of physical and mental disharmony. A person on a strict Yin diet almost always binges on Yang foods. A Yang (diet) person binges on Yin food. According to the cycles of Yin and Yang; Yin, in the extreme turns to Yang, and Yang in the extreme turns or transforms into Yin. If one denies Yin, they will crave Yin; if one denies Yang, they will crave Yang. We are pulled toward what we need, if we deny it in our diet or elsewhere. Raw fooders (Yin) become underweight or emaciated (contraction, Yang). Cooked grain, bean or meat eaters (Yang) are also (Yang, contracted).

A healthy and nutritionally balanced person has no need to fly from one extreme to another; they eat only according to their inner physiological needs and requirements, and select foods from a wide variety of nature's bounty. When out of physical and dietetic balance or half-starved, the lower conscious mind sends a message to the subconscious mind for a more adequate and balanced diet. Always remember: The inner physiological voice or subconscious mind can never be denied without ill-effects. The lower mind or will can make or break you; it can be used to help you develop superior health or turn you into a dietetic cripple, mental and physical wreck or health hypochrondriac. The choice is yours.

The body cell is bi-polar; it's nucleus is positive (Yang); the cytoplasm is negative (Yin). The cytoplasm is alkaline, which is surrounded by the nucleus, acid. For a proper balance the cells need an 80/20 ratio, that is, 80% alkaline and 20% acid. This is of vital importance and is essential for that spark of animation or electric potential between the nucleus and cytoplasm. If an excess of acid foods are eaten, the alkalinity of the cell is reduced. If an excess of alkaline foods are eaten the acidity (nucleus) of the cell is reduced. An excess or deficiency of either acid or alkaline elements in the diet will result in a loss of that vital spark which is so necessary to maintain vibrant health.

Although one can Imitate the diet by observing the techniques of others, this is not enough. There are many people who, even after several years of observing what they consider to be the (ultimate) diet, are still unable to make themselves healthy and happy. Because they have not yet understood the principle behind the diet, without comprehension of which the technique is dangerous. For example, if a person living in a hot climate were to maintain a diet consisting of about 75% grains, 15% cooked vegetables, 5% beans, seaweeds and pressed salad, that person would eventually become very sick (too yang). But such a diet would be a good approximation for the average person living in a cold climate (depending on such variables as age, activity, previous eating habits, and other variables). In short, the clearer one's understanding of the Unique Principle, the better able one is to follow the (correct) diet successfully.

The two most fundamental ways to establish health, freedom and happiness in our life are One: (Yin) by improvement of our thinking ability toward the highest judgment (awareness of Absolute Truth), and Two: (Yang) by dietary discipline in accord with the Unique Principle (Yin and Yang). But actually, these two ways are one, for without using our judgment, how can we eat correctly? And without eating correctly, how can we become aware of Truth? A clear mind cannot exist in a disturbed body.

Sodium and Potassium Balance

The Yin/Yang balance is achieved by regulating the Potassium and Sodium intake. Generally, the ratio is *2* ½ Potassium to 1 Sodium in the human organism. The formed elements of blood contain twenty times as much Potassium as Sodium. This is the main reason why strict grain eaters become underweight, lose muscle form and tone; they lack sufficient potassium, which fills out the muscle tissue and imparts beauty. A 7 to 1 Potassium to Sodium ratio, as advocated by some is much too low for health maintenance. A healthy person does not deny the body what it requires.

To achieve a proper Yin/Yang and Acid/Alkaline balance, it is best to consume food grown in one's own local environment, which includes a daily quota of raw fruits and vegatables, cooked grains, legumes etc. Then, listen to the inner physiological voice, whether to eat Yin or Yang. Our inner body intelligence knows what kind and how much food we require to maintain nutritional balance.

You are What You Eat

You are what you eat is an old axion as true today as it ever was. Food does make or break one's mind, health or character. If one is skeptical of this statement, they are urged to experiment on themselves by eating certain Yin or Yang foods exclusively for several weeks or months, and observe the change or reversal in their temperament, character, and overall health and well-being. Only then will they personally know that we are exactly what we eat, digest, assimilate, absorb, and nothing can change that fact. We can control our health and life by becoming master of our habits. It is an extraordinary blindness to live without investigating what we are. A sound brain is not found in an unsound body; nor do we find a sound body nourished by an impure blood stream.

Balancing the Life Cycle Triangle

Everything in life affects the Yin/Yang and Acid/Alkaline balance. Activity, such as exercise, work, study, etc., creates acidity (Yang), while rest, sleep, creates alkalinity (Yin) within the body. Cold weather is Yin/Alkaline upon the body, while hot weather is Yang/Acid upon the body. Anger, hate and jealousy create Yang and Acidity; peace, love, harmony in thoughts and actions and enthusiasm create a natural body balance. Positive thoughts are Yang; negative thoughts are Yin.

Exercise creates acidity within the body. Vigorous exercise, where there is a breakdown of muscular tissue, as in barbell training, distance running, swimming, etc., will cause much lactic acid to be generated in the system. In this case, the athlete will require more calories from complex carbohydrates (grains, legumes) to replace the broken down tissues. However, Yin/Alkaline foods must also be consumed to balance the acidity of the exercise and to replace and renew electrolytes within the cells and tissues. This is not to say that one must overeat; on the contrary, the demands made upon the athlete's body will automatically require that he eat enough to sustain his endurance, stamina, strength and health. A non-exerciser cannot possibly utilize his food as efficietly as an exerciser, due to slower blood circulation, poor stomach tone and weak assimilation of food.

Only you can judge how much activity or rest you require, and also how to balance your diet properly. You must listen to your inner conscience (voice) to know when, what and how much to eat, sleep, work, exercise, etc. Be moderate in all your activities.

The Life Cycle Triangle is the Law of Rhythm in dynamic action. By understanding the universal law of rhythm, one may achieve superior health and harmony.



Fig. 7.4. Life Cycle Triangle

Feminine and Masculine

Yin and Yang can also be viewed in terms of our feminine and masculine qualities. It is a common misconception that only women should have feminine qualities and only men should possess masculine qualities. Yin/Yang theory is a theory of relativities, not absolutes. All of us are whole as we are, and thus we have our Yin aspects and our Yang aspects. These aspects include the following:

Feminine	***Masculine***
Intuition	Logic
Receptive	Creative
Passive	Active
Internal	External
Subconscious	Personality

Step IV: Make the Cross on the Top of the Cup

Put Sword Fingers on top of the Cup. Ask for the Yin Power: **Command 1:** ***"Yin Power and good fortune, come from the east. Yin has the power to dissolve all negative energy, all sickness and bad fortune."***

Command 2: Make the cross on the top of the cup and say ***"By my request......"***.



Fig. 4.27 *Give the command: "Fortune comes from the East - Yin has the power to dissolve all negative energy, all sickness and bad fortune. By my request....".*

Step V: Charge the Water to Transform it into Sacred Water

Bring your arm down and point the sword fingers into the glass of water. Smile and circle the sword fingers around the inner rim of the glass.

Continue to order: ***"Please carry out the order now."*** Repeat 3 times to charge the water with the Yin Power. As you do this, project a good thought into the water.



Fig. 4.28 *"Please carry out the order now" Repeat three times, charging the water with the yin power.*

We all possess all abilities and are complete in our self. However, when we are with another person, we may be relatively feminine (Yin) or masculine (Yang) compared to them (regardless of gender). Often (but not always) a woman is relatively Yin compared to a man, but she still possess Yang qualities within herself.

These individual differences are what give us our individuality and do not need to be fixed or changed. It is only when the harmony within our self becomes unbalanced that we may need to take remedial action. For example, a person with a lot of feminine qualities may be always cooler than their more masculine and partner who has a warmer body temperature. This does not need to be viewed as a problem as it is simply individual differences.

However, if a person suddenly feels that they are much colder than they used to be, and begins to suffer discomfort from it, then there may have been a change in their own internal balance that needs to be addressed.

In terms of remedial action, we can see that proteins and fats enhance our masculine or Yang qualities; whereas carbohydrates enhance our feminine or Yin qualities. We often think of meat as being a masculine food, and we think of sweet foods as being a favourite of women. If the Yin/Yang imbalance starts to cause health and wellbeing imbalances, then we may need to use the opposite food to bring ourselves back into balance. Five Element Dietary Therapy is a delicate art of listening to the body & responding accordingly.

Yin and Yang Dietary Guidelines

The balance between Carbohydrates and Proteins/ Fats is the most broad way to balance Yin and Yang. However, there are many different aspects of diet that can assist in this, including:

Cooking Methods
Thermal Properties of Foods
Water Content of Foods
Flavors
Colors
Parts of Plants Eaten

In Five Element Dietary Therapy, these factors all have a subtle influence on the energetics of our food. Paying attention to them can enhance the effectiveness of our dietary therapy.

Cooking Methods:

Raw foods and lightly-cooked foods have a more cleansing and cooling effect on the body. Thus they can be used to treat an overly Yang situation, especially where there is heat and toxicity. The longer a food is cooked, the more warming and nourishing it becomes. Therefore, these cooking methods can be used to treat an overly Yin situation, especially where there is coldness and weakness.

Nourishing	***Cleansing***
Grilled	Raw
Baked	Steamed
Pressure Cooked	Stir-Fried

Thermal Properties of Foods:

The ancient Taoists discovered that each food has its own thermal property, regardless of its actual temperature. These can be chosen specifically to regulate internal temperature imbalances. Some examples include:

Warming	***Cooling***
Ginger, oats, chestnut, sesame seeds, sweet potato, garlic, kale, date, cinnamon.	Lettuce, cucumber, celery, cabbage, tofu, wheat, yoghurt, peppermint.

This can be taken as additional information and used if there is a specific temperature imbalance.

Water Content of Foods:

One of the features of overly Yin is to have an excess of water, such as fluid retention, dampness and phlegm. A feature of the overly Yang situation is to be too dry, such as dry skin, dry hair, dry nails and dry lungs imbalance may choose lighter foods such as fruits and salad vegetables.

Parts of Plants Eaten:

Yin and Yang are relative terms, and thus they can be applied to any whole unit. Therefore, we can find Yin and Yang aspects within one vegetable. Some parts of the plant will have a more expansive effect, others more contractive, and some centering.

Just as we saw with the tree example, the roots of a vegetable will have a more grounding and contracting effect. The shoots and stalks have a more neutral effect. Leaves and flowers have the most expansive and uplifting effect.



Fig. 7.5. Parts of Plant Eaten

Eating all parts of a vegetable will have a balanced and whole effect, or we can choose specific parts for their specific qualities.

Yin/Yang Guidelines:

Therefore there are many different aspects of the food we eat that we can attend to when we are trying to regain balance. The relative amounts of carbohydrates versus proteins and fats is the most powerful factor, but the others can be used to rebalance on a more subtle level.

To Treat Overly Yin		***To Treat Overly Yang***	
Quality	***Effect***	***Quality***	***Effect***
Protein/Fats	Slow-Release Energy	Carbohydrates	Fast-Release Energy
Long Cooking	Nourish	Light Cooking	Cleanse
Warming	Warms	Cooling	Cools
Low Water-Content	Dries	High Water-Conten	Moistens
Salty	Grounding	Sweet	Uplifting
Dark colour	Grounding	Light colour	Uplifting
Roots	Grounding	Leaves	Uplifting

No Extremes

Five Element Therapy always warns us about the dangers of extremes, if we choose an extreme diet we will always pull ourselves off-center, and building a strong center is so important for health and happiness. One of the rules of Yin/Yang theory is that an extreme will always turn into its opposite. Remember the example of the workaholic who suddenly collapses with exhaustion? This rule applies also to dietary therapy.

Thus the overly Yin person may benefit from the addition of a few extra proteins and quality fats. However, if they were to embrace a diet exclusively of these foods, they may in fact end up feeling too heavy and even more lethargic! Sometimes excessive consumption of meat is not calming and grounding, but actually creates aggression. This is an example of an extreme having the reverse effect.

Similarly the overly Yang person will benefit from a few more carbs in the diet. For example, a few salads and steamed veggies will cool and calm them immensely. However, if they were to go overboard on fruit juices and sweet foods their blood sugar would rise up excessively, causing too extreme an energy rise. It is thought wiser to take one’s time and add a few foods into the diet for rebalancing. Once again the golden rule of the center appears: if we are eating some centering foods, plus the rebalancing items, then we will have a more successful result in the long-term.

We have become a very mind-dominated society in the modern world. This can lead to the situation in which we try to rule the body with the mind. However, a healthy relationship in one in which listening and acting are equal therefore we must listen to the body and then act. This will improve the relationship between mind and body. Controlling the body with the mind can lead to the development of an eating disorder and can bring us a long way from feeling whole.

Taoist practices always aim to harmonize the different aspects of the self, indeed, this is another way to balance Yin and Yang: the body is Yin relative to the mind (yin= material, Yang = immaterial), and so to harmonize the two is healing in itself.

Eating Habits versus Making Changes

Our eating behaviors are directly correlated with our psychological patterns. Eating is tremendously tied in with our emotional being; it is far more than meeting our physiological requirements. Humans are the only animal that has taken the act of eating beyond the practical level. Therefore, to look only at the micronutrients in our food is to overlook a major aspect.

Think about the emotional aspect of eating: we celebrate occasions with elaborate feasts, when we fall in love we exchange gifts of food (chocolates especially!) and we take our beloved out for dinner. As well as expressing joy with food, we can then use food to try to recreate that sense of happiness when are no longer feeling it; hence the concept of comfort eating (one extreme being bulimia nervosa). Think of the woman who has just ended her relationship munching her way through a big box of cookies.

Other people are used to receiving attention through pain, it is not uncommon for victims of abuse to develop eating behaviours through which they punish themselves with food. They may try to starve themselves (anorexia nervosa) or to eat very plain foods or extremely strict diets. This is a way of reinforcing the belief that they are guilty and must be punished.

This emotional link with food operates on even a more subtle level, and we receive comfort or pain on a highly subconscious level all of the time. It is easy for us to develop eating patterns and habits that reinforce our psychological blocks, and this will create cravings for foods that do not serve us.

Intuition vs. Addiction:

We often talk about the body's wisdom and natural intuitive ability. We may assume that our body's desires are always for what will heal us or for what we need. How do we know whether we are craving a food that we are addicted to, or that our body is asking for what it needs? We can see how cravings arise when we look at the more addictive foods. If we have been drinking coffee for many years then our body adapts its energy system, as it expects a cup of coffee every morning. This leads to a craving for coffee, which will maintain our current equilibrium, though it will not bring us into vibrant health. This is a craving for what our body expects rather than a desire for what our body needs.

When we develop an eating habit, for any food, then we may crave it as our body's way of maintaining routine. The further a food is from the center the more addictive it can become. Centering foods are the least addictive.


Expansive
Drugs: Caffeine, MSG,
Flavorings, Colorings
Alcohol
Sugar
Fruit Juice
Fruit
Salad
Leafy Vegetables
Vegetables
Root Vegetables
Whole Grains
Tofu
Seeds
Nuts
Lentils
Beans
Miso
Fish
White Meat
Red Meat
Eggs
Salt
Center
Contractive

Fig. 7.6. Intuition vs. Addiction

Most addictive foods: drug-foods, including 1MSG and caffeine, alcohol, sugar. The more refined a food is, the more expansive and thus addictive. At the other end of the spectrum we have the most contractive foods, especially salt, but also an excess of meat and eggs. Dairy products may become addictive as they have the effect of protecting us from difficult emotions. More extreme foods are more addictive.

Balancing foods include vegetables, salads, whole grains, tofu, seeds, nuts and lentils. It is unlikely that we will develop an addiction for these foods, unless they have been refined or have additives. Therefore we have to be on alert for what is a true instinctive desire and what is a habitual craving, it is important to learn to distinguish between the two so that we can choose healing. If we wish to restore our health we may have to address our habitual patterns and release the underlying emotions.

How to Spot a Craving: The desire for a food tends to feel more urgent; our body may feel mildly panicky; sometimes there is a secretive aspect to the desire and we will consume the food where no one else can see us (we feel ashamed); or we may hang out with others who share our habit to justify ourselves; extreme contractive or expansive foods are the most addictive; it is a desire for the same substance over and over; we may want more and more an insatiable desire.

How to Know an Intuition: The desire Is deep, but not urgent; our body feels calm and relaxed; our desires change as they are responses to the changing environment; once we have taken the food, we are satisfied and the desire is gone.

There is no right or wrong in this, We all have a choice at every moment. If you feel ok in your current situation, then do not try to make changes. If you are motivated to make a shift, then change your diet and make space for transformation. Do not change your diet for no reason. Rather, learn to listen to your body and act (or not) accordingly.

Clearing Habits: Fasting and cleansing are great ways to clean the slate and start again. For example, just following a simple diet of organic centering foods, with no salt, sugar, caffeine or additives, can helps us to clear attachment to old patterns. Such procedures must be accompanied by consciousness: it is important to take time to look at what is going on so that we can really make the shift at a deeper level. Often when we remove our comfort foods, emotions will arise that we had been suppressing. This needs to be met with awareness, so that we can find ways to meet the underlying pain and thus heal it. It can be a wise idea to go to a Fasting Center, where you will receive guidance throughout your cleanse and emotional support will be offered. Meditation is a great accompaniment to any cleanse or fast, as it helps us to bring consciousness to our process.

Healthy Habit Formation: If you have a strong mind, be wary not to let your mind overtake your healing process. It may be that we feel great when we fist make a dietary change; for example, we add more protein to a protein-deficient diet. At first we feel fantastic at this change. But then the mind takes over, adding protein to every meal, if we do not listen to the body, then we may not hear a signal that our diet has been rebalanced and it is time to move back to a more balanced diet. In this way, what started as a healthy change soon becomes yet another mind-controlled habit. When the mind takes over our eating habits, it is possible to develop an obsessive disorder, it is even possible to become so obsessed with eating what the mind considers health foods that a disorder called Orthorexia Nervosa can develop.

In Five Element Dietary Therapy, the focus is only to correct an imbalance if one exists. Once everything is back into balance, the person is encouraged to eat a wide variety of foods and a balanced diet. Obsession with food is considered an imbalance of the Earth Element (of the Taoist Five Element Theory) and is a sign that the person has a weak center. It can be the result of consuming too many extreme foods and of partaking of too many extreme activities.

Maintaining Balance

There is a difference between using dietary therapy to correct an imbalance, and eating to maintain health. Often when people fist become interested in nutrition, it is because a health problem has motivated them to make change. However, once that problem has been healed, we then need to switch our diet towards one that simply maintains our good health.

Maintenance Diets need to have Several Qualities:

1. They must be stable, and not extreme, so that they are easy to follow continuously.
2. There is evidence that they have been in use for long periods of time.
3. They promote wellbeing and health.
4. They promote longevity.

Thus to find an ideal maintenance diet, it can be helpful to look into different cultured to find diets that have been in use for a long time and in which the members of that population enjoy good health and longevity.

It is important not to mistake rebalancing diets for maintenance diets. Rebalancing diets will involve going to the opposite extreme for a period until we come back to balance. However, once balance is achieved, it is important to switch to a maintenance diet, else we will swing the other way. For example, many people suffering from the results of an excessive lifestyle: too much fat, sugar, toxins and stress, will benefit from a cleansing diet such as raw food. However, after a period, one should return to a more balancing diet else eventually the body will weaken.

Different cultures can be observed to have very high levels of longevity and wellbeing. For example, the island of Okinawa in Japan is known for the outstanding longevity of its inhabitants. This population has been studied extensively to gain better understanding of their dietary habits. The average citizen of Okinawa will consume a diet made up of the following:

> At least seven servings of vegetables daily, and an equal number of grains (in the form of noodles, bread, and ricemany of them whole grains).
> Two to four servings of fruit.
> Green tea (full of anti-oxidants).
> Tofu and other forms of soy; various types of seaweed (soya and seaweed balance each other in terms of iodine)
> Sweet potatoes, bean sprouts, onions, and green peppers are prominent in the diet.
> Vegetables, grains, and fruits make up 72% of the diet by weight.
> Soy and seaweed provide another 14%.
> Meat, poultry, and eggs account for just 3% of the diet
> Fish about 11%; fish rich in omega 3 is taken (about three times a week).
> There is an emphasis on green vegetables rich in calcium.
> Okinawans, like other Japanese, don’t eat much dairy (calcium comes from the dark leafy greens).
> Okinawans do drink alcohol, but women usually stick to one drink a day, while men average twice that. Moderation is key.

In terms of vegetables, there is a special emphasis on sweet potatoes, which play a central role in the diet. This food has a very different effect on health than the normal potato. For example, a baked potato releases blood sugar very fast, whereas a sweet potato Is slow-releasing. In Five Element Therapy, the sweet potato is known to improve digestive ability by enhancing the spleen-pancreas.

The diet of the Okinawans is in fact what Five Element Therapy would call a centering diet. It minimizes extreme foods and focuses on those that have a centering quality. According to Five Element Therapy, such a diet puts least stress on the body (extremes cause most stress) and help to maintain wellbeing.

Building a Strong Center

In Five Element Therapy, the strength of the center can be seen by the power of our digestive ability. The ideal situation is one in which we can eat anything without a problem. This is called having a good digestive fire; though even this does not want to be excessively strong. Digestive fire is a concept in many Asian nutritional systems; in Ayurveda it is called “agni”. In Five Element Nutrition they take the model of having a small fire burning in the belly. The stomach is like a cooking pot, and when we ingest food it enters the cooking pot and is broken down by the fire.

If our fire is not strong enough, we will struggle to digest the food that we eat. We may feel tired after eating, have constipation or lose stools, or even undigested matter in the stools. Feeling that we cannot absorb the food that we eat is frustrating to those who are trying hard to improve their health. There are several steps we can take to enhance our digestive ability, including:

1. ***Chew.*** This is the most simple and efficient way to boost digestive fire.
2. Taking root vegetables can be very helpful to nourish the digestive fire: pumpkin, sweet potatoes and carrots.
3. Adding a few digestive spices, such as cinnamon, cloves, nutmeg & garlic can assist. Avoid these if there are heat signs.
4. Avoid foods that are cold, sweet or mucus forming, as these will diminish the fire! Ice cream is a prime example, but also iced drinks, refined sweets and dairy.
5. Eat a good breakfast: this is the time that the Earth Element, which rules the digestion, is active. Therefore, a wholesome breakfast that is not too sweet can help our digestive ability.

Try not to get too scattered during the day: taking on too many tasks, seeing too many different people, being too long on the internet or having different communication sources all going off at once these will all scatter your Chi and diminish your center. The more we can build a sense of center, the better our digestion will become.

Step VI: Command 3: *"All sick cells please listen : Clear, Clean and Bright, this Sacred Water will take all the Sickness away."*

Give the above command. Use the thumb and index finger to pick up sick energy from the cup, without touching the water. Do this three times.



***Fig. 4.29** "All sick cells please listen: clear, clean and bright, this sacred water will take my/your sickness away".*



A.

B.

Fig. 4.30

***A.** Ask for the power to see the cells - if they are toxic and dark, ask for them to be cleaned out.*
***B.** "Clear, clean and bright".*

Chapter 8

Diet Fads, Junkfoodism to Extreme Yin and Yang

Confusion Reigns Supreme

Webster defines a fad as a pet idea, a passing fad or fashion. There are literally dozens of dietary fads in vogue today. It is the thing to do. Each fad has it’s own set of prejudices, rules and regulations. Many people often experiment on themselves, changing from one dietary program to another without learning sound and scientific nutritional and health principles. In most cases, the fad diet does not meet their own individual and physiological requirements.

Confusion reigns supreme and many people give up in disgust and return to the realm of junk food. Thus ignorance, prejudices, fashion, gullibility due to fear tactics or false hope, and a relaxing sense of security which comes from allowing someone else to think for us, are all forces which make people susceptible to dietary fads. Some food fads are harmless, while others can be very dangerous to the body. An occasional exclusive fruit or eliminative cleansing diet when the physiological need arises is definitely bene-ficial and health building; but carried to extremes it can lead to malnourishment and ill-health. The same with an all grain diet; it is very cleansing and healthful for a specific period of days, but carried on exclusively or permanently, it can be damaging.

An exclusive fruit diet, vegetable diet or grain diet are referred to as mono-diets. Each diet itself is based on simplicity, which makes digestion much easier, to allow for healing, cleansing, rebalancing the internal organs, and rejuvenating the blood and lymph system. Thus, a mono-diet improves one’s physical and physiological health. Complete rest, mental poise, sunshine, exercise, pleasant and healthful environmental conditions are all key factors along with a simple nourishing diet that produce favorable results in any dietary system or health program. Generally, if one’s diet is well balanced in all food elements and if one exudes energy, glowing health, and vitality constantly, that person is cultivating good eating and living habits. This person is not a food faddist. He or she is balanced mentally, physically, spiritually and emotionally.



Fig. 8.1. Whatever you do, or dream you can do, begin it.
Boldness has genius, power and magic in it.
We can live in the Tao by just deciding to do it.

The fact that a cult or organization has a large following, or that its followers experience certain benefits, are not conclusive proof for or against the philosophy it teaches. People can be helped temporarily by almost any change in diet away from the conventional meat and potato, coffee and donut mode of existence. Dietary and reducing fads are more fashionable than sensible. Propaganda is the tool used to rake in enormous financial profits. People are commercially exploited by fast and slick salesmen who prey on the credulous and fearful public.

Many strict dieters limit themselves unnecessarily in their choice of foods, in the false belief that these foods are fattening, mucous forming or acid producing. Some people cannot tolerate fruit due to gas; others shun grains and beans; some are strict food combiners; and some cannot tolerate nuts or dairy products. These notions are generally not based on a solid foundation of facts. Such people make themselves miserable by attempting to live by a set strict standard of rules and regulations; of do nots and cannots. So, for the bewildered dieter, what is left to eat?

The longest lived and healthiest people throughout the world do not follow any dietary fads; they are usually much too busy working outdoors planting, gathering food, climbing mountains and working the fields. They achieve good health by living close to Mother Earth, making work their exercise and remaining physically fit well over the century mark: sunshine, fresh air and outdoor activity are part of their daily living habits. People who are bored with life nothing constructive to accomplish lacking exercise and physical fitness and seeking excitement and stimulation in artificial things, are the ones who run, like bees to a hive, to the first dietary fad that sounds plausible to them. If results are not forthcoming, they look to other dietary cults for further relief or guidance to their health phobias.

Raw Foods vs Cooked Foods

Most fruits and some vegetables should be eaten raw. Grains can be sprouted, cooked or made into bread and casseroles. Root vegetables, squashes, beans and peas are more easily digested and assimilated when well cooked, steamed or baked. The body requires some raw fruits and vegetables daily; they furnish vitamins, minerals, enzymes, especially vitamin C which is lost in cooking. There is no absolute necessity for anyone to consume all foods in the raw state.

In fact, there is no proof whatsoever of strict raw fooders living any longer, or being any healthier than a person on a well balanced moderate natural and mixed food diet. Many raw fooders have digestive problems because of sensitive and expanded (Yin) intestines and kidneys. Protein deficiencies are also common. A good natural food mixed diet, including raw and cooked foods, is better for most people.

Food Crank

We are living in an age of the food crank. Many theories are expounded concerning the natural food of humans, and how to prepare food. The theories and speculations are abundant. Listed below are just a few now in vogue. Cooking is evil and against nature, only raw foods should be eaten. Eat lots of meat, humans are carnivores. Eat only cooked grains and vegetables, raw food is for apes. Eat only raw fruits and nuts, humans are like apes. Drink only fruit juices, humans are fruitarians and was not originally meant to eat solid food. The body requires no protein, eat only sprouts and fruit. The high-protein diet is necessary for health and strength. Live on air alone, human are breatharians and should fast as much as possible, drinking only water. And on and on. If all of them are right, we should all, right now, stop eating and never leave our homes from all this confusion. However, all is not lost; there is bright hope for survival in this nutritional/dietary jungle; a healthy, vibrant life can be achieved by thinking, studying, contemplating and applying the secrets of the ancients as set forth in this book.

Overcoming the Junk Food Syndrome

Because of nationwide publicity, in recent years, on the subjects of natural living, health foods and vegetarianism, the public has become more consciously aware of their health and well being; taking positive responsibility for their actions. The term Junk Food Junkie was coined during the surge of health awareness in the 1960s, and refers to those people who take little or no responsibility for their own health usually consuming a great deal of processed, chemicalized, unhealthy junk food. This group generally refers to a health food conscious individual as a health food nut.

However, many health food nuts, if not balancing their diet carefully, can be easily caught in the Junk Food Syndrome. There is a difference between a Junk Food Junkie, and one who is caught in the Junk Food Syndrome. The former consumes junk food at almost every meal; the latter eats healthy food most of the time, but all too often finds himself caught in the vicious circle of junk food eating the Junk Food Syndrome.

We will address those health fooders who would like to put an end, once and for all to their hinging, or Junk Food Syndrome. Fasting or cleansing programs: Many people fast or attempt a raw food cleansing diet indiscriminately, or when their body does not require one. They have usually been on a general health food diet for several years or have undergone several detoxification programs with some degree of success. However, this person may believe that a fast or raw food diet of long duration will cleanse the body permanently. They have experienced the Junk Food Syndrome for many years and believe that fasting or raw foods only will cure their cravings for junk food. All too often, this group will be found junking-up or pigging-out on their favorite morsel of junk food soon after a fast or raw food trip. (Pizza, ice cream etc.). Fasting is extremely alkaline on the body cells and fluids, which are necessary to cleanse and purify a toxic and diseased organism. A very sick and diseased conventional calamity food eater will benefit greatly by a long fast or an extended juice diet. Why? Because they are so acid, Yang and full of mucus, toxins and wastes, that fasting or raw juices will counteract, neutralize and allow the body to eliminate these diseased conditions toxemia. They need a fast to balance out their alkaline reserves and Yin/Yang polarities.

However, most vegetarians and health culturists do not need a fast, as they are quite alkaline, Yin and flushed out from all the alkaline and Yin foods they have been eating. What they need is proper and complete nutrition to put an end to the Junkyism Syndrome. An occasional short fast, fruit or juice diet for a few days should not cause any problems, provided a sound nutritional program is followed afterwards. Eating too much fruit or juices, especially in cold weather, (Yin) will cause a swing in body polarity to eating heavier and more Yang and Acid forming foods such as, starches of all kinds and heavy protein foods to excess.

The key to good health is to balance these two factors according to the weather, environment and physical requirements on any given day or hour. You must listen to your inner voice and body intelligence for its daily food needs.

Causes of Junkfoodism

Junkfoodism in health food (conscious) people, can better be defined as a syndrome or symptom brought on by poor dietary habits, bad digestion, poor assimilation and absorption and malnourishment. Although health fooders consume much more natural, pure and healthful foods than the conventional eater, they do, more often than they would like to admit, garbage-up or eat calamity junk foods such as, ding-dongs, cakes, pies, soft drinks, cookies, moon pies, candy, pizzas, twinkies, ice cream, fast food hamburgers and on and on. The reader can easily add to this list.

What causes Junkfoodism and the Junk Food Symdrome? How may one overcome the insidious and incessant cravings for junk food? Are you beginning to wonder if it is possible for anyone to live on a natural food diet without experiencing those hidden hunger pangs and the Junk Food Symdrome? Is there something wrong with you, or does everyone experience these health food growing pains?

We have all experienced the Junkyism Syndrome in our own personal way. Each of you can relate a case history of your trials and experiments on various diets and junk food trips. However, there is only one basic cause or reason for Junkyism, and it is this: The body is crying out for vital nourishment in every cell and tissue of its being. If your body could talk it would tell you that it needs an adequate supply of top quality protein, natural vitamins, minerals, trace elements, carbohydrates, fats and enzymes; to be eaten in such a manner that it can easily assimilate, absorb, digest and utilize the vital essences of those foods.

The diet and health suggestions as outlined in this book can help one overcome the Junk Food Syndrome and guide them to mastery of their eating habits. Junkfoodism can be overcome, and eventually one may look upon it as an experience or growing pains in their quest for super health. There are certain practices, misapplications, lack of thorough understanding of health principles and poor living habits that cause abnormal food cravings and malnourishment, that turn a person into a junkfooder or health hypochondriac. An excessive daily consumption of raw foods, raw greens, dried, unsoaked nuts and seeds, dried fruits, lack of oxygen after meals, lack of exercise, too much fruit or juices, fasting when not required, lack of sufficient sleep and lack of proper nourishing foods and food supplements are some of the reasons why health food people turn into junk food junkies.

Flowing with the Tao and Yin/Yang Forces

As we give up our junk food habits, such as coffee, alcohol, sugar, ice cream, milk, meat, pastries, etc., we begin to crave and desire these products as they are being eliminated from our system. An outright denial of these cravings can be disastrous to both mind and body. But the reason we desire these foods is because they cause an addiction and when they are eliminated too fast we experience withdrawal symptoms, the same as a drug addict. However, this is only temporary, until elimination of internal toxins is complete, and the body becomes balanced.

When we totally deny our addictions to junk food, with the attitude or affirmation of never eating them again for the rest of our lives, we become obsessed with denying that which our body craves for. If the mind denies junk food strongly enough, it will run to what it dwells upon, and cause one to junk up hi large quantities. A good method to overcome junk food addiction is to say to yourself, I will avoid junk food for as long as I can, then when I desire some junk food, I will eat it in small quantities only. This will satisfy the addiction or withdrawal symptoms, and your mind and body will be more at peace. As your body continues to cleanse and eliminate poisons slowly, over a period of weeks or months the junk food that once tempted you, will no longer do so. Your cravings will vanish like magic, and you will become the master instead of the slave of your dietary habits.

The reason this method works is because we are not negating or feeling guilty about eating a small amount of junk food occasionally. When we affirm to our mind that we may eat anything at any time, the struggle between our mind and body ceases. This no deny method removes the tension and stress which accompanies the attempt to live up to our perfect dietetic expectations or ideals. Tell yourself that you cannot have something, and you will want it even more. An extreme Yang action will change into an extreme Yin reaction.

When the mind/will/ego are used (in a Yang way) to overcome, control or deny physical or physiological cravings and addictions (Yin) which are still present in the system extreme junk food binging is generally the result. If the Yang mind strongly denies an inner craving, the craving usually wins out. If Yang will not bend, it will break. Yin and Yang must be balanced within the body for optimum health. This is the unique principle of physical life.

Deny something, and you will be pulled toward it. Place a wet paint sign next to a freshly painted fence, and people will touch it to see for themselves if it is wet or dry. Vow to become a celibate, and your sexual cravings will overwhelm you, unless your whole being body, mind and soul has overcome the desire without struggle. Denying or struggling against something takes us away from the flow of life from harmony with the Tao. Tell a child a fire will burn and hurt him, and in spite of the warning, he will play with fire and get burned. Deny him the real experience and he will be attracted to it unconsciously.

Eat too Yang, and you will crave extreme Yin, and vice-versa. The mind and body operates in unison; an unbalanced body creates an unbalanced mind, and an unbalanced mind further imbalances the body. The mind creates the body. A sound mind in a sound body is what we should strive to attain. In this physical three-dimensional world all is duality and change. Nothing here remains forever the same. All phenomena are constantly spiraling onward and upward evolving into higher and greater things. Change *is* the illusion of the physical world; the spiritual worlds never change they are absolute and non-dual; it is where the dual physical world is born. The One (Wu Chi) becomes the two (Yin and Yang), the two becomes the three (Trinity) and the three becomes 10,000 things.

Flexibility is the Key to Yin and Yang Balance

Second generation teachers like Michio Kushi, Michael Abehsera, and Herman Aihara modified these (Ohsawa's) practices and recommended a somewhat wider application of grains and vegetables. Michio Kushi's standard diet of fifty percent cereal grains, twenty-five percent cooked vegetables, and twenty-five percent supplementary foods such as miso-soup, beans, seaweeds, fruit, is an example. While this diet is generally sound for the temperate zones, it can still create complications if its practitioners do not understand how to apply the unifying principle of yin and yang. A principle without a practice is useless; a practice without a principle is dangerous. I have seen too many people become too yang that is, contracted, rigid in their thinking, subject to a variety of symptoms associated with over-stimulation of the parasympathetic nervous system, etc. Aside from the discomfort of being too yang, such people suffer an inability to discharge old, poor-quality, stored yin such as cholesterol, crystals, stones, and cysts. The simple fact of the matter Is that the heart must expand as well as contract, we must breathe In as well as out, and so on. Yin Is necessary to life. In fact, as a general rule we need at least seven or eight times as much yin as yang In our diet, and the ratio can go much higher if, for example, we are very active (yang) in hot weather (yang). However, if we become too yang the body will necessarily retain its stored animal fats and yin toxins, particularly if we consume too much salt and other minerals such as those contained in seaweed. The farther we move toward yang and away from balance, the more desperately will the body hold on to yin.

The frequent practice of macrobiotics is to deny cravings until they build up to a point of Irreslstabllity, at which time many people binge wildly, eating pints of ice cream, sugar-rich foods, meat, or even on occasion turning to drugs such as marijuana, LSD, or cocaine. The law of front and back Is undeniable. Balance will be made sooner or later. We must learn to change and be flexible in our diet and health program. What worked for you in the past may not work for you now. You are a different person every second, every minute, every hour, every month and year. Without constant change, growth and flexibility, we would die of stagnation. Accepting change and flexibility in this physical Yin and Yang world spirals us onward in our quest for perfection, toward the Universal Force.

Overcoming the Junk Food Syndrome

1. Consume a well balanced diet consisting of whole grains, beans, peas, sea vegetables, seeds, nuts, fruits and vegetables, miso, tofu.
2. All seeds and nuts should be soaked and germinated overnight for proper assimilation and protein absorption. These can be blended into a seed or nut shake the next day. Eat germinated seeds and nuts more in hot weather and sparingly in winter. Seeds/nuts can be roasted in winter.
3. Use whole food supplements daily: nutritional yeast, alfalfa seeds (powder or tablets), carrot calcium, kelp, dulce, nori etc., raw vegetable juice (more in summer), fresh raw wheat germ, miso, soybean powder, etc.
4. Beverages: cereal grain coffee, dandelion, bancha twig tea, Mu tea, jasmine tea, alfalfa tea.

5. Consume vegetable stock soups highly nourishing.
6. Eat more cooked grains, beans, vegetables and soups in winter according to inner bodily requirements; more raw food, in season, in summer. Use the various methods of cooking: sauteing, boiling, steaming and baking.
7. Consume some raw food daily, more in summer; less in winter. Best fruits: apples, peaches, all berries, cherries, pomegranates, apricots. Best vegetables raw: celery, green peppers, sprouts, cucumbers.
8. Avoid tropical foods as much as possible, unless living in the tropics, including, tomatoes, oranges, avocado, eggplant, potatoes, yams, pineapple, etc.
9. Avoid all animal fats, eggs, high fat dairy, fried foods in grease, meat, soft drinks, sugars, white flour, white vinegar, hot spices, MSG, saccharine, coffee, commercial tea. Sweeteners such as: honey, maple syrup, barley malt, rice bran syrup can be used sparingly. Avoid canned, packaged and most restaurant foods.
10. Go outside after meals for proper digestion & assimilation. Oxygen is necessary for proper metabolism & absorption.
11. Daily Exercise: yoga, running, swimming, cycling, body building, breathing/stretching exercises & Chi Kung exercises.
12. These natural low fat dairy products can be used occasionally: Yogurt, buttermilk, cottage cheese (raw milk). Tofu can be used to supplement dairy products. Yang people should not use eggs and all others should use them sparingly.

The foods listed here, plus the health suggestions will nourish and vitalize your body. They will halt all cravings for junk food. A poorly nourished body is in a half-starved condition and needs many vital food elements: a half-starved body will cause deficiency diseases and result in the ubiquitous Junk Food Syndrome. May you eat in peace. We are creatures of habit. We succeed or we fail as we acquire good habits or bad ones; and we acquire good habits as easily as bad ones. Most people do not believe this. Only those who find out succeed in life.

Step VII: Let go of the Sick Energy to be transformed by the Earth

As you **repeat** the order, picture yourself removing the sick energy from the cells and discarding it down into the Earth to be transformed and recycled.



Fig. 4.31 *Sick Energy return to the Earth.*



Fig. 4.32 *See the Cells become Clean, Bright and Smiling.*

Fig. 8.2. If you smile, it smiles with you in return. If you frown, you will be frowned at. If you sing, you will be invited in joyous company. If you love the world you will be surrounded by loving friends, and nature will pour the treasures of the Tao.

Extreme Yin and Yang Foods and Poisons

Did you know that the average American diet is costing this nation over 30 billion dollars yearly in doctor bills? Americans are consuming 102 lbs. of refined white sugar, 53 lbs. of processed oils and fats, 100 lbs. of white flour, 7 lbs. of white rice, many gallons of alcohol & thousands of cigarettes per person annually.

Disease is on the rise. Hospitals are filled to capacity. Jails and mental institutions are over crowded. One of the main causes of these confusing problems can be attributed to very poor living and eating habits over decades, such as the consumption of processed and demineralized foods and poisonous substances (drugs, marijuana, coffee, sugar, alcohol).

List of Extreme Yin and Yang Foods and Poisons:

1. Meat, Fish and Fowl
2. Pasteurized Milk and its Products
3. White Flour and its Products
4. White Sugar and its Derivatives
5. Vegetable Oils, Animal Fat and Derivatives
6. Tobacco, Alcohol, Vinegar, Tea, Coffee, Sodas, & Cocoa
7. Processed Peanut Butter, Nut Butters, Ungerminated Seeds and Nuts, and Dried Fruit
8. Salt and Condiments
9. Marijuana
10. Commerical Eggs

Meat, Fish and Fowl (Extreme Yang Food):

Flesh foods affect the body. Meat contains urea (uric acid or the urine of the animal), creatinine, creatine and phenolic acids. They may contains synthetic female sex growth hormones (des); other chemicals pcb, mga, antibiotics, drugs, nitrates, nitrates and red dye coloring to preserve and make the otherwise cadaver grey flesh more pleasing to the eye at the bucher’s counter. These are all cancer causing agents. It is loaded with trichina worms, parasites and putrefactive bacteria. Pork contains 31,080, 000,000 putrefactive bacteria per ounce; steak and beef, 24,500,000,000; hamburger, 21,000, 000,000; sausage; 20,000,000,000 per ounce. Excessive flesh eating produces toxic metabolic wastes in the system causing toxemia, malnutrition, high-acidity, purine bodies, intestinal putrefaction, and contributes to the diseases of meat-eaters, such as cancer, kidney and liver disorders, arthritis, hardened arteries, mental disorders, bone and blood diseases and many others. Meat eaters generally age faster, have less endurance, develop more diseases, and have a lower life expectancy than vegetarians. The flesh of an animal is not food; it is the result of food plant life. All animal and human life is dependent upon the plant kingdom for its sustenance. Meat eating animals are not the strongest and longest lived animals in nature the elephant, rhino and gorilla (vegetarians) are the true kings of the jungle. Several years ago the government placed a ban on the use of growth hormone drug (des) fed to cattle to stimulate weight and growth. Some cattle owners have been taken to court for continuing to use the hormones. The cattle were losing too much weight and this became unprofitable to cattle owners. Growth drugs have been used for over 20 years as a cattle feed additive or injection to increase growth quickly, without using extra feed. There is a close link between these growth drugs to human cancer and other diseases. Over 300 cattlemen throughout the United States are still using growth hormones in their livestock. If they get caught and convicted, they could get a 3 year sentence and a $10,000 fine. The ban on growth hormones and the penalty if caught using them seem to have no effect on the law breakers. Profit is clearly more important than health or honesty. This is just another very good example and reason for you to consider alternative sources of nutriment, relatively free of hormones and poisonous substances, such as found in plant food.

Pasteurized Milk & Products (Extreme Yin or Yang/Acid Food): Drinking milk may be hazardous to your health. This statement appeared in the National Enquirer a few years ago, along with an excellent article explaining the menace of pasteurized milk. Some milk supplies have been found contaminated with penicillin and chloramphenicol, two antibiotics, which are supposed to be forbid-den by law. Among the ailments attributed to milk are: Pesticide poisoning, adverse drug reactions, drug resistance, salmonella, and staphylococcus poisoning, anemia, hypercalcemia (excess calcium in the blood), diarrhea, asthma and liver damage, plus insecticides, lethal drugs and radioactive material. If you are eating pasteurized cheeses, ice cream, sour cream, powdered milk, cottage cheese, cream cheese and anything made from the pasteurized milk, you are getting a dose of the above poisons.

Think about that the next time you go shopping in your local market Dr. Pottenger conducted another experiment on cats. He fed them pasteurized milk and in three generations they displayed homosexual tendencies and were unable to produce offspring. They developed brittle bones and lung diseases. Pasteurized milk and its products lack the necessary enzymes, vitamins and minerals so necessary to maintain health. Milk drinkers are always full of mucous, coughs, headaches, colds and flus. Pasteurization is for the purpose of keeping bad milk in a saleable condition and for no other purpose. Pasteurized cow milk products are primary factors in causing body cramps, allergies, arthritis, fatigue, indigestion, gas and diarrhea due to fat and lactose intolerance. Lower back pains can also be attributed to milk consumption. Most humans do not produce enough of the enzyme lactase, after the weaning period, which digests the milk-sugar, lactose which causes trouble. Cheeses and cow milk are extremely high in lactose and fat, both extreme yin elements and contributing factors in heart disease, high cholesterol, diabetes, colds, skin diseases and cancer. Cheese is so concentrated that it takes 5 quarts of milk to make one pound of cheese. There is more fat in regular cheese than in most meats. Scientists have discovered that pasteurized cow milk products remain unmetabolized in many adults because it lowers hydrochloric acid in the stomach, which is required for protein and mineral assimilation. Milk the intestines to generate excessive amounts of lubricating substance called mucous, to help keep foods moving through the system. This material has the ability to harden and forms a coating on the inner lining of the intestines that makes it almost impossible for nutrients to pass through into the blood stream, which of course means poor absorption. Poor absorption leads to chronic fatigue. An excessive build up of mucous travels up to the lungs, bronchial tubes, nasal cavity and head causing colds, flu, headaches, pneumonia and asthma. Cow's milk contains hormones which are secreted by the cow for the purpose of stimulating growth in a calf, to move its weight from about 80 pounds at birth to 1,000 pounds two years later you probably weighed about 7 pounds at birth and it took you a full 21 years to reach your present weight. Milk is an excellent source of calcium but many people just don't seem to be able to metabolize It properly. It may be because the pasteurization of milk destroys enzymes in milk, or the heat of pasteurization distorts the calcium. No one really knows, but laboratory animals raised on pasteurized milk exhibited all the symptoms of arthritis. Anyone who depends upon milk for his calcium is making a mistake. Low calcium intake can cause muscle cramps. Non-dairy sources of good quality calcium can be found in sesame seeds, cabbage, okra, parsley, watercress, wheat, kale, cauliflower, lemons, straw-berries and collards. Pasteurization totally changes protein molecules in milk making it difficult to digest and assimilate. The body cannot utilize 42% of the protein contained in pasteurized milk according to Dr. S. C. Deal in his book “New Life Through Nutrition,” 1974). High fat dairy foods, i.e., butter, processed cheeses, sour cream, cream cheese, and regular raw and pasteurized cheeses (cheddar, muenster, edam) are all extremely Yin, and should be eaten very sparingly. Low fat yogurt, buttermilk, and skim milk are more Yin and Yang balanced, and can be consumed in moderation. Low fat skim milk cheese, swiss cheese, low fat cottage cheese, and highly salted cheeses are extremely Yang due to their fat-free concentrated protein and high salt (Yang) content, and should be eaten very sparingly. Goat milk, goat cheese or feta cheese are Yang.

White Flour and Products (Yang/Acid Poison):
White flour and its derivatives affect the body. White flour products, such as white bread, noodles, pizza, etc., are considered Yang and are the main cause of Yang of constrictive constipation. The stools are dry, small and hard and bowel elimination is difficult. It contains a calcium sulfate, a chemical name for Plaster of Paris it will plaster-up, clog and close-up the eliminative channels of the body if continually indulged in. Intestinal statis or constipation causes anemia and pasty complexion, which can be attributed to white flour products. It is totally lacking in the entire vitamin B-complex family. It also depletes these vitamins from the body if eaten exclusively. It contains zero roughage or bulk, which is necessary for healthy digestion and proper intestinal and bowel action. They add empty calories and unhealthy weight to the body. White flour products maintain long shelf life, due to their lack of whole food value. Whole grain flour products cannot keep long because of their freshness and high nutrition. Bugs and insects will not eat white flour due to its lack of nutritional qualities. The wheat bran and wheat germ are fed to livestock for health and prize-winning reasons, while the farmers poison themselves unwittingly. These show animals are healthier than most humans.

The bread millers remove all of the vitamins, minerals, protein, bulk elements out of the wheat and enrich it with a tiny amount of synthetic vitamins and minerals, which cannot be absorbed by the body. This goes for all supermarket products, such as macaroni, gravies, spaghetti, etc. Twenty-six natural elements are removed from the flour, and a fraction of a penny's worth of inorganic vitamin/mineral elements are added back. White rice has the bran removed, which contains the valuable B-complex vitamins. It is constipating and does not promote health. It contains some or all of the following inorganic chemicals and unwholesome substances: plaster of Paris, polysorbate 60, calcium bromate, azodicarbonamide, sodium stearoyl-2-lactylate, amomonium phosphate, carrageenin, propylene glycol, diacetyl tartaric acid, monoglycerides and diglycerides and synthetic vitamins. Propyleneglycol is used in antifreeze; carragennin is a possible cancer causing agent; be suspicious of the other chemicals also.

All soft, fluffy supermarket bread is puffed with air in big vats, to blow it up for shelf life. If bread can be squeezed like an accordian it is not fit for human consumption. Supermarket cereals are made from white flour, with added, salt, sugar, BHA, BHT, artificial additives, pyridoxine hydrochloride, colorings, cotton seed oil, hydrogenated oils and preservatives. Cheap cereals contain as much as 70% to 85% refined sugar and white flour starch. Cheap hydrogenated coconut oils and salt come next as chief ingredients in cereals; artificial colorings are also high on the list. Cereal was named after the Roman goddess of grains, Ceres. The real cereals are whole grains: rye, rice, wheat, corn, barley, buckwheat, oats, millet etc. Whole grains are not fattening; legumes are not fattening; fruit, vegetables and low fat dairy are not fattening. Whole fiber foods cause one to eat less and to move the stomach and bowel contents along, thus aiding weight loss. White flour is devoid of nourishing elements, fiber bulk which will make you fat. You can make your own whole grain flour products and avoid obesity, disease and a thin wallet. White flour products do not fill you up, therefore you can keep on eating them, while chalking up the calories and fat. Over $2 billion dollars are poured, yearly, into advertising white flour products by large companies. Avoid all products containing white flour, sugar, additives etc. Use only 100% whole grain products. Avoid canned, bottled or frozen food and drinks (the sugared or salted variety), such as salad dressings, ketchup, tomato and other sauces, crackers, chips etc.

Consume foods made from whole grains, fresh vegetables, fruits, seeds, nuts, rice, melons, pure unsweetened fruit or vegetable juice, popcorn, grain cookies, honey oatmeal cookies. Make your own pasta and noodles with a pasta machine. Make your own tofu or yogurt salad dressing. In the long run, whole foods natural cooking can save you loads of money, prevent disease, increase your health force and most importantly, save your life.

White Sugar and Derivatives (Yin/Acid Poison):
Sugar, its derivatives and other unnatural sweeteners and food additives affect the body. It is an extreme-Yin substance, and psychologically and physically addicting. It contains zero minerals, vitamins, enzymes, protein, natural fiber, trace minerals and other food value. It contains empty calories, and can make one obese and lethargic. It uses up insulin and causes diabetes, obesity, heart disease, poor eyesight, skin diseases, bad memory, cancer, kidney and liver disorders. It places a drain on the alkaline buffer salts and causes calcium to be depleted from bones, teeth, hair, nails, eyes, causing tooth decay, soft nails, blindness, bone disease and hair loss. It robs the body of iron, the major blood-building mineral. Sugar is a main ingredient in most processed foods: ice cream, 30%-50%; white bread, 10%; commercial cereals, 40%-50%; peanut butter, mayonnaise, salad dressing, ketchup, 20%-30%, non-dairy coffee creamer, 30%-40%; imitation fruit juice, 98%; gelatin desserts, 85%; cigarettes, 50%; cigars, 20%;, pipe tobacco, 40%, canned fruits, 20%-35%; candy, 30%-50%; baby food and infant formulas, 20%-30%; spaghetti sauce, 10-20%; colas and soft drink sodas, 40-60%; hot dogs, 10%; cookies, cakes, pies, donuts, etc., 30%-50%. Sugar in any form is harmful. Read labels. Any of the following is just another name for sugar: sucrose, fructose, glucose, maltose, lactose, galactose, cane syrup, corn syrup, corn sugar, invert sugar, dextrose, saccharin (coal tar product), cyclamates etc. Most fast-foods contain high percentages of both sugar (Yin) and salt (Yang). Sugar is sold to the tune of 32 billion pounds and $6.4 billion per year. Dental bills cost Americans $6 billion a year. Isolated societies and rural cultures worldwide, who do not consume sugar and its derivatives are free from tooth decay. Excess sugar in the blood can result in brain damage, schizophrenic tendencies, depression and extreme mood changes. Sugar consumption is now up to approximately 200 pounds per person per year.

The death rate from diabetes has also increased 52% in 70 years. As sugar intake increases, degenerative diseases also increase. Refined sugar, fats and empty calorie carbohydrates exhaust the pancreas, which results in diabetes. Diabetes, hypoglycemia, skin diseases etc., are all unknown in societies who do not consume sugar and refined foods. Diabetes and hypoglycemia can be controlled and prevented on a sugar-free and junk food-free diet. The diet must contain whole grains, legumes, vegetables, fruits, seeds, nuts, low-fat dairy. Brown sugar is white sugar colored with molasses, and it reacts exactly the same in the body. Honey, rice bran syrup, molasses, barley malt syrup, dried powdered dates, carob powder, malt powder, etc., are all natural sweeteners and substitutes for all forms of white sugar and its derivatives. However, these substitutes should be used very sparingly and in small quantities in cooking or flavoring food. All sweet foods and substances are extremely Yin (expansive to mind and body) and can cause disease if used indiscriminately). Intestinal mucous is usually simply an extension of mucous of the stomach, and is always aggravated and instigated by the use of white sugar and other similar irritants. Chronic diarrhea is often the result of the free use of sugar in its various forms, causing intestinal (Yin) expansion and loose stools. Dilation or distention of the stomach, with enormous quantities of gas and fermentation can be attributed to sweets and sugar. Gastric ulcers can be caused and greatly aggravated by sugar products. The stomach requires a good calcium supply to function properly; sugar causes rapid calcium loss. Gout, chronic rheumatism, nervous headache, neurasthenia, eczema, apoplexy, leukemia, ms, tb, md, and other chronic diseases require entire abstinence from white sugar and its derivatives, if there is any chance or hope of a healthy recovery. White sugar is not digested in the mouth or stomach, but only in the small intestine, where it comes in contact with the intestinal juice. Several hours pass after eating a meal before the intestinal fluid is able to digest white sugar and prepare it for absorption. This is not true, however, of fruit or other natural sugars. It is evident that cane sugar is a crude vegetable product not well adapted to human nutrition. Stomach acidity, catarrh, indigestion, gas, ulcers and hyperacidity in many cases are due to this cause. The extensive use of candies, preserves, sodas, sweets of various kinds, as well as the free use of white sugar, corn syrup, etc., with cereals, pancakes, in coffee, tea, and in other ways, may be directly held responsible as the one cause of indigestion and chronic disease which prevails throughout the civilized world. Millions of men, women and children are suffering from disordered conditions of the body due to the excessive use of white sugar without being aware of the real cause of their distresses. Not a few intelligent, observing people have discovered that sugar is productive of sour stomach and various other gastric disturbances. It is evident, then, that white sugar and its derivatives are totally devoid of properties which are found in wholesome natural foodstuffs. No healthy human being can suffer physical ills from consuming whole grains, legumes, fruit, seeds, yogurt or vegetables because these foods are natural to the human digestive process. Up to 90 percent of our supermarket food is loaded with chemicals, dyes, sugars, salt, colorings, additives, and preservatives. Their sole purpose is to give taste, prevent spoilage and impart bright colors for eye appeal and saleability. Most packaged supermarket goods fall into the category of yin substances (expansive qualities) which tend to produce specific and systemic biochemical and hormonal imbalances. Sugar and salt are sold to the tune of 15 million pounds each per year; corn syrup, 6V& billion pounds; sodium bicarbonate, 60 million pounds; monosodium glutamate, 30 million pounds and monosodium diglycerides, 90 million pounds. There is now about 2000 different chemicals used in foods for various reasons. It is amazing that the human being can survive at all.

They strongly urge and recommend that people drastically reduce their salt intake for young and old alike. Americans, they say, should eat less meat, whole milk products and eggs which are rich in cholesterol. The study states that people get 24% of their daily calories from refined sugar and 40% from fats. This is extremely high and the committee recommends that people eat less of these high calorie foods and more of the complex carbohydrates, that are the natural ingredients of fruits, vegetables and whole grains. In fact, as much as 45% of what people eat should be starch, and the fats they eat should be primarily unsatured (of vegetable origin), the study says. Although the report urges people to substitute more fish and poultry for meat, we recommend that seeds, nuts, raw goat milk products, soya protein, grains, beans and nutritional yeast can completely take the place of all meat; including fish and poultry.

With the adoption of proper nutrition and eating habits, the study estimates that most major diseases could be reduced up to 50%, including overweight problems. Our research reveals that the healthy, vibrant and disease-free centenarians from around the world prove that disease can be nonexistent.

Vegetable Oils, Animal Fat & Derivatives (Extreme Yin/Acid): Vegetable oils, animal fats and their derivatives affect the body. Fats are used as fuel in the body. The amount of fat required daily is quite small. The body's preference is to store up fat for use in emer-gency. It is deposited under the skin between the layers of muscles and serves as a padding around the internal vital organs; it is used to nourish the nerves also. Fats are converted into soap in the intestines by the action of the digestive fluids. Soap is soluble in water and in this form the fat is absorbed after the soap is decomposed and the original fat is reconstructed. Kidney and gall stones are nothing more than hard round soap balls, developed in the system from an excessive consumption of fatty foods and oils. The less oils and fats in your diet, the healthier you will be there is no secret about this. Bottled oils Even vegetable oils will cause liver and bladder trouble if eaten to excess. Why is this so? Because all oils, from either vegetable or animal sources, are super concentrated food derivatives of which the human body was never designed to handle. For example, several pounds of nuts are required to manufacture one small bottle of nut oil it is the same with all other oils the whole food factor has been removed from the original product, (fractionated) and we are left with a highly concentrated food substance, which the human chemistry system and internal organs are burdened beyond their capacity to deal with. Result: malnutrition, indigestion, chronic fatigue, liver and bladder disease, anemia, falling hair, malabsorption of food, poor eyesight, and ultimately, cancer. The body was designed to handle foods in their whole form, with oils intact, such as found in all seeds, nuts, legumes, beans, grains, olives, cultured dairy products etc. In this manner, we can be assured of obtaining the whole food factor in the right combination and proper proportion. Remember: no more than one to two tablespoons of free oils or other fats daily. One famous health writer and researcher has discovered that any consumption of free-fats as found in vegetable oils or other animal fats, which have been fractionated and placed in bottles, is deleterious to one's health. So again, heed the warning: The less free-

Step VIII: Fill the Water with Compassion

Hold the cup with both hands near the heart and project goodness into the water. **Command 4:** ***"This sacred water will give me/you health, wealth and longevity."***

Project love, joy, thankfulness, gratefulness, appreciation and the energy of compassion into the cup.



Fig. 4.33 *"This Sacred Water will give you health, wealth and longevity."*

Step IX: Drink the Sacred Water

The Sacred Water will carry the message to all the cells. It will keep the message of the Sacred Water practice in all the cells. Use both hands to pass the Sacred Water to the student you are working with, or drink it yourself and/or in unison with your group. **Feel the water go into all the cells of your body. Feel it removing the sick cells and purifying your body.**

You can also sprinkle it on to any area that requires healing.



Fig. 4.34 *Drink the Sacred Water.*

oils in your diet, the healthier and longer you will live. Animals in nature do not consume such things it is common sense that we should follow that line of logic also. Cold pressed vegetable oils should be used mostly in cold weather (winter), and very sparingly in summer. The body requires a very small percentage of fats in the daily diet these can be acquired mostly from whole natural foods, without injuring one's health. Most Americans consume from 50% to 60% fat daily, which is why we have the highest death rate from heart disease in the world. With the excessive consumption of animal protein, sugar, salt and fat, it is easy to see why the United States is one of the most chronically diseased countries on earth. Most people consume over 2000 calories in fat per day. Overconsuming fatty foods and oils does not give the body an opportunity to manufacture its own fat as is the case when only small quantities are eaten. The human body is an amazing work of art, and it can do many things on its own if we feed and take care of it properly.

One ounce of fat contains 240 calories more calories than the same amount of carbohydrates or protein. The excessive use of oils or fats creates chronic digestive disorders, takes several hours to digest, and leads to a multitude of illnesses. Left to its own, the body will form its required fat from natural complex carbohydrate foods, i.e., whole grains, legumes, seeds, nuts, fruits, and vegetables. The fat formed in this way is different from other fats because it contains the special characteristics of human fat, which was specifically designed by nature for the human body. Expensive margarines are an extremely Yin and inferior product. Margarines made from soybean or other oils are all hydrogenated and artificially flavored and colored. For example, soybean oil is heated to high temperatures, and hydrogen gas is bubbled through it, which causes the liquid oil/fat to become solid and made into bars of commercial brightly packed margarine. This hydrogenation process does two things to the unsaturated oil: 1) it makes it hard; 2} it changes polyunsaturated fats into saturated fats, which are more chloresterol forming than butter or eggs. Avoid all margarines, including corn, safflower, soybean and any other ones made from cheap oils. Use yogurt, tofu, natural cooking herbs, miso, etc., to make your own fresh toppings and salad dressings. They are all fast, easy to make, inexpensive, and will save you doctor bills.

Metallic nickel is also used in the process of turning unsaturated liquid vegetable oils into a hard stick of phoney imitation butter. Free nickel in the system can cause ill-health. Imitation margarines will raise your cholesterol, not lower it it will clog-up your organs and arteries, not clear them out. Coconut oil, animal fats, lard and butter are all highly saturated fats 100% fat. Coconut oil is the most saturated of all fats butter, lard, and animal fat comes next. Coconut oil is added to almost all processed foods, including imitation baby milk it is also used to make soap. Cottonseed oil is another highly processed, non-nutritive product used in many commercial foods, including potato chips, candy, pastries, ice cream, etc. This harmful oil has been reported to lower the sperm count in the testicles of male animals. In simple terms: cottonseed oil will lower your sex drive, reproductive powers and cause impotence. Palm oil is usually found in the same products as cottonseed oil. Read labels, even the ones in health food stores, and avoid these disease producing poisons.

The best polyunsaturated vegetable oils, if one must use them are: cold-pressed virgin safflower oil, dark sesame oil and olive oil. Safflower oil contains the highest amount of linoleic acid (75%) which is the most polyunsaturated oil of all. The lower the linoleic acid content, the more saturated a fat or oil is. Deep fried foods in oils, especially rancid, cheap commercial oils can cause severe organic health disorders. Vegetables sauteed in a small amount of pure dark sesame oil or safflower oil is permissible during the cold winter months. Use less oil in summer.

Tobacco/Alcohol/Vinegar, Tea/Coffee/Sodas (Yin/Acid Poisons): These poisons affect the body. Tobacco dulls the finer senses and severely weakens the pineal and pituitary glands, the very receptors of higher values and intuition. There are 19 poisons in cigarettes, i.e., nicotine, arsenic, methene, etc. Smokers are known to take on Buerger’s disease which lowers skin temperature and causes gangrene. Smoking pregnant women can easily pass on the habit to their offspring. In many cases, the children of smoking mothers are sick from birth. Smoking is a contributing factor in all cases of heart disease and circulatory disorders. It lowers the red blood count and causes anemia. Heavy smokers do not generally have a taste for natural foods everything they eat is heavily sugared, salted or spiced, which further imbalances the system. Stomach ulcers are greater in smokers than non-smokers.

Smokers generally appear 10 to 15 years older than their actual age. The heavy tar substances in cigars or cigarettes adhere to the lung walls, coating them thick and black, and obstructing the oxygen and blood exchange within the lungs. It cripples the brain cells, causing them to harden, thicken and finally lose their finer nerve tissue. Brain cells do not regenerate or grow back when destroyed through smoking or other nerve poisons.



Normal Brain Cell **Tobacco-Crippled Brain Cell**

Fig. 8.3. Tobacco affects the Brain.

The nausea and sickness following the first attempt to use tobacco is definite evidence of the poisonous character of this drug. Vertigo, pallor, high pulse rate, pounding heart beat, breathing difficulty, vomiting, and in extreme cases unconsciousness are produced by a very small quantity of tobacco smoke in persons not accustomed to its use. Almost no one dies of nicotine poisoning when first smoking, because the human system possesses great powers of accommodation to circumstances. In this way tne worst poisons may by degrees be tolerated until enormous doses can be taken without immediate fatal results. However, the system is still slowly poisoned, and remains in a lowered state of health, until the smoker suffers and dies 10 to 20 years or more before his natural life span. A single cigar or several cigarettes will, in thirty minutes, produce a rise of blood-pressure amounting to twenty points. One pound of tobacco contains 350 grains of nicotine. One-thirtieth of a grain causes toxic symptoms in man. One drop kills a dog. Nine-tenths of a grain will kill a man. One pound of tobacco, then, contains more than enough to kill three hundred people.

When smoking is stopped, it takes about a month to get the nicotine out of the body. It takes several months to a few years to completely clean out the lungs and internal systems, provided a wholesome dietary and exercise program is adopted.

Alcohol and Vinegar:

These products are proroplasmic poisons. Vinegar is extremely acid and harmful to the stomach, kidneys and liver. They destroy red blood cells and lessen the functioning power of the brain. Alcohol over stimulates the brain and body, leaving the drinker fatigued and washed out after its effects have worn off. It eats away the stomach lining, leading to ulcers and cancer. It expands the liver and kidneys, causing chronic disease symptoms. Alcohol is a narcotic, which impairs one's intelligence, weakens the memory, judgment and the reasoning faculty. It lessens endurance and the power to resist disease. Healthy blood corpuscles help to prevent disease; a pint of alcohol puts 20% of our blood cells out of commission. The craving for alcohol, in many cases, can be traced to poor nutritional habits and deficiencies, lack of exercise and fresh air and stress. Alcohol is extremely Yin, and heavy drinkers generally crave much meat (Yang). Any extreme always creates a craving for its opposite. A healthy, well functioning liver will feel the effect of even one drink. Heavy drinkers do not feel the effects after a few drinks because their liver has become diseased and unable to react to any further poisoning. It produces a profuse flow of mucous in the stomach, the purpose of which is to protect the mucous membrane from the irritating effects of the alcohol. It hinders the formation and accumulation of glycogen in the liver, thus lessening resistance to infection. Alcohol diminishes muscular vigor, nerve sensibility, vital endurance, and has a retarding effect upon digestion. It causes depression and mental degeneracy. It hinders the formation and the action of the gastric ferments, in as little as one part to 250 of water, ½ of 1 %.

Alcohol always diminishes, never increases the energy of the heart, and is detrimental rather than beneficial in cases of shock, collapse, fainting, etc. It increases the liability to infectious disease, and prevents the development of immunity. It diminishes the alkalinity of the blood, and so diminishes vital resistance and increases susceptibility to disease.

Tea, Coffee, Sodas and Cocoa:

Coffee and commercial tea are artificial mild narcotic stimulants, and are definitely addicting and habit forming when continually used. They are extremely Yin and Acid-forming in the body, containing poisonous substances that narcotize the brain, nerves and blood. They excite the nervous system temporarily, followed by physical and mental let-down, fatigue and depression. Strong cravings for these substances are definite indications that they contain mild narcotic poison-stimulants, which create a dependency-addiction syndrome, and withdrawal symptoms when they are abruptly taken away from the user. They cause transitory stimulation, followed by marked increase of fatigue. Commercial tea contains tannic acid; it inter-feres with gastric juice in the stomach. All of these Yin poisons expand and weaken the kidneys, bladder, liver and intestines, etc., causing their acids to flow into the blood, poisoning the system. Many tea and coffee drinkers develop discoloration of their teeth and skin. Coffee contains pyramidine, a smoke poison produced by the roasting process. Caffein's effects on the nerves cause wakefulness, nervousness, excitability, insomnia and muscle twitching. It raises the blood pressure. Eight ounces of coffee contains 85 to 90 mg. of caffeine; colas about 75 mg. of caffeine.

Colas and soft drinks contain 7 to 8 teaspoons of white sugar per bottle (about an ounce). Other orange or lemon flavored imitation drinks contain brominated vegetable oil, corn and cottonseed oil, and the poisonous chemical bromine. All colas and soft drinks eat away at the vital organs, including the reproductive glands. Colas were also known to contain small amounts of cocaine. Cocoa contains a mild narcotic called theobromin, equal chemically and pharmacologically to caffein in tea and coffee and its effects on the body are the same. It should not be difficult in the light of these facts, for any intelligent person to reach the conclusion that these poisonous stimulants do not build health or instill vitality within the body they only waste vital energy, exhaust the body's reserve force, and lower immunity and resistance to disease. Rest and sleep are the only natural and healthful remedies for fatigue. Addiction to these dele-terious substances confuses and dulls the body's natural signals for rest and sleep, thereby re-sulting in nerve exhaustion, nervous disorders and mental confusion. If you value your personal well-being, and are interested in building your vital health force, avoid these artificial stimulant/ poisons like you would arsenic capsules.

Processed Nut Butter & Ungerminated Seeds/Nuts (Extreme Yin/Acid Food):

Nut butters and dried seeds and nuts affect the body. Commercial peanut butter contains, salt, sugar, cheap hydrogenated oils, about 80% fat, and nickel which can cause lung infections. All nut butters and nuts are extreme Yin due to their high fat content. These products should be used sparingly. Excessive fats expand the liver and decrease normal bile functioning. A diseased liver causes poor eyesight, jaundiced eyes, dandruff and falling hair, skin diseases and other maladies. Unsoaked or ungerminated seeds and nuts are only about 10 to 20 percent digestible and assimilable, due to the fact that their life force is lying dormant the life force becomes active only when moisture (liquid) is added to them. They then become active and start growing or germinating: only then will they become almost 100% digestible and assimilable in the human system. Dried seeds and nuts can cause severe digestive disorders. The following seeds and nuts can be soaked overnight in water: sunflower seeds, pumpkin seeds, sesame seeds, pumpkin, almonds, walnuts, pecans, etc. After soaking, they can be placed in a blender with some added apple or pineapple juice and you can enjoy a zesty seed or nut milk. Soaked cashews also make a delicious cashew milk, creamy and good tasting. Soaking and blending seeds and nuts makes their protein value more easily digestible. Two to three ounces of a single seed or nut, or in any combination will add variety to the seed milk. You may also soak a couple dried figs or apricots with the seeds, and blend them together; add one-half teaspoon of licorice powder to moving blender for pleasant taste. Use this seed/nut blended mixture more during hot weather, two or three times per week.

Dried Fruit:

These include dried apricots, raisins, apples, pineapples, figs, peaches etc. All dried fruit should be soaked at least 10 to 12 hours before eating. It takes about 9 or 10 hours to properly digest dried fruit. They will cause intestinal gas before being acted upon by the digestive juices. The natural fruit liquid has been removed from dried fruit, which turns them into a very concentrated sugar. They almost always cause skin eruptions when eaten dried, or if eaten excessively, soaked. You may eat them mostly during cold weather when fresh fruit is not available, and very sparingly no more than 1 or 2 apricots or figs, or a teaspoon of raisins per day maximum.

Being difficult to digest and assimilate in dried form, they pass out of the body before being properly and adequately absorbed. All dried fruit is extremely Yin and Acid, and is the cause of much distress and ill-health among dieters today, who use them excessively. Dried fruit should not be used as staples in the diet, but only occasionally, and mostly in cold weather as a supplement to the diet. Dried fruit may also be boiled in water for a few minutes, and let stand overnight. Soaked dried fruit can be used in bread and other baked dishes.

Soaking dried fruit and seed and nut germination has been one of the most important health secrets that we have investigated and researched in the health field. When on a vegetarian or health diet, do not become a health-nut and attempt to live on dried nuts and fruit, as some have attempted to do with disastrous results in poor health. The practice of seed and nut germination has been a regular practice of the ancient Yogis, Chinese Taoists, and other long lived people throughout the world for centuries. Make it your practice too, and experience the vibrant health force that you are capable of attaining.

Salt and Condiments (Yang/Alkaline, Poison in Extreme): Salt and condiments affect the body. Salt is composed of the caustic alkali, sodium, and a poisonous gas, chlorine. Common table salt is an inorganic compound which cannot be assimilated by the system. It has no nutritional value because it cannot be dissolved and utilized by the cells and tissues. We need about 200 milligrams per day for optimum health from sea salt or kelp. The average person who eats processed commercial food, consumes more than 2000 milligrams of cheap salt. Excessive consumption of salt will cause high blood pressure, hypertension, kidney disease (Yang) hardened arteries, eye disorders, unbalanced chemistry etc. It also depletes calcium from bones and teeth, and irritates the mucous lining of the stomach and intestinal tract; it affects the nervous system causing nerve disorders and irritability. Today, our lands are demineralized and chemically fertilized, plus the top soil is very poor due to bad agriculture methods, thus washing away of the more soluble sodium salts, leaving it high in potassium. The result of this sodium loss led to the use of a deadly substitute sodium chloride, or common table salt. Biologists have shown that a half ounce of salt absorbs and holds four pounds of water in the body, thus leading to edema and obesity. It draws the vital fluids from cells, tissues, glands and organs causing them to atrophy or dry up. It degenerates the lymphatic and endocrine systems. The thymus is known to be very sensitive to salt rapid aging accompanies the deterioration of the thymus gland.

In China, salt in a saturated solution has been used as a means of suicide. Poor capillary circulation, hot or cold hands and feet, anemia, dizziness, headaches, nose bleeds and sexual hyperesthesia are all symptoms of excessive salt in the system. The only salt that the body can actually use is the organic salts formed from air, water, soil, and solar energy into plant life. From the plant, man can digest, assimilate and fully utilize the organic salts. Inorganic table salt destroys the electrochemical balance between the natural combination of organic salts in the body the sixteen mineral elements. We require more than just one mineral salt we need all of them in the right combinations potassium, silicon, calcium, iron, lime, chlorine, etc. Common salt is not an organic salt, and therefore, causes an imbalance of the sodium/potassium elements that make up cell life. Sodium is found in the fluids of the body, and potassium exists mainly within the cell. Salt, including all restaurant and most processed foods, smothers or crowds potassium out of the cell, where it rightly belongs, and the inorganic table salt overloads the cell, causing local irritation, Yang inflammations, hypertension etc. African natives do not use salt, and the Eskimos, not only do not use salt, but abhor its taste. Animals will eat salt only when there is no fresh green grass and herbs to eat. They shun the salt-lick during summer months. Salt eating is a habit, just like tobacco, alcohol, coffee or drugs. It hinders the digestion of albumen, by interfering with the secretion of gastric juice. Gout is aggravated by the use of salt, and attacks of gouty pain subside when salt is stopped. Eczema, skin diseases and dropsy, along with swellings, are directly attributed to salt eating.

Overeating has become a universal habit. The use of salt and salted foods, plus the use of other table condiments, such as monosodium glutamate (MSG) and black pepper, are largely responsible for the desire to overeat, especially of devitalized foods. Salt deadens the sensitive tastebuds on the tongue. Regular salt eaters generally have no desire to eat fresh raw foods because they have lost the finer sensitive nerves of taste on the tongue. The more salt one eats, the more he will crave junk food, and the less he will desire fresh wholesome poison-free food.

Salt removes water from blood and lymph which is needed for its excretion by the kidneys. This causes abnormal thirst, only satisfied by copious drinking of water, alcohol, sodas etc. Heavy salt eaters are generally also heavy meat eaters and drinkers. This person requires plenty of liquids to quench his thirst and to dilute the poisonous salt. In the long run, the internal organs become diseased and malfunction at an early age. Salt is also used in meat products to preserve and mask the taste and appearance of the dead, decaying and decomposing flesh. Ancient civilizations used salt to preserve and embalm the mummified bodies of their dead royalty. It is ironic, and rather sad that today, we are preserving and mummifying living bodies in early preparation for burial.

Here is a list of foods that are commonly eaten by millions of people, containing large quantities of salt and other unmentionables: All cheeses, except the low-sodium variety; commercial bread; processed boxed cereals; ketchup, sauces, and spreads; frozen dinners; salad dressings; cottage cheese; margarine and butter, except unsalted butter; cakes, cookies, pies, candy; dried soups in envelopes, canned soups, vegetable, beans etc.; The list goes on and on. Read labels and buy only salt free food.

Commercial salt contains the following chemicals: silicon dioxide (common sand), aluminum calcium silicate, tricalcium silicate, sodium calcium aluminosilicate, sodium aluminosilicate, calcium silicate, magnesium silicate, yellow prussiate of soda and sodium ferrocyanide. Do you agree that commercial salt should be labeled with skull and cross bones.

For your improved health use the following salt substitutes: Powdered kelp, Dr. Bronner's Balanced-Mineral Salt, Vegetable (dried powder) seasonings, miso (from soybean), soy sauce (from health store), sea salt etc. Awareness is the key; be aware of what you buy from food stores. Read labels. Ask questions. Think. Think. Think. It requires little effort to cease the consumption of junk food when a sound nutritional program is adopted. Cravings for unwholesome foods and poisons are always a sign of malnutrition, poor eating habits, bad digestion and assimilation which are the effects of lack of knowledge and misapplication of universal and natural health laws.

Marijuana (Extreme Yin Poison-20 times more Yin than Sugar): You can only shake your head in wonder every time an educated person says marijuana is harmless, or repeats the comment that there is no scientific evidence that marijuana is dangerous. In the 13th century All al-Hariri reported the dangers of marijuana smoking. Warnings kept cropping up over the next 600 years and in 1893 the Indian Hemp Drugs Commission urged great caution. In 1924, the League of Nations unanimously classed marijuana as a dangerous drug. And it remained a dangerous drug until the early 1960's when 'due to a lack of solid evidence' researchers decided that marijuana was harmless. The evidence was there, it was just being ignored. A few tried to get their anti-marijuana views before the public and were hooted down. Others conducted research and published the results in obscure medical journals rather than face the public ridicule that an anti-marijuana stance brought. Finally, in 1974, the Senate Judiciary Committee conducted hearings on the marijuana epidemic and anti-marijuana research was made public. The collective testimony of 20 of the world's leading medical researchers unquestionably revealed that:

1. THC (intoxicating chemical in marijuana) tends to accumulate in the brain, glands, and fatty tissues.
2. Marijuana causes massive damage to entire cellular process.
3. Smoking marijuana causes irreversible brain damage.
4. There is danger of genetic damage from marijuana use.
5. Chronic smoking (three joints or pipeful per week) produces lung damage in six months that would take 20 years of heavy smoking of normal cigarettes to equal.
6. Marijuana and tobacco smoke are far more damaging to lung tissue than either by itself.
7. Prolonged use results in emotional problems.

These opinions were not the result of a single, isolated study as the nation's media reported and implied. Instead they were compiled after the study of many, many research projects. Nor were the studies conducted by unknowns trying to make a name for themselves. Dr. Julius Axelrod, a Nobel prize winner for his study of drugs and the brain said, marijuana causes an irreversible damage to the brain. Dr. Phillip Ze in ben berg, senior research psychiatrist at New York State Psychiatric Institute, said, chronic marijuana smoking causes bronchitis, diminished lung capacity and changes in lung tissue. He went on to say that it was very much more dangerous than first expected.

G. Empty and Fill

Ask for permission to work on the student by communicating with their personal star. Point your sword hand down to the ground. Project your hand ‘very big and very long’ and your feet ‘very big and very long’ - extended down to the ground. Now very slowly inhale, bring up the earth energy. An important part of the practice is to extend a ‘line’ down from universe into yourself and one into the student. The line sinks through the Tan Tien into the universe below. You can send your energy up to your energy body and it will be brought down to the energy body of the other person.



Fig. 4.35 *Feel your hands are long as down into the earth they extend.*



Fig. 4.36 *Project the other person’s legs deep into the earth.*



Fig. 4.37 *Blend the universal energy and Earth Chi - bring it into all of the bones and cells.*

Dr. Harvey Powelson, a research psychiatrist at the University of California, Berkeley, was highly praised for his pro-marijuana stand in 1964. He was attacked in the press and in person when he changed his views. Opposition to the decriminalization of marijuana laws was unanimous. The committee was opposed and the witnesses were opposed. Facts supported their decision and logic refuted every pro-marijuana argument. The main reason was the conclusion that marijuana can cause death. This view may *be* shocking but scientific evidence proves that the dangers of death are great because marijuana increases:

1. The heart beat and blood pressure, enhancing the danger of a stroke.
2. Blood pressure and fainting, which could come while working or driving a car there is no advance warning,
3. The potency of barbituates, thus a non-lethal dose could be turned Into a lethal dose without the know-ledge of the barbituate user.

Those are the hard facts. Medical evidence also revealed dangers of chromosome damage, sexual impotence, and emotional changes, all of which the marijuana user may not be aware of until it is too late. Dr. Powelson's views changed as his psychiatric study deepened. He found that marijuana disrupts the thinking process and that memory and time become distorted. Brain damage to chronic users is permanent said Dr. Powelson. He said that three years of chronic smoking left one with a brain damage equal to 10 years of heavy drinking.

The effect of cannabis (marijuana): It is subtle and insidious, but harmful reactions in the heart and circula-tory system are suspected, and there are indications of adverse reaction in the body's anti-infection chemistry, said Dr. Henry Brill, regional director of the New York State Department of Mental Hygiene. While no one suggested that all marijuana users will move on to heroin, it was brought out, and unchallenged by the pro-marijuana groups, that 'the greater use of pot, the greater use of other drugs and that marijuana is the universal threshold drug through which young people make their entry Into the drug culture. But the biggest reason for opposing marijuana, both the use and sale, was brough out by Dr. Hardirt B. Jones, perhaps the world's most respected authority on drugs and drug abuse. Dr. Jones is professor of medical physics, professor of physiology, and assistant director of the

Donner Labora-tory at the University of California at Berekeley. He has taught drug abuse courses and interviewed over 1,600 drug users. Jones' findings, after many years of research, show that marijuana use kills cells in the area of the brain necessary for the awareness of pleasure the very part of the brain that allows the full awareness of the joys of being alive. There is perhaps no greater hell, said Dr. Jones, even with pain, than not to be able to feel alive. Those who are not able to feel alive will ever seek pain to get relief from their remorse. And that is the hell that is projected for those who use cannabis. The medical evidence filled 400 pages in the record of the hearings. This summarizes only a tiny bit. Marijuana also decreases the sperm count and volume in males, from ages 18 to 28; blood plasma is reduced 50% below normal.

Commerical Eggs:

Eggs may be used by those on transition diets stemming from the use of flesh foods, or by extrememly rundown and protein deficient individuals. Eggs contain complete proteins of high biological value, but the white of an egg, when taken to excess, is capable of producing intestinal putrefaction to a great degree. Non-fertile, unhygenic commercial eggs, increase stomach putrefaction to an ever greater degree. Many people are very sensitive to egg albumen and suffer symptoms of toxic poisoning, causing nausea, vomiting and diarrhea. The free use of eggs, especially of the white of egg, is found to be injurious in many cases of Bright's disease. Eggs encourage the growth in the colon of germs of putrefaction, which have been proved to be the cause of membranous colitis and of appendicitis. The regular and excessive intake of eggs, overworks the liver, causes gas, constipation and an over supply of albuminous matter in the body.

It can be seen then, that eggs, as a class of food, cannot be recommended without qualification. Infants, young children and invalids should use them very sparingly, or not at all. This class of people can better utilize raw goat milk products, as it contains high quality proteins with less danger of toxic residues. Cooked eggs are harder to digest than raw ones. Raw eggs are practically liquid. All foods must be turned to liquid before the body can digest it. The longer an egg is cooked the more difficult it will be to assimilate. Cook eggs as little as possible, never allowing the white to set. Coddled, soft boiled or poached eggs are the easiest to digest.

One egg contains 6 grams of protein, which is utilized about 94% by the body. Egg yolks are rich in all the elements necessary for complete nutrition, including iron, minerals, Vitamin B Complex and fats. Powdered egg shells are very high in calcium. Eggs are one of the few foods high in Vitamin D and A. The best eggs from the health standpoint are the ones bought locally from a farmer who allows a rooster to roam freely in the chicken coop, which produces fertile eggs. The chickens should also be allowed the freedom to soak up the outdoor fresh air and sunshine and be fed pure whole grains and food substances. Eggs being an extreme Yang food, should not be eaten in warm weather; they can be digested and utilized easier in cold (Yin) weather. People with Yang livers, kidneys, heart, colon and intestines should avoid the Yangizing affect of eggs. Meat, fish and eggs are not absolutely necessary to reach and maintain the highest level of optimum health, nutrition and longevity. If at first you succeed try to hide your astonishment.

Fig. 8.4. You have neither friends or enemies, only teachers. Learn from the Tao and you will have Internal Peace.

Chapter 9

Tao Garden's Healing Meals

As knowledge with regard to the effects of food upon humans increases, it is more than conceivable that the races that first avail themselves of the new values of nutrition may decrease the handicaps of disease, lengthen their lives, and so become the leaders of the future. Regimen is better than physic. Everyone should be his own physician. We ought to assist, and not to force nature. Eat with moderation what agrees with your constitution. Nothing is good for the body but what we can digest. What medicine can procure digestion? Exercise. What will recruit strength? Sleep. What will alleviate incurable evils? Patience.

The consensus of worldwide research and observation idicates that the ideal diet for mankind should consist of foods that are high in natural carbohydrates and low in animal protein, especially meat. This diet consists of the following foods and nutritional elements: Seeds, nuts and grains, which contain high quality B-Complex vitamin factors, Vitamin E, natural fatty acids, lecithin, phosphorus, iron, magnesium, zinc, proteins, fat lowering and energy building elements; fresh fruits and vegetables, especially berries, sub-acid and sweet fruit, fresh squeezed vegetable and fruit juices. These foods contain a super abundance of essential organic vitalizing vitamins, minerals, trace minerals, enzymes, alkaline cleansing, purifying and blood enriching elements.

This Ultimate Super Diet may be supplemented with yogurt, buttermilk, whey, nutritional yeast, kefir, sea kelp, alfalfa liquid, brown rice polishings and soybean powder with enzymes. These are natural protective foods. Use moderately.

Golden Nuggets of Nutrition

Seeds	***Nuts***	***Grains***	***Legumes***
Sunflower	Almonds	Buckwheat	Peanuts
Sesame	Walnuts	Rice, Corn	Soybeans, Peas
Pumpkin	Pecans	Millet, Oats	Aduki, Carbanzo
Alfalfa	Fillberts	Wheat	Black Beans
Chia	Cashew	Barley	Lima Beans
Flaxseed	Pine Nuts	Rye	Pinto Beans

Fig. 9.1. It is better to light one candle (Light of the Sun), than to curse the darkness. There is not enough darkness in the world to put out the light of one candle; nor is there enough ignorance or wrongdoing on earth to submerge what is corrected (The Way of the Tao).

Grains are Nourishing and Strengthening

All grains can be sprouted or used in making bread. Cooked grains are best in cold weather. In combination with legumes and vegetables, grains form nutritionally complete proteins. Grains are high in sodium, a Yang element. Grains are also high in phosphorus, an important mineral for proper brain functioning. Natural whole grains are excellent sources of B vitamins and contain six of eight essential amino acids. The other two amino acids can be supplied by adding seeds, nuts, vegetables or legumes to grain meals.

Grains are heat producers and impart sustaining energy. For example, two slices of whole grain bread well-chewed, will impart more energy and working power to the body than two pounds of steak. The European centenarians are known to work all day in the fields on a bowl of vegetable soup, raw fruit and a few slices of dark whole grain bread. The hard working, enduring Chinese consume whole rice and seaweeds as their energy and strength sustaining foods. The Turkish people are extremely hardy and robust and eat grains, sesame seeds, dates, and raw camel or goat milk. The strong Russians use buckwheat and millet. The Mexicans use corn and beans. The Bulgarians are a lactovegetarian culture. They are a very hard working and strong people. The Bulgarian diet consists of whole grains, mainly barley, sunflower seeds, honey, sauerkraut, fresh fruits and vegetables.

Buckwheat is the most Yang grain, high in vitamin E and protein. Rice is more balanced and easy to digest. Rye and wheat are good muscle builders and give great endurance to the body. Barley is also very easy to digest. It can be mixed with vegetables, used for bread making and excellent for soups. Oats, flaked or rolled are good in cereals, soups and cookies. They are high in fat and aid people with slow working thyroid glands. Corn is an excellent summer food; corn meal and flour make delicious corn bread. Corn builds the blood and imparts high energy; it is high in calcium and natural complex carbohydrates. Millet is a yang grain, but not as acid forming as other grains. Its nut-like flavor makes a delicious and nutritious meal on cold winter days.

Grains are high in natural carbohydrates and should be used mostly during the cold winter months for heat and body energy. They should be used in smaller quantities in warm weather. Warm weather is Yang, and the body needs more fresh fruits and vegetables to maintain its fluids in proper Yin/Yang balance.

Whole Grains

Rice:

There are two types of brown rice long grain and short grain. Long grain rice is a summer food; short grain rice is more Yang and imparts more heat energy for the cold weather. Brown rice is an easily digestible starch, good for weak constitutions and for building overall good health. Rice, and all other grains should be chewed very well, from 30 to 50 times each mouthful; this will insure perfect digestion and assimilation. Rice can correct conditions of diarrhea and constipation, due to its balanced qualities. A regular diet of rice can lower blood pressure and help arteriosclerosis. Due to its high B-complex, rice calms the nerves and brain; it helps to overcome allergies. Brown rice contains phytin acid, which eliminates toxins and poisons from the body.

Oats:

Oats are valuable in cases of underactive thyroid and overweight conditions. Oat meal or steel cut oats are best eaten in the winter and late fall. It has been used with success to combat sterility and sexual impotence. Oats are high in silicon, a mineral element which gives one a healthy complexion, shiny hair, strong nails and sparkling eyes. Diabetics can become stronger and healthier with the regular use of oats in the diet. Oats help to eliminate stored protein and toxic wastes from the body. Oats are excellent in cooking breads, cookies and soups. Lungs and large intestines are most benefited by oats and rice.

Millet:

Millet is rich in phosphorus, magnesium, iron, silicon, fluorine, manganese, vitamin A and B-complex. Yellow millet aids digestive problems and can help repair the gastro-intestinal system. With its high B-complex, magnesium and manganese, it is excellent for all nervous conditions and mental fatigue. Millet has been used to help prevent miscarriages and correct deficiencies in pregnant women. Yellow millet should be used mostly in the fall, or Indian Summer. Red Millet is more Yin, and is a summer grain. Millet is the most alkaline of all grains, therefore it aids conditions of toxemia and acidosis. It is a good source of protein. The spleen is the organ most benefited by millet, as is the stomach.

Rye:

Rye helps improve the circulation and clean the blood vessels, therefore helping artereosclerosis. Rye helps strengthen and tones muscles and imparts high energy and endurance. It is very low in gluten. Rye is a spring food. Rye strengthens and purifies the liver and gall bladder. Rye is a hardy grain used by many European cultures. Rye is used to make bread, or as a cooked cereal.

Buckwheat:

Buckwheat has the highest amount of protein of all grains. It is also rich in minerals and vita-mins. In analysis, buckwheat contains 12% to 16% protein. The amino acid lysine is very high in buckwheat, therefore it has the same high biological value and nutritive quality as the protein found in animal food. The darker the buckwheat, the more protein it contains. Buckwheat contains a large amount of manganese, a mineral generally deficient in many people. Manganese strengthens the nerves, muscles and helps build good posture and courage to carry on the responsibilities of life. The manganese in buckwheat is necessary for muscle control, growth, metabolism and the reproductive system. Buckwheat is rich in rutin, one of the bioflavonoids, which is vital in reducing capillary fragility and maintaining sound blood vessels. Buckwheat helps to overcome environmental radiation poisoning and fallout. Its magnesium helps to calm, relax, cleanse and balance the nutrients in the blood.

Buckwheat is rich in Vitamin C. It should be used mostly in winter, as it imparts high energy and heat. The kidneys and bladder are most benefited by buckwheat. The very hardy Russians and other European countries thrive on this most versatile grain. It can be used in noodles, cereals, casseroles, loafs, and takes the place of meat products. Buckwheat is also a good blood builder and helps to overcome anemia.

Corn:

Corn is very rich in calcium, Vitamins B, C, A and F. It is a summer grain. Corn aids conditions of underweight and overactive thyroid; it slows down the metabolism. It is beneficial for the heart and small intestines. Corn builds strong bones, teeth and muscles. Our ancestors thrived and survived on corn. The early Native Americans and Mayans cultivated corn for centuries. They built great civilizations, and their people were robust and long lived. Corn can be eaten on the cob, made into corn bread and soups. It is the most Yin grain and should be used mostly in summer. It imparts good vitality, aids digestion, and builds rich red blood. Corn is the sweetest of all grains, and is converted into sugar within the system very quickly, giving quick energy and endurance. Corn oil contains vitamins F and E. Corn meal is highly nourishing and contains vitamin A.

Barley:

Barley is a fall food. It is beneficial for the lungs and large intestines. Barley is very easy to digest and is good for those with weak digestive systems. It can be used in soups and bread; it is used in making barley miso, which is not as Yang as soybean miso. Barley is used by many cultures around the world. It imparts much heat and energy and gives one strength and endurance. Valuable in conditions of underweight, stomach ulcers, diarrhea. Contains vitamins B-l and B-2. Also as poultice for skin diseases and burns.

Wheat:

Wheat contains the highest vitamin and mineral content of all grains. The bran in wheat imparts good digestion and elimination. The germ in wheat contains a rich source of vitamin E, which builds a strong reproductive system, improves endurance and aids the heart function. Wheat is beneficial to the liver and gall bladder.

The gluten in wheat will not cause allergies if the liver, kidneys, and eliminative channels are kept clean and free of toxic wastes. Many times allergies are caused, not by wheat alone, but by a system filled with milk, cheese, fats and sugars. The gluten may react allergically in a body that is weakened by high fat and sugar foods. Experiment on yourself; discontinue all fatty, oily and sugared products, including dried fruit and tropical fruit for several weeks. Then eat whole wheat for a few days, and observe the reaction in your body. Poorly masticated wheat can cause indigestion, mucous, allergies and poor health. Chew and salivate all grains very well, and watch your health improve, and allergies vanish like magic.

Wheat is used in bread making, cereals, sprouting, noodles, pancakes, bulghur and couscous. Wheat is high in protein and gluten. Wheat has been used by all great civilizations and cultures throughout history. Allergies are unknown in wheat eating cultures where there is no milk, sugar and fatty food.

Beans and Legumes

Legumes take in the whole bean family, including peanuts, peas, split peas and lentils. Legumes consist of both protein and starch they are considered complex carbohydrates and are rich in vitamins and minerals, especially the B-complex vitamins. All legumes should be eaten moderately more in winter than summer.

Aduki Beans: Used successfully in kidney disorders, and is a good bean for general use. When cooking all beans, use about 3 cups of water to one cup of beans.

Black Beans: Aid kidney functioning and sexual disorders, such as menstrual difficulties, frigidity, barrenness, low sex drive. Black bean juice the liquid left over after cooking the beans, (use 1 or 2 extra cups of water when making any bean juice) can be used for throat disorders, such as laryngitis and hoarseness. Black turtle beans are excellent in soups and combined with rice or buckwheat.

String Beans: More like vegetables, and contain more protein than vegetables. They should be eaten in warm summer months, in season when available. They are good for constipation, rheumatism, acidosis, bladder and kidney disorders. They are low in protein and rich in vitamin A, B-1, C and B-2.

Soybeans: Not generally recommended to be eaten regularly, as they contain difficult to assimilate substances that adversely affect the thyroid gland. Tofu, a soybean cheese can be used occasionally. Miso and tamari sauce are made from soybeans and can be used more often during winter months for body warmth. These products are high in vitamin B-12 and iron. They also help the body fight off the harmful effects of environmental radiation and fallout. They are beneficial to the thyroid gland. Soybean products are also high in protein.

Green Peas: Good for the stomach and lungs. They contain many valuable vitamins and minerals. Green peas are highly nourishing and strengthening. They aid conditions of anemia, emaciation and low blood pressure. Contain vitamins A, B-1, B-2, B-6 and nicotinic acid. Good with most grain dishes and salads. Yellow split peas are excellent for all digestive disorders, and are very easy to assimilate. They can be used at all times of the year for warmth and energy. Lentils contain similar properties of split peas and cook the same way. They are all good sources of protein. Dried peas can be cooked without soaking overnight, in 60 to 90 minutes on the stove. Pressure cooking takes about 30 minutes.

White Beans: Aid in discharging excess toxicity from the heart. They are a good all around bean to eat with grains and vegetables.

Garbanzo Beans: They are also called Chickpeas. Good source of protein. Used in many cultures around the world, including Greece, the Near East and in most American restaurant salad bars. Chickpeas can be eaten in soups, salads, loafs, sauces and dressings. They have a rich flavorful taste and are highly nourishing.

Bring the energy up to your feet, into your bones. Let it enter all the bones, organs and cells. Feel it blending with all the sick energy. Turn your palm up, turn it back down again and exhale; let go of all the sick energy, the negative energy, the worries and the burdens all the way down to the earth. Down, down, down to the earth. Again from the earth up. Do it at least three, six or nine times. When people are very sick, you need to clean them thoroughly. Bring the earth energy up into your bones again. Feel numb, tinkling electricity flowing in all your cells. Return the energy down, down, down to the earth. Relax, let go; worries, burdens, let everything go. It is very important to say to yourself or group: **"You must let go of all your sick energy. Let go of all your burdens. Let go of all your worries, down to the earth".** Repeat it once again. Inhale from the universe and into the earth. From the earth let it enter into your bones. From the bones all the way to your inner self. Feel the energy blend with the sick energy. Exhale and let go of all your sick energy, any negative emotions burdens, worries, anxieties; release them all the way down into the earth.



Fig. 4.38 *Bring the Universal Chi down and let it blend with the sick and negative energy. Bring it down into the earth and bury it there.*

Empty negative, sick energy, burdens, worries, go deep down into the earth. Dig a hole and bury them there - tell them "Do not come back; you will be happy there."

Feel that the feet are long and extended into the earth. The hollow bones have been compacted with compressed Chi.

Pinto Beans: Contain the highest RNA and DNA factors of almost all foods, except sardines. They have been used in the south and Mexico for many years, and are usually combined with corn bread and other corn recipes. Pinto beans are also high in protein, vitamins and minerals.

Kidney Beans: Shaped like the human kidney and are said to strengthen the kidneys. They are rich in protein, and are very warming and nourishing to the body. They can be used in salads, casseroles and other grain dishes.

Lima and Butter Beans: Good sources of iron and are easily digested and assimilated. Good for anemic people and weak digestive systems. These beans are very strengthening and building and can help to overcome emaciation and malnutrition. They contain vitamins B-6, B-1 and B-2. Good protein source. Good in casseroles, grain and cooked vegetable dishes. Lima beans aid the discharge of toxins from the liver, and build strength in that organ.

Germinated Seed and Nuts

The king of all nuts is the almond. The sunflower and sesame seeds are the queens of all seeds. Germinated seeds and nuts are alive with life; they have the power to grow and to create new life. They can create a new rebirth in your own body if used regularly. The world renowned health authority and longevity researcher, Seeds have been found in Tutankaman's tomb three thousand years old they have been put in the soil and have grown. Sunflower seeds have been found in the old missions that are two hundred years old and, when planted, have grown. The seed is the element that contains the birth of a tree, the birth of a plant, the birth of vegetables. In the seed of the tree we have the pattern for the bark, the sap, the flowers, the fruit everything that had to be put into that seed to begin with. All the life giving elements are contained in seeds, carefully locked in. They are there for our good. Seeds contain nearly every single food element that has been discovered, and doubtless all the additional factors not yet identified. No other one food is so rich in nutrients, the seed containing as it does, the life forces needed to build the new generation. Seeds have highly potent therapeutic values. They are prime sources of most of the nutrients and one of the most potent sources of unsaturated fatty acids needed to maintain youthful and elastic arterial conditions.

Seeds and nuts are high in calcium, Vitamin E, phosphorus, niacin, lecithin, fatty acids, iron, natural oils and a good high quality protein. Pumpkin seeds contain zinc, a hard to get mineral necessary for proper prostate functioning. Seeds are rich in Vitamin A, B-Complex and magnesium. Germinated seed and nut milks are an excellent substitute for regular milk, and contain complete proteins of a superior biological value, capable of sustaining life in perfect health indefinitely.

Miracle of Seed and Nut Germination

Seeds and nuts are essential nutrients for the body. Mention seeds or nuts to someone and this is what you hear. They make me constipated. They cause skin problems. They are indigestible. Yes, when seeds and nuts are eaten in the conventional way they can cause these problems.

Seeds and nuts are loaded with vitamins, minerals, fats and proteins of a high biological value. But if they are eaten after a heavy meal, snacked on between meals, poorly chewed, ungerminated, salted, oiled and preserved with chemicals, they can cause much harm to the liver and intestines. Seeds and nuts are very concentrated, so they must be eaten in small quantities.

Since seeds and nuts are quite difficult to digest for most people, passing through the body unassimilated, it is important that they be soaked or germinated, at least overnight in water or juice. The longer you sprout a seed or nut, the more alkaline it becomes, and the less acid reacting qualities it will have. So, we recommend soaking the seeds or nuts overnight to maintain the protein elements that are needed for the daily acid/alkaline balance. Three to seven day old sprouts are excellent alkaline foods, but they should be balanced with 1 day old seeds or nuts, soaked.

Soaking seed and nuts, and the sprouting process make them very easy to digest and assimilate. This method also converts them into complete protein, allowing the body to utilize up to 100% nutrition as a result. Unsoaked or ungerminated seeds and nuts contain only 20 to 30% nutrition: the rest being waste products, causing indigestion and cravings for junk food. Humans cannot derive complete nutrition from dried fruits and dried seeds and nuts. Undigested protein from these foods creates toxemia, which can cause the following conditions in time: falling hair, poor eyesight, anemia, diabetes and weakness.

Dried fruits, nuts and seeds, unless soaked overnight, are extremely constipating and toxic. They can become as disease producing as devitalized foods, due to their indigestibility and poor assimilation. Dried apricots, figs, dates and raisins should be soaked in water or juice from 4 to 8 hours. Use dried fruits in moderation and mostly during the winter months. The Taoist of China and India, who maintain vibrant health and youth far into advanced ages, from 120 to 200 years old or more, advocate and practice the eating of soaked and germinated seeds, grains and some nuts.

Germinating Seeds and Nuts

If we could pick nuts and seeds right from the tree and eat them on the spot, there would be no need to soak them because the necessary moisture and life force would still be intact. In the dried state the life force is lying dormant, therefore, these foods require soaking to wake up the Life Force within them. This is the same principle used in sprouting wheat grass, lentils, mung beans or alfalfa seeds. The life force within the seed or nut is tremenously increased.

Since we are living in an unnatural society and environment, we have to resort to these methods, which are in no way contrary to Natural Law. In fact, it is natural to germinate all seeds and nuts. Also as these foods were already tampered with through the process of early picking and storing; we are merely replacing the natural moisture that was taken out. Another important benefit from soaking seeds and nuts, is that their protein quality is enhanced, along with a higher quality natural taste. We are simply bringing out their finer qualities, and not detracting one iota from the health value. The same method is true of soaked, dried fruits. Their vitamin, mineral and iron content, and assimilability greatly increases. For more variety, use different seeds or nuts. Try sunflower, pumpkin and sesame seeds, almonds, filberts, pine nuts, walnuts and pecans. Make sure that you hull these seeds and nuts before soaking them. The seeds need only be soaked overnight. The heavier nuts can be soaked up to 24 hours for better assimilation and nutrition. If you are planning to sprout seeds and nuts for a longer time, use a sprouting dish, or a jar with a screen on the lid. Wash them with water 2 or 3 times a day; let the water drain over the sink, and in 3 to 6 days you will have some nutritious and delicious green sprouts. The last day of sprouting, place the sprouts on the window ledge and the sprouts will turn green. You can sprout anything that will grow from a seed. Sprouts and all seeds and nuts contain Vitamin E. They also build up the glandular system of the body.

The maximum benefit is received from dried fruits if they are soaked first, as unsoaked dried fruits almost always cause gas before the digestive juices can get to them. The normal digestive process for dried fruits lasts about ten hours, and before the unsoaked dried fruits are adequately soaked up by the digestive juices, the body is ready to expel them. Thus, we do not get the good out of them unless they have been pre-soaked. There is an art to soaking the dried fruits properly. Wash, add cold water to cover, and bring slowly to a boil. Remove from heat and allow them to stand all night. The boiled wated kills all insects and parasities that might otherwise cause trouble. Remember to start with cold water, so that the increasing heat will penetrate into the inside of the fruit. They also may be soaked overnight and liquified with juice in a blender.

Enzyme Inhibitors in Unsoaked Seeds/Nuts

According to Dr. Edward Howell, research biochemist in the field of nutrition and enzymes states that any ungerminated raw seeds or nuts contain enzyme inhibitors. These inhibitors are necessary for the protection of the seed, to keep it from germinating prematurely and die. Raw seeds and nuts actually neutralize some of the enzymes our body produces. In fact, Howell states, eating foods with enzyme inhibitors causes a swelling of the pancreas. Raw peanuts and egg whites contain the most enzyme inhibitors. Most fruits and vegetables do not contain enzyme inhibitors; they are rich sources of living enzymes.

Sprouting and germinating seeds and nuts destroys the enzyme inhibitors and also increases the enzyme content from a factor of 3 to 6. Peanut butter and other nut butters, because of their lack of enzymes and high fat content, are very indigestible and should not be eaten often; use sparingly. The same goes for all seeds and nuts, unsoaked or unsprouted.

Germinated and Blended Seed/Nut Milk

When soaking seeds and nuts overnight they become much easier to digest and assimilate in combination with sub-acid fruits. No more than 2 or 3 ounces should be eaten. Soak seeds or nuts overnight in fruit juice or water, and the next morning or afternoon make a blended nut milk. Add berries and juice along with 1 teaspoon of vegetarian protein powder; blend together and you will have a meal of total and complete nutrition. After a few weeks on these super nutritious foods, your complexion will glow and your blood count will rise. As health culturists, let us look the part, so that we may be an inspiration to everyone we meet. Remember, the proof is in the doing.

Sprouts: Wonder Food

Sprouts are truly a miracle food. They are an excellent source of vitamin A, B-Complex, C, D, E, G, K, and U. Dr. Pauline Berry Mack, at the University of Pennsylvania, found that soybean sprouts of 72 hours contain more Vitamin C than 6 glasses of orange juice. Sprouts also contain all eight of the amino acids which make up protein. It only takes about a tablespoon of alfalfa seeds and two to three times that much to plant 25-30 square inches. Soak the seeds overnight in a warm dark place in about three times as much water as you have seeds. The water should be warm (70-80 degrees) and free of chlorine and flourine, which can sterilize the tender embryo.

Pour the water off and rinse them well to prevent mold. This water is excellent for juices and stock. Place seeds in a warm, moist, dark container. Flush every 4 to 6 hours with water to clean them and assure adequate growth. Be certain the seeds drain well because they will sour and rot if you do not. In 3 to 6 days, depending on the temperature (80 to 90 is best) and seed variety, your seeds will have doubled or tripled and be ready for consumption. Sprouts reach their highest vitamin peak 60 to 80 hours after germinating.

If you expose your sprouts to indirect sunlight during the final several hours of growth, they will develop chlorophyll. The chlorophyll molecule is very similar to the hemoglobin, the only difference being that chlorophyll has magnesium at the center, while hemoglobin has iron, and consequently, acts as a blood booster.

Probably the simplest container is the mason jar, substituting a wire mesh for the lid. A large bowl makes an excellent container for the jar since it should be at a 45 degree angle to assure proper drainage.



Fig. 9.2. Sprout Seeds

1. Individual portion, put a ¼ inch layer of seeds in a water glass.
2. Fill glass about ¾ full of distilled water. (Do not use tap water). Let this soaking take at least six hours, or if done just before going to bed, let stand overnight.
3. Pour contents of glass into a small flower pot that has small holes on the bottom. If it is a pot with one large hole, put cheese cloth or wire mesh over the hole.
4. Bring flower pot under water faucet and allow water to thoroughly rinse over seeds.
5. Cover seeds with wet cheesecloth, or turkish toweling. Repeat rinsing of seeds three times a day (as in No. 4), replacing moist cloth over seeds.
6. Sprouts should look like this on the third day ready to eat.

Fruits for Beauty, Health and Longevity

The bioelectric forces of the earth in its mysterious way, combined with the biomagnetic forces of the sun and atmosphere, produce fresh, ripe blood building fruit. Fresh wholesome fruit, taken in season, and in moderation, release upon the forces of the body vital alkaline vitamins and mineralsthe living building blocks so necessary for healthful robust living.

The living fruit, kissed by the basking rays of the energizing solar sun, absorbing draughts of magnetized air, attracting to itself all the vital elements necessary for its perfection, is a cosmic miraclean electrochemical laboratory of Nature (the Tao). Scientists can remove all the chemicals of an apple out of a chemist's dish, but he cannot construct an apple. They may probe and analyze all the elements of a cherry, but they is dumbfounded to know what makes them red. They may take apart and attempt to reconstruct a plum, and they will find that the plum will help support life, but the broken down chemicals do not. Fruit contains essential bioelectric principles Yin and alkaline elements which, when eaten in additon to a well-rounded, balanced diet, will give the electric spark of life and vital health force.

Who has not had his mouth water on seeing a luscious peach, cherry or melon before him when hungry. The sight, aroma and taste of fruit, bring on an abundant secretion of digestive juices; they are very digestible on an empty stomach. A total fruit or eliminative diet can be used as a remedy to balance Yang kidneys, liver, colon and intestines, for a short period of time. Otherwise, use fruit in season and grown locally. Eat more fresh raw fruit in hot summer months when they are abundant; less in cold weather when they are not in season and less abundant. Apples or pears can be baked or steamed in the winter for warmth and variety.

Berries	***Melons***	***Seasonal Fruits***	***Tropical Fruits***
Blueberries	Watermelon	Cherries	Oranges
Blackberries	Cantaloupe	Grapes	Grapefruit
Strawberries	Honeydew	Apples, Figs	Tangerine
Raspberries	Casaba	Pears, Raisins	Pineapple
Huckleberries	Persian	Peaches	Mango
Gooseberries	Cranshaw	Apricots	Papaya
Elderberries		Plums	Lemons
Loganberries		Nectarines	Limes, Avocado
Boysenberries		Persimmons	Banana, Dates

Fig. 9.3. Seasonal Fruits

Fresh berries head the list as being the best of all blood builders, containing a rich source of iron and vitamin B-12. Ripe fruit, in moderation, does not cause acid or toxic conditions in the body, nor do they cause diabetes or other diseases when used judiciously. Sub-acid or acid fruits may aggravate a system that is already highly toxic or acidic: they will stir-up the internal acids and cause pain or discomfort. Acid and Yang conditions can benefit from the use of non-acid fruit, such as all melons, and neutral vegetables and their juices.

In healthy people, fruits are alkaline in reaction in both urine and ash lung tests. Fruits are easy to assimilate, and if eaten moderately, do not overwork the pancreas, as does pastries, fats and sugar products. However, be advised that an excess of fruit will over-alkalize the body and blood, and cause Yin diseases, such as, hypoglycemia and diarrhea. Melons are a rich source of minerals and vitamins, however, they should be eaten only in small quantities, especially if one has expanded (Yin) kidneys.

The longest lived and healthiest people on earth consume some fruit everyday rounding out their daily diet with grains, seeds, nuts, vegetables and some raw milk yogurt or buttermilk. Chlorophyll is not only found in the green element of vegetables, but also in all fruits kissed by the sun. Fruit is also more likely to be free from strontium 90 radiation fallout than other food grown close to the ground. Fruits are manufactured from cosmic sun rays, the oxygen absorbed through the leaves, and the water filtered by the roots in the soil. A large fruit orchard will produce over 100 times more pounds of fruit than meat in the same acreage.

Fruits are very abundant in organic vitamins, mineral salts, purified distilled water, and refreshing and healthful. They are high in natural sugars and fruit acids. Most fresh fruits contain about 90% water, 10% carbohydrates and not more than 1 ½ % protein. Fruits are cooling and refreshing to the body because of their high water and organic acid content. All ripe fruits are alkaline reacting within the system. These alkalies neutralize the acid poisons, uric acid and acidosis, usually coming from a high protein meat diet. Overeating of fruit, especially the citrus variety will saturate the body with citric acid, which can cause serious calcium loss, mineral depletion and an unbalanced blood chemistry resulting in Yin arthritis, stiff joints, tooth decay, nervousness, nerve diseases and toxic acidity.

All fresh berries and especially strawberries, excel almost all other foods in easy to assimilate iron and organic bases to neutralize acid wates. Fruits contain citric acid, malic acid and tartaric acid. Citric acid is found in all citrus fruits and in other fruits such as, cherries, currants, berries, pomegranates and tomatoes. Malic acid is found mostly in pears, plums, apples, pineapples and cherries. Grapes contain tartaric acid. Oxalic acid is found in small amounts in most fruits, but cranberries, spinach and most greens are high in it.

Fig. 9.4. Seasonal Melons

Sweet fruits are especially valuable for their delightful sugars, so easily digested (sometimes almost predigested), which sustain the body with so little energy expenditure for digestion.

Fruits can help you overcome Yang constipation, especially cherries, grapes, prunes, figs, berries and lemons. The acids of fruits increase the secretions of the intestines, move the bowels and increase their peristaltic action. Fruit meets the bodily need for natural bulk and intestinal health.

Most fruits contain phosphates and alkalies, together with acids, which increase the solubility of the blood, causing it to flow through the system more readily. Since fruits are Yin, overeating them can easily cause Yin constipation (expanded colon and intestines). In this condition, eat less fruit, and increase consumption of cooked grains, vegetables, miso and tamari, for a natural balance and healthy colon.

A balanced diet, including fruit, purifies the blood, that even the cravings for alcoholic drinks have been known to disappear. When the blood is purified and its pure nutrient stream bathes the cells and tissues, it will remove wastes, impurities and dead cells, and leave behind strong healthy tissues. In time, the alcoholic will be completely purified and cleansed, and in his right mind. Alcohol will then be repugnant after the cleansing period.

Eat Fruit Alone

Fruits should be eaten on an empty stomach, and not as a dessert, after the appetite is satisfied and the digestion is already sufficiently taxed. Fruit taken in the morning, before the fast of the night has been broken, is very refreshing, and in addition to its nutritive qualities, serves as a stimulus to the digestive organs. Berries, cherries, melons, tropical fruits, apples or pears are all excellent at this time. Eat ½ hour before protein or starch meals.

Fruit to be most valuable as an article of diet, should be ripe, sound, fresh, and in every way of superb quality, and be eaten raw or baked. If you live in the sub-tropics, you can pick and enjoy fruit directly from the trees almost all year long. Northerners will find apples, pears, peaches and plums most enjoyable during the summer and winter months.

Many people believe that fruit does not agree with them. In such cases, the trouble may be traced to the abuse and misuse of the fruit, or because of digestive weakness due to wrong eating habits previously. Fruits combined properly will not cause problems. Fruits eaten with starch or other junk foods will cause fermentation. Fruits eaten moderately and by themselves are easily digested.

Once again guide the good Chi from earth up to the fill the person again. See the cells as big as the stars and fill them with Chi to blend with the dirty and sick energy. Then empty them again down to the earth.



Fig. 4.39 *You can also use a Tree to guide the Chi down into the Earth.*

H. Clean with Green Light

Become aware of your liver and breathe into your throat center. Feel that you are breathing the green light into your throat center and let it blend in the Tan Tien. The Chi comes up to blend in the heart, up to the crown, spirals and goes up to the universe. Raise your hand in a spiraling motion up to the universe. Use your 'one hand' to spiral in the universe. Spiral clockwise first. Spiral green light from the universe. Now reverse, counterclockwise - multiply and spiral counterclockwise, bringing the Chi down to clean out your communities, your house, the Tao Garden, the meditation hall, your bodies and all of the people that are 'here' - fill yourselves with Chi. You will use this power to see the cells.



Fig. 4.40 *Spiral Sick Energy Counterclockwise down to the Earth. Smile to the Cells and let the Green Light clean out the sickness, flushing it down into the Earth below.*

Fig. 9.5. Seasonal Vegetables

Vegetables: Rich in Chlorphyll

Vegetables, especially the non-starchy greens, contain the greatest amount of blood building chlorophyll. Chlorophyll, as found in fruits and greens, is necessary for the health and well-being of all living creatures on this planet. The strongest and longest lived animals in the world are vegetarians and consume rich green chlorophyll in the form of plant food, which is adapted to their complex digestive system.

Chlorophyll is composed of a combination of tiny molecules of a substance called pyrrole. These pyrroles are the building blocks of the animal blood pigment, hematin or hemoglobin. The pyrroles in plant chlorophyll are tied together by an atom of magnesium, whereas in human blood, the mineral bond of these pyrroles is iron. The human system requires green chlorophyll for proper blood formation, which builds healthy cells and tissues. The color green, according to the ancient art of color therapy is a healing agent and bone mender. Green vegetables are excellent sources of Vitamins A, B-l, B-2, C, K and Vitamin E as well as an abundance of organic mineral salts, alkaline elements, trace minerals and enzymes. Vegetables rank high as health builders, and are superior blood and bowel regulators.

The best raw vegetables for salad making are: alfalfa and mung sprouts, cucumbers, green and sweet red peppers, onions, radishes, celery, romaine, bib and Boston lettuce. Coarse, tough vegetables should not be used instead use the tender juicy variety. Root vegetables, cabbage, beans, peas, squash should all be cooked for proper assimilation. Hardly a person exists that can properly digest and assimilate these foods without the aid of fire to soften the cellulose and tough fibers, a substance that is indigestible for humans, and which is not acted upon by the digestive fluids, unless it is softened by heat.

All raw vegetable greens can be easily utilized and assimilated by the system when they are juiced and consumed immediately. The rich green chlorophyll in vegetable juices is easily absorbed into the system within a matter of minutes. Use juices moderately at all times. Use small raw salads in warm weather, and cooked vegetables in cold weather. A word of caution: Consuming large salads daily will overwork the liver and stomach causing digestive disorders. Too much raw vegetables cause expansion (Yin) conditions within the body. Man does not possess several stomachs as a cow does, to assimilate and digest hugh amounts of raw vegetables. About 20% to 30% of the daily diet should consist of raw and cooked vegetables.

Besides drinking vegetable juices, you can make delicious vegetable broth soups, steam a variety of starchy and mildly starchy vegetables such as potatoes, pumpkin, beets, carrots, broccoli, celery and cabbage, or cook grains such as brown rice, buckwheat, millet or oats. Steam and cook your vegetables and grains in a stainless steel pressure cooker, steamer, or waterless cooker over a very low flame. This will insure that the goodness and freshness of the cooked food remains intact when you serve it at the table.

Cultured Dairy Products

The long lived Russians, Europeans and Bulgarians, believe strongly in the use of cultured dairy foods. Scientists have found that cultured dairy products help to increase the beneficial and friendly bacterial flora in the intestines, maintaining its cleanliness and health. Soured acidophilus milk rejuvenates the intestinal tract, improves digestive problems and relieves constipation.

Those who want to use dairy food, without the harmful effects of high fat milk and cheese, can consume the following low fat dairy products in moderation: buttermilk, low fat yogurt, cottage cheese and skim milk. These products are not extreme Yin or Yang, but are more neutral except for low fat cottage cheese which is more Yang. Cultured dairy food should be used very sparingly in cold weather, and moderately in warm weather. Yogurt began its rise to fame many years ago in the European countries, and suddenly it has become a super food of the world. Yogurt contains high quality and easily digestible proteins, vitamins, minerals, enzymes, including Vitamin D and B-12. Because it flourishes with friendly bacteria it is almost a predigested food, quickly absorbed and assimilated into the blood stream. The sparing use of low fat dairy products can add variety and nourishment to your natural food diet. However, that milk was originally intended for infants only. Use wise judgment in the dietary use of this food.

The kind of food you eat is even more important to your existence than the kind of air you breathe. More good healthor ill healthcan be traced directly to food than to any other of the outside factors surrounding your existence.

Fig. 9.6. Seasonal Foods

General Dietary Principles

The daily menu plans should be flexible and adaptable to meet individual needs and requirements. It is very difficult to set down a specific dietary eating program for all persons under varying conditions on a daily basis. Each person must use supreme judgment in choosing foods, recipes and menus to fit their own personal and environmental needs. One has to devise their own pattern of how to eat, when to eat, where to eat and what to eat. For example, people working physically hard outdoors all day long may require a more substantial breakfast to meet their energy demands. People not working as hard will require less food and calories.

The main point to remember is to eat only when hungry in the morning and/or throughout the day. Keep in mind, however, that the body is not fully awake and ready to absorb and assimilate a heavy meal soon after waking. The ancient Taoist recommend that we may eat more food at breakfast in cold winter weather and less food in the evening during warm summer months. Many people consume far too much food and exercise very little, whereas, if they would exercise moderately everyday, they would utilize their food more efficiently and not require as much volume. Or, many people consume too much fruit and not enough vegetables, or too much meat and dairy, and not enough of grains and legumes.

The key to good health is to balance our eating habits with our daily work, exercise and living habits, and thus maintain the body in a constant youthful condition. We learn a thing by constantly doing itif we constantly cultivate healthy habits, we will reap or create healthy bodies and freedom form disease. The ultimate choice is yours; you can be master of your destiny if you truly understand that your health can be no better than what you eat, assimilate, absorb and digestand the effort, discipline and value you place on internal and external physical fitness.

By daily cultivating these dietary and health principles for the rest of your long life, you will not worry about vitamin or mineral deficiencies, malnourishment, calories or ill-health. The suggested menus should not be a strict cut and dried calculation. Use them as approximations of what to eat according to climate, locality and daily body requirements. Study the diets of various countries around the world. Many nationality dishes are vegetarian or can be easily converted. Many nations with a history of longevity and good health have a national staple based on legume and grain combinations which are easily included in a vegetarian or transition diet.

Food Cooking

To cook or not to cook, that is the question that has been hotly debated by healthfooders for many years. It is true that some articles of food can be eaten without preparation or cooking with full benefits of health and nourishment, i.e., most fruits and some vegetables, such as cucumbers, all germinated seeds and nuts, green peppers, celery and other tender juicy greens. Much of the food consumed by the long lived people of the earth has been raw, i.e., yogurt, seeds, grapes, pears, berries and celery. However, during cold winter months these robust people consume cooked grains, vegetables, legumes and soups. Since cold weather is extremely Yin upon the body, properly cooked natural foods are a physiological necessity to keep the body warm and in Yin and Yang balance. We need more Yang cooked food in winter, and much less in summer; eat more raw food in summer. This is the law of nature. If we try to deny our physiological requirements, i.e., consuming raw food exclusively or cooked food only, the body will not function efficiently and in good health.

It has been argued that all wild animals take their food raw. This is true. However, they have a digestive system adapted to digest tough raw vegetables. Their system consists of several stomachs, larger livers and kidneys, very powerful enzymic and digestive secretions and acids. Fire is one of the five elements of nature. Fire is what separates humans from beast. Without fire, civilizations would not advance; we would still be like the animals in a wild or primitive stateno advancement, no civilization, no evolution, no great intelligence, no art, no culture, no mental and spiritual upward movement. Humankind was given the knowledge of the use of fire to advance themselves; to populate the globe, including the cold northern regions. To accomplish this task, heat and fire was a necessity to keep warm, survive and grow; heat energizes food. A total raw food diet would not meet this requirement. Constant change and advancement is the law of the universe. Without change, there is decay. Without change, there is no advancement. When we learn to flow with the change, we can become healthy, and advance successfully. The human system cannot possibly assimilate and digest raw legumes, grains and root vegetables the starch molecule must be broken down or dextrinized by the use of fire to absorb the food value. Raw starch is indigestible. Sprouted grains and seeds are also Yin and can be used in salads, along with cooked legumes and grains.

Fruits can be eaten raw in season, and can be absorbed and digested easily, however, they cannot sustain the body in superior health exclusively. It is true that cooking has been abused in modern times, but this does not mean that proper cooking is bad; it is good. Because water drowns people is no reason to stop drinking it; because fire can burn and destroy life and property is no reason to not use it to heat the house or cook the food. In general, foods that are palatable raw, should be eaten in that form. Other foods not suitable to the human stomach raw, are better cooked, in which state they are more readily acted upon by the digestive juices of the stomach.

Fig. 9.7. Code of Eating Natural Foods

Vital Keys to increase your Life Force

1. Refrain from overeating at any one meal. Leave the table one-half to three-quarters full. This will allow proper assimilation and digestion. Overeating overworks the liver, kidneys and internal secretions and can take 30 to 40 years off of your life and cause many illnesses.
2. Always go outside after a meal. Because the body requires plenty of oxygen to properly oxidize and assimilate food, especially protein or starch foods. Take a slow outdoor walk for one-half to one hour after meals and gaze into the distance; this relaxes the digestive and nervous systems, allowing smooth and easy digestion.
3. Never eat according to the clock. Eat only when there is a very strong desire for wholesome foods. Hunger is a watery

mouth and throat sensation. Nausea, headaches, addictive cravings, or stomach pangs are a sign of stomach trouble. When not hungry, fast until it returns in full force.

4. Always chew or masticate your food to a liquid state before swallowing it. The stomach has no teeth. The more you chew, the better your digestion will be. Starch foods, i.e.,grains, legumes, root vegetables especially require ptyalin, an internal chemical secretion in saliva which starts the process of digestion of starches. If you have trouble chewing food, eat a bite of celery with every bite of starch; you will chew longer.
5. Do not eat when in pain, worry, emotional upset or when sick; food cannot digest in these states.
6. It is best to eat the evening meal no later than sundown, when the earth's energy and magnetic forces are still present. Allow 3 to 4 hours from the evening meal to bedtime.
7. Keep meals simple for easiest digestion and most efficient utilization of nutrients.
8. Use only soaked or germinated seeds and nuts. Roasted seeds and nuts are more Yang and can be used more in winter. Roasting lessens the fat content.
9. Always soak dried fruits over night. Use more in winter.
10. Use kelp, powdered vegetables seasonings, miso, tamari on foods for taste.
11. Use pure vegetable oil in cooking or salads; no more than 3 teaspoons/day. Make dressings with yogurt or seed sauces.
12. Eat foods mostly grown in the region you live; eat seasonally, i.e., foods grown in your area at each season. Eat more raw food in summer; more cooked food in winter.
13. Use mostly neutral herb teas for daily consumption: Mu tea, bancha, jasmine and dandelion are good.
14. If possible, eat food organically grown without pesticides.
15. Plan meals not only for nutritional content, but also aesthetic interest. Blend and harmonize colors, textures and flavors.
16. Cut vegetables in small pieces; they will cook quicker.
17. In food combining use nuts and seeds or milk products with acid or sub-acid fruit or non-starchy vegetables; use grains and vegetables together; do not use fruits and starches together and do not use sweet fruits and protein together. Sweet fruits are best eaten alone.
18. Be cheerfulness at mealtimes to aid digestion.

By making these General Dietary Principles a daily habit, you can attain excellent health and long life. However, everyone is different, and they must vary these dietary suggestion to fit their own individuality. Changes can also be made for people on special diets or severe digestive disorders, such as blending salads or pureed fruits and nut and seed milks. Weak digestive systems need much help, and they can greatly benefit from the use of blenders, juicers, mixers etc.these are life saving dietary measures to be used when necessary.


Fire
Bitter: Bitter Greens, Bitter Gourd, Winter Melon
Earth
Sweet: Fresh Cane Juice, Palm Sugar, Longan Fruit Juice, Mango Sauce
Metal
Pungent: onion, garlic, daikon, radish
Water
Salt: Himalayan Rock Salt, Bamboo Salt, Kikkoman Soya Sauce
Wood
Sour: Tamarind, Lemon, Passion Fruit

Fig. 9.7. Five Element Food Tastes in the Creation Cycle at Tao Garden

Five Elements and Food

Balancing the Five Elements can become extremely complex. However, there is a lot you can do with careful choice of food to rebalance your own organs and health. Firstly, we look at the different internal and external climates and foods to help them:

Condition:	***Symptoms***	***Foods***
Too Windy:	Moving Pains, Wind, Spasms, Dizziness, Spring Season	Oats & Pine Nuts; Chamomile Tea, Ginger and Fennel. Fresh Greens and Salads bring a Spring Cleanse.
Too Hot:	Feeling Hot, Flushed Skin, Summer Season	Raw Foods, Fruit, Cooling Herbs (Mint). Light Eating.
Too Dry:	Dry Skin, Thirst, Constipation, Autumn Season	Soya Products, Nuts, Seeds, Dairy. Psyllium, Malva Nuts, Flaxseed Tea.
Too Cold:	Feeling Colder than people around you, Winter Season	Soups, Casseroles, Warming Spices, Ginger. Warmth-Building Foods.
Too Damp:	Having too much Mucus or Phlegm, Rainy Season/ Seasonal Changes	Avoid Dairy. Avoid Cold Foods. Mung Beans, Aduki Beans, Garlic and Pumpkin Reduce Damp.

Different flavors are used in Five Element nutrition to balance each element. Different flavors have different energetic effects:

Sweet: This is actually the central flavor of the diet. Thus, the basis of our diet is full sweet foods such as wholegrains, beans and root vegetables. The empty sweet flavour of sugars, honey and fruit should be used more cautiously.

Pungent: This flavor helps expel fluids and pathogens from the body. Thus, it is a flavor we use when we are getting a cold or flu, and also to clear mucus and heat. Warming pungents are ginger, cayenne and pepper. Cooling pungents include peppermint and radish.

Salty: The salty flavor is grounding. It can be used when one feels high or scattered, such as over-excited or having difficulty concentrating. Salty foods include sea salt, miso and seaweed.

Sour: Sour draws energy inwards and so can be used wherever there is abnormal fluid leakage or prolapsed organs. Sour food includes lemons, limes and pickles.

Bitter: This is the most cooling flavor and is excellent when there is body-heat or fever. Many herbs used for fevers are extremely bitter indeed. Bitter foods include endive lettuce, alfalfa, bitter melon and rye.

Tao Garden's Organic Gardens

These principles of Five Element nutrition have been incorporated into Tao Garden's kitchen. We grow as much food as possible on site in our organic gardens. In this way, we can preserve the Chi of the food. Much Chi is lost through storage and transportation of foods over long distances.



Fig. 9.8. Tao Garden's Organic Gardens

In addition, many fruits are picked before they have been ripened by the sun, so that they do not rot before they reach the supermarket shelves. At Tao Garden we allow the fruit to ripen naturally in the sun and it is harvested only when it is ready for eating. Some of the food you will eat at Tao Garden will have been picked only hours previously. This is called living food as its life-force energy is flourishing.



Fig. 9.9. Tao Garden's Kwan Yin Dining Hall

See the cells enlarged and this green energy go in and blend with the dirty, black and cloudy energy. See it come out and let it go down into the earth. Dig a hole and bury it there. Tell it, "Don't come back. You will be happy down there". Become aware of the green light and spiral counterclockwise. Spiral down, cleaning out the stress. Clean out your house. Send everything down into the earth. Repeat three, six, nine, thirty six or one hundred and eight times. This depends on how much sick energy you are dealing with in your body.

Green:



Fig. 4.41 *Clean with green.*

Green cleans and detoxifies all of the body's cells. Green Chi is mild and safe. Green Chi is used for cleansing, and as a decongestant for diseased parts. It 'loosens' the area. The light green Chi is used to break down dirty or diseased energy, like a detergent is used for washing clothes or dishes. Afterwards, the cells will be rinsed with blue light, like clean water is used to rinse the detergent and residue from clothes or dishes.

Throat Center Green

Be aware of the liver's green color, the throat and the forest. Breathe into the throat, feel yourself breathing in the green light. Guide it down to the Tan Tien, blend and move it up to the heart and the crown.

Project it to the universe; spiral and let it multiply.

Channel one direct line down to the student, one to your crown and one to your palm.



Fig. 4.42 *Blend Green Chi into the Three Tan Tiens - project to the Universe, multiply and bring the Energy back down to the Student.*

Breakfast

Before Breakfast: Upon arising, drink two ounces of any one of the following juices: apple, grape, cherry fig, prune; mixed with four ounces of pure water. Or, you may drink your favorite herb tea. Follow this with a light internal exercise program, deep breathing and a short morning meditation.

Breakfast: If not truly hungry for a protein or grain breakfast, eat a piece of fruit, such as apples, pears, peaches, berries, grapes. Eat melons alone. Breakfast of Brunch Suggested Choices:

1. Seed or nut milk (germinated/soaked overnight), with berries, apples, peaches etc. Best in summer.
2. Whole grain cereal with slice of rye or wheat wheat bread, and four ounces of cereal grain beverage. Best in cool or moderate weather.
3. Low fat cottage cheese, yogurt, buttermilk, with sub-acid fruit. Best in summer.
4. Oatmeal cooked with a few raisins (soaked overnight), and a slice of corn bread. Best in cool weather.
5. Whole grain granola cereal. Pour warm water over cereal, add ¼ teaspoon licorice powder, lecithin granules, fresh wheat germ flakes; mix contents; cover bowl and let stand 10 minutes. Eat and enjoy. Best in cool to moderate weather.

At Tao Garden we strive to make breakfast the best start to the day. From 7 a.m. to 9 a.m. the stomach is active, and from 9 a.m. to 11 a.m. the Spleen-Pancreas. These are the main organs involved in digestion and in balancing blood sugar. If the wrong food is taken at this time, digestion become sluggish and blood-sugar levels may begin to rise and fall too fast, leading to energy levels crashing.

Breakfast Bad Habits: Minimize hidden sugars: check your cereal, bread and spread ingredient lists. Minimize other sugars: if your blood-sugar levels tend to crash, watch out not to eat too much fruit and fruit juice for breakfast. Minimize heavy oils: cooked foods can be cooked in broth or grilled rather than fried in a lot of oil. If you eat bread, choose an unrefined variety, preferably without yeast.

Breakfast Guidelines: If your digestion is weak, choose warm foods for breakfast. If you are cleansing, choose fruit. Use only sugar-free jams and spreads. Make or buy breads with wholegrain flours. Goat's dairy is easier to digest than cow's dairy. If you choose cow dairy, opt for organic varieties.

Lunch or Dinner Menu

Vegetable salad (raw, best in warm weather), natural complex carbohydrate (grains and legumes) as specified and your favorite health drink.

Salad Suggestions (Raw): Sweet Red Peppers, Green Peppers, Celery, Cucumber, Tomatoes (Sparingly), Onions and Garlic. Romaine, Bib or Boston Lettuce, Alfalfa, Mung or other Sprouts Steamed Beets, Avocado (Sparingly) Wheat Grass.

Complex Carbohydrates:
Grains: Rice, Barley, Buckwheat, Rye, Wheat, Millet, Oats, Corn.
Legumes: Lima, Soybeans, Aduki, Navy, Pinto, Kidney Beans, Split Peas, Lentils, Chick Peas, etc.
Whole Grain Breads: Wheat, Rye, Corn, Bran Muffins, Rye Crisp.
Sandwich Spreads: Tofu, Sesame, Tahini, Humus.
Soups: Vegetable Broth, Miso Soup, Bean Soup, Pea or Lentil Soup, Barley Soup, Mushroom Soup, etc.
Health Beverages: Fresh Raw Vegetable Juice, Grain Beverages, Herbal Teas. Beverages should be salivated thoroughly before swallowing; two to 4 ounces after meals is sufficient. Lunch can be interchanged with dinner meal; be flexible.

Mid-Afternoon Snack (If Hungry Only)

Any health beverage of your choice, fresh carrot or celery juice, or any fruit in season.

Dinner (For Noon or Evening)

Raw vegetable salad (in warm weather), one or two steamed vegetables. Vegetable juice one-half hour before dinner, legume or vegetable soup, grains and beans.

Steamed or Baked Vegetables: Corn, String Beans, Sauerkraut Cauliflower, Asparagus, Beets & Greens, Endive, Zucchini, Squash, Onions, Broccoli, Carrots, Turnips, Peas, Brussels Sprouts, Yam, Artichokes, Kale, Swiss Chard, Summer Squash, Dandelion Greens, Mushrooms (Sparingly), Celery, Okra, Potato (Sparingly).

Protein and Carbohydrate: If you are on a transition diet away from meat products, use only lean meats two or three times per week, such as: white fish, halibut, trout, chicken. Avoid pork, beef or any other high fat meats. Eggs: two to three times per week.
Lacto-Vegetarians: Buttermilk, Goat Milk, Skim Milk, Cheese, (Vegetable Rennet), Yogurt, Kefir, Clabbered Milk, Cottage Cheese.
Use High Fat Dairy Sparingly: Cheddar, Muenster, Edam and Swiss. If you can maintain good health without these foods, do so.
Complete Vegetarians/Vegans (Vegetable Proteins): All Legumes, Beans, Soybeans, Tofu, Miso, Sunflower, Sesame, Pumpkin Seeds, Almonds and other Nuts (Germinated), Wheatgrass, sprouts, Peanuts, Buckwheat, Alfalfa, Spirulina, Seaweed Products.

Legume & Grain Combinations for Complete Proteins Meals

1. Split Pea or Lentil Soup with Whole Grain Bread
2. Beans and Corn Bread
3. Chickpea Felafel with Whole Grain Pita Bread
4. Beans and Rice
5. Whole Grain Spaghetti with Chickpea Balls
6. Pea Soup with Corn Bread
7. Buckwheat and Lima Beans
8. Tempheh (Soy) and Millet
9. Tofu Spread and Rye Bread

Hot Weather Grains: Corn, Red Millet, Long Grain Brown Rice
Cold Weather Grains: Buckwheat, Oatmeal, Short Grain Brown Rice, Barley
Temperate Weather Grains: Wheat, Rye, and Yellow Millet

Cold Weather Menu Samples

Mornings: Cooked Cereals, Cream of Wheat, Rye, Millet, Rice; Oatmeal; 7 Grain Cereal, Whole Wheat or Buckwheat Pancakes/ Waffles; Brown Rice, Bread Ohsawa Loaf, Drop Biscuits, Muffins.

Scrambled Tofu or Tempeh; Tofu Bread Pudding; Marinated Fried Tofu; Baked Stuffed Apple, Baked Potato with Gamasio; Beans.
Mid-Day: Soups, Vegetarian Barley; Miso; Beans; Brown Rice; Leek; Chowder. Sandwiches Spreads: Humus; Tofu; Kidney Bean; Bulghur; Pita Bread Stuffings: Spreads & Sprouts; Cooked Grains with Beans and Veggy Burgers. All leftovers for quick & easy lunch.
Evening: Soups, Vegetables Stir Fried, Sauteed, Steamed, Curried; Arame/Carrot; Sesamed Scallion; Stuffed Squash; Baked Squash; Tempura. Casseroles, Baked Cheese Spaghetti; Chili; Rice Curry; Pasta with Sauce. Soy Dishes, Tofu Quiche; Tofu Lasagne; Stroganoff; Baked Tempeh with Nutritional Yeast; Tofu Enchilladas. Grains & Beans; Nut Loaves; Whole Wheat Pizza.

Warm Weather Menu Samples

Mornings: Fruit or Fresh Fruit Compote; Vegetable Juice; Smoothie; Kelloggs Nutri Grain Cereal; Granola; Seed or Nut Milk (With Fruit, Cereal or Alone); Rice or Bread Pudding; Applesauce.
Mid-Day: Soups, Burgers, Stuffed Tomatoes, Felafel. Salads: Carrot-Raisin; Cucumber Onion; Tabbouli; 3 Bean Dish; Macaroni or Potato; Fresh Fruit Compote; Raw Vegetables with Sprouts. Cold Soups: Gazpacho; Vichyssoise; Fruit Soup.
Evening: Soups, Salads, Grains, Beans and Vegetables. Emphasize Salads and Raw Vegetables.

Fig. 9.8. Recipes for Healing Meals

Cooking Tips

1. Cooking with a loving heart (Cooking Attitudes).
2. Digestion: Fruits 2 hrs; Grains 2-4 hrs; Animal Products 4-8 hrs.
3. Cutting Vegetables determines how they are cooked (Sideways).
4. Combining certain foods while cooking brings out food flavors.
5. Olive oil is too heavy for cooking but is good for salads.
6. Use corn, safflower, or soy oils for cooking; they are lighter.
7. Cooking Heat: Charcoal-Juicy Food; Gas-Neutral; Electric-Dry Food.
8. Cook to the smell for correct timing and adding foods.
9. For steaming food chop food in bigger pieces & thinner in stir fry.

Eating Habit Tips

We all eat too fast. Slowly enjoy your meal. Emotional state is important. Eat with joy and happiness in a good environment. Chew slowly tasting each of the Five Elements activating each organ. Breakfast eat like a King (9:00am-10:00am) (1st meal should be easy to digest); lunch eat like a Prince (1:00pm-2:00pm) (4hrs inbetween each meal); dinner eat like a Pauper (5:00pm-6:00pm). Morning meal should be hot food; body is slow to start; it needs to warm up with grain soup or cereal. Eating fried foods hurts.

Overeating: Eat 1/2 stomach level and double your life. It takes too much energy to digest the food. Eat normally not too much just enough. No liquids with food with exception of thick soups. Drink no iced or cold drinks; drink only herbal tea or hot water. You need warmth to digest the food. Rice (only) soup stops diarrhea. Chinese tea draws out oils, fats and mucus of the body, but it can hurt the heart. Oranges activate lungs.

If your waistband gets tighter with every holiday party, give yourself a ticket for speed eating. It is tempting to blame your aunt’s triple chocolate rum balls and that box of sugar cookies in the office coffee room, but a compelling new study suggests that how fast you eat may be as important as what you put on your plate. Researchers already know that speedeaters are twice as likely to be overweight as those who munch in a leisurely fashion. Scarfing down food reduces the release of appetite regulating hormones into your bloodstream. These chemicals normally tell your brain to get your hand off of those sugar cookies. A new Athens University study had volunteers wolfed down two-and-a-half scoops of ice cream in five minutes; on another, they made the treat last for 30 minutes. The scientists measured blood levels of two types of appetite lowering hormones PYY and GLP-1 before and after, and discovered that when people savored their ice cream slowly, the levels of appetite regulating hormones were 25 to 30 percent higher. PYY and GLP-1 are two of more than a dozen hormones responsible for making you feeling full and satisfied. Other mechanisms, such as stretch receptors in the lining of your stomach, play important roles, too.

Fortunately, we know more than ever about how these checks and balances work and how modern food choices and eating habits can short circuit them. There is no better time to help your body's natural appetite control system. Spoil your dinner with a handful of nuts. Begin with a crunch. Your stomach can stretch only so far take advantage. Filling it with raw veggies activates stretch receptors that signal your brain that you are full. Studies have found that people who start meals with a large, low-cal salad eat 12 percent fewer calories during the meal than those who do not.

Dine in the slow lane. Take small bites, chew thoroughly and put utensils down between bites. Fill your senses and notice the colors, aromas, flavors, textures and temperatures of foods before and while you eat them. Fill your tank only to 80 percent. When you eat till you burst, your stomach feels fuller and fuller for nearly an hour afterward. That is a delayed reaction. Harness your meal when you are just 80 percent full. Wait 20 minutes and you will feel fully satisfied. In Japan, they call this trick ham hachi bu and consider it a key to longevity.

Prayer: Chi Charging your Food

By connecting to heaven and earth you will maximise the wholistic healing potential to your physical and subtle bodies. We recommend that you spend a few minutes placing your hands over your food and sending Chi into it connecting with your Ten Tien with the Universal Forces. Sending good Chi into the foods helps your digestion. Always perform this Sacred Chi Food practice before each meal and thanks after. If there is no energy in your Tan Tien, then there will be no energy to work with. Tan Tien and the Universe means connect your center to the infinite source of the universe, the Tao. When you make the connection you access this power. When you are aware of your Chi, you can direct heavenly light straight into your food and energize your body.

Tao Garden's Healing Recipes

The Professor's Ambrosia - Food of the Gods *(Morning Cereal)*

Ingredients:

Rolled Oats, Millet, Rye or Barley.
Raisins, Apricots, Dates or Pineapple.
Almond, Pumpkin or Sunflower Seeds
Cinnamon
Chopped Apples or Pears.

Recipe:

1. Soak 2-3 Dried Fruits and Seeds or Nuts in a pot of water over night.
2. In the morning boil the mixture with two or three pieces of diced Fresh Fruit and a Seasoning.
3. After the mixture has boiled pull off of the fire and let it sit.
4. Boil 3 cups of water to 1 cup of Whole Grain and add Whole Grain after the water boils and let it sit so the Whole Grain can absorb the hot water or for Rolled Grains soak in water.
5. After Whole or Rolled Grain has absorb the water mix the Fruit Compote together with the soaked Grain; and let it sit to marinate for an hour; and serve with honey if needed.

Tao Garden Cashew Nut Butter:

Ingredients:	Cashew Nuts	200G
	Honey	2 Tsp

Recipe:

1. Dry-Fry the cashew nuts in a wok, continuously moving them around to prevent sticking.
2. Blend together in a coffee grinder.
3. Add a little honey and blend in a normal blender.

Tao Garden Sesame Seed Butter:

Ingredients:	White Sesame Seeds	200G
	Sesame Oil	3 Tsp

Recipe:

1. Dry fry the seeds in a wok, moving around to prevent sticking. Watch as they change colour and take on a golden hue. Remove from the heat before they burn.
2. After they have cooled down a little, blend the seeds in a coffee grinder.
3. Add a little sesame oil and blend in a normal blender.

Tao Garden Fruit Compote: *(Builds Digestive Fire)*

Ingredients:

Apple*	1
Orange*	1
Banana*	1
Raisins	½ Cup
Prunes (chopped)	½ Cup
Chinese red date	½ Cup
Cinnamon	1 Tbsp
Water to cover	

*You may use local seasonal fruit to make your compote.

Recipe:

1. Put everything in a sauce pan over medium flame.
2. Stew together for 20 minutes until it all becomes very soft.
3. Serve warm as an accompaniment to another dish.

Tao Garden Vegetable Broth: *(Mineralizing and Alkalizing)*

Ingredients:

Celery/Coriander Roots	50 G
White/Red Radish	300 G
Pumpkin	300 G
Ginger Root	100 G
Green Papaya	500 G
Onion	1
Pandanus Leaf	50 G
Black Pepper (Dried)	30 G
Soy Bean (Rinsed)	50 G
Radish Pickle	30 G
Water	5 Litres

Recipe:

1. Rinse everything well and cut into big pieces (you can leave seeds and peelings on the vegetables). Bring water to a boil on maximum heat. Add all the vegetables, ground black pepper seed, soy bean, and coriander root to the water.
2. When it is boiling again, reduce heat and simmer for three to four hours with a lid on the pot. Skim the froth off the surface of the liquid from time to time using a strainer. Strain off the liquid to use as broth.

Tao Garden Brown Rice Soup: *(Kao Tom Tan Ya Peut)*

Ingredients:

Cooked Brown Rice	1½ Cups
Vegetable Stock	1 Liter
Sunflower Seeds	1 Tbsp
Pumpkin Seeds	1 Tbsp
Roasted White Sesame	1 Tbsp
Minced Spring Onion	1 Tbsp
Minced Coriander	1 Tbsp
Celery (Fine Chopped)	1 Tbsp
Boiled Corn Kernels	½ Cup
Fried Garlic	1 Tbsp
Soya Sauce/Tamari	4 Tbsp

Recipe:

1. Heat the vegetable stock until it comes to a boil. Add the cooked brown rice, reduce the heat & cook for about 20 min.
2. Add the sunflower seeds, pumpkin seeds, sweet corn kernels, and white sesame and stir in well. Season according to taste with the soya sauce. Add the celery, spring onion, coriander and garlic to the soup and turn off the heat.

Tao Garden Goat's Milk Yoghurt: *(Cooling and Probiotic)*

Ingredients: Goat's Milk
Vita-Ferment Yoghurt
(Yoghurt Starter)

Recipe:

1. Bring goat's milk close to boiling point, 85-95 degrees.
2. Let the milk cool down to 42-45 degrees. Mix in 1 pouch of Vita-Ferment yoghurt bacteria until the ferment is dissolved. Pour into a sterilized container.
3. Close lid and place cultured milk into a 42-45 degree warm place for 6-8 hours.
4. During this time don't move or shake the fermented goat milk.
5. After fermentation period place yoghurt in refrigerator for 12 hours.

Tao Garden Broccoli Soup: *(Calming and Moves Stagnant Chi)*

Ingredients:

Vegetable Broth	2½ Cups
Broccoli	3 Cups
Himalayan Rock Salt	1 Tsp
Ground Pepper	½ Tsp
Onion	1
Butter	1 Tbsp

Recipe:

1. Cook the chopped onion in the butter over a high heat.
2. Add the broccoli cut into small pieces.
3. Add the vegetable broth, salt and pepper.
4. Cook until the vegetables are soft.
5. Blend to a smooth consistency.

Tao Garden Tom Yam Soup: *(Stimulates Stagnant Chi)*

Ingredients:

Vegetable Broth	6 Cups
Coriander Root	6 Pieces
Shallots	8 Bulbs
Lemongrass	2 Sticks
Mushrooms (3)	2 Cups
Kaffir Lime Leaf	2 Leaves
Small Red Chili	4
Coriander Leaf	1 Sprig
Soya Sauce	2 Tbsp
Lime Juice	2 Tbsp

Recipe:

1. Put the vegetable broth over a medium flame until it begins to boil.
2. Add the soya sauce and lime juice to taste.
3. Add the coriander root, shallots, lemongrass, kaffir lime and chili. Add the three types of mushrooms.
4. Cook together and serve with a sprig of coriander placed on top.



Be aware of the liver, the gall bladder, the forest and the throat breathing.

Be aware of the green light in the universe. Let the light come in and blend in the Tan Tien, up to the heart to blend with the compassion in the heart, and up to the crown.

Project the light up to the universe. See it spiral and let it multiply.

Always keep your Lower Tan Tien Fire warm. **Spiral in your Tan Tien and spiral the energy down to the student.** Spiral 1,000 revolutions per minute, 10,000, 30,000 and 60,000.

Fig. 4.43 *Draw down the Green Light from the Universe.*

Cleanse and Remove Sickness

Extend your arms up, with palms facing the heavens. Use one hand to spiral the green force down. The other hand holds the position and connects to the universe. Let this big pool of green light in the universe spiral down – through your community, your home and then into your crown.

Let the Green light blend into the cells and bond with sickness and toxins. Let the green light bring the sickness out of the cells and flow down to the center of the earth.

Dig a hole and bury it. Give the command: "Don't come back. You will be happy down there. You will be transformed into good Chi." Smile. Always smile.

Repeat it six, nine or eighteen times. For people who are very sick, who have cancer or may be terminally ill, you can do this two or three hundred times.



Fig. 4.44 *Green Light bonds with the Sickness and Toxins before returning them to the Earth.*

Tao Garden Pumpkin Soup: *(Builds Digestive Fire)*

Ingredients:

Pumpkin	500 G
Onion	100 G
Butter	2 Tbsp
Vegetable Stock	1½ Liters
Light Soy Sauce	To Taste

Recipe:

1. Clean the pumpkin and chop into pieces.
2. Stir-fry the onion in the butter (those on an oil-free diet can soften the onion by cooking it in a little water).
3. Add the vegetable stock and pumpkin.
4. Boil until the pumpkin is soft. Add soya sauce to taste.
5. Allow to cool slightly and then process in a blender until smooth. Heat until hot and serve.

Tao Garden Green Papaya Salad: *(Anti-Parasite Remedy)*

Ingredients:

Unripe Papaya,	250G
Carrot	30G
Tomato	50G
Garlic	2
Chili	2
Peanuts (Optional)	50G
Lime	2 Tbsp
Soybean Sauce	2 Tbsp
Tamarind Sauce	1 Tbsp
Palm Sugar	½ Tbsp
String Beans	3

Recipe:

1. Peel and shred fresh green papaya. Slice tomatoes thinly.
2. In a clay mortar, pound the fresh chilies (whole), yard-long beans, and garlic. Add string beans, sliced tomato, and roasted peanuts, and pound lightly (do not over-crush).
3. Add soy sauce, tamarind, palm sugar and lime juice.
4. Add these items spoon-by-spoon, and taste as you go. Lightly pound (optional). Add shredded papaya and carrot and pound together until mixed well. Serve on a dish with fresh cabbage and string beans on the side.

Tao Garden Stir-Fried Mixed Vegetables: *(Easily Digestible)*

Ingredients:

Mixed Vegetables	3 Cups
Coconut/Sesame Oil	2 Tbsp
Vegetable Stock	2 Tbsp
Kikkoman Soya Sauce	To Taste
Fresh Cane Juice	To Taste
Garlic (Optional)	½ Tsp
Cashew Nuts	½ Cup

Recipe:

1. Wash and prepare your vegetables. There are many different ways to cut your vegetables, each giving different energetic properties. Cutting vegetables energizes them (as you add some of your Chi as you cut them). Smaller pieces have more energy, making grated vegetables highly energizing. Whole vegetables retain their wholeness and complete energy, and will take longer to cook.
2. Pour a little oil & vegetable broth into a wok over a high heat.
3. When the mixture is hot, add the vegetables and condiments, and stir with a wooden spatula. Keep the vegetables moving so that they do not stick. Cook for a few minutes and serve whilst the vegetables are still warm.

Tao Garden Rice: *(Balancing)*

Ingredients:

Rice* (Rinsed)	1	Cup
Cold Water	2	Cups
Himalayan Rock Salt	¼	Tsp
Mixed Seeds (Optional)	½	Cup

*(Brown, Jasmine, Gac or White)

Recipe:

1. It is preferable to soak the rice (or any grain) in water for 8-12 hours before cooking. This breaks down the enzyme-inhibitors and makes the grain more alkalizing. Place the rice, water and salt into a pan. Cover with a tight-fitting lid and bring to a boil over full heat.
2. Turn heat to low and simmer until the water has been absorbed (roughly 12 minutes for white; 20 minutes for brown)
3. Stir in the mixed seeds if desired and serve hot.

Tao Garden Baked Fish (Turmeric): *(Anti-Inflammatory)*

Ingredients:

Fresh Filleted Fish	1 Medium
Turmeric	1 Tsp
Galangal	1 Tsp
Garlic	1 Clove
Sweet Chili	2
Lemon Grass	1 Tsp
Soya Sauce	1 Tbsp

Recipe:

1. Preheat the oven to 220°F.
2. Blend the turmeric, galangal, garlic, lemongrass and one of the sweet chilies in the soya sauce. Cut three long diagonal lines along the length of the fish, on both sides.
3. Pour all of the sauce over the fish and put into a preheated oven in a baking tray (lined aluminum foil). Bake for one hour.
4. Slice the remaining sweet chili and add over the top of the fish and serve.

Tao Garden Curried Chicken (String Beans): *(Warming)*

Ingredients:

Chicken (Breast, No Skin)	300	G
Curry Paste	1½	Tbsp
Sugar Cane	½	Tbsp
Soya Sauce	½	Tbsp
Chicken Stock Water	½	Cup
String Beans	200	G
Vegetable Oil (Optional)	2	Tbsp
Kaffir Leaves	3	
Red Pepper (Sliced)	1	

Recipe:

1. Heat the oil OR a small amount of the chicken stock (for an oil-free version). Add curry paste, sugar cane, and soy sauce.
2. Heat at low temperature.
3. Add chicken and (the rest of) the stock water.
4. Increase to medium temperature and cook until the water has evaporated. Add string bean, kaffir leaf, and red pepper.
5. Continue to cook until beans begin to get a little soft (not too long). Serve with rice.

Tao Garden Fried Eggelant (Tofu): *(Moves Stagnant Blood)*

Ingredients:

Firm Tofu	250	G
Green Eggplants	2	Large
Miso Paste	2	Tbsp
Unrefined Brown Sugar	½	Tbsp
Freshly Ground Pepper	½	Tsp
Vegetable Stock	3	Tbsp
Chilies (Cut Diagonally)	5	Piece
Fresh Sweet Basil Leaves	10	
Soya Sauce		To Tas
Cooking Oil	1	Tbsp

Recipe:

1. Cut the eggplants into long strips and cover in salt. Leave for 20 minutes and then rinse the salt off.
2. Grill the eggplant (both sides) until it is soft. Set to one side.
3. Cut the tofu into 2.5 cm cubes and steam until cooked. Stir-fry the miso paste in hot oil until fragrant. Add soya sauce, pepper, vegetable stock, steamed tofu and eggplant.
4. Add chilies and basil, stir and serve.

Tao Garden Fried Noodles (Pad Thai): *(Cell Builder)*

Ingredients:

Rice Noodles	50	G
Tofu, Shrimp or Egg	100	G
Garlic (Minced)	1	Tsp
Shallot (Minced)	1	Tbsp
Sesame Oil	3	Tbsp
Tamarind Juice	3	Tbsp
Crushed Peanuts	1	Tbsp
Chinese Green Chives	1	Tbsp
Ground Chili Pepper	½	Tbsp
Chicken/Vegetable Broth	2	Tbsp

Recipe:

1. Soak dry noodles (15 min.). Chop tofu, chives. Rinse the bean sprouts; mince shallots and garlic together.
2. Fry the shallots, garlic, tofu and stir them until they start to brown. Add broth, tamarind juice & chili pepper. Stir. Crack the egg onto the wok & scramble. Fold egg into the noodles.
3. Stir adding bean sprouts, chives a few more times.
4. Pour onto a serving plate and sprinkle with crushed peanuts.

Tao Garden Salad Dressings: (*Moistens and Enhances Flavor)*

Ingredients:

Tamarind Sauce

Tamarind Paste
Coconut Milk
Miso Paste

Ginger Sauce

Minced Ginger
Sesame Oil
Onion
Kikkoman Sauce
Soya Bean Paste

Mango Sauce

Mango (Ripe)
Chili Sauce
Raw Cane Juice/Maple Syrup
Himalayan Rock Salt
Lemon Juice

Passion Fruit Sauce

Passion Fruit Juice (Juice only; not the Seeds)
Chili Sauce
Raw Cane Juice/Maple Syrup
Himalayan Rock Salt
Lemon Juice



Sesame Sauce

Sesame Spread
Water
Himalayan Rock Salt
Lemon Juice

The Professor's Confection Sauce

1 Bunch of Green Onions-Chopped in Food Processor
1 Cup of Water
1 Cup of Tamari
1 Cup of Safflower Oil
3 Tablespoons of Tahini
Juice of 1 Lemon
Few Dashes of Cayenne
2 Tablespoons of Honey
Blend All Ingredients in Food Processor and Chill

Tao Garden Salad Toppings: *(To your Own Taste)*

Ingredients:

Pumpkin Seeds *(Soaked for 4 Hours-Drained)*
Rich in zinc and thus helpful for impotency, prostate swelling, bladder problems, parasites.

Sunflower Seeds*(Soaked for 4 Hours-Drained)*
Chi energy tonic, lubricates intestines and clears constipation.

Garlic
Expels worms and parasites, reduces candida clears colds and other infections, detoxifies body. Use cautiously can cause over heating.

Ginger
Aids digestion by boosting the digestive fire (Kidney Yang) and for any cold condition. Use cautiously can cause over heating.

Turmeric Root
Anti-inflammatory and anti-oxidant qualities, protects liver from toxins, helps break down tumors. Good for gallbladder cleanse.

Dried Seaweed and Sesame
Provides a very mineral-rich alternative to salt. Sesame seeds are extremely rich in calcium providing non-dairy source of minerals. Increases alkalinity of body, assists in elimination of toxins.

Limes/Lemons
Highly alkaline forming once digested for balancing body pH & removing toxins. Good for liver and gallbladder cleansing and move stagnant liver Chi.

Note: Experiment with local nuts, seeds, herbs and roots to add to your salads.

The Professor's Penetrating Split Pea Soup:

Ingredients:

Green/Yellow Split Peas	2	Cups
Water	4	Cups
Onion, Sliced	1	Med.
Carrots, Diced	2	Med.
Celery	2	Stalks
Water	1	Cup
other Vegetables as Desired		

Recipe:

1. Cook peas and onion in 4 cups of water until soft (about 35 minutes). Separately, cook together carrots, celery and other vegetables in 1 cup of water. (20 minutes)
2. Puree peas and combine with cooked vegetables. Serve garnished with chopped parsley.

The Professor's Enervatizing Gazpacho:

Ingredients:

Carrot	1	
Safflower Or Olive Oil	½	Cup
Celery	2	Stalks
Vinegar (Apple Cider)	2	Tbsp
Garlic, Minced	2	Cloves
Whole Cumin	½	Tbsp
Fresh Tomato	2	Cup
Tamari	1	Tbsp
Parsley	2	Springs
Tofu, Cubed	1½	
Pepper, To Taste		

Recipe:

1. At high speed, blend the carrot, celery, garlic, 1 cup tomato and parsley. Pour into bowl. Next, blend lemon juice, oil, vinegar, pepper, cumin, tamari & 1 cup tomato; add to first mixture.
2. Add some sliced zucchini & red pepper, along with the tofu cubes. Refrigerate. Garnish with finely sliced green onions.

The Professor's Vitalizing Humus Spread:

Ingredients:

Raw Chickpeas	1½	Cup
Tahini	1/8	Cup
Garlic, Minced	3	Cloves
Parsley Flakes (½ C Fresh)	3	Tbsp
Salt	1½	Tbsp
Chives Or Basil	2	Tbsp
Tamari	½	Tbsp
Cayenne	1/8	Tbsp
Lemon	2	
Scallions, Minced	¼	Cup

Recipe:

1. Soak chickpeas overnight; boil until soft (45 min.).
2. Cool the beans, then mash to a thick paste.
3. Combine everything and chill.

The Professor's Confection Whole Wheat Pizza:

Ingredients:

Dry Yeast	1	Pkg.
Unbleached Flour	1¼	Cup
Whole Wheat Flour	¾	Cup
Sesame Seeds	¼	Cup
Soy Flour Sift Together	¼	Cup

Recipe:

1. Combine: 1/3 Cup warm water, 2 Tbsp oil, ¼ Cup tofu.
2. Knead; roll out. Add your favorite spaghetti sauce with extra tomato paste to thicken.
3. Garnish with sauteed mushrooms, garlic, onions, peppers, tofu and sun cheese.
4. Bake at 400 ° for 20 minutes.

The Professor's Clarification Lemonade:

Ingredients:

Lemon	1	
Organic Maple Syrup	1	Tbsp
Cayenne	1/8	Tbsp
Pure Water	1	Glass

Recipe:

1. Squeeze Lemon into glass of pure water with Syrup and Cayenne.

The Professor's Liberation Lima Bean Soup:

Ingredients:

Lima Beans	1	Cup
Garlic, Minced	3	Cloves
Scallions, Minced	1	Cup
Pure Water	3	Cups

Recipe:

1. Soak Lima Beans over night and boil with chopped Garlic and Scallions. Let simmer and cool then eat.

The Professor's Perfection Thai Coconut Ice Cream:

Ingredients:

Fresh Coconut Milk	1	Cup
Fresh Coconut Meat	80	G
Sugar Cane	½	Cup
Salt	¼	Tbsp
Pure Water	¼	Cup

Recipe:

1. Mix all Ingredients together and Freeze.

The Professor's Titillation Dip and Hordorves:

Ingredients:

Dip:		
Organic Almond Butter	1	Bowl
Lemon (Squeeze)	1	
Dr. Bragg's Amino Acids	¼	Cup
Hordorves:		
Dried Smoked Salmon	½	Cup
Pickle Cucumbers	½	Cup
Daicon (Chopped)	½	Cup
Green Onions	½	Cup
Radishes	½	Cup
Boiled Scrimp	½	Cup
Celery	6	Stocks
Carrots	6	Sticks

Recipe:

1. Mix all ingredients for dip and dip with vegetables and fish.

Tao Garden Mung Beans: *(Thua Khiaw Tom Nam Taan)*

Ingredients:

Mung Beans	1	Cup
Unrefined Brown Sugar	¼	Cup
Ginger Root (Chopped)	2	Tbsp
Water	2	Cups

Recipe:

1. Soak the mung beans over night.
2. Add the beans to water and bring to the boil until the beans are soft.
3. Add the sugar and ginger and continue to stir.
4. Serve warm.

Tao Garden Rice Ball in Coconut Milk: *(Bualoi)*

Ingredients:

Glutinous Rice Flour	350	G
Flour	2	Tbsp
Water	100	G
Coconut Cream	300	G
Palm Sugar	300	G
Pumpkin (Pureed)	200	G
Taro (Steamed/Pureed)	200	G
Coconut Milk	750	G
Himalayan Rock Salt	¼	Tsp

Recipe:

1. Mix the rice flour with enough water to make a firm paste.
2. Mix some rice paste with pumpkin puree, and then mix the rest of the rice paste with the taro puree. Knead well and then form pea-sized balls.
3. Bring a large pot of water to a boil, toss in the balls and remove when they float to the surface. Drain.
4. Bring the coconut cream to a boil, add palm sugar and salt.
5. Stir constantly to prevent it from separating.
6. Add the flour balls.
7. When the mixture returns to a boil, remove from heat.
8. Serve as a dessert in small bowls.

I. Clean with Blue Light

Be aware the blue light, kidney blue. Breathe the blue light into the throat center. Now slowly blend the blue light in the Tan Tien. Blend the blue light in the heart, in the crown and project it up to the universe, spiraling clockwise. Then feel the universe pouring the blue light back down; counterclockwise. Spiral down. Look at the cells and see the blue light, like water, go in to the cells to rinse and clean all the dirty things, down, down, down to the earth. All the way down. Repeat three, six or nine times. Smile.

Blue:



Fig. 4.45 *Rinse with Blue.*

Blue is like cold water; it has the yin power to dissolve all kinds of negative energy and sickness. It has an inhibiting effect. Blue yin energy is the opposite of red yang, which has a strengthening and stimulating effect. Blue has a cooling effect; it can reduce pain, inflammation and can help blood to clot. It stops bleeding and reduces fever. It can help to induce rest and sleep.

Throat Center Blue

Be aware of the kidneys' blue color and breathe the blue light into your throat. Guide it down to the Tan Tien, blend and move back up to the 'heart of compassion' and then the crown.

Project up to the universe, spiral and let it multiply.

Channel one direct line down to the student, one to your crown and one to your palm.



Fig. 4.46 *Multiply the Universal Blue Light - guide the Energy from the Throat, Heart and Crown into the Universe and back down.*

Tao Garden's Condiments

Fresh Ground Green/Red Chili (Rice Vinegar): Dissolves mucous, warm stomach, and increase blood flow to the face and brain.
Red Chili Sauce: Helps digestion, restores alkaline condition to blood, prevents & cures cancer, provides boosts immune system.
Dry Papaya Seed: Ground seaweed and sesame seed with a little sea salt Good for the brain. Contains iodine (Thyroid/Metabolism).
White Sesame Seeds: High in Calcium and Fatty acids. Contains very similar amounts of essential amino acids to red meat.
Black Sesame Seeds: Strengthens Kidneys, Liver and Brain food.
Wheat Germ: High Protein, High Fiber and contains Vitamin E.
Dry Banana Powder: Nice energy booster and natural sweetener.
Dry Papaya Powder: Aids body to remove undigested proteins and putrefactive materials.
Stevia Leaf: Sweetener that helps the body regulate blood sugar, correcting both high and low blood sugar. It appears to lower blood pressure, without affecting normal blood pressure. It inhibits growth and reproduction of harmful bacteria and infectious organisms, and those causing gum disease and tooth decay. It can also be used in concentrate to help heal skin problems including acne, seborrhea, dermatitis, psoriasis, burns cuts and eczema without scarring.
Pandanus Leaf: Helps to expel urine, nourishes the heart with a cooling effect. Good remedy for diabetes used with cooking & tea.
Olive Oil: Best used raw or lightly heated assists in gall bladder Cleansing (Lime Juice) and heart disease with essential fatty acids.
Coconut Oil: Enables rapid breakdown in digestion. Helpful in thyroid disorders, candida and digestive disorders because of its stable nature can be used at high temperatures.
Sesame Oil: Stable oil can be cooked at higher temperatures without risk of becoming rancid.
Nut Butters: Freshly and powerfully ground each day.

Tao Garden's Organic Fresh Sprouts

Adzuki: 25% Protein, High in Calcium, Niacin, Iron & Amino Acids.
Alfalfa: 35% Protein, Chlorophyll, Vitamins A, B, C, D, E, F, K, U.
Buckwheat: 12% Protein, High in Lecithin, Rutin and Minerals.
Fenugreek: Blood Liver and Kidney Cleanser. Mucus Remover.
Garbanzo: 20% Protein. High in Iron, Calcium, Vitamins A and B.
Lentil: 25% Protein, Vitamin E, Iron Phosphorus, C & B.
Peas: 22% Protein, Magnesium, Chlorophyll and Amino Acids.
Pumpkin: 30% Protein, High in B Vitamins Phosphorus, Iron, Zinc.

Radish: Contains Vitamin C, Calcium and Potassium.
Sesame: 18% Protein (1125 mg's) Vitamin E, B1, Niacin.
Sunflower: Vitamin B Complex, D, E, and all Minerals & Zinc.

Tao Garden's Organic Herbal/Flower Teas and Juices

Safflower (Stevia Leaf): Cleans the Blood, Dilutes it, and lowers cholesterol and high blood pressure. Makes a dark orange tea.
Lemon Grass (Stevia/Pandanus Leaf): Activate the thymus, improving the immune system, and helps ward off mosquitoes and insects. Mildly Green tea.
Ginger (Stevia/Pandanus Leaf): Warms the stomach (aiding digestion) and helps blood flow.
Lingzhi (Stevia Leaf): Lingzhi is a kind of mushroom, said to strengthen the heart.
Chrysanthemum (Buddha Fruit): Helps the throat, clears mucous, & cools the system.
Bael Fruit: Common Thai Herb, which the locals say improves your sex appeal when consumed after dark.
Green Jasmine: Has some caffeine. They will wake you up a bit. It is best not to drink them in the evening.
Mint Leaf: Served with lime.
Ginkgo Biloba: Improves circulation to the brain.
Mulberry (Stevia/Pandanus Leaf): Harmonizes construction, assisting the Middle Burner.
Roselle: When made into a tea is a cooling blood purifier.
Ginger/Ginseng: Freshly prepared daily. Stimulates, Warms and Energizes for fighting off Colds and Influenza Viruses.
Senna: Mild laxative and cleansing drink with one part Senna with three parts of your favourite Fresh Tea to aid Bowel Contractions.
Japliang: Ancient blend of Chinese herbs to assist in Cooling Body.
Soymilk (Pandanus Leaves): Breaks down of Proteins with no additives becomes a digestive delight, refreshing wholesome drink.
Yogurt: Made from Thai Goat's Milk effective in sweetening the levels of beneficial bacteria within the large intestine.
Green Vegetable Juice: Chinese Cabbage, Scallion, Panadus Leaf, Pennywort, Parsley, Lettuce, Sprouts, Lime & Cane Sugar juice for sweetening with Natural Enzymes, Chlorophyll and Vitamins that alkalinizes blood and cleanse system of putrefactive debris.
Rice Milk: Contains the Building Blocks for DNA production. 4-7 Grains are used to produce this Milk, fresh every evening.
Dragon-Eye (Longan): Thai Traditional Way to Sweeten Food. Contains Fruit Sugar and so Blood Sugar is Balanced.



Fig. 9.9. Happiness is like a butterfly. The more you chase it, the more it eludes you. But if you turn your attention to other things, it comes and softly sits on your shoulders. This is the Way of the Tao.

Solar Light, Fresh Oxygen and Pure Water

Ancient cultures worshipped the sun as a manifestation of the All Powerful Creator. They derived great benefit from its healing power. The Greeks and Romans built solariums where the sick came to fast and bask in the relaxing and healing ultraviolet rays of old sol. Ancient physicians were well versed in the knowledge of solar light therapy, in conjunction with fasting, herbs, natural foods, and physical exercise therapy. Pastries, sugar, white flour, and other junk foods were non-existent, therefore healing and rejuvenation through the use of heliotherapy (sun-therapy), herbs, hydrotherapy (water-therapy), and fasting was rapid and effective.

The bright solar orb (Sun) is the most powerful source of energy and light on this planet. It sustains all vegetation food for man and animal life through the process of photosynthesis. It provides us directly with Vitamin D, but it must shine on our bare skin to receive its benefits. Sunlight directly affects the retina of the eye and the hypothalamus which is a control center in the body. The hypothalamus coordinates the nervous system and the pituitary gland, which is known as the master gland because of its influence on the endocrine system. Hormones from these glands directly influence metabolism, growth, sexual activity, and the overall health and vitality of the body. Poor inside lighting is responsible for many physical and mental defects, from nervous conditions to cancer.



Fig. 9.10. Solar Light

Man needs the full spectrum of the sun, not artificial lights. To stay in good health, we must enjoy the outdoors as much as possible. In the wintertime keep your rooms well ventilated to let in as much light and fresh air as possible. Sunglasses are harmful to the eyes, causing fatigue and tension. Pinhole sunglasses are the best as they admit the entire spectrum of sunlight & reduce glare.

Fresh air and sunshine increase the quality and quantity of the blood by 25% within four hours time. Our blood has more hemoglobin in Summer than Winter. Sunlight makes better use of calcium and phosphorus for bone strength and development. Vitamin D from the Sun helps the body's absorption of carbohydrates and the control of body weight. It acts on the pineal gland and in turn on the sex glands releasing nerve hormones which build up the sex glands.

The rays of the sun help us to utilize our vitamins, minerals and proteins and fats. It helps to overcome insomnia. Sunshine assists in overcoming colds, flus, gland infections, TB, anemia, etc. It distributes calcium in the body and it tones up the muscles. Sunlight helps more ailments than all the drugs in the world.

Blondes require less sun than brunettes. Too much sunlight for the blonde people is very exhausting to their nerves and body. The extra pigment in the brunette gives them more protection from the sunlight. Sun dried fruits and vegetables are excellent sun charged foods loaded with nourishment. The sun vitalizes the waters of the sea and the soil of the earth. The ancient Greeks and Romans and the races ages before them used sunlight for healing the sick and diseased, and for preventing ailments. The powerful rays of the sun help to overcome infections, acting as a disinfectant. Fruit trees take in the most sunlight of all food grown, because it is under the sun's rays throughout the year. Sun and air baths help the body to eliminate its waste material daily. Fresh mountain or ocean air is the best tonic known for poor health.

A few weeks in the mountains or on the ocean beach, with the sun shining on the bare skin, is the best known physical and mental rejuvenator of all. Instead of lying in a head shrinker's office, stretch out your nervewracked body on your favorite beach or mountain resort and let nature restore your health.



Fig. 9.11. Breathing and good blood circulation are inseparable. Pure blood built from wholesome food, fresh outdoor oxygen, sunshine and physical exercises that enhance free blood and nerve circulation create superior health and freedom from disease and microbes.

Solar Time Clock

It is well known that sunshine and solar energy are necessary for health and life on earth, but it is not generally recognized that there is quite a difference between morning and afternoon sunshine energy. At 4 p.m., on a clear day, one feels the heat of the sun more than at 8 a.m., although the sun is in the same position or height in the sky. The morning sun is tempered by the earth's atmosphere travelling in the opposite direction. Plants utilize morning sunshine better than that of the afternoon.

From dawn to noon the sun and earth forces are in opposition; the sun is radiating towards the West while the earth is revolving towards the East. All life depends on the opposition of these cosmic forces. From dawn until noon the eliminative powers are at their peak; toxins are neutralized or discarded, putrefaction and fermentation is inhibited, and infections are eliminated. During the pre-dawn hours the cosmic energy is at its lowest and more people die at this time than at any other period of the day, especially sick people and hospital patients.

The solar forces in the afternoon operate in the same direction as the rotating earth, East, and have a constructive and recharging influence; the food eaten at this time is thoroughly assimilated and absorbed into every cell of the body for constructive purposes. Therefore, the logical conclusion is that from morning until noon physical and mental activity should be at its height, and the afternoon and evening hours for comparative rest and relaxation. To do otherwise is to work in opposition to the Law of Rhythm and Universal Yin/Yang Balance. Early daylight hours are Yang; full of energy, activities and heat, while early evening hours are Yin, passive, restful, cool and calm. This is the Law of Nature, and is designed for our health and benefit.

Vibratory Light Waves

One of the greatest scientific achievements of this century has been the discovery of the indispensable health benefits that are locked up in sunlight. Although sunlight seems to us to be merely brilliant white light, actually a single beam of sunlight runs the gamut of all colors. If a ray of light is divided by a prism into its different wave lengths, the prism separates what the human eye recognizes as the seven colors of the scale of Light (Red, Orange, Yellow, Green, Blue, Indigo and Violet).



Fig. 9.12. ***Solar Spectrum:*** *7-Color Scale of life and birth. Rays just beyond the violet have the greatest effect in building vitality and health. Rays beyond red are very useful in reducing congested, inflamed tissues.*

Healing Ultra-Violet

When we speak of healing by sunlight, we mean, principally, the healing partly produced by the violet rays of the invisible band of sunlight, together with the ultra-violet rays of invisible light. We are healed, so to speak, by rays of light too short for the human eye to see. Some of the therapeutic properties of sunlight, it is true, are found in the infrared rays. In rheumatism or arthritis, bathing in sunshine has the effect of breaking up the uric/acid crystals into disposable by-products. The uric/acid from the harmful and tissue-stiffening uric/acid crystals is thrown off through the skin and kidneys and some iron, curiously, is released from the crystals for constructive work in the bloodstream.

This property of the infrared rays (invisible long rays of sunlight) in assisting the assimilation of iron by the system, proves to be valuable in certain cases of anemia. The action of the infra-red rays enables the iron (thus released into the bloodstream) to combine with oxygen in the formation of red blood corpuscles.

Sun Bathing

Wait at least two hours after eating your main meal before taking a sun bath. Use pinhole sunglasses to protect the eyes from glare. Winter sun is just as good, or even better than summer sun. Never sunbathe between the hours of 11 a.m. to 2 p.m., especially during the summer months. Nine to 11 a.m. and 2 p.m. to 5 p.m. are the best periods to expose the entire body to the sun. Make every effort to get out into the sun, bathe in it, walk in it, work in it, learn to love it.

Overexposure to the sun where one becomes red or burned causes a negative reaction in the immune system. Gradual and slow tanning in 5 or 10 minute increments benefits and enhances the body's immune system. The healing power of the sun's ultraviolet light is strongest at midday. One can burn very easy on cloudy days due to ultraviolet rays penetrating the clouds, so be cautious.

Scientific Solar Research

Millions of Americans eat diets heavy in refined and animal fatsthese are the diets loaded with fried food, rich pastries and fatty beef. These people should not be getting a lot of sunlight.

Medical science has determined that one of the causative factors of skin, bowel and breast cancer as well as aging of the skin is a high fat diet. The National Cancer Institute has recommended that Americans cut down on total fat in their diets. Experiments have shown that animals fed a high-fat diet and exposed to intense sunlight suffer considerable cancer whereas it is hard to induce cancer in animals getting the same amount of sunlight but eating a low fat diet.

The sunlight acts as an accelerator of cancer, but not as a cause, when there are a lot of fatty substances in the tissues. Wrinkling works the same way. It is the bad diet that has a lot to do with aging of the skin. (Excessive salt is the biggest culprit.) For extra protection, people should eat diets that are rich in vitamin C, E and carotene, a form of vitamin A. These nutrients help prevent harmful chemical reactions in the skin.

In addition, a diet rich in natural complex carbohydrates, grains, legumes, fresh fruits and vegetables, germinated seeds, nuts and sprouts eaten in season, will maintain the body in optimum health and superior protection from cosmic solar rays. When we learn how to live in har-mony with the laws of nature, we are protected and nourished by all of her elements fire, air, water and earth.

Summary Benefits of Sunlight

1. Lowers high blood pressure and cholesterol levels.
2. Strengthens bones, teeth, hair, nails, lessens cavities by increasing absorption of vitamin D and calcium.
3. Decreases susceptibility to bacteria, germs and virus.
4. Improves the immune system by increasing the amount and activity of anti-bodies and white blood cells; these cells manufacture interferon, an internal substance, which aids in healing diseased conditionsinternal and external.
5. Helps to overcome mental and emotional disturbances.
6. Helps to overcome hypoglycemia by lowering blood sugar.
7. Lessens frequency of colds, flus and tuberculosis.
8. Aids in atherosclerosis, angina, cancer and arthritis cases.
9. Decreases the need for insulin in some diabetics, in conjunction with proper exercise, herbs and diets, etc.
10. Improves over-all health, well-being and physical appearance.

Fresh Outdoor Oxygen

Man can live for weeks without food, a few days without water, but only a few minutes without air. Yet modern man stays cooped up in his home or office practically all day with the windows shut. He breathes in impure, stagnant air and wonders why he feels dopey and sluggish all day long. Have you ever noticed stale air in a room with closed windows after one has slept in it? The air is literally charged with autogenerated body poisons! Many heart attacks could be prevented by sleeping in a room with good oxygen ventilation.

Breathing oxygen sustains our life on earth; when oxygen is withdrawn, existence ceases. The most mentally and physically active people are the ones who breathe deeply and use their lungs to the fullest capacity; they are full of energy, vitality, health and youthfulness at any age! The joy of living glows on their face: their cells, tissues and blood is pumped and energized with life giving oxygen. They enjoy life to the utmost, and people are attracted to their magnetic charm and vitality. Diseased, pale-faced, and anemic people are full of uneliminated toxins and poisons in every cell and organ; they do not obtain sufficient vital oxygen to burn up the wastes; they are weak breathers, with poor health force; they are wasting away in their own waste and do not know it; their thinking is poor due to oxygen starvation and poor circulation. The power-charged vital oxygen breather and exerciser functions on 220 volts with energy to spare. Fresh oxygen, sunshine, wholesome food, and exercise are key factors in building super health force.

When the body possesses a high health force rating, four star and above, one is obtaining plenty of oxygen. There is a joy of living; we are happy to be alive; we bounce out of bed mornings with a song in our heart; depression, envy, hate, jealousy, worries, anxieties flee like phantoms in the night; we enjoy our work, and our creativity is enhanced; we are inspired to master life, and accomplish great deeds without struggle. A person who practices scientific breathing does not shun responsibility; they approach it head on with courage, fortitude and determination; they create and invent, but do not follow fleeting fads. The weak shallow breather, on the other hand, is an escapist, turning to drugs, alcohol, morbidness, perversion, fantasy, self-delusion, fads and the make believe tinsel worldmaterial illusion.



Be aware of the kidneys, the bladder, the oceans and the throat breathing.

Be aware of the blue light in the universe. Let the light come in and blend in the Tan Tien, up to the heart to blend with the compassion and up to the crown.

Project the light up to the universe. See it spiral and let it multiply.

Fig. 4.47 *Draw the Blue Light from the Universe - rinse clean and remove sickness.*

Rinse and Flush

Extend your arms in the air, with palms facing heaven. Use one hand to spiral the green force down. The other hand holds the position and connects to the universe. Let a big pool of green light in the universe spiral down – through your community, your home, and then into your crown.

Let the blue light flush into the cells and flush out sickness and toxins towards the center of the earth.

Dig a hole and bury them. Give the command: “Don’t come back. You will be happy down there. You will be transformed into good Chi.”

Repeat it six, nine or eighteen times. For people who are very sick, who have cancer or who may be terminally ill you can do this up to thirty six, seventy two or one hundred and eight times.



Fig. 4.48 *Blue Light flushes out the sickness and toxins before returning them to the earth.*

Health Benefits of Deep Oxygen Breathing

1. Deep breathing builds a state of high-level health force.
2. Oxygen burns up and eliminates poisons in the lungs and blood stream.
3. Deep breathing builds rich red blood cells.
4. Oxygen breathing helps to overcome the craving of artificial stimulants.
5. The body heals faster when sufficient oxygen is present.
6. It improves the memory and thinking ability and it cleans away the cob webs from the gray matter.
7. It creates healthy circulation to all parts of the body.
8. Helps to overcome anemia and nervous diseases.
9. Deep oxygen breathing improves muscle tone, lung capacity, complexion, flattens the abdomen, reduces wrinkles.
10. Diaphragm deep breathing aids digestion, assimilation and utilization of food.
11. Fresh outdoor oxygen after meals helps us to digest our food efficiently.
12. Deep breathing improves the singing voice and makes the speaking voice beautiful and harmonious.



Fig. 9.13. Living and Breathing the Tao

Oxygen: Blood, Flexibility and Longevity

Why is deep oxygen breathing so necessary to health? Because our very life blood depends upon it. Oxygen is a food for the body and it is absolutely vital in purifying the blood. All the blood in the body passes through the lungs every three-quarters of a minute and then purified and enriched by the oxygen we breathe.

While I was in North Africa I was amazed at the beauty, strength and endurance of their native dancers. One of the tricks which cause wonderful beauty of North African girls is the development of their breathing musclethe diaphragm. Through its action in drawing in large quantities of fresh air and throwing out waste material, these girls have a delicious and fascinating complexion and skin, eyes of desire and the grace and suppleness of a fawn. The blood-making spleen sends out that rich material which causes your cheeks to be red and ruddy; the other blood making cells in the marrow of the bones voraciously grab the oxygen the diaphragm draws in. This is the whole secret for all these exercises. They make you breathe right and all the internal organs get the benefit of this right way of breathing.

They do not get this benefit by the ordinary way of breathing, and this is why so many men and women, when they have lived thirty, forty or more years have stiffened intestines, cemented joints, hardening of the liver, inelastic arteries and veins, cold feet and hands, indigestion and nervous dispositionsin fact, why so many indi-viduals commence to deteriorate at a period in life when they should be in the best of physical and mental state.

The human is an oxygen creature and cannot live without air. We should be outdoors for several hours each day, even in cold weather; dress accordingly. A short walk should be taken in the open air after meals. Perfect digestion and assimi-lation requires lots of oxygen. During sleep there should be maximum ventilation, while making sure you are sufficiently warm.

An abundance of fresh oxygen will make a great difference in the way you feel and think. Get your share! Large cities have a great deal of pollution, but outside air is still better than inside air. Go to the country, or near the lake or ocean whenever possible to obtain clean fresh oxygen.

Training yourself to get More Oxygen

People with plenty of oxygen are the happiest, most influential people of all. They make promoters, master salesmen, orators and organizers of note. There is a trick way of causing your lungs to change their position, to enlarge, and to assimilate more oxygen. This is done, in conjunction with proper deep breathing techniques, by the simple trick of flattening the small of the back. After a few attempts you will see that more air is taken into your lungsthat you walk with the stride of youth.

Stand straight up with your back flat against the wall. Leave no room between your back at any part, and the wall. It requires a little practice, but this brings all internal organs into their correct working position. Learning to walk with the back flat is the trick. Stand, walk, he, and sit with the small of the back flat, and the head held erect, and then oxygen will take care of itself in the body. This carriage throws the hips forward and upward and practice gives grace and greater height to the figure.

Water: Liquid of Life

The finest of all water is that found in fresh fruit, vegetables and juices; it is organic water of the highest quality. Pure rain water sent from the heavens is the cleanest liquid substance that nature has to offer. Rain water is naturally distilled by the clouds and gently sent down in little organic droplets for the benefit of mankind. Cloud distilled rain water is vitalized, energized and aerated by the atmosphere on its journey to earth; it is full of life electricity and magnetism.

Rain water may be caught directly from the clouds and stored in a clean, dry and cool place. The easiest way to collect rain is during the whiter when nature pours her white snow flakes to earth in great quantities. The purest rain or snow is found in the country, ocean or mountains where air pollution is at a minimum.

Pure rain or distilled (aerated) water acts as a solvent and dissolves uric acid, old age salts, mineral deposits and toxic wastes within the body that makes one grow older years too soon. Pure vitalized water is a blood-builder because it picks up the internal filth and cleanses the entire system.



Fig. 9.14. Living in the Tao's Liquid of Light

Distilled and Mineral Water

Factory distilled water is pure lifeless liquid and it lacks the electricity of vitalized rain water. The cosmic rays of the sum and atmosphere are the life-giving principle ingredients that make rain water a superior liquid. However, man-made distilled water may be vitalized and solar-aerated by pouring it from one container to another in the morning sunlight and outdoor atmosphere, thus imparting to it a degree of solar energized electricity. Still waters grown stagnant and lifeless; while moving and churning waters attract to itself more sunlight, oxygen and atmospheric life force. This is the reason that you should aerate your distilled water. You may also store the aerated water in colored glass containers and let it stand in the direct sunlight, covered until ready to use.

The centenarians of high mountain regions utilize pure glacier waters that have been energized by the unpolluted atmosphere; this water is very fast moving and it remains in a constant aerated state for daily use. Mountain or spring water does pick up some inorganic material, but these have always been a part of man's natural environment and are not known to be harmful to the body.

Inorganic mineral water does not cause hard-ened arteries as some people believe. Hardened arteries, and other civilized diseases are the result of a high animal food intake, calamity junk food, stress conditions and lack of pure wholesome natural foods. Cholesterol deposits from wrong foods is the cause of hardened blood vessels and other old age symptoms.

Do not be afraid of a few inorganic mineral sub-stances or a couple of harmless microbes, but on the other hand, be intelligent enough not to use contaminated sewers, stagnant lakes or ponds, or the chemically treated, chlorinated and fluoridated city tap waters. Water which flows in a living stream or which comes to you fresh from the clouds, charged with solar energy and laden with cosmic electricity, is Nature's sweet gift and you cannot improve on it in any way.

Deep mineral waters as a rule are not as good as those which are clear, aerated and fresh. It is a general rule, however, that young and growing persons need to drink water which contains lime, as it builds and hardens the bones and teeth; this is called hard water. It is probable that after a person reaches fifty years of age they will be benefited by drinking soft water, distilled (aerated) or rain water which prevents the rapid solidifying, hardening and aging of the body. Seventy five percent of the human body is composed of water. Water flushes out internal wastes and purifies the cells, tissues and organs.

Drink Only When Thirsty

Liquids should be taken only when thirst is present. Over-consumption of liquids causes polyuria (excessive passage of fluids or frequent urination). It also causes expanded kidneys and intestines, a yin condition. Overconsuming fluids causes the kidneys to excrete urine instead of cleansing the blood and ridding the body of uric acid and metabolic toxins.

Ancient and Modern

There are many modern systems in use, and systems are constantly evolving. Modern research uses experimentations and science as its tools, rather than the observation of Nature, energy and spirit. However, despite such different methodologies, very often the modern systems replicate the findings of the ancient ones.

By understanding the parallels we give ourselves more options, such as new ways of considering old theories. We also open up the opportunity to use modern medical testing procedures to assist us in making accurate diagnosis. We do not need to throw out the old to make way for the new, but can integrate them to bring an even more comprehensive system of Five Element Nutritional Therapy. We will examine several different modern nutritional theories that support the ancient Yin and Yang theory of health.

Metabolic Typing

One sophisticated system of diagnosis and treatment is that of Metabolic Typing. Harold J. Krista and James M. Haig are two of the leading pioneers of this technique. They have proposed a system in which individual differences in metabolism are measured and different dietary therapy is applied to each group.

Tenets of Yin-Yang Metabolics:

1. One man's medicine is another man's poison.
2. Our internal metabolic systems can operate in different ways.
3. Some foods are not healing, no matter what type you are: these are those that are far from being whole: refined and processed foods.
4. When we come more into harmony, we become less of a type and more balanced. Symptoms are reduced, and we become harder to diagnose because there is nothing wrong.

This is a close reflection of the Yin and Yang theory, in which we can look at people along a sliding scale from one extreme to the other. Rather than using the ancient diagnostic techniques. Metabolic Typing uses a series of sophisticated medical tests. These look at various aspects of metabolism.

Just as in Oriental Therapy, there are two main groups that can be distinguished. Another similarity with Oriental Therapy is that these two groups can be further subdivided into an underlying four groups. Balance is also sought as a health ideal in Metabolic Type Five Element Nutrition. To an Five Element Therapy practitioner, balance is the absence of disease plus vibrant health and wellbeing. Kristal and Haig suggest that when such a condition exists, the underlying metabolic state is one in which there is a blood pH of 7.46; slightly alkaline. However, because our metabolic systems operate in different ways, the diet that we have to follow to reach this pH differs from one type to the next. This is because the way that we receive energy from our food can take very different forms.

Metabolic Types

The Metabolic Type method aims to create a slightly alkaline pH (7.46) of the blood for health. This in itself is not a new theory, and there are many advocates of alkalizing. However, what Kristal and Haig discovered is that foods and nutrients that alkalize one group of people actually have the opposite effect on others. They also found that some people have blood that is slightly too acidic, but in others it is too alkaline. It all depends on how people source and metabolize their energy.

Oxidative Types: One group of people, the Oxidative types, gain most of their energy from the metabolism of glucose. There is a system within the body's cells called the Krebs cycle. In this cycle glucose is converted into a useable energy form called ATP. This may be balanced, but in some people this process happens too fast and they process glucose very rapidly. They are called fast-oxidizers, and their blood tends to be too acidic. Others do not process glucose fast enough, and they require more glucose to be fed into the Krebs cycle to produce energy efficiently. These people are called slow-oxidizers and their blood tends to be too alkaline.

Autonomic Types: All humans process energy through the Krebs cycle. However, there are some people who are more affected by the activity of their autonomic nervous system (ANS) than by their oxidative system. This is the part of the nervous system that regulates involuntary metabolic processes.

There are two different divisions of the ANS: the sympathetic and the parasympathetic. The sympathetic nervous system puts us into fight or flight mode, making our body ready to respond hastily to a threat. Some types, called Sympathetic Types, utilize this state as their main form of energy and they have a blood pH that is slightly too acidic. The parasympathetic nervous system puts our body into a state of relaxed and rested. In such a state our body would not be ready to respond to an emergency, but is calm and using very little energy. Some people are governed most by this branch of the ANS, and are called Parasympathetic Types. They have a blood pH that is slightly too alkaline.

Oxidative Systems Two Groups:

Fast-Oxidizers
Slow-Oxidizers

Autonomic Nervous Systems Two Groups:

Sympathetics
Parasympathetics

These are underlying metabolic processes. However, we can also look at health as measured by blood pH.
There are two groups that tend towards having a blood pH that is too acidic:

Fast Oxidisers
Sympathetics

There are two groups that tend towards having a blood pH that is too alkaline:

Slow Oxidizers
Parasympathetics

The aim of Metabolic rebalancing is always the same: to restore blood pH to 7.46. The method however will vary depending on the underlying metabolic system.

Acid and Alkaline Balance

Many nutritionists have realized that blood needs to be slightly alkaline, at 7.46, for health. However, so-called alkalizing diets only seem to work for some people. The Metabolic Type theory states that this is because: The pH effect of a given food is a result of the interaction between the inherent qualities of the food itself and the metabolism of the person eating it. The Oxidative and Autonomic types have different responses to foods, as shown in the table below:

Type	***Food Eaten***	***Response of Blood pH***
Oxidizers	Protein/fat	More acidic
	Carbs	More alkaline
Autonomies	Protein/fat	More alkaline
	Carbs	More acidic

Notice that the two food groups, proteins/fats and carbohydrates are the same two food groups used to rebalance Yin and Yang imbalances in Five Element Dietary Therapy.

Creating Balance

So we can see that the food groups have the same effect on both types of Oxidizer, and the opposite effect on the Autonomic Groups. However, we have also seen that the sub-groups within each type have different pH imbalances: Fast Oxidizers and Sympathetic are too acidic, whereas Slow Oxidizers and Parasympathetics are too alkaline. From this we can work out which food groups will rebalance which types:

- Fast Oxidizers need to become more alkaline, and thus they need to eat more proteins/fats.
- Slow Oxidizers need to become more acidic, and thus they need to eat more carbs.
- Sympathetics need to become more alkaline, and thus they need to eat more protein/fat.
- Parasympathetics need to become more acidic, and thus they need to eat more carbs.

So we can see that both Fast Oxidizers and Sympathetics need more protein/fat; whereas Slow Oxidizers and Parasympathetics need more carbs.

Metabolic Groups

To make this simpler to use, Kristal and Haig grouped together the sub-groups that require the same diet to bring them into rebalance. Thus they placed Fast Oxidizers and Sympathetics into Group I, and Slow Oxidizers and Parasympathetics into Group II.

	Group I	***Group II***
Oxidative Types	Fast Oxidizers	Slow Oxidizers
Autonomic Types	Sympathetics	Parasympathetics

Though the underlying situation is vastly different in each of the four subgroups, the treatment applied is according to the Group. This is similar to Yin and Yang therapy, in which we have two treatment protocols, but four underlying situations.

Dietary Recommendations

The broad outline is that Group I can eat more complex carbohydrates to restore balance. Group II require more quality proteins and fats for their balance.

Complex carbohydrates includes whole grains, vegetables and fruit. However, it does not imply that we should eat the sugars and refined foods that fill our supermarket shelves.

Proteins and Fats includes high quality meats and fish, especially oily fish, Fats must be of high quality, such as fish oils and cold-pressed oils. It does not include poor-quality and rancid oils or deep-fried food.

In addition to these guidelines, there are some specific foods found to have differing effects on blood pH. George Watson, and later Rudolf Wiley, tested many foods and their effects on blood pH. Thus they have created a detailed list of foods for each Group.

J. Charge with Violet Light



Fig.4.49 *Intelligent Luminous Violet*

Luminous Violet has intelligence and can be programmed. The universe is full of violet light, especially the North Star and the Big Dipper. The color of the star of the higher self or soul, above the crown, is also violet light, the Divine or Soul energy.

It has properties of other Chi colors. It has a rapid regenerating effect on damaged organs and nerves. Always use green and blue light before using violet. Violet light develops the crown center, the spiritual core. It is good for psychological ailments as well as for physical deficiencies.

Primordial Force

Turning the three minds into one mind, go deep into the empty space of the cell and deep into the chromosomes, magnify the space as you enter into the DNA and return to the original cells. The empty space is the Wu Chi. When you enter this stage you turn the subconsciousness into consciousness and you can talk to your body and cells. You can change the programming of DNA and RNA.

Ask for the power to see the cells and look at the brain cells spread out into the space. “Brain cells please listen. Clear, Clean, and Bright: fill with violet light and return to normal function”.

Violet Light into the Cells

See violet light. Be aware of your crown. The Tan Tien Chi and the negative Chi all combine in the crown. Extend a violet light up to the universe. See the North Star in the Big Dipper. Tell the student to hold their arms in the air, so that they can funnel the Chi into their personal star. Bring the North Star and the Big Dipper down; hold the handle of the Big Dipper and pour the violet light over the student’s personal star. The higher cells will be programmed. Let the Chi enter the brain and ask for the power to see the brain cells. “Brain cells listen to the command”. If there is sickness in the brain, give the command. “Sickness go away”.

Group I Foods *(Slow Oxidizers & Sympathetics)*

Proteins			***Carbohydrates***			***Fats***
Meat	***Seafood***	***Dairy +***	***Grains***	***Veggies***	***Fruit***	***Oils - Nuts***
Eat Lighter Meats	***Eat White Fish***	***Low Fat Cow/Goat***	***All Whole Grains***	***Emphasize these Foods***	***OK***	***Sparingly***
Buffalo	Catfish	Cheese	Amaranth	Beet	Apples	Almonds
Chicken	Cod	Cottage	Barley	Broccoli	Banana	Cashews
Breast	Flounder	Cheese	Rice	Brussels	Berries	Almond
Ostrich	Haddock	Milk	Buckwheat	Sprouts	Cherries	Butter
Pork	Perch	Yogurt	Com	Cabbage	Citrus	Tahini
Turkey	Scrod	(Plain)	Millet	Chard	Grapes	Olive Oil
Breast	Sole		Quinoa	Cucumber	Melons	
	Trout		Rye	Eggplant	Peaches	***Moderately***
Minimize	Tuna (Lite)	Eggs	Wheat	Garlic	Pineapple	Coconut Oil
Salty Foods	Shrimp		(Very Best)	Kale	Plum	Sesame Oil
Organ Meats	Crab			Greens		Other Nuts
Red Meats	Crayfish		***Minimize***	Lettuce	***Minimize***	Seeds
	Lobster		Oats	Onions	Avocado	
			Beans	Peppers	Artichoke	
			Lentils	Potatoes	Asparagus	***Minimize***
	Minimize			Sprouts	Carrots	Butter
	Oily Fish			Squash	Cauliflower	Fatty Foods
				Tomatoes	Olives	
				Turnip	Peas	
				Yam	Spinach	
				Zucchini		

Eat 3 regular meals per day; eat protein foods at least twice a day; do not eat the same foods every day.

Avoid processed and fast food, and refined or partially hydrogenated vegetable oils; use unrefined oils only.

Eat organic meat, eggs and produce whenever possible; emphasize a variety of vegetables and leafy greens.

Bake, broil, grill, poach or stew animal foods; do not overcook or blacken.

Drink 2 cups of filtered water on arising; drink a total of 6-8 glasses per day.

Minimize alcohol (especially hard liquor) and coffee; completely avoid all sodas (regular or diet).

Avoid all sugar and artificial sweeteners (NutraSweet®, etc.); use stevia, xylitol or lo han instead.

Restrict salt intake; use unrefined sea salts, such as Celtic, Eden, Mediterranean or Real Salt.

Group II Foods *(Fast Oxidizers & Parasympathetics)*

Proteins			***Carbohydrates***			***Fats***
Meat	***Seafood***	***Dairy +***	***Grains***	***Veggies***	***Fruit***	***Oils - Nuts***
Eat Darker Meats	***All OK Oily Fish***	***All OK Cow/Goat***	***OK in Moderation***	***Emphasize these Foods***	***OK in Moderation***	***OK***
Beef	Anchovies	Cheese	Amaranth	Artichoke	Apples (Tart)	Butter
Buffalo	Caviar/Roe	Cottage	Barley	Asparagus	Granny	Nut Butters
Lamb	Herring	Cheese	Buckwheat	Avocado	Smith	Tahini
Liver	Mackerel	Cream	Corn	Carrots	Pippins	
Kidneys	Salmon	(Full)	Kamut	Cauliflower	Banana	***Oils:***
Ostrich	Sardines	Milk	Millet	Celery	(Firm)	Coconut
Poultry	Tuna (Dark)	Ricotta	Oats	Green Beans	Blueberries	Olive
(Dark)	Crab	Yogurt	Quinoa	Mushrooms	Pears (Firm)	Sesame
Red Meat	Lobster	(Plain)	Rice (Brown)	Olives		
	Shrimp		Rye	Peas		
Minimize	Oyster	***Misc.***	Spelt	Spinach	***Moderately***	***Nuts/Seeds:***
Broccoli	Shellfish	Eggs		Winter	Apricots	Almonds
Potatoes		Beans	***Minimize***	Squash	Berries	Brazils
Mustard		(Dried)	Wheat & All		Plums	Cashews
Greens		Lentils	By-Products	***Moderately***		Pecans
Soft		Tempeh	White Rice	Chard	***Minimize***	Pumpkin
Squashes		Tofu		Green Salads	Citrus Fruits	Sunflower
Tomatoes				Kale	Grapes	Walnuts
Zucchini					Fruit Juice	
Vinegar						

Chapter 10

Three Treasures of the Tao

Psychological Aspects of Yin and Yang

Just as physical objects, food and climate are classified into Yin and Yang, there are also psychological aspects, mental characteristics, societal conditions and individual tendencies of Yin and Yang. Yin and Yang is the Law of Polarity or the Law of Opposites. Nothing can exist except in relation to its opposite. Without mountains there can be no valleys. Without shadows there can be no perception of light. If masculinity only existed we would have no perception of feminine beauty. There would be no such thing as evil unless we were able to compare it with good. Without wisdom, there can be no ignorance. Without age there can be no such thing as youth.

The enlightened (Yin/Yang balanced) person is a realist. He or she knows how to use Yin and Yang to improve their life. He knows there are basically two types of people in this world; the leaders and the followers. If people refuse to become the leader of their own life and circumstances, they become followers. If they will not become masters of their own life and health, then they become slaves to their uncontrolled desires.

By studying the Yin and Yang principles in all its aspects, you will be able to think and see clearly, thereby developing better judgment and supreme wisdom. Of course, if you do not want to think or see clearly, that is your own funeral. If you let others do your thinking for you, do not feel depressed or offended when their thinking turns out to be for their own advantage and to your disadvantage. The shepherd exists solely to fleece his sheep, and all his loving kindness and solicitude for their welfare is necessary to his fattening them for the slaughter.

Balancing your Yin and Yang Forces

A person who is balanced and controlled in all of their Yin and Yang aspects of egoistic, intellectual, motive, emotive, moral and spiritual can write their way to success and happiness. The Extreme/Deficient/Yin and the Extreme/Excessive/Yang person are not in conscious control of their physical and psychological forces.

They are tossed about by outer circumstances because they have unbalanced their physical and mental Yin and Yang polarities. The Yin and Yang balanced individual consciously maintains and flows harmonously with the natural forces of life as daily situations arise. He is poised in every undertaking, whether it be working in a factory or selling insurance. Nothing disturbs his center of balance or his energy. He does not use the forces of nature or his own power to gain an advantage over another person. He knows that any coersion or force will bring dire consequences upon himself and misery for others. The Extreme/Yang person, on the other hand, consciously uses Yin passive people for his own ends, and he creates a Hell on Earth for himself and others.

By doing this, he sets the wheels of cause and effect in motion and eventually reaps what he sows pain, grief and suffering. Taoist wisdom teaches that: The wise man seeks everything in himself; the ignorant man tries to get everything from somebody else. The essential difference between the Controlled/Balanced/Yin and Yang person and the Extreme/Yin and Yang ones is in the degree of conscious awareness. The former consciously balances his inner mind and soul with his outer physical body, while the later is unbalanced and totally controlled by his desires, habits and physical environment. If we enter into a relationship with a controlled attitude, without attachment or possession, we are considered balanced we must also maintain a kind and loving nature. A person is considered Extreme/Yin in a relationship if he possesses, holds, or becomes emotionally crippled with uncontrolled attachment and desire. In most modern day relationships there is the lover (Yin) and the beloved (Yang). The lover pursues and attempts to possess the beloved, who in many cases is indifferent or unattached to the lover. A true relationship is based on mutual love and respect, where both people have totally balanced natures. Emotionalism is a Yin condition not based on true love. An unbalanced relationship is generally emotional, possessive, which develops into jealousy, self-pity and loss of self-confidence.

Yin Temperament

Need someone or something excessively and you will become Extreme/Yin. Let it affect you mentally, physically, emotionally and spiritually and you will become useless to everyone, including yourself. Excessive and uncontrolled desires are the cause of much pain and heartbreak. We fail to see life as it is seeing with tunnel vision to escape universal truths and realities of life. To supress a truth is to give it force beyond endurance. It is easier to realize truth than to supress it in the long run. Essentially we live on a material plane, or in a Yin-type world. There is no such thing as a totally Yang person. Since we live in the Yin world of matter, we have a certain amount of Yin within us merely to keep us alive to adapt to the needs of existence. Thus, right from birth we are trained to be Yin, to be materialists enough to support ourselves. We are trained by society to react Yin to outward circumstances. And since Yin is decay and death, we are schooled more in the art of dependence and confusion (Yin), than in the art of healthful living and clear thinking (Yin-Yang Balance) for ourselves.

Yin reacts uncontrollably to outward conditions. Yin needs. Yin is also dominated. That is the whole mystery of it in a nutshell. Yin is dependent. Crave something uncontrollably, and you are its slave. Psychologists say that you are on your way toward becoming an alcoholic as soon as you tell yourself, I need a drink. Alcohol itself is an extremely Yin substance and it tends to expand or Yinnize the body and brain. Respond to something and you are in sympathy with it; you are a part of it. Respond to worry (Yin) and you will have more worries.

Put yourself in the position of craving, lusting and excessively worrying about money, and you will never get enough of it because you are not ruling money, you are letting money rule you. If you are ruled by money, you are Yin. Excessive miserly greed is extreme Yang. Neither condition is healthy. Money in itself is neither Yang nor Yin it is just a manifestation. It is when you let yourself react to it that it becomes Yin. The right attitude about money is to agree to its worth, but do not crave it excessively and let the world see that you do not lust after it and you will get all you need.

It works 100% if you give it a try.

Creditors are Yang. They have control over your money if you allow it. You are Yin and have created a need for something beyond your immediate capacity to buy. Someone once stated that if you want peace of mind, owe no debts. Balancing your Yin and Yang nature in all of its aspects will automatically lead you to peace of mind. The Way of the Tao is this: to take from those who have more than enough and give to those who do not have enough. Man’s way is to take from those who do not have enough, to give to those who already have too much.

Yin and Yang manipulate each Other

When you ask for sympathy, you are becoming more Yin; you are putting yourself into the power of another. Like attracts like. Feel sorry for yourself (Yin reaction to circumstances) and the only person who will sympathize with you is somebody else who is feeling sorry for himself (Yin). Do not expect a disappointed lover to sympathize with your money troubles, unless he has lost sums of money in his pursuit of love. Few things are sweeter than money love and money. But fortunate is the healthy lover who has money. This explains why those who have suffered much, understand others who are still suffering. The less someone has, the more (in proportion he is likely to give you. The millionaire who is never known suffering or poverty, wil not understand your need for money. Since we exist within material bodies on a material plane we cannot totally escape its manifestation. We affirm a thing by denying it, just as much as we do by accepting it.

Success comes from creating a need in others. For instance, advertising is the biggest business in the world. It depends on its success by making others need (Yin) things, (a lot of which they do not really need). In a business sense advertising is Yang. People who believe the propaganda are Yin. A person in Yin and Yang Balance always uses good judgment in all of his purchases and never gets duped against his will by false advertising. A salesman can sell things to people that they do not really need. In that case, he is Extreme/Yang and you are Extreme/Yin. Allow financial worries to take you over and you cannot possibly lick them. You have become a slave to the dollar. If you worry about security, you will never attain it. There is no such thing as absolute security in this finite ever changing material world. Nothing ever remains the same.

The only true security in this world is to live in harmony with the Tao or the natural laws of life. Everything in life constantly changes; it is dynamic, not static, and the wise person flows smoothly with these changes.

Overcoming Temptations

Consider the temptations of a mystic, sage, monk or holy man. Since the majority of the human race has been trained to be Yin, and is Yin whole-heartedly, there are very few people who can bring themselves to believe that there is, indeed, enlightened and self-realized sages, saints and holy men and women now living on this planet. The world has its own vices (Yin enslavements, Yin needs, Yin habits) and is convinced that the holy person must have his own vices also. Maybe he conceals them, they think, but he still has them. So what do they do? They try to tempt him.

Fig. 10.1. Conserve your powers. Be like the expansive ocean, which quietly absorbs the rivers of the senses. Cravings deplete your inner peace; through them, vital waters are wasted in the barren soil of material things. Wrong desire is the greatest enemy of happiness.

He does not like rich food. Just give me the simple things of life, he informs them. They will tempt him with goodies and try to force him into a craving (Yin) for them. As long as he can honestly reject them, he is safe. No one is forcing the slave to remain the slave. If he's going to retain his vices, if he insists on being dominated by his desires and those of society, there is no hope to help him unless he is willing to be helped. Heaven helps those who help themselves.

Master the Yin and Yang World

If you are a writer, you will have difficulty getting an agent until such time as you no longer need one. An agent will not start handling you for free until you have proved your ability (on your own) to sell scripts. Then he will agree to handle you for a commission, or what he can get out of you and because then he needs (Yin) you.

Take a look at all the slaves of fashion (who try to get you to have your hair clipped off in the latest style) and the slaves of decoration (who try to persuade and seduce you into stocking your house with all sorts of dust-catching objects). It is the women who are independent of fashion who set the fashion and become leaders of fashion. All the latest fashion designers achieved success and reputation by being innovative, creative and unique and not following the trend.

Why do we revere Lincoln, Washington, Einstein, Edison, Shakespeare, etc? Because they dared to be different; to be individualists and being first in their field. They were in complete harmony with their Yin and Yang natures. Set a price on yourself (whether for your services or your integrity) and nobody will want you. Refuse to set a price on yourself and people will swarm on their knees to you because they will know you can be trusted. An Extreme/Yin or Yang person cannot always be trusted. If you are Yin and Yang balanced and demonstrate that you can do without anything, you will have it thrust upon you. Especially demonstrate that you disdain something that the masses lustfully crave, and you will be totally overwhelmed by it, because you will be a challenge to the whole materialistic (Yin) world.

Give someone a gift everyday, and very soon it will lose its meaning. Give it when its least expected and the person will react favorably. Many parents complain, I gave my child everything his little heart desired, and what did I get in return? A child does not necessarily want material things he really wants love, approval and firm, but gentle guidance. Bribe him with gifts and he will despise you forever. Give him love and he will love you forever.

Show a manufacturer that you need his product and he will raise its price. Walk away from his product, be indifferent to it, and he will come running after you. If we continue to allow the oil companies to sell us gas at exorbitant prices, that we need, the price will continue to rise. If everyone in the world stopped using their cars and machines for a week or two, the oil barons would come running after us to buy their oil, dirt cheap. Have you ever found yourself at a table with others who loved to eat rich foods and lived to eat? They will tell you to forget your silly health diet and eat up, you can start back on your diet tomorrow. They are the slave (Yin) to food and want to make sure that you are as much enslaved as they are. Slaves do not want other people to be free. When in Rome, do as the Romans do. If you are surrounded by Yin food gluttons, they will ostracise and deride you if you do not eat and act like them. Yin people dislike others who think for themselves in a controlled Yin and Yang manner. Since they are not free of their rebellious habits, they despise others who are free. A vain nature invites diverting pleasures and must suffer accordingly. If a person is unstable within, he indulges indiscriminately in the pleasures of the world, and thus they have an influence so powerful that he is swept along by them. In this case, it is no longer a question of danger, of good fortune or misfortune. He has given up direction of his own life; what becomes of him depends on chance.

Attitude changes with your Circumstances

The best method of all is to stop needing so much. Stop letting yourself be dominated by outward circumstances. So you have to live without certain modern conveniences for awhile. You will not die. Our ancestors lived on earth for eons of time and they managed to survive nicely, and to healthy and advanced ages also. A philosopher once said that contentment consists not in great wealth, but in few wants. If you develop a little guts and gumption by being more independent of such things, you can easily master this life in due time. He who knows that enough is enough will always have enough.

Strikes succeed because they are controlled by Extreme/Yang forces (the ability to walk away from something) and the manufacturers have to give in (Yin) to the demands (Extreme/Yang) of labor because they need (Yin) the workers to produce their products. As long as your employer needs you, your job is safe. Demand and complain (Extreme/Yin) that you need a raise, and he will pretend that he did not hear you. Demonstrate to him that you are wanted by another company for a higher salary, and he will probably give in to your demands. It seems a general rule that we always get a thing when we no longer want it, when our attitude is indifferent toward it. It is wise to never take anything for granted, because to take a thing for granted is to rely on it and not on the natural forces within yourself therefore to be subject to its domination. You may ask, Why do millionaires continue to make money, if they are not dominated by money and therefore Extreme/Yin. That question answers itself. Most millionaires manage investments and big business deals not because of lack. They made their money to assert their egos, to prove their ideas to themselves first, and to others secondly. They do not worry about making big deals or losing a few thousand dollars here and there. It is all a discussion of theory and inventive reasoning, of out smarting the competitor or getting him to react, meaning forcing him into the position of Extreme/Yin. The money is merely incidental. It's the excitement and adventure of pulling a fast one that motivates him, not security.

To receive relief from the wrong way of living, one must follow the way of the Tao, or lose the chance to gain enlightenment.
A long life is only the blink of an eye. If you seek only material things and earthly pleasures, the mirror will reflect your own pale face and the degeneration of your body. Material things may fill the valley, but possessions cannot last and do not help acquire the things which do not come back.

Becoming a Free Individual

The universal laws of life are exact in their operation. As you sow, so shall you reap. For every action, there is an opposite and equal reaction. It is the law of cause and effect on the physical plane. Plant a rose and you will not get rice. Sow Yin, harvest Yin. Sow hate, harvest hate. Sow friendship, harvest friendship. Sow love, harvest love. Like begets like. Sow war, harvest war. Sow politics, and all you get is more politics. A good man (woman) contributes toward a good family, a good family contributes toward a good nation, good nations contribute toward a good world.

We all have a tendency to let ourselves become slaves; the herd instinct. We all want to follow some sort of leader or authority without question, allowing somebody else to do our thinking for us, and take over our personal responsibilities. We want a certain thing because we've acquired the habit (Yin) of it and we lack discipline and courage to break the habit, whatever it is. Buddha knew the secrets of life when he said desire is the source of all pain.

What the world calls repose, the sage does not. His repose derives from his mental attitude. It becomes the mirror of the universe. Nothing disturbs his tranquility. Hence his repose.

A too strong Extreme/Yang attitude is likely to bring an overwhelming Extreme/Yin reaction in others, perhaps even hatred or destruction. Extremes are to be avoided at all times. The key is to balance your Yin and Yang polarities through proper diet, sufficient exercise, attention to the needs of others, kindness, and spiritual development. Extremes in any endeavor only creates pain, suffer-

The North Star is a major source of violet light.

The Big Dipper is a major source of red and infrared light. Taoists understand that the cup of the Big Dipper gathers all the violet light from the universe. The left hand holds the handle of the big dipper - pour it down to your crown. It then flows down throughout the body.



Fig. 4.50 *Connect with the North Star to receive the Violet Light.*



Fig. 4.51 *Practitioner connects with Universal Violet Light.*

ing, disease and trouble. The idea is to never need anything so badly that you cannot do without it.

The sage cares not for himself but responds to the needs of others. Be good to people who are good. To those who are not good be also good. Thus goodness is achieved. Be sincere to those who are sincere. To people who are not sincere, be also sincere. Thus all shall be sincere and this is the Way of the Tao.

Harmonize your Life with the Tao

Our goal in life is to develop all of our forces mental, physical and spiritual. This will lead us to a true understanding of creation, peace of mind, the sense of beauty and the appreciation of our real inner self. By blending these forces into one we perfect, harmonize and realize the completion of our being. One quality is almost useless without another. Intelligence can be of no real value unless it has physical strength back of it to carry out its ideas. Moral power can be totally ineffective if it lacks the physical strength to carry out its ideals. Inversely, health alone is valueless unless it is accompanied by mental and spiritual development. A criminal may be intelligent, but he is not well-balanced. He lacks the moral and esthetic sense, and he very often is poor in health. Complete wholeness and harmony are necessary for the perfect life.

It takes wisdom and intelligence to follow the path of Yin and Yang. The more these fundamental laws are followed, the more one will be guided in life by the Supreme Force or Creator. The code to this unifying principle is very simple: Moderation and Balance. Following the middle path of life activity and diet and avoiding extremes will automatically create a Yin and Yang balance, leading to harmony in body, happiness in mind and soul and success in life.

Marriage of Truth & Love (Yin & Yang)

In the Divine Mind, Truth and Love are indissolubly wedded. All human undertakings which count for anything exemplify this union, for it is according to the pattern showed to thee in the mount. The forces of evil try to divorce truth and love in the consciousness of men, and to make them believe that truth can be advanced through war and strife, carried on with motives of anger, hatred, revenge, self-interest, or self-justification.

Ever and anon, problems of importance must be discussed and settled in our families, in our business relations, and in the larger negotiations of politics, law, diplomacy, government and religion. In these discussions, let us defeat the one evil through understanding and bearing in mind that, by no amount of argument, however valid, and by no amount of force of any kind, can we successfully promulgate truth and permanently bring to pass the real issue, unless, during our efforts, we purposely and habitually exercise the spirit of good will, right feeling and right purpose.

In dealing with others, reasoning and goodwill are as the wings of a bird. If a bird tries to fly with only one wing, he whirls round and round, to his own confusion, making no headway; but using both wings, he will make much progress in his flight. Only as the male principle, truth, and the female principle, love, are wedded in our consciousness, can we obey the spiritual command: Be fruitful (of righteous thoughts and deeds), and multiply (them), and replenish the earth (with them), and subdue it. Truth will go no further and no faster than love leads as a companion.

Balancing Yin and Yang Qualities

To balance the elements in one individual, it is well to understand that there is no mental characteristic found in men which is wholly absent from women. There is no mental quality found in women which is not possessed in some measure by men. This is on the human plane. On the spiritual plane there is no sex distinction. Spiritual person possesses both the masculine and feminine qualities in balance.

In music, certain notes, when struck separately, make discord. The same notes, when struck together, make harmony. The same law applied to the characteristics here given will bring about like results. In electrophysics and practice the negative and positive currents produce the circuit. The feminine elements above named and the masculine elements, balancing each other, make for harmony, and complete the circuit of life on the human plane. To bring this balance or harmony about, one must get the idea in mind of the two elements under the heading of feminine and masculine, converging into each other. This attitude must be held, and Its opposite denied, until the fusion is complete in consciousness and demonstrated in life and power.

Yin Feminine Qualities	Yang Masculine Qualities

Feeling	is balanced by	Intellect
Love	“	Wisdom
Meekness	“	Self-Value
Caution	“	Courage
Freedom	“	Responsibility
Patience	“	Aggressiveness
Tenderness	“	Stability
Joy	“	Moderation
Faith	“	Understanding
Gentleness	“	Strength
Intuition	“	Logical Reasoning
Generosity	“	Economy
Repose	“	Energy
Zeal	“	Reflection
Ambition	“	Unselfishness
Charity	“	Justice
Candor	“	Tactfulness
Aspiration	“	Judgment
Benevolence	“	Discrimination
Liberty	“	Obedience to Law

Success and health is the perfectly natural culmination of harmonious development. It means a fulfillment of our desires, whether they be in the material or the spiritual world. We know that we cannot fail; if we have completed our development. No earthly force can stop us. If we want health, success and peace, we are certain of achievement, for no one with complete harmony of being can fail It is as impossible to visualize failure as it is to imagine the failure of the sun to appear in the heavens. Let us be thankful and joyful that we have the opportunity to achieve all that we have yearned for during a lifetime. ‘A high purpose is magnetic and attracts rich resources.



Fig. 10.2. The Yin and Yang Within.

Majesty of Inward Calmness

Are you discouraged with life? Do you worry over trifles? Are you full of fear and doubt? Do you make mountains out of molehills? Do you get angry over nothing? Are you nervous and irritable? Are you constantly grumbling, criticizing and complaining? Are you envious of the success of others? Are you plagued by the green-eyed monster jealousy? Do you carry grudges, trying to get even with other people? If you are a slave to any of the above habits, you can never have mental peace and Inward Calm. You must realize that confusion in the mental kingdom disorganizes the body and poisons the blood. The person who cultivates Inward Calm will always possess self-control and be moderate in all phases of living. A well-functioning body imparts vibrant health and Inward Calm. Worry, fear, hate and all negative thoughts lead to enervation and finally to disease. Very few individuals in this world possess that great treasure: Peace of Mind. Would you like to be at peace with yourself and the world over-flowing with joy and happiness? Of course you would. To be poised in both mind and body is the greatest thing in the world. You will be looked up to as a leader and teacher.

Cleansing Power of Forgiveness

Spend a few minutes each night in forgiving everyone who might have committed a transgression against you. Let go of your hates, anxieties, problems, then ask God to lead you in your life. You will find a change in your life for the better. Real calmness will set in. Just as it is necessary to cleanse the physical body through fasting to attain a state of good health, so is it necessary to cleanse the heart. Forgiveness is the best means of cleansing the mind. You will never have perfect health or peace of mind while holding a grudge or seeking revenge. Thoughts are things and they will come back to you just as sure as the sun rises in the East. When you forgive, you release a tremendous amount of tension. As you mentally bless and forgive others, yourself included, a heavy weight will be released from your mental shoulders. As you cleanse your mind of hate, vengence, envy, jealousy, peace and love will flow right in. You will experience a peaceful bliss and feel uplifted. Send out thoughts of love to everyone. Do not go to bed any night feeling that you have an enemy in the world. Forgiveness is the great mental nerve tonic, and is unparalleled in bringing about a state of Inward Calm. No matter how badly anyone has treated you, you must forgive him. If you do not, you are the only one who suffers. This is why the ancient sages and saints have all taught to love one another. Forgiveness cleanses and renews.

Fig. 10.3. Peace and Harmony of the Tao

Peace through Individual Freedom

Each and every day we must extend total freedom to every person in the universe, including our families and close friends. Let them live then own lives. Stop trying to change the world and other people's habits against their will. Let every person make his own decisions, good or bad. No one wants to be fenced in, we all want to be free. The Tao forces no one, for love cannot compel, therefore it is a thing of perfect freedom. Realize that you cannot improve another. He of himself must do the work; all we can do is inspire. This is where the old saying of an example is worth more than a thousand sermons, holds true. The natural way of spreading ideas calls for more than ridding ourselves of name calling, propagandizing, telling others what to think or how to act, and other such actions. It suggests that the soul be cleansed of any such notion, for it is clear that we can no more improve another person than we can alter the heavens above. Quit trying to make carbon copies of others, give them, rather, something to copy.

When you give up the ill-habit of dictating another's life, you open up the channel of love between individuals. Peace will then be yours. You will attract more friends, and your acquaintances and family will find boundless joy and happiness in your presence.

Be Grateful: Live a Life of Cheerfulness

Stop grumbling and complaining. Stop feeling sorry for yourself! Let go of that gloomy attitude. No one likes to be around such a person. Self-pity destroys health and happiness. Instead of complaining about your life and environment, be thankful for what you already possess in life. There are people in far worse circumstances than you! Seek beauty in everyone and everything wherever you may be. The loving, cheerful person beams with vibrant health and happiness. Those who grumble, complain, whine, murmur, criticize and constantly find fault with life, will never have life smile upon them. They are repulsive people and drive from them all the wonderful and beautiful things of life. Conversely, the happy cheerful individual attracts all the grand and lovely things of life. Always remain cheerful. All that we are is the result of what we have thought. It is founded on our thoughts; it is made up of our thoughts. If a man speaks or acts with an evil thought, pain follows him, as a wheel follows the foot of the ox that draws the carriage.

Positive Mental Attitude

Discouragement is a disease. It leads to failure, narcotics, prostitution, gambling and anger; it destroys confidence and faith in oneself. To feel inferior, and to think that you are a nobody, is to be your own worst enemy. Negative thoughts must be overcome if you are seeking a Positive Mental Attitude and an Inward Calm. Keep in mind that you are a child of the Tao. You are the light of the world, a great being. Why not act like one. Perhaps up until now you have failed, or experienced many reverses in your life and you think that you cannot succeed. You can turn things around right now! Failure is no reason to give up. Use failure as a stepping stone to a higher and better achievement. Start again. Never give up. You cannot be defeated unless you allow failure to defeat you. No matter how dark the clouds in your life may be, or how many obstacles may stand in your way, do not give up. Keep on with persistence and determination, and you will succeed beyond your fondest dreams. Stop making excuses. Quit feeling sorry for yourself! Instead, believe that you can and will be a success. Feel deep down in your heart that you are already a complete success! Believe, know and have faith that your dreams will come true. Cultivate a taste for the beautiful classical music. Visit places of culture and refinement and beauty. Make your life beautiful. Spread hope, kindness and sunshine everywhere. If you are discouraged and depressed, give yourself thoughts of confidence, courage and love. Believe in your heart that these wonderful attributes are yours. Make a list of positive inspiring words or phrases; then read them outloud to yourself, especially when feeling discouraged, distressed or blue. Repeat these words with as much feeling and power as you possibly can. The habit of reading outloud to yourself will give you courage, confidence and faith; it will help you to overcome shyness and timidity.



Fig. 10.4. As a wheel follows the foot of the ox that draws the carriage.

Positive, inspiring affirmations implant into your subconscious mind the qualities you require for a successful, harmonious life. Repeat these inspiring affirmations until the subconscious mind picks them up and you actually begin to feel more positive and happy. Then and only then should you discontinue the affirmations for the time being. At first this may take you up to an hour before you feel relaxed and at peace. And afterwards repeat the affirmations only when the inner need arises. This follows the natural rhythm cycle; there is no need to affirm confidence or peace when you are already in those states of consciousness. When you are already in a positive frame of mind, and you continue to affirm more positive thoughts, it causes mental and physical exhaustion. If we affirm positive (Yang), thoughts and actions in the extreme, it always reverts to the other extreme (Yin) tiredness, depression and unhappihess.

The true positive attitude is to be content and balanced, with calm self-controlled emotions neither extremely happy or sad. When reading these positive affirmations do not become over-emotional or over-joyous to the point of losing self-control. Positive thoughts have ten times the power when we have a controlled mental and emotional poise. Be still for a few minutes each day, and feel the presence of the Tao; this will help you to be in control, physically, mentally, emotionally and spiritually, with very little effort. Here is a list of positive words, character building qualities, and affirmations. Repeat them with deep sincerity from your heart and mentally visualize yourself as you wish to be.

1. I am master of my surroundings nothing disturbs me adversely I am Master of my situations.
2. I am well poised, calm and self-controlled always.
3. I surround myself with an atmosphere of shining success, happiness and love.
4. I have perfect mastery over my temper, emotions & passions.
5. I am pure in thought and deed and no evil shall befall me as the Divine is in my body and watches over me.
6. I ask for strength, guidance and to be surrounded by the white light of Divine protection.
7. With the Creator’s help, I am master of my destiny.

We build our future, thought by thought, for good or ill and know it not. Yet so the universe is wrought thought is another name for fate, choose then thy destiny and wait, for love brings love, and hate brings hate.

Words and Qualities that stimulate Positive Thought:
Thankful, Courage, Love, Peace, Strength, Encouragement, Consideration, Tact, Dignity, Politeness, Beauty, Compassion, Joy, Poise, Relax, Cheer, Patience, Honesty, Happiness, Sympathy, Optimistic, Relaxation, Charm, Humility, Health, Virility, Decisiveness, Harmony, Unselfish, Hope, Enthusiasm, Kindness, Tolerance, Forgiveness, Trust, Humor, Understanding, Energy, Gentleness, Bravery, Freedom, Self-Control, Gladness, Dynamic, Power Dependable, Loyalty, Confidence, Mercy, Success, Ease, Sincerity, Alert, Determination, Affection, Faith, Magnetism and Vitality.

These positive traits make it easier on the body to eliminate its toxins, as it relaxes the system, mentally and physically.

Discontinue these Negative Faults and Thoughts:
Hate, Vengence, Fault Finding, Discouragement, Selfishness, Needless Talking, Grumbling, Sorry, Dominating, Gloominess, Anger, Nagging, Inferiority, Self-Pity, Fear, Pessimism, Shouting, Bully, Doubt, Superiority, Grief, Complaining, Jealousy and Greed.

Be courageous. See no evil in another. See only the good and beautiful. Do not even hint at the bad. Charge the atmosphere with sunshine, cheerfulness and loving kindness. You will be rewarded well. Positive traits build the magnetic personality. Negative traits prevent the body from eliminating the toxins properly.

Easy Way to Overcome Worry

Do you constantly worry? Do the smallest problems get you down? Does life seem hopeless? You cannot sleep nights because of your problems, so you worry not only about the problem, but because you cannot sleep. We all know that worry is a great destroyer of health and happiness. But, how many of us can stop worrying about our problems and the problems of the world? If you are a victim of fears and worries, say this to yourself; So what, and your troubles will dwindle in size. Stop tormenting yourself with useless questionings and imaginary doubts. You cannot carry the whole world on your back. Do the best you can with what you have as working tools. Get in harmony with the Laws of life. Love your neighbor and forget about the troubles of the world today. Simply say, So what and fall off to sleep. When morning arrives you will

Bring the violet light down to the student's personal star above their crown. Pause to let the higher cells of the brain reprogram the violet light at the personal star. Continue to spiral the violet light down through the cells of the brain and down through the cells of the whole body.



Fig. 4.52 *Pause to reprogram the Violet Light at the other Person's Personal Star.*



Fig 4.53 *Lead the person and guide them to follow you.*
Tell them to focus on the part of their body that you are working on.

be refreshed and filled with zest for living. Then, your problems can be easily solved, and the imaginary ones will fade out of existence. Give up self-assertion and relax. Let go! Give up all efforts to be important or superior to your fellowman. You will be more in harmony with life if you do. This is a sign of a magnetic personality. No matter what happens to you in life, always be poised and calm; this is the quality of a great person.

A worrier is not a realist; his perceptions are very narrow; he does not have a universal view of life. He or she is dwelling on their own small individual problems, without seeing the whole picture of existence. Those who think broadly are philosophers; they relinquish their small ego to the larger Spiritual Force (the Tao), who creates and sustains the limitless universe.



Fig. 10.5. Winds of Freedom in the Tao

Littleness of Humanity

There are many billions of suns in the sky. Each sun is called a star. Each star is the center of a system that contains many worlds known as planets. Each such world contains millions or billions of people. Our sun is a small star. This earth is a small planet. As compared with the million, billions, trillions of others worlds in the sky, this earth is like a grain of sand on an endless shore. How much more tiny are we in comparison. We worry over small trifles, yet the Great Universe operates in perfect order.

Littleness of Time

That greater vision has seen the earth pass from a state of rock to a state of fertile soil as in the twinkling of an eye; yet it revolved on its axis billions of times, and circled the sun a hundred million years; but this vast lapse seemed as nothing. A century is reeled off so quickly that it is too small a trifle to arrest the attention; yet a woman giving birth to a child looks upon the hours of suffering as an age of duration. But millions are born year in and year out, new beings are opening their eyes to the wonders of earth, they grow, they build, they accomplish gigantic tasks, and they pass on.

His coming is so slight an event in the succession of a thousand generations that there is no way of permanently recording his achievements. The remotest event of history is not six thousand years old; and the earth is more than a hundred million years of age. Cities that contain massive structures will some day be rolled under the crust of this earth, and not one trace of them will be found by the peoples who shall come here six thousand years hence. To the greater eye this world is rushing on with whirling speed; weeks, months, and years are too slight to be counted; nothing but aeons are worthy of attention; and yet an aeon witnesses the rise of races the writing of a few thousand years of history, then the wiping of the slate to erase everything. Seventy years on this planet is in fact no more than the span of life of the germ that is born, grown, aged and dead, all in ten minutes.

Unconcer of the Future

One hundred years from now you will be wholly forgotten. Every year many millions like you pass to their sleep in earth. They have been going and coming for aeons. They will keep coming and going for aeons yet. If your greatest achievements were to over-topple the tasks of the past, they and you would disappear and be wholly lost in the melting changes of time and nature. What is the use of worrying when there is nothing at stake for you? You think and fear that this trifle is fearfully and terribly wrong. The spot on your clothing, the loss of a dollar, the breaking of the glass, the ill remark of an acquaintance, this, that, or something else, racks your mind and depresses your buoyancy. The rich man who loses all his wealth is to be pitied. The calamity that has overtaken you may be worse. But what does it matter? Humanity are but insects, ants that swarm to and fro about the surface of the world. The span of the longest life is but a second of time on the clock of the universe. In a century it will not matter what you win or tose, what you accomplish or suffer. Look upward and outward; now downward and inward. Then you will worry no more. Toothaches, earthquakes, disasters, holocausts are seemingly great evils, but what difference will it make when the surface of the earth is rolled up as a scroll, and a new aeon shall be under way? His (Chuang Tzu's) view is that the real source of worry and confusion is the apparently real world, with all its pressures and entanglements. The truly wise person, realizing that these may well be an illusion, does not take them too seriously. Thus he is free to achieve harmony with nature however it may be. He does not need to worry about obtaining true knowledge about the state of the world. To nourish the mind there is nothing better than to make the desires few.

Hurry, the Scourge of Humanity

The universe never hurries. Nature plans her activities slowly and patiently, without hurry. Hurry always shows a lack of proper planning and method, confusion and anxiety in the mental realm. Hurried and arrogant ambition can ruin the best of projects. The intelligent person never hurries, but is always thoughtful and calm before undertaking the task at hand. Failures usually run full steam into projects, and soon give up in despair; they lack thought and planning. Hurry creates distress, disease, tension and a multitude of physical and mental ills. A hurried, worried and anxious attitude will never give one good health, long life and peace of mind.

A hurried, diseased person relies on pills and drugs to get him well; but this method never gives one good health. Health improvement and main-tenance requires patience, deep thought, study and proper application over a period of time. The ill demand quick release from suffering, and it never comes, because nature works ever so slowly and surely in returning us to health. The hurried person does not care about his health; does not plan his life according to the laws of health, and therefore does not achieve it.

People hurry for wealth, not caring about their health. They seek to attain some ambition to satisfy their ego at the expense of truth and spiritual attainment. Hurry takes us away from the flow of Tao in our lives; it is the opposite of a calm, dignified and poised attitude. Hurried eating causes indiges-tion; and we hurriedly reach for a bottle of pills to cure us.

All great projects in life are the result of slow growth; patient and careful planning; correct and proper action at the right time. The oak takes years to reach maturity, but it lives for decades; weeds sprout and die quickly. We cannot cause the sun to set or rise ahead of its time; it moves in exact cycles. If we desire success we must accept slow growth, and realize that we will reach our goal in due time, after we have paid our dues in proper study and work and patience. We should do the best we can at the moment, and let the future take care of itself. If we fail, we must not "quit", but keep plodding on until we reach the final pinnacle of success. You cannot fail if you do not give up the ship. Approach the goal slowly, inch by inch, and you will always succeed. Since it is impossible to please men in all things, our only care should be to satisfy our own consciences.

Self-Reliance: Key To Success

One can be very self-confident, and yet lack self-reliance. Self-confidence sees the possibilities and opportunities for a person; self-reliance puts them into action or reality. Every soul must work out their own salvation; financially, emotionally, morally, mentally, socially, physically and spiritually. We are judged according to our own acts and accomplishments. We make or break our own selves; no one is out to get us. We can be our own best friend, or our own worst enemy.

All books, all words, all religious teachings, all health teachings are but guides, tools, and theo-ries. The self-reliant individual functions beyond the letter of the word, and he or she relies on the still small voice within. He listens to the advice and teachings of others, but does not follow others blindly, or worship graven imagesmortals, books, statues, organizations, etc. We must learn to save ourselves from our arrogance and ignorance.

Self-reliance seeks to follow no one; and it does not seek a following. He is friendly, compassionate and kind to all. He does not have an axe to grind. The self-reliant one is beyond argument, anger and self-righteousness; he relies on his inner truth to carry him along through life. If we do not rely on ourselves, we drift through life without direction, waiting for someone else to give us a push.

Fig. 10.6. Self-Reliance in the Tao

Opportunities are Self-Made

Opportunities are there for the asking; we must be ready and prepared for them at the right time, and then take the proper action. We must develop our own talents, and rise to meet the challenge or opportunity that presents itself. No one can give us good health, but ourselves; no one can eat for us, exercise for us, breathe for us, or study for us. The self-reliant ones know that attaining good health requires knowledge, time and personal application; no institution or professional can do it for him.

The weak dependent individual blames others for his failures. He doubts and fears that he will fail, because no one cares about him, and he lacks good judgment. He thinks society is against him, and no one will listen, appreciate or recognize him. He thinks no one has suffered failure and poverty as much as he.

The self-reliant person seeks only to discover and conquer his own shortcomings, failures and weaknesses that keep him from success and happiness. He goes within, to the power source to find reliance to overcome the influences around him. All the greatest men and women in history never had it easy; they all had to overcome obstacles and pitfalls along the way to success. The self-reliant ones realize that there is light at the end of the tunnel; that sunshine always conies out of darkness; that storms are only temporary; that cold winter blasts give way to warm summer sunshine. One's freedom and independence is in proportion to one's self-reliance, and the power to sustain himself from within. He draws from his inner strength to overcome the trials and tribulations of life; he needs no one to hold him up; it is accomplished from within the temple of the inner soul. When storms are brewing, the self-reliant are calm and peaceful, and sail unharmed to the quiet waters beyond the storm. No external advantages can supply the place of self-reliance. The force of one's being, if it has any force, must come from within. No one can safely imitate another; nor by following in the footsteps of another can he ever gain distinction or enjoy prosperity. The spirit of self-help is the root of all genuine growth in the individual; and, exhibited in the lives of many, it constitutes the true source of national vigor and strength. Help from without is often enfeebling in its effects, but help from within invariably invigorates.

Rely on Yourself

Man and woman to be successful in all areas of life must be self-reliant. He does not have to know all things, but he must be self-reliant in his own profession. He is not conceited or aloof; he dares to stand apart from the crowd and think and speak his mind. He or she is an oak, not a weed. He offers others support and inspiration, but does not crave or desire it for himself. He is independent, not dependent.

We are all in life alone, and we must make deci-sions and reach our goals alone. Humanity does not care whether you fail or succeed it pays little heed to the individual. However, it acknowledges and recognizes the self-reliant and successful. If you desire success, strength, ability to perform, do not envy others, or wish you had their abilityemulate the process of success in others, train for it, rely on yourself, and you may develop equal power.

Look upon yourself as a deep well of infinite possibilities and opportunities, and develop and cultivate them to their fullest; dig deep and bring up from within your depths your hidden talents and powers. Surpass yourself, not others. Progressing in an upward spiral brings harmonious growth to mind, body and soul. If we do not grow in wisdom, expand our consciousness, we stagnate, decay and die before our death. Grow from within, outward. Create your own life and circumstances. Do not follow in the foot steps or greatness of another; think for yourself; act for yourself and depend on yourself. Be a strength to others by living the example of self-reliance. As you become stronger, you will be able to help others in their crisis of weakness.



Fig. 10.7. Happiness comes from Within

Happiness comes from Within

Happiness grows from within. It does not come from possessions, people or money. It consists not of getting something, but of being, enjoying the moment; total contentment and peace within the heart, regardless of outward conditions. We create our own happiness and misery. If we attempt to find happiness in material things, disappointment will follow. Happiness is an intangible, spiritual possession.

True happiness of the soul allows us to overcome obstables and trials with a calm joyous heart. Excessive cravings and desires are the root of all unhappiness and discontent. We are satisfied and content when we are thankful and grateful for the things we have. False appetites and illusory desires destroy our poise and inner peace. We may possess a million dollars, yet still be unhappy. Happiness is soul-satisfaction, not the stimulation and satisfaction of the mind and body. Be content with what you have, but always grow and expand your present consciousness.

A happy person does not struggle or worry. He does not seek happiness in pleasures; but seeks to place the happiness of others above his own. True happiness is egoless; it is optismistic, faithful, loving, honest and simple. No one who criticizes, complains or hates can ever attain inner happiness. The cynic looks for the evil in others, because it is in his own heart.

Unselfish Service: Key to Happiness

Unselfishness, service to others, or a high ideal is the key to happiness. Forget yourself and help those around youit is the key to the gates of heaven. Accomplish good because it is the correct thing to do. You do not have to tell anyone of your good deeds; we are judged for our good or bad deeds whether others see us or not. The Creator or Tao of the Universe sees to it that we get back exactly what we give out. If we are discontent, unhappy or dissatisfied, we can blame no one but ourselves. We cannot put happiness into someone else’s head; our mate, parents, children cannot infer it upon us. We can cultivate happiness by patience, self-reliance, honesty, good deeds, and unselfishness. When we follow these higher ideals, we do not have to search for happiness at the end of the rainbow; it will be with us forever.

Honesty is the Best Policy

Can I always be depended upon to do what I say I shall do? Honesty and dependability are two of the greatest character traits one could possibly possess. To give your word and not keep it, is to lose self-respect and your influence over others. You will never be truly respected. The person who keeps his word is always admired and respected. When a person is honest and dependable his voice is always full of love and sincerity. He is sympathetic to all people. Oh, what a tangled web we weave, when at first we practice to deceive. The dishonest person might seem successful at first, but in the long run the honest person will acquire peace, happiness and success. He will then display a clear conscience for all the world to see. Make it your policy to be honest.

Right Action leads to Harmony

A decisive positive attitude leads to health and happiness. A negative confused attitude creates disease and unhappiness. You must choose your own life style. You have been given free choice to chart a destiny during this life. No one else can alter or chart a course for you. No one can live your life for you. There are no magic pills, no potions, no masters, no gurus, no books that can take action for you. Only you can make this decision and take the necessary action that will eventually bring forth the blessings of Health, Happiness and Success to your life. By cleansing your blood and body of impurities, eating wholesome natural foods, purifying your mind and thinking positive optimistic thoughts, you will lose the eight basic fears which plague humanity:



Fig. 10.8. Right Action leads to Harmony in the Tao

It is More Blessed to Give

The average person always thinks in terms of getting or what can I get out of so and so. Try living the opposite way of the world; instead of clinging and holding on to what is yours, learn to give. This will enable you to relax and let go of tensions, thereby letting the universal Divine Supply flow into your life. Too many people believe that getting is what brings happiness; but giving is the true answer that leads to joy, happiness and life without strain. If you hold and cling onto what you have, you will find yourself in difficult situations. You may at times feel that the world is against you; this is the time to stop want-ing your own way and reverse your objective. Go out of your way to help someone in need. Be of service to humanity. Give of yourself for a change. Give your best to the world and the world will give its best back to you. Do a good deed without seeking a reward. Give of yourself unselfishly and you will attain physical, emotional, mental and spiritual happiness.

Taoist Secrets of Personal Magnetism and Peace in Life:

1. Seek beauty in everyone and everything.
2. Love unselfishly.
3. Speak in a positive manner, if not be silent.
4. Maintain calmness and poise at all times.
5. Do unto others as you would have them do unto you.
6. Cultivate a charming, pleasing disposition.
7. Develop a personality that wins, holds and attracts others.
8. Improve your life by learning something new each day.
9. Get interested in people, life or a hobby.
10. Cultivate a pleasing, magnetic voice; cultured and flexible.
11. Always lend a helping hand to those in need.
12. Be clean and neat in your dress and appearance.
13. Always be polite and courteous to everyone.
14. Avoid affectation and veneer. Be your natural self.
15. Be thoughtful and considerate of others.
16. Never gossip, criticize, nag or scold others.
17. Past forgotten, do not worry about the future; live in the now.
18. Praise and flatter others with sincerity and with good taste.
19. Avoid arguments, physical violence and hostility.
20. Assert yourself positively, but graciously.
21. Eliminate self-pity, fear, anxiety, nervousness and doubt.
22. Be dignified and poised, without stiffness.

1. Ask for the power to see into the cells of the brain. Ask the student to move their hands to cover their brain. “Brain cells listen to the command: Sickness go away. Clear, clean and bright; fill with violet light and return to normal function”.


Frontal Lobe
Parietal Lobe
Occipital Lobe
Temporal Lobe
Cerebellar Hemisphere
Pineal Gland
Thalamus
Hypothalamus
Cortex of Cerebellum
Pituitary Gland
Mammillary Body
Pons
Medulla Oblongata

Fig. 4.54 *“Clear, clean and bright; fill with violet light and return to normal functions”.*



Brain Cells

Healthy Happy Cells

Fig. 4.55 *‘Intent’ to Heal.*

23. Acquire a flexible, healthy, attractive body.
24. Develop a wholesome, positive, active mind.
25. Be a gentleman or lady at all times.
26. Cultivate mastery over your mind and emotions.
27. Think clearly before you act and speak.
28. Have a daily objective and a goal for life.
29. Improve yourself in small ways waiting for big opportunity.
30. Never let a day go by without doing something constructive.
31. Take prompt right action when the opportunity presents itself.
32. Express yourself in a poised, confident manner.
33. Eat foods that agree with your body and nerves.
34. Maintain order in your home and belongings.
35. Develop self-confidence. Affirm outloud to yourself daily that you are now healthy, happy and successful.
36. Enjoy every task you perform and complete each one before going on to the next one.
37. Practice moderation in all activities. Stop before your limit. All things are accomplished by following the middle path.
38. Forgive everyone who has done wrong to you. Never hold a grudge. If you forgive, you will be forgiven. Release all those who have wronged you, and peace will flow into your life. Love all.
39. Allow others to live their own lives expect nothing from others and you will never be disappointed. Do not try to change people against their will, as you would not like to be changed against your will. Enjoy people for their company and friendship. Avoid fault-finding or critizing, and you will always have dedicated and true friends.
40. Meditate daily until you feel the peace and presence of the Creative Force of the Universe flowing through the Tao.

Golden Stairs in the Tao

A clean life, an open mind, a pure heart, an eager in-tellect, an unveiled spiritual perception, a brotherliness for all, a readiness to give and receive advice and instruction, a courageous endurance of personal injus-tice, a brave declaration of principles, a valiant defense of those who are unjustly attacked, and a constant eye to the ideal of human progression and perfection which the sacred science depictsthese are the golden stairs up the steps of which the learner may climb to the Temple of Divine Wisdom.



Fig. 10.9. Personal Magnetism in the Tao

Law of Personal Magnetism and Attraction

Magnetism is attraction, repulsion of the opposite. Hypotism is an evil use of the power of influence. As magnetism is not understood it is useless to elaborate on the magnetic laws that govern affinity. Each type of person has his or her own power of attraction and each individual has a magnetism or influence of his own, either pleasing or displeasing, uplifting or depressing. Magnetism used for evil purposes is hypnotic. A rattlesnake or a blood-thirsty tiger is hypnotic. A soulless, heartless, evil and power-hungry person is hypnotic, whereas a saint is magnetic. That special kind of magnetism in a woman or in a man that exalts your power, mind and soul, is to you the right kind of affinity magnetism, but if you feel humble, insignificant, stupid, strange, inferior, mean, nervous, angry, etc., in the presence of a man or woman, he or she is not the one for you. Affinity magnetism and magnetic love exalt, broaden, and enlarge all your powers, otherwise it is not magnetic love, nor affinity magnetism. If you become lustful and familiar in the presence of your chosen one, you are not the one or him or her. That which you then mistake for love is nothing but stormy amatory infatuation very dangerous to your future happiness.

Three Treasures of Tao

Kind Gentle Nature

Being kind, one can be brave; being moderate, one gains ability, not venturing to go ahead, one becomes great. The universe is a great whispering gallery; it whispers back to us the echos of our thoughts and deeds. It is like a mirror; when we frown, it frowns back; when we smile, it smiles back. When we hold negative, cruel or hateful thoughts and wish them upon others they come back to us like a boomerang and deprive us of happiness and a joyful life. This is the universal law of cause and effect; whatever we sow, so shall we reap. Forceful, critical and aggressive people, by their very attitude, create for themselves much trouble, suffering and unhappiness. A gentle natured person is well mannered, tolerant, kind and relaxed a true gentleman or lady. Whatever troubles come to you in life, if you react to them with a kind gentle nature, they will be much easier to master. Calmness is the key to success, happiness and love in life. If we are calm and gentle, we likewise attract to us other people of the same spiritual quality. If our nature is harsh, irritable or unfriendly, we not only repel those around us, but we also cause suffering to ourselves and others.

If we use our clever intellect to outwit or cheat someone, in like proportion we attract to ourselves people of the same cleverness who will try to outwit or cheat us. It is that simple. What we give out comes back to us tenfold, good or bad. If we use physical or mental force to dominate others and get our way, we will meet with a similar force in return. Although, even if we always get our way, we are still the loser, because people are generally repelled by and dis-like forceful and dominant characters. On the other hand, if we are fair, considerate and well mannered, others will likewise be fair, kind and honest with us.

Understand: We are all sons and daughters of the Tao; a king and queen in the physical realm. The ancients teach that we are one with the Tao. A kind gentle nature brings us closer to our Divine Creator. When we see the good in another, they will see the good in you. A kind and gentle nature requires one to be totally relaxed in mind and body. We cannot be kind or gentle when we are tensed or stressed. The key to relaxation is to totally let go of mental and physical problems. Feel your muscles relax; relax your forehead, neck, abdomen, pelvis, legs and feet. Allow yourself a few minutes a day for meditation to throw your cares to the wind and let the Universal Force, or the Tao guide your life. Dwelling on the past or worrying about the future takes us away from doing our best in the present.

Fig. 10.10. Developing a Kind Gentle Nature in the Tao

Be Still and Listen

Cultivate quiet moments throughout the day; still your thoughts and body movements; feel the presence of the Tao within your consciousness and in the universe. The Tao is everywhere as close as our breath, and to the end of the galaxies.

The human body and mind are finite; a manifestation of the Tao (Infinity). The limited finite conscious mind often attempts to solve the difficult problems of life. If we learn to let go and relax, the Tao will show us the correct answers that we seek. Trust in the Universal Force and It will never fail you. Ask, and you shall receive; seek, and you will find; knock, and the doors (of wisdom) shall be opened onto you. When the lower mind and fleeting passions and desires are transcended, the Tao operates through us for the good of all. When we let go of our problems, then the mind becomes open to the inner voice, or the Tao within, which guides us in the right direction. Be still, and know that I am, applies to stilling the mind and listening for inner guidance. A heavy mind bogged down with worries, problems, uncontrolled desires and emotions slams the door in the face of the Tao and shuts us off from true guidance answers to our problems. A mind that is light, relaxed and at peace is always open for correct Divine guidance. Such a mind overcomes worries and problems by not thinking about them, or struggling with the lower mind to solve them. We can accomplish much by performing right action at the right time according to our guidance from within.

Struggling, overworking and becoming heavy in mind and body does not create high level health mentally, physically and spiritually. When we learn to relax and be gentle, we create a heaven right here on earth. Thy will be done on earth as it is in heaven. Realize that a dictator creates tension and fear; the gentle, kind person allows life to flow with the Tao, and he/she radiates peace and love wherever they go.

Love vs Power

A wise, loving person in a leadership position commands without exercising any authority or egotistic force. He or she has mastered himself and has harmonized his consciousness with the Creative Force. The Tao is love; this is the ultimate reality in the universe; therefore, the wise person is kind, gentle and tender. He gives love without seeking it in return, because he knows that everyone needs to be understood and loved. The Power of Love overcomes all harshness, fear and weakness. If you would be perfect in knowledge, wisdom and principles, be perfect in Love, compassionate in heart, and calm in mind. Only then will you banish sorrow, suffering and grief.

Men engage in heated controversies, and foolishly imagine they are defending the Truth, when in reality they are merely defending their own petty interest and perishable opinions. The follower of self takes up arms against others. The follower of truth takes up arms against himself. Truth, being unchangeable and eternal, is independent of your opinion and of mine. We may enter into it, or we may stay outside, but both our defense and our attack are superflous, and are hurled back upon ourselves.

Men and women enslaved by self, passionate, proud, and condemnatory, believe their particular creed or religion to be the Truth, and all other religions to be error; and they proselytize with passionate ardor. There is but one religion, the religion of Truth. There is but one error, the error of self. Truth is not a formal belief; it is an unselfish, holy, and aspiring heart, and he who has Truth is at peace with all, and cherishes all with thoughts of love.

Fig. 10.11. Seek the Truth and the Truth shall make you free - free from suffering, sickness, limitation and distress.

Moderation and a Simple Life

Moderation and simplicity in living has been taught by all of the great sages, saints, mystics and religions throughout history. A moderate simple life is one of balance and equanimity. An immoderate person lives life in extremes over-working, too much talking and useless chatter, excess and/or lack of exercise, reading and studying to the point of mental and physical exhaustion; extremes in dieteating to repletion or fasting excessively, and becoming nutritionally deficient or anorexic.

The little mind clamors after selfish desires and ego aggrandizement. It seeks excitement in sophisticated immoderate pleasures, such as drinking, smoking, mind expanding drugs, laziness etc. The greater mind seeks only to maintain balance and simplicity. Many modern diseases have developed due to our unnatural and immod-erate habits of living, thinking and eating. Extremes in living lead to nerve exhaustion; fatigue and exhaustion cause mental depression, in which we selfishly and constantly dwell upon our problems, making them larger and more complicated than they really are resulting in failure, suffering and unhappiness.

Some millionaires who attain great power and notoriety through long and hard work become weak, ill and exhausted in the prune of their life. They are, in many cases, unable to truly enjoy their wealth and die an untimely death.

Life is Simple

Life and being are simple. The universe is simple. The laws of life are simlple. Man only complicates the original simplicity with his secret vices, lusts, desires, passions and opinions about this or that; he remains ignorant in the university of wisdom, though he attain many college degrees. The simple and moderate life is where true joy resides.

When we learn to listen to our inner voice, and are guided by it in all of our life's activities of eating, sleeping, playing, meditating, exercising, singing and working only then can we become master of this life. By cultivating moderation and simplicity, we will be at one with the Tao, and enjoy a peaceful and happy life without strain. With a tranquil mind I abandon the written and spoken word and find deep contentment in the joy of illumination.

Thankful Humble Attitude

When you do not venture to go ahead, one becomes great. Western religion says, He who exalts himself, shall be humbled. He who humbles himself, shall be exalted. Eastern and Taoist religions over 5,000 years ago said, He who is first is last. He who is last is first. The philosophy is identical. When we strive to be self-assertive and act important, we become exalted and our ego puffs up; this is not humbleness or humility. An overblown ego can be easily deflated or humbled. A humble person does not over or under estimate himself. He does not brag, show-off, complain, criticize or suffer a deflated ego. His attitude is humble and thankful. He or she is free from envy, jealousy, greed, self pity, and self conceit. He does not seek ego gradification, nor does he desire to be the first in the eyes of others, or to exalt his talents to prove himself. If he is wise and talented, people will find out through his every deed, action and word.

If we are unhappy because others possess the wealth we do not have, we are stricken with the problem of envy. If we are to be happy and dispel envy, we should feel joy and goodness for the success of others. This thankful humble attitude places us in harmony with life and the Tao. By this attitude, we flow with the grain of life, and not against it; and the good that we send out will come back to us. If we pity ourselves because we do not have the right partner or a true friend, jealousy is the problem. Likewise, be happy when you see a married couple in love; this attitude of mind places us in the right and proper vibration, which will eventually attract our true love to us.

If we continually strive after wealthscheming, toiling and savingdwelling on our own life and problems, we create a self-made prison for ourself. Greed, selfishness, unthankfulness, and pride all lead to a life of loneliness and misery. The selfless humble person who lives a life of giving and sharing, and is kind and encouraging to all, will have peace of mind and a life of happiness.

Dwelling on our past actions and feeling sorry for ourselves because we are not yet successful, happy or healthy, causes us more suffering and trouble. Graditude and thankfulness can lead us out of this self-pitying attitude. Thankfulness and humbleness is true prayer. If we are thankful two percent of the time, we will be happy only two percent of the time. If we are thankful one hundred percent of the time, we will always be happy. The universe pays us back exactly what we give out. In fact, the more we grumble and complain, the tougher and more difficult will our life become. Nations begin to fall when the people constantly complain & criticize.

Be Thankful

Be thankful for the home you live in, the friends you have, the food you eat and all the good things of life. Realize that no matter how much we own, how highly degreed we are, or how much discipline we have applied in our religious beliefs, we are not better or higher in the eyes of the Tao. To think otherwise is to miss the mark. When pride comes, a fall comes. No matter how much intellectual understanding of the Tao we may have, how beautiful a temple we pray in, or what religion we are in, we are all on equal grounds with the person who prays and meditates with sincerity and thankfulness in a humble ghetto shack or a barren desert. The Kingdom of Heaven is within us. We need not go anywhere to pray. Just simply bow our heads and ask the Creative Force for guidance (It speaks to us non-verally - it is a feeling) and with that attitude we can live a heavenly joyous life, even during difficult and troubled times.

Your good is here. Accept it. Your joy is near. Embrace it. Your power is within. Harness it. Your victory is now. Claim it. Your freedom is real. Declare it. Your abundance is overflowing. Share it. Your prosperity is good. Receive it. Your problem is purposeful. Bless it. Your spirit is divine. Free it. Your love is great. Give it. Your faith is mighty. Use it. Your song is beautiful. Sing it.

Fig. 10.12. Lao-Tse, Taoist sage, author of the Tao-Teh-Ching

Know Thyself First

The easiest thing in the world is to give advice; the most difficult is to know thyself. Advice is like salt; it should be given only when asked, and only in small doses. When we attempt to change others against their own will, we stifle the Tao within them. We stop their personal growth and experiences. Realize, that the same Tao that is guiding your life is the same One guiding another’s life. Many people have lost touch with their inner voice, or the Tao within, and they consequently live against the grain of their own being, experiencing much suffering as a result.

The enslaved and tyrannical individual, not free himself, attempts to dominate others or force them into his way of living and thanking in order to justify his own enslaving habits. He does not allow the free soul to live out the experiences he really needs in life.

Parents attempt to mold their children into their own image; marriage partners try to make each other perfect; friends tend to criticize each other's faults; congressmen attempt to legislate morality. This cannot be done. These enslaving efforts only stifle and suppress the freedom and Divine power in others.

The ancient sage Lao Tse said that there is nothing worse than the desire to change others against their will. When Confucious came to Lao Tse and announced that the leaders of the world would not listen to him on how to make the world peaceful, even though he gave them the greatest wisdom and advice, Lao Tzu answered, that is good, because your advice would have stirred up more suffering and trouble for the nation. He added that the more laws you make, the further you take the nation's people away from the Tao within. You remove the last speck of individual creativity from their soul. Leave them alone do not interfere with their life force. If you stir muddy water, it becomes muddier. When the water is still, the mud will fall to the bottom the water will clear of itself. Be thankful and humble, and your mind will be clear and sharp. You will then know the joy of creativity, happiness, success and harmony in life. You will attract to you all that is necessary for your health and well being.

Sympathy and Compassion Unlocks Hearts

Sympathy is the key that unlocks the door to every heart. To develope sympathy and compassion for others practice listening sympathically and with attention to others; speak softly this helps the other person to relax and listen; try to understand the ideas and thoughts of others. Never argue, but agree on common ideas; look with understanding eyes; people can see your sympathy in your eyes. We are all alike in that we all want to be loved, appreciated, caressed and understood. With this spiritual attitude self-righteousness cannot be present, because you will become at one or in harmony with those around you.

Without compassion you cannot be happy; give it to others and you will receive it in return. The person of humility does not attempt to reform others or to make them good, but always loves and makes them happy, for in so doing, they become good.

2. Ask for the power to see the cells of the sense organs. Ask the student to move their hand to cover their senses. Give the command: “Eyes, ears, nose, tongue and mouth cells listen to the command. Sickness go away. Clear, clean and bright; fill with violet light and return to normal function”.


Light
Cornea
Pupil
Lens
Iris
Conjunctiva
Retina
Blood Vessels
Lateral Rectus Muscle
Optic (II) Nerve
Optic Disk (Blind Spot)

Fig. 4.56 *“Eyes, listen; clear, clean and bright; fill with Violet Light and return to normal function”.*


Temporal Bone
Semicircular Canal
Auricle
Cochlea
Eardrum
Elastic Cartillage
To Nasopharynx
External Auditory Canal

Fig. 4.57 *“Ears, listen; clear, clean and bright; fill with Violet Light and return to normal function”.*

Fig. 10.14. Sympathy and Compassion Unlocks Hearts

Life is a Stage

Life is a stage and we are all acting out a part. The stage is set. You have been given a role to play. It is now your time or cue to go into action and to utilize the parts, props and scenes that the Creator has so generously given you to perform with natural foods, air, water, sunshine, exercise and breathing, and a brain to think with. These are the fundamental Taoist Secrets that no man or woman can ever do without. They are part and parcel of life itself. Our function is to learn how to play our role in life superbly well, and become the star attraction we were all designed to be.

Through the understanding and application of natural law physical, mental and spiritualwe become an acting part of the Creative Force that has brought us to this earth stage. We urge you to seek this path to health, beauty and spiritual evolvement; sincerely believe in it and inspire others to follow your message and example.

We trust that we have shed some light on the subjects of health, happiness, fitness and longevity. May this book wing its way across the earth to those in need of help, inspiration and hope. Our sincere intention is to help others, so that they may help themselves. May you live in love and peace, and may the Tao be with you always. Life is just a manifestation of energy. If you have complete energy, you have a fuller life. If your energy is incomplete, you only enjoy part of life. It does not matter whether you are rich or poor, noble or ignoble. What matters is the good virtue found inside of you, such as honesty, sincerity, patience, and courage. It is particularly important to cultivate these basic virtues with a positive attitude. The more you worry, the more you darken your soul and weaken your power. The virtue of life is by no means external or artifically contrived. It is deeply rooted within your being.

Remember the way you look and feel tommorrow depends on what you do today. We come from nothingness, we belong to nothingness and we are destined for nothingess (the Tao). For things to get better you have to get better. For things to change you have to change. We are all the controller of our own destiny because we are all Divine with our understanding of the Tao and after a combined over hundred years of reseach and experiences on health and longevity we will leave you with one final thought, “It takes a lean horse for a long race” and whatever means you use to become lean will give you your health and longevity. Good luck.



Fig. 10.14. We are destined for nothingess (the Tao).

Bibliography and Recommended Reading

Abehsera, Michel, Zen *Macrobiotic Cooking,* New York: Avon Books, 1971.

Airola, Pavvo, N.D., *Are You Confused,* Phoenix, Arizona: Health Plus Publishers, 1973.

_____, *Health Secrets from Europe,* New York: Arco Books, 1972.

_____, How *to Get Weil,* Phoenix, Arizona: Health Plus Publishers, 1974.

Allen, James, *The Way of Love,* Lakemont, Georgia: CSA Press, 1971.

Austin, Mary Dr., *Acupuncture Therapy,* New York: Asi Publishers Incorporated, 1972.

Bether, May, *The Healing Power of Herbs,* Hollywood, CA: Wilshire Book Co.

Bogert, Jean L, Ph.D., *Diet and Personality,* New York: The Macmillan Company, 1934.

Bragg, Paul C., *The Mircale of Fasting,* Burbank, CA: Health Science, 1965.

_____, *Super-Brain Breathing,* Santa Ana, CA: Health Science, 1963.

Brodsky, Greg, From *Eden to Aquarius,* New York: Bantam Books, 1974.

Carque, Otto, *Rational Diet,* Mokelumme Hill, CA: Health Research, 1971.

Carrington, Hereward, *Vitality, Fasting and Nutrition,* New York: RebmanCo., 1908.

Carroll, David, *The Complete Book of Natural Medicines,* New York: Summit Books, 1980.

Chang, Stephen, M.D., *The Book of Internal Exercises,* San Francisco: Strawberry Hill Press, 1978.

Chia, Mantak, *Awaken Healing Energy Through the Tao,* New York: Copen Press, 1981.

_____, *Taoist Ways to Transform Stress into Vitality,* New York, Universal Tao Publications, 1985.

_____, *Chi Self-Massage: the Tao of Rejuvenation,* New York, Universal Tao Publications, 1986.

_____, *Cosmic Healing I,* Thailand, Universal Tao Publications, 2001.

_____, *Cosmic Orbit,* Thailand, Universal Tao Publications, 2003.

_____, *Living in the Tao,* Thailand, Universal Tao Publications, 2007.

_____, *Simple Chi Kung,* Thailand, Universal Tao Publications, 2008.

Ching, Ni, Hua, *The Taoist Inner View of the Universe and the Immortal Realm,* Malibu, CA: The Shrine of the Eternal Breath of Tao, 1979.

Clark, Linda, *How To Improve Your Health,* New Canaan, Conn.: Keats Publishing, Inc., 1979.

Clark, P.L., How *to Live and Eat for Health,* Chicago: The Health School, 1923.

Claunch, S.K., *Exploding the Germ Theory,* Pacific Grove, CA: 1960.

Cott, Allan, M.D., *Fasting; The Ultimate Diet,* New York: Bantam Books, 1975.

Crampton, Ward C., *Physical Exercise for Daily Use,* New York: G. P. Putnam's Sons, 1924.

Davis, Adelle, *Let's Eat Right to Keep Fit,* New York: Harcourt, Brace, Jovanovich, Inc. 1970

deSmedt, Evelyn et al., *Lifearts,* New York: St. Martin's Press, Inc., 1977.

Donsback, Kurt W., D.C., *Preventive Organic Medicine,* New Canaan, Conn.: Keats Pub., 1976.

Doyle, Rodger P., and Redding, James L., *The Complete Food Handbook,* New York: Grove Press, Inc., 1980. Ehret, Arnold, *Mucousless Diet Healing System,* Beaumont, CA: Ehret Literature Publishing Co., 1970.

Estes, St. Louis, M.D., *Food and Health,* Chicago: Estes Health Club, 1923.

Fryer, Lee, and Dickinson, Annette, *A Dictionary of Food Supplements,* New York: Mason/Charter, 1975.

Gach, Michael Reed, and Marco, Carolyn, *Acu-Yoga,* Tokyo: Japan Publications, Inc., 1981.

Gaines, Thomas R., *Vitalic Breathing,* New York: Thomas Galnes, 1926.

Garten, M.O., D.C., *The Health Secrets of a Naturopathic Doctor,* New York: Parker Publishing Company, Inc., 1967.

Graves, W.H., D.C., *Banish Constipation,* P.O. Box 248, Columbian, CA: 1953.

Hass, Elson M., M.D., *Staying Healthy With The* Seasons, Millbrae, CA: Celestial Arts, 1981.

Hall, Manly P., *Questions Answered on the Problems of Life,* Los Angeles: Philosophical Research Society, Inc., 1965.

Hills, Christopher, *Secrets of Spirulina,* Boulder Creek, CA: JNM Books, 1980.

Hyde, Emily M., *Physical and Mental Rejuvenation,* Super Science, Inc.

Iijima, Kanjitsu, Rev., *Buddhist Yoga,* Tokyo: Japan Publications, Inc., 1975.

Inches, Howard V.H., *Brother, Heat Thyself,* Cleveland, OH: Phoe-nix Press, Inc., 1938.

Jackson, Robert G., How to Be *Always Well,* Toronto, Canada: Print Craft Limited Publishers, 1927.

Jensen, Bernard, D.C., *Nature Has a Remedy,* Provo, Utah: Bi-World Publishers, 1978.

_____, *Vital Food for Total Health,* Los Angeles: Mason-Springs Corp., 1959.

Jordon, William George, *The Majesty of Calmness,* New Jersey: Fleming H. Revell Company.

Kellogg, John H,, M.D., *The Health Question Box,* Battle Creek, MI: The Modern Medicine Publishing Co., 1930.

_____, How to Have Good *Health Through Biologic Living,* Battle Creek, MI: The Modern Medicine Publishing Co., 1932.

Kerschner, H.E., M.D., *Nature's Healing Grasses,* Riverside, CA: H.C. White Pub., 1970.

Kime, Zane, M.D., *Sunlight Can Save Your Life,* Penryn, CA: World Health Pub., 1979.

Kloss, Jethro, *Back to Eden,* Riverside, CA: Lifeline Books, 1973.

Kroeger, Hanna, Rev., *Old Time Remedies for Modem Ailments,* 1971.

Kulvinskas, Viktoras, Tne New *Age Directory,* Woodstock Valley Conn.: Omangod Press, 1981.

_____, *Survival into the 21st Century,* Woodstock Valley, Conn.: Omangod Press, 1976.

Kushi, Michio, How *to See Your Health,* Tokyo: Japan Publications, Inc., 1980.

Lappe, Frances M., *Diet for a Small* Planet, New York: Ballantine Books, 1976.

Lindlahr, Henry, M.D., *Philosophy of Natural Therapeutics,* Chicago: The Lindlahr Publishing Co., 1921.

Liu, Da., *The Tao of Health and Longevity,* New York: Schocken Books, 1978.

Lucas, Richard, Secrefs *of the Chinese Herbalists,* New York: Cornerstone Library, 1978.

Lust, John, *The Herb Book,* Bantam Books, 1976.

Macfadden, Bernarr, Home *Health Library,* New York: Bernarr Macfadden. Mastrom, Stan, N.D., Own *Your Own Body,* USA: Bell Press, 1977.

Mann, Felix, M.B., *Acupuncture,* New York: Vintage Books, 1973.

Minick, Michael, *The Kung Fu Exercise Book,* New York: Bantam Books, 1974.

Muramoto, Naboru, *Helaing Ourselves,* New York: Avon Books, 1973.

Nichols, Joe D., M.D., and Presley, James, *Please, Doctor, Do Something,* Atlanta, Texas: Natural Food Associates, 1972.

Null, Gary and Steve, *The Complete Handbook of Nutrition,* New York: Dell Books, 1972.

Nutrition Search, Inc., Nutrition Almanac, New York: McGraw-Hill, 1975.

Nyoiti, Sakurazawa, *You Are All Sanpaku,* Trans. William Dufty, New York: Avon.

Ohsawa, George, *Practical Guide to Far Eastern Macrobiotic Medicine,* Oroville, CA: George Ohsawa Macrobiotics Foundation, 1976.

Ott. John N., *Health and Light,* New York: Pocket Books, 1976.

Palos, Stephen, The *Chinese Art of Healing,* New York: Herder and Herder, 1963.

Price, Weston, A., D.D.S., *Nutrition and Physical Degeneration,* Los Angeles: The American Academy of Applied Nutrition, 1942.

Reuben, David, M.D., *Everything You Always Wanted to Know About Nutrition,* New York: Avon Books, 1978.

Rocine, V.C., *Unfoldment of the Great Within,* Portland, OR: Rocine's Pub. Service, 1934.

Rodale, J.I., *The Complete Book of Food and Nutrition,* Emmaus, PA: Rodale Books, 1961.

Rodidal, Jean, *Do In,* Wemingborough, Northamptonshire: ThorsonsPub. Limited, 1981.

Saran, Steven, *Body Messages I,* Boulder, CO: Asian, Box 1858, 80306,1979.

Schelmann, Eugene, M.D., *A Doctor's Guide to Better Health Through Palmistry,* New York: Parker Publishing Co., Inc., 1969.

Deier, Gerhard, W., *Light to Healthy Living,* Winnipeg, Manitoba: Health Book Supply Co., 1976.

Shaftesbury, Edmund, *Life Electricity,* Plymouth, MI: Universal Books, 1978.

Shelton, H.M., D.C., *Basic Principles of Natural Hygiene,* San Antonio, Texas: Dr. Shelton's Health School, 1949.

_____, *The Hygienic System, Orthotrophy Vol. II,* San Antonio, Texas: Dr. Shelton's Health School, 1947.

Tilden, J.H., M.D., *Toxemia Explained,* Mokelumni Hill, CA: Health Research, 1970.

Tilney, Frederick, Ph.D., *Young at 73 and Beyond,* New York: Information, Inc., 1968.

_____, *Your Wishes Realized,* Hollywood, Florida, 1938.

Van Lysebeth, Andre, *Yoga Self-Taught,* New York: Barnes and Noble Books, 1973.

Veith, Ilza, *The Yellow Emperor's Classic of Internal Medicine,* trans, Ilza Veith, Los Angeles: University of California Press, 1972.

Wade, Carlson, *Magic Minerals,* New York: Arc Books, Inc., 1971.

Watts, Alan W., *The Two Hands of God,* New York: Collier Books, 1963.

Wiley, Harvey W., M.D., *Intestinal Gardening for the Prolongation of Youth,* New York: Matthew Bender & Company, 1926.

Taoist Master's School

Universal Healing Tao Center, Tao Yoga at Tao Garden Health Spa & Resort

The first & best East-West holistic resort & health spa in a beautiful and healthy environment

Tao Garden Training Center in northern Thailand is the home of Master Chia and serves as the worldwide headquarters for Universal Tao activities. This integrated wellness, holistic health, and training center is situated on eighty acres surrounded by the beautiful Himalayan foothills near the historic walled city of Chiang Mai. The serene setting includes flower and herb gardens ideal for meditation, open-air pavilions for practicing Chi Kung, a health and fitness spa.

The Center offers classes year-round, as well as summer and winter retreats. It can accommodate two hundred students, and group leasing can be other resources.

Tao Garden Health Spa & Resort is the perfect place to get away from the city and other modern annoyances. It is a place where guests can pick and choose from a wide selection of disciplines ranging from detoxification and parasite cleansing program such as skin detox (Thai herbal oxygen and ozone steam), foot detox, Chi Nei Tsang (abdominal detox massage) and Karsai Nei Tsang (genital detox massage). Loosing weight program such as slimming massage and herbal steam bath. Ancient holistic treatments such as ayuvedic body care, traditional Chinese medicine, chi kung, meditation and yoga.

Universal Healing Tao Center
274 Moo 7, Luang Nua, Doi Saket, Chiang Mai, 50220 Thailand
Tel: +66 (0) 53 495-596 Fax: +66 (0) 53 495-853
universaltao@universal-tao.com, www.universal-tao.com,
www.chi-nei-tsang-official-site.com
www.tao-garden.com

Master School

of the Healing Tao, Tao Yoga, Universal Healing Tao Center at Tao Garden Health Spa & Resort

For Worldwide of North & South America, Europe & Asia information
For Center, Books, Product, Retreat and other Resources Contact:

Universal Healing Tao Center
274 Moo 7, Luang Nua, Doi Saket, Chiang Mai, 50220 Thailand
Tel: +66 (0) 53 921 200 Fax: +66 (0) 53 495-852
Email: ***universaltao@universal-tao.com***
Website: ***www.universal-tao.com***

For ***Retreats and Health Spa information***
Tao Garden Health Spa & Resort
Emails: ***info@tao-garden.com, reservation@tao-garden.com***
Website: ***www.tao-garden.com***

For **Products Order** *Email:* ***orders@universal-tao.com***

Tao Garden Wellness Retreat is Mantak Chia's home, school and training center. The Resort is a perfect place to relax and get away from the pressures of every day life for groups or meetings.

Please look into our Web Site: ***www.tao-garden.com***

The first & best East-West holistic resort & health spa
in a beautiful and healthy environment
Good Air * Good Water * Good Food * Good Chi * Good Heart * Good Mind

For ***information on Products*** *and* ***Instruction*** *from* ***W.U. Wei***
The Professor - Master of Nothingness
The Myth that takes the Mystery out of Mysticism
Email: ***tpweitzu@gmail.com (1)(503) 794-2717***
Website: ***www.the-professor-mon.com***

$19.95

Cosmic Nutrition

Taoist Understanding, Lifestyle & Longevity



Mantak Chia

W. U. Wei

Cosmic Nutrition

In Cosmic Nutrition the student will discover the Cosmic Dust Particulars that gives life to all living beings every morning at sunrise and evening at dusk (sunset). This star dust is the Life Force of the universe discovered by Antonie Bechamp (French Chemist) in 1866 as microznias (living ferments) which further confirms the Taoist's understandings for the last five thousand years through the Creative and Controlling Cycles.

Taoist Lifestyle for Longevity

In Cosmic Nutrition Master Mantak Chia and William Wei share their Taoist's understandings with the student of Yin/Yang Principles, Self Diagnosis, Physician Within, Acid/Alkaline Balance, Nature's Element and Five Elements Nutrition for health and longevity based their fifty years of research, experience and joy of dining.

Four Bodies into One

The student will learn how to heal and balance the physical body and emotional, mental and spiritual bodies at the same time through Medicine Meals prepared & developed from Tao Garden's organic fruit and vegetable gardens & Five Elements kitchen at Kuan Yin Dining Hall.

ISBN 974-85401-3-8

9 789748 540139

Universal Tao Publications


Olfactory Tract
Olfactory Bulb
Olfactory Nerve
Superior Nasal Canal
Epiglottis
Root of Tongue
Bitter
Sour
Salty
Sweet

Nose **Tongue**

Fig. 4.58
"Nose, tongue, listen; clear, clean and bright; fill with violet light and return to normal function"

3. Move your hands down to your throat center and give the command: "Thyroid, parathyroid and Thymus glands, listen to the command; Clear, clean and bright; fill with violet light and return to normal function".


Right Lobe of Thyroid Gland
Larynx
Left Lobe of Thyroid gland
Common Carotid Artery
Trachea
Stern
Throat Center
Thyroid Parathyroid Glands (Behind)
Thymus Gland
Thyroid Gland
Trachea

Fig. 4.59
"Thyroid, parathyroid and thymus glands - listen; clear, clean and bright; fill with violet light and return to normal function".

AMERICAN ACADEMY OF OPHTHALMOLOGY

SEVENTH
EDITION

FOR MEDICAL STUDENTS AND
PRIMARY CARE RESIDENTS

Basic ophthalmology

CYNTHIA A. BRADFORD, MD
EXECUTIVE EDITOR

Basic Ophthalmology

for Medical Students and Primary Care Residents

Seventh Edition

Cynthia A. Bradford, MD
Executive Editor

AMERICAN ACADEMY
OF OPHTHALMOLOGY

AMERICAN ACADEMY
OF OPHTHALMOLOGY

P.O. Box 7424
San Francisco, CA 94120-7424

Clinical Education Secretaries
Thomas A. Weingeist, PhD, MD
Senior Secretary for Clinical Education

Thomas J. Liesegang, MD
Secretary for Instruction

For the **7th** Edition
Cynthia A. Bradford, MD, *Executive Editor*

Denise R. Charnblee, MD, *Revision Contributor*

Jennie M. Hunnewell, MD, *Revision Contributor*

Rebecca K. Morgan, MD, *Revision Contributor*

Scott C. Sigler, MD, *Revision Contributor*

Interspecialty Education Committee
Anne L. Coleman, MD, *Chair*

Terry J. Bergstrom, MD

Cynthia A. Bradford, MD

Deborah S. Jacobs, MD

Robert Jay Granadier, MD

Academy Clinical Education Staff
Kathryn A. Hecht, EdD
Vice President

Hal Straus
Director of Publications

William J. Hering, PhD
Director of Programs

Kevin Stepelton
Program Manager

Margaret Petela
Managing Editor

Ruth Modric
Production Manager

Beth T. Berkelhammer
Production Editor

The Academy provides this material for educational purposes only. It is not intended to represent the only or best method or procedure in every case, nor to replace a physician's own judgment or give specific advice for case management. Including all indications, contraindications, side effects, and alternative agents for each drug or treatment is beyond the scope of this material. All information and recommendations should be verified, prior to use, with current information included in the manufacturers' package inserts or other independent sources, and considered in light of the patient's condition and history. Reference to certain drugs, instruments, and other products in this publication is made for illustrative purposes only and is not intended to constitute an endorsement of such. Some materials may include information on applications that are not considered community standard, that reflect indications not included in approved FDA labeling, or that are approved for use only in restricted research settings. The FDA has stated that it is the responsibility of the physician to determine the FDA status of each drug or device he or she wishes to use, and to use them with appropriate patient consent in compliance with applicable law. The Academy specifically disclaims any and all liability for injury or other damages of any kind, from negligence or otherwise, for any and all claims that may arise from the use of any recommendations or other information contained herein.

Each author states that he or she has no significant financial interest or other relationship with the manufacturer of any commercial product mentioned in the text that he or she contributed to this publication or with the manufacturer of any competing commercial product.

Copyright © **1975, 1976, 1978, 1982, 1987, 1993, 1999**
American Academy of Ophthalmology®
All rights reserved.

Library of Congress Cataloging-in-Publication Data
Basic ophthalmology for medical students and primary
care residents. — 7th ed. / Cynthia A. Bradford,
executive editor.
p. cm.
Includes bibliographical references and index.
ISBN 1-56055-098-8 (pbk.)
1. Ophthalmology. **2.** Primary care (Medicine)
I. Bradford, Cynthia A., **1958–** .
[DNLM: **1.** Eye Diseases. **2.** Diagnostic Techniques,
Ophthalmological. WW **10083114 19991**
RE46.065 1999
617.7—dc21
DNLM/DLC 98-27992
for Library of Congress CIP

97 96 95 94 5 4 3 2 1

Contents

Figures and Slides vii
Preface ix
Who's Who in Eye Care xi
Test Your Knowledge xiii

Chapter 1
The Eye Examination 1

Objectives 1
Relevance 1
Basic Information 2
Anatomy 2
Optics 3
Visual Acuity 3
When to Examine 6
Additional Tests 6
How to Examine 7
Distance Visual Acuity Testing 7
Near Visual Acuity Testing 10
Visual Acuity Estimation in an Uncooperative Patient 10
External Inspection 10
Pupillary Reaction Testing 11
Ocular Motility Testing 12
Ophthalmoscopy 12
Intraocular Pressure Measurement 16
Anterior Chamber Depth Assessment 18
Confrontation Field Testing 19
Amsler Grid Testing 19
Color Vision Testing 19
Upper Lid Eversion 20
Fluorescein Staining of Cornea 20
Summary of Steps in Eye Examination 21
Management or Referral 22
Reduced Visual Acuity 22
Abnormal Fundus Appearance 22
Shallow Anterior Depth/ Elevated Intraocular Pressure 23
Points to Remember 23
Sample Problems 23
Annotated Resources 25

Chapter 2
Acute Visual Loss 26

Objectives 26
Relevance 26
Basic Information 26
How to Examine 27
Visual Acuity Testing 27
Confrontation Field Testing 27
Pupillary Reactions 27
Ophthalmoscopy 27
Penlight Examination 27
Tonometry 27
How to Interpret the Findings 28
Media Opacities 28
Retinal Disease 29
Optic Nerve Disease 32
Visual Pathway Disorders 35
Functional Disorders 36
Acute Discovery of Chronic Visual Loss 36
Points to Remember 36
Sample Problems 36
Annotated Resources 38

Chapter 3
Chronic Visual Loss 39

Objectives 39
GLAUCOMA 39
Relevance 39
Basic Information 40
Intraocular Pressure 40
Optic Nerve 41
Relationship of IOP and Optic Nerve 41
When to Examine 42
How to Examine 42
How to Interpret the Findings 42
Management or Referral 44
CATARACT 45
Relevance 45
Basic Information 46
Lens 46
Cataract 46
Symptoms of Cataract 46
When to Examine 48
How to Examine 48
How to Interpret the Findings 48
Management or Referral 49
MACULAR DEGENERATION 49
Relevance 49
Basic Information 49
Macular Anatomy 49
Age-Related Macular Changes 50
When to Examine 52
How to Examine 52
How to Interpret the Findings 54
Management or Referral 54
The Visually Impaired Patient 54
Points to Remember 55
Sample Problems 55
Annotated Resources 57

Chapter 4
The Red Eye 58

Objectives 58
Relevance 58
Basic Information 58
Disorders Associated With a Red Eye 59
How to Examine 62
How to Interpret the Findings 64
Signs of Red Eye 64
Symptoms of Red Eye 67
Associated Systemic Problems 68
Laboratory Diagnosis 69
Management or Referral 69
Blepharitis 69
Stye and Chalazion 70
Subconjunctival Hemorrhage 71
Conjunctivitis 71
Therapeutic Warnings 72
Topical Anesthetics 72
Topical Corticosteroids 72
Points to Remember 72
Sample Problems 73
Annotated Resources 75

Chapter 5
Ocular and Orbital Injuries 77

Objectives 77
Relevance 77
Basic Information 77
Anatomy and Function 77
When to Examine 80
How to Examine 81
History 81
Visual Acuity Testing 81
External Examination 82
Pupillary Reactions 84
Ocular Motility Testing 84
Ophthalmoscopy 04
Radiologic Studies 84

Management or Referral 84
True Emergency 85
Urgent Situation 85
Semiurgent Condition 87
Treatment Skills 87
Ocular Irrigation 87
Foreign-Body Removal 88
Eye Medication Prescription 88
Patching 89
Suturing 89
Points to Remember 90
Sample Problems 90
Annotated Resources 92

Chapter 6
Amblyopia and Strabismus 94

Objectives 94
Relevance 94
Basic Information 94
Amblyopia 95
Strabismus 96
How to Examine and Interpret the Findings 98
Amblyopia Testing 99
Strabismus Testing 101
Other Tests 104
Management or Referral 105
Amblyopia 105
Strabismus 106
Points to Remember 106
Sample Problems 106
Annotated Resources 109

Chapter 7
Neuro-Ophthalmology 110

Objectives 110
Relevance 110
How to Examine 110
Visual Acuity Testing 111
Visual Field Testing 111
Pupillary Reactions 111
Ocular Motility Testing 113
Ophthalmoscopy 114
How to Interpret the Findings 114
Pupillary Disorders 114
Neuromotility Disorders 115
Other Cranial Nerve Palsies 118
Optic Nerve Disease 120
Visual Field Defects 122
Points to Remember 123
Sample Problems 125
Annotated Resources 128

Chapter 8
Ocular Manifestations of Systemic Disease 129

Objectives 129
Relevance 129
Diabetes Mellitus 130
Sickle Cell Anemia 133
Hypertension 134
Arteriolar Sclerosis 134
Elevated Blood Pressure 135
Diagnostic Concerns 135
Management 136
Thyroid Disease 136
Sarcoidosis and Inflammatory Conditions 137
Malignancy 138
Acquired Immunodeficiency Syndrome 139
Syphilis 140
Other Systemic Infections 141
Points to Remember 142
Sample Problems 142
Annotated Resources 143

Chapter 9
Drugs and the Eye 145

Objectives 145

Relevance 145

Basic Information 145

Topical Ocular Diagnostic Drugs 146
Fluorescein Dye 146
Anesthetics 147
Mydriatics 147

Topical Ocular Therapeutic Drugs 148
Decongestants 148
Agents for Relief of Allergic Conjunctivitis 149
Anti-Inflammatory Agents 149
Antibiotics 149

Systemic Side Effects of Glaucoma Medications 150
Beta-Adrenergic Blockers 150
Cholinergic-Stimulating Drugs 150

Alpha-2 Adrenoreceptor Agonists 151
Topical Brimonidine 151
Topical Apraclonidine 151
Adrenergic-Stimulating Drugs 152

Prostaglandin Analog 152
Topical Latanoprost 152

Carbonic Anhydrase Inhibitors 152
Oral Acetazolamide, Methazolamide, and Dichlorphenamide 152
Topical Dorzolamide 152

Ocular Side Effects of Systemic Drugs 153
Corticosteroids 153
Chloroquines 153
Digitalis 153
Amiodarone 154
Diphenylhydantoin 154
Ethambutol 154
Chlorpromazine 154
Thioridazine 154

Points to Remember 154

Sample Problems 155

Annotated Resources 156

Index 159

Figures and Slides

Figures

1.1 Cross-section of the eye
1.2 External landmarks
1.3 Extraocular muscles
1.4 Equipment for a basic eye examination
1.5 Snellen eye chart
1.6 Rosenbaum pocket vision screener
1.7 Fundus diagram
1.8 Electronic tonometry
1.9 Estimation of anterior chamber depth
1.10 Upper lid eversion
3.1 Cross-section of anterior chamber angle and ciliary body
3.2 Central macula
3.3 Neovascular net
3.4 Amsler grid testing
5.1 The bony orbit
6.1 Types of heterotropia
6.2 Picture card
6.3 Tumbling E chart
6.4 Corneal light reflex
6.5 Cover test
7.1 Pupillary pathways
7.2 Pupillary reflexes
7.3 Anatomy of sympathetic pathway
7.4 Internuclear ophthalmoplegia
7.5 Visual pathways with associated field defects
9.1 Instillation of topical drops

Slides

Numbers for the color photos designated "Slide" in the text correspond to numbered slides in the companion *Basic Ophthalmology* Slide Set.

Chapter 1

1 Red reflex
2 Normal posterior pole
3 Scleral crescent and pigmented crescent
4 Myelinated nerve fibers
5 Fluorescein stain
6 Fluorescein stain highlighted

Chapter 2

7 Retinal detachment
8 Central retinal artery occlusion
9 Central retinal vein occlusion
10 Papillitis
11 Papilledema
12 Ischemic optic neuropathy

Chapter 3

13 Temporal pallor of the optic nerve
14 Cup:disc ratio
15 Glaucomatous cupping
16 Glaucomatous optic atrophy
17 Immature cataract
18 Mature cataract
19 Drusen
20 Retinal pigment epithelial atrophy
21 Subretinal hemorrhage

Chapter 4

22 Acute angle-closure glaucoma
23 Ciliary flush
24 Herpes simplex keratitis
25 Conjunctivitis
26 Scleritis
27 Dacryocystitis
28 Pterygium
29 Purulent conjunctivitis
30 Large keratic precipitates
31 Corneal edema
32 Corneal leukoma
33 Irregular corneal reflection
34 Corneal ulcer with hypopyon
35 Chronic proptosis
36 Staphylococcal blepharitis
37 Seborrheic blepharitis
38 External hordeolum
39 Internal hordeolum
40 Chalazion

Chapter 5

41 Corneal perforation with iris prolapse
42 Hyphema
43 Subluxated lens
44 CT scan of foreign body
45 Alkali burn
46 Conjunctival foreign body
47 Corneal foreign body
48 Full-thickness lid laceration
49 Subconjunctival hemorrhage
50 Irrigation
51 Pressure patch
52 Shield

Chapter 6

53 Concomitant strabismus
54 Incomitant strabismus
55 Epicanthus
56 Small-angle right esotropia I
57 Leukocoria

Chapter 7

58 Homer's syndrome
59 Third-nerve palsy
60 Third-nerve palsy
61 Sixth cranial nerve paresis
62 Unilateral right internuclear ophthalmoplegia
63 Pseudopapilledema and true papilledema
64 Optic atrophy

Chapter 8

65 Nonproliferative diabetic retinopathy
66 Exudates in nonproliferative diabetic retinopathy
67 Cotton-wool spots in nonproliferative diabetic retinopathy
68 Proliferative diabetic retinopathy
69 Proliferative diabetic retinopathy
70 Panretinal argon laser photocoagulation
71 Hypertensive retinopathy
72 Arteriovenous crossing changes
73 Malignant hypertension
74 Thyroid stare
75 Anterior uveitis
76 Cotton-wool spots in AIDS
77 Cytomegalovirus retinitis in AIDS
78 Herpes zoster ophthalmicus

Preface

Basic Ophthalmology for Medical Students and Primary Care Residents is designed to help the user learn the techniques of a complete eye examination and the most important concepts of diagnosis and management of ocular disorders. The history of this textbook began in 1975 with the publication by the American Academy of Ophthalmology of a study guide in outline form for medical students. The book's developers identified seven common problem areas in ophthalmology and developed study objectives. Each subsequent edition was changed based on suggestions from users. The fifth edition, which was developed by the joint committee of the American Academy of Ophthalmology and the Association of University Professors of Ophthalmology, abandoned the outline form for chapters with expository text. The sixth edition, published in 1993, was one of the American Academy of Ophthalmology's most popular clinical education products, with 25,000 copies sold since its introduction. This seventh edition is an update of the excellent work of Dr. Frank Berson and the Medical Student Education Committee in response to recent changes in clinical medicine and health-care delivery, which have increased the need for primary care physicians-in-training in the areas of diagnosis, management, and referral of ocular disease.

Prior to undertaking this revision, a user evaluation of the sixth edition was conducted among previous authors, Academy members involved in medical student education, medical students, and primary care residents. Chapters have been revised based on the resulting recommendations. Much information and many photographs have been improved and updated. For example, glaucoma care has undergone significant changes in the past 5 years, and these are reflected in this edition's descriptions of glaucoma medications and tonometry.

As in previous editions, the seventh edition features a number of new photographs and updated and expanded annotated resources. The book's color photographs depicting normal and abnormal eye conditions are also available as a companion set of 78 color slides. Where appropriate, tables are presented to summarize textual information and facilitate study.

This book can be used in a variety of teaching settings. The concise presentation of information makes it ideal for brief ophthalmology rotations. If greater time is available, the resources can be consulted for more detail. Thus, the book is intended to be a flexible instrument that summarizes the important concepts, techmques, and facts of ophthalmology for all physicians, especially those in primary care. The Interspecialty Education Committee anticipates that medical students will use this book in conjunction

4. Move your hands to the heart and the lungs. Ask for the power to see the cells of the heart and lungs. Give them the command: "Lungs and heart cells, listen to the command". If there is no sickness, just clean them out. See the cells and clean them out with violet light. If there is sickness, tell the sickness to "go away - be clear, clean and bright; fill with violet light and return to normal function". Make sure that you say this part aloud. Give the command in a very firm tone of voice.





Fig. 4.60
"Heart and lung cells please listen; clear, clean & bright; fill with violet light and return to normal function".

5. Move your hands to cover the left and right sides of the ribcage. Ask for the power to see the cells of the liver, gallbladder, spleen, pancreas and stomach. Give them the command: "Liver, gallbladder, spleen, pancreas and stomach cells, listen to the command". If there is no sickness, just clean them out. If there is sickness, tell the sickness to, "go away - be clear, clean and bright; fill with violet light and return to normal function". Make sure that you say this part aloud. Give the command in a very firm tone of voice.





Fig. 4.61
"Liver, gallbladder, pancreas and spleen cells please listen; clear, clean and bright: fill with violet light and return to normal function".

with the comprehensive texts and other related resources annotated at the end of each chapter.

The current contributors would like to thank their predecessors on the Medical Student Education Committee who, partially through this book, built a great foundation for medical student learning. Current contributors include Denise R. Chamblee, MD; Jennie M. Hunnewell, MD; Rebecca K. Morgan, MD; and Scott C. Sigler, MD. Thanks are due the following individuals who contributed photographs to this edition: David W. Parke II, MD; Bradley K. Farris, MD; Reagan H. Bradford, Jr, MD; Anne L. Coleman, MD, PhD; and Neil R. Miller, MD.

Who's Who in Eye Care

Ophthalmologist

An ophthalmologist is a physician (doctor of medicine or doctor of osteopathy) who specializes in the medical and surgical care of the eyes and visual system and in the prevention of eye disease and injury. The ophthalmologist has completed four or more years of college premedical education, four or more years of medical school, one year of internship, and three or more years of specialized medical, surgical, and refractive training and experience in eye care. The ophthalmologist is a specialist who is qualified by lengthy medical education, training, and experience to diagnose, treat, and manage all eye and visual system problems and is licensed by a state regulatory board to practice medicine and surgery. The ophthalmologist is the medically trained specialist who can deliver total eye care: primary, secondary, and tertiary care services (ie, vision services, spectacles, contact lenses, eye examinations, medical eye care, and surgical eye care), diagnose general diseases of the body and treat ocular manifestations of systemic diseases.

Optometrist

An optometrist is a health service provider who is involved exclusively with vision problems. Optometrists are specifically educated and trained by an accredited optometry college in a four-year course, but they do not attend medical school. They are state licensed to examine the eyes and to determine the presence of vision problems. Optometrists determine visual acuity and prescribe spectacles, contact lenses, and eye exercises. Optometrists may perform all services listed under the definition of opticians. Most states have passed legislation that permits optometrists to treat some eye conditions.

Optician

An optician is a professional who makes, verifies, delivers, and fits lenses, frames, and other specially fabricated optical devices and/or contact lenses upon prescription to the intended wearer. The optician's functions include prescription analysis and interpretation; determination of the lens forms best suited to the wearer's needs; the preparation and delivery of work orders for the grinding of lenses and the fabrication of eye wear; the verification of the finished ophthalmic products; and the adjustment, replacement, repair, and reproduction of previously prepared ophthalmic lenses, frames, and other specially fabricated ophthalmic devices.

Test Your Knowledge

Test you present awareness about eye care by taking this quick true-false quiz. The test contains many statements that you may have heard before. Answers follow.

1. Reading for prolonged periods in dim light can be harmful to the eyes. T F
2. Children should be taught not to hold their books too close when reading, because doing so can harm their eyes. T F
3. Wearing glasses that are too strong can damage the eyes. T F
4. If children sit too close to the television set, they may damage their eyes. T F
5. Older people who may be having trouble seeing should not use their eyes too much because they can wear them out sooner. T F
6. People with weak eyes should rest their eyes often to strengthen them. T F
7. In time, children usually outgrow crossed eyes. T F
8. Contact lenses can correct nearsightedness, so that eventually neither contact lenses nor eyeglasses will be needed. T F
9. Children who have a problem learning to read are likely to have an eye coordination problem and can be helped with special exercises. T F
10. A cataract can sometimes grow back after cataract surgery. T F
11. A cataract has to be "ripe" before surgery can be done. T F
12. Nearsighted people become farsighted as they age, and farsighted people become nearsighted. T F
13. In older people, a sign of healthy eyes is the ability to read the newspaper without glasses. T F
14. People who wear glasses should have their vision checked every year to determine whether a change in prescription is needed. T F
15. Watching a bright television picture in a dimly lighted room can be harmful to the eyes if done for long periods. T F
16. Ideally all people should use an eyewash regularly to cleanse their eyes. T F
17. A blue eye should not be selected for transplantation into a brown-eyed person. T F
18. In rare instances, a contact lens can be lost behind the eye and even work its way into the brain. T F

19. A cataract is actually a film over the eye that can be peeled off with surgery. T F
20. Headaches are usually due to eye strain. T F

Answers

1. False. Except in extreme circumstances, the way in which light enters the eye is not important. Reading in dim light does not harm the eyes any more than taking a photograph in dim light would harm a camera.
2. False. Holding books close to the eyes to read is common in children, and no harm can come of it. Their eyes can accommodate (focus on near objects) easily and can keep near objects in sharp focus. In rare cases, holding a book close could be a sign of severe nearsightedness, which should be investigated; however, the habit of close reading itself will not cause nearsightedness in children.
3. False. Because glasses are hung in front of the eyes (from the nose and ears), they affect light, not the eye. Looking through them cannot harm the eyes. However, an incorrect prescription may result in blurred vision, which is uncomfortable and may lead to headaches.
4. False. Children with normal sight commonly want to sit close to the television set, just as they want to get close to reading material. This will not harm their eyes. All individuals will hold reading material or watch television at a distance that is comfortable for them.
5. False. The eyes are made for seeing. No evidence exists that using them for their purpose will wear them out.
6. False. Eyes that are "weak" for whatever reason did not become so from overuse, so they cannot be improved by rest.
7. False. Crossed eyes in children should always be considered serious; in fact, the condition requires referral to an ophthalmologist. Some children have apparent but not truly crossed eyes. In such cases, the apparent crossing is due to a broad bridge of the nose in young children. As the nose matures, this apparent crossing lessens and disappears. However, truly crossed eyes should never be ignored, as the condition will not improve with time.
8. False. Incorrectly fitted contact lenses can change the shape of the cornea but do not thereby correct myopia. Intentionally fitting contact lenses incorrectly to change corneal shape can cause permanent harm to the eyes.
9. False. The idea that reading problems are due to poor eye coordination is a misconception, as the results of many controlled studies have indicated.
10. False. Because a cataract is an opacity in the lens of the eye, the cataract cannot grow back when the entire lens is removed (intracapsular extraction). However, the posterior capsule of the lens may

opacify when the lens is not completely removed (extracapsular extraction). This latter technique is nevertheless currently preferred.

11. False. The need for cataract surgery is indicated principally by the degree of functional impairment caused by the cataract, not by any criteria related to its duration.
12. False. All individuals become presbyopic (their eyes lose some of their ability to adjust) with age, regardless of their underlying refractive error.
13. False. The ability of an older person to read without glasses may show only that they have myopia in one eye with reasonably good visual acuity. The nearsightedness could be caused by a cataract. Furthermore, the field of vision could be extremely constricted, as in advanced glaucoma, or one eye could be completely blind.
14. False. Glasses do not affect the health of the eyes. As long as an individual is satisfied with the vision provided by the present glasses, routine visual acuity examinations are generally unnecessary.
15. False. As indicated in some earlier answers, the eye cannot be harmed by the way in which light enters it. The eye merely deals with light, regardless of contrast. Watching television with or without illumination is a matter of comfort rather than harm. An individual who finds the marked contrast of a bright television picture in a dimly lighted room uncomfortable should turn on a light, but neither situation will harm the eyes.
16. False. Eyewash should be used as infrequently as possible. As long as it is functioning properly, the eyes' natural lubrication system is adequate for cleansing them.
17. False. Only the cornea can be transplanted, and the cornea is colorless in all eyes. (The iris gives eyes their color.)
18. False. The conjunctiva prevents a contact lens from passing behind the eye.
19. False. A cataract is an imperfection in the transparency of the normal lens of the eye, not a "growth" or "film" that covers the eye. If the lens becomes opaque enough to significantly impair a person's functional vision, all or most of the lens is surgically removed. Nothing is "peeled" away.
20. False. Headaches are not usually caused by ocular factors.

You will find more detailed and specific rationales for these answers in the various chapters of this text and in the resources suggested at the end of each chapter.

Chapter 1

The Eye Examination

Objectives

As a primary care physician, you should be able to recognize the significant external and internal ocular structures of the normal eye and to perform a basic eye examination.

To achieve these objectives, you should learn

- The essentials of ocular anatomy
- To measure and record visual acuity
- To assess pupillary reflexes
- To evaluate ocular motility
- To use the direct ophthalmoscope for a systematic fundus examination and assessment of the red reflex
- To dilate the pupils as an adjunct to ophthalmoscopy
- To evaluate visual fields by confrontation

Relevance

The proper performance of a basic eye examination is a crucial skill for the primary care physician. Systematic examination of the eye enables the primary care physician to evaluate ocular complaints and provide either definitive treatment or appropriate referral to an ophthalmologist. Furthermore, many eye diseases are "silent," or asymptomatic, while serious ocular damage is occurring. Performing a basic eye examination can reveal such conditions and ensure that patients receive the timely care they need. A basic eye examination may provide early warning signs of any of the following conditions:

- **Blinding eye disease** Important examples of blinding eye diseases that are potentially treatable if discovered early include cataract, glaucoma, diabetic retinopathy, macular degeneration, and, in young children, amblyopia.
- **Systemic disease** Potentially life-threatening systemic disorders that may involve the eye include diabetes, hypertension, temporal arteritis, and an embolism from the carotid artery or the heart.
- **Tumor or other disorders of the brain** These conditions may threaten both vision and life. Important examples include meningioma, aneurysms, and multiple sclerosis.

Basic Information

Figures 1.1 through 1.3 show key external and internal ocular structures. The principal anatomic structures are described below.

Anatomy

- Eyelids The outer structures that protect the eyeball and lubricate the ocular surface. Within each lid is a tarsal plate containing meibomian glands. The lids come together at the medial and lateral canthi. The space between the two open lids is called the *palpebral fissure.*
- Sclera The thick outer coat of the eye, normally white and opaque.
- **Limbus** The junction between the cornea and the sclera.
- Iris The colored part of the eye that screens out light, primarily via the pigment epithelium, which lines its posterior surface.
- Pupil The circular opening in the center of the iris that adjusts the amount of light entering the eye. Its size is determined by the parasympathetic and sympathetic innervation of the iris.
- Conjunctiva The thin, vascular tissue covering the inner aspect of the eyelids (palpebral conjunctiva) and sclera (bulbar conjunctiva).
- Cornea The transparent front "window" of the eye that serves as the major refractive surface.
- Extraocular muscles The six muscles that move the globe medially (medial rectus), laterally (lateral rectus), upward (superior rectus and inferior oblique), downward (inferior rectus and superior oblique), and torsionally (superior and inferior obliques). These muscles are supplied by three cranial nerves: cranial nerve IV, which innervates the superior oblique; cranial nerve VI, which innervates the lateral rectus; and cranial nerve III, which controls the remainder of the extraocular muscles.
- Anterior chamber The space that lies between the cornea anteriorly and the iris posteriorly. The chamber contains a watery fluid called aqueous humor.
- Lens The transparent, biconvex body suspended by the zonules behind the pupil and iris; part of the refracting mechanism of the eye.
- Ciliary body The structure that produces aqueous humor. Contraction of the ciliary muscle changes tension on the zonular fibers that suspend the lens and allows the eye to focus from distant to near objects (accommodation).
- Posterior chamber The small space filled with aqueous humor behind the iris and in front of the vitreous.
- Vitreous cavity The relatively large space (4.5 cc) behind the lens that extends to the retina. The cavity is filled with a transparent jelly-like material called vitreous humor.
- Retina The neural tissue lining the vitreous cavity posteriorly. Essentially transparent except for the blood vessels on its inner surface, the retina sends the initial visual signals to the brain via the optic nerve. The retina, macula, choroid, and optic disc are sometimes referred to as the *retinal fundus* or, simply, *fundus.*

Macula The area of the retina at the posterior pole of the eye responsible for fine, central vision. The oval depression in the center of the macula is called the fovea.

- Choroid The vascular, pigmented tissue layer between the sclera and the retina. The choroid provides the blood supply for the outer retinal layers.
- **Optic disc** The portion of the optic nerve visible within the eye. It is comprised of axons whose cell bodies are located in the ganglion cell layer of the retina.

Optics

The cornea and the lens make up the refractive surfaces of the eye. The cornea provides approximately two thirds of the refractive power of the eye, and the lens approximately one third to form an image on the retina. Reduced visual acuity will result if the axial length of the eye is either too short (ie, hyperopia; also called *hypermetropia*) or too long (ie, myopia) for the refracting power of the cornea and lens. Visual acuity also is reduced if the refracting power of the cornea and lens is different in one meridian than in another (ie, astigmatism). These optical defects can be corrected by the use of either eyeglass lenses or contact lenses. A pinhole placed directly in front of the eye will narrow the effective pupillary aperture and thereby minimize the blurring induced by a refractive error.

The ability of the ciliary muscle to contract and the lens to become more convex is called accommodation. With increasing age, the lens of every eye undergoes a progressive hardening, with loss of ability to change its shape. Loss of accommodation is manifested by a decreased ability to focus on near objects (ie, presbyopia), while corrected distance visual acuity remains normal. Presbyopia develops progressively with age but becomes clinically manifest in the early to mid 40s, when the ability to accommodate at reading distance (35 to 40 cm) is lost. Presbyopia is corrected by eyeglass lenses, either as reading glasses or as the lower segment of bifocal lenses, the upper segment of which can contain a correction for distance visual acuity if needed. Some myopic patients with presbyopia simply remove their distance glasses to read, because they do not need to accommodate in an uncorrected state.

Visual Acuity

Visual acuity is a measurement of the smallest object a person can identify at a given distance from the eye. The following are common abbreviations used to discuss visual acuity:

- VA visual acuity
- OD (oculus *dexter*) right eye
- OS (*oculus sinister*) left eye
- OU (*oculus uterque*) both eyes


Iris
Conjunctiva
Posterior chamber
Zonules
Optic disc
Central retinal artery and vein
Dura mater
Anterior chamber
Cornea
Pupil
Limbus
Schlemm's canal
Lens
Ciliary body
Sclera
Choroid
Retina
Vitreous cavity
Fovea
Macula
Optic nerve

Figure 1.1 Cross-section of the eye. (Courtesy Christine Gralapp.)


Upper eyelid
Pupil
Limbus
Iris
Sclera
Lower eyelid
Upper lacrimal punctum
Superior canaliculus
Lacrimal sac
Inferior canaliculus
Lower lacrimal punctum
Nasolacrimal duct

Figure 1.2 External landmarks.
(Courtesy Christine Gralapp.)


Inferior oblique
Superior oblique
Medial rectus
Superior rectus
Inferior rectus
Lateral rectus

Figure 1.3 Extraocular muscles.
(Courtesy Christine Gralapp.)

6. Move your hands to the large and small intestine on the front of the abdomen. Ask for the power to see the cells of the intestines. Give them the command: “Large and small intestine, listen to the command”. If there is no sickness, just clean them out. See the cells and clean them out with violet light. If there is sickness, tell the sickness to, “go away - be clear, clean and bright; fill with violet light and return to normal function”. Make sure that you say this part aloud. Give the command in a very firm tone of voice.



Intestines **Healthy cells**

Fig. 4.62 *“Small and large intestine cells listen to the command: clear, clean and bright; fill with violet light and return to normal function”.*

7. Move your hands to the kidney and sexual organs and ask for the power to see their cells. Give the command: “Kidney and sexual organ cells listen to the command: Clear, clean and bright; fill with violet light and return to normal function”. Gather the violet light again and let it pour down and fill all the cells. See the violet light again and feel and see that all the cells are, “clear, clean and bright”. Smile.



Kidney **Testes** **Ovaries**

Fig. 4.63 *“Kidneys and Sexual Organs listen”.*



Figure 1.4 Equipment for a basic eye examination. **(A)** Electronic tonometer (or other instrument for measuring intraocular pressure). **(B)** Near vision card. **(C)** Penlight. **(D)** Direct ophthalmoscope. **(E)** Fluorescein strips. **(F)** Mydriatic. **(G)** Topical anesthetic. (Part **A** courtesy Mentor.)

When to Examine

All patients should have an eye examination as part of a general physical examination by the primary care physician. Visual acuity, pupillary reactions, extraocular movements, and direct ophthalmoscopy through undilated pupils constitute a minimal examination. Pupillary dilation for ophthalmoscopy is required in cases of unexplained visual loss or when fundus pathology is suspected (eg, diabetes mellitus).

Distance visual acuity measurement should be performed in all children as soon as possible after age **3** because of the importance of detecting amblyopia early. The tumbling E chart (see Chapter 6) is used in place of the standard Snellen eye chart.

Depending on what the examination reveals and on the patient's history, additional tests may be indicated (listed below). Details on how to perform both basic and adjunctive ocular tests appear in the following section, "How to Examine."

Additional Tests

- **Tonometry** Should be performed as clinically indicated whenever the diagnosis of glaucoma is suspected.
- Anterior chamber depth assessment Indicated when narrow-angle glaucoma is suspected and prior to pupillary dilation.

a Confrontation field testing May be suggested by the patient's history or symptoms to confirm a suspected field defect.

- Color vision testing May be part of an eye examination when requested by the patient or by another agency and in patients with retinal or optic nerve disorders.
- Fluorescein staining Is necessary when a corneal epithelial defect or abnormality is suspected.
- Eversion of the upper lid Is necessary when the presence of a foreign body is suspected.

How to Examine

Equipment for an eye examination consists of a few items that can be transported, if necessary, with other medical instruments (Figure 1.4). The slit-lamp biomicroscope is a stationary office instrument that augments the inspection of the anterior segment of the eye by providing an illuminated, magnified view. Standard equipment in an ophthalmologist's office, the slit lamp is also available in many emergency facilities.

Distance Visual Acuity Testing

Distance visual acuity is usually recorded as a ratio or fraction comparing patient performance with an agreed-upon standard. In this notation, the first number represents the distance between the patient and the eye chart (usually the Snellen eye chart, Figure 1.5); the second number represents the distance at which the letters can be read by a person with normal acuity. Visual acuity of 20/80 thus indicates that the patient can recognize at 20 feet a symbol that can be recognized by a person with normal acuity at 80 feet.

Visual acuity of 20/20 represents normal visual acuity. Many "normal" individuals actually see better than 20/20—for example, 20/15 or even 20/12. If this is the case, you should record it as such. Alternative notations are the decimal notation (eg, 20/20 = 1.0; 20/40 = 0.5; 20/200 = 0.1) and the metric notation (eg, 20/20 = 6/6, 20/100 = 6/30).

Visual acuity is tested most often at a distance of 20 feet, or 6 meters. Greater distances are cumbersome and impractical; at shorter distances, variations in the test distance assume greater proportional significance. For practical purposes, a distance of 20 feet may be equated with optical infinity.

To test distance visual acuity with the conventional Snellen eye chart, follow these steps:

1. Place the patient at the designated distance, usually 20 feet (6 meters), from a well-illuminated Snellen chart (see Figure 1.5). If glasses are normally worn for distance vision, the patient should wear them.
2. By convention, the right eye is tested and recorded first. Completely occlude the left eye using an opaque occluder or the palm of your hand; alternatively, have the patient cover the eye.



Figure 1.5 Snellen eye chart.

3. Ask the patient to read the smallest line in which he can distinguish more than one half of the letters. (If the E chart is being used, have the patient designate the direction in which the strokes of the E point.)
4. Record the acuity measurement as a notation (eg, 20/20) in which the first number represents the distance at which the test is performed and the second number represents the numeric designation for the line read.
5. Repeat the procedure for the other eye.
6. If visual acuity is 20/40 or less in one or both eyes, repeat the test with the subject viewing the test chart through a pinhole occluder and record these results. The pinhole occluder may be used over the subject's glasses.

If a patient cannot see the largest Snellen letters, proceed as follows:

1. Reduce the distance between the patient and the chart. Record the new distance as the numerator of the acuity designation (eg, 5/70).
2. If the patient is unable to see the largest Snellen letter at *3* feet, hold up one hand, extend two or more fingers, and ask the patient to count the number of fingers. Record the distance at which counting fingers is done accurately (eg, CF 1 ft).
3. If the patient cannot count fingers, determine whether or not he can detect the movement of your hand. Record a positive response as hand motion (eg, HM 2 ft).

4. If the patient cannot detect hand motion, use a penlight to determine whether he can detect the presence or direction of light. Record the patient's response as LP (light perception), LP with projection (light perception with direction), or NLP (no light perception).

Visual Impairment vs Visual Disability

The term visual acuity impairment (or simply visual *impairment*) is used to describe a condition of the eyes. Visual disability describes a condition of the individual. The disabling effect of an impairment depends in part on the individual's ability to adapt and to compensate. Two individuals with the same visual impairment measured on a Snellen eye chart may show very different levels of functional disability. Table 1.1 summarizes the differences between visual impairment and visual disability.

Table 1.1 Visual Impoairment vs Visual Disability

Visual Impairment	Visual Disability	Comment
20/12 to 20/25	Normal vision	Healthy young adults average better than 20/20 acuity.
20/30 to 20/70	Near-normal vision	Usually causes no serious problems, but vision should be explored for potential improvement or possible early disease. Most states will issue a driver's license to individuals with this level of vision in at least one eye.
20/80 to 20/160	Moderate low vision	Strong reading glasses or vision magnifiers usually provide adequate reading ability; this level is usually insufficient for a driver's license.
20/200 to 20/400 or CF 10 ft	Severe low vision; legal blindness by US definition	Gross orientation and mobility generally adequate, but difficulty with traffic signs, bus numbers, etc. Reading requires high-power magnifiers; reading speed reduced.
CF 8 ft to 4 ft	Profound low vision	Increasing problems with visual orientation and mobility. Long cane useful to explore environment. Highly motivated and persistent individuals can read with extreme magrufication. Others rely on nonvisual communication: braille, "talking books," radio, etc.
Less **than** CF 4 ft	Near-total blindness	Vision unreliable, except under ideal circumstances; must rely on nonvisual aids.
NLP	Total blindness	No light perception; must rely entirely on other senses.

Near Visual Acuity Testing

Near visual acuity testing may be performed if the patient has a complaint about near vision. Otherwise, testing "at near" is performed only if distance testing is difficult or impossible—at the patient's bedside, for instance. In such situations, testing with a near card may be the only feasible way to determine visual acuity.

If the patient normally wears glasses for reading, he should wear them during testing. This holds true for the presbyopic patient in particular. The patient holds the test card—for example, a Rosenbaum pocket vision screener (Figure 1.6)—at the distance specified on the card. This distance is usually 14 inches or 35 centimeters. While the examiner occludes one of the patient's eyes, the patient reads the smallest characters legible on the card. The test is then repeated for the other eye.

Letter size designations and test distances vary. To avoid ambiguity, both should be recorded (eg, J5 at 14 in, 6 point at 40 cm). Some near cards carry distance-equivalent values. These are valid only if the test is done at the recommended distance. If a standard near vision card is not available, any printed matter such as a telephone book or a newspaper may be substituted. Both the approximate type size read and the distance at which the material was held are recorded.

Visual Acuity Estimation in an Uncooperative Patient

Occasionally, you will encounter a patient who is unwilling or unable to cooperate with standard visual acuity testing or who may be suspected of faking blindness. Because the typical visual acuity test will not work for such a patient, you will need to be alert to other signs. Withdrawal or a change in facial expression in response to light or sudden movement indicates the presence of vision. A brisk pupillary response to light also suggests the presence of vision. The exception to this is the patient with cortical blindness, which is due to bilateral widespread destruction of the visual cortex. If there is any doubt, referral to an ophthalmologist is recommended.

Chapter 6 discusses visual testing of infants and toddlers.

External Inspection

With adequate room light, the examiner can inspect the lids, surrounding tissues, and palpebral fissure. Palpation of the orbital rim and lids may be indicated, depending on the history and symptoms. Inspection of the conjunctiva and sclera is facilitated by using a penlight and having the patient look up while the examiner retracts the lower lid or look down while the examiner raises the upper lid. The penlight also aids in the inspection of both the cornea and the iris.



ROSENBAUM POCKET VISION SCREENER

Card is held in good light 14 inches from eye Record vision for each eye separately with and without glasses Presbyopic patients should read thru bifocal segment Check myopes with glasses only

Figure 1.6 Rosenbaum pocket vision screener.

Pupillary Reaction Testing

Inspection of the pupils should be part of the physical examination. The patient's direct and consensual pupillary reactions to light are evaluated in a room with reduced illumination and with the patient looking at a distant object.

To test the direct pupillary reaction to light, first direct the penlight at the patient's right eye and see if it constricts (a normal reaction). Repeat for the left pupil. To test the consensual pupillary reaction to light, direct the penlight at the right eye and watch the left pupil to see if it constricts along with the right pupil (a normal consensual response). Repeat for the left pupil, watching the right pupil for the response. Occasionally, this examination may reveal indications of neurologic disease. (See Chapter 7 for a description of the swinging-flashlight test for the detection of an afferent defect in the anterior visual pathway.) Pupillary inspection may reveal active or prior ocular disease with alterations in pupillary shape or size that are the result of local intraocular processes (eg, damage to the pupillary sphincter or adhesion of the iris to the lens).

Ocular Motility Testing

The patient is asked to follow an object in six directions, the cardinal fields of gaze:

1. fight and up
2. Right
3. Right and down
4. Left and up
5. Left
6. Left and down

This enables the examiner to systematically test each muscle in its primary field of action (Table 1.2). Thus, a possible isolated weakness or paralysis of muscle can best be detected. (See Chapter 6 for a description of the cover test for the detection of strabismus, a misalignment of the two eyes.)

Ophthalmoscopy

When examining the patient's right eye, hold the direct ophthalmoscope in the right hand and use your right eye to view the patient's eye. Use your left hand and left eye to examine the patient's left eye. The patient's eyeglasses are removed, and, barring large astigmatic refractive errors, most examiners prefer to remove their own glasses as well. Contact lenses worn by either patient or examiner may be left in place.

Pupillary Dilation

Pharmacologic dilation of the patient's pupils greatly facilitates ophthalmoscopy. Recommended agents include tropicamide 1% and phenylephrine hydrochloride 2.5% (see Chapter 9). Dilation of the pupil should not be done under the following conditions:

1. If assessment of anterior chamber depth suggests a shallow chamber and a narrow angle, do not dilate because an attack of angle-closure glaucoma might be precipitated.
2. If a patient is undergoing neurologic observation and pupillary signs are being watched (eg, a head-injured patient), do not dilate until the neurologist or neurosurgeon determines it is safe to do so.

Table 1.2 Cardinal Fields of Gaze

Right and **Up**	Left and **Up**
Right superior rectus	Left superior rectus
Left inferior oblique	Right inferior oblique
Right	Left
Right lateral rectus	Left lateral rectus
Left medial rectus	Right medical rectus
Right and Down	Left and Down
Right inferior rectus	Left inferior rectus
Left superior oblique	Right superior oblique

3. If a patient has had a cataract extraction with implantation of an iris-supported intraocular lens, do not dilate because the lens implant could dislocate. The iris-supported intraocular lens was a popular implant at one time but is no longer available, although many individuals still retain these implants in their eyes. The pupil in such a patient is usually square-shaped.

See Chapter 9 for instructions on applying topical agents.

Method of Direct Ophthalmoscopy

To perform direct ophthalmoscopy, follow these steps:

1. Have the patient comfortably seated. Instruct the patient to look at a point on the wall straight ahead, trying not to move the eyes.
2. Set the focusing wheel at about +8. Set the aperture wheel to select the large, round, white light.
3. Begin to look at the right eye about 1 foot from the patient. Use your right eye with the ophthalmoscope in your right hand. When you look straight down the patient's line of sight at the pupil, you will see the red reflex (see below).
4. Place your free hand on the patient's forehead or shoulder to aid your proprioception and to keep yourself steady.
5. Slowly come close to the patient at an angle of about 15° temporal to the patient's line of sight. Try to keep the pupil in view. Turn the focusing wheel to bring the patient's retina into focus.
6. When a retinal vessel comes into view, follow it as it widens to the optic disc, which lies nasal to the center of the retina.
7. Examine the optic disc, retinal blood vessels, retinal background, and macula in that order (see below).
8. Repeat for the left eye.

Red Reflex

Light reflected off the fundus of the patient produces a red reflex when viewed through the ophthalmoscope at a distance of 1 foot. A normal red reflex (Slide 1) is evenly colored and is not interrupted by shadows. Opacities in the media appear as black silhouettes and can be best appreciated when the pupil has been dilated (see Slide 17 in Chapter **3).**

Optic Disc

In most cases, when viewed through the ophthalmoscope, the normal optic disc (Slide 2) is slightly oval in the vertical meridian and has a pink color. A central depression in the surface of the disc is called the *physiologic cup*. The optic disc can be thought of as the yardstick of the ocular fundus. Lesions seen with the ophthalmoscope are measured in disc diameters (1 disc diameter equals approximately 1.5 mm).



Slide 1 Red reflex. Reddish light reflected from the fundus can be visible even at a distance of 1 or 2 feet when the direction of illumination and the direction of observation approach each other—a condition that can be achieved with the ophthalmoscope.



Slide 2 Normal posterior pole. A normal optic disc is shown, with a small central physiologic cup and healthy neural rim. Major branches of the central retinal artery emanate from the disc, whereas the major branches of the central retinal vein collect at the disc. Temporal to the disc is the macula, which appears darker; no blood vessels are present in the center.

A great deal of normal variation exists in the appearance of the optic disc. The size of the physiologic cup varies among individuals. (See Chapter 3 for a discussion of glaucomatous cupping.) The pigmented coats of the eye—the retinal pigment epithelium and the choroid—frequently fail to reach the margin of the optic disc, producing a hypopigmented crescent (Slide **3,** left). Such crescents are especially common in myopic eyes on the temporal side of the optic disc. Conversely, an excess of pigment may be seen in some eyes, producing a heavily pigmented margin along the optic disc (see Slide 3, right). The retinal nerve fibers (ie, ganglion cell axons) ordinarily are nonmyelinated at the optic disc and in the retina, but occasionally myelination may extend onto the surface of the optic disc and retina, producing a dense, white superficial opacification with feathery edges (Slide 4).

Retinal Circulation

The retinal circulation is composed of arteries and veins, visible with the ophthalmoscope (compare Figure 1.7 with Slide 2). The central retinal artery branches at or on the optic disc into divisions that supply the four quadrants of the inner retinal layers; these divisions lie superficially in the



Slide 3 Scleral crescent and pigmented crescent. This figure shows normal variants of the optic disc. On the left, retinal and choroidal pigmentation does not reach the disc margin, leaving an exposed white scleral crescent. On the right, pigment accumulation is seen at the disc margin.



Slide 4 Myelinated nerve fibers. Usually, the axons of the retinal ganglion cells acquire myelin sheaths only behind the optic disc. Occasionally, as a variant, myelin is deposited along axons at the border of the disc or even away from the disc, elsewhere in the retina. These white, feathery patterns may be mistaken for papilledema.

nerve fiber layer. A similarly arranged system of retinal veins collects at the optic disc, where spontaneous pulsation (with collapse during systole) may be observed in 80% of normal eyes. The ratio of normal vein-to-artery diameter is 3:2. Arteries are usually lighter in color than veins and typically have a more prominent light reflex from their surfaces than do veins. The examiner should follow arteries from the disc and veins back to the disc in each quadrant, noting in particular the arteriovenous (A/V) crossing patterns.


Sacrum
Rectum
Uterine (Fallopian) Tube
Ovary
Uterus
Cervix of Uterus
Clitoris
Mons Pubis
Urethra
External Urethral Orifice
Coccyx
Anus
Vagina
Urinary Bladder
Urinary Bladder
Seminal Vesicle
Prostate
Pubic Bone
Ductus (Vas) Deferens
Urethra
Penis
Testis
Scrotum
Glans Penis

Fig. 4.64 *Male and Female Sexual Organs*



Egg **Sperm**

Fig. 4.65 *"Clear, clean and bright: fill with Violet Light and return to normal function".*



Figure 1.7 Fundus diagram.

Retinal Background

The normal retinal background is a uniform red-orange color due primarily to the pigmentation of the retinal pigment epithelium. The blood and pigment of the choroid also contribute to the appearance of the retinal background. For example, in heavily pigmented eyes, the fundus may have a darker color due to increased choroidal pigment content.

Macula

The normal macula (see Figure 1.7 and Slide 2), located directly temporal and slightly inferior to the optic disc, usually appears darker than the surrounding retina because the specialized retinal pigment epithelial cells of the macula are taller and more heavily pigmented. In some eyes, the macula may appear slightly yellow due to the xanthophyll pigment in the retina. The central depression of the fovea may act as a concave mirror during ophthalmoscopy and produce a light reflection known as the *foveal reflex*.

Intraocular Pressure Measurement

Intraocular pressure (IOP) is determined largely by the outflow of aqueous humor from the eye. The greater the resistance to outflow, the higher the intraocular pressure. Alterations in the actual production of aqueous humor also have an effect on the intraocular pressure.



Figure 1.8 Electronic tonometry. Electronic tonometry can be performed with the patient in any position. (Courtesy Mentor.)

Intraocular pressure varies among individuals. An IOP of 15 millimeters of mercury (mm Hg) represents the mean in a "normal" population. However, an IOP in the range from 10 to 21 mm Hg falls within 2 standard deviations of the mean.

Measurement of IOP is an essential part of a glaucoma screening examination, along with ophthalmoscopic assessment of the optic cup. IOP determination is especially helpful for diagnosing patients in the early stages of chronic open-angle glaucoma, when pressure is elevated but pathologic cupping has not yet developed. IOP determination is also useful when the diagnosis of acute angle-closure glaucoma is being considered.

In the past, the Schiøtz (indentation) tonometer has been used by primary care physicians to measure intraocular pressure. Schiøtz tonometry is an inexpensive and simple method of measuring intraocular pressure and, if available, can be used to measure the intraocular pressure in a patient with suspected angle-closure glaucoma. With the patient in a supine position, the Schiøtz device with a given weight is placed on the patient's anesthetized cornea and indents the cornea in an amount related to the IOP. A printed conversion table that accompanies the tonometer is used to determine the IOP in millimeters of mercury.

Currently, handheld electronic tonometers are available in some hospital emergency departments to measure intraocular pressure (Figure 1.8). One such device is brand-named Tono-Pen. An electronic tonometer is a solid-state strain gauge that converts the IOP to an electrical signal. This battery-operated device weighs just a few ounces and can be used with the patient in any position, as opposed to other devices that require the patient to be either seated or supine. The intraocular pressure results are obtained rapidly with the electronic tonometer and correlate highly with those obtained by the Goldmann applanation tonometer. Electronic tonometers are expensive and require daily calibration.

To perform electronic tonometry, the practitioner instills topical anesthetic in the patient's eyes and, starting with the patient's right eye, separates the lids and applies the calibrated tonometer to the patient's cornea. The pressure reading and reliability rating displayed on the device are noted in the patient's record.

Topical anesthetics applied for tonometry have little effect on the margins of the eyelids. If the tonometer touches the lids, the patient will feel it and squeeze the lids together, impeding IOP measurement. This can be avoided by holding the patient's lids wide apart with the free hand while applying the tonometer tip with the other hand. Take care not to apply digital pressure to the eyeball while holding the lids apart, as it may produce a falsely high pressure reading. Tonometry should never be attempted in a patient suspected of having a ruptured globe; doing so could result in further damage to the eye.

Anterior Chamber Depth Assessment

When the anterior chamber is shallow, the iris becomes convex as it is bowed forward over the lens. Under these conditions, the nasal iris is seen in shadow when a light is directed from the opposite side (Figure 1.9). As the shallowness of the anterior chamber increases, so do the convexity of the iris and the shaded view of the nasal iris. A shallow anterior chamber may indicate narrow-angle glaucoma (also called angle-closure glaucoma) or a narrow angle that could close with pupillary dilation.

To assess anterior chamber depth, follow these steps:

1. Shine a light from the temporal side of the head across the front of the eye parallel to the plane of the iris.
2. Look at the nasal aspect of the iris. If two thirds or more of the nasal iris is in shadow, the chamber is probably shallow and the angle narrow.



Figure 1.9 Estimation of anterior chamber depth.

3. If you are unsure of the extent of shadow, direct the light more from the front of the eye, which will eliminate shadows entirely, and then return the light to the temporal side of the head.
4. Repeat the test for the other eye.

Confrontation Field Testing

The examiner takes a position in front of the patient. The patient is asked to cover the left eye with the palm of the left hand; the examiner closes the right eye. Thus, the field of the examiner's left eye is used as a reference in assessing the field of the patient's right eye. The patient is asked to fixate on the examiner's left eye and then count the fingers of the examiner in each of the four quadrants of the visual field. Wiggling the fingers as a visual stimulus is not desirable. After the patient's right eye is tested, the procedure is repeated for the left eye, with the patient covering the right eye with the palm of the right hand, and the examiner closing the left eye.

Amsler Grid Testing

Amsler grid testing is a method of evaluating the functioning of the macula. (See Figure 3.4 and Chapter **3** for details.)

Color Vision Testing

The normal retina contains three color-sensitive pigments: red-sensitive, green-sensitive, and blue-sensitive. A developmental deficiency in either the concentration or the function of one or more of these pigments causes various combinations and degrees of congenital color vision defects. Most such defects occur in males through an X-linked inheritance pattern. Color vision abnormalities also may be acquired in individuals with retinal or optic nerve disorders.

Color vision testing is performed with the use of pseudoisochromatic plates (eg, Ishihara plates), which present numbers or figures against a background of colored dots. The person with abnormal color discrimination will be confused by the pseudoisochromatic plates, which force a choice based on hue discrimination alone while concealing other clues such as brightness, saturation, and contours.

The patient should wear glasses during color vision testing if they are normally worn for near vision. The color plates are presented consecutively under good illumination, preferably natural light. Results are recorded according to the detailed instructions provided with the plates. Usually, a fraction is specified, with the numerator equivalent to the number of correct responses and the denominator the total plates presented. The type of color defect can be determined by recording the specific errors and using the instructions provided with the plates.



Figure 1.10
Upper lid eversion.

Upper Lid Eversion

Upper lid eversion is sometimes required to search for conjunctival foreign bodies or other conjunctival signs. Topical anesthetic facilitates this procedure. The patient is asked to look down and the examiner grasps the eyelashes of the upper lid between the thumb and the index finger. A cotton-tipped applicator is used to press gently downward over the superior aspect of the tarsal plate as the lid margin is pulled upward by the lashes (Figure 1.10). Pressure is maintained on the everted upper lid while the patient is encouraged to keep looking down. The examiner should have a penlight within reach to inspect the exposed conjunctival surface of the upper lid for a foreign body or other abnormality. A cotton-tipped applicator soaked in topical anesthetic can be used to remove a foreign body. To return the lid to its normal position, the examiner releases the lid margin and the patient is instructed to look up.

Fluorescein Staining of Cornea

Corneal staining with fluorescein (a yellow-green dye) is useful in diagnosing defects of the corneal epithelium. Fluorescein is applied in the form of a sterile filter-paper strip, which is moistened with a drop of sterile water, saline, or topical anesthetic and then touched to the palpebral conjunctiva. A few blinks spread the fluorescein over the cornea. Areas of bright-green staining denote absent or diseased epithelium (Slide 5). Viewing the eye under cobalt-blue light enhances the visibility of the fluorescence (Slide 6).

Two precautions to keep in mind when using fluorescein are

1. Use fluorescein-impregnated strips instead of stock solutions of fluorescein because such solutions are susceptible to contamination with Pseudomonas species.
2. Have the patient remove soft contact lenses prior to application to avoid discoloration of the lenses.



Slide 5 Fluorescein stain. A corneal abrasion is delineated by fluorescein stain, which marks any area denuded of epithelium. Irregularity of the corneal surface is indicated by the distorted light reflection.



Slide 6 Fluorescein stain highlighted. The addition of cobalt-blue light dramatically defines the corneal epithelial defect.

Summary of Steps in Eye Examination

1. Measure the visual acuity for each eye.
2. Perform a confrontation field test for each eye.
3. Inspect the lids and the surrounding tissues.
4. Inspect the conjunctiva and sclera.
5. Test the extraocular movements.
6. Test the pupils for direct and consensual responses.
7. Inspect the cornea and iris.
8. Assess the anterior chamber for depth and clarity.
9. Assess the lens for clarity through direct ophthalmoscopy.
10. Use the ophthalmoscope to study the fundus, including the disc, vessels, and macula.
11. Perform tonometry when indicated.

Management or Referral

Reduced Visual Acuity

The guidelines below apply for patients in whom reduced visual acuity is found, unless the patient has been seen by an ophthalmologist and the condition has been confirmed as stable.

- **VA less than** *20120* Any patient with visual acuity less than 20/20 in one or both eyes should be referred to an ophthalmologist if visual symptoms are present. Reduced visual acuity is the best single criterion by which to differentiate potentially blinding conditions from less serious ocular disorders.
- **VA less than** *20140* Any patient with visual acuity less than 20/40 in both eyes is an equally important candidate for referral, even in the absence of complaints. Although many such patients suffer only from uncorrected refractive errors, undetected painless but progressive loss of vision does occur in many disorders of the eyes and visual system.
- **Asymmetry** Any patient with a difference in visual acuity between the eyes of 2 lines or more on the Snellen chart should be referred promptly, even if visual acuity in one or both eyes is better than 20/40. Generally, visual function is nearly identical between the eyes; thus, in the absence of known causes of reduced vision, asymmetry of visual acuity may be a sign of occult disease.
- **Presbyopia** Presbyopia is manifested by reduced near vision with no change in distance visual acuity. Middle-aged or elderly patients complaining of this combination will benefit from a referral for the prescription of corrective lenses.

Abnormal Fundus Appearance

Only after performing numerous fundus examinations will the practitioner be able to recognize the great range of normal ophthalmoscopic appearances. When an abnormality is suspected, further studies or consultation may be required because fundus abnormalities can indicate significant ocular or systemic diseases. Ophthalmologic consultation should be sought for fundus changes accompanied by acute or chronic visual complaints.

Photographs of the fundus are taken with a special camera that provides a greater field of view than is possible with the direct ophthalmoscope. Many fundus abnormalities have three-dimensional qualities, such as elevation or depression, but the examiner is limited to a monocular, two-dimensional view with the direct ophthalmoscope. It is necessary to learn to think in three dimensions in order to grasp the pathophysiology.

Shallow Anterior Chamber Depth/Elevated Intraocular Pressure

A patient suspected of having shallow anterior chamber depth (at risk for angle-closure glaucoma) or documented intraocular pressure of 22 mm Hg or greater should be referred to an ophthalmologist for further evaluation.

Points to Remember

1. To prevent patients from reading the visual acuity chart with both eyes, either intentionally or unintentionally, the examiner must ensure that one eye is completely occluded.
2. A well-lighted hallway often provides an acceptable location for distance visual acuity testing with a standard Snellen chart.
3. To avoid measurement error when performing tonometry, the examiner must keep the lids apart by holding them firmly against the bony margins of the orbit, rather than by pressing them against the globe.

Sample Problems

1. A 14-year-old boy is seen for a physical examination at school. He admits to difficulty in reading the blackboard but not in reading textbooks. He does not wear glasses. You record VA as OD 20/100, pinhole 20/25; and OS 20/100, pinhole 20/25. What is your diagnosis? Would you manage or refer this patient?

   Answer: The combination of decreased distance vision with preserved near vision is typical of myopia, which often becomes symptomatic during adolescence. Presumptive evidence of refractive error is provided by the marked improvement in visual acuity that occurs with the use of the pinhole. Note that visual acuity with pinhole frequently does not reach 20/20. The patient should be referred to an ophthalmologist as a regular rather than an urgent consultation.

2. A 78-year-old woman is seen for an annual physical examination and complains of mild difficulty in reading and seeing street signs. You record OD 20/70, no improvement with pinhole; and OS 20/50, no improvement with pinhole. Upon direct ophthalmoscopy, you note a dullness of the red reflex and you have difficulty seeing fundus details in both eyes. What is your diagnosis? Would you manage or refer this patient?

   Answer: Cataract is a common cause of painless progressive loss of vision in older individuals. Her complaints about her visual ability are an indication for referral to an ophthalmologist for evaluation for possible cataract surgery.

3. A 40-year-old man is seen for an annual executive physical. He has no complaints and does not wear glasses. You record VA as OD 20/15; and OS 20/100, no improvement with pinhole. During examination, the patient revealed that he has been aware since childhood that his left eye was a so-called lazy eye—in other words, that he suffered from amblyopia. Would you refer this patient?

Answer: Referral is not indicated since the cause of decreased vision is established and progressive loss is not occurring. Note that this healthy individual has better than 20/20 acuity in his right eye.

4. A 50-year-old man visits your office because he noted decreased visual acuity in the right eye the preceding day while accidentally occluding his left eye. When his present glasses were prescribed 2 years ago, his vision was equal in both eyes. You record VA as OD 20/50, no improvement with pinhole; and OS 20/20. Upon ophthalmoscopy, no abnormalities are detected. What, if any, is your diagnosis? Would you manage or refer this patient?

Answer: The patient has an unexplained loss of vision of unknown duration in one eye. An unexplained decrease in vision in one or both eyes requires referral to an ophthalmologist, because it may indicate occult disease of the eyes or central nervous system that is not detectable by examination methods available to the primary care physician. In this case, the patient's decreased vision was due to a macular disturbance detectable only by more precise methods of examination (eg, special lenses and fluorescein angiography).

5. A 55-year-old man, wearing goggles, was sawing wood in his garage shop. He removed the goggles to clean up and, while sweeping up small wood chips, had the sudden onset of a foreign-body sensation in his right eye. The irritation was not relieved with artificial tears, and it intensified with every blink. His wife rushed him to their family doctor for emergency treatment. The physician was able to examine him after placing a topical anesthetic in the right eye. Visual acuity in the right eye was 20/80. Fluorescein staining revealed multiple vertical linear abrasions of the cornea.

A. Explain the clinical findings.

Answer: By history, this man has been exposed to small particles that could abrade his eye. The vertical linear abrasions in conjunction with the feeling of irritation with each blink imply the presence of a foreign body under the upper lid.

B. What further examination is required, and how is it performed?

Answer: Eversion of the upper lid (see page 20) will expose the foreign body, which can then be removed using a cotton-tipped applicator stick.

Annotated Resources

Gittinger JW Jr: *Ophthalmology: A Clinical Introduction.* Boston: Little, Brown & Co; 1984. Chapter 1, "Ocular History and Examination," covers the eye examination in this excellent introductory text for medical students.

Keltner JL, Wand M, Van Newkirk MR: *Techniques for the Basic Ocular Examination.* San Francisco: American Academy of Ophthalmology; 1989. This videotape covers visual acuity testing, ocular motility testing, confrontation field testing, glaucoma screening, and funduscopic examination.

Newell FW: *Ophthalmology: Principles and Concepts.* 8th ed. St Louis: CV Mosby Co; 1996. This comprehensive text covers in detail anatomy (Chapter 1), physiology (Chapter 2), symptoms of eye disease (Chapter 4), and examination techniques (Chapters 5 and 6).

Pavan-Langston D: *Manual of Ocular Diagnosis and Therapy.* 4th ed. Boston: Little, Brown & Co; 1995. Chapter 1, "Ocular Examination Techniques and Diagnostic Tests," of this spiral-bound manual covers the full gamut of techniques, including those that would be used only by an ophthalmologist.

Trobe JD: *The Physician's Guide to Eye Care.* San Francisco: American Academy of Ophthalmology; 1993. This brief but comprehensive and well-illustrated resource covers the principal clinical ophthalmic problems that nonophthalmologist physicians are likely to encounter, organized for practical use by practitioners. Chapter 1 presents techniques for performing a screening examination, and Chapter 2 outlines rationale, frequency, and components of the routine examination for asymptomatic patients.

Vaughan DG, Asbury T, Riordan-Eva P: *General Ophthalmology.* 14th ed. Norwalk, CT: Appleton & Lange; 1995. This is a useful and popular textbook for medical students, ophthalmology residents, and other physicians. Chapter 1, "Anatomy & Embryology of the Eye," contains good anatomic illustrations; Chapter 2, "Ophthalmologic Examination," contains information on ophthalmic instruments and examination techniques.

Wilson FM II, ed: *Practical Ophthalmology: A Manual for Beginning Ophthalmology Residents.* San Francisco: American Academy of Ophthalmology; 1996. Intended for beginning ophthalmology residents, this comprehensive book presents numerous step-by-step protocols for a wide range of basic ophthalmologic examinations, which medical students and residents may find useful.

K. Activate the Defense and Immune System

The Defense System relates to the white blood cell and the immune system relates to the Lymphatic System.


Palatine Tonsil
Submandibular Node
Cervical Node
Right Lymphatic Duct
Thymus
Lymphatic Vessel
Thoracic Duct
Intestinal Node
Large Intestine
Appendix
Red Bone Marrow
Lymphatic Vessel
Axillary Node
Spleen
Small Intestine
Iliac Node
Inguinal Node
Hypothalamus
Pineal Gland
Pituitary Gland
Thyroid Gland
Adrenal Gland
Pancreas
Ovary

Fig. 4.66 *Ask the cells to listen to the command.*
The bone marrow produces red and white blood cells. The lymphatic system cleans the toxic and polluted material and bacteria from the cells.

Chapter 2

Acute Visual Loss

Objectives

As a primary care physician, you should be able to evaluate a patient complaining of a sudden decrease in visual acuity or visual field, to construct a differential diagnosis, and to recognize situations requiring urgent action.

To achieve these objectives, you should learn

- Which questions to ask the patient
- To utilize appropriate examination techniques, with special attention to pupillary responses, visual field testing, and ophthalmoscopy
- Which conditions are most likely to cause acute visual loss

Relevance

For most people, sudden blindness is a paradigm of disaster. The primary care physician needs to recognize the conditions responsible for acute visual loss in order to make urgent referrals to an ophthalmologist and to actually initiate therapy, when appropriate. The ultimate visual outcome may well depend on early, accurate diagnosis and timely treatment.

Basic Information

Important patient history questions to ask in the event of sudden visual loss include

- Is the visual loss transient or persistent?
- Is the visual loss monocular or binocular?
- What was the tempo? Did the visual loss occur abruptly, or did it develop over hours, days, or weeks?
- What are the patient's age and medical condition?
- Did the patient have documented normal vision in the past?

How to Examine

Visual Acuity Testing

The first thing to be determined in evaluating acute visual loss is the visual acuity, with best available correction, in each eye. For detailed information on visual acuity testing, see Chapter 1.

Confrontation Field Testing

Normal acuity does not assure that significant vision has not been lost, because the entire visual field, including peripheral vision, must be considered. For instance, a patient who has lost all of the peripheral vision on one side in both eyes—a homonymous hemianopia—generally has normal visual acuity. For instruction on assessing the visual field through confrontation field testing, see Chapter 1.

Pupillary Reactions

The reaction of the pupils to light is useful in the evaluation of visual loss, especially when that reaction is asymmetric. In the swinging-flashlight test, a bright light is moved from one eye to the other and the pupillary reactions are observed. When there is a lesion in the retina or the optic nerve of one eye, the brain-stem centers controlling pupillary size perceive the light as being brighter in the normal eye. Thus, when the light beam is moved from the normal eye to the abnormal eye, the pupil of the abnormal eye may continue to dilate. This positive swinging-flashlight test indicates a relative afferent pupillary defect, also known as a Marcus Gunn pupil. The presence or absence of a relative afferent pupillary defect is often an important piece of information in the evaluation of monocular visual loss. For more information on pupillary reactions and the swinging-flashlight test, see Chapter 7.

Ophthalmoscopy

Ophthalmoscopy is probably the most important examination technique in the evaluation of visual loss because it allows direct inspection of the fundus and an assessment of the clarity of the refractive media. For information on the technique of direct ophthalmoscopy, see Chapter 1.

Penlight Examination

Simple penlight examination usually will detect corneal disease responsible for acute visual loss.

Tonometry

Tonometry to measure intraocular pressure may help confirm the presence of angle-closure glaucoma.

How to Interpret the Findings

Media Opacities

Any significant irregularity or opacity of the clear refractive media of the eye (cornea, anterior chamber, lens, vitreous) will cause blurred vision or a reduction of visual acuity. These opacities do not cause relative afferent pupillary defects, although pupillary reflexes may be altered (eg, miosis in acute iritis or middilated and fixed pupils in acute angle-closure glaucoma). Acute visual loss may result from conditions that cause rapid changes in the transparency of these tissues.

Corneal Edema

One cause of sudden opacification of the cornea is corneal edema, which is recognized by a dulling of the normally crisp reflection of incident light off the cornea. The cornea, crystal-clear when healthy, takes on a ground-glass appearance.

The most common cause of corneal edema is increased intraocular pressure. Visual loss accompanying an attack of angle-closure glaucoma (an ocular emergency) is largely the result of corneal edema. (See Slide 22 in Chapter 4.) Chronic damage to the corneal endothelium by dystrophies or following cataract surgery produces corneal edema, but the visual loss has a gradual onset. Any acute infection or inflammation of the cornea (eg, herpes simplex keratitis) may mimic corneal edema.

Hyphema

Blood in the anterior chamber is known as a hyphema (see Slide 42 in Chapter 5). Any significant hyphema reduces vision, and a complete hyphema will reduce vision to light perception only. Lesser degrees of hyphema may not affect visual acuity. Most hyphemas are the direct consequence of blunt trauma to a normal eye; however, the presence of abnormal vessels (which occurs with tumors, diabetes, intraocular surgery, and chronic inflammation—all causes of neovascularization) predisposes to hyphema.

Cataract

Most cataracts develop slowly. The rare patient may interpret rapid progression of a cataract as sudden visual loss. Even in a patient with a clear lens, sudden changes in blood sugar or serum electrolytes can alter the hydration of the lens. These changes in lens hydration can result in large fluctuations in refractive error, which may be interpreted by the patient as visual loss. In this situation, acuity may simply be improved with refraction.

Vitreous Hemorrhage

Bleeding into the vitreous reduces vision in the same way that hyphema does: in relation to the amount and location of opaque blood. Large vitreous hemorrhages occur after trauma and in any condition causing retinal neovascularization (eg, diabetes or retinal vein occlusion). In addition, vitreous hemorrhage may accompany subarachnoid hemorrhage and is one cause of visual loss from aneurysms. Vitreous hemorrhage may be difficult to appreciate when viewed with the ophthalmoscope, especially through an undilated pupil. If the red reflex cannot be seen but the lens appears clear, vitreous hemorrhage should be suspected. Diagnosis can be confirmed by an ophthalmologist with slit-lamp examination through a dilated pupil.

Retinal Disease

Retinal detachment, macular disease, and retinal vascular occlusion are all associated with sudden visual loss. However, acute visual loss may develop in any inflammatory process that affects the retina, including infectious chorioretinitis, vasculitides, and idiopathic inflammation. These conditions may be distinguished from other causes of acute visual loss by their ophthalmoscopic findings.

Retinal Detachment

Acute visual loss is a feature of an extensive retinal detachment. Typically, the patient with a retinal detachment (Slide 7) complains of flashing Lights followed by large numbers of floaters and then a shade over the vision in one eye. A detachment extensive enough to reduce visual acuity usually produces a relative afferent pupillary defect in the involved eye. The diagnosis is made by ophthalmoscopy through the dilated pupil. The retina appears elevated, sometimes with folds, and the choroidal background is indistinct. However, the findings may not be obvious, and emergency ophthalmologic consultation is indicated.



Slide 7 Retinal detachment. A 60" view of the fundus reveals folds of retina extending into the macula inferotemporal to the disc. In this photograph, the focus is on the elevated retina, which renders the disc slightly out of focus.

Macular Disease

Macular disease reduces visual acuity, but unless the disease is extensive, a relative afferent pupillary defect may not be present. Sudden visual loss from macular disease is often an index of bleeding from a neovascular net formed as part of the process of age-related macular degeneration (see Chapter 3). If the visual loss is preceded by metamorphopsia (a defect of central vision in which the shapes of objects appear distorted), the neovascularization may be identified and treated with laser surgery before progression to significant and permanent visual loss occurs.

Retinal Vascular Occlusion

Retinal vascular occlusion is a relatively common cause of sudden visual loss and may be transient or permanent. Transient monocular visual loss due to arterial insufficiency is called *amaurosis fugax* and is a very important symptom. In a patient over age 50, the report of visual loss in one eye lasting for several minutes should lead to investigation of the ipsilateral carotid circulation, looking for an atheroma, which may be the source of emboli that transiently interrupt blood flow to the retina. The evaluation and management of such a patient raises complicated issues, and referral should be made to an ophthalmologist, a neurologist, or a vascular surgeon.

Central Retinal Artery Occlusion Prolonged interruption of retinal arterial blood flow causes permanent damage to the ganglion cells and other tissue elements. Central retinal artery occlusion (Slide 8) is manifested as a sudden, painless, and often complete visual loss. The ophthalmoscopic appearance depends on how soon after the visual loss the fundus is seen. Within minutes to hours, the only findings may be vascular stasis: narrowing of arterial blood columns and interruption of venous blood columns with the appearance of "boxcarring" as rows of corpuscles are separated by clear intervals.

Some hours after a central retinal artery occlusion, the inner layer of the retina becomes opalescent. The loss of the normal transparency of the retina is most visible ophthalmoscopically where the retina is thickest



Slide 8 Central retinal artery occlusion. The retina is opaque, except for the relatively thin area within the macula, producing the "cherry-red spot."

around the fovea. In the fovea itself, the inner layers are attenuated. Pallor of the perifoveal retina stands in contrast to the normal color of the fovea, causing the characteristic "cherry-red spot" of central retinal artery occlusion. A chronic cherry-red spot is also a feature of storage diseases, such as Tay-Sachs disease and some variants of Niemann-Pick disease, in which the ganglion cells become opalescent because of the deposition of intermediate metabolites.

The optic disc, which is supplied by other branches of the ophthalmic artery, does not swell unless the occlusion is in the ophthalmic or carotid artery, proximal to the origin of the central retinal artery or in the small vessels supplying the disc. The peculiarities of the eye's vascular supply also can explain the possible preservation of some vision in the presence of a complete central retinal artery occlusion. If part of the retina derives its blood supply from the choroidal circulation via a cilioretinal artery, its function is spared. After a central retinal artery occlusion, the retinal edema slowly resolves and the death of the ganglion cells and their axons leads to optic atrophy. Months later, the characteristic ophthalmoscopic appearance is a pale disc in a blind eye.

When ophthalmoscopy shows the diagnosis of an acute central retinal artery occlusion, immediate treatment is warranted unless circulation has already been restored spontaneously. *This* is *a true ophthalmic emergency;* restoration of blood flow may preserve vision if the occlusion is only a few hours old. Instances are reported in which vision has returned after treatment of an occlusion that has been present for several days. In a blind eye, there is little to lose by aggressive measures, and an ophthalmologist's advice should be obtained as quickly as possible.

As an emergency measure, the primary care physician may wish to compress the eye with the heel of the hand, pressing firmly for 10 seconds and then releasing for 10 seconds over a period of approximately 5 minutes. The sudden rise and fall in intraocular pressure could serve to dislodge a small embolus in the central retinal artery and restore circulation before the retinal tissues sustain irreversible damage. An ophthalmologist might employ more vigorous and invasive techniques, including retrobulbar injection of an anesthetic and paracentesis of the anterior chamber.

Branch Retinal Artery Occlusion When only a branch of the central retinal artery is occluded, only part of the retina opacifies and vision is only partially lost. A branch retinal artery occlusion is more likely to be the result of an embolus than is a central retinal artery occlusion, and a source should be sought. If visual acuity is affected, attempts should be made to dislodge the embolus by ocular massage, as discussed above.

Central Retinal Vein Occlusion The ophthalmoscopic picture of disc swelling, venous engorgement, cotton-wool spots (which appear as small white patches on the retina), and diffuse retinal hemorrhages indicates a central retinal vein occlusion (Slide 9). Loss of vision may be severe, although the onset is generally subacute, unlike the dramatic sudden blindness of a central retinal artery occlusion. The fundus picture is so striking that the description "blood and thunder" is sometimes applied.



Slide 9 Central retinal vein occlusion. Dilated and tortuous veins, flame-shaped hemorrhages, and cotton-wool spots characterize this condition.

Despite its dramatic appearance, there is no generally accepted acute management, and a central retinal vein occlusion is not a true ophthalmic emergency.

A central retinal vein occlusion is most often encountered in older patients with hypertension and arteriosclerotic vascular disease. Carotid artery occlusion may produce a similar but milder fundus picture. In rare cases, diseases that alter blood viscosity—such as polycythemia vera, sickle-cell disease, and lymphoma-leukemia—induce a central retinal vein occlusion.

The acute hemorrhages and disc swelling resolve with time; however, they may be followed by the development of shunt vessels from the retinal to the choroidal circulation and by ocular neovascularization. The patient with a central retinal vein occlusion needs a general medical evaluation and followup by an ophthalmologist, who may be able to prevent the late complication of neovascular glaucoma by performing laser photocoagulation surgery of the ischemic retina.

Optic Nerve Disease

Conditions affecting the optic nerve can often result in acute visual loss. Although the optic nerve head may or may not appear normal initially by ophthalmoscopy, pupillary responses are usually abnormal in unilateral disease.

Optic Neuritis

Optic neuritis is an inflammation of the optic nerve that is usually idiopathic but may be associated with multiple sclerosis in a significant number of cases. Reduced visual acuity and a relative afferent pupillary defect are regular features of optic neuritis. The optic disc appears hyperemic and swollen. The prognosis for the return of vision after a single attack of optic neuritis is good. Patients with suspected optic neuritis should be referred to an ophthalmologist for further evaluation. Certain patients with optic neuritis may benefit from high-dose intravenous corticosteroids.

Retrobulbar Optic Neuritis

A young adult who is experiencing a monocular loss of vision that has developed over hours to days and that is often accompanied by pain on movement of the eye but who shows no abnormalities on ophthalmoscopic examination probably has retrobulbar optic neuritis. Again, vision is poor and an afferent pupillary defect is present. Included in the differential diagnosis of retrobulbar optic neuritis is compressive optic neuropathy, which can appear as acute visual loss. The pattern of visual field loss may point to a noninflammatory cause, for example, by a finding of visual field loss in the other eye. Computed tomography or magnetic resonance imaging of the orbits and chiasmal region will identify most compressive lesions, which are potentially treatable with surgery.

Papillitis and Papilledema

Like retrobulbar optic neuritis, papillitis (Slide 10) is a subtype of optic neuritis. Specifically, papillitis is an inflammation of the optic disc, or papilla. Papilledema (Slide 11), on the other hand, refers to swelling of the optic disc from increased intracranial pressure; both optic discs are affected. In optic neuritis (either retrobulbar neuritis or papillitis), vision is usually (but not always) significantly decreased and examination of the



Slide **10** Papillitis. The disc is swollen, with blurred disc margins. In papillitis, the disc is hyperemic, rather than pale as in ischemic optic neuropathy. Papillitis is usually unilateral. Bilateral papillitis can be differentiated from papilledema based on decreased visual acuity in papillitis.



Slide **11** Papilledema. The optic disc is elevated and the margins are indistinct. There is microvascular congestion on the disc, the retinal veins are dilated, and flame-shaped hemorrhages are present. The appearance in the other eye should be similar.

pupils will reveal a relative afferent pupillary defect. In papilledema, the visual acuity and the pupillary reflexes are usually normal.

Some patients with acute papilledema complain of momentary blurring or transient obscurations of vision. Although chronic papilledema may lead to loss of vision, most patients with acute papilledema suffer only minor alterations in vision.

Ischemic Optic Neuropathy

Swelling of the disc and visual loss in an older adult are likely to represent a vascular event rather than inflammation. Ischemic optic neuropathy (Slide 12) is a vascular disorder that presents as a pale, swollen disc, often accompanied by splinter hemorrhages and loss of visual acuity and visual field. The field loss with ischemic neuropathy is often predominantly in the superior or inferior field, a pattern known as *altitudinal.*

Giant-Cell Arteritis

The development of acute ischemic optic neuropathy in a patient over age 60 raises the possibility of giant-cell, or temporal, arteritis. When this systemic arteritis is present, there are often associated complaints of malaise, headache, fever, weight loss, pain and tenderness of muscles and joints (polymyalgia rheumatica), scalp tenderness or discomfort when combing the hair, and a virtually pathognomonic pain in the jaws on chewing, termed *jaw claudication.* Ocular complaints may include sudden visual loss and diplopia (double vision).

Even in an otherwise asymptomatic elderly patient who has ischemic optic neuropathy (or, for that matter, a central retinal artery occlusion or an unexplained ophthalmoplegia, a paresis of extraocular movement), a sedimentation rate should be obtained immediately. Many elderly persons with giant-cell arteritis have markedly elevated sedimentation rates, to greater than 60 mm per hour. If the sedimentation rate is elevated or if there are other symptoms or signs of giant-cell arteritis, treatment with high-dose systemic corticosteroids is mandatory unless there is a very strong contraindication to their use. This course of treatment may preserve



Slide 12 Ischemic optic neuropathy. This figure shows pale swelling of the optic disc, with associated flame-shaped hemorrhages.

vision in the remaining eye and prevent vascular occlusions elsewhere that would cause stroke or myocardial infarction. *Immediate* referral to an ophthalmologist is indicated if giant-cell arteritis is a strong diagnostic possibility. Biopsy of the temporal artery may demonstrate pathologic changes that confirm the diagnosis: giant cells, fragmentation of the elastica with surrounding chronic inflammation, and occlusion of the vessel.

If no systemic arteritis is demonstrated, there is no clear evidence that systemic corticosteroids benefit patients with ischemic optic neuropathy. Unfortunately, there is an approximately 40% chance that the other eye will become involved with nonarteritic ischemic optic neuropathy, with or without treatment.

Trauma

Trauma is another potential cause of visual loss due to involvement of the optic nerve (traumatic optic neuropathy). Apparently, in a small number of cases, concussive head trauma shears the vascular supply to the optic nerve, producing blindness. Surgical decompression of the optic canal may be undertaken in selected cases.

Visual Pathway Disorders

Hemianopia

The cerebral visual pathways are susceptible to involvement by vascular events or tumors. In older persons, a homonymous hemianopia, defined as loss of vision on one side of both visual fields, may result from occlusion of one of the posterior cerebral arteries with infarction of the occipital lobe. Other vascular events occurring in the middle cerebral artery distribution also may produce a hemianopia, but usually other neurologic signs are prominent. Almost any patient with a hemianopia warrants examination by cerebral computed tomography or magnetic resonance imaging to localize and identify the cause. See Chapter 7 for further information about hernianopic visual field loss.

Cortical Blindness

Much rarer than a hemianopia is extensive bilateral damage to the cerebral visual pathways resulting in complete loss of vision. This condition is referred to variously as cortical, central, or cerebral blindness. Because the pathways serving the pupillary light reflex separate from those carrying visual information at the level of the optic tracts, a patient who is cortically blind has normal pupillary reactions. This finding, along with a normal fundus on ophthalmoscopic examination, helps make the diagnosis of cortical blindness. Most patients with cortical blindness either improve or will die due to severe neurologic damage. Transient cortical blindness has been observed in children after subconcussive head trauma.


T Cells and Macrophages
Afferent Lymphatic Vessels
B Cells
Valve
Lymphatic Sinuses
Reticular Fibers
Efferent Lymphatic Vessels
Capsule
Valve
Afferent Lymphatic Vessels
Lymph Node
Cervical Vertebrae
Thoracic Vertebrae
Lumbar Vertebrae
Sacral Vertebrae
Coccygeal Vertebrae
Spine

Fig. 4.67 *"Immune Cells and Vertebrae please listen: clear, clean and bright; fill with Violet Light and return to normal function".*


Bone Marrow Tissue

Sacrum: The sacrum controls all the bones and marrow. It effects the production of red and white blood cells. The bone marrow produces the lymphatic cells (white blood cells). When the blood is full of Chi it becomes lighter. Negative emotions make the blood thick and acidic. The blood cells in a healthy body can live up to ten times longer than in a weak or diseased one.

Bone Marrow: A tissue rich in fats, containing plenty of nourishment for the comprehensive production of the different blood cells: red cells for the transport of oxygen, blood platelets for clotting and the various white cells for the immune system.

Bacterium: Represents the foreign invader, but it is only one of many invaders. Parasites, fungi, viruses, chemicals, mineral fragments, metal particles—these and a great deal besides, set the immune system to work.

Thymus Gland: Perhaps the most important organ of the immune system. The vital training of the different T-lymphocytes takes place inside. When they pass through the thymus they receive a program to convert them into 'T' lymph cells. When they pass through the liver and large intestine they become 'B' cells and helper cells.

Functional Disorders

The adjective *functional* is used in preference to *hysterical* or *malingering* to describe visual loss without organic basis. Often the diagnosis is apparent because the examination produces results incompatible with organic blindness. For example, the patient who reports complete blindness in one eye and normal vision in the other but has normal stereopsis and no relative afferent pupillary defect most likely has a functional disorder. In other patients, sophisticated ophthalmologic examinations may be necessary to make an accurate diagnosis.

Acute Discovery of Chronic Visual Loss

A surprising number of cases of chronic visual loss turn up as acute discoveries. Because the eyes usually function together, this sudden discovery of what has actually been an ongoing problem is most likely to occur when the vision in one eye is normal. A person who claims acute visual loss in one eye but has advanced optic atrophy must have had a prolonged but unrecognized problem. In doubtful cases, it is desirable to obtain records of previous formal eye examinations before accepting visual loss as an acute event and proceeding with expensive or invasive workups.

Points to Remember

1. Early, accurate diagnosis and timely treatment are critical to a positive visual outcome in cases of acute visual loss.
2. Patient ocular history, including timing, tempo, and unilaterality or bilaterality of visual loss, as well as medical history and prior visual acuity, are important to accurate diagnosis.
3. Pupillary responses, visual field testing, and ophthalmoscopy are particularly valuable in determining the causes of acute visual loss.
4. The following conditions require emergency measures and referral: acute angle-closure glaucoma; retinal detachment; acute central retinal artery occlusion; ischemic optic neuropathy if suspected to be related to giant-cell arteritis.

Sample Problems

1. A 58-year-old woman complains of a sudden shower of dust-like particles floating before her right eye. You record VA as 20/20 in each eye. Upon dilated ophthalmoscopy, you see a normal fundus. Your diagnosis is of a possible retinal tear, with the danger of retinal detachment. What is your course of action?

   Answer: Prompt ophthalmologic consultation. A sudden shower of floaters may indicate red blood cells in the vitreous due to a retinal tear. Floaters may be visible to the patient but not to the ophthalmoscopist.

Because the retina has no sensitivity to pain and is, in fact, limited to the sensation of light, the patient may report flashes of light as the retina tears or detaches. Retinal tears usually are located in the far periphery of the retina and may easily elude detection. Symptoms alone indicate the need for referral.

2. A 67-year-old man experienced sudden loss of vision in the left eye 3 hours ago. You record VA as OD 20/20 and OS no light perception. The right pupil responds to light directly but not consensually. The left pupil responds to light consensually but not directly. Dilated fundus examination of the right eye is normal. The left eye shows a white, opacified retina, a cherry-red spot in the macula, and sluggish retinal circulation. You diagnose a central retinal artery occlusion. What is the proper management?

   Answer: You use the heel of your hand to apply pressure to the affected eye, pressing and releasing several times, in the hope that the induced alterations of intraocular pressure may dislodge an embolus. You seek ophthalmologic consultation and undertake a prompt search for the cause of this vascular event.

   Because the retina is neural tissue and survives complete circulatory deprivation poorly, the prognosis for recovery of useful vision in the affected eye is not good. Probably as important is the detection of underlying disease (such as giant-cell arteritis) or a site of embolus formation (such as carotid atheroma) that might lead to future vascular occlusions.

3. A 78-year-old man has recently noticed poor vision in the right eye. He thinks the onset was rather sudden. He has been otherwise healthy but has lost 5 pounds over the last month and thinks he has "less energy." He also has noticed a headache on the right side over the last several days. Your examination reveals a visual acuity of 20/70 on the right and 20/30 on the left. The right pupil seems suspicious for an afferent pupillary defect but is difficult to interpret. The optic nerve looks swollen on the right. What is your course of action?

   Answer: The patient has giant-cell arteritis but does not have all of the classic symptoms and signs. Your index of suspicion should be high in this patient because of his reduced vision, possible afferent pupillary defect, headache, and swollen optic nerve. Obtain a STAT sedimentation rate and refer the patient to an ophthalmologist immediately. High-dose systemic corticosteroids may be needed to preserve vision and prevent other systemic complications.

Annotated Resources

Beck RW, Cleary PA, Trobe JD, et al: The effect of corticosteroids for acute optic neuritis on the subsequent development of multiple sclerosis. The Optic Neuritis Study Group. N Engl *J Med* 1993;329:1764–1769. In this multicenter randomized controlled clinical trial involving 389 patients without known multiple sclerosis, short-term high-dose IV corticosteroid administration appeared to reduce the rate of development of the disease over a 2-year period.

Boghen DR, Glaser JA: Ischemic optic neuritis: the clinical profile and natural history. Brain 1975;98:689–708. This article clearly distinguishes the different types (arteritic vs nonarteritic ischemic optic neuritis) and gives a good discussion of the natural history of these several conditions.

Gutman FA: Evaluation of a patient with central retinal vein occlusion. *Ophthalmology* 1983;90:481–483. One of several articles in the same volume of this journal outlining the diagnosis, evaluation, and management of central retinal vein occlusions.

Hurwitz BJ, Heyman A, Wilkinson WE, et al: Comparison of amaurosis fugax and transient cerebral ischemia: a prospective clinical and arteriographic study. Ann *Neurol* 1985;18:698–704. This series of over 300 patients with amaurosis fugax or transient cerebral ischemic attacks is part of a large literature on the subject, but one of the few prospective studies. Two thirds of middle-aged or elderly patients with amaurosis fugax had operable carotid lesions.

Miller NR, Newman N: Walsh & Hoyt's Clinical Neuro-Ophthalmology. 5th ed. Baltimore: Williams & Wilkins; 1997. The second volume of this excellent four-volume set provides an extensive discussion of disorders of the optic nerve.

Ravits J, Seybold ME: Transient monocular visual loss from narrow-angle glaucoma. Arch *Neurol* 1984;41:991–993. Three patients with intermittent angle-closure glaucoma had their transient visual loss attributed to other causes until glaucoma was considered.

Rizzo JF, Lessell S: Risk of developing multiple sclerosis after uncomplicated optic neuritis. Neurology 1988;38:185–190. A good discussion of the factors to be considered before assigning an episode of optic neuritis to a demyelinating etiology.

Savino PJ, Glaser JS, Cassady J: Retinal stroke: is the patient at risk? Arch *Ophthalmol* 1977;95:1185–1189. A review of different forms of retinal artery occlusion, with recommendations regarding causes and approaches.

Trobe JD: The Physician's Guide to Eye Care. San Francisco: American Academy of Ophthalmology; 1993. A brief but comprehensive resource covering the principal clinical ophthalmic problems that nonophthalmologist physicians are likely to encounter, organized for practical use by practitioners.

Chapter 3

Chronic Visual Loss

Objectives

As a primary care physician, you should be familiar with the major causes of chronic, slowly progressive visual loss in an adult patient—namely, glaucoma, cataract, and macular degeneration—and be able to identify the basic characteristics of each. (See also Chapter 8 for a discussion of diabetic retinopathy, another important cause of chronic visual loss.) In addition, you should be able to evaluate the nerve head, classifying it as normal, glaucomatous, or abnormal but nonglaucomatous. You also should be able to evaluate the clarity of the lens as well as the function and appearance of the macula.

To achieve these objectives, you should learn

- To recognize those characteristics of the optic disc useful in determining whether a given disc is normal or abnormal
- To recognize a cataract and to determine its approximate potential effect on the patient's vision
- To determine whether a cataract is the only cause of a patient's visual decrease
- To examine the macula with the ophthalmoscope and recognize the signs and symptoms of maculopathy

Glaucoma

Relevance

Glaucoma is a significant cause of blindness in the United States and is the most frequent cause of blindness among African Americans. If glaucoma is detected early and treated medically or surgically, blindness can be prevented. Most patients with early glaucoma are asymptomatic. The great majority of patients lack pain, ocular inflammation, or halos (luminous or colored rings seen around lights). Much peripheral vision can be lost before the patient notices visual disability.

Glaucoma is usually insidious because symptoms and noticeable visual field defects occur late in the disease. Visual field defects are characterized by arcuate-shaped *scotomas* (areas of reduced or absent vision) and a contraction of the peripheral field, usually sparing the central vision until late in the disease process. Detection in the early asymptomatic stage requires an active effort. The early detection of glaucoma is important because blindness can usually be prevented if glaucoma is treated adequately and if treatment is begun in time.

Because glaucoma usually involves elevation of intraocular pressure above the statistically normal range, routine measurement of the pressure is a valuable means of screening for glaucoma. Prolonged elevation of intraocular pressure can lead to optic nerve damage, but in some cases, glaucomatous optic nerve changes are evident despite an apparently normal pressure. Therefore, examination of the optic nerve is another way to detect glaucoma. Other disorders, such as brain tumor, can also cause changes in the optic nerve, making the ability to recognize abnormalities of the optic nerve important in and of itself.

Basic Information

Intraocular Pressure

Within the eye is a mechanism for the continuous production and drainage of fluid. This fluid, called *aqueous humor*, is produced by the ciliary body of the eye. Aqueous humor flows through the pupil into the anterior chamber, where it is drained through the trabecular meshwork to Schlemm's canal (Figure 3.1), and onward to the venous system. Because of some resistance to the flow of aqueous through the trabeculum and Schlemm's canal, pressure is created in the eye. All eyes have an internal pressure.

Intraocular pressure is largely dependent on the ease of flow through the trabeculum and Schlemm's canal. The greater the resistance to flow, the higher the pressure in the eye. Although the eye contains several compartments within it, for purposes of pressure it can be considered a single closed space. Thus, the pressure exerted within the eye is equal over the entire wall of the eye. Most normal eyes have an intraocular pressure (IOP) of 21 mm Hg or less.

In the common, insidious form of glaucoma, the chamber angle remains open. Accordingly, this form of glaucoma is called *open-angle glaucoma*. In rare instances, the trabeculum can become suddenly and completely occluded by iris tissue. This causes an abrupt rise in intraocular pressure known as *acute angle-closure glaucoma* (see Slide 22 in Chapter 4) and constitutes an ocular emergency. The abrupt rise in pressure causes symptoms not found in the insidious form of glaucoma, including pain, nausea, and the visualization of colored halos or rainbows around light. An acute attack of angle closure usually produces a red, teary eye with a hazy cornea and a fixed, middilated pupil. The eye feels extremely firm to palpation in most cases.


Anterior chamber angle
Canal of Schlemm
Trabecular meshwork
Cornea
Limbus
Conjunctiva
Sclera
Anterior chamber
Iris
Zonules
Ciliary muscle
Posterior chamber
Anterior lens capsule
Ciliary body
Posterior lens capsule

Figure 3.1 Cross-section of anterior chamber angle and ciliary body.

Optic Nerve

The optic nerve is composed of more than 1.2 million nerve fibers. These nerve fibers originate in the ganglion cells of the retina, gather in a bundle as the optic nerve, and carry visual information to the brain. An interruption of these nerve fibers results in damage to vision.

The optic nerve can be seen at its origin by using the ophthalmoscope. At the point of origin, the nerve is called the *optic disc.* The optic disc often has a small depression in it called the *cup of the optic disc.* The size of the cup in normal eyes can vary with the individual. A complete description of the optic disc appears in Chapter 1.

Relationship of IOP and Optic Nerve

Intraocular pressure is exerted on all walls of the eye, including the optic nerve and its blood vessels. The optic nerve is supplied with blood via branches of the ophthalmic artery, itself a branch of the internal carotid artery. If pressure in the eye is too high, the result may be that blood is prevented from adequately perfusing the optic nerve. If prolonged, this deficiency can damage the nerve. (Mechanical injury can also cause optic nerve damage; see "Optic Atrophy" in Chapter 7.)

Damage to the optic nerve results in visual field loss. Such loss is selective but can become severe and even total over time. Detection of glaucomatous visual loss is accomplished by visual field testing. Visual acuity usually does not suffer initially. Measurement of intraocular pressure and evaluation of optic nerve appearance can detect potential and actual damage so that proper evaluation and treatment can be initiated.

When to Examine

Ophthalmoscopy should be part of every comprehensive eye examination. Particular attention should be given to patients who are predisposed to glaucoma, such as elderly individuals or those with a family history of glaucoma. The American Academy of Ophthalmology recommends a glaucoma screening every 2 to 4 years past age 40, as the incidence of the disease increases with age. Because African-Americans have an even greater risk for development of glaucoma, those between ages 20 and 39 should additionally be screened every **3** to 5 years.

How to Examine

Palpation can detect only very hard and very soft eyes; it is totally unreliable in the range of the most common glaucomatous intraocular pressures. Intraocular pressure is best measured via tonometry, which may be performed in any of several ways. Indentation, or Schiøtz, tonometry involves an inexpensive instrument that is simple to use. However, hand-held applanation tonometers are available and give much more reliable readings. Although more costly, these are also easy to use and require no special patient positioning. Detailed information on various methods of tonometry appears in Chapter 1. The technique of direct ophthalmoscopy, also described in Chapter 1, is particularly useful in assessing the state of the optic disc.

An ophthalmologist evaluating a patient with suspected glaucoma will usually perform perimetry to formally evaluate the visual field. The ophthalmologist also may examine the anterior chamber angle structures using a special contact lens on the topically anesthetized cornea, a technique called *gonioscopy.*

How to Interpret the Findings

The appearance of the optic disc can be described generally in terms of its color and of the size of its physiologic cup (a recognizable central depression with the optic disc). The color of the optic nerve can be important in determining atrophy of the nerve that is due to glaucoma or other causes.



Slide 13 Temporal pallor of the optic nerve. Diseases that damage optic nerve fibers may result in temporal pallor of the optic nerve. Note the normal nerve color present only on the nasal aspect of the disc.



Slide 14 Cup:disc ratio. In this nondiseased optic disc, the cup is less than one half the diameter of the disc, indicating absent or low level of suspicion of glaucoma.

Temporal pallor of the optic nerve (Slide 13) can occur as a result of diseases that damage the nerve fibers, such as brain tumors or optic nerve inflammation, or in conjunction with glaucomatous cupping.

The term *glaucomatous clipping* refers to an increase in the size of the optic cup relative to the optic disc that occurs in glaucoma. This so-called cup:disc ratio is determined by comparing the diameter of the disc to that of the cup (Slide 14). The larger the cup, the greater the probability of a glaucomatous optic nerve. A cup measuring one half the size of the disc or larger—a cup:disc ratio of 0.5 or more—raises suspicion of glaucoma (Slide 15). A large cup should be suspected if central pallor of the disc is prominent. Because the cup is a depressed area of the disc, retinal vessels passing over the disc are seen to bend at the edge of the cup, a useful sign in evaluating cup size. Vessel displacement, then, as well as disc color, should be evaluated in determining the size of the cup (Slide 16).

The optic discs generally should appear symmetric between the eyes. Discs that exhibit asymmetric cup:disc ratios should arouse suspicion. In some cases, edema of the optic disc may be present (called *papilledema* when caused by elevated intracranial pressure), and the cup may be reduced or obliterated (see Slide 11 in Chapter 2).



Slide 15 Glaucomatous cupping. The left side shows a cup:disc ratio of 0.9 (high level of glaucoma suspicion) and the right side shows a cup:disc ratio of 0.7 (moderate level of glaucoma suspicion). The asymmetry of the cup:disc ratios here also raises suspicion of glaucoma.



Slide 16 Glaucomatous optic atrophy. Optic nerve cupping is increased vertically, with a cup:disc ratio of 0.8. Cupping is apparent at the point where the vessels disappear over the edge of the attenuated rim.

Management or Referral

Table 3.1 provides a convenient method of analyzing a patient's level of glaucoma risk. A moderate or high level of glaucoma risk warrants referral to an ophthalmologist for further evaluation. In addition, any patient who has one or more of the following conditions should be referred to an ophthalmologist:

- Intraocular pressure over 21 mm Hg
- Intraocular pressure not elevated, but a difference of 5 mm Hg or more between the eyes
- An optic cup diameter one half or more of the disc diameter (ie, a cup:disc ratio of 0.5 or greater)
- One cup significantly larger in one eye than in the other eye
- Symptoms of acute glaucoma (refer immediately; see Slide 22 in Chapter 4)

For a discussion of systemic side effects of topically administered drugs used in the treatment of glaucoma, see Chapter 9.

Table 3.1 Glaucoma Risk Factor Analysis

History-Based Risk Factor Weights

Variable*	Category	Weight
Age	<50 years	0
	50–64 years	1
	65–74 years	2
	>75 years	3
Race	Caucasian/other	0
	African-American	2
Family History of Glaucoma	Negative or positive in non–first-degree relatives	0
	Positive for parents	1
	Positive for siblings	2
Last Complete Eye Examination	Within past 2 years	0
	2–5 years ago	1
	>5 years ago	2

*Other historical variables, such as high myopia or hyperopia, systemic hypertension, corticosteroid use, and perhaps diabetes, are not strong enough to be assigned a weight but may be considered in the overall assessment of glaucoma risk.

Level of Glaucoma Risk	Weighting Score
High	4 or greater (referral advisable)
Moderate	3 (referral advisable)
Low	2 or less

Cataract

Relevance

Cataract may occur as a congenital or genetic anomaly, as a result of various diseases, or with increasing age. Some degree of cataract formation is to be expected in all persons over age 70. In fact, age-related cataract occurs in about 50% of people between ages 65 and 74 and in about 70% of those over 75. Cataract is the most common cause of decreased vision (not correctable with glasses) in the United States. However, it is one of the most successfully treated conditions in all of surgery. Approximately 1.4 million cataract extractions are done each year in the United States, usually with

We have obtained Fig. 4.68 and the following text from the publication 'The Body Victorious' by Lennart Nilsson and Jan Lindberg.

We hope that you find this short selection of material as informative as we did.

"The illustration below is a highly schematic and simplified picture of our immune system. *Top left*, the pale yellow 'house' symbolizes the bone marrow, where all blood cells are born. *Bottom Right*, a solitary bacterium (yellow) represents the foreign invader that the immune system needs to combat. The light blue path represents the older defenses, with various feeding cells that tackle all foreign substances and also function as a kind of cleaning system. They deal with all the old, dead and used-up material in the body. The newer, special defense force, which develops later, follows the green path. Its cells are more specialized; they obtain their special training and reach maturity in organs such as the thymus gland and in the lymphoid tissue around the intestines and in the liver. In the lymphoid tissue, the yellow 'half-way house' (far right), the 'B-lymphocytes are trained. These are the precursors of the large plasma cells - the pale green cells (far right) in the illustration, which produce the body's sniper ammunition, the antibodies (Red and Y-Shaped).


Bone Marrow
Lymphocytes
Feeding Cells
Complement System
Thymus
Intestinal Tissue Liver, etc.
B-Cell
T-Lymphocytes
B-Lymphocytes
General Defence
Killer Cell
Suppressor Cell
Monocyte
Plasma Cell
Helper Cell
Complement Factors
Macrophage
Antibody
Granulocytes
T-Cell
Killer Cell
Bacterium (Foreign Invader)

Fig. 4.68

Bone marrow, bacterium and thymus please listen: clear, clean and bright; fill with violet light and return to normal function".

implantation of an intraocular lens. If an implant is not used, visual rehabilitation is still possible with a contact lens or thick (aphakic) eyeglasses.

It is important to be certain that visual loss is explained fully by cataract and not by other causes, such as glaucoma, macular degeneration, or diabetic retinopathy. Cataract may coexist with these conditions, making assessment more difficult.

Basic Information

Lens

The crystalline lens focuses a clear image on the retina. The lens is suspended by thin filamentous zonules from the ciliary body between the iris anteriorly and the vitreous humor posteriorly. Contraction of the ciliary muscle permits focusing of the lens. The lens is enclosed in a capsule of transparent elastic basement membrane. The capsule encloses the cortex and the nucleus of the lens as well as a single anterior layer of cuboidal epithelium. The lens has no innervation or blood supply. Nourishment comes from the aqueous fluid and the vitreous.

The normal lens continues to grow throughout life. The epithelial cells continue to produce new cortical lens fibers, yielding a slow increase in size, weight, and density over the years. The normal lens consists of 35% protein by mass. The percentage of insoluble protein increases as the lens ages and as a cataract develops.

Cataract

A cataract is any opacity or discoloration of the lens, whether a small, local opacity or the complete loss of transparency. Clinically, the term *cataract* is usually reserved for opacities that affect visual acuity because many normal lenses have small, visually insignificant opacities.

A cataract is described in terms of the zones of the lens involved in the opacity. These zones of opacity may be subcapsular, cortical, or nuclear and may be anterior or posterior in location. In addition to opacification of the nucleus and cortex, there may be a yellow or amber color change to the lens. A cataract also can be described in terms of its stage of development. A cataract with a clear cortex remaining is immature (Slide 17). A mature cataract (Slide 18) has a totally opacified cortex.

The most common cause of cataract is age-related change. Other causative factors include trauma, inflammation, metabolic and nutritional defects, and radiation damage. Cataracts may develop very slowly over the years or may progress rapidly, depending on the cause and type of cataract.

Symptoms of Cataract

Patients may first notice image blur as the lens loses its ability to resolve separate and distinct objects. Patients are first aware of a disturbance of vision, then a diminution, and finally a failure of vision. The degree of visual disability caused by a cataract depends on the size and location of



Slide 17 Immature cataract. The nucleus of this lens is opaque (nuclear cataract), while the cortical layers remain clear. The opacity appears as a dark shadow against the red reflex. This particular cataract, which is congenital, will obstruct vision more when the pupil is small than when it is dilated, as shown here.



Slide 18 Mature cataract. A cataract is called *mature* when the lens is totally opacified. A red reflex cannot be obtained; the pupil appears white. The radial spokes in this figure reflect variations in density of the radially arranged fibers in the cortical layers of the lens. Light still reaching the retina is totally diffused and will allow the perception of light but not form.

the opacity. Axial opacities—affecting the nucleus or central subcapsular areas (see Slide 17)—cause much more disabling visual loss than do peripheral opacities.

Patients with nuclear sclerosis may develop increasing lenticular (ie, referring to the crystalline lens) myopia because of the increased refractive power of the denser nucleus. As the size of the cataract increases, patients become progressively more myopic. Patients may find they can read without the glasses normally required, a phenomenon often called second sight. Patients may note monocular double or multiple images, due to irregular refraction within the lens.

Patients with posterior subcapsular cataracts may note a relatively rapid decrease in vision, with glare as well as image blur and distortion. This type of cataract is frequently associated with metabolic causes such as diabetes mellitus and corticosteroid use.

With enough time, all cataracts will lead to a generalized impairment of vision. The degree of impairment may vary from day to day. With yellowing of the lens nucleus, objects appear browner or yellower to the patient than they actually are.

When to Examine

A patient with decreasing vision requires examination to determine the cause of the visual decrease. In testing for the presence of cataract, it is also important to attempt to demonstrate that the retina and optic nerve are healthy and that the visual decrease is due to lens changes only or primarily.

If the lens is densely cataractous, the ophthalmoscope will not provide a view of the fundus through the opacity. In this situation, the risk of overlooking retinal or other disease conditions exists, as does the risk of performing surgery for cataract without the assurance that vision loss is due primarily to lens changes. Therefore, to detect fundus changes early, ophthalmoscopic examination should be part of every physical examination. Special attention is given to the macula when a patient reports difficulty with near work, blurred vision, or metamorphopsia (ie, a wavy distortion of central vision).

How to Examine

The following examination methods are particularly helpful in determining whether visual loss is attributable to cataract, to some other cause, or to a combination of causes:

- Visual acuity The first step in any evaluation of visual decrease is the measurement of visual acuity. Refer to Chapter 1 for details.
- Pupillary responses Chapter 7 describes how to perform a basic pupillary examination and provides details on the neurologic implications of pupillary responses. Even an advanced cataract would not produce a relative afferent pupillary defect.
- Ophthalmoscopy The examiner's view into the eye should be about the same as the cataract patient's visual acuity; that is, the cataract should affect the physician's view into the eye through the direct ophthalmoscope to about the same extent as it does the patient's view out of the eye.

How to Interpret the Findings

An early cataract is not visible to the unaided eye. If the cataract becomes very dense, it may appear as a white pupil, or leukocoria. The lens can be evaluated with the ophthalmoscope using a plus-lens setting. The lens opacification with a partial cataract will appear black against the red reflex of the fundus (see Slide 17). Generally, the denser the cataract, the poorer the red reflex and the worse the visual acuity.

In addition to ophthalrnoscopy, an ophthalmologist would routinely perform a slit-lamp examination, which provides a magnified, stereoscopic view of the lens and other anterior segment structures.

Management or Referral

It is important not to assign visual loss to cataract before ensuring that other, more serious causes of visual loss have not been overlooked. The decision to refer a patient with cataract should be based in part on whether or not the cataract keeps the patient from doing what he or she wants to do. A cataract can interfere with patients' daily activities of living by limiting their ability to drive safely, read, or participate in sports or other hobbies. Patients with cataract-associated visual loss that negatively affects their daily living may benefit from a surgical procedure of cataract extraction with intraocular lens implantation. After cataract-removal surgery, patients commonly undergo a laser surgical procedure to open an opacified posterior capsule, leading to a popular misconception that a cataract can actually be removed with a laser.

Macular Degeneration

Relevance

In the United States, age-related macular degeneration is the leading cause of irreversible central visual loss (20/200 or worse) among people aged 52 or older. Because certain types of macular degeneration are treated effectively with laser, it is important to recognize this entity and to refer for appropriate care. It is important to distinguish between the possible causes of visual loss, whether cataract (surgically correctable), glaucoma (medically or surgically treatable), or macular degeneration (potentially laser treatable).

Basic Information

Macular Anatomy

The macula is an oval area situated about 2 disc diameters temporal and slightly inferior to the optic disc (see Slide 2 in Chapter 1 for a depiction of the normal fundus). The macula is composed of both rods and cones and is the area responsible for detailed, fine central vision. The central macula



Figure 3.2 Central macula. The central macula is avascular, as demonstrated in this fundus fluorescein angiogram. The central capillary-free zone identifies the foveal region. A small hemorrhage is made more visible against the fluorescein-enhanced background.



Slide 19 Drusen. Distinct yellow-white lesions may be seen in the posterior pole surrounding the macular area. Although acuity may be normal initially, these lesions can lead to significant visual loss if the central macula becomes involved.

(Figure 3.2) is avascular and appears darker than the surrounding retina. The fovea is an oval depression in the center of the macula. Here, there is a high density of cones but no rods are present. The central depression of the fovea may act like a concave mirror during ophthalmoscopy, producing a light reflection (ie, foveal reflex).

Age-Related Macular Changes

Macular changes due to age include drusen, degenerative changes in the retinal pigment epithelium, and subretinal neovascular membranes.

Drusen are hyaline nodules (or colloid bodies) deposited in Bruch's membrane, which separates the retinal pigment epithelium (the outermost layer of the retina) from the inner choroidal vessels. Drusen may be small and discrete (Slide 19) or larger, with irregular shapes and indistinct edges. Patients with drusen alone tend to have normal or near-normal visual acuity, with minimal metamorphopsia. Drusen may be seen with increasing age, during retinal or choroidal degeneration in disease states, and as a primary dystrophy.



Slide 20 Retinal pigment epithelial atrophy. An irregular area of depigmentation is seen in the macula. The underlying choroidal vasculature is typically more prominent when the pigment epithelium is absent or atrophic.



Slide 21 Subretinal hemorrhage. Age-related macular changes often include subretinal hemorrhage, fibrosis, and pigment epithelial degeneration.

Degenerative changes in the retinal pigment epithelium itself may occur with or without drusen. These degenerative changes are manifested as clumps of hyperpigmentation or depigmented atrophic areas (Slide 20). The effect on visual acuity is variable.

About 20% of eyes with age-related macular degeneration develop subretinal neovascularization. The extension of vessels from the inner choroid layer into the subpigment epithelial space and eventually into the subretinal space means that a defect has developed in Bruch's membrane.

The subretinal neovascular net may be associated with subretinal hemorrhage (Slide 21), fibrosis, pigment epithelial degeneration, and photoreceptor atrophy. A hemorrhage may result in acute visual loss (see Chapter 2). The larger the membrane and the closer to the center of the fovea, the worse the prognosis for good central vision.

Fluorescein angiography, a technique utilized by ophthalmologists, may be necessary to identify neovascularization and is mandatory before considering laser surgery. Intravenous injection of fluorescein dye and subsequent retinal examination or photography help demonstrate the retinal and choroidal vasculature. In contrast to competent retinal veins and arteries, new vessels can be identified because they leak fluorescein dye. In addition, the retinal pigment epithelium acts as a physical and optical barrier to fluorescein, and thus angiography facilitates identification of pigment epithelial defects. Indocyanine green is another dye used to demonstrate new vessels.



Figure 3.3 Neovascular net. This fluorescein angiogram of the same fundus shown in Slide 21 reveals a subretinal neovascular net, responsible for the subretinal hemorrhage seen in that figure. In this angiogram, the net appears as a white, irregular area of fluorescein leakage.

Compare Slide 21, a fundus photograph depicting a subretinal hemorrhage and other age-related changes, with Figure 3.3, a fundus fluorescein angiogram of the same eye, which reveals neovascularization associated with the hemorrhage. These photographs demonstrate both atrophy and neovascularization.

Age-related changes are almost totally confined to the posterior pole of the eye. Thus, the patient with macular degeneration may have very poor central vision, but will tend to retain functional peripheral vision. Visual aids, such as high-plus magnifiers and telescopic devices, may help the patient. In addition to age, other causes of chronic maculopathy include heredity and metabolic changes.

When to Examine

Any patient with decreasing vision requires examination to determine the cause of the visual decrease. In assessing a patient with decreased or distorted central vision, every effort should be made to examine the macula with the ophthalmoscope. Of course, opacities in the cornea, lens, or vitreous may preclude an adequate view of the macula.

How to Examine

The following techniques are especially helpful in evaluating macular degeneration as the cause of visual decrease or major changes in vision:

- Visual acuity measurement Refer to Chapter 1 for instructions.
- Amsler grid testing Amsler grid testing (Figure 3.4) is a useful method of evaluating the function of the macula. The test is carried out by having the patient look with one eye at a time at a central spot on a page with horizontal and vertical parallel lines making up a square grid pattern. This grid pattern is usually printed in white against a black background. The



Figure 3.4 Amsler grid testing. **(A)** The patient indicates the nature and location of his central field defect by sketching what he perceives on the Amsler grid. **(B)** The typical grid pattern of white lines on a black background.

patient is asked to note irregularities in the lines. Irregularities may be reported as lines that are wavy, seem to bow or bend, appear gray or fuzzy, or are absent in certain areas of the grid, indicating a scotoma.

The straight line, right angle, and square are geometric figures in which the eye can distinguish distortions most easily. With the chart held at a normal reading distance of 30 cm from the eye, the Amsler grid measures 10° on each side of fixation. This allows for an evaluation of 5.36 mm in all directions from the center of the macula (ie, the fovea). Thus, the entire macula is evaluated with this examination.

- Ophthalmoscopy The macular area is studied with the direct ophthalmoscope. Sometimes it is helpful to have the patient look directly into the light of the instrument. Dilation of the pupil may be necessary for adequate examination.
- Additional studies The ophthalmologist may elect to carry out special studies to better evaluate the macula and macular function. Procedures such as stereoscopic slit-lamp examination and fluorescein angiography may be necessary to determine pathologic changes.

How to Interpret the Findings

The appearance of the macula often does not accurately predict the visual acuity. The macula may look more or less involved than the vision indicates. Drusen, areas of decreased or increased pigmentation, subretinal exudate, and hemorrhage or neovascularization are all important signs to check for in an examination of the macula. The absence of the foveal reflex and a mottled appearance of the underlying retinal pigment epithelium are among the early signs of macular disease.

Management or Referral

Any patient who has one or more of the following should be referred to an ophthalmologist:

- A recent onset of decreased visual acuity
- A recent onset of metamorphopsia, or distortion of central vision
- A recent onset of a scotoma, or blind spot
- Any ophthalmoscopic abnormalities in the appearance of the macula, such as drusen, degenerative changes in the retinal pigment epithelium, exudate, or subretinal neovascular membranes

A patient with metamorphopsia may have drusen in the macula only and not be a candidate for laser treatment, but 20% of eyes with age-related macular degeneration develop subretinal neovascularization. Clinical studies have indicated that argon laser photocoagulation of subretinal neovascular membranes that are not too close to the fovea significantly reduces the central visual loss.

The Visually Impaired Patient

Despite medical or surgical therapy, some patients will have a significant residual visual impairment. These patients are candidates for low-vision services and should be referred to an ophthalmologist capable of supplying these services. More than 11 million Americans have a vision impairment that interferes with routine activities; 1.5 million are classified as severely visually handicapped. The use of visual aids will allow many of these patients to continue to function independently. The appropriate and timely intervention by the low-vision specialist is an important part of patients' rehabilitation and should be considered a continuation of their ongoing medical therapy.

Points to Remember

1. Glaucoma should be suspected when ophthalmoscopy reveals either prominent cupping of the optic discs or significant asymmetry of the cup:disc ratio.
2. The primary indication for cataract extraction in most patients is interference with the daily pattern of living rather than reduction of visual acuity to a particular level.
3. Both laser surgery of neovascular membranes and low-vision aids can be helpful to patients with age-related macular degeneration.

Sample Problems

1. During a thorough physical examination of a 38-year-old male patient, you record intraocular pressure of 20 mm Hg in the right eye and 24 mm Hg in the left eye. Based on these findings, which of the following represents a reasonable course of action on your part?
   a. Explain to the patient that he has glaucoma and that you want to recheck his intraocular pressure in 3 months.
   b. Evaluate the optic discs carefully and, if they are normal, recheck the patient in 6 to 12 months.
   c. Refer the patient to an ophthalmologist.
   d. Inquire about a family history of glaucoma and, if there is none, reassure the patient that his intraocular pressure is probably in the upper range of normal.

   Answer: c. Elevated intraocular pressure alone is not a definite indication of glaucoma. It would be correct to tell this patient that his intraocular pressure is slightly elevated on this one occasion. In tonometry screening, it is best to determine the pressure and act accordingly rather than make decisions regarding a definitive diagnosis of glaucoma and a decision on management. Thus, the correct approach in this case is to refer the patient to an ophthalmologist, because pressure of 22 mm Hg or higher is statistically abnormal. The ophthalmologist may decide merely to observe the patient without treatment, but this decision should be left to the ophthalmologist, who should communicate this to the referring physician.

   It is good to know whether the optic discs are normal, but once you find an elevated pressure, your next move should be referral. On the

The three paths from the thymus are intended to show that there are different types of T- lymphocytes - among others, aggressive killer cells, helper cells and suppressive cells. All of them have specialized tasks to perform when the immune system launches a counterattack. The three blue paths of the older defenses have three different kinds of feeding cells. First, the large and powerful macrophages (orange) advance on the enemy; then come the granulocytes (blue), smaller and faster moving, followed by the (pink) monocytes. The nuclei in the shimmering cell bodies are faintly discernable. In addition, there is an important complement system (middle), symbolized here by a multicolored range of small spheres flocking toward the foreign bacterium. These molecules play a large part in increasing the efficiency of both antibodies and feeding cells. In addition, they have the capacity to destroy bacteria by shooting holes in them. The complement factors are produced in many different cells in the body.

Chi Kung has a very strong effect against viruses. Altough medical science is struggling to discover a medicine that will kill them, Chi Kung practice is able to prevent them from occuring in the first place. Whether we are sick or healthy, we all need our defense system to be in good shape.

Defense System - Outline of Practice

1. Work on yourself first to activate your sacrum. Project the sacrum as big as the universe. See the eight holes in the bone and visualize them breathing. Breathe and compress the Universal Chi into the bones. Feel the Chi begin to rise up the spine and into your mideyebrow and temple bones. When you feel that there is enough Chi, project it out to the universe, multiply it and spiral it back down. Project it towards the student and ask them to touch their sacrum. Rub your hands until warm and touch the sacrum. Picture the sacrum getting bigger and bigger, breathing into the eight holes. Tell the person to smile at the sacrum and start to work on your Tan Tien and universe. Multiply more energy and picture the Chi from the universe coming down to the sacrum of the other person (and your own) and then charge up the spine, to the rib cage, to the temple bone and to the mideyebrow.



Fig. 4.69 *Visualize and feel the Bone Marrow filling with Chi.*

other hand, in situations where you find normal pressure but questionable optic discs, remember that glaucoma still could exist and that referral still may be indicated. Finally, although glaucoma has some hereditary aspects, this should have no bearing in a case in which you find elevated pressure. However, should you have a patient with a strong positive family history of glaucoma, it may be wise to suggest that the patient obtain an ophthalmologist's evaluation despite your finding normal pressure.

2. A retired patient of yours is developing the nuclear sclerotic form of cataract, and his visual acuity has decreased to OD 20/30 and OS 20/40. The only time his vision bothers him is in a dark restaurant, where he has some difficulty reading the menu. Friends have told him about a doctor who will operate with a laser to remove his cataract without risk and who will do it for free. He asks your advice. What do you tell him?
   a. If it's free and he really is a doctor, then go ahead.
   b. Tell him that a laser is not used to remove cataracts, but he should go ahead anyway.
   c. Advise that (1) the indications to remove a cataract are that it endangers the health of the eye or keeps the patient from doing what he needs and wants to do; (2) lasers are not used to remove cataracts; and (3) no surgery is free or without risk. The disability of decreased vision must warrant the risks inherent in surgery.

   Answer: c.

3. A 76-year-old man has noted visual distortion over the past week. His concern increased when he discovered that the distortion was in the right eye only. Straight lines viewed through his left eye remained straight, but they appeared to dip down in the center when viewed with his right eye only. Visual acuity testing revealed 20/50 OD, 20/20 OS.
   A. What further tests will help determine the source of the patient's visual loss?

   Answer: Amsler grid testing will document the patient's symptoms of metamorphopsia. Dilated fundus examination may reveal retinal drusen, retinal hemorrhages secondary to subretinal neovascular membranes, or retinal pigment epithelial atrophy as a manifestation of age-related macular degeneration.

   B. What technique is used by ophthalmologists to identify neovascularization in consideration for laser treatment?

   Answer: Fluorescein angiography is used to document neovascularization.

   C. What percentage of patients with age-related macular degeneration develop subretinal neovascularization?

   Answer: Twenty percent of patients with age-related macular degeneration develop subretinal neovascularization.

Annotated Resources

Jaffe NS, Jaffe MS, Jaffe GF: *Cataract Surgery and Its Complications.* 5th ed. St Louis: CV Mosby Co; 1990. An excellent text covering the contemporary methods of surgical management of cataracts, including phacoemulsification, and the major intraoperative and postoperative complications associated with this surgery.

Macular Photocoagulation Study Group: Argon laser photocoagulation for neovascular maculopathy: three-year results from randomized clinical trials. *Arch Ophthalmol* 1986;104:694–701. The beneficial effects of argon laser photocoagulation are demonstrated in eyes with an extrafoveal choroidal neovascular membrane.

Mangione CM, Phillips RS, Lawrence MG, et al: Improved visual function and attenuation of declines in health-related quality of life after cataract extraction. *Arch Ophthalnzol* 1994:112:1419–1425. Improved visual function after cataract surgery was associated with better health-related quality of life, suggesting that age-related declines in health may be attenuated by improvements in visual function.

Shields MB: *Textbook d Glaticoma.* 4th ed. Baltimore: Williams & Wilkins; 1997. An excellent reference covering current medical and surgical therapies of the primary and secondary glaucomas.

Tasman W, Jaeger EA, eds: *Duane's Clinical Ophthalmology.* Pluladelphia: JB Lippincott Co; 1996. The section "Diseases of the Lens" in Volume 1 provides basic background material on the anatomy, embryology, and physiology of the lens as well as the pathogenesis of cataract. The section "Glaucoma" in Volume 3 provides information on contemporary concepts about the glaucomas and their treatment. Both basic and sophisticated information is available in this volume. Chapter 23 in Volume 3 covers acquired macular disease, providing current information on age-related macular degeneration.

Trobe JD: *The Physician's Guide to Eye Care.* San Francisco: American Academy of Ophthalmology; 1993. A brief but comprehensive resource covering the principal clinical ophthalmic problems that nonophthalmologist physicians are likely to encounter, organized for practical use by practitioners.

Chapter 4

The Red Eye

Objectives

As a primary care physician, you should be able to determine whether a patient with a red eye requires the prompt attention of an ophthalmologist or whether you can appropriately evaluate and treat the condition.

To achieve this objective, you should learn

- To perform the nine basic diagnostic steps
- To recognize the danger signs of a red eye
- To describe the treatment for those cases you can manage and to recognize the more serious problems that should be referred
- To describe the serious complications of prolonged use of topical anesthetic drops and of corticosteroids

Relevance

A primary care physician frequently encounters patients who complain of a red eye. The condition causing the red eye is often a simple disorder such as a subconjunctival hemorrhage or an infectious conjunctivitis. These conditions either will resolve spontaneously or can be treated easily by the primary care physician. Occasionally, the condition causing a red eye is a more serious disorder, such as intraocular inflammation, corneal inflammation, or acute glaucoma. A patient with one of these vision-threatening conditions requires the immediate attention of an ophthalmologist, whose specialized skills, knowledge, and examining instruments are needed in order to make correct therapeutic decisions.

Basic Information

Red eye refers to hyperemia of the superficially visible vessels of the conjunctiva, episclera, or sclera. Hyperemia, or engorgement of the conjunctival blood vessels, can be caused by disorders of these structures or of adjoining structures, including the cornea, iris, ciliary body, and the ocular adnexa. Specific disorders are discussed in the following section.

Disorders Associated With a Red Eye

Any patient who complains of a red or painful eye should be examined to diagnose the condition as one of the following:

- Acute angle-closure glaucoma An uncommon form of glaucoma due to sudden and complete occlusion of the anterior chamber angle by iris tissue (Slide 22); serious. The more common chronic open-angle glaucoma causes no redness of the eye. (See Chapter 3 for a discussion of glaucoma.)
- Iritis or iridocyclitis An inflammation of the iris alone or of the iris and ciliary body; often manifested by ciliary flush (Slide 23); serious.
- Herpes simplex keratitis An inflammation of the cornea caused by the herpes simplex virus (Slide 24); common, potentially serious; can lead to corneal ulceration.
- Conjunctivitis Hyperemia of the conjunctival blood vessels (Slide 25); cause may be bacterial, viral, allergic, or irritative; common, often not serious.
- Episcleritis An inflammation (often sectorial) of the episclera, the vascular layer between the conjunctiva and the sclera; uncommon, without discharge, not serious, possibly allergic, occasionally painful.



Slide 22 Acute angle-closure glaucoma. The irregular corneal reflection and hazy cornea suggest edema. The pupil is middilated; the iris appears to be displaced anteriorly, with shallowing of the anterior chamber. These findings plus elevated IOP are diagnostic of acute angle-closure glaucoma.



Slide 23 Ciliary flush. Dilated deep conjunctival and episcleral vessels adjacent and circumferential to the corneal limbus cast a violet hue characteristic of ciliary flush and best seen in natural light.



Slide 24 Herpes simplex keratitis. In the center of the cornea is an irregular, dendritic (branch-like) lesion of the corneal epithelium.



Slide 25 Conjunctivitis. The hyperemia seen here is produced by a diffuse dilation of the conjunctival blood vessels. The dilation tends to be less intense in the perilimbal region, in contrast to the perilimbal dilation of deeper vessels characteristic of ciliary flush.



Slide 26 Scleritis. This localized, raised hyperemic lesion is characteristic of scleritis, which is associated with collagen, vascular, and rheumatoid diseases. Episcleritis appears flat, involves more superficial tissue, and is usually not associated with serious systemic disease. The cause of episcleritis may be allergic.

- **Scleritis** An inflammation (localized or diffuse) of the sclera (Slide 26); uncommon, often protracted, usually accompanied by pain; may indicate serious systemic disease such as collagen-vascular disorder; potentially serious to the eye.
- **Adnexal disease** Affects the eyelids, lacrimal apparatus, and orbit; includes dacryocystitis (Slide 27), stye, and blepharitis. Red eye can also occur secondary to lid lesions (such as basal cell carcinoma, squamous cell carcinoma, or molluscum contagiosum), thyroid disease, and vascular lesions in the orbit.



Slide 27 Dacryocystitis. This obvious, raised erythematous mass represents an acute inflammation of the lacrimal sac, usually secondary to a nasolacrimal duct obstruction. A purulent discharge may be extruded from the lid puncta by massage over the lacrimal sac.



Slide 28 Pterygium. This wedge-shaped growth of vascularized conjunctiva extends onto the cornea. The initial sign of pterygium may be a localized chronic conjunctivitis.

- Subconjunctival hemorrhage An accumulation of blood in the potential space between the conjunctiva and the sclera (see Slide 49 in Chapter 5); rarely serious.
- **Pterygium** An abnormal growth consisting of a triangular fold of tissue that advances progressively over the cornea, usually from the nasal side (Slide 28); usually not serious. Localized conjunctival inflammation may be associated with pterygium. Most cases occur in tropical climates. Surgical excision is indicated if the pterygium starts to encroach on the visual axis.
- **Keratoconjunctivitis** sicca A disorder involving the conjunctiva and sclera resulting from lacrimal deficiency; commonly called dry eyes; usually not serious.
- Abrasions and foreign bodies Hyperemia can occur in response to corneal abrasions or foreign-body injury.
- Secondary to **abnormal** lid **function** Bell's palsy, thyroid ophthalmopathy, or other lesions causing ocular exposure, such as that which occurs in some comatose patients, can result in a red eye; potentially serious.



Slide 29 Purulent conjunctivitis. With the lower lid everted, a creamy-white exudate is visible, highlighted by the conjunctival hyperemia.



Slide 30 Large keratic precipitates. Multiple gray-white opacities on the back surface of the cornea are seen against the background of the red reflex. These precipitates can result from chronic iridocyclitis.

How to Examine

Nine diagnostic steps are used to evaluate a patient with a red eye:

1. Determine whether the visual acuity is normal or decreased, using a Snellen chart (see Chapter 1).
2. Decide by inspection what pattern of redness is present and whether it is due to subconjunctival hemorrhage, conjunctival hyperemia, ciliary flush, or a combination of these.
3. Detect the presence of conjunctival discharge and categorize it as to amount—profuse or scant—and character—purulent (Slide 29), mucopurulent, or serous.
4. Detect opacities of the cornea, including large keratic precipitates (Slide 30) or irregularities of the corneal surface such as corneal edema (Slide 31), corneal leukoma (a white opacity caused by scar tissue, Slide 32), and irregular corneal reflection (Slide 33). Examination is done using a penlight or transilluminator.
5. Search for disruption of the corneal epithelium by staining the cornea with fluorescein (see Chapter 1).
6. Estimate the depth of the anterior chamber as normal or shallow (see Chapter 1); detect any layered blood or pus, which would indicate either hyphema or hypopyon, respectively. (Compare Slide 34, a corneal ulcer with hypopyon, with hyphema, Slide 42, Chapter 5.)



Slide 31 Corneal edema. In this fiery red eye, the normally sharp corneal reflex is replaced by a diffuse, hazy appearance. Iris details are not as clear as in a healthy eye.



Slide 32 Corneal leukoma. This dense, white corneal scar represents fibrosis secondary to a previous corneal insult, most frequently trauma or infection. Outside the scar, the cornea is clear. If the scar encroaches on the visual axis, acuity may be impaired.



Slide 33 Irregular corneal reflection. This localized irregularity of the normally sharp corneal light reflection indicates local disruption of the corneal epithelium.

7. Detect irregularity of the pupils and determine whether one pupil is larger than the other. Observe the reactivity of the pupils to light to determine whether one pupil is more sluggish than the other or is nonreactive (see Chapters 1 and 7).
8. If elevated intraocular pressure is suspected, as in angle-closure glaucoma, and reliable tonometry is available, then measurement of intraocular pressure can help confirm the diagnosis. (Tonometry is omitted when there is an obvious external infection.)
9. Detect the presence of proptosis (Slide 35), lid malfunction, or any limitations of eye movement.



Slide 34 Corneal ulcer with hypopyon. This inflamed eye shows a white corneal opacity associated with an irregular corneal reflex. In addition, a prominent layering of purulent material appears in the inferior aspect of the anterior chamber, a hypopyon.



Slide 35 Chronic proptosis. The right eye of this patient is proptotic, or anteriorly displaced. Marked edema (chemosis) with hyperemia of the conjunctiva is also evident, with tissue prolapse over the lower lid margin. The patient has an orbital tumor.

How to Interpret the Findings

Although many conditions can cause a red eye, and the associated signs and symptoms of the various disorders overlap to some extent, several signs and symptoms signal danger. The presence of one or more of these danger signals should alert the physician that the patient has a disorder requiring an ophthalmologist's attention. Tables 4.1 and 4.2 summarize significant signs and symptoms in the differential diagnosis of a red eye. In the sections that follow, an exclamation point after a sign or symptom indicates a danger signal.

Signs of Red Eye

Reduced Visual Acuity ❗

Reduced visual acuity suggests a serious ocular disease, such as an inflamed cornea, iridocyclitis, or glaucoma. It never occurs in simple conjunctivitis unless there is associated corneal involvement.

Table 4.1 Signs of Red Eye

Sign	Referral Advisable if Present	Acute Glaucoma	Acute Iridocyclitis	Keratitis	Bacterial Conjunctivitis	Viral Conjunctivitis	Allergic Conjunctivitis
Ciliary flush	Yes	+	+	+	–	–	–
Conjunctival hyperemia	No	+	+	+	+	+	+
Corneal opacification	Yes	+	–	+	–	+/–	–
Corneal epithelial disruption	Yes	–	–	+	–	+/–	–
Pupillary abnormalities	Yes	+	+	+/–	–	–	–
Shallow anterior chamber depth	Yes	+	–	–	–	–	–
Elevated intraocular pressure	Yes	+	+/–	–	–	–	–
Proptosis	Yes	–	–	–	–	–	–
Discharge	No	–	–	+/–	+	+	+
Preauricular lymph-node enlargement	No	–	–	–	–	+	–

Note:
+ = Usually has sign
– = Does not usually have sign
– – = May or may not have sign

Ciliary Flush

Ciliary flush (see Slide 23) is an injection of the deep conjunctival and episcleral vessels surrounding the cornea. It is seen most easily in daylight and appears as a faint violaceous ring in which individual vessels are indiscernible to the unaided eye. Ciliary flush is a danger sign often seen in eyes with corneal inflammations, iridocyclitis, or acute glaucoma. Usually, ciliary flush is not present in conjunctivitis.

Conjunctival Hyperemia

Conjunctival hyperemia (see Slide 25) is an engorgement of the larger and more superficial bulbar conjunctival vessels. A nonspecific sign, it may be seen in almost any of the conditions causing a red eye.

Corneal Opacification

In a patient with a red eye, corneal opacities always denote disease. These opacities may be detected by direct illumination with a penlight, or they may be seen with a direct ophthalmoscope (with a plus lens in the viewing aperture) outlined against the red fundus reflex. Several types of corneal opacities may occur:

2. Tell the student to move their hands to the hip bones. Tell them to smile to these bones. Feel them as ‘funny, laughing, happy bones’. Tell them to feel the electricity in the sacrum and bone marrow.
3. Touch the femur bones. Feel the electricity running up the legs.
4. Touch the humerus bones. Feel the electricity running up the arms.
5. Touch the lower part of the sternum and feel the Chi penetrate into the bones and spread out to the rib cage. Feel the electricity run throughout the rib cage.

Practice

1. Touch the sacrum, feel your fingers grown ‘long’ and penetrate into the marrow. Feel that the sacrum is as big as the universe and that the Chi has been compacted. Fill the sacrum with Chi. The eight holes are breathing. Let the fingers touch the sacrum and become aware of the Tan Tien spiraling, until you feel the crown and the mideyebrow spiral and connect to the universe. Hold until the universe fills the sacrum once again and rises up the spine to the mideyebrow.



Bone Marrow Cells



Fig. 4.70 *Touch the Sacrum - see the Eight Holes breathing - fill the Sacrum, Mideyebrow and Crown with Chi - empty to the universe and ‘fill’ again.*

Sacrum Breathing to get Chi

Breathe through the sacrum; feel red and yellow light enter. Guide it into Tan Tien. Blend the Chi in the Tan Tien. Move up to the Heart Center. Move up to the Crown and project up to the universe; let it blend and multiply. Multiply in the universe

Open a direct channel down to the other person, and one to your palm.

Table 4.2 Symptoms of Red Eye

Symptom	Referral Advisable **if Present**	Acute Glaucoma	Acute **Irido-** cyclitis	Keratitis	Bacterial Conjunctivitis	Viral Conjunctivitis	Allergic Conjunctivitis
Blurred vision	Yes	3	1 to 2	3	0	0	0
Pain	Yes	2 to 3	2	2	0	0	0
Photophobia	Yes	1	3	3	0	0	0
Colored halos	Yes	2	0	0	0	0	0
Exudation	No	0	0	0 to 3	3	2	1
Itching	No	0	0	0	0	0	2 to 3

Note: The range of severity of the symptom is indicated by 0 (absent) to 3 (severe).

- Keratic precipitates, or cellular deposits on the corneal endothelium, usually too small to be visible but occasionally forming large clumps; these precipitates can result from iritis or from chronic iridocyclitis (see Slide 30)
- A diffuse haze obscuring the pupil and iris markings, characteristic of corneal edema (see Slide 31) and frequently seen in acute glaucoma
- Localized opacities due to keratitis or ulcer (see Slide 32)

Corneal Epithelial Disruption

Disruption of the corneal epithelium occurs in corneal inflammations and trauma. It can be detected in two ways:

1. Position yourself so that you can observe the reflection from the cornea of a single light source (eg, window, penlight) as the patient moves the eye into various positions. Epithelial disruptions cause distortion and irregularity of the reflection (see Slide 33).
2. Apply fluorescein to the eye. Diseased epithelium or areas denuded of epithelium will stain a bright green. (See Slides 5 and 6 and accompanying text in Chapter 1 for the technique of fluorescein staining.)

Pupillary Abnormalities

The pupil in an eye with iridocyclitis typically is somewhat smaller than that of the other eye, due to reflex spasm of the iris sphincter muscle. The pupil is also distorted occasionally by posterior synechiae, which are inflammatory adhesions between the lens and the iris. In acute glaucoma, the pupil is usually fixed, middilated (about 5 to 6 mm), and slightly irregular. Conjunctivitis does not affect the pupil.

Shallow Anterior Chamber Depth

In a red eye, a shallow anterior chamber should always suggest the possibility of acute angle-closure glaucoma (see Slide 22). Anterior chamber depth can be estimated through side illumination with a penlight. If possible, compare the anterior chamber depth of the red eye with that of the other, unaffected eye. (See Chapter 1 for details on estimating the depth of the anterior chamber.)

Elevated Intraocular Pressure ❗

Intraocular pressure is unaffected by common causes of red eye other than iridocyclitis and glaucoma. Intraocular pressure should be measured when angle-closure glaucoma is suspected. (See Chapter 1 for the use of tonometry to measure intraocular pressure.)

Proptosis ❗

Proptosis is a forward displacement of the globe. Sudden proptosis suggests serious orbital or cavernous sinus disease; in children, orbital infection or tumor should be suspected. The most common cause of chronic proptosis is thyroid disease; however, orbital mass lesions also result in proptosis and should be ruled out early in the diagnosis (see Slide 35). Proptosis may be accompanied by conjunctival hyperemia or limitation of eye movement. Small amounts of proptosis are detected most easily by standing behind the seated patient and looking down to compare the positions of the two corneas.

Discharge

The type of discharge may be an important clue to the cause of a patient's conjunctivitis. Purulent (creamy-white, see Slide 29) or mucopurulent (yellowish) exudate suggests a bacterial cause. Serous (watery, clear or yellow-tinged) discharge suggests a viral cause. Scant, white, stringy discharge sometimes occurs in allergic conjunctivitis and in keratoconjunctivitis sicca, a condition commonly known as *dry eyes.*

Preauricular Lymph-Node Enlargement

Enlargement of the lymph node just in front of the auricle is a frequent sign of viral conjunctivitis. Usually, such enlargement does not occur in acute bacterial conjunctivitis. Preauricular node enlargement can be a prominent feature of some unusual varieties of chronic granulomatous conjunctivitis, known collectively as *Parinaud's oculoglandular syndrome.*

Symptoms of Red Eye

Blurred Vision ❗

Blurred vision often indicates serious ocular disease (see "Reduced Visual Acuity" in the preceding section, "Signs of Red Eye"). Blurred vision that improves with blinking suggests a discharge or mucus on the ocular surface.

Severe Pain ⚠

Pain may indicate keratitis, ulcer, iridocyclitis, or acute glaucoma. Patients with conjunctivitis may complain of a scratchiness or mild irritation but not of severe pain.

Photophobia ⚠

Photophobia is an abnormal sensitivity to light that accompanies iritis, either alone or secondary to corneal inflammation. Patients with conjunctivitis have normal light sensitivity.

Colored Halos ⚠

Rainbow-like fringes or colored halos seen around a point of light are usually a symptom of corneal edema, often resulting from an abrupt rise in intraocular pressure. Therefore, colored halos are a danger symptom suggesting acute glaucoma as the cause of a red eye.

Exudation

Exudation, also called mattering, is a typical result of conjunctival or eyelid inflammation and does not occur in iridocyclitis or glaucoma. Patients will often complain that their lids are "stuck together" on awakening from sleep. Corneal ulcer is a serious condition that may or may not be accompanied by exudate.

Itching

Although it is a nonspecific symptom, itching usually indicates an allergic conjunctivitis.

Associated Systemic Problems

Upper Respiratory Tract Infection and Fever

Infection of the upper respiratory tract accompanied by fever may be associated with conjunctivitis, particularly when these symptoms are due to adenovirus type 3 or type 7 (both of which cause pharyngoconjunctival fever). Allergic conjunctivitis may be associated with the seasonal rhinitis of hay fever.

Erythema Multiforme

Erythema multiforme is a serious systemic disorder, possibly an allergic response to medication, which can result in severe conjunctivitis, irreversible conjunctival scarring, and blindness. In erythema multiforme, bull's-eye or target-shaped red lesions are found on the skin. The name *Stevens-Johnson syndrome* is given to the form of erythema multiforme associated with ocular involvement.

Laboratory Diagnosis

In practice, most mild cases of conjunctivitis are managed without laboratory assistance. This represents a compromise with ideal management but is justified by the economic waste of obtaining routine smears and cultures in such a common and benign disease. Most clinicians, after making a presumptive clinical diagnosis of bacterial conjunctivitis, proceed directly to broad-spectrum topical ophthalmic antibiotic treatment. Cases of presumed bacterial conjunctivitis that do not improve after 2 days of antibiotic treatment should be referred to an ophthalmologist for confirmation of the diagnosis and appropriate laboratory studies. In addition, in cases of hyperpurulent conjunctivitis, when copious purulent discharge is produced, conjunctival cultures and ophthalmologic consultation are indicated because of a possible gonococcal cause. Gonococcal hyperpurulent conjunctivitis is a serious, potentially blinding disease.

In doubtful cases, smears of exudate or conjunctival scrapings can confirm clinical impressions regarding the type of conjunctivitis. Typical findings include polymorphonuclear cells and bacteria in bacterial conjunctivitis, lymphocytes in viral conjunctivitis, and eosinophils in allergic conjunctivitis. Cultures for bacteria and determinations of antibiotic sensitivity are also useful in cases resistant to therapy.

Management or Referral

The following conditions either require no treatment or may be appropriately treated by a primary care physician. Patients with chronic, unilateral blepharitis should be referred to an ophthalmologist to rule out a malignant process such as sebaceous cell carcinoma or squamous cell carcinoma. Cases requiring prolonged treatment or those in which the expected response to treatment does not occur promptly should also be referred to an ophthalmologist.

Blepharitis

Response to the treatment of blepharitis, or inflammation of the eyelid, is often frustratingly slow, and relapses are common. The mainstays of treatment are

- Eradication of staphylococcal infection (Slide 36) with frequent applications of appropriate antibiotic eyedrops or ointment
- Treatment of scalp seborrhea with antidandruff shampoos to prevent the spread of seborrhea to the eyes
- Cleansing of the lids to alleviate seborrheic blepharitis (Slide 37)



Slide 36 Staphylococcal blepharitis. Chronic staphylococcal lid infection produces inflamed, swollen lids that may ulcerate. The oily discharge binds the lashes and sometimes condenses to form a collarette around a lash.



Slide 37 Seborrheic blepharitis. The dry, flaky lashes and red lid margins seen here are characteristic of seborrheic blepharitis.



Slide 38 External hordeolum. This large, acute swelling, which is red and painful, involves the hair follicles or associated glands of Zeis or Moll and points toward the skin.

Stye and Chalazion

A stye, or hordeolum, is an acute inflammation of the glands or hair follicles in the eyelid. Hordeola can be categorized as external or internal according to where the inflammation is located in the lid (Slides **38** and **39).** A chalazion is a chronic inflammation of a meibomian gland in the eyelid that may develop spontaneously or may follow a hordeolum (Slide 40).

Styes are initially treated with hot compresses. Topical antibiotics can be used if the lesion is tender and infection is suspected. However, most styes



Slide 39 Internal hordeolum. An acute infection of a meibomian gland produces a swelling directed internally toward the conjunctiva. This figure demonstrates a discrete, circumscribed area of inflammation highlighted by a hyperemic conjunctiva.



Slide 40 Chalazion. This large, nontender lid mass is a chronic granulomatous inflammation of a meibomian gland.

and chalazia are sterile inflammatory reactions. Incision with curettage is indicated when lesions do not resolve spontaneously or with medical therapy. A persistent or recurring lid mass should undergo biopsy because it may be a rare meibomian gland carcinoma or squamous cell carcinoma of the lid rather than a benign chalazion.

Subconjunctival Hemorrhage

In the absence of blunt trauma, hemorrhage into the subconjunctiva, the potential space between the conjunctiva and the sclera, requires no treatment and, unless recurrent, no evaluation. (See Slide 49 in Chapter 5.) Causes include a sudden increase in ocular venous pressure, such as occurs with coughing, sneezing, vomiting, or vigorous rubbing of the eye. Many subconjunctival hemorrhages occur during sleep. If recurrent, an underlying bleeding disorder should be considered.

Conjunctivitis

Bacterial conjunctivitis is treated with frequent antibiotic eyedrops as well as antibiotic ointment applied at bedtime. Cool compresses may give some relief. There is no specific medicinal treatment for viral conjunctivitis, although patients should be instructed in proper precautions to prevent contagion. It cannot be emphasized too strongly that corticosteroids have no place in the treatment of infectious conjunctivitis and that eyedrops containing a combination of antibiotics and corticosteroids are seldom indicated for the treatment of ocular inflammation.

Therapeutic Warnings

Topical Anesthetics

Topical anesthetics should ***never*** be prescribed for prolonged analgesia in ocular inflammations and injuries for three reasons:

1. Topical anesthetics inhibit growth and healing of the corneal epithelium.
2. Although rare, severe allergic reaction may result from instillation of topical anesthetics.
3. Corneal anesthesia eliminates the protective blink reflex, exposing the cornea to dehydration, injury, and infection.

Topical Corticosteroids

Topical corticosteroids have three potentially serious ocular side effects:

1. Keratitis Both herpes simplex keratitis (see Slide 24) and fungal keratitis are markedly potentiated by corticosteroids. Corticosteroids may mask symptoms of inflammation, making the patient "feel" better, while the cornea may be melting away or even perforating.
2. Cataract Prolonged use of corticosteroids, either locally or systemically, will often lead to cataract formation.
3. Elevated intraocular pressure Local application of corticosteroids for 2 to 6 weeks may cause an elevation of intraocular pressure in approximately one third of the population. The pressure rise may be severe in a small percentage of cases. Optic nerve damage and permanent loss of vision can occur.

The combination of a corticosteroid and an antibiotic carries the same risk. Topical corticosteroids alone or in combination with antibiotics should not be administered to the eye by a primary care physician. They can be very helpful when used under the close supervision of an ophthalmologist.

Points to Remember

1. If visual acuity is acutely and significantly reduced, a diagnosis of conjunctivitis is extremely unlikely.
2. Fluorescein should always be instilled in a red eye to test for integrity of the corneal epithelium.
3. A pupillary inequality in a patient with red eye(s) is a danger signal for serious ocular disease.

Sample Problems

1. A 23-year-old school teacher complains that her right eye is red and irritated. You note moderate injection of the larger conjunctival vessels, watery discharge, and a palpable preauricular lymph node.

   A. From this information alone, what tentative diagnosis would you make?

   Answer: The conjunctival injection and discharge suggest conjunctivitis. The serous nature of the discharge plus the preauricular adenopathy indicate that she has viral conjunctivitis.

   B. Again based on the above information, which of the following symptoms or facts might be elicited by careful history-taking?

      a. Blurred vision
      b. Sore throat
      c. Exposure to children with colds
      d. Itching

   Answer: b and c. Sore throat often accompanies viral conjunctivitis; in such cases, a history of exposure to other individuals with upper respiratory tract infections can often be elicited. Blurred vision, a danger signal of serious ocular disease, is not a feature of simple conjunctivitis. Itching is a symptom of allergic, not viral, conjunctivitis.

   C. Which of the following are also likely findings in this case of viral conjunctivitis?

      a. A small pupil in the right eye
      b. Lymphocytes in a smear of conjunctival scrapings
      c. Keratic precipitates

   Answer: b. Lymphocytes are usually found in scrapings from eyes with viral conjunctivitis. A small pupil and keratic precipitates are signs of iritis.

   D. Management by a primary care physician should consist of which of the following?

      a. Corticosteroid eyedrops
      b. Broad-spectrum antibiotic eyedrops
      c. Referral to an ophthalmologist
      d. Instruction to the patient to use cool compresses and stay home from school until the redness resolves

   Answer: **d.** Because the disease is contagious, the patient should be instructed to remain home from work. There is no specific medicinal treatment for viral conjunctivitis. Corticosteroids are contraindicated.

2. A man returned recently from an African journey. During his trip he had three episodes of blurring and pain in his left eye; each episode lasted about 2 hours and was relieved by sleep. A few hours before consulting you, his symptoms recurred.

A. Which of the following signs convince you that the patient does not have conjunctivitis?
   a. Visual acuity of 20/200 in the left eye
   b. Conjunctival injection
   c. Ciliary flush
   d. Absence of exudate

Answer: a and c. Reduced visual acuity, as well as ciliary flush, often signals ocular disease more serious than conjunctivitis.

B. You note a diffuse haziness of the patient's left cornea. What is the most likely diagnosis?

Answer: Diffuse haziness of the cornea is usually due to edema. This and the history of recurrent attacks relieved by sleep suggest the diagnosis of acute angle-closure glaucoma.

C. You seek confirmatory data for your tentative diagnosis. What do you expect the following tests to show if your diagnosis is correct?
   a. Estimation of anterior chamber depth: deep or shallow?
   b. Determination of pupil diameter: large, middilated, or small?
   c. Measurement of intraocular pressure: high or low?

Answer: In angle-closure glaucoma, the anterior chamber is shallow, the pupil is usually *middilated,* and the intraocular pressure is high.

D. Your management should be which of the following?
   a. Corticosteroid eyedrops
   b. Advice to see an ophthalmologist the next day
   c. A telephone request to an ophthalmologist for immediate examination

Answer: c. Angle-closure glaucoma requires emergency treatment to lower the intraocular pressure. The patient should be referred immediately to an ophthalmologist. If an ophthalmologist is not immediately available, you may begin topical pilocarpine hydrochloride 1% or 2%, a topical beta-adrenergic blocker, and a systemic carbonic anhydrase inhibitor. (See Chapter 9 for details on these drugs.)

3. After working in his garden, a 57-year-old man complains of moderate discomfort and redness in his right eye. You note a visual acuity of 20/25 in the right eye and 20/15 in the left eye. The right eye has mild hyperemia of the conjunctival vessels; the right cornea appears clear to penlight examination. You diagnose a probable allergy to pollen and advise the patient to use topical dexamethasone sodium phosphate 0.1% for **3** days.

A. Give two reasons why your diagnosis of allergic conjunctivitis is unlikely to be correct.

Answer: Unless the patient has always had weaker vision in his right eye, this finding should alert you to the possibility of a more serious inflammation, such as iritis, keratitis, or glaucoma. Also, the patient did not complain of itching, which you might expect in an allergic reaction.

B. What other diagnostic techniques should you have performed to be certain that the cornea is normal?

Answer: If the patient has an early herpes simplex keratitis or if his cornea has been scratched by a twig, the epithelial disruption might not be easily seen during a penlight examination. However, it most likely would be rendered visible by fluorescein staining of the cornea.

C. Is there any hazard in your prescribed course of treatment? Explain.

Answer: Yes. The virulence of both herpes simplex and fungal infections, which can result from trauma involving organic material, is markedly potentiated by the application of topical corticosteroids to the eye.

4. A 38-year-old woman complains of a 3-day history of a red, tender right eyelid. Physical examination reveals a tender nodule of the right lower eyelid with minimal injection of the inferior conjunctiva.

A. Which of the following would constitute appropriate management by the primary care physician? (More than one course of action may be possible.)
   a. hot compresses
   b. broad-spectrum systemic antibiotics
   c. topical antibiotics
   d. immediate surgical incision and drainage to prevent cellulitis

Answer: a **and** c. The patient has a stye. Because she has only had symptoms for 3 days and the lesion is tender to touch, she would benefit from hot compresses. Topical antibiotic ointment might benefit a small percentage of patients. Incision and drainage is indicated only when lesions do not resolve spontaneously or with medical therapy. Usually surgical intervention occurs only after the lesion has been present for several weeks. Systemic antibiotics are not indicated.

B. If the patient reports she has had numerous nodules in this same area over the last 5 years, how should the primary care physician change the management plan?

Answer: A persistent or recurring lid mass should undergo biopsy to rule out an eyelid malignancy. Referral to an ophthalmologist is indicated.

Annotated Resources

Albert DM, Jakobiec FA, eds: *Principles and Practice of Ophthalmology.* Philadelphia: WB Saunders Co; 1993. Chapters with information relevant to red eye conditions include Chapter 6, "Viral Disease of the Cornea and External Eye"; Chapter **7,** "Bacterial Infections of the Conjunctiva and Cornea"; and Chapter 152, "Eyelid Infections."

Newell FW: *Ophthalmology: Principles and Concepts.* 8th ed. St Louis: CV Mosby Co; 1996. This comprehensive text includes detailed discussions of diseases of the conjunctiva and cornea.

Sacrum Chi

Project the student's feet down to the earth and connect to the earth's core.


Eight Holes Breathing

Third Eye and Temple Bones are aligned in a triangle.

Activate the Sacrum until you feel the Chi rising up the spine and feel it pulsing; be aware of the Temple Bones.

Fig. 4.71 *Activate the Sacrum - Be aware of the Temples.*

2. Tell the student to move their hands to the hip bones. Tell them to smile to these bones. Feel them as 'funny, laughing, happy bones'. Tell them to feel the electricity in the sacrum and bone marrow. Tell the student to pack and compress the Chi into the bones in order to revitalize and revive bone marrow. Give the command. "Produce healthy white and red blood cells".


Breast Bone
Ribs
Spine
Become aware of your arms. The bones are as big as the universe.
Hip Bones
Become aware of your legs. The bones are as big as the universe.

Fig. 4.72 *"Hip Bones produce healthy White and Red Blood Cells".*

Tasman W, Jaeger EA, eds: *Duane's Clinical Ophthalmology.* Philadelphia: *JB* Lippincott Co; 1991, vol 4. Updated, comprehensive discussions of various forms of conjunctivitis are found in Chapters 4 to 9A and of anterior uveitis in Chapters 39 to 42.

Trobe JD: *The Physician's Guide to Eye Care.* San Francisco: American Academy of Ophthalmology; 1993. A brief but comprehensive resource covering the principal clinical ophthalmic problems that nonophthalmologist physicians are likely to encounter, organized for practical use by practitioners.

Chapter *5*

Ocular and Orbital Injuries

Objectives

As a primary care physician, you should be able to evaluate the common ocular or orbital injuries and to determine whether or not the problem requires the prompt attention of an ophthalmologist. In situations of true ocular emergency, such as chemical burns, you should be able to institute therapy when necessary.

To achieve these objectives, you should learn

- To recognize which problems are emergent or urgent and deal with them accordingly
- To obtain the salient historical facts
- How to examine the traumatized eye
- To record the visual acuity as accurately as possible
- How to determine whether to manage or to refer the most common injuries

Relevance

One day, whether in your own home or yard or while on duty in the emergency center, you will be confronted with an unexpected ocular injury. Your skill in dealing with major eye injuries can mean the difference between preservation and loss of a patient's vision. The purpose of this chapter is to assist in developing confidence when approaching minor or major eye injuries; it will further your competence in acquiring the basic techniques and knowledge necessary to assess and initiate treatment of the eye and its surrounding structures.

Basic Information

Anatomy and Function

Bony Orbit

- The orbit is the bony, concave cavity in the skull that houses the globe, the extraocular muscles, and the blood vessels and nerves of the eye (Figure 5.1).
- The rim of the orbit protects the globe from impact with large objects.


Frontal bone
Superior orbital rim
Palatine bone
Optic canal
Ethmoid bone
Lesser sphenoid wing
Medial orbital rim
Lateral orbital rim
Greater sphenoid wing
Zygomatic bone
Inferior orbital rim
Maxillary bone
Lacrimal bone

Figure 5.1 The bony orbit.

- A rim fracture usually causes no decrease in ocular or visual function.
- The very thin orbital floor (consisting of the maxillary, palatine, and zygomatic bones) may "blow out" into the maxillary sinus from blunt impact to the orbit, for instance, from a fist or tennis ball. Orbital contents, including the inferior rectus and inferior oblique muscles, may become trapped, restricting vertical eye movement and causing double vision (diplopia).
- A medial fracture of the thin ethmoidal bone may be associated with subcutaneous emphysema of the eyelids.
- A fracture at or near the optic canal, through which the optic nerve and ophthalmic artery pass, may cause damage to the optic nerve or the vessels that supply it (traumatic optic neuropathy), with resulting visual loss.

Eyelids

- The lids close reflexively when the eyes are threatened.
- The act of blinking keeps the cornea clear through constant surface contact and tear production.
- In the case of a facial nerve palsy, the globe may be exposed to drying or other injury.
- Lid margins must be intact to ensure proper lid closure and tear drainage.

Lacrimal Apparatus

- Tear drainage occurs at the medial aspect of the lids, primarily through the lower lacrimal punctum, and continues through the canaliculi to the lacrimal sac, and via the nasolacrimal duct to the nose (see Figure 1.2 in Chapter 1).
- Failure to recognize and properly repair a canalicular laceration can result in chronic tearing (epiphora).

Conjunctiva and Cornea

- The corneal epithelium usually heals quickly following abrasion.
- Small lacerations of the conjunctiva heal quickly and, consequently, may conceal a penetrating injury of the globe.

Anterior Chamber

- The aqueous humor often escapes in penetrating injuries, sometimes resulting in a shallow or flat chamber.

Iris and Ciliary Body

- Following laceration of the cornea or limbus, the iris may prolapse into the wound (Slide 41), resulting in an irregular pupil.
- Blunt trauma to the eyeball may produce iritis, resulting in pain, redness, photophobia, and a small pupil (miosis).
- Contusions may deform the pupil by tearing the iris root or by notching the pupillary margin.
- Contusions may result in tearing of small vessels in the anterior chamber angle, causing hemorrhage into the anterior chamber (hyphema, Slide 42). A hyphema is generally the result of trauma and usually resolves spontaneously.



Slide 41' Corneal perforation with iris prolapse. Slight distortion of the pupil, irregularity of the corneal reflection, and a knuckle of soft, brown tissue at the limbus indicate a corneal perforation through which the iris has prolapsed.



Slide 42 Hyphema. In the anterior chamber at the 6-o'clock position, a dark pool of blood with a flat top is visible. Note also the conjunctival hyperemia.

Lens

- Injuries to the lens usually proceed to cataract formation.
- Blunt trauma to the globe can cause a partial dislocation (subluxation) of the lens (Slide 43).

Vitreous Humor

- Loss of transparency may be observed in the presence of hemorrhage, inflammation, or infection.

Retina

- The retina is protected externally by the sclera (a tough outer layer) and the choroid (an underlying vascular layer).
- The retina is thin and vulnerable. If the surface is scratched or has been penetrated by a foreign body, retinal detachment may occur (see discussion and Slide 7 in Chapter 2).
- Retinal hemorrhage may develop as a result of direct or indirect trauma.
- The retina turns white when edematous.
- Macular damage will reduce visual acuity without producing complete blindness.

When to Examine

Most ocular injuries present with obvious redness and pain. However, not *all* injuries provide such obvious warning signs. For example, a sharp perforation may produce minimal redness and escape attention. The examiner should be especially alert to perforating injuries caused by small projectiles resulting from metal striking metal. An intraocular foreign body (Slide 44) produces no pain because the lens, retina, and vitreous have no nerve endings to conduct sensations of pain.

If disease of the posterior segment is suspected, including retinal detachment or intraocular foreign body, referral to an ophthalmologist is



Slide 43 Subluxated lens. Light reflected off the fundus and back through a dilated pupil silhouettes the edge of a subluxated lens with stretched zonular fibers. Ordinarily, the edge of the lens is not visible even if the pupil is widely dilated.



Slide 44 CT scan of foreign body. A small, radiopaque intraocular foreign body is visible in the anterior segment of the eye.

indicated. The ophthalmologist's examination of the fundus will be facilitated if you do not use ointment in the eye.

How to Examine

For an eye injury, you should obtain a patient history if possible, and perform a complete examination of the eyes and surrounding structures. This should include visual acuity, external examination, the pupils, eye movements, and ophthalmoscopy. Two sample examinations are provided in Tables 5.1 and 5.2.

History

In the evaluation of ocular injuries, it is important to document the type of traumatic event as well as the time of onset and the nature of the symptoms. Specific historical information to obtain includes the time, place, and type of injury (eg, blunt or sharp trauma; acid or alkali burn) and the patient's history of eye conditions, drug allergies, and tetanus immunization. As in any trauma situation, you should not delay prompt treatment for a detailed history if an obvious injury, such as a chemical burn, exists.

After significant trauma has occurred, the patient may be unconscious or unable to answer questions. In this case, the physician can question whoever accompanied the patient for as much historical information as possible, but must be prepared to assess the injury and proceed with treatment or referral in the absence of adequate historical information.

Visual Acuity Testing

Visual acuity should be recorded as specifically as possible. Refer to Chapter 1 for instructions on the use of the Snellen eye chart. If a Snellen chart is unavailable, determine the patient's ability to read available print material and record the type of print used (eg, newspaper, telephone book) and the

Table 5.1 Sample Examination: Foreign-Body Sensation

History	
Type of injury, time, and place	Foreign-body sensation, 3:15 AM, seen in emergency center
Pertinent chain of events Is trauma centered in OD, OS, or OU?	At about 2:45 AM, patient awoke with severe foreign-body sensation OU
Subjective visual loss, if *any*, and amount of visual decrease Associated complaints, symptoms	No injury, although admits to using sunlamp to tan face for 20 minutes previous evening. Now unable to open eyes, which aggravates burning foreign-body sensation. Unable to see well but uncertain about degree of visual loss.
Was vision normal prior to injury?	Patient states vision has been normal until now.
Examination	
Best correctable VA for both eyes, ie, with glasses if available, with pinhole if necessary	Unable to cooperate until 1 drop proparacaine 0.5% administered OU VA: OD 20/25; OS 20/20
Appearance and function of:	
Bony orbit and lids	Bony orbit intact Marked eyelid spasm until anesthetic drops given
Cornea and conjunctiva	Cornea stains irregularly with fluorescein Conjunctival injection OU, pronounced near limbus
Media (aqueous, lens, vitreous)	Media clear on gross inspection
Diagnosis	Ultraviolet conjunctival and corneal injury
Management	Cycloplegic drops, antibiotic ointment, and moderate pressure dressing

distance at which it was read. Note in particular whether vision is equal in both eyes. If vision is below reading level, determine the patient's ability to count fingers, perceive hand motions, or respond to light.

External Examination

An examination of the external structures of the eye may include palpation, penlight inspection, lid eversion, fluorescein staining, and topical anesthesia. Palpation of the orbital rims should be performed if a blunt injury or fracture is suspected. A penlight is used to inspect the eye for signs of perforation, such as reduced depth of the anterior chamber or uveal prolapse (see Slide 41). Hyphema (see Slide 42) may be present without perforation and, in fact, often accompanies blunt injury. Lid eversion (retraction and eversion of the upper and lower eyelids) will facilitate

Table 5.2 Sample Examination: Double Vision

History	
Approximate onset of symptoms Type of symptoms, frequency, regularity	A 16-year-old boy complains that he awoke 2 days ago with fullness OS. Later, he noted vertical double vision when looking straight up, up and right, and up and left; no double vision when looking straight ahead. No other problem except mild aching when looking up. Hit by knee in left eye in wrestling class 3 days earlier.
Increasing or decreasing severity?	Symptoms unchanged since first noted.
Examination	
Ocular findings	Perform complete eye examination, with particular attention to testing extraocular muscles. Rule out possible damage to the globe. Patient unable to elevate left eye beyond primary gaze. Globe examination unremarkable except for localized subconjunctival hemorrhage. Visual acuity normal.
X-rays	Obtain Waters view, which reveals opacification of the maxillary antrum and downward herniation of orbital structures. CT scan more clearly delineates fracture of orbital floor.
Diagnosis	Blowout fracture left orbit with muscle entrapment.
Management	Call ophthalmologist. Patient should be evaluated semiurgently for consideration of surgical repair.

inspection for a foreign body or chemical burn. *Do not manipulate the eyelids if you suspect a penetrating injury of the globe.*

If the patient has a foreign-body sensation or if there is a history of blunt or sharp injury, fluorescein is used to stain the cornea to identify any corneal epithelial defects. (See Chapter 1 for the technique of fluorescein staining.)

Drops can be used to provide topical anesthesia, especially to relieve foreign-body sensation or discomfort due to radiant energy burns or prolonged wear of contact lenses. Use of 1 drop of proparacaine hydrochloride 0.5% will provide almost instantaneous pain relief and allow you to proceed with an adequate evaluation, including determination of visual acuity, which would otherwise be impossible due to discomfort. Do not prescribe or distribute samples of anesthetic drops or ointment because prolonged use can result in corneal ulceration and inadvertent injury.

Pupillary Reactions

Always check pupillary reactions in trauma cases. Diminished direct pupillary reaction to light with an intact consensual response (a relative afferent pupillary defect) may indicate an optic nerve injury (see Chapter 7).

Ocular Motility Testing

Movement of the eye may be generally restricted in the case of orbital hematoma. Vertical restriction combined with vertical diplopia should make you suspect a blowout fracture. If limitation of eye movements is accompanied by proptosis, auscultate the head and eye for a bruit, which would be suggestive of a carotid–cavernous sinus fistula.

Ophthalmoscopy

If the fundus is visible, look for edema, retinal hemorrhages, retinal detachment, and, if penetration is suspected, a foreign body. In the event of a positive finding or the suspicion of a penetrating injury or foreign body, refer the patient to an ophthalmologist immediately.

The normal red reflex from the fundus is evenly colored and not interrupted by shadows (see Slide 1 in Chapter 1). If the red reflex is absent, immediate referral to an ophthalmologist is indicated. Absence of the red reflex may be due to hyphema in the anterior chamber, cataract from acute swelling of the lens, or vitreous hemorrhage. Hyphema is visible on external examination with a penlight, whereas the detection of cataract and vitreous hemorrhage requires assessment with a direct ophthalmoscope.

Pupillary dilation to permit evaluation of the fundus should be routine. The only general exceptions to this rule would be in patients with head trauma where pupillary signs might be important for neurologic evaluation and patients whose shallow anterior chamber predisposes them for narrow-angle glaucoma.

Radiologic Studies

Radiologic evaluation is suggested if there is any question of facial or orbital fracture or of ocular or orbital foreign body. A CT scan can often provide additional useful detail. MRI should not be ordered if a metallic foreign body is suspected, because the metal may heat, vibrate, or move during the scan, resulting in additional intraocular injury.

Management or Referral

The primary care physician may not be able to provide definitive care for each of the entities discussed below, but should be able to initiate treatment in every case.



Slide 45 Alkali burn. Blanching of the conjunctiva and a large corneal epithelial defect, demonstrated by application of fluorescein, indicate a relatively serious injury.

True Emergency

Therapy must be instituted within minutes. A chemical burn of the conjunctiva and cornea represents one of the true ocular emergencies. *An* alkali burn (Slide 45) usually results in greater damage to the eye than an acid burn, because alkali compounds (eg, lye, anhydrous ammonia) penetrate ocular tissues more rapidly. All chemical burns require immediate and profuse irrigation, followed by referral to an ophthalmologist.

Urgent Situation

Urgent situations require therapy to be instituted within a few hours. The following list describes common urgent ocular situations and appropriate actions to take for each.

- Penetrating injuries of the globe, whether actual or suspected, necessitate the protection of an eye shield. Neither a patch nor an ointment is advisable. *An* x-ray or CT scan of the orbit to check for radiopaque foreign bodies (see Slide 44) should be ordered. Referral to an ophthalmologist is indicated.
- Conjunctival or corneal foreign bodies (Slides 46 and 47) require topical anesthetization followed by removal of the object with either vigorous irrigation or a cotton-tipped applicator. See "Foreign-Body Removal," below, for specific instructions.
- For corneal abrasions, take the following steps:
  1. Anesthetize with proparacaine 0.5%.
  2. Perform a gross examination.
  3. Stain with fluorescein to enhance the view. (For a depiction of a fluorescein stain delineating a corneal abrasion, see Slides 5 and 6 in Chapter 1.)
  4. Instill antibiotic drops; instill short-acting cycloplegic drops for the relief of pain as indicated.
  5. Some physicians apply a pressure patch to maintain lid closure for 24 hours, although others feel that abrasions less than 10 mm in diameter heal better and more quickly without a pressure patch.
  6. Refer severe cases to an ophthalmologist.
- Hyphema requires immediate referral to an ophthalmologist. Elevation of intraocular pressure may necessitate medical or surgical intervention.







White Blood Cell
(Neutrophil)

Leave the fingers touching the hip bones and start to spiral in the Tan Tien until you feel the crown and the mideyebrow also spiral. Expand your awareness to the Universe and the Universe will charge into the hip bones.

Fig. 4.73 *Touch and feel the bones. Leave your fingers there - lower your mind into the Tan Tien and the universe.*

3. Touch the middle part of the femur bone to help increase the production of healthy red blood cells. Feel the electricity running up the legs. Give the same command for the femur bones: "Funny, laughing, happy bones produce healthy white and red cells." After that put your mind into the Tan Tien and universe so that the Chi can charge into the bones. Feel electricity run throughout the whole skeleton.

Fig. 4.74 *"Funny, laughing, happy femur bones produce healthy white and red blood cells".*





4. Touch the humerus bones. Feel the electricity running up the arms.Give the same command: "Funny, laughing, happy bones produce healthy white and red cells." After that, put your mind into the Tan Tien and universe so that the Chi can charge into the bones. Give the same command for the lower part of the sternum. Chi penetrates into the bone and spreads out into the rib cage 'Tan Tien and Universe'. Put your mind into the Tan Tien and the universe so that the Chi can charge into the bones.



Slide 46 Conjunctival foreign body. A foreign body often lodges under the edge of the upper eyelid. As this figure shows, the foreign body is easily seen and removed upon eversion of the eyelid.



Slide 47 Corneal foreign body. Visible here is a small piece of iron embedded in the surface of the cornea. Surrounding the iron are a ring of rust and grayish corneal edema.

Also, the hyphema may be a sign of globe rupture or some other, initially obscure, serious ocular injuries, such as dislocated lens or retinal detachment.

- A lid laceration can be sutured if not deep and neither the lid margin nor the canaliculi are involved; otherwise, refer to an ophthalmologist. (The lid laceration shown in Slide 48 would require referral because it is full-thickness and involves the lid margin. There is also a possibility of canalicular involvement because the laceration is close to the medial canthus.)
- Radiant energy burns, such as welder's burn or snow blindness, require topical anesthesia, examination, topical antibiotic and cycloplegic agents, and patching. (See Chapter 9 for information about instilling ocular medications.)
- Traumatic optic neuropathy, although uncommon, should always be considered in patients with cranial or maxillofacial trauma. Patients present with a history of facial or frontal trauma, usually with unilateral decreased vision and a relative afferent pupillary defect, but further examination reveals no clear ocular origin. High-resolution CT imaging of the orbital apex, optic canal, and cavernous sinus is essential if traumatic optic neuropathy is suspected. Patients may benefit from intravenous high-dose methylprednisolone if given in the first 8 hours after initial injury. If a patient is suspected of having traumatic optic neuropathy, a prompt referral to an ophthalmologist is indicated.



Slide 48 Full-thickness lid laceration. The lower eyelid is partially everted with the applicator stick, revealing an irregular laceration of the lid margin, orbicularis muscle, tarsal plate, and conjunctiva. Note the proximity of the laceration to the medial canthus, indicating possible canalicular involvement.



Slide 49 Subconjunctival hemorrhage. This circumscribed hemorrhage is located between the conjunctiva and the sclera; the history of a sudden appearance and the bright red color are characteristic.

Semiurgent Condition

Refer patients with semiurgent conditions to an ophthalmologist within 1 to 2 days. An orbital fracture falls in this category. Subconjunctival hemorrhage (Slide 49) in the presence of blunt trauma is also a semiurgent condition, unless a globe rupture or intraocular hemorrhage is suspected, in which case urgent referral to an ophthalmologist is indicated.

Treatment Skills

To manage eye injuries properly, every physician should be proficient in ocular irrigation, foreign-body removal, eye medication prescription, patching, and suturing.

Ocular Irrigation

Plastic squeeze bottles (Slide 50) of eye irrigation solutions and normal saline IV drip with plastic tubing are ideal for ocular irrigation. Irrigation may be facilitated by the use of a topical anesthetic. However, first aid for chemical injuries of the eye may demand the earliest possible irrigation using any source of water available, such as a garden hose, drinking



Slide 50 Irrigation. Here the examiner uses a plastic squeeze bottle of water or normal saline to irrigate the eye. The patient is instructed to look in various directions while the opposite portions of the conjunctival cul-de-sac are flushed vigorously.

fountain, or faucet. It cannot be overstated that chemical burns require immediate and profuse irrigation. Always direct the irrigating stream toward the temple and away from an unaffected fellow eye.

Foreign-Body Removal

To remove a superficial foreign body from the cornea or conjunctiva, instill an anesthetic such as proparacaine 0.5% and then gently roll a cotton-tipped applicator across the globe to pick up the object. A forceful stream of irrigating solution delivered from a squeeze bottle will often dislodge a superficial conjunctival or corneal foreign body. A sharper instrument may be required if the foreign body remains embedded, and referral to an ophthalmologist should be considered. The orange-brown "rust ring" resulting from an embedded iron foreign body is a common problem that requires special attention.

Eye Medication Prescription

All physicians should be able to prescribe or administer confidently the following ocular drugs. (See Chapter 9 for more detailed discussions and for the method of administering topical ocular drugs.)

- Cycloplegics Homatropine hydrobromide 2% or cyclopentolate hydrochloride 1% may be used to relax the iris and ciliary body and to relieve the pain and discomfort of most forms of nonpenetrating ocular injuries. Longer-acting cycloplegics (eg, atropine) are usually contraindicated.
- Antibiotic ointment In general, if employed for one-time use in clean wounds, antibiotic ointments can be used safely without side effects. If more frequent use is necessary, the possibility of allergic reactions or superinfections must be considered.
- Anesthetic drops and ointment Ocular anesthetics should never be prescribed for home use because they are toxic to the corneal epithelium when used repeatedly.

Patching

- **Pressure patch** A moderate pressure patch is used following injuries that affect the corneal epithelium (eg, corneal abrasions) and after removal of foreign bodies. Two eye patches or one eye patch plus a fluffed piece of gauze is applied by putting moderate tension on the strips of tape used (Slide 51). Make sure the patch is tight enough to prevent the patient from inadvertently opening the eye under it. The patch should not be so tight as to cause the patient discomfort or severely compress the globe, which can compromise the retinal blood flow.
- **Shield** For more serious ocular injuries, such as penetration of the globe or hyphema, a shield should be taped over the eye as an interim measure to protect the eye from rubbing, pressure, and further injury prior to treatment by an ophthalmologist. The shield may consist of a perforated, malleable piece of metal (Slide 52), plastic, or a trimmed-down paper cup.

Suturing

Suturing of any eyelid skin laceration that does not involve the eyelid margin or the lacrimal canaliculi can be performed by the primary care physician. More complicated lid lacerations should be referred to an ophthalmologist.



Slide 51 Pressure patch. The patient is instructed to close the affected eye while one or more oval, gauze eye patches are taped firmly enough to immobilize the lid in a closed position.



Slide 52 Shield. Shown here is the Fox shield, made of malleable metal and perforated. The shield is carefully shaped so that it is supported by the rim of the orbit when taped in place.

Points to Remember

1. Know your limits: Do not attempt complex repair, and know the results of inadequate repair.
2. Almost without fail, a teardrop-shaped pupil and a flat anterior chamber in an injured eye are associated with a perforating injury of the cornea or of the limbal area. Look for prolapse of dark tissue (either iris or ciliary body) at the point of the teardrop.
3. Avoid digital palpation of the globe in the patient who may have a corneal laceration or other perforating injury.
4. In a patient with a chemical burn, immediate irrigation is crucial just as soon as the nature of the injury has been learned. Do not attempt to neutralize or buffer the chemical substance. The goal is simply to dilute the chemical as thoroughly as possible by copious flushing.

Sample Problems

1. Your neighbor, a 43-year-old woman, is cleaning her swimming pool. While pouring some concentrated algicide into the pool, a large dollop of this solution splashes into her right eye. You are mowing your lawn when you hear her screams. You come to her aid less than 30 seconds after the injury. Which of the following should you do first?
   a. Bundle her into your car and speed off for the nearest emergency center.
   b. Run back home to get your medical bag where you keep a squeeze bottle of ophthalmic irrigating solution that you can use to flush out her eye.
   c. Run back to your study to look up the specific antidote for algicide.
   d. Carefully examine her eye for evidence of ocular hyperemia.
   e. Dunk her head into the swimming pool, instructing her to hold her eyes open to flush out the chemical.

   Answer: *e.* This is one of the few true emergencies of all the ocular injuries that you must know. Early and copious irrigation with whatever source of water is handy is the right approach to this problem. Even with prompt treatment, serious ocular injuries and visual damage may result, depending on the offending chemical. Time is of the essence. Do not resort to methods that will cause delay.

2. You are on duty in the emergency center when an 18-year-old high school student comes in because of pain, tearing, sensitivity to light, and blurred vision in his right eye. His symptoms began sometime that afternoon. Earlier, he had been working on his car and he remembers something flying into his right eye while he was trying to knock a rivet off the chassis with a hammer and chisel. You examine his eye and take visual acuity measurements. You determine that visual acuity is 20/50 in the right eye and 20/20 in the left eye. There is some conjunctival hyperemia. The pupil of the right eye seems to be peaked and pointing to the 7-o'clock position of the limbus. There is a small, dark, slightly

elevated body at the 7-o'clock position of the limbus. You cannot see fundus details of the right eye, but the left eye appears normal. Which of the following would be the appropriate initial management for this situation?

a. Irrigation of the limbal foreign body
b. Application of a protective shield
c. Removal of the limbal foreign body with a cotton-tipped applicator
d. Removal of the limbal foreign body using forceps
e. A prescription for topical anesthetic (eg, proparacaine 0.5%) to relieve the patient's symptoms, with strict instructions that he return to see you if his blurred vision continues into the week

Answer: b. Any patient whose recent activities involve striking metal on metal should be suspected of having a foreign body, even with minimal signs and symptoms. However, the case illustrated includes a giveaway sign, namely, peaking of the pupil toward the 7-o'clock position. At that position, the dark body is likely to be iris or ciliary body rather than a foreign body. This indicates a penetrating ocular injury, and the patient should be protected from further eye trauma by a protective shield. A CT scan will confirm the diagnosis of ocular or orbital foreign body. The patient should be considered an urgent referral to an ophthalmologist.

3. While cutting his roses, a neighbor develops a sudden pain in his left eye. Inspection is limited because his eyes are closed, but nothing is visible on external examination.

A. What do you think might have happened?

Answer: Possibilities include a foreign body on the eye or under the lid; a superficial abrasion; or, less likely but still possible, perforation by a thorn.

B. What steps would you need to take to assess and treat this problem?

Answer: (1) Open the lids gently; never force them open, and never apply pressure to the globe if perforation is suspected. Instill a drop of topical anesthetic, if necessary, to facilitate examination. (2) Inspect the cornea and the sclera for a foreign body or possible perforation. **(3)** Evert the lids to look for a foreign body, unless perforation is suspected. (4) Remove the foreign body by irrigation or with a cotton-tipped applicator. (5) Act on any indications for drops, ointment, or patching. *(6)* If by history a possibility of ocular penetration exists, referral to an ophthalrnologist is indicated. Clinical findings in such cases can be very subtle. Ocular penetration with vegetable matter such as a thorn carries not only the usual risks of ocular penetration (ie, endophthalmitis, cataract, and corneal scar) but also the possibility of a fungal infection.

4. While you are on duty in the emergency center, a patient is brought in who has been involved in a car accident. His face is bloody, especially around the eyes. His history is unclear.

A. What would you do? What would you avoid?

Answer: Cleanse carefully. Avoid pressure of any kind on the eye.

B. While cleansing, you find a cut in the eyelid. It seems easy to stitch, but the lids are swollen and the patient cannot open his eye. What next? Do you stitch the lid?

Answer: First, inspect the eye for possible perforation. Because the lid laceration is not an emergency, stitching is not immediately necessary.

C. If the eye is normal, how should you analyze the problem of the lid laceration?

Answer: The appropriate choice of treatment depends on the level of damage. If only the skin is involved, you may be able to stitch the lid. If the laceration is full-thickness or involves the lid margin, referral to an ophthalmologist is preferred. Any involvement of the canaliculi requires exquisite repair in order to avoid a tearing problem for the rest of the patient's life; referral to an ophthalmologist is mandatory.

5. A 25-year-old man visits the emergency room complaining of decreased vision and pain in his right eye after being involved in a fist fight. Although he has edema and ecchymosis of the eyelids, you are able to examine his eye. His visual acuity is 20/70 OD and 20/20 OS, and his pupils are round and reactive. However, the right pupil is sluggish, and shining a light in either eye causes pain in his right eye. He has no restriction of motility. On examination of the anterior segment, you notice a diffuse haze in the anterior chamber and early layering of blood inferiorly. Direct ophthalmoscopy is difficult, but the central retina appears flat without hemorrhages. Which of the following would be the most appropriate treatment?

a. Instill antibiotic ointment and cycloplegic drops, apply a pressure patch, and have the patient follow up with an ophthalmologist in a few days.
b. Prescribe steroid drops and cycloplegic drops, and tell the patient to keep his head elevated at all times.
c. Immediately refer the patient to an ophthalmologist to rule out ruptured globe or increased intraocular pressure.

Answer: c. Although option *b* may represent appropriate treatment for hyphema, the patient needs to be adequately evaluated for a ruptured globe. The periphery of the retina needs to be evaluated closely. Option *a* represents treatment for corneal abrasion, not hyphema.

Annotated Resources

Deutsch TA, Feller DB, eds: *Paton and Goldberg's Management of Ocular Injuries.* 2nd ed. Philadelphia: WB Saunders Co; 1985. Used widely by ophthalmology residents, this book contains extensive information useful to the student or emergency center physician who desires more Information on serious eye trauma.

External Disease and Cornea. Section 8 of Basic and Clinical Science Course. San Francisco: American Academy of Ophthalmology; updated annually. An excellent summary of anterior segment trauma, covering general principles, burns, superficial injuries, blunt trauma, and perforating injuries.

Kaiser PK, Corneal Abrasion Patching Study Group: A comparison of pressure patching versus no patching for corneal abrasions due to trauma or foreign body removal. *Ophthalmology* 102;12:1936–1942. Patients with noninfected non-contact-lens-related traumatic corneal abrasions and abrasions secondary to foreign body removal healed faster with less pain using antibiotics and mydriatics alone, without the need for a pressure patch.

Kaiser PK, Pineda R, Corneal Abrasion Patching Study Group: A study of topical nonsteroidal anti-inflammatory drops and no pressure patching in the treatment of corneal abrasions. *Ophthalmology* 104;8: 1353–1359. The addition of a topical NSAID to antibiotic treatment of non-contact-lens-related traumatic corneal abrasions increased patient comfort and sped time to resumption of normal activities.

Newell FW: *Ophfhalmology: Principles and Concepts.* 8th ed. St Louis: CV Mosby Co; 1996. Ocular injuries are summarized succinctly in "Injuries of the Eye" in this comprehensive textbook.

Trobe JD: *The Physician's Guide to Eye Care.* San Francisco: American Academy of Ophthalmology; 1993. A brief but comprehensive resource covering the principal clinical ophthalmic problems that nonophthalmologist physicians are likely to encounter, organized for practical use by practitioners.

Chapter **6**

Amblyopia and Strabismus

Objectives

As a primary care physician, you should be able to recognize the signs and symptoms of amblyopia and strabismus; be able to perform the necessary tests to screen for these conditions; and, if the patient is a child, be cognizant of the need to arrange for prompt ophthalmologic consultation, particularly when intraocular disease is suspected.

To achieve these objectives, you should learn

- To measure or estimate visual acuity in children
- To detect strabismus by general inspection, the corneal light reflex test, and the cover test
- To perform ophthalmoscopy in a child to rule out any organic causes of impaired vision when amblyopia is suspected
- To explain to parents the need for prompt treatment of amblyopia

Relevance

Amblyopia is a form of treatable visual loss found in approximately 2% of the young adult population of the United States. It can be defined as a loss of visual acuity not correctable by glasses in an otherwise healthy eye. Amblyopia develops in infancy or early childhood and usually can be detected in very young patients, principally by measuring or estimating visual acuity. If detected and treated early, amblyopia can be cured. For best results, treatment should begin before age 5; treatment for amblyopia is rarely successful if initiated past age 10. At least half of all patients with amblyopia also have strabismus, a misalignment of the two eyes.

The pediatrician or family physician will most likely be the first to see a young patient with amblyopia or strabismus and, therefore, will have the principal responsibility for screening. The child's physician must be familiar with the different kinds of amblyopia and strabismus, the close relationship of these two conditions, and how best to detect them.

Basic Information

Vision is a developmental sensory function. Vision at birth is relatively poor, but through proper visual stimulation in the early months and years of life, a normal acuity is achieved at approximately **3** years of age. If this developmental process—the stimulation of the vision-receptive cells in the brain—is prevented because of strabismus, abnormal refractive error, congenital cataract, or some other condition, vision will not develop properly. This is a failure of the developmental process, not primarily an organic abnormality of the eye.

Amblyopia

Amblyopia results from a disruption of the normal development of vision, which distinguishes it from vision loss resulting directly from organic ocular defects, such as cataract, retinoblastoma (a life-threatening tumor of early childhood), and other inflammatory and congenital ocular disorders. It is usually unilateral, but it can (rarely) affect both eyes. Amblyopia does not cause learning disorders.

Amblyopia may develop in young children who receive visual information from one eye that is blurred or conflicts with information from the other eye. To understand how amblyopia may develop in this way, consider that the brain is receiving two stimuli for each visual event: one from a visually aligned (fixating) eye and one from an "abnormal" eye (vision blurred or eye misaligned on another target). The child's brain selects the better image and suppresses the blurred or conflicting image, which results in the faulty development of vision in the amblyopic eye. In other words, the brain continually "favors" the eye with better vision, to the eventual detriment of visual development in the other eye. For this reason, amblyopia is often referred to colloquially as "lazy eye."

A number of predisposing factors can lead to the development of amblyopia. These are summarized below.

Strabismic Amblyopia

A child can develop amblyopia in the context of strabismus (misaligned eyes). An adult onset of strabismus generally will cause diplopia (double vision) because the two eyes are not aligned on the same object. The brain of a child, on the other hand, is more adaptive. In a similar strabismic situation, the child's brain ignores (suppresses) the image from one of the eyes—usually the one that provides the blurrier image. Although such an adaptation overcomes the troublesome symptom of diplopia, this cortical suppression of sensory input from one eye may interrupt the normal development of vision in the higher centers of the brain; this interruption may result in reduced vision, which is amblyopia.

Sometimes the degree of misalignment between the two eyes is very slight, making detection of strabismus and suspicion of strabismic amblyopia difficult. Even with a small angle of strabismus, amblyopia may be quite dense.

Refractive Amblyopia

Amblyopia can result from a difference in refractive error between the two eyes. The eye with the lesser refractive error provides the clearer image

5. Touch the lower part of the sternum and feel it and the rib cage as funny, happy, laughing bones. Feel the Chi and electricity penetrate into the bones and spread out to the rib cage. Touch the lower part of the sternum. Give the same command again. “Produce healthy white and red cells”. After that you put your mind into the Tan Tien and universe so that the Chi can charge into the bones.

You have finished activating the defense system.



Fig. 4.75
A. *“Humerus bones produce healthy white and red blood cells”.*
B. *Tan Tien and the Universe.*
C. “*Lower sternum produce healthy white and red blood cells”.*

Immune System

1. The Immune System starts with the top part of the sternum. Touch the top part of the sternum. Project your fingers ‘very long’ into the bone and feel them penetrate right into the thymus. Activate the thymus gland. Gradually, feel the fingers rising up to the thyroid and parathyroid. Activate the thyroid and parathyroid and throat center. Give the command, “Clear ,clean and bright fill with violet light and return to normal function”.



Fig. 4.76 *Touch the Top of the Sternum & activate the Thymus, Thyroid and Parathyroid Glands.*

and usually is favored over the other eye; suppression occurs and amblyopia develops. Children with asymmetric hyperopia are susceptible, because unequal accommodation is impossible; the child can bring only one eye at a time into focus. Refractive amblyopia may be as severe as that found in strabismic amblyopia. However, the pediatrician or family physician may overlook the possibility of amblyopia because there is no obvious strabismus. Detection of amblyopia must be based on an abnormality found in visual acuity testing.

Form-Deprivation and Occlusion Amblyopia

Form-deprivation amblyopia (amblyopia ex anopsia) can result when opacities of the ocular media, such as cataracts or corneal scarring, prevent adequate sensory input **and,** thus, disrupt visual development. The amblyopia can persist even when the cause of the media opacity is removed. Rarely, occlusion amblyopia can result from patching of the normal eye.

Strabismus

Strabismus is a misalignment of the two eyes, so that both eyes cannot be directed toward the object of regard. Strabismus may cause or be caused by the absence of binocular vision; as with amblyopia, strabismus does not cause learning disabilities.

It is clinically useful to distinguish between concomitant (nonparalytic) and incomitant (paralytic or restrictive) strabismus. Additionally, a number of terms are used to describe and classify strabismus. These distinctions and terms are summarized below.

Concomitant Strabismus

Strabismus is called *concomitant* or *nonparalytic* when the angle (or degree) of misalignment is approximately equal in all directions of gaze (Slide 53). The individual extraocular muscles are functioning normally, but the two eyes are simply not directed toward the same target. Most concomitant



Slide 53 Concomitant strabismus. In the three views presented here, the misaligned eyes exhibit approximately the same degree of inward deviation (esotropia) in each position of gaze.

strabismus has its onset in childhood. In children, it often causes the *secondary* development of suppression to overcome double vision and thus leads to strabismic amblyopia. Concomitant strabismus in patients under age 6 is rarely caused by serious neurologic disease. Strabismus arising later in life may have a specific and serious neurologic basis. Concomitant strabismus may occur in an adult who loses most or all of the vision in one eye from intraocular or optic nerve disease. A blind eye in an adult will frequently drift outward, while in a child the eye will turn inward.

Incomitant Strabismus

Strabismus is called incomitant, paralytic, or restrictive when the degree of misalignment varies with the direction of gaze (Slide 54). One or more of the extraocular muscles or nerves may not be functioning properly or normal movement may be mechanically restricted. This type of strabismus may well indicate either a serious neurologic disorder, such as third cranial nerve paresis (see Chapter 7), or an orbital disease or trauma, such as the restrictive ophthalmopathy of thyroid disease or a blowout fracture.

Heterophoria and Heterotropia

Heterophoria is a latent tendency for misalignment of the two eyes that becomes manifest only if binocular vision is interrupted, such as by covering one eye. During binocular viewing, the two eyes of a patient with heterophoria are aligned perfectly; both eyes are directed at the same object of regard. However, when one eye is covered, that eye will drift to its position of rest. Once the cover is removed, the eye will realign itself with the other eye. A minor degree of heterophoria is normal for most individuals.

Heterotropia is really another term for strabismus. In general, tropia refers to a manifest deviation that is present when both eyes are open (no covers). Usually binocular vision is reduced. Some patients, however, can demonstrate an intermittent heterotropia and thus achieve binocular vision part of the time.



Slide 54 Incomitant strabismus. The eyes appear straight in right gaze (top) and straight-ahead gaze (middle), but a misalignment is obvious in left gaze (bottom), indicating a paralysis of the left lateral rectus muscle or a restriction of the left medial rectus. These eye positions would be found in a left sixth cranial nerve palsy.

Heterotropia and heterophoria can be subdivided further according to the direction of the deviation involved. In esotropia and esophoria, the deviating eye is directed inward toward the nose. Esotropia is a manifest deviation and is the most common type of deviation in childhood. Exotropia is much more likely to be intermittent than esotropia, with an outward deviation of an eye alternating with alignment of the eyes. Children with this condition suppress double vision when the deviating eye is turned out and achieve some degree of binocular vision when the two eyes are straight. Vertical heterotropias and heterophorias have many different causes, including paralysis or dysfunction of vertically acting extraocular muscles. When vertical deviations are described, the deviating eye (right or left) should be specified. Table 6.1 summarizes the directions of deviation in heterophoria and heterotropia. Figure 6.1 depicts the different kinds of heterotropia.

How to Examine and Interpret the Findings

Pediatric vision screening is important for detecting not only amblyopia and strabismus but also congenital cataract, glaucoma, retinoblastoma, and other vision- or life-threatening conditions. Regular screening by the pediatrician or family physician helps ensure that the child's vision is developing normally or, if it is not, that early treatment is instituted. At a minimum, all children should undergo an evaluation to detect eye and vision abnormalities during the first few months of life and again at about **3** years.

Visual acuity testing is important for detecting amblyopia as well as refractive error, which can lead to amblyopia in young children. Strabismus may be detected by general inspection, the corneal light reflex test, or the cover test. Additional tests are important for general eye screening in children of all ages: pupillary reactions are important in assessing normal eye function and health; direct ophthalmoscopy is required to detect media opacities by eliciting a red reflex and to examine the fundus for retinal abnormalities. These techniques are discussed later in the chapter.

Table 6.1 Summary of Heterophoria and Heterotropia

Prefix	**Name** of Disorder		Description
	-phoria (latent)	-tropia (manifest)	
eso-	esophoria	esotropia	inward deviation
exo-	exophoria	exotropia	outward deviation
hyper-	hyperphoria	hypertropia	upward deviation
hypo-	hypophoria	hypotropia	downward deviation



Figure 6.1 Types of heterotropia. Note the corneal light reflex. (**A**) Esotropia (inward). (**B**) Exotropia (outward). (**C**) Hypertropia (upward). (**D**) Hypotropia (downward).

Amblyopia Testing

Amblyopia can be detected by testing the visual acuity in each eye separately. Although there is no specific Mendelian pattern of inheritance, strabismus and amblyopia cluster in families. Restoration of normal visual acuity can be successful only if treatment is instituted during the first decade of life, when the visual system is still in the formative stage. Techniques for measuring or estimating visual acuity (or visual function) and detecting amblyopia vary with the child's age, as described below.

Newborns

True visual acuity cannot be measured in newborns. However, infants' general ocular status should be assessed through corneal light reflex testing, evaluation of the red reflex, pupillary testing, and, if possible, fundus examination.

Infants to 2-Year-Olds

With infants, it is possible only to assess visual function, not visual acuity. To test for amblyopia in infants (from a few months to about 2 years old), cover each eye in turn with the hand or, preferably, an adhesive patch and note how the child reacts. The infant should be able to maintain central fixation with each eye. If amblyopia is present, the child will likely protest—vocally or by evasive movements—the covering of the "good" eye. Visual function, including ocular motility, may be further assessed by passing an interesting object, such as a ring of keys, before the baby and noting how the infant watches and follows the moving object. Moving the child's head can be used to demonstrate full ocular motility if not otherwise documented by following movements.

Age 2 to 4 or 5

A picture card (Figure *6.2)* may be used to test visual acuity in children between 2 and *3* years old. At age *3* (or before, if the child can follow directions and communicate adequately), visual acuity should be tested with the tumbling E chart (Figure *6.3).* Use of an adhesive patch is the best way to ensure full monocular occlusion and accurate acuity measurement in children at these ages.

Vision should be rechecked annually once visual acuity has been determined to be normal in each eye. Young children may not quite reach 20/20 acuity; this is no cause for concern as long as vision is at least 20/40 and both eyes are equal.

Age 4 or 5 and Up

The Snellen chart may be used to test visual acuity in children aged 4 or 5 and up who know the letters of the alphabet (see Chapter 1). A recent



Figure 6.2 Picture card. This figure shows one type of picture card used to test visual acuity in young children. To use the picture card, the examiner familiarizes the child with the pictures at close range. Each eye is then tested individually at a testing distance of 6 meters (20 feet) from the child by asking the child to name the various objects.



Figure 6.3 Tumbling E chart. Visual acuity testing in children should be done at 6 meters (20 feet) with charts such as the tumbling E shown here. The child indicates the direction of the "arms" of the E by pointing with his or her fingers.



Slide 55 Epicanthus. An extended lid fold and a relatively flat nose bridge may give the false appearance of an esotropia.

advance in early detection of amblyogenic factors is photoscreening. A computerized camera takes a photograph of the child's undilated eyes. Refractive errors, strabismus, anisometropia, and media opacities are visible in the photos. This technique permits screening of preverbal children and those unable to cooperate with other types of testing.

Strabismus Testing

Strabismus testing for children (and adults) consists of general inspection, the corneal light reflex test, and the cover test, all described below.

Children up to 3 or 4 months old may exhibit temporary uncoordinated eye movements and intermittent strabismus. However, if occasional deviation persists beyond this age, a referral to an ophthalmologist should be made. Constant deviations should be referred at any age.

Epicanthus (Slide 55), in which epicanthal skin folds extend toward the upper eyelid and brow and the nose bridge is flat, may give an infant the appearance of esotropia, especially if the head or eyes are turned slightly to the right or left. As the child's head grows and the nose bridge develops, the epicanthus becomes less obvious. This may be mistakenly interpreted as the child outgrowing presumed strabismus; however, a child does not outgrow a true strabismus. The cover test and evaluation of the corneal light reflex will distinguish between pseudostrabismus (epicanthus) and true strabismus. However, it is important to keep in mind that strabismus can also occur in the presence of epicanthus.

General Inspection

For infants and older children, a general inspection may reveal an identifiable deviation of one eye. Having the patient look in the six cardinal positions of gaze may reveal whether the deviation is approximately the same in all fields—indicating concomitant strabismus—or is significantly different in one field of gaze—indicating a possible incornitant strabismus. Involuntary eye jerks known as *nystagmus* may be detected in primary or other fields of gaze. The patient may assume an abnormal head posture (ie, a tilt or turn to one side) to reduce the nystagmus and improve the visual



Figure 6.4 Corneal light reflex. The position of the light reflection indicates **(A)** a normal alignment, **(B)** a small esotropia, **(C)** a moderate esotropia, and **(D)** a large left esotropia.

acuity or to obtain binocular vision in cases of congenital cranial-nerve palsy. All infants or children with nystagmus should be examined and followed up by an ophthalmologist.

Corneal Light Reflex

Observation of the corneal light reflex constitutes an objective assessment of ocular alignment. Certainly in newborns and often in young children, it may be the only feasible method of testing for strabismus.

The patient is directed to look at a penlight held directly in front of the eyes by the examiner at a distance of 2 feet. The examiner aligns his or her eye with the light source and compares the position of the light as reflected by the cornea of each eye (Figure 6.4). Normally, the light is reflected on each cornea symmetrically and in the same position relative to the pupil and visual axis of each eye. In a deviating eye, the light reflection will be eccentrically positioned and in a direction opposite to that of the deviation. The size of the deviation can be estimated by the amount of displacement of the light reflex, but this is a relatively gross estimate.

Cover Test

The cover test (Figure 6.5) is easy to perform, requires no special equipment, and detects almost every case of tropia. It can be used on any patient over the age of 6 or **7** months. To perform the test, have the patient look at a fixation point, such as a detailed or interesting target (eg, a toy) or the Snellen chart. Note which eye seems to be the fixating eye. Cover the fixating eye and observe the other eye. If the uncovered eye moves to pick up



Figure 6.5 Cover test. The cover test can be used to screen for strabismus. The results depicted here indicate a right esotropia. When the left eye is covered, the right eye moves outward to pick up fixation. (When the left eye is uncovered, the left eye moves outward to pick up fixation and both eyes assume their original positions.)

the fixation, then it can be reasoned that this eye was not directed toward the object of regard originally (ie, when both eyes were uncovered). If the eye moves inward to fixate, then originally it must have been deviated outward and hence is exotropic. If the eye moves outward to fixate, then it was deviated inward and is esotropic. If the eye moves up or down, then it is hypotropic or hypertropic, respectively; the deviating eye must be specified in a hypertropia or hypotropia. Of course, each eye must be tested separately because there is no way of knowing which eye may be expressing the deviation.

No shift on cover testing means there is no tropia, but a phoria could still be present. A phoria is detected by alternate cover testing. Each eye is alternately occluded and the examiner observes the uncovered eye for a refixation shift. The patient has an esophoria if the uncovered eye moves outward to fixate, and an exophoria if the eye moves inward to fixate.

A very small-angle deviation (Slide 56) may be difficult to detect by evaluating the corneal light reflex or performing the cover test. For this reason, visual acuity testing is important in all cases of suspected strabismus for detection of amblyopia.

Other Tests

The following tests are part of general screening for all children.

Red Reflex

Light is reflected off the fundus as red when it is examined through the ophthalmoscope from a distance of about 1 foot (the red reflex; see Slide 1 in Chapter 1). Media opacities appear in the red reflex as black silhouettes (see Slide 17 in Chapter 3). Leukocoria ("white pupil"), is a white reflex that may sigrufy the presence of cataract or retinoblastoma (Slide 57).

All infants and children should be evaluated for the red reflex; pupillary dilation may be necessary to achieve a red reflex (phenylephrine 1.0% and cyclopentolate 0.2% in infants, readily available in combination as Cyclomydril). If the examiner cannot elicit a red reflex, the infant or child should be referred to an ophthalmologist urgently.



Slide 56 Small-angle right esotropia. The corneal light reflex in the right eye is displaced very slightly to the temporal aspect of the pupil.



Slide 57 Leukocoria. A cataract is not the only cause of a white reflex. In this child, a retinoblastoma fills the vitreous cavity. Any change from the normal red reflex warrants careful ophthalmic examination.

Ophthalmoscopy

A careful ophthalmoscopic examination of both eyes through dilated pupils is mandatory for any patient with reduced vision or with strabismus. In this way, the examiner can detect potentially serious intraocular lesions, such as cataract, malignancies such as retinoblastoma, or other abnormalities.

Pupillary Testing

Abnormal pupillary responses may indicate neurologic disease or other ocular defects. Pupillary testing is discussed in Chapter 1; further discussion and specific techniques appear in Chapter 7.

Management or Referral

The early detection of amblyopia and strabismus is an important responsibility for those involved in infant and child health care. Delayed diagnosis may have serious consequences for visual acuity, eye disease, or systemic disease. If an abnormality is suspected, the patient should be referred promptly to an ophthalmologist.

Amblyopia

In children younger than 5, strabismic amblyopia can usually be treated effectively by the ophthalmologist through occlusion of the unaffected eye. The child wears an adhesive patch over the good eye, forcing the brain to utilize the previously suppressed eye. In general, the success of occlusion treatment for amblyopia patients between the ages of 5 and 9 will depend on the age of the patient, the degree of the amblyopia, and the persistence of patient compliance with treatment. Treatment is better tolerated by younger children but can be successful in children as old as 10. A treatment

2. Move the fingers to touch both sides of the jaw bones to help activate the tonsils, the body's first line of defense. The jaw bone affects the lymph nodes beneath, which include the tonsils. Fill them with Chi. Give the command, "Clear, clean and bright; fill with violet light and return to normal function".


Jaws control Tonsils.

Fig. 4.77 *Activate the Tonsils and Jaw Bones.*

3. Touch the mideyebrow and crown, which control the pituitary and pineal glands respectively. Touch the third eye, feeling it open and feel the light from heaven entering into your brain and into your body. Touch the crown. Feel your fingers reaching deep inside and feel the Chi penetrating all the way down to your perineum. Give the command, "Clear, clean and bright fill with violet light and return to normal function".


Crown
Third Eye
Mideyebrow controls all the Glands and the Energy Center.

Fig. 4.78 *Third Eye, Mideyebrow and the Crown affects the Immunity and Defense Systems.*

4. Rub both of your hands until they are warm and cross the hands on the neck and feel the lymphatic system has been activated. Cross your arms and hold your hands

program started early in life often must be continued throughout the patient's first decade. Amblyopia treatment by patch occlusion of the unaffected eye must be monitored carefully, especially during the younger years, to avoid causing amblyopia through sensory deprivation of the occluded eye.

Treatment of refractive amblyopia consists first of wearing glasses, followed by patching of the better eye if the visual acuity difference persists after 4 to 8 weeks of wear. Equal vision in both eyes is readily achievable with parental cooperation. In general, the earlier the individual with amblyopia is diagnosed and treated, the better the chance of achieving equal vision.

Strabismus

The most effective way to support fusion (binocular vision) is to treat the amblyopia and equalize the vision. Glasses can treat some or all of the esotropia in a farsighted, or hyperopic, individual and may decrease the frequency of deviation in a myopic individual with exotropia. However, surgical correction of the misalignment may still be necessary, particularly in those children who develop esotropia before the age of 6 months (congenital esotropia). Even when binocular vision may not be achievable, the impact of a disfiguring strabismus on a patient's self-image is a valid indication for surgery. It must be stressed that surgery is not an alternative to glasses and patching when amblyopia is present.

Optometric "vision training" is rarely indicated for the treatment of amblyopia or strabismus.

Points to Remember

1. Amblyopia must be detected early to be treated successfully.
2. The importance of visual acuity testing in detecting amblyopia cannot be overemphasized. Amblyopia may be present in eyes without strabismus, so the vision in each eye may not be normal even if the eyes appear normally aligned.
3. Several serious organic conditions cause strabismus as one manifestation of the disease; therefore, all patients with strabismus should be referred to an ophthalmologist at the time of diagnosis for further testing.
4. Children may have cataracts, glaucoma, and retinal diseases, so children with unusually large eye(s), decreased or no red reflex, or poor vision should be referred to an ophthalmologist.

Sample Problems

1. A 3-year-old boy is brought to you by his mother, who tells you that she suspects his right eye is not straight. What steps would you take to determine if a significant problem is present?

Answer: Visual acuity testing should be attempted using the tumbling E chart or a picture card, with each eye alternately covered by an adhesive patch. A difference in visual acuity between the eyes or decreased vision in both eyes is significant.

Test the alignment of the eyes by evaluating the corneal light reflex. Then proceed to the cover test. Unequal positioning of the light reflex or movement of the uncovered eye to pick up the fixation would suggest a misalignment of the eyes.

Perform an ophthalmoscopic examination, preferably through dilated pupils, to determine if there is any intraocular basis for visual loss, such as cataract, retinoblastoma, or a retinal abnormality.

If visual acuity is asymmetric or if there is a suspicion of intraocular disease, the patient should be referred for an urgent ophthalmologic evaluation. If visual acuity and the fundus examination are normal but strabismus is suspected because of other examination findings or patient history, a nonurgent referral should be made.

2. A family has just moved into your area and the mother brings her 6-month-old baby to your family practice office for a routine checkup. She mentions that the child's grandfather has noted that in several photographs the baby's left eye appears crossed. He is adamant in his observation and feels that "something should be done." The mother has felt that, at times, the eye has appeared crossed, but the baby's father has not observed this phenomenon. How should you proceed?

   Answer: Inquire about any family history of strabismus or amblyopia and evaluate for the presence of epicanthus. Place your hand in front of one eye and then the other to see if the child exhibits displeasure. Observe the alignment of the child's eyes as well as extraocular movements if possible. Use a penlight to assess the position of the corneal light reflex.

   Examination reveals that significant lid folds are present. The corneal light reflex is the same in each eye, and full extraocular movements are seen in all cardinal fields of gaze. Although in this case the appearance of a crossed eye is probably the result of epicanthus, continued observation on the next visit is indicated. Remember that strabismus and amblyopia can occur in a patient with epicanthus, and the strabismus may be intermittent. Any suspected abnormality should be referred to an ophthalmologist.

3. A 2-year-old boy is brought to your office because his mother has noticed that over the past 2 weeks his right eye has deviated inward during periods of fatigue. On the previous evening, the boy's father claimed to have noted a white reflex in the child's right eye. How should you proceed?

   Answer: Show the child a toy and cover his left eye with your hand; evaluate his response. Cover his right eye to compare his response. Evaluate the corneal light reflex and perform the cover test. In particular, note whether an abnormal response is elicited on covering one eye.

Test the pupillary light reflexes. Perform an ophthalmoscopic examination, preferably through a dilated pupil, to assess the red reflex and observe for organic pathology.

Examination reveals equal pupillary light reflexes. A white reflex is noted on ophthalmoscopic examination of the right eye as compared with the left. No detail can be seen in the right fundus. Your findings indicate the need for an urgent referral. Following ophthalmologic consultation, the esotropia in this child was diagnosed as secondary to a retinoblastoma.

4. A 54-year-old man has early cataracts in both eyes. With glasses, the right eye cannot be corrected to better than 20/200, whereas with the left eye he can read the 20/40 line with best correction. The amount of cataract is exactly the same in each eye. Examination of the optic disc and macula, pupillary reaction, color vision, and retinal blood vessels proved entirely normal in each eye. However, the right eye appears to be turned slightly inward when you evaluate the corneal light reflex, and the patient has not experienced diplopia. Additional questioning reveals that the patient wore a patch over one eye as a child. Why would information concerning his childhood ocular condition be relevant in this situation?

   Answer: The poor vision in the right eye may be due to a long-standing amblyopia. If this is the case, an ophthalmologist will conclude that removal of the cataract would result in vision only as good as that during the adolescent years and surgery would probably not be recommended.

5. A 4-year-old boy with attention-deficit disorder comes to your office for his routine preschool physical examination. Your nurse tests his visual acuity with the picture card and obtains 20/30 vision on the right. During testing of the left eye the patient loses attention and refuses to cooperate further with testing. What course of action should you take?

   Answer: Often children become uncooperative with visual acuity testing due to poor vision in the eye being tested. This is sometimes misinterpreted as a behavioral rather than an ocular issue. This patient can return on another day to have the left eye tested first, with the right eye covered by an adhesive patch. If visual acuity measurement is still unsuccessful, the patient should be referred to an ophthalmologist for evaluation.

6. A 4-year-old girl is brought to your office by her mother, who says that she sees her daughter's right eye "drifting." You test the patient's vision, which is 20/20 in each eye. There is no epicanthus. The corneal light test shows no deviation, and the cover test fails to reveal strabismus. What is your next step?

   Answer: Strabismus can be intermittent. Intermittent esodeviations are usually early manifestations of a constant deviation and may be difficult to detect during the early stages. Intermittent exodeviations are more pronounced when the patient is tired or sick but can be easily missed. If the patient has a reliable history of strabismus but you are unable to detect the deviation, referral to an ophthalmologist is recommended.

7. A mother reports that her 1-year-old child is sensitive to light and his right eye looks larger than the left. On examination you note that although the child's right eye does look larger, the pupillary reactions are equal in both eyes, the corneas are clear, and there is a good red reflex in each eye. What should you tell the mother?

a. Do not worry, the child will "grow into" his eyes.
b. Return in 1 month for a reexamination.
c. Take the child to an ophthalmologist on my referral.
d. This is probably a cancer of the right eye, and you should take the child to an oncologist on my referral.

Answer: c. Children can have glaucoma, which causes buphthalmos, or enlargement of one or both eyes. Although glaucoma may be associated with increased tearing, sensitivity to light, and a hazy or white cornea, the only sign of glaucoma in some children may be enlargement of the eye or eyes. This child should be referred immediately to an ophthalmologist for diagnosis and management.

Annotated Resources

Gittinger JW Jr: *Ophthalmology: A Clinical Introduction.* Boston: Little, Brown & Co; 1984:131–149. Provides the reader with a concise overview of strabismus and amblyopia. A short section on the anatomy and function of the extraocular muscles is particularly good.

Newell FW: *Ophthalmology: Principles and Concepts.* 8th ed. St Louis: CV Mosby Co; 1996. Disorders of ocular motility are well covered. The short discussion of the development of amblyopia will be beneficial to the reader. Ocular muscle function and ocular motility are presented in different areas of the textbook. Provides a good overview.

Trobe JD: *The Physician's Guide to Eye Care.* San Francisco: American Academy of Ophthalmology; 1993. A brief but comprehensive resource covering the principal clinical ophthalmic problems that nonophthalmologist physicians are likely to encounter, organized for practical use by practitioners.

Vaughan DG, Asbury T, Riordan-Eva P: *General Ophthalmology.* 14th ed. Norwalk, CT: Appleton & Lange; 1995. The chapter on strabismus is a well-illustrated, comprehensive review of the subject.

Chapter 7

Neuro-Ophthalmology

Objectives

As a primary care physician, you should be able to perform a basic neuro-ophthalmic examination and to recognize and interpret the more common signs and symptoms of neuro-ophthalmic disorders.

To achieve these objectives, you should learn

- To measure visual acuity
- To examine pupillary reactions
- To test the function of the extraocular muscles
- To evaluate the visual fields
- To inspect the optic nerve head

Relevance

The visual pathways and the oculomotor system reflect much of the status of the nervous system as a whole. Approximately **35%** of the sensory fibers entering the brain are in the two optic nerves. It is estimated that 65% of intracranial diseases exhibit neuro-ophthalmic symptoms or signs. Routine neurovisual examination allows the primary care physician to identify abnormalities indicating life-threatening or vision-threatening neurologic disorders and other systemic diseases. Important examples are brain tumors, multiple sclerosis, cerebrovascular disease, giant-cell arteritis, and intracranial arterial aneurysms.

How to Examine

The neuro-ophthalmic survey may be simplified to the point where only a few minutes of the primary care physician's time are required, or a detailed neuro-ophthalmic examination may occupy many hours of an ophthalmologist's time and need to be substantiated by sophisticated procedures. This chapter will address routine tests and screening procedures.

Visual Acuity Testing

The first step in any eye examination is to measure visual acuity in each eye. The chief complaint of most patients with ocular problems is some aberration of vision. Measurement of visual acuity is an absolute necessity. Use of the conventional Snellen eye chart is currently the easiest and best method of measuring the function of the macular fibers, although any reading material may be useful for screening purposes. Both distance and near vision ideally should be measured and recorded using the patient's corrective lenses if available. (See Chapter 1 for performance instructions.)

Visual Field Testing

Evaluation of the visual fields should never be omitted from the basic eye examination. Gross confrontation field testing is an accepted screening procedure. Each eye must be tested separately. While fixing on the examiner's eye with the nonoccluded eye, the patient is asked to count fingers in each of the four quadrants of the visual field. (See Chapter 1 for a detailed description of confrontation field testing.)

Because most visual field defects affect central vision, attention should be paid to the area within the central 30". A method of screening for central field defects is to ask the patient to look at a piece of graph paper or an Amsler grid, which is similar but specific for this type of testing. (See Figure 3.4 in Chapter *3* for a depiction of the Amsler grid and further discussion on its use in central visual field testing.) Sometimes, use of a grid will demonstrate subtle bitemporal hernianopic field loss due to chiasmal compression or small homonymous field defects due to occipital lobe disease. An acceptable alternative method includes asking the patient to recognize a small, white pin head or similar object in all fields of vision. **A** red test object may also be valuable in evaluating patients with optic nerve or chiasmal disease.

Pupillary Reactions

Pupils should be inspected while the patient is looking at distance to avoid the pupillary constriction that occurs with a near target. Inspection of pupils in patients with dark-brown irides can be facilitated with a tangentially applied light. The pupils should be round and equal in diameter, although less than 1 millimeter of inequality may be a normal variation. Poor pupillary dilation in dim light may indicate dysfunction of the sympathetic nervous system, and poor pupillary constriction to bright light may indicate parasympathetic dysfunction. For schematic illustrations of the pupillary pathways and reflexes, see Figures 7.1 and 7.2.

The swinging-flashlight test is the most valuable clinical test for optic nerve dysfunction currently available to the general physician. The abnormality detected with this test is the afferent pupillary defect, also known as the Marcus Gunn pupil (see "Afferent Defect" in Figure 7.2). To perform



Pretectal nucleus
3rd cranial nerve nucleus
Edinger-Westphal nucleus (part of the 3rd cranial nerve nucleus)
Lateral geniculate body
3rd cranial nerve with parasympathetic fibers
Optic nerve
Ciliary ganglion
Afferent pathway
Efferent pathway
Right
Left
Light source

Figure 7.1 Pupillary pathways. The view shown is a cross-section. The dotted line represents the efferent pathway, and the solid line represents the afferent pathway. A light stimulating the left retina will generate impulses that travel up the left optic nerve and divide at the chiasm. Some impulses continue up the left tract; some cross and continue up the right tract. The impulses arrive at each pretectal nucleus and stimulate cells, which in turn send impulses down the third cranial nerve to each iris sphincter, causing each pupil to contract. It is because of the double decussation, the first in the chiasm and the second between the pretectal nuclei and the Edinger-Westphal nuclei, that the direct pupil response in the left eye equals the consensual response in the right eye.

this test, dim room illumination and a bright light are helpful. The patient maintains fixation on an object 15 feet or more away. The bright light is held directly in front of one eye for **3** to 5 seconds, moved rapidly across the bridge of the nose to the front of the other eye for ***3*** to 5 seconds, and then shifted back to the first eye. This procedure should be repeated several times until the examiner is certain of the responses. The critical observation to be made is the behavior of the pupil when it is first illuminated.



Figure 7.2 Pupillary reflexes. The orientation depicted is that of the examiner looking at the patient's eyes.
*Note normal constriction from consensual response.

A normal response is initial pupillary constriction followed by variable amounts of redilation. An abnormal response is slow dilation without initial constriction. The relative afferent pupillary defect almost always indicates a lesion in the optic nerve on the affected side, although rarely a large retinal lesion may produce this defect. Additional support for the diagnosis may be gained by asking the patient to compare the brightness of the light or the color of a red object between the two eyes. A patient with an optic neuropathy will usually say that the light does not appear as bright and that a red object appears faded with the eye that has an afferent pupillary defect.

Ocular Motility Testing

Eye movements should be tested, especially if the patient has a complaint of double vision or if any neurologic disease is suspected. First, alignment of the eyes should be assessed to identify a deviation that could be due to strabismus, extraocular muscle malfunction, or oculomotor nerve dysfunction. (See "Ocular Motility Testing" in Chapter 1 and "Strabismus Testing" in Chapter 6.) Ophthalmoplegia can be distinguished from nonparalytic strabismus by the presence of incomitancy. Rapid eye movements (saccades) are tested by asking the patient to direct the eyes quickly to a target that the examiner is holding right, left, up, and down. Tracking movements (pursuit) are tested by asking the patient to follow a slowly moving target first horizontally and then vertically. The examiner should be looking for the following abnormalities:

1. Strabismus
2. Limitation of movement of one eye
3. Limitation of gaze (both eyes affected similarly)
4. Nystagmus (spontaneous jerking eye movements)

Ophthalmoscopy

Evaluation of a patient with neurologic symptoms is not complete without evaluation of the ocular fundus. Particular attention should be given to the appearance of the optic disc. In some neuro-ophthalmic conditions, the optic disc may be swollen and elevated; in others, it may be pale and atrophic. The examiner should attempt to note the presence of spontaneous venous pulsations, indicating that the intracranial pressure is normal (not elevated).

How to Interpret the Findings

Pupillary Disorders

Disorders of pupillary function are among the most accurate of the localizing signs of neurologic disease. Ocular disease and the influence of systemic or local drugs on the pupils must be assessed before pupillary abnormalities can be considered neurologically significant. Some commonly encountered pupillary abnormalities are discussed below.

Dilated Pupil

A dilated pupil, especially one that does not react to light, usually indicates a lesion in the efferent limb of the pupillary reflex (see "Efferent Defect" in Figure 7.2). A dilated pupil in a patient with a head injury or a cloudy sensorium may indicate compression of the third cranial nerve (oculomotor nerve) by herniation of the temporal lobe and may have grave importance. A life-threatening aneurysm also can manifest with a dilated pupil, usually associated with a droopy lid and double vision. On the other hand, a dilated, fixed pupil in an otherwise asymptomatic, healthy patient is usually benign. In a healthy individual, a dilated pupil may reflect a benign lesion in the ciliary ganglion (an Adie's tonic pupil) or may be secondary to instillation of a dilating eyedrop or use of certain motion-sickness medications.

Tonic Pupil

The tonic pupil, known as *Adie's* pupil, is seen predominantly in young women and is usually unilateral. In ordinary light, the tonic pupil is usually larger than its counterpart; the reaction to light is either diminished or absent. Instillation of weak cholinergic agents (eg, 1/8% pilocarpine hydrochloride) will cause constriction of a tonic pupil, indicating denervation hypersensitivity, whereas this constriction will not occur in a normal pupil. By itself, a tonic pupil is of no neurologic significance.



Slide 58 Homer's syndrome. This acquired lesion of the cervical sympathetic chain has caused a mild ptosis of the right upper eyelid and a narrowing of the right pupil.

Unilateral Small Pupil

A small pupil in one eye that has normal reactivity to light and near stimuli is usually physiologic and is of no neurologic significance. However, when accompanied by ptosis of the upper eyelid, a small pupil may indicate Homer's syndrome (Slide 58). Homer's syndrome is caused by a congenital or an acquired lesion of the sympathetic pathways, either in the central or preganglionic portion from the hypothalamus to the superior cervical ganglion or in the postganglionic portion from the cervical ganglion to the eye (Figure 7.3). Carotid dissection, carotid aneurysm, and tumor are life-threatening lesions that can present with Horner's syndrome. Detection of Homer's syndrome can be accomplished through the topical instillation of 4% cocaine, which will dilate a normal pupil but not a desympathectomized pupil. Differentiation of preganglionic from postganglionic lesions is important and can usually be accomplished through the instillation of hydroxyamphetamine drops if available.

Argyll Robertson pupil is a small, irregular pupil that constricts to light poorly or not at all but constricts normally to convergence. Usually both pupils are involved. However, initial involvement may be unilateral or asymmetric. Because Argyll Robertson pupil is associated with tertiary syphilis, the patient should be evaluated for syphilis with RPR or WRL and FTA-ABS testing.

Neuromotility Disorders

Some significant oculomotor disorders that the primary care physician should recognize are discussed below. (It may be helpful to refer to Figure 1.3, which illustrates the extraocular muscles.)

Evaluation of the patient whose complaint is double vision must include a thorough, neurologically oriented history. True diplopia—which means that two separate, equally bright images are visualized, with one of the images disappearing when one eye is closed—signifies strabismus

under your armpits. Picture the lymphatic system of the armpits as you activate the lymph nodes. Give the command; "Clear, clean and bright fill with violet light and return to normal function". The lymphatic system of the upper body is clear, clean and bright and the lymphatic fluid flows! Smile.



Fig. 4.79 *Lymphatic System of the Neck and Armpits are clear, clean and bright.*

5. Move the hands to the cover the groin area. Give the command to the lymph nodes there. Next, cover the lymph nodes of the navel area, and give the command; "Clear, clean and bright fill with violet light and return to normal function". The groin and the navel area lymph nodes become clear, clean and bright.


Tonsil
Neck Lymph Nodes
Thymus
Armpit Lymph Nodes
Navel Area
Lymph Nodes
Groin Area
Lymph Nodes



Fig. 4.80
Activate the Lymph Nodes in the Groin.


Hypothalamus
to Müller's muscle
Abducens nerve
Long ciliary nerve
3rd-order neuron
Superior cervical ganglion
To face and to sweat glands
1st-order neuron
2nd-order neuron
Subclavian artery
Ciliospinal center of Budge
Lung

Figure 7.3 Anatomy of sympathetic pathway. Shown are pathways of first-order central neuron (solid line), second-order intermediate neuron (dashed line), and third-order neuron (dotted line). Note the proximity of pulmonary apex to sympathetic chain, as well as the relationship of the intracavernous sympathetic fibers to the abducens nerve. (Illustration by Christine Gralapp.)

acquired after the age of 7 or 8 years. Patients sometimes say they have double vision when they mean they have blurred vision of one eye; for example, aberration due to corneal disease, cataract, or strands of mucus in the tear film. It is important to note in the history whether the diplopia is transient or persistent; sudden or gradual in onset; horizontal, vertical, or diagonal; and the same or different in various positions of gaze.



Slide 59 Third-nerve palsy. Lids are manually elevated in the middle and lower photos. Middle photo shows patient's attempt to look straight ahead; lower photo shows patient's attempt to look left. (Reprinted by permission from Miller NR, ed: Walsh & *Hoyt's Clinical Neuro-Ophthalmology,* 4th ed, Vol 2. Baltimore: Williams & Wilkins; 1985.)

Third Cranial Nerve Paresis

Cranial nerve III (oculomotor nerve) supplies the levator palpebrae muscle of the upper eyelid, the superior rectus, medial rectus, inferior rectus, and inferior oblique muscles, as well as the parasympathetic fibers to the sphincter of the iris. Complete paralysis of the oculomotor nerve produces both horizontal and vertical diplopia, with ptosis of the upper eyelid and an inability to rotate the eye inward, upward, or downward (Slides 59 and 60). The pupil may be dilated and nonresponsive. The most common causes of isolated third-nerve palsy include intracranial aneurysm (especially of the posterior communicating artery), vaso-occlusive disease within the nerve (usually associated with diabetes and hypertension), trauma, and brain tumor.



Slide 60 Third-nerve palsy. Lids are manually elevated in all photos. From top, patient's attempt to look right, up, and down. (Reprinted by permission from Miller NR, ed: *Walsh & Hoyt's Clinical Neuro-Ophthalmology,* 4th ed, Vol 2. Baltimore: Williams & Wilkins; 1985.)

Fourth Cranial Nerve Paresis

Cranial nerve IV (trochlear nerve) innervates the superior oblique muscle so that complete paralysis causes vertical diplopia. The patient often notices more difficulty in downgaze and may tilt the head toward the opposite shoulder to minimize the diplopia. The most frequent cause of



Slide 61 Sixth cranial nerve paresis. Shown here is an impairment of abduction of the right eye on right gaze.

isolated fourth-nerve palsy is closed-head trauma, but the condition is also found in patients with small-vessel disease, especially associated with hypertension or diabetes.

Sixth Cranial Nerve Paresis

Cranial nerve VI (abducens nerve) supplies the lateral rectus muscle; therefore, complete paralysis produces loss of abduction and horizontal diplopia, with the greatest separation of images in gaze directed toward the affected side (Slide 61). Intracranial tumors account for approximately 30% of cases of isolated sixth-nerve paralysis. Head trauma, small-vessel disease, viral infections, and increased intracranial pressure are also frequent causes of abducens paresis.

Other Cranial Nerve Palsies

Cranial nerve V is assessed by checking corneal sensation and bilateral facial sensation on the forehead, cheek, and chin. To reveal weakness of cranial nerve VII, ask the patient to smile and then to squeeze the eyes tightly shut, while you attempt to open the patient's eyes. To check cranial nerve VIII, ask the patient if he or she can hear the noise made as you rub your thumb and index fingertips together next to the patient's ear.

Myasthenia Gravis

Myasthenia gravis is a chronic autoimmune condition that interferes with neuromuscular transmission in skeletal muscles. The disease can affect any muscles, but ptosis and double vision are the presenting signs in about half the patients. Characterized by fatigability of muscle function on sustained effort, myasthenia gravis may mimic nearly any other oculomotor problem, including third-, fourth-, and sixth-nerve disease, gaze paresis, and internuclear ophthalmoplegia. Myasthenia gravis does not affect the pupil. All patients with unexplained diplopia or ptosis should have an edrophonium chloride (Tensilon) test.



Figure 7.4 Internuclear ophthalmoplegia. Information travels from the sixth-nerve nucleus (VI) to the ipsilateral lateral rectus muscle (LR) and, via the medial longitudinal fasciculus (MLF), to the contralateral third-nerve nucleus (III) and on to the contralateral medial rectus (MR) to make both eyes turn to the side of the stimulating sixth-nerve nucleus. A lesion blocking the path between the ipsilateral sixth-nerve nucleus and the contralateral third-nerve nucleus results in an internuclear ophthalmoplegia.

Internuclear Ophthalmoplegia

Lesions of the medial longitudinal fasciculus, which carries input from the ipsilateral sixth-nerve nucleus to the contralateral third-nerve medial rectus subnucleus, are usually of considerable diagnostic significance (Figure 7.4). The clinical manifestations of such a lesion include straight eyes in primary gaze but weakness of the adducting eye and nystagmus of the abducting eye in lateral gaze (Slide 62). It may be unilateral or bilateral, and convergence is usually intact. In older individuals, unilateral internuclear ophthalmoplegia suggests small-vessel disease within the distribution of the vertebral-basilar arterial system. In young adults, bilateral internuclear ophthalmoplegia is almost always due to demyelinating disease. In children, however, internuclear ophthalmoplegia may be due to a pontine glioma.

Nystagmus

Spontaneous, rhythmic, back-and-forth movement of one or both eyes is referred to as *nystagmus* (see "General Inspection" in Chapter 6). The direction may be horizontal, vertical, rotary, or a combination.

The three most common forms of nystagmus are benign and do not indicate central nervous system dysfunction. The first form of benign nystagmus occurs in end-gaze, when the patient is attempting to maintain the eyes in extremes of lateral gaze. In this position, it is not unusual for the eyes to drift back slightly from the extreme horizontal gaze position and then refixate with a small jerk movement. End-point nystagmus is usually not well sustained and disappears as the patient is permitted to move the



Slide 62 Unilateral right internuclear ophthalmoplegia. This 32-year-old patient with multiple sclerosis is unable to adduct the right eye on left horizontal gaze (bottom). The eyes are straight in primary gaze (middle), differentiating this condition from medial rectus underaction of intrinsic muscle or third-nerve origin.

(Reprinted by permission from Miller NR, ed: *Walsh & Hoyt's Clinical Neuro-Ophthalmology, 4th* ed. Vol 2. Baltimore: Williams & Wilkins; 1985.)

gaze slightly away from the extreme position. The second form of benign nystagmus is induced by drugs: diphenylhydantoin, barbiturates, and other sedatives. In this form, a jerk nystagmus may be present in all positions of gaze. The third form, a searching, pendular nystagmus, is commonly seen in individuals who are visually impaired from birth.

Nystagmus may indicate central nervous system dysfunction. Representative diseases that cause nystagmus are multiple sclerosis, brain tumor, and degeneration of the central nervous system.

Optic Nerve Disease

Many disorders of the anterior visual pathways are accompanied by abnormalities of the optic nerve head. These include swelling due to infiltration or inflammation or ischemia of the anterior optic nerve head and atrophy usually due to damage from various disorders.

Optic Disc Elevation

Congenital Anomalous Disc Elevation Occurring in slightly less than 1% of the population, congenital anomalous disc elevation is a benign, nonprogressive condition. The optic disc margins are blurred, the disc substance is elevated, and the optic cup is absent. However, there is no evidence of edema or hemorrhage, and often spontaneous venous pulsation can be observed. Congenital disc elevation may be associated with hyperopia and may be accompanied by the accumulation of calcified protein within the optic disc itself (optic disc drusen). Because of its deceptive appearance, congenital fullness of the optic nerve has been referred to as *pseudopapilledema* (Slide **63,** left). The condition should not be confused



Slide 63 Pseudopapilledema and true papilledema. On the left, pseudopapilledema from optic nerve drusen is shown; note several discrete drusen on the superior edge of the disc. On the right, true papilledema is shown; note congested capillaries and swollen nerve bundles.

with true, acquired papilledema (Slide 63, right). Such differentiation may be difficult, and the diagnosis of true papilledema sometimes cannot be made without lumbar puncture, once intracranial mass has been ruled out by MRI with and without gadolinium.

Papilledema One of the most important ophthalmoscopic findings is papilledema; swelling of the optic disc secondary to increased intracranial pressure occurs in approximately 50% of patients with a brain tumor. Characteristics of fully developed papilledema include hyperemia of the disc, tortuosity of the veins and capillaries, blurring and elevation of the margins of the disc, and hemorrhages on and surrounding the nerve head. The signs of early papilledema may not be distinct, with subtle elevation of the disc margins, loss of previously identified spontaneous venous pulsations, and mild hyperemia. In addition to intracranial mass lesions, papilledema may be seen in pseudotumor cerebri and in severe acute systemic hypertension. The first step in evaluating papilledema is to measure the blood pressure.

Papillitis Inflammatory edema of the disc, known as papillitis or *anterior* optic neuritis, may be indistinguishable from papilledema by its ophthalmoscopic appearance. (For a comparison of papillitis and papilledema, see Slides 10 and 11 in Chapter 2.) Whereas papillitis is more commonly unilateral and associated with decreased visual acuity and impaired color vision, papilledema is usually bilateral and usually associated with good central vision.

Ischemic Optic Neuropathy Ischemic optic neuropathy presents as a pale, swollen disc, often accompanied by splinter hemorrhages and loss of visual acuity and visual field. The field loss with ischemic neuropathy is often altitudinal, that is, predominantly within the superior or inferior field.

Amaurosis Fugax

Amaurosis fugax is transient monocular visual loss due to arterial insufficiency. Patients over age 50 complaining of monocular visual loss lasting several minutes should be investigated for atheroma affecting the ipsilateral carotid circulation. Atheroma may be the source of emboli that



Slide 64 Optic atrophy. This disc is flat and totally white. The sharp margins and clear definition of the disc suggest a primary disturbance of the retinal ganglion cells or their axons, rather than an inflammatory cause at the disc.

transiently interrupt retinal blood flow. Evaluation of amaurosis fugax is complex, and patients should be referred to an ophthalmologist, neurologist, or vascular surgeon for further workup.

Optic Atrophy

Optic atrophy (Slide 64), or pallor of the optic disc, results from damage to the nerve fiber layer of the retina, the optic nerve itself, the optic chiasm, or the optic tracts. With progressive loss of axons and alteration in glial tissue, the optic disc becomes pale. After extensive damage, the disc may become white.

There is a wide range of normal coloration of the disc. A diagnosis of optic atrophy should not be made unless there is decreased visual acuity or visual field loss accompanying the paleness of the optic disc or, if unilateral, a relative afferent pupillary defect. Common causes of optic atrophy include

- Previous optic neuritis or long-standing papilledema
- Compression of the optic nerve by a mass lesion, such as a meningioma, or pituitary adenoma
- Ischemic damage to the optic nerve due to small-vessel disease or giant-cell arteritis
- Glaucoma (see Chapter 3)

Visual Field Defects

The following terms are commonly used to discuss visual field loss:

- Scotoma An area of reduced or absent vision within an otherwise intact visual field.
- Hemianopia Loss of half the visual field. Usually, this involves loss of either the right or the left half of the visual field in either eye; however, the term *altitudinal* **hemianopia** may be used to distinguish loss of the superior or inferior half of the visual field.
- Homonymous hemianopia Loss of either the right or the left half of the visual field in both eyes.
- Bitemporal hemianopia Loss of the right half of the visual field in the right eye and loss of the left half of the visual field in the left eye.

Lesions anywhere in the visual system, from the retina to the occipital lobes, will produce visual field defects (Figure 7.5). Although detection and analysis of these visual field defects have led to entire texts written on the science of perimetry, most physicians need be concerned with only a few types of visual field loss. Neurologically significant field defects are most often central scotomas (due to optic nerve lesions), bitemporal field defects (due to chiasmal disease), or homonymous visual field defects (due to retrochiasmal damage to the optic tracts, the radiations, or the occipital cortex). In almost all locations, the effects produced are most profound within the central 30° of the visual field.

Isolated lesions anterior to the chiasm within the optic nerve produce visual field defects in one eye only. Optic nerve dysfunction typically produces a central scotoma, with accompanying reduction in visual acuity. Common causes of unilateral optic neuropathy include optic neuritis, optic nerve glioma, meningioma, and ischemic optic neuropathy.

Lesions in the optic chiasm produce visual field defects that affect both eyes, but in a dissimilar fashion. The most common example is a bitemporal hemianopia caused by pituitary adenoma. Another common visual field defect due to disease near the chiasm is loss of central field in one eye and a temporal visual field defect in the other eye.

Lesions affecting the visual pathways behind the chiasm produce homonymous hemianopias or homonymous defects that are less than a complete hemianopia. Because the fibers serving the corresponding portions of the two retinas lie increasingly closer together as the fibers pass back toward the occipital cortex, there is greater correspondence of the field defects in the two eyes as the lesions occur more posteriorly. Central visual acuity is not affected in homonymous hemianopias unless both hemispheres are involved. Stroke is the most common cause of a homonymous hemianopia. Middle cerebral artery occlusion tends to cause a complete hemianopia with other neurologic signs, whereas posterior cerebral artery occlusion causes isolated, congruous (identical) hemianopic scotomas.

Points to Remember

1. Testing of both visual acuity and visual fields is critical in the evaluation of the abnormal optic disc.
2. **A** patient with a unilateral optic nerve lesion should have equal pupils in ambient light, but a positive swinging-flashlight test.
3. A blurred disc margin is not diagnostic for papilledema. Other signs and symptoms must be considered.
4. Chiasmal disease is most likely to cause a bitemporal field defect.
5. If one of the following is abnormal—pupil, lid position, or ocular motility—look closely for involvement of the others.
6. Cranial nerves V and VII should be checked if ocular motility is abnormal and cranial nerve palsy is suspected.
7. Slowly progressive vision loss or cranial nerve palsy should prompt consideration of a compressive lesion, such as a tumor or aneurysm.


Visual Pathways
L
R
Temporal
Nasal
Nasal
Temporal
1
2
3
4
5
6
7
8
Optic radiations
Visual cortex in occipital lobes
Associated Field Defects
L
R
1
2
3
4
5
6
7
8

Figure 7.5 Visual pathways with associated field defects. For the visual pathways, the view shown is a cross-section seen from above. Note that objects in the right half of the visual field form images in the left half of each retina and are transmitted to the left hemisphere. The numbers correspond to lesions in the visual pathways and to the field defects that result from these interruptions. For the purposes of the diagram, the fields shown reflect the effects of total interruption of the indicated structures. In actuality, partial impairment is more the rule than the exception. The key at the top of the facing page indicates the site of each lesion and the associated field defect.

Figure 7.5 (continued)

Site of Lesion	Associated Field Defect
1 Optic nerve	Monocular loss of vision
2 Optic nerve merging with chiasm	Monocular loss of vision associated with contralateral impairment of temporal field
3 Optic chiasm	Bitemporal hemianopia
4 Optic tract	Total homonymous hemianopia (usually noncongruous if incomplete)
5 Temporal lobe	Upper homonymous hemianopia
6 Geniculate body	Rare total homonymous hemianopia
7 Parietal lobe	Lower homonymous quadrantanopia
8 Occipital lobe	Variety of homonymous hemianopias, ranging from total to small homonymous scotomas, depending on portion of lobe involved; high degree of congruity

Sample Problems

1. A 45-year-old woman comes to the emergency center because of severe left-sided headache and double vision that began the night before, immediately following vigorous exercise. As you examine her, she continues to complain of severe left-sided headache. Her neuro-ophthalmologic examination is normal, except that the left upper lid is ptotic; the left eye is deviated outward and fails to elevate, depress, or adduct normally; and the left pupil is dilated 3 mm more than the right and responds very poorly to light, both directly and consensually. What is your differential diagnosis? How would you proceed with evaluation and management?

Answer: The findings are those of a left third-nerve palsy with involvement of the pupil. The features of this case—including the age and gender of the patient, the suddenness of onset, the accompanying headache, and the fact that onset occurred in conjunction with vigorous exercise—are presented to raise the issue of a possible berry aneurysm of the circle of Willis. All of the preceding factors are commonly observed in acutely expanding aneurysms arising at the junction of the internal carotid and posterior communicating arteries. Such an aneurysm is the most common cause of third-nerve palsy with pupillary involvement. Even though the patient may have no symptoms other than headache and those symptoms caused by the third-nerve palsy, an aneurysm must be suspected. This is one of the true ophthalmic emergencies. The management in this case calls for an immediate neurosurgical consultation.

In this situation, the pupil was dilated. If the same patient appeared with exactly the same findings except for a normal left pupil, the diagnosis and management would be different. A pupil-sparing third-nerve palsy most likely is due to diabetes or some other microvascular obstruction causing ischemia of the core of the oculomotor nerve.

6. Place your palms over your navel and activate the lymph nodes. Give the command; "Clear, clean and bright fill with violet light and return to normal function". See them become clear, clean and bright. You have now activated the immune system.



Fig. 4.81
Touch and activate the Lymph Nodes in the Navel.

Summary - General Healing Session

This General Healing Session will help everybody.

A. Three Minds into One
B. Activate the Six Directions
C. Activate the Three Fires
D. Linking Personal Stars, Energy Bodies and the Universe
E. Protective Circle and Chi Field
F. Chi Water (Sacred Water) Practice
G. Empty and Fill
H. Clean with Green Light
I. Clean with Blue Light
J. Charge with Violet Light
K. Defense and Immune System

A. Three Minds into One

Smile to the inner universe, activate the heart compassion energy; feel the love and joy within. Smile and empty the mind and heart down into the Tan Tien. Fill the Tan Tien with Chi and spiral the energy. When the Tan Tien is full, the energy will rise up to fill the brain. Manifestation will occur at the mideyebrow.

B. Activate the Six Directions

Expand the awareness to connect to the Six Directions at the crown, mideyebrow, heart and Tan Tien.

Therefore, a pupil-sparing third-nerve palsy is not a neurosurgical emergency and the patient should be worked up for diabetes, giant-cell arteritis, syphilis, and other vascular disease. It is important to note that a third-nerve palsy can be considered pupil-sparing only if the palsy is complete and the pupil is totally normal.

2. A 25-year-old medical student suddenly complains of horizontal diplopia. Her eyes are straight when looking directly ahead, but when she attempts to look to the right or left, the adducting eye fails to move normally. However, when she is asked to look at the examiner's finger at a distance of 6 inches, both eyes converge normally. She also exhibits vertical nystagmus when she looks up. What is the neuro-anatomic localization of this problem? What is the etiologic diagnosis?

   Answer: The description is that of bilateral internuclear ophthalmoplegia. The medial longitudinal fasciculi conduct impulses to those third cranial nerve nuclei essential for participation in horizontal gaze movements. Acute, bilateral impairment of function of the medial longitudinal fasciculi occurring in this age group is typical of multiple sclerosis.

3. A 32-year-old female geologist has noticed slowly progressive blurring of vision for about a month. An optometrist changed her prescription, but the new glasses were of minimal benefit. After the symptom had been present for **3** months, she visited her family doctor, who found nothing wrong and referred her to a neurologist. The neurologist could find no abnormality and suggested she might be suffering from stress. She has now come to the emergency center because her vision has become distressingly blurred. You conduct a basic eye examination and find the following: visual acuity in the left eye is 20/60 and does not improve with a pinhole lens; the swinging-flashlight test discloses a left relative afferent pupillary defect; a confrontation visual field test suggests a temporal defect in the left eye only; and ophthalmoscopy reveals mild pallor of the left optic disc. What is the differential diagnosis? Is additional testing required at this time, or should the patient merely be observed further?

   Answer: The history of slowly progressive visual loss and the presence of a relative afferent pupillary defect are evidence of a left optic nerve lesion. Optic neuritis is a possibility, but it usually produces sudden onset of visual loss, with recovery after a few weeks or months. The history and the findings are strongly suggestive of a tumor compressing the left optic nerve. Detailed visual field testing will probably reveal a major field defect in the left eye and a normal field in the right eye. This localizes the lesion to the prechiasmal optic nerve, either in the orbit or in the brain. A CT scan or MRI with and without gadolinium would be the test to order next, with the expectation that it will show a meningioma or another kind of mass compressing the optic nerve.

4. A patient cannot see in the temporal visual field in either eye. Which one of the following findings is most likely to be associated with this defect?
   a. tilted optic discs
   b. pituitary tumor
   c. neurofibromatosis
   d. optic nerve toxicity
   e. infarction

   Answer: b. The fact that the field loss respects the vertical meridian in each eye localizes the pathology to the optic chiasm. Pituitary tumor is the most common cause of a chiasmal syndrome. Tilted optic discs can produce temporal field loss, but the defects would extend only up to the blind spot and not to the vertical meridian. Neurofibromatosis can be associated with chiasmal glioma, but pituitary tumor is a more common association. This is not the picture of optic nerve toxicity, which is typically characterized by bilateral central scotomas with intact peripheral fields. Infarction rarely occurs in the chiasm.

5. A 64-year-old woman reports progressive onset of ptosis and diplopia over an 8-month period. On examination, the left eye is normal but the right eye reveals 4 mm of ptosis, limitation of eye movement in all directions, a 4-mm pupil that does not react to light or dilate in darkness, and loss of corneal sensation. Which of the following is the most likely diagnosis?
   a. myasthenia gravis
   b. Graves' ophthalmopathy
   c. intracavernous meningioma
   d. aneurysm of the posterior communicating artery
   e. glioma of the right midbrain

   Answer: c. The patient's findings can best be explained by involvement of the third, sixth, fifth, and sympathetic nerves. Fourth-nerve involvement cannot be determined from the description. A middilated pupil that does not react to light or dilate in darkness usually indicates impairment of both the parasympathetic and the sympathetic innervation of the pupil. This finding as well as the other findings can best be explained by a lesion in the cavernous sinus. Meningioma and internal carotid artery aneurysm are the most common causes, particularly with a history of slow progression. Myasthenia gravis and Graves' ophthalmopathy would not produce the pupillary or sensory findings noted in this patient. An aneurysm of the posterior communicating artery could produce a third-nerve palsy but would not be expected to produce the other findings. A midbrain lesion typically produces bilateral ptosis, if any, and could not explain the sensory findings.

Annotated Resources

Glaser JS: *Neuro-ophthalmology.* 2nd ed. Philadelphia: JB Lippincott Co; 1990. This is an excellent, readable reference in neuro-ophthalmology, concise yet thorough. A new edition is due late in 1998.

Keltner JL, Wand M, Van Newkirk MR: *Techniques for the Basic Ocular Examination.* San Francisco: American Academy of Ophthalmology; 1989. This videotape covers visual acuity testing, ocular motility testing, confrontation field testing, glaucoma screening, and ophthalmoscopy.

Miller NR, Newman N: *Walsh & Hoyt's Clinical Neuro-Ophthalmology.* 5th ed. Baltimore: Williams & Wilkins; 1997. This multivolume set is the complete reference for clinical neuro-ophthalmology — the encyclopedia on the subject. Most importantly, it contains a thorough review of the literature.

Spalton DJ, Hitchins RA, Hunter PA: *Atlas of Clinical Ophthalmology.* St Louis: Mosby-Year Book; 1994. The neuro-ophthalmology section in this atlas is very good.

Trobe JD: *The Physician's Guide to Eye Care.* San Francisco: American Academy of Ophthalmology; 1993. A brief but comprehensive resource covering the principal clinical ophthalmic problems that nonophthalmologist physicians are likely to encounter, organized for practical use by practitioners.

Chapter 8

Ocular Manifestations of Systemic Disease

Objectives

As a primary care physician, you should be aware that most systemic diseases have ocular signs and symptoms and that serious ocular sequelae may result from these diseases. You should become familiar with the important features of several of these conditions, including diabetes mellitus, sickle cell anemia, hypertension, thyroid disease, sarcoidosis and inflammatory conditions, malignancy, acquired immunodeficiency syndrome, syphilis, and other systemic infections.

To achieve these objectives, you should learn

- To perform a thorough eye examination (see Chapter 1)
- To recognize the characteristic features, especially the ophthalmoscopic features, of these diseases
- To determine when it is appropriate to refer a patient to an ophthalmologist for consultation or treatment

Relevance

Recognition of the ocular signs, symptoms, and complications of many systemic diseases is vitally important for good medical practice. Diabetes mellitus affects nearly 16 million Americans and is the leading cause of new cases of blindness in working-age Americans. Treatment of diabetic retinopathy is directed toward the prevention of visual loss. Several national clinical trials sponsored by the National Eye Institute have demonstrated that with appropriate referral and treatment the incidence of severe visual loss can be reduced by at least 90%. Acquired immunodeficiency syndrome is a disease of epidemic proportions. More than 75% of AIDS patients have ocular involvement of some kind (from asymptomatic retinal infarctions to vision-threatening cytomegalovirus retinitis). Because ocular findings may reflect disease progression, regular ophthalmologic examination can be beneficial in initiating or modifying'treatment in a timely fashion.



Slide 65 Nonproliferative diabetic retinopathy. Dot-and-blot hemorrhages and exudates are shown scattered throughout the posterior pole. Microaneurysms (pinpoint dots) are difficult to see without high magnification.



Slide 66 Exudates in nonproliferative diabetic retinopathy. Clusters of hard, yellowish exudates are prominent in the superior aspect of the macula. The exudates extend to the fovea, threatening the central vision.

Diabetes Mellitus

Although diabetes may have a number of ocular effects (eg, cataracts, changes in refractive status), the most important ocular complication is retinopathy.

The longer a person suffers from diabetes, the greater the likelihood of developing diabetic retinopathy. About 5 years after diagnosis, 23% of patients with insulin-dependent diabetes mellitus (IDDM, Type I) have diabetic retinopathy, and after 15 years, 80% have retinopathy. Diabetic patients who have non–insulin-dependent diabetes mellitus (NIDDM, Type II) have a similar but slightly lower incidence of retinopathy. Because patients with Type II diabetes may not be diagnosed until years after onset of their disease, many patients already have significant retinopathy at the time of diagnosis.

The initial stage of the ocular disease is called *nonproliferative diabetic retinopathy* (NPDR). Capillaries develop leaks and later become occluded. The retinal findings of mild and moderate NPDR include microaneurysms, dot-and-blot hemorrhages, hard exudates, and macular edema (Slides 65 and 66). Patients experience visual loss only if there is clinically significant macular edema (CSME), which is present in from 5% to 15% of diabetic



Slide 67 Cotton-wool spots in nonproliferative diabetic retinopathy. Microinfarctions of the nerve fiber layer produce the lesions shown. Cotton-wool spots are opaque and white, have feathery edges, and obscure the underlying blood vessels. Venous beading and telangiectasia of the retinal vasculature are shown.

patients, depending on the type and duration of the disease. CSME is the most common cause of mild to moderate visual loss from diabetic retinopathy.

In time, some patients progress to severe NPDR, which heralds the onset of the most serious form of retinopathy, the proliferative stage. Severe NPDR is marked by increased vascular tortuosity and hemorrhagic activity, venous beading, and widespread intraretinal microvascular abnormalities; it may also include many microinfarctions of the nerve fiber layer, or cotton-wool spots (Slide 67). Of patients diagnosed with severe NPDR, 40% will develop proliferative diabetic retinopathy within 1 year.

Proliferative diabetic retinopathy (PDR) is responsible for most of the profound visual loss from diabetes. As a response to continued retinal ischemia, new blood vessels (neovascularization) form in the area of the optic disc or elsewhere on the retinal surface (Slides 68 and 69). Neovascularization can occur elsewhere in the eye; for example, on the surface of the iris (rubeosis iridis), causing severe glaucoma.

If an eye with proliferative retinopathy is not treated, these fragile new vessels will bleed into the vitreous. Fibrous tissue that accompanies the new vessels will contract and cause a traction retinal detachment. Once these severe complications (massive vitreous hemorrhage or traction retinal detachment) have occurred, laser surgery is unlikely to be effective and a vitrectomy may be necessary in the attempt to restore some vision.

PDR and CSME often remain asymptomatic well beyond the optimal stage for treatment. All patients with diabetes should be referred to an ophthalmologist for examination and followup. Some patients with macular edema will require laser surgery (focal treatment) to areas of leaking blood vessels. This treatment has been demonstrated to reduce visual loss by approximately 50%. All patients with nonproliferative and proliferative retinopathy require frequent ophthalmoscopic examinations, and some require specialized examination techniques such as fluorescein angiography to document the extent of the vascular abnormalities and to guide therapy. Detection of treatable macular edema and proliferative retinopathy requires stereoscopic biomicroscopy and indirect opthalmoscopy through dilated pupils. Examination with the hand-held direct ophthalmoscope is not sufficient to rule out significant, treatable diabetic retinopathy.



Slide 68 Proliferative diabetic retinopathy. These photographs are from the same patient. The right optic nerve has two new vessels over the superior aspect of the optic nerve. The left optic nerve has more advanced neovascularization. To prevent progression of the neovascularization and possible vitreous hemorrhage, panretinal photocoagulation is required.



Slide 69 Proliferative diabetic retinopathy. Shown here is more advanced neovascularization of the optic nerve. These new vessels proliferate and extend into the vitreous.

In treating proliferative retinopathy, the ophthalmologist scatters 1000 to 2000 laser bums over the entire surface of the retina except the macula and the papillomacular bundle (Slide 70). This treatment is based on the concept that a reduction of the metabolic oxygen requirement of the retina promotes regression of the neovascular tissue. Appropriately timed effective panretinal laser photocoagulation surgery can reduce the incidence of severe visual loss by at least 50% and as much as 90%. Many patients require frequent treatments when the disease is actively progressing.

All persons with diabetes should be examined at the time of diagnosis and thereafter annually by an ophthalmologist. More frequent examinations are required for patients who have poor glycemic control, hypertension, proteinuria, or anemia, as they are at higher risk for more rapid progression of their retinopathy. Patients who have already been treated with laser



Slide 70 Panretinal argon laser photocoagulation. Shown here are old argon laser burns in the posterior pole of a diabetic patient with proliferative retinopathy. Initially the burns are white, but with time they develop variable pigmentation from chorioretinal scarring.

surgery or vitrectomy should adhere to a followup schedule determined by their ophthalmologist. It is not unusual to require additional treatment.

Pregnant patients with Type I diabetes should be examined by an ophthalmologist during the first trimester and every 3 months thereafter until completion of the pregnancy. Ideally, women who are planning a pregnancy should have a baseline ophthalmologic examination before conception, as pregnancy can severely exacerbate diabetic retinopathy.

The Diabetes Control and Complications Trial (DCCT) showed that intensive glycemic control is associated with a reduced risk of newly diagnosed retinopathy and reduced progression of existing retinopathy in people with insulin-dependent diabetes mellitus (IDDM). Furthermore, the DCCT showed that intensive glycemic control (compared to conventional treatment) was associated with reduction in progression to severe nonproliferative and proliferative retinopathy, incidence of macular edema, and need for panretinal and focal photocoagulation. Advanced diabetic retinopathy is associated with cardiovascular disease risk factors. Patients with proliferative diabetic retinopathy are also at increased risk of heart attack, stroke, diabetic nephropathy, amputation, and death. The results of the DCCT showed that the lowering of blood glucose reduces not only ocular complications but also other end-organ complications, including nephropathy, neuropathy, and cardiovascular disease. It is important that all patients with Type I and most patients with Type II diabetes be educated about the importance of determining and maintaining glycosylated hemoglobin levels to improve glycemic control.

Sickle Cell Anemia

Patients with SC and S Thal disease are more likely to have ocular involvement due to sickle cell than patients with SS disease. Intravascular sickling, hemolysis, hemostasis, and then thrombosis lead to arteriolar occlusion followed by capillary nonperfusion. As with diabetes, inadequate perfusion of the retina can stimulate neovascularization, which can lead to vitreous hemorrhage and retinal detachment. Appropriately timed laser surgery can prevent many vision-threatening complications in these patients.

Hypertension

To understand the effects of systemic hypertension on the retinal vasculature, it is helpful to divide hypertensive retinopathy into two classifications: changes due to arteriolar sclerosis, and changes due to elevated blood pressure.

Arteriolar Sclerosis

Although aging causes thickening and sclerosis of the arterioles, prolonged systemic hypertension (usually diastolic pressure greater than 100 mm Hg) accelerates this process. Thickening of the walls of the retinal arterioles results in characteristic ophthalmoscopic features of retinal arteriolar sclerosis: changes in the light reflex of the arteriole, and changes in arteriovenous (AV) crossing. The amount of arteriolar sclerosis depends on the duration and severity of the hypertension and may reflect the condition of the arterioles elsewhere in the body.

In a normal eye, the retinal arterioles are transparent tubes with blood visible by ophthalmoscopy; a light streak is reflected from the convex wall of the arteriole. As arteriolar sclerosis causes thickening and fibrosis of the vessel wall, the central light reflex increases in width (Slide 71). After sclerosis progresses, the light reflex occupies most of the width of the vessels; at this point, the vessels are called copper-wire arterioles. As fibrosis continues, the light reflex is obscured totally and the arterioles appear whitish and are referred to as silver-wire arterioles.

Because the arterioles and veins share a common sheath within the retinal tissue at crossing sites, arteriovenous crossing changes can be seen (Slide **72).** There may be zones of concealment where the vein is hidden in the region that underlies the artery. The concealment appears as narrowing (so-called nicking) of the vein as it fades on either side of the arteriole.

The vein may be elevated or depressed by the arteriole and, in more severe cases, may undergo an abrupt right-angle change in course just as it reaches the arteriole (see Slide 72). Alterations in the caliber of the vein may occur because of compression and constriction at the A/V crossing, resulting in dilation of the distal portion of the vein. All of these A/V crossing



Slide 71 Hypertensive retinopathy. A single retinal vessel with areas of copper-wiring and silver-wiring is visible in this patient with longstanding hypertension.

changes are most significant when found at or beyond the second bifurcation of the arteriole, which is about 1 disc diameter distal to the optic nerve head. A/V nicking can lead to branch retinal vein occlusions, which can decrease central visual acuity and require laser treatment in certain cases.

Elevated Blood Pressure

A moderate acute rise in blood pressure results in constriction of the arterioles. A severe acute rise in blood pressure (usually, diastolic pressure greater than 120 mm Hg) causes fibrinoid necrosis of the vessel wall, resulting in exudates, cotton-wool spots, flame-shaped hemorrhages, and sometimes whitish swelling and edema of large portions of the retina. In the most severe form of hypertensive retinopathy, malignant hypertension (Slide 73), the optic disc swelling that occurs resembles the swelling seen in papilledema.

Diagnostic Concerns

The changes due to acute hypertension are best seen (and sometimes only seen) in previously normal arterioles; that is, in those not affected by arteriolar sclerosis, because the thickening and fibrosis of the vessel walls protect



Slide 72 Arteriovenous crossing changes. In this magnified view of Slide 71, an abrupt right-angle change of a vein is visible at the first AV crossing, and nicking of the vein is seen at the second AV crossing.



Slide 73 Malignant hypertension. This figure demonstrates the ocular findings associated with severe hypertension: optic nerve swelling, extreme arterial constriction, hemorrhages, early exudates, and cotton-wool spots. Untreated, the optic nerve swelling may progress to resemble papilledema.

C. Activate the Three Fires

Activate the Tan Tien, Kidney and Heart Fires.

Activate the Sacred Fire Triangle circulating the energy between the Tan Tien, kidneys and the heart. Feel the energy's force multiply.

Activate the personal stars; the cosmic star above the head and the earth star below the soles of the feet.

Keep the Tan Tien warm, and spiral at the sacrum and mideyebrow. Turn your eyes to look upwards and see the crown spiraling, connecting to the cosmic star about six inches above the crown point. Feel the cosmic and earth stars pull the body simultaneously towards heaven and earth. See the cup of the Big Dipper fill with Violet Light, gathering Chi from the North Star and the universe. When the cup is full, pour the light down into the cosmic star above your head. Feel the violet light spreading throughout your entire system, filling the Upper, Middle and Lower Tan Tiens.

D. Linking Personal Stars, Energy Bodies and the Universe

Feel the central channel running from your cosmic star, through your three Tan Tiens and connecting to the earth energy below. Use you 'Yi' power to connect to the personal or cosmic star above the head. Connect the personal star to the stars of each other person in the meditation. Create a Chi body and become the major connecting point. Create a left spiral pattern to connect all the stars into a larger group. All the meditators then become a satellite, creating a group energy body.

E. Protective Circle and Chi Field

Raise the hands and touch the Universal Fire. Use your Yi to bring the energy down and manifest a Sacred or Chi Fire around the room, creating a protective circle. Create a Chi Dome and set up the guardian animals and/or angels. Activate the eight elemental forces of nature and the universe.

F. Chi Water (Sacred Water) Practice

Invoke the power of the Sacred Water practice to cleanse the body of all sickness, negative energy and bad fortune. Energize and renew the self at a cellular level with health, wealth and longevity.

G. Empty and Fill

Empty any remaining negative energy, sickness, burdens and worries, down in the depths of the molecular mother, the earth. Bury the energy there so that the earth can recycle it. Bring recycled energy up from the center of the earth into the body. Fill and compact the Chi into the 'hollow bones'. See all of the cells on the horizon of your mind's eye; spread them across the panorama and see the cells as big as the stars in the night sky. Fill them with Chi, blending it with any sick or grey energy. Then empty again, as you guide the all of the Chi back into the earth for recycling. If you wish, you can fill with earth Chi once again before you begin to 'clean with green'.

against fibrinoid necrosis. For instance, arteriolar sclerosis might mask hypertensive changes in a young patient with a pheochromocytoma or in a pregnant woman with toxemia.

It may be difficult to differentiate chronic hypertensive vascular changes (ie, arteriolar sclerosis) from normal involutional (ie, age-related) changes. In order of importance, the most sensitive ophthalmoscopic indicators of hypertension are attenuation of the retinal arterioles, focal narrowing, and A/V crossing changes.

Management

The primary goal in managing systemic hypertension is adequate control of the blood pressure to preserve the integrity of the cerebral, cardiac, and renal circulations. A sudden, severe increase in blood pressure also can compromise the retinal and choroidal circulations, resulting in loss of vision or visual field. Under these circumstances, the blood pressure should be lowered in a controlled fashion because a sudden drop in tissue perfusion could result in optic nerve infarction and permanent loss of vision.

Thyroid Disease

Graves' disease is an example of an important autoimmune disease that may have ocular manifestations. A common clinical feature of thyroid eye disease is retraction of the upper and lower eyelid, with upper-lid lag on downgaze. Thyroid eye disease is also the most common cause of unilateral or bilateral protrusion of the globes, or exophthalmos, in adults. Exophthalmos (proptosis) in combination with retraction of the eyelids may produce an appearance referred to as *thyroid* stare (Slide 74).

Both eyelid retraction and exophthalmos may result in corneal exposure and drying, causing the patient to complain of a foreign-body sensation and tearing. These bothersome symptoms usually can be relieved by the frequent instillation of over-the-counter artificial-tear preparations and the application of lubricating eye ointment at night. The eyelid edema and



Slide 74 Thyroid stare. The staring appearance of this patient is due to forward protrusion of the eyes and retraction of the eyelids, exposing white sclera above and below the limbus.

conjunctival vascular congestion that sometimes accompany thyroid eye disease usually do not require therapy. Proptosis may be surgically treated if severe and persistent.

Thyroid eye disease may cause other serious complications requiring an ophthalmologist's care. Diplopia due to extraocular muscle involvement is common and may require strabismus surgery. Compression of the optic nerve within the orbit can cause loss of vision, necessitating surgery to decompress the orbit or irradiation to reduce the inflammatory swelling of the muscles.

Sarcoidosis and Inflammatory Conditions

Sarcoidosis is a chronic disease of uncertain derivation that affects several organ systems, including the eye. Ocular manifestations are characterized histologically by the presence of focal noncaseating granulomas. Sarcoidosis is most common in African-American women aged 20 to 40. Laboratory findings include increased serum calcium (12% of patients), lack of energy (50% of patients), elevated angiotensin-converting enzyme (75% of patients), and abnormal results on chest x-ray (80% of patients). Important histopathologic information also can be obtained from ocular tissues. The easiest tissue from which to obtain a biopsy specimen is the conjunctiva, but tissue from the lacrimal gland may be obtained as it is also a frequent locus of granulomatous infiltration. Both of these biopsy procedures can be performed under local anesthesia; these areas should be considered before performing potentially more complicated mediastinal or transbronchial biopsies of lymph nodes.

Because ocular involvement from sarcoidosis may be asymptomatic, all patients suspected of sarcoidosis should have a complete ophthalmic evaluation. Sarcoidosis may cause anterior or posterior uveitis. Anterior uveitis is inflammation of the iris and ciliary body (Slide 75); posterior uveitis is inflammation of the choroid. Early initiation of topical or systemic corticosteroids is effective and may prevent complications, such as



Slide 75 Anterior uveitis. Inflammatory cells collect on the inner surface of the cornea, producing opacities called keratic precipitates.

glaucoma, cataract, and adhesions of the iris to the lens. Involvement of the retina is usually associated with posterior uveitis and may include perivasculitis, hemorrhages, and neovascularization of the peripheral retina. Involvement of the central nervous system is twice as common when the fundus is involved, increasing from 10% or 15% to between 20% and 30%. Ophthalmic manifestations of neurosarcoidosis include optic neuropathy, oculomotor abnormalities (including sixth-nerve palsy), and, rarely, chiasmal and retrochiasmal visual field loss.

Dry eye caused by reduced tear production may be seen in sarcoidosis because of lacrimal gland infiltration, but it also occurs in a variety of rheumatologic conditions. The most common are systemic lupus erythematosus and rheumatoid arthritis. Dry eye also is common in a mild form in healthy individuals over age 40. Symptoms include a sensation of burning or grittiness of the eyes, especially late in the day. Accumulation of mucus on the eyelids also occurs in affected patients upon awakening. Many patients complain of tearing, presumably after the eye becomes dry enough to stimulate reflex tearing. Treatment includes the application of artificial tears and occasionally lubricating ointment at night. In the vast majority of patients, the condition is annoying, but rarely leads to serious ocular problems. Occasional patients with advanced rheumatoid arthritis develop severe drying, have corneal damage, and are at greater risk for corneal infection.

Juvenile rheumatoid arthritis is an important childhood systemic condition with ocular manifestations. About 10% of all juvenile rheumatoid arthritis patients have iritis, but the inflammation is more common with the pauciarticular form of the disease (20% to 30% of patients) and much less common in the polyarticular form. Patients who have juvenile rheumatoid arthritis, especially the pauciarticular form, require visits to the ophthalmologist every 3 months because the iritis is commonly asymptomatic. If inflammation is not recognized, extensive ocular complications arise, including cataract, glaucoma, and calcification of the cornea. Iritis is also a common complication of ankylosing spondylitis (10% to 15% of affected patients), Reiter's syndrome, and Behçet's disease.

Malignancy

Cancer originating within the eye or ocular adnexa is rare. More often, the eye is affected secondarily by cancer or by the various forms of cancer therapy. Ocular and orbital metastases are found in up to 5% of cancer patients at autopsy, most often from the breast or the lung. Usually, the tumors infiltrate the choroid, but the optic nerve as well as the extraocular muscles also may be affected. Systemic lymphoma affects the eye in about 3% of patients by infiltrating the conjunctiva or the orbit and causing proptosis or limitation of extraocular movement. In children, leukemic infiltration of ocular tissues can occur. More than 75% of leukemia patients seen at autopsy have ocular adnexal metastases. Commonly, patients with leukemia develop superficial retinal, preretinal, or subconjunctival hemorrhages as a result of thrombocytopenia or the effects of transfusion on normal clotting. Cancer may have remote effects on the eye, including autonomic dysfunction of the pupils as well as a rare but devastating retinal degeneration that has a presumed autoimmune pathogenesis.

Radiation of tumors in the vicinity of the eye may lead to the development of cataract. The lens is susceptible to doses of radiation in the range of 2000 rads. Radiation damage causes a delayed retinal vasculopathy and optic neuropathy. A variety of cancer chemotherapeutic agents have secondary ocular effects. Superficial keratitis may be caused by cytosine arabinoside, optic neuropathy may occur with vincristine injections, and retinal artery occlusion may be caused by carotid artery injection of BCNU (carmustine). Mucosal damage from graft-vs-host disease may involve the conjunctiva, leading to dryness and corneal decompensation with subsequent infection.

Acquired Immunodeficiency Syndrome

Acquired immunodeficiency syndrome (AIDS) is a severe disorder in which depression of the immune system results in the development of multiple opportunistic infections and malignancies. Ophthalmic examination may confirm the diagnosis. Common ophthalmic manifestations are cotton-wool spots (AIDS retinopathy), cytomegalovirus retinitis, and Kaposi's sarcoma affecting the eyelids. The less common complications include herpes zoster (shingles), herpes simplex keratitis, conjunctival microangiopathy, luetic and toxoplasmic uveitis and retinitis, and visual field defects or oculomotor dysfunction resulting from central nervous system involvement.

Retinal cotton-wool spots (Slide 76) are due to the focal occlusions of retinal capillaries that result in accumulation of axoplasm in the region of the retinal nerve fiber layer. In AIDS, the occlusions are thought to be due to microthrombi from antigen-antibody complexes and fibrin. These are frequently the sole ocular finding in patients with AIDS (more than 50%). Cotton-wool spots and hemorrhages with white centers are found in



Slide 76 Cotton-wool spots in AIDS. Scattered cotton-wool spots, as well as some hemorrhages, are depicted in this retina of a patient with AIDS.



Slide77
Cytomegalovirus retinitis in AIDS. The multicentric retinitis is characterized by discrete, fluffy, white retinal necrosis, with retinal hemorrhages and vasculitis. There is a sharp, distinct border between the diseased retina and the normal retina.

patients with a variety of other infectious conditions, including subacute bacterial endocarditis and systemic candidiasis.

Cytomegalovirus (CMV) retinitis (Slide 77) is the leading cause of visual loss in patients with AIDS, occurring in more than 25% of patients. The distinctive ophthalmoscopic appearance of CMV retinitis is characterized by hemorrhagic necrosis of the retina. Areas of involved retina have distinct borders and abruptly abut areas of normal retina. The disease progresses over weeks to months and results in total atrophy of the affected retina. Most patients who develop CMV retinitis have a poor prognosis for survival.

Kaposi's sarcoma, characterized by multiple vascular skin malignancies, may involve the conjunctiva of either the lid or the globe. Unless suspected, this sarcoma may be misdiagnosed as a subconjunctival hemorrhage or a hemangioma.

Until recently, therapeutic intervention has been aimed at halting progression of the opportunistic infection. However, with the advent of protease inhibitors, some patients have shown resolution of their opportunistic infection.

Any patient with a diagnosis of HIV should be referred to an ophthalmologist for a complete ophthalmologic examination. Detailed discussion of therapeutic intervention is beyond the scope of this book. However, when such intervention is indicated, many variables must be considered, and it is important that good communication be established among the patient's other treating physicians and that therapy be determined based on a team approach.

Syphilis

Intraocular inflammation due to syphilis can be cured, even in patients with AIDS. Delay in diagnosis of syphilitic chorioretinitis can lead to permanent visual loss that might have been avoided with early treatment.

Acute interstitial keratitis with keratouveitis occurs in patients with congenital syphilis between the ages of 5 and 25 years. It is bilateral in congenital disease and unilateral if acquired. It is believed to be an allergic



Slide 78 Herpes zoster ophthalmicus. Crusting lesions (no longer vesicles) are present in the distribution of the ophthalmic division of the fifth cranial nerve. The conjunctiva is red and the lids are swollen, indicating ocular involvement by herpes zoster. (Fluorescein has been instilled.)

response to *Treponema pallidum* in the cornea. Symptoms and signs include intense pain and photophobia, and a diffusely opaque cornea with vision reduced, even to light perception. Blood vessels invade the cornea, and when they meet in the center of the cornea after several months, the inflammation subsides and the cornea partially clears. Late stages show deep ghost (nonperfused) stromal vessels and opacities. Any patient with syphilitic uveitis should have a spinal fluid examination.

Ocular involvement in secondary syphilis may feature pain, redness, or photophobia, or blurred vision and floating spots. The patient may present with iritis or choroiditis. There may be exudates around the disc and along the retinal arterioles in secondary syphilis. Arteritis and periarteritis may occur.

In latent syphilis, the presenting ocular complaint is usually blurred vision. The presence of chorioretinitis usually indicates cerebrospinal fluid involvement or neurosyphilis. Diffuse neuroretinitis with papillitis and periarterial sheathing may also occur.

Other Systemic Infections

In addition to AIDS, other systemic infections may affect the eye. The most common are candidiasis and herpes zoster. The typical *Candida* lesion is a fluffy, white-yellow, superficial retinal infiltrate that may lead to the rapid development of overlying vitreous haze and eventual vitritis. Rarely, inflammation of the anterior chamber occurs. The presence of ocular candidiasis is a specific indication for systemic therapy with amphotericin B.

Herpes zoster ophthalmicus (Slide 78), from varicella zoster involving the ophthalmic division of the fifth cranial nerve, may result in ocular manifestations, especially when vesicles appear on the tip of the nose from extension along the nasociliary branch. Corneal infiltration with the virus may lead to disruption of the epithelium, best seen as fluorescein dye staining of the cornea. However, the epithelium usually heals spontaneously and rapidly. The most important ocular side effect of herpes zoster is anterior uveitis, which can be confirmed by slit-lamp examination. The combination of anterior uveitis and keratitis, especially with loss of normal corneal sensation, is a serious vision-threatening effect. Affected patients should be referred to an ophthalmologist immediately for assistance in diagnosis and treatment. Rare ocular complications of herpes zoster include optic neuritis and oculomotor nerve involvement with subsequent diplopia.

Points to Remember

1. To recognize many ocular manifestations of systemic disease, the primary care physician must perform a thorough fundus examination, preferably through dilated pupils.
2. Early diagnosis of diabetic retinopathy is crucial to the ultimate success of treatment, which is effective for both nonproliferative and proliferative stages of the disease when patients are referred in a timely fashion.
3. Any patient with an autoimmune disease or systemic infection who presents with a red eye, decreased vision, photophobia, or floaters should be referred to an ophthalmologist for a slit-lamp examination to look for subtle but vision-threatening intraocular inflammation.

Sample Problems

1. An adult patient with a 10-year history of non–insulin-dependent diabetes comes to your office for the first time, having recently moved from another state. She tells you that she has never seen an ophthalmologist nor had a dilated ophthalmoscopic examination. Her visual acuity is normal, but on dilated fundus examination, you find neovascularization of the optic disc. How do you manage this patient?

   Answer: Although this patient's visual acuity is normal, neovascularization of the optic disc is diagnostic of proliferative diabetic retinopathy, which places this patient at high risk for developing marked visual loss. She should be referred immediately to an ophthalmologist for examination and treatment. Panretinal laser photocoagulation surgery can be initiated to reverse the course of the neovascularization and reduce the risk of serious visual loss.

2. A 45-year-old man comes to your office complaining of headaches and nosebleeds. His blood pressure is 180/120 mm Hg. On dilated fundus examination, you find numerous exudates, flame-shaped hemorrhages, cotton-wool spots, and severe attenuation of the arterioles. You do not find AV crossing changes, and the arteriolar light reflex is normal. What information does your ophthalmoscopic examination provide about the chronicity of the patient's systemic hypertension?

   Answer: Flame-shaped hemorrhages and cotton-wool spots are ophthalmoscopic changes indicative of acute, severe hypertension. When these features occur in the absence of arteriolar sclerotic changes (ie, AV crossing phenomenon), the hypertension is most likely of recent onset.

In such cases, hypertension may be associated with renal insufficiency, encephalopathy, and impairment of cardiac function. Controlled reduction of blood pressure should be initiated immediately.

3. A previously healthy 40-year-old woman presents with bilateral proptosis and lid retraction, but she denies any pain. The most likely diagnosis is

a. metastatic tumor to orbit
b. orbital cellulitis
c. orbital pseudotumor
d. thyroid eye disease
e. carotid artery-cavernous sinus fistula

Answer: d. Thyroid eye disease is the most common cause of unilateral or bilateral proptosis in adults. Thyroid eye disease can be present with normal thyroid function. Orbital pseudotumor usually causes pain, whereas thyroid eye disease does not. Orbital cellulitis usually presents with swollen, tender, erythematous lids, malaise, and elevated white blood cell count. Carotid cavernous sinus fistula causing proptosis is more common following trauma and is not associated with lid retraction, and often a bruit can be auscultated with the stethoscope over the orbit. Metastatic tumor of the orbit would not likely be bilateral with a negative past medical history.

Annotated Resources

Benson WE, Brown GC, Tasman W: *Diabetes and Its Ocular Complications.* Philadelphia: *WB* Saunders Co; 1988. A thorough discussion of the many ocular complications of diabetes.

Diabetes Control and Complications Trial Research Group. The effect of intensive treatment of diabetes on the development and progression of long-term complications in insulin-dependent diabetes mellitus. *N Engl J Med* 1993;329:977–986. Intensive therapy effectively delays the onset and slows the progression of diabetic retinopathy, nephropathy, and neuropathy in patients with insulin-dependent diabetes mellitus.

Diabetic Retinopathy Study Research Group: Photocoagulation treatment of proliferative diabetic retinopathy: the second report of diabetic retinopathy study findings. *Ophthalmology* 1978;85:82–106. A report of the findings in this classic prospective, randomized, multicenter study on diabetic retinopathy.

DRSR Group, ETDRSR Group: *Management of Diabetic Retinopathy for the Primary Care Physician.* San Francisco: American Academy of Ophthalmology; 1990. This videotape helps the primary care physician identify and distinguish between the various stages of diabetic retinopathy. It covers the associated risks of each stage, the essentials of followup and treatment, a brief description of the pathophysiology, and the importance of timely referral.

Duane TD, Osher RH, Green WR: White-centered hemorrhages: their significance. *Ophthalmology* 1980;87:66–69. A good review of the causes and pathophysiology of Roth's spots.

Ferry AP, Font RL: Carcinoma metastatic to the eye and orbit, I: a clinical pathologic study of 227 cases. *Arch Ophthalmol* 1974;92:276–286. The classic article on the subject.

Iwata K, Namba K, Sobue K, et al: Ocular sarcoidosis: evaluation of intraocular findings. *Ann* NY *Acad Sci* 1976;278:445–454. *An* overview of ocular sarcoidosis with incidences of each occurrence.

Kanski JJ: Juvenile arthritis and uveitis. *Surv Ophthalmol* 1990;34:253–267. A major review of the subject with many references.

Palestine AG, Rodrigues MM, Macher AM, et al: Ophthalmic involvement in acquired immunodeficiency syndrome. *Ophthalmology* 1984; 91:1092–1099. One of the best summaries of the ophthalmic changes associated with the acquired immunodeficiency syndrome.

Parke DW, Jones DB, Genry 0 0: Endogenic endophthalmitis among patients with candidemia. *Ophthalmology* 1982;89:789–794. *A* useful study of hospitalized immunocompromised patients who needed ophthalmic consultation.

Results from the early treatment of diabetic retinopathy study. *Ophthalmology* 1991;98(suppl):739–840. *A* comprehensive review of the current approach to background diabetic retinopathy.

Trobe JD: *The Physician's Guide to Eye Care.* San Francisco: American Academy of Ophthalmology; 1993. A brief but comprehensive resource covering the principal clinical ophthalmic problems that nonophthalmologist physicians are likely to encounter, organized for practical use by practitioners.

Van Dyk HJL: Orbital Graves' disease: a modification of the "NO SPECS" classification. *Ophthalmology* 1981;88:479–483. A clear discussion of the progression of this common disease.

Walsh JB: Hypertensive retinopathy: description, classification and prognosis. *Ophthalmology* 1982;89:1127–1132. A good review of hypertensive effects on the eye with simplification of various classifications.

Chapter 9

Drugs and the Eye

Objectives

As a primary care physician, you should be able to use pharmacologic agents to facilitate an eye examination, including staining the corneal surface with fluorescein, anesthetizing the cornea with a topical anesthetic, and dilating the pupil with one or more mydriatic drugs. You should be aware of the potential ocular complications of the eyedrops and systemic drugs that you prescribe and be able to recognize these ocular complications when they occur. In addition, you should be cognizant of the systemic effects of the topical ophthalmic drugs that an ophthalmologist might prescribe for your patients.

To achieve these objectives, you should learn

- The technique of applying drugs to the conjunctival sac
- The ocular effects and complications of common topical ocular drugs used for diagnosis and therapy, including anesthetics, mydriatics, and corticosteroids
- The systemic side effects of glaucoma medications: beta-adrenergic blockers, cholinergic stimulators, adrenergic drugs, prostaglandin analogs, and carbonic anhydrase inhibitors
- The ocular side effects of systemically administered corticosteroids, the chloroquines, digitalis, amiodarone, diphenylhydantoin, ethambutol, chlorpromazine, and thioridazine

Relevance

You will need to use diagnostic drugs to perform a complete ocular examination, which entails skills that every primary care physician should possess. You must be familiar with the side effects and complications of diagnostic and therapeutic drugs to minimize the potential for problems and to recognize them when they do occur.

Basic Information

Using the proper technique to instill eyedrops ensures maximum patient cooperation and adequate delivery of medication to the eye. To instill topical ocular medications, follow these steps:

H. Clean with Green Light

Green cleans and detoxifies all of the body's cells**.** Green Chi is mild and safe. Green Chi is used for cleansing, and as a decongestant for diseased parts. Be aware of the liver's green color, the throat and the emerald forest. Breathe into the throat, feel yourself breathing in the green light. Guide it down to the Tan Tien, blend and move it up to the heart and the crown.

Project it to the universe; spiral and let it multiply. Channel one direct line down to the student, one to your crown and one to your palm. Bring the energy back down and blend it with any sickness in the liver, gallbladder or anywhere else in the body. Spiral the energy counter clockwise and down into the earth. Continue cleaning with green until you see that all the cells have been charged with the emerald light of the forest.

I. Clean with Blue Light

Be aware of the kidneys' blue sapphire color and breathe the blue light into your throat. Guide it down to the Tan Tien, blend and move back up to the 'heart of compassion' and then to the crown.

Project up to the universe, spiral and let it multiply. Channel one direct line down to the student, one to your crown and one to your palm. Then feel the universe pouring the blue light back down; clockwise. Spiral down. Look at the cells and see the blue light, like water, go into the cells to rinse, clean and remove any sickness. Spiral the energy counter clockwise and down into the earth. Continue rinsing with blue light until you see that all the cells have been charged with the sapphire blue.

J. Charge with Violet Light

Luminous Violet has intelligence and can be programmed.

Turn three minds into one mind, go deep into the empty space of the cell and deep into the chromosomes, magnify the space as you enter into the DNA and return to the original cells. Ask for the power to see the cells and look at the brain cells spread out into the space. "Brain cells please listen. Clear, Clean, and Bright: fill with violet light, back to normal function". See violet light. Be aware your crown. The Tan Tien Chi and the negative Chi all combine in the crown. Extend a violet light up to the universe. See the North Star and the Big Dipper. Tell the students to hold their arms in the air, so that they can funnel the Chi into their personal star. Bring the North Star and the Big Dipper down; hold the handle of the Big Dipper and pour the violet light over the student's personal star. The higher cells will be programmed. Let the Chi enter the brain and ask for the power to see the brain cells. "Brain cells listen to the command". If there is sickness in the brain, give the command. "Sickness go away". Continue to spiral the violet light down through the cells of the whole body.

1. Ask for the power to see into the cells of the **Brain.** Ask the student to move their hands to cover their brain. "**Brain Cells** listen to the command;"Sickness go away. Clear, clean and bright fill with violet light and return to normal functions".

1. Wash your hands; wear disposable gloves if desired.
2. Instruct the seated patient to tilt the head back and to look up.
3. Expose the palpebral conjunctiva by gently pulling downward on the skin over the cheekbone (Figure 9.1). Avoid direct pressure on the eyeball.
4. Instill the correct amount of medication into the lower conjunctival fornix. Avoid applying drops directly to the cornea, which is the most sensitive part of the eye, and avoid touching the tip of the applicator to the patient's lids or eye.
5. Instruct the patient to close both eyes gently for a few seconds. Wipe any excess medication from the patient's skin with a tissue.

Topical Ocular Diagnostic Drugs

The drugs discussed in this section are used in executing a basic eye examination and assessing certain ocular complaints commonly encountered by the primary care physician. Before administering any medication, always ask patients if they may be allergic to the agent.

Fluorescein Dye

Sodium fluorescein is a water-soluble, orange-yellow dye that becomes a brilliant green when viewed under cobalt-blue or fluorescent light. The dye, which does not irritate the eye, is extremely helpful in detecting abrasions of the corneal surface because fluorescein stains damaged epithelium (see Slides 5 and 6 in Chapter 1). To instill the dye, a sterile, individually packaged dry fluorescein strip is moistened with a drop of sterile water or saline and then applied to the inferior bulbar conjunctiva. A few blinks spread the now-visible tear film across the cornea. Although no systemic complications accompany the use of topical fluorescein, a local complication is the staining of a soft contact lens because of its porous structure. To avoid discoloration, contact lenses should be removed before the fluorescein is instilled.



Figure 9.1 Instillation of topical drops.

Anesthetics

Among the topical anesthetics, the most widely used agents are proparacaine hydrochloride 0.5% and tetracaine 0.5%. The instillation of 1 drop of these surface-active compounds renders the corneal epithelium insensate within 15 seconds. Such anesthesia is useful to make surface manipulations painless; for example, to remove a superficial corneal foreign body or perform tonometry. Use of an anesthetic also facilitates the examination of a damaged cornea, which otherwise might be difficult because of the pain. Patients should be instructed not to rub their eyes for at least 10 minutes after receiving topical ocular anesthetics to avoid their inadvertently scratching their corneas.

Topical anesthetics may produce local or systemic allergy, but this is rare. They should never be prescribed for repeated use by patients because they are toxic to the corneal epithelium; they inhibit mitosis and cellular migration and can lead to corneal ulceration and permanent corneal scarring. (See Chapter 4 for a discussion of therapeutic warnings.)

Mydriatics

Mydriatics are drugs that dilate the pupil; dilation may be necessary for ophthalmoscopy. The two classes of mydriatics are cholinergic-blocking (or parasympatholytic) drugs and adrenergic-stimulating (or sympathomimetic) drugs.

Cholinergic-Blocking Drugs

Drugs in this category dilate the pupil by paralyzing the iris sphincter. Several such drugs are in regular use: tropicamide 0.5% or 1%; cyclopentolate hydrochloride 0.5% or 1%, and homatropine hydrobromide 1% or 2%. Atropine sulfate 0.5% or 1% and scopolamine hydrobromide 0.25% or 5% are also available for topical ocular use, but they should never be used just to dilate the pupil for diagnostic purposes because their effects may last 1 to 2 weeks.

Cholinergic-blocking drugs produce not only mydriasis but also cycloplegia, or paralysis of the muscles of the ciliary body. For this reason, these drugs are often referred to as *cycloplegics*. Cycloplegia produces paralysis of accommodation (focusing), so that patients find their near vision may be blurred until the effects of the cycloplegic wear off. Nevertheless, these drugs are widely employed by physicians because they produce excellent mydriasis and the cycloplegic effect facilitates refraction.

Tropicamide is a popular mydriatic with primary care physicians and ophthalmologists alike because of its rapid onset and short duration. Maximum pupillary dilation is attained about 30 minutes after instillation, and the effect diminishes within 4 to 5 hours. Cautions regarding pupillary dilation are discussed in Chapter 1. Systemic side effects of tropicamide are decidedly rare because of its brief duration of action, but they may be serious; they include nausea, vomiting, pallor, and vasomotor collapse. Cyclopentolate produces more complete cycloplegia and is used by ophthalmologists to perform refractions in children.

Adrenergic-Stimulating Drugs

These drugs dilate the pupil by stimulating the pupillary dilator muscle. Only one such drug is in regular use: phenylephrine hydrochloride 2.5%. Just 1 drop applied to the eye dilates the pupil in 30 to 40 minutes, but has no effect on accommodation; thus, phenylephrine is a mydriatic but not a cycloplegic. Because accommodation is not affected, the patient can use near vision after instillation. However, the mydriasis produced is not as great as with tropicamide, and the pupil remains reactive to light. For these reasons, phenylephrine is seldom used alone as a mydriatic.

When maximum mydriasis is required—for example, when the far periphery of the retina must be examined—phenylephrine in combination with tropicamide is ideal because the effects are additive. This combination is often used to dilate the pupil of a brown iris as well, because mydriatics are less effective in dark-eyed individuals than in blue-eyed ones. The 2.5% solution of phenylephrine is much preferred to the 10% solution because the stronger preparation has been associated with acute hypertension and even with myocardial infarction in some patients.

In infants, the combination of cyclopentolate hydrochloride 0.2% and phenylephrine hydrochloride 1.0% (Cyclomydril) is the safest and most effective agent. Hypertension and reduced gastric emptying may occur if stronger agents are used.

Topical Ocular Therapeutic Drugs

The topically applied ocular drugs reviewed in this section are of clinical importance.

Decongestants

This group of drugs is important if only because more than a million bottles of over-the-counter ocular decongestant are purchased each month in the United States. These weak adrenergic-stimulating drugs temporarily whiten the conjunctiva through their vasoconstrictor effect. They are advertised as effective in relieving redness of the eye due to minor eye irritations caused by smoke, dust, smog, wind, glare, swimming, contact lenses, or fatigue.

Naphazoline hydrochloride 0.012%, phenylephrine hydrochloride 0.12%, and tetrahydrozaline hydrochloride 0.05% are the three major drugs in this category. The widespread belief that the use of these compounds is part of good ocular hygiene is a misconception. Red, burning eyes may benefit as much from a cold, wet compress to the closed eyelids as they would from these compounds. Nevertheless, these agents are purchased in high volume.

The most frequent complication of ocular decongestants arises from overuse, with rebound vasodilation of conjunctival vessels. In other words, when used in excess, these preparations can increase rather than decrease redness of the eyes. In rare instances, acute angle-closure glaucoma may be precipitated in susceptible eyes by the use of sympathomimetic drugs because they can dilate the pupil. However, these drugs may be used without harm by patients with chronic open-angle glaucoma because they do not produce a rise in pressure if the filtration angle is open.

Agents for Relief of Allergic Conjunctivitis

Combinations of naphazoline and antazoline or pheniramine drops are available over the counter as remedies for redness and itching associated with seasonal allergic conjunctivitis. These provide decongestant action (see above) as well as antihistamine effects. Prescription medications are also available for management of these symptoms. The mast-cell stabilizers cromolyn and lodoxamide prevent the release of inflammatory mediators and are administered chronically for prevention of allergic symptoms. Levocabastine, an antihistamine, and ketorolac, a nonsteroidal anti-inflammatory agent, are helpful for use as needed for symptomatic relief.

Anti-Inflammatory Agents

Both corticosteroids and nonsteroidal topical preparations are useful in the management of various ocular situations. Topical ocular corticosteroids should never be prescribed by a primary care physician. The serious complications of this class of drugs are discussed in Chapter 4 and include promotion of viral, bacterial, and fungal infections as well as possible development of glaucoma and cataract. Nonsteroidal anti-inflammatory agents do not potentiate these complications. Topical ocular preparations include diclofenac, ketorolac, flurbiprofen, and suprofen. These alone are generally not potent enough to control significant intraocular inflammation, however. They are also used by ophthalmologists for other specific indications, such as ocular itching, macular edema, or prevention of miosis during cataract surgery.

Antibiotics

Topical antibiotics may be used for bacterial infections of the conjunctiva and cornea. The choice of agent is based on the suspected infecting organism. Many commercial agents are available in ophthalmic preparations of drops or ointment.

Topical antibiotics are useful for treating common bacterial conjunctivitis. Useful antibiotics include fluoroquinolones, sulfacetamide, and erythromycin. Neomycin-containing agents, although effective as antibacterials, often cause increased redness and tearing because of topical sensitivity. Antibiotics combined with corticosteroids should be used only under the direction of an ophthalmologist, because the combination may accelerate the progression of a herpes simplex or fungal infection and cause permanent damage.

Systemic Side Effects of Glaucoma Medications

The topically administered glaucoma drugs discussed in this section may have potent systemic side effects. Any drug instilled in the conjunctival cul-de-sac may be absorbed systemically by the conjunctiva, nasopharyngeal mucosa, or gastrointestinal tract (after saliva is swallowed in the nasopharynx). One class of agents, the carbonic anhydrase inhibitors, may also be given orally and may cause side effects as well.

Beta-Adrenergic Blockers

Topical Timolol, Levobunolol, Metapranolol, and Carteolol

Nonselective beta-adrenergic antagonists reduce the formation of aqueous humor by the ciliary body and thereby reduce intraocular pressure. Timolol and its analogs levobunolol, metapranolol, and carteolol are highly effective and widely used. Because the systemic beta-adrenergic effects include bronchospasm, these drugs are contraindicated in patients with asthma or chronic obstructive pulmonary disease. Several deaths have been reported secondary to the pulmonary complications of topically administered timolol. Because of their cardiac effects, topical beta-adrenergic antagonists may precipitate or worsen cardiac failure and must be used with caution if bradycardia or systemic hypotension would adversely affect the patient.

Topical Betaxolol

A cardioselective beta-1-adrenergic antagonist, betaxolol hydrochloride was developed to avoid the pulmonary complications of timolol. Betaxolol may be as effective as nonselective beta-adrenergic antagonists in lowering intraocular pressure. However, pulmonary effects have occasionally been noted, and caution should be used when this drug is employed in patients with excessive impairment of pulmonary function.

Cholinergic-Stimulating Drugs

Topical Pilocarpine

Pilocarpine, available in drop and ointment forms, lowers intraocular pressure by increasing aqueous outflow through the trabecular meshwork. Because of frequent local side effects, including diminished vision due to pupillary constriction and headaches from ciliary muscle spasm, this drop is a less popular glaucoma agent. Systemic side effects are rare, however, as systemic toxicity occurs only at 5 to 10 times the usual ocular dosage. Nevertheless, lacrimation, salivation, perspiration, nausea, vomiting, and diarrhea may occasionally occur, especially with overdosage.

Topical Echothiophate

A long-acting anticholinesterase, echothiophate iodide also mimics stimulation of the parasympathetic nervous system and is, therefore, used clinically to treat glaucoma and occasionally accommodative esotropia. The side effects of echothiophate are identical to those described for pilocarpine but are more common. In addition, because long-term use of this drug inactivates plasma cholinesterase, patients are more susceptible to the effects of succinylcholine and procaine because plasma cholinesterase hydrolyzes those agents. Prolonged apnea and even death have been reported from the use of succinylcholine during anesthesia in patients with low blood cholinesterase secondary to treatment with topical ocular echothiophate.

Alpha-2 Adrenoreceptor Agonists

Topical Brimonidine

Brirnonidine tartrate is a relatively selective alpha-2 agonist that lowers intraocular pressure by a presumed dual mechanism of decreased aqueous production and increased uveoscleral (non–trabecular meshwork) aqueous outflow. To date, systemic side effects of this new glaucoma medication have been few but may include oral dryness, headache, and fatigue and drowsiness. Brimonidine should not be given to infants because of the risk of severe hypotension and apnea. In adults it may cause a local allergic reaction.

Topical Apraclonidine

Apraclonidine, a derivative of clonidine, decreases aqueous formation and increases uveoscleral outflow. It is primarily utilized for temporary intraocular pressure control in critical situations or as prophylaxis against pressure spikes after glaucoma laser procedures, but it may also be used chronically to treat glaucoma. Its most concerning systemic side effects include promotion of orthostatic hypotension and vasovagal episodes. Locally it has a fairly high rate of sensitivity reaction and may cause an impressive contact dermatitis of the lids and conjunctiva. Use of topical apraclonidine is associated with mild pupillary dilation, whitening of the conjunctiva, and elevation of the upper eyelid.

Adrenergic-Stimulating Drugs

Topical Epinephrine and Dipivefrin

Epinephrine hydrochloride and dipivefrin, an epinephrine prodrug, are occasionally used in the treatment of glaucoma. Epinephrine in particular may cause cardiac arrhythmia or an increase in systemic blood pressure in some patients due to its adrenergic stimulation.

Prostaglandin Analog

Topical Latanoprost

A relatively new glaucoma medication, latanoprost is a synthetic analog of prostaglandin $F_{2\alpha}$. It increases aqueous outflow through the uveoscleral pathway, a supplemental route through which a small portion of the aqueous drains. No major, concerning systemic toxic effects of this drug have been reported, but it has the peculiar potential to darken iris color in some patients with blue, green, or hazel irides. Latanoprost also has been associated with lengthening and increased fullness of eyelashes in treated eyes. In addition, it may cause swelling of the macula in patients who have had cataract extractions.

Carbonic Anhydrase Inhibitors

Oral Acetazolamide, Methazolamide, and Dichlorphenamide

These aqueous suppressants are the only oral drugs utilized for glaucoma management. Their use, particularly on a chronic basis, is limited by a number of side effects, which include paresthesias, anorexia, gastrointestinal disturbances, headaches, altered taste and smell, sodium and potassium depletion, and a predisposition to form renal calculi, and rarely, bone marrow suppression.

Topical Dorzolamide

Topical dorzolamide lowers intraocular pressure by the same mechanism as oral carbonic anhydrase inhibitors. It has a significantly lower (but still possible) incidence of systemic side effects.

Ocular Side Effects of Systemic Drugs

The drugs covered in this section are systemically administered medications that may have profound ocular or neuro-ocular effects.

Corticosteroids

Corticosteroids or, more properly, adrenocorticosteroids, when given long-term in moderate dosage, produce posterior subcapsular cataracts. Asthmatic individuals, renal-transplant recipients, and patients with rheumatoid arthritis are groups in whom this phenomenon has been commonly observed. Patients with rheumatoid arthritis may develop posterior subcapsular cataracts in the absence of corticosteroid therapy, but the incidence increases with corticosteroid therapy. The use of systemic or inhaled corticosteroids is associated with elevated intraocular pressures (steroid-induced glaucoma) in susceptible individuals.

Chloroquines

Chloroquine phosphate and hydroxychloroquine sulfate, originally used to treat malaria, are now also used to treat rheumatoid arthritis, lupus erythematosus, and other autoimmune disorders. Chloroquines can produce corneal deposits and retinopathy. The corneal deposits are usually asymptomatic, but can produce glare and photophobia. The deposits regress when the drug is discontinued, but the retinopathy is much more serious. This drug-induced retinal damage is insidious, slowly progressive, and usually irreversible. The typical bull's-eye macular lesions do not become visible ophthalmoscopically until serious retinal damage has already occurred. Patients taking high dosages of chloroquine phosphate (eg, more than 250 mg a day) or having long-term treatment (eg, 3 or more years of at least 300 g total dosage) are at greatest risk. Patients using the chloroquines require regular ophthalmologic examinations, with visual acuity, color vision, Amsler grid, visual field, and ophthalmoscopic testing at the minimum.

Digitalis

Intoxication with this widely used cardiovascular drug almost always produces blurred vision or abnormally colored vision (ie, chromatopsia). Classically, normal objects appear yellow with the overdosage of digitalis, but green, red, brown, or blue vision can also occur. White halos may be perceived on dark objects, or objects may seem frosted in appearance. Usually, fatigue and weakness develop concomitantly with digitalis intoxication, but the visual disturbances often dominate the patient's complaints.

Amiodarone

Amiodarone is a cardiac arrhythmia drug that produces whorl-shaped, pigmented deposits in the corneal epithelium. These deposits are dosage-related and reversible if the dosage is decreased or the drug is discontinued entirely. Visual symptoms are rare.

Diphenylhydantoin

Still widely used for the control of seizures, diphenylhydantoin sodium causes dosage-related cerebellar-vestibular effects. Horizontal nystagmus in lateral gaze, vertical nystagmus in upgaze, vertigo, ataxia, and even diplopia occur with mildly elevated blood levels of the drug. More complex forms of nystagmus and even ophthalmoplegia may accompany extremely high blood levels. These effects are reversible if the drug is discontinued.

Ethambutol

Ethambutol is useful in the chemotherapy of tuberculosis. As a side effect, ethambutol produces a dosage-related optic neuropathy. With dosages of 15 mg/kg/day, optic neuropathy occurs in less than 1% of patients, but increases to 5% of patients receiving 25 mg/kg/day and to 15% receiving 50 mg/kg/day. The onset of visual loss may be within 1 month of starting the drug. Recovery usually occurs when the drug is stopped, but may take months; occasionally, visual loss is permanent.

Chlorpromazine

This psychoactive drug produces punctate opacities in the corneal epithelium after long-term use. Occasionally, opacities develop on the lens surface as well. These opacities rarely cause symptoms and are reversible with discontinuation of the drug.

Thioridazine

Thioridazine, commonly used to treat patients with psychoses, produces a pigmentary retinopathy after high dosage, usually at least 1000 mg/day. The current recommendation is 800 mg/day as the maximum dose.

Points to Remember

1. When administering eyedrops, avoid dropping them directly on the sensitive central cornea. Instead, release the drops into the lower conjunctival fornix.
2. Never give a patient a prescription for a topical anesthetic (or a sample, either).
3. Never use atropine or scopolamine to dilate the pupil for a fundus examination.

4. Never use or prescribe a topical ocular corticosteroid unless you have a precise diagnosis for which the drug is specifically indicated. You must be prepared to monitor the patient for serious side effects, such as glaucoma or cataract.

Sample Problems

1. A busy student comes to you during exam week because she is experiencing severe headaches. As part of a complete physical, you perform a basic eye examination. During ophthalmoscopy you cannot fully see the optic disc because the patient's pupil is very small. You find no contraindications to dilating the pupil so you decide to do so to facilitate ophthalmoscopy. Your patient is brown-eyed, 20 years old, and has no other health complaint. Which of the following drugs would you select to dilate the pupils?
   a. Phenylephrine hydrochloride 0.12%
   b. Phenylephrine hydrochloride 2.5%
   c. Phenylephrine hydrochloride 10%
   d. Atropine sulfate 1%
   e. Tropicamide plus phenylephrine hydrochloride 2.5%

   Answer: e. The patient is experiencing severe headaches. A potential source of these headaches is increased intracranial pressure due to brain tumor, with resultant papilledema. Therefore, it is important to see the optic disc clearly to examine for these findings. Phenylephrine hydrochloride 2.5% may not be effective when used alone as a mydriatic in a brown-eyed patient. Atropine sulfate 1% is never used for simple pupillary dilation because its effects may last 1 to 2 weeks. The 0.12% solution of phenylephrine is the strength found in many over-the-counter ocular decongestants and will dilate the pupil minimally. The 10% solution is not the preferred concentration because it may be associated with serious systemic side effects in certain individuals. A combination of tropicamide with phenylephrine 2.5% usually provides excellent pupillary dilation with a relatively short duration of action and minimal systemic risk.

2. A man who has recently moved to the area is referred to you by a friend. He reports feeling especially tired lately becoming fatigued after only moderate activity. He is also concerned about his vision; everything seems "dingy" or "yellow" to him. He's not sure when this visual symptom started. The patient has a history of heart disease, for which he takes cardiac medications. Examination reveals no health problems, other than his heart condition, which appears stable. How would you treat this patient? Should you refer him to an ophthalmologist at this time?

   Answer: Symptoms of blurred vision or abnormally colored vision occur with digitalis intoxication. Fatigue and weakness are also characteristic. Usually, such symptoms occur only with overdosage and

2. Ask for the power to see the cells of the sense organs. Ask the student to move their hand to cover their senses. Give the command; **"Eyes, Ears, Nose, Tongue and Mouth** cells listen to the command. Sickness go away. Clear, clean and bright fill with violet light and return to normal function".
3. Move your hands down to your Throat Center and give the command; **"Thyroid, Parathyroid and Thymus Glands** listen to the command; Clear, clean and bright fill with violet light and return to normal function".
4. Move your hands to the heart and the lungs. Ask for the power to see the cells of the heart and lungs. Give them the command; **"Lungs and Heart Cells** listen to the command; Clear, clean and bright; Fill with violet light and return to normal function".
5. Move your hands to cover the left and right sides of the ribcage. Ask for the power to see the cells of the liver, gallbladder, spleen, pancreas and stomach. Give them the command; **"Liver, Gallbladder, Spleen, Pancreas and Stomach Cells** listen to the command; Clear, clean and bright fill with violet light and return to normal function".
6. Move your hands to the large and small intestine on the front of the abdomen. Ask for the power to see the cells of the intestines. Give them the command; **"Large and Small Intestine**, listen to the comm and Clear, clean and bright fill with violet light and return to normal function".
7. Move your hands to the kidney and sexual organs and ask for the power to see their cells. Give the command; **"Kidney and Sexual Organ Cells** listen to the command; Clear, clean and bright fill with violet light and return to normal function". Gather the violet light again and let it pour down and fill all the cells. See the violet light again and feel and see that all the cells are "clear, clean and bright". Smile.

K. Defense and Immune System

Defense System

1. Work on yourself first to activate your **Sacrum**. Project the sacrum as big as the universe. Breathe and compress the universal Chi into the sacrum until it rises up to fill your brain. Project out into the universe, multiply the energy and spiral it back down. Project it to the students and tell them to touch the sacrum.
2. Tell the students to move their hands to the **Hip Bones**. Tell them to smile to these bones. Feel them as 'funny, laughing, happy bones'. Tell them to feel the electricity in the sacrum and bone marrow.
3. Touch the **Femur Bones.** Feel the electricity running up the legs.
4. Touch the **Humerus Bones.** Feel the electricity running up the arms.
5. Touch the lower part of the **Sternum** and feel the Chi penetrate into the bones and spread out to the **Rib Cage**. Feel the electricity run throughout the rib cage.

resolve with reduction of dosage or discontinuation of the drug. Because no other health problems exist, it is reasonable to attribute his symptoms to digitalis intoxication. The step to take in this case is to measure the digitalis level in the blood and, if elevated, reduce the dose of digitalis. The patient should be monitored until the visual symptoms and fatigue are eliminated. Referral to an ophthalmologist is not necessary if the visual symptoms resolve.

3. **A** 25-year-old man makes an appointment to see you for complaints of difficulty breathing that developed after an injury. While playing basketball, he was knocked to the floor and struck his head. He went to the emergency room, where the only problem noted was a small hyphema in the right eye. He was seen by an ophthalmologist, who subsequently saw the patient for a return visit and instituted a pressure drop in the injured eye. The next day he developed shortness of breath and wheezing, and he asked to see you as he feared he may also have injured his chest when he fell. He thinks his parents told him he once had a brief episode of asthmatic bronchitis as a child, but he had previously felt this was not worth mentioning, as the condition required no chronic followup or therapy. What other history might be helpful for you in evaluating this patient's current symptoms? Would consultation with the ophthalmologist be necessary?

   Answer: The onset of symptoms suggestive of asthma or other obstructive airway disease after institution of an ocular anti-hypertensive drop should make the clinician highly suspicious that the patient has been placed on a topical beta-blocker. Systemic absorption of either selective or nonselective drops in this class may be sufficient to cause significant contraction of bronchial smooth muscle, especially in asthmatics. The ophthalmologist should be contacted to determine the exact ocular medication regime and to inform him or her about the development of the side effects. The topical beta-blocker should be discontinued immediately, but because the intraocular pressure could subsequently rise to a dangerous level, the ophthalmologist should be consulted to determine if further ocular assessment or alternative drop therapy is advised.

Annotated Resources

Elson WL, Fraunfelder FT, Fills JN, et al: Adverse respiratory and cardiovascular events attributed to timolol ophthalmic solution, 1978–1985. Am *J Ophthalmol* 1986;102:606–611. A good general overview of various ocular and systemic complications associated with Timoptic.

Fraunfelder FT, Roy FH, eds: Current *Ocular* Therapy 4. Philadelphia: WB Saunders Co; 1995. An extensive text written by approximately 70 contributing authors and edited by two experienced ophthalmologists. Coverage is wide and fairly detailed, with a good emphasis on drug complications.

Grant WM, Schuman JS: *Toxicology of the Eye.* 4th ed. Springfield, IL: Charles C Thomas; 1993. Another encyclopedic treatment. A prodigious and scholarly work, carefully documenting ocular and neuro-ocular side effects of numerous chemicals and drugs.

Hardman JG: *Goodman and Gilman's The Pharmacologic Basis of Therapeutics.* 9th ed. New York: Pergamon Press; 1996. One of the best basic science textbooks on drugs. Serves as an encyclopedic reference on drugs in general.

Mauger TF: *Havener's Ocular Pharmacology.* 6th ed. St Louis: CV Mosby Co; 1994. A readily comprehended book with good emphasis on side effects and complications.

McMahan CD, Shaffer RN, Hoskins HD, et al: Adverse effects experienced by patients taking timolol. *Am J Ophthalmol* 1979;88:736–738. A good general reference regarding potential side effects of Timoptic, including a specific case report of a patient similar to that in Sample Problem 3 in this chapter.

Physicians' Desk Reference for Ophthalmology. Oradell, NJ: Medical Economics Co; updated annually. A slim volume distilling from the encyclopedic *PDR* those drugs used by ophthalmologists. As in the parent volume, the text of the package insert for each drug is reproduced. Supplementary charts, tables, and flow charts of use to clinicians are included. Besides sections on ophthalmic lenses and low vision, the book contains a reprint of the American Medical Association's *Guide to the Evaluation of Permanent Visual Impairment.*

Schoene RB, Martin TR, Charan NB, et al: Timolol-induced bronchospasm in asthmatic bronchitis. *JAMA* 1981;245:1460–1461.

Trobe JD: *The Physician's Guide to Eye Care.* San Francisco: American Academy of Ophthalmology; 1993. Chapters 6 and 7 deal respectively with common ocular medications and with ocular side effects of systemic drugs.

Index

Note: Page numbers in *italics* indicate illustrations; tables are indicated by *t*.

A

Abducens nerve. *See* Cranial nerve VI
Abrasion
  corneal, management of, *85*
  and hyphema, *61*
Accommodation, *2,3*
Acetazolamide, 152
Acquired immunodeficiency syndrome (AIDS), ocular manifestations of, *129,* 139–40
Acute visual loss
  and cataract, *28*
  and corneal edema, *28*
  and functional disorders, 36
  giant-cell arteritis and, *34–35*
  hemianopia and, *35*
  and hyphema, *28*
  and inflammation, *29*
  ischemic optic neuropathy and, 34–35, *34*
  and macular disease, *30*
  media opacity and, *28–29*
  and neovascularization, 29, 30, 32
  optic neuritis and, *32–33*
  papilledema and, 33–34, *33*
  papillitis and, 33, *33*
  and retinal detachment, 29, *29*
  and retinal disease, *29–35*
  and retinal vascular occlusion, 30–32, *30*
  trauma and, *35*
  and visual pathway disorders, *35*
  and vitreous hemorrhage, *29*
Adenovirus, *68*
Adie's (tonic) pupil, *114*
Adnexal disease, *60*
Adrenergic-stimulating drugs (sympathomimetics), *148,152*
Adrenocorticosteroids. *See* Corticosteroids
Afferent pupillary defect. *See* Relative afferent pupillary defect
African Americans, eye disease in, 39, 42, 45*t*, *137*
Age-related macular degeneration, *49–52*
AIDS. *See* Acquired immunodeficiency syndrome
Allergic conjunctivitis, 65*t*, 66*t*, 67, 68, 69, 149
Allergy
  to drugs, 68, 72, 81, 146, 147, 151
  episcleritis and, *60*
  and erythema multiforme, *68*
Alpha-2 adrenoreceptor agonists, *151–52*
Amaurosis fugax, *30,121–22*
Amblyopia, 1, 94, 95–96
  examination for, 6, 98, 99–101
  form-deprivation (amblyopia ex anopsia), *96*
  as "lazy eye," *95*
  occlusion, *96, 106*
  refractive, *95–96,106*
  strabismic, *95*
  treating, in children, 105–06
Amiodarone, *154*
Amphotericin B, *141*
Amsler grid testing, 19, 52–54, *53*, 111
Anatomy, of the eye, 2–3, *4–5*
  cataract and, *46*
  glaucoma and, *41*
  macular, 3, *4, 14,* 16, *16,* 49–50, *50*
  pupillary pathways, *112*
  trauma and, 77–80, *78*
Anesthetic(s), topical, 6, *147*
  contraindications for, *88*
  diagnostic, 82, 82*t*, *83,147*
  for ocular irrigation, *87*
  to remove a foreign body, 85, 88
  for tonometry, 18
Aneurysm
  and acute visual loss, *29*
  carotid, associated with Horner's syndrome, *115*

- Aneurysm *(continued)*
  - and eye disease, *1,110,114,115*
  - intercranial, and cranial nerve paresis, *117*
- Angiography, fluorescein, *50*, 51, 52, *52*, 54, 131
- Angle-closure glaucoma, 6, 12, 17, 18, 23, 27
  - acute
    - as an ocular emergency, 40, 44, 58
    - ciliary flush and, *65*
    - drugs for, contraindicated, *149*
    - halos and, *68*
    - IOP and, 63, 67
    - pain and, *68*
    - pupil in, *66*
    - pupillary reflex and, *28*
    - and red eye, 59, *59*, 65*t*, *66t*
  - contraindication for dilation of pupils in, 12, 84
  - and corneal edema, *28*
  - diagnosing, 42–44, *59*
  - and red eye, *67*
- Ankylosing spondylitis, iritis and, *138*
- Antazoline, *148*
- Anterior chamber
  - anatomy of, 2, 4, *41*
  - angle, *41*, 42
  - depth assessment of, 6, 12, 18–19, *18*, 62, 82
  - injury to, *79*
  - opacity of, and acute visual loss, *28*
  - and red eye, 65*t*, *66–67*
  - shallow, 23, 65*t*, 66–67, 90
- Antibiotic(s), *149*
  - for conjunctivitis, 69, 71, 149
  - for corneal abrasion, *85*
  - ointment, for eye injury, *88*
  - for sties, *70*
  - use of, with corticosteroids, *72,149*
- Anti-inflammatory drugs, *149*
- Apraclonidine, *151*
- Aqueous humor, 2, 16, 40, 79
  - anterior chamber trauma and, *79*
  - intraocular pressure and, 16, 40
- Argyll Robertson pupil, *115*
- Arteriolar sclerosis, and hypertensive retinopathy, 134–36
- Arteriosclerosis, vascular, and central retinal artery occlusion, *32*
- Arteriovenous (A/V) crossing patterns, *15*, *134–35,135*
- Arteritis. *See* Giant-cell (temporal) arteritis
- Arthritis. *See* Rheumatoid arthritis
- Artificial tears, use with dry eyes, *138*
- Asthma, side effects from drugs and, *150,153*
- Astigmatism, *3*
- Atheroma, and amaurosis fugax, *30,121–22*
- Atropine sulfate, *88,147,154*
- Autoimmune disorders
  - Graves' disease, *136–37*
  - myasthenia gravis, *118*
  - rheumatoid arthritis, *138,153*
- A/V crossing patterns. *See* Arteriovenous crossing patterns

B

- Bacterial infections
  - conjunctivitis, 65*t*, 66*t*, 67, 69, 71
  - endocarditis, subacute, *140*
  - staphylococcal blepharitis, *69*, *70*
- Basal cell carcinoma, red eye and, *60*
- BCNU (carmustine), *139*
- Behçet's disease, iritis and, *138*
- Bell's palsy, as red eye cause, *61*
- Beta-adrenergic blockers, *150*
- Betaxolol hydrochloride, *150*
- Biomicroscopy, *7,131*
- Blepharitis, 60, 69–70, *70*
- Blindness
  - cortical (central, cerebral), 10, 35
  - diseases causing, 1, 69, 129
  - erythema multiforme and, *68*
  - as a side effect of corticosteroids, *72*
  - snow, treating, *86*
  - and strabismus, *97*
  - sudden. *See* Acute visual loss
  - testing for fake, *10*
- Blind spot. *See* Scotoma
- Blink reflex, topical anesthetics and, *72*
- Blood pressure, hypertensive retinopathy and, *135,136*
- "Blood and thunder" fundus, *31–32*
- Blowout fracture, 78, 97
  - testing for, 83*t*, *84*
- Blurred vision
  - and diplopia, *116*
  - latent syphilis and, *141*
- red eye and, 66*t*, *67*

Note: Page numbers in *italics* indicate illustrations; tables are indicated by *t*.

Bony orbit. *See* Orbit
"Boxcarring," *30*
Bradycardia, and glaucoma drugs, *150*
Brain tumor
  and eye disease, *1,110,117,120*
  and optic nerve changes, 40, 43
  papilledema and, *121*
Branch retinal artery occlusion, *31*
Branch retinal vein occlusion, *135*
Breast cancer, ocular metastases from, *138*
Brimonidine tartrate, *151*
Bruch's membrane, 50, 51
Bruit, examining for, *84*
Burn
  chemical, emergency treatment of, *85,* 86–87, 90
  radiant energy, treatment of, *86*
  radiation. *See* Radiation, damage from

Canaliculi, *5,* 78, 86, *87*
Canal of Schlemm. *See* Schlemm's canal
Cancer, ocular, *138–39. See also specific types,* Carcinoma
Candidiasis, ocular, *140,141*
Carbonic anhydrase inhibitors, *150,152*
Carcinoma
  basal cell, and red eye, *60*
  meibomian gland, *71*
  squamous cell, and red eye, 60, 71
Cardinal fields of gaze, testing, 12, 12*t*, *102*
Carmustine (BCNU),*139*
Carotid aneurysm, 115
Carotid artery occlusion, central retinal vein occlusion and, *32*
Carotid-cavernous sinus fistula, *84*
Carotid dissection, associated with Horner's syndrome, *115*
Carteolol, *150*
Cataract, 1, 46, 55, 116
  appearance of, *4849*
  causes of, *46*
  congenital, *98*
  color, perception of, and, *48*
  cortical, *46*
  corticosteroids and, 48, 72, 153, 155
  examination for, *4849*
  and form-deprivation amblyopia, *96*
  immature, 46, *47*
  injury to the lens and, 80, 84
  intraocular lens and, *13*
  iritis and, *138*
  mature, 46, *47*
  nuclear, 46, *47*
  and radiation of tumors, *139*
  signs of, *104*
  subcapsular, 46, 48
  surgery, and corneal edema, *28*
  symptoms of, *4648*
  testing for, *105*
  and visual loss, *28,4549*
Cavernous sinus
  CT imaging of, *86*
  disease of, *67*
Central nervous system (CNS), *120,138,139*
Central retinal artery, 4, 14–15, *16*
  occlusion of, *31*
Central retinal vein, 4, *14,* 15, *16*
  occlusion of, *31–32*
Cerebral artery, occlusion of, *123*
Chalazion, *70–71, 71*
Chart. *See* Snellen eye chart; Tumbling E chart
Chemical bum, emergency treatment for, *85,* 86–87, 90
Chemotherapy, ocular effects of, *139*
"Cherry-red spot," retinal occlusion and, *30,* 31
Chiasm, optic
  compression of, *111*
  lesions of, visual field defects and, *123,124, 125*
Children. *See also* Infants
  amblyopia in, 94, 95
  concomitant strabismus in, *97*
  cortical blindness in, from head trauma, *35*
  cycloplegics for, *147*
  esotropia in, *98*
  eye examinations in, 6, 98, 99–105
  internuclear ophthalmoplegia in, *119*
  leukemia in, and ocular adnexal metastases, *138*
  proptosis in, *67*
  rheumatoid arthritis in (juvenile),*138*
Chloroquine phosphate, *153*

Note: Page numbers in *italics* indicate illustrations; tables are indicated by ***t***.

Cholinergic-blocking drugs (parasympatholytics) (cycloplegics), 85, 88, 147
Cholinergic-stimulating drugs, 150–51
Chorioretinitis, 137
  and acute visual loss, 29
  syphilitic, 140,141
Choroid
  anatomy of, 2, 3, *4*, 14, 16, 80
  cancer in, 138
  degeneration of, 50
Choroiditis, and secondary syphilis, 141
Chromatopsia, digitalis-induced, 153
Chronic visual loss, 39–57. See also Visual loss
  acute discovery of, 36
  in cataracts, 4549
  in glaucoma, 39-45
  in macular degeneration, 49–54
Ciliary body
  anatomy of, 2, *4*, *41*
  cycloplegia and, 147
  inflammation of, 137
  prolapse of, and perforating injury, 90
Ciliary flush, and red eye, 59, *59*, 62, 65, 65*t*, 66
Ciliary ganglion, lesion in, 114
Ciliary muscles, 41
CMV retinitis. See Cytomegalovirus retinitis
Cobalt-blue light source, 21,146
Cocaine test, for Horner's syndrome, 115
Color vision testing, 7, 19
Concomitant (nonparalytic) strabismus, 96–97, 96,102
Compress, 70, 71, 148
Computed tomography (CT), 33, 35, *81*, 84, 85, 86. See also Radiology, examination by
Confrontation field testing, 6, 19, 27, 111
Congenital anomalous disc elevation, 120–21
Conjunctiva
  anatomy of, 2, *4*, *41*
  bulbar, 2
  damage to, 79, *85*
  discharge from, 62, *62*, 67, 68
  foreign body in, 85, *86*
  hyperemia of, and red eye, *60*, 65, 65*t*, 67, *79*
  inspection of, 10
  microangiopathy of, 139
  palpebral, 2
  scarring of, 68
Conjunctivitis, 60
  allergic, 65*t*, 66*t*, 67, 68, 69, 149
  bacterial, 65*t*, 66*t*, 67, 69, 71
  chronic, *61*, 67
  erythema multiforme and, 68
  gonococcal, 69
  laboratory diagnosis of, 69
  pain and, 68
  purulent, *62*, 69
  and red eye, 58, 59, 64, 65*t*, 66
  treatment of, 71–72
  and upper respiratory tract infection and fever, 68
  viral, 65*t*, 66*t*, 67, 69, 71–72
  visual acuity and, 72
Contact lenses
  examination for prolonged wearing of, 83
  fluorescein staining and, 20,146
Copper-wire arterioles, 134
Cornea
  abrasion of, treating, 85
  anatomy of, 2, *4*, *41*
  calcification of, and iritis, 138
  damage to, 79,147
  deposits on, drug-induced, 153,154
  edema of, 28, *59*, 62, *63*, 66, 68, *86*
  effect of corticosteroids on, 48, 72, 154
  endothelium
    dystrophy and, 28
    keratic precipitates on, 66
  epithelium
    to anesthetize, 147
    damage to, 79, *85*, 147
    defective, 21
    herpes zoster ophthalmicus and, 141
    and red eye, *60*, 62, *63*, 65*t*, 66, 72
    testing, 20–21, *21*, 62, 72
    topical anesthetics and, 72, 88
  examination of, 10, 66
  fluorescein staining of, 20–21, *21*
  foreign body in, 85, *86*
  inflammation of, and red eye, 58, 59, 64, 65, 68. See also Keratitis
  leukoma of, 62, *63*
  light reflex of, 98, *99*, 102, *102*, 104. See also Cornea, reflection from, irregular
  opacity of
    and acute visual loss, 28

Note: Page numbers in italics indicate illustrations; tables are indicated by t.

    and red eye, 62, 65–66, 65*t*
    and syphilis, 141
  optics and, 3
  perforation of, 79
  reflection from, irregular, *59*, 62, *63*, 66, 79. See also Cornea, light reflex of
  ulcer of, 62, *64*, 66, 68
Corticosteroids
  and cataracts, 48, 72, 153, 155
  combined with antibiotics, 72,149
  contraindicated, 72,149,153,155
  giant-cell arteritis and, 34
  for glaucoma, 45t
  optic neuritis and, 32
  to relieve inflammation, 149
  side effects of, 72,149,153,155
  for uveitis, 137–38
Cotton-wool spots
  in AIDS retinopathy, 139–40,139
  hypertensive retinopathy and, 135
  NPDR and, 131,131
  retinal vein occlusion and, 31, *32*
  subacute bacterial endocarditis and, 140
  systemic candidiasis and, 140
Counting fingers (CF), as visual acuity test, 8, 82,111
Cover test, 98, 103–04, *103*
Cranial nerves
  III (oculomotor), 2, *97*, 113, 114
    herpes zoster and, 142
  IV (trochlear), 2
  V, 118,141
  VI (abducens), 2, *97*, *119*
  VII, 118
  VIII, 118
  paresis (palsy) in, 117–18,117,118,138
    111,117,117
    IV, 117–18
    VI, 118,118,138
    and nystagmus, 103
    and strabismus, 97, *97*
CSME. See Macular edema, clinically significant
CT. See Computed tomography
Cup:disc ratio, 43, *43*, 44, *44*, 55
Cup of the optic disc. See Physiologic cup
Cupping, glaucomatous, 43, *44*, 55
Cyclomydril, 105,148
Cyclopentolate, 88,104,147,148
Cycloplegia, cholinergic-blocking drugs causing, 147
Cycloplegics. See Cholinergic-blocking drugs
Cytomegalovirus (CMV) retinitis, 129,139, 140,140
Cytosine arabinoside, 139

D

Dacryocystitis, 60, 61
DCCT. See Diabetes Control and Complications Trial
Death
  drug-induced, 149,151
  PDR and, 133
Decongestants, ocular, 148–49
Dermatitis, as a side effect of apraclonidine, 151
Deviation. See Amblyopia; Strabismus
Diabetes Control and Complications Trial (DCCT),133
Diabetes mellitus, 130–33
  and cataract, 48
  and cranial nerve paresis, 117,118
  and eye disease, 1, 6, 45*t*
  hyphema and, 28
  insulin-dependent (IDDM; Type I), 130,133
  non–insulin-dependent (NIDDM; Type 11), 130,133
  retinopathy and. See Diabetic retinopathy
  visual loss and, 129
  and vitreous hemorrhage, 29
Diabetic retinopathy, 1,129,130–33,142
  anemia and, 132
  cardiovascular disease and, 133
  nonproliferative (NPDR),130–31,130,131
  pregnancy and, 133
  proliferative (PDR), 131–32, *132*
Diagnostic drugs, topical ocular, 146–48
Dichlorphenamide, 152
Diclofenac, 149
Digitalis, 153
Dilation, pupillary. See Pupil, dilation of
Diphenylhydantoin, 120,154
Dipivefrin, 152

Note: Page numbers in *italics* indicate illustrations; tables are indicated by t.

Diplopia (double vision), 78
  and blurred vision, 116
  in children, 98
  and cranial nerve paresis, 117–18
  drug-induced, 154
  examination for, 81, 83*t*
  and giant-cell arteritis, 34
  herpes zoster and, 142
  injury and, *78*, 83*t*, 84
  and myasthenia gravis, 118
  and ocular motility, 113,115–18
  sample examination for, 82, 83*t*
  strabismic amblyopia and, 95
  and thyroid disease, 137
Disability, visual, 9
Discharge, 67. See also Exudate
  conjunctival, and red eye, 62, 65*t*, 67
  mucopurulent, 62, 67
  purulent, 62, *62*, 67, 69
  serous, 62, 67
Dorzolamide, 152
Double vision. See Diplopia
Drugs. See also specific types
  anesthetic. See Anesthetic(s), topical
  antibiotic. See Antibiotic(s)
  anti-inflammatory,149
  decongestant, 14849
  dilating, for ophthalmoscopy, 12–13
  diagnostic, 14648
  for glaucoma, side effects of, 150–52
  mydriatic, *6*, *104–05*, *115*, 147–48, 154
  for ocular injuries, 88
  systemic, ocular side effects of, 153–54
  therapeutic, 148–49
  topical, instillation of, 14546
Drusen (hyaline nodules), 50–51, *50*, 54, 120,
    121
Dry eye(s). See Keratoconjunctivitis sicca
Dura mater, 4
Dye
  fluorescein. See fluorescein dye
  indocyanine green, 51

Echothiophate iodide, 151
Edrophonium chloride (Tensilon) test, 118
Efferent pupillary defect, 113,114
Embolism
  and eye disease, 1
  and retinal artery occlusion, 31
Emergency, ophthalmic. See also Urgent
    treatment
  acute angle-closure glaucoma as, 40
  central retinal artery occlusion as, 31
  chemical burns as, 85, 87–88
Emphysema, of the eyelids, subcutaneous, 78
Epicanthus (pseudostrabismus), *101*, 101–02
Epinephrine hydrochloride, 152
Epiphora (chronic tearing), 78
Episcleritis, red eye and, 59, *60*
Erythema multiforme, and red eye, 68–69
Erythromycin, 149
Esophoria, 98, 98*t*, 104
Esotropia, *96*, *98*, 98*t*
  with concomitant strabismus, 96
  congenital, 106
  corneal light reflex and, 102,102,104
  cover test for, 103
  glasses for, 106
  small-angle, 104,104
  treating, 151
Ethambutol, 154
Examination. See also specific *types;* Tests
  for acute visual loss, 27, 29
  basic, 6–21, 23
  for cataract, 4849
  of children, 102–03
  for double vision (sample), 81, 83*t*
  equipment for, *6*, *7*, *8*, *11*
  external, 10, 82–83
  extraocular movement, 6
  for foreign-body sensation (sample), 81, 82*t*
  for glaucoma, 42
  for injury, 80–84
  for macular degeneration, 52–54
  neuro-ophthalmic, 110–14
  optic disc, 13–14, 42–44, *44*
  for proptosis, 67
  pupillary reaction, 6, 10
  for red eye, 62–63, 66
  retinal circulation, 14–16
  slit-lamp, 29, 49, 141
  visual acuity, 6, 7–10
Exophoria, 98*t*, 104
Exophthalmos. See Proptosis

Note: Page numbers in italics indicate illustrations; tables are indicated by t.

- Exotropia, 98, 98*t*, *99,104,106*
- External examination, 10, 82–83
- Extraocular muscles, 2, *5*, 12, 12*t*, *113,138*
  - oblique, 2, *5*, 12
  - rectus, 2, *5*, 12, *97*
- Exudate. See *also* Discharge
  - NPDR and, *130*
  - red eye and, 66*t*, *68*
  - subretinal, and macular degeneration, *54*
- Eye
  - anatomy of, 2–3, 77–80, *78*
  - cross-section of, *4*
  - examination of, 6–21, 23
  - external landmarks of, 5
- Eyeball. See Globe
- Eyedrops
  - dilating, *114*
  - to instill, 145–46, *146*
- Eyeglasses
  - aphakic, for cataract, *46*
  - for presbyopia, *3*
  - for refractive amblyopia, *106*
  - for strabismus, *106*
- Eyelid
  - abnormality in, and red eye, *61*
  - anatomy of, 2, *5*, 78
  - emphysema, subcutaneous, of, *78*
  - eversion of, 7, 20, *20*, 82–83, *86*
  - function of, *78*
  - inflammation of, and red eye, 68, 69–70
  - injury to, *78*
  - inspection of, *10*
  - laceration of, as an urgent situation, 86, *87*, *89*
  - lesions of, and red eye, 60, 61
  - malfunctioning, and red eye, 63
  - mass on, biopsy for persistent, *71*
  - ptosis of, *115,115,117,118*

- Fibrosis, 51, *63*, 134
- Field of vision. See Visual field
- Fluorescein angiography, *50*, 51, 52, *52*, 54, 131
- Fluorescein dye, *146*. See *also* Fluorescein angiography
  - to instill, *146*
  - precautions for, *20*
  - staining with, 7, 20–21, *21*, 66, 85, *85*, *141*
  - strips, *6*, 20, 146
- Fluoroquinolones, *149*
- Flurbiprofen, *149*
- Foreign bodies
  - detecting, 20, 80, *81*, 84, *86*
  - iron, *86*, 88
  - red eye and, *61*
  - removal of, *88,147*
  - sensation of. See Foreign-body sensation
- Foreign-body sensation
  - examining for, 81, 82*t*
  - thyroid disease and, 136–37
- Form-deprivation amblyopia, *96*
- Fovea, 3, *4*, *16*, 50, *50*
  - and acute visual loss, *31*
- Foveal reflex, 16, 50, 54
- Functional disorders, *36*
- Fundus, retinal, 2, 16, *16*. See *also* Retina
  - abnormal appearance of, *22*
  - "blood and thunder," *31–32*
  - examination of, 6, 48, 65, 84, 114, 142
  - fluorescein angiogram of, *50*, *52*
  - normal, *14*
- Fusion. See Vision, binocular

G

- Gaze
  - cardinal fields of, testing, 12, 12*t*, *102*
  - direction of, and strabismus, 96, *96*, 97, *97*
  - limitation of, *113*
  - nystagmus and, *119*
- Geniculate body, and visual field defect, *124,125*
- Giant-cell (temporal) arteritis, *34–35*, *110*, *122*
  - and eye disease, *1*
  - and syphilis, *141*
- Glare, chloroquine-induced, *153*
- Glaucoma, 1, 39–45, 55, 98, 122
  - acute angle-closure. See Angle-closure glaucoma, acute
  - drugs for, side effects of, *150–52*
  - examination for, *42*
  - gonioscopy for, *42*
  - IOP and, 17, 40, 63, 67
  - iritis and, *138*

Note: Page numbers in *italics* indicate illustrations; tables are indicated by *t*.

- Glaucoma (continued)
  - neovascularization and, 131
  - open-angle. See Open-angle glaucoma
  - risk for, 44, 45*t*
  - steroid-induced, 153,155
  - testing for, 6, 17, 42
- Glaucomatous cupping, 43, *44*, 55
- Glioma
  - optic nerve, 123
  - pontine, 119
- Globe
  - damage to, 79
  - ruptured, 18, *86*
  - shielding, 89, *89*
- Glycemia, control of, and diabetic retinopathy, 132,133
- Gonioscopy, 42
- Gonococcal conjunctivitis, 69
- Granuloma, focal noncaseating, in sarcoidosis, 137
- Graves' disease, 136

H

- Halos
  - digitalis-induced, 153
  - in glaucoma, 39, 40, 68
  - red eye and, 66*t*, 68
- Hand motions (HM), as visual acuity test, 8, 10, 82
- Hay fever, and red eye, 68
- Heart attack. See Myocardial infarction
- Hemianopia, 122
  - and acute visual loss, 35
  - altitudinal, 122
  - bitemporal, 122,123
  - homonymous, 27, 35, 122, 123
  - and occlusion of cerebral artery, 123
- Hemorrhage
  - into the anterior chamber, 62, 79
  - into the vitreous cavity, 29, 84, 131, 133
  - neovascularization and, 51, *51*
  - retinal, 80, 84, 135
  - subarachnoid, 29
  - subconjunctival
    - and red eye, 58, 61, 62, 71
    - as semiurgent, 87, *87*
  - subretinal, 51, *51*, 52, *52*, 54
- Heredity
  - and macular degeneration, 52
  - strabismus and amblyopia and, 99
- Herpes simplex keratitis, 28
  - AIDS and, 139
  - and red eye, 59, *60*
  - as a side effect of corticosteroids, 72,149
- Herpes zoster ophthalmicus, 139,14142,141
- Heterophoria, 97, 98, 98*t*
- Heterotropia, 97–98, 98*t*, 99
- HIV. See Human immunodeficiency virus
- Homatropine hydrobromide, 88,147
- Hordeolum. See Stye
- Homer's syndrome, 115,115
- Human immunodeficiency virus (HIV), 140
- Hyaline nodules. See Drusen
- Hydroxyamphetamine, 115
- Hydroxychloroquine sulfate, 153
- Hyperemia, conjunctival, 58, *60*, *62*, 65, 65*t*, 79. See also Red eye
- Hypermetropia. See Hyperopia
- Hyperopia, 3, 45*t*, 96,106,120
- Hyperphoria, 98t
- Hypertension, 134–36
  - and central retinal artery occlusion, 32
  - and cranial nerve paresis, 117,118
  - diagnosis of, 135–36
  - drug-induced, 148
  - and eye disease, 1, 45*t*
  - malignant, 135,135
  - and papilledema, 121
  - retinopathy and, 132,134–36
- Hypertropia, 98*t*, 99,104
- Hyphema
  - and acute visual loss, 28
  - contusions causing, 79, *79*, 82
  - and corneal abrasion, 61
  - and red eye, 62, *79*
  - shielding, 89, *89*
  - as symptom, 86
  - trauma and, *79*, 84
  - as urgent situation, 85–86
- Hypophoria, 98t
- Hypopyon, corneal ulcer and, 62, *64*
- Hypotension, and glaucoma drugs, 150,151
- Hypotropia, 98*t*, 99,104

Note: Page numbers in italics indicate illustrations; tables are indicated by t.

Immune System

1. The Immune system starts with the top part of the **Sternum**. Touch the top part of the sternum. Project your fingers ‘very long’ into the bone and feel them penetrate right into the **Thymus**. Activate the thymus gland. Gradually, feel the fingers rising up to the thyroid and parathyroid. Activate the **Thyroid** and **Parathyroid** and **Throat Center**. Give the command; “Clear, clean and bright fill with violet light and return to normal function”.
2. Move the fingers to touch both sides of the **Jaw Bones** to help activate the **Tonsils,** the body’s first line of defense. The jaw bone affects the **Lymph Nodes** beneath, which includes the tonsils. Fill them with Chi. Give the command; “Clear clean and bright fill with violet light and return to normal function”.
3. Touch the **Mideyebrow** and **Crown**, which control the **Pituitary** and **Pineal Glands** respectively. Touch the third eye, feeling it open and feel the light from heaven entering into your brain and into your body. Touch the crown. Feel your fingers reaching deep inside and feel the Chi penetrating all the way down to your perineum. Fill the glands with Chi. Give the command; “Clear, clean and bright fill with violet light and return to normal function”.
4. Rub both of your hands until they are warm. Cross your arms and hold your hands under your **Armpits**. Picture the **Lymphatic System** of the armpits as you activate the lymph nodes. Give the command; “Clear, clean and bright fill with violet light and return to normal function”. The lymphatic system of the upper body is clear, clean and bright then the lymphatic fluid flows! Smile.
5. Move the hands to the cover the **Groin** area. Give the command to the **Lymph Nodes** there. Give the command; “Clear, clean and bright fill with violet light and return to normal function”.
6. Place your palms over your **Navel** and activate the **Lymph Nodes**. Give the command to the lymph nodes there. Give the command; “Clear, clean and bright fill with violet light and return to normal function”. **You have now activated the immune system.**

IDDM. See Diabetes mellitus, insulin-dependent
Impairment, visual. See Visual acuity impairment
Incomitant (paralytic or restrictive) strabismus, 96, 97, *97*, 102, 113
Indocyanine green dye, 51
Infants. See *also* Children
  contraindications of drugs for, 151
  eye examination in, 99–100
  mydriatics for, 148
  strabismus in, 101,106
Infection
  bacterial. See Bacterial infections
  corneal edema and, 28
  fungal, from corticosteroids, 149
  orbital, and red eye, 67
  systemic, and ocular manifestations, 141–42
Inflammation
  and acute visual loss, 29
  cataract and, 46
  chronic, and hyphema, 28
  conjunctival, 61, 68
  corneal, and red eye, 58, 65, 68
  drugs to relieve, 149
  edema, corneal, and, 28
  eyelid, 68, 70, 71
  idiopathic, 29
  intraocular, and red eye, 58, 59
  iris, 137
  optic nerve, 43
Injury, ocular. See *also* Trauma
  medications for, 88
  perforating, 80, 82, 90
    as a contraindication for lid eversion, 83
    treating, 85, 87–89
Instillation of topical drugs, 14546
Internuclear ophthalmoplegia, 119
Intraocular lens (IOL), 13, 46, 49
Intraocular pressure (IOP)
  drugs to reduce, side effects of, 151,152
  elevated, 23, 65*t*, 67, 68, 72
  and glaucoma, 27, 40, 42, 44
  normal range for, 17, 40
  and the optic nerve, 41–42
  and red eye, 63, 65*t*, 67, 68
  testing, 16–18, 42
IOL. See Intraocular lens
IOP. See Intraocular pressure
Iridocyclitis
  IOP and, 67
  and pain, 68
  and red eye, 59, *62*, 65*t*, 66, 66*t*
Iris
  anatomy of, 2, *4*, *5*, *41*
  inflammation of, 137
  examination of, 10
  neovascularization of, 131
  prolapse of, 79, *79*, 82, 90
Iritis
  acute, 28
  and cataract, 138
  juvenile rheumatoid arthritis and, 138
  photophobia and, 68
  and red eye, 59, *59*, 66
  secondary syphilis and, 141
  trauma and, 79
Irrigation, procedure for ocular, 87–88, *88*
Ishihara plates, 19. See *also* Color vision testing
Itching, ocular
  relief of, 149
  as a symptom of conjunctivitis, 66*t*, 68

J

Jaw claudication, in giant-cell arteritis, 34
Juvenile rheumatoid arthritis, 138

K

Kaposi's sarcoma, 139,140
Keratitis. See *also* Cornea, inflammation of; Herpes simplex keratitis
  acute interstitial, and congenital syphilis, 14041
  fungal, as a side effect of corticosteroids, 72
  herpes zoster ophthalmicus and, 142
  and red eye, 65*t*, 66, 66*t*, 68
  superficial, chemotherapy and, 139
Keratoconjunctivitis sicca (dry eye)
  and red eye, 61, 67
  and sarcoidosis, 138
Keratouveitis, 14041
Ketorolac, 149

Note: Page numbers in *italics* indicate illustrations; tables are indicated by *t*.

L

Lacrimal apparatus, function of, 78
Lacrimal puncta, *5*, 78
Lacrimal sac, 5
Laser surgery
  for A/V nicking, 135
  for hypertensive retinopathy, 135
  for neovascularization, 30, 32, 54, 55, 131, 133
  for PDR, 132–33,133
Latanoprost, 152
"Lazy eye." *See* Amblyopia
Learning disorders, amblyopia and, 95
Lens (crystalline lens)
  anatomy of, 2, *4*, 46
  capsules, 41
  cataract and, 46, 49, 84
  color of, 46
  dislocation of. *See* Lens, subluxation of
  effect of radiation on, 139
  hydration of, 28
  injury to, 80, *80*, 84, 86
  intraocular, cataract and, 46
  opacity of
    and acute visual loss, 28
    and cataract, 46, 47, *47*, 49
  optics and, 3
  subluxation of, 80, *80*
Lens, intraocular, 13, 46, 49
Leukemia, ocular manifestations of, 32,138–39
Leukocoria ("white pupil"), *47*, 48, 104, *105*
Leukoma, corneal, 62, *63*
Levobunolol, 150
Levocabastine, for allergic conjunctivitis, 149
Lid. *See* Eyelid
Light perception (LP), testing of, 9, 82
Light reaction, pupillary, 11, 27, 111–13, *112*, 113
Light reflex, corneal. *See* Cornea, light reflex of
Light sensitivity. *See* Photophobia
Limbus, 2, *4*, *5*, *41*, *79*
Lodoxamide, 149
Low vision, 9t
  distance acuity testing in, 8–9
  services for patients with, 54–55
Lung cancer, ocular metastases from, 138
Lupus erythematosus, 138,153
Lymph node, preauricular enlargement of, and red eye, *65t*, 67
Lymphoma, ocular manifestations of, 32,138

M

Macula
  anatomy of, 3, *4*, *14*, 16, *16*, 49–50, *50*
  damage to, 80,153
  diseased, 29, 30, 130
  edema of, 130–31, 149
Macular degeneration, 1, 49–55
Macular edema, clinically significant (CSME), 130–31,149
Magnetic resonance imaging (MRI). *See also* Radiology
  contraindicated, for detecting metal foreign bodies, 84
  hemianopia and, 35
  papilledema and, 121
  retrobulbar optic neuritis and, 33
Malignancy, ocular manifestations of, 138–39
Marcus Gunn pupil. *See* Relative afferent pupillary defect
Mattering. *See* Discharge
Medications. *See* Drugs
Meibomian glands, 2
  carcinoma of, 71
  inflammation of (chalazion), 70–71, *71*
Meningioma, and eye disease, 1,122,123
Metabolism
  defects of, and cataract, 46, 48
  changes in, and macular degeneration, 52
Metamorphopsia, and visual loss, 30, 48, 50, 54
Metapranolol, 150
Methazolarnide, 152
Methylprednisolone, 86
Microangiopathy, conjunctival, in AIDS, 139
Miosis
  in acute iritis, 28, 79
  prevention of, in surgery, 149
Moll, glands of, 70
Molluscum contagiosum, and red eye, 60
MRI. *See* Magnetic resonance imaging
Multiple sclerosis, and eye disease, 1, 32, 110, 120
Muscle(s)
  ciliary, 41
  extraocular. *See* Extraocular muscles

Note: Page numbers in *italics* indicate illustrations; tables are indicated by *t*.

Myasthenia gravis, 118
Mydriasis. See Pupil, dilation of, drugs for
Mydriatics, *6*, 12, 104–05, 147–48, 154
Myocardial infarction
  drug-induced, 148
  and PDR, 133
Myopia, 3
  and glaucoma risk, 45t
  lenticular, and cataract, 47
  pigmentation and, 14
  strabismus and, 106

N

Naphazoline, 148,149
Narrow-angle glaucoma. See Angle-closure glaucoma, acute
Nasolacrimal duct, 5
National Eye Institute, 129
Near vision card, *6*, 10
Neomycin, 149
Neovascularization (retinal neovascularization)
  and acute visual loss, 28, 29, 30, 32
  laser surgery for, 30, 32, 54, 55, 131, 133
  PDR and, 131,132
  sickle cell disease and, 133
  subretinal, and chronic visual loss, 51, *51*, 54, 55
Nephropathy, diabetic, and PDR, 133
Nerve. See also Sympathetic nervous pathway to eye
  abducens. See Cranial nerve VI
  cranial. See Cranial nerves
  facial, paresis of, 78
  oculomotor. See Cranial nerve III
  optic. See Optic nerve
  retinal, myelination of, 14, *15*
  trochlear. See Cranial nerve IV
Neuritis, optic, 32–34,122,123,142
  anterior. See Papillitis
Neuro-ophthalmic examination, 110–14
Neuropathy, optic
  drug-induced, 154
  ischemic, 121,122,123
    and acute visual loss, 34–35, *34*
  and neurosarcoidosis, 138
  traumatic, 78, 86
  unilateral, 123
  vincristine injections and, 139
Neuroretinitis, 141
Neurosarcoidosis, 138
Neurosyphilis, 141
Nicking, in A/V crossing patterns, 134,135
NIDDM. See Diabetes mellitus, non–insulin-dependent
Niemann-Pick disease, and retinal vascular occlusion, 31
Nonsteroidal anti-inflammatory drug, 149
Notation, of visual acuity, 7–9
NPDR. See Diabetic retinopathy, nonproliferative
Nuclear sclerosis, cataract and, 47
Nutrition, defective, and cataract, 46
Nystagmus
  drug-induced, 120,154
  and neuro-ophthalmology, 119–20
  in ocular motility testing, 113
  in strabismus testing, 102–03

O

Oblique muscles, 2, *5*, 12
Occipital lobe, 111, 125
Occlusion amblyopia, 96,106
Ocular motility
  blowout fracture and, 84
  cranial nerve paresis and, 117–18
  disorders in, 115–20
  and proptosis, 64, 67, 84
  testing, 12, 84, 100, 113
Oculomotor nerve. See Cranial nerve III
Open-angle glaucoma, 40, 59, 149. See also Glaucoma
Ophthalmoplegia
  distinguishing from strabismus, 113
  drug-induced, 154
  internuclear, 119,119,120
Ophthalmoscope, direct, 6
Ophthalmoscopy, 6, 12–13
  and acute visual loss, 27
  cataract and, 48, 49
  for corneal opacification, 65
  direct, procedure for, 12–13

Note: Page numbers in *italics* indicate illustrations; tables are indicated by *t*.

Ophthalmoscopy *(continued)*
  glaucoma and, 42
  indirect, 131
  for macular degeneration, 54
  for media opacities, 98
  for neuro-ophthalmologic disease, 114
  for strabismus, 105
  trauma and, 84
Optic atrophy, 122,122
Optic chiasm. See Chiasm, optic
Optic cup. See Physiologic cup
Optic disc, 33. See also Optic nerve
  anatomy of, 2, 3, *4*, *16*, 41
  appearance of, 42–43, *44*, 114, 122
  cup of. See Physiologic cup
  edema of, 43
  elevation of, 120–21
  examination of, 13–14, 42–43, *44*
  malignant hypertension and, 135,135
  normal, 14,122
  optic neuritis and, 32
  pallor of (in optic atrophy), 122,122
  pigmentation and, 14, *15*
  retinal artery occlusion and, 31
Optic nerve, 3, *4*, 41, *43*. See also Optic disc
  cancer in, 138
  damage to, 42, *72*, *78*, 84
  disease of, 3235,120–22
  glaucoma and, 40, *43*, *44*
  and IOP, 41-42
  lesion in, 27,113,123,124,125
  thyroid disease and, 137
Optic neuritis, 32–34, 122, 123, 142
Optics, 3
Optic tract, damage to, 123,124,125
Orbit
  anatomy of, 77–78, *78*
  floor of, blow out and, 78
  fracture in, 84, 87
  vascular lesions in, and red eye, 60

PQ

Pain
  in acute angle-closure glaucoma, 40
  in jaw, in giant-cell arteritis, 34
  in retrobulbar optic neuritis, 33
  severe, and red eye, 66*t*, 68
  syphilitic uveitis and, 141
  trauma and, 79
Palpation, eye
  for glaucoma diagnosis, reliability of, 42
  in trauma evaluation, 82, 90
Palpebral fissure, 2, 10
Palsy. See Paresis
Papilledema, 33,121,121,122
  acute visual loss and, 33–34, *33*
  glaucoma and, 43
  myelination mistaken for, 15
Papillitis (anterior optic neuritis), 33, *33*, 121, 141
Paracentesis, anterior chamber, 31
Parasympatholytic drugs. See Cholinergic-blocking drugs
Paresis (palsy)
  cranial nerve, 117–18,117,118,138
    and nystagmus, 103
    and strabismus, 97, *97*
  facial nerve, 78
Parietal lobe, and visual field defect, 124,125
Parinaud's oculoglandular syndrome, 67
Patch. See also Shield, use of
  after removal of foreign bodies, 89
  application of, 89, *89*
  corneal abrasion and, 85
  occlusion amblyopia from, 96
  for refractive amblyopia, 106
Patient history
  and eye injuries, 81, 82*t*, 83t
  and glaucoma risk, 45*t*
PDR. See Diabetic retinopathy, proliferative
Pediatric ophthalmology. See Children
Penlight, 6
  examination with
    in acute visual loss, 27
    external, 10
    in eye injury, 82, 84
    in red eye, 62, 65, 66
Periarteritis, syphilis and, 141
Perimetry, glaucoma and, 42
Pheniramine, for allergic conjunctivitis, 149
Phenylephrine, 12,104,148
Pheochromocytoma, 136
Phoria, detecting, 104
Photophobia
  chloroquine-induced, 153
  red eye and, 66*t*, 68

Note: Page numbers in italics indicate illustrations; tables are indicated by *t*.

  in syphilitic uveitis, 141
  trauma and, 79
Photoscreening, for amblyopia, 101
Physiologic cup, 13, *14*, 41
  in glaucoma, 42–43, *43*, *44*, 55
Picture card, for testing visual acuity, 100,100
Pigmentation
  in macular degeneration, 51, *51*
  and optic disc, 14, *15*
  retinal, 16, 19
Pilocarpine hydrochloride, 114,150–51
Pituitary adenoma, 122,123
Polycythemia vera, 32
Polymyalgia rheumatica, 34
Posterior chamber, anatomy of, 2, *4*, *41*
Posterior synechiae, 66
Precipitate, keratic, and red eye, 62, *62*, 66
Pregnancy, ocular problems in
  diabetes Type I and, 133
  toxemia and, 136
Presbyopia, 3, 22
Pressure patch. *See* Patch
Procaine, 151
Proliferative diabetic retinopathy. *See* Diabetic retinopathy, proliferative
Proparacaine hydrochloride, 82*t*, 83, 85, 88, 147
Prostaglandin analog, 152
Protease inhibitors, use in AIDS patients, 140
Proptosis (exophthalmos)
  and red eye, 63, *64*, 65*t*, 67
  and reduced ocular motility, 67, 84
  in thyroid disease, 136–37,136
Pseudoisochromatic plates, 19
Pseudomonas species, solutions contaminated with, 20
Pseudopapilledema, 120,121
Pseudostrabismus. *See* Epicanthus
Pseudotumor cerebri, 121
Psychoses, ocular side effects of drugs for, 154
Pterygium, red eye and, 61, *61*
Ptosis, 115,115,117,118
Puncta. *See* Lacrimal puncta
Pupil
  abnormality of, 65*t*, 66, 72, 105, 114–15
  Adie's tonic, 114
  anatomy of, 2, *4*, *5*
  Argyll Robertson, 115
  damage to, 90
  dilation of, 12–13, 84, 104–05
    in dark-eyed patients, 148
    drugs for (mydriatics), 6, 12,10445,115, 14748,154
    drugs not recommended for, 154
    in infants, 148
    and nerve dysfunction, 111,112,113,114
  disorders of, and neurologic disease, 114–15
  distorted, 79
  examination of, 63,105,111–13
  light reaction of. *See* Light reaction, pupillary
  Marcus Gunn. *See* Relative afferent pupillary defect
  normal, 111
  pathways of, 112
  red eye and, 63, 65*t*, 66, 72
  small unilateral, 115,115
  square shaped, 13
  tonic. *See* Pupil, Adie's (tonic)
  "white." *See* Leukocoria
Pupillary pathways, 112
Pupillary reaction
  and acute visual loss, 27, 32
  and cataracts, 48
  examination of, 6, 11, 111–13, *113*
  normal, 113
  and optic nerve dysfunction, 111–13
  and pediatric vision screening, 98
  and red eye, 63
  trauma and, 84

R

Race, and glaucoma risk, 45t
Radiant energy bum, treatment of, 86
Radiation, damage from
  and cataract, 46,139
  examining for, 83
Radiology, examination by, 84. *See also* X-rays; Computed tomography (CT); Magnetic resonance imaging (MRI)
Rectus muscles, 2, *5*, 12, *97*
Red eye
  abrasions and, 61
  causes of, 58
  disorders associated with, 59–61, *59*, *60*, *61*, 62

Note: Page numbers in *italics* indicate illustrations; tables are indicated by t.

Red eye *(continued)*
  examination for, 62–63
  signs of, 64–67, *65t*
  symptoms of, 64, *66t*, 67–68
  systemic problems associated with, 68-69
  therapeutic warnings for, 72
Red reflex, 13, *14*, *47*, 65
  absence of, 29, *47*, 84
  cataract and, *47*, 49
  normal, *14*, 84
  testing for, 13, 104–05
  and vitreous hemorrhage, 29
Reduced visual acuity, 3, 22
Refractive errors, types of, 3
Reiter's syndrome, iritis and, 138
Relative afferent pupillary defect, 27, 28, 29, 30, 84, 111–13, *113*
Renal transplants, ocular side effects of drugs for, 153
Respiratory tract, infection of, and conjunctivitis, 68
Retina
  and acute visual loss, 27
  anatomy of, 2, *4*, *16*, 80. *See also* Retina, examination of
  arteries of. *See* Retinal circulation
  degeneration of, 139
  detachment of
    and acute visual loss, 29, *29*
    hyphema as sign of, 86
    PDR and, 131
    sickle cell anemia and, 133
    and trauma, 80, 84
  disease of. *See* Retinitis; Retinopathy
  edema of, 80, 84, 135
  examination of (ophthalmoscopy), 12–16
  hemorrhage and, 80, 84
  infarction of, 129
  ischemic, laser photocoagulation surgery for, 32
  lesion on, 27,113
  perifoveal, 31
  uveitis and, 138
  veins. *See* Retinal circulation
Retinal circulation, 14–16, *14*, *16*
  central, *4*, 30–31, *30*
  examination of, 14–16
  occlusion of, 30–32, *30*, 139
Retinal pigment epithelium, 2, 14, 16
  appearance of, 54
  atrophy of, 51, *51*
  degeneration of, 50, 51, *51*
Retinitis, 139
  cytomegalovirus (CMV), and AIDS, 129, 139,140,140
Retinoblastoma, 98,104,105,105
Retinopathy. *See also* Diabetic retinopathy
  AIDS (cotton-wool spots), 13940,139
  drug-induced, 153,154
  hypertensive, 134–36,134
Retrobulbar optic neuritis, 33
Rheumatoid arthritis
  juvenile, 138
  sarcoidosis and, 138
  and ocular side effects of drugs for, 153
Rhinitis, seasonal, and red eye, 68
Rosenbaum pocket vision screener, 10, *11*
Rubeosis iridis, 131

S

Saccades (rapid eye movements), testing, 113
Sarcoidosis, ocular manifestations of, 137–38, 137
Schlemm's canal, *4*, 40, *41*
Sclera
  anatomy of, 2, *4*, *5*, *41*, 80
  examination of, 10
Scleritis, red eye as, 60, 60
Scopolamine hydrobromide, 147,154
Scotoma (blind spot), 122,123,124–25
  in glaucoma, 40
  in macular degeneration, 54
Seborrhea, in blepharitis, 69, 70
Sedatives, as nystagmus cause, 120
Shield, use of, 89, *89*. *See also* Patch
Sickle cell anemia, 32,133
Silver-wire arterioles, 134
Sinus. *See* Cavernous sinus; Carotid-cavernous sinus fistula
Slit-lamp, examination by, 29, 49, 54
Snellen eye chart, 7–8, *8*, 23, 62, 81, 104, 111
  eye injury and, 81
  procedure for testing visual acuity with, 7–8, 23, 111
  red eye and, 62
use with children, 6,101

Note: Page numbers in *italics* indicate illustrations; tables are indicated by *t*.

Snow blindness, treating, 86
Sodium fluorescein. See Fluorescein dye
Squamous-cell carcinoma, and red eye, 60, 71
Staphylococcus, blepharitis and, 70
Stevens-Johnson syndrome, 69
Strabismus, 94, 96–98. See also Heterotropia
  and amblyopia, 95
  concomitant (nonparalytic), 96–97, *96*, 102
  diplopia and, 115–16
  incomitant (paralytic or restrictive), 96, 97, 97,102,113
  pseudo. See Epicanthus
  testing for, 98,101–04,113
  treating, in children, 105,106
Stroke
  and homonymous hemianopia, 123
  and PDR, 133
Stye (hordeolum), 60, 70, *70*, *71*
Succinylcholine, 151
Sulfacetamide, 149
Suprofen, 149
Surgery. See also Laser surgery
  for cataract, 49
  intraocular, and hyphema, 28
  optic canal decompression and, 35
  for pterygium, 61
  for strabismus, 106
Suturing, of Lid lacerations, 89
Swinging-flashlight test, 27,111–12
Sympathetic nervous pathway to eye, anatomy of, *116*
Sympathomimetic drugs. See Adrenergic-stimulating drugs
Syphilis, 115, 140–41
Systemic drugs, ocular side effects of, 153–54

T

Tarsal plate, 2
Tay-Sachs disease, and retinal vascular occlusion, 31
Tearing
  chronic. See Epiphora
  dry eye and, 138
  in thyroid disease, 136
Temporal arteritis. See Giant-cell (temporal) arteritis
Temporal lobe, and visual field defect, 124,125
Tensilon test, 118
Tests. See also Examination
  adjunctive ocular, 6–7
  Amsler grid, 19, 52–54, *53*, 111
  anterior chamber depth, 12, 18–19, *18*
  cardinal fields of gaze, 12, 12*t*, 102
  color vision, 7, 19
  confrontation field, 6, 19, 27, 111
  corneal light reflex, 98, *99*, *102*, 103
  cover, 98,103–04,103
  edrophonium chloride (Tensilon), for myasthenia gravis, 118
  intraocular pressure (IOP), 16–18. See also Tonometry
  ocular motility, 12, 84, 100, 113
  red reflex, 13,104–05
  swinging-flashlight, 27,111–12
  Tensilon, 118
Tetanus, immunization against, and eye injury, 81
Tetracaine, 147
Tetrahydrozoline hydrochloride, 148
Therapeutic drugs, topical ocular, 148–49
Thioridazine, ocular, 154
Thrombocytopenia, 138
Thyroid disease
  ocular manifestations of, 61, 136–37
  and proptosis, 67
  and red eye, 60
Thyroid stare, 136,136
Timolol, 150
Tonic pupil (Adie's pupil), 114
Tonometer, 6
  applanation, 17, 42
  electronic, 17, *17*
  indentation (Schiøtz), 17
Tonometry, 6, 17–18, 23, 27, 42
  contraindication for, 18, 63
  procedure for, 18,147
Tono-Pen, 17
Trabecular meshwork, 40, *41*
Transilluminator, inspection by, 62
Trauma. See also Injury, ocular
  and acute visual loss, 35
  cataract and, 46
  and cortical blindness, 35
  and emergency situation, 85
  examination for, 81

Note: Page numbers in italics indicate illustrations; tables are indicated by t.

- Trauma *(continued)*
  - hyphema and, *28*
  - and optic neuropathy, *86,117,118*
  - and semiurgent situation, *87*
  - treatment skills for, *87–89*
  - and urgent situation, *85–86*
  - and vitreous hemorrhage, *29*
- *Treponema pallidum, 141*
- Trochlear nerve. *See* Cranial nerve IV
- Tropia, *97*
  - cover test for, *10344,103*
- Tropicamide, *12,147,148*
- Tuberculosis, ocular side effects of ethambutol for, *154*
- Tumbling E chart, *6,100,101*
- Tumor
  - brain. *See* Brain tumor
  - and eye disease, *115,118*
  - hyphema and, *28*
  - intracranial, *118*
  - orbital, and proptosis, *64*, 67
  - radiation of, and cataract, *139*

U

- Ulcer, corneal, 64, *64*, 66, 68
- Ultraviolet burn, *82t*
- Urgent treatment, *85–86*. *See also* Emergency, ophthalmic
- Uveitis
  - anterior, *137,137*
  - corticosteroids and, *137–38*
  - herpes zoster ophthalmicus and, *14142*
  - luetic, *139*
  - posterior, *137*
  - sarcoidosis and, *137–38,137*
  - syphilitic, *140–41*
  - toxoplasmic, *139*

V

- Vascular stasis, *30*
- Vasculitides, and acute visual loss, *29*
- Vincristine injections, optic neuropathy and, *139*
- Viral conjunctivitis, 65*t*, 66*t*, 67, 69, 71–72
- Vision
  - binocular (fusion), strabismus and, *106*
  - blurred, and disease, 66*t*, *67,116,141*
  - central
    - and lesions in the visual system, *123*
    - and macular degeneration, *54*
    - testing, 111
  - development of, *94–95*
- Vision training, optometric, contraindication of, *106*
- Visual acuity, *3*
  - and acute visual loss, *27*
  - and anatomy of eye, *3*
  - asymmetry in, *22*
  - degrees of, *9t*, *22*
  - distance, testing, *7–9*
  - examination of, 6, 7–10
    - for amblyopia, 96, 98, 99, 104
    - for injury, *81–82*
    - for macular degeneration, *52*
    - for strabismus, *98,104*
    - in uncooperative patient, *10*
    - for visual loss, 27, 48
  - impairment, *9*
    - services for patients with, 54–55
  - and macular degeneration, 52, 54
  - near, testing, *10*
  - and red eye, 64, 72
  - reduced, 3, 8–9
    - management of, *22*
  - scotoma and, *123*
  - testing, for neuro-ophthalmological disease, *111*
- Visual disability, *9*
- Visual field
  - altitudinal loss in, *34*
  - defects, 39–40, 42, 139
  - and neuro-ophthalmological disorders, *111, 121,122–23,138*
  - testing, 6, 19, 42, 111
- Visual impairment. *See* Visual acuity, impairment
- Visual loss
  - acute. *See* Acute visual loss
  - chronic. *See* Chronic visual loss
  - CSME and, *131*
  - drug-induced, *154*
  - examination for, 27, 48
- Visual pathway

Note: Page numbers in italics indicate illustrations; tables are indicated by *t*.

disorders of, 35,123
field defects and, 123, *124–25*
Vitrectomy, 131,133
Vitreous cavity
anatomy of, 2,4
hemorrhage into, 29, 84
Vitreous humor, 2
injury and, 80
opacity of, and acute visual loss, 28

W

Welder's burn, 86
Women, eye disease in, 133,137

X

Xanthophyll pigment, 16
X-rays, eye injury and, 83*t*, 85. *See* also Radiology

YZ

Zeis, glands of, 70
Zone, of cataract opacity in lens, 46
Zonules, 2, *4*, *41*

Note: Page numbers in italics indicate illustrations; tables are indicated by *t*.

Basic Ophthalmology for Medical Students and Primary Care Residents is designed to help you learn the techniques of a complete eye examination and the most **important** concepts of **diagnosis** and management of ocular **disorders.**

The **seventh** edition features many updated color images, the latest **information on** glaucoma **medications** and treatment, updated references, added Sample Problems, and many more **improvements.**

Basic Ophthalmology Slides, a **companion** set of 78 35-mm teaching slides duplicating the **slide** images shown in the text, is also available **from the Academy.**

CONTENTS

1 The Eye **Examination**
2 **Acute Visual** Loss
3 **Chronic** Visual Loss
4 The Red Eye
5 Ocular and Orbital Injuries
6 Amblyopia and Strabismus
7 **Neuro-Ophthalmology**
8 Ocular **Manifestations** of Systemic Diseases
9 Drugs and the Eye

Item No. 0230048

ISBN 1-56055-098-8

Chapter V
Cosmic Healing I - Basic

Source of Chi and Color

There are different sources of Chi in the universe: cosmic (air), earth, nature and human. Different parts of the human body have different energies and are correlated with the universe and nature. Each part of our body, especially the organs and glands can produce, receive, transform and emit different Chi and color.



Mars - Red Chi
Frontal Bone - 1

Saturn - Yellow Chi
Frontal Bone - 2

Jupiter - Green Chi
Right Parietal Bone - 3

Mercury - Blue Chi
Occipital Bone - 4

Venus - White Chi
Left Parietal Bone - 5

Sun - Golden Chi
Third Eye - 6

Earth - Yellow Chi

Moon - Silver Chi
Sacral Bone - 7

Fig. 5.1 *Planet, Bone and Cosmic Colors*



Technical information given from the IARGA contactteam.

their describtions on the matter of TIME

- AND MORE

picture is described later

12. The analog carrierfield model, an instruction model.

The cosmic carrier field of all space and matter performs a sixfold function, of which some have already been discussed in gereral way.

1. The carrier function of an infinitely strong forcefield blocked in itself contains the fluidum conducting all waves without dissipation and maintained to eternity.
2. The orientation of the time-axes of the universes with respect to nothing provides the structure of the carrier-field of three dimensions, the bounded Love-will, creating our life and existence.
3. The time synchronisation function locks all universes in the iron grip of the law of cosmic counter-balance from which no atom can escape.
4. The feedback principle of time to the total mass of the universe is the function of the coupling-field by counterbalance (and interference) of the time-bound waves.
5. The function of the timeless primeval atom-field, the atom-principle, as the transmitter program containing the code of matter of which all atoms are remote manifestations.
6. The function as bearer of the absolute ALL-knowledge and goal consciousness, manifesting itself as the laws of nature and as the intelligent goal of life: the spirit of God.

The last function concerns the existential aspects, which have been discussed in the previous section of this book.

The first analog model is a mechanical instruction model explaining the cosmic carrier field by means of symbols. This model was built on another life-supporting planet on a high mountain and was many meters high. It was the gathering point for contemplation of that intelligent race for devotion to its Creator.

It was the symbol by which the majority of the race acknowledged the goal of Creation, simultaneously the sign that the cosmic isolation had been lifted. The other function of the carrier-field will be discussed with the help of this mechanical instruction model.

The analog model consisted mainly of the six edges of a huge equilateral triangular pyramid built out of solid soft-iron bars. The many metres thick edges of the pyramid contain an impressive number of iron bars parallel to the direction of the edges and cast in a kind of plastic resin following a process similar to that of casting concrete(betong). So a mainly iron-frame was formed especially suitable for conduction of magnetic pulses of high power without much loss.

So far the carrying fuction of the cosmic time-field, which primarily maintains the timeless waves is symbolized in the model. The magnetic pulses in the edges of the pyramid run backwards and forwards like the timeless waves in reality.

With respect to the other edges of the pyramid, the magnetic pulses are phase-shifted. The problem is that up to now the forward propagation (forplantning) in time has been missed out. In fact we look for the equivalent of the two little wagons on the vibrating rail. The solution can be found in the symbol of the rotating flywheel, as *with the atom its rotation is continuous in time, it is in fact time propagation.* Therefore the iron frame of the pyramid is discontinued at two places in each of the six edges of the pyramid. At this discontinuation point a linear magnetic impulse motor is installed, on the axis of which a large flywheel is mounted.



NBF=NonFerroBridge

PE=PyramidEdge and soft iron bars

PMR=PermanentMagneticRotor

The flywheel symbolizes not only the propagation of time, but also the inertia of matter and so the flywheel is in effect the total mass of the universe. This type of magnetic impulse motor is not self-starting, so at the inside on the flywheel axis a starter-motor is mounted, fitted solely for the purpose of starting. One rotating the synchronous motor maintains the exact number of revolutions at the same frequency of the magnetic alternation field. Thus in each of pyramid's edges two synchronous motors are mounted making twelve flywheels in total.

The two flywheels per axis rotate in opposite directions to symbolize the time propagation in opposite time directions. This type of linear impulse motor is chosen because it can be made to rotate in either direction.

The first analog model.

In one triangular plane of the pyramid the six synchronous motors in the iron frame demonstrate a rotating magnetic field, seen from the center of the plane. Each edge of the pyramid has the right phase-shift with respect to the other edges of the triangle.

The first model has four central rotating magnetic field generators in the middle of each triangular plane. (See figure of unfolded pyramid indicating the actual phase-shift).

These four synchronous (three phase) generators are coupled together by a gearbox and are driven by the main electric motor (not shown in the drawing). Consequently the four three-phase generators fulfill the synchronisation and constant phase-shifts for the flywheels of the pyramid-edges. The four separate rotating fields together, initate the complex three-dimensional rotation of the carrier field (or atom-field).

The disadvantage of the first model is that it is further away from reality, because the atomic field is not symboized as one three-demensional rotating field. However it shows better how to imagine the complicated rotation in three dimensions.

The second or the real analog model.

This mechanical model has only one central generator in the middle of the pyramid, instead of the four rotating field generators of the first model. All magnetic waves in the pyramid edges go straight to the pyramid's center. The rotor of the 3-dimensional rotating generator is like a yo-yo with spherical end-surfaces.

It requires a touch of genius to provide the drive-connection between the central motor and the spherical rotor, which has to be started up in a complex rotation. The six diametrically opposed pole-shoes from the middle of the pyramid's edges around the spherical rotor form in pairs, three axes of right angles - representing a Cartesian coordinate system. So it shows that the six time-axes of the edges of the pyramid can be converted into the three principal time-axes of the central sphere.

Together it imitates three-dimensional time, which causally creates the three-dimensional space of our universe.

The principles of the first and second analog models are equivalent. One version can be converted into the other, for example, converting the four rotating fields to one three-dimensional rotation in the centre-mass of the pyramid.

The model can be started by switching on the thirteen drive-motors. As the flywheels reach velocity the twelve starter-motors are switched off and only the central motor drives the complete gigantic model. The essence is that all flywheels have exactly the same number of revolutions. They are all either synchronous motors or generators. Then the flywheels are marked and illuminated by a stroboscopic flash light. *Seen by the normal eye they do not appear to move showing the synchronous rotation and the constant phase-shifts between the flywheels.*

These mechanical models are meant to explain the unimaginable Creation out of the nothing by symbolic imitation of the carrier-field. However it is only a weak symbol of Creation. The carrier-field is the esoteric medium, a transmutation of the absolute spirit or conscience, it is the spiritual force field of infinite strength which is present everywhere in the universe.

The imitation of the carrier-field functions.

Nevertheless the analogy of reality is incredible. This will be shown in the next explanation of the five functions of the cosmic carrier-field.

The carrier-function

The foundation of the carrier-field is the infinite force-field created by interference quenching (avbrytende stopp) of the original infinite vibration. The mode initiates this force-field with the six bundles of soft-iron bars as the edges of the pyramid.

As in reality, the three-dimensional magnetic rotating field in our model is caused by the linear waves of each time-axis. *The timeless waves alternate backwards and forwards as in our model*. They drive the flywheels representing the masses of the universes, and their rotation is the propagation (spredning) in time.

The orientation of the time-axes with respect to the nothing.

The relative position of one time-axis in the apparent nothing plays an important role in the orientation of the universes in reality, determining the direction of each time-axis. Here the first model is shown representing the four three-phase synchronous generators in the planes of the pyramid. Only with decompostion of the three-dimensional rotation into four rotations can one show that the three-dimensional rotating field has left no remaining component in the nothing, while in contrast a two-dimensional rotating field can not be nullified, a remaining component will always exist in the nothing. This can be explained by considering a single plane of the pyramid with its six flywheels at the edges, the analog for a two-dimensional

carrier-field. The rotation impulse of the flywheels is compensated by the opposite rotations but the rotation impulse of the central three-phase generator is left over. It can be measured by the outside world (the nothing).

It requires four field three-phase generators (maintaining overall symmetry) to compensate for these rotation impulses.

With this the three-dimensionality of the carrier-field has been shown and the orientation of the time-axes with respect to the nothing is determined.

The time synchronization function.

Impressively the model imitates the time synchronization, simultaneously maintaining the cosmic counter-balance by which the universes continue to exist. The rotation of the two flywheels per axis is in opposite directions and they rotate with exactly the same speed. Thus it imitates the circular motion to the timeless waves which progresses exactly synchronous by their mutual interference coupling.

The twelve cosmic systems run without any dissipation, once started, the perpetuum mobile continues into eternity with the absolute accuracy of time-synchronisation. If one supposes the model to be without loss and without using the eternal driving motors, it will continue to run synchronously due to the inertia of the flywheels and the fact that the synchronous linear impulse motors can function as generators as well.

This symbolizes another property of the continuous circular motion of the timeless waves, because every wave somewhere in the pyramid circuit at each moment has its opposite value resulting in an overall zero at any moment.

This is the law of conservation of the nothing.

The couplingfield function.

Time synchronization is not alone determined by the iron grip of the three-dimensional carrier-field and the principle of cosmic counter-balance. Apart from this an important effect is realized from the feedback of the gigantic masses of the universes to the timeless waves. These masses can be considered as enormous flywheels without loss. Once started by the super flash, no change in speed is possible, because a force of sufficient magnitude is simply not available. This function of the coupling field can also be shown in our model, because the linear synchronous motors of the flywheels are also generators. If the central driving motor is switched off, then the flywheels continue for some time to drive the central three-dimensioal rotating sphere. Everything stays exactly synchronous with the same phase-shifts.

This experiment shows how the flywheels feed their energy back and have a stabilizing function in time-synchronization. The coupling-field of the masses of the universes is fed back in the time-bound vibrations of the atom-field from which no atom total mass of the universes is fed back to one single atom.



This is a painting by Rudolf Dass of the analogous visual-mechanical carrier-field model which symbolizes time and matter creation and synchronization in twelve universes. This giant working construction that was a cross between a monument and a machine was seen on an artificially flattened mountaintop on **Iarga**. This place was perceived as a place of pilgrimage, a place of meditation and contemplation, and the machine was a symbol of creation. The **Iarga**ns know no separation between science and religion, and religious and spiritual theories are entirely scientific. The model was several hundred yards(meters) long. The machine seemed to operate by some kind of perpetual motion, neither running on fuel or electrical power.

The Instructional Analog Model

The mechanical instruction models are the visual representations of the principles of the cosmic unified field theory. The model is intended to demonstrate that time, matter, and energy are creations out of the nothing and therefore the counter-balance has to be maintained to allow the causal infinity of the nothing to exist. In a broader context the physical symbols all take on new meaning and demonstrate the unification of science and religion. In a religious sense the spherical three-dimensional time-field in the heart of the pyramid symbolizes the Soul of the Creator. The pyramid symbolizes his infinite lovewill, the cage in which the infinity of His existence has been blocked irrevocably. The lines symbolize the different frequencies of the timeless waves. The flywheels on the edges of the pyramid symbolize the twelve associated and interrelated universes, including ours, that make up this unity. One cannot exist without the others.

The timeless primeval atom-principle, the transmitter function.

The atom-field is a time-creating field and as such a remote manifestation of the primeval atom principle. It can be compared with a transmitter. As soon as the program is converted into waves of great power, billions of radios can receive the same program, the number is unlimited. Everything depends on the one program of the transmitter, the primeval atom-field. If this exists with infinite strength, it is at the same time the vibration medium (the carrier-field) which helps it to spread everywhere. *Thus any atom in any universe can receive the timeless basic program.* The second model shows the three-dimensional time-field of the primeval atom field most clearly, although this is a three-dimensional rotation of the central sphere in spatial sense. This is an analog of reality, the atom has a spherical field which is defined by six linear time-vibration directions. Any atom is a remote manifestation of the one carrier-field of infinite strength.

Considering this fifth function of the carrier-field one has to realize that only the central sphere, the atom, is visible to us. The fields in the pyramid edges outside the sphere are invisible. It is the time-field reality of which the atom is a reflection.

The mechanical instruction models are the visual representations of the principles of the cosmic unified field theory. This requires however some marginal notes. A material comparison to explain spiritual abstractions is always in some ways incomplete. There are several hiatus of which only the three most important ones are mentioned.

1. In the model one time-axis represents only *one frequency* of the magnetic field, while in reality all frequencies are contained. Every frequency however can be initiated for each time-axis for which the interference representation of the analog model is valid.

2. The model demonstrates the rotating field of the *timeless waves.* It *does not imitate the time-bound waves* by which our time-axis the propagation speed of time is X, then the phase velocity of the two time-axes connected to "our" pyramid edge is ½X. The other two time-axes connecting our time-axis with the other corner of the pyramid is -½X, making up for the time speed of our anti-universe -X. The crossing, not-touching time-axis is perpendicular to our time-axis and does not contribute.

3. In our model the masses of the universes are given by the flywheel symbol. In fact this is *fundamentally wrong, because it is separated from the three-dimensional rotation of the central sphere.* It can therefore basically not maintain the counterbalance of the nothing.

The most important conclusion of the analog model is that *time, matter and energy are creations out of the nothing and therefore the counter-balance has to be maintained to allow the causal infinity of the nothing exist.*

14. The existential symbolism of the model.

So far the physical aspects of the model have been unravelled, but if one wants to give a wider context to the model suddenly all the physical symbols change their meaning. In relation to philosophical or theological disciplines the model takes on the additional meaning of the unification of science and religion. By certain inherent (medfødte) laws within any intelligent race the denial of God's existence will be destroyed sooner or later. Earth science will provide an indestructible contribution to our final knowledge-awareness, which we shall attribute as typical human attainment in the cosmic integration. It is that piece of our human identity and self-awareness, which we shall possess and care for throughout eternity. *It the light of this purpose, science serves God and the distinction between science and religion fades away.*

In a religious sense the spherical three-dimensional time-field in the heart of the pyramid has a special meaning. **It symbolizes the Soul of the Creator**, the Father who is the pure Identity of the infinite origin. The pyramid symbolizes his infinite Love-will, the cage in which the infinity of his Existence has been blocked irrevocably. He sacrificed his Ego and his freedom, to love his twelve Sons once. He is present only indirectly in his Creation as the reflection of the infinity, the Supreme Being, as the one Ego-consciousness of the Archangels.

That is why the theologian covers the central sphere with pure gold, symbolizing the golden Heart, the Holy of Holies, the most sacred secret of the universe. The pyramid is then painted dark red, the universal colour of love. Over the red many thin golden stripes run in the direction along the pyramid edges. These stripes symbolize the different frequencies of the timeless waves, the expressions of Love and faith of the Father and his infinite Will.

Gathered around the golden Heart are the twelve flywheels, coloured white, the colour of purity and innocence. The model shows that every universe has the power to awaken the matter-consciousness and to transform it to the new

God: the Son. The goal of Creation is therefore the awakening and the formation of the twelve Sons of the Father.

This is not in contradiction with the Bible telling us that the Father sent his only-begotten Son. The Bible is solely directed to man. It is our instruction book for life describing our attitude towards God and our fellow man. The Bible does not tell anything about life on other planets, because it is not relevant in our relationship with God now.

The same goes for our parallel universes. In fact they do not exist for us, because they are not in our world of existence but somewhere else. They do not exist for all intelligent races in this universe, we shall never be able to observe them nor experience them in any way. Perhaps at the end of all time we shall meet. In *our* world the Father has one only-begotten Son and this truth is already so unimaginable that nobody can conceive the consequences yet.

END OF IARGAN DISCUSSION

---

mainpage

the IARGA CONTACT story

ufo-contact-material

Earth Chi

While Cosmic Chi (the atmosphere over us and the universal force) is ethereal in nature, what is called earth Chi is not. This Chi appears as the line visible above the horizon when the sun is low in the sky, and seems to hover just above the ground. It actually also sinks into the ground.

Earth Chi contains yellow and some white Chi. When the ground and the cosmic (air) combine they will become white Chi. This Chi has a very powerful healing energy, not too overheated, but balanced and mild.

When treating a problem, white Chi, in the proportion 7:3 (7 white to 3 of the selected color) acts as a brake on colors which are hot or too active. This enables the body to take in chi more easily.


Sacrum
70% White
30% Red
Light Whitish Red
Throat
70% White
30% Green
Light Whitish Green
Throat
70% White
30% Blue
Light Whitish Blue
Crown
70% White
30% Violet
Light Whitish Violet

Fig. 5.2 *Use White Chi to blend all the other Colors.*

Special Note: Many of the color references came from the following books: *"Let There be Light"* by Darius Dinshah and *"Advanced Pranic Healing"* by Master Choa Kok Sui.

Technical information given from the IARGA contact-team.

their describtions on the matter of TIME

- AND MORE

APPENDIX 1

An Analog Model

1. Introduction

This appendix is not a part of the story of the Creation which is explained in religious terms in Chapter 1 (Part 2). It is a complementary way of reasoning to prove the existence of God, using the concepts of time, matter and energy. These concepts are also used in physics. The problem, which now arises, is that the author will use physical concepts without understanding the real meaning of the words, because he is not a specialist. The words atom, atom-field, matter, etc., must all be understood within the context of this book and they have no direct connection with the ideas used in modern science. Especially the words "matter" and "atom" are most confusing, because the **Iarga**n author knows about the existence of matter in three configurations (and its opposite possibilities as anti-matter); i.e., time-matter, phase-matter and *reflection-matter* (the one we know about in our universe), but he fails to interpret these concepts due to his lack of knowledge of physics. He only knows that these forms of matter are all related to one or none of the directions of time- propagation (tidsforplantning) of the atom of which time is fundamentally three-dimensional. It therefore determines in which form these configurations can exist in our universe.

In this appendix - time-creation out of NOTHING is described - by making use of the concept of more time-dimensions. The explanation of time-creation is very difficult because it uses an overall carrier-field of infinite strength and then this concept is called the cosmic unified field theory. In defining this term, one has to be careful, *because this theory is of a different basic nature from the existing unified field theories here on earth.* Our unified field theories try to unify the four basic forces in nature, which are the electro-magnetic, the weak strong nuclear force and gravitation. The unified field theories accepted by most prominent scientists find their origin in the general relativity theory of Einstein, which itself explains matter and energy in terms of space and time.

The problem now is to find a method, explaining the spiritual or esoteric reality, the cosmic time-field. On other planets, this problem was solved by explaining the basic concepts of the cosmic unified field theory. The elementary functions of these concepts can be understood with a mechanical instruction model demonstrating the cosmic time-field visually.

Why indulge in this complication of describing a theory which will probably only be fully grasped by a few individuals? It does not concern the author very much, he only carries out his commission. His **Iarga**n instructors gave three reasons for publishing the concepts of this theory:

1. The future integration of science and religion requires a material proof of God's existence. This explanation could be the start of the exchange between these two.

2. In the previous story of Creation the limitation of the infinite is explained unambiguously(upretendiøst), but the working principle was completely neglected.

3. The cosmic unified field theory published in this book will be the only possible verification for the true identity of this book, providing the link for the future development of the human race.

2. The physical approximation of the NOTHING.

One concept in physics is that all atoms and energy consist of vibrations and wave appearances. In a material way, every atom or form of energy is caused by vibration. The physical approximation (tilnærmelse) describes the nothing of the idea of vibration - and *does not touch on the spiritual aspects and the consciousness of matter*. It does not distinguish between the "nothing" and the spiritual "No-Thing" (the ALL). It only recognizes the material aspects of the nothing.

If everything is vibrations or waves, then it is not necessary to speak of matter or energy, then Creation is fundamentally based on this concept of vibration. The primeval vibration (before the limitation) can be described as infinite in time, infinite in all its aspects and possibilities, infinite in frequency and amplitude and existing in all time directions (omnitime). Unchanging, timeless and powerful to all limited vibrations in every bound power. It is the omnipotent definition.

In this approximation the nothing is more simple to understand. Before the creation - the infinite omnipotent vibration existed- *but a vibration in every direction and of infinite frequency and amplitude is not a vibration*. The apparent paradox can be eliminated by stating: Only at the instant when this infinite vibration blocks itself by interference, *as in a flash, all bound waves and frequencies were created.* This condition is very close to the existential view of the Creation out of NOTHING in Chapter 1.

The nothing (here) has no counteraction, but in contrast the omnipotent vibration - can manifest itself only by counter-acting in such a way that the infinite allows the nothing to be. So one can also state that all vibrations were created because the nothing bound itself by a mechanism of interference quenching - (counteracting vibrations) of infinite force, which blocked the infinite possibilities of these vibrations. *This universe can only be considered as the limitation of the unbounded nothing.*

3. The bounding of the omnipotent infinite vibration, the cosmic time field.

One of the basic principles on which the mechanism of bounding is based is: *If one property of a power (any power) of something is bound, then all properties and powers of this something will be bound.* In infinity the finite cannot exist. To limit the omnipotent vibration it was sufficient to bind only one of the perhaps infinite number of possibilities. Because if only just a little something were to be formed in the nothing, the nothing would be altered and cancelled irrevocably, then the complete finity (endelighet/begrensethet) was a fact. OR, if there were just the three-dimensional rotating time-field as a possibility of the primeval atom in the infinity of the nothing, then the finite was a fact. This atom-field needed to be a force-field of infinite strength, the carrier-field, to counteract the omnipotent vibration, the cosmic time-field.

4. The Creation can only exist as a result of counter-balance.

One of the functions of the carrier-field is time-synchronization by which the cosmic counter-action and therefore the nothing can BE. *Matter and energy* *cannot exist on its own in the nothing.* The principle of time synchronization is given:

1. Time is only relative, it is motion or propagation (spredning) in relation to at least a second motion of time.
2. the cosmic law of counterbalance dictates that the second time has to counterbalance the first time. So time can only exist in relation to a second exact *opposite direction* of time (running backwards in relation to our time).

3. Time exists only through the presence of atoms or matter. Then the backward-running time can only exist through matter in which the time propagation is opposite, *running backwards* in relation to us (antitime matter). Anti-matter or reflection antimatter may exist in our universe with an opposite electric charge with respect to our known reflection matter. The question, as to which charge antitime matter has in the anti-universe, is of no importance in this appendix.

4. Because neither matter nor energy can exist on its own in the nothing - another quantity of matter of opposite properties *must* exist which is exactly similar to that in our universe. This balance of matter and energy is so accurate, that one surplus atom is impossible.

This explains nearly as per definition the cosmic law of counter-balance allowing the nothing to be. There must be at least a second universe exactly like ours, in which time runs backwards according to us, but normally for life in that universe. In the following it is shown that there are not just two, but *eleven* other universes in addition to ours necessary to maintain the cosmic law of counter-balance.

6. The time-synchronization field.

The law of counter-balance also applies to time. The timedirection is opposite and the time velocity is equal to ours. Time is the propagation of vibrations of the atom. Then the atomvibrations in both universes are equal and opposite with respect to the timelessness. This is only possible if these times are caused by one field (time-field).

The definition of a field (any field in physics) is: If an event occurs, because another event takes place somewhere else without a mechanical or visible connection between these events, then these events are caused by a field. Time-synchronization occurs according to this definition. The atom vibrations in our universes are exactly similar, because the atom vibrations of our anti-universe occur despite the enormous difference in time and without any dissipation of energy. It is about 30 billion (milliarder) years since the occurrence of the super flash Creation (big bang) between the two universes.

The law of conservation of counter-balance is causal to the law of energy conservation in every universe. Each universe is a closed system and without energy dissipation outside itself. The amount of matter and energy once created remains constant. *A loss of energy is impossible, because our time-bound energy propagates forwards, while the time-bound matter and energy of the anti-universe propagate backwards in time.* These universes are separated by a time-barrier through which no communication nor transfer of life is known. (Well - according to information in the book UFO-CONTACT FROM PLANET KOLDAS and also told by the et-contact ASKET and Semjase - there are some methods for entering the mirroruniverse - but this can not be touched here - reseach yourself if interested!! R.Ø.remark.)

6. What is a timeless vibration or wave?

The question is how the field functions maintain the time-synchronization of the atom-waves between the universes separated by billions of years. It is only possible if the synchronization stands still in time, but exists simultaneously in all the time elapsed since the beginning of the super flash, as well in all the future. *A timeless vibration does not normally move in time*, the amplitudes of the field propagation - alternate forwards and backwards in time. Time synchronization is the principle by which our universe catches every forward-moving amplitude and the anti-universe catches every backward moving amplitude of one and the same timeless wave.

On other planets there are simple mechanical models explaining the function of time synchronization. One such model is very similar to our well-known mini-model rail upon which are two little wagons. The model has two lengths of rail of say 1.50 meters each, which are in direct line with each other.



Picture of the model wagons with a Electric drive motor which letting an excentric, and so the rails vibrate horisontally.

Rail and wagon model demonstrating the principle of the timeless waves. The vibration is present at any point of the rail and at any time during the whole process period. Also from the moment of the super flash until the end of all times (ALWAYS).

The rails are mounted on small springs to allow them to vibrate forwards and backwards in horizontal direction (from left to right and vice versa). The two rails are connected to a little electric motor with a double eccentric, each driving one rail, letting the rails vibrate about 1 millimeter of linear distance, also backwards and forwards. The amplitude is small enough to be invisible to the eye.

Then one little wagon is placed on each rail and each wagon has a catch with a catchwheel (tilbakeløps-sperre) on one of the wheelaxes, so the wagon can ride in only one direction. *The movement in the other direction is blocked.* The wagons are placed with their rears against each other, after which the electric motor is switched on. If the teeth of the catchwheel have the same beat as the vibrator mechanism, the wagons roll away from each other with exactly the same speed to the end of each rail.

With this simple model time synchronization for the atom-vibrations of both departing universes (in time) by a timeless field "always existing everywhere" has been demonstrated sufficiently. At the same time a flaw(feil) comes to light. It is impossible to maintain an energy time flux of the timefield for the two departing universes, because where is then the inexhaustible energy source to maintain the time-flux?

This is one of the reasons that a one-dimensional time-field is not possible. Only a three-dimensional time-field, which encloses the energy time-flux in itself, allows our universe and the others to exist.

7. The principle (mechanism) to create finity: INTERFERENCE.

So far the function of time-synchronization of the carrier-field has been considered. Now we will discuss the medium of conserving and maintaining the timeless vibration into eternity. It is the infinite force-field carrying all matter and energy.

We are at the moment of the flash or big bang, the moment at which the infinite primeval vibration limited (transmutated) itself to the carrier-field. This mechanism of blocking is well known and based on the principle of wave interference. (Interference of lightwaves is important today in laser technology.) Interference is the action or counter-action of two or more waves. If the *wave-propagation(-forplantning) is opposite and parallel* and the frequencies of the waves equal, mutual amplification (gjensidig forsterkning)or attenuation (fortynnelse) of the intensities of the wave is possible, depending on the phase relation between these waves.

If *the phases are opposite* and the *amplitudes of the waves are equal,* total quenching (dempning/kvelning)is possible. This is the principle of the binding of infinity. If an infinite wave manifests itself in one time-direction, automatically the equivalent absolute counteraction is created which counter-balances the infinity, allowing the nothing to be.

The infinite primeval wave blocked itself at the moment it created itself and so it never existed in reality. It was in fact a *transmutation of infinity;* the transmutation of the infinite vibration of infinite amplitude and frequency to a carrier-field of infinite strength, which blocked itself by interference.

8. The time-bound vibrations or waves.

The primeval wave blocked itself in a three dimensional time-axis system (propagation directions) by interference, and trans-mutated to an infinite, timeless, immobile force-field. How could the bound timeless waves exist, which synchronize our universe?

It is an error of thinking to suppose that by quenching the omnipotent vibration - all finite waves were also cancelled. It is just the opposite. A vibration with infinite frequency is not a vibration in reality. The infinite prevented the vibration, because a vibration can only exist in the finite. As soon as infinity was removed, the prevention disappeared and the real bound wave was a possibility. It is the carrier forcefield although of infinite strength and energy density which gets its finite value due to interference quenching. All timeless waves are as it were encapsulated in infinity and therefore indestructible. However "belonging" to infinity and not bound by time themselves, they create time forever, they are the eternal ripples on the static ("krusning i likevekten"), unchangeable and loss-free field of infinite strength. (This must be what the Danish wiseman Martinus call the X2- principle and the primeval-desire or "urbegjæret" in Danish. R.Ø.remark.)

Because of this, all time-bound waves such as light, radio-waves or gravitation, exist in space without any loss and it is the empty space in the universe, which is the non-modulated structure of the carrier-field. It is one of the most fantastic touches of genius of Creation, that the non-vibrating infinity was transmutated to a loss-free medium carrying all time-bound and timeless waves. A few properties of this medium can be measured with instruments, the other part of its structure cannot be objectively observed yet, *it is the esoteric fluidum or the infinite Love-will of the Father which carries the whole Creation.*

9. ***The unimaginable three-dimensional time.***

One time-axis counter-balances only one direction of time propagation of the omnipotent (allmektige)wave. In infinity all possibilities of vibration exist and therefore all time-propagation directions. The question is, could infinity be limited by just one time-direction and one co-existing propagation direction going the opposite way?

One way to answer this was already given in the previous paragraph, in which it was stated that the energy time-flux of the primeval wave of two universes is not a closed system. Another plausible answer can be by simply reasoning.

The atom is causal for the time - and space dimensions, due to its time-creating properties, already mentioned. *The space-creating properties are easy to understand, because the atom takes up space.* It is three-dimensional in space and therefore it creates space in three dimensions. If all atoms were two-dimensional then the whole of creation would have been on a plane and space would not have been more than a flat or curved plane. Our time-space is no more than a bound part of the nothing - being filled with matter or energy. Anything that space distinguishes of the time - and - dimensionless void, is caused by atoms or energy. If atoms have three space dimensions, then the timeless waves creating the atoms also have three dimensions.

1. The timeless primeval atom-field has three time dimensions.

2. The timeless waves could not be bound by only one time-axis, but must necessarily have three time-axes.

3. The timeless atom-field should consist of a three-dimensional rotating field of infinite strength, which is attenuated (fortynnet) of itself by interference. It conserves the law of cosmic counter-balance of the no-thing. *The atom of such a rotating field structure has six time-axes, but in principle these six axes can always be reduced to three time-dimensions, no further reduction is possible.*



Picture of ONE-TIME-AXIS: The cosmic symbol of one time-axis.

In the following parpagraphs of the analog carrier-field model it is shown, why the atom-field has to be a three-dimensional and not a two-dimensional field.

10. The six time-axes of the time-creating, cosmic carrier field.

How can it be established that the carrier-field of all matter in twelve universes has six time-axes? The first part of the answer is simple to explain. *A well-known type of rotating field on earth is that of the electric three-phase synchronous motor.*

This type of electromagnetic-field system consists of three linear magnetic fields, which are arranged at angles of 120 round a rotor. The phase-differences of the three alternating magnetic-fields, which have the same frequencies (say 50 Hz) are also at each 120 degrees. Each alternating field is in itself an exact linear vibration oriented in one direction. The rotating field exists only if the three linear vibrations are combined together with the proper phase-relation between them. So a two-dimensional rotating field in space is created. It can force a piece of magnetic material to rotate around its axis with a great power.

Insert pict of motor



The principle of an electric three-phase synchronous motor.

The fact that it is possible to create rotating fields by combining three linear alternating waves does not mean that it has to be the same for fields of infinite strength, it can be more than three, but it is not very likely as first guess, because the three wave principle (the equilateral triangle) is the most simple and effective. According this principle, for a three dimensional field six linear waves are required to form an *equilateral triangular pyramid,* but why an angle of 60 degrees between time-axes?

The first answer can initially be given in a very simple way, the second is more complicated, but at least more to the point.

A simple way of reasoning to derive (utlede) the answer to the question of 60 degrees is the following. The atom field of matter has spatial (romlig)structure, therefore the time-axes must be positioned in such a way that they form a closed three-dimensional geometric object, because the energy fluxes of time must be closed in itself due to the law of counter-balance.

The time-axes form straight lines, which cannot be parallel lines, because parallel time-axes form one and the same time-direction. *The most simple three-dimensional closed object is an equilateral triangular pyramid.* There are no reasons to suppose it should be an a-symmetric pyramid if three-dimensional time is considered, on the contrary, it must be symmetrical in all positions. So it is simply a equilateral triangular pyramid of which the lanes are equilateral triangles. There is no more simple object in three-dimensional space with these requirements.

The more sophisticated answer to the question of 60 degrees is time given by approaching the question from the relativity of time frequencies between the other universes (the other time-axes). Time is the wave propagation of atoms which determines the direction of the past to the future. Simultaneously these time-creating or timeless waves are the linear phase waves combining to maintain the atomic rotating field. The problem is that "our' atoms do not experience the right frequencies of the other time-axes, because they do not propagate (spredes)with the same speed, but advance in time.

Thus there is an apparent frequency-shift, a kind of Doppler shift, by which the frequencies of the "other" time-axes are experienced by "our" atom. One should realize that the timeless vibrations of the other universes also exist in our universe.

At first sight it seems impossible for a rotating field to posess a constant phase-shift because between vibrations of different frequencies a constant phase-shift is not possible unless the frequencies are related to each other in a particular way. They are harmonic. Two vibrations are harmonic if the apparent frequencies have constant ratios to each other, like 1:2, 1:3, 1:4, etc.

Timeless waves can only exist when the frequencies are related by the harmonic ratio 1 : 2.

Human and Nature Chi

These include the things we can see on the earth: the mountains, lakes, seas, forests, streams, caves, valleys, rocks and precious stones. Taoism classifies five elemental forces: earth, metal, water, wood and fire.

So there are five elements in our body and five elements in nature; there are five elements in the cosmic and five elements in the universe.

According to the Taoists, when we can make the connection and control our body's elements, we will quickly make connections to nature and the universal forces and employ them very easily.

Solar Chi

Before sunrise or sunset there is more white Chi in the air, which we can use abundantly for health and healing. White Chi affects the lungs and the large intestine, so we direct this Chi to these organs. This will generate further Chi to maintain our daily activities. All colors of the spectrum are present in white.

Simple Practice

Look at the horizon at sunrise and sunset. Stand still and extend your palms toward the sun, smile and absorb the rising or setting sun's energy into yourself.

General Information

Energy can be introduced to the affected area of the body by moving the hand clockwise in a spiral.

Move the hand **anticlockwise** with a spiraling motion to clean, flush and remove energy from the treatment area. After this, brush down the whole body, to direct the sick energy into the earth.

Use an anticlockwise spiraling movement in order to clean, then expel the energy.

Use a clockwise movement to bring energy in and an anticlockwise one to take it out.

As a general rule and especially when you are beginning to practice the techniques, keep the color combinations simple. **Always use blue (to cool, calm and stabilize), green to clean, white to harmonize and violet (which carries the properties of all the other colors) to program.**

Although it is important to learn all of the applications, it is more important to begin practice, maintaining a serene state of mind throughout. You will immediately realize that Cosmic Healing provides the practitioner with as much benefit as the student. The more you practice the more you heal.



Picture explaining the frequency-shift for 60 degrees time-axis angle.

The frequency ratio is determined by the angle between the two time-axes, as the picture shows. Our time direction is T1 while another time direction is shown as T2. The time direction propagating forwards (from past to future) is useful to our universe, while the backward-moving impulses of the timeleess wave do not "catch" the rotating field of "our" atoms. Secondly the time-axis at a right angle (90dg) to our axis T1 does not make any contribution, we experience this time-axis as non-existing.

As the picture shows, due to the angle of 60 degrees, 'our' atom experiences exactly half the time-speed of the other time-axis and this makes the frequency harmonic. As T1=2 times T2, the result is the simplest harmonic ratio of 1:2, determined by the angle of projection of 60 degrees between two time-axes. (Pythagoras' law for right angled triangles).

All other possibilities and other harmonic ratios fail to give non-destructive contributions for the necessary interference intensification. Other excitations of higher order harmonic ratios give more complicated time-axes structures of the rotating atom field and cannot be stable. Also because the couple-field feedback to the total mass (inertia) of the universes is not optimized (see the following paragraphs).

It supposes simultaneously the existence of a higher number of co-existing universes, which seems highly unlikely (higher than twelve). Therefore we must decide for the simplest three-dimensional geometric form: the equilateral triangular pyramid.

11. The ancient symbol of God, the Star of David.

It is necessary to summarize the above issues of the principle.

1. The choice of the mechanism of limitation determined the existence of all types of timeless waves, among which was the (most complex) three-

dimensional rotating time-field.

2. The limitation took place by interference quenching the primeval infinite vibration (possibility) affording more time-axes in three dimensions.

3. A time-axis is a part of the infinite force-field. This only exists as a single linear vibration.

4. For a three-dimensional rotating field at least six linear field waves are necessary, which are located spatially in time having angles of 60 degrees between the time-axes.

5. The angle of 60 degrees could only be created by an apparent frequency shift maintaining the harmonic vibrations of the rotating field.

These considerations determine the mechanism of blocking the infinite. It consists of six time-axes forming a closed three-dimensional object, which creates and restricts the speed of the rotating atom-field.

Though every time-axis carries two universes(universe and anti-univers), there are in the frightening depth of cosmic space twelve distinct cosmic structures, separated by the unbridgeable barrier of time. Not only are there eleven other universes apart from ours, *but they are all embedded in the same cosmic or geometric space*. All universes have the same size and the same energy content. The geometric space is necessarily the location in the nothing - in which the omnipotent vibration quenched itself by interference. It is the location for waves encountering each other, as it is for light-waves interfering with each other. But it does not require that every atom has twelve buldges at the same space-point in time. Or more crucially, it does not mean that every human being has twelve images of himself without knowing it.

It is the mechanism of interference synchronisation of the timeless waves which uncouples the universes at each space-point, simultaneously maintaining the time-propagation of each universe.

The equilateral triangular pyramid is the symbol of God, the Father as it is known everywhere in the universe (after lifting the cosmic isolation). We know it as the double equilateral triangles of the Star of David, also six time-axes with angles of 60 degrees. It means that the principle of the limitation was revealed to humanity centuries ago, but we did not understand its meaning so far.

make in your thoughts : The Star of David.

Link to next part

mainpage

the Iarga-story

philosofic Iarga-material


Iargan space-exploration fleet
leaving the ringed home planet
IARGA.

UFO-CONTACT FROM PLANET IARGA

POWERPOINT ON THE CASE (and here norwegian ppoint)
| audiobook mp3 a/30min | part2 | 3 | 4 |

interview with this contactperson from ca 1968?- translated to engl.subtitles on youtube
Translation of Denaerde interview (or txt)part 1 on youtube | part2







pictures made by div.artists - in center on how Stefan first saw them on their waterfloating ship, and right an idea of "them" - home on Iarga

INTRODUCTION (short introfile here)

This is a true story of a UFO contact from

a planet called IARGA - by the alien astronauts visiting our Earth. They say that their Sun is about 10 light years as

we count time from us, and that they have been observing us for some time.....

This story was first published in Dutch by Ankh-Hermes of Deventer, Netherlands in 1969 and has gone through 11 Editions and 40,000 hardbound copies in Dutch since then. It has been published as science fiction up to now because the publisher originally felt that this story would not sell as fact. Nevertheless it is a true account of real events and we are publishing it as such, here, for the first time, together with the very extensive follow-on data as the contacts continued right up to the present time. We have investigated this case extensively over the past 4 years and conclude that the facts do in reality verify and support the story. The witness is a very well educated and highly articulate master mechanical engineer and an architectural artist as well, a rare combination ideally suited for this contact if the alien visitors wanted their information to be understood and presented with any degree of accuracy.

The witness is also a well known multinational industrialist in Europe whose real name would be immediately recognized. He is the owner of several companies doing international business. To preserve his identity in order to protect his private life, we are using a pseudonym given him by the extraterrestrials themselves. They referred to him as "Stef van den Earde" (Stef of the Earth) from which Stefan Denaerde was derived. When I first met this man I was surprised by his size. He is a big man, about 6'4" tall and weighing perhaps 220 to 230 pounds.

contactperson Stefan Danaerde (!.9m tall) left and author W.C.Stevens.

He dresses conservatively in expensive business suits and is very courteous and polite. He is mild mannered and introspective by nature, and speaks with almost perfect economy of words. He says what he means and means what he says. In discussions he is not given to elaboration and volunteers little information by himself He answers questions forthrightly, directly and honestly, and looks one right in the eye as he speaks. He is not known to tell fictitious stories, but is considered to be a model of truthfulness and integrity.

He lives in an upper class quiet neighborhood in a professional suburb of Den Hague. His home, on a beautiful treelined street, looks to have a $150,000 to $200,000 value, and is well maintained and beautifully landscaped. It faces a park reserve across the street from him. The neighborhood looks scrubbed dean. This man was not a UFO buff and has no collection of UFO books and journals. He does not lecture or talk on his experience publicity or privately. He does not write articles on it or give interviews. He did not believe in the phenomena and had gone to no pains to evaluate if before his own contact. He still does not believe in UFOs as such.

His experience was real AND WAS IDENTIFIED. In the long course of contact discussions, he learned a great deal about our real history, where we have been and where we are going, and how we fit into this great universe. He found that our written histories are not very accurate because of our constant revisions by different regimes. He was shown a future course of events in store for Us if we do not change our ways, and was then shown how fixed we are in our course and the improbability that we will change in time. He is saddened and discouraged by our lack of real progress, and feels that revelation of this information is a needless and ineffective burden for a self-destructive humanity. He does not see Us changing in time! The first book, "Buitenaardse Beschaving", printed in Dutch, is an account of the contact experience up to the departure of the spacecraft the following day. The contacts continued, however, and a vast amount of technical information was communicated to the witness over the next several months and even years.

The Iargans compared their society and their philosophies to ours, and described advanced technologies, man's place in the greater universe, and what is in store for all of Us in the future. These communications continued and ultimately developed into a sort of mechanical transmission from a technical device aboard the spacecraft to the mind of the witness, something like the way it was done during his visit aboard the spacecraft in the Oostscheld, except that now the pictures were transmitted to his mind instead of viewing them on a screen. Unknown to the witness however, and this will be news to him when he sees it in print for the first time, communications experts working with NATO in defense systems had picked up a strange incoming RF (radio frequency) electronic signal in the vicinity of a high security NATO defense installation in the Netherlands, and became very disturbed about the nature and purpose of this transmission. It was in an unusual bandwidth and had a strange character. It also was only detectable within a limited area in Den Hague (The Hague near where the sensitive installation is located. NATO Intelligence, believing this may be an attempt to interfere with the defense installation and its equipment, moved hundreds of thousands of dollars worth of highly sophisticated detection equipment into the area to try to find out what was happening.

It seems that this strange signal would begin about 4:00 PM and continue for an hour or more several days each week. Now, before this information came to light, my interviews with the witness had shown that his contacts were coming in several days each week on a more or less regular basis. The witness's habit was to come home from his office about 3:00 PM daily, read his personal mail and relax in his living room for a while. Often, when he was contacted, the "telepathic" transmission would begin about 4:00 PM, and would continue for an hour or more. This strange coincidence became of paramount importance when I learned that the search for the strongest signal was taking them only a few blocks from this man's home where he was receiving the contacts!

I don't know whether they have identified the source of the transmissions yet or not, and I don't know yet if there was any other transmission that may have occupied this time period by pure coincidence. In either case I am sure that I would not be advised because intelligence information usually goes only one direction. A point of particular interest in this case is the fact that this witness was told by the Iargan visitors themselves, that their group had contacted four other Earth humans in a similar manner, and had imparted similar information to each of them, and that once one of them got into print and became known, the others would make an attempt to contact him. This will certainly be a curious validation if any one of these others do in fact turn up. These contacts are still continuing on a lesser schedule and an unbelievable amount of information has been imparted to this man. !

(As the text is scanned here - there may be some wordmistakes.The book is long ago out of print. The pictures can be some enlarged by clicking on them. Some words are translated into scandinavian in ()).

FOREWORD FROM THE AUTHOR

*This book is the account of a meeting with the crew of a spacecraft from a distant solar system in our milky-wa*y. There are many who claim to have spoken with alien beings, often resulting in strange or garbled stories, so many in fact that their credibility has decreased to almost zero. After my own experience, I think that I understand the cause of the problem. The honesty of these people is beyond reproach, but their ability as observers may leave much to be desired. These experiences take place in the zones between our normal, material method of communication, and the immaterial method that we usually describe as thought transference or telepathy. With this, the conditioning of the observer determines the

Healing Colors

White Chi

The color of the chi from the air, earth and sun is always white and acts as a calming agent for the surplus chi produced by the other colors. It also redirects this chi to areas of the body which need it. For this reason, use white in combination with another color in the proportion 7:3.

Shining white chi should be concentrated at the center, while colored Chi goes to the edge. This can also be reversed. It is also possible to blend the white and colored Chi together.

It is safe to use white chi when you are not sure which color might be suitable for a patient, especially when treating babies, toddlers, the elderly and the weak. People with minor problems can be treated with blue, green or mauve, while gold colored Chi or mauve/white Chi is better when the problem is serious. For a stimulating and strengthening effect use white-red.

When it becomes necessary to switch from one color to another, an abrupt shaking movement of the hand should ensure a smooth transition to a new color.

There is a very strong violet light in the North Star. You can dilute the color with white. White Chi is composed of red, orange, yellow, violet and blue.

Blue Chi

The effect of blue Chi is one of cooling, and hindering similar to yin or water energy. The opposite effect can be obtained with the use of red Chi.

When we draw the energy down, some peoples' bodies can't adjust to the energy immediately, so using blue Chi is always good. "Water blue' is the one element that always brings harmony and does not cause any harm.

a. Blue Chi, like yin, water energy, has a cooling effect. It also can act as a restraining agent.

b. Because of blue Chi's ability to cool, soothe and numb, it is particularly appropriate for promoting relaxation and sleep, reducing abnormally high body temperature, minimizing pain and swelling. It can also hinder the proliferation of viruses and bacteria and assist in the rapid clotting of blood.

Blue (and green) can detoxify and also energize.

Green Chi

While tangerine Chi can be quite dangerous, the action on green chi is gentle and harmless. Freeing up a damaged area so that cleaning can then take place may be done with green Chi. Once it's loose you can then use blue or organ's color Chi to expel the disease completely. It can therefore remove the disease and bad energy by locally sweeping either to and then out of the arms for the upper body or out of the legs for the lower body.

quality of the reception. For example, subjects which do not affect him personally will, within his abilities, be received with the greatest clarity; whereas anything that touches him emotionally will be strongly biased or not received at all. Due to this, even a sworn statement from a completely trustworthy observer is useless, because no guarantee can be given that he knows what really confronts him.

I realize that it must seem strange for me to warn the reader of the risks involved with this type of observer when I fall into the same category, but this is because I do not want to be just believed, partly because I know why a certain group of people refuse to believe. When you have read this book, it will be dear what I mean by this. The only means of checking the credibility of the observer is logic. Due to her cosmic isolation, humanity is ignorant in certain fields, and someone who really has communicated with a super-civilization that has evolved above the material state (the minimum demand for interstellar travel), and understood them, must have access to information that is new, logical, and that can be checked in order to be convincing. As I have said, I do not seek belief, I ask my readers to be critical, but to bear in mind that the subject is so complex that it would be unreasonable to expect my story to be faultless. The content of this book is divided into two parts; the first is a description of the planet Iarga and her inhabitants and, as such, meets the demand for an identification procedure which is a mandatory introduction to all exchanges between intelligent races. The identity of a race is determined by its planet and its history, and these must be explained.

The aim of the first part is therefore purely the identification of this alien race and is not an attempt to create some kind of picture of earthly ideals, something that we should try to emulate. Iarga is different in every way. The planet and her inhabitants have a different mentality and character, and therefore a different cycle of evolution. One difference is that Iarga is almost completely covered with water. The available area of land is. spread over numerous islands with a total surface area not much larger than Australia, and according to our standards, is much too small to feed and accommodate the billions of beings needed to reach the goal of their creation. The extreme efficiency of their planning and food production methods would be pointless on Earth, and their population density forces them to a kind of over-socialized community. Only beings that posses the ability to continually improve their mentality and eliminate all aggression, have a chance of reaching perfection on such planets. We do not have this ability, the reincarnation-selection of Iarga does not exist on Earth. Here, the weeds grow up with the corn until the harvest.

Despite the vast differences, a remarkable likeness can be detected in some things; so much so that these beings can be regarded as humans that have physically adapted to life on an alien world. Their intellectual, emotional, and creative capabilities are the same as ours, and if we had been placed in the same situation, we would have become roughly the same. When the second part of this book has been read, this will no longer cause any surprise; it will have become dear that these beings are not only our cosmic brothers and sisters, but that there also exists our ego-counterpart with which we will one day be united. With the introduction complete, the real work can begin. The reason for their visit is so strange that preliminary explanation is necessary. The human race lives in complete isolation from the other intelligent races for as long as the so-called "transformation phase" continues.

The plan of creation demands that we, like all others, complete the transformation phase in ignorance of our origin and our purpose. Through this we, create our individual identity and, at the same time, have the opportunity to develop our godlike talents by exploiting our creative powers and defining them, thereby earning our immortality.

The number of talent fractions is not infinite, so the time must come that the numbers of man are fulfilled. When this happens, the transformation phase will be terminated by certain external encroachments that will subjugate the will and sovereignty of the human race. The plan of creation forbids interference in the development of an ignorant race, thus the necessity for the planting of knowledge here on Earth. This knowledge appears to be comprehensive. To begin, the complete scientifically verifiable story of the creation, from the creation of time, matter, and energy from nothing; to the goal of the creation of the universe: the cosmic integration of all the intelligent races in one all-encompassing consciousness that is beyond our understanding. In this we are given a glimpse of the wonderful future that awaits Us. Beside this, a great deal of information regarding ourselves, our origin, our development, the present transformation process, the spiritual development after death, our creation mandate, and our future is given.

The first point is the most important, only when we under-stand the creation process, and in particular the development process of man, can we understand and accept the reason for the external interference that will take place in the near future. Without this knowledge the interference would be useless and therefore undesirable. Lastly, their information includes a general description of other intelligent races and their different evolution cycles, which will enable Us to approach a determination of our unique position in the midst of an incredible number of intelligent races. The fundamental reason for this book is the abolition of Earth's isolation and the announcement of the fulfilling of the numbers of man. Our first mandate was carried out in ignorance, the second will be carried out in full consciousness. The only question that remains is to what extent does this book reach its goal of removing the Earth's cosmic isolation. The question is all the more impelling when it is said that I had to give my word never to attempt to prove the existence of Iarga, because this would damage the individual freedom of mankind. I have fought with this problem for many years, until at last the problem solved itself. Even though I shall continue to avoid giving a direct answer to the question of the veracity of this story, the immensity of Earth-alien knowledge contained in this book will serve to prove beyond a doubt that the planet Iarga is not fiction, but fact.

Stefan Denaerde and W. Stevens:

contactperson Stefan Danaerde (!.9m tall) left and author W.C.Stevens.

CONTENT

- PART I
- Identification
- CHAPTER 1 Confrontation 11

- CHAPTER 2 Aboard the Alien Spacecraft 24
- CHAPTER 3 Planet Iarga 53
- CHAPTER 4 Iargan Society 88
- CHAPTER 5 Iargan Spacecraft 100
-
- PART II ON PHILOSOFY link
- apendix: understanding time
- other cosmic races

- you can click the pictures and they then open in new window
-

PART 1: Identification

This part includes the initial contact with the extraterrestrial visitors and the nearly 8 hours of events and discussions that took place aboard the alien spacecraft as the witness was shown and experienced scenes and conditions in the life of the Iargans, both on their home planet and in their spacecraft.

CHAPTER 1

Confrontation

Iarga; I can talk about it now, the fascinating dusky green planet with its somber pink sky is no dream but-just a moment. I must first sort out the mass of information gamed during my astounding experiences and relate it logically and coherently.

I need to do this for myself as well. Any explanation of my chaotic memories may help me to become my old self gain. It is difficult for me to remember the man I used to be. How I felt that beautiful summer evening on board my yacht that drifted like a huge white swan on the windless waters of the Oosterscheld (An art of the sea in the southwestern delta of the Netherlands.)

"Hey, Dad, do you know that the compass is broken?"

I took no notice; it was probably just one of my son's childish jokes. I sat stretched out in a deck chair, contentedly sipping my coffee and surveying the distant coast of Schouwen-Duive-land (An island in the delta.) where we planned to arrive before dark.

On the small strip of land above the horizon, I could see the light that marked the harbor entrance at Burgsluis. "Honest, Dad, it's broken. Come and look," persisted my son. Still disbelieving, I forced myself to stand up and walked over' to where my wife, son and small daughters were standing looking at the compass as though they had never seen it before in their lives. Something was definitely wrong. The map was hanging at a crazy angle, but worse still, the north indicator was pointing in the direction of the Zeeland bridge, to the east! I looked accusingly at the discoverer of the trouble. It wasn't out of the question that my young son was playing a joke on his father with a magnet. I was disappointed to find that this was not the case and so I started a serious investigation. In the meantime, Miriam did the dishes and put the children to bed. By the time I decided to return to Burgsluis on the motor, it was getting quite dark, and the fact that I had been unable to find the cause of the trouble irritated me immensely. Miriam was right in saying that I should not let a compass spoil such a beautiful day, but I could not rest until I knew what was wrong. Ah well, I could do that in the harbor.

- 

  arrow where the contact took place in the bay of Oosterscheldt in the region Zeeland in Holland, in the mid 60's.

- I pushed the tjalk (an old-world, flat-bottomed sailing ship) at full power through the darkness of the *Oosterscheldt.* There was the light buoy. I read the number automatically and turned sharply to port. In the distance lay the next buoy, marking the channel to Burgsluis. About six miles and we would be home. But things didn't go quite the way I had planned. Something unbelievable happened.

  Suddenly, out of the darkness, a strong, blue-white searchlight shone in my eyes from a point directly in front of the bow, and at the same time I heard a high-pitched whining noise above the noise of my motor. My heart pounded. It came so unexpectedly, that it must have been several seconds before I acted. Reverse, full power! Damn, it was too late! With a frightening noise the tjalk came to a standstill against something solid, but what? Who on earth would be in the middle of the channel without lights? With shaking hands I stopped the motor and in the sudden stillness saw the startled face of Miriam appear in the cabin doorway.

"Is anyone there?" I yelled over the water. In answer the light went out, but no reply. Miriam came on deck and behind her stood the children, wide eyed with fear. "Look... there... that flat thing in the water." It looked like the hull of an overturned ship or pontoon, but we were at least thirty feet away and couldn’t possibly have hit it, whatever it was. "Is anyone there?" I called a second time. The searchlight flashed on again; the strangely small beam of light swept over the water and cast a cold glare on the side of the tjalk. I caught my breath. Floating on the incoming tide was a body, face down, apparently dead. The actions that followed were carried out at nerve-racking speed. There was only one thought in my mind: to do something quickly, before the body drifted away into the darkness.





how they stood on the ship floating when he first saw them- picture of jim nichols

pictures not from book

Instinctively, I carried out the motions that I had so often gone over in my mind in the event of one of the children falling overboard. Seconds later, I jumped overboard with the line from the lifeboat in my hand. But what now? I was standing in less than three feet of water, and my knees and ankles hurt from landing on something as hard as steel. In my confusion, I saw the line from the dinghy drifting away. I stood up and dived to catch the rope, and, swimming with the small boat behind me, managed to grab the body. It wouldn't move. How would I get such a weight into the boat? First, tie the rope around him, climb into the boat myself and pull his head above the water; yes, that was it. Just then an alarm signal began to sound somewhere in the back of my mind. What kind of a man was this? He was wearing a kind of metallic suit and around his head was a rubbery ball which reflected the blue light so strongly that I was unable to see his face. I began to think about astronauts, but how on earth did he come to be in the Oosterscheldt? I started the outboard motor and began slowly back toward the tjalk, but what now? What should I do with this strange burden beside me? Why had I gone to all this trouble? My indecision grew by the minute.

The blue light made it plain that I must carry on. It was kept in my direction by someone who followed the rescue closely from beginning to end, but what did they want? In terrible confusion, I came at last alongside the tjalk, tied up the dinghy and stopped the outboard. In the silence, I heard the voices of Miriam and my eldest daughter. Thank

If there is a need to energize with the organ's color Chi, first energize with pale green Chi. Always use green chi before using the colors purple, tangerine and red.

Use the throat to activate and draw the green Chi up to the crown, rising to the universe to be multiplied and brought back down for use. Always add blue Chi when there is pain. The motion of pushing and pulling through the affected part is very powerful. You also can also use the 'sword finger' in a small area and for infection.

Green can also be used for energizing together with violet; first use green and follow with violet.

Pale green and pale tangerine chi can be employed in sequence, as the first acts on the 'sick' energy, reducing it to a form which can easily be driven out by the second.

Simultaneous use of pale green pale tangerine and white chi in the ratio 2:1:7 is recommended to treat stubborn areas because the effects are intensified when these proportions are used together.

In the treatment of cancer, dark green and tangerine Chi may be employed, preceded by blue. This can assist in toxin removal, and in the cleaning and freeing up of disease affected areas so that necrotic cellular tissue is released. These colors can relieve congestion and free up 'sick' energy which is 'stuck' when used with brushing movements over the affected areas. They also help with treatment of colds and elevated body temperatures, and in the dispersal of blood clots.

Red Chi

Cerise chi makes the area to which is applied stronger, while crimson chi has the opposite effect. When using color for healing, project luminous white in the center and cerise at the edges for a strengthening effect. Always combine red with blue and green; never use it on its own.

Cerise mixed with white, because of its expansion abilities, can help widen blood vessels and breathing tubes. It also helps those with heart and asthma problems.

Red chi with its qualities of warmth and expansion, has a number of benefits. It is good for the circulatory and respiratory systems and the blood, as it expands blood vessels and other tubes, thus improving circulation and breathing, particularly for heart patients and asthma sufferers. It also brings increased energy into the blood and helps allay feelings of fatigue or weakness, driving out 'sick' energy along with toxic substances and other waste materials. It can also help those who are sensitive to allergens. It may help those whose lives are near the end have a longer period on earth, and promote revival of consciousness.

Avoid the use of dark colors, which may cause an adverse reaction. If a person is suffering from a sexually transmitted disease, it is not advisable to treat him or her with chi which is crimson. Chi of this color makes the microbes that cause such diseases multiply at a fast rate and can also produce an inflammatory or constrictive reaction.

goodness everything was all right there. Then my peace of mind received its death blow. There was suddenly a sea of light, a great diffused light *under the surface of the water.* A sound made me turn toward the strange object in the water and I saw a dark shape wading quickly toward me. It was a perfect copy of the being I had fished out of the water, with the same shiny metallic suit and a transparent ball around its head. Step by step, it came closer, and I instinctively grabbed the boat hook to defend myself. He held out an arm in a friendly gesture and turned his face toward me. I sprang back as though bitten by a snake; a wild fear cut off my breath. It was a nightmare. A terrible, indescribable feeling took hold of me. The being in front of me was not human! An animallike face, with large square pupils in the eyes, eyes which were both hypnotic and self-assured. It struck me like a thunderbolt. Here I stood, facing an alien being from a race more intelligent than my own! But why was I still so afraid? I cannot explain. If it had been a gorilla, for example, then I would have quickly sprung on board my ship and put up a fight with the boat hook to prevent the animal from coming on' board. There would have been no time for the fear that came from the feeling of helplessness in recognition of his superiority.

The fear grew into panic, a panic which told me to get away from there as quickly as possible, before it was too late! I sprang overboard again and raced through the shallow water toward the ship as though the Devil were at my heels. Panting, I pulled myself on board and started the motor. Reverse full power. I wanted to get away from there as quickly as possible. The ship didn't move an inch. Over the bow I saw the being pull the dinghy onto the dark platform, lift the body in his arms and walk away with robotlike steps. It suddenly went dark and they were gone. With a feeling of apprehension, I stopped the motor. The situation on board was surprisingly peaceful, for they had no idea of the real drama. There was a feeling of satisfaction over father's ability as a lifesaver. My eldest daughter had developed the theory that we had rammed a submarine, which was not so unlikely, considering we were dose to a naval training area. Only Miriam realized that something was wrong. She looked at me as though I were a stranger and her uneasiness grew by the minute. She had never seen me like this before. She poured me a whisky and sent the children to bed with the excuse that we had something to talk over. The alcohol did me good, but now it seemed that I had another problem: Miriam didn't believe me! "This trip is too much for you, Stef. There are no men from Mars in the Oosterscheldt." She kept talking, perhaps to try and talk some courage into both of us. I couldn't just stay inside; I had to see what was happening outside.

With a flashlight in one hand and a boat hook in the other, I stood on deck and let the beam of light play over the platform. It lay just above the surface of the water, a sinister4ooking dark-gray thing. Its diameter was about the same as the length of our ship, certainly fifty feet. It was resting on a ledge, which reflected the light so strongly that it looked like glass. In the middle was a pillar, slightly twisted, about six feet wide and eight feet high. The total size of the thing surprised me. I knew what was under the water. I could walk at least the length of a swimming pool without falling off the edge. Could this be one of the much talked-about flying saucers? Were they really so huge and could they also operate under water? I turned the flashlight out and began systematically probing around the ship with the boat hook. In front, by the bow, about two feet, and aft, about four feet. It was strange that each time I had to use force to pull the boat hook off the bottom, as though someone were holding it.

Suddenly I remembered the strange trouble with the compass-magnetism! We had collided with a huge, magnetic monster! We were imprisoned, stuck fast on a huge magnet. In the grip of strange, unearthly beings. The only possibility of escape was the plastic dinghy. In case of emergency there was room for all of us. The dinghy still lay in the same place on the platform, and in the peaceful stillness of this complete isolation a daring plan was born in me. After all, the dinghy was only about thirty feet away from me. For the third time that evening I jumped into the water, waded as quickly as I could to the boat and pulled it free. Within half a minute I was back on board with the dinghy alongside. So, that was that! I began to regain some of my self-confidence. But my uncertainty came flooding back as I heard a scraping, hissing sound. I grabbed the searchlight and shone the beam on the platform. On the edge, a sort of lid hinged open slowly and steadily. Out of the hole crawled two figures, dressed in the now familiar space suits, who pulled out some objects after them which were joined together by cables or wires. Their movements reminded me of the old-time silent films, fast and jerky. What were they doing now?

They stood on the platform and, with one hand against their ball-shaped helmets at about the height where their foreheads would be, made slow, respectful bowing movements in my direction. I understood. What a relief. It was a greeting, a friendly, respectful greeting. With quick, short paces they walked to the edge of the platform, where the bowing was repeated and emphasized, and then they stood like statues in the light of my flashlight. A strange and dramatic scene; on the

Oosterscheldt a man is confronted with an alien intelligence. But the man was poorly prepared for the meeting; he was nothing more than a sailor in difficulty who could feel his legs trembling in his wet clothes. The two figures in front of me were about five feet tall and from a distance looked deceptively human-arms, head and legs, all in their proper places-but their legs were shorter than ours so that their arms reached down to their knees. Their metallic costumes were smooth and seamless. Only by the shoulders and elbows were folds to be seen. The short, heavy legs ended in broad feet that also stuck out behind, and the front part of their footwear was split in the middle. The hands were covered by supple, ribbed gloves; these were different from ours too in that not only the thumb but also the second finger was enclosed. They were heavy, clawlike hands.

A broad, gold-colored belt around each of their middles, sewn with motifs and tools, was particularly noticeable, one piece of which was dearly a hammer with a sharp striking edge. And on their right side was something that vaguely resembled a pistol. A kind of drum, wound with thin glistening thread, rested on the middle of their stomachs. The remainder of their equipment was unknown to me. I gamed the impression of immense physical strength, not only from their long, heavy arms and enormous shoulders, but also from their quick movements. The round ornaments around their heads were less transparent than I had originally thought. When the beam from my flashlight fell on them, they changed into glistening Christmas-tree balls, and only with more indirect light was it possible to vaguely make out their heads.

The silent confrontation was suddenly broken by a bud voice. "Do you understand English?" I nearly jumped out of my skin. Owing to my surprise that they could speak English, I didn't realize that they had asked me a question. The voice was totally devoid of any questioning tone. It sounded more like a statement.

"Do you understand English?" The same statement floated over the water.

"Yes, I do." "We want to thank you for the rescue of our crew member."

.... of course. Who are you?"

"We come from another solar system."

"My God," I called back. The situation was so strange that at that moment I couldn't think of anything else to say. There followed a short silence and I wondered about that strange accent which, in fact, wasn't English at all. To my ears it sounded more like Dutch, my own language. I could understand it perfectly, but I couldn't repeat a single word of what they actually said. The voice came again, and over the still dark water an unbelievable conversation began. "Is your ship damaged?"

"No, I don't think so." "Will you turn the light out?"

"All right."

"Thanks. Does the ship belong to you?"

"Have you a radio transmitter on board?"

"We would like to show our appreciation for the rescue of our crew member."

"You can do that by simply explaining some of this to me. It's just too much. How long have you been here?"

"We have been near Earth for some time."

"Why do you hide? Why haven't you tried to make contact with us?"

"Our reason is that you do not know the laws of a higher civilization."

"I don't understand."

"There is still a great deal that the people of this planet do not understand." I hesitated. How much did they know about us? "You know us well, then?"

"We have studied you for some time."

"You don't have a very high opinion of us, I gather."

"Your remark shows some insight."

"Are your people more intelligent than mine?"

"No, only more developed."

"If that's so, then I don't understand why you haven't made contact with us. You could help us."

"That would constitute a breach of the laws of nature." I shrugged my shoulders. Despite the strange situation, I began to feel more at ease. This was an unimaginably important meeting, and I began wondering how I could manage to squeeze some information out of these beings. I could learn things that man, for centuries, has only been able to guess at, and I could find out about their spaceships!

"We wish to give you something as a token of our thanks. If we give you an object with which you can prove our existence, it will surely also be worth a great deal of money. We hope that you will accept it. It is sterilized."

"What is it?"

"It is a block of inert metal that is many times stronger than your best steel and only half as heavy. It has a superconductive structure that is so straight that current can only flow through it when a positive pole is placed directly opposite a negative pole, in line with the structure of the metal. If one of the electrodes is moved only one-thousandth of an inch, the current ceases to flow. With this structure it is possible, with correctly placed electrodes, to form a spiral current pattern, the result being that when a direct current is connected to two feed wires, a supermagnet is created with a negligible current consumption. Also, the metal has a melting point much higher? than anything known on Earth. We use this metal for the outer skin of our spacecraft. That is the gift. We hope you will accept it."

I was greatly impressed. "This is incredible. I am grateful. I expected no gifts for saving your crew member, but I imagine that your intention is to help us and I accept it with heartfelt thanks."

"We admire your unselfishness, but we must point out that the block of metal represents a far too advanced technique to be of any use to you in your research. Technically speaking, it is useless, but you are right in thinking that something else is behind it. We wish to give you proof that you are being observed by intelligent alien races, who know you so well that they are able to communicate with you, but refrain from doing so. We live in the perhaps desperate hope that people exist who, with this information, will be able to understand the reason for our reluctance."

"And what is the reason?"

"You do not have the values, the ethics, of a developed civilization. Because of this, the human race has, as yet, no chance of eternal survival. It blocks the way to cosmic integration."

I shrugged my shoulders. I had never heard of "cosmic integration." They also began to irritate me. I found them a little too arrogant.

"You regard us as children, then?"

"No. An adult does not blame a child for the fact that he is not yet grown up."

"But you do blame us for something?"

"And what is that?"

"Any English-speaking Negro, Chinese or American Indian can give you the answer."

The conversation was not going exactly the way I had imagined. I had to think of something else, and at the same time be careful that the contact was not broken. I was afraid that they would climb back into their saucer and that I would never see them again.

"I think I understand what you mean. May I ask a couple more questions? This is a once-in-a lifetime experience." "That is correct. The present generation will not have the chance again."

"Answers to my questions seem to me to be much more important than the block of metal."

"Your insight surprises us. The answer to carefully selected

Tangerine Chi

When using orange Chi, always use blue Chi first; to tone and calm down the ailing body area, before applying the vitality of orange.

Pale tangerine chi with added white can be used; however certain areas are inappropriate for treatment by this color because of its power. Do not use with the eyes (including retinal problems), heart, head, throat, brain (for example bleeding in the brain) or the spleen.

The large intestine benefits from the use of tangerine chi, but this color should be used sparingly on areas like the solar plexus and navel. Appendix problems should not be treated with this color as it could exacerbate the problem. Tangerine chi has an effect on the bowel, and can also aid in returning an unconscious person to consciousness or in stimulating someone who is dying.

To treat cancers of certain types, dark green and dark tangerine are suitable because of their ability to destroy. Always avoid the head and the heart when using orange.

Forcible removal of waste products, toxic substances, ‘sick’ energy, viruses and bacteria
Menstrual difficulties
Waste elimination problems
Freeing up ‘sick’ energy
Breakdown of clots in the blood
Problems of the urinary and respiratory systems
Diseases of joints and connective tissue
Common cold
Problems caused by allergens
Cysts

Yellow Chi

Yellow Chi has a close connection to the nerves, the bones and the bone marrow. It is the color of the spleen; in Taoism we feel the spleen is involved in the assimilation and processing of food and the appetite. This doesn't mean eat a lot, but when the spleen is balanced the appetite will be controlled.

Chi which is yellow in color is beneficial in the treatment of nerves as it promotes re-growth. It also helps in the repair of fractures and cells. It is good for the health of bones, tissues and organs. It has the power to increase bone marrow production.

Violet Chi

Violet Chi has the properties of all the other colors. It’s used for severe types of sickness.

questions is certainly much more important."

I was surprised that they agreed to my request so quickly and easily; they suddenly seemed much more friendly.

"In that case, I would like to know what your spacecraft looks like, and, more important, how it is powered."

"You disappoint us with this question about technical knowledge. The most dangerous natural law governing the development of an intelligent people states: a highly technological society does away with all discrimination or self-destructs. To supply technical information to a people like yourselves is a serious crime against the cosmic laws. The last thing that you need is technological information to increase the gap between your intellectual development and your almost nonexistent social development. Carry on playing with your Mars 'probes for the moment, as half of your world's population lives in poverty and hunger. The only information you need lies in the field of societal standards."

I was terribly disappointed. There went my dream of learning breathtaking technical discoveries.

"I am afraid that very few people would be interested in that kind of information."

"We are afraid so too."

"When do you think that the time will be ripe to give us information about space travel?"

"The cosmic isolation of an intelligent race can only be lifted when the minimum culture level has been reached; we call it 'social stability."

"Hmm... and this conversation, then?"

"We feel ourselves justified, because of your actions, in supplying certain small pieces of information which will set the present generation to thinking."

"What do you call a socially stable culture?"

"We could give you the answer, but we doubt that you would understand it."

"I will take that chance. It seems to be important."

"Be sure that you know what you want. This answer demands an explanation in word and **vision for at least two days.** Furthermore, you must choose between the material gift-the block of metal-and the immaterial gift in the form of information. We cannot give you both."

"I don't understand what one has to do with the other."

"There is still so much that you do not understand, but after our explanation, this question will also be answered for you.

"Are you really prepared to spend two days explaining this to me?" My tone dearly showed my surprise.

"We are, for at least two days. A conversation of shorter duration would have no point; it is the minimum time in which we can give you the necessary information. We have all the time in the world-space travelers are never in a hurry-but we must warn you: we doubt that the information that we will give you will make your life happier, so be sure that you know what you are doing."

I shrugged my shoulders. It was dear to me that these beings were devious, but I did not intend to let this one chance in a million slip through my fingers.

"All right, what do I have to do?"

"We have a small, sterilized decompression chamber, and only from there will you be able to hear us and see our screen. Food and drink you will have to bring from your ship, which should stay here. We must warn you again: you will become wiser for this experience but not happier."

"We can leave with our ship whenever we want, right?"

"Naturally, but if you leave us it is for good, and with our blessing. All we ask now is a solemn vow from you and your wife that as long as we are here you will not contact anyone else and will do everything in your power to keep our presence a secret."

"I need to talk it over with my wife."

"Naturally." But my decision had already been made. I will not tire you with Miriam's arguments, nor with the latter part of my conversation with the aliens, which consisted only of a number of instructions regarding anchoring, lighting, knock signals and so on. The visit itself was to begin early the following morning, for which preparations were needed.

The two statues turned about and, laden with their apparatus, disappeared as quickly as they had come. As if sleepwalking, I went slowly to the bow and, as agreed, let the anchor fall onto the hard metal bottom complete with an extra piece of chain.

Soon afterwards the platform sank with a bud zooming noise under the surface of the water. A dull shock followed and the ship floated in its element once again. A short time later my brain received yet another jolt. The dead stillness of the night was broken by a terrible noise, a bud zooming combined with the screaming, howling tone of a circular saw. The anchor chain jerked tight and the surface of the water became strangely disturbed. The spaceship was acting as a submarine. We were pulled forward over a broad foam track which was lit from beneath a dull yellow-green light. The noise was unearthly and frightening. I stood, fascinated, and began to wonder what I had let myself in for.

CHAPTER 2

Aboard the Alien Spacecraft

"Good God!" Miriam's exclamation so early in the morning reflected both surprise and repulsion. In answer to my repeated knocking signals, the huge, round platform had risen again above the surface of the water and now, in broad daylight, the sight was much more impressive. The slightly domed platform lay, just as it had yesterday evening, with its edge level with the surface of the water. Its surface was for the most part as smooth as polished stone and dark gray in color with scattered patches of off white which made it appear as though someone had been throwing around bags of flour. Over this otherwise perfectly smooth surface ran innumerable ragged, charred grooves which ended in a small crater, as though something had exploded there. Nearly all the scratches and grooves ran in one direction and gave the impression that the spaceship had been grazed by enemy fire or that someone had been at work with a blow torch. All in all, it was an ominous sight, and Miriam's reaction was not very reasoning.

"Stef, please don't go. Something as alien as that can only spell trouble for Us all."

She was right, of course. There was something wrong about entering this thing, but even the latent fear from last evening and the leaden feeling in my stomach brought on by the sight of this forbidding platform were not enough to hold me back. A few moments later I was sitting on the edge of the platform, drying my feet after wading through the water, I donned my shoes and socks and, armed with sandwiches, thermos and note paper, I began to look for the opening that they had described. I had hardly taken a couple of steps when a round, safelike door slowly began to open near the edge and a small quantity of sand and water which had settied in the jomt was blown away by a stream of compressed air. I went closer and looked down through a round hole, about three feet in diameter, into a cubeshaped space about eight feet across. Once again, I heard the voice.

"Welcome on board. Be careful as you come below. The ladder is dangerous for you."

Indeed, the "ladder" was nothing more than a pole with staggered steps on either side formed to place my feet. I stopped in my descent and waved to Miriam, saying, "Don't worry. I'll be back around five o'clock. The reception has been very friendly, and it's really quite cozy in here."

Once below, I cast my eyes around the room. Unimaginably complicated equipment lined the walls and the ceiling. The only things that were vaguely familiar were huge reels and drums, wound with every possible size of cable and pipe. In the floors was a metal door that looked remarkably earthly, with a round knob in the middle over which I nearly stumbled. In one corner stood a kind of desk with rows of knobs, and above, a panoramic screen, about five feet long and three feet high, that glowed with a soft green fluorescent light. Behind the desk stood a strangely normal-looking chair with a metal frame and leather upholstery.

The voice invited me to sit and explained that the seat had unlimited possibilities for adjustment but that certain instructions from the voice would be necessary before I could be comfortably seated. "Yes, thank you. What happens now?"

"Introductions would seem to be the best way to start. Will you answer a few questions?"

"Yes, of course."

"How should we address you?"
"Call me Stef."

"All right, Stef. The language we speak is not your own language, although it seems to be. It is the language of all living species in this universe. Even a plant or an animal will understand it. This language was spoken on Earth before the Babylonian confusion of tongues. You don't hear words but sounds that are directly reflected by your emotional structure, the life-field. Therefore, don't try to understand words, but listen to the reflections of your soul."

"Is that a kind of thought transference?"

"Not exactly, but you can compare it with that."

"I understand."

"How old are you?"

"I am forty-three."

"Are you in good health?"

"Yes, perfect."

"Have you a high social function?"

"High? What do you mean by high? I am the director of a business with a few hundred employees."

"So you are a representative of the directing class of the Westblock?" (husk møtet skjedde på 60-tallet)

"I don't quite understand the question. What do you mean by Westblock?"

"Let Us ask, then: are you a supporter of a free economy?"

"Yes, without a doubt."

"Now it is your turn. Would you perhaps like to see Us from dose up?"

I tensed involuntarily, and my heart began to beat faster. "I am afraid that I will get a shock if I see you."

"That is true. Nothing is more intense than a visual confrontation with another intelligent race. Do you feel strong enough not to panic?"

"Now that I know that I have nothing to fear from you, I will not panic."

"You certainly have nothing to fear from us; on the contrary, we are indebted to you. Look through the window to the right of the screen. When we turn on the light, you will be able to look into our navigation room. Ready? Right, then, here we go."

I looked into a huge, round chamber, about forty-five feet across and nine feet high. From the decompression chamber I could see over the greatest part of the navigation area, with its vast contents of instruments and control panels. Strangely, all the instruments and panels were mounted on the floor with walkways alongside and separated by vertical metal grills that reached the roof. Everything was dark blue in color, almost black, causing a very strange lighting effect. The dominating blue-black surfaces acted as an almost invisible background against which all the white or polished metal knobs, handles and instruments stood out in dear relief as though luminous. The encompassing vertical wall of the dome looked as though it was made of glass; the highly polished material reflected strongly and gave a very strange lighting effect from the reflections. On many of the panels diversely colored lights burned, interposed by dark transparent strips on which flashes or darting lines could be seen. An imposing piece of technology. I suddenly realized that there was no sign of life whatsoever. "Well, where are you, then?"

"Prepare yourself. You may see Us now." A light came on illuminating an area directly in front of the window. I sprang back! In spite of my mental preparation, the paralyzing fear had returned quite suddenly and cold shivers ran over my scalp, through my neck and over my shoulders. On the other side of the window, in a half circle as though at a conference table, sat eight strange humanoid beings. Their faces and forms radiated as much primitive animal power as haughty intelligence superiority. I felt again the uncertainty of yesterday, a reaction to their obvious superiority and self-assurance. I am convinced that any intelligent man would have felt the same, and that this reaction is a part of our makeup. The same feeling that I did not belong here, that even these steel walls could not protect me from

The qualities found in all colors are contained in purple chi, therefore it is particularly effective for serious illnesses. Mauve (light purple) chi which contains elements of blue and green, helps to restore organs and nerves affected by disease or trauma.

Although mauve chi can be employed on certain kinds of severe infections, chi which is dark purple should be avoided when diseases of the respiratory system are present, as it could cause the proliferation of disease causing microbes.

Violet Chi is use chi that is pale white/green or pale white/tangerine and, selecting each in turn, with a brushing movement apply to the whole spinal area and especially to the area where the trauma is located.

If purple chi is used in combination with other colors, it will intensify their qualities and if used together with red, tangerine or yellow chi can be dangerous; it may cause the undesirable proliferation of some cells.

Dark electric violet can be used for tumors or cancers. Always use the blue or green first.

In order to make an area which has become weak stronger, mauve mixed with white can be used, but for really fast strengthening use cerise mixed with white.

Both white and violet have the properties of all the Chi colors. The difference is that violet Chi has a greater penetrating effect and is easier to assimilate than white.

Because bright purple chi has been acted upon by the soul, it has the capacity for independent thought and action.

Energy or chi which comes from the air, the earth and the sun is called purple chi. There is a second type of chi with this color, but having more brightness – this has been called bright purple chi and is derived from the soul through the crown of the head, the point connected to the North Star or Big Dipper.

Bright purple chi can only be brought down from the universe via the crown point if the practitioner has highly developed senses, The effects of chi from air, earth and the sun depends on the development of the practitioner’s soul.

In contrast to purple chi, the chi which is bright purple in color has a much greater potency because it can help in the restoration of nerves and organs which have been affected either by disease or trauma. This bright purple chi can be used to remove infection and to promote fast healing, even in the case of serious illness.

In addition, this chi has been said to possess its own consciousness (Master Choa Kok Sui. Advanced pranic healing:49)

When cancer and other growths are being treated, use bright purple chi because it has the ability to destroy. However, beforehand, the affected area should be energized with pale blue chi.

the mental impact made by this intelligent "pressure group" from a much higher level of civilization and development, with their fantastic knowledge, belonging to a strange, distant world. Their unearthly, somewhat animal, faces, with a dynamic expressive ability, emphasized the difference in our places of origin to such an extent that I am convinced it touches areas that to Us are still taboo, and which have been since time began. When you are unable to draw, how on earth can you expect someone else to draw a face that he has never dreamed existed? How can you create a portrait with words? My friend, Rudolf Das, who accepted the task of drawing the pictures of this book, was driven nearly to distraction by my dubious attempts to produce a good likeness, one which would demonstrate their superiority. He finally convinced me that even a photograph would not effectively convey what I had in mind. The facial expressions must be left, unhappily, to the imagination of the reader.

It was the hypnotic effect of their eyes, with their large, rectangular pupils) that made the deepest impression on me. They were the thoughtful, peaceful eyes of deep philosophical thinkers that were studying me with quizzical friendliness. Their heads were about the same size as ours, only slightly deeper toward the back; and in the middle of the skull was a bony ridge that changed into a deep groove in the center of the forehead. It gave the impression of a skull divided into two separate compartments. Toward the back of their heads the ridge ended in a semicircular muscle formation that ran down the neck and into the shoulders, making the side view of the neck much heavier looking than ours. The same is true of the whole construction of their bodies. They were much more solidly built than we are. Their arms and shoulders, although of much the same proportions as ours, were much heavier and more muscular and, combined with the clawlike hands, gave an impression of strength that would have come a dose second to a bench vise. All this combined with their broad chests and short stocky legs made them look as though they would not even step out of the path of a gorilla!

Their muscle tissue also seemed to be different, more like solid rubber, and their thin skin followed the contours of their muscles more closely than ours. The top of the head to the back of the neck was covered with short, smooth hair that shone like the coat of a smooth, furry animal. The color of this hair was different with each of them; rust-brown, gold and silver-gray showed either separately or mixed. Their hairless skin had a pale, glasslike sheen to it. Along the edges of the face the skin showed slightly darker gray-brown than in the middle. As they turned their heads, the skin seemed to reflect the light and shade of their surroundings. This changing color effect was something that caught my attention many times. Their teeth were two seamless white strips, above and below, that closed in a scissorlike fashion. Both their teeth and the yellow-white of their eyes reflected the strange lighting in such a way that their faces looked slightly artificial. Their movements were also strange.

They could sit or stand perfectly still for much longer periods and more often than we would even attempt, but when in action, their movements were lightning fast and emphasized their tremendous strength. They were like volcanoes. After a period of rest, they would erupt into a wave of energy and temperament that would have made a Spaniard jealous. They were wearing a kind of uniform in the form of dark-blue, silky overalls, with three-quarter sleeves and a deep V neck. Under this was a white shirt with a rather old fashioned high collar around the back of the neck. Around their waists was a broad, gold-colored belt, decorated with what seemed to be atom formations, which ran along the edge of the deep V in the neck as well, incorporating, however, still other motifs in its design. (cont.under)



The following is text for the picture of the humanoid from Iarga: *Humanoid from the planet Iarga, which is a little more than ten light-years away from Earth. Although these beings have the same origin and identity as man, and their physique is comparable in many ways, there appear to be many great differences which result from the different planetary conditions. Their planet is larger, the gravity is nearly 3g, and the atmosphere pressure is more than 7 bar with higher nitrogen and ammonia contents than our air. The average wind speed is less than ours; but the denser atmosphere in combination with* *heavy rains and the higher terminal velocities, sometimes cause storms that an unprotected human could not survive. To withstand these conditions, they have a short, compact physique with well-developed muscles, especially the legs; armored skulls, and deep-set eyes. Their darting movements are interposed with periods of rest, during which they only move their heads. They walk stiffly, with short steps, as if they are walking on ice.*

They were originally amphibians, and really belong in the water. Their bodies are as streamlined as that of a seal, and are covered with short smooth hair, like an otter. Their hands and feet are large and broad, and they have webs between their fingers and toes. We could not possibly compete with them in a swimming race. They are capable of killing a small whale-sort by ramming it like a torpedo, a group will then tow the catch back to the shore. (swimming).

Their sex drives are different from ours, and they find sex less important; partly because they derive less pleasure from it than we do. The population growth is slow, and they lack the sex signals of humans, such as full lips, ear lobes, pointed nose, protruding female breasts and the external male sex organ. This is why it is not necessary for them to cover their bodies as we do, their reproduction impulse is born of love and not lust. We seem to be abnormal in this respect. Their weak point is the development of their individuality. They do almost *everything in groups (tribes), they think collectively and they obey the laws of their society to the letter. They live for and through the friendship and love within the group.*

cont. from above: .....I decided to end the silent confrontation. "I'm sorry that it's taken so long to get used to the sight of you."

"We have only compliments for you. You have remarkable self-control. You demonstrated the same quality with your rescue of our crewman, for which we would once more like to offer our thanks."

"Oh, that was nothing. When I see all the technical capabilities at your disposal, I wonder if my help was really necessary?"

"The value of an unselfish deed cannot in any way be influenced by asking afterwards if it could not have been done in some other way. As a matter of fact, your help came so quickly and efficiently that it would have been impossible for Us to have managed it in a shorter time. It was precisely this speed and efficiency that gave Us the idea that you could possibly be a man with whom we could communicate, the first communication with a representative of this world. Make sure that you realize what this conversation will demand of you. You will be speaking with a race that is far ahead of yours in evolution. This means not only an enormous technical lead, but also the same lead in mental development and inner culture. This last is the most difficult to explain and yet we must make it dear if you are to understand what social stability represents.

"We will therefore lead you, step by step, through the secrets of a highly developed culture, and we will do this by means of a holographic film which will take you to our planet Iarga. We will let you see what the world 'civilization' really means. It will be an interesting experience for you, the value of which is impossible for you to judge at this moment. But what you also cannot judge is the personal danger involved. We know the dangers and will protect you against them. The most important thing for Us is to ensure that your freedom of thought is not damaged. Freedom of thought is the essence of humanity, and if we were to damage that we would, according to our ethics, be committing a crime. Therefore, we will only convey knowledge to you, and not convictions.

"We wish no discussions. We will only answer questions when you do not understand something, and we will remain silent when you do not agree with Us. We will help you to climb the ladder of knowledge, rung by rung, first to social stability, then to the super culture and, if you can follow this, to the misty heights of cosmic integration. "We will only give you knowledge. **You must remain free to do with this knowledge what you will**. If as a result of this knowledge you should find yourself forming any convictions, do so with care. Make sure that they are lasting convictions, born of independent creative thinking, and not the sort of passing convictions that the impact of strenuous visual emotions tend to provoke. These pseudo convictions paralyze individual freedom and make men rigid and dogmatic.

"Knowledge is a material part of the human condition and, as with all material things, it can be mechanized or automated. We have at our disposal a method of teaching that utilizes a certain type of radiation. This takes place at a speed of which you never dreamed. Above your head we have fitted one of these radiation reflectors. It makes the spoken word unnecessary to a great extent. On the screen in front of you we will show our explanation in the form of a picture story, the words of which serve only to direct your attention in a certain direction; we call this fixing the concentration, but the true source of information is the radiation. You do not have to take notes; information gamed through radiation remains locked in the memory forever.

"Experience this adventure with an open mind. Anything else will disturb your concentration. Do not become angry if we say something that goes against your principles. We have no intention of antagonizing you. If we do so, understand that it is purely a result of our ignorance regarding the many taboos and prejudices of western man."

They started the radiation device working with the film. At first I was not quite sure what was happening. I felt cold and somewhat lightheaded suddenly, a feeling comparable to having had a little too much wine. You believe you can think very dearly but you feel somewhat removed from reality. The fantastic film projection was accompanied by a rather childish description of what was to be seen. Now and then a few words brought my attention to the size of something-the height, the speed, the form or the connection between two things, and so on. An endless stream of words and short sentences formed a slender thread of explanation. The essence, the real information, reached me unnoticed, and that was a weird experience. The knowledge that these beings, through their machine, could feed information directly into my brain, strengthened my feeling that

I did not belong here. The difference between Us was too great. I was defenseless. As far as I can gather, radiated information is a combination of visual stimulants and thought transference, all of which takes place at fantastic speed. The images came in such rapid succession that at first it made me irritable, and only after some considerable time did it become dear what was expected of me. I had only to act as a relaxed spectator, who observes with interest what is happening; they did the rest. It is understandable that this type of information is not suited to the written word and therefore I have attempted to relate everything in the form of a two-sided conversation. This tends to give the impression that I was a partner in an animated discussion, but nothing is further from the truth. My function during this meeting can be compared with that of a tape recorder. The authenticity of the hologram was so fantastic that it could no longer be describe as a picture.

As long as I kept my head in the correct position, it was just like looking through a window. The three-dimensional, panoramic, color screen offered so persuasive an illusion of reality that after the first few minutes I looked behind the screen to make sure that nothing was there. The adjustment of the picture was controlled by several of the many knobs and handles on the desk in front of me. My first experience with the radiation took the form of knowing, without further instruction, which of the knobs I had to use to adjust, for example, the focus or the position of the picture on the screen. The test card, a jungle of vertical stripes, vanished and I looked into a great, black hole in the middle of which hung a blinding ball. I recoiled involuntarily, at which the picture blurred, but I quickly got control of myself. The hole was very deep; I was looking into the endlessness of the cosmos. Against the black, somewhat violet background, sewn with thousands of stars, a gigantic, pink-white ball hung in stately beauty. The planet Iarga.

The sight was very moving. I felt as through I was really present in space and a strange emotion began to flow through me. The cloud formation was, in contrast with that of Earth, unbroken, with small, swirling patterns that caught the sunlight. The pink patches occurred where the sun was able to penetrate deeper into the clouds. Most remarkable were two gigantic, flat, concentric rings which formed a halo around the planet. They were rather like the rings of our Saturn, except that these consisted of a small inner ring and a much broader outer ring, both casting a sharp band of shadow on the clouds. There was also a large moon to be seen, with the same pockmarked surface as ours. Iarga, the

Do not use bright purple chi at the same time as chi which is yellow, green, tangerine or red because it will intensify and increase the effects of these colors. In addition, the use of any dark colors with bright purple chi (either preceding or following its use) should be avoided, as this will produce a very damaging result. As a general guideline, use blue before electric violet.

Golden Chi

Gold colored chi, which has almost the same qualities as bright purple chi, is formed when bright purple chi meets the spirit body. The color changes to cerise (pale red) when this gold colored chi enters the physical body. However, this chi is does not have as much influence as the bright purple chi, being gentler and therefore less effective as a cleansing agent. Gold colored chi should be used to treat a very local area, while bright purple chi can be employed over a wider area.

Spleen

The spleen is connected to the solar plexus and the navel, the major center that connects to all the organs. Holding solar energy or a white ball at the solar plexus will help distribute Chi to all the organs.

If the solar plexus gets clogged up the liver and spleen will also become blocked. The spleen, the Door of Life and the navel are all linked together; the navel and the Door of Life sit opposite each other. We call this an emotional link. Many diseases are caused by emotional links; people use psychology to deal with it which can work to a certain level, but all the energy would eventually get stuck at this main juncture or plexus. White chi is taken in mainly at the spleen, and before being sent to the various parts of the body, is split into its colored forms of red, green, purple, blue and tangerine.

If the spleen is not clean, the immune system will be affected, together with the production of bone marrow. The blood will be dirty and diseases of the joints and connective tissue encouraged.

Cosmic Healing Chi Kung works very well with Chi Nei Tsang. The Cosmic Healing Chi Kung, Chi Nei Tsang and all the other Universal Tao practices all play a unique role in working to heal the physical and subtle bodies. When you combine these three in synergy, it allows you to perform many healing tasks. The spleen (located under the left side of the rib cage), spleen center or navel can absorb white Chi directly into the front or back. The Chi will be broken down into color and distributed to other centers and their associated organs.

There is one thing that I always advise: the recipient or student should be under a doctor's supervision and that they should alternate between the medicine from the doctor and the work with us at the Universal Tao. The doctor should be advised of what we intend to do with the student.

home of these astronauts, is a planet in another solar system, not much more than ten light years away from US. More details of the location of the planet they would not tell me. The diameter and mass are much greater than the Earth's; the gravitational force is greater and the atmosphere is much thicker. The speed of rotation is much slower than that of Earth, so that the duration of day and night is longer, but the regular tilting of the rings around the planet change certain days into nights and certain nights into days, due to the fact that the rings reflect the sunlight.

As a result, Iarga does not have the regular pattern of day and night that we know. Because of the thicker atmosphere and higher air-pressure, which is of a different composition than ours, Iarga knows no bright sunlight, and sees nothing of the moon or stars. A permanent layer of mist exists at the higher levels of the atmosphere which filters the sunlight. The color blue only appears in lighter tints and green is more pronounced there than here, which may account for the fact that they seem to have a preference for blue in their artificial lighting. They describe the Earth as the blue planet with the blinding light, and, in contrast, Iarga as the green planet with the misty light. The living conditions are very different from those on Earth. Temperature extremes are much less than here, but when you hear that the wind speed can reach three times our maximum, and that ram and snowfall can be as much as ten times greater, and you combine this with the fact that the terminal velocity is much higher, it becomes dear that it would be very unwise for any of Us to be caught in a rainstorm on Iarga! After being informed that a fall from a height of six feet was fatal, I began to understand a little more of the reason for the physical appearance of these Iargans.

The rubbery muscle formations, armored skulls and long arms were products of very different climatic conditions than ours. There earthquakes also seemed to occur with more intensity and frequency than ours. Just as I was beginning to ask myself what the buildings on such a planet would be like, the picture changed and showed the view from a fast-moving spaceship that had just passed through the outer layer of mist around the planet. Initially, I saw only clouds: above me, the pink layer of mist that I had seen earlier; then a second, broken cloud layer which was primarily responsible for the strange, diffused light on the planet. We passed through this layer at a height of about twenty miles, and viewed from the underside it was a mixture of yellow-gray, brown and greenish clouds that gave a very somber and threatening impression. Lastly came a cloud layer that in height, form and color, closely resembled ours, and after passing through this, I had an unobstructed view of the surface. We flew over a bright-green ocean with white wave crests.

Above the water ran an orange strip as straight as an arrow, which, separated by a white-beached horse-shoe-shaped island, split and continued in different directions. It was only when the spaceship came steadily lower that I realized what this strip was. A railway bridge! On long, slim towers, high above the water, ran a bridge as far as the eye could see. Along this bridge slim shining torpedoes moved in both directions. Their speed was only slightly less than that of the spaceship and there were far too many of them for me to count. The distance between the torpedoes was about ten times their own length, all spaced exactly alike along an eight4rack system which was divided into two layers, one above the other. I had little time to study the trains further, for we moved on.

Land came into view - a low-lying coast, split by a broad river with large adjoining lakes-and before my astonished eyes a strange, unearthly panorama unfolded. For as far as the eye could see, the land was divided by the orange railway into regular rectangles. The long torpedoes moved between huge, glass, oiltank like constructions with shiny dome-shaped roofs. Areas of green on either side of the railway looked something like prehistoric forests. The longer I studied this landscape, the more I became aware that this was ribbon development in its extreme form. The area between the buildings seemed to be used namely for agriculture, only now and then making way for an industrial complex. The camera sped on. The landscape changed and became undulating, split by walls into huge terraces which compared with the wine fields of Italy. Behind this lay mountains, and in a great bowl between the peaks a red-brown lake came into view. The machine tilted its nose steadily lower until I was able to see vertically below. Around the shores of the lake, numerous buildings were to be seen, among which were several gigantic combs.

In three places, powerful blue-white lights, flanked by orange lights, flashed. Everything pointed to the fact that the spaceship was going to land here, and just at the last second, before the picture vanished, I saw something that made me catch my breath. On the right side of the screen, low above the lake, three shiny discs hung like sentries in the air. They had the form of perfect, streamlined discuses. "I saw flying saucers!"

"You saw three of our aircraft."

"In the form of a saucer?"

"Exactly. And if you are interested, we will let you see them."

"I certainly am. Did you come here in something like that?"

"No. These aircraft have about as much in common with our spacecraft as an Indian arrow has with your Mars probe. We hope that you have more important questions to ask than about aircraft."

"Of course. Am I to understand that the glass tanks are your houses?"

"Yes, We call them house rings because they are in fact built in the form of a ring with a covered central recreation area."

"Is the whole planet built in this way?"

"Yes, all areas that are suitable for living are built in this manner." The screen showed a view of a living area from a great height."

"So you all live in the same type of house?"

"From the outside they are all the same, but inside there is great variation."

"The uniformity appalls me. Do your top men also live in the cylinders?" I had an idea, judging from the length of the trains, which I guessed were about one hundred and fifty feet, that these buildings were enormous, at least nine hundred feet in diameter and more than three hundred feet high.

"The words 'top men' suggest something of the Earth's ideas of status; you surely do not imagine that in a higher civilization, standards of justice can exist that allow status to play a part?"

"I don't see what status has to do with more variation in house building. Why not simpler, smaller houses with more privacy?" "Small houses with separate pieces of land form a system that you call 'towns,' and such inefficiency is unthinkable to Us. "Why inefficient? When you have our problem of overpopulation, you must build large cities to house all the people. We cannot afford the luxury of large areas of woodland as you can."

"What do you call overpopulation?"

"Our small country has more than three hundred people to the square kilometer, which in my opinion is quite dense." "Compared to Earth's average of twenty-five to the square kilometer, that is indeed dense. Estimate the number of people living in the area that you see here. Every ring houses about ten thousand. Work it out per rectangle."

"Ten thousand per ring?"

"Yes, and we have more square meters per person than you have." I did a quick calculation. Each rectangle contained thirty-six rings, so thirty-six times ten thousand is . . . heavens! Three hundred and sixty thousand! I hadn't expected that. It made each rectangle a complete city! But, then, it was also a lot of land. "How long is the rectangle?"

"Roughly ten kilometers." I judged that the width must then be in the region of six kilometers, so that an area was then sixty square kilometers and therefore my solution must be 600 people per square kilometer. "I was certainly mistaken about your population - 600 per square kilometer. That's double ours. I was under the impression that it was much less. When I see the space that you have left, I must admit that it is a very clever solution."

"Your answer amuses Us because you have made a small mistake. You have the decimal point in the wrong place." I calculated again and came to the ridiculous total of six thousand. "It can't be six thousand."

"It is, Stef. What you see here houses a population of six thousand people to the square kilometer."

"But that's ridiculous. How can you do it? That's twenty times as many as our overpopulated land."

"Your word 'overpopulation' is pure nonsense. Our planet has a population density at least one hundred times greater than yours and we do not speak of overpopulation."

I began to feel uneasy, that was madness. I knew it. I should never have started this conversation. It was leading nowhere. I stared with new interest at the picture in front of me and tried to calculate the living space of these people. Strange as it may seem, there were no signs of overpopulation. On the contrary, there was room enough, round the cylinders, and the roads that ran through the woodland areas were in no way obstructed with people or traffic. "This is so incomparable with anything that we know that I am at a loss for words."

"That is the right attitude. With this confrontation with a totally different world, with totally different standards and a totally different philosophy, we are trying to make it dear that you must not draw comparisons. Doing so prevents you from understanding this world and its level of civilization. Forget your own world and try to understand what is happening here. Try, without prejudice, to follow our explanation, as this alone will be difficult enough. "The reason for our dense population is the small area of dry-land on our planet. Iarga is almost completely covered with water forming deep oceans, which leaves Us with a surface area of dry-land which can be compared to the area of Australia, and this is distributed over numerous islands. We were faced with the problem of feeding and housing the billions of beings which we needed in order to achieve our creation goal, on the smallest possible area of land. This imposed the greatest demands on our planning and social systems; these demands do not occur on Earth, you have room to spare.

"What we needed to create a high level of culture were three things: freedom, justice and efficiency. We will explain these concepts one at a time, beginning with the last, efficiency. "You are shocked by the size of our population, but the space surprises you. Strange, eh? It is not so strange when you realize that you are not shocked by the number of people but by the space that is left over in what to you is a ridiculously overpopulated world. You are shocked by our efficiency. To Us, it is the most normal thing in the world, because without this concept, we simply could not exist. Without efficiency, our world would immediately collapse. You will continually come up against this concept in our explanations because we must make it dear to you how carefully each of the three concepts- freedom, justice and efficiency - we had to employ to reach the level of civilization that can be called stable. "Also, justice is a condition for efficiency.

For example, if houses play a part in showing a difference in status between people, then justice fails, and efficiency in a setting such as this is impossible. It demands, therefore, a different, more social way of life." This was roughly the beginning of the explanation of the concept of efficiency, and I absorbed it with some difficulty. Who would expect the description of a super culture to begin with a lecture on efficiency? Anything but that! And it is almost impossible to relate just how efficient they were. Take, for example, their method of planning. It is simply based on the maximum number of people that a given land-area can accommodate. The housing and the roadways take up the smallest possible area-not more than five percent-in order to leave a maximum of land for farming and natural beauty. The farming areas produce the maximum in food that their technique allows, in order to support their huge population. The woodland areas are necessary to maintain a sufficient quantity of oxygen in the atmosphere and also serve as recreation areas. Everything is used to maximum advantage.

What would you imagine to be the mode of transport of a super culture? You think perhaps supersonic aircraft or rockets, and hovercraft type ships or hover-cars? Out of the question. Anything so inefficient, with so many moving parts which can wear out and require so much maintenance, would be madness on Iarga. What do they use, then? Very simple. A fully automatic, robot rail system. Slim torpedo trains that move without creating friction, the only component requiring servicing being the doors, and these are made of such a high quality that they can last at least one hundred years. As a well-brought-up Earth man, I didn't give up too easily and pointed out that our aircraft, so fast and comfortable, were surely much better than trains that can only reach a speed of about four hundred kilometers per hour. I got the most surprising answers. An aircraft is not only inefficient but is downright antisocial!

They only appear on a planet where status still exists, and they are only for the upper classes, because they are useless as a medium of mass transport and the cost per passenger-kilometer is at least ten times that of their rail system. They began to talk about transport capacity. The six-lane rail system between the house blocks (only the upper layer) can transport one million persons per hour operating at maximum capacity. Did I think that aircraft could compete with this?

No, I did not. Confronted with such astronomical figures as these, further argument is pointless. They were not yet finished. Did I really think that their transport was slower than ours? Yes, I did get that impression. Well, I was very wrong. I must think in terms of average speed, and the hours that we wasted waiting for connections, delays caused by unservice-ability or bad weather and our wonderfully inefficient trafficjams! Having thought of all this, I was readily prepared to believe them when they said that their average speed of all transport systems together was about five times higher than ours - inclusive aircraft. Had I mentioned something about comfort? Yes, I had.Wonderful, because comfort was also an aspect of efficiency. Trains had proven to be the cheapest form of transportation, and the only problem that remained was to get as many people as possible to leave their cars at home and use the tram. The only way to do this was through comfort, and this comfort was really something.

These trains were shock free and silent, apart from wind noise. Due to their position high above the ground and their large windows, they offered a breathtaking view of the surrounding countryside, and the interior was so luxurious that it left nothing to be desired. They were unaffected by weather conditions and one hundred percent reliable. The frequency was so high that timetables were unnecessary. Did I now know enough? Absolutely not! It had gradually become dear to me that their understanding of efficiency was totally different from ours. It influenced their very souls.

Cosmic Healing Planetary Colors

In Taoism we give each planet a color which enhances the healing power. Have the ‘Planets’ chart (located at the beginning of this chapter) in front of you, look at the relevant planet and close your eyes. Hold the planet in your mind.



Fig. 5.3 *Channel the Cosmic Planetary Energy into the body.*

Mars: Focus your awareness on the star above you, turn your eyes up and look up to the crown. Hold the image of Mars and extend your sight beyond the crown, looking up into infinity. See the **Red Light** and gradually bring it down to your head about 6 feet above you. Form it into a red ball, a holographic image of the planet Mars shining its red light above you. Invite it to flow down to your ‘star’ (located above your crown) and continue to flow into your Upper Tan Tien for processing. Let it flow down to the heart (or T-2) and down to the palms. Red and orange light also can be breathed in through the sacrum. Feel the sacrum pulsing and breathing in the red and orange light. Practice 9 to 18 times, rest and shake your hands.

Venus: Become aware of the star above you, turn your eyes up and look up to the crown and into infinity, seeing the expanse of **White Light.** Gradually bring the light down to your head, about 6 feet above you. Form it into a white ball, a holographic image of the planet Venus shining its white light above you. Invite it to flow down to the star above your crown and continue to flow into your Upper Tan Tien, for processing. Now it may flow down to your lungs freely.

Efficiency had become almost a religion. One of the most imposing visions on the screen was their trans-oceanic rail connections. A wonderful, orange-colored construction, about seventy-five feet above the restless green water, crossing the ocean in a dead straight line. I thought at first, perhaps a little naively, that the support towers stood on the ocean floor, but no-nothing so primitive. The whole construction floated, supported by huge balls under the towers which were anchored to the sea bed by adjustable cables.

The balls were placed at a depth where the water always was comparatively peaceful, unaffected by the conditions on the surface. The question that intrigued me was how the trains could function without friction and wear. I discovered that it was not so difficult once superconductive materials and supermagnets, the same sort of materials that were used for the outer skin of their spaceships, were used. The train was supported on magnetic shoes over its whole length which ran in a hollow rail. Through the polarity and the strength of the magnetic field, the shoes were held floating in the middle of the rail. A fantastic piece of construction. The system was controlled from large electronic control centers and was almost fully automatic. Optical signaling was not used, so that the speed was unaffected by even the thickest fog. Their cargo trains intrigued me the most, for they were in fact nothing more or less than self-homing containers. The route program was plugged into the nose of the unit and the ghost train left on its journey without a living sour on board, finding its own way over the rail network to its destination, silent and vibrationless, and without lighting at night.



Some things were rather amusing. There seemed to be a rather popular pastime that they called traveling in hotel trains. A group of about twenty-five people would order a unit that was fitted out as a self-service hotel and simply go where the mood took them. Everywhere in the beauty spots were "campings," where the trains could stay for a couple of days or more, and all you needed to do to travel further was to program the unit for its next destination. Traveling this way, often at night, they could cover enormous distances. As soon as I asked a question that fell outside the program, I received more of their strange answers. "Can everyone afford to go on in this way?"

"No, nobody can afford it, **because we have no money**, but everyone can go on holiday in this way if they wish."

At my request, they showed me one of their cars. In front of one of their huge, glass living cylinders stood a highly streamlined vehicle on ridiculously small wheels; nevertheless, it could be classed as a motor car. My enthusiasm for motor cars was suddenly diverted by the sight of two Iargan women who, accompanied by four small children, were to demonstrate the car. I sat staring at those strange exotic beings so intensely that the explanation about the car was for the most part lost on me. Their faces were smoother and finer than the astronauts' and they were made up with white and purple stripes on their fore heads and around their eyes. It made me think of Indians on the warpath, and this thought was strengthened by the colorful motifs on their clothing. This 'clothing' seemed to be more for decoration than anything else. It was just a broad piece of cloth with a hole in the middle that fell over the head and was fastened at the waist with a broad belt, leaving the arms and the sides of the body uncovered. Under this garment, they wore a pair of silky trousers which fastened tightly around the ankles. The shoes over the wide naked feet were open sandals. They carried themselves as refined models would, demonstrating the peculiarities of the car with lightening fast movements. The strangest thing was that their explanation, which I found inaudible, was directed at me, and due to the perfection of the picture I felt as though I was actually present and the center of their attention. "Is this the way your women normally dress?"

"We are showing you two mothers with their children, on their way to a recreation area, and we will follow them with the camera. They are wearing holiday clothing, fitting for a day out. We do not find clothes so important and as we do not have any other films on this subject, please confine your attention to the automobile."

The ladies had, in the mean time, entered the car with their restless offspring, and were demonstrating the maneuverability of the vehicle on its tiny wheels. These wheels only served the purpose of transporting the car from the cylinders to the rail system where, in contrast to the trains, they hung on magnetic shoes under the rails instead of above. This explained the large glass panel that extended under the feet of the occupants of the front seat, giving the vehicle the appearance of a helicopter from a frontal view. The interior was luxurious-two wide three-seat benches, and behind, the baggage space. There was only one sliding door on one side, and nowhere could I discover any access to the motor. After this demonstration, the ladies rode away along a broad, ocher- colored road, to where the huge central rail system ran between the house cylinders. The huge "motorways," which looked like thin orange lines from the air, were in fact a three-level road and rail system carrying heavy traffic at unimaginable speeds. The top level was a six-track rail system which carried the long torpedoes, the four inside tracks for fast, long-distance traffic, and the two outer tracks for local traffic.

The other two levels were for the cars, again using the outer tracks for slow, local traffic and the inner tracks for higher speeds and longer distances. The stations were huge, cross-shaped buildings through which the car-tram tracks passed in tunnels. At ground level, around these stations, was a huge bading terminal for the transfer of freight from the rail containers to the wheeled transport. The camera continued to follow the fantastic journey along the rails and the two ladies who were at the moment playing with their children. The voice called my attention to the house cylinders. The first thing noticeable from dose up is the perfectly smooth exterior, with neither grooves nor joints in evidence. The different floors were visible only as creamy-white bands of about three feet in height, on which rested glass panels about fifteen feet high and sixty feet wide. The panels were met by anthracite-gray pillars that ran from top to bottom throughout the whole building. "Isn't it rather warm, all that glass in your houses, cars and trains?"

"No, because it is not ordinary glass at all, but a combination of glass and plastic. It contains two electrically conductive layers with which the transparency can be regulated to give a greater or lesser reflective quality." The hologram images crossed a broad river, and I could see thousands of Iargans walking along its banks. I also saw hundreds of small boats braving the strong winds and stormy water. They were catamaran type constructions, with streamlined cabins supported on legs above the water. The hulls were almost completely submerged, and the strangest thing was that the rough water seemed to have no effect on them. They were fast and made no bow waves.



(Picture text: Cross cross-section of one of the floating and rotating house-cylinders. The construction is so stable that despite the heavy Iargan

earthquakes, the framework (base, wall, and roof) has a minimum useful life of more than a thousand years. The plastic flats (apartments)(20 x 20 x 6 meter) are removable horizontally. The diameter of the building is more than 300 meters, the height is 135 meters. It provides housing for 10,000 persons, each with so m2 to themselves, plus a part of the heated communal garden. The smooth exterior is necessary in connection with the strong winds and the rainfall. Comfort and labor saving have been perfected to such a point that the housewife is freed from housework, but the protection and comfort of the house-cylinders has become subordinate to the creation of the possibility of numerous "human" contacts in the utmost freedom.)

The camera allowed me no time for further study. The landscape changed, the ground became undulating and in the distance high mountains borne in the misty, liazy light of Iarga. The cylinders in their oblong formations continued as far as the eye could see into the foothills and even beyond where the ground was terraced off with long, high walls. As the ground became more mountainous, the buildings stopped, as did the roadway, but the railway continued on through the wild and rocky landscape. The rest of the journey became real science fiction. Like a giant snake, the railway wended its way around mountain peaks and over deep ravines, across fantastic suspension bridges and along vertical rock walls, now over gaping depths and then over grassy, woody plateaus, and in every suitable spot were the stations and the parking areas for the cars. This was one huge recreation area, with its rugged mountains and beautiful waterfalls.

Just as we were approaching a large, green mountain lake with nearby buildings, the picture faded and was replaced by the now familiar view of the Iargans' living areas, but I saw it now through different eyes, eyes which had begun to notice the wonderful perfection of this strange world; a world that sustained its huge population through utmost efficiency; a world without refuse, smells, exhaust gases, traffic jams and noise.

I also began to understand a little of something else, and that was the justice that they were always talking about. Although I had only just begun to become acquainted with this distant culture, I understood that everyone here had equal rights. They lived in the same houses, rode in the same cars and stepped into the same trains. There were neither rich nor poor; there was no separation between nationalities, races or colors.

This must be a universally governed planet, but seemingly so strictly governed that everything was streamlined and standardized. What a terrible thought! I had no idea then that my horror at the thought of such monotony was soon to change into longing.... I began to wonder what the millions of miles of railroad must have cost; it was certainly a triumph of engineering. "Can you give me some idea of what such a transport system costs?"

"That is difficult. We know roughly what a dollar represents in production ability, but to translate that into the cost of a transport system... well, we can only guess. For one billion dollars you would not get much farther than three miles."

"Can't it be done for less?"

"Naturally, but then we would have to make concessions with quality, and that is not our method of working. Such a system can only exist if it is built to last for centuries, otherwise we would constantly be repairing it."

"We'd never be able to afford such quality."

"You see it in front of you. What you need is not a vault full of banknotes, but production capacity. Only a society with a completely efficient economic system can realize such things for itself."

"But can all this be compared to the communist system that we have on Earth?"

"Our cosmic universal economic system can be compared to both communism and the capitalist Western economy. One can also say that our cosmic economics can't be compared with either."

"If we don't have this system on Earth, how can you call it universal?"

"It is only through this system that a race can achieve a cultural level of social stability. And from there onward toward immortality. It is the cosmic condition, based on natural laws."

"What's your definition of culture, then, exactly? I'm beginning to think that we define the word differently."

"That's a very important question, Stef. Culture is the measure through which a society caters to the least fortunate man. The measure in which the sick, invalid, old or poor people are taken care of. In short, the measure of collective unselfishness." "But what has this got to do with immortality?"

"Just this, that unselfishness makes an intelligent race immortal. But before you can understand this, you will first have to climb the ladder with Us to the misty heights of comic integration."

"Unbelievable! I thought that you practiced efficiency as a sort of religion, but now I see that your economic system is a religion of sorts as well."

"You are beginning to understand, but the word 'religion' is not well chosen."

"Something like it, then?"

"Correct."

"Do you mean that to start with we should build a world with this standard of efficiency and quality?"

"We do not remember ever having suggested that you should build rail systems and cylindrical houses, nor have we said that your population should become as large as ours. You are again needlessly creating comparisons, which you should not do, for it leads you nowhere. Try only to understand how we have used the three essentials of higher culture-freedom, justice and efficiency-in our world, and what culture really is to Us. Only then will you be able to understand our answer to the great question that you have asked."

CHAPTER 3

Planet Iarga

After the Iargans had explained their concept of efficiency, they turned without pause to their ideas of justice. In the same relentless and efficient manner, I was pumped full of the laws upon which they based their social and economic system in a very short time. The main theme was the same: the efficiency of the justice. It's interesting to fully understand what a cosmic universal economic system is. They explain it as follows: an economic plan, aimed at efficiently satisfying man's needs so that he is released from the tyranny of material things over his daily life. In other words, if everyone has everything at his disposal, then the acquisition of material goods is no longer of paramount importance. This can only be achieved by providing "equal shares for everyone"; otherwise envy will always exist. The culture then becomes more or less stable. I nodded in agreement; mankind released from material problems, no envy or greed, that was an answer.

Only one small problem: how is it done? A little magic perhaps? There are only two solutions: everyone must own the same; or no one must own anything. The last is the most efficient. I sat bolt upright in my chair. Were they telling me, a well-to-do company director, that I must dispense with personal property? These beings were pure communists! It was useless to carry on this conversation; it was getting me nowhere. I sat wondering if I should voice my displeasure, but the explanation continued with the following hypothesis: consequently, because money is an unmistakable

Saturn: The **Yellow Light** from Saturn can also be absorbed via the earth through the soles of your feet and perineum. This is for your spleen. Follow as above.

Mercury: The **Blue Light** from Mercury may be absorbed through the throat center. This is for your kidneys.

Jupiter: The **Green Light** from Jupiter can also be absorbed through the throat center. This is for your liver. Follow as above.

Summary - Working with Color

(Practitioner to Student)

There are two ways of doing this type of healing session:

One way is to focus on the specific location in your own body, using your hands and ask the other person to do the same. Together you complete the entire route.

Another way is to focus on your own energy body and ask the student to do the same. Bring a channel or line down from your energy body into your physical body and do the same for the student. Once again, complete the routes together.

For reasons of clarity this text only mentions one student and uses the male gender; *this session may however be performed with a group also*. Before starting the session do some group meditation practice and warm ups.

1. Be aware of the Tan Tien and connect to the universe. Let the student sit with his back to you. You are behind him. Be aware of your **Sacrum** area and feel the Chi; **wait for the Chi to rise up to the crown** and to the universe. Spiral the Chi down to the student's and your own energy body and it will flow into the physical realm.
2. Draw in the green light with your palm, push it right through the sacrum and disperse the sickness throughout the other side of the universe. Pull the green light from the universe through the sacrum and push the sick Chi out to the universe. Do this 6 to 9 times until you feel the **sacrum has been cleaned**. When you pull back stop the green Chi at the student's sacrum; there is no need to pull it back to you.

   Yellow light from the earth will help strengthen the sacral bone. Visualize the sacrum and vitalize the complete bone structure with yellow light passing throughout.
3. Be aware of the energy body above the **Crown**; extend yourself up from above your crown and **channel down the white light from the center of the universe and the violet light from the North Star.** Using your 'mind-power' ask the inside of the bone structure to open, allowing the white and violet light to **flow into the marrow.** Focus on the energy body; you can picture the energy body's sacrum and bone

form of property, it should be abolished. They went even further. Personal property is an indication of a very primitive level of culture. We had enough intelligence to build rockets, but not enough to see that the laws of the survival of the fittest and might is right must be abolished. Perhaps I could explain to them how I thought we could survive with such a system. Because though ours was a highly interesting system, what they had found here in discrimination beat anything that they had ever encountered before.

Earth people seem to be continually occupied with thinking of new discriminations, and using them as solutions to the ones that already exist. Someone could not formulate any social or political plan without someone else immediately attacking it. I really must not blame the spacemen when they said that all this useless talking, the continual working against one another, made them laugh. On the other hand, it was more terrifying than amusing that power had now been added to this difference in insight in the form of an atomic-weapon arsenal which had an unimaginable destructive and poisonous effect. And all this under the control of a few buttons! How was it possible that we could still sleep peacefully? One learns to live with things that are impossible to change. What a foolish idea; of course it was possible to change things. All we had to do was to stop discriminating, simply change our laws. The concept of private property, of course, stood in our way. But surely we could sort that out. .... .1 didn't think so. Abolish personal possessions? Never would that work.

While we are all quite willing to improve the world, it had to begin with our neighbor.

Surely even a selfish man can understand that a world without discrimination would be a better place in which to live. Perhaps we could even create a prosperity that, universally speaking, could be ten times better than that of the present? That they could understand. It was a pity that the communistic ideals were lost in inefficiency, otherwise they could have done a lot of good. It was a case of state-controlled economic leaders making the decisions. My humor improved considerably; they were not communists after all. But what were they, then? I will try, briefly, to explain their system, as far as I was able to understand it.

The total production of goods and services is, on Iarga, in the hands of a very small number of huge companies, the "trusts." These are huge organizations with millions of employees, active over their whole planet. There are primary trusts, which distribute directly to the consumer, and secondary trusts, which supply the primary. **Nothing is paid for on Iarga,** only registered. W*hat a consumer uses is registered in the computer center in each of the house cylinders, and this may not exceed that to which he has a right. These computers are coupled to the huge shopping centers in each of the cylinders. You cannot buy anything. Large and expensive things, such as houses, cars, boats, valuable artifacts, and so on, can only be hired. They call this the right of acquisition. Less expensive things are not hired because that is not efficient. They are registered for their total value and the right of* *use remains for life. This is almost the same as personal ownership, except that in the event of death, the goods are returned to the trusts. The last category is articles for consumption and public services. Their total value is registered, at which point right of usage becomes yours*.

As far as goods are concerned, you may not have more "in stock" than is reasonable for your own use, otherwise the surplus can be confiscated. It is practically the same sort of thing as a bank account, except that they place the control on the expenditure, whereas we place it on the income. This difference is worth a lot of thought. Legally, all the goods remain the property of the trusts that supplied them. This means not only that the trust is responsible for the upkeep, repair and the guarantee of a certain minimum life, but they also take the total risk of loss or destruction. Thus, all the articles are made to such a high standard that repair is never necessary; repairs are not only expensive but terribly inefficient. Insurance companies and repair firms would make a poor living on Iarga! The trusts work on a cost-price basis whereby our term "profit" is replaced by "the cost of continuation." Each trust was constantly occupied with improving and expanding its production. Their economy was as stable as a rock. They showed me two of their fully automatic factory complexes, one that produced cars and another that produced the trans-oceanic rail bridges.

The star-shaped building had a diameter of about one kilometer and the area around the factory was a maze of rails supporting hundreds of their freighttorpedos which entered the building at the points of the star. The film then moved to the factory's interior. The points of the star contained the automatic unbading system that emptied the trains of their raw materials, and this was the first time that I was able to hear original sounds. Strange hollow knocking, interposed with screeches and clicks, it was an inferno of noise that echoed strangely in the small metal chamber in which I was sitting. The same realistic effect as the film itself; left, right, above, below; I heard the sounds exactly as if I had been present when they were made, and I began to hear exactly which machine was making a particular noise. The size of the machine park was indescribable. Boilers, collectors, hinging lids, ovens with white-hot metal, presses that belched steam each time they opened; huge horseshoe shaped sections with high-voltage insulators and spark-spitting machines. Small, delicate machines turned, twisted or juggled with their products.

I saw a few Iargans at work, dressed in orange colored overalls with space-suit like helmets on their hs which left only the mouth and nose uncovered; there were never more than about 40 workers outside the control room. The production lines converged towards the middle of the factory and it became dear that this factory produced automobiles. The most sinister, I found, were the metal claws that functioned exactly the same way as a human hand and arm. They were mounted on a system of arms and made movements exactly as a living being would; large ones moved slowly, and small ones moved at lightening speed, exactly synchronized with the placing of a part. The machine completed its task piece for piece until a complete product emerged at the end of the line, faultless, fast, and untouched by "human" hand. It was mostly the claws that gave the impression that this monster with all its noise, had an intellect of its own. The two production lines joined exactly in the middle of the star, the complete under section of the car, complete with wheels, seats, steering and controls was joined in one operation to the upper section with glass, doors and the rail skis. Here I saw the most impressive battery of arms and claws, the finished automobiles were picked up by the skis, swung round, and placed onto the rail system exactly next to the previous one, with only a few millimeters between them.

The camera rested for a while on this end phase, and it began to dawn on me just exactly what this machine was capable of doing. This kilometer long monster that knew no failure, turned raw material into a finished automobile at the rate of one every twenty seconds! or four thousand five hundred per day. When my noise-numbed brain registered this, I got a rather strange feeling in my stomach; this was inhuman! They were also "kind" enough to show me another factory that produced the trans-oceanic rail bridges, but I will spare you the details. The need to continually write in superlatives tends to bring aversion, my comments can be condensed into one word, terrible! How the Iargans can develop and build such mechanical monsters is a mystery to me. They also thought it desirable to show me the robot production of the houses; even a nonefficient Earth man could surely under-stand something of the advantages of standardization. I thanked them kindly for the offer, but I had seen enough of all that automation, where Iargans only checked to see that everything was working properly. I was quite prepared to accept the fact that they could build houses fully automatically. They were disappointed, but perhaps I would like to see how they assembled the units into the huge cylinders? Okay, the, just to please them.

- 

Iargan family-life.
IARGANS are very connected to each other - always stays close together. A amph.race w. group-conciousness.

How do Iargans build their houses? This efficiency began to tickle my sense of humor. They began by building a factory, on site, and placed in it one of the mechanical monsters that produced the complete, ready-for-use, plastic housing units. Each unit was roughly sixty by sixty feet and eighteen feet high, completely finished with glass, furniture, household machines, communication system, and so on, divided into two layers or floors. On the site itself lay, in the ground, a huge, star-shaped rib construction with a diameter of more than nine hundred feet. Just as the roofs of the cylinders were domed, so was the foundation, but with the convex side under, like a half discus. The ribs were joined in the middle to a huge ring, the depth of the ribs at this point being approximately sixty feet. The plating on the under-side of the ribs was dark grey and looked rather like the skin of their spaceships. On this "saucer" foundation a massive cylinder with a steel frame was built, filled in with something that looked like black concrete, the whole construction having a diameter of approximately eight hundred feet and a wall thickness of approximately nine feet. The whole construction was covered by the domed roof which seemed to be almost as strong as the foundations, only this roof was covered by glass.

On the out side of this cylindrical wall were rows of heavy support beams, onto which the house units were placed, each unit fitting perfectly against the insulated surfaces of its neighbor. If one of the units should be damaged at any time, for example by fire, then it was simply removed and a new one put in its place. A wonderful piece of engineering. The "working life" of these constructions was calculated to be at least *one thousand years.*

"When I hear you continually talking about quality and a useful life of thousands of years, and a rail system that can stand for hundreds of years, I get the feeling that your plans for the future make ours, which only take into account the next twenty or thirty years, look like child's play," I told them during a break in the film.

"The explanation is not difficult," a spokesman answered calmly. "A race that lives under the constant threat of war and destruction does not logically make any plans for the distant future. For an absolute race, that is different. The continual improvement of our mental capacity directs our thoughts more and more into the future. We have created a planet on which our race can survive for an eternity. We live in a stable world on a clean planet, where the balance of nature can be maintained for unlimited time. We live for the future, because we expect great things from it. We are constantly occupied with making our world a better place to live in. The Earth, on the other hand, lives for the present and the past, and does not worry about the future generations."

"Remarkable, this farsighted concern for future generations."

"When you understand what a super culture represents, you will share our concern."

I was delighted when they agreed to my request to see one of their flying saucers. I cherished the hope that we might also become capable of constructing such a machine, but, alas, the technique was so advanced that I was unable to understand the first thing about it. It was a beautiful, polished, silver, streamlined discus, about ninety feet in diameter, with a domed glass pane) above the below in the middle. There were slots around the rim on the underside, and when the machine flew low over the ground, I could see dust being blown up. I thought at first that this was caused by air pressure, but they explained that it was due to the "ground echo" from the antigravity machine. It was astounding to see just what these machines could do. They showed me the transportation of a rail section to an inaccessible mountain area. The saucer lifted the heavy section on two steel cables and transported it effortlessly over the mountains. It was maneuverable in all directions, and could, even in a storm, hover motionlessly in the air. It was equally capable of operating either in the atmosphere or outside it. In answer to my remark that it was surely, then, a spaceship, I was told that they were confined to the gravitational field of the planet.

Gravity was their only means of returning to the surface. One therefore had to be careful not to fly fast enough to exceed the escape velocity, which would then necessitate rescue by a real spaceship. *My request to be allowed to see one of their spaceships was politely refused;*

perhaps at the end of our conversation. They felt that we had much more important things to discuss than technique. They thought that they had sufficiently described the production facilities and the investment capacity of their trusts, and that I would now be interested in their structure. To be quite honest, I had at the moment very little interest in structures. A society without personal ownership was all very well and good as a curiosity, but I did not see any practical use for it.

I was later to regret my attitude, for the efficiency of radiation information is dependent on the interest of the "student," and because of my lack of interest, I missed an important part of the organizational structure. I remember only a small part of it. The system worked with divisions and branches that were as far removed from one another, geographically, as possible, and allowed for automatic production. At the head of each trust was a president who was a member of the production group of the world government. The trusts competed with each other, and the prices were determined by the law of supply and demand, the principle of the free market. Their cost price was computed on the standard work hour, the ura. (cont. Under) structure to help guide the energy inside and see the whole body light up from deep within.

4. Then focus on the **Door of Life and the Navel.** First flush them through with **green** light, cleaning them out. Draw the green light from the Door of Life through to the navel, and then push back through. To cool down the Door of Life (if necessary), draw the **blue** light and push it through from the navel to the Ming Men, connecting with the universe. Then bring the **white or violet light down and activate the Lower Tan Tien.** Always teach people about their Tan Tien. It is like an ocean and the body is like a hollow bamboo. The bamboo can bring the water up. This way energy will never dry up.
5. Concentrate on the **Solar Plexus and the Chi Chung (T-11)**. Once again, draw the **green** light, spiral it, use it to flush, then **energize with white and violet light**. As before, always allow the energy to stream through both the points completely. The solar plexus holds all the emotions. When working on the solar plexus, the **most important thing to remember is to connect the 'backside' to the universe.** There is literally no end to this connection. Just allow the Chi to come all the way down and then pull it towards the rear slightly. Simply clean out the path. Allow the information to condense; allow any images to manifest and then release. Then stabilize the energy. Picture the Chi-Field enveloping the person as a big protective bubble. **Cool down with blue.**
6. Proceed to the **Heart and the Shen Dao (T5/ T6).** Draw in the **green** light, push it through and repeat several times. Now scan the heart with your palm, sensing its strength; then select an appropriate hue, i.e., not too dark. Send the **red** light through the heart to strengthen it.

   Cool down any excess heat in the heart, flushing down and out, using **blue** color. Draw in the **white** Chi; push it through to the **Wing Point (T5/T6)**. **Energize the center at the back of the heart using violet and golden Chi.** Picture the heart surrounded by a golden aura.
7. Move up to the **Throat Center, flushing through to C-7**, using **blue** light first to open and clear it and then **green** light to clean.
8. Next activate the **mideyebrow.** Focus on the mideyebrow in your own body. Use **golden yellow** Chi; use it to **flush and stabilize** the mideyebrow. Flush it all the way through to the backside of the head. **Energize with violet golden light.**
9. Proceed up to the **third eye** in the middle of the forehead. **Connect to the Kun Lun** at the back of the crown. **Flush** through both points using the pale **violet light. Energize** with **electric white or golden light.**
10. Concentrate on the **crown**. Use **violet** or **golden** light to enter and **flush** all the way down through the **central channel**, leaving the body at the **perineum**. **Cool down the system by showering blue light over the whole body.**

    When people have a serious infection, they should consult a doctor. It is common for infections to take a long time to clear up nowadays, even when using antibiotics.


IARGA
Anti-gravity Air Transport
Top
Highly polished silver metallic color
bottom
Slots around the rim
Performs heavy lifting jobs in remote areas
Operation is confined to gravity field of planet
Transparent dome on top of ship
Carries tripod landing gear retracted inside
Transparent dome on bottom also
Estimated 90' diameter

"Anti-gravity" machine.

Text for UFO-drawing: Small disc-shaped anti-gravity air vehicles observed were not capable of flight outside of a gravity field. They were a beautifully polished silver in color, were highly streamlined, and were about 90 feet in diameter with a transparent dome above and below in the center. There were slots around the rim on the under side. The performance of these vehicles was astounding. They were observed 'lifting whole sections of the rail system structure into place in mountainous areas with ease. Their operation is confined to the gravitational field of a planet.

Text. Cont. Here: My question as to how they calculated the cost of natural resources was answered by saying that **in a society where personal ownership did not exist, natural resources were, in principle, free.** This meant that the price was calculated from the cost of winning, processing and distribution.

"How can a trust that works on a cost-price basis sell gold, for example, which, due to the law of supply and demand, represents a much higher income than its cost price?" I asked.

"You use gold as an example, but there are many scarce articles that represent a profit far above the cost price. This is not a problem. The trusts simply absorb this extra profit and use it to subsidize other articles in the production scheme. Careful central planning can also influence the law of supply and demand."

"Surely that can be done by advertising?" Then they really went to town! What we did under the guise of "advertising" and "public relations" was something that bordered on indecency. The money and manpower-in other words, potential prosperity-that we limit for a nonefficient brain. Can you imagine what these Earth people thought of now? Artificial aging! A continual stream of seemingly new models compelled our status-symbol oriented society to discard things before they had reached the end of their useful life. A terrible waste of raw material and production capacity, and, even worse, it was a stimulant for jealousy and greed, and this was criminal. This promotion of materialism, a deadly danger for an intelligent race, was directly opposed to any idea of justice. I thought they were finished, but their most remarkable argument was yet to come. Our advertising was a despicable form of propaganda which was ethically unacceptable. In a socially stable society, you had not only freedom of speech, but, even more important, freedom of thought. Propaganda, repeated one-sided information, damaged the freedom of thought, and that was unacceptable discrimination. My tentative question as to how they could practice competition without advertising initiated another detailed explanation. Competition exists only through the free choice of the consumers, and has nothing to do with trying to influence that choice, as we try to do with advertising. They influenced this choice (naturally!) much more efficiently.

On Iarga, there are two worldwide consumer organizations, which are responsible for all market research. They examine the usage value of all the goods and services and inform the public in the most objective manner about the available assortment. They stimulate the trusts to produce the goods that are needed. The trusts are not permitted to advertise or exert any influence on the consumer, as this could never be objective. Thus the choice is not made by inexpert or unprice-conscious persons but by experts with test facilities at their disposal. When, for example, they see that it is necessary that the public have a choice of five different types of television sets, then they insure that these are produced.

I didn't believe a word of it! From what I had seen on Iarga, there was no choice at all. Everything seemed the same, cars, houses, trains, and so on. They were afraid that I had failed to understand anything of what they had told me. "The presidents of the two trusts are a part of the central planning group of the world government. This group attempts to lead the race to the goal of a culture. To begin with, they must, by means of production adjustment, dispense with the law of supply and demand, and thereafter create a situation of unbridled prosperity, so that no one is troubled any more by material things. As a result this group also stimulates the mental development of the race. Take, for example, the cars and houses. There comes a time when the cultural level has reached a point where these no longer function as status symbols. What then influences the choice of the public? Two things, mainly: comfort and price. Maximum comfort and low production cost can only be achieved with robot automation. And what happens then? Everyone chooses the most efficient car and the most efficient house and so the development proceeds. "Another thing that has a great influence on consumption is the general interest in the conservation of natural resources. A race that lives for the future is concerned with the utmost efficient use of natural resources, because the longer the planet is inhabited, the scarcer these become. The presidents of the consumer trusts have a great influence in these things, because they have public opinion behind them."

"All right, I understand the relationship between the trusts and the public, but, now, how much does such a president earn as compared to the lowest paid worker?"

"The question is not easily answered. The goal of the universal economic system is naturally the leveling of income, but that is not possible in the early stages of social stability. A material reward must be offered to stimulate a greater personal effort. A similar reward must also be offered to stimulate young people to complete the long studies necessary to reach high technological development, or to induce people to work harder or to accept more responsibility.
"You must begin by determining a social minimum that everyone always receives and you must attempt to establish security for everyone, young and old. Women also have a right to their own income; the social minimum must be free of any discrimination. You must also determine that the maximum and the combined income for a man and wife can never exceed four times the determined minimum."

"Do you think that you could find presidents here who would be willing to accept such a modest income?"

"Of course, as long as the minimum is high enough. A president and wife earn, for example, eight uras and the minimum is then two uras."

"How do you cope with general costs, the kind that we pay for with taxes?"

"They are calculated in the price of consumer goods and services."

"Doesn't this make the price rather high?"

"Now you are thinking in terms of money and payment, while on Iarga, money does not exist and nothing is paid for. What **we conveniently call "price" is in fact purely a method of expressing the production time demanded by a certain article, and is** only used to determine the distribution of prosperity. When you ask if the prices are high, you really mean to ask if there is a lot available to us, if we are rich or poor. In fact you are asking about the production level per head of the population, and compared to Earth's standards, this is very high. **The answer is, we are all rich. The universal economic system that exists by a great many intelligent races, does not concern itself with money, possession, or payment. The aim of this system is to free the people from material influences and motivation; and in contrast to the Earth's economy**, this system is very simple, it can be explained in a couple of minutes. "The explanation is indeed simple, but it must be accompanied by one or two marginal notes. It appears to be a socialist heaven, and as such is rather misleading. Earthly Marxism makes the fault of thinking that all people are good, and that only their social and economic situation makes them "bad"; change their situation and the problem is solved. If only this were true. Every intelligent race is dualistic, and as absolute necessity, contains an extremely evil consciousness component that now and again comes to the surface in the form of lies, deceit, sadism, homicide, etc. etc. One of the reasons for the terrible murder of millions of women and children in gas chambers.

"A detailed explanation will come later, so let it suffice here to say that beings on Iarga that possess this mentality are denied reincarnation. This selection is the cause of the continuing improvement in mentality, generation after generation, which enables a race to become unselfish. "On Earth, this selection was blocked some twenty centuries ago by extra-terrestial intervention whereby we cannot improve our average mentality. This system is therefore unsuitable and undesirable for us because it would stimulate the egoism. The lazy and the profiteers would disrupt the system. The universal economic system is just an utopian dream for us. "The beginning of this system is their worldorder. The unity of such a race comes from the fact that they obey a set of Godly laws and therefore have a uniform legal system. Add this to their love of travel, which results in the mixing of the races, and the result is the disappearance of nationalism, which happened long ago. The total production of all goods and services is controlled by globally operating trusts or cooperatives, the presidents of which form the world-government. These are not so much economic as political formations that perform most of the tasks that fall here under governments and ministries.

"The consumers cooperations comment on the performance of the trusts and so stimulate the assortment and availability. Once this situation has been reached, there is not much left to be written in a book on economics. The only thing that could be entered is any idea to improve the systems product efficiency *which will reduce the amount of servile labor*. They regard this kind of work as a waste of time.
"Appropriately, they use the term: welfare efficiency of the working population. The theoretical maximum of 100% could be reached when the total working population should take part in the direct production process of goods and services, with the highest attainable level of automation and the highest possible quality and durability. This maximum is obviously never reached, and the welfare efficiency is always below 100%. The higher the figure the larger the availability of goods and services, and the greater the prosperity. The three determining factors are:

"1. The occupation factor shows the percentage of the working population that takes part in the direct production process of goods and services in the public sector. Here it may be useful to list the professions that do not exist on Iarga or that fall outside the direct production process: banks, insurance companies, stock exchange, lawyers, sales organizations, public relations.... (cont.under)



Text for picture of housing complexes: *The ring-shaped housing complexes, looking much like huge glass silos, are about 900 feet in diameter by 300 feet high, and they accommodate about 10,000 Iargans each. The central core structure is built up complete as a single unit and the apartments are installed on the outside which results in the glass-like finish. These circular housing units are arranged in rectangular cities about 10 kilometers by 6 kilometers wide encompassing up to 36 such units. The resulting population density is as high as 6000 persons per square kilometer.*

View of an automatic farming machine which is controlled from a central post. The unit works a piece of land 250 wide and 10 Km long. Fertilizers and sprays are introduced via the central rail and administered by means of a rolling tank. At the end of the rails, the whole unit turns through 18o degrees and returns *over the parallel strip of ground. No poisonous sprays or artificial fertilizers are used on Iarga, the ground is sterilized with a deadly ray before the seeds are planted, (keep out of the way when it is working). The contrast with our primitive farming methods and these "super efficient" methods on Iarga is bizarre.*

Text.cont: ....and advertising agencies, tax offices, accountants, consultants, ministries, the whole weapons industry, the army, airforce, navy, administration and bookkeeping for as far as it is not connected with the registration of the direct production process, etc, etc... The universal system reaches the unlikely figure of 90%, but this has an additional reason. All creative work is not taken into account because they do not regard this as servile work. It is performed after working hours as a sort of hobby, and includes things such as planning, strategy, innovation, research, development, scientific research, all art forms and the organization of events. This occupation percentage for the industrialized western countries lies somewhere in the region of 30 to 40%.

"2. The production effectivity is expressed in terms of the relationship to the maximum possible at that moment. What it boils down to is that everything that can be automated is classed as 100%, and the rest is related to that. So exists a model for each system by which other systems can be judged. Think for a

There are two ways to deal with this; allopathically or naturally. The Taoist practices are in great conflict with ‘contemporary (i.e., not alternative/natural) western concepts’. The western concepts recommend a full course of antibiotics. Using the theories of Chi Kung, a baby for example, would absorb natural antibiotics via the bones. Western Allopathic Practice consider antibiotics as wonder drugs. The only ‘wonder’ is when will they realize the many harmful effects that it has on the body? Babies that have been ‘fed’ with antibiotics frequently suffer many organ related problems by the time they reach 20 to 30 years of age. The worst thing is that they are given to children nearly every time that they become ill. If you scan (cosmically) the solar plexus, thymus or spleen of such a person, the area feels like a hollow void. This means that the immune system is totally non-functional. The same thing applies to ***Aids***: the immune system no longer functions. Any virus can enter the body - medicine cannot kill it. There is nothing left to ‘fight with’.

In my experience and following my own experiments, in circumstances like the above my own practices are as follows: I clean my colon; there are a few ways to do that. I eat fiber, vegetables, especially green leafy ones. I eat a big bowl of vegetable soup. I also add things like onion, pumpkin, carrots and cabbage, which will give it a sweet taste. I don’t eat any meat and drink a lot of water. The colon is cleansed within two days. I also brush the skin, which is a very good detoxifier. The vegetables will provide natural carbohydrates which are digested and absorbed very quickly. A healthy diet consists of many whole natural foods. It is ‘alkaline’ as opposed to ‘acid’ based. I also use the ‘colema’ which I feel is the best cleanser.

moment of the gigantic investment capacity of these trusts in relation to ours, for the most part, small concerns. The Iargan figure is relative, so it does not have much meaning for us; but I think it would be safe to say that our figure would be somewhere in the region of 5o% lower.

"3. The qualityfactor determines the effect of certain goods or investments on the prosperity. An object that lasts twice as long as another has twice the effect on the prosperity. All repair time, direct or indirect, lessens the effect; and beside this is the ethical reason for the quality control, the scarcity of raw materials. An object that lasts twice as long as another uses half the amount of raw materials; that is why they are so critical when it comes to the question of quality, and the trusts allow no concessions in this respect.
"Consumer goods that pass the quality test, such as food, score 100%, but all the rest are meticulously checked for durability and repair demands. Durability is expressed in a percentage of the maximum attainable or desirable, and the servicing hours are deducted in percent. When it is said that their rail-system has a useful life of more than one hundred Earth years, and that the frames of their house-cylinders last for many hundreds of Earth years, perhaps you will get an idea of their standards of quality. To set our quality standard again at fifty

percent is perhaps ridiculous, but that is not really the point. "The welfare efficiency is calculated by multiplying the three factors by each other, and they state that the universal economic system easily gets 70% average among numerous intelligent races. The average of our industrialized countries can perhaps reach the 7 to 9% figure. This shocking conclusion means that with our present technical development, the welfare profit could be eight to ten times as high as it now is. With a just and efficient system, our present number of workers could have conquered all the poverty in the world. We have a ridiculously inefficient production system caused by too many professions that consume prosperity instead of creating it. Our stupid way of sharing prosperity causes so-called over-production and we resist automation for the sake of employment, while the majority of our world-population lives in poverty.

The low quality of our goods, helped by artificial aging, means that we simply throw away a large part of our welfare profit. Perhaps we can't help it because our mentality is wrong, but no matter how you try to excuse it, it remains stupid." They were dearly pleased that I was at last awake and was able to understand that efficiency and justice were not just loose, idealistic words. But, good heavens, first a hundred times the population density and then times the production. How is that possible? Unbridled overpopulation and unbridled overproduction? Rubbish! We do not know what the words "overpopulation and "overproduction" mean. When we complain about overpopulation, we mean inefficient economic structure and planning. With overproduction, we mean roughly the same: the low purchasing power of the average income through the inefficiency of our antisocial economy. As soon as we begin to distribute our products in a just manner, we will see that the problem lies in a too low productive capacity.

"Because, friend Stef, make no mistake as to what men will use if given the opportunity. Take, for example, the consumption capacity for a family who, because of their financial state, can have everything they want. Their level lies at least twenty times higher than the world average. Your economy will have to work very hard before you can create genuine overproduction. This shows itself in a failing interest in a larger income when it means a higher working intensity or more responsibility. The remedy is simple: everyone works shorter hours. It works both ways; shorter hours lower the income and stimulate consumption. The wish to work increases in order to increase the income and at the same time the first steps can be taken in narrowing the wage gap by raising the minimum wage. As soon as market saturation manifests itself, the leveling of wages increases. The 'rich' remain as rich as they were before and the 'poor' are raised to the same level and so, with efficiency and justice, you create a stable world!"

"So everyone will then have the same income?"

"Yes, exactly. The prosperity is then fairly shared by everyone. Unlimited prosperity creates complete security."

"You work shorter hours than we do?"

"Yes, much shorter."

"Everyone has the same rights? They all earn the same and there is no difference between a white collar and a pair of overalls?"

"No. Everyone wears overalls from time to time. That is why we hate maintenance and repair work. Are you beginning to understand something about our quality?"

"Yes, and that is another argument for efficiency: you get a different set of tasks for the people. Does your world president also wear overalls sometimes?"

"Of course, since there is no upper or lower class anymore, only a difference between directive and executive work. When we talk about a short work period, we are talking about noncreative production and maintenance work, and everyone does this, even the president. Direction is purely creative work and we do this in our free time."

"Am I to understand that all the top positions are a sort of hobby?"

"We do not differentiate between high and low positions. We choose people to direct us who, outside of their slave labor, also have an interest in this activity as an expression of their creativity, like a hobby. In this stage of development, creativity is no longer considered labor, because it is the target of men."

"That's all well and good, and I can see that if we were to use the same system, things could be much better for us, but to induce people to change their entire way of life is not easy, not to say impossible. It requires higher education and more knowledge. It's easy for you to teach people by the use of your information radiation. Why don't you give us the knowledge to make such machines? We could then easily guide our people along the right path and it would greatly increase the tempo of Earth's development."

"We tremble at the thought of giving you the secrets of immaterial radiation. It would not be long before man discovered that it could be used as a weapon, with the almost certain result of self-destruction. "And even if it were not so used, who would profit from its advantages? Surely only the developed nations, because the equipment is expensive. This would mean that the white race would be in an even stronger discriminating position against the other races. A race that does not know its responsibilities cannot be helped."

Moving on to the next subject, freedom, they began by showing me one of their living, or house, cylinders. The film opened on the ring road outside the building. An automatic sliding door opened and gave access to the parking space for the cars, in the basement. The cars stood in neat rows, four deep, with the front wheels in shallow grooves in the floor. The camera moved through this area and out through a door which led to the central "garden" of the hollow cylinder. A beautifully laid out recreation area of at least three hundred yards in diameter. A quarter segment of the cylinder was glass which, combined with a gigantic glass roof about three hundred feet above the ground, gave the effect of being inside a huge glass house. Galleries ran around the inside at each floor. And on the lowest gallery, which was wider than the rest, small rail transport units moved. The central space was a huge garden of tropical-looking plants and flowers. A huge central pillar was at its base, surrounded by a rock garden with plants and flowers in the most exotic colors. Streams and waterfalls came out into ponds and tanks that contained strange and brightly colored fish. Green, mosslike areas were broken up by patches off lowers and shrubs. I saw sport fields and playgrounds with rather technical-looking apparatus, ponds in which children were paddling and a large swimming pool into which people dived from a large, slowly turning wheel construction.

Most amazing was the behavior of these Iargans in the water. Even small children could swim with a power and speed that was nothing short of surprising. They floated effortlessly, many swam in pairs with their arms entwined by taking turns in making a sort of scissor movement with their legs. They had immense pleasure, and demonstrated something that could be called a feeling of freedom, freedom from gravity. They sprung and dived under water for so long that it was difficult to see if they ever came up again. The real meaning of this water affinity became clear to me. **These beings did not emerge from the land as we did, but from the water; they developed from amphibians. The broad webs between the widespread fingers and toes was originally a fin which enabled them to spring out of the water like dolphins. They could move in water faster and more easily than on land.** Everywhere were seats, arranged in half or full circles. An magnificent meeting point for young and old, for the Iargan children did not play in the streets. Everything necessary for living was here, a complete city housed in one huge cylinder, highly efficient and superbly comfortable.

Before I go on to describe their houses, I would like to say something about the general layout of these buildings. In the basement, a huge set of machinery was installed. They used the planet's internal heat as the only power supply and this was distributed as water, under extremely high pressure and temperature. Except for this, these buildings were completely self-supporting. *Even an external sewage and garbage collection did not exist.* They had a fantastic recycling system. Most of the garbage was separated into its raw materials, while human excrements were used as dung for the surrounding agricultural lands, resulting in a nearly one hundred percent circular course. The final debris was burnt and ground to a fine powder. Together with waste water, this was pumped away, deep into the planet's crust. This had something to do with the prevention of heavy earthquakes by means of initiating light ones.

The next floors, underground, they used for offices, workshops and production work at a full day's cycle. They worked at home. This was to prevent unnecessary transport of people to and from their work. Speaking of overpopulation and pollution, there was really something to learn for us! Something else that we could learn from was their method of food production. They only used the word "overpopulation" in relation to the quantity of food that is available; as long as everyone has enough to eat, the planet is not overpopulated. They are very careful to prevent food shortages as this would disrupt their whole society. Investments in the farming areas are much greater than those even in the housing sector. Cultivation, and the associated ground-water control, the spraying, fertilizing and the agricultural machines demand gigantic earth transports and millions of kilometers of pipelines and drainage systems, and again the construction of a canal system and gigantic pump stations. ....cont.under.



A view of one of the huge automated cultivating machines.

Text for drawing: *Huge automated cultivating machines consisted of great bridge structures with a free span of more than a hundred meters. These bridges moved transversely along rails which ran the full length of the fields. They work a piece of land up to 250 meters wide by 10 kilometers long and operate in rows of up to*

20 machines side by side. The bridge structures carried a variety of equipment which was controlled from a central control room. Fertilizers and sprays are introduced via the central rail and administered by means of a rolling tank. At the end of the rail the whole unit turns and returns over a parallel strip of ground.

Cont: All this is a part of their attempt to accommodate the largest possible number of beings on their planet; the first requisite for this is a maximum food production. They then introduced me to one of their numerous cultivating machines which are mounted in the vast fields situated between the house cylinders. These consisted mainly out of an imposing bridge construction with a free span of more than a hundred meters. These bridges moved transversely along rails which ran the full length of the fields (some ten kilometers) in rows of twenty, placed side by side. The bridges were supported about three meters above the ground and could carry a variety of equipment which was controlled from a central control room. One of the bridges that was working was fitted with a machine that performed many operations in one go. First a strip of ground was cut out in two layers by two U shaped blades; then the strip was sterilized with a deadly (!) ray, sprayed with a muddy looking fertilizer, turned, and returned to the furrow. Then a row of fast moving gooseneck-

Chapter VI

Individual Healing Session

The Individual Healing session embodies all of the techniques that you have used previously and consolidates them for use on a one-to-one basis. The session comprises the following three parts:

A. Almighty Knife (Chi Knife)

The almighty knife can be used for any health problems. We can charge the knife with Yin or Yang energy. We charge the almighty knife most often with Yin Power. Yin is the cold energy and is used for any inflammation, pain or heat. Yin is used to break up illness. Charge the almighty knife with Yang for strengthening, melting or expelling. Only use the Yang when there is no pain.

B. Energizing and Activating the Immune System

C. Cleansing the Internal Organs

A. Almighty Knife



Fig. 6.1 *Almighty Chi Knife*

Since the dawn of ages and our descent into the material realm, we have constructed, manufactured and used tools to facilitate the progress of events. They are an extension of ourselves that enable us to enhance, mould and magnify our intrinsic nature as inquisitive playful beings.

We have used implements to help nourish, protect and amuse ourselves and further our progress in attempting to understand the ‘how’ and ‘why’ of existential reality. The knife has served as a means to carve our way into the present. It is a simple, yet powerful ‘friend’ and derives as much power as we wish to lend it.

type pipes planted the seeds for the next harvest, and finally, the surface was rolled flat and covered with a transparent layer.

When the machine was finished the result resembled a dancefloor. They certainly were masters in automation. Beside the farming, their food production was supported to a great extent by the fisheries. Their preference for fish probably has something to do with their amphibian origin, and the fact that they have so many oceans. Their method of catching fish is, in one word, absurd. So absurd in fact, that I thought in the beginning that they were trying to make a fool out of me. Later, I discovered that this was just a by-product of their system of climate control. It was a gigantic water-moving project whereby the warmest water in the oceans is pumped to the islands and seems to have something to do with controlling the rainfall. The system utilizes thousands of kilometers of flexible pipes running under water, each with a.......

text for picture/drawing: The bridge structures performed many operations simultaneously in one run. First, a strip of ground is cut out in two layers by two "U" shaped blades. Then the strip i~ sterilized with a ray, is sprayed with a muddy-looking fertilizer, turned, and returned to the furrow. Then a row of fast moving gooseneck-type tubes plant seeds for the next harvest. Finally the surface is rolled flat and covered with a transparent layer, leaving the field looking flat and finished as a dancefloor. .....

.....diameter of more than one hundred meters. The catch consists purely of fish that have been sieved out of the system. The strange thing was that these fish looked just the same as fish here on earth. I saw some fish with a length of four to five meters which, for as far as my knowledge of biology can be trusted, were perfectly normal sharks. I also saw swordfish; and preditory fish were hunted with the aid of sound waves and flavored bait, the carcasses were thrown back into the sea. Beside this, they also eat meat, but it would be going too much into details to describe their breeding methods here. To tell the truth, *I was somewhat disappointed to see that a super race still killed animals.*

I only relate this information on their food production in order to comply with their request to do so; they see this information as an important part of the process of identification. This process will be dealt with later. For the same reasons, I will also describe some details of their schools and the hospitals in the house cylinders. These were, together with other social services, situated on the top floor, with the glass roof serving as the ceiling. The school classrooms were square, with four walls from corner to corner, forming four triangles. Where the triangles joined in the middle were four large screens, on which the lesson was shown. The means of teaching was exactly the same as was used for me in the spaceship: a film with a simple explanation;

the real information was transmitted by the radiation.

In the space behind the four screens sat the "teacher," who really had nothing to do with the lessons but acted more as an observer, noting the behavior of the children and advising parents on their upbringing. *The lessons were the same over the whole planet, this having the advantage that should a child move to another area, which happened frequently, he could simply pick up the lessons where he left off without having to repeat or miss anything. This basic schooling continued until the child had reached the age of fifteen or sixteen years.*

When I think of the information that I gamed in two days from the radiation, I can imagine the level these children must reach when subjected to the radiation for ten years or more. Their basic schooling must be above the level of our universities. Having completed this basic instruction, the children moved on to the advanced schools, a normal cylinder where all the students lived together and where they could specialize in their chosen subjects. The hospital that they showed me was not the type that was situated in each of the cylinders, but areal hospital where special medical treatment was given. Seen from the outside, it looked like a normal house cylinder, but half was the accommodation for the personnel and the other half for the patients. I do not think it is necessary for me to describe the working of such a hospital in detail. The reader can imagine that everything was regulated with the usual Iargan efficiency, and to describe things that can only be clarified by superlatives becomes rather boring. One thing, however, does strike me as interesting. Each patient was "connected" to a computer that catered to the individual needs and wishes of its "charge"; pain alleviation, medicine, contact with friends or relatives, entertainment or information-the computer took care of it!

"Do people still die on your planet?"

"Control of death demands a different medical ethic. We feel justified in prolonging the possibility of happiness, but not in extending a life that nature regards as being at an end."

Going back to the houses, I noted that silent, air-operated elevators with electromagnetic stops functioned as vertical transport, while, broad galleries formed the horizontal connections. From these there was a fantastic view of the central gardens. Each house had a large entrance hall which was open to the gallery, so that anyone who happened to be passing by could look into it. This would not have seemed too strange to me had it not been for the fact that on one side was a row of showers! Here my shocked confrontation with the living habits of these beings and the breathtaking freedom that typified their relations with one another began.

Young and old had the strange social duty, on returning from school, work or any other activity outside the house, of washing themselves from head to toe before re-entering the living quarters. What happened then? Everyone undressed in the hall with the greatest of ease and stepped into the shower. These were tubes, about three feet in diameter, with a glass screen in front, and on the floor were two raised steps on which to stand. At the back of the tube was a vertical bar, to which, at ground level, a flat elliptical tube was connected. Having closed the glass screen, the occupant pressed a button and the elliptical tube immediately began spraying jets of white foam while moving upwards along the vertical bar; the occupant was transformed within a few seconds into a snowman. On reaching the top of the bar, the spray changed to clean water and came slowly back to its original position at the base of the tube. Warm air was then circulated in the tube to dry the bather, washed and dried within three minutes with a minimum use of water. Having dressed, one was then permitted to enter the living quarters. Dressed is perhaps the wrong word, for their house attire was nothing more than a kind of sarong that left the woman, as well as the men, naked above the waist.

You must not think that this bears any comparison with humans dressed in the same manner, the only really noticeable difference between male and female Iargans being that the men are more powerfully built and more muscular than the women. Their behavior toward one another was really remarkable. I never once saw a man in the vicinity of a woman who did not put at least one arm around her. A big hug was their normal manner of greeting one another, and this also applied to the children. When the warm greetings were completed, the camera followed the party into the house. The hall came out in the corner of a large room of about sixty by sixty feet, the central living area of the house. The first thing that I noticed was a huge glass wall over the whole length of the room, which gave a magnificent view of the surroundings. I could see the imposing rail system that passed through a woodland area, and on the other side, two more of the cylinders. The floor of the room sloped down toward the windows in a series of shallow steps and stopped about nine feet from it, where the edge was finished in a king of balustrade. The window continued down to the lower floor, where it ended in a wall about two feet high. The interior was luxurious, but the color combinations were rather too bright for my taste. Loose furniture was nowhere to be seen. The seating was built into the floor in the form of couches, spread with thick, comfortable cushions.

The lower floor was connected to the upper by two steppless "escalators," moving or stationary at the will of the user. The "bedrooms" were not large, but intimate and colorful. In one wall there was a large screen and another contained a shower identical to the ones in the entrance hall. The ceiling glowed with a diffused orange lighting, and strange objects decorated the walls. The next scene was fascinating: the family at table. The group of some twenty-five people, about half of which were children, gathered in a rather bare-looking corner of the large upper floor. One of the company operated a kind of lever and out of the floor rose a vertical "wall" that opened out into a table about eighteen feet long and five feet wide. At the same time, two sliding panels in the wall opened to reveal a cupboard containing partitions and a lot of complicated equipment. In the manner of a self-service restaurant or cafeteria, each person took a tray and helped himself to various dishes, which were then warmed up for a few seconds in an ovenlike apparatus. Within a few minutes everyone was seated, cross-legged on the floor, around the table. At the head and tail ends of the table sat a man and a woman who did not eat with the rest. As soon as everyone was seated, the man at the head of the table raised his hand and said something, upon which the rest became silent. They held in one hand a gold-colored, spoonlike implement and the other hand was placed on the knee of the person next to them. The people eating remained silent and listened to what the man and woman who were not eating had to say. It was a fascinating scene of the customs of these beings from a strange, distant world.

The way they made a ceremony of eating made them seem rather like mythological gods. When everyone had finished eating, they all stood up and each threw an arm around the shoulders of his neighbor, thus forming a chain around the table. They stood that way for a couple of seconds and then commenced to dear their implements from the table, and when this was finished, the table was again retracted into the floor. The spoons were placed on a machine for cleaning, the plates and trays went into a disposal unit for plastics and everyone finished by washing his hands and cleaning his teeth. Hand towels and dish towels were nonexistent here. Everything was dried by warm air, and I began to wonder what the Iargan housewives had to do, especially as there seemed to be five or six women in each house.Shopping was done automatically by a computer; the order was placed in the computer and the goods were delivered sometime later in a container. "Don't your women have to do housework anymore?"

The Iargans laughed. "We have told you that we no longer have any class distinctions, and this also applies to women. Chores are shared equally by everyone."

"But when men are at work outside the home, the women must surely work too."

"That is true. If men work for three hours a day, women do the same, no more and no less, otherwise there is discrimination." "Strange. So the women may only do housework for three hours per day?"

"Your ideas are slow to change. Housework, in other words, the necessary upkeep, is done by everyone together. If the task of some women is the upbringing and teaching of the children and other social work, then they too have the same right to work outside the home as men do."

"What about the women who don't have any children?"

"All Iargans have the same duty to the children in the group in which they live. The upbringing of the child to the mentally stable and developed adult that a high culture needs is a difficult and complicated task. The schools plant the knowledge by means of the radiation but the adults must help the child to transform this knowledge into experience. The home sphere plays an important part in the development of these things. A race that seeks income leveling must give the utmost attention to raising the mental level of the people, because the raising of the general minimum wage must be in balance with this level. Value and income differences between people can be overcome only by a high minimum mental level."

"So those women feel happy with the task of teaching children because they are able to fulfill themselves on different levels. They choose what they do."

"Everyone who fulfills his or her task with interest and inventiveness feels happy. What more could one possibly expect from life than being successful in love and able to teach this to children."

"This 'love,' has it got anything to do with sex?"

"The sexual relationship between man and woman plays an indispensible but nevertheless unimportant part in our understanding of the word love. It is directed to be creative individual expression and that is a thing that must begin to be taught to children as young as possible.

"I don't understand that."

"That is logical, for we have only just begun with our explanation of the concept of freedom. Let us start at the beginning. Freedom is the absence of compulsion and because compulsion is a form of discrimination, it follows that freedom is the absence of discrimination. A step further: freedom exists, logically, on the

Its design may consist of any combination of the five elements (Earth) which when combined with Universal (Heaven) and Cosmic (Man) forces, provide a unit of energetic substance which receives and transmits magnification, purpose and power in accordance with the human will that governs it. ‘Chi Knife’ and “Powers of Ten’ adopt the precepts of a truly magical existence. When we arrive at our destination we will realize that we have indeed turned “the Wheel of Law’. In achieving this end we will have completed the cycle and returned to the beginning of the journey. We will understand that the simple things in life, like the knife, contain the same amount of power as state of the art technology.

We are all returning to the Garden of Eden. Complex telescopic and microscopic equipment now enables us to see the truth:

> “Inside has no outside; outside has no inside”.

They are one in the same thing. When they merge together we will indeed enter the Kingdom of God.

Outline of Practice

1. Hold the knife in the right hand (left, if you are left handed). Hold the other hand near your body, with the thumb and index finger touching. Project the Chi Knife as big as the universe, ‘long and big - reaching to Heaven’. The bones in your arm are hollow and the ‘bottom’ is sealed at the shoulder. Feel them ‘fill and pack’ with the power coming from above.
2. Then give the command: **“Power comes from the east. This Chi Knife has the power to dissolve all the negative energy, sickness and bad fortune. By my request, please carry out the order now.”** Wait until you feel that your arm and the knife are heavy and full of Chi.

Eye Problems

Use the thumb and the index finger to hold the eye wide open.

You hold the knife like holding a pen, 3 to 6 cm away from the eye. Use the little finger for leverage and support.

WARNING!

DO NOT USE A KNIFE. THE **MASTERS** OF GREAT EXPERIENCE USE RITUAL SCALPEL TYPE KNIVES. THE STUDENT SHOULD USE THE “SWORD HAND” FINGERS (P.76, FIG. 4.24).

DO **NOT** USE SHARP OBJECTS NEAR THE EYES**.**



Fig. 6.2 *Hold the knife three to six cm. from the eye.*

basis of justice and efficiency. The development of an intelligent race is governed by two dangerous natural laws, which in fact are the laws of cosmic selection. They formulate the demands for entrance to the higher regions of evolution, the cosmic integration."

"And is that worth the trouble?"

"Certainly, for it is the choice between everlasting life and everlasting death."

"Oh, I see, a religious aspect. That ceremony at the table had something do to with your religion too?"

"Our understanding of religion is so far evolved that it is incomparable with yours. Have you a religion?"

"I am a Catholic."

"How strange, a Christian! We are familiar with the work of Christ and the Bible. **After you've eaten, you must explain to us how someone with so much property c*an seriously call himself Christian*. We are intrigued.**

On the other hand, it simplifies the explanation of the two cosmic selection laws. The first confirms Christ's condemnation of social discrimination. A high level of technical development liquidates every discrimination and compulsion under pain of chaos and eventual self-destruction. The Earth demonstrates the justice of this law in a convincing manner. The social chaos exists already and the threat begins to manifest itself. At the moment, only the great powers have nuclear weapons at their disposal, but the smaller nationalist groups will soon be in the same position. "The situation becomes more dangerous every year. Within a short time you will discover the possibility of immaterial radiation and then a handful of people will be capable of producing a weapon that is capable of destroying all mankind. Where does all this lead? How long can a civilization continue to exist where science does not know its responsibilities?

"The second selection law compels the correct understanding of human relationships. It poses 'Christian love' as a condition for cosmic integration. **Only unselfish behavior that restores the original efficiency of natural order can give an intelligent race the certainty of survival until cosmic integration is achieved."**

"That word 'unselfish' sounds so strange."

"The selfish behavior of the masses, where everyone takes everything they can, prevents the ability to work for the common good-to create, for example, a clean planet where the balance of nature can be maintained for an unlimited time. It is also impossible to limit the use of natural resources for the sake of future generations, because a selfish person cannot give up anything for someone else. The greatest problem lies in the law of degeneration: a race that does not succeed in restoring the efficiency of natural selection as it existed in the prehistoric times shall become extinct."

"How do you justify unlimited freedom with reproduction selection that drastically limits the choice of partners?"

"The answer is that it *can only be justified with unselfishness. The partner choice is determined by one's feeling of responsibility."*

"I see, through artificial insemination."

"Where did you get that idea? That doesn't prevent degeneration, it accelerates it! "We are not concerned with producing that biological phenomenon, 'man.' The body with all its selfish demands is just a shell. *We are only concerned with the creative intellect, the soul that is capable of unselfish thought.* How do we educate children for the freedom and happiness? Freedom is the absence of the effect of compulsion on the individual's behavior. **Freedom cannot be obtained with a weapon in the hand.** It can only be obtained by the parents' careful mental forming of their child then, by the correct conception of good and evil. It is a difficult and complicated task that only becomes possible with natural parental love and the variety of other groups.

"There may never by any doubt as to who is the father or mother of a child. The important thing is not having children, but bringing them up. For this reason, artificial insemination is unacceptable. "The unselfishness is the selection requirement for the immortality of the race, but it is also a requirement for a being with a high mental development before he can achieve happiness. *Happiness is being at peace with oneself and one's surroundings*. This is determined to a large extent by one's success in achieving self-set goals, in other words, *by a ruthless appraisal of oneself.* This individual striving to reach a self-chosen goal is the creativity in man.

"Creativity is thought that is continually occupied with changing the circumstances in one's life or in that of another. It is creativity that drives men to do 'even more' or 'even better.' There are two kinds of creativity, the material and the immaterial. The first is the individual striving to improve his own living standards. This is done mostly in the field of sex, property and power and is the cause of all the misery on this planet. The individuality expresses itself in egocentricity, greed and avarice. In the continual reaching for a material goal, a measure of satisfaction is experienced, *but when the goal is reached, the satisfaction shows itself to be relative and of short duration,* *merely an object for comparison with what others have. So it continues toward the next goal, usually a higher income or a higher position, and the search continues, because the satisfaction lies only in the searching.*

But then a time comes when the search cannot be continued because of sickness, or old age, and life continues in dissatisfaction with itself. The individual has not understood that material gains can never bring lasting satisfaction and happiness.

"On the other hand, there is the immaterial creativity-your Christian love - and this is lasting happiness. It is the continual striving to improve the living standards of others. It expresses itself in helpfulness, understanding, pity, tolerance, friendliness, esteem-in short, the total concept of unselfish love."

"It sounds to me like a sort of sterile idealism."

"Try to understand that it is not. Do you believe that social stability creates unlimited prosperity and complete security?"

"Yes, I can accept that."

"Can you also accept that a man without creativity can never be happy?"

"Yes, I understand that."

"What goal can human creativity have when material motives vanish? What can a materialist do in our world, other than be bored to tears? *What does a man really possess who possesses everything except love? The answer is: nothing!*

"Everything that previous generations have done to create a stable world with a high level of scientific and technical development and unlimited prosperity is worthless when man lacks the love that can give him happiness.

"Every unselfish deed, every self-sacrifice, heightens the feeling of personal value, of satisfaction. A man who has reached a high degree of unselfishness manifests a lasting personal value as a noticeable side of his personality - wisdom - which appears to be unaffected by setbacks or aging. He becomes invulnerable in his feeling of personal value, his peace with himself, his happiness. There is no alternative, Stef. Natural selection laws are inexorable. Only a race with a high level of unselfishness, or, as we call it, an immaterial structure, can survive."

"Does all this also apply to us? I can’t imagine this world being inhabited by people who love each other."

"The more we talk, the more we become convinced that you are not a Christian. The whole point of Christ's teaching - love - is completely strange to you. You have apparently never heard of the striving for unselfishness in the Buddhist religion. There is no choice. O*nly when man is free of material influences can he succeed in bringing up children who, through their unselfish mental attitude, can be really free and happy.* You must teach them to love and concern themselves with others. They must learn to be very expressive with their feelings. This makes great demands on their eloquence, to be able to put their feelings into words. This is characterized by their honesty, spontaneity and enthusiasm, their helpfulness and, above all, their ability to raise their love contacts above the physical to great spiritual heights. We seek adventure in the quantity and depth of our human contacts. You have seen this all on the screen in front of you. Iarga is a planet where the people love each other, where people are happy to meet each other and where they find it a pity that they can only take one person at a time in their arms.

"As soon as our children have reached the age of sexual maturity, the parents arrange for the child to undergo a psychological and medical test. If they pass this, they are then declared legally free and obtain the rights of voting and sexual freedom. We celebrate this with a great feast. The parents rejoice with the children in the fact that they have been judged as being worthy of true freedom."

"Good lord, Then the parents permit them to go to bed with anyone and everyone?"

"Your surprise is understandable, because you do not know the character structure of our race. *Our urge to reproduce is much less than yours, partly because we do not experience the same pleasure in sex. We do not use it as a way of passing the time, but as an expression of intimacy and love. The evolution cycle of Iarga is different and we have a precisely controlled population growth. Earth should strive for a population explosion so that the race is complete before it has a chance to destroy itself. Sex plays a completely different role by us, there is no comparison.*

"We should add that the position of our women is also vastly different to yours. They have a different creation mandate which causes a fundamental difference. Earth women have a heavy task(oppgave) in the future, which is why they now have the command of obedience to the man. This will give her the right in the future to take over the task of leadership without damaging the principle of equality.

"Iargan men and women are equals, but have different mandates. Women have the dominant position because they must lead the mental development, they are not sex objects. The subject of sex, which here on Earth is regarded as forbidden fruit and therefore takes on an unhealthy appeal, has no adverse effect on us at all. *A man-woman relationship that is based solely on sex we consider degrading.* Our women would rather die on the spot than be used for a kind of physical training; they make high demands of their partners. They demand their interest, their tenderness and mostly their respect for her as a person, for her intellectual level. Everything is directed at creative expression and the sex act plays a very minor part in it.

"In many relationships, sex is totally absent, without that absence having any effect on the satisfaction experienced. Once you have really learned to live, it is difficult to understand what Earth being can have as their reason for living."

"We often wonder about this ourselves, but I think I am beginning to understand what that reason should be."

The lesson continued, but I am afraid that it did not penetrate to any great extent. I was too busy with my own thoughts. They were explaining their marriage concepts and personal relationships, based on the separation of sex and propagation, but my mind was filled with questions and doubts. All this was very interesting, but what had it to do with me? It was dear that they had a better life than we have, but, then, they were not human, they did not live in our world, and if they did, they would surely be the same as we are. If, but, why, how; my mind was running around in circles. At the moment that they tried to make clear to me that sexual freedom was not permitted to the Earth because we failed in love, I gave up.

"What is the point of this confrontation with your way of life? Your way of life is not possible for us, even if we wanted to live as you do. The Earth can never become like Iarga. Your society strikes me as being a curiosity that has no practical use for us whatsoever."

"You are right. The Earth will never become like Iarga. The Earth is, in contrast to Iarga, a thin-atmosphere planet of a different character, and this applies also to her inhabitants. We *have a different evolution cycle than you, but the goal in the evolution of all the intelligent races in this universe is one and the same.* **The ways are different; the goal is the same.** The practical purpose of this confrontation is the planting of insight, not insight into our technique or our social structure, although this could be of use to you, but into our mentality.

CHAPTER 4

Iargan Society



Chi knife - "Almighty Knife" helps all eye problems". Cut up and down and sideways in the cross pattern 'through' the eye thoroughly. Tell the student to move the eye left and slowly move to the right as you cut with the Chi Knife. When they move their eye to the right, move the Chi Knife to the left. **Remember that the knife is used for 'energetic surgery' and should never make contact with the eye itself.**



"Slice" the eye toward the right side for 50 to 100 knife movements and do the same to the left side.

Fig. 6.3 *"Almighty Chi Knife helps eye all problems".*



"Almighty Knife, please destroy all kinds of wounds, warts and tumors". Cut up, down and sideways in the cross pattern through the part that has the 'condition'.

Fig. 6.4 *"Almighty Knife, please destroy all kinds of wounds, warts and tumors".*

The almighty knife can be used for any problem in the body. Follow the same procedure to carry out 'energetic surgery' on all parts of the anatomy. It is especially good for soft tissue repair, including the brain.

When you feel that the Chi Knife is full of sick Chi, spiral counter clockwise and discard it down to the ground. When you feel that the knife is 'empty' charge it with Chi from the universe.

I should try to sum up a number of my conclusions. Iargans and humans would seem to be totally different beings, but in fact the only real difference is a body that is adapted to life on their respective planet. Other differences are caused by different upbringing and environmental effects, but intellectually and emotionally we are about the same. If a Iargan were to be born on Earth, he would become a normal human being; and if a human were to be born on Iarga, he would become a normal Iargan. So, if this is true, how do we account for the vast difference in mentality? The oversocialized community that eliminates all discrimination and aggression would demand a tremendous improvement in human mentality, otherwise it would be misused by the greedy and the lazy. It demands a race with a high degree of unselfishness."

"Am I to understand from this, that Iarga's secret lies in a perfect method of bringing-up children? "

"No; due to her planetary conditions, Iarga has a different cycle of evolution than the Earth. Due to this, we have the ability to continually improve our mentality through many generations. Iarga's secret is that we are bound by the law of cause and effect and are therefore subject to reincarnation-selection. This law lost its validity on Earth long ago. On Earth, the weeds grow up with the corn until the harvest, and then the selection takes place. Because of this, mankind cannot improve her mentality. You are still troubled by the demonic element of human dualism and there is no escape. "On Iarga, on the other hand, the weeds are constantly removed, which neutralizes the demonic element. Naturally, the childrens upbringing plays a large part in the mental attitude, but it is not the cause of the improvement. "Your supposition that a human born on Iarga would grow into a normal Iargan is incorrect. In the first place, he would not have taken part in the reincarnation cycle of Iarga and what is more, his character would not fit. "Due to the planet conditions, a human is willful and disobedient. He obeys no God, no commandment, and no conscience; he even pretends that he doesn't have one. He knows everything better. I *hope that we never have to accept one of these beings into our system, it would be a terrible mistake, without counting the damage it would do to his surroundings.* **A large dose of unselfishness can only exist in an environment that is protected from evil.** You see that it is not as simple as you think."

"Great Gods, what have I got myself into? More or less by accident I seem to ask a relevant question, and during the answer I hear expressions that are meaningless to me. What am I supposed to make of expressions such as reincarnation-selection, evolution cycle, and demonic dualism?"

"To answer this we will have to explain the whole plan of creation, is this what you want?"

"Certainly!"

"Excellent, but we will have to change the nature of our explanation. Before long, something exceptional is going to happen, the Earth's isolation will be broken. The exchange of information between intelligent races will take place, and this is bound by stringent rules and conditions. "The first rule is that such exchange must be preceded by an identification procedure in which credentials are exchanged. Next to the physical confrontation, this demands an illustrated description of the planet and the type, evolution, and history of the race. Normally this takes place during exchange visits, which implies the capability of space flight, but in your case a different procedure will have to be followed, you will visit Iarga only in the mind by means of a special system that we have established. The pictures that you have stored in your memory are real, and not from a film. "We possess the power of mind over matter, as you also will within a short time.

"Before we can begin with the explanation of the plan of creation we must complete the identification. You must know who we are, where we come from, and what our intentions are. We already know these details of mankind, because we have access to the source of human knowledge, or if you prefer it, the spirit of man, where all human thoughts and experiences are determined. We know your thoughts too."

"Now I realize that you started this identification process already from the beginning. I can't think of any other explanation for this detailed description of yours. Did you know how this conversation was going to turn out before we began?"

"Yes, time and matter are creations out of the void and are therefore composed of pure contradictions that leave the original infinity intact. Therefore, they do not really exist. *The timeless consciousness that sent us here knew who we would find here,* and what he would do with the information. Every detail of every human life is known in advance."

"Then this meeting was no accident?"

"Most certainly. *The goal of creation would be impossible if coincidence did not exist.* A coincidence just happens, and is therefore free. The fact that a timeless consciousness in a nonmaterial existence knows the outcome of the coincidences in advance, changes nothing in the freedom of the coincidence. For us you are, and will remain, a coincidence; *even when we know roughly what will take place.*

Your freedom remains undamaged; should you decide to leave now, nobody would attempt to stop you. **If you decide not to use the information you will receive, you are perfectly free, nobody Will compel you."**

"I reserve my comments. May we continue?"

"Since we have now received your freely given consent, we can intensify the further transfer of information. You will be induced to sleep, and when you awake, you will recollect a very lengthy lecture in which you have gathered a wealth of information."

The strangest thing about this is that I remember nothing of falling asleep or waking up. If they had not told me about it, I would have noticed nothing except that something had gone wrong with the time. All the information that I can remember so clearly, *would normally have taken weeks to gather;* I realized later that the exercise must have been completed in about one and a half hours. It is a casual demonstration of their power to manipulate the human mind, their power of "mind over matter" that will be explained in the second part of this book. It confirms my first feelings during the confrontation, the fear you feel when you know you are helpless; even these steel walls cannot protect me from this intelligent pressure group. Some kind of primitive instinct warned me. I wonder if my participation in this meeting was as voluntary as they would have me believe. The mental pressure that was put upon me, especially in the second part of the conversation, certainly gave me my doubts. Now, after many years, the doubts have gone.

The question of my freedom during the confrontation is no longer of importance, the question now is, if I am free in the use of the information, and the answer to this is yes. No person or situation has exerted any kind of pressure to influence my decision in whether or not to publish the information. Having completed this note, I will continue with the real purpose of this book, and relate the information that has been burned into my memory. During this, I will ignore the dialog form, and concentrate more on the efficiency of reporting. The subject is the further development of the Iargan race and in particular the birth of the superculture. Their definition of the word **civilization** or culture has nothing to do with the scientific or technological development level, **but with the manner in which the community takes care of the handicapped or weaker beings**. (This is exactly as the danish, clairseeing editor Martinus(1890-1981) says: A sivilisations stage of evolution, can be measured in how the society takes care of the weak and sickly ones in the society. R.Ø. comment)

The word superculture defines the situation that arises when through individual effort, a groups structure has arisen which abolishes any discrimination against any individual. It is of the greatest importance not to forget that this situation was only possible *due to the fact that the reincarnation selection exists on Iarga* which roots out the adepts of evil. This is therefore an environment which is protected from the influence of evil. This development is also of importance to us, because we will also develop a superculture one day. This Earth-adapted version will develop during the approaching kingdom of peace and justice after the "resurrection" selection.

The things described here in connection with the identification procedure are only the developments themselves, the background causes can only be dealt with in part two. The description of this development fits in perfectly with the previous explanations. The universal economic system shows itself in practice to be an efficient production system of goods and services, placing prior importance in the sectors housing, nutrition and transport. The produce is then shared by simply controlling the individual use or consumption. The aim of this system is to free the individual as much as possible from non-creative, servile work. As soon as the production reaches a point of overproduction, the work day is shortened which allows more time for creative pursuits. The importance that they place in creativeness deserves some explanation. They see the purpose of their existence as threefold.

1. The creation of their individual identity. This occurs more or less automatically by being born, by living, and by working.

2. The creation of their immortality by the use of their talents. They stimulate each others activities by attempting to reach self-chosen creative goals. They think that they live on in their works, in their creativity.

3. The choice of their second identity, being the culmination of their daily choice between selfish and unselfish creativity. This determines whether the individual will take part in the formation of a godly or ungodly consciousness. This conviction is the cause of their unbridled pursuit of creativity in the broadest meaning of the word. The first assignment is fulfilled automatically so that the second becomes the most important. *The search for unselfishness comes later.*

This resulted in a dominant interest in freeing themselves for individual creativity. With this idea in mind, they created a highly efficient, almost completely automated production system. Next, they sought to reduce the consumption of goods and services by appealing to the self-discipline, in order to attain a reduction in production or an increase in population. Eventually **they reached the situation in which everyone,**

without exception, had only to work for one day in the week on the direct production process. The voluntary constraint of consumption and the equality of the non-creative work output, lead automatically to the equalization of incomes. People waive (frafaller) their right to consume and their needs decrease.

Then comes the great moment in the development of the Iargan race, the control on consumption is lifted. *All goods and services are freely available to all above a certain age.* The individual self-discipline has come of age, material greed has been conquered. The Iargans look upon this as the beginning of the superculture. ***Free access to all this prosperity, for everyone, makes it impossible for an individual to be wanting when compared to others***. This is the welfare state without discrimination, that takes care of you from the cradle to the grave, that we, lacking the selection, can never create on Earth.(never?? - Martinus means it will take long time - at least 500 years to reach this level here on Earth. RØ:comm)

What a shame, human beings cradled in the warmth of unselfishness would be wondrous. Happiness and satisfaction means reaching the goal of your creativeness together with others, as long as this strengthens the feeling of self-respect. This can only work as long as there are none of the types that always want all of the glory for themselves, and this makes great demands on the leaders of any creative project. This is obviously only a part of their battle to eliminate the spiritual or immaterial backlog. It is impossible to describe this comprehensive system of caring for each other, simply because it is so far removed from what we regard as possible. I think that it may be impossible for many people to imagine such a situation, and I can perhaps better confine myself to a description of some of the end results. A superculture can be recognized by its unbridled creative power. It is unbelievable what a dedicated group can attain in a short time when no time has to be wasted on control or supervision. It is the hey-day of science, technology, and art.

Laboratories and observatories are built and they discover the secrets of the universe. Their creativeness builds gigantic spacecraft which operate on reaction free power, they build submarines for the exploration of their oceans, their knowledge knows no bounds. They develop a strong affinity for beauty, which manifests itself in numerous artifacts. The central gardens in the house cylinders change into complete art exhibitions that attract a constant flow of visitors. Their designs especially, show their affinity with the creator and the universe. Half abstract art forms illustrate the details of creations beauty. A kind of religious art form. They are continually occupied, and demonstrate an activity that

B. Energizing and Activating the Immune System

In cases of severe illness, you will want to do this technique many many times, because it is essential to stimulate the body's defence-systems. This technique is also beneficial for debilitation and infection. You may also want do this in a preventative manner.

Activating the immune system always involves the bone structure, especially the round bones in the arms and legs and the flat bones in the skull, jaw, rib cage, hips and spine. All of these are involved with the production of white blood cells. The **thymus gland** and the **spleen** are of special importance to the immune system, because they are involved with programming and training the white blood cells (called T-Cells) to do the right job. **The lymphatic system is involved in removing toxic waste from the body; it is therefore beneficial to stimulate the lymph flow as well.** This is best done in combination with Chi Nei Tsang. *For details refer to the Chi Nei Tsang Books.*



Fig. 6.6
Touch the top of Sternum to activate the Thymus.



Fig. 6.7 *Happy Cells.*

If you work on a one-to-one basis, first perform the general cleansing session, where you ‘pour energy’ over the other person. After that use your hands, drawing Chi and pushing it through. Remember to push the energy all the way through and connect it with the universe beyond. Ask your student to concentrate on the areas that you are treating, preferably by guiding them, touching each point as you go.

astounds the earthly observer. This can also be said of the speed with which the one discovery follows the other; this appears to have no connection with the fact that they are highly intelligent, but b*ecause they have the ability to tune in to cosmic vibrations, the ancient knowledge of the creator.*

They call this the ability of final contemplation, a state of mind that they can reach as a group. It is impossible for us to reach this stadium for some time, the Iargan evolution cycle is a closed circuit in which external interference is excluded. They are self-supporting because they obey a Godly law, they are aware of their dependence on an almighty creation plan,(the Word).

They obtain the knowledge that we can only learn from others, this is why the races with an open cycle are helped by the races with a closed cycle of evolution. This short description should make it clear that the following description of the final contemplation is purely a part of the identification process, very essential, but for us purely a curiosity, at least for the moment. *It is one of the sweet fruits of a very high level of unselfishness.*

I was witness to a bizarre "happening" in the garden of one of the house-cylinders. Some hundred Iargans sat or lay in a mosscovered hollow about 30m across. This amphitheater arrangement afforded them all a view of a kind of abstract statue placed in the middle of the hollow. It was a hub with a series of shafts, on which were mounted about ten spoked, wheel-like objects. A man and a woman were, as artists, engaged in attaching colored globes to the ends of the spokes; beside them, a man addressed the gathering. Wide-eyed, I observed this colorful gathering that was engaged in a remarkable kind of "touching"(rørende) ceremony. Left, right, and center, all were lying or sitting in, as far as we are concerned, intimate poses; looking and listening. This took place in the early stages of their super culture.

They used a "simple" method of teaching their riper youth to develop their powers of final contemplation, and these had been prepared for this evening by a day of special activities and mental training. The orator in the middle of the group concentrated their thoughts on the object by means of questions, the purpose being that everyone present would feel the answer at the moment of the ecstatic climax. *The contemplation training is aimed at the development of a strong collective thought power*, a matter controlling power, through mutual concentration on a visual object. *In this case a kind of electronic fire that had to be synchronized by their power of thought.* The orator had ended his questions, and now made a gesture in the direction of a number of musicians seated at some long, low instruments.

These placed their fingers on the ten keys of the instrument and began to press them in and out in a certain rhythm, and at the same time, move them from left to right and back again. Each set of five keys could move independently, a sort of movable piano keyboard. The gathering reacted immediately, they sat straight up with their legs crossed and their hands on the shoulders or knees of the person next to them. Seven women dressed in transparent blue veils stood up from the front row and formed a ring around the central object. The artists that had decorated the object seated themselves at another piece of equipment that also had keys, fitted in discs that could tilt as well as turn.

Then the lights went out and they were seated in darkness. I had slowly but surely become used to seeing strange situations, but this was the climax of the Iargan series. The object began to move. It turned in its vertical axis, and the individual spoke systems each turned on its own axis, while tilting at the same time. The globes at the end of the spokes began to throw off sparks as if they were glowing hot. Then the sparks began to form a haze and sprung over between the wheels until the whole two meter high object was transformed into a turbulent ball of fire. The intensity of the light increased, and the original bluewhite color changed into a fantastic color composition of boiling waves of individual spots of orange, red, yellow, green, blue, and white.

At points where spots of the same color touched each other, blinding flashes appeared; the final result is best described as a blinding, boiling fireball, that illuminated the surroundings with intense flashes of multicolored light. The seven veiled women danced with jerky movements to the rhythm of the music, such a graceful, refined, perfectly coordinated dance, that I can only call it staggering. Their transparent veils and their glass-like skin seemed to absorb the light flashes to such an extent that it seemed as if they themselves were emitting a constantly changing glow of light. The haughty concentration with which they performed their dance made them seem like supernatural beings, elevated far above the material. The gathering watched the fire dance in deep concentration, moving slightly to the beat of the music. The turbulence and flashing of the globes began to take on a more regular pattern; suddenly, the lights formed into colored bands and the flashing ceased. At that moment a shock ran through the gathering, they seemed to increase their concentration on the fireball. The music stopped and the dancers stood like statues. Deadly silence. Suddenly, the flashes of light began again, but this time in the colored bands, and in a controlled pattern of movement. This was the supreme moment at which their powers of contemplation manifested themselves invisibly.

Their collective thoughtpower was used to compel(tvinge) the two operators of the electronic fire to perform the fast and faultless actions that were needed to synchronize the colors, something that is impossible to do alone. As soon as the synchronization was accomplished, the two operators removed their hands from the controls and the necessary control was performed purely by the thought-power of the group.This continued for several minutes. The impression that all this made on me was almost destructive. I was in such a state of confusion that I nearly lost control of myself and was at the point of fainting. Only later did I realize why I reacted in this way. I was a real witness to the happening. It wasn't the sight of all this that so disturbed me, but the direct experience of their will power. Their thoughts had to control the confusing electronic fire, and they had to transmit exceptionally strong impulses which only served to confuse me!

It is good that we do not yet possess these powers, they would only make things more difficult for us. On the other hand, it made it clearer to me how they can heal people by the power of thought, it is a power that moves every sinue in your body. The principle of the final contemplation is more difficult to understand. **They state that the creative power of man is not personal,**

***but something that he has borrowed for a time*. It is a reflection of the ever present creativity field that I call the omnicreativity. Totally, it was the power of the creator, and as such, almighty**. Now it is available as an impersonal consciousness component t*hat waits for the intelligent races to use it.*

By using it, it becomes a personal consciousness component by which personalities are created that have the power of mind over matter. *One who has reached this level, is capable of omni-creative contacts without the aid of a group, and then has the ability of final contemplation*. They describe the contemplative climax as the feeling as if the skull opens and the thoughts take wing into an unbounded space. It can also be described as the mind entering the presence of the blinding light of truth and cherishing warmth. (et slags kollektivt kosmisk glimt. Rø -komm) The physical sensation is described as a moment of shuddering ecstatic happiness. No words can fully describe the sensation of coming face to face with the source of all knowledge and wisdom, the being will then approach a condition of all-knowledge and allwisdom through multiple repetitions of contemplative contacts.

This is in fact the beginning of the cosmic integration process, taking part in a new godly consciousness. To attain this, the person must have freely and irrevocably chosen for it, and freed himself from his demonic consciousness component. In other words, he must have passed the selection; we have not yet done this, and it is therefore beyond our reach. The reason for this premature explanation (it really belongs in the second part of this book) is to give the reader some idea of how the Iargans obtained the knowledge of the creation plan in which they instruct others. It can also serve to aid the understanding of the Iargan cycle of evolution as a part of the identification process. How the final contemplation binds a race of billions of beings, who differ little from us, into a homogeneous group that knows only one goal; the perfection of their society by mutual love so that the whole race, including the slower ones, is capable of taking part in the omni-creative integration process.

This longing for absolute values creates a mutual bond, so dominant, that a situation of collective consciousness replaces the individual. In this last phase of the super-culture, the Iargan race reaches such a high grade of love, knowledge, and wisdom; such a level of perfection that it is impossible for us to imagine. Even less imaginable is that we too will one day reach the same level. For the rest of the identification procedure, I refer you to the second part, because it is impossible to separate it from the explanation of the plan of creation. The real reason for their visit was, as has been said, the planting of information, *describing the future of the Earth* and the reason for the external interference that will disturb the authority and sovereignty of the human race. This information has been placed in the second part of this book and, in this, has misplaced the sequence of the original conversation. The next two chapters clearly belong in the introduction and contribute to the identification, they therefore belong in the first part, according to my feelings. I have chosen to use the dialog form again because this conforms with the reality. It is in fact the farewell ceremony which took place when I awoke from my "trance".

CHAPTER 5

Iargan Spacecraft

"We will now keep the promise we made at the beginning of this meeting and show you our spacecraft."

The screen showed a new picture in space with thousands of stars in the endless black depths of the cosmos. In the middle hung four shining round discs, spaced at regular intervals and exactly in line. A moment later these objects turned slowly and I was able to see a side view. I felt a wild triumph welling up inside me.

"Flying saucers-real, live flying saucers!" In the side view they had the streamlined profile of a perfect discus with knife-sharp edges. They were marked from above and below with many concentric rings, but windows or any other sign that living beings were on board were nowhere to be seen. Only on the outer right ship was a small projecting cylindrical ridge to be seen, which blindingly reflected the sunlight. They were connected to each other by a cable and apart from this, I could see no other details. "How large are those things?"

"You can judge that for yourself. The navigation dome is raised in the last craft and you have walked over it."

"You don't mean that small shining ridge?"

"Certainly."

I was shocked. You would build a villa on that platform! "But. . .now, let me see. They must be nearly one thousand feet in diameter!"

"our compliments on your power of estimation."

I was breathless. A supertanker could turn on one of them! "Such a monster is surely not here underwater?"

"No, this is a landing unit, a complete spacecraft of much smaller dimensions that can detach itself from the mother ship, operate independently in space and land on planets."

"Why are they so large?"

"They are not so large. We would like to build them bigger, but for safety reasons, each space command consist of five ships. You cannot see the last one here because the film was made by this ship during a coupling maneuver close to Iarga. The ships are connected to each other by a hollow tube containing a lift. We are therefore able to visit each other."

"Why do they have the discus form?"

"The discus is the final universal form of starships. The main reason is the round form of the propulsion unit, **the sun wheels.** To give you an idea of this, here is a film."

A gigantic, round, factory hall appeared, at least twelve hundred feet in diameter and with a self-supporting roof construction. One of these craft was under construction. A complicated, star-patterned rib construction in which the contours of an enormous discus could dearly be seen. Hundreds of Iargans in orange-colored overalls were working in innumerable floor levels between cranes and other equipment. Close to the outer edge of the discus were two

Outline of Practice

Guide the student as you practice together. Work with your own energy body and tell the student to work with theirs. Presuming that you have already done the previous set of general healing, you can start with the **coccyx**.

1. Be aware of your Tan Tien and connect to the universe. Direct the Chi down to the fingers. Touch your coccyx with the fingers concentrating a beam of white light on to it. Picture the sacrum opening and the white light streaming inside, flowing up the spine and streaming out over the whole bone-structure. Transfer the feeling of Chi in the coccyx up to the universe, multiply it and guide it down to your energy body.
2. Always be aware of the Tan Tien and the universe first. Attract the yellow light; spiral and condense the healing light into the tip of your fingers; move the fingers up to touch the sacrum. Send out a beam of yellow Chi into the sacrum, directing it up the spine. This will stimulate the production of red blood cells. If you are not sure whether you are able to send it right into the marrow, picture the marrow or emit the Chi from your fingers, while at the same time concentrating on the bone marrow of the energy body. Transfer the feeling of 'Bone Chi' up to the universe and down to the energy body.



***Fig. 6.9** Touch the Sacrum.*

3. Proceed to the crown, showering it with violet light. Then spread from the crown throughout the bones of the body. Repeat several times. Instruct the student to feel the bone structure breathing. Ask him/her to extend up from the crown to the Big

round pipes, each of about twenty feet in diameter and about twelve feet apart, one above the other. Outside this doubletube system was a much larger tube with a triangular cross section, rounded off at the corners. This was connected to the other two tubes by tangential, trumpet-shaped pipes. *This ring system was the sun wheel.*

"When I don't understand how a set of tubes can power a spaceship, you can hardly expect me to understand why they must be round."

"The mass-kinetic propulsion principle is understandable to you. In both the round tubes, matter is spun round at relative speed. The direction in each tube is opposite, one left and one right."

"Oh, I see-a sort of cyclotron?"

"Let us say a sort of synchrotron. The outlet principle of a rocket is known to you. Hot gases, or material, is forced out at the highest possible speed. A universal spaceship does in fact do the same thing. Matter is forced out at the speed of light, but not into space; *it comes into an antimass field,* where it simply disappears and falls back as immaterial energy in the cosmic carrier field. Look at this ring system from above and strike a line square at the flight direction through the center point. You then have two diametrically opposite points. At these points and where the material stream is in a backward direction, you set a cosmic laser working, which continually lets the fastest moving particles escape. You then have the same effect as a rocket which blasts material out at the speed of light through two nozzles. Through the circle form, the two lasers can be moved, so that the propulsive power can be used in any direction from the horizontal plane."

"I understand it so far, but you must need an awful lot of fuel in order to continually allow material to excape."

"That is the secret of the universal spaceship. No matter is lost in the propulsion process. The matter blasted backwards vanishes but stays as an overdose of immaterial energy of the cosmic carrier field in a complicated power field within the spaceship. Because of this, we can create new matter within a fraction of a second, which is again introduced and accelerated. The process repeats itself as an endless cycle. Through the disappearance of ....

(cont.under)


General arrangement of a flying saucer

text for craftdrawing: *Sectioned view of a "space discus". The discus form of the mother ship, which is approximately 250 m in diameter, is a compromise between a maximum surface area for cooling and a minimum frontal area with a maximum capacity. This is the universal solution for space travel at cosmic velocities. The power source, a "sun-wheel" (two opposed cyclotrons with an outer ring for the control of weightless energy) is unknown to US and demands the circular planform. The danger of collision with cosmic dust at relative speeds necessitates the smallest possible frontal area. The two smaller modular discs are in fact landing units, the mother-ship always remains in space. Electro-magnetic fields, high temperatures, and the ionization of the surrounding air, make it impossible for Us to see these craft in clear detail. A race that can finance such machines is by axiom peaceful, they need global Cooperation before it is possible.*

Key to the numbers on drawing:.

1. Armor plating

2. Main power unit

3. Tangential connectors between cyclotrons and collector ring

4. Main frames

5. Outer skin and cooling system

6. Pressure skin

7. Equipment area

8. Fuel tanks (water)

9. Crew area, food cultures, etc.

10. Landing unit (tanker) for wet planets

11. Water tanks in landing unit

12. Crew area in landing unit

13. Command tower (retractable)

14. Direction of constant acceleration (or deceleration)



(text for painting-image of Iargan city, page 102-103 in the book) *The dwelling units, great covered rings, over 900 feet in diameter by nearly 300 feet high, housed about 10,000 people per unit, and included all services and facilities of all kinds for that many individuals. They were arranged in rectangular formations of 36 ring-complexes per "city" giving a population density of about 6,000 per square kilometer. The strange vegetation has evolved to withstand the heavy gravity and the high winds that prevail here. With only a 10% land surface available on this planet high density living became a necessity and developed efficiently. The strange vegetation has evolved to withstand the heavy gravity and the high winds that prevail here. The fully automated robot rail transport system operated with frictionless efficiency, moving vehicles of many sizes and configurations at high speeds.*

There were individual cars for small groups, collective units like trains for mass movement, cargo units for commerce, and even a peculiar development something like a hotel tram. A group of people wanting to travel together would order a unit that was fitted out as a self-service hotel and simply go where the mood took them. The system was marvelously efficient and could move over one million persons per hour past any point using only the upper six-lane rail system between the house blocks. The rail system and equipment was designed with a useful life expectancy of 1,000 years, a kind of quality undreamed of on Earth.

(cont. From above).....the matter, the movement energy is lost, which is to say that it is changed into a reaction-free force, but the mass energy is retained."

"You've lost me. You can really create reaction-free forces in a closed circuit! How is that possible? I always thought that the law of action-reaction was correct."

"That law is indeed correct. And in order to overcome the law you must overcome natural laws, or, in other words, the cosmic carrier-field laws."

"Are you not afraid that with this information we could construct a sun wheel?"

"No. The cardinal point, the reversal of the matter-energy carrier-field transformations, defying the laws of nature, demands such a high standard of advanced atomic science *that you will no longer be able to reach it.* Energy surplus(overskudd) from the carrier field, which can create matter particles, is an extremely dangerous phenomenon. Such unimaginable concentration of energy can only be controlled in gravitational fields of which even the most elementary knowledge is absent here on Earth. Such a sun wheel radiates a force that *even over long distances can cause certain electron movements to cease and metal constructions to disintegrate.* You have no idea of the technique that goes into building universal spacecraft."

"Why do you call it a sun wheel? What has it got to do with the sun?"

"Suns, due to the rotation of their critical mass, are natural spacecraft which, under the influence of the particle bombardment of their neighbors, navigate space with free cosmic vector powers. Through these powers they maintain their distance from other stars and cause the turning moment and the expansion of galaxies. *The sun wheel, therefore, is a copy of the power of a sun.* A sun wheel can exert power only in the horizontal plane and one alone can, therefore, not navigate. It is necessary to place a smaller wheel beside the main central wheel, on both sides, that of the landing units, so that a torque can be created in order to steer the ship. When this ring system is covered by metal plating, the discus form appears naturally."

"Why do they have to be so streamlined, since space is surely empty?"

"We wish that were true! For spaceships that travel at relative speeds, space is not empty enough and not only streamlining but armor plating is also necessary. You have seen our ship and can see that armor is not a useless luxury. They have no windows; they are heavy, armored projectiles, whose strength comes from the discus form. (comment: other cosmic races for ex. Pleiadians from planet Erra (Semjase..) - seems to have developed a system with magnetic protection shields, which apperently serve the same purpose as here described. But it seems as **these** beeings - Iargans -dont travel interdim./through jumps in hyperspace, as the Erra-siv. describes. And because of that - their spacetravels seems to take very long time as will be said later in the text. In earlier times the pleiadians/our ancestors from the system of Lyra, also had these "first generation space travels", then the trips took very,very long time. - R:ø.remark)


Iargan space-discus ("sun Wheel")
250 m diam. with two laning units(discs)
over and under this mother-ship

"When our radar warns us of dust or material, we make the banking maneuver that you have just seen. This then presents the smallest possible surface area to the danger. Nevertheless, each particle of dust makes burn marks on the plating. For this reason we always fly in line formation. The command consists of five ships and the lead ship is always unmanned, because this one runs the greatest risk. The ships are connected by a cable, because at relative speeds radio contact is impossible. "Another advantage of the discus form is the great natural resistance to thermal variations and the large cooling surface. The ships are very hot under normal working conditions and the outer plating acts as a cooler for control of the energy processes on board. Lastly, the discus form is ideal for creating a strong magnetic field that protects the occupants from dangerous radiation in space. We hope your question is answered."

"Yes, fine, thank you- ,,but didn't you say something about a protective weapon which you could use if material threatened to cross the path of the spacecraft?"

"The antimatter ray, Stef, is a defense against larger blocks which only rarely occur in space. The use of this ray demands not only enormous quantities of energy, but it is controlled by strong restrictions to prevent disturbing the natural balance. We are only justified in its use when no other methods are possible. This weapon cannot replace the armor plating of our ships."

"I understand. What is life like on board in weightless conditions? It seems to me that it must not be very pleasant."

"In weightless conditions it would indeed not only not be pleasant, it would even be impossible. An intelligent being cannot live without gravity during the endless journey between the stars. We have solved this problem by the continual use of the sun wheel, which creates a constant acceleration or deceleration exactly like the conditions on our planet. We do not subject our people to abnormal gravity forces. The acceleration of our ships is always constant so that we can live on board exactly as in our homes. "The journey begins with a long period of acceleration until we have reached the maximum speed at which navigation is possible. Then we alternately slow down and speed up. The last part of the journey is a long period of deceleration. Gravity is always normal, because of the continual working of the great, central sun wheel. The small sun wheels are not used for normal propulsion." (Again: other cosmis races for ex. Pleiadians from planet Erra (Semjase..) - have developed a system which creates a artifical gravitition field, where all atoms (in people aboard) are affected of the same progressive forces as of the ship. R.ø.)

"What is 'above' and 'below' with you on board?"....... (cont. below)


Iargan space-exploration fleet
leaving the ringed home planet
IARGA.

(text for UFO-painting): *Painting of an Iargan exploration leaving the ringed home planet on an interstellar journey. An exploration command frequently consists of five thousand-foot-diameter universal spacecraft powered by "sun wheels." They fly in line-astern formation connected by an umbilical. One of the two twohundred-fifty-foot detachable landing modules may be seen in the center of each of the larger excursion vessels. Painting by Jim Nichols. (cont.from above)*

.......The screen again showed the view of the four ships in line formation joined by the cable. "You see here the formation of our command shortly after leaving our planet. The acceleration was in the direction off light and the ships flew to the left. The left ship is therefore above the right one, where the navigation dome is out, is below."

"So you are standing upright in the area that is horizontal in the picture. I see you then on your side."

"Exactly."

I stared into the navigation dome and suddenly I understood: "I see- This navigation dome is normally vertical, which explains

Dipper and North Star, channelling down the red and violet light into the thymus gland.

4. Continue to the throat, stroking down with your palms, using green color to move the lymph down towards the backside of the heart. **(Never stroke up towards the head. Only guide the lymph down).**



A. ***B.***

Fig. 6.10 A. *Channel the Violet Light of the North.*
B. *Use your Palms to bring the Lymph flow back to the Heart.*

5. Proceed to the lymph nodes under the armpits and across the sternum. Next activate the lymph nodes in the groin. From the groin you guide the lymph up to the navel center (Not down where it will get stuck in the legs).
6. Return to the navel center. Send the energy deep inside, energizing the lymph nodes at the back. Pull back, drawing green energy, flushing out any waste products that are stuck in them.

why all the instruments are on the floor. The metal grills are the floor levels for using the instruments and the track in the middle is for a lift to bring you to the different levels."

"We have no complaints about your powers of observation."

"Is the control of such a machine so complicated that all these instruments are necessary?"

"The control of the ship does not require all these instruments. They are for other purposes. To explain it we must begin at the beginning. "This landing unit is a part of the huge mother ship. It can release itself and operate independently in space and land on planets. In the normal situation, these landing units are an integral part of the mother ship. You must realize that the central wheel of a landing unit is one of the two steering wheels of the mother ship. We will show you a landing unit in action and then you will understand better."

The view changed. Right in front of me was a huge discus. I saw only the upper surface, pockmarked with burns and melted stone masses. Then, slowly, out of this monster, rose a tiny black pole that I recognized as the black pole approximately five feet in diameter. Then appeared the shining rim of the navigation dome. Immediately after, a small discus rose out of the middle of the spaceship as though it was forcefully pushed away. The thing accelerated and disappeared as a speck of light in the background of stars. It was an asymmetrical discus of much smaller dimensions. Its upper surface matched the curve of the mother ship perfectly, but the underside was more rounded and it had a conical rim. Also on the underside was a further thickening in the form of a flat dome. The mother ship was left with a deep bowl in the middle, in which the landing unit fitted.


IARGA
Space Excursion Vessel
Top
Dark dull gray color
Bottom
Non reflective finish
D=330
Iargan space-exploration mother-ship
Space convoy of 5 large ships fly line-astern
metallic skin in ered with strip plates
Estimated 1000' diame
Detachable modules 250' diameter top and bottom
Fuel in water
Large ships may be coupled in stack through detachable modules
Large ship lands only in water on home planet
Smaller unit lands on tripod legs
D=80 m
Coupling device on top and also on bottom of the detachable modules

Thousand foot diameter space excursion vessel.

"Is the landing unit's navigation dome as big as this?"

"Yes."

"Good heavens-then the unit must be at least two hundred and fifty feet in diameter."

"That is nearly correct."

"Inconceivable!"

"Exactly. The technical know-how that goes into the building of a universal spacecraft is beyond the conception of Earth men. This navigation dome is the nerve center of the spaceship. Imagine what is involved in navigation and communication, what is needed only in instruments, data records and calculating machines. Each navigation dome can carry out all the control functions of the, entire fleet, including climate control, food production, entertainment and the study program for the children. All in all, too much to mention, but we can assure you that the number of instruments is kept to an absolute minimum."

"Exactly. The technical know-how that goes into the building of a universal spacecraft is beyond the conception of Earth men. This navigation dome is the nerve center of the spaceship. Imagine what is involved in navigation and communication, what is needed only in' instruments, data records and calculating machines. Each navigation dome can carry out all the control functions of the entire fleet, including climate control, food production, entertainment and the study program for the children. All in all, too much to mention, but we can assure you that the number of instruments is kept to an absolute minimum."

"What did you say? Study programs for the children? Do you have children on board?"

"Yes, we are not just an expedition. We live on board with our wives and children, sometimes for twenty years or more. Space is our home. For people seeking contemplation as the greatest happiness, the warm intimate contact is a life experience and a mental enrichment that we would not miss for anything. You could compare us to your monks. We wish to live and die among the stars."

"Yes, you must be rather like monks if you lead your lives in a steel box."

"You have no idea of the comfort on board our ships, but we will leave it at that."

"How long can you keep the sun wheel constantly in motion?"

"long time, even up to twenty years; then we must refuel."

"So you must make sure that you are back on your own planet within that time?"

"No, our fuel is water. The oxygen is used for ourselves and the hydrogen is our source of energy. Many solar systems have a wet planet and this is usually the goal of our journey, so finding water is no problem. Our landing units are fitted out for the efforts to publish

transportation of water. This is how they are able to remain under water like your submarines."

"So you only take water on board?"

"That is so.

"Then what do you eat over all the years?"

"This is one of the main problems involved with the construction of universal spaceships. The technique is only half the problem. The other half is making a livable environment on board with a 100 percent recycling system. It is difficult to keep intelligent beings alive under space conditions.

"We can give you no more information about our spacecraft, this was more than enough and we have reached the end of our talk. If you wish to ask anything special, this is your last chance."

"You surely cannot leave without giving me instructions as to how I am to publish this conversation?"

"Do not expect us to give you instructions, you are free to do as you will, our work is done. The knowledge has been planted, and even if you should decide to do nothing, it has also been planted in the collective consciousness of man, of which you have the knowledge. Millions of the departed have listened with you, they know as well as you do."

"I don't understand; on the one hand you impress upon me the importance of this information to humanity at the end of time, and on the other hand you tell me that

I am free to publish or not; I can't make head or tail of this!"

"The first law of interplanetary contacts is that the free will of a cosmic race may never be infringed. Pure knowledge does not infringe the freedom unless we are dealing with a race that has not yet made its choice, as we are here.

"Let us begin with the first observation; knowledge does not infringe freedom. This means that we are permitted to plant knowledge, and nothing more than that. We may never exert any kind of pressure to make you do anything with this knowledge. This is why we tell you that the knowledge is planted in the collective consciousness of man, sooner or later it must come to the surface. You have no obligations at all, you are free.

"The second observation causes greater problems. Knowledge can influence the freedom of choice of an ignorant race, as we have already explained; and certainly when this knowledge is presented with authority, or by one means or the other, it can be made indisputable.

"This is why you must never try to prove our existence, and the proof of the existence of God may only be used when all other efforts to publish have failed."

"You can rest assured that I would hate myself if I did not publish this knowledge. I assume that you could still give me some advice when I am ready to publish?"

"When it is obvious that you have chosen of your own free will, we will be prepared to give you a few hints. The first thing you must do is to control the impact of your publication to prevent hysteria and fanaticism. You can only accomplish this by being mysterious about the source of your information. *We know that you have made photos of our navigation dome and you must destroy them*. The block of metal which we offered you at the beginning of our conversation cannot be given anymore. If, however, you do manage to find some proof of our existence, things will get out of hand and you will be destroyed by the hysteria of mankind. Write your book in clear sciencefiction style and bring in certain, so that it cannot be used as irrefutable logic. **You must leave people free to believe or not, as they choose.** If anyone should ask you if it really happened, you must deny it and say that it is pure imagination.

The people for whom the book is destined will say: 'I am not interested whether it really happened or not; for me, it is true. It has changed my insight and now I live consciously. I know the meaning behind life.'

"Honesty is dangerous for you and no measure in interplanetary contacts. Therefore, you must not publish all the information in one shot, but step by step and measure the results. *Never strive to be believed*. Your duty is only to publish this information and nothing more. Let the books lead their own lives and avoid publicity stunts. **They will then pass from hand to hand and reach the people for whom they are intended.** Insure that they are published in a sufficient number of languages and use the income from the book to this end. Make sure that it is *available at the end time* when people will begin to ask for it. *Never try to convince people of the truth in the book if they are not ripe for it, or if they are unable to understand it.* Never bring pressure to bear on your surroundings, for that will only create panic and hysteria. "Remain modest. Answer questions only from people who have for the most part understood the book and accepted it. Never say anything in conflict with the Christ insight such as it appears in the Bible. His authority is unassailable in the whole universe. He is the only way; the only truth and the life. "No one comes to the father except through him" (means: His way of living - foregiving everything you feel as injustice against you).

. "Our conversation is over. It is late and you must reach the harbor before dark. We are going to say our good-byes. Are you ready to leave?"

A feeling of despair began to come over me, mixed with a strange emotion. They were leaving; they were going to leave me alone! There were a great many more questions to ask, and who was going to help me when they were gone? I rose slowly and walked to the window so that I could see these eight space travelers once more at dose range.

"Yes, we must say good-bye. I shall miss you terribly. There is so much more to ask and to be explained, but what I shall miss most is your interest and affection for Us. The pleasant warmth that you call unselfishness. I will never be able to explain what this contact with you has done to me. It has in a short time made another man of me, with a wider horizon and a deeper insight. It has made me a man with purpose, and I have received a commission which must be carried out.

"I will accept the challenge. Greet the people on Iarga and the other planets for me, and thank them for their part in this journey of yours that has made all this possible. Tell them that this man envies them their world of perfection, where intelligent people can really be happy. Tell them that I understand, in spite of the questions that have not yet been answered. And now it is my difficult task to thank you all for-"

"Stop, Stef. You do not have to thank Us. Our satisfaction in the fact that you have accepted the challenge makes thanks unnecessary, but there is still one big problem. You know how we worry that you will try to prove our existence and this would mean that we had gone too far. *You can relieve us of a great burden by promising to destroy the film and reframing from any attempt to collect proof*."

I smiled, a little regretfully. "I have even understood and accepted the ethics of interplanetary contacts. I assure you on my word of honor that I will destroy the film and refrain from trying to collect any kind of proof"

The disinterested attitude of the eight suddenly changed. They got up and came to stand in a half circle around the window. For the first time, I saw some kind of emotional reaction on their faces.

"*You have taken a great weight off our minds.* We trust your honesty and you have therefore made it possible for US to allow you to leave unhindered with all your knowledge. Only now do we feel justified in doing this. Operation cosmic integration Earth is a success. A heavy burden has been lifted from Us.

"We rely on you to understand that it is our duty to convince ourselves that you have destroyed the film, and we ask you to do so before you step on board your ship, and dearly within sight of the black pole. Thereafter, we will let your ship loose, and leave. "Farewell, Stef, and we wish you the courage to trust. May the inspiration of the Spirit



A. ***B.***

Fig. 6.11 A. *Activate the Lymph Nodes in the Armpits and Groin.*
B. *Energize and flush the Lymph Nodes in the Navel.*

C. Cleansing the Internal Organs Technique

Healing Some Common Illnesses

This session can be used for any kind of ailment and carried out with any number of students. It can take place on a singular, paired, small group or large group basis. Numbers can range from one person, one hundred, one thousand, ten thousand, ad infinitum. It is more likely that a greater energetic current will be created in much larger groups. In the case of 'mass' healings, there will always be a 'guide' or 'conductor', to open the channel for the students to follow. In the case of solo practices you will of course be the guide. **The following instructions have been set out on a one-to-one basis**.

By connecting to heaven, earth and your student, you will maximise the wholistic healing potential to your physical and subtle bodies. We recommend you spend about twenty minutes on the general healing before moving on to the more localized practices of emptying and cleansing the body's centers, systems and organs, contained within this chapter. We recommend that you spend between five to fifteen minutes on all of these. **Always perform the Sacred or Chi Water practice before.**

of truth accompany you on your journey. Farewell."

Above my head the hatch opened. The eight creatures made a respectful bow with one hand held against their foreheads. I returned the greeting in the same manner. "Farewell, a thousand thanks."

A while later, Miriam and the children stood wide eyed to observe the sight of a man with a thoughtful expression who stood up to his knees in the water and opened a camera. He than pulled the film out and threw it in the water. He then waved in the direction of the black pole as a last greeting, and climbed on board. It was a beautiful, windless evening and we all stood on board waiting and wondering what was going to happen. For the last time we heard the zooming noise as the navigation dome retracted, but this time the intricately formed black pole remained extended. Shortly afterwards, a dull shock went through the ship, as the astronauts released US and the ship floated once again in its element. We started drifting with the tide and we could hear the anchor chain scraping over the surface of the spaceship until it reached the edge; then the anchor fell and the chain jerked tight.

As I began to wind up the chain, I heard the propulsion system of the spaceship start working and the black pole began moving through the water, seaward. I stood watching from the foredeck and was surprised when I noticed how slowly they were traveling; it could not have been more than six or seven knots. It suddenly came to me that perhaps they did not dare to go any faster with the huge discus in this water, which was full of sandbanks and shallows, and at the same time the idea occurred to me that I could perhaps follow them for a while and might even be able to see something of the takeoff. I ran aft and quickly started the motor and followed the broad form wake at full power, dispite the protests of Miriam, who could not see the glamour of this new adventure. In half an hour we had left the coast of the inlands of Walcheren and Schouwen behind Us and were on the open sea.

The sun had set in a beautiful red glow and the still dark water swelled slowly. It had been a strange voyage. The complete loneliness, the wide expanse of water, and, mostly, the presence of the strange machine put a pressure on all of US against which my stubbornness was no match. As soon as I lost sight of the wake left by the spaceship, I stopped the motor and left the ship to float on its own while we all had a cup of coffee. In this complete stillness we sat on deck, tense and listening. Just as I had decided to give up and return to harbor, we heard the jangling sound of the propulsion in the distance. I jumped up, put the binoculars before my eyes and began feverishly scanning the water. Miriam saw it first.

"There, Stef, a light!"

Through the binoculars I saw a huge disc that, with a swaying motion, rose out of the water. The light was caused by a sparkling halo that spread over the whole visible surface of the spaceship. Close to the water it was yellow-orange, further up yellow-green and on top blue, and thanks to this lighting effect, I was able to see the discus quite plainly despite the distance. Suddenly the noise and the intensity of the light increased. Some few seconds later the machine disappeared in a huge cloud of steam. Shortly thereafter, it appeared again above the cloud, a huge glowing discus that rose at a steep angle in the form of a spiral with our ship as its middle point. The sight was much more impressive than the films I had seen of space. Actually, there was very little of the discus to be seen; it was surrounded by an orange-red cloud that prevented a dear view. Around this cloud hung a huge misty halo which made the spaceship look bigger than it really was.The fiery light caused a cry of alarm to come from Miriam. She thought that something had gone wrong, but I was able to reassure her.

"It is quite normal. Things glow with heat when the propulsion is working."

We stood breathlessly looking at this unearthly, indescribably impressive show of power from these beings, who, as a final gesture, flew in a huge circle round our ship, then rapidly dwindled to a tiny point of red light that was soon lost in the darkness of the evening sky. Despite my triumphant feeling that I had succeeded in seeing the takeoff, I felt strangely lonely, the sort of feeling that comes after saying good-bye to a good and trusted friend. Miriam seemed to share something of my feelings, for she came and stood beside me and put her arm through mine. Before she could say anything, we again heard the screaming whine of the propulsion *and to our surprise another discus rose out of the water in the same place*. We witnessed the same display of sparks and the steam cloud, only this time it did not fly in a spiral, but went straight up like a rocket.

"Good heavens," whispered Miriam, "another one of those monsters. How many of them are there? Please, let's go. If another one goes off, I shall scream!"

I did not answer. I stood as if in a trance, staring at the point of light until it had disappeared into the night. For some minutes we stood still on the swaying deck, hoping or fearing that perhaps a third would take off, but nothing more happened. Suddenly Miriam gave a cry. "There, Stef, there they go!"

High in the dark sky, a speck of light had appeared. The first of the machines had broken free of the Earth's shadow and flew in the light of the sinking sun. Through the binoculars I saw a misty object that gave off an orange glow and was surrounded by a misty halo. This was followed shortly by the second one. Quite suddenly the halos vanished, and they were seemingly free of the atmosphere and proceeded as two cigar-shaped objects that were slowly swallowed up in the endlessness of space. Miriam lay her head on my shoulder.

"So, have you finished?" I sighed and put my arm around her.

"No, dear. They-" and I pointed to the place where they had vanished, "they are finished, but for Us it has just begun!"


The depature of the Iargan landing module ship - after Denaerdes 8 h - visit aboard.

PUBLISHER'S NOTE:

The exact date and time of this first contact event are in fact *known as well as other evidential support. There are other witnesses and there is material evidence supporting this story, but in keeping with the contactee's solemn promise never to try to PROVE the reality of the story or the actual existence of the Iargans, for very good reason, we have chosen not to reveal it. Wendelle C.Stevens*

- PART II ON PHILOSOFY link
- apendix: understanding time
- other cosmic races
- main contact-page or here
- another site for part2 of the IARGA book

youtube video on how NATO found com. signals seemingly coming from the IARGA team

POWERPOINT ON THE CASE (and here norwegian ppoint) | czech translation (mirror) Translation of Denaerde interview (or txt)part 1 on youtube | part2

This interview was broadcasted on 19 August 1969, so it took place on that date or (probably) some weeks or months before that.

more on the case "The ultimate Theory Of Everything according to Stefan Denaerde "

-

mainpage

New science page

The ultimate Theory Of Everything according to Stefan Denaerde

---

- (NEW): Denaerde interview + translations
- Why Denaerde?
- Stefan Denaerde, a new complete theory of physics
- Achievements of the theory
- Consequences of the theory (NEW)
- RELATED SITES
    - Theory-of-God, the official Denaerde site
- CONCLUSIONS
- Related links





This animation shows that the flux in the time axes is driven by the rotation of the central bar. This causes the alternating flux of time along a time axis. After 6 time steps the cycle is repeated again.

Note that the famous Barbury Castle formation has a circle with 6 steps in it.
This formation is also based on a tetrahedron...
One half of a time axis represents our universe. The midpoint of a time axis represents t=0, the endpoint t=infinity



Updated : 30-August-2010

Home:
HC+RS
www.hcrs.at

Kapitel:
Warnungen
Hochfrequenz
Magnetismus
Elektrotechnik
Physik
Esoterik
Allgemeines

Info:
Suche
Forum
Stichwörter
Seitenübersicht
Linksammlung
Frage&Antwort
Änderungen
Download

Autoren:
Wir über uns
H. Chmela
R.Smetana

Die Polschuhe der Rotoren sind aus massiven Weicheisen gefertigt, in deren Mitte sich zwei starke Neodym-Magnete befinden. Zur mechanischen Überbrücku



Anstelle der 12 Seitenrotoren im originalen Modell werden in diesem vereinfachten Modell Spulen verwendet. Über diese kann eine S
entspricht und so können Rückschlüsse auf die komplexen Phasenverschiebungen gezogen werden. Über die unterbrochenen Eisenteile an den Kanten werden
geschlossenen Magnetkreis gerecht zu werden. Wichtig ist allerdings dabei, die Windungzahl pro Schenkel gleich groß wie die der Gesamtspule zu machen, d

Im Aufbau wurden die Eisenblechpakete durch Distanzhülsen in den Langlöchern der Grundplatte fixiert. Die Spulen wurden mit jewe
Gewebeband isoliert. Die Zuleitungen zu den Spulen wurden auf eine zentrale Klemmleiste geführt, um später jede einzelne der 12 Spulen messen zu können.

Ist das Iarga Funktionsmodell erst einmal fertig zusammen gebaut, so sieht man wenig von seinem aufwendigen Innenleben. Der Gleic
variabler Drehzahl betreiben zu können.

Uhrzeit: 08:46:52 Themenwahl: Wählen Sie: ▼ Besuchszeit: 00:00:

The Lacerta Files

Reptoids of the Inner Earth.

It is important to remember that if there is no energy in your Tan Tien, then there will be no energy to work with. ‘Connecting the Tan Tien and the Universe’ means connect your center to the infinite source of the universe, the Tao. When you make the connection you access this power. Always hold on to your center; it is the only thing that is truly yours. Keep the fire warm and spiraling. When you are aware of your Chi, you can direct heavenly light straight into your energy body and then into the student’s.

General Principles

1. Push and pull the energy through the student’s body. Push and disperse the sick energy into the universe and out to the planets, where it will be transformed and recycled.
2. Pull the energy back and stop it between yourself and the student.
3. Spiral the energy counterclockwise until you see the **green** light mix and clean the sick energy. Spiral and flush the energy down into the earth.
4. Spiral with **blue** light; see it mix and flush the energy within the student’s body. Spiral this energy down to the ground.
5. Energize the student with **white** or **violet** light.
6. You can also use both hands to channel Chi when you ‘push and pull’ through the body.
7. Energy can be introduced to the affected area of the body by moving the hand clockwise in a spiral.
8. Move the hand anticlockwise with a spiraling motion to clean, flush and remove energy from the treatment area. After this, brush down the whole body, to direct the sick energy into the earth.
Use an anticlockwise spiraling movement in order to clean, then expel the energy.
Use a clockwise movement to bring energy in and an anticlockwise one to take it out.
9. When you begin pushing, pulling and sweeping, you may feel resistance in the body. As you progress and the energy centers open, this feeling will diminish.
10. There are many color combinations that can be applied to the various parts of the body. When you start practice, stick to the basic ‘blue, green, white, violet and blue’ formula. When you are working on a specific area, you can keep this book near by, or write a short ‘color recipe’ before you begin. In this way, you will be able to relax your mind.
11. ‘Pushing and pulling’ is like fanning and venting the body; when you fan your hands in front of your face, it will have a cooling effect. Ventilation enables the stagnant, sick energy to leave the body.
Below is a list of the body’s organs in relation to their tendency to ‘store heat’. They are listed in descending order, i.e, the head is the hottest:

Reptoids of the Inner Earth

The Lacerta Files

Jimmy Bergman, Owner, Sweden.

Published in this website on December 26, 2004.

Note of the Editor of Brother Veritus' Website: These English translations were edited to correct English grammatical errors but message and intent were left intact. The word "Ilojiim" or "Illojim" used extensively in these texts could mean "Elohim", since this is the equivalent traditional word used in Western culture, however, this term may indicate a different galactic race. The illustrations are not of Lacerta.

Lacerta File I

Translation by Chris Pfeiler, Editor and Translator. Taken from http://www.sabon.org/reptiloid/index3.html .

Introduction



I certify that the following text is the absolute truth and no work of fiction. These are parts of a transcript of an interview I've made with a non-human and reptilian being in December 1999. This female being was already in contact with a friend of mine (whose name is given only with the abbreviation E.F. in the text) since some months. Let me declare, that I was all my life a skeptic about UFOs, aliens and other weird things and I thought that E.F. tells me just dreams or fictitious stories when he talked with me about his First Contacts with the non-human being "Lacerta". I was still a skeptic when I met this being on December 16 last year in that small warm room in the remote house of my friend near to a town in the south of Sweden, despite the fact that I saw now with my own eyes that she was not human. She has told and shown me so many unbelievable things during that meeting that I can't deny the reality and the truth of her words any longer. This is not another of that wrong UFO papers which claim to tell the truth but tell in fact just fiction, I'm convinced that this transcript contains the only truth and therefore you should read it.

I had talked with her for over 3 hours, so the following transcript shows you only shortened parts of the interview, because she asked me after the interview not to publish everything she had told me already now. The order of the questions in this transcript is not always the same order in which I had asked them, so it may seem sometimes a little bit confusing to you. It was not easy to delete all the important parts she had asked me to delete from the transcript, so I apologize for the maybe unusual order.

I’m in the possession of the entire transcript of the interview (49 pages with some of my drawings of her body and her equipment) and also of some tapes on which I have the full interview, but I will not reveal this before I have permission from her.

I will send this shortened form of the still fascinating document to four of my reliable friends to Finland, Norway, Germany and France and I hope they will translate it into their own languages and into other languages and I hope as many people as possible will be able to read and to understand the transcript. If you receive it, please send it to all your friends via e-mail or make print-outs and copy them.

I certify furthermore, that various "paranormal" abilities of her species like telepathy and telekinesis (including the moving and dancing of my pencil on the table without touching and the flying of an apple around 40 centimeters over her hands) were shown to me during the 3 hours and 6 minutes of the meeting and I’m absolutely sure that these abilities were no tricks. The following is certainly difficult to understand and to believe for someone who hasn’t experienced it, but I was really in contact with her mind and I’m now completely sure that everything she said during the interview is the absolute truth about our world.

Unfortunately, if I read the entire transcript and (much more) this very shortened form by myself I have the strong impression, that everything I’ve written sounds too unbelievable to be true, that everything sounds more like a bad science fiction story from TV or cinema and I have doubts that anyone will believe my experiences. But they are true, if you believe it or not. I can’t expect from you that you believe my simple words without evidence, but I can’t give you that evidence. Please read the transcript and think about it and you will maybe see the truth in these words.

There will be a new meeting between me and her (again in the same house in Sweden) on April 23 2000 and she promised me to give me maybe some evidence for her existence. In the meantime I collect questions which I will ask her then. Maybe she gives me permission to reveal more of the missing parts in that transcript and about the coming war.

Believe it or not, this makes no real difference (but I hope you will believe.)

Ole K.

Transcript of Interview (Shortened Version)

December 16, 1999

Question: First of all, who are you and what are you? Are you an extraterrestrial species or can your origin be found on this planet?

Answer: As you could see with your own eyes, I’m not a human being like you and to be honest I’m no real mammal (despite my partly mammal-like body features, which are a result of evolution.) I’m a female reptile being, belonging to a very old reptilian race.

We are the native terrans and we live on that planet since millions of years. We are mentioned in your religious writings like your Christian Bible and many of the ancient human tribes were aware of our presence and worshipped us as gods, for example the Egyptians and the Inca and many other old tribes. Your Christian religion has misunderstood our role in your creation, so we are mentioned as "evil serpent" in your writings. This is wrong. Your race was genetically engineered by aliens and we were just the more or less passive visitors of this accelerated evolution process. You must know (some of your scientists have already supposed this) that your species had evolved in a naturally completely impossible speed within just 2 - 3 millions of years. This is absolutely impossible, because evolution is a much slower process if it's natural but you have not understood this. Your creation was artificial and done by genetic engineering, but not by us but by an alien species. If you ask me, if I'm an extraterrestrial, I must answer no. We are native terrans. We had and have some colonies in the solar system, but we originate on this planet. It's in fact our planet and not yours - it was never yours.

Question: Can you tell me your name?

Answer: This is difficult, because your human tongue is not able to pronounce it correctly (and a mispronunciation of our names is very offensive for some of my kind.) Our language is very different from yours, but my name is —I will try to say it smoother by use of your human letters— something like "Sssshiaassshakkkasskkhhhshhh" with a very, very strong pronunciation of the "sh" and "k" sounds. We have no forenames like you but only a single but unique name which is divided and characterized by the way of speaking and which is given not to children (who have an own children-name) but only in a special procedure in the adolescent age at the time of either religious or scientific "enlightenment" or awareness (as you would call it.) I would appreciate it if you don't try to say my real name with your human tongue. Please call me "Lacerta", this is the name I generally use when I'm among humans and talk with them.

Question: How old are you?

Answer: We measure the time not like you in astronomical years and in the revolving of the earth around sun, because we usually live beneath the surface of the planet. Our time measurement depends on periodically returning cycles in the earth magnetic field and according to this (and said with your numbers) I'm today —let me calculate— 57,653 cycles old. I have reached my adult phase and my awareness 16,337 cycles ago (this is a very important date for us.) According to your human time scale I'm around 28 years old.

Question: What is your task? Do you have a "job" like us?

Answer: To say it with your words: I'm a curios student of the social behavior of your species. That's why I'm here and talk to you, that's why I have revealed my real nature to E.F. and now to you and that's why I give you all that secret information and why I will try to answer all the questions on your many sheets of paper honestly. I will see how you react, how others of your kind react. There are so many crazies and liars of your kind on this planet who claim to know the truth about us, about UFOs, about aliens and so on and some of you believe their lies. I'm interested to see how your species will react if you make the truth (which I will tell you now) public. I'm quite sure everyone of you will refuse to believe my words, but I hope I'm wrong, because you need to understand if you want to survive the coming years.

Question: I’ve read your full statement (which you have given to E.F.) about this, but can you give me now just a short answer: are UFOs real flying objects piloted by extraterrestrials or do they belong to your species?

Answer: Some observed UFOs - as you call them - belong to us, but most not. Most of the "mysterious" flying objects in the sky are not technological devices but mainly misinterpretations of natural phenomena your scientists have not understood (like spontaneous plasma flares in the high atmosphere.) Nevertheless, some UFOs are real craft belonging either to your own species (especially to your military) or to other alien species or at last to us (but a minority of sighted craft belongs really to us, because we are generally very careful with our movements in the atmosphere and we have special ways to hide our ships.) If you read a report about a sighting of a metallic bright-gray cigar-shaped cylindrical object with a length of —there are different types— let me say between 20 and 260 of your meters and if this object had made a very deep humming sound and if there were 5 bright red lights on the metallic surface of the cigar (one at the top, one in the middle, two at the end) then it’s likely that someone of you have seen one of our ships and this means that it was either partly defect or that someone of us was not careful enough. We have also a very small fleet of disc-shaped craft, but such UFOs belong usually to an alien species. Triangular UFOs belong generally to your own military but they use foreign technology to build them. If you really want to try to see one of our craft, you should have a look at the skies over the Arctic, the Antarctic and over Inner Asia (especially over the mountains there.)

Question: Have you a special symbol or something like that with which we can identify your kind?

Answer: We have two major symbols representing our species. One (the more ancient) symbol is a blue serpent with four white wings on a black background (the colors have religious meanings for us.) This symbol was used from certain parts of my society, but it is today very seldom —you humans have copied it very often in your old writings. The other symbol is a mystic being you would call a "Dragon" in the shape of a circle with seven white stars in the middle. This symbol is much more common today. If you see one of that symbols on a cylindrical craft I’ve described in my previous answer or on some underground installation, this thing or place belongs definitely to us (and I would advise you to go away from there as soon as possible.)

Question: The seven stars in the second symbol you’ve mentioned, do they mean the Pleiades?

Answer: Pleiades? No. Actually, the seven stars are planets and moons and they are a symbol for our former seven colonies in the solar system. The stars are shown in front of a blue background and the dragon-circle means the shape of Earth. The seven white stars mean Moon, Mars, Venus and 4 moons of Jupiter and Saturn, we had colonized in the past. Two colonies are no longer in use and abandoned, so 5 stars would be more correct.

Question: As you have not allowed me to make photos —what would be very useful to prove your real existence and the truth of this story— can you describe yourself detailed?



Answer: I know that it would be helpful to prove the authenticity of this interview if you can make some photos from me. Otherwise, you humans are very skeptic (that’s good for us and for the real alien species acting secretly on this planet) so even if you had such photos, many of your kind would say that they are fraud, that I’m just a masked human woman or something like that (that would be very offensive for me.) You must understand that I can’t give you permission to make photos of me or of my equipment. This have various reasons, which I want not to discuss with you further, but one of the reasons is the keeping up of the secrecy of our existence, another reason is more religious. Nevertheless, you have permission to make drawings of my look and of my equipment I can show you later. I can also try to describe myself, but I doubt that others of your kind will be able to imagine my real look just from simple words, because the automatic denial of the existence of reptilian species and generally of intelligent species other than your own is part of the programming of your mind. Well, I will try.

Imagine the body of a normal human woman and you have at first a good imagination of my body. Like you, I have a head, two arms, two hands, two legs and two feet and the proportions of my body are like yours. As I’m female I have also two breasts (despite our reptile origin, we have started to give milk to our babies during the evolution process —this happened around 30 million years ago— because this is the best thing to keep the young alive. Evolution had done this for your species already in the dinosaur age and —a little bit later— also for ours. That means not that we are now real mammals) but the breasts of us are not as large as those of human woman and the size of them is generally equal for every female of my kind. The external reproduction organs are for both sexes smaller than those of humans, but they are visible and they have the same function as yours (another gift of evolution to our species.)

My skin is mainly of a green-beige colour - more pale green - and we have some patterns of brown irregular dots (each dot of the size of 1 - 2 centimeters) on our skin and in our face (the patterns are different for both sexes but females have more, especially in the lower body and in the face.) You can see them in my case as two lines over the eyebrows crossing my forehead, at my cheek and at my chin. My eyes are a little bit larger than human eyes (for this reason, we can see better in the darkness) and usually dominated from the large black pupils, which are surrounded from a small bright-green iris (males have a dark-green iris). The pupil is slit and can change its size from a small black line to a wide-open egg-shaped oval, because our retina is very light sensitive and the pupil must compare this. We have external round ears but they are smaller and not so curved as yours, but we can hear better because our ears are more sensitive for sonic (we can also hear a wider range of sonic). There’s a muscle or "lid" over the ears which can completely close them (for example under water). Our nose is more pointed and there is a V-shaped curving between the nostrils, which enabled the ancestors to "see" temperature. We have lost most of this ability, but we can still feel temperature much better with this "organ". Our lips are shaped like yours (those of females a little bit larger than those of males) but of a pale brown colour and our teeth are very white and strong and a little bit longer and sharper than your soft mammal teeth. We have no different hair colors like you (but there is a tradition to colour the hairs in different ages) and the original colour is —like mine— a greenish brown. Our hairs are thicker and stronger than yours and they grow very slow. In addition, the head is the only part of our body where we have hairs.



Our body, arms and legs are similar in shape and size to yours, but the color is different (green-beige, like the face) and there are scale-like structures on the upper legs (over the knee) and upper arms (over the elbow). Our five fingers are a little bit longer and thinner than human fingers and our skin on the palm is plain, so we have no lines like you but again a combination of a scale-like skin structure and of the brown dots (both sexes have the dots on the palm) and we have no fingerprints like you. If you touch my skin, you will feel that it is smoother than your hairy skin. There are small sharp horns on the upside of both middle fingers. The fingernails are grey and generally longer than yours. You see that my nails are not so long and round at the top. This is because I'm female. Males have sharp pointed nails with a length of sometimes 5 or 6 of your centimeters. The following feature is very different from your body and part of our reptilian origin: if you touch the backside of my upper body you will feel a hard bony line through my clothing. This is not my spine but a very difficult shaped external plate-structure of skin and tissue following exactly our spine from the head to the hip. There is an extremely high number of nerves and large blood vessels in this structure and in the plates (which are around two or three centimeters long and very touch sensitive - this is the reason why we have always problems to sit in chairs with a back like this chair.) The main task of these small plates (beside a role in our sexuality) is simply the regulation of our body temperature and if we sit in natural or artificial sunlight, these plates become more blood-filled and the vessels become wider and the sun is able to heat up our reptoid blood (which circulates through the body and through the plates) for many degrees and that gives us a great pleasure.

What else is different from your kind? Oh, we have no navel, because we were born in a different way to your mammal birth. The other exterior differences from your kind are minor and I think I must not mention all now, because most of them are not visible if we wear clothing. I hope the description of my body was detailed enough. I would advice you to make some drawings.

Question: What kind of clothing do you generally wear? I suppose this is not the way you dress normally?

Answer: No, I wear this human every-day-clothing only when I'm among humans. To be honest, it's not very comfortable for me to wear such tight things and it is always a very unusual feeling. If we are in our own home (this means in our subterranean home) or in our large artificial sun areas and if we are together with others near to our own name, we are usually naked. Is this shocking for you? When we are in the public and together with many others of my species we wear very wide and soft clothing made of thin, light stuff. I have told you that many parts of our bodies are very touch sensitive, mostly the small back plates so we can't feel comfortable in tight clothing because it can hurt us. Man and woman wear often the same kind of clothing, but the colors are different for the sexes.

Question: You've said "others near to your own name". Do you mean your family?

Answer: No, not really. You would call it "family" but with this word you mean only those of your kind which belong genetically together like father or mother and child. As I have said earlier we have a very difficult and unique name. Part of the pronunciation of that name is absolute unique and there is no other being with the same name, but part of this name (the middle part) is pronounced in a way that told the others to which "family" (I must use the word, because you haven't the right one in your vocabulary) you belong.

This means not that all in that group are genetically related to you, because these groups are usually very large and contain between 40 and 70 of us. This group includes generally your genetic relations - except one of them had decided to left this group - and your connection with father and mother is often the strongest. It would be too difficult for me to explain you now our very old social system which is very complex and we would need many hours only for the primary things. Maybe we can meet another time and I can give you detailed descriptions of all these things.

Question: Have you a tail like normal reptiles?

Answer: Do you see one? No, we have no visible tail. If you look at our skeleton, there is only a small rounded bone at the end of our spine behind the pelvis. This is a useless rudiment of the tail of our ancestors, but it is not visible from the outside. Oh, our embryos have tails during the first months of development, but these tails disappear before they were born. A tail makes only sense for a primitive species which tries to walk on two legs and must held the balance with the tail, but our skeleton had changed during evolution and our spine is nearly in the same shape as yours, so we need no tail to stay on two feet.

Question: You said that you were born in a different way to us. Do you lay eggs?

Answer: Yes, but not like your birds or primitive reptiles. Actually, the embryo grows in a protein liquid inside the mother's womb, but there is also an egg-shaped but very thin chalk hull around it, that fills the whole womb. The embryo inside this hull is completely autarky from the mother's body and it has every substance it needs to develop inside this chalk hull. There is also a cord like your navel cord which is connected to a point hidden behind the back plates. When the baby is going to be born, the whole egg is pressed through the vagina covered in a slimy protein substance and the baby came out of this soft egg after some minutes. These two horns on our middle fingers were instinctively used from babies to break through the chalk hull to take their first breath. Our young are not so large as your babies when they were born, they are between 30 and 35 of your centimeters tall, the egg is around 40 centimeters tall (this is because our vagina is smaller than a human one) but we grow to a normal size of 1,60 to 1,80 meters.

Question: What about your body temperature? You've said that you enjoy to lay in the sun. What effect has this to your organism?

Answer: We are no mammals and as reptiles our body temperature depends on the temperature of our surrounding. If you touch my hand you will maybe feel that it is colder than yours, because our normal body temperature is around 30 to 33 degree Celsius. If we sit in the sun (especially naked and with our row of small back plates in the sun) our body temperature can rise for 8 or 9 degrees within minutes. This rise causes a production of many enzymes and hormones in our body, our heart and brain and every organ becomes more active and we feel than very, very good. You humans only enjoy being in the sun but for us it is the greatest pleasure you can imagine (maybe like your sexual excitement.) We also enjoy swimming in very warm water or other liquids to rise our body temperature. If we are for some hours in the shadow, our temperature goes back to 30 to 33 degrees. This can cause no harm to us, but we feel much better in the sun. We have artificial sun-rooms in the underground but this is not the same for us like the real sun.

Question: What do you eat?

Answer: Generally various things like you: flesh, fruit, vegetables, special kinds of fungus (from subterranean farms) and other things. We can also eat and digest some substances which are poisonous for you. The main difference between you and us is that we must eat flesh, because our body needs the proteins. We can't live completely vegetarian like your kind because our digestion would stop working and we would die after some weeks or maybe months without flesh. Many of us eat raw flesh or other things which would be disgusting for you. Personally, I prefer cooked flesh and surface fruits like apples or oranges.

Question: Can you tell me something about the natural history and evolution of your species? How old is your species? Have you evolved from primitive reptiles as mankind has evolved from apes?

Answer: Oh, this is a very long and complex story and it sounds certainly unbelievable to you, but it's the truth. I will try to explain it in short. Around 65 million years ago, many of our unadvanced ancestors from the dinosaur race died in a great global cataclysm. The reason for this destruction was not a natural disaster - an asteroid impact as your scientists believe falsely - but a war between two enemy alien groups that took mainly place in the orbit and high atmosphere of your planet. According to our limited knowledge about the early days this global war was the first alien war on planet earth but it was definitely not the last (and a future war is coming soon, while a "cold war" - as you call it - between alien groups is ongoing since the last 73 years on your planet.) The opponents in this 65 million year old war were two advanced alien species, whose both names are again not pronounceable for your tongues. I'm able to say them but it would hurt your ear if I tell you the names in their original way. One race was humanoid like your species (but much older) and was from this universe, from a solar system in the star constellation you call "Procyon" today in your maps. The other species - about which we know not so much - was a reptilian species, but they have nothing to do with our own species, because we have evolved from local saurians without exterior influence (except the successful manipulation of our own genes by us. More about that later.) The advanced reptilian species came not from this universe but from a - well, how should I explain it to you. Your scientists have not really understood the true nature of the universe, because your illogical mind is not able to see the easiest things and relies on wrong mathematics and numbers. This is part of the genetic programming of your kind to which I will come later. Let me say, that you are nearly as far away from the understanding of the universe as you were 500 years ago.

To use a term you will maybe understand: the other species came not from this universe but from another "bubble" in the foam of the Omniverse. You would call it maybe another dimension, but this is not the right word to describe it correctly (by the way, the term dimension is generally wrong in the way you understand it.) The fact you should remember is, that advanced species are able to "walk" between bubbles by use of - as you would call it - quantum technology and sometimes in special ways only by use of their mind (my own species had also advanced mental abilities in comparison to your species, but we are not able to do the matter-string/bubble changing without technology, but other species active on this planet are able and this looks to you like magic as it had to your ancestors.)

Back to our own history: the first species (the humanoids) had reached Earth around 150 years before the reptilians and they built some colonies on the former continents.

There was a large colony on the continent you call "Antarctica" today and another one in the continent you call "Asia" today. These people lived together with animal-like saurians on the planet without problems. When the advanced reptilian species arrived in this system, the humanoid colonists from "Procyon" tried to communicate peacefully, but they were not successful and a global war started within months. You must understand that both species were interested in this young planet not for his biology and undeveloped species, but for only one reason: raw material, especially copper. To understand this reason, you must know that copper is a very important material for some advanced species (even today) because it is - together with some unstable materials - able to produce new stable elements if you induce a high electromagnetic field in the right angle with a high nuclear radiation field to produce an over-crossing of fluctuating fields. The fusion of copper with other elements in such a magnetic/radiation field-chamber can produce a force field of special nature that is very useful for various technological tasks (but the base for this is an extremely complex formula you are not able to discover because of the restrictions of your simple mind.) Both species wanted to have the copper of Planet Earth and for this reason they fought a not very long war in space and orbit. The humanoid species seemed to be successful during the first time, but in a last battle the reptilians decided to use a mighty experimental weapon - a special kind of fusion bomb which should destroy the life forms on the planet but should not harm the valuable raw materials and the copper. The bomb was fired from space and detonated at a point of your planet you call "Middle America" today. As it detonated in the ocean, it produced an unpredictable fusion with hydrogen and the effect was much stronger than the reptilians had expected. A deadly radiation, an over-production of fusion-oxygen, a fall-out of different elements and a "nuclear winter" for nearly 200 years were the result. Most of the humanoids were killed and the reptilians lost their interest on the planet after some years for (even for us) unknown reasons - maybe because of the radiation. Planet Earth was on its own again and the animals on the surface died. By the way, one result of the fusion bomb was the fall-out of different elements and materials created in the burning process and one of those materials was Iridium. Your human scientists today see the Iridium concentration in the ground as an evidence for an asteroid impact that killed the dinosaurs. That is not true, but how should you know that?

Well, most of the dinosaurs died (not all in the detonation but in the bad things which came after the war, especially in the nuclear winter and in the fall-out.) Nearly all dinosaurs and reptilians were dead within the next 20 years. Some of them —especially those in the oceans— were able to survive for the next 200 to 300 years even in this changed world, but these species also died, because the climate had changed. The nuclear winter ended after 200 years, but it was colder on earth than before. Despite the cataclysm, some species were able to survive: fish (like the sharks), birds, little creepy mammals (your ancestors), various reptiles like crocodiles... and there was a special kind of small but advanced dinosaurs which had developed together with the last large animal-reptilians like the species you call Tyrannosaurus.

This new reptile was walking on two legs and looked at little bit like your reconstruction of an Iguanodon (it originated in this family) but it was smaller (around 1.50 meters tall) with some humanoid features, a changed bone structure, a larger skull and brain, a hand with a thumb which was able to grab things, a different organism and digestion, advanced eyes in the middle of the head like your eyes and most important...with a new and better brain structure. This was our direct ancestor. There are theories that the radiation from the bomb took part in the mutations of the organism of this new breed, but this is not proven.

Nevertheless, this little humanoid-like dinosaur evolved during the following 30 million years (as I have said earlier, a species need generally more time to evolve than you think, if the evolution is not artificially induced like in your case) from an animal to a more or less thinking being. These beings were intelligent enough not to die in the next millions of years, because they learned to change their behavior, they lived in caves instead in the cold nature and they learned to use stones and branches as first tools and the use of fire as help to warm them - especially to warm their blood which is very important for our kind to survive. During the next 20 million years this species was divided by nature into 27 sub-species (unfortunately, former reptilian species were prone to divide themselves in a more or less illogical way into sub-species during the evolution process. You can clearly see this in the unnecessary high number of animal-dinosaur species in earlier times) and there were many (mainly primitive) wars between this sub-species for dominance.

Well, nature was not very friendly to us and as far a we know from the 27 sub-species 24 were extinct in primitive wars and in evolution, because their organism and mind was not developed enough to survive and (as main reason) they were not able to change their blood temperature in the right way if the climate changed. 50 million years after the war and after the end of Dinosaurs, only three (now also technological) advanced reptilian species were remaining on this planet together with all the other lower animals. Through natural and artificial crossbreeding these three species were united to one reptilian species and through the invention of genetic manipulations, we were able to "eliminate" the dividing-prone genes in our genetic structure. According to our history and belief, this was the time when our final reptilian race - as you see me today - was created by use of genetic engineering. This was around 10 million years ago and our evolution nearly stopped at this point (well, actually there were some minor changes in our look toward a more humanoid and mammal-like appearance during the coming ages, but we have not divided again into sub-species). You see, we are a very old race in comparison to your kind, which was jumping around as small monkey-like animals in the trees at this time while we invented technology, colonized other planets of this system, built large cities on this planet (which disappeared without a trace in the ages) and engineered our own genes while your genes where still those of animals.

10 million years ago the small simians started to grow and they came down from the trees to the ground (again because of the change of the climate - especially on the so-called African continent.) But they evolved very slow as it is normal for a mammal and if nothing extraordinary had happened to your kind, we wouldn’t be able to sit here and talk because I would sit in my comfortable modern house and you would sit in your cave clothed with fur and trying to discover the secrets of fire - or you would maybe sit in one of our zoos. But the things had developed differently and you believe now you are the "crown of creation" and you can sit in the modern house and we must hide and live beneath the earth and in remote areas. Around 1,5 million years ago, another alien species arrived at Earth (it was surprisingly the first species since over 60 million years. This would be more surprising for you if you would know how many different species are today here.) The interest of this humanoid species - you call them "Illojim" today - was not the raw material and the copper, it were to our astonishment the unadvanced ape-humanoids. Despite of our presence on this planet, the aliens decided to "help" the apes to evolve a little bit faster, to serve them in the future as some kind of slave-race in coming wars. The fate of your species was not really important for us, but we didn’t like the presence of the "Illojim" on our planet and they didn’t liked our presence on their new "galactic zoo" planet and so your sixth and seventh creation was the reason for a war between us and them.

Head, heart, liver, lung, stomach and spleen, large intestine and small intestine, kidneys and sexual organs (which become hot when aroused).

Outline of Practice

Occupying a position amongst most of the internal organs, the solar plexus acts as a kind of clearing center for energy generated by the emotions. It also lies in between the lower and higher energy centers.

1. Scan; ask for the power to look at the cells.
2. Push, pull and give the command, “Disperse”. Push until you feel the solar plexus clear and open.
3. Spiral green Chi counterclockwise. Talk to the sick energy; tell it to “leave”, you will take it to “a better place, where it will be happy”. Give the command, “Out”.
4. Spiral Blue Chi counterclockwise, flushing out any remaining sickness. Guide the sick energy into the earth.
5. Spiral and sweep Blue-Green and Red Chi into the solar plexus, sweeping the organs. If the patient is expecting a baby, has an infection or bleeding in the intestinal area; do not use this method.



Fig. 6.12
Spiral Green Chi counterclockwise in the Navel.



Fig. 6.13 *Charge your Hands with Chi - project the Hand Bones into the Universe and feel them fill and pack with Chi.*

You can read about that war for example partly in the book you call "Bible" in a very strange way of description. The real truth is a very long and difficult story. Should I continue?

Question: No, not now. I've made some notes about your history and now I have some questions.

Answer: Please ask.

Question: First of all, you handle with a very large time scale. You claim that your primitive ancestors lived together with the dinosaurs, survived the - as you called it - artificial cataclysm and evolved then over 40 million years and your evolution was completed 10 million years ago. This sounds very unbelievable to me. Can you say something to this?

Answer: I understand that this must sound absolutely unbelievable to you, because you are a young and genetically engineered species. Your historical horizon ends at a scale of just some thousands of years and you think this is right. But it isn't. This is impossible. Your programmed mind is obviously not able to handle with such large time scales. Our evolution time may seem incredible long to you, but this is in fact the original way of nature. Remember, your early mammal ancestors developed together with dinosaurs and they survived the bomb like us. They evolved slowly during the next millions of years and they divided into various species and shapes, some of them larger, some of them smaller. This is evolution of the body. But what about their mind and intelligence? They were simple animals. The mammals evolved since —let us say— 150 millions of years, but only in the last 2 - 3 millions of years they were able to became intelligent and thinking. And within this small period beings like you were created. From nature? 148 millions of year's time for the evolution of animal-like mammals, 2 millions of year's time for the development of (more or less) intelligent beings like you? Ask yourself: Do you really think this accelerated evolution is natural? Then your species is more ignorant than I've thought. We have not evolved wrong but you.

Question: I understand. But I have another question. You've mentioned many facts about the ancient war between the aliens 65 million years ago. This happened very long before your kind became really intelligent (as far as I have understood you). Why do you know so many things about that "first war" and about the evolution of your species?

Answer: This is a good question (much better than the previous) and I have not explained it properly to you. Our knowledge about the first war comes completely from an ancient artifact, which was found around 16,000 years ago from our archeologists on the continent you call North America today. They found there a round plate with a diameter of approximately 47 of your centimeters. The plate was made of an even for us unknown magnetic material and inside the plate there was another smaller crystal plate which contained an enormous amount of information coded in the molecular structure of the crystal. This "memory plate" was manufactured from the last bomb survivors of human race from "Procyon" already 65 million years ago but it was completely intact when we found it. Our scientists were able to encode the messages and data and so we heard the first time about the events which took place in the distant past and which led to the extinction of the dinosaurs. The plate contained detailed descriptions of both species (but more about the humanoids) and about the events and weapons, including the fusion bomb. It contained also a description of the animals and saurians on earth, including our pre-intelligent ancestor species. The rest of our knowledge about our evolution comes from skeletons and from the back-reading and de/encoding of our DNA.

You see, we know the real truth about our roots since 16,000 years. Before that time, there was a more religious idea of our creation.

Question: What have happened with the both alien species?

Answer: We don’t know exactly. The surviving humanoids on earth obviously died in the years after the bomb and others of their kind and the reptilians never came back to Earth (as far as we know). Concerning the reptilian aliens, there is a possibility that it was physically impossible for them to return, because the matter between bubbles is sometimes in rapid movement. The current theory is, that both species had ceased to exist during the millions of years.

Question: You’ve mentioned skeletons of your kind. How can it be, that human scientists haven’t found any trace of you and your ancestors if you really live for such a long time on this planet? We have found many skeletons of primitive dinosaurs, but none of an advanced reptilian being with a larger skull and brain and a hand with a thumb as you have described it before.

Answer: Yes, you have. But your "great" scientists were not able to reconstruct the skeletons completely, because they wanted to reconstruct reptilian animals, not intelligent beings. You would laugh if you would know how many of the (especially small) saurian skeletons in your museums are totally wrong constructions of never-existing beings, because you used many bones which didn’t really belong together and sometimes you made artificial bones if something was missing you needed to construct an "animal" saurian. Many of your scientists are aware of this problem, but they don’t make it public, because they can’t explain it and they claim, that the right bones were just missing and their reconstruction is right. Many bones of us were used for Iguanodon reconstructions, for example the hands with the visible thumb (look at an Iguanodon in a museum and you will see that I’m right.) A scientist in the country you call United States had built a nearly correct skeleton of our kind some years ago, but the local government (which is partly aware of our existence) confiscated the reconstruction. As we live today (and since thousands of years) nearly completely beneath the earth, you will not find any cadavers or skeletons of us.

Question: You speak sometimes about underground cities and artificial sunlight. Do you mean something like a "hollow Earth" with this? Is there a second sun inside our planet?

Answer: No, Earth is not really completely hollow and there is no second sun inside. This story is ridiculous and physically not possible (even your species should be intelligent enough not to believe this.) Do you know how much mass a sun must have to produce energy and light for a longer time by fusion? Do you really think that there could be a small active sun inside the planet? When I talk about our subterranean home, I talk about large cave systems. The caves you have discovered near to the surface are tiny in comparison to real caves and huge caverns deeper in the earth (in a depth of 2,000 to 8,000 of your meters, but connected with many hidden tunnels to the surface or to surface-near caves) and we live in large and advanced cities and colonies inside such caves. Major sites of us are beyond the Arctic, the Antarctic, Inner Asia, North America and Australia. If I talk about artificial sunlight in our cities I don’t mean a real sun but various technological sources of light (including gravitational sources) which illuminates the caverns and tunnels. There are special cave areas and tunnels with a strong UV light in every city and we use that places to heat our blood. Furthermore, we have also some surface sun places in remote areas, especially in America and Australia.

Question: Where can we find such a surface-near entry to your world?

Answer: Do you really think I will tell you their exact location? If you want to find such an entry, you have to search it by yourself (but I would advise you not to do that.) When I came to the surface four days ago, I used an entry approximately 300 of your kilometers north from here near to a large lake, but I doubt that you would be able to find it (there are only a few entries in this part of the world - more are far more north and east.) As a little advice: if you are in a narrow cave or in a tunnel or even in something that looks to you like an artificial mine shaft and as deeper you walk as smoother appear the walls and if you feel unusual warm air streaming from the depth or if you hear the rushing sound of streaming air in a ventilation or elevator shaft, then look for a special kind of artificial and smooth wall somewhere in the cave with a door made of gray metal. If you would be able to open that door (but I doubt this) you would be in a usually round technical room with ventilation systems and elevators to the depth. This is probably an entry to our world. If you have reached this point, you should know that we are now definitely aware of your presence. You are already in big trouble if you have entered the round room, but you should look for one of the two reptilian symbols on the walls. If there are no symbols or other symbols, you are maybe in bigger trouble as you think, because not every underground installation belongs to our kind. Some new tunnel systems are operated from alien races (including hostile races). My general advice if you find yourself in a, for you, strange underground installation: run away as fast as you can.

Question: You mentioned earlier that you use the name "Lacerta" when you are among humans and that you enjoy it to be in the real sun on the surface of earth. But how can you be among humans? You don’t look like us, so anyone will see that you belong to another species. Why have nobody seen and described a being like you if your kind lives already since our "creation" together with us on the same planet. Can you explain that to me?

Answer: First, my kind was of course seen and described (and worshipped) many times in your primitive past, for example in your religious writings like your Christian Bible. You can find descriptions and even simple drawings of us for also in the southern part of the American continent on various temples. So-called "wise" men from India and from the Asian mountains have described our species many times in writings, together with other "wise" men from the African continent. I think we are the most mentioned non-human species (maybe beside the "Illojim") in your history. If you don’t believe me, have a look at your history and you will see the truth in my words. Your "great" scientists called the belief in us "superstition" and "religion" and today’s "intelligent" humans have forgotten our presence on the surface in the past.

Furthermore, our species is seen even today sometimes from human witnesses in its original shape on earth or in our surface-near entries and tunnel systems, but fortunately you and your media didn’t take the reports of such "crazies" serious (that’s good for us and that’s the reason why we allow those people to see us as we really are.) Some of my species are also in direct contact with human scientists and politicians from the surface, but this is top-secret —as you would call it— and nobody of your public knows anything about it (the matter of these meetings is generally the upcoming war with and between the alien species and our assistance in this war). But there is also another explanation, why we can walk among you and why you are not able to recognize us: mimicry.

The following may again sound unbelievable and even shocking to you, but as you have asked I will explain it. I have told you before, that we have more advanced mental abilities than your species and with "more advanced" I mean, that we are able to use telepathy and telekinesis from our birth on (in fact, mother and new-born child communicate generally with telepathy during the first months) without special training as you need it to activate these sleeping parts of your brain. The structure of our brain is a little bit different to yours and our hypothesis is larger and more active than yours - especially when we are in sunlight. Our own abilities are very strong in comparison to yours, but weak in comparison to the "matter-string/bubble" mind forces of some of the alien species on this planet. I was never very good in that mind things, but we all have these primary abilities and can use them for example for our protection or even for attack.

When we are on the surface and we meet human beings (even a large group of them - this makes no difference. All of your minds are like one mind) we are able to "touch" their mind and induce them via telepathy the command "See us as one of your kind" and the weak human mind will accept this order without re-fusion and they will see us (despite our reptilian look) as normal humans. I've done this many times and you weak humans generally see me as an attractive brown-haired woman, because I have created this special "mimicry image" in my mind years ago and I can induce it into your minds without problems. I've needed some time at the beginning to learn the use of the mimicry correctly, but then it worked nearly automatically and I can even walk among a group of yours and nobody will recognize what I am. There is a simple switch ("See us as we really are / See us as we want you to see us") in your consciousness which was placed there from the "Illojim" when they created your kind and we can use this switch to convince you that you see humans when you look at us (other aliens use this switch, too). It is easier as you think. When there are meetings between your kind and aliens which seem to look exactly like yours, these aliens have used that switch and some of the meetings with man-like aliens can be also explained with meetings with my kind.) When I met E.F. the first time, he saw me also as a normal human woman and I remember that he was very frightened and shocked when I revealed him my real appearance.

Question: Do you mean, that you can really make me belief that I talk now with an attractive brown-haired human woman instead of a reptilian being like you?

Answer: Probably, but I don't think so in your special case. When someone expects to see a human woman instead of me, I can do it without problems with his mind (even with large groups) because nobody expects to see a reptile woman. But I have allowed your mind to see me in my original appearance from our first meeting on and I have never induced something into your mind, so you have already realized that I'm not human. If I would now try to change this, it would probably lead to an absolute confusion or to unconsciousness and I don't want to harm you. As I have said I'm not very good in these things.

Question: That's very scary. Can you kill with those abilities?

Answer: Yes, but it's forbidden. This means not that it was not done in previous times.

Question: Have both sexes these abilities?

Answer: Yes.

Question: What about photos? How do you appear on photos?

Answer: This is a silly question. I appear on photos as a reptile being, because I can’t have influence on the photo or on the camera itself but only on the photographers mind. If he or she would develop the film and show the photo to others, they would see me in my original shape. That’s the reason why it is forbidden for our kind to be filmed or photographed and we must avoid every camera on the surface (that is very difficult and we were filmed sometimes in the past without our knowledge, especially from certain of your governments and secret agencies.)

Question: What other commands can your kind induce into our minds? Something like "Serve us" or "Obey"?

Answer: This is again a strange question. We are not your enemy (most of us not) so why should we do this? To answer your question: it depends on the strength of the human mind and on the strength of the sending reptilian. There is no "Serve us" or "Serve me" switch in your mind, so such a command is much more difficult to induce. If the human mind and consciousness is weak and the reptilian inducer is experienced in these things and was some hours in the sun before he or she tries to do it, then it could probably work for a certain time. There are secret teachings about such things, but I’ve never learned anything about it. I use my primary abilities for mimicry and for communication with my own kind and sometimes for other private things, but I’ve never used it to harm humans or their mind. I would appreciate it if we can end with this topic here.

Question: A last question: you’ve said earlier, that you can hide your UFOs? Do you use the same abilities to do this?

Answer: Yes, but on a technical base. There is a powerful device inside each craft which is able to send an artificial signal to your minds to convince you, that you see either nothing but only the sky or that you see normal aircraft like planes instead of our ships. This isn’t used very often, because we avoid human public when we move in the atmosphere. If you are able to see our "UFOs" it means that the device is either defect or deactivated for some reason. The camouflage effect didn’t work on photos - to answer this possible question of you already in advance - but why should someone make a photo of the sky when he could not see anything unusual there. By the way, most of the surface-near entry points to our tunnels are also hidden with such a device and your kind will generally see only normal cave walls instead of the door. That’s one reason why I’ve said that I doubt that you will be able to find such a secret door to our world (but it have happened a few times in the past.)

Question: Back to your and our own history. You’ve mentioned the race of the "Illojim" who have created our human race. From where did they come and how did they look like? What had exactly happened when they arrived? Are they our "God"?

Answer: The "Illojim" came from this universe, from the solar system you call "Aldebaran" in your maps. They were a very tall humanoid species whit usually blonde hairs and a very white skin (they avoided the sunlight, because it hurt their skin and their eyes. This was absolutely unbelievable for a sun-loving species like us).

They seemed to be intelligent and peaceful at the beginning and we started a more or less friendly communication with them, but later they showed their real intentions and plans: they wanted to evolve the apes to a new breed and we were a disturbing factor for them on their new zoo planet. At first, they caught around 10,000 or maybe even 20,000 of your simian ancestors and they left the planet for some hundred years. When they returned, they brought your (now more human) ancestors back. Then they left Earth again for some thousands of years and the primitive pre-humans lived together with us without major problems (they were just afraid of our aircraft and technology). The "Illojim" had taught their mind and enhanced their brain and their body structure and they were now able to use tools and fire. The "Illojim" returned within 23,000 years seven times and accelerated the evolution speed of certain of your kind. You must understand that you are not the first human civilization on the planet. The first advanced humans (who lived at the same time with less-developed pre-humans, because the "Illojim" had experimented with different speeds and stages of evolution) with technology and speech existed around 700,000 years ago on this planet (your scientists have not understand this, because they've found only the bones of the pre-humans and some primitive cave drawings showing advanced humans and flying devices.) This genetically advanced human breed lived together with us, but they avoided contact with my kind, because the "Illojim" teachers had warned them with misleading purpose that we are evil beings and that we lie to them.

Well, after some centuries the aliens decided to extinct their first creation and they accelerated the evolution of a second and better test series and so on and so on. The truth is that your modern human civilization is not the first on this planet Earth but already the seventh. The buildings of the first breeds are lost, but the fifth civilization was the one, which built the large triangular constructions you call "Egyptian Pyramids" today around 75,000 years ago (your Egyptians just found that large ancient pyramids in the sand and tried not very successful to built similar constructions) and the sixth civilization was the one, which built the cities which ruins you can find today beneath the sea in the so-called Bimini Area around 16,000 years ago. The last creation of the seventh breed - of your series - was done just 8,500 years ago and this is the only creation you can remember and to which your religious writings refer. You rely on archeological and paleonthological artifacts which show you a wrong and short past, but how should you know anything about the six civilizations before. And if you find evidence for their existence, you deny and misinterpret the facts. This is partly a programming of your mind and partly pure ignorance. I will tell you in the following only about your creations, because the six previous mankinds are lost and therefore they should not concern you.

There was a long war between us and the "Illojim" and also between certain groups of the "Illojim" themselves, because many of them were the opinion that the again-and-again creation of human species on this planet makes no real sense. The last battles in this war were fought around 5,000 years ago in orbit and surface. The aliens used powerful sonic weapons to destroy our underground cities but on the other hand we were able to destroy many of their surface installations and bases in space.

The humans of your series were very frightened when they observed our battles and they wrote it down in form of religious myths (their mind was not able to understand what was really going on.) The "Illojim" - who appeared as "gods" for the sixth and seventh breed - told them that it is a war between good and evil and that they are the good and we are the evil race. This depends certainly on the point of view. It was our planet before they arrived and before they started their evolution project with your kind. In my opinion, it was our right to fight for our planet. It was exactly 4,943 years ago - according to your time scale - that the Illojim left the planet again for unknown reasons (this is a very important date for us, because many of our historians called it a victory.) Fact is that we don't know what had really happened. The "Illojim" were gone from one day to another, they vanished without a trace together with their ships and we found most of their surface installations destroyed by them. The humans were on their own and your civilization developed. Many of us were in contact with certain (more southern) tribes of your species in the coming centuries and we were able to convince some of them that we are not the "Evil" the aliens wanted them to believe. During the time from 4,900 years ago to today, many other alien species arrived the planet (some of them used the old teaching and programming of your mind and "played" again God for you) but the "Illojim" themselves never came back. They had left the planet for a duration of some thousand years also earlier, so we expect their return one day in future to end their project or to maybe extinct also the seventh breed, but we don't really know what have happened to them (to answer this question of you in advance).

Your current civilization doesn't know anything about your real origin, about your real past, about your real world and universe and you know very little about us and our past. And you know nothing about the things to come in near future. As long as you will not understand and believe my words - I tell you the truth because we are not your enemy - as long there is danger for your species. Your enemies are already here and you have not understood. Open your eyes or you will be in big trouble soon. If you haven't believed anything of the things I've told you before, then you should really believe and remember this.

Question: Why do you think I don't believe you?

Answer: I have a certain feeling that you don't believe me, despite the fact that I'm sitting here in front of you. Everything I have told you in the last two hours is the absolute truth about our world.

Question: How many alien species are active on earth at the moment?

Answer: As far as we know 14 species. 11 from this universe, 2 from another "bubble" and 1 very advanced from a very different plain. Don't ask me for names, because nearly all are not pronounceable for you, eight of them are not pronounceable even for us. Most of the species - especially the more advanced - are just studying you as animals and they are not very dangerous for you and for us and we work together with some of them, but three species are hostile, including the one which was in contact with some of your governments and exchanged their technology for copper and other important things and which had betrayed your kind. There was and is a "cold war" between two of these hostile races during the last 73 years and the third species seemed to be the "winner" in this useless struggle. We expect a more "hot" war between them and you in the near future (I would say in the next 10 or 20 years) and we are worried about that development. In the last time, there were some rumors about a new, fifteenth species which had arrived on Earth just 3 or 4 years ago, but we don't know anything about their intentions and we were not in contact with them till now. Maybe the rumors are wrong.

Question: What do the hostile alien races want?

Answer: Various raw materials, including copper for their technology, your water (or better the hydrogen in your water, which is a source of energy in advanced fusion processes) and certain chemical elements in your air. Furthermore, two of the species are also interested in your body, in your human tissue and blood, because their own genetic structure is defect through bad evolution and radiation (as far as we know) and they need intact strings from your kind and from animals to repair their own genetic again and again, but they are not really able to repair the defects completely because their DNA and your DNA is not fully compatible (my own species is absolutely incompatible with them, so they are not very interested in us) and they try to make more compatible crossbreeds between you and them by use of artificial fertilizations and artificial wombs. We suppose that the coming war between the three races or between you and one or all of them will be fought for raw material, hydrogen, air and DNA.

Question: Is this the reason for the "abductions"?

Answer: Partly, especially when the aliens took egg and sperm samples from you. Sometimes the abductors belong to another and more advanced race and they just want to study your body and your mind (which is more interesting for some of them than your solid body) as you would study a primitive animal. As I have said, three alien species are hostile and this means that they do not care for your fate or for your life and people who were "abducted" by them came very rarely back alive. If someone is able to report about an abduction, it means in my opinion that he or she has not met one of the aggressive species or that he or she is a very, very lucky human to be alive. Advanced and "friendly" races also took sometimes egg and sperm samples, but for other reasons.

Question: You’ve said there are only 14 species active on earth. But why describe people who saw alien beings so many different and bizarre types of them?

Answer: I think I have already answered to this question. As I have said, most of the alien races have much more advanced mind abilities than you or even me (there is just one alien race completely without such abilities). They are able to appear in your mind and memory as whatever they want and this induced "image" has nothing to do with their real appearance. You remember them as normal humans or grey dwarfs or even extremely bizarre animals because they want you to remember that or sometimes they want you to completely forget anything about a meeting with them. Another example: you can for example remember that you were just in a normal of your human hospitals and that some doctors were examining you and you think not further about what have happened to you (maybe till you discover that there is no hospital in the street were you supposed it) but in fact you were examined by them in one of their laboratories. You can’t rely on your mind in this case. They appear in different shapes to you to confuse you and to make so-called abduction witnesses who were able to remember the events - or who believe they are able to remember - ridiculous in the public and as far as we know, they are successful. Believe me, there are only 14 alien species on this planet and only eight of them abduct humans at the moment (again as far as we know.) In addition, not everyone of your "abductees" is one and some of the aliens in their reports are really just imagination or lies.

Question: How can we protect us against this influence on our mind?

Answer: I don’t know. I doubt you can, because your mind is like an open book to read and write for nearly every species I know. This is partly the guilty of the "Illojim" themselves, because they had constructed or better mis-constructed (partly intentionally) your mind and your consciousness without real protection mechanisms. If you are aware that someone tries to manipulate your mind, you can only concentrate on that suspicion and try to analyze every one of your thoughts and memories. Very important: don’t close your eyes (this would lead to a different form of brain waves which are more easy to access) and don’t sit or lay down to rest. If you stay awake during the first minutes, you can maybe try to filter the other thoughts and waves in your brain and the inducer will give up after some minutes if he or she is not successful because it will start to hurt his or her own brain. This is very difficult and certainly painful and it can harm you, so better don’t try to resist but it would be the only possibility you have. However, you can try this only with the more weaker species, not with the strong.

Question: What do you mean with "one species comes from a very different plain"?

Answer: Before I can explain that correctly to you, you must be able to understand the universe and this would mean a maybe useless teaching of your mind (including the remove of some barriers) of many weeks and with teaching I mean not only teaching by words. I have said this with your word "plain" or "level" because you have again no better word in your vocabulary and dimension would be in this case absolutely wrong (it’s rather wrong even for another "bubble") because a dimension can’t exist without plains. If you would be a species living in another or over the plain and if you would be furthermore able to enter plains without technology so that your body is not made of that kind of matter you know, then you would be the mightiest being you can imagine. This very advanced race I’ve mentioned had developed outside of here and they’ve evolved in fact over billions of years. They would be able to destroy all of you and us and everything with just a single thought. We were in contact with them only 3 times in our whole history, because their interest in your planet is different from that of all other races. They are definitely no danger for you or us.

Question: What will happen when the war begins?

Answer: This is difficult to answer. It depends on the enemy race and on their tactic. "War" is not always that primitive thing you humans mean with the word, "War" can be fought on various levels. One possibility they have is the "destruction" of your social system by influence on political leaders, another is the use of advanced weapon systems which can cause earthquakes or volcanic eruptions or other disasters (including weather disasters) which may seem natural to you. The special fields from copper-fusion I’ve mentioned earlier are able to have an influence on your global weather. I think they will not attack the planet directly before the human civilization is weak, because even you have possibilities to destroy their craft (but not many.) Let me say, that we are not absolutely sure if there will be really such a "hot" war already in the next years. I don’t want to talk further about this.

Question: This is the end of the interview. Do you want to say a last sentence or message?

Answer: Open your eyes and see. Don’t believe only in your wrong history or your scientists or your politicians. Some of them know the truth about various things, but they don’t inform the public to avoid confusion and panic.

I think your species is not as bad as some of my kind thinks and it would be a pity to observe your end. That’s everything I can say. Go through your world with open eyes and you will see - or maybe not. Your kind is ignorant.

Question: Do you think anyone will believe that this interview is the truth?

Answer: No, but it is an interesting experiment for my social studies. We will meet again in some months and you will tell me then what have happened after the publication of my message. Maybe there is hope for your kind.

All Rights Reserved ©

The Lacerta File II

Translation by Doug Parrish. Taken from http://www.sabon.org/reptiloid/index4.html .

Introduction

I once again reaffirm that the following text is the absolute truth and is not fiction. It was composed from three original tape recordings which were made on April 24, 2000 with a tape recorder during my second interview with the reptilian creature known as "Lacerta". At Lacerta's request, the original text of 31 pages was revised and shortened up to deal with some questions and answers. Some existing questions were partially shortened or amended. It was even undertaken to extract message and significance from it. This part of the interview, either not mentioned or not mentioned completely in the transcript, deals primarily with personal issues, paranormal demonstrations, the social system of the reptilian species and alien technology and physics.

The reason for the shifting of the date and time of the second meeting was a possible observation and surveillance of my own person after the publication of the first transcript. Although everything was attempted on the advice of Lacerta to keep my identity a secret, just two days after the dissemination of the document abroad, and various unusual events took place. Please don't think that I am paranoid; however, I believe that the publication of the interview has drawn either official attention or the attention of some organization to me. Up until this time, I usually regarded people who believed that they were being followed by the state to be nothing more than jokers. But now I have begun to revise my ideas on that since events in January. It began with a failure of my telephone for several hours. When the phone became operational once again, there were quiet echoes and strange clicking and whirring sounds when I made calls. A defect could (ostensibly) not be found anywhere. Overnight, important data disappeared from the hard drive in my computer. The testing program reported "defective sectors" where strangely enough there were only data which dealt with illustrations and completed textual material from the interview. These "defective sectors" also contained material of a paranormal nature in the field of my research. (Fortunately, the material was also stored on floppies.) In addition I discovered by pure chance some hidden data in a likewise hidden directory index. The name which appeared on the data and the directory index was "E72UJ."

Work on cleaning out the **organs**. Scan the person and see which parts are hot. A lot of people will have an overheated solar plexus, which means that this area will require a lot of attention. You will feel the heat when you scan.

You can **clean the organs by 'pushing and pulling'**. Picture the organ and push; feel your hands are very 'long', extending through the organs and reaching out to the universe. Project all the sick energy down into the earth and out to the universe. Use your intent to guide it into the earth and out to the other planets in the solar system, where it will be processed and recycled. Pull the universal energy back towards yourself; push and disperse all the negative energy out to universe. Pull; when you pull the Chi back past the student, stop in between the two of you. Push, pull, push and pull, until you feel the energy or power. **Ask; "Give me the power to see". Feel your Chi entering into the organs with ease.**



A. ***B.***

Fig. 6.14

A. *Extend through the solar plexus and reach out to the universe.*

B. *'Clean and energize with Green' - push and pull to help loosen the solar plexus. Spiral counterclockwise with a Green Light. Blend with the sick energy and guide it down to the ground.*

Clean with Green Light. Spiral counterclockwise. Feel the green light mixing with the sick energy. Push and pull until you feel the energy in the solar plexus begin to disperse. Spiral the energy counterclockwise and guide it down to the ground.

A friend, who is a computer expert, could not make anything of this designation, and when I was about to show it to him, the directory index had disappeared. One evening, my apartment door was standing wide open, my TV set was running —and I am absolutely confident that I had turned the TV set off.

A minivan with British markings and the imprint of a Europe-wide supermarket chain parked in front of my house. I noticed the same minivan again on several occasions traveling at a distance behind my car, even when I visited the town of ...... 65 kilometers away. When I returned, the car was on the other side of the street once again. I never saw anyone get into or out of the car. A knock on the door of the vehicle and on the tinted windows caused no reaction of any kind. After about two weeks, the minivan disappeared again. When I informed E.F. personally about these events, he suggested that I change the place and date of the meeting in order to assure our own and Lacerta's safety. The meeting took place on April 27, 2000 in another isolated location. It was unobserved as far as I can determine.

Once again, all of this may sound strange and paranoid, like a fantasy from a cheap science fiction film; however, I can only repeat to and assure the reader once again: all of this is the unadulterated truth. Believe my words or don't believe them. These things have happened and they will continue to happen, whether you believe it or not. Until it is too late. Our civilization is in danger.

Ole. K. – May 3, 2000

Transcript of the Interview (Shortened Version)

Date of Interview: April 27, 2000

[Comment by Ole. K.: The meeting began with an appraisal of diverse questions and opinions which I had gotten from readers of the first transcript in anonymous fashion through distribution from my trustworthy friends. Some of these opinions—all together there were over 14 pages of paper—contained comments shaped by everything from a radically religious to a fanatical tendency to welcome contact with a reptilian species. Some of these comments contained stereotypical phrases like "Servants of Hell" or "Species of the Evil One". I don't want to go into any kind of detailed description here since I don't want pass on further any false and radical realm of thought.]

Question: When you read these religious and animosity-ridden comments here, what do you think and feel then? Is the relationship between your species and ours really shaped from that kind of total negation?

Answer: Does it amaze you that I am not completely angered by that? I had fully expected those kinds of extreme reactions. The programming for the utter negation of another species (especially the reptilian species) as in your own case is deeply embedded in each of your own individual consciousnesses. This ancient conditioning stems from the days of your third artificial creation and, biologically speaking, is passed down as an information genome from generation to generation. The identification of my species with the powers of darkness was a primary intention of the Illojim, who liked seeing themselves in the role of the powers of light —something which in and of itself represents a paradox, since that humanoid species was extremely sensitive to your sunlight.

In case you were expecting me to act offended, I guess I'll have to partially disappoint you. These obscure intentions are not really your fault; you are simply following for the most part what you have inherited from your ancestors. It is indeed actually somewhat disappointing that many of you develop no especially strong individual self-conscience, for this would help you to overcome the conditioning. As I already said, we were in direct contact in the last several centuries with some of your more primitive human tribes; these tribes had themselves succeeded in breaking through the old "creation programming;" they were able to meet us without tension, hate and total rejection. Apparently many of your modern civilized individuals are not in a position to think on their own, but rather let themselves be guided by programming and religion (which is also a manifestation of that ancient programming and part and parcel of the plan of the Illojim). Therefore, comments of that kind I'd sooner regard as amusing than irritating; they simply confirm in large measure for me my suppositions about your defined mode of thinking.

Question: Therefore, you are not the "Species of the Evil One" as was remarked earlier?

Answer: How am I supposed to answer that? Your people still think according to a simple and completely inappropriate scheme of generalizations. Simply put, there are absolutely NO purely evil species. There exist in every terrestrial and extraterrestrial species alike both good and evil individuals; it's even true of your own people; but there is NO such thing as an absolutely evil species. This conception is really very primitive. You people have believed from time immemorial what you are supposed to believe—what was foreseen for you to believe by your creators. Every well-known species, even the more highly developed ones, consists of a great number of individual consciousnesses (at least a portion of the consciousness is individual, even though there are connecting fields of consciousness); these self-sufficient spirits are able to decide freely for themselves a lifestyle which is either good or evil, according to your own human standards. It depends again on the respective point of view; your people are not necessarily in a position to judge whether the deeds of a much more highly developed species are good or evil, because you stand at a lower observation point, from which an assessment is not possible. Your simple words "good" and "evil" are in any case examples of a tendency towards generalization; in my language there are many concepts for the various shades of meaning of individual behaviors in comparison to the norms of a society.

Even those extraterrestrial species which are inclined to act with antagonism towards you are not "Species of the Evil One," even though they operate negatively with respect to your own race. They do this for their own reasons and do not regard themselves as evil; were your structured way of thinking more linear and more focused as theirs is, then you would also behave in such a fashion. The attitude of a species towards other kinds of existence naturally depends very heavily on its respective structured way of thinking; each species sets its own priorities. To classify that as "good" or "evil" is really quite primitive, for the survival of any species argues for many varieties, among them your own, as well as for even the most varied of the worst or negatively-directed deeds. I won't even exclude my own kind in this regard, for there have been certain occurrences in the past which I don't personally welcome, but about which I would also not like to go into detail. None of these occurrences have happened in the last 200 years of your time scale. But please note the following: there are NO absolutely good and there are NO absolutely bad species, because each and every species always consists of individuals.

Question: In the letters that I got, there was often the question, whether you could go into any greater detail regarding the advanced physics that you commented on last time. Many people said, your words made no sense. For example, how do UFOs function, how do they fly, how do they perform the maneuvers that they do?

Answer: I ought to explain that to people? That's not all that simple. Let me think about it for a minute. I always have to use very simple words in order to make clear to you the basic principles of a higher kind of science. Let's try this: You have to be clear about some fundamental facts. The very first thing is that you must divide up the conception of the physical world because each existence consists of different layers; let's say for simplicity's sake that it consists of a material illusion and a sphere of influence. {TRANSLATOR'S NOTE: No legitimate translation exists for this word 'Feldraum'; "Feld" means "field," "Raum" means "space, room, expanse." Therefore, I'm translating it as "sphere of influence."} Certain physical conditions are associated only with the realm of the material {as in 'concrete'}, while other and more complicated conditions are associated only with the sphere of influence of the material world. Your conception of the physical world is based upon a simple material illusion. That illusion is further subdivided into three elementary or basic conditions of matter. A fourth and very important condition also exists, which you simply pay attention to more or less as you choose; it is the one bordering on the sphere of influence or plasma realm. For you, the theory for a controlled transformation or an elevation of the frequency of matter and the stable existence of this fourth aggregate condition of matter is not very common, or it exists at a very primitive level. (As an aside, there are simply five states of matter, but the post-plasma state would really be going too far and it would only serve to confuse you. Besides, it is not necessary for an understanding of the basic theory; it is connected with diverse phenomena which you would characterize as paranormal.) Now, back to the essentials: Plasma...now, with plasma I don't mean just "hot gas"—as the concept is generally simplified by your people—but rather I mean a higher aggregate condition of matter. The plasma state of matter is a special form of matter which lies between its real existence and the sphere of influence, that is, a complete loss of mass and pure accretion of energy of various form whenever matter is "pushed or shoved." {NOTE: No explanation was given for the use of the word "pushed, shoved" as used in this context. Your guess is as good mine.}



The fourth state of matter is very important for certain physical conditions which can be used for example to...how should I express this to you...generate antigravity. (That's a rather strange human word and not really correct, but you ought to understand it better this way.) Essentially, in the world of real physics, there are no bipolar forces, but rather only "observer dependent reflective behavior" of a single, large unified force at different levels.

With antigravity or the displacement of gravitational characteristics into levels, one can, for example, cause apparently solid matter to levitate; this method is employed partly by us and by extraterrestrials as well as a means of propulsion for their UFOs. You people are moving on a really primitive level towards a similar principle for your secret military projects, but since you have more or less stolen this technology (and it was later falsely passed on to you intentionally by the extraterrestrials), you lack the real physical understanding; as a result, you have to struggle with problems of instability and radiation with your "UFOs". According to my information, there have been a great number of deaths of your people because of intense radiation and field disturbances. Don't you agree, this is also an example of the business regarding the question of "good" and "evil"? You people play with unknown forces and thereby accept the death of colleagues of your own kind, for they are dying for a greater cause, namely, for the advancement of your technology, which as a result is being put into place once again for the purpose of war, i.e., for negative pursuits. Now, one can give you the benefit of the doubt, that only the least number of your kind have any knowledge about these alien projects which are —as you explain it— top secret. It was told to you that the higher the ordinal or ranking number of basic matter, the simpler the heightening of the condition, but that is only partially correct. If you can't circumvent these powers, then you're better off not attempting it. But your kind has always been ignorant and has from time immemorial tried to play around with forces which you have not even understood. Why would that ever change?

You remember this business of copper fusion? By means of the fluctuation at the right angle with the induced radiation field, copper is fused with other elements. (The illusion of matter is fused, the fields in the sphere of influence overlap each other, but the main force would be reflected by that process and would assume a quasi-bipolar character.) The resulting connection and the field would therefore not be stable in the normal condition of matter and unsuited for tasks. As a result, the entire field spectrum is shifted to a higher plasma-like condition, whereby the spectrum comes together with this harsh shifting to the opposite pole side —the word is NOT correct— of the force field and it resembles quite closely a gravitational shift. This shifting causes a "tilting" of the repulsing quasi-bipolar force, which now no longer flows to the interior of the force field, but rather flows partly to the exterior of the field. The result is an inter-stratifying reflective force field which is very difficult to modulate within certain technical boundaries in relation to its own characteristics. It can also carry out a multiplicity of tasks, as for example, causing massive flying objects to be levitated and maneuvered. It can also exert a camouflage function in the realm of electromagnetic radiation as well as manipulate temporal sequences of events—indeed only to very limited extent—and other things as well. Are you familiar with your "quantum tunnel effect"? Even the amplitude equalizations among genuine matter can be achieved with one of those kinds of fields if the frequency and the distance from the plane of the field are high enough. Unfortunately, the whole thing that I have explained to you in your words has come out to be rather primitive, I'm afraid. It sounds rather strange and certainly impossible for your comprehension, but perhaps this simple explanation can be of some use to you in helping you to understand. But then again, maybe not.

Question: Is there a scientific substantiation for paranormal powers, as for example with your powers of thought?

Answer: Yes. In order to explain that, one has to acknowledge the physical reality of the sphere of influence {Feldraum}. I'll try to do it...wait just a second...you are going to have to separate yourself mentally from the illusion that that which you see is the true nature of the universe.

It is, at best, the surface of a side. Imagine for yourself that all the matter here —you, this table, this pencil, this technical device, this paper— does not really exist, but that it is rather only the result of a field oscillation and a concentration of energy. All matter that you see, every creature, every planet and star in this universe, has an "information-energy equivalent" in the sphere of influence which is located on a main field —the general level {of things}. Now, there is not only one level, but several. Last time, I had mentioned that highly-developed species which is capable of changing levels (which is something completely different from the simple bubble changing, for bubbles are a part of each and every level). Do you understand? Dimensions, as you call them, are a part of a solitary bubble, bubbles or universal foam are a part of a level, and levels are layers in the sphere of influence, while the sphere of influence, acting in the capacity of single physical size, is essentially unending; it is composed of innumerable information-energy layers and general levels. There are in the sphere of influence no null-levels; all are the same, but they are separated by means of their energy conditions. I notice that I am confusing you now. I think I ought to stop with this explanation.

Question: No, please continue. How do concrete paranormal powers arise?

Answer: Well, OK then. Let's try something simpler. Again, it is not completely correct, but let's begin in this manner: Tangible matter on this side is mirrored in the sphere of influence {Feldraum} as a field with distinct layers. These layers contain information, as an example, about the simple structure of matter or the string frequency, but also there is stored information stemming from the development of matter. Are you familiar with the human concept of "morphogenetic fields?" One part of the layer could be designated as such. Now there is still another intermediary layer for which you unfortunately have no human concept, since the theory is not common in human thinking. Let's call it a "para-layer," for this layer is mainly responsible for everything which you call PSI and paranormal and which lies outside the boundaries of your primitive science. This para-layer lies between the layers of matter and the morphogenetic layers of a field in the sphere of influence. It can actively integrate with both. Your body, for example, is mirrored as a field in the sphere of influence {Feldraum}. That doesn't mean that it does not also exist here as well —as flesh, blood, bones— in the form of matter strings or atoms, but not only that. Existence is always a duality. Some layers of the field contain simple information about the solid matter of your body and its frequency, while other layers {contain information about} your spirit, your consciousness or, speaking from a human-religious point of view, your soul. Awareness or consciousness in this case is a simple energy matrix, divided into different layers of your field in the sphere of influence —nothing more, nothing less. Genuine awareness can also exist here on the matter side, but only in the form of post-plasma {the fifth form of matter}. With the necessary physical knowledge and the corresponding technology, the consciousness/awareness matrix, or soul, can also be separated from its field of rest. It can, despite its removal, continue to exist in a self-sufficient manner for a certain amount of time. That has the strange occult name of "soul robbing." But above all, we're talking about science here, not about magic or dark forces.

[Comment by Ole. K.: The "soul robbing" was mentioned in one of the radical, religiously-motivated comments in connection with the reptilian species.]

But back to your Question: Creatures with more powerful mental powers can have a direct influence on the para-layer by means of their consciousness/awareness fields.

Now this layer is not limited only to the individual, but rather as a part of a general information layer —you could call it in a prosaic sense the community soul— that is connected with all animate and inanimate matter and all consciousness which exist on this main level. The biological cause for these abilities lies on the side of matter, by the way, in the pituitary gland, which always is in the position to generate the frequencies to actively control the sphere of influence {Feldraum}. Even you people could theoretically do this; however, you are solidly blocked in these things. As I have said, the para-layer can interact with mind as well as with matter. For example, if I decide to use my mental powers once more in order to move this pencil, then, simply said, I imagine in my mind how my consciousness/awareness expands/amplifies itself on the matter side in the form of post-plasma to the pencil. In the sphere of influence this causes simultaneously an automatic command from the consciousness/awareness layer to the para-layer to interact with the matter layer of the pencil. Since the para-layer is not confined to the body, it is not even a problem that the pencil lies over there, for I can unerringly reach it, even without moving my matter body. Post-Plasma on this side, para-layer on the other. I have control over the pencil and the interaction brings the matter field of the pencil to the point where it changes in the manner in which it moves, for example.

[Comment by Ole K.: I certify that the pencil mentioned above abruptly at that very moment jumped into the air to a height of 20 cm and then fell back to the surface of the table. The sound is clearly heard on the recording tape. No one visibly had touched that pencil.]

Question: That is fascinating. Which kinds of paranormal activities can one generate with that?

Answer: All kinds. Everything that you call paranormal. As I said, this special layer lies in the sphere of influence {Feldraum} between the morphogenetic information layers and the matter layers and can interact with respect to both sides. That is to say, it can be interacted with solid matter as well as with mind or mental information, wherewith we can achieve everything that is generally designated as telekinesis and telepathy. The "connection absorption" with another consciousness/awareness is generally separate in the procedure from the simple influence of matter, since different consciousness/awareness fields work with different oscillations. A consciousness/awareness that sends or a consciousness/awareness that listens must first adapt itself to the other mind exactly, before any access is possible. Most species also have chances to block the alien access, but you people don't have this. The following is generally valid: the stronger the paranormal abilities of a species, the simpler the adaptation and the access. Our own abilities are not so powerfully developed; therefore, first we have to learn specifically alien mind influence in order to use our mimicry, for example—where mimicry is actually quite simple in your minds due to the implanting of the on/off switch. Some of these abilities are also partially inherited; mother and child of my kind as an example are attuned exactly during the first months of life —partially also in the egg covering in the expectant mother— and communicate telepathically. In order to influence you people, we need a certain amount of time for practicing, despite your simple structure. Therefore, it is forbidden, for example, for adults of my kind before the "Age of Enlightenment" to come to the surface of the Earth. (That term is synonymous, along with other things, with full physical strength.) In the case of not fully developed abilities, the danger of discovery by you would be too great. By the way, there are of course numerous secret teachings about the real possibilities which can give one these abilities, but I really don't know anything exact about that.

Whenever an alien mind ought to be influenced, then there are some generally valid steps, which are set into motion by other extraterrestrial species.

First and foremost, the alien oscillation must be felt, something generally that is done automatically by the brain, i.e., for the one the field oscillation, for the other the quasi-electrical brain waves here in the normal space {which matter inhabits}. That is not especially difficult. After that, one simply probes for the other consciousness/awareness in the mind with a post-plasma manifestation, the sphere of influence {Feldraum} reacts and the connection is there. Now one can read out information from the first one and record the desired information to the second one in the correct location. You asked me last time whether you people have the opportunity to protect yourselves against this influence, and I told you that only an awake and concentrated mind had any kind of a chance to withstand it. In this state of mind the oscillations change very abruptly and access becomes complicated; more precisely, it can come as a painful recoil. Whenever you close your eyes, then the field becomes "flat," and alien access {to the mind} is immediately possible and without restriction. In terms of your chances against a more highly developed species, you have none at all. They are able to adjust the oscillations faster than you can change. I could even demonstrate it on you, but you were really horrified and confused the last time, so we'll just leave it at an explanation.

This explanation presumably sounds to you like —as you say— something esoteric or from the occult or magic. The reason for that is simply that you lack the basic understanding for seeing the background reasons. All paranormal phenomena have a purely scientific origination. None of this has anything to do with supernatural powers. We grow up with this kind of knowledge, we know how one makes use of these powers, and where they come from. We are acquainted with theory and practice. You are not. Therefore, you really don't understand what happens in your world—you see only one side of existence, not the other (I mean here both that are physical). Everything paranormal is dualistic, and it exists in the space that matter inhabits as well as in the sphere of influence {Feldraum}. To be explained...it can only be explained by the acceptance of the latter, because the sphere of influence {Feldraum} is the basis. I would welcome an end to the scientific questions since you really aren't grasping them anyway. We're wasting more or less valuable time by doing this.

Question: Only one last question. At our first meeting in December, you made it quite clear that you didn't want to discuss scientific and paranormal concerns. Why the openness now?

Answer: The last time I saw really no necessity in overburdening you with facts of that kind (and now you are obviously overburdened). Therefore, I had preferred only to mention these topics in a peripheral sense. Apparently, however, some of my performances today have set you to thinking about your world, something that can't be all bad. And by the way, your human scientists will tend to regard my comments as "humbug." And so I see no great danger in spreading this information widely. No one will pay much attention to it. By the way, the words of people who have characterized me as a "Creature of Evil" have their basis in the belief in occult powers and magic —both of which things DO NOT exist. There is no magic, only highly developed science, and everything that you label as "magic" is only a part of science. If you would only comprehend that, then you would be a step ahead in your development. My openness on this issue ends here. Pose other questions, please.

Question: Good. Let's talk about UFOs. Can you explain to me how our governments came into possession of UFO material to the point that they could start their own projects? Did it have anything to do with the "Roswell Incident?"

Answer: Yes, but that incident was not the first one. I am no historian, I am studying only your current behavior, so my knowledge about those events in your history is presumably not very extensive. I will try to explain to you what I know about those things which happened at that time. Let me think about it for a second. In the years 1946 to 1953 in your time scale, there were five cases where extraterrestrial ships crashed to the surface of the Earth. In that crash which you call the "Roswell Incident," there was not only one alien ship involved, but two that crashed after a collision in different parts of the land in the west—the one you call the USA. (You have to know that the ships of this particular species can remain levitating in the air for a particular period of time even though they are damaged; that accounts for the spatial difference {in their crash locations}.) These were indeed not the first crashes, but by that time the second and the third. Another ship had crashed in 1946, but it was destroyed beyond usability.

One thing first before the explanation: it certainly sounds ridiculous to you that such highly developed extraterrestrial ships simply crash, and that a relatively large number did so in a relatively short amount of time. The explanation for that is likewise more than strange, but it is correct. It does not lie in the ship's drive itself, but rather in the direction of the field to your planet. This species that we are discussing —and it was always in this time period that this species used a disk-shaped craft— used a propulsion system which ran according to the normal principle of fusion, to be sure, but one that at that time employed a more than unconventional method for field alignment. This method had various advantages but also disadvantages. The repelling field must of course lie in the absolute correct angle to the surface of the Earth. This species used an alignment technology in their ships, with which the field locked into place all points of the Earth's magnetic field. Now at that time this species had just arrived on the earth and their point of origin lay on a planet with a more stable magnetic field, for which they had developed and aligned their drive. The magnetic field of the Earth is not really all that stable; it is subject to cyclical variations and it forms field eddies under unfavorable conditions. Whenever a ship with one of those kinds of drives gets into a field fluctuation or into an eddy that is too strong, then for a short time the repelling field can no longer align itself correctly and the ship glides uncontrolled on its flight path. The drive is operating correctly, to be sure, but the field fluctuates in all directions and because of that, the ship can crash. In the case from 1947 which you addressed, it is my understanding that one of the ships got caught in a fluctuation, its field linked up unintentionally with that of its squadron leader and it collided with another ship whereby both of them were heavily damaged. The cause for the magnetic fluctuation at that time was probably an electrical disturbance brought about by a weather event. Both ships crashed as a result; one of them fell near the collision point, the other a hundred of your kilometers or so distant. All occupants were killed in the impact. The thin hull structure of that kind of disk craft is in and of itself not very stable, since those disks have not been designed for crashes as well as for flight in a field where there are exterior forces at work.

Now, your human military collected the individual pieces at first until they discovered the whole ships with the dead creatures aboard. Immediately they classified everything as "Top Secret" and brought them to their military bases in order to analyze the drive. The secret endeavor was to set the alien technology in place later against evil enemies of that great country. That is as primitive as it is ridiculous.

I believe I remember—I don't want to specify exactly your date—that it was probably between 1949 and 1952 that there was a rather bad accident during some research being done on one of the wrecks. According to what I heard—what members of my species were told by members of that government—it resulted in an unintentional activation of one of the drive's components in the unshielded condition. As a result, for a very short period of time—how should I phrase this—there was an unchecked shift of the environment to a plasma-like condition, which on the other hand, through a very, very unfortunate accident, caused an overturning of the general power field into a magnetic pulse of immense power. Do you have any idea what kind of an effect a plasma-magnetic jolt has, when it comes into contact with an organism? No, how should you know that. Of course you don't. Disturbance in the structure of the field and bioelectric feedback. Imagine, if you will, a human body which is engulfed in bright flames for 3 or 4 of your days. Those flames apparently do not go out and they burn the body right down to its last constituents. Well, then you have an approximate impression of what happened. I think that 20 or 30 of your scientists were killed in that lab.

Two further crashes occurred in 1950 and 1953 in the water catchment area of the American continent. Those ships were able to be recovered from the crashes relatively intact. (The one in 1953, as I remember, even had an intact drive core. It was by means of that device that you saw for the first time that you had understood the entire concept fully incorrectly and that you had reconstructed it fully incorrectly. Even today you still don't have it right.) That species, which had built the ships in the first place —a species which I, by the way, count among those who are unfriendly towards you— was naturally worried about the investigation of their own technology by your kind. They did not want, however, at that early point in time, to begin direct conflict with you, and so they chose the diplomatic path and came into contact with that government during your 1960's. Of course, they did not divulge the real reasons for their being here —copper, hydrogen, air— but rather they pretended to be curious "researchers" and offered to show people the functioning principle of the ships whereby they would expect in return some "favors." Simple-minded as you are, you of course agreed to it...and were deceived. You gave them raw materials, you gave them secured locations for their bases, you gave them access to your most secret defense data, you gave them access to your DNA and much more—and all just to quench your greed for power and information. The alien species of course quickly noticed that they were dealing with simple-minded creatures, and they gave you false and inferior information about their technology so that they receive much more out of the collaboration than your kind do. For example, they gave you information that the drive can only be constructed with unstable elements of a higher ranking number, but they withheld the information that the field drive can be constructed with various modifications to work as well with stable elements of a lower periodic number, and generally, that's the way it's done. Through these half truths they made you dependent on the synthesizing of high {numbered} elements, and thereby renewed by their own technology. Their clues to the construction of your "UFOs" were laid out in such a way that the solution to old problems caused new problems to arise simultaneously. They never told you the complete truth, but always built in again and again clever lies, which later lead to technical problems —and to your dependence on them.

In the last years of your 1970's and your early 1980's, it finally came down to various events between the alien species and that human government —I don't want to go into detail here since there is much that even I am not exactly sure of. The whole thing lay in the context with some new, or better said, the old technical problems with your own self-constructed ships whose camouflage and drive partially failed to function in test flights in the open.

Because of that, the function of secrecy was threatened. Your military and your politicians slowly—very slowly—came to the conclusion after more than 20 years of this that they had been deceived by that alien species. Multitudinous incongruities and the overstepping of bounds of the treaties by both sides finally led to an altercation between you and the extraterrestrials, which culminated in the lift-off of three of the alien aerial objects through a special —how do you say it?— EMP {electromagnetic pulse} weapon and a military skirmish at one of their underground installations. As a consequence of these attacks, the alien species ultimately withdrew from all contact with you and was understandably more than angered about your kind. Therefore, I count these extraterrestrials among the three groups who are hostile towards you, and while the other two are more occupied with their own business, among them waging a cold war for dominance on your planet, your old "friends" and partners are preparing to supply themselves finally with the sole and absolute dominance over raw materials and human DNA. At the moment it is probably true that they lack some of the technical possibilities and the large amount of forces which they need in order to achieve their goals directly. In spite of that, we are counting on negative actions —possibly ever of a more subtle kind— against you in the next few years or decades.

Question: Will the other extraterrestrial species undertake nothing against these war-like actions? Specifically, something ought to be on Earth for the more highly developed species.

Answer: You're wrong there. Specifically, for the more highly developed species there is simply at the very least your fate. You are animals for them. Animals in a very large lab. Understandably, an alien intervention on your planet would disturb their projects, but I don't think that they accept a confrontation with other species for it. Many of them could look for another research planet for themselves or they could study over a long distance your behavior and your consciousness/awareness, since crisis situations could have an attraction for their studies. Whenever you people take a look at an ant hill, and another person comes along and steps on the ant hill, what do you do? You go on your way, or you search for another ant hill or you observe the ants in their crisis condition. But would one of you —even though he were larger and more powerful than the one who stepped on the ant hill in the first place— defend the meaningless ants? No. You have to imagine for yourself the viewpoint of the more highly advanced creatures. You are the ants. Don't expect any help from them.

Of course we would also ask for help when it became clear that your old partners were ganging up on you. Some members of that human government are fully aware of our existence —also partially owing to an old religious basis. For example, there is a gigantic partially underground building in the capital which is totally dedicated to my species and that also has a direct approach to an elevator shaft and to an underground system. In this building partial meetings have taken place and do take place between us and humans. We have passed on information to you in the last few years; according to what I know, we will keep ourselves as far away from the conflict as we can. You ought to learn to solve your own problems yourselves or to become intelligent enough never to create those kinds of situations. What will come and who will possibly place themselves on your side, only time will tell. I really do not want to make any indications about that.



A. ***B.***

Fig. 6.15 A. *'Push and Pull' to help disperse the energy in the Solar Plexus.*
B.*'Flush and stabilize with Blue'-Picture Ocean Blue and flush sick energy down into the Earth.*

Rinse and flush with blue light. Picture ocean blue and flush down to the earth. See and feel the solar plexus becoming cleaner. Flush the sick energy down to the earth.

Now clean out the whole body again. With all the organs: from the lungs, heart, liver, gall bladder, pancreas, spleen, stomach, small intestines, large intestine, kidneys and sexual organs. Clean all the way down to the earth. **When you clean the solar plexus and all the other organs you remove all the negative emotional energy.**

Energize the **spleen**, **liver** and **kidneys** with blue or white light. Then project green, followed by orange light to the cores of the liver and kidneys. Clean with the green and orange light and stabilize with blue light.

Work on the **back** of the **spleen** and **kidneys**. Energize them with blue-white light. The spleen is on the student's left and kidneys on the right and left. They all help to clean the blood. Spiral the energy clockwise into the spleen. See it in your mideyebrow. See the cells and spiral the light into them. Give the command, "**Stay**". This is very important; it makes sure that none of the cells hide from the dazzling light that you are sending. Give the command again. Then stabilize them with blue light. Picture the kidneys and see their cells and feel the blue light go into the cells.

Work on the **Liver** on the student's right hand side. Smile and laugh to the liver and see all of its cells. Give the command, "**Stay**"; then send in the healing light. Send in blue or white (energize), followed by green (energize and clean), blue (rinse and stabilize), violet (recharge and reprogram) and then blue to stabilize again.

Question: I have here 5 prints of different UFOs, which claim to show UFOs. Can you take a look at the pictures and tell me in which of them actual extraterrestrial aerial craft can be seen?

Answer: I can try it. You pose many questions to me today which even I cannot answer unequivocally. Don't overestimate my knowledge, I'm no expert in alien technology and the construction of extraterrestrial ships. To be sure, there are mostly some technical details and peculiarities about genuine "UFOs," with whose help one can easily differentiate them from natural phenomena or human forgeries. You falsify sometimes the pattern of genuine ships; therefore, it is not so easy simply with absolute certainty to identify an object. I'll try it. Show me the photos.

[Comment by Ole K.: She considered the pictures respectively for only a couple of seconds and then sorted out photos 1, 3 and 5.]

These three pictures here are obvious counterfeits or erroneous identifications. In the one picture, it certainly seems to me that a real existing ship of an alien species was adapted for a small model here. It lacks important characteristics which are tied in with the technically- and physically-associated field. Generally speaking, a picture is all the more a fake, the clearer the outline and the colors are, because a levitating ship is generally hidden in a shifted-field condition that even distorts the colors or the forms according to alignment. It might perhaps sound strange, but hazy and spectrally-shifted photos are sometimes to be interpreted as an indication for a possibly authenticity. By the way, this object is floating above the water. If it were a genuine ship, we would have to see in any case either a trough or a swell on the surface. Since the surface is flat, it is obviously not a genuine ship. In my opinion, none of these three pictures show genuine objects in flight or UFOs. Here in this picture I see above all no artificial object in flight; it seems much more to deal with only a light reflex in your simple optical cameras. You really ought to be intelligent enough not to fall for a mix-up like that. When your general public chases counterfeits and frauds for a long time, then they will presumably discover too late, what is really going on in front of them in their atmosphere.

PHOTO 2: Albiosc, France, 1974

This one seems to be genuine, at least it displays the necessary characteristics. I would assign it at first glance to an alien species who have been visiting your planet for the last 35 years or so. The object itself is metallic and disk-shaped; certainly it is distorted in form and color by means of a field effect. These four white and very long "processes" on the underside of the ship itself portray a kind of quasi-gravitational light manipulation, i.e., the universal force field is being shifted in the direction of a simulated gravity. Actually, it is not a genuine light (it is mostly not a genuine light whenever you see illuminating "UFOs") but a special strongly charged form field which manifests itself in the space that matter inhabits as a quasi-light. The reason for the activation of this special high-energy system in an atmosphere is not completely clear to me; it's possible that it is a kind of investigating or influencing of the environment. In any case, it is terribly careless of that species to allow this technology to be photographed by humans. Well, I guess that most of you just plain don't understand it, and those who do will not say anything about it to the general public.

PHOTO 4: Petit Rechain, Belgium, 1990

This is in fact a genuine aerial object; it is in no way extraterrestrial. Triangular aerial objects in flight are simply not used by alien species, or not in this form, at least. That streamlined kind of form is a human concept. It is one of your own secret military projects that you build with the help of immature alien technology —technology that was handed over to you by the extraterrestrials during the 1960's and the 1970's. Generally, the form of the hull for a genuine extraterrestrial ship is of no consequence, for inside the field itself there are no exterior forces that have any effect there; in general, the ships have a rounded off form and they are built without hard edges —as a disk or a cylinder— so that the field can flow more easily. Your projects decree that along with the alien drive field there also be a conventional jet engine system; therefore, they are always triangular and built thus with streamlining in order to be steerable with this primitive recoil principle.

In the example here the ship glides above all on its genuine field drive. Do you see the distortion and the quasi-light in the rotating cylinders? That is an unmistakable indication for the authenticity of the photo. But why, you might ask, are there 4 cylinders? That's unusual —even the interval seems to be incorrect. The coloring is very dark and the interior optical distortion is very noticeable. Presumably a reconstruction of the original system by your scientists. Since the alien species has just not given you any more information since the disagreement, they are rebuilding the systems single-handedly without actually being able to understand what kind of dangerous thing they are doing there. This construction does not make the system better, only more unstable. Both of the forward cylinders are too close to each other; they will definitely flow into each other. The color shows me a powerful residual radiation; it was probably the case that high elements were used again as customary for the shifting. It is in any case very dangerous to be unshielded in the vicinity of the field. Did the person who took the photo display any kind of radiation and burn damage?

Question: I don't know. Where do these military "UFOs" come from? From the United States?

Answer: Yes. I think generally that's true. From the western continent.

Question: Why then do they fly over thickly populated areas of Europe? This photo comes from Belgium. That doesn't make any sense. Can you explain?

Answer: Why is it that ONLY I am able to explain strange human deeds? It's possible that these are long-distance tests or tests with the electromagnetic camouflage systems. The old enemy of the American nation is on this side of the world, so why shouldn't they test here? At home they've had enough time to have had their ships crossing back and forth. Maybe they have aroused too much observation there. With one of those kinds of unstable field structures —as your photo indicates— I consider it somewhat improbable that that ship is capable of making a flight of that length over the ocean. It's possible there is a test station here on your continent. Unfortunately, I don't know anything about it.

Question: Many readers of the first transcript have posed the question how your original contact with E.F. came about. I already know the story from your narratives, but could you repeat it here once again for this volume and for the new transcript?

Answer: Of course. Now, the story began about two of your years ago here in Sweden. I have been strongly interested in your species and your behavior since my youth; I had already studied your literature at that time, as well as possible. (Naturally, it is not easy in my homeland to come into possession of human books, but since my group or family stands in a higher ranking order, I was able to gather some material together and sometimes to speak with others of my kind who have already been in contact with you.) I was really very curious about your species and as soon as I was allowed to come to the surface, I attempted to assemble more information immediately; above all, it was expressly forbidden for me to commence direct contact with humans because in my position at that time, there existed no necessity for doing so.

It was in your year 1998, when I was on my way further north from here in the remote forests in the vicinity of the entrance to my world and was looking for biological specimens, which we use in order to watch over environmental pollution and destruction of your flora and fauna statistically by your own kind. At the time, I was already on the return path to the entrance—we can even orient ourselves more easily, by the way, through our senses to the Earth's magnetic field—and already in the vicinity of the large lake, when much to my surprise I came across a cabin in the woods. In this cabin I sensed a human consciousness/awareness. It was E.F. Actually, I had no permission for contact with another species, but by the same token I had set in place my mimicry capability quite successfully prior to this—even with larger groups of you (I had never ever come across a human being when I was alone). Now, let's call it primitive curiosity; I wanted to talk with the person in this cabin and so I knocked on the door. E. opened the door and we got into an interesting conversation. His language was not quite yet common at that time for me, but it's not all that hard to learn a new language when one can read the information in the consciousness/awareness of the opposite individual. I simply told him that I came from a foreign country in the east. Of course at the time, he did not really "recognize" who I was; he was totally convinced that he was talking with a creature of his own kind, although it was simply only a mimicry image.

Since my assignment anyway had as its goal an investigation of this terrain which was to last for several days, I visited him in this span of time three times as a human person. At first we talked mainly about really ordinary things; later we got into religious and physical topics. He seemed to be impressed by my knowledge, and I was likewise impressed with his clear thoughts and his—for a human being—well displayed personality structure and his own opinions. You really like giving yourselves over completely to a public opinion or conditioning, as for example, "reptilian species are evil" and stuff like that. I steered the conversation in this direction, and E.F. said something to the effect that he believed in alien species and that they did not have to necessarily be evil, but perhaps only different than his kind are. That pleased me. At that juncture of time, of course, I could not speak concretely with him about my knowledge because he wouldn't have believed me—he would have taken me for a human practical joker. I cultivated the very, very unusual idea (for my kind) to show him my true exterior, something that I did during our conversation at our fourth meeting in the cabin. Actually, he was predestined for contact: he was open-minded, honest, intelligent, not religiously inclined or conditioned; he lived alone and isolated, and no one would believe him, should he decide to go public with his story.

I dared to take the step, but then I had serious doubt about the propriety of my act, especially when he reacted...very...violently. He got control of himself again after a time and we could finally talk concretely about definite matters. Now he had no choice but to believe me. This was the beginning of a series of meetings which initially took place there in the woods, but later took place in his remote residence. Finally he brought you into contact with me...and for that reason we are now sitting here once again and talking about things which probably won't be believed out there in human society.

Question: You said, you would not have had permission at that time for contacts with human beings. Do you now then have permission to talk with E.F. and me about all these things and even to make this scientifically public?

Answer: Yes. That is difficult to explain and for you to understand. Let's just say, I find myself in the position now to arrange this permission without having to take into account any consequences. In this position I am quasi-"immune" against certain restrictions. Let's look it that way. Yes.

Question: If other people want to come into contact with your kind, do they have a chance to do so?

Answer: Generally not. We avoid contact with you and we operate on the surface only in remote areas and there we use the mimicry techniques in case we should meet some people. That I am talking with you now does not mean that others will follow my example. It goes without saying that you could try to find an entrance to my world and penetrate your way into there. However, that can sooner lead to unpleasant consequences for the infiltrator. You have next to no chances on the surface of recognizing us. You can't even contact us directly, we have to contact you, just as I did with E.F. Those kinds of contacts however are not the rule but are very rare occurrences.

Question: Can you describe your subterranean homeland location?

Answer: I can attempt to do so, but I certainly will not tell you where this place is located. My homeland lies in one of our smaller underground settlements to the east of here. I'll give you some numbers so that you can make a better impression for yourself. Just a minute...I have to try to convert the measurements approximately into your units. It is a dome-shaped cavern at a distance of about 4300 meters from the Earth's surface. The cavern was organized as a colony about 3000 years ago; a major portion of the ceiling structure is artificially integrated into the rock and the form was remodeled into an almost elegantly proportioned and very flat dome with an oval ground plan. The diameter of the dome according to your measures is about two-and-a-half kilometers. The height of the dome at the highest point is about 220 meters. Underneath that highest point in every colony there stands a special whitish-gray cylindrical building—a kind of supporting column which holds the honeycomb net-carrying structure of the dome. This building is the tallest, largest and oldest in the entire dome for it is always situated as the first construction together with the security of the ceiling. (In the meantime of course there were times when it was completed and reconditioned.) That building has a very special name and religious significance. We have only one of those columns; larger colonies even have more columns according to the construction of the ceiling.

One of the main colonies in Inner Asia has as an example 9 of those kinds of supports, but that colony is also over 25 of your kilometers in size. The central building is generally a center of religion, but also a center for climate control, and a center for the behavior and the regulation of the lighting system.

We have at our location all together 5 large artificial light sources which generate your UV light and its warmth through gravitational sources. The air shafts and the light systems from the surface likewise run through these columns and naturally, they are very intensely controlled.

By the way, we have 3 air shafts and 2 elevator systems there, and even a tunnel connection to the next main colony which lies approximately 500 kilometers to the southeast. One elevator shaft leads to a cavern near the surface, the other leads to one of our depots for the ships —you remember, the cylindrical ships— that is naturally concealed closer to the surface behind a rocky mountain face. Normally, there are only three ships there —it's a small depot. The other buildings of the colony are, for the most part, concentrically ordered in oval circles around the main supporting column, and they are without exception much flatter; generally only between 3 and 20 meters tall. The shape of the buildings is round and dome-like. The color is even differentiated according to circle and distance from the main column. To the north of the column, there is an additional, very large but very flat round building. This building interrupts the concentric system of the colony with its diameter of about 250 meters. It is the artificial sun zone in which specially illuminated corridors and rooms are housed. In these locations very powerful UV light predominates, and they are used in order to warm our blood. There is even a medical dispensary and a meeting room located there. Beyond the outer ring of the colony, there are zones in which animals are kept—you know, we MUST consume flesh as nourishment—and the gardens in which plant nourishment and mushroom culture are cultivated; there is also hot and cold running water there from subterranean sources. The power station is located on the edge of the colony. The station is driven by fusion as its base and it supplies the colony and the "suns" with energy. My group or "family" lives, by the way, in the fourth ring of buildings out from the central support column. So much in such a short time. To describe to you all the buildings and their tasks would be going too far. It is difficult to describe something like that to you, for it is a completely different set of surroundings and culture from what you are accustomed to in your life on the surface. You really have to see it for yourself to be able to believe it.

Question: Will I myself see it sometime?

Answer: Who knows, maybe. Time brings new opportunities.

Question: How many creatures of your kind live in this colony?

Answer: Approximately 900.

Question: That is the end of the interview. Do you have any final message for the readers of the transcript?

Answer: Yes. I am thoroughly surprised at the many comments to my words; of course, I am naturally also disappointed about the religious portrayals of me as the enemy which have been voiced and which have buried themselves deeply in your mind. You should learn to set yourselves apart from the old conditioning and not to stand quasi under the control of something or someone who has already been gone for 5000 years. You are, after all, free spirits. Those are my final words.

All Rights Reserved ©

Category Mind Control

NOV **14** 2017

Invited presentation by Magnus Olsson at the 2017 First Annual Unity and Hope Conference

Invited presentation by Magnus Olsson

"Invited presentation by Magnus Olsson, at the 2017 First Annual Unity and Hope Conference" This event was for targeted individuals and those concerned about the growing crimes of electronic harassment.

(https://nanobrainimplant.com/240_f_116659017_ryiguzdnplfxcwaattixa25shzy5nkt4/)

The conference was held from October 20-22 at the Mass Audubon Blue Hills Trailside Museum: 1904 Canton Ave., Milton, MA 02186, USA. This presentation was co-produced by Mårten Hernebring. The speaker, Magnus Olsson, can be reached at bionicgate@live.se Event Description from the Conference Web Site: "Our goal is to bring together as many support groups, media shows, activism groups, and organizations of targeted individuals, so we can work together and learn from each other and strategize on solutions to bring about change and end the suffering of hundreds of thousands of victims nationwide.

The number of people experiencing electronic harassment and gang-stalking is growing exponentially daily. Our hope is to come together, to build, empower, and educate the community on technology, resources, and support, and as a unified front attempt to educate the public. As a result of this conference, we will be able to strategically fight for freedom and justice for the victims of targeted crimes.

The goal of this conference is to unify all the groups worldwide and provide a knowledge and understanding of the program and the technology. We also strongly encourage targeted individuals to bring friends and family for support and to educate the ones around them on what invisible crimes are being committed against them."

By mindcontroleurope • Posted in Man vs Machine, military, Mind Control • Tagged artifical-intelligence, electronic harassment, gang-stalking, Hive Mind, hybrid brain, hybrid mind, magnus olsson, mind control, targeted individual, Targeted Individuals, Unity and Hope Conference

DEC **11** 2016

IMAGE

Now declassified & available! Russian Quantum Leap technology enhances RNA/DNA, cures diseases, stops Bio hacking

Now declassified & available online! Russian Quantum Leap enhances RNA, DNA & health, cures diseases (e.g. diabetes, cancer 2), stops TI targeting.

December 6, 2016

Now declassified & available online! Russian Quantum Leap technology enhances RNA, DNA & health, cures diseases (e.g. diabetes, cancer 2), stops TI targeting.

By Alfred Lambremont Webre

WATCH QUANTUM LEAP PANEL INTERVIEW

Watch Russian Television RT Interview with Magnus Olsson [Seen by 14 million persons]

Mind Control – Remote Neural Monitoring: Daniel Estulin and Magnus Olsson on Russia Today


(https://i2.wp.com/newsinsideout.com/wp-content/uploads/2016/12/Alfred-Webre-Morton-Hernebring-Magnus-Ollson-4.png?ssl=1)

alfred-webre-mårten-hernebring-magnus-olsson

You Tube: https://www.youtube.com/watch?v=o9bd-B2dqCM (https://www.youtube.com/watch?v=o9bd-B2dqCM)

VANCOUVER, BC – Newly arrived from Russian Quantum Leap by the American Reaserch and Development Company Wave Genos and its Founder and Sole Owner Irene Caesar Ph.D. Magnus Olsson and Madlen Namro, are joined by their colleagues Mårten Hernebring to launch the public version of Quantum Leap technology of Wave Genome Irene Caesar Ph.D, a declassified technology used by Russian Special Forces to enhance DNA, RNA, personal health profile and performance, eye and vision health, as well as provide personal protection against Transhumanist agenda weaponry including remote directed energy weapon [DEW] and psychetronic attacks, such as "V2K (Voice To Skull) and cancer guns, subliminal advertising and psychic attacks".

MindTechEnterprises, authorized distributors outside Russia for the ULTIMATE TESLA GENERATOR, created and produced by the American company Wave Genome and its President, Sole Owner and Founder Irene Caesar Ph D,"

"The information-wave technology of the Laser Biohologrpahy has been perfected by decades of research experience and clinical trials; it has been patented, licensed and certified by the Russian Ministry of Health; and, at the present moment, it is widely commercialized all over Russia. The information-wave technology of Laser Biohologrpahy is based upon the application of Quantum Physics to Genetics, a new theory of Genetics, which is called Structuralist Genetics (© Irene Caesar, Ph.D., 2010), and the application of the stabilized He-Ne lasers with internal mirrors."

MindTech-Enterprises Website

(https://nanobrainimplant.com/2016/12/11/now-available-russian-quantum-leap-technology-enhances-rnadna-cures-diseases-stops-bio-hacking/mind-tech-logo-01a/)

Full details of this first-ever public roll-out of Russian classified protective and health-status enhancing technology are set out in the above Panel interview and at Quantum Leap's distributors website at:

http://www.mindtech-enterprises.com/ (http://www.mindtech-enterprises.com/)

Quantum Leap Scalar Technology online

Quantum Leap technology, now available online through mini-Tesla Psi generators from the www.MindTech-Enterprises.com (http://www.mindtechenterprises.com/) website and through smart-phone apps, reportedly enhances the user's RNA, DNA & health profile, prevents and cures diseases such as diabetes, Stage 2 cancer, and stops Transhumanist Agenda weapons such as Voice to Skull and electromagnetic remote targeting.

The Quantum Leap technology's Mini-Tesla Generators come with Digital Pharmacy and a subscription service.

Quantum Leap technology, in applications developed in conjunction with Russian scientist Irene Caesar PhD. According to Dr. Caesar, the technology results in "Rejuvenation of all the Physiological systems, including endocrine system, digestive system, cardiovascular system, hearing / eye sight, reproductive system, intellectual abilities, improvement of memory."

Some features of the Quantum Leap Ultimate Generator

According to Wave Genome Irene Caesar Ph.D, *"The device is easy to wear in the form of a pendant cased in pearl, completely unobtrusive, and people can't tell exactly what it is because it is cased in pearl and does not look too unusual or like a "medical device", etc. The device is indestructible. The device is waterproof for basic small splashes, but should not be immersed in water.*

(https://nanobrainimplant.com/2012/07/11/scientists-humans-and-machines-will-merge-in-future/imagesca38vl83-3/)

The team uses a high resolution picture of yourself from early childhood (around 4-6 years of age) to develop sophisticated holography matrices from the picture using laser technologies and quantum technologies including scalar waves. They are able to recreate your energy field from when you were a child in a personal digital wave matrix and then use the device to continuously feed your current energy field with information from your childhood energy field. This helps to restore your current energy field to healthier conditions. This newer model has logarithmically more powerful protection features compared to the older versions of this device.

This new model still comes with all the health features of the older model including the E-Pharmacy, and ongoing health monitoring by professionals. The older more generic version of the device has been worn by members of parliament and Special Forces in Russia as well as the Russian Olympic Team. Over 5000 scientists/researchers from Russia have collaborated to work on this special project developing this device using the most advanced science in the world.

Some benefits of the Ultimate Generator:

The advanced technologies in the device can neutralize psychotronic/electronic attacks. The device is able to eliminate V2K. You can sign up for a monthly membership service to have the expert professional staff at the Moscow clinic in Russia monitor your health on an ongoing basis. If anything goes wrong with your health they are able to correct deviations from normal even before you notice symptoms of any actual medical condition. If medical conditions exist, many of them can be completely healed. You can receive medications remotely administered through the device. They get filtered through your own energy field and are guaranteed to never cause any adverse side effects.

The device helps to boost your immune system to diminish susceptibility to any illness. The device can help neutralize the negative effects of cosmic radiation when you fly in an airplane long distances. It can also reduce jet lag as well as keep you healthy while traveling. The device can help boost your energy, can help you sleep better, and can help you recover from any stressful events, sleep deprivation, etc., much faster. It can help you think more clearly and improve overall cognitive function. (Irene Caesar Ph.D.)

How purchasing works:

You can buy online at the website. Please see

http://www.mindtech-enterprises.com/ (http://www.mindtech-enterprises.com/)

Choose which version of the product you want to purchase. We recommend the Ultimate Generator as it is the most powerful version. Payments are processed using Paypal and other methods. You will be contacted to send a high resolution childhood picture of yourself. You will receive the device in the mail within 6 weeks. It takes this long to produce this device and to customize it for each individual. But don't worry, it will be worth the wait!



Spleen - Front and Rear



Liver



Fig. 6.16 *'Push and Pull' to help disperse the energy in the Liver and Spleen. Clean with Green and flush and stabilize with blue. Flush the sick energy down into the Earth.*

It is essential that you feel and talk to any sick energy. **If the student is healthy then you will feel their 'light'.** Ask their energy body to tell you where it **may** need some healing. Send in 'light radar'. Transmit green light and flush down to the earth. **When you feel that energy is accumulating, start to spiral more.** Push and pull and give the command for the sick energy to leave.

The more you clean, the more you heal. Tell your student to practice at home after the session, at an agreed time. You can then carry out 'absent or distance' healing, linking everyone's personal star, energy body and the universe. **With time, you will master the techniques, imprinting them with your own manner.** Eventually symptoms disappear, as the blockages are cleared and the flow returned.

Cleansing the Spinal Cord

Always cleanse the spinal cord, which protects the entire body from diseased and negative energy, both physical and psychic. When you open the spinal cord and solar plexus you can release many energy blockages. Sweep the hand in a clockwise motion to energize the spine with either/or a combination of; **blue, green, white and ultra-violet**. Then spiral counterclockwise and **brush** the spine down to the ground. Continue sweeping until you feel that the spinal cord has cooled down. Remember not to use orange or red.



Spine

Tesla Glasses

IRENE CAESAR, PH.D.: ON TECHNOLOGY AND THEORY OF TESTLA GLASSES

The Panel also discusses Tesla glasses that have been developed and successfully used by Russian Security Forces for prevention and correction of:

- Stress and its consequences;
- Deterioration of the physical and mental performance;
- Reduction of immunity and the bodily defenses;
- Eye diseases;
- Diseases of the internal organs and physiological systems

(https://i1.wp.com/newsinsideout.com/wp-content/uploads/2016/12/1.TESLA_.GLASSES3.jpg?ssl=1)

Tesla Glasses

According to Wave Genome ***Tesla Glasses*** *use the method of Polarized Holography. Polarized Holography is the application of Quantum Physics for the purpose of rejuvenating all organs of the person through the Eye Crystal (Eye Lens and Iris). It is proven to provide significant physical and mental improvement, including a significant improvement in brain functions: decision speed, attention and memory.*

The method consists in the control of the brain via triggering the holographic signal in the eye, and its modulation. This control overwrites any verbal and mental imperatives, is non-local (can be used for instantaneous transmission of information at infinitely large distances), instantaneous (exceeds speed of light), and simultaneously reaching out towards every cell in the body.

The method is based upon Quantum Physics, specifically, upon the theory and technology of Polarized Holography, which uses the modulation of the holographic signal according to the Kozyrev Mirror principle.

The method is based upon the special ability of an eye to convert any linear signal into the holographic signal. The process of this conversion consists in the emergence of the scalar wave diffraction grating, polarization and refraction toward the zero center of the wave crystal (torus). Since the universe is holographic, we can record and transmit information only via the holographic signal, and through the zero center of the wave crystal. The zero center of every toroidal wave crystal coincides from the zero center of every chromosome on the cellular level, and every atom and subatomic particle on the subatomic level to the zero center of our galaxy.

Any healing, rejuvenation, and mental, psychic, and physical enhancement are based upon the ability to produce, control and enhance the holographic signal. The holographic signal instantaneously reaches the zero center of every wave crystal in our body, from the subatomic and atomic to the molecular levels – from the zero center of our skull and every bone to the zero center of every metacentric chromosome. Our eyes, skull, bones and chromosomes are centered and focused similar to our eye crystal according to the laws of the geometrical optics.

Hence, the eye is a very unique receiver, transmitter, and producer of the holographic signal. And that is precisely why vision is a trigger of brain activity. Via correct triggering the holographic signal in the zero center of the eye crystal, we can immediately reach the zero center of the toroidal wave crystal of our brain, thus delivering controlling information instantaneously into the zero center of the wave crystal of every metacentric chromosome in cell division, and into the zero center of the wave crystal of every bone, so that stem cells are programmed in a correct way in the bone marrow.

MINDTECH ENTERPRISES

(https://nanobrainimplant.com/2016/12/11/now-available-russian-quantum-leap-technology-enhances-rnadna-cures-diseases-stops-bio-hacking/mind-tech-logo-01a/)

Correct triggering consists in the modulation of the holographic signal in the eye. The modulation of the holographic signal in ***Tesla Glasses*** *consists in (1) modulation by the Schumann holographic signal; (2) modulation by human Brain holographic signal; (3) modulation by the holographic signal of a healthy organ and physiological system, recorded upon the chip in the glasses. It is combined with the modulation by the narrowband light-emitting diode sources of five colors. Research had shown that five colors, used by the glasses, benefit organs and physiological systems. The signal for every color is produced from the holographic signal of healthy organs and physiological systems, and, then, it is matched with the color. The signal of the color is not simply the color frequency.*

The carrier holographic signal is the individual holographic signal of the user – the unique [indestructible and uncreated] non-local wave matrix of the user. This is the primary holographic signal. The modulation holographic signals are the holographic enhancers, which help the unique [indestructible and uncreated] non-local wave matrix of the user get centered and focused in this dimension (on this planet). These are secondary holographic signals.

The advantage of the glasses over other Quantum Leap Polarized Holography devices is that glasses use an eye as a filter for filtering out all harmful linear signals, which unseal wave crystals. For example, microwave radiation shortens brain waves via "unsealing" the involuted wave crystals, thus, literally lowering the intellectual potential of people.

(https://nanobrainimplant.com/2016/12/06/now-declassified-available-online-russian-quantum-leap-technology/240_f_68304591_ovk9v6qieaoepraueh02gzahmcl49ymn/)

Thus, the effect of the ***Tesla Glasses*** *is based not simply upon the superficial stimulation of innervation. The stimulation of innervation, tone of the eye muscles, blood circulation, regeneration, and enhancement of all other biochemical and bioelectrical processes in the body are based upon the structural efficacy of Polarized Holography, which centers and focuses chromosomes, and prevents the transformation of metacentric chromosomes into acrocentric chromosomes.*

The modulation via secondary holographic signals (see above) allows for the emergence of the most coherent and sophisticated scalar wave diffraction grating that produces the more clear zero focus within the wave crystal (of a wave torus on every level from the atomic, subatomic to cellular and molecular levels).

The modulation occurs through the designated areas of Iris, each one corresponding to a specific organ in the body. As a result, the user achieves the stimulation of the projection zones in the Iris, each one being connected to a specific organ in the body.

In addition, ***Tesla Glasses*** *use the same effect as the binaural therapy. Binaural therapy uses the stereo effect, when signal in one ear gets into the brain with delay in relation to signal in the other ear. This produces the emergence of the complex scalar wave diffraction grating in the skull, based upon Kozyrev Mirror principle (polarization, refraction and emergence of the zero center of the wave crystal). Similar to this,* ***Tesla Glasses*** *use the stereo effect of color signal, when color signal in one eye gets into the brain with delay in relation to signal in the other eye.*

Product by:

WAVE GENOME

(https://nanobrainimplant.com/2016/12/11/now-available-russian-quantum-leap-technology-enhances-rnadna-cures-diseases-stops-bio-hacking/wave-genome/)

Ophthalmologists have found that all healthy people have rhythmic alternation visual perception. Man sees in turn by the right eye, and, then, by the left eye at regular intervals.

These intervals last for 2-3 seconds. The research was conducted using modern 3D technologies. And if one eye is covered by a blue filter, and the other eyes is covered by the red filter, the healthy person sees both colors simultaneously and separately. The left eye sees 20% of the image, and the right eye sees 80% of the image.

With age, these rhythms get broken. But the restoration of the "biological clock" is possible using Polarized Holography, modulated by color signals, with the frequency of the alpha rhythm of the brain of a healthy person. And, as the positive effect, we can achieve a significant rejuvenation of the body.© Irene Caesar 2015

The text is quoted from http://www.wavegenom.com (http://www.wavegenom.com)

More information on Tesla Glasses is available, and Tesla Glasses can be purchased at:

http://www.mindtech-enterprises.com/ (http://www.mindtech-enterprises.com/)

References

Quantum Leap, available from:

Wave Genome

MindTechEnterprises

http://www.mindtech-enterprises.com/ (http://www.mindtech-enterprises.com/)

Contact:

Email:

mindtechtrade@gmail.com

Send A Message:

http://www.mindtech-enterprises.com/ (http://www.mindtech-enterprises.com/)

Alfred Lambremont Webre Contact/News:

Related


(https://newsinsideout.com/2016/09/part-magnus-olsson-reveals-artificial-crystals-blood-spread-via-smart-dust-transhumanist-remote-neural-weapon-control/)

PART I: Magnus Olsson reveals artificial crystals in his blood, spread via smart dust, are a Transhumanist remote neural weapon for control (https://newsinsideout.com/2016/09/part-magnus-olsson-reveals-artificial-crystals-blood-spread-via-smart-dust-transhumanist-remote-neural-weapon-control/)

PART I: Magnus Olsson reveals artificial crystals in his blood, spread via smart dust, are a Transhumanist remote neural weapon for control Transhumanist think tanks foreshadowed revelation in 2011 VOLVO TV ad – "Magnus Olsson: it gets in your blood" NewsInsideOut.com By Alfred Lambremont Webre WATCH EXOPOLITICSTV INTERVIEW VANCOUVER, BC…

September 20, 2016

In "AI Artificial Intelligence"

EUCACH Director: Dr. Rauni Kilde radiated for four days with DEW.

EUCACH Director: Dr. Rauni Kilde radiated for four days with DEW. Remotely assassinated by NSA? By Alfred Lambremont Webre NewsInsideOut.com WATCH ON YOU TUBE VANCOUVER, BC – Magnus Olsson, director of the European Coalition against Covert Harassment (EUCACH.ORG), revealed today in a NewsInsideOut.com interview that EUCACH Board of Directors member,…

(https://nanobrainimplant.com/2016/12/11/now-available-russian-quantum-leap-technology-enhances-rnadna-cures-diseases-stops-bio-hacking/mind-tech-logo-01a/)

By mindcontroleurope • Posted in Man vs Machine, military, Mind Control, News, Uncategorized • Tagged artifical-intelligence, biohacking, brain, disease, dna, electronics, health, interfaces, magnus olsson, military, military / medical classified research, neurohacking, quantum leap, rna, russian quantum leap, scalar, targeted individual, ti, Transhumanism, wave genome
SEP **11** 2016

THE Reality of Magnus Olsson’s blood – doctor’s report

THE Reality of Magnus Olsson’s blood – doctor’s report



(https://nanobrainimplant.com/?attachment_id=1102)

During my staying in Poland, in Lublin I met a specialist Dr, who took a sample of my blood from my finger and we watched this together through an atomic microscope.

I will not now describe what is wrong with my blood, but I want you to notice the cristal which was made artificially.

what this is doing to me:

1. 1. makes my blood, not circulate in a natural manner (blood is too dense)
2. 2. damage DNA
3. 3. Influence memory (lack of memory)
4. 4. you can not walk normally nor run
5. 5. destroy your skin (you may have albinism)
6. 6. having a hard time sleeping
7. 7. easy access to the brain
8. 8. lack of oxygen

and many other symptoms…

There are millions of this in my blood. Every victim should do this checking with a doctor who knows about People Online and will check this blood with you through a atomic microscope.

This, together with the waves RF, ELF, SCALAR, NEUTRINOS, QUATUM SPECTRA, LASER, SONAR and others is devastating.

Previewing...

(https://nanobrainimplant.com/2016/09/11/the-reality-of-magnus-olssons-blood-doctors-report/magnus-olsson-blood-2/)

The most important for us is to secure ourselves and then cure. I am now working on a breathtaking solution for all of us, and I hope we will be free pretty soon. Then we can recover and heal.

Love and Light

Your Magnus

THE Reality of Magnus Olsson's blood – doctor's report:

Crimes against humanity are certain acts that are committed as part of a widespread or systematic attack directed against any civilian population or an identifiable part of a population:
https://en.m.wikipedia.org/wiki/Crimes_against_humanity (https://en.m.wikipedia.org/wiki/Crimes_against_humanity)
THE PENTAGON'S BLUE-SKY research arm wants to trick out troops' brains, from the areas that regulate alertness and cognition to pain treatment and psychiatric well-being. And the scientists want to do it all from the outside in:
http://google.co.in/patents/US3951134 (http://google.co.in/patents/US3951134)

https://en.m.wikipedia.org/wiki/Rayleigh_wave (https://en.m.wikipedia.org/wiki/Rayleigh_wave)

https://en.m.wikipedia.org/wiki/High_Frequency_Active_Auroral_Research_Program (https://en.m.wikipedia.org/wiki/High_Frequency_Active_Auroral_Research_Program)
What if a machine could read your mind?
https://drive.google.com/file/d/0B4iZUaEgNfFfMnpyem5fX1BPTTg/view (https://drive.google.com/file/d/0B4iZUaEgNfFfMnpyem5fX1BPTTg/view)
While most developmental robotics projects strongly interact with theories of animal and human development, the degrees of similarities and inspiration between identified biological mechanisms and their counterpart in robots, as well as the abstraction levels of modeling, may vary a lot.
https://en.m.wikipedia.org/wiki/Neuron_(software) (https://en.m.wikipedia.org/wiki/Neuron_%28software%29)
While some projects aim at modeling precisely both the function and biological implementation (neural or morphological models), such as in neurorobotics www.humanbrainproject.eu (http://www.humanbrainproject.eu/), some other projects only focus on functional modeling of the mechanisms and constraints described above, and might for example reuse in their architectures techniques coming from applied mathematics or engineering fields.
https://en.m.wikipedia.org/wiki/Developmental_robotics (https://en.m.wikipedia.org/wiki/Developmental_robotics)

https://m.facebook.com/Artificial-Brain-Sweden-1014306015294202/ (https://m.facebook.com/Artificial-Brain-Sweden-1014306015294202/)
What are the ethical issues involved in simulating a human brain and in technology derived from human brain simulation?
Building computer models of the brain may challenge our concepts of personhood, free will and personal responsibility, and the nature of consciousness.
(Delgado stated that "brain transmitters can remain in a person's head for life.
The energy to activate the brain transmitter is transmitted by way of radio frequencies.
https://en.m.wikipedia.org/wiki/Jos%C3%A9_Manuel_Rodriguez_Delgado (https://en.m.wikipedia.org/wiki/Jos%C3%A9_Manuel_Rodriguez_Delgado))

https://drive.google.com/file/d/0B4iZUaEgNfFfZl9iU1BpbzNJTW8/view (https://drive.google.com/file/d/0B4iZUaEgNfFfZl9iU1BpbzNJTW8/view)
In medicine, brain simulation could make it easier to communicate with people who cannot speak (e.g. people with severe disabilities, people in a vegetative state or with locked-in syndrome) or to enhance cognitive function in people with cognitive disabilities (e.g. dementia, trauma and stroke victims, etc.).
https://en.m.wikipedia.org/wiki/Wetware_(brain) (https://en.m.wikipedia.org/wiki/Wetware_%28brain%29)
As in other fields of science, it also possible that new knowledge about the brain will be abused – deliberately, for example to create new weapons – but also involuntarily, because society does not realize the power and consequences of new technologies.
https://m.facebook.com/Martin-Ingvar-KI-1528410917453814/ (https://m.facebook.com/Martin-Ingvar-KI-1528410917453814/)
For instance, it may be possible in the future to use knowledge about the brain to predict and modify individual behaviour, or even to irreversibly modify behaviour through electrical stimulation of the brain, pharmacology or neurosurgery. In cases of intractable mental disease, this may be desirable, but in other cases, the costs and benefits will be debatable. One example of debate is whether society should allow cognitive enhancement in healthy people.
Similar considerations apply to technology. Future computers that implement the same principles of computation and cognitive architectures as the brain have enormous potential to improve industrial productivity and offer new services to citizens.
However, they could also be used to implement new systems of mass surveillance and new weaponry.
https://m.youtube.com/watch?v=o9bd-B2dqCM&feature=youtu.be (https://m.youtube.com/watch?v=o9bd-B2dqCM&feature=youtu.be)

If such systems came into widespread use they would undoubtedly have a huge impact on patterns of daily life and employment – this could be both beneficial and detrimental
https://www.humanbrainproject.eu/faq/ethics (https://www.humanbrainproject.eu/faq/ethics)

This is what it's all about:
https://m.youtube.com/watch?v=01hbkh4hXEk&feature=youtu.be (https://m.youtube.com/watch?v=01hbkh4hXEk&feature=youtu.be)
The development of your Future connected to a mindreading machine:
https://www.rt.com/usa/265029-kurzweil-google-hybrid-brain/ (https://www.rt.com/usa/265029-kurzweil-google-hybrid-brain/)

http://www.ted.com/talks/ray_kurzweil_get_ready_for_hybrid_thinking (http://www.ted.com/talks/ray_kurzweil_get_ready_for_hybrid_thinking)
And the developing of Future Surveillance:
https://m.youtube.com/watch?list=PL9DCCHoTYZ8KaMFrLrUzNblMsIECi9vQ0&v=30seQeBI-Tc (https://m.youtube.com/watch?list=PL9DCCHoTYZ8KaMFrLrUzNblMsIECi9vQ0&v=30seQeBI-Tc)

https://m.youtube.com/watch?feature=youtu.be&v=pW1HACMaOME (https://m.youtube.com/watch?feature=youtu.be&v=pW1HACMaOME)
Imagine what U.S could do if they could master the nanoparticles that are distributed in vaccine to human's worldwide and use them for remote neural monitoring:
https://mind-computer.com/2012/12/20/remote-neural-monitoring-a-technology-used-for-controlling-the-human-brain/ (https://mind-computer.com/2012/12/20/remote-neural-monitoring-a-technology-used-for-controlling-the-human-brain/)
Nanoparticles BMI https://en.m.wikipedia.org/wiki/Brain%E2%80%93computer_interface (https://en.m.wikipedia.org/wiki/Brain%E2%80%93computer_interface) in vaccine:
Nanofluids also have special acoustical properties and in ultrasonic fields display additional shear-wave reconversion of an incident compressional wave; the effect becomes more pronounced as concentration increases.
https://en.m.wikipedia.org/wiki/Vaccine (https://en.m.wikipedia.org/wiki/Vaccine)

https://en.m.wikipedia.org/wiki/Aluminium (https://en.m.wikipedia.org/wiki/Aluminium)

http://sharpbrains.com/blog/2015/03/19/non-invasive-brain-stimulation-meets-nanotechnology/ (http://sharpbrains.com/blog/2015/03/19/non-invasive-brain-stimulation-meets-nanotechnology/)

http://globalbiodefense.com/2012/07/28/darpa-program-hits-milestone-in-plant-based-vaccines-for-pandemics/ (http://globalbiodefense.com/2012/07/28/darpa-program-hits-milestone-in-plant-based-vaccines-for-pandemics/)

https://en.m.wikipedia.org/wiki/Nanofluid (https://en.m.wikipedia.org/wiki/Nanofluid)
This speaks volumes about the hidden impact certain vaccines may have on your body and your brain in particular…
http://articles.mercola.com/sites/articles/archive/2011/08/06/vaccine-increases-narcolepsy-by-660-percent.aspx (http://articles.mercola.com/sites/articles/archive/2011/08/06/vaccine-increases-narcolepsy-by-660-percent.aspx)

Delgado stated that "brain transmitters can remain in a person's head for life.
The energy to activate the brain transmitter is transmitted by way of radio frequencies.
https://en.m.wikipedia.org/wiki/Jos%C3%A9_Manuel_Rodriguez_Delgado (https://en.m.wikipedia.org/wiki/Jos%C3%A9_Manuel_Rodriguez_Delgado)

https://www.google.com/patents/DE10253433A1?cl=en&dq=inassignee%3A (https://www.google.com/patents/DE10253433A1?cl=en&dq=inassignee%3A)

https://archive.org/details/pubmed-PMC4086297 (https://archive.org/details/pubmed-PMC4086297)

https://en.m.wikipedia.org/wiki/Neurorobotics (https://en.m.wikipedia.org/wiki/Neurorobotics)

https://drive.google.com/file/d/0B4iZUaEgNfFfell0YWFFMHd3RnM/view (https://drive.google.com/file/d/0B4iZUaEgNfFfell0YWFFMHd3RnM/view)

https://en.m.wikipedia.org/wiki/Cybernetics (https://en.m.wikipedia.org/wiki/Cybernetics)

https://en.m.wikipedia.org/wiki/Target_Motion_Analysis (https://en.m.wikipedia.org/wiki/Target_Motion_Analysis)

http://www.raytheon.com/ (http://www.raytheon.com/)
In analysis such as computational fluid dynamics (CFD), nanofluids can be assumed to be single phase fluids.
http://www.datacenterdynamics.com/news/sgi-gives-us-military-the-fastest-supercomputer/91007.fullarticle (http://www.datacenterdynamics.com/news/sgi-gives-us-military-the-fastest-supercomputer/91007.fullarticle)
The Worldwide Security Grid: MATRIX Smartdust is a system of many tiny microelectromechanical systems (MEMS) such as sensors, robots, or other devices, that can detect, for example, light, temperature, vibration, magnetism, or chemicals. They are usually operated on a computer network wirelessly and are distributed over some area to perform tasks, usually sensing through radio-frequency identification.
http://www.foi.se/en/Customer–Partners/Projects/Edge1/Edge/ (http://www.foi.se/en/Customer--Partners/Projects/Edge1/Edge/)
Without an antenna of much greater size the range of tiny smart dust communication devices is measured in a few millimeters and they may be vulnerable to electromagnetic disablement and destruction by microwave exposure.
https://en.m.wikipedia.org/wiki/Smartdust (https://en.m.wikipedia.org/wiki/Smartdust)
The Grid Security Infrastructure (GSI), formerly called the Globus Security Infrastructure https://en.m.wikipedia.org/wiki/Grid_Security_Infrastructure (https://en.m.wikipedia.org/wiki/Grid_Security_Infrastructure), is a specification for secret, tamper-proof, delegatable communication between software in a grid computing environment. Secure, authenticatable communication is enabled using asymmetric encryption.
http://ieeexplore.ieee.org/xpl/login.jsp?reload=true&tp&arnumber=6028683&url=http%3A%2F%2Fieeexplore.ieee.org%2Fxpls%2Fabs_all.jsp%3Farnumber%3D6028683 (http://ieeexplore.ieee.org/xpl/login.jsp?reload=true&tp&arnumber=6028683&url=http%3A%2F%2Fieeexplore.ieee.org%2Fxpls%2Fabs_all.jsp%3Farnumber%3D6028683)
In software engineering, the terms "front end" and "back end" are distinctions which refer to the separation of concerns between a presentation layer and a data access layer respectively.
The front end is an interface between the user and the back end. The front and back ends may be distributed amongst one or more systems.
In software architecture, there may be many layers between the hardware and end user. Each can be spoken of as having a front end and a back end. The

front is an abstraction, simplifying the underlying component by providing a user-friendly interface.
https://en.m.wikipedia.org/wiki/Pervasive_game (https://en.m.wikipedia.org/wiki/Pervasive_game)
In software design, for example, the model-view-controller architecture provides front and back ends for the database, the user and the data processing components. The separation of software systems into front and back ends simplifies development and separates maintenance. A rule of thumb is that the front (or "client") side is any component manipulated by the user. The server-side (or "back end") code resides on the server.
https://en.m.wikipedia.org/wiki/Front_and_back_ends (https://en.m.wikipedia.org/wiki/Front_and_back_ends)

https://m.youtube.com/watch?v=o9bd-B2dqCM&feature=youtu.be (https://m.youtube.com/watch?v=o9bd-B2dqCM&feature=youtu.be)
The Utah Data Center, also known as the Intelligence Community Comprehensive National Cybersecurity Initiative Data Center, is a data storage facility for the United States Intelligence Community that is designed to store data estimated to be on the order of exabytes or larger.
Its purpose is to support the Comprehensive National Cybersecurity Initiative (CNCI), though its precise mission is classified.
http://www.defense.gov/News/Speeches/Speech-View/Article/606635 (http://www.defense.gov/News/Speeches/Speech-View/Article/606635)

https://www.iarpa.gov/index.php/research-programs/neuroscience-programs-at-iarpa (https://www.iarpa.gov/index.php/research-programs/neuroscience-programs-at-iarpa)

https://en.m.wikipedia.org/wiki/Wetware_(brain) (https://en.m.wikipedia.org/wiki/Wetware_%28brain%29)

http://www.datacenterdynamics.com/news/sgi-gives-us-military-the-fastest-supercomputer/91007.fullarticle (http://www.datacenterdynamics.com/news/sgi-gives-us-military-the-fastest-supercomputer/91007.fullarticle)

http://bioethics.gov/node/4704 (http://bioethics.gov/node/4704)

https://m.facebook.com/Brain-Print-1585272778401091/ (https://m.facebook.com/Brain-Print-1585272778401091/)
The National Security Agency (NSA) leads operations at the facility as the executive agent for the Director of National Intelligence.
It is located at Camp Williams near Bluffdale, Utah, between Utah Lake and Great Salt Lake and was completed in May 2014 at a cost of $1.5 billion.
https://en.m.wikipedia.org/wiki/Utah_Data_Center (https://en.m.wikipedia.org/wiki/Utah_Data_Center)

Any Questions?

http://www.lifecoachcode.com/2016/05/28/the-father-of-fractal-geometry-reveals-the-pattern/ (http://www.lifecoachcode.com/2016/05/28/the-father-of-fractal-geometry-reveals-the-pattern/)

In the computer software world, open source software concerns the creation of software, to wIntelligence.
https://en.m.wikipedia.org/wiki/List_of_artificial_intelligence_projects (https://en.m.wikipedia.org/wiki/List_of_artificial_intelligence_projects)

https://m.facebook.com/Artificial-Genocide-1716276305283944/ (https://m.facebook.com/Artificial-Genocide-1716276305283944/)

https://m.facebook.com/Doomsday-Computers-AGI-ASI-516866275144461/ (https://m.facebook.com/Doomsday-Computers-AGI-ASI-516866275144461/)

https://m.youtube.com/watch?list=PL9DCCHoTYZ8KaMFrLrUzNblMsIECi9vQ0&v=g1lVBNV6ztw (https://m.youtube.com/watch?list=PL9DCCHoTYZ8KaMFrLrUzNblMsIECi9vQ0&v=g1lVBNV6ztw)

#NBIC #DualUseTechnology #HBP #LofarLois #Ericsson #IBM #SGI #Raytheon #NSA #MilitaryNanoTechnology #BrainInitiative #NeuroEthics

hich access to the underlying source code is freely available.
This permits use, study, and modification without restriction.
In computer security, the debate is ongoing as to the relative merits of the full disclosure of security vulnerabilities, versus a security-by-obscurity approach.
There is a different (perhaps almost opposite) sense of transparency in human-computer interaction, whereby a system after change adheres to its previous external interface as much as possible while changing its internal behaviour.
That is, a change in a system is transparent to its users if the change is unnoticeable to them.
https://en.m.wikipedia.org/wiki/Transparency_(behavior) (https://en.m.wikipedia.org/wiki/Transparency_%28behavior%29)

All Human's are Computers in Ubiquitous Computing that are monitored by Artificial Intelligence/Ambient

By mindcontroleurope • Posted in Implant for Synthetic Telepathy, military, Mind Control, Nano Brain Implant, Nano ICT Brain Implants • Tagged artifical-intelligence, blood, brain-computer-interface, doctor, intelligence-gathering, magnus olsson, mind control, poland, post doctoral research, waves, world cach
AUG 5 2016

Assassination is the murder of a person, often (but not or ruler, usually for political reasons or paymen. Or the common man.

Assassination is the murder of a person, often (but not always) or ruler, usually for political reasons or paymen. Or the common man.

(https://nanobrainimplant.com/2016/08/05/assassination-is-the-murder-of-a-prominent-person-often-but-not-always-or-ruler-usually-for-political-reasons-or-paymen-or-the-common-man/brain-control-2/)

An assassination may be prompted by, political, or military motives; it is an act that may be done for financial gain, to avenge a grievance, from a desire to acquire fame or notoriety, or because of a military, security or insurgent group's command to carry out the homicide.

The World Coalition against Covert Harassment is committed to raising awareness to the legal systems as well as to the medical and scientific community to the crime of illegal biomedical and weaponry research committed on citizens in the European Union and beyond. As a European network, EUCACH acts as a lobbying and advocacy platform towards the EU. Using our international network of scientific and technology experts, partner civil and human rights organisations as well as important stakeholders in civil society, we provide consultancy services to the EU Institutions based on our expertise. EUCACH's organisational goal is to influence EU legislation and the decision-making process in calling for a worldwide ban on weapons that might enable any form of manipulation of human beings.

Online-connected brains and neural networks.

"ICT" = Information and Communication Technologies

"BMI" = Brain Machine Interface, brain-computer interconnection

"FET" = Future and Emerging Technologies

"S.T." = Synthetic Telepathy

"A.I." = Artificial Intelligence.

On the road to mind control: DARPA's new program will use a chip to connect brains.For additional background to the latest press release from DARPA posted in full below, I encourage you to read the following selection of linked articles
where I discuss the scope and chronology of what is being studied. Therein, you will find that the U.S. BRAIN Initiative and its European counterpart, the Human Brain Project, are not spending multi-billions of dollars on neuroscience research
simply to help people with Post Traumatic Stress Disorder and organic brain dysfunction. It is, perhaps first and foremost, a military endeavor that has wide ramifications if even 1/10th of what is being studied comes to fruition. In short, it's more about mind control than it is about brain restoration and improvement. Please keep this in mind when you read DARPA's emphasis on "new therapies." •Obama Doubles Down on BRAIN Project and Military Mind Control

•Mind Control Scientists Find New Memory Manipulation Technology
•Secret DARPA Mind Control Project Revealed: Leaked Document
•The 9 Goals of Mind Control: Interim Report
•New Mind Reading Research Aims to Synchronize Humans
•Nanoparticles Enable Remote Control Brains Via Magnetic Field: New Study

DARPA Press Release:

(https://nanobrainimplant.com/2014/12/17/disturbing-weapons-now-being-used-on-the-masses/darpa/)

A new DARPA program aims to develop an implantable neural interface able to provide unprecedented signal resolution and data-transfer bandwidth between the human brain and the digital world. The interface would serve as a translator, converting between the electrochemical language used by neurons in the brain and the ones and zeros that constitute the language of information technology. The goal is to achieve this communications link in a biocompatible device no larger than one cubic centimeter in size, roughly the volume of two nickels stacked back to back.

The program, Neural Engineering System Design (NESD), stands to dramatically enhance research capabilities in neurotechnology and provide a foundation for new therapies.

“Today’s best brain-computer interface systems are like two supercomputers trying to talk to each other using an old 300-baud modem,” said Phillip Alvelda, the NESD program manager. “Imagine what will become possible when we upgrade our tools to really open the channel between the human brain and modern electronics.”

Among the program’s potential applications are devices that could compensate for deficits in sight or hearing by feeding digital auditory or visual information into the brain at a resolution and experiential quality far higher than is possible with current technology.

Neural interfaces currently approved for human use squeeze a tremendous amount of information through just 100 channels, with each channel aggregating signals from tens of thousands of neurons at a time. The result is noisy and imprecise. In contrast, the NESD program aims to develop systems that can communicate clearly and individually with any of up to one million neurons in a given region of the brain.

Achieving the program’s ambitious goals and ensuring that the envisioned devices will have the potential to be practical outside of a research setting will require integrated breakthroughs across numerous disciplines including neuroscience, synthetic biology, low-power electronics, photonics, medical device packaging and manufacturing, systems engineering, and clinical testing. In addition to the program’s hardware challenges, NESD researchers will be required to develop advanced mathematical and neuro-computation techniques to first transcode high-definition sensory information between electronic and cortical neuron representations and then compress and represent those data with minimal loss of fidelity and functionality.

To accelerate that integrative process, the NESD program aims to recruit a diverse roster of leading industry stakeholders willing to offer state-of-the-art prototyping and manufacturing services and intellectual property to NESD researchers on a pre-competitive basis. In later phases of the program, these partners could help transition the resulting technologies into research and commercial application spaces.

To familiarize potential participants with the technical objectives of NESD, DARPA will host a Proposers Day meeting that runs Tuesday and Wednesday, February 2-3, 2016, in Arlington, Va. The Special Notice announcing the Proposers Day meeting is available athttps://www.fbo.gov/spg/ODA/DARPA/CMO/DARPA-SN-16-16/listing.html. More details about the Industry Group that will support NESD is available athttps://www.fbo.gov/spg/ODA/DARPA/CMO/DARPA-SN-16-17/listing.html. A Broad Agency Announcement describing the specific capabilities sought is available at: http://go.usa.gov/cP474 (http://l.facebook.com/l.php?u=http%3A%2F%2Fgo.usa.gov%2FcP474&h=LAQF0y59EAQFQR18F27x04gXa7Y_rindsR25iSKphNuN6zA&enc=AZOpn7sJYv1piS9gSXGfy_NqXsCO7oB0S40
wwq-BZaaREHQxwob2U8UXt8kfaCnxig3GT6vilhS7K6HhnYGtn9hKAUxHcqAYyBQ8RvfuBKDruex9_vs-icDjhjTswRnvlZiuFpTbFop5HBD3RZ38KhQmXzcBN3gFvyHixaG5LgtM-FvdH37Galx8Kne2oujUkZt3E&s=1).

DARPA anticipates investing up to $60 million in the NESD program over four years.

NESD is part of a broader portfolio of programs within DARPA that support President Obama’s brain initiative. For more information about DARPA’s work in that domain, please visit:http://www.darpa.mil/…/our-r…/darpa-and-the-brain-initiative (http://l.facebook.com/l.php?u=http%3A%2F%2Fwww.darpa.mil%2Fprogram%2Four-research%2Fdarpa-and-the-brain-initiative&h=HAQECCJXjAQEZD2OkSMYSVL85yN-3EkJvVb9bU9LzVZeKmQ&enc=AZNCWwf9R2i6Uy5lFdfkj6UBSyM39uSN_sZKmEQN0J14oy0ih7JhkHYCtvqG0N0PmELXHOuKdGmXs9kWiHDiy7ubLMS
cr3v6PcjPMVGzyRQND8fQLFaQwZVkVqmre58u3yG7h1NdxM8L8zYhn-_5v&s=1).

FET and ICT research and development (of the new “computer – brain language”) allows computers to read and learn human thought patterns by using injectable brain – machine – interface.

About the same brain-machine interface has has been used to cure Parkinson’s disease , Alzheimer’s and depression can also be used for accessing the brain’s memory.



(https://nanobrainimplant.com/2016/08/05/assassination-is-the-murder-of-a-prominent-person-often-but-not-always-or-ruler-usually-for-political-reasons-or-paymen-or-the-common-man/brain-mind-e/)

Digital Mind

Professor Goran Hermerén OPINION OF THE EUROPEAN GROUP ON ETHICS IN SCIENCE AND NEW TECHNOLOGIES TO THE EUROPEAN COMMISSION (ETHICAL ASPECTS OF ICT IMPLANTS IN THE HUMAN BODY) March 2005

Link to document

The new software for the brain-machine interface in nano electronics combined with "Europe's new information technology" provides the researchers with the possibillities for reading and taking "software images" of the brain's neuron network.

A method that provides high-resolution copies of the brains cognitive behavior and human perception.

Tomorrow's high-speed computers and related research has evolved into a sophisticated "computer game" with "mind reading" on real people….

These research methods are unknown to our society's legal system!

So how can research on the brain by "serious" (criminal) organizations in ICT-FET be stopped?

SYNTHETIC TELEPATHY for medicine or mind reading is a direct communication with nanoelectronics between computer and human brain.

Synthetic telepathy is a communication system based on thought, not speech.

It can be used to control for example a prosthesis and cure diseases such as Parkinson's disease but can also decode the patterns used to study cognitive behavior such as memory, learning and emotion. With nano technology, the digital information can be recorded using the new quantum-inspired computers.

Simulation of behavior can be identified and provide diagnostic data for identifying the precursors to diseases such as dementia, stroke and myocardial infarction

This letter is intended to demonstrate a paradox in the Swedish so-called "protection of human rights" and thus the entire Swedish justice system. Synthetic telepathy could, as practiced in Sweden, lie behind an unknown number of violent crimes and suicides due to research deliberately kept hidden from regulators.

Doctors and psychiatrics diagnose people with "voices in his head" following their "manuals". DSM-IV (Diagnostic and Statistical Manual of Mental Disorders) published by the American Psychiatric Association and the ICD-10 (International Statistical Classification of Disorders and Related Health Problems).

This is an old-fashioned black and white and diagnose when the EU priority FET ICT research and develop new information technologies adapted to nano-electronics.

mind-control-weapons

Ulf Gorman writes in the book that with nano technology, we open the doors to an unknown area where we do not know how to apply ethics. What should be and what should not be allowed when you implant a chip that can both read and influence the brain? He takes the example of studying learning and memory.

Micro Implants can provide unprecedented opportunities to understand how we learn and remember things, and hence why we forget and find it difficult to learn. And it can be understood as a form of abuse to look like that into our most private mental world.

Lund University writes about the development of nano-electrodes that can both listen and communicate with neuronal synapses and their cell membranes.

EU priority ICT and FET research are talking about a "A whole new communication technology in Europe" "It will help us understand and exploit the ways in which social and biological systems, organization and evolution, will pave the way for the development of new opportunities for next-generation software and network technologies ".
To understand how the human brain works not only leads to innovations in medicine but also provides new models for energy, fault-tolerant and adaptive computing technologies ".
An initiative of the Virtual Human Physiology that are individually tailored and virtual simulations of the human body where you would expect enormous progress in disease prevention and health care.
The pioneering work carried out also on new ideas such as artificial living cells, synthetic biology, chemical communication, collective intelligence and two-way interface between brain and machine.

(https://nanobrainimplant.com/2016/08/05/assassination-is-the-murder-of-a-prominent-person-often-but-not-always-or-ruler-usually-for-political-reasons-or-paymen-or-the-common-man/new-brain-2/)

Brain reading

Cleansing the Blood (Lungs)

Pale green/white and tangerine/white chi work as cleaning agents for the blood. Diseases of the blood and arteries can be treated. The chi first energises the lungs and as the blood passes through them, it takes in the chi, thus becoming purified. The benefit is then carried to the rest of the body as the blood circulates. Serious infections can also be treated in this way; however, the technique should not be used on women who are pregnant.



A. ***B.***

Fig. 6.17 A. *Cleansing the Blood and emptying the Lungs.*
B. *Become aware your Three Tan Tiens. Connect to the Universe and ask for 'the Power to See'.*

Outline for Cleansing the Blood/Lungs



1. Scan the student.
2. Push through and open the lungs from the back to the front.
3. When the lungs need to be given energy, use pale green/white followed by pale tangerine/white chi beginning at the front and moving top the rear.
4. To make weak patients stronger, cerise/white chi can be employed as this will bring energy into the lungs.
5. Purification of the blood is carried out by the liver, kidneys and spleen. Use white chi to bring energy to these areas, after first pushing and pulling through them.
6. The blood requires a lot of cleaning on a regular basis.
7. Energize with white Chi. **Germs can only grow in the dark. 'Fill yourself with the light'.**

Other sources, e.g The UCI (University of California Irvin. Department of Cognitive Science) describes the development of Synthetic Telepathy:

Collaboration between cognitive science, neuro-science, specialists in speech recognition and brain imaging will develop a brain-machine interface. This device could help paralyzed and soldiers would be able to send messages directly from the brain to a computer.

Researcher Michael D'Zmura, President of the UCI describes that the system begins with "the little voice in your head".

How can a medical diagnosis unequivocally describe people's perception of voices in their head and that no alternative can exist except mental disease.

Why? -because it is a prerequisite to be able to "hear" voices for the use of new information technology?

This is why these researchers must be forced to go public and announce this new scientific communication technology.

This paradox must be investigated immediately.With the exclusion of the development of a Swedish and European military force with superior two-way "radio" communication with the brain.



(https://nanobrainimplant.com/2012/07/11/scientists-humans-and-machines-will-merge-in-future/imagescaygmuja/)

A number of past court cases are more or less directly caused by S.T. This "voice to skull" technology must immediately be taken into consideration as an alternative for triggering a number of previously committed violent crimes and suicides.

During the development of BMI, software and network technologies are also computerized and long distance imaging of peoples cognitive behavior and perception. Material that is recorded in the computer that runs the real time simulation and creation of artificial intelligence (for initializing A.I. and computerized decision making.)

The image of the brain's "machine-code" is probably the most comprehensive and advanced ever made. Cognitive behavior depicted and simulated, language and meaning of the words for the subjects are identified. Human perception and mapping how the brain handles information, the image of mathematics reached its perfection.

neuron wave A new research scandal and the fatal consequences for the wider community.

Around the clock the computerized study goes on using collective, artificial intelligence and self-learning systems. The victims testimonies tells us that you can sadly conclude unequivocally that the studies will not be completed until the victim in one way or another has been broken down and / or otherwise inactivated.

This provides power to simulate decomposition for the digital copy thus the fact that the criminal research will not end and is never disclosed.

Descriptions to the vulnerable people who eat psychotropic drugs due to their experiences the experiments and testing goes on, various medicines can affect the "test objects" (or guinea pigs) everything is recorded and compared with previous values (from the multi-annual copy of their real-time neural network and thus the registration of their behavior.)

Obviously this is a disgusting and illegal way to meet the advanced development of tomorrow's medicine.

The "studies" have resulted in enormous damage to many subjects.The number of unrecorded victims/subjects is probably very high.Families are fragmented, the children of these families are suffering tremendously. One of the subjects have recently been hospitalized with a cracked skull, caused by disconnecting the balance system remotely. The accident occurred in public settings.

A new research scandal and the fatal consequences for the wider community.

To influence the balance system is another typical example of how technology is used against the victim to incapacitate them for society. Direct assassination attempts on several previous occasions orchestrated by the brain control deliberately strikes out the human balance system, Why this happens is likely as an alternative to the mentally ill to be treated (as "possessed") or having a neurological disease.

(https://nanobrainimplant.com/2012/06/03/2050-and-immortality-is-within-our-grasp/imagescaaztqrn/)

Brain – copying with BMI and broadband access is definitely no longer a marginal research.Employers have over the years lost millions of dollars and cut-downs is to be expected due to excluded employees. Broken families, children who, years later can not study or work is now forced to seek psychiatric care.

Siblings, grandparents and their closest friends are suffering tremendously. Advanced Medical and hospital care due to study design is a mockery of health-care and doctors who are not familiar with this research. Insurance in the multi-million figures was raised through direct damage caused by brain control. Property for millions of dollars are lost.

Injuries and privacy intrusion of thousands of people is done through "volunteers" that serve as multimedia machines i.e node for the recording of all contacts they have, such as politicians, scientists, lawyers, friends, acquaintances, relatives, international business relations, etc..

Security codes, access codes, etc. is with the new technology no longer private.How can we know that people are not equipped with the new brain-machine interface which makes the person a multimedia application with a function as a live missile is already deployed as nodes in the political and financial world of illegal recording of their conversations with the world?

A sinister JOY seems to embrace the researchers and perpetrators over this superior and powerful tool for mind control and copying brainwave patterns. The tool is, without a doubt, a weapon of offense and stealth.

Implant technology in these forms should immediately be classified as a lethal weapon! It communicates directly with the brain's neurons and can bring the entire neural nervous system to a halt.(Exclusion of balance can be immediately implied on a victim.)

The technology is now used for purposes of breaking down the persons psyche, with serious accusations, threats, mock execution, incitement to suicide, physical violence, e.g, decrease and increase heart rate, pain in and around the heart, severe chest pains, sudden and painful headaches, difficulty to breathe, tampering with rectum, prostate and muscles to name a few.

The macabre in the use of this technology is that subjects are exposed to these atrocities while the society is not legally able to influence the situation. Sweden is in this matter a lawless country where the researchers grossly exploit the situation.

(https://nanobrainimplant.com/2013/03/24/brain-control-war-too-big-to-fail/imagescaay7q87/)

Face mind

This ultimate humiliation has reached a whole new level. The researchers tries with the enforced communication and slow decomposition enslave people with exhortations to try to see the individual results of the brain control. One can calculate due to the nature and perennial perspective that there are naturally a unrecorded number of people who have been driven to madness and death with this technology.

There is nowhere the victims can hide or escape the access signals to their thoughts. Scientists simulate with computers, 24/7 365 days a year to break down the subjects and stop them from trying to understand what's happening to them…

A series of grotesque roles played in order to manipulate the brain, threats and statements that are mixed with modern technology. It is also in the researchers' strategy to make the picture unclear for the subjects if they attempt to get an overall picture of who the perpetrator is and the real goals of the research, a military strategy conducted by veterans and experts in the matters.

The disrespectful research performed and visualized in a 3D virtual game world in the researchers' computers, with no ethical boundaries and human rights but with real living human beings as "avatars". It is quite similar to the popular interactive game "The Sims', But this game delivers human reality-based measurement data for research.

Cover-up of brain monitoring technologies means that the crime is waterproof, human rights laws and manipulated by a hidden militant regime researcher with expertise in information technology. In addition, the researchers say they in the dialogue to be the police power which in itself is an extremely serious offense.

For the victims– former high-performance hard-working people with families, children, an orderly life and social contacts. People who all his life been performing taxpayers. Because of a work-related mental fatigue and time on medical therapy sessions with the scientists the opportunity to take advantage of the situation of persons for investigation and contemporary development of the new BMI and brain monitoring technologies.

As these technologies and opportunities are not announced, but several instances re-written, must be able to use knowledge and skills which are available. Sweden is a small country and the people engaged in this activity may not be so difficult to identify and stop.

The researchers in these studies have assumed the right that during the permanent reproduction of human neurotransmitters in the long term also destroy them and their life's work. The issue is called for; How affected society to know that the violent crime and suicide has been performed in the Stockholm area and Europe in recent years and clearly diagnosed as being caused by mental illness with the voices in heads is an expression of pure brain research!

By: Magnus Olsson

(https://nanobrainimplant.com/2013/04/23/nsa-mind-control-and-psyops-2/nsa/)

HOW WE DO IT…

- Awareness-raising campaigns to disseminate information and mobilise public opinion on the issue of covert technologies and techniques that enable the manipulation of human beings
- Providing expert consultancy to key decision-makers on the creation of appropriate EU legislation to protect citizens from this kind of covert crimes.
- Organising networking events (workshops, seminars, conferences) involving all actors concerned to exchange experiences and best practices for the establishment of clear ethical boundaries to strictly regulate the use of systems enabling the manipulation and control of human beings.

It is our philosophy that all men are equal before the law. Everybody's right to life shall be protected. Nobody shall be subjected to torture or held in slavery. Any technologies and techniques capable of endangering the human physical and/or psychological health, to modify the individuals' autonomy and affect their dignity should be strictly prohibited.

Read more about ICT – implants at the European Group on Ethics and New Technologies:

http://ec.europa.eu/…/european-group-eth…/docs/avis20_en.pdf (http://ec.europa.eu/bepa/european-group-ethics/docs/avis20_en.pdf)

Terminology used in the document:

Cybernetics,,,,,, // Magnus Olsson

EPSC – European Commission (http://l.facebook.com/l.php?u=http%3A%2F%2Fec.europa.eu%2Fbepa%2Feuropean-group-ethics%2Fdocs%2Favis20_en.pdf&h=YAQGijSpj&enc=AZMq9f7N-rRi1oqozQeUDtiMrtgkAjH0PKPRaj0LR7nx44ZZmRLHC78kpg1NdCUG2ACxLZxzxYSdqtdeKAhL_RSUBcFCA0LkDQJxno5Rq7aQMwWo3MtKGZPGl3Id990LNnmKm_llFA98bTSAsGUrtrY&s=1)
EPSC
ec.europa.eu
By: Magnus Olsson (Sweden)

By mindcontroleurope • Posted in Computerbrain, Implant for Synthetic Telepathy, military, Mind Control, Uncategorized • Tagged artifical-intelligence, brain, brain implant, brain implants, cross sectional area, electrical resistance, eu brain, intelligence-gathering, magnus olsson, military / medical classified research, mind, transcranial-magnetic-stimulation
JUL 7 2016

Worldcach.com's Leo Angesleva (Sweden) about Mind Control and the Transhumanist Agenda and Alfred Webre

Alfred Lambremont Webre, Worldcach.com's Leo Angesleva (Sweden) about Mind Control and the Transhumanist Agenda

Interview with Alfred Lambremont Webre, Worldcach.com (http://worldcach.com/)'s Leo Angesleva details how the "Obama" [read "U.S."] Brain Project and the U.S. Army, along with other agencies covertly committed to the Transhumanist Agenda, are facilitating AI Artificial Intelligence reading and controlling all human brains and minds worldwide, and constructing Cyborg armies.

MAN VERSUS MACHINE

(https://nanobrainimplant.com/2012/08/22/ibm-get-close-to-mimicking-a-human-brain/imagescast4tl3/)

WORLD CACH
The World Coalition Against Covert Harassment

(https://nanobrainimplant.com/2016/07/07/alfred-lambremont-webre-worldcach-coms-leo-angesleva-sweden/world-cach/)

By mindcontroleurope • Posted in Computerbrain, Man vs Machine, military, Mind Control • Tagged Alexander, artifical-intelligence, brain-computer-interface, cyborg, Cyborg-soldier, eucach, hologram, Leo, magnus olsson, mind control, nano brain, transcranial-magnetic-stimulation, world cach
MAR 4 2016

Magnus Olsson launches World Coalition against transhumanist neural robotoid agenda

Magnus Olsson launches World Coalition against transhumanist neural robotoid agenda

<iframe width=”640″ height=”360″

World Coalition against Covert Harassment (WorldCACH)

(https://nanobrainimplant.com/2013/02/11/are-people-superfluous/jj/)

STATEMENT OF GARY OWEN

It was Sunday 28th of February 2016, Magnus Olsson was staying at my house in Spain, I had been appointed the Vice President of World CACH 2 days before. We were planning the roll out of the World CACH, deciding the agenda of the organisation, we had a great day on the Saturday, we appointed the technical director, spoke to one of our legal team Alfred Lambremont Webre, he’s the guy that won the war crimes tribunal against Tony Blair and George Bush. We explained that what we wanted to do with World CACH was to set up a Global Intelligence Service that acts for the people against the Governments and security services that no longer represent the people, and take the Masons who have infiltrated all levels of the government and security Services to the war crimes tribunal for genocide and racketeering against the population of earth. He thought both ideas were sensational and invited us to go on his show the following day, which would go out to 250,000 people.

On the Sunday, I started hearing the high pitched noise again in my ear I had not heard it for a few days, since Magnus arrived, and all of a sudden it was back along with the voice to skull. We were to meet for lunch with some people and later talk on Skype with William Binney and then do the show with Alfred where we would break the news to the world about what we were doing. It was only 30 minutes to the lunch meeting and I had heard nothing from Magnus, so I went down to the apartment he was staying in below my house. I knocked on the door and he answered saying he needed medical help, he was in a terrible state. He was physically shacking none stop, and his face was bright red with a high temperature.

(https://nanobrainimplant.com/links/globe1001-2/)

After some phone calls we decided to go to the emergency Chemist and get some pain killers and antibiotics as it looked like a virus. The Chemist said we should go to the emergency doctors in the town, by this time I was having to support Magnus while he walked, he was on the verge of passing out none stop.

Four doctors in the emergency room at Torrox looked at him and did all the tests they could and found nothing wrong. But they agreed something was wrong, so we were dispatched to the main hospital in Valez. I arrived at the emergency entrance, Magnus was no longer able to walk, they put him in a wheel chair. He was fading in and out and incoherent. After 2 hours we got to see a very proficient doctor, he was very thorough. Magnus had come round a little after drinking two litres of cold water. I thought the worst was over, Magnus was dispatched for X-rays and 12 blood tests, we did the X-rays first, no problems, then we went to do the blood tests, half way through taking the blood, they took a lot of blood, about 6 tubes, all of a sudden Magnus took a severe turn for the worse, it started by Magnus telling me that he was going to pass out. I tried to explain this to the Spanish nurse. Then he went as white as snow, all over, his face was pure porcelain white and I noticed that his hands were the same. I was instructed by the nurse to wave his hat in front of his face to try and revive him, his eyes rolled back into his head and you could only see white eyes and a white face it was shocking. By this time the nurse was in a sheer panic and the doctor that had seen him was called.

Before the doctor could arrive, Magnus started to have muscle spasms all over his body, they started on his spine, and spread all over, he was put on a gurney and was contorted and jerking all over the place with his eyes rolled back in his head. It was clear he would die of a heart attack if they did not stop it, they pressed the emergency button and doctors came from everywhere, he was wheeled at speed to the ICU Critical Emergency ward. They stripped of his cloths and by now there was a dozen people trying to figure out what was wrong.

I heard the original doctor tell the others that Magnus was working with CIA whistle blowers, we had explained a bit about the organisation to the doctor during the initial examination. They dismissed it and moved on, they could find nothing wrong. They injected him with Diazepam a strong muscle relaxant. He was in critical for two hours, during the first part I took a picture, I had taken several others, so I could put them on the World CACH facebook site later.

The last photo I took one of the doctors went crazy and threatened me to take no pictures and if any of the pictures I had taken were made public I would be charged by the police. This escalated and security arrived, one more sensible doctor said would you be OK to delete them, as you're not allowed to take photos in a Spanish hospital. There were no signs saying you couldn't.

I agreed to delete them rather than be arrested, I was taken to the public waiting room, three hours went by. A man arrived and told me I could visit Magnus, I was taken through, he was looking better but had an oxygen mask on, and was drained. I was told that in a few hours provided he remained stable he could leave, he was put on an intravenous antibiotic and saline drip. They dosed him up with the anti-biotics and gave me a prescription for a weeks long course and some diazepam in case the spasms started again.

After 7 hours in there we left, Magnus was back but very weak. The doctors told me that every test they did showed nothing, everything was exactly normal through the whole process. They agreed something was wrong but they did not know what it was. The whole day I had a strong high pitched noise whistling in my ear that is part of the Gangstaklking they are perpetrating on people now.

You have to ask yourself about the coincidences involved.

1/ Magnus and I were not being attacked like normal until we decided to Form a Global Intelligence Service for the people against the governments. Then we were both attacked.

2/ Nothing was found to be wrong with Magnus at all.

3/ That day we were to go on video and announce the plan to the TI world.

4/ We were making significant progress on the roll out of World CACH, talking to the leaders around the world of the individual country CACHs. Appointing the technical director. Getting the war tribunals accepted by a judge.

On the way home I started to wonder if we could not get the images back from the camera so I asked a young tech guy Alex Axon to see if it was possible, and a few hours later he had recovered three images and all the thumb nails. They were a bit degraded but we now have the images.



(https://i2.wp.com/newsinsideout.com/wp-content/uploads/2016/03/Magnus-Olsson-atHospital-ICU-Critical-Room-Feb.-28-2016.jpg?ssl=1)

Magnus Olsson at Hospital ICU Critical Room – Feb. 28, 2016

Magnus in ICU Critical Unit

What a day!

Gary Owen

World Coalition against Covert Harassment (WorldCACH)

By mindcontroleurope • Posted in Implant for Synthetic Telepathy, Magnus Olssons story, military, Mind Control, Nano Brain Implant, Uncategorized • Tagged airforce, artifical-intelligence, artificial telepathy, interfaces, magnus olsson, Nanobots, science, synthetic-telepathy, technology, transcranial-

magnetic-stimulation
JAN **28** 2015

The real-life Mind-Matrix…

(https://nanobrainimplant.files.wordpress.com/2015/01/mail-on-line.png)The real-life Matrix: MIT researchers reveal interface that can allow a computer to plug into the brain

(https://nanobrainimplant.files.wordpress.com/2015/01/fgnfgjtyjty.jpg)

- **System could deliver optical signals and drugs directly into the brain**
- **Could lead to devices for treatment of conditions such as Parkinson's**

It has been the holy grail of science fiction – an interface that allows us to plug our brain into a computer.

Now, researchers at MIT have revealed new fibres less than a width of a hair that could make it a reality.

They say their system that could deliver optical signals and drugs directly into the brain, along with electrical readouts to continuously monitor the effects of the various inputs.



Christina Tringides, a senior at MIT and member of the research team, holds a sample of the multifunction fiber that could deliver optical signals and drugs directly into the brain, along with electrical readouts to continuously monitor the effects of the various inputs.

HOW IT WORKS

The new fibers are made of polymers that closely resemble the characteristics of neural tissues.

The multifunction fiber that could deliver optical signals and drugs directly into the brain, along with electrical readouts to continuously monitor the effects of the various inputs.

Combining the different channels could enable precision mapping of neural activity, and ultimately treatment of neurological disorders, that would not be possible with single-function neural probes.

‘We’re building neural interfaces that will interact with tissues in a more organic way than devices that have been used previously,’ said MIT’s Polina Anikeeva, an assistant professor of materials science and engineering.

The human brain’s complexity makes it extremely challenging to study not only because of its sheer size, but also because of the variety of signaling methods it uses simultaneously.

Conventional neural probes are designed to record a single type of signaling, limiting the information that can be derived from the brain at any point in time.

Now researchers at MIT may have found a way to change that.

By producing complex fibers that could be less than the width of a hair, they have created a system that could deliver optical signals and drugs directly into the brain, along with simultaneous electrical readout to continuously monitor the effects of the various inputs.

RELATED ARTICLES

The newC technology is described in a paper in the journal Nature Biotechnology.

The new fibers are made of polymers that closely resemble the characteristics of neural tissues, Anikeeva says, allowing them to stay in the body much longer without harming the delicate tissues around them.

To do that, her team made use of novel fiber-fabrication technology pioneered by MIT professor of materials science Yoel Fink and his team, for use in photonics and other applications.

The result, Anikeeva explains, is the fabrication of polymer fibers ‘that are soft and flexible and look more like natural nerves.’

Devices currently used for neural recording and stimulation, she says, are made of metals, semiconductors, and glass, and can damage nearby tissues during ordinary movement.

‘It’s a big problem in neural prosthetics,’ Anikeeva says.


© Melanie Gonick/MIT

The result, Anikeeva explains, is the fabrication of polymer fibers ‘that are soft and flexible and look more like natural nerves.

HOW IT WORKS

The new fibers are made of polymers that closely resemble the characteristics of neural tissues.

The multifunction fiber that could deliver optical signals and drugs directly into the brain, along with electrical readouts to continuously monitor the effects of the various inputs.

Combining the different channels could enable precision mapping of neural activity, and ultimately treatment of neurological disorders, that would not be possible with single-function neural probes.

‘We’re building neural interfaces that will interact…



(https://nanobrainimplant.files.wordpress.com/2013/02/robot-brain.jpg)

- The result, Anikeeva explains, is the fabrication of polymer fibers 'that are soft and flexible and look more like natural nerves.'

'They are so stiff, so sharp — when you take a step and the brain moves with respect to the device, you end up scrambling the tissue.'

The key to the technology is making a larger-scale version, called a preform, of the desired arrangement of channels within the fiber: optical waveguides to carry light, hollow tubes to carry drugs, and conductive electrodes to carry electrical signals.

These polymer templates, which can have dimensions on the scale of inches, are then heated until they become soft, and drawn into a thin fiber, while retaining the exact arrangement of features within them.

A single draw of the fiber reduces the cross-section of the material 200-fold, and the process can be repeated, making the fibers thinner each time and approaching nanometer scale.

During this process, Anikeeva says, 'Features that used to be inches across are now microns.'

Combining the different channels in a single fiber, she adds, could enable precision mapping of neural activity, and ultimately treatment of neurological disorders, that would not be possible with single-function neural probes.

For example, light could be transmitted through the optical channels to enable optogenetic neural stimulation, the effects of which could then be monitored with embedded electrodes.

© PUBLICITY PICTURE

Combining the different channels in a single fiber, she adds, could enable precision mapping of neural activity, and ultimately treatment of neurological disorders, that would not be possible with single-function neural probes.

At the same time, one or more drugs could be injected into the brain through the hollow channels, while electrical signals in the neurons are recorded to determine, in real time, exactly what effect the drugs are having.

MIT researchers discuss their novel implantable device that can deliver optical signals and drugs to the brain, without harming the brain tissue.

The system can be tailored for a specific research or therapeutic application by creating the exact combination of channels needed for that task. 'You can have a really broad palette of devices,' Anikeeva says.

While a single preform a few inches long can produce hundreds of feet of fiber, the materials must be carefully selected so they all soften at the same temperature.

The fibers could ultimately be used for precision mapping of the responses of different regions of the brain or spinal cord, Anikeeva says, and ultimately may also lead to long-lasting devices for treatment of conditions such as Parkinson's disease.

John Rogers, a professor of materials science and engineering and of chemistry at the University of Illinois at Urbana-Champaign who was not involved in this research, says, 'These authors describe a fascinating, diverse collection of multifunctional fibers, tailored for insertion into the brain where they can stimulate and record neural behaviors through electrical, optical, and fluidic means.

The results significantly expand the toolkit of techniques that will be essential to our development of a basic understanding of brain function.'

Read more: http://www.dailymail.co.uk/sciencetech/article-2927410/The-real-life-Matrix-MIT-researchers-reveal-interface-allow-computer-plug-brain.html#ixzz3Q9lDVQv4 (http://www.dailymail.co.uk/sciencetech/article-2927410/The-real-life-Matrix-MIT-researchers-reveal-interface-allow-computer-plug-brain.html#ixzz3Q9lDVQv4)

By mindcontroleurope • Posted in Computerbrain, Implant for Synthetic Telepathy, Mind Control • Tagged ai, artifical-intelligence, bioelectronics, brain, brain-computer-interface, human brain, mind control, mit, research, science, synthetic-telepathy
FEB 8 2014

Medical Nanobots Will Connect Brain to Cloud Computing – Ray Kurzweil

Thursday, February 6, 2014

Medical Nanobots Will Connect Brain to Cloud Computing – Ray Kurzweil (http://www.activistpost.com/2013/08/the-dna-nanobots-have-arrived.html)

(https://nanobrainimplant.files.wordpress.com/2013/05/mbj.jpg)

Update on the emergence of DNA nanobots and nanocomputers.

Nicholas WestThe Human Body Version 2.0 (http://lifeboat.com/ex/human.body.version.2.0#nanobots) project features none other than arch-Transhumanist Ray Kurzweil (http://www.amazon.com/The-Singularity-Is-Near-Transcend/dp/0143037889/ref=as_li_tf_sw?&linkCode=wsw&tag=permacultucom-20) as its main proponent. The goals have been openly stated for some time:

Circulatory/Heart System General



One of the basic problems pertaining to the circulatory system and heart is hypertension and hypotension. Once again, the sacrum and solar plexus are involved. The sacrum controls the bones; indirectly, it stimulates the marrow and enhances the quality of the blood. Good blood is like running the highest quality motor oil through the engine of a motor vehicle.

(Within the Universal Tao System we also have the view that the sacrum controls the Chi-pulse. If there is enough Chi, the heart does not have to work so hard, because the Chi pushes the blood).

The solar plexus relates to the emotions, affecting the heart through two mechanisms:

- It may affect the heart directly, causing rhythmic disturbance or pressure around the heart muscle
- Malfunction in the liver or digestive tract, leading to high cholesterol levels or gas which pushes up towards the heart from the intestines and causes unwanted heat and pressure.

Cleaning out the Solar Plexus will greatly improve these conditions. If you have been trained in Chi Nei Tsang you can use it in combination with the Cosmic Healing techniques.

Specific

Working on the Heart Muscle:
Clean out the Solar Plexus as outlined above. Push and pull with green and blue.
Detoxify the liver, flush with green.
Enhance with white and violet light.
Use the finger to work on the lower left and upper right part of the heart.
Remember that the heart muscle is very delicate.
You draw the force, you spiral and you push.
Stabilize with white.
For enlarged heart use blue.
Carefully use the red light to balance the blood and open the blood vessels.
Sweep the sacrum with green, red and blue.
Sweep the solar plexus with green, blue, red, white and violet.
Energize and cool down the throat center, using blue.
Working on Hypertension (High Blood Pressure):

> *In the coming decades, a radical upgrading of our body's physical and mental systems, already underway, will use nanobots to augment and ultimately replace our organs. We already know how to prevent most degenerative disease through nutrition and supplementation; this will be a bridge to the emerging biotechnology revolution, which in turn will be a bridge to the nanotechnology revolution. By 2030, reverse-engineering of the human brain will have been completed and nonbiological intelligence will merge with our biological brains.*


Nanotech data storage memory system
Metabrain
Error correction device - instant data replay and feedback
Network sonar sensors map data onto visual field
Solar protected skin with tone - texture changeability
Increased frequency range, parabolic hearing
Cardio flow and function monitor
Turbocharged suspension flexibility
In vivo fiberoptic communications backbone
Smart Skin
Internal wholebody navigational grid
biosensors externally stimulate atmospheric tensions
Replacement organs
primo posthuman

(https://nanobrainimplant.files.wordpress.com/2014/02/ef606-primo_posthuman.png)

Picture from Natasha Vita-More

Link to Vita-More: http://www.natasha.cc/ (http://www.natasha.cc/)

In fact, the reverse engineering of the human brain (http://www.activistpost.com/2013/08/hardware-and-software-combining-to.html) has already been announced to be well under way via new microchips and accompanying software. And, while full nanobot rewiring of the brain is not expected before 2020, Phys.org (http://phys.org/) has reported that our DNA has been successfully targeted by nanobots "for drug therapy or destruction."

Taking this even one step further, Ray Kurzweil said in a new interview with *The Wall Street Journal* (see below) that our extension into non-biological realms will include nanobot computers that will enter our brain and connect us to Cloud computing.

From science fiction horror, directly to the human body, the nanobots are no longer speculation. Also unlike science fiction, they won't arrive via immediate worldwide takeover — they are already here, and will be introduced incrementally, as Kurzweil has previously stated:

> *It will be an incremental process, one already well under way. Although version 2.0 is a grand project, ultimately resulting in the radical upgrading of all our physical and mental systems, we will implement it* ***one benign step at a time****. Based on our current knowledge, we can already touch and feel the means for accomplishing each aspect of this vision. (emphasis added)*



DEEP BRAIN STIMULATION Researchers at the Cleveland Clinic have treated patients with obsessive-compulsive disorder by inserting a pacemaker in the chest that shoots electrical pulses to the brain. To the doctors' surprise, two-thirds of the patients in a small trial scored much higher on memory tests after the treatment.

MIND OVER MATTER At Brown University, a small number of paralyzed patients have had chips implanted in their brains that detect neural signals. The chips are wired to computers programmed to carry out certain tasks the patients think about performing. After training on this system, some patients were able to move a cursor on the computer screen simply by thinking about doing so.

MEMORY CHIPS Doctors treating stroke patients who suffer from memory loss would like to replace damaged brain tissue with semiconductors. Working with rats, a team of scientists led by the University of Southern California's Theodore W. Berger learned how neurons responsible for memory react to varying patterns of electrical stimulation. They've turned those reactions into equations on chips, which will soon be implanted in a rat's hippocampus. The chips receive signals from one set of healthy brain cells, process them digitally, and pass them along to other healthy cells—taking over the function of damaged tissue. One day, chips might boost memory capacity in healthy brains as well.

HERDING NEURONS At the far reaches of brain research, scientists are learning to turn individual neurons on and off at will, raising hopes for quelling disturbing events in the mind and promoting useful ones. Edward Boyden, professor of neuroengineering at MIT, uses colored light on genetically engineered brain cells in mice. When exposed to a fast pulse of blue light, the neurons in the brain switch on; a yellow flash turns them off. Medical applications might include treating Parkinson's tremors or epileptic fits by switching off swaths of diseased tissue. But the technique also could let researchers pinpoint and study those sets of neurons that control cognitive functions such as decision-making. The end result could be the ability to identify, flick on, and coordinate whole networks of neurons to enhance specific cognitive skills.

(https://nanobrainimplant.files.wordpress.com/2014/01/mndcntrl-2.jpg)

Researchers from Columbia University have developed a fleet of molecular *nanorobots* that can deliver drugs to specific cells and also identify certain genetic markers by using fluorescent labeling. After such identification, a chain reaction can be initiated:

> *On cells where all three components are attached, a robot is functional and a fourth component (labeled 0 below) initiates a chain reaction among the DNA strands. Each component swaps a strand of DNA with another, until the end of the swap, when the last antibody obtains a strand of DNA that is fluorescently labeled.*
>
> *At the end of the chain reaction—which takes less than 15 minutes in a sample of human blood—only cells with the three surface proteins are labeled with the fluorescent marker.*

Naturally, this type of targeted therapeutic approach (http://medicalxpress.com/news/2013-07-molecular-robots-therapeutics.html#inlRlv) could prove beneficial, as the researchers highlight — especially for cancer treatment which sweeps up healthy cells along with malignant ones, very often doing more harm than good (if one were to choose the establishment medical route).



Vaccination Is Not Immunization
Tim O'Shea
Why doctors don't vaccinate their own kids
Read More>>

(http://activistpost.net/vaccinetruth.html)

This is always how new technologies are sold to the public, however, and it would be naive not to consider the darker applications as well.

Direct brain modification already has been packaged as "neuroengineering." A Wired article (http://www.wired.com/science/discoveries/news/2009/03/neuroengineering1) from early 2009 highlighted that direct brain manipulation via fiber optics is a bit messy, but once installed "it could make someone happy with the press of a button." Nanobots take the process to an automated level, rewiring the brain molecule by molecule. Worse, these mini droids can autonomously self-replicate, forcing one to wonder how this genie would ever be put back in the bottle once unleashed.

Here is one scenario offered by Kurzweil for how these nanobots could enter our bodies:

> *A significant benefit of nanobot technology is that unlike mere drugs and nutritional supplements, nanobots have* ***a measure of intelligence****. They can keep track of their own inventories, and intelligently slip in and out of our bodies in clever ways. One scenario is that we would wear a special "nutrient garment" such as a belt or undershirt. This garment would be loaded with nutrient bearing nanobots, which would make their way in and out of our bodies through the skin or other body cavities. (emphasis added)*

That might seem to offer a level of participatory choice — to wear or not to wear the garment — but Kurzweil reveals that the nanobots will eventually be everywhere:

> *Ultimately we won't need to bother with special garments or explicit nutritional resources. Just as computation will eventually be ubiquitous and available everywhere, so too will basic metabolic nanobot resources be embedded everywhere in our environment.*

In a recent interview with *The Wall Street Journal*, Kurzweil highlights why Google has taken an interest in nanotechnology and the possibilities he sees for humans as they increasingly become non-biological and form direct connections with computers, augmenting and/or supplanting our natural processes as we head into the era of cyborgs (http://www.activistpost.com/2014/01/the-era-of-cyborgs-has-begun.html) and beyond:

And of course once our neocortex is uploaded to the Cloud, it positions Google perfectly for searching our every thought and pre-thought. While this might sound like an impossible amount of information to upload, let alone interconnect and search, it is being announced that researchers have designed the first nanocomputer that can push beyond the concept of Moore's Law, which imposes a theoretical limitation on the expansion of computer processing power.

> *The team designed and assembled, from the bottom up, a functioning, ultra-tiny control computer that is the densest nanoelectronic system ever built.*
>
> *A technical paper has been published online (http://www.pnas.org/content/early/2014/01/23/1323818111.abstract) in the Proceedings of the National Academy of Sciences on the research.*
>
> *The ultra-small, ultra-low-power control processor—termed a* ***nanoelectronic finite-state machine (http://en.wikipedia.org/wiki/Finite-state_machine)*** *or "nanoFSM"—is smaller than a human nerve cell.*
>
> *[…]*
>
> *In their recent collaboration they combined several tiles on a single chip to produce a first-of-its-kind complex, programmable* ***nanocomputer****. (Source (http://www.33rdsquare.com/2014/02/nanocomputer-points-way-to-push-past.html))*


TeslaSecret
Complete Step-By-Step Instruction On
HOW TO BUILD A
NIKOLA TESLA FREE ENERGY DEVICE
CLICK HERE NOW!
(http://activistpost.net/teslasecret/)

It shouldn't be seen as coincidence that these developments are happening simultaneously. What appears on the surface to be discoveries in entirely different fields are coalescing rapidly as we approach the theoretical date of The Singularity – the full merger of human and machine – estimated to occur between 2029-2045.

Despite the benign language of futurists, we know that a concerted effort is already underway to manage and predict human behavior (http://www.activistpost.com/2013/07/secret-darpa-mind-control-project.html) for a whole range of potentially anti-human applications (http://www.activistpost.com/2013/06/7-future-methods-of-mind-control.html). As our free will is also targeted like the cells of our body — for drug therapy or elimination — ethical concerns must be voiced loud and clear. Scientists seem content with opening Pandora's Box, then worrying about negative consequences later … and that is only if we assume that their intentions are benign from the beginning. One should take time to examine the history of military experimentation on human populations (http://www.amazon.com/The-Medusa-File-Coverups-Government/dp/0963906240/ref=as_li_tf_sw?&linkCode=wsw&tag=permacultucom-20) to see all of this through a very different lens.

At the very least, instead of the fully realized vision of Human Body 2.0, this might be Big Pharma 2.0 — a new phase where conventional drugs are incrementally replaced by nanodrugs (http://www.sciencedaily.com/releases/2013/08/130810063717.htm) and nano-fleet delivery systems. Coupled with applications that directly enter our brain to connect us to the computer matrix, we are rapidly entering an entirely new human paradigm.

The funding is already there, and a massive amount of money is waiting to be made by companies like Google. Here again, for those who might only see the bright side to this technology, we ought to question who is really in control of it.

Sources:
http://phys.org/news/2013-08-dna-nanorobots-tag-cellular.html (http://phys.org/news/2013-08-dna-nanorobots-tag-cellular.html)
http://www.nature.com/nnano/focus/dna-nanotechnology/index.html (http://www.nature.com/nnano/focus/dna-nanotechnology/index.html)
http://www.nature.com/nnano/journal/v8/n8/index.html (http://www.nature.com/nnano/journal/v8/n8/index.html)
http://blogs.wsj.com/cio/2014/02/04/googles-ray-kurzweil-envisions-new-era-of-search/ (http://blogs.wsj.com/cio/2014/02/04/googles-ray-kurzweil-envisions-new-era-of-search/)

Recently by Nicholas West:

- Robots to Breed with Each Other and Humans by 2045 (http://www.activistpost.com/2014/01/robots-to-breed-with-each-other-and.html)
- Robots to Get Internet Cloud Brain: "Wikipedia For Robots" (http://www.activistpost.com/2014/01/robots-to-get-internet-cloud-brain.html)
- Amazon Patents The Use Of Predictive Behavior Technology For Future Shipments (http://www.activistpost.com/2014/01/amazon-patents-use-of-predictive.html)

By mindcontroleurope • Posted in Implant for Synthetic Telepathy, Man vs Machine, Mind Control • Tagged artifical-intelligence, artificial telepathy, biological brains, chemical stimulus, cloud-computing, DNA nanobots, medical nanobots, Nanobots, nonbiological intelligence, science, trans humanist, transcranial-magnetic-stimulation
JAN **17** 2014

Mind Control in the 21st Century

Mind Control in the 21st Century—Science Fiction and Beyond

(http://www.veteranstoday.com/wp-content/uploads/2014/01/mind-control2_banner.jpg)

Mind Control in the 21st Century—Science Fiction & Beyond

… by Steven DiBasio

Understanding
MIND
CONTROL
(http://www.veteranstoday.com/wp-content/uploads/2014/01/51vrpnPx+jL.jpg)

Is it coming to a home near you?

Conspiracy Theory?

"Mind control" is a topic commonly perceived as "conspiracy theory" or "X-Files" fare. That is, it is seen as possibly not "real," and certainly not something about which one should be "overly" concerned.

This attitude at least partially arises from the widespread belief or assumption that the human brain is so complicated—("the most complex entity in the universe" is a common formulation)—that it has not, and perhaps cannot, be comprehended in any depth.

One writer, for example, describes the brain as of "perhaps infinite" complexity,[1] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn1) while another, David Brooks of the *New York Times*, writes that it is "probably impossible" that "a map of brain activity" could reveal mental states such as emotions and desires.[2] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn2)

Similarly, Andrew Sullivan, blogger and former editor of *The New Republic*, opines that neuroscience is still in its "infancy," and that we have only begun "scratching the surface" of the human brain, and links to a *New Yorker* piece in support of that position.[3] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn3)

And the cover story for the October 2004 issue of Discovery Magazine entitled "The Myth Of Mind Control" advises the reader that while mind control is a "familiar science-fiction" staple, there is little reason for real concern, because actually deciphering the "neural code" would be akin to figuring out other "great scientific mysteries" such as the "origin of the universe and of life on Earth," and is therefore hardly likely.[4] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn4)

According to the article, as the brain is "the most significant mystery in science" and quite possibly "the hardest to solve,"[5] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn5) mind control remains at worst a distant concern.

The underlying idea seems to be that sophisticated mind control is unlikely without understanding the brain; and we do not understand the brain.

(http://www.veteranstoday.com/wp-content/uploads/2014/01/mindcontrol.gif)

Understanding the "Neural Code"

Of course, one might question the notion that a full understanding of the "neural code" is a prerequisite for mind control since it is not always necessary to know how something works for it to be effective. Nonetheless, the assumption that the brain is so complex that little progress has been made in "solving" it is itself incorrect.

As neuroscientist Michael Persinger has said, the "great mythology" of the brain is that it is "beyond our understanding; no it's not."[6] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn6) In fact, according to inventor and "futurist" Ray Kurzweil, "very detailed mathematical models of several dozen regions of the human brain and how they work…."[7] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn7) had already been developed over a decade ago.

Kurzweil also said at that time that science is "further along in understanding the principles of operation of the human brain than most people realize…."[8] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn8) While the brain may be complicated, "it's not *that* complicated (emphasis added)."[9] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn9)

Similarly, an Air Force report from 1995, in a section entitled "Biological Process Control," predicts that before 2050 "… [w]e will have achieved a clear understanding of how the human brain works, how it really controls the various functions of the body, and how it can be manipulated…:"[10] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn10)

> ***One can envision the development of electromagnetic energy sources … that can couple with the human body in a fashion that will allow one to prevent voluntary muscular movements, control emotions (and thus actions), produce sleep, transmit suggestions, interfere with … memory, produce an experience set, and delete an experience set. [11] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn11)***

As disturbing as such "predictions" may be, is it possible that technologies to prevent (or perhaps even impel) muscular movement, control emotions, transmit suggestions, delete memories, create false memories, and so on, have already been developed?

Certainly, even a cursory review of the "open literature" reveals that various sophisticated mind control technologies already exist.[12] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn12) Indeed, it is rather shocking to realize how advanced mind control technology was, even several decades ago.

(http://www.veteranstoday.com/wp-content/uploads/2014/01/PTSD1.jpg)

"Altering brain waves"

For example, there is the 1974 invention of Robert G. Malech for which a patent was granted in 1976 and assigned to defense contractor Dorne & Margolin, Inc.—for a method of "remotely monitoring and altering brain waves."[13] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn13)

Moreover, experiments conducted over thirty years ago at the Stanford Research Institute (SRI) showed that basic mind reading from EEG readouts was possible, revealing the existence of "a non-symbolic language" of "brain-wave patterns" which could be deciphered and translated.[14] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn14)

Indeed, "…[b]y the late 1960s … 'remote control' of the human brain—accomplished *without* the implantation of electrodes—was well on its way to being realized."[15] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn15) A means of stimulating a brain "by creating an electrical field completely outside the head" was developed,[16] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn16) and it was discovered that electric pulses could stimulate the brain using far less energy than previously "thought … effectual in the old implanting technique."[17] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn17)

Not surprisingly, with such developments arose legitimate fears of a future world where "human robots" would perform the bidding of the "military."[18] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn18)

And one source quotes a 1970s Pentagon agency report as saying that it will likely be possible in "several years" to induce sounds and words directly into the brain (bypassing the ears), as well as to use "combinations of frequencies and other signal characteristics to produce other neurological effects….,"[19] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn19)

The report notes that the Soviets had observed "various changes in body chemistry" and "functioning" of the brain from the exposure of the brain to various frequencies.[20] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn20) Also mentioned are studies at MIT showing that "magnetic brain waves can be picked up … and amplified as if the brain were a radio transmitter," no implants or electrodes required.[21] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn21)

Finally, an article from 1981 describes how "microwave generators" placed in appropriate locations and transmitting at low energy would create "interference patterns" out of the interaction with brainwaves (brain electricity).

These interference patterns "could then be built up by computer into a three-dimensional moving picture of mental processes"—in other words, a remote "thought scanner" (and tracking device) could be developed.[22] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn22)

Recent "Advances"

(http://www.veteranstoday.com/wp-content/uploads/2014/01/crazy.jpg)

Subjected to outside influences

In light of these past developments, it is perhaps rather surprising to read modern articles describing supposedly recent innovations in "mind reading" and mind control technology – in which it is sometimes claimed, for example, that scanners, electrodes and proximity to the subject is required to read and "control" minds.

Such claims reflect an apparent failure of the science of "mind control" to progress as one might have expected considering the presumed interest, as well as the spectacular rate of advancement of science and technology in general in recent decades.

Of course, it would not be all that surprising if mind control technology has advanced considerably, but that research has been carried out in secret for reasons of "national security."

CIA affiliated scientists have certainly conducted much research which they have been prohibited from sharing with their peers,[23] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn23) and inventions that implicate "national security" are routinely suppressed under Pentagon secrecy orders.[24] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn24) Also, it might seem desirable to hide research programs which sometimes "require" relaxation of ethical standards, such as that of informed consent.

That said, even ignoring the likely existence of a "secret science" of mind control, recent public advancements are quite troubling in their own right.

Some examples:

6S
6S
22
2E
3M
24
3M
130
(http://www.veteranstoday.com/wp-content/uploads/2014/01/th.jpg)

"New connections" are being made all the time.

1) In 2004, 25,000 rat neurons on a glass dish learned to fly an F-22 jet fighter simulator.[25] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn25) After scientists placed the neurons on the dish, the neurons quickly began "to reconnect themselves, forming a living neural network—a brain."[26] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn26)

The lead scientist added that "one day," though of course a "long way off," disembodied brains might actually be used to fly drones,[27] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn27) though the current experiment was merely to enhance knowledge of how the brain works, and possibly provide "clues to brain dysfunction."[28] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn28)

2) In August 2013, researchers revealed that "miniature" human brains had been grown in the laboratory.[29] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn29) As is typical, any negative implications or reasons for worry were minimized, while possible "therapeutic" uses were highlighted. Thus, the breakthrough was hailed as a great opportunity to understand "developmental defects." Though the writer does mention "the spectre of what the future might hold," the reader is reassured that the research is "primitive territory"[30] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn30)—though one researcher did comment on the "undesirability" of growing larger laboratory brains.[31] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn31)

3) On July 1, 2013, a magazine reported a claim by neuroscientist Sergio Canavero that it was now feasible to transplant the head of one human to the body of another and reattach the spinal cord.[32] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn32)

4) Scientists have reconstructed random images viewed by subjects, from fMRI brain scans, in research that "hints" that "one day" scientists might be able to "access dreams, memories and imagery…."[33] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn33)

5) The brains of two rats have been linked, such that one, located in North Carolina, responded "telepathically" to the thoughts of the other, located in Brazil.[34] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn34) The second rat's brain processed signals from the first rat's brain, delivered over the internet, as if they were its own. The scientist speculated about the "future possibility" of a "biological computer, in which numerous brains are connected…."[35] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn35)

6) A brain-to-brain interface has been created, allowing humans to move a rat's tail just by thinking about it.[36] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn36) Readers are told that while it is not yet possible to "communicate brain to brain with our fellow humans … we may be on our way to … controlling" other species.[37] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn37) But, since it is "still very early days" the writer "hope(s)" that any ethical concerns can be "iron(ed) out."[38] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn38) Of note, the study used focused ultrasound to deliver impulses to the rat's brain.[39] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn39)

7) Continuing the ultrasound "theme": Focused pulses of low intensity low frequency ultrasound, transmitted noninvasively through the skull to the human brain, have been shown capable of producing, not only pain, but also sound, as well as evoking "sensory stimuli."[40] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn40) Accordingly, a lab with a "close working relationship" with DARPA, the Department of Defense, and U.S. Intelligence communities, has been looking into using pulsed ultrasound to encode "sensory data onto the cortex"; in other words, producing hallucinations through the remote and direct stimulation of brain circuits.[41] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn41) Possibilities are the ability to "remotely control brain activity" and the "creation of artificial memories."[42] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn42) Even Sony has gotten in on the act, patenting a device for using ultrasound to produce hallucinations—again described as "transmitting sensory data directly into the human brain."[43] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn43) Most troublingly, one source recently alleged that the NSA is using this ultrasound technology to target individuals through their smartphones.[44] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn44)

8) A researcher was able to make a fellow researcher in a different office move his finger just by thinking about it, in the "first" demonstration of a human brain-to-brain interface.[45] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn45)

9) A low cost means of tracking people, even through walls, has been developed. While in the past individuals could be tracked anywhere by the "military" using radar technology, this technology might enable entities with fewer resources to track people as well.[46] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn46)

 (http://www.veteranstoday.com/wp-content/uploads/2014/01/mindcontrol_nano-testing_crop.jpg)

10) Scientists have remote controlled a worm by implanting magnetic nanoparticles into it, and then exposing the animal to a "radiofrequency magnetic field" which stimulated its neurons. The scientists suggest that their research could lead to "innovative cancer treatments" and "improved diabetes therapies," as well as

11) Americans can now be spied on in their homes through their internet-connected appliances, according to (former) CIA Director David Petraeus.

Petraeus made his statements at about the same time a huge microchip company, ARM, unveiled new processors which will connect home appliances such as refrigerators, washers and driers to the internet.[48] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn48)

12) LED lights have been ostensibly pushed for their efficiency over traditional bulbs. However, LED lights are also semiconductors capable of inducing "biological and behavior effects."[49] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn49)

"Breakaway" Science?



 (http://www.veteranstoday.com/wp-content/uploads/2014/01/stress-510010.jpg)

Nural Codes

While the aforementioned public developments are quite concerning, the reality is they may not actually represent the true state of the art in "mind control" technology.

It would not be that surprising, after all, for a domain with national security implications to at some point in its development branch off onto separate "tracks," one public and the other "hidden."

If such a bifurcation were to occur, advancements made in secret would not necessarily be incorporated into the public sphere. Eventually perhaps, innovations and breakthroughs would result in the development of an essentially new, covert science.

An example of a domain in which this bifurcation process seems to have occurred is aviation. In the public sphere, the most advanced aircraft might well be the F-22 fighter jet, or perhaps the F-35. However, if insider testimony is credited, these aircraft seem almost primitive in comparison with flying machines developed in secret.

Perhaps the most compelling statements in this regard come from Ben Rich, former Director of Lockheed-Martin's Advanced Development Projects, or "Skunk Works," a Lockheed division notable for its super high-tech, top secret projects, among them the U2 spy plane and the SR-71 Blackbird.

As Joseph P. Farrell's reports in his book *Saucers, Swastikas, and Psyops*, Rich made a number of peculiar and provocative comments at the end of his career, and following his retirement on December 31, 1990 (prior to his death five years later), comments strongly hinting at "the development of … an off-the-books physics and technology…."[50] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn50)

For example, on September 7, 1988, in a presentation to the American Institute of Aeronautics and Astronautics in Atlanta, Georgia, Rich lamented that he was prohibited from discussing Skunkwork's current projects, but he did say that they "call for technologies once only dreamed of by science fiction writers."[51] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn51)

In ensuing years, Rich elaborated slightly. For instance, while speaking to the UCLA School of Engineering Alumni Association in 1993, Rich said that "an error in the equations" had been discovered and corrected, making it possible "to travel to the stars."[52] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn52) He added, however, that "these technologies are so locked up in black programs, that it would take an act of God to ever get them out to benefit humanity."[53] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn53)

100 YEARS OF ACCELERATING TOMORROW

(http://www.veteranstoday.com/wp-content/uploads/2014/01/Ben-Rich-Ftr.jpg)

Ben Rich – Who saw it it…lived it all.

Farrell goes on to relay a statement from an unnamed Lockheed retired engineer who was quoted in a magazine article in 1988 as saying that "we have things flying in the Nevada desert that would make George Lucas drool."[54] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn54) In the same article an Air Force officer involved in the development of the SR-71 said "[w]e are testing vehicles that defy description.

To compare them conceptually to the SR-71 would be like comparing Leonardo da Vinci's parachute design to the space shuttle." And a retired Colonel chimed in: "We have things that are so far beyond the comprehension of the average aviation authority as to be really alien to our way of thinking." [55] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn55)

Consider then for a moment the possibility that within the classified world, in 1993, a technology, to quote Ben Rich, "to take ET back home" had already been developed.[56] (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/#_ftn56) The implications are enormous, not to mention rather frightening. One wonders where the technology must be in 2014, more than twenty years later.

And if the aforementioned statements are true, and this seems plausible (why would these individuals lie, or even exaggerate, especially to Engineering Associations and Aeronautics institutes), what might this imply about the current state of the art in domains other than aviation, such as neuroscience, which has itself been the subject of intense "weaponization" efforts.

Indeed, what does such a vast discrepancy between what people believe and what is actually true suggest about the nature of our perceived reality in general?

Steven DiBasio is a writer, attorney, and sometime musician. He lives in the Midwest. And more will be on the way. He can be reached at: steven.dibasio@gmail.com (mailto:steven.dibasio@gmail.com)

Editing: Jim W. Dea (http://www.veteranstoday.com/staff-writers/)

Original: http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/ (http://www.veteranstoday.com/2014/01/13/mind-control-in-the-21st-century-science-fiction-beyond/)

By mindcontroleurope • Posted in Implant for Synthetic Telepathy, military, Mind Control • Tagged artifical-intelligence, artificial telepathy, brain-computer-interface, microwave, military, mind control, nsa, radio-engineering, transcranial-magnetic-stimulation
JAN 5 2014

NSA Spy Program Is Absolutely Orwellian Intelligence

The EMF Brain Mapping Of The People And Its Use As Part Of A Signals Intelligence Driven Spy Program Is Absolutely Orwellian



(https://nanobrainimplant.files.wordpress.com/2014/01/44.png)

Former US National Security Agency contractor Edward Snowden appeared in a televised Christmas message released to the world public by TV station Channel 4 on Wednesday. (Dec. 25)

Investigative Journalists Targeted For An Ongoing **FBI COINTELPRO STING OPERATION/SMEAR CAMPAIGN** — been used as an unwitting target of (MKULTRA) non consensual human experimentation for decades via the **NSA's SIGNALS INTELLIGENCE EMF Scanning Network – a covert spy program which uses brain scanners deployed via NSA signals intelligence satellites to remotely scan the brainwaves of any citizen in the world.** The NSA's SIGNIT EMF Scanning Network is an outgrowth of the Pentagon and CIA's MIND and TAMI (MKULTRA) "mind control" programs, which use EEG Heterodyning technology to synchronize AI computers with the unique brainwave print of each citizen. This technology enables the NSA to brand us like heads of cattle. Google: AKWEI VS NSA & The Matrix Deciphered by Dr. Robert Duncan to learn more about this Orwellian attack on the people's Constitutional rights.

By mindcontroleurope • Posted in Man vs Machine, Mind Control • Tagged artificial intelligence, artificial telepathy mind, b, Brain Implants for MIND/BRAIN CONTROL, brain-computer-interface, Implant for Synthetic Telepathy, military, nsa, orwell, snowden, transcranial-magnetic-stimulation

Powered by WordPress.com.

Overactive adrenals/ kidneys often cause hypertension. Clean out the solar plexus first, because the adrenals (T11) are connected to it. The adrenal glands produce adrenaline, the hormone that stimulates the heart to pump. Overactive adrenal glands will eventually affect the heart.
Tune-up the Door of Life with blue, calming it.
Take the pressure from the heart, use green.
Energize the heart, use violet.
Flush down from head to feet with blue;
The basic problem with hypertension is that the Chi goes up and cannot come down. Work on the sacrum, using orange and yellow.

Working on Hypotension (Low Blood Pressure):
In hypotension the Door of Life and T11 are underactive.
First clean out the Solar Plexus, this time focus on removing blocks or stuck energy.
Energize the Door of Life, using green and red.
Energize the Sacrum (same colors).
Energize the Base of Skull with green and violet.

Stomach Pains

Pass your hands over the patient and brush the whole abdomen, especially the solar plexus, navel and lower abdomen. The navel should be treated with a combination of green and blue, and blue should be used at the end to firm up the energy.

If problems persist: A) Treat with Chi Nei Tsang B) Seek the advice of a qualified medical practitioner.

Relieving Pain: *Blue Chi*

Chi that is associated with the colors blue and green can be utilized in different ways. While green chi acts to free up energy that has become ‘sick’ and ‘stuck’, blue chi can act as a painkiller because of its ability to reduce the severity of pain.

1. Push and pull the through the affected part out to the universe or ground the sick energy until partial relief is attained.
2. A large amount of pale blue/white chi together with pale green/white chi should be used to transmit energy to the problem area.
3. For the alleviation of pain, use pale green/white chi and pale tangerine/white chi in turn.

Energize means draw the Chi into the part that you want to receive healing. Cleansing means push energy through the affected part and send it out to the universe. Pull the new Chi back into the same area. Light green Chi is used in loosening and cleansing delicate organs like the eyes and the brain.

(/)


TECHNOLOGICAL REVOLUTION
IS NOW
JOIN US IN BUILDING
WAVE MATRIX OF THE FUTURE

HOME / ГЛАВНАЯ (/)

SERVICES / УСЛУГИ (/SERVICES--105910571051105910431048.HTML)

PRODUCTS / ТОВАРЫ (/PRODUCTS--105810541042104010561067.HTML)

CONTACT / КОНТАКТ (/CONTACT--1050105410531058104010501058.HTML)

TESLA PSI-GENERATORS WITH COMPLETE DIGITAL PHARMACY - THE FRONTIER OF QUANTUM GENETICS



You can place an order via filling up **THE ORDER FORM (/order-form.html).** Prices differ depending on the service, client's condition, and disease.

Models of **TESLA PSI-GENERATOR**S differ by the size of the chip (the number of layers). The chip is multilayered and it takes longer than one day to produce just one layer. Our **SUPER**, **ULTRA** and **ULTIMATE PSI-GENERATORS** has twice as much layers than our **BASIC TESLA PSI-GENERATOR**. Production of our **ULTRA** and **ULTIMATE MINI-TESLA PSI-GENERATORS** takes about or longer than one month.

Each model comes in **GENERIC** and **INDIVIDUAL** version. Generic version has the universal human biohologram (aka DIGITAL CELL) encoded via laser into the chip on nano level. And the individualized version has the personal human biohologram encoded via laser into the chip on nano level.

GENERIC TESLA PSI-GENERATORS are produced for large families, who would like to share the same **TESLA GENERATOR** for all members of the family. Generic Human Biohologram, aka DIGITAL CELL, is the result of decades of research, and is the foundation for our diagnostics procedures.

INDIVIDUAL TESLA PSI-GENERATORS have individual biohologram of a client in the chip, being encoded via laser onto the chip on nano level. Individual biohologram is recorded from your childhood photograph (or navel blood / placenta) via laser, digitized, diagnosed, and encoded into the chip via laser.

INDIVIDUAL TESLA PSI-GENERATORS are produced for the ultimate protection against genetic and psychotronic warfare.

Each chip (inside a pendant) comes with the **COMPLETE DIGITAL PHARMACY** as software on a flash drive with 44 modules for every essential bodily organ and physiological system. Market value is 35,000 Euros only one module.

COMPLETE DIGITAL PHARMACY SOFTWARE PROGRAM

All our models of TESLA PSI-GENERATORS (chip) come with a separate flash drive with the complete **DIGITAL PHARMACY** software program for every essential bodily organ and physiological system **(PSI-PROGRAM**) to run on your computer in order to generate **E-DRUGS** / **BIOELECTRONIC DRUGS** (aka wave matrices / biohologram) for every health condition.

SECOND-BIRTH TESLA PSI-GENERATOR

SECOND-BIRTH TESLA PSI-GENERATOR

(a) **has a more advanced, second generation chip encoded by laser on nano level with the most valuable bioholographic information on the global market: EMBRYONIC STEM CELL;**

(b) has a new technology of encoding the chip by the newly invented laser (patented);

(c) layers of the chip are made of a new material of organic nature more advanced than our other chips;

(d) its efficacy is proven by the clinical trials at the Medical Clinic of the Moscow Bauman Russian State Technical University, the most important Science University in Russia, of MIT level. twice as more layers of the chip than the **BASIC MINI-TESLA PSI-GENERATOR.**

(e) has
either **GENERIC** or **INDIVIDUAL** biohologram.

(f) provides the ultimate modulation for the scalar wave diffraction grating for the most precise focus / zero center of the biohologram (aka 'wave crystal") in the process of rejuvenation.

GENERIC MATRIX MINI-TESLA GENERATOR - $3000

INDIVIDUAL MATRIX MINI-TESLA GENERATOR - $3500

BASIC-X TESLA PSI-GENERATOR



SUPER TESLA PSI-GENERATOR



ULTRA TESLA PSI-GENERATOR



ULTIMATE TESLA PSI-GENERATOR



BASIC TESLA PSI-GENERATOR (chip)

(a) has twice less layers of the chip than our other models**.**

(b) has either the **GENERIC** or **INDIVIDUAL** biohologram of a healthy human in the chip, being encoded via laser onto the chip on nano level.

(c) **BASIC TESLA PSI-GENERATOR** has both sides of the casing for the chip made of Real Solid Pearl.

(d) **BASIC-X TESLA PSI-**

SUPER MINI-TESLA GENERATOR (chip)

(a) has twice as more layers of the chip than the **BASIC MINI-TESLA PSI-GENERATOR.**

(b) has either **GENERIC** or **INDIVIDUAL** biohologram.

(c) Both sides of the casing for the chip are made of Real Solid Pearl.

GENERIC SUPER MINI-TESLA GENERATOR - $1179

INDIVIDUAL SUPER MINI-TESLA GENERATOR - $1768

MATRIX TESLA PSI-GENERATOR

MATRIX TESLA PSI-GENERATOR

(a) has twice as more layers of the chip than the **BASIC MINI-TESLA PSI-GENERATOR.**

(b) has either **GENERIC** or **INDIVIDUAL** bioh

ULTRA MINI-TESLA GENERATOR (chip)



ULTIMATE MINI-TESLA GENERATOR (chip)

(a) has twice as more layers of the chip than the **BASIC MINI-TESLA PSI-GENERATOR.**

(b) has either **GENERIC** or **INDIVIDUAL** biohologram.

(c) One side of the casing for the chip is made of Real Solid Pearl, and another side of casing is made of 3D printing plastic, encoded with the

GENERATOR has one side of the casing for the chip made of Real Solid Pearl, and another side of casing made of 3D printing plastic, encoded with the immune system rejuvenation **E-DRUG** (**BIOELECTRONIC DRUG** / **DIGITIZED BIOHOLOGRAM**). This makes **"TWO-CHIPS IN ONE"** solution.

GENERIC BASIC MINI-TESLA GENERATOR - $856

INDIVIDUAL BASIC MINI-TESLA GENERATOR - $1179

INDIVIDUAL BASIC-X MINI-TESLA PSI-GENERATOR - $1534

ologram.

(c) Both sides of the casing for the chip are made of 3D printing plastic, encoded with the immune system rejuvenation **E-DRUG** (**BIOELECTRONIC DRUG** / **DIGITIZED BIOHOLOGRAM**). This makes **"TWO-CHIPS IN ONE"** solution.

GENERIC MATRIX MINI-TESLA GENERATOR - $2122

INDIVIDUAL MATRIX MINI-TESLA GENERATOR - $2947

(a) has twice as more layers of the chip than the **BASIC MINI-TESLA PSI-GENERATOR.**

(b) has either **GENERIC** or **INDIVIDUAL** biohologram.

(c) One side of the casing for the chip is made of Real Solid Pearl, and another side of casing is made of 3D printing plastic, encoded with the immune system rejuvenation **E-DRUG** (**BIOELECTRONIC DRUG** / **DIGITIZED BIOHOLOGRAM**). This makes **"TWO-CHIPS IN ONE"** solution.

GENERIC ULTRA MINI-TESLA GENERATOR - $1768

INDIVIDUAL ULTRA MINI-TESLA GENERATOR - $2358

RNA **E-DRUG**(**BIOELECTRONIC DRUG** / **DIGITIZED BIOHOLOGRAM**) for the ultimate protection against psychotronic and genetic warfare. This makes **"TWO-CHIPS IN ONE"** solution.

GENERIC ULTIMATE MINI-TESLA GENERATOR - $2358

INDIVIDUAL ULTIMATE MINI-TESLA GENERATOR - $2712 (promotional price)

MINI-TESLA GENERATOR

MANUAL FOR MINI-TESLA PSI-GENERATOR

ABOUT THE DEVICE

The device consists of two parts: a chip in a pendant and a computer program (software) on a flash drive.

CHIP:

The user wears a pendant with a chip inside on his/her neck at the level of the solar plexus. We have chips of first and second generation. First generation chip is an artificial polymer crystal with electret properties, which has two modules, depending on how you turn it towards your body: open module (reinforcing the impact of a user on the environment) and closed (protecting a user from the harmful effects of the environment). Second generation chip (more advanced) has the entirely holographic technology, and functions through the focus / zero center of the scalar wave diffraction grating in the hologram encoded into the chip via laser on nanolevel.

Chips are structured by laser at the nano level. The laser writes to the chip at the nano level client's digitized biohologram, which is read by the laser from the childhood photograph, placenta or umbilical cord blood of the client for the individual generators, or the biogologram of a average healthy person for the generic generators.

When user is wearing the chip, the electret is emitting the wave crystalline structure (hologram or matrix) upon the user, and makes his chromosomes repeat the wave crystalline structure of a healthy person during cell division.

The laser and chip itself use the principle of Kozyrev Mirrors. The Universe consists of energy for 93%, and of particles only for 7%, and particles are the concentrated energy. The universe is holographic, that is, it is entirely in its every Matrix Point. Wave Hologram or Matrices exist in two forms: in the form of a Torus (simultaneously present from the infinitely small to the infinitely large dimensions) and in the form of the Wave Crystal. Man exists in the form of a Torus during sleep. During waking hours, the person is in the form of a Wave Crystal.

Wave Crystals are formed in the structures, which reproduce in their shape the Kozyrev Mirrors. Kozyrev Mirrors reflect any external wave signal, and, therefore, are called "mirrors". These structures neutralize any external linear signal, and refract it towards their Zero Center or focus. Neutralization of any external signal happens due to the reflection of the wave and the polarization, and the creation of a so-called standing (scalar wave). Trough of the back-running wave neutralizes the peak of the forward-going wave, when the initial wave is reflected. This provides protection from harmful electro-magnetic and other technogenic or anthropogenic influences.

As a result of the standing (scalar) wave, there emerges the interference (diffraction) grating, which refracts any next linear signal line towards the center (focus) of the Wave Crystal.

It is necessary to know this, because all the information in the universe is transmitted and received only through the Zero Center of the Wave Crystal. This is analogous to the work of our eye. We see only because there is the gathering

"PSI" stands for "psychotronic", that is, for the technology that is offering technical means for managing biosystems.

Every **MINI-TESLA psi-generator** comes with

(1) a **CHIP**, structured with a laser on a nano-level with the digitized Wave Matrix / Biohologram of healthy human or your own individual wave matrix in childhood (recorded from your childhood photograph), and cased either in pearl or 3-D printing plastic, or combination of these two materials. You wear it on a chain on your solar plexus all the time, taking it off only for bathing;

(2) and psi-program - a flash drive with the software that has the entire **DIGITAL PHARMACY** generated as the holographic / granulated signal (aka "white noise" - signal beyond your auditory perception) and encoded in music. You are getting the complete **DIGITAL PHARMACY** for your lifetime and for every system and vital organ in your body. You run this software at least once a day for best results. If you are sick, you run this software as often as possible.

All sales upon agreeing to c**lient consent conditions** (/client-consent.html), no refunds.

(/order-your-mini-tesla-generator-russian.html)

Нажмите на Русский флаг для перемещения на версию сайта на Русском языке

Refer to our **FAQ (Frequently Asked Questions) (/mini-tesla-generator-faq.html)** for any concerns.

IMPORTANT: CHIP has two modes : OPEN and CLOSED. In the **OPEN MODE**, you increase your information-wave impact upon people. The **CLOSED MODE** is the **SHIELD MODE**, which protects you from any psychotronic attack, including V2K (voice to skull) and cancer guns, subliminal advertising and psychic attacks. Those customers who are endangered with these attacks can wear their **CHIP** in the protective mode nonstop. **PLEASE NOTE**: Plastic towards your body is a **SHIELD MODE**. For casing which has both sides from plastic, the **SHIELD SIDE** is thinner so that the chip is noticeable beneath plastic. For casing which has both sides from Pearl, the darker side of Pearl towards your body is the **SHIELD MODE**.

DIGITAL PHARMACY SOFTWARE PROGRAM (/digital-pharmacy-software--1057105410601058-10621048106010561054104210541049-1040105510581045105010481048.html)

of all the external linear signals in the focus of the lens (Wave Crystal). If focus is not achieved, and the refraction of the signal takes place before or behind the center of the lens, we have developed the long-sightedness (hyperopia), or the long-sightedness (myopia), and we don't see well. Receiving information by both our eye, and our DNA takes place strictly in accordance with the laws of geometrical optics. The technology used for creating the chip is called "Polarized Holography".

It is possible to record and transmit only a holographic signal. To record Wave Crystals (Bioholograms or Matrices) of users, we use devices that can record and transmit holographic signal - He-Ne laser with internal mirrors. These lasers convert any external linear signal into a holographic signal, i.e., changing the nature of the initial signal. For example, our bones produce stem cells only because their shape and structure is analogous to the laser tubes, which "involute" a signal.

Similarly, our DNA is able to transmit and receive information, only because, in its structure, it is the Wave Crystal. Two strands of DNA are literally the standing (scalar) wave, since in the first strand of DNA, a wave goes in the direction opposite to the wave going in the second strand of DNA. Moreover, DNA coils into the crystalline structure, which literally reproduces the interference / diffraction grating of the standing wave in the Kozyrev Mirror, in order to most accurately refract any external linear signal toward the Zero Center / Focus of its Wave Crystal.

We live only thanks to cell division. During cell division, chromosome is formed. A chromosome is formed when two sisters chromatids unite together into a cruciform structure. Chromosomes come in two main shapes: acrocentric and metacentric. In acrocentric chromosomes, two endings of the sisters chromatids are shorter than the other two endings. On the contrary, metacentric chromosome has all the endings the same, so that it is absolutely symmetrical. Metacentric chromosome resembles the quadratic / symmetrical cross (Crux Quadrata / Gammadion), as well as the lens of a well-seeing eye. The same gene in apes, in children with Down syndrome, and wild horses of Przewalski has the acrocentric chromosome, whereas in humans, normal children, and Arabian horses, the same gene has the metacentric shape of the chromosome. That is, the functionality of the species directly depends upon the shape of chromosome, that is, upon the laws of the Polarized Holography of Wave Crystals.

Our device is centering and focusing the chromosomes during cell division, giving them the metacentric form.

Because the entire universe is entirely in its every Matrix Point, each Matrix Point is not simply different from any other Matrix Point, but is unique



Click here (/digital-pharmacy-software--1057105410601058-10621048106010561054104210541049-104010551058104510501048.html) to see screen shots of the DIGITAL PHARMACY SOFTWARE PROGRAM.

Produced according to TU 9444-021-42844321. Certificate # 77, FC.19.944. P.2455.11.00

Our **MINI-TESLA GENERATOR** is used by Russian Special Forces and Olympic Team.

MINI-TESLA GENERATOR is a CHIP (artificial / polymer crystal), structured by laser on a nanolevel, as a collector and retransmitter of wave structures (Matrices or Bioholograms), which functions as a dispenser for WAVE MATRICES (http://www.wavegenome.com/wave-pharmaceuticals.html) within the revolutionary paradigm of LASER POLARIZED BIOHOLOGRAPHY, which is the true WAVE PHARMACEUTICALS (/wave-pharmaceuticals.html) **-- information technology of a new generation. Generator or retransmitter functions like a vibrator, which emits micro vibrations of special kind - scalar wave diffraction grating.**

WAVE MATRICES (http://www.wavegenome.com/wave-pharmaceuticals.html) can be generic or individualised. Wave matrices can be of a human as a whole, of specific bodily system, or of a specific medication.

Comes with the software that has 44 modules of DIGITISED WAVE MATRICES (http://www.wavegenome.com/wave-pharmaceuticals.html) for every bodily system and every vital organ in your body.

E-VIAGRA

Individualized ELECTRONIC CODE for the rejuvenation of your sex function.

FAQ Frequently Asked Questions (/mini-tesla-generator-faq.html)

READ INFORMATION LEAFLET FOR THE MINI-TESLA GENERATOR

(COMES WITH THE UNIT) (/information-leaflet-for-mini-tesla-generator.html)

Over the course of decades, our institute participated in the research in the field of information technologies of a new generation, and their commercialization. The institute created the system of information-energy correction, which is the most advanced in the world, and is the two-way connection through the energy-information cloud. In Russia, our **MINI-TESLA generator** is used by Special Forces and the Olympic Team in order to help them cope with stress and enhance their performance.

(© Irene Caesar, 2012). Each Matrix of each person is the uncreated and indestructible unique nonlocal Wave Matrix. If we have two copies of a unique non-local Wave Matrix, we can instantaneously transfer information from one copy of a unique non-local Wave Matrix to another copy. In this way, birds and insects share one unique non-local Wave Matrix for their entire species, and instantaneously transmit information between all individuals of a given species. But each man has his own unique nonlocal Wave Matrix. If you order an individual generator, you get your unique non-local Wave Matrix with the most clear focus / center of the Wave Crystal. Your generator transmits upon your chromosomes your unique uncreated and indestructible information from the noosphere of the universe. If you order the generic (universal) generator, its action is limited, but it, nevertheless, helps your chromosomes to get centered and focused.

We also offer the remote therapy by the distant laser signal that instantly, through Quantum Non-locality, affects your genetic apparatus according to the principle described above. The user uses his/her individual generator as an antenna and a filter for the remote laser signal.

DIGITAL PHARMACY SOFTWARE

The user uses the computer program (software) every day once a day in a normal state of health, and several times a day, depending on the complexity of his/her state of health. When working with the computer program of the generator, the user must turn his/her generator to the open module.

Computer program of the generator is a comprehensive Digital Pharmacy of the digitized Bioholograms (Wave Crystal structures or Matrices) of all healthy vitally important organs and physiological systems. The user tales a self-test for self-therapy, and the program generates for him the granular (holographic) signal, which is encoded in the music.

Self-therapy is the binaural therapy, which uses the Kozyrev Mirrors principle alike the chip inside the generator. Binaural therapy is based on the effect of the stereo signal to both ears, so that signal is delayed in one ear with respect to the signal applied to the second ear. It is in this way that the Kozyrev Mirrors effect is created, when human skull itself becomes the Kozyrev Mirror. The signal is reflected; there emerges a standing (scalar), the wave interference / diffraction grating; and the signal is refracted toward the Zero Center / focus of the wave crystal.

Also, the user can order any pill or tincture in the form of a software module of the Digital Pharmacy. Digital Pill module is attached to the Digital Pharmacy software, and the user receives the Digital Pill as the granular (holographic) signal encoded in the music. We record the Digital Pill via a laser and as the wave structure (Hologram or Matrix), which is afterwards gets digitized.

DIGITISED WAVE MATRICES (http://www.wavegenome.com/wave-pharmaceuticals.html) also can be either generic or individualised, and of a human as a whole, of a specific bodily system, or of a specific medication.

(/uploads/3/5/1/1/35112207/3881928_orig.png)

The first-generation model of MINI-TESLA PSI-GENERATOR, which combined the chip with the flash drive containing the DIGITAL PHARMACY software.

BASIC MINI-TESLA GENERATOR emits generic **HUMAN CELL HOLOGRAM**, recorded by the laser from healthy human cells and bodily systems, and then used to structure the crystal via the laser on nanolevel.

SUPER, ULTRA, MATRIX AND ULTIMATE MINI-TESLA PSI-GENERATORS emit individual **HUMAN CELL HOLOGRAM** in the form of your childhood wave matrix, which is recorded from your childhood photograph when you were a healthy child. We also need your date of birth. We use the complex systematic approach to read the bioholographic information from your photograph, including the application of laser.

After your matrix is recorded from your photograph, we run a special diagnostic program in our Institute to reveal the defects in your matrix, and to correct them.

If no childhood photograph is available, we can use your adult photograph, since the Institute can diagnose **WAVE MATRICES (http://www.wavegenome.com/wave-pharmaceuticals.html)** and correct them.

We can "record" wave matrices / bioholograms upon various media, and not only on the electret-based chip of the MINI-TESLA PSI-GENERATOR. Examples of such media are CDs that are used "as such", and not for extracting the digital files from them.

We can combine your childhood wave matrix with wave medications.

We can tune up your childhood matrix.



(/uploads/3/5/1/1/35112207/3725345_orig.jpg)

The first-generation model of MINI-TESLA PSI-GENERATOR, which combined the chip with the flash drive containing the DIGITAL PHARMACY software.

MINI-TESLA psi-generator cased in pearl

The second-generation model of MINI-TESLA PSI-GENERATOR, with casing of chip made from Pearl and Wood. Now this model is offered in Pearl for the BASIC MINI-TESLA GENERATOR (chip structured by the laser with the generic biohologram of a healthy human on nano level).

The device is in fact very necessary in modern times when we are bombarded by the harmful electro-magentic radiation.

The device is designed in such a way that you can turn it either with darker-colorer side to yourself, and, in this case, the generator is programmed to open your biofield; or to turn it with the lighter-colored side (aspen side in generators coated in wood) to yourself, and, in this case, the generator becomes your psychotronic "firewall".

IF you are a jet setter, you are receiving a huge amount of radiation each time you fly. Radiation is one of the causes of cancer. That is why our MINI-TESLA GENERATOR is indispensable for jet-setters.

If you get sick, e.g., infected with a virus or bacteria, your wave imprint / data received at the institute will immediately alert the system, and we will correct the situation via sending you the necessary correction to your wave-diagram (available only for **ULTRA MINI-TESLA PSI-GENERATORS)**

Digital Pills do not have the danger of overdose and side effects.

ОЛИМПИЙСКАЯ КОМАНДА РОССИИ
RUSSIAN OLYMPIC TEAM

(/uploads/3/5/4/1/35112207/7731776_orig.gif)
Our MINI-TESLA GENERATOR is used by Russian Olympic Team.

ВОЙСКА
СПЕЦИАЛЬНОГО НАЗНАЧЕНИЯ

(/uploads/3/5/4/1/35112207/1566232_orig.gif)
Our MINI-TESLA GENERATOR is used by Russian Special Forces.

We can tune up your childhood matrix in such a way that some specific bodily systems or organs are stimulated.

SELF-MAINTENANCE

You run software with **PSI-PROGRAM** on your computer in order to perform the self-maintenance as often as you need. **PSI-PROGRAM** has 44 modules for every bodily system and every vital organ in your body. These 44 modules were recorded by the laser from healthy human cells and bodily systems, and, then, digitised.

Software has (1) the chart of bodily systems and organs to choose from for self-maintenance; (2) the scale of self-assessment from the worst to the best; (3) and two biofeedback tests, based upon graphology.

QUANTUM COMPUTER

Besides conventional tests, Institute developed a completely new way of recording and transmitting information. We call it **QAUNTUM BIOINTERNET**.

When you run the **PSI-PROGRAM**, the spin states of the software and the spin states of your crystal / chip in the generator constitute one and the same torus (hologram). There is the instantaneous biofeedback / bioresonance two-way communication between the running software and the crystal inside the **MINI-TESLA PSI-GENERATOR.**

The crystal / nano chip in the **MNI-TESLA PSI-GENERATOR** and the **PSI-RPOGRAM** software (during its operation on your computer) constitute one integrated **QUANTUM COMPUTER**. The spin states of the crystal / nanochip in the generator and the spin states of the software coincide / resonate or oppose each other, according to the principles of the polarised holography. The principles of the polarised holography are expressed by geometrical optics.

The software reads via its own spin states the information off the crystal (its spin states), and corrects it. Then, the crystal tunes via the bioresonance of the spin states to the hologram, corrected by the operating software.

In this way, the crystal / nanochip inside the generator self-corrects itself based upon the operation of this **QUANTUM COMPUTER**.

MAINTENANCE BY WAVE GENOME LLC

(http://www.wavegenome.com/wave-genome---prices.html).

Some bacteria and viruses are considered to be incurable because they leave a wave imprint in the body, even after they are cleared up on the biochemical level. And, then, these wave imprints can literally rebuild the virus and bacteria from scratch. This same principle is seen in the classic physics experiment involving passing photons and molecules through two slits simultaneously. That is why it is necessary to protect and cure oneself on the wave level.

(/uploads/3/5/4/1/35112207/5220735_orig.jpg)
The first-generation model of the MINI-TESLA PSI-GENERATOR, which was approximately 2 inches long, and which was worn at your solar plexus the same way as the new model of the MINI-TESLA PSI-GENERATOR. Both models are invisible when you wear it. The first-generation model had chip and flash drive with the software combined in one piece.

MAINTENANCE VIA QUANTUM INTERNET BY WAVE GENOME LLC

In the case of **QUANTUM INTERNET**, you send your information **REMOTELY** and **WIRELESSLY**. At the WAVE GENOME LLC, the laser reads the feedback from your wave matrix in real time, using your digitised wave matrix on record at the Institute.

According to the holographic principle, the universe is holographic, meaning that it is entirely in its every matrix part. The holographic principle has three important implications:

The first implication of the holographic principle postulates the **UNIQUENESS** of every wave matrix. if the universe is entirely in its every matrix point, then, every matrix point is not simply different from any other matrix point, but is unique.

The second implication of the holographic principle postulates the **NON-LOCALITY** of every wave matrix. If the universe is entirely in its every matrix point, then every wave matrix is simultaneously present in the infinite number of dimensions via its tokens. Though there are infinitely many tokens of the same non-local wave matrix, all of them constitute one integrated **SYSTEMATIC WHOLE**.

The non-local holographic nature of wave matrices also means that the wave matrix has the infinite set

WAVE GENOME offers everyday **MAINTENANCE** of **WAVE MATRICES** with the purchase of the **ULTRA MINI-TESLA PSI-GENERATOR** and **SUBSCRIPTION PACKAGES.**

The maintenance consists in receiving the necessary correction of your bio-field from the institute.

To obtain MAINTENANCE from the Institute, you send in your information. The Institute tracks down the changes in your **WAVE MATRIX** and makes necessary corrections. Corrections also account for the changes in the earthly electromagnetic activity, solar and lunar activity, geophysical activity, weather anomalies, and predicted social unrest.

There are two ways to send in your information. You can send your biofeedback information either **DIGITALLY** through the conventional internet, or via **QUANTUM INTERNET**.

DIGITAL MAINTENANCE BY WAVE GENOME

In the case of **DIGITAL MAINTENANCE BY WAVE GENOME LLC, WAVE GENOME LLC** corrects the digital files in the software of your **PSI-PROGRAM**.

When you connect your **MINI-TESLA GENERATOR** to your computer, you both receive and transmit through the internet the information, needed for your utmost performance, to and from the our facility.

Your childhood matrix, recorded onto the generator-transmitter, is your antennae that helps your body tune to the waves which are beneficial to you, and ward off harmful waves. That is why this technology is also called "the resonance technology".

Device strengthens the immune system and body's resistance to infectious and toxins;
Improves performance and cognitive abilities, including, sharpness of thinking and memory, and overall quality of life;
Protects against stress factors of any nature (technogenic, including, electromagnetic, as well as physical and psychic)
Speeds up recovery and healing
It is unique in the prevention of many diseases

Especially recommended for people who are in stressful situations: to sportsmen, businessmen, professionals with busy schedule, flights and business trips.

of waves, particles and fields within its **TORUS** -- from infinitely micro to infinitely macro dimensions. It is impossible to talk of each individual wave matrix as "a specific frequency". And it is impossible to postulate any "medium" of its existence, like "scalar wave", "aether", "Higgs / boson field", "torsions", "leptons", etc. There is no specific medium for transferring the information.

The third implication of the holographic principle postulates that there is the **QUANTUM ENTANGLEMENT** in the form of the instantaneous transmission of information between all the tokens of the same non-local wave matrix. The signal that records and transmits the **ENTANGLED INFORMATION** between different wave matrices or between the tokens of the same non-local wave matrix has specific nature. It is **HOLOGRAPHIC**. Only lasers can record and transmit holographic signal, based upon the principles of the polarised refraction holography (described in terms of geometrical optics). Thus, the principle of recording and transmitting the **MATRIX SIGNAL** is structural, and not medium-based.

Thus, it is possible to remotely and instantaneously transfer some wave information to a man via the entanglement between his body (at one location) and his photograph (at another location), as two tokens of his non-local wave matrix.

For example, it is possible to remotely lower blood sugar in a diabetic man via scanning his photograph with the laser ray, which is passing through insulin before reaching the photograph.

© Irene Caesar, Ph.D. from her book **"WAVE PHARMACEUTICALS"** (2014)

PRIVACY POLICY (/privacy-policy.html)

SHIPPING POLICY (/shipping--warranty.html)

RETURN POLICY (/return-policy.html)

TERMS OF SERVICE (/terms-of-service.html)

Headache: *Light Whitish Green and Light Whitish Blue Chi*

1. To check for areas that are congested or lacking in energy, the eyes, temples, spine and solar plexus area should be scanned. Also, the crown, mideyebrow, forehead and back of the head and neck.
2. The eye and temple areas should be brushed down when the headache is because of eyestrain and then flushed into the ground.
3. The whole head, particularly the painful section should be brushed and then pale green/white, blue/white and pale purple/white Chi used to bring energy into the area.

Migraine Headache: *Light Whitish Green Blue and Violet Chi*

1. Persons who suffer from prolonged or chronic headaches including those types termed 'migraine' headaches have an abnormal accumulation of energy in various parts of their bodies. Starting with the solar plexus, this energy follows a route up the vertebral column and thence into the neck and head. As a result the various blood vessels in the head expand, causing pain in the head area. Mental strain and emotional disturbances usually cause this type of headache.
2. Use a pushing movement to clean and open the solar plexus and liver areas. First use pale green/white, then pale blue/white and finally mauve/white chi to bring energy to the solar plexus area.
3. In order to send the 'sick' red chi into the ground, brush down the spinal column.
4. The back of the heart can be opened by pushing through in order to remove the dirty Chi. Then bring energy to the heart by using pale green/white and purple. Use your mind to see the heart center expanding and opening.
5. Brush down the dirty chi from the head area and send it into the earth.
6. Use a combination of pale green/white, blue and purple to bring energy to the back of the head, the crown point and the forehead.

Toothache: *Light Whitish Green and Blue Chi*

1. Brush down the area with pale green/white Chi.
2. Energy should be brought into the area with pale green/white, mauve/white and blue Chi.

Broken Bone: *Orange-Yellow Chi*

For anything relating to the bones always activate the sacrum. Light orange-yellow Chi is used to encourage broken bones to knit quickly, Chi which is pale yellowish tangerine may be employed. The sacrum attracts the orange-yellow Chi; feel the eight holes in the bone breathing. The orange-yellow Chi enters, transfers up to the crown and is sent up to the universe to multiply.

1. The fracture area should be brushed using a combination of pale green/white and pale tangerine/white chi.
2. To promote fast knitting of fractures, a daily treatment with pale tangerine yellow Chi mixed with white can be employed, in the ratio of 7:1.5:1.5 of white (for the center), yellow and tangerine respectively. Push through and brush the sacral and navel areas, using a cerise (light red) Chi mixed with white.

FDA DISCLAIMER: Content on this site is for reference purposes and is not a substitute for advice from a licensed health-care professional. You should not rely solely on this content, and wave genome.com assumes no liability for inaccuracies. Always read directions before using a product. Statements regarding products and services have not been evaluated by the FDA, and these products and services are not intended to diagnose, treat, cure, or prevent any disease or condition.

Payment in full is due ahead of services. No refunds and returns.

COPYRIGHT NOTICE: Text, graphics, and HTML code on wavegenome.com belong to Irene Caesar, Ph.D., their sole author, and are protected by US and International Copyright Laws, and may not be copied, reprinted, published, translated, hosted, or otherwise distributed by any means without explicit permission from Irene Caesar, Ph.D., and in violation of the International Laws for citing references. Any citation of the wavegenome.com website should be accompanied with the proper reference to Irene Caesar, Ph.D. Any citation exceeding the length, permissible for the reference length by the International Copyright Law, will be considered to be a violation of the International Copyright Law.

© IRENE CAESAR, PH.D., FOUNDER AND SOLE OWNER OF WAVEGENOME 2010-2017 ALL RIGHTS RESERVED

(/)

WAVE GEHOME IS
THE INFORMATION-WAVE
MATRIX OF THE FUTURE WORLD

- HOME / ГЛАВНАЯ (/)
- SERVICES / УСЛУГИ (/SERVICES--105910571051105910431048.HTML)
- PRODUCTS / ТОВАРЫ (/PRODUCTS--105810541042104010561067.HTML)
- CONTACT / КОНТАКТ (/CONTACT--1050105410531058104010501058.HTML)





Dr. Irene Caesar, author of the theory of Wave Optics in Chromosomes as Bioholography, and author of the technological model for recording and transferring the bioholograms of cells and drugs via refractions codes in the scalar wave diffraction grating; the Head of the group of technical professionals to verify the technological model offered and theoretically substantiated by her.

PRESS RELEASE ON GLOBAL LAUNCH OF THE SECOND-BIRTH TESLA PSI-GENERATOR BY WAVE GENOME

JANUARY 13, 2018

© Irene Caesar, Ph.D., President, Founder and Owner of Wave Genome

Wave Genome is proud to announce its most advanced MINI-TESLA PSI-GENERATOR ever: the SECOND-BIRTH Mini-Tesla Psi-Generator.

We called the new chip the "SECOND BIRTH" generator, because the client gets the most valuable bioholographic treatment ever for rejuvenation -- the biohologram of the embryonic stem cell. The SECOND-BIRTH Biohologram is available as a chip encoded by laser on nanolevel. The clinical trials were conducted by the Bauman University Medical Center. The clinical trials had demonstrated the radical improvement in the wellbeing of the participants in the clinical trials.

In the GENERIC SECOND-BIRTH Tesla Generator, the biohologram of the embryonic stem cell is generic. It is a DIGITAL CELL. It is not the biohologram of a specific embryo, but the result of the Embryonic research based upon the Quantum Leap diagnostic of holograms according to the coherence of the geometrical optics in chromosomes.

In the INDIVIDUAL SECOND-BIRTH Tesla Generator, the biohologram of the embryonic stem cell is modulated by client’s most coherent biohologram, recorded via laser from his

(/ask-our-maven-russian.html)

childhood photograph.

The INDIVIDUAL SECOND-BIRTH Tesla Generator is stronger than the GENERIC one, since it has a more precise focus due to the finer / smaller grid of the scalar wave diffraction grating. But you can use the GENERIC one for the entire family, and this is also a great benefit.

If somebody else will wear your own unique INDIVIDUAL Tesla Generator, this individual will simply not connect to the focus of your unique biohologram encoded on the chip, since this person has his/her own geometrical code for refraction in the scalar wave diffraction grating of his/her biohologram.

When the modulation is added to the carrier wave in the scalar wave diffraction grating, the resulting hologram is different from these two components taken separately.

In the biohologram, the polarization emerges due to the change of the spin in the integral torsion. Due to polarization, the external signal is reflected upon itself, so that the scalar / standing wave emerges. In the scalar wave, the peak of the forward-going wave is annulled by the trough of the same wave when it is reflected upon itself. Scalar wave creates the diffraction grating, so that any next external signal is refracted towards the focus / zero center of the biohologram (aka “wave crystal”).

Any external signal is only a trigger, and the external signal can be a psychotronic attack. This is a great benefit of the Quantum Leap Laser Polarized Bioholography. The more modulations the biohologram has, the more precise focus / zero center is achieved via refraction, and the better is your protection against the psychotronic attack.

Because the SECOND-BIRTH Tesla Generator has the most fine / small / scaled scalar wave diffraction grid among our other generators, the SECOND-BIRTH Tesla Generator provides the most precise focus / zero focus of client’s biohologram and the best defense against psychotronic attack.

Thus, with the SECOND-BIRTH Chip, you will experience the most radical rejuvenation effects, including mental and physical enhancement, a more emotional control, and a better defense against psychotronic attacks.

Those of our clients, who already own one of our MINI-TESLA PSI-GENERATORS, can either wear both generators together, or carry one of the generators in a pocket, or alternate generators.

WAVE GENOME HAS INTELLECTUAL PRIORITY FOR THE WAVE OPTICS IN CHROMOSOMES AS BIOHOLOGRAPHY

Click here (/diaschev-dipol-di-pol.html) to read on how WAVE GENOME’s technology differs from Dr. Gariaev’s and Dr. Diaschev’s technology (DIPOL or DI-POL Generator).

Prof. Alexander K. Volkov, Ph.D., Medical Sciences, Director of the Scientific, Medical, Technological and Educational Center of the Bauman Moscow Russian State Technical University, who headed the group of medical professionals to verify the technological model offered by Dr. Irene Caesar.



Prof. Vladimir I. Sinopalnikov, Ph.D. Medical Sciences, The Renowned Physician of the Russian Federaration, Deputy Director of the Scientific, Medical, Technological and Educational Center of the Bauman Moscow Russian State Technical University, who participated in the group of medical professionals to verify the technological model offered by Dr. Irene Caesar.

НАУЧНО-ОБРАЗОВАТЕЛЬНЫЙ МЕДИКО-ТЕХНОЛОГИЧЕСКИЙ ЦЕНТР
МГТУ ИМ. Н. Э. БАУМАНА

Scientific, Medical, Technological and Educational Center of the Bauman Moscow Russian State Technical University, in possession of the cutting edge lasers, and other technology.

Bauman Moscow Russian State Technical University, major Science University of Russia, of MIT level.

PRIVACY POLICY (/privacy-policy.html)   SHIPPING POLICY (/shipping--warranty.html)   RETURN POLICY (/return-policy.html)   TERMS OF SERVICE (/terms-of-service.html)

FDA DISCLAIMER: Content on this site is for reference purposes and is not a substitute for advice from a licensed health-care professional. You should not rely solely on this content, and wave genome.com assumes no liability for inaccuracies. Always read directions before using a product. Statements regarding products and services have not been evaluated by the FDA, and these products and services are not intended to diagnose, treat, cure, or prevent any disease or condition.

Payment in full is due ahead of services. No refunds and returns.

COPYRIGHT NOTICE: Text, graphics, and HTML code on wavegenome.com belong to Irene Caesar, Ph.D., their sole author, and are protected by US and International Copyright Laws, and may not be copied, reprinted, published, translated, hosted, or otherwise distributed by any means without explicit permission from Irene Caesar, Ph.D., and in violation of the International Laws for citing references. Any citation of the wavegenome.com website should be accompanied with the proper reference to Irene Caesar, Ph.D. Any citation exceeding the length, permissible for the reference length by the International Copyright Law, will be considered to be a violation of the International Copyright Law.

© IRENE CAESAR, PH.D., FOUNDER AND SOLE OWNER OF WAVEGENOME 2010-2017 ALL RIGHTS RESERVED

WAVE GENOME (/)

HEALING VIA WAVE PHARMACEUTICALS
AND QUANTUM BIOCOMPUTING

(/tesla-generator.html) TESLA PSI-GENERATOR

(/order-tesla-selenium.html) TESLA SELENIUM

(/tesla-water.html) TESLA WATER

(/order-tesla-glasses.html) TESLA GLASSES

(/digital-pharmaceuticals--- DIGITAL PHARMACY

(/order-tesla-screen.html) TESLA SCREEN

IRENE CAESAR, PH.D.

President & Founder

WAVE GENOME LLC

465 Buckland Hills Drive

Unit 33211, Manchester, CT 06042

1-646-480-0496

ORDER YOUR MINI-TESLA GENERATOR

(/tesla-generator.html)

WAVE GENOME IS A FRONTIER OF THE TECHNOLOGICAL REVOLUTION

WAVE GENOME IS AN AMERICAN COMPANY LOCATED IN CONNECTICUT - A PROUD PIONEER OF PRODUCING WAVE MATRICES / BIOHOLOGRAMS BY LASERS FOR THE LOCAL AND REMOTE MANAGEMENT OF BIOSYSTEMS AND HUMAN CONDITION

WAVE GENOME PRECEDED GOOGLE'S BIOELECTRONIC DRUGS R&D PROGRAM FOR 6 YEARS OF ACTUAL SALES AND 50 YEARS BEYOND R&D.

WAVE GENOME HAS INTELLECTUAL PRIORITY FOR THE WAVE OPTICS IN CHROMOSOMES AS BIOHOLOGRAPHY (/diaschev-dipol-di-pol.html)

(http://www.facebook.com/pages/Wave-Genome/203765456304318?fref=ts)

(/wave-genome--russian.html)

Нажмите на Русский флаг для перемещения на версию сайта на Русском языке

ВОЛНОВОЙ ГЕНОМ

WAVE
PHARMACEUTICALS

(/wave-pharmaceuticals.html)

VISIT OUR CLINIC
FOR CURE AND
REJUVENATION

(/quantum-clinic.html)

TESLA SELENIUM IS THE ONLY ORGANIC AND BIVALENT SELENIUM IN THE WORLD
Se 2+
TESLA SELENIUM PRO
BY WAVE GENOME LLC
1 pill = Organic Selenium 25 µg, Organic Germanium 100 µg, Organic Zinc 5 mg
60 pills
WAVEGENOME.COM
Se 2+
TESLA SELENIUM MAXI
BY WAVE GENOME LLC
1 pill = Organic Selenium 70 µg
60 pills

(/order-tesla-selenium.html)

USED BY
MILITARY PILOTS AND
ASTRONAUTS
ORDER TESLA GLASSES
EYE SIGHT RESTORATION
AND TREATMENT OF
PHYSIOLOGICAL SYSTEMS
VIA POLARIZED BIOHOLOGRAPHY

(/order-tesla-glasses.html)

Read about TESLA GLASSES here (/order-tesla-glasses.html).
Order TESLA GLASSES here (/order-form.html).

EIGHT YEARS OF SATISFIED CUSTOMERS

WE OFFER ADVANCED WEATHER CONTROL. BUT WHAT CAN BE NOBLER THAN SAVING LIVES!
(/quantum-clinic.html)

BIOWAVE GENOME HAS DISTRIBUTORS ALL OVER THE WORLD:

Germany, Sweden, Poland, United States, Russia, Thailand

Click here (/diaschev-dipol-di-pol.html) to read on how WAVE GENOME's technology differs from Dr. Peter P. Gariaev's and Dr. Alexander D. Panchenko's technology (DIPOL or DI-POL Generator, sold by Dr. Diaschev).

EMBRYONIC STEM CELL
BIOHOLOGRAM
EXCLUSIVELY
BY WAVE GENOME LLC

(/second-birth-mini-tesla-psi-generator.html)

GLOBAL LAUNCH OF THE SECOND-BIRTH MINI-TESLA PSI-GENERATOR BY WAVE GENOME (/second-birth-mini-tesla-psi-generator.html)

JANUARY 13, 2018

Wave Genome is proud to announce its most advanced MINI-TESLA PSI-GENERATOR ever: the SECOND-BIRTH Mini-Tesla Psi-Generator.

We called the new chip the "SECOND BIRTH" generator (/second-birth-mini-tesla-psi-generator.html), because the client gets the most valuable bioholographic treatment ever for rejuvenation -- the biohologram of the embryonic stem cell. The SECOND-BIRTH Biohologram (/second-birth-mini-tesla-psi-generator.html) is available as a chip encoded by laser on nanolevel. The clinical trials were conducted by the Bauman University Medical Center. The clinical trials had demonstrated the radical improvement in the wellbeing of the participants in the clinical trials.

Click here to read more. (/second-birth-mini-tesla-psi-generator.html)

WAVE GENOME LLC uses Bauman Moscow Russian State Technical University, major Science University of Russia, of MIT level, to verify WAVE GENOME'S technological models.

WORLDWIDE LAUNCH OF HOLONET (© Dr. Irene Caesar) - HOLOGRAPHIC BIOINTERNET & HOLOGRAPCHIC DRUGS, BIOELECTRONIC DRUGS AND INTERNET DRUGS

H-DRUGS, E-DRUGS AND I-DRUGS

FOR REMOTE AND LOCAL REJUVENATION

NEWS



IRENE CAESAR INTERVIEW FOR MINDTECH ENTERPRISES DEC 13 2016

IRENE CAESAR - INTERVIEW FOR MINDTECH ENTERPRISES DEC 13 2016 (https://www.youtube.com/watch?v=ap8kHpuYIxM&feature=youtu.be)

IRENE CAESAR INTERVIEW FOR RIPSONAR NEWS APRIL 22 2017
54:42 / 56:35

IRENE CAESAR, Ph.D., PRESIDENT AND OWNER OF WAVE GENOME: INTERVIEW FOR RIPSONAR NEWS, APRIL 22, 2017 (https://www.youtube.com/watch?v=iTTHLETrz1A).

(/quantum-clinic.html)
Large-size AURA PSI-GENERATOR for radical rejuvenation of all bodily organs and physiological systems.



(/quantum-clinic.html)
Large-size AURA PSI-GENERATOR offers radical rejuvenation for patents rejected by conventional medicine to the degree they do not need conventional medicine any longer.

Click here (/quantum-clinic.html) to read about our clinic.

Consortium "MATRIX CITY - city as one integrated wave matrix" (/consortium.html)



(/irene-caesar---matrix-city-project.html)

QUANTUM REMOTE REJUVENATION

(/quantum-rejuvenation-clinic-om---english.html)



BIT's 1st World Congress of Biomedical Engineering-2017 (WCBME-2017)

www.bitcongress.com/wcbme2017/scientificprogram.asp

Cloud Popular News

	Dr. Zhuo Li, General Manager of Greater China, NanoTemper Technologies, China

01: Neural Engineering	
Time: 13:30-14:25, Nov. 9, 2017 (Thursday) ; Place: Yu Lin Room A, 2nd Floor, Hilton Xi'an	
Chair	***Dr. Irene Caesar,*** CEO, Matrix City LLC, Russia
13:30-13:35	**Chair's Introduction**
13:35-13:55	***Title:*** *Remote Biomedical Engineering via Mastering the Geometrical Optics of Chromosomes* ***Dr. Irene Caesar,*** CEO, Matrix City LLC, Russia
13:55-14:05	***Title:*** *A Potential Activation Blocking Mechanism of High Frequency Stimulation on Axons* ***Ms. Longzhi Mei,*** Senior Research Assistant, Beth Israel Deaconess Medical Center USA
14:05-14:25	***Title:****Modelling Cognitive Laws for Recognizing Emotions* ***Dr. Guihua Wen,***Professor, South China University of Technology, China

NOVEMBER 9-11, 2017

DR. IRENE CAESAR WAS INVITED TO BE A CHAIR OF THE NEURAL ENGINEERING SECTION OF THE BIT'S 1st WORLD COGRESS OF BIOMEDICAL ENGINEERING, Theme: Co-creating a New Future of Biomedicine, November 9-11, 2017, in Xi'an, China. I will deliver paper called **"REMOTE BIOMEDICAL ENGINEERING VIA MASTERING THE GEOMETRICAL OPTICS OF CHROMOSOMES"**. List of Renowned Speakers include professors from University of Oxford, UK; Harvard Medical School, USA; American College Of Clinical Engineering, USA; California South University, USA; University of Illinois at Chicago, USA; The Mount Sinai Medical Center, USA; University of California, USA; Washington University School of Medicine, USA; The Salerno Center for Complementary Medicine, USA; National Cancer Institute, NIH, USA; University of Pennsylvania, USA; Washington University in St. Louis Campus, USA; International Federation For Medical and Biological Engineering, USA; Louisiana State University Health Sciences Center in Shreveport, USA; International Spine Research Foundation, USA; RWTH Aachen University, Germany; Technical University of Munich, Germany; Institut Curie, France; University of Queensland, Australia; Tsinghua University, China; Asia Pacific Association for Medical Informatics, South Korea; European Medical Association, Belgium; University of Geneva, Switzerland; Gyeongbuk Institute of Science and Technology, South Korea; University of Geneva, Switzerland; The Standing Committee of European Doctors, Belgium; International Scociety of Medical Laser Applications, Austria.

Link to the NEURAL ENGINEERING Session: http://www.bitcongress.com/wcbme2017/scientificprogram.asp

List of Renowned Speakers: http://www.bitcongress.com/wcbme2017/default.asp

"REMOTE BIOMEDICAL ENGINEERING VIA MASTERING THE GEOMETRICAL OPTICS OF CHROMOSOMES"

Abstract

The same gene is expressed in functional individuals and species by metacentric chromosome, and in dysfunctional individuals and species via acrocentric chromosome. Metacentric chromosome is analogous to a well-centered and focused eye crystal, while acrocentric chromosome is analogous to a myopic or farsighted eye. Chromosome is a lens that allows our cells to focus the needed wave information during cell division, analogously to a crystal in our eye. Thus, Biomedical Engineering is possible only via mastering the Geometrical Optics of Chromosomes by Laser Bioholography. Current genetic engineering via cutting and pasting DNA snippets destroys the systematic wholes of chromosomal bioholograms and the refraction of the geometrical optics in chromosomes, and, therefore, causes genetic collapse. The Quantum Leap in the Biomedical Engineering is the cost of our survival. Biomedical Engineering as Bioholography is based on Quantum Physics, and understanding the non-local nature of the Bioholograms. Since universe is holographic, we can record and transmit only holographic information, based upon changing the refraction of the scalar wave diffraction grating in chromosomes. According to Holographic principle, Universe is entirely in its every matrix point. The implication of the Holographic Principle states that if Universe is entirely in its every matrix point, then, every matrix point is not simply different from any other matrix point, but is unique. This means that



(https://www.youtube.com/watch?v=uxfui6xTtEc)

IRENE CAESAR, Ph.D., PRESIDENT AND OWNER OF WAVE GENOME: INTERVIEW FOR POROZMAWIAJMY TV CONDUCTED BY ALEXANDER BERDOWICZ, FEBRUARY 7, 2017. (https://www.youtube.com/watch?v=uxfui6xTtEc)



IRENE CAESAR, Ph.D., PRESIDENT AND OWNER OF WAVE GENOME: LECTURE "MATRIX AS A GLOBAL MANAGEMENT SYSTEM OF LIFE. MECHANISM OF REMOTE MANAGEMENT OF BIOSYSTEMS," CONFERENCE "PSYCHICS - YESTERDAY, TODAY, AND TOMORROW, (4TH MEETING OF THE ASSOCIATION OF ASTRAL ANTHROPOLOGY AND PSYCHOLOGY), MOSCOW, RUSSIA, OCTOBER 10, 2016. (https://www.youtube.com/watch?v=eEKzZQ4Wzcc)



IRENE CAESAR, PH.D., PRESIDENT AND OWNER OF WAVE GENOME, IN THE FILM BY RENOWNED RUSSIAN PRODUCER GALINA TSAREVA "I WANT TO REMAIN HUMAN", AUGUST, 2016. (https://www.youtube.com/watch?v=YTTWaIRT_0Y)

(https://www.youtube.com/watch?v=XuwV_QCTf2I)

IRENE CAESAR, PH.D., PRESIDENT AND OWNER OF WAVE GENOME: "REMOTE MANAGEMENT OF BIIO SYSTEMS BASED UPON THE SHAPE OF CHROMOSOMES AS DIFFRACTION GRATING FOR

Models of TESLA PSI-GENERATORS by WAVE GENOME.



TRUE BIOELECTRONIC E-DRUGS

The MINI-TESLA psi-generator **DIGITAL PHARMACY (/digital-pharmacy-software--1057105410601058-10621048106010561054104210541049104010551058104510501048.html)** software program generates HOLOGRAPHIC SIGNAL (as white noise) encoded in music for every system and vital organ in your body.

MILESTONES

Over the span of the 20th century, generations of extraordinary scientists, among whom Russian scientists played a leading role, laid down scientific foundation for the technological revolution of information-wave technology of the Quantum Leap.

MORE (/milestones.html)



(/uploads/3/5/1/1/35112207/5553543_orig.jpg)

For developing and producing its products, WAVE GENOME is teaming with most advanced scientists all over the world. Here we see Scientific Research Institute for National Security in Moscow, now closed. The scientific group still

every wave matrix is both non-local, and unique. Thus, if we have two exact copies of the same non-local wave matrix, we can transmit information instantaneously and remotely, from one copy of the same non-local unique wave matrix to another copy. Thus, the precision in the Biomedical Engineering is achieved not via the precision of localization, but, vice versa, via the precision of refraction in the unique and non-local bioholograms aka “wave crystals”. The secret in the remote Biomedical Engineering as Quantum Biocomputing lies in the recording and instantaneous transmission of a structural phantom. I will introduce the new method for recording and remote transmitting of bioholograms via laser spectroscopy and coding electrets on nanolevel via laser. The technology creates “lenses” assisting our chromosomes in correcting their refraction for focusing genetic bioholographic information, both locally and remotely.

APRIL 25-27, 2017

IRENE CAESAR, PH.D., SPEECH "REMOTE MANAGEMENT OF BIOSYSTEMS AS BIOHOLOGRAPHY BASED UPON THE SHAPE OF CHROMOSOMES FOR FOCUSING GENETIC INFORMATION" at the Annual World Congress of Molecular & Cell Biology Xi'an, China. **Click here** (http://www.bitcongress.com/cmcb2017/)for the official webpage of the Summit. **Click here (http://www.bitcongress.com/cmcb2017/scientificprogram_4.asp)** for the official list of participants.



BIT'S 7TH ANNUAL WORLD

CONGRESS OF MOLECULAR & CELL BIOLOGY

Date: April 25-27, 2017 Place: Xi'an, China

Section 401: Role of Molecular & Cell Biology in Translational Medicine

13:55-14:15

Title: Remote Management of Biosystems as Bioholography Based upon the Shape of Chromosomes for Focusing Genetic Information

Dr. Irene Caesar, CEO, Matrix Ltd., Russia; President, Wave Genome, USA

BIT's World Congress of Molecular & Cell Biology Since 2011
Matrix



BIT'S 7TH ANNUAL WORLD CONGRESS OF MOLECULAR & CELL BIOLOGY

APRIL 25-27 2017

XI'AN, CHINA

IRENE CAESAR, PH.D.

PRESIDENT, WAVE GENOME

CEO, MATRIX CITY

REMOTE MANAGEMENT OF BIOSYSTEMS AS BIOHOLOGRAPHY BASED UPON THE SHAPE OF CHROMOSOMES FOR FOCUSING GENETIC INFORMATION

WG
WAVE GENOME

Keynote speakers: Dr. Christian Paterman, Former Director, European Commission, Germany; Dr. Martin Banwell, Professor, Australian National University, Australia; Dr. Robert S. Plumb, Professor, Imperial College London, UK; Dr. Dongping Zhong, Professor, Ohio State University, USA.

FOCUSING GENETIC INFORMATION" - RECORDING OF THE LECTURE, BANGKOK THONBURI UNIVERSITY 2ND INTERNATIONAL SYMPOSIUM, JULY 23, 2016.

(https://www.youtube.com/watch?v=XuwV_QCTf2I)



(https://www.youtube.com/watch?v=pSsgOPUzz9A)

IRENE CAESAR, PH.D., PRESIDENT AND OWNER OF WAVE GENOME: "REMOTE MANAGEMENT OF BIIO SYSTEMS BASED UPON THE SHAPE OF CHROMOSOMES AS DIFFRACTION GRATING FOR FOCUSING GENETIC INFORMATION" - SLIDE SHOW OF THE LECTURE, BANGKOK THONBURI UNIVERSITY 2ND INTERNATIONAL SYMPOSIUM, JULY 23, 2016.

(https://www.youtube.com/watch?v=pSsgOPUzz9A)

IRENE CAESAR - GOSPEL OF IRENE
15:52 / 39:01

IRENE CAESAR, PH.D., FOUNDER, OWNER AND PRESIDENT OF WAVE GENOME: LECTURE "GOSPEL OF IRENE" (PAPER "GOSPEL OF IRENE" WAS PUBLISHED IN FULL IN THREE ISSUES OF THE SOCIALIST FACTOR MAGAZINE, LUCKNOW AND LONDON), THE STRATEGIC INFORMATICS ADVISORY, MARYLAND, USA, JULY 7, 2016.

(https://www.youtube.com/watch?v=QFEErBqSJjY&feature=youtu.be)



ИРИНА ЦЕЗАРЬ - ГИПЕРБОРЕЙСКАЯ ТЕОРИЯ С ТОЧКИ ЗРЕНИЯ КВАНТОВОЙ ФИЗИКИ
17:27 / 17:49

IRENE CAESAR, PH.D., PRESIDENT AND OWNER OF WAVE GENOME: "HYPERBOREAN THEORY FROM THE POINT OF VIEW OF QUANTUM PHYSICS" - PAPER DELIVERED AT THE CONFERENCE "ESOTERICS, NEW TURNAROUND", ASSOCIATION OF ANTHROPOLOGY AND PSYCHOLOGY, MOSCOW, MAY 16, 2016. (https://www.youtube.com/watch?v=CRbRsohA8i4)

operates the clinic. Among clients of the clinic were Russian President Boris Yeltsin, famed American astronaut Edgar Mitchell, and actor celebrity Alexander Kalyagin. The institute has received the written Blessing of Patriarch Alexis and Patriarch of Constantinople.

(/uploads/3/5/1/1/35412207/4353994_orig.jpg)

Famed American Astronaut Edgar Mitchell received a treatment by GENERATOR AURA-001.

OUR PLEDGE

We build our strategy upon a firm foundation of the highest standards of ethics.

MORE (/our-pledge.html)

Our MINI-TESLA PSI-GENERATOR is used by Russian Special Forces.

Our MINI-TESLA PSI-GENERATOR is used by Russian Olympic Team.

Our TESLA GLASSES are used by Russian Central Intelligence Service.

Our TESLA GLASSES are used by Russian Space Forces.

Re
Biosyste
upon t
for Foc

2017第八届国际DNA和基因组活动周
BIT's 8th Annual World DNA and Genome Day-2017
NO. 03
BIT'S 7TH ANNUAL WORLD CONGRESS OF MOLECULAR & CELL BIOLOGY
APRIL 25-27 2017
XI'AN, CHINA
WG
WAVE GENOME
IRENE CAESAR, PH.D.
PRESIDENT, WAVE GENOME
CEO, MATRIX CITY
REMOTE MANAGEMENT OF BIOSYSTEMS AS BIOHOLOGRAPHY BASED UPON THE SHAPE OF CHROMOSOMES FOR FOCUSING GENETIC INFORMATION
NO. 04

Abstract

We are standing at the threshold of the biggest scientific revolution in the history of human kind, called Quantum Leap. All Transhumanist models of genetic modification of organisms, relying on global artificial intellect and brain-computer interfaces are obsolete technologies of the pre-Quantum Era. Either Biology makes Quantum Leap, or humankind will be destroyed by genetic collapse. Human enhancement is possible only through mastering the geometrical optics of chromosomes via Bioholography.

Now bioengineering fails since it does not account for the geometrical optics of chromosomes, leading to the corruption of genomes. The same gene gets expressed in dysfunctional individuals by acrocentric chromosome, and in functional individuals by metacentric chromosome. I claim that chromosome is a geometrical code and functions via refraction in the wave crystal, i.e., nonlocal unique biohologram or wave matrix that focuses genetic information unique to this individual via his / her own unique scalar wave diffraction grating. The implication of the holographic principle states that if the universe is entirely in its every matrix point, then, every matrix point is not simply different from any other matrix point, but is unique. Thus, if we have two exact copies of the same unique non-local biohologram, we can transmit information remotely and instantaneously from one copy to another copy for the remote management of biosystems.



BIT's 7th Annual World Congress of Molecular & Cell Biology-2017 Xi'an, China

Title: Remote Management of Biosystems as Bioholography Based upon the Shape of Chromosomes for Focusing Genetic Information

Dr. Irene Caesar
CEO
Matrix Ltd., Russia
President
Wave Genome, USA

Abstract

We are standing at the threshold of the biggest scientific revolution in the history of human kind, called Quantum Leap. All Transhumanist models of genetic modification of organisms, relying on global artificial intellect and brain-computer interfaces are obsolete technologies of the pre-Quantum Era. Either Biology makes Quantum Leap, or humankind will be destroyed by genetic collapse. Human enhancement is possible only through mastering the geometrical optics of chromosomes via Bioholography. Now bioengineering fails since it does not account for the geometrical optics of chromosomes, leading to the corruption of genomes. The same gene gets expressed in dysfunctional individuals by acrocentric chromosome, and in functional individuals by metacentric chromosome. I claim that chromosome is a geometrical code and unctions via refraction in the wave crystal, i.e., nonlocal unique biohologram or wave matrix that focuses genetic information unique to this individual via his/her own unique scalar wave diffraction grating. The implication of the holographic principle states that if the universe is entirely in its every matrix point, then, every matrix point is not simply different from any other matrix point, but is unique. Thus, if we have two exact copies of the same unique non-local biohologram, we can transmit information remotely and instantaneously from one copy to another copy for the remote management of biosystems.

Biography

Irene Caesar, Ph.D., is a Co-Founder and CEO of Matrix Ltd., Russia, company creating global subscription platforms for bioelectronic drugs (founded 2016); Founder and President of Wave Genome, company producing bioelectronic devices and software for the distribution of bioelectronic drugs for rejuvenation only (founded 2010); Co-Founder of 'Matrix City' Consortium with the Institute for National Security in Moscow for building self-sufficient human settlements based upon the remote management of biosystems, climate and geophysical processes for the first time in the history of humankind (founded 2012), presented in the Honorary Lecture at the Harriman Institute of the Columbia University in September 2012; Co-Founder of the Quantum Biointernet for the remote rejuvenation via distant laser signal, commercially offered for the first time in the history of humankind by Irene Caesar's company Wave Genome in May 2013; Colonel of Irkutsk Cossack Military, awarded the Medal of Faith and Service to Russia (2014). Dr. Caesar received her Doctoral Degree from the Graduate Center of the City University in New York.

Section 401



IRENE CAESAR, PH.D., PRESIDENT AND OWNER OF WAVE GENOME: "HOLOGRAPHIC PRINCIPLE OF THE STRUCURE OF THE UNIVERSE" - PAPER DELIVERED AT THE CONFERENCE "UNKNOWN COSMOS", ASSOCIATION "PROTOHISTORY", MOSCOW, MAY 14, 2016. (https://www.youtube.com/watch?v=M4oYWLLmP4c)



(https://www.youtube.com/watch?v=RT1nSUJilbY)

IRENE CAESAR, PH.D., PRESIDENT AND OWNER WAVE GENOME: "STRUCTURALIST WAVE GENOME AS THE FOUNDATION FOR SUPER INTELLECT" - PAPER DELIVERED AT THE CONFERENCE OF THE ASSOCIATION FOR ANTHROPOLOGY AND PSYCHOLOGY, MOSCOW, APRIL 26, 2016. (https://www.youtube.com/watch?v=RT1nSUJilbY)

Another version of this video recording. (http://www.wavegenome.com http://www.thematrixcity.com)



(http://Skip navigation RUUpload Search Analytics Video Manager ИРИНА ЦЕЗАРЬ О ВОЛНОВОЙ ГЕНЕТИКЕ И СЕБЕ ГЛОБАЛЬНАЯ ВОЛНА 3 АПРЕЛЯ 2016 Irene Caesar Irene Caesar Channel settingsDownload720 Add to Share More 82 views Published on Jun 7, 2016 ИРИНА ЦЕЗАРЬ О ВОЛНОВОЙ ГЕНЕТИКЕ И СЕБЕ ГЛОБАЛЬНАЯ ВОЛНА 3 АПРЕЛЯ 2016 SHOW MORE Comments are disabled for this video. Autoplay Up Next Сергей Салль Ответ еврейке Цезарь - Салль позор России игра в бисер 12,851 views 50:28 ИРИНА ЦЕЗАРЬ - РАВВИН ЭТО РУСО-АРИЙ ГЛОБАЛЬНАЯ ВОЛНА Irene Caesar 97 views 2:52:41 Засланный казачок Ирина Цезарь или очередной проект сатаноизбранных (Сергей Салль) Светослав 4,499 views 50:28 ИРИНА ЦЕЗАРЬ - СТРУКТУРНАЯ ВОЛНОВАЯ ГЕНЕТИКА КАК ОСНОВА СВЕРХРАЗУМА Irene Caesar 362 views 18:05 СПИЦЫН - Золотая Орда. Дмитрий Донской. Нашествия ханов. Куликовская битва. Монголы и Русь. Евгений Спицын ИСТОРИЯ РОССИИ Recommended for you 57:16 ИРИНА ЦЕЗАРЬ

Our TESLA GLASSES are used by Russian Strategic Missile Forces.

Our TESLA GLASSES are used by Russian Ministry of Emergency Situations.

Our TESLA GLASSES are used by Russian Federal Security Service.

Our TESLA GLASSES are used by Russian Interior Ministry.

WAVE GENOME employs scientists from most advanced research group all over the world, including the present Moscow Bauman Russian State Technical University, the major Science University in Russia, of MIT level; and scientists of the former most secret USSR Research Institutes, which conducted studies in psychotronics, e.g., "Scientific-Research Institute Energy" (founded in 1937, with 5000 scientists under supervision of the National Security Agencies of the Soviet Union (Научно- производственное Объединение Энергия). The Scientific-Research Institute Energy was developing devices and services for the first persons in the State, military commanders, diplomats, Special Forces and the Olympic Team. Technologies of the Institute were declassified in 2008. In the US, these technologies are still classified. Dr. Irene Caesar was also collaborating with the Scientific Research Institute for the National Security in Moscow, Russian Federation, now closed.

Nonetheless, it was Dr. Irene Caesar herself who was first to offer to record the holographic signal of the wave matrices via laser from the pharmaceutical drugs as recreated bioholograms representing in this dimension the scalar wave diffraction gratings of multidimensional wave crystals. And Dr. Caesar was first to offer an idea to encode electrets via laser on nanolevel with these bioholograms of the pharmaceutical drugs.

Dr. Caesar created a theory of the Wave Optics (Geometrical Optics) in chromosomes as refraction in the scalar wave diffraction grating.

GLOBAL LAUNCH OF ULTIMATE TESLA PSYCHOTRONIC GENERATOR BY WAVE GENOME

Click here (/ultimate-mini-tesla-psi-generator.html) to read **PRESS RELEASE** on the **GLOBAL LAUNCH OF THE ULTIMATE TESLA PSI-GENERATOR by WAVE GENOME**

ULTIMATE TESLA PSI-GENERATOR IS BASED UPON IMPORTANT DISCOVERY BY DR. IRENE CAESAR REGARDING THE SHAPE OF CHROMOSOMES AS DIFFRACTION GRATING / REFRACTION MECHANISM FOR FOCUSING GENETIC INFORMATION

IRENE CAESAR & MAGNUS OLSSON ULTIMATE TESLA LAUNCH BY WAVE GENOME
14:36 / 15:22

(https://www.youtube.com/watch?v=Iyfh-C3oSm0&feature=youtu.be)

ON DECEMBER 2, 2016, IRENE CAESAR, PH.D.. PRESIDENT, FOUNDER AND OWNER OF WAVE GENOME, LAUNCHED HER NEW PRODUCT -- ULTIMATE MINI-TESLA PSI-GENERATOR FOR THE ULTIMATE PROTECTION AGAINST PSYCHOTRONIC AND GENETIC WARFARE. Intellectual and Commerical Property belongs to WAVE GENOME. Magnus Olsson, President of Mindtech Enterprises, becomes the designated Distributor for WAVE GENOME'S ULTIMATE MINI-TESLA PSI-GENERATOR, available on wavegenome.com (http://www.wavegenome.com) and mindtechenterprises.com (http://www.mindtechenterprises.com). **Click here (https://www.youtube.com/watch?v=Iyfh-C3oSm0&feature=youtu.be)** to see the official video of the global launch of THE ULTIMATE MINI-TESLA PSI-GENERATOR by WAVE GENOME.

- ДОКАЗАТЕЛЬСТВА ДРЕВНОСТИ РУСОВ Irene Caesar 162 views 1:09:36 America)

IRENE CAESAR, PH.D., PRESIDENT AND OWNER OF WAVE GENOME - NTERVIEW ABOUT WAVE GENOME ON GLOBAL WAVE, MOSCOW, APRIL 3, 2016

(https://www.youtube.com/watch?v=VNLtnfLCOlk&feature=youtu.be)



(https://www.youtube.com/watch?v=tgF8PCbRJCQ&feature=youtu.be)

IRENE CAESAR, PH.D., PRESIDENT AND OWNER OF WAVE GENOME: "GENOME IS THE REFRACTION OF SIGNALS TOWARDS THE FOCUS IN THE WAVE CRYSTAL OF CHROMOSOMES" - GUEST PUBLIC LECTURE "DNA GENEALOGY IN THE LIFHT OF RUSSIAN IDEA", EXTRACT, RESEARCH CENTER ON THE ETHICS OF THE RUSSIAN WORLD, MOSCOW, MARCH 16, 2016

(https://www.youtube.com/watch?v=tgF8PCbRJCQ&feature=youtu.be)



Рис. 5. Интерференция прямой и обратной волн при перпендикулярном отражении от поверхности и сдвиге фаз на 180 градусов. Образование стоячей волны и возникновение противофазы.

(https://www.youtube.com/watch?v=nPgyM2d0HQg&feature=youtu.be)

IRENE CAESAR, PH.D., PRESIDENT AND OWNER OF WAVE GENOME: "CONFIRMATION OF THE HYPERBOREAN THEORY BY QUANTUM PHYSICS" - GUEST PUBLIC LECTURE "DNA GENEALOGY IN THE LIFHT OF RUSSIAN IDEA", EXTRACT, RESEARCH CENTER ON THE ETHICS OF THE RUSSIAN WORLD, MARCH 16, 2016

(https://www.youtube.com/watch?v=nPgyM2d0HQg&feature=youtu.be)



(https://www.youtube.com/watch?v=ONPUDcRVgHY&feature=youtu.be)

IRENE CAESAR, PH.D, PRESIDENT AND OWNER OF WAVE GENOME: "SHAPE OF CHROMOSOMES AS A KEY TO WAVE GENOME - GUEST PUBLIC LECTURE, CHETEK ("MAN, TECHNOLOGY, CAPITAL"), MOSCOW, JANUARY 27, 2016

Back Injury: *Light Whitish Blue and Green Violet Chi*

1. Scan the student to see which parts are congested.
2. Use chi that is pale white/green or pale white/tangerine and, selecting each in turn, with a brushing movement apply to the whole spinal area and especially to the area where the trauma is located.
3. To bring energy to the damaged area, use a combination of pale blue/white, green and purple.
4. White chi should be used with a brushing movement on both the back and front of the solar plexus area.

Infection and Inflammation: *Light Green Chi*

Treat the damaged area with green and tangerine/white chi, using a brushing movement. For the heart and spleen, these colors should be replaced with green and purple.

Bring energy to the area by the use of mauve, white, tangerine, green and blue and strengthen the natural immune of the body.

Cysts: *Light Green and Blue Chi*

During the course of the session, repeatedly pass your hands over the patient's body. Treat the solar plexus area with a combination of green and blue chi. The cyst can be removed using a chi knife, spiraling clockwise with green and tangerine chi; moving the 'stuck' red chi out of the body and grounding it in the earth. After, blue chi should be used for a calming effect, while green and tangerine can also provide energy. For maximum benefit, sessions should be thrice weekly.

As foods containing a lot of highly spiced ingredients have a lot of red chi, these should be kept to a minimum. The patient should use the Inner Smile to calm and balance his/her emotional state.

It is sometimes necessary to sweep 100-200 times, to cool the affected area. Scanning will enable you to take a temperature reading. If the area is still hot then continue sweeping until it reaches a satisfactory temperature.

Fever

1. Brushing can be done with blue or green Chi.
2. Push and pull through the affected part, sweeping the spleen with green and blue. Clean and rinse thoroughly.
3. The solar plexus area can be treated with tangerine and blue Chi but tangerine should not be used on a patient with diarrhea.
4. The thymus gland can be stimulated by the application of green, tangerine and purple Chi. First, brush the heart area with green and blue. This helps the body to ward off infection.
5. Both lungs should be brushed and energy brought into the back of the lung area by the use of tangerine and green.
6. Sweep the spleen with green.

Dr. Caesar was first to offer an idea of DIGITAL PHARMACY as the collection not of frequencies, but of bioholograms.

WAVE GENOME is focused on developing and commercializing **QUANTUM BIOCOMPUTING** as the **INFORMATION-WAVE TECHNOLOGY OF THE LASER BIOHOLOGRAPHY** in the fields of rejuvenation, wellness and agriculture.

THE INFORMATION-WAVE TECHNOLOGY OF LASER BIOHOLOGRAPHY is based upon the application of Quantum Physics to Genetics, a new theory of Genetics, which is called **STRUCTURALIST GENETICS** (© Irene Caesar, Ph.D., 1989-2010), and the application of various lasers, including the stabilized He-Ne lasers with internal mirrors.

Specifically, this technology applies:
- the holographic model of the Quantum Vacuum identical for macro and micro dimensions;
- the holographic torsion model of the cell as a torus;
- polarized bioholography and polarized bioholograms, based upon the principles of geometrical optics;
- the notions of two kinds of torus: torus as a boundless sphere and torus as a wave crystal (© Irene Caesar, Ph.D., 1989);
- the Kozyrev Mirror principle for the reflection of the external signal upon itself, and creating the scalar wave diffraction grating (wave crystal);
- the diffraction grating (wave crystal) for the refraction of the external signal towards the zero center;
- the notion of the zero center of the wave crystal as the information portal;
- the notion of the instantaneous and remote transmission of information through the zero center of the wave crystal via quantum entanglement in the paradigm of the **QUANTUM BIOINTERNET**.

INFORMATION-WAVE TECHNOLOGY OF THE LASER BIOHOLORAPHY is radically different from the Digital Homeopathy and Bioresonance Technology, though it is also based upon the wave-particle duality in physics. Cell dies when it goes into bioresonance with itself. Soviets had the psychotronic weapon, based upon the principle of bioresonance. Thus, the bioresonance technologies in the West are still wide spread simply because they cannot do enough harm due to incompetence. The information is received and transmitted not through waves (frequencies). The information is received and transmitted through the **GEOMETRICAL CODES** of the wave crystals.

Also, the **INFORMATION-WAVE TECHNOLOGY OF THE LASER BIOHOLORAPHY** is not the scalar wave technology, since scalar waves neutralize any external signal. And to call the **INFORMATION-WAVE TECHNOLOGY OF THE LASER BIOHOLOGRAPHY** as the "scalar wave technology" is to say nothing. Scalar waves are only one element of this technology. Information is not received and transmitted via scalar waves. Scalar waves are simply used for creating the diffraction grating inside the wave crystal in order to refract the external signal toward the zero center of the wave crystal. Information is received and

GLOBAL LAUNCH OF
TESLA GLASSES
BY WAVE GENOME

(/order-tesla-glasses.html)

PROGRAM SELECT

(/order-tesla-glasses.html)

Click here (/order-tesla-glasses.html) to read about WAVE GENOME TESLA GLASSES.

IRENE CAESAR - HOW TESLA PSI GENERATOR WORKS

(https://www.youtube.com/watch?v=Z8Otz0gbqeM)

DECEMBER 2, 2016

IRENE CAESAR, PH..D, PRESIDENT, FOUNDER AND OWNER OF WAVE GENOME: "HOW THE ULTIMATE TESLA PSI-GENERATOR WORKS", Global Launch of the ULTIMATE TESLA PSI-GENERATOR by WAVE GENOME. **Click here (https://www.youtube.com/watch?v=Z8Otz0gbqeM)** for the video.

IRENE CAESAR ON WAVE GENOME PRODUCTS

(https://www.youtube.com/watch?v=H8hkdkMMkMg)

DECEMBER 2, 2016

IRENE CAESAR, PH..D, PRESIDENT, FOUNDER AND OWNER OF WAVE GENOME ON WAVE GENOME PRODUCTS, Global Launch of the ULTIMATE TESLA PSI-GENERATOR by WAVE GENOME. **Click here** (https://www.youtube.com/watch?v=H8hkdkMMkMg) for the video.



(https://www.youtube.com/watch?v=6BpWw4R8XBo)

DECEMBER 2, 2016

IRENE CAESAR, PH.D., FOUNDER AND PRESIDENT OF WAVE GENOME, ON POLARIZED BIOHOLOGRAPHY. Click here (https://www.youtube.com/watch?v=6BpWw4R8XBo&feature=youtu.be) for the video.

IRENE CAESAR - VOICE TO SKULL OF MAGNUS OLSSON
Irene Caesar, Ph.D., President and Founder of

(https://www.youtube.com/watch?v=2QgxLxAbkWs&feature=youtu.be)

DECEMBER 2, 2016

IRENE CAESAR, PH.D., FOUNDER AND PRESIDENT OF WAVE GENOME: "WAVE GENOME FOR VICTIMS OF VOICE TO SKULL" (WAVE GENOME helps V2K victim Magnus Olsson). **Click here** (https://www.youtube.com/watch?v=2QgxLxAbkWs&feature=youtu.be)for the video.

(https://www.youtube.com/watch?v=ONPUDcRVgHY&feature=youtu.be)

venation information-wave technologies of the Institute, the Colonel of the Interna

(https://www.youtube.com/watch?v=2BCiU31THbQ)

IRENE CAESAR, PH.D., PRESIDENT AND OWNER OF WAVE GENOME: "WAVE GENOME - LOCAL AND REMOTE BIOELECRONIC DRUGS AS FRONTIER OF QUANTUM LEAP" - LECTURE, HOSTED BY PRAXIS DR. GRUENAGEL, TRANSLATED BY KATIA MEIER, MD (OWNER OF THE CLEAR SKY MEDICAL, PC, IN DENVER, CO), WACHENHEIM, GERMANY, FEBRUARY 18, 2015, PART 1 (https://www.youtube.com/watch?v=2BCiU31THbQ)

PART 2 (https://www.youtube.com/watch?v=2a9dDLfCE5g)

PART 3 (https://www.youtube.com/watch?v=Ntg-IJFC974)

Katia Meier, MD
Irene Caesar, PhD

(https://www.youtube.com/watch?v=PasGu7KjhyQ)

IRENE CAESAR, PH.D., PRESIDENT AND OWNER OF WAVE GENOME: "QUANTUM LEAP VIA WAVE GENOME" - LECTURE, AS PART OF WAVE GENOME'S PARTICIPATION IN EVOLVE EXPO 2015, EVOLVE EXPO 2015, THE NATIONAL WESTERN COMPLEX, DENVER, COLORADO, USA, FEBRUARY 7-8, 2015 (https://www.youtube.com/watch?v=PasGu7KjhyQ)


Irene Caesar PH.D.
- President of Wave Genome Technologies
- Exclusive Representative for Products and Services of the Institute for National Security in Moscow based on the Revolutionary Laser technology of the Quantum Leap.
- www.wavegenome.com

(https://www.youtube.com/watch?v=xWYkXpzVJPo)

KATIA MEIER, MD, REPRESENTATIVE OF WAVE GENOME IN COLORADO, OWNER OF CLEAR SKY MEDICAL, PC, ON HER REPRESENTATION OF WAVE GENOME - LECTURE AS PART OF WAVE GENOME'S PARTICIPATION IN EVOLVE EXPO 2015, EVOLVE EXPO, THE NATIONAL WESTERN COMPLEX, DENVER, COLORADO, USA, MARCH 7-8, 2015 (https://www.youtube.com/watch?v=xWYkXpzVJPo)

transmitted **ONLY** through the zero center of the biohologram / wave matrix (wave crystal). The information is transmitted from one identical token to another identical token of the same unique non-local wave matrix **REMOTELY**
and **INSTANTANEOUSLY**
via **QUANTUM INTERNET**.

WAVE GENOME LLC employs only professional and experienced specialists to administer rejuvenation treatments in its partner clinics and produce its products, including the **TESLA WATER (/tesla-water.html)** and **MINI-TESLA GENERATOR (/tesla-generator.html)**. Majority of **WAVE GENOME LLC** specialists are both MD and Ph.D. and are well-known doctors all over the world.

WAVE GENOME'S LLC scientists have conducted the first in the world experiment for the remote lowering of the blood sugar in a diabetic cow at a distance of 20 kilometers in the mid 1990s. **WAVE GENOME LLC** has eight years of benefiting global market with its services and products, which are patented, licensed, and certified.

2016
Health 2.0 Asia
智慧医疗与大健康产业高峰论坛
International Summit on Smarter Healthcare & Great Health Industry
Irene Caesar
俄罗斯Matrix公司首席执行官；
Genome公司董事长
Irene Caesar
CEO, Matrix Ltd., Russia; Pre
Wave Genome, USA

Irene Caesar, Ph.D., Speech "Remote Management of Biosystems Based upon the Shape of Chromosomes as Diffraction Grating for Focusing Genetic Information", International Symposium HEALTH 2.0, Nanjing, China, November 9-10, 2016.

Irene Caesar
俄罗斯Matrix公司首席执行官；美国Wave Genome公司董事长
Irene Caesar
CEO, Matrix Ltd., Russia; President, Wave Genome, USA

Irene Caesar, Ph.D., Speech "Remote Management of Biosystems Based upon the Shape of Chromosomes as Diffraction Grating for Focusing Genetic Information", International Symposium HEALTH 2.0, Nanjing, China, November 9-10, 2016.

IRENE CAESAR AND MAGNUS OLSSON WAVE GENOME HELP TO V2K VICTIMS
Евгений Гигаури posted in

(https://www.youtube.com/watch?v=zQgSz2_PdG0&spfreload=10)

DECEMBER 2, 2016**. IRENE CAESAR & MAGNUS OLSSON WAVE GENOME HELP TO V2K VICTIMS**. Click here (https://www.youtube.com/watch?v=zQgSz2_PdG0) for the video.

IRENE CAESAR ON QUANTUM LEAP OF WAVE GENOME
0:37 / 8:48

(https://www.youtube.com/watch?v=sgttqrKAFlg)

DECEMBER 2, 2016**. IRENE CAESAR ON THE QUANTUM LEAP OF WAVE GENOME.** Click here (https://www.youtube.com/watch?v=sgttqrKAFlg) for the video.


IRENE CAESAR'S INTERVIEW FOR ALFRED LAMBREMONT WEBRE
15:46 / 59:34

(https://newsinsideout.com/2017/01/dr-irene-caesar-reveals-russian-quantum-leaps-new-science-next-evolution-health-now-available-online-mindtechenterprises-com/)

JANUARY 2, 2017

ARTICLE BY ALFRED LAMBREMONT WEBRE ON DR. IRENE CAESAR AND HER COMPANY WAVE GENOME: "Dr. Irene Caesar reveals Russian Quantum Leap's new science – Our next evolution in health, now available online at MindTechEnterprises.com and wavegenome.com", News Insideout. **Click here** (https://newsinsideout.com/2017/01/dr-irene-caesar-reveals-russian-quantum-leaps-new-science-next-evolution-health-now-available-online-mindtechenterprises-com/) to read the article.


Dr Irene Caesar reveals Russian Quantum Leap's new science - Our next evolution in health
2:20 / 59:34

(https://www.youtube.com/watch?v=OwHafg-VJNI)

DECEMBER 17, 2016

IRENE CAESAR, PH.D., INTERVIEW TO ALFRED LAMBREMONT WEBRE: "Dr. Irene Caesar reveals Russian Quantum Leap's new science – Our next evolution in health, now available online at MindTechEnterprises", By Alfred Lambremont Webre. With the participation of MindTech Enterprises Team -- distributors of products of Irene Caesar's company Wave Genome, Magnus Thorwald Olsson and Madlen Namro. Click here to see the video (https://www.youtube.com/watch?v=2T2VRsJNE34).

Dr. Irene Caesar, CEO, Matrix Ltd., Russia; President, Wave Genome, USA

+View Bio

IRENE CAESAR SEMINAR AT ORANIA ZENTRUM, GERMANY
26:30 / 32:54

IRENE CAESAR'S, PH.D., SEMINAR WELLENGENOM @ ORANIA-ZENTRUM, GERMANY, KURNACH BEI WURZBURG, FILM BY EXTREME NEWS, NOVEMBER 21-23, 2014 (https://www.youtube.com/watch?v=PHPBOCkdmiQ)

(http://www.wavegenome.com/1/post/2013/08/leakpro
the-singularity-irene-caesar-interviews-roman-yampolskiy.html)

LEAKPROOFING THE SINGULARITY: IRENE CAESAR INTERVIEWS ROMAN YAMPOLSKIY, AUGUST 6, 2013 (http://www.wavegenome.com/1/post/2013/08/leakproofing-the-singularity-irene-caesar-interviews-roman-yampolskiy.html)

IRENE CAESAR MATRIX CITY LECTURE AT THE HARRIMAN INSTITUTE (SHORT)

(https://www.youtube.com/watch?v=rVU1MHIruwQ)

IRENE CAESAR, PH.D.: "MATRIX CITY - PUBLIC LECTURE AT THE HARRIMAN INSTITUTE, COLUMBIA UNIVERSITY, SEPTEMBER 13, 2012 (https://www.youtube.com/watch?v=rVU1MHIruwQ)

MORE (/news.html)

In November 2011, Dr. Irene Caesar presented to President Vladimir Putin's Agency for Strategic Initiatives her project of the MATRIX CITY - the self-sufficient city as an integrated information-wave matrix, built with the application of the information-wave technologies of the Quantum Leap. In August 2012, Dr. Irene Caesar offered her project of the MATRIX CITY to the Institute for National Security in Moscow for practical realization. As a result, Dr. Irene Caesar, Founder, Owner and President of Wave Genome, and Dr. Alexej Diaschev had established the Consortium **"Matrix City" (http://www.thematrixcity.com).** Irene Caesar, Ph.D., presented her project of the Matrix City in her public lecture at the Harriman Institute of the Columbia University on September 13, 2012.



DISPATCH FROM MOSCOW

Irene Caesar

Irene Caesar, Ph.D. (born 1963, Russia), is a Russian-American philosopher and conceptual artist who first used psychotronics in art via encoding her portrait with the wave matrix of her Manifesto Man-Sun via lasers of the Institute for National Security in Moscow; Colonel of the International Irkutsk Cossack/Kazak Military; Ataman of the Cossack/Kazak Embassy in the US, awarded the Medal "For Faith and Service to Russia" (January 2015); President at Wave Genome (from 2010); co-founder of the Kazak-TV (cassak.tv) Information Agency (2015); co-founder of the Consortium "Matrix City" with the Institute for National Security in Moscow (July 2012) for building self-sufficient cities as united information-wave matrices with application of information-wave technology of the Quantum Leap for the remote control over biosystems, climate and geophysical processes, and quantum laser-based genetic engineering; founder of the Society for Protecting Negroid Israel (2014); author of the theory and project of "Quantum Biointernet" for the remote laser control over biosystems (July 2013).

Quantum Genetics

We are standing at the greatest turning point in the history of humankind, called Quantum Leap.

Quantum Leap technologies allow us remote management of biosystems, climate and geophysical processes and unlimited access to energy and resources – the systems' management superior to Global Artificial Intellect.

Quantum Genetics plays the leading role in Quantum Leap, since Quantum technologies are operator based, meaning that operator should be one with the Quantum Nonlocality in order to operate Quantum Technologies.

The following presentation on Quantum Genetics is the result of my research from the mid 1980s, and the research conducted by the Soviet Institute "Energy", the largest Scientific Center in the field of Quantum Leap technologies in the USSR, which was founded in 1937, with 5000 scientists, and which was privatized in 2000 as the Institute for National Security.

Wave Genome is an exclusive trade and marketing agent of the Institute for National Security in the field of Quantum Leap technologies applied to health and rejuvenation.

In August 2012, I co-founded the Consortium "Matrix City" with the Institute for National Security for building self-sufficient cities with the help of Russian Quantum Leap technologies.

In August 2012, I also formulated the implication of the holographic principle.This implication theoretically explains the possibility of remote management of biosystems, which was already conducted by the Institute for National Security in 1990s.

In 2013, I co-founded with the Krasnoyarsk research group the Quantum Biointernet for the Remote Rejuvenation via distant laser signal. At that moment, nobody in the world had commercial offering of Remote Quantum Biointernet via Laser Holography. The Krasnoyarsk group itself was operating only by locally applying laser holograms recorded via lasers upon solid material of DVDs.

In the 1980s, I formulated a hypothesis that holograms function as Wave Crystals, which "fold" the signal due to Polarization. Thus, the holographic signal is a "folded signal". The process of folding creates Refraction and Focus (© Irene Caesar 1987).

In 2014, I extended my 1980s Wave Crystal Theory to the Geometrical Optics

Irene Caesar participated in the decedent movement against the communist regime, was invited to make a speech at the founding conference of the Free ...

Source: www.irenecaesar.com

SOCIALIST FACTOR | September 2016 41

(/theory---105810451054105610481071.html)

SEPTEMBER 2016

IRENE CAESAR'S ARTICLE "QUANTUM GENETICS" IN SEPTEMBER 2016 ISSUE OF "SOCIALIST FACTOR" MAGAZINE (LUCKNOW AND LONDON), as the publication of Irene Caesar's paper "Remote Management of Biosystems Based upon the Shape of Chromosomes as Diffraction Grating for Focusing Genetic Information", delivered as lecture at the Bangkok Thonburi University International Symposium, July 23, 2016. **Click here** (http://2016-9-irene-caesar-quantum-genetics-socialist-factor-magazine.pdf) for the PDF of the article.



(https://www.youtube.com/watch?v=MuYnjs6khiU)

OCTOBER 1-2, 2016

IRENE CAESAR'S SEMINAR "REMOTE MANAGEMENT OF BIOSYSTEMS BASED UPON THE SHAPE OF CHROMOSOMES AS DIFFRACTION GRATING FOR FOCUSING GENETIC INFORMATION", Jane Mackenzie's Rejuvenating Centre, Johannesburg. **Click here** (https://www.youtube.com/watch?v=MuYnjs6khiU) for the video.



Health 2.0 Asia 2016

International Summit on Smarter Healthcare & Great Health Industry

Theme: Smart Science & Technology Services Health

Time: November 9-10, 2016 Place: Nanjing, China

15:50-16:10	题目：基于作为聚焦遗传信息衍射光栅的染色体形状的生物系统远程管理 **Title:** Remote Management of Biosystems Based upon the Shape of Chromosomes as Diffraction Grating for Focusing Genetic Information **Irene Caesar**博士，俄罗斯Matrix公司首席执行官；美国Wave Genome公司董事长 **Dr. Irene Caesar,** CEO, Matrix Ltd., Russia; President, Wave Genome, USA

NOVEMBER 9-10, 2016

IRENE CAESAR, PH.D., SPEECH "REMOTE MANAGEMENT OF BIOSYSTEMS BASED UPON THE SHAPE OF CHROMOSOMES AS DIFFRACTION GRATING FOR FOCUSING GENETIC INFORMATION" at the International Health 2.0 Asia 2016 Conference in Nanjing, China, supported by Nanjing Municiple Government, and with the participation of Professor Daniel Shechtman, Nobel Prize Laureate in Chemistry (2011). **Click here (http://www.bitcongress.com/HEALTH2016/default.asp)** for the official webpage of the Summit. **Click here (http://www.wavegenome.com/2016_11_9_10_Irene_Caesar_at_Health_2_Asia_International_Summit_Speaker_List.pdf)** for the official list of participants.

IRENE CAESAR, Ph.D.
Remote management of biosystems based upon the shape of chromosomes as diffraction grating for focusing genetic information
2016 健康2.0亚洲会议 Health 2.0 Asia
国际生物医药产业发展高峰论坛暨人才与项
International Biomedicine Industry Development
中国·南京 2016.11

Irene Caesar, Ph.D., Speech "Remote Management of Biosystems Based upon the Shape of Chromosomes as Diffraction Grating for Focusing Genetic Information", International Symposium HEALTH 2.0, Nanjing, China, November 9-10, 2016.



证书 Certificate

2016 健康2.0亚洲会议 Health 2.0 Asia

Irene Caesar 博士/教授

应邀参加2016健康2.0亚洲会议智慧医疗与大健康产业发展高峰论坛并作大会报告。特发此证！

This is to certify that Dr. Irene Caesar participated as an Invited Speaker in the Health 2.0 Asia 2016 International Summit on Smarter Healthcare & Great Health Industry in Nanjing, China on November 9-10, 2016.

2016健康2.0亚洲会议智慧医疗与大健康产业发展高峰论坛组委会
Organizing Committee of Health 2.0 Asia 2016
International Summit on Smarter Healthcare & Great Health Industry
二〇一六年十一月十日 中国·南京
2016.11.10 Nanjing, China

Irene Caesar, Ph.D., Speech "Remote Management of Biosystems Based upon the Shape of Chromosomes as Diffraction Grating for Focusing Genetic Information", International Symposium HEALTH 2.0, Nanjing, China, November 9-10, 2016.



(https://www.youtube.com/watch?v=bECHfG4WttQ)

OCTOBER 10, 2016

LECTURE BY IRENE CAESAR, Ph.D., "MATRIX AS A GLOBAL

WE OFFER:

1:40 / 20:29
IRENE CAESAR AND MAGNUS OLSSON WAVE GENOME HELP
IRENE CAESAR AND MAGNUS OLSSON WAVE GENOME HELP

Irene Caesar, Ph.D., Founder, Owner and President of WAVE GENOME with Magnus Olsson, President of Mind Tech Enterprises, and Director of World, European and US Coalitions Against Covert Electronic Harassment, one of Distributors of WAVE GENOME.

- **MINI-TESLA PSI-GENERATOR (/tesla-generator.html)**

as a chip (artificial crystal) structured with the generic or personal biohologram / wave matrix by the laser on the nano level for healing, rejuvenation and self-defense from harmful electromagnetic fields, psychotronic and psychic attacks, and genetic warfare;

- **WAVE PHARMACEUTICALS (/wave-pharmaceuticals.html) VIA DIGITAL PHARMACY (/digital-pharmacy-software--1057105410601058-10621048106010561054104210541049-104010551058104510501048.html)**

via generic and individual wave matrices. **WAVE MATRIX** (http://www.wavegenome.com/wave-pharmaceuticals.html) is the hologram, recorded by the laser. **WAVE MATRICES** (http://www.wavegenome.com/wave-pharmaceuticals.html) include (a) INDIVIDUAL WAVE MATRIX (http://www.wavegenome.com/wave-pharmaceuticals.html), recorded by the laser from the childhood photograph, placenta or navel blood, or/and (b) generic **WAVE MATRIX** (http://www.wavegenome.com/wave-pharmaceuticals.html) recorded by the laser from the healthy human cells and bodily systems, and digitised as **DIGITAL CELLS, (http://www.wavegenome.com/wave-pharmaceuticals.html)**(c) generic or personal **WAVE MATRICES (http://www.wavegenome.com/wave-pharmaceuticals.html)** of medications as psi-medications, including such psi-pharmaceuticals, as psi-VYagra, psi-hormones, etc. **WAVE PHARMACEUTICALS (/wave-pharmaceuticals.html)** has various platforms for dispensation, including:

(1) generic or personal **WAVE MATRICES (http://www.wavegenome.com/wave-pharmaceuticals.html),** encoded by the laser in the chip of the **PSI-GENERATOR (http://www.wavegenome.com/order-your-mini-tesla-generator.html)** on the nano level;

(2) **INDIVIDUAL WAVE MATRIX (http://www.wavegenome.com/wave-pharmaceuticals.html), DIGITAL CELL (http://www.wavegenome.com/wave-pharmaceuticals.html)** and **DIGITAL PHARMACEUTICALS (/wave-pharmaceuticals.html)** -



IRENE CAESAR, PH.D.

Remote Management of Biosystems
based upon the
Shape of Chromosomes as a
Diffraction Grating for Focusing Genetic Information

OCTOBER 1-2, 2016

REJUVENATING CENTRE BY JANE MACKENZIE
26 PORTMAN ROAD, BRYANSTON, JOHANNESBURG

www.janemackenzie.co.za
Bookings:

OCTOBER 1-2, 2016

IRENE CAESAR'S SEMINAR "REMOTE MANAGEMENT OF BIOSYSTEMS BASED UPON THE SHAPE OF CHROMOSOMES AS DIFFRACTION GRATING FOR FOCUSING GENETIC INFORMATION", Jane Mackenzie's (http://www.janemackenzie.co.za) Rejuvenating Centre Johannesburg. (http://www.rejuvenatingcentre.co.za)

MANAGEMENT SYSTEM OF LIFE. MECHANISM OF REMOTE MANAGEMENT OF BIOSYSTEMS." Conference "Psychics - yesterday, today and tomorrow", October 10, 2016, (4th Meeting of the Association for Astral Anthropology and Psychology), House of Culture "Scarlet Sails", Moscow, Russia. **Click here** (https://www.youtube.com/watch?v=bECHfG4WttQ) for the video. **Click here (https://www.youtube.com/watch?v=eEKzZQ4Wzcc)** for another version of vidoe recording.

(/theory---10581045105410561048107l.html)

JULY 2016

IRENE CAESAR, PH.D., LECTURE "REMOTE MANAGEMENT OF BIOSYSTEMS BASED UPON THE SHAPE OF CHROMOSOMES AS DIFFRACTION GRATING FOR FOCUSING GENETIC INFORMATION", Bangkok Thonburi University International Symposium, July 23, 2016. **Click here** (https://www.youtube.com/watch?v=XuwV_QCTf2I) for the recording of Irene Caesar's lecture at the Bangkok Thonburi University. **Click here** (https://www.youtube.com/watch?v=pSsgOPUzz9A) for the slide show of Irene Caesar's lecture at the Bangkok Thonburi University International Symposium.



IRENE CAESAR, PH.D.

REMOTE MANAGEMENT OF BIOSYSTEMS BASED UPON THE SHAPE OF CHROMOSOMES AS DIFFRACTION GRATING FOR FOCUSING GENETIC INFORMATION

HEALING VIA WAVE PHARMACEUTICALS
AND QUANTUM BIOCOMPUTING

Weekend Seminar - October 1-2, 2016

Jane Mackenzie's Rejuvenating Centre
Johannesburg

We are proud to present Irene Caesar, Ph.D., extraordinary researcher, President, Founder and Sole Owner of Wave Genome (founded 2010) who created a new "phenomenal new theory" of genetics that perfectly explains Autism and other degenerative diseases (Dr. Jay Dubinsky, co-owner of EGG PHARMA) via the application of Geometrical Optics to Chromosomes.

OCTOBER 1-2, 2016

PRESS RELEASE FOR IRENE CAESAR'S SEMINAR "REMOTE MANAGEMENT OF BIOSYSTEMS BASED UPON THE SHAPE OF CHROMOSOMES AS DIFFRACTION GRATING FOR FOCUSING GENETIC INFORMATION", Jane Mackenzie's Rejuvenating Centre Johannesburg. **Click here (http://www.wavegenome.com/2016_9_1_irene_caesar_seminar_zar_press_release_final.pdf)** for PDF file of the Press Release.



"REMOTE MANAGEMENT OF BIO SYSTEMS BASED UPON THE SHAPE OF CHROMOSOMES AS DIFFRACTION GRATING FOR FOCUSING GENETIC INFORMATION"
LECTURE BY
IRENE CAESAR, PH.D.

THE 2ND INTERNATIONAL
BANGKOK THONBURI SYMPOSIUM 2016
AT
BANGKOK THONBURI UNIVERSITY
23/07/2016

(/theory---10581045105410561048107l.html)

SEPTEMBER 2016

PUBLICATION OF IRENE CAESAR'S, PH.D., PAPER "REMOTE MANAGEMENT OF BIOSYSTEMS BASED UPON THE SHAPE OF CHROMOSOMES AS DIFFRACTION GRATING FOR FOCUSING GENETIC INFORMATION" in the Proceedings of the Bangkok Thonburi University International Symposium, July 23, 2016, also published in the September Issue of the "Socialist Factor" Magazine (Lucknow and London). **Click here** (http://www.wavegenonome.com/2016_BTUSymposium.pdf) for PDF of the BTU Symposium Proceedings.

generic or personalised wave matrices of human cells and pharmacueuticals recorded by lasers, digitised and administered as holographic / granulated signal in the form of the **WHITE NOISE (http://www.wavegenome.com/wave-pharmaceuticals.html)**, encoded into the music in the acoustic and video **PSI-PROGRAM (/digital-pharmacy-software--1057105410601058-10621048106010561054104210541049-1040105510581045105010481048.html)** of the binaural self-therapy. Each psi-generator comes with the flash drive, which contains a software with **COMPREHENSIVE DIGITAL PHARMAC (/digital-pharmacy-software--1057105410601058-10621048106010561054104210541049-1040105510581045105010481048.html)Y** that has 44 digital modules of the digitized wave matrices in the form of the white noise, encoded into the music, for every bodily system (e.g., endocrine system, reproductive system, cardiovascular system, digestive system, etc.) and every vital organ in the body (e.g., liver, kidney, brain, etc.) -- 22 modules for organs and 22 modules for physiological systems. Digital drugs per se, like psi-vyagra or psi-hormones, are offered as extra. White noise, generated by the **PSI-PROGRAM (/digital-pharmacy-software--1057105410601058-10621048106010561054104210541049-1040105510581045105010481048.html)**, can be used for programming water. Digital encoding of wave matrices onto various media via laser is available;

(3) **QUANTUM INTERNET (/quantum-rejuvenation-clinic-om---english.html)** - wireless programming of biosystems, water and human condition via laser. **QUANTUM INTERNET** is **REMOTE, WIRELESS,** and **INDIVIDUALISED;**

- **TESLA WATER (/tesla-water.html)**

Bioactive restructured water charged remotely via **QUANTUM INTERNET** with the use of laser through Quantum nonlocality**,** or charged locally by the white noise (initially programmed by the laser, and, then, digitized), when you run your program of the **DIGITAL PHARMACY** (/wave-pharmaceuticals---digital-pharmacy.html) on your computer. In both cases, you need to purchase **MINI-TESLA PSI-GENERATOR (/tesla-generator.html)**. **TESLA WATER (/tesla-water.html)** is either individualised for every client or generic for specific conditions. **TESLA WATER** can be used in agriculture to increase its productivity manifold;

- **REMOTE REJUVENATION "OM" (/quantum-rejuvenation-clinic-om---english.html)**

via **QUANTUM INTERNET** for all the physiological systems, including endocrine system, digestive system, cardiovascular system, hearing / eye sight, reproductive system, intellectual abilities, improvement of memory, psychic abilities, sexual potency, etc. This service is provided remotely via **WIRELESS QUANTUM INTERNET (/quantum-rejuvenation-clinic-om---english.html);**

- **SUBSCRIPTION PACKAGES FOR MAINTENANCE (http://wavegenome.com/wave-genome---prices.html) (in works)**

Client can purchase the everyday maintenance of his **WAVE MATRIX (http://www.wavegenome.com/wave-pharmaceuticals.html).** Client sends his data to the Institute either via the conventional internet, and via the **QUANTUM INTERNET (/quantum-rejuvenation-**

clinic-om---english.html). HOLOGRAPHIC MAINTENANCE (http://www.wavegenome.com/wave-pharmaceuticals.html) is the correction of the intensity and modules of bioholograms / wave matrices in accordance with the changing client's condition, earthly electro-magnetic activity, solar and lunar activity, geophysical activity, and predicted social unrest. The correction is provided by the specialists of WAVE GENOME LLC remotely or locally. **HOLOGRAPHIC MAINTENANCE (http://www.wavegenome.com/wave-pharmaceuticals.html)** is provided via the update of the digital files in the Digital Pharmacy and by the remote (non-local) laser signal via **QUANTUM INTERNET (/quantum-rejuvenation-clinic-om---english.html).** For example, we can offer the remote management of diabetes;

- **CLINIC with LARGE-SIZE PSI-GENERATORS (/quantum-clinic.html)**

Exclusive rejuvenation services in our partner clinics for restoration and self-defense, especially for patients who were refused by conventional medicine, infertility cases, impotence, drug dependence, and rehabilitation. BIOHOLOGRAPHIC TREATMENT can restore menstruation cycles in the post-menopausal women over 60 years old, so that a woman can again bear a child;

- **TESLA ENHANCEMENT (/quantum-clinic.html)**

Special programs in our partner clinics for those who are seeking to enhance their mental and physical abilities via **LARGE-SIZE PSI-GENERATORS (/quantum-clinic.html);**

- **CONSULTING SERVICES (/ask-our-maven.html)**

regarding the Quantum Leap information-wave technologies by our mavens.

Irene Caesar

Listen to my gospel till it is not too late

(/uploads/3/5/1/1/35112207/4952633_orig.jpg)

OCTOBER 2016

IRENE CAESAR, PH.D., ARTICLE "LISTEN TO MY GOSPEL TILL IT IS NOT TOO LATE" IN OCTOBER 2016 ISSUE OF "SOCIALIST FACTOR MAGAZINE (LUCKNOW AND LONDON). Click here (http://www.wavegenome.com/2016-10-irene-caesar-listen-to-my-gospel-socialist-factor-magazine.pdf) for the PDF of the article.

DISPATCH FROM MOSCOW

Irene Caesar

Irene Caesar, Ph.D. (born 1963, Russia), is a Russian-American philosopher and conceptual artist who first used psychotronics in art via encoding her portrait with the wave matrix of her Manifesto Man-Sun via lasers of the Institute for National Security in Moscow; Colonel of the International Irkutsk Cossack/Kazak Military; Ataman of the Cossack/Kazak Embassy in the US, awarded the Medal "For Faith and Service to Russia" (January 2015); President at Wave Genome (from 2010); co-founder of the Kazak-TV (cassak.tv) Information Agency (2015); co-founder of the Consortium "Matrix City" with the Institute for National Security in Moscow (July 2012) for building self-sufficient cities as united information-wave matrices with application of information-wave technology of the Quantum Leap for the remote control over biosystems, climate and geophysical processes, and quantum laser-based genetic engineering; founder of the Society for Protecting Negroid Israel (2014); author of the theory and project of "Quantum Biointernet" for the remote laser control over biosystems (July 2013).

How to Build Matrix City

The problem with digital insulin seemed to be the fact that digital insulin meant cure. People get cured from diabetes, even type 1. This takes a sick person off the insulin market, and, as a result, the insulin producer loses money. If the technology produces mass healing, the insulin producer would sooner or later get bankrupt. But this is a major misunderstanding of the information-wave technology. This technology is in fact a subscription, rather than simply a cure. You get your own personal matrix in digital form, recorded onto the MINI-TESLA generator. Then, you connect your personal generator every week to the information-wave center, which corrects (tunes) your personal wave matrix, and combines it with digital drugs if needed.

Russian scientists are serving farms with lasers and generators already for many years for the sake of manifold increasing the crop yield. They do not sell generators - they sell only the service.

The same can be done by Big Pharma, after it switches from the analog to the digital. This model of "subscription" or "contract" will involve much more people into the information-wave system than it is now involved by Big Pharma.

Young people can get the service for enhancing their mental and physical abilities. It is possible to enhance sexual performance, and take vitamins and other supplements in the information-wave form.

I believe that in one generation, everybody will be using this technology in every aspect of life. Those who will accept this technology will get a chance to live for 200 years and longer. In 10 years from now, "getting one's maintenance via information-wave technology" will be like brushing one's teeth every morning.

WHAT ABOUT CHIPPING?

I believe that information-wave technology has nothing to do with chipping the population. Chipping the population is the AI paradigm, when the choice is alienated, and the holographic principle is violated. The AI cannot in principle perfect human wave matrices or create a superman (Übermensch), who will be more perfect than humans. Human matrices are "uncreated", non-local, that is-eternal, indivisible, and infinite, while AI is "artificial", limited, divisible, and finite in virtue of definition. AI can in principle only assist in having healthier children.

That is why psi-generators should not be in-built in the human body, but only added to it as a kind of amulets of the psychotronic era. Man is himself a powerful and most perfect generator. Having audacity of installing into a human a generator that is supposed to "control" or "rule" the human is laughable.

I will give you an example so that you understand what I mean. There are clearly two paradigms of Übermensch right now. The first one is a NATO "transformer", stuffed with nanobots, who is a paradigm of cut-and-paste genetic engineering on the bio-chemical-cyber level. The other paradigm is Russian paradigm of non-contact combat. We can enhance a Russian soldier from Special forces with psi-generators, as, in fact, Dr. Diashev does, but we cannot substitute a generator or chip for his mind or "eidos", which is quantum infinity itself, non-local and

Source: futurewarstories.blogspot.com

Women comprise around 20% of most modern military

38 August 2016 | SOCIALIST FACTOR

(/theory---105810451054105610481071.html)

AUGUST 2016

IRENE CAESAR'S ARTICLE (2012) "HOW TO BUILD MATRIX CITY" IN AUGUST 2016 ISSUE OF "SOCIALIST FACTOR" MAGAZINE (LUCKNOW AND LONDON), first published on thematrixcity.com in 2012, as a major document of the Matrix City Consortium (founded August 2012), Co-founded by Dr. Irene Caesar and the Institute for National Security in Moscow. **Click her** (http://wavegenome.com/2016-8-irene-caesar-matrix-city-socialist-factor-magazine.pdf)**e** for the PDF of the article.

PRIVACY POLICY (/privacy-policy.html) SHIPPING POLICY (/shipping--warranty.html) RETURN POLICY (/return-policy.html) TERMS OF SERVICE (/terms-of-service.html)

FDA DISCLAIMER: Content on this site is for reference purposes and is not a substitute for advice from a licensed health-care professional. You should not rely solely on this content, and wave genome.com assumes no liability for inaccuracies. Always read directions before using a product. Statements regarding products and services have not been evaluated by the FDA, and these products and services are not intended to diagnose, treat, cure, or prevent any disease or condition.

Payment in full is due ahead of services. No refunds and returns.

COPYRIGHT NOTICE: Text, graphics, and HTML code on wavegenome.com belong to Irene Caesar, Ph.D., their sole author, and are protected by US and International Copyright Laws, and may not be copied, reprinted, published, translated, hosted, or otherwise distributed by any means without explicit permission from Irene Caesar, Ph.D., and in violation of the International Laws for citing references. Any citation of the wavegenome.com website should be accompanied with the proper reference to Irene Caesar, Ph.D. Any citation exceeding the length, permissible for the reference length by the International Copyright Law, will be considered to be a violation of the International Copyright Law.

© IRENE CAESAR, PH.D., FOUNDER AND SOLE OWNER OF WAVEGENOME 2010-2017 ALL RIGHTS RESERVED

IRENE CAESAR, PH.D. / ИРИНА ЦЕЗАРЬ, ДОКТ. ФИЛОСОФ. НАУК ~ http://www.thematrixcity.com

Tag Archives: *wave pharmaceuticals*

Remote management of biosystems based upon the shape of chromosomes as diffraction grating for focusing genetic information

14 Tuesday Jun 2016

POSTED BY IRENE CAESAR, PH.D. / ИРИНА ЦЕЗАРЬ, ДОКТОР ФИЛОСОФСКИХ НАУК IN NEGROID BLOODLINE OF THE QUEEN OF ENGLAND

≈ 3 COMMENTS

Tags

acrocentric chromosome, chromosome shape, crystalline structure of torus, diffraction grating, digital drugs, e-drugs, electronic drugs, he-ne laser, holographic principle, i-drugs, institute for national security in moscow, irene caesar, matrix city, metacentric chromosome, nano chips of new generation, nanotechnology, polarized holography, quantum biointernet, remote control over biosystems, structuralist genetics, toroidal, torsion, torus, wave crystal, wave genome, wave matrix, wave pharmaceuticals

Remote management of biosystems based upon the shape of chromosomes as diffraction grating for focusing genetic information

Irene Caesar, Ph.D.

June 13, 2016

Abstract

The same gene gets expressed in dysfunctional individuals by acrocentric chromosome, and in functional individuals by metacentric chromosome, and till now nobody was able to explain why. I claim that chromosome functions as wave crystal, i.e., nonlocal unique wave matrix that focuses genetic information unique to this individual via his / her own unique scalar wave diffraction grating. Thus, chromosome is a structural / geometric code or shape that has holographic nature allowing for the remote management of biosystems via laser polarized holography.

Keywords

Irene Caesar, wave genome, polarized holography, chromosome shape, metacentric chromosome, acrocentric chromosome, remote control over biosystems, digital drugs, electronic drugs, quantum biointernet, wave pharmaceuticals, diffraction grating, wave crystal, crystalline structure of torus, nanotechnology, nanochips of new generation, remote laser control system, holographic principle, wave matrix, matrix city, structuralist genetics

Introduction

We can conduct remote laser management of the biosystems, and, thus, create individuals with enhanced physical and psychic abilities, and dramatically extend life span, based upon the implication of the holographic principle (© Quantum Biointernet, Irene Caesar 2013), and mastering the geometric codes of chromosomes.

Objectives

The objective is to build a Matrix City, i.e., the self-sufficient human settlement of the Quantum Leap Era (http://www.thematrixcity.com and specifically: http://www.thematrixcity.com/structure-of-the-matrix-city-r…), where enhanced man in enhanced environment can have enhanced life of any life span he chooses. The objective includes: (1) creating BANKS OF WAVE MATRICES for every living creature on this planet; (2) creating MATRIX CITY ZONES, where individuals receive all their supplements and medications via E-DRUGS and I-DRUGS from the MATRIX CITY based upon subscription model; (3) cultivating men with enhanced physical, intellectual and psychic abilities.

Review of Related Literature

The Polarized Holography is mainly based upon Russian research, especially upon the research of Nikolai Kozyrev, and his so called “Kozyrev Mirror” principle; the structuralist genetics by Alexander Gurvich; as well as upon the toroidal (“torsion”) research by Anatoly Akimov and Gennady Schipov. In 2002 some information got licked to the West, when two researchers of the NPO “Aura” (NPO “Energy”/BINAR, which became “The Institute for National Security” in 2000) Peter Gariaev and George Tertyshny, who did not have clearance and full access to the research, have brought a laser to Toronto to demonstrate remote management of the artificially induced diabetes via the laser signal at a distance of 20 kilometers in the rats of the same genetic line. But Gariaev and Tertyshny did not have access to the Digital Pharmacy of the digitized bioholograms of healthy bodily organs and physiological systems (aka “Digital Cell”), and could not diagnose wave matrices. The technology was classified at that time in Russia, and got declassified only in 2008.

Conceptual Framework

Universe is holographic, i.e., it is entirely contained in its every matrix point. Since universe is holographic, we can record, transmit and receive only holographic information. The implication of the holographic principle states that, If entire universe is contained in its every matrix point (holographic principle), then, every matrix point is not simply different from any other matrix point, but is unique (implication of the holographic principle, © Irene Caesar 2012). If we have an exact copy of the unique nonlocal wave matrix, we can send information instantaneously through Quantum Nonlocality, from one copy of the unique nonlocal wave matrix to the other copy, to any dimension, any planet, or galaxy, to the past, and to the future.

Research Methodology

The chromosome geometry changes the nature of the external signal from linear to holographic (@ Irene Caesar 2012, implication of holographic principle) via (1) torus polarization (via the change of the spin in the integral toroidal field of DNA); (2) reflection of any external linear signal upon itself and creation of the scalar / standing wave diffraction grating, which neutralizes any external signal; (3) refraction of any incoming signal towards the zero center of the wave crystal, which functions as a focus similar to how our eye functions (Irene Caesar, Chromosome Geometry ©2014).

Quantum Leap technology applying knowledge of the chromosome geometry is called “polarized holography”, and is based upon application of stabilized Helium-Neon Lasers with internal mirrors. This kind of lasers are capable of creating holographic signal. Analogously, our bones are capable of producing stem cells, only because the shape of the bone is analogous to laser tube and is capable of changing the nature of external signal.

Research Results

As of today, the Institute for National Security in Moscow offers the local and remote management of biosystems, and individuals:
(1) via electronic / digital drugs (DIGITAL PHARMACY consisting of digitized biohologram s of wave matrices for every healthy bodily organ and physiological system; and including E-DRUGS [additional upon subscription], of which more than 300 are already created, including E-VYAG-RA and I-VYAG-RA);
(2) via remote laser signal (I-DRUGS or Quantum Biointernet).

Institute has conducted the first in the world official and public remote lowering of blood sugar in diabetic calf via the laser signal at the distance of 20 kilometers for the American Diabetic Association in 1999. Over 2015, the Institute has created the digital platform for dispensation of E-DRUGS and I-DRUGS via subscription analogous to mobile phone subscription programs.

E-DRUGS are offered in two forms: (1) as chips inside a pendant [MINI-TESLA PSI-GENERATOR] of electret nature structured by laser on the nanolevel, and (2) as software program on flash drive sold with a MINI-TESLA PSI-GENERATOR, which contains the entire DIGITAL PHARMACY (soon only by subscription).

Discussion

It is clear that the exiting model of Human Genome is not correct, since it cannot explain 98% of DNA calling it “Junk DNA”. Thus, genetic engineering based upon “cutting and pasting” of “identifiable” 2% of DNA is doomed for failure. Only the Holographic Wave Genetics, based upon chromosome geometry, can explain the difference between functional and dysfunctional individuals, and promote the advance in genetic engineering.

Advertisements


THE ONLY SD-WAN
THAT DELIVERS IT ALL
SEE HOW
riverbed

Report this ad


Application
monitoring redefined
Cloud native, AI powered,
automated
Start free trial
dynatrace

Report this ad

Irene Caesar – Article in the “I KNOW” Magazine “On How to Build Matrix City”, March 28, 2015

21 Thursday May 2015

POSTED BY IRENE CAESAR, PH.D. / ИРИНА ЦЕЗАРЬ, ДОКТОР ФИЛОСОФСКИХ НАУК IN NEGROID BLOODLINE OF THE QUEEN OF ENGLAND

≈ 3 COMMENTS

Tags

bci, brain-computer interface, chipping, global artificial intellect, how to build matrix city, i know magazine, irene caesar, matrix city, matrix zones, non-fossil energy, wave genome, wave pharmaceuticals

If the student has a fever then they must lie down to receive the healing. This applies in all cases where the student is unable to sit up comfortably.

Insomnia: *Green and Blue*

Inability to sleep may be the result of too much activity in the solar plexus and the sacral area. The solar plexus may also be congested. Similar problems can also occur in the throat, mideyebrow and forehead, as well as at the crown point.

Repeatedly pass your hands over the patient's body as the treatment progresses and use a combination of blue and green chi to clean the sacral and solar plexus areas.

Sleep can be brought on by use of blue, as it soothes the solar plexus area. Use blue and green to brush the mideyebrow, forehead and crown point and white and tangerine on the navel. Finish with blue.

Do not eat food late in the evening.

Sleep in a separate bed from your partner. You can place two beds next to each other.

Tinnitus

Relates to weakened kidneys. Work on the kidneys, mideyebrow and forehead.

Blood Clotting: *Blue Chi* - Fresh Burns: *Green and Blue Chi*

Because of the cooling and calming properties of blue chi, it can be used to remove the heat from burns. Green has a similar effect.

The area needing treatment should be scanned, then brushed with a combination of pale green/white and blue Chi until relief is felt and the heat in the cells released.

Old Minor Burns: *Green and Red Chi*

Pass your hands over the damaged areas and repeat this during the treatment period. Use pale green/white and tangerine, but do not use on the head, eyes or brain, or other sensitive organs.

To reduce discomfort in the damaged area and promote fast healing, firstly pale blue Chi mixed with white should be employed, followed by cerise mixed with white, and green in equal proportions as this mixture optimizes the breaking down of necrotic cellular material. However, cerise should not be used in the head area but be replaced by mauve mixed with white.

Use cerise/white chi to brush the sacral and navel areas and follow with blue which assists in the release of the stagnant Chi. This session should be repeated for 2 or 3 days.

IRENE CAESAR, PH.D. ON HOW TO BUILD MATRIX CITY

“I KNOW” Magazine, Canada, March 28, 2015

http://www.iknowmagazine.ca/irene-caesar-ph-d-build-matrix-city/



www.iknowmagazine.ca/irene-caesar-ph-d-build-matrix-city/
ikipedia News Popular Screen Shot …4.06.12.png
I KNOW Magazine
HOME CONTACT US FORUM VIDEO AVAILABLE ON AMAZON Find Us Online:
FASHION LIFESTYLE RELATIONSHIP RECREATION AND LEISURE EVENTS ISSUES
NEWS AND POLITICS
LOGIN WITH:
Powered bv OneAll Social Login
To Be or Not to be Page 19

cuánto tiempo se tarda cialis trabajar
ProAdzCycler No Repurchase AdHitz Ads

ABOUT THE POST

AUTHOR INFORMATION

Posted by: Pablo Cobretti

POST INFORMATION

Posted on: March 28, 2015
Posted in: LIFESTYLE
Comments: 0 Comments

SHARE THE POST

Please use the following buttons below to share the post that you are reading with the popular aggregators:

IRENE CAESAR, PH.D. ON HOW TO BUILD MATRIX CITY

By: Irene Caesar, Ph.D., Colonel of the International Irkutsk Cossack Military, Ataman of the Cossack Embassy in the United States, Co-founder of the Consortium "Matrix City" with the Institute for National Security in Moscow.

SUBSCRIPTION INSTEAD OF MEDICATION

Irene Caesar's Article "On how to build Matrix City" in the "I KNOW" Magazine, Canada, March 28, 2015.

Irene Caesar's Article "On how to build Matrix City" in the "I KNOW" Magazine, Canada, March 28, 2015.

By: Irene Caesar, Ph.D., Colonel of the International Irkutsk Cossack Military, Ataman of the Cossack Embassy in the United States, Co-founder of the Consortium "Matrix City" with the Institute for National Security in Moscow.

SUBSCRIPTION INSTEAD OF MEDICATION

The problem with digital insulin seemed to be the fact that digital insulin meant cure. People get cured from diabetes, even type 1. This takes a sick person off the insulin market, and, as a result, the insulin producer loses money. If the technology produces mass healing, the insulin producer would sooner or later get bankrupt. But this is a major misunderstanding of the information-wave technology. This technology is in fact a subscription, rather than simply a cure. You get your own personal matrix in digital form, recorded onto the MINI-TESLA generator. Then, you connect your personal generator every week to the information-wave center, which corrects (tunes) your personal wave matrix, and combines it with digital drugs if needed.

Russian scientists are serving farms with lasers and generators already for many years for the sake of manifold increasing the crop yield. They do not sell generators – they sell only the service.

KONICA MINOLTA
KONICA MINOLTA

Irene Caesar "How to Build Matrix City", "I KNOW" Magazine, Photo credit: GôDiNô / Foter / CC BY-NC-ND

The same can be done by Big Pharma, after it switches from the analog to the digital. This model of "subscription" or "contract" will involve much more people into the information-wave system than it is now involved by Big Pharma.

Young people can get the service for enhancing their mental and physical abilities. It is possible to enhance sexual performance, and take vitamins and other supplements in the information-wave form.

I believe that in one generation, everybody will be using this technology in every aspect of life. Those who will accept this technology will get a chance to live for 200 years and longer. In 10 years from now, "getting one's maintenance via information-wave technology" will be like brushing one's teeth every morning.

WHAT ABOUT CHIPPING?

I believe that information-wave technology has nothing to do with chipping the population. Chipping the population is the AI paradigm, when the choice is alienated, and the holographic principle is violated. The AI cannot in principle perfect human wave matrices or create a superman (Übermensch), who will be more perfect than humans. Human matrices are "uncreated", non-local, that is — eternal, indivisible, and infinite, while AI is "artificial", limited, divisible, and finite in virtue of definition. AI can in principle only assist in having healthier children.

That is why psi-generators should not be in-built in the human body, but only added to it as a kind of amulets of the psychotronic era. Man is himself a powerful and most perfect generator. Having audacity of installing into a human a generator that is supposed to "control" or "rule" the human is laughable.

I will give you an example so that you understand what I mean. There are clearly two paradigms of Übermensch right now. The first one is a NATO "transformer", stuffed with nanobots, who is a paradigm of cut-and-paste genetic engineering on the bio-chemical-cyber level. The other paradigm is Russian paradigm of non-contact combat. We can enhance a Russian soldier from Special forces with psi-generators, as, in fact, Dr. Diashev does, but we cannot substitute a generator or chip for his mind or "eidos", which is quantum infinity itself, non-local and entangled with everything forever.

CULTIVATION OF OPERATORS

Irene Caesar “How to Build Matrix City”, “I KNOW” Magazine, Photo credit: Photo credit: digitalbob8 / Foter / CC BY

The matrix is the energy structure, which has a wave component of indestructible omnipresent nature, i.e., quantum non-locality and quantum entanglement. This infinite wave literally gives life – it heals, increases life span, and gives joy. The point of building Matrix Cities is to have such architecture, agriculture, medicine, industry, energy, education, and all other sides of human life, so that they all have access to this wave component.

That is why the agenda of Matrix Cities would be the cultivating of operators who would be producing wave matrices. This cultivation should be voluntary. And those who do not want to join should be left alone.



Irene Caesar "How to build Matrix City", "I KNOW" Magazine, Canada, Photo credit: sachman75 / Foter / CC BY-NC-ND.

STRUCTURE OF MATRIX CITY

Lasers and generators will constitute the INNER CORE or the NUCLEUS of the Matrix City under the protection of agencies for national security.

The NUCLEUS will consist of concentric circles with centers for the production and conservation of wave matrices.

The center of NUCLEUS will consist in the production of non-fossil fuel generators of energy.

The conservation center will take care of the wave matrices banks for the Matrix Zone.

The NUCLEUS will handle the production of bioactive water, which itself is a generator.

The NUCLEUS will regulate all forms of life in the Matrix Zone, from organism to species, from bacteria to man.

The NUCLEUS will produce lasers and generators.

Around NUCLEUS, there will be a protective perimeter.

Over the protective perimeter, around the NUCLEUS, there will be concentric circles with housing for operators, their centers for education and cultivation, the Secondary Production Centers, and the Subscription Center.

Matrix City will handle subscription to its service. Service should be provided via personal mini psi-generators, which should be connected to the information-wave system of the Matrix City through the internet at least once a week.

The Secondary Production Centers will consist of farms as agro-factories and industrial park, which will produce all components of information-wave technology — bioactive construction and industrial materials, wave pharmaceuticals, etc.

MATRIX ZONES

Old Severe Burns: *Green and Red Chi*

1. Scan at the beginning and end of the treatment (Note:I do not think scan can be seen as plagiarism and I don't know what other word to use in this context as I do not have the full text)
2. The local area should be brushed first with pale green/white and then with pale tangerine white. Keep repeating but make sure to omit sensitive organs and the head area.
3. To speed up healing and reduce pain and infection, the damaged area should be filled with energy from pale blue white, pale green white and mauve with white Chi.
4. To help speed up the healing process, wait a few days until there is much less pain, then use pale green white and cerise mixed with white Chi. If the head area is affected, use mauve mixed with white in place of the cerise.
5. Brush in the sacral and navel areas and to speed up healing use white Chi.
6. After making your healing intent stable, release it.

Old Wounds: *Green and Red Chi*

Green chi, in equal proportion of pale green/white and pale red/white should be employed on injuries which are not new as, when used in large quantities, it attacks and disperses damaged cellular matter, promoting fast healing. On recent injuries, it will have an adverse effect because it is likely to cause the trauma area to become moist, and it also will not be able to work quickly.

> Scan at the beginning and end of the treatment, and brush the damaged area with pale green/white and pale tangerine/white Chi. Some pale blue/white can be employed locally to energise the area. Use of pale green/white followed by cerise mixed with white can speed up the healing process and assist in the breakdown of cellular material.
>
> The navel and sacral areas should be brushed using pale cerise/white Chi. This will fill the area with energy and make the wounds heal faster. Before the Chi is let go, it should be stabilized.

Some Specific Points and Ailments

The following descriptions are mere guidelines. Each case is different and much depends on your own abilities. One needs practice to detect diseases. Best results with Cosmic Healing will be obtained when practiced in combination with Chi Nei Tsang.

Remember that these techniques are not meant to replace the doctor, but merely to assist him. The student must always work with the practitioner. ***The practitioner is a channel, the student the healer.***

Irene Caesar “How to build Matrix City”, “I KNOW” Magazine, Canada, Photo credit: GôDiNô / Foter / CC BY-NC-ND.

The country should be divided into the Matrix Zones. Each Matrix zone should have its own Matrix City, which would serve its zone with wave matrices.

It looks like, advanced people will gather in special zones which are serviced by the Matrix City, the same way as now those who can are looking for areas with better schools for their children. These zones will be ecologically pure, with bioactive architecture, and bioactive water. These zones should accept everyone who wants to join, independently of money. The only condition should be the acceptance of a connection to the Matrix City. But nobody should be forced to join.

This condition will put down all accusations that Matrix Cities are a new exploitation device and a new segregation device. In fact, Matrix Cities should take care of personal, racial and national uniqueness and survival as much as the rare animal species are protected by the Red Book. DNA wave matrices banks should preserve all the variety of human genome.

SPECIAL CHARTER FOR MATRIX CITIES

Generators and lasers producing wave matrices should be protected by the state and agencies for national security.

Matrix Cities should have their own Charter, i.e., be special, semi-military zones, because ultimately this is a more powerful weapon than nuclear bomb, and, if used peacefully, generators will be more desirable thing than gold.

It is completely clear that without the control from the state and agencies for national security, this technology cannot be commercialized in principle. Matrix City is basically a conversion of psychotronic weapons into peaceful applications in industry, medicine, agriculture, etc.

Coca-Cola
Coca-Cola

Irene Caesar "How to build Matrix City", "I KNOW" Magazine, Canada, Photo credit: GôDiNô / Foter / CC BY-NC-ND.

Remote & Wireless Maintenance via Quantum Internet by the Institute for National Security

in Moscow

__15__ Saturday Nov 2014

POSTED BY IRENE CAESAR, PH.D. / ИРИНА ЦЕЗАРЬ, ДОКТОР ФИЛОСОФСКИХ НАУК IN BIOHOLOGRAM, BIOHOLOGRAMS, HE-NE LASER, HOLOGRAPHY, INSTITUTE FOR NATIONAL SECURITY, IRENE CAESAR, MATRIX CITY, ORANIA, POLARISED HOLOGRAPHY, QUANTUM INTERNET, QUANTUM LEAP, WAVE GENOME, WAVE MATRIX, WAVE PHARMACEUTICALS, WELLENGENETISHER HEILUNGSCODE

≈ **3 COMMENTS**

Tags

biohologram, bioholograms, he-ne laser, holography, institute for national security, irene caesar, matrix city, orania, polarised hologrpahy, quantum computer, quantum leap, torus, wave genome, wave matrix, wave pharmaceuticals, wellengenetisher heilungscode, zero field

REMOTE AND WIRELESS MAINTENANCE VIA QUANTUM INTERNET BY THE INSTITUTE FOR NATIONAL SECURITY IN MOSCOW

November 15, 2014



Matrix City © Irene Caesar

In the case of QUANTUM INTERNET, you send your information REMOTELY and WIRELESSLY. At the Institute, the laser reads the feedback from your wave matrix in real time, using your digitised wave matrix on record at the Institute.

According to the holographic principle, the universe is holographic, meaning that it is entirely in its every matrix part. The holographic principle has three important implications:

The first implication of the holographic principle postulates the UNIQUENESS of every wave matrix. if the universe is entirely in its every matrix point, then, every matrix point is not simply different from any other matrix point, but is unique.

The second implication of the holographic principle postulates the NON-LOCALITY of every wave matrix. If the universe is entirely in its every matrix point, then every wave matrix is simultaneously present in the infinite number of dimensions via its tokens. Though there are infinitely many tokens of the same non-local wave matrix, all of them constitute one integrated SYSTEMATIC WHOLE.

The non-local holographic nature of wave matrices also means that the wave matrix has the infinite set of waves, particles and fields within its TORUS — from infinitely micro to infinitely macro dimensions. It is impossible to talk of each individual wave matrix as “a specific frequency”. And it is impossible to postulate any “medium” of its existence, like “scalar wave”, “aether”, “Higgs / boson field”, “torsions”, “leptons”, etc. There is no specific medium for transferring the information.

The third implication of the holographic principle postulates that there is the QUANTUM ENTANGLEMENT in the form of the instantaneous transmission of information between all the tokens of the same non-local wave matrix. The signal that records and transmits the ENTANGLED INFORMATION between different wave matrices or between the tokens of the same non-local wave matrix has specific nature. It is HOLOGRAPHIC. Only lasers can record and transmit holographic signal, based upon the principles of the polarised refraction holography (described in terms of geometrical optics). Thus, the principle of recording and transmitting the MATRIX SIGNAL is structural, and not medium-based.

Thus, it is possible to remotely and instantaneously transfer some wave information to a man via the entanglement between his body (at one location) and his photograph (at another location), as two tokens of his non-local wave matrix.

For example, it is possible to remotely lower blood sugar in a diabetic man via scanning his photograph with the laser ray, which is passing through insulin before reaching the photograph.

© Irene Caesar, Ph.D. from her book “WAVE PHARMACEUTICALS” in co-authorship with Steve Schwartz, MD (2014)

http://www.wavegenome.com

http://thematrixcity.com/structure-of-the-matrix-city-english.html

WELLENGENETISCHER HEILUNGSCODE seminar by Dr. Irene Caesar in Germany:

21. November 2014, Freitag, 18 – ca. 21 Uhr

http://www.orania-zentrum.de/index.php/abendveranstaltungen/infoabend-wellengenetischerheilungscode
http://www.orania-zentrum.de/index.php/seminare/seminar-wellengenetische-heilungscode

(/)



HOME / ГЛАВНАЯ (/)
SERVICES / УСЛУГИ (/SERVICES--105910571051105910431048.HTML)
PRODUCTS / ТОВАРЫ (/PRODUCTS--105810541042104010561067.HTML)
CONTACT / КОНТАКТ (/CONTACT--1050105410531058104010501058.HTML)

ORDER
YOUR MINI-TESLA
GENERATOR

(/tesla-generator.html)

QUANTUM REMOTE REJUVENATION

(/quantum-rejuvenation-clinic-om---english.html)

ORDER
BIOACTIVE
WATER

(/tesla-water.html)

PRICES

Ordering your MINI-TESLA PSI-GENERATOR (/tesla-generator.html), REMOTE REJUVENATION SERVICE (/quantum-rejuvenation-clinic-om---english.html), E-VIAGRA (/tesla-generator.html) and I-VIAGRA (/quantum-rejuvenation-clinic-om---english.html), TESLA BIOACTIVE WATER (http://www.wavegenome.com/order-bioactive-water.html), VISIT TO OUR CLINICS IN MOSCOW OR SIBERIA (http://www.wavegenome.com/visit-our-clinic-for-cure-and-rejuvenation.html), and CONSULTATION (http://www.wavegenome.com/ask-our-maven.html) means you accept the conditions of the Client Consent Form. (/client-consent.html) All Bank fees for payments are paid by the clients.

MODELS OF MINI-TESLA PSI-GENERATOR (/tesla-generator.html)

(1) BASIC TESLA PSI-GENERATOR (chip)

(a) has twice less layers of the chip than our other models**;** (b) has either the **GENERIC** or **INDIVIDUAL** biohologram of a healthy human in the chip, being encoded via laser onto the chip on nano level; (c) **BASIC TESLA PSI-GENERATOR** has both sides of the casing for the chip made of Real Solid Pearl; (d) **BASIC-X TESLA PSI-GENERATOR** has one side of the casing for the chip made of Real Solid Pearl, and another side of casing made of 3D printing plastic, encoded with the immune system rejuvenation **E-DRUG** (**BIOELECTRONIC DRUG** / **DIGITIZED BIOHOLOGRAM**). This makes **"TWO-CHIPS IN ONE"** solution.

GENERIC BASIC MINI-TESLA GENERATOR - $856
INDIVIDUAL BASIC MINI-TESLA GENERATOR - $1179
INDIVIDUAL BASIC-X MINI-TESLA PSI-GENERATOR - $1534

(2) SUPER MINI-TESLA GENERATOR (chip)

(a) has twice as more layers of the chip than the **BASIC MINI-TESLA PSI-GENERATOR;** (b) has either **GENERIC** or **INDIVIDUAL** biohologram; (c) Both sides of the casing for the chip are made of Real Solid Pearl.

GENERIC SUPER MINI-TESLA GENERATOR - $1179

Frequently Asked Questions
FAQ

(/mini-tesla-generator-faq.html)

READ INFORMATION LEAFLET FOR THE (/information-leaflet-for-mini-tesla-generator.html) MINI-TESLA GENERATOR (/information-leaflet-for-mini-tesla-generator.html)

ULTIMATE MINI-TESLA PSI-GENERATOR is the ultimate protection against psychotronic and genetic warfare.

ULTIMATE TESLA PSI-GENERATOR (/ultimate-mini-

WAVE GENOME TESLA GLASSES are not "glasses" per se, but the Quantum Biocomputer. TESLA GLASSES improve eye sight guaranteed, and treat internal organs via Polarized Biohologhraphy.



Irene Caesar, Ph.D., Founder, Owner and President of WAVE GENOME with Magnus Olsson, distributor of WAVE GENOME products.

INDIVIDUAL SUPER MINI-TESLA GENERATOR - $1768

(3) ULTRA MINI-TESLA GENERATOR (chip)

(a) has twice as more layers of the chip than the **BASIC MINI-TESLA PSI-GENERATOR;** (b) has either **GENERIC** or **INDIVIDUAL** biohologram; (c) One side of the casing for the chip is made of Real Solid Pearl, and another side of casing is made of 3D printing plastic, encoded with the immune system rejuvenation **E-DRUG** (**BIOELECTRONIC DRUG** / **DIGITIZED BIOHOLOGRAM**). This makes **"TWO-CHIPS IN ONE"** solution.

GENERIC ULTRA MINI-TESLA GENERATOR - $1768
INDIVIDUAL ULTRA MINI-TESLA GENERATOR - $2358

(4) MATRIX TESLA PSI-GENERATOR (chip)

(a) has twice as more layers of the chip than the **BASIC MINI-TESLA PSI-GENERATOR.**

(b) has either **GENERIC** or **INDIVIDUAL** biohologram.

(c) Both sides of the casing for the chip are made of 3D printing plastic, encoded with the immune system rejuvenation **E-DRUG** (**BIOELECTRONIC DRUG** / **DIGITIZED BIOHOLOGRAM**). This makes **"TWO-CHIPS IN ONE"** solution.

GENERIC MATRIX MINI-TESLA GENERATOR - $2122
INDIVIDUAL MATRIX MINI-TESLA GENERATOR - $2947

(4) ULTIMATE (/ultimate-mini-tesla-psi-generator.html)MINI-TESLA GENERATOR (/ultimate-mini-tesla-psi-generator.html) (chip)

(a) has twice as more layers of the chip than the **BASIC MINI-TESLA PSI-GENERATOR**; (b) has either **GENERIC** or **INDIVIDUAL** biohologram; (c) One side of the casing for the chip is made of Real Solid Pearl, and another side of casing is made of 3D printing plastic, encoded with the RNA **E-DRUG**(**BIOELECTRONIC DRUG** / **DIGITIZED BIOHOLOGRAM**) for the ultimate protection against psychotronic and genetic warfare. This makes **"TWO-CHIPS IN ONE"** solution.

GENERIC ULTIMATE MINI-TESLA GENERATOR - $2358
INDIVIDUAL ULTIMATE MINI-TESLA GENERATOR - $2712 (promotional price)

(5) SECOND-BIRTH TESLA PSI-GENERATOR (/second-birth-mini-tesla-psi-generator.html) (chip)

(a) **chip is encoded by laser on nano level with the most valuable biohologhraphic information on the global market: EMBRYONIC STEM CELL;**

(b) has a new technology of encoding the chip by the newly invented laser (patented);

(c) layers of the chip are made of a new material of organic nature more advanced than our other chips;

(d) its efficacy is proven by the clinical trials at the Medical Clinic of the Moscow Bauman Russian State Technical University, the most important Science University in Russia, of MIT level. twice as more layers of the chip than the **BASIC MINI-TESLA PSI-GENERATOR.**

(e) has either **GENERIC** or **INDIVIDUAL** biohologram.

(f) provides the ultimate modulation for the scalar wave diffraction grating for the most precise focus / zero center of the biohologram (aka 'wave crystal") in the process of rejuvenation.

GENERIC SECOND-BIRTH MINI-TESLA GENERATOR - $3000
INDIVIDUAL SECOND-BIRTH MINI-TESLA GENERATOR - $3500

tesla-psi-generator.html) **IS BASED UPON IMPORTANT DISCOVERY BY DR. IRENE CAESAR REGARDING THE SHAPE OF CHROMOSOMES AS DIFFRACTION GRATING / REFRACTION MECHANISM FOR FOCUSING GENETIC INFORMATION**

ULTIMATE MINI-TESLA psi-generator (/ultimate-mini-tesla-psi-generator.html) has the digitized biohologram of RNA encoded into the casing. RNA is a single-stranded spiral antennae, and it is RNA which sends and receives wave information. While DNA is a double-stranded structure which neutralizes every external linear signal in the standing / scalar / zero wave (reflects every wave upon itself, so that the peak of the forward-going wave is neutralized by the trough of the same wave when it is reflected upon itself and backward-going). Thus, DNA is protected by its very structure. while RNA is vulnerable due to its very structure. Protection against Psychotronic and Generic warfare does essentially consist in tuning RNA, making our chromosomes center and focus our own unique generic information during cell division.

To read about the **ULTIMATE TESLA PSI-GENERATOR click here (/ultimate-mini-tesla-psi-generator.html)**.

Our clinic has AURA PSI-GENERATOR specifically for treating spine issues.

TESLA GLASSES (/order-tesla-glasses.html)

TESLA GLASSES for restoration of eye sight, and treatment of physiological systems and bodily organs via Polarized Bioholography of Eye Crystal and iris. Can be used by all members of the family. Hit of sales - **$1090**

TESLA SELENIUM (/order-tesla-selenium.html)

TESLA SELENIUM MAXI is 60 pills a bottle/pack, each pill is 70 μg of Organic Two-Valent Selenium.**PROMOTIONAL PRICE:**

3 PACKS FOR $210
5 PACKS FOR $300
10 PACKS FOR $500

TESLA SELENIUM PRO is 60 pills a bottle/pack, each pill is 25.0 μg of Organic Two-Valent Selenium, 100 μg of Organic Germanium, and 5.0 mg of Organic Zinc.**PROMOTIONAL PRICE:**

3 PACKS FOR $240
5 PACKS FOR $350
10 PACKS FOR $600

TREATMENTS AT THE CLINIC (/quantum-clinic.html)

TREATMENT AT OUR CLINICS (/quantum-clinic.html) is priced on the individual basis. We help with travel, lodging, escort and interpreting services at extra cost according to regular Russian rates, for example, interpreter is usually billed $177 for the first hour of translation / escort (or below one hour) with $59 for every next hour (regular 8 hours working day); while for working days with overtime (over 8 hours regular working day), client is billed at $177 for the first hour, and $94 for every next hour. We accept only our own interpreters. Clinics are RUSSIAN CLINICS. **WAVE GENOME** does NOT own any of these clinics, but offer **VISITATION** programs for getting treatments at Russian clinics.

PRIVACY POLICY (/privacy-policy.html) SHIPPING POLICY (/shipping--warranty.html) RETURN POLICY (/return-policy.html) TERMS OF SERVICE (/terms-of-service.html)

FDA DISCLAIMER: Content on this site is for reference purposes and is not a substitute for advice from a licensed health-care professional. You should not rely solely on this content, and wave genome.com assumes no liability for inaccuracies. Always read directions before using a product. Statements regarding products and services have not been evaluated by the FDA, and these products and services are not intended to diagnose, treat, cure, or prevent any disease or condition.

Payment in full is due ahead of services. No refunds and returns.

COPYRIGHT NOTICE: Text, graphics, and HTML code on wavegenome.com belong to Irene Caesar, Ph.D., their sole author, and are protected by US and International Copyright Laws, and may not be copied, reprinted, published, translated, hosted, or otherwise distributed by any means without explicit permission from Irene Caesar, Ph.D., and in violation of the International Laws for citing references. Any citation of the wavegenome.com website should be accompanied with the proper reference to Irene Caesar, Ph.D. Any citation exceeding the length, permissible for the reference length by the International Copyright Law, will be considered to be a violation of the International Copyright Law.

© IRENE CAESAR, PH.D., FOUNDER AND SOLE OWNER OF WAVEGENOME 2010-2017 ALL RIGHTS RESERVED

WAVE GENOME

www.wavegenome.com

www.heavenlyharmony.co.za www.orgoniseafrica.com www.rejuvenatingcentre.co.za

IRENE CAESAR, PH.D.

REMOTE MANAGEMENT OF BIOSYSTEMS BASED UPON THE SHAPE OF CHROMOSOMES AS DIFFRACTION GRATING FOR FOCUSING GENETIC INFORMATION

HEALING VIA WAVE PHARMACEUTICALS
AND QUANTUM BIOCOMPUTING

Weekend Seminar - October 1-2, 2016

Jane Mackenzie's Rejuvenating Centre
Johannesburg



We are proud to present Irene Caesar, Ph.D., extraordinary researcher, President, Founder and Sole Owner of Wave Genome (founded 2010) who created "phenomenal new theory" of genetics that perfectly explains Autism and other degenerative diseases (Dr. Jay Dubinsky, co-owner of EGG PHARMA) via the application of Geometrical Optics to Chromosomes.

.

Dr. Irene Caesar is an Exclusive Sales and Marketing Representative of the Institute for National Security in the field of Quantum Leap technologies applied to health and rejuvenation, Co-founder of the Matrix City Consortium (2012) with the Institute for National Security in Moscow for building self-sufficient cities with the help of Russian Quantum Leap technologies, Co-founder of Quantum Biointernet via the remote laser signal (2013) with the Krasnoyarsk Scientific Group, and Colonel of the Irkutsk Cossack Military. Dr. Irene Caesar was awarded the Medal for Service to Russia (2015).

Solar Plexus: *Blue Chi*



The Solar Plexus is the connection point for practically all the nerves inside the body. That is why it becomes laden with emotions so easily. When the Solar Plexus jams up and overheats, the liver will overheat; when this happens, the heart will also overheat; this will in turn affect the thyroid and parathyroid; finally the brain will be affected. Cleaning out this center is therefore extremely important. This type of cleaning may be done from the top down (as in the general cleansing session) or aimed at the Solar Plexus directly. Draw the green light, spiral it, flush with the green light, then energize with white and violet light. As before, always allow the energy to stream through both the points fully. The Solar Plexus holds all the emotions. When working on the Solar Plexus, the most important thing to remember is to connect the backside to the universe. There is literally no end to the 'other' end of this connection. Just allow the Chi to come all the way down and slightly pull inwards a little. Simply clean out the path. Allow the information to condense, allow any images to come out. Then stabilize the energy. Picture the Chi-field enveloping the person as a big protective bubble. Cool down with blue.

Skin Infection: *Blue Chi*

The skin is related to the lungs and the kidneys. Whenever there is an infection, the immune system is involved.

1. Enhance immunity as outlined in pages 101-108.
2. Focus on strengthening the lungs. Always start with green to flush out. Then send orange light into the lungs. Make sure you are not sending it up to the brain. Energize the lungs with blue and white.
3. Detoxify the kidneys, purify the blood (green) and energize with blue. Ask the person to visualize a fresh mountain-stream to stimulate the kidneys.
4. Treat the area locally, using your hands. If the area is big, use your palm, if small use the fingers. Do not focus on your palms - refer to the section 'Forget About Your Palms'. on page 152. Draw green Chi from the forest, and then energize with violet.
5. To diminish pain or itch, use blue to cool down. Also use the Chi knife to work on the infection.

In case the skin problem is allergy-based, you should also treat the mideyebrow; there might be some irritation here. First clean with green, then either energize with

In her July 23, 2016 lecture at the International Symposium of the Thonburi University in Bangkok, Thailand, Dr. Irene Caesar said: “We are standing at the greatest turning point in the history of humankind, called Quantum Leap. Quantum Leap technologies allow us remote management of biosystems, climate and geophysical processes and unlimited access to energy and resources – the systems’ management superior to Global Artificial Intellect.” Quantum Leap gives us cure of “incurable diseases” and radical rejuvenation, so that enhanced man in enhanced environment can live enhanced life of any life span he chooses.

Dr Irene Caesar will be giving her Seminar at Jane Mackenzie’s (MBA, B Pharm) Rejuvenating Centre in Johannesburg, with the assistance of Georg Ritschl, Wave Genome’s Exclusive Representative in the South African Republic. Jane Mackenzie is Wave Genome’s partner, and a leading Rejuvenation Practitioner focusing on epigenetics, nutrigenomics and homotoxicology. Georg Ritschl is the owner of Organise Africa, and a leading producer of Orgonite on the global market.

Dr Irene Caesar is bringing to the South African Republic the World Leading Russian Rejuvenation technology, still classified in the West. Wave Genome technology was created for the first persons in the State, military commanders, diplomats, Special Forces and Olympic Team.

Wave Genome offers:

(1) **MINI-TESLA PSI-GENERATOR**

MINI-TESLA PSI-GENERATOR consists of two parts: (a) Chip (in casing) structured by laser on nanolevel with client’s biohologram recorded by laser from client's childhood photograph; for the **ULTRA MINI-TESLA PSI-GENERATOR**, the casing itself is structured by laser on nanolevel with the biohologram of the immune system rejuvenation **E-DRUG** (electronic drug); (b) flash drive with the complete **DIGITAL PHARMACY** (software) consisting of the digitized bioholograms of all essential bodily organs and physiological systems. Both of these components are not available elsewhere on the global market. **MINI-TESLA PSI-GENERATOR** is a certified protection against V2K (Voice to Skull), and all other kinds of psychotronic weapons, and harmful radiation. THERE ARE NO ANALOGUES ON THE GLOBAL MARKET, or devices that provide actual protection.

(2) **AURA PSI-GENERATOR**

AURA PSI-GENERATOR is a large-size device for radical rejuvenation and enhancement of physical, mental and psychic abilities. **AURA PSI-GENERATOR** comes with revolutionary diagnostics, not available elsewhere, which detects all malfunctions in your body, inaccessible for any conventional diagnostics, via using formerly super secret military technology, which was created by Soviet scientists for detecting enemy in the outer space. **AURA PSI-GENERATOR** has the complete **DIGITAL PHARMACY**, consisting of digitized bioholograms for every essential bodily organ and physiological system, e.g., immune system, endocrine system, etc. For example, complete rejuvenation for clients with diabetes type two takes 10 sessions. Each session is about 2 hours. **AURA PSI-GENERATOR** detects whether a person got any implants, including Nanobots (computers of the molecular size), or whether a person is under Psychotronic attack. After detection, **AURA PSI-GENERATOR** destroys microchips of any kind and protects the client from the Psychotronic or Psychic attack.

Text on the Quantum Leap Technology of Laser Polarized Holography by Wave Genome:
© Irene Caesar, Ph.D. 2016 www.wavegenome.com / mail@wavegenome.com

Jane Mackenzie, MBA B Pharm
Wave Genome’s Partner
www.janemackenzie.co.za / info@janemackenzie.co.za

Georg Ritschl
Wave Genome’s ZAR Representative
https://www.orgoniseafrica.com / orgonisehelpdesk@gmail.com

BOOKING: www.janemackenzie.co.za

HOME / HOME CONSORTIUM / CONSORTIUM PARTNERS / PARTNERS NEWS / NEWS CONTACT / CONTACT

IRINA CAESAR

DOCTOR

OF PHILOSOPHICAL SCIENCES

ABOUT HOW TO BUILD THE CITY OF THE MATRIX

SUBSCRIPTION INSTEAD OF DRUGS

The problem with digital insulin seemed to be that digital insulin meant healing. People are cured of diabetes, even type 1. This leads the patient out of the insulin market, and as a consequence, the insulin producer loses money. If the technology produces mass healing, the insulin producer sooner or later becomes bankrupt. But this is a fundamental misunderstanding of information-wave technology. This technology is actually a subscription, not just a cure. You get your own personal matrix in digital form, recorded on the MINI-TESLA generator. Then you connect your personal generator every week to the information-wave center, which adjusts (adjusts) your personal wave matrix, and combines it with digital medications, if necessary.

Russian scientists have been servicing farms with the help of lasers and generators for many years for the purpose of repeatedly increasing the yield of agricultural crops. They do not sell generators - they only sell services.

The same can be done by large pharmaceutical concerns (Big Pharma) after they switch from analog production to digital. This model of "subscription" or "contract" will include much more people in the information-wave system, than is now attracted by pharmaceutical concerns.

Young people can receive services to increase their mental and physical abilities. It is possible to increase sexual efficiency, and take vitamins and other supplements in information-wave form.

I believe that in one generation, everyone will use this technology in every aspect of life. Those who adopt this technology will have the opportunity to live up to 200 years and longer. After 10 years, "human service through information-wave technology" will be as familiar as brushing your teeth every morning.

HOW ABOUT CHIPS?

I believe that information-wave technology has nothing to do with implanting the population with chips. Implantation of the population by chips is a paradigm of artificial intelligence (AI), when the choice is alienated, and the holographic principle is violated. AI can not, in principle, improve the human wave matrix or create a superman (Übermensch), which would be more perfect than humans. Human matrices are "uncreated," quantum-non-local, that is, eternal, indivisible, and infinite, whereas artificial intelligence is "artificial," limited, divisible, and finite by definition. AI, in principle, can only help in creating more healthy children.

That is why psi generators should not be implanted in the human body, but only added to it as a kind of amulet of the psychotronic era. Man himself is a powerful and most perfect generator. The arrogance of implanting a human generator, which should "control" or "control" a person is ridiculous.

I will give you an example so that you understand what I mean. To this day, there are two distinct paradigms of the superman (Übermensch). The first is a NATO "transformer" stuffed with nanobots, which is a paradigm of genetic engineering at the bio-chemical-cybernetic level on a "cut and paste" principle. Another paradigm is the paradigm of Russian contactless combat. We can improve the Russian soldier from special forces with the help of psi generators, which, in fact, Dr. Diashev does, but we can not replace the generator or chip with the soldier's mind or his eidos, which is the most quantum infinity, non-local and related with everything for good.

CULTIVATION OF OPERATORS


ЗАЩИТНЫЙ ПЕРИМЕТР
ПРОИЗВОДСТВО ЛАЗЕРОВ И ГЕНЕРАТОРОВ
РЕГУЛИРОВАНИЕ ФОРМ ЖИЗНИ
ПРОИЗВОДСТВО БИОАКТИВНОЙ ВОДЫ
УПРАВЛЕНИЕ ПОГОДОЙ И ГЕОФИЗИЧЕСКИМИ ПРОЦЕССАМИ
ХРАНИЛИЩА МАТРИЦ
ПРОИЗВОДСТВО БЕСТОПЛИВНЫХ ГЕНЕРАТОРОВ ЭНЕРГИИ
ЯДРО ГОРОДА МАТРИЦА

STRUCTURE OF THE CITY OF MATRIX

Lasers and generators will be an INSIDE STOCK or NUCLEUS CITY Matrix protected by national security agencies.

The nucleus will consist of concentric circles with centers for the production and conservation of wave matrices.

In the core of the NUCLEAR will be the production of fuel-free energy generators.

The Storage / Matrix Conservation Center will take care of storing the banks of the matrix matrix waveforms.

The nucleus will produce bioactive water, which in itself is a generator.

The nucleus will regulate all life forms in the Matrix Zone, from organism to species, from bacteria to humans.

A matrix is an energy structure that has a wave component with an indivisible ubiquitous character, that is, with quantum nonlocality and quantum confusion. The goal of building Matrix Cities is to have such architecture, agriculture, medicine, industry, energy, education and all other aspects of human life, so that they all have access to this wave component.

That is why the goal of the Matrix Cities will be the cultivation of operators that will produce wave matrices. This cultivation should be voluntary. And those who do not want to connect to the Matrix Cities should be left alone.

The nucleus will produce lasers and generators.

Around the nucleus there will be a protective perimeter.

Behind the protective perimeter, around the core, there will be concentric circles with housing for operators, their training centers and centers for their cultivation, secondary production centers and the Center for Subscription.

The city of Matrix will process a subscription for its services. The service will be provided through personal mini-psi generators, which must be connected to the information system of the City of Matrix via the Internet at least once a week.

Secondary production centers will consist of farms as agro-factories and an industrial park that will produce all components of information and wave technologies - biologically active building and industrial materials, wave pharmaceuticals, etc.

MATRIX ZONES

The country should be divided into Matrix Zones. Each Matrix Zone must have its own City Matrix, which will serve its zone with wave matrices.

Obviously, advanced people will gather in special areas that are serviced by the City of Matrix, just as now those who can, are looking for areas with the best schools for their children. These zones will be environmentally friendly, with bio-active architecture, and bio-active water. These zones should accept all who want to join, regardless of the money. The only condition is to connect to the City of Matrix. But no one should be forced to connect.

This condition will refute all accusations that Matrix Cities are a new invention for exploitation and segregation. In fact, Matrix Cities should take care of personal, racial and national identity and survival, just as rare species of animals are protected by the Red Book. Banks (storehouses) of DNA wave matrices should preserve the entire diversity of the human genome.

SPECIAL LEGAL STATUS OF MATRIX CITIES

Generators and lasers producing wave matrices should be protected by the state and national security agencies.

Matrix cities should have a special legal status, that is, be special, semi-military zones, because ultimately information-wave technology is a more powerful weapon than an atomic bomb, and if it is used peacefully, the generators will be more valuable than gold.

It is perfectly clear that without the control of the state and national security agencies, this technology can not be put on the market in principle. The city of Matrix is essentially a conversion of psychotronic weapons into peaceful use in industry, medicine, agriculture, etc.

© IRENE CAESAR, PH.D., MATRIX CITY, ALL RIGHTS RESERVED, 2012



Quantum Biholography



Genetic Code,



Copyrighted Material

DNA Decipher Journal

Volume 1 Issue 2

March 2011

Wave Genetics, Quantum Bioholograhy
& Quantum Evolution

Brought to You by:
QuantumDream, Inc.

Copyrighted Material



ARTICLE

http://holographicarchetypes.weebly.com/quantum-biohologrpahy.html

(http://holographicarchetypes.weebly.com/quantum-biohologrpahy.html)



DNA Decipher Journal | March 2011 | Vol. 1 | Issue 2 | pp. 1-107
Table of Contents

Table of Contents

Articles

Exploration of Wavegenetics & Wave Immunity
P. P. Gariaev, A. A. Kokaya, E. A. Leonova-Gariaeva, E. R. Muldashev, M. V. Smelov, G. G. Tertishny & N.V.Ustinova

Quantum Biohologrpahy
Iona Miller, Richard A. Miller & Burt Webb

From Helix to Hologram
Iona Miller & Richard A. Miller

Quantum Evo-Devo Universe: Quantum Evolution and the Evidence of Evolutionary-Developmental Biology
Graham P. Smetham

Gariaev, 2012 -

DNA Wave biocomputer functions

- **The problem of creation of the DNA-WAVE biocomputer is considered, in which one the storage locations on genetic molecules will be used. In the basis of tendered idea are trusted to experimental and theoretical activities of the writers, in which one a) to be demonstrated capacity of DNA to the laser, b) capacity of DNA to generate solitonic waves with memory, c) the phenomenon of transition of the localized photons in radio waves is revealed,**

d) the phenomenon of spectral storage of DNA by the localized photons is revealed, e) the transport phenomena of the genetic information in polarization modulations of an electromagnetic field is revealed at transition of a photon - radio wave. On the basis of these data the theory of wave genes is built, in which one the dualistic explanation of the genetic information as unity of material and wave encoding functions of the chromosomes is offered. The hypothesis quantum nonlocality of genome of higher organisms is offered. The set of the obtained outcomes allows the writers to suspect, that artificial DNA computing cannot be carried out to the full without the registration of listed properties of the genetic apparatus. Key pattern of the DNA-WAVE computer will be the phenomenon of DNA memory on solitons and on the localized photons with participation of quantum nonlocality of such memory.



DNA Decipher Journal ("DNADJ," http://www.dnadecipher.com) is a publication in which biologists, physicists, mathematicians and other learned scholars publish their research results and express their views on the origin, nature and mechanism of DNA as a biological program and entity and its possible connection to a deeper reality. This is DNADJ Volume 1 Issue 2 first published in March 2011. It is entitled "Wave Genetics, Quantum Bioholograhy & Quantum Evolution" and contains following articles: (1) Exploration of Wavegenetics & Wave Immunity; (2) Quantum Bioholography; (3) From Helix to Hologram ; and (4) Quantum Evo-Devo Universe: Quantum Evolution and the Evidence of Evolutionary-Developmental Biology.



DNA Decipher Journal Volume 1 Issue 2: Wave Genetics, Quantum Bioholograhy & Quantum Evolution by Quantum Dream Inc. (Mar 29, 2011)

★★★☆☆ (1 customer review)

Formats	Price	New	Used
Paperback Order in the next **19 hours** to get it by **Monday, Mar 26**. Eligible for FREE Super Saver Shipping.	$14.90		

Excerpt - Front Matter: "... **DNA Decipher Journal Volume 1 Issue 2** March 2011 Wave Genetics ..." See a random page in this book.

DNA Decipher Journal Volume 2 Issue 1: Focus Issue on Biocosmology by Quantum Dream Inc. (Jan 31, 2012)

Formats	Price	New	Used
Paperback Order in the next **19 hours** to get it by **Monday, Mar 26**. Eligible for FREE Super Saver Shipping.	$14.90		

Excerpt - Front Cover: "... Decipher Journal **DNA Decipher Journal Volume 2 Issue 1** January 2012 ..." See a random page in this book.

DNA Decipher Journal Volume 1 Issue 3: Quantum Models of Novel Biological/DNA Effects by Quantum Dream Inc. (Nov 30, 2011)

Formats	Price	New	Used
Paperback Order in the next **19 hours** to get it by **Monday, Mar 26**. Eligible for FREE Super Saver Shipping.	$14.90		

Excerpt - Front Cover: "... **DNA Decipher Journal Volume 1 Issue** 3 November 2011 Quantum Models ..." See a random page in this book.

amazon.com



JNLRMI
Journal of Nonlocality
&
Remote Mental Interaction

Quantum Bioholography: a review of the field from 1973-2002

Iona Miller, Richard Alan Miller, and Burt Webb

URL: www.emergentmind.org/MillerWebbI3a.htm (http://www.emergentmind.org/MillerWebbI3a.htm)

Abstract: Complex information can be encoded in EM fields, as we all know from coding and decoding of television and radio signals. Even more complex information can be encoded in holographic images. DNA acts as a holographic projector of acoustic and EM information which contains the informational quintessence of the biohologram. Only 3% of human DNA encodes the physical body. The remaining 97% of the 3 billion base pair genome contains over a million genetic structures called transposons, that have the capacity to jump from one chromosomal location to another (Kelleher, 1999). We are 99.9% alike in our genetic legacy. Our individuality is expressed in three million small variations in our cells, called single nucleotide polymorphisms.

Gene-expression is the mechanism by which new patterns are called into being (Rossi, 2000). There is also a strong correlation between modulation of the brain's EM field and consciousness (Persinger, 1987; McFadden, 2002). The Gariaev group has discovered a wave-based genome and DNA phantom effect which strongly supports the holographic concept of reality (Miller, Webb, Dickson, 1975). This main information channel of DNA is the same for both photons and radio waves. Superposed coherent waves of different types in the cells interact to form diffraction patterns, firstly in the acoustic domain, secondly in the electromagnetic domain -- a quantum hologram -- a translation process between acoustical and optical holograms.

Creative, novel and enriching psychotherapeutic experiences can lead to neurogenesis, gene expression, and healing which facilitate mindbody communication and can have a long-term transformative effect on the whole person (Rossi, 2002). Thus, bioholography has relevant applications for optimizing health, well-being and even self-realization. It is relevant in biophysics, medicine, psychobiology, psychotherapy and the holistic healing arts. It provides us with a more genetically integrated model of the complex dynamics of the mindbody -- one arising in the domain underlying the standard genetic code triplet model.

Wave-genetics, Peter Gariaev

-
    - Brief introduction into WaveGenetics (https://www.facebook.com/groups/wavegenetic/doc/132917683496885/)
    - by Peter Gariaev and Irene Caesar

- **Its scope and opportunities**

  Gariaev Peter

  The history of wave genetics has been developing for more than 80 years. In 20s and 30s of the last century Russian scientists, A G Gurwitsch and A A Lubishev postulated that not only does genetical apparatus of living organisms on the Earth operate at material, physical level but also at...

-
  - The operation of the laser holographic-data converter (https://www.facebook.com/groups/wavegenetic/doc/132916856830301/)
  - by Peter Gariaev (https://www.facebook.com/Peter.Gariaev)
  - For the purpose of acquiring an insight into principles of operation of the laser holographic-data converter, which is in fact – quantum bio-computer (Ref 26), works of Denisuk U N on dynamic holography are of particular attraction (Ref 17). He has developed the basics of holographic imaging of material objects, including objects in motion in ...
-
  - Wave Genetic Bio-Management nanotechnologies. (https://www.facebook.com/groups/wavegenetic/doc/132914663497187/)
  - by Peter Gariaev (https://www.facebook.com/Peter.Gariaev)
  - **Wave Genetic Bio-Management nanotechnologies. Theory and empirical evaluation Tertishnii G.G. and Gariaev P.P. New medicine technologies, №7, p. 49-64 (2007)**

    In this paper a further development of previously propounded theory of external quantum management and self management of organisms 'in vitro - in vivo' by means of bio-holographic...
-
  - Antenna Model (https://www.facebook.com/groups/wavegenetic/doc/132907646831222/)
  - by Peter Gariaev (https://www.facebook.com/Peter.Gariaev)
  - We have noted earlier (Gariaev, Maslova et all, 1996 (a); Gariaev, Maslova et all., 1996 (b)), that in the role of the main molecules perceiving external electromagnetic fields as a regulators – ar the proteins and especially metal containing. Functioning of a set of biological macro-moleculs (ferments in particular) is largely determined ...
-
  - Mathematical Modeling of solitons on DNA (https://www.facebook.com/groups/wavegenetic/doc/132903276831659/)
  - by Peter Gariaev (https://www.facebook.com/Peter.Gariaev)
  - Mario Salerno was the first to experiment with solitons on DNA on computer not only as formal mathematical structures but also tried to link their behavior in a mono-dimensional space of poli-nucleotides with their bio-genetic, or more accurately with their epi-genetic functions. He had been developing the first soliton model on DNA ...
  - 3. Molecular – tissuey “radio stations” (https://www.facebook.com/groups/wavegenetic/doc/132902406831746/)
  - by Peter Gariaev (https://www.facebook.com/Peter.Gariaev)
  - Additional theoretical approaches here, possibly, lie in effects of so called “weak ifluence” [Chukova, 2002]. Apparently regenerative and cytoprotective effects in our experiments bear endoergic character where even weakly absorbed energy of coherent red polarized laser light by the bio-preparations goes in to escalation of Helmholtz free...
-
-
  - 2. Quantum teleportation of genetic-metabolic information/data in permissive version. (https://www.facebook.com/groups/wavegenetic/doc/132898556832131/)
  - by Peter Gariaev (https://www.facebook.com/Peter.Gariaev)
  - (based on works of [Prangishvil ,Gariaev, Maksimenko et al., 2000(б); http://www.wavegenetics.jino-net.ru/zip/Teleport.zip (http://www.wavegenetics.jino-net.ru/zip/Teleport.zip)

    The abovegiven biological experiments on remote transmission of morphogenetic, or more accurately – genetic-metabolic information/data from a donor to recipient may be interpreted from views of non-localized ...
-
  - EXPLORING WAVEGENETICS AND WAVE IMMUNITY. (https://www.facebook.com/groups/wavegenetic/doc/132895870165733/)
  - by Peter Gariaev (https://www.facebook.com/Peter.Gariaev)
  - THEORETICAL MODELS *.

    Gariaev P.P., Kokaya A.A., Leonova-Gariaeva E A., Muldashev E.R., Mikhina I.V.,

    Smelov M.V., Tertishnii G.G., Tovmash A.V., Chalkin S.F., Shatrov Y.K., Yagujinski L.S.

    * Disclaimer: This translation and English text editing have been done to the best knowledge and understanding of the translator who is not a specialist...
  - Last edited about a month ago (Saturday, February 18, 2012 at 5:36am) ·
-
  - Publications (https://www.facebook.com/groups/wavegenetic/doc/132893456832641/)
  - by Peter Gariaev (https://www.facebook.com/Peter.Gariaev)
  - **Publications**

    Publications in foreign journals

    1. Garyaev P.P., Vikhert A.M., Zakharkina G.A., Alexandrova L.G., 1977, Endogenous reserpine-like substances in the myocardium and other tissues of man and animals., USA-USSR First Joint Symposium on Sudden Death. Yalta, USSR, October 3-5, 1977, pp.323-338.

2. Gariaev P.P., Chudin V.I., Komissarov...

Brief Introduction into WaveGenetics
By Peter Gariaev and Irene Caesar in Wavegenetic (https://www.facebook.com/groups/wavegenetic/) **· Its scope and opportunities**

Gariaev Peter

The history of wave genetics has been developing for more than 80 years. In 20s and 30s of the last century Russian scientists, A G Gurwitsch and A A Lubishev postulated that not only does genetical apparatus of living organisms on the Earth operate at material, physical level but also at certain waves/fields level and is able to transfer genetic data/information via electromagnetic (EM) and acoustic waves. The science has recently taken a major leap in its advancements of the theory and reproducible experiments and thus the theory of wave genome has been put forward.

One of the first attempts to rationalize and expound the wave genome theory in Russia had been made by *P P Gariaev* and *A A Berezin* from the department of Theoretical Matters of Russian Academy of Science, and also with participation of A A Vaciliev, a fellow member of Institute of Physics of Russian Academy of Science. As a theoretical foundation, principles of *coherent physical radiations*, *holography* and *solitons*, *theory of physical vacuum*, *fractal representation of DNA* and *human verbal expression/speech* have been employed to describe and substantiate the empirical results obtained through many experiments conducted.

The *quintessence* of the wave genome theory may be represented as following:

genome of the highest organisms is considered to be a bio-computer which forms the space-time grid framework of a bio-systems.

In that bio-system, as the carriers of a field epi-gene-matrix - *wave fronts* are being used, which are assigned by gene-holograms and so-called solitons on DNA – distinct type of acoustic and electromagnetic fields, produced by biogenetic apparatus of the organism/bio-system under consideration and being a medium of strategic regulatory data/information exchange between cells, tissues and organs of the bio-system.

It is also vital to note that the holographic grids/frameworks, which are also the elements of fluctuating structures of solitons, are, in fact, discrete simplest cases of code-originated information, anchored in chromosome continuum of an organism.

At present the dominant viewpoint in respect of genetics and molecular biology is that[1]:

1. **the genetic apparatus functions as a purely material structure**
2. **all the functions of genetic control of an organism occupy approximately 2 % of DNA of a bio-system and fulfill designated functions such as replication of RNA and proteins, so called coding DNA of an organism. The other 98% is considered to be “junk DNA” not carrying out any genetical functions, which may represent a graveyard of virus DNA.**

The biologists and geneticists use the language of analogies and metaphors to explain how genetic apparatus operates. The genetic apparatus consisting of 46 chromosomes is viewed as a library consisting of 46 volumes or books. Each book (a chromosome), contains a text (instructions of how to build an organism) which consists of sentences (DNA) consisting of words (genes). And each word (a gene) consists of 4 letters (certain “chemical letters”), i.e. the “genetic alphabet” consists of only 4 “letters”. The material realizations of the DNA molecules are famous double helixes, consisting of segments which are genes. In essence, genetic apparatus operates as follows. The texts, written in the “DNA language”, are first translated by the organism into the “RNA language” and then into the “Protein language”. And proteins are the stuff that we are mostly made of (not counting water). Proteins perform two principle functions in the organism: they metabolize substances that we eat and participate in the morphogenesis, i.e. development of the spatial-temporal organization of an organism.

It is to be pointed out that the primary focus of the wave genome theory is on the remaining aforementioned 98% of chromosomes as being the *key* “intellectual” structure of all cells of an organism including the brain. It is those chromosomes that operate on the wave, on the “ideal” (fine-field) level.

It the *ideal* component, that may be called super-gene-continuum, is a strategic vital figure/formation that ensures

violet (if resistance is low) or soothe with a light shade of yellow. If the skin problem is related to asthma, open the lungs with bright red clean the throat center with green and energize it with (deep) blue.

If the problem is due to toxicity, also clean out the liver flushing with a combination of green and orange. Energize with green. Enhance the immune system by working on the sacrum.

Eyes: *Green Chi*



The right and left eye are governed by the forehead and mideyebrow respectively. The eyes are also linked to the temples. Ask the person to touch their temple bone and guide them to take in the (white or light violet) Chi. Send Chi through the mideyebrow and forehead (all the way through). Ask the person to visualize the light coming in. Use soft shades of green with golden yellow to stimulate the optic nerve. Use blue to calm the eye muscles and light violet to stimulate the inner eyesight.

The eyes are connected to the liver. Scan the liver and energize with green. Scan the jawbone to see if there is any unreleased anger. Cool down with blue. Channel bright green into the liver.

Ears: *Violet Chi*

The right and left ears are governed by the forehead and mideyebrow respectively. Push and pull green Chi to clean. The ears are connected to the kidneys, so you can work on them also. The ears are also connected to the sinuses and upper respiratory tract. This means that infections need to cool down before you can use any cleaning technique. Use blue to cool and clean with violet. As long as fever and severe infection persist, use blue to cool them down. When clean, energize with violet.

Have Better Health, Less Stress and Remain Young

Brush specifically on the areas of the solar plexus, liver, stomach and pancreas.

White chi brings energy to the crown point, head (at the back) and both sides of the brain.

Both the front and rear of the heart and lungs can receive energy from white/purple Chi.

Both the front and rear of the spleen, the navel and lower abdominal area, the spinal cord, the kidneys, using white Chi.

On the sexual center use white chi but if the problem is difficult to shift, use green. You can also use white Chi on the sacral area, and green or purple on other organs.

development and life of humans, animals, plants and also their *programmable* natural dying. Along with that, it is important to conceive that there is no sharp and insurmountable distinction between genes and super-genes. Both these levels of encoding constitute material (physical) matrixes, however genes supply material replications in the form of RNA and proteins, whereas super-genes transform endo- and exogenous fields, forming from them super-gene-signal wave structures. Furthermore, the genes may be components of holographic grids/frameworks of super-genes and supervise their field activity

Particular attention in the wave genome theory should be devoted to substantiating of the unity of fractal (replicating itself on varying scales) sequence structures of DNA and of a human speech. In 1990 Jeffrey Delrow discovered four "letters" of the genetic alphabet (Adenine, Guanine, Cytosine and Thymine) in DNA "texts" form fractal structures.

Later on, a discovery of similar fractal structures in a human speech, not limited to multy-letter alphabets of Russian and English texts and including a sequence of words from those texts came as a promising surprise for both genetics and linguists. Nonetheless this is in accordance with a branch in semiotics named "*Genetical Linguistics*", which studies incomprehensible and unexplainable precise application of laws of Formal Genetics to formation of interlingual and intro-lingual words-hybrids.

A group of scientists headed by P P Gariaev and M U Maslov, developed a theory of so called fractal representation of natural (human) and genetical languages. Within the confines of this theory it is said that the quasi-speech of DNA possesses potentially inexhaustible "supply of words" and, moreover, what had been a sentence on the scales of DNA–"texts" "phrases" or a "sentence" becomes/turns into a word or a letter on the other scale. Genetical apparatus can be viewed as the triunity of its structure-functional organization consisting of holographic, soliton and fractal structures.

This theory allows a refined quantitative comparison of symbolic structure of any texts including *genetical*. Thereby a possibility has been wide open to approach a deciphering of a lexicon of one's own gene-code, and accordingly, more accurate composition of algorithms of addressing a genome of a human with an aim of potentially any type of programming of one's vital activity such as treatment, increasing one's life expectancy and so on and so forth.

Empirical tests of wave genetic theory in the light of "speech" characteristics of DNA demonstrate strategically correct stance and direction of the research.

Phenomenal experimental findings may be *briefly* presented here. For the first time in history of the science we successfully managed to obtain experimental evidences of abilities of the genetic data/information to function on more than simply one material level, for instance, in the wave/field (electromagnetic) form

Over decades, having been conducting extensive theoretical researches, we successfully managed to formulate theoretical biology and physics-mathematical description, explanation and substantiation of fundamental principles of genetic apparatus functioning on the wave/field level.

These principles allowed us to design and create a *quantum bio-computer* essential element of which is a specially tuned laser beam with certain wavelength and frequency characteristics.

The quantum bio-computer can perform:

i. Scanning and reading the wave/field equivalent of the genetical-metabolic data from the (stem) cells, tissues, organs of a donor's bio-system employing photon of the laser beam;

ii. Conversion of the photons obtained into wide-wavelength-band preserving the scanned and read data;

iii. Precise and pointed introduction of such scanned and converted principal/dominant data radio waves into the organism-recipient, located at a certain distance from the donor's bio-system (from few centimeters to 20 km);

iv. Strategic control/management of metabolism and postembryonic morphogenesis of the organism-recipient according to two vectors/modes:

a. "Do as/what I do" – that is holographic principle, and

b. Wave/field transmission of a signal that contains commands activating required programs in the stem cells of, for instance, rats; programs that direct/guide the stem cells development on their way of, as in our experiments, building pancreas gland in rats. These vectors/modes are intended to be used on humans.

At present we are able to program/manage/encode stem cells of various types by means of a *quantum bio-computer*. The *quantum bio-computer initiates* wave/field-based commands, given to cells and tissues of the donor/recipient, and accordingly the stem cells exposed to the waves/field will be prompted to guided cytodifferentiation leading to emergence and development of planned/projected new organs and tissues. This will bring us closer to the fact of substantially increased life expectancy.

Significant achievements in applying *WaveGenetics* have been made thus far in regeneration of pancreas in rats previously destroyed by chemical substance called alloxan

Three series of experiments with identical protocol were conducted by the groups of P. Gariaev in 2000 in Moscow Russia, in 2001 in Toronto, Canada, and in 2005 in Nizhni Novgorod, Russia. These are more advanced experiments based on the principles and technology of *WaveGenetics*. The goal of the experiments was to test new technology for regenerating damaged pancreas. Pancreas is an endocrine gland which has several vital functions, the major one being production of insulin, a hormone responsible for sugar metabolism.

A control group of rats was injected a lethal doses of a poison called alloxan which destroys pancreas. As a result, all the rats in the control group died from diabetes in 3-4 days. Then the same lethal dose of alloxan was injected to another group of rats. And when the rats reached the critical condition, they were exposed to light images/waves coming from a *quantum bio-computer*. Those light images/waves were created beforehand when the bio-computer read information from the pancreas surgically removed from healthy newborn rats of the same species as those used in the alloxan experiments.

One can explain the results of the experiment using the following analogy. The pancreas gland contains DNA-movies with information about healthy condition of the pancreas in its genetic apparatus. And this video morphogenic information *programmed the stem cells* of sick rats *to regenerate their pancreas gland*. Combined statistics for all 3 series of experiments is as follows. Altogether, around 90% of all the rats had their pancreas gland restored and their health recovered.

In some of the experiments *the quantum bio-computer* was modified to allow successful transmission of the healing information to sick rats at the distance of 20 kilometers. Note, that no known physical fields have the capability to transmit such extremely week signals with such unbelievably powerful results.

Furthermore, the WaveGenetics research and application has significant prospects of solving issues as regards ageing process in humans and increase of life expectancy. This view is grounded on the experiments we have been conducting with rats.

It is Opportunities of technologies of *WaveGenetics* are not limited to what has been outlined above. The development and application of the technology is *far-reaching* and is substantiated by experimental data obtained in numerous tests, experiments, observations.

In addition, it ought to be mentioned, such a technology – a quantum bio-computer, is capable of:

- **treating oncological diseases on fundamentally distinct basis – without use of any chemical substances,**
- **eliminating pathogenic viruses and bacteria and agricultural vermin parasites – also without used of any chemical substances.**

It may seem as a technology of another age, from distant future. However, a discovery of fundamental properties of living organisms is occurring today and it is our task to research and explain the phenomena and bring it to the service of humanity.

Peter Gariaev, Ph.D.,

Director of Wave Genetics Institute,

Russia, Moscow.

Antenna Model

- By Peter Gariaev (https://www.facebook.com/Peter.Gariaev) in Wavegenetic (https://www.facebook.com/groups/wavegenetic/) ·
- We have noted earlier (Gariaev, Maslova et all, 1996 (a); Gariaev, Maslova et all., 1996 (b)), that in the role of the main molecules perceiving external electromagnetic fields as a regulators – ar the proteins and especially metal containing. Functioning of a set of biological macro-moleculs (ferments in particular) is largely determined by processes occurring in the active centres surrounded by bio-polimer sequences having a sign topology. Based on this perception of informational bio-macro moleculs, it is normal to suppose that theyir interaction with physical fields external in relation to the biosystem and internal radiations leads to excitation dipolar-active fluctuations of monomers, forming the said chain, and they in turn induce fluctuation if the active centre. In toher words, such system will work as a peculiar antenna.

  There excited fluctuations can lead to transitioning of bio-macr-molecul in to toher conforming (topological, sign) state.

  Such conception in a principal plane is adequate to the whole set of functionally important bio-macro molecule, for example, chlorophyll, hemoglobin, mioglobin and so on,. These macromolecules are joined by two structural properties: 1) in their geometrical centre there is ion (in the case of chlorophyll – ion of magnium, in the case of hemoglobin –ion of iron); 2) near ion symmetrically placed 4 pirrolik rings (pseudo structure.)

  Other types of polymers, corresponding to antenna model, can be relatively simple cycles such as valinomycine (potassium ions' carrier) and complex over-molecular chromosom structures, DNA of which contains higly organized associates of such metals as magnesium, calcium, nickel, cobalt, copper, ferrum, zink and so on. Their role is not clear and is considered to neutralize OH-groups of remnants of phosphoric acid of polynucleotide. It is proposed that functions of metals in DNA and RNA is substantially wider and is realized along the lines of sign and/or energy interchangewith endo – and exogenous, in relation to the biosystem, physical fields. The same is applicable to the proteinsnot containing porfirine centre yet specifically binding metals, e.g. as such you can considersite-specific proteins with domens like "zink fingers" which participate in regulation genes, often located long awayfrom these governing proteins. Atoms of metals in DNA and proteins can in resonance interact via electromagnetic channels within the meaning of antenna model. Let defined the definition of antenna model.

  External energy (in particular, connected with resonance interaction extremely high frequency electromagnetic radiation with proteins) travels to the periphery, that is onto ensemble of sub-units (not necessarily identical in structures). As a result of an active "conversation" predetermined by bio-chemical links between peripheral acceptor (received encoded energy) and centre-associate (in this case and ion of irongem-containing proteins), the latter receives energy (information) which effects the biological action. The degree of reactive ability of bio-macromoleculs is considerably dependent on the level of excitation of central sub-units. Lets look closely in to potential mechanisms of wave interactions of physical fields and active centres of informational bio-moleculs within the boundries of the proposed antenna model.

  As an example of the simliest model for illustrating antenna effect we consider 2-dimentional closed (cyclic) chain of monomers. There is anactive centre, connected to monomers of chain by dipole-dipole interaction.

  http://eng.wavegenetic.ru/index.php?option=com_content&task=view&id=20&Itemid=1 (http://eng.wavegenetic.ru/index.php?option=com_content&task=view&id=20&Itemid=1)

Molecular – tissuey "radio stations"

By Peter Gariaev (https://www.facebook.com/Peter.Gariaev) in Wavegenetic (https://www.facebook.com/groups/wavegenetic/) ·

Additional theoretical approaches here, possibly, lie in effects of so called "weak ifluence" [Chukova, 2002]. Apparently regenerative and cytoprotective effects in our experiments bear endoergic character where even weakly absorbed energy of coherent red polarized laser light by the bio-preparations goes in to escalation of Helmholtz free energy accumulated in chemical relations of metabolites of bio-preparations, which leads to significant bio-effects. Atoms of informational molecules (DNA, RNA, proteins), interacting with the laser beam together with the energy of the light

quanta also obtain their momentum quantity motion, which creates inversed overpopulation in nuclear zeeman levels, that is – chemical polarization of nucleuses occur. Quantum polarization exit, that is a number of excess kernel spins on the top Zeeman level correlated to the every absorbed quantum of light, can be 30%. Inversely populated protonic-spin system can issue quanta with 6,5·10-26 Jouls of energy which correspond to frequencies of about 10Mhz [Buchachenko, 1979]. Further advancing the aforesaid, one could consider that when bio-preparations are scanned by the laser beam there appears combinative frequencies, occupying blue and UV diapason. Moreover as we previously suggested in an appropriate model of localized light, there is transformation of frequencies in diapason from 2 omega to zero takes place. [Prangishvili, Gariaev et al, 2000 (b)]. Besides when scanning the bio-preparations there is a presence of wideband radio radiation of the gas discharge laser. Taking this into account, we believe that in our experiments bio-preparations-donors are scanned ("read" by the laser) by way of multiplicity of frequencies. Metabolising chemical compounds of bio-preparations, which interact with dynamically polarized red light of the probing laser (and wide spectrum of additional radiation), can generate electromagnetic radiofrequency oscillations. In this instances the bio-samples of pancreas and spleen "assume" a role of idiomatic organ-molecular radio stations where every type of their molecules possess characteristic frequencies that can be reinforced owing to stochastic resonances.

From the other hand, certain types of molecules of pancreas affected by alloxan in the ill animals and/or their stem cells in the blood can resonantly absorb such radiation/emission which carries informational component required for launching bio-chemical eactions which lead to regeneration of tissues of the pancreas and protective anti-alloxan processes. This does not exclude significant contributions of the earlier explored concepts/mechanisms related to teleportational and holographic features/properties of bio-preparation-donor's genome. Let's have recourse to known theses of chemistry and physics http://www.chem.msu.su/rus/publ/Buchachenko/buch5.html (http://www.chem.msu.su/rus/publ/Buchachenko/buch5.html), setting quantum scenario of the genetic-bio-chemical events in question. In the ensemble of molecules-products with inverse population in Zeeman's reservoir/cavity energy is accumulated; it can be spent in the form of heat (via spin-grid magnetic relaxation), but can also convert in to stimulated radiation at Zeeman's nuclear frequency. In this case the reaction does, in fact, become radio frequency emitter, quantum generator with chemical pumping (similar to chemical lasers).

This is new phenomenon – radio emission of a chemical reaction – it was predicted in theory and than discovered empirically. It emerges when Zeeman's cavity/reservoir energy exceeds the generation threshold; the motion of the nuclear spins spontaneously becomes coherent and such coherent system of nucleuses then becomes a quantum generator emittiin in microwave diapason/spectrum. Yet this is only one aspect of chemical radio physics. Chemical reaction can be not only a generator but a receiver of the microwaves. Reception at chemical level follows from principles of spin chemistry: resonant microwave radiation stimulates triplet-singlet conversion of radical couples (or couples of other spin carriers) and alters exit of chemical products. In this way magnetic-spin phenomena make biochemical reaction a receiver of microwave irradiation/emission. Moreover such receiving can be selective. If the microwave pumping touches upon all radical couples (biochemical substratum) then total result boils down to changing the reaction product exit at resonance frequencies. This phenomenon is called reaction yield detected magnetic resonance (RYDMR).

If the "pumping" is selective and involves only radical couples with magnetic nucleuses, a phenomenon is brought about – radio induced magnetic isotopic effect (RIMIE). And, at last, if the microwave "pumping" is selective also in respect of nucleuses' spin orientation (that is involves ensembles of radical couples with chosen orientation of the nucleuses' spins.) then stimulated polarization of the nucleuses (SPN) occur. This is linked to so called spin catalysis It is notable for its spin conversion of reagents being induced by paramagnetic particle-spin catalyzer. Conversion occurs as a result of catalyses (ferment) interactive exchange with reagents. Spin catalyzer accelerates recombination of radicals, wax isomerization of compounds with double connections (by seven-eight orders), recombination of spin-polarized atoms and so on. It is possible that spin catalysis functions in bio-chemical processes of the indicated phenomenon of regeneration of pancreas and in cyto-protective effect. At the base of spin chemistry and chemical radio-physics lays manipulation of electronic and nucleus spins. When such manipulations are performed by the chemical reaction itself, magnetic-spin effects appear and among them – generation of microwaves when the reaction becomes molecular radiostation.

When manipulation with spins occur under microwave influence then other new magnetic effects of the second generation are produces. They serve as indicators of microwave radiation receiving. Spin chemistry and chemical radiophysics are closely related however they have their individual tasks. The former develops new principles of chemical reaction management (including microwaves) whereas the latter possessed significant applied bio-medical aspect to it.

In relation to version (?) of molecular – tissue radiostations vital question arises about highly permeable ability of modulated wideband electromagnetic radiation (MWER). As far as we remember one group of the animals (rats) in our experiment was placed in to isolated concrete ground level chamber and nonetheless the effect of MWER on the animals was authentically and reliably recorded. If biologically (morphogenetically) part of MWER occupies microwave diapason of Zeeman's reservoir then that region of MWER spectrum would have been filtrated by the concrete walls of that ground floor bunker where the rats were placed at the time of wave irradiation on them. Yet the rats perceive/receive the radiation. How?

Possible explanation could be that electrons og Zeeman's level energies of all metabolites including genetic structures whilst existing in a potential "energy pit/cavity" experience supe fine Lamb shift of those levels by about 1000Mhz. This is allowed by existence of longitudinal atomic kernels of photons causing its longitudinal (electrostatic) field which dipolarly excites the vacuum and with this excitation interact moving orbital electrons of atom. They in turn possess their own electrostatic fields composed of similar longitudinal photons.

This way the atomic system of electrons (alternating in time) induces around itself a composit alternation longitudinal electric field which in the form of longitudinal electric wave (LEW) moves instantly in the entire surrounding environment infinitely. Umov-Poynting vector of this wave is equal to zero, that is energy-impulse of this given atomic system is not emitted. However there exist vortexes of longitudinal electric Maxwell's field described by the substantial part of bi- quaternions [Bezin et al, 2003] which are able to transfer information/data which has numerical energy equivalent of Shannon and Brillouin. Yelded in such a way LEW possessing abnormally (incredibly) high permeability properties, passes almost without attenuation through various obstacles (metallic screens, ferromagnetics and dielectrics, concrete and so on). Cellular nucleuses and their main component – DNA – excite solitons [Smelov, 2001] of the linked electron waves and hyper-acoustic fluctuation of liquid crystal chromosomic structures, that is electron-vibron fluctuations [Bersuker, 1976] or electron-nucleus wave fluctuation of DNA's double helix. The said electron-vibron waves retransmit (dissipate) the received LEW back in to the vacuum (ether) and can be received by the other bo-systems similar to the first one (radiated by the primary LEW).

Owing to high corpulence (?)~1014 of all electron-vibron fluctuation systems, they possess high sensitivity estimated in terms of Planck's quantum piece energy for one element of coherent fluctuating chain which can be a DNA spiral or cellular membrane. In opend states DNA spirals, initiated by thermal motion in a living cell, electron-vibron fluctuations exist in the form of solitonic (helicoids, spiral, vortical) motions of atoms in the chain. These are so called Salerno-Maslovs solitons and these are capable of readinginformation from DNA-RNA "text" sequences. Emission/radiation by such "informational" solitons is generated by electron-vibron DNA and RNA fluctuations. Herewith scanned/read information from genetic molecules can be transmitted to other cells (and beyond the bio-system) in a relay mode employing mechanism of dissipation with LEW's frequency alterations irradiated in to the area of radio frequencies and acoustic fluctuations. Along with this, informational radio emission of electron-vibron oscillations in the form of LEW at certain frequencies, in principle, can govern/operate biochemical processes. And the other way around, biochemical reactions in preparations being probed by the polarized laser light can generate electromagnetic radiofrequency oscillations.

Due to probable wave genetic-symbolic bearing of the vortical solitonic states, initiated on DNA and RNA molecules in vivo, let's look at these processes in more details. [Blagodatskix, Gariaev et al, 1996; Gariaev, 1997]

Quantum teleportation of genetic-metabolic information/data in permissive version.

By Peter Gariaev (https://www.facebook.com/Peter.Gariaev) in Wavegenetic (https://www.facebook.com/groups/wavegenetic/) **· based on works of [Prangishvil ,Gariaev, Maksimenko et al., 2000(б); http://www.wavegenetics.jino-net.ru/zip/Teleport.zip (http://www.wavegenetics.jino-net.ru/zip/Teleport.zip)**

The abovegiven biological experiments on remote transmission of morphogenetic, or more accurately – genetic-metabolic information/data from a donor to recipient may be interpreted from views of non-localized contacts in accordance with mechanics of quantum teleportation in permissive version/mode. The laser device, practically – quantum bio-computer (of which we mentioned before), apart from unique capability of wave transfer of morphogenetic information, can also perform a conversion of red coherent photons into radio waves of rather wide spectrum. These very waves – are candidates for the first act of scanning and transmitting.

When scanning bio-samples or some other substances with the laser light, in essence a biologically active spectroscopy is performed of a distinct kind. We propounded a tentative explanation of this phenomenon [Gariaev.

Tertishnii, Gotovskii, 1997], which is primary substantiation of the new king of spectroscopy - called polarized laser-radio-wave spectroscopy (PLRS) [Prangishvili, Gariaev at al., 2000 (b)]. Such spectroscopy is designed to research and examine unknown spin-fluctuating quantum-molecular characteristics of bio-systems, bio-tissues, hard, liquid and gas substances, and also plasma conditions/states. The type of PLRS that we describe here takes a narrow optical diapason – red light, yet it is planned in the future that modification from UV to IR diapason be available.

This present version of the device – He-Ne laser ( ) with generation of two orthogonal linked in their intensity optical modes, which are mobile and depend on the object being probed and are connected in that way so the total of their intensities remains constant irrespective of preparation (bio-sample, tissue) being scanned. When even one of the modes is interacting with the substance, reflected and dispersed emission of which is returned in to optical resonator, redistribution of intensities of these optical modes occur in line with the law of polarization change, attributed to the new state/condition after the interaction of the laser beam with dynamic micro-polarizers, which are located on section/cut of illuminated area of the sample in question. Dynamics of the micro-polarizers is determined by internal dynamics of the object being examined. (metabolism, acoustics of chromosomes and DNA in vivo-in vitro, fluctuations of crystal grids and so on). One of the laser modes, in regime of photons being returned back to resonator, is capable of causing emission/irradiation by our device of modulated radio waves in wide spectrum, correlated with modulations in optical modes of emission in our laser. (Rather complex sentences-the meaning may be lost – rephrase-translator's remarks)

These modulations depend on spinning fluctuating micro-structural components (for instance, of LCC domens in vivo-in vitro) of substances under examination and level of their optical activities. Frequency interval of radio waves created when converting photons in accordance with theoretical model (further below) lies in diapason from 2 up to 0. The maximum of such irradiation is located in the region of 1 MHz. Radio wave signal having been detected is passed to a CPU of a computer with designated software for the signal processing. At the other end Fourier spectrum of radiowaves is recorded, charachterising polarized-dynamic features of substances with which one of the laser beams is interacting and also a spectral memory of emitting substances. The second light beam is returned to the resonator of the laserfor creating a resonance interaction wit hatomic oscillators of the gas mixtures. The reason for photons being converted in to radio waves, as we believe is nonw-stiff dispersion and localization of the light of the main laser modes upon the system of non- homogeneity of the mirrors in the laser resonator. Mechanism for localization (localization in the non-stiff dispersion channel) is given further on. In particular we believe that in the resonator there exists a stiff-dispersed localized light.

The radio wave emission that is generated by the laser is able to "read information", for example, from DNA samples or organs or tissues. The reading mechanism resembles process of usual induced radiation. An option of closing and opening laser's resonator allows localization or "record" in it spectrums of various objects/samples under examination. Radio wave radiation is able to scan and transmit such spectrums. Then we discovered an effect of spectral memory; during a certain macroscopic lengh of time one reproduces radio wave spectrums of objects in question, which reflect the laser beam back into resonator and than removed from the exposition zones. In this way we managed to record DNA spectrums and revealed their highly bio-activities, more likely to be linked with wave mode of transmission of genetic-metabolic information/data. [Gariaev, Leonova, 2003]. IT appears that quantum non-locality of genetic (chromosome) information/data (as manifestation of its total distribution (continuality) inside multi-cell bio-systems), is a particular instance. In reality, there are at least6 levels of non-locality in bio-systems.

Level 1 – organisms' level. Non-locality here is expressed in ability to regeneration, for instance in Planaria worms. After cutting of these organisms, any part of their body reproduces the whole body. In other words in this case there is no an attachment of the common pool of genetic information to any particular part of these worms. The same applies to vegetative reproduction in plants.

Level 2 – cellular. Out of any cell (and not only from zygote) one could grow the whole organism. For living biosystems it is more difficult, however possible. Every cell is a potential continuum of the organism.

Level 3 – cellular-nucleotide. Enucleation of nucleuses from somatic and gamete cells with subsequent injection of other nucleuses does not hinder a normal development of an organism. Cloning of this kind is already being performed on the high bio-systems, sheep for instance. Every cellular nucleus – is a potential continuum of a bio-system. Localization of genetic potencies on certain kind of cells is not the case. Gamete cells perform the same role but with haploid set of chromosomes, combining in zygote in to double set, the same as in somatic cells.

Level 4 – molecular: ribosome "reads" informational RNA not only on separate codons, but the whole of it in certain

context, that is – non locally, but continually.

Level 5 – chromosomic-holographic. Genome possesses holographic memory [Gariaev et al., 1991; Gariaev, 1994], and this is tipically distributed (non-local) associative memory. At this and the subsequent levels non-locality obtaines new quality, dualistic material-wave/field character since the holograms I the same manner as materials are scanned by electromagnetic or/and acoustic fields, which carry genetic-wave information/data beyond material substance of chromosomes. Here we deal with physical field or fields, as calibration formations marking future space-time of an organism. It appears that holographic memory of cortex pertains to this fields as well, which sets mental, rational and imaginary spaces, which calibrate potential actions of higher bio-systems in a socium (?) as a super-organism. This is the highest level of socio-genetic processes.

Level 6 – quantum non-locality of genome. Up to the level 6 genetic information/data non-locality is realized in space of the organism and also in socium. Level 6 has a special character and new quality. It is expressed in one of the forms of quantum non-locality, namely – pemissive, postulated in this paper. In that case non-locality is instantly realized across the space of the bio-system as much as on its own, "compressed" until zeroed - time. Instantaneously distributed in this manner genome-wave programs, isomorphic materially, perform in the organism "here and there at the same time', therefore it is meaningless to use the semantic structure "now and then". This is a strategic factor, incredibly vital evolutionary achievement for multi-cell bio-systems. Billions of cells of the organism ought to "know" one another and about one another if not everything than at least a lot and instantly. Without phenomena of "wave informational instantaneity" gigantic multi-cell continuum if the highest bio-systems is not capable of holistically coordinate metabolism, its own physiological and other functions. Intercellular diffusion of signaling substances and nervous processes are overly slow, inert for these purposes. Even if we suppose that symbolic electromagnetic field as quick as speed of light (which is sensible supposition) take part in intercellular exchange, then this is not sufficient either. It must possess a mechanism of quantum non-locality and it can be applied to genetic apparatus, which may perform as an instantly distributed quantum (wave) object, isomorphic to material chromosomes.

Utilizing non-locality, genetic apparatus of the highest bio-systems creates amazing phenomenon, when at certain moments in "compressed" space-time of bio-system "here and there", "now and then" are working as a continuity providing for the organisms super-coherence, informational super-abundance, super-informed, connectedness and as a result integrity (survival). As a manifestation of these phenomena one can observe regenerative abilities in organd and tissues in inferior organisms (hydra, worms, amphibians, lizards, Crustacea), the ability which has largely been lost by humans. However, it may be activated considering principles of wave self-organization processes that we advance and develop in this paper and in our experiments.

As an illustration of these phenomena serves the very first successful grafting of implanted donor's tissues in a blind human with recovery of vision [Muldashev, 2000]. As a foundation (ideology) for such surgeries and regenerative processes were used our models of morphogenesis and holographic memory of genome. The key moment of this surgery was utilization of donor's retina as a hologram and intercellular substance (alloplant) as systems of additional coordination post-embryonic morphogenesis of the eye, which was in fact predicted earlier [Gariaev, 1994].

Meanwhile these theoretical-experimental researches here are tentative and initial and require physics-mathematical foundation and consideration and advancement. For that reason we show formalized model of photonic-radio-wave processes, brought in to existence when laser beam is interacting with the substances, processes, which can be view as foundation of PLRS and one of the version of quantum informational events in chromosomes.

The fundamental grounding of our ideas lies in theories of localization of light in dispersing space-correlated systems. The Phenomenon of localization of light received a wide acknowledgement since 1985 after works of [Albada, 1985]. Today it is one of most dynamically developing spheres in physics, closely interrelating with such issues as, for instance, quantum teleportation, new methods of recording and reading information and so on.

- **Mathematical Modeling of solitons on DNA**
- **By Peter Gariaev (https://www.facebook.com/Peter.Gariaev) in Wavegenetic (https://www.facebook.com/groups/wavegenetic/) ·**
- **Mario Salerno was the first to experiment with solitons on DNA on computer not only as formal mathematical structures but also tried to link their behavior in a mono-dimensional space of poli-nucleotides with their bio-genetic, or more accurately with their epi-genetic functions. He had been developing the first soliton model on DNA proposed by Englander and et al. This model and its more detailed variations including ours (see further**

below) is represented in term of mechanical systems as a chain of oscillators (DNA base) linked by resilient non-linear sugar-phosphate connections. Following Salerno we have paid particular attention to objectively existing known DNA sequences and thei effects onto solitons behaviour.

In the first stage we have replicated his experiments yet on significantly longer DNA parts. Indeed, solitonic kink excitations are sensitive to the place of their initiation; their motion along one of DNA chains (when they are opened as a result of temperature fluctuations) is accompanied by specific modulation of kink trajectory in time and in single-dimension space of poly-nucleotides. Such solitons are structures that emit electromagnetic and acoustic fields; their inner oscillation structures are capable of reflecting and retranslating texts and other symbolic structures of DNA in to into and out of cellular space at least at the level of large blocks of sequences. As an example behavior of kink on a fragment of singular DNA chain, which is 1020 nucleotides long from a virus of bird sarcoma

C (or S) area of DNA (1 1020 nucleotide) on 3'-end of virus of bird sarcoma contains several "semantically" certain areas such as polypeptide-coding area (between 558 and 675 nucleotides); PolA (936) 3'-end of virus RNA, poly-adeniling site; 916 nucleotide - 5'-end of virus RNA ("capping site"); Red-sector - () – short end replica of the virus genome; Pro – possible component of observing the transcription (between 870-9000); palindrome – "pin" (870 912) .

(5' beginning) GGC CTA TGT GGA GAG GAT GAA CTA CGT GCA CCG AGA CCT GCG GGC GGC CAA CAT CCT GGT GGG GGA GAA CCT GGT GTG CAA GGT GGC TGA CTT TGG GCT GGC ACG CCT CAT CGA GGA CAA CGA GTA CAC AGC ACG GCA AGG TGC AAG TTC CCC ATC AAG TGG AGA GCC CCC GAG GCA GCC CTC TAT GGC CGG TTC ACC ATC AAG TCG GAT GTC TGG TCC TTC GGC ATC CTG CTG ACT GAG CTG ACC ACC AAG GGC CGG GTG CCA TAC CCA GGG ATG GGC AAC GGG GAG GTG CTG GAC CGG GTG GAG AGG GGC TAC CGC ATG CCC TGC CCG CCC GAG TGC CCC GAG TCG CTG CAT GAC CTT ATG TGC CAG TGC TGG CGG AGG GAC CCT GGA GGA GCG GCC CAC TTT TCG AGC TAC CTG CAG GCC CAG CTG CTC CCT GCT TGT GTG TTG GAG GTC GCT GAG TAG TGC GCG AGT AAA ATT TAA GCT ACA ACA AGG CAA GGC TTG ACC GAC AAT TGC ATG AAG AAT CTG CTT AGG GTT AGG CGT TTT GCG CTG CTT CGC GAT GTA CGGGCC AGA TAT ACG CGT ATC TGA GGG GAC TAG GGT GTG TTT AGG CGA AAA GCG GGG CTT CGG TTG TAC GCG GTT AGG AGT CCC CTC AGG ATA TAG TAG TTT CGC TTT TGC ATA GGG AGG GGG AAA TGT AGT CTT ATG CAA TAC TCT TGT AGT CTT GCA ACA TGG TAA CGA TGA GTT AGC AAC ATA CCT TAC AAG GAG AGA AAA AGC ACC GTG CAT GCC GAT TGG TGG AAG TAA GGT GTA CGA TCG TGC CTT ATT AGG AAG GCA ACA GAC CGG GTC TGA CAT GGA TTG GAC GAA CCA CTG AAT TCC GCA TCG CAG AGA TAT TGT ATT TAA GTG CCT AGC TCG ATA CAA TAA ACG CCA TTT GAC CAT TCA CCA CAT TGG TGT GCA CCT GGG TTG ATG GCT GGA CCG TCG ATT CCC TAA CGA TTG CGA ACA CCT GAA TGA AGC AGA AGG CTT CATT 1020 (3'-ending)

In Fig.1 and 2 the kinks appear in a form of "mountine ranges" rather tha as steps, because a derivative of sinus-Gordon equation function was taken. In here a horizontal axis – DNA sequence, vertical – soliton amplitude. Axis to the observer – time. It is visible that wnen soliton's initiation location is altered at certain sequences of poly-nucleotide, the dynamics of that single range/wave is notably alters too in a form of spinning-fluctuating motions along DNA sequence.

The molecul's area under this research is rich functionally (semantically) by biologically significant sectors and we are reasonably expecting that these sectors will alter, modulate, that is – will be introducing/injecting in to a single chain of DNA or RNA "textual" information. This such aspect will be realized in the spectrum of solitonic wave fluctuations alongside poly-nucleotide chain. This spectrum will mirror sequences of nucleotide and by that will perform a role of the carrier of genetic information/data/messages. Such modulation of the fluctuation structures is clearly observed in the presented graphs. It is plausible to believe that spectral composition of oscilating frequencies of solitons appear to be one of the mechanisms of text conversion of DNA and RNA structures in to wave form and a means of transmitting genetic and other messages in a mono-dimentional space alongside the poly-nucleotide chains and/or in 3D of the genome as a single cell as well as the tissue continuum of the bio-system.

The same as Fig.1, apart from the epicenter of the perturbation – 450th nucleotide in here.

This is how the soliton dynamics computer modeling works developed by Salerno after it had been propounded by Englender. Salerno gave formalism describing spin nucleotide fluctuations of DNA molecule in order to explain experimental data in hydrogen-tritium exchange in DNA. In accordance with that model, Engleder, in DNA chain

there can appear (under thermal radiation/noise) and distribute open states ("melting" the DNA double-helix in short segments enriched by AT-couples) in the form of localized dislocations.

Mario Salerno continuing works of Englender in a simplified form, discovered influence of nucleotide sequence on none-linear solitonic dynamics of spin fluctuations of nucleotides within (однотяжных- word is not known by the translator)… DNA areas, which form such open fields (open states). Later, Yakushevich, Fedianin and Khomma et al. revied various generalizations of Englender's model assessing specifics of DNA structuring taking in to account a break in hydrogen connection when the base is opened, paired DNA chains and other aspects of reedom distinct from spinning. However, as it seems, it is not shown in those works the reasons for emergence of dislocations in DNA.

We put forward a possible mechanism of that process in DNA, which is alternative to Englender's hypothesis about thermal noise influence as a cause for opening the bases of couples. We think that dislocations in DNA can be triggered when the period of DNA double-helix is altered (Maslov's proposition). In our model DNA nucleotides are viewd as oscillators suspended on masless non-extendable rod/pivot; sugaf-phosphate links between neighbor nucleotides in the chain are modeled by linear springs, spiralisation along the chain is not taken in to account; hydrogen links between complementary bases are modeled by "gravitational" potential. Hamiltonian, as in accordance with M. Salerno, liiks like the following:

http://eng.wavegenetic.ru/index.php?option=com_content&task=view&id=23&Itemid=1 (http://eng.wavegenetic.ru/index.php?option=com_content&task=view&id=23&Itemid=1)

EXPLORING WAVEGENETICS AND WAVE IMMUNITY.By Peter Gariaev (https://www.facebook.com/Peter.Gariaev) in Wavegenetic (https://www.facebook.com/groups/wavegenetic/) · Edit Doc (https://www.facebook.com/ajax/docs/inline_edit_get.php?group_id=129999910455329&doc_id=132895870165733&permalink=1&show_brief=0)THEORETICAL MODELS *.

Gariaev P.P., Kokaya A.A., Leonova-Gariaeva E A., Muldashev E.R., Mikhina I.V.,

Smelov M.V., Tertishnii G.G., Tovmash A.V., Chalkin S.F., Shatrov Y.K., Yagujinski L.S.

*** Disclaimer: This translation and English text editing have been done to the best knowledge and understanding of the translator who is not a specialist in the field although having a good understanding of Russian language and advanced level of English complemented with rather good understanding of basic physics and biology. The reader is encouraged to seek specialist opinion in any event. Extensive resources are used to understand the concepts in order for the translation to be s precise and accurate as possible. Where possible Russian abbreviations are to be preferred as they represent the most accurate references. An approach of translating the concepts, not the discrete words, has been employed in a belief that this is the most appropriate form of conveying a thought and/or concept from one language into another; of course a detour from this mode is taken where deemed necessary for the sake of clarity.**

All authors have equally contributed to the research in this paper.

Many researchers have pointed out in their works to the dangers posed by geptil pollution to the environment and that it adversely and detrimentally affects health of livings organisms [http://www.seu.ru/conference/ecoprvo/geptil.htm (http://www.seu.ru/conference/ecoprvo/geptil.htm)]. In this present paper a possibility of principled approach to the development of technology is demonstrated, which allows bio-systems to trigger resistance mechanisms to protect the organism from the toxic impact of geptil substance by mean of electromagnetic fields/waves. Theoretical foundations for conducting this kind of research are illustrated on the following website http://www.wavegenetics.jino-net.ru/ (http://www.wavegenetics.jino-net.ru/). Prior to commencing this research/investigation in this direction, we had organised a series of initial model experiments with alloxan. Alloxan is a cytotoxic substance with a dominant detrimental effect on β-cells of pancreas resulting in to Type 1 diabetes.

The earlier experimental works [Gariaev P.P., Kokaya A.A.] have suggested that modulated by pancreas and spleen – modulated wideband electromagnetic radiation (MWER) generated by helium-neon laser influences upon progression of the experimental diabetes in rats. Diabetes is provoked by intro-peritoneal/abdominal injection of alloxan in a dose of 200mg/kg of the mass of the animal.

Irradiating rats with such a frequency resulted in prolonged life expectancy of the animals in the test groups when compared to the control group, leading to normalisation of blood glucose level and, crucially, facilitated pancreas tissue regeneration process.

The aim of this present paper is to assess the phenomenon of resistance to alloxan developed in animals having been previously preventively irradiated by MWER. For that purpose a special laser was used which features interconnected complementary orthogonal polarization of the light beam. Generation of the WER (wideband electromagnetic radiation) was conducted in accordance with Fabri-Perot interferometer's scheme, where the operational laser ray many times passed through the thin freshly-prepared sections/samples of pancreas and spleen from a healthy rat. We believe that the samples specifically and uniquely modulate the laser ray in such a way that this system reveals the following capabilities:

1) reinforce/enhance WER released from discharge interval of He-Ne laser;

2) WER is parametrically connected with the sample-modulated laser ray and as a result it obtains a property of being biologically highly active;

3) biological effect can be observed at relatively long distances from the source of WER;

4) Genetical-metabolic managing/primary information is transmitted from bio-donor to the bio-recipient. The information is carried by MWER (modulated wideband electromagnetic radiation) modulated by the bio-object from the donor

As a donor/bio-structure tissue, probed by the laser beam in the present system, following can be used: living and/or quasi-living organisms, for instance, bacteria, viruses and also living through tissues and organs, metabolites and abiogenic substances.

RESEARCH METHODOLOGY. PHYSICS' PART

To obtain WER modulated by the bio-structures/samples we utilized developed earlier biotechnology with use of helium-neon laser [Gariaev P.P., Tertishni G.G. 1999]. Helium-Neon laser of 2 MW with 632.8 nm of the wavelength possesses two superposed, orthogonal linear polarized modes of emission, single-frequency in each of them. Laser ray probes/scans DNA samples/bio-structures - newly retrieved tissues of pancreas and spleen of a newborn rat Wistar strain. Semitransparent tissues were deposited onto a a lab glass and then covered that by a second lab glass and this "sandwiched" object was fixed in front of the optical axis of the laser. Adjustment of the glasses with the tissues had been done so as to provide partial reflection of the modulated (by the tissues) laser beam back in to the laser resonator. In this way we ensured a multiple passages of the laser beam through the tissues and the tissues be an optical correlator [Mazur, Grachev, 1985] and therefore affect redistribution of the secondary modes of the laser emissions.

Optical signals were registered and transmitted to an electronic circuit, which governs laser's generation regimes; frequency stabilization of the coherent radiation is also performed at this stage. In this mode the laser generates, apart from the red light, WER modulated by the tissues – that is – the MWER itself. Distance from the target to the active element of the laser is 11cm.

RESEARCH METHODOLOGY. BIOLOGICAL PART

Wistar strain of rats matured to reproductive stage, 5-6 months old were used, with average mass of 180-220 gram. Diabetes for the purposes of this experiment was provoked by way of intro-peritoneal/abdominal injection of alloxan in a dose of 200mg/kg of mass of the animal after 24-hour fasting period with normal/common levels of blood glucose level. The animals were divided into 4 groups:

Group 1 control (n=20) – no WER irradiation; Group 2 (n=20) and Group 3 (n=20) – were subject to preliminary irradiation of WER; Group 4 (n=10) – placebo, where WER was not modulated by DNA samples and the laser ray passed through empty lab glasses without the tissues.

Group 2 rats were placed 20 meters from the source of MWER in the lower ground level of the lab. Alloxan diabetes was provoked one month later from the day of the last irradiation by MWER.

White Chi can be employed for the arms and hands, while the legs and feet should be treated with white and purple Chi.
Eye problems with green/yellow energy.

After a session, patients who are particularly weak should not bathe for one full day. The energy which has been put into their bodies can thus be kept there by application of pale blue/white Chi at the end of the session.



Fig. 6.18 *Use Compassion, Love and Kindness.*

Summary of Individual Healing Session

A. Chi Knife
B. Energizing and Activating the Immune System
C. Cleansing with the Internal Organ Techniques

General Outline of Practices

1. Gain experience by working with one person. **Stand in front of them with your feet shoulder width apart.** Hold your hands at your heart in salutation. Transmit your love and compassion and ask for their permission to help them to help themselves heal.

Group 3 and Group 4 were placed 70 cm from the source of MWER. Alloxan diabetes in these groups was triggered one day after the last irradiation by MWER.

Irradiation by MWER of Group 2 and Group 3 was being performed daily for 30 minutes during 4 days scheduled as follows: 10 minutes irradiation by MWER (modulated by samples of pancreas), 10 min irradiation by MWER (modulated by samples of spleen) and 10 minutes irradiation by MWER (modulated by samples of pancreas).

Group 4 – placebo – was being irradiated by WER – not modulated by any samples the laser beam though passing through the empty lab glasses – for 30 minutes daily during 4 days.

Group 1 – control - was not subject to the irradiation by WER nor was it by MWER.

During the experiment we assessed general health condition of the experimental animals, recorded the death date for the animals from the moment of alloxan injection, in all observed groups. The animals of Group 2 and Group 3 were observed for 1.5 months from the day of alloxan injection. In 8 animals from Group 2 and 3 were recorded with the reproductive function still active when the blood glucose level reached its peak value. (3 rats from Group 2 and 5 rats from Group 3).

Measurements of the blood glucose level were performed by glucometer Ascensia Entrust made by Bayer. Measurement range of the glucose level spreads from 2.0 mmol/l up to 30.6 mmol/l. Measurements of glucose level higher than 30.6 mmol/l were marked as HI.

Removal of heart- lung- liver- kidney- spleen- and pancreas- tissues was done in order to perform microscopic description and histological analysis in:

Group 1 – control – on day 3 and 4 after alloxan injection which corresponded to the highest death rate of the animals;

Group 2 and 3 on the day 8 from the alloxan injection, and also on the 42 day of the experiment after assessing reproductive function in male animals.

For histological analysis purposes the tissue had been fixed in 10% neutral formalin, dehydrated in spirits of increasing concentration and then sealed them in paraffin wax. Paraffin sections of 5-7 micro kilometers thin were obtained on microtome Leica SM 2000R, were colored in hematocsilin-eosin and then analysed by microscope Leica DMLS. Video footage was obtained by using CCD-cameras.

Statistical survey of the experiment's results were conducted by means of using statistical software suits "Stastica 6.0", MS-Exel" for Windows. Degree of accuracy (p) was determined using Student criterion, employing confidential coefficient and a digit of degree of freedom (1) in accordance with table. Calculations of all mathematical values had been performed in compliance with commonly known formulas on a PC.

Research in this series of experiments revealed that application of the said dose of alloxan in control and placebo groups developed diabetes complicated by toxic damage of live-crucial organs and systems. This led to low survival rate of the animals in within the groups. On the contrary, in Group 2 and 3 we observed resistance/increased immunity in the animals to the detrimental/destructive effects of alloxan expressed in various degrees.

Group 1 – control – survival rate after alloxan injection of the animals on the day 2 was 55% yet by the day 4 it went down to 30% (Fig.1). Glucose level in Group 1 animals on day 2, 3 and 4 is reliably distinct ($p<0.05$) from the initial value/level (Table 1). Animals dying in Group 1 (control) at terminal stage were put down by euthanasia (5 rats), organs used for patho-morphological analysis. There was no discrete/spontaneous reduction in glucose level in Group 1 (control) within the period of monitoring. However, there was one rat exhibiting resistance to alloxan and its blood glucose level remained within the limits. Table 1. Blood Glucose level over time in animals after alloxan injection, dose of 200mg/kg of the mass

*** - blood glucose level in Group 3 by the 2nd, 3rd, and 4th day of initiating alloxan diabetes is different ($p<0.05$) from the level of glucose in blood of the animals in Groups 1 and 2 by the 2nd, 3rd, and 4th day, and is also different ($p<0.05$) from glucose level in blood from the animals in Group 4 by the 2nd day;**

**** - blood glucose level in Group 1 by the 2nd, 3rd, 4th day is in fact different ($p<0.05$) from the initial level;**

***** - blood glucose level in Group 2 by the 2nd, 3rd, 4th day is different ($p<0.05$) from the initial level;**

****** - blood glucose level in Group 4 by the 2nd day is different ($p<0.05$) from the initial level;**

^ - in Group 4 by the 3rd and 4th day of observance there was one survived rat.

All animals were injected alloxan – 200mg/kg of an animal mass. Group 1 (control) was not subject to WER or MWER. Group 2 – MWER was conducted; the animals were places 20 meters from the source of emission. Induction of alloxan diabetes was effected one month later after the last radiation by MWER. Group 3 – MWER was conducted, animals were located 70 cm from the source. Induction of alloxan diabetes was done one day after the last radiation by MWER. Group 4 – placebo – was irradiated by WER – not modulated by DNA samples (that is to say that the laser beam was passing through the empty lab glasses). The animals were placed 70 cm from the source of the emission. Alloxan diabetes was induced a day after the treatment.

Animals in Group 4 – placebo - were observed with altered glucose level different from the initial one ($p<0.05$). 80% of the animal survived by the day 2 and only 10% remained alive by day 4. This was considerably at variance with what we observed in Group 2 and Group 3; Group 1 exhibited lower death rate and survival was at 30%. (Fig. 1)

Preventive irradiation by MWER significantly influences the alloxan diabetes progression in the animals of Group 2 and Group 3 (Figs. 1, 2, 3, Table 1) and is accompanied by safeguarding, cyto-ptotective effect. (Fig. 4). That had been seen in both abovenamed Groups despite the fact that diabetes in Group 2 was induces a month later after the last preventive irradiation/treatment

Survival rate in Group 2 (n=20) reached 90% by the 3rd and 4th day from the moment of alloxan injection (Fig.1) which is significantly distinct from survival data obtained from the control Group (30%) and in the Group 4 (placebo) (10%). Glucose level increase ($p<0.05$) is observed in Group 2 animals by day 2, 3 and 4 when compared with the initial value (Table 1). By the 4th day 13 animals in Group 2 (65%) the glucose level in their blood was 14.5 mmol/l, whereas 5 animals (25%) from the same group were observed with normal physiological level of glucose (Fig.2)

Glucose level in Group 2 by the 4th day is ($p<0.05$) different from the initial level. (Table 1). By the 7th day in Group 3 survival rate decreased to 75% (out of 20 animals with hyperglycemia 5 animals died) and remained at the same level up to the end of observation term (1.5 months Fig.1). By the 8th day euthanasia had been conducted to 6 animals from Group 2 and tissues were extracted for patho-morphological analysis. The other 9 animals were observed for a period of 1.5 months. It is important to note that from the day 8 up to 15th animals with hyperglycemia a reduction in glucose level was observed (Fig. 2).

However by the 18th day 4 animals of Group 2 regained the hyperglycemia (more than 30,6 mmol/l) which remained during the entire observation period. The overall health condition of these 4 animals were assessed as satisfactory. Similar results were present during our previous experiments [Gariaev, Kokaya et al, 2007]. The other 5 animals maintained normal level of glucose.

Reproductive functions were noted in 3 animals of Group 2 with hyperglycemia (glucose level over 30.6 mmol/l). These animals gave birth to healthy multiple posterity. After 1.5 months tissues were extracted for the analysis.

Fig.2 Effects of preventive/preliminary irradiation by MWER on progression of alloxan induced diabetes in Group 2.

Alloxan was injected at 200mg/kg dose one month after the preventive irradiation by [MWER] modulated wideband electromagnetic radiation/field. The irradiation was being performed for 4 days, 30 minutes in each day. Distance from the radiation source – 20 meters. The irradiation schedule: 10 min irradiation time using tissues of the pancreas, then 10 minutes of the spleen tissues, and for 10 minutes – pancreas tissues. The beginning is the day of the alloxan injection.

The most manifested effects were observed in Group 3 located at 70 cm distance from the source of the modulated waves. Alloxan diabetes modeling was performed one day after the irradiation by MWER ended (Fig.1,3, Table 1). Every animal in the Group survived. We observed 100% survival rate during the entire period. It is clear that 90% of animals retained their normal physiological glucose level during the 1.5 month of observation, which is clearly different ($p<0.05$)

from the control Group, Group 4 and Group 2.

However 2 animals from Group 3 by the day 6 of the experiment had excessive glucose level increase of 20 mmol/l with subsequent reduction to the normal level. On the 8th day of the experiment6 animals were performed euthanasia for a patho-morphological analysis. Reproductive function could be detected in 5 animals of Group 3. All the animals gave birth to a healthy posterity. 1.5 months later tissues from 6 animals from the same Group were taken for the analysis. Glucose level was at normal levels. Health condition of all the animals of Group 3 was satisfactory.

Fig.3 Effects of preventive/preliminary irradiation by MWER on progression of alloxan induced diabetes in Group 3.

Alloxan was injected at 200mg/kg dose one day after the preventive irradiation by [MWER] modulated wideband electromagnetic radiation/field. The irradiation was being performed for 4 days, 30 minutes in each day. Distance from the radiation source – 70 centimeters. The irradiation schedule: 10 min irradiation time using tissues of the pancreas, then 10 minutes of the spleen tissues, and for 10 minutes – pancreas tissues. The beginning is the day of the alloxan injection.

After histological analysis of the pancreas tissues in Groups 1,2 and 3 a number of distinctive features have been observed (Fig.4). Histological picture of the pancreas tissues from animals of control Group was cjaracterised as having clearly visible degenerative alterations of Langer Islands (Fig.4b). The number and size of the islands are reduced, they are of unusual and irregular form. Quantity of β-cells is sharply reduced and in most of them cytoplasmic vacuolation was observed, the nucleus size decrease, chromatin condensation and cariopicnose in some of the cells. Gathering of lymphocyte infiltrate had been revealed around and inside of the islands.

In Group 2 by the 8th day histological situation if pancreas tissues could be described as having damaging processes of various degree: the islands were reduced in size, of irregular form, β-cells reduction, the total portion of insulin apparatus in the islands was significantly reduced. Only a relatively small part of the islands apparatus maintained rather preserved (intact) structure (Fig. 4c).

Situation in Group 3 by the 8th day after modeling alloxan diabetes was considerably different from the control Group and Group 2. Along with the pathological processes in the tissues of pancreas in question, there was also observed a large quantity of islands, large as well as medium and small sizes with lightened cytoplasm, of normal spherical form, large roun nucleuses containing the core (Fig.4e).

A month and a half later histological situation in Group 2 was also described as having damaged islands' apparatus (Fig.4d)

As opposed to Group 2 and control Group, Group 3 after 1.5 months had hypertrophy and hyperplasia of the pancreas. Numerous islands of varying size and normal spherical form were noted (Fig.4f). Attention was attracted by the large number of small islands and discreete agglomeration of β-cells, where as large islands contained increased number of β-cells which in turn were located in a close proximity to one another. The structure if the islands and β-cells were not altered, the kernels in the cells were large; round, in which it was possible to locate nucleuses.

Fig.4 Pancreas tissue structure, Langerhans islands:

a – intact rats:

b – Group 1 (control), after alloxan injection of 200mg/kg dose;

c – Group 2 by the 8th day from the day of alloxan injection of 200mg/kg dose. A month prior to the inducing alloxan diabetes, this Group was preventively treated by the irradiation and was located at about 20 meters distance from the source I the basement of the laboratory.

d – Group 2 after 1.5 months after alloxan injection of 200mg/kg dose.

e – Group 3 by the 8th day from the day of alloxan injection of 200mg/kg dose. One day prior to the alloxan injection this group was also preventively treated by the irradiation being located at 70 centimetres distance from the source of radiation.

f – Group 3 after 1.5 months after alloxan injection of 200mg/kg dose

Enlargement: 1 x 400, 1 x 100. Colouring agents: Haematoxylin and Eosin.

DISCUSSING THE RESULTS

It can be stated that a positive effect was reached by using MWER in Groups 2 and 3. Differences in the dynamics of glucose level and survival rates of the animals in these two groups point to an interconnectedness between the length of the irradiation by MWER and modeling the alloxan diabetes. Biological long range defensive effects when irradiating with MEWR which were discovered in our previous experiments [Gariaev, Kokaya et al, 2007] has been confirmed in this series of experiments – this research. The effects is manifested in the glucose level dynamics in Group 2 animals and also in the very fact of the animals surviving in this group, when compared with control Group and placebo Group. In spite of the reliable data ($p<0.05$) suggesting increase in glucose level in the animals of Group 2 compared to the initial state, and an absence of any reliable differences in the glucose level data obtained from Groups 1 and 2 by the 2nd, 3rd and 4th day of the alloxan injection, survival rate in the Group 2 was high. Evidential hyperglycemia in 20% of the animals in this group did not result in to their death but were remaining I a satisfactory health condition for the entire period of the observation.

Irradiation by the MWER on the animals of Group 3 facilitated development of resistive properties of their immune system to the alloxan triggered diabetes and the glucose level was at the normal physiological lever at all times for the entire period of observation (this is reliably different ($p<0.05$) from data obtained from Groups 1, 2 and 4). Survival rate in Group 3 was at 100%. Having analyzed the histological data of pancreas from different Groups, it can now be stated that preventive irradiation by MWER in Group 3 resulted not only in cyto-protective effect on the cells of pancreas but also encouraged hypertrophy and hyperplasia processes in it, which, as it seems, were functioning in a compensatory mode. The present experimental findings are in good conformance with the results of our previous experiments conducted earlier. [Gariaev, Kokaya et al, 2007]

In this way, three phenomena of MWER irradiation on the animals with alloxan diabetes were manifestly observed:

Firstly – the factor of survival with contemporaneous and obvious hyperglycemia within prolonged period of observation with preserved reproductive functions in the animals.

Secondly – it was revealed in the previous experiments, and confirmed in the present one that MWER is facilitating pancreas regeneration in the ill animals in situ.

Thirdly – preliminary irradiation by MWER on the animals facilitates development of resistance to alloxan effects.

The recorder effects are related to the fundamental issues of “recording” and transmission of electromagnetic component of genetic information during the post-embryonic growth with wave (frequency) processes taking part in genome and organism as a whole. MWER, parametrically linked with photons (which in turn were modulated by the tissues), appears to be a carrier and transmitter of the information from the bio-donors to the bio-system (bio-organism which precisely and specifically receives this information as strategically superior (that is of higher topology? Of the sort that can manage and govern processes in the recipients organism)). Most likely, MWER – performs a function of a frequesncy (wave) trigger, which initiates “awaiting” (stand by) regenerative morphogenetic processes, of which the information is contained in genome of every cell. Quantum mechanisms of MWER effects on embryonic and post-embryonic processes remain to be discovered, thoughsome ideas were expressed in our earlier works. [Garyaev, 1994; Gariaev, 1997; Prangishvili, Gariaev and et al, 2000 (b); Gariaev et al, 2001; Gariaev, 2003] and are being further advances at present. The defensive and cyto-protective action of MWER are promising field of research with rather sound perspectives.

It may be that a specific role in the discovered defensive-protective manifestations plays a so called factor of “weak influence” [Chukova, 2002]. In this regard it can be put forward that the discovered effects bear endoergic character where even weakly absorbed energy of coherent polarized laser beam results in the increase of free Gelmgolc energy which is accumulated in chemical links of tissue metabolites in pancreas and spleen. For instance, atoms of informational macro-molecules (DNA, RNA and proteins), while absorbing light, together with the energy had by a quantum of light they gain the same momentum of quantity of motion, which creates inversed population of nuclear zeeman levels (see Zeeman effect). Occurs so called chemical polarization of the nucleuses. In this manner, biochemical reactions in preparation (tissues) initiated by the polarized laser light are able to generate electromagnetic

radio frequencies (fluctuations). In this situation the preparations (tissues) of the pancreas and the spleen assume a role of specific molecular radio station where every type of molecules has its own frequency (vibration level) which can be amplified due to stochastic resonance produced by the wideband radiofrequency gas discharge laser.

Based on the obtained experimental data it is proposed to attempt to create a technology allowing development of resistance to toxic effects of Geptil/ hydrazine in animals. We suppose that the resistance to Geptil/ hydrazine and to many other toxic substances can be developed by influencing strategic metabolic vectors most vital of which are – functions of genetic apparatus at quantum level http://www.wavegenetics.jino-net.ru/ (http://www.wavegenetics.jino-net.ru/).

DISCUSSION OF THE EXPERIMENTAL RESULTS.

THEORETICAL MODELING.

The obtained data has wider implications than demonstration of capabilities of possible wave defensive antidote-effect and require theoretical consideration since they relate to strategic (quantum) mechanisms of genetic apparatus functioning of multicell bio-systems. At his stage we propose three formalized hypotheses of the wave processes while “reading or scanning” from bio-structures of donor genetic-metabolic wave information (data), remote addressed transmission of it, introduction of the information in to the bio-system-acceptor and metabolism management using that information.

1. Endogenous polarization-holographic processes in bio-systems

Wave informational scenarios – unfolding in the bio-system itself as well as during scanning by the laser beam at the initial phase – occur at photon level. Let’s consider that level in more details. In our previous researches we presented two- and three-dimensional models of bio-holographic management of building spatial structure of multicell organisms during embryogenesis.At the initial view subject to relatively stationary conditions in bio-systems (final phases of morphogenesis), these models are plausible. However, in living organisms statics and dynamics are paradoxically intertwined.

An adult organism is relatively static spatially on macro scales and significantly changes on this plane only at the stages of deep aging. Along with this that statics are provided for by the internal space-time dynamics of metabolic processes on micro levels of bio-systems organization. This is a case due to the fact that metabolic processes are a mobile aggregate of bio-chemical-bio-physical space-time reformations of the organism’s microstructures. Having considered the non stationary structures of bio-systems, more advanced model is proposed of endogenous informational polarized-holographic managing (governing) processes in multicell organisms, which are realized/effected at genome levels. The model reflects bio-holographic aspect of metabolism as a whole and therefore includes bio-morphogenesis as it specific case. The model utilizes appropriate physics-mathematical formalism for the polarized-holography yet extrapolates it onto probable endogenic analogical processes in the genetic apparatus of multicell organisms.

As a foundation for the model we used our experimental data where we employer special double-polarized He-Ne laser (= 632,8 nano мeter), having two orthogonal, linked optical modes, of which we have mentioned earlier. When such laser beam of this quantum generator interacts with the bio-tissues, with dynamic holographying on the oncoming beam (bunch) mode on, simultenious acts of recording and scanning of previously unknown information occur, the information about dynamic spinning-fluctuating processes on optical and atomic-molecular levels. Of particular interest can be data obtained about genetic structures and/or living cells. The entire informational structures of an organism, including DNA, RNA and proteins, are optically active, that is to say they are capable of spinning light polarization planes and they are dichroic – difference between absorption of right- and left hand polarized light. Modulations of polarization that correlate with structural-functional condition of any metabolite, present themselves as unique in their capacity storage of information about metabolism and its dynamics and along with it – that is a channel of intercellular photonic bio-symbolic contacts.

Such special processes, in their polarized-holographic version, are apparently inherent to genome workings as a bio-computer. This allows their modeling with use of the aforementioned laser. IT is capable of polarized-holographic recording, scanning, remote transmission and “injection” of wave commanding genetic-metabolic information from one bio-system to another. Besides, such laser performs a conversion of photons probing the bio-system in to wideband electromagnetic spectrum with frequencies from 2 to 0 according to mechanisms of localizing and

delocalizing of photons. During this stage, it is apparent, quantum non-local (teleportation) polarized connection across the whole spectrum of frequencies is retained (maintained, saved), including radio waves. Utilization of such laser as reading-transmitting photon-radio-wave system, imitating analogical wave-bio-computer-symbolic non local processes intercellular communications provided with opportunity to carry out remote wave transmission of primary /managing genetic-metabolic information from donor's bio-system to recipient's bio-systems (so called addressed transmission). In the light of this fact it seems rational and vital to attempt presentation of more advanced formalism of bio-symbolic photon-polarized-holographic processes in chromosome apparatus of higher bio-systems, all the more so that the radiowave equivalent of these processes possessed strikingly distinct morphogenetic potencies.

Let's record vector diffraction Kirchhoff's integral in paraxial approximation, which describes wave field, for instance photon field, formed by non-stationary bio-system's fragment. This sort of field may radiate from liquid crystal continuum of chromosome (LCCC) in vivo. Such emission may be expressed by the following:

For the purpose of simplification we will consider that non stationary LCCC is not a function of frequency of translucent light.

Both polarisational modes of coheren laser light are depolarized by geno-symbolic acoustic LCCC and are partially elliptically polarized. With this, they can interfere forming specl-structures, and their total intensity is transferred from one mode in to another by means of earlier postulate manner [Prangishvili, Gariaev et al, 2000 (b)].

Modified Johns' vector of every passed orthogonal polarized waves immediately behind the object may be presented in the form of partially coherent orthogonal components of elliptical polarization

In a bio-system in the composition of LCCC (with only one polarizational component) we use as a hypothetical a carrying wave, which passed, for instance, through infinitely narrow time shitter lock, possessing - figurative characteristic of time transmission (perhaps "gating"). Such a shutter lock completely depolarizes initially polarized wave. The resulting wave, passed behind the gating lock, has continuous spectrum in the whole diapason with evenly distributed spectral density, where as the modified vector of the carrying wave has a form of orthogonal basis of elliptical polarization:

Parameters of the total ellipse p and g are defined via ellipse's polarization component of every basis A and B, as in Ref [14]

Endogenous biological registration of the summary wave field (5) pertaining to LCCC as a basic element of DNA-wave bio-computer, assumes presence of polarization-sensitive environment in organisms, which is not selective of any particular spectrum across the whole range of active frequencies (similar to the non stationary fragment of biological object, for instance LCCC).

Due to the polarization characteristics of the inducing light in a light-sensitive registering environment of LCCC, photo-anisotropy and photogyrotropy are created (are produced). To describe the vector photo-response polarized-sensitive environment functions of isotropic , anisotropic - and gyrotropic reactions are introduced, which are constants for every frequency of the active spectrum. Using Johns' matrixes and rules of their construction for cases of partially polarized inducing irradiation, for the resulting Johns' matrix we get:

where - LCCC's hologram fragment size

- distance between the point on the hologram surface and the point of observation.

Than, successively substituting in (17) expressions for matrixes (10), (14) and (15), let's define formed by the hologram zero, imaginary and real depictions. It is only now that we can determine, what endogenous or/and exogenous wave for an organism is necessary to utilize as a reconstructing one in order to obtain in the imaginary style regeneration of the required fragment of the wave image of the shaping bio-system. In order to do so it is essential to determine their vectors and corresponding values of matrix. It appears that with precision of up to constant multiplier own vectors of matrix are in essence

It follows that regeneration is performed by a wave identical to the one used while recording by the carrying wave. So, as apparently, in bio-systems at LCCC level recording and reconstruction ensue ither simulteniusly or in accordance with the last equation, then the reconstructed imaginary depiction corresponds to the real one and it is not subject to

any distortions. The latter is principallycrucial for preservation of the wave images-vectors of morphogenesis, which compensate physiologic-bio-chemical and mechanical non-stationary stae of the bio-system as a whole and its LCCC in particular. Nonetheless, non-stability of strategic photonic-images of organism's structures will occur though in term of long lengths of time while aging and its pathological states, for instance in the case of cancerogenesis.

For a passed wave without diffraction the zero depiction has the following appearance:

An analysis of the last correlation shows that with precision up to its multiplier it contains complete reconstruction of space-time structure as well as polarization characteristics of the field of its non- stationary object wave that have passed through, for instance, LCCC. These photo or/and radio wave dynamic structures are, apparently, used by multicellular organisms for their own organization in their own space-time since these structures-images completely retain the true real calibration size without deformations imposed by non-stationary bio-systems and reproduce them in adequate sizes require for a developing or an adult organism. In accordance with the reconstructed wave gradients scanned polarized holograms occurs 4D organization of metabolic "fluxes"/"streams", cellular architectonics and morphogenetic motions during embryo genesis and also partial regeneration of bio-systems in case of them having been damaged. In other word what occurs is calibration of dynamic potential space-time of bio-system.

Under polarized-holographic-bio-control we imply endogenous or intentional (artificial) modification of recipient's cell structure and condition as a result of controlling holographic operations from donor's side. In our case the holographic signal, which was modulated by healthy samples (tissues, cells) of the donor, is transmitted and recorder onto donor's diseased (ill) cells in form of a hologram. Further, the process of control occurs as follows: in the beginning from the modified cells of the recipient by means of regenerative wave the holographic image of donor's healthy cells is scanned. It is reconstructed in terahertz wave diapason as a 3D image encompassing every recipient's cell together with its content.

Mainly, there exist two forms sources of regenerative wave. First form is endogenous. In this instance the processes flow due to innate reserves i.e. "internal" irradiation (emission) of the neighbouring cells. Second form appears to be exogenous reconstruction, when the sources are external emitters. Both forms of sources operate in the recipient's cells and act simultaneously and continuously, regenerating and complementing the same image of donor's healthy cells over and over again

According to gradients of intensity of donor's reconstructed cell images, as if it was a "drawing", growth and regeneration of recipient's damaged (ill) cells occur. The cells of the recipient "assume" a role of a photographic film (plate), in which a hologram of the healthy cells is recorded. Processes of the growth and regeneration, flowing analogically to processes of photo-tropism, require certain length of time. In the upshot the recipient's "sick" cells partially transfer to healthy ranking and partially destroyed. Products of such decomposition are diverted out of the recipient's organism.

That being so, during the replacement process of recipient's cells by healthy ones, analogous to those of donor's, occurs polarized-holographic-control which is in effect germination of the recipient's damaged cells biomass in to offered to them dynamic holographic form of healthy donor's cells. As a consequence, while controlling the process, the form and dynamic state (condition) of recipient's cells is gradually modified under the controlling signal – "pattern", obtained from the donor.

Needless to say that this form of "pattern" is much more complex than those seen in simple controlling systems. It sets spatial distributions terahertz signal on gradients of which the growth and formation of live cells in recipients occur. Therefore acts of growth and formation of recipient's cells happen in line with bio-chemical laws, which control their vital functions, and the "pattern" signal sets a program or guide of growth for young cells' structures and modulation of processes in them.

For more comprehensive description of internal working mechanisms of holographic circular-polarized informational-laser transformation in live organisms it is necessary to have a fair good understanding of basics of polarized-dynamic holographic theory and informational exchange between recipient's live healthy cells and all other cells included in organs and tissues of the ill organism. When dealing with these issues we utilize de

Transmission of modulated information from donor to recipient occurs by means of rectilinearly propagating longitudinal mutually entwined waves, carrying multilevel modulated information. For the short distance transmissions we can use a term of cellular nucleuses – optical poliaroids (polarizers?), where as for longer distances – a term of

quasi lenses (objectives) (here is a reference to some previous papers). Let's look in to description of such process proffered for purposes of registering color holograms without using lasers [Alexanderov, 1998]. When adapting it to a bio-system, we outline requisite conditions for realizing non-coherent polarized-holographic method of control (management). It ought to be noted that in such systems, having done microscopic studies of the systems, it was discovered long ago that they have microscopic polarisers, i.e. cells' nucleuses, as well as optically active protein substances, which spin the polarizational plane of emissions that are passed through them. These aspects are long knowng to researchers [Bischof, 1995], however until now this observed phenomenon was neither explained not utilized.

Holographic transmission function can be defined on the basis of Fourier transformation of equation (13). To remind, the wavelength of the probing signal is not included in this formula therefore that wave can be selected from wide range of waves light, electromagnetic and acoustic diapason. The created hologram encompasses whole information about spatial coordinates features of donor's bio-object being holographed, or about spatial distribution of all donor's points in relation to holograph registering planes of recipient.

So the resulting solution of the task is, generally speaking, analogical to traditional approach. At the same time the method put forward is fundamentally different from other known interferential methods and possesses certain advantages.

Firstly, instead of some wavelength with its monochromatic features and coherence we use dispercing spinning ability of optically active environments and spatial locally-distributed polarizational filtration. This is sufficient for recording polarized-dynamic hologram of donor (provided that there is motion in donor's cell in non-coherent wide spectrum irradiation of the recipient)

Secondly, this method allows uncovering the reasons of vibro-resistance when registering and reconstructing holograms without laser sources of light inside bio-systems in terahertz diapason of waves. It efficacy is determined by the value of polarized-optical spinning ability and thickness of the optically active environment . It is known that spinning ability of certain liquid crystals reaches 40000 degrees/mm, which when used in holographic information-laser convertor is sufficient for polarized-holographic transmission of information and accordingly holographic controlling of the biosystem's structures and processes.

Experimental works on wave interaction in living systems were actively been initiated in 1980s. In the beginning these included researched on interactions between cells [Kirkina et al, 1981; Molchanova, 1985], followed by researches on interaction of living organism [Burlakov et al., 1999]. These works were successfully furthered by A B Budagovski et al. [Budagovski, 1990; Budagovski, Evseeva, 1995; Budagovski et al, 1997; Budagovski et al, 2001]. It was shown that there is a communication and exchange of information of non-chemical (wave, coherent) nature. Such kind of interchange processes, occurring with participation of bio-regulatory signals and occurring without molecular and ion carriers of that information, were labled as processes of remote intercellular interaction (RII) [Budagovski, 2004]. However it seemed incredible that weak electromagnetic cellular signals can produce controlling influences against the background of strong electromagnetic interfering signals of natural and technogenic origins. Nonetheless it appears that with coherent reception light and other electromagnetic non-coherent noises with approximation are zeroed where as those weak coherent and deterministic signals can accumulate [Tertishni et al., 1997, 1998, 2000]

In the last years these works have received the deserved advancements in the Institute of management issues. In particular, utilization of polarized-dynamic holography, which allows formation of little movable polarizational rings. For urposed of transmitting undistorted image of every donor's point to the remote recipient's zone, a sensory quasi objective (lenses) were created, and on its basis a holographic device designated for experimental testing of holographic controlling possibilities.

Publications in foreign journals

1. Garyaev P.P., Vikhert A.M., Zakharkina G.A., Alexandrova L.G., 1977, Endogenous reserpine-like substances in the myocardium and other tissues of man and animals., USA-USSR First Joint Symposium on Sudden Death. Yalta, USSR, October 3-5, 1977, pp.323-338.

2. Gariaev P.P., Chudin V.I., Komissarov G.G., Berezin A.A., Vasiliev A.A., 1991, Holgrphic Associative Memory of Biological Systems, Proceedings SPIE - The International Society for Optical Engineering. Optical Memory and Neural Networks. v.1621, p.280- 291. USA.

3. Gariaev P.P., 1994, DNA as source of new kind of God "knowledge", Act and Facts/Impact series, N12, pp,7-11.

4. Maslov M.U., Gariaev P.P., 1994, Fractal Presentation of Natural Language Texts and Genetic Code. 2nd International Conference on Quantitative Linguistics "QUALICO-94". September 20-24. (1994). Moscow, Lomonosov Moscow State University, Philological Faculty. pp.193-194.

5. Gariaev P.P., Vasiliev A.A., Berezin A.A., 1994, Holographic associative memory and information transmission by solitary waves in biological systems. SPIE - The International Society for Optical Engineering. CIS Selected Papers. Coherent Measuring and Data Processing Methods and Devices. v.1978, pp.249-259.

6. S.A. Reshetnyak, V.A. Shcheglov, V.I. Blagodatskikh, P.P. Gariaev, and M.Yu.Maslov, 1996, Mechanism of interaction of electromagnetic radiation with a biosystem, Laser Physics, v.6, N2, pp.621-653.

7. Berezin A.A., Gariaev P.P., Gorelik V.S., Reshetniak S.A., Shcheglov V.A., 1996, Is it possible to create laser on information biomacromolecules? Laser Physics, v.6, N6, pp.1211-1213.

8. A.A. Berezin, P.P. Gariaev, S.A. Reshetniak, K.V. Shaitan, V.A. Shcheglov., 1996, To the problem of possible development at a biolaser working on Frolich modes. Prepr. P.N.Lebedev Physical Institute №49, 12 c .

9. Gariaev P.P., Tertishny G.G., Kampf U., Muchamedjarov F., Leonova E.A., 1999, Fractal structure in DNA code and human language: Towards a semiotics of biogenic unformation. 7 th International congress of the international association for semiotic studies (IASS/AIS). TU Dresden, October 3-6, 1999. p. 161.

10. Peter P. Gariaev, Boris I. Birshtein, Alexander M. Iarochenko, Peter J. Marcer, George G. Tertishny, Katherine A. Leonova, Uwe Kaempf ., 2001, The DNA-wave biocomputer. “CASYS” – International Journal of Computing Anticipatory Systems (ed. D.M.Dubois), Liege, Belgium, v.10, pp.290-310.

11. Peter P. Gariaev, George G. Tertishny, Katherine A. Leonova., 2002, The Wave, Probabilistic and Linguistic Representations of Cancer and HIV. http://www.emergentmind.org/gariaevI2.htm (http://www.emergentmind.org/gariaevI2.htm)

12. P.P.Gariaev, G.G.Tertishny, A.M. Iarochenko, V.V.Maximenko, E.A.Leonova, 2002, The spectroscopy of biophotons in non-local genetic regulation. Journal of Non-Locality and Remote Mental Interactions Vol.I Nr. 3

13. Peter P. Gariaev, Boris I. Birshtein, Alexander M. Iarochenko, George G. Tertishny, Katherine A. Leonova, Uwe Kaempf, Peter J. Marcer, 2002, Fractal structure in DNA code and human language: towards a semiotic of biogenetic information. International Journal of Computing Anticipatory Systems, volume 13, 2002, pp. 255-273, ISSN 1373-5411 ISBN 2-9600262-7-6.

14. P. Gariaev, 2003, Der wellengenetische Code. Tattva Viveka, №20, pp.68-73. (in German)

15. P. Gariaev, W. Wagner, auch auszugsweise, 2005, Der Phantomeffekt. Spiegelung zwischen Geist und Materie. (Teil 1). Tattva Viveka, №26, pp.54-65. (in German)

16. Peter Gariaev, Mark J. Friedman, Ekaterina A. Leonova-Gariaeva. Principles of Linguistic-Wave Genetics. http://dnadecipher.com/index.php/ddj/article/viewFile/2/2 (http://dnadecipher.com/index.php/ddj/article/viewFile/2/2) ; http://dnadecipher.com/index.php/ddj/article/view/2 (http://dnadecipher.com/index.php/ddj/article/view/2) DNA Decipher Journal, Vol 1, No 1 (2011).

17. Peter Gariaev, Peter J. Marcer, Katherine A. Leonova-Gariaeva, Uwe Kaempf, Valeriy D. Artjukh. http://dnadecipher.com/index.php/ddj/article/view/2 (http://dnadecipher.com/index.php/ddj/article/view/2) DNA as Basis for Quantum Biocomputer PDF; http://dnadecipher.com/index.php/ddj/article/viewFile/3/13 (http://dnadecipher.com/index.php/ddj/article/viewFile/3/13) . DNA Decipher Journal, Vol 1, No 1 (2011)

18. Peter Gariaev, Matti Pitkanen, Model for the Findings about Hologram Generating Properties of DNA PDF ; http://dnadecipher.com/index.php/ddj/article/view/2 (http://dnadecipher.com/index.php/ddj/article/view/2) . http://dnadecipher.com/index.php/ddj/article/view/2 (http://dnadecipher.com/index.php/ddj/article/view/2) . DNA

Decipher Journal, Vol 1, No 1 (2011)

2012 - Mirrored Material is Fair Use for Educational Purposes Only

Represented by Irene Caesar, Ph.D., President, Wave Genome Research and PublishingPhone in the US: 1-347-352-0044email: irenecaesar@wavegenome.com (mailto:irenecaesar@wavegenome.com)
Skype: Irene Caesar

The history of wave genetics has been developing for more than 80 years. In 20s and 30s of the last century Russian scientists, A G Gurwitsch and A A Lubishev postulated that not only does genetical apparatus of living organisms on the Earth operate at material, physical level but also at certain waves/fields level and is able to transfer genetic data/information via electromagnetic (EM) and acoustic waves. The science has recently taken a major leap in its advancements of the theory and reproducible experiments and thus the theory of wave genome has been put forward.

One of the first attempts to rationalize and expound the wave genome theory in Russia had been made by P P Gariaev and A A Berezin from the department of Theoretical Matters of Russian Academy of Science, and also with participation of A A Vaciliev, a fellow member of Institute of Physics of Russian Academy of Science. As a theoretical foundation, principles of coherent physical radiations, holography and solitons, theory of physical vacuum, fractal representation of DNA and human verbal expression/speech have been employed to describe and substantiate the empirical results obtained through many experiments conducted.

The quintessence of the wave genome theory may be represented as following:

genome of the highest organisms is considered to be a bio-computer which forms the space-time grid framework of a bio-systems.

In that bio-system, as the carriers of a field epi-gene-matrix - wave fronts are being used, which are assigned by gene-holograms and so-called solitons on DNA – distinct type of acoustic and electromagnetic fields, produced by biogenetic apparatus of the organism/bio-system under consideration and being a medium of strategic regulatory data/information exchange between cells, tissues and organs of the bio-system.

It is also vital to note that the holographic grids/frameworks, which are also the elements of fluctuating structures of solitons, are, in fact, discrete simplest cases of code-originated information, anchored in chromosome continuum of an organism.

At present the dominant viewpoint in respect of genetics and molecular biology is that :
1. the genetic apparatus functions as a purely material structure
2. all the functions of genetic control of an organism occupy approximately 2 % of DNA of a bio-system and fulfill designated functions such as replication of RNA and proteins, so called coding DNA of an organism. The other 98% is considered to be "junk DNA" not carrying out any genetical functions, which may represent a graveyard of virus DNA.

The biologists and geneticists use the language of analogies and metaphors to explain how genetic apparatus operates. The genetic apparatus consisting of 46 chromosomes is viewed as a library consisting of 46 volumes or books. Each book (a chromosome), contains a text (instructions of how to build an organism) which consists of sentences (DNA) consisting of words (genes). And each word (a gene) consists of 4 letters (certain "chemical letters"), i.e. the "genetic alphabet" consists of only 4 "letters". The material realizations of the DNA molecules are famous double helixes, consisting of segments which are genes. In essence, genetic apparatus operates as follows. The texts, written in the "DNA language", are first translated by the organism into the "RNA language" and then into the "Protein language". And proteins are the stuff that we are mostly made of (not counting water). Proteins perform two principle functions in the organism: they metabolize substances that we eat and participate in the morphogenesis, i.e. development of the spatial-temporal organization of an organism.

It is to be pointed out that the primary focus of the wave genome theory is on the remaining aforementioned 98% of chromosomes as being the key "intellectual" structure of all cells of an organism including the brain. It is those chromosomes that operate on the wave, on the "ideal" (fine-field) level.

It the ideal component, that may be called super-gene-continuum, is a strategic vital figure/formation that ensures development and life of humans, animals, plants and also their programmable natural dying. Along with that, it is

2. Connect to the student's and your own cosmic star above your head and ask for universal permission. **Radiate your love and transfer three minds into one mind**. Lower your Upper Tan Tien. Activate your consciousness: Three minds become one mind. Expand your awareness in the mideyebrow and the crown. Feel the Tan Tien, heart, mideyebrow and crown spiraling. Expand to the universe.
3. Visualize the person's legs as being 'very long', extending down to the earth. **Activate the Sacred Fire** and bring it down. Clean out the room and make a big Chi field around you and the student.
4. **Call the Elemental Forces:** water, fire, thunder, lightning, rain, lake, earth, mountain, wind and Heavenly Chi. Call the guardian animals; Blue Tortoise from the north, Red Pheasant from the south, Green Dragon from the east, White Tiger from the west, Yellow Phoenix from above and Black Tortoise from below. Feel that you are protected by the Chi; gather the power of all the mountains, rivers, streams, stones and rocks into the room. Activate them with lightning, thunder and wind - filling the whole room with electrified Chi.

A. Chi Knife

1. Hold the knife in right hand (left, if you are left handed). Hold the other hand near your body with the thumb and index finger touching. Project the Chi Knife as big as the universe, 'long and big - reaching to Heaven'. The bones in your arm are hollow and the 'bottom' is sealed at the shoulder. Feel them 'fill and pack' with the power coming from above.
2. Then give the command: **"Power comes from the east. This Chi Knife has the power to dissolve all the negative energy, sickness and bad fortune. By my request, please carry out the order now."** Wait until you feel that your arm and the knife are heavy and full of Chi.

   Carry out energetic surgery, **cutting and slicing the affected area with cool yin energy**. When you feel that the Chi Knife is full of sick Chi, spiral counterclockwise and discard it down into the ground. When you feel that the knife is 'empty', charge it with Chi from the universe. Continue until you feel that the area has been cleansed.

B. Energizing and Activating the Immune System

In cases of severe illness, debilitation and infection, it is essential to stimulate the body's defence systems. You may also want do this in a preventative manner. Guide the student as you practice together. Presuming that you have already done the previous set of general healing, you can start with the coccyx.

1. Be aware of your Tan Tien and connect to the universe. Touch your **coccyx** with the fingers concentrating a beam of white or yellow light on to it. Picture the sacrum opening and the light streaming inside, flowing **up the spine** and streaming out over

important to conceive that there is no sharp and insurmountable distinction between genes and super-genes. Both these levels of encoding constitute material (physical) matrixes, however genes supply material replications in the form of RNA and proteins, whereas super-genes transform endo- and exogenous fields, forming from them super-gene-signal wave structures. Furthermore, the genes may be components of holographic grids/frameworks of super-genes and supervise their field activity

Particular attention in the wave genome theory should be devoted to substantiating of the unity of fractal (replicating itself on varying scales) sequence structures of DNA and of a human speech. In 1990 Jeffrey Delrow discovered four "letters" of the genetic alphabet (Adenine, Guanine, Cytosine and Thymine) in DNA "texts" form fractal structures.

Later on, a discovery of similar fractal structures in a human speech, not limited to multy-letter alphabets of Russian and English texts and including a sequence of words from those texts came as a promising surprise for both genetics and linguists. Nonetheless this is in accordance with a branch in semiotics named "Genetical Linguistics", which studies incomprehensible and unexplainable precise application of laws of Formal Genetics to formation of interlingual and intro-lingual words-hybrids.

A group of scientists headed by P P Gariaev and M U Maslov, developed a theory of so called fractal representation of natural (human) and genetical languages. Within the confines of this theory it is said that the quasi-speech of DNA possesses potentially inexhaustible "supply of words" and, moreover, what had been a sentence on the scales of DNA–"texts" "phrases" or a "sentence" becomes/turns into a word or a letter on the other scale. Genetical apparatus can be viewed as the triunity of its structure-functional organization consisting of holographic, soliton and fractal structures.

This theory allows a refined quantitative comparison of symbolic structure of any texts including genetical. Thereby a possibility has been wide open to approach a deciphering of a lexicon of one's own gene-code, and accordingly, more accurate composition of algorithms of addressing a genome of a human with an aim of potentially any type of programming of one's vital activity such as treatment, increasing one's life expectancy and so on and so forth.

Empirical tests of wave genetic theory in the light of "speech" characteristics of DNA demonstrate strategically correct stance and direction of the research.

Phenomenal experimental findings may be briefly presented here. For the first time in history of the science we successfully managed to obtain experimental evidences of abilities of the genetic data/information to function on more than simply one material level, for instance, in the wave/field (electromagnetic) form

Over decades, having been conducting extensive theoretical researches, we successfully managed to formulate theoretical biology and physics-mathematical description, explanation and substantiation of fundamental principles of genetic apparatus functioning on the wave/field level.

These principles allowed us to design and create a quantum bio-computer essential element of which is a specially tuned laser beam with certain wavelength and frequency characteristics.

The quantum bio-computer can perform:
i. Scanning and reading the wave/field equivalent of the genetical-metabolic data from the (stem) cells, tissues, organs of a donor's bio-system employing photon of the laser beam;
ii. Conversion of the photons obtained into wide-wavelength-band preserving the scanned and read data;
iii. Precise and pointed introduction of such scanned and converted principal/dominant data radio waves into the organism-recipient, located at a certain distance from the donor's bio-system (from few centimeters to 20 km);
iv. Strategic control/management of metabolism and postembryonic morphogenesis of the organism-recipient according to two vectors/modes:
a. "Do as/what I do" – that is holographic principle, and
b. Wave/field transmission of a signal that contains commands activating required programs in the stem cells of, for instance, rats; programs that direct/guide the stem cells development on their way of, as in our experiments, building pancreas gland in rats. These vectors/modes are intended to be used on humans.

At present we are able to program/manage/encode stem cells of various types by means of a quantum bio-computer. The quantum bio-computer initiates wave/field-based commands, given to cells and tissues of the donor/recipient, and accordingly the stem cells exposed to the waves/field will be prompted to guided cytodifferentiation leading to emergence and development of planned/projected new organs and tissues. This will bring us closer to the fact of substantially increased life expectancy.

Significant achievements in applying WaveGenetics have been made thus far in regeneration of pancreas in rats previously destroyed by chemical substance called alloxan

Three series of experiments with identical protocol were conducted by the groups of P. Gariaev in 2000 in Moscow Russia, in 2001 in Toronto, Canada, and in 2005 in Nizhni Novgorod, Russia. These are more advanced experiments based on the principles and technology of WaveGenetics. The goal of the experiments was to test new technology for regenerating damaged pancreas. Pancreas is an endocrine gland which has several vital functions, the major one being production of insulin, a hormone responsible for sugar metabolism.

A control group of rats was injected a lethal doses of a poison called alloxan which destroys pancreas. As a result, all the rats in the control group died from diabetes in 3-4 days. Then the same lethal dose of alloxan was injected to another group of rats. And when the rats reached the critical condition, they were exposed to light images/waves coming from a quantum bio-computer. Those light images/waves were created beforehand when the bio-computer read information from the pancreas surgically removed from healthy newborn rats of the same species as those used in the alloxan experiments.

One can explain the results of the experiment using the following analogy. The pancreas gland contains DNA-movies with information about healthy condition of the pancreas in its genetic apparatus. And this video morphogenic information programmed the stem cells of sick rats to regenerate their pancreas gland. Combined statistics for all 3 series of experiments is as follows. Altogether, around 90% of all the rats had their pancreas gland restored and their health recovered.

In some of the experiments the quantum bio-computer was modified to allow successful transmission of the healing information to sick rats at the distance of 20 kilometers. Note, that no known physical fields have the capability to transmit such extremely week signals with such unbelievably powerful results.

Furthermore, the WaveGenetics research and application has significant prospects of solving issues as regards ageing process in humans and increase of life expectancy. This view is grounded on the experiments we have been conducting with rats.

It is Opportunities of technologies of WaveGenetics are not limited to what has been outlined above. The development and application of the technology is far-reaching and is substantiated by experimental data obtained in numerous tests, experiments, observations.

In addition, it ought to be mentioned, such a technology – a quantum bio-computer, is capable of:
- **treating oncological diseases on fundamentally distinct basis – without use of any chemical substances,**
- **eliminating pathogenic viruses and bacteria and agricultural vermin parasites – also without used of any chemical substances.**

It may seem as a technology of another age, from distant future. However, a discovery of fundamental properties of living organisms is occurring today and it is our task to research and explain the phenomena and bring it to the service of humanity.

Peter Gariaev, Ph.D.,
Director of Wave Genetics Institute,
Russia, Moscow.


ИНСТИТУТ КВАНТОВОЙ ГЕНЕТИКИ
ПЕТР ГАРЯЕВ
ЛИНГВИСТИКО-ВОЛНОВОЙ ГЕНОМ
ТЕОРИЯ И ПРАКТИКА
ЛИНГВИСТИКО-ВОЛНОВОЙ ГЕНОМ
ПЕТР ГАРЯЕВ

Hi Iona...I have been following Gariave's work since I became aware of it. I have about 25 years of experience with DNA in the lab. A serious problem with his approach is that he still believes in the "junk" DNA notion which has run its course..now there is excellent evidence that ~80% of the genome contains important information. In addition to coding for proteins, there is a plethora of RNAs, micro, ribosomal, long repeat, siRNA etc that play a role in developemt, disease and so forth. Another weakness is that all his experiments were done with purified DNA. In the cell, DNA is part of a protein-DNA complex, which is very tightly packed at very high concentrations ..chromatin has totally different biochemical and biophysical properties than the dilute solutions of DNA that he works with..(The cell is so concentrated with proteins and nucleic acids, that its closer to a liquid crystal than a bag of solutes)

CREATE A FREE WEBSITE

POWERED BY

HOW TO CULTIVATE VIRTUES AND ERADICATE VICES



SWAMI SIVANANDA

HOW TO CULTIVATE VIRTUES
AND
ERADICATE VICES

HOW TO CULTIVATE VIRTUES AND ERADICATE VICES

Sri Swami Sivananda

Published by

THE DIVINE LIFE SOCIETY
P.O. SHIVANANDANAGAR—249 192
Distt. Tehri-Garhwal, Uttarakhand, Himalayas, India
www.sivanandaonline.org

First Edition:	1952
Second Edition:	1986
Third Edition:	1993
Fourth Edition:	1998
Fifth Edition:	2002
Sixth Edition:	2006
Seventh Edition:	2009
Eighth Edition:	2011

(1,000 Copies)

©The Divine Life Trust Society

ISBN 81-7052-059-2
ES64

PRICE: ₹125/-

Published by Swami Padmanabhananda for The Divine Life
Society, Shivanandanagar, and printed by him at the Yoga-Vedanta
Forest Academy Press, P.O. Shivanandanagar,
Distt. Tehri-Garhwal, Uttarakhand, Himalayas, India
www.sivanandaonline.org

Om
Dedicated to
Parents and Teachers
Leaders and Preachers
Who mould the characters
Of men and women

the whole bone structure. Feel the Chi rising up to the universe, multiply it and guide it down to your energy body.

2. Be aware of the Tan Tien and the universe. Attract the yellow light; spiral and condense the healing light into the tips of your fingers; move the fingers up to touch the **sacrum**. Send out a beam of yellow Chi into the sacrum, directing it up the spine. This will stimulate the production of red blood cells. Transfer the feeling of 'Bone-Chi' up to universe and down to your energy body.
3. Proceed to the **crown**, showering it with violet light. Then spread from the crown throughout the bones of the body. Repeat several times. Instruct the student to feel the bone structure breathing. Ask him/her to extend up from their crown to the Big Dipper and North Star, channelling down the red and violet light into the thymus gland.
4. Continue to the **throat**, stroking down with your palms, using green color to move the lymph down towards the backside of the heart. (Never stroke up towards the head! Only guide the lymph down).
5. Proceed to the **lymph nodes under the armpits and across the sternum**. Next activate the lymph nodes in the **groin**. From the groin you guide the lymph up to the navel center (Not down where it will get stuck in the legs).
6. Return to the **navel center**. Send the energy deep inside, energizing the lymph nodes at the back. Pull back, drawing green energy, flushing out any waste products that are stuck in them.

Activate the points at the inside of the **elbows** and the **knees**.

Shower the whole body with healing light and energize the **perineum** with blue Chi.

Always remember to ground any sick energy by sending it deep into the ground. Ask the student to do the same and it will be more effective. You should do this while giving the session as well as when closing it.

C. Cleansing the Internal Organs (Repeated from pages 132-133 and pages 136-137)

This session can be used for any kind of ailment and carried out with any number of students. **It is important to remember that if there is no energy in your Tan Tien, then there will be no energy to work with.** When you are aware of your Chi, you can direct heavenly light straight into your energy body and then into the student's.

General Cleansing Procedure

1. Push and pull the energy through the student's body. Push and disperse the sick energy into the universe and out to the planets, where it will be transformed and recycled.
2. Pull the energy back and stop it between yourself and the student.
3. Spiral the energy counterclockwise until you see the **green** light mix and clean the sick energy. Spiral and flush the energy down into the earth.

SRI SWAMI SIVANANDA

Born on the 8th September, 1887, in the illustrious family of Sage Appayya Dikshitar and several other renowned saints and savants, Sri Swami Sivananda had a natural flair for a life devoted to the study and practice of Vedanta. Added to this was an inborn eagerness to serve all and an innate feeling of unity with all mankind.

His passion for service drew him to the medical career; and soon he gravitated to where he thought that his service was most needed. Malaya claimed him. He had earlier been editing a health journal and wrote extensively on health problems. He discovered that people needed right knowledge most of all; dissemination of that knowledge he espoused as his own mission.

It was divine dispensation and the blessing of God upon mankind that the doctor of body and mind renounced his career and took to a life of renunciation to qualify for ministering to the soul of man. He settled down at Rishikesh in 1924, practised intense austerities and shone as a great Yogi, saint, sage and Jivanmukta.

In 1932 Swami Sivananda started the Sivanandashram. In 1936 was born The Divine Life Society. In 1948 the Yoga-Vedanta Forest Academy was organised. Dissemination of spiritual knowledge and training of people in Yoga and Vedanta were their aim and object. In 1950 Swamiji undertook a lightning tour of India and Ceylon. In 1953 Swamiji convened a 'World Parliament of Religions'. Swamiji is the author of over 300 volumes and has disciples all over the world, belonging to all nationalities, religions and creeds. To read Swamiji's works is to drink at the Fountain of Wisdom Supreme. On 14th July, 1963 Swamiji entered Mahasamadhi.

PUBLISHERS' NOTE

Man is different from beast only in his infinite capacity to manifest in himself the perfection in virtues that go to make up the Superman, the Divinity upon earth. *Minus* Virtue man is no man, but worse than a beast, for the virus of vice combines with the power of his intelligence to produce the best representative of Satan on earth.

In this volume, therefore, Sri Swami Sivananda has given not only the positive virtues that *must* be developed as also the negative side of human weaknesses that should be wiped out in order that Man's soul might acquire that Sparkling Lustre of Divine Splendour that truly belongs to it.

This is a volume that should be constantly at your elbow, to guide you in your daily life—if you really wish to grow into a Superman.

—THE DIVINE LIFE SOCIETY

INTRODUCTION

ETHICS AND MORALITY

Ethical culture will result in ethical perfection. An ethical man is more powerful than an intellectual man. Ethical culture brings in various sorts of occult powers.

Morality goes hand in hand with spirituality. Morality co-exists with spirituality. Ethical culture prepares you for Vedantic realisation of '*Sarvam Khalvidam Brahma*'—all indeed is Brahman. There is no such thing as diversity.

All aspirants commit the mistakes in jumping to Samadhi and meditation all at once as soon as they leave their houses without caring a bit for ethical purification.

The essentials of moral life are: straightforwardness, honesty, mercy, humility, respect for life, tender regard for every creature that breathes, absolute unselfishness, truthfulness, celibacy, non-injury, non-covetousness, absence of vanity and hypocrisy, and cosmic love.

A man of right conduct has ideal principles and mottoes. He strictly follows them, removes his weaknesses and defects, develops good conduct and becomes a Sattvic man.

Righteousness is eternal. Do not leave the path of righteousness even if your life is in danger. A righteous, virtuous life and a clear conscience give great deal of comfort to man while living and at the time of his death also. Sound character is the only diamond you must crave to wear. Virtues are conducive to Self-knowledge.

Immortality can be attained only by performing acts of kindness constantly and sticking to ethical principles.

Practice of charitable acts, compassion and kind services purify and soften the heart, turn the heart-lotus upwards and prepare the aspirant for the reception of divine light.

The practice of truth, austerities, celibacy and self-restraint are all auxiliaries in the attainment of the knowledge of the Eternal.

Humility is the highest of all virtues. God helps you only when you feel utterly humble. Therefore develop this virtue to a considerable degree. Virtue will develop and survive only when practised positively and actively.

The law of non-injury is as much exact and precise as the law of gravitation. If you can be fully established in the practice of non-violence in thought, word and deed, you are God.

The path of Ahimsa is narrow, but if you practise Ahimsa in right earnest, you can easily travel the path, since you cannot but get the divine grace at every step.

A holy man with piety is far superior to the mighty kings of countries. God is much pleased with a pious man.

A man who keeps up his promise creates a very good impression on the minds of others and merges in Divinity.

Cultivate sympathy, love, mercy and sincerity and other divine virtues described in the Gita. Lead a well-regulated life. Moral strength is the backbone of spiritual progress. Ethical culture is part and parcel of spiritual Sadhana.

RELIGION: THE BASIS OF MORALITY

Morality is the quality of being moral. Morality is that in an action which renders it right or wrong. It is the practice of moral duties apart from religion.

Morality is the doctrine of the right and wrong in human conduct. It is virtuous life. Sometimes in a limited sense it means sexual purity.

Morality is virtue. Morality is ethics. It is the doctrine which treats of actions being right or wrong.

Morality is everywhere the same, because it comes from God.

Morality is religion in practice; religion is morality in principle.

What you ought to do, that you should do and that you must do, though it brings pain and loss. Why? Because, it is right.

You must do what is right at whatever cost of pain and loss.

All successful actions stand on the foundation of morality.

Morality without religion has no roots. It becomes a thing of custom, changeable, transient and optional.

There can be no high civility, no courtesy, no politeness, no elegant manners without a profound morality.

There is no true and abiding morality that is not founded on religion.

There can be no divorse of religion from morality. Morality is the basis of religion. Morality and religion are inseparable like heat and fire, coolness and ice, fragrance and flower.

Morality without religion is a tree without roots, a house built on the sand, a stream without any spring to feed it.

Discourses on morality are the best means to improve the character of man and recover him out of his vices and ignorance.

Morality must not be without religion. If so, it may change as you see inconveniences. Religion must govern it.

The morality of an action depends upon the motive from which you act. First have righteous principles and then you will not fail to do virtuous actions.

National morality cannot prevail in an exclusion of religious principle.

Without religion, morality will die. Religion is the very root of morality.

Put morality on its proper and right basis, viz., the fear and love of God.

Morals without religion will wither and die like a seed sown upon stony ground.

Morality is the doctrine of moral duties in life or of men in their social character.

Morality without God is bottomless impiety.

MORALITY AND ETHICS

The moral principles are not absolute in the sense that there is a state which transcends moral restrictions. But it does not mean that the moral laws can be neglected. Morality is the adherence to the inherent sense of the right which is voiced by the conscience that is not bound by selfishness and its several expressions or effects. Morality is the soul-sense, the truth-sense, which refuses to be restricted by the autocracy of the passions that disregard the universality of what is good, and which is free from the agony of imperfection. The purpose of the moral sense is to point out the way to perfection, and morality, therefore, can be judged from how far it directs the consciousness to unrestricted happiness which is not confined to one or some individuals or even to a part of the universe or merely to an aspect of existence. The wider the scope of the selfless consciousness and the joy consequent upon it, the more moral is the method with which such selflessness is practised or the act by which such selflessness is expressed. All selfish actions are immoral. What, then, is selfish action? It is an action which is intended to bring satisfaction to the senses and the ego of one's own individual being, without any intention to overcome the desires of the senses and the ego. In addition to those positive indulgences, immoral action includes other acts like causing harm, practising falsehood and committing theft, either in thought or word or deed. Passion, anger, greed, pride and jealousy are immoral qualities. Even benevolence cannot justify the violation of moral rules. Morality is "a great vow which is universal, not restricted either by conditions, states, places, times or circumstances." (Yoga-Sutras)

CONTENTS

PART 1

HOW TO CULTIVATE VIRTUES

Introduction 7
Abstinence. 19
Adaptability 20
Adversity. 22
Ahimsa 24
Alertness 24
Amiability 25
Application. 26
Aspiration 27
Attention 28
Behaviour 29
Benevolence. 30
Character 32
Charity 34
Cheerfulness 37
Complacency 39
Compassion 40
Consideration 41
Contentment. 42
Counter-thoughts 46
Courage 47
Courtesy. 48
Destiny 49
Determination 50
Dignity 51
Discretion 51
Discrimination 52
Dispassion. 53
Duty 53
Earnestness 54
Elegance 55
Emulation 57
Endurance. 58
Equanimity. 58

Faith 59
Fidelity 61
Firmness. 61
Forbearance 62
Forgiveness 63
Fortitude 63
Friendship 66
Frugality 68
Generosity 69
Gentleness 70
Goodness 70
Hints on Developing Goodness, Purity and Truthfulness 72
Gracefulness 74
Gratitude. 74
Heroism 75
Honesty 76
Hope. 77
Hospitality 78
Humility 78
Industriousness 79
Initiative 80
Inspiration 80
Integrity 81
Intuition 81
Kindness. 82
Love 83
Magnanimity 90
Manliness 90
Manners 91
Meekness 92
Mercy 92
Moderation 95
Modesty 97
Nobility. 99
Obedience. 99
Optimism 100
Patience 101
Patience and Perseverance 102
Patriotism 103
Peace 104
Perseverance 105
Philanthropy 106
Pity 106

Pluck. 107
Pluck or Knack 107
Politeness 108
Promptness 110
Prudence 111
Punctuality. 112
Purity 113
Pushing Nature 113
Regularity and Punctuality. 114
Renunciation 116
Repentance 117
Resolution 118
Resourcefulness. 118
Right Conduct 119
Righteousness—The Breath of Life 124
Self-analysis 126
Self-control 127
Self-denial 129
Self-examination. 130
Self-help 130
Self-confidence 131
Self-restraint. 131
Self-discipline 131
Self-improvement 131
Self-reliance 132
Self-sacrifice. 134
Serenity 134
Silence. 135
Simplicity 135
Sincerity 136
Sympathy 141
Sweetness. 141
Tact 143
Temperance 143
Toleration 146
Truth Alone Triumphs 148
Will-power 155
Zeal 159
Justice 159
Meditation on 12 Virtues. 161
List of Virtues to be Developed 162
Word-picture of Virtues 163
Song Of Eighteen 'Ities 164

PART II

HOW TO ERADICATE VICES

Affectation 171
Ahamkara 172
Anger 177
Anxiety. 179
Arrogance 180
Avarice 184
Song of Avidity. 185
Backbiting 185
Boasting 186
Bribery. 187
Cares, Worries and Anxieties 188
Carelessness and Forgetfulness 191
Covetousness 192
Cowardice 192
Crooked-mindedness 193
Depression 193
Diffidence 194
Dilly-dallying 195
Dishonesty. 195
Envy 196
Evil Company 197
Fanaticism. 197
Fashion: A Terrible Curse 198
Fault-finding 201
Fear 203
Fickleness 205
Film-going 206
Forgetfulness 207
Gloom and Despair 208
Gambling 208
Greed 209
Hatred 210
Religious Hypocrisy 213
Idleness 213
Impure and Immoderate Food 214
Inconstancy 215
Indolence 215
Indecision 216
Inertia 217

4. Spiral with blue light; see it mix and flush the energy within the student's body. Spiral this energy down to the ground.
5. Energize the student with **white** or **violet** light.
6. You can also use both hands to channel Chi when you 'push and pull' through the body.
7. **Spiral in** - spiral clockwise to bring energy into the body and energize it.
8. **Spiral out** - spiral counterclockwise to cleanse, flush and remove energy.
9. When you begin pushing, pulling and sweeping, you may feel resistance in the body. As you progress and the energy centers open, this feeling will diminish.
10. There are many color combinations that can be applied to the various parts of the body. When you start practice, stick to the basic 'blue, green, white, violet and blue' formula. When you are working on a specific area, you can keep this book near by, or write a short 'color recipe' before you begin. In this way, you will be able to relax your mind.
11. 'Pushing and pulling' is like fanning and venting the body; when you fan your hands in front of your face, it will have a cooling effect. Ventilation enables the stagnant, sick energy to leave the body.

    Below is a list of the body's organs in relation to their tendency to 'store heat'. They are listed in descending order, i.e, the head is the hottest.

    Head, heart, liver, lung, stomach and spleen, large intestine and small intestine, kidneys and sexual organs (which become hot when aroused).

Outline of Practice

The **solar plexus** is the clearing house for emotional energy and is situated in between the lower and higher energy centers and in the center of most of the internal organs. All the organs dump their negative emotions here. The internal organs can be cleansed by sweeping the solar plexus, energizing, cleaning and flushing it of sick energy. When you feel sick energy in the body, give the command: "Stay". This is very important; it makes sure that none of the cells hide from the dazzling light that you are sending in.

1. Scan; ask for the power to look at the cells.
2. Push, pull and give the command "Disperse". Push until you feel the solar plexus clear and open.
3. Spiral green Chi counterclockwise. Talk to the sick energy; tell it to "Leave", you will take it to "a better place, where it will be happy". Give the command "Out".
4. Spiral Blue Chi counterclockwise, flushing out any remaining sickness. Guide the sick energy into the earth.
5. Spiral and sweep Blue - Green and Red Chi into the solar plexus, sweep the organs. Do not use in cases where there is intestinal infection and internal bleeding (which can be worsened) or in the presence of pregnant women.

Sense of Inferiority 218
Intolerance 218
Irresolution 219
Jealousy 219
Jilly-jallying 222
Manorajya 222
Mean-mindedness 223
Meat-eating 224
Miserliness 226
Name and Fame 229
Novel-reading 230
Obstinacy 230
Ostentation 231
Over-credulousness 232
Passion 232
Pessimism 240
Pig-headedness 241
Pilfering Habit 242
Prejudice 243
Moral and Spiritual Pride 244
Procrastination 245
Prodigality 245
Revenge 246
Rudeness 247
Self-assertion 248
Self-conceit 248
Self-justification 249
Selfishness 250
Self-sufficiency 251
Shilly-shallying 252
Shyness 253
Slang Terms and Abuses 254
Sleeping in Daytime 255
Smoking Habit 255
Suspicion 257
Tale-bearing 258
Timidity 258
Treachery 258
Vanity 259
Villy Vallying 261
Worry 262
Destroy Evil Vrittis 263
List of Vices to be Eradicated 264

PART I

How to Cultivate Virtues

ABSTINENCE

Abstinence is abstaining or refraining especially from some indulgence. Abstinence is temperance.

Abstinence is the act, practice or state of abstaining from something or some act or practice especially a total abstaining from the use of intoxicating drinks; self-denial, self-restraint as abstinence from the pleasure of the table, abstinence from alcoholic beverages, sexual indulgence.

Abstinence is refraining from an indulgence of appetite or from customary gratifications of animal propensities. We speak of abstinence from meat, abstinence from whisky, abstinence from food or sexual indulgence.

Total abstinence is the specific name for the act and practice of refraining from the use of intoxicating liquors.

Abstinence is continued temperance which gives longevity, good health, and keeps the body free from diseases.

Abstinence is a discipline which gives Vairagya or dispassion and helps the aspirant to march forward in the path of Yoga. Abstinence is the practice of Yama or self-restraint. It is the ground-work of virtue.

Abstinence is the strongest fence against diseases. It is the defensive virtue against ailments. It is the bestower of radiant health, vim, vigour and vitality.

Give up tea or coffee or smoking for a week. This will give you strength or will-power for the next abstinence. The third abstinence will be more easy.

The aim of abstinence is to set the mind above the lower appetites. It is indeed an aid for self-improvement.

Abstemiousness, continence, fasting, moderation, self-control, self-denial, self-restraint, sobriety, temperance are synonymous with abstinence.

Drunkenness, excess, gluttony, greed, intemperance, intoxication, revelling, revelry, self-indulgence, sensuality, wantonness are the opposites of abstinence.

Abstinence from food commonly signifies going without it. Abstemiousness is partaking moderately. Abstinence may be for a single occasion. Abstemiousness is habitual moderation.

Self-denial is giving up what one wishes. Abstinence may be refraining from what one does not desire. Fasting is abstinence from food for a limited time and generally for religious reasons. Sobriety and temperance signify maintaining a quiet, even temper by moderate indulgence in something, complete abstinence from others. We speak of temperance in eating, but of abstinence from vice.

ADAPTABILITY

Adaptability is a virtue or noble quality by which one adapts or fits himself to others, whatever their nature may be. A man of adaptability accommodates himself with others, whatever their temperaments may be. This is a most desirable habit or quality for success in life. This has to be developed slowly. The vast majority of persons do not know how to adjust themselves with others. Adaptability is a peculiar knack or pluck to win the hearts of others and ultimately the battle of life by a little bit of bending.

The wife does not know how to adapt herself to her husband. She displeases her husband always and makes room for quarrels in the house and gets a divorce. The clerk does not know how to adapt himself to his boss or superior. He quarrels with him and gets an immediate sack. The disciple does not know how to adapt himself to his Guru. The business man does not know how to adapt himself to the customers and therefore loses his customers and business! The Dewan does not know how to adapt himself to the Maharajah. He has to leave the state service. The world runs on adaptability. He who knows the art or science of adaptability pulls on quite well in this world and is always happy under all conditions of life.

The man must be pliable if he wants to adapt himself. It does need much wisdom and ingenuity for developing adaptability. If the clerk understands well the ways, habits and temperament of his superior and accordingly adjust himself nicely to suit his ways, his superior becomes a slave of the clerk. You will have to use some kind words and castoroil. A little lubricant to soften his heart is all that is needed. That is all. Speak gently and sweetly. Carry out his orders to the very letter. Never retort him. Remember the maxim: “Obedience is greater than service.” The superior wants a little respect. Say “Hanji-Hanji, Ji-huzur, very well Sir.” It costs you nothing. Then your superior becomes your slave. He has for you a soft corner in his heart. You become his pet. He will do whatever you want. He will excuse your mistakes. Humility and obedience are necessary for developing adaptability. That egoistic, proud man finds it very difficult to adapt himself. He is always in trouble. He always fails in his attempts. Egoism and pride are two important and insurmountable obstacles in the way of developing adaptability.

When one student does not know how to adapt himself to his fellow students who are living in the same room, friction comes and their friendship is at stake. Adaptability makes friendship last for a long time. Students fight for little things. One student says: "I gave Mr. X tea for several days. I took him to the cinema on my own account for many days. I asked him to lend me the book 'Boswell's Life of Johnson' for reading. He has bluntly refused now. What sort of friend he is! I do not like him at all." Thus the friendship is broken now. A simple thing upsets the mind. Adaptability is a strong catgut ligature that links people in bonds of unbroken love and friendship. A man of adaptability can pull on with anybody in any part of the world. People unconsciously love a man of adaptability. Adaptability gives immense strength and profound joy. Adaptability develops will.

A man of adaptability has to make some sacrifice. Adaptability develops the spirit of sacrifice. It kills selfishness. A man of adaptability has to share what he has with others. He has to bear insult and hard words. A man of adaptability develops the feeling of unity or oneness of life. For Vedantic Sadhana it is of invaluable help.

He who practises adaptability has to destroy the feelings of Ghrina, contempt and the idea of superiority. He has to mix with all. He has to embrace all. Adaptability develops universal love and kills the feeling of hatred.

A man of adaptability has to put up with the unkind words of his fellowmen. He has to develop patience and endurance. These virtues develop by themselves when he tries to adapt himself with others. A man of adaptability can live in any environment. He can bear the heat of Benares or Africa. He can live in a hut. He can live in a cool place. He develops balance of mind. He can bear extreme heat and cold. Adaptability brings eventually Atma-Jnana. He who has this noble virtue is a great man in all the three worlds. He is always happy and successful.

ADVERSITY

I

Adversity is adverse circumstance. It is affliction or misfortune or calamity.

Adversity is a state or condition characterised by untoward, harassing circumstances, severe trial or affliction. It is opposed to prosperity. Adversity is an event or series of events which oppose success or desires. It is a state of unhappiness.

Adversity is a blessing in disguise. Sweet are the uses of adversity. It strengthens the will power and the power of endurance and turns the mind more and more towards God. It instils dispassion or Vairagya in the heart. It is the first path to truth.

Adversity is a virtue. It makes the idle industrious. It draws out the faculties of the wise. It puts a man to the necessity of trying his skill. It has the effect of eliciting talents, capacities which in prosperous circumstances have remained dormant.

It is easy to bask in the sunshine of prosperity. The crucial test is your conduct under hardship and adversity.

Do not put on a sad countenance when you are in adverse circumstances. Smile. Laugh. Rejoice. Draw power and strength from within. Sing Ram, Ram, Ram. Chant Om, Om, Om. There is a magazine of power and knowledge and bliss within in your own Soul or Atman. Feel this. Realise this.

A smooth ocean never made one a dexterous Captain of a ship or an Admiral. The storms of adversity rouse the faculties and talents of an individual and generate prudence, skill, fortitude, courage, patience and perseverance. Adversity makes one think, invent and discover.

When you are in a prosperous condition, you will have countless friends, but when you are in adversity, they will leave you. Adversity is the only balance to weigh friends; prosperity is no just scale.

You will learn many lessons during adversity. Adversity will mould you properly. It is your great teacher. It is the best and severe instructor.

Great persons and saints have been tried, smelted, polished and glorified through the furnace of adversity.

Adversity is highly beneficial. Do not weep when you are in adverse conditions. Adversity strengthens your nerves and sharpens your skill.

Bereavement, calamity, disaster, distress, hardship, ill-fortune, misfortune are synonymous with adversity.

Any considerable disappointment, failure, misfortune, such as loss of fortune, position and the like constitutes adversity.

For the loss of friends or relations by death we commonly use the term bereavement.

Calamity and disaster are used for sudden and severe misfortunes, often overwhelming; ill-fortune and ill-luck of lighter troubles and failures.

We speak of the misery of the poor, the hardship of the soldier.

Blessing, boon, happiness, prosperity, success are the opposites of adversity.

II

You will find in the writings of Shakespeare, "Sweet are the uses of adversity which, like the toad, ugly and venomous, wears yet on its head a precious jewel." The best thing in this world is pain or adversity. During pain only man remembers God. Pain is the eye-opener. The quest of God begins from pain. The starting point of philosophy is from pain. Had there not been pain in this world, man would never have attempted to get freedom (moksha). He would have been satisfied with mundane life only. In trying to get rid of pain, he comes across Truth or the abode of Peace, Parama-Dhama. He starts prayer, Japa, charity, selfless service, study of religious books, etc. Bhaktas always pray to God, "O Lord! Give us sufferings always so that we shall ever remember Thee." Kunti Devi prayed to Lord Krishna, "Hae Prabhu, let me always have adversity, so that my mind shall be ever fixed at Thy lotus feet." Adversity develops power of endurance and will-force. Adversity develops fortitude and forbearance. Adversity melts a stony heart and infuses devotion to God. Adversity is a divine blessing in disguise. Do not be afraid, therefore, when you are in adverse circumstances. Adversity has got its own virtues. People have risen to power and position from adverse conditions of life. Adversity makes a man to struggle hard. The late Sir T. Muthuswami Iyer, Chief Justice, High Court, Madras, was in adverse circumstances.

He used to study at night under a municipal street lantern. Many Prime Ministers of England had risen high from adverse conditions of life. All the prophets, saints, Fakirs, Bhaktas, Yogins of yore had to struggle hard in adverse circumstances. Sankara, Jnana Deva, Rama Tirtha and Tukaram were all highly benefitted by adversity. They would never have achieved greatness and glorious spiritual heights had they been placed in luxurious conditions.

AHIMSA

(1) Let not anyone injure life, but be as assiduous in cherishing the life of another as his own. For Ahimsa is the highest religion. —*Tirthankara Mahavira.*

(2) So let us for all creatures, great or small, develop such a boundless heart and mind. Aye, let us practise love for all the world. —*Goutama Buddha.*

(3) Thou shalt not kill. —*Jesus Christ.*

(4) He who saveth a life, shall be as though he had saved all mankind alive. (For) there is no beast on earth nor bird which flieth with its wings but the same is a people like unto you. —*Mohammed (Koran, VI-38).*

(5) A man should prefer good to harm, good deeds to sins, virtue to vice, light to darkness. —*Zoroaster.*

(6) One Self dwells in all. All are manifestations of the One God. By injuring another you injure your own self. By serving another you serve your own self. Love all. Serve all. Hate none. Insult none. Injure none, in thought, word or deed.

—*Swami Sivananda.*

ALERTNESS

Alertness is watchfulness. It is briskness. It is sprightliness.

Alertness is an attitude of vigilance. It is used principally in the phrase 'on the alert' as 'the watchman stood on the alert.'

A captain of a ship is ever alert. A fisherman is ever alert. A surgeon in the operation theatre is ever alert. Even so a thirsting, hungry aspirant, should be ever alert. Then alone can he curb and subdue this mischievous, turbulent and formidable mind. Alertness is an important qualification of a student in the path of Yoga.

Be on the alert. Have an alert attitude. Be on the lookout. Be ever ready. Be circumspect. Be watchful. Be vigilant. You will always attain success in all undertakings and spiritual Sadhana.

A man of alertness is keenly watchful. He is ready to act at a short notice. He is nimble like the squirrel. He is characterised by briskness.

An alert man is lively. He is prompt and ever prepared. He is wide awake.

'Alert', 'ready' and 'wide awake' refer to a watchful promptness for action.

'Ready' suggests thoughtful preparation. The wandering Indian is alert; the trained soldier is ready.

'Ready' expresses more life and vigour than 'prepared.' The gun is prepared. The man is ready.

'Prompt' expresses readiness for appointment or demand at the required moment. The good General is ready for emergencies, alert to perceive opportunity or peril, prompt to seize the occasion.

The sense of brisk 'nimble' is the secondary and now less common signification of alertness.

Drowsy, dull, heavy, inactive, sluggish, stupid are the opposites of 'alert'.

Let a pastor live in a state of alertness toward all resources of oratorical knowledge. Let magistrates alertly perform their parts.

The French are alert rather than spontaneous.

AMIABILITY

Amiability is the quality of being amiable or of exciting love.

A man of amiability is of sweet disposition. He radiates so much of mental sunshine, love and joy that he is reflected in all appreciative hearts.

Amiability is the constant desire to please and love others.

Amiability is kindness or sweetness of disposition. It is loveableness.

A man of amiability possesses the agreeable mood or social qualities that please and make friends. He is friendly or pleasing in disposition. He is kind-hearted, gracious, genial. He has good na-

Cleansing the Spinal Cord

Always cleanse the spinal cord, which protects the entire body from diseased and negative energy, both physical and psychic. When you open the spinal cord and solar plexus you can release many energy blockages. Sweep the hand in a clockwise motion to energize the spine with either/or a combination of: blue, green, white and ultra-violet. Then spiral counterclockwise and brush the spine down to the ground. Continue sweeping until you feel that the spinal cord has cooled down. Remember not to use orange or red

Cleansing the Blood (Lungs)

The blood can be cleansed by energizing the lungs with whitish green, then with light whitish orange. The blood passing through the lungs will absorb the green and orange Chi, thereby cleansing the blood plasma and vessels and the rest of the body. This technique is very useful for treating ailments of the blood and of the arteries and for severe infections. Do not use it on pregnant women.

Outline of Practice

1. Scan the student.
2. Push through and open the lungs from the back to the front.
3. Energize the lungs from front to back with light whitish green, then with light whitish orange. Push through.
4. If the student is weak, energize the lungs with light whitish red, which will provide a strengthening effect.
5. The **spleen**, **liver and kidneys** purify the blood. Push and pull through the organs and energize with white Chi.
6. The blood requires a lot of cleaning on a regular basis.
7. Energize with white Chi. **Germs can only grow in the dark. 'Fill yourself with the light'.**

General Principles

Energy can be introduced to the affected area of the body by moving the hand clockwise in a spiral. **Flush** means to return the sick energy to the earth for recycling.

Stabilize means to return the area to normal functioning.

Spiral in a **clockwise** motion when you are '**stabilizing**'.

Use **blue or white** light to energize the area that you are working on.

Use **green** light to **energize** and **clean** the area that you are working on.

Use **blue** light to **flush** and **stabilize** the area that you are working on.

Use **violet** light to **balance** the sick energy and **reprogram** the cells of the body.

ture. He is free from irritation. He possesses sweetness of temper, kind-heartedness, excellent lovable disposition.

Kind smiles and courteousness pay high dividends.

The man of amiable character has ready affection and kindliness for others, with the qualities that are adapted to win their love. Amiable is a higher and stronger word than good-natured or agreeable.

'Amiable' denotes a disposition desirous to cheer, please and make happy. The really amiable man avoids harsh words and rudeness. He has an easy disposition to get along comfortably with every one in all circumstances.

Kind, good-natured people may be coarse and rude.

Abominable, churlish, cruel, disagreeable, hateful, ill-tempered, unlovely, unamiable are the opposites of "amiable."

Cultivate amiability. Let it become part and parcel of your nature.

APPLICATION

Application comes from the root *applicatio*, a binding on, or joining to; from *applicatus*, to join or fasten to. It is the art of fixing the mind. There is intensity of thought in application. It is close study.

Application is diligence. Application is close thought and attention. Assiduity is application.

Application is the testing or carrying into effect of a general law, truth or precept by bringing it into relation with practical affairs or applying it to a particular cause. It is also the capacity of being thus used or means of result of such action as the application of the Sermon on the Mount or the Yogic Yama-Niyama in daily life.

Application is the fixing of the attention closely on that upon which one is engaged; also the habit or capability of so fixing it.

Steady application to work is the healthiest training for every individual.

In common parlance we say: "Mr. John injured his health by application to study." We also say: "Had his application been equal to his talents, his progress might have been greater."

A man who is endowed with the virtue of application gets success in all his undertakings. Prosperity is his attendant.

A man of application rises up early and goes to bed at the proper time. He never wastes even a single second. He is ever watchful, vigilant and diligent. He is ever active. He never loses opportunities. He is like the surgeon in the operation theatre. He is like the captain in a ship.

He is healthy. His mind is light and cheerful. His thoughts are clear. His room is in order. He is methodical in his work. He has resolution and determination. He never repents nor regrets.

He is wealthy. He is free from want. He rises to power and eminence. He attains fame. He is honoured and respected.

Whatever you resolve to do, do it now, do it quickly. Tarry not a second. Defer not till the evening what you can accomplish in the morning.

This moment is yours. The next second is in the womb of the future. You know not what it may bring forth.

Do not depend much upon the future. Do not regret for the past. Live in the living, solid present. Act, act, act now. Strive, strive, strive now. Exert, exert, exert. Apply all your vigour, strength and energy. You are bound to succeed. You will surmount easily all sorts of temptations and obstacles. Failure is unknown to a man of intense application.

Without intense application you cannot enter into deep meditation and Samadhi.

Sloth, inertia, idleness, carelessness, recklessness, procrastination are the opposites of application.

O Ram! Cultivate application and attain success, plenty, peace and prosperity and Kaivalya now and here.

ASPIRATION

Aspiration is burning desire to attain God-realisation.

To aspire is to desire eagerly or to aim at high things.

God is the one true aim of all right human aspirations.

Aspiration is earnest longing or an earnest wish for that which is above one's present reach or attainment, especially for what is noble, pure and spiritual.

To aspire is to rise or reach upward. To aspire is to have an earnest desire, wish or longing as for something high and good, not yet attained usually accompanied by endeavour to attain it.

ATTENTION

Attention is steady application of the mind.

Attention is the direction of the mental powers to a specific object with vigour and concentration.

Attention strengthens the will. It is at the base of the will. Attention develops concentration.

Attention leads to sure success. It is for want of attention that man meets with failures.

Attention makes the genius. The power of applying attention, steady and undissipated to a single object is the sure mark of a superior genius.

All learning, science and skill depend upon attention. Attention opens new worlds, heals diseases.

Attention is the source of poetic genius and of the genius of discovery and success.

It was attention that led Newton to the discovery of gravitation, Hervey to find out the circulation of the blood, and Davy to those views which laid the foundation of modern chemistry.

Attention is a form of psychical energy which necessarily enters into the determination of the character of every field of consciousness.

It is the act or process of giving especial clearness to one or more particulars in the complex content of consciousness.

It is the form of mental functioning or faculty which makes possible the selection of certain of the contents of consciousness, for the purpose of giving to them an increasing clearness.

The general fact of experience from which the conception and doctrine of attention in modern psychology take their rise is that some objects or parts of objects in the field of consciousness are more clearly and vividly impressed than others or are apperceived and recognised, while others are only dimly or scarcely at all apprehended.This difference in clearness often seems to be dependent on a selective act or process of the subject. In reflex or non-voluntary attention the object seems to force itself upon the mind either through the intensity of the stimulus or the advantage of special interest. In voluntary attention, the subject in order to gratify curiosity or carry out some other purpose seems to choose the object which shall be more clearly apprehended.

A man hears with attention. Then we say: “He has an attentive ear.” He sees with attention. Then we say: “He has an attentive eye.” In contemplation one has application of the mind. When a man is attentive to the words of a speaker and to the manner and matter of his speech at the same time, he has application of the mind and the senses, too.

BEHAVIOUR

Behaviour is conduct, manners or deportment, especially good manners.

To behave well is to conduct well with others.

You can know the nature of a man and the nature of his mind from his behaviour.

Behaviour is a mirror in which every one shows his image.

Good behaviour is a passport for friendship and favourable reception in society.

Knowledge gives confidence to the outward behaviour.

Levity of behaviour or lightness of conduct is the bane of life.

Oddities and singularities of behaviour, whimsical peculiarities are blemishes of a man. He should correct himself and remove these defects. He who wants to improve himself must be ashamed of these defects.

To observe propriety in personal conduct is good behaviour. To conduct in a fitting or proper manner is good behaviour.

Behaviour is an expression of knowledge and taste and feeling in combination.

Behaviour is our action in the presence of others. Conduct implies personality and moral responsibility.

Carriage expresses simply the manner of holding the body, especially in sitting or walking as when it is said of lady “She has a fain carriage.”

Bearing refers to the bodily expression of feeling or disposition, as a haughty bearing, a noble bearing.

Demeanour is the bodily expression, not only of feelings, but of moral states, as a devout demeanour.

Breeding denotes that manner or conduct which result from good birth and training.

Deportment is behaviour as related to a set of rules as “the students’ deportment was faultless.”

A person's manner may be that of a moment or toward a single person; his manners are his habitual style or behaviour toward or before others, especially in matters of etiquette and politeness, as 'good manners are always pleasing.'

Behaviour is the manner of our behaving ourselves towards others.

Conduct is the manner of our conducting ourselves and involves the general tenor of our actions. The former, like deportment, is shaped chiefly by circumstances; the latter is a development of the individual.

Behaviourism is the study of the individual based on objective analysis and personal behaviour. The theory that all investigation of behaviour must be objective and introspection is invalid.

BENEVOLENCE

Benevolence. Latin: *Benevolentia*, good feeling; *bene*—well, and *volens*—to wish.

Benevolence is disposition to do good. It is gift of money, especially for support of the poor. It is an act of kindness. It is generosity.

Benevolence is the disposition to seek the well-being or comfort of others. It is the desire to alleviate suffering or promote happiness. It is love of mankind or kindliness of heart or charitableness.

Benevolence is the all-inclusive virtue. In order to attain the perfection of benevolence itself the moral judgment of men requires all the other most cardinal virtues both of will and of judgment. All these other cardinal virtues qualify benevolence, as benevolence employs, consecrates and qualifies them.

Benevolence is the natural organ or propensity that prompts to kindness and liberality.

Benevolence is the minister of God. It is a rare virtue.

To feel much for others and little for ourselves, to restrain our selfish and excercise our benevolent affections, constitutes the perfection of human nature.

No one in this world is perfectly independent. He is in need of the assistance of others. Man is placed in society to receive and confer reciprocal helps and mutual obligations.

Your food, your clothes, your health, your protection from injuries, your enjoyment of the comforts and pleasures of life—all these you owe to the assistance of others. Therefore, be benevolent to others. Be a cosmic benefactor. Be a friend to mankind.

The conqueror is regarded with awe; the wise man commands our respect, but it is only the benevolent man who wins our affection.

A benevolent man enjoys peace, joy and tranquillity. He rejoices in the happiness and prosperity of his neighbour and all other people.

He who employs his wealth, his thought, his speech, to advance the good of others is a glorious man. He is a veritable god on this earth.

He always searches out occasions for doing good to others in a variety of ways.

The laws of social benevolence require that every man should endeavour to assist others.

Barbarity, brutality, churlishness, greediness, harshness, ill-liberality, illwill, inhumanity, malevolence, malignity, niggardliness, selfishness, stinginess, unkindness are the opposites of benevolence.

Alms-giving, beneficence, benignity, bounty, charity, generosity, goodwill, humanity, kind-heartedness, kindliness, kindness, liberality, munificence, philanthropy, sympathy, tenderness, are all synonymous with benevolence.

Kindness and tenderness are personal. Benevolence and charity are general. Kindness extends to all sentient beings whether men or animals, in prosperity or in distress. Tenderness especially goes out towards the young, feeble and needy. Humanity is kindness and tenderness toward man or beast. Generosity is self-forgetful kindness in disposition or action. It includes much besides giving.

Bounty applies to ample-giving, which on a larger scale is expressed by munificence.

Liberality indicates broad, genial, kindly views, whether manifested in gifts or otherwise.

We speak of the bounty of a generous host, the liberality of the founder of a college, or of the liberality of a theologian toward the holders of conflicting beliefs.

Philanthropy applies to wide schemes for human welfare often, but not always, involving large expenditure in charity or benevolence:

Do not wait for extraordinary circumstances to do good actions. Try to utilise ordinary situations.

CHARACTER

Character is the aggregate of peculiar qualities which constitute an individuality.

Character is the combination of qualities distinguishing any person or class of persons. It is any distinctive mark or trait of a person.

Character is power. Character is everything. Character is real property. It is the noblest of all possessions.

Character is perfectly educated will. It is higher than intelligence.

Every man is the architect of his own character. You sow an action, and reap a habit. You sow a habit and reap a character.

Actions, looks, words, steps, form the alphabet by which you may spell characters.

A man is known by what he loves—friends, places, books, dress, food, thoughts, actions, speech; from these his character is told.

Determination to build definite character in life is needed. This must be followed up with persistent striving.

All that is lasting is your character. You can take nothing else with you save your character when you leave the world.

Character is not born. It is formed.

The noblest contribution which any man can make for the benefit of posterity is that of a good character.

Character is a diamond that scratches any other stone.

Character lives and abides.

Good nature, benevolence, truthfulness, tolerance, temperance, justice, etc. lie at the foundation of character.

Character is the end and aim of all your intellectual discipline.

Character is the produce of self-discipline. The grand aim of man's creation is the development of a grand character.

Character is more worthy of attainment than anything else in this world.

The richest bequest which any man can leave to the world is that of a shining, spotless example.

The essential factors in character building are morality, truthfulness, justice, temperance, wisdom, nobility, nonviolence, purity and benevolence.

Nothing in this world—wealth, name, fame, victory—is worth a fig or a straw without character. Character must stand behind and back up everything.

It is not wealth or power nor is it mere intellect that governs the world. It is moral character associated with moral excellence that really rules the entire universe.

Character is not developed in a day. It is created bit by bit and day by day.

Wealth comes and goes. Fame evaporates. Power dwindles. Only one thing endures. That is Character.

Strong character is formed by strong and noble thinking.

A man's true estate of power and wealth lies in his own essential character.

Take care of your character. Your reputation will take care of itself.

A good character is the fruition of personal exertion. It is the result of one's own endeavours.

Truthfulness is a corner-stone in character.

Not education, but character, is man's greatest need and greatest safeguard.

There is no single royal road to build your character. A variety of routes will always need to be used.

Build your character; you can shape your life.

Character is power. Character is influence. It makes friends. It draws patronage and support. It creates friends and funds. It opens a sure and easy way to wealth, honour, success and happiness.

Character is the determining factor in victory and defeat, success and failure and in all the issues of life. A man of good character enjoys life herein and hereafter.

Man is not a creature of circumstances. He is really the architect of circumstances. A man of character builds an existence out of circumstances. He steadily perseveres and plods.

He does not look back. He marches forward bravely. He is not afraid of obstacles. He never frets and fumes. He never gets discouraged and disappointed. He is full of vigour, energy, vim and vitality. He is ever zealous and enthusiastic.

Small kind acts, small courtesies, small consideration, small benevolence, habitually practised in your social intercourse give a greater charm to your character than great platform lectures, discourses, oration, exhibition of talents, etc.

Character is like an inward and spiritual grace of which reputation is the outward and visible sign.

Character is what one is: reputation, what he is thought to be. His record is the total of his actions. A man's record will substantially express his character. His reputation may be higher or lower than his character or record will justify. One's nature includes all his original endowments or propensities; character includes both natural and acquired traits.

Character is the peculiar quality impressed by nature or habit on a person which distinguishes him from others.

Dominant characters are, in heredity, the predominant characteristics which are transmitted by either parent to the offspring with little or no variations and which form the prevailing characters.

Recessive characters are characters found in the offspring which may be referred to one or the other of the parental forms, but which are not the prevailing characters. In subsequent generations, the recessive characters never predominates.

CHARITY

I

Charity is alms-giving. It is the disposition to think favourably of others and do them good. Charity is universal love. It is liberality to the poor. It is benevolence. That which is given to relieve the needy is charity.

In a general sense, charity means love, benevolence and goodwill. In a theological sense it is universal goodwill to men and supreme love of God. In a more particular sense, it means love, kindness, affection, tenderness, springing from natural relations as the charities of father, son and brother.

True charity is the desire to be useful to others without thought of recompense or reward.

He who is least unjust is the most charitable in his judgement.

The deeds of charity you have done will stay for ever with you.

Give cheerfully, quickly and without hesitation.

Give one-tenth of your income or one anna per rupee in charity.

Charity covereth multitude of sins. Charity is a great purifier of the heart.

Prayer takes you halfway to God, fasting to the door of His Supreme Abode and charity procures you admission.

Charity is love in action.

Charity begins at home, but it should go abroad. The whole world is your home. You are a citizen of the world. Cultivate a generous feeling for the welfare of the whole world.

That charity which advertises ceases to be charity. It is only pride and ostentation.

Every good act is charity. Giving water to the thirsty is charity. An encouraging word to a man in distress is charity. Giving a little medicine to the poor sick man is charity. Removing a thorn or a glass piece on the road is charity.

A little good thought and a little kindness are often worth more than giving a great deal of money.

Defer not charities till death. Do charity daily.

If you give food to a poor man, he again wants food when he becomes hungry. The best form of charity is Vidya-Dana, imparting wisdom. Wisdom removes ignorance, the cause for taking a body and destroys in toto all sorts of miseries and suffering, for ever.

The second best form of charity is giving medicine to the sick. The third best form of charity is Anna-dana or giving food to the hungry.

Do charity silently. Do not advertise; what your right hand does, the left hand should not know.

First daughter to the love of God is charity to the poor.

Do discriminate charity in the beginning. Later on practise indiscriminate charity. When you feel that every being is a man-

For **general infections** always **use green** (energize and clean) and **blue** (stabilize) light. Use violet light to balance the sick energy and reprogram all the cells. Use the ‘Chi Knife’ for infections as well. Never use orange on the head, heart and spleen.

Give the command **“Stay”** to make sure **all the cells receive the light** you are sending in. Remember that germs and bacteria cannot hide in the light.

Energize means to draw the Cosmic Chi into the part that requires healing.
Cleanse means to clean all the cells being treated.

You can also work on yourself. You may need some help when working on the back. If you obtain optimum health and practice the Cosmic Orbit regularly then you will never ‘need’ to apply any of these techniques to yourself.

Like all Chinese medicine, Cosmic Healing works on the system as a whole, balancing the entire organism, treating the cause to cure the symptoms.

The techniques really are simple.

When in doubt use; blue, green, white, violet, blue.
You can always use white and violet.
Upper organs - use violet.

You can practice group healings and then link your students’ personal stars together, at an agreed time later in the day. **You can then perform the World Link Cosmic Healing**.

Work on any other ailments that the student may have.
The simplest way to learn is to begin practicing today.
The simplest way to heal is to allow yourself to be healed.

ifestation of the Lord, it is difficult to discriminate. Who is good? Who is bad?

Charity given with an unwilling heart is not charity.

Charity is not confined to giving in term of dollars, rupees or shillings. Think well towards suffering people. Pray for their welfare. This will accomplish more good than much money.

II

Prof. XYZ, M.A., Ph.D., gave a blanket in charity to a poor man. He afterwards thought, "I ought not to have given him a blanket." His heart was in a state of agitation and agony. He wanted to get the blanket back from the poor man. If you do such a kind of charity, you will not derive any benefit. You will not get purity of heart. Many worldly-minded people perform charitable acts of this description only. This world abounds in such charitable persons.

Charity must be spontaneous and unrestrained. Giving must become habitual. You must experience extreme joy in giving. You must not think, "I have done a very charitable act. I will enjoy happiness in heaven. I will be born as a rich man in the next birth. The charitable act will wash away my sin. There is no charitable man like me in my town or district. People know that I am a very charitable man." Begging is mean and deplorable.

Some people do charity and are anxious to see their names published in the newspapers with their photos. This is a Tamasic form of charity. This is no charity at all.

Lord Jesus says: "The left hand should not know what the right hand is doing." You should not advertise about your charity and charitable nature. There must not be an exaltation in your heart, when people praise you for your charitable nature.

You should be thirsty to do charitable acts daily. You should create opportunities. There is no Yoga or Yajna greater than Sattvic charity of the spontaneous type. Karna and Raja Bhoja did countless charitable acts. So, they still live in our hearts.

Give to the poor, the sick, the helpless and the forlorn. Give to the orphans, the decrepit, the blind, the helpless widows. Give to the Sadhus, Sannyasins, religious and social institutions. Thank the man who gives you an opportunity to serve him by doing charity. Give with the right mental attitude, and realise God through charitable acts. Glory to those who do charity with the right spirit.

CHEERFULNESS

I

Cheerfulness is the state or quality of being joyful, lively and of good spirits.

Cheerfulness lightens sickness and the burden of life, poverty and affliction, and gives wonderful strength and great power of endurance.

A cheerful man will do more work, in the same time, will do it better, and will persevere in it longer than a cheerless man.

Be cheerful always. Cheerfulness is the best tonic. It gives radiant health and peace.

A kind and sympathetic man will be over cheerful. Cheerfulness is health. It makes the mind serene. It bestows longevity. It strengthens the heart.

The light of a cheerful face diffuses itself. You are refreshed by the presence of a cheerful man.

A cheerful man is like a sunny day. He radiates brightness on all around.

Be cheerful, sweet, happy and smiling. You will become very healthy and you will radiate health in every direction.

Cheerfulness is an index of a happy mind and a pure, good heart. It is a passport and recommendation in society.

A cheerful man is a public benefactor. He gladdens the hearts of all.

There is no friend like cheer.

The contagion of cheer has a wonderful effect. It transforms depression into brightness, sicklessness and health. A cheery word spontaneously gives cheer to others.

Cheerfulness is a habit of mind. Gaiety is an occasional excitement of animal spirit. Mirth or merriment is noisy gaiety.

A cheerful man smiles; a merry man laughs; a sprigthly man dances; a gay man takes his pleasure.

II

Cheerfulness is joyful frame of mind.

A cheerful man is full of good spirits. He is lively. He radiates joy everywhere.

Cheerfulness is a potent mental tonic.

A cheerful mind strengthens the head and makes one steadfast in good conduct.

Be cheerful always. Cultivate cheerfulness. Wear a cheerful smile with a cheerful face.

A cheerful man is a public benefactor. He makes others happy and cheerful. There is no friend like cheer.

Cheer is contagious. It has a marvellous effect on others. It transforms darkness into light, depression into brightness and sickness into health.

The cheerful live a long life. They are healthy, radiant and vibrant.

Cheerfulness is the soul. It is offshoot of goodness. It is a beautifier.

A cheerful man creates friends quickly. He is attractive to all.

What sunshine is to flowers, cheerful, happy smiles are to humanity.

Cheerfulness is a solace in solitude and distress. It lightens sickness, poverty and affliction.

Wonderful is the strength of cheerfulness. Cheerfulness is a power. A cheerful man has great power of endurance. He will do more in the same time, will do it better, will presevere in it longer, than a cheerless man.

Cheerfulness is health; cheerlessness is disease.

A man whose heart is full of kindness, benevolence and sympathy will always be cheerful.

Mirth is an act. Cheerfulness is a habit of the mind. Mirth is short and transient. Mirth is like a flash of lightning. Cheerfulness is fixed and permanent.

Cheerfulness is a friend to grace. It puts the heart in tune to praise God. A cheerful man can meditate for a long time.

There are some persons who are born cheerful. This is due to their previous good, spiritual samskaras or impressions.

A cheering word spontaneously gives cheer to others.

A cheering word is more distinctly planned to cheer and encourage.

Gaiety, mirth, merriment, blithesomeness, gladness, jollity, liveliness, sprightliness, vivacity are synonymous terms.

COMPLACENCY

(MUDITHA)

Complacency is the state of being pleased with oneself or others. It is self-satisfaction. It is satisfaction with one's acts or surroundings. It is pleasant, good nature. It is the manifestation of tranquil satisfaction.

Complacency is inclination or disposition to please others. It is civility or amiability. A man of complacency adjusts, adapts and accommodates.

We say: "Purushottam's manners are so elegant, so gentle, so unassuming, that they at once engage esteem and diffuse complacence."

Chatterjee says: "Every moment of Bannerjee's life brings me fresh instances of his complacency to my inclinations."

Father loves his son with the love of complacency.

Disposition or wish to please or oblige others is complacency.

He who has complacency will not be jealous of those who are in a better position. He will have Chitta-prasada or peace of mind. Complacency eradicates jealousy and fills the heart with love.

People seldom improve when they have no other model but themselves to copy after.

The majority of people fail in their life, because they never learn to guard and strengthen their weak points.

Complacency makes a superior amiable, an equal agreeable and an inferior acceptable. It pleases all, prejudices none, strengthens friendship, redoubles love.

Complacency is a social virtue. It gives lustre and brilliance to every talent a man posseses.

When complacency is united with justice and generosity, it makes a man a centre of attraction, admiration, love, respect and honour.

Complacency sweetens conversation, smooths distinction and makes everyone in the company pleasant with himself. It is a leveller in society.

Complacency generates good nature and mutual benevolence, soothes the turbulent and humanises the fierce.

COMPASSION

(KARUNA)

Compassion is fellow-feeling or sorrow for the sufferings of another.

Compassion opens the door for Freedom and expands the heart. It melts the sin-hardened hearts of worldly people, and makes them as soft as butter.

The heart of a saint, sage or Yogi is filled with compassion.

Compassion leads to the attainment of peace or Chitta-prasada.

Compassion is sorrow or pity with a desire to help or to spare, excited by the suffering or distress of another or others. It is sympathy with pain or sorrow, that prompts one to relieve the pain and suffering of others.

The dew of compassion is a tear.

By compassion you make another's misery your own and so by relieving them, you relieve yourself, too.

Pity, commiseration, fellow-feeling, sympathy, kindness, tenderness, clemency are synonymous with compassion.

Most of the people are unsympathetic. They have no compassion. They are absolutely selfish. They may present a car worth Rs. 15,000/- to their daughter. They may spend Rs. 3,000/- for the petrol. But they will not spend even a rupee to relieve the sufferings of poor people. They have their eyes and ears closed. They do not hear the cry of distress of people in distress. They do not see the stream of tears flowing from their neighbours. They close their doors and eat Rasagulla, Kalakand and Parottas.

The whole world is one family. All are children of God. The whole world is your abode. Feel this. Open your heart to compassion. Share what you have with others. Wipe the tears of sufferers. God will bless you.

Cultivate compassion. Have a tender, soft heart. Know and understand the sufferings of others, and be ever ready to help them.

Compassion is strength. It gives strength and joy. It prepares your mind for the descent of divine Light.

May compassion arise in your heart!

CONSIDERATION

Consideration is indeed a beautiful virtue. A man of consideration always attains success in all undertakings.

Consideration is the soil in which wisdom grows. Therefore, cultivate this virtue, consideration, to a maximum degree.

Disregarding, ignoring, overlooking, neglecting, slighting and trifling are the opposite of consideration.

A thoughtless and talkative man who speaks at random entangles himself in the web of foolishness of his words.

In consideration there is mature thought, there is serious deliberation. You consider a matter well at first and then decide.

In consideration, you consider the matter well before deciding. You think about it, closely reflect upon it, you ponder over it, you give close attention to it, you cogitate, you study, you weigh it, you observe closely and carefully.

The art of taking into account and examining a thing is consideration.

Moral causes come into consideration in proportion as the progress of knowledge is advanced. Men of faith consider conscience of more importance than knowledge.

Take into consideration the consequences of your hasty decision.

Think with consideration.

Act with consideration.

Have consideration, respect or regard for the feelings of others. Consider the virtues of others.

Weigh your words before you utter them.

Consider well every step you take.

Do not plunge suddenly into action. Consider the consequences well and then act. Then alone will you not repent, you will not feel sorry.

A thoughtless man who has not controlled his organs of speech speaks at random without any consideration and weeps for his foolishness in the end. He is put to shame and disgrace. Therefore, be considerate at all times, on all occasions.

O man! Harken unto the voice of consideration and become wise. She will guide you and show you the path to safety, security, wisdom, truth, peace, immortality and bliss.

CONTENTMENT

I

I will now talk to you this most vital subject, contentment. You all know the maxim "A contented mind is a continual feast." The mind is always restless on account of greed. Greed is a kind of internal fire that consumes a man slowly. Contentment is a powerful antidote for the poison of greed. Just as a man who comes from a long walk in the sun is quite refreshed by taking a plunge in the Ganges, so also that greedy man who is burnt by the fire of Lobha finds immediate joy and relief by a dip in the ambrosial water of contentment. There are four sentinels who guard the domain of Moksha. They are Santi, Santosha, Satsanga and Vichara. If you can approach any one of these sentinels you can get hold of the other three. If you can get hold of Santosha or contentment, you can easily see the other three sentinels following you.

There is no greater gain than contentment. A man who is fully endowed with this important virtue is the richest man in all the three worlds. The peace that he enjoys cannot be adequately described in words. He is a mighty emperor on this earth. Tayumana Swami, the reputed sage of Southern India sings: "Even the richest man in this world who is equal to Kubera, who possesses Chintamani, Kamadhenu and Kalpataru, desires to have domain overseas. He tries to practise alchemy to have more wealth. That man who is living up to 150 years tries to prolong his longevity by taking Rasayanas and Siddha Kalpas. He who possesses one hundred crores of rupees tries his level best to make it two hundred crores of rupees. The mind grasps one thing and leaves it the next moment and tries to grasp another. Man moves restlessly in this world and says: "This is mine. That is mine. I will try to possess that also. O restless mind! Do not drag me in these impure desires and sensual objects. I know your ways pretty well. Keep quiet. O Supreme Being! Give me a desireless pure mind. Let my mind be ever fixed in the Truth. Let me be mindless. Let me rest in the Satchidananda Swarupa. O All-full Bliss! O Radiant Bliss! that permeates and pervades all these names and forms." Contentment is one of the important items in the Niyamas of the Raja Yoga philosophy. The Gita also says: "Be contented with whatever you get by chance and apply yourself to meditation with a dispassionate mind." Socrates speaks very highly of this virtue.

Although people know that contentment is a virtue that gives peace of mind, yet they do not try to develop this virtue. Why? Because they have lost the power of discrimination and the power of Atmic enquiry or Vichara Shakti on account of passion and greed. Greed is the Chief Officer of Passion. Wherever there is greed, there is passion and wherever there is passion there is greed almost invariably. The understanding gets clouded, the intellect gets perverted and the memory gets confused by passion and greed. Therefore people find it difficult to develop this virtue, contentment.

An objector says: "Well, Swamiji, what you say is quite correct. I quite realise that contentment gives peace. But I have a doubt. If I become contented, all my ambitions will die. I will become lethargic and lazy. On account of my various sorts of ambitions, I move about hither and tither, I exert and I am energetic. Kindly remove this doubt of mine. I am quite bewildered." My reply is simply this: "Contentment can never make you idle. It is a Sattvic virtue that propels man towards God. It gives strength of mind and peace. It checks unnecessary and selfish exertions. It opens the inner eye of man and moves his mind towards divine contemplation. It turns his energy in the inner, Sattvic Channels. It transmutes the gross energy viz., greed that is forcing man towards selfish exertions into spiritual energy, Ojas. That man who is contented is full of Sattva. He is more energetic now. He is inward. He has an inner life in the Atman. He is always peaceful. He turns out more work calmly and with one-pointed mind. All the dissipated rays of the mind are collected now. Do you understand the point now?" The objector replies: "Yes, Swamiji, the matter is quite clear now. I am fully satisfied."

It is on the strength of contentment that the sages and Rishis of yore, the Fakirs and Bhikshus move about in the world in a carefree manner by living on Bhiksha. It is contentment that gives strength to an aspirant to walk in the path of Self-realisation and emboldens him to march fearlessly in the rugged and thorny path of spirituality. It is contentment that makes an aspirant look upon the worthless, perishable things of this world as dung, poison, straw or dust. Contentment develops Vairagya, discrimination and Vichara.

Mira had perfect contentment. She never cared for the paltry things of the world. She lived on Bhiksha though she was a Rani of Chitore. She lived on bread that came by begging and took it to the banks of Jumna and was quite satisfied with this meagre food and plain water which served as drink. What gave her strength? It was contentment. Contentment opens the door of Moksha and the realms of eternal bliss and sunshine. Contentment is a divine virtue. He who has perfect contentment brings balance of mind and perfect poise.

Pattinattu Swami, a very great sage of Southern India was a very greedy man in his earlier life. He was very rich too. Yet he wanted to hoard up wealth. Lord Siva took the form of a small boy and presented a bundle of needles which had no eyes with a chit inside which contained the message: "What is the earthly use of the treasure of this world? Even this broken needle will not follow you when you die." This opened the eyes of the greedy merchant and infused Vairagya and contentment. He abandoned his home, wealth, wife and everything and lived upon alms, developed perfect contentment and realised his Self.

Contentment is Bliss. Contentment is nectar. Contentment gives immortality and infinite peace. Therefore develop this virtue. Lead a happy life. Rest in everlasting peace. Have a mental image of this virtue. Repeat mentally "OM CONTENTMENT." The mental habit of contentment will develop.

II

A contented mind is the greatest blessing a man can enjoy in this world. It has a beneficial influence on the soul of man. It destroys all inordinate ambitions, all murmuring, repining, and makes one serene, happy and rich. It is a pearl of inestimable value.

Contentment is the best tonic. It is the best medicine. It gives best health and peace of mind.

Happiness consists, not in possessing much but in being content with what you possess. He who wants little always has enough.

Wealth or power brings its peculiar inconveniences and troubles. A rich man is ever unhappy and discontented. Artha (wealth) is Anartha (an evil).

A poor man does not experience the vexations and anxieties of the rich, the difficulties and perplexities of power. A rich man and a man of power have their own secret griefs.

When your mind is troubled for want of shoes, think of the man who has no feet and be contented.

When you are discontented by looking at people who are superior to you, look at those who are inferior to you and be contented.

Want of desire is the greatest wealth. A desireless man is the most wealthy and contented man in this world. A contented man is never poor. The discontented man is never rich.

Be always contented with what happens. Know that what God chooses is better than what you choose.

If you are not contented with what you have, you will not be contented with what you like to have.

Contentment is natural wealth. Luxury is artificial poverty.

Abandon all desires. Desire only the will of God. Seek Him alone. You will find perfect contentment, peace and bliss.

If you increase your wealth, you increase your cares, worries and anxietes. But a contented mind is a hidden, supreme treasure. A man of contented mind knows not cares and anxieties.

A contented man is easy in mind. He does not repine. He is satisfied with things as they are. He never complains. He is resigned, satiated and satisfied.

Contentment is a celestial ambrosia or nectar. It cools the fire of greed.

O man! Lead a life of perfect contentment and be happy for ever. Live in God who is Nitya Tripti or Supreme Satisfaction or Contentment.

III

Contentment is the best virtue; contentment is called the true enjoyment; and the contented man gets the best repose. For a man of contentment sovereignty of the world is no better than chaff. Enjoyments of objects will appear to be poison to him. His mind is turned towards higher spiritual things and Atma Vichara. He derives happiness from within. He is never disturbed in adverse conditions. Contentment is the healer of all evils. It is a panacea for the cure of the dire disease—avarice or

Chapter VII
Different Hand Techniques

Forget about your Palms

An extremely important theory of Cosmic Healing Hand Techniques is to ‘forget about your palm’. This means that you should only use the palm (which is incredibly sensitive), for ‘guiding’ the universal energy into the right spot, sending out a minute beam of light, like a laser, that marks the place where the energy should be sent. Your palm is connected to your brain, which has been sunk into your Tan Tien. The light marker will serve as a beacon for the force that is directed down by your mind. Draw down the Universal Chi, guide it to the right spot and give the command; "Stay". This is very important, otherwise the Chi will disappear once you move your hand.

When you practice Cosmic Healing it makes no difference how many people you treat, because you are not transferring your own energy.

Don't Focus your Mind on the Sick Part

If you direct your attention towards something, your energy will go there. If you focus on some ailment, you are already sending out your energy. Instead you should try to connect with a greater source, Universal Chi, extending your mind very far away. This way you won't lose your power. The only thing you do as a practitioner is to form the connection between nature, the student and the sick energy or between the universe, the Chi field and the sick part.

Cosmic Healing is Teaching

One of the best methods of protection for a practitioner is the Fusion practice (*Refer to ‘Fusion of the Five Elements I by Mantak Chia*). Perhaps even better is for the practitioner not to perceive him/herself as a healer, but as a person that comes to guide people in something they have to do themselves. When you say; "I am a healer", the sickness or bad energy, has already found a new home. When you check it out, first it will try to hide, and then it will try to attach itself to you. But if you don't interfere, the energy will go straight to the ground. So it is very important to clarify that you are not a healer, but a practitioner that can help, and that the student or sick person has to do most of the job.

greed. The mind cooled by calm contentment is ever peaceful. Divine light can descend only on an aspirant who is endowed with contentment. A contented man though poor is the emperor of the whole world. A contented man is one who does not long after what he has not possessed; and enjoys what he has in right manner. He is quite satisfied with whatsoever he gets. He is magnanimous and graceful. Siddhis and Riddhis wait on him as if they are his servants. He is free from cares and anxieties. The sight of the calm countenance of a contented person gives delight to those who come in contact with him. Such a person is revered by the great Tapaswins and all great men.

COUNTER-THOUGHTS

(PRATIPAKSHA BHAVANA)

Thoughts of worry and thoughts of fear are fearful forces within us. They poison the very sources of life and destroy the harmony, the running efficiency, the vitality and vigour. While the opposite thoughts of cheerfulness, joy and courage heal, soothe, instead of irritating, and immensely augment efficiency and multiply the mental powers. Be always cheerful. Smile. Laugh.

Every thought or emotion or word produces a strong vibration in every cell of the body and leaves a strong impression there. If you know the method of raising an opposite thought or counter-thought, then you can lead a happy harmonious life of peace and power. A thought of love will at once neutralise a thought of hatred. A thought of courage will immediately serve as a powerful antidote against a thought of fear.

When there are diseases, discord, disharmony in the cells of the body owing to influence of vicious thoughts, worry-thoughts, fear-thoughts, hatred-thoughts, jealousy-thoughts, lustful-thoughts you can neutralise the poison or canker in these diseased, morbid cells and establish peace, harmony, health, new vigour and vitality by entertaining sublime, soul-stirring, life-giving, soul-awakening, Sattvic, Divine thoughts by vibrations of OM chanting, by repetition of the different names of the Lord, by Pranayama, Kirtan (singing of the Names of the Lord), study of the Gita and the holy scriptures, by meditation etc.

COURAGE

Courage is bravery, undaunted spirit, fearlessness, intrepidity. It is the quality that enables men to meet dangers without fear.

Courage enlarges your resources but cowardice diminishes them.

Abhayam is courage or fearlessness. In the Sixteenth Chapter of the Gita this virtue comes first. No spiritual progress is possible without courage. Courage is an essential of high character.

There cannot be truth without courage, you cannot do anything in this world without courage. It is the greatest virtue of the mind.

Courage triumphs. Courage succeeds. Courage conquers.

Courage is that quality of mind which enables man to encounter danger, opposition and difficulties with firmness, calmness and intrepidity or without fear or depression of spirits.

A courageous man is cool and calm. At the very time of danger he is extremely serene. He is resolute-minded.

Physical courage and moral courage are necessary to make a man great. Moral courage is a virtue of higher order than physical. It is very ennobling.

Physical courage depends upon bodily strength and intrepidity. Moral courage is that quality which enables one to pursue a course deemed right through which one may incur contempt, disapproval or opprobrium.

True courage is not the brutal force of vulgar heroes, but the firm resolve of virtue and reason. The courage of a soldier in the battle is Rajaso-Tamasic, but the courage of an aspirant or a Sage or a saint is Sattvic. The former is the hardness of the rash and foolish, but the latter is the courage of the wise.

Do not possess Dutch courage, but be really courageous. Dutch courage is a fictitious courage induced by drinking. It evaporates quickly when the influence of alcohol wanes. Courage must become part and parcel of your very nature.

Have the courage of your convictions. Have the courage to act up to or consistently with your views or opinions.

Always pluck up your courage to nerve yourself to something daring.

Courage is the sterner stuff of which heroes are made.

If you have courage and confidence, you can accomplish anything in this world. Courage is the source of all success. Impossible things become possible if you have courage and confidence.

You have strength in proportion to courage. Your ability to perform deeds is in accordance with your courage and confidence.

You may have courage when everything is going right; but it is difficult to have courage in times of panic and danger. The really courageous man is one who knows no fear when danger is on his heels and helps others with a calm attitude of mind.

Bravery, intrepidity, valour, boldness, fortitude, fearlessness, daring, heroism, gallantry, dauntlessness, mettle, pluck—are synonymous with courage.

Cowardice, fear, fright, timidity, pusillanimity, poltroonery are the opposites of courage.

Meditate ceaselessly on the absolutely fearless Atman or the Immortal Soul that dwells in the chambers of your heart. You will become an embodiment of courage.

COURTESY

Courtesy is elegance of manners. It is an act of civility and respect.

Courtesy is elegance or politeness of manners. It is politeness combined with kindness. It is complaisance. It is an act of kindness or favour performed with politeness.

Courtesy is politeness originating in kindliness and exercised habitually. It is courtliness, civility, graciousness. It is a gesture of civility, reverence or respect.

Courtesy denotes an act of kindliness or good breeding.

He who sows courtesy reaps friendship.

Sweet and gracious is that fine sense of courtesy.

Be courteous even in common speech. You will be loved by all.

Courtesy is the sister of charity which keeps love alive and quenches the fire of hatred.

Show courtesy to all. Let it be artless, continuous and uniform. Have courtesy in your heart. Show courtesy in your outward behaviour.

Return a salute joyfully. Salute the person who salutes you with a better salutation. Always salute first to all.

Courtesy sweetens and ennobles life. It makes smooth the road of life, like grace and beauty. It opens the door and allows the stranger into the house. It enlivens the hearts of guests and visitors.

Be pleasant and courteous in your behaviour towards your inferiors and all persons.

Small kindness, small courtesies, small consideration habitually practised in your social intercourse give a great charm to your character.

Courtesy charms at first sight and leads on to great intimacy and friendship.

A man of courtesy is a man of fine and polished manners. All people love him.

Show not scant courtesy at any time to any person. Be liberal in your courtesy.

Urbanity, civility, complaisance, condescension, affability, elegance, courteousness, good breeding are synonymous with courtesy.

DESTINY

Courage is thy birthright but not fear; peace is thy divine heritage but not restlessness. Immortality is thy birthright but not mortality; strength, but not weakness; health but not disease; bliss but not sorrow; knowledge but not ignorance.

Pain, sorrow, ignorance are all illusory; they cannot live. Bliss, joy, knowledge are true; they cannot die.

You are the architect of your own fate. You are the master of your own destiny. You can do and undo things. You sow an action and reap a tendency. You sow a tendency and reap a habit. You sow a habit and reap your character. You sow your character and reap your destiny. Therefore destiny is your own creation. You can undo it if you like. Destiny is a bundle of habits.

Purushartha is right exertion. Purushartha can give you anything. Change your habits. Change the mode of thinking. You can conquer destiny. You are thinking now “I am the body.” Start the spiritual (cross-current) and think “I am the Immortal, diseaseless, sexless, Atman.” Think “I am Akarta (non-doer) and Abhokta (non-enjoyer)." You can conquer death and attain the Immortal seat of supreme splendour.

By virtuous deeds and right thoughts you can disarm destiny. You have a free will to act. By exertion Ratnakar became Valmiki. By exertion, Markandeya conquered death. By exertion, Savitri brought her husband Satyavan back to life. By exertion alone did Uddalaka attain Nirvikalpa Samadhi.

Therefore, apply yourself tenaciously to Atmic enquiry and meditation. Be vigilant and diligent. Kill the thoughts and desires. Overcome tomorrow's evil by today's right exertion. Destroy unholy desires (Asubha Vasanas) through holy desires (Subha Vasanas). Slay unholy thoughts by holy thoughts and gain victory over your destiny.

Do not yield to fatalism. Do not become impotent. Stand up like a lion. Exert and attain independence or Atma Svarajya. There is a vast ocean of knowledge within you. All faculties are latent in you. Unfold them and become a Jivanmukta (liberated soul).

The positive overcomes the negative. This is the immutable law of nature. Purushartha (self-exertion) is a mightier power. Purushartha is the lion or the elephant, Prarabdha (destiny) is the ant or the jackal. God helps those who help themselves. Vashishtha asked Rama to do Purushartha. Fatalism will induce inertia and laziness. Therefore gird up your loins and exert yourself to the utmost.

May you all attain Self-realisation or Brahma-Jnana in this very birth! May you all live immersed in an ocean of bliss in an illumined state! May you all shine as liberated sages!

DETERMINATION

Determination is resolution, fixedness of purpose, decision of character. It is the act of deciding. It is firmness.

It is a firm resolve as a determination to conquer.

Determination is a manly trait.

Determination is the mental habit of setting upon some line of action with a fixed purpose to adhere to it. It is adherence to aims and purposes, resoluteness as a 'man of determination.'

If you have fiery determination only, you can attain success in all undertakings, in Self-realisation, too.

Decision is literally a cutting off, or cutting short, of debate or questioning.

Determination is a settling of the limits within which one must act.

Resolve is a separating of the essential act from all that might cause doubt or hesitation. It always refers to a single act.

Resolution may have the same meaning, or it may refer to the habit of mind which readily forms and adheres to resolves.

Decision or determination especially marks the beginning of action.

Resolution holds one to the end.

Doubt, faltering, fickleness, hesitation, indecision, instability, irresolution, vacillation, wavering are the opposite terms.

A man of strong, pure, irresistible will can have fiery determination.

Strengthen your will and cultivate determination.

DIGNITY

Dignity is elevation of mind or character. It is grandeur of mien. It is degree of excellence.

Dignity is grave and noble bearing. It is impressiveness of character or manner. It is serenity of demeanour.

Dignity is the state or quality calculated to inspire awe, respect or reverence. It is stateliness.

Against lies, calumnies, etc., dignity is the only weapon.

Dignity of position adds to dignity of character as well as dignity of carriage.

The statesman's dignity is innate.

Dignity is the state or quality of being excellent, worthy or honourable, as the dignity of labour.

If you will only call a headache a cephalalgia, it acquires dignity at once, and the patient becomes rather proud of it!

To stand upon one's dignity is to have or assume an exalted idea of one's own importance, especially if offended.

DISCRETION

Discretion is prudence. It is liberty to act at pleasure.

Discretion is the ability and tendency to choose or act with prudence. It is instinctive perception of what is wise or proper, united with caution. It is sagacity. It is the habit of wise judgement, especially in relation to one's own conduct.

Discretion is liberty of action and decision, as in a particular matter. It is freedom in the exercise of judgement; also action resulting from such liberty or freedom; as "the matter is subject to your discretion."

A man of discretion is wise in avoiding errors or evil or in selecting the best means to accomplish a purpose. He has good discernment. He is judicious.

Discretion is that discernment which enables a person to judge critically of what is correct and proper united with caution.

It is nice discernment and judgment, directed by circumspection and primarily regarding one's own conduct.

Discretion is the victor of the war, valour the pupil.

Discretion is the liberty or power of acting without other control than one's own judgment; as "the management of affairs was left to the discretion of the president."

There are many shining qualities in the mind; but none so useful as discretion.

Discretion in speech is more than eloquence.

Discretion is the salt of life. It preserves life.

Discretion is the perfection of reason. It is your guide in all your duties of life.

Discretion is the better part of valour.

Discretion is found only in men of sound sense and good understanding.

DISCRIMINATION

Discrimination or Viveka is the faculty or power of the Sattvic mind to distinguish between the Real and the unreal, the Permanent and the impermanent, Atma and Anatma.

Discrimination dawns through the grace of the Lord, in a man who has done virtuous actions in his previous births as offerings unto the Lord without expectation of fruits and without egoism.

Viveka or discrimination is strengthened by study of scriptures and Satsanga.

If you have discrimination, surely you will have lasting dispassion.

The edifice of wisdom is built up on the strong foundation of discrimination.

Brahman or the Absolute alone is the Real, Imperishable thing. All things other than Brahman are transient and perishable.

DISPASSION

Dispassion is Vairagya. Dispassion is indifference to sensual enjoyments herein and hereafter. Dispassion is non-attachment to sensual objects.

This is an important requisite for attaining God-realisation.

Man is bound to this world, through Raga or passion or attachment. He is liberated through Vairagya.

Vairagya born of discrimination between the Real and the unreal only will be of a lasting nature. Such a Vairagya alone will help you to attain spiritual progress and illumination. Karana-Vairagya due to loss of property or death of your son will be temporary. It will be of no use to you. It is volatile like ammonia.

Look into the defects of sensual life or sensual pleasure. You will develop dispassion.

Sensual pleasure is momentary, deceptive, illusory and imaginary.

Enjoyment cannot bring about satisfaction of a desire; on the contrary it makes the mind more restless after enjoyment through intense craving.

Sensual pleasure is the cause for birth and death. It is an enemy of devotion, wisdom and peace.

DUTY

Duty is what one is bound by any obligation to do.

Do your duty and leave unto the Lord the rest.

He who knows his duty but does not practise it, is the worst man in this world.

You are not in this world to do what you wish. You must be willing to do that which is your duty.

Regard all duties as sacred. Do your duty unselfishly. Then duty ceases to be irksome. It becomes joyful.

Do your duty in your shop, in your kitchen, in the office, in the school, in the home, very faithfully. Apply your whole heart even in doing little things such as arranging of your papers, cleaning your room, the sorting of your clothes, etc.

Your daily duties are a part of your religious life.

Duty is carrying on promptly and faithfully the affairs now before you.

Duty is the sublimest of ideas, for it implies the idea of God, of the soul, of freedom, of responsibility, of immortality.

The worthy fulfilment of the duties of every stage of life brings honour to man.

Be exact in doing even your little duties. You will derive much joy and happiness.

There is no mean work. Work is worship. All actions are sacred. Performance of duty is practice of religion.

Duty performed is a moral tonic. It strengthens the mind and the heart.

Human happiness and moral duty are inseparably connected.

Do as you would be done by. Do unto others as you wish others do unto you. This is the great moral law.

You are not born to solve the problems of the universe.You are born to find out what you have to do.

This span of life is given to you for lofty duties, not for selfishness, not to be spent worthlessly in idle gossiping, eating, drinking and sleeping, but to improve yourself, to cultivate virtues, serve humanity selflessly and to attain God-realisation.

EARNESTNESS

Earnestness is the state of being earnest. It is enthusiasm tempered by reason.

An earnest man is determined. He is eager to obtain. He is intent, sincere and serious. He shows strong desire. He is ardent in the pursuit of an object. He gives his whole heart to the work on hand.

Do you wish to master any science or accomplishment? Then give yourself to it. Be sincere and earnest. You will attain sanguine success.

Far more than mere talents, enthusiasm and earnestness in work carry the day.

It will be found everywhere that the men who have attained success in business or anything have been the men who have earnestly given themselves to it.

An earnest man finds means. He creates means.

Earnestness strengthens weakness, braves dangers, overcomes pain, sustains hope, lightens difficulties, lessens the sense of weariness in overcoming them, gives endurance.

A man may be the cleverest of men; he may be brilliant. But, without earnestness no one is ever great or does really great things.

You cannot be earnest about anything which does not naturally and strongly engage your thoughts.

Earnestness is the devotion of all the faculties. It gives patience. It is the cause of patience. It gives zeal and enthusiasm.

Earnestness is the best source of mental power. It gives intellect.

There is no substitute for thorough-going, ardent, sincere, earnestness.

An earnest man is serious in purpose. He is zealous and determined especially in matters of moral and religious import, spirit and speech.

There must be a great and earnest soul behind a great cause.

When a man is earnest in his speech, attempt and action, we say: “Rama’s speech is earnest speech; Krishna’s attempt is earnest endeavour. Siva is an earnest doctor.”

ELEGANCE

Elegance is the state or quality of being elegant. It is the beauty of propriety. It is refinement, polish or gracefulness. That which is nice and pleasing to good taste is elegance.

When the mind loses its feeling for elegance, it becomes corrupt.

Elegance is something more than a freedom from awkwardness. It implies a precision, a polish, a sparkling and brilliance.

Fig. 7.1 *The Stronger your Awareness of your Inner Body,*
the Easier it will be for others present to pick up this Sense.

If you guide those present, this will greatly enhance your healing session. Sit or stand facing your student. Any time you want him or her to focus on a particular point of the body, ask them to touch it with their hands. For example, "Now place your hands on your navel", while you do the same thing yourself. As soon as you feel the Chi there, you instruct them to focus on the navel themselves. This way you are actually helping them to deepen their bodily awareness. The stronger your own awareness of your inner body, the easier it will be for the others present to pick it up. This means that if you are treating some part of another person's body, or if you see that the person is not aware of any energy in some part of the body, you can help by focusing your awareness on this particular part of your own body.

Chi Kung Diagnosis: Hand Scanning

Hand scanning is a simple and effective diagnostic tool of External Chi Healing. It involves passing your palm over the body of your student from one inch to one foot above the surface of the skin and being aware of the energetic state of the various bodily areas. What one senses is described as the electromagnetic field, the aura or the energy body.

General Variations in the Energy Field

The variations you may sense with scanning that have diagnostic significance are:

Though elegance is reckoned among the smaller and secondary morals, yet it is of no mean importance in the regulation of life. It greatly decreases the evils of vice.

Elegance is choice or delicate structure, form or action; beauty resulting from a combination of fine qualities; as elegance of proportion, motion, style or manner.

A clear and sharp-cut enunciation is one of the elegancies of speech.

We say: "Among the Indians, we find profound and elegant scholars."

An elegant thing is marked by grace or symmetry and refinement. It exhibits faultless taste and delicacy of finish. It possesses a fine sense of beauty, purity or fitness. We say: "This is an elegant apartment." We say: "Rama's argument was elegant." It is marked by completeness, simplicity. It is appropriate.

'Elegant' refers to that assemblage of qualities which makes anything choice to persons of culture and refinement. It refers to the lighter, finer elements of beauty in form or motion.

A dress may be elegant, but such expressions as "an elegant field of corn" "an elegant ride" or "an elegant time" are glaring lexical improprieties.

Exquisite denotes the utmost perfection of the elegant in minute details. We speak of an elegant garment, an exquisite lace. Exquisite is also applied to intense keenness of any feeling as exquisite delight, exquisite pain.

Elegance is beauty resulting from perfect propriety or from the absence of anything calculated to produce a disagreeable sensation, said of manners, language, style, form, architecture and the like; as elegance of dress.

That which pleases by its nicety, symmetry, purity or beauty is elegant.

Polished, polite, refined, graceful, pleasing to good taste are elegant manners.

Polished, pure, rich in expressions, correct in arrangement is elegant style or composition.

Symmetrical, regular, well-formed in part, proportions and distribution is an elegant structure.

Rich, costly and ornamented is elegant furniture or equipage.

Nice, sensible to beauty, discriminating beauty from deformity or imperfection, is an elegant taste.

EMULATION

Emulation is an attempt to equal or excel. It is a healthy competition. It is a desire for like excellence with another.

It is a noble passion. It is striving to excel, not by depressing others, but by raising oneself. It keeps within the terms of honour and makes the contest for glory just and generous.

Without emulation nothing great or excellent can be done. Emulation is laudable ambition. It urges you to advance and make improvement. It admires and strives to imitate great actions. But envy is only moved to malice.

Emulation is the shadow of aspiration. It looks out for merits so that it may exalt itself by a victory.

Through emulation one exalts oneself to something that is praiseworthy. He exerts, strives and struggles. He does not have a cut-throat competition with others.

He does not envy the merit of another, he improves his own talents, faculties and capacities. He does not boast of himself; and he does not deride others.

He who emulates does not depress his competitors by any dishonest or unworthy methods. He endeavours to raise himself only by excelling him. By virtuous emulation, the spirit of a man is exalted. He is ever diligent, vigilant and persevering. He always soars higher and higher.

He keeps before his mind the examples of illustrious persons and strives to follow them and reaches their level quickly. He forms great designs and executes them.

But the heart of an envious man is gall and bitter. His heart burns at the success and prosperity of others. He is restless. His heart is filled with hatred and malice. He does mischief to others. He harms and ruins others. He depreciates those who excel him.

In all the pursuits of active and speculative life, emulation is the most powerful spring of the efforts and improvements of mankind.

Emulation regards the abstract, competition the concrete. We speak of competition in business, emulation in scholarship, rivalry in love, politics, etc.; emulation of excellence, success, achievement; competition for a prize; rivalry between persons or nations. Competition may be friendly; rivalry is commonly hostile. Opposition is becoming a frequent substitute for competition in business language. It implies that the competitor is an opponent and hinderer.

Carelessness, indifference, false satisfaction are the opposites of emulation.

ENDURANCE

(TITIKSHA)

Endurance is the state of enduring or bearing. It is a suffering patiently without sinking or yielding to the pressure, without resistance.

Endurance is the capacity or power to endure without opposition. It is ability to suffer pain, distress, hardship or any very, prolonged stress without succumbing or murmuring or complaining, lamenting or repining. It is patient fortitude. It is the ability to bear and continue in spite of destructive forces.

To endure is to bear with strain and resistance with conscious power. To brook is quietly to put up with provocation or insult.

He who endures conquers. Through endurance, will-power and patience are developed. Through endurance evils and difficulties are overcome.

Your strength often increases in proportion to the obstacles imposed upon you. Endure them bravely.

Difficulties and troubles, adversities and calamities have often built the character of men.

The palm-tree grows best beneath a ponderous weight, and even so the character of man.

The greater the difficulty, the more glory in surmounting it. Skilful pilots become famous from storms and tempests.

Through endurance you exhibit your divine grandeur and make alliance with God.

EQUANIMITY

Equanimity is equality or evenness of mind or temper. It is balanced mind in pleasure and pain, success and failure, honour and dishonour, censure and praise.

Equanimity is composure of spirit, especially calmness and steadiness of mind, amidst trying circumstances.

The excellence of equanimity is beyond all praise. That man who is endowed with this virtue is not dejected in adversity, nor elated in prosperity. He is affable to others and contented in himself.

He who is endowed with equanimity has poise at all times under all conditions of life. He bears losses with equanimity.

A Jeevanmukta has always an evenness of mind or equanimity or poise. He has a perfect, unshakable balance of mind, rooted in insight, intuition or Atman.

In this world of pairs of opposites, man is tossed about hither and thither by various waves of emotion. Now he gets gain, successs, honour, praise. The next moment, he gets failure, loss dishonour, censure and disappointment. He who has evenness of mind or poise can pull on in this world joyfully and peacefully.

Root yourself in your own unchanging, all-blissful Atman within, by disciplining the mind and the senses. Then alone will you rest peacefully for ever. No worldly wave can upset you. You will rest silently in the bed rock of your own innermost Self within, which is an ocean of peace.

Samatvam or equanimity is Yoga. To attain this state it needs constant vigilance, perseverance, patience and perfect discipline of body, mind and senses. This is not a day's or week's or a month's effort.

Constantly think of the "Samam Brahman" which is seated equally in all beings. Gradually you will develop equanimity.

Eradicate desires, cravings, attachments, likes and dislikes. Cultivate discrimination, serenity, dispassion, self-restraint, self-control, self-denial. You will be slowly established in equanimity.

FAITH

Faith is belief in the truth of revealed religion. It is confidence and trust in God. It is confidence in one's own Self. It is belief in the statements, utterances and teachings of one's Guru or Preceptor or saints. It is belief in religious scriptures.

Faith is a firm conviction of the truth of what is declared by another by way either of testimony or authority without any other evidence.

Faith is that personal attitude by which divine revelation is subjectively appropriated. It does not originate from logical processes, but from an immediate inner experience.

Men with no assets but tremendous faith in themselves have accomplished wonders.

Have perfect faith in God. Surrender your entire being unto Him. He will take care of you. All fears and tribulations will vanish in toto. You can ever remain at ease.

Faith should not be forced. Trying to compel religious belief leads to unbelief.

Faith in God elevates the soul, purifies the heart and emotions and leads to God-realisation.

Faith is the soul of religion. It creates new hopes and awakens immortality.

Faith is the eye that sees the Lord, and the hand that clings to Him.

Faith is power. Faith is strength. Faith is abundant energy.

He who has faith is strong. He who doubts is weak. Doubt cramps energy. Strong faith precedes great actions.

Much divine knowledge is lost to you through lack of faith.

Faith illumines the spiritual path, builds a bridge across the gulf of death and takes the aspirant to the other shore of fearlessness and immortality.

We give credence to a report, assent to a proposition or to a proposal. Belief is stronger than credence. Conviction is a belief established by argument or evidence.

Assurance is belief beyond the reach of argument.

Faith is a union of belief and trust. Faith is chiefly personal. Belief may be quite impersonal. We speak of belief in a proposition, faith in a promise, because the promise emanates from a person.

Confidence is a firm dependence upon a statement as true, or upon a person as worthy. We have reliance upon the uniformity of nature. We have trust or faith in God.

FIDELITY

Fidelity is faithful and careful performance of duty, or performance of obligations. It is faithfulness to a husband or wife. It is honesty. It is firm adherence.

Fidelity is hearty allegiance to those to whom one is bound in affection or honour. It is loyalty, devotion, as the fidelity of an officer, matrimonial fidelity, fidelity to a father or friend, the fidelity of subjects to their king, the fidelity of a servant to his master.

Fidelity finds its reward and its strength in exalted purpose.

Fidelity is nine-tenths of success in business.

Fidelity is the friend of justice.

Nothing is more noble, nothing more venerable than fidelity. It is a fundamental virtue of mind.

Fidelity is strict adherence to truth or fact; reliability, veracity, honesty; as the fidelity of a report or a witness, the fidelity of a portrait.

Allegiance, constancy, devotion, faith, faithfulness, honesty, integrity, loyalty, truth, truthfulness, are synonymous terms.

Disloyalty, infidelity, treachery, treason are the opposites of fidelity.

Be constant as the Pole Star. Be faithful and devoted.

FIRMNESS

Firmness is steadiness, resoluteness, determination, constancy. We speak of the firmness of foundation, firmness of step, firmness of faith, firmness of purpose or resolution, firmness of mind or soul.

A man of firmness is not easily moved or disturbed. He is unshaken by anything. He is courageous.

Cleverness, talents, faculties, abilities, capacities, eloquence, elegant manners, winsome ways, graceful speech are nothing unless they are protected by the shield of firmness.

Firmness enables a man to overcome obstacles and difficulties very easily. A man of firmness always attains success in all undertakings.

You must have firmness both in suffering and exertion. Then alone will you attain greatness and victory.

Firmness is indeed a noble quality, but it must be guided by knowledge. Otherwise it becomes rashness or obstinacy.

Firmness of purpose is the best instrument for success. It is one of the most necessary sinews of character.

Firmness is then only a virtue when it accompanies the most perfect wisdom.

Firmness is the faculty that gives stability, persistency and obstinacy.

Firmness belongs to the wise act; constancy to the affection and principles—the former prevents us from yielding and the latter from fluctuating.

FORBEARANCE

Forbearance is exercise of patience. Forbearance is command of temper or clemency. It is a great divine virtue.

Forbearance is patient endurance or toleration of offences. It is lenity. It is restraint of passions. Forbearance is refraining or abstaining from, avoiding voluntarily. It is a refraining from feelings of resentment or measures taken in retaliation.

Forbearance is a mysterious mixture of mercy, sympathy, pity, compassion, patience, endurance, forgiveness and strong will.

He who practices forbearance keeps himself in check. He practises self-restraint or self-control and forgiveness. He bears injuries, insults, annoyance and vexatious mocking, patiently, prayerfully and with self-control and thus develops a strong will-power.

Cover the blemishes, faults, weaknesses of others. Excuse their failings. Bury their weaknesses in silence. Proclaim their virtues from the house-top.

Find out occasions to forbear. Pity and forgive weak persons. Cultivate forbearance till your heart yields a fine crop of it.

Lord Jesus and Lord Buddha were embodiments of forbearance. Glory to these divine personages. Follow their example and become divine.

O Man! Forbear! Have patience even under greatest provocation. You will reap a rich harvest of peace and bliss.

FORGIVENESS

(KSHAMA)

Forgiveness is pardoning. Forgiveness is to overlook an offence or debt. It is disposition or inclination to pardon or excuse.

A man who is endowed with forgiveness is merciful and compassionate.

To err is human; to forgive divine.

Pretence of forgiveness is common. Real forgiveness is rare.

If you practise forgiveness, you will become strong and noble. You can control anger easily.

Forgiveness saves the expense of anger, the cost of hatred, the waste of spirits.

Forgiveness ought to be like a cancelled note—torn in two and burnt up, so that it never can be shown against one.

He who practises forgiveness ceases to cherish displeasure or resentment towards a man who has injured him.

Kshama or forgiveness is an antidote to anger.

"Forgive" points to inward feeling and supposes alienated friendship. When we ask for forgiveness, we primarily seek the removal of anger.

"Pardon" looks more to outward things or consequences and is often applied to trifling matters, as when we beg pardon for interrupting. The magistrate grants a pardon, and not forgiveness.

FORTITUDE

I

Fortitude is the mental power of endurance. It is firmness in meeting danger. It is strength, power of resistance or attack.

Fortitude comes from Latin *fortitudo*, from *fortis*—strong, powerful.

Fortitude is strength or firmness of mind to endure pain and adversity patiently, without murmuring, depression or despondency, or to encounter danger undismayed with coolness and courage. It is patient and constant courage.

Fortitude is power to resist or attack.

Fortitude is passive courage or still courage, enduring courage. It is that quality which is able not merely to endure pain, or trial but steadily to confront dangers that can be actively opposed or against which one has no adequate defence. It takes courage to charge a battery, fortitude to stand still under an enemy's fire. Resolution is of the mind. Endurance is partly physical. It requires resolution to resist temptation, endurance to resist hunger and cold.

Active fortitude is demanded when evils are to be encountered and overcome. It comprehends resolution or constancy and intrepidity or courage. Passive fortitude is demanded when evils are to be met and endured. It includes patience, humility, meekness etc.

In itself it is an essential virtue. It is a guard to every other virtue.

This is a world of pain, misery, sorrow, perils, misfortunes, want, injury and disease. Every man has his share of pain and trouble. Cowards crouch beneath their load and men of fortitude bear without repining.

He who fights with the lower nature and overcomes, that man is adorned with the best virtue—fortitude.

Patience, courage, endurance, heroism, resolution and presence of mind are the ingredients of fortitude.

Fortitude will sustain you through all perils, adversities, misfortunes. Just as the dashing of the waves cannot disturb a rock, so also all the tribulations of mundane life will not disturb you.

Fortify thy mind with fortitude, courage and patience. You can surmount all the troubles of this mundane life boldly and can remain ever calm and peaceful. In the hour of danger you will not be embarrassed and confounded. In the days of misfortune you will not sink with despair, or despondency.

Fortitude will sustain you and the steadiness of your mind will bear you out. You will emerge with victory and joy.

Prahlada, Sita, Damayanti, Nalayini and Savitri were all embodiments of fortitude.

II

Fortitude is Dhriti. Fortitude is mental power of endurance. It is firmness in meeting danger. It is strength, power of resistance or passive negative aspects of attack.

The birth of a man is due to his mixed Karmas, mixture of good and evil. Every man will have to meet dangers, calamities adversities, catastrophies, want, pain, injury at some period of his life. He who is endowed with fortitude will bear them calmly with great presence of mind and tide over them with a smiling face.

Fortitude is a sweet mysterious spiritual mixture of courage, calmness, patience, presence of mind and endurance. It is a virtue born of Sattva. It gives great strength of mind to Sadhakas, who tread the path of Truth and even to those who live in the world and tread the path of Pravritti.

That Sadhaka who is not endowed with fortitude leaves his Sadhana during times of peril, privation and sickness. He faints, creaks and loses heart. But fortitude of a man sustains him through all perils, calamities, privations and sickness. It was fortitude that sustained Lord Rama and Sita, Nala and Damayanti, Yudhishthira and his brothers during their life in the forest when they were in great distress. Sri Harishchandra, Jesus Christ, Rana Pratap, Abdul Baba are examples of heroes who possessed immense fortitude.

Fortitude is a friend in need. It is a nursing mother. It is a mental tonic and panacea. It is a shield and an armour to protect one from hunger, thirst, heat, cold. It is an unfailing injection to instil inner strength during times of threatening collapse and heart failure. It is a potent weapon to combat against trying conditions of life and unfavourable circumstances.

The man of fortitude stands firm like the Himalayas during adversities. He keeps the balance of mind under all conditions of life. He is not shaken by heavy sorrows. Just as a rock on the sea-shore stands firm and is not affected by the dashing of waves, so also he stands firm even amidst storms and vicissitudes of this dire Samsara.

Just as the man in the battlefield protects his nose, eyes and other parts through special contrivances from the disastrous effect of explosive bombs, so also the Sadhaka and the wise man protects himself from the explosive gases of worldly adversities through fortitude and comes out victorious.

But the timid, weak man with the dastardly spirit who lacks in fortitude, trembles in the hour of danger shrinks, faints and falls down in utter shame. He sinks in despair. He is bewildered and confused. He does not know what to do. He is like the reed

Temperature

Heat generally indicates excess, while cold indicates deficiency. However, some areas of the body are naturally warmer or colder than others. This is described below under "Hand Scanning the Internal Organs."

Thickness

A feeling of thickness over the area would indicate excess, while thinness may indicate deficiency.

Wind

You may feel sensations of wind leaving the body at various places. This may indicate internal wind at a given location, or it may point to an area of the body that is "leaking energy" and needs to be ‘patched’ or ‘sealed’. It may also be a positive sign that you are driving wind out of the body.

Peaks and Valleys

Peaks in the energy field will feel like mountains or hills in the aural landscape. They may actually push your hand away. Valleys feel like depressions or energy vortexes drawing you in. They may also feel empty, like a hole or pit. Peaks indicate excess or stagnation, while valleys indicate deficiency.

Tingling

Accumulations of sick Chi may cause your hand to tingle, feel prickly, throb, or even hurt. These are excesses of energy and upon inquiry, the student may complain of pain in this area.

Hand Scanning the Internal Organs

Each Organ Emits a Different Aura

Each organ emits a different kind of force or aura through the skin. By passing a hand one or two inches above the skin, you can feel different sensations that reflect the condition or state of the internal organs. You need to develop the sensitivity to receive and identify the vibration or frequency of each organ. Practicing the Cosmic Chi Kung Meditations will help develop such sensitivity.

Liver and Gall Bladder Scanning

Healthy liver and gall bladder energy feels warm.

Negative Emotions: When you pass your hand over the liver, under the right side of the rib cage, you will feel a charged energy come up to your hand. This is a sign of anger in the liver.

that is shaken even by the least puff of breeze. He loses presence of mind. Fear, faintheartedness, impotency overpower him. He hopelessly meets with failure and sorrow. He succumbs and yields during times of adversity and misfortunes.

Develop fortitude gradually and stand firm like that yonder Meru or Himavan. Cultivate this virtue again and again patiently.

Fortitude shows power of character. Just as to a man of high office his authority is his strength, to a noble man his pedigree is his strength, to a great leader his status is his strength and to a wealthy man his money is his strength, even so to a man of character fortitude is his strength. It is what sustains him. It denotes self-confidence and self-reliance. Where there is fortitude there discouragement and pessimism dare not approach. Fortitude is therefore the only real lasting strength, for high office, birth, leadership, money all pass away. Character is lasting wealth, fortitude is a lasting power.

May you all attain success in worldly life and God-realisation through fortitude.

FRIENDSHIP

Friendship is attachment for mutual esteem. It is cordiality. It is intimate acquaintance.

Friendship is the mutual liking, esteem or regard cherished by kindred minds, as the basis of the mutual interchange of kind offices. In friendship there is congeniality of sentiment; there is close intimacy or acquaintance leading to sympathy or helpfulness.

Friendship is attachment to a person, proceeding from intimate acquaintance and a reciprocity of kind office or from a favourable opinion of his amiable and respectable qualities.

Man is a social animal. He wants company and talk. He desires to have friends. He cannot live well without friends.

Two persons cannot keep friendship for a long time if they cannot forgive each others' little defects or weaknesses or shortcomings.

Friendship with the upright and sincere men is advantageous.

Friendship with men of vanity, insincerity, double-dealing and crookedness is injurious.

Be slow to make friendship with anybody. Once you have made friendship with some one, be firm and constant.

Sincere friends are rare in this world. You will find selfish friends in abundance. Your only sincere, immortal friend is the Indweller of your heart, the Antaryamin, the Inner Ruler.

You will find the friendship of many people as mere outward show. It is like the harlot's tears.

False friendship decays soon, but true friendship gives new life and animation.

A friend in need is a friend indeed. Be more prompt to go to a friend in adversity than in prosperity.

True friendship is infinite and immortal.

Friendship is a fragile thing and requires as much care in handling as any other fragile thing. Be careful. Let it grow.

Your friend should be one in whose understanding, virtue and opinion you can safely confide.

Be not the tenth friend of him who had nine before and lost them.

A good virtuous man will be your best friend. Make friendship with him at once. Retain his friendship till the end of your life. You will be immensely benefited by his counsels and friendship. He will help you, guide you and serve you.

A true, sincere friend will advise you justly, assist you readily at all times, will defend you courageously when you are in difficulties, and will continue to be your friend unchangeably.

Do not make friendship hastily. If you make friendship with anybody, hold fast to him. Do not be always changing your acquaintances and friends.

True friendship is one of the sweetest joys of life.

Friendship between mean, diplomatic, greedy and crooked people will not last long.

The best of friendship is found not only in prosperity but in adversity. A true friend loves at all times.

There are true, lasting affection, harmony and goodwill between sincere friends.

Friendship augments joy and happiness and decreases misery by the doubling of our joy and the dividing of our grief.

Friendship is a deep, quiet, enduring affection, founded upon mutual respect and esteem. Friendship is always mutual. There is never unreciprocated or unrequited friendship.

Friendliness is a quality of friendly feeling without the deep and settled attachment implied in the state of friendship.

Affection is purely natural. Friendship is a growth. Friendship implies some degree of equality.

Comity is mutual, kindly courtesy, with care of each other's right.

Amity is a friendly feeling and relation, not necessarily implying special friendliness as the comity of nations or amity between neighbouring countries.

Friendship is more intellectual and less emotional than love. It is easier to give reasons for friendship than for love. Friendship is more calm and quiet, love more fervent. Love often rises to intensest form. We cannot speak of the passion of friendship.

A friend is one who is attached to another by affection or who entertains for another sentiments of esteem and respect which lead him to desire his company and to seek to promote his happiness and prosperity.

There can be no friendship without confidence and no confidence without integrity.

FRUGALITY

Frugality is thrift or economy with efficiency.

Frugality is prudent economy in the case of money or goods or provisions of any kind. It is good husbandry or housewifery.

Frugality makes a poor man rich. By sowing frugality, you reap liberty, a golden harvest.

Be frugal, but not niggardly or parsimonious or miserly.

Frugality is a virtue but niggardliness or miserliness is a vice.

The way to wealth depends on industry and frugality. Waste neither time nor money. Make the best use of both.

Without frugality, none can become rich and with it, few would be poor.

Abandon the superfluities or luxuries of life. Be simple. Have the motto: “Simple or plain living and high thinking.” You will be free from want. You will enjoy infinite happiness.

Frugality is the daughter of prudence, the sister of temperance and the parent of liberty.

He who is extravagant will soon become poor. He will become dependent. He will be corrupted.

Economy is a wise and careful administration of the means at one's disposal.

Miserliness is the denying oneself and others the ordinary comforts or even necessaries of life for the sake of mere hoarding money.

Economy manages, frugality saves, providence plans, thrift at once earns and saves with a view to wholesome expenditure at fitting time.

Extravagance, lavishness and prodigality are the opposites of frugality.

GENEROSITY

Generosity is nobleness or liberality of nature. The essence of generosity is self-sacrifice. A generous man is bountiful.

Generosity is a disposition to give liberally or to bestow favours heartily. It is the act or practice of giving freely and kindly. It is beneficence or munificence. A generous man has a large or magnanimous heart. His charity is overflowing.

A generous man is endowed with a noble disposition. He is most pliant and courteous in his behaviour to his inferiors.

Generosity is the accompaniment of high birth. A generous man always gives and gives. His heart is filled with sympathy. Sympathy and benevolence are the attendants of generosity.

Generosity during life is different from generosity at the time of death. The former proceeds from real liberality and benevolence, the latter from pride or fear.

Liberality, munificence, magnanimity, beneficence, bounteousness are synonymous with generosity.

Generous refers to the self-sacrificing heartiness of the giver, liberal to the amount of gift. One is generous by a kindness of heart that will rejoice in the welfare rather than in the punishment of the offender. A child may show himself generous in the gift of an apple; a millionaire makes a liberal donation. A munificent gift is vast in amount whatever the motive of its bestower may be. 'Disinterested' suggests the thought of one's own self-denial. One is magnanimous by a greatness of soul that rises above injury or insult.

Ignoble, illiberal, mean, miserly, parsimonious, petty, stingy nature is the opposite of generous nature.

GENTLENESS

Gentleness is the state or quality of being mild and refined in manners and mild in disposition.

Gentleness is tenderness of feeling. It is love and consideration. It is sympathy.

Gentleness is softness or sweetness of disposition. It is mildness. It is docility. It is absence of roughness.

A man of gentleness is amiable, soothing and courteous. He is polite in manners. He is free from rudeness and harshness. He is sweet and soft.

Gentleness corrects whatever is offensive in your manners.

If one is gentle, it does not mean, he is weak and inefficient. Only the strong can be really gentle. Nothing is so strong as gentleness. Rudeness or harshness is sign of weakness, ignorance, impoliteness and inexperience.

Gentleness is a power.

Gentle describes the natural disposition; tame, that which is subdued by training; mild implies a temper which is, by nature, not easily provoked; meek, a spirit which has been schooled to mildness by discipline or suffering.

GOODNESS

Supreme goodness is God.

Goodness is virtue, excellence, benevolence.

Goodness is the state or quality of being good in any sense of that word especially kindness, benevolence, morality, virtue. It is an act or expression showing goodness. It is an act of benevolence, compassion or mercy.

If you do good to humanity, you approach nearly to the gods. “Be good; and do good.” The whole ethics and right conduct are contained in this. If you practise this, you will soon attain God-realisation.

A good man always lives with God. He lives in God. He has a divinity within him.

A good man who does good actions attains fame and longevity.

A good deed is never lost. It purifies the heart and leads to the descent of divine light and dawn of divine grace.

He who sows courtesy reaps friendship. He who plants kindness, reaps love.

Goodness is love in action. It is noble to be good.

Goodness is the greatest virtue. Every good deed is a grain of seed for immortality or eternal life. Promote the welfare of the whole world. Work for the solidarity of the world.

Do all the good you can in all the ways you can, to all people you can, in every place you can, at all the times you can, with all the zeal, strength, love and heart and interest you can, as long as ever you can.

Return good for evil. It is the sign of a real man. Love begets love, hatred begets hatred.

Doing good and bringing happiness to others bring goodness and happiness to you.

Good is the conquest over evil. It is not the absence of evil.

Goodness makes life a blessing. Goodness will bring sure success and prosperity in life.

To do good is human. To be good is divine.

Little self-denial, honest service, little words of cheer, encouragement, sympathy and kindness, little acts of kindness, little virtuous deeds, little silent victories over temptations—these will pave a long way to the attainment of eternal bliss, perennial joy, everlasting peace and immortality.

Nations and peoples do not obey the laws of goodness. Therefore, the present world is beset with evils of various sorts.

The law of cause and effect is inexorable and unrelenting. You reap a harvest of suffering, poverty, pain and sorrow, beacuse you have sown the seeds of evil in the past. You reap a harvest of plenty and bliss, owing to your sowing the seeds of good. Try to understand this law. You will then begin to sow only seeds of good.

Entertain good, sublime, divine thoughts. Shut your mind from evil thoughts just as you shut your doors against the approach of enemies, thieves and dacoits. Always perform good actions. Evil cannot enter your mind now.

Cultivate good habits. Goodness is a habit. Goodness of nature is an inclination. Without goodness man is a brute or a vermin. He is a mischievous, wretched, despicable thing on this earth. He is a burden on this earth.

Even a little good thinking and a little doing good are highly beneficent. It will lead to eternal bliss. Then, why not try a little good thinking and good doing?

HINTS ON DEVELOPING GOODNESS, PURITY AND TRUTHFULNESS

1. The noble soul who always does good to the world and entertains sublime divine thoughts is a blessing to the world at large.

2. A person of good deeds and good, pleasant, sweet speech has no enemy. If you really want spiritual growth and salvation, do good to those men who attempt to poison or hurt you.

3. Purity leads to wisdom and immortality. Purity is of two kinds, internal or mental and external or physical. Mental purity is more important. Physical purity is also needed. By the establishment of internal, mental purity, cheerfulness of mind, one-pointed mind, conquest of Indriyas and fitness for realisation of the Self are obtained.

4. Purity is the best jewel of a Yogi. It is the best and greatest treasure of a sage. It is the best wealth of a devotee.

5. Practice of compassion, charitable acts, kind services purifies and softens the heart, turns the heart-lotus upwards and prepares the aspirant for the reception of the Divine light.

6. Japa, Kirtan, meditation, charity, Pranayama can burn all sins and purify the heart quickly.

7. Truth is the highest wisdom. Truth stands even if there is no public support. Truth is eternal. Truth reigns supreme. Those who are truthful and pure, do not die. Those who are untruthful and lustful are as if dead already.

8. You must have a pure mind if you want to realise the Self. Unless the mind is set free, and casts away all desires, cravings, worries, delusion, pride, lust, attachment, likes and dislikes, it cannot enter into the domain of Supreme Peace and unalloyed felicity or the Immortal Abode.

9. Mind is compared to a garden. Just as you can cultivate good flowers and fruits in a garden by ploughing and manuring

the land and removing the weeds and thorns and the watering plants and trees so also you can cultivate the flower of devotion in the garden of your heart by removing the impurities of the mind such as lust, anger, greed, delusion, pride, etc., and watering it with divine thoughts. Weeds and thorns grow in the rainy season, disappear in summer; but their seeds remain underneath the ground. As soon as there is shower, the seeds again germinate and sprout out. Even so the Vrittis or modification of the mind manifest on the surface of the conscious mind, then disappear and assume a subtle seed-state, the form of Samskaras, and again become Vrittis either through internal or external stimulus. When the garden is clean, when there are no weeds and thorns you can get good fruits. So also when the heart and the mind are pure, you can have the fruit of good deep meditation. Therefore, cleanse the mind of its impurities first.

10. If you do not clean a plate daily, it will lose its lustre. It is the same with the mind too. The mind becomes impure if it is not kept clean by the regular practice of meditation.

11. Speaking truth frees one from worries and bestows peace and strength.

12. Speaking truth is the most important quailfication of a Yogi. If truth and one thousand Ashwamedha Yajnas are weighed in a balance, truth alone will out-weigh.

13. God is Truth. He can be realised by speaking the Truth and observing Truth in thought, word and deed.

14. Truthfulness, self-control, absence of envious emulation, forgiveness, modesty, endurance, absence of jealousy, charity, thoughtfulness, disinterested philanthropy, self-possession and unceasing compassion and harmlessness are the thirteen forms of truth.

15. Some persons hold that a lie, that is calculated to bring immense good is regarded as truth. Suppose an unrighteous king has ordered a sage to be hanged without any cause. If the life of this sage can be saved by uttering a falsehood, the falsehood is only Truth.

16. By speaking the truth always in all circumstances, the Yogi acquires Vak Siddhi. Whatever he thinks or speaks, turns to be true. He can do anything even by mere thought.

17. "This Atman is attainable by the strict observance of Truth." "There is nothing greater than the Truth" is the emphatic declaration of the Srutis. Take the life of Yudhishthira and

Satyavrati Harischandra. They did not part with the truth even at the critical junctures.

GRACEFULNESS

Gracefulness is easy elegance in form and manner. It is marked by propriety or fitness. It is the outward expression of the inward harmony of the soul.

Gracefulness is elegance of manners or deportment. It is beauty with dignity in manner, motion or courteousness.

A graceful figure is a perpetual letter of recommendation.

A graceful man is free from affectation and pretence. He has a dignified personality. He thinks, speaks and acts with propriety.

A man of gracefulness is characterised by grace, elegance, beauty, harmony or ease. He is pleasing in appearance, motion or language. He is graceful in form, action, looks or speech.

Graceful suggests motion or the possibility of motion. Beautiful applies to absolute fixity. A landscape or a sky is beautiful but neither is graceful. Graceful commonly applies to beauty as addressed to the eye though we often speak of a graceful poem or a graceful compliment. Graceful denotes a pleasing harmony of outline, proportion, etc., with a certain degree of delicacy. A Hercules is massive, an Appolo or a woman is graceful.

We speak of graceful attitude, graceful drapery.

We speak "Sita walks and speaks gracefully" i.e., with a natural ease and propriety, elegantly.

GRATITUDE

Gratitude is warm and friendly feeling towards a benefactor; thankfulness.

Gratitude is a sense of appreciation of favours received, accompanied with goodwill towards the benefactor. It is an emotion or sentiment of thankfulness, kindness or goodwill to a benefactor and a disposition to make a suitable return of benefits or services or, when no retuns can be made, a desire to see the benefactor prosperous and happy.

Gratitude is a duty which ought to be paid. It is much more than a verbal expresion of thanks. It is an indication of a noble nature. It is a virtue most deified. It is not only the memory of the benefit received from a good and kind man, but the homage of the heart rendered to him for his good deeds.

Gratitude is the noblest of virtues, the most capital of all duties.

Just as a river pours its waters into the ocean from which it drew its supply, so also a man of gratitude returns a benefit received from others. He looks upon his benefactor with reverence and love. If he is not able to return the benefit, he keeps it in his memory with kindness. He does not forget it during his whole life time.

Be grateful to God, your Creator, for all the bounties He has given you. Pray to Him fervently from the bottom of your heart. Sing His glory. Remember Him at all times. Surrender your entire being to him, obtain His Grace and be happy for ever.

An ungrateful man is a miserable wretch in this world. His lot is pitiable, lamentable and deplorable indeed! This world abounds with ungrateful wretches.

Be grateful. All will admire and revere you. You will reap a rich harvest of peace and immortal bliss.

Harohara. Tat Twam Asi. Om Shanti.

HEROISM

Heroism is courage or boldness.

A hero is distinguished for valour, fortitude, or bold enterprise. He is deified or regarded as a demi-god. Death of a hero puts him in a more exalted rank. He is worshipped in local festivals.

Hero is a man of distinguished bravery. He is very daring.

Heroism is the brilliant triumph of the soul over fear, fear of suffering, fear of death, etc.

Heroism is the sum of herioc qualities as lofty aim, fearlessness, resolution, fortitude.

Courage is generic, denoting fearlessness of danger. Fortitude is passive courage, the habit of bearing up nobly under trials, dangers and sufferings.

Bravery and valour are courage in battle or other conflicts with living opponents.

Intrepidity is firm courage, which shrinks not amid most appalling dangers.

Overactivity: When you pass your hand over the liver and feel a rush of hot energy, this indicates that the liver is overheating because of toxins or emotional stress.

Underactivity: When you pass your hand over the liver and you feel a dense and hot energy, the liver is weak, congested and sick.

Lungs Scanning

Healthy lung energy feels cool and dry.

Negative Emotions: Pass your hand over the lungs. Do the Lungs' Sound and listen to the echo of the sound as it rebounds from the lungs. Sadness will feel like a deflating ball pressed between your hands.

Overactivity: Energy that feels dry and hot indicates an overworked organ.

Underactivity: Energy that feels damp and cool under the scanning hand indicates underactive or congested lungs that can lead to respiratory problems.

Heart Scanning

Healthy heart energy feels warm and energetic.

Negative Emotions: Hot and charged energy indicates impatience, hastiness and arrogance in the heart.

Overactivity: If your hand detects hot, charged and overly expansive energy, this indicates that the heart and blood may be overheating.

Underactivity: Energy that feels cool and less expansive indicates an underactive or congested heart.

Spleen Scanning

Healthy spleen energy feels lukewarm.

Negative emotions: Energy that feel damp and sinking indicates excessive worry.

Overactivity: The energy feels hot and damp when the spleen is overactive.

Underactivity: The energy feels cool and damp.

Kidneys Scanning

Healthy kidney energy feels cold, but not too cold.

Negative emotions: Energy that feels cold and chilly indicates fear.

Overactivity: When the kidneys are overworked or overstimulated by excessive exercise or improper diet and liquid intake, the energy can feel damp, stick and hot.

Underactivity: When toxins are blocking the organs, the energy can feel damp and cold.

Hand scanning is an art, and may take a while for you to feel confident using it. Practicing Cosmic Chi Kung is one of the best ways to develop greater sensitivity in hand scanning.

Gallantry is adventurous courage, dashing into the thickest of the fight.

Heroism may call into exercise all these modifications of courage.

The world in all ages has worshipped its heroes, but the standard of heroism has always been improving. We reckon heroism today, not so much on account of the thing done, as for the motive behind the act.

HONESTY

Honesty is integrity, candour, freedom from fraud, frankness, fair dealing.

Honesty is the only virtue upon which individual or national life can safely rest. The society can only endure when it is built with the tempered mortar of honesty, justice and righteousness.

There is one immutable law—honesty. Honesty in the house, in the office, in politics, in business, on the highway, in the courts of justice, in all assemblies—is what we need.

Honesty is not the best policy, but it is the best virtue. It is the highest wisdom.

Honesty is conformity to justice and moral rectitude.

Honesty is a disposition to conform to justice and honourable dealing. It is uprightness of conduct in general. It is justice, fairness, probity, rectitude, uprightness.

The basis of high thinking is perfect honesty.

An honest man is characterised by openness, genuineness or sincerity. He is faithfull, sincere, straightforward, true, trustworthy, upright. He is always disposed to act with careful regard for the rights of others, especially in matters of business or property. He scrupulously observes the dictates of a personal honour that is higher than any demands of mercantile law or public opinion and will do nothing unworthy of his own inherent nobility of soul. He does not steal, cheat or defraud. He will not take an unfair advantage that would be allowed him.

He who is honest in the highest and fullest sense, is scrupulously careful to adhere to all known truth and right even in thoughts.

Deceitfulness, dishonesty, faithlessness, treacherousness, falsehood, hypocrisy, are the opposites of honesty.

No success in Yoga, no spiritual progress is possible without honesty.

HOPE

A desire of some good, with expectation of obatining it, or a belief that it is obtainable, is hope. Hope is anticipation.

Hope is a stimulant. Hope is a tonic. Man lives here through hope alone. He hopes to become better. He hopes to get something which will give him solace, satisfaction, comfort, peace, bliss and immortality.

Great things are never done, even small success is never achieved, when there is no hope.

Hope is the balm and life-blood of the soul. Hope gives you strength. Hope pushes and urges you to struggle, strive, achieve and attain.

Man always hopes to attain something and make himself better and better. The natural flight of the mind is from hope to hope.

Nil desperandum. Never despair. Life begins fresh each morning. Look not into the past. Be always hopeful. You will succeed.

Hope is your companion. Hope is the mother of success. Hope is your prop to lean upon and hope gives you happiness. Hope pushes you to sublime heights of splendour and glory. Hope conducts you through life by an agreeable path. Hope inspires and encourages. It conducts you in an easier and more pleasurable way to your journey's end.

Every man or woman in this world rests on hope. A medical student hopes to become a famous doctor with roaring practice. A young girl hopes to marry a beautiful, intelligent, rich husband. A businessman hopes to become a millionaire. A Munsiff hopes to become a District Judge.

Heart is the last organ that ceases its functioning. Hope is the last thing that dies in man.

You live not on what you have, but on what you hope.

Hope is that which is welcome. Expectation is either welcome or unwelcome. Trust and confidence denote dependence on a person or thing to bring about that which is desired.

The promises of hope are very sweet.

He who hopes helps himself.

Give up vain hopes. Fix not your hopes beyond the bounds of probability.

Be strong to hope, Oh heart!

Oh Auspicious Hope! In thy sweet garden grow the flowers of success and happiness.

HOSPITALITY

Hospitality is the spirit, practice or art of receiving and entertaining strangers and guests without reward and with kindness and consideration.

A hospitable man is generous and bountiful.

Hospitality is Atithi Yajna. It is one of the five Yajnas or daily sacrifices which are to be practised by the householders.

Hospitable people are rare in this world. All shut their doors and feed their stomachs with avidity, cupidity and stupidity.

Hospitality is a direct passport to heaven or higher blissful regions.

If rich people are hospitable, the woes of this world will be lightened.

Let the hospitality of the house with respect to the poor, be kept up.

HUMILITY

Even if you are a man of great erudition, you must be very humble. A learned man with humility is very much revered by all.

If you want to drink water at the tap, you will have to bend yourself. Even so, if you want to drink the spiritual nectar of immortality, you will have to bend. You must be meek and humble.

Humility is the highest of all virtues. 'Blessed are the meek; for they shall inherit the earth' (St. Mathew, Chap. V—51). You can destroy your egoism by developing this one virtue alone. You can influence the whole world. You will become a magnet to attract many persons. All the lives will be drawn towards you. Humility must be genuine. Feigned humility is hypocrisy. It cannot stand.

God helps you only when you feel utterly humble. Therefore develop this virtue to a considerable degree. Become an embodiment of humility. Become humility personified.

There is no virtue greater than humility. Through this one virtue alone you can get salvation. Humility destroys egoism, brings Sama-bhava, Atma-vasya, peace of mind, good sleep and rest, Atma Bhava or Narayana Bhava in all beings and eventually Self-realisation or Vishnu Padam.

INDUSTRIOUSNESS

This is the quality of being diligent. It is assiduity. This is steady application to labour, study or writing.

A man of industrious nature is laborious. He is very hard-working.

This is the opposite of idleness, sloth and indolence.

An industrious man earns the fairest fruits and the richest rewards.

Industry will improve your talents, make up your lack of abilities and supply their deficiencies.

Great persons achieved their greatness by industry rather than by mere brilliance.

The way to wealth and prosperity depends upon industry and frugality.

Industry makes all things easy. It always achieves triumph. An industrious man will never starve. Poverty and failure are unknown to him.

Industry keeps the body healthy and strong, the mind clear, the heart whole and the purse full.

Industrious nature produces cheerfulness, joy; destroys evil tendencies and habits, sweetens enjoyment and seasons your attainments with a delightful relish.

We speak in common parlance: “Sri Tawker is an industrious workman; Sri Bannerjee is an industrious man of letters; Sri Ramaswami had an industrious career.”

Goldsmith writes in his “The Traveller”:

“Industrious habits in each bosom reign
And industry begets a love of gain.”

Be industrious and attain success and prosperity.

INITIATIVE

Initiative is the power or rite of commencing. It is an introductory step or action. It is making a beginning. It is the performance of the first act. It is a first move, beginning or start.

We say: “Rama took the initiative in that noble work.”

Initiative is the power to originate or start. It is the aptitude to develop or undertake new enterprises. It is the first active procedure in any enterprise.

It is the power of commencing. It is the power of taking the lead or of originating.

Many people lack the initiative as they are timid, shy, lazy and indolent, as they are lacking in pluck, tact, pushing nature, strength of will, vigilance, diligence, perseverance and courage. Therefore, they are not successful in life.

Be bold. Be cheerful. Be tactful. Be skilful. Be vigilant. Be persevering. Be patient. The initiative will come and you will attain sanguine success in all your undertakings.

INSPIRATION

Inspiration is a superior, elevating, divine influence.

It is the supernatural divine influence exerted upon the sacred teachers and writers by the Spirit of God by which divine authority is given to their writings.

It is the supernatural influence by which prophets, apostles, saints and sacred writers are qualified to set forth divine truths without any mixture or error.

It is the communication of the divine will to the understanding by suggestions or impressions on the mind, which leave no room to doubt the reality of their supernatural origin.

All sacred scriptures are given by inspiration of God.

Inspiration is the infusion or communication of ideas or poetic spirit by a superior being or presiding power.

Inspiration is spiritual inexhaustible wealth. It gives joy, peace and bliss eternal.

An inspired writing convinces and converts sinners, atheists, sceptics. It edifies and comforts believers. It prepares them for emancipation or the final beatitude. It is a safe, infallible, trustworthy, guide, concerning the way of emancipation.

It is majestic, pure, forcible, clear. It is the word of God.

INTEGRITY

Integrity is uprightness of character, honesty, purity. Integrity is the first step to true greatness. A man of integrity is honoured and respected by all. All place confidence in him.

To maintain integrity costs self-denial. It is liable to opposition, but its end is glorious. The whole world will pay homage to it.

Integrity comprehends the whole moral character, but has a special reference to uprightness in mutual dealings, transfers of property and agencies for others.

The moral grandeur of independent integrity is the sublimest thing in this world.

INTUITION

Intuition is direct supermental knowledge of Atman through direct Self-realisation. There is no reasoning here. Intellect ceases to function here. There is no sensation here. Intuition is beyond relativity.

This is an inner spiritual experience which cannot be adequately described in words. Language is imperfect; also it cannot express this whole, ineffable, transcendental experience. Words are merely conventional.

You can realise God or Atman only through intuition.

In intuition everything is clear. All doubts vanish in toto.

Intuition is immediate knowledge in contrast with mediate-knowledge. Through intuition the aspirant perceives the truth of things without reasoning or analysis.

Intuition is knowledge from within. First there is the flash of intuition. Thereupon the aspirant is established in his own Atman or self.

Intuition is immediate knowledge of the Absolute through the eye of wisdom as opposed to knowledge of the objects through the senses and intellect.

Intuition transcends reason, but is not opposed to reason.

Intuition is truth obtained by internal apprehension without the aid of perception or the reasoning powers.

Intuition is the direct perception and apprehension of the divine reality underlying the manifested and the unmanifested universe.

The sage in his flights of intuition ascends to that supramental region where he experiences the Divine Reality or the Absolute. The superconscious experience is very vivid, vital and vibrant. It is intensely real to the sage. He lives in it, moves in it and breathes in it. The intuitive experience-whole is grand, sublime and profound.

The knowledge of God would have been lost to mankind but for the intuition and revelation of the seers and sages.

Intuition is the only way by which the Absolute can be realised and experienced in all its totality and integrality. These mortal limited senses and the finite intellect cannot comprehend the all-pervading Reality.

The mind and senses require time and space to function, but the Reality which is beyond this temporal, spacial and causal order of things can only be grasped and apprehended by intuition.

Reason can give you only conceptual knowledge and conceptual knowledge does not give you knowledge of the Reality in its whole, in its totality, but it divides, fragmentises and breaks things into pieces.

The Indwelling Soul of this material universe is pure consciousness. Indian sages and seers have intuited this Reality in all its integrality and have given to mankind the rich and precious pearl of wisdom of the Self.

KINDNESS

Kindness is the state or quality of being kind. It is goodwill, humaneness, tenderness.

Kindness is that temper or disposition which delights in contributing to the happiness of others. Any act of benevolence which promotes the happiness or welfare of others is kindness.

Kindness is a grace very near the likeness of God.

A kind man is disposed to do good to others. He is benevolent. He is good-natured, sympathetic, friendly, tender, accommodating and amicable.

A kind man wins the hearts of others.

Kindness is the cheapest of all things. Exercise of kindness does not involve much trouble and sacrifice. Smile, serve, radiate joy. Speak kind and sweet words. Cheer up a man in distress.

Kind words soothe, quiet and comfort the hearer.

Kindness is the golden chain by which people are bound together.

Heaven is open to all kind-hearted persons.

A kind man is really the king of a vast domain. He is indeed the Emperor of emperors.

A kind look, a kind word, a kind act, a friendly smile, all cost nothing but bring to others happiness which money cannot buy. They are priceless in their value.

He who entertains kind thoughts is ever calm and cheerful. Kind thoughts increase the flow of vital energy into your body and mind.

Do kind acts now. Do not procrastinate.

Kindness is like a healing balm. It soothes suffering.

Kindness is the language the deaf can hear and the dumb understand.

Little drops of water make the mighty ocean. Even so, little acts of kindness make an ocean of goodwill.

By 'many kindness' is meant not 'much kindness' nor 'great kindness', but kindness manifested in many forms or shown on many occasions, many acts of kindness.

Kindness is a direct passport to the kingdom of Eternal Bliss.

Cultivate kindness. Be kind to all. You will soon attain God-realisation.

LOVE

Love is the living essence of the divine nature which beams full of all goodness. Love is the golden link or tie which binds heart to heart, mind to mind, soul to soul. Love is the crowning grace of humanity.

It is the holiest right of the soul. Love is the masterkey to open the door of Moksha or eternal bliss.

Love is the best thing in this world. It cements broken hearts.

Life is a sweet flower of which love is the honey. The great pleasure of life is love. Love is the whole, the very life-breath of your heart.

Love is indeed heaven upon earth. It casts out all sorts of fears.

This world has come out of love. It exists in love. It finally dissolves in love.

Love inspires, illumines, designates and leads the way. Love inspires love.

Love never reasons but profusely gives. It is not affected by offence or insult. It looks not with the eyes, but with the heart. It looks through a telescope.

Love makes great sacrifices. Love is anxious to help and serve others and make others happy. Love forgives.

Love is a saviour of life unto life. Love is a divine elixir. It bestows immortality, supreme peace and everlasting joy.

God is an embodiment of love. He is an ocean of love. If you wish to attain God-realisation, you must also become an embodiment of love.

The only greatness lies in unselfish, pure love. There is not even a tinge of selfishness in pure love.

The love of a mother is never exhausted. It never changes. It never tires. Mother's love endures for ever. Love is not getting or bargaining, but giving. Love is goodness, honour and peace and pure living.

Pure love is bliss. Pure love is sweet. Pure love is without selfish attachment. Pure love is immortal, divine essence. Pure love is a divine flame. It is ever brilliant. It is never exhausted.

It is the very essence of pure love to be willing to suffer for the good of others, to place its happiness in the happiness of others.

Pure love strengthens and ennobles the character, gives a higher, pure motive and a nobler aim to every action of life, and makes a man strong, noble and courageous.

True, pure love or divine Prema is eternal, unchanging, infinite. It takes unselfish interest in other people's welfare, interest in other lives than its own.

Physical love is animalism. It is passion exalted and refined. It is gross and sensual.

Love of body or skin is passion. Love of God is Prema or devotion. It is pure love. It is love for love's sake.

To love any one for attaining some selfish gain is selfish love. It binds you to this earth.

To love all beings with Narayanabhava as manifestations of the Lord is pure love. It is divine love. It leads to liberation.

Pure love redeems, purifies the heart and transmutes you into divinity.

A husband loves his wife not for the sake of his wife, but loves her for the sake of his own self. He is selfish. He expects sensual pleasure from her. If leprosy or small-pox destroys her beauty, his love for her ceases.

All loves are simply stepping stones to the love of God.

Cultivate pure love slowly in the garden of your heart through Japa, prayer, Kirtan, faith, devotion, service of saints, humanity and all beings, meditation and company of saints, etc.

Love all. Embrace all. Include all in the warm embrace of your love. Cultivate cosmic love or unreserved love.

Love your neighbour as your own self. Love God with all your heart, mind and soul.

Hatred ceases not by hatred but ceases by love. Return love for hatred.

Love your enemies, love your inferiors. Love all animals. Love your Guru. Love all saints and sages.

Love little, but love long. Love must be of an enduring nature.

Speak lovingly. Act lovingly. Serve lovingly. You will soon enter the Kingdom of Heaven or Supreme Peace.

Love not perishable, mundane objects. You will come to grief and destruction if you love them.

Love God. Love your own immortal Self or Atman. You will be blissful for ever. You will become immortal.

Eat in love. Drink in love. Bathe in love. Talk in love. Sleep in love. Write in love. Think in love. Serve in love. Walk in love. Become an embodiment of love.

UNIVERSAL LOVE

The only Sara Vastu in this world is Prema or Love. It is eternal, infinite and undecaying. Physical love is passion (Moha) or infatuation. Universal love is only Divine love. Cosmic love and universal love are synonymous terms. God is love. Love is God. Selfishness, greed, egoism, vanity, pride, hatred, contract the heart and stand in the way of developing universal love.

Develop universal love gradually through selfless service, Satsanga with great souls, prayer, recitation of Guru Mantras, etc. When the heart is contracted through selfishness in the be-

Chapter VIII
Cosmic Chi Kung Palm and Finger Training

Why We Practice the Cosmic Chi Kung

The Cosmic Chi Kung is also known as Buddha Palm. The reason we train with the Empty Force practice in connection with the Cosmic Healing is to learn how to project Chi through the space in the cosmos, the space between your hands and to project Chi through the space to your students. Usually when we touch the student we pick up sick energy. This practice will teach you how to ground the sick energy to the earth and to disperse it into the Universe to be decomposed and recycled by the planets.

Practice until you can project Chi out from your palms and fingers and when you feel the Chi coming into your body through your hands. The most important part is to always remain connected with the Universal Force coming from all six directions. If you focus on healing from your hands or your Tan Tien you will use up your own energy. You must be connected to the Cosmic Universal Force.

Expand your awareness to nature, the oceans, the lakes, the forests and mountains. Smile to nature and feel it smile back to you; inhale and draw the Chi into your palms. Expand your awareness to connect to the light, the Milky Way and the cosmos.

Be aware of the heart and the red light in the heart; expand your awareness to infinity. The light will come close to you; picture the red planet Mars above you. See it shine down to your crown, feeling the light in your palms. Be aware of the six directions, feel your body growing bigger; until you touch the sky, your feet still planted in the earth.

ginning, man loves only his wife, children, a few friends and relatives. As he evolves, he loves the people of his own district, then the people of his own province. Later on he develops love for men of his country. Eventually, he begins to love other people of different countries. In the long run he begins to love all. He develops universal love. All the barriers are broken now. Heart is expanded infinitely. It is very easy to talk of universal love. But when you want to put it into actual practice, it becomes extremely difficult. Petty-mindedness of all sorts comes in the way. Old wrong impressions which you have created by your wrong mode of life in the past, act as stumbling blocks. Through iron determination, strong will- power, patience, perseverance and Vichara (right enquiry), you can conquer all obstacles quite easily. The grace of the Lord will descend on you if you are sincere.

Universal love terminates in Advaitic unity or oneness or Upanishadic consciousness of seers and sages. Pure love is a great leveller. It brings equality and equanimity. Hafiz, Kabir, Mira, Gouranga, Tukaram, Ramdas—all have tasted this universal love. What others have achieved you can also attain.

Feel that whole world is your body; your own home. Melt or destroy all barriers that separate man from man. The idea of superiority is ignorance or delusion. Develop Viswa-prema, all-embracing love. Unite with all. Separation is death. Unity is eternal life. The whole world is Visva-Brindavan. Feel that this body is moving temple of God. Wherever you are, whether at home, in office, railway station or market, feel that you are in the temple. Consecrate every act as an offering unto the Lord. Transmute every work into Yoga by offering its fruits to God. Have Akarta, Sakshi Bhava if you are a student of Vedanta. Have Nimitta Bhava if you are a student of Bhakti Marga. Feel that all beings are images of God. *Isaavasyamidam Sarvam*—this world is indwelt by the Lord. Feel that one power of God works through all hands, sees through all eyes, hears through all ears. You will become a changed being. You will enjoy the highest peace and bliss.

May Lord Hari take you all to His bosom and bathe you with waters of sweet love!

May your heart be filled with cosmic love!

COSMIC LOVE AS AHIMSA

Much has been written and said about cosmic love. An exhortation to develop selflessness and cosmic love has become part of religious preaching. It is as it should be. For, selflessness and cosmic love are the very alpha and beta of spiritual life. They form the foundation of life divine, and their influence is felt throughout the superstructure. It would be quite true to say that these twin-virtues form the most essential prerequisites, the disciplines, the test of progress, the Supreme Attainment and its later manifestation. Selflessness and cosmic love are the Sadhana, the Sadhya and Siddhi. They are the guiding light of the Sadhaka, and the aura of the Siddha. In neither can it be absent! Hence the supreme importance of our understanding aright the true meaning of selflessness and cosmic love, or, shall we say selflessness or cosmic love, for, on a closer scrutiny we shall find that the two are in fact one. One who is truly selfless, who has given up love of the self, finds himself in Cosmic Love. One in whose heart the rarest flower of cosmic love grows has hardly a thought for his own self, much less a love for it: he is utterly selfless.

Cosmic love as Sadhana is the golden mean between Raga (inordinate love or attachment) and Dvesha (hatred). It is very important for an aspirant to remember that *cosmic* love is the very antithesis of love of any one particular thing or being. Love of one is Moha (delusion) and Raga (attachment). It is the root of bondage to Samsara. Cosmic love, on the other hand, is liberating and has to be distinguished from Raga. Therefore, do the scriptures and saints ask the Sadhaka to develop Vairagya (the antidote to the poison of Raga) to the highest degree.

Again, Vairagya is good so far as it goes. But it should not lead the Sadhaka to the self-exclusiveness which is none other than a subtle form of selfishness. Here, too, there is need for caution. The aspirant who zealously cultivates Vairagya might turn away from the world, might shun company and comforts; but he might become extremely selfish. He might all the time be thinking of himself, his Sadhana, and his Vairagya. Naturally, he would come to regard everything and everyone that does not fall in line with his views, his behaviour, his standards of conduct, and his Sadhana as inimical to himself. Now, this, again is extreme. Vairagya is not contemptuous aversion, but the absence of Raga or inordinate love or attachment. Contemptuous aversion, on the other hand, is subtle Dvesha (dislike or hatred), subtle Himsa—the negation of Ahimsa.

Vairagya should be the natural corollary to Ahimsa. Attachment to everything other than the Self or Atman should be given up. Love of self, of the body, of the modes of thought that take the form of pet dogmas and ideologies—everything other than the Self should be given up. For, one who worships these "little" things, the unrealities, the objects of phenomena, is bound to get entangled in the Dvandvas of "love" (Raga) and "hate" (Dvesha). To illustrate; one may have no attachment whatsoever to one's family, to one's property to one's own body even—but he may be attached to some pet ideology. It may outwardly seem that he has great Vairagya, that he is perfectly selfless. You will find on closer analysis that it is not really so. Adoration of a pet ideology means, in however subtle a degree, an aversion to (if not hatred of) some other opposing ideology; and, though one may strive not to translate this aversion into personal animosity towards those who hold different views yet it lurks at the back of one's mind. There is attachment (Raga) to that ideology; and so there is no Vairagya. There is adoration of something born of the self, however subtle it may be—so, there is no selflessness either. Cosmic love is (by the same test) found to be absent.

Now, we have to find That which is not attachment, nor self-exclusiveness. That certainly is cosmic love, which knows no hatred in however subtle a degree or sublimated a form. It is impossible to define this Cosmic Love—*Anirvachaneeyam Prema-Svarupam.* The wise Patanjali Maharshi, therefore, enjoined upon the Sadhakas to get established in Ahimsa. Note the wisdom that prompted him to give a negative nomenclature, Ahimsa. Harbour not evil thoughts; utter no evil word; harm none. Here, then is a Sadhaka that carefully, wisely and efficiently avoids all the extremes, all chances of perversion. When the Sadhaka thus gets established in Ahimsa, the Light of Self-knowledge dawns in him. He realises that the Self that resides in him, resides as the Self of all beings. That state in which this knowledge fully manifests itself is Cosmic Love.

Such a sage (for a Sage is one in whom Cosmic Love resides) does not shun society; he hates none. He loves all, not as a matter of gracious condescension, but as a natural course of conduct of one who does not love his own self above anything else, who hates none, nothing, and in whom there is not the slightest trace of hatred or ill-will. He loves the Self which pervades all creatures. As this Self is all-pervading, he is attached to none, nothing. He identifies himself with all, because he is free from self-adoration. Selfless service springs from him as the breath springs from all living beings. Whomever he comes into contact with in the normal course of his daily life, he adores as the manifestation of his own Self. He wishes them well. He is filled with goodwill, as he has cast ill-will out of his heart. The very practice of Ahimsa has enabled him to root out selfishness. A selfish man can never truly practise Ahimsa. Love of self always means no-love of something else; eagerness to acquire something for oneself must necessarily mean effort to deprive some one else of it. The sage who is established in Ahimsa or Cosmic Love, on the other hand, takes as much delight in others' enjoyment as in his own. When he finds that some one is suffering, he rushes to relieve. Not because he loves that particular person; but because he has realised that his own Self pervades the other person, because the goodwill or cosmic love that fills his heart naturally flows towards the suffering man and endeavours to remove his affliction. This service he renders naturally—service for the sake of service; love for love's sake—these expressions can be understood only if you watch the behaviour of one whose heart is filled with Cosmic Love. It is a love that does not clamour for reciprocity; it is service which does not look back for appreciation or reward. In this love, in this service, the Sage of Cosmic Love makes no distinction whatsoever. All are equal to him. Otherwise, it would not be Cosmic Love, it would not be Ahimsa, it would not be selflessness. He is tranquil and peaceful, for Cosmic Love has extinguished the fire of selfishness, lust, anger and greed, that consume the peace of an ordinary man. He is ever happy for he has no desires, and Cosmic Love keeps him ever happy-at-the-happiness-of-all, and he lives in the Consciousness of the Immortality of the Self, in the indestructibility of the soul of man.

Glory, glory to the Sage of Cosmic Love! May Cosmic Love dwell in the hearts of all.

MAGNANIMITY

Magnanimity is greatness of soul. It is elevation of dignity, of mind. It is that quality of mind which raises a person above all that is mean or unjust. It is generosity. It is nobility.

Magnanimity is generosity in sentiment or conduct towards others. It is exaltation above envious, cowardly, vindictive or selfish motives. It is loftiness of character or action. It is large-heartedness.

Magnanimity is that elevation or dignity of soul which encounters danger and trouble with tranquillity and firmness, which raises the possessor above revenge and makes him delight in acts of benevolence, which makes him disdain injustice, and meanness and prompts him to sacrifice personal ease, interest and safety for the accomplishment of useful and noble objects.

A man of magnanimity is elevated in sentiment. He is brave and unselfish. He scorns temptations, what is mean and base and despises earthly pomp and splendour.

Of all virtues, magnanimity is the rarest.

Mighty of heart, mighty of mind—magnanimous is indeed to be great in life.

Generosity, high-mindedness, chivalrousness, large-heartedness, nobleness of soul are synonymous with magnanimity.

MANLINESS

Manliness is bravery.

Manliness is not merely courage. It is the quality of soul which frankly accepts all conditions in human life and makes it a point of honour not to be dismayed or wearied by them.

Dignity is manliness. Nobility is manliness.

Manliness is freedom from childishness, boyishness or womanishness.

A manly man possesses characteristics of a true man as bravery, resoluteness, etc.

Every virtue or the higher phase of manly character begins in this—in truth and modesty before the face of all maidens; in truth and pity, or truth and reverence to all womanhood.

'Manly' refers to all the qualities and traits worthy of a man.

We speak of manly decision, manly gentleness or tenderness—such as firmness, bravery, undaunted spirit, dignified nature, nobility and stateliness.

MANNERS

'Manners' is good behaviour or respectful deportment. It is good character. It is good breeding.

'Manners' is the demeanour or bearing peculiar to one. It is personal carriage. It is mien. It signifies polite, civil or well-bred behaviour.

A man of good manners is free from rudeness. He is well-behaved. He is complaisant, civil, courteous and polite.

Good manners constitute good behaviour. They consist of courtesy and kindness. They are the art of making those people easy with whom you converse. They give colour to life.

Manners are the result of much good sense, some good nature and a little self-denial for the sake of others.

A man of good manners is always sociable and complaisant.

Good manners are the best thing in the world to get a good name and make friendship.

A man of good manners eats quietly, moves quietly, lives quietly and loses even his money quietly.

Good manners are stronger than laws.

Good manners make the road of life smooth. They render a superior amiable, an equal agreeable and an inferior acceptable. They smooth distinctions, sweeten conversation, and make everyone in the company pleasant with himself. They produce good nature, mutual benevolence, soothe the turbulent, encourage the timorous and humanise the fierce.

Manners are minor morals. They are the shadows of virtue. They are a passport to regard. They are the blossom of good sense and good feeling.

Pride, ill-nature, want of sense, arrogance, impatience are the great sources of ill-manners.

Good manners are a part of good morals. They are a rare gift. They easily and rapidly ripen into morals.

Be silent as to yourself. Say little or nothing about yourself.

MEEKNESS

Meekness is the state or quality of being mild and gentle of temper. It is submissiveness. It is humility. It is gentleness of disposition. It is submission to divine will. It is that low, sweet root from which all divine virtues shoot.

Blessed are the meek, because they will soon attain eternal peace.

Meekness abounds in goodwill. It excludes revenge, irritability, morbid sensitiveness.

A meek man bears patiently the resentments of others.

Meekness is the noblest self-denial. It is abstinence from self-love and self-conceit.

Meekness is a solid foundation of all the virtues.

Meekness is the essence of true religion. It is a fundamental virtue of a saint. It is not a weak and timid quality. It is a power. Meekness is nobility. It is always grace. The flower of meekness grows on a stem of grace.

God delights to dwell in the hearts of the meek.

The first, the second and the third thing in religion is meekness. Meekness is the avenue to spiritual glory. It makes a man divine.

Meekness is the root, mother, nurse, of all virtues.

Meekness is the one road to lead you to God.

Meekness, courtesy, benevolence, politeness, gracefulness are virtues of the same stock.

The first test of a saint or a truly great man is his meekness.

Meekness reveals the divine light.

God walks with the meek. He reveals Himself to the meek.

MERCY

Karuna Sagara Narayana
Karuna Sindhu Sadasiva.

God is an ocean of mercy or Karuna. He is all-merciful. If you want to have communion with Him, if you want to unite with Him, if you wish to dwell in Him, you must also become an embodiment of mercy.

Mercy is a fundamental attribute of a saint. If you do not find mercy in him, do not take him for a saint.

Mercy is an enemy of cruelty, atrocity, harshness, rudeness, ferocity. It is a friend of gentleness, softness, sweetness.

Mercy among the virtues is like the moon among the stars.

Mercy is a great power. It is intense strength. It gives strength.

Mercy opens the door to freedom, immortality and eternal bliss. It makes the narrow heart as wide as the sky. It gives wings to soar high to the realm of Supreme Peace.

Mercy transforms you into divinity. It is mightiest in the mightiest.

Sweet mercy is nectar. It is nobility's true mark or Linga. It is a celestial shower of Grace and love. It is a magnet.

Mercy is the greatest attribute of God. Mercy softens and purifies a sin-hardened heart.

Mercy shines with even more brilliance than justice. It bestows Chitta-Prasada or peace of mind. Therefore, be merciful.

Mercy is tenderness and forbearance shown in sparing an offender in one's power. It is a forgiving disposition.

Mercy is compassion or benevolence. Mercy is sublime goodness. It knows and understands the sufferings of others and is ready to help them.

The heart of a merciful man is more soft than butter. Butter melts near fire, but the heart of a merciful man melts when he sees the sufferings of others even at a distance.

The ingredients of mercy are tenderness of heart, fellow-feeling, good feeling, sympathy, compassion, supreme goodness, kindness, affection, love, charity, generosity, selflessness and sacrifice.

Mercy, compassion, sympathy and pity are virtues of the same genus. Mercy is the foremost amongst them. It is divine. It includes not only compassion, but also forgiveness, love and service. The man of mercy serves and loves the person who has wronged him.

Compassion comes next. Compassion is a fellow-feeling or sorrow for the sufferings of another. Compassion combines the tenderness of pity and the dignity of sympathy with the active helping nature of mercy; but it is exercised only in the case of those who are suffering and are unfortunate. Mercy has forgiveness, tolerance, forbearance and cosmic love also, in addition to the qualities that make up compassion.

Sympathy and pity are merely feeling for the others. Whereas compassion embraces in its love human beings and animals, sympathy is felt only for one's own equals or those who are above oneself. But, sympathy is not dynamic like compassion or mercy.

Pity is feeling for the suffering of inferiors. It implies a certain amount of vanity and arrogance in the person who pities another. On account of this vanity, pity almost always ends in words!

The thoughts, words and deeds of a merciful man are full of sympathy and compassion. He always shares what he has with others. He sacrifices even his own needs and comforts for the sake of others.

If you have a hard heart, try to do little acts of kindness and mercy. Give a cup of milk to the poor sick man. Give a small blanket to the poor man during winter. Feed a poor man or Sadhu once a month. Visit a Hospital and serve the sick patients. Thus cultivate mercy.

Feel for others' sufferings. Be merciful in your judgement of others. Remember your own defects, frailties and weaknesses. Be slow in your criticism of others and generous towards those who do wrong actions.

Show mercy to others. Others will also be merciful to you. You will receive mercy when it shall be most needed. This is the immutable law of God.

Remember again and again Lord Buddha and his actions and other saints. Study 'Lives of Saints' and 'Saints and Sages.' You will gradually develop mercy.

The sun, the tree, the river, are impartial. Even so you will have to show mercy towards your friend and your enemy.

Remain in the company of sages and saints. Meditate on the Lord. Repeat His Name. Sing Kirtan and His glory. You will develop mercy.

Meditate in the early morning on the quality of mercy. When you move in the world, feel 'I will be merciful today. I will perform acts of mercy.' Slowly mercy will become part and parcel of your nature.

Show mercy to animals and persons who are in distress. Wipe their tears. You will indeed be blessed.

Follow the example of Sri Swami Chidananda who has a wonderful heart filled with mercy. He dressed a dog which had an ulcer with maggots. He dressed a leper for three months, with his own hands.

Charitable institutions, charitable hospitals, decrepit homes, construction of wells, tanks, poor feeding homes, Annakshetra, Dharmashalas, animal welfare leagues, social service institutions—are all manifestations of mercy.

May mercy arise in your heart. May your heart be filled with mercy.

MODERATION

Moderation is freedom from excess. It is the act of restraining or tempering or lessening or repressing.

A man of moderation keeps himself within measure or bounds. He regulates his food and other things. He is temperate. He is reasonable.

Moderation is the inseparable companion of wisdom.

Moderation gives a charm to life. It bestows longevity and good health.

The choicest pleasures of life lie within the circle of moderation.

Moderation or temperance is the keeping of the proper mean between extremes and the tempering of excitement or passion. It is not so much a virtue in itself as a means to obtain it.

Moderation is an important quality which is to be cultivated by a student of ethics or an aspirant. Moderation is freedom from excess in anything. Moderation is calmness of mind. Moderation is equanimity. Moderation is skill in Yoga. Without moderation no success is possible in Yoga, and material pursuits also. All the luminaries of the world of the past have observed moderation.

You should be moderate in eating, drinking, sleeping, reading, laughing, copulation, talking, exercise, etc. Lord Krishna says, "Verily Yoga is not for him who eats too much, nor who abstains to excess, nor who is much addicted to sleep, nor even to wakefulness. Yoga kills all pains in him who is regulated in eating and amusement, regulated in performing actions, regulated in sleeping and waking" (Gita, VI. 16, 17). If you eat too much you will get too much sleep. Various diseases of stomach, intestines and liver will develop. All the internal or-

Opening Heaven and Earth Force in the Palms with Heaven and Earth Spirals

The purpose of this technique is to draw in the forces of heaven and earth through the palm. Activate the spirals, the symbol for the heaven and earth force in the center of the palm.



***Fig. 8.1** Enhances the symbol of Heaven and Earth Force, in the Laogong - Pericardium 8.*

This is accomplished by drawing these spirals with the palm itself. As you draw the spirals, you should actually feel the palm breathing, inhaling these forces in. In the beginning, however, you may only be able to use your own mental imagery and imagine that you are absorbing these forces. In time the feelings will replace your imagination.

You breathe in Heavenly Chi when you draw the heaven spirals, and breathe in Earthly Chi when drawing the earth spirals. You may draw in both in one session; you may also choose just to draw in either Heaven or Earth Chi if you feel you need more of one or the other. It is important to balance these energies whenever you do this exercise.

1. Begin by raising the right hand to about shoulder height with the elbow sunk and the palm facing forward. Slightly pull back (open) the index finger, and slightly stretch the thumb forward and down. This will activate the Laogong point on the palm.

   At the same time, touch the tips of your left thumb and index fingers together. This will allow the right hand to draw in the Heaven and Earth Chi. The left hand will then be held palm up to draw in the heavenly force, or held palm down to draw in the earthly force.

gans will be overtaxed. Too much copulation will drain your energy and cause weakness, low vitality and various diseases. Too much talking will disturb peace of mind.

Lord Buddha plunged into extreme austerity in the beginning of his spiritual practices. He gave up food entirely. He did rigorous tapas. He suffered very much. His body became emaciated. He did not make much spiritual progress. Then he adhered to the golden medium. He began to take food in moderation. He regulated his spiritual practices. Only then he attained illumination. He always taught disciples to stick to the middle path only. He learnt lessons from experience.

It becomes difficult for some to control the tongue. If the dishes are palatable, they go beyond the limits of moderation. They overload the stomach. College students who have plenty of money with them go to the sweetmeat shops and eat sweetmeats for Rs. 5 at a time. They cannot get up till the stomach is completely filled up. Complete filling of stomach is unhygienic and unscientific. Half the stomach only should be filled with food, quarter with water; one quarter of the stomach must be free for expansion of gas. This is Mithahara or moderation in diet. You can check overloading of stomach through complete fasting.

Always get up when there is still inclination to eat. Giving up salt for two or three days in a week will help you to reduce the quantity of your food. Reduction of food will not kill you. It will keep you quite healthy. It will help you to attain longevity.

Some students begin to study hard forcing away sleep with strong tea, burning midnight oil just before appearing for the final examination. They lead a happy-go-lucky life for ten months. This is very bad. That is the reason why they fall sick on account of undue strain during the period of examination. Study must be well regulated. You must prepare your lessons thoroughly every day.

Some aspirants give up their food and try to live on Neem leaves for 40 days. This is foolish tapas. They fall sick, become weak, and are not able to do any Sadhana. Lord Krishna condemns this: "The men who perform severe austerities enjoined by the scripture, wedded to vanity and egoism, impelled by the force of their desires and passions, unintelligent, tormenting the aggregate elements forming the body and Me who is seated in the inner body, know these to be demonaical in their resolves." Do not spoil your health in the name of Tapascharya. Do not go to extremes in anything.

Sadhana also must be well-regulated. The period of meditation must be gradually increased. The period of Sirshasana must be gradually increased. The reduction of sleep must be gradual. When Sadhana is done by fits and starts there will be no spiritual progress.

Some people make friendship quickly with others, love them intensely for sometime and break it quickly on account of some trivial causes. They are extreme in their manifestations of emotions. They love either intensely or hate intensely. The emotions also must be well-controlled. Do not move too much with anybody. Be moderate in this direction also. You can keep lasting friendship with everybody.

Be moderate in your expenditure. Regulate your expenses. Some are imprudent. They thoughtlessly spend in one month too much and borrow in the next month.

Be moderate in thinking. Kill all irrelevant, nonsensical, loose thoughts. Do not think too much. Entertain sublime, divine thoughts.

Be moderate in work. Do not overwork. Overwork is cause for many diseases. If you overwork, you cannot meditate.

He who is perfectly moderate in everything is a real Yogi. He enjoys happiness here and in the next world also. He moves about happily and is always cheerful. He keeps perfect health and a higher standard of vigour, vim and vitality. He attains longevity and fame. He attains spiritual and material success.

Therefore stick to golden or happy medium. Follow always the middle path. Give up extremes in everything and be happy for ever.

May moderation be your motto and ideal!

MODESTY

Modesty is a shining light. It prepares the mind to receive wisdom and the heart to receive the Truth.

Modesty is the colour of virtue. It is not only an ornament but also a guard to virtue.

Modesty gives new lustre to one's character. It is a discerning grace. It is the citadel of beauty and virtue. It is a beautiful setting to the diamond of talent and genius. It is the greatest ornament of an illustrious life. It is the appendage of sobriety.

Modesty is ever amiable. It resides in a heart which is enriched with noble virtues.

Modesty is a feminine virtue. It is humility. It is purity of thought and manners. It is becoming behaviour. It is chastity. It is purity. It is moderation.

Modesty is the sense of propriety. It is the absence of all tendency to overestimate oneself. It is absence of anything suggestive of sexual impurity. It is decency. It is purity of manners, chiefly in reference to women.

Modesty is freedom from excess, exaggeration or extravagance. It is decent reserve or propriety of manner or speech. It is purity of thought, character, feeling or conduct. It is decorousness.

We speak of maidenly modesty. We speak of modest scholar. "He is too modest to speak."

There is no conceit in a modest man or woman. As a plain garment gives very good beauty to a woman, so a decent behaviour or modesty is the greatest ornament of wisdom.

A modest man or woman is unostentatious or unassuming, unpretentious. He is disinclined to bring himself into notice or limelight. He is free from show or gaudiness.

A modest man does not brag. He turns away his ear from his own praise. He is free from vanity and pride. He is very very simple.

A modest woman is bashful. She is not forward.

An egoistic man will always speak of himself, but a modest man ever shuns making himself the subject of his conversation.

The speech of a modest man is inspiring, and elevating. It touches your heart. It penetrates your heart. It breathes love and wisdom. It gives lustre to truth.

Make no display of your talent or attainments. Do not blow your trumpet. Be modest. All will admire and acknowledge your talents, abilities and achievements. A pot full of water makes no sound. Empty vessels make much sound. Modesty is eloquence itself.

A modest man wins the heart of all. He is respected and adored by all. Therefore be modest. Cultivate modesty to a maximum degree.

NOBILITY

Nobility is the quality of being noble. It is greatness of mind or character. It is dignity, excellence, generosity.

Nobility is the state or quality of being noble in character as distinguished from selfishness, cowardice and meanness. It is dignity and grace of character. It is magnanimity, greatness, nobleness.

Nobility is that elevation of soul which comprehends bravery, generosity, magnanimity, intrepidity, and contempt of everything that dishonours character.

It is not wealth nor ancestry, but honourable conduct and and a noble disposition that makes you great.

Nobility without virtue, is a fine setting without a gem. Virtue is the first title of nobility.

If you are endowed with a generous mind, this is the best kind of nobility.

Nobility is a graceful ornament to a man or woman. True nobility is derived from virtue, not from birth.

The true standard of quality is in the mind. He who thinks nobly is really noble.

Nobility is the finer portion of the mind and heart linked to divinity.

The essence of true nobility is neglect of self.

Sweet mercy is the true badge of nobility.

OBEDIENCE

Obedience is willingness to obey commands.

Obedience is submission to or compliance with a command, prohibition, known laws, or rule of duty. It is the performance of what is required or enjoined or the abstaining from what is prohibited. Obedience is submission to authority as obedience to a person or to a law.

To obey is better than sacrifice.

He who obeys only can command or rule.

The man who commands efficiently must have obeyed others in the past and the man who obeys dutifully is worthy of being some day a commander

From obedience spring all other virtues.

True obedience neither procrastinates nor questions.

Obedience is the mother of success, and is wedded to safety.

Let your child's first lesson be obedience.

Wicked men obey from fear; good men from love.

Command is anxiety; obedience is ease.

Goodness is a river that follows from the lotus feet of the Lord by the path of obedience.

If the heart is not satisfied, obedience is not truly performed by the body.

OPTIMISM

Optimism is the doctrine that everything is ordered for the best. It is a disposition to take a bright, hopeful view of things.

Optimism is the doctrine or view that everything in nature and the history of mankind is ordered for the best, the order of things in the universe being adapted to produce the highest good.

It is the doctrine that the universe is tending toward a better state. It is the disposition to believe that, however things may appear to the contrary, whatever is or occurs is right and good. It is sanguine temperament opposed to pessimism.

Pessimism is the opposite of optimism.

An optimist sees an opportunity in every difficulty; a pessimist sees a difficulty in every opportunity.

There is a bright side to every situation. Adopt a hopeful, confident state of mind. The trouble is half overcome before you start on it.

An optimist gets the best out of life. He hopes the best and makes the best of people and circumstances and thinks the best of people.

Optimism is hope. It is happy life. It saves people.

How can the existence of evil be reconciled with the goodness of God? Optimism solves the question by affirming that evil is the necessary antecedent of good.

Optimism makes you happy and cheerful. The accident is not as terrible as you feared. The hill is not so steep as you thought before you begin climbing. The difficulty is not as great as you expected. Things come out better than you hope.

PATIENCE

Patience is the quality of being patient or able calmly to endure. It is the quality of sustaining pain without repining.

A man of patience is not easily provoked. He is calm and serene even under adverse conditions.

Patience is strength. It is the support of weakness. It is the greatest and sublimest power. Patience can work wonders. It can move mountains. Patient working can achieve anything in this world. It will surmount every obstacle in the search after truth. A patient man can have what he will.

Everything comes if you only will wait. To know how to wait is the great secret of success. Patience lies at the root of all pleasures. Patience develops will-power and the power of endurance.

Patience is not passive. It is indifference. It is concentrated strength. It is the pillar of human peace on this earth.

Patience is a chief ingredient of wisdom. It is the finest and worthiest part of fortitude and forbearance. It is the key of contentment. It is the courage of the conqueror.

Be patient in little things. Learn to bear the daily trials and annoyances quietly and calmly. You will develop great strength and bear severe calamities, privations, sufferings and adversities.

Patience strengthens the spirit, sweetens the temper, stifles anger, develops the will force, extinguishes jealousy, subdues pride, controls the organ of speech, restrains the hand.

Patience is the sister or daughter of fortitude. Patience is genius.

Patience is bitter, but its fruit is extremely sweet.

Patience is the soul of peace. It makes a man divine. The best of men, all the saints, sages, Yogis and Sannyasins had immense patience. It was their ornament or crest-jewel

Patience is a specific remedy for control of anger. It is a penicilin injection to kill anger.

Patience is passive fortitude. It is the habit of mind shown in passive endurance of the evils to which man is liable.

Patience is unflinching, undaunted perseverance. Genius is patience. It is the exercise of unaltering endurance and perseverance in any work or activity or in pursuit of a desired end.

We say: “Ram has patience in study.”

Patience may also have an active force denoting uncomplaining steadiness in doing, as in tilling the soil, removing the shell of “chilgosa”, etc. There is untiring energy.

Endurance hardens itself against suffering and may be merely stubborn. It may be made to have a passive force, as when we speak of “passive endurance.”

Fortitude is endurance animated by courage. Patience is not so hard as endurance, so self-effacing as submission. Submission is ordinary and resignation always applies to matters of great moment, while patience may apply to slight worries and annoyances.

Forbearance is abstaining from retaliation or revenge. Patience is keeping kindliness of heart under vexatious conduct. Long suffering is continual patience.

Patience refers to the quietness or self-possession of one’s own spirit; resignation to his submission to the will of another.

There is patience in or amidst sufferings. There is patience with or toward opposers or offenders. There is patience under affliction. We do not speak of patience of heat or cold or hunger.

In patience there is quiet endurance or forbearance under distress, pain, injury, insult, suspense, calamity, provocation.

A man of patience has a calm, unruffled temper. He has endurance without murmuring or fretfulness or retaliation.

Patience is also the act or quality of waiting for justice or expected good without discontent.

A patient man is not hasty.. He is not overeager or impetuous.

PATIENCE AND PERSEVERANCE

Patience and perseverance are noble qualities that are born of Sattva. No success either in the material world or in the spiritual path is possible without these qualities. These qualities develop the will-power. Difficulties do crop up at every stage and these are to be overcome by patient efforts and perseverance. The success of Mahatma Gandhi was due to these qualities. He never got discouraged by failures. All great persons of the world have achieved greatness and success and eminence through patience and perseverance. You will have to develop these virtues slowly.

A patient man always keeps his head cool. He keeps a balanced mind. He is not afraid of failures and difficulties. He finds out methods to strengthen himself. For the practice of concentration of mind one should have assinine patience. Many people get discouraged when they encounter some difficulities and give up the work as hopeless. This is very bad. Aspirants should not give up their Sadhana when they come across some difficulties.

The ants collect small particles of sugar and rice and store them up in their abode. How patient and persevering they are! In the Bible you will find the words; "Go to the ant, thou sluggard, and observe its ways and be wise." The bees collect a drop of honey from each flower patiently and store the honey in the honey-comb. How patient and persevering they are! How patient are the engineers who construct big dams and bridges over seas and big rivers. How patient was the scientist who found out that diamond was only carbon. See how patient is Sir J.C. Bose in his laboratory when he is making experiments with plants! The saint who is living in the caves of the Himalayas is more patient than these men in his practices of mind-control.

A patient man cannot be irritated even a bit. Patience helps a man in the conquest of temper. Patience gives immense strength. Do all your routine of the day patiently. Slowly develop virtues. Be eager to develop them. Have a mental image of "OM PATIENCE", in your mind. The habit will slowly develop. Meditate on this virtue in the morning. Try to do all actions of the day patiently. Never grumble or murmur. Think of the advantages of patience and I assure you that you will become an embodiment of patience ultimately.

PATRIOTISM

Patriotism is love of and devotion to one's country.

Patriotism is the passion which influences one to serve one's country, either in defending it from invasion or protecting it from invasion or protecting its rights and maintaining its laws and institutions in vigour and purity.

It is the spirit that, originating in love of country, prompts to obedience to its laws, to the support and defence of its existence, rights and institutions, and to the promotion of its welfare.

He who truly loves and serves his motherland is a patriot.

Love of one's country is one of the loftiest virtues.

Your country's welfare is your first concern. He who promotes that best, best proves his duty.

The noblest motive is the public good.

That patriotism which animates and prompts to deeds of self-sacrifice, of valour, of devotion and of death itself—that is public virtue, that is the sublimest of public virtues.

First patriotism. Then comes Vedantism.

PEACE

The peace that passeth all understanding has been, since the remotest times, the axis round which Indian culture has revolved in all its aspects.

Peace is a state of quiet. It is freedom from disturbance, anxiety, agitation, riot or violence. It is harmony, silence, calm, repose, rest. Specifically it is the absence or cessation of war.

Peace is the very nature of the soul, or Atman. All the Vrittis or modifications of the mind are dissolved in the soul. There is no Sankalpa or thought.

Selflessness, desirelessness, non-attachment freedom from I-ness and mine-ness, cravings, devotion to God or Atman, self-restraint, control of senses and mind bring happiness and peace of mind.

National peace comes from goodwill, sympathy, tolerance and right understanding between nations.

Develop cosmic love, kindness, forgiveness; understand the views of others.

Peace is not in the heart of the carnal man. Peace is not in the heart of ministers, advocates, businessmen, dictators, kings and emperors. Peace is in the heart of Yogis, sages, saints and spiritual men.

Peace comes from prayer, Japa, Kirtan, meditation, good and sublime thoughts and understanding.

Peace should be built on right understanding between nations, mutual goodwill, a striving after a common welfare and a higher good.

Speak, move, act in peace. Realise that stupendous peace of God which passeth all understanding.

Nothing can bring you peace but yourself. Nothing can bring you peace but the victory over your lower self, triumph over your senses and mind, desires and cravings.

If you have no peace within yourself, it is vain to seek it in external objects and outward sources.

Greed, lust, jealousy, envy, anger, pride, egoism, are the six enemies of peace. Slay these enemies by the sword of dispassion, discrimination and non-attachment. You will enjoy perpetual peace.

Peace is not in money, estate, bungalows, wealth and possession. Peace does not dwell in outward things, but within the soul. Withdraw yourself from external objects, meditate and rest in your soul. You will realise everlasting peace now.

Peace is a precious jewel. It is a priceless treasure.

Peace is the happy, natural state of man. It is his birthright. War is his corruption; his disgrace; his shame.

The peace of God fills your heart. Realise this Supreme Peace through meditation and devotion.

PERSEVERANCE

Perseverance is continued application to anything which one has begun. It is a going-on till success is attained.

Perseverance is steadfast pursuit or prosecution of a resolution, business or course marked out. It is persistence in purpose and efforts. It is assiduous endeavour.

God is with those who persevere.

If you have perseverance, you can do all that you wish.

The tendency to persevere, to persist in spite of hindrances, discouragements and impossibilities—it is this that distinguishes the strong soul from the weak.

A man of perseverance never meets with failures. He always attains success in all his undertakings.

When you start any work, you should not leave it till you attain complete success. Pursue it resolutely.

A man of diligence, vigilance and strong resolution grows into a genius.

The nerve that never relaxes, the eye that never blenches, the thought that never wanders—these are the masters of victory.

2. Begin **drawing the heaven spiral** by moving the **palm in a clockwise motion**, with the circles getting smaller and smaller, spiraling inward. At the same time, your left hand is held at your side, palm up with thumb and index tips touching each other. Draw seven or nine (planets of our solar system) small spirals with your right hand in this way, drawing in the violet heavenly energy.
3. Next, lower your right hand slightly and turn your left palm down to face the earth. Then begin **drawing the earth spiral** by moving the right palm in a **counterclockwise motion** with the circles getting larger and larger. Draw five spirals (five elements), drawing in the blue earth energy as you move. Inhale into the palm, feeling the energies.
4. You may now bring both hands down to the beginning position of Cosmic Chi Kung, or you may open the Cosmic Channel to the planets for healing. This is discussed in the next section, Part I, ‘Opening to Heaven, Earth and Cosmic Chi’.

Cell Breathing

By understanding the operations of our cells, we establish a foundation for our experience of Cosmic Chi Kung. Each cell is a living, breathing entity, absorbing energy with each inhalation and releasing toxins with each exhalation. Thus with every breath, we are creating more Chi.

We are made up of over one hundred trillion cells (one trillion is one thousand billion). Each one of these cells is constantly breathing. In order for our cells to function optimally, we must follow nature's teachings.

Fig. 8.2 *Each Cell is a Living, Breathing Entity.*

Victory belongs to the most persevering. Perseverance gives power to weakness, and opens to poverty the whole wealth of the world.

With steady perseverance, great difficulties come to an end.

'Continue' denotes 'to do as one has done hitherto'; 'to persevere' is to continue in a given course, from a desire to obtain an object; 'to persist' is to continue from a determination of will not to give up.

PHILANTHROPY

Philanthropy is goodwill towards all men. It is love of mankind especially as shown in good deeds and services to others.

Philanthropy is disposition or effort to promote the happiness or social elevation of man as man or of mankind on a large scale.

Philanthropy is desire or effort to mitigate social evils and increase and multiply social comforts, as based on broad and sound views of man's nature and condition. It is comprehensive benevolence, but often specified in its objects. It is active humanitarianism. It is love of the entire humanity. It is goodwill to all men shown by kindly actions.

He who tries to benefit mankind is a philanthropist.

A true philanthropist lives not for himself but for the world. He has a generous feeling for the welfare of the whole world.

A philanthropist is characterised by kindness to one's fellow-beings. He works for the good of mankind. He is benevolent. He is a humanitarian.

PITY

Pity is a feeling for the sufferings of others. Where pity dwells, the peace of God is there.

It is the feeling of grief or pain, awakened by trials, misfortunes or distresses of others, joined with a desire to help or relieve. It is sympathy with the suffering of others, inclining to help.

Sympathy (feeling or suffering with) implies some degree of equality, kindred or union. Pity is for what is weak or unfortunate and so far, at least, inferior to ourselves; hence pity is often resented where sympathy would be welcomed.

We have sympathy with one in joy or grief, in pleasure or pain, pity only for those in suffering or need. We may have sympathy with the struggles and triumphs of a conqueror; we are moved with pity for the captive or the slave.

Pity may be only in the mind, but mercy does something for those who are its objects.

Compassion, like pity, is exercised only with respect to the suffering or unfortunate; but combines with the tenderness of pity, the dignity of sympathy and the active quality of mercy.

Commiseration is as tender as compassion, but more remote and hopeless. We have commiseration for sufferers whom we cannot reach or cannot relieve.

Condolence is the expression of sympathy.

Barbarity, brutality, cruelty, ferocity, hard-heartedness, harshness, inhumanity, mercilessness, pitilessness, ruthlessness, are the opposites of pity.

PLUCK

Pluck is courage. Pluck is spirit. Pluck is confidence and spirit in the face of difficulties. Pluck is undismayed energy and resolution.

Pluck is endurance. Pluck is resolution in the face of difficulties.

A man of pluck can achieve great results.

When your luck is out, put a ‘p’ before it. You can start a fresh life now and attain anything you want!

President Chadbourne put pluck in place of his lost lung and worked thirty-five years after his funeral had been arranged.

PLUCK OR KNACK

This quality is most essential for a businessman as for any other man. Knack is dexterity or adroitness. When a man flourishes in business, people say: “Mr. Banerjee has got good business knack. He has got the pluck.” Aptitude is another term which is synonymous with pluck or knack. Politeness, courtesy, good behaviour, are all hidden in this quality ‘pluck.’ When any man enters a shop for some purchase, the salesman has to approach him with great gentleness and address him politely:

"Well, Sir, could I do anything for you? Kindly take your seat here, Sir. Will you have some tea or a cold drink?" A rough and rude man cannot prosper in business. Gushing nature is also hidden in business.

A man of business knack is very careful in his accounts. He has a good memory. He knows the current market prices of all goods. He knows economy with efficiency. He knows the places from where he can get things at very cheap rates. He knows how to advertise. He has presence of mind. He is not afraid of failure or loss. He will make it up very quickly by starting some other side-line. The mind of a businessman who has pluck is always very inventive. A man of pluck is very intelligent.

Doctors and lawyers also want this pluck if they wish to become very successful practitioners. Some people are born with knack. You can also develop it in no time if only you will. A man with pluck or gushing nature can work wonders in the world. Even religious preachers are in need of knack. Then alone can they influence people and spread their teachings far and wide. Sri Sankara was very aggressive. He formed an army of Naga Sadhus for fighting against the Buddhists. Guru Govind Singhji had great pluck and a remarkable pushing nature. Though he was a spiritual man, he had the martial spirit. Religious teachers have to adopt various methods of work according to the times, conditions and needs.

POLITENESS

Politeness is refinement of manners. It is good breeding. It is polished, smooth, refined nature.

Politeness is ease and gracefulness of manners. It is polish or elegance of manners. It is gentility, good breeding.

Politeness moderates and softens your sentiments. It is an easy virtue, costs little and has great power.

Politeness is the flower of humanity. It consists of treating others just as you love to be treated yourself.

A polite man is loved and respected by all. It brings good name.

Politeness is a mixture of courtesy, discretion, civility, complaisance and circumspection.

Politeness tells not only on the manners, but on the mind and the heart. It renders the feelings, the opinions and the words moderate and gentle.

Politeness is kindness kindly expressed. Put it in practice daily. Be polite. All will be charmed with your manners.

A polite man is agreeable and pleasant.

Politeness is the result of good sense and good nature. It makes one a perfect gentleman.

Politeness is a mirror in which every one shows his own image. Politeness is good nature regulated by good sense.

Politeness requires humility, good sense and benevolence.

Politeness is kind feeling toward others. It is the result of good sense, some good nature and some self-denial for the sake of others.

There is politeness of the heart. Politeness of outward behaviour springs from the politeness of heart.

A polite man exhibits in manner or speech a kindly regard for the comfort or happiness of others. He is polished and courteous in behaviour. He is polished in language.

Politeness is polish or elegance of manner, courtesy or complaisance in speech.

Affability, amenity, civility, courtesy, complaisance, courteousness, comity, courtliness, decorum, elegance, gentility, polish, refinement, urbanity, suavity are synonymous with politeness.

Arrogance, coarseness, discourtesy, impertinence, impoliteness, impudence, uncivility, insolence, rudeness, rusticity, sauciness, boorishness, bruskness, clownishness, uncouthness are the opposites of politeness.

A polite man observes such propriety of speech and manner as to avoid being rude. He observes more than the necessary proprieties, conforming to all that is graceful, becoming and thoughtful in the intercourse of refined society.

A man may be civil with no consideration for others, simply because self-respect forbids him to be rude, but one who is polite has at least some care for the opinions of others. If he is polite in the highest and truest sense he cares for the comfort and happiness of others in the smallest matters.

'Civil' is a colder and more distant word than polite.

'Courteousness' is fuller and richer, dealing often with greater matters and is used only in a good sense.

'Genteel' refers to an external elegance which may be showy and superficial. It is inferior to politeness and courtesy.

'Urbane' refers to a politeness that is genial and successful in giving others a sense of ease and cheer.

'Polished' referes to external elegance of speech and manner without reference to spirit or purpose.

'Cultured' refers to a real and high development of mind and soul, of which the external manifestation is the smallest part.

'Complaisance' denotes a disposition to please or favour beyond what politeness would necessarily require.

'Politeness' denotes ease and gracefulness of manners and a desire to please others by anticipating their wants and wishes and avoiding whatever might give them pain.

Courtesy displays itself in the address and manners. It is shown more especially in receiving and entertaining others and is a union of dignified complaisance and kindness.

PROMPTNESS

Promptness is readiness and quickness of decision and action. It is alacrity.

Promptness is favourable to fortune, reputation, influence and usefulness.

Promptness is the soul of business.

A man of promptness at once plans, resolves, executes and succeeds.

Promptness is your duty. It is a part of good manners.

Time is most precious. Know the true value of time. Snatch, seize and enjoy every moment of it. Utilise every second profitably and usefully. No idleness, no delay, no procrastination. Never put off till tomorrow what you can do today.

Be prompt in giving reply to your letters. This will produce a very deep and good impression on those who receive your reply.

PRUDENCE

Prudence is a universal virtue. It enters into the composition of all the rest. Where there is no prudence, fortitude loses its name and virtue.

Prudence is a necessary ingredient in all the virtues. It is the pivot on which many virtues turn. Prudence will protect you.

Prudence is the habit of acting with deliberation and discretion. It is principally in reference to actions to be done and due means, order, season and method of doing.

Prudence differs from wisdom only in degree. Wisdom is more consummate habit of prudence. Prudence is a lower degree or weaker habit of wisdom.

Folly, audacity, foolhardiness, foolishness, heedlessness, imprudence, indiscretion, rashness, recklessness, thoughtlessness, unwaryness, are the opposites of prudence.

Prudence is wisdom applied to practice. A prudent man is cautious and wise in conduct. He is careful. He is discreet. He is dictated by forethought. He is frugal.

Prudence is the best safeguard. Sensible men often learn from their enemies. That man is prudent who neither hopes nor fears anything from the uncertain events of the future. Happy is that man who learns prudence from the doings and experiences of others, as he does not purchase it by personal suffering.

A prudent man takes care to avoid practical mistakes or entanglements. He is cautious. He is endowed with circumspection. He has good judgement and foresight, in practical affairs, He is economical. He has consideration. He has foresight, forethought, judgement, judiciousness and wisdom. He watches, guards and saves. As he has forethought, he thinks in accordance with the wise views of the future.

A prudent man is habitually careful to avoid practical errors and to follow the most profitable course. He is worldly wise also. He is very attentive to his own interests. He exercises sound judgement. He is wisely thoughtful. He is careful and judicious. He foresees evil and hides himself. He has practical wisdom. He is sagacious.

A prudent man is cautious or circumspect in determining on or adopting an action or line of conduct. He is careful of the consequences of any measures, actions or business undertaken.

It would be the point of prudence to defer forming one's ultimate irrevocable decision so long as new data might be offered.

Hear the words of prudence. She will guide you in the right path. She will give you wise counsels. Give heed unto her counsels. Store them in your heart. Follow them cautiously. All the virtues lean upon her.

Learn wisdom from the experiences of others. Correct your faults from their failings. Have foresight. You will never be in want or trouble. Use not today what tomorrow may want.

Cultivate prudence to a maximum degree.

PUNCTUALITY

Punctuality is the keeping of the exact time of an appointment.

A punctual man is scrupulously exact in keeping time, engagements and appointments.

Punctuality is faithfulness to a time promised.

A man of punctuality is observant and exact in points of time, as in working hours, appointments and the like. He arrives promptly on occasions as relating to a fixed time.

Punctuality is the stern virtue of men of business and great men.

A man of punctuality is always succeessful in life.

Better be two hours too soon than one moment too late.

When a Secretary of Washington, excusing himself for being late, said that his watch was too slow, the reply of Washington was "You must get a new watch, or I must get a new Secretary."

The most indispensable qualification of a doctor, a cook, an officer, a Professor, is punctuality.

I have always been half an hour before my time. This is the secret of my success.

Strict punctuality is the cheapest virtue. Want of punctuality is a want of virtue.

The vast majority of persons are indolent by nature and habit. It is very difficult to find a man of real, undeviating punctuality.

Method is the very hinge of business and all important works. There is no method without punctuality.

"Better late than never" is not half so good a maxim as "Better never late."

Be punctual. You will have success in all undertakings.

PURITY

Purity is freedom from sin or defilement. Purity is chastity in thought, word and deed. Purity is freedom from lustful, sexual thoughts. It is moral cleanness.

Purity (Saucha) is of two kinds—internal purity and external purity. Freedom from Raga-Dwesha, purity of intentions, purity of motives, and purity of Bhava, constitute internal purity. Purity of body through bath, etc., purity of clothes, purity of surroundings like the house and its neighbourhood, constitute external purity.

Purity is the main part of virtue. Purity lives and derives its life solely from the spirit or soul.

Your soul is Nitya Suddha (eternally pure). Through your contact with the mind and the senses, you have become impure. Regain your original purity through, Japa, Kirtan, prayer, meditation, enquiry of 'who am I', the practice of Pranayama, Study, Satsanga and Sattvic food.

Without purity, no spiritual progress is possible. Atman is purity. You should attain this ever-pure Atman through the practice of purity, through the virtue purity, through Brahmacharya in thought, word and deed.

I pray: "O adorable Lord! Make my mind pure. Free me from all impure thoughts. Make my mind as transparent as a crystal, pure as the Himalayan snow, brilliant as the shining mirror."

What greater undertaking lies before you than purifying your life of all enmity, impurity, hartred, lust and filling it with love, purity, peace and goodness?

PUSHING NATURE

Pushing nature is also called 'gushing nature.' That is the opposite of shyness. The man is aggressive. He tries to penetrate into all places like ether. Some doctors and advocates are starving. Why? Because they have not got this pushing nature. They are very intelligent and clever, but unfortunately they are so incorrigibly shy. They cannot influence other people. The man of gushing nature can talk sweetly and is very adventurous. He is very very bold.

A man of pushing nature is very active. He knows how to please other people and win others' hearts. He knows how to serve people and to get into their confidence. He creates work for himself. He cannot remain idle. He always plans, schemes, and speculates. He wants to rise up in the ladder of fortune and in the estimation of the world. He is of a very joyous nature. Very jovial and can mix with all. He knows how to adjust himself with other people of different temperaments. Pushing nature is necessary for success in life and God-realisation. You will have to cultivate it to the maximum degree. Desire fervently to develop this habit and try your best to make it your intimate friend. Then your other intimate friend, the sub-conscious mind and the Will, will do the work for you. Have a clear mental image of the thing you want. That is all that is needed.

Europeans have this nature in a large measure. Englishmen came in the biginning to India as mere traders and started the East India Company. Then slowly and slowly they became the rulers of this soil only through their pushing nature. People of Malabar have got this pushing nature. You can find Malabaris in every nook and corner of this fair earth. Vasco Da Gama had this pushing nature. He discovered a sea-route to India. So did Colombus who discovered America. The people of Japan are remarkable for their pushing nature. That is the reason why they have risen to prominence in so short a time. Japan is a small piece of land. They compete in the field of industry and commerce with almost any other country in the world.

Pushing nature keeps a man always active and is useful for the religious aspirant too. Business people should possess this quality to an enormous degree. This is an important qualification for all.

REGULARITY AND PUNCTUALITY

No man can reasonably expect success in life and God-realisation if he does not possess these two qualifications. Perfect discipline can only be maintained by regularity and punctuality. There cannot be any success without discipline. Discipline is an enemy of mind. The mind is very terribly afraid when it hears the terms discipline, regularity, Tapas, Vairagya, renunciation, Sadhana etc. These practices bring death of the mind or Manonasa.

Man evolves quickly by regular practices. He who meditates regularly gets Samadhi quickly. He gets the meditative mood easily without any exertion. He who does physical exercises regularly gets rapid development of body. That man who is irregular and does his actions by fits and starts cannot reap the fruits of his efforts.

Learn your lessons from nature. Mark how the seasons rotate regularly! Mark how the sun rises and sets, how the monsoon comes, how the flowers blossom, how the fruits and vegetables crop up, how the revolution of the moon and the earth take place, how the days and nights, weeks and months and years roll on! Nature is your Guru and guide. The five elements are your preceptor and teacher. Open your eyes and receive instructions and follow.

Regularity and punctuality and discipline go hand in hand. They are inseparable. College and school students in India imitate the West in fashion, style, cropping the hair etc. These are all vile imitations. Have you imbibed from them the important virtues such as punctuality and regularity? See how an Englishman adjusts his time to the very second! How very punctual he is! The number of specialists and research scholars is larger in the West than in India. There may be a few geniuses in India like Tagore, Bose, Aurobindo and a few sages and Yogis. But there are innumerable specialists and scholars in the West. They are more studious, regular and punctual than the Indians. They are reputed for this one qualification viz., punctuality. A European manager does not like his clerks if they are unpunctual. He will issue immediate notice to that man who is not punctual. That man who is regular and punctual will get sure success in all departments of life. There is no doubt of this.

Indians are famous for their "Indian punctuality." If there is an announcement in the newspaper that there will be a meeting in the Town Hall at 4 p.m. Indians will slowly begin to gather at 5.30 p.m. only. This is what is known as Indian punctuality. If there is an announcement in the notice that there will be a Kirtan at night at 8 o'clock people will come at 9-30 only. If there is a difference of a few minutes it does not really matter. I have had enough experiences in my Sankirtan and lecturing tours.

The first thing is to keep your cells free of toxins. Eat nutritional foods. This helps the Chi to flow smoothly through your energy channels and aids greater assimilation of vitamins and minerals. Learn and apply Five Element nutrition principles, eating according to the seasons and to your own constitution.

The second thing is to keep your cells free of excess emotions. Develop the skill of acting positively to situations, rather than reacting, especially negatively. Don't allow anyone to make you sad and unhealthy. Some people like to say, "You make me angry," or "You made me worry." We cannot allow other people to make us so emotional. We do not need to accept the negative emotions that other people try to dump on us. Cellular and psychic boundaries are related. Negative emotions disturb the cells' ability to absorb Chi and to generate the energy necessary for healing. We need all the Chi that we can get. Learn and apply the Six Healing Sounds, the Cosmic Inner Smile and the Fusion of the Five Elements meditation to transform negative emotions into personal power.

Third, create more energy by cultivating a happy attitude, so that your cells can regenerate more easily. **Smiling and loving** are the two quickest ways to make more Chi. In order to have an ample supply of Chi, develop an attitude of **joy and love** in yourself and towards others.

Mind, Eyes, Heart and Intention (YI)

The opening of the mind, eyes, heart and use of intention is vital for further activating and increasing your Chi. In the Tao we achieve this by cultivating our "Yi" (pronounced "yee"). "Yi" means mind power, intention, awareness and concentration. The Yi leads and guides the Chi. With our mind we control thought patterns. With our eyes we control the senses of sight, hearing, smell and taste. With our heart we control all our organs and their related emotions: the kindness/anger of the liver, the joy/impatience of the heart, the openness/worry of the spleen, the courage/sadness of the lungs and the gentleness/fear of the kidneys.



***Fig. 8.3** 'Yi' leads and guides the Chi.*

Indians should be ashamed now of their defect and should try to rectify it soon. Wake up Indians, wake up!

The one important qualification that gave success in my life is this one important virtue, punctuality. Even Europeans used to admire my punctuality. I used to be very punctual wherever there was appointment. It produced a greater impression. I never missed trains. I was always punctual at the station. An unpunctual man misses always his trains. He fails in his business. He loses all his customers. The professor dislikes students who are unpunctual. If a man fails to attend the courts punctually of course he has to lose his case.

Have regular habits in all walks of life. Be regular in going to bed and in rising up early in the morning. "Early to bed and early to rise makes a man healthy, wealthy and wise." Be very regular in your meals always. Be regular in your studies, in your physical exercises, in your meditation etc., and you will have a very successful life and a happy one too. Regularity should be your watch-word.

RENUNCIATION

Immortality or Self-realisation is attained through Tyaga or renunciation alone.

Renunciation strengthens the mind and the will and bestows peace.

Renounce the objects. This is Vishaya-tyaga. Renounce attachment to the objects. This is Sanga-tyaga. This is mental discipline.

Without Tyaga, not an iota of spiritual progress is possible.

The secret of renunciation is the renunciation of egoism, mine-ness, Vasanas and Trishnas, subtle desires and cravings, the Bheda-Buddhi that differentiates, and the Kartritva-Abhimana, doership or agency.

Complete renunciation does not come in a day. It takes a long time.

Satsanga with saints and sages, study of books which treat on Vairagya and Tyaga such as "Necessity for Sannyasa", etc., are aids in the practice of renunciation.

He who has renunciation is the real King of kings, Emperor of emperors.

Renunciation is the greatest force on this earth.

REPENTANCE

Repentance is contrition for sin, producing newness of life. It is remorse for past, sinful conduct.

Repentance is a turning with sorrow from a past course. It is sorrow for something done, with desire to make things right by undoing the wrong and doing the right.

Repentance is the destroyer of sins. It purifies the heart. Every tear has a cleansing virtue.

Repentance creates a movement toward a new and better life. It has a tremendous purifying power.

True repentance is to cease from sinning.

Repentance is sorrow or grief, on account of some wrong actions or past misdeeds.

Repentance is a heavy sorrow for past evil actions and a sincere resolution and endeavour to the utmost of our power to conform all our actions to the law of God.

Repentance without a change of heart and conduct, without amendment, is of no use.

Death-bed repentance will not produce any tangible effect.

There must be repentance with a contrite or penitent heart. There must be a sincere and thorough changing of the mind and disposition in regard to sins. Otherwise, it is of no avail.

Repentance is sorrow for sin with self-condemnation and complete turning away from the sin.

Penitence is transient and may involve no change of character or conduct.

Remorse is a biting or gnawing back of guilt upon the heart, with no suggestion of divine forgiveness.

Regret is sorrow for any painful or annoying matter. One is moved with penitence for wrong-doing.

There may be sorrow without repentance, as for consequences only, but not repentance without sorrow.

Contrition is a subduing sorrow for sin, as against divine holiness and love.

Self-congratulation, self-complacency, self-approval, impatience are the opposites of repentance.

RESOLUTION

Resolution is fixed determination. It is steadiness. It is constancy or fixed purpose.

A man of resolution is determined. He has a fixed purpose. He is constant in pursuing a purpose. He is unshakably firm and steady. He is bold and unflinching. He is a man of resolute will. He has steadiness of purpose and firmness in adhering to it, especially in the face of dangers or difficulties. He has active fortitude.

He who is firm and resolute in will attains success in all undertakings. Failure is unknown to him.

Put on the dauntless spirit of resolution. March on, hero! Your efforts will be crowned with sanguine success. All obstacles will be removed at once.

Resolution is omnipotent. A man of resolution scales all barriers which stand in his way. All difficulties vanish for him. Courage, steady perseverance, fortitude and strength are the companions of resolution.

A man of resolution has the nerve which never relaxes, the eye which never blenches, the thought which never wanders, the purpose that never wavers. He always attains victory.

Resolution is your soul help in need. Be fixed and resolute. March on steadily. Gird up your loins. Persevere. You can conquer the whole world.

A man of resolution pulverises the Himalayas, swallows the fire and drinks the waters of the ocean in a minute. He can accomplish anything in the three worlds in the twinkling of an eye.

Even if the whole world opposes him, he marches forward with undaunted spirit.

All great men who have achieved greatness and who have accomplished superhuman deeds in this world possessed resolution.

Wherein there is resolution, there is the dynamic, irresistible, strong will. Resolution and strong will, go hand in hand.

Be resolute. Stick to resolves. Strengthen your resolves. You will develop your will.

RESOURCEFULNESS

Resourcefulness is means of any kind.

A man of resourcefulness is fertile in resources or expedients or contrivances. He is skilled in methods of efficiency. He possesses abundant means.

That which is resorted to, relied upon or made available for aid or support is resource.

An expedient to which one may resort for aid or safety is resource.

We speak of "a business resource;" "a woman's resource is patience;" "a country of inexhaustible resources;" "Rama has a resourceful brain. He can deliver lectures on anything at any time without any preparation;" "Sri Vyasa tried the resources of philosophy."

Resources are—pecuniary means, funds, money or any property that can be converted into supplies; means of raising money or supplies; available means or capabilities of any kind; as "In the Russo-Japanese war the resources of Russia were several times more than those of Japan."

He who has a resourceful brain can become the General of an Army, the Admiral of a Navy, the inventor of scientific instruments.

RIGHT CONDUCT

Ethics or ethical science treats about Sadachara or right conduct or morality or duty. Ethics is the science of morals, that branch of philosophy which is concerned with human character and conduct.

Conduct is behaviour. Deportment, carriage, demeanour, conduct and behaviour are synonymous terms. The way in which rational beings should behave towards each other as well as towards other creatures is dealt with in the science of morals or ethics.

To speak the truth, to practise Ahimsa, not to hurt the feelings of others in thought, word and deed; not to speak harsh words to any one; not to show any anger towards anybody; not to abuse others or speak ill of others and to see God in all beings is Sadachara. If you abuse anyone, if you hurt the feelings of others, really you are abusing yourself and hurting the feelings of God only. Himsa is a deadly enemy of Bhakti and Jnana. It separates and divides. It stands in the way of realising unity or oneness of Self.

That act or exertion which does not do good to others, or that act for which one has to feel shame, should never be done. That act on the other hand, should be done, for which one may be lauded in society. This is a brief description of what right conduct is.

Lord Manu says in his Smriti, "Achara (good conduct) is the highest Dharma, declared by the Smriti and the Sruti. Therefore let the twice-born that knoweth the Self ever diligently engage therein. Thus beholding the path of Dharma issue from Achara, the sages embrace Achara as the root of all Tapas."

Righteousness, truth, good works, power and prosperity all originate from conduct. You will find in the Mahabharata "The mark of Dharma is Achara (good conduct). Achara is the mark of good. Higher than all teachings is Achara. From Achara Dharma is born; Dharma enhances life. By Achara man attains life; by Achara he attains prosperity, and by Achara he attains fair name, here and hereafter. He who is the friend of all beings, he who is intent on the welfare of all with act, thought and speech—he only knoweth Dharma!"

Dharma is extremely subtle (Ati Sukshma), intricate and complex. Even sages are perplexed. Dharma gives wealth, satisfaction and liberation in the end. Dharma tops the list of the four Purusharthas viz., Dharma, Artha, Kama and Moksha. Dharma is generally termed as 'Duty,' 'Righteousness' etc. Any action that is best calculated to bring Sreya (Moksha) is Dharma. That which brings well-being to human beings is Dharma.

All that is free from any motive of injury to any being is surely morality. For indeed the moral precepts have been made to free the creatures from all injuries. Dharma is so called because it protects all. Indeed morality saves all creatures.

The conduct is the root of prosperity. Conduct increases fame. It is conduct which prolongs life. It is conduct which destroys all calamities and evils. Conduct has been said to be superior to all the branches of knowledge. Knowledge is power; but character is better power.

It is by conduct that one acquires a long life, and it is by conduct that one acquires riches and prosperity. It is a means to attain the goal of life. Without good conduct no one can achieve the goal. Good conduct brings in fame, longevity, wealth and happiness. It eventually leads to Moksha. It is conduct that begets virtue, and it is virtue that prolongs life. Conduct gives fame, long life and heaven. Conduct is the most efficacious rite of propitiating the celestials. The self-create Brahma Himself has said, "That one should show mercy to all orders of men."

Virtue is singled out by conduct. The good and virtuous are so on account of the conduct they follow. The marks again of good conduct are afforded by the deeds of those that are good or righteous. Indeed, it is by conduct that one acquires fame that depends upon great deeds both in this world and next. Forsooth, one may, by his conduct alone, conquer the three worlds. There is nothing which virtuous persons cannot obtain. A person of good deeds and good, pleasant and sweet speeches has no peer. People have great regard for that man who acts righteously and who does good acts even if they only hear of him without actually seeing him.

The man whose conduct is improper or wicked never acquires long life. All creatures fear such a man and are oppressed by him. If, therefore, one wishes his own advancement and prosperity, one should in this world, follow the path of righteousness and conduct himself righteously. Good conduct succeeds in removing the inauspiciousness and misery of even one who is sinful.

The man of right conduct has ideals, principles and mottoes. He strictly follows them, removes his weaknesses and defects, develops good conduct and becomes a Sattvic man. He is very careful in behaving with his elders, parents, teachers, Acharyas, sisters, brothers, friends, relatives, strangers and other creatures. He attempts to know what is right and what is wrong, by approaching Sadhus and Mahatmas and studying scriptures very carefully and then treads with joy the path of righteousness or Dharma.

The man of right conduct always cares for the welfare of all beings. He lives in harmony with his neighbours and all people. He never hurts the feelings of others, and never speaks lies. He practises Brahmacharya. He checks the evil tendencies of the mind and prepares himself through the practice of right conduct to attain the bliss of union with Paramatma or Self.

An aspirant went to Veda Vyasa and said: "Oh Maharshi, Avatara of Vishnu, I am in a dilemma. I cannot properly comprehend the right significance of the term 'Dharma.' Some say it is right conduct. Others say that, that which leads to

Sreya (Moksha) and happiness is Dharma. Anything, any action that brings you down is Adharma. Lord Krishna says 'Even sages are puzzled to understand perfectly what is Dharma? What is Adharma? *Gahana Karmano Gatihi*—mysterious is the path of action.' I am bewildered Oh Maharshi, kindly give me a very, very easy definition of Dharma to enable me to follow Dharma in all my actions." Maharshi Vyasa said "Oh aspirant! hear me, I shall suggest an easy method. Remember the following sayings with great care when you do any action. Do as you would be done by. Attend to this carefully. You will be saved from all troubles. If you follow these wise maxims, you can never give pain unto others. Practise this in your daily life. Even if you fail one hundred times, it does not matter. Your old Samskaras, Asubha Vasanas are your real enemies. They will come in the way as stumbling blocks. But persevere. You will succeed in the attainment of the Goal." The aspirant strictly adhered to Vyasa's instructions and attained liberation.

This is a very good maxim. The whole gist of Sadachara or right conduct is here. If one practises this very carefully, he will not commit any wrong act. To work in accordance with the Divine will is right; to work in opposition to the Divine will is wrong.

God, Religion and Dharma are inseparable. All human beings are characterised by righteousness and they in course of natural progress and improvement attain to the dignity of God. Man evolves through practice of Dharma according to his caste and order of life and eventually attains Self-realisation, the ultimate goal of life, which brings infinite Bliss, Supreme peace, unbroken joy, highest knowledge, eternal satisfaction and Immortality. Ethical perfection is a pre-requisite to Self-realisation.

Metaphysics rests on Morality, Morality rests on Metaphysics. Morality has Vedanta as its basis. The Upanishad says, "Thy neighbour, in truth, is thy very Self and what separates you from him is mere illusion." Sadachara is the basis for the realisation of Atmic unity or oneness of life or Advaitic feeling of oneness everywhere. Ethical culture prepares you for the Vedantic realisation of "*Sarvam Khalvidam Brahma*—All indeed is Brahman. There is no such thing as diversity."

GLORY OF RIGHT CONDUCT

A man who has attained ethical perfection by the continued practice of Right Conduct or Yama and Niyama has got a magnetic personality. He can influence millions. Character gives a strong personality to man. People respect a man who has good character. Moral people command respect everywhere. He who is honest, sincere, truthful, kind and liberal-hearted always commands respect and influence at the hands of all people, Sattvic virtues make a man divine. He who speaks truth and practises Brahmacharya becomes a great dynamic personality. Even if he speaks a word there is power in it and people are magnetised. Character-building is of paramount importance if a man wants to develop in personality. No development of a strong personality is possible without celibacy.

A man may die but his character remains. His thoughts remain. It is the character that gives real force and power to man. Character is power. Without character the attainment of knowledge is impossible. That man who has no character is practically a dead man in this world, he is ignored and despised by the society. If you want success in life, if you want to influence others, if you want to progress well in the spiritual path, if you wish to have God-realisation, you must possess an unblemished or spotless character. The character of a man survives or outlives him. Sri Sankara, Buddha, Jesus and other Rishis of yore are remembered even now because they had wonderful character. Character is a mighty soul-force. It is like sweet flower that wafts its fragrance far and wide. A man of noble traits and good character possesses a tremendous personality. Personality is character only. A person may be a skilful artist, clever songster, an able poet or a great scientist, but if he has no character he has no real position in the society.

You must be polite, civil and courteous. You must treat others with respect and consideration. “Good manners and soft words have brought many a difficult thing to pass.” He who gives respect to others gets respect. Humility brings respect by itself. Humility is a virtue that subdues the hearts of others. A man of humility is a powerful magnet or loadstone.

Note carefully how the Rishis of yore gave instructions to their students when they have finished their course of study. “Speak truth. Do your duty. Do not neglect the study of Vedas. Do not swerve from truth and duty. Do not neglect your welfare and prosperity. Do not neglect the learning and teaching of Vedas. Do not neglect the duties towards God and forefathers. May the mother be thy God (*Matru Devo Bhava*). May the father be thy God (*Pitru Devo Bhava*). May the preceptor be thy

God (*Acharya Devo Bhava*). Do such actions as are blameless and not others. Those Brahmins that are superior to us, they should be comforted by thee with seats, etc. Give with faith. Do not give without faith. Give with joy, with modesty, with fear, with kindness."

Righteousness is eternal. Do not leave the path of righteousness even if your life is in danger. Do not leave righteousness for the sake of some material gain. A virtuous life and a clean conscience give great deal of comfort to man while living and at the time of his death also. A holy man with piety is far superior to the mighty potentate. God is much pleased with a pious man. Lord Krishna says "Even if the most sinful worshippeth Me, with undivided heart, he too must be accounted righteous, for he hath rightly resolved." There is a great hope even for a cut-throat, if he makes a strong determination and takes up the spiritual path.

Dear friends: Do your duties in a satisfactory manner in accordance with Sadachara. Apply yourselves diligently to all kinds of your daily duties. Consult the Sadacharis and Mahatmas whenever you are in doubt. Build up your character. This will give you success in life. Struggle hard daily to remove old evil habits. Establish daily virtuous healthy habits. Character will help you to attain the goal of life. Character is your very being. Struggle hard to practise Sadachara. Stick to Sadachara with leech-like tenacity. Practise it and realise Sat-chit-ananda state right now in this very second. May character confer on you the Atmic Bliss and Self-realisation! May Joy, Bliss, Immortality and Peace and poise abide in you for ever!

RIGHTEOUSNESS—THE BREATH OF LIFE

Righteousness is the Kalpa-Vriksha on which the fruits of peace, happiness and prosperity grow in abundance. The righteous men are happy here. They enjoy the satisfaction of having lived a life in accordance with the Divine Law of Dharma. Righteousness is the fire that reduces the Samsara wood-pile into ashes within the twinkling of an eye. The righteous man is liberated here and now.

Be righteous. You will enjoy both Bhukti (prosperity, happiness) and Mukti (Liberation). Righteousness takes you nearer to God. When you lead a life of strict righteousness, you live in constant communion with God; for God is righteousness.

The unrighteous man knows no peace nor happiness. *Satyameva Jayate Na Anritam.* An unrighteous man is doomed to failure and abject misery. His lot is pitiable indeed. His life is full of anxiety, fear, remorse and regret. He can never find happiness here; for his happiness depends on illusory objects here. Happiness is the other half of righteousness; where there is righteousness there happiness resides, too.

Ascend the ladder of Truth and reach the summit of Truth Absolute. Light the candle of Love and behold the Supreme Lord of Love, Who resides in every heart. Wear the garment of purity and enter the Kingdom of the Ever-pure Atman. Breathe the air of unity and attain union with the Supreme One, the All-pervading Brahman.

That is the purpose of your life on earth. That is the purpose for which you have taken this human birth; not to eat, drink and make merry. Every moment is precious. Every moment rolls silently by and drops into the ocean of eternity; you cannot recall it. Live well. Love all.

Universal love is the very foundation of righteousness. Selfless service is the corner-stone. Dispassion, discrimination, cultivation of virtues, and a strong yearning for liberation are the pillars. The superstructure is eternal happiness, peace, prosperity and immortality. In this temple is the Supreme Lord enshrined. Adore Him there. You will soon attain Him.

It is only when you are convinced that true happiness can be had only in God and not in the objects of this world that you can really be righteous. This is not pessimism. This is glorious optimism. You will sometimes get your cherished objects of enjoyment; you will later on lose them, and often you may not get them at all! Not so is the case with God. He is your very Self. He is nearer to you than your jugular vein. He is closer to you than your life-breath. You can never be without Him. If you realise that happiness can be had only in Him, and if you seek His constant communion, you will be ever immersed in bliss. Is this not optimism of the highest order?

What have you to do to get this happiness? You will have to be indifferent towards the objects of the world. This is not a loss to you. Is it a loss to throw a bug out of your bed? Is it a loss to pull out a thorn that has entered your foot, and to throw it out? To renounce craving for sensual pleasure is itself a great joy. From such a renunciation springs righteousness.

Every excellent achievement in our lives depends upon the quality and efficient operation of our Yi. Combining the awareness of the mind, eyes, heart and intention into one, causes the creation of a rich and rare alchemical mixture. The power of the Yi is the magical catalyst that assures energetic results.

The basic teachings are all in the Microcosmic Orbit, the Cosmic Inner Smile and the Six Healing Sounds. As long as you are alive and healthy, you are able to draw in energy from the universe and nature. The stronger the battery, the better it is able to store this energy. If you're weak and sick, you have no way to draw any energy from nature or the universe. When the cells stop drawing in energy, life ends. If you have perfected these practices, you have all the personal physical, mental and spiritual power that you need. Everything comes together. Your mind is aware of the original force. From the knowledge of Oneness, you are inwardly aware of your mind, senses and heart; you are outwardly aware of the universal energy. Now you are capable of receiving the abundantly available healing power of the universe; you can tune into everything, inwardly and outwardly in all directions. This is what we are here for: to heal and become whole again. We have higher goals to reach. The foundation for reaching our goals is a strong and healthy body.

Cosmic Healing Chi Kung is merely an extension of the universe within yourself. You draw the universe in through your palms, skin, heart and crown. With your Yi you breathe in the cosmos through these various open cavities of receptivity in your body, absorb its power, condense it, transform it and use it for the benefit of all.

Connecting the Bridge

Contracting the muscles of the perineum, sexual organs and anus activates our connection with the earth energy. By pulling up these areas and drawing in energy through the soles of the feet, we immediately become grounded and bring the earth (yin) energy into the Microcosmic Orbit. Pulling up should be done gently and directed by the Yi.

When we speak of "Connecting the Bridge," we are referring to the above exercise, except that we do not pull up on the perineum. Pull up gently and lightly on the sex organs and anus while leaving the perineum totally relaxed. After performing the first contractions, when you then relax the perineum, the earth energy will continue to flow into the body using the principles of a siphon. We thus connect the "Bridge" across the perineum from the sexual organs to the anus using the Yi to direct the energy. This actively combines the earth energy and your sexual energy and directs it into the Microcosmic Orbit. This energy is circulated during Cosmic Chi Kung. Holding a very gentle contraction will keep you grounded during the exercise. It can be done sitting or standing.

A righteous merchant will not be greedy. He will not hoard. He will not indulge in falsehood, blackmarketing and adulteration. He will see his God in his customers. He will conduct his business in the spirit of worship of this God. Glory, glory to such businessmen. The world is in need of them today.

A righteous employer will look upon his employees as his co-pilgrims on the path to God. He will treat them with love and kindness. He will look after them as he will look after himself. He will see God in all.

A righteous employee will consider that his employer is an Amsa of God Himself. He will serve the employer with faith and devotion.

Every righteous man will strive day and night for the attainment of the goal of his life, viz., God-realisation, and thus contribute to the peace and welfare of the world at large. He will radiate peace. He will work for the welfare of humanity. To such a man even the Devas pay their homage. He is verily a God-on-earth. He is fit to be worshipped by all.

May you all become righteous, pious, noble and wise! May you all shine as Jivanmuktas and Yogis in this very birth! May God bless you all with health, long life, peace, prosperity and Kaivalya Moksha!

SELF-ANALYSIS

Self-analysis is self-examination. It is self-scrutiny through introspection. It is good to check up daily your thoughts, words and actions.

Sum up at night what you have done in the day and in the morning what you have to do.

Keep watch over your thoughts, words and actions. Be vigilant. Be on the alert. Be diligent. Be circumspective.

Finish your daily stock-taking of your thoughts, speeches and actions at night just before you go to sleep.

Daily self-analysis or self-examination is indispensably requisite. Then alone can you remove your defects and can grow rapidly in spirituality. A gardener watches the young plants very carefully. He removes the weeds daily. He puts a strong fence around them. He waters them at the proper time. Then alone do they grow beautifully and yield fruits quickly. Even so, you should find out your defects through daily introspection and self-analysis, and then eradicate them through suitable methods. If one method fails, you must adopt a combined method. If prayer fails, you should take recourse to Satsanga or association with the wise, Pranayama, meditation, dietetic regulation, enquiry etc. You should destroy not only big waves of pride, hypocrisy, lust, anger, etc., that manifest on the surface of the conscious mind, but also their subtle impressions which lurk in the corners of the sub-conscious mind. Then only are you perfectly safe.

These subtle impressions are very dangerous. They lurk like thieves and attack you when you are napping, when you are not vigilant, when your dispassion wanes, when you slacken a bit your daily spiritual practice, and when you are provoked. If these defects do not manifest even under extreme provocation on several occasions, even when you are not practising daily introspection and self-analysis, you can rest assured that the subtle impressions also are obliterated. Now you are safe. The practice of introspection and self-analysis demands patience, perseverance, leech-like tenacity, application, iron will, iron determination, subtle intellect, courage etc. But you will gain a fruit of incalculable value. That precious fruit is Immortality, Supreme Peace and Infinite Bliss. You will have to pay a heavy price for this. Therefore you should not murmur when you do daily practice. You should apply your full mind, heart, intellect and soul to spiritual practice. Then only is rapid success possible.

Keep daily spiritual diary and practise self-analysis (self-examination) at night. Note down how many good actions you have done, what mistakes you have committed during the course of the day. In the morning resolve: “I will not yield to anger today. I will practise celibacy today. I will speak truth today.”

SELF-CONTROL

Self-control is control or restraint exercised over one’s self.

Self-control is the power or habit of having one’s inclinations, and emotions, desires and appetites, senses and mind under control.

Control yourself first. Then you can control others.

Self-control clears the mind, strengthens judgement and elevates your character. It gives you freedom, peace, bliss and joy. It strengthens your will.

He who conquers himself is greater than the commander-in-chief who conquers a country.

Self-control is the master-key that opens the realm of eternal bliss and immortality.

There is no triumph more glorious than that of the victory obtained over your own self.

Control your senses and mind. You will attain Self-realisation.

Obtain self-mastery. Conquer thyself. Till you have done this, you will only be a slave of the senses.

He who is subject to his passions is the worst slave on the surface of this earth. He who rules his passions, desires, cravings and senses is the real king of kings. He is the Supreme Ruler or President of Self-Government. Crowns and sceptres are nothing for him. His is the best Government.

Every temptation that is resisted, every evil thought that is subdued, every desire or craving that is destroyed, every bitter word that is withheld, every wrong action that is checked paves a long way to the attainment of everlasting peace and bliss.

He who can command and govern himself can govern and command others.

Self-control gives you power to withstand trial, to bear suffering and to face danger.

Self-control leads to the highest merit. Self-control is the eternal duty of man. Self-control surpasses in merit charity and study of the Vedas.

Self-control increases your energy. Self-control is highly sacred. Through self-control you will be purified of all your sins, and gifted with energy and character. You will acquire the highest blessedness.

There is no other duty equal to self-control. Self-control is the highest virtue in the world. Through self-control you can enjoy the highest happiness both in this world and in the next. Gifted with self-control you will win great virtue.

The self-controlled man sleeps happily and awakes happily and moves in the world happily. He is always cheerful. Self-control is the best of all vows.

The man who is without self-control always suffers misery. He brings upon himself many calamities, all begotten by his own faults.

Forgiveness, patience, abstention from injury, impartiality, truth, sincerity, control of the senses, cleverness, mildness, modesty, firmness, liberality, freedom from anger, contentment, sweetness of words, benevolence, freedom from malice—all these combined make up self-control.

It also consists of respect for the preceptor and mercy for all. The man of self-control avoids both adulation and slander. Depravity, infamy, falsehood, lust, covetousness, pride, arrogance, fear, envy and disrespect are all shunned by the man of self-control.

He never incurs obloquy. He is free from envy.

That eternal region in Brahman which originates from Vedic penances and which is concealed in a cave can only be acquired by self-control.

The self-controlled man is never fettered by the attachments originating from earthly connections and sentiments.

That is a forest where the man of self-control lives. That is ever a sacred place. Of what use is a forest to a man of self-control? Of what use is the forest to him who has no self-control?

The man of self-control acquires great reward in the next world. He acquires esteem in this world and attains to a high end hereafter. He acquires the state of Brahman. He attains liberation.

SELF-DENIAL

Self-denial is the denial of one's self. It is the non-gratifying of one's own appetites or desires in the interests of one's own higher good, or the welfare of others. It is refusal to gratify self, especially when done with a moral or religious motive.

The more you deny, the more you shall obtain from God, the more you will grow in spirituality.

The first lesson in the Yoga-Vedanta School is self-denial.

Self-denial is necessary for building a strong and noble character. Self-denial is an excellent guard of virtue.

O Adhyatmic hero! O brave conqueror! Practice self-denial. Wage war against your own lower appetites, impulses and desires, and enter into the illimitable domain of eternal bliss and become an Atma-Samrat (Self-King).

The penalty of evading self-denial is just you get the lesser instead of the larger good.

Practise self-denial. Teach self-denial. You can create for the world a better destiny.

The practice of self-denial is the highest education. Wthout it all other education is mere chaff or straw.

Know how to deny yourself. This is the secret of all success.

He who carries on a successful warfare against his own appetites, passions and desires and keeps them under perpetual control is the greatest conqueror or hero.

Abstinence, self-abnegation are synonymous with self-denial.

SELF-EXAMINATION

Self-examination is a scrutiny or enquiry into one's own state, conduct, motives, mental and moral condition and thoughts, etc., especially with regard to one's religious feelings and duties.

Self-examination consists of self-introspection and self-analysis.

Self-examination will lead you to the Knowledge of your own nature. It will improve your heart and correct all your mistakes, defects, weaknesses and faults. It will bestow wisdom on you.

When you are alone, watch your thoughts. Examine your heart. Find out your defects and foibles.

Before retiring to bed, take stock of your thoughts, speeches and acts of the day. Find out "What evil quality have I mastered today?" "What temptations have I resisted?" "Which virtue have I developed today?" "Which Indriya have I controlled?" You will evolve quickly.

SELF-HELP

Self-help is the use of one's own powers and abilities to attain one's ends.

SELF-CONFIDENCE

Self-confidence is the state or quality of having confidence in oneself or in one's own unaided powers, judgement or opinions. Self-confidence is self-reliance. Self-confidence is the attribute of greatness. A man of self-confidence will always attain success and victory.

SELF-RESTRAINT

Self-restraint is the restraint of the lower nature or passions or the senses by the force of one's own will. Self-restraint is restraint over one's appetites or desires. Self-restraint is self-control.

SELF-DISCIPLINE

Self-discipline is discipline of the body, senses and the mind. Through self-discipline, the body, the senses and the mind are brought under one's control. Asanas, Pranayama, Pratyahara, Yama, Niyama, are aids in the practice of self-discipline. The emotions and impulses are kept under perfect control.

SELF-IMPROVEMENT

Exercise thyself. Improve thyself. Know thyself. Fortify your heart with virtuous principles. Discipline your body, senses and mind. Grow daily and evolve quickly.

Enlighten your mind with useful knowledge. Annihilate evil habits, evil thoughts, evil speech and cultivate good habits, good thoughts and good speech.

Talk a little. Hear much. Reflect alone. Hear the wise counsels of sages, saints and Yogis.

Make good resolves. Stick to them tenaciously. Strengthen them.

Waste not time. Time is most precious. Seize spare moments and utilise them to your best advantage. Do Japa. Practise meditation. Study religious books. Cultivate virtues. Increase your earning capacity. Serve the society. Serve your country. Serve elders. Serve teachers. Serve your parents. Serve sick people. Serve the poor. Your heart will be purified quickly.

Look into your own character and conduct. Read your own heart.

Keep the picture of great men and sages before your mind's eye. Remember their teachings and sayings. Follow their ideas. Practise their instructions.

Remove one vicious habit every month and cultivate one virtue every month. You will have quick self-improvement.

Be willing to learn from whatever source possible. Have an open heart.

Whatever you dislike in another person, take care to correct in yourself.

Try to do a thing better today. The only way you can make tomorrow a better day is to think and do today what invites a better tomorrow.

Serve. Pray. Reflect. Cogitate. Meditate. Sing the Lord's glory and name. Think rightly. Speak gently and sweetly. Thus grow, evolve and improve thyself.

SELF-RELIANCE

Self-reliance is reliance on one's own abilities, powers, resources or judgement. Self-reliance is independence, of character.

Rely on your own self. Help thyself and God will help thee.

You will always be poor without your own industry and labour.

God helps those who help themselves.

He who depends upon himself lives happily. He is a man of manly character and wisdom.

Self-reliance constitutes the true source of your success, vigour, strength and growth. It invigorates and sustains you.

Dependence on others enfeebles you and brings failure. You can never prosper.

He who has no faith in himself and his powers is the weakest man.

There is a vast, limitless magazine of power and wisdom within you. Rely on your own self and tap it.

He conquers who believes he can. He attains success who believes he can attain success.

Think for yourself. Get knowledge wherever possible. Listen to the opinions of those who are more experienced than yourself, but do not allow anyone to do your thinking for you.

Self-reliance is a very important virtue. Self-reliance gives immense internal strength. This is an important qualification for material spiritual success. The vast majority of persons have got a leaning mentality. They have lost their powers of self-reliance. Luxurious habits have rendered people very weak. A doctor and a lawyer want servants to put on their shoes and socks. They cannot draw a pot of water from the well. They cannot walk even a furlong.

In olden days our forefathers washed their own clothing and did all sorts of work for the house. They could even split fuel. They could draw water from the well for hours together. They could walk 40 miles daily. They had wonderful physique and vitality. They had longevity of life. They were absolutely free from any kind of disease. Pyorrhoea, appendicitis and blood pressure were Latin and Greek to them in those days.

Nowadays man depends on others for everything. He has lost this virtue of self-reliance. He has forgotten all about Atmic-Sakti. He has no idea of the vast magazine of power and knowledge within in the Atman. His mind goes outwards. He has no inner life.

You must know how to cook your own food. You must give up servants. You must wash your own clothes. You must walk daily to your office. Give up the false idea of prestige and position. Sir T. Muthuswami Iyyer, the late reputed High Court Judge of Madras used to walk to the court. His name is still remembered for his virtue of self-reliance.

Householders want now a magical pill from the hands of Sannyasins for their spiritual uplift. They do not want to do any kind of Sadhana. Everyone of you should yourself place each step in the spiritual ladder. You are your own redeemer. You are your own saviour. Remember this point well. No one can save another. Stand on your own legs and get success in the world and in the spiritual path. Tap the source by closing the eyes and draw power.

SELF-SACRIFICE

Self-sacrifice is the act of yielding up one's life, interests, etc., for others.

Self-preservation is the first law of nature. Self-sacrifice is the highest rule of grace.

Self-sacrifice is self-abnegation. It is the sacrifice, surrender or subordination of one's own self or one's personal happiness, or comfort, for the sake of duty or to advance the interests of others.

Self-sacrifice kills egoism and leads to the descent of divine grace and divine light. A Karma Yogi annihilates this ego through self-sacrifice.

Self-sacrifice is the sacrifice of oneself or of self-interest for the good of another.

SERENITY

(SAMA)

Serenity is the state or quality of being serene. It is calmness or coolness of mind or peace.

Serenity is evenness of temper. Serenity is undisturbed state of mind.

A serene mind is unclouded or unruffled.

In a serene mind alone the Divine Light descends.

Serenity comes when you annihilate all desires and cravings. Desires and cravings produce restlessness.

If you are serene, it is the greatest manifestation of power and strength.

Do not hurry. Do not worry. Regret not. Do not fret and fume. Control irritability. Control your temper. Be contented. You will have serene mind.

Practise daily prayer, Japa, meditation. You will have serenity.

Serenity does not come in a day, or week. You will have to struggle hard for a long time in cultivating this fundamental divine virtue.

Serenity is the topmost virtue in the group of Shad-Sampat or six-fold wealth of the four-fold Sadhana of Jnana Yoga.

Be serene. Meditate and know that you are the All-pervading, Immortal Atman or the Soul.

SILENCE

Silence is the state of being silent. It is absence of sound or speech. It is calmness.

Silence is Brahman or the Absolute.

Silence is like sleep. It conserves energy and refreshes you.

Silence is a strong weapon which so few of us are strong enough to wield.

Silence is death for a talkative man. It is nectar for an aspirant or a Muni.

True silence is the rest of the mind. All thoughts subside. There is perfect peace.

Silence is a great virtue. It avoids disputes and unnecessary discussions and prevents sin.

Silence is eloquence. Silence is greater than speech.

Be silent and hear the inner voice of the Soul.

Silence from words is good; but silence from desires and passions is better as it promotes quietness of spirit. The best of all is silence from all thoughts as it leads to Self-realisation.

There is a great power in silence. Silence gives peace and strength. Many sublime conquests are effected in silence.

Be silent and know thyself.

SIMPLICITY

Simplicity is plainness, artlessness, unaffectedness, straightforwardness, guilelessness, cunninglesssness, absence of ostentation.

Simplicity is freedom from duplicity, affectation or pretension.

In dress, in food, in character, in manners, in style, in all things, the supreme excellence is simplicity.

There is a majesty in simplicity. Simplicity is Nature's first step and the last of art.

Be what you say. Say what you are. Write as you speak. Speak as you think.



Women lightly contract the Vagina

Men lightly contract the Perineum and Anus

***Fig. 8.4** Connect the Bridge - combine Earth and Heavenly Energy.*

Cosmic Chi Kung Preparation

Cosmic Chi Kung can be practiced either in a sitting or a standing position.
Sitting, relax as much as possible and invoke the **Cosmic Inner Smile**.

1. Be aware of your **heart** and listen to your **kidneys** with your inner senses. Smile to your heart and kidneys and feel them pulsing; feel them communicating and interacting with each other. The **Kan** and **Li**; the water of the kidneys and the fire of the heart, balance and **begin to mix**.
2. Open the arm pits as if you were holding a ping pong ball there and slightly move the fingers to activate the Chi flow. Relax. **Feel** the sensations of the **Chi flow**: tingling, warmth, pulsing, electric and magnetic feelings.
3. Be aware of your palms. Draw in Chi by **activating the bone breathing** process. Become aware of the perineum; slightly pull up the perineum, sexual organs and anus and "**connect the bridge**." (Remember to relax the perineum).
4. Breathe into the palms of the hands and soles of the feet, further enhancing your connection to the earth force. Smile to the blue earth energy as it flows up your arms and legs and suffuses your body with pleasant Yin energy.
5. Breathe into the **mideyebrow** point and activate your connection with the **Cosmic Force**. Smile to the golden light of the cosmic energy as it swirls into your mideyebrow point and flows throughout your body, healing and balancing your energy.
6. Breathe into your **crown** point and activate your connection with the **Heavenly Force.** Smile to the red and violet light of the heavenly force as it flows into your brain and washes your body with subtle pure Yang energy.

Be simple like a child. The door of Moksha will be opened unto you.

The greatest truths are the simplest; and so are the greatest men.

Goodness and simplicity are indissolubly united.

A simple, frank man is the most agreeable man.

Purity and simplicity are the two wings with which man soars high to the Kingdom of God.

SINCERITY

Sincerity is honesty of mind. It is freedom from pretence. It is frankness.

In sincerity there is honesty of purpose and character. There is freedom from hypocrisy, deceit or simulation. There are genuineness, truthfulness and integrity.

Sincerity is to speak as you think, to do as you pretend and profess, to perform and make good what you promise, and really to be what you would seem and appear to be.

The foundation of steadiness and constancy in friendship is sincerity. Nothing is steadfast which is not sincere.

Profound, great and genuine sincerity is the first characteristic of a virtuous man and an aspirant.

Sincerity is a trait of true and noble manhood.

A sincere man is trusted by all. He is honoured by all.

All virtues increase and strengthen by themselves if you are sincere.

Sincerity is the basis of every virtue.

A sincere man says what he thinks, nothing more or less. He cannot say one thing and mean another.

A sincere man speaks the truth. He is guileless and undissembling, plain, upright and incorruptible.

Sincerity is a fundamental characteristic of the person. Honesty is but a part of sincerity. It denotes simply the absence of intentional or fraudulent concealment. 'Sincere' and 'honest' denote personal characteristics. 'True' denotes a characteristic of a thing.

Sincerity is being in reality what one is in appearance.

A sincere man is clear, pure, unfeigned, frank, honest, true and virtuous.

Sincerity is the basis of every virtue. It is the face of the soul. It is the first of virtues.

Sincerity is the indispensable ground of all conscientiousness.

Sincerity is the foundation of that steadfastness and constancy which you seek in friendship. Nothing is steadfast which is not sincere.

It does not matter what you believe, if you are only sincere.

All virtues increase and strengthen themselves by the practice of sincerity. The shortest and surest way to live with honour in this world is to be sincere, is to be in reality what you would appear to be.

Hypocrisy and deceit are unknown to a man of sincerity. He has dignity of his character. He never stoops.

In common parlance it is said "Rama has made a promise in sincerity;" "Krishna has sincere intention;" "Sri Rama's regret was sincere;" "Sri Krishna is my sincere friend."

A sincere man is honest in intention, action or profession. He is true, plain, incorruptible and upright.

A man of sincerity is always consistent with himself. He is courageous. He has a clean conscience and pure heart. He is free from fear and tribulations. His tongue and his heart are in unison. The words of his mouth are the thoughts of his mind. Whatever he promises he puts into action.

An insincere man cannot make even an iota of spiritual progress.

Sincerity and honesty designate personal characteristics. True denotes a characteristic of a thing.

A sincere man and one who is honest always gets success in his work. He is very much liked by his superiors. These are Sattvic virtues. Honesty is the best policy in the West but is is a sacred virtue in the East. That man who is endowed with these two noble qualifications can penetrate into any region of the world. People will receive him with outstretched hands. Sincere and honest people are very, very rare.

A sincere man feels for the troubles of others and tries his level best to alleviate their sufferings. He is very sympathetic. He is very, very soft-hearted. A sincere man is also generous. He is free from any crookedness, cheating, diplomacy and double-dealing. People place their implicit faith in his words. A sincere man is always reliable. He is quite unassuming. There is not a bit of hypocrisy in him. He is quite frank and honest and true. He will not find any difficulty in getting a job anywhere. People are quite eager to take a sincere man in their service. A sincere man has always the well-being of his master in his mind. He works very hard.

Sincerity is one of the important qualifications in the path of spirituality. Throughout the Gita the one ringing note is that the aspirant in the path of Self-realisation should possess the important virtue, sincerity. The Sanskrit term for sincerity is Arjava.

Look at the sincerity of Lakshmana and Bharata and their unflinching devotion to Lord Rama. Wherever there is sincerity there is devotion also. Savitri was very sincere to her husband Satyavan. Maitreyi was very sincere to her husband Yajnavalkya. So she received the Atma-Vidya from him. Mira was very sincere towards her beloved Lord Krishna. She had the good fortune to have Darshan of Giridhar Gopal. A sincere friend, a sincere devotee, a sincere husband, a sincere wife, a sincere son and a sincere servant are gods on earth. There is no virtue greater than sincerity. It should be developed at all costs by one and all.

BE SINCERE, FRIEND

Sincerity is a virtue born of Sattva. It is known as Arjava in Yoga philosophy. It is one of the virtues mentioned in the thirteenth and sixteenth chapters of the Gita, which are necessary for the attainment of Brahma Jnana or wisdom of the Self. It is a Daivi Sampat. It is an aspect of Satyam or truthfulness. It is a Vritti or modification of the Sattvic Antahkarana.

A sincere man is respected in society. Every man places confidence in him. He says, "Mr. X is the most sincere man. I have not seen a man like him in my life. I have great reverence for him. I have intense faith in him."

An insincere man is a dead man while living. He is a burden on this earth. Of what avail is knowledge of the Universities and titles, of what avail is Tapas, practice of Asana and Pranayama, wearing of matted lock and rosaries on the neck, putting on orange-coloured robe, of what avail is renunciation and position in society, of what avail is wealth and possessions if a man is insincere?

A man who is endowed with this noble virtue gets success in all his attempts. He struggles hard with great sincerity. He never shirks responsibilities. He plods on and perseveres. He works diligently. He is vigilant.

If one possesses even this one laudable trait, all the other virtues will cling to him. Sincere people are rare in this world.

Therefore be sincere, friend, at all times. Develop this virtue to a maximum degree and attain Brahman or the Absolute. Brahman is an embodiment of sincerity. Therefore attain Brahman through sincerity.

A man of sincerity does hard work with intense love and devotion. He takes all responsibilities of his master, preceptor or employer on himself. What ten people can do, he does that himself with zeal, enthusiasm, fervour and love. Sincerity is a great dynamic spiritual force. It gives immense strength. Double-dealing, diplomacy, cunningness, crookedness, petty-mindedness are unknown to him. He is frank and straightforward. He will not hide or conceal anything. He will not conceal his thoughts. His thoughts will agree with his speech and his speech with his actions.

An insincere man never sticks to his promises. He breaks his promises and gives some excuse or other. People do not place any faith in his words. He cannot talk forcibly. He has no strong will-power. He tries to pose for a sincere man by trying to please his friends in a variety of ways, by gifts, artificial sweet and nice speech born of cunningness and other cunning methods. But he does not know that there are better intelligent people to detect the crow which shines in borrowed feathers. He is soon found out.

Man knows fully well that insincerity is not good and yet he clings to it. He cannot leave his evil trait. He does not try to eradicate this evil quality. What is the cause for this? This is due to delusion got up by Avidya or Maya. Mysterious is Avidya; Mysterious is the force and working of evil Samskaras! This delusion can be rent asunder only by Satsanga and service of preceptor.

O friend Venu! You have become insincere on account of intoxication from selfishness and greed. You do not know what you are exactly doing. You have a clouded understanding. Your conscience will prick you severely at one time. Your heart will bleed when you come to your senses. Your heart must bleed through repentance with a contrite heart. Then only can you purify yourself. Do Japa. Sing Lord's Name. Fast on Ekadasi. Do not take even a drop of water. You will develop sincerity and through sincerity you will achieve freedom, peace and perfection.

Large-heartedness, simplicity, unpretentiousness, harmlessness, rectitude, forgiveness, purity, steadfastness, self-control, fearlessness, cleanliness of life, absence of wrath, peacefulness, uncovetousness, mildness, modesty, absence of fickleness, vigour, forgiveness, fortitude, absence of envy and pride are intimately connected with sincerity.

Hyprocrisy, arrogance, conceit, wrath, harshness, unwisdom, deceitfulness, falsehood, diplomacy, cunningness, crookedness, petty-mindedness are connected with insincerity.

An officer wanted to do some constructive religious work. He wanted to build an institute. He was sending his savings regularly to his son for the purpose. But the insincere son kept all money in the name of his wife and cheated his own father. A certain Guru sent his disciple to spread his message. The disciple started his own institution and became a President-Founder himself. But he did not thrive on account of his insincerity. He did some mischief here and there and had to conceal himself to escape from the police warrant. Vice brings its own punishment at once in this world. Insincere people cannot thrive or prosper. They will meet with failure, dishonour, misery here and torture in hell hereafter.

If the husband is insincere, the wife begins to entertain suspicion; there is always quarrel and disharmony in the house. If the head clerk is insincere, the office work suffers, the office superintendent gets displeased and he gets a sack. If the Minister is insincere he is discharged at once by the Maharaja. An insincere man in any social or spiritual organisation creates much disharmony and disturbance and the whole work suffers a great deal.

Even disciples who get initiation from their preceptors become insincere and faithless and ungrateful. An insincere disciple betrayed Lord Jesus. Some of the disciples of Lord Buddha became his traitors and enemies. They left their Guru and did much harm and mischief. Even now there are plenty of insincere disciples who cheat even their Guru. What a shame! What a sad state! Their lot is highly deplorable! Such disciples will meet with miserable death. They will be tortured in the

Maharaorava hell. They will be thrown in lower wombs in the next birth and suffer from incurable diseases.

Padmapada was the most sincere disciple of Sri Sankara. He was able to walk over the river on account of the grace of his Guru. At each step there was lotus. Hence his name Padmapada. Sri Sankara was the most sincere disciple of Sri Govindapada. He never wrote anything without paying his adorations to his Guru first. A sincere disciple only will flourish in the spiritual path. He will earn undying fame. He only will reach the goal of life and attain immortality.

May the Lord abound with sincere people and sincere disciples who can turn out stupendous useful work! May your heart be filled with faith, devotion and sincerity!

SYMPATHY

Sympathy is feeling for another. It is compassion. It is pity. It is oneness with others in their striving and suffering.

Sympathy is a feeling of compassion for another's suffering. It is fellow-feeling. It is the quality of being affected by the condition of another, with feelings corresponding in kind, if not in degree.

A few more smiles of silent sympathy, a look of sympathy, a few more tender and gentle words, a few more kind acts, will pave a long way to contribute to the happiness of the suffering humanity.

True sympathy is putting yourself in another's place.

To ease another's headache is to forget your own. To mitigate another's grief is to alleviate or dispel your own.

Sympathy is the key that fits the lock of any heart.

Shame on those hearts of granite that cannot melt at the sufferings of others.

Open your hearts to sympathy. Sympathy prepares the mind for receiving the impressions of virtue.

There can be no politeness or courtesy without sympathy. Sympathy is the universal solvent.

SWEETNESS

Really sweet people are rarely found in this universe. Though sweetness is a feminine virtue, yet it is not found in the females too. Most of the females are harsh and gall-hearted though their speech appears to be sweet for the time being. A businessman, a lawyer, a doctor and a sister of ill-fame are all apparently sweet till they get money from their clients. This is not natural, lasting, beneficent, elevating sweetness. It is false glittering. It is commercial or mercenary.

A really sweet man is divine. He does not expect anything from others. His very nature is sweet. He brings joy to others by his innate sweetness.

Sweetness is born of Sattva. It is the sweet potent divine golden residuum after Rajas and Tamas have been squeezed out through protracted Yoga-Sadhana. It is the concentrated quintessence of Sattva. It is the sweet aroma that is wafted from the blossoming of the rare sweet flower of perfected soul—Siddha Purusha, adept or Arhat through long and intense Tapas, discipline, Yoga-practice and communion through mind—melting in Silence.

Sweetness must be an essential attribute of a spiritual propagandist and public worker. Without possessing this virtue, no propagandist can turn out efficient and solid work. He who wants to establish a Mutt or Ashram or spiritual institution must possess this ennobling virtue. All public workers and Ashramites must equip themselves with this divine quality.

The Rajasic ego should melt in the crucible of Yoga. Then this golden sweetness will shine in its glory. Rajas must be churned out. Then the butter of sweetness will float on the surface of the Sattvic mind.

Be sweet in speech. Be sweet in behaviour. Be sweet in manners. Be sweet in singing Kirtan. Be sweet in lecturing. Be sweet in look. Be sweet in serving others. Be soft, gentle courteous and polite too. This will increase your sweetness.

Develop this sweetness through service, self-restraint, Mouna, prayer, Pranayama, meditation, introspection, self-analysis, control of anger.

Sweetness is Radha Tattwa: Sweetness is the stuff out of which the heart of Radha is fashioned. Truthfulness, Prema, sincerity, cosmic love, Ahimsa are all modifications of sweetness. Sweetness is a rare divine blend of all these Sattvic attributes. It is millennium potency.

An argumentative, intolerant, impatient, proud, irritable, fault-finding man cannot cultivate sweetness.

May you all be endowed with this noble quality of sweetness which will enable you to root yourself in Brahman, the embodiment of Rasa, divine bliss.

Glory to Brahman, the Sweetness of sweetness.

TACT

Tact is adroitness or cleverness in managing the feelings of persons dealt with. It is new perception in seeing and doing exactly what is best in the circumstances. It supplies the place of many talents.

Tact is a quick or intuitive appreciation of what is fit, proper or right. It is fine or ready mental discernment shown in saying or doing the proper thing or especially in avoiding what would offend or disturb. It is skill or facility in dealing with men or emergencies.

Tact implies self-restraint, good temper, quick and kindly sympathy with the feelings of others. A tactful man will always have success in life. Tact removes all obstacles and surmounts all difficulties.

Tactfulness demands a quick and sound judgement, good commonsense, kind feeling and an instinctive perception of character.

Talent is power, tact is skill; talent is wealth, tact is ready money.

A tactful man says the right thing at the right time to the right people.

Tact is the open eye, the quick ear, the keen smell, the lively touch and the judging taste.

Tact loses no time; loses no opportunities. It takes all hints. It is ever alert, nimble and vigilant. It makes no false steps.

The principal elements of tact as a quasi-moral affair would seem to be (1) sensitiveness of feeling, (2) insight into the motives of others, (3) experiences as to the consequences of conduct, and (4) subtlety of reasoning, especially with reference to details.

TEMPERANCE

Temperance is moderation especially in the indulgence of the natural appetites and passions. In a narrower sense it is moderation in the use of alcoholic liquors and even entire abstinence from such.

Temperance is the spirit and practice of rational self-control. It is habitual moderation.

Temperance is self-restraint in the conduct of one's life or business. It is suppression of any tendency to passionate actions. It is calmness, patience.

Temperance is self-restraint in the indulgence of any natural affection of appetency. It is moderation in the pursuit of a gratification or in the exercise of a feeling as temperance in eating, temperance in drinking, temperance in the use of books, temperance in joy or grief.

If you are temperate your head will be clear, your health will be better, your heart will be lighter and your purse will be heavier.

Temperance is the foundation and source of health, strength and peace.

Temperance gives Mother Nature her full play and enables her to exert herself in all her force and vigour.

The ingredient in the liquor is the devil. It will excite you to do all sorts of mischievous and disgraceful actions. It will sap your vitality. Therefore, give up liquor at once.

Temperance puts money in the purse, contentment and peace in the house, vigour in the body, intelligence in the brain and spirit in the whole constitution. Therefore, be temperate.

It bestows vigour of body, health and strength, purity of mind, unclouded reason, refined sentiment and tranquillity of mind. It is the best guardian of youth and support of old age. It is the physician of the soul as well as the body. It is the Goddess of health and universal medicine of life.

Cultivate understanding. You can avoid the allurements of voluptuousness and fly from her temptations.

Your insincere friends will tempt you. They will take you to the bars and induce you to drink. The liquor will sparkle in the cup and entice you. It will preach "Here is joy and happiness." Now is the hour of danger. Let understanding and reason stand firmly in your guard.

Give up the company of drunkards at once. They will deceive and betray you. They will bring you to utter ruin.

The enjoyments in the bar will lead on to diseases and death. Beware. Beware. Beware. Are the drunkards not meagre? Are they not sickly? Are they not joyless and spiritless?

If you wish to keep the mind clear and the body healthy, abstain from all kinds of liquors.

Temperance is the foundation of all social and political reforms.

If temperance prevails, then education can prevail. If temperance fails, then education must fail.

Temperance is reason's girdle, the strength of the soul and the foundation of virtue. It is the strongest fence and defence against diseases.

Temperance keeps the senses clear and makes you quite fit to do great and hard work. It makes you cheerful and joyful. It cleanses the blood, clears the head, eases the stomach, strengthens the nerves and perfects digestion.

Liquors produce temporary excitement. Then follow depressions of spirits, cheerlessness, nervousness, irritability, gastric pain, loss of appetite, headache, prostration, debility, weakness, etc.

An intemperate man walks with tottering steps. There is no strength in his limbs. His heart is filled with shame, care, grief, sorrow and repentance. Diseases and wants oppress him.

A temperate man sings, dances and whistles. He has rosy cheeks. There is lustre in his eyes, joy in his face, and radiant smile on his lips. He is full of vigour, vim and vitality. He is always cheerful, brave, active and lively. He sleeps soundly. His mind is serene and restful. He has peace and poise. He has coolness and clearness of head.

Cultivate temperance and lead a happy life.

Temperance Movement is a political agitation for the restriction or abolition of the use of alcoholic liquors.

Temperance Society is usually an association of total abstainers from alcoholic liquors.

Temperance drink is any non-alcoholic beverage, especially one that is flavoured as Sarsaparilla, etc.

Temperance hotel is a hotel in which no intoxicating liquors are served.



Fig. 8.6 *Invoke the Cosmic Inner Smile.*



Fig. 8.5
Place the Tip of the Tongue on the Upper Palate.

7. Place the tip of your tongue on the upper palate behind the teeth in a comfortable position.

8. As you begin to move through the postures of Cosmic Chi Kung, always be aware of the Chi flow and its attending sensations.

Cosmic Chi Kung Preparation Standing

1. Stand with your **feet parallel** and shoulder width apart.
   Tilt your **sacrum** and **pelvis** slightly forward until you feel your feet press more firmly into the ground. As you tilt the pelvis, feel your lumbar vertebrae pressing outward; this is called "**Opening the Door of Life**."
2. Relax your **chest** and sink your **sternum**. Draw your chin in slightly, and hold your **head, neck** and **spine** erect as if your head and spine were suspended from above by a string.
3. Follow the same instructions for the preparations of Cosmic Chi Kung.

TOLERATION

Toleration is enduring of offensive person or opinions.

Tolerance is freedom from bigotry. It is a spirit of charitable leniency.

Tolerance is a disposition to tolerate or not to judge or deal harshly or rigorously in cases of differences of opinion, conduct or the like.

You have not the monopoly of wisdom. Do not criticise destructively. Your neighbour's way and opinion may not be yours. It may nevertheless be as good.

Never condemn rashly but judge righteously. Be charitable and kind to one another. Be tolerant.

Religious tolerance is necessary. It will establish religious harmony in the country.

There are diversities of opinion even among the best men. This should not breed hatred. No two minds are alike in nature.

Intolerance is a crime.

Have a wide vision. Have a broad outlook. Give space in your heart for everybody, for every religionist. Be broad as the sky.

Tolerance in religion is absolutely the best fruit of all the struggle and labours.

TOLERANCE LEADS TO BLISS

As there are men of various temperaments, capacities and tastes, various schools of thought, cults and societies are necessary. The followers of cults or sects should have a large heart to include other sects also. The fundamental principles or essentials of all religions are the same. One should have perfect tolerance towards other faiths. Cults and Mandals help the beginners to grow but all cults culminate in Vedanta eventually.

During the life-time of the founders only some cults, Mandals, sects, societies and other institutions function well. After they pass away, the followers do not keep up the integrity and goodwill of the institution. Gurudom creeps in. Selfishness penetrates and overwhelms the heads of the institution. They become money-making concerns. The original sweet spiritual aroma fades and vanishes gradually. The followers unsettle the minds of others by decrying their faith and eulogising their own cult or society and thus produce much harm to the people at large.

People begin to trade in the name of religion. That is the reason why some of the cults, sects, Mandals and societies, instead of becoming dynamic spiritual centres, become fighting centres eventually.

The followers do not do any rigorous Tapas and meditation. They do not go in for seclusion for rigorous Tapas and Sadhana. They are not endowed with dispassion, renunciation and discrimination. They have tall talk. They simply talk of 4th region, 5th place, 7th sphere etc. The institution which was once enjoying spiritual fame and glory during the life-time of the founder, dwindles into a mere social institution gradually on account of lack of a spiritual dynamic personage to run the institution. Mere intellectual grasp of truths or eloquence or oration will not really make one a Yogi or a sage.

Those who say that Lord Krishna and Lord Rama are lower personages, know nothing of religion and philosophy.

A renowned doctor, an M.D., of the Punjab, went to see the chief of a particular faith at a certain place. He heard him saying "Lord Krishna is a lower personage." At once he left the place and had no faith in him. He told me later on that he had full faith in the Sloka of the Gita: "There is nothing whatsoever higher than Me, O Dhananjaya; all this is threaded on Me as rows of pearls on a string." Ch. VII-7.

To say that Lord Krishna is on an inferior stage, that one can have Santi through this faith only, is highly deplorable. Some say, "Join our cult, faith or society, you will have Darshan of the Lord within fifteen days. If you join our faith or cult you will go beyond Para Brahman also. You can have peace and Mukti through our faith and cult only." This is perfect intolerance and narrowness.

Just listen to what Lord Krishna Himself says in the Gita: "In whatever way men approach Me, even so do I reward them. My path do men tread in all ways, O son of Pritha." Ch. IV-11.

May Lord bless you with broad tolerance and large heart. May you be free from carping and cavilling. May you all recognise the Oneness or Unity of Atman. May you embrace others with divine love. May you all realise the unity of all religions. May you not indulge in religious controversies and debates.

May you all silently rest in your own All-blissful and silent Self and enjoy the Eternal Bliss within through deep meditation!

Om Santi! Santi! Santi!

TRUTH ALONE TRIUMPHS

(Satyameva Jayate)

Truth is simple; it is made to appear complex by the distracted intellect. The sublimest things are always the most simple.

Truth can never be defeated by untruth. Truth shall always win victory over untruth. When the path of Truth is trodden, everything else also is done. When the root is watered, all the branches are automatically watered.

The path of Truth is a precipitous one. It is slippery and as sharp as the razor's edge. Hard it is to tread, difficult a path it is. Giants among spiritual men walk over it to the City of perfection.

The Absolute is All. Truth is Absolute. You are That. This is the essence of spiritual teaching.

Truth is utterly public. It cannot be hidden even if one would try to do so. Truth persists and is expressed even in the extreme of untruth. The extreme of Truth is the Absolute. Untruth is a shadow of Truth. The world is untruth and the Absolute is the Truth. The world is represented by sex and ego; the Absolute is represented by the Noumenal Gnostic Being.

Truth is not expressed even by Existence-Consciousness-Joy! It is only the nearest relative of Truth. Truth is even greater, grander, mightier, truer!

All is well with him whose heart is turned towards the Truth. No disease, physical or mental, can assault him.

The mover towards the Truth is mighty, lives long, knows everything and is ever delighted; for he is nearing the Almighty.

Truth is: untruth is not; hence it is not absolutely correct even to say that Truth is One, for Truth is Existence Itself and is neither one, nor not-one. Truth is undivided.

The Absolute baffles the mind of even the greatest scholar. It eludes the grasp of even the mightest intellect. It is experienced as Pure consciousness where intellect dies, scholarship perishes and the entire being itself is completely lost in it. All is lost, and all is found!

The Absolute is perfectly scientific, logical, symmetrical, balanced, systematic, reasonable, rational! It is not irregular and haphazard. It is not a supra-natural mystery but the natural fact of life. The infinite and indivisible nature of existence is not a wonder; it is the actual condition of being even as brilliance is of fire, liquidity of water, weight of lead. It is the highest Perfection of Eternal, Immortal, Real Life.

Everything that changes itself is untruth. Hence Truth is infinite. Truth alone endures, while everything else perishes. Everyone, right from Brahma down to a blade of grass, moves towards Truth, some consciously, some unconsciously. They differ only in degree of consciousness or to the extent of mental purification or subtlety of condition. Every leaf that flies in the air, every breath that flows from us, in other words, every act of universal life, is a step taken nearer the Truth; for, Truth is the eternal Home of all beings. Into it they all enter and find permanent satisfaction and peace. It is Truth, that triumphs over falsehood, not falsehood over Truth, whatever the apparent and immediate experience may be.

TRUTH

Truth constitutes the essence of the Vedas. Control over passions constitutes the essence of truth. Self-denial or refraining from the worldly enjoyments forms the essence of self-control. These attributes are always present in a virtuous man.

Truth is one eternal Brahman. Truth is the one undecaying penance. Truth is the one undecaying Swarupa. Truth is the one undecaying Veda. The fruits attached to truth have been described as the highest. From truth originate righteousness and self-control. Everything depends upon truth.

There is no penance like truth. Truth creates all creatures. Truth sustains the entire universe. It is with the help of truth that one goes to heaven. That which exists in the past, present and future is truth.

Truth is the origin of creatures. Truth is their progeny. It is by truth that the world moves. It is by truth that the sun gives heat. It is by truth the fire burns. It is on truth that Heaven rests. Truth is sacrifice, penance, Vedas, the verses of Sama, Mantra and Saraswati.

Truth is knowledge. Truth is the ordinance. Truth is observance of vows and fasts. Truth is the prime syllable, Om.

There is truth where righteousness is. Everything multiplies through truth.

Truth is righteousness. Righteousness is light and light is bliss. Ahimsa, Brahmacharya, purity, justice, harmony, forgiveness, peace are forms of truth.

Truth is duty. Truth is Yoga. Truth is a great sacrifice. Everything depends upon truth.

Impartiality, self-control, modesty, endurance, goodness, renunciation, meditation, dignity, fortitude, compassion and abstention from injury are the various forms of truth.

Truth is immutable, eternal and unchangeable. It is won through Yoga. It is won through practices which do not oppose any of the other virtues. You will gain universal goodwill by continual devotion to Truth.

The quality by which an esteemed and good man puts up with both what is agreeable and disagreeable is forgiveness. You can cultivate this by the practice of Truthfulness.

You should always practise forgiveneses. You should ever be devoted to Truth. The wise man who can renounce joy, fear and anger can develop fortitude.

Abstention from injury to all creatures in thought, word and deed, and kindness are the permanent duties of the good.

All the above virtues, though seemingly different, have but one and the same form, namely, Truth. All these hold up Truth and strengthen it.

It is impossible to exhaust the merits of Truth. That is the reason why the Brahmanas and the gods speak highly of Truth.

There is no duty which is higher than Truth and no sin more dreadful than untruth.

From Truth originates gifts, sacrifice with presents, the three-fold Agnihotras, the Vedas and everything else which lead to righteousness.

Once upon a time, Truth and all religious observances including a thousand virtues were weighed on a scale. When both were weighed that scale on which Truth was, proved weightier.

Harishchandra practised Truth. He adhered to Truth at the risk of his life, and attained immortality and eternal bliss and undying fame. He still lives in our hearts.

Truth always exists in a pure and unmixed state. Truth is always a duty with the good. Truth is eternal duty. Truth is the greatest refuge of all. Hence respectfully bow to Truth.

Brahman is Truth. You can attain Truth only be practising Truth. Therefore be firm in Truth. Realise Truth by practising Truth.

TRUTHFULNESS

Srutis emphatically declare "*Satyam Vada*—speak truth. *Satyameva Jayate Nanrutam*—Truth alone triumphs but not falsehood." God is Truth and Truth must be realised by speaking the Truth. A truthful man is absolutely free from worries and anxieties. He has a calm mind. He is respected by society. If you observe speaking truth for twelve years, you will get Vak Siddhi. Then whatever you speak will come to pass. There will be power in your speech. You can then influence thousands.

Your thought should agree with your words and the words should agree with your actions. In the world people think of one thing, say another thing and do another thing. This is horrible. This is nothing but crookedness. You must carefully watch your thoughts, speeches and actions. The little gain that you get by telling lies is no gain at all. You pollute your conscience and infect your subconscious mind. The habit of telling lies is carried to your next birth also and you undergo suffering from birth to birth. Have you ever thought over this matter? Be very serious and stop the evil habit of telling lies from this very second.

The name of Harishchandra is even now a household word because he was a truthful man. He stuck to his principles of speaking truth at all costs. He never cared for his wife or dominion. He underwent all sorts of suffering. He was truthful to the very last. Visvamitra tried his level best to make him a liar. He failed in all his various schemes. Truth alone triumphed in the end.

Write in bold types the words "SPEAK TRUTH" on card boards and hang them in different places in your house. This will remind you, when you are about to speak any lie. You will check yourself at once. A time will come when you will be established in the habit of speaking truth. Punish yourself by fasting if you tell a lie and record the lies in the diary. Gradually the number of lies will decrease and you will become a truthful man.

SPEAK THE TRUTH

Truth is a common word that is commended by one and all every moment of our life from generation to generation, from time to time and from day to day. It is an ideal to be worshipped and followed. It is so important that man should stick to it at all costs. God is Truth and Truth is God. You render all your worship to truth as you do to the Almighty. It is an essential of life. It is a blessing in itself. It has the splendour of the Sun. It has the blessing of the Lord. It is complete in itself. Truth has a strong foundation in itself. It is bold, it has no fears. It has no limit of space or time. It is a fearless free bird in the sky. It does not care for status. It is wealth in itself.

Truth can be compared to a road of pasture, while falsehood can be compared to a bush of thorns. In a man who indulges in false thoughts, there is a lurking fear at every moment, an uneasiness, a fear of the self, a want of confidence and a feeling that something wrong may happen. Truth is the path of righteousness which certainly leads to success only in the long run. It is a straight road with no doubtful cross-roads. We have heard in the History of Sri Harishchandra what a lot of suffering the king passed through to establish the goodness of truth. In the day-to-day world, it seems as though it is impracticable to strictly follow a path of truth, but if it is practised as your ideal and goal in life, you have your way. All the stumbling blocks on your road to truth will melt away as you proceed along the direct road.

There are certain fallacies that arise in following the straight path of truth. It is absolutely no harm for a mother who fondly nurses the child in just diverting the attention of the child by saying that the small piece of sweetmeat has been carried away by the crow a short while back, and when she shows to be extremely sorry for it and brings round the ideas of the child by saying 'Papa, do not mind it, I shall bring a bigger cake for you in the evening.' The father out of affection for the child gives hope to the boy of seven that if he completes the five sums from his tough arithmetic book before the end of the day, he will be having a prize of two penny; but it so accidentally happens that the father winds himself in his blanket and pretends to be asleep, by the time the boy completes the sum and runs fast to the mother and says 'Mama, I have completed my contract, but, alas, father has gone to bed and I do not like to disturb him as he is very much tired.' It is absolutely no untruth if you do not interfere with others, wound their feelings, harm others or spoil others. If you refuse a small loan, certainly with something for you to fall back upon, if you refuse to lend your pen or any object that you would like not to lend, these cannot be counted as untruths.

If your falsehood disturbs the peace in you, the peace of others and if your untruth spoils the career in others, there is no greater sin in this world than this. You will be having your time for repaying the same in your own coin to your own self with so much of remorse. You are certainly erring and it is so much of swerving from the path of righteousness, which road definitely deviates from the road of Self-realisation. Truth is an ideal to be worshipped, to be followed, to be adhered to at any cost. It is the be-all and end-all of human existence.

When you are only a petty officer with no status of your own, why do you assume so much about your own self, and feed others with vain promises? Can you not afford to be plain in your dealings and guide your friend in the right way? To keep your friend for a longer time in suspense, than to dispose of him with a few kind words of advice directing him definitely for a short distance in the right path—does this help either you or your friend in any way?

Always be bold, be plain, never have the shyness of a nerveless man. Follow the straight road. Serve others to a small definite extent that you are capable of. Do not imagine too much of yourself. Always be plain. Love the neighbour and give him only proper advice or no advice at all. Do not misguide him. Do not give false hopes. Do not say "I shall try, I shall let you know in a day or two, I shall see what I can do in the matter." Such indefinite words do not cost you anything, they cost your neighbour all the world, because he has wasted much of his time in depending upon you and particularly lost by ill-guided advice, the most important period of his life, when probably he cannot afford to mend his faults. Art is long and time is short is the old saying. Time should never be killed. A man of untruth definitely kills his time, as also the time of others. Once you feel yourself you have misguided him, you think for yourself and you will realise that you have definitely swerved from the right path, and this pricks you for a very long time.

Therefore stick to the path of truth at all costs. Truth has a lustre of its own. It shines for itself and sheds light on others. When you stick to it as your only religion, you will be liked by all around you. You cannot afford to harm any one by simply adhering to the path of truth. Nay, you will be respected you will be feared, you will have a peaceful and a blissful heaven around you. There is no kingdom wider in space, there is no bliss more blissful, there is no enjoyment more happy, there is no pleasure more worth this life than the straight road of truth. In the long run there is a world of love between yourself and your colleagues in whatever walk of life they may be, there is a world of smile all around you, for you have no burden to carry, no sense of past thoughts and you are absolutely free.

The whole world aspires for every kind of freedom, the heart in every man aspires to be free of unnecessary thoughts, people around you would like to have a free talk to you, and such being the ideal before you all—why can you not stick to it? Strictly speaking there is no inexplicable 'Circumstance' as you call it to speak the untruth. Untruth is only a means and it leads to no destination. It is all for the nerveless, it is for the weak, it is for the timid to speak the untruth. It is for the shy and the wavering to think and to speak untruth.

For a man treading the right path, everything can be approached with absolute boldness, with free will, and with smiling pleasure; because he releases all his thoughts and he does not attach any importance to the self as distinct from the other. To him service alone counts, he is calm and serene with what little he does and he has always a bold and a sure step before him. There is no ego in him. He loses himself in his love for others. Service, service and service alone is his ideal. The result of service does not come into the picture at all; for he does not imagine any kind of result nor does he entertain any room for idle imaginations. '*Karmanyeva Adhikarasthe-ma Phaleshu Kadachana*' is the end and aim of his life. He is not hampered by negative results. The whole world is an indifferent drama before him. He is never moved at all. He simply witnesses the drama and passes away most serenely. Such a silent career is the most successful career in any era of life. May the Almighty bless us in treading the path of truth and Ahimsa.

WILL-POWER

Will is the power of choosing or determining. It is volition.

Will is the power of controlling one's own movements and internal states, feelings and thoughts by conscious and especially by deliberate choice. It is the faculty of self-determination distinguished from all those activities of the mind and body which are initiated or directed wholly by external stimuli and which are, therefore, constrained or impulsive, and from all that play of the intellectual and emotional life which falls under the control of instinct, association and habit, purely. It must always be recognised, however, that the element of choice or volition is a matter of indefinite degrees, and that the control of attention is the primary and most disctinctive evidence of the presence in the mental life of so-called will.

With Aristotle free-will was rational desire, implicating a sort of force comparable to that of a rushing wind.

Will is that faculty or power of mind by which we determine either to do or not to do something which we conceive to be in our power. It is the faculty which is exercised in deciding among two or more objects, which we shall embrace or pursue. It is the power of control which the mind possesses over its own operations.

The combination of the two elements of emotion and self-determining force toward the gratification of emotion controlled the ancient two-fold division of the faculties into understanding and will.

The modern three-fold division into intellect, feeling and will arose from a more searching and thorough analysis of the socialised faculties.

The still more recent and more nearly complete analysis of students of psychology would seem to favour the use of the word 'will' as a term to cover, not any one faculty, but the entire active side or aspect of mental life so far as it is consciously voluntary and culminates in deliberate choice.

Desire, wish, will are states of mind which every one knows and which no definition can make plainer.

If with the desire there goes a sense that attainment is not possible, we simply wish; but if we believe that the end is in our power, we will that the desired feeling, having or doing shall be real.

Opening to Heaven, Earth and Nature

The natural world is the source of our power. Cosmic Chi Kung teaches us about nature and its energies. In the Tao, nature and the universe are equivalent to God. You are a part of nature and can easily learn to open to the forces in the macrocosm and let them flow through you. This is very simple. Just tune into the frequencies around you. Your fingers are antennae, which transmit and receive.

1. To begin your practice of Cosmic Chi Kung, simply **stand** up and **feel the energy around you**. When you stand or sit, be aware of your soles (Bubbling Spring points) making a good connection with the earth. Your perineum (Hui Yin point) is relaxed and open. You are connecting to the earth force and can expand further down on to the other side of the universe. This is one type of energy.
2. When you draw your **chin in**, slightly **relax your chest** and tilt your head slightly forward; you begin to be aware of the heavenly force. This is another type of energy.
3. The qualities of the **Five Elements** reveal themselves as woody trees (growing force), fiery deserts (expanding force), earth mountains (stabilizing force), metal air (contracting force) and watery oceans and lakes (gathering force). We call the combination of these elements the '**Cosmic Force**'.

Thus, your mind and body learn to gather, absorb, direct and transform the heaven, earth and cosmic energy for your own use. This is the essence of Chi Kung. Today there is a lot of emphasis on learning movements and forms of Chi Kung. However, if the inner feeling is not there, the movements are of little value.

Heavenly force is Yang. Earth force is Yin. By learning to connect to the energies of heaven and earth, you have a powerful tool for restoring and maintaining your inner balance of Yin and Yang.

Outline of Practice

Before practicing each of the Cosmic Chi Kung sets in this chapter and in the following chapters begin with the heaven and earth spirals as outlined on page 157.

First **Create the Chi Field**.

Hold each of the Cosmic Chi Kung postures for at least 5 - 30 seconds, gradually lengthening the time to 60 - 120 seconds per posture.

Note: While holding the postures count the breath from 5 to 15 seconds, being aware of the **Tan Tien** and feeling the Chi in the Tan Tien which then moves up to the **crown** and expands up to the universe; fuse your Chi with the Universal Chi and let it multiply down to your palms. **Just concentrate on the 'Tan Tien and the Universe'**; do not concentrate on the palms at all.

Throughout parts I, II, III and IV 'Tan Tien and Universe' means to spiral into the Tan Tien and spiral out into the universe connecting 'Tan Tien and Universe'.

This self-determining side of man's mental life and development, as the basis of civic and moral responsibility, has always been recognised by reflective thinking and in the popular mind, although in different ways and with differences in the extent of its application. In the conception of will, the two elements of desire or willing intention, and of power or efficiency to realise desire, have both quite uniformly been united.

Great souls have willing; weak souls have only wishing.

According to Vedanta, will is Atma-Bala or spiritual force, born of Atman or soul.

He who has a firm, strong, pure, irresistible will can accomplish anything in this world. He can move the whole world. He can move the three worlds.

When you are free from desires, cravings, the will grows stronger and stronger. Ultimately, you obtain freedom of the will.

Do total surrender unto the Lord. Then your individual will will become one with the Divine Will. Then you shall find every burden light and every duty a joy.

Do God's Will as if it were thy will, and He will accomplish thy wish as if it were His own.

To will what God wills is the only way which gives you perfect peace and rest.

HOW TO DEVELOP THE WILL-POWER

Attention, power of endurance, overcoming aversion, dislikes and irritations, fortitude in suffering, Tapas (austerities such as standing on one foot, sitting in the hot sun) or Panchagni Tapas before five fires, standing in cold water in piercing winter, raising the hands above and keeping in the same position for an hour, fasting, patience, command of temper, forbearance, clemency, mental power of endurance, firmness in meeting danger, power of resistance or attack, Satyagraha, keeping up daily diary—all pave a long way in developing the will. One should patiently hear the words of others even though they are not interesting and charming. He should not fret and fume. Patient hearing develops will and wins the hearts of others. One should do actions or tasks that are uninteresting. This also develops the will-power. The actions that are not interesting will become interesting after some time.

Never complain against bad environments. Create your own mental world wherever you remain and wherever you go. There are some difficulties and disadvantages wherever you go. If the mind deludes you, at every moment and every step, try to overcome the obstacles and difficulties by suitable means. Do not try to run away from bad, unfavourable environments. God has placed you there to make you grow quickly.

If you get all sorts of comforts in a place you will not grow strong. Your mind will be puzzled in a new place when you cannot get these comforts. Therefore, make the best use of all places. Never complain against surroundings and environments. Live in your own mental world. Nothing can upset your mind. You will find Raga-Dvesha even in the eternal snowy regions of the Himalayas, near Gangotri. You cannot get an ideal place and ideal surroundings in any part of the world. Kashmir is very cool, the scenery is very enchanting but Pissus (small insects like fleas) trouble you at night; you cannot sleep. Banaras is a centre of Sanskrit learning but it is famous for hot winds in summer. Uttarakasi in the Himalayas is beautiful but you cannot get vegetables or fruits there; the cold is so very biting in winter. This world is a relative plane of good and evil. Remember this point at all times. Try to live happily in any place, under any condition. You will become a strong and dynamic, pocket and unlock the Elysian regions, the spiritual realms and the immortal abode. You can get sanguine success in any undertaking. You can conquer any difficulty.

The practice of concentration is of great help to strengthen the will. You must have an intelligent understanding of the habits of the mind, how it wanders and how it operates. You must know easy and effective methods to control the wandering of the mind. The practice of thought-culture, the practice of concentration, the practice of memory-culture, are all allied subjects. All these are of immense help in the practice of will-culture. You cannot draw a line of demarcation to denote where the practice of concentration or memoryculture ends and the practice of will-culture begins. There is no hard and fast rule. For further particulars on the practice of concentration, please see my book "Concentration and Meditation."

Mr. Gladstone and Mr. Balfour could go to deep sleep the moment they went to bed through mere willing. They had such a strong will. Even Mahatma Gandhi had this practice. They could get up in the morning at any time they wanted, to the very minute. The sub-conscious mind was their obedient servant. It would wake them up at the very second. Every one of you should develop this habit through will and become a Gandhi, a Gladstone or a Balfour. Generally, the vast majority of persons simply roll in their beds for hours together and do not get sound sleep even for half an hour. It is the quality of sleep and not the quantity that gives refreshment. Sound sleep for even an hour is quite sufficient to refresh the body and revitalise the mind. The moment you go to bed, simply relax the mind and give the suggestion "I will have good sleep now." Don't think of anything. Napoleon had this habit. Even when the bugle was blowing and the drums were beating on the battle field, he would be snoring. His sub-conscious mind would wake him up at the very second he wanted to get up. With a cool mind Napoleon would appear like a lion on the battlefield. One should train himself to sleep in running cars, trains and when moving in the aeroplanes even in a sitting posture. This practice is of immense help for busy medical practioners, advocates and businessmen, who have to do immense work daily and a good deal of travelling. Life has become so very complex nowadays that busy people do not find time to get enough sleep. Whenever they find some leisure, even for five minutes, they should close their eyes in any place and go to sleep for a short time. This would give great rest. They can continue their further activities. This kind of practice is a blessing to busy people. Their nerves are under great tension and pressure. By relaxing them every now and then, they could refresh themselves and keep quite fit for further activities. One should be able to sleep on the platforms of Howrah or Bombay railway stations when trains are moving at all times. This is a wonderful practice that gives immense strength. Dr. Annie Besant used to write editorial columns, when moving in the cars. There are some busy doctors who read newspaper even when they are in the water closet. They keep their minds fully occupied. The practice of keeping the mind fully occupied is the best of all practices for keeping up physical and mental Brahmacharya. Those who want to become magnetic and dynamic personalities or prodigies should utilise every second to the best possible advantage and should try to grow mentally, morally and spiritually every second. Idle gossiping should be given up entirely. Every one of us should realise the value of time. Will is bound to become dynamic if one utilises his time very profitably. Application and tenacity, interest and attention, patience and perseverance, faith and self-reliance, can make a man a wonderful world-figure.

ZEAL

Zeal is boiling or passionate ardour for anything. It is enthusiasm. It is intense eagerness, especially disinterested eagerness in promoting some end. It is enthusiastic devotion. It is fervour.

Success is due less to ability than to zeal. Give yourself to your work body, mind and soul. Success is surely yours.

Your offerings please God according to your zeal and not according to their nature.

Zeal is like fire.

JUSTICE

Justice is integrity, impartiality.

A man of justice is lawful, upright, exact, true and righteous, equitable.

Justice reigns. Injustice is fleeting and illusory.

He who believes in justice remains calm through all trials and difficulties.

Justice consists in doing no injury to men. Justice is decency. A man of justice gives no offence to any man.

The peace of society depends on justice. Lawyers, solicitors, judges, public prosecutors, police inspectors and superintends and all Government officials should be just. Let the hand of justice lead them aright.

When justice prevails in the Government, there is foundation for social security, general happiness of humanity and the improvement and progress of the nation.

In Government relations, justice is the giving to every person exactly what he deserves. Equity is giving everyone as much advantages, previleges or consideration as are given to any other. In personal and social relations justice is the rendering to everyone what is due or merited whether in act, word or thought. In matters of literary work or reasoning justice is close, faithful, unprejudiced and unbiased adherence to essential truth or fact. We speak of the justice of a statement or of doing justice to a subject.

Justice is the bread of the nation. Justice alone triumphs.

Justice is the greatest and simple principle which is the secret of success in all Government. It is the first virtue of officers.

Do not misappropriate. Be not covetous. Return your loans to others. Pay your debts to others. Cast not an evil eye on the property of others. Let no temptation allure you nor any provocation excite you.

If you acted unjustly, pray, repent, do Japa of Lord's Name. Correct yourself immediately and be careful in future.

Give up black-marketing at once. Do not cheat others. You will suffer. You will be thrown in lower births. You will be punished in the hell severely. You will get incurable diseases. You will meet with premature death. Your conscience will torment you.

Do not charge too much when you sell things. Be moderate. Get a small profit.

Oppress not the poor. Exploit not the credulous, the ignorant and the weak.

Betray not. Be faithful to your master. Be faithful to your trust. Cheat not the man who relies on you.

Be always impartial, honest and just in your dealings with others.

Bear no false witness against anybody.

To be perfectly just is an attribute of the divine nature. A just man is a glorious man. He is a veritable God on this earth.

Impartiality is the life of justice. Justice is the constant desire and effort to render to every man his due.

An honest man always thinks justly.

Understand well the consequences of injustice. You will become just.

Be just and fear not.

Justice without wisdom is not possible. Justice is in conformity with the laws.

If you want to enjoy peace, be just.

Justice is the idea of God. It is the ideal of man. It is man's rule of conduct. Therefore, be just. Practise justice.

A just man conforms to the requirements of right or of poisitive law. He renders exactly what is due as in punishments and reward.

Justice applies to either ethics or law, denoting something that which is morally right and fair, and sometimes that which is right and fair according to positive laws.

Equity, fairness, fairplay, impartiality, integrity, justness, lawfulness, rectitude, righteousness, truth, uprightness are synonymous with justice.

Integrity, rectitude, righteousness and virtue denote conformity of personal conduct to the moral law and thus necessarily include justice which is giving others that which is their due.

Corruption, dishonesty, faithlessness, one-sidedness, partiality, treacherousness, unrighteousness, unfairness are the opposite of justice.

O man! Be just always. Examine your heart. Hear the whisperings of conscience. You will reap a rich harvest of peace and bliss.

MEDITATION ON 12 VIRTUES

Meditate on these 12 virtues for 10 minutes daily:

Humility in January.
Frankness (*Arjava*) in February.
Courage in March.
Patience in April.
Mercy (*Karuna*) in May.
Magnanimity in June.
Sincerity in July.
Pure love in August.
Generosity in September.
Forgiveness in October.
Balanced state in November.
Contentment in December.

Meditate also on Purity, Perseverance, Diligence, Sahasa and Utsaha. Imagine that you are in the actual possession of these virtues. Say unto yourself: "I am patient. I will not get irritated from today. I will manifest this virtue in my daily life. I am improving." Think of the advantages in possessing this virtue, "Patience" and disadvantages of irritability.

The spiritual path is rugged, thorny and precipitous. It is too long. The feet may become tired and bruised. The heart may pant. But the reward is very great. You will become immortal. Persevere. Plod on diligently. Be on the alert. Be agile and nimble like the squirrel. There are no resting places on the path. Hear the small inner voice. It will guide you if you are pure and sincere.

LIST OF VIRTUES TO BE DEVELOPED

(Take a copy of this and hang it in a prominent place in your house.)

(A) Major Virtues

Alms-giving
Balance of mind
Brahma Chintana
Courage
Diligence
Equanimity
Feeling His presence at
  all times and in all actions
Generosity
Mouna
Obedience to all
Perseverance
Purity of heart
Self-control and sacrifice
Serving nature
Sincerity
Tolerance
Truth-seeking
Vairagya
Work without attachment

Always speaking truth
Brahmacharya
Calm and cheerful nature
Desirelessness
Discipline
Fearlessness
Forbearance
Frankness
Humility
Nobility
Patience
Power of endurance
Renunciation
Serenity
Simplicity
Strong will-power
Tranquillity of mind
Unfailing devotion
Unshakable faith in God

(B) Minor Virtues

Abstinence
Accepting one's own
  faults and weaknesses
Austerity
Aversion to slander
Bearing insult and injury
Chivalrous nature
Compassion to living beings
Contemplation
Control of Indriyas

Absence of Greed
Affection
Always uttering your
  Ishta Mantra
Avoiding bad company
Charity towards all
Cleanliness
Constancy
Contentment
Dauntlessness

Detachment
Equal-mindedness
Firmness
Fortitude
Freedom from malice and overweening conceit
Heroism
Joyful nature
Kindness to all
Loving nature
Mercy
Modesty
Non-injury in thought, word and deed
Not caring for public criticism
Observing elegant manners and principles
Quick and nimble in every action
Satisfaction
Satsangh with Mahatmas
Selfless service
Steadfastness in knowledge, and devotion and sacrifice
Sublime thoughts
To be kind and generous towards all
Vigour
Enterprise
Fasting on principal days
Forgiving and forgetting one's ill-treatment
Gentleness
Giving nature
Innocence
Keeping up one's own word at any cost
Magnanimity
Moderation in everything
Non-covetousness
Non-stealing
Non-violence
Nursing the sick with Bhava
Politeness
Praising others
Reducing sleep
Resourcefulness
Righteousness
Self-effacement
Speaking well of others
Steadiness
Study of scriptures
Sympathy towards all
To talk little and sweet
Uprightness

WORD-PICTURE OF VIRTUES

1. **Temperance**—Eat not to dullness; drink not to elevation.

2. **Silence**—Speak not but what may benefit others or yourself; avoid trifling conversation.

3. **Order**—Let all your things have their places, let each part of your business have its time.

4. **Resolution**—Resolve to perform what you ought; perform without fail what you resolve.

5. **Frugality**—Make no expense but to do good to others or yourself; i.e., waste nothing.

6. **Industry**—Lose no time; be always employed in something useful; cut off all unnecessary actions.

7. **Sincerity**—Use no hurtful deceit; think innocently and justly, and, if you speak, speak accordingly.

8. **Justice**—Wrong done by doing injuries, or omitting the benefits that are your duty.

9. **Moderation**—Avoid extremes; forbear resenting injuries so much as you think they deserve.

10. **Cleanliness**—Tolerate no uncleanliness in body, clothes or habitation.

11. **Tranquillity**—Be not disturbed at trifles, or at accidents common or unavoidable.

12. **Chastity**—Rarely use venery but for health or offspring, never to dullness, weakness, or the injury of your own another's peace or reputation.

13. **Humility**—Imitate Jesus and Socrates.

(Have similar word-pictures for other Virtues you wish to cultivate.)

SONG OF EIGHTEEN 'ITIES

Serenity, regularity, absence of vanity,
Sincerity, simplicity, veracity,

    Equanimity, fixity, non-irritability,
    Adaptability, humility, tenacity,

Integrity, nobility, magnanimity,
Charity, generosity, purity,

    Practise daily these eighteen 'ities,
    You will soon attain immortality.

Brahman is the only real entity,
Mr. So and so is a false non-entity,

    You will abide in eternity and infinity,
    You will behold unity in diversity,

You cannot attain this in the university,
But you can attain this
In theYoga-Vedanta Forest University.

THE EIGHTEEN 'ITIES

For everyone's success in life, and especially for a Sadhaka's success in the spiritual life, it is essential that he should develop certain cardinal virtues. Virtue is strength, power and the key to peace. A virtuous man is ever happy, peaceful and prosperous. People ask me for a specific mention of the virtues that one should develop. The "Song of Eighteen 'Ities" enumerates the virtues that everyone should cultivate. Take up any one virtue and develop it to a very high degree of perfection; eradicate in toto its opposite evil quality even in its most subtle form. Meditate on these virtues, their benefits; the methods of cultivating these virtues. The Eighteen 'Ities are:

(1) **Serenity**: Be tranquil within. Let that inner peace and inner joy radiate through a serene countenance. A serene countenance is peaceful, smiling, serious, and does not betray any violent emotions. It is like the surface of a still lake.

(2) **Regularity**: Be regular in your daily habits, work and Sadhana. Get up at a particular time daily; go to bed at a particular time. Be clock-like in your daily activities. You will be free from worry, anxiety, haphazard and shabby work. You will do the right thing at the right moment.

(3) **Absence of vanity**: Do not boast of your birth, position, qualifications and spiritual attainments. Remember the evanescent nature of all things phenomenal. Praise others. See good in all. Treat even the lowliest creatures as your equal.

(4) **Sincerity**: Let your words agree with your thoughts; let actions agree with your words. Let there be harmony between your thoughts, words and actions.

(5) **Simplicity**: Be artless. Be simple in your speech. Do not twist words and topics. Be plain, avoid diplomacy, cunningness and crookedness. Be simple in your dress. Be simple in your diet. Develop a child-like nature.

(6) **Veracity**: Be truthful. Stick to your promises. Do not exaggerate. Do not twist facts. Think twice before you speak. Speak truthfully, speak sweetly; be precise in what you say.

(7) **Equanimity**: Be calm. Bear patiently insult, injury, suffering, failures, and disrespect. Be not elated by praise, pleasure, success and honour. Look upon both with equal vision. Behave alike towards friends and foes. Never let a thing disturb your inner peace.

(8) **Fixity**: Remeber you can achieve nothing if you are fickle-minded. Do Vichara. Choose your goal or ideal. Always remember that. Never let it go out of your mind even for a moment.

Part I
Opening to Heaven, Earth and Cosmic Chi

Opening Movements

Three Minds into One Mind

Empty the mind and heart down to the Tan Tien.
Hold the hands together at the heart center.
Smile and make the heart feel soft; feel love, joy and happiness.
Turn your consciousness inward and your awareness out.



Fig. 8.7 *Empty your Mind and Heart down to your Lower Tan Tien.*

Feel your legs lengthen extending down to the center of the earth.
Feel your hands lengthen extending to the universe below.
Let the mind expand and be aware all the way down to the universe.
Feel the 'long' bones of the arms and legs and begin bone breathing.
Feel universal Chi filling, packing and compressing into the bones.
Draw this Chi down to the back of your crown and feel a heavy pressure press on the crown; feel slightly numb or a light electric downward flow, like oil dripping down. 'Focus at Tan Tien and Universe'. Count to five.

(9) **Non-irritability**: Irritability is the precursor of violent outburst of anger. Watch for the disturbance in the mental equilibrium. Watch for the ripples of anger that might arise in the lake of the mind. Quell them then and there. Do not allow them to assume greater proportions. Then you will attain non-irritable state of peace and love.

(10) **Adaptability**: Understand the nature of the people with whom you came into contact. Adjust your mode of approach to them, your conduct towards them in such a way as would be pleasing to them. Joyfully bear with the eccentricities of other people. Always react in a harmonious manner. Serve all and love all. Have the Bhavana that the Lord is in all as the Self of all.

(11) **Humility**: Respect everybody. Bow with folded palms before everybody. Do not talk in a loud voice in the presence of elders and venerable persons. Look at the toes while you walk. See the Lord in all and feel that you are His servant and so the servant of all. Consider none as inferior to you.

(12) **Tenacity**: This is the natural friend of fixity. Once you have fixed your aim and chosen your path, stick to it. Do not waver. Be steadfast. Never compromise on your fundamental principles. Have the mental attitude "I may give up my life; but I will not swerve the Path, I will not break my vows."

(13) **Integrity**: Develop an integral personality. Tie all the loose ends of your character. Become a man of high moral principles. Lead a Dharmic life. Let righteousness waft its fragrance from you. Everyone will trust you, obey you, respect you and revere you.

(14) **Nobility**: Shun mean-mindedness as dung and poison. Never look into other people's defects. Appreciate everyone's good qualities. Be dignified in bearing. Never stoop to low thoughts, words of actions.

(15) **Magnanimity**: Take a broad view of things. Ignore other people's faults. Be great and high-minded in whatever you do. Avoid silly talk and childish prattle. Let not the mind dwell on little things and insignificant incidents.

(16) **Charity**: Give, give and give. Radiate thoughts of goodwill and love. Forgive other people's faults. Bless the man who injures you. Share what you have with others. Feed and clothe all. Disseminate spiritual knowledge, to one and all. Use the material wealth, knowledge and spiritual wisdom that you

possess as a divine trust, entrusted to you by God, to be distributed among His children.

(17) **Generosity**: In whatever you give, be liberal. Have a large heart. Be not stingy. Take delight in other people's joys, in making other people happy. Generosity is a sister-virtue of charity. Generosity is the fulfilment of charity, magnanimity and nobility.

(18) **Purity**: Be pure at heart. Eradicate lust, anger, greed and other evil tendencies. Be pure in your thoughts; let no evil thought enter the mind. Think of God always; think of the well-being of all. Be pure in your words; never utter a vulgar, harsh or unkind word. Be pure in body also; keep it clean, keep your dress and your surroundings clean. Observe the rules of physical, mental, moral and spiritual hygiene

These eighteen 'Ities will pave the way for you to march into the kingdom of God. They will open out the gates of immortality for you. You will achieve great success in this life on earth also. A man who possesses these qualities in a very large measure is a saint, indeed, who will be respected, adored and worshipped by one and all. May you all become Jivanmuktas and the very embodiments of these virtues!

PART II

How to Eradicate Vices

AFFECTATION

DAMBHA

Affectation is a striving after or an attempt to assume, what is not natural or real. It is pretence.

Affectation is to make a show or pretence of, to assume, to counterfeit, or pretend to.

Affectation is a studied or ostentatious pretence. It is artificial, false or shallow display. It is artificiality of manner or behaviour.

Affectation is an attempt to assume or exhibit what is not natural or real. It is false pretence, artificial appearance or show.

Affectation proceeds either from vanity or hypocrisy. Vanity puts on false characters to gain applause. Hypocrisy conceals vices under the appearance of their opposite virtues, in order to avoid censure.

Affectation proceeds from the supposition of possessing something better than what the rest of the world possesses.

Affectation is a trick or stratagem played by vanity. It is a perpetual disguise of the real character by false appearances.

Affectation is a badge of ignorance or stupidity.

A man of affectation knows his defects and attempts to conceal them by artificial excellence. He is easily found out by others. He is an object of disgust for his neighbours.

Be natural. Be yourself. Do not imitate. Ape no greatness. Give up all affectation. What is natural is best.

Cultivate simplicity, humility, nobility, integrity, magnanimity, etc.

A man is not humble, but he puts on a show or affectation of humility.

Affectation is petty hypocrisy.

Pretence commonly signifies the offering of something for what it is not.

Hypocrisy is the pretence of moral excellence, either as a cover for actual wrong or for the sake of the credit and advantage attaching to virtue.

Sanctimoniousness is the assumption of saintly manner without a saintly character.

Cant is hypocrisy in utterance.

Sanctimoniousness is hypocrisy in appearance as in looks, tones, etc.

Affectation is in matters of intellect, taste, etc., much what hypocrisy is in morals and religion.

Sham is a trick or device that puts one to shame or that shamefully disappoints expectation or falsifies appearances.

AHAMKARA

EGOISM

I

Ahamkara or egoism is the self-arrogating principle in man. It is a Vritti or modification that arises in the mind. Patanjali Maharshi calls this by the name 'Asmita.' The same mind assumes the form of egoism when man self-arrogates to himself. Ahamkara manifests first and then comes "Mamata."

This baneful egoism generates actions, desires and pains. It is the source for all evils. It is illusory. It deludes people. Though it is nothing, it is everything for the worldly people. It is associated with mineness. It is born of Avidya or ignorance. It springs from false conceit. Vanity fosters it. It is the greatest enemy. If one renounces this dire Ahamkara he will be happy. The secret of renunciation is renunciation of egoism. Ahamkara has its seat in the mind. It is under the influence of egoism that man commits evils and wrong actions. It is deep rooted. Anxieties and troubles proceed from egoism. Ahamkara destroys our virtues and peace of mind. It spreads the snare of affection to entrap us. He who is free from egoism is very happy and peaceful. Desires multiply and expand on account of egoism. Our inveterate enemy of egoism has spread about us the enchantments of our wives, friends, children etc., whose spells it is hard to break. There is no enemy greater than egoism.

He who neither desires nor dislikes anything and who preserves the serenity of mind at all times is not affected by the feeling of egoism. There are three kinds of egoism in the world. Of these two kinds of egoism are beneficial and of superior nature but the third is of a vile kind and is to be abandoned by all.

The first is the supreme and undivided ego which is eternal and which pervades through the world. It is the supreme soul, besides which there is nothing in nature. Meditate on the formula '*Aham Brahma Asmi*—I am Brahman.' Identify yourself with Brahman. It is Sattvic Ahamkara. The knowledge which makes us perceive our own Self to be more subtle than the tail-end of paddy or to be as minute as the hundredth part of a hair and to be ever existent is the second kind of Ahamkara. These two kinds of egoism are found in Jivanmuktas or liberated sages. They lead to the liberation of men. They will not cause bondage. Hence they are of beneficial and superior nature. The third kind of Ahamkara is the knowledge which identifies the 'I' with the body composed of the hands, feet, etc., which takes the body for the soul or the Self. This is the worst or basest form of egoism. This is found in all worldly persons. This is the cause for the growth of the poisonous tree of rebirths. Those who possess this kind of egoism can never come to their right senses. Countless persons have been deluded by this form of Ahamkara. They have lost their intelligence, power of discrimination and power of enquiry. This kind of egoism produces baneful results. People come under the influence of all evils of life. Those who are slaves of this form of Ahamkara are troubled by various desires which induce them to do wrong actions. It debases them to the state of beasts. This kind of Ahamkara should be destroyed by the other two kinds of Ahamkara. The more you thin out this egoism, the more you will get knowledge of Brahman or the light of the soul.

Again there are three kinds of Ahamkara, viz., Sattvic egoism, Rajasic egoism and Tamasic egoism. Sattvic egoism will not bind a man to Samsara. It will help the aspirant to attain the final emancipation. If you try to assert '*Aham Brahma Asmi:* I am Brahman'—this is Sattvic egoism. Even in a Jivanmukta there is a slight trace of Sattvic egoism. He does actions through this Sattvic egoism. 'I am a king, I know everything. I am very intelligent'—this is Rajasic egoism. 'I am a fool. I do not know anything'—this is Tamasic egoism.

The literal meaning or Vachyartha of 'Aham' Pada is Aham Vritti that arises in the mind, the little 'I' which identifies itself with the physical body. The indicative meaning or Lakshyartha of 'Aham' Pada is Atman or Brahman, the big or infinite 'I.' Mere illusion is the cause of egoism. Knowledge is the cause of egoism. Knowledge is produced through the illusory objects such as the body, tree, river, mountains, cow, horse, etc. If there are no objects, cow, horse, etc., we will have no knowledge of objects at all. Then egoism, the seed of Manas, will be absorbed.

The idea of 'I' which is the nest containing all frailties is the seed of the tree of mind. The sprout which at first germinates from the seed of Ahamkara is Buddhi or intellect. From this sprout, the ramifying branches called Samkalpa take their origin. Through such a differentiation, the mind, Chitta, and Buddhi are but the different names or qualities of the same Ahamkara. The branches of Vasanas will naturally produce innumerable crops of Karmas, but if with the sword of Jnana you sever them from the heart's core, they will be destroyed. Cut the branches of the tree of mind and eventually destroy the tree at its root completely. Cutting the branches is only a secondary thing, the primary one being the eradication of the tree at its root. If you, through virtuous actions, destroy the idea of 'I' at the root of the tree (mind) then it will not grow up. Atma Jnana or knowledge of the Self is the fire which destroys the conception of Ahamkara, the seed of the tree.

There is another classification of egoism, viz., gross (Sthula) and subtle (Sukshma). When you identify yourself with the gross physical body, it is gross egoism. When you identify yourself with the mind and Karana Sarira (seed-body), it is subtle egoism. If you destroy pride, selfishness, desires and identification with the body, the gross egoism will perish but the subtle egoism will remain. You must annihilate the subtle egoism also. Subtle egoism is more dangerous and more difficult of eradication. 'I am a rich man, I am a king, I am a Brahmin,'—this is gross egoism. 'I am a great Yogi, I am a Jnani, I am a good Karma Yogi, I am a moral man, I am a good Sadhaka or Sadhu'—this is subtle egoism. There is another classification of Ahamkara viz., Samanya Ahamkara (ordinary egoism) and Visesha Ahamkara (special egoism). Ordinary egoism is present in animals. Visesha Ahamkara is present in human beings.

You say, "This body is mine." The vultures, jackals and fishes also say, "this body is mine." If you peel off the layers of the onion one by one, the onion dwindles into an airy nothing. So is the 'I.' This body, mind, Prana, senses, etc., are all combinations of the five elements and Tanmatras. They are all modifications of the Prakriti only. Where is the 'I' then? This physical body belongs to Virat, astral body to Hiranyagarbha and causal body to Isvara. Where is the 'I' then? 'I' is an illusory nothing fabricated by the juggler mind. Nothing can be said to exist. That which is produced through Karmas is not itself the cause. The knowledge or consciousness that we have of it is itself illusory. Therefore, Ahamkara and other effects which are produced through the delusion of knowledge are also non-existent. The real 'I' is the Sat-Chit-Ananda Brahman only.

Just as the motion of the train or the boat is apparently transferred to the trees, so also 'I' is transferred, through the jugglery of Maya, to the body, mind, Prana and senses. When you say, 'I' am stout, 'I' am lean, the 'I' is transferred to the body and you identify yourself with the body; when you say, 'I' am hungry, 'I' am thirsty, the 'I' is transferred to the Prana, you identify yourself with the Prana; when you say, 'I' am angry, 'I' am lustful, the 'I' is transferred to the mind. If you identify yourself with the Supreme Self, all false identifications will vanish.

If you kill the commander of an army, you can very easily subdue the soldiers. Even so, if you kill the commander-egoism in the Adhyatmic battlefield, you can very easily subdue the soldiers, viz., lust, anger, pride, jealousy, greed, delusion, hypocrisy, who fight for their master—egoism.

Try to attain Brahman by means of the first two kinds of superior egoism. If you are firmly established in that supreme immaculate state wherein even these two kinds of superior egoism are abandoned one by one, then such a state is the imperishable abode of Brahman. Do not identify the 'I' with the physical body. Identify yourself with the Supreme Self or Para Brahman.

You might have reduced or thinned out your egoism to a very great extent but if you are still susceptible to censure and praise, know that the subtle egoism is still lurking in you.

An aspirant who treads the path of devotion destroys his egoism through self-surrender or Atma Nivedana to the Lord. He says, "I am Thine, my Lord. All is Thine. Thy will be done." He feels that he is an instrument in the hands of the Lord. He dedicates all his actions and the fruits of his actions to the Lord. He feels that there is nothing but the Lord, that everything is done by the Lord, that even an atom cannot move without Him and that all live, move and have their very being in Him alone.

Channeling the Earth Force - Washing the Bone Marrow

Smile into the **perineum, palms** and **crown**. Then slowly raise the arms, palms facing each other, to chest height keeping the elbows relaxed and sunk. Rotate the arms slowly until the palms are facing down. Be aware of the mideyebrow and feel your breath and lightly contract your eyes and round muscles around the eyes. Connect the perineum bridge by slightly squeezing the sex organs and the anus; do this a few times.

Rest and **smile to soles of the feet**, feel the Chi bubbling and feel like you are standing on a hot spring starting to bubble up.

Be aware of your Tan Tien and expand your mind down past the earth to connect with the galaxy below you. Multiply and bring your mind back to the Tan Tien. Gradually feel the Chi being absorbed through the whole body and absorb it into the bones and body like a **rising steam or mist**. Feel the earth force move through the center of the bones and enter the bone marrow move up the calves and thighs (femur bones) through the hip bones, spine, **scapula**, **arms**, **neck** and **skull**. Finally **swirl the energy around your brain. 'Focus at Tan Tien and Universe'**.



***Fig 8.8** Activate the Hip: Large Intestine 4, Pericardium 8 and Small Intestine 3.*



Raise your index finger slightly upward to activate the Hegu Point (Large Intestine).

***Fig. 8.9** Open the 'Tiger's Mouth'.*

A Karma Yogin destroys his egoism through self-sacrifice. A Jnana Yogin kills his egoism through self-denial or self-abnegation, through Vichara and the practice of "Neti-Neti—I am not this body, I am not the Prana, I am not the senses", and through identification with the Supreme Self by meditating on the formula 'I am the all-pervading Self or Brahman.'

May you rest in the big Infinite 'I', the pure Sat-Chit-Ananda Brahman and enjoy Eternal Bliss by annihilating this little illusory 'I', the product of Maya, through self-sacrifice or self-surrender.

II

A certain Brahmin went to a landlord to get a house for feeding Sadhus on a Bhandara. The landlord gave him a house. He utilised it for the purpose. He did not vacate the house on the next day, but remained there for some months. The landlord asked the Brahmin when he would vacate the house. The Brahmin said he would keep the house for some months more, as he wanted to celebrate his son's marriage. The landlord granted permission. The greedy Brahmin did not vacate even after two years. The landlord again asked the Brahmin when he would vacate it. The Brahmin said that he lost his mother and he would keep the house till the anniversary was over. The landlord patiently allowed. Three years passed. Now the covetous Brahmin thought that he could claim the house as his own, as he had lived in the house for a pretty long time and as the neighbours also knew well that he was the proper resident and owner. When the landlord asked now the Brahmin about the house, the Brahmin said that the house belonged to him, and refused to vacate it. The matter went to the chief court. The poor Brahmin was not able to produce proper records, though he managed to bring false witnesses. He had to give back the house to the landlord.

Similarly, you are provided with the house, the physical body, to inhabit for some years, during which period you are expected to realise Sat-Chit-Ananda and vacate the body during Videha-kaivalyam. Instead of doing this, owing to Ahamkara you are behaving like the covetous Brahmin. Destroy Ahamkara and rest in Brahman.

ANGER

KRODHA

Anger is a negative Vritti or whirlpool in the mindlake. It is born of ignorance.

It is a strong emotion, excited by a real or fancied injury and involving a desire for retaliation.

Anger is the natural passion or emotion of displeasure and antagonism aroused by injury or insult, real or imagined, and directed against the cause thereof. Anger arises from an idea of evil having been inflicted or threatened.

Anger is often accompanied by a desire to take vengeance, or to obtain satisfaction from the offending party.

It begins in folly and ends in repentance.

The fire you kindle for your enemy, burns yourself.

When anger arises, think of the consequences. It will soon subside.

You think of objects of senses. Attachment to these objects develops. From attachment desire is born. From desire anger comes forth. From anger proceeds delusion; from delusion confused memory; from confused memory the destruction of reason; from destruction of reason you perish.

Raga or attachment is a long-standing associate of anger.

Control anger through patience, enquiry, self-restraint, love and meditation. This is manly and divine. This is wise and glorious.

To become angry for trifling things is mean, childish and brutal.

When you are angry, count twenty before you speak. If you are very angry, count one hundred.

An angry man is again angry with himself when he comes to his senses.

When anger is on the throne, reason takes to its heels.

Be always ready to forgive the faults of others. Kill the spirit of revenge. Return good for evil.

Anger begins from folly or weakness. It ends with remorse and repentance. Act not in a furious passion.

He who is influenced by anger is like one intoxicated with a strong liquor.

Fury, indignation, choler, ire, temper, irritation, rage, resentment, wrath are synonymous with anger.

Displeasure is the mildest and most general word. 'Temper' is used in the sense of anger. This is colloquial. We say: "Mr. Johnson is a man of hot temper, a fiery temper."

Anger is sharp, sudden and brief. Resentment is persistent. It is the bitter brooding over injuries. Exasperation, a roughening, is a hot superficial intensity of anger, demanding instant expression.

Rage drives one beyond the bounds of prudence or discretion. Fury is stronger and sweeps one away into uncontrollable violence.

Anger is personal and usually selfish, aroused by real or supposed wrong to oneself. Indignation is impersonal and unselfish displeasure at unworthy acts. Pure indignation is not followed by regret and needs no repentance. It is also more self-controlled than anger. Anger is commonly a sin. Indignation is often a duty. We speak of "righteous indignation."

Wrath is deep and vengeful displeasure. It simply expresses the culmination of righteous indignation without malice in a pure being.

Anger is a stronger term than resentment, but not so strong as "indignation" which is awakened by what is flagitious in character or conduct; nor as wrath, fury, rage in which anger is wrought up to a still higher point in the order of these words. Anger is a sudden sentiment of displeasure; resentment is a continued anger; wrath is a heightened sentiment of anger.

CONTROL OF ANGER

Control anger by practice of Kshama, love, Dhairya, patience, and Nirabhimanata (absence of egoism).

When anger is controlled, it will be transmuted into an energy by which you can move the whole world.

Anger is a modification of passion. If you can control lust, you have already controlled anger.

Drink a little water when you become angry. It will cool the brain and calm the excited, irritated nerves.

Repeat 'OM Santi' ten times.

Count twenty. By the time you finish counting twenty, anger will have subsided.

Try to nip anger when it tries to emerge out from the subconscious mind to the surface of the conscious mind. Watch the small impulse or wave of irritability carefully. Then it will be more easy. Take all precautions. Do not allow it to burst out and assume a wild form.

If you find it extremely difficult to control it, leave the place at once and take a brisk walk for half an hour.

Pray to God. Do Japa. Meditate on God. You will gain immense strength.

Be careful in the selection of your company. Have congenial company. Move with Sannyasins, Bhaktas and Mahatmas. Read the Gita and the Yoga Vasishtha. Do not waste your semen. Take Sattvic food, milk, fruit, etc. Give up hot curries and chutnies, meat, alcohol and smoking. Tobacco makes your heart irritable (tobacco-heart). It produces nicotine poison.

ANXIETY

VYAKULATA

Anxiety is uneasiness regarding something doubtful.

Anxiety is uneasiness or distress of mind regarding some uncertain event which may involve danger or misfortune.

Anxiety is strained or solicitous desire, as for some object or purpose, or eagerness, as one's anxiety to please all.

It is a condition of restlessness and mental agitation with a distressful feeling of tightness and oppression in the region of the heart.

Anxiety is the rust of life. It destroys its brightness and weakens its power.

Anxiety is the poison of human life. Do not anticipate trouble or worry about what may never happen. Sufficient to each day are the duties to be done and the trials to be endured.

Full faith in God puts an end to anxiety. A childlike and abiding trust in God is its best preventive and remedy.

The cares of tomorrow weigh a man down. Do not torment yourself with imaginary dangers or trials or reverses. Be always happy and cheerful. Trust in God and do the right. Leave the rest to God.

God looks after everybody. He feeds even the frog that lives between the strata of rocks. Be not, therefore, anxious, and say

'What will be my fate next year? What shall I eat tomorrow? What shall I do for my clothing and blanket? How can I arrange for the education of my son or the marriage of my daughter?' God knows that you have need for all these things. He will do everything for you.

Do not make yourself wretched by imagining catastrophes unforeseen in the distant future. Do not anticipate misfortune.

Be always busy. Keep yourself ever occupied. Anxiety will take to its heels.

He who worships God, who sings His glory, who recites His Name is raised above anxiety for earthly wants.

You anticipate calamities, dangers and troubles. But they never come. Why do you unnecessarily worry yourself and waste your time, energy and strength?

Be of good cheer. Never bother about trouble till trouble actually troubles you.

Anxiety is mental. It is in regard to the unknown, or what may happen. It refers to some future event, always suggesting hopeful possibility.

Worry is a more petty, restless and manifest anxiety. Anxiety may be quiet and silent. Worry is communicated to all around.

Solicitude is a milder anxiety.

Perplexity often involves anxiety, but may be quite free from it. A student may be perplexed regarding a translation, yet, if he has time enough, not at all anxious regarding it.

Assurance, calmness, carelessness, confidence, ease, light-heartedness, satisfaction, tranquillity are the opposites of anxiety.

ARROGANCE

DARPA

Arrogance is undue assumption of importance. It is unreasonable or excessive assumption or assertion as of superiority. It is overbearing pride.

An arrogant man is unduly or excessively proud, as of wealth, status, learning, etc. He shows pride in spirit or conduct. He is unwarrantably assuming, overbearing and haughty.

It is that species of pride which consists in exorbitant claims of rank, dignity, estimation or power, or which exalts the worth or importance of the person to an undue degree. It is pride with contempt for others.

An arrogant man is abject and base. His head is swollen, like the swelling of dropsy.

Haughtiness thinks highly of itself and poorly of others.

Arrogance claims much for itself and concedes little to others.

Pride is an absorbing sense of one's own greatness.

Haughtiness feels one's own superiority to others.

Disdain sees contemptuously the inferiority of others to oneself.

Presumption claims place of privilege above one's right.

Pride deems nothing too high.

In the presence of superiors, overweening pride manifests itself in presumption or insolence.

Pride is too self-satisfied to care for praise.

Vanity intensely craves admiration and applause.

Superciliousness, as if by the uplifted eyebrow, as its etymology suggests, silently manifests mingled haughtiness and disdain.

Insolence is open and rude expression of contempt and hostility, generally from an inferior to superior, as from a servant to a master or mistress.

Assumption quickly takes for granted superiority and privilege which others would be slow to concede.

PLAY OF ARROGANCE

Ya Devi Sarva Bhuteshu Darpa Rupena Samsthita;
Namastasyai, Namastasyai, Namastasyai, Namo Namah.

Salutations, Salutations to that Devi, who dwells in the form of arrogance in all human beings.

The Sanskrit word for arrogance is "Darpa." Arrogance is undue assumption of importance. Arrogance is claiming proudly and unduly. It is a mixture of Rajasic-Tamasic egoism, insolence, rudeness, over-bearing nature and impertinence or imprudence. It is a modification of egoism. It is Ahamkara itself. It is born of ignorance. Maya keeps up her Lila or play through the arrogance of the deluded souls.

A man behaves insolently with an elderly man, treats him with contempt, sneers at him and speaks disrespectful words. This is arrogance.

Another man throws a book or a note-book in front of a person in anger and utters vulgar words. This is arrogance.

Another person says to another man in anger, "Don't you know who I am? I will break your jaw. I will break your skull. I will break your teeth. I will drink your blood." This is arrogance.

Another man says, "I cannot be dictated by anybody. I have my own ways. Nobody can question me. I cannot dance before him. Why should I go to him? Why should I follow his instructions? Is he more learned than me? Who is he, after all? Who are you to order me? Who are you to question me?" This is arrogance.

Generally a thoughtless man who is not practising introspection and self-analysis says, "I have no arrogance at all. I am humble, gentle and kind." But when the test comes, he hopelessly and miserably fails a thousand and one times. Such is the force or strength of arrogance.

A Sadhaka is very good. He is very intelligent. He is a learned man. He delivers lectures. He meditates silently in a solitary room for hours together. And yet he is not free from arrogance. When a man goes against his sweet will or wish, when a man speaks ill of him and criticises him, when he is not respected, he becomes arrogant and behaves very rudely.

Arrogance assumes various forms. One man may be arrogant on account of his great physical strength. He may say, "I will neck you out now. Get thee gone." Another man may be arrogant on account of his wealth, position and power. Another man may be arrogant on account of his secular learning. Another man may be arrogant owing to his scriptural erudition. Another man may be arrogant owing to his psychic Siddhis, moral virtues, spiritual progress, Sannyasihood, Mahantship, etc.

A man may renounce his wife, children, property, position, wealth, etc. He may renounce the world and live in a cave in the Himalayas for several years, practising Yoga and yet he finds it difficult to renounce arrogance. When he becomes impulsive he is overpowered by arrogance. He does not know what he is exactly doing. He repents afterwards. Impulse is a motive force to make one arrogant.

Watch your thoughts, words and actions very carefully. Know the power of words and use them cautiously. Respect all. Speak sweet and measured words. Be kind. Cultivate patience, love, humility. Enquire. Observe Mouna or the vow of silence. Again and again think, “This world is unreal. What will I gain by being arrogant?” Think of the immense benefits of the opposite virtue, HUMILITY.

You may fail one hundred times. But again stand up and strengthen your resolve: “I have failed yesterday. I will be humble, kind and patient today.” Gradually your will-force will develop and you will conquer arrogance, the enemy of peace, devotion and wisdom.

With all your care and vigilance arrogance will hiss and raise its hood several times daily. Raise the rod of Viveka, discrimination and sword of humility and chop its head. Arrogance is a myriad-headed monster, or Asura like the Raktabeeja who fought the Devi. He will again develop more heads. Continue the battle with more vigour, force and strength. Use combined methods, prayer, meditation, enquiry, Brahmabhyasa, self-restraint, Japa, Kirtan, Pranayama. Take recourse to the Yoga of synthesis. He will be burnt in toto and reduced to ashes.

If an arrogant man remains in the cave or in the room, there is no scope for him to eradicate this Vritti. It will lurk in his mind and harass him. An aspirant must mix with persons of different mentality and temperament and watch his thoughts, when he is ill-treated, disrespected and persecuted. If he is calm and serene and humble even under worst trying conditions know that he has eradicated this terrible foe.

The more the learning, the more the arrogance. The bigger the position, the greater the arrogance. The more the wealth, the more the arrogance.

May you all be free from this evil trait! May you all conquer this demon through humility, patience, kindness and love, and enjoy eternal bliss and immortality!

AVARICE

LOBHA

Avarice is an eager desire for wealth. It is extreme covetousness or greed.

Avarice is passion for getting and keeping riches.

Avarice is insatiable. It produces extreme discontentment and restlessness. It is an enemy of peace, wisdom and devotion.

Avarice increases with the increasing pile of gold or bank balance.

Of all the vices, avarice is most apt to taint and corrupt the heart.

An avaricious man is immoderately desirous of accumulating wealth. He is eager to accumulate and hoard. He is greedy of gain. He is ever grasping.

Avaricious and covetous refer especially to acquisition; miserly, niggardly, parsimonious and penurious, to expenditure. The avaricious man desires both to get and to keep, the covetous man to get something away from its possessor. One may be made avaricious by the pressure of great expenditure.

The rapacious have the robber-instinct and put it in practice in some form, as far as they dare. The avaricious and rapacious are ready to reach out for gain.

Greedy is used not only of money, but often of other things, as food, etc. The greedy child wishes to enjoy everything himself; the stingy child to keep others from getting it.

Avarice sheds a blasting influence over the finest affections and sweetest comforts of mankind.

The covetous eagerly desire wealth, even at the expense of others; the avaricious hoard it; the penurious, parsimonious and miserly save it by disgraceful self-denial and the niggardly, by meanness in their dealings with others.

Miserly and niggardly persons seek to gain by mean and petty savings; the miserly by stinting themselves, the niggardly by stinting others.

Parsimonious and penurious may apply to one's outlay either for himself or for others; in the latter use they are somewhat less harsh and reproachful terms than niggardly.

Bountiful, generous, liberal, munificent, are the opposites of avaricious nature.

SONG OF AVIDITY

(*Just as the Song of Eighteen 'Ities places before you a set of positive virtues that yo u should cultivate, this Song of Avidity places before you a set of evil traits that you should guard yourself against. It also shows you the method of overcoming them.*)

Avidity, cupidity, stupidity,
Audacity, turbidity, unstability,
Angularity, eccentricity, irritability,
These are the obstacles to Samadhi.
These are the impurities of the mind.
Avidity is covetousness or greed.
Cupidity is lust or passion.
Stupidity is delusion or infatuation.
Audacity is arrogance or impertinence.
Turbidity is confusion of mind.
Unstability is wandering of the mind.
Angularity is a form of vanity.
Eccentricity is slavery to whims and fancies.
Irritability is anger in all its forms.
Remove these impurities through the opposite virtues.
Avidity through practice of generosity;
Cupidity through practice of purity;
Unstability through Trataka and Pranayama,
Upasana and Japa;
Angularity through practice of humility;
Eccentricity through practice of right conduct;
Irritability through practice of patience, forbearance.
You will enter into Samadhi and attain Kaivalya.

BACKBITING

This is a dirty, abominable habit of petty-minded people. Almost all are victims of this dire malady. This has become an ingrained habit of narrow-hearted, mischievous people. This is a Tamo-Guna Vritti. The Lila of this world is kept up by this evil habit of man. It is Maya's strong weapon to spread restlessness throughout the world. If you see four men sitting in a

Then **stretch your thumbs out to the sides and down**, so that they end up pointing downwards toward the earth. This activates Large Intestine 4 (Hegu). Large Intestine 4 is found in the webbing between the thumb and index finger. It is called the "eye of the hand"; this area is also known as the "Tiger's Mouth."

Slowly draw the elbows back and lower the hands until your palms are facing down beside the "eye of the hip" (the iliac crest) with the "eye of the hand" (Large Intestine 4) aligned with the "eye of the hip. "Be aware of the Tan Tien (Yi, the abdominal brain) and expand your mind out into space, the Cosmos and the universe. Remember: The fingers and the energy point act just like a laser to help guide the universal force flow; as soon as you focus on the fingers or the palms you are starting to use your own energy. Feel your Tan Tien and the crown full with Chi. Just use your second mind intention, lightly aware of the area between the hips and LI-4 points. Focus at Tan Tien and the universe. This will activate the lungs and large intestines. **Hold for a 30 second count** and gradually you will feel the ascending colon and the sigmoid colon have been activated; you may feel some movement around this area.



Fig. 8.10 *Activate the Organ Energy.*

Use your Yi to rotate your hands so that the fingers first point out, then back, turn the palms up and finally point the middle finger in toward the eye of the hip. Tan Tien and the universe - **95 % aware of the 'Tan Tien and the Universe' and 5 % aware of energy flowing back and forth between the tips of the middle fingers** (Pericardium 9); feel the Chi passing through the hips. This will activate the pericardium.

group, think that some backbiting is surely going on there. If you behold that four Sadhus are talking, you can at once infer without any shadow of doubt that they are backbiting against some person or other. A Sadhu who is engaged in contemplation will always be alone. The Sadhu will be talking: "The food of that Kshetra is very bad. That Swamiji is a very bad man." Backbiting is more prevalent amongst the so-called Sadhus than amongst householders. Even educated Sannyasins and householders are not free from this dreadful disease.

The root cause of backbiting is ignorance or jealousy. The backbiter wants to pull down or destroy the man who is in a prosperous condition by false vilification, slander, calumny, false accusation, etc. There is no other work for a backbiter except scandalmongering. He lives on backbiting. He takes pleasure in backbiting, mischief-making. That is his Svabhava. Backbiters are a menace to society. They are the worst criminals. They need capital punishment. Double-dealing, crookedness, diplomacy, chicanery, quibbling, tricks, artifices are the retinues of backbiting. A backbiter can never have a calm, peaceful mind. His mind is always planning or scheming in wrong directions. An aspirant should be absolutely free from this dreadful vice. He should walk alone, live alone, eat alone and meditate alone. If a man who has not removed jealousy, backbiting, hatred, pride, selfishness says: "I am meditating for six hours daily", it is all nonsense. There is no hope of getting a meditative mood even for six minutes unless a man removes all these evil Vrittis and purifies his mind first by selfless service for six years.

BOASTING

ATMASTUTI

Boasting is ostentatious display or bragging. It is an expression of pride.

To boast is to talk vaingloriously, to speak proudly, to magnify or exalt one's own self.

Boast not of what you can or would do. Actions speak louder than words. Doing is the only practical achievement.

Humility is natural to wisdom. Boasting is natural to ignorance.

The boaster may not know a great deal, but it is certain that he does not know as much as he thinks he knows.

The sun has no need to boast of his brilliance, nor the moon of her effulgence. Honest and courageous people have very little to say about their honesty or their courage.

An empty vessel alone makes much sound. So is a boaster. He talks loudly of himself. His neighbours do not like this. They know his real worth. They laugh at him.

Where boasting ends, then dignity begins.

Usually the greatest boasters are the smallest workers. The deep rivers pay a larger tribute to the ocean than shallow brooks and yet empty themselves with less noise.

He is only a beggar who can count his worth.

A braggart should fear this; he will be found an ass soon.

You wound your modesty and make foul the clearness of your deservings when you yourself publish and advertise them.

BRIBERY

The habit of taking bribes is very common. If you ask anybody working in any office: "What is your salary, Mr. Jayadev?" He will say: "Well, my salary is only Rs. 50/- but my income is about Rs. 75/-." This income is nothing but bribe. People are ignorant. Even the so-called educated people have no idea of the law of action and reaction, Samskaras and their force. If you take bribe, you will be punished for this wrong action and the Samskara of taking bribes will force you to take bribes even in the next birth. You will be a dishonest man even in the next birth. Your thoughts and actions are registered in the subconscious mind. You carry your dishonesty from birth to birth and undergo enormous sufferings. Reduce your wants and live honestly within your means. You will have a clean conscience. You will be ever free from anxieties and worries. You will have a peaceful death. I suppose you now understand the gravity of the law. Become an honest man and be true from this very second you read these lines. Never, never join those offices which are amenable to corruption and temptations. You will be corrupted. The educational line is very good. There are very few chances of taking bribes or committing sins. You can lead a quiet life. There are plenty of holidays for study of religious and philosophical literature and for doing practical Sadhana. You can easily evolve rapidly in the spiritual line.

CARES, WORRIES AND ANXIETIES

CHINTA, PIDA, AUTSUKYA

Cares, worries and anxieties are the products of Avidya or nescience. When the mind rests in Brahman during sleep, when the mind is disconnected from the body by chloroform, anaesthesia, there is no pain; there are no cares, worries and anxieties. From this it follows that cares, worries and anxieties are all pure mental creation. They do not at all exist in the blissful Self. If nescience, which is the root cause, is annihilated, these cares and worries die of themselves. Therefore you will have to treat the cause and remove the original cause by getting knowledge of the Self or Atman.

The Sanskrit word for anxiety is Chinta. Cares, worries and anxieties are one and the same. Only sounds are different, like water and aqua, pani and jal. They co-exist. A man says: "I have to take care of my children and old parents; I have to take care of my wife, house and lands; I have to take care of my cows; I have to take care of my body." Identification or Abhimana is the chief factor that brings cares and worries. This Abhimana is brought about by ignorance. When the little ignorant Jiva mistakes this impure perishable body for the pure imperishable Self, all these evils crop up. All originate from this body only. Body is your first enemy. You will have to treat this as a dog and have no Abhimana. Whenever hunger and thirst oppress you, give some food and drink, just as you look after your cows and bulls. This is all. Be a Udaseena. Be indifferent.

Looking at the face in the mirror fifty times daily, application of soap, powder and scented oils, wearing ties, collars and fashionable apparel, intensifies Deha-Abhimana and augments cares. The identification of the Self with this body is extended with those who are connected with this body, such as, wife, son, house, father, mother, sister, etc., and cares increase a hundredfold. You will have to take care of all these people. You will have to take care of the toys of your son also, because the toys are connected with your son. There is absolutely no end for these cares and worries. Man creates for himself all these cares. No one is to blame. Just as the silk-worm and the spider create a web for their own destruction, out of their own saliva, so also, man creates these cares and worries for his own destruction out of his own ignorance. The clouds arise from the ocean by evaporation of the heat of the sun and then obstruct the sun itself which gives heat for the rising of the cloud. So also, cares and worries are created by man for his annihilation. How can these cares and worries have real existence in the Atman which is an embodiment of bliss and peace? Destroy Abhimana of the body. All connection and cares will die by themselves, this very second. Do this now and feel the bliss. There is no use of hearing the method for preparing a custard pudding. Eat the pudding and rejoice. This is what I expect from you without delay.

A businessman worries himself: "How can I pay my debts? There is trade depression now. The business is dull." The college student worries himself: "I have appeared for the M.Sc. examination. I don't know whether I will pass or not. Then I don't know what I will do in order to earn a livelihood. There is keen competition everywhere nowadays. There is no scope of employment in any office. Even M.Sc.'s and graduates get only Rs. 50/- in sugar factories. For that post also there are no vacancies. My father has sold all his property for my education. Now he is starving. I am thinking of opening a hair-dressing saloon or a shop for manufacturing shoes. I now realise the dignity of labour. I shall now follow the teachings of Mahatma Gandhi and his path. The cinema is no doubt paying now. But I have not got the gift of an actor, not even a good voice. I am the only prop of my parents." The husband worries himself: "My wife had serious abortion on two occasions. She is now in the family way. It is six months now. I have no money to pay the doctor. I have not saved a single pie. I don't know what to do." The Raja says: "My tenants have not paid their taxes this year. They say that crops have failed. My treasury is empty. I have spent away about two lakhs for my trip to the continent. I donated five lakhs to the Earthquake fund." He also cries. Thus you see no one is free from cares and worries in this world. But a Yogi, a Jnani or a Bhakta is absolutely free from all these.

The hairs of a man turn grey within a couple of hours if he worries himself much. Worries have got a corroding effect on the brain tissues, nerves and cells. Worries impair digestion, bring exhaustion and sap the vitality and vigour of man. Worries make a man anaemic and bloodless. The mental energy is dissipated by cares and worries. Worries, when combined with fear and anger, kill a man in a second. In fact worries shorten the life of man. Many diseases take their origin in worries. Worries weaken the will. A man of worries cannot turn out any good work with attention. He is careless and listless. He cannot apply himself steadily to any work. He is a living dead man. He is a burden to his family and to mother earth.

Some people have developed a worrying habit. You cannot find any bit of cheerfulness on their faces. They always have "castor-oil faces" or "quinine-faces." Have you carefully noticed the face of a man when he takes a dose of quinine or castor oil? They are gloomy and depressed. Such people should not come out of their rooms. They pollute the world atmosphere and the thought-world and affect other people. Gloomy is an epidemic disease. All those who come in contact with gloomy people are immediately affected. A gloomy man should cover his face when he comes out.

The mind that worries much, takes a merry-go-round inside. I think you know what I mean by merry-go-round? A worrying habit is formed in the mind. The worrying thoughts recur again and again and the mind moves in a circle.

Never worry yourself over any matter. Be always cheerful. Think of the opposite which is cheerfulness. Use your reason and commonsense always. Be sagacious and prudent. You can avert dangers and failures. You can overcome any shortcomings. If you are careful and also vigilant, if you are honest and straightforward, if you discharge your daily Sandhya, meditation, prayer, and other duties of Varnashrama, and if you speak truth and practise celibacy, nothing can harm you. Even Brahma, the creator, will be afraid of you. Everything will go on smoothly. You will have an unruffled life. Even difficulties will roll on smoothly without affecting you a bit. Why then should there be room for cares and worries. Have always a balanced mind. Always smile and laugh. Develop this habit. Even if any difficulty manifests, keep a cool mind. Remember the formula: "EVEN THIS WILL PASS AWAY." Reflect and assert: "Why should I unnecessarily worry myself? I have gained power now. I know the ways to pull on in this world now. I am not afraid of anything. I have a strong will now. I meditate on Atman. Nothing can upset me now. I am invincible. I can move the world. I am a dynamic personality. I know how to adjust myself to my environments and surroundings. I can influence people. I know the art of suggestion and auto-suggestion. I will never worry myself about anything. I am always peaceful and strong. I derive bliss from within. I always say now: 'Mr. Worry, good-bye unto you.' I am a different man now. I am made of a sterner stuff. Worries are now afraid to show their faces to me. I can also remove the worries of millions of other people."

O little man of little faith! See how the birds are care-free and happy. Become as care-free as the bird or a Paramahamsa Sannyasin. Have faith in your inner Self. Rely on your Self. Stand up and assert the divine majesty of your Self. Thou art not this perishable body. Thou art the All-pervading blissful Self. Even if you have nothing to eat, even if you have nothing to wear, never budge an inch from this position. Blessed is he who is care-free and who is resting in his own Svarupa, always smiling and laughing and radiating joy unto others.

CARELESSNESS AND FORGETFULNESS

ASAVADHANA, VISMRITI

Carelessness and forgetfulness are two other evil qualities that stand in the way of success of man. A careless man cannot do any work in a neat and proper manner. These are qualities born of Tamas. Application and tenacity are unknown to a careless and forgetful man. There is lack of attention in him. He loses his key, shoes, umbrella and fountain pen daily. He cannot produce papers and records to the office at the proper moment. He blinks. Follow the lessons in memory-culture and you can have a good memory within a short time. You will have to develop a strong desire to remove these qualities and develop their opposites. This is important. Then alone the will and the subconscious mind will do the work for you. Keep your money in the inside pocket. Keep your spectacles in the side pocket. Always count your belongings whenever you travel in railway trains. Keep accounts regularly.

COVETOUSNESS

LALASA

Covetousness is greed or avariciousness. Inordinate desire of wealth is covetousness.

All virtue, all honesty and peace run away from a man of covetousness.

A covetous man is always poor and discontented. A covetous man is a fool. He is a miserable wretch. He lives in perpetual slavery, fear, suspicion, sorrow, discontentment. He never enjoys life.

A covetous man heaps up riches not to enjoy, but to have them. He starves himself in the midst of plenty. His sons squander his money quickly.

Covetousness is the first vice in corrupt nature which moves and the last which dies.

A covetous man acquires money by unjust or unlawful means. He leads a miserable life. His lot is pitiable and lamentable!

COWARDICE

KATARYA

Cowardice is want of courage. It is timidity.

A coward is a faint-hearted person. He is afraid of danger. He fawns upon those who are above him. He falters. He yields to fear. He dreads pain or harm unduly.

A coward is a poltroon. He is a pusillanimous man. He is a dastard.

A coward dies many times before his death. A coward can never attain God-realisation.

Cowardice is the one deadly sin. Cowardice is loss of fame.

A lie is contemptible, chiefly because it is cowardly.

CROOKED-MINDEDNESS

KAUTILYA

Crooked-minded people also are to be found in abundance in the world. Crooked-mindedness is a Tamo-Guna Vritti. Such people are always crooked in talking and arguing. They indulge in quibbling and wrangling. They are always fond of vain talks. They will assert emphatically that only their statement is correct and the statements of others are false and absurd. They cannot keep quiet even for a single minute. Their arguments are very peculiar. They will not argue with any person in a respectable manner. They will take to vituperation and fall out in the end. Cultivation of nobility, politeness and straight-forwardness will eradicate this evil quality.

DEPRESSION

VISHADA

Depression is a failing in or sinking. It is dejection, cheerlessness.

Depression causes pessimism. It stultifies all effort; it kills initiative, produces despair and sickness of mind and body.

Depression is falling of the spirits. It is low spirits or dejection. It is a lowering of vital powers. It is a state of sadness. It is want of courage or animation as depression of the mind.

Hope, courage and work can overcome all depression and fear, and convert your mountains of trouble into molehills. Things are never so bad as you believed them to be.

Stand up and gird up your loins. Pray. Do Japa. Do Kirtan, Meditate on the All-Blissful Atman. Cultivate cheerfulness. Depression will take to its heels.

Depression is a negative state. It cannot last for a long time. Be cheerful. Positive always overcomes the negative.

Chant OM. Do Pranayama. Study my article “Thy Real Nature.” Hear the record “Thy Real Nature.” You will be filled with new strength, joy and cheer.

Thy real nature is Satchidananda. Realise this and roam about happily.

Aspirants get moods of depression occasionally. These moods may be due to indigestion, cloudy condition, influence of lower astral entities, and revival of old Samakaras from within. Treat the cause. Remove the cause. Do not allow depression to overpower you. Immediately take a brisk, long walk. Run in the open air. Sing divine songs. Chant OM loudly for one hour. Walk along the sea-side or river-side. Play on the harmonium if you know the art. Do some Kumbhakas and Sitali Pranayama. Drink a small cup of orange juice or hot tea or coffee. Read some of the elevating portions of Avadhoota Gita and Upanishads.

DIFFIDENCE

AVISHVASA

Diffidence is want of confidence, want of self-reliance.

A diffident man lacks faith in his own self. He is distrustful of his own self.

Diffidence is want of confidence in oneself. It is lack of trust in one's own power, correctness, wisdom, judgment or ability. It is timidity, self-distrust, shyness.

Diffidence checks resolution and obstructs performance of actions. It sinks you down.

Cultivate confidence and self-reliance. Think less of what others may think of you. This will help you to overcome diffidence and aid you to self-possession, confidence and self-reliance.

We say: "Ram, fearing the critics, wrote with diffidence." "Krishna failed through diffidence alone." Many people are always diffident. They have no self-confidence. They have energy, capacity and faculty. But they have no confidence in their own powers and faculties and in getting success. This is a kind of weakness that brings failures in all attempts. A man appears on the pulpit to deliver a lecture. He is a capable man. He is well-read. But he is diffident. He thinks foolishly that he would not be able to produce an impressive speech. The moment this kind of negative thought comes to his mind, he becomes nervous, he staggers and gets down the platform. This failure is due to lack of self-confidence. You may have little capacity and yet you must have full confidence that you will succeed in your venture. There are people who have very little substance and capacity and yet they can thrill the audience. This is due to their self-confidence. Confidence is a kind of power. It develops will.

Always think: "I will succeed. I am fully confident of my success." Never give room for negative quality, diffidence, to enter your mind. Confidence is half success. You must fully know your real worth. A man of confidence is always successful in all his attempts and ventures.

DILLY-DALLYING

(Aimless Wandering)

VRITHA PARIBHRAMANA

Some aspirants have got a habit of wandering aimlessly. They cannot stick to one place even for a week. The wandering habit must be checked. They want to see new places, new faces and want to talk with new people. A rolling stone gathers no moss. A Sadhaka should stick to one place at least for a period of twelve years (one Tapas period). If his health is delicate, he can stay for six months in one place during summer and rainy season and in another place for six months during winter. During winter he can stay either at Rajpur (Dehradun) or Rishikesh. During summer he can go to Badrinath or Uttarkashi. Sadhana suffers if one wanders constantly. Those who want to do rigorous Tapas or Sadhana and study must stay in one place. Too much walking produces weakness and fatigue.

DISHONESTY

DHURTATA

Dishonesty is another evil quality. Almost all have got some form of dishonesty or another. Honest people are very rare. Dishonesty is the hand-maid of greed or avarice. Wherever there is dishonesty, there are double-dealing, diplomacy, cheating, fraud, chicanery, etc. These are the retinues of dishonesty. Greed is the chief officer of passion. For the gratification of lust, all dishonest practices are indulged in. If lust and greed are eradicated the man becomes honest. A dishonest man cannot thrive in any kind of business. Sooner or later, his dishonesty will be found out. He will be hated by all men in society. He will fail in all his ventures. He will not hesitate a bit to take bribes and tell lies. To cover up an untruth he will tell ten lies. To establish the ten lies, he will tell fifty lies. He will not be

Rotate the hands again until the fingers are pointing forward with the **palms facing up**. Align the knife edges (Small Intestine 3) with the eyes of the hip. 'Focus at Tan Tien and the Universe'. Be lightly aware of the energy passing back and forth between the two hands. This will activate the heart and small intestine.



Fig. 8.11 *Activate the Heart and Small Intestine.*

Absorb the Heavenly Force Washing the Bone Marrow - Crown to Soles



Extend the arms forward to chest height with the palms facing upward.



Fig. 8.12 *Draw Heavenly Energy into the Palms.*

Become aware of the **Tan Tien, the Crown and the Star above you**. Expand your mind (YI) out to the universe and connect to the galaxy. Be aware of the palms and the crown which are connected to the galaxy. Activate the Laogong point (Pericardium 8).

Feel the heavenly energy come directly to your palms, and be aware of the violet light of the North Star and the red light of the Big Dipper both shining radiantly.

able to speak even truth with force. He has a rotten Antahkarana. Develop honesty by eradicating dishonesty. Be content with your lot. Never crave for more. Lead a simple life. Let your thoughts be lofty. Fear God. Speak the truth. Love all. See your own self in all. Then you will not be dishonest in your dealings with others. You will be prepared to sacrifice even the very little that you possess. You will develop a large heart and a magnanimous nature. That is what is exactly wanted of you if you want to succeed in life and in God-realisation.

ENVY

IRSHYA

Envy is grief and burning of heart at the sight of another's success and prosperity.

Envy is spite, hatred, ill-will; envy is an evil eye.

Envy is uneasiness, mortification or discontent at the sight of another's superiority or success, accompanied with some degree of hatred or malignity and often or usually with a desire or an effort to deprecate the person envied.

Envy is the daughter of pride and the author of murder and revenge.

Envy is like a fire. It consumes a man quickly.

If you rejoice in the happiness of another, you increase your own happiness.

One is envious of that which is another's and to which he himself has no right or claim.

He is jealous of intrusion upon that which is his own or to which he maintains a right or claim.

Envy is a venom which consumes the flesh and dries up the marrow of bones.

Deformed persons, eunuchs, old men and bastards are envious. Fellows in office, relatives, envy their equals when they are raised to a better status.

Contentment, friendliness, satisfaction, well-disposed nature are the opposites of envy.

Crush this envy, dire enemy of peace, devotion and wisdom through the practice of nobility, magnanimity and contentment.

EVIL COMPANY

DUHSANGA

The effects of evil company are highly disastrous. The aspirant should shun all sorts of evil company. The mind is filled with bad ideas by contact with evil companions. The little faith in God and scriptures also vanishes. A man is known by the company he keeps. Birds of the same feather flock together. These are all proverbs or wise maxims. They are quite true. Just as a nursery is to be well-fenced in the beginning for protection against cows etc., so also a neophyte should protect himself very carefully from foreign evil influences. Otherwise he is ruined totally. The company of those who speak lies, who commit adultery, theft, cheating, double dealing, who indulge in idle-talks, backbiting, talebearing, who have no faith in God and in the scriptures etc., should be strictly avoided. The company of women and of those who associate with women is dangerous.

Bad surroundings, obscene pictures, obscene songs, novels that deal with love, cinemas, theatres, the sight of pairing of animals, words which give rise to bad ideas in the mind, in short anything that causes evil thoughts in the mind constitutes evil company. Aspirants generally complain: “We are doing Sadhana for the last fifteen years. We have not made any solid spiritual progress.” The obvious answer is that they have not totally shunned evil company. Newspapers deal with all sorts of worldly topics. Aspirants should entirely give up reading of newspapers. Reading of newspapers kindles worldly Samskaras, causes sensational excitement in the mind, makes the mind out-going, produces an impression that the world is a solid reality and makes one forget the Truth that underlies these names and forms.

FANATICISM

Fanaticism is wild and excessive religious enthusiasm. It is extravagant or frenzied zeal.

Nothing has brought more prejudice to religion or brought more disparagement upon truth than fanaticism or the boisterous or unreasonable zeal.

Be not so bigoted to any custom as to worship it at the expense of truth.

Earnestness is good, but fanaticism overdoes and is consequently reactionary.

Fanaticism is the offspring of false zeal and superstition. It is the father of intolerance and persecution.

Fanaticism is the false fire of an overheated mind.

The blind fanaticism of one man causes more evil than the combined efforts of one hundred rogues.

Bigotry is narrow; fanaticism is fierce; superstition is ignorant. Bigotry is obstinate and unreasonable attachment to a cause or creed.

Fanaticism and bigotry usually include intolerance which is unwillingness to tolerate beliefs or opinions contrary to one's own.

Superstition is ignorant and irrational religious belief.

Credulity is not distinctly religious, but is a general readiness to believe without sufficient evidence, with a proneness to accept the marvellous. Credulity is weak; intolerance is severe.

Bigotry has not the capacity to reason fairly; fanaticism has not the patience; superstition has not the knowledge and mental discipline; intolerance has not the disposition.

Bigotry, fanaticism, and superstition are perversions of the religious sentiment. Credulity and intolerance often accompany scepticism or atheism.

Cynicism, indifference, latitudinarianism are the opposite of fanaticism.

FASHION: A TERRIBLE CURSE

This subject is not foreign to Karma Yoga. He who wears simple dress, who is free from this terrible scourge of fashion only can do Karma Yoga. One should be fully aware of the disastrous effects of fashion. Hence I have introduced this article here.

People are dying of fashion. Gents and ladies have become absolute slaves of fashion. If there is a slight error in the cutting of a gown or uniform, there are damage suits in courts in London and Paris against tailors. Even Bombay and Delhi have become Paris nowadays. You can see the multifarious fashions in the evening. Fashion consists in half-nudity. They will call this as scientific, hygienic ventilation of the exposed parts. Half the chest, half-arms, half-legs, must be exposed. This is fashion. They have full control over their hairs. This is their Siddhi or psychic power. They can cut it and dress it in any way they like in a hair-dressing saloon. Fashion increases and excites passion.

Even a poor lady at Bombay pays five rupees for making a single ordinary frock. She never thinks a bit how her husband will be able to manage all these things. Poor husband! a slave of passion! a miserable soul! borrows here and there something, takes bribes in various ways, and pleases his wife anyhow with an outward smile and an inward burning resentment. He kills his conscience, destroys his intellect and walks self-deluded in this world, and gets carbuncles and pyorrhoea as a result of his bad actions. He cries when he is in trouble; "I am a great sinner. I cannot bear this pain. I have done many bad actions in my previous birth. O Lord! forgive me, save me." But he never tries a bit to improve his lot in this birth.

The whole world can be clothed out of the cuttings of the vain fashionable people. Money is wasted enormously in fashion. Man wants after all very little on this earth, a pair of ordinary clothes, four breads and a tumbler of cold water. If this money that is wasted in fashion is utilised in virtuous actions, in charity and service of society, man will be transmuted into Divinity. He will be in the enjoyment of eternal peace and bliss. What do you see now, instead, in fashionable people? Restlessness, anxiety, worry, fear, depression and pallor of face. They may be dressed in silken gowns or dinner suits in up-to-date fashion and style with stiff double collar, ties and bows. But you see in their faces cheerlessness and ugliness. The canker of worry, greed, passion and hatred has eaten the very core of their hearts.

If you ask a Baron of England to remove his boots and hat when he is about to enter a Hindu temple, he feels he has lost all personality. Look at the vanity of an egoistic man! A small piece of leather, a card-board covered with a cloth make up a mighty Baron; minus these he dwindles into an airy nothing. There is no spirit or strength in him. The pulse fails at the wrist. He cannot talk now with the same force. The world is full of people with a small heart and little understanding. They imagine that turbans and fashionable long-coats, hats and boots constitute a big man. A really big man is one who is simple and free from egoism and Raga-Dvesha (likes and dislikes).

Why do ladies and gents put on fashionable dress? They want to appear as big people in the eyes of others. They think they will get respect and honour by putting on fashionable dress. The wife wants to appear beautiful in the eyes of her husband. She wants to attract him. The husband puts on fashionable dress to attract his wife. The sister of ill-fame wants to get more customers by putting on fashionable dress. This is all delusion. Can a fashionable dress give real beauty? This is all artificial decoration, temporary false glittering, decaying false beauty! If you possess good virtues such as mercy, sympathy, love, devotion and forbearance, you will be respected and really honoured. This will give everlasting beauty even though one is clad in rags.

Fashion is a terrible curse. It is a dreadful enemy of peace. It infuses evil thoughts, lust, greed and devilish tendencies. It fills the mind with worldly taints. It begets poverty. Fashion has made you beggar of beggars. Annihilate this desire for fashion to the very root. Wear simple clothing. Have sublime thinking. Do not keep company with fashionable people. Remember those saints who led a simple life and those living persons of today who are very simple. Simplicity will cause piety. It will infuse divine thoughts. You will be free from worry and unnecessary thoughts. You can devote more time to divine contemplation and spiritual pursuits.

A Sattvic man or lady is really beautiful. He or she does not require any artificial decoration with gold pins, with nose screws or with any ornament or fashionable dress. Millions of people are attracted unconsciously towards them even when they are in very poor dress.

How simple was Mahatma Gandhi in his dress! He had a loin cloth only. How simple was Ramana Maharshi? He had a Kaupeen only. A loin cloth and a Kaupeen were thier personal effects. They did not want suit-cases or trunks to carry their dresses. They were as free as a bird. Avadhutas like Krishnashram of Gangotri, Brahmendra Sarasvati of Sendamangalam, Salem, South India, have not even a Kaupeen. They are absolutely nude. They are now in the same state as they were when they were born.

This body is like a big wound or ulcer with various filthy discharges. It has to be bandaged simply with any piece of cloth. Silken, laced borders, frills etc., are not necessary. It is the height of folly to decorate this filthy perishable compound of flesh and bone with artistic borders. Have you realised your folishness now? Stand up. Give up fashion now. Take a vow. Give me a definite promise that you will use simple clothing from this very second.

You came naked. You will go naked. Your silken waist-thread and upper-cloth even will be snatched for the use of your grandchildren, when you are on the death-bed. Why, then, do you make these ceaseless selfish efforts for earning money and preparing fashionable dress? Realise your folly. Learn to discriminate. Get wisdom of the Self and rest in ever-lasting peace.

O fashionable man! O fashionable woman! O ye slayers of the inner Atman! Why do you waste your time, energy and life in vanity, in running after fashionable dresses? This is highly preposterous. The beauty of beauties, the undecaying source of beauty, the ever-lasting beauty is ever shining in the chambers of your hearts. The whole beauty of this world is a mere shadow or reflection of that fountain-head of beauty. Purify your heart. Control your mind and the senses. Sit quietly in a room and meditate on this Beauty of beauties—your Immortal Friend, Atman, or the highest Self. Realise this Self. Then and then alone you are really beautiful. Then and then alone you are really happy. Then and then alone you are really rich. Then and then alone you are really a big man.

FAULT-FINDING

This is a detestable old habit of man. It clings to him tenaciously. The mind of the aspirant who always tries to poke his nose into the affairs of other men is always out-going. How can he think of God, when his mind is ever engaged in finding the faults of others?

If you spend even a fraction of the time that you waste, in finding your own faults, you would have become a great saint by this time. Why do you care for the faults of others? Purify yourself first. Improve yourself first. Reform yourself first. Wash the impurities of your own mind. He who applies himself diligently to his spiritual practices cannot find even a single second to look into the affairs of others.

If the fault-finding nature dies, there will be no occasion for criticising others. Much time is wasted in backbiting, tale-bearing, scandalmongering, etc. Time is most precious. We do not know when will Lord Yama take away our lives. Every second must be utilised in Divine contemplation. Let the world have its own ways. Mind your own affairs. Clean your mental factory.

That man who does not interfere with others is the most peaceful man in the world.

Fault-finding is the art of pointing out faults. It is making of frivolous objections. It is carping criticism.

Do not be quick to tell people of their faults. Look for your own faults.

To find fault is easy; to do better may be difficult.

Everyone is eagle-eyed to see another's faults!

Endeavour to be always patient of faults and imperfections of others, because you have many faults and imperfections which require forbearance. If you are not able to make yourself that which you wish, how can you expect to mould another in conformity to your will?

Fault-finding nature only indicates narrowness of mind and ill nature.

Never speak of the faults if you do not think thereby to effect some useful purpose.

Develop the good-finding nature in others. Every man has his own virtues and good points which can be appreciated. The fault-finding nature will perish.

A fault-finder is dishonoured and condemned by the society.

Why do you poke your nose into other people's affairs, when you yourself have a thousand and one faults? Correct your faults first. Others will take care of their own faults. Mind your business. Do not interfere with other people. You can enjoy peace.

A Rajasic man sees only the defects in others. He cannot see their virtues. He even superimposes vices on others when they have not got these evil traits. But a Sattvic man sees only the virtues in others.

A sage beholds only the Atman in all beings. He never looks either into defects or virtues.

FEAR

Fear is a great human curse. It is a negative thought. It is your worst enemy. It assumes various forms, viz., fear of disease, fear of death, fear of public criticism, fear of losing your property or money, etc.

Fear blights many lives, makes people unhappy and unsuccessful. Think you are immortal, fearless Atman (Amrita, Abhaya). Slowly the fear will vanish. Develop the positive virtue, namely, courage. Fear will slowly disappear.

The power of imagination in the mind intensifies fear. Attachment to the body (Moha, Dehadhyasa) is the cause of all fear. He who can throw off the physical sheath (Annamaya Kosha) either by Yoga or Jnana will be free from fear.

He who has conquered fear has conquered everything, has gained mastery over the mind.

Some people can bravely face the shell or the shot in the battlefield. But they are afraid of public criticism and public opinion. Some can face a tiger fearlessly in the forest. But they are afraid of the surgeon's knife. You should get rid of fear of all sorts.

The one idea that you are the Immortal Self (Atman) can destroy efficiently fears of every description. This is the only potent tonic, the one sure panacea for this dire disease of fear.

Fear is a very great obstacle in the path of God-realisation. A timid aspirant is absolutely unfit for the spiritual path. He cannot dream of Self-realisation even in one thousand births. One must risk the life, if he wants to attain immortality.

The spiritual wealth cannot be gained without self-sacrifice, self-denial or self-abnegation. A fearless dacoit who has no Deha-Adhyasa is fit for God-realisation. Only his current will have to be changed.

Fear is not an imaginary non-entity. It assumes solid forms and troubles the aspirant in various ways. If one conquers fear, he is on the road to success. He has almost reached the goal.

Tantrika Sadhana makes the student fearless. This is the one great advantage in the line. He has to make practices in the burial ground, by sitting over the dead body at mid-night. This kind of Sadhana emboldens the student.

Fear assumes various forms. There are fear of death, fear of disease, scorpion-phobia, fear of solitude, fear of company, fear of losing something, fear of public criticism in the form of "What will people say of me?" Some are not afraid of tiger in the forests. They are not afraid of gun-shots in the battlefield. But they are awfully afraid of public criticism. Fear of public criticism stands in the way of the aspirant in his spiritual progress. He should stick to his own principles, and his own convictions, even though he is persecuted and even though he is at the point of being blown up at the mouth of a machine gun. Then only he will grow and realise.

All aspirants suffer from this dire malady, fear. Fear of all sorts should be totally eradicated by Atma-Chintana, Vichara and devotion and cultivation of the opposite quality, courage. Positive overcomes negative. Courage overpowers fear and timidity.

Fear is a painful emotion excited by danger. It is apprehension of danger or pain. Fear is an emotion excited by threatening evil or impending pain, accompanied by a desire to avoid or escape it and to provide for one's security.

Fear is born of ignorance. It is a negative Vritti or wave in the mind. It has no real form or existence. It is a product of imagination.

Constant fear saps your vitality, shakes confidence and destroys your ability. It makes you powerless. It is an enemy of your success. Therefore, shun fear and be courageous always.

From fear proceeds misfortune. The fears of a coward expose him to dangers. Terrify not yourself with vain fears. Be bold, friend.

Fear is a kind of bell which rings in the mind to make it quick and alert for the avoidance of danger.

Fear is the beginning of all evil. Therefore, conquer fear through meditation on the fearless Brahman or cultivate the opposite virtue, courage.

Poverty and failure are due to thoughts of fear.

If you are afraid of something, look at it in the face. Fear will vanish.

What paralysis is to the physical body, so is fear to the mind. It paralyses the mind and makes you powerless.

Fear is the most destructive emotion. It breaks down the nervous system and undermines your health. It creates worry and renders happiness and peace of mind impossible.

Wherever there is attachment to objects, there are fear and anger. Anger and worry are the long-standing associates of fear.

Fear assumes various forms. There are fear of disease, fear of death, fear of loss of property, fear of enemy, fear of public criticism, fear of scorpion, fear of cobra, and fear of wild animals.

Fear in all its different phases is the greatest enemy of man. It has destroyed the happiness and efficiency of man. It has made more men cowards, more people failures.

Fear of God is the beginning of wisdom. This is virtuous fear, the effect of faith.

There is vicious fear, the effect of doubt.

Half of your fear is baseless and imaginary.

Fear kills effort and stultifies endeavour.

Alarm, apprehension, awe, consternation, dismay, dread, fright, horror, misgiving, terror, timidity, trepidation are synonymous with fear.

Boldness, assurance, bravery, confidence, courage, fearlessness, fortitude, trust are the opposites of fear.

FICKLENESS

Fickleness is unsteadiness of the mind. It is inconsistency or irresoluteness.

A fickle mind oscillates and changes every second. It is never steady. It ever wanders.

A fickle-minded man now promises and breaks his promises the next second. You cannot rely on him.

A fickle memory is bad, a fickle course of conduct is worse; but a fickle heart and purpose is the worst of all.

A fickle-minded man is unduly changeable in feeling, judgment or purpose. He is wavering, inconsistent and capricious.

A fickle-minded man is like the restless sea or the restless monkey.

A fickle-minded man is irresolute, shifting, vacillating and whimsical.



Fig. 8.13 *Hold the Big Dipper.*

Picture yourself holding the handle of the Big Dipper and turn the 'cup' pouring the light over your head. Draw this light in through the palms and the crown point and feel it washing your bone marrow. Always remember your Tan Tien. **Direct the sensations down through the skull, cervical vertebrae, clavicle, scapulas and sternum. Activate your thymus gland and continue drawing the healing heavenly light down through the rib cage, arms, spine, hips, femurs and calf bones, feet and toe bones. Be aware of the soles bubbling up to the perineum and up to the crown**.

Lightly rock yourself like riding a horse; this will help keep your spine open and Chi can flow easily throughout the practice.

Absorb the Earth Force and the Other Side of the Galaxy

Rotate the arms until the **hands are palms down**.

Raise the index fingers slightly and extend the thumbs first towards each other and then toward the ground. Be 95% aware of the Tan Tien and the Universe, and 5 % aware of the index fingers and the big toes. Wait until you feel the Chi enter. Fill the joints of the fingers and up to the wrists; feel 'tense but not tense' and let the **Chi continue to fill the joints** up to the elbows, up to the shoulders and gradually up to the neck and the head. Go from the toes up the legs to the hips and on into the spine and the rib cage **completing all the joints of the body**.

Be aware of the Tan Tien and the universe and only slightly aware of the palms (Laogong), the soles of the feet (Kidney 1-Bubbling Spring), and the perineum (Conception Vessel 1-Hui Yin) bubbling. Activate these points, feel the earth energy and continue smiling through the earth to connect with the galaxy, Milky Way, and the universe. Draw this light in through the palms and soles and let it wash up through the center of your bones from the feet up. Let it **steam and cleanse your marrow**. Picture any impurities or illness dripping out of your bones and draining down into the earth, where they will be recycled and purified.



Fig. 8.14 *Open the index fingers.*

A fickle-minded man always fails in any attempt. Success is unknown to him. He weeps and regrets.

A fickle-minded man has a wavering disposition. He is unsteady in opinion or purpose.

Fickleness of mind is a great obstacle in meditation. Light Sattvic diet and practice of Pranayama will remove this state of mind. Do not overload the stomach. Walk briskly in your compound hither and thither for half an hour. As soon as you have made a firm resolve, you must carry it out promptly at any cost. This will remove fickleness of mind and develop your will power.

Constancy, decision, determination, firmness, fixedness, immutability, resoluteness, steadfastness, steadiness are the opposites of fickleness.

Fickleness is due to too much Rajas or passion. Annihilate Rajas by increasing Sattva or purity or harmony. Take Sattvic food. Practise Japa, Kirtan, concentration, Trataka or gazing, Pranayama. Study sacred scriptures. Fickleness will take to its heels. Steadiness alone will prevail.

FILM-GOING

CHALANACHITRA-DARSANAM

Drinking, meat-eating, hearing vulgar music, company of prostitutes, attendance at nautch parties, theatres and cinemas, excite passion and throw the victim into the fire of hell. The Cinema has become a curse even in India. An officer spends half of his salary on cinemas and runs into debts. All have developed a bad habit for some kind of sight-seeing. They cannot remain without it. The eyes want to see some kind of lights and sensational pictures. The Cinema is a very good paying business nowadays. Various sorts of half-nude pictures and obscene sights are shown on the screen. College boys and young girls are unduly thrown into a state of mental excitement. Various sorts of evils are propagated. The Cinema is an enemy of devotion. It is havocking the world. It does immense harm to the people. It is a great drain on the resources of man. It is a great temptation. All bad films should be thoroughly investigated and censored. Films should be passed by a religious body before they are brought on the screen. Only films which contain religious stories that are calculated to develop the moral and philosophical aspects of man may be allowed to come on the screen.

It is gratifying to note that highly educated men and women of India take part in the cinema. But college education will not do. If they want to impress the people and to do real spiritual good to the world, they should lead a life of Tapas, meditation and Brahmacharya.

Cinemas produce an evil habit in man. He cannot remain even for a day without attending a show. His eyes want to see some half-nude pictures and some kind of colours, his ears want a little music. Young girls and boys become passionate when they see the actors in the film kissing and embracing. Those who want to develop themselves in the spiritual line should entirely shun cinemas. Spiritual people only can bring out impressive stories with good morals that can elevate the minds of the spectators.

FORGETFULNESS

Forgetfulness is losing or putting away from the memory.

Forgetfulness is the quality of being apt to let anything slip from the mind.

Forgetfulness is loss of remembrance or recollection; oblivion.

We speak of sweet forgetfulness of human care.

Forgetfulness is careless omission; inattention is forgetfulness of duty.

There is a noble forgetfulness—that which does not remember injuries.

Learn the art of forgetting; you often remember what you would not and cannot forget what you would.

Forgetfulness is a blessing of God. If you remember constantly certain unhappy things, you will die quickly.

People who have bad memory are forgetful. They are inattentive. They neglect to do certain things. This must be got rid of by cultivating good retentive memory.

Forget not good deeds done by others and help given to you by others in times of your distress. Be grateful to them.

Forgetfulness is a personal quality, as in “He was noted for his forgetfulness.” Obliviousness, the stronger word, is a state into which a person or thing has fallen or passed completely, as "His obliviousness of his duties."

Prayer, practice of Pranayama, meditation, practice of exercises in memory as indicated in "Sure Ways for Success in Life and God-realisation," application of Brahmi-Amla oil, taking of Brahmi Ghee or Brahmi Powder with milk, will increase your memory power.

GLOOM AND DESPAIR

Just as clouds screen and obstruct the sun the cloud of gloom and despair will stand on your way of practice. Even then you must not leave the practice of Japa, concentration and meditation. These small clouds of gloom and despair will pass off soon. Give the suggestion to the mind: "EVEN THIS WILL PASS AWAY."

GAMBLING

DYUTA

Gambling is another dreadful curse. It is a great friend of Satan or anti-God. It is Maya's great weapon. It has broken the hearts of many. It tantalises, tempts and deludes. A little gain in the first betting itches the nerves of the gamblers and forces them to bet a large sum. Eventually they lose everything and return home with black or weeping faces. Man becomes a bankrupt by gambling. He weeps bitterly. Yet he will not leave it. Maya havocks through wrong habits, wrong thinking, wrong Samskaras and through bad company, gambling, cinema, drinking, smoking and meat-eating. Reason and discrimination fail. Intellect becomes perverted. Enormous money is wasted uselessly in gambling, drinking etc. No virtue will dwell in the heart of a man who gambles. Gambling is a net spread by Maya to entrap the bewildered souls. There is no evil greater than gambling. All vices cling to a gambler. No real gain will come to a gambler. He is always drowned in sorrow. He drags a cheerless life from day to day. Cards-play and horse-races are modifications of gambling only.

O Man! It is very difficult to get a human birth. Life is meant for God-realisation. Perennial joy, eternal bliss are in God. Do not waste this precious life in drinking, gambling, smoking and meat-eating. What will you say to the God of Death at the time of your death? No one will help you. You will carry your own thoughts and actions. Give up gambling, meat-eating, drinking, cinema, smoking from this very second. Give me a definite promise now. I am your friend and well-wisher. Wake up now. Open your eyes. Become a virtuous man. Do good actions. Sing Hari's Name. God's Name is a potent antidote for all evil habits. Study religious books. Seek the company of sages and devotees. All evil habits will be eradicated. Serve. Love. Give. Purify. Concentrate. Meditate. Realise this very second. Time is the most precious thing in the world. Ignorant people waste their whole time in playing cards and gambling. What a horrible state of affairs. Highly deplorable! How powerful is Avidya or Ignorance! People are lamentably sunk in the mire of darkness! Pitiable specimens of humanity! Slayers of Atman! May Lord Krishnaswami, Antaryami, the Indweller of your heart, give you strength to overcome all these evil habits! May His blessing be upon you all!

GREED

LOBHA

First comes Kama. Then comes anger. Then comes greed. Then comes Moha. Kama is very powerful. So prominence is given to it. There is intimate connection between Kama and Krodha. Similarly there is close relationship between greed and Moha. A greedy man has got great Moha for his money. His mind is always on the money-box and the bunch of keys he has tied to his waist-cord. Money is his very blood and life. He lives to collect money. He is a gate-keeper only for his money. The enjoyer is his prodigal son. He sucks the blood of poor people by taking enormous interest (25%, 50% and even 100% at times). Cruel-hearted people! They pretend to show that they are of charitable disposition by doing acts such as opening of Kshetras, buildings, etc.

Such acts cannot neutralise their abominable sins and merciless acts. Many poor families are ruined by these people. They do not think that the bungalows and palaces in which they live are built out of the blood of these people. Greed has destroyed their intellect and made them absolutely blind. They have eyes but they see not. Greed always makes the mind restless. A man of one lakh of rupees plans to get 10 lakhs. A millionaire schemes to become a multimillionaire. Greed is insatiable. There is no end for it. Greed assumes various subtle forms. A man thirsts for name and fame and applause. This is greed. A sub-judge thirsts for becoming a High Court judge; a third class magistrate thirsts for becoming a first class magistrate with full powers. This is also greed. This is another form of greed. A Sadhu thirsts for opening several Ashrams in different centres. This is also greed. A greedy man is absolutely unfit for spiritual path. Destroy greed of all sorts by Vichara, integrity, disinterestedness and enjoy peace.

HATRED

DVESHA

Hatred is another evil quality. This world is full of hatred. There is no real love. The son dislikes his father and tries to poison him to take possession of the legacy soon. The wife poisons the husband to marry another young man of wealth and position. Brothers fight in courts. Guru Nanak and Kabir have tried best to unite the two great communities in our land but failed very miserably in their attempts. Vedanta alone can unite them. How can a man who beholds the same Self in all, hate or dislike another man? The principles of Vedanta should be taught in all schools and colleges. This is an imperative necessity. The sooner this is done the better. From the very early boyhood healthy ideas should be sown in the minds of young boys. All boys should be trained in the service of humanity. The necessity of universal love should be very clearly emphasised. Then alone there can be a possibility of developing pure love and eradicating hatred. You all should try from now onwards to remove hatred sincerely and earnestly. Conquer hatred by love, jealousy by love and intolerance by love and you will succeed in life.

Hatred is the deadliest foe of an aspirant. It is an inveterate enemy. It is an old-standing associate of the Jiva. Ghrina, contempt, prejudice, sneering, taunting, teasing, ridiculing, mocking, frowning, showing wry faces are all forms of hatred. Hatred bubbles out again and again. It is insatiable like lust or greed. It may temporarily subside for sometime, and may again burst out with redoubled force. If the father dislikes a man his sons and daughters also begin to hate that man without any rhyme or reason whatsoever, although that man has not done them any wrong or injustice. Such is the force of hatred. If anyone even remembers the figure of a man who has done him some serious injury some forty years ago, at once hatred creeps into his mind immediately and his face shows clear signs of enmity and hatred.

Hatred develops by repetition of hatred-Vritti. Hatred ceases not by hatred but ceases by love only. Hatred needs prolonged and intense treatment as its branches ramify in various directions in the sub-conscious mind. It lurks in different corners. Constant selfless service combined with meditation for a period of twelve years is necessary. An Englishman hates an Irishman and an Irishman hates an Englishman. A Catholic hates a Protestant and a Protestant hates a Catholic. This is religious hatred. There is communal hatred. One man hates another man at first sight without any reason. This is Svabhavic. Pure love is unknown in this world amongst worldly people. Selfishness, jealousy, greed and lust are retinues of hatred. In Kali-Yuga the force of hatred is augmented.

A son hates his father and sues him in the court. The wife divorces her husband. This has come to stay even in India. In course of time divorce courts also will be established in India. Where is the Pativrata Dharma of Hindu ladies? Has it disappeared from the soil of India? In India marriage is a sacrament. It is a sacred act. It is not a mere contract as in the West. The husband holds the hands of his wife, both look at Arundhati star and take a pledge before the holy fire. The husband says, "I shall be as chaste as Rama and promise to live with you peacefully, procreating healthy, intelligent offspring. I shall love you till I die. I will never look at the face of another lady. I will be true to you. I shall never separate myself from you." The wife in return says, "I shall be unto you like Radha unto Krishna, like Sita unto Rama. I shall serve thee till the end of my life in sincerity. Thou art my very life—Thou art my Prana Vallabha—I shall realise God by serving thee as God." Look at the horrible state of present day affairs! Absolute freedom should not be given to Hindu ladies. Manu says: "Hindu ladies should always be kept under control." This deplorable state of affairs is due to so-called modern civilisation and modern education. Pativrata Dharma has gone. Ladies have become independent. They forsake their husbands and do whatever they like. Culture does not consist in husband and wife walking on Mount Road and Marina Beach holding their hands or placing their hands on the shoulders. This is not real freedom. This is vile imitation. This is unfit for Hindu ladies and destroys the feminine grace and modesty which are their characteristics and which adorn them.

Pure unselfish love should be cultivated. One should have fear in God. Solomon says: "Fear of the Lord is the beginning of wisdom." Service with Atma Bhava can remove hatred completely and bring in Advaitic realisation of oneness of life. Ghrina, prejudice, contempt etc., will completely vanish by selfless service. Vedanta in daily life when put into actual practice can eradicate all sorts of hatred. There is one Self hidden in all beings. Then why do you hate others? Why do you frown at others? Why do you treat others with contempt? Why do you divide and separate? Realise the unity of life and consciousness. Feel Atman everywhere. Rejoice and radiate love and peace everywhere.

HOW TO ERADICATE HATRED?

Adveshta Sarvabhutanam Maitrah Karuna Evacha
Nirmamo Nirahamkarah, Samaduhkha Sukhah Kshami.

Gita, Chap. XII. 13.

A Bhagavata or devotee who has attained God-realisation has no hatred to any being. He is friendly and compassionate. He is without attachment and egoism. He is balanced in pleasure and pain and is forgiving.

Hatred can be removed by the cultivation of virtues such as friendliness, compassion, forgiveness and eradication of egoism and mine-ness. Positive overcomes negative.

An egoistic man is easily upset by trifling things. As his heart is filled by vanity and pride, a little disrespect or harsh word or mild rebuke or censure throws him out of his balance. He hates others out of his wounded vanity. Hence removal of pride and egoism will pave a long way towards eradication of hatred.

Hatred is born of egoism. Eradication of egoism by the root will itself lead to the annihilation of hatred.

If you are attached to a thing you will hate that man who tries to take away from you the thing to which you are attached. If you are endowed with the quality of forgiveness you will excuse that man who tries to harm you or who has done you any harm, and you will entertain no hatred for anybody.

Cultivation of divine virtues like compassion, love, forgiveness, etc., will thin out or attenuate hatred. Vision of God or God-realisation or the knowledge of the Supreme Being can completely eradicate or burn hatred.

May you all be free from hatred and become Bhagavatas with God-vision and Daivi Sampat!

RELIGIOUS HYPOCRISY

DHARMIKA-CHALA

There are as many fashions in Sadhus as there are in worldly persons.

Just as hypocrisy prevails in the worldly persons, so also hypocrisy manifests in aspirants, Sadhus and Sannyasins who have not completely purified the lower nature. They pretend to be what they are not in reality. They pose for big Mahatmas and Siddha-purushas when they do not know even the alpha-beta of Yoga or spirituality. They put on serious Sunday faces. This is a dangerous Vritti. They cheat others. They boast too much of themselves. They do mischief wherever they go. They practise hypocrisy to get respect, honour, good food and clothing and to cheat credulous simpletons. There is no greater crime than trading in religion. This is a capital sin. Householders can be excused. There cannot be any excuse for aspirants and Sadhus who are treading the path of spirituality and who have renounced everything for God-realisation. Religious hypocrisy is more dangerous than the hypocrisy of worldly persons. A long drastic course of treatment is needed for its eradication. A religious hypocrite is very far from God. He cannot dream of God-realisation. Thick Tilaks, elaborate painting of the fore-head, wearing of too many Tulasi and Rudraksha Malas on neck, arms, forearms, ears are some of the external signs of religious hypocrisy.

IDLENESS

ALASYA

An idle man is a burden to himself. He wastes his life.

He is sickly, anaemic. He has no application. He has no resolution. He has no purpose in life. He has no determination.

His mind is clouded. His thoughts are confused. He drags a dreary, cheerless existence.

He has ruined his life. He puts his head down in shame and repentance.

IMPURE AND IMMODERATE FOOD

ASUDDHA-AHARA

Mind is formed out of the subtlest portion of food. If the food is impure, the mind also becomes impure. This is the dictum of sages and psychologists. Food plays an important part in the evolution of mind. Meat, fish, eggs, stale, unwholesome food, onions, garlic, etc., should be avoided by spiritual practitioners as they excite passions and anger. The food should be simple, bland, light, wholesome and nutritious. Liquors and narcotics should be strictly abandoned. Chillies, condiments, spiced dishes, pungent articles, hot things that are sour, sweetmeats etc. must be rejected.

In the Gita you will find: “The foods that augment vitality, energy, vigour, health, joy and cheerfulness, delicious, bland, substantial and agreeable, are dear to the pure. The passionate desire foods that are burning, and which produce pain, grief and sickness. That which is stale and flat, putrid and corrupt, leavings also and unclean, is the food dear to the dark”—Ch. XVIII 8, 9, 10. Aspirants should not overload the stomach. Ninety percent of diseases take their origin in immoderations in diet. People have developed a strong habit of eating more food than what is actually necessary from their very boyhood. Hindu mothers stuff the stomachs of their children with too much food. This is not the way of caressing and loving children. Overloading produces drowsiness and sleep immediately. If there is no hunger, you must not take any food. The night meals should be very light for Sadhakas. Half a seer of milk, with one or two plantains is quite sufficient. Overloading is the chief factor in bringing night-pollution. Sannyasins and aspirants should take their Bhiksha from the hands of those householders who earn their livelihood by honest means.

INCONSTANCY

ASTHIRATA

Inconstancy is fickle-mindedness. The mind is subject to frequent change.

Inconstancy is instability of affection or temper. It is the quality or state of not being uniform. A man of inconstancy is unstable. He is vacillating. He has a character or constitution which renders change natural or preferable. He is inconstant in friendship or love like an inconstant flame. He changes his views and opinions. He is not firm in resolution. He is unsettled in his thoughts, speech and action.

Clocks will go as they are set, but man, irregular man, is never constant, never certain. His mind ever vacillates, oscillates, and fluctuates, on account of Rajas or passion.

Inconstancy makes you imperfect, fills you with faults and makes you run through sins.

The man of inconstancy has no peace of mind. He is never at ease. His life is unequal. Today he loves you, tomorrow he detests you. This morning he is joyful and laughs; this evening he weeps and is sorrowful.

Cultivate resolution, firmness and steadiness and conquer inconstancy, the cause for unhappiness and misfortune.

Be firm, be steady, be resolute, you will attain success in all your undertakings. You will have neither anxiety nor disappointment.

INDOLENCE

AALASYA

Indolence is the sleep or inertia of the mind.

Indolence is indisposition to exertion, arising from a love of ease or aversion to work, or the resultant inaction. It is habitual idleness.

An indolent man is indisposed to activity. He is dull and lethargic and lazy and slothful.

Indolence is the waste of what might be a happy and useful life.

Core Movements of Part I

Grasping the Moon

Connecting the Heaven and Earth Forces - Right Side over Left

Open Position: Heaven Force - Slightly raise the index fingers to open the palms. Bring the arms up , bending the elbows so that the left hand is under the right elbow with the left index finger pointing up to Heart 3.



Fig. 8.15 *Complete the Heavenly Circuit.*

The right index finger is pointing up toward heaven and connecting to the galaxy. The right forearm is over the left forearm, with the tip of the right index finger held above the Large Intestine 11 point of the left arm.

The **right index finger draws in the heavenly force** like antennae. The force flows up the bones of the right arm, across the shoulders to the left arm and through the bones of the left arm to the left index fingertip. It **then flows through the index finger of the left hand** into the Heart 3 point of the right arm, **completing the heavenly circuit**. Continue cycling in this way. Hold the position and count to five.

The practice uses the 'Empty Force'; this means that there is no contact. The fingers must be 'tense without tensing'. When you tense and raise the index finger, you will feel the Laogong point opening.

Indolence is born of Tamas or darkness or inertia. It is an enemy of evolution, progress, success, peace, devotion and wisdom.

Indolence and stupidity are first cousins.

Indolence is a sort of suicide.

A man of indolence can be compared to a buffalo. He is a burden on this earth.

Indolence is the dry rot of even a good mind and good character.

Dullness, torpor, inactivity, sluggishness are synonymous with indolence.

INDECISION

ANISCHAYA

Indecision is want of decision or resolution.

Indecision is want of settled purpose or resolution. It is failure or inability to form a judgement or decide on a course of action. It is indetermination or irresolution.

A man of indecision is not able to decide or come to a final definite conclusion. He has a wavering mind.

Indecision is want of decision, want of settled purpose or of firmness in the determination of the will as an indecisive state of mind.

A man of indecision is unsettled. There is always hesitation for him.

Half the worries of the day spring from indecision. Determine on a plan, work on a policy. March forward.

The lot of man of indecision is indeed pitiable. He is ever unhappy. He always fails in all his undertakings. He is like a feather or cottonwool in the air which is blown about hither and thither by every breeze.

Some people are not able to decide anything definitely in certain important matters. They have not got an independent power of judgement. They will simply prolong the matter. They will not come to a definite positive decision. The opportunity will slip away. It will be too late to gather honey in winter. You must think deeply over a matter for some time and should be able to come to a definite decision. At once you must apply your will. You must immediately try to put the matter into execution. Then only you will succeed. Too much thinking will upset the matter. In important matters you can consult some of your elders who have got plenty of experience in the line and who are your real well-wishers. Remember the wise saying: "Cut the Gordian knot."

INERTIA

TAMAS

A microscopic minority only are fit for wholetime meditation. People like Sadasiva Brahman and Sri Sankara only can spend whole time in meditation. Many Sadhus who take to Nivritti Marga have become completely Tamasic. Tamas is mistaken for Sattva. This is a great blunder. One can evolve beautifully by doing Karma Yoga in the world if he knows how to spend his time profitably. A householder should seek the advice of Sannyasins and Mahatmas from time to time, draw a daily routine and adhere to it strictly amidst worldly activities. Rajas can be converted into Sattva. Intense Rajas takes a Sattvic turn. It is impossible to convert Tamas all on a sudden into Sattva. Tamas should be first turned into Rajas. Young Sadhus who take to Nivritti Marga do not stick to routine. They do not hear the words of elders. They do not obey the orders of the Guru. They want absolute independence from the very beginning. They lead a happy-go-lucky life. There is no one to check. They have their own ways. They do not know how to regulate the energy and how to chalk out a daily programme.

They aimlessly wander about from place to place. They become Tamasic within six months. They sit for half an hour in some Asana and imagine that they are having Samadhi. They think they are realised souls. If an aspirant who has taken Nivritti Marga finds that he is not evolving, he is not improving in meditation, he is going into Tamasic state, he should at once take up some kind of service for some years and work vigorously. He should combine work along with meditation. This is wisdom. This is prudence. This is sagacity. Then he should go in for seclusion. One should use his commonsense all throughout his Sadhana. It is very difficult to go out of Tamasic state. A Sadhaka should be very cautious. When Tamas tries to overtake him, he should immediately do some brisk work. He can run in the open air, draw water from wells etc. He should drive it off by some intelligent means or other.

SENSE OF INFERIORITY

HEENA BHAVA

Many a man worries himself too much that he is inferior to others. The idea of superiority and inferiority is purely mental creation. The inferior man can become a superior man if he exerts, struggles and develops virtues. The superior man may become inferior if he loses his property and falls into evil ways. Never think that you are inferior or superior to anybody. If you think that you are superior to others, you will begin to treat them with down-right contempt. The idea of superiority and inferiority is the product of ignorance. Develop equal vision. Live in the true spirit of the Gita. Hear what the Gita says: "Sages look equally on a Brahmin adorned with learning and humility, a cow, an elephant, and even a dog, and an outcaste." Namdev ran after a dog with a cup of ghee to soften and moisten the bread. He said: "O dog, you are a form of Vittala. This dry bread will hurt your throat. Pray, allow me to apply this ghee to this bread." Ekanath gave the Ganga water (which he carried from Gangotri on his shoulder for Abhisheka at Rameswaram) to an ass which was very thirsty and lying on the roadside. Where is superiority or inferiority when you behold the one Self in all and everywhere? Says William Hazlitt, the reputed essayist: "The sense of inferiority in others without an indirect appeal to self-love is a painful feeling and not an exalting one." Change your angle of vision or mental attitude and rest in peace.

INTOLERANCE

ASAHANAM

Then comes another undesirable negative quality, intolerance. There is religious intolerance. There is intolerance of all sorts. Intolerance is nothing short of petty-mindedness. It is unreasonable dislike for little things. The Sikh can drink alcohol. There is no harm in this. But he becomes intolerant when he sees anybody smoking. A Deccani Brahmin can do anything which is an infringement of the moral code but he becomes intolerant when he sees a Kashmiri Pandit taking meat. A South Indian Brahmin can take anything in a restaurant but he is intolerant when he sees a Bengali taking fish. All restlessness and fighting in this world of man takes its origin in intolerance. An Englishman is intolerant towards an Irishman or a German. A Hindu is intolerant towards a Muslim and vice versa. An Arya Samajist is intolerant towards Sanatanist and vice versa. This is due to perfect ignorance. How can a sage who sees the one Atman in all beings be intolerant? All these small petty differences are pure mental creations. Expand! Expand!! Expand!!! Embrace all. Include all. Love all. Serve all. Behold the Lord in all. See God in everything. See the Lord in every face. Feel the Indwelling Presence everywhere. Change the angle of vision. Be liberal and catholic in your views. Destroy all barriers that separate man from man. Drink the eternal Atmic Bliss. Become perfectly tolerant. Excuse the baby souls who are struggling in the path of life's journey and who are committing mistakes. Forget and forgive their mistakes. You will succeed in life. You will realise God quickly. There is no other way.

IRRESOLUTION

ANIRDHARA

Irresolution is lack of firmness in purpose, or want of resolution or decision.

Irresolution is the cause of failures and unhappiness. It is a great vice.

A man of irresolution lacks determination of character. He is ever vacillating, wavering and hesitating. He is given to doubt. He is without firmness of mind. He is without decision. He has a fluctuation of mind as in doubt or between hope and fear.

Indecision denotes lack of intellectual conviction. Irresolution denotes defect of volition, weakness of will.

A thoughtful man may be undecided as to the course to take in perplexing circumstances, but when decided, he may act with promptness. An irresolute man lacks the nerve to act. Indecision commonly denotes a temporary state or condition, irresoluteness a trait of character.

JEALOUSY

Jealousy is another canker that consumes man. It is nothing but petty-mindedness. Even educated people and Sannyasins are not free from this terrible scourge. All restlessness and fighting between one community and another, one man and another, one nation and another, are due to this evil quality. The heart of a jealous man burns actually when he sees his neighbour in more prosperous condition. The same is the case with nations and communities. Jealousy can be eradicated by developing the opposite quality, viz., nobility or magnanimity; just as pride is removed by developing frankness and simplicity; and anger is overcome by developing Kshama and a spirit of service.

Jealousy is also a great obstacle. Even Sadhus who have renounced everything, who live with one Kaupeen only in the caves of Gangotri and Uttarkashi in the Himalayas are not free from this evil Vritti. Sadhus' hearts burn when they see some other Sadhu in a flourishing condition, when they notice that the neighbouring Sadhu is respected and honoured by the public. They try to vilify this neighbour and adopt methods for his destruction or elimination. What a sad sight! What a deplorable spectacle! Horrible to think! Dreadful to imagine! When the heart burns, how can you expect peace of mind? Even highly educated people are very mean and petty-minded. Jealousy is a worst enemy of peace and Jnana. It is the strongest weapon of Maya. Aspirants should be always on the alert. They should not become slaves of name and fame and jealousy. If there is jealousy he is a small, little being only. He is far from God. One should rejoice at the welfare of others. One should develop Mudita (complacency) when he sees others in prosperous conditions. He should feel Atma-Bhava in all beings. Jealousy assumes various forms such as Irshya, Asuya, Matsarya etc. All forms of jealousy must be totally eradicated. Just as milk again and again bubbles out during the process of ebullition, so also jealousy bursts out again and again. It must be entirely rooted out.

The Sanskrit term for jealousy is Irshya. Irshya, Matsarya, Asuya are all synonymous terms. But there is a subtle difference. Jealousy is a particular kind of emotion or Vritti that arises in a Rajasic mind wherein the victim looks upon with a grudging eye on the prosperity or success or higher virtuous qualities of his neighbour or any other person. His heart burns when another man is more prosperous than himself. Hatred and anger are hidden in jealousy. Ill-will is the modification of jealousy. A man filled with jealousy hates another man if he is in a better position than himself. He gets grief at the sight of another's success. He tries his level best to pull down the prosperous man, to undermine him by various foul means, by backbiting, tale-bearing or vilification. He tries to injure the man also. He attempts to annihilate him. He creates dissensions and party-spirit amongst his friends. These are the external, physical manifestations of a man of jealousy.

A man of Irshya thinks that he should not get any kind of sorrow and that all others should be afflicted with grief. A man of Asuya gets agitated when another man enjoys like himself. A man of Matsarya cannot bear the sight of a man more prosperous and wealthy than himself. This is the subtle difference between Irshya, Asuya and Matsarya.

Jealousy is the root of all evils. It is very deeply rooted. Maya havocks through this particular Vritti. The restlessness of the world, Asanti, is due to jealousy. The whole play or Lila of Maya is kept up by this one emotion. Anger, hatred, malice exist side by side with jealousy. They are the old-standing associates or comrades of jealousy. If jealousy dies, hatred and anger die by themselves without any further treatment. Many murders are committed on account of sex-jealousy, money-jealousy.

No one can enjoy an iota of real happiness if his mind is filled with jealousy. Kings, Barons, Lords and Earls cannot have any happiness so long as they are slaves of this emotion. What can money do? It can only augment the uneasiness of the mind. "Uneasy lies the head that wears the crown."

There are six ways of eradicating this emotion:

1. Rajayogic method.
2. Vedantic method.
3. Bhakta's method.
4. Karma Yogin's method.
5. Method of Vichara of Vivekins.
6. Theosophist's method.

A Raja Yogi destroys the Vritti by "*Yogah Chitta Vritti Nirodhah*." He destroys all Sankalpas of jealousy by introspection, careful watch and meditation. He adopts another method of "Pratipaksha Bhavana" by cultivating the opposite virtues of jealousy, viz., nobility or magnanimity, "Udarata." Jealousy is the result of petty-mindedness. If nobility is supplanted, jealousy will die of itself.

JILLY-JALLYING

ATIBHASHANAM

Too much talking is jilly-jallying. If a man talks too much he suffers from diarrhoea of the tongue. Quiet people cannot sit even for a second in the company of these loquacious or garrulous people. They will talk five hundred words per second. There is an electric talking-dynamo in their tongues. They are restless people. If you lock these people for a day in a solitary room, they will die. Much energy is wasted by too much talking. The energy spent in talking must be conserved for divine contemplation. The Vak-indriya distracts the mind considerably. A talkative man cannot dream of having peace even for a short time. An aspirant should talk only a few words when necessary and that too on spiritual matters only. A talkative man is unfit for the spiritual path. Practise Mouna daily for two hours and especially during meals. On Sundays observe full Mouna for 24 hours. Do lot of Japa and meditation during Mouna. The Mouna that is observed during meditation cannot be taken as vow of silence. Then sleep also should be taken as Mouna. Mouna should be observed by house-holders at such a time when there are opportunities for talking and when visitors come to meet. Now only the impulse of speech can be checked. Ladies are very talkative. They create troubles in the house by idle-talks and gossiping. You should speak measured words only. Too much talking is Rajasic nature. Great peace comes by observance of Mouna. By gradual practice, prolong the period of Mouna to six months and then to two years

MANORAJYA

Manorajya is building castles in the air. This is a trick of the mind. Look at this wonder! The aspirant is meditating in an isolated cave in the Himalayas. He plans in the cave: “After finishing my meditation, I must move about in San Francisco and New York and deliver lectures there. I must start a centre of spiritual activity in Columbia. I must do something new in the world. I must do something which no one has done upto this time.” This is ambition. This is egoistic imagination. This is a great obstacle. This is a powerful Vighna. This will not allow the mind to rest even for a second. Again and again there will be resurrection of some scheme, speculation, plan or the other.

The aspirant will be thinking that he is having deep meditation, but if he closely watches his mind through introspection and self-analysis, it will be a pure case of building castles in the air. One Manorajya will subside and another will crop up in the twinkling of an eye. It will be a small Sankalpa or ripple in the mind-lake. But it will gain tremendous force within a few minutes by repeated thinking. The power of imagination is tremendous. Maya havocks through the power of imagination. Imagination fattens the mind. Imagination is like musk or Siddha-Makaradhvaja. It renovates and vivifies a dying mind. The power of imagination will not allow the mind to keep quiet even for a second. Just as swarms of locusts or flies come forth in a continuous stream, so also currents of Manorajya will stream forth incessantly. Vichara, discrimination, prayer, Japa, meditation, Satsanga, fasting, Pranayama, practice of thoughtlessness will obviate this obstacle. Pranayama checks the velocity of the mind and calms the bubbling mind. A young ambitious man is unfit to remain in a solitary cave. He who has done selfless service in the world for some years and who has practised meditation for several years in the plains in solitary rooms can live in a cave. Such a man only can really enjoy the solitude of the Himalayan retreats.

MEAN-MINDEDNESS

KSHOUDRAM

This world abounds in mean-minded people of every sort. Ninety nine per cent of people are mean-minded in some way or other. This is due to Tamo-Guna. The heart of a mean-minded man burns when he sees others in prosperous condition. It burns when he hears of the success and attainments or virtuous qualities of others. He vilifies them and aims at their downfall. He does scandal-mongering and backbiting. He is extremely jealous and envious. Mean-mindedness is a form of jealousy. One may be an intellectual giant. He may be a very great poet. His books might have been prescribed as texts for the students of M.A. in the University. But he may be a very mean-minded man without any scruples or principles. The whole society may admire his talents as a poet or as a scholar and at the same time may hate him as he is very mean. As a real man he is nothing.

A mean-minded man will not hesitate to poison his brother to usurp his property. He will not hesitate to put false signature, utter deliberate lies, defraud a man, commit adultery and rob a man of his wealth. He is ready to do any kind of mean act to amass wealth. He has not got a clean conscience. He is very calculative. Miserliness goes hand in hand with mean-mindedness. He will be pained to part even with a paisa. Charity is unknown to him. He may be a great man in society but he will be fighting on the railway platform shamelessly with a porter for two paise. He may spend kerosene-oil worth about two annas to find out a missing paisa in his daily account. He will eat sweetmeats, fruits, etc., but his heart will burn if his servant also eats the same articles. He will ask his servant to eat gram and black sugar. He will make great differences in serving tea or anything to others. He will keep the best things for himself and distribute the rotten stuff to others. He will not give even a single morsel of food to save a dying man. He has a heart as hard as flint.

Rich people are meaner than poor people. A mean-minded man fights with others for trifling things. He is of a quarrelsome nature. He is proud, egoistic and irritable. He is of highly suspicious nature. He is ever gloomy and depressed. The accumulated money of mean-minded people is generally squandered away by their profligate sons. A large portion of such money goes to pay the doctor's bills and lawyer's fees. They do not enjoy life. They are simply care-takers of their money.

The remedy for this dire disease is the cultivation of the opposite virtue which is nobility or magnanimity. Charitable nature, cosmic love and the spirit of service should be developed. Satsanga is highly beneficial. Regular meditation on the virtue of nobility is necessary. Sit very quietly in a solitary room at night and close your eyes. Introspect and find out what sort of mean actions you did during the course of the day. Record these in your daily spiritual diary. Watch also the mean Vrittis that arise from the mind-lake and nip them in their very bud.

MEAT-EATING

MAMSA-BHAKSHANAM

Meat is not at all necessary for the keeping up of health. Meat-eating is highly deleterious to health. It brings a host of ailments such as tapeworm, albuminuria and other diseases of the kidneys. After all man wants very little on this earth. A few breads, a little dal will quite suffice to keep up his health, vigour and vitality. Killing of animals for food is a great sin. Instead of killing the egoism and the idea of "Mine-ness," ignorant people kill innocent animals under the pretext of sacrifice to Goddess but it is really to satisfy their tongues and palates. Horrible! Most inhuman! Ahimsa is the greatest of all virtues. "*Ahimsa Paramo Dharmah*." Ahimsa is the first virtue that a spiritual aspirant should possess. We should have reverence for life. Lord Jesus says: "Blessed are the merciful, for they shall obtain mercy." Lord Jesus and Mahavir shouted at the top of their voice: "Regard every living being as thyself, harm no one." The law of Karma is inexorable, unrelenting and immutable. The pain you inflict upon another will rebound upon you and the happiness you radiate to another will come back to you, adding to your happiness.

Dr. J. Oldfield, senior physician, Lady Margaret Hospital, writes: "Today, there is the chemical fact in the hand of all, which none can gainsay that the products of the vegetable kingdom contain all that is necessary for the fullest sustenance of human life." Flesh is unnatural food, and therefore tends to create functional disturbances. As it is taken in modern civilisation, it is infected with such terrible diseases (readily communicable to man) as cancer, consumption, fever, intestinal worms, etc., to an enormous extent. There is little need for wonder that flesh-eating is one of the most serious causes of the diseases that carry off ninety-nine out of every hundred people that are born.

Meat-eating and alcoholism are closely allied. The craving for liquor dies a natural death when the meat diet is withdrawn. The question of birth-control becomes very difficult in the case of those who take meat diet. To them mind control is absolutely impossible. Mark how the meat-eating tiger is ferocious, and the cow and the elephant, which live on grass are mild and peaceful! Meat has a direct evil influence on the compartments of the brain. The first step in the spiritual advancement is the giving up of meat diet. The divine light will not descend if the stomach is loaded with meat diet. In large meat-eating countries cancer mortality is very high. Vegetarians keep up sound health till old age. Even in the West in the hospitals, doctors are

Close Position: Tan Tien, earth and the universal force - keeping the arms in the same position, move both index fingers to point down. The **right index finger will now point toward the Large Intestine 11 point of the left arm and the left index finger will point downward toward the earth** and continue down to connect to the universe. Draw in the earth force through the left index finger, bringing it through the bones of the left arm, across the shoulders through the right arm to the right index finger and out into the Large Intestine 11 point of the left arm. Continue cycling in this way, **completing the earth circuit**.

Open and close three times altogether ending in the open position. Hold each count for five seconds.

Holding and Activating the Chi Ball
Tan Tien and the Original Force - Right Side over Left

Turn the **left palm upward** and lower it to the Tan Tien with the pinky pointing inwards.

Lower the right palm to the navel, palm down, as though you were holding a small Chi ball. Lower the right thumb to point toward the left Laogong point. This opens the eye of the right hand (LI-4), then point it toward the navel. Be aware of Tan Tien and universe.



***Fig. 8.16** Right Side over Left - 'Holding the Ball'.*

Yin/Yang Palms

Separate the hands and extend them out in front of the body at navel level. The **left palm** is still pointing up, and is **Yang** drawing in the heavenly force through Laogong. The **right palm** is still facing down, and is **Yin** drawing in the earth and the galactic force from below.

Conclude by turning the left palm over to face downward. **Draw in the earth force through both palms.**



***Fig. 8.17** 'Yin and Yang Palms' - Right Hand connecting to Earth and Left to Heaven.*

now putting patients on a vegetable diet. They convalesce very quickly.

Pythagoras, the Grecian sage, preached: "Not to kill nor injure any creature." He condemned meat diet as sinful food. Just hear what he says: "Beware, O mortals, of defiling your bodies with sinful food! There are cereals, there are fruits, bending their branches down by their weight, and luxurious grapes on the vines. There are sweet vegetables and herbs which the flame can render palatable and mellow. Nor are you denied milk, nor honey, fragrant of the aroma of the thyme flower. The bountiful earth offers you an abundance of pure food and provides for meals obtainable without slaughter and bloodshed."

If you want to stop taking mutton, fish, etc., just see with your own eyes the pitiable, struggling condition at the time of killing the sheep. Now mercy and sympathy will arise in your heart. Then you will determine to give up flesh-eating. If you will fail in this attempt just change your environments and live in a vegetarian hotel where you cannot get mutton and fish and move in that society where there is only vegetable diet. Always think of the evils of flesh-eating and the benefits of a vegetable diet. If this also cannot give you sufficient strength to stop this habit, go to slaughter-house and butcher's shop and personally see the disgusting rotten muscles, intestines, kidneys and other nasty parts of the animal which emit bad smell. This will surely induce Vairagya in you and a strong disgust and hatred for meat-eating.

MISERLINESS

KRIPANATA

My experience after close study is that miserliness is ingrained in many persons. That is why they do not make any progress in the spiritual line despite their earnestness, sincerity and other qualifications and continued practice of Yoga. A miser is very far from God. He who expects Samadhi and Darshan of God by practising Asanas and Kumbhaka, and little Japa keeping up extreme miserliness and unsympathetic hard heart, cheats himself. He is a downright hypocrite indeed.

Miserliness is a great curse. It is an enemy of peace and a friend of selfishness. Miserly persons are quite unfit for the spiritual path. Generous-hearted persons are very rare. Many have achieved power, popularity, peace and happiness only through a generous heart. Miserly persons can never dream to have these and get success in life. Their very company is very dangerous for spiritually-minded persons. They poison the whole atmosphere on account of their corrupted, contracted hearts.

You should have a very large heart. You should throw money like stones to poor people. Then only you can develop Advaitic feeling, Samadhi and Cosmic love. The majority of householders are absolutely selfish in these days. Money is their blood. You will find cheerlessness and ugliness in their faces. Worry, greed, passion, jealousy, hatred, depression and all other evil qualities stick to the man who has the miserly nature in him and they consume the very core of his heart. It is a pity even judges and zamindars fight with porters on the railway platforms for the sake of an anna.

One may be able to stand on his head for three hours. One may be able to stop the breath for ten minutes. But this is nothing if he has no generous heart. See the fun here: Madrasis take their food on plantain leaves. Some of the ladies are very miserly. They will open the bundle of leaves and take out the decaying ones for the day's use and keep the good ones for the next day. By the time they open the bundle the following day, these good ones also will be rotting. In this manner, they will be using daily rotten leaves only. They cannot enjoy fresh leaves on any day. Such is their niggardliness. A fruit-seller also will be daily eating the rotten fruits only. He will never eat good ones. He preserves the good ones to get money from the people. If they are sold, then he will eat the rotten ones. Same is the case with the Panshopwalas. Misers have no happiness here and hereafter. They are watchmen only for their money. Many misers will not use new clothes. They will be wearing torn clothes. By the time they open the trunk, all new clothes will be eaten away by moths. Such miserly people will not part with anything of their own and in the name of generosity, they will give away in charity the property of others.

If a miserly man keeps Rs. 50,000 he will not enjoy the money but crave for a lakh more. A millionaire will be craving to become a multi-millionaire. It is horrible to find that rich persons are so miserly and hard-hearted that they do not live to share with their friends some of the rich delicacies. They will keep nice cakes in the almirah under lock and key and eat them in the night when others have gone to bed. Such persons will not give even a pie in charity. They will be eating nice food, but they will never have a heart to give a small portion even to a poor man who has been starving since three days. Such is the nature of their heart. They will take nice fresh cow's milk and offer only diluted milk to their guests. They will take fresh rich articles of food and offer the useless preparations to their servants, after keeping them for three days. They will wait for three days for getting good opportunity to use the old preparations of food and then throw them to their servants with a painful heart. They do not like to part with these decaying things also. You will find such heart-rending instances in almost all the houses of rich persons. To hide their inborn miserly nature, they will talk high philosophy on economy. They will never admit their actions are due to miserly nature, but will try to prove that it is economical.

Some officers retire from service and live on the banks of the Ganga, Narmada and Yamuna. They do a little Japa and meditation and study the Yoga Vasishtha and the Upanishads, and imagine they are Jivanmuktas. They entertain still intense Moha for their children. They remit their pension money to their sons and grandchildren. They are the embodiments of miserliness. They are hopeless, self-deluded souls! A miser cannot dream of Self-realisation even in thousand births. Lord Jesus says: "It is easier for a camel to go through the eye of a needle than for a rich man to enter the kingdom of God."

If one can destroy this miserly nature a greater portion of Sadhana is over. He has achieved something substantial. Sins can be destroyed by charity. Lord Jesus says: "Charity covereth multitude of sins." In the Gita you will find: "*Yajno danam tapaschaiva pavanani manishinam*—Yajna, charity and austerity are purifying to the wise."

Doing abundant, spontaneous and unrestrained charity to relieve the pains of the suffering humanity is an effective means to destroy this evil nature. Develop therefore this Udaravritti. Then only you can become a King of kings. Never think of your wife, children and dependents only. Whenever you come across poor people, wherever there is suffering, give money like water. If you give, the whole wealth of the world is yours. Money will come to you. This is the immutable, inexorable, unrelenting law of nature. Therefore give, give. See God everywhere. Share with all. The best portion must be given to others. Destroy the ingrained miserliness. Your heart will expand. You will have broad outlook on life. You will have a new wide vision. You can feel the help from the Indweller of your heart. You can experience an indescribable thrill of Divine ecstasy and Spiritual Bliss. This will give tremendous inner strength. Your rooting in the spiritual path will be firm. You will become a modern Buddha!

NAME AND FAME

One can renounce even wife, son, property, but it is difficult to renounce name and fame. Pratishtha is established name and fame. This is a great obstacle in the path of God-realisation. This brings downfall in the end. This does not allow the aspirant to march forward in the spiritual path. He becomes a slave of respect and honour. As soon as the aspirant gets some purity and ethical progress, ignorant people flock to him and pay homage and salutations. The aspirant gets puffed up with pride. He thinks he is a great Mahatma now. He becomes eventually a slave of his admirers. He cannot notice his slow downfall. The moment he mixes up freely with householders, he loses what little he had gained during eight or ten years. He cannot influence the public now. The admirers also leave him because they do not find any solace or influence in his company.

The people imagine that the Mahatma has got Siddhis and they can get children through his grace, wealth and roots for removal of diseases. They always approach a Sadhu with various motives. The aspirant through bad association loses his Vairagya and Viveka. Attachment and desires crop up now in his mind. Therefore an aspirant should hide himself always. Nobody should know what sort of Sadhana he is doing. He should never attempt to exhibit any Siddhi. He should be very humble. He should pass for quite an ordinary man. He should not accept any rich present from householders. He will be affected by the bad thoughts of those who offer presents. He should never think that he is superior to anybody. He should not treat others with contempt. He should always treat others with respect. Then only respect will come by itself! He should treat respect, honour, name and fame as dung or poison. He should wear disrespect and dishonour as a golden-necklace. Then only he will reach the goal safely.

NOVEL-READING

Novel-reading is another evil habit. Those who are in the habit of reading novels that deal with passion and love cannot remain even for a single second without novel reading. They always want their nerves to be tickled with sensational feelings. Novel reading fills the mind with base, lustful thoughts and excites passion. It is a great enemy of peace. Many people have started libraries for distribution of novels on a small subscription of four annas per mensum. They have not at all realised how much harm they are doing to the country. It is better they chalk out another avocation to eke their livelihood. They spoil the minds of young men by the distribution of these worthless novels which excite their passion. The whole atmosphere is polluted. Severe punishment is awaiting them in the Yama Loka. Newspaper reading is also an evil habit. People cannot leave their papers while they are taking their food also. They always like to hear some sensational news. They feel quite dull when they do not read the papers. They are quite unfit for a life of meditation and seclusion. Place them in solitude for three days. They will feel like fish out of water. The reading of newspapers makes the mind always outgoing, brings in revival of worldly Samskaras and makes a man forget God.

OBSTINACY

HATHA

Obstinacy is foolish stubbornness, born of Tamas or darkness. It is pig-headedness.

Obstinacy is stubborn adherence to purpose, opinion or course of action, arising from conceit or the desire to have one's own way and generally unreasonable.

It is the quality of being unyielding or difficult to control or subdue.

A man of stubbornness is unyielding to argument or entreaty. He has no regard for the wishes and views of others.

The man of obstinacy is bluntly and unyielding.

Obstinacy is the vice of the ignorant who vainly persevere in their own understanding.

Obstinacy is the strength of the foolish, weak and the stupid.

Firmness founded upon principle, upon duty, truth, right, order and law is the obstinacy of the Yogi and the sage.

Obstinacy is certainly a great vice. It is the cause of great mischief.

Firmness or adherence to truth and duty is sometimes mistaken for obstinacy by those who have no knowledge of its nature.

A child (Bala-Hatha), a Yogi (Yogi-Hatha), a woman (Sthree-Hatha), and Raja (Raja-Hatha) are reputed for their obstinacy.

The headstrong person is not to be stopped in his own course of action, while the obstinate and stubborn is not to be driven to another's way.

The headstrong act; the obstinate and the stubborn may simply refuse to stir.

The most amiable person may be obstinate on some one point; the stubborn person is for the most part habitually so. We speak of obstinate determination, stubborn resistance.

Obstinacy is a habit of the mind. Stubborn and headstrong are species of the obstinate. The former lies altogether in the perversion of the will; the latter in the perversion of the judgement.

Be not under the dominion of your own will. Hold not to all your determinations, but to those which are right.

OSTENTATION

DAMBHA

Ostentation is the art of making a display to draw attention or admiration. It is boasting.

Ostentation is display or show dictated by vanity and intended to invite applause or flattery. It is an ambitious showing forth of whatever is thought adapted to win admiration or praise.

Ostentation is the signal-flag of hypocrisy. It is the master sin of the devil and the father of lies.

As in a pair of bellows there is a forced breath without life, so in those who are puffed up with the wind of ostentation, there are empty words without action.

Ostentation may be without words as the ostentation of wealth in fine residences, rich clothing, costly equipage or the like. When in words, ostentation is rather in manner than in direct statement, as the ostentation of learning.

Boasting is indirect statement and is louder and more vulgar than ostentation. There may be great display or show with little substance. Ostentation suggests something substantial to be shown.

Pomp is some material demonstration of wealth and power, as in grand and stately ceremonies, rich furnishings, processions, etc., considered as worthy of the person or occasion in whose behalf it is manifested. Pomp is the noble side of that which as ostentation is considered as arrogant and vain.

OVER-CREDULOUSNESS

ANDHAVISVASA

Some people are over-credulous. This is also bad. They are very easily cheated by others. You must know his nature, qualities, his antecedents and his behaviour. You must try and test him on several occasions. When you are fully satisfied, then you can place your entire confidence in him. He may be a deep man. He may put on a false appearance and turn out to be quite reverse after some time. You will have to watch him very closely and move with him shoulder to shoulder and hear all about him from several other persons with whom he has moved. Man cannot hide his nature for a very long time. His face is the advertisement board that registers all his inner thoughts and, in short, all that take place in the inner factory. After close examination and test only, one should place his confidence and trust in another man.

PASSION

RAGA

Any strong desire is passion.

Passion is an intense or overpowering feeling, such that the mind is as if passively swayed by it. Any intense or inordinate, continuous affection or impulse as, the passions of love, pride, jealousy, avarice etc., specifically, ardent affection for one of the opposite sex, is passion. Amorous feeling is passion. A fit of intense and furious anger is also passion.

Passion is an emotion by which the intellect is swayed. The object of strong desire is passion. We say: "Music became a passion with Ram."

Passion is an enemy of peace, devotion and wisdom. If you do not have victory over passion, it will annihilate your happiness, health and peace.

He who is ruled by passion is the worst of slaves.

Passion is like a convulsive fit. It is a momentary excitement. It weakens you after enjoyment.

Passion is like an unruly horse. Govern it through prudence, dispassion and discrimination and grow wiser and better. Deliver yourself from passions and you will be free.

Destroy your ruling passion, your master passion first. Then all other passions can be easily annihilated.

A dictator or king rules the people, but passion rules the dictator or the king. A sage or a Yogi alone is a master of the passion. He alone is ever happy, blissful and peaceful.

Your headstrong passion shuts the door of the illimitable kingdom of Bliss. Slay this passion and enter the domain of Bliss.

The strongest of animal passions is that with which you cling to life mundane.

Have passion for God-realisation. This will kill all worldly passions.

CONQUEST OF PASSION

RAGAJAYA

In a broad sense, passion means any strong desire. There is passion for service of the country in patriots. There is passion in first class aspirants for God-realisation. In some people there is a strong passion for novel-reading. There is passion for reading religious books. But generally in common parlance, passion means lust or strong sexual appetite. This is a physical craving for sexual or carnal gratification. When any sexual act is repeated very often, the desire becomes very keen and strong. The sexual instinct or the reproductive instinct in a man involuntarily prompts him for sexual acts for the preservation of his species.

Passion is a Vritti or modification that arises from the mind-lake when the Rajo-Guna predominates. It is an effect or product of Avidya. It is a negative Vikara in the mind. Atman is ever pure. Atman is Vimala or Nirmala or Nirvikara. It is Nitya-Suddha. Avidya Sakti has taken the form of passion for keeping up the Lila of the Lord. You will find in 'Chandi-Path' or 'Durga-Sapta-Sati': "*Ya Devi sarva bhuteshu kamarupena samsthita, namastasyai namastasyai namastasyai namo namah*—I bow to that Devi who has taken the form of passion in all these beings."

Passion is in a seed state in young boys and girls. It does not give them any trouble. Just as the tree is latent in the seed, so also, passion is in a seed state in the minds of children. In old men and women passion gets suppressed. It cannot do any havoc. It is only in young men and women who have reached adolescence that this passion becomes troublesome. Men and women become slaves of passion. They become helpless.

Rajasic food such as meat, fish, eggs etc., Rajasic dress and Rajasic way of living—scents, novel-reading, cinemas, talk on sensual things, bad company, liquors, intoxicants of all description, tobacco, etc.—excite passion. It is very difficult to understand, even by the so-called educated persons, the fact that there is super-sensual happiness in the Atman which is independent of sensual objects. They experience the Atmic bliss daily during deep sleep. They rest in their own Self daily at night. They crave for it. They cannot remain without it. They prepare nice bedding and pillows to enjoy the bliss of the Atman where the Indriyas do not play, where the mind gets rest and the two currents of attraction and repulsion do not operate. They say every morning: "I had a sound sleep last night. I enjoyed it. I did not know anything. There was no disturbance. I went to bed at eight and got up only at seven in the morning." Yet man forgets everything. Such is the force of Maya or Avidya. Mysterious is Maya! It hurls down a man into abyss of darkness. Man again starts his sensual life from the morning. There is no end.

Some ignorant people say: "It is not right to check passion. We must not go against nature. Why God has created young beautiful women? There must be some sense in His creation. We should enjoy them and procreate as many as possible. We should keep up the progeny of the line. If all people become

Sannyasins and go to forests what will become of this world? It will come to an end. If we check passion we will get disease. We must get plenty of children. There is happiness in the house when we have abundant children. The happiness of married life cannot be described in words. It is the be-all and end-all of life. I do not like Vairagya, Tyaga (renunciation), Sannyasa and Nivritti." This is their crude philosophy. They are the direct descendants of Charvaka and Virochana. They are life members of Epicurean school of thought. Gluttonism is their goal of life. They have a very large following. They are friends of Satan. Admirable is their philosophy!

When they lose their property, wife and children, when they suffer from an incurable disease, they will say: "O God, relieve me from this horrible disease. Forgive me of my sins. I am a great sinner."

Passion should be checked at all costs. Not a single disease comes by checking passion. On the contrary, you will get immense power, joy and peace. There are also effective methods to control passion. One should reach the Atman beyond nature by going against nature. Just as fish swims up-stream in a river, so also you will have to move against the worldly currents of evil forces. Then alone you can have Self-realisation. Passion is an evil force and it should be checked if you want to enjoy undecaying Atmic bliss. Sexual pleasure is no pleasure at all. It is attended with dangers, pain, fear, exertion and disgust. If you know the science of the Atman or Yoga you can very easily control the dire malady which is passion. God wants you to enjoy the bliss of the Atman which can be had by renouncing all these pleasures of this world. These beautiful women and wealth are the instruments of Maya to delude you and entrap you into the nets. If you wish to remain always as a worldly man with low thoughts, debasing desires, you can by all means do so. You are at perfect liberty. You can marry three hundred and fifty wives and procreate as many children. No body can check you. But you will soon find that this world cannot give you the satisfaction you want, because, all objects are conditioned in time, space and causation. There are death, disease, old age, cares, worries and anxieties, fear, loss, disappointment, failure, abuse, heat, cold, snake-bites, scorpion-stings, earthquakes, accidents etc. You cannot at all find rest of mind even for a single second. As your

Left Side: **Repeat on the left hand side with the left arm over the right**. Holding the Chi ball the left hand is on top. Hold for a count of five seconds.



Fig. 8.18 *Open the Heavenly Circuit. Then the bottom hand slides and turns 'Palm-Up' and the Top Arm slides to 'hold the Chi Ball'*



Fig. 8.19 *Holding the Chi Ball - Left Side over Right.*

Closing Movements

Activate the Chi Channels - Balance the Organs


Heart Governor (HG-9)
Heart (HT-9)
Lung (LG-11)
Pericardium (P-8)
Triple Warmer (TW-1)
Large Intestine (LI-1)
Small Intestine (SI-1)
LI-4
SI
TW
LI

Fig. 8.20 *Finger Points*

mind is filled with passion, and impurity, your understanding is clouded and your intellect is perverted now. You are not able to understand the illusory nature of the universe and the everlasting bliss of the Atman.

Passion can be effectively checked. There are patent methods. After checking passion, you will enjoy real bliss from within—from the Atman. All men cannot become Sannyasins. They have various ties and attachments. They are passionate and cannot therefore leave the world. They are pinned to their wives, children and property. Your proposition is wholly wrong. It is Asambhava (impossible). Have you ever heard in the annals of world history that this world had become vacant as all men were Sannyasins? Then why do you bring in this absurd proposition. This is an ingenious trick of your mind to support your foolish arguments and satanic philosophy which has passion and sexual gratification as its important tenets. Do not talk like this in future. This exposes your foolishness and passionate-nature. Do not bother yourself about this world. Mind your own business. God is All-powerful. Even if this world is completely evacuated when all people retire to forests, God will immediately create crores of people by mere willing within the twinkling of an eye. This is not your look-out. Find out methods to eradicate your passion.

The population of the world is increasing by leaps and bounds. People are not religious even a bit. Passion is reigning supreme in all parts of the world. The minds of people are filled with sexual thoughts. The world is all fashion, restaurants, hotels, dinners, dances and cinemas. Their life ends in eating, drinking and procreating. That is all. The food production is inadequate to meet the demands of the people. There is likelihood of severe famine and pestilence. Mother of the world sweeps away the extra population when the supply or production of food cannot meet adequately their demands. People are trying to have birth-control methods, or check pessaries, French letters, rubber goods, injection and application of protargol jellies. These are foolish attempts. Further the seminal energy is wasted. There is conservation and transmutation of this energy into Ojas by the practice of celibacy. People are wasting their money in these useless contraceptives. The whole world is under a tremendous sexual intoxication. The so-called educated persons are no exceptions to this rule. All are deluded and move in the world with perverted intellects. Poor miserable specimens of humanity! My sympathies are with them. May God elevate them from this quagmire and open their eyes towards spiritual realms. Self-restraint and celibacy are the only effective natural methods of birth control.

Early marriages form a menace to the society. It is indeed an evil. Bengal and Madras are filled with young widows. Many young men in whom there is a spiritual awakening write to me in pitiable words: “Dear Swamiji, my heart throbs for higher spiritual things. My parents forced me, much against my will, to marry. I had to please my old parents. They threatened me in various ways. I now weep. What shall I do now?” Young boys, who have no idea of this world and this life, are married when they are eight or ten years of age. We see children begetting children. There are child-mothers. A boy of about eighteen has three children. What a horrible state of affairs! There is no longevity. All are short-lived. Frequent child-bearing destroys the health of women and brings in a host of other ailments.

A clerk who gets a salary of Rs. 50/- has six children at the age of 30. Every two years there is an addition. He never thinks, “How shall I maintain such a big family? How shall I educate my sons and daughters? How shall I arrange for the marriage of my daughter?” At the heat of sexual excitement, he repeats the same ignoble act again and again. He has not got a bit of self-control. He is an absolute slave to passion. Like rabbits, he procreates and brings forth numberless children to swell up the number of beggars in the world. Even animals have got self-control. Lions visit their partners only once in all their lives or once in a year. It is only man with his boasted intellect that breaks the rules of health and has become a criminal in this direction. He will have to pay a heavy penalty in the near future for violating the laws of nature.

You have adopted various habits from the West in matters relating to dress and fashion. You have become a creature of vile imitation. They, in the West, do not marry unless they are able to maintain a family decently. They have got more self-restraint. They first secure a decent station in the life, earn money, save something and then only think of marriage. If they have not got sufficient money they remain bachelors throughout their lives. They do not want to bring forth beggars into this world just in the same manner as you do. He who has understood the magnitude of human suffering in this world will never dare bring forth even a single child from the womb of a woman.

When a man with a poor salary has to maintain a big family, he is forced to take bribes. He loses his sense and power of understanding and is prepared to do any kind of mean act to collect money. The idea of God is forgotten. He is swayed by passion. He becomes a slave to his wife. He bears, with a shrug of his shoulders, her taunts and scolding when he is unable to supply her demands. He has no knowledge of the theory of Karma, Samskaras and the working of the inner mental factory. The evil habits of taking bribes, cheating others and telling lies, are imbedded in the sub-conscious mind and is transferred to every physical body in its future births. He brings his own wrong Samskaras and starts the same life of cheating and telling lies in the following births. Will a man who knows this immutable law of Samskaras ever do wrong deeds? A man by his wrong actions spoils his mind and becomes a thief or a cheat in the coming births also. He brings in his old thoughts and feelings which are by nature devilish. One should be very careful in his thoughts, feelings and actions. He should always watch his thoughts and actions and entertain divine thoughts, sublime feelings and do noble actions. Action and reaction are equal and opposite. One should understand and remember this law. Then he will not do any wrong action.

Throughout the Gita the one ringing note that arrests the imagination and mind of the readers is that the man who has calmed his passion-nature is the most happy man in this world. It is also very very easy to control passion which is your deadliest enemy if only you take this subject very seriously and apply yourself to spiritual Sadhana whole-heartedly with a single-minded devotion and concentration. Nothing is impossible under the Sun. Dietetic adjustment is of paramount importance. Take Sattvic food, such as, milk, fruits, green dal, barley, etc. Give up pungent foods such as, curries, chutneys, chillies, etc. Take simple diet. Do Vichara. Chant 'OM.' Meditate on the Atman. Enquire "Who am I"? Remember that there is no Vasana in the Atman. Passion belongs to the mind only. Sleep separately. Get up at 4 A.M., and do the Japa of Maha Mantra or 'Om Namah Sivaya' or 'Om Namo Narayanaya' according to your taste, temperament and capacity. Do meditation on the Divine attributes such as Omnipotence, Omniscience Omnipresence, etc. Study one chapter of the Gita daily. Make it a point not to tell lies even at the cost of death itself. Fast on Ekadasi days or whenever your passion troubles you. Give up novel-reading and cinema-going. Spend every minute profitably. Practise Pranayama also. Study my book "*Science of Pranayama*." Do not look at women with passionate intents. Look at your toes when you walk along the streets and meditate on the form of your deity. Repeat always your Guru Mantra even while walking, eating and working in the office. Try to see God in everything. Keep the daily diary regularly and send it to me for review at the end of every month. Write down your Guru Mantra daily in a clean note book for an hour and send the notebook to me.

You will be able to control passion if only you strictly adhere to the above instructions to the very letter. You can laugh at me if you do not succeed. Blessed is the man who has controlled his passion for he will soon have God-realisation. Glory unto such a soul!

Practise Sirshasana, Sarvangasana and Siddhasana simultaneously, with Pranayama. These are all highly useful in the conquest of passion. Do not overload your stomach at night. Night meals should be very light. Half a seer of milk or some fruits will constitute a good regimen or menu at night. Have the motto: "PLAIN LIVING AND HIGH THINKING" engraved in letters of gold in the forefront of your conscience.

Study select works of Sankara such as, Bhaja Govindam, Maniratna Mala or Prasnottari, Viveka-Chudamani, etc. Read with care "Vairagya Sataka" of Bhartrihari. They are all very elevating and inspiring. Practise always Atma Vichara. Have Satsanga. Attend Kathas, Sankirtan and philosophical discourses. Do not be too familiar with anybody. Familiarity breeds contempt. Do not multiply friends. Do not court friendship with women. Do not also be very familiar with them. Familiarity with women will eventually end in your destruction. Never forget this point. Friends are your real foes.

Avoid looking at women with lustful intents. Entertain Atma Bhava or the Bhava of mother, sister or Devi. You may fail many times. Again and again try to realise this Bhava. Whenever the mind runs towards attractive women with lustful thoughts have a definite clear-cut photo in the mind of the flesh, bone, urine and faecal matter of which women are composed. This will induce Vairagya in the mind. You will not commit again the sin of unchaste look at a woman. It takes some time no doubt. Ladies can also practise the foregoing method and can keep a mental picture just the same way as is described there.

Inflict self-punishment if the mind runs towards women with lustful ideas. Give up night meals. Do twenty Malas of Japa more. Hate lust but not women. Always wear a Kaupeen (Langoti).

Gradually give up salt and tamarind. Salt excites passion and emotion. Salt excites and strengthens the Indriyas. Renunciation of salt brings in a cool condition of the mind and the nerves. It helps meditation. You will suffer a bit in the beginning. Later on you will enjoy a saltless diet. Practise at least for six months. In this way you will be able to realise your own Svarupa very quickly. All that is wanted of you is sincere and earnest effort. May Sri Krishna give you courage and strength to tread the path of spirituality and attain the goal of life.

PESSIMISM

NIRASAVADA

Pessimism is the doctrine that on the whole the world is bad rather than good. It is a temper of mind that looks too much on the dark side of things. It is a depressing view of life. It is the opposite of optimism, which looks on the bright side of life and things here.

Pessimism is a disposition to take a gloomy or despairing view of life. It is a habit of anticipating failure or misfortune. It is a tendency to look on the dark side.

It is the doctrine that the world and human life, or some essential and permanent conditions and limitations of either or both, are essentially evil; in its extreme form, that this is the worst possible world compatible with its continuance in existence.

A pessimist is one who believes that everything is tending to the worst. He who looks too much on the dark side of things is a pessimist.

Pessimism is the great destroyer. It is despair and death. No matter if property, health or even reputation is lost, there is always life if you maintain faith in yourself and look up.

Do not be sure the worst will happen; it rarely does.

The Vedantic and Buddhist view is that life is illusory and burdensome.

Hume's view is that good and evil are so mixed that a beneficent First Cause cannot certainly be predicated.

Schopenhauer's view is that it is the worst possible under the conditions essential to its existence at all, and that life should be a denial and suppression of will.

Pessimism is an undesirable negative quality. This is a temper of mind that looks too much on the darker side of things. It is the doctrine that the whole world is bad rather than good. It is a depressing view of life. Buddhists preach pessimism. Vedantins, though they talk that the world is unreal, are wonderful optimists. They talk of Vairagya to create a taste in the mind of people for the immortal blissful life in Brahman and a distaste for the worthless materialistic life of this world. The opposite of pessimism is optimism. It always looks on the bright side of the picture. A pessimist is ever gloomy and depressed, lazy and lethargic. Cheerfulness is unknown to him. He infects others. Pessimism is an epidemic and infectious disease. A pessimist cannot succeed in this world. Become a powerful optimist and rejoice in the all-pervading Atman. Try to be very cheerful under any condition of life. You will have to practise this.

PIG-HEADEDNESS

HATHA

Pig-headedness is Tamasic obstinacy or stubbornness. This is born of Tamo Guna or darkness. The pig-headed man sticks tenaciously to his own foolish ideas. I gave instructions to a young aspirant. "Do not climb the hill with a plate in each hand and with shoes on, you will slip and break your bones." I gave him an example of a European lady who died instantaneously near Badri Hills from a fall from the summit of a mountain when she was making a vigorous attempt to get Himalayan herbs. I further cited to him another example of a professor of Geology, an M.Sc., of the Lucknow University, who also died of a fall from the mountain in Lakshman-Jhula (Rishikesh), when he was attempting to find out the nature of the rock. The young aspirant did not listen to my words. He was very obstinate. Despite my clear instructions, he climbed the Tehri hills with his shoes on and plates in his hands. This is a clear case of pig-headedness. Pig-headed students cannot make any definite progress in the spiritual path. You should eradicate this evil modification of mind. You should be ever eager to get good instructions from any source, from any sage. You should be ever ready to grasp the truth, no matter from whatever corner it comes.

PILFERING HABIT

ALPACHOURYA

Steya or the pilfering habit is very dangerous. It may develop into a serious crime under suitable conditions and favourable circumstances. If the aspirant is not established in perfect Asteya or non-stealing, he cannot hope to get an iota of progress in the spiritual path. He may retain his breath for five hours, he may do Trataka on the mid-day sun, he may get himself buried underneath the ground for three months or he may show many other dexterous Yogic feats. These are of no value if he has the pilfering habit. He may be respected and adored for a week or a month. People will treat him with contempt when he starts pilfering.

Do not be deceived by external appearances. Just hear this remarkable incidence. A Pundit of vast erudition was a guest of high personage. The Pundit could recite by-heart the whole of the Vedas and the Upanishads and he had done great Tapasya. He was very abstemious in his diet and took only a very small quantity of food. He would never waste unnecessarily a single minute of the day and was always absorbed in the study of religious books, Puja, Japa and meditation. His host held him in very high esteem. This learned Pundit stole one day some articles from his host's house. They were not valuable at all. In the beginning he totally denied the theft. Later on he admitted it and apologised. Would anybody take such a learned Pundit of severe austerities for a petty thief? The subtle Vritti of pilfering was hidden in the Pundit's mind, he had not destroyed it through self-analysis and drastic purificatory Sadhana. He had only controlled his tongue to a small extent and crammed some sacred books.

PREJUDICE

AVICHARAPURVA-PAKSHAPATA

Prejudice is judgment or opinion formed beforehand or without due examination of the facts or reasons that are essential to a just and impartial determination. It is unreasonable presupposition for or against anything. It is bias.

The destructive qualities of prejudice can be removed by goodwill.

Prejudice shuts out the truth and often leads to ruinous error.

Prejudice is a mist which dims your vision and obscures the good and glorious objects.

Prejudiced persons never speak well, but also never think well of those whom they dislike.

Prejudice is the child of ignorance. It is a great obstacle to progress.

When the judgment is weak, the prejudice is strong.

A prejudice is grounded often on feeling, fancy, associations, etc. A prejudice is always unfavourable.

Prejudice is unreasonable dislike for something or some person. Prejudice makes the brain callous. The brain cannot vibrate properly to grasp the things in their true light. One cannot endure honest differences of opinion. This is intolerance. Religious intolerance and prejudice are great obstacles in the path of God-realisation. Some orthodox Sanskrit Pundits strongly think that only Sanskrit-knowing people will have God-realisation. They think that English-knowing Sannyasins are barbarians and they cannot have Self-realisation. Look at the thick foolishness of these bigoted Pundits! Incorrigible, petty-minded, narrow-hearted, crooked sectarians! If one has prejudice against Bible or Koran, he cannot grasp the truths that are included there. His brain becomes hard, stony and callous. A man can realise by studying and following the principles that are laid down in Koran, Bible or Zend Avesta or the Pali books of Lord Buddha.

Aspirants should try to remove prejudice of all sorts. Then only they can see truth everywhere. Truth is not the sole monopoly of the Sanskrit Pundits of Benares or the Vairagis of Ayodhya. Truth, Rama, Krishna, Jesus are the common property of all. Our Bengalee brothers think that Ramakrishna Paramahamsa and Vivekananda belong to the Bengalees only. There is a general complaint that the Bengalees and Bengalee Sannyasins are clannish and provincial. It is high time now for them to remove this undesirable spirit in them. This is a great taint. They are famous for their intelligence. Those Sannyasins who have gone abroad to the Continent and those who are educated in the West are exceptions. They are catholic.

Sectarians and bigoted people confine themselves to a small circumscribed circle or area. They have no large heart. They cannot see the good points in others on account of their jaundiced vision. They think that their principles and doctrines only are good. They treat others with contempt. They think that their Sampradaya only is superior to others, and that their Acharya only is a man of God-realisation. They always fight with others. There is no harm in praising one's own Guru and sticking to his principles and teachings. But one should pay equal regard to the teachings of other prophets and other saints. Then only the feeling of universal love and universal brotherhood will manifest. This will eventually lead to the realisation of God or Atman in all beings. Prejudice, intolerance, bigotry, sectarianism should be thoroughly eradicated. Prejudice and intolerance are forms of hatred.

MORAL AND SPIRITUAL PRIDE

NAITIKA GARVA, ADHYATMIKA GARVA

As soon as an aspirant gets some spiritual experiences or Siddhis he is puffed up with vanity and pride. He thinks too much of himself. He separates himself from others. He treats others with contempt. He cannot mix with others. If anyone has some moral qualifications such as spirit of service or self-sacrifice, or Brahmacharya, he will say: “I am Akhanda Brahmachari for the last twelve years. Who is pure like myself? I lived on leaves and gram for four years. I have done service in an Ashram for ten years. No one can serve like myself.” Just as worldly people are puffed up with the pride of wealth, so also Sadhus and aspirants are puffed up with their moral qualifications. This kind of pride is also a serious obstacle in the path of God-realisation. It must be eradicated thoroughly. As long as a man boasts himself, so long he is the same little Jiva only. He cannot have Divinity.

PROCRASTINATION

VILAMBANAM

Procrastination is putting off till a future time, through indolence or lack of resolution. It is dilatoriness. It is postponing or delaying. It is culpable delay.

Procrastination is the thief of time. It is the destroyer of initiative. It closes the door to advancement.

That "tomorrow" will never come. Tomorrow is too late for anything. He who sees help and salvation in tomorrows shall continually fail and fall today. That lazy tomorrow will be like today.

The foolish man says: "I will rise early tomorrow. I will pray and meditate tomorrow. I will carry out my intentions tomorrow." But the wise man rises early today, starts prayer and meditation today, carries out his intentions today and attains strength, peace, and success today.

What you can do this morning never postpone till the evening. Never put off till tomorrow that which you can do today.

Tomorrow is a period found in the fools' calendar alone.

Be wise today. Delay not till tomorrow. Tomorrow's sun may never rise.

'By and by' is a dangerous thing. You can arrive at the house of 'never' by the avenues of 'by and by.'

PRODIGALITY

ATIVYAYA

Prodigality is extravagance. It is spending without necessity.

A prodigal wastes his money. He throws away his money without necessity.

A prodigal squanders his fortune in bagnios, gambling and drinking and digs his own grave.

He falls into poverty, misery and abject disgrace. He becomes a victim to various vices.

The closing movements balance organ energy while activating the Chi Channels.

Hold the arms extended forward with the palms down at solar plexus level. Hold each stage for a count of five seconds.

Index Fingers:

Tense all the fingers and feel the Chi filling all the joints; open the index fingers, raising them up, while keeping the rest of the fingers level.





Large Intestine

Fig. 8.21 *Activate the Index Fingers - Up.*

The tension should be like the string of a tuned musical instrument. When lightly tense the Heavenly Chi will be drawn in through the index fingers.

Relax the hands and bring the index fingers back to the neutral position, level with the other fingers.





Energy to Large Intestine

Fig. 8.22 *Draw Earth Energy through the Index Fingers - Down.*

Stretch out and tense all the fingers and **press the index fingers to point down** toward the earth and continue down to the universe. Keep the other fingers level. **Draw in earth energy through the index fingers and circulate it through the body.**

He is intemperate, luxurious and ultimately starves. He cannot get even the necessities of life. He drags a cheerless existence. He leads a life of dissipation.

It is said that the prodigal of twenty makes the miser of seventy.

Spend money in charitable purposes. Be extremely liberal, but not extravagant. Waste not money.

REVENGE

PRATIKARA, PRATIDROHA

Revenge is injury inflicted in return. It is a malicious injury in return for an injury received. It is passion for retaliation.

To revenge is to inflict punishment, or injury, whether positive or negative in retaliation for an injury in a vindictive, malicious or spiteful manner.

Revenge is vindictive nature. It is a desire to inflict injury in return.

If anyone injures you, ignore it, forgive it. It is finished. You will have peace of mind.

Revenge is a common passion. The religion of love emphatically condemns it. Nothing so debases man as revenge.

Revenge is no valour. To bear an insult and an injury is indeed valour, strength and conquest.

Revenge returns back and hits your own heart with a heavy blow. It recoils on your own self. Revenge is a self-tormentor. Therefore, revenge not. Forget and forgive.

The spirit of revenge is the very spirit of the devil.

If any man injures you out of malicious nature, it is like the thorn which pricks and scratches. Mind it not. Be noble. Love him. He is weak and ignorant. He knows not really what he is exactly doing.

The indulgence of revenge tends to make man more savage and cruel.

Sweet is revenge, especially to women.

Revenge boils your blood and produces various diseases. It burns your heart and disturbs your peace. Therefore, revenge not.

Retaliation and revenge are personal and often bitter. Retaliation may be partial. Revenge is meant to be complete and may be excessive.

Vengeance, which once meant an indignant vindication of justice, now signifies the most furious and unsparing revenge.

Revenge emphasises more the personal injury in return for which it is inflicted: vengeance is the ill-desert of those upon whom it is inflicted. A requital is an even return, such as to quit one of obligation, for what has been received and may be good or bad. Avenging and retribution give a solemn sense of exact justice, avenging being more personal in its infliction whether by God or man, and retribution to the personal visitation of righteous law.

Compassion, excuse, forgiveness, grace, mercy, pardon, pity, reconciliation are opposites of revenge.

RUDENESS

DHRISHTATA

Rudeness is roughness, harshness, wildness.

Rudeness is uncivil nature. It is brutal nature. It is ferocious nature. It is barbarous nature.

It is born of ignorance. It is the child of Tamo-Guna.

It is due to lack of culture, good breeding, good manners, good education.

Whoever one is, and wherever one is, one is always in the wrong if one is rude.

Rudeness is characterised by abrupt or rough discourtesy, as of manner or speech.

A rude man is offensively blunt or uncivil. He is impolite. He is impudent. He is impetuous. He is insolent. He is boisterous.

We say: “Mr. John is a rude fellow. He uses rude language.”

Rudeness is characterised by lack of polish, refinement, or delicacy, as from lack of training or acquaintance with polite or civilised usage.

A rude man is a raw, crude man. He is without grace, finish, or cultivation. He is clownish. He is lacking good taste, chasteness, grace or elegance.

Rudeness is characterised by violence, harshness or cruelty.

Cultivate politeness, courtesy, good manners, elegance, civil nature, gentleness, softness, sweetness. Rudeness will take to its heels.

Be gentle. Be sweet. Be soft. Be polite. Be courteous. You will win friends. You will be liked by all. You will be honoured and respected.

SELF-ASSERTION

AHAMPRATYAYA, AHAMTA, ATMASLAGHANAM

Self-assertive nature is a great obstacle in the spiritual path. This is an evil quality born of Rajas. This is accompanied by vanity and arrogance. The aspirant who is a slave of the self-assertive nature wants to cut an important figure. He poses to be a great Yogi with many Siddhis. He says, "I am much advanced in Yoga. I can influence many people. No one is equal to me in the field of Yoga. I possess tremendous psychic powers." He expects others to pay respect to him and do prostration. He gets easily annoyed with people if they do not honour him and do not make prostrations. He tries to keep up his position and prestige. The self-assertive aspirant does not pay any attention to the instructions of his Guru. He has his own ways. He pretends to be obedient to his Guru. At every step his little ego asserts itself. He is disobedient and breaks discipline. He creates party-spirit, revolt, chaos and disorder. He forms parties. He criticises Mahatmas, Sannyasins, Yogis and Bhaktas. He has no faith in the scriptures and the words of sages. He insults his own Guru even. He conceals facts and tells deliberate lies to keep up his position or to cover up his wrong actions. He tells several lies to cover up one lie. He twists and tortures real facts.

SELF-CONCEIT

SVABHIMANA

Self-conceit is an over-high opinion of one's own self, one's own merits, abilities, acquirements, etc. Self-conceit is vanity.

A fool thinks he knows everything. He will not learn anything.

A man of self-conceit is not able to discover his mistakes, defects and weaknesses. His intellect is veiled and clouded.

His intellect is turbid. His intellect is in a state of intoxication. Conceit is more intoxicating than alcohol, opium or cannabis indica.

A man of self-conceit will always speak of himself.

Self-conceit and affectation are twins. They are merely different shades of the same feeling.

A man of self-conceit will not stoop to be vain. He is very busy in wriggling to catch fair words from others.

The more you speak of yourself, the more you are likely to utter falsehood.

Self-conceit is the tongue of egoism and vanity. A man of self-conceit always bores all persons.

If you want men to speak well of you, never speak well of yourself.

A man of self-conceit talks so much about himself that he gives no time for others to speak.

You can never expect justice from a man of self-conceit.

A man of self-conceit is a slave of praise. He is a slave to everyone who flatters him. He is everybody's fool.

Self-conceit is the foundation of the most ridiculous and contemptible vice.

Kill this ignoble self-conceit ruthlessly, through humility, meekness, and enjoy peace.

SELF-JUSTIFICATION

ATMAPRATIPADANAM

This is a very dangerous habit for an aspirant. It is an old-standing habit. Self-assertion, self-sufficiency, obstinacy, dissimulation, speaking falsehood are the constant retinue or attendants of self-justification. He who has developed this can never improve himself as he will never admit his faults. He will always try his level best to justify himself in various ways. He will not hesitate to tell several lies to support his false statements. He will tell one lie to cover another lie and he will speak lies *ad infinitum*. The aspirant should always admit his faults, mistakes, weaknesses, etc., then and there. Then only he can improve quickly.

SELFISHNESS

SVARTHAPARATA

Selfishness is the state or quality of being selfish.

A selfish man chiefly or wholly regards one's own self. He is void of regard for others. He acts from the consideration of what will give him the greatest pleasure.

He who clings to self is his own enemy. He is surrounded by enemies. He who abandons self is his own saviour. He is surrounded by friends.

O man! Fear the atom bomb far less than human selfishness.

Selfishness is the basis of all the world's troubles. It is at the root of all evils. It is the bane of happiness. It is a detestable vice. It destroys spirituality. It is the dire enemy of peace.

Selfishness is that evil quality of wholly regarding one's own self without regard for others.

Selfishness is an undue or exclusive care for one's own comfort or pleasure regardless of the happiness and often of the rights of others. It limits endeavour to a narrow circle of intensely personal aims, destroys all tender sympathies and is ultimately fatal not only to the welfare but to the happiness of him who cherishes it.

Selfishness is a detestable vice. It is the basis of all the worldly troubles and wars. It is at the root and source of all national and moral evils.

Destroy selfishness, the bane of happiness, through the practice of cosmic love, disinterestedness and selflessness.

Selfishness destroys your spiritual nature.

A selfish man lives only to benefit himself.

Selfishness is the root of all sins.

Selfishness is leprosy. Selfishness is cancer.

Selfishness is only generosity with narrow walls. A selfish man maintains a wife in luxury and makes his children rich.

Selfishness is the root and source of all natural and moral evils. Selfishness itself is the master evil of the world.

Sensual pleasure is the chief aim of a selfish man. Selfishness works through the senses. A selfish man gives a full play to his senses.

Selfishness is undue regard for one's own interest, gratification, advantage or the like, regardless of others and exhibited as disposition, character or conduct, distinguished from a reasonable self-regard or self-love.

A selfish man is influenced by personal motives or desires to the disregard of the rights, comforts or wishes of others.

Self-love is due care for one's own happiness and well-being, which is perfectly compatible with justice, generosity and benevolence towards others.

Selfishness is an undue or exclusive care for one's own comfort or pleasure, regardless of the happiness and often of the rights of others.

Self-love is necessary for high endeavour, and even for self-preservation. Selfishness limits endeavour to a narrow circle of intensely personal aims, destroys all tender sympathies, and is ultimately fatal not only to the welfare but to the happiness of him who cherishes it.

Selfishness is the cause of war. Selfishness, lust and greed co-exist.

According to the selfish theory of morals man is incapable of acting from other than a selfish motive.

Destroy selfishness through selflessness, nobility and magnanimity, and become a selfless Karma-Yogin.

SELF-SUFFICIENCY

ALAMBUDDHI

Self-sufficiency is another evil Vritti in the mind-lake. This also is born of a mixture of Rajas and Tamas. It acts as a stumbling block in the spiritual path. The student who is a victim to this evil trait thinks foolishly that he knows everything. He is quite contented with his little knowledge and achievements. He stops his Sadhana. He never attempts for further acquisition of knowledge. He never endeavours to attain the highest knowledge of Bhuma (Highest Self). He does not know that there is a vast realm of knowledge beyond. He is like the toad in the well which has no knowledge of the ocean, which thinks that the well is the only illimitable expanse of water.

A self-sufficient man foolishly thinks and imagines, "I know everything. There is nothing more to be known by me." Maya spreads a thick veil in his mind. The self-sufficient man has a turbid mind, clouded understanding and a perverted intellect.

Self-sufficiency is a strong weapon of Maya with which she deludes people and puts a strong break on the Sadhana of an aspirant. She does not allow him to proceed further or look beyond the veil, as he is carried away by false contentment through self-sufficiency.

The self-sufficient scientist who has knowledge of electrons and laws of the physical aspect of nature thinks that there is nothing beyond this. The moralist who has developed some ethical virtues thinks that there is nothing beyond this. The self-sufficient Yogic student who experiences Anahata sounds and flashes of lights thinks that there is nothing beyond this. The self-sufficient Sannyasi who knows the Gita and the Upanishads by heart thinks that there is nothing beyond this. The self-sufficient Yogi or Vedantin who gets experiences of the lower Samadhi thinks that there is nothing beyond this. All are groping in the dark. They know not what perfection is.

Maya tests the student at every step, at every stage, and appears before the student in various forms and colours, like an Asura or a chameleon. It is very difficult to detect Her presence. But he who has obtained the grace of the Mother will experience no difficulty in his onward march. She Herself lifts him up and carries him in Her hands to the destination to introduce him to Her Lord—Lord Siva—and to get him established in unshaken Nirvikalpa Samadhi.

The aspirant should always think, "What I know is very little. It is only a handful of knowledge. What is still to be learnt by me is oceanful." Then alone he will have intense aspiration or yearning for further knowledge.

SHILLY-SHALLYING

VIKSHEPA

Vikshepa is tossing or oscillation of mind. This is an old habit of the mind. All Sadhakas generally complain of this trouble. The mind never stays at a fixed point for a long time. It jumps hither and thither like a monkey. It is always restless. This is due to the force of Rajas. Whenever Sri Jaya Dayal Goyandka came to me for an interview he used to put always two questions: "Swamiji, what is the remedy to control sleep? How to remove

Vikshepa? Give me an easy and effective method." My answer was: "Take light diet at night. Do Sirshasana and Pranayama. Sleep can be conquered. Trataka, Upasana and Pranayama will remove Vikshepa." It is better to have a combined method. This will be more effective. Patanjali Maharshi prescribes Pranayama for destroying Rajas which induces Vikshepa and for getting one-pointed mind.

In the Gita Lord Krishna prescribes a Sadhana for removing Vikshepa. "As often as the wavering and unsteady mind goeth forth, so often rein it in, let him bring it under the control of the Self. Abandoning without reserve all desires born of the imagination, by the mind curbing in the aggregate of the senses on every side, little by little let him gain tranquillity by means of Reason controlled by steadiness; having made the mind abide in the Self, let him not think of anything"—Chapter VI: 24, 25, 26. Trataka is an effective method for destroying Vikshepa. Practise this for half an hour on a picture of Lord Krishna or on a black point on the wall. First do this for two minutes and gradually increase this period. Close the eyes when tears come. Look steadily at the object without winking. Do not strain the eyes. Look gently. There are students who can do Trataka for 2 or 3 hours. For full description read my book: "*Kundalini Yoga.*"

SHYNESS

LAJJA

Shyness is a great hindrance in the path of success in life. This is a form of timidity of low fear. Almost all boys have got this weakness. This is a feminine quality which is the Svabhava of women. Shyness manifests when one is in the wrong path. Every woman knows that the goal of life is God-realisation and yet she indulges in sexual pleasures. This wrong action makes her shy when she appears before any man. A shy boy or man cannot express his thoughts boldly before any person. He cannot look directly at the eyes of another man. He will talk something and look at the ground. He cannot approach freely any stranger. A shy man cannot get on well in any kind of business or office. Modesty is not shyness. Modesty is decency or chastity. This comes out of politeness and polish of character. Some *zenana* ladies are very shy in the beginning in talking to men when they come outside after the death of their husbands.

Gradually they become bold and shyness vanishes. Those who are shy should try to talk with others boldly. They should look directly at the eyes of others. Shyness is a great weakness. It should be eradicated quickly by cultivating courage.

SLANG TERMS AND ABUSES

APASABDA, NINDA

The vast majority of persons have got the evil habit of using slang terms and abuses every second, during their conversation. When they become excited and angry they pour forth a continuous shower of all sorts of foul words. It cannot be described. There are people who use such words as *Sala*, every second. It will come out like the words: 'you see' in some people. '*Sala*' means brother-in-law (in Hindi). If you call anybody by the term '*Sala*' he will become very furious. People have got a vulgar habit and use these slang terms. A man of refined taste, culture and polish can never utter any such words. English people very often use the words; "Damn fool: The son of a bitch," etc. The English military people use the word 'Damn' every second. They cannot talk without a *damn* in a sentence. This also is a very bad habit. See the children in the streets. They fight, quarrel and use obscene words. When any Englishman comes to India or to any new country, he first tries to learn some obscene words. Look at human nature! He does not want to learn the names of God. When the cart-driver twists the tail of the bull, when the *Tongawala* whips the horse, there come the words: "*Sala, Badmash, Suwar Ka Batcha*, the son of a pig," and so on.

Parents should check their children when they utter any bad words. They themselves should not use any bad words. They themselves become the Gurus for these children. Children simply imitate. Children have got a strong power of imitation. Practise to use the words such as: "Hare Rama, Hare Krishna, Hae Prabhu" always, even when you talk. Bring these words every second. Train your children also. This itself will form a kind of Japa or remembrance of God. Train your mind. Check also people who often use vulgar words through bad habit. This is the most important duty of the parents. Any healthy habit sown in the minds of children becomes firmly rooted.

SLEEPING IN DAY TIME

DIVASVAPA

Sleeping in day time is another evil habit. It shortens life. Time is wasted considerably. It brings in laziness and lethargy. It develops gastritis, dyspepsia and a host of other ailments. It should be entirely given up, if you want to grow quickly. Snatch every second and utilise it properly. Life is fleeting, time is short, death is waiting. How happy is the man who is thoroughly destitute of a single evil habit. He can attain great success in life and apply himself diligently to Yogic Sadhana.

SMOKING HABIT

DHUMRAPANAM

He who smokes is unfit for the practice of Karma Yoga. He becomes dull when he cannot get a whiff of smoke. He cannot work in the absence of cigarettes. He wastes his money that can be very well utilised in the service of others. A Karma-yogi should be strictly free from the evil habit of smoking.

Smoking is an evil habit. Smokers bring a little bit of philosophy and medical opinion in support of their principles. They say: “Smoking keeps bowels free. I get a good motion in the morning. It is very exhilarating to the lungs, brain and the heart. When I sit for meditation after a smoke, I get nice meditation. Why should I give it up?” Very sound philosophy! They bring in ingenious arguments to support their evil habit. They cannot get rid of this evil habit. They are heavy smokers who can finish a tin of cigarettes within five minutes. This habit starts from early boyhood. A little boy gets a curiosity smoking. He stealthily removes a cigarette from his elder brother’s pocket and tries a first smoke. He gets little tickling of nerves and hence he continues stealing daily. After some time he arrives at a stage when he finds it extremely hard to manage with a few cigarettes. He begins to steal money to get a tin of cigarettes independently. The father, brothers and sisters are all heavy smokers. They are the Gurus for these little boys for initiation in smoking. What a nasty state of affairs! Horrible indeed is the sight!

The parents are wholly and solely responsible for the evil conduct of their sons and daughters. Any intoxicant breeds in a bad habit soon and the man finds it difficult to give up the habit.

Bring the index fingers back to neutral and relax your hands.

Once again **open the index fingers by raising the index fingers up**, while keeping the rest of the fingers level. **Draw in the Heavenly Chi through the index fingers**.

Bring the index fingers back to neutral again and relax your hands.

Ring Fingers:

Stretch the ring fingers down toward the earth, keeping the rest of the fingers level. Draw in earth energy through the ring fingers and circulate it through the body.



Pericardium sack around the Heart

Fig. 8.23 *Draw Earth Energy through the Ring Fingers.*

Bring the ring fingers back to neutral and relax your hands.

Once again open the index fingers by raising the index fingers up, while keeping the rest of the fingers level, and draw in the Heavenly Chi through the index fingers.

Bring the index fingers back to neutral again and relax your hands.

Thumbs:

Stretch the thumbs out and down toward the earth, keeping the rest of the fingers level. Draw in earth energy through the thumbs and circulate it through the body.

Bring the thumbs back to neutral and relax your hands.





Fig. 8.24 *Draw Earth Energy through the Thumbs.*

He falls a prey to smoking. Maya havocks through habits. This is the secret of her workings. You will not get an iota of benefit from smoking. Pray, give up this wrong, foolish imagination. Money is simply wasted. Smoking brings irritable heart, "tobacco heart" and amblyopia and other deadly diseases of the eyes and nicotine poisoning of the system. Various nervous diseases and impotency also develop.

Short-sightedness, palpitation of the heart, irregular action of the heart, angina pectoris (a painful disease of heart), gastric catarrh, throat troubles, inflammation of the wind pipe or trachea, tremors, muscular weakness etc., have been traced to smoking and the consequent nicotine poisoning. There is cumulative effect of nicotine from protracted smoking. The nicotine accumulates in the system by the addition of slow doses and produces deleterious effects on the constitution, various systems and different organs.

The correction of any evil habit is very simple. An advocate was a terrible smoker for a period of fifteen years. With one strong and powerful will he abandoned it entirely. Feel strongly first that you have got an evil habit and feel strongly also that you should give up that evil habit immediately. Think strongly of the advantages of sobriety and temperance. Then you have already attained success. Will strongly: "I will give up this intolerable habit this very second." You will succeed. Giving up any bad habit at once is better. The habit of slowly giving up by gradual reduction generally does not turn out to be productive of good results. Beware of recurrences. Turn your face resolutely when a little temptation tries to reappear. Keep the mind fully occupied in your work. Be always busy. Entertain a strong desire: "I must become a great man presently." All these habits will take to their heels. Feel strongly: "I must become a spiritual man." All these habits will fly away. Use your subconscious mind for the eradication of your habits. It is your intimate bosom friend with whom you should keep companionship at all times. He will make matters all right. Establish new and healthy habits. Develop your will also. Give up bad company and always enjoy Satsanga or the company of learned Sadhus and Mahatmas. Their strong currents will overhaul your evil habits. Prayer, Japa and meditation will also help in the eradication of this evil habit. There is nothing impossible under the sun. Where there is a will there is a way.

SUSPICION

SANKHA

Suspicion is the imagining of something without evidence or on slender evidence. It is mistrust.

Suspicion is conjecture with imperfect or with little or no evidence to support it, that something, especially something wrong exists or is about to happen. It is doubt.

Suspicion clouds the mind. It creates rupture among friends. It loses friends. It is a defect not in the heart, but in the brain.

Suspicion is the mark of a mean spirit and a base soul. A noble man suspects none.

Suspicion checks business, disposes kings to tyranny and irresolution, husbands to jealousy and hatred.

Freedom from suspicion promotes happiness in man. Suspicion is an enemy to happiness.

Ignorance is the mother of suspicion. Attain knowledge. Suspicion will vanish.

Suspicion is the poison of true friendship.

If suspicion enters your mind, love and confidence will go out.

Suspicions among thoughts are like bats among birds. They ever fly by twilight.

Suspicion is an enemy to virtue. A suspicious man will soon be corrupt. He who is corrupt is naturally suspicious.

Too much suspicious nature is very bad. This is the opposite to over-credulousness. Mind always moves in extremes. Husband suspects his wife always. The wife also suspects the husband. There is always tug-of-war and trouble in the house. The proprietor of a shop suspects his servants always. How can business go on smoothly? The world runs on faith. The directors of biggest railway companies in India are in England. They do not know in detail what exactly is going on in India. Yet the railways run smoothly. The directors have full confidence in the Agents, the officials. These people in turn believe the directors. The shareholders of the coffee, tea and rubber estates in India and Ceylon are in America and England and the business goes on well. Business runs on faith. If people are too much suspicious, friction and rupture will be always going on. Allow a margin and try the man. Do not go to extremes. Do not be over-credulous. Do not be over-suspicious. Keep to the golden medium.

TALE-BEARING

PISHUNATA

Tale-bearing is the act of maliciously telling tales or giving information. It is the act of spreading scandal.

A tale-bearer circulates idle and injurious tales with a view to making mischief. He is a scandal-monger, a meddling informer.

Do not go up and down as a tale-bearer among your people. Where there is no tale-bearer, all quarrels stop.

Tale-bearing is despicable. A tale-bearer is condemned by all.

Why do you meddle in the affairs of others unnecessarily? Abandon tale-bearing. Mind your business. You can save time. Spend your time profitably in prayer, Japa, Kirtan, meditation and study of religious books. You will attain eternal peace.

TIMIDITY

KAATARATA

Timidity is another meanness. This is faint-heartedness. This is a form of fear. This is also akin to shyness. A timid man has a chicken-heart. He is unfit for public activities and any kind of adventurous work. He is a toad that lives in a small well. He cannot run out to be a resourceful man in life. He cannot talk boldly to his superiors. He cannot deal boldly with his customers. How then can he expect prosperity? He is also afraid of losing his life, wife, children and property. He is afraid of public opinion. A timid man is more or less like a woman. Timidity must be eradicated by developing courage. Timidity is a curse. It weakens man. It checks his growth. It hinders his success in life.

TREACHERY

VISVASA-GHATA

Treachery is faithlessness.

A treacherer is a traitor.

There is no knife that cuts so sharply and with such poisoned blade as treachery.

Violation of allegiance, confidence or plighted fact is treachery. Traitorous or perfidious conduct is treachery.

A treacherous man is untrustworthy. He gives a specious and misleading impression. He puts on a good or fair appearance, but he is bad in character or nature. He betrays a trusted friend.

He smiles and laughs, but cuts the throat in the end.

You cannot place any confidence on a treacherous man. He is waiting for opportunities to plunder and kill you. He is deceptive.

'Treacherous' respects a man's private relations; 'traitorous' his public relation to his country. He is a treacherous friend and a traitorous subject or citizen.

One may be treacherous to his enemies as well as his friends. One may be traitorous to his country by abstaining to lend that aid which is in his power.

A soldier is traitorous who goes over to the side of the enemy against his country. A man is guilty of treasonable practices who attempts on the life of the ruler or aims at subverting his government.

Kill this treacherousness by practising honesty, reliability and trustworthiness.

VANITY

DAMBHA

Vanity is empty pride or ostentation. It is vain display or idle show.

Vanity is a feeling of shallow pride. It is inordinate self-esteem. It is conceit. It is emptiness.

Vanity is the quality or state of being vain or elated with a high opinion of one's own accomplishments or achievements. It is empty pride inspired by an overwhelming conceit of one's personal attainments or decorations and causing its possessor to be morbidly anxious for the notice, admiration and applause of others.

Vanity is that species of pride which, while it presumes upon a degree of superiority in some particular articles, fondly courts the applause of everyone within its sphere of action, seeking every occasion to display some talents or some supposed excellence.

Vanity exposes a man to scorn and derision and ruins his character. He is ridiculed wherever he goes. Vanity is the foundation of the most ridiculous and contemptible vices of affectation and uttering falsehood.

A man of vanity takes immense delight to speak of himself but he knows not others do not like to hear of him.

A man of vanity is arrogant. He is puffed up with pride. He does not hear the wise counsels of elders. He cares not for the judgment and opinion of others.

He treats others with insolence. He treats his inferiors with contempt and impudence. He puts on showy dress and walks in the public street. He casts round his eyes and courts observation.

He takes immense delight in hearing and speaking of himself throughout the day. He gossips and wastes his time.

Vanity is the mother. Affectation is the darling daughter. Pride and vanity are merely different shades of the same feeling. A man of pride has at least something, but a man of vanity is absolutely empty.

One does not know anything of Yoga. He may know a few Asanas, but he poses as a great Yogi of Nirvikalpa Samadhi. This is one form of vanity.

One does not know anything of Vedanta. He might have learnt a bit of Vicharasagara and Panchadasi; but he poses as a realised Sage. This is another form of vanity.

Even a fool, a porter, a wood-cutter, wishes to have his own admirers. Vanity is so rooted in the heart of every man.

Vanity is attached to the opinion of others while conceit is perfectly satisfied with its opinion of itself.

Everyone cherishes vanity at the bottom of his heart. Even the crow, the pig or the deformed man thinks himself good-looking and beautiful.

This world is a vanity fair. It is a scene of vanity and folly. It is the world of fashion. It is a collection of the most alluring temptations of the world.

A learned Pundit who is versed in the Sastras and who is proud of his knowledge in vain without any spiritual Anubhava is pitiable indeed. He is like a peacock. He is fond of pedantry and arguments. He engages himself in lingual warfare and intellectual gymnastics. He is a '*Dukrin Karane*' of Sri Sankara's Bhaja Govindam song. Surely high sounding Johnsonian words cannot make a man pious.

Even if you know the Gita, the Upanishads and the Brahma Sutras by heart what would all these profit you if you have not got the Grace of the Lord and Anubhava? You will be like the ass which carries a heavy load of sandal-wood on its back. Have you not heard the stories of Bharadwaja and Narada who carried a cart-load of religious books to Indra and Sanat Kumara respectively?

What you have learnt is only a handful. What you have not learnt is an oceanful. False learning makes one proud and self-conceited.

Do not think much of yourself and your learning. This is pure self-conceit.

Vanity is exaggerated pride. A proud man possesses at least something either physical or mental. But a man of vanity (Dambha) or hypocrisy does not possess anything and yet he thinks that he is superior to all.

Some aspirants have got more vanity than worldlings. They are proud of their moral virtues, some sort of Siddhis and their spirituality and Samadhi.

Moral and spiritual pride are more dangerous than the ordinary pride of wealth and power. Also they are more difficult to be eradicated. Aspirants should be ever vigilant and cautious. They should always keep up the spirit of service and humanity.

VILLY VALLYING

DISCUSSING TOO MUCH

Some people in whom the reason has developed have got the habit of entering into unnecessary controversies and discussions. They have got Tarkika Buddhi. They cannot remain quiet even for a second. They will create opportunities for heated debates. Too much discussions end in enmity and hostility. Much energy is wasted in useless discussions. Intellect is a help if it is used in the right direction of Atmic Vichara. Intellect is a hindrance if it is used in unnecessary discussions. Intellect takes the aspirant to the threshold of intuition. Thus far and no further. Reason helps in inferring the existence of God and finding out suitable methods for Self-realisation. Intuition transcends reason but does not contradict reason. Intuition is direct perception of Truth. There is no reasoning here. Reasoning concerns matters of physical plane. Wherever there is why and wherefore there is reasoning. In transcendental matters which are beyond the reach of reason, reason is of no use.

Intellect helps a lot in reflection and ratiocination. But people in whom reasoning has highly developed become sceptical. Their reason becomes perverted also. They lose faith in the Vedas and in the teachings of Mahatmas. They say: "We are rationalists. We cannot believe anything which does not appeal to our reason. We do not believe the Upanishads. We reject anything that does not come within the domain of reason. We have no faith in God and Sat-Gurus." Those so-called rationalists are a type of atheists only. It is very difficult to convince them. They have an impure, perverted reason. Thoughts of God cannot enter their brains. They will not do any kind of spiritual Sadhana. They say: "Show us your Brahman of the Upanishads or Isvara of the Bhaktas." Those who are of doubting nature will perish. Reason is a finite instrument. It cannot explain many mysterious problems of life. Those who are free from the so-called rationalism and scepticism can march in the path of God-realisation.

WORRY

Worry is tearing oneself with anxiety, vexation, trouble, perplexity, etc., as the worry of business, the worry of politics, the cares and worries of life.

Do not anticipate trouble or worry about what may never happen.

Keep yourself always very busy. Be doing something useful. This is the surest antidote for worry.

No one has yet been able to claim any good thing through worry. Then, why worry?

It is not the cares of today, but the cares of tomorrow that weigh you down. When tomorrow's burden is added to the burden of today, then the weight is more than a man can bear.

Worry not over what is past. Forget it.

Do not worry about things which are not likely to happen. "Sufficient unto the day is the evil thereof."

Worry is uneasiness in mind by reason of cares or solicitude. It is a state of perplexing care, anxiety or annoyance. It is distracting or disturbing care or occasion for anxiety. It is vexation, fret.

Worry is harassing turmoil as the worry of business, the worry of politics, the worry of a householder. We generally say: "The cares and worries of life here are formidable."

Worry kills a man. It destroys his joys of life. It is a canker or cancer that slowly eats away a man. It wears you out.

Hard work with a peaceful, harmonious mind will never kill anyone. It builds up the system and prolongs life but worry kills a man. It shortens life.

Do not worry over what is past. Forget it. No one has yet been able to claim any good thing through worry.

Do not worry about things which are likely to happen, so often they don't. Sufficient for the day is the evil thereof.

The surest antidote or penicillin injection for worry is to keep busy. Do always something useful.

Do your best and leave the rest to God. Do not worry. You are indeed blessed now.

DESTROY EVIL VRITTIS

1. Lust (Kama)	Brahmacharya, Mumukshutva.
2. Anger (Krodha)	Love, Kshama (forgiveness), mercy (Daya), Maitri (friendship), Santi, Dhriti (patience), Ahimsa.
3. Pride (Mada)	Humility (Namrata or Vinaya).
4. Greed (Lobha)	Honesty, disinterestedness, generosity, Santosha (contentment), Aparigraha (non-covetousness).
5. Jealousy (Irshya)	Nobility (Udarata), magnanimity, Mudita (complacency).
6. Moha (delusion)	Viveka (discrimination).
7. Dambha (vanity, hypocrisy)	Simplicity.
8. Darpa (arrogance)	Politeness, Hri (modesty).
9. Paisunam, (cunningness, crookedness)	Arjava Straightforwardness.

10. Parushyam (harshness)	Mardavam (mildness).
11. Raga (attachment)	Vairagya.
12. Insincerity (Asraddha)	Sraddha (faith).
13. Fickleness (Chanchalatvam)	Determination, Nischaya Vritti (Adhyavasya).

LIST OF VICES TO BE ERADICATED

(Take a copy of this and hang it in a prominent place in your house.)

Ambition
Arrogance
Avaricious nature
Backbiting
Conceit

Crooked-mindedness
Cruelty
Desire
Dullness
Egoism
Envy
Godlessness
Hatred
Jealousy
Lust
Merciless nature
Obstinacy
Scandal-mongering
Tale-bearing
Unchaste look

Anger
Attachment
Avenging nature
Censure and criticism
Committing cruel and atrocious deeds
Deceitful nature
Depression
Double-dealing
Eating more than enough and very often
Evil thoughts and habits
Harsh words
Hypocrisy
Laziness
Mischief-mongering
Miserliness
Pride
Selfishness
Telling lies

MINOR VICES

Arguing nature
Belittling
Brooding over nothing
Chicanery
Delusion
Diplomacy

Agitation of mind
Bragging
Building castles in the air
Degrading others
Despondency
Drinking habit

Emotions
Fault finding
Gambling
Greed
Humbug
Impertinence
Indolence
Interrupting nature
Killing ants and other small insects
Mental Weakness
Mocking at others
Novel-reading
Obscurity
Pedantry
Pettiness
Planning and scheming
Protesting nature
Rashness
Retaliating
Roguery
Self-conceit
Slander
Sleeping during day time
Smoking habit
Stubborn nature
Talking too much
Unnecessary arguments
Unsteady mind
Vanity
Wasting time for nothing and in useless company
Enmity
Fighting nature
Gloomy appearance
Haughtiness
Ill-treating the menials
Improper actions
Injustice
Irritability
Looking into others' faults
Maliciousness
Misbehaving
Negligence
Obloquy
Ostentatious nature
Persecution
Pilfering
Procrastinating
Quarrelling nature
Restlessness
Revenging nature
Rudeness
Showing one's skill and power before others
Slothful nature
Stagnation
Talking ill of others
To have a honied tongue and a gall-heart
Using obscene words
Wandering nature
Worrying habit

Once again open the index fingers by raising the index fingers up, while keeping the rest of the fingers level, and draw in the Heavenly Chi through the index fingers.

Bring the index fingers back to neutral again and relax your hands.

Pinky Fingers:

Stretch the pinky fingers out and down toward the earth, keeping the rest of the fingers level. Draw in earth energy through the pinky fingers and circulate it through the body.



***Fig. 8.25** Draw Earth Energy through the Pinky Fingers.*

Bring the pinky fingers back to neutral and relax your hands.

Once again open the index fingers by raising the index fingers up, while keeping the rest of the fingers level. Draw in the Heavenly Chi through the index fingers. Bring the index fingers back to neutral again and relax your hands.

Middle Fingers:

Stretch the middle fingers out and down toward the earth, keeping the rest of the fingers level. Draw in earth energy through the middle fingers and circulate it through the body.

Bring the middle fingers back to neutral and relax your hands.

Once again open the index fingers by raising the index fingers up, while keeping the rest of the fingers level. Draw in the Heavenly Chi through the index fingers.

Bring the index fingers back to neutral again and relax your hands.



***Fig. 8.26** Draw Earth Energy through the Middle Fingers.*

TWENTY IMPORTANT SPIRITUAL INSTRUCTIONS

By

H.H. Sri Swami Sivanandaji Maharaj

1. Get up at 4 a.m. daily. This is Brahmamuhurta which is extremely favourable for meditation on God.

2. ASANA: Sit on Padma, Siddha or Sukha Asana for Japa and meditation for half an hour, facing the east or the north. Increase the period gradually to three hours. Do Sirshasana and Sarvangasana for keeping up Brahmacharya and health. Take light physical exercises as walking, etc., regularly. Do twenty Pranayamas.

3. JAPA: Repeat any Mantra as pure Om or Om Namo Narayanaya, Om Namah Sivaya, Om Namo Bhagavate Vasudevaya, Om Saravanabhavaya Namah, Sita Ram, Sri Ram, Hari Om, or Gayatri, according to your taste or inclination, from 108 to 21,600 times daily.

4. DIETETIC DISCIPLINE: Take Sattvic food, Suddha Ahara. Give up chillies, tamarind, garlic, onion, sour articles, oil, mustard, asafoetida. Observe moderation in diet (Mitahara). Do not overload the stomach. Give up those things which the mind likes best for a fortnight in a year. Eat simple food. Milk and fruits help concentration. Take food as medicine to keep the life going. Eating for enjoyment is sin. Give up salt and sugar for a month. You must be able to live on rice, Dhal and bread without any chutni. Do not ask for extra salt for Dhal and sugar for tea, coffee or milk.

5. Have a separate meditation-room under lock and key.

6. CHARITY: Do charity regularly, every month, or even daily according to your means, say six paise per rupee.

7. SVADHYAYA: Study systematically the Gita, the Ramayana, the Bhagavata, Sri Vishnu-Sahasranama, Lalita-Sahasranama, Aditya Hridaya, Upanishads or Yoga Vasishtha, the Bible, Zend Avesta, the Koran, the Tripitakas, the Granth Sahib, etc., from half an hour to one hour daily and have Suddha Vichara.

8. BRAHMACHARYA: Preserve the vital force (Veerya) very, very carefully. Veerya is God in motion or manifestation—Vibhuti. Veerya is all power. Veerya is all money. Veerya is the essence of life, thought and intelligence.

9. PRAYER SLOKAS: Get by heart some prayer-Slokas, Stotras and repeat them as soon as you sit in the Asana before starting Japa or meditation. This will elevate the mind quickly.

10. SATSANGA: Have Satsanga. Give up bad company, smoking, meat and alcoholic liquors entirely. Do not develop any evil habits.

11. FAST ON EKADASI: Fast on Ekadasi or live on milk and fruits only.

12. JAPA MAALA: Have Japa Maala (rosary) round your neck or in your pocket or underneath your pillow at night.

13. MOUNA: Observe Mouna (vow of silence) for a couple of hours daily.

14. SPEAK THE TRUTH: Speak the truth at all cost. Speak a little. Speak sweetly.

15. Reduce your wants. If you have four shirts, reduce the number to three or two. Lead a happy, contented life. Avoid unnecessary worry. Have plain living and high thinking.

16. NEVER HURT ANYBODY: Never hurt anybody (Ahimsa Paramo Dharmah). Control anger by love, Kshama (forgiveness) and Daya (compassion).

17. DO NOT DEPEND UPON SERVANTS: Do not depend upon servants. Self-reliance is the highest of all virtues.

18. SELF-ANALYSIS: Think of the mistakes you have committed during the course of the day, just before retiring to bed (self-analysis). Keep daily diary and self-correction register. Do not brood over past mistakes.

19. FULFIL DUTIES: Remember that death is awaiting you at every moment. Never fail to fulfil your duties. Have pure conduct (Sadachara).

20. SURRENDER TO GOD: Think of God as soon as you wake up and just before you go to sleep. Surrender yourself completely to God (Saranagati).

Om Santih Santih Santih!

This is the essence of all spiritual Sadhanas.
This will lead you to Moksha.
All these Niyamas or spiritual canons must be rigidly observed. You must not give leniency to the mind.

About This Book:

This volume would rank foremost among the works of H.H. Sri Swami Sivanandaji Maharaj. In this he has presented to the men and women of the present-day world a theme that is dearest to his heart and that would transform men into gods and nations into paradise on earth.

The keynote of Sri Swamiji's teachings is righteousness in thought, word and deed, the cultivation of a sterling character, and the practice of the Religion of the Heart. In this respect, he is like Lord Buddha. But, like Lord Krishna, Sri Swamiji explicitly declares that righteousness is a means to an end, i.e., Jnana or Self-knowledge. This has a direct appeal to the soul of man.

Every one of Swamiji's books has uniformly stressed this aspect of Sadhana—Cultivation of Virtues and Eradication of Vices. Whenever Swamiji has spoken, at mass meetings or individual conversations, he has thundered: "It is only through righteousness that you can attain the Supreme Reality."

In this volume Sri Swamiji Maharaj has given us a sweet garland of all the virtues that should adorn every earnest Sadhaka; and we offer it to the readers with our sincere prayer that it might ennoble them and divinise them, make them better and more successful men and women who would make the world they live in a vast home of peace and brotherhood.

ISBN 81-7052-059-2

ES64 ₹ 125/-

THE DIVINE LIFE SOCIETY PUBLICATION



MUSHROOMING WITHOUT FEAR

The Beginner's Guide to Collecting Safe and Delicious Mushrooms



ALEXANDER SCHWAB

Table of Contents

Title Page
Copyright Page

Mushrooming Without Fear

It’s Safe, Easy and Fun
How to use this guide

- The size of mushrooms

What is a Mushroom?

- Gills
- Tubes
- Spines
- Ridges

How to Pick Mushrooms

- Rules:

Positively Identifying Mushrooms

Mushrooms With Tubes

- Cep or King Bolete
- Red Cracked Bolete
- Hen of the Woods
- Larch Bolete
- Bay Bolete
- Birch Bolete

Mushrooms With Ridges

- Chanterelle
- Trumpet Chanterelle

Mushrooms With Spines

- Hedgehog Fungus

Mavericks

- Common Puffball
- Horn of Plenty
- Cauliflower Mushroom

Mushrooming Miscellany

The Mushrooming Regions

- Eastern North America
- The Pacific Northwest
- California

Trees and Mushrooms

- Always remember

Handling, Storage and Cooking

- Handling
- Storage
- Cooking
- Basic preparation of dried mushrooms

Beyond the Stove

It is easy to do without silver and gold
and your toga and cloak
but it is difficult to give up mushrooms.

Martial, Roman poet (AD 40 - 102)
Epigrams, Book 13, Number 48

Crane's Beak and Swallow the Saliva:

Form the "Crane's Beak" with both hands by bringing all the fingertips together with the thumbs inside. **Inhale** and **contract the sexual organs**.

Move your tongue and suck the mouth to **activate the saliva**. Divide it into three parts, tighten the neck and gulp down the **first part** to the center of the **navel**; force the **second** mouthful of nectar down to the **left side of the navel** and the **third** to the **right side of the navel**. Raise the forearms up to shoulder height with the fingers pointing down. Slowly open the palms and begin to lower the arms to the sides, until the palms are facing each other before the starting position.



Fig. 8.27 *Form the 'Crane's Beak'.*



Fig. 8.28 *Raise Forearms to Shoulders.*



Fig. 8.29 *Lower Arms to the Sides.*



Fig. 8.30
Palms facing each other to cover the Navel.

Conclusion:

Bring awareness to the navel. Notice the quality and intensity of the energy generated and **collect your energy at the navel**. Men place hands over the navel with the right hand on top; women vice versa. Rest.

Summary:

Practice Part I daily for one or two weeks until you can do it well. Then you can proceed to learning Part II.

Mushrooming Without Fear

The Beginner's Guide to Collecting Safe and Delicious Mushrooms

Alexander Schwab

Consultants Monika Lehmann and Roy Mantle

Skyhorse Publishing

Text and photographs © by Alexander Schwab, 2006

First published by Merwin Unwin Books Ltd (Ludlow, UK) in 2006

All Rights Reserved. No part of this book may be reproduced in any manner without the express written consent of the publisher, except in the case of brief excerpts in critical reviews or articles. All inquiries should be addressed to Skyhorse Publishing, 555 Eighth Avenue, Suite 903, New York, NY 10018.

www.skyhorsepublishing.com

Library of Congress Cataloging-in-Publication Data is available on file.

ISBN-10: 1-60239-160-2
ISBN-13: 978-1-60239-160-4

10987654321

Picture credits:

Frank Moser: cep page 40, middle picture cep page 42, orange birch bolete, page 68
Thomas Beer: larch boletes bottom right and middle right, page 57
Niels Sloth (www.biopix.dk): pestle shaped puffball, page 90

Every effort has been made to insure the accuracy of the information in this book. In no circumstances can the publisher or the author accept any liability for any loss, injury or damage of any kind resulting from an error in or omission from the information contained in this book.

Printed and bound in India

Mushrooming Without Fear

It's Safe, Easy and Fun

Follow this guide and you can enjoy picking and eating delicious mushrooms uninhibited by fear and doubt. In order to enjoy a homemade gourmet mushroom dinner you do not really need to know what *basidia or hyphae* are. Nor do you need to know how to identify dozens of tasteless or poisonous mushrooms which you wouldn't want to eat in the first place.

Even advanced mushroom pickers face many uncertainties.
The same mushroom looks different in the various stages of its development and different again when conditions are, for example, very wet or very dry. There are no end of edible mushrooms. Twenty-odd of these are of serious culinary interest, of which about a dozen are outstanding. Quality, not quantity, is what you are after. By good luck, the quality mushrooms are also among the most easily identifiable mushrooms and some of these are among the most frequently encountered.

Mushrooms may look beautiful, but that does not mean that they are edible.

You wouldn't buy a soggy, wormy, half rotten mushroom in the supermarket. So why pick it in the wood? Quality is what the discerning mushroom hunter is after.

With the safe method explained in this book, you will be able to identify the best mushrooms positively by their unique and unmistakable features.

Your part in the safe method is:

1. As a beginner, leave alone most mushrooms you pass
2. Look closely at what you see before you, not at what you wish was there
3. Stick to the rules and tick off every stage in the mushroom identification process

The fly agaric is the most well-known species. For gnomes, pixies, fairies and other such folk it is safe. For us common mortals it is poisonous! Do not believe any old wives' tales regarding the identification of poisonous mushrooms. Stick to the safe method in order to identify the best edible mushrooms.

Why is the safe method safe? If you follow the safe method to the letter, you'll automatically steer clear of deadly mushrooms or mushrooms causing permanent damage.

In the families of mushrooms presented and recommended here, there is not one deadly mushroom.

This is the reason why the field mushroom is not in this guide.
The field mushroom belongs to the group of mushrooms with gills, and especially when young, the feld mushroom can be confused with some deadly species. The safe method therefore asks you to ignore all mushrooms with gills because it is within the gilled group that all the seriously poisonous and deadly mushrooms are found. If you're absolutely sure about the field mushroom, then pick it by all means. But unless you are 100 percent certain, hunt for field mushrooms and other species with gills in the supermarket only.

Within the recommended groups you will find some slightly poisonous mushrooms but these happen to be so bitter, hot-tasting or strong-smelling that nobody sane would eat them anyway should they find their way into a meal (which they won't if you follow the safe method).
Poisonous mushrooms in the recommended groups cause gastrointestinal trouble of varying intensity. In other words: tummy ache.
Nevertheless there is absolutely no reason for complacency: a harmless tummy ache together with an existing medical condition can be dangerous.

Now, enough with the warnings. With this guide in hand, you are sure to have a safe and memorable experience collecting delicious mushrooms. Good luck and have fun!

How to use this guide

1. Read the entire book twice in order to understand the approach
2. Study the “Gills,” “Tubes,” “Spines” and “Ridges” sections until you’re confident you can correctly distinguish these features; then you’re ready for a foray
3. Double-check at home by going through the full identification process step-by-step

The size of mushrooms

The size of mushrooms varies enormously, so any measurements given in this book are only a rough average. Don’t be put off if you see an exception. The size can vary disproportionately due to weather conditions: if it is very dry, the mushrooms will be smaller than average. The other great variable is the growing medium. Don’t be surprised if near a building site, for example, you find surprisingly large mushrooms growing out of sawdust, or where woodchips have been laid at the edges of paths.

Part II
Opening the Bridge and Regulator Channels

Theory

Chi flows through your body along numerous channels or meridians. The channels are divided into two major groups: the **extraordinary** or special channels and the **ordinary** channels. After your mother's egg and your father's sperm joined together to form a single cell, that cell began to divide. The extraordinary channels were the first energy channels formed as a result of that early cell division.

There are **Eight Extraordinary Channels:**

Governor Channel
Functional or Conception Channel
Thrusting Channel
Belt Channel
Yang Regulator Channel
Yin Regulator Channel
Yang Bridge Channel
Yin Bridge Channel

Later, as your fetus developed, your Original Chi flowed through the eight extraordinary channels to help create your internal organs and their energy channels. These twelve "ordinary channels" are divided into yin and yang. The yin Channels are connected to the solid organs, and the yang channels are connected to the hollow organs.

The **Twelve Ordinary Channels:**

Lung (Yin) Channel
Large Intestine (Yang) Channel
Stomach (Yang) Channel
Spleen (Yin) Channel
Heart (Yin) Channel
Small Intestine (Yang) Channel
Bladder (Yang) Channel
Kidneys (Yin) Channel
Pericardium (Yin) Channel
Triple Warmer (Yang) Channel
Gall Bladder (Yang) Channel
Liver (Yin) Channel

What is a Mushroom?

A mushroom is a highly complex organism. Here are the essentials:



Fruitbody

The technical term for what is colloquially called the "mushroom" is the "fruitbody." Mycologically speaking, the real mushroom is the mycelium which is a fine structure of filaments on or in the forest soil. What we see as mushrooms (the fruitbody) are like the apples on an apple tree.

Cap

The caps of mushrooms have many different forms but what we're interested in is what is under the cap. Under the cap you'll find either . . .

Gills
Tubes
Spines
Ridges

Gills, tubes, spines and ridges produce, contain and release the spores. Wind and rain disperse the spores. Given the right conditions new mycelia and mushrooms form from the spores.

Stalk

Mycelium

The mycelium

This is a close-up of about 4 mm of the mycelium above, as seen under a microscope. When conditions are right, the mycelium forms a fruitbody, pushing the mushroom up in order to disperse the spores or to wait for you to come along and pick it.

Rule number 1

Never, never take a mushroom with gills!!!

Gills

Identifying gills is the first and most important step. You must be sure that you're able to identify gills. Caps of gilled mushrooms come in many different shapes. Gills are the radiating blades on the underside of the cap. They fan out in a distinctly regular way. Gills have precise forms and come in many colors. Some of them are brittle some of them are soft. They can be rubbed off or separated from the underside of the cap quite easily. Gills are always attached to the stem or to the cap in a uniform way.

In perfect conditions the distinctly regular way in which the gills fan out is clearly visible.



Weather-beaten or old gills might be damaged or broken but on closer inspection their regularity will become apparent. Damage or no damage: either way they look as if drawn with a ruler.





In their regular way, gills differ in spacing and formation.
For example:

Gills can fork once or more.



Gills can be mixed: long and short gills.



Gills can be crowded.

Gills can be distant.



Gills are always uniformly attached to the cap or the stem. They start radiating from the same height along the stem or the same line around the cap.

Rule number 2

> **Only take mushrooms with tubes, spines and ridges and the mavericks portrayed in this book**

These twelve organs serve to extract energy from the food and water we ingest and the air that we breathe to create energy through the metabolic processes of respiration, circulation, digestion, elimination and reproduction. This energy is called PostNatal Chi, as it comes in after we are born. Thus the extraordinary channels serve as the link between our Original or Prenatal Chi which came from our mother and father, and our Postnatal Chi which comes from our food and air as a result of metabolism.

General Functions of the Eight Extraordinary Channels

They serve as reservoirs of Chi.

About two thousand years ago, one of the great texts of Chinese medicine, the Nan Ching was written. This classical text describes the twelve ordinary channels as rivers and the eight extraordinary channels as reservoirs of Chi. When the ordinary channels become low in energy, they can draw from the reservoirs of energy in the extraordinary channels. On the other hand, if the ordinary channels become too full, the excess can be taken up by the extraordinary channels. In this way the extraordinary channels help us to maintain a balance in our energy body.

They store and circulate Ching Chi.

The extraordinary channels all draw their energy from the kidneys, which are the storehouse of Ching Chi (essence or sexual energy) in the body. Thus the extraordinary channels circulate the Ching Chi around the body, particularly to the skin and hair, and to the five ancestral organs: the brain and spinal cord, the bone marrow, the blood, the uterus and the liver and gall bladder.

They circulate Defensive Chi to protect the body.

The Chi that protects the body against invasion by external pathogens is called Defensive Chi or Wei Chi. The extraordinary channels circulate Defensive Chi over the back, abdomen and thorax. These functions are performed by the Governor Channel, the Functional Channel and the Thrusting Channels, respectively.

They regulate our life cycles.

In the first chapter of the Yellow Emperor's Classic of Internal Medicine (Huang Di Nei Ching Su Wen), another of the classical texts of Chinese medicine, the life changes of women and men are described in 7 and 8 year cycles respectively. The Functional Channel and the Thrusting Channel govern these cycles.

Tubes
Tubes are fine and tightly packed on the underside of the cap. The openings at the ends of the tubes are called pores.



Spines
Spines hang like stalactites from the cap.



Ridges

Ridges are cross-veined, irregular and don't form a distinct pattern. Ridges are not attached to the cap: they are part of the cap.





Remember Rule number 1

Never, never take a mushroom with gills!!!

Tubes

This is the underside of a cap with tubes. The tubes are fine and tightly packed and the openings at the end which are seen here are called pores. Tubes can be removed easily from the cap.



Pores form a regular pattern resembling a sponge.



This cross-section shows the tubes and the pores.


Tubes
Pores

Spines

Spines hang like stalactites from the cap.





Ridges

Ridges are on the underside of the cap and are part of it. They are not just attached to the cap or stem: they're part of them, which is why you can't rub them off or pull them off easily.



Ridges are cross-veined, irregular and they don't form a set, uniform pattern.



They are not attached to the stem in a distinct and regular way, as gills are: they are part of the stem.



The ridges are part of the stem. There is no distinct pattern in the way they grow out of the stem. Some ridges begin further up, some further down the stem. There is no regularity.



In contrast to gills and tubes, the section of a mushroom with ridges shows no typical features. Because of the irregular nature of ridges each section will look different whereas with tubes and gills you will find the same features each time.



How to Pick Mushrooms

Rule number 1 says not to take anything with gills. This also means you do not touch or cut every mushroom you spot in order to check for gills.

In nine out of ten cases you can see whether a mushroom has gills or not without even touching it. Looking under the cap by kneeling down provides good exercise.

Eight Extraordinary Channels and Chi Kung

There are few texts available today that describe the purpose and function of the eight extraordinary channels and their place in Chi Kung practice. To make matters more confusing, the extraordinary channels and points used in Chi Kung are often quite different from those used in acupuncture, even though they may bear the same names.

Most acupuncturists pay little attention to the eight extraordinary channels in diagnosis and treatment with the exception of some modern Japanese researchers. By contrast, the extraordinary channels have been of special importance to Taoists and Chi Kung practitioners for thousands of years. Taoists see the extraordinary channels as the foundation of our bodily energy, as the bridge between our Original or Prenatal Chi and our Postnatal Chi; these channels affect us on the deepest level of our basic constitutional energy.

Therefore, Taoists focus on opening up the flow of energy through the eight extraordinary channels as a prerequisite for opening the energy flow in the twelve ordinary channels. In the Universal Tao system, you first open up the Governor Channel and the Functional Channel in the Microcosmic Orbit Meditation. The second pair: the Thrusting Channels and the Belt Channels are opened in the Fusion of the Five Elements II Meditation. The last four channels, the Yin and Yang Bridge Channels and the Yin and Yang Regulator Channels are opened in the third level of Fusion of the Five Elements Meditation. After opening all eight channels, in the next level of Taoist inner alchemical meditation called the Lesser Enlightenment of Kan and Li, the twelve ordinary channels are then opened.



If you really can't see what's underneath a cap, break off just a little to see what's there. If you want to be absolutely safe, you could use surgical gloves or a paper napkin which you discard later.

If you have established that you have, say, a mushroom with tubes and it is in reasonable condition and it tallies with the field identification card—then, and only then, should you pick it.

Rules:

Rule number 1

Never, never take a mushroom with gills!!!

This is our life insurance.

Rule number 2

Only take mushrooms with tubes, spines and ridges and the mavericks portrayed in this book

This means thoroughly understanding the information on pages 18-27 of this book.

Rule number 3

Only eat mushrooms which you have clearly identified with ALL the positive ID marks

The mushrooms you take must be a certain size in order to show all the identification marks. In their baby stage, so to speak, some deadly and poisonous mushrooms are almost indistinguishable from harmless species.

Rule number 4

If a mushroom smells rotten, it is rotten and if it feels soggy, it is soggy

There are a surprising number of people who believe that somehow a half decomposed, soggy, smelly mushroom will improve on the way home. It never does. Only take mushrooms which are in mint condition, that is, the flesh is firm and there are hardly any worms.

Rule number 5

Never, never eat wild mushrooms raw

The reasons for this are manifold but, to state the obvious, some areas in some woods are dog-ridden.

Rule number 6

Look before you cut

Always cut mushrooms, do not pull them out. You don't chop down an apple tree to pick the apples. Cut just above the ground and cover the remaining stem with a little mud or dead leaves. Whether this is of any conservational value is disputed but it does no harm. My recommendation is to cut and cover.

Picked mushrooms want to breathe. Do not suffocate them in plastic bags. Use a wicker or rattan basket or a linen bag. If possible use a proper mushroom knife with an integrated brush for cleaning. As the first cleaning of the mushroom should be done in the woods, the brush is very useful. However, any knife will do, as long as the blade can be folded into the knife handle, for safety. Common sense is your best adviser but be aware of any likelihood of ticks where you go mushrooming.

You might want a stick. It can be any kind of stick and you will find it helpful on the slopes. But you will also find it useful for pushing aside the grass and ferns, affording you a better look at the ground. Different mushrooms can be put together in your wicker basket. Better still, have a few paper bags in the basket; one paper bag (breathable) for each species. Putting, say, all trumpet chanterelles in the same bag helps you to spot the odd one out which you have inadvertently cut while not fully concentrating (see page 78).



Rule number 7

Mushrooms want to breathe: Do not suffocate them in plastic bags

Either in the woods or at home.

Special Functions of the Bridge and Regulator Channels

The Bridge and Regulator Channels have no points of their own. They borrow points from the other 'ordinary' channels linking together and controlling the flow through all the separate channels of the body. The Bridge and Regulator Channels travel along the same paths. There is no 'real' difference between them. Both of them connect or 'bridge' and 'regulate' the flow of Chi in the body's meridians.


GB-16
GB-15
GB-14
ST-2
ST-4
CV-23
LI-16
CV-22
L-1
ST-13
P-2
ST-16
LV-14
P-3
SP-16
SP-15
P-6
M-
SP-13
P-8
SP-10
SP-9
K-6
GB-41
SP-4

Fig. 8.31 *Yin Bridge and Regulator Channels*

Rule number 8

If in doubt, leave it

Now you’re ready for a foray.

Positively Identifying Mushrooms

Always remember

Rule number 1

Never, never take a mushroom with gills!!!

Rule number 2

Only take mushrooms with tubes, spines and ridges and the mavericks portrayed in this book

Rule number 3

Only eat mushrooms which you have clearly identified with ALL the positive ID marks

Rule number 4

If a mushroom smells rotten, it is rotten and if it feels soggy, it is soggy

Rule number 5

Never, never eat wild mushrooms raw

Rule number 6

Look before you cut

Rule number 7

Mushrooms want to breathe. Do not suffocate them in plastic bags

Rule number 8

If in doubt, leave it

Mushrooms With Tubes

Cep or King Bolete

Boletus edulis



The cep is the king of mushrooms. Some truffles are rarer, pricier and confined to relatively small areas in France and Southern Europe. The cep on the other hand reigns supreme everywhere. Ceps can be found in the same location year after year. They can disappear in certain areas for a couple of years only to return spectacularly in masses.

Some people gather only ceps which is understandable because of their beauty, taste and the thrill of finding them on the same spot time after time. Ceps vary greatly in general appearance, color and size. The size of the little fellow in the foreground of the picture above is about 2 inches in height whereas the giant is about 14 inches in height.

If conditions are right (starting off with a nice wet and humid spring or early summer) you should begin to look for ceps as early as the beginning of July. July and August are the months of the summer ceps.


White network


White network

These are summer ceps. However all ceps, summer or autumn, show a fine white network on the top of the stem right underneath the tubes.

A classic autumn cep, the king of mushrooms.



This is the key ID mark. The white net-pattern must be visible! All ceps, regardless of their time of emerging or stage of their development, have a fine white net-pattern at the top of their stalk.

This is what a cep ideally looks like when cut. Not a single worm has even looked at this beauty. The tubes and the flesh do not change color when cut or touched.



Cep tubes are off-white and firm when young. Later they turn yellow-olive and are less firm. In maturity the tubes are olive. Tubes of mature ceps are soft as a sponge and the tubes of old ones are soggy and often like those of the big fellow on page 38. This does not always mean that the inside of old ceps is rotten but more often than not, it is.



Cep stalks vary greatly in appearance. These specimens clearly show the white net-pattern all over the stalk.



Nevertheless, it is that top section of the stalk just below the cap where it matters: there the white network must be clearly visible.

Positive ID Checklist

Cep or King Bolete

☐ Tubes, pores and flesh do not change color when cut or bruised
☐ Tubes are off-white, cream, yellow-olive or olive
☐ Pores do not show any pink tinge
☐ White network on top of stem

☐ Cap matches the color bar range (above)



Avg. size across cap: 5 inches when mature



Appearance:	July to November in eastern North America; July and August in the southern Rockies; September to November in the Pacific Northwest; November to February in California
Habitat:	Conifers, oak, beech, and birch in eastern North America; Engelmann spruce in the Rockies; pines and spruce in the west
Tip:	Where you find one cep, you'll often find others in the vicinity.

Bridge Channels Yin and Yang Chiao Mo Function

The Bridge Channels, also called the Heel Vessels as they originate at the heels, regulate the amount of energy being used by all the other meridians in the body. They act like a bridge linking together the stored Chi in the body and the areas in need of Chi. Usually if any meridian uses more energy than it needs to flow properly, then other meridians become deficient as a result. Thus the Bridge Channels seek to assure that your energy is distributed in a balanced way. The Yin Bridge Channel runs along the front or yin side of the body, while the Yang Bridge Channel runs along the back of the body.


GB-17
GB-16
GB-20
M-HN-29
SI-13
GB-21
TW-15
SI-10
B-38
SI-9
LI-14
B-42
LI-11
B-47
TW-5
B-48
GB-29
GB-31
GB-34
B-62

Fig. 8.32 *Yang Bridge and Regulator Channels*

Red Cracked Bolete

Xerocomus chrysenteron



The red cracked bolete is probably the most common of all mushrooms with tubes. Its name describes its key identification feature perfectly.
As the mushroom matures, the cracks become more prominent. Some people love eating the red cracked bolete, others quite like it and there are a few who don’t take to it at all. The reason is its distinct fruity smell. In any case the red cracked bolete should only be picked as long as the pores are bright yellow and firm. The ideal size of the cap is about 1 inch across. Anything larger will make your dish all slimy.

Chrysenteron means ‘with golden-yellow flesh.’

The color of the cap ranges from a velvety dark brown to a light brown.



Stems vary in color from yellow, to yellow with a little red to yellow flushed with red. Note the bright yellow pores. The stem and the pores bruise blue. The intensity of the bruising varies. See picture opposite page, far left.



This specimen is too old for the kitchen. The pores have lost their brightness. The dull yellow signals that it’s no good anymore. When the pores are this color, the mushroom feels soft-to-soggy.



This is the perfect specimen. It has bright, firm golden-yellow pores and a nice firm cap about 1 inch across.



The caps are invariably cracked or lightly damaged. The typical identification mark of the red cracked bolete is the red showing through the cracks or the eaten-away patches.



When cut, the white-to-bright-yellow flesh turns blue. This can be very light blue and confined to certain patches.



Positive ID Checklist

Red Cracked Bolete

☐ Yellow tubes
☐ Yellow pores bruise blue (varying intensity)
☐ Flesh bruises blue (varying intensity)
☐ Cracks and damaged patches in cap show a distinct red tinge
☐ Cap matches the color bar (above)



Avg. size across cap: 2 inches when mature



Appearance:	June to October in eastern North America; fall in the Pacific Northwest; November to January in California
Habitat:	Associated with a wide variety of trees, including hardwoods (like oak) and conifers
Tip:	Take only small specimens (cap no wider than 1 inch across)

Hen of the Woods

Grifola frondosa



For thousands of years, the hen of the woods mushroom has been prized for its medicinal and culinary value in China and Japan. Maitake, the Japanese name for the hen of the woods, means "dancing mushroom" and one of the many interpretations of this name is that those who found a hen of the woods started to dance with joy because it was such a highly-prized mushroom.

It can be cultivated commercially. However, the wild hen of the woods mushroom you pick is infinitely superior because, firstly, you found it yourself; and secondly because it is as different from the farmed version as is a wild salmon to a farmed one. Finding a hen of the woods is indeed a reason to dance: a culinary event of the first order—and it's good for you too. There aren't that many things in life of which that can be said.

The hen of the woods is a cluster of fan-shaped overlapping caps.



On the underside of the cap (approx. 2 inches across) the tubes are at this stage visible to the naked eye. At this point the hen of the woods reaches gourmet status. Start picking now.



Actual size 2 inches

Disorders of the Bridge Channels

Excess Yang Energy

When yin energy is slowed down in the Bridge Channels, yang energy flows more rapidly. The excess yang can cause the following problems: insomnia, difficulty in closing the eyes, hypertension, stiff back and waist, inability to bend down, thigh tumors, bad colds, spontaneous sweating, headaches, painful eyes, paralysis of the arms and legs, vomiting of milk in infants, deafness, epilepsy, nose bleeding, swelling of the body, pain in the joints and head sweating.

Excess Yin Energy

When yang energy is slowed down in the Bridge Channels, yin energy moves more rapidly. The excess yin causes the following problems: sleepiness, difficulty in keeping the eyes open, hypotension, choking, painful urination, stomach rumbling, vomiting, diarrhea, difficult bowel movements, difficult labor and unconsciousness.

Regulator Channels

Yin and Yang Wei Mo Function

The Regulator Channels, also called the Linking Vessels, bind together all the meridians in the body. The Regulator Channels are also divided into yin and yang. The yin aspect, which runs along the front of the body, moves the yin energy and regulates the blood and inner parts of the body. It connects with all the yin channels: the Liver, Spleen, Kidney, Heart, Pericardium and Lung channels. If the yin aspect becomes imbalanced, the person may suffer from heart pains.

The yang aspect, which runs along the back side of the body, moves the yang energy, controls Defensive Chi, regulates resistance to external infections, and regulates the external parts of the body. It connects with all the yang channels: the Stomach, Bladder, Gall Bladder, Large Intestine, Triple Warmer & Small Intestine channels. If the yang aspect becomes out of balance, the person may catch colds and fevers easily.

By joining together the various channels, the Regulator Channels help to maintain a harmonious and cooperative interaction between the different channels.

The Regulator Channels in Taoist Yoga and Chi Kung are slightly different from those presented in acupuncture texts. The Chi Kung Regulator Channels include the yin and yang arm routes as well; some Taoist Yoga texts also refer to the arm routes as the Yin Yu and the Yang Yu. Acupuncture texts, by contrast, include only the leg, trunk and head routes. Many recent Chi Kung texts, unaware of these differences, depict illustrations from acupuncture texts alone, further adding to the confusion.

The fan-shaped caps with radial furrows are typical of the hen of the woods.



The tubes are clearly visible at this stage.



The cross-section shows a cauliflower-like structure with one central stem. The widest part of this particular specimen is approx. 12 inches.



On older specimens the tubes are larger in diameter but remain whitish. As the tubes grow larger they almost look like spines-but tubes they are.

The main colors of the hen of the woods range from off-white, gray-beige, gray-brown, gray-black, brown-black to light brown-black. The hen of the woods can grow up to 30 inches across.



The culinary value of the hen of the woods depends on its age. Size is not always an indicator of age. Some specimens grow very big, very fast. Despite their size these are still young specimens with

white, firm, fibrous flesh with a pleasant smell.
Older specimens have a distinct unpleasant smell and their caps get more and more flabby and the edges crumble.



Positive ID Checklist

Hen of the Woods

- ☐ Central stem
- ☐ Fan-shaped caps
- ☐ Caps with dark radial streaks
- ☐ White flesh does not change color when cut
- ☐ Cauliflower-structured cross-section
- ☐ White tubes
- ☐ Tubes do not change color when bruised
- ☐ Main cap color matches color bar (above)



Avg. size across cap: 12 inches, but can grow up to 30 inches



Appearance:	Common to ubiquitous in the fall in eastern North America
Habitat:	Almost exclusively at the base of large oak trees
Tip:	Grows on the same spot for many years

Larch Bolete

Suillus grevillei



It is as if pure gold has grown out of the ground-and where there is one nugget, there are others. It's very rare to find a single larch bolete.
More often than not larch boletes form a fairy ring. Always found near larch trees, this beautiful and delicious mushroom is covered with a yellow veil when young (above left). As the maturing mushroom grows, the veil breaks, leaving a transient ring on the stalk (above, center, and right). Always peel the cap of the larch bolete on the spot because otherwise it will make your basket and later your recipe all slimy. In wet conditions, the cap of the larch bolete is always slimy.

Grevillei refers to the Scottish mycologist R. K. Greville.

The veil still covers the cap in a 'baby' larch bolete.

The tubes must be clearly visible when you view a cross-section.



As the mushroom grows, the veil breaks. This picture (right) shows a larch bolete shortly after the breaking of the veil. The ring is transient (i.e., it often drops off) but even in the mature larch bolete you can always see a mark where the ring has been.


Tubes
Solid stem
Faint lilac coloring
Veil



Above the ring marks: net pattern (can be very faint). Below the ring marks: mature specimens show distinct reddish-rusty streaks on the yellow stem.

If a larch tree is nearby and you see several gold nuggets,they are bound to be larch boletes. The beautifully golden (and slimy when wet) caps are the key sign. Positive identification however requires ticking off all of the identification marks.






Positive ID Checklist

Larch Bolete

☐ Yellow tubes
☐ Solid stem
☐ Bright orange-yellow or golden-yellow sticky cap (slimy when wet).
☐ Flesh in cap flushes lilac (faint)
☐ Found near larch trees
☐ Other specimens found in the vicinity
☐ Young: tubes covered with a veil
☐ Intermediate stage: ring visible, faint net-pattern above ring zone
☐ Mature: ring zone still visible, faint network above ring zone
☐ Cap color matches cap color bar (above)

Disorders of the Regulator Channels

Excess Yang Energy

When yin energy is slowed down in the Regulator Channels, yang energy moves more rapidly. The excess yang can cause the following problems: swelling and pain in the joints, cold knees, paralysis of the arms and legs, painful back and sides, aching muscles, pain in the head, neck and edge of the eyebrows, fever, rashes, night sweating, tetanus, painful red eyes, colds and superficial fevers.

Excess Yin Energy

Similarly, when yang energy is slowed down in the Regulator Channels, yin energy moves more rapidly. The excess yin can cause the following problems: heart pain, diarrhea with stomach rumbling, difficulty swallowing, pain on both sides of the chest, diseases associated with cold and convulsions.

Summary

The Bridge and Regulator Channels link all of the yin and yang channels in the body together and regulate the flow of energy in these channels to maintain a state of energetic balance in the body. The channels used for meditation are somewhat different from the ones seen in Chinese medical text and acupuncture charts. This is because their purposes are different.

Chinese medicine aims to restore sick people to health. The points being treated must be superficial so that they can be activated by acupuncture needles.

Chi Kung and Taoist meditation aim to maintain health and to take one beyond mere physical health to spiritual immortality. The channels and points can be deep within the body, since the energy is guided by the mind or by postures and movements rather than by needles.

The movements used in Cosmic Chi Kung Part II to activate the Bridge and Regulator Channels are relatively simple. To completely master the Bridge and Regulator Channels, you must learn and practice the third level of Fusion of the Five Elements Meditation. Once you have done so, this part of Cosmic Chi Kung practice will be particularly powerful and balancing for you.



Avg. size across cap: 2.5 inches when mature



Appearance:	Across northern North America
Habitat:	Always near larch
Tip:	Always remove the cap skin

Bay Bolete

Xerocomus badius



The bay bolete is an excellent mushroom and by good luck, it is also very common. The main bay bolete months are September and October but it can be found as early as June. If you find one, there are bound to be others nearby.

Badius means ‘beautifully brown.’



Off-white pores:

This is the stage when the bay bolete is at its best. If the pores turn dirty yellow or green (see opposite page, top) the mushroom is past its culinary best. Take only specimens which have white or off-white pores.

Downwards-streaked stem:

The background color of the stalk is yellow-brown and is vertically frosted with brown streaks. The general appearance of the stalk ranges from light to dark brown but the vertical streaks will always be visible.

The off-white pores bruise green-blue.



The change in color of the pores to green-blue varies in intensity. Here it's quite extreme.



The young bay bolete has pale yellow tubes which then turn to yellow, olive-yellow and dirty olive-yellow as the mushroom matures. Whatever the stage, the tubes and the flesh bruise blue.



The intensity of the coloring varies but pores, tubes and flesh will always bruise green-blue.



This is what the ideal bay bolete looks like: off-white pores and tubes, white to white-yellow flesh, without a trace of a worm.



Not as good: but if you discard the soft pores and cut away the wormy parts, it will still be excellent.

The color of the cap will always be “bay” (chestnut brown) but bay has a considerable range.





When wet, the cap will be slightly slimy and this will intensify the color of the cap.



When dry, the color of the cap will be duller.



Positive ID Checklist

Bay Bolete

- ☐ Yellow tubes
- ☐ Off-white to gray pores (yellowish when aged) bruise green-blue
- ☐ Tubes and flesh bruise blue
- ☐ Stem is vertically frosted with brown streaks
- ☐ There is no net-pattern of any description on the stem
- ☐ Cap color matches cap color bar (above)



Avg. size across cap: 3.5 inches when mature



Appearance:	June to November in northeastern North America; west to Minnesota
Habitat:	Pine, spruce, and hemlock; often found growing on rotten logs
Tip:	Remove soft tubes

Birch Bolete

Leccinum scabrum



The birch bolete is the most common of the “rough stalks.” Rough stalks are mushrooms with a scaly stem. The birch bolete and its cousin, the orange birch bolete, are the most common rough stalks. Birch woods or groups of birch trees are the places to look for them.

The birch bolete and the orange birch bolete have numerous relatives, all of which have a black or brown scaly stalk. They are all edible but it is recommended to stick to the two species presented here.

Scabrum means “rough.”

Close-up of stalk, showing black scales.

Practice

Opening Movements

The Opening Movements for this second part of Cosmic Chi Kung are the same as for the first part. By now you should be familiar with these movements, so they will be described briefly. For a more detailed description, refer to Part I, Opening Movements.

Hands down at sides, palms facing each other. Commence Bone breathing. Be aware of the Tan Tien and absorb Cosmic Chi. Be aware of the Tan Tien and channeling the earth and galactic forces.

Washing the Bone Marrow

Raise arms to chest height - palms facing each other. Rotate arms until palms face down. Open the 'Tiger's Mouth' - Index finger up, thumb down.



Fig. 8.33 *Hands lower to the Sides. Lower the Mind to the Tan Tien.*



Fig. 8.34 *Open the 'Tiger's Mouth'.*

Activate and Beam to the Eye of the Hip

A. Large Intestine 4 - Eye of the Hand
B. Pericardium 9 - Tip of the Middle Finger
C. Small Intestine 3 - Knife Edge of the Hand


Tubes off-white
Pores off-white
Pores bruise brownish
Stalk covered with black scales



Pores and tubes change from off-white to a gray-white color as the mushroom matures. As a rule, you should only pick the birch bolete if it is firm and the pores are off-white.



Occasionally larger specimens are still nice and firm especially when conditions have been very dry.



These are the perfect birch boletes: a feast for the eyes and delicious to eat.



The orange birch bolete, *Leccinum versipelle,* is a beautiful mushroom. Its key identification mark is the stem covered with black scales, and of course the orange cap. When cut, the flesh turns faintly blue at the stalk base, displays traces of wine red and finally turns and stays gray. This color combination doesn't look especially appetizing but be assured the orange birch bolete is delicious.



Positive ID Checklist

Birch Bolete

☐ Pores off-white
☐ Pores bruise brownish
☐ Stalk with small black scales
☐ Cap color matches cap color bar (above)



Avg. size across cap: 3.5 inches when mature



Appearance:	July to October in eastern North America; winter in California
Habitat:	Birch; ornamental birch in California
Tip:	Discard stem and tubes of larger specimens

Always remember

Rule number 1

Never, never take a mushroom with gills!!!

Rule number 2

Only take mushrooms with tubes, spines, and ridges and the mavericks portrayed in this book

Rule number 3

Only eat mushrooms which you have clearly identified with ALL the positive ID marks

Rule number 4

If a mushroom smells rotten, it is rotten and if it feels soggy, it is soggy

Rule number 5

Never, never eat wild mushrooms raw

Rule number 6

Look before you cut

Rule number 7

Mushrooms want to breathe. Do not suffocate them in plastic bags

Rule number 8

If in doubt, leave it

Mushrooms With Ridges

Chanterelle

Cantharellus cibarius



The chanterelle is not surprisingly the most popular mushroom. It is delicious and very common. As it is imported throughout the year, the supermarket is a good place to familiarize yourself with the chanterelle. There is, however, nothing like the chanterelle you find yourself. Refrain from picking tiny chanterelles, that is, little yellow buttons which hardly show the identification marks. At some time you'll come across one lonely chanterelle standing there in the middle of nowhere for no particular reason at all. Leave it.

Cibarius means "belonging to food."

The classic color of the chanterelle is egg-yolk yellow which, however, can vary from light yellow or yellow-orange to yellow-ochre. The chanterelle does not change color when bruised. The entire mushroom is of the same color.



Young chanterelles have a flat cap with a slightly out-rolled margin. Do not pick any chanterelles smaller than 3 cm high.

The more mature the chanterelle, the more funnel-shaped it becomes.



The stalk is solid. The whitish to yellowish flesh does not change color when bruised or cut.

Whether young or mature, the chanterelle’s ridges must be clearly visible.



Some mature forms can look highly irregular but on closer inspection, the funnel shape will still be there.



Fig. 8.35 *Activate the Large Intestine, Pericardium and Small Intestine.*



Be aware of the Tan Tien and absorb the Heavenly Force Washing the Bone Marrow Crown to Soles.

Extend the arms forward - palms upward. Be aware of the Tan Tien and absorb the heavenly force. Rotate the arms until the palms face down. Raise the index fingers slightly. Absorb the Earth Chi.



Fig. 8.36
A. *Be aware of the Tan Tien and absorb the Heavenly Force.*

B. *Index Fingers up - be aware of the Tan Tien and absorb the Earth and Universal Force.*



Positive ID Checklist

Chanterelle

- ☐ Young specimen: Flat, wavy-edged cap, slightly out-rolled margin
- ☐ Mature specimen: Funnel-shaped
- ☐ Solid stem
- ☐ Found in groups on the ground, but not clustered at the base of trees; never on wood
- ☐ Ridges must be clearly visible
- ☐ Color matches cap color bar range (above)

Be Careful:

Don’t mistake the chanterelle for the Jack O‘Lantern, a mushroom that grows across eastern North America. The Jack O’Lantern is orange, glows in the dark, has gills, and is not edible.



Avg. size across cap: 2 inches when mature



Appearance:	July to October in eastern North America; July and August in the southern Rockies; fall in the Pacific Northwest; November to February in California
Habitat:	Under conifers (pine and spruce) and hardwoods (especially oak)
Tip:	Watch for mossy patches with little plant cover

Trumpet Chanterelle

Cantharellus tubaeformis



In comparison to the attractively-colored chanterelle, the trumpet chanterelle (also known as the autumn chanterelle, and winter chanterelle) looks modest. On closer inspection, however, it is just as beautiful as the chanterelle. The trumpet chanterelle pops up overnight so quickly that you could watch it grow. It is an endearing mushroom not least because it tends to appear in great numbers and is frost-resistant.

Tubaeformis means "trumpet-shaped."

A cluster of trumpet chanterelles.



Color and shape vary according to age and weather conditions. Each individual trumpet chanterelle has more than one color. The cap is brownish and has a hole in the center. The ridges and the stalk range from brown-yellow to gray-yellow to gray-lilac.



The jagged edges here are due to frost.

The advantage of having a paper bag for each species (see page 32) is seen here. You can spot the odd one out immediately.



The trumpet chanterelle has a hollow stem.



PositiveIDChecklist

Trumpet Chanterelle

- ☐ Found in groups
- ☐ Brownish, thin-fleshed, wavy-edged cap with hole in center
- ☐ Hollow stem
- ☐ Ridges
- ☐ Cap color matches color bar (above)



Avg. size across cap: 0.75-1 inch when mature



Appearance:	August to November in eastern North America; December to February in California
Habitat:	In conifer woods; on moss; on decayed, mossy logs
Tip:	Mossy banks are a favorite habitat

Always remember

Rule number 1

Never, never take a mushroom with gills!!!

Rule number 2

Only take mushrooms with tubes, spines, and ridges and the mavericks portrayed in this book

Rule number 3

Only eat mushrooms which you have clearly identified with ALL the positive ID marks

Rule number 4

If a mushroom smells rotten, it is rotten and if it feels soggy, it is soggy

Rule number 5

Never, never eat wild mushrooms raw

Rule number 6

Look before you cut

Rule number 7

Mushrooms want to breathe. Do not suffocate them in plastic bags

Rule number 8

If in doubt, leave it

Mushrooms With Spines

Hedgehog Fungus

Hydnum repandum



There are other mushrooms with spines but the only one of real culinary interest is the hedgehog fungus. The hedgehog fungus is a great delicacy. It grows on the ground but never on trees.

Repandum means “bent upwards” and refers to the way the cap often reveals its underside.

The spines are the key identification marks of the hedgehog fungus. The flesh is matte white and colors in places to a yellow-brown or rusty yellow.

Core Movements of Part II
Opening the Bridge and Regulator Channels

Activate the Throat Center - Right Side

Keeping the elbows sunk, raise the left palm first so that it is about 1 inch in front of the throat center (Conception Vessel 22), palm facing in. Then bring the right hand up so that it is about 1 inches in front of the left hand, palm facing in. Align the Lung 10 point in the middle of the eminence of the left hand with the **throat center. Feel the Chi go through the neck to C-7**. Continue smiling to the universe and connect to the back side of the universe. Hold for a 5 to 30 count and feel the throat center activated.



Fig. 8.37 *Connect to the Throat Center.*



Fig. 8.38
Feel the connection to the Universe at the Back.

Move both hands out slowly like you're pulling silk; when the feeling is diminished or the silk starts to break stop there. Be still and feel the beam connect the throat center to C-7 and the universe. Maintain the energy beam as you move in and out three times altogether ending with the hands as above.

Activate Mideyebrow Point - Right Side

Be aware of the Tan Tien and the universe. Keeping the Lung 10 points aligned, raise the hands up to the level of the mideyebrow point about one inch in front of the face. **Keep the points aligned and beam the energy passing through both hands into the mideyebrow point and through to the base of the skull.** Continue smiling and extending to make a connection to the back universe for a 5 to 30 count.

Use only 5% of the awareness to move both hands very slowly out, like you are **pulling silk**; continue to move out as long as your can feel the connection to the mideyebrow, C-7 points and the universe, maintaining the energy beam as you move.

Move in and out three times altogether, ending with the hands as above.



Some hedgehog fungi grow in a very irregular fashion, up to the size of two fists. Nevertheless, all hedgehog fungi have distinctive spines. The specimens here show the entire color range of the cap. No other mushroom with spines has these colors.



Take only specimens where the spines are clearly visible. The hedgehog fungi pictured here are the perfect size for the kitchen. The cap size is 2.5-4 inches across.

Positive ID Checklist

Hedgehog Fungus

- ☐ Spines
- ☐ Flesh matte white when freshly cut; flesh colors in places to yellow-brown or rusty yellow
- ☐ Cap margin wavy-edged
- ☐ Found on ground but not on trees
- ☐ Cap color matches color bar (above)



Avg. size across cap: 2.5 inches when mature



Appearance:	August to November in eastern North America; October to November in the Pacific Northwest; December to February in California
Habitat:	Common under oaks and mixed hardwoods in eastern North America; under conifers in the West and Pacific Northwest
Tip:	Avoid older specimens; they are slightly bitter

Always remember

Rule number 1

Never, never take a mushroom with gills!!!

Rule number 2

Only take mushrooms with tubes, spines, and ridges and the mavericks portrayed in this book

Rule number 3

Only eat mushrooms which you have clearly identified with ALL the positive ID marks

Rule number 4

If a mushroom smells rotten, it is rotten and if it feels soggy, it is soggy

Rule number 5

Never, never eat wild mushrooms raw

Rule number 6

Look before you cut

Rule number 7

Mushrooms want to breathe. Do not suffocate them in plastic bags

Rule number 8

If in doubt, leave it

Mavericks

Common Puffball

Lycoperdon perlatum



The common puffball is a curious little mushroom. One cluster of common puffballs might number merely four specimens; the next about forty. The common puffball is a welcome addition to any mix of mushrooms. Cooked on its own, it is not everyone’s cup of tea because of its distinct taste. The giant puffball is another matter and as good a reason as you’ll get for a dinner party.

Perlatum means “widely spread.”

The conical spines are visible to the naked eye and leave an unmistakeable net-pattern when rubbed off. Only pick specimens on which the white conical spines are clearly visible. The common puffball has no unpleasant smell.





These common puffballs are the perfect size (height 1-2 inches) and condition. When cut, the inside is all white and firm. Only when the flesh is uniformly white and firm, is the mushroom all right for use.





A variation of the common puffball is the pestle puffball. It too has spines but these are finer than those of the common puffball. It is pestle-shaped and it grows larger (height up to 8 inches) than the common puffball. It has no smell. If the flesh is uniformly white, and firm, it is good to eat.

The big brother of the common puffball is the giant puffball. Giant means it can grow to 3 feet in diameter. From a distance it looks all white but it can have a light yellow or yellow-brown tinge. The surface is smooth and feels rather like suede. The small specimen cut in two in the picture is about the size of a fist. When cut open, the flesh must be white and firm. Only then is the giant puffball edible- and delicious at that.


Mideyebrow to Jade Pillow

Pull and feel the connection of the string of Chi flow

Fig. 8.39 *Connect to the Mideyebrow, Jade Pillow and the Universe at the Back.*

Keeping the palms and thenars (Lung 10) aligned, move the hands back down to the position in front of the throat center. Keeping the forearms horizontal at shoulder height, separate the hands so that the Laogong point is aligned in front of Stomach 13, just **below the clavicle** on a vertical line above the nipple or mammillary line. The middle fingertips should almost be touching. **Beam energy from the Laogong points into ST-13 through the back on the side of the spine and connect to the universe**. You will be following this vertical line, which passes through the nipples, down the torso to the level of the navel, **stopping to focus and beam energy into key points along the way.** On each of these, focus your Yi on beaming energy into the organs inside each position. Stomach 13 is the location that activates the Heart and Lungs. Feel the change in your breathing as you activate the lungs.



Fig. 8.40 *Beam Energy into ST13.*



Positive ID Checklist

Common Puffball

☐ Conical spines
☐ Flesh must be firm and all-white
☐ Flesh undifferentiated, no thick rind or outline of mushroom visible in cross-section
☐ Net-patterned when spines are rubbed off
☐ Color Color white to off-white
☐ Found Found in groups
☐ No unpleasant smell

☐ Cap color matches cap color bar (above)

Be Careful:

Don’t mistake the Puffball for the Stinkhorn, which has a thick rind and black-and-white interior, or the Destroying Angel, which has gills and a differentiated interior. They are not edible.



Avg. size across cap: Size of a golf ball. Giant puffball 12 inches



Appearance:	July to November in eastern North America; fall in the Pacific Northwest; November to February in California
Habitat:	Seems to feel at home everywhere, but especially in grassy areas

Horn of Plenty

Craterellus cornucoploides



The horn of plenty is a real challenge to the mushroom forager.
Growing low on the forest-floor, it is so well-camouflaged that you can look at masses of them and not see any at all. If you spot one, there will be more: proceed with the utmost care because they are easily trampled. The horn of plenty is without a shadow of doubt one of the most delicious mushrooms in the world. But it has its price. Cleaning the horn of plenty can be quite a job but the reward is well worth the effort. Besides, when everybody joins the cleaning party, it is fun.

Cornucopioides refers to a cornucopia, or horn of plenty.

The horn of plenty is a funnel, the outer side of which looks smooth but in fact is slightly wrinkled. The color on the outer side is ash-gray, gray or pale gray with a bluish or lilac tint.

The inside of the funnel is brown, brown-gray, soot-gray or black. The surface is scaly or flaky and the top is out-rolled. In older specimens the top is wavy and split.



The horn of plenty seen from above in dry conditions.



The horn of plenty seen from above in wet conditions.



The funnel shape and the out-rolled top are typical.





This looks a rather battered group of horn of plenty. Some of the tops have already split. Don’t be put off-they still taste good.



Positive ID Checklist

Horn of Plenty

- ☐ Found in groups
- ☐ Funnel shaped
- ☐ Smooth-looking but slightly wrinkled outer surface
- ☐ Scaly inside surface
- ☐ Outer surface matches color bar above (top line)
- ☐ Inside surface matches color bar above (bottom line)



Avg. size across cap: 0.75-1 inch when mature



Appearance:	July to October in eastern North America; fall in the Pacific Northwest; January to March in California
Habitat:	Under beech in eastern North America; conifers in the Pacific Northwest; oak in California
Tip:	Always split them down the middle when cleaning and evict residents

Cauliflower Mushroom

Sparassis crispa



This is the mushroom of superlatives. For many people it is the very best of all. It may be a bit chewy but each bite releases a unique culinary sensation. If you fall for it, you'll be a dedicated cauliflower mushroom hunter forever. It resembles a cauliflower or a sponge.
Once you learn to recognise its spicy smell, you could identify the cauliflower mushroom blindfolded. And then there is the size: it can grow so big that people simply overlook it. This specimen weighed in at 22.5 1b.

Crispa means "frizzy."

Not all specimens grow to giant size. This one here is about the size of two fists. Its cauliflower or sponge-like appearance and the curved lobes are the key identification marks. There is nothing pointed or jagged in the cauliflower mushroom. The color ranges from creamy white to light brown. If it turns any browner than the specimen here, it has spoiled.




Curved lobes



Positive ID Checklist

Cauliflower Mushroom

☐ No gills, pores, tubes or spines

☐ No stem
☐ Looks like a cauliflower or sponge
☐ Lobes
☐ Matches range of color bar (above)



Avg. size across cap: 12 inches but can grow up to three feet



Appearance:	July to October in eastern North America; fall in the Pacific Northwest; December to February in California
Habitat:	On pine stumps; at the base of oaks in the Northeast
Tip:	Grows on the same spot for many years

Move the hands down the mammillary line to Stomach 16, about one inch above the nipple (in the space between the third and fourth ribs). Chi connects to the back and to the universe. Again, beam energy to energize and balance the **heart and middle of the lungs**. Move the hands down to Liver 14 (about 2 - 3 inches below the nipple in the space between the 6th and 7th ribs). Beam healing energy into the **liver and gall bladder.** Feel the Chi or the vibration of the palms activate the liver and feel the energy moving inside there.



Fig. 8.41 A. *Energize and balance the Lungs at ST16.*
B. *Energize and balance the Liver and Gallbladder at LV14.*

Move the hands down to **Spleen** 16 (just below the rib cage on the mammillary line). Beam healing energy into the **stomach, pancreas and spleen and the liver.** Picture the organs receiving the Chi from the cosmic and the universe.

Move the hands down to Spleen 15 (on the mammillary line to the level of the navel). Beam healing energy from your palms into the **small intestine and the Tan Tien.**



Fig. 8.42 A. *Energize the Stomach, Pancreas, Spleen and Liver at SP 16.*
B. *Energize the Tan Tien and Small Intestine at SP15.*

Mushrooming Miscellany

The Mushrooming Regions

Eastern North America

Throughout this book, “Eastern North America” means regions primarily north of Georgia.

The Pacific Northwest

The Pacific Northwest consists primarily of Washington and Oregon (and parts of Idaho).

California

Throughout the book, “California” refers to the Bay Area, two hours north and south of San Francisco. Mushrooms also grow in Los Angeles and San Diego, but these appear toward the end of the California season.

As you can see, the timing and proliferation of mushrooms varies regionally. A good mushroom crop also depends heavily on weather conditions over the whole year. So the dedicated mushroom hunter need not confine himself to a mere couple of months of pleasure.

Trees and Mushrooms

Beech, birch, oak, pine, spruce, aspen and larch are the most important trees in mushroom-hunting, trees which are easily identifiable by their leaves or bark or both. It is most useful to know these five species of tree because if, for example, you explore a new wood, they will guide you to the mushrooms.

Beech
Especially: horn of plenty

Oak
Especially: chanterelle

Birch
Especially: birch bolete

Pine
Especially: cauliflower mushroom

Larch
Especially: larch bolete



The larch is the only tree whose needles change color in autumn. You can’t miss it

Always remember

Rule number 1

Never, never take a mushroom with gills!!!

Rule number 2

Only take mushrooms with tubes, spines, and ridges and the mavericks portrayed in this book

Rule number 3

Only eat mushrooms which you have clearly identified with ALL the positive ID marks

Rule number 4

If a mushroom smells rotten, it is rotten and if it feels soggy, it is soggy

Rule number 5

Never, never eat wild mushrooms raw

Rule number 6

Look before you cut

Rule number 7

Mushrooms want to breathe. Do not suffocate them in plastic bags

Rule number 8

If in doubt, leave it

Hold the Chi Ball - Right Hand on Top

Turn the **left palm up** and align the Chi Ball with the Tan Tien. Turn the **right palm down** and align the eye of the hand (LI-4) with the navel. Feel your palms holding a Chi ball and feel a **Chi ball inside the Tan Tien**. Feel the Chi ball connect to the Cosmic Chi outside. Feel the north (usually left) and south (usually right) poles in the hands. Lower the right thumb to point toward the left Laogong point.



Fig. 8.43
Hold the 'Chi Ball' - One in the Tan Tien and the other in the hands - Right Hand over Left.

Yin/Yang Palms

Separate the hands and extend them out in front of the body at solar plexus level. The **left palm** is still pointing up and is yang drawing in the **Heavenly Force** through Laogong. The **right palm** is still facing down and is yin drawing in the **Earth Force** energy. **'Be Aware Tan Tien and Universe'**.



Fig. 8.44 *Connect to Heaven and Earth.*

Handling, Storage and Cooking

Handling

The first rough cleaning of the mushroom should be done in the woods. Once you're at home you verify your spoils against the positive ID check lists and then-and only then-can you start the fine-cleaning. Do not wet mushrooms to clean them. Brush or wipe them with a cloth. Part of the cleaning process is to check the quality. Evict residents, cut away soft and soggy tubes and cut the remaining mushroom into bite-size pieces.

Storage

Drying

Drying is the classic way to store mushrooms. This method actually intensifies the taste of the mushrooms and they'll keep for years if you follow the procedure correctly. Do not dry anything you wouldn't eat fresh. Drying does not improve the overall quality of your mushrooms. There are various methods of drying mushrooms but there is only one way which guarantees consistent high-quality results and that is the only one I recommend: a dehydrator. Whatever the make, the principle is the same: warm air circulation. The sliced mushrooms are placed on trays and then dried in the dehydrator. Dried mushrooms are best stored in any air-tight container or a sealed plastic bag and then kept in a dark place. Mix all the species except the cauliflower mushroom. The more species in the mix, the better the taste. The cauliflower mushroom should be dried and stored separately (see page 115). Do not dry chanterelles. All other mushrooms in this book are suitable for drying. Dried mushrooms should be crackle-dry and snap when broken.

Freezing

Freezing is the other method. Results improved enormously when home vacuum-packaging machines became available. I recommend only freezing vacuum-packed mushrooms. Frozen mushrooms retain their color, texture and taste.

Never thaw frozen mushrooms!

Put deep frozen mushrooms in sizzling butter or hot water. Like this they keep their texture.

- Mix all the species except the cauliflower mushroom. Again: the more species in a mix, the better.
- I recommend deep freezing some cep, and horn of plenty, separately. You might want to add just a few of them for a particular dish or use the cep for a tasty starter.

The cauliflower mushroom should always be frozen separately (see page 115).

The chanterelle must be cooked before deep freezing - all other mushrooms in this book can be frozen raw.

Drying or freezing?

Either way, use only perfectly fresh mushrooms. Drying mushrooms gives them that deep, strong mushroom taste. The frozen mushroom is more subtle, but the colors of frozen mushrooms are as bright as on the day they were picked and this adds considerably to the pleasure of eating. Dried and frozen mushrooms can be mixed to get the best of both worlds.

Cooking

Famous chefs win awards for stylish cuisine. Simplicity as a rule is not in their repertoire because no stars can be won by doing as little as possible. There are some really attractive mushroom books with some really attractive recipes but my advice is: do not try to emulate the recipes of the famous chefs - you'll never get there anyway. The place to enjoy grand cuisine is in the restaurant.

Do what you can do better than the professionals and do what they can't do and you're in for a feast. Besides, it's much less trouble, expense, and frustration to do it your own way rather than to follow recipes which pre-suppose the infrastructure of a five star establishment.

So where can't the professionals compete with you?

1. Freshness

This is not to say that restaurants use old mushrooms. They're just not as fresh as yours.

Chervil is a tasty and attractive herb for mushroom dishes.

Your mushrooms have the shorter way from the wood to your kitchen. As a rule the restaurants' mushrooms come from a market and some of those mushrooms on the market have traveled a long way, some of them half way round the world.

2. Sourcing

You know where your mushrooms came from, whereas the chef in the restaurant, as a rule, knows only that it is the type of mushroom he wants. You know the very wood from which you picked them, and this is important because, for example, a cep can taste differently from one wood to another.

3. Quality

You know exactly where your mushrooms come from, and therefore you know their quality. In other words, you can be sure, for example, that your mushrooms grew in a non-polluted habitat or a dog-free zone.

4. Freedom

You are at liberty to vary the mushrooms that go into dish and to change ingredients. In top restaurants, recipes are more precise and designed to he produced time and again. Your mushroom feas the other hand, can be unique each time.

5. Soul

There is a satisfaction in picking your own wild mushrooms and cooking them yourself that not an match.

Garnishing with finely chopped vegetables makes your mushroom dish a feast for the eyes.

Mushrooms are not garnish

The mushrooms in this book are of culinary value in their own right and should be treated accordingly. Treat a wild mushroom with the same culinary respect as you would a wild salmon.

Olive oil and mushrooms

Most contemporary mushroom cookbooks recommend olive oil for cooking mushrooms, but if you really want to draw out all the subtle flavors of your mushrooms and realize their full culinary potential, then olive oil is, generally, not a good idea. Unsalted butter brings out the best in your mushrooms.

Chives are the classic garnish for mushrooms.

Kills all known germs

There is a potential but very low risk of catching something nasty from a mushroom. To reduce that risk to zero, do not eat raw mushrooms and in the cooking process, increase the heat at one stage so that the dish either boils for a couple of seconds or sizzles in the butter. For that brief moment, turn the mushrooms in the pan so that they're exposed to the heat on all sides.

Curly or flat-leafed parsley underline the mushroom taste and add aesthetic appeal. Sprinkle on raw just before serving.



Conclude by turning the left palm over to face downward. **Draw in the 'Earth Force' through both palms.**

Fig. 8.45 *Draw the Earth Force through the Palms.*

Repeat the sequence with the left palm over the right.

Start by moving the right palm to the throat and then the left palm. Scan the body, as in the previous sequence, using both palms to connect to the points running down the front of the body. Remember to maintain a sense of the Chi flowing between the points in the front and their corresponding points in the back of the body.



Fig. 8.46 *Repeat the Practice on the Left Side. Push and Pull the silk at the Throat.*



Special Cases

Chanterelle

The chanterelle must not be dried because it goes chewy. It must not be frozen without prior cooking because it will turn bitter.

Horn of Plenty

Some people like it on its own. Others use it only as a spice to add to a mix of mushrooms. In order to find out what you like best, dry and freeze separately.

Cauliflower mushroom

The cauliflower mushroom is also very distinct in taste and perhaps best on its own. Dry or deep freeze separately.

Basic preparation for fresh or frozen mushrooms

There's a lot of flexibility in these basic preparations. The amounts stated can vary considerably and you'll still get an excellent result. And the beauty of it is that you can't overdo mushrooms. The key to culinary success is the quality of the mushrooms.

Serves 4

What you need
Essential:

5-8 cups fresh or frozen mushrooms
4 cups water
1 cup white wine
1 teaspoon salt
1 shallot or small onion, chopped
1 cup cream
¼ cup chives or parsley

Optional:

A mix of finely chopped vegetables, such as carrot, zucchini, and celery: approx. ½ cup
¼ cup chervil

What you do

1. Put water, white wine, salt, and shallot into a pan
2. Do not thaw frozen mushrooms. Add frozen or fresh mushrooms and bring to the boil
3. Reduce heat and simmer until approx ⅔ of liquid has evaporated
4. Add cream
5. Simmer again until approx. half the liquid has evaporated. Stir occasionally. If you feel there's too much liquid, simmer until it reduces still further. The less liquid, the more intense the taste and vice versa. Add water or cream to taste.
6. Add more salt and pepper to taste
7. You now have a wonderful mushroom sauce which you can serve with meat (chops, steak, etc.) or on its own with pasta or rice. Sprinkle with chives, parsley or chervil and the finely chopped vegetables

Basic preparation of dried mushrooms

Serves 4

What you need
Essential:

- 1-2 ounces dried mushrooms
- 4 cups lukewarm water
- 1 shallot or small onion, chopped
- ¾ cup dry white wine
- 1 teaspoon salt
- ¾ cup cream
- ¼ cup chives or parsley

Optional:

- A mix of finely chopped vegetables e.g. carrot, zucchini, and celery: approx. ½ cup
- ¼ cup chervil

What you do

1. Take the dried mushrooms and put in a bowl or pitcher. Add 4 cups of lukewarm water. Soak for 1½ hours (until the mushrooms float in brown liquid)
2. Put wine, shallot, salt, mushrooms and the brown liquid into a pan
3. Bring to the boil for 10 seconds Reduce heat and simmer until ⅔ of the liquid has evaporated
4. Add the cream

5. Simmer until approx. half the liquid has evaporated. Stir occasionally. If there is too much liquid, simmer until further reduced. The less liquid the more intense the flavor, and vice versa Add water or cream to taste
6. Add salt to taste
7. You now have a wonderful mushroom sauce which you can serve with meat (chops, steak, etc.) or on its own with pasta or rice. Sprinkle with chives, parsley, or chervil and the finely chopped vegetables

Beyond the Stove

No summer or winter woodland walk will ever be the same again once you become aware of the amazing universe of the forest floor, which in terms of color and life is a match for any coral reef. And the forest floor is right at your feet, so to speak, or at least not far from your door.

When in autumn you walk through a beech wood and marvel at the intensity and variety of the colors, think for a moment about those leaves.

There are about 2 tons of leaves to one acre of beech wood. After their job is done on the branches, they fall to the ground. If they did not decompose we would soon be swimming through a sea of leaves.

Likewise, unrotted fallen branches would in time pile up as insurmountable obstacles.

A leaf falls to the ground, inspiring on its way a poet who happens to be passing by: but on a more practical level, bacteria are the first organisms to get busy.

Shortly afterwards, it is fungi, algae and protozoans which play their part in the work of decomposition.

Soon, millions of organisms and little animals are at work on that single leaf. In due course the leaf is fully decomposed, its constituent parts recycled back into the forest soil, keeping it fertile by providing the essential substances for all the plants in the wood.

The vital role of mushrooms

Fungi are key players in maintaining tree growth and health. The reason the birch bolete is always found near birch trees, and the larch bolete always near larch trees, is that these pairs live in a symbiotic relationship. They need each other.

The mycelium of the birch bolete and the fine root-ends of the birch tree link up and exchange substances. There is a lot of chemistry going on, with a net result of mutual benefit. There are intricacies and complexities in all matters fungi and there are, so to speak, vast uncharted areas on the fungal map. However, even the most half-hearted mushroom-hunter will soon become aware of the all-encompassing interrelations in the wood. Mushrooming makes you see and appreciate the woodland differently.



Fig. 8.47 *Project to the Mideyebrow and Base of the Skull - connect to the Universe at the back. Then hold the Ball and repeat Finger Movements, as below.*

Continue with the left side, now pulling the silk at throat (C-7).



Fig. 8.48 *Beam Energy into each of the Organs like the last time.*

Closing Movements

The closing movements, crane's beak and finish are the same as before. Activate the Chi channels - balancing the organs.

Index Fingers



Fig. 8.49 *Open (up)*



Fig. 8.50 *Neutral*



Fig. 8.51 *Close (down)*











There is a practical point to these impressions which will help you in your mushrooming.

The similarity of patterning between the trunk of the birch tree and the stalk of the birch bolete is there for all to see. The similarity in color between the larch needles (once they change color in autumn) and the larch bolete seems obvious. These pointers can all act as nature's clues and reminders for the mushroom forager. But why is this so? Whatever the scientific answer, if indeed there is one, this similarity illustrates beautifully the interconnected nature or, if you prefer it, the mutual dependence, of life in the wood.

Perhaps even more intriguing is the similarity between the pine bark and the cauliflower mushroom, which grows near pine trees. It could be a coincidence or it could be a complex pattern at work. Either way, the cauliflower mushroom is utterly delicious - but if you mull over a conundrum like this, doesn’t it add interest and pleasure to mushroom hunting?



But I still want more advice on the secrets of successful mushrooming.

Mushroom hunting and the world of fungi have more than their fair share of mysterious lore, imponderables and surprises. Take that inexplicable instinct for the right spot to find mushrooms, for example. The experienced mushroomer knows his favorite haunts and whenever conditions are right, the mushrooms seem to call him. The dedicated mushroom hunter doesn’t have to make a conscious effort to memorize the perfect weather conditions for a particular species. Nor does he have to keep a log on the wind direction. Over the years, he just knows that on the right day he has to go to spot X. As vague as that sounds, the mushrooming “instinct” may well have a rational explanation, but it needn’t be a conscious one.

No exact science to mushrooming-hunting, then?

True, if you meet gnomes, pixies, fairies, elves or goblins in the woods, your rationality will be doubted.

But when fingers of fog creep eerily through the lonely wood, mythical creatures don’t seem far away. When out mushrooming in the twilight, you can easily understand how our forebears believed there were strange goings-on in the woods. Perhaps there were: and perhaps our modern powers of perception are just that much weaker than they used to be. The cold light of reason may have evicted all those colorful beings from the woods and now nobody is quite sure where they are anymore.



But they did leave their mark. The last bastion of mysticism is the fly agaric (left) which to this day has the power to fire the imagination. No decent fairy tale illustration is complete without the fly agaric. If the cep is the king of mushrooms, the fly agaric must be the queen. And as always with mushrooms, the mystical mixes with the scientific.

Fly agarics are useful indicators: where they are, there are often ceps nearby. Fly agarics wave and shout “Over here! Over here there are beautiful ceps!” The king is always near the queen.

Yet another mingling of fact and fiction: the fly agaric got its name from its surprising powers: it is a natural insecticide. Pieces of it are put in milk to attract flies. The flies then get drugged and die. In fact, the hallucinogenic properties of the fly agaric have inspired some mind-boggling theories and experiences.


JERSEY
Amanita muscaria
Fly Agaric
1994
23p
17Ft
Trombitagomba Craterellus cornucopioides
MAGYARORSZÁG
2,00
MONACO
PARC NATIONAL DU MERCANTOUR
1988
JERSEY
Cantharellus cibarius
Chanterelle
1994
30p
Leccinum versipelle
1980
FINLAND
SUOMI
ÍSLAND
85,00
GULBRODDI
Hydnum repandum

Shamans, or holy priests, reportedly used the hallucinogenic fly agaric to make contact with the gods, while lesser mortals joined in the ritual by drinking the urine of the shaman. This would have been little more than water with the hallucinogenic substances still active in it, because, before the ceremony, the shaman had to fast for several days before ingesting the fly agaric.

The phrase “to go berserk” refers to the Berserkers (Viking warriors) who went fearlessly into battle and were reported to fight “like mad dogs and wolves.” This is said to be the fly agaric’s work.



It surely now comes as no surprise that Santa Claus is also linked to the fly agaric. After all, there are the same distinctive colors: and there he is in his reindeer-powered sleigh, flying all over the world, filling stockings, and involuntarily cleaning chimneys. Only a full-blown shamanic fly agaric ritual could take Santa Claus and come up with a tale like that!

These are just a few of the theories and ideas linked to the fly agaric. Fly agarics are also supposed to bring good luck, and in certain parts of the world they remain a popular emblem in advertising, on stamps, and on Christmas and New Year’s cards. Luck is a fitting theme with which to conclude this book. Don’t trust your luck when identifying mushrooms. Follow the instructions in this book and enjoy mushrooming without fear.

* * *



EDIBLE AND POISONOUS MUSHROOMS OF THE WORLD

IAN R. HALL
STEVEN L. STEPHENSON
PETER K. BUCHANAN
WANG YUN
ANTHONY L. J. COLE

EDIBLE AND POISONOUS MUSHROOMS OF THE WORLD



Fig. 8.52
Ring Finger *- down, neutral.*
Index Finger *- open, neutral.*



Fig. 8.53
Thumb *- in and down, neutral.*
Index Finger *- open, neutral.*

Fig. 8.54
Pinky Finger *- down, neutral.*
Index Finger *- open, neutral.*



Fig. 8.55
Middle Finger *- down, neutral.*
Index Finger *- open, neutral.*



Crane's Beak

Form the crane's beak with both hands by bringing the fingertips together with the thumbs inside. Activate the saliva and swallow down three times to the Tan Tien. Raise the forearms to shoulder height with the fingers pointed down, inhaling gently as you raise. Open the palms slowly and begin to lower the arms to the sides as you exhale, until the palms are facing each other in the starting position.

Finish

Bring the awareness to the navel and notice the quality and intensity of the energy generated. **Collect energy at the navel**. Men, place the hands over the navel with the right hand on top; vice versa for women.

EDIBLE AND POISONOUS
MUSHROOMS
OF THE WORLD

IAN R. HALL

STEVEN L. STEPHENSON

PETER K. BUCHANAN

WANG YUN

ANTHONY L. J. COLE

Timber Press
Portland • Cambridge

Copyright © 2003 by the New Zealand Institute for Crop & Food Research Limited. All rights reserved. Mention of trademark, proprietary product, or vendor does not constitute a guarantee or warranty of the product by the publisher or authors and does not imply its approval to the exclusion of other products or vendors.

Published in 2003 by

Timber Press, Inc.	Timber Press
The Haseltine Building	2 Station Road
133 S.W. Second Avenue, Suite 450	Swavesey
Portland, Oregon 97204, U.S.A.	Cambridge CB4 5QJ, U.K.

Printed through Colorcraft Ltd, Hong Kong

Library of Congress Cataloging-in-Publication Data

Edible and poisonous mushrooms of the world / Ian R. Hall ... [et al.].
p. cm.
Includes bibliographical references (p.)
ISBN 0-88192-586-1
1. Mushrooms, Edible--Identification. 2. Mushrooms, Poisonous--Identification. 3. Mushrooms, Edible--Pictorial works. 4. Mushrooms, Poisonous--Pictorial works. I. Hall, Ian R. (Ian Robert), 1946-

QK67.E37 2003
579.6'163--dc21 2002075652

CONTENTS

Warnings 6
Preface 10
Acknowledgments 12
Introduction 13

CULTIVATING MUSHROOMS 27
COLLECTING WILD MUSHROOMS 93
A LIST OF WILD MUSHROOMS 119

Conversion Chart 301
Chinese Names of Mushrooms 303
Helpful Addresses 318
Web Sites 321
Glossary 323
References and Further Reading 327
About the Authors 347
Index 349

WARNINGS

Certain poisonous and edible mushrooms are easily confused. Before eating any mushroom, be absolutely sure of its identity and edibility. When it comes to mushrooms that are not illustrated in this book, or that are known to vary in appearance from the illustrations included in this book, it may be necessary to consult other texts listed in the bibliography, or a mushroom specialist. Please note, however, that the edibility of many mushrooms is still unknown. If there is any doubt whatsoever as to the identity and edibility of a mushroom, do not eat it. Even for a mushroom known to be edible, one should eat only a small amount the first time. Moreover, when eating wild mushrooms or new cultivated mushrooms, always place some uncooked ones aside in the refrigerator in case there has been a mistake or there is an allergic reaction to the mushroom. If any illness is experienced after eating a mushroom, consult a doctor immediately.

Reasonable efforts have been made to publish reliable data and information, but the authors and publisher cannot assume responsibility for the validity of all materials or for the consequences of their use. The publishers and the authors can take no responsibility for the misidentification of mushrooms by the users of this book nor any illness that might result from their consumption.

Lưu ý

Một số loại nêm độc rêt khó phân biệt với các loại nêm có thể ăn được. Vì vậy trước khi ăn bêt cứ loại nêm nào, bạn phải biết chắc chắn về nguồn gốc và tố chêt của nó. Bạn cần tra cứu lại danh mục cuốn sách hoặc tham vên các chuyên gia về nêm nếu gặp phải những loại nêm không được mô tả trong cuốn sách này hoặc hình dách của nó khác với những loại được minh họa. Xin lưu ý, chúng ta vẫn chưa biết rõ nguồn gốc và độc tố của một số loại nêm. Vì vậy xin đừng ăn nếu bạn có nghi ngờ về nguồn gốc và độc chêt của các loại nêm đó. Khi ăn các loại nêm dại hoặc các giống nêm mới, bạn nên luôn để dành một ít vào tủ lạnh phòng khi bạn bị dị ứng với loài nêm đó. Nếu cảm thêy khó chịu sau khi ăn bạn nên đến xem bác sỹ ngay lập tức. Tác giả và nhà xuêt bản đã nổ lực để mang đến cho bạn những thông tin chính xác đáng tin cậy.

Tuy nhiên chúng tôi sẽ không chịu trách nhiệm về sự chính xác tuyệt đối của các thông tin trên và hậu quả của việc sử dụng nó. Chúng tôi sẽ không chịu trách nhiệm nếu độc giả không phân biệt đúng các loài nấm và những căn bệnh gây ra bởi sử dụng các loài nấm trên.

注意

毒茸か食べられる茸か紛らわしいのがあります。茸を食べる前に、その正体と食用性を、必ずご確認ください。この本に描かれていない茸、またはこの本に含まれている図とその外見が異なっていることが知られている茸については、参考文献に挙げられている他の教本を調べたり、茸の専門家に相談する必要があるかも知れません。しかしながら、食用性がまだ知られていない茸は多いので、初めてその茸をお試しになられる際は常に少量お召し上がりになることをお気に留めください。もしその茸の正体と食用性が少しでも疑わしい場合は、お召し上がりにならないでください。野性の茸や新たに培養された茸をお召し上がりになられる際は、誤りがあった場合やその茸にアレルギー反応があった場合に備えて、料理されていない茸をいくつか別に冷蔵庫に取っておいてください。もし茸を食べた後に何か病状が現われた場合は、直ちに医師にご相談ください。

信頼性のある資料や情報を出版するのにかなりの努力が成されましたが、著者と出版者は全ての資料に関する有効性とまたはその利用法の結果に関して、責任を負えません。著者と出版者は、この本の利用者が茸の正体を間違ったり、茸を食べたことから起こる如何なる病状に関しては責任は取れません。

경고

어떤 독버섯과 식용 버섯은 쉽게 혼동되기도 합니다. 어떠한 버섯이든지 먹기 전에 그 버섯의 정체와 먹을 수 있는지 여부에 대한 절대적인 확신을 가져야 합니다. 이 책에 사진으로 설명되지 않은 버섯이나 또는 이 책의 사진 설명과 모양에 차이가 있는 버섯에 관하여는 참고 서적 목록에 나와 있는 다른 책을 참고하거나 또는 버섯 전문가와 상의하십시오. 하지만 먹을 수 있는 버섯인지 아닌지 아직도 규명되지 않은 것들이 많으며, 따라서 어느 경우라도 처음 먹어보는 버섯인 경우는 아주 조금만 먹어야 합니다. 버섯의 정체나 식용 가능여부가 불확실하면 그 버섯은 먹으면 안됩니다. 야생 버섯이나 인공 재배한 새로운 버섯을 먹을 때는 항상, 실수나 또는 버섯에 대한 알레르기 반응에 대비하여, 요리하지 않은 버섯을 조금 냉장고에 따로 보관해야 합니다. 버섯을 먹은 후 조금이라도 이상한 징후가 나타나면 즉시 의사와 상담해야 합니다.

신뢰할 수 있는 데이터와 정보를 출판하려고 상당한 노력을 기울였지만, 저자와 발행인은 모든 자료의 확실성 또는 이 자료를 사용한 결과에 대하여 책임을 질 수 없습니다. 발행인과 저자는 이 책의 독자가 버섯을 잘못 확인하거나 또는 그 결과로 버섯을 먹어서 생기는 일체의 병에 대하여 책임지지 않습니다.

He Whakatūpato

Kei haere pōhēhē te tangata ki te kato i ngā harore me ngā kōpurawhetū, kei riro mai ko ngā harore paihana i te taha o ngā harore e taea te kai! I mua i te kainga i tētahi harore, kia tino mōhio koe he aha taua harore! Kia tae ki ngā harore kāore i tāia he pikitia i tēnei pukapuka, ki ngā harore rānei he rerekē te āhua i tēnā rā, i tēnā rā, arā, he rerekē i ngā whakaahua i tēnei pukapuka, me tiki rawa ki ngā pukapuka kua oti te whakarārangi i te rārangi pukapuka. Ā, me haere rānei ki te tino tangata pūkenga mō ngā harore katoa. Kia tūpato! Kāore anō ngā tohunga kia mōhio ki te tōtika o ngā harore katoa hei kai. Mehemea kātahi anō koe ka kai i tētahi harore, me whakamātau kau atu, kia iti te kainga. Mehemea kei te rangirua ō whakaaro, kāore koe e mōhio he aha rawa taua harore, kaua e kainga. Kia tae koe ki te kai i ngā harore i tupu noa i te tuawhenua, ki ngā harore hou rānei, nā te tangata i whakatupu, meatia atu ētahi harore mata tonu, (kāore i tunua) ki roto i te pouaka makariri. He mea tēnei mō ngā wā kua pōhēhētia ngā momo harore, mō ngā ohonga pāwera (allergic reaction) rānei o te tangata ki taua harore. Ki te māuiui te tangata i muri i te kainga o tētahi harore, whakapā tika atu ki te tākuta.

I mahi nui mātou ki te tā i ngā mōhiotanga whai tikanga, me ōna whakamārama katoa e tika ana, heoi anō, e kore e taea e te kaiwhakaputa te kī, he pono tūturu ngā whakamārama katoa a te tangata kē i roto i tēnei pukapuka, me ngā āhuatanga ka puta i te haringa hei tino kōrero whai-mana e te tangata. Kāore hoki te kaiwhakaputa me ngā kaituhi e whakaae ka tau te hē ki a rātou mō te whakaingoa pōhēhē a te tangata kē, i ētahi o ngā harore i tēnei pukapuka, me ngā māuiuitanga tērā pea ka pā ki te tangata i te kainga o aua harore.

คำเตือน

เห็ดบางชนิดสามารถนำมารับประทานได้และบางชนิดเป็นเห็ดมีพิษซึ่งสามารถทำให้เกิดควมสับสนได้เสมอ แต่ก่อนที่จะรับประทานเห็ดชนิดใดก็ตาม ก็จะต้องให้แน่ใจจริงๆว่าเป็นเห็ดที่เรารู้จักและสามารถรับประทานได้ สำหรับเห็ดใดก็ตามที่มิได้นำมาแสดงไว้ในหนังสือเล่มนี้ อาจจำเป็นต้องไปค้นคว้าหาความรู้เพิ่มเติมเอาจากหนังสือเล่มอื่นตามที่มีรายชื่อปรากฏอยู่ในหน้าบรรณานุกรม หรือไปขอรับคำปรึกษาจากผู้เชี่ยวชาญด้านเห็ด และขอให้โปรดทราบไว้ด้วยว่ายังมีเห็ดอีกเป็นจำนวนมากที่ยังไม่ทราบว่าสามารถรับประทานได้หรือไม่ หากต้องรับประทานเห็ดชนิดใดเป็นครั้งแรก ก็ขอให้รับประทานเพียงจำนวนเล็กน้อยก่อน เมื่อมีข้อสงสัยว่าเป็นเห็ดชนิดใดและสามารถรับประทานได้หรือไม่ ก็ไม่ควรรับประทานเข้าไป และเมื่อต้องรับประทานเห็ดที่ขึ้นเองหรือเห็ดชนิดใหม่ที่ได้มาจากการเพาะเลี้ยง ขอให้นำส่วนที่ยังมิได้ปรุงเป็นอาหาร จัดเก็บไว้ในตู้เย็นจำนวนหนึ่ง เมื่อมีความผิดพลาดเกิดขึ้นจากการเพาะเลี้ยง หรือมีอาการแพ้ที่เกิดขึ้นจากเห็ดนั้นๆ ถ้ารับประทานเห็ดเข้าไปแล้วมีอาการไม่สบายขึ้นมา ก็ให้ไปพบแพทย์ทันที

หนังสือเล่มนี้ได้พยายามที่นำเสนอที่มีรายละเอียดและเนื้อหาที่น่าเชื่อถือ แต่ผู้เขียนกับผู้พิมพ์โฆษณาไม่สามารถแสดงความรับผิดชอบต่อความสมจริงสมจังของสาระเนื้อหาหรือสิ่งอื่นใดที่จะเกิดขึ้นตามมาภายหลังจากที่ได้นำไปปฏิบัติ ดังนั้นผู้เขียนและผู้พิมพ์โฆษณาจึงไม่สามารถรับผิดชอบในการที่ผู้อ่านหนังสือเล่มนี้นำไปใช้ระบุชนิดของเห็ดแล้วเกิดความผิดพลาด หรือต่อความเจ็บป่วยที่เกิดจากการรับประทานเห็ดเหล่านั้น

PREFACE

The past few decades have witnessed a dramatic increase in the diversity of mushrooms gracing the tables of our restaurants and the shelves of our supermarkets. While the increased consumption has consisted primarily of cultivated varieties of Asian origin, there has also been an upsurge of interest in mushrooms that can be obtained only from the wild.

A concern over a lack of knowledge in Australasia, the often prevailing opinion that "if it's natural it must be edible," and some significant incidents of mushroom poisonings prompted the development and ultimate publication of a book on the subject in New Zealand in 1998. The book, written by Ian Hall, Peter Buchanan, Wang Yun, and Tony Cole, covered the most important edible and poisonous mushrooms that Australians and New Zealanders might encounter in the wild, as well as the edible mushrooms that could be purchased in supermarkets. The original authors were joined by Steve Stephenson, a mycologist from the United States, and their combined efforts produced this new book. Whereas the first book mentioned or illustrated about 205 taxa, this book treats about 280 taxa, and many taxa only mentioned or illustrated in the first book are now discussed. The resulting reference is truly international in its coverage and will appeal to enthusiasts from around the world.

Edible and Poisonous Mushrooms of the World is aimed at individuals who are interested in mushrooms and wish to expand their knowledge about the subject, including information on the roles of fungi in nature and how they can be grown and cultivated. The introduction provides essential background information about what mushrooms are, both poisonous and edible, how they are named, and how they fit into the big picture, both as part of the natural world and as part of the world market. The first section, Cultivating Mushrooms, divides its attention between nonmycorrhizal mushrooms, including the eight most popular saprobic mushrooms, and mycorrhizal mushrooms, with an emphasis on the Périgord black truffle. The second section, Collecting Wild Mushrooms, discusses the identification and collection of mushrooms and the rules that should be followed when picking them. It also includes a helpful list of the major poisoning syndromes and the mushrooms known to be associated with each one. The final section, A List of Wild Mushrooms, is the cornerstone of the book, providing details of size, color, habit, and other identifying factors for the world's most common edible wild mushrooms (including those with major international markets), for poisonous species that should be avoided at all costs, and for mushroom curiosities likely to be encountered in nature.

Many hundreds of species of questionable or unknown edibility have been omitted, as have a large number of lesser edible mushrooms that may be important in one country but not in others. For information on these species it would be wise to consult mushroom field guides in the relevant country.

A vast amount of information on mushrooms can be found on various Web sites, a few of which are listed in *Mushroom Cultivation with Special Emphasis on Appropriate Techniques for Developing Countries* (Oei 1996) and related articles in *Mycologist* magazine (Hamlyn 1996, 1997a, 1997b). Simply typing the word "mushroom" into a general search engine will bring up tens of thousands of references. A more useful and orderly search can be obtained by accessing Cornell University's WWW Virtual Library of Mycology. While a good proportion of the information available from the Web is of high quality, much of it is also ephemeral, and this creates major problems for those using it. Web addresses also have a tendency to change when those who created the Web page change employment or move to another server. Consequently, the list of Web addresses at the back of the book includes only those sites expected to be reasonably permanent, such as those run by universities or other major institutions.

Chinese Names of Mushrooms is a helpful list of edible mushrooms at the back of the book. It should be a useful tool for those wanting to purchase mushrooms at Chinese markets. Addresses of organizations and periodicals that might be of interest are also listed, and a glossary is included to familiarize readers with terms used in the book. All amounts of money stated in dollars are United States currency.

ACKNOWLEDGMENTS

We are indebted to designer Jo Smith of the New Zealand Institute for Crop and Food Research at Lincoln for producing the graphics, Lynette Mitchell for patiently making all the many corrections and changes to our text, and Sue Zydenbos, Tracy Williams, and Angela Templeton for their essential editorial work. We are extremely grateful to a number of friends and colleagues who provided photographs for inclusion in this book. Without their contributions it would have been impossible to make this book a comprehensive introduction to the edible and poisonous mushrooms of the world. Particular thanks are extended to Masana Izawa, Emily Johnson, Tony Lyon, and Tian Jinghua. Additional slides were provided by Jim Douglas, Forest Research, Juliet Fowler, Bruce Fuhrer, Don Hemmes, Mario Honrubia, HortResearch, Peter Johnston, Landcare Research, William C. Roody, Jack Squires, and Alessandra Zambonelli. Our thanks also go to Mel Boulton, Ilse and Erhard Jungmayr, Peter Katsaros, Orson K. Miller, Jr., Jean-Marc Moncalvo, Makoto Ogawa, Peng Jin Torng, Shaun Pennycook, Fabio Primavera, Scott Redhead, Geoff Ridley, Barbara Segedin, Walter Sturgeon, Jim Trappe, Georgette Wang, and Wu Chi Guang for their assistance on various aspects of this project. Finally, we are indebted to the Agricultural and Marketing Research and Development Trust and the Foundation for Research, Science, and Technology for their foresight in funding the 1998 book on which this book is founded.

Part III

Opening the Functional and Governor Channels

Theory: Functional and Governor Channels

The Functional and Governor Channels are the first two of the eight extraordinary channels described earlier in this chapter (beginning p.178). They serve as the reservoirs of yin and yang energy in the body. The Functional or Conception Channel is yin and all of the ordinary yin channels connect to it. Similarly, the Governor Channel is yang and all of the ordinary yang channels connect to it.


Pineal Gland beneath Crown (Enlightenment Gland, Gland of Direction)
Pituitary Gland (Mideyebrow)
Crystal Room Cavity of the Spirit Tongue
Yui-Gen (Cranial Pump)
Ta-Chui (Central Control of the Tendon Connections of the Hands and Spinal Cord)
Hsuan Chi (Throat Energy Center)
Shan Chung (Thymus Gland) Rejuvenation Center
Gia-Pe (Opposite Heart Center)
Chung Wan (Solar Plexus, Pancreas)
Chi-Chung (Adrenal Gland Center at T-11)-Mini pump
Chi-Chung (Navel, Spleen)
Ming-Men (Kidney Point - Door of Life); Prenatal energy storage safety point.
Ovary/Sperm Palace
Chang-Chiang, Coccyx (Sacral Pump)
Extra 31 (He ding)
Hui-Yin (Perineum - Gate of Death and Life)
Wei-Chung BL-40; extra Spirit Energy is stored here.
Functional Channel
Governor Channel
Yung-Chuan K-1 (bubbling spring)

Fig. 8.56 *Cosmic Orbit*

INTRODUCTION

When tree leaves change color, dew rises, and autumn mists descend, mushrooms begin to appear above the soil, and logs, stumps, and fallen branches come alive with “toadstools” and other mysterious protuberances. This is the signal for mushroom collectors to take to the fields and forests. They often do so with the zeal and passion of antique collectors in a flea market, or miners smitten by gold fever—though experienced collectors temper excitement with caution, knowing as they do that an inaccurate identification can be fatal. Others may hunt mushrooms for different reasons, appreciating them as intriguing life forms or marvelous photographic subjects.

This book provides a brief introduction to edible mushrooms for the layperson, while also including warnings about poisonous species. It also introduces mushroom cultivation methods, points the way to additional sources of information for those who would like to try to grow mushrooms, and provides a useful reference to anyone with a scientific interest. The aim, however, is not solely to inform but also to generate interest in the fascinating world of fungi.

Fungi, Mushrooms, Toadstools, and Truffles

Many people grow up thinking fungi are the molds and spots on roses and shower curtains, mushrooms are the things sold in the market or collected in the woods, toadstools include everything else and are probably poisonous, and truffles are expensive chocolates. But there is a lot more to these subjects. Because of their sudden appearance and disappearance, their frequent association with decaying organic matter, their vivid colors, fantastic shapes, and, in some instances, poisonous properties, mushrooms have often been regarded as objects of mystery, and have even at times been associated with the supernatural. In reality, mushrooms are among the most fascinating and beautiful inhabitants of the natural world.

This book adopts a very broad definition of the word “mushroom,” using it in its widest sense to encompass not only what the layperson would call mushrooms but also toadstools, truffles, puffballs, stinkhorns, bracket fungi on wood, and various other forms, whether they are edible or not—in other words, any fungus with “a distinctive fruiting body that is large enough to be . . . picked by hand” (Chang and Miles 1992). Such readily visible fruiting bodies (as opposed to the many fungi with microscopic fruiting bodies, such as molds) may include a stalk, cap, and gills, as with the button mushrooms found in the supermarket, or, as with many other fungi, quite bizarre shapes.

All life forms can be segregated into a few kingdoms. The animal kingdom, thanks to the huge numbers of insects, contains the greatest number of species. The fungi are the second largest assemblage of organisms and should be considered quite separate from the plant kingdom, containing several times as many species. Fungi comprise an estimated 1.5 million species of nonphotosynthetic (chlorophyll-free) organisms that absorb their nutrients from dead or living organic matter, have cell walls containing chitin and β-glucans, and reproduce sexually or asexually. Most fungi are placed together in their own group, known as the kingdom Fungi. This is where the mushrooms are found (Alexopoulos et al. 1996, Hudler 1998, Kirk et al. 2001).

The fungi are an exceedingly diverse group of organisms. Because they cannot manufacture their own food, they must obtain nourishment from plants and animals or their products, or even from other fungi. Each day people come into contact with both the harmful and the beneficial effects of fungi, the former including the molds that grow on bread and shoes and those that cause plant and animal diseases. Fungi play a positive role in foods such as beer, bread, and blue cheese, as they do in antibiotics like penicillin (from *Penicillium*), the immunosuppressant cyclosporine (from *Tolypocladium*), which reduces organ rejection after transplant operations, and ergometrine, which is extracted from diseased flowers (ergots) of rye and used in the management of the third stage of labor and the treatment of bleeding after childbirth (Reynolds and Parfitt 1996). However, the most important service provided by fungi has to do with the role they play as decomposers: fungi help rid the earth of huge quantities of plant and animal remains by recycling the nutrients found in dead matter. They also help plants grow through mycorrhizal relationships.

A number of the larger mushrooms are also valuable for their medicinal qualities, some even having been used at one time as styptics to constrict blood vessels and check the flow of blood (Baker 1989). Mushrooms have more obscure uses as well: a beautifully colored timber is produced when oak is infected with beefsteak fungus (*Fistulina hepatica*); a dye used by the New Zealand Maori in tattooing is prepared by grinding steamed and dried caterpillars infected with the vegetable caterpillar fungus (*Cordyceps robertsii*); and the Australian Aborigines use the stalked puffball (*Podaxis pistillaris*) to darken white hair and repel flies (Kalotas 1997, Riley 1994).

Where Do They Come From?

Mushrooms as a group are found all over the world. The individual organism (the "body" of the fungus) consists of an extensive network of very finely branched microscopic threads called hyphae. Collectively, the hyphae making up such a network are referred to as a mycelium. The structure we recognize as a mushroom is in reality just a highly organized system of hyphae, specialized for reproduction, that develops from the otherwise vegetative mycelium inhabiting soil, leaf litter, or decaying wood. The individual hyphae obtain the nutrients and water the fungus needs to grow. After a period of growth, and under favorable conditions of temperature and moisture, the mycelium gives rise to one or more fruiting bodies, or mushrooms. As such, what is thought of as a mushroom performs the same function and is analogous to an apple on an apple tree, since it is the "fruit" of the mycelium. Long-distance dispersal is achieved by the many millions of microscopic spores produced by the fruiting body. These spores can be carried by wind currents to very distant places. While mushrooms are the most visible representatives of the fungi, they form only a minor part of a group that has, in an evolutionary sense, been very successful. Fungi occupy nearly every imaginable type of habitat, including both fresh water and the sea as well as all habitats found on land, and have been said to have twice the collective biomass of all animals on earth.

Although fungi have long been thought of as members of the plant world, their ancestors might actually have been animals. The divergence of the fungi and animal kingdoms must have occurred a very long time ago, since molecular evidence suggests that fungi have been present on the earth for as long as one billion years (Heckman et al. 2001). Regardless of their exact evolutionary affinities, a wealth of fungi now exist, including mushrooms with complex structural organizations. These structures, as already noted, are only the visible fruiting bodies of often very extensive underground networks of hyphal threads. According to recent reports, there is one fungus in the United States that occupies some 600 hectares of forestland, making it the world's largest organism (Brasier 1992). At an estimated age of well over a thousand years, it is also one of the oldest.

A few of the mushrooms seen in one place may have arrived from another part of the world as mushroom spores borne on wind currents. Others may have arrived in a very different way, perhaps on soil adhering to plants, shipping containers, or boots, or even within the bodies of plants carried from one country to another by early settlers. As a result, it can be very difficult to distinguish between a country's native fungi and those that have been introduced or have recently arrived from elsewhere.

Edible Specialty Mushrooms

Everyone is familiar with the white button mushrooms found in plastic containers on supermarket shelves, and many will have ventured to

A mushroom counter in a large supermarket in Hong Kong. (Buchanan)

A wild mushroom collector sells hatsudake (*Lactarius hatsudake*) on a roadside in northern Hunan, China. (Hall) try the darker, larger, and better-flavored Swiss brown strain button mushrooms, shiitake, and, perhaps without even realizing it, straw mushrooms, which are often used in dishes at Chinese restaurants. For many people, however, experimentation with alternative mushrooms may well have stopped there. In China, where mushrooms have been cultivated for thousands of years, and in continental Europe and many other parts of the world, shops, roadside and market stalls, and supermarkets offer a wide range of mushrooms. To the unenlightened these could be regarded as unappetizing, even dangerous, but in reality they are often a gourmet's delight.

There are many devotees of mycophagy (fungus eating) in Japan, where more than one hundred types of wild mushrooms are popular (Ueda et al. 1992). In Britain the population is not noted for consumption of specialty mushrooms (cultivated mushrooms other than *Agaricus bisporus* and *A. bitorquis*), and keen mycologists have struggled to assemble a similar list, eventually coming up with only twenty commonly eaten wild mushrooms (Legg 1990). Sadly, in countries such as Australia, New Zealand, England, and the United States,



Tremella fuciformis (white jelly fungus), *Lentinula edodes* (shiitake), *Dictyophora indusiata* (bamboo mushroom), and *Auricularia polytricha* (wood ear) in a local market at Wuyi Mountain, Fujian, China. (Buchanan)

TABLE 1. EDIBLE MUSHROOMS PRODUCED IN TWENTY-TWO CHINESE PROVINCES IN 1998 (Chinese Association of Edible Fungi 2000).

Scientific name	**Common name**	**Amount produced (× 1000 tons)**
Lentinula edodes	shiitake	1338
Pleurotus spp.	oyster mushroom	1020
Auricularia polytricha	wood ear	432
Agaricus bisporus and *A. bitorquis*	button mushroom	426
Flammulina velutipes	enokitake	189
Tremella fuciformis	white jelly fungus	100
Auricularia auricula	wood ear	59
Volvariella volvacea	straw mushroom	32
Pholiota nameko	nameko	31
Hypsizygus marmoreus	shimeji	22
Grifola frondosa	hen of the woods	10
Boletus spp.	boletes	8.1
Ganoderma spp.	conks	6.7
Lactarius deliciosus	saffron milk cap	6.0
Hericium erinaceus	lion's mane mushroom	2.8
Coprinus comatus	shaggy ink cap	1.8
Dictyophora indusiata	bamboo mushroom	1.1
Pleurotus cornucopiae var. *citrinopileatus*	golden oyster mushroom	0.5
Agaricus blazei	almond portobello	0.1
Others		293.9
TOTAL		**4350**

mushrooms such as the delicious giant puffball (*Calvatia gigantea*) and porcini (*Boletus edulis*) are more likely to receive a swift dispatch with the end of a boot than to be picked as a delicacy.

Identifying and Naming

Most people are familiar with *Homo sapiens*, the scientific Latin binomial name for humans, and perhaps also with names such as *Rosa*, the genus in which roses are placed, *Ficus*, which might be found on a label attached to a rubber tree, and *Amanita muscaria*, commonly known as fly agaric, the red mushroom with white markings often seen in autumn and illustrated in children's books. Though they are sometimes awkward to pronounce, there is really no substitute for these scientific names. The strict rules attached to their usage make confusion over different kinds of fungi unlikely—and confusion is to be avoided, especially when trying to distinguish between edible and poisonous mushrooms. These names are universally accepted and are common to publications on mushrooms in Japanese and Chinese as well as those written in English or the languages of continental Europe. However, they are not always used in China, which is one reason why pinyin names have been included at the back of the book (see Chinese Names of Mushrooms).

That said, even scientific names occasionally cause problems. Thus, to be precise, each scientific name should be followed by the name of the person, called the authority, who first described the fungus in question. Authorities can be found in many books on mushrooms. For the species mentioned in this book, this information appears in the index. Occasionally taxonomists may not be absolutely sure which species they are dealing with. When this happens they will insert "aff." or "cf." between the genus and species names, meaning that it belongs to the genus and is similar to the species. When they are really stumped, they will simply put "sp." after the name of the genus (for example, *Amanita* sp.) to indicate that it is an unidentified species. The abbreviation "spp." simply refers to several species of a genus.

The genus and species are always set in italics, and only the genus is capitalized. Once the name of a species (*Amanita muscaria*, for example) has been used in a text, it is permissible to abbreviate the genus name (*A. muscaria*) for the rest of the paragraph, unless there could be confusion with another genus beginning with the same letter. Genera with similar features (though these are not always obvious to a nonspecialist) are grouped together in families, the names of which almost always end in *-aceae* (as in Agaricaceae, the family that includes the button mushroom). In turn, families are grouped together into what, for the fungi, can be rather artificial groupings, called orders, with names ending in *-ales* (as in Gasteromycetales, the group that includes puffballs). Above that, they are grouped into classes. Mushrooms can be found in the class Basidiomycetes, which contains the majority of mushroom species, and the class Ascomycetes, which includes the truffles (for example, *Tuber*), morels (*Morchella*), false morels (*Gyromitra*), and the cup fungi (for example, *Peziza* and *Paxina*). Members of the Ascomycetes are considered more primitive than those of the Basidiomycetes and usually produce their spores in small sacs called asci.

Common names, like "field mushroom," are very loosely applied and can be used for one species in one particular area and for something quite different in another area. Therefore, it is preferable to use a common name only when it is clearly equated with a scientific name. Many mushrooms have multiple common names. For the purposes of this book, only one common name is given per scientific name. More common names can be found in the multilingual *Elsevier's Dictionary of Edible Mushrooms* (Chandra 1989) and in *An Index of the Common Fungi of North America* (Miller and Farr 1975).

To Eat or Not to Eat

In China, Japan, and parts of Europe, the well-established tradition of eating wild mushrooms is sustained with books filled with color photographs and information on what is edible and what is not. Children in such places—rural France or Italy, for example—might be taken mushroom hunting with their families, from whom they learn about edible and poisonous species. Later, in the kitchen, mouthwatering traditional recipes might be handed down, along with the special preparations a few mushrooms require to render them safe to eat.

In Germany after World War II, in places where food was in short supply, many people collected wild mushrooms from forests and either ate them themselves or sold them in the marketplaces. To limit the number of inevitable poisonings, inspectors were employed to ensure that people were not sold inedible or poisonous species (I. Jungmeyer and E. Jungmeyer, personal communication), and books were distributed containing watercolor paintings of not-so-edible mushrooms and describing the relative merits of edible species (for example, Neuhaus and Neuhaus 1947). A similar book was issued in Britain just after



Estimated world consumption of edible mushrooms in 1997 (× 1000 tons) (from Chang 1999).

World War II (Ministry of Agriculture and Fisheries 1945), but no inspectors were employed, which perhaps reflects the level of interest the British then had in wild mushrooms. Mushroom inspectors are still employed in countries such as France and Finland to check the edibility of mushrooms on sale in markets (Ohenoja and Lahti 1978, Renaud 1989). French collectors who are unsure of the edibility of a mushroom can also approach their local pharmacist for advice. During mushroom season it is not uncommon to find pharmacies open on Sunday mornings to cope with the demand for such counsel.

Unfortunately the increased interest in both cultivated and wild mushrooms has led to a mistaken belief by some that anything

Chi Ball

In Part III we also begin to focus more on the sensation of Chi being emitted from our palms. This energy is emitted from the **Laogong** points primarily, but you can also feel it throughout the palms and fingers. It will feel like a balloon between your hands that is expanding and contracting or like two magnetic fields repelling and attracting each other.

Once you have practiced Cosmic Chi Kung for awhile and have become skillful at it, you may find that Grasping the Chi ball is all you need to do to activate your flow of healing energy before doing a session. As you become sensitive to the sensation of your own Chi, it becomes an easy step to feel the Chi of others.



Fig. 8.57 *Grasping the Chi Ball.*

Opening Movements, Hands Down at Sides, Palms Facing Each Other
Bone Breathing - Absorbing Cosmic Chi

The Opening Movements are the same as in the sequence in Part I, 'Opening to Heaven, Earth and Cosmic Chi', on page 164.

A. **Channeling the Earth Force - Washing the Bone Marrow** Raise arms to chest height - Palms facing each other. Rotate arms until **palms face down.** Open the Tiger's Mouth - Index finger up, thumb down.
B. **Activate and Beam to the Eye of the Hip**
C. **Absorb the Heavenly Force Washing the Bone Marrow - Crown to Soles**

TABLE 2. TYPICAL WHOLESALE PRICES FOR THE MAIN CULTIVATED MUSHROOMS (Anonymous 2000a, Chang 1999).

Scientific name	**Common name**	**Typical wholesale prices (per kilogram)**
Agaricus bisporus, *A. bitorquis*	button mushroom	\$1.76–\$3.74, up to \$7.70 for portobello
Pleurotus spp.	oyster mushroom	\$4.40–\$8.36
Lentinula edodes	shiitake	\$7.04–\$12.47
Auricularia spp.	wood ear	approx. \$5.00–\$10.00
Volvariella volvacea	straw mushroom	approx. \$5.00–\$10.00
Flammulina velutipes	enokitake	\$4.60–\$12.56
Tremella fuciformis	white jelly fungus	approx. \$5.00–\$10.00
Pholiota nameko	nameko	\$4.77–\$6.35

To enable comparisons, the following exchange rates are assumed: \$1.00 = 14.70 Austrian schillings, 7.00 Chinese yuan, 1.02 European euros, 7.03 French francs, 2.10 German marks, 2072.00 Italian lire, 113.00 Japanese yen, 2.29 New Zealand dollars, 0.67 pounds sterling, 1.72 Singapore dollars.

"natural" must be edible. There are instances of people eating poisonous mushrooms like *Scleroderma* species because "they smell like mushrooms," and the lethal death cap (*Amanita phalloides*) and destroying angel (*A. virosa*) because they resemble edible species. A few mushrooms are deadly poisonous and can be lethal even when only small quantities are consumed. Others are less poisonous but can still produce nausea, stomach upsets, or hallucinations, while some contain compounds that can trigger an allergic reaction months or years after the mushroom was first eaten. A few are only poisonous if consumed with alcohol. Consequently, great care has to be taken to identify a mushroom before it is eaten

TABLE 3. APPROXIMATE WORLD MARKET VALUE AND TYPICAL PRICES FOR MYCORRHIZAL MUSHROOMS.

Scientific name	**Common name**	**Approximate in-season retail market**	**Approximate wholesale prices** (per kilogram, grade one)
Boletus edulis	porcini	> $250 million	$13–$198
Cantharellus cibarius	chanterelle	$1.62 billion	$8–$19
Tricholoma matsutake	matsutake	$500 million	$40–$500
Tuber melanosporum	Périgord black truffle	> $150 million	$250–$1200
Tuber magnatum	Italian white truffle	> $150 million	$1000–$30,000

(Haard and Haard 1980, Lincoff and Mitchel 1977, Scates 1995, Spoerke and Rumack 1994).

There are no rules that make it easy to distinguish between edible and poisonous mushrooms. Forget about a mushroom being edible if it can or cannot be peeled or if it blackens a silver spoon—these are old wives' tales. The only safe practice is to accurately identify a mushroom and then check a good textbook or field guide to determine if it is edible. The golden rule remains the same: if in doubt, throw it out.

Idiosyncratic adverse responses to some mushrooms are not uncommon. When trying a new and confirmed edible mushroom, keep a sample in the refrigerator in case an adverse reaction occurs later on and calls for further identification of the mushroom. It is always best to cook mushrooms before eating them, as some contain poisons that are destroyed by heat; but not all mushroom poisons are so easily destroyed, so be careful.

Many fungi accumulate heavy metals and radioisotopes, some containing one hundred times the levels found in the soil (Benjamin 1995). Avoid eating mushrooms found on roadsides, where lead levels may be high, or from areas where the soil may be rich in elements like cadmium, chromium, and mercury. Likewise, do not eat mushrooms grown where chemical sprays may have been used.

In countries such as Australia and New Zealand there is a general lack of background information on native and introduced mushrooms. This is partly because the native peoples of both countries appear to have used few mushrooms, a fact reflected in the limited literature available on the subject. The Australian Aborigines' native bread (*Laccocephalum mylittae*) and beech strawberry (*Cyttaria gunnii*) are two notable exceptions (Fuhrer 1985, Kalotas 1997). Few of the early European settlers brought information of any use with them, since the species they encountered in Australia and New Zealand were quite different from the species in Europe.

It's a Big Market

It has been estimated that more than six million tons of cultivated mushrooms were consumed worldwide in 1997 (Chang 1999). It is often assumed in Western countries that button mushrooms dominate the market, but in fact they represent only a third of production, with the bulk made up of a dozen or so specialty mushrooms. Assuming a modest average retail price of $5 per kilogram, in United States terms this equates to an annual market of around $30 billion.

However, the real market is larger still. In addition to the cultivated mushrooms that pass through official markets, hundreds of thousands of tons of wild mushrooms are collected from fields and forests, and among these are some of the most expensive foods in the world.

About half of all cultivated mushrooms are produced in China (Chang 1999), where around 2.7 kg of mushrooms are consumed every year by more than a billion people (Chinese Association of Edible Fungi 2000, Sun and Xu 1999). Similar quantities are consumed in the United States, where mushrooms are now the fifth largest crop and are worth around $870 million to approximately three hundred growers (ERS 2002, NASS 2000).

The price paid for each mushroom species tends to reflect the ease or efficiency with which it can be cultivated and, particularly in the case of wild mushrooms, its scarcity and market demand (Anonymous 2000a). For example, the straw mushroom can be grown relatively easily and quickly on almost any cellulosic material, provided the temperature is high enough, and consequently it commands a low price. In contrast, the Périgord black truffle and Italian white truffle, which can take up to twenty years to begin fruiting on their host plants, are in great demand by chefs and gourmets and can command a price equal to that for gold (Hall et al. 1994, Johnston 2000).

This page intentionally left blank

CULTIVATING MUSHROOMS

This page intentionally left blank

Depending on how they obtain nutrients, mushrooms are either nonmycorrhizal (saprobic or parasitic) or mycorrhizal. Saprobes gain their nutrition from dead plants and animals. Many can be cultivated, with varying degrees of difficulty (Stamets 2000). Some, like the morels, require very specialized conditions, while others have never been cultivated (Anonymous 1997, Stamets 1993). In contrast to the saprobes, parasitic mushrooms, such as the honey mushroom (*Armillaria mellea*) and some bracket and oyster mushrooms (for example, *Pleurotus eryngii* and *P. ostreatus*), obtain their nutrition from living plants, often causing severe damage to them in the process. Mycorrhizal or symbiotic mushrooms also derive nutrients from living plants, but instead of harming the host plant they assist its growth by stimulating the uptake of nutrients from the soil. Edible examples include the truffles (for example, *Tuber*), matsutake (*Tricholoma matsutake*), porcini (*Boletus edulis*), chanterelle (*Cantharellus cibarius*), and the saffron milk cap (*Lactarius deliciosus*).

NONMYCORRHIZAL MUSHROOMS

About 95 percent of all cultivated mushrooms are saprobic and can be cultivated on various dead organic materials such as straw, wood, and wastepaper. Some saprobes are produced in what are little more than cottage industries, while others are grown in huge, highly efficient factories, their production and sale the basis of multimillion-dollar industries. Certain saprobes, called the sugar fungi, can only use sugars available in the growth medium. Others, including many edible varieties, can break down much more complicated molecules, such as cellulose or other highly resistant compounds found in wood.

Although around fifty saprobic mushrooms are cultivated in China, only eight of these make up the lion's share of the market worldwide: the button mushroom (*Agaricus bisporus* and *A. bitorquis*), shiitake (*Lentinula edodes*), oyster mushroom (*Pleurotus* spp.), wood ear (*Auricularia* spp.), straw mushroom (*Volvariella volvacea*), enokitake (*Flammulina velutipes*), white jelly fungus (*Tremella fuciformis*), and nameko (*Pholiota nameko*). The other cultivated saprobic mushrooms are consumed in relatively small quantities, although locally they can be very important. For example, *Hypsizygus marmoreus*, *Hericium* aff. *erinaceus*, and *Grifola frondosa* are important in East Asian countries, and *Stropharia rugosoannulata* is eaten widely in Germany, Hungary, and Poland. Many other saprobic mushrooms are not cultivated at all, and supplies of many are restricted to what can be collected from nature.

Commercial Considerations

The principles of growing many saprobic mushrooms can be found in scientific literature and other published sources, some of which include descriptions of apparently detailed methods. However, there is a significant difference between producing a few mushrooms in a pilot trial and continuously turning out a consistent, high-quality, high-yielding, disease-free product to be sold to a discerning public. Many important factors are discovered only through experience, and these trade secrets are often jealously guarded. Hygiene and climatic controls are crucial to a successful operation, and failure to prevent and control pests and diseases can jeopardize one or more production cycles. Methods developed in one country are rarely directly applicable to another without first making adjustments. Different growth media, pests, diseases, and ambient climatic conditions will affect the productivity of particular strains.

As previously mentioned, people in Asia are accustomed to eating a wide range of mushrooms, whereas people in Australasia, Europe, and North America have only recently begun to acquire a taste for something more exotic. Therefore, careful market research is required to determine if there is a local demand for a new mushroom and, if so, what quantity the market can absorb—and at what price. If mushrooms are to be exported, it is also necessary to determine whether it is possible to produce mushrooms at a price and quality that will compete with those produced in Asian countries such as China, India, Indonesia, Thailand, and the Philippines, where economies of scale and cheap labor allow production costs to be kept low. It is particularly important to consider the Chinese mushroom industry, which employs ten million people, generates $1 billion in exports, and which increased its production from 0.59 million tons in 1986, 26.8 percent of the world's production, to 4.35 million tons in 1998, more than half of the world's requirements (Sun and Xu 1999).

Quarantine restrictions should also be considered, as some countries prohibit the importation of mushrooms that might have been in contact with contaminated soil. Species with pathogenic traits may also be prohibited imports. For example, *Pleurotus ostreatus*, a common species of oyster mushroom cultivated in many parts of the Northern Hemisphere, cannot be imported into New Zealand because it does not occur there naturally and can pose a risk to plant health (Buchanan 1996).

When it comes to mushrooms as familiar as the button mushroom (*Agaricus bisporus* and *A. bitorquis*), there is a wealth of information available on cultivation. Such subjects as the buildings and equipment required, how to prepare a growing medium, where to get the best strains of mushroom for the climate and growing medium, and what pests and diseases are likely to be encountered have all been widely studied (Penn State Mushroom Laboratory 2002). There are societies and research organizations, such as the American Mushroom Institute and the Mushroom Council, that coordinate market analysis, advertising, and research, and that hold educational conferences, farm visits, and training courses. The Penn State University mushroom industry short course has been given annually in Pennsylvania since 1959. There are seminars on the cultivation of specialty mushrooms as well, such as those run by Paul Stamets, founder and president of Fungi Perfecti.

One essential component in commercial mushroom production is the use of high-quality spawn. Spawn is a culture of a fungus used to inoculate the medium on which the mushroom will grow and fruit, called the substrate. It may be purchased from a spawn company or produced using starter cultures and appropriate equipment. Unfortunately it is rarely possible to simply produce a starter culture from a fresh mushroom and then expect to obtain quality spawn. Not just any spawn will do. It must be one produced from a superior strain, selected from the dozens available, and capable of producing the best-quality mushrooms at the best price for the substrate and ambient climate, a task that usually requires a lot of research. During this preliminary research it is also necessary to find out how much latitude is allowable in the control of environmental conditions and substrate. The methods adopted or developed for the cultivation of the mushroom must also be efficient in terms of staff time, energy costs, and materials.



Button mushrooms (*Agaricus bisporus*) growing in plastic bags filled with substrate. Huon Valley Mushrooms, Australia. **EDIBLE.** (Hall)

Core Movements of Part III

Grasping the Chi Ball

Slowly rotate the hands so that your palms face each other in front of your navel.



Fig. 8.58 *Hold the Chi Ball.*



Fig. 8.59 *Stretch and squeeze it.*

Feel the invisible ball of energy between your hands. Allow the energy to push your hands apart keeping the feeling of connection between your palms. When you have less feeling stop the palms and hold it there and reestablish the feeling of the Chi ball.

Let the energy draw your hands back toward each other, like a magnet, until you feel as if you were squeezing and compressing the ball.

Stretch and squeeze the Chi ball three times by opening and closing your palms in this way.



A high standard of hygiene is essential when cultures and spawn are being prepared and when the fungus is first introduced into the substrate. Special items of equipment such as a sterilizing autoclave and a lamina flow cabinet or sterile room are needed to do this. Nevertheless, no matter how much care is taken, there still may be a build-up of pests and diseases, and expertise and special methods must then be used to deal with these problems. For some specialty mushrooms there may be only skeletal published information available, with crucial commercial details treated as trade secrets. Finally, before mushrooms are produced in commercial quantities, the grower must have already made contacts in the marketplace. The mushrooms must then be effectively marketed, packaged to enhance shelf life and appeal, and labelled to comply with food regulations as well as to attract, inform, and educate the consumer.

Agaricus bisporus and *Agaricus bitorquis* (Button Mushroom)

The impetus for developing cultivation techniques may be a mushroom's popularity, but the ease and efficiency with which it can be cultivated, the convenience of the product, and its price are very important. It is for these reasons that more button mushrooms are consumed in the Western world than any other type of mushroom.

Button mushrooms are typically cultivated on a composted medium made up of moistened wheat or barley straw, horse and/or chicken manure, and gypsum (calcium sulfate—plaster of Paris). The raw ingredients are mechanically mixed and brought to a suitable moisture content. Composting material is formed into ricks, also known as windrows, 2–3 m wide and high, or may first be formed into piles before preparation of ricks. Piles and ricks are mechanically turned at regular intervals. Supplements to regulate nitrogen content may be added. On a simple concrete pad this Phase I composting will take more than three weeks, but the speed can be increased, aerobic conditions maintained, and the level of unpleasant odors reduced by introducing air into the composting material through pipes and holes in the concrete pad. During composting, the internal temperature should be 65–80°C.

Traditionally Phase I composting occurs outdoors, but increasingly strict environmental restrictions in many countries are encouraging indoor composting in bunkers. Indoor composting reduces odor emissions and allows environmental conditions to be closely monitored and controlled in order to achieve a more consistent product. Successful production of compost is both an art and a science. Parameters



Mechanical assembly of compost materials for button mushroom (*Agaricus bisporus*) cultivation. Prewetted bales of straw are opened, and straw mixed with poultry manure and gypsum is added from the hopper on the right. Meadow Mushrooms, New Zealand. (Buchanan)



Completion of mechanical assembly. The compost mixture will be placed in piles and ricks (in background) for Phase I composting. Meadow Mushrooms, New Zealand. (Buchanan)



Turning button mushroom (*Agaricus bisporus*) compost. Meadow Mushrooms, New Zealand. (Buchanan)

Air pumped through the concrete floor assists in the preparation of the compost. Meadow Mushrooms, New Zealand. (Buchanan) such as pH, moisture, ammonia, nitrogen, ash, actinomycete concentration, and carbon-nitrogen ratio can be prescribed and measured, but compost quality is often best assessed from experience. This usually involves careful evaluation of odor, appearance, and texture of handfuls extracted from deep within the composted material.

Mushrooms are cultivated on compost in wooden trays, in bags, or on shelves. The compost may be mechanically transferred directly into these containers, followed by pasteurization, or alternatively the compost may be pasteurized and spawned before it is loaded into the growing containers. Pasteurization (also known as Phase II composting) requires temperatures of 50–60°C for five to eight days, during which time an adequate supply of air is essential. In this phase the nutritional status of the substrate is altered to favor growth of the button mushroom and to eliminate potentially contaminating microorganisms and pests.

Spawn is prepared by inoculating sterilized grain with a high-yielding, commercially bred strain of the button mushroom. After cooling the pasteurized compost, spawn is introduced, allowed to colonize for some days, and a layer of casing is applied. A form of spawn known as casing inoculum may be added to the casing layer to improve yield.

In countries where the button mushroom industry is most highly developed, composting, spawn-making, casing, and mushroom production may be performed by separate companies. Compost companies may supply compost ready for pasteurization or compost already spawned. The growing rooms of farms that employ a shelf system, for example, can be rapidly loaded by trucks simultaneously delivering spawned compost and the overlying casing layer. In modern Dutch farms, mechanically harvested mushrooms are grown in large rooms of 1000 sq. m growing surface; smaller rooms with 300 sq. m growing surface are used for hand-harvested mushrooms (J. Janssen, personal communication).

A temperature of 16–20°C with high humidity and low carbon dioxide is required for fruiting, although optimal conditions will vary with each strain used. Mushrooms fruit and are harvested in flushes, six to twelve days apart, with usually three to four flushes per crop. A typical mushroom farm is run on a continuous cycle, with several rooms each at a different stage in the process. Mushrooms are harvested at different stages of maturity to generate products of different appearance (for example, buttons, cups, and flats). Mushrooms to be sold fresh are handpicked, while those to be canned are mechanically



A sophisticated shelving system with automatic watering used for cultivating button mushrooms *(Agaricus bisporus*). Quality Mushrooms, New Zealand. (Buchanan) harvested. Selective breeding has produced a range of commercially available strains, including the firmer Swiss brown strain.

Pests and diseases can be a major problem, not just with button mushrooms but with all cultivated species. Bacterial blotch, viruses, and flies can wipe out a producer's commercial venture (Fletcher et al. 1989).

In industrialized countries, most button mushrooms are produced by large, efficient, and highly mechanized companies. This, in addition to the requirement that mushroom growers meet strict environmental pollution standards, means that small new growers may find it difficult to become established. Nevertheless, a number of publications provide a good introduction to the cultivation of button mushrooms. Due to the scale of production in some parts of the world, the disposal of spent mushroom compost presents a major headache for button mushroom growers. In 1994 a conference was held in Philadelphia where the problems were highlighted (Wuest et al. 1994).

Lentinula edodes (Shiitake)

Cultivation of shiitake originated in China about A.D. 1000, but much of its technological development (and the capture of its marketing

The fruiting bodies of the cultivated Swiss brown strain of *Agaricus bisporus*. Parkvale Mushrooms, New Zealand. **EDIBLE.** (Buchanan)



Shiitake (*Lentinula edodes)* sawdust spawn has been placed in holes drilled into bedlogs and then sealed with wax. Tottori Mycological Institute, Japan. (Buchanan)



Bedlogs inoculated with shiitake and stacked under a canopy of bamboo. Tottori Mycological Institute, Japan. (Buchanan) name) has come from Japan. Although shiitake is primarily consumed as a food, a lot of attention is paid to the medicinal properties of lentinan, a polysaccharide that can be extracted from this fungus (Chang et al. 1993, Mizuno 1995).

The traditional method of growing shiitake—a method that arguably produces the highest-quality product—involves growing it on logs in a shady situation. Just before bud break in spring, logs about 1 m long and 75–150 mm in diameter are cut from trees and carefully dried. Oak (*Quercus*) is traditionally used, but other hardwoods can be substituted. Examples include birch (*Betula*), hornbeams (*Carpinus*), hickory (*Carya*), chickapin (*Castanopsis*), beech (*Fagus* and *Nothofagus*), tanoak (*Lithocarpus*), and poplars (*Populus*) (see also Oei 1996). Once the logs have dried, a netlike pattern of small holes is drilled into the wood. Spawn, prepared by growing the fungus on sawdust or small wooden dowels, is pushed into the holes. These are then sealed over with something like wax to prevent the entry of other fungi and to keep the inoculum from drying out. The inoculated logs are stacked under a forest canopy or in artificial shade, where the temperature is 10–27°C (optimally 20–25°C).

During the six to twelve months following inoculation, the moisture content of the logs is monitored and maintained at 35–55 percent. The fungus grows out from the inoculum and along the log, breaking down the wood and thereby gaining nutrients—a phase called the spawn run. Eventually the fungus forms its fruiting bodies on the sides of the log, but this is usually induced by soaking the logs in cold water. Once the first flush of fruiting bodies has been harvested, the logs are "rested" by maintaining the moisture content at 30–40 percent and the temperature at 15–25°C. When the fungus has accumulated sufficient nutrients, another cycle of fruiting can be induced by again soaking the logs in cold water. Using these techniques, the natural six-month fruiting cycle can be increased in frequency for some strains to four three-month flushes per year. Colonized logs may remain productive for two to five years until decomposition is nearly complete. A maximum yield of about 2 kg of shiitake is possible from a log with an initial fresh weight of about 11 kg (dry weight of 6 kg) (Przybylowicz and Donoghue 1988).

Today most shiitake is produced on sawdust in bags. A typical procedure is to first fill special heat-resistant plastic bags, similar to oven bags, with a mixture of sawdust and supplements (for example, bran). The top of the bag is gathered together and a collar is passed around the outside. The neck is plugged with foam plastic or cotton



Shiitake (*Lentinula edodes*) fruiting on logs that have been artificially inoculated with the fungus. **EDIBLE.** (Buchanan) wool to allow gaseous exchange. The bag and its contents are then heated to 121°C using steam under pressure in an autoclave. When the bag has cooled down, shiitake spawn is inoculated into it through the neck and the plug is replaced, or the spawn is inoculated through holes cut in the sides of the bag, which are later sealed. This has to be done in very clean conditions such as in a lamina flow cabinet. As with logs, it is essential that a strain of shiitake is used that suits both the climatic conditions and the sawdust mix in the bag. The next step is spawn run: the bags are incubated, preferably at about 25°C, on racks for four to fifteen weeks.

During the spawn run the fungus completely colonizes the sawdust mix, which turns white and is referred to as a "block." The collar is removed from the top of the plastic bag, and the bag is either rolled down the sides of the block or removed completely. The exposed surfaces of the block develop a brown outer layer that functions rather like the bark of a log. At this point the temperature of the blocks is reduced either by plunging them into cold water or lowering the air



Auger bag filler commonly used in China. (Tian)

Activate the Outer and Inner Arm Gates

Activate Waiguan Triple Warmer 5 and Neiguan Pericardium 6 - **Right** arm on top. Slowly rotate the arms so that both **palms face down.**

Cross the right wrist over the left wrist with 1 inch of space between the hands. Align PC-6 of the right wrist with TW-5 of the left wrist. Feel the two gates activate each other like metal and magnet drawn to each other. Hold for a 5 to 30 second count.



Fig. 8.60 *Align and activate PC-6 (Right) with TW-5 (Left).*

Keeping the wrists crossed, slowly rotate hands **turning the palms upward**. Now TW-5 of the right wrist will be aligned with PC-6 of the left wrist. Hold and count and feel the points activated. 'Be aware of Tan Tien and Universe'.



Fig. 8.61
Align and activate TW-5 (Right) with PC-6 (Left).



Fig. 8.62 *Feel the Chi Ball and beam energy from LI-4 into the Navel Point.*

Open the Functional Channel with LI-4

Bring the left hand down to the level of the Tan Tien with the Chi Knife facing in. Lower the right hand, palm down and align the eye of the hand, the LI-4 point with your navel. **Feel the Chi ball between your two hands**, and at the same time beam energy from LI-4 into the **navel** point.

temperature. Shiitake fruiting bodies then form on the sides of the block. High carbon dioxide levels inhibit fruiting, and so good ventilation is essential. Light is also required to trigger fruiting, which is perhaps a surprising fact since fungi, unlike green plants, do not require light to produce carbohydrates. Once fruiting has been completed, further harvests can be triggered by allowing the blocks to recover for two to four weeks and then again inducing fruiting. Cultivation procedures that use a shelf system, similar to those for growing button mushrooms, have been developed for shiitake, but they are not popular. Year-round fruiting under ambient conditions can be achieved by using strains that have different temperature requirements at different times of the year.

Size, thickness of the cap, taste, texture, moisture content, and the pattern on the cap contribute to the perceived quality of shiitake fruiting bodies. The highest grade, *hua gu* (Chinese) or *donko* (Japanese), has a pattern of cracks that resembles a flower on the surface of the cap and can command much higher prices than the lower grade, *dong gu*



Steel tanks partly filled with water and heated with a wood fire are used in China to pasteurize loose medium or bags of medium. (Tian)

Heat-resistant bags, filled with sterilized medium and plugged with a cotton bung to prevent the entry of contaminating organisms and pests, partly colonized by shiitake (*Lentinula edodes*). (Buchanan)

(Chinese) or *koshin* (Japanese). While it is possible to grow *hua gu* on sawdust blocks, the more usual method is to grow the fungus on logs, using the traditional techniques. Some growers of shiitake on sawdust-based media will scar the surface of the fruiting bodies when they are at the button stage. When these grow to maturity they have the cracked appearance of *hua gu*, although the texture of the caps usually belies their origin.

Once the last flush of mushrooms has been picked, the grower is left with the spent remains of what was once sawdust. The spent material, like spent button mushroom compost, can be used as a garden mulch. However, Forest Foods Company in Christchurch, New Zealand, developed a novel way of growing shiitake on pine sawdust, of which there is a surfeit in New Zealand, and then using the nitrogen-rich spent material as a stock food (Reddish 1995).

Over the past decade there have been major advances in China in minimizing the cost of producing specialty mushrooms like shiitake. The techniques used by Luo Qi Gin in Zhang Jia Jie, Hunan, are typical of those that can be seen throughout China. Mr. Luo's substrate is made from 1000 kg of cotton husks mixed with a suspension

Lentinula edodes (shiitake) fruiting on sawdust blocks. **EDIBLE.** (Buchanan)

of 2 percent calcium hydroxide, 2 percent calcium sulphate, and 2–5 percent ground rock phosphate in water. The mixture is then covered with clear polyethylene and left in the sun until it reaches pasteurization temperature—about five days. The pasteurized materials (2.5 kg) are then placed in polypropylene bags cut from a roll of tubing. The ends of the tubing are passed through 50-mm rings, the bag folded backward over the outside of the ring, and the open neck covered with newspaper. The bags are then inoculated in three positions along the length of each bag, stacked four to five high in rooms, and incubated at approximately 22–27°C for three to four weeks. Remarkably, contamination is not a significant problem. The bags are then removed and the colonized substrate buried horizontally in a field, leaving only the upper 3–5 cm exposed. Fruiting occurs after two weeks and there are a total of five flushes separated by intervals of two weeks. Alternatively the bags may be incubated in rudimentary shelters where, despite a complete lack of hygiene, yields are remarkably high, typically in the order of 1 kg of fresh mushrooms from each kilogram of fresh substrate. A modification of the above technique is to form the sawdust mix into rectangular blocks and incubate these on shelving similar to those used in *Agaricus* mushroom cultivation.



Shiitake-inoculated bags of medium incubating in a simple shade house in China. (Tian)



Simple huts used in China to incubate bags inoculated with various saprobic mushrooms. (Tian)

Lentinula edodes (shiitake) fruiting on slabs of sawdust medium. **EDIBLE.** (Wang)

Yet another method that has gained great favor in China is to raise shiitake in beds of inoculated media between other crops in a field. A sawdust-based mix is first steamed in a steel vessel for five hours and allowed to cool. Channels are then made in the soil between rows of a crop, lined with polyethylene, and filled with the steamed mixture, after which point the spawn inoculum is added. The polyethylene is folded over the bed, and a protective cover of straw supported on wooden hoops is placed over the bed to prevent overheating by the sun. When the mycelium has completely colonized the substrate, the covers and polyethylene are removed and the beds kept moist to ensure fruiting.

Pleurotus Species (Oyster Mushroom)

The common name "oyster mushroom" refers to several species of edible mushrooms all belonging to the genus *Pleurotus*. These are among the most colorful edible mushrooms, ranging from golden yellow (*P. cornucopiae* var. *citrinopileatus*) and pink (*P. djamor*) to gray (*P. pulmonarius*—phoenix mushroom, also widely but incorrectly called *P. sajor-caju*), bluish gray, cream, and brown. Although many



As the first step in the production of shiitake between rows of maize, steamed sawdust medium is used to fill a polyethylene-lined channel cut in the soil. (Tian)



Next the steamed sawdust medium is inoculated and covered with mats made from rice straw. (Tian)



For the third step, the rice straw mats are removed to reveal the fruiting shiitake. (Tian)



The fruiting bodies of *Pleurotus djamor* (pink oyster mushroom) showing the distinctive color of the gills. **EDIBLE.** (Douglas)



Pleurotus pulmonarius (phoenix mushroom) fruiting on horizontally arranged sawdust blocks. Mushroom Developments, New Zealand. **EDIBLE.** (Johnston)

oyster mushrooms are easy to grow, the same factors as those outlined for shiitake must be considered: strain selection, optimal substrate, climatic conditions, and prevention of pests (especially flies) and diseases.

Fruiting bodies of most oyster mushrooms have a characteristic form, with circular to tongue-shaped or shell-like caps developing from a lateral or eccentric stalk and gills that tend to extend partway down the stalk. Like shiitake and most other specialty mushrooms, oyster mushrooms grow naturally as saprobes on dead wood, although a few species, such as *Pleurotus eryngii* (king oyster mushroom), are parasitic.

Oyster mushrooms can be cultivated on a range of waste materials from forestry and agriculture, including hardwood sawdust, paper, cereal, maize, sugar cane bagasse, and banana leaves. This versatility of substrates and relative ease of cultivation, coupled with the number of oyster mushrooms that are edible, have led to rapid increases in production in recent years. As a result, oyster mushrooms are now second only to button mushrooms in terms of volumes produced.

Although oyster mushrooms may be cultivated on hardwood logs, the most common system involves bags and is similar to that used for shiitake. The bags are filled with moist substrate material and addi-

Lower surface of *Pleurotus pulmonarius* (phoenix mushroom) fruiting on a sterilized mixture of sawdust and other ingredients. Mushroom Developments, New Zealand. **EDIBLE.** (Johnston)

tives, and a collar is placed around the neck, which is plugged to prevent entry of contaminating organisms while still allowing for gaseous exchange. After being sterilized in an autoclave, typically at 121°C, the bags are cooled and inoculated with spawn. During the spawn run the substrate becomes paler as it is colonized by the fungus. Fruiting occurs through perforations cut in the bag or over the exposed surface if part or all of the bag is removed. High carbon dioxide concentrations reduce the size of the caps; consequently, adequate ventilation is essential. Each bag often produces three to four flushes of mushrooms. The bags are rested between flushes and successive fruitings are induced by soaking the bags in water.

A simpler process popular among farmers in China involves pasteurizing the bagged substrate instead of sterilizing it. This is usually carried out in a steel vessel about 1.5 × 1.5 × 1.5 m fitted with a grid toward the bottom. Below the grid is a space for water. Several large mesh boxes containing twenty to thirty bags are placed in the vessel, and a fire is lit underneath it. The water eventually boils, raising the temperature of the bagged substrate above 70°C. After several hours the substrate is pasteurized. However, there is a greater risk of contamination using this technique, and as a result, poorer yields are



Pleurotus ostreatus fruiting on a bagged sawdust-based medium. **EDIBLE.** (Hall)




Mideyebrow
Throat Center
Heart Center
Solar Plexus
Navel Center

Fig. 8.63 *Magnify the Power of the Beam to the Solar Plexus.*

Fig. 8.64 *Activate all the Points.*

Raise the right hand up the Functional Channel, stopping and aligning LI-4 with the **solar plexus**, hold for a 5 to 30 second count and feel the points open and starting to activate each other.



Fig. 8.65
Beam to the Heart Center.



Fig. 8.66
Beam to theThroat



Fig. 8.67
Beam to the Mideyebrow

Continue to move up to the **heart**, **throat** (CV-22) and **mideyebrow** points. Beam energy from the eye of the hand into each of these points and at the same time, continue to feel the Chi ball connection between the two hands.



Pleurotus pulmonarius (phoenix mushroom) fruiting through slits made in the side of a large plastic bag filled with substrate. Huon Valley Mushrooms, Australia. **EDIBLE.** (Hall) achieved. In another technique, pasteurized or sometimes even raw, untreated, or fermented substrate is formed into columns, horizontal or vertical slabs, or loaded into trays and inoculated with the spawn. When the first flush of mushrooms is harvested, the bags or slabs are rested and successive fruitings are induced by soaking them in water. Typically four flushes are harvested.

In contrast to the labor-intensive systems used in China, Japanese production is largely automated and based on unit trays, each containing sixteen wide-mouthed polypropylene bottles fitted with caps containing an air filter. Following sterilization in an autoclave, each bottle is inoculated with spawn inside a clean room. Sterility of the room is ensured by maintaining absolute cleanliness, pumping in filtered air and using ultraviolet germicidal lamps. The bottles are then taken to climatically controlled rooms where they are incubated at a temperature that suits the particular strain being cultivated. *Pleurotus pulmonarius*, for example, typically requires 18–25°C, a high relative humidity (85–95 percent), low carbon dioxide concentration, and moderate light levels. In this species, fruiting is initially induced by dropping the temperature of the bottles to 10–20°C. Species such as *P. ostreatus* and *P. eryngii* fruit best at lower temperatures, typically 15–20°C. Additional details of the cultivation process for several species of oyster mushrooms can be found in the books *Growing Gourmet and Medicinal Mushrooms* (Stamets 2000) and *Mushroom Cultivation with Special Emphasis on Appropriate Techniques for Developing Countries* (Oei 1996), and in a short paper titled “Indoor Cultivation of Paddy Straw Mushroom, *Volvariella volvacea*, in Crates” (Gutierrez Reyes 2000). An extensive literature on oyster mushroom cultivation can also be found in *Edible Mushrooms and Their Cultivation* (Chang and Miles 1989), while details of a simple technique for producing small quantities are described in an article titled “Cultivation of the Oyster Mushroom in Traditional Brick Pots” (Abate 1996).

As some workers may develop an allergic reaction to the massive numbers of airborne spores released by even immature oyster mushrooms, respirators may have to be worn during harvest. Sporeless strains of some species have been developed to reduce this problem.

Oyster mushrooms are sold fresh, canned, or in brine. The shelf life of fresh oyster mushrooms is maximized by picking the mushrooms before they are mature. Most are rather delicate and so are usually prepacked at the factory to prevent damage. Of all species, the robust fruiting bodies of *Pleurotus eryngii* store best. Many believe this species also has the best flavor.

Pleurotus eryngii (king oyster mushroom) fruiting through the necks of plastic bottles filled with a sterilized sawdust medium. **EDIBLE.** (Hall)

Oyster mushrooms are among the most efficient converters of substrate to fungal fruiting bodies among the edible mushrooms. Fresh-weight yields of mushrooms in excess of the dry weight of the substrate can be achieved (expressed as a biological efficiency rating greater than 100 percent). The spent compost is used as an animal feed, as a soil supplement, and as a substrate for the cultivation of other edible fungi such as *Stropharia rugosoannulata*.

Auricularia Species (Wood Ear)

Very different in appearance to a conventional mushroom, the wood ear is thin, rubbery, ear-shaped, and lacks gills. In *Auricularia polytricha* the typically convex upper surface may be covered with whitish hairs, while the concave lower surface, from which spores are produced, is purplish brown. This species has a broad geographic and host range and is commonly seen fruiting on dead wood in the forests of many regions. *Auricularia polytricha* and the related *A. auricula* are widely cultivated, particularly in Asia, and both species have been used in traditional medicine. An aqueous extract (probably adenosine) obtained from *A. polytricha* is thought to have the property of reducing atherosclerosis, while *A. auricula* has been used as a treatment for hemorrhoids.

Spawn for *Auricularia polytricha* is prepared using cereal grains such as millet, rye, and wheat or aged hardwood sawdust amended with rice bran and other supplements. Alternatively, if the mushrooms are to be grown on logs, spawn can be grown on hardwood dowels. Cultivation follows, using a procedure similar to that described for shiitake, with both log and, more recently, bag techniques being common.

Logs 1 m long and about 10–20 cm in diameter of selected hardwood trees, such as *Acacia*, beech (*Fagus*), and mulberry (*Morus*), are cut between late autumn and early spring and inoculated within one week by pushing spawn or dowels into holes drilled into them. The holes are sealed to prevent contamination and to retain moisture. The inoculated logs are then moved to a laying yard, where shade is provided by a natural forest canopy or by artificial shelter. There must be adequate ventilation and a steady temperature. The logs are turned



Auricularia polytricha (wood ear) fruiting on sawdust blocks. **EDIBLE.** (Buchanan) and watered for thirty to forty days. The logs are then transferred to a shaded cropping yard, where they are placed in an almost upright position. Fruiting is induced by raising the humidity to about 85 percent, sometimes after soaking. The optimum temperatures for fruiting are 23–28°C. Successive crops of mushrooms can be harvested from the logs while the temperatures are high. During winter the logs are covered with straw, and in spring fruiting is induced by heavily watering or soaking the logs.

The procedure for cultivating wood ear in bags is similar to that used for shiitake. Substrates include hardwood sawdust, cotton seed hull, sugar cane, corn, and rice straw. The optimum temperatures are 22–30°C during the spawn run and 20–24°C during the fruiting phase. The bags are stood on end and fruiting is induced by cutting small holes in the sides of the bags and raising the humidity to 90–100 percent. Alternatively, the tops and bottoms of the bags are opened and the bags stacked on their sides to form walls. Although fruiting is quicker on bags of sawdust than on logs, typically only three to four flushes are obtained.

Most wood ear continues to be marketed today in dried form, equating to about 10–12 percent of fresh weight, with simple rehydration prior to cooking. The mushroom is better known for its soft, crunchy, somewhat cartilaginous texture than for any distinctive flavor. It is often added to vegetable and meat dishes in Chinese cooking.

Volvariella volvacea (Straw Mushroom)

The straw mushroom derives its name from the fact that in China this fungus was traditionally cultivated on rice straw. The mushroom is adapted to subtropical and tropical climates, with optimal temperatures of 32–36°C for vegetative growth of the mycelium and 28–30°C for fruiting (Chang and Miles 1989). The cultures must also be stored at high temperatures and will die if stored in conventional low-temperature systems.

Spawn can be prepared on a range of materials, including cereal grains, short lengths of rice straw, and cotton waste. Rice straw is a suitable substrate, but in recent times it has been largely superseded by cotton waste from the textile industry. The highest yields are produced indoors, where climatic conditions can be managed, using pasteurized composted substrates. To create the compost, a mixture of cotton waste, lime, and water is fermented outdoors for three to seven days. The composting pile is turned once and protected from

Volvariella volvacea (straw mushroom) fruiting on a bed of cellulosic waste. **EDIBLE.** (Hall)

rain and cold. The compost is then loaded onto shelves in the growing house and pasteurized with steam for two hours at 62°C, followed by eight to sixteen hours at 50–52°C. This is a very important step because inadequate fermentation of the compost and incomplete pasteurization can result in severe nematode infestations. The pasteurized compost is then cooled to about 36–38°C, spawn is introduced, and the inoculated compost is covered with plastic sheeting. Full colonization occurs in three to four days at 32–34°C. The covers are then removed, and the first primordia appear about the fifth day. The first mushrooms are harvested eight to ten days after spawning. Increased aeration and light levels and a slight reduction in temperature and humidity assist initiation and development of fruiting bodies. Generally there is a large first flush of fruiting bodies followed by a smaller second one.

Straw mushrooms may also be cultivated outdoors when ambient temperatures are high enough to support fruiting. Cultivation beds consist of layers of water-soaked bundles of unfermented rice straw, with each layer spawned as it is laid down. The beds are then covered with a layer of rice straw, followed by a sheet of polyethylene. The sheet



Volvariella volvacea (straw mushroom) sectioned to show the cap and stalk forming inside the egg. **EDIBLE.** (Hall)

is removed after four days, after which time the stacks are watered regularly until fruiting ceases. Further details of cultivation procedures can be found in *Edible Mushrooms and Their Cultivation* (Chang and Miles 1989) and *Mushroom Cultivation with Special Emphasis on Appropriate Techniques for Developing Countries* (Oei 1996).

When mature, the mushrooms have a typical stalked appearance, but they are usually harvested when immature and in what is known as the egg stage, with the cap still inside the volva. When fresh, the mushrooms have a shelf life of only three days, so these mushrooms are often canned. Straw mushrooms are frequently used in Chinese cuisine.

Flammulina velutipes (Enokitake)

Enokitake is a common saprobic wood-decay fungus in the forests of many countries. While the mushroom can be cultivated on a small scale, production in countries such as Japan (where it was first commercialized) and Taiwan is now in the hands of a limited number of very large companies, which have adopted fully automated systems. These farms use sterile circulated air, fully climate-controlled

Flammulina velutipes (enokitake) being harvested and automatically weighed in a factory near Hiroshima. (Hall)



Flammulina velutipes (enokitake) fruiting through the necks of bottles of sawdust and other ingredients. Note the clear plastic collar around the neck of each bottle to maintain high carbon dioxide concentrations. Tan Mushrooms, Tai-chung, Taiwan. **EDIBLE.** (Hall)



Flammulina velutipes (enokitake) fruiting in the light through holes in the side of a bag of substrate. Note the difference in the form of the fruiting bodies with those grown in bottles of sawdust. **EDIBLE.** (Cole) environments, conveyor transportation, and automated manipulation of the growing containers.

The mushroom is cultivated on a mixture of aged sawdusts amended with rice bran. In Japan, Japanese red cedar (*Cryptomeria*), cypress (*Chamaecyparis*), and pine (*Pinus*) sawdusts are commonly used. Spawn is also prepared on a mixture of sawdust and rice bran. Wide-necked polypropylene bottles are then filled with the substrate, capped, placed in trays, and autoclaved. After cooling, spawn is introduced through the neck of the bottle and the cap is replaced.

The bottles are incubated at about 18–20°C for twenty to twenty-five days. Just before the fungus has colonized all the substrate, the caps are removed and the surface of the sawdust is mechanically scraped to give a flat, even surface or cone-shaped depression. Fruiting body primordia are initiated by dropping the temperature to 10–12°C and adjusting the humidity to 80–85 percent. The temperature is then further reduced to 3–5°C for three to five days, during which time the stalks begin to elongate. When the stalks are about 2 cm high, the temperature is raised to 5–8°C and the mouth of each bottle is surrounded by a tall, paper or plastic, cylindrical collar. This supports the elongating stalks and raises the carbon dioxide concentration, which reduces the size of the cap to little more than a slightly swollen end on the top of the stalk. The humidity is also reduced to 70–80 percent, and overwatering is avoided in order to produce dry fruiting bodies. When the stalks are 13–14 cm high, the collars are removed and the harvested mushrooms are either sold in 5-kg bags for the wholesalers or 100-g packets for the retail trade. The mushrooms can be grown in tall narrow bags instead of bottles, but in this case the bag is only partially filled with substrate and the open extended mouth is used to support the elongating stalks.

Consumers prefer mushrooms with white stalks and caps rather than the golden wild type, and this has resulted in breeding programs, particularly in Japan, for white strains. These strains dominate the market. Enokitake is sold fresh or canned and is a frequent ingredient in Asian soups and stir-fried meat and vegetable dishes.

Tremella fuciformis (White Jelly Fungus)

Members of the genus *Tremella* are common saprobic wood-decay fungi in the forests of many countries, from tropical to temperate regions. Commercially produced fruiting bodies of the white jelly fungus consist of white to pale yellow convoluted folds of gelatinous

Return down the Functional Channel in the same manner, starting from the mideyebrow and stopping to beam energy into each point.

Next beam into the **throat center, heart center, solar plexus** and finally the **navel**. Hold the Chi ball at the navel with the right hand over the left.

Yin/Yang Palms

Separate the hands and extend them out in front of the body at solar plexus level. The left palm is still pointing up and is yang drawing in the heavenly force through the Laogong point. The right palm is still facing down and is yin drawing in the earth force energy.



***Fig. 8.68** Separate the Hands, one palm facing up and one down - draw in the Forces of Heaven and Earth.*



***Fig. 8.69** Draw in Earth Force.*

Conclude by turning the left palm over to face downward. Draw in the earth force through both palms.

Activate the Chi Ball, Tan Tien and the Original Force

Turn the right palm upward and lower it to the Tan Tien with the Chi knife pointing inwards.

Lower the left palm to the navel, palm down. Lower the left thumb to point toward the right Laogong point. This opens the eye of the left hand (LI-4), pointing it toward the navel.



***Fig. 8.70** Activate the Chi Ball, Tan Tien and the Original Force - Right Hand over left, the 'Large Intestine 4' pointing at the Navel.*



Tremella fuciformis (white jelly fungus) fruiting on a sawdust block. **EDIBLE.** (Buchanan)

Tremella fuciformis (white jelly fungus) drying in the sun in Gutian, Fujian Province, China. **EDIBLE.** (Buchanan) translucent fungal material 8–15 cm across that somewhat resemble a chrysanthemum flower. They were first cultivated on hardwood logs by a method very similar to that used for shiitake, but most are now grown on bagged sawdust or cottonseed hulls.

Unlike the cultivation of other mushrooms, acceptable yields of the white jelly fungus can only be achieved if a companion fungus is grown with it. This fungus degrades the substrate in advance of the white jelly fungus. One companion species that can be used is the ascomycete *Hypoxylon archeri* (Chang and Miles 1989). Spawn production is a specialized procedure. First the slower-growing white jelly fungus is inoculated onto the spawn medium, which consists of sterilized sawdust or bagasse mixed with rice bran, and incubated at 23–25°C. Only when it has become established is the companion fungus introduced. The quality of a spawn is assessed by judging the fruiting bodies that develop on its surface. High-quality spawn is then bulked up for inoculation of the substrate.

Substrates for cultivation include hardwood sawdust (Oei 1996) and cottonseed hulls, along with sources of nitrogen such as corn cobs and wheat bran. These are mixed with gypsum and other ingredients and compressed into long, narrow (perhaps 12 × 55 cm) bags, which are then autoclaved. Spawn is introduced through three to five holes punched in the sides of the bag, which are then resealed with tape. The inoculated bags are incubated at 28–30°C. The temperature is subsequently lowered to 20–25°C and the tape covering the inoculation points lifted to allow gaseous exchange. The first fruiting body primordia appear about sixteen to eighteen days after inoculation. The tape is removed, the inoculation holes enlarged, and the temperature raised to 23–25°C. Once the fruiting bodies have formed, they are covered with newspaper until mature—about thirty-five to forty days after inoculation. In China harvested mushrooms are commonly dried on racks in the sun. Alternatively they can be dried in an oven (first drying the outer surface at about 30°C, followed by higher temperatures to complete the drying process).

Tremella fuciformis has both medicinal and culinary uses. The polysaccharides and steroids it contains reportedly have antitumor and anti-inflammatory properties and also serve as a general tonic. The white jelly fungus can be included in desserts and added to soups and other dishes. Though it has little flavor, the smooth gelatinous texture of this mushroom is appealing to the Asian palate. Other species of *Tremella*, such as the golden ear (*T. aurantia*), are also cultivated in China and used in traditional medicines.



Pholiota nameko (nameko) with caps too mature for Japanese consumers. **EDIBLE.** (Cole)

Pholiota nameko (Nameko)

The small caps of nameko are very popular in Japan. Although the gelatinous surface of the cap sometimes reduces its immediate appeal to Westerners, the slime is not readily apparent once the fruiting body is cooked. The mushroom makes a delicious addition to Japanese soups. Nameko fruits at low temperatures, like enokitake, and is cultivated by a similar procedure (Chang and Miles 1989, Stamets 2000), although Japanese producers usually employ broader-mouthed bottles than those used for enokitake. A range of sawdust substrates has been used, including both hardwood sawdust, such as oak (*Quercus*), and softwoods such as pine (*Pinus*) and Japanese red cedar (*Cryptomeria*), to which is added cereal bran. The fully colonized substrate is subjected to high humidity, low light, and low temperatures (10–15°C) to initiate fruiting. Adequate ventilation is required to lower carbon dioxide concentrations so that the caps develop normally. The production of orange slime on the surface of the substrate often precedes the development of primordia. During maturation of the mushrooms, the temperature is maintained at 13–18°C. In Japan the short-stalked mushrooms are sometimes harvested using scissors as they mature, so that each bottle has to be harvested on more than one occasion. A



Pholiota nameko (nameko) fruiting through wide-necked bottles filled with substrate. Note the partially opened caps required by Japanese consumers. **EDIBLE.** (Buchanan)

second flush can be induced by scraping the substrate surface to expose growing mycelium (Stamets 2000).

Other Species

Several other mushroom species are commercially cultivated in relatively small quantities, often for the production of medicinal products. These include the almond portobello (*Agaricus blazei*), grown as an alternative to button mushrooms (Stamets 2000); several species of *Agrocybe*, which have only recently gained acceptance in the marketplace; bamboo mushroom (*Dictyophora indusiata*), a phalloid mushroom that emerges from an egg and is cultivated mainly in China on bamboo and wood chips outdoors, for both taste and medicinal effects; reishi (*Ganoderma* aff. *lucidum*), a polypore cultivated for its fruiting bodies and their spores; hen of the woods (*Grifola frondosa*), cultivated mainly in Japan; lion's mane mushroom (*Hericium erinaceus*); shimeji (*Hypsizygus marmoreus*), which is popular in Japan and increasingly so in China; *Kuehneromyces mutabilis*, a small, brown, stalked mushroom grown on hardwood pieces in eastern Europe; fat pholiota (*Pholiota adiposa*), cultivated in China; *Pleurotus*

Display of medicinal mushroom products in Hong Kong. (Buchanan)



The fruiting bodies of *Hypsizygus marmoreus* (shimeji) growing in wide-necked plastic bottles. **EDIBLE.** (Buchanan)



Dictyophora indusiata (bamboo mushroom) in its egg stage, fruiting on buried bamboo pieces. **MEDICINAL AND EDIBLE.** (Buchanan)



Mature *Dictyophora indusiata* (bamboo mushroom) fruiting outdoors on buried bamboo pieces. **MEDICINAL AND EDIBLE.** (HortResearch)



Ganoderma aff. *lucidum* (reishi) fruiting on the base of a stump. **MEDICINAL.** (Izawa)



Ganoderma aff. *lucidum* (reishi) cultivation in China on bags of substrate covered with soil. The sheets hanging from the roof are used to collect the more valuable spores. **MEDICINAL.** (Tian)



Ganoderma aff. *lucidum* for sale in Changsha, Hunan, China. **MEDICINAL.** (Hall)



The deformed fruiting bodies of this *Ganoderma* species were produced by growing the mushroom with an elevated level of carbon dioxide. Qi Feng free market, Changsha, Hunan, China. **MEDICINAL.** (Hall)



The large and distinctive fruiting bodies of *Grifola frondosa* (hen of the woods) growing in wide-necked plastic bottles. **EDIBLE.** (Hall)



Trametes versicolor (many-colored polypore) is an extremely variable species. Here it grows on a *Nothofagus* species. **MEDICINAL.** (Buchanan)



The fruiting bodies of *Pholiota adiposa* (fat pholiota) cultivated in China. **EDIBLE.** (Wang)

Open the Functional Channel with the Left Hand



A. **B.** **C.**

***Fig. 8.71 A.** Bring LI4 point up to the Solar Plexus and Heart Center.*
***B.** Then up to the Throat Center.*
***C.** Then up to the Mideyebrow. Descending down the channel in reverse, finishing at the Navel.*

After going up the functional channel come down the channel with the left hand.

Holding a Chi Ball: Open the hands with the palms facing each other holding a Chi ball. Stretch and squeeze the Chi ball a few times in order to feel the Chi as a substance; open and then relax the palms as you squeeze.



***Fig. 8.72** Hold and squeeze the Chi Ball.*



Fig. 8.73
Feel the Chi Ball expanding, growing Bigger.



The fruiting bodies of a white variety of *Trametes versicolor*, clustered on a decaying trunk. **MEDICINAL.** (Wang) *tuber-regium*, a species cultivated not for its fruiting bodies but for the medicinal properties of the sclerotia it produces (Chen and Huang 2001); and many-colored polypore (*Trametes versicolor*), another polypore grown for its medicinal properties.

MYCORRHIZAL MUSHROOMS

Many edible mushrooms are found only in association with the roots of certain trees. In these intimate symbiotic relationships the fungus benefits the growth of the tree by helping with the uptake of essential elements, and the plant provides the fungus with carbohydrates and a place to live. These are the mycorrhizal mushrooms, and among them are some of the most expensive foods in the world.

To understand the high value placed on edible mycorrhizal mushrooms and why attempts to cultivate them have so often proved fruitless, it is useful to understand mycorrhizas and how they function. Many people are surprised to learn that most higher plants, from ferns to flowering plants, do not technically have roots but instead possess mycorrhizas (literally “fungus roots”), the composite structures formed when a mycorrhizal fungus infects the roots of a higher plant (Smith and Read 1997, Mycorrhiza Information Exchange 2002). This relationship generally benefits both the plant and the fungus and is therefore an example of symbiosis. Plants in a few families—the brassicas (Brassicaceae) and nettles (Urticaceae), for example—do not form any type of mycorrhiza, but collectively these amount to only 10–15 percent of all species. Mycorrhizal relationships have existed for a very long time; in fact, mycorrhizas have been reported in 460-million-year-old Ordovician fossils (Redecker et al. 2000, Sanders 2000). Over this long span of time, mycorrhizal fungi have become very specialized so that most cannot survive unless they are in contact with their host plant. Many plants have become equally dependent on mycorrhizal fungi and without them become stunted and yellow—often due to a lack of phosphorus. A lack of these fungi is one reason why some plants, raised in a sterile, soilless potting mix and purchased from a garden center, die when transplanted in the garden (Hall 1988).

The most common mycorrhiza is the vesicular-arbuscular mycorrhiza (VAM), which is formed by almost all agricultural and horticultural plants. In this type, most of the fungus is found inside the root, where the fungus produces small storage organs called vesicles (literally “small bladders”) and arbuscules (literally “little trees”), which are



Dichotomously branched ectomycorrhizas formed by *Lactarius deliciosus* (saffron milk cap). The fine external fungal hyphae can be seen between the roots. (Wang)

well adapted to the transfer of nutrients between the host plant and the fungus. These fungi do not produce mushroom fruiting bodies.

Another mycorrhiza is the type known as an ectomycorrhiza. This is the type of particular interest, because some of the fungi that form ectomycorrhizas produce mushrooms, some of which are edible. An ectomycorrhizal fungus forms a layer of fungal material over the surface of small roots, much like the fingers of a glove. This layer is called the mantle. Short fungal threads, called hyphae, extend from the inner surface of the mantle and grow between the outer layers of root cells, producing a three-dimensional structure called the Hartig net. You can get some idea of the structure of the Hartig net if you imagine that it looks like the mortar between the bricks (equivalent to the outer cells of the root) in a brick chimney. From the outer surface of the mantle, hyphae extend out into the soil. There they absorb nutrients such as phosphorus and nitrogen and pass them back down the hyphae to the mantle, eventually reaching the plant via the Hartig net. The fungus obtains carbohydrates from the plant in return, but the loss is more than offset by the increased plant growth made possible by improved access to nutrients.

Host plants for ectomycorrhizal fungi include birches (Betulaceae), oaks and beeches (Fagaceae), eucalypts (Myrtaceae), pines and spruces (Pinaceae), poplars and willows (Salicaceae), rock roses (Cistaceae), and dipterocarps (Dipterocarpaceae) (Becker 1983, Smith and Read 1997). Edible ectomycorrhizal mushrooms are never found associated with, for example, horse chestnuts (Hippocastanaceae), maples (Aceraceae), and apples, apricots, or peaches (Rosaceae), since all of these form vesicular-arbuscular mycorrhizas. Because of the importance of ectomycorrhizal trees in most of the world's forests, it is unusual to find areas where there are no ectomycorrhizal fungi. But there are a few exceptions. For example, all but a handful of New Zealand's native plants form vesicular-arbuscular mycorrhizas. Consequently, ectomycorrhizal fungi, which are dependent on their host plants for survival, are generally restricted to those areas where their southern beech (*Nothofagus*) and tea tree (*Leptospermum* and *Kunzea*) host plants are found (Johnson 1977). Moreover, forests in many areas of the tropics are predominantly composed of vesicular-arbuscular mycorrhizal trees.

Because of the importance of mycorrhizas and the fungi that produce them, more than ten thousand specialist scientific publications deal with the subject. Some of these provide good summaries of the salient points. The Mycorrhiza Information Exchange Web page is a good place to start, while *Mycorrhizal Symbiosis* (Smith and Read 1997) is an excellent book for those wanting a more in-depth treatment.

Commercial Considerations

Mycorrhizal mushrooms are renowned for the flavors they impart to meals, but also for the high prices some of them command—up to $30,000 per kilogram. Compared with their saprobic cousins, the market in dollar terms is disproportionately higher than the relatively small quantities that are harvested. Since only a handful have ever been cultivated commercially, the chef and gourmet have to rely on professional or amateur collectors harvesting the mushrooms from the wild during the few months that they fruit.

Just what quantities are in fact harvested is unknown. Estimates that have been made are very approximate, with official statistics probably containing some gross errors. One reason for this is that many mycorrhizal mushrooms are sold under the counter so that the picker and purchaser can avoid paying taxes. Many more are taken home after a day's collecting without ever passing through a market.

Portia Barnes, one of a small number of competent wild mushroom collectors in Victoria, Australia, with a basket of grade-one *Lactarius deliciosus* (saffron milk cap). **EDIBLE.** (Hall)



Tuber melanosporum (Périgord black truffle) production in Quercy, France, since 1920 (Fauconnet and Delher 1998).

However, there is mounting concern that the quantities of mycorrhizal mushrooms that can be harvested are declining. While articles with titles like "Disappearing Mushrooms: Another Mass Extinction?" (Cherfas 1991) are somewhat alarmist, it is undeniable that there have been catastrophic declines in the harvest of some mycorrhizal mushrooms over the past hundred years. For example, at the beginning of the twentieth century production of the Périgord black truffle is estimated to have been 1000–2000 tons, but modern production, even in a good year, is often less than 10 percent of this. Forty tons is considered a bad year, 150 tons a good one (Lefevre and Hall 2001, Olivier 2000). The official figures for truffle production for Quercy, France, illustrate this trend well, as do those for matsutake harvests in Japan.

Many suggestions have been advanced to explain the decline. Very likely causes are deforestation and the establishment of plantation forests with trees that are poor hosts or that are planted much closer together than occur in natural forests. Other possibilities include compaction of the soil by hordes of pickers; acid rain that can make a soil too acid for either the mycorrhizal fungus or its host plant; global warming that has gradually made climatic conditions unsuitable for the fungus or host; the loss, during two world wars, of many of the people with knowledge of where and how to harvest mushrooms (particularly so with species such as truffles that fruit underground); the underreporting of harvests by those reluctant to pay taxes; and younger generations being more inclined to spend their



Tricholoma matsutake (matsutake) production in Japan since 1915 (Wang et al. 1997, Japan External Trade Organization 2000a, 2000b).

time behind a computer in an office than wandering around chilly forests at daybreak searching for an unpredictable income (Ciani et al. 1992, Olivier 2000).

Pickers may also be picking mycorrhizal mushrooms when they are still too small, knowing that if they leave them until the following morning to grow to a reasonable size someone else may get there first. An example of what happens when wild mushroom mania strikes comes from Christchurch, New Zealand, in the 1990s. Hagley Park in Christchurch was established in the 1850s with oaks from England that were brought out by some of the first "official" European settlers. It seems likely that around the same time these oaks were introduced porcini (*Boletus edulis*) also arrived, probably on the roots of the same trees. Until 1993 porcini was quietly harvested in Hagley Park by a few Europeans who knew what they were harvesting and did not intend to tell anyone else about it. Across town, on the Canterbury University campus, porcini was meeting a more ignominious fate as periodic mowing delivered shredded porcini to the compost heap. Then in 1993 an observant gardener on the university campus decided to take a couple of the fruiting bodies to Tony Cole for identification. This in turn led to exposure on television and in newspapers and scientific articles, all heralding the find. Since that time there have been dozens of collectors, rather than a few keen amateurs, and the fruiting bodies have been collected almost as soon as they show themselves above the ground. One picker even admitted going out hunting with a torch early in the morning just to make sure he found a few for his breakfast. As a consequence, the weight of porcini now harvested in Christchurch is quite probably lower today than it was in the 1980s.

The edible ectomycorrhizal mushrooms held in the highest regard are the Périgord black truffle (*Tuber melanosporum*), Italian white truffle (*Tuber magnatum*), porcini (*Boletus edulis*), chanterelle (*Cantharellus cibarius*), and matsutake (*Tricholoma matsutake*). However, Caesar's mushroom (*Amanita caesarea*), honshimeji (*Lyophyllum shimeji*), Burgundy truffle (*Tuber uncinatum*), Oregon white truffle (*Tuber gibbosum*), saffron milk cap (*Lactarius deliciosus*), shoro (*Rhizopogon rubescens*), and many other mushrooms are also very popular in some countries.

Because of the general decline in the harvest of many edible mycorrhizal mushrooms, prices have been steadily climbing, particularly since the 1980s. However, the price of the Italian white truffle outshines all others, with retail prices increasing fourfold from around $1000 per kilogram in 1995 to $4000 per kilogram in 1999 (Anonymous 2000a). By 2000, retail prices had jumped to $5680 per kilogram in Milano, with $13,243 per kilogram paid for a 497-g specimen at the Alba Truffle Festival (Johnston 2000). The prices of the next two most expensive species of mycorrhizal mushrooms are trivial by comparison, with Périgord black truffles produced in New Zealand and out of season to the Northern Hemisphere managing only $1450 per kilogram, about twice the 1999–2000 in-season price. It is to be wondered what price Italian white truffles would fetch if they too were produced out of season in New Zealand!

Cultivation Techniques

The earliest cultivation of an edible ectomycorrhizal mushroom was achieved by Joseph Talon in the early 1800s in France (Hall et al. 1994). He found, probably accidentally, that if he transplanted oak seedlings from the rooting zones of trees that produced Périgord black truffles, eventually the transplants would also produce truffles. Despite its lack of sophistication, Talon's technique was widely used for 150 years. A similar technique has been used in Japan to produce plants infected with *Lyophyllum shimeji* (Fujita et al. 1990).

The main drawback with Talon's technique is that seedlings are exposed to infection by all organisms in the rooting zone of the parent tree and, consequently, may become contaminated by pathogenic fungi, nematodes, and insect pests, as well as faster-growing competing ectomycorrhizal fungi that do not produce edible mushrooms. However, in the late 1970s, after much research, French and Italian scientists developed techniques that subsequently led to routine greenhouse practice for infecting plants with various species of truffles. Scientists have also had limited success infecting plants with other types of edible mycorrhizal mushrooms, including Caesar's mushroom (*Amanita caesarea*), porcini (*Boletus edulis*), chanterelle (*Cantharellus cibarius*), saffron milk cap (*Lactarius deliciosus*), dotted-stalk bolete (*Suillus granulatus*), Jersey cow bolete (*Suillus bovinus*), shoro (*Rhizopogon rubescens*), and matsutake (*Tricholoma matsutake*).

Currently only a few species of *Tuber*, including the Périgord black truffle, Italian white truffle, and Burgundy truffle, have been produced in commercial quantities in plantations, although fruiting bodies of saffron milk cap and dotted-stalk bolete have formed in experimental plantations. This situation has partly arisen because effective techniques for infecting plants with many edible ectomycorrhizal mushrooms have yet to be devised. Also, research has not yet identified the climate and soil biological and physiochemical conditions most edible ectomycorrhizal mushrooms require, both to proliferate and fruit. Publications consolidating this type of information have only recently begun to appear.

Tuber melanosporum (Périgord Black Truffle)

Although the cultivation of the Périgord black truffle is still an inexact science, this truffle has been cultivated for much longer than any other ectomycorrhizal fungus. As a result, Périgord black truffle truffières now cover thousands of hectares in Europe (Pacioni and Comandini 2000). The cultivation of this truffle is covered in some detail in books in English, French, Italian, and Spanish, but as it provides such a useful template for other edible mycorrhizal mushrooms, the most important points are included here. Périgord black truffle cultivation is also encouraged by governments in several countries as an alternative source of income to conventional agriculture (Colinas et al. 1999, Olivier 2000).

Production of infected plants

Although Talon's technique is still used by some Périgord black truffle growers, their plants are often heavily contaminated with fast-growing and aggressive contaminants such as *Scleroderma* species

(Hall et al. 1994). Consequently, greenhouse techniques predominate. Many trees will host the Périgord black truffle, but hazel (*Corylus avellana*) is most commonly used because it can be grown relatively easily, it forms many fine roots that are readily converted to mycorrhizas by the fungus (Chevalier 1998), and it commonly produces truffles several years earlier than other host plants (Giovanetti et al. 1994, Hall et al. 1994). Other host plants include Mediterranean hazel (*C. colurna* and *C. heterophylla*), various species of oak (*Quercus*), and hop hornbeam (*Ostya carpinifolia*), which are produced by, among others, Agri Truffe in France and the New Zealand Institute for Crop and Food Research (Chevalier 1998, Craddock 1994, Hall et al. 1994, Lefevre and Hall 2001).

Unfortunately, some producers of infected plants make no distinction between inoculated and infected states. "Inoculated" merely means that the fungus has been introduced to the plant. However, unless the fungus also produces a good infection on the plant's roots, mushroom production will not occur. Completely uninfected plants

Soil-covered *Tuber melanosporum* (Périgord black truffles) for sale in a French marketplace. Bottled truffles are displayed on one side of the table and silver truffle shavers are on the display stand. **EDIBLE.** (Hall)

Double Palm and Double Beam - Palm to Palm
Activate the Functional and Governor Channels - Right Palm on Left

Bring the left palm in first to face the navel, about 1 inch away, aligning the Laogong point with the navel. Follow by bringing the right hand in front of the left hand, **aligning the Laogong of the right palm with the Laogong of the left hand and the navel**. Both palms are now facing in. Beam energy through both Laogong points to the **navel and through the body to the Door of Life**, between L-2 and L-3 (Lumbar Vertebrae). Hold for a 5 to 30 second count and feel the vibration of the palms and Chi beam penetrate through the two points; feel them link together.



Fig. 8.74
Left Palm to Navel.



Fig. 8.75
Right on Top.



Fig. 8.76
Beam from Navel to Door of Life.

Next raise the left palm up to the solar plexus, aligning the Laogong point with the solar plexus.

Follow with the right palm aligning the Laogong to the left palm. Beam energy into the **solar plexus point and through the body to the T-11 point (thoracic vertebrae)**.



Fig. 8.77
Raise Left Palm to Solar Plexus.



Fig. 8.78 *Follow with the Right Hand to form the Double Beam.*

are rare, but it is not unusual to find the roots of commercially produced plants only partly infected with the Périgord black truffle and the remainder infected with competing ectomycorrhizal fungi. Some commercial producers of truffle-infected plants assume that when their plants are placed in ideal sites any contaminating competing fungi on the roots will eventually die out, but there is little justification for this belief.

Although the inoculation procedure is an important step in producing plants infected with Périgord black truffles, the critical phase is the subsequent six to twenty-four month incubation period. During this time, incorrect watering, air or soil temperatures, light levels, soil pH, nutrient concentrations in the potting medium, and, not least, contaminating ectomycorrhizal fungi, can all upset the infection process. Saprobic fungi may also cause problems, sometimes forming a loose weft of hyphae around the host plant's uninfected root tips, perhaps attracted by sugars leaking out. This presents a significant barrier to infection by the Périgord black truffle. Inoculated plants can also become contaminated with major pathogens. For this reason, plants infected with the Périgord black truffle that are produced in Europe cannot be imported into Australia, North America, New Zealand, or South Africa unless treated with chemicals that render them useless. In some cases infected plants have been smuggled into countries via a back door with no regard to the devastation a major pathogen riding piggyback on the host plants might have on a country's forests and plantation forest industry. Needless to say, the penalties these people face if caught are significant.

Soils and climate

It is critical that infected plants are placed in areas where the ecological conditions suit both the host plant and its fungal partner. In France, Italy, and Spain extensive surveys have determined where the ideal truffle-growing areas are located. These have well-aerated, well-drained, alkaline soils rich in calcium carbonate and with a carbon-nitrogen ratio of about 10:1, and they experience warm summers and cool winters. In Europe these areas are found to the west, south, and east of the Massif Central in France, in the southwest corner of France, northeastern Spain, and northern Italy (Hall et al. 1994). Somewhat surprisingly, of the eight productive Périgord black truffle truffières outside Europe, all but one have been established on naturally acidic soils that have been limed so that the pH is closer to the pH 7.9 optimum for the Périgord black truffle.



The main areas in which *Tuber melanosporum* (Périgord black truffle) can be found in Europe.

Planting and maintenance

A wide range of planting arrangements has been suggested by researchers (Hall et al. 1994). They usually recommend an alternating arrangement of several species of host plants, as one might be better suited to the ecological conditions than another, and as some species, like hazels, may produce early in the life of a truffière while others, like oaks, may start producing later but continue for longer. Planting two or more host species, such as hazels and oaks, also affords some protection against pathogens, which are unlikely to affect dissimilar species.

While expensive, artificial windbreaks have been used in some truffières. This involves surrounding the young trees with protectors such as Tree Guards, strong plastic tubes 10–15 cm across and 60–100 cm high. These are usually successful in preventing desiccation and damage by wind and browsing animals, at least for the first year or two. After planting, irrigation is often necessary to prevent plant death. Careful aeration of the ground in spring, particularly in areas where the soil has a poor structure, is also important in assisting spread of the truffle fungus and producing large, well-formed truffles (Lefevre and Hall 2001).



A young hazel (*Corylus avellana*) seedling infected with *Tuber melanosporum* (Périgord black truffle) grows in a rendzina soil rich in limestone. The seedling is protected from wind and browsing animals by a Tree Guard protector. (Hall)

Once fruiting starts, perhaps ten years after planting, soil moisture must again be maintained, particularly from midsummer onward, to ensure that young truffles do not die. The trees are usually pruned to a cone shape (with the point downward) to ensure that the soil is heated sufficiently by the sun in spring and autumn and protected from losing too much moisture during the heat of the day in summer. Laying branches on the soil around the trees and adding various mulches have also been used as ways to conserve moisture. The ancient French adage "Water in July, truffles at Christmas" clearly embodies an understanding of the importance of soil moisture.

Plant health is critical to successful truffle growing. In Europe, the pests and diseases of host trees cause major problems, and books have been published offering advice on how to control them (for example, Sourzat 1994). Iron deficiency in plants growing on very alkaline soils can cause yellowing of leaves and, in severe cases, death, with oaks more susceptible than hazels. This condition can be treated by placing chelated iron, such as Ferri-Chel Microgranular, in the rooting zone. Alternatively, a solution of chelated iron, such as Sprint 138, can be sprayed onto the foliage from bud break onward, with repeat sprayings every ten to fourteen days. Weeds around the trees can be treated with various herbicides, but Roundup has been used most frequently. The very poisonous desiccant herbicide Paraquat has also been used in the past, but Buster is a much safer option.

Harvesting

Once the fungus has become well established around its host tree, it kills many of the weeds in the rooting zone, leaving bare areas around the truffle-infected trees. In France this area is called the brûlé, and its development is said to herald the start of truffle production. Prior to the formation of the brûlé, weed control is often done by hand to avoid root damage, but in large truffières machinery or the careful application of herbicides is essential. In France once the brûlé has developed the truffière can be intensively managed with spring tilling, tree pruning, and irrigation, which, in combination, lead to early fruiting. This system is called the Pallier method (Chevalier 1998) and the techniques are similar to those used in New Zealand (Hall et al. 1994). The alternative is the Tanguy method, in which mowing replaces tilling and trees are left unpruned. In France the additional costs associated with the Pallier method have been estimated to be the equivalent of 8 kg of truffle per hectare (Olivier 2000). The cost is likely to be smaller in Southern Hemisphere countries because of the



Two closely planted oaks (*Quercus*) infected with *Tuber melanosporum* (Périgord black truffle). Notice the strong brûlé. (Hall)

Truffle hunters often take their dogs out early in the morning when there are few people about. A thin, long-handled trowel is used to unearth the truffle after the truffle dog has located it. (Hall)

higher returns from the sale of truffles, which are out of season to the Northern Hemisphere harvest.

Unlike most edible mycorrhizal mushrooms that form above the ground, black, rough-walled, potato-like Périgord black truffles are formed just at the soil surface or below ground. Finding them can, therefore, be a bit of a problem. One way is to get down on hands and knees and sniff them out. However, using this method, the owner of even a modest-sized truffière would probably spend more on trousers than could ever be made from collecting truffles. Another technique, developed out of desperation by a dogless New Zealand owner of a productive truffière, was to walk around in bare feet. Because the soil did not contain any stones, she reasoned that a hard spot under the soil surface represented a truffle. She then went down onto her hands and knees and sniffed to confirm whether the truffle was ripe or not before claiming her prize. What is really needed, however, is a more mobile nose—preferably one much more sensitive than that of a human. The traditional solution is a female pig, which has not only a nose even better than a dog's but also a natural yearning for truffles.

To select a pig, simply walk into a litter of piglets with a truffle in your hand, or tucked into your sock, and buy the one that shows the most interest. Train the piglet to walk on a lead. When she finds a truffle, persuade her that a piece of turnip, bread, or cheese is a fair swap—a bargain that may have to be reinforced with a couple of prods with a sharp stick. With piglets this is perhaps not too difficult, but it can pose something of a problem when the piglet grows to twice your own weight and does not discriminate between truffles and fingers. Consequently the majority of truffle hunters now use specially trained dogs, which, incidentally, fit better on the back seat of a car and are a bit less obvious when taken truffle poaching.

Yields

Under ideal conditions Périgord black truffle production can begin three years after inoculated trees are planted (Giovanetti and Fontana 1982), but generally the owner of a truffière will have to wait five to ten years or more before the first, often elusive, truffle is found. In artificial truffières, yields are often considerably higher than the 10 kg per hectare that might be expected from a forest that naturally produces Périgord black truffles. Yields in excess of 40 kg per hectare are infrequent, primarily because contaminating fungi often partially or completely occupy the roots of many of the trees (Chevalier 1998, Hall et al. 1994). However, several eleven- to fourteen-year-old French truffières have produced up to 150 kg per hectare (Chevalier 1998).

A truffle is just an elegant bag of spores, so those not eaten by a pig, dog, or human are not wasted: they eventually rot in the ground, release their spores, and await the arrival of a root from the right host plant. Similarly, the spores in truffles that were eaten by a pig will eventually find their way back to a well-manured patch of soil, probably some distance from the original host, where they may wait, perhaps for years, until conditions are right for germination.

Cultivation outside Europe

In the early 1980s many truffières were established in the United States using plants that were imported from Agri Truffe in France (Picart 1980). While truffles have never been harvested from the vast majority of these truffières and many have now fallen into disrepair, one near Ukiah in northern California began producing Périgord black truffles around 1988 (B. Hatch, personal communication). Truffles were also found in a truffière on Franklin Garland's property near Hillsborough, North Carolina, in 1993, when a group of students was

Oakland Truffière, near Gisborne, New Zealand, where the first Périgord black truffles were harvested in the Southern Hemisphere. Note the strong brûlés around the trees. (Hall)

casually invited to have a look for themselves (F. Garland, personal communication).

The first attempts to produce the Périgord black truffle in the Southern Hemisphere for out-of-season Northern Hemisphere markets began in New Zealand in the mid 1980s when English oak and hazel seedlings were infected with the fungus. Fortunately these experiments were successful, and the first truffières were established in 1987 (Hall et al. 1994). Oakland Truffière, near Gisborne on the east coast of the North Island, produced a few small truffles in 1993, some five years after planting. Disaster then appeared to have struck when *Tuber maculatum* and *T. dryophilum*, two less desirable truffle species, seemed to have taken over the 0.5-hectare truffière and began producing more than 100 kg of their own truffles each year. However, a new management regime was implemented, and between May and August 1997, 9 kg of Périgord black truffles were harvested, some weighing more than 1 kg. This was the first commercial harvest of a cultivated ectomycorrhizal mushroom in the Southern Hemisphere and the successful culmination of more than a decade of research. Since then, harvests have gradually increased, and although the owner of Oakland Truffière is a little reluctant to say just how much of the delicacy he is now harvesting, it is in excess of 40 kg per hectare. In 2000, three other New Zealand truffières and two Tasmanian truffières (Anonymous 2000b) between the latitudes 39°S and 43°S also began producing.

Sources of advice for growers

Throughout France and Italy, truffle societies hold parades during the truffle season and competitions are held to find the best truffle dog, which may later be offered for sale for perhaps more than $1000. Workshops and visits to truffières provide an important forum for the exchange of information between growers and scientists. Helpful periodicals such as *Le Trufficulteur Français* and *Tartufomania* are also available, while articles in popular horticultural and agricultural magazines review important topics such as choice of soil, size of harvests, and marketing (Garcia-Falces and De Miguel Velasco 1995a, Primavera 1995, Urbani 1995). Not surprisingly, elsewhere in the world similar associations are few and far between, although there is the North American Truffling Society, the New Zealand Truffle Association, and the fledgling Australian Truffle Association. Details on periodicals and societies are listed at the back of the book.

Forestry Plantations

The owners of plantation forests receive almost no income during the life of a forestry plantation, apart from the sale of small amounts of timber from thinnings. They must carry the cost of establishing the plantation, plus interest charges, for twenty-five years or more before seeing a return on their investment. In many countries this has meant that only species with relatively short rotations are planted, while species with rotations longer than seventy years have been largely ignored, even though they may produce timber with superior characteristics.

Wild mushrooms are harvested from forests in many countries where their collection and sale are significant industries. For example, in 1992 the forests of Idaho, Oregon, and Washington in the United States yielded $41 million worth of wild mushrooms (Schlosser and Blatner 1995, Thomas and Schumann 1993). The edible mushrooms in these forests are there because they were either in the soil when a plantation was established or were acquired from the nursery soil where seedlings were raised. It is the exploitation of this second possibility that has excited scientists in a number of countries, including

New Zealand (Hall and Wang 1996), Sweden (Danell 1994), and England (Hall and Wang 2000).

Very expensive mycorrhizal mushrooms, like the Périgord black truffle, Italian white truffle, Caesar's mushroom, and matsutake, warrant the expense of establishing plantations dedicated to their production (Hall et al. 1994, Hall, Zambonelli et al. 1998). Because of the high costs and the not inconsiderable risks involved, it is questionable whether there is sufficient economic justification for setting up specialized plantations dedicated to the production of mushrooms with relatively low prices, such as porcini and saffron milk cap. An alternative is to produce these lower-priced mushrooms as secondary crops in plantation forests (Hall and Wang 2000).

Southern Hemisphere

All the main edible ectomycorrhizal mushrooms of commerce are native to the Northern Hemisphere. Only a few of these—for example, porcini (Hall, Lyon et al. 1998, Marais and Kotzé 1977, Van der Westhuizen 1983), saffron milk cap, and shoro—have made the accidental journey to the Southern Hemisphere. This probably occurred on the roots of small deciduous trees that some of the early European settlers of Australia, New Zealand, and South Africa took with them as reminders of the land of their birth. Perhaps if more of the early settlers had been French or Italian instead of British, delicacies like the chanterelle, Périgord black truffle, and Italian white truffle would already be established in these countries.

Because most edible ectomycorrhizal mushrooms of commerce are available fresh only in the Northern Hemisphere for the short periods during the year in which they fruit, the chef, the gourmet, and those who would like to include one of these mushrooms in a favorite dish out of season are reliant on preserved specimens. There is, therefore, a golden opportunity to produce these fungi, such as the Périgord black truffle, in Southern Hemisphere countries in order to satisfy out-of-season demand in Northern Hemisphere markets.

Continue in the same way with the left hand leading to the **heart point and wing point,** the **throat point and C-7 (cervical vertebrae)**, the **mideyebrow point and Jade Pillow**, and the **crown point and perineum**. **Always remember 'Tan Tien and the universe'.**



Fig. 8.79 *Beam into the Heart Center and to the back of the Heart.*



Fig. 8.80 *Beam into the Throat Center and to C7.*

When you reach the crown lightly spiral the palms and feel the Chi slowly penetrate deep into the body reaching the perineum; this will also open the **Thrusting Channels.** This might take a longer time, try a 30 to 60 second count.



Fig. 8.81 *Beam into the Mideyebrow to the base of the Stall.*



Fig. 8.82 *Beam from the Crown down to the Perineum.*

COLLECTING WILD MUSHROOMS

This page intentionally left blank

Throughout continental Europe the arrival of autumn brings with it some unusual sights and seemingly bizarre behavior. For example, in France, Germany, and Italy, lines of empty cars can be seen parked next to what might seem rather unprepossessing areas of woodland. Inside these forests are people with their heads bent down, apparently wandering about aimlessly. Occasionally they pick up a mushroom, carefully inspect and smell it, and then perhaps nibble a corner before either spitting it out and tossing the mushroom aside or consigning it to their basket. People with truffle dogs or truffle pigs are much less likely to be seen. They tend to do their hunting in secret, keeping the location of valuable truffle beds to themselves.

Individuals have a right to pick mushrooms in state-owned forests in many countries, but in Europe and parts of North America and Asia the pursuit is so popular and the number of collectors so great that soil disturbance and compaction have reduced the productivity of some wild mushrooms (Cherfas 1991, Palm and Chapela 1997, Pilz et al. 1999). It is not unusual to see busloads of Italian day-trippers with packed lunches crossing the border to pick mushrooms in the relatively well-stocked Austrian forests, much to the chagrin of many Austrians.

Not every year is a good fruiting year for wild mushrooms. A warm, moist summer followed by a cooler, moist autumn often produces the best fruitings. Some autumns in eastern North America may produce tons of field mushrooms where there were none the year before. Similarly, in New Zealand during a good year it is possible to walk into a forest of Monterey pine (*Pinus radiata*) and see a carpet of slippery jacks and fly agarics. But if a dry autumn follows a hot, dry summer and frosts precede winter rains, most autumn-fruiting mushrooms will not fruit at all, although if the following year is favorable there often seem to be bumper harvests.

When and Where to Look

Learning where a particular mushroom might be expected to appear is the first step to finding it. Each species has its own special ecological niche and occurs only in certain habitats. Knowing what and where these are will eventually save a great deal of futile searching. For example, the fruiting bodies of ectomycorrhizal fungi will only be found associated with those plants that form this type of association, such as beech, birch, fir, oak, pine, spruce, and eucalyptus. Consequently you would not expect to find the fruiting bodies of such fungi as *Amanita* and *Russula* in a forest that does not contain at least some ectomycorrhiza-forming trees.

Fungi are the major group of organisms responsible for wood decay, and the species involved represent a special group. Some of these fungi are generalists and can decompose a wide range of different types of woody substrates, but others are limited to one or a few types. For example, some wood-decay fungi are found only on the wood of conifers, while others are almost invariably associated with wood from broadleaf trees. In the same way, the dead leaves that fall to the forest floor do not continue to pile up year after year because various litter-decomposing fungi break them down. These fungi are not the same species as those found on wood—an unsurprising fact, since the two different types of substrates, wood and litter, are quite dissimilar in terms of their physical and chemical properties.

Another habitat exploited by certain fungi is dung, and many of the species involved are never found anywhere else. Such is the case for a number of species in the genus *Coprinus*. Being aware of such ecological relationships increases the chances of both finding fruiting bodies of the fungus in question and making a positive identification.

In good textbooks on mushrooms, a brief description of each species' habitat is usually provided. The starting point when identifying a mushroom is to take careful note of where it was found, such as on the surface of soil, below ground, or in association with a particular substrate. Noting details of the vegetation, especially of any trees growing nearby, is particularly relevant for ectomycorrhizal species. The amount of limestone in the soil (seen as white or off-white pebbles or flecks), the elevation, how wet the soil is, and other features of the site may also be important. If a mushroom is found on dead wood or a living tree, make a note of the host plant and on what part of the plant the mushroom is fruiting.

When collecting wild mushrooms, it is best to store them in paper bags or a basket. Mushrooms sweat inside plastic bags and, as a result, decay rapidly. A small cooler containing a few freezer pads wrapped in a towel makes a good temporary refrigerator until you can get the mushrooms home. An article in *The Observer* (Slater 2000) stating that "mushrooms should [be kept] in a bag in the fridge for a day or so, so that they become a bit damp and woodsy" is certainly a risky procedure for wild mushrooms and not to be recommended.

In many parts of the world people have traditionally climbed over a fence to pick mushrooms from a farmer's field. However, this is little different from the same farmer walking into your garden and taking one of your cabbages, so make sure you have the permission of a landowner first. The situation on publicly owned land varies from country to country. In some cases you will have to obtain a permit from a government authority to pick mushrooms, whereas in many European countries the general population has a right to do so.

Identifying Wild Mushrooms

Having recorded details of a mushroom's habitat, the next step is to note its distinguishing features. Key factors include colors, dimensions, and whether the underside of the mushroom is covered with gills, spines, or a system of tubes that makes the underside look like a finely textured sponge. If gills are present, details such as whether they are attached or free from the stalk, or extend down the stalk, their color, and thickness are important. Two very important details are whether the stalk has a ring and a volva. Sometimes the volva is below the soil surface and can easily be missed if the base of the stalk is not carefully excavated. Rings may only be present on very young stalks, so it is important to collect both younger and older fruiting bodies.

The next step is to prepare a spore print. The best way to do this is to get a sheet of smooth black paper and a sheet of white paper, overlapping the two. Cut the stalk off the mushroom and place the cap, gills downward, half on the white paper and half on the black paper. The mushroom should then be covered in order to retain moisture and keep air currents from blowing the spores around. Half a glass petri dish will work well, allowing you to see what is going on inside it (a glass casserole dish lid will work too, but wash it carefully afterward in case the mushrooms are poisonous). After six to twenty-four hours,



A spore print being prepared from the cap of a Swiss brown strain button mushroom (*Agaricus bisporus*). (Hall)

sufficient spores will be released from the cap and deposited on the paper to determine their color. In many cases, placing the mushroom in a small, sealed plastic bag will also work. White and other light-colored spores, of course, show up better on the black paper, while dark-colored spores are better seen on the white paper. Eventually, as experience is gained, either the black or white paper may be omitted.

One way to identify a wild mushroom is to obtain a comprehensive, well-illustrated guide to the mushrooms that grow in your area, something you can flick through to locate the illustration that looks most like your specimen. A word of warning, however: some fungal genera contain mushrooms with very different effects. *Amanita*, for example, includes Caesar's mushroom (*A. caesarea*), which is not only edible but also quite delicious; false death cap (*A. citrina*), which can produce unpleasant vomiting for twenty-four hours after consumption; fly agaric (*A. muscaria*), which causes hallucinogenic effects and often severe nausea; and death cap (*A. phalloides*), which leads to an unpleasant death over several days. Alternatively mushrooms may be identified using printed keys or computer databases (see Percudani et al. 1996), or by speaking with an expert who is well



Spore print of a Swiss brown strain button mushroom (*Agaricus bisporus*). (Hall)

acquainted with the mushrooms of the region. Such experts can be difficult to find, although the botany department of the local university or research center might be able to assist.

A key is a device used for identifying organisms, in this case mushrooms, based on their distinguishing features. With printed keys the user is usually presented with lists of questions to which there are two or more answers. Once a question is answered, the user moves on to the next question until eventually the mushroom is identified. For example, a key that separates members of four of the more commonly encountered groups of mushrooms might look like this:

1. Fruiting body with an expanded cap supported by a stalk 2
   Fruiting body with or without a cap but lacking an obvious stalk 3
2. Fruiting body with gills beneath the cap.......... agaric
   Fruiting body with pores beneath the cap .... bolete
3. Fruiting body shelflike or bracket-like .... polypore
   Fruiting body more or less spherical.......... puffball

The problems arise when you attempt to identify something not in the key—perhaps one of the few polypores that does have a stalk; or a representative of another group of mushrooms, such as a spherical truffle; or a mushroom that has a stalk and cap but neither gills nor pores, such as a morel. Obviously it is possible to construct a key that gets around these problems, but with mushrooms the questions asked often become rather technical and require some degree of expertise to answer. For many species, distinguishing features are mostly at the microscopic level, and this presents a challenge for all but the most serious amateur mycologists.

A short, easy-to-use key to edible mushrooms of the United Kingdom is provided in *How to Identify Edible Mushrooms* (Harding et al. 1996). After answering a few questions, the reader is referred to an illustration of an edible mushroom, which is followed by illustrations of edible and poisonous look-alikes. A pictorial key helps users identify mushrooms using pictures that illustrate key features. An excellent annotated pictorial key to mushrooms in general that requires a minimum of technical expertise and terminology to work can be found in *The Mushroom Book* (Læssøe and Del Conte 1996), while the *Discover Mushrooms* computer-based key is easy to use for those with a rudimentary knowledge of computers (Samuels 2002). Some simple keys that also rely only on macroscopic features are included in *Mushrooms and Toadstools of Britain and Europe* (Courtecuisse and Duhem 1995).

Good keys to mushroom genera can be found in *A Colour Atlas of Poisonous Fungi* (Bresinsky and Besl 1990) and in the first volume of *How to Identify Mushrooms to Genus* (Largent 1986), but a full knowledge of mushroom terminology is needed to use them. The keys provided in this book, while very rudimentary, are probably an adequate introduction for a beginner.

Trick or Treat

A few mushrooms are deadly poisonous, while others, though not lethal, may produce most unpleasant symptoms if eaten. Consequently, it is important to know how to avoid these "tricksters." There is no simple way to distinguish between those that are poisonous and those that are harmless. There are many myths surrounding the edibility of mushrooms that over the years have taken on the status of rules, but these should all be laid to rest.

Common among the myths: mushrooms that can be peeled are edible; mushrooms that grow in spring or late autumn are edible;


Gills
No volva
Gills do not run down stalk
Gills run down stalk
Tubes under cap
Volva or volva-like ring
White spores
Brown spores
Pink spores
On ground
No ring on stalk
Broken caps do not produce milk
Gills close together
Caps not brittle and crumbly
Caps brittle and crumbly
Waxy, widely spaced gills
Ring on stalk
On wood
No cortina
Caps not sulfur-yellow
On wood
On ground
Cortina
Young broken caps produce white or colored milk
Stalk attached centrally
Broken caps do not produce milk
Caps not funnel-shaped
Brown spores
Gills may fork but no network
Gills form a net
White spores
Caps brown with scales
Gills forked, caps large and white
Gills not forked, caps without scales
Funnel-shaped cap
Stalk attached to edge of cap
White spores
Pink spores
Ring on stalk
Network on stalk
Scales on stalk
No spines, gills, or tubes under cap
Spines under cap
Purple-brown or black spores
Green spores
Caps brittle and crumbly
Caps not brittle and crumbly
Broken caps do not produce milk
Young broken caps produce white or colored milk
Caps sulfur-yellow in tufts on wood
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29

1	*Cortinarius*
2	*Hebeloma*
	Inocybe
	Panaeolus
	Psathyrella
	Stropharia
3	*Agrocybe*
	Gymnopilus
	Pholiota
	Psilocybe
4	*Armillaria*
	Flammulina
5	*Armillaria*
	Lepiota
	Macrolepiota
6	*Hygrocybe*
	Laccaria
7	*Calocybe*
	Collybia
	Lyophyllum
	Marasmius
	Mycena
	Termitomyces
	Tricholoma
8	*Russula*
9	*Lactarius*
10	*Cantharellus*
11	*Paxillus*
12	*Lentinula*
13	*Leucopaxillus*
14	*Clitocybe*
15	*Clitocybe*
	Gomphus
	Hygrophoropsis
	Phylloporus
16	*Lampteromyces*
	Omphalotus
	Pleurotus
17	*Amanita*
18	*Volvariella*
19	*Suillus*
20	*Austroboletus*
	Boletus
	Tylopilus
	Xerocomus
21	*Leccinum*
	Strobilomyces
22	*Craterellus*
	Hypomyces
23	*Hydnum*
	Sarcodon
24	*Agaricus*
	Coprinus
25	*Chlorophyllum*
26	*Russula*
27	*Entoloma*
	Lepista
28	*Lactarius*
29	*Hypholoma*

A key to the main mushroom genera covered in this book that have caps with stalks.


On or under the ground
On wood or rocks
Spherical, with or without a stalk
Less than 20 cm in diameter
Solid with a network, circles or flecks inside
Dry inside
Thin skin of white lines inside
Thick skin, no network of white lines
Slimy inside
Greater than 20 cm in diameter
Spongy
Not powdery at maturity
Powdery at maturity
Spores released through terminal pore
No terminal pore
Folded piece of suedelike material on a grooved stalk
Honeycomb-like head on a hollow stalk
Brainlike head on a multi-chambered stalk
Swollen or star-, stick-, coral-, or spindle-like head on stalk
Not attached to an insect or truffle
Arising from an insect
Hatching from an egg
Phallic, with a stalk
Star- or basket-shaped
Cup-shaped and fragile
On tips of branches or maize cobs
Cushion-shaped and fragile, on wood or ground
Bracket-like or spherical
Lobed and gelatinous
Not woody
Woody
Fragile and divided
Leaflike
Finely divided, toothlike
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22

1	*Gyromitra*
2	*Morchella*
	Verpa
3	*Helvella*
4	*Calvatia*
5	*Melanogaster*
6	Truffles
7	*Scleroderma*
8	*Rhizopogon*
9	*Lycoperdon*
10	*Bovista*
	Calvatia
	Vascellum
11	*Auricularia*
	Tremella
12	*Fistulina*
	Laccocephalum
	Laetiporus
	Lenzites
	Schizophyllum
	Trametes
13	*Daldinia*
	Ganoderma
14	*Grifola*
	Sparassis
	Umbilicaria
15	*Hericium*
16	*Fuligo*
17	*Cyttaria*
	Uromyces
	Ustilago
18	*Aleuria*
	Cyathus
	Paxina
	Peziza
19	*Aseroe*
	Ileodictyon
20	*Dictyophora*
	Mutinus
	Phallus
21	*Cordyceps*
22	*Clavaria*
	Clavulina
	Geastrum
	Podaxis
	Ramaria
	Xylaria

A key to the main mushroom genera covered in this book that have various shapes—those not cap-shaped with stalks.

Return down the front, point by point in the same way, leading with the left hand.

Go up and down this way three times. The double palm and beam activate both the Functional and Governor Channels. The energy beam passes all the way through the body at each point.

Grasping the Chi Ball

Separate the hands and slowly extend the arms in front of you at navel level, palms facing each other, holding the Chi ball.



Fig. 8.83 *Squeeze the Chi Ball.*



Fig. 8.84 *Magnify its Energy.*

Stretch and squeeze the Chi ball three times as before by opening and closing the palms. 'Be Aware of Tan Tien and Universe'.



A. ***B.*** ***C.***

Fig. 8.85 *Repeat the double palm and beam with the* ***left hand on the outside and the right palm leading,*** *beaming from;* ***A.*** *Navel to Door of Life.* ***B.*** *Solar Plexus to T11 and Heart Center to the Wing Point* ***C.*** *Throat Center to C7.*

mushrooms that grow on live trees are edible, while those that grow on dead trees are poisonous; mushrooms eaten by snails or other small animals, or that are not poisonous to animals such as squirrels, are edible; violet and viscid mushrooms are poisonous; mushrooms whose flesh changes color on cutting are poisonous; mushrooms that exude latex are poisonous; mushrooms that smell like flour are edible; mushrooms that discolor a silver spoon put into the pot while cooking are poisonous, while those that do not are edible; poisonous mushrooms cause milk or egg white to coagulate, while those that do not are edible; brown-gilled mushrooms are edible, but white-gilled mushrooms are poisonous; mushrooms lose their poison if boiled in water with or without salt or vinegar; mushrooms lose their poison through drying; and those that taste good are safe to eat. None of these statements is true!

The only way to know whether a mushroom is safe to eat is to be sure of what you are eating and to have access to reliable advice on its edibility. To sample the "treats" you must know how to identify and avoid the "tricksters."

Unfortunately, many mushrooms do look alike—especially those growing on your lawn at home, in the nearby woods, or on fallen branches. The common edible field mushroom (*Agaricus campestris*) can be mistaken for numerous brown-gilled species growing in the grass, including poisonous species of *Panaeolus* and *Psilocybe* and toxic species of *Agaricus*. In its button stage the same mushroom, and especially its larger cousin the horse mushroom (*A. arvensis*), can look every bit like some poisonous *Amanita* species in their button stage, especially the fly agaric (*A. muscaria*) and the panther cap (*A. pantherina*). These are white, and the scales on the caps are sometimes not easily discernible. In addition, fruiting bodies at the button stage can create confusion between the highly prized porcini (*Boletus edulis*), other edible boletes, and the button stage of poisonous species of *Amanita*. A number of mushrooms, both edible and poisonous, look just like golf balls in the grass when at their button stage. *Amanita* at a slightly more advanced stage may take on the shape of an inverted pear and can then be confused with some edible puffballs such as *Calvatia* species and *Bovista* species. The common field mushroom and the horse mushroom may also be readily confused with a close relative, yellow stainer (*Agaricus xanthoderma*), which stains yellow quickly on bruising and is renowned for causing stomach disorders.

Within woodlands it is also easy to make mistakes. The honey mushroom (*Armillaria mellea*), a deadly parasite of trees, grows at the base of infected trees or stumps and is considered by some to be good to eat. It can also superficially resemble the big laughing gym (*Gymnopilus junonius*), a psychoactive species, or the sulfur tuft (*Hypholoma fasciculare*), which causes severe gastroenteritis. On dead trees the oyster mushroom *Pleurotus ostreatus* is a particularly desirable species and is widely grown commercially, but in Australia poisoning incidents have been reported when this species has been mistaken for the morphologically very similar *Omphalotus nidiformis*; and in Japan the oyster mushroom has been confused with *Lampteromyces japonicus*. Similarly, the edible and now commercially produced enokitake (*Flammulina velutipes*), which naturally grows on decaying tree stumps, must be carefully identified before eating, since it resembles some species of *Galerina*, which if consumed can prove fatal.

The destroying angel (*Amanita virosa*) is a fungus to avoid at all costs. Its pure white color belies its toxicity, and it must not be confused with other elegant, white mushrooms that occur in similar habitats, such as some species of *Volvariella*. Another group of elegant species are the parasol mushrooms (*Macrolepiota* spp.), which when in their button or juvenile stage are similar to the deadliest of mushrooms: death cap (*Amanita phalloides*). *Tricholoma* is also a difficult genus, containing species with whitish or yellow gills with extremely varied appearances. Not only can choice edible species be confused with poisonous ones within the same genus, but some can be readily confused with the most poisonous species of *Amanita*. Such mistakes are not rare events. In 1996 in the Ukraine ninety-two people died out of eleven hundred who were hospitalized after confusing light-colored *Amanita* species for edible mushrooms (CBC Newsworld 1996), and at the end of the same year nine people in northern California were hospitalized after consuming *Amanita* species (CDC 1997). There are similar examples wherever wild mushrooms are consumed. Around nine thousand mushroom poisonings occur in the United States each year alone (Kidcheck 2002).

Among the most visually appealing mushrooms are the chanterelles (*Cantharellus* spp.), the undersides of their caps covered with blunt, gill-like ridges. Yet here again care needs to be taken so that misidentification does not occur. The highly prized golden chanterelle (*Cantharellus cibarius*) can be mistaken for *Omphalotus olearius* (jack-o'-lantern), the consumption of which promotes the most unpleasant of symptoms, including nausea and vomiting (Lincoff and Mitchel 1977). The poisonous brown roll rim (*Paxillus involutus*) also resembles the chanterelles and the saffron milk cap (*Lactarius deliciosus*) and should not be eaten. Also similar to *P. involutus* is false chanterelle (*Hygrophoropsis aurantiaca*), which is best avoided, since it is known to be hallucinatory.

Some of the most recognizable mushrooms are the morels (*Morchella* spp.), which are said to look like small human brains and are delicious to eat. Unfortunately they can be confused with another brainlike fungus, the false morel (*Gyromitra esculenta*), which has the distinction of containing a chemical compound that is the precursor of methylhydrazine, a rocket propellant used by NASA, and that can have lethal effects. Another species of *Gyromitra*, the hooded false morel (*G. infula*), has a spectacular appearance but is deadly poisonous when eaten raw. Wrinkled thimble cap (*Verpa bohemica*), which closely resembles the cap of the edible half-free morel (*Morchella semilibera*), used to be eaten but is now recognized as poisonous.

Ink caps (*Coprinus* spp.) are another easily recognizable group of edible mushrooms. The common ink cap (*C. atramentarius*) is one such species, though it should never be consumed with alcohol and alcohol should not be taken within one to two days after eating it because severe symptoms will result, including an alarmingly rapid pulse rate and nausea.

Puffballs are easily recognizable, but they also need close examination to distinguish the edible from the nonedible varieties. They should not be eaten without first being cut to ensure there are no gills lurking in the button of a puffball look-alike and to discern the color of the flesh. Young fruiting bodies of the earthballs (*Scleroderma* spp.) have also been mistaken for truffles or puffballs.

Last but certainly not the least is the deceiver (*Laccaria laccata*), which lives up to its name. Though edible, its great variability in form and even color, depending on the environment, allows for misidentification. It may closely resemble a host of poisonous little brown mushrooms (LBMs), such as *Inocybe* species and *Galerina* species.

It is important to remember that there may be large differences in the appearance of the same mushroom in different parts of the world. Even though you may be familiar with and have eaten certain mushrooms in your home country, you cannot assume those of similar appearance in unfamiliar surroundings are edible. Since the edibility of most mushrooms remains unknown, there is plenty of room for error—the look-alike examples given in this section by no means comprise an exhaustive list. Useful generalizations such as being very wary of white-capped and white-gilled mushrooms should be heeded, but also remember that some brown-gilled brown mushrooms are among the deadliest. Err on the side of suspicion and note the old adage, "There are plenty of old mushroom hunters and plenty of bold mushroom hunters, but there are no old, bold mushroom hunters."

Mushroom Toxins

Despite the warnings prominently displayed in books on edible mushrooms, mushroom poisonings are not infrequent for those individuals looking for an out-of-body experience or for bona fide mushroom hunters who have failed to follow the rules. Once these unfortunates get to a hospital, the standard treatment is to feed them with activated carbon, which acts like a chemical sponge, and observe their symptoms. From the particular group of symptoms—or syndromes, as they are called—the toxicologist is often able to determine what type of toxin the patient has consumed and hazard a guess at what follow-up treatments may be necessary (Benjamin 1995). However, the toxicologist may not be able to decide just what has been consumed from the symptoms alone, because several genera and many species may contain the same toxin. For example, amatoxins are found not just in *Amanita* species but also in species of *Conocybe*, *Galerina*, and *Lepiota*.

Detailed descriptions of the syndromes, which toxins are found in which species, treatments used in mushroom poisonings, death rates, and so on, are the subjects of whole books, as with the detailed, though somewhat academic *A Colour Atlas of Poisonous Fungi* (Bresinsky and Besl 1990) and the very entertaining *Mushrooms: Poisons and Panaceas* (Benjamin 1995). Consequently this book is restricted to the following brief descriptions of the syndromes. A list of poisonous mushrooms containing the toxins that cause the syndrome follows each description, and additional symptoms caused by the mushrooms are also provided (primarily from Benjamin 1995, Bessette et al. 1997, Both 1993, Bresinsky and Besl 1990, Dhabolt 1993, Imazeki et al. 1988, Lincoff and Mitchel 1977, Miller 1981, Phillips 1981, 1991, Stamets 1996).

Protoplasmic poisons

Amatoxin (cyclopeptide) syndrome. Symptoms are caused by fungal toxins such as amanitin and amanin, formed of eight amino acids arranged in a ring (cyclopeptides), and develop from six to twenty-four hours after eating the mushrooms. There will be a day or so of violent vomiting, diarrhea, and stomach cramps, followed by lowered blood pressure, accelerated pulse, and dehydration. By this time it may be too late for some patients as many of the amatoxins in the mushroom will have been absorbed from the intestine and will have begun to damage the liver. After the initial stage there is sometimes an apparent recovery, but two to three days later jaundice and liver and kidney failure develop (Bresinsky and Besl 1990, Freedman 1996, Phillips 1981). Death is not infrequent in severe cases. Complete blood dialysis or a liver transplant have been used to treat severe poisonings; other treatments are listed on the Centers for Disease Control and Prevention (CDC) Web site. Amatoxins are not broken down by boiling.

Amanita bisporigera
Amanita phalloides
Amanita verna
Amanita virosa
Conocybe filaris
Conocybe rugosa
Galerina autumnalis
Galerina fasciculata
Galerina marginata
Galerina sulciceps
Galerina venenata
Hypholoma fasciculare (other symptoms include gastrointestinal syndrome, impaired vision, paralysis)
Lepiota brunneoincarnata
Lepiota castanea
Lepiota citrophylla
Lepiota helveola
Lepiota josserandii
Lepiota subincarnata

Gyromitrin syndrome. Symptoms begin two to twenty-four hours after ingestion and can include abdominal pain, diarrhea, vomiting, coma, convulsions, delirium, fever, headache, restlessness, respiratory failure, and liver damage leading to jaundice. Kidney failure may also occur, and death is possible in severe cases. The breakdown products of gyromitrin are hydrazines, which are carcinogenic; however, there is no evidence that these cause cancer in humans.

Cudonia circinans
Gyromitra ambigua

Gyromitra californica
Gyromitra caroliniana
Gyromitra esculenta
Gyromitra fastigiata
Gyromitra gigas
Gyromitra infula
Gyromitra korfii
Gyromitra sphaerospora

Paxillus syndrome (**immune hemolytic anemia**)**.** In addition to gastrointestinal reactions, *Paxillus involutus* may cause a potentially fatal immune response that leads to a breakdown of red blood cells in those who have eaten the mushroom, possibly for many years, without experiencing symptoms.

Paxillus involutus

Orellanine syndrome (**delayed onset renal failure**)**.** Symptoms typically develop from thirty-six hours to three weeks after mushroom ingestion and include progressive kidney failure associated with an insatiable thirst and frequent urination, nausea, vomiting, lethargy, headaches, and shivering without fever or liver damage.

Cortinarius gentilis
Cortinarius orellanoides
Cortinarius orellanus
Cortinarius speciosissimus
Cortinarius splendens

Neurotoxins

Muscarine syndrome. The effects of muscarine poisoning—salivation, lacrimation, urination, defecation, gastrointestinal problems, and emesis—have given rise to the acronym SLUDGE. Other symptoms include decreased blood pressure, profuse sweating, and death due to respiratory failure.

Boletus pulcherrimus (other symptoms include gastrointestinal syndrome)
Clitocybe aurantiacum
Clitocybe candicans
Clitocybe dealbata

Clitocybe dilatata
Clitocybe ericetosa
Clitocybe gibba
Clitocybe nebularis
Clitocybe phaeophthalma
Clitocybe phyllophila
Clitocybe rivulosa
Clitocybe truncicola
Entoloma rhodopolium (other symptoms include gastrointestinal syndrome)
Inocybe bongardii
Inocybe dulcamara
Inocybe fastigiata
Inocybe geophylla
Inocybe godeyi
Inocybe griseolilacina
Inocybe hirtella
Inocybe lacera
Inocybe maculata
Inocybe napipes
Inocybe patouillardii
Inocybe praetervisa
Inocybe sororia
Mycena pura

Hallucinogenic syndrome. Symptoms, which develop within an hour and last for up to six hours, are similar to those produced by hallucinogenic chemicals like lysergide. They include vivid hallucinations, lack of contact with reality, seizures, prolonged reaction time, increased heart rate, dilation of pupils, and increased blood pressure.

Conocybe cyanopus
Gymnopilus junonius
Inocybe corydalina
Lycoperdon marginatum
Panaeolus ater
Panaeolus campanulatus
Panaeolus foenisecii
Panaeolus papilionaceus
Panaeolus retirugis
Panaeolus sphinctrinus

Panaeolus subbalteatus
Pluteus cyanopus
Pluteus salicinus
Pluteus villosus
Psilocybe argentipes
Psilocybe baeocystis
Psilocybe caerulescens
Psilocybe caerulipes
Psilocybe coprophila
Psilocybe crobula
Psilocybe cubensis
Psilocybe fasciculata
Psilocybe merdaria
Psilocybe subaeruginascens
Stropharia coronilla (other symptoms include gastrointestinal syndrome, malaise, headache, ataxia, dizziness)

Pantherine syndrome. There is a rapid onset of symptoms, including intoxication, ataxia, dizziness, lethargy (but sometimes with periods of manic behavior), nausea, vomiting, muscle cramps, tremor, seizures, hallucinations, and dilated or restricted pupils, with the patient finally moving into a coma-like state.

Amanita cothurnata
Amanita crenulata
Amanita gemmata
Amanita muscaria
Amanita pantherina
Amanita regalis
Amanita solitaria
Tricholoma muscarium

Gastrointestinal irritants

Gastrointestinal syndrome. The main symptoms, which can occur from a few minutes to a few hours after a meal, include abdominal pain followed by nausea, profuse sweating, vomiting, and diarrhea.

Agaricus hondensis
Agaricus placomyces
Agaricus praeclaresquamosus
Agaricus xanthoderma

Amanita brunnescens
Amanita chlorinosma
Amanita flavoconia
Amaniata flavorubescens
Amanita frostiana
Amanita parcivolvata
Armillaria mellea
Boletus erythropus
Boletus haematinus
Boletus luridus (other symptoms include coprine syndrome)
Boletus pulcherrimus (other symptoms include muscarine syndrome)
Boletus sensibilis
Bondarzewia berkeleyi
Chlorophyllum molybdites
Clitocybe acromelalga (other symptoms include sharp pains, red swelling of hands and feet one week after ingestion)
Collybia acervata
Collybia dryophila
Cortinarius cinnamomeus
Dermocybe sanguinea
Entoloma rhodopolium (other symptoms include muscarine syndrome)
Entoloma sinuatum
Gomphus bonari
Gomphus floccosus (other symptoms include neurological impairment)
Gomphus fujisanensis
Gomphus kauffmanii (other symptoms include neurological impairment)
Hebeloma crustuliniforme
Hebeloma mesophaeum
Hebeloma sinapizans
Hebeloma vinosophyllum
Hygrocybe conica
Hygrocybe ovina
Hypholoma fasciculare (other symptoms include amatoxin syndrome, impaired vision, paralysis)
Lactarius chrysorheus
Lactarius helvus
Lactarius piperatus

Lactarius pubescens
Lactarius repraesentaneus
Lactarius rufus
Lactarius scrobiculatus
Lactarius torminosus
Lactarius uvidus
Laetiporus sulphureus
Lampteromyces japonicus
Lepiota clypeolaria
Lepiota cristata
Lepiota lutea
Lespista irina (other symptoms include neurological impairment)
Megacollybia platyphylla
Meripilus giganteus
Morganella subincarnatum
Nolanea quadrata
Nolanea verna
Omphalotus illudens
Omphalotus nidiformis
Omphalotus olearius
Paxillus involutus (other symptoms include paxillus syndrome; possibly also a mutagen and carcinogen)
Phaeolepiota aurea
Phaeolus schweinitzii
Pholiota squarrosa (other symptoms include coprine syndrome)
Ramaria formosa
Ramaria gelatinosa
Ramaria pallida
Russula emetica
Russula sardonia
Scleroderma cepa (other symptoms include spasms, tingling sensations, rigidity)
Scleroderma citrinum
Stropharia coronilla (other symptoms include hallucinogenic syndrome, malaise, headache, ataxia, dizziness)
Suillus granulatus
Tricholoma album
Tricholoma inamoenum
Tricholoma pessundatum
Tricholoma pardinum
Tricholoma saponaceum



Fig. 8.86 *Activate the Mideyebrow to the Base of the Skull.*



Fig. 8.87 *Activate the Crown and feel the Energy penetrate to the Perineum.*

A. Lower the right hand to the mideyebrow and penetrate to the skull.
B. Lower the right hand down to the throat center, following with the left.
C. Lower down to the solar plexus and penetrate to T11.
D. Lower down to the navel and penetrate to the Door of Life.



Fig. 8.88 *Channel the Earth Force.*

Tricholoma sejunctum
Tricholoma sulphureum (other symptoms include neurological impairment)
Tricholoma venenata
Tricholoma zelleri
Tricholomopsis platyphylla (other symptoms include muscle cramps)
Verpa bohemica
Verpa conica

Alcohol dehydrogenase inhibition

Coprine (Antabuse) syndrome. Coprine may inhibit the function of alcohol dehydrogenase, an enzyme needed in the conversion of alcohol to acetic acid. The symptoms are similar to those of Antabuse (disulfiram), which is used for the treatment of alcoholism. Symptoms develop soon after ingestion and include severe headaches, rapid pulse, flushed face and chest, sweating, low blood pressure, confusion, nausea, and vomiting.

Boletus luridus (other symptoms include gastrointestinal syndrome)
Clitocybe clavipes
Coprinus africanus
Coprinus atramentarius
Coprinus insignis
Coprinus micaceus
Coprinus quadrifidus
Coprinus variegatus
Pholiota squarrosa (other symptoms include gastrointestinal syndrome)
Tricholoma aurantium

Raw Mushrooms

Many mushrooms, such as *Amanita rubescens*, *Armillaria mellea*, *Gyromitra esculenta*, *Lactarius* spp., *Laetiporus sulphureus*, *Lepista nuda*, *Morchella* spp., *Paxillus involutus*, and *Russula* spp., can cause poisoning when eaten raw. In *G. esculenta*, this can lead to death. Therefore, as a general rule it is safer to cook all mushrooms before eating. Only a few mushrooms—traditionally known as salad mushrooms—are safe to eat raw. Examples include button mushrooms (*Agaricus bisporus* and *A. bitorquis*) and *Boletus edulis* (Benjamin

1995, Bresinsky and Besl 1990). In many countries the edibility or toxicity of many indigenous mushrooms is unknown. For this reason, most are best avoided.

Rules for Picking and Eating Mushrooms

There are some simple rules that should be followed when picking wild mushrooms for the table. Each is included here for a very good reason, and, if followed, may one day save you from an unpleasant experience, or even save your life.

Do not eat any mushroom if you have doubts about its identity or edibility. Carefully check every mushroom you are going to eat, first in the field and then when you return to the kitchen. Pick only mushrooms that show no signs of decomposition: worms and insect larvae often found in old mushrooms, as well as the bacteria that follow them, may themselves produce toxins. Cut small puffballs in two vertically to see if there are any structures inside that might suggest they are *Scleroderma* or the button stages of, for example, an *Amanita* species. Do not eat raw mushrooms, which may contain toxins that are destroyed during cooking. Be absolutely certain of the identity of mushrooms with a ring or volva on the stalk, with scales or warts on the surface of the cap, or with white gills.

Unless you really are an expert, do not eat any small *Lepiota*, *Agaricus* that stains yellow, *Lactarius* that does not have red or orange milk, boletes that stain blue when bruised and/or are orange or red on the underside of the cap, brainlike mushrooms (*Gyromitra*), chanterelle-like mushrooms (*Gomphus* and *Hygrophoropsis aurantiaca*), unidentified coral-like mushrooms (*Ramaria*), or little brown mushrooms.

Eat a small quantity of a mushroom the first time you try it, and wait forty-eight hours before eating more of it or another species; if you are allergic to the mushroom, any poisons that might be present may take twenty-four hours to have an effect. Save a couple of uncooked mushrooms in the refrigerator just in case you make a mistake and need medical attention. Do not eat mushrooms from roadsides where lead levels may be high or from areas where the soil may be rich in elements such as cadmium, chromium, and mercury. Similarly, do not pick mushrooms from areas that might have been sprayed with herbicides or pesticides. Never assume a mushroom you have picked in another country is the same species as a similar one you have consumed back home.

Finally, if you have taken all precautions, are sure you have identified a mushroom accurately, and have eaten a hearty meal but have begun to show adverse symptoms, consult a doctor immediately. If you are unable to find a doctor, contact the National Capital Poison Center in the United States (telephone: 800-222-1222; TDD line for the deaf: 202-362-8563) or one of the regional poison centers in the United States or Canada. Do not delay—seek medical attention immediately.

Other countries have similar national poison centers, and the telephone numbers to these are usually prominently displayed in telephone directories. Considerable information is available online—for example, on the Web site provided by the National Capital Poison Center in the United States and in the *Bad Bug Book* from the U.S. Food and Drug Administration—but access to details in the United Kingdom's National Poisons Information Service "Toxbase" is restricted to hospitals and other registered users within the United Kingdom.

A Permanent Record

Once a careful note has been made of a mushroom's habitat, spore prints have been prepared, and features have been noted, it may be worth making a permanent record of the mushroom. One way to do this is to dry the material in a warm dry place, which preserves most microscopic features. Mushrooms can be dried in a small food dehydrator, on a wire screen above a heat source, or in an airing cupboard. A proper thermostatically controlled drying oven set at 40–50°C is best, but a perfectly useful drying chamber can be constructed from a wooden box containing a 100-watt light bulb coupled to a domestic thermostat like those used to control electric heaters. If the mushrooms are particularly important specimens, such as the first collection of a new species for a region or country, they should be deposited in an internationally recognized herbarium (Holmgren et al. 1990). People working in the botany department of a local university or research center should be able to provide guidance on where these herbaria are located.

Photographing Mushrooms

Taking photographs is a good way to record what a mushroom looks like, but because of the size of many mushrooms and the dark places where many are found, a standard point-and-shoot camera will be of little use. Almost any reflex camera will do, provided it has a built-in light meter, a manual exposure override, a cable shutter release, a good range of slow shutter speeds or a timed exposure setting that allows the shutter to stay open as long as a finger is pressed down on the cable release button (usually marked "B" for "Bulb" on the shutter speed setting knob), a set of extension tubes for taking close-ups, and a tripod. A secondhand single-lens reflex camera with extension tubes and a miniature tripod might cost only $100.

A fully automatic camera flash controlled by the camera's light meter is very easy to use and can take almost all the guesswork out of photographing mushrooms against the background of a dark forest floor. With the right kind of flash and camera you can even take photographs at night, though finding mushrooms under such conditions can prove difficult. An automatic ring flash can be used, but it is best to cover up part of the ring; otherwise all the shadows and many details may disappear. This can render a photograph less lifelike and may make it difficult to see certain details, such as pale gills. If you have no flash, a piece of crumpled aluminum foil (about 30 sq. cm) taped to some stiff cardboard can provide that little extra light to highlight one side of a mushroom or illuminate shaded stalks or gills. Many professionals don't like using flash photography, preferring to use a tripod and very long exposure times of thirty seconds or more. If they do use a flash, it might only be to highlight a feature or improve background detail.

In dark places light meters on relatively simple reflex cameras can usually be tricked into giving a reasonably accurate exposure guide. To do this the film speed setting is increased, say from ISO 100 to 3200. A meter reading is then taken at a particular aperture. If it indicates that a one-second exposure should be used, the true exposure is thirty-two times this. Incidentally, don't forget to reset the ISO setting on your camera afterward or you may finish up with a roll of blank film. It is also a good idea to take a few more photographs of the same mushroom with 50 percent and 100 percent longer exposure times, as films tend to behave more slowly than their ISO rating would indicate when given long exposures, something known as the reciprocity effect (Eastman Kodak 1988). The colors may also turn out somewhat different than they really are because the sensitivities of the three color layers of many films are dissimilar with exposure times longer than one twenty-fifth of a second. Fortunately, a few films have been developed that are stable up to a hundred seconds (Barnhart 2000).

When taking close-ups it is very important to mount the camera securely, as it may shake slightly when the shutter opens and closes.

The camera may also shake when the shutter release is pressed, but this can be minimized if a flexible shutter release cable is used in conjunction with a good tripod. Better still are the electronic shutter release mechanisms that can be fitted to many modern cameras. Finally, choose an internationally recognized brand of film to ensure quality results. While fast films give shorter exposures in dark places, they also tend to be more grainy, so in general it is better not to use a film faster than ISO 100. Digital cameras can provide some excellent results, but take care to choose one with a macro facility, automatic flash compatibility, and an image size of at least 1 megapixel.

The Web can provide much valuable information on photographing small objects like mushrooms. Most large photographic companies have good Web sites. Agfa has an especially good photo course.

Photography through a microscope

Spore shapes and other microscopic details are often essential to identify mushroom species. Drawings can be made, but it is also possible to create photographic records (Smith 1990, Thomson and Bradbury 1987). Sophisticated equipment is not absolutely necessary to do this. If certain precautions are taken, good results can be obtained with relatively inexpensive equipment. The simplest equipment would be a student microscope with a vertical eyepiece tube, a single-lens reflex camera with through-the-lens metering or a digital camera, and a microscope adapter. Automatic reflex cameras without a manual override are generally not suitable. More expensive microscopes have triocular heads that permit a camera to be left mounted on the microscope when it is not being used. They usually also have built-in, high-intensity light sources and light-balancing filters, which make taking photomicrographs much easier.

This page intentionally left blank

A LIST OF WILD MUSHROOMS

This page intentionally left blank

For some people the collection of wild mushrooms is simply an adjunct to an enjoyable walk in the countryside, but for others their collection and sale are a profitable hobby or even a full-time business. Anyone who eats or intends to eat wild mushrooms must be knowledgeable about species with unpleasant flavors or textures and, more importantly, species that can lead to serious poisoning or even death.

Some mushrooms found growing in the wild are not actually indigenous but have found their way, whether accidentally or intentionally, from another part of the world. For example, porcini (*Boletus edulis*) and saffron milk caps (*Lactarius deliciosus*) found in New Zealand and Australia are certainly not native and have only come to the attention of scientists there within the past few years (Segedin 1987, Segedin and Pennycook 2001, Wang et al. 1995). The same is true of the deadly poisonous *Amanita phalloides*, which seems to have found its way to North America from Europe (R. Tulloss, personal communication). As a result, the mushrooms included in this section are those that might be found in a whole range of countries. This selection concentrates on important poisonous mushrooms and conspicuous edible species, particularly those with sizeable international markets, although the occasional interesting curiosity is also included. The simple keys in Collecting Wild Mushrooms and the photographs of individual species can be used to help identify the edible mushrooms covered and to distinguish them from the poisonous species. As always, however, only eat a mushroom if you are absolutely sure of its identity. See Collecting Wild Mushrooms for more information on symptoms of various poisoning syndromes and a list of toxic mushrooms.

To provide some structure that will allow for easy navigation, mushrooms have been placed into sometimes artificial groups based on their appearance. The following simple key should help to locate the appropriate section.

---

1. Mushrooms with gills and a more or less centrally placed stalk; white or pale green spore print, rarely with pale pink or other pale-colored spores (page 124)

2. Mushrooms with gills and a more or less centrally placed stalk; pale pink spore print (page 179)

3. Mushrooms with gills and a more or less centrally placed stalk; brown spore print (page 183)

4. Mushrooms with gills and a more or less centrally placed stalk; purple-brown to black spore print (page 195)

5. Mushrooms with ear-shaped or bracket-like fruiting bodies; stalk either absent or poorly developed and attached to the edge of the cap; spores produced on gills, gill-like folds, or directly on the lower undifferentiated surface of the fruiting body (page 209)

6. Mushrooms with more or less funnel-shaped fruiting bodies (or fruiting bodies triangular in cross section), with the spores formed on the outer surface, either on gill-like folds or simply on a rough surface (page 216)

7. Mushrooms with a central, well-developed stalk supporting the cap and no gills but with many tubes present that give the underside of the cap a spongelike appearance—boletes (page 221)

8. Mushrooms with an undersurface devoid of gills or tubes but with minute spines or elongated, toothlike structures (page 236)

9. Mushrooms with a distinct stalk, a conical or spherical honeycomb-like top, or a folded piece of suedelike material on top of a grooved stalk (page 239)

10. Mushrooms with pulvinate to spherical fruiting bodies that are parasitic on living plants (page 252)

Rotate the **hands to face downward** and draw in the earth force through the palms, soles and perineum.

Closing Movements

Activate the Chi Channels - Balancing the Organs

The closing movements, crane's beak and finish are the same as before.
Index Finger *open (up), close (down), neutral (even with the other fingers)*
Ring Finger *- down, neutral.*
Index Finger *- open, neutral.*
Thumb *- in and down, neutral.*
Index Finger *- open, neutral.*
Pinky Finger *- down, neutral.*
Index Finger *- open, neutral.*
Middle Finger *- down, neutral.*
Index Finger *- open, neutral.*



Fig. 8.89 *Form the Crane's Beak.*



Fig. 8.90 *Palms to Front.*



Fig. 8.91 *Lower to Sides.*

Crane's Beak

Form the crane's beak with both hands by bringing the fingertips together with the thumbs inside. Activate the saliva and swallow this elixir down three times to the Tan Tien. Raise the forearms to shoulder height with the fingers pointed down, inhaling gently as you raise.

Open the palms slowly and begin to lower the arms to the sides as you exhale, until the palms are facing each other in the starting position.

Finish

Bring awareness to the navel and notice the quality and intensity of the energy generated. Collect energy at the navel. Men, place the hands over the navel with the right hand on top; vice versa for women.

---

11. Mushrooms lacking stalks or whose stalks are rudimentary and attached to one side, with the spores formed in tubes or on the undersurface of the caps (page 255)

12. Mushrooms with fruiting bodies above or below the ground and more or less spherical—puffballs, truffles, and false truffles (page 262)

13. Mushrooms with fruiting bodies consisting of a simple or branched linear structure growing from decaying wood or arising from an adult or larval insect (page 283)

14. Mushrooms with spindle-, coral-, icicle-, or cauliflower-shaped fruiting bodies (page 286)

15. Mushrooms with basket-shaped fruiting bodies or fruiting bodies with tentacle-like arms hatching from an egg (page 292)

16. Mushrooms with spherical fruiting bodies that open out into star-shaped structures, with the spores contained in a central ball that discharges dry spores through a small central pore—earthstars (page 293)

17. Mushrooms with more or less cup-shaped fruiting bodies, with the spores produced inside the cup on a feltlike surface or within small egglike structures (page 293)

18. Mushrooms with cushion-shaped fruiting bodies that are at first outwardly slimy, then rather fragile (page 297)

19. Mushrooms with leaflike fruiting bodies that are dark green or nearly black and closely appressed to vertical rocky surfaces (page 299)

1. Mushrooms with gills and a more or less centrally placed stalk; white or pale green spore print, rarely with pale pink or other pale-colored spores

Amanita Species

The genus *Amanita* contains a few delicious species and, unfortunately, some of the most deadly. Making sure you have the right species before sitting down to dine is therefore absolutely essential. Identification can be rather difficult. Mistaking a poisonous species like *A. pantherina* or *A. virosa* for an edible one has led to the demise of a number of keen amateurs and even an occasional professional mycologist. It is therefore appropriate to begin with those white-spored species that fruit on the ground under trees, with which they very likely form ectomycorrhizal associations.

Amanita jacksonii and *Amanita caesarea* (Caesar's Mushroom)

Caesar's mushroom is so named because it was a favorite of the emperor Claudius and led to his demise when he ate some that had been mixed with poison (Benjamin 1995). It is found throughout eastern North America and the warmer parts of southern Europe in summer and autumn associated with oaks and other deciduous trees. Although the American and European forms of this mushroom are listed under *Amanita caesarea* in many texts, the former is now considered to represent a different species: *A. jacksonii*. The combination of an orange cap up to 18 cm in diameter, orange-tinged stalk up to 15 cm high, orange-tinged ring, distinct volva, and orange gills makes this mushroom unlikely to be confused with any other *Amanita* in North America or Europe, although it is possible that a faded *A. muscaria* might mislead an inexperienced collector, particularly if the scales have been washed off by rain. The very similar species *A. hemibapha* is common in East Asia, where it is also highly regarded.

Amanita citrina (False Death Cap)

Amanita citrina is one of several mushrooms that might be confused with the death cap (*A. phalloides*). Like the death cap, the cap of *A. citrina* may have a greenish tint, and the base of the stalk is conspicuously enlarged. However, *A. phalloides* generally has a cup-shaped volva at the base of the stalk, while *A. citrina* simply has an



Amanita caesarea (Caesar's mushroom) showing the well-formed volva at the base of the stalks. **EDIBLE.** (Johnson)



Amanita hemibapha from Japan. Note the prominent cup-shaped volva at the base of the stalks. **EDIBLE.** (Izawa)



Amanita citrina (false death cap) with young caps pushing through the soil surface. In this species the volva is reduced to a bulbous base just below the soil surface. **EDIBILITY UNKNOWN: AVOID.** (Hall)



Amanita citrina (false death cap). Note the downward hanging veil. **EDIBILITY UNKNOWN: AVOID.** (Johnson) expanded base to the stalk, without a distinct volva. Both have a skirt-like ring on the stalk. Fruiting bodies of *A. citrina* have a cap 4–12 cm in diameter and a stalk 6–13 cm long. Although not nearly as poisonous as *A. phalloides*, the false death cap should not be collected for the table. It is often very common in oak (*Quercus*) forests in eastern North America during the autumn.

Amanita muscaria (Fly Agaric)

No introduction should be required for the fly agaric, which can be found illustrated in a host of children's books and is probably the most photographed of all mushrooms. The orange to red cap with white scales and white gills, stalk, and volva make it almost impossible to mistake. The unopened fruiting bodies can be white but gradually turn orange as they develop. When fully expanded the cap can be up to 20 cm in diameter and the stalk up to 20 cm high and 3 cm in diameter. Some specimens lose their white markings and might then be confused with the edible *Amanita caesarea* (Caesar's mushroom), although the volva of the latter is large and loose, the edge of its cap is striated, and its gills and stalk are a pale orange. In Europe and North America *A. muscaria* forms mycorrhizas primarily with birch (*Betula*), pine (*Pinus*), and spruce (*Picea*), and in countries where European and North American host trees have been introduced, this mushroom has often moved with



Amanita muscaria (fly agaric). Note the white ring on the white stalk. The cup-shaped volva is only just visible on the base of the swollen stalk on the fruiting body at left. **POISONOUS.** (Hall)



Amanita muscaria (fly agaric) that has lost most of the white spots on the surface of its cap. **POISONOUS.** (Hall)



Vertical section of a young fruiting body of *Amanita muscaria* (fly agaric), the cap and stalk forming inside the surrounding veil. **POISONOUS.** (Hall)



The caps of *Amanita phalloides* (death cap) exhibit a large range in colors. In this specimen the cup-shaped volva is visible at the base of the stalk of the larger, colored mushroom. The younger, almost white mushroom has just begun to break free of the volva. **POISONOUS.** (Hall)



Fully mature fruiting bodies of *Amanita phalloides* (death cap). **POISONOUS.** (Hall)



Mature fruiting bodies of *Amanita phalloides* (death cap). **POISONOUS.** (Buchanan)

its hosts. Occasionally this has resulted in the fly agaric jumping onto new indigenous hosts, such as southern beech (*Nothofagus*) in Australia and New Zealand (Johnston and Buchanan 1997).

The common name "fly agaric" probably comes from this mushroom's traditional use as a fly killer (Bresinsky and Besl 1990, Cooke 1980, Phillips 1981). After the mushroom is dried, the dried pieces are placed in a bowl of milk. A compound in the cap (1,3-diolein) attracts flies, who feed on the cap, become intoxicated, and either fall into the milk and drown or die from the toxins they consume. They may not die as quickly as they would from a can of fly spray, but the effect is more ecologically sustainable. *Amanita muscaria* has been used through the ages in religious rites and abused for its hallucinogenic properties, which increase when the cap is dried, due to the conversion of ibotenic acid to muscimol (Benjamin 1995, Bresinsky and Besl 1990, Hobbs 1995). The presence of a number of toxins produces other effects as well, including nausea, vomiting, and diarrhea. Although muscarine was first found in *A. muscaria*, this mushroom actually contains relatively little of this poisonous compound compared with the levels found in some species of *Inocybe* and *Clitocybe*.

Amanita phalloides (Death Cap)

Amanita phalloides accounts for the great majority of deaths from mushroom poisonings worldwide. In the button stage, the fruiting bodies of the death cap are almost white and have a smooth surface that rapidly turns light green to light brown. In this stage they may resemble a puffball, and this resemblance appears to have led to many accidental poisonings (Buchanan 1995, Cole 1993, 1994, Nicholls et al. 1995). As they open, the cap and stalk gradually turn light brown or pale green to greenish brown, becoming yellow with age and sometimes developing a hint of faint radial markings on the surface of the cap. There is also a variety that remains white at maturity. The caps are 4–13 cm in diameter and strongly convex when young, though flat when fully expanded. The stalk is 5–13 cm high and up to 2 cm thick. The white volva is distinct, even on mature fruiting bodies, but can be below ground level and can therefore be missed if care is not taken. Although the spore print is white, the gills can have a faint greenish color at maturity. The smell is sickly sweet and gets stronger after mushrooms have been picked and stored. The western United States has experienced a recent spate of poisonings from death caps, new immigrants from Asia mistaking them for straw mushrooms (*Volvariella volvacea*), which they superficially resemble. The consumption of less than 50 g of the death cap, or about one medium fruiting body, is enough to kill. A smaller dose can cause severe poisoning in adults and can kill a child. Even the spores of the death cap are poisonous, and so edible mushrooms that have been stored in the same collecting bag should always be discarded. If you have been



Amanita pantherina (panther cap). **POISONOUS.** (Lyon)

Part IV

Activating the Yin and Yang Channels and the Chi Belt

Theory

In this final part of Cosmic Chi Kung, you will focus on opening the yin and yang channels of the arms and on activating the Chi Belt around the waist. Mastery of Part IV of Cosmic Chi Kung will enhance your ability to project Chi through your fingers for healing.

Yin and Yang Channels of the Arms

There are six important energy channels flowing through the arms. These channels are paired together with each pair comprised of a yin channel and a yang channel. The yin channel of each pair flows down the inside of the arm from torso to fingertip, while its yang counterpart flows up the outside of the arm from fingertip to head.
The pairs are as follows:

Metal Element - Yin - Lung Channel - Thumb
Yang - Large Intestine Channel - Index Finger
Fire Element - Yin - Pericardium Channel - Middle Finger
Yang - Triple Warmer Channel - Ring Finger
Fire Element - Yin - Heart Channel - Pinky Finger
Yang - Small Intestine - Pinky Finger

Projecting Healing Energy through the Fingers

Emitting Chi from the fingers for healing is known in China as the **"One Finger Art."** Because the various energy channels of the arms either end or begin at the fingertips, the fingers are very effective instruments for projecting healing energy. Your fingers can focus energy like a laser beam toward a concentrated area such as a specific acupuncture point. You can also emit energy from all the fingers at once creating a combined effect to target an area. Part IV of Cosmic Chi Kung will stimulate all of the arm channels and will give you an opportunity to activate all of the fingers for beaming energy.

Fig. 8.92 *"One Finger Art"*

handling a death cap, do not put your fingers near your mouth, and always wash your hands before eating anything. After eating a death cap there may be a period of six to twenty-four hours before amatoxin syndrome begins.

Amanita pantherina (Panther Cap)

The panther cap is a pale brownish yellow to light brown mushroom. The cap is up to 10 cm in diameter and has white markings on its surface. The white stalk is up to 10 cm high and 2.5 cm wide, with a prominent ring. The volva is prominent and white. The panther cap can be found in summer and autumn (and occasionally spring) associated with deciduous trees, especially beech (*Fagus*) in Europe and eastern North America. The toxins it contains produce delirium and a deep coma-like sleep, and consumption may prove fatal. This species might easily be mistaken for *Amanita rubescens* (the blusher).

Amanita rubescens (The Blusher) and *Amanita excelsa*

The mature caps of the blusher are 5–15 cm in diameter, brown with a pinkish tinge, and have white to pinkish, irregularly shaped patches



Amanita rubescens (the blusher). **EDIBLE WHEN COOKED.** (Hall)



Amanita excelsa in Hagley Park, Christchurch, New Zealand. **EDIBILITY UNKNOWN: AVOID.** (Hall)



The young fruiting body of *Amanita excelsa* has the superficial appearance of a small puffball. **EDIBILITY UNKNOWN: AVOID.** (Hall)

on the surface. The stalk is 5–14 cm high and white when young, becoming marked with pink patches as it ages. There is a prominent white ring, but the volva, so characteristic of other species of *Amanita*, is usually little more than a ridge at the top of a swollen



Amanita virosa (destroying angel). **POISONOUS.** (Izawa)

base to the stalk. The flesh of the cap and stalk is white when young but gradually becomes pink when cut and exposed to air. *Amanita rubescens* may be eaten, but only if it is first thoroughly cooked. This process renders the mushroom safe to eat, although it can still produce an adverse reaction in some people. Because of the difficulty in distinguishing *A. rubescens* from *A. pantherina* and other poisonous *Amanita* species, many experienced mycologists will not take the risk of eating it. *Amanita excelsa* is similar to *A. rubescens*, and while this mushroom is considered edible in Europe (Phillips 1981), in Japan it is regarded as poisonous (Hongo et al. 1994).

Amanita virosa (Destroying Angel)

The caps of the destroying angel are often bulbous when immature but expand to 5–12 cm in diameter. The stalk is 10–20 cm high, and the volva often occurs just below soil level and is easily missed. The destroying angel fruits from early summer to early autumn in the eastern United States. It is rather uncommon in the United Kingdom (Harding et al. 1996), which is probably why it causes fewer fatalities there than the death cap (Læssøe and Del Conte 1996). This probably also explains why there is some confusion over its habitat, which in different texts is given either as mixed or hardwood forests (Phillips 1981) or conifer forests (Læssøe and Del Conte 1996). The destroying



Amanita vaginata (grisette). **AVOID.** (Izawa) angel and the white form of the death cap are the most dangerous poisonous mushrooms. This is not because they contain more toxic compounds than other poisonous species but because they can be mistaken for edible white-capped species. Like other species of *Amanita*, the destroying angel can be easily confused with *Volvariella* species. It has a pleasant smell and is reputed to taste quite good. Great care should always be taken when collecting white mushrooms near trees or when picking what appear to be puffballs but which actually may be disguised, unopened caps of an *Amanita*. *Amanita abrupta*, which is common in eastern North America, is another example of a white, highly toxic species (Imazeki et al. 1988).

Amanita vaginata (Grisette)

Some of the names that have been applied to members of the genus *Amanita* are known to refer to a complex of several morphologically very similar species and not just to a single biological entity. This is certainly the case for *A. vaginata*, which occurs throughout temperate regions of the Northern Hemisphere. Unlike the other species of *Amanita* described, *A. vaginata* lacks a ring on the stalk, though it does have a prominent volva. The cap is gray, 5–10 cm in diameter, and has a conspicuously striate margin. The stalk is white, smooth to finely fibrous, 10–20 cm high, and 10–15 mm thick. This mushroom occurs in hardwood as well as coniferous forests. Though not poisonous, it is best avoided because of possible confusion with other deadly species of *Amanita*.

Armillaria mellea (Honey Mushroom)

Over the years taxonomists have come to recognize that *Armillaria mellea* is actually a complex of species that share a similar appearance. The caps of *A. mellea* proper (sensu stricto) are 3–12 cm in diameter and light to dark brown, sometimes tinged olive. The gills are white or off-white. The stalks, which taper slightly toward the base, are up to 15 cm high and paler at the top, though similar in color to the cap at the base. There is a prominent, cottony, thick, off-white ring toward the top of the stalk. These mushrooms can be found from summer to early winter throughout temperate regions of the Northern Hemisphere, where they occur on stumps, logs, at the bases of dead but still standing hardwoods or conifers, or on buried wood around the trunks of trees that have become parasitized by the



Armillaria mellea (honey mushroom). Members of the *Armillaria mellea* sensu lato species complex display a great variability in form. **EDIBLE WHEN COOKED.** (Johnson)



Armillaria mellea (honey mushroom) growing on a rotting stump in northern Italy. **EDIBLE WHEN COOKED.** (Hall)



Armillaria mellea (honey mushroom) from the eastern United States. **EDIBLE WHEN COOKED.** (Johnson)



Armillaria novaezelandiae (bootlace mushroom), a species similar to the more widespread *A. mellea.* **EDIBLE WHEN COOKED.** (Hall)

fungus. The fungus spreads from one infected tree to another by long, dark gray to black, shoestring-like hyphae called rhizomorphs (Brasier 1992). *Armillaria mellea* causes gastric upsets when eaten raw or poorly cooked, and for some consumers even after cooking—a feature it shares with several dozen fungi. *Armillaria novaezelandiae* (bootlace mushroom) and *A. tabescens* (ringless honey mushroom) are also edible (Miller 1981, Hood 1992), but it would also be advisable to cook these mushrooms before eating.

Calocybe gambosa (St. George's Mushroom)

The fruiting body of St. George's mushroom has a white to off-white cap and a mealy smell. It can have a cap up to 15 cm in diameter, with a stalk up to 6 cm high and 1–3 cm thick. It is often found fruiting in rings in grasslands, along roadsides, in lawns, and at the edges of woodlands. The caps do not stain red when bruised. The common name for this mushroom stems from the likelihood of first finding its edible fruiting bodies on or about St. George's Day in the Northern Hemisphere (23 April). Its French name, *mousseron*, is probably the



Calocybe gambosa (St. George's mushroom) growing in grasslands in the United Kingdom. **EDIBLE.** (Lyon)

source of the English word "mushroom." This species might be confused with the brown-spored, red-staining *Inocybe patouillardii*, which is very poisonous. St. George's mushroom has white gills, but it has neither volva nor ring, and it fruits in spring rather than autumn. It is therefore unlikely to be confused with any white *Amanita*.

Clitocybe Species

The strongly funnel-shaped edible caps of *Clitocybe geotropa* are up to 20 cm in diameter and have stalks up to 15 cm high and 3 cm thick. The caps are buff when young but turn pale peach with age. The gills are the same color as the caps and extend down the stalk. *Clitocybe gibba* (common funnel cap), a species common in eastern North America, is smaller and has gills that are white to buff. Both species are found in autumn under deciduous trees or in mixed woodlands and consequently are unlikely to be confused with the smaller mushrooms of the deadly poisonous ivory clitocybe (*C. dealbata*) and *C. rivulosa*, which are usually found in grassy areas such as lawns and roadsides. *Clitocybe gibba*, *C. maxima*, and *C. robusta* are all edible



Clitocybe dealbata (ivory clitocybe). **POISONOUS.** (Lyon)



Clitocybe gibba (common funnel cap). **EDIBLE.** (Izawa)

Activating the Chi Belt - Dai Mo

The Chi Belt or Belt Channel (also called the Girdle Vessel) is the only channel in the body that runs horizontally. It encircles the body at the waist level, connecting together all the vertical channels running through the torso. Thus, the Belt Channel plays an important role in maintaining a good energetic communication between the upper and lower body. In women it strongly affects the uterus and the menstrual cycle in particular.

In Taoist Chi Kung, the Belt Channel is not limited to the waist region. It encircles the entire body, almost like weaving an energetic cocoon around you from head to foot. Activating the Belt Channel strengthens the aura and helps to defend and protect you from outside negative energies.



Fig. 8.93 *Belt Channel*



Clitocybe maxima. **EDIBLE.** (Wang)



A *Clitocybe* species of unknown edibility grows beneath a Douglas fir. (Hall) species eaten widely in China and Japan. The edibility of a number of other species is unknown.

Because the small, white to buff, flat to slightly funnel-shaped fruiting bodies of the ivory clitocybe (*Clitocybe dealbata*) have no ring on the stalk, have gills that extend down the stalk, and are only 4 cm in diameter and 4 cm high, it is unlikely that this species would be confused with field mushrooms growing in the same habitat. However, the ivory clitocybe could easily be confused with the edible fairy ring mushroom (*Marasmius oreades*), with which it is sometimes associated. Great care, therefore, needs to be taken when picking fairy ring mushrooms. Other poisonous *Clitocybe* species such as *C. nebularis* can be found in mossy or grassy areas, on litter in hardwood and conifer forests, or in heathland.

Collybia dryophila (Oak-Loving Collybia)

Few other woodland mushrooms are as common and widespread in North America as *Collybia dryophila*, whose fruiting bodies can be found scattered or in small clusters from late spring through autumn. Although especially common in oak (*Quercus*) forests, the species also



Collybia dryophila (oak-loving collybia). **AVOID.** (Johnson) occurs in other types of hardwood forests, as well as in those dominated by various conifers. The cap is 1–7 cm in diameter and has a smooth surface that is dark reddish brown to yellow-brown when young but soon fades to orange-brown or tan, with the central portion darker than the margin. The stalk is 3–9 cm high and 2–8 mm thick, smooth, hollow, and distinctly cartilaginous. The gills are crowded, white to pale yellow, and produce a white spore print. *Collybia dryophila* is often confused with *C. butyracea*, though the latter has a pale pink spore print. Both species resemble the fairy ring mushroom (*Marasmius oreades*) but differ in that they occur in forests while the fairy ring mushroom is found in grassy areas. While edible, the thin caps and tough stalk make *C. dryophila* not worth eating.

Flammulina velutipes (Enokitake)

Fruiting bodies of enokitake growing wild on decaying logs look nothing like those of the cultivated mushroom. The caps are smooth and gelatinous, up to 10 cm in diameter, and light tan to light orange-brown toward the center but with pale yellow edges. The tops of the stalks are similar in color to the edges of the caps, but the stalks are dark brown at the base and, unlike the cultivated strains, rarely more than 4 cm high. The gills do not run down the stalk and are pale yellow. The common name is Japanese and comes from enokitake's habit of fruiting on tree species such as Japanese hackberry (*Celtis sinensis*). It is also known as winter mushroom due to its habit of fruiting from late autumn to early winter. Enokitake is even capable of freezing, thawing out, and then continuing to grow (Stamets 2000).

Hygrocybe conica (Witch's Hat)

Hygrocybe conica belongs to a group of small, waxy, brightly colored mushrooms usually referred to as waxy caps. Members of the group characteristically have gills that are thick, soft, and waxy in appearance, much like a wax crayon. This is quite unlike the appearance of the gills in most other gilled fungi. The witch's hat is typical for the group in that it occurs on the ground in moist places on the forest floor, usually (but not always) under conifers. The cap is 3–8 cm in diameter and sharply conic to bell-shaped, often with a prominent raised center, called an umbo. The surface of the cap is smooth, slightly sticky when moist, and scarlet-red to red or orange. The stalk is 2–20 cm long, 0.5–1.5 cm thick, the same color as the cap toward



Flammulina velutipes (enokitake) growing on the stump of a tree has a completely different appearance than the cultivated mushroom. **EDIBLE.** (Hall)



Hygrocybe conica (witch's hat). **EDIBILITY UNKNOWN: AVOID.** (Johnson)

the apex but white toward the base, and appears twisted. When bruised, the flesh of the witch's hat turns black. There is some question as to the edibility of this mushroom. As such, it is best left alone.

Laccaria laccata (The Deceiver)

This edible, highly variable, deceptive mushroom (hence the common name) is often found in clusters under deciduous and coniferous trees in late summer and autumn throughout temperate regions of the Northern Hemisphere. The caps, which are 1.5–6 cm in diameter and have widely spaced gills, are usually reddish brown with peach tones when moist, yellowish brown when dry. The caps are dome-shaped and shiny when young but become flattened with a depression in the center, or funnel-shaped with a wavy edge, as they mature. With age the caps may become dry and dull. The stalks and gills are a similar color to the caps. The stalks are typically 5–10 cm high (though this may be highly variable), 0.5–1 cm thick, and often somewhat compressed or twisted. Moreover, the stalk may have a constant diameter throughout or taper toward either the apex or the base. *Laccaria laccata* sometimes resembles poisonous species.



Laccaria laccata (the deceiver). **EDIBLE.** (Wang)

Laccaria amethystea (Amethyst Laccaria)

The edible and rather common amethyst laccaria is found from late summer to early winter in coniferous or deciduous forests. Its distinctive color, lack of a cortina, and white spores make it unlikely to be confused with a brightly colored poisonous species of, for example, *Cortinarius*. The caps are 1–6 cm in diameter and dome-shaped when young, becoming flattened or depressed in the center as they mature. Like the deceiver, the gills are widely spaced and the stalks are 4–10 cm high, tough, and often twisted.

Lactarius Species

Members of the genus *Lactarius* share many of the same features noted for species of *Russula*, which is not surprising since the two genera are very closely related. In both genera, fruiting bodies have a brittle, granular texture and what could be considered a rather simple overall structure, with no evidence of such features as a ring on the stalk. Moreover, in the majority of species the gills and stalk are white. *Lactarius* and *Russula* are among the more important mycorrhizal



Laccaria amethystea (amethyst laccaria). **EDIBLE.** (Hall)



Lactarius camphoratus (aromatic milky). **EDIBLE.** (Izawa) mushrooms, forming ectomycorrhizal associations with many different kinds of trees in the forests of the world. The most important difference in the two genera is the presence of a latex in the fruiting bodies of *Lactarius* that is absent in those of *Russula*. The latex, which can be clear, milky, or colored, is exuded when the flesh of either the gills or stalk is bruised or cut.

Lactarius camphoratus (Aromatic Milky)

Lactarius camphoratus can be recognized by the combination of a reddish brown cap, reddish brown gills, and a fragrant odor much like that of sweet clover. The aromatic milky is a relatively small mushroom, with a cap 1.5–5 cm in diameter and a stalk 1.5–6 cm tall and 0.3–1.0 cm thick. The cap is at first convex, becoming depressed with age, often with an umbo at the center. The latex is watery white and does not change color. *Lactarius camphoratus* occurs scattered or in groups, usually under or near conifers, in forests throughout temperate



Young fruiting bodies of *Lactarius deliciosus* (saffron milk cap) display the characteristic darker-colored orange blotches on the stem and cap and the orange latex oozing from the cut on the inverted cap. **EDIBLE.** (Hall)

Lactarius deliciosus (saffron milk cap) fruits prolifically under *Pinus radiata* (Monterey pine) in Victoria, Australia. **EDIBLE.** (Hall)



Young *Lactarius deliciosus* (saffron milk cap), some just showing the green markings that appear on old or damaged caps and stems. **EDIBLE.** (Hall)

Practice

Opening Movements

These opening movements have been described in Parts I, II, III. Refer to Part I to refresh your practice.

Hands Down at Sides - Palms Facing Each Other - Bone Breathing - Absorbing Cosmic Chi.

Channeling the Earth Force - Washing the Bone Marrow.
Raise arms to chest height - Palms facing each other.
Rotate arms until palms face down.
Open the Tiger's Mouth - Index Finger up, thumb down.

Activate and Beam to the Eye of the Hip.
Large Intestine 4 - Eye of the Hand.
Pericardium 9 - Tip of the Middle Finger.
Small Intestine 3 - Knife Edge of the Hand.

Absorb the Heavenly Force - Washing the Bone Marrow - Crown to Soles.
Extend the arms forward to chest height - palms upward.

Absorb the Earth Force.
Rotate the arms until the palms face down.
Raise the Index Fingers slightly.

Fig. 8.94 *Mother Earth's Healing Power*

regions of the Northern Hemisphere. This is an edible mushroom. When dried and powdered it is used as a flavoring in some parts of Europe (Philips 1981).

Lactarius deliciosus (Saffron Milk Cap)

Young saffron milk caps have a small depression in the center of the cap that gradually deepens so that mature caps become funnel-shaped. Both the caps and stalks are pale orange, with darker orange blotches arranged in concentric rings on the surface of the cap. Similarly colored blotches are also found on the stalk. Green stains develop on the caps and gills as the caps mature or if they are bruised. The gills, which are bright orange in young caps and dull carrot-orange in mature caps, are attached to the stalk and extend a short way down it. All species of *Lactarius* exude a sticky latex when young caps are broken. In the saffron milk cap, the latex is carrot-orange to bright orange. This mushroom is found in late summer and autumn under spruce (*Picea*) and pines (*Pinus*) throughout Europe, Asia, and North America as well as under pines in southern Australia. It is widely eaten in Europe, particularly in Spain, and is one of the few wild mushrooms collected commercially in Australia. The morphologically rather similar hatsudake (*L. hatsudake*) is widely consumed throughout East Asia.

Lactarius indigo (Indigo Milky)

Few other species of *Lactarius* are as distinctive as *L. indigo*. Its fruiting body is dark indigo-blue in fresh specimens, pale gray-blue in older ones. The latex is also dark blue at first but slowly turns green. The indigo milky is a moderately large mushroom, with a cap 5–15 cm in diameter and a stalk 2–8 cm high and 1–2.5 cm thick. This mushroom is found on the ground in oak (*Quercus*) and pine (*Pinus*) forests in eastern North America. It is edible but has been reported to have a slightly bitter taste.

Poisonous *Lactarius* Species

Three poisonous European species—*Lactarius torminosus* (woolly milk cap), *L. chrysorheus*, and *L. zonarius*—might be confused by a novice for the edible *L. deliciosus* (saffron milk cap). However, these other mushrooms do not have the green markings characteristic of the



Lactarius indigo (indigo milky). **EDIBLE.** (Johnson)



Lactarius zonarius. **POISONOUS.** (Hall)



Lactarius blennius. **POISONOUS.** (Hall)



Lactarius pubescens. **POISONOUS.** (Hall) saffron milk cap, and they have a bitter taste and white latex. As a general rule, it is unwise to eat a *Lactarius* that does not produce red or orange latex immediately after the cap is broken. *Lactarius blennius*, which is commonly found under beech (*Fagus*) in Europe; *L. pubescens*, a species with white latex; and the Australian species *L. piperatus* (Cribb 1987) are all poisonous.

Lepiota, Macrolepiota, and *Chlorophyllum* Species

The parasol mushroom (*Macrolepiota procera*) can have caps up to 40 cm in diameter, but it typically reaches only half this size. When young, the caps are egg-shaped, cream to light brown, covered with darker brown scales, and borne on a stout stalk. As the cap opens, it becomes at first umbrella-shaped and then flattened with a raised central portion without scales. The flesh does not change color when bruised. The covering of scales gives the edge of the cap a somewhat irregular appearance. The hollow stalks are up to 30 cm high, have a prominent ring, and are covered with small scales. The gills are free from the stalk and white at first but eventually turn light brown. Although there is often a swollen base to the stalk, there is no volva. In Europe and eastern North America, parasol mushrooms are found in late summer and autumn on the edges of woods and in grasslands. These mushrooms have a sweet and pleasant taste, are widespread, and are ranked very highly by some.

The shaggy parasol (*Macrolepiota rachodes*) has many features in common with the parasol mushroom, but the scales on the cap are chestnut-colored and the cap turns orange-red when cut. Some people develop intestinal problems after eating the shaggy parasol (Southcott 1974). *Chlorophyllum molybdites* can closely resemble the edible *M. rachodes* since it has a similar shape and size, white gills when young, a ring on the stalk, distinct scales on the cap, and no volva. It can, however, be distinguished by its pale green to lime-green spore print and the green color of the gills in mature fruiting bodies. Poisoning from this mushroom begins one to three hours after eating, with severe abdominal pain that progresses to vomiting, diarrhea, and dehydration. It can be fatal.

Like *Macrolepiota*, species of *Lepiota* typically have rings on the stalk, white gills and spores, gills not attached to the stalk, and no volva. Some species like *L. cristata* are poisonous, with symptoms similar to those caused by *Amanita* (Southcott 1997), and consuming *L. brunneoincarnata* may be fatal. However, these species have a quite



Macrolepiota procera (parasol mushroom). **EDIBLE.** (Buchanan)



Macrolepiota rachodes (shaggy parasol). **EDIBLE.** (Hall)



Chlorophyllum molybdites. **POISONOUS.** (Roody)



Lepiota cristata. **POISONOUS.** (Lyon) different appearance from the edible species *M. procera* and *M. rachodes* and are unlikely to be confused with them. Good illustrations of the suspect and poisonous species can be found in a number of books (see Læssøe and Del Conte 1996, Lincoff and Nehring 1995, Phillips 1981).

Leucopaxillus giganteus (Giant Clitocybe)

As with the giant puffball, the most obvious feature of the giant clitocybe is size: mature funnel-shaped caps can be up to 40 cm in diameter with stalks 4–15 cm high and 4 cm thick. The caps and gills are creamy white, but the caps can develop light brown stains as they age. The cream gills are tightly packed together and extend down the stalk. When young, the edges of the caps are rolled downward. The giant clitocybe often forms very large fairy rings in pastures but can also be found in other grassy areas such as along roadsides. The smell and taste of this mushroom can be mild and pleasant but is sometimes truly disgusting. Occasionally consumption results in stomach cramps and diarrhea.



Leucopaxillus giganteus. **EDIBLE.** (Wang)

Lyophyllum shimeji (Honshimeji)

Honshimeji is a mycorrhizal mushroom that grows in association with various hardwood trees in Japan and other parts of eastern Asia. The caps resemble those of a *Russula* and are 2–8 cm in diameter and buff to light brown or occasionally mid brown. They are strongly convex when young, becoming flattened with age, occasionally with a small depression in the center. The stalks are white to off-white, 2–7 cm high, and somewhat swollen at the base when young. The gills are white to slightly pastel pink or brown. This mushroom is very highly regarded in Japan, where it commands high prices. Researchers there have recently selected a strain of *Lyophyllum shimeji* that is capable of growing saprobically (Fujita et al. 1990, Ohta 1994). This development may eventually result in commercial cultivation of honshimeji.

Marasmius oreades (Fairy Ring Mushroom)

This small fairy ring mushroom has light brown caps that are 2–5 cm in diameter, often with a raised, more darkly colored center portion.



Lyophyllum shimeji (honshimeji). **EDIBLE.** (Izawa)

When fully opened the edges of the caps turn up, revealing widely spaced white, cream, or light brown gills. The tough, fibrous stalks are 2–10 cm high and white at first but turning off-white. The smell is characteristically that of fresh sawdust.

Marasmius oreades can be found in grassy areas such as lawns and pastures from late spring to late autumn. As the fungus grows through the soil it releases nutrients that stimulate the growth of the plants above the ground, often causing them to be a deeper green. As the fungus continues to grow through the soil, nutrients become depleted, toxins are released by the fungus, and the soil becomes somewhat water-repellent, so that plant growth is reduced. However, the fungus only occupies the soil while the nutrients it requires to grow are present; eventually the fungal hyphae die and plant growth returns to normal. Other species that grow in grassy areas and can produce fairy rings include *Agaricus arvensis*, *A. campestris*, *Clitocybe dealbata*, and *Hygrocybe pratensis*, although only the latter two have white spores.



Marasmius oreades (fairy ring mushroom). **EDIBLE.** (Hall)



Marasmius siccus (orange pinwheel). **EDIBILITY UNKNOWN: AVOID.** (Johnson)

Core Movements of Part IV Yin and Yang Channels - Chi Belt

Activating the Yin Channels - Left Side

Turn the palms down and slightly open the index fingers. Smile to your palms and soles and channel the earth force.

Turn your right palm up and pass it just one inch below the left arm yin channels from the left palm to the armpit, **without physically touching the arm**. Feel the Chi moving. Turn your right palm to face your left rib cage and pass your right hand down the left side of your abdomen along the descending colon, and a cross the pelvis to the right side to activate the **yin** energy.



Fig. 8.95 *Channel the Earth Force.*



Fig. 8.96 *Activate the Yin Energy from the Palm to the Pelvis.*



Fig. 8.97 *Raise Chi in the Right Palm.*



Fig. 8.98 *Pass it to the Left.*

Although the fairy ring mushroom has a pleasant flavor that can make a useful addition to soups and stews, it can also be confused with the deadly poisonous *Clitocybe dealbata* and *C. nebularis*, which are often found growing with it.

Marasmius siccus (Orange Pinwheel)

The fruiting bodies of most species of *Marasmius* are smaller than those produced by *M. oreades* and occur in situations where they are less likely to be as easily noticed. Most members of the genus are associated with decaying leaves, pine needles, twigs, and various other smaller bits of plant debris found on forest floors. The fruiting body of a typical species of *Marasmius* is unusual in that it can dry out and become shriveled but then revive and regain the appearance of a fresh specimen when adequate moisture becomes available. *Marasmius siccus* is one of the most colorful and distinctive species in the genus. The rust-orange to rose-colored cap, which looks like a miniature parasol, is pleated, bell-shaped to convex, and 0.3–3 cm in diameter. The flesh is very thin, and the widely spaced gills are white. The stalk, which is white to blackish brown, is very thin (0.2–1.0 mm thick) and relatively long in relation to the size of the cap. *Marasmius rotula* (horsehair mushroom) has a smaller, white cap and a long, shiny black stalk. Moreover, it is more likely to be found on dead twigs and small roots than on dead leaves, the usual habitat for *M. siccus*. Though not known to be poisonous, the fruiting bodies of these and other species of *Marasmius* are much too small to be considered for the table.

Mycena haematopus (Bleeding Mycena)

One of the more distinctive members of the genus *Mycena* is *M. haematopus*, the bleeding mycena. This mushroom is so named because the stalk exudes a deep blood-red latex when broken. Found throughout North America and Europe, the bleeding mycena is common on well-decayed wood, where it occurs in small clusters. The cap is red-brown at the center and reddish gray toward the margin, conical to bell-shaped, and 1–5 cm in diameter. The stalk is 4–10 cm high, 2–3 mm thick, hollow, and typically hairy to strigose at the base. *Mycena haematopus* is edible but hardly worth collecting because of its small size.



Mycena haematopus (bleeding mycena). **EDIBILITY UNKNOWN: AVOID.** (Johnson)



Mycena leaiana (orange mycena). **EDIBILITY UNKNOWN: AVOID.** (Johnson)

Mycena leaiana (Orange Mycena)

Mycena is a large genus that contains a diverse assemblage of mostly relatively small, largely nondescript mushrooms. Only a few species are large enough to be easily noticed or to be considered for the table. One prominent example is *M. leaiana*, which occurs in dense clusters on the decaying wood of various hardwoods throughout central and eastern North America. It is particularly common on beech (*Fagus*). The caps are bell-shaped, 1–5 cm in diameter, smooth, and slightly slimy. A conspicuous bright reddish orange when young, the caps become more yellow as they mature. The gills are crowded, relatively thick, and yellow to pink with bright red-orange edges. The stalk is 3–7 cm high, 1–3 mm thick, and tough, with a base covered in dense, coarse hairs. The edibility of most species of *Mycena* is not known. Although *M. leaiana* is probably not poisonous, there would seem to be little food value in this small species.

Russula aeruginea (Green Russula)

Species of *Russula* are some of the easiest mushrooms to identify, as they have a granular texture when broken, regularly arranged brittle



Russula aeruginea (green russula). **EDIBILITY UNKNOWN: AVOID.** (Johnson) gills, and usually brightly colored caps. When young the caps are dome-shaped, usually with a small depression in the top. As they mature they flatten out and the depression in the cap deepens. The stalks have a constant diameter throughout and are often rounded at the base. There is no ring on the stalk and no volva. All species of *Russula* form mycorrhizal associations with hardwoods or conifers.

Though the fruiting bodies of fungi come in an assortment of colors, some colors are much less common than others. For example, there are relatively few green mushrooms. One prominent member of this underrepresented group is *Russula aeruginea*, rather appropriately called the green russula. Widely distributed in both North America and Europe, *R. aeruginea* typically occurs under oak (*Quercus*), aspen (*Populus*), and birch (*Betula*). The dull green to dark green cap is 3–9 cm in diameter and convex at first but becomes flattened or slightly depressed in mature specimens. The surface of the cap is smooth and slightly sticky when moist. The stalk is 4–8 cm high, 1–2 cm thick, and white or faintly yellow. The green russula is regarded as edible by some authors but probably is best avoided (Arora 1986). Edible species of *Russula* include the wine-colored *R. vinosa*, yellow *R. violeipes*, and greenish *R. virescens*.



Russula emetica (the sickener). **POISONOUS.** (Hall)

Poisonous *Russula* Species

The poisonous Northern Hemisphere species *Russula emetica* (the sickener), *R. mairei* (beechwood sickener), and *R. luteotacta* have red or faded red caps along with white stalks and gills. It is highly unlikely that these would be confused with *Amanita caesarea* (Caesar's mushroom), particularly as the latter has a prominent volva at the base of the stalk. The Japanese species—*R. foetens*, *R. japonica*, *R. omiensis*, *R. senecis*, and *R. subnigricans*—are also toxic (Imazeki et al. 1988). Unless you know a *Russula* species to be edible, do not eat it. Do not eat red, pink, or pink-tinged varieties such as *R. atropurpurea* or those with a hot, bitter, or peppery taste when raw.

A number of species of *Russula* are extremely variable in appearance. To correctly identify these requires careful examination of the color of the spore print, colors of the cap, details of the cap edge, taste, smell, whether the surface layers of the cap can be peeled away, the reaction of the flesh of the fruiting body to various chemicals, and certain microscopic details.



Russula atropurpurea. **EDIBILITY UNKNOWN: AVOID.** (Hall)



The fruiting bodies of *Termitomyces eurrhizus* (termite mushroom) grow from the fungal garden tended by the worker termites. **EDIBLE.** (Izawa)

Termitomyces eurrhizus (Termite Mushroom)

Most termites, which feed on dead plant material such as wood and leaf litter, are only able to digest cellulose and lignin because they have symbiotic protozoa and bacteria living in their intestine. However, the most advanced species in the Macrotermitinae found in Africa, Madagascar, India, and much of Southeast Asia do not have these symbiotic protozoa and bacteria. Instead they rely on their food being processed by one of two dozen mushroom species in the genus *Termitomyces* (Wood and Thomas 1989). These termites forage for food and then deposit fecal pellets on a spongelike "garden" of *Termitomyces* that may be up to 50 cm in diameter. These gardens, which are tended by the worker termites, are inside mounds up to 6 m high and 3 m across and are equipped with air shafts that keep them aerated and cool. Clusters of fungal spores, called sporodochia, develop on the fungal garden and are eaten by the workers, with the king, queen, soldiers, and nymphs living off the salivary secretions of the workers.

When rainfall exceeds about 2 cm per day, *Termitomyces* produces long-stalked, edible mushrooms above the ground that are considered a delicacy. They are widely used as food throughout much of Africa (Rammeloo and Walleyn 1993). Although it is possible to grow *Termitomyces* in culture, all attempts to cultivate these mushrooms commercially have been unsuccessful.

Tricholoma flavovirens (Canary Tricholoma)

The distinguishing feature of the canary tricholoma is the pale yellow to sulfur-yellow color of the cap, gills, and stalk. The caps are usually 5–10 cm in diameter and the stalk is 3–7 cm high. This species can be found as solitary fruiting bodies or in clusters on the ground under conifers and in mixed forests throughout temperate regions of North America and Europe. It typically fruits in late summer and autumn. *Tricholoma flavovirens* is often listed as edible. However, some people develop an upset stomach after eating it, and a few cases of poisoning have been reported. For this reason, it should be avoided.

Tricholoma matsutake (Matsutake)

When young and unopened, the fruiting bodies of matsutake (literally "pine mushroom") are somewhat club-shaped and 10–30 cm long. They are creamy white with a light brown top and brown



Tricholoma flavovirens (canary tricholoma). **EDIBILITY UNKNOWN: AVOID.** (Johnson)



Grade-one fruiting bodies of *Tricholoma matsutake* (matsutake), the most important edible mushroom in Japan. **EDIBLE.** (Hall)

blotches along the sides. At this immature stage the mushrooms are mostly below ground, with perhaps only the tops showing through cracks in the soil surface. As they open, the fruiting bodies take on a more conventional mushroom shape. When fully expanded, the caps



Grade-three fruiting bodies of *Tricholoma matsutake* (matsutake) are at the stage of growth just before the cap opens. **EDIBLE.** (Hall)

are creamy brown with prominent brown markings and can be 10–30 cm in diameter. The stalks are typically 10–20 cm high and have a ring toward the top and coloring similar to that of the caps.

In Japan matsutake is primarily associated with *Pinus densiflora* (Japanese red pine), an early colonizer of bare or disturbed soil, although it is also associated with a range of other conifers. This mushroom forms distinctive white, compact fungal colonies in the soil, called the shiro. These occur just below the litter layer and can be up to 25 cm thick. Volatile antibiotics produced in the shiro eliminate most soil microorganisms (Ogawa 1977, Ohara and Hamada 1967). Fruiting normally begins when the host trees are about twenty years old and 4–5 m high. Production peaks in forty- to fifty-year-old forests and can reach 100 kg per hectare. It then gradually declines over the following thirty to forty years as the litter layer builds up and Japanese red pine is replaced by other trees such as deciduous oaks.

Matsutake is more than just a food in Japan: it is a symbol of autumn and a special part of Japanese culture. Such is the status of this mushroom that many presentation packs of matsutake are never eaten but are instead kept as symbols of autumn and friendship. It is quite an expensive mushroom too, however, and so many people succumb to the temptation of trying it in their favorite dish. Thinly slicing the fruiting bodies lengthwise and then cooking slivers in

Roasting *Tricholoma matsutake* (matsutake) over a charcoal fire, Yamagata Mura, Japan. (Hall)



A typical *Tricholoma matsutake* (matsutake) forest in Japan with about 75 percent canopy cover and limited understory plants. The positions of previously collected matsutake have been marked by colored flags and show the approximate extent of the shiro. (Hall)

Pass your right hand up the right side of the abdomen to the level of your forehead with the palm facing diagonally toward the left palm (which simultaneously turns palm up at the level of the navel). Project the Chi from palm to palm for 30 to 60 seconds, vibrating the palm and feeling Chi from the right palm sent to the left picking up by the left palm. Keep the palms open and relaxed.

Next point the right ring finger toward the left palm and project Chi making very small circles from the right ring finger (Triple Warmer channel); emit the Chi to the left palm for 30 to 60 seconds.

Then return the right index finger to neutral position. Point the left ring finger up toward the right palm, project into the right palm for 30 to 60 seconds, and then return to neutral.

Next both ring fingers project toward the opposite palms at the same time for 30 to 60 seconds and then return to neutral. Notice that the energy may meet in the middle.



Fig. 8.99 *Project Energy and balance Left and Right.*

Activate the Yang Channels - Left Side

Turn the left palm down and lower the right palm to cover the back of the left hand, palm down. Pass the right palm over the left arm's **yang** channels from the back of the left hand to the left shoulder. Then pass the right palm across the upper chest and across the right breast. Scoop the right palm under the right armpit, fingers first. Then bring the right palm forward, palm down and press forward with the left palm at the same time. Relax and channel the earth force.



A small tunnel house, called a "Hiroshima tunnel," is used to stimulate the fruiting of *Tricholoma matsutake* (matsutake) in Japan. (Hall) miso soup is one way to enjoy matsutake. One of Ian Hall's most memorable experiences in Japan was eating this mushroom in a thatched cottage in Yamagata Mura at the northern end of Honshu. There, surrounded by good company and lubricated with more than adequate quantities of sake, matsutake was simply roasted over a charcoal fire.

If you are invited to a Japanese home for dinner during autumn, a suitable present would be a small presentation pack of unopened grade-one matsutake. But beware: Because of the shape of unopened fruiting bodies, in past times the word "matsutake" became synonymous with the male organ. Consequently, in polite company the word was dropped in favor of "the take." When Ian visited a wholesaler near Hiroshima, a packer went into a fit of giggles when asked to bring out specimens of grade-one matsutake, and his interpreter showed distinct discomfort when asked to hold one while he took a photograph. As previously mentioned, this is a pricey mushroom, so when you go out to buy your presentation package take plenty of money. At the start of the fruiting season, in late August, prices for unopened grade-one matsutake can be up to 160,000 yen ($1250) per kilogram, with prices reflecting grade, quality, origin, and availability.

In the early 1940s about 12,000 tons of matsutake were harvested each year in Japan, but since then production has gradually fallen to about 1000 tons (Wang et al. 1997). Another 2000 tons of matsutake, white matsutake (*Tricholoma magnivelare*), and European matsutake (*T. caligatum*) are imported from Canada, China, Korea, Morocco, Taiwan, and the United States, but demand still exceeds supply, which is why matsutake commands very high prices. The estimated annual retail market for matsutake in Japan is worth $250 to $500 million.

All attempts to produce matsutake-infected plants and establish new matsutake forests have failed. However, considerable progress has been made in Japan in developing methods to maximize production in forests where matsutake occurs naturally (Ogawa and Ito 1989). Surveys show that production is greatest when the canopy provides only 75 percent cover, the shrub layer is relatively sparse, the soil is moist but not wet, and the litter layer is about 3 cm deep. It has also been found that production can be increased by raking the litter layer to reduce the depth to 3 cm, and by removing some of the shrubs and large trees to ensure adequate aeration and to allow sufficient sunlight onto the forest floor (Ogawa and Ito 1989). Modifying the soil humidity and temperature by erecting irrigated tunnels over shiros, the so-called Hiroshima method, has also been found to stimulate



Tricholoma magnivelare (white matsutake) is slowly gaining favor in Japan. It can fruit in Canada right up to the first snowfall. **EDIBLE.** (Hall) fruiting (Iwase et al. 1988, Tominaga 1975, Tominaga and Komeyama 1987). In South Korea plastic tunnels have been replaced with small plastic hoods or caps to cover shiros or individual fruiting bodies.

Tricholoma terreum

Tricholoma terreum is fairly common throughout temperate regions of the Northern Hemisphere, where it can be found fruiting in late summer and autumn. The caps are light to dark gray, often with a slight violet hue when young, and 4–10 cm in diameter. The gills and stalks are white. The stalk is up to 8 cm high and has no ring. The gills are attached to the stalk but do not extend down it. The taste of this mushroom is pleasant but not outstanding.

Other *Tricholoma* Species

Like *Lepiota*, some species of *Tricholoma* are either suspect or known to be poisonous. Tiger tricholoma (*T. pardinum*) causes severe intestinal symptoms and in the early 1900s was responsible for about 20 percent of all poisonings in Switzerland (Bresinsky and Besl 1990).



Tricholoma terreum. **EDIBLE.** (Hall)



Tricholoma ustale (burnt tricholoma). **POISONOUS.** (Izawa)



The fruiting bodies of *Tricholoma pessundatum* under *Pinus radiata* (Monterey pine). **POISONOUS.** (Wang)

Tricholoma ustale (burnt tricholoma) is a common cause of poisoning in Japan, presumably because of its similarity to *T. bakamatsutake* and *T. matsutake*.

While *Tricholoma pessundatum* has been consumed by some without ill effects, others have experienced twenty-four hours of moderate stomach upsets. It is possible, however, that the ill effects were caused by the presence of bacteria in old, decaying mushrooms rather than by the mushrooms themselves. Symptoms of diarrhea, sweating, difficulty in focusing, and restriction of the pupils have also been reported after ingestion of an unidentified species of *Tricholoma* (Southcott 1997).

Hypomyces lactifluorum (Lobster Mushroom)

Hypomyces lactifluorum is a parasitic fungus that infects species of *Lactarius* and *Russula*. The infection of the mushroom by this fungus distorts the shape of the fruiting body, producing a funnel-shaped structure 10–15 cm wide and 7–15 cm high with a stalk 5–10 cm thick. The infected mushrooms are characteristically bright orange. They can be found from midsummer to midautumn and are very popular in North America, where they are frequently available in markets and featured widely on restaurant menus.



Hypomyces lactifluorum (lobster mushroom). **EDIBLE.** (Hall)

---

2. Mushrooms with gills and a more or less centrally placed stalk; pale pink spore print

---

Entoloma Species

The fruiting bodies of *Entoloma* species can be confused with those of edible *Lepista* species because they have pink spores and pale lilac to buff to lilac-brown gills that are attached to the stalk. Some species of *Entoloma* are edible; others, such as *E. rhodopolium*, are poisonous. The novice would be wise to avoid species in this genus.

Lepista Species

Species of *Lepista* produce a pale pink spore print. When the spores are observed under a microscope they are found to be elliptical and covered with minute spines, particularly if stained with cotton blue, a dye commonly used by mycologists. It is very important to make a spore print when identifying species of this genus, as it is possible to



Entoloma rhodopolium. **POISONOUS.** (Izawa)



Lepista nuda. **EDIBLE WHEN COOKED.** (Lyon)



Lepista aff. *luscina*. **EDIBLE WHEN COOKED.** (Hall) mistake some for brown-spored species of *Cortinarius*, which may be poisonous. Many species of *Lepista* have the odor of a sweet perfume and the general shape of a *Tricholoma*. No species of *Lepista* appears to be toxic, provided it is cooked first (Benjamin 1995).

Lepista nuda has lilac-tinged gills when young, but these turn pale pinkish brown as the mushroom ages. The caps are at first conical, later becoming flattened with a raised portion in the center, and are 6–12 cm in diameter. The stalks are 5–9 cm high, sometimes with a bulbous portion at the base. This mushroom has a very powerful, attractive smell. In Europe and North America it is found in woodlands, hedgerows, and gardens in late summer to autumn and occasionally throughout winter. Techniques have been developed in France for cultivating *L. nuda* (Guinberteau et al. 1989), so it is now available in European markets. Other edible species in the genus include *L. irina*, *L. luscina*, and *L. personata*.

Pluteus atricapillus (Deer Mushroom)

Another group of pink-spored mushrooms is represented by members of the genus *Pluteus*. These small to medium mushrooms occur on decaying wood and wood debris, most often from broadleaf trees. Perhaps the most commonly encountered species is *P. atricapillus*,



Pluteus atricapillus (deer mushroom). **EDIBLE.** (Johnson)



The fruiting bodies of *Volvariella speciosa* showing the distinctive volva at the base of the stem. **EDIBLE.** (Wang)

also known as *P. cervinus*, which can be quite common in forests throughout North America and Europe from late spring until early autumn. The dark brown to drab brown cap is 5–14 cm in diameter, smooth to fibrous, and convex to somewhat flattened. The gills are white when young but become pink as the spores mature. The stalk is white, 5–12 cm high, 6–16 mm thick (becoming enlarged toward the base), and streaked with tiny grayish brown hairs. *Pluteus atricapillus* is edible, but the flesh of this mushroom is soft and quickly spoils in warm weather. As a result, specimens must be refrigerated or prepared for the table as soon as possible after being collected.

Volvariella Species

Like *Amanita*, the fruiting body of *Volvariella* develops within a cup-shaped volva, the remains of which can be seen at the base of the stalk of mature fruiting bodies. While *Volvariella* has no ring on the stalk, this is not a reliable characteristic for distinguishing this genus from *Amanita* because rings are not found on all *Amanita* mushrooms. However, the two genera are relatively easy to distinguish from the



A. *Left Palm down, lower Right Palm to cover the back of Left Hand.*

B. *Pass the Right Palm over the Left Arm's Yang Channels.*



C. *Pass the Right palm across the chest and scoop under the Right Armpit, Fingers first.*

D. *Press both Palms forward, relax and channel the Earth Force.*

Fig. 8.100 *Balance Left Side Yin and Yang and Channel Earth Energy.*



Volvariella volvacea (straw mushroom) fruiting on plant debris in the wild. **EDIBLE.** (Izawa)

spore print—*Volvariella* has a pink spore, whereas that of *Amanita* is white. The cultivated *V. volvacea* can be found fruiting in tropical countries, while other species, such as *V. speciosa*, are common in temperate countries on ground containing considerable organic matter, such as stable manure and compost heaps.

3. Mushrooms with gills and a more or less centrally placed stalk; brown spore print

Agrocybe Species

The brown-spored *Agrocybe* species can be confused with *Agaricus* species, but they have a prominent, though thin, sometimes membranous ring on the stalk. The gills are a little paler than those found in *Agaricus* species and are attached to the stalk. In some species of *Agrocybe*, the gills may extend down the stalk a short distance. Many species are edible. The edible *Agrocybe praecox* is often found in pastures rich in animal waste, where its fruiting bodies might be confused with those of *Agaricus* species. Many species of *Agrocybe* occur on



Agrocybe parasitica. **EDIBILITY UNKNOWN: AVOID.** (Fowler)

wood, and some are parasites. *Agrocybe parasitica*, for example, is a parasite on trees and can often be found fruiting on decaying stumps. A few species of this genus have been cultivated and are becoming popular in parts of China.

Cortinarius Species

The many species in this genus have rust-brown spores and a cortina, which extends between the edge of the cap and the stalk on immature fruiting bodies. The remains of the cortina may be found on the stalk or along the margin of the cap on older fruiting bodies. Species of *Cortinarius* also often have a distinct bulb at the bottom of the stalk. Many have yellowish, orange-red, purplish, violet, or greenish stalks and flesh. Some species are edible, but *C. orellanus* is deadly poisonous, and the toxicity of many other species is unknown. The genus is therefore best avoided by the novice. Members of this group of mushrooms are ecologically important because they form ectomycorrhizal associations with their host trees. At times, especially in some high-latitude spruce (*Picea*) forests of the Northern Hemisphere, the fruiting bodies of *Cortinarius* are exceedingly common.



Young fruiting bodies of *Cortinarius*, with the cortina covering the gills of the cap on the left. **EDIBILITY UNKNOWN: AVOID.** (Hall)



Unidentified *Cortinarius* species. The discolored markings on the stalk of the largest mushroom represent all that remains of the cortina. **EDIBILITY UNKNOWN: AVOID.** (Hall)



Many species of *Cortinarius* are vividly colored. **EDIBILITY UNKNOWN: AVOID.** (Hall)

Galerina Species

Members of the genus *Galerina* have brownish, relatively small caps up to 7 cm in diameter, and brown spores. There can be a ring on the stalk, which tends to be scaly below the ring. *Galerina mutabilis* is considered edible and good (Phillips 1981). However, *G. autumnalis* contains amatoxins and is considered deadly poisonous. *A Colour Atlas of Poisonous Fungi* (Bresinsky and Besl 1990) lists a number of poisonous species of this genus, including *G. marginata* ("Dangerously poisonous fungus! Can be fatal!"). Of the three species listed in *The Audubon Society Field Guide to North American Mushrooms* (Lincoff and Nehring 1995), two are considered deadly. Some poisonous species have been confused with *Armillaria mellea* and other edible species. Because some poisonous species of *Galerina*, such as *G. unicolor*, are often found in damp grassy or mossy areas and a number of these can have a raised peak in the center of the cap, it is perhaps not surprising that they have been mistaken for species of *Psilocybe*.

Gymnopilus junonius (Big Laughing Gym)

The pale orange to orange-brown fruiting bodies of the big laughing gym can be found in late summer and early autumn in spectacular



Galerina fasciculata. **POISONOUS.** (Izawa)



Gymnopilus junonius (big laughing gym). **POISONOUS.** (Hall)



Hebeloma crustuliniforme (poison pie). **POISONOUS.** (Hall)

clusters on stumps and on soil containing rotting wood. The caps are up to 18 cm in diameter with a surface that is suedelike or covered with tiny scales. The gills are brown and often covered with a dusting of rusty brown spores. The stalks are somewhat lighter in color than the cap and are up to 20 cm high and 3 cm thick. There may be a ragged ring on the stalk or merely a darker zone where the veil was attached. The smell of this mushroom is not unpleasant, but it has a very bitter taste and so is unlikely to be consumed for its psilocybin content. Consumption may result in uncontrollable laughter, nausea, abdominal pain, convulsions, or death (Benjamin 1995, Craw 1995).

Hebeloma and *Inocybe* Species

Mushrooms belonging to the genera *Hebeloma* and *Inocybe* have ochre to brown spores, and most have no ring on the stalk. *Hebeloma crustuliniforme* (poison pie) and *H. sinapizans* have tan caps, light brown gills, whitish stalks, and are found associated with hardwoods and conifers in late summer and autumn. Both species smell strongly of radish and have a bitter taste. Many species of *Inocybe* have a small brown cap with a raised center and a variety of strange smells,



Inocybe fastigiata, one of the little brown mushrooms. **POISONOUS.** (Izawa)

including that of semen. The gills are grayish beige when young, turning darker brown with age. Although most are associated with hardwoods and conifers, some can be found in the grassy margins of paths and trails. Many *Hebeloma* and *Inocybe* species, including those referred to in *The Audubon Society Field Guide to North American Mushrooms* (Lincoff and Nehring 1995), are of unknown



Inocybe geophylla. **POISONOUS.** (Izawa)



An unidentified species of *Inocybe*. **POISONOUS.** (Hall)

edibility or are toxic due to their muscarine content. No European species are considered edible (Phillips 1981), many are poisonous, and *I. patouillardii* (red-staining inocybe) is potentially deadly.

Paxillus involutus (Brown Roll Rim)

Found in the Northern Hemisphere on deciduous trees such as beech (*Fagus*) and birch (*Betula*) in late summer and autumn, the brown roll rim has caps 5–12 cm in diameter on stalks up to 8 cm high. It can be identified by the strongly inward-rolled edge to the yellowish brown to mid brown cap, the concave often slimy center of the surface of the cap, the gills extending down the stalk, and the brown spores.

In many parts of the world the brown roll rim is considered safe to eat, although if not cooked properly it may cause severe gastric upsets within one or two hours of eating. It is suspected that people who have eaten the mushroom in the past without any apparent harmful effects may develop an allergy to it, which only shows up perhaps several years later (Bresinsky and Besl 1990). Because poisoning is an acquired allergic response to the brown roll rim, others who have eaten it at the same meal often appear to be completely unaffected.



Paxillus involutus (brown roll rim). **POISONOUS.** (Hall)

Symptoms include abdominal pain, vomiting, diarrhea, pain in the region of the kidneys, and kidney failure. Consumption of raw or poorly cooked brown roll rim can also lead to direct gastrointestinal symptoms (Southcott 1997). *Paxillus involutus* (brown roll rim) has been confused with *Lactarius deliciosus* (saffron milk cap). The other species in the genus are either not edible or are of unknown edibility. Consumption of *Paxillus* species is therefore best avoided.

Pholiota Species

Species of *Pholiota* are found in summer to late autumn at the bases of trees or on rotting stumps or logs, occasionally on living trees, or on burnt ground. The yellowish to light brown to brown caps, which can be up to 12 cm in diameter, may be very gelatinous, but many species have conspicuous scales on the edge or surface of the cap and/or stalk. Some species are very slimy, as with *P. nameko* (nameko). It is this textural characteristic, in addition to flavor, that makes nameko a favorite in Japan and other East Asian countries. While nameko is one of the ten most important cultivated mushrooms in the world, its characteristic sliminess also makes it unattractive to some in the West. While *P. adiposa* and a number of other species are eaten in

Repeat, Activating the Yin and Yang Channels to the Right Side



Fig. 8.101 *Balance right side yin and yang and channel earth energy*

Then repeat **Activating the Yin and Yang Channels** with the other fingers and channels in the following order:

Index Finger - Large Intestine
Thumb - Lung
Pinky Finger - Heart and Small Intestine
Middle Finger - Pericardium



Fig. 8.102 *One Finger Art - activating the Laogong.*



Pholiota adiposa (fat pholiota) displays the scaly cap and stalk characteristic of some members of the genus. **EDIBILITY UNKNOWN: AVOID.** (Hall)

China (Ying et al. 1988) and Japan (Imazeki et al. 1988), Roger Phillips (1981), author of *Mushrooms and Other Fungi of Great Britain and Europe*, variously lists the European species he illustrates as "edibility unknown," "not edible," or "edible—not worthwhile." *Pholiota highlandensis*, *P. limonella*, and *P. terrestris* are mildly toxic and may cause mild to moderate stomach upsets (Benjamin 1995, Imazeki et al. 1988).

Pholiota squarrosa (Scaly Pholiota)

One of the most distinctive and easily identified species in the genus *Pholiota* is *P. squarrosa*. Both the surface of the cap and the stalk are covered in coarse, red-brown or yellow-brown, down-turned scales. The convex to somewhat flattened cap is dry, yellow-brown, 2.5–10 cm in diameter, and has an incurved margin that usually contains fragments of the partial veil. The very similar species *P. squarrosoides* can be distinguished from *P. squarrosa* by virtue of having a cap with a sticky surface and more erect, pointed scales. The stalk of the scaly pholiota is 5–10 cm tall and 0.3–1.5 cm thick, tapering slightly toward the base. Like most other species of *Pholiota*, the scaly pholiota occurs on wood, from both broadleaf trees and conifers. The species is widely distributed throughout temperate regions of the Northern Hemisphere. *Pholiota squarrosa* has been regarded as edible by some people but can cause severe gastrointestinal discomfort and should therefore be avoided.



The clustered habit of *Pholiota squarrosa* (scaly pholiota) is characteristic of many species in this genus. **AVOID.** (Hall)

4. Mushrooms with gills and a more or less centrally placed stalk; purple-brown to black spore print

Agaricus arvensis (Horse Mushroom)

The large, excellent-tasting horse mushrooms, with caps 6–20 cm in diameter, are commonly found in pastures from late summer to late autumn, usually in clusters but sometimes in huge fairy rings. At first the mushrooms are white with a fine suedelike surface, and they have a shape similar to the button mushroom, although they are larger. As the caps open they become gently convex and creamy white, sometimes with yellowish patches. The stalks are up to 10 cm high and 3 cm thick, with a ring formed of two thin layers. The gills are pale grayish brown at first, turning pinkish brown and then chocolate-brown.

Agaricus campestris (Field Mushroom)

Field mushrooms are smaller than horse mushrooms, rarely reaching more than 10 cm in diameter, and have a smoother surface. They are common in pastures, as their name suggests, and are never associated

A fairy ring formed by *Agaricus arvensis* (horse mushroom). **EDIBLE.** (Hall)



Agaricus arvensis (horse mushroom). **EDIBLE.** (Wang)

with trees. The gills are pink both before and after the caps open, only turning brown when the caps are fully expanded. While the stalks may be slightly yellow toward the base, they do not stain chrome-yellow like the poisonous *Agaricus xanthoderma*.

Agaricus xanthoderma (Yellow Stainer) and *Agaricus pilatianus*

Agaricus xanthoderma and *A. pilatianus* have relatively large caps, up to 15 cm in diameter, with prominent rings on the stalks. The gills are white when young, becoming brownish with age. They therefore superficially resemble the common field mushroom (*A. campestris*), but both species are poisonous and should not be eaten. *Agaricus xanthoderma* can be easily distinguished because it stains bright yellow when bruised or cut, while *A. pilatianus* stains yellow only when young. Because both *A. xanthoderma* and *A. pilatianus* are similar to the edible species of *Agaricus*, they are a common cause of poisonings. The genus *Agaricus* contains a number of other toxic species, including the deadly poisonous *A. aurantioviolaceus*, which is found in tropical Africa (Walleyn and Rammeloo 1994).



Agaricus campestris (field mushroom) fruiting in a well-tended lawn. **EDIBLE.** (Hall)



Agaricus xanthoderma (yellow stainer). **POISONOUS.** (Hall)

Coprinus atramentarius (Common Ink Cap)

The light brown caps of the common ink cap are larger than those of the non-inky coprinus (*Coprinus disseminatus*); they are typically 3–7 cm high and 4–7 cm in diameter. The caps are borne on a white stalk 7–17 cm high, which can have the remains of a ring close to the base. This species is often found growing in unlikely places such as along roadsides and in waste areas where there is rotting wood in the soil. It also occurs in lawns. The caps are edible but must be cooked within a few hours of picking as they rapidly turn black and release the spores in a black liquid (which, incidentally, was used in the past as a substitute for ink). If consumed with alcohol or within twenty-four hours of having had any alcohol, the common ink cap will cause a period of extreme nausea, stomach cramps, and palpitations. These symptoms are so unpleasant that the mushroom has been used to cure alcoholics. In North America the scaly ink cap (*C. variegatus*) has similar effects if eaten with alcohol (Fischer and Bessette 1992), as does *C. africanus*, a species normally found growing on dung in tropical Africa (Walleyn and Rammeloo 1994).



Coprinus atramentarius (common ink cap) is unlikely to be confused with the shaggy ink cap. **DO NOT CONSUME WITH ALCOHOL.** (Lyon)

Coprinus comatus (Shaggy Ink Cap)

The shaggy ink cap is much larger than the common ink cap, occasionally reaching as much as 40 cm in height. The caps are cylindrical at first but eventually become bell-shaped. The gills are initially white, soon turning pink and then black. Once the gills are black, the bottom edge of the cap begins to drip a black liquid that contains the spores. Shaggy ink caps are usually found in waste areas and along roadsides during late summer to late autumn. Old caps do not look very appetizing but do have a good flavor, though they must be cooked within a few hours of picking. This mushroom is very widely distributed throughout the world, in part because it has been introduced into regions where it is not indigenous.

Coprinus disseminatus (Non-Inky Coprinus)

Most members of the genus *Coprinus* are characterized by fruiting bodies with gills that dissolve, producing an inky fluid, when the spores are mature. This process, called deliquescence, accounts for



Coprinus comatus (shaggy ink cap) just before the release of spores. **EDIBLE.** (Buchanan)



Coprinus comatus (shaggy ink cap) releasing spores in a black ink. **EDIBLE.** (Hall)



Coprinus disseminatus (non-inky coprinus). **EDIBLE.** (Izawa) the name “ink cap.” *Coprinus disseminatus* is an exception to this rule, as its gills do not become inky. The fruiting bodies occur in large groups (often several hundred in a single fruiting) on well-decayed stumps and other wood debris from broadleaf trees. The rather delicate pale buff to brownish gray caps are 0.5–1.5 cm in diameter, have a deeply grooved margin, and are ovoid at first but expand to become bell-shaped to convex. The stalk is 15–40 mm high and 1–3 mm thick. This mushroom is edible but not worth eating because of its small size.

Hypholoma fasciculare (Sulfur Tuft)

The bright yellow fruiting bodies of the sulfur tuft can be found throughout the year on fallen logs or stumps of deciduous trees. The caps are 2–8 cm in diameter, the stalks up to 10 cm high. The gills are sulfur yellow when young, becoming olive and finally brown. The remnants of the veil often remain attached to the edge of the cap. Although the sulfur tuft has a mushroomy smell, the taste is bitter. Symptoms of poisoning begin up to nine hours after consumption and include nausea, vomiting, and abdominal pain. Fatalities have been reported in Japan and Europe (Fischer and Bessette 1992), though the mushroom is described in *Mushrooms and Other Fungi of Great Britain and Europe* (Phillips 1981) as merely inedible.

Panaeolus foenisecii (Haymaker's Mushroom)

The fruiting bodies of *Panaeolus foenisecii* occur scattered or in small groups in lawns and other grassy areas. The species is often very common, especially in the Northern Hemisphere, and can be found from late spring to early autumn. The cap is 1–3 cm in diameter and occurs on a stalk that is 2.5–10 cm high and 1.5–3.0 mm thick, with no hint of a ring. More or less bell-shaped when young, the cap expands and becomes almost flat in fully mature fruiting bodies. The cap is at first reddish brown to grayish brown, usually fading to grayish tan, often with a dark band apparent near the margin. The gills are thin and grayish brown to tan, the spore print deep brown or purple-brown. Though small and thus easily overlooked, the haymaker’s mushroom is potentially poisonous to a small child who is at the stage in which everything goes into the mouth. Instances have been reported of dogs consuming this fungus and showing evidence of its hallucinogenic properties.

Activate the Chi Belt - Right Foot Forward

Step forward with the right foot. The right palm covers the navel and the left palm covers the Door of Life. Feel the Chi beam penetrate from palm to palm.

Turn your hips to the right and shift weight to your right leg. At the same time move your right palm to the Door of Life in a brushing manner, while your left palm moves to the right hip in a sweeping manner. Note that the palms face the Chi belt.

Repeat the above three times altogether.



Fig. 8.103 *Activate the Chi Belt - Right Side.*

Activate the Chi Belt - Left Foot Forward

Repeat the above with the left foot forward and reversing the right and left hands.



Fig. 8.104 *Activate the Chi Belt - Left Side.*



Coprinus disseminatus (non-inky coprinus). **EDIBLE.** (Johnson)



Clustered fruiting bodies of *Hypholoma fasciculare* (sulfur tuft) at the base of a stump. **POISONOUS.** (Izawa)



Panaeolus foenisecii (haymaker's mushroom). **POISONOUS.** (Johnson)



Psathyrella candolleana (common psathyrella). **AVOID.** (Hall)

Psathyrella candolleana (Common Psathyrella)

Psathyrella is a large genus containing several hundred species, most of which are quite small and of unknown edibility. *Psathyrella candolleana* is often found in lawns or in areas where there is an abundance of decaying wood debris, such as under trees or on or near rotting stumps. The caps are 2–7 cm in diameter, the stalks 4–10 cm high. While some consider *P. candolleana* edible, its thin caps and fragile stalks might easily be confused with small, poisonous, dark brown-spored mushroom species, which makes its collection and consumption not worth the risk.

Psilocybe Species

The small, almost insignificant species of *Psilocybe* are perhaps as well recognized as *Amanita muscaria*. This is not because of their food value, which must be trivial, but because of the hallucinogenic LSD-like effects produced by eating them. These effects are caused by the tryptamine derivatives psilocybin and psilocin, which begin to take effect fifteen minutes to two hours after consumption and last for up to five



Psilocybe argentipes, one of the many hallucinogenic species in the genus. **POISONOUS.** (Izawa) hours. Most species grow in grasslands or on rotting wood, dung, and compost where there is abundant organic matter (Stamets 1996).

Species of *Psilocybe* are little brown mushrooms. Consequently the novice in search of a hallucinogenic experience runs a very real danger of consuming other poisonous or possibly deadly little brown mushrooms of the genera *Clitocybe*, *Conocybe*, *Galerina*, and *Inocybe*, which occur in similar habitats. There are large amounts of popular literature available on hallucinogenic mushrooms—Web sites such as Psylocybe Fanaticus and The Vaults of Erowid, for example, and the book *Psilocybin Mushrooms of the World* (Stamets 1996)—but users should be aware of a country's laws governing their collection and use. Other hallucinogenic mushrooms containing tryptamine derivatives include *Copelandia cyanescens*, *Gymnopilus*



Psilocybe fasciata. **POISONOUS.** (Izawa)



The fruiting bodies of *Psilocybe semilanceata* (liberty cap) display the characteristic long stalks. **POISONOUS.** (Lyon)



The fruiting bodies of *Psilocybe subaeruginosa* (little blues), another member of the little brown mushrooms. **POISONOUS.** (Johnston)



The slimy caps and stems of *Stropharia aeruginosa* (blue-green stropharia) are characteristic of the genus. **POISONOUS.** (Hall) *junonius*, *Panaeolus foenisecii* and other *Panaeolus* species, and some species of *Mycena*, *Psathyrella*, and *Stropharia* (Allen et al. 1991, Benjamin 1995, Beug 1999, Bresinsky and Besl 1990).

Stropharia aeruginosa (Blue-Green Stropharia)

Like most members of the genus, *Stropharia aeruginosa* has caps that are slimy when wet. These are blue-green, 2–8 cm in diameter, and dome-shaped when young, becoming flattened with age. The gills are white to begin with but turn purple or chocolate-brown. The stalks are 3–8 cm high, up to 1 cm thick, and may have a fragile ring that often disappears with age. This species is found during spring, summer, and early winter in a wide variety of habitats, including forests and pastures, particularly where there is abundant woody debris in the soil. While some species in the genus are edible, *S. aeruginosa* is poisonous.

5. Mushrooms with ear-shaped or bracket-like fruiting bodies; stalk either absent or poorly developed and attached to the edge of the cap; spores produced on gills, gill-like folds, or directly on the lower undifferentiated surface of the fruiting body

Lampteromyces japonicus

The fruiting bodies of *Lampteromyces japonicus* have caps very similar in appearance to those of shiitake (*Lentinula edodes*), but the former has a laterally attached stalk and the cap is rose-pink. Both species are found growing on decaying tree trunks. Along with *Entoloma rhodopolium* and *Tricholoma ustale* (burnt tricholoma), *Lampteromyces japonicus* shares the distinction of being one of the three most common causes of mushroom poisoning in Japan (Benjamin 1995, Imazeki et al. 1988). Like *Omphalotus*, the fruiting bodies are bioluminescent.

Omphalotus Species

Members of the genus *Omphalotus* share a most unusual feature not found among many other mushrooms: their gills glow in the dark. However, this bioluminescence can only be observed in fresh specimens in which the spores are still forming. The species found in Europe (*O. olearius*), North America (*O. olivascens* and *O. illudens*), and



Lampteromyces japonicus. **POISONOUS.** (Izawa)



The gills of the bioluminescent *Lampteromyces japonicus* glow in the dark. **POISONOUS.** (Buchanan)

Australia (*O. nidiformis*) all have gills that glow in the dark and share a common characteristic of fruiting in late summer and autumn. *Omphalotus olearius* is found on the roots of trees, particularly chestnut (*Castanea*), oak (*Quercus*), and olive (*Olea*), while *O. olivascens* and *O. illudens* typically occur on the dead stumps of hardwood trees or buried wood. In Australia *O. nidiformis* is common on *Eucalyptus* and other native trees as well as on stumps of exotic pines (*Pinus*).

Omphalotus illudens, *O. olearius*, and *O. olivascens* (the jack-o'-lanterns) are sometimes confused with the honey mushroom (*Armillaria mellea*), which also occurs on dead stumps of hardwood trees. The cap of *O. illudens*, found in eastern North America, is 7–18 cm in diameter, and its gills extend down the upper portion of the stalk, which is 5–18 cm high. Because of their color and size, the jack-o'-lanterns are easily noticed in the forests in which they occur—a fact that undoubtedly increases the odds that an unsuspecting person will collect these mushrooms to eat. Poisoning from *Omphalotus* causes intestinal problems that begin a few hours after eating and that can last for up to two days.



Omphalotus nidiformis under *Pinus radiata* (Monterey pine) in Victoria, Australia. **POISONOUS.** (Fuhrer)



Omphalotus illudens (jack-o'-lantern). **POISONOUS.** (Johnson)

The fruiting bodies of *Omphalotus illudens*, *O. nidiformis*, *O. olearius*, and *O. olivascens* are shades of yellow or orange and are therefore somewhat suggestive of chanterelles. However, they all have clearly distinct gills and white or cream spores. The similarity of *O. nidiformis* to the edible *Pleurotus ostreatus* (oyster mushroom) has resulted in a number of poisonings, although the presence of bioluminescence in *Omphalotus* is a useful distinguishing feature (Southcott 1997).

Pleurotus ostreatus and Similar Species (Oyster Mushroom)

The fruiting bodies of *Pleurotus* are usually flattened, with the stalks attached either eccentrically or to one edge of the cap. They are found on dead or moribund trees or logs, usually in autumn, although *P. ostreatus* can be found at any time of the year. The spores can be lilac, gray, or white. Several species of *Pleurotus* are widely cultivated, with colors including white, gray, yellow, and pink, although cultivated mushrooms generally look rather different from their wild cousins.

Channel the Earth Force

Bring the hands forward and rotate the palms to face downwards. **Smile** and channel the earth force as before.

For these Closing Movements see the pictures beginning on page 171.

Closing Movements
Activate the Chi Channels - Balancing the Organs

Index Finger - open (up), close (down), neutral (even with the other fingers).
Ring Finger - down, neutral.
Index Finger - open, neutral.
Thumb - in and down, neutral.
Index Finger - open, neutral.
Pinky Finger - down, neutral.
Index Finger - open, neutral.
Middle Finger - down, neutral.
Index Finger - open, neutral.

Crane's Beak

Form the crane's beak with both hands by bringing the fingertips together with the thumbs inside. Swallow the saliva. Raise the forearms to shoulder height with the fingers pointed down, inhaling gently as you raise.

Open the palms slowly and begin to lower the arms to the sides as you exhale, until the palms have returned to the starting position.

Finish

Bring the awareness to the navel and notice the quality and intensity of the energy generated.

Collect energy at the navel. Men, place the hands over the navel with the right hand on top; vice versa for women.



Pleurotus cornucopiae var. *citrinopileatus* (golden oyster mushroom) fruiting in the wild. **EDIBLE.** (Wang)



Pleurotus ostreatus (oyster mushroom) fruiting in the wild. **EDIBLE.** (Lyon)

Schizophyllum commune (Common Split Gill)

The most distinctive characteristic of the common split gill, and the basis for its common name, is the presence of longitudinally split or grooved gills on the lower side of the cap. The white to gray cap is without a stalk, fan- or shell-shaped, 1–4 cm wide, and has an upper surface that is densely hairy. This mushroom typically occurs in small groups or rows on dead branches of various deciduous trees. It is one of the most widely distributed of all fungi and is found throughout the world. Unlike most other small shelflike or bracket-like fungi, which would seem too tough to be of any value as food, *Schizophyllum commune* is collected for human consumption over large areas of the African and Asian tropics. The fruiting bodies are often chewed uncooked or used in soups (Rammeloo and Walleyn 1993). This mushroom has also been reported to cure leukorrhea, to serve as a general tonic, and to have antitumor properties.



Pleurotus opuntiae (white oyster mushroom) fruiting on a dead cabbage tree (*Cordyline australis*). **EDIBLE.** (Buchanan)



Schizophyllum commune (common split gill). **EDIBILITY UNKNOWN: AVOID.** (Izawa)

---

6. Mushrooms with more or less funnel-shaped fruiting bodies (or fruiting bodies triangular in cross section), with the spores formed on the outer surface, either on gill-like folds or simply on a rough surface

---

Cantharellus cibarius (Chanterelle)

The bright yellowish orange caps of the chanterelle are 2–10 cm in diameter and are borne on a tapered stalk 2–8 cm high and up to 3 cm thick at the top. At first the caps are dome-shaped with the margins rolled downward, but a depression develops in the center of the caps as they mature, and they eventually become funnel-shaped with a wavy margin. The gill-like folds are narrow, forked, egg-yellow, about 2 mm deep, and extend down the stalk some distance. The spores are buff to pale yellow.

Cantharellus cibarius is found throughout the temperate zones of Europe, North America, and Asia, from mid August to October beneath conifers and deciduous trees, in moist, shady situations, and often among mosses. It is not found in the Southern Hemisphere,



Cantharellus cibarius (chanterelle). **EDIBLE.** (Hall)

though there are similar species in South American and Australasian native forests. The bright color, characteristic shape, and apricot-like smell of the chanterelle make it difficult to mistake. However, the false chanterelle (*Hygrophoropsis aurantiaca*) might confuse a novice.

The chanterelle's smell, peppery taste, and excellent keeping qualities give it a popularity rivaled only by porcini (*Boletus edulis*). Although it can be bottled and canned, much of its flavor and firm texture is lost as a result of these procedures. If dried using a kitchen desiccator or threaded onto a piece of string and hung up to dry, its flavor is retained and concentrated. Like porcini, it can then be used to flavor soups and stews during the winter months.

The chanterelle is currently the mycorrhizal mushroom most in demand in Europe and North America. During July and August chanterelles are imported from North America, but later in the year they are imported from Europe. While fresh chanterelles are preferred by the retail market and by the manufacturer because they make a "slightly better product," the demand for convenient, prepared, cooked foods (for example, chanterelle pizzas) means that there is a steady demand for cheaper chanterelles that are dried or pickled in brine. In Scotland and Northern England an experienced picker can earn about $3000 per week collecting chanterelles at the height of the fruiting season.

The volume of chanterelles consumed is difficult to estimate, again because of the large quantities consumed or traded outside markets where official records are kept. However, it has been estimated that world consumption is about 200,000 tons per year, which would be worth $1.62 billion (Baker 1997). Typical wholesale prices in the United States are $30 to $38 per kilogram (Anonymous 2000a), while in 1996 at the Markthalle in Innsbruck, Austria, fully expanded broken chanterelles sold for 160 to 190 Austrian schillings ($9 to $12) per kilogram. In previous years in Europe prices were much higher when demand exceeded supply.

Although the chanterelle has never been cultivated, recent work in Sweden and the United States (Danell 1994, Danell and Camacho 1997) has resulted in a technique for infecting plants with the fungus. Small numbers of fruiting bodies have been produced on experimental plants in greenhouses. Whether or not this technique can be scaled up is not yet known. If it can, plantations will be established with infected trees, making it possible to produce chanterelles where they cannot be produced at the moment, such as in Southern Hemisphere countries for out-of-season Northern Hemisphere markets.



Hygrophoropsis aurantiaca (false chanterelle). **POISONOUS.** (Izawa)

Hygrophoropsis aurantiaca (False Chanterelle)

Like the chanterelle, the false chanterelle is funnel-shaped and yellow to orange, with yellow to yellowish brown gills that extend down the stalk. The cap is 2–8 cm in diameter, and the stalk is 3–5 cm high and up to 1 cm thick. The false chanterelle can be distinguished from the chanterelle by the strongly in-rolled margin of its cap, which is similar to that of *Paxillus involutus*, combined with its lack of the chanterelle's characteristic apricot-like smell, its lack of flavor, and its white spores. Although the false chanterelle is said to be edible, some people experience hallucinations after eating it (Phillips 1981).

Gomphus floccosus (Scaly Vase Chanterelle)

A native of North America, the scaly vase chanterelle differs from the true chanterelle in having quite distinctive scales on the surface of its funnel-shaped, orange cap. This mushroom is found fruiting in hardwood and conifer forests from early summer to autumn. It is 5–13 cm in diameter and 5–18 cm high. Although some can eat this mushroom without ill effects, others suffer intestinal pain, nausea, and diarrhea.



Gomphus floccosus (scaly vase chanterelle). **POISONOUS.** (Izawa)

Craterellus cornucopioides (Horn of Plenty)

In France the horn of plenty is known as *trompette de la mort* ("the trumpet of death"). But though its dry, dark brown, funnel-shaped caps look anything but appetizing, this mushroom is simply an edible delicacy in disguise. The dark color of the caps also makes the horn of plenty particularly difficult to see against a background of decaying leaves on the forest floor. The caps are 2–8 cm in diameter and 4–12 cm high. These mushrooms are often found growing in clusters under hardwoods and conifers from late summer to early winter. The white spores are formed on the outside of the funnel, and, unlike many other basidiomycetes, there are no gills, spines, or tubes. At first the outer surface of the funnel is black, but it becomes grayish as the spores begin to form. *Craterellus fallax*, a very similar species found in eastern North America, has spores that are pale yellow to salmon.



Craterellus cornucopioides (horn of plenty). **EDIBLE.** (Izawa)

---

7. Mushrooms with a central, well-developed stalk supporting the cap and no gills but with many tubes present that give the underside of the cap a spongelike appearance—boletes

---

As a group, the boletes are usually rather easy to recognize because of the spongelike appearance of the lower surface of the cap, which is due to the presence of numerous pores that make up the mouths of tubes. The spores are produced on the inner walls of these tubes.

Austroboletus betula (Shaggy-Stalked Bolete)

One bolete that is unlikely to be confused with any other species is the shaggy-stalked bolete, *Austroboletus betula*. This very distinctive mushroom is easily recognized by the combination of a smooth, somewhat slimy, apricot-yellow cap and a long, shaggy, yellow to reddish yellow stalk. The convex cap is 3–9 cm in diameter, and the pore surface is yellow to greenish yellow. The stalk is 10–20 cm long, 0.5–2.0 cm thick, and has a coarsely reticulate to shaggy surface with



Austroboletus betula (shaggy-stalked bolete). **EDIBLE.** (Johnson) raised yellow ridges that may redden with age. Solitary to scattered fruiting bodies of the shaggy-stalked bolete occur on the ground in mixed oak and pine (*Quercus* and *Pinus*) forests and beech (*Fagus*) forests throughout eastern North America (Bessette et al. 2000). This mushroom is considered edible.

Boletus edulis (Porcini)

The characteristic features of the five or so species that make up the *Boletus edulis* species complex are a spongelike covering (consisting of many tiny tubes) instead of gills on the lower side of the cap; a very fat stalk that, when young, can be wider than the cap itself; a raised network covering the stalk; and an absence of the black scales that are characteristic of the birch boletes and other species of *Leccinum*. Some fungal taxonomists divide *B. edulis* into a number of subspecies or separate taxa including *B. aereus*, *B. aestivalis*, *B. edulis*, *B. pinicola*, and *B. reticulatus*. None of these can readily be confused with any poisonous species, but care should still be taken when identifying porcini. When the cap opens out, it can be as much as 20 cm in diameter. However, an illustration in *The Mycologist* shows a 3.2-kg



Young *Boletus edulis* (porcini) from Christchurch, New Zealand. **EDIBLE.** (Hall)

Healing Others

Summary and Combined Practice

After learning the four sets of Cosmic Chi Kung, you may want to combine them all into a short and simple daily practice. This combined set, previously called Buddha Palm I, synthesizes the movements from the first three sets into one basic sequence. The movements are done on the right side only, so the entire set can be completed in **ten to twenty minutes**.

Cosmic Chi Kung: Simple Combined Sequence

Opening Movements

Bone Breathing - Absorbing Cosmic Chi

1. Stand with your hands down by your sides. Feel your Chi moving and activate the **bone breathing**.
2. Activate the cosmic force by using your mental intention (Yi) to spiral at the **mideyebrow** point and draw in the golden light energy. Breathe through the mideyebrow point in the same manner as in bone breathing, allowing the energy to **flow through the Microcosmic Orbit**. Alternatively you can breathe the golden light down into your navel to charge up your Original Chi at the Tan Tien. You can also simply circulate the golden light throughout your body. Relax, smile and enjoy the sensation of your entire body breathing in the cosmic energy.

Channeling the Earth Force - Washing the Bone Marrow

1. Connect with the earth force by activating the **perineum** and the **soles of the feet, Kidney 1, Bubbling Spring**. Connect the bridge by slightly squeezing the sex organs and the anus. Wash the bone marrow from the soles to the crown.
2. **Smile** into the perineum, palms, mideyebrow and crown. Then slowly raise the arms, palms facing each other to chest height keeping the elbows relaxed and sunk. Then slowly rotate the arms until the **palms are facing down**. Absorb the Earth Chi through the soles, perineum and palms; feel it being absorbed into the bones and body like a **steam or mist rising from the earth**. Feel the earth force move through the **center of the bones**, up the calves, thighs (femur bones), through the hip bones, spine, scapulas, arms, neck and skull. Finally swirl the energy around your brain.



The network on the stalk of *Boletus edulis* (porcini) is a characteristic feature of *Boletus* species. (Hall)



Old *Boletus edulis* (porcini), each weighing about 500 g. **EDIBLE.** (Hall)

monster collected in the United Kingdom in 1995 with a cap 42 cm in diameter and a stalk 18 cm high and 14 cm across (Kozikowski 1996).

Porcini is found throughout North America up to 3500 m in the Rocky Mountains, continental Europe, Asia, and from the coolest parts of Scandinavia to as far south as Mexico and Morocco. It is also one of the few edible mycorrhizal mushrooms to reach the Southern Hemisphere, where it is found growing on various species of pine in the Southern Natal Midlands of South Africa (Eicker 1990, Marais and Kotzé 1977) and on oak (*Quercus*), beech (*Fagus*), birch (*Betula*), and lime (*Tilia*) trees around Christchurch, New Zealand (Wang et al. 1995). Almost all boletes form ectomycorrhizal associations with host trees.

What makes porcini so popular is its powerful mushroomy taste, which is retained even after drying. It can be picked in autumn and, if necessary, sliced or cubed, dried, and stored to flavor dishes in winter. A few reconstituted slices can enliven any dish of store-bought mushrooms. Its flavor is also retained after cooking at high temperatures in pressure cookers and during bottling or canning. Porcini is therefore in great demand by soup and stew manufacturers. It is very difficult to make reliable estimates of how much porcini is consumed around the world, but official figures for 1988 show that about 3000 tons passed



Boletus subvelutipes (red-mouth bolete) stained blue where the cap has been cut. **POISONOUS.**

through the marketplaces of France, Italy, and Germany. Nevertheless, actual consumption is much, much higher than this because of informal trade and consumption by collectors. It has been estimated that between 20,000 and 100,000 tons are eaten (Hall, Lyon et al. 1998) annually worldwide. During autumn in the Northern Hemisphere prices range from $20 to $80 per kilogram. However, in New York during 1997 rare fruiting bodies harvested in spring had a wholesale price of $218 to $231 per kilogram (Anonymous 2000a).

Many species of *Boletus* are edible—or if not edible, they have an unpleasant flavor and are not dangerous. However, a dozen or so species are poisonous, and *B. satanas* (devil's bolete) is possibly lethal. It is therefore necessary to learn the characteristics of edible species and how these differ from poisonous ones.

Poisonous *Boletus* Species

Boletus calopus, *B. haematinus*, *B. legaliae*, *B. luridus*, *B. pulcherrimus*, *B. pulverulentus*, *B. purpureus*, *B. rhodoxanthus*, *B. satanas*, *B. satanoides*, *B. sensibilis*, and *B. subvelutipes* are all poisonous boletes, *B. satanas* (devil's bolete) being possibly deadly (Benjamin

1995, Imazeki et al. 1988, Lincoff and Nehring 1995, Phillips 1981). While it would be difficult to confuse these species with the edible boletes, care is still needed. These poisonous species are orange or red on the underside of the cap and/or stain blue when bruised or cut. Boletes with these characteristics should not be eaten.

Red-mouth bolete (*Boletus subvelutipes*) is a typical member of the group of poisonous boletes. It is fairly common in eastern and central North America, where it occurs in hardwood as well as in coniferous forests (Bessette et al. 2000). Fruiting bodies have a cap that is 6–13 cm in diameter and yellowish brown to brown or reddish brown. The stalk is 3–10 cm high and 1–2 cm thick, and mature specimens often have short, thick, dark red hairs at the base.

Boletus pseudosensibilis

Boletus pseudosensibilis is an edible bolete that might be confused with the poisonous species because its fruiting body stains blue when bruised or cut, a feature of many poisonous boletes. However, the underside of the cap in this mushroom is yellow to ochre-yellow when young and olive-ochre in mature specimens, not the orange or red



These *Boletus pseudosensibilis* exhibit blue stains, a characteristic of poisonous species in the genus. **AVOID.** (Johnson) associated with most of the poisonous boletes. Nevertheless, *B. pseudosensibilis*, which appears to be most common in northeastern North America (Bessette et al. 2000), is best considered unfit for human consumption in order to avoid any chance of an unfortunate mistake.

Leccinum scabrum (Brown Birch Bolete)

As the common name implies, the brown birch bolete forms mycorrhizal associations with birch and can be found from midsummer to late autumn. The caps are 5–10 cm in diameter, pale to dark gray-brown, suedelike when dry, and somewhat sticky when wet. The tubes on the underside of the caps are off-white to pale gray and turn brown when bruised. The stalk is 6–12 cm high, white to off-white, covered with small black scales, and tapers toward the attachment to the cap. Although the smell of the brown birch bolete is pleasant, it is described in *Mushrooms and Other Fungi of Great Britain and Europe* (Phillips 1981) as edible but not worthwhile—an opinion not shared by all. Despite this, the brown birch bolete is not as good as porcini (*Boletus edulis*), although a number of inexperienced chefs have confused the two species.



The dark scales on the stalk of *Leccinum scabrum* (brown birch bolete) readily distinguish it from *Boletus edulis*. **EDIBLE.** (Hall)



Leccinum versipelle (orange birch bolete) with the typical dark scales on the stalk. **EDIBLE.** (Izawa)

Leccinum versipelle (Orange Birch Bolete)

The easily detected dull orange fruiting bodies of the orange birch bolete are common in summer and autumn throughout Europe under birch (*Betula*) or in mixed woodlands containing birch. The caps are 8–20 cm in diameter, dry at the surface, and, when young, slightly downy. The stalks are up to 20 cm high, up to 4 cm thick, usually swollen toward the base, white to grayish, and instead of having a raised network on the stalk like some species of *Boletus*, are covered in almost black scales. The tubes are small and off-white when young, becoming gray, while the spores are brown. When cut, the flesh is at first white to off-white and gradually turns gray-blue, particularly toward the base of the stalk.

Leccinum aurantiacum (Orange-Capped Bolete)

Leccinum aurantiacum, a species common in North America, is rather similar in appearance to *L. versipelle*, but the flesh turns burgundy and then changes to gray or purplish black. The rusty red to orange-red caps of *L. aurantiacum* are 5–20 cm in diameter and



Leccinum aurantiacum (orange-capped bolete). **EDIBLE.** (Roody) rounded to broadly convex at first but flattened in older specimens. The stalk is 10–16 cm high and 2–3 cm thick, with the base slightly larger than the apex. This mushroom occurs scattered or in clusters under aspen (*Populus*) and pine (*Pinus*) throughout central and northern North America. While no species of *Leccinum* are outstandingly flavorsome, this species is among the best. There are apparently no references to poisonous species in this genus.

Phylloporus rhodoxanthus (Gilled Bolete)

In some boletes the pores are arranged in rows that radiate outward from the stalk, thus giving the lower surface of the cap a somewhat gill-like appearance. The most extreme expression of this condition is found in the genus *Phylloporus*, in which the greatly elongated pores are truly gill-like (in fact the name of the genus literally means "gill-like pores") (Bissette et al. 2000). *Phylloporus rhodoxanthus* occurs throughout eastern North America as scattered fruiting bodies or in groups on the ground in broadleaf forests under beech (*Fagus*) and oak (*Quercus*). The cap is 2.5–10 cm wide, obtuse to convex at first but becoming flattened, and ranges from dark red to reddish brown



Phylloporus rhodoxanthus (gilled bolete). **EDIBLE.** (Izawa) or olive-green. The stalk is 3–9 cm high, 3–14 mm thick, and widest at the apex, tapering slightly toward the base. This is an edible mushroom and is considered good by some (Miller 1981).

Strobilomyces floccopus (Old Man of the Woods)

One of the more distinctive mushrooms you are likely to encounter in the forests of eastern North America is *Strobilomyces floccopus*, the old man of the woods. In this species both the cap and stalk are woolly to scaly. The cushion-shaped to somewhat flattened cap, which is 4–15 cm in diameter, is grayish black and has a ragged margin. The stalk, which is similar in color to the cap, is 5–12 cm high and 1.5–2.5 cm thick, sometimes with a slightly enlarged base. The old man of the woods is found in hardwood and mixed hardwood and pine (*Pinus*) forests. It is edible when young but not particularly flavorsome. One unusual feature of this mushroom is that it does not decay as readily as most other mushrooms, and old fruiting bodies can be found well beyond the usual fruiting season. *Strobilomyces confusus* is a morphologically very similar species also found in eastern North America. Fruiting bodies are slightly smaller than those of *S. floccopus*, and the warts and scales on the surface of the cap are firm and erect. In *S. floccopus*, the warts and scales feel soft and woolly.

Suillus grevillei (Larch Bolete)

The shiny or slimy orange to bright yellow fruiting bodies of the larch bolete can be found under larch (*Larix*) from midsummer to late autumn. The caps are 3–12 cm in diameter, and the stalks are 4–8 cm high and up to 2 cm thick. As with most species of *Suillus*, a ring is present on the stalk. The tubes are pale yellow and narrow. The larch bolete is edible, but the slimy surface of the cap should be peeled off before cooking.

Suillus luteus (Slippery Jack)

Fruiting in autumn, particularly under pines (*Pinus*), slippery jack is difficult to confuse with any other mushrooms. The caps are 6–15 cm in diameter, chestnut-brown to dark brown, and very slimy when wet. On drying they become shiny. The stalks are 4–10 cm high and each has a prominent ring. The portion of the stalk above the ring is rough. At first the portion of stalk below the ring is white or creamy white to



Strobilomyces floccopus (old man of the woods). **EDIBLE.** (Izawa)

Activate the Hip - Large Intestine 4, Pericardium 9 and Small Intestine 3

1. Raise your index finger slightly upward to activate the Laogong point (Pericardium 8). Then stretch your thumbs out to the sides and down, so that they end up pointing downwards toward the earth to activate Large Intestine 4 (Hegu). **Large Intestine 4 is found in the webbing between the thumb and index finger. It is called the "eye of the hand"; this area is also known as the "Tiger's Mouth."**
2. Slowly draw the elbows back and lower the hands until your palms are facing down beside the "eye of the hip" (the iliac crest) with the "eye of the hand" (Large Intestine 4) aligned with the "eye of the hip". **Use your mind intention to beam the energy back and forth between your two LI-4 points. This will activate the large and small intestines.**
3. Rotate your hands so that the fingers first point out, then back and finally point the fingers in toward the eye of the hip. **Beam energy back and forth between the tips of the middle fingers** (Pericardium 9) passing through the hips.
   Rotate the hands again until the fingers are pointing forward with the palms facing up. Align the knife edge (Small Intestine 3) with the eyes of the hip, and **beam the energy back and forth between the two hands.**

Absorb the Heavenly Force - Washing the Bone Marrow - Crown to Soles

Extend the arms forward to chest height with the **palms still facing upward**.

Become aware of the palms and the crown. Activate the Laogong point (Pericardium 8). Feel the heavenly energy, and be aware of the violet light of the North Star and the red light of the Big Dipper shining down. Draw this light in through the palms and the crown point and feel it washing your bone marrow. Direct the sensations down through the skull, cervical vertebrae, clavicle, scapulas and sternum. Activate your thymus gland and continue drawing the healing heavenly light down through the rib cage, arms, spine, hips, femurs, calf bones, feet and toe bones. **Feel your bones activated with a positive electrical force (the positive force comes from heaven, negative from the earth).**

Absorb the Earth Force

1. Rotate the arms until the **palms face down**.
   Raise the index fingers slightly, extend the thumbs first towards each other, and then towards the ground.
2. Become aware of the palms (Laogong), the soles of the feet (Kidney 1, Bubbling Spring) and the perineum (Conception Vessel 1, Hui Yin). Activate these points, feel the earth energy, and **be aware of a gentle blue light or white light rising up from the earth like a pure steamy mist.** Draw this light in through the palms and soles and let it wash up through the center of your bones as it steam cleans your



Suillus grevillei (larch bolete). **EDIBLE.** (Hall



Suillus luteus (slippery jack). **EDIBLE.** (Hall) light brown, but this soon becomes stained mid to dark brown. There are no references to poisonous species of *Suillus*, but it is known that some contain laxatives (Benjamin 1995). A Russian chef once told Ian Hall that slippery jack is very popular in Russia and quite good to eat with lemon and garlic, though the texture is rather slimy. When asked what it tastes like, the chef replied, "Lemon and garlic." If this mushroom is to be eaten, many say it is better to remove the tubes first.

Tylopilus felleus (Bitter Bolete)

Tylopilus felleus is occasionally confused with *Boletus edulis*, but the reticulation on the stalk is brown in the bitter bolete and white in porcini. In addition, the underside of the cap of the bitter bolete is pink when mature. As its common name suggests, *T. felleus* has a very bitter taste even after cooking. The cap of this mushroom is 5–30 cm in diameter and rounded to convex at first but becoming broadly convex to flat. The cap is pinkish to reddish purple when young but turns brown, buff, or tan with age. The stalks are 4–20 cm high, 1–3 cm thick, and the lower portion becomes somewhat enlarged, although not to the extent



The brown network on the stalk of *Tylopilus felleus* (bitter bolete) distinguishes it from *Boletus edulis* (figure 180). **EDIBILITY UNKNOWN: AVOID.** (Johnson) found in porcini. Fruiting bodies of the bitter bolete can be found from early summer until autumn throughout eastern North America. The species typically occurs in forests with at least some conifers present. Although not poisonous, this mushroom is best considered inedible because of its bitter taste.

Xerocomus badius (Bay Bolete)

The fruiting bodies of the bay bolete have the smell of button mushrooms (*Agaricus bisporus*). They are found in autumn, and the cap is about the color of a horse chestnut seed. The caps are 4–15 cm in diameter and have a soft suedelike surface when young, but the mature caps are sticky when wet and shiny when dry. The stalks are 5–13 cm high and have a downy patterned surface rather than a raised network like some species of *Boletus*. There is no ring. The tubes are pale cream at first, becoming pale lemon-yellow, and will rapidly bruise a dark blue-green. Great care needs to be taken to distinguish the edible bay bolete from toxic boletes that also stain blue-green when bruised, although these usually have red caps or tubes.

Xerocomus chrysenteron (Red-Cracked Bolete)

Red-cracked bolete is found associated with hardwood trees, particularly oak (*Quercus*), in autumn. Caps are 4–12 cm in diameter and are



Xerocomus badius (bay bolete). **EDIBLE.** (Lyon)



Xerocomus chrysenteron (red-cracked bolete). **EDIBLE.** (Hall)

a dull brown or sepia. When young the surface of the cap has a suede-like feel, but eventually it becomes cracked and stained red within the cracks. The stalk is 4–8 cm high, lemon-yellow at the top and red below, and often has a light brown base. The tubes are large and angular, lemon-yellow when young but becoming tinged slightly green with age, and bruise bluish green. While edible, red-cracked bolete has a poor flavor and a rather mushy texture after cooking. Care needs to be taken to ensure that this mushroom is not confused with poisonous boletes that have red tubes or that stain blue when bruised.

8. Mushrooms with an undersurface devoid of gills or tubes but with minute spines or elongated, toothlike structures

Hydnum repandum (Hedgehog Mushroom)

The hedgehog mushroom is easily recognized by the small spines that hang vertically from the lower side of the creamy or creamy yellow caps. Fruiting bodies are found on the ground, associated with both hardwoods and conifers, in late summer and autumn. The stalks are short and stout, 3–8 cm high and up to 4 cm thick. The caps are 3–17 cm in diameter with off-white to cream to salmon-pink spines.



Hydnum repandum (hedgehog mushroom). **EDIBLE.** (Izawa)

The caps have a pleasant smell, and although the taste of older specimens is somewhat bitter, the hedgehog mushroom is considered an excellent edible mushroom in Europe. The French name for this species is particularly descriptive: *pied de mouton*, meaning “sheep’s foot.”

Sarcodon imbricatum (Scaly Tooth)

As with *Hydnum repandum*, the large, cracked, conspicuously scaly, mottled brown caps of the scaly tooth have spines hanging vertically from their lower surface. At first the spines are off-white, but they gradually turn brown with age. The caps are 5–20 cm in diameter, the stalks 5–8 cm high and up to 5 cm thick. The scaly tooth is found under conifers in autumn and is considered edible, though it can have a slightly bitter taste.

Hericium Species

Lion’s mane (*Hericium erinaceus*), coral tooth (*H. coralloides*), and comb tooth (*H. ramosum*) mushrooms occur on both the dead wood and living trunks of broadleaf trees, whereas the conifer coral tooth mushroom (*H. abietis*) is found on conifers. These are among the most distinctive of all mushrooms and are not likely to be confused



Sarcodon imbricatum (scaly tooth) growing under conifers in the Austrian Alps. **EDIBLE.** (Hall)



The spores of *Sarcodon imbricatum* (scaly tooth), like those of *Hydnum repandum*, are formed on fine spines that cover the undersurface of the cap. **EDIBLE.** (Hall)



Hericium clathroides (fungus icicles). **EDIBLE.** (Izawa)

with members of any other group. All are very good to eat. *Hericium clathroides* (fungus icicles) is a species very similar to *H. abietis*.

9. Mushrooms with a distinct stalk, a conical or spherical honeycomb-like top, or a folded piece of suedelike material on top of a grooved stalk

Morchella Species (Morels)

Mushroom connoisseurs consider morels to be among the finest of edible mushrooms, and in certain parts of the world they are much sought after in spring when they appear. They have been likened to a "sponge on a stalk," but this belies their gastronomic delights. In North America, morels may be found in great abundance, especially in the first spring following a forest fire. They can be found in grassy areas, gravel bars along rivers, woodlands, gardens, even the ashes of a barbecue pit (Chang and Hayes 1978). Morels are sporadic and unpredictable—Ian Hall saw his first morels in the 1960s but has not seen them in the same area since.



Morchella esculenta, a yellow morel. **EDIBLE.** (Wang)

Morels are always found on the ground, either alone or in small groups. Unlike most edible mushrooms, morels (as well as truffles) belong to the Ascomycetes. Their reproductive spores, called ascospores, are contained in asci lining the hollows of the sculptured, coarsely honeycomb-like caps of the fruiting body. The fruiting body is hollow from the base of the stalk to the top of the cap, and the spore print, which can be difficult to obtain because of the shape of the caps, is white, cream, or pale yellow.

The fruiting bodies of *Morchella esculenta*, a yellow morel, are some 6–20 cm in height and have a round to oval cap. The cap is yellowish cream to light brown and consists of deep, irregular, angular pits bordered by acute ridges. The base of the cap is joined to a whitish to cream stalk that is generally smooth but may be slightly grooved. The base of the stalk is usually slightly swollen at soil level.

Morchella elata and *M. conica*, two of the black morels, grow to about 10 cm high and have caps that are at first sooty brown but become dark, almost black, with age. The caps are more conical than those of *M. esculenta* and have ridges aligned vertically that tend to be more or less parallel. The cap is supported by a hollow white to cream stalk that is unevenly ribbed and coated with small wartlike



Morchella semilibera (half-free morel), a black morel. **EDIBLE.** (Cole) granules. Like the yellow morels, the black morels are a highly variable group, and it is often difficult to distinguish species.

Although there is evidence to suggest that some morels may form mycorrhizal associations (Buscot and Kotte 1990), in the mid 1980s the Neogen Foundation in the United States developed a technique to cultivate them (Anonymous 1997, Beauséjour 2000, Ower 1988, Stamets 1993). The current owner of the technique plans to increase production to meet the huge demand for morels. However, it has been reported that these cultivated morels are not as pleasant to eat as their wild cousins (Coombs 1994).

Of the morels, *Morchella esculenta* would take the prize in terms of edibility, but all are considered good eating. If you are so lucky as to find a profusion of fruiting bodies and it is your first encounter, go easy on the amount eaten, as there is always the possibility that you might prove to be allergic. The black morel has also been accused of causing stomach distress when consumed with alcohol (Benjamin 1995, Harding et al. 1996). It is said that morels should not be eaten raw, and blanching for a minute or two before cooking is also recommended. Old morels showing signs of decay should not be eaten, as they may be poisonous (Harding et al. 1996). Because these mushrooms are easy to recognize, the danger of picking a poisonous lookalike is not great. Care, however, should be taken to avoid picking the poisonous false morel (*Gyromitra esculenta*), which at first sight could be mistaken for a true morel.

Morels dry well. The method traditionally used involves threading the caps onto string and hanging them in the sun. As with porcini, the flavor is concentrated in the process. Typical wholesale prices for fresh morels in spring in the Northern Hemisphere are $5 to $20 per kilogram (Anonymous 1997, Rowe 1997). Dried morels can command a price of $600 per kilogram or more in Swiss retail stores.

Verpa bohemica (Wrinkled Thimble Cap)

The fruiting body of the wrinkled thimble cap has a shape similar to that of a morel (*Morchella*). However, the cap of the former is attached to the stalk only at the very top, whereas in morels more than just the top of the cap is attached. In North America the wrinkled thimble cap fruits in mixed and hardwood forests during spring, often appearing before the true morels. The cap is 1–5 cm in diameter and 1–5 cm high, thimble- to bell-shaped, and pale to dark yellow-brown or tan, becoming darker with age. The stalk is 6–15 cm high marrow. Picture any impurities or illness dripping out of your bones and draining down into the earth, where they are recycled and purified.

Core Movements

Grasping the Moon - Connecting the Heaven and Earth Forces

1. **Open Position:** Heaven Force - Bring the arms up to shoulder height, bending the elbows so that the **left hand is under the right elbow** with the left index finger pointing up to Heart 3.
2. The right forearm is over the left forearm with the tip of the right index finger held above the Large Intestine 11 point of the left arm. The right index finger is pointing up toward heaven.
3. The right index finger draws in the heavenly force like an antenna. The force flows up the bones of the right arm across the shoulders to the left arm, and through the bones of the left arm to the left index fingertip. It then flows through the index finger of the left hand into the Heart 3 point of the right arm **completing the heavenly circuit**. Continue cycling in this way.
4. **Close Position:** Earth Force - Keeping the arms in the same position, move both index fingers to point down. The right index finger will now point toward the Large Intestine 11, point of the left arm and the left index finger will point downward toward the earth. Draw in the earth force through the left index finger bringing it through the bones of the left arm, across the shoulders through the right arm to the right index finger and out into the Large Intestine 11 point of the left arm. Continue cycling in this way **completing the earth circuit.**

   Open and close three times altogether ending in the open position.

Activate the Throat Center

1. Draw the elbows out to the side and rotate the palms to face in so that the left palm is about 3 - 6 inches in front of the Throat Center (Conception Vessel 22), palm facing in, and the right hand is about 1 - 3 inches in front of the left hand, palm facing in. Align the Lung 10 point of the right hand with the Lung 10 of the left hand, and align the Lung 10 points in the middle of the thenar eminence of the left hand with the Throat Center. **Keep the points aligned and beam the energy passing through both hands into the Throat Center.**
2. Move both hands about 12-18 inches out from the Throat Center maintaining the energy beam as you move.
3. Move in and out three times altogether in this way ending with the hands in as in preivous point above.



Verpa bohemica (wrinkled thimble cap). **POISONOUS.** (Johnson) and 0.8–3 cm thick. Like *Gyromitra*, specimens of the wrinkled thimble cap must be boiled and the water discarded before eating. Some people tolerate this mushroom, but it is poisonous to others, producing intestinal upsets and uncoordinated movement. As such, it is hardly worth considering for the table.

Gyromitra esculenta (False Morel)

Like the true morels (*Morchella* spp.), the false morel is an ascomycete and can be found in spring in coniferous forests. The cap is more brainlike than that of a morel. It has wrinkles and folds, is not honeycomb-like, and lacks true pits. If you slice the cap of a false morel from top to bottom, you will find it to be multichambered, unlike the true morel, which has a single hollow chamber continuous with the stalk. Some false morels (*Gyromitra* spp.) do not resemble true morels as much as *G. esculenta*. For example, the hooded false morel (*G. infula*), which is common throughout North America, derives another common name, saddle-shaped false morel, from its characteristic saddle-shaped to three-lobed cap.



Gyromitra esculenta (false morel). **POISONOUS.** (Buchanan)



Gyromitra infula (hooded false morel) showing the characteristic cap. **POISONOUS.** (Cole)



The fruiting body of *Dictyophora duplicata* (netted stinkhorn) hatches from an egg. The base of the bell-shaped cap is encircled by a white, skirtlike, netted veil. **MEDICINAL.** (Johnson)

Despite its name (*esculenta* means "edible"), the false morel is deadly poisonous unless cooked and causes poisoning in some individuals even after cooking. Even so, it remains a popular mushroom in parts of Europe, with about 100 tons passing through the Finnish markets each year (Bresinsky and Besl 1990). Cooking involves boiling the mushrooms twice, discarding the water after each boil, before incorporating them into a dish. However, care must be taken when cooking, because the toxins are volatile and it is possible to be poisoned by breathing the fumes produced during boiling.

Dictyophora duplicata (Netted Stinkhorn)

The fruiting bodies of the netted stinkhorn (*Dictyophora duplicata*) and the bamboo mushroom (*D. indusiata*) have the same general form as those of the common stinkhorn (*Phallus impudicus*), but the base of the bell-shaped cap in both *Dictyophora* species is encircled by a white, netlike, flaring veil.

When mature, with the veil fully expanded, the netted stinkhorn is not likely to be confused with any other mushroom. A mature fruiting body is 15–25 cm high, with the cap, usually 3–4 wide and 4–5 cm long, representing approximately a third of the total height. The netted stinkhorn is occasionally found fruiting on the ground under hardwoods in the forests of eastern North America. However, most species of *Dictyophora* are limited to the tropics, and members of the group are not uncommon in tropical forests such as those of Central and South America. Fruiting bodies typically occur on areas of the forest floor rich in humus or with accumulations of well-decayed wood, and are most likely to be encountered during periods of rainy weather. Although these mushrooms are not poisonous, most people would not consider them suitable for the table. However, *D. duplicata* and *D. indusiata* are sometimes consumed for medicinal reasons: both contain an active agent that is reputed to lower blood pressure and reduce body fat.

Mutinus caninus (Dog Stinkhorn)

Unlike the common stinkhorn (*Phallus impudicus*) and the netted stinkhorn (*Dictyophora duplicata*), the dog stinkhorn (*Mutinus caninus*) does not have a clearly defined head (as the caps of stinkhorns are usually called). Instead, the mature fruiting body consists of a single white to pale yellow-buff to orange-red stalklike structure that



Mutinus caninus (dog stinkhorn). **EDIBILITY UNKNOWN: AVOID.** (Johnson)



Immature fruiting bodies of the dog stinkhorn (*Mutinus caninus*) inside the eggs. **EDIBILITY UNKNOWN: AVOID.** (Johnson)

extends upward from a white pouch (the ruptured egg) and tapers almost to a point at its apex. The entire structure is 10–18 cm high and 1.5–2.5 cm thick, the upper portion covered with the slimy, olive-brown, foul-smelling spore mass. The dog stinkhorn is encountered occasionally in forests, gardens, and waste areas in eastern North America and Europe. *Mutinus elegans* is a very similar species but can be distinguished by its taller fruiting body, which has a relatively larger area covered by the spore mass. Moreover, the portion of the fruiting body below the spore mass is pitted in *M. caninus* and pebbly in *M. elegans*. Both *M. caninus* and *M. elegans* are apparently nonpoisonous, but few people would have the stomach to eat them.

Phallus impudicus (Common Stinkhorn)

A pleasant summer stroll through a forest in Europe or eastern North America can be quickly interrupted if you come across a group of stinkhorns: the smell is truly disgusting. When fully expanded, the fruiting bodies are up to 25 cm tall and 6 cm thick. The entire fruiting body expands out of an egg 4–6 cm in diameter and is in this respect similar to the basket fungus (*Ileodictyon cibarium*). The upper portion of the fruiting body is represented by a clearly defined head



Mature fruiting bodies of *Phallus impudicus* (common stinkhorn), with the remains of the egg from which they have emerged just showing above the ground. **EDIBILITY UNKNOWN: AVOID.** (Wang)

that is covered with a fetid, slimy, olive-green spore mass. While the common stinkhorn is edible before it has expanded out of the egg stage, disassociating the mild taste from the smell of a mature fruiting body would presumably take some effort. Flies, however, are attracted by the smell and sometimes cover the fruiting bodies. Spores then adhere to the flies and are carried away with them, which aids in the dispersal of the fungus. While the stinkhorns superficially resemble morels (*Morchella* spp.), the smell of a stinkhorn would make confusing the two virtually impossible.

Podaxis pistillaris (Stalked Puffball)

The stalked puffball is not uncommon in the Hawaiian Islands and Australia, where it can be found in drier, disturbed areas such as along roadsides. The common name might suggest this species is related to the giant puffball (*Calvatia gigantea*), but it is actually more closely related to the shaggy ink cap (*Coprinus comatus*) (Hopple and Vilgalys 1994).The edibility of the stalked puffball is unknown, but the fact that it is used by Australian Aborigines to dye white hair and ward off flies suggests it might be less than palatable.



Podaxis pistillaris (stalked puffball). **EDIBILITY UNKNOWN: AVOID.** (Hemmes)



Helvella crispa (white helvella). **EDIBLE.** (Lyon)

Helvella Species

Species of *Helvella* have a fruiting body that somewhat resembles a crumpled sheet of velvet on top of a grooved stalk. Like the true and false morels (*Morchella* spp. and *Gyromitra* spp.), they are ascomycetes, with spores produced on the velvet-like surface of the cap. The white *H. crispa* and black *H. lacunosa* are edible, but the edibility of some species is unknown. Although it is possible to confuse fruiting bodies of *Helvella* with those of the false morel, species of *Helvella* normally fruit in autumn, while the morels and false morels fruit in spring. They are usually found in wooded areas.

10. Mushrooms with pulvinate to spherical fruiting bodies that are parasitic on living plants

Cyttaria Species

Cyttaria is a genus of mushrooms that are parasitic on certain species of *Nothofagus* (the southern beeches of, for example, southern South America, Australia, and New Zealand). These fungi attack the fine

Activate the Third Eye

1. Keeping the Lung 10 points aligned, raise the hands up to the level of the mideyebrow point. Keep the points aligned and **beam the energy passing through both hands into the mideyebrow point.**
2. Move both hands about 12-18 inches out from the mideyebrow point maintaining the energy beam as you move. **Move in and out three times** altogether in this way, ending with the hands as previously.
3. Keeping the palms and thenars (Lung 10) aligned, move the hands back down to the position in front of the **Throat Center.**

Open the Bridge and Regulator Channels

1. Keeping the forearms horizontal at shoulder height, separate the hands so that the Laogong points are aligned in front of Stomach 13 just below the clavicle on a vertical line above the nipple or **mammillary** line. The fingertips should almost be touching. Beam energy from the Laogong points into ST-13. You will be following this vertical line, which passes through the nipples, down the torso to the level of the navel stopping to focus and **beam energy into key points along the way**. On each of these, focus your Yi on beaming energy into the organs inside each position. Stomach 13 is the location that activates the Heart and Lungs. Feel the change in your breathing as you activate the **lungs**.
2. Move the hands down the mammillary line to Stomach 16, about one inch above the nipple (in the space between the third and fourth ribs). Again, beam energy to energize and balance the **heart and lungs**.
3. Move the hands down to Liver 14 (about 2 - 3 inches below the nipple in the space between the 6th and 7th ribs). Beam healing energy into the **liver and gall bladder**.
4. Move the hands down to Spleen 16 (just below the rib cage on the mammillary line). Beam healing energy into the **stomach, pancreas and spleen**.
5. Move the hands down to Spleen 15 (on the mammillary line to the level of the navel). Beam healing energy from your palms into the **small intestine and the Tan Tien**.

Grasping the Chi Ball

1. Slowly rotate the hands so that your palms face each other in front of your navel. Feel the invisible ball of energy between your hands. Allow the energy to push your hands apart keeping the feeling of connection between your palms.
2. Let the energy draw your hands back toward each other, like a magnet, until you feel as if you are squeezing a ball.
3. Stretch and squeeze the Chi ball three times by opening and closing your palms in this way.



Cyttaria gunnii (beech strawberry), a parasite of the fine branches of a southern beech (*Nothofagus menziesii*). **EDIBLE.** (Forest Research, New Zealand)

branches of beech trees, eventually producing galls of deformed host tissue upon which clusters of fruiting bodies develop. The fruiting bodies are soft, yellowish orange, spherical, 1–3 cm in diameter, and superficially similar to the cap of a morel. *Cyttaria espinosae* is eaten in South America, where the production of fruiting bodies in suitable areas has been estimated to be 80–90 kg per hectare (Gamundí 1991, Gamundí and Horak 1995). *Cyttaria gunnii* (beech strawberry) is a traditional food of Australian Aborigines in southern Victoria and Tasmania (Kalotas 1997) and may have been eaten by Maori in New Zealand.

Uromyces digitatus

Most rusts form the powdery yellow, brown, or reddish lesions often found on cereals and other grasses. Some species, however, such as *Uromyces digitatus*, form galls on the ends of branches. Although formation of the gall is triggered by the fungus, most of the internal tissue is of plant origin.



Uromyces digitatus forming a gall on a wattle (*Acacia*). **EDIBILITY UNKNOWN: AVOID.** (Hall)

Ustilago maydis (Corn Smut)

Corn smut is a pathogenic fungus found virtually everywhere corn is grown. Ears of corn infected by the fungus exhibit tumor-like growths that are as much as 2 cm long or wide and have the general appearance of grossly overgrown corn kernels. Although they might not appear to be particularly appetizing, these maize mushrooms, as the growths are sometimes called, are considered a great delicacy in Mexico and the southwestern United States. Indeed, although the



Ustilago maydis (corn smut). **EDIBLE.** (Johnson)

economic losses worldwide from *Ustilago maydis* are considerable, Mexican farmers welcome its appearance in their cornfields because infected ears of corn command a higher price than those that remain healthy (Arora 1991). At first almost white, the growths soon darken to gray. They are considered suitable for consumption when gray on the outside and black and juicy or slightly grainy on the inside. The Spanish name for the maize mushroom is *cuitlacoche*.

11. Mushrooms lacking stalks or whose stalks are rudimentary and attached to one side, with the spores formed in tubes or on the undersurface of the caps

Anyone who has ever taken a stroll through a forest has certainly noticed the bracket-like or shelflike growths that occur, often in great profusion, on logs, stumps, dead branches, and even living trees. Most of these growths are tough, leathery, or woody, but a few are soft and fleshy, at least when young. The vast majority are the fruiting bodies of a very large and exceedingly diverse assemblage of wood-rotting fungi. Several different taxonomic groups are represented in this assemblage, but the polypores are easily the most important. The polypores (literally "many pores") are so named because they produce fruiting bodies with small tubes on the underside of the cap, and the opening at the end of each tube is called a pore. Each fruiting body has numerous pores, which in most instances are more or less cylindrical.

Although most polypores are too tough and woody to be considered for the table, some have been used in traditional medicine. The reputed medical benefits of *Ganoderma* aff. *lucidum* (reishi) are particularly noteworthy in this regard. Products derived from this mushroom have been championed as cures for everything from venereal diseases to cancer. The mycelial mats produced by *Fomitopsis officinalis* in decayed wood were once used by American lumberjacks to stop bleeding caused by ax wounds (Gilbertson 1980), and the agaric acid obtained from the fruiting bodies of this mushroom has been used as a purgative. Antibiotics have been isolated from the fruiting bodies of a number of polypores (Quack et al. 1978), and examples such as *Trametes versicolor* (many-colored polypore) and *Wolfiporia cocos* contain polysaccharides and steroids reported to have antitumor properties. *Pycnoporus sanguineus* is reputed to be useful in treating mouth ailments, while substances extracted from some species of *Phellinus* have been used to treat sore throats, respiratory conditions, and diarrhea. In addition to their uses in traditional medicine, fruiting bodies of polypores have been used as sources of dyes for fabrics, as tinder for starting fires, as razor strops, and as currycombs for horses (Alexopoulos et al. 1996).

Fistulina hepatica (Beefsteak Fungus)

The beefsteak fungus forms a fairly firm bracket up to 20 cm across and 2–7 cm thick on the trunks of chestnuts (*Castanea*) and oaks (*Quercus*) that it parasitizes. Fruiting bodies are pink or orange to begin with but change to red or purplish brown with age. When cut they exude a blood-red sap from the dark pink flesh, which looks a little like uncooked meat. The lower surface of the bracket is covered with a system of fine pores, each of which is less than 0.5 mm in diameter. The reddish brown timber from trees parasitized by the beefsteak fungus is highly sought after by cabinet makers. The fungus itself is edible.

Laccocephalum mylittae (Native Bread)

The fruiting body of the polypore *Laccocephalum mylittae* is stalked, mushroom-shaped, and inedible. However, it arises from a sclerotium



Fistulina hepatica (beefsteak fungus). **EDIBLE.** (Izawa)



An excavated fruiting body of *Laccocephalum mylittae* (native bread) growing on buried wood. **EDIBLE.** (Fuhrer)



Detail of the buried portion of *Laccocephalum mylittae* (native bread). **EDIBLE.** (Fuhrer) that can be as large as a football and weigh several kilograms. This is a traditional food eaten cooked or raw and a valuable source of water for the Aborigines in the central arid regions of Australia (Kalotas 1997). The fruiting bodies also appear to have some medical uses, since they contain proteinases that have been reported to kill parasitic worms and help relieve indigestion.

Laetiporus sulphureus (Chicken of the Woods)

The bracket-like fruiting bodies of the chicken of the woods can be found on dead wood, stumps, or living trees such as oaks, chestnuts, and willows from spring to autumn. They can be up to 40 cm across and are, when young, bright orange above and sulfur-yellow below, drying to a very pale yellowish brown. Chicken of the woods has a strong mushroomy smell, while the taste is not unpleasant. It is a very popular mushroom in the United States, Germany, and east European countries, but there is evidence of severe allergic reactions in some people, especially when consumed with alcohol (Evans 1996, Jordan 1996).



The fruiting bodies of *Laetiporus sulphureus* (chicken of the woods) growing from the base of a dead tree. **EDIBLE WHEN COOKED.** (Lyon)



Lenzites betulina (gilled polypore). **EDIBILITY UNKNOWN: AVOID.** (Johnson)

Lenzites betulina (Gilled Polypore)

In *Lenzites betulina*, the lower surface of the cap is conspicuously gill-like, and only near the margins are there more or less typical pores present. The fruiting bodies of this mushroom occur scattered or more often in overlapping clusters on the decaying logs and stumps of various hardwoods throughout temperate regions of the Northern Hemisphere. The individual caps are stalkless, 3–10 cm wide, semicircular to kidney-shaped, and nearly flat. The surface of the cap is velvety to hairy, with distinct concentric multicolored zones that range from white to gray to brown, sometimes with pink, orange, or yellow tints. *Lenzites betulina* is much too tough to be considered edible.

Auricularia Species (Wood Ear)

The wood ears are classified with the jelly fungi, like *Tremella*, and do not produce their spores in tubes like the bracket fungi. This group is included here simply because on first glance a bracket-like wood ear might be mistaken for a bracket mushroom. When young, the brown to purplish brown ear-shaped fruiting bodies of wood ears are gelatinous, with a smooth, shiny, spore-producing lower surface, and, in



Auricularia polytricha (wood ear) on the trunk of a dead tree. **EDIBLE.** (Buchanan) one species (*Auricularia polytricha*), a downy, sterile upper surface. When old, the fruiting bodies remain attached to the host log or stump and become shrunken, dry, and tough. Wild wood ears can reach 10 cm in diameter, although, like cultivated wood ears, they are sometimes much larger.

12. Mushrooms with fruiting bodies above or below the ground and more or less spherical—puffballs, truffles, and false truffles

While specialists have always had problems identifying particular species of truffles and false truffles (Trappe 1979), poisonings suggest that nonspecialists also have difficulty distinguishing edible truffles from false truffles, puffballs, and unopened fruiting bodies of, for example, *Amanita*. The truffles fall into two groups: the true truffles, which are ascomycetes, and the false truffles, which are basidiomycetes. The latter are generally agreed to have evolved from a typical mushroom through reduction and the adoption of an underground fruiting habit. This seems to be the case, for example, in genera such as *Melanogaster* and *Rhizopogon*. Puffballs are also basidiomycetes.



The shape, structure, and ornamentation of truffle spores are key features in the identification of species. Pictured are spores of *Tuber maculatum*, a species with little commercial value. (Hall)

Activate the Outer and Inner Arm Gates
Waiguan - Triple Warmer 5 and Neiguan - Pericardium 6 - Right Arm on Top

1. Slowly rotate the arms so that both palms face down.
2. Cross the right wrist over the left wrist with 1-3 inches of space between the hands. Align PC-6 of the right wrist with TW-5 of the left wrist.
3. Keeping the wrists crossed, slowly rotate hands turning the palms upward. Now TW-5 of the right wrist will be aligned with PC-6 of the left wrist.

Open the Functional Channel with LI-4

1. Bring the left hand down to the level of the Tan Tien with the Chi Knife facing in. Lower the right hand, palm down, and align the eye of the hand, the LI-4 point with your navel. Feel the Chi ball between your two hands, and at the same time beam energy from LI-4 into the navel point.
2. Raise the right hand up the Functional Channel stopping and aligning LI-4 with the **solar plexus, heart, throat** (CV-22) and **mideyebrow** points. **Beam energy from the eye of the hand into each of these points**, and at the same time continue to feel the Chi ball connection between the two hands.
3. Return down the Functional Channel in the same manner stopping to beam energy into each point. **Go up and down the Functional Channel** in this way three times.

Yin/Yang Palms

1. Separate the hands and extend them out in front of the body at solar plexus level. The left palm is still pointing up and is yang drawing in the heavenly force through Laogong. The right palm is still facing down and is yin drawing in the earth force energy.
2. Conclude by turning the left palm over to face downward. Draw in the earth force through both palms.

Double Palm and Beam to Activate the Functional and Governor Channels

1. Bring the left palm in first to face the navel, about 3 - 5 inches away, aligning the Laogong point with the navel. Follow by bringing the right hand in front of the left hand, aligning the Laogong of the right palm with the Laogong of the left hand and the navel. Both palms are now facing in. **Beam energy through both Laogong points to the navel and through the body to the Door of Life**.
2. Next raise the left palm up to the **solar plexus** aligning the Laogong point with the solar plexus. Beam energy into the solar plexus point and through the body to the T-11 point. Your right hand remains at the navel level beaming energy to the navel and the Door of Life.
3. Raise your right hand up to the outside of the left hand at the solar plexus level, and beam energy through both hands into the **solar plexus point and the T-11 point**. Continue in the same way with the left hand leading to the **heart point and wing**

When a true truffle is cut in two with a sharp knife, a system of white lines can be seen radiating through a matrix that, depending on the species, is off-white, cream, light to dark brown, black or occasionally gray, gray-blue, or even blue (Astier 1998). The false truffles appear quite different inside and are often somewhat spongy. Other characteristics used to separate the genera and species of truffles include the surface appearance of the fruiting bodies and the shape, size, and ornamentation of the spores (visible under a microscope) found on the inside.

Tuber melanosporum (Périgord Black Truffle)

Périgord black truffles range from little more than the size of a fingernail to larger than a tennis ball, sometimes weighing more than 200 g. The surface is covered in small diamond-shaped facets and is a dark ruddy brown when young, turning black at maturity. When cut in two, the interior of a young truffle is cream to light coffee-colored and traversed by a system of fine, pure white lines. As the truffle matures, the interior turns black, but the pure white lines are retained. Immature Périgord black truffles have little odor, but as the number of mature spores increases inside, so too does the aroma. Once the truffle is fully mature, the smell is almost overpowering, so that even a small truffle is enough to scent an entire room. The Périgord black truffle is found from just at the soil surface to 30 cm below and is associated mostly with hardwood trees, including oaks and hazels. As with many other expensive foods, this truffle has a reputation for being an aphrodisiac (Hall et al. 1994).

The Périgord black truffle was exported from France to North America in the late 1970s, to New Zealand in 1985, and to Tasmania around 1993. Since then, plants infected with it have been established in truffières in various localities. It can be expected that the fungus will eventually escape from these truffières, perhaps inside a pig, and become established on appropriate host plants growing in other areas with suitable conditions.

Wholesale prices of Périgord black truffles in season can range from $200 to $800 per kilogram, although retail prices as high as $10,000 per kilogram have been reported in Japan. As a result a number of other truffles are often substituted for the Périgord black truffle. These include the winter truffle (*Tuber brumale*), Burgundy truffle (*T. uncinatum*), and various Asiatic truffles, including *T. himalayense*, *T. indicum*, and *T. sinense*.



Very immature *Tuber melanosporum* (Périgord black truffles) with a light brown interior traversed by a network of pure white lines. **EDIBLE.** (Hall)



Section of a mature *Tuber melanosporum* (Périgord black truffle) with the black tissue crossed by a system of white lines. **EDIBLE.** (Hall)

A *Tuber melanosporum* (Périgord black truffle) weighing about 250 g. **EDIBLE.** (Hall)



The surface ornamentation of *Tuber melanosporum* (Périgord black truffle) is not sufficient to distinguish it from some Asiatic truffles. **EDIBLE.** (Hall)

Some Asian truffles are so similar in appearance to the Périgord black truffle that they are difficult to distinguish without using a high-powered microscope. Because Asian truffles have either a poor taste and smell or none at all, in China they fetch only a few dollars per kilogram. However, opportunists in Europe mix them with the Périgord black truffle or sprinkle them with artificial black truffle essence to give them some flavor and then market them as the real thing. The marketing of these truffles as true Périgord black truffles has the potential to degrade the industry in France, Italy, and Spain (Chevalier and Riousset 1995, Courvoisier 1995). Some people also fear that these Asian truffles will eventually find their way into European truffières and begin to displace the native species.

The Burgundy truffle (*Tuber uncinatum*), which is easily distinguished by its coffee-colored interior and the network of ridges that covers the surface of its spores, is widely consumed in Italy and parts of France (Chevalier and Frochot 1997), and was popular in Victorian England. It is also canned and bottled by companies like Urbani in Italy, and the preserved products are readily available in retail stores throughout Europe. However, the smell and flavor of this truffle are not as powerful as those of the Périgord black truffle and the Italian white truffle. The winter truffle (*T. brumale*) is often found in the same truffières as the Périgord black truffle, and though its flavor is not as powerful, the two species are often sold mixed together.

Tuber magnatum (Italian White Truffle) and Other *Tuber* Species

Italian white truffles are only white when very young. At maturity they are usually cream to light brown and have a suedelike surface, quite unlike the faceted surface of the Périgord black truffle. They typically range from the size of a golf ball to that of a tennis ball, although most people are only likely to see two or three white truffles about 10 mm in diameter preserved in a small bottle in a delicatessen. The inside of an Italian white truffle is light brown to coffee-colored and crisscrossed by a system of white lines. When ripe, Italian white truffles have a strong garlic-like smell that is quite distinct from the smell of the Périgord black truffle.

The Italian white truffle is found in northern and central Italy, Istria in Croatia, southeastern France, and southern Switzerland (Lawrynowicz 1993, Zambonelli and Di Munno 1992) from late summer to early winter. Mycorrhizal host plants include oaks (*Quercus*), poplars (*Populus*), willows (*Salix*), and limes (*Tilia*) (Hall,



Tuber uncinatum (Burgundy truffles) coated in soil, which adds to the weight. Note the tan interior. **EDIBLE.** (Hall)



Immature *Tuber sinense*, a Chinese truffle. When mature this species can easily be mistaken for *Tuber melanosporum* (Périgord black truffle). **EDIBLE.** (Wang)



A dish of Italian white truffles (*Tuber magnatum*), the most expensive mushrooms in the world. **EDIBLE.** (Squires)

Zambonelli et al. 1998). The soils in which the white truffle is found are extremely soft and porous and contain large amounts of limestone. Fresh soil and plant materials are often naturally incorporated into such soils—for example, on the banks of streams or where the soil is cultivated (Hall, Zambonelli et al. 1998).

The aroma of the Italian white truffle is easily lost when cooked. As a result, white truffles are usually shaved over salads or over hot dishes just before serving—giving Italian chefs plenty of opportunities to show their skill and panache. There is little competition in the marketplace between the Italian white truffle and the Périgord black truffle, due to their different smells, uses, and harvesting times. Over the past few years the price of the Italian white truffle has rocketed, reaching $13,200 per kilogram at the annual Alba truffle festival in November 2000 (Johnston 2000). Even modest specimens retailed for $9000 per kilogram, and the market annually is worth several hundred million dollars (Hall, Zambonelli et al. 1998).

A number of other species of truffles are superficially similar to the Italian white truffle. These include *Tuber borchii*, *T. dryophilum*, and *T. maculatum*. The Oregon white truffle (*T. gibbosum*) is found under

A natural *Tuber magnatum* (Italian white truffle) truffière in central Italy. (Zambonelli)



Tuber borchii (bianchetto), sometimes mistaken for *Tuber magnatum* (Italian white truffle). **EDIBLE.** (Hall)



Tuber maculatum, another truffle mistaken for *Tuber magnatum*. **EDIBLE.** (Hall)



Terfezia claveryi, a desert truffle, fruiting in the rooting zone of a rock rose (*Helianthemum*), its mycorrhizal host plant. **EDIBLE.** (Honrubia)

Douglas fir (*Pseudotsuga menziesii*) and other hosts in the Pacific Northwest region of North America and is said by some to be as good as the Italian white truffle. It is consumed in small quantities not only by keen trufflers (Evans and Evans 1987) but also by small mammals, some of which have an exclusive diet of truffles (Malajczuk et al. 1987, Maser et al. 1978). While toxic mushrooms in the genus *Scleroderma* are quite different from *T. magnatum*, they are not infrequently assumed to be white truffles, and many specimens have been sent in error to specialists for identification either before or after someone has eaten them.

The Italian white truffle has been successfully cultivated only within the last decade (Giovanetti 1990, Giovanetti et al. 1994). Although the techniques used commercially to produce plants infected with this truffle have not been published, it is likely that variations on Talon's technique are used by some. As such, sterile seedlings are grown in the rooting zone of a mother plant already infected with the fungus. Unfortunately, some plants that are claimed to be infected with the Italian white truffle may actually be infected with other species. A comprehensive scientific review of the Italian white truffle has been published (Hall, Zambonelli et al. 1998).

Terfezia and *Tirmania* Species (Desert Truffles)

The desert truffles (*Terfezia* and *Tirmania*) are found throughout the Middle East and northern Africa in areas between the desert proper and adjacent wetter areas. Desert truffles are associated with small shrubs such as rock rose (*Cistus* and *Helianthemum*) and are among the largest truffles in the world, sometimes weighing 1 kg or more. These truffles have a relatively mild taste and flavor, particularly when cooked with spicy Middle Eastern and northern African dishes. Like the Périgord black truffle, they are reputed to have aphrodisiac qualities (M. Zaptia, personal communication).

Bovista nigrescens, *Bovista plumbea*, and *Vascellum pratense* (Common Puffballs)

Bovista nigrescens, *B. plumbea*, and *Vascellum pratense*, collectively known as the common puffballs, are 2–4 cm in diameter (sometimes as much as 6 cm) and are often found in lawns and other grassy areas. These are edible in the immature stage before the interior of the fruiting body changes from white to brown, which indicates spore formation.



Bovista plumbea, a common puffball. **EDIBLE.** (Hall)

point, the **throat point and C-7**, the **mideyebrow point and jade pillow** and the **crown point and perineum**.

4. Return down the front, point by point in the same way, leading with the left hand. Go up and down in this way three times. **The double palm and beam activate both the Functional and Governor Channels. The energy beam passes all the way through the body at each point**.

Grasping the Chi Ball

1. Separate the hands and slowly extend the arms in front of you at navel level, palms facing each other holding the Chi ball.
2. Stretch and squeeze the Chi ball three times as before by opening and closing the palms.

Channel the Earth Force

Rotate the hands to face downward, and draw in the earth force through the palms, soles and perineum.

Closing Movements

Activate the Chi Channels - Balancing the Organs

Index Finger - open (up), close (down), neutral (even with the other fingers).
Ring Finger - down, neutral.
Index Finger - open, neutral.
Thumb - in and down, neutral.
Index Finger - open, neutral.
Pinky Finger - down, neutral.
Index Finger - open, neutral.
Middle Finger - down, neutral.
Index Finger - open, neutral.

Crane's Beak

1. Form the crane's beak with both hands by bringing the fingertips together with the thumbs inside. Raise the forearms to shoulder height with the fingers pointed down, inhaling gently as you raise.
2. Open the palms slowly and begin to lower the arms to the sides as you exhale, until the palms are facing each other in the starting position.

Finish

1. Bring the awareness to the navel and notice the quality and intensity of the energy generated.
2. Collect energy at the navel. Men, place the hands over the navel with the right hand on top; vice versa for women.

It is essential to distinguish between small puffballs and other, sometimes poisonous fungi that may appear rather similar. Examples of the latter include *Scleroderma*, immature specimens of *Geastrum* of unknown edibility, and immature fruiting bodies of the death cap (*Amanita phalloides*). It is always important to check the interior of a puffball to ensure that it is white throughout and that there are no developing gills or caps. This is particularly important if what appear to be puffballs have been collected near ectomycorrhizal trees, in which case the mushrooms in question may be immature fruiting bodies of poisonous species of *Amanita*. Even so it is still possible to confuse very young specimens of *Scleroderma* with puffballs, so it is important to section older specimens to see if there is any blackening of the interior, which is characteristic of mature *Scleroderma*.

Calvatia cyathiformis (Purple-Spored Puffball)

Though not as large as those of the giant puffball, the fruiting bodies of *Calvatia cyathiformis* can be as much as 20 cm in diameter. Usually nearly round to somewhat oval when young, fruiting bodies tend to become more pear-shaped or top-shaped as they mature. The purple-



Calvatia cyathiformis (purple-spored puffball). **EDIBLE.** (Johnson)



Calvatia excipuliformis (long-stemmed puffball). **EDIBLE.** (Hall)

spored puffball is most common in pastures, lawns, and other grassy areas. The spore mass is at first white, then yellow, finally turning a dull purple to purple-brown at maturity. The purple color of the spore mass distinguishes *C. cyathiformis* from all other species of *Calvatia*. Old weathered fruiting bodies, usually consisting of the sterile base along with remnants of the spore case, often persist for several months and can be found during the winter or even early spring. *Calvatia cyathiformis* is edible until the flesh begins to turn light tan. *Calvatia excipuliformis* (long-stemmed puffball) can be found in grasslands and forests.

Calvatia gigantea (Giant Puffball)

A modest football-sized giant puffball would be impossible to confuse with any other mushroom, and this would be doubly true for a larger specimen. However, smaller specimens of the giant puffball might be confused with the unopened fruiting bodies of much less edible mushrooms, such as poisonous species of *Amanita*. *Calvatia gigantea*, also known as *Langermannia gigantea*, is usually found growing on bare soil or in grassy areas in places where there is



Calvatia gigantea (giant puffball). The larger puffball has had a slice removed to show the firm, edible interior. The smaller, more mature puffball, which is well beyond the edible stage, displays the small stalk at its base that attached it to the mycelium in the soil. **EDIBLE.** (Hall)



A fruiting body of *Calvatia gigantea* (giant puffball) that has split while growing. **EDIBLE.** (Hall) considerable organic matter in the soil. It is commonly found in well-manured pastures, gardens, and around silage pits in autumn. The base of the puffball is attached to the mycelium in the soil by a thick central stalk. While fruiting bodies are normally more or less spherical, if growth is very rapid they can split like overwatered cherries and become irregularly shaped.

To determine if a giant puffball is ready for eating, tap the outside. A sound similar to that of tapping an inflated football is a good indication that it can be consumed. Next, try to push a finger gently into the surface. If this leaves a depression, as it would with risen dough, the puffball has probably started to produce spores and is no longer in an edible condition. Giant puffballs appear to rapidly pass into the inedible spore-producing stage after being exposed to a day or so of sunshine. This developmental stage is associated with a change in the color of the interior of the fruiting body from white to pale yellow and then to greenish or brownish gray, by which time the contents will have become powdery and the puffball will have split open, allowing the spores to spill out. It may then become detached from the soil and perhaps roll around in the wind.

One of the easiest ways to prepare the giant puffball is to simply slice it and fry the pieces in butter, although finding a large enough frying pan may be a challenge. The very largest specimens of the giant puffball ever reported were more than 150 cm in diameter, 45 cm high, and would have weighed more than 100 kg when fresh (*Guinness Book of Records* 2000).

Lycoperdon perlatum (Gem-Studded Puffball) and *Lycoperdon pyriforme* (Pear-Shaped Puffball)

Species of *Lycoperdon* produce a fruiting body with an approximately spherical head (as the upper portion of a puffball is often called) supported by a broad stalk. When mature the head becomes filled with light to dark brown spores, which are released through a pore that develops at the top of the fruiting body. While the edibility of some species of *Lycoperdon* has not been determined, and while *L. marginatum* (peeling puffball) and *L. mixtecorum* contain hallucinogens (Benjamin 1995), *L. perlatum* (gem-studded puffball) and *L. pyriforme* (pear-shaped puffball) are edible provided they are picked when young and the contents of the head are still white and firm. Moreover, the spore mass of a number of different species of *Lycoperdon* has been used in traditional medicine to help stop the



Lycoperdon perlatum (gem-studded puffball). **EDIBLE.** (Hall)



Lycoperdon pyriforme (pear-shaped puffball). **EDIBLE.** (Johnson) flow of blood from open wounds and to relieve the pain of burns (Walleyn and Rammeloo 1994).

Lycoperdon perlatum is very widely distributed and is probably the single most common woodland puffball in North America. It can be found from midsummer to autumn as solitary, scattered, or clustered fruitings on the ground in both coniferous and hardwood forests. The fruiting bodies are pear-shaped to nearly round with a narrowed base, 2.5–6.5 cm wide, and 2.5–8 cm tall. The surface of the upper portion of the fruiting body is covered with short, cone-shaped white spines, which leave pockmarks when they fall off.

Lycoperdon pyriforme is a widespread, rather common puffball. The fruiting bodies are similar in shape to those of *L. perlatum* but lack the covering of conelike spines on the upper surface and are usually smaller, 1.5–4.5 cm in diameter and 2–5 cm high. However, the most important difference is that fruiting bodies of the pear-shaped puffball occur on decaying wood instead of the ground, though sometimes fruiting bodies growing on buried wood or wood debris may appear to be on the soil surface. This species is found during autumn and often occurs in dense clusters on old decaying logs and stumps.



Melanogaster ambiguus (false truffle). **EDIBLE.** (Hall)

Melanogaster Species

The fruiting bodies of species of *Melanogaster* superficially resemble those of truffles and are also very strong smelling. When people find these mushrooms they often jump to the conclusion that they have found a true truffle. However, the contents of a *Melanogaster* fruiting body are spongy, and though they may be black, sometimes with white flecks, they always lack the distinct network of white lines found in true truffles. *Melanogaster* can be eaten (Evans and Evans 1987), but the very pungent smell might be off-putting. *Melanogaster ambiguus* is a false truffle that fruits below the soil surface.

Rhizopogon rubescens (Shoro)

While shoro (literally "dew of the pine") can be found fruiting at the soil surface, this mushroom, like the truffle, is also found below ground. Fruiting bodies are typically spherical and 1–7 cm in diameter. They are white with pinkish or reddish blotches when young, turning light to mid brown with age. When conditions are dry, the surface of the fruiting body may crack, exposing the lighter-colored



Rhizopogon rubescens (shoro). **EDIBLE.** (Hall) interior. When young, the interior of the fruiting body is pale, spongy, and edible. However, as it matures the contents become darker and unpalatable. Eventually the whole fruiting body turns into a light brown, gelatinous mass. Occasionally shoro is found growing with *Rhizopogon luteolus*, which is not as palatable.

During the nineteenth century, shoro was consumed in large quantities in Japan, particularly in the Osaka and Kyoto districts. However, the mushroom is now rare and many Japanese chefs are unsure how to cook it. Although shoro has little flavor of its own, the spongelike texture of the fruiting body allows it to absorb the flavors of the food with which it is cooked. Its crisp texture is referred to by the Japanese as having a “good tooth touch,” which adds to its appeal. Shoro is also found in North America under pines (*Pinus*) and in April 2001 was cultivated on Monterey pine (*P. radiata*) in New Zealand.

Scleroderma Species (Earthballs)

The earthballs, belonging to the genus *Scleroderma*, occur as ectomycorrhizal associates of a wide range of trees, including oaks (*Quercus*) and eucalypts (*Eucalyptus*). Fruiting bodies are formed at the surface of the soil or just below it, and their more or less spherical shape makes it easy to confuse them with the often edible puffballs and truffles. *Scleroderma verrucosum*, for example, is sometimes mistaken for a truffle. Earthballs can be distinguished from puffballs and truffles by cutting their fruiting body in half with a sharp knife. Immature earthballs have an off-white, spongy interior; but as they mature, brown spores form inside, giving the contents a purple-brown to black color. This dense, dark tissue is surrounded by a tough white or light brown covering. Some species also have a stalk at the bottom of the fruiting body. Earthballs do not have the network of pale lines characteristic of truffles. Puffballs, in contrast, are white inside until the spores mature and gradually turn yellowish, eventually becoming brown and powdery.

Although earthballs sometimes smell like field mushrooms, at least four species—*Scleroderma albidum*, *S. areolatum*, *S. cepa*, and *S. citrinum*—are poisonous. Symptoms can occur within an hour of eating and include loss of consciousness, nausea, severe abdominal pains, vomiting, perspiration, generalized tingling sensations, spasms, cramps, paralysis, and anaphylactic shock (Benjamin 1995, Bresinsky and Besl 1990, Southcott 1997).



Scleroderma verrucosum. **POISONOUS.** (Hall)



As they mature, the contents of *Scleroderma* species turn black and spongy. **POISONOUS.** (Hall)

Daldinia concentrica (Carbon Balls)

Daldinia concentrica belongs to a large and diverse group of ascomycetes that decay the wood of living and dead broadleaf trees. The irregularly spherical to cushion-like fruiting bodies of this fungus are commonly encountered on dead but not yet decorticated trunks and on branches of such trees as ash (*Fraxinus*), beech (*Fagus*), and oak (*Quercus*). At first red-brown but later becoming black (hence the common name), fruiting bodies are 2–4 cm across and quite hard to the touch. When sectioned, the conspicuous concentric zones present on the interior of the fruiting body are revealed. Nothing about this fungus suggests it might be suitable for the table.



Daldinia concentrica (carbon balls). **EDIBILITY UNKNOWN: AVOID.** (Johnson)

Chapter IX
Universal Tao Practices

Cosmic Inner Smile



Fig. 9.1 *Inner Smile*

The Inner Smile begins at the eyes and the mideyebrow point and moves down to the heart. As you activate the heart, the loving energy will flow out and you will feel the energy of your Inner Smile flow down the entire length of your body like a waterfall. This is a very powerful and effective tool to counteract stress, tension and negative Chi.

13. Mushrooms with fruiting bodies consisting of a simple or branched linear structure growing from decaying wood or arising from an adult or larval insect

Cordyceps Species (Vegetable Caterpillar Fungi) and *Claviceps* Species

Vegetable caterpillar fungi typically infect insects or their larvae, though some species infect spiders and other small animals. Once inside, the fungus grows through the tissues, producing a mummy more or less in the shape of the host. Eventually one or more thin spindle-shaped stalks grow upward out of the mass of fungal tissue, and the spores are produced in small flask-shaped structures located at the top of the stalk. Some of the caterpillars infected by *Cordyceps* live in vertical underground burrows, and finding the light to dark brown, twiglike fungal stalks that grow out of these burrows can take some practice. While most species of *Cordyceps* are parasitic on insects, *C. ophioglossoides* and *C. capitata* grow on *Elaphomyces* species.

Several species of *Cordyceps* have been used in traditional medicine for the treatment of such things as liver disorders. Moreover, the



All that can be seen of the vegetable caterpillar fungus (*Cordyceps robertsii*) is a thin twiglike fruiting structure above the soil surface. **MEDICINAL.** (Wang)



Cordyceps robertsii that has been excavated to show the association between the underground infected caterpillar and aboveground fruiting structure. **MEDICINAL.** (Wang)



The parasitic *Cordyceps ophioglossoides* grows on a truffle (*Elaphomyces* sp.). **EDIBILITY UNKNOWN: AVOID.** (Wang) active agents found in these fungi (probably ophiocordin and various polysaccharides) have been reported to have antitumor, antibiotic, and antifungal properties. In China *C. sinensis* is so revered as a medicine that it sells for up to $2000 per kilogram. Members of the closely related genus *Claviceps* are parasites on cereal grains such as wheat and rye, producing sclerotia in the diseased flowers of the host plant. The sclerotia of *Claviceps purpurea* (wheat ergot) contain several types of toxic alkaloids that can result in death when consumed by humans or livestock. However, these same substances have also been used medicinally to induce labor, to prevent hemorrhaging associated with childbirth, and to ease the pain of migraine headaches (Alexopoulos et al. 1996).

Xylaria polymorpha (Dead Man's Fingers)

The genus *Xylaria* is both large and widely distributed throughout the world. One of the most common species is dead man's fingers (*X. polymorpha*), so called because the fruiting bodies are somewhat finger-like in both shape and size. These are typically 2–8 cm high and 1–3 cm thick, occurring in clusters (though solitary fruiting bodies are occasionally encountered) on logs and stumps of broadleaf trees, especially beech (*Fagus*) and maple (*Acer*). Gray-brown or light brown when young, they become black when mature. Only the crust-like surface of the fruiting body is black, however: the interior is white. This fungus is much too tough to be considered edible.

14. Mushrooms with spindle-, coral-, icicle-, or cauliflower-shaped fruiting bodies

Clavaria, *Clavulinopsis*, and *Ramaria* are among the common genera of club and coral mushrooms. Most are found on the ground or on wood, and some form mycorrhizas. *Ramaria formosa* (pink coral mushroom) often forms in large mats, while *Clavulina cavipes* can sometimes be little more than a few small stalks on the soil surface. *Clavulina rugosa* and some species of *Clavaria* and *Clavulinopsis* are edible (Imazeki et al. 1988, Phillips 1981), whereas *R. formosa* and *R. pallida* cause stomach cramps and diarrhea. However, most species are too small and tasteless to be worth collecting for the table.



Xylaria polymorpha (dead man's fingers). **EDIBILITY UNKNOWN: AVOID.** (Izawa)



Ramaria formosa (pink coral mushroom). **POISONOUS.** (Izawa)



Clavulina cavipes, a coral mushroom. **EDIBILITY UNKNOWN: AVOID.** (Hall)



Clavulina cristata (crested coral). **EDIBILITY UNKNOWN: AVOID.** (Johnson)

Clavulina cristata (Crested Coral)

Clavulina cristata is a widely distributed species of coral mushroom often encountered on the ground in hardwood and coniferous forests throughout temperate regions of the Northern Hemisphere. The fruiting body is a white to buff, many-branched structure that is 2.5–8.0 cm high and 2–4 cm wide. The individual branches have toothlike, jagged tips. This mushroom is edible but too tough to be worth considering for the table. *Ramaria stricta* is very similar in appearance to *C. cristata* but has consistently parallel straight branches and, more importantly, occurs on wood.

Sparassis crispa (Cauliflower Fungus)

The cauliflower fungus is a parasite of pines (*Pinus*) and can be found around the bases of infected trees and on wood buried in the ground. It can be up to 50 cm in diameter and is therefore large enough to provide an entire meal. The fruiting body consists of numerous



Sparassis crispa (cauliflower fungus). **EDIBLE.** (Izawa)



Ileodictyon cibarium (basket fungus). **EDIBLE.** (Cole)



Ileodictyon cibarium (basket fungus) just beyond the edible egg stage. (Cole)



Aseroe rubra hatching from an egg that is tightly wrapped around the base of the stem. **EDIBILITY UNKNOWN: AVOID.** (Squires)



Geastrum saccatum (earthstar). **EDIBILITY UNKNOWN: AVOID.** (Johnson)

flattened, somewhat leaflike branches arising from a short, thick, deeply rooted, central stalklike base. The branches are at first white to buff but darken with age. This widely distributed species is found throughout temperate regions of the Northern Hemisphere. It is considered a choice edible mushroom, but it has to be cleaned of bits of wood, insects, and soil before cooking, and this can be a real chore.

15. Mushrooms with basket-shaped fruiting bodies or fruiting bodies with tentacle-like arms hatching from an egg

Clathrus ruber (Latticed Stinkhorn) and *Ileodictyon cibarium* (Basket Fungus)

Both the latticed stinkhorn and the basket fungus grow from an egg about 5 cm in diameter. The North American species *Clathrus ruber*

1. Be aware of the **mideyebrow,** imagining that your are in one of your favorite places in the world, a place where you feel safe, relaxed and happy. Recall the sights you might have seen there, the sounds you might have heard, the scents, sensations and flavors that you associate with that place.
2. Imagine that one of your favorite people is standing in front of you, smiling to you with loving, happy, radiant shining eyes. **Smile** to your face and slightly lift up the corners of your mouth.
3. Feel yourself responding to that special person's smile with a smile of your own. Feel your eyes smiling and relaxing.
4. Smile down to the **thymus gland** and picture a white flower blossoming. Gently inhale into the thymus gland, connecting your breath to the olfactory organ. Smell the good fragrance.
5. Aim your inner attention at your **heart**, picturing the heart before your inner eye and smile to it. **Smile** until you feel the heart smile back to you. Picture your heart like a red rose, gradually opening. This will activate the **love** and fire of **compassion** in the heart. Once you feel the red light and loving awareness it will activate the **cosmic red healing light** or mist from above and around you.
6. Smile at the light or mist and very slowly with a soft, long, deep breath draw the red mist, love and compassion into the mideyebrow, down through the mouth and throat, into the heart and gradually overflowing to the **small intestine**. Exhale, but retain the red light and the love and compassion in the **heart and small intestine**. At the same time exhale the cloudy, black or negative energy. Keep on doing this breathing 18 to 36 times waiting until the heart becomes bright red before your inner vision and starts to radiate out to the tongue, mouth, nose, ears and eyes. Allow the red light to whirl around you and form a **red aura**. Feel your skin glowing with red energy.
7. Let the heart's loving energy radiate out to the **lungs**. Aim your attention at the lungs; picture them before your inner eye and smile to them. **Smile** until you feel the lungs smile back to you. Picture your lungs like a white rose, gradually opening; smell the good fragrance. This will activate the courage in the lungs. Once you invoke the white light and courage into the lungs, you will also activate the **cosmic white healing light** or mist from above and around you.
8. Smile at the light or mist and very slowly, softly take a long deep breath and draw the white mist into the mideyebrow, the mouth and down to the lungs, gradually overflowing into the **large intestine**. Exhale but retain the white light and the feeling of courage in the lungs. At the same time exhale the cloudy, black or negative energy. Keep on doing this kind of breathing 18 to 36 times, waiting until the lungs become bright white and start to radiate out to the nose, ears, eyes, tongue and mouth. Invite the white light to whirl around you and form a **white aura** covering your skin like autumn dew.
9. The **spleen, pancreas and stomach** correspond to the yellow color of the earth element. Connect to these organs and smile down into them from the mideyebrow.

is probably not edible. *Ileodictyon cibarium* is edible while in the egg stage, but once it opens out into a basket-like structure 10–15 cm in diameter, it begins to produce an unpleasant aroma that attracts flies. At one time the New Zealand Maori ate the basket fungus in the egg stage (Riley 1988).

Clathrus archeri and *Aseroe rubra* (Octopus Stinkhorns)

While octopus stinkhorns are edible in the egg stage before they hatch from the egg (Arora 1986), they eventually open out into star-shaped structures that, though attractive to look at, have awful aromas. These aromas attract flies, which carry the slimy spore masses away on their legs.

16. Mushrooms with spherical fruiting bodies that open out into star-shaped structures, with the spores contained in a central ball that discharges dry spores through a small central pore—earthstars

Geastrum saccatum (Earthstar)

Geastrum saccatum is closely allied to puffballs. The fruiting bodies are initially spherical but with a two-layered wall. The outer wall splits from the top down, opening out into a star-shaped structure with the spherical inner wall at its center. A pore forms at the top of the central sphere, and through this the dry spores are released.

17. Mushrooms with more or less cup-shaped fruiting bodies, with the spores produced inside the cup on a feltlike surface or within small egglike structures

Aleuria aurantia (Orange-Peel Mushroom)

The shallow cup-shaped fruiting body of *Aleuria aurantia* somewhat resembles a discarded piece of orange peel, which accounts for the common name of this mushroom. Usually occurring on areas of disturbed soil such as those found along roads and paths, orange-peel mushroom is widely distributed throughout the world. Fruiting bodies are commonly 2–10 cm in diameter, occur in clusters, and lack



Aleuria aurantia (orange-peel mushroom). **EDIBLE.** (Johnson)

a stalk. The upper (inner) surface is bright orange to reddish orange or orange-yellow, with the lower (outer) surface noticeably lighter and slightly downy. Though thin and rather brittle, the fruiting bodies are edible and have been consumed either raw or cooked. The latter, of course, is the safer choice.

Peziza, *Helvella*, *Paxina*, and *Sarcosphaera* Species

Peziza, *Helvella*, *Paxina*, and *Sarcosphaera* are all ascomycetes that produce cup-shaped fruiting bodies, with the spores formed in asci that cover the concave upper surface of the cups. These mushrooms are typically found on the surface of soil. The fruiting bodies of *Peziza vesiculosa* (common dung cap), *Helvella acetabulum* (brown-ribbed elfin cup), and *Paxina leucomelas* (white-footed elfin cup) are poisonous unless cooked well (Phillips 1981), while the similar species *Sarcosphaera crassa* (crown fungus) is considered suspect (Bresinsky and Besl 1990). The edibility of many other species of these genera is unknown.



An ascocarp of *Peziza ammophila* growing in a sand dune. **EDIBILITY UNKNOWN: AVOID.** (Wang)



Peziza species growing on a bark-based potting mix in a garden shop. The green color is the result of an alga growing in the surface layers of the fruiting body. **EDIBILITY UNKNOWN: AVOID.** (Hall)



Cyathus striatus (bird's nest fungus). **EDIBILITY UNKNOWN: AVOID.** (Johnson)

Cyathus striatus and *Crucibulum laeve* (Bird's Nest Fungi)

Most fungi with cup-shaped fruiting bodies are ascomycetes, but a few are basidiomycetes. Such is the case for the bird's nest fungi, so named because the fruiting bodies produced by members of this group resemble miniature bird's nests with eggs inside. What look like eggs are actually peridioles. The "nests" function as splash cups, using the force of falling raindrops to disperse the peridioles. Under ideal conditions, a peridiole can be displaced more than a meter from the fruiting body, where it may land on some type of organic debris subject to being colonized by the mycelium that develops from the spores inside the peridiole. The broadly cup-shaped fruiting bodies of *Cyathus striatus* are commonly 7–15 mm high and 6–8 mm wide at the top, narrowing below. The outer surface of the cup is firm, cinnamon-brown to dark brown, and covered with shaggy, woolly hairs. The inner surface is smooth, shiny, and noticeably grooved. The peridioles are 1–1.5 mm in diameter, somewhat triangular, and dark in color. In *Crucibulum laeve*, another common and widely distributed bird's nest fungus, the peridioles are white to buff. Fruiting bodies of *Cyathus striatus* occur on hardwood debris, twigs, bark, and wood chips throughout North America.

18. Mushrooms with cushion-shaped fruiting bodies that are at first outwardly slimy, then rather fragile

Fuligo septica (Scrambled-Egg Slime Mold)

All the mushrooms described thus far belong to two major taxonomic classes: the Ascomycetes and the Basidiomycetes. *Fuligo septica* belongs to an entirely different group of organisms: the Myxomycetes, or slime molds. Slime molds have long intrigued and perplexed biologists because they possess characteristics of both fungi and animals. The fruiting bodies they produce resemble those of fungi, but some of their other characteristics, including the capability for locomotion during the feeding stage, are normally associated only with animals. In fact myxomycetes are now considered to be members of the Protozoa, separate from both fungi and animals. For most of its life a slime mold exists as a thin, free-living mass of protoplasm. Sometimes this mass is several centimeters across and, as the name "slime mold" suggests, viscous or slimy to the touch. This mass of protoplasm, called a plasmodium, can change form and creep slowly about, much like a giant amoeba. As it moves along, the plasmodium feeds upon bacteria and bits of organic matter.

Slime mold plasmodia occur in moist, shady places such as within crevices of decaying wood and beneath the partially decayed bark of logs and stumps. After a period of feeding and growth, the plasmodium moves out of its usual habitat and into a drier, more exposed location. Here it transforms into one or more fruiting bodies. Most slime mold fruiting bodies are quite small, often no more than a millimeter or two in height. However, this is not the case for *Fuligo septica*, which produces cushion-shaped fruiting bodies often 10–20 cm wide and 1–3 cm thick. They are red to bright yellow or, less often, white to pale or bright pink. The outer portion of the fruiting body is calcareous and rather fragile. When disrupted, a dark gray or dull black spore mass is revealed. Fruiting bodies typically occur on decaying wood or bark but can also be found on forest floor litter and even bare soil. *Fuligo septica* is one of the few slime molds reported to have been consumed by humans (Stephenson and Stempen 1994).



Fuligo septica (scrambled-egg slime mold). **EDIBLE.** (Izawa)

However, it is the transforming plasmodium and not the mature fruiting body that is eaten. In any case, this mushroom should not be considered an item for the table.

---

19. Mushrooms with leaflike fruiting bodies that are dark green or nearly black and closely appressed to vertical rocky surfaces

---

Umbilicaria esculenta (Iwatake)

Umbilicaria esculenta is a lichen—a "composite" organism formed by a fungus and an alga. It is considered a delicacy in China and Japan, where it has been collected and eaten for centuries. It is usually found on exposed, rocky, mountainous, vertical faces, which is why it is commonly known as *iwatake* ("rocky fungus") in Japan and as *shier* and *yaner* ("rocky ear") in China. Intrepid collectors, often hanging suspended on a rope, pluck iwatake from the rock surfaces upon which it occurs, and later dry it before offering it for sale. Iwatake is often incorporated into soups or stir fry dishes with meats. Before cooking with it, however, the lichen is soaked in warm water and soil and other debris are removed. In China iwatake is used in traditional medicine to treat coughs (Hu et al. 1980).



Umbilicaria esculenta (iwatake). **EDIBLE.** (Hall)

This page intentionally left blank

CONVERSION CHART

inches	centimeters
⅛	0.3
¼	0.6
⅓	0.8
½	1.25
⅔	1.7
¾	1.9
1	2.5
1¼	3.1
1⅓	3.3
1½	3.75
1¾	4.4
2	5.0
3	7.5
4	10
5	12.5
6	15
7	17.5
8	20
9	22.5
10	25
2	30
5	37.5
8	45
20	50
24	60
30	75
36	90

feet	meters
¼	0.08
⅓	0.1
½	0.15
1	0.3
1½	0.5
2	0.6
2½	0.8
3	0.9
4	1.2
5	1.5
6	1.8
7	2.1
8	2.4
9	2.7
10	3.0
15	4.5
20	6.0
25	7.5
30	9.0
35	10.5
40	12
45	13.5
50	15

°C = 5⁄9 × (°F–32)

°F = (9⁄5 × °C) + 32

1 hectare = 2.47 acres

1 acre = 0.405 hectare

This page intentionally left blank

First connect to the heart, then attract the clear yellow light from above and around you. You might see the **golden yellow aura** of a wheat field ready for harvest. Expel feelings of worry; exhale the cloudy, sticky energy. Breathe in the golden yellow aura, filling your spleen center with golden yellow light. Repeat to complete 18 to 36 cycles, then allow the light to radiate out to your mouth, nose, ears, eyes and tongue. Wrap the golden aura around you, leaving a golden shine on your skin.

10. The **kidneys and bladder** correspond to the blue color of the water element. Gentleness is contained within the blue healing light. Inhale the blue aura into the kidneys. Expel feelings of fear or stress on breathing out. Allow your energy field to expand, breathing in and out the blue energy 18-36 times, until it starts to radiate out from your kidneys to your ears, eyes, tongue, mouth and nose. Gather the blue mist on your skin enveloping you with a **blue aura**.
11. The **liver and gall bladder** connect to the green color of the element wood; kindness replaces anger, which is expelled on breathing out. Do the same as above and create a **green aura** around you. Exhale the dark red, cloudy heat. Inhale the nourishing green of the forests. Do 18 to 36 cycles, until the green light has completely filled the liver and starts to radiate out to your eyes, tongue, mouth, nose and ears. Invite the green light to form a green aura around you.
12. **Smile** down to the **sexual organs** and reproductive system. Feel love and sexual arousal and the heart and sexual organs uniting. Observe how this process transforms the sexual energy into Chi. Channel down orange and red light to the sexual organs. Thank them for their work in keeping you alive and healthy. Rest. Do nothing. Gather and store the energy by smiling and spiraling in the Tan Tien.

Six Healing Sounds

The Six Healing Sounds enhance Therapeutic Work

Everyone has heard stories about gifted beings who possess great healing powers. People seek out gifted healers. Yet even in the best of circumstances, how much time can a great healer spend with you? One hour a day? An hour a week? What about the rest of the time? Thus you must learn how to take care of yourself; you must learn how to clear out your negative energy and transform it into positive healthy energy. If you maintain yourself in this way it will surely enhance any other therapy you are receiving.

The Six Healing Sounds are a simple yet powerful tool to promote physical, energetic and emotional healing and balance. If you are healing others, you can teach your students one or two of the Six Healing sounds each session, to enhance the effects of your therapeutic work. During the practice of the sound the resting period is very important. Growing the good virtue of the organs is essential so the negative or sick energy has less room to grow.

CHINESE NAMES OF MUSHROOMS

Chinese common names, scientific names, and English common names of edible and medicinal mushrooms known from China. Some of the mushrooms listed are not mentioned in the text because of their relatively minor importance outside of China. Additional information is provided in the text for many of the more important examples. English common names are given only for those species for which they are available.

† Species known or suspected to be mycorrhizal. $^{\mathrm{C}}$ Cultivated species.

*** Name formulated by Wang Yun.**

Chinese common name	Pinyin	Scientific name	English common name
白柄乳牛肝菌	baibing runiuganjun	*Suillus albivelatus* A. H. Sm., Thiers et O. K. Mill.†	
白草菇	baicaogu*	*Volvariella diplasia* (Berk. et Broome) Singer$^{\mathrm{C}}$	straw mushroom
白侧耳	baiceer*	*Pleurotus opuntiae* (Durieu et Lév.) Sacc.$^{\mathrm{C}}$	white oyster mushroom
白冬块菌	baidongkuaijun*	*Tuber hiemalbum* Chatin†	white winter truffle
白黄侧耳	baihuangceer	*Pleurotus cornucopiae* (Paulet) Rolland$^{\mathrm{C}}$	yellow oyster mushroom
白鸡油菌	baijiyoujun*	*Cantharellus subalbidus* A. H. Sm. et Morse†	white chanterelle
白块菌	baikuaijun*	*Tuber borchii* Vittad.†	bianchetto
白蜡伞	bailansan	*Hygrophorus eburneus* (Fr.) Fr.†	ivory waxy cap

Chinese common name	**Pinyin**	**Scientific name**	**English common name**
白林地菇	bailindigu	*Agaricus sylvicola* (Vittad.) Peck[C]	woodland agaricus
白香蘑	baixiangmo	*Lepista caespitosa* (Bres.) Singer	
白鲜菇	baixiangu	*Agaricus bernardii* Quél.	salt-loving agaricus
白猪块菌	baizhukuaijun*	*Choiromyces meandriformis* Vittad.[†]	white truffle
棒柄杯伞	bangbing beisan	*Clitocybe clavipes* (Pers.: Fr.) P. Kumm.	club-foot clitocybe
棒地菇	bangdigu*	*Terfezia claveryi* Chatin[†]	desert truffle
半开羊肚菌	bankai yangdujun	*Morchella semilibera* DC.: Fr.	half-free morel
鲍鱼侧耳	baoyuceer	*Pleurotus abalonus* Y. H. Han, K. M. Chen et S. Cheng[C]	abalone mushroom
巴西蘑菇	baxi mogu	*Agaricus blazei* Murrill	almond portobello
贝形拟侧耳	beixing nicer*	*Pleurocybella porrigens* (Pers: Fr.) Singer	angel's wings
杯形秃马勃	beixing tumabo	*Calvatia cyathiformis* (Bosc) Morgan	purple-spored puffball
变黑离褶伞	bianhei lizhesan	*Lyophyllum sykosporum* Hongo et Clémençon	
变绿红菇	bianlu honggu	*Russula virescens* (Schaeff.) Fr.[†]	quilted green russula
变盔孢伞	bianquibaosan	*Kuehneromyces mutabilis* (Schaeff.: Fr.) Singer et A. H. Sm.[C]	changeable pholiota
波甘地块菌	bogandi kuaijun*	*Tuber uncinatum* Chatin[†]	Burgundy truffle
伯格诺利块菌	bogenuoli kuaijun*	*Tuber mesentericum* Vittad.[†]	bagnoli truffle
波缘多孔菌	boyuan duokongjun	*Albatrellus confluens* (A. et S.: Fr.) Kotl. et Pouz.[†]	
彩色豆马勃	caise doumabo	*Pisolithus tinctorius* (P. Micheli ex Pers.: Pers.) Coker et Couch	dye-maker's false puffball
草地拱顶菌	caodi gongdingjun	*Camarophyllus pratensis* (Pers: Fr.) P. Kumm.[†]	meadow waxy cap
草菇	caogu	*Volvariella volvacea* (Bull.: Fr.) Singer[C]	straw mushroom
草莓菌	caomeijun*	*Cyttaria gunnii* Berk.	beech strawberry

Chinese common name	Pinyin	Scientific name	English common name
草原侧耳	caoyuan ceer*	*Pleurotus eryngii* (DC.: Fr.) Quél.[C]	king oyster mushroom
长根小奥德蘑	changgen xiaoaodemo*	*Oudemansiella radicata* (Relhan: Fr.) Singer	rooting oudemansiella
蝉花	chanhuan	*Cordyceps sobolifera* (Berk.) Berk.	
茶烟白齿菌	chayanbaichijun*	*Bankera fuligineoalba* (J. C. Schmidt: Fr.) Coker et Beers ex Pouzar[†]	
茶银耳	chayiner	*Tremella foliacea* Pers.: Fr.	
橙盖鹅膏	chenggai egao	*Amanita caesarea* (Scop.: Fr.) Pers.[†]	Caesar's mushroom
橙红乳菇	chenghongrugu	*Lactarius akahatsu* Tanaka[†]	
橙网孢盘菌	chengwang baopanjun	*Aleuria aurantia* (Pers.: Fr.) Fuckel[C]	orange-peel mushroom
赤褐鹅膏	chihe egao	*Amanita fulva* (Schaeff.) Fr.[†]	tawny grisette
虫草	chongcao	*Cordyceps sinensis* (Berk.) Sacc.	Chinese caterpillar fungus
垂幕菇	chuimugu	*Psathyrella candolleana* (Fr.: Fr.) Maire	common psathyrella
刺拟小齿伞	cinixiaochisan*	*Mycoleptodonoides aitchisonii* (Berk.) Maas Geest.	
刺托竹荪	cituo zhusun	*Dictyophora echinovolvata* M. Zang, D. R. Zheng et Z. X. Hu[C]	
粗鳞大环柄菇	culin dahuanbinggu	*Macrolepiota rachodes* (Vittad.) Singer	shaggy parasol
粗腿羊肚菌	cutui yangdujun	*Morchella crassipes* (Vent.: Fr.) Pers.	thick-footed morel
粗网柄牛肝菌	cuwangbingniuganjun	*Boletus ornatipes* Peck[†]	ornate-stalked bolete
粗壮口蘑	cuzhuangkoumo	*Tricholoma robustum* (Alb. et Schwein.: Fr.) Ricken (sensu Imazeki)[†]	
大孢菇	dabaogu*	*Agaricus macrosporus* (F. H. Møller et Jul. Schäff.) Pilát	

Chinese common name	**Pinyin**	**Scientific name**	**English common name**
大肥菇	dafeigu	*Agaricus bitorquis* (Quél.) Sacc.[C]	button mushroom
大马勃	damabo	*Calvatia gigantea* (Batsch: Pers.) Lloyd	giant puffball
大乳头蘑	darutoumo*	*Catathelasma imperiale* (Fr.) Singer[†]	imperial cap
大团囊虫草	datuannang chongcao	*Cordyceps ophioglossoides* (Ehrenb.: Fr.) Link	
大紫菇	dazigu	*Agaricus augustus* Fr.	the prince
点柄乳牛肝菌	dianbing runiuganjun	*Suillus granulatus* (L.: Fr.) Roussel[†]	dotted-stalk suillus
冬块菌	dongkuaijun	*Tuber brumale* Vittad.[†]	winter truffle
短柄乳牛肝菌	duanbing runiuganjun	*Suillus brevipes* (Peck) Kuntze[†]	short-stalked suillus
短裙竹荪	duanqun zhusun	*Dictyophora duplicata* (Bosc) E. Fisch.[C]	netted stinkhorn
盾蚁巢伞	dunyichaosan*	*Termitomyces clypeatus* R. Heim	termite mushroom
多汁鳞伞	duozhi linsan	*Pholiota adiposa* (Batsch: Fr.) P. Kumm.	fat pholiota
多汁乳菇	duozhi rugu	*Lactarius volemus* (Fr.: Fr.) Fr.[†]	weeping milky cap
俄勒冈白块菌	elegang baikuaijun*	*Tuber gibbosum* Harkn.[†]	Oregon white truffle
发光蜜环菌	faguang mihuangjun	*Armillaria tabescens* (Scop.) Emel	ringless honey mushroom
绯红蜡菇	feihong lagu*	*Hygrocybe coccinea* (Schaeff.: Fr.) P. Kumm.[†]	scarlet waxy cup
非洲地蘑	feizhou dimo*	*Tirmania africana* Chatin[†]	desert truffle
粉侧耳	fenceer*	*Pleurotus djamor* (Rumph. ex Fr.: Fr.) Boedijn[C]	pink oyster mushroom
凤尾菇	fengwuigu	*Pleurotus pulmonarius* (Fr.: Fr.) Quél.[C]	phoenix mushroom
粉状绒盖牛肝菌	fenzhuang ronggainiuganjun	*Xerocomus pulverulentus* (Opat.) J. E. Gilbert[†]	
粉紫香蘑	fenzixiangmo	*Lepista personata* (Fr.: Fr.) Cooke[†] [C]	field blewit

Chinese common name	Pinyin	Scientific name	English common name
浮雕马勃	fudiao mabo	*Calvatia caelata* (Bull.) Morg.	
茯苓	fuling	*Wolfiporia cocos* (F. A. Wolf) Ryvarden et Gilb.	fuling
肝色牛排菌	ganse niupaijun	*Fistulina hepatica* (Schaeff.: Fr.) With.	beefsteak fungus
干小皮伞	ganxiaopisan	*Marasmius siccus* (Schwein.: Fr.) Fr.	orange pinwheel
高大环柄菇	gaodahuanbinggu	*Macrolepiota procera* (Scop.: Fr.) Singer†	parasol mushroom
高丝膜菌	gaosimojun	*Cortinarius elatior* Fr.†	
高羊肚菌	gaoyangdujun	*Morchella elata* Fr.: Fr.	black morel
革质红菇	gezhi honggu	*Russula alutacea* (Pers.: Fr.) Fr.†	
格状猴头菌	gezhuang houtoujun	*Hericium clathroides* (Pall.: Fr.) Pers.	fungus icicles
冠锁瑚菌	guan suohujun	*Clavulina cristata* (Holmsk.: Fr.) J. Schröt.	crested coral
光孢环枝瑚菌	guangbao huangzhihujun	*Ramaria obtusissima* (Peck) Corner†	
光滑鳞伞	guanghua lingsan*	*Pholiota lubrica* (Pers.: Fr.) Singer	
管形鸡油菌	guangxing jiyoujun	*Cantharellus tubaeformis* (Bull.: Fr.) Fr.	autumn chanterelle
鬼笔	guibi	*Phallus impudicus* L.: Pers.†	common stinkhorn
古尼虫草	guni congcao	*Cordyceps gunnii* (Berk.) Berk.	vegetable caterpillar fungus
古氏地空菌	gushi dikongjun	*Geopora cooperi* Harkn.†	fuzzy truffle
含糊黑腹菌	hanhu heifujun	*Melanogaster ambiguus* (Vittad.) Tul. et C. Tul.	black-veined false truffle
好哈吐虫草	hauhatu chongcao*	*Cordyceps robertsii* (Hook.) Berk.	vegetable caterpillar fungus
好吐鲁虫草	hautulu chongcao*	*Cordyceps hauturu* Dingley	vegetable caterpillar fungus
褐环乳牛肝菌	hehuan runiuganjun	*Suillus luteus* (L.: Fr.) Roussel†	slippery jack

Chinese common name	Pinyin	Scientific name	English common name
黑孢块菌	heibao kuaijun	*Tuber melanosporum* Vittad.†	Périgord black truffle
黑地蕈	heidixun*	*Picoa carthusiana* Tul.	
黑蚁巢伞	heiyichaosan*	*Termitomyces fuliginosus* R. Heim	termite mushroom
褐圆孢牛肝菌	henyuanbaoniuganjun	*Gyroporus castaneus* (Bull.: Fr.) Quél.†	chestnut bolete
褐绒盖牛肝菌	heronggainiuganjun	*Xerocomus badius* (Fr.: Fr.) Kühner†	bay bolete
合生离褶伞	hesheng lizhesan*	*Lyophyllum connatum* (Schumach.: Fr.) Singer	
荷叶离褶伞	heye lizhesan	*Lyophyllum decastes* (Fr.: Fr.) Singer†	hatakeshimeji
褐疣柄牛肝菌	heyoubingniuganjun	*Leccinum scabrum* (Bull.: Fr.) Gray†	brown birch bolete
红盾赤褶菇	hongdun chizhegu	*Rhodophyllus clypeatus* (L.: Fr.) Quél.†	Roman shield entoloma
红盖鹅膏	honggai egao*	*Amanita hemibapha* (Berk. et Broome) Sacc.†	slender Caesar's mushroom
红菇蜡伞	honggu lasan	*Hygrophorus russula* (Schaeff.: Fr.) Quél.†	russula-like waxy cap
红鸡油菌	hongjiyoujun	*Cantharellus cinnabarinus* (Schwein.: Fr.) Schwein.†	red chanterelle
红绒盖牛肝菌	hongronggainiugangjun	*Xerocomus chrysenteron* (Bull.) Quél.†	red-cracked bolete
红须腹菌	hongxufujun	*Rhizopogon rubescens* (Tul. et C. Tul.) Tul. et C. Tul.†	shoro
红汁乳菇	hongzhi rugu	*Lactarius hatsudake* Tanaka†	hatsudake
厚环乳牛肝菌	houhuan runiuganjun	*Suillus grevillei* (Klotzsch) Singer†	larch bolete
厚鳞多孔菌	houlin duokongjun*	*Pachyma hoelen* Rumph. ex Fr.: Fr.	hoelen
猴头	houtou	*Hericium erinaceus* (Bull.: Fr.) Pers.[C]	lion's mane mushroom
桦澳洲牛干菌	hua aozhouniuganju*	*Austroboletus betula* (Schweinitz) E. Horak	shaggy-stalked bolete

Chinese common name	**Pinyin**	**Scientific name**	**English common name**
滑 菇	huagu	*Pholiota nameko* (T. Ito) S. Ito et S. Imai[C]	nameko
花 脸 香 蘑	hualian xiangmo	*Lepista sordida* (Schumach.: Fr.) Singer	
华 美 牛 肝 菌	huamei niuganjun	*Boletus speciosus* Frost[†]	
黄 孢 红 菇	huangbao honggu	*Russula xerampelina* (Schaeff.) Fr.[†]	shrimp russula
黄 地 蘑	huangdimo*	*Tirmania pinoyi* (Maire) Malençon[†]	
黄 金 耳	huangjiner	*Tremella mesenterica* Retz.: Fr.[C]	witch's butter
黄 鸡 油 菌	huangjyoujun*	*Cantharellus luteocomus* H. E. Bigelow[†]	
黄 丝 膜 菌	huangsimojun	*Cortinarius claricolor* (Fr.) Fr. var. *turmalis* (Fr.) M. M. Moser[†]	
灰 鹅 膏	huiegao	*Amanita vaginata* (Bull.: Fr.) Lam.[†]	grisette
灰 盖 鬼 伞	huigai guisan	*Coprinus cinereus* (Schaeff.: Fr.) Gray[C]	shaggy dung coprinus
灰 光 柄 菇	huiguangbinggu	*Pluteus atricapillus* (Batsch) Fayod[†]	deer mushroom
灰 褐 香 蘑	huihexiangmo	*Lepista luscina* (Fr.: Fr.) Singer	
灰 口 蘑	huikoumo	*Tricholoma portentosum* (Fr.: Fr.) Quél.[†]	streaked tricholoma
灰 离 褶 伞	huilizhesan*	*Lyophyllum fumosum* (Pers.: Fr.) P. D. Orton	ashy tricholoma
灰 色 锁 瑚 菌	huisesuohujun	*Clavulina cinerea* (Bull.: Fr.) J. Schröt.	gray coral
灰 树 花	huishuhua	*Grifola frondosa* (Dicks.: Fr.) Gray	hen of the woods
虎 皮 小 牛 肝 菌	hupi xiaoniuganjun	*Suillus pictus* (Peck) Kuntze[†]	painted suillus
假 猴 头	jiahoutou	*Hericium ramosum* (Bull.) Letell.[C]	comb tooth mushroom

Chinese common name	**Pinyin**	**Scientific name**	**English common name**
尖羊肚菌	jianyangdujun	*Morchella conica* Pers.: Fr. var. *deliciosa* (Fr.: Fr.) Cetto	black morel
胶玉蘑	jiaoyumo*	*Hypsizygus marmoreus* (Peck) H. E. Bigelow[C]	shimeji
加州块菌	jiazhou kuaijun*	*Tuber californicum* Harkn.[†]	California truffle
洁丽香菇	jieli xianggu	*Lentinus suffrutescens* (Brot.: Fr.) Fr.	train-wrecker
金耳	jiner	*Tremella aurantia* Schwein.: Fr.	golden ear
晶粒鬼伞	jingli guisan	*Coprinus micaceus* (Bull.: Fr.) Fr.	mica cap
金褐伞	jinhesan	*Phaeolepiota aurea* (Matt.: Fr.) Maire	
金毛多汁鳞伞	jinmao lingsan	*Pholiota aurivella* (Batsch.: Fr.) P. Kumm.	golden pholiota
金针菇	jinzhengu	*Flammulina velutipes* (Curtis: Fr.) Singer[C]	enokitake
寄生田头菇	jisheng tiantougu*	*Agrocybe parasitica* Stevenson	poplar mushroom
鸡油菌	jiyoujun	*Cantharellus cibarius* Fr.: Fr.[†]	chanterelle
卷缘齿菌	juanyan chijun	*Hydnum repandum* L.: Fr.[†]	hedgehog mushroom
菌核侧耳	junhe ceer	*Pleurotus tuber-regium* (Rumph. ex Fr.: Fr.) Singer[C]	sclerotia-producing pleurotus
空柄小牛肝菌	kongbing xiaoniuganjun	*Suillus cavipes* (Opat.) A. H. Sm. et Thiers[†]	hollow-stalked boletus
口蘑	koumo	*Tricholoma mongolicum* S. Imai	
喇叭菌	labajun	*Craterellus cornucopioides* (L.: Fr.) Pers.[†]	horn of plenty
兰黄红菇	lanhuang honggu	*Russula cyanoxantha* (Schaeff.) Fr.[†]	blue russula
兰绿乳菇	lanlu rugu	*Lactarius indigo* (Schwein.: Fr.) Fr.[†]	indigo milky
兰圆孢牛肝菌	lanyuanbaoniuganjun	*Gyroporus cyanescens* (Bull.: Fr.) Quél.[†]	bluing bolete
肋脉羊肚菌	leimai yangdujun	*Morchella costata* (Vent.) Pers.	morel

Chinese common name	Pinyin	Scientific name	English common name
雷蘑	leimo	*Leucopaxillus giganteus* (Sibth.: Fr.) Singer[†]	giant clitocybe
裂褶菌	liezhejun	*Schizophyllum commune* Fr.: Fr.	common split gill
鳞多孔菌	lin duokongjun	*Polyporus squamosus* (Huds.: Fr.) Fr.	dryad's saddle
林地蘑菇	lindi mogu	*Agaricus sylvaticus* Schaeff.	forest mushroom
棱柄马鞍菌	lingbing maanjun	*Helvella lacunosa* Afzel.: Fr.[†]	elfin sandle
柄条孢牛肝菌棱	lingbing tiaobaoniuganjun	*Boletellus russellii* (Frost) J. E. Gilbert[†]	jagged-stalked bolete
菱红菇	linghonggu	*Russula vesca* Fr.[†]	edible russula
灵芝	lingzhi	*Ganoderma* aff. *lucidum* (W. Curt.) P. Karst.[C]	reishi
栗牛肝菌	liniugajun*	*Boletus aestivalis* (Paulet) Fr.[†]	white-cap bolete
硫磺菌	liuhuangjun	*Laetiporus sulphureus* (Bull.: Fr.) Murrill	chicken of the woods
梨形灰孢	lixing huibao	*Lycoperdon pyriforme* Schaeff.: Pers.[†]	pear-shaped puffball
隆纹黑蛋巢菌	longwei heidanchaojun	*Cyathus striatus* (Huds.: Pers.) Willd.	bird's nest fungus
漏斗鸡油菌	loudou jiyoujun	*Cantharellus infundibuliformis* (Scop.) Fr.[†]	funnel-shaped chanterelle
鹿花菌	luhuajun	*Gyromitra esculenta* (Pers.) Fr.[†]	false morel
雷丸	luiwan	*Laccocephalum mylittae* (Cook et Massee) Núñez et Ryvarden	native bread
铆钉菇	maodinggu	*Chroogomphus rutilus* (Schaeff.: Fr.) O. K. Mill.	viscid gomphidius
毛木耳	maomuer	*Auricularia polytricha* (Mont.) Sacc.[C]	wood ear
毛头鬼伞	maotou guisan	*Coprinus comatus* (Müll.: Fr.) Pers.[C]	shaggy ink cap
美味牛肝菌	meiwei niuganjun	*Boletus edulis* Bull.: Fr.[†]	porcini
美味红菇	meiwui honggu	*Russula delica* Fr.[†]	milk-white russula
美味乳菇	meiwui rugu	*Lactarius deliciosus* (L.: Fr.) Gray[†]	saffron milk cap

Chinese common name	Pinyin	Scientific name	English common name
美洲松茸	meizhou songrong	*Tricholoma magnivelare* (Peck) Redhead[†]	white matsutake
蜜环丝膜菌	mihuan simojun	*Cortinarius armillatus* (Fr.: Fr.) Fr.[†]	bracelet cortinarius
摩冬块菌	modongkuaijun*	*Tuber brumale* Vittad. var. *moschatum* Ferry[†]	
蘑菇	mogu	*Agaricus campestris* L.: Fr.	field mushroom
墨汁鬼伞	mozhi guisan	*Coprinus atramentarius* (Bull.: Fr.) Fr.	common ink cap
木耳	muer	*Auricularia auricula* (Pers.: Fr.) Fuckel[C]	wood ear
南非地菇	nanfi digu*	*Terfezia pfeilii* Henn.[†]	
囊侧耳	nangceer*	*Pleurotus cystidiosus* O. K. Mill.[C]	abalone mushroom
囊马勃	nangmabao*	*Vascellum pratense* (Pers.: Pers.) Kreisel	common puffball
粘柄丝膜菌	nianbing simojun	*Cortinarius collinitus* (Sow.: Fr.) Fr.[†]	
粘小奥德蘑	nianxiaoaodemo	*Oudemansiella mucida* (Schrad.: Fr.) Höhn.[C]	porcelain fungus
鸟褐地菌	niaohedijun*	*Phaeangium lefebvrei* Pat.[†]	desert truffle
拟兰紫丝膜菌	nilanzisimojun*	*Cortinarius pseudosalor* J. E. Lange[†]	
柠檬蜡伞	ningmeng lasan*	*Hygrophorus lucorum* Kalchbr.[†]	
牛舌菌	niushejun	*Fistulina hepatica* (Schaeff.: Fr.) With. var. *antarctica* (Speg.) J. E. Wright	chestnut tongue
拟凹陷块菌	niwaxian kuaijun	*Tuber pseudoexcavatum* Y. Wang, G. Moreno, Riousset, Manjón et G. Riousset[†]	Chinese truffle
浓香乳菇	nongxiang rugu	*Lactarius camphoratus* (Fr.: Fr.) Fr.[†]	aromatic milky
欧洲松茸	ouzhou songrong	*Tricholoma caligatum* (Viv.) Ricken[†]	European matsutake

The sounds are also used to generate certain frequencies for specific healing. Each sound can generate different energy for the healing of the different organs.

Once the movements, sounds and information have been integrated into your practice you can simplify and make the Six Healing Sounds more powerful. For example, when you are settled into the lung sound and you are breathing white healing light and feel the mideyebrow wide open, you put the awareness in the 'Tan Tien and Universe'.

Chi will flow from the universe into the Tan Tien and just the right amount and quality will flow from the Tan Tien into the lungs and large intestine. Just set up the location (the organ) and connect to the universe and the Chi will flow to the correct location!

When doing these, the eyes are open only while making the sound.

Six Healing Sounds - Practice



Lung Sound

Element: Metal
Associated Organ: Large Intestine
Sound: SSSSSSS (Tongue behind Teeth)
Emotions: Negative - Grief, Sadness, Depression
Positive - Courage, Righteousness, High Self Esteem
Color: White, Clear, Metallic
Season: Fall
Direction: West

Position: Sit in a chair with your back straight and your hands resting palms up on your thighs. Have your feet flat on the floor about a hip's width apart . **Smile** down to your lungs and be aware of any sadness, grief or excess heat in your lungs. Slowly inhale and raise your hands up your center line with your fingers pointing toward each other. When your hands pass your shoulder level, begin to rotate the palms out as you continue raising your hands up in front of you and above your head with the palms up. Point your fingers towards the fingers of the opposite hand and keep your elbows slightly bent.

Sound: Part your lips slightly, keeping your jaw gently closed. Look up through the space between your two hands and push your palms slightly upward as you slowly exhale and make the sound, "SSSSSSS". Picture and feel any excess heat, sadness, grief, depression, sickness and dingy white color expelled and released as you exhale slowly and fully.

Chinese common name	Pinyin	Scientific name	English common name
平菇	pinggu	*Pleurotus ostreatus* (Jacq.: Fr.) P. Kumm.^C	oyster mushroom
葡萄状枝瑚菌	putaozhuang zhihujun	*Ramaria botrytis* (Pers.: Fr.) Ricken†	purple-tipped coral fungus
捕蝇口蘑	puying koumo*	*Tricholoma muscarium* Kawam. ex Hongo†	
漆蜡蘑	qi lamo	*Laccaria laccata* (Scop.: Fr.) Berk. et Br.†	the deceiver
翘鳞伞	qiaolingsan	*Pholiota squarrosa* (Oeder: Fr.) P. Kumm.	scaly pholiota
球杯伞	qiubeisan*	*Clitocybe gibba* (Pers.: Fr.) P. Kumm.	common funnel cap
日本口蘑	ribenkoumo*	*Tricholoma japonica* Kawam.†	
绒盖条孢牛肝菌	ronggai tiaobaoniuganjun	*Boletus mirabilis* Murrill†	admirable bolete
绒红铆钉菇	ronghongmaodinggu	*Chroogomphus tomentosus* (Murrill) O. K. Mill.	woolly gomphidius
绒木耳	rongmuer*	*Auricularia fuscosuccinea* (Mont.) Henn.^C	black jelly fungus
肉色杯伞	rouse beisan	*Clitocybe geotropa* (Bull. ex DC.) Quél.	
肉色香蘑	rouse xiangmo	*Lepista irina* (Fr.) H. E. Bigelow	
乳牛肝菌	runiugangjun	*Suillus bovinus* (L.: Fr.) Kuntze†	Jersey cow bolete
稍厚赤褶菇	shaohou chizhegu	*Rhodophyllus crassipes* (Imazeki et Toki) Imazeki et Hongo†	
沙生地菇	shasheng digu*	*Terfezia arenaria* (Moris) Trappe†	desert truffle
傻松茸	shasongrong	*Tricholoma bakamatsutake* Hongo†	bakamatsutake
石耳	shier	*Umbilicaria esculenta* (Miyoshi) Minks	iwatake
双孢蘑菇	shuangbao mogu	*Agaricus bisporus* (J. E. Lange) Imbach^C	button mushroom
树状蜡伞	shuzhuang lansan	*Hygrophorus arbustivus* Fr.†	

Chinese common name	Pinyin	Scientific name	English common name
丝盖口蘑	sigai koumo	*Tricholoma sejunctum* (Sowerby: Fr.) Quél.[†]	separating tricholoma
丝盖小包脚菇	sigai xiaobaojiaogu	*Volvariella bombycina* (Schaeff.: Fr.) Singer[C]	silky volvaria
松茸	song rong	*Tricholoma matsutake* (S. Ito et S. Imai) Singer[†]	matsutake
松牛肝菌	songniuganjun*	*Boletus pinicola* (Vittad.) A. Venturi[†]	cep
桃红牛肝菌	taohongniuganjun	*Boletus regius* Krombh.[†]	butter bolete
田头菇	tiantougu	*Agrocybe praecox* (Pers.: Fr.) Fayod	spring agrocybe
铁杉灵芝	tieshan lingzhi	*Ganoderma tsugae* Murrill[C]	hemlock polypore
铜绿红菇	tongluhonggu	*Russula aeruginea* Lindblad ex Fr.	green russula
铜色牛肝菌	tongse niuganjun	*Boletus aereus* Bull.: Fr.[†]	cep
土褐牛肝菌	tuheniuganjun	*Boletus pallidus* Frost[†]	
陀螺菌	tuoluojun	*Gomphus clavatus* (Pers.: Fr.) Gray[†]	short-stalked chanterelle
网柄牛肝菌	wangbing niuganjun*	*Boletus reticulatus* Schaeff.[†]	cep
网兜菌	wangdoujun*	*Ileodictyon cibarium* Tul. et C. Tul.	basket fungus
网纹灰孢	wangwen huibao	*Lycoperdon perlatum* Pers.: Pers.[†]	gem-studded puffball
凹陷块菌	waxian kuaijun	*Tuber excavatum* Vittad.[†]	hollowed truffle
纹环球盖菇	wenhuan qiugaigu*	*Stropharia rugosoannulata* Farl. ex Murrill[C]	wine-cap stropharia
纹褶小奥德蘑	wenzhe xiaoaodemo*	*Oudemansiella venosolamellata* (Imazeki et Toki) Imazeki et Hongo	
污褐牛肝菌	wuheniuganjun	*Boletus variipes* Peck[†]	
夏块菌	xiakuaijun	*Tuber aestivum* Vittad.[†]	summer truffle
线柄松塔牛肝	xianbing songtaniugang	*Strobilomyces floccopus* (Vahl: Fr.) P. Karst.[†]	old man of the woods
香杯伞	xiangbeisan	*Clitocybe odora* (Fr.) P. Kumm.	anise-scented clitocybe

Chinese common name	Pinyin	Scientific name	English common name
香菇	xianggu	*Lentinula edodes* (Berk.) Pegler	shiitake
香肉齿菌	xiangrouchijun	*Sarcodon aspratus* (Berk.) S. Ito[†]	
香信口蘑	xiangxing koumo	*Calocybe gambosa* (Fr.: Fr.) Singer	St. George's mushroom
小牛肝菌	xiaoniuganjun	*Fuscoboletinus paluster* (Peck) Pomerleau[†]	
小蚁巢伞	xiaoyichaosan*	*Termitomyces microcarpus* (Berk. et Broome) R. Heim	termite mushroom
细柄丝膜菌	xibing simojun*	*Cortinarius tenuipes* (Hongo) Hongo[†]	
斜盖伞	xiegaisan	*Clitopilus prunulus* (Scop.: Fr.) P. Kumm.	sweet bread mushroom
新西兰榛蘑	xinxilan zhenmo*	*Armillaria novaezelandiae* (Stevenson) Herink	bootlace mushroom
绣球菌	xiuqiujun	*Sparassis crispa* (Wulfen: Fr.) Fr.[C]	cauliflower fungus
血红乳菇	xuehong rugu	*Lactarius sanguifluus* (Paulet) Fr.[†]	red-juice milk cap
羊肚菌	yangdujun	*Morchella esculenta* Pers.: Fr.	yellow morel
羊肚菌	yangdujun	*Morchella esculenta* var. *rigida* Krombh.	yellow morel
羊肚菌	yangdujun	*Morchella esculenta* var. *rotunda* Pers.: Fr.	yellow morel
羊肚菌	yangdujun	*Morchella esculenta* var. *umbrina* (Boud.) S. Imai	yellow morel
羊肚菌	yangdujun	*Morchella esculenta* var. *vulgaris* Pers.: Fr.	yellow morel
艳乳菇	yanrugu*	*Lactarius laeticolor* (S. Imai) Imaz.[†]	
烟云杯伞	yanyun beisan	*Clitocybe nebularis* (Batsch.: Fr.) P. Kumm.	clouded clitocybe
药用层孔菌	yaoyong cengkongjun	*Fomitopsis officinalis* (Batsch: Fr.) Bondartsev et Singer	purging agaric
亚香棒虫草	yaxiangbang chongcao	*Cordyceps hawkesii* G. R. Grey	

Chinese common name	Pinyin	Scientific name	English common name
亚砖红沿丝伞	yazhuanhong yansisan	*Naematoloma sublateritium* (Fr.) P. Karst.	brick caps
野蘑菇	yemogu	*Agaricus arvensis* Schaeff.	horse mushroom
蚁巢伞	yichaosan	*Termitomyces albuminosa* (Berk.) R. Heim	termite mushroom
意大利白块菌	yidali baikuijun*	*Tuber magnatum* Picco[†]	Italian white truffle
印度块菌	yindu kuaijun	*Tuber indicum* Cooke et Massee[†]	Indian truffle
银耳	yiner	*Tremella fuciformis* Berk.[C]	white jelly fungus
硬柄皮伞	yingbing pisan	*Marasmius oreades* (Bolton: Fr.) Fr.[C]	fairy ring mushroom
蛹虫草	yong chongcao	*Cordyceps militaris* (L.: Fr.) Link	scarlet caterpillar fungus
油口蘑	youkoumo	*Tricholoma flavovirens* (Pers.: Fr.) S. Lundell[†]	canary tricholoma
油味乳菇	youwei rugu	*Lactarius quietus* (Fr.: Fr.) Fr.[†]	southern milk cap
远东疣柄牛肝菌	yuandong liubingniugangjun	*Leccinum extremiorientale* (Lar. N. Vassiljeva) Singer[†]	
元蘑	yuanmo	*Hohenbuehelia serotina* (Pers.: Fr.) Singer[C]	mukitake
缘纹丝膜菌	yuanwen simojun	*Cortinarius praestans* (Corda) Gillet[†]	
榆耳	yuer	*Gloeostereum incarnatum* S. Ito et Imai	
榆黄蘑	yuhuangmo	*Pleurotus cornucopiae* (Paulet) Rolland var. *citrinopileatus* (Singer) Ohira	golden oyster mushroom
云芝	yunzhi	*Trametes versicolor* (L.: Fr.) Pilát	many-colored polypore
玉髯	yuran	*Hericium coralloides* (Scop.: Fr.) Gray[C]	coral tooth mushroom
玉蕈离褶伞	yuxun lizhesan*	*Lyophyllum shimeji* (Kawam.) Hongo[†]	honshimeji
皂腻口蘑	zaoni koumo	*Tricholoma saponaceum* (Fr.: Fr.) P. Kumm.[†]	soap-scented tricholoma

Chinese common name	Pinyin	Scientific name	English common name
杂色黑腹菌	zase heifujun	*Melanogaster variegatus* (Vittad.) Tul. et C. Tul.	black-veined false truffle
赭盖鹅膏	zhegai egao	*Amanita rubescens* Pers.: Fr.†	the blusher
榛蘑	zhenmo	*Armillaria mellea* (Vahl: Fr.) P. Kumm.	honey mushroom
中非议巢伞	zhongfei yichaosan*	*Termitomyces schimperi* (Pat.) R. Helm	termite mushroom
中华块菌	zhonghua kuaijun	*Tuber sinense* K. Tao et B. Liu†	Chinese truffle
轴灰包	zhou huibao	*Podaxis pistillaris* (L.: Pers.) Morse	stalked puffball
皱盖罗鳞伞	zhougai luolinsan	*Rozites caperatus* (Pers.: Fr.) P. Karst†	gypsy mushroom
猪苓	zhuling	*Grifola umbellata* (Pers.: Fr.) Pilát.	umbellate polyporus
竹荪	zhusun	*Dictyophora indusiata* (Vent.: Pers.) Desv.C	bamboo mushroom
柱状田头菇	zhuzhuang tiantougu	*Agrocybe cylindracea* (DC.) MaireC	southern poplar mushroom
紫晶腊蘑	zijing lamo	*Laccaria amethystea* Cooke†	amethyst laccaria
紫牛肝菌	ziniuganjun	*Boletus violaceofuscus* W. F. Chiu†	
紫绒丝膜菌	zirongsimojun	*Cortinarius violaceus* (L.: Fr.) Fr.†	violet cortinarius
紫色马勃	zise mabo	*Calvatia lilacina* (Mont. et Berk.) Henn.	puffball
紫色丝膜菌	zisesimojun	*Cortinarius purpurascens* (Fr.) Fr.†	
紫珊瑚菌	zishanhujun	*Clavaria purpurea* O. F. Müll.: Fr.	purple fairy club
紫香蘑	zixiangmo	*Lepista nuda* (Bull.: Fr.) Cooke† C	wood blewit
棕红块菌	zonghong kuaijun	*Tuber rufum* Picco†	cinnamon truffle

HELPFUL ADDRESSES

Australasian Mycological Society
c/o Cheryl Grgurinovic
Australian Biological Resources Study
G.P.O. Box 787
Canberra, A.C.T. 2601, Australia

Australian Truffle Association
c/o Australian Truffle Industries
P.O. Box 93
Bombala, New South Wales 2632, Australia

British Mycological Society
Joseph Banks Building
Royal Botanic Gardens, Kew
Richmond Surrey, TW9 3AB, United Kingdom

Danish Mycological Society
Foreningen til Svampekundskabens Fremme
Søndermarken 75
3060 Espergærde, Denmark

German Mycological Society
Deutsche Gesellschaft für Mykologie
c/o Wolfgang Thrun
Postfach 700447
D-81304 München, Germany

Italian Mycological Society
Unione Mycologica Italiana
c/o Gilberto Govi
Centro di Micologia
Università di Bologna
Via Filippone 8
1-40126 Bologna, Italy

Korean Society of Mycology
c/o Department of Applied Biology
College of Biological Resources Science
Dongguk University
Seoul 100-715, Republic of Korea

Mycological Society of Finland
Suomen Sieniseura Ry
Unioninkatu 44
SF 00170 Helsinki 17, Finland

Mycological Society of Japan
c/o Business Center for Academic Societies Japan
5-16-9 Honkomagome
Bunkyo-ku, Tokyo 113-8622, Japan

Mycological Society of the Republic of China
c/o Wen-Hsui Hsieh
Department of Plant Pathology
National Chung Hsing University
Taichung, Taiwan, Republic of China

Netherlands Mycological Society
c/o Centraalbureau voor Schimmelcultures
Postbus 85167
3508 AD Utrecht, Netherlands

New Zealand Truffle Association
c/o New Zealand Institute for Crop and Food Research
Invermay Agricultural Centre
Private Bag 50034
Mosgiel, New Zealand

North American Mycological Association
c/o Judy Roger, Executive Secretary
6615 Tudor Court
Gladstone, Oregon 97027-1032, United States

North American Truffling Society
P.O. Box 296
Corvallis, Oregon 97339, United States

Norwegian Mycological Society
Norsk Soppforening
Postboks 2828 Tøyen
N-0655 Oslo, Norway

Swedish Mycological Society
Sveriges Mykologisk Förening
c/o Arne Ryberg
Boafallsvägen 10
293 72 Jämshög, Sweden

Tartufomania
25 Via Zena
40065 Bologna, Italy

Le Trufficulteur Français
B.P. 7065
rue de Jardin Public
24007 Périgeaux, France

WEB SITES

American Mushroom Institute (AMI).
http://www.americanmushroom.org/

Bad Bug Book. Foodborne pathogenic microorganisms and natural toxins handbook. U.S. Food and Drug Administration, Center for Food Safety and Applied Nutrition.
http://www.cfsan.fda.gov/~mow/chap40.html

British Mycological Society (BMS).
http://www.ulst.ac.uk/faculty/science/bms/

Canadian Poison Control Centers. A list created by the Children's Safety Association of Canada. http://www.safekid.org/

Centers for Disease Control and Prevention (CDC).
http://www.cdc.gov

Economic Fungi of China.
http://www.has-china.com/new_page_1.htm

Fungi Images on the Net. http://www.in2.dk/fungi/

Fungi of California. http://www.mykoweb.com/CAF/index.html

Fungi Perfecti. www.fungi.com

George Barron's Web Site on Mushrooms and Other Fungi. University of Guelph. Guelph, Ontario.
http://www.uoguelph.ca/~gbarron/

Introduction to the Fungi. University of California, Berkeley.
http://www.ucmp.berkeley.edu/fungi/fungi.html

Malawi Fungi. http://www.malawifungi.org/

Mushroom Council. http://www.mushroomcouncil.com/

Mushroom Toxins. vm.cfsan.fda.gov/~mow/chap40

Mycorrhiza Information Exchange. http://mycorrhiza.ag.utk.edu/

Myxo Web: A Virtual Field Guide to the Myxomycetes.
http://www.wvonline.com/myxo/

National Capital Poison Center (United States).
http://www.poison.org/

National Poisons Information Service (United Kingdom). http://www.npis.org/

Northwest Fungus Group. http://www.fungus.org.uk/nwfg.htm

Penn State University Mushroom Industry Short Course. http://conferences.cas.psu.edu/

Poison Center Directory. http://www.aapcc.org/director2.htm

Psylocybe Fanaticus. http://www.fanaticus.com/

Sacred Mushrooms: The Vaults of Erowid. http://www.erowid.org/plants/mushrooms/

Tom Volk's Fungi. Department of Biology. University of Wisconsin, La Crosse. http://www.botit.botany.wisc.edu/toms_fungi/

Truffle.org: The New Smell of Truffles. http://www.truffle.org/

Wild Mushrooms from Tokyo. http://www.ne.jp/asahi/mushroom/tokyo/right

WWW Virtual Library of Mycology. Cornell University. http://www.mycology.cornell.edu

Resting Posture: When you have completely exhaled, rotate the palms to face downward with the fingers still pointing toward each other. Slowly lower the palms and bring them just in front of the chest feeling the lung's aura.

Close your eyes and be aware of your lungs. **Smile** into your lungs, and as you inhale, imagine that you are breathing in a **bright white mist of light**. Breathe this light into your lungs and feel it cooling, cleansing, invigorating, healing and refreshing your lungs. Feel it flowing down to the large intestine to balance the energy of the yin lungs and yang large intestine, allowing the **courage** quality of your lungs to emerge. Grow more courage, so sadness and depression have less room to grow. With each inbreath, feel yourself drawing in cool fresh energy. With each outbreath, mentally make the Lung Sound and release any remaining sadness or hot energy.

Repeat at least three times. For the first two repetitions, you can make the sound aloud. On the third or last repetition, make the sound sub-vocally (vocalizing the sound so softly that only you can hear it) Repeat six, nine, twelve or twenty four times to alleviate extreme sadness, depression, colds, flu, toothaches, asthma and emphysema.



Kidney Sound

Element: Water
Associated Organ: Bladder
Sound: CHOOOOOO (with your lips forming an "O" as if blowing out a candle.)
Emotions: Negative - Fear, Shock
Positive - Gentleness, Wisdom
Color: Dark Blue or Black
Season: Winter
Direction: North

Position: Now move the hands to cover the kidneys. **Smile** to your kidneys, and be aware of any excess cold or heat in the kidney region. Then bring your legs together, ankles and knees touching. Lean forward and clasp the fingers of both hands together around your knees. Inhale and pull your arms straight from the lower back while bending the torso forward (this allows your back to protrude in the area of the kidneys). Tilt your head upward as you look straight ahead, still pulling on your arms from the lower back. Feel your spine pulling against your knees.

Sound: Round the lips slightly and slowly exhale while making the sound "CHOOOOOO." Simultaneously contract your abdomen, pulling it in toward your kid-

GLOSSARY

For other mycological terms and names see *Elsevier's Dictionary of Edible Mushrooms* (Chandra 1989) and *Ainsworth and Bisby's Dictionary of the Fungi* (Kirk et al. 2001).

Actinomycete. Usually filamentous, gram-positive bacteria (for example, *Streptomyces*) that superficially resemble filamentous fungi.

Aerobic. Living and growing only in the presence of oxygen.

Arbuscules. Microscopic treelike structures that form in vesicular-arbuscular mycorrhizas and help transfer nutrients between the host plant and fungus.

Ascocarp. A cup-shaped structure formed by some ascomycetes, on which asci develop.

Ascomycetes. The largest class of fungi, containing more than thirty-two thousand species. Members are referred to as ascomycetes.

Ascospore. A sexual spore produced by ascomycetes and usually borne in an ascus.

Ascus (pl. **asci**). A saclike structure produced by ascomycetes in which ascospores are produced.

Autoclave. An oven used to sterilize media and equipment using steam typically at 121°C.

Bagasse. The dry pulp (as of sugar cane, for example) left after extracting juice from plant material.

Basidiomycetes. A class of fungi containing more than thirty thousand species, including the rusts, smuts, and most fungi that produce what are commonly called "mushrooms." Members are referred to as basidiomycetes.

Biological efficiency rating. The fresh weight of mushrooms expressed as a fraction of the dry weight of the substrate.

Bioluminescent. Producing light through a biological process.

Biomass. A quantity of biological material.

Block. A substrate formed into a more or less rectangular slab.

Brûlé. The bare area around truffle-infected trees, said to indicate the start of truffle production.

Button stage. The stage of a young mushroom before the cap has expanded and opened out.

Cap. The fertile, usually upper section of a mushroom. Also called the pileus.

Carbon-nitrogen ratio. The organic carbon present in a soil, expressed as a fraction of total nitrogen.

Casing. A mixture of moistened peat, top soil, and lime spread over mushroom compost.

Cellulose. A carbohydrate composed of very long chains of glucose molecules. Cellulose is the major structural component in the cell walls of higher plants.

Cortina. A network of delicate weblike material that covers the gills in some mushrooms.

Culture. The cultivation of an organism on a suitable medium, as with nutrient agar grown in a petri dish.

Cyclopeptides. Amino acids arranged in a ring.

Ectomycorrhiza. A mycorrhizal fungus that usually forms a mantle.

Gasteromycetales. An artificial group of about twelve hundred species that do not actively discharge their spores, placed in the Basidiomycetes.

Gills. The vertical plates on the underside of the caps of certain mushrooms, on which spores are formed. Also called the lamellae.

Hartig net. A hyphal network formed by ectomycorrhizal fungi that extends from the inner surface of the mantle into the root of a host plant.

Head. The name generally given to the upper expanded portion of stinkhorns and puffballs.

Heavy metal. A generally toxic metal, such as chromium, lead, and mercury.

Herbarium. A systematically arranged collection of dried plant or fungal specimens.

Hypha (pl. **hyphae**). One of the filaments of a fungal mycelium.

Infect. To contaminate, as when a fungus invades a plant.

Indigenous. Native to a particular area.

Inoculate. To place a culture of something—for example, a fungus—on a culture medium or potential host plant.

Lamina flow cabinet. A sterile chamber that allows an operator to manipulate bacterial and fungal cultures.

Little brown mushrooms (LBMs). A category of mushrooms, some of which are poisonous and all of which are difficult to identify without the use of a microscope.

Macroscopic. Large enough to be seen by the naked eye.

Mantle. The layer of fungal material covering the fine roots of an ectomycorrhizal host plant.

Membranous. Very thin.

Microscopic. Too small to be seen by the naked eye.

Mycelium. A mass of fungal hyphae.

Mycorrhiza. The close symbiotic association of a fungus and a host plant.

Niche. A habitat that supplies the appropriate set of conditions needed for a species to grow and thrive.

Parasite. An organism that gains its nutrients from a host organism with or without causing damage to the host.

Pasteurization. A process that involves heating a substance in order to free it of objectionable organisms.

Pathogen. An organism that causes disease.

Peridioles. Small egglike packages containing spores; characteristic of the bird's nest fungi.

pH. A measure of soil acidity and alkalinity. A value of 7 indicates neutrality, a value higher than 7 indicates alkalinity, and a value lower than 7 indicates acidity.

Plasmodium (pl. **plasmodia**). The irregular, amoebic structure formed by slime molds.

Polysaccharide. A chain of sugar molecules.

Primordium (pl. **primordia**). An organ, such as a fruiting body, in the early stages of development.

Quarantine. A period of isolation imposed on animals or plants that have arrived from elsewhere or that may have been exposed to an infectious disease.

Radioisotope. A radioactive isotope.

Ring. A ringlike structure on the stalk of some mushrooms that represents the remains of the partial veil. Also called the annulus.

Saprobe. An organism that gains its nutrients from animal or plant remains.

Sclerotium (pl. **sclerotia**). A mass of fungal tissue most often appearing underground.

Shiro. The underground fungal colony formed by *Tricholoma* species.

Spawn. A culture of a fungus used to inoculate the substrate.

Specialty mushroom. Any cultivated mushroom other than *Agaricus bisporus* and *A. bitorquis*.

Spines. The vertical projections on the underside of the caps of certain mushrooms, such as species of *Hydnum* and *Sarcodon*, on which spores are formed.

Spore. A general term for a typically small reproductive structure in bacteria, bryophytes, ferns, fungi, lichens, and slime molds.

Stalk. The section of a mushroom between the substrate and the cap. Also called the stipe or stem.

Sterilize. To completely free of living organisms.

Strain. A clonal culture of an organism.

Substrate. The material on which a fungus or bacterium grows.

Symbiosis. A close physical relationship between dissimilar organisms in which both partners generally benefit.

Toadstool. A mushroom with an umbrella-shaped cap. The word is a corruption of the German *Todesstuhl* ("death's stool"), which has no scientific meaning.

Toxin. A poison produced by a living organism.

Truffle. The underground fruiting body of fungi in the Tuberales, such as species of *Tuber*.

Truffière. A natural area or artificial plantation where truffles are found.

Tubes. The vertical pores on the underside of the caps of certain mushrooms, such as *Boletus* and *Suillus* species, in which spores are formed.

Veil. A membrane that covers the gills on certain mushrooms.

Vesicles. Swollen cells at the end of hyphae that form in vesicular-arbuscular mycorrhizas and function as small storage organs.

Vesicular-arbuscular mycorrhiza (**VAM**). A mycorrhiza formed by the vast majority of higher plants in association with fungi in the family Endogonaceae.

Volva. The cup at the base of the stalk, especially of species of *Amanita*.

REFERENCES AND FURTHER READING

In addition to references cited, we have included information about useful Asian, Australasian, and Western field guides and books on the cultivation of saprobic, mycorrhizal, and medicinal mushrooms.

Abate, D. 1996. Cultivation of the oyster mushroom in traditional brick pots. *Mycologist* 9: 179–181.

Alexopoulos, C. J., C. W. Mims, and M. Blackwell. 1996. *Introductory Mycology*. 4th ed. New York: John Wiley and Sons.

Allen, J. W., M. D. Merlin, and K. L. R. Jansen. 1991. An ethnomycological review of psychoactive agarics in Australia and New Zealand. *Journal of Psychoactive Drugs* 23: 39–69.

Anonymous. 1997. Cultivating morels. *The Mushroom Growers' Newsletter* 5 (12): 2–5.

Anonymous. 2000a. U.S. wholesale market prices. *The Mushroom Growers' Newsletter* 9 (5): 4.

Anonymous. 2000b. Truffle kerfuffle. *Divine Food and Wine* 23: 6–12.

Arora, D. 1986. *Mushrooms Demystified: A Comprehensive Guide to the Fleshy Fungi*. 2nd ed. Berkeley, California: Ten Speed Press. Western field guide.

Arora, D. 1991. *All That the Rain Promises and More: A Hip Pocket Guide to Western Mushrooms*. Berkeley, California: Ten Speed Press. Western field guide.

Astier, J. 1998. *Truffes Blanches et Noires* (Tuberaceae and Terfeziaceae). La Penne sur Huveaune, France: Joseph Astier. Western field guide.

Baker, H. 1989. Fungal styptics. *Mycologist* 3: 19–20

Baker, H. 1997. Gourmet mushrooms for all. *New Scientist* 153: 2066.

Barnhart, H. 2000. Reciprocity law failure fixed? *Mushroom: The Journal of Wild Mushrooming* 69 (4): 22.

Beauséjour, T. M. 2000. Morel cultivation for the adventurous and observant. *Mushroom: The Journal of Wild Mushrooming* 18 (3): 21–24.

Becker, P. 1983. Ectomycorrhizae on *Shorea* (Dipterocarpaceae) seedlings in a lowland Malaysian rainforest. *Malaysian Forester* 46: 146–170.

Bencivenga, M., and G. Vignozzi. 1989. *I tartufo in Toscana*. Firenze, Italy: Il vantaggio edizioni. Guide to cultivation of mycorrhizal mushrooms.

Benjamin, D. R. 1995. *Mushrooms: Poisons and Panaceas*. New York: W. H. Freeman.

Bessette, A. E., A. R. Bessette, and D. W. Fischer. 1997. *Mushrooms of Northeastern North America*. Syracuse, New York: Syracuse University Press. Western field guide.

Bessette, A. E., O. K. Miller, Jr., A. R. Bessette, and H. H. Miller. 1995. *Mushrooms of North America in Color*. Syracuse, New York: Syracuse University Press. Western field guide.

Bessette, A. E., W. C. Roody, and A. R. Bessette. 2000. *North American Boletes: A Color Guide to the Fleshy Pored Mushrooms*. Syracuse, New York: Syracuse University Press. Western field guide.

Beug, M. 1999. Your behaviour—just having a home and a lawn—could get you into trouble. *Mushroom: The Journal of Wild Mushrooming* 17 (4): 13–14.

Both, E. E. 1993. *The Boletes of North America*. Buffalo, New York: Buffalo Museum of Science. Western field guide.

Bougher, N. L., and K. Syme. 1998. *Fungi of Southern Australia*. Nedlands, Western Australia: University of Western Australia Press. Australasian field guide.

Branzanti, B., and A. Zambonelli. 1987. Effetti della micorrizazione sullo sviluppo di semenzali di *Pinus pinaster*. *Micologia Italiana* 16: 53–57. Guide to cultivation of mycorrhizal mushrooms.

Brasier, C. 1992. A champion thallus. *Nature* 356: 382–383.

Breitenbach, J., and F. Kränzlin. 1984–1995. *Fungi of Switzerland*. 5 vols. Lucerne, Switzerland: Verlag Mykologia. Western field guide.

Bresinsky, A., and H. Besl. 1990. *A Colour Atlas of Poisonous Fungi*. London: Wolfe.

Brightwell, S. 1993. Feasting on fungi. *New Zealand Geographic* 18 (April–June): 35–58. Australasian field guide.

Buchanan, P. K. 1995. Recent mushroom poisonings in New Zealand. *Australasian Mycological Newsletter* 14 (4): 57–60.

Buchanan, P. K. 1996. The mushroom cultivation industry in New Zealand. In *Proceedings of the Annual Meeting of the Mushroom Technology Society of Japan*. Chiba, Japan. 18–22.

Buchanan, P. K., R. S. Hseu, and J. M. Moncalvo, eds. 1995. *Ganoderma*: systematics, phytopathology, and pharmacology. In *Proceedings of Contributed Symposium 59 A, B, Fifth International*

Mycological Congress, 14–21 August 1994. Vancouver, British Columbia. Guide to medicinal mushrooms.

Buscot, F., and I. Kotte. 1990. The association of *Morchella rotunda* (Pers.) Boudier with roots of *Picea abies* (L.) Karst. *New Phytologist* 116: 425–430.

CBC Newsworld. 1996. Poison mushrooms kill 92 in Ukraine. Retrieved 1997 from http://newsworld.cbc.ca/archive/html/1996/10/01/poisonmushrooms

Centers for Disease Control and Prevention (CDC). 1997. *Amanita phalloides* mushroom poisoning—northern California, January 1997. Morbidity and Mortality Weekly Report 46 (22): 489–492. Retrieved 1997 from http://www.cdc.gov/epo/mmwr/preview/mmwrhtml/00047808.htm

Ceruti, A., M. Tozzi, and G. Reitano. 1988. Micorrize di sintesi tra *Boletus edulis*, *Pinus silvestris*, e *Picea excelsa*. *Allionia* 28: 117–124. Guide to cultivation of mycorrhizal mushrooms.

Cetto, B. 1989–1992. *I Funghi dal Vero*. 7 vols. Trento, Italy: Saturnia. Western field guide.

Chandra, A. 1989. *Elsevier's Dictionary of Edible Mushrooms: Botanical and Common Names in Various Languages of the World*. Amsterdam: Elsevier Science.

Chang, S. T. 1991. Mushroom biology and mushroom production. *Mushroom Journal for the Tropics* 11: 45–52. Guide to cultivation of saprobic mushrooms.

Chang, S. T. 1999. World production of cultivated edible and medicinal mushrooms in 1997 with emphasis on *Lentinus edodes* (Berk.) Sing. in China. *International Journal of Medicinal Mushrooms* 1: 291–300.

Chang, S. T., J. A. Buswell, and S. W. Chiu, eds. 1993. *Mushroom Biology and Mushroom Products*. Hong Kong: Chinese University Press. Guide to medicinal mushrooms and cultivation of saprobic mushrooms.

Chang, S. T., J. A. Buswell, and P. G. Miles. 1993. *Genetics and Breeding of Edible Mushrooms*. Chemin de la Sallaz, Switzerland: Gordon and Breach. Guide to medicinal mushrooms and cultivation of saprobic mushrooms.

Chang, S. T, and W. A. Hayes, eds. 1978. *The Biology and Cultivation of Edible Mushrooms*. New York: Academic Press. Guide to medicinal mushrooms and cultivation of saprobic mushrooms.

Chang, S. T., and P. G. Miles. 1989. *Edible Mushrooms and Their Cultivation*. Boca Raton, Florida: CRC Press. Guide to medicinal mushrooms and cultivation of saprobic mushrooms.

Chang, S. T., and P. G. Miles. 1992. Mushroom biology—a new discipline. *Mycologist* 6: 64–65. Guide to medicinal mushrooms and cultivation of saprobic mushrooms.

Chang, S. T., and T. H. Quimio. 1989. *Tropical Mushrooms: Biological Nature and Cultivation Methods*. Hong Kong: Chinese University Press. Guide to medicinal mushrooms and cultivation of saprobic mushrooms.

Chauvin, J. E., and G. Salesses. 1988. Quelques aspects de la culture in vitro chez le chataignier (*Castanea* sp.). In *Septieme colloque sur les recherches fruitières, 23 Decembre 1987, Pont de la Maye*. Bordeaux, France: CTIFL/INRA. 147–160. Guide to cultivation of mycorrhizal mushrooms.

Chen, A. W. 1997. Topical use of *Ganoderma* mushrooms. *The Mushroom Growers' Newsletter* 5 (11): 2–3. Guide to medicinal mushrooms.

Chen, A. W. 2001. A practical guide to the production of *Agaricus blazei*: a mushroom of culinary and biomedical importance. *The Mushroom Growers' Newsletter* 9 (9): 3–7. Guide to cultivation of saprobic mushrooms.

Chen, A. W., and N. L. Huang. 2001. Production of tuber-like sclerotia of medicinal value by *Pleurotus tuber-regium* (Fr.) Singer. *The Mushroom Growers' Newsletter* 10 (3): 2–7. Guide to cultivation of saprobic mushrooms.

Chen, A. W., P. Stamets, and N. L. Huang. 1999. Compost-substrate fermentation and alternatives for successful production of *Agaricus blazei*. In *Proceedings of the Third International Conference on Mushroom Biology and Mushroom Products and AMGA's Twenty-Sixth National Mushroom Industry Conference, October, 1999*. Two CD-ROMs. Eds. A. J. Broderick and N. G. Nair. Hawkesbury, Sydney, Australia: University of Western Sydney. Guide to cultivation of saprobic mushrooms.

Cherfas, J. 1991. Disappearing mushrooms: another mass extinction? *Science* 254: 1458.

Chevalier, G. 1998. The truffle cultivation in France: assessment of the situation after twenty-five years of intensive use of mycorrhizal seedlings. In *Proceedings of the First International Meeting on Ecology, Physiology, and Cultivation of Edible Mycorrhizal Mushrooms*. Uppsala, Sweden.

Chevalier, G., and C. Desmas. 1975. Synthèse axenique des mycorhizes de *Tuber melanosporum*, *Tuber uncinatum*, et *Tuber rufum* sur *Pinus sylvestris* a partir de cultures pures du champignon. *Annales de Phytopathologie* 7: 338. Guide to cultivation of mycorrhizal mushrooms.

Chevalier, G., and C. Dupré. 1990. Recherche et experimentation sur la truffe et la trufficulture en France. In *Atti del Secondo Congresso Internazionale sul Tartufo, 24–27 Novembre 1988*. Eds. M. Bencivenga and B. Granetti. Spoleto, Italy. 157–166. Guide to cultivation of mycorrhizal mushrooms.

Chevalier, G., and H. Frochot. 1997. La Truffe de Bourgogne, *Tuber uncinatum* Chatin. Levallois-Perret, France: Pétrarque. Guide to cultivation and ecology of mycorrhizal mushrooms.

Chevalier, G., and G. Riousset. 1995. Truffes de Chine. Quelle truffe? *Tuber himalayense* ou *T. indicum*. *Le Trufficulteur Français* 11: 13–14.

Chinese Association of Edible Fungi. 2000. Production of edible mushrooms in China. *Edible Fungi of China* 19 (2): 6.

Ciani, A., B. Granetti, and D. Vincenti. 1992. Il tartufo in Italia e nel mondo: aree di produzione, mercato e prezzi. *Líinformatore Agrario* 47: 51–62.

Cole, F. M. 1993. *Amanita phalloides* in Victoria. *Medical Journal of Australia* 158: 849–850.

Cole, M. 1994. Edible and poisonous fungi in southern Australia—cases of mistaken identity. *Mycologist* 8: 35–36.

Colinas, C., J. A. Bonet, and C. Fischer. 1999. Truffle cultivation: an alternative to agricultural subsidies. In *Proceedings, Fifth International Congress on the Science and Cultivation of Truffles*. Aix-en-Provence, France. (Abstract)

Cooke, R. C. 1980. *Fungi, Man, and His Environment*. 2nd ed. London: Longman Group.

Coombs, D. H. 1994. Cultivated morels are promised but—. *Mushroom: The Journal of Wild Mushrooming* 12 (4): 7.

Courtecuisse, R., and B. Duhem. 1995. *Mushrooms and Toadstools of Britain and Europe*. London: Collins. Western field guide.

Courvoisier, M. 1995. Les importations de truffes fraîches en provenance de Chine. *Le Trufficulteur Français* 11: 10–11.

Craddock, J. 1994. Mycorrhizal association between *Corylus heterophylla* and *Tuber melanosporum*. *ISHS Acta Horticulturae* 351: 291–298.

Craw, C. J. 1995. *Poisonous Plants and Fungi of New Zealand*. Whangarei, New Zealand: Northland Regional Council.

Cribb, A. 1987. Mushrooms and toadstools. In *Toxic Plants and Animals: A Guide for Australia*. Eds. J. Covacevich, P. Davie, and J. Pearn. Brisbane, Australia: Queensland Museum. 22–31.

Crowe, A. 1983. *A Field Guide to the Native Edible Plants of New Zealand*. Auckland, New Zealand: Collins. Australasian field guide.

Danell, E. 1994. *Cantharellus cibarius*: mycorrhiza formation and ecology. Acta Universitatis Upsaliensis. Comprehensive summaries of Uppsala dissertations from the Faculty of Science and Technology 35. Uppsala, Sweden. Guide to ecology of mycorrhizal mushrooms. http://www.mykopat.slu.se/mycorrhiza/kantarellfiler/texter/rtf.htm

Danell, E., and F. J. Camacho. 1997. Successful cultivation of the golden chanterelle. *Nature* 385: 303. Guide to cultivation of mycorrhizal mushrooms.

Dauncey, E. A., ed. 2000. *Poisonous Plants and Fungi in Britain and Ireland: Interactive Identification Systems on CD-ROM*. Kew, England: Royal Botanic Gardens. Western field guide.

Dhabolt, J. 1993. Mushroom poisons and poisonous mushrooms. *The Puffball: Newsletter of the Willamette Valley Mushroom Society* 16 (3). http://www.mv.com/ipusers/dhabolt/dad/mushroom/puffball/puffball4/poisonous.html

Dickinson, C., and J. Lucas. 1979. *The Encyclopedia of Mushrooms*. London: Orbis. Western field guide.

Duc-Maugé, B., and B. Duplessy. 1997. *Le Livre de la Truffe*. Aix-en-Provence, France: Édisud. Guide to cultivation of mycorrhizal mushrooms.

Eastman Kodak. 1988. *Photography through the Microscope*. 9th ed. Rochester, New York: Professional Photography Division.

Economic Research Service (ERS). 2002. Vegetables and Melons Outlook. U.S. Department of Agriculture, Washington, D.C. http://www.ers.usda.gov/publications/vgs/

Ecoplanning. 1992. Norme pratiche per la coltivazione del tartufo. Città di Castello, Italy: Ministero Dell'Agricoltura e Delle Foreste. Guide to cultivation of mycorrhizal mushrooms.

Eicker, A. 1990. Commercial mushroom production in South Africa. Bulletin 418. Pretoria, South Africa: Department of Agricultural Development.

Eto, S. 1990. Cultivation of the pine seedlings infected with *Tricholoma matsutake* by use of in vitro mycorrhizal synthesis. Bulletin of the Hiroshima Prefectural Forestry Experiment Station

neys. Imagine any fear, sickness, imbalances, excess cold or heat energy being released and squeezed out of the fascia surrounding the kidneys.

Resting Posture: After you have fully exhaled, slowly sit erect and return the hands to touch the aura of the kidneys. Close your eyes and again be aware of your kidneys. **Smile** to your kidneys and, on the inbreath, imagine you are breathing a brilliant **luminous blue light mist** into them; feel this mist healing, balancing and refreshing your kidneys and bladder and picture them glowing a bright blue color. On the outbreath, imagine you are still making the Kidney Sound.

Repeat at least 3 times, as with the previous sound. Repeat six, nine, twelve, or twenty four times to alleviate extreme fear, fatigue, low-pitched ringing in the ears, dizziness, back pain, bladder and urinary infections or other problems of the reproductive system.



Liver Sound

Element: Wood
Associated Organ: Gall Bladder
Sound: SHHHHHHH
Emotions: Negative - Anger, Frustration, Resentment
Positive - Loving Kindness, Benevolence, Forgiveness
Color: Green
Season: Spring
Direction: East

Position: Place the hands on the liver. **Smile** to your liver and be aware of any anger, frustration, resentment or excess heat. Slowly begin to inhale a deep breath as you extend your arms up from the sides with your palms up. Continue to raise them over your head. Interlace your fingers together and turn your joined hands over to face the sky, palms up. Push out through the heels of the palms and extend the arms up, keeping the shoulders relaxed. Bend a little to the left and stretch your right arm slightly to gently open the area of your liver.

Sound: Open your eyes wide (the eyes are the sensory opening of the liver). Slowly exhale, making the sound, "SHHHHHHH" sub-vocally. Feel that you are releasing any trapped excess heat, anger, illness and negativity from your liver and that these are riding out of your body on your breath.

Resting Posture: Once you have fully exhaled, separate your hands, turn the palms

24: 1–6. Guide to cultivation of mycorrhizal mushrooms (in Japanese).

Evans, F., and K. Evans. 1987. *The Cookbook of North American Truffles*. Corvallis, Oregon: The North American Truffling Society.

Evans, S. 1996. Reaction to *Laetiporus sulphureus*. *Mycologist* 10: 87.

Fauconnet, C., and G. Delher. 1998. Infuence des facteurs climatiques sur la production des truffes en Quercy. *Le Trufficulteur Français* 24 (3): 19–21. Guide to cultivation of mycorrhizal mushrooms.

Fischer, D. W., and A. E. Bessette. 1992. *Edible Wild Mushrooms of North America: A Field-to-Kitchen Guide*. Austin, Texas: University of Texas Press.

Flegg, P. B., D. M. Spencer, and D. A. Wood, eds. 1985. *The Biology and Technology of the Cultivated Mushroom*. Chichester, England: John Wiley and Sons. Guide to cultivation of saprobic mushrooms.

Fletcher, J. T., P. F. White, and R. H. Gaze. 1989. *Mushrooms: Pests and Disease Control*. Newcastle upon Tyne, England: Intercept. Guide to cultivation of saprobic mushrooms.

Flück, M. 1995. *Welcher Pilz Ist Das?* Stuttgart, Germany: Franckh-Kosmos Verlags.

Freedman, B. 1996. Recent *Amanita phalloides* poisonings. *Mushroom: The Journal of Wild Mushrooming* 14 (3): 9–11.

Fuhrer, B. 1985. *A Field Companion to Australian Fungi*. Hawthorn, Australia: Five Mile Press. Australasian field guide.

Fuhrer, B., and R. Robinson. 1992. *Rainforest Fungi of Tasmania and South-east Australia*. Melbourne, Australia: CSIRO. Australasian field guide.

Fujita, H, T. Fujita, and T. Ito. 1990. Study on cultivation technique of *Lyophyllum shimeji* using infected tree seedling. Annual Report of the Forestry Experimental Station, Kyoto Prefecture, Japan. (In Japanese)

Gamundí, I. J. 1991. Review of recent advances in the knowledge of the Cyttariales. *Systema Ascomycetum* 1 (2): 69–77.

Gamundí, I. J., and E. Horak. 1995. *Fungi of the Andean-Patagonian Forests*. Buenos Aires: Vazquez Mazzini Editores.

Garcia-Falces, R. S., and A. M. De Miguel Velasco. 1995a. Situación actual de la truficultura en Navarra. *Navarra Agraria* 89: 31–36.

Garcia-Falces, R. S., and A. M. De Miguel Velasco. 1995b. *Guia Practica de Truficultura*. Universidad de Navarra. Guide to cultivation of mycorrhizal mushrooms.

Garnweidner, E. 1990. *Pilze*. Munich: Gräfe und Unzer. Western field guide.

Genders, R. 1990. *Mushroom Growing for Everyone*. London: Faber and Faber. Guide to cultivation of saprobic mushrooms.

Gilbertson, R. L. 1980. Wood-rotting fungi of North America. *Mycologia* 72: 1–49.

Giovanetti, G. 1990. Prima produzione di carpofori di *Tuber magnatum* Pico da piante micorrizate fornite da vivai specializzati. In *Atti del Secondo Congresso Internazionale sul Tartufo, 24–27 Novembre 1988*. Eds. M. Bencivenga and B. Granetti. Spoleto, Italy. 297–302. Guide to cultivation of mycorrhizal mushrooms.

Giovanetti, G., and A. Fontana. 1982. Mycorrhizal synthesis between Cistaceae and Tuberaceae. *New Phytologist* 92: 533–537. Guide to cultivation of mycorrhizal mushrooms.

Giovanetti, G., N. Roth-Bejerano, E. Zanini, and V. Kagan-Zur, eds. 1994. Truffles and their cultivation. *Horticultural Reviews* 16: 71–107. Guide to cultivation of mycorrhizal mushrooms.

Gregori, G. L., and R. Ciappelloni. 1990. Contronto dell`intensita di micorrizazione fra *Corylus avellana* L. di tipo selvatico e da frutto con *Tuber magnatum* Pico. In *Atti del Secondo Congresso Internazionale sul Tartufo, 24–27 Novembre 1988*. Eds. M. Bencivenga and B. Granetti. Spoleto, Italy. 185–190. Guide to cultivation of mycorrhizal mushrooms.

Grgurinovic, C., and K. Mallett, eds. 1996. *Fungi of Australia*. Vols. 1A and 1B, Introduction: Fungi in the Environment. Canberra, Australia: Australian Biological Resources Study. Australasian field guide.

Guinberteau, J., J. M. Olivier, and M. R. Bordaberry. 1989. Données récentes sur la culture des "pieds bleus" (*Lepista* sp.). *P. H. M., Revue Horticole* 298: 17–22.

Guinberteau, J., G. Salesses, J. M. Olivier, and N. Poitou. 1990. Mycorization de vitroplants de noisetiers clones. In *Atti del Secondo Congresso Internazionale sul Tartufo, 24–27 Novembre 1988*. Eds. M. Bencivenga and B. Granetti. Spoleto, Italy. 205–210. Guide to cultivation of mycorrhizal mushrooms.

Guinness Book of Records. 2000. Stamford, Connecticut: Guinness.

Gutierrez Reyes, R. 2000. Indoor cultivation of paddy straw mushroom, *Volvariella volvacea*, in crates. *Mycologist* 14: 174–176.

Guzmán, G., and R. Watling. 1978. Studies in Australian agarics and boletes, 1: some species of *Psilocybe*. *Notes from the Royal Botanic Garden Edinburgh* 36: 199–210. Australasian field guide.

Haard, R., and K. Haard. 1980. *Poisonous and Hallucinogenic Mushrooms*. Seattle, Washington: Homestead. Western field guide.

Hall, I. R. 1988. Potential for exploiting vesicular-arbuscular mycorrhizas in agriculture. In *Biotechnology in Agriculture*. Vol. 9, Advances in Biotechnological Processes. Ed. A. Mizrahi. New York: Alan R. Liss. 141–174.

Hall, I. R., G. Brown, and J. Byars. 1994. *The Black Truffle: Its History, Uses, and Cultivation*. 2nd ed. Christchurch, New Zealand: New Zealand Institute for Crop and Food Research. Guide to cultivation of mycorrhizal mushrooms.

Hall, I. R., A. J. E. Lyon, Y. Wang, and L. Sinclair. 1998. Ectomycorrhizal fungi with edible fruiting bodies. 2. *Boletus edulis*. *Economic Botany* 52: 44–56. Guide to cultivation and ecology of mycorrhizal mushrooms.

Hall, I. R., and Y. Wang. 1996. Edible fungi—supplementary crops to wood production in plantation forests. In *Proceedings of the New Zealand Institute of Forestry Conference*. Invercargill, New Zealand. 77–82.

Hall, I. R., and Y. Wang. 2000. Edible mushrooms as secondary crops in forests. *Quarterly Journal of Forestry* 94: 299–304.

Hall, I. R., A. Zambonelli, and F. Primavera. 1998. Ectomycorrhizal fungi with edible fruiting bodies. 3. *Tuber magnatum*. *Economic Botany* 52: 192–200. Guide to cultivation and ecology of mycorrhizal mushrooms.

Hamlyn, P. F. 1996. Mycologist's guide to the internet. *Mycologist* 9: 165–167.

Hamlyn, P. F. 1997a. Mycological resources on the internet. *Mycologist* 10: 7.

Hamlyn, P. F. 1997b. Creating a mycological site on the internet. *Mycologist* 11: 23–26.

Harding, P., T. Lyon, and G. Tomblin. 1996. *How to Identify Edible Mushrooms*. London: Harper Collins. Western field guide.

Harris, B. 1993. *Growing Shiitake Commercially*. Summertown, Tennessee: Second Foundation Publications. Guide to cultivation of saprobic mushrooms.

Hayes, W. A. 1987. Edible mushrooms. In *Food and Beverage Mycology*, 2nd ed. Ed. L. R. Beuchat. New York: AVI. 355–390. Guide to cultivation of saprobic mushrooms.

Heckman, D. S., D. M. Geiser, B. R. Eidell, R. L. Stauffer, N. L. Kardos, and S. B. Hedges. 2001. Molecular evidence for the early colonization of land by fungi and plants. *Science* 293: 1129–1133.

Hobbs, C. 1995. *Medicinal Mushrooms*. Santa Cruz, California: Botanica Press. Guide to medicinal mushrooms.

Holmberg, P., and H. Marklund. 1996. *Nya Svampboken*. Stockholm, Sweden: Prisma. Western field guide.

Holmgren, P. K., N. H. Holmgren, and L. C. Barnett, eds. 1990. *Index Herbariorum, Part 1: The Herbaria of the World*. 8th ed. Regnum Vegetabile 120. Bronx, New York: New York Botanical Garden.

Hongo, T., T. Ueda, and M. Izawa. 1994. *Fungi: Field Book Number 10*. Toyko: Yama-kei. Asian field guide (in Japanese).

Hood, I. A. 1992. *An Illustrated Guide to Fungi on Wood in New Zealand*. Auckland, New Zealand: Auckland University Press.

Hopple, J. S., and R. Vilgalys. 1994. Phylogenetic relationships among coprinoid taxa and allies based on data from restriction site mapping of nuclear rDNA. *Mycologia* 86: 96–107.

Hu, S. Y., Y. C. Kong, and P. P. H. But. 1980. *An Enumeration of the Chinese Materia Medica*. Hong Kong: Chinese University Press. Guide to medicinal mushrooms.

Hudler, G. W. 1998. *Magical Mushrooms, Mischievous Molds*. Princeton, New Jersey: Princeton University Press.

Imazeki, R., Y. Otani, T. Hongo, M. Izawa, and N. Mizuno. 1988. *Coloured Illustrations of Mushrooms of Japan*. Tokyo: Yama-kei. Asian field guide (in Japanese).

Iwase, K., T. Ito, H. Fujita, S. Matsui, T. Tanigichi, and A. Obayashi. 1988. Acceleration of fruit-body formation under environmental control in an area with shiro of *Tricholoma matsutake*. *Transactions of the Mycological Society of Japan* 29: 97–105.

Jacab, C. 1993. *Mushrooms and Other Fungi*. Auckland, New Zealand: Pye Anderson. Western field guide (for children).

Japan External Trade Organization (JETRO). 2000a. Japanese Market Report: Mushrooms. Shares of Imports in the Japanese Market. http://www.jetro.go.jp/ec/e/market/jmr/044/1-DE.html#1-D

Japan External Trade Organization (JETRO). 2000b. Japanese Market Report: Mushrooms. Trends in Domestic Production. http://www.jetro.go.jp/ec/e/market/jmr/044/1-B.html

Johnson, P. 1977. Mycorrhizal endogonaceae in a New Zealand forest. *New Phytologist* 78: 161–170.

Johnston, B. 2000. Gold not worth its weight in truffles. *The Daily Telegraph*, 14 November. United Kingdom.

Johnston, P. R., and P. K. Buchanan. 1995. The genus *Psilocybe* (Agaricales) in New Zealand. *New Zealand Journal of Botany* 33: 379–388. Australasian field guide.

Johnston, P. R., and P. K. Buchanan. 1997. Invasive exotic fungi in New Zealand's indigenous forests—you can help. *New Zealand Botanical Society Newsletter* 47: 8–10.

Jones, K. 1995. *Shiitake: The Healing Mushroom*. Rochester, New York: Healing Arts Press. Guide to medicinal mushrooms.

Jordan, M. 1996. Evidence of severe allergic reaction to *Laetiporus sulphureus*. *Mycologist* 9: 157–158.

Jordan, P., and S. Wheeler. 1995. *The Ultimate Mushroom Book*. London: Anness. Western field guide.

Kagan-Zur, V., E. Raveh, S. Lischinsky, and N. Roth-Bejerano. 1994. Initial association between *Helianthemum* and *Terfezia* is enhanced by low iron in the growth medium. *New Phytologist* 127: 567–570. Guide to cultivation of mycorrhizal mushrooms.

Kalotas, A. C. 1997. Aboriginal knowledge and use of fungi. In *Fungi of Australia*. Vol. 1B, Introduction: Fungi in the Environment. Eds. C. Grgurinovic and K. Mallett. Canberra, Australia: Australian Biological Resources Study. Australasian field guide.

Kidcheck. 2002. Mushrooms. *Kidcheck: An Interactive Guide to Children's Health*. http://www.kidcheck.org/wildlife/wildlife3.html

Kirk, P. M., P. F. Cannon, J. C. David, and J. A. Staplers, eds. 2001. *Ainsworth and Bisby's Dictionary of the Fungi*. 9th ed. Wallingford, England: CABI.

Kozikowski, G. R. 1996. Foray report from Skye. *Mycologist* 10: 183–184.

Læssøe, T., and A. Del Conte. 1996. *The Mushroom Book*. London: Dorling Kindersley. Western field guide.

Læssøe, T., and B. Spooner. 1994. The uses of gasteromycetes. *Mycologist* 8: 154–159. Guide to medicinal mushrooms.

Largent, D. L. 1986. *How to Identify Mushrooms to Genus*. Vol. 1, Macroscopic Features. Eureka, California: Mad River Press.

Lawrynowicz, M. 1993. Distributional limits of truffles in Northern Europe. *Micologia e Vegetazione Mediterranea* 7 (1): 31–38.

Lefevre, C., and I. R. Hall. 2001. The global status of truffle cultivation. In *Fifth International Congress on Hazelnuts*, August 2000. Corvallis, Oregon: Acta Horticulturae.

Legg, A. 1990. Your top twenty fungi: the final list. *Mycologist* 4: 23–24.

Lincoff, G. H., and D. H. Mitchel. 1977. *Toxic and Hallucinogenic Mushroom Poisoning: A Handbook for Physicians and Mushroom Hunters*. New York: Van Nostrand Reinhold.

Lincoff, G. H., and C. Nehring. 1995. *The Audubon Society Field Guide to North American Mushrooms*. New York: Alfred A. Knopf.

Luo, X. C., and M. Zang, ed. 1995. The biology and technology of *Lentinula* mushroom. In *Proceedings of the International Symposium on Production and Products of Lentinula Mushroom*. 2 vols. Qingyuan, China: China Agricultural Scientech Press. Guide to cultivation of saprobic mushrooms.

Malajczuk, N., J. M. Trappe, and R. Molina. 1987. Interrelationships among some ectomycorrhizal trees, hypogeous fungi, and small mammals: Western Australia and northwestern American parallels. *Australian Journal of Ecology* 12: 53–55.

Marais, L. J., and J. M. Kotzé. 1977. Notes on ectotrophic mycorrhizae of *Pinus patula* in South Africa. *South African Forestry Journal* 100: 61–71.

Marchand, A. 1971–1986. *Champignons du Nord et du Midi*. 9 vols. Perpignan, France: Société Mycologique des Pyrénées Méditerranéennes. Western field guide.

Maser, C., J. M. Trappe, and R. A. Nussbaum. 1978. Fungal–small mammal interrelationships with emphasis on Oregon coniferous forests. *Ecology* 59: 799–809.

May, T. W., and A. E. Wood. 1997. *Fungi of Australia*. Vol. 2A, Catalogue and Bibliography of Australian Macrofungi. 1. Basidiomycota p.p. Canberra, Australia: Australian Biological Resources Study. Australasian field guide.

Mendaza Rincón De Acuña, R., and G. Díaz Montoya. 1994. *Las Setas en la Naturaleza*. Madrid: Iberdrola. Western field guide.

Miller, O. K., Jr. 1981. *Mushrooms of North America*. New York: Chanticleer Press.

Miller, O. K., Jr., and D. F. Farr. 1975. *An Index of the Common Fungi of North America: Synonymy and Common Names*. Bibliotheca Mycologica 44. Vaduz, Germany: J. Cramer.

Ministry of Agriculture and Fisheries. 1945. *Edible and Poisonous Fungi*. Bulletin 23. London: Her Majesty's Stationery Office.

Mirabella, A., F. Primavera, and L. Gardin. 1992. Formation dynamics and characterization of clay minerals in a natural truffle bed of *Tuber magnatum* Pico on Pliocene sediments in Tuscany. *Agricoltura Mediterranea* 122: 275–281. Guide to cultivation of mycorrhizal mushrooms.

Mischiati, P., and A. Fontana. 1993. In vitro culture of *Tuber magnatum* isolated from mycorrhizae. *Mycological Research* 97: 40–44. Guide to cultivation of mycorrhizal mushrooms.

Mizuno, T., ed. 1995. Mushrooms: the versatile fungus—food and medicinal properties. *Food Reviews International* 11 (1): 1–236. Guide to medicinal mushrooms.

Monnier, G, and R. Courtecuisse. 1993. *Guide de Poche des Champignons*. Lausanne, Switzerland: Delachaux et Niestle. Western field guide.

Montecchi, A., and G. Lazzari. 1993. *Atlante Fotografico di Funghi Ipogei*. Vicenza, Italy: Associazione Micologica Bresadola, Centro Studi Micologici. Western field guide.

Mycology section. 1988. *Poisonous Mushrooms*. Mycology Section of the Institute of Microbiology, Academia Sinica. Beijing: Science Publishing House. Asian field guide (in Chinese).

Mycorrhiza Information Exchange. 2002. http://mycorrhiza.ag.utk.edu/

National Agricultural Statistics Service (NASS). 2000. Mushrooms: record high levels continue for volume and value of sales of all mushrooms. U.S. Department of Agriculture, Washington, D.C., 18 August. http://usda.mannlib.cornell.edu/reports/nassr/other/zmu-bb/mush0800.txt

Neuhaus, V., and K. Neuhaus. 1947. *Pilze*. Iserlohn, Germany: Holzwarth-Verlag.

Nicholls, D. W., B. E. B. Hyne, and P. Buchanan. 1995. Death cap mushroom poisoning. *New Zealand Medical Journal*, 14 June.

Oei, P. 1996. *Mushroom Cultivation with Special Emphasis on Appropriate Techniques for Developing Countries*. Leiden, Netherlands: Tool Publications. Guide to cultivation of saprobic mushrooms.

Ogawa, M. 1977. Microbial ecology of shiro in *Tricholoma matsutake* (Ito et Imai) Sing. and its allied species. V. *Tricholoma matsutake* in *Tsuga sieboldii* forests. *Transactions of the Mycological Society of Japan* 18: 34–46. (In Japanese)

Ogawa, M., and S. Ito. 1989. *Is It Possible to Cultivate Matsutake?* Tokyo: Sou Shin Press. (In Japanese)

Ohara, A., and M. Hamada. 1967. Disappearance of bacteria from the zone of active mycorrhizas in *Tricholoma matsutake* (S. Ito et Imai) Singer. *Nature* 217: 528–29.

Ohenoja, E., and S. Lahti. 1978. Food from the Finnish forests. In *Proceedings of the Eighth World Forestry Congress, 16–28 October 1978*. Vol. 3, Forestry for Food. Jakarta. 1013–1021.

Ohta, A. 1994. Production of fruit-bodies of a mycorrhizal fungus, *Lyophyllum shimeji*, in pure culture. *Mycoscience* 35: 147–151.

Olivier, J. M. 2000. Progress in the cultivation of truffles. In *Mushroom Science XV: Science and Cultivation of Edible Fungi*. Vol. 2. Ed. L. J. L. D. Van Griensven. Rotterdam, Netherlands: Balkema. 937–942.

Olivier, J. M., J. C. Savignac, and P. Sourzat. 1996. *Truffe et Trufficulture*. Perigueux, France: Fanlac. Guide to cultivation of mycorrhizal mushrooms.

Ortega, A., J. Piqueras, and P. Amate. 1996. *Setas: Identificatión, Toxicidad, Gastromicología*. Granada, Spain: Proyecto Sur. Western field guide.

Oss, O. T., and O. N. Oeric. 1976. *Psilocybin: Magic Mushroom Growers' Guide*. Berkeley, California: And/Or Press. Western field guide.

Ower, G. L. 1988. Cultivation of *Morchella*. U.S. patent number 4866878.

Pacioni, G., and O. Comandini. 2000. *Tuber*. In *Ectomycorrhizal Fungi: Key Genera in Profile*. Eds. J. W. G. Cairney and S. M. Chambers. New York: Springer-Verlag. 163–186.

Palm, M. E., and I. H. Chapela, eds. 1997. *Mycology in Sustainable Development: Expanding Concepts, Vanishing Borders*. Boone, North Carolina: Parkway.

Pegler, D. N. 2000. Useful fungi of the world: some uses of bracket fungi. *Mycologist* 14: 6–7. Guide to medicinal mushrooms.

Pegler, D. N., T. Læssøe, and B. M. Spooner. 1995. *British Puffballs, Earthstars, and Stinkhorns*. Kew, England: Royal Botanic Gardens. Western field guide.

Pegler, D. N., and B. M. Spooner. 1997. *The Mushroom Identifier*. London: Grange. Western field guide.

Pegler, D. N., B. M. Spooner, and T. W. K. Young. 1993. *British Truffles: A Revision of British Hypogeous Fungi*. Kew, England: Royal Botanic Gardens. Western field guide.

Penn State Mushroom Laboratory. 2002. http://mushroomspawn.cas.psu.edu/

Percudani, R., A. Zambonelli, and S. Ottonello. 1996. Computer-assisted recognition of truffles. Abstracts of the First International Conference on Mycorrhizae, 4–9 August: 96. University of California, Berkeley.

Phillips, R. 1981. *Mushrooms and Other Fungi of Great Britain and Europe*. London: Pan. Western field guide.

Phillips, R. 1991. *Mushrooms of North America*. Boston: Little, Brown. Western field guide.

Picart, F. 1980. *Truffle: The Black Diamond*. Santa Rosa, California: Agri-Truffe.

Pilz, D., J. Smith, M. P. Amaranthus, S. Alexander, R. Molina, and D. Luoma. 1999. Mushrooms and timber: managing commercial harvesting in the Oregon Cascades. *Journal of Forestry* 97 (3) 4–11.

Pirazzi, R. 1990. Micorrizazione artificiale con miceli isolati "in vitro" di *Tuber melanosporum* Vitt. e *T. magnatum* Pico. In *Atti del Secondo Congresso Internazionale sul Tartufo, 24–27 Novembre 1988*. Eds. M. Bencivenga and B. Granetti. Spoleto, Italy. 173–190. Guide to cultivation of mycorrhizal mushrooms.

Poitou, N., M. Mamoun, M. Ducamp, J. Guinberteau, and J. M. Olivier. 1989. Mycorrhization controlée et culture expérimentale du champ de *Boletus* (=*Suillus*) *granulatus* et *Lactarius deliciosus*. In *Proceedings of the Twelfth International Congress on the Science and Cultivation of Edible Fungi, 1987*. Brunswick, Germany. 551–563. Guide to cultivation of mycorrhizal mushrooms.

Primavera, F. 1995. La coltivazione del tartufo "secondo natura." *Terra e Vita* 45: 57–59.

Przybylowicz, P., and J. Donoghue. 1988. *Shiitake Growers' Handbook*. Dubuque, Iowa: Kendall/Hunt.

Quack, W., T. Anke, F. Oberwinkler, B. M. Giannetti, and W. Steglich. 1978. Antibiotics from basidiomycetes, 5. Merulidial, a new antibiotic from the basidiomycete *Merulius tremellosus* Fr. *Journal of Antibiotics* 31: 737–741.

Rammeloo, J., and R. Walleyn. 1993. *Scripta Botanica Belgica*. Vol. 5, The Edible Fungi of Africa South of the Sahara: A Literature Survey. Meise: National Botanic Garden of Belgium.

Reddish, D. 1995. Delicious radiata! *New Zealand Pine International* (January–February): 27.

Redecker, D., R. Kodner, and L. E. Graham. 2000. Glomalean fungi from the Ordovician. *Science* 289: 1920–1921.

Reid, D. A. 1980. A monograph of the Australian species of *Amanita* Pers. ex Hook. (Fungi). *Australian Journal of Botany, Supplementary Series* 8: 1–96. Australasian field guide.

Renaud, Y. 1989. Controle des champignons sauvages effectué au Marché Central, rapport d'activité. Service des Marchés, Ville de Nancy, France.

Reyna Domenech, S. 1992. *La Trufa*. Madrid: Agrogías mundi-prensa. Guide to cultivation of mycorrhizal mushrooms.

Reynolds, J. E. F., and K. Parfitt. 1996. *Martindale: The Extra Pharmacopoeia*. London: Royal Pharmaceutical Society.

Riley, M. 1988. *Maori Vegetable Cooking*. Paraparaumu, New Zealand: Viking Sevenseas.

Riley, M. 1994. *Maori Healing and Herbal*. Paraparaumu, New Zealand: Viking Sevenseas.

Riousset, G., G. Chevalier, and M. C. Bardet. 2001. *Truffes d'Europe et de Chine*. Paris: CTIFL/INRA. Western field guide.

Rowe, R. F. 1997. The commercial harvesting of wild edible mushrooms in the United States. *Mycologist* 11: 10–15.

Samuels, C. B. 2002. *Discover Mushrooms*. Computer database. www.mushroom.cc/discover.htm

Sanders, R. 2000. New fossil find pushes age of terrestrial fungi back 60 million years, to the same era when green plants pulled themselves onto land. *Campus News*, 14 September. University of California, Berkeley. http://www.berkeley.edu/news/media/releases/2000/09/14_funghi.html

Scates, K. 1995. *Diagnosis and Treatment of Mushroom Poisoning on the Basis of Symptoms and Mushrooms*. Portland, Oregon: Fungal Cave Books. Wall chart.

Schlosser, W. E., and K. A. Blatner. 1995. The wild edible mushroom industry of Washington, Oregon, and Idaho. *Journal of Forestry* (March): 31–36.

Scrase, R. 1996. Cultivating mushrooms: making composted and non-composted substrates. *Mycologist* 10: 52–55. Guide to cultivation of saprobic mushrooms.

Segedin, B. P. 1987. An annotated checklist of agarics and boleti recorded from New Zealand. *New Zealand Journal of Botany* 25: 185–215.

Segedin, B. P., and S. R. Pennycook. 2001. A nomenclatural checklist of agarics, boletes, and related secotioid and gasteromycetous

down and slowly lower your arms to the sides, leading with the heels of the hands. **Smile** and inhale a **shiny spring green mist**, illuminating the liver and gall bladder. Bring your hands back to rest on the liver's aura. Close your eyes and smile into your liver. With each inbreath, breathe fresh Chi into your liver and gall bladder and mentally make the Liver Sound with each outbreath.

Repeat at least three times, as with the previous sound. Repeat six, nine, twelve or twenty four times to alleviate extreme anger, to relieve red or watery eyes, to remove a sour or bitter taste in the mouth or to detoxify the liver.

Heart Sound



Element: Fire
Associated Organ: Small Intestine
Sound: HAAAAAAAW
Emotions: Negative - Arrogance, Harshness, Cruelty, Hatred
Positive - Joy, Honor, Respect, Love, Happiness
Color: Red
Season: Summer
Direction: South

Position: Let both hands rest on the heart. **Smile** to your heart and be aware of any arrogance, haughtiness, hatred, giddiness, cruelty or hastiness. Slowly begin to inhale a deep breath as you extend your arms up from the sides with your palms up, as you did with the Liver Sound. Continue to raise them over your head. Interlace your fingers together and turn your clasped hands over to face the sky, palms up. Push out through the heels of the palms and extend the arms up, keeping the shoulders relaxed. Bend a little to the right and stretch your left arm slightly to gently open the area of your heart.

Sound: Keep your eyes soft and relaxed, looking up through your hands. Slowly exhale, making the sound, "HAAAAAAAW" sub-vocally. Feel that you are releasing any trapped heat, negative emotions, illness and imbalances from your heart and that these are riding out of the body on your breath.

Resting Posture: Once you have fully exhaled, close your eyes, separate your hands, turn the palms down and slowly lower your arms to the sides, leading with the heels of the hands. As you move inhale a **bright red mist** into the heart and small intestines. Bring your hands back to rest on your heart's aura . Smile into your heart. With each inbreath, breathe fresh Chi into your heart with each outbreath mentally repeat the heart sound.

fungi recorded from New Zealand. *New Zealand Journal of Botany* 39: 285–348.

Shepherd, C. J., and C. J. Totterdell. 1988. *Mushrooms and Toadstools of Australia*. Melbourne, Australia: Inkata Press. Australasian field guide.

Simons, D. M. 1987. Poisonous mushrooms. In *Food and Beverage Mycology*. Ed. L. R. Beuchat. New York: AVI. 391–433. Western field guide.

Singer, R. 1986. *The Agaricales in Modern Taxonomy*. 4th ed. Koenigstein, Germany: Koeltz Scientific Books. Western field guide.

Slater, N. 2000. Down to earth. *The Observer*, 10 September. London.

Smith, R. F. 1990. *Microscopy and Photomicroscopy: A Working Tool*. Boston: CRC Press.

Smith, S. E., and D. J. Read. 1997. *Mycorrhizal Symbiosis*. London: Academic Press.

Sourzat, P. 1994. *Guide pratique de trufficulture*. Station d'experimentations sur la truffe. Lycée professionnel agricole Cahors-Le Montat, Le Montat.

Southcott, R. V. 1974. Notes on some poisonings and other clinical effects following ingestion of Australian fungi. *South Australian Clinics* 6: 441–478.

Southcott, R. V. 1997. Mechanisms of macrofungal poisoning in humans. In *Fungi of Australia*. Vol. 1B, Introduction: Fungi in the Environment. Eds. C. Grgurinovic and K. Mallett. Canberra, Australia: Australian Biological Resources Study. 297–313. Australasian field guide.

Spoerke, D. G., and B. H. Rumack, eds. 1994. *Handbook of Mushroom Poisoning: Diagnosis and Treatment*. Boca Raton, Florida: CRC Press.

Stamets, P. 1993. Cultivating morels. *Mushroom: The Journal of Wild Mushrooming* 11 (4): 9–15.

Stamets, P. 1996. *Psilocybin Mushrooms of the World: An Identification Guide*. Berkeley, California: Ten Speed Press.

Stamets, P. 2000. *Growing Gourmet and Medicinal Mushrooms*. Berkeley, California: Ten Speed Press. Guide to cultivation of saprobic mushrooms.

States, J. S. 1990. *Mushrooms and truffles of the Southwest*. Tucson, Arizona: University of Arizona Press. Western field guide.

Stephenson, S. L., and H. Stempen. 1994. *Myxomycetes: A Handbook of Slime Molds*. Portland, Oregon: Timber Press.

Stevenson, G. 1994. *New Zealand Fungi: An Illustrated Guide*. Christchurch, New Zealand: Canterbury University Press. Australasian field guide.

Sun, W. S., and J. Y. Xu. 1999. Cultivation of edible fungi has become one of the backbone industries in the rural economy of China. *Edible Fungi of China* 18 (2): 5–6.

Taylor, M. 1983. Some common fungi of Auckland city. *Tane* 29: 133–142. Australasian field guide.

Taylor, M. 1991. *Mushrooms and Toadstools*. Wellington, New Zealand: Reed. Australasian field guide.

Thomas, M. G., and D. R. Schumann. 1993. Income opportunities in special forest products: self-help suggestions for rural entrepreneurs. Agriculture Information Bulletin 666. Washington, D.C.: United States Department of Agriculture.

Thomson, D. J., and S. Bradbury. 1987. *An Introduction to Photomicrography*. Oxford: Oxford University Press.

Tocci, A, G. Gregori, and G. Chevalier. 1985. Produzione di piantine tartufigene (*Tuber magnatum* Pico) sinitesi micorrizica col sistema dell' "innesta" radicale. *L'Italia Forestale e Montana* 3: 143–152. Guide to cultivation of mycorrhizal mushrooms.

Toleman, E. E. 1985. *Mushrooms*. Information Services Aglink. 4 vols, HPP 317–320. Wellington, New Zealand: Ministry of Agriculture and Fisheries. Guide to cultivation of saprobic mushrooms.

Tominaga, Y. 1975. Studies on the tunnel cultivation, the so-called Hiroshima method of *Tricholoma matsutake* (Ito et Imai) Sing., I: On the forcing culture of *Tricholoma matsutake* in the year 1974. Bulletin of the Hiroshima Agricultural College 5: 165–80. (In Japanese)

Tominaga, Y., and S. Komeyama. 1987. *Practice of Matsutake Cultivation*. Tokyo: Youken. (In Japanese)

Trappe, J. M. 1979. The orders, families, and genera of hypogeous Ascomycotina (truffles and their relatives). *Mycotaxon* 9: 297–340.

Ueda, T., M. Uchida, S. Oogi, S. Miyauchi, and Y. Yamada. 1992. The best 100 wild mushrooms. Kinoko 1. *Yume Shizen* (September): 35–67. Asian field guide (in Japanese).

Urbani, G. 1995. La tartuficoltura razionale: analisi di un investimento. *L'informatore Agrario* 31: 29–32.

Van der Westhuizen, G. C. A. 1983. Mushrooms and toadstools: a guide to the common edible, inedible, and poisonous South African species. South African Department of Agriculture Bulletin 396.

Van Griensven, L. J. L. D., ed. 2000. Science and cultivation of edible fungi. In *Proceedings of the Fifteenth International Congress, Maastricht, Netherlands, 15–19 May 2000*. Rotterdam, Netherlands: A. A. Balkema. Guide to cultivation of saprobic mushrooms.

Vitroplant. 1994. Propone piante di qualità con micorrizazione garantita. Gambettola, Italy: Vitroplant. Guide to cultivation of mycorrhizal mushrooms.

Walleyn, R., and J. Rammeloo. 1994. *Scripta Botanica Belgica*. Vol. 10, The Poisonous and Useful Fungi of Africa South of the Sahara: A Literature Survey. Meise: National Botanic Garden of Belgium.

Wang, Y. 1995. *Tricholoma matsutake*. Ph.D. Thesis, University of Otago, Dunedin, New Zealand. Guide to cultivation of mycorrhizal mushrooms.

Wang, Y., I. R. Hall, and L. Evans. 1997. Ectomycorrhizal fungi with edible fruiting bodies. 1. *Tricholoma matsutake* and allied fungi. *Economic Botany* 51: 311–327. Guide to cultivation and ecology of mycorrhizal mushrooms.

Wang, Y., I. R. Hall, L. Sinclair, and A. L. J. Cole. 1995. *Botetus edulis* sensu lato: a new record for New Zealand. *New Zealand Journal of Crop and Horticultural Science* 23: 227–231.

Wasser, S. P., and A. L. Weis. 1999. Medicinal properties of substances occurring in higher basidiomycetes: current perspectives (review). *International Journal of Medicinal Mushrooms* 1: 31–62. Guide to medicinal mushrooms.

Wood, T. G., and R. J. Thomas. 1989. The mutualistic association between Macrotermitinae and *Termitomyces*. In *Insect-Fungus Interactions*. Eds. N. Wilding, N. M. Collins, P. M. Hammond, and J. F. Webber. London: Academic Press. 69–92.

Wuest, P. J., D. Levanon, and Y. Hadar, eds. 1994. Spent mushroom substrate symposium 1994. In *Proceedings of the Spent Mushroom Substrate Symposium*. Philadelphia.

Wuest, P. J., D. J. Royce, and R. B. Beelman, eds. 1987. Cultivating edible fungi. Developments in crop science 10. In *Proceedings of the International Symposium on Science and Technical Aspects of Cultivating Edible Fungi*. Amsterdam: Elsevier Science. Guide to cultivation of saprobic mushrooms.

Ying, J. Z., X. L. Mao, Q. M. Ma, L. W. Yu, and Y. C. Zong. 1988. *Edible Mushrooms*. Beijing: Science Publishing House. Asian field guide (in Chinese).

Ying, J. Z., X. L. Mao, Q. M. Ma, Y. C. Zong, and H. A. Wen. 1987. *Icones of Medicinal Fungi from China*. Beijing: Science Press. Guide to medicinal mushrooms.

Young, T. 1982. *Common Australian Fungi*. Kensington, Australia: New South Wales University Press. Australasian field guide.

Zambonelli, A., and R. Di Munno. 1992. Indagine sulla possibilità di diffusione dei rimboschimenti con specie tartufigene: aspetti tecnico-colturali ed economici. Ministero dell'Agricoltura e delle Foreste. Citta di Castello, Italy.

Zambonelli, A., G. Govi, and A. Previati. 1989. Micorrizazione in vitro di piantine micropropagate di *Populus alba* con micelio di *Tuber albidum* in coltura pura. *Micologia Italiana* 3: 105–111. Guide to cultivation of mycorrhizal mushrooms.

Zuccherelli, G. 1988. Prime esperienze sulla produzione di piante forestali micorrizate con *Boletus edulis*. *Monti e Boschi* 39: 11–14. Guide to cultivation of mycorrhizal mushrooms.

ABOUT THE AUTHORS

Photo by Jack Squires.

Ian Hall was awarded a Ph.D. in botany (mycology) from Otago University, New Zealand, for his research on the effects of vesicular-arbuscular mycorrhizas on native plants, carried out under the direction of Professor Geoff Baylis. He has worked at Illinois University with Dr. Jim Gerdemann and at the Ministry of Agriculture and Fisheries at Invermay Agricultural Centre near Dunedin, where he studied the pathology of grasses oversown into native grasslands and the beneficial effects of vesicular-arbuscular mycorrhizas on pasture species. In 1985 he shifted his attention to ectomycorrhizal fungi and some of the edible mushrooms they produce. He is now a scientist with Crop and Food Research at Invermay, specializing in edible mushrooms and mycorrhizas.

Photo by Barbara Stephenson.

Steve Stephenson received a Ph.D. in botany (plant ecology) from Virginia Polytechnic Institute and State University in the United States. He is a professor of biology at Fairmont State College, West Virginia, and author of *Myxomycetes: A Handbook of Slime Molds*. He has collected and studied mushrooms and other fungi on six continents, from the tropics to the polar regions of both hemispheres.

Photo by Martin Heffer.

Peter Buchanan was awarded a Ph.D. in fungal taxonomy from the University of Auckland, New Zealand. He has worked as a mycologist at the Mt. Albert Research Centre, Auckland, since 1977. His early research focused on microfungi of grasses but has since extended to wood-decay fungi, especially the identification, classification, and ecology of polypores. Publications include taxonomic treatments of polypores, corticioid (crust) fungi, and mushrooms. A research interest in the cultivation of edible and medicinal mushrooms has led to several trips to Asia to study mushroom cultivation and to trials in Auckland to grow new kinds of mushrooms for New Zealand consumers.

Photo by Jack Squires.

Wang Yun earned degrees from Northwest Agricultural University and Academia Sinica in China and received a Ph.D. in botany (mycology) from Otago University in New Zealand. He has worked as a scientist at the Forestry Sciences Laboratory in Corvallis, Oregon, and as professor and director of the Department of Botany at the Institute of Applied Ecology, Academia Sinica. Since 1990 he has worked as a mycologist at Invermay Agricultural Centre, specializing in the beneficial effects of ectomycorrhizas, edible mushrooms, and silviculture.



Photo by M. J. Walters.

Tony Cole received an M.S. in mycology from the University of Nottingham, England, and a Ph.D. in plant pathology from the University of London. After spending one year at Cornell University as a research associate, he returned to England in 1968 as a lecturer in microbiology at the University of Hull. Since 1973 he has been at the University of Canterbury. His teaching and research interests are mainly mycological, with a special interest in biologically active compounds from fungi.

INDEX

Numbers in bold refer to figures.

abalone mushroom. See *Pleurotus abalonus*, *P. cystidiosus*
admirable bolete. See *Boletus mirabilis*
Agaricus, 45, 101, 103, 114, 183, 196
Agaricus arvensis Schaeff., 103, 161, **195**, **196**, 316
Agaricus augustus Fr., 306
Agaricus aurantioviolaceus R. Heim, 196
Agaricus bernardii Quél., 304
Agaricus bisporus (J. E. Lange) Imbach, 16, 18, 19, 22, 23, 25, 30, 31, **32**, 33–35, 37, **38**, **98**, **99**, 113, 235
Agaricus bitorquis (Quél.) Sacc., 18, 19, 22, 23 25 30, 31, 33, 113, 305
Agaricus blazei Murrill, 19, 66, 304
Agaricus campestris L.: Fr., 103, 161, 195, 196, **197**, 312
Agaricus hondensis Murrill, 110
Agaricus macrosporus (F. H. Møller et Jul. Schaeff.) Pilát, 305
Agaricus pilatianus Bohus, 196
Agaricus placomyces Peck, 110
Agaricus praeclaresquamosus A. E. Freeman, 110
Agaricus sylvaticus Schaeff., 311
Agaricus sylvicola (Vittad.) Peck, 303
Agaricus xanthoderma Genev., 103, 110, 196, **197**
Agrocybe, 66, 101, 183
Agrocybe cylindracea (DC.) Maire, 317
Agrocybe parasitica G. Stev., **184**, 310
Agrocybe praecox (Pers.: Fr.) Fayod, 183, 314
Albatrellus confluens (Alb. et Schwein.: Fr.) Kotl. et Pouzar, 304
Aleuria, 102
Aleuria aurantia (Pers.: Fr.) Fuckel, 293, **294**, 308
almond portobello. See *Agaricus blazei*
Amanita, 20, 96, 98, 101, 103, 104, 105, 114, 124, 134, 135, 137, 141, 156, 182, 205, 262, 273
Amanita abrupta Peck, 137
Amanita bisporigera G. F. Atk., 107
Amanita brunnescens G. F. Atk., 111
Amanita caesarea (Scop.: Fr.) Pers., 80, 81, 92, 98, 124, **125**, 128, 166, 305
Amanita chlorinosma (Austin) Lloyd, 111
Amanita citrina (Schaeff.) Pers., 98, 124, 125, **127**
Amanita cothurnata G. F. Atk., 110

Amanita crenulata Peck, 110
Amanita excelsa (Fr.: Fr.) P. Kumm., 133, **134**, 135
Amanita flavoconia G. F. Atk., 111
Amanita flavorubescens G. F. Atk., 111
Amanita frostiana (Peck) Sacc., 111
Amanita fulva (Schaeff.) Fr., 305
Amanita gemmata (Fr.) Gillet, 110
Amanita hemibapha (Berk. et Broome) Sacc., 124, **126**, 308
Amanita jacksonii Pomerl., 124
Amanita muscaria (L.: Fr.) Lam., 20, 98, 103, 110, 124, **128**, **129**, 130, 131
Amanita pantherina (DC.: Fr.) Secr., 103, 110, 124, **132**, 133, 135
Amanita parcivolvata (Peck) J. E. Gilbert, 111
Amanita phalloides (Fr.) Link, 23, 98, 104, 107, 121, **130**, **131**, 132, 133, 273
Amanita regalis (Fr.) Michael, 110
Amanita rubescens Pers.: Fr., 113, **133**, 135, 317
Amanita solitaria (Bull.: Fr.) Secr., 110
Amanita vaginata (Bull.: Fr.) Lam., **136**, 137, 309
Amanita verna (Bull.: Fr.) Pers., 107
Amanita virosa (Fr.) Bertillon, 23, 104, 107, 124, **135**
amethyst laccaria. See *Laccaria amethystea*
angel's wings. See *Pleurocybella porrigens*
anise-scented clitocybe. See *Clitocybe odora*
Armillaria, 101
Armillaria mellea (Vahl: Fr.) P. Kumm., 29, 103, 111, 113, 137, **138**, **139**, 186, 211, 317
Armillaria novaezelandiae (G. Stev.) Herink, **140**, 315
Armillaria tabescens (Scop.) Emel, 140, 306
aromatic milky. See *Lactarius camphoratus*
Aseroe, 102
Aseroe rubra Labill., **291**, 293
ashy tricholoma. See *Lyophyllum fumosum*
Asiatic truffle. See *Tuber himalayense*, *T. indicum*, *T. sinense*
Auricularia, 23, 30, 55–57, 102, 260
Auricularia auricula (Pers.: Fr.) Fuckel., 19, 55, 56, 312
Auricularia fuscosuccinea (Mont.) Henn., 313
Auricularia polytricha (Mont.) Sacc., 18, 19, 55, **56**, **261**, 262, 311
Austroboletus, 101
Austroboletus betula (Schwein.) E. Horak, **221**, 308
autumn chanterelle. See *Cantharellus tubaeformis*

bagnoli truffle. See *Tuber mesentericum*
bakamatsutake. See *Tricholoma bakamatsutake*

bamboo mushroom. See *Dictyophora indusiata*
Bankera fuligineoalba (J. C. Schmidt: Fr.) Coker et Beers ex Pouzar, 305
basket fungus. See *Ileodictyon cibarium*
bay bolete. See *Xerocomus badius*
beech strawberry. See *Cyttaria gunnii*
beechwood sickener. See *Russula mairei*
beefsteak fungus. See *Fistulina hepatica*
bianchetto. See *Tuber borchii*
big laughing gym. See *Gymnopilus junonius*
birch bolete. See *Leccinum*
bird's nest fungus. See *Crucibulum laeve*, *Cyathus striatus*
bitter bolete. See *Tylopilus felleus*
black jelly fungus. See *Auricularia fuscosuccinea*
black morel. See *Morchella conica*, *M. conica* var. *deliciosa*, *M. elata*, *M. semilibera*
black-veined false truffle. See *Melanogaster ambiguus*, *M. variegatus*
bleeding mycena. See *Mycena haematopus*
blue-green stropharia. See *Stropharia aeruginosa*
blue russula. See *Russula cyanoxantha*
bluing bolete. See *Gyroporus cyanescens*
blusher, the. See *Amanita rubescens*
bolete. See *Boletus*
Boletellus russellii (Frost) J. E. Gilbert, 311
Boletus, 19, 101, 225, 235
Boletus aereus Bull.: Fr., 222, 314
Boletus aestivalis (Paulet) Fr., 222, 311
Boletus calopus Pers.: Fr., 225
Boletus edulis Bull.: Fr., 20, 22, 24, 29, 80–81, 92, 103, 113, 121, 217, **222–224**, 227, 234, 311
Boletus erythropus (Fr.: Fr.) Krombh., 111
Boletus haematinus Halling, 111, 225
Boletus legaliae Pilát, 225
Boletus luridus Schaeff.: Fr., 111, 113, 225
Boletus mirabilis Murrill, 313
Boletus ornatipes Peck, 305
Boletus pallidus Frost, 314
Boletus pinicola (Vittad.) A. Venturi, 222, 314
Boletus pseudosensibilis A. H. Sm. et Thiers, **226**, 227
Boletus pulcherrimus Thiers et Halling, 108, 111, 225
Boletus pulverulentus Opat., 225
Boletus purpureus Fr., 225
Boletus regius Krombh., 314
Boletus reticulatus Schaeff., 222, 314
Boletus rhodoxanthus Schwein., 225
Boletus satanas Lenz, 225
Boletus satanoides Smotl., 225
Boletus sensibilis Peck, 111, 225

Boletus speciosus Frost, 309

Boletus subvelutipes Peck, **225**, 226

Boletus variipes Peck, 314

Boletus violaceofuscus W. F. Chiu, 317

Bondarzewia berkeleyi (Fr.) Bondartsev et Singer, 111

bootlace mushroom. See *Armillaria novaezelandiae*

Bovista, 102, 103

Bovista nigrescens Pers., 272

Bovista plumbea Pers., **272**

bracelet cortinarius. See *Cortinarius armillatus*

brick caps. See *Naematoloma sublateritium*

brown birch bolete. See *Leccinum scabrum*

brown-ribbed elfin cup. See *Helvella acetabulum*

brown roll rim. See *Paxillus involutus*

Burgundy truffle. See *Tuber uncinatum*

burnt tricholoma. See *Tricholoma ustale*

butter bolete. See *Boletinus regius*

button mushroom. See *Agaricus bisporus*, *A. bitorquis*

Caesar's mushroom. See *Amanita caesarea*, *A. jacksonii*

California truffle. See *Tuber californicum*

Calocybe, 101

Calocybe gambosa (Fr.: Fr.) Singer, 140, **141**, 315

Calvatia, 102, 103, 274

Calvatia caelata (Bull.) Morgan, 306

Calvatia cyathiformis (Bosc) Morgan, **273**, 274, 304

Calvatia excipuliformis (Scop.) Perdeck, **274**

Calvatia gigantea (Batsch: Pers.) Lloyd, 20, 250, 274, **275**, 276, 306

Calvatia lilacina (Mont. et Berk.) Henn., 317

Camarophyllus pratensis (Pers.: Fr.) P. Kumm., 304

canary tricholoma. See *Tricholoma flavovirens*

Cantharellus, 101, 104, 105

Cantharellus cibarius Fr.: Fr., 22, 24, 29, 80, 81, 92, 104, 216, **217**, 310

Cantharellus cinnabarinus (Schwein.: Fr.) Schwein., 308

Cantharellus infundibuliformis (Scop.) Fr., 311

Cantharellus luteocomus H. E. Bigelow, 309

Cantharellus subalbidus A. H. Sm. et Morse, 303

Cantharellus tubaeformis (Bull.: Fr.) Fr., 307

carbon balls. See *Daldinia concentrica*

Catathelasma imperiale (Fr.) Singer, 306

cauliflower fungus. See *Sparassis crispa*

cep. See *Boletus aereus*, *B. pinicola*, *B. reticulatus*

changeable pholiota. See *Kuehneromyces mutabilis*

chanterelle. See *Cantharellus*, *C. cibarius*

Repeat at least three times, as with the previous sound. Repeat six, nine, twelve or twenty four times for the heart and small intestines; feel them balanced. This will alleviate extreme impatience, hastiness, arrogance, nervousness, moodiness, jumpiness, irritability, tongue ulcers, palpitations, sore throat, heart disease, insomnia and detoxify the heart.

Spleen Sound



Element: Earth
Associated Organ: Pancreas, Stomach
Sound: WHOOOOOOO (gutturally from the throat)
Emotions: Negative - Worry, Excess Sympathy, Overthinking
Positive - Fairness, Balance, Equanimity, Justice, Openness
Color: Yellow
Season: Indian Summer
Direction: Center (where you stand, looking out to the Six Directions)

Position: Place your hands on the body covering the spleen, pancreas, and stomach area. Be aware of your spleen and **smile** sincerely into it. Inhale deeply as you move the arms outward in an embrace and aim the fingers up under the left rib cage. Place your fingers of both hands just beneath the sternum and rib cage on the left side.

Sound: Look out, lean into your fingers and gently push your fingertips in. Exhale slowly and make the sound, "WHOOOOOOO," from the depths of your throat. Feel yourself releasing any trapped heat, worry, mental fixations or excess sympathy.

Resting Posture: Once you have fully exhaled, close your eyes, slowly release the hands and extend the arms out embracing the earth; return your hands to the resting position on the spleen's aura. Smile to your spleen, pancreas and stomach. Inhale fresh Chi to your spleen, pancreas and stomach as a brilliant **luminous yellow healing mist** that cleanses and refreshes your organs. Mentally do the Spleen Sound with each outbreath.

Repeat at least three times, as with the previous sound. Repeat six, nine, twelve or twenty four times to alleviate extreme indigestion, heat or cold in the stomach or spleen, worry, nausea, hemorrhoids, fatigue, organ prolapse or loose stools.

chestnut bolete. See *Gyroporus castaneus*
chestnut tongue. See *Fistulina hepatica* var. *antarctica*
chicken of the woods. See *Laetiporus sulphureus*
Chinese caterpillar fungus. See *Cordyceps sinensis*
Chinese truffle. See *Tuber pseudoexcavatum*, *T. sinense*
Chlorophyllum, 101, 156
Chlorophyllum molybdites (G. Mey.: Fr.) Massee, 111, 156, **158**
Choiromyces meandriformis Vittad., 304
Chroogomphus rutilus (Schaeff.: Fr.) O. K. Mill., 311
Chroogomphus tomentosus (Murrill) O. K. Mill., 313
cinnamon truffle. See *Tuber rufum*
Clathrus archeri (Berk.) Dring, 293
Clathrus ruber P. Micheli ex Pers.: Pers., 292
Clavaria, 102, 286
Clavaria purpurea O. F. Müll.: Fr., 317
Claviceps, 286
Claviceps purpurea (Fr.) Tul., 286
Clavulina, 102
Clavulina cavipes Corner, 286, **288**
Clavulina cinerea (Bull.: Fr.) J. Schröt., 309
Clavulina cristata (Holmsk.: Fr.) J. Schröt., **288**, 289, 307
Clavulina rugosa (Bull.) J. Schröt., 286
Clavulinopsis, 286
Clitocybe, 101, 131, 141, **143**, 144, 206
Clitocybe acromelalga Ichimura, 111
Clitocybe aurantiaca (Wulfen) Fr., 108
Clitocybe candicans (Pers.: Fr.) P. Kumm., 108
Clitocybe clavipes (Pers.: Fr.) P. Kumm., 113, 304
Clitocybe dealbata (Sowerby: Fr.) P. Kumm., 108, 141, **142**, 161, 163
Clitocybe dilatata (Pers.) P. Karst., 109
Clitocybe ericetorum (Bull.) Fr., 109
Clitocybe geotropa (Bull. ex DC.) Quél., 141, 313
Clitocybe gibba (Pers.: Fr.) P. Kumm., 109, 141, **142**, 313
Clitocybe maxima Gaertn. et G. Mey., 141, **143**
Clitocybe nebularis (Batsch: Fr.) P. Kumm., 109, 144, 163, 315
Clitocybe odora (Fr.) P. Kumm., 314
Clitocybe phaeophthalma (Pers.) Kuyper, 109
Clitocybe phyllophila (Fr.) P. Kumm., 109
Clitocybe rivulosa (Pers.: Fr.) P. Kumm., 109, 141
Clitocybe robusta Peck, 141
Clitocybe truncicola (Peck) Sacc., 109
Clitocybe prunulus (Scop.: Fr.) P. Kumm., 315
clouded clitocybe. See *Clitocybe nebularis*

club-foot clitocybe. See *Clitocybe clavipes*
Collybia, 101
Collybia acervata (Fr.) P. Kumm., 111
Collybia butyracea (Bull.: Fr.) P. Kumm., 145
Collybia dryophila (Bull.: Fr.) P. Kumm., 111, **144**
comb tooth mushroom. See *Hericium ramosum*
conifer coral tooth mushroom. See *Hericium abietis*
conk. See *Ganoderma*
Conocybe, 106, 206
Conocybe cyanopus (G. F. Atk.) Kühner, 109
Conocybe filaris (Fr.) Kühner, 107
Conocybe rugosa (Peck) Watling, 107
Copelandia cyanescens (Berk. et Broome) Singer, 206
Coprinus, 96, 101, 105
Coprinus africanus Pegler, 113, 198
Coprinus atramentarius (Bull.: Fr.) Fr., 105, 113, **198**, 312
Coprinus cinereus (Schaeff.: Fr.) Gray, 309
Coprinus comatus (Müll.: Fr.) Pers., **19**, **199**, **200**, 250, 311
Coprinus disseminatus (Pers.: Fr.) Gray, 198, **201**, 202, **203**
Coprinus insignis Peck, 113
Coprinus micaceus (Bull.: Fr.) Fr., 113, 310
Coprinus quadrifidus Peck, 113
Coprinus variegatus Peck, 113, 198
coral tooth mushroom. See *Hericium coralloides*
Cordyceps, 102, 283
Cordyceps capitata (Holmsk.) Link, 283
Cordyceps gunnii (Berk.) Berk., 307
Cordyceps hauturu Dingley, 307
Cordyceps hawkesii G. R. Gray, 316
Cordyceps militaris (L.: Fr.) Link, 316
Cordyceps ophioglossoides (Ehrenb.: Fr.) Link, 283, **285**, 306
Cordyceps robertsii (Hook.) Berk., 15, **283**, **284**, 307
Cordyceps sinensis (Berk.) Sacc., 286, 305
Cordyceps sobolifera (Berk.) Berk., 305
corn smut. See *Ustilago maydis*
Cortinarius, 101, 148, 181, 184, **185**, **186**
Cortinarius armillatus (Fr.: Fr.) Fr., 312
Cortinarius cinnamomeus (L.: Fr.) Fr., 111
Cortinarius claricolor (Fr.) Fr. var. *turmalis* (Fr.) M. M. Moser, 309
Cortinarius collinitus (Sowerby: Fr.) Fr., 312
Cortinarius elatior Fr., 307
Cortinarius gentilis (Fr.) Fr., 108
Cortinarius orellanoides Rob. Henry, 108
Cortinarius orellanus Fr., 108, 184

Cortinarius praestans (Corda) Gillet, 316
Cortinarius pseudosalor J. E. Lange, 312
Cortinarius purpurascens (Fr.) Fr., 317
Cortinarius speciosissimus Kühner et Romagn., 108
Cortinarius splendens Rob. Henry, 108
Cortinarius tenuipes (Hongo) Hongo, 315
Cortinarius violaceus (L.: Fr.) Fr., 317
Craterellus, 101
Craterellus cornucopioides (L.: Fr.) Pers., **220**, 310
Craterellus fallax A. H. Sm., 220
crested coral. See *Clavulina cristata*
crown fungus. See *Sarcosphaera crassa*
Crucibulum laeve (Huds.) Kambly, 296
Cudonia circinans (Pers.) Fr., 107
cuitlacoche. See *Ustilago maydis*
cup fungi. See *Peziza*, *Paxina*
Cyathus, 102
Cyathus striatus (Huds.: Pers.) Willd., **296**, 297, 311
Cyttaria, 102, 252
Cyttaria espinosae Lloyd, 253
Cyttaria gunnii Berk., 25, **253**, 304

Daldinia, 102
Daldinia concentrica (Bolton) Ces. et De Not., **282**
dead man's fingers. See *Xylaria polymorpha*
death cap. See *Amanita phalloides*
deceiver, the. See *Laccaria laccata*
deer mushroom. See *Pluteus atricapillus*, *P. cervinus*
Dermocybe sanguinea (Wulfen: Fr.) Wünsche, 111
desert truffle. See *Phaeangium lefebvrei*, *Tirmania africana*, *Terfezia arenaria*, *Terfezia claveryi*
destroying angel. See *Amanita bisporigera*, *A. virosa*
devil's bolete. See *Boletus satanas*
Dictyophora, 102, 247
Dictyophora duplicata (Bosc) E. Fisch., **246**, 247, 306
Dictyophora echinovolvata M. Zang, D. R. Zheng et Z. X. Hu, 305
Dictyophora indusiata (Vent.: Pers.) Desv., 18, 19, 66, 68, 247, 317
dog stinkhorn. See *Mutinus caninus*
dotted-stalk suillus. See *Suillus granulatus*
dryad's saddle. See *Polyporus squamosus*
dung cap, common. See *Peziza vesiculosa*
dye-maker's false puffball. See *Pisolithus tinctorius*

earthball. See *Scleroderma*, *S. albidum*, *S. areolatum*, *S. cepa*, *S. citrinum*, *S. verrucosum* earthstar. See *Geastrum saccatum*

edible russula. See *Russula vesca*

Elaphomyces, 283, **285**

elfin sandle. See *Helvella lacunosa*

enokitake. See *Flammulina velutipes*

Entoloma, 101, 179

Entoloma rhodopolium (Fr.) P. Kumm., 109, 111, **179**, 209

Entoloma sinuatum (Bull.: Fr.) P. Kumm., 111

European matsutake. See *Tricholoma caligatum*

fairy ring mushroom. See *Marasmius oreades*

false chanterelle. See *Hygrophoropsis aurantiaca*

false death cap. See *Amanita citrina*

false morel. See *Gyromitra*, *G. esculenta*, *G. gigas*

false truffle. See *Melanogaster ambiguus*

fat pholiota. See *Pholiota adiposa*

field blewit. See *Lepista personata*

field mushroom. See *Agaricus campestris*

Fistulina, 102

Fistulina hepatica (Schaeff.: Fr.) With., 15, 256, **257**, 307

Fistulina hepatica var. *antarctica* (Speg.) J. E. Wright, 312

Flammulina, 101

Flammulina velutipes (Curtis: Fr.) Singer, 19, 22, 23, 30, 59, **60**, **61**, 62, 65, 104, 145, **146**, 310

fly agaric. See *Amanita muscaria*

Fomitopsis officinalis (Batsch: Fr.) Bondartsev et Singer, 256, 315

forest mushroom. See *Agaricus sylvaticus*

Fuligo, 102

Fuligo septica (L.) F. H. Wigg., 297, **298**

fuling. See *Wolfiporia cocos*

fungus icicles. See *Hericium clathroides*

funnel cap, common. See *Clitocybe gibba*

funnel-shaped chanterelle. See *Cantharellus infundibuliformis*

Fuscoboletinus paluster (Peck) Pomerl., 315

fuzzy truffle. See *Geopora cooperi*

Galerina, 104–107, 186, 206

Galerina autumnalis (Peck) A. H. Sm. et Singer, 186

Galerina fasciculata Hongo, 107, **187**

Galerina marginata (Batsch) Kühner, 107, 186

Galerina mutabilis (Schaeff.: Fr.) P. D. Orton, 186

Galerina sulciceps (Berk.) Boedijn, 107

Galerina unicolor (Vahl: Fr.) Singer, 186

Galerina venenata A. H. Sm., 107

Ganoderma, 19, **71**, 102

Ganoderma lucidum (Curtis) P. Karst., 66, **69**, **70**, 256, 311

Ganoderma tsugae Murrill, 314

Geastrum, 102, 273

Geastrum saccatum Fr., **292**, 293
gem-studded puffball. See *Lycoperdon perlatum*
Geopora cooperi Harkn., 307
giant clitocybe. See *Leucopaxillus giganteus*
giant puffball. See *Calvatia gigantea*, *Langermannia gigantea*
gilled bolete. See *Phylloporus rhodoxanthus*
gilled polypore. See *Lenzites betulina*
Gloeostereum incarnatum S. Ito et S. Imai, 316
golden ear. See *Tremella aurantia*
golden oyster mushroom. See *Pleurotus cornucopiae* var. *citrinopileatus*
golden pholiota. See *Pholiota aurivella*
Gomphus, 101, 114
Gomphus bonari (Morse) Singer, 111
Gomphus clavatus (Pers.: Fr.) Gray, 314
Gomphus floccosus (Schwein.) Singer, 111, **219**
Gomphus fujisanensis (S. Imai) Parmasto, 111
Gomphus kauffmanii (A. H. Sm.) Corner, 111
gray coral. See *Clavulina cinerea*
green oyster mushroom. See *Hohenbuehelia serotina*
green russula. See *Russula aeruginea*, *R. virescens*
Grifola, 102
Grifola frondosa (Dicks.: Fr.) Gray, 19, 22, 30, 66, **71**, 309
Grifola umbellata (Pers.: Fr.) Pilát., 317
grisette. See *Amanita vaginata*
Gymnopilus, 101, 104
Gymnopilus junonius (Fr.: Fr.) P. D. Orton, 109, 186, **187**, 206, 208
gypsy mushroom. See *Rozites caperatus*
Gyromitra, 21, 102, 104, 114, 244, 252
Gyromitra ambigua (P. Karst.) Harmaja, 107
Gyromitra californica (W. Phillips) Raitv., 108
Gyromitra caroliniana (Bosc: Fr.) Fr., 108
Gyromitra esculenta (Pers.) Fr., 105, 108, 113, 242, **244**, 247, 311
Gyromitra fastigiata (Krombh.) Rehm, 108
Gyromitra gigas (Krombh.) Quél., 108
Gyromitra infula (Schaeff.: Fr.) Quél., 105, 108, 244, **245**
Gyromitra korfii (Raitv.) Harmaja, 108
Gyromitra sphaerospora (Peck) Sacc., 108
Gyroporus castaneus (Bull.: Fr.) Quél., 308
Gyroporus cyanescens (Bull.: Fr.) Quél., 310

half-free morel. See *Morchella semilibera*
hatakeshimeji. See *Lyophyllum decastes*
hatsudake. See *Lactarius hatsudake*

haymaker's mushroom. See *Panaeolus foenisecii*
Hebeloma, 101, 188
Hebeloma crustuliniforme (Bull.) Quél., 111, **188**
Hebeloma mesophaeum (Pers.) Quél., 111
Hebeloma sinapizans (Paulet) Gillet, 111, 188
Hebeloma vinosophyllum Hongo, 111
hedgehog mushroom. See *Hydnum repandum*
Helvella, 102, 252, 294
Helvella acetabulum (L.: Fr.) Quél., 294
Helvella crispa (Scop.: Fr.) Fr., **252**
Helvella lacunosa Afzel.: Fr., 252, 311
hemlock polypore. See *Ganoderma tsugae*
hen of the woods. See *Grifola frondosa*
Hericium, 102, 237
Hericium abietis (Weir) K. A. Harrison, 237
Hericium clathroides (Pall.: Fr.) Pers., **239**, 307
Hericium coralloides (Scop.: Fr.) Gray, 237, 316
Hericium erinaceus (Bull.: Fr.) Pers., 19, 30, 66, 237, 308
Hericium ramosum (Bull.) Letell., 237, 309
hoelen. See *Pachyma hoelen*
Hohenbuehelia serotina (Pers.: Fr.) Singer, 315, 316
hollowed truffle. See *Tuber excavatum*
hollow-stalked boletus. See *Suillus cavipes*
honey mushroom. See *Armillaria mellea*
honshimeji. See *Lyophyllum shimeji*
hooded false morel. See *Gyromitra infula*
horn of plenty. See *Craterellus cornucopioides*
horse mushroom. See *Agaricus arvensis*
horsehair mushroom. See *Marasmius rotula*
Hydnum, 101
Hydnum repandum L.: Fr., 236, **237**, 238, 310
Hygrocybe, 101
Hygrocybe coccinea (Schaeff.: Fr.) P. Kumm., 306
Hygrocybe conica (Scop.: Fr.) P. Kumm., 111, 145, **147**
Hygrocybe ovina (Bull.: Fr.) Kühner, 111
Hygrocybe pratensis (Pers.: Fr.) Bon, 161
Hygrophoropsis, 101
Hygrophoropsis aurantiaca (Wulfen: Fr.) Maire, 105, 114, 217, **218**, 219
Hygrophorus arbustivus Fr., 313
Hygrophorus eburneus (Fr.) Fr., 303
Hygrophorus lucorum Kalchbr., 312
Hygrophorus russula (Schaeff.: Fr.) Quél., 308
Hypholoma, 101
Hypholoma fasciculare (Huds.: Fr.) P. Kumm., 104, 107, 111, 202, **203**

Hypomyces, 101
Hypomyces lactifluorum (Schwein.: Fr.) Tul., **178**
Hypoxylon archeri Berk., 64
Hypsizygus marmoreus (Peck) H. E. Bigelow, 19, 22, 30, 66, **67**, 310

Ileodictyon, 102
Ileodictyon cibarium Yul. et C. Tul., 249, **290**, 293, 314
imperial cap. See *Catathelasma imperiale*
Indian truffle. See *Tuber indicum*
indigo milky. See *Lactarius indigo*
ink cap, common. See *Coprinus atramentarius*, *C. micaceus*
Inocybe, 101, 105, 131, 188, **191**, 206
Inocybe bongardii (Weinm.) Quél., 109
Inocybe corydalina Quél., 109
Inocybe dulcamara P. Kumm., 109
Inocybe fastigiata (Schaeff.: Fr.) Quél., 109, 189
Inocybe geophylla (Sowerby: Fr.) P. Kumm., 109, **190**
Inocybe godeyi Gillet, 109
Inocybe griseo-lilacina J. E. Lange, 109
Inocybe hirtella Bres., 109
Inocybe lacera (Fr.: Fr.) P. Kumm., 109
Inocybe maculata Boud., 109
Inocybe napipes J. E. Lange, 109
Inocybe patouillardii Bres., 109, 141, 191
Inocybe praetervisa Quél., 109
Inocybe sororia Kauffman, 109
Italian white truffle. See *Tuber magnatum*
ivory clitocybe. See *Clitocybe dealbata* (Sowerby: Fr.) P. Kumm.
ivory waxy cap. See *Hygrophorus eburneus*
iwatake. See *Umbilicaria esculenta*

jack-o'-lantern. See *Omphalotus illudens*, *O. olearius, O. olivascens*
jagged-stalked bolete. See *Boletellus russellii*
Jersey cow bolete. See *Suillus bovinus*

king oyster mushroom. See *Pleurotus eryngii*
Kuehneromyces mutabilis (Schaeff.: Fr.) Singer et A. H. Sm., 66, 304

Laccaria, 101
Laccaria amethystea Cooke, 148, **149**, 317
Laccaria laccata (Scop.: Fr.) Berk. et Broome, 105, 147, **148**, 313
Laccocephalum, 102
Laccocephalum mylittae (Cooke et Massee) Núñez et Ryvarden, 25, 256, **258**, 311
Lactarius, 101, 113, 114, 148, 153, 156, 178
Lactarius akahatsu Tanaka, 305
Lactarius blennius (Fr.: Fr.) Fr., **155**, 156

Lactarius camphoratus (Fr. : Fr.) Fr., **150**, 151, 153, 312
Lactarius chrysorheus Fr., 111, 153
Lactarius deliciosus (L.: Fr.) Gray, 19, 29, **75**, 77, 80–81, 92, 104–105, 121, **151–152**, 153, 192, 311
Lactarius hatsudake Tanaka, **17**, 153, 308
Lactarius helvus (Fr.: Fr.) Fr., 111
Lactarius indigo (Schwein.: Fr.) Fr., 153, **154**, 310
Lactarius laeticolor (S. Imai) Imaz., 315
Lactarius piperatus (Scop.: Fr.) Pers., 111, 156
Lactarius pubescens (Schrad.) Fr., 112, **155**, 156
Lactarius quietus (Fr.: Fr.) Fr., 316
Lactarius repraesentaneus Britzelm., 112
Lactarius rufus (Scop.: Fr.) Fr., 112
Lactarius sanguifluus (Paulet) Fr., 315
Lactarius scrobiculatus (Scop.: Fr.) Fr., 112
Lactarius torminosus (Schaeff.: Fr.) Gray, 112, 153
Lactarius uvidus (Fr.: Fr.) Fr., 112
Lactarius volemus (Fr.: Fr.) Fr., 306
Lactarius zonarius (Bull.) Fr. sensu Neuhoff, 153, **154**
Laetiporus, 102
Laetiporus sulphureus (Bull.: Fr.) Murrill, 112, 113, **259**, 311
Lampteromyces, 101
Lampteromyces japonicus (Kawam.) Singer, 104, 112, 209, **210**
Langermannia gigantea (Batsch: Pers.) Rostk. See *Calvatia gigantea*
larch bolete. See *Suillus grevillei*
latticed stinkhorn. See *Clathrus ruber*
Leccinum, 101, 222, 230
Leccinum aurantiacum (Bull.) Gray, 228, **229**, 230
Leccinum extremiorientale (Lar. N. Vassiljeva) Singer, 316
Leccinum scabrum (Bull.: Fr.) Gray, **227**, 308
Leccinum versipelle (Fr.) Snell, **228**
Lentinula, 101
Lentinula edodes (Berk.) Pegler, 18–19, 22–23, 30, 38–40, **41**, 42–44, **45**, 46, **47**, 56–57, 64, 209, 315
Lentinus suffrutescens (Brot.: Fr.) Fr., 310
Lenzites, 102
Lenzites betulina (L.: Fr.) Fr., **260**
Lepiota, 101, 106, 114, 156, 176
Lepiota brunneoincarnata Chodat et C. Martin, 107, 156
Lepiota castanea Quél., 107
Lepiota citrophylla (Berk. et Broome) Sacc., 107
Lepiota clypeolaria (Bull.: Fr.) P. Kumm., 112
Lepiota cristata (Bolton: Fr.) P. Kumm., 112, 156, **158**
Lepiota helveola Bres., 107

Lepiota josserandii Bon et Boiffard, 107

Lepiota lutea (Bolton) Quél., 112

Lepiota subincarnata J. E. Lange, 107

Lepista, 101, 179, 181

Lepista caespitosa (Bres.) Singer, 304

Lepista irina (Fr.) H. E. Bigelow, 112, 181, 313

Lepista luscina (Fr.: Fr.) Singer, **180**, 181, 309

Lepista nuda (Bull.: Fr.) Cooke, 113, **180**, 181, 317

Lepista personata (Fr.: Fr.) Cooke, 181, 306

Lepista sordida (Schumach.: Fr.) Singer, 309

Leucopaxillus, 101

Leucopaxillus giganteus (Sibth.: Fr.) Singer, **159**, 310

lion's mane mushroom. See *Hericium erinaceus*

little blues. See *Psilocybe subaeruginosa*

lobster mushroom. See *Hypomyces lactifluorum*

long-stemmed puffball. See *Calvatia excipuliformis*

Lycoperdon, 102

Lycoperdon marginatum Vittad., 109, 276

Lycoperdon mixtecorum R. Heim, 276

Lycoperdon perlatum Pers.: Pers., 276, **277**, 278, 314

Lycoperdon pyriforme Schaeff.: Pers., 276, **277**, 278, 311

Lycophyllum, 101

Lyophyllum connatum (Schumach.: Fr.) Singer, 308

Lyophyllum decastes (Fr.: Fr.) Singer, 308

Lyophyllum fumosum (Pers.: Fr.) P. D. Orton, 309

Lyophyllum shimeji (Kawam.) Hongo, 80, **160**, 316

Lyophyllum sykosporum Hongo et Clémençon, 304

Macrolepiota, 101, 104, 156

Macrolepiota procera (Scop.: Fr.) Singer, 156, **157**, 158, 306

Macrolepiota rachodes (Vittad.) Singer, 156, **157**, 159, 305

maize mushroom. See *Ustilago maydis*

many-colored polypore. See *Trametes versicolor*

Marasmius, 101, 163

Marasmius oreades (Bolton: Fr.) Fr., 144, 145, 160, **161**, 163, 316

Marasmius rotula (Scop.: Fr.) Fr., 163

Marasmius siccus (Schwein.: Fr.) Fr., **162**, 163, 307

matsutake. See *Tricholoma matsutake*

meadow waxy cap. See *Camarophyllus pratensis*

Megacollybia platyphylla (Pers.: Fr.) Kotl. et Pouzar, 112

Melanogaster, 102, 262, 279

Melanogaster ambiguus (Vittad.) Tul. et C. Tul., **278**, 279, 307

Melanogaster variegatus (Vittad.) Tul. et C. Tul., 317

Meripilus giganteus (Pers.) P. Karst., 112
mica cap. See *Coprinus micaceus*
milk-white russula. See *Russula delica*
Morchella, 21, 101, 104, 105, 113, 239, 242, 244, 250, 252
Morchella conica Pers.: Fr., 240, 309
Morchella conica var. *deliciosa* Fr., 309
Morchella costata (Vent.) Pers., 310
Morchella crassipes (Vent.: Fr.) Pers., 305
Morchella elata Fr.: Fr., 240, 242, 307
Morchella esculenta Pers.: Fr., **240**, 242, 315
Morchella esculenta var. *rigida* Krombh., 315
Morchella esculenta var. *rotunda* Pers.: Fr., 315
Morchella esculenta var. *umbrina* (Boud.) S. Imai, 315
Morchella esculenta var. *vulgaris* Pers.: Fr., 315
Morchella semilibera DC.: Fr., 105, **241**, 304
morel. See *Morchella*, *M. conica* var. *deliciosa*, *M. costata*, *M. crassipes*
mousseron. See *Calocybe gambosa*, *Marasmius oreades*
mukitake. See *Hohenbuehelia serotina*
Mutinus, 102
Mutinus caninus (Huds.: Pers.) Fr., 247, **248**, **249**
Mutinus elegans (Mont.) E. Fisch., 249
Mycena, 101, 163, 165, 209
Mycena haematopus (Pers.: Fr.) P. Kumm., 163, **164**
Mycena leaiana (Berk.) Sacc., **164**, 165
Mycena pura (Pers.: Fr.) P. Kumm., 109
Mycoleptodonoides aitchisonii (Berk.) Maas Geest., 305

Naematoloma sublateritium (Fr.) P. Karst., 316
nameko. See *Pholiota nameko*
native bread. See *Laccocephalum mylittae*
netted stinkhorn. See *Dictyophora duplicata*
Nolanea quadrata (Berk. et M. A. Curtis) Sacc., 112
Nolanea verna (S. Lundell) Kotl. et Pouzar, 112
non-inky coprinus. See *Coprinus disseminatus*

octopus stinkhorn. See *Aseroe rubra*, *Clathrus archeri*
old man of the woods. See *Strobilomyces floccopus*
Omphalotus, 101, 209, 211
Omphalotus illudens (Schwein.: Fr.) H. E. Bigelow, 112, 209, 211, **212**
Omphalotus nidiformis (Berk.) O. K. Mill., 104, 112, **211**, 212
Omphalotus olearius (DC.: Fr.) Singer, 104, 112, 209, 211, 212
Omphalotus olivascens H. E. Bigelow, O. K. Mill. et Thiers, 209, 211, 212

Triple Warmer Sound



The Triple Warmer refers to the upper, middle and lower body, and to the distinct metabolic transformations that occur within each area. The Upper Warmer is the area above the diaphragm, where the heart and lungs are located. This area tends to become hot and is responsible for respiration and cardiovascular circulation. The Middle Warmer, the area between the diaphragm and the navel, becomes warm and is where the digestive organs are located. The Lower Warmer, the area below the navel, is responsible for reproduction and elimination and is cool in temperature. The sound "HEEEEEEE" balances the temperatures of the three levels by bringing hot energy down to the lower center and cold energy up to the higher centers.

Position: Lie on your back with your arms resting palms up at your sides. Keep your eyes closed. **Smile**. First breathe into the upper part of your lungs to expand the Upper Warmer; then breathe into the middle of the lungs to expand the Middle Warmer; finally, with the last part of your inhalation, expand your lower lungs and fill the Lower Warmer. Breathing in this way creates more space inside for each organ, helping to release and circulate any internal heat or cold.

Sound: Exhale with the sound "HEEEEEEE" sub-vocally, first flattening your chest, then your solar plexus, and finally your lower abdomen. Feel the dark and cloudy color, cold and chill energy exit from the tips of the fingers.

Resting Posture: Once you have fully exhaled, do not to focus on any emotions or purification process at all. Just let go and relax your body and mind completely.

Repeat at least three times, as with the previous sound. Repeat six, nine, twelve or twenty four times to alleviate insomnia and stress.

When you have completed the Six Healing Sounds just rest, **smile** and do nothing.

Regular daily practice of the Six Healing Sounds will help you to keep in touch with the energetic and emotional state of your internal organs. Most importantly do the sounds in the evening before going to sleep. This will help clear out the negative emotions before sleeping, so you can feel that the night's rest recharges your energy positively. This practice will greatly benefit your personal Cosmic Healing Chi Kung practice. It will help sensitize you to the varieties and differing qualities of Chi. This knowledge will also help you in diagnosing and treating others.

For more details of this practice please see the book "Taoist Ways to Transform Stress Into Vitality", by Mantak Chia.

orange birch bolete. See *Leccinum versipelle*
orange-capped bolete. See *Leccinum aurantiacum*
orange mycena. See *Mycena leaiana*
orange-peel mushroom. See *Aleuria aurantia*
orange pinwheel. See *Marasmius siccus*
Oregon white truffle. See *Tuber gibbosum*
ornate-stalked bolete. See *Boletus ornatipes*
Oudemansiella mucida (Schrad.: Fr.) Höhn., 312
Oudemansiella radicata (Relhan: Fr.) Singer, 305
Oudemansiella venoslamellata (Imazeki et Toki) Imazeki et Hongo, 314
oyster mushroom. See *Pleurotus*, *P. eryngii*, *P. ostreatus*

Pachyma hoelen Rumph. ex Fr.: Fr., 308
paddy straw mushroom. See *Volvariella volvacea*
painted suillus. *See Suillus pictus*
Panaeolus, 101, 103, 209
Panaeolus ater (J. E. Lange) Kühner et Romagn., 109
Panaeolus campanulatus (P. Kumm.) Quél., 109
Panaeolus foenisecii (Pers.: Fr.) Kühner, 109, **204**, 209
Panaeolus papilionaceus (Bull.: Fr.) Quél., 109
Panaeolus retirugis (Fr.) Gillet, 109
Panaeolus sphinctrinus (Fr.) Quél., 109
Panaeolus subbalteatus (Berk et Broome) Sacc., 110
panther cap. See *Amanita pantherina*
parasol mushroom. See *Macrolepiota procera*
Paxillus, 101, 192
Paxillus involutus (Batsch: Fr.) Fr., 104, 105, 108, 112, 113, 191, **192**, 219
Paxina, 21, 102, 294
Paxina leucomelas (Pers.) Kuntze, 294
pear-shaped puffball. See *Lycoperdon pyriforme*
peeling puffball. See *Lycoperdon marginatum*
Périgord black truffle. See *Tuber melanosporum*
Peziza, 21, 102, 294, **295**
Peziza ammophila Durieu et Mont., **295**
Peziza vesiculosa Bull.: Fr., 294
Phaeangium lefebvrei Pat., 312
Phaeolepiota aurea (Matt.: Fr.) Maire, 112, 310
Phaeolus schweinitzii (Fr.) Pat., 112
Phallus, 102
Phallus impudicus L.: Pers., 247, 249, **250**, 307
Phellinus, 256
phoenix mushroom. See *Pleurotus pulmonarius*
Pholiota, 192, 194
Pholiota adiposa (Batsch: Fr.) P. Kumm., 66, **72**, 192, **193**, 306
Pholiota aurivella (Batsch.: Fr.) P. Kumm., 310

Pholiota highlandensis (Peck) A. H. Sm. et Hesler, 194
Pholiota limonella Peck, 194
Pholiota lubrica (Pers.: Fr.) Singer, 307
Pholiota nameko (T. Ito) S. Ito et S. Imai, 19, 22, 23, 30, **65**, **66**, 192, 308
Pholiota squarrosa (Oeder: Fr.) P. Kumm., 112, 113, **194**, 313
Pholiota squarrosoides (Peck) Sacc., 194
Pholiota terrestris Overh., 194
Phylloporus, 101, 230
Phylloporus rhodoxanthus (Schwein.: Fr.) Bres., **230**, 231
Picoa carthusiana Tul., 307
pine mushroom. See *Tricholoma matsutake*
pink coral mushroom. See *Ramaria formosa*
pink oyster mushroom. See *Pleurotus djamor*
Pisolithus tinctorius (P. Micheli ex Pers.: Pers.) Coker et Couch, 304
Pleurocybella porrigens (Pers.: Fr.) Singer, 304
Pleurotus, 19, 23, 30, 47–55, 101, 212
Pleurotus abalonus Y. H. Han, K. M. Chen et S. Ching, 304
Pleurotus cornucopiae (Paulet) Rolland, 304
Pleurotus cornucopiae var. *citrinopileatus* (Singer) Ohira, 19, 47, **213**
Pleurotus cystidiosus O. K. Mill., 312
Pleurotus djamor (Rumph. ex Fr.: Fr.) Boedijn, 47, **49**, 306
Pleurotus eryngii (DC.: Fr.) Quél., 29, 50, 54, **55**, 56, 305
Pleurotus opuntiae (Durieu et Lév.) Sacc., **215**, 303
Pleurotus ostreatus (Jacq.: Fr.) P. Kumm., 22, 29, 31, **52**, 54, 104, 212, **214**, 312
Pleurotus pulmonarius (Fr.: Fr.) Quél., 47, **50**, **51**, 53, 54, 306
Pleurotus sajor-caju (Rumph. ex Fr.: Fr.) Singer, See *Pleurotus pulmonarius*
Pleurotus tuber-regium (Rumph. ex Fr.: Fr.) Singer, 66, 74, 310
Pluteus, 181
Pluteus atricapillus (Batsch) Fayod, **181**, 182, 309
Pluteus cervinus P. Kumm. See *Pluteus atricapillus*
Pluteus cyanopus Quél., 110
Pluteus salicinus (Pers.: Fr.) P. Kumm., 110
Pluteus villosus (Bull.) Quél., 110
Podaxis, 102
Podaxis pistillaris (L.: Pers.) Morse, 15, 250, **251**, 317
poison pie. See *Hebeloma crustuliniforme*
Polyporus squamosus (Huds.: Fr.) Fr., 311
poplar mushroom. See *Agrocybe parasitica*
porcelain fungus. See *Oudemansiella mucida*
porcini. See *Boletus edulis*
prince, the. See *Agaricus augustus*
psathyrella, common. See *Psathyella candolleana*
Psathyrella, 101, 205, 209

Psathyrella candolleana (Fr.: Fr.) Maire, **204**, 205, 305
Pseudotsuga menziesii (Mirb.) Franco, 143, 271
Psilocybe, 101, 103, 205, 206
Psilocybe argentipes K. Yokoy., 110, **205**
Psilocybe baeocystis Singer et A. H. Sm., 110
Psilocybe caerulescens Murrill, 110
Psilocybe caerulipes (Peck) Sacc., 110
Psilocybe coprophila (Bull.: Fr.) P. Kumm., 110
Psilocybe crobulus (Fr.) Kühner et Romagn., 110
Psilocybe cubensis (Earle) Singer, 110
Psilocybe fasciculata Hongo, 110, **206**
Psilocybe merdaria (Fr.) Ricken, 110
Psilocybe semilanceata (Fr.) P. Kumm., **207**
Psilocybe subaeruginascens Höhn., 110, **208**
puffball. See *Bovista*, *Calvatia*, *Lycoperdon*, *Vascellum*
puffball, common. See *Bovista nigrescens*, *B. plumbea*, *Vascellum pratense*
pukurau. See *Calvatia caelata*
purging agaric. See *Fomitopsis officinalis*
purple fairy club. See *Clavaria purpurea*
purple-spored puffball. See *Calvatia cyathiformis*
purple-tipped coral fungus. See *Ramaria botrytis*
Pycnoporus sanguineus (L.) Murrill, 256

quilted green russula. See *Russula virescens*

Ramaria, 102, 114, 286
Ramaria botrytis (Pers.: Fr.) Ricken, 313
Ramaria formosa (Pers.: Fr.) Quél., 112, 286, **287**
Ramaria gelatinosa (Coker) Corner, 112
Ramaria obtusissima (Peck) Corner, 307
Ramaria pallida (Schaeff.) Ricken, 112, 286
Ramaria stricta (Fr.) Quél., 289
red chanterelle. See *Cantharellus cinnabarinus*
red-cracked bolete. See *Xerocomus chrysenteron*
red-juice milk cap. See *Lactarius sanguifluus*
red-mouth bolete. See *Boletus subvelutipes*
reishi. See *Ganoderma lucidum*
Rhizopogon, 102, 262
Rhizopogon luteolus Fr., 280
Rhizopogon rubescens (Tul. et C. Tul.) Tul. et C. Tul., 80, 81, **279**, 280, 308
Rhodophyllus clypeatus (L.: Fr.) Quél., 308
Rhodophyllus crassipes (Imazeki et Toki) Imazeki et Hongo, 313
ringless honey mushroom. See *Armillaria tabescens*
rocky ear. See *Umbilicaria esculenta*

rocky fungus. *See Umbilicaria esculenta*
Roman shield entoloma. See *Rhodophyllus olypeatus*
rooting oudemansiella. See *Oudemansiella radicata*
Rozites caperatus (Pers.: Fr.) P. Karst, 317
Russula, 96, 101, 113, 148, 160, 165, 178
Russula aeruginea Lindblad ex Fr., **165**, 314
Russula alutacea (Pers.: Fr.) Fr., 307
Russula atropurpurea (Krombh.) Britzelm., **167**
Russula cyanoxantha (Schaeff.) Fr., 310
Russula delica Fr., 311
Russula emetica (Schaeff.: Fr.) Gray, 112, **166**, 167
Russula foetens Pers.: Fr., 167
Russula japonica Hongo, 167
Russula luteotacta Rea, 167
Russula mairei Singer, 167
Russula omiensis Hongo, 167
Russula sardonia Fr., 112
Russula senecis S. Imai, 167
Russula subnigricans Hongo, 167
Russula vesca Fr., 311
Russula vinosa Lindblad, 166
Russula virescens (Schaeff.) Fr., 166, 304
Russula violeipes Quél., 166
Russula xerampelina (Schaeff.) Fr., 309
russula-like waxy cap. See *Hygrophorus russula*
saddle-shaped false morel. See *Gyromitra infula*
saffron milk cap. See *Lactarius deliciosus*
St. George's mushroom. See *Calocybe gambosum*
salt-loving agaricus. See *Agaricus bernardii*
Sarcodon, 101
Sarcodon aspratus (Berk.) S. Ito, 315
Sarcodon imbricatus (L.: Fr.) Karst., 237, **238**
Sarcosphaera, 294
Sarcosphaera crassa (Santi) Pouzar, 294
scaly ink cap. See *Coprinus variegates*
scaly pholiota. See *Pholiota squarrosa*
scaly tooth. See *Sarcodon imbricatum*
scaly vase chanterelle. See *Gomphus floccosus*
scarlet caterpillar fungus. See *Cordyceps militaris*
scarlet waxy cap. See *Hygrocybe coccinea*
Schizophyllum, 102
Schizophyllum commune Fr.: Fr., 214, **216**, 310
Scleroderma, 23, 81, 102, 105, 114, 271, 273, 280, **281**
Scleroderma albidum Pat. et Trab., 280
Scleroderma areolatum Ehrenb., 280
Scleroderma cepa Pers.: Pers., 112, 280
Scleroderma citrinum Pers.: Pers., 112, 280

Scleroderma verrucosum Pers.: Pers., 280, **281**
sclertia-producing pleurotus. See *Pleurotus tuber-regium*
scrambled-egg slime mold. See *Fuligo septica*
separating tricholoma. See *Tricholoma sejunctum*
shaggy dung coprinus. See *Coprinus cinereus*
shaggy ink cap. See *Coprinus comatus*
shaggy parasol. See *Macrolepiota rhacodes*
shaggy-stalked bolete. See *Austroboletus betula*
sheep's foot. See *Hydnum repandum*
shier. See *Umbilicaria esculenta*
shiitake. See *Lentinula edodes*
shimeji. See *Hypsizygus marmoreus*
shoro. See *Rhizopogon rubescens*
short-stalked chanterelle. See *Gomphus clavatus*
short-stalked suillus. See *Suillus brevipes*
shrimp russula. See *Russula xerampelina*
sickener, the. See *Russula emetica*
silky volvaria. See *Volvariella bombycina*
slender Caesar's mushroom. See *Amanita hemibapha*
slippery jack. See *Suillus granulatus*, *S. luteus*
soap-scented tricholoma. See *Tricholoma saponaceum*
southern milk cap. See *Lactarius quietus*
southern poplar mushroom. See *Agrocybe cylindracea*
Sparassis, 102
Sparassis crispa (Wulfen: Fr.) Fr., **289**, 315
split gill, common. See *Schizophyllum commune*
spring agrocybe. See *Agrocybe praecox*
stalked puffball. See *Podaxis pistillaris*
stinkhorn, common. See *Phallus impudicus*
straw mushroom. See *Volvariella diplasia*, *V. volvacea*
streaked tricholoma. See *Tricholoma portentosum*
Strobilomyces, 101
Strobilomyces confusus Singer, 231
Strobilomyces floccopus (Vahl: Fr.) P. Karst., 231, **232**, 314
Stropharia, 101
Stropharia aeruginosa (Curtis: Fr.) Quél., **208**, 209
Stropharia coronilla (Bull.: Fr.) Quél., 110, 112
Stropharia rugosoannulata Farl. ex Murrill, 30, 55, 314
Suillus, 101, 231, 234
Suillus albivelatus A. H. Sm., Thiers et O. K. Mill., 303
Suillus bovinus (L.: Fr.) Kuntze, 81, 313
Suillus brevipes (Peck) Kuntze, 306
Suillus cavipes (Opat.) A. H. Sm. et Thiers, 310

Suillus granulatus (L.: Fr.) Roussel, 81, 95, 112, 306
Suillus grevillei (Klotzsch) Singer, 231, **233**, 308
Suillus luteus (L.: Fr.) Roussel, 231, **233**, 307
Suillus pictus (Peck) Kuntze, 309
sulfur tuft. See *Hypholoma fasciculare*
summer truffle. See *Tuber aestivum*
sweet bread mushroom. See *Clitopilus prunulus*
Swiss brown strain button mushroom. See *Agaricus bisporus*

tawny grisette. See *Amanita fulva*
Terfezia, 272
Terfezia arenaria (Moris) Trappe, 313
Terfezia claveryi Chatin, **271**, 304
Terfezia pfeilii Henn., 312
termite mushroom. See *Termitomyces albuminosa*, *T. clypeatus*, *T. eurrhizus*, *T. fuliginosus*, *T. microcarpus*, *T. schimperi*
Termitomyces, 169
Termitomyces albuminosa (Berk.) R. Heim, 315
Termitomyces clypeatus R. Heim, 306
Termitomyces eurhizus (Berk.) R. Heim, **168**, 169
Termitomyces fuliginosus R. Heim, 307
Termitomyces microcarpus (Berk. et Broome) R. Heim, 315
Termitomyces schimperi (Pat.) R. Heim, 317
thick-footed morel. See *Morchella crassipes*
tiger tricholoma. See *Tricholoma pardinum*
Tirmania, 272
Tirmania africana Chatin, 306
Tirmania pinoyi (Maire) Malençon, 309
train-wrecker. See *Lentinus suffrutescens*
Trametes, 102
Trametes versicolor (L.: Fr.) Pilát, **72**, **73**, 256, 316
Tremella, 62, 102, 260
Tremella aurantia Schwein.: Fr., 64, 310
Tremella foliacea Pers.: Fr., 305
Tremella fuciformis Berk., 18, 19, 22, 23, 30, 62, **63**, 64, 316
Tremella mesenterica Retz.: Fr., 309
Tricholoma, 101, 104, 176, 178, 181
Tricholoma album (Schaeff.) Fr., 112
Tricholoma aurantium (Schaef.: Fr.) Ricken, 113
Tricholoma bakamatsutake Hongo, 178, 313
Tricholoma caligatum (Viv.) Ricken, 174, 312
Tricholoma flavovirens (Pers.: Fr.) S. Lundell, 169, **170**, 316
Tricholoma inamoenum (Fr.) Quél., 112

Tricholoma japonica Kawam., 313
Tricholoma magnivelare (Peck) Redhead, 174, **175**, 178, 311
Tricholoma matsutake (S. Ito et S. Imai) Singer, 22, 24, 29, 80, 81, 92, 169, **170**, **171**, 172, 173, 174, 314
Tricholoma mongolicum S. Imai, 310
Tricholoma muscarium Kawam. ex Hongo, 110, 313
Tricholoma pardinum (Pers.) Quél., 112, 176
Tricholoma pessundatum (Fr.) Quél., 112, 176, **177**
Tricholoma portentosum (Fr.: Fr.) Quél., 309
Tricholoma robustum (Alb. et Schwein: Fr.) Ricken (sensu Imazeki), 305
Tricholoma saponaceum (Fr.: Fr.) P. Kumm., 112, 316
Tricholoma sejunctum (Sowerby: Fr.) Quél., 113, 314
Tricholoma sulphureum (Fr.) P. Kumm., 113
Tricholoma terreum (Schaeff.: Fr.) P. Kumm., **176**
Tricholoma ustale (Fr.: Fr.) P. Kumm., **177**, 178, 209
Tricholoma venenata G. F. Atk., 113
Tricholoma zelleri (D. E. Stuntz et A. H. Sm.) Ovrebo et Tylutki, 113
Tricholomopsis platyphylla (Pers.: Fr.) Singer, 113
truffle. See *Tuber*
trumpet of death. See *Craterellus cornucopioides*
Tuber, 21, 29, 81, 266
Tuber aestivum Vittad., 314
Tuber borchii Vittad., 268, **270**, 303
Tuber brumale Vittad., 263, 266, 306
Tuber brumale var. *moschatum* Ferry, 312
Tuber californicum Harkn., 310
Tuber dryophilum Tul. et C. Tul., 90, 268
Tuber excavatum Vittad., 314
Tuber gibbosum Harkn., 80, 268, 306
Tuber hiemalbum Chatin, 303
Tuber himalayense B. C. Zhang et Minter, 263
Tuber indicum Cooke et Massee, 263, 316
Tuber maculatum Vittad., 90, 262, 268, **270**, 271
Tuber magnatum Picco, 22, 24, 25, 80, 81, 92, 266, **268**, 316
Tuber melanosporum Vittad., 22, 24, 25, 78, 80, 81, **82**, 83–92, 263, **264**, **265**, 266, 307
Tuber mesentericum Vittad., 304
Tuber pseudoexcavatum Y. Wang, G. Moreno, Riousset, Manjón et G. Riousset, 312
Tuber rufum Picco, 317
Tuber sinense K. Tao et B. Liu, 263, **267**, 317
Tuber uncinatum Chatin, 80, 81, 263, 266, **267**, 304
Tylopilus, 101
Tylopilus felleus (Bull.: Fr.) P. Karst., **234**

umbellate polyporus. See *Grifola umbellata*

Umbilicaria, 102
Umbilicaria esculenta (Miyoshi) Minks, **299**, 313
Uromyces, 102
Uromyces digitatus Halst., 253, **254**
Ustilago, 102
Ustilago maydis (DC.) Corda, 254, **255**

Vascellum, 102
Vascellum pratense (Pers.: Pers.) Kreisel, 272, 312
vegetable caterpillar fungus. See *Cordyceps gunnii*, *C. hauturu*, *C. robertsii*
Verpa, 102
Verpa bohemica Krombh., 105, 113, 242, **243**
Verpa conica (O. F. Müll.: Fr.) Sw., 113
violet cortinarius. See *Cortinarius violaceus*
viscid gomphidius. See *Chroogomphus rutilus*
Volvariella, 101, 104, 137, 182
Volvariella bombycina (Schaeff.: Fr.) Singer, 313
Volvariella diplasia (Berk. et Broome) Singer, 22, 25, 303
Volvariella speciosa (Fr.: Fr.) Singer, **182**
Volvariella volvacea (Bull.: Fr.) Singer, 18, 19, 22, 23, 25, 30, 57, **58**, **59**, 132, **183**, 304

weeping milky cap. See *Lactarius volemus*
wheat ergot. See *Claviceps purpurea*
white-cap bolete. See *Boletus aestivalis*
white chanterelle. See *Cantharellus subalbidus*
white-footed elfin cup. See *Paxina leucomelas*
white jelly fungus. See *Tremella fuciformis*
white matsutake. See *Tricholoma magnivelare*
white oyster mushroom. See *Pleurotus opuntiae*, *P. ostreatus*
white truffle. See *Choiromyces meandriformis*
white winter truffle. See *Tuber hiemalbum*
wine-cap stropharia. See *Stropharia rugoso-annulata*
winter truffle. See *Tuber brumale*
witch's butter. See *Tremella mesenterica*
witch's hat. See *Hygrocybe conica*
Wolfiporia cocos (F. A. Wolf) Ryvarden et Gilb., 256, 314
wood blewit. See *Lepista nuda*
wood ear. See *Auricularia*, *A. auricula*, *A. polytricha*
woodland agaricus. See *Agaricus sylvicola*
woolly gomphidius. See *Chroogomphus tomentosus*
woolly milk cap. See *Lactarius torminosus*
wrinkled thimble cap. See *Verpa bohemica*

Xerocomus, 101
Xerocomus badius (Fr.: Fr.) Kühner, **235**, 308
Xerocomus chrysenteron (Bull.) Quél, 235, **236**, 308
Xerocomus pulverulentus (Opat.) J. E. Gilbert, 306
Xylaria, 102, 286
Xylaria polymorpha (Pers.: Fr.) Grev., 286, **287**

yaner. See *Umbilicaria esculenta*
yellow morel. See *Morchella esculenta*
yellow oyster mushroom. See *Pleurotus cornucopiae* var. *citrinopileatus*
yellow stainer. See *Agaricus xanthoderma*

zoned-stemmed russula. See *Russula delica*

Edible
Wild
Plants

A
NORTH
AMERICAN
FIELD GUIDE

Thomas S. Elias & Peter A. Dykeman

AN
OUTDOOR
LIFE BOOK

Sterling Publishing Co., Inc. New York

Appendix

Guide to the Acupuncture Points used in Cosmic Chi Kung

The following is a detailed description of the acupuncture energy points used in the Cosmic Chi Kung practice. It is necessary to know the exact location of the points to do the practice well. However, you do not have to know the traditional Chinese medical functions and energetics of the points to do the practice. These are included in this appendix as an item of interest.

The names of the points are given first by the channel and number, second by the English translation of the traditional Chinese name for the point and finally by the name in Chinese.

We are emphasizing the traditional Chinese medical therapeutic properties of the points given herein. Many of these points also have very different purposes in Taoist Yoga. *For a description of the Taoist Yoga energetics, refer to "Awaken Healing Light of the Tao" by Mantak Chia.*

Pericardium 8

"Lakor's Palace" - Laogong

Ying Spring, Fire Point

Location: On the center of the palm, where the tip of the middle finger touches when making a loose fist.



Functions: Cools the heart, drains heat from the heart, cools the blood, calms the spirit, regulates the heart Chi and yang, Ghost Point for treating spirit possession.

Indications: Coma from stroke, heat exhaustion, angina pectoris, mania, hysteria, mental illness, excessive sweating of the palms, mouth problems.



Library of Congress Cataloging-in-Publication Data

Elias, Thomas S.
Edible wild plants : a North American field guide / Thomas S. Elias & Peter A. Dykeman.
p. cm.
Includes index.
Reprint. Originally published: New York : Outdoor Life Books, c1982.
1. Wild plants, Edible—United States—Identification. 2. Wild plants, Edible—Canada—Identification. 3. Cookery (Wild foods) I. Dykeman, Peter A., 1935– II. Title.
QK98.5.U6E35 1990
581.6'32'0973—dc20 90-39506
CIP

10 9 8 7

Published 1990 by Sterling Publishing Company, Inc.
387 Park Avenue South, New York, N.Y. 10016
Originally published as *Field Guide to North American Edible Wild Plants*
by Outdoor Life Books © 1982 by Thomas S. Elias and Peter A. Dykeman
Distributed in Canada by Sterling Publishing
℅ Canadian Manda Group, P.O. Box 920, Station U
Toronto, Ontario, Canada M8Z 5P9
Distributed in Great Britain and Europe by Cassell PLC
Villiers House, 41/47 Strand, London WC2N 5JE, England
Distributed in Australia by Capricorn Ltd.
P.O. Box 665, Lane Cove, NSW 2066
Manufactured in the United States of America
All rights reserved

Sterling ISBN 0-8069-7488-5

Contents

Acknowledgments 4

Introduction 5
- How to Use This Book 5
- Nature's Diversity 7
- What Determines the Taste of Wild Plants? 9
- Danger of Overharvesting 9
- Habitat Guide 10
- Harvest and Preparation 12
- Plant Foods of the Indians 22
- Nutrition 25
- Other Plant Identification Guides 27

Key to Edible-use Symbols 29

Seasonal Key to Plants 30

Spring 56

Summer 126

Autumn 208

Winter 248

Poisonous Plants 258

Appendix: Nutritional Contents of Selected Foods 274

General Index 277

Index to Plant Names (Common and Scientific) 278

Acknowledgments

This book is a compendium of information we gathered over many years of study. Of course, any work on edible wild plants builds upon the experiences of others, beginning with the accounts of the American Indians and early European settlers, and continuing to the present.

Many people assisted us in the preparation of this book. Central to the entire effort was Neil Soderstrom, who served as editor and friend. His ideas helped make the book more useable and his encouragement and prodding brought it to fruition. Jeff Fitschen designed the pages and created the maps. Lloyd Birmingham drew the edible symbols. Helen Dykeman helped with typing, and Brian Elias assisted in some of the photo sessions. We are also grateful to the New York Botanical Garden for use of its botanical library resources, among the finest in North America.

While the majority of the photographs here are our own, many came from other sources. We are grateful to friends, colleagues, and institutions that supplied color transparencies. We've listed full names of photo sources below, alphabetically. Credits by last name or institutional abbreviation appear in parentheses in photo captions.

Dr. Loran C. Anderson
Nelson T. Bernard Jr.
Frank P. Bogel
James Clawson
Bill Cramer
Dr. Garrett Crow
Desert Botanical Garden, Phoenix, AZ
Dr. Peter A. Dykeman
Dr. Thomas S. Elias
Osbra L. Eye
Dr. Albert Feldman
Dr. George W. Folkerts
Dr. James Hardin
Jepson Herbarium, University of California, Berkeley
Bob Hutchins
Berrie Kavasch
Arthur R. Kruckenberg
Dr. Dale McNeal
John Mathisen
Dr. Robert H. Mohlenbrock
Helen Mulligan
New York Botanical Garden (NYBG), Bronx, NY
Dr. Robert Ornduff
John Pawloski
Robert A. Ross
James R. Shevock
Neil Soderstrom
Robert Speas
James Stevenson
University of California, Davis
U.S. Dept. of Agriculture (USDA)
C. S. Webber
Dr. William A. Weber
Kay Young

T.S.E. and P.A.D.

Introduction

How to use this book

This is a season-by-season guide to identification, harvest, and preparation of over 200 of the most popular and common edible wild plants of the U.S. and Canada. Hundreds of related edible species are also noted. In addition, the book covers identification of 20 poisonous plants and notes many other poisonous ones. Neither edible nor poisonous mushrooms are included.

Detailed texts, maps, drawings, and nearly 400 photos (mostly in color) allow easy identification. But since there are over 20,000 species of plants to choose from in North America, excluding Mexico, it's important to make identifications with care and caution. The trick is to carefully compare features of the plant at hand against those here. Remember this rule: *When in doubt, leave the plant out.*

We have included edible plants for each season from every major region of the U.S. and Canada, except for the subtropical areas of southern Florida. We have excluded obscure plants and plants that are only marginally edible. Likewise, we have omitted plants that occur in limited numbers or are threatened. Two such plants are the Joshua tree *(Yucca brevifolia)* and the Saguaro cactus *(Cereus giganteus),* both slow-growing trees of the southwestern U.S. Rare or threatened species should never be gathered.

The book's plant-seeking and identification systems are simple and versatile. In most cases, you'll probably want to begin by consulting the "Seasonal Key to Plants," beginning on page 30. This Key groups plants by *primary* "edible season," with other edible seasons noted there as well. Within the Key, you can easily hunt up plants in various ways: whether by common or scientific name, by distribution range, by general plant type, by habitat, or by edible options—whether you have an urge for something boiled, baked, raw, and so on. The more you use the Key, the more you'll like it.

On the other hand, you may know a plant's scientific or common name and simply want to learn more about it. In this case, just find its page reference in the Index in the back of the book. *Caution:* Often, unrelated plants share a common name—from region to region, and from guidebook to guidebook. Thus, it is wise to learn or at least check the scientific names.

At other times, you might prefer to browse a seasonal section in the body of this book itself to see what kinds of plants you might encounter on your next outing. There you'll find plants arranged as they are in the Key, by edible season. Within each of these seasonal sections, plants are arranged by type. That is, ferns appear first. Then come monocots such as the lilies and grasses. Last come the largest group, the dicots, which include herbs (most soft-stemmed plants), then vines and shrubs, and finally trees. Within the herb groupings themselves, the plants are arranged according to flower color and leaf arrangement.

The following table gives contrasting features of monocots and dicots.

Monocots	**Dicots**
(such as onions, wild rice, cattail, corn lily, sweet flag, reed, camass lily)	*(such as amaranth, mustard, blackberries, strawberries, sunflower, plums, cherries, blueberries)*
Narrow leaves with parallel veins	Broader leaves with netlike veins
Flower parts in 3s or multiples of 3	Flower parts in 5s, sometimes 4s
Vascular strands (bundles) scattered throughout a nonwoody stem	Vascular strands (bundles) arranged in a ring on stem that may be woody
One seed leaf per seed	Two seed leaves per seed

Common names and scientific names. Common names are useful, especially so if they are descriptive, but they often vary from region to region. Adding to the disadvantage of using only common names, several plant species may be known by the same common name. In this book, we've preferred to use a single common name but may list a second or even third common name when the names are widely used. But you'd be wise to confirm scientific names when consulting other plant guides or when using common names in everyday discussions.

The scientific name, in Latin, is important because it is the universally accepted name. Scientific names for all plants and animals adhere to a binomial (two-word) system and are always italicized. The first word designates the genus and begins with a capital letter. A genus is a group of closely related species. The second word indicates the species and begins with a small letter. A species is a group (or groups) of individuals that look similar and can freely interbreed. Hybrids between species do occur though.

Typographical tipoffs. The texts covering each plant in this book employ typographic variations that highlight categories for quick reference and announce whether a mentioned plant is covered elsewhere in this book. As in the example shown two paragraphs below, each species text begins with the common name or names, beneath which are listed additional seasons in which the plant is edible. Then comes the scientific name, always in *italics,* which may be followed by an italicized synonym in parentheses. This synonym is the outdated scientific name under which you may find the plant listed in older plant guides.

Bold face type draws your eyes to the sequence of descriptive categories. ***Bold face italic*** announces primary identifying features. SMALL CAPITAL LETTERS are used for common names of plants covered in detail elsewhere in the book and located by means of the Index. For mentioned plants not covered in detail, both the common and the scientific names are given. To look up these plants in other guides, use the scientific name.

Utah juniper *Juniperus osteosperma*
Also edible autumn, winter (synonym: *J. utahensis*)

Habitat: mesas, mountain slopes, high plains, principally from 1,000–2,650 m (3,300–8,700 ft) elevation in dry rocky or gravelly soils. **Identification:** large ***shrub*** or small ***bushy tree*** to 8 m (26 ft) high with ***furrowed ash-gray bark that shreds in long, loosely attached strips. Leaves*** tiny, ***scalelike, opposite and overlapping one another in 2s, closely pressed against branchlets,*** 3–4 mm (0.1–0.2 in) long, usually gland-dotted on back, ***sharp-pointed at tip, yellowish-green.*** Male and female flowering cones usually produced in spring on separate trees, inconspicuous and usually overlooked. ***Fruits small, leathery berries 6–9 mm*** (0.2–0.4 in) ***in diameter, nearly globe-shaped, reddish-brown, resinous, sweet,*** with mealy texture, containing 1, rarely 2, seeds. **Harvest and preparation:** same as for ROCKY MOUNTAIN JUNIPER. **Related edible species:** CALIFORNIA JUNIPER and ROCKY MOUNTAIN JUNIPER (preceding). **Poisonous look-alikes:** same as for ROCKY MOUNTAIN JUNIPER.

Nature's diversity

Some plants taste good and are easy to digest, while others are marginally so. Many others are unpalatable or even poisonous. Why? Plants, like animals, are products of millions of years of evolution and adaptation. Through all this time and even today, they are subject to many influences, including changes in climate, soil, and water; competition from other plants; and the scores of plant-eating animals, ranging from insects to mammals. Some animals, particularly the insects, have gradually specialized by feeding on and laying eggs on specific plant species and groups. If a plant fails to adapt to these external influences, the result can be serious depletion or even extinction of its species.

Plants, like animals, have developed a myriad of defense mechanisms to counter the continuing attacks by animals. But, unlike animals, plants cannot pick up their roots and race for safety. Nor have many plants taken the offensive and become predators; the parasitic and insectivorous plants are remarkable exceptions. So to defend themselves or ensure survival of their species, most plants have developed elaborate mechanical, chemical, and reproductive characteristics.

Reproduction. Some plant species survive largely because of their high reproductive capacity. Here, the plants reach sexual maturity early, produce large quantities of seeds or other propagules, and may be adapted to a wide variety of habitats, especially on sites disturbed by man. In these ways, dandelions, chickweed, shepherd's purse, and other plants channel much of their resources into reproduction. With their rapid growth and early maturation, they outcompete many slower-growing plants. This phenomenon is easiest to observe in yards and on land reverting back to a wild state.

Armament. Still other plants employ an arsenal of external structures (spines, thorns, stinging hairs) that can deter larger animals from browsing. These defensive structures often occur in conjunction with internal mechanisms such as tough fibers and bitter-tasting or even poisonous chemical compounds. Did you ever notice how many thistles remain uneaten in fields otherwise heavily browsed by deer or cattle?

External chemical defense. Another defense is the production of tiny glands or glandular hairs on the plant surfaces. These structures may produce an array of chemical compounds that may even be secreted onto the surfaces of stems and leaves. Secreted substances usually glisten in direct light and are sticky. They may also emit a repulsive odor. Many members of the sunflower family have tiny glands on the leaves, stems, or outer surface of the flower clusters. As a test, place some fresh leaves and flowers of tarweed (*Grindelia* species) in a plastic bag for a few hours and then open the bag. You'll smell a heavy resinous odor from the glandular secretions. The secretion and odor are believed to repel leaf-eating animals.

Internal chemical defense. Many plants produce chemical compounds within the leaves, flowers, and fruits, which make the plant taste bad or render it toxic.

The cholla's armament, below left, consists of spines that readily pierce flesh. Spine tips may break off when you attempt to remove them. Below right, the glistening, sticky coating on tarweed flowers is secreted by tiny flower glands. As a chemical defense, it renders the plants unappetizing to potential predators. (Elias photos)



This is why some recipes later in this book tell you to soak the plant parts in water first or to discard the water after the plants have been cooked. Other recipes recommend using only young leaves or stems because the young parts do not contain high levels of the undesirable chemical compounds. Also, young parts are tenderer because the vascular strands and fibers have not had enough time to enlarge and toughen. Even extended cooking won't render all plants edible. The poisonous components in such plants as irises, water hemlock, and others cannot be broken down, nor can they be leached out by water changes or cooking.

Appeal to animals. There are times when it is to a plant's advantage to be eaten. After plants have flowered and produced fruits, reproduction and, ultimately, survival of the species require that the seeds be dispersed to sites suitable for germination and growth. To achieve seed dispersal, plants use unwitting animals. Consider the tasty and nutritious flesh of wild berries. The tiny seeds inside many kinds of berries pass through animals unaffected by the digestive process and are so dispersed in excrement.

What determines the taste of wild plants?

Experienced foragers know that the taste of a particular species from one site may differ slightly from that of the same species at another site. This is due to genetic variation usually manifested in differing physical or chemical characteristics. Thus, the degree of bitterness or mildness in many members of the mustard and daisy families, for example, can be attributed to natural genetic variations. Chemical composition of the soil along with other substances added by man or animals can affect the taste of some plants, especially smaller herbs.

Then too, people themselves differ in their ability to taste and in their tolerance of certain plant compounds. Just as many foragers enjoy fresh dandelion greens and boiled cattail stalks, others may detest them. You might acquire a taste for certain wild edibles only after experimenting with harvest and preparation techniques.

Danger of overharvesting

Avoid overharvesting and thus eradication of a plant from a site. Try to make a note of the reproduction levels of wild edibles in your area. If you harvest native plants faster than they can reproduce, you'll have a detrimental impact on the environment. It's a good rule always to leave some mature plants to produce fruits and seeds.

Obviously, you won't cause serious ecological damage if you harvest plants introduced from other countries. Introduced plants are already alien to native habitats. The widespread invasions of these introduced plants in the wake of man's new settlements have permitted them to become established and in some

In summer, gravelly flood-scoured streambanks may be dominated by purple loosestrife, as shown left. Beneath the loosestrife, mature ostrich fern fronds are drying. Their brown plumes will remain until spring to help foragers find the fern's tasty young fiddleheads. Right, the density of this cattail "garden" on the edge of an artificial pond was annually increased by weeding. (Dykeman photos)

cases to overcome the natives. Examples of introduced species include dandelions, chickweed, mustard, and plantain.

Habitat guide

With the acquisition of this book, you have taken the first and easiest step toward a feast of wild edibles. Though good eating is a major goal here, don't overlook the potential fun in simply foraging for plants. With a little knowledge of plant ecology and field identification you can find an abundance of wild foods.

Except for nuts, acorns, and sap in season, forested areas have fewer edibles to offer than most unforested areas. Yet in northern deciduous forests you might find Indian cucumber and bunchberry, among many other plants. In hardwood forests early in the growing season, look for marsh marigold, toothwort, and several of the violets near small streams and adjacent mucky areas. In the rich,

Left, bulldozed two years prior to the photo at left, this "disturbed" site offers various edibles including dock (brown mature seed stalks), evening primrose (yellow-flowered stalks), and stinging nettle (dark green plants topped by long slender flower spikes). Right, desert habitats dominated by tall saguaro cacti, with edible fruits, may also offer edible prickly pear and mesquite. (Dykeman and Elias photos)

moist and neutral-soil woods you may find wild onions and leeks. Near the edge of the woods, you may see the broad leaves of garlic mustard. Here also dwell the greenbriers and catbrier.

In spring, along gravelly stream banks regularly scoured by floods, look for the delicious fiddleheads of the ostrich fern. The task is easier if you first notice the tall brown fern plumes from the previous year. Later this habitat may offer tender young nettles and one or both species of jewelweed, which, away from streams, may grow in moist, fairly open areas. Partially sunny areas in spring may reward you with mints and watercress.

Marshy pond edges often offer wild-food bonanzas. From the cattail ("Cossack asparagus") early in spring to the arrowhead tubers in the fall and winter, these sites provide continuous sources of foods. Among the providers are pickerelweed, cattail, common reed, arrowhead, water lilies, great bulrush, and wild rice. It's often wise to start the spring harvest by checking for new sprouts on the cattail roots. Fortunately, none of us needs to complete the harvest season in December the way the Indian squaws did, according to Lewis and Clark, by standing in chest-deep ice water, loosening arrowhead tubers from the mud with their toes.

Sights disturbed by bulldozers or plows are always worth a close look. For a grand variety of greens, from early spring to summer, visit such disturbed areas frequently. Lawns provide dandelions, chicory, plantain, and other greens best gathered as early as possible. In recently disturbed sites such as last year's garden, mustard, winter cress, chickweed, and shepherd's purse are followed by lamb's quarters, amaranth, purslane, and many other edible "weeds." A year or so after being disturbed, these sites may then produce docks, pokeweed, evening primrose, salsify, milkweed, and many other edibles.

Roadsides offer bounty closely akin to bulldozed areas. Yet auto traffic and its pollutants often make roadside foraging unhealthy. In June along a lightly traveled dirt road, you may want to cut poke or asparagus shoots, or pick common day lily buds. In fall, you might dig for Jerusalem artichokes or common day lily tubers.

While foraging for spring greens, note locations of the flowers of blackberry, raspberry, blueberry, and elderberry. Most old fields and forest edges produce one or more species of berry plants during the succession toward a woodland plant community. Elderberry blossoms are edible, but be sure to leave plenty for fruit production. In the Northeast, raspberries and blueberries fruit first, followed by blackberries and elderberries. If you live in an area with heavily fruiting serviceberries, first locate their white flowers in spring against the leafless grays and browns of woods and river edges. Gather the serviceberries that the birds don't get first, during blackberry time in midsummer.

In summer throughout the rough lands of the West, look for currants, yuccas, prickly pears, and immature mesquite pods.

If you plan your vacation to the East Coast for late summer, look for ripe beach plums. They are frequently plentiful, though few people seem to pick them. If camping in national or state parks, of course, first obtain permission to pick.



Large Intestine 4
"Adjoining Valleys" - Hegu

Yuan Source Point
Location: On the back side of the hand between the thumb and index finger, in the web approximately at the middle of the metacarpal bone of the index finger.
Functions: Disperses wind, relieves exterior conditions, suppresses pain and clears the channels, clears lung heat, calms the spirit.
Very powerful point for moving the Chi and blood of the whole body; main point for pain; main point for headache; main point for ailments of the head, face and sensory organs; main point for immunity.
Indications: Headaches, common cold, redness with pain and swelling of the eyes, toothache, facial swelling, sore throat, finger cramps, arm pain, fever, abdominal pain, constipation.
Caution: Contra-indicated in pregnancy.



Small Intestine 3
"Back Creek" - Houxi

Shu Stream, Wood Point
Master Point of the Governor Channel
Coupled Point of the Yang Bridge Channel
Location: When a loose fist is made, the point is near the head of the fifth metacarpal bone on the knife edge of the hand at the junction of the red and white skin.
Functions: Relaxes the tendon-muscular channels, opens the Governor Channel, clears the Spirit, drains evil Chi from the heart.
Indications: Seizures, psychosis, hysteria, intercostal neuralgia, headache, stiff neck, red, painful and congested eyes, deafness, spasms of the arm, elbow and fingers; fever, night sweating, whiplash, occipital headaches.

Used for structural/musculo-skeletal problems; opens the Governor Channel for problems with back, neck and head, main point for stiff neck, antispasmodic for muscle spasms; anti-inflammatory for spinal arthritis, intestinal inflammation.



Lung 10
"Fish Border" - Yuji

Ying Spring, Fire Point
Location: In the middle of the ulna eminence below the thumbs at the junction of the red and white skin.
Functions: Cools heat in the lungs, benefits the throat.
Indications: Sore throat, cough, laryngitis, tonsillitis, fever with common cold.

In the East, September is a great month for sumac berries along the edges of woods and in old fields. The staghorn sumac is best then and the smooth sumac, which reaches its peak earlier, still has good flavor. In the West, squawbush fruits are harvested in September. As the first frost approaches, grapes and viburnums ripen along brushy fencerows and wood's edge. Early fall is also the time to drive the country roads looking for the first fallen nuts. The best-producing nut trees are in the open and along roads and old fences. Make note of the nut tree locations early and check them periodically in order to beat wildlife to the nuts when they begin to fall. In fact, you can gain the advantage over wildlife by climbing nut trees and shaking the nuts loose.

Through the fall, look in fields for hawthorn and rose fruits undergoing their post-frost sweetening. After that, you might sit back and relax until the following spring's maple sugar season.

Winter foraging serves almost exclusively for survival fare or for diversion during a January thaw. If the wild food fever strikes you in winter, you'd be best served in warmer southern climes.

Harvest and preparation

Shoots, leaves, and other aboveground parts. For all aboveground tender parts, the time between harvest and eating is critical. Some plants lose much of their vitamin content in a few hours. So avoid saving them until they taste as flat as if they'd come from a supermarket!

It's also important to forage at correct times. Several greens, including chicory and winter cress, become bitter very early in the growing season. Pokeweed shoots increase in toxicity as they grow. And many other greens such as ostrich fern and plantain become tough or fibrous with age.

Even though the shoots lose palatability as they grow, new leaves and growing tips of many plants, such as miner's lettuce and lamb's quarters, remain tender and edible throughout the growing season. Plants such as milkweed, cattail, and common day lily also produce edible flower buds and flowers, and during the growing season are worth several foraging visits. As the years pass, you may want to develop your own regional calendar of the harvest dates for plant parts.

Some plants are best picked by hand—a leaf or tender tip at a time. Densely leaved plants such as sheep sorrel and chickweed are best pulled up whole before you use scissors to shear off the leaves. Since nettles, greenbrier, and some other edibles are armed in various ways, you'll need gloves and shears for harvesting.

Wash the freshly harvested plants with cold water. Then cook them with concern for their taste, tenderness, and nutritional value. With shoots, you can retain most vitamins by bundling and steaming them like asparagus. This works well with fern fiddleheads, cattail shoots, Japanese knotweed, and, of course, wild asparagus. Shoots with bitter sap like milkweed's or a toxic substance, as in pokeweed, may be bundled but must be submerged in changes of boiling water to render the plants safe to eat.

Normally you should avoid submerged boiling of tender, delicate leaves and



Left, for a nutritious flour additive, shake pollen from cattail male flower spikes. Plants at right (not all edible) illustrate terms used in this book to characterize underground plant parts: l. to r. are a wild carrot taproot, a jack-in-the-pulpit corm, a lily-of-the-valley bulb, violet rhizomes, and day lily tubers. (Dykeman photos)

growing tips. Here boiling has about the same effect as soaking your breakfast cereal in boiling water and then draining the water off: All the flavor and texture and much of the nutritional value are lost. For such plants, including lamb's quarters and chickweed, use just a few tablespoons of water beyond that which is left from washing. Within 1–3 minutes such greens are done to perfection.

Coarser greens such as dock and cleavers require longer cooking, barely covered with water. Cook until tender instead of just chewy. Plants with toxic or bitter substances must be boiled in changes of water, although the process reduces much of the vitamin content. A pinch of baking soda will help tenderize tough greens but promotes vitamin loss.

When possible, try to combine bland greens with those having a bitter or sour character. While coarse dry-textured greens are cooking, add a little bacon grease or butter. Season only *after* cooking.

Roots, tubers, and other underground parts. Several plants produce taproots, tubers, or corms that are excellent substitutes for potatoes and root crops. These plants are usually best from fall through early spring when most other wild foods are scarce. The underground structures serve as storehouses of carbohydrates and are richest in starch at the end of the growing season. As the earth warms in early spring the starch is converted to sugars that may sweeten the underground structures. When the plants begin to grow and most of the starches have been converted, the underground structures generally become soft and unpalatable.

But there are disadvantages to using underground parts as food. The aboveground parts of many plants die in autumn and either shrivel greatly or break away from the root, making foraging very difficult. Then positive identification is a tough challenge since you nearly always need aboveground parts for reference. Mistaking a species such as death camass *(Zygadenus)* for the edible camass *(Camassia)* would be fatal. As with all wild food gathering, be certain of what you collect.

Once you have gathered a batch of fleshy roots or other underground parts, cook them like potatoes. Options include boiling, baking, and frying, as well as the pit-roasting method used by Indians in dry climates. For pit roasting, dig a hole at least 2 ft by 3 ft and about 2 ft deep. Line the bottom and sides with rocks. Build an intense fire inside the pit to heat the stones and adjacent earth. After several hours of burning, clean out the burning wood and coals and line the rocks with green grass or leafy twigs. Lay in the food to be roasted and cover it with more grass. Pour in a pint of hot water to produce steam. Top the pit with 5 cm (2 in) of soil and build a fire on it. For groundnuts and arrowhead tubers, maintain the fire for 3–4 hours. To reduce camass bulbs to a sweet blackish mass, Indians cooked them from up to 3 days. Whatever way you cook underground edibles, leave the skins on to preserve most of the vitamins.

Underground parts of some plants are excellent raw as trail nibbles or in salads. Examples include wild onions, Indian cucumber, and cattail root tips. You can experiment to determine which others are neither too tough nor too bitter for eating raw.

Tough roots of cattails and some other species can be crushed to release the starch, which can then be dried for use as flour. Other species may be dried whole or sliced and stored for long periods, a very valuable preparation for Indians, who relied on seasonally available foods. Drying also removes the toxicity of the roots of plants such as skunk cabbage and jack-in-the-pulpit, which are not included in this book because of their toxicity when fresh.

Beverages. You can brew teas from a wide range of leaves, fruits, twigs, and even roots, many of them high in vitamin C. Most tea materials may be used fresh or dried; check the species texts in this book to learn which is best for each plant.

Pick leaves at their peak growth. Then dry them in a warm place out of direct sunlight. If you use a warm oven, remember that too much heat will drive off oils that give the beverage its flavor. Store dried leaves in a sealed container. The

Below, a berry scoop fashioned from a plastic container can greatly increase your harvest rate, but it won't distinguish between ripe and unripe berries. Right, you can use a fabric-covered board to bounce most hard, unripe berries beyond a collector box. (Dykeman photos)

same principles apply to the drying and storage of fragrant twigs and root bark and to flowers of such species as basswood and clover.

To prepare a cup of tea, 1 tsp of dried material or 2 tsp of fresh are usually enough. Steep the dried ingredients in boiling water, but do not boil the tea. Otherwise you'll drive off the fragrant oils. Like commercial teas, strong-flavored ingredients need only a few minutes of steeping. Delicately flavored strawberry leaves, birch twigs, and the like may require 15 minutes or more.

For flavor variations in teas, experiment with blends of ingredients. Since many plants make good teas, the combinations are limitless, as suggested by the labels on commercially packaged wild tea blends. *Caution:* Be certain that all of your ingredients are safe to use. In this book we've avoided mention of folk remedies and medicinal uses of plants. Some of these are unproven and even dangerous. And those that may have merit often depend on correct diagnosis of an ailment. You're better off using commercially prepared medicine. Still, a cup of birch tea for a queasy stomach won't hurt you.

Coffee substitutes are usually made from roasted, coarsely ground roots and tubers. Some, such as chicory and dandelion, are best harvested outside the growing season, while chufa tubers are firm and good to use anytime. Roast the material slowly, browning it all the way through. Too high a temperature will scorch it and give you a terrible cup of coffee. Store the prepared material in a sealed container. Generally use 2 tbsp of "coffee" per cup of water. Brew it like regular coffee but do not overbrew unless you have a cast-iron stomach.

Fruits and fruit juices. You'll need to handpick many fruits because they'll be attached too firmly to be shaken loose. But the shake method works well for bushes or trees such as mulberry, cherry, and highbush blueberry. Any large sheet of plastic or fabric will suffice. Just spread it under a portion of the plant and shake the branches above. You may be amazed at the quantities you harvest. Large trees may require climbing. This method works well on nut trees, too, and helps you beat the squirrels to the nuts.

If shaking won't work but the fruits are large and firm like cranberries, improvise a toothed scoop from a plastic 2 liter (2 quart) jug. With practice, you can make this scoop a highly efficient gathering device.

Some clustered fruits such as grapes, mountain ash berries, and elderberries will not yield to shaking or scoops. Here you'll need to take the whole cluster with fingers, knife, or pruning shears. Then you can strip the fruits from their stems. Soft fruits like strawberries and raspberries have to be picked by hand.

If you strip firm fruits such as blueberries from the twigs, you'll usually wind up with many unripe fruits in the bucket. You can sort out unripe fruits tediously by hand, or you can rig up a bounce board, as shown in the accompanying photo.

Drying Fruits. Drying processes are described later in many of the texts on individual species or plant groups. But as a general rule, select only fully ripe fruits. Dry small fruits whole, pit the pitted ones, and cut large ones into pieces or slices.

For best results place the fruits in a single layer on a rack made with a nylon screen or thin cloth. If drying is done outside, place the rack out of direct sunlight. Turn the fruit once or twice daily and cover the rack or take it inside at night. You may find it more convenient to place the rack in an attic, which may be ideally warm and dry during the summer. Just be certain there are no mice or squirrels there. Attic and outdoors drying requires from a few days to two weeks, depending on the fruit and the weather.

If you are ambitious, make a solar dryer, which is basically a sun absorbing box with adjustable vents to allow air exchange while maintaining a temperature below 80°C (175°F). The effect is the same as from using a warm oven, but the energy is free. Drying time in a solar box or kitchen oven will be from 6 hours to 2 days. Remember to turn the fruit occasionally to promote uniform drying. The process is completed when no juice can be squeezed from the fruit. If you fail to dry the fruit enough, it will mold. Store it in sealed plastic or glass containers away from light.

Most dried fruits store well but a few, such as saguaro, may have insect eggs on them and will become wormy in time. Avoid worms by pulping and boiling the fruit, then drying it in a thin sheet to make fruit leather. This lightweight, nutritious fruit form is great for trail use. For cooking use ¾ cup of dried fruit per cup of fresh fruit called for in a recipe. But soak the dried fruit about 15 minutes beforehand.

Cold drinks can be made from the juices of many fruits. Extract the juices after crushing the fruits and cooking them over low heat. To finish the beverage, you usually need only add sweetening and perhaps a little water. Grapes, cranberries, and red mulberries are among the best fruits for juices. To extract the flavors of drier fruits such as the sumacs, soak them in hot water. Served cold or hot with or without sweetening, sumac juice is delicious.

Saps from maples, birches, and other trees, taken during sugaring season, make excellent drinks. Sap is best within a day or two of harvest. Try some in spring while you are making maple syrup.

Jellies. Most jellies are made from fruits, but any leaves with fragrant oils can be used as a base, mints being the best example. For most preparations, select firm ripe fruit. Some fruits such as grapes produce better jelly from a mixture of ripe and unripe fruits.

Wash the fruits and remove blossom ends and stems. Cut up large fruits. Crush soft fruits to start the release of juice. Add water and cook until very soft or until all seeds are free from the pulp. Pour into a wet jelly bag and drain. Squeezing the bag increases quantity but reduces clarity of the juice.

Accompanying recipes are based on the use of commercial powdered pectin. But, depending on ripeness and type, some fruits may not need pectin. To determine the need for pectin, mix 1 tbsp each of juice and alcohol (grain or wood). If a solid mass forms, no additional pectin is needed. If flakes or a loose mass forms, add pectin. Slightly underripe fruits are generally richer in pectin than ripe ones.

Jelly Recipes

Note: All recipes except grape require pectin.

Fruit	*Approx. amount (cups)*	*Water (cups)*	*Approx. simmer time (min)*	*Juice (cups)*	*Sugar (cups)*	*Lemon*	*Yield (cups)*
Barberry/Apple	6/3	1	20	4	3	none	4
Blackberry, Dewberry	8	none	3	3½	5	none	6
Blueberry, all types	11	1	10	5½	7	¼ C	9
Buffaloberry	8	1	10	4	6	none	7
Cherry	7	½	10	3½	4½	none	5
Currant	14	1½	10	6	6	none	8
Grape (use no pectin)	8	½	10	4	4	none	6
Huckleberry	11	1	10	5½	7	¼ C	9
Indian Fig	6	2½	20	4	4	½ C	6
Mint	1½ *	3½	**	3	4	¾ C	5½
Mountain Ash	8	4	10	4	7	¼ C	7
Mulberry, Red	8	2	20	4	5½	none	6
Plum, American	8	1½	20	6	6	3 tbsp	8
Plum, Beach and Flatwood	8	1½	20	6	8	3 tbsp	8½
Prickly Pear	6	2½	20	4	4	½ C	6
Raspberry, Black	14	1	10	5	6½	none	7
Raspberry, Red; Wineberry; Thimbleberry	10	1	5	4	5½	none	6
Rose Hips	6	2	25	4	7	none	7
Salal	6	2	20	5	5	none	7
Serviceberry	6	4	20	4½	3	½ C	6
Thornapple	8	4	10	4	7	¼ C	7
Violet Blossom	4	†	‡	2	4	¼ C	4

*Chopped leaves **Quick boil; let stand 10 min. †3 C boiling water ‡Infuse 24 hr.

You can substitute liquid pectin or apple juice for powdered pectin, or you can boil the juice down until the jelly temperature reaches 105°C (220°F).

Measure the specified volume of juice in a large kettle that will allow the rolling boil required for jelly making. Stir in pectin and lemon juice, if indicated in the recipe. Bring to a full boil with constant stirring. Stir in sugar and bring to a rolling boil. Boil hard for one minute, remove from heat, and skim off foam. Immediately pour into hot, sterilized jars. When jelly is set, cover the surface with at least ⅛ inch of hot, melted paraffin. Remove any bubbles and make certain a complete seal is formed with the jar.

For the recipes in the accompanying jelly table, amounts of water and sugar will vary according to the individual batch of fruit, desired consistency of the jelly, and your taste preferences.

Jams. Jams are made from whole fruits, cooked to a thick syrupy consistency. Select fully ripe fruits, and prepare no more than 3–4 quarts of fruit in one batch.

Wash and drain fruit. Remove pits, if present. Seeds of species such as black-

Jam Recipes

Fruit	*Approx. amount*	*Special procedures*	*Fruit pulp (cups)*	*Sugar (cups)*	*Other*	*Yield (cups)*
Barberry	5 C	Crush in 1 C water; cook 20–30 min; sieve seeds	3	3¼	none	4
Blackberry	2 qt	Crush; sieve seeds; no water	5	7	none	7½
Blueberry	1½ qt	Crush thoroughly; no water	4	4	2 tbsp lemon	5½
Gooseberry	2½ qt	Remove ends; grind; no water	5½	7	none	8½
Ground Cherry	1 qt	Halve and crush; 1 cup water	4	4½	¼ C lemon	5½
Grouseberry	1½ qt	Crush thoroughly; no water	4	4	2 tbsp lemon	5½
Huckleberry	1½ qt	Crush thoroughly; no water	4	4	2 tbsp lemon	5½

Fruit	*Approx. amount*	*Special procedures*	*Fruit pulp (cups)*	*Sugar (cups)*	*Other*	*Yield (cups)*
Mayapple	2 qt	Crush in ½ C water; cook gently 20 min; colander	4	4	⅛ tsp salt	5½
Mulberry, Red	2 qt	Crush; ½ C water	4	3	none	5
Persimmon	2 qt	Halve; colander; no water	4	3	none	5
Plum, Amer.	4 qt	Pit; chop fine; ½ C water	6	8	none	9½
Plum, Beach and Flatwood	4 qt	Pit; chop fine; ½ C water	6	10	none	10½
Raspberry, Wineberry, Thimbleberry (See Blackberry)						
Salal	1½ qt	Crush and sieve; no water	3¾	5	½ C lemon	6
Sea Grape	2 qt	Crush in 2 C water; cook 15 min; colander seeds	5	2	none	5
Serviceberry	1 qt	Chop with 2 oranges; grate orange peels; water to cover	4	3	5 tbsp lemon	5½
Strawberry	2 qt	Crush; sieve seeds; no water	5	7	none	7½

berries and grapes may be strained out during the process. Chop, grind, or crush the fruits as indicated in the accompanying jam recipe table. Put in a saucepan, add water (if called for), and simmer 8–10 minutes—longer if specified. Measure fruit pulp into a large saucepan and add pectin. Bring to a full boil with constant stirring. Stir in sugar and other ingredients. Boil hard for 1 minute. Skim off foam. Ladle the jam into hot, sterilized jars to within ¼ inch of top. Seal with paraffin or airtight lids. If you use canning jars with 2-piece lids, sterilize the filled, loosely capped jars in a canner after you fill them.

For jams without commercial pectin, boil prepared fruit pulp with an approximately equal volume of sugar for about 30 minutes. Pack and store as above.

Uncooked jam can easily be prepared from many fruits by grinding or blending 2 cups of fruit with 4 cups of sugar. Let stand 30 minutes. Bring to a boil one package of powdered pectin in 1 cup of water. Stir liquid into fruit and sugar. Pour into sterilized jars and cover. Leave at room temperature for one day before refrigerating or freezing. Use within 3 months.

Pies. Pie fillings can be as simple as fruit and sugar, but usually additional ingredients will enhance the quality. If the fruit is bland, add lemon juice; if dry, add 2 or 3 tbsp water. Vary the amounts of flour and sugar according to juiciness and sweetness. Spices may add zest. Experiment with the extras. The accompanying pie recipe table gives general, not absolute, quantities.

Nine-inch pies will require 3–4 cups of fruit unless other ingredients add significantly to the volume of the filling. For most pies, pour the fruit into the pie shell. Then mix the flour, sugar, lemon juice, water, and salt as called for and pour over the fruit. Top with spices and butter. Fruits such as huckleberries make better fillings if floured before going into the pie shell. Once again, experience or a detailed recipe book will help you arrive at the best procedure.

Bake pies at 190–205°C (375–400°F) for 40–50 minutes, unless you partially cook the fruit and other ingredients before putting them into the pie shell. For baking next to a campfire the temperature is right if you can hold your hand for

Pie Recipes

Fruit	*Amount (cups)*	*Sugar (cups)*	*Lemon juice*	*Flour*	*Other ingredients*
Blackberry	4	1	none	3 tbsp	2 tbsp butter
Blueberry	4	1	1½ tbsp	3 tbsp	½ tsp nutmeg, 2 tbsp butter, mix berries with flour
Currant	2	2	none	2 tbsp	2 beaten eggs

Fruit	*Amount (cups)*	*Sugar (cups)*	*Lemon juice*	*Flour*	*Other ingredients*
Elderberry	3½	1½	4 tbsp	2 tbsp	2 tbsp butter
Ground Cherry	3	¾	3 tbsp	none	½ tbsp ground cloves, 2 tbsp butter
Huckleberry	4	1	1½ tbsp	3 tbsp	½ tsp nutmeg, 2 tbsp butter, mix berries with flour
Japanese Knotweed	4	1½	none	4 tbsp	3 beaten eggs, ¾ tsp nutmeg
Mayapple	3 (halves)	¾	6 tbsp	none	½ tsp each, ground cloves and cinnamon
Mountain Ash	3	1¼	1 tbsp	2 tbsp	½ tsp cinnamon, 2 tbsp butter
Mulberry, Red	3	1	none	4 tbsp	2 tbsp butter
Pawpaw	6 large, sliced fruits	1	4 tbsp	none	1 tsp cinnamon, ½ tsp allspice, 2 tbsp butter
Plum	1½ sliced	1½	none	4 tbsp	1½ C sliced peaches, 2 tbsp butter
Raspberry, all	4	1	none	2 tbsp	½ tsp cinnamon, 2 tbsp butter
Serviceberry	4	¾	1½ tbsp	3 tbsp	½ tsp cinnamon or nutmeg, 2 tbsp butter
Spanish Bayonet	3 pulp	¾	3 tbsp	none	½ tsp cinnamon, ¼ tsp ground cloves or nutmeg, 2 tbsp butter
Strawberry	4	¾	none	4 tbsp	
Wineberry	4	1	none	2 tbsp	½ tsp cinnamon, 2 tbsp butter

Triple Warmer 5

"Outer Gate" - Wai Guan



Luo Connecting Point
Master Point of the Yang Regulator Channel
Coupled Point of the Belt Channel

Location: About two fingers width above the wrist crease on the outsi arm.

Functions: Regulates the Yang Regulator Channel and Belt Channel, tonifies and consolidates Protective (Wei) Chi, releases exterior hot and cold conditions, helps circulate stagnant Chi in the channels.

Indications: Common cold with alternating chills and fever, high fevers, pneumonia, deafness, migraine headaches, paralysis, stiff neck.

Pericardium 6

"Inner Gate" - Nei Guan



Luo Connecting Point
Master Point of the Yin Regulator Channel

Location: About two fingers width above the wrist crease on the i the arm, between the two prominent tendons.

Functions: Calms the heart and spirit, regulates the Chi, opens and relaxes the chest, regulates and harmonizes the stomach, regulates the liver, relieves pain.

Indications: Rheumatic heart disease, shock, angina pectoris, palpitations, chest pain, asthma, shortness of breath, tightness or fullness in the chest, spasm of the diaphragm, vomiting, stomach ache, abdominal pain, morning sickness, motion sickness, migraine headaches, hysteria, anxiety, irritability, insomnia, seizures, swollen and painful throat, painful menses or nausea with period.

Large Intestine 11

"Crooked Pond" - Qu Chi



He Sea, Earth Point
Ghost Point

Location: When the elbow is flexed, in the depression at the outer and upper end of the elbow crease.

Functions: Cools heat, clears fire, drains dampness, eliminates wind and exterior conditions, regulates and moistens large intestine.

Indications: Arthritic pain in the arms, paralysis, hypertension, high fever, anemia, allergies, skin problems, Parkinson's Disease. Main point for skin diseases; main point for high fever.

not more than 8–10 seconds where the pie will be placed. In situations where heat may be uneven, rotate the baking pie a part of a turn every few minutes. On a campout few diners will complain even if the pie isn't cooked to perfection.

Grains, nuts, and seeds. These fruits, like the fleshy fruits, generally ripen late in the growing season. Grains, nuts, and seeds are usually high in proteins and oils, making them valuable wild foods. Oily seeds and nuts may be used in many ways: Chopped or sliced, they serve well in baked goods and preserves and with green vegetables. They can be eaten fresh or pressed for oil extracts. Most people have tried hickory nuts, walnuts, and—perhaps among westerners—pinyon nuts. But these few most popular nuts are just the beginnings of nature's grain, nut, and seed bounty.

If you forage close to civilization, abandoned and disturbed sites will provide seeds of common weeds such as lamb's quarters, amaranth, and purslane. Conduct experimental harvests after the seeds are fully formed but before they have fallen from the plants. Cut whole plants and dry them on a cloth. When dry, the seeds can be shaken out and separated from other plant parts. This is labor-intensive harvesting, but it can be fun.

With dozens of grasses, you can separate grains from their hulls by rubbing them between your hands or rolling or pounding them lightly with a rolling pin between two towels on a hard surface. Use either a natural breeze or an electric fan to blow the hulls away as you pour the mixture of hulls and grains from a height of several feet into a container. Here are two other winnowing methods: (1) Shake the seeds and chaff in a deep container or sack, causing the denser seeds to settle to the bottom while the hulls and other light debris rise to the top. (2) Also, you can shake the mixture in water, causing the seeds, which are heavier, to sink and other materials to float. Experimentation will yield the most effective process for the seeds you have at hand.

You can grind seeds into flour the old way with stones, but a modern blender or food mill makes the task much faster. Substitute your wild flour for some of the commercial flour in any recipe. You will soon concoct some favorite blends. Some ground-up seeds also make a pleasant boiled gruel.

Little need be said about the various nuts in addition to the comments you'll find on each species later in this book. But here are a few general tips: When collecting hickory nuts and walnuts, search out trees that produce large nuts because nut cracking is too much effort to make small nuts worthwhile. The husks of hickory nuts are easy to remove. Those of the walnut must be crushed and rubbed off. If you take the trouble to remove husks in the field, you'll eliminate a stain and mess at home. Drying the nuts for at least a month makes nutmeat extraction easier.

Plant foods of the Indians

As the big-game hunting phase of American Indian history evolved into the hunting/gathering phase, wild plants became an increasingly important part of the Indian diet. Inland tribes in particular could no longer sustain themselves almost wholly on game within tribal territory, and infringement on territory of competing tribes posed a more sudden threat to life than malnourishment did. The successful tribes learned to use the plants of their region in hundreds of ingenious ways. Overall, Indians used more than 250 species of wild fruits alone.

The first cultivated crop in the Southwest was probably sunflower. But well before that crop, several thousand years B.C., Mexican Indians began to cultivate upland vines and grasses that bore goodly quantities of edible fruits and seeds. From these efforts came many forms of squashes, pumpkins, and gourds and six species of Indian-cultivated corn with more than 150 varieties. Later, Indians domesticated beans that through the centuries became five species with many color varieties. Through sound agricultural practices, Indians developed bean varieties that thrived in the many climates from Mexico to Maine. In various parts of the country, Indians also began cultivating peanuts, white and sweet potatoes, chocolate, vanilla, sunflower, Jerusalem artichokes, and other plants.

Agriculture gave the Indians more reliable food sources and, therefore, more control over their lives. Yet many tribes continued to spend much of the year away from their summer settlements by taking advantage of a sophisticated system of wild food harvesting. For example, cultivated crops accounted for only about 25 percent of the Apaches' food.

Harvesting game and wild plants dictated a nomadic life with extensive knowledge of nature. The tribes learned to harvest crops such as berries and wild rice at very specific stages to minimize losses to wildlife and natural shedding.

In the dry Southwest, sparse vegetation resulted in intensive harvesting. And Indians naturally learned to favor high-calorie foods. Saguaro fruits provided the first succulent, sweet food of the summer for the Pimas and Papagos. In addition to high sugar content, the saguaro fruits offer high amounts of fat, protein, and vitamin C. Unfortunately, today as in early times, the dried fruits become infested with fly larvae and so can't be kept long. Thus, eating the fruits, like harvesting, is seasonal. Since harvesting does not destroy the saguaro and since plenty of seeds are left behind for reproduction, intensive use over the centuries has had little effect on the saguaro population.

Other desert plants including prickly pear, agave, Spanish bayonet, and the mesquite and screw beans provided important fleshy foods. A few plants such as pigweed, purslane, and tumbleweed provided greens. To the Sonoran desert Indians, mesquite and screw beans were nutritionally more important than corn. Generally, the edible seeds used by the desert tribes came from more than 50 species of grasses. Gathering them was extremely tedious. Several hours of work often provided only a cupful of seeds that served more as a flavoring than as a nutritional ingredient.

In arid regions, the Indians employed as little water as possible when preparing foods. Many foods were prepared from dried ingredients which were soaked and then baked or roasted. Early Indians boiled foods by placing hot stones in water-filled watertight baskets or hides. Later, ceramic pots came into use. Because of the mealy nature and bland taste of the major edibles in the Southwest, Indians supplemented the flavor with herbs, salt, sugar, onions, and chili.

In less arid regions, Indians made extensive use of hundreds of plants. Roots, shoots, and leafy foods were often cooked with oils from animals, nuts, acorns, and sunflowers. Most inland tribes lacked access to salt but employed flavor accents such as mints, bearberry, spicebush, onions, leeks, and partridgeberry. Sweets came from maple sugar and many fresh and dried fruits.

To help ensure good harvests, Indians gave special care to many native plants in their natural settings. These included rice, water lilies, blackberries, cherries, currants, mulberries, oaks, hickories, walnuts, beeches, and chestnuts.

By the time the Pilgrims landed, all northeastern tribes except those of eastern Maine employed agriculture. This involved burning and clearing land, followed by the planting of native and introduced crops. Native plants included strawberries, grapes, plums, Jerusalem artichokes, and milkweed. Large fields were planted with the "three sisters"—corn, beans, and squashes (including pumpkins) introduced from the Southwest.

For some northern tribes rice was the staple food, often served with maple sugar. Family groups staked out fields for harvesting one or two weeks before the grains ripened. They harvested most of the crop by boat or canoe using two sticks—one to bend the stalks over the canoe, the other to sweep the grains off the stalk. Skilled harvesters made only the ripe grains fall. The complete crop was taken in several harvests a few days apart. Yet Indians took care to leave enough grains to produce the next year's crop. A canoe full of grain was considered a good day's work. After gathering came a complex process of drying, parching, pounding, winnowing, and a final treading to remove the last bits of the hulls before storage in bags.

In the Northeast, maple sugaring was a family project. Each family had its own reserved woodland dominated by sugar maples (sugar bush) with a sugaring lodge and a smaller storage lodge. An average camp with 900 taps in trees would obtain several hundred pounds of sugar. Sugaring was especially difficult before the introduction of iron kettles. Till then the Indians boiled sap by immersing hot stones into hide or bark containers and then reheated the stones as they cooled. After three to four weeks of maple sugaring, the family returned to their village with all the sugar they could carry. They stored the rest underground.

Today, we still use many Indian food processing techniques. For example, the Indians parched or thoroughly sun-dried grains and then stored them until grinding them just before use. Stone grinding, touted by commercial bakeries today, was the only method available to the Indians. Beans, roots, and fruits were sun-dried. For an energy rich trail food, Indians made pemmican, consisting of dried berries, tallow, and meat. This combination was usually stuffed into a cleaned intestine of a large game animal and hung to dry. The Indians also gave us techniques of barbecuing, pit steaming, and baking, as well as dishes such as succotash, bannock, and hominy.

Colonists introduced many food plants to North America. Many came by intent. Others were unwittingly introduced in the soil ballast of ships. And many of these foreign plants established themselves quickly. Today's Pimas and Papagos of Arizona may include in their diets lamb's quarters, curly dock, and dandelion introduced in the East by the colonists.

Nutrition

Media advertisements give the impression that highly refined, vitamin enriched foods are the most nutritious. Vitamins are added to compensate for those lost in processing. Next come more additives to extend shelf life. Only the food companies know how it's all prepared. Certainly food additives have some merit in today's hurry-up lifestyle, but it's doubtful that they improve on nature.

Wild foods aren't advertised since they're free for the picking. Yet wild plants are just as tasty and nutritious as store-bought produce; often more so since they're fresh and unadulterated. Nutrition, the process of digestion and utilization of foods, is the same regardless of whether the food is wild or cultivated. The more we know about nutrition, the more assurance we have for balancing our diet.

You can think of food as body fuel. The energy produced by food is measured in calories. An adult male requires about 18 calories a day, per pound of body weight. Women require somewhat less; children and adolescents, somewhat more. Strenuous exercise can increase requirements upwards of 50 percent, and exposure to cold also increases caloric needs. Thus a 175-pound man might burn a little over 3,000 calories during a 24-hour period of normal activities and burn over 5,000 calories climbing a mountain in winter.

It's impossible for us to eat exactly the right amount of food at the rate we need it, so we all carry reserves of food energy in our bodies. The most readily available energy is stored in muscles and liver in the form of animal starch, or glycogen. When energy is needed, this starch can be quickly converted to sugar. Fat, the body's secondary energy reserve, takes longer to break down into a useable source of energy. But the fat reservoir is larger. Even slim people carry enough fat to sustain life for two weeks without additional food. Fat is the most concentrated form of food energy and contains about 3,500 calories per pound.

What we eat is just as important as how much. All food contains three primary nutritional building blocks in addition to water. These are protein, fats, and carbohydrates. The enzyme action of our digestive system requires a combination of these three substances in order to function properly. Thus a knowledge of them will help you practice good nutrition and supplement your diet with wild plants in the most beneficial way.

1. ***Protein.*** This is the only substance that can supply the amino acids necessary for building and maintaining body tissue. Protein not needed for tissue is converted to sugar and used for energy, or further converted to fat and stored. Protein in its original form cannot be stored by the body, and neither sugar nor fat can be reconverted to protein. Thus our bodies need a constant protein supply. Nutritionists recommend that 15 to 20 percent of caloric intake come from protein.

Protein also promotes the oxidation (burning) of fats and sugars for energy. An adult needs roughly a half gram of protein a day per pound of body weight; more for growing youngsters and people who are sweating heavily. Most Americans eat more protein than they need.

Although all foods contain some protein, the most significant amounts are provided by animal sources such as meat, milk, eggs, fish, and poultry. Protein from these sources is complete and contains all amino acids necessary in the diet. This is not true of vegetable protein. Each plant species is unique in the amounts and types of amino acids it provides, and no single species supplies all of the essential ones. Incomplete proteins from two or more species, however, may be combined to form a complete protein. Beans and corn are complementary in this respect, and the combination is a popular one when cooked with tomatoes. Plant and animal protein combinations also complement nicely. In this case it doesn't take much meat to satisfy human requirements. Orientals have long used poultry and fish primarily as a condiment, combined with vegetables to provide complete and adequate protein.

2. ***Fats.*** These should provide another 15 to 20 percent of your caloric intake. Eggs, nuts, milk, cheese, butter, and oils are important sources of fats. Most people feel that fatty foods "stick to your ribs" longer, which is just another way of saying that it takes longer to digest them. This is also true of protein, so the traditional breakfast of bacon and eggs, heavy on fats and protein, sticks to the ribs. A normal diet containing meat and milk usually provides a full quota of fat.

3. ***Carbohydrates.*** About 65 percent of your caloric intake should come from carbohydrates. And wild plants are primarily valuable for their carbohydrates. For dietary purposes, carbohydrates fall into two groups: starches and sugars. Foods high in carbohydrates include grains, vegetables, and fruit. Of these, vegetables are especially important because they are a secondary source of protein. The traditional breakfast of bacon and eggs usually includes toast and jelly, the sugars from both providing a quick shot of energy. When that's used up, the fats and proteins will be ready to provide additional fuel. Since carbohydrates are digested faster than fats and proteins and are then burned up quickly, don't be surprised if snacks of cookies, crackers, and candy don't satisfy your hunger very long. Nuts would do a better job since they also contain significant amounts of protein.

Vitamins and minerals. Vitamins and minerals in small amounts are essential for good nutrition. Nature has provided amply in the foods we eat, and if we eat the right foods, the vitamins and minerals will be included. The table, below, shows recommended adult daily requirements. Some people (including female adolescents and pregnant and lactating women) require somewhat more.

Recommended Dietary Allowances

	MINERALS			*VITAMINS*				
	Calcium (mg)	*Phosphorus (mg)*	*Iron (mg)*	*Vitamin A (IU)*	*Thiamine (mg)*	*Riboflavin (mg)*	*Niacin (mg)*	*Ascorbic acid (mg)*
Male	800	800	10	5,000	1.4	1.6	18	45
Female	800	800	18	4,000	1.0	1.2	13	45

Source: *Recommended Dietary Allowances,* National Academy of Sciences, Washington, DC

A balanced diet. Vital over the long term, a balanced diet is also important over short periods. Insufficient protein intake, if extended over several days, will cause fatigue, even if you consume enough carbohydrates. In addition, a disproportionate amount of fats in relation to carbohydrates usually results in an upset stomach. This is nature's way of acknowledging poor eating habits. Achieving proper balance, however, is easy if you remember this simple proportion: Measured in calories, food consumption should total about $^1/_5$ protein, $^1/_5$ fats, and $^3/_5$ carbohydrates.

If you want to fine tune your diet, the Appendix table on page 274 should help. The table was extracted from the Department of Agriculture's *Handbook of the Nutritional Contents of Foods.* Though with only a limited listing of wild edibles, it is the most comprehensive and reliable reference available. The table can help you balance your diet, because wild vegetables, fruits, and nuts are shown together with supermarket foods such as beef, milk, and eggs. Food values for wild plants not included are often approximately the same as those of similar cultivated plants. For example, fiddleheads would approximate asparagus in food value.

In addition to the energy content of foods, we've also included values for vitamins and minerals. Foods vary greatly in their nutritional content, and we've included this information to dramatize the need for a balanced diet.

Preparation methods. Nutritional values of fruits and vegetables depend greatly on preparation. Fresh green leaves or shoots that must be cooked in two changes of water to make them palatable lose much nutritional value compared to those that can be eaten fresh. Also, the longer fresh vegetables are cooked, the greater the loss of vitamins and minerals to the water. Proteins and carbohydrates are less affected by cooking. So for the sake of nutrition, the preferred order of preparation options is raw, quick-cook or steam, bake, boil.

Other plant guides

Since it is impossible to distinguish among all 20,000 North American species in this or any other book, you may also want to refer to identification guides devoted to your own region or state. There are many wildflower guides available, yet even these treat only the most common species.

Here's a sampling of good regional plant guides:

- *The New Britton and Brown Illustrated Flora of the Northeastern U.S. and Adjacent Canada* by H. A. Gleason, third printing, 1963.
- *Manual of Vascular Plants of Northeastern U.S. and Adjacent Canada* by H. Gleason and A. Cronquist, 1963.
- *Manual of Vascular Flora of the Carolinas* by A. Radford, H. Ahles, and C. Bell, 1964.
- *Flora of the Pacific Northwest* by C. Hitchcock and A. Cronquist, 1976.
- *A California Flora and Supplement* by P. Munz, 1968, 1973.
- *Manual of the Vascular Plants of Texas* by D. Correll and M. Johnston, 1970.
- *Rocky Mountain Flora* by W. Weber, 1976.

Good less-technical guides include these:

- *Newcomb's Wildflower Guide* by L. Newcomb, 1977.
- *The Audubon Society Field Guide to North American Wildflowers (Eastern Region* by W. Niering, 1979; *Western Region* by R. Spellenberg, 1979).

For North American trees, we recommend *The Complete Trees of North America* by T. Elias, 1980.

Key to edible-use symbols

The symbols below appear in the "Seasonal Key to Plants" that follows and later in page margins of texts on each plant. After you've read the explanations below, you'll probably find the symbols distinctive enough to make repeated reference to this page unnecessary. You can exploit the symbols in either of two ways based on (1) your general interest in a plant's range of edible uses and (2) your desire to locate plants with specific edible uses.

🚶 **Trail nibble:** plant part eaten as picked along the trail

✗ **Salad:** used raw in tossed salad (seldom steamed)

🍲 **Cooked "green" vegetable:** boiled or steamed greens, shoots, buds, flowers, or young fruits used as a vegetable

🥕 **Underground vegetable:** roots, tubers, corms, bulbs, rhizomes prepared as vegetables, usually by boiling or roasting

🍳 **Fritter:** plant part dipped in batter and deep fried

🍎 **Raw fruit:** fruits eaten uncooked, though perhaps with toppings

🥧 **Cooked fruit:** true fruits or nonfruit parts (such as rhubarb) used in pies, baked goods, and other dessert recipes

🫙 **Jams, jellies, sauces:** made from fruits

🫗 **Syrup and sugar:** such as made from maple sap

🍬 **Candy:** plant parts or substances that may or may not contain their own sugar that are boiled in sugar syrup to produce a confection

🌾 **Grains:** for cereal and for cooking whole, such as rice

🌰 **Nuts, nutlets, large seeds:** used whole and for oil extract

XXX **Flour or meal:** grains, nuts, other seeds, or starchy roots from which flour or meal can be ground

☕ **Hot beverage:** from tea or coffee-like preparations

🥤 **Cold beverage:** fruit juices or originally hot tea or coffee-like beverage that has cooled

🥒 **Pickle:** from pickling recipes

🧂 **Seasoning:** flavoring from ground, grated, or cooked-whole parts

🥣 **Thickener:** used like cornstarch to thicken soups

🚦 **Caution:** minor reaction may result from eating wrong part, or too much of right part, or eating at wrong stage

☠ **Poisonous:** severe reaction results from eating wrong part, or eating at wrong stage

Seasonal key to plants

Spring

Page / Plant	Region	Habitat	Edible Uses
FERNS			
58 Ostrich fern *Matteucia struthiopteris*		swamps, bottomlands, stream banks, ponds	🧍 🍴 🍲
HERBS: MONOCOTS			
Flowers many in dense heads			
58 Wild onion *Allium cernuum*		dry woodlands, ridges, rocky slopes, prairies	🌿 🧂 🍴 🍲 🥒
60 Wild garlic *Allium canadense*		open woodlands, fields, prairies	🌿 🧂 🍴 🍲 🥒
60 Wild leek *Allium tricoccum*		moist woodlands	🌿 🧂 🍴 🍲 🥒
62 Corn lily *Clintonia borealis*		rich woodlands, thickets	🍲 🍴
Flowers single, leaves threadlike			
62 Asparagus *Asparagus officinalis*	 Introduced and grows wild. Widespread.	roadsides, disturbed sites	🍲 🚦

Page / Plant	Region	Habitat	Edible Uses
	Flowers in elongate clusters		
64 Eastern camass *Camassia scilloides*		wet meadows, fields, moist open woods	🥕 🍴
	Vines		
64 Common greenbrier *Smilax rotundifolia*		roadsides, disturbed woodlands	🚶 🍴 🍲
66 Bullbrier *Smilax bona-nox*		roadsides, fields, open woodlands	🚶 ☕ 🥤 🍴 🥣 🍲 🛍 🫙
66 Carrion flower *Smilax herbacea*		roadsides, fields, margins of woodlands	🚶 ☕ 🥤 🍴 🥣 🍲 🛍
	Large semiaquatic		
68 Cattail *Typha latifolia*		ditches, margins of ponds and lakes	🚶 🥕 🍴 🍲 🛍
68 Narrow-leaved cattail *Typha angustifolia*		ditches, margins of ponds and lakes	🚶 🥕 🍴 🍲 🛍
	Small grasslike		
70 Hard-stem bulrush *Scirpus acutus*		edges of ponds, lakes, streams and marshes	🚶 🥕 🍴 🍲 🛍 🍶
70 Great bulrush *Scirpus validus*		edges of ponds, streams, marshes	🚶 🥕 🍴 🍲 🛍 🍶

Conception Vessel 22

"Heaven's Chimney" - Tian Tu



Intersecting Point of the Yin Regulator Channel on the Conception Vessel, Window of the Sky Point

Location: At the top of the breastbone (sternum) in the V-shaped indentation (suprasternal notch). Press in and downward at a forty-five degree angle.

Functions: Cools the throat and clears the voice, facilitates and regulates movement of lung Chi, frees the breath and helps restore the proper functioning of the lungs and bronchi, helps open Conception Vessel (Functional Channel).

Indications: Asthma, bronchial asthma, bronchitis, coughing, pharyngitis, goiter, hiccups, nervous vomiting, hoarse voice, spasms of the esophagus, diseases of the vocal cords, sore throat.

Conception Vessel 17

“Central Altar” - Tan Zhong

Front Mu-Alarm Point of the pericardium, Influential Point of Chi of the body
Sea of Chi Point, Master Point of the Middle Tan Tien

Location: On the frontal midline at the level of the fourth intercostal space, between the nipples.

Functions: Regulates the lungs and the Upper Warmer, tonifies Ancestral Chi, opens and relaxes the chest, diffuses lung Chi, regulates and tonifies Chi, transforms phlegm.

Indications: Pulmonary tuberculosis with shortness of breath, bronchitis, asthma, bronchial asthma, chest pain; all breast problems such as mastitis, insufficient lactation, breast abscesses, wheezing, chest pain, labored breathing, palpitations, difficulty swallowing food, anxiety.

Conception Vessel 12

"Middle Cavity" - Zhongwan (Solar Plexus)



Front Mu-Alarm Point of the stomach, Influential point of all yang organs

Location: Approximately midway between the navel and the top joint of the xiphoid process.

Functions: Regulates the stomach Chi and yin, regulates, strengthens and tonifies the spleen Chi and yang, regulates the Middle Warmer, reduces digestive stagnation, tonifies nutritive Chi, regulates Chi and blood, redirects rebellious Chi downwards, clears stomach fire and heat, calms the fetus, controls the aura.

Indications: Acute or chronic gastritis, stomach and duodenal ulcers, prolapsed stomach, acute intestinal obstruction, stomach ache, vomiting, abdominal distention, diarrhea, constipation, acid regurgitation, indigestion, hypertension, mental diseases.

HERBS: DICOTS

Flowers small, inconspicuous

Page/Plant	Region	Habitat	Edible Uses
72 Pigweed *Amaranthus retroflexus*	 Introduced and grows wild. Widespread.	waste areas, roadsides, abandoned land	🍴 🍲 🫙
72 Green pigweed *Amaranthus hybridus*	 Introduced and grows wild. Widespread.	fields, roadsides, disturbed sites	🍴 🍲 🫙
74 Lamb's quarters *Chenopodium album*	 Introduced and grows wild. Widespread.	vacant lots, roadsides, cultivated land	🍴 🍲 🫙
74 Poverty weed *Menolepis nuttalliana*		dry salty or alkaline soils	🍲 🫙

Flowers tiny, stems & leaves fleshy

Page/Plant	Region	Habitat	Edible Uses
76 Glasswort *Salicornia europaea*		salt marshes, sea coast, alkaline soils	🏃 🍴 🍲 🥒
76 Russian thistle *Salsola kali*		sandy beaches, dry alkaline soils	🍲 ☠

Stinging hairs on stem

Page/Plant	Region	Habitat	Edible Uses
78 Stinging nettle *Urtica dioica*		roadsides, trailsides, stream banks	☕ 🍲 🚦

Page/Plant	Region	Habitat	Edible Uses
	Flowers tiny, leaves basal		
78 Plantain *Plantago major*	 Introduced and grows wild. Widespread.	yards, roadsides, disturbed sites	☕ ✕ 🍲 ⊠
	Flowers white		
80 Shepherd's purse *Capsella bursa-pastoris*	 Introduced and grows wild. Widespread.	yards, vacant lots, roadsides	🧂 ✕ 🍲
80 Toothwort *Dentaria laciniata*		moist woodlands, ravines, floodplains	⛏ 🧂
82 Peppergrass *Lepidium virginicum*	 Introduced and grows wild. Widespread.	fields, vacant lots, roadsides	🧂 ✕ 🍲
82 Field cress *Lepidium campestre*		fields, vacant lots, roadsides, waste areas	🧂 ✕ 🍲
82 Field pennycress *Thlaspi arvense*	 Introduced and grows wild. Widespread.	fields, vacant lots, disturbed soils	✕ 🍲
84 Garlic mustard *Alliaria officinalis*		shady woodlands, trailsides	🧂 ✕ 🍲
84 Common chickweed *Stellaria media*	Introduced and grows wild; widespread in East and Midwest	yards, moist soils, woodlands, waste areas	✕ 🍲

Page/Plant	Region	Habitat	Edible Uses
84 James chickweed *Stellaria jamesiana*		mountain meadows, seepage areas, woodlands	🍴 🍲
86 Cleavers *Galium aparine*		rich woodlands, fields, edges of streams and lakes	☕ 🍴 🍲
86 Northern bedstraw *Galium boreale*		stream banks, fields, open woodlands	☕ 🍴 🍲
88 Bugleweed *Lycopus uniflorus*		wet or boggy soils, wet woodlands	🌱 🧂 🍴 🥒
88 Edible valerian *Valeriana edulis*		ditches, moist meadows, prairies, swamps	🌱 🫙
90 Wild strawberry *Fragaria virginiana*		open woodlands, fields, margins of woodlands	🚶 🍎 ☕ 🥤 🥧 🫙
90 Spring beauty *Claytonia virginica*		rich woodlands, wet fields, wooded floodplains	🚶 🌱 🍴 🍲
92 Alpine spring beauty *Claytonia megarhiza*		tundra, rocky slopes	🚶 🌱 🍴 🍲
92 Western spring beauty *Claytonia lanceolata*		high mountain slopes, moist woodlands	🚶 🌱 🍴 🍲

Page / Plant	Region	Habitat	Edible Uses
94 Miner's lettuce *Montia perfoliata*		lower mountain slopes, moist sites, springs	🚶 🍴 🍲
94 Canada violet *Viola canadensis*		bluffs, deciduous woodlands, rich soils	🚶 ☕ 🍴 🍲 🫙
96 Pale violet *Viola striata*		wooded floodplains, stream banks, meadows	🚶 ☕ 🍴 🍲 🫙
96 Pokeweed *Phytolacca americana*		disturbed soils, roadsides, woodland margins	🍲 🥒 ☠
98 Japanese knotweed *Polygonum cuspidatum*		disturbed sites, vacant lots, roadsides	🍲 🥧 🫙
	Flowers yellow		
98 Wintercress *Barbarea vulgaris*		fields, wet meadows, ditches, roadsides	🍴 🍲
100 Black mustard *Brassica nigra*		fields, yards, disturbed sites	🧂 🍴 🍲
100 Marsh marigold *Caltha palustris*		edges of streams, ponds, freshwater swamps	🍲 🥒 ☠

Page/Plant	Region	Habitat	Edible Uses
102 Evening primrose *Oenothera biennis*		prairies, fields, roadsides	🌿 🍴 🍲 🍬
102 Sow thistle *Sonchus arvensis*		roadsides, fields, rights-of-way	🍴 🍲 ☠
104 Prickly lettuce *Lactuca serriola*	Introduced and grows wild. Widespread.	fields, vacant lots, disturbed sites	🍴 🍲 🚦
104 Dandelion *Taraxacum officinale*	 Introduced and grows wild. Widespread.	lawns, yards, disturbed sites	🌿 ☕ 🍴 🍲 🍳
106 Goat's beard *Tragopogon pratensis*		roadsides, fields, disturbed sites	🌿 🍴 🍲

Flowers pink, reddish, or purple

Page/Plant	Region	Habitat	Edible Uses
106 Common milkweed *Asclepias syriaca*		fields, meadows, margins of woodlands, roadsides	🥘 🍲 🚦
108 Fireweed *Epilobium angustifolium*		ravines, clearings, woodlands	☕ 🍴 🍲
108 Alfilaria *Erodium cicutarium*	 Introduced and grows wild. Widespread.	fields, pastures, roadsides, disturbed sites	🍴 🍲
110 Live-forever *Sedum purpureum*		roadsides, disturbed sites, open woodlands	🌿 🍴 🍲 🥒

Page / Plant	Region	Habitat	Edible Uses
110 Lady's thumb *Polygonum persicaria*	 Introduced and grows wild in moist soils	low wet sites, roadsides, disturbed sites	🍴 🍲 🚦
112 Common burdock *Arctium minus*		vacant lots, roadsides, disturbed sites	🏃 🥕 🍴 🍲 🍬

Flowers purple

Page / Plant	Region	Habitat	Edible Uses
112 Salsify *Tragopogon porrifolius*		roadsides, fields, rights-of-way	🥕 🍴 🍲
114 Bull thistle *Cirsium vulgare*	 Introduced and grows wild. Widespread.	fields, meadows, roadsides, disturbed sites	🥕 🍴 🍲 ▣
114 Chicory *Cichorium intybus*	 Introduced and grows wild. Widespread.	roadsides, fields, vacant lots	🥕 ☕ 🍴 🍲
116 Henbit *Lamium amplexicaule*	 Introduced and grows wild. Widespread.	fields, yards, vacant lots, disturbed sites	🍴 🍲
116 Wood violet *Viola palmata*		wooded floodplains, rich forests, slopes	🏃 ☕ 🍴 🍲 🫙 🍶

Flowers tiny, often greenish

Page / Plant	Region	Habitat	Edible Uses
118 Orange-flowered jewelweed *Impatiens biflora*		along streams, ponds, springs, wet areas	🧂 🍲 🚦

Page / Plant	Region	Habitat	Edible Uses
118 Yellow-flowered jewelweed *Impatiens pallida*		wet meadows, moist woodlands	🧂 🍲 🚦
	Flowers orange to yellow		
120 Sheep sorrel *Rumex acetosella*		old fields, gardens, disturbed sites	🚶 ☕ 🍴 🍲 🚦
120 Sour dock *Rumex crispus*	Introduced and grows wild. Widespread.	fields, roadsides, vacant lots, disturbed sites	🍲 ▣ 🚦
TREES: CONIFERS			
122 Eastern hemlock *Tsuga canadensis*		cool moist ravines, protected valleys	☕ ▣
TREES: DECIDUOUS			
122 Yellow birch *Betula alleghaniensis*		rich woodlands, wet soils	☕ 🥤 ▣ 🫗
122 Sweet birch *Betula lenta*		open woodlands, rich soils	☕ 🥤 ▣ 🫗
124 Sassafras *Sassafras albidum*		bottomlands, open woodlands	🧂 ☕ 🥤 🍴 🥣 🫙
124 Sugar maple *Acer saccharum*		eastern deciduous forests	🌰 🥤 🫗

Summer

Page / Plant	Region	Habitat	Edible Uses
HERBS: MONOCOTS			
	Large grasses		
128 Reed grass *Phragmites communis*		edges of streams, lakes, ponds, marshes, ditches	🌱 🍴 🍲 ▣ 🌾 🫗
128 Wild rice *Zizania aquatica*		marshes, shallow ponds, lakes, streams, bays	▣ 🌾
	Small grasslike		
130 Chufa *Cyperus esculentus*		ditches, banks of ponds and streams, low wet soils	🥕 🌱 ☕ 🥤 ▣ 🍬
	Semiaquatic, flowers blue		
130 Pickerelweed *Pontederia cordata*		edges of lakes, ponds, streams, bays	🥕 🌰 🍴 🍲
132 Lance-leaved pickerelweed *Pontederia lanceolata*		shallow water of lakes, ponds, streams	🥕 🌰 🍴 🍲
	Leaves large, swordlike		
132 Sweet flag *Acorus calamus*		ditches, ponds, swamps, lakes and streams	🥕 🧂 🍬

Page/Plant	Region	Habitat	Edible Uses
	Flowers white, showy		
134 Spanish bayonet *Yucca baccata*		dry slopes, sandy soils	🍎 🌰 ☕ 🥤 🍴 🍲 🥧
134 Soapweed *Yucca glauca*		prairies, roadsides, pastures	🍴 🍲 🥧
	Flowers orange, showy		
136 Common day lily *Hemerocallis fulva*		vacant lots, abandoned home sites, roadsides	🍃 🍴 🥣 🍲 🌼
	Flowers blue		
136 Western camass *Camassia quamash*		wet mountain meadows	🍃 🍴
	Flowers greenish-yellow		
138 Indian cucumber *Medeola virginiana*		moist woodlands, bogs, swamps	🏃 🍴 🥒
HERBS: DICOTS			
	Stems large, fleshy		
138 Indian fig *Opuntia humifusa*		rocky bluffs, sand dunes, dry grasslands	🍎 🥣 🍲 🌾 🥧 🫙
140 Prickly pear *Opuntia phaeacantha*		canyons, valleys, hills, rocky and sandy soils	🍎 🥣 🍲 🌾 🥧 🫙

Page/Plant	Region	Habitat	Edible Uses
	Flowers white		
140 May apple *Podophyllum peltatum*		rich woodlands, shaded roadsides, meadows	🍎 🥤 🥧 🫙 ☠
142 Bunchberry *Cornus canadensis*		bogs, moist woodlands, mountains	🏃 🍎 🥧
	Stems 4-sided, flowers white		
142 Peppermint *Mentha piperita*	 Introduced and grows wild. Widespread.	ditches, along stream banks, wet meadows	🧂 ☕ 🍬 🫙
144 Spearmint *Mentha spicata*	 Introduced and grows wild. Widespread.	wet areas, ditches, stream banks	🧂 ☕ 🍬 🫙
	Flowers violet to purple		
144 American brooklime *Veronica americana*		edges of streams, swamps, springs, ponds	✕ 🍲
	Flowers pink		
146 Marsh mallow *Althaea officinalis*		edges of salt marshes	🥕 🍳 🍲 🥒 🍬
	Flowers white		
146 Watercress *Nasturtium officinale*		springs, cool clear streams	🧂 ✕ 🍲

Mideyebrow Point

"Seal Hall" - Yin Tang



Master Point of the Upper Tan Tien
Location: At the midpoint between the two eyebrows.
Functions: Calms the spirit, activates the Crystal Room, opens the Governor Channel, draws in Cosmic Chi, eliminates wind heat.
Indications: Headache, vertigo, rhinitis, sinusitis, common cold, hypertension, infantile convulsions, sore eyes.

Conception Vessel 6

"Chi Ocean" - Chi Hai



Master Point of the Lower Tan Tien
Location: Approximately three fingers width below the navel.
Functions: Regulates Chi, tonifies Original Chi, strengthens weak kidneys, harmonizes the blood, regulates the Thrusting Route Conception Vessel, reinforces Ching Chi, enriches yin.
Indications: Neurasthenia, abdominal distention, abdominal pain, irregular menstruation, impotence, spermatorrhea, urinary retention, frequent urination, intestinal paralysis, incontinence, constipation, infertility, uterine bleeding, hernia.

Stomach 13

"Chi's Household" - Chi Hu



Location: Below the midpoint of the collarbone along the mammilary line (directly above the nipple).
Functions: Clears heat, loosens the chest, relaxes the diaphragm, regulates lung Chi.
Indications: Asthma, bronchitis, chest and back pain, hiccups.

Stomach 16

"Breast's Window" - Ying Chuang

Location: In the space between the third and fourth ribs, one rib directly above the nipple in men, slightly higher in women.
Functions: Stops pain, reduces swelling, clears heat, resolves depression, opens lungs, stops cough, relaxes chest, moves Chi.
Indications: Coughing, asthma, swelling of the breasts, chest and stomach pain, heartburn, shortness of breath, melancholy, diarrhea

Page/Plant	Region	Habitat	Edible Uses
	Flowers yellow		
148 Ground cherry *Physalis pubescens*		old fields, open woodlands, moist sites	🚶 🍎 🥧 🫙 ☠
	Flowers brownish-purple		
148 Groundnut *Apios americana*		thickets, bottomlands, moist woodlands	🌰 🥕
	Flowers blue		
150 Common breadroot *Psoralea esculenta*		prairies, plains, dry rocky woodlands	🥕 ✕ ▣ 🌾
	Low creeping plants		
150 Wintergreen *Gaultheria procumbens*		rich woodlands, clearings, poor acid soils	🚶 🍎 ☕ 🥧 🫙
152 Creeping snowberry *Gaultheria hispidula*		subalpine and alpine, northern coniferous forests	🚶 🍎 ☕ 🍲 🥧 🫙
	Leaves sheathing stems		
152 Mountain sorrel *Oxyria digyna*		high mountains, subalpine and alpine fields	🚶 ☕ ✕ 🍲
154 American bistort *Polygonum bistortoides*		along streams, wet meadows, subalpine meadows	🥕 ✕ 🍲 🌾

Page/Plant	Region	Habitat	Edible Uses
154 Alpine bistort *Polygonum viviparum*		arctic regions, alpine and subalpine slopes	🚶 🌿 ✕ 🍲 🍡

Flowers yellow

Page/Plant	Region	Habitat	Edible Uses
156 Purslane *Portulaca oleracea*	 Introduced and grows wild. Widespread.	fields, vacant lots, waste sites, gardens	✕ 🥣 🍲 xxx 🥒
156 Sunflower *Helianthus annus*	 Native in West	prairies, plains, roadsides, disturbed sites	🌰 ☕ xxx
158 Quickweed *Galinsoga parviflora*	 Introduced and grows wild. Widespread.	roadsides, yards, gardens, waste areas	🍲

SHRUBS: DICOTS

Leaves evergreen

Page/Plant	Region	Habitat	Edible Uses
158 Bearberry *Arctostaphylos uva-ursi*		higher mountains, subarctic, circumboreal	☕ 🥧
160 Salal *Gaultheria shallon*		woodlands, clearings	🚶 🍎 🥛 🥧 🫙
160 Creeping wintergreen *Gaultheria humifusa*		subalpine and alpine	🥛 🥧 🫙
160 Labrador tea *Ledum groenlandicum*		bogs, fens, heaths, northern woods	☕ 🥛 ☠

Page/Plant	Region	Habitat	Edible Uses
162 Mountain cranberry *Vaccinium vitis-idaea*		subarctic, alpine, bogs, cold seepage areas	🏃 🍎 🥤 ▣ 🥧 🫙
162 Cranberry *Vaccinium macrocarpon*		bogs, swamps, shores of cold acid lakes	🥤 ▣ 🥧 🫙
	Leaves deciduous		
164 Bog bilberry *Vaccinium uliginosum*		arctic, bogs, rocky outcrops	🏃 🍎 🥧 🫙
164 Highbush blueberry *Vaccinium corymbosum*		bogs, low wet woodlands, swamps	🏃 🍎 🥧 🫙
164 Late sweet blueberry *Vaccinium angustifolium*		mountain slopes, barrens, dry rocky soils	🏃 🍎 🥧 🫙
166 Black huckleberry *Gaylussacia baccata*		woodlands, clearings	🏃 🍎 🥧 🫙
166 Beach plum *Prunus maritima*		coastal areas, sandy soils	🏃 🥧 🫙
168 Golden currant *Ribes aureum*		along streams, ravines, washes, slopes	🏃 🍎 🥧 🫙

Page/Plant	Region	Habitat	Edible Uses
170 Wax currant *Ribes cereum*		canyons, dry ravines, prairies, hillsides	🚶 🥧 🫙
170 Subalpine prickly currant *Ribes montigenum*		along streams, ravines, washes, forests	🚶 🥧 🫙
170 Fragrant golden currant *Ribes odoratum*		prairies, open woodlands, bluffs, ravines	🚶 🍎 🥧 🫙
172 American hazelnut *Corylus americana*		thickets, woodlands	🚶 🌰 XXX 🍬
172 Beaked hazelnut *Corylus cornuta*		woodlands, hills, slopes	🚶 🌰 XXX 🍬
174 Sweet fern *Comptonia peregrina*		pastures, old fields, clearings	🚶 🌰 ☕

Leaves fragrant when rubbed

Page/Plant	Region	Habitat	Edible Uses
174 Southern bayberry *Myrica cerifera*		coastal plains, swamps, edges of ponds, barrens	🧂
176 Sweet gale *Myrica gale*		swamps, along ponds and streams	🧂 ☕

Page/Plant	Region	Habitat	Edible Uses
	Flowers white		
176 New Jersey tea *Ceanothus americanus*		open woodlands, prairies	☕
	Leaves with silvery scales		
178 Silver buffaloberry *Shepherdia argentea*		canyons, plains, meadows, river banks	🏃 🍎 ☕ 🥤 🥧 🫙
	Leaves usually compound		
180 Red raspberry *Rubus idaeus* var. *strigosus*		clearings, margins of woodlands, old fields	🏃 🍎 ☕ 🥧 🫙
180 Wineberry *Rubus phoenicolasius*		along rivers, streams, roads	🏃 🍎 ☕ 🥧 🫙
180 Thimbleberry *Rubus parviflorus*		woodlands, canyons, trailsides, stream banks	🏃 🍎 ☕ 🥧 🫙
182 Common blackberry *Rubus allegheniensis*		old fields, fencerows, edges of woodlands	🏃 🍎 ☕ 🥧 🫙
182 Black raspberry *Rubus occidentalis*		old fields, fencerows, edges of woodlands	🏃 🍎 ☕ 🥧 🫙
184 California blackberry *Rubus ursinus*		along trails, roads, canyons, fields	🏃 🍎 🥧 🫙

Page/Plant	Region	Habitat	Edible Uses
	Leaves pinnately compound		
184 Smooth sumac *Rhus glabra*		fields, open woodlands, stream banks, trailsides	🏃 ☕ 🥤 🫙 🚦
186 Squawbush *Rhus trilobata*		foothills, canyons, slopes, washes	🏃 ☕ 🥤 🫙 🚦
186 Staghorn sumac *Rhus typhina*		fencerows, roadsides, edges of woodlands	🏃 ☕ 🥤 🫙 🚦
188 Screwbean mesquite *Prosopis pubescens*		washes, riverbottoms, stream banks	🍵 🫗
188 Glandular mesquite *Prosopis glandulosa*		desert valleys, grazing lands, range	🏃 ☕ 🥤 xxx 🫗
190 American elder *Sambucus canadensis*		along streams and rivers, edges of woodlands	🥤 🍳 🥧 🫙 ☠
190 Blue elder *Sambucus cerulea*		stream banks, washes, edges of fields	☕ 🥤 🥧 🫙 ☠
TREES: CONIFERS			
192 Singleleaf pinyon pine *Pinus monophylla*		foothills, canyons, mountain slopes	🌰 xxx

Page/Plant	Region	Habitat	Edible Uses
192 Sugar pine *Pinus lambertiana*		mountain slopes	🌰 ▣

Leaves tiny, scaly

Page/Plant	Region	Habitat	Edible Uses
192 Digger pine *Pinus sabiniana*		foothills, lower mountain slopes	🌰 ▣
194 Rocky Mountain juniper *Juniperus scopulorum*		ridges, bluffs, dry rocky hillsides	🧂 ☕ 🚦
194 California juniper *Juniperus californica*		dry slopes, canyons, desert slopes	🏃 🧂 ☕
196 Utah juniper *Juniperus osteosperma*		mesas, mountain slopes, high plains	🧂 ☕ 🚦

TREES: FLOWERING

Evergreen

Page/Plant	Region	Habitat	Edible Uses
196 Sea grape *Coccoloba uvifera*		beaches, sea shores	🫙
198 California laurel *Umbellularia californica*		hillsides, flatlands, lower mountain slopes	🌰 🧂 ▣

Deciduous

Page/Plant	Region	Habitat	Edible Uses
198 Pawpaw *Asimina triloba*		river valleys, bottomlands	🍎 🥧 🚦

Page/Plant	Region	Habitat	Edible Uses
	Leaves unlobed or 1- to 3-lobed		
200 White mulberry *Morus alba*	 Introduced and grows wild. Widespread.	fencerows, roadsides, old fields	🚶 ☕ 🥧 🍬 🚦
200 Red mulberry *Morus rubra*		river valleys, floodplains, low hills	🚶 🍎 🥤 ☕ 🥧 🫙 🚦
	Flowers white, showy, early		
202 American plum *Prunus americana*		deciduous woodlands, stream banks	🚶 🍎 🥧 🫙 ☠
202 Flatwood plum *Prunus umbellata*		coastal plain; piedmont; rivers, swamps, hammocks	🚶 🍎 🥧 🫙
204 Black cherry *Prunus serotina*		mixed hardwood forests, woodlands	🚶 🍎 🥤 🥧 🫙 ☠
204 Common chokecherry *Prunus virginiana*		moist soils of roadsides, fencerows, woodland margins	🚶 🥧 🫙 ☠
206 Downy serviceberry *Amelanchier arborea*		woodlands, rocky slopes, river banks	🚶 🍎 🥧 🫙
206 Saskatoon serviceberry *Amelanchier alnifolia*		mountain slopes, hillsides, prairies, stream banks	🚶 🍎 🥧 🫙

Autumn

Page/Plant	Region	Habitat	Edible Uses
HERBS			
	Land plant, flowers yellow		
210 Jerusalem artichoke *Helianthus tuberosus*		roadsides, low wet ground, waste areas	
	Aquatic plants		
210 Lotus lily *Nelumbo lutea*		lakes, ponds, slow-moving streams	
212 Yellow pond lily *Nuphar advena*		lakes, ponds, slow streams, tidal waters	
	Semiaquatic, flowers white		
212 Arrowhead *Sagittaria latifolia*		edges of lakes, ponds, streams, ditches	
VINES			
214 Riverside grape *Vitis riparia*		edges of woodlands, streams, rivers	
214 Frost grape *Vitis vulpina*		along streams and rivers, in floodplains and thickets	

Page / Plant	Region	Habitat	Edible Uses
216 California grape *Vitis californica*		along streams and rivers, moist canyons	🏃 🥤 🍶 🥧 🫙
216 Wild potato vine *Ipomoea pandurata*		fields, fencerows, roadsides	🍃 🚦

SHRUBS

Flowers yellow, leaves simple

Page / Plant	Region	Habitat	Edible Uses
218 Common barberry *Berberis vulgaris*		fields, fencerows, roadsides, disturbed sites	🏃 🥤 🫙
218 Spice bush *Lindera benzoin*		along streams, rich woodlands	🧂 ☕
220 Desert hackberry *Celtis pallida*		desert foothills, mesas	🏃 🍎 🥧 🫙

Leaves compound, flowers white or pink

Page / Plant	Region	Habitat	Edible Uses
220 California rose *Rosa californica*		along streams and rivers, washes, canyons	🏃 ☕ 🫙 🍬
222 Wild rose *Rosa carolina*		open woodlands, fields, pastures	🏃 ☕ 🫙 🍬
222 Sweetbrier rose *Rosa eglanteria*		roadsides, old fields, fencerows	🏃 ☕ 🫙 🍬



Liver 14

"Gate of Hope" - Chi Men

Front Mu-Alarm Point of the liver
Intersecting point of the Yin
Regulator and spleen channels on the liver channel
Location: In the sixth intercostal space, directly below the nipple.
Functions: Spreads liver Chi, transforms and removes congealed blood, strengthens spleen and stomach, expands and relaxes the chest.
Indications: Difficulty in breathing, chest pain, hepatitis, enlarged liver, gall stones, pleurisy, nervous stomach, menopausal disorders, cholera, failure to discharge the placenta after childbirth.

Spleen 16

"Abdomen's Sorrow" - Fu Ai

Location: Just below the bottom edge of the rib cage on the mamillary line.
Functions: Frees bowel Chi, dispels damp and heat, opens the organs and clears Chi stagnation.
Indications: Pain in the navel region, indigestion, dysentary, constipation.

Spleen 15

"Great Horizontal" - Da Heng

Intersecting point of the Yin Regulator Channel on the spleen channel
Location: At the level with the navel along the mamillary line.
Functions: Regulates the spleen, regulates and moistens the intestines, reduces digestive stagnation and transforms damp-heat.
Indications: Abdominal distension, diarrhea, constipation, intestinal paralysis, parasitic worms in the intestines, chronic sadness.

Conception Vessel 8

"Spirit Palace Gate" - Shen Que



Doorway to the Original Chi,
Location: In the center of the navel
Functions: Tonifies, strengthens and regulates the spleen (Chi and yang), and stomach Chi, regulates the intestines, warms the interior and reduces digestive stagnation, tonifies the kidneys, warms the yang, dries dampness and dispels cold.
Indications: Chronic diarrhea, intestinal tuberculosis, all urinary disorders, shock resulting from intestinal adhesions, heatstroke, rectal or anal prolapse, restless fetus.

Page/Plant	Region	Habitat	Edible Uses
222 Wrinkled rose *Rosa rugosa*		roadsides, sandy dunes, near seashores	🚶 ☕ 🫙 🍬
	Leaves simple, flowers white		
224 Highbush cranberry *Viburnum trilobum*		along streams, wet thickets, moist woodlands	🥤 🥧 🫙
224 Hobblebush *Viburnum alnifolium*		stream banks, ravines, moist woodlands	🚶 🥧
226 Nannyberry *Viburnum lentago*		swamps, stream banks, hillsides	🚶 🥧
226 Squashberry *Viburnum edule*		along streams, wet thickets, moist woodlands	🥤 🥧 🫙
TREES: CONIFER			
228 Pinyon pine *Pinus edulis*		mesas, plateaus, foothills, lower mountain slopes	🌰 ▤
TREES: DECIDUOUS			
	Leaves simple, fruits nuts		
228 White oak *Quercus alba*		eastern deciduous forests	🌰 ☕ ▤ 🍬
230 Chestnut oak *Quercus prinus*		slopes and ridges of deciduous forests	🌰 ☕ ▤ 🍬

Page / Plant	Region	Habitat	Edible Uses
230 Gambel's oak *Quercus gambelii*		dry foothills, canyons	🌰 ☕ ▣ 🍬
230 Blue oak *Quercus douglasii*		interior valleys, rolling hills, mountain slopes	🌰 ☕ ▣ 🍬
232 Northern red oak *Quercus rubra*		valleys, ravines, lower mountain slopes	☕ ▣ 🚦
232 American beech *Fagus grandifolia*		river valleys, deciduous forests, mountain slopes	🌰 ☕ ▣
234 Allegheny chinkapin *Castanea pumila*		dry woodlands, slopes, sandy coastal areas	🌰 ☕ 🍲

Leaves simple, fruits berrylike or fleshy

236 Washington hawthorn *Crataegus phaenopyrum*		old fields, stream banks, open woodlands	🏃 ☕ 🫙
236 Downy hawthorn *Crataegus mollis*		along rivers, streams, lowland fields	🏃 ☕ 🫙
238 Fleshy hawthorn *Crataegus succulenta*		hillsides, old fields, coastal areas	🏃 ☕ 🫙
238 Cockspur hawthorn *Crataegus crus-galli*		river valleys, old fields, hillsides	🏃 ☕ 🫙

Page/Plant	Region	Habitat	Edible Uses
238 Common persimmon *Diospyros virginiana*		bottomlands, edges of woodlands, old fields, fencerows	🍎 ☕ 🥧 🫙
Leaves compound, fruits berrylike			
240 American mountain ash *Sorbus americana*		rocky slopes and ridges, seepage areas	🍎 🥧 🫙
Leaves compound, fruits nuts			
240 Pecan *Carya illinoensis*		bottomlands	🚶 🌰 ▣
242 Big shellbark hickory *Carya laciniosa*		floodplains, bottomlands, river valleys	🚶 🌰 ▣ 🫗
242 Shagbark hickory *Carya ovata*		dry upland slopes, well-drained lowlands	🚶 🌰 ▣ 🫗
244 Mockernut hickory *Carya tomentosa*		ridges, slopes, river valleys	🚶 🌰 ▣ 🫗
244 Black walnut *Juglans nigra*		bottomlands, floodplains, low mixed woodlands	🚶 🌰 ▣ 🫗
246 California walnut *Juglans californica*		along streams and rivers, in bottomlands	🚶 🌰 ▣
246 Butternut *Juglans cinerea*		bottomlands, floodplains, mixed deciduous forests	🚶 🌰 ▣ 🥒 🫗

Winter

Page / Plant	Region	Habitat	Edible Uses
SHRUBS			
	Leaves compound		
250 Staghorn sumac *Rhus typhina*		fencerows, roadsides, edges of woodlands	🚶 ☕ 🥤 🫙 🧂
	Leaves simple		
250 Highbush cranberry *Viburnum trilobum*		along streams, wet thickets, moist woodlands	🥤 🥧 🫙
252 Squashberry *Viburnum edule*		along streams, wet thickets, edges of woodlands	🥤 🥧 🫙
TREES: DECIDUOUS			
	Leaf scars alternate		
252 Sweet birch *Betula lenta*		open woodlands, moist slopes	☕ 🥤 🛍 🏺
254 Yellow birch *Betula alleghaniensis*		rich woodlands, lower mountain slopes	☕ 🥤 🛍 🏺
254 American mountain ash *Sorbus americana*		rocky slopes, seepage areas	🍎 🥧 🫙
	Leaf scars opposite		
256 Sugar maple *Acer saccharum*		eastern deciduous forests	🌰 🥤 🏺

Spring

Spring is the prime season for vitamin-rich shoots and leafy greens. At this time, certain flowers are edible too, and free-flowing sap in trees can be tapped for syrups and tea bases. There's an abundance of plants offering roots, bulbs, and underground stems rich in carbohydrates and other nutrients. Besides, a few other plants already sport nourishing berries and seeds.

The secret for catching the most spring edibles at opportune times is planning. For this, simply consult this book's illustrated table of contents. From it you can make a list of edibles you might encounter on your next spring outing. Or you might even decide to schedule an outing to coincide with the probable readiness of specific plants. Of course, you might prefer a more casual approach and just refer to the book whenever you encounter plants that interest you. Whatever your method, spring's edible bounty awaits you.

Additional spring edibles

Plants listed below have parts that are edible in spring and at least one additional season. Descriptions and photos of these plants appear in a seasonal section other than "Spring," as indicated.

Alpine bistort (*Polygonum viviparum*), p. 154
American bistort (*Polygonum bistortoides*), p. 154
American brooklime (*Veronica americana*), p. 144
American elder (*Sambucus canadensis*), p. 190
Arrowhead (*Sagittaria latifolia*), p. 212
Blue elder (*Sambucus cerulea*), p. 190
California grape (*Vitis californica*), p. 216
California laurel (*Umbellularia californica*), p. 198
Chufa (*Cyperus esculentus*), p. 130
Common day lily (*Hemerocallis fulva*), p. 136
Creeping snowberry (*Gaultheria hispidula*), p. 152
Creeping wintergreen (*Gaultheria humifusa*), p. 160
Frost grape (*Vitis vulpina*), p. 214
Groundnut (*Apios americana*), p. 148
Indian fig (*Opuntia humifusa*), p. 138
Jerusalem artichoke (*Helianthus tuberosus*), p. 210
Labrador tea (*Ledum groenlandicum*), p. 160
Lotus lily (*Nelumbo lutea*), p. 210

Prickly pear (*Opuntia phaeacantha*), p. 140
Red mulberry (*Morus rubra*), p. 200
Reed grass (*Phragmites communis*), p. 128
Riverside grape (*Vitis riparia*), p. 214
Soapweed (*Yucca glauca*), p. 134
Spanish bayonet (*Yucca baccata*), p. 134
Spice bush (*Lindera benzoin*), p. 218
Sweet fern (*Comptonia peregrina*), p. 174
Watercress (*Nasturtium officinale*), p. 146
Western camass (*Camassia quamash*), p. 136
White mulberry (*Morus alba*), p. 200
Wild potato vine (*Ipomoea pandurata*), p. 216
Wintergreen (*Gaultheria procumbens*), p. 150
Yellow pond lily (*Nuphar advena*), p. 212

Ostrich fern *Matteucia struthiopteris*

(synonyms: *M. pensylvanica, Pteretis nodulosa*)

Habitat: bottomlands, swamps, streamsides, ponds; rich forest soil. **Identification:** ***perennial herb with 2 leaf types. Larger plumelike, sterile green leaves (fronds) 0.6–1.6 m (1–5 ft) long,*** with stiff leafstalks to 40 cm (16 in) long, ***leaf blade broadest above middle,*** short-tapering at tip, long-tapering at base, with 20 or more pairs of side branches (pinnae), the pairs alternating. ***Smaller fertile leaves dark brown when mature,*** 40–65 cm (16–26 in) long, stiff, with side branches 3–5 cm (1–2 in) long, bearing powdery reproductive spores. Immature leaves or fiddleheads usually emerge in clusters amid few remaining, upright, brown fertile leaves of previous year, sparsely covered near top with papery, brown scales that fall away as the leaves uncoil; leafstalk (rachis) is conspicuously grooved. **Harvest:** Collect coiled fiddlehead leaves to 20 cm (8 in) tall in April in southern part of range and early May farther north, about same time as flowering of SERVICEBERRY trees. **Preparation:** Scrape inedible brown scales off by hand or wash in cold water. To cook, steam 10 min, season and butter hot; can also be boiled. In field, eat raw as a trail snack or salad item. **Related edible species:** bracken fern *(Pteridium aquilinum)* and cinnamon fern *(Osumunda cinnamomea)*. **Poisonous look-alikes:** None.

Wild onion, Nodding onion *Allium cernuum*

Also edible summer, autumn

Habitat: dry woodlands, rocky slopes, ledges, ridges, prairies. **Identification:** ***perennial herb*** to 60 cm (24 in) high; underground ***bulb usually reddish-purple, slender,*** broadest near base, tapering above. Stem (scape) erect except ***arching at tip. Leaves*** several, from base of plant, linear, mostly 2–4 mm (0.1 in) wide, shorter than stem, ***with onion odor when broken,*** soft, flexible. Flowers in rounded to flat-topped cluster, nodding when young, erect with age, each long-stalked, stalks 10–24 mm (0.4–0.9 in) long, petallike parts white to pink, 4–6 mm (0.2 in) long. ***Fruiting capsules*** in summer nearly rounded to broadest near tip, 3–5 mm (0.1–0.2 in) long, ***3-parted, each part with 2 pointed crests;*** seeds triangular, black. **Harvest:** young tops before flowers appear. Bulbs in spring and fall. **Preparation:** For creamed onions, melt 1 tbsp butter in saucepan, add 2 tbsp flour, ¾ tsp salt, dash of pepper, and cook with constant stirring for 1 min. Add 1 cup boiled onion bulbs and leaves. Stir in milk and simmer until thickened. For wild pickles, pack top bulb clusters in pickle jar, add 1 tbsp mixed pickling spices, and fill with mixture of 2 parts cider vinegar to 1 part water. Seal, store cool for a month or more before using. **Related edible species:** WILD GARLIC and WILD LEEK (next), and several other *Allium* species. **Poisonous look-alikes:** Field garlic *(A. vineale)* is not poisonous but is too strong for most tastes. Avoid all onionlike plants that lack onion odor; some, such as DEATH CAMASS, are highly poisonous.



Ostrich fern: young fronds, or fiddleheads, left; and mature summer leaves (Dykeman).

Wild onion: entire plants and flowers (NYBG).





Wild garlic: flowers (Speas). Entire plant (Kavasch).

Wild leek: rootstocks and entire plants (Dykeman).



Wild garlic *Allium canadense*

Also edible summer, autumn

Habitat: common, open woodlands, fields, prairies. **Identification:** ***perennial herb*** to 58 cm (23 in) high; ***underground bulb brown, egg-shaped to nearly globe-shaped, 2–3 cm*** (0.8–1.2 in) ***across.*** Stem (scape) erect. ***Leaves*** several, from or near base, linear, to 35 cm (13.8 in) long, 2–5 mm (0.1–0.2 in) wide, rarely wider, flat, flexible, ***with strong onion odor when broken,*** shiny green. ***Flower*** (spring) ***clusters consist of several tiny white to purple bulbils*** (miniature bulbs) ***and zero to few pink to white flowers on long, flexible stalks. Fruiting capsules*** rounded or nearly so, 2–3 mm (0.1 in) long, 3-parted, ***smooth on top;*** seeds triangular, tiny, black. **Harvest:** Use whole plant in early spring before flower stalk appears, or use bulbs in spring and fall. Bundle bulbs with 15–20 cm (6–8 in) stems and dry at room temperature for later use. Pick green top bulb clusters on flower stalk in late spring before ripe. **Preparation:** For salad or vegetable, remove tough outer layers of young whole plant. Chop into green salad or boil whole for ½ hr in salted water, then drain, season with butter, and serve. For soup, use drained-off water to make cream of onion soup. Combine 1 qt onion water, 2 tbsp butter, 1 cup half-and-half. Add smooth mixture of 2 tbsp flour in milk, heat to simmer, and serve. Use this plant in any soup recipes calling for onions or with many cooked vegetables and meats. For other uses, see WILD ONION (preceding). **Related edible species:** WILD ONION, WILD LEEK (next), and several other *Allium* species. **Poisonous look-alikes:** See WILD ONION.

Wild leek, Ramp *Allium tricoccum*

Also edible summer, autumn

Habitat: rich, neutral, moist woods, frequently under maples. **Identification:** ***colonial herb. Leaves directly from bulb, 2 or 3 in number, 10–30 cm (4–12 in) long, 2–6 cm (0.8–2.4 in) wide, light green, smooth, fleshy, onion scented, appearing in early spring, shrivel by flowering in midsummer.*** Flowers small, white, in hemispherical cluster on leafless stalk 15–40 cm (6–16 in) tall. Fruit capsule small, 3-lobed, each lobe with 1 hard seed. **Harvest:** young tops before they unfurl into broad leaves; bulbs from early spring through autumn. **Preparation:** add fine-chopped young leaves to salads or boil whole for 20 min in salted water, drain, season, and serve. Excellent in soup. Bulbs excellent pickled, chopped in salads, cooked alone, or with meat or other vegetables. Add chopped fine bulbs to mashed potatoes. For fried leeks parboil 3 min, drain, add more water, boil until tender. Saute in butter, serve covered with bread crumbs. *Caution:* Leeks are often very strong flavored and may cause gastric distress. Eat sparingly. **Related edible species:** WILD ONION, WILD GARLIC (preceding), and several other *Allium* species. **Poisonous look-alikes:** See WILD ONION.

Governor Vessel 4

"Door of Life" - Ming Men

Back Doorway to the Lower Tan Tien
Location: Below the spinous process of the second lumbar vertebrae. Approximately at the level of the navel.
Functions: Nourishes the Original Chi, strengthens and harmonizes the kidneys, tonifies ching and yang, clears channels and invigorates collateral vessels, benefits the lower back and bones, regulates water pathways.
Main point to build life fire; main point for sexual/genital problems.
Indications: Bone disorders, chronic nephritis, enuresis, low sex drive, fatigue, spermatorrhea, impotence, irregular menses, painful menses, no menses, scanty menses, abnormal uterine bleeding, lower back stiffness and pain, kidney pain radiating to the abdomen, hemorrhoids, urinary incontinence, painful urination, diarrhea, sciatica, spinal myelitis.



Governor Vessel 6

"Middle of Spine" - Jizhong

Location: Below the spinous process of the 11th thoracic vertebrae (T-11).
Functions: Stimulates Ching Chi, benefits spleen, stomach and kidneys and liver.
Indications: Hepatitis, seizures, low back pain, paralysis of lower limbs, blood in stools, diabetes, diarrhea.



Governor Vessel 11

"Spirit's Path" - Shen Tao

Location: Below the spinous process of T-5 (opposite CV-17, the Heart Point).
Functions: Calms heart and mind, regulates heart Chi and yang, expands and relaxes the chest, benefits heart and lungs, sedates pain, sedates fright and dispels wind.
Indications: Anxiety and palpitations due to fear or fright, neurasthenia, asthma, cough, shortness of breath, chest and hypochondriac pain, insomnia, aphasia due to winds, stroke, forgetfulness, fever.



Corn lily, Clinton's lily *Clintonia borealis*

Habitat: rich woodlands, deep thickets, higher elevations, cool moist sites. **Identification:** ***perennial herb*** to 40 cm (16 in) high, from a slender underground stem (rhizome); ***each plant with 2–5 large basal leaves. Leaves*** usually broadest near or above the middle, ***10–38 cm*** (4–15 in) ***long,*** 4–14 cm (1.6–5.5 in) wide, pointed at tip, entire along margin, dark shiny green. ***Flowers 3–8 at top of erect stalk,*** nodding, each with 6 greenish-yellow, narrow petallike structures 1.3–1.8 cm (0.5–0.7 in) long. ***Fruits are globe-shaped, bright blue berries 8–10 mm*** (0.3–0.4 in) ***in diameter.*** **Harvest:** Gather leaves before fully unfurled. Fully formed leaves are tough and unpleasant tasting. **Preparation:** Chop young leaves into salad with other greens of the season. Boil leaves about 10 min and serve with butter and seasonings. **Related edible species:** White clintonia *(C. umbellata)* has white flowers and black fruit. **Poisonous look-alikes:** *Be positive* of corn lily's young-growth identification features because some similar-looking species are poisonous.

Asparagus *Asparagus officinalis*

Habitat: roadsides, disturbed sites, especially sandy and well-drained soils. **Identification:** ***perennial herb*** 1–2 m (3.3–6.6 ft) high from thick, white, underground stem (rhizome); ***stems*** upright, often branched, ***green***, becoming very slender at top. ***Leaves*** alternate, ***reduced to small scales, lance-shaped,*** to 2.5 cm (1 in) long. ***Flowers produced along upper stems, usually singly or in pairs, hanging on slender stalk, narrowly bell-shaped, 3–6 mm*** (0.1–0.2 in) ***long, yellow to greenish-yellow, 6-lobed. Fruits*** are ***globe-shaped berries 4–8 mm*** (0.2–0.3 in) ***in diameter, bright red,*** fleshy, containing 3–6 black seeds. **Harvest:** identical to cultivated asparagus. Locate by presence of dried Christmas-tree-shaped stalks of previous year. Slice off young stalks just below ground level when green shoots protrude only a few inches. More shoots will grow, allowing reharvesting. *Caution: Avoid older stalks and other parts, which are mildly toxic.* **Preparation:** Wash stalks and peel off any tough covering near base. Tie stalks in bundle and steam or boil until tender, usually 10–15 min. Serve with butter and seasonings or cream sauce. Excellent prepared as cream soup. See any vegetable cookbook for other recipes. **Related edible species:** none. **Poisonous look-alikes:** none.



Corn lily: flowering and fruiting plants (NYBG).

Asparagus: young shoots (Dykeman). Mature branch with fruit (Elias).


Introduced and grows wild. Widespread.



Eastern camass: flower and field (NYBG).

Common greenbrier: fruiting branch (Elias). Flowers (NYBG).



Eastern camass, Camass lily *Camassia scilloides*

Also edible summer, autumn, winter

Habitat: fields, wet meadows, moist open woodlands. **Identification:** ***perennial herb*** from a globe-shaped bulb 1–3 cm (0.4–1.2 in) in diameter. ***Leaves attached at base, long-narrow, 20–60 cm*** (7.9–23.6 in) ***long, 5–17 mm*** (0.2–0.7 in) ***wide,*** pointed at tip. ***Flowering stalk upright to 60 cm (24 in) tall;*** stalked flowers in narrow cluster; ***each flower with 6 white, blue, or violet petals*** or petallike structures 7–12 mm (0.3–0.5 in) long. ***Fruit*** small, nearly globe-shaped, ***3-parted capsule*** 6–12 mm (0.2–0.5 in) in diameter. **Harvest:** Dig or pull bulbs any season; safest when blue flowers distinguish it from DEATH CAMASS. Dig and transplant in ground free of DEATH CAMASS. Study descriptions of DEATH CAMASS carefully. **Preparation:** Raw bulbs are palatable. May be boiled 25–30 min or baked in foil for 45 min at 175°C (350°F) but best preparation is the pit method used by Indians and described in the Introduction, in which eastern camass is baked for 1–3 days. The baked bulbs are very dark and sugary. Slice pit-baked or boiled bulbs. Then dry in sun or warm oven before storing in paper bag in dry place. Bulbs can be used as a potato substitute. **Related edible species:** WESTERN CAMASS. **Poisonous look-alikes:** DEATH CAMASS, narrow-leaved plants with green, white, or bronze flowers, single or several in narrow spike.

Common greenbrier, Catbrier *Smilax rotundifolia*

Also edible summer

Habitat: common plant of roadsides, secondary woodlands, woodland clearings, streamsides, thickets. **Identification:** ***climbing perennial vine, stems*** tough, becoming woody, ***often strongly 4-sided,*** green, tendrils many, ***armed with stout, sharp thorns. Leaves*** alternate, deciduous to almost evergreen (southern part of range), 4–10 cm (1.6–4 in) long, nearly as wide, ***broadest near base to nearly circular,*** pointed at tip, entire along margin, ***leathery,*** dark shiny green. Vines bearing either male or female flowers in several-flowered, flat-topped clusters, green or yellow. ***Fruits bluish-black berries,*** globe-shaped 5–9 mm (0.2–0.4 in) in diameter, often containing 2 or 3 seeds. **Harvest:** Gather new shoots and growing tips, plus uncurling leaves and tendrils, while they are still crisp and tender during spring and summer. **Preparation:** excellent raw as trail nibble. For salads use tenderest parts raw or boil slightly older tips 2–3 min, drain and cool. Add your favorite salad dressing. Steam or boil bundled shoots like asparagus or boil tendrils, leaves, and shoots together like spinach. Cook until tender and serve with sauces and seasonings as you would other vegetables. **Related edible species:** several other *Smilax* species, including BULLBRIER and CARRION FLOWER (next). **Poisonous look-alikes:** none.

Bullbrier, Greenbrier *Smilax bona-nox*

Also edible summer

Habitat: open woodlands, fields, abandoned farmlands, roadsides, disturbed sites. **Identification:** perennial ***climbing vine, stems 4-sided,*** becoming woody, frequently branching, green, tendrils present, with scattered stiff thorns or thornless. ***Leaves*** alternate, deciduous, 4–8 cm (1.6–3.2 in) long, triangular in shape, broadest near base, pointed at tip, entire or with few sharp teeth along ***thickened margin,*** almost leathery texture. Vines with either male or female flowers in several-flowered, rounded or flat-topped stalked clusters. ***Fruits black berries,*** globe-shaped or nearly so, ***6–9 mm*** (0.2–0.4 in) ***in diameter,*** usually 1-seeded. **Harvest and preparation:** shoots, tips, tendrils, leaves same as COMMON GREENBRIER. Also, dig and clean tuberous roots. Cut them into short pieces and pound them in metal container until fibers are separated and gelatinous sediment is released. Wash sediment from fibers and allow to settle. Strain out fibers and other floating matter. Carefully pour off water and allow sediment to dry and turn red. Boil 1 tbsp powdered sediment per cup of water for 10 min. Cool to make jelly or dilute and sweeten for drink. Also use powder as thickener for stews or substitute for part of flour in pancake batter. **Related edible species:** COMMON GREENBRIER (preceding) and CARRION FLOWER (next). Other tuberous-rooted *Smilax* species, such as China-root *(S. tamnoides)* in the East and *S. californica* in the West, are usable for gelatin. **Poisonous look-alikes:** none.

Carrion flower *Smilax herbacea*

Also edible summer

Habitat: open woodlands, margins of woodlands, roadsides, fields. **Identification:** perennial climbing ***vine; green stems, never woody,*** freely branching, tendrils present, ***lacking prickles or thorns. Leaves*** alternate, deciduous, broadest near base to almost rounded, pointed to rounded at tip, heart-shaped to rounded at base, entire along margin, becoming leathery. Vines bearing either male or female ***flowers on long stalks from junctions of uppermost leaves;*** flowers in densely-clustered rounded heads. Fruits in dense, rounded clusters, each ***fruit a berry***, globe-shaped, ***8–12 mm*** (0.3–0.5 in) ***in diameter, dark blue to bluish-black,*** containing several seeds. **Harvest and preparation:** same as for COMMON GREENBRIER and BULLBRIER (preceding). **Related edible species:** COMMON GREENBRIER and BULLBRIER. **Poisonous look-alikes:** none.



Bullbrier: flowering and fruiting branches (NYBG).

Carrion flower: flowering branch (NYBG). Fruiting branch (Kavasch).





Cattail: flowering stalk and roots (Dykeman).

Narrow-leaved cattail: entire plants and flowers (Elias).



Cattail *Typha latifolia*

Also edible summer, autumn, winter

Habitat: shallow water of lakes, ponds, bays, ditches, marshes. **Identification:** large upright perennial herb to 3 m (9.8 ft) tall, with large stout, horizontal underground stems (rhizomes). ***Leaves*** sheathing at the base of stem, ***1–2.5 m*** (3.2–8.2 ft) ***long, 8–24 mm*** (0.3–0.9 in) ***wide, narrow, swordlike,*** pointed at tip, ***grayish green.*** Flowers at tip of erect stalks, tiny male flowers densely clustered in narrow, cylinder-shaped mass directly above female flowers densely clustered in a cylinder-shape 5–20 cm (2–8 in) long. ***Fruits*** in ***cigar-shaped clusters 2–3.5 cm*** (0.8–1.4 in) ***thick*** which break apart in soft downy-haired seeds in autumn. **Harvest and preparation:** In early spring, dig up roots to locate small, pointed dormant sprouts at ends of roots. Sprouts are edible raw or cooked. Later, similar sprouts appear on roots at bases of leaves. From then until plants are 60–90 cm (2–3 ft) tall, grasp leafy stalks below water surface and pull straight up, usually breaking stalks off at root. Peel away tough leafy layers to tender core, about 12 mm (0.5 in) diameter and to 30 cm (12 in) long. This "Cossack asparagus" is excellent raw, eaten like celery, or sliced into a salad. Or, cover cores with boiling water and simmer about 10 min. Serve with butter, salt and pepper or with oil-and-vinegar. Later pick green bloom spikes while still in papery sheaths and before pollen ripens above them. Remove sheaths and boil spikes in slightly salted water until tender. Eat like corn on cob, or scrape buds from cores for "corn" casserole. As pollen ripens, shake and rub it off stalks into container. Sift through fine screen to remove nonpollen materials. Substitute for part of flour in muffin, fritter, or pancake batter. For white flour, dig roots from fall through early spring. Wash and peel roots, crush cores thoroughly in container of water, and strain out fibers. Wash resulting starch several times, letting it settle and carefully pouring off water after each washing. Dry thoroughly for storage or use wet. **Related edible species:** NARROW-LEAVED CATTAIL (next). **Poisonous look-alikes:** stalks and roots of wild iris species (including YELLOW FLAG, BLUE FLAG). Harvest cattails where old stalks are abundant.

Narrow-leaved cattail *Typha angustifolia*

Also edible summer, autumn, winter

Habitat: ponds, lakes, swamps, bays, ditches. **Identification:** ***large*** upright ***perennial herb*** to 2 m (6.6 ft) tall, with thick, horizontal, underground stems (rhizomes). ***Leaves*** sheathing at base of stem, 0.6–1.5 m (2–5 ft) long, ***3–8 mm*** (0.1–0.3 in) ***wide, very narrow***, strap-shaped, flattened, pointed at tip. ***Flowers*** at tip of erect stalks, ***tiny male flowers*** densely clustered in narrow, cylinder-shaped column 2.5–7.5 cm (1–3 in), ***spaced at intervals above the larger, brown, cylinder-shaped clusters of female flowers*** 3–12 cm (1.2–4.7 in) long. ***Fruits are narrow, cigar-shaped clusters 5–15 cm*** (2–6 in) ***long*** which break apart into soft, downy-haired seeds in autumn. **Harvest and preparation:** same as for CATTAIL (preceding). **Related edible species:** CATTAIL. **Poisonous look-alikes:** See CATTAIL for details.

Hard-stem bulrush *Scirpus acutus*

Also edible summer, autumn, winter

Habitat: shores of ponds, lakes, streams, rivers, marshes. **Identification:** ***perennial herb*** 1–3 m (3.2–9.8 ft) high, from thick, tough, brownish underground stems (rhizomes); ***stems upright***, rounded, ***stiff, yellowish-green, unbranched,*** leaf blades absent or sometimes present, to 10 cm (4 in) long. ***Flowering heads (spikes) densely clustered and originating from one place near the tip of the stem,*** with 1 to several stalks each bearing several heads, each head cylinder-shaped, 8–18 mm (0.3–0.7 in) long, composed of several overlapping scales. Fruits are hard, somewhat flattened seeds 2–3 mm (0.1 in) long. **Harvest:** See GREAT BULRUSH (next). **Preparation:** Peel and cut firm older roots into sections. Crush them and boil in water until you have white gruel. Separate out any fibers and dry gruel into flour. For biscuit dough, add oil and water to reach right consistency. Add salt and baking powder, knead and roll to about ½-in thickness. Bake at 230°C (450°F) or twisted on stick by campfire. Also prepare flour by drying cleaned roots thoroughly, crush, and remove fibers. Pound and grind remaining material into flour. Use pollen as flour additive. Also grind seeds to use alone or with pollen and root flour for baking. Also see GREAT BULRUSH. **Related edible species:** All North American *Scirpus* species may be edible. **Poisonous look-alikes:** none because the fruiting pattern is distinctive.

Great bulrush, Tule *Scirpus validus*

Also edible summer, autumn, winter

Habitat: shallow water of lakeshores, ponds, and streams; fresh and brackish water marshes. **Identification:** ***perennial herb*** to 3 m (9.8 ft) high from tough, reddish scaly underground stems (rhizomes); ***stems upright, rounded, soft, pale green, unbranched;*** leaf blades absent. ***Flowering heads (spikes) produced near stem tips,*** with several stalked, branched clusters, each head egg-shaped, 0.4–1 cm (0.1–0.4 in) long, somewhat flattened, composed of a series of overlapping scales. Fruits hard, flattened seeds 2–3 mm (0.1 in) long. **Harvest:** Bulrushes, like CATTAILS, provide food year-round. Cut off young shoots in early spring or when they've formed in autumn. Later remove cores from bases of older stalks. Shake and beat pollen from stalks into bucket in summer and return to collect seeds the same way from late summer into winter. Dig up roots year-round to use firm, sweet ones as vegetable or as sugar source and older ones for flour. **Preparation:** Peel new shoots and youngest rootstocks and separate cores from older stalks. Eat them raw, sliced in salads, or boiled. Roast young shoots and roots, or slice and fry like potatoes. Bruise young roots and boil for several hours, boiling off water to produce sweet syrup. For other preparations, see HARD-STEM BULRUSH (preceding). **Related edible species:** HARD-STEM BULRUSH. **Poisonous look-alikes:** none.



Hard-stem bulrush: flowers (Speas).

Great bulrush: fruiting (Kavasch).





Governor Vessel 14

" Big Vertebra" - Da Zhui

Influential point of yang
Sea of Chi point
Intersection point of all yang channels.
Location: Below the spinous process of the seventh cervical vertebra (C-7), approximately at the level of the shoulders.
Functions: Opens the yang, clears the brain, calms the spirit, tonifies Protective (Wei) Chi, reduces fever, relieves exterior conditions, clears heat.
Indications: Fever, sunstroke, malaria, psychosis, seizures, bronchitis, asthma, pulmonary tuberculosis, emphysema, hepatitis, blood diseases, eczema, hemiplegia, pain in the back of the shoulders, cold-induced diseases, cough, fever and chills.

Governor Vessel 16

“Jade Pillow” or "Wind Palace" - Feng Fu

Sea of Marrow Point, Window of Sky Point, Ghost Point
Intersection point of the Yang Regulator Channel on the Governor Vessel
Location: At the base of the skull, about one inch above the posterior hairline.
Functions: Benefits and clears the brain, calms spirit, opens the sensory orifices, dispels wind, wind-cold and wind-heat, smoothes joint functions.
Indications: Seizures, mania, hemiplegia, loss of speech due to stroke, delirium, suicidal behavior, fear and fright, anxiety, common cold, sensation of heaviness in the head, headache, dizziness, numbness of the limbs, deaf-mutism, blurred vision, sinusitis, stiff neck.

Governor Vessel 20

"One Hundred Meetings" - Bai Hui



Sea of Marrow Point
Location: At the crown of the head, approximately on the midpoint of the line connecting the top apex of the two ears.
Function: Clears the senses, calms the spirit, extinguishes liver wind, stabilizes ascending yang.
Indications: Headache, dizziness, shock, depression, hypertension, insomnia, seizures, prolapsed anus, prolapsed uterus, mental dullness, hemorrhoids.

Pigweed, Redroot *Amaranthus retroflexus*

Also edible summer, autumn

Habitat: common and widespread; especially recently abandoned land, waste areas, roadsides. **Identification:** ***coarse annual herb*** to 2 m (6.6 ft) high; stem upright, stout, usually branched. ***Leaves*** alternate, ***long-stalked,*** broadest near base, ***5–10 cm*** (2–4 in) ***long, 2.5–6 cm*** (1–2.4 in) ***wide,*** blunt to short-pointed at tip, wavy along margin. ***Flowers*** late summer and fall, ***densely crowded on narrow spikes*** 6–18 cm (2.4–7.1 in) long, on upper part of stem. ***Fruits*** flattened, 1–2 mm (0.1 in) across, dry, each ***partially enclosed by rigid pointed bracts 5–8 mm*** (0.2–0.3 in) ***long;*** seeds rounded, shiny black, tiny. **Harvest:** For greens, pick young leaves when plants are only a few inches tall and before stem becomes woody. Use leaves fresh or dry. Pick seed clusters as plants mature but before seeds begin to drop. Dry, thresh by shaking or trampling, winnow by shifting in breeze. Dry on tray at 190°C (375°F) for 40–50 min, stirring occasionally. Store in paper bag in dry place. **Preparation:** Fresh greens excellent as potherb. Boil for 10–20 min until tender and serve with seasonings and butter. For livelier flavor, boil with other greens such as mustard or dandelion, or add vinegar, bacon, hard-boiled eggs, or grated cheese. For salad, use fresh young leaves as major component of tossed salad. Use dried leaves in soups. Seeds edible whole or ground into meal using food mill or stones. For muffins, combine 1 cup pigweed meal, ½ cup whole-wheat flour, 2 tsp baking powder, ½ tsp salt, 3 tbsp honey, brown sugar, or molasses. Add 2 egg yolks, 1¼ cups milk, and ¼ cup butter. Blend until mix is moist. Beat 2 egg whites until stiff and fold into mix. Bake in greased muffin tin about 20 min at 190°C (375°F). Makes approximately 18. Thin batter with milk for pancakes. **Related edible species:** GREEN PIGWEED (next) and several other *Amaranthus* species. **Poisonous look-alikes:** Since pigweed is a concentrator of nitrates, plants from nitrate-fertilized areas should be eaten only in moderation.

Green pigweed *Amaranthus hybridus*

Also edible summer, autumn

Habitat: common and widespread in eastern and midwestern North America; fields, roadsides, disturbed sites. **Identification:** ***coarse annual herb*** to 2 m (6.6 ft) high; stems upright, with several upright branches. ***Leaves*** alternate, long stalked, broadest below or near middle, ***8–15 cm*** (3.2–6 in) ***long, 2–5 cm*** (0.8–2 in) ***wide,*** short-pointed at tip, wavy along margin. ***Flowers*** tiny, ***densely crowded in slender, green to red spikes.*** Fruits tiny, flattened, 1.5–2 mm (0.1 in) across, dry, ***partially enclosed by short, flexible bracts*** to 2 mm (0.1 in) long; seeds tiny, rounded, shiny black. **Harvest and preparation:** Same as for PIGWEED (preceding). **Related edible species:** PIGWEED and related species. **Poisonous look-alikes:** See PIGWEED.


Introduced and
grows wild.
Widespread.

Pigweed: basal stalk and flowering head (USDA).

Green pigweed: fruiting stalks (Hardin).


Introduced and
grows wild.
Widespread.


Introduced and grows wild. Widespread.

Lamb's quarters: basal leaves of young plant and mature stem (Dykeman).

Poverty weed: entire plant (Weber).



Lamb's quarters *Chenopodium album*
Also edible autumn

Habitat: common and widespread; yards, vacant lots, roadsides, waste areas, disturbed sites; introduced from Europe. **Identification:** small to medium-size annual ***herb*** to 0.6 m (2 ft) high; stems erect, usually branched, ***with a pale green or whitish cast. Leaves*** alternate, lower ones ***almost triangular,*** 3–10 cm (1.2–4 in) long, ***blunt at tip, coarsely toothed along margin, mealy white beneath,*** stalked, upper ones smaller. ***Flowers*** in late spring to autumn, ***tiny, inconspicuous, produced in dense short spikes in junctions of upper leaves and at tip.*** Fruits tiny, globe-shaped but depressed at tip, enclosed in persistent calyx lobes, in short dense spikes. **Harvest:** Pick young leafy stems to 25 cm (10 in) tall or tender growing tips of older plants. Gather abundant seeds in autumn by rubbing fruiting spikes into paper bag and winnow away chaff. **Preparation:** a superlative green vegetable, lacking strong flavor and high in vitamins A and C. Use leafy stems alone in salad or mix with stronger greens. For potherb, use large quantity of greens because cooking greatly diminishes bulk. Boil young leafy stems in small quantity of water about 5 min until tender. Add butter, salt and pepper or sauce of ¼ cup diced onion, 4 slices crisp bacon chopped fine, ¼ cup vinegar, salt and pepper, simmered gently. Use same sauce on raw greens as salad dressing. Soften seeds by boiling, crush, grind in food mill or blender. This produces nutritious black flour, good mixed with wheat flour for pancakes and muffins. **Related edible species:** Berlandier's lamb's quarters *(C. berlandieri),* Fremont's lamb's quarters *(C. fremontii)*. **Poisonous look-alikes:** Species of *Chenopodium* that have bad odor and taste can be somewhat toxic.

Poverty weed *Monolepis nuttalliana*
Also edible autumn

Habitat: dry areas of high salinity or alkaline soils. **Identification:** ***annual herb*** to 55 cm (22 in) tall, spreading; branches numerous, stout, somewhat fleshy, upright or nearly so. ***Leaves*** alternate, ***triangular to lance-shaped,*** 1–4 cm (0.4–1.6 in) long, pointed at the tip, entire or irregularly toothed along the margin, sharply lobed at the base. ***Flowers small, numerous, inconspicuous, produced in junction of upper, smaller leaves, each bisexual, greenish, petals absent.*** Fruits are small, flattened, brown; winged seeds 1 mm (less than 0.1 in) across. **Harvest:** Pick young leafy stems. Roots are edible but usually not tasty. If you have the patience, strip seeds from stems when fully ripe late in growing season. **Preparation:** Like its relative, LAMB'S QUARTERS (preceding), which it superficially resembles, poverty weed is a good green vegetable. Boil young stems in small quantity of water until tender, but avoid overcooking. Serve with butter and seasonings or the following sauce hot: Simmer together for a few minutes ¼ cup dried onion, 4 slices crisp bacon (chopped fine), ¼ cup vinegar, salt and pepper. Southwestern Indians ground seeds with corn and mesquite beans to make pinole. **Related edible species:** Species of the *Chenopodium* genus (including LAMB'S QUARTERS) are of the same family as poverty weed. **Poisonous look-alikes:** none.

Glasswort *Salicornia europaea*

Also edible summer, autumn

Habitat: sea coast, salt marshes, alkaline soils. **Identification:** ***annual herb*** to 40 cm (16 in) high; ***stems*** erect to spreading, ***stiff, succulent*** (may be unbranched to many branched), green turning orange or red in autumn; leaves opposite, minute, scalelike, ***appearing leafless. Flowers*** (late summer) tiny, numerous, produced ***in erect*** to slightly spreading ***spikes 2–6 cm*** (0.8–2.4 in) ***long,*** joints longer than broad. Fruits are seeds, tiny, egg-shaped, 1.2–3 mm (0.1 in) in diameter. **Harvest:** Pick tender tips from branches midspring to autumn. **Preparation:** Tips are crispy and salty; good for trail nibble. Or chop and serve raw as salad with spicy vinegar dressing or add to other salad greens. For pickles pack jars with very tender, clean, raw tips or older tips that have been boiled in a little water for 5 min. Make pickling liquid from 4 cups cider or wine vinegar, 3 tbsp pickling spices, 1 grated onion, ½ cup honey or sugar, plus garlic, bay leaves, or other spices. Combine ingredients and boil 5–6 min. Cover glasswort with boiling liquid and seal jars. Store at least 1 month. For vegetable, place tips in boiling water and cook until tender 5–10 min. Serve buttered. **Related edible species:** Other species of *Salicornia* look very similar and are edible; one is perennial *(S. virginica).* **Poisonous look-alikes:** none.

Russian thistle, Saltwort *Salsola kali*

Also edible summer

Habitat: sandy beaches on East Coast; dry, alkaline soils in West. **Identification:** ***annual herb*** to 1 m (3.2 ft) high; stems branching, upright to spreading, smooth, hairy, or with mealy appearance. ***Leaves alternate,*** simple, ***fleshy, rounded, 2–5 cm*** (0.8–2 in) ***long, lance- to needle-shaped, spine-tipped,*** entire along margins, lacking distinct leafstalk. Flowers numerous in narrow, elongated spikes in junctions of stems of upper leaves and at branch tips; each flower tiny, bisexual, sepals 5, winged on margins; petals absent. ***Fruits are flattened, winged, and nearly circular, 3–6 mm*** (0.1–0.2 in) ***across,*** yellowish to slate-colored. **Harvest:** Pull up shoots of new spring growth when less than 15 cm (6 in) tall; also succulent new plants after rains in late spring and in summer. Beware of spines at leaf tips. *Caution:* Plants occasionally contain toxic levels of nitrates and oxalates. **Preparation:** Cut off roots. Wash tops and boil for about 15 min. Serve like spinach with butter and seasonings, cream sauce, or vinegar. Mix with other greens of season. **Related edible species:** other *Salsola* species mainly in the Southwest. **Poisonous look-alikes:** none.



Glasswort: stems showing two color phases (NYBG).

Russian thistle: flowering branches (NYBG).





Stinging nettle: young plants and flowering plant (Elias).

Plantain: young plant (Dykeman). Mature plant (Elias).


Introduced and grows wild. Widespread.

Stinging nettle, Nettle *Urtica dioica*

Habitat: widespread, especially in moist fertile soils in disturbed areas, margins of woods, trails, stream banks, roadsides, vacant lots. **Identification:** perennial, upright, to 1 m (3.2 ft); erect ***stem with bristly, stinging hairs. Leaves opposite, long-stalked,*** blade 5–14 cm (2–5.5 in) long, broadest near base, coarsely toothed, veins depressed, ***with stiff, stinging hairs on both surfaces.*** Each plant either male or female. Flowers produced in junctions of leafstalks, each flower tiny, male or female, borne in many-flowered, loosely branched, elongated, cream-colored clusters. Fruits tiny, inconspicuous, hard, nutletlike, about 2 mm (0.1 in) long. **Harvest:** In spring, wear gloves to avoid stinging hairs, or use scissors to cut young shoots and tender top leaves directly into pot or bag. Later leaves are tough and gritty. **Preparation:** Boiling destroys irritant. As potherb, barely cover with water and simmer until tender. Drain, add seasonings, butter, lemon juice, or wine vinegar. Use cooking water as beverage with lemon and sugar or as soup with salt, pepper, and vinegar. To make a simple stinging nettle puree, rub 2 cups cooked stinging nettles with juice through sieve, or puree in blender. Reheat, add 2 tbsp butter, salt to taste, simmer 10 min more. Stir in ¼ cup light cream; season with black pepper. A versatile plant, stinging nettle cooking juice may also be used as rennet (milk coagulant) for junket pudding and as beer ingredient. Plant is high in vitamins A and C, protein, and minerals. **Related edible species:** wood nettle *(Laporta canadensis),* slender nettle *(U. gracilis).* **Poisonous look-alikes:** none.

Plantain *(Also edible summer, autumn)* *Plantago major*

Habitat: yards, roadsides, disturbed sites; common weed introduced from Europe. **Identification:** ***perennial herb*** with fibrous root system. ***Leaves basal,*** numerous, broadest near or below middle, ***5–20 cm*** (2–8 in) ***long, 2.5–12 cm*** (1–4.7 in) ***wide,*** rounded to pointed at tip, toothed, entire or wavy along margin, ***rough on both surfaces,*** smooth or hairy. ***Flowers tiny, numerous along upper part of erect spike*** to 20 cm (8 in) high, each flower with 4 translucent petals. Fruits are tiny capsules produced along spike; each capsule contains 10–18 seeds. **Harvest:** Pick young leaves before flower stalk appears or pick new leaves through summer; otherwise leaves develop stringy veins that are tough to chew. Strip ripe seeds from flower stalks from late spring through fall. **Preparation:** Use tenderest leaves in salads with other greens of season. For cooked vegetable, soak leaves in salt water for 5 min. Boil with little water in covered pot until tender but not overcooked. For beverage, steep handful of leaves in pint of boiling water for ½ hr or longer. Dry seeds thoroughly and grind into flour. For pancakes, combine 2 cups plantain flour with 3 tsp baking powder, ½ tsp salt, 3 tbsp sugar, 2 eggs, 3 tbsp cooking oil, 1 cup milk. Mix thoroughly. Add more milk or flour for proper consistency; add fruit, if desired. Cook on hot griddle. **Related edible species:** Species of the *Plantago* genus are found throughout North America; most are edible. Boil leaves of bitter species in sweetened water. Seaside plantain *(P. juncoides)* is one of the best and is found only along East Coast. **Poisonous look-alikes:** none.


Introduced and grows wild. Widespread.

Shepherd's purse: entire plant and flowering stalks (Elias).

Toothwort: flowering plant (NYBG).



Shepherd's purse *Capsella bursa-pastoris*

Habitat: yards, vacant lots, roadsides, other disturbed areas; widespread weed, introduced from Europe. **Identification:** small to medium-size ***annual or biennial herb*** to 60 cm (2 ft) high, unbranched or sparingly branched, ***with a flattened, basal rosette of leaves,*** the ***basal leaves*** 4–10 cm (1.6–4 in) long, uniformly wide to broadest near tip, ***shallowly to deeply lobed along sides.*** Upright stems with few, smaller, narrower leaves. Flowers produced in narrow elongate cluster, each tiny, stalked, with 4 white petals 2–4 mm (0.1 in) long. ***Fruits slightly flattened, heart-shaped, notched at tip, 4–10 mm*** (0.2–0.4 in) ***long.*** **Harvest:** Gather leaves before flowering stage. If too peppery, bleach by covering with sawdust, leaves, or flower pots for week or more. Strip off seed pods as they ripen. **Preparation:** Use raw leaves as salad greens, if not too peppery, or with other milder greens. For a potherb, boil leaves in water for about 20 min with one change of water if needed. Season with salt and vinegar. Use dried pods and seeds as seasoning in soups and stews. Western Indians once ground seeds into meal, but process is tedious. **Related edible species:** red shepherd's purse *(C. rubella)* and slender shepherd's purse *(C. gracilis).* **Poisonous look-alikes:** none.

Toothwort *Dentaria laciniata*

Habitat: moist deciduous woodlands, ravines, floodplains. **Identification:** perennial herb from a jointed, white underground stem (rhizome); stem upright, to 40 cm (15.7 in) high. Basal leaves absent at flowering, ***stem leaves in a whorl of 3 on upper half, deeply 3-parted, leaf segments lance-shaped, coarsely toothed to nearly entire,*** the terminal segment often deeply parted. ***Flowers*** produced in a terminal, elongate, hairy cluster, each flower stalked, ***with 4 white petals*** 1.2–2 cm (0.5–0.8 in) long. Fruits narrow, elongate, 2–4 cm (0.8–1.6 in) long, splitting open lengthwise at maturity to release the tiny seeds. **Harvest:** Dig rootstocks in small numbers from areas where plentiful. Other plants will grow from pieces of perennial root remaining in the soil. **Preparation:** Use as spicy trail nibble. Wash roots, chop and grind them in vinegar, add a dash of salt; use like horseradish. Add chopped roots to wild tossed green salads to liven flavor. **Related edible species:** At least six other species, similar in appearance, are distributed in moist woodlands of the East and West. All may be used like the species described. **Poisonous look-alikes:** none.

Bibliography

Bensky, Dan. Acupuncture: A Comprehensive Text, Seattle, WA: Eastland Press, 1981.
Chia, Mantak. Awaken Healing Light of the Tao, Huntington, NY: Healing Tao Books, 1993.Chi Nei Tsang: Internal Organ Chi Massage. Huntington, Ny: Healing Tao Books, 1990.
Cooper, Groffrey M. The Cell, A Molecular Approach, Washington, DC: Sinauer Associates, 1996.
De Lee, H. Lorenzen. Message from Water: Word of Recommendation, 1984.**DeLaney, Colleen, Leonard, David, and Kitsch, Lancelot.** The Acupuncture Point Book, Santa Cruz, CA: Roast Duck Productions, 1989.
Dong, Paul and Esser, Aristide H. Chi Gong: The Ancient Chinese Way to Health. New York: Paragon House, 1990.
Jou, Tsung Hwa. The Tao of Meditation: Way to Enlightenment. Piscataway: Tai Chi Foundation, 1983.
Lade, Arnie. Acupuncture Points: Images and Functions, Seattle, WA: Eastland Press, 1989.
Lindsay, Mary. The Visual Dictionary of the Human Body, First American Edition, New York, NY: Dorling Kindersley Publications, 1991.
Lu, Kuan Yu. Taoist Yoga: Alchemy and Immortality, New York, NY: Samuel Weiser, 1970.
Maciocia, Giovanni. The Foundations of Chinese Medicine, Edinburgh, Scotland: Churchill Livingstone, 1989.
Matsumoto, Kiiko and Birch, Stephen. Extraordinary Vessels. Brookline: Paradigm Publications, 1986.
McGraw-Hill Companies Human Physiology, 1999.
Morrison, Philip and Phylis and the Office of Charles and Ray Eames. Power of Ten:1982
Nilsson, Lennart. The Body Victorious. New York: NY: Delacorte Press, 1985.
Shanghai College of Traditional Medicine, translated by O'Connor, John and Teeguarden, Iona Marsaa. Acupressure Way of Health: Jin Shin Do, Tokyo, Japan: Japan Publications, 1978.
Tortora, Gerard J. and Grabowski, Sandra R. Introduction to the Human Body, Fifth Edition. New York, NY: Wiley, 2000.
Yang, Jwing-Ming. The Root of Chinese Chi Kung Jamaica Plain, MA: YMAA, 1989.

Peppergrass *Lepidium virginicum*

Habitat: fields, vacant lots, roadsides, other disturbed areas, waste sites. **Identification:** annual or biennial ***herb,*** upright to 50 cm (19.7 in) high, occasionally taller. ***Basal rosette of leaves 4–10 cm*** (1.6–3.9 in) ***long,*** 0.8–2 cm (0.3–0.8 in) wide, broadest near tip, ***doubly toothed, lobed, or deeply dissected*** along margin; stem leaves smaller, toothed or entire, becoming linear near top. ***Flowers*** produced in several, narrow, elongate clusters; each flower stalked, ***with 4 small white petals. Fruits flattened, widest near middle to almost circular, 2–4 mm*** (0.1 in) ***long,*** nearly as wide, ***slightly notched at tip,*** containing tiny reddish-brown seeds. **Harvest:** young shoots and leaves in spring. **Preparation:** another member of the mustard family. Use peppergrass greens sparingly in salad with less bitter species. As a potherb boil in 1 or 2 changes of water. Try recipes given for other MUSTARDS. Leaves high in vitamins A and C. Peppery seeds can be used to season meats, soups, and salads. **Related edible species:** Fremont's peppergrass *(L. fremontii)* and FIELD CRESS (next). **Poisonous look-alikes:** none.

Field cress, Cow cress *Lepidium campestre*

Habitat: fields, vacant lots, roadsides, disturbed sites; introduced from Europe. **Identification:** annual or biennial ***herb,*** upright to 60 cm (2 ft) high, ***stems densely hairy.*** Basal leaves 4–8 cm (1.6–3.2 in) long, 1–1.6 cm (0.4–0.6 in) wide, narrow but broadest near tip, coarsely toothed, lobed or dissected along margin; ***stem leaves*** smaller, almost circular in shape, ***lobed at base. Flowers*** produced in several, narrow, elongate clusters; each flower stalked, ***with 4 small, white petals. Fruits flattened,*** widest near tip to ***almost round in outline, 2–3 mm*** (0.1 in) ***long,*** slightly notched at tip, narrowly winged, containing tiny dark brown seeds. **Harvest and preparation:** same as for PEPPERGRASS (preceding). **Related edible species:** PEPPERGRASS and related species. **Poisonous look-alikes:** none.

Field pennycress *Thlaspi arvense*

Habitat: fields, vacant lots, waste areas, other disturbed sites; more common in northern portion of its range. **Identification:** ***annual herb*** 40–80 cm (16–32 in) high; stems branched, upright, smooth. Basal leaves narrow, widest near tip, withering and absent at flowering. ***Stem leaves 2–10 cm*** (0.8–4 in) ***long,*** 0.4–3 cm (0.2–1.2 in) wide, ***lance-shaped*** to narrow but broadest near tip, wavy or coarsely toothed or entire along margin, ***lobed at base, lobes pointed. Flowers*** numerous in narrow, elongate clusters (racemes), each flower stalked, ***with 4 white petals. Fruits flattened, nearly circular in outline, 0.8–1.8 cm (0.3–0.7 in) in diameter, deeply notched at tip, broadly winged,*** containing several tiny black seeds. **Harvest:** young shoots and leaves in spring. **Preparation:** Since plant has characteristic bitterness of MUSTARD family, boil shoots and leaves in 1 or 2 changes of water for 15–25 min. Serve with butter, salt and pepper. Use tender greens if not too bitter with other species in tossed salads. **Related edible species:** pennycress *(T. perfoliatum)* and many other members of mustard family Cruciferae. **Poisonous look-alikes:** none.


Introduced and grows wild. Widespread.

Peppergrass: fruiting plant (Elias).



Field cress: top photo, wilting flowers after being picked and entire plant (Dykeman).


Introduced and grows wild. Widespread.

Field pennycress: flowers, top, and fruits on lower portion of flowering cluster (Dykeman).



Garlic mustard: young plants and flowering plant (Dykeman).


Introduced and grows wild; widespread in East and Midwest

Common chickweed: flowering plants (NYBG).

James chickweed: flowering branch and flower (NYBG).



Garlic mustard *(Also edible summer)* *Alliaria officinalis*
Habitat: partially shaded roadsides, paths in open woods, shady disturbed areas. **Identification:** ***biennial herb, 2nd year growth to 90 cm (3 ft). Leaves triangular to heart-shaped, coarsely toothed, long-stalked, with garlic odor when crushed. Flowers white,*** 6–8 mm (0.2–0.3 in) across, in ***clusters at tips of stems and at leaf bases,*** April–June. Fruits are very ***slender pods (siliques) to 5 cm (2 in) long,*** containing numerous tiny seeds. **Harvest:** young leaves, blossoms, and seed pods in spring and early summer. **Preparation:** chop tender growth raw in salad; for cooked vegetable steam or boil in little water, season with salt and butter. Use for garlic flavor with meats and vegetables. **Related edible species:** no other *Alliaria* species present; many other members of MUSTARD family *(Cruciferae)* are edible. **Poisonous look-alikes:** none.

Common chickweed *(Also edible summer, autumn, winter)* *Stellaria media*
Habitat: yards, disturbed sites, moist and wet areas, cultivated land, woodlands; common weed introduced from Europe. **Identification:** annual herb sometimes to 30 cm (12 in) high; stems weak, trailing along ground before becoming upright, with rows of hairs. ***Leaves opposite,*** simple, ***1–3.5 cm*** (0.4–1.4 in) ***long, about ⅔ as wide,*** usually broadest near base or middle, pointed at tip, entire along margin, rounded at base, lower leaves with a conspicuous leafstalk. ***Flowers single*** or in few-flowered clusters at tips, ***long-stalked, each flower with 5 deeply lobed, white petals that are shorter than sepals.*** Fruits are small reddish-brown capsules 5–8 mm (0.2–0.3 in) long, egg-shaped, containing many small seeds. **Harvest:** Pick tender leaves and stems from young plants any time they are not blooming; available year-round in some regions. Quicker method, pull up the whole plant and cut off tender growth with scissors. **Preparation:** Mild flavored chickweed is excellent by itself or with other, stronger greens. Use generously raw in salads. Boil only 2–5 min; add it to other less delicate greens near end of their cooking period. Serve with butter, seasonings, and a little chopped onion. Also see JAMES CHICKWEED (next). **Related edible species:** JAMES CHICKWEED. **Poisonous look-alikes:** none.

James chickweed *(Also edible summer, autumn)* *Stellaria jamesiana*
Habitat: mountain meadows, seepage areas, woodlands, usually between 1,220–2,590 m (4,000–8,500 ft) elevation. **Identification:** ***small perennial herb*** to 35 cm (14 in) tall from slender roots with thickened tuberlike structures; stems erect or nearly so, branched frequently, hairy. ***Leaves opposite,*** simple, ***4–15 cm*** (1.6–6 in) ***long, about one-fourth as wide, lance-shaped,*** long pointed at tip, entire along margin. ***Flowers produced in loose, spreading clusters at tips*** and at junctions of upper leaves in spring and early summer. ***Each flower with 5 deeply notched white petals.*** Fruits are small tan capsules, 3–5 mm (0.2 in) long, containing many tiny, dark brown seeds. **Harvest:** same as COMMON CHICKWEED (preceding). **Preparation:** Add chickweed to soups and stews. For pancakes, drain and blot 1–2 cups leaves. Blend into prepared pancake batter (2 cups mix to 1½ cups water). Adjust consistency. Fry and serve with butter and tart jelly. **Related edible species:** COMMON CHICKWEED, star chickweed *(S. pubera)*, and mouse-ear chickweed *(Cerastium vulgatum)*. **Poisonous look-alikes:** none.

Cleavers, Goosegrass, Bedstraw *Galium aparine*

Also edible summer

Habitat: wide spread on moist sites, rich woodlands, along streams, lakes, vacant lots and fields. **Identification:** ***annual herb;*** stems weak, slender, often leaning on other plants or rambling along ground, 4-sided, with numerous tiny, stiff, hooked hairs causing plants to cling to clothing; ***leaves in whorls of 8,*** each very narrow but ***widest above middle,*** 4–8 cm (1.6–3.2 in) long, 2–6 mm (0.1–0.2 in) wide, with recurved hairs along margin. Flowers tiny, white, produced in usually 3-flowered, stalked clusters in junction of upper leaves in late spring or early summer. ***Fruits consist of twin, fused, globe-shaped, dry structures 2–4 mm (0.1 in) long, covered with numerous hairs hooked at tip.*** **Harvest and preparation:** Pick young greens in spring when tender. Steam leafy stems in strainer or colander over boiling water for 5–10 min or boil in small amount of water until tender. Serve with butter and seasonings. Combines well with nettle greens. For salad take 3 cups boiled, cooled cleavers and add 1 cup cooked asparagus cut in 1 in lengths, ½ cup slivered nuts, ¾ cup French dressing. Gather fruits in June and July as they turn brown. For excellent noncaffeine coffee substitute, roast fruits in warm oven 150°C (300°F) until dark and crisp, about 1 hr. Grind in blender or crush on any hard surface. Simmer ¾ cup prepared fruits in 1 qt water until medium to dark brown. Strain and serve. **Edible related species:** NORTHERN BEDSTRAW (next). *Note:* The many species of cleavers or bedstraw in North America are difficult to tell apart; however, none of them is known to be poisonous. **Poisonous look-alikes:** none.

Northern bedstraw *Galium boreale*

Habitat: stream banks, fields, open woodlands. **Identification:** ***perennial herb;*** stems usually upright, to 1 m (3.2 ft), slender, 4-sided, smooth. ***Leaves in whorls of 4, each narrowly lance-shaped, 2.5–5 cm*** (1–2 in) ***long,*** 2–7 mm (0.1–0.3 in) wide, with 3 main veins, finely hairy along margins. Flowers tiny, white, produced in compact many-flowered, branched, elongated clusters (inflorescences) at or near growing tips. ***Fruits consist of 2 fused, globe-shaped structures (rarely 1) that are 2–3 mm (0.1 in) in diameter, smooth or with long straight hairs or shorter ones hooked at tip.*** **Harvest and preparation:** same as for CLEAVERS (preceding). **Edible related species:** See CLEAVERS. **Poisonous look-alikes:** none.



Cleavers: flowering stalks (C. S. Webber, Jepson Herbarium).

Northern bedstraw: flowering stalks (NYBG).





Bugleweed: flowering stalk and flowers (NYBG).

Edible valerian: flowering stalks (NYBG).



Bugleweed *Lycopus uniflorus*

Also edible autumn, winter

Habitat: low wet or boggy ground in North, wet woodlands and mountain bogs in South. **Identification:** ***perennial herb*** to 1 m (3.2 ft) tall; stems upright, unbranched or sparingly branched, finely hairy. ***Leaves opposite,*** simple, 3–10 cm (1.2–4 in) long, 0.6–3.4 cm (0.2–1.3 in) wide, ***lance-shaped*** to almost uniformly wide, pointed at tip, ***with few teeth along margin,*** tapering at base, light green and papery; leafstalks absent. ***Flowers produced in compact, many-flowered clusters in junctions of upper leaf stems;*** each flower tiny, ***petals white,*** fused, with 2 upper and 3 lower lobes. Fruits are tiny, flattened, irregular nutlets 1–2 mm (less than 0.1 in) long, with small bumps (tubercles) on top. **Harvest:** Tubers grow best close to the base of old stems in loose sandy soil. Dig tubers from fall through early spring when they are highest in stored nutrients. **Preparation:** Add peeled, sliced tubers to tossed salad or chop fine as mild relish. Boil tubers in salted water until tender, about 10–15 min. Serve with butter and seasonings. For pickles, peel tubers, boil in water about 5 min, drain and cover with wine vinegar. Store for several weeks before using. **Related edible species:** sessile-leaved water horehound *(L. amplectens)* is found in sandy East Coast areas. Other species of *Lycopus* lack tubers. **Poisonous look-alikes:** none.

Edible valerian *Valeriana edulis*

Also edible autumn, winter

Habitat: open moist sites, meadows, prairies, ditches, swamps. **Identification:** ***perennial herb*** to 1.2 m (3.8 ft) from large, elongated root. ***Leaves opposite,*** featherlike (pinnate) divided; ***basal leaves spoon-shaped,*** widest near tip, 12–30 cm (4.7–12 in) long, ***entire or sometimes featherlike (pinnate) divided*** with narrow lateral segments, thick, hairy along margins; stem leaves pinnately divided into few narrow segments, smaller. ***Flowers tiny, produced in*** tightly branched, elongated, ***many-flowered clusters*** at tips in late spring; each flower white to pink, 3–5 mm (0.1–0.2 in) long. Fruits dry, flattened, 1-seeded, egg-shaped, 3–4 mm (0.2 in) long. **Harvest and preparation:** Dig roots in autumn and early spring, when firm. Steam 24 hr or longer to remove disagreeable odor. Then use in soups as you would potato or squash. Dry and grind steamed roots into flour for use in bread, as did the Indians. Bake Indian pit style 2 days. **Related edible species:** Other valerians have been used in folk medicine. **Poisonous look-alikes:** toxicity of look-alikes not well documented.



Wild strawberry: mature fruits and flower (Elias).

Spring beauty: flowering stalk (NYBG).



Wild strawberry *Fragaria virginiana*

Also edible summer

Habitat: open woodlands, margins of woodlands, fields. **Identification:** small perennial herb, lacking distinct stem, sometimes producing runners. ***Leaves basal, compound and 3-parted*** (trifoliolate), leaflets widest near or above middle, 2–10 cm (0.8–4 in) long, sharply toothed along margin, hairy beneath. ***Flowers*** several in short spreading cluster, each ***with 5 white petals*** 8–14 mm (0.3–0.5 in) long. ***Fruits are tiny, hard (achenes), embedded in large, fleshy tissue (receptacle)*** that is 0.5–2 cm (0.2–0.8 in) in diameter, ***red, sweet.*** **Harvest:** one of the best wild fruits. Locate your site early and check regularly from early June for ripe berries. Collect leaves anytime but best in late summer. **Preparation:** Use wild strawberries in any strawberry recipes. For quick beverage, crush handful of berries and mix with 1 cup water and a little sugar. For fruit leather, add ½ tbsp sugar or honey to each cup of fruit. Bring just to boil, cool, and process through food mill. Pour no more than 5 mm (0.2 in) thick onto Teflon cookie sheet. Heat in oven at lowest setting for 6–7 hr. When leathery, roll and seal in plastic wrap. Stores well at any temperature. See basic pie and jam recipes in book's introductory material. For tea high in vitamin C, steep 2 handfulls fresh or ½ cup dried leaves in 1 qt boiling water for 5 min. To dry leaves, spread on clean surface in warm, dry area (sun or shade). When thoroughly dried (use warm oven, if necessary), crumble leaves and store in paper bag in dry place. **Related edible species:** Several are widely distributed, basically alike, and easy to identify. **Poisonous look-alikes:** none.

Spring beauty *Claytonia virginica*

Habitat: rich woodlands, wooded floodplains, wet fields. **Identification:** ***perennial herb*** to 40 cm (16 in) tall, ***from globe-shaped, bulblike tuber 1–5 cm*** (0.4–2 in) ***in diameter;*** stems several, upright, weak, sometimes leaning. ***Leaves*** simple, ***5–14 cm*** (2–5.5 in) ***long, 0.2–2 cm*** (0.1–0.8 in) ***wide, linear*** to narrow but widest above the middle, blade gradually merging with leafstalk. ***Flowering stem with 5–20 weakly stalked flowers, each flower white to pink with dark pink veins, petals 5,*** 1.2–2 cm (0.5–0.8 in) across. Fruits are egg-shaped to nearly globe-shaped capsules 5–10 mm (0.2–0.4 in) long, containing numerous, tiny, dark red seeds. **Harvest:** Because this is a beautiful spring flower, use only where very abundant or when desperately needed. In spring, pick young leaves and dig tubers when identifiable by blossoms. Keep only largest tubers; replant others. **Preparation:** Use leaves as trail nibble or chop a few in green salads. Boil leaves for a few minutes in salted water for edible but not exceptional vegetable. Eat washed tubers raw or add to salads. Boil tubers with jackets in salted water about 10–15 min. Peel and serve whole or mashed, fried, or in salad like potatoes. Tubers also good baked; peel before eating. **Related edible species and poisonous look-alikes:** See ALPINE SPRING BEAUTY (next).

$19.95



Cosmic Healing I

Cosmic Chi Kung

Mantak Chia

Illustrated by Udon Jandee

Cosmic Healing I

Cosmic Healing I builds on the healing aspects of the Universal Tao foundation practices. In Cosmic Healing I the student will learn how to use the Cosmic Healing Chi Kung in combination with color for guiding the healing learn to process in yourself & other, you'll make use of your Personal Stars & connections with the Big Dipper & North Star so as to have the chi to "sweep & clean out" sick energies.

A New Approach to Healing

In Cosmic Healing I Master Mantak Chia, continue to bring the ancient, time-tested wisdom of the Universal Tao System to the Western world. Cosmic Healing I presents a whole new understanding and approach to healing with detailed explanations of self-healing techniques and ways to transform negative, sick energies from them and others.

Hand Techniques for Detoxifying and Rejuvenating the Vital Organs

Learn to develop your most powerful healing potential through the Cosmic Chi Kung combined with your Mind, Eyes, Heart & Intention. The Cosmic Chi Kung encourages your Compassion to bloom so as to enhance your self- healing & your ability to support other in healing them selves.

0 097487 672561

Universal Tao Publications

Alpine spring beauty *Claytonia megarhiza*

Habitat: rocky crevices, rock slides in alpine zone, tundra. **Identification:** ***low perennial herb*** from thick, fleshy, purple to dark-red taproot. ***Basal leaves spreading, forming large rosette,*** leaves 2–15 cm (0.8–6 in) long, ***broadest near tip to almost circular in outline,*** pointed to rounded at tip, entire along margin, gradually tapering and winged at base; stem leaves alternate, linear to narrow and broadest near tip. ***Flowers*** stalked, produced in elongate cluster; each flower 1.2–2.5 cm (0.5–1 in) across, ***with 5 white to pink petals with red veins,*** 6–10 mm (0.2–0.4 in) long. Fruits are tiny, 3-parted, egg-shaped capsules. **Harvest:** Because of habitat and scarcity, use as survival food only. Pick rosettes of leaves or pull up whole plant for fleshy root. **Preparation:** similar to SPRING BEAUTY (preceding). Peel roots before boiling to avoid strong flavor and use like tubers of SPRING BEAUTY. **Related edible species:** SPRING BEAUTY, WESTERN SPRING BEAUTY (next); also Carolina spring beauty *(C. caroliniana),* widely distributed in northern U. S. **Poisonous look-alikes:** To avoid confusion with poisonous lilies, learn to identify leaves or collect when in bloom.

Western spring beauty *Claytonia lanceolata*

Habitat: mid to high mountain slopes, moist woodlands to alpine zone. **Identification:** ***perennial herb*** to 20 cm (8 in) high, ***from nearly globe-shaped,*** bulblike underground ***stem base*** (corm) 1–2 cm (0.4–0.8 in) in diameter; stems 1 to several, upright. Basal leaves 1 or 2, 4–8 cm (1.6–3.2 in) long, broadly lance-shaped; ***stem leaves 2, opposite, 3–6 cm*** (1.2–2.4 in) ***long,*** narrow to broadly lance-shaped, 0.8–2 cm (0.3–0.8 in) wide. ***Flowering stems*** upright, ***with 3–15 stalked flowers, each bowl-shaped, with 5 pink petals*** 0.8–1.2 cm (0.3–0.5 in) long. Fruits are egg-shaped capsules 3–5 mm (0.1–0.2 in) long, containing a few shiny, black seeds. **Harvest and preparation:** Because of habitat and scarcity, use as survival food only. Similar to SPRING BEAUTY. Leaves are edible but not exceptional; boil 10–15 min. Crispy but small tubers are good raw or cooked for about 25 min at about 1,640 m (5,400 ft) altitude. **Related edible species and poisonous look-alikes:** See ALPINE SPRING BEAUTY (preceding).



Alpine spring beauty: flowering plant (NYBG).

Western spring beauty: flowering plant (NYBG).





Miner's lettuce: flowering plants (NYBG).

Canada violet: flower and flowering plant (NYBG).



Miner's lettuce *Montia perfoliata*

Also edible summer (synonym: *Claytonia perfoliata*)

Habitat: valleys, lower mountain slopes, springs, moist sites. Introduced from Europe; miner's lettuce has expanded its range in the East. **Identification:** ***annual herb*** to 30 cm (12 in) high, ***from fibrous root system.*** Leaves mostly basal, simple, 6–20 cm (2.4–8 in) long including the long leafstalk, blade variable, usually broadest below or above middle, entire along margin, smooth; ***stem leaves 2, opposite and fused into a circular disc just below flowering stalk.*** Flower stalk elongate, bearing numerous, whorled, short-stalked flowers, each tiny, with 5 white, clawed petals 3–6 mm (0.1–0.2 in) long. Fruits are tiny, 3-parted capsules containing 1–3 shiny, black seeds. **Harvest:** blossoms, leaves, stems, and roots any time during growing season. **Preparation:** Young upper leaves and stems are excellent as picked or in salads. Include blossoms when available. For salad add chopped hard-boiled eggs and oil and vinegar dressing. For cooked vegetable, boil leaves and stems in very little water until tender; boil young leaves as little as 3–4 min. Excellent source of vitamin C. Wash roots and boil for just a few minutes. Butter and lightly season to bring out water chestnut flavor. **Related edible species:** Siberian miner's lettuce *(M. sibirica)* of southern Alaska. **Poisonous look-alikes:** none.

Canada violet *Viola canadensis*

Also edible summer

Habitat: mixed deciduous woodlands, bluffs, rocky to deep, rich soils. **Identification:** perennial herb with thick underground stem (rhizome); stems upright, smooth, to 40 cm (16 in) high. ***Leaves*** basal and along stem, simple ***4–12 cm (1.6–4.7 in) long, nearly as wide, broadest near base, long pointed at tip,*** toothed along margin, ***heart-shaped at base,*** leafstalks long, ***with small, lance-shaped bract (stipule)*** at base of each leaf. ***Flowers*** produced on upper third of plant, each stalked, ***white often with purple on back, 2–3 cm*** (0.8–1.2 in) ***across, petals 5, lateral ones fringed.*** Fruits are egg-shaped to nearly globe-shaped capsules 5–10 mm (0.2–0.4 in) long, containing several tiny brown seeds. **Harvest:** Strip blossoms from plants, avoiding stems. When possible gather bright green leaves which are young and tender, but even older leaves in late summer are edible. **Preparation:** Leaves and blossoms are superior sources of vitamin C; the leaves are high also in vitamin A. Use blossoms as snack straight from plant or for jelly, jam, syrup, and candy. For jelly, see book's introduction. Use leaves and flowers raw with other ingredients in tossed salad. Cook chopped leaves with minimum water in covered pot for about 15 min. Season and serve alone or with mustard greens. For tea, dry leaves in warm shade and store in paper bag in cool dry places. Steep 1 oz dried leaves per cup of boiling water. **Related edible species:** PALE VIOLET (next), and WOOD VIOLET, and SOUTHERN WOOD VIOLET. It is likely that all of the species of violets are edible, with some more palatable than others. Some, especially yellow-flowered violets, may be cathartic. Thus, moderate initial consumption is advised. **Poisonous look-alikes:** Violet leaves may resemble leaves of other wildflowers, some of which are toxic. So it's safest to collect violet leaves only when flowers are in bloom.

Pale violet *Viola striata*

Also edible summer

Habitat: wooded floodplains, meadows, stream banks. **Identification:** ***perennial herb*** with short thick underground stem (rhizome); stems several, upright or reclining, smooth, to 50 cm (20 in) high. Basal leaves soon withering; ***stem leaves*** simple, ***3–8 cm*** (1.2–3.2 in) ***long,*** as wide or nearly so, ***broadest near base and almost circular in outline,*** pointed to blunt at tip, toothed along margin, shallowly heart-shaped at base, leafstalks long; ***with large, leaflike bract (stipule) at base of each leaf. Flowers*** usually produced at tips of stems, each on a slender stalk, ***creamy white with purplish-brown veins near base, 2–2.5 cm (0.8–1 in) across, petals 5, lateral ones densely fringed, forming spur 3–6 mm*** (0.1–0.2 in) ***long on backside.*** Fruits are egg-shaped to globe-shaped capsules 4–8 mm (0.2–0.3 in) long. **Harvest and preparation:** same as for CANADA VIOLET (preceding). **Related edible species:** CANADA VIOLET. **Poisonous look-alikes:** See CANADA VIOLET for details.

Pokeweed *Phytolacca americana*

Habitat: woodland margins, disturbed sites, waste ground, roadsides, fencerows. **Identification:** ***large, perennial herb*** to 3 m (9.8 ft) tall with thick fleshy roots; stems branched, upright, smooth, ***with disagreeable odor when broken.*** Leaves alternate, 9–30 cm (3.5–12 in) long, 3–12 cm (1.2–4.7 in) wide, broadest near base, pointed at tip, entire along margin; leafstalks to 5 cm (2 in) long. ***Flowers greenish to white, produced in narrow elongate clusters*** (racemes); each flower 2–4 mm (0.1 in) long, petals absent. ***Fruits are 5–12-parted berries, wider than long, 6–10 mm*** (0.2–0.4 in) ***in diameter, green turning purplish-black at maturity.*** **Harvest:** young shoots up to 15 cm (6 in) long in late spring before leaves unfold. Identify from presence of previous year's stalks. Cut stems from perennial root as you would asparagus. *Caution: The root is poisonous; avoid all parts of the plant except young shoots.* If shoots show any purple coloration, avoid them as well as mature stems. For winter use, dig root in fall and plant in large container of soil. After hard freeze move to warm area and water regularly. Harvest shoots as above. **Preparation:** Boil shoots 10 min with 1 or 2 water changes; drain, add fresh boiling water and season, cover, and simmer until tender. Serve like broccoli or asparagus with butter, cheese, or other sauces. For casserole, alternate layers of cooked pokeweed shoots, white sauce, and sliced, boiled eggs. Top with seasoned bread crumbs. Bake 30 min at low temperature 165°C (330°F). Boiled, peeled shoots may also be pickled. **Related edible species:** none. **Poisonous look-alikes:** None, but see *caution* above.



Pale violet: flowering plant (Mohlenbrock).

Pokeweed: fruiting stalks (Crow). Flowers (Elias). Young shoots attached to cut root top (Dykeman).


Introduced in West



Japanese knotweed: young shoots (Dykeman). Flowering branch (Feldman).

Wintercress: entire plant, leaf, and flowering head (Dykeman).



Japanese knotweed *Polygonum cuspidatum*

Habitat: disturbed and waste sites, vacant lots, roadsides; introduced weed from Asia. **Identification:** ***large perennial herb to 3 m*** (9.8 ft) ***high,*** often forming dense colonies; ***stems*** upright, ***with hollow core,*** smooth, mottled, frequently branching. ***Leaves*** alternate, simple, ***10–16 cm*** (4–6.3 in) ***long, 6–12 cm*** (2.4–4.7 in) ***wide, broadest near base,*** long tipped, ***wavy along margin,*** squared to rounded at base, almost leathery; ***leafstalk*** stout and ***enclosed at base by membranous sheath that also surrounds stem.*** Flowers produced in elongate, branched clusters in junctions of upper leaves, each flower tiny, 1–2 mm (less than 0.1 in) long, white. Fruits are dark brown, shiny, winged nutlets. **Harvest:** Locate papery dry stalks of previous year. Gather young shoots up to 30 cm (1 ft) long for potherb, up to 90 cm (3 ft) for other use. **Preparation:** Boil tips of young shoots in salt water or steam 4–5 min. Serve like ASPARAGUS, hot on toast with butter or white sauce, or cold in salad. Also, force cooked shoots through mill for puree. Add salt, butter, sweetener, to taste, and reheat. Or prepare casserole of cooked young shoots, bread crumbs, grated cheese, cream, and seasonings; bake at 200°C (390°F) until top is browned. Peel older stalks 30–90 cm (1–3 ft) and use like rhubarb. For sauce combine 4 cups peeled and cut shoots, 1 cup sugar, and nutmeg. Simmer until soft. Serve hot or cold. See basic jam recipe in book's Introduction. Prepare pie from peeled shoots using rhubarb pie recipes. **Related edible species:** giant knotweed *(P. sachalinense),* Alaskan knotweed *(P. alaskanum),* AMERICAN BISTORT, ALPINE BISTORT, LADY'S THUMB and others. Some may cause a light-sensitive skin reaction. **Poisonous look-alikes:** none.

Wintercress *Barbarea vulgaris*

Also edible autumn, winter

Habitat: fields, wet meadows, ditches, roadsides; common and widespread, introduced from Europe. **Identification:** ***biennial or perennial herb*** to 0.7 m (28 in) high; stems erect, sparingly branched above. Lower ***stem leaves*** broadest near or above middle, 7–15 cm (2.8–6 in) long, ***deeply lobed along sides,*** stalked; leaves of upper stem much smaller, stalkless and lobed at base, coarsely toothed. ***Flowers from April to June, numerous in cylinder-shaped clusters, each flower*** narrow, stalked, ***with 4 narrow, yellow petals. Fruit pods very narrow, 1.5–3 cm (0.6–1.2 in) long, tipped with short beak to 3 mm (0.1 in) long,*** splitting open lengthwise to release tiny seeds. **Harvest:** Pick leaves after frosty weather and into spring until flower stalks appear. Leaf rosettes grow on warm winter days; become bitter in spring. Leaves blanch and lose bitterness if you tie them in bundle with plant rooted and cover with a bucket. Pick buds and flowers until blooming is over, April or May. **Preparation:** Use early and blanched leaves in salads with other late-winter foods such as COMMON DAY LILY tubers and WATERCRESS. Boil later, bitter leaves in 2 changes of water until tender and treat as for BLACK MUSTARD (next). Buds and flowers are excellent with cheese sauce. Cover clusters with boiling water for 1 min. Drain, cover with fresh boiling water, heat, and boil 3 min more. Drain, season, and cool for 5 min. **Related edible species:** early wintercress *(B. verna).* **Poisonous look-alikes:** none.

Black mustard *(Also edible summer)* *Brassica nigra*

Habitat: common and widespread, fields, yards, disturbed sites; introduced from Europe. **Identification:** ***medium-size to large annual herb*** to 1.2 m (4 ft) high; stems erect, hairy on lower parts. Leaves alternate, stalked, usually broadest above or near the middle, 8–18 cm (3.2–7 in) long, ***lower leaves lobed, upper leaves narrower, wavy toothed. Flowers few in narrow, elongate, loose clusters,*** each ***flower*** stalked, about 1 cm (0.4 in) across, ***with 4 yellow petals. Fruits*** narrow linear ***capsules 1–2 cm*** (0.4–0.7 in) ***long, roughly 4-sided,*** upright, ***beaked, beak 1–2 cm*** (0.4–0.8 in) ***long,*** splitting open lengthwise to release tiny seeds. **Harvest:** leaves very early in spring or blanch later leaves as with WINTERCRESS (preceding). Pick buds and flowers until nearly all flowers have opened. Avoid bitter leaves. For seeds, harvest during summer when oldest pods open. Pile them on fine cloth or plastic tarp and sun-dry for several days. Beat with flail to release seeds, remove stalks, winnow seed from chaff. **Preparation:** Use early and blanched leaves in salads. Boil older greens with 1 change of water for about 30 min. Season with butter and vinegar or mix with crumbled bacon and chopped wild onions. Top with hard-boiled egg slices and French dressing or vinegar. Excellent source of vitamins A, B, and C. For buds and flowers, treat as WINTERCRESS. Sprinkle seeds lightly on salad. To make mustard, grind seeds in food mill; use dried. Or for mustard spread, combine equal parts mustard powder and oven-browned flour with half-and-half mix of vinegar and water. Add other spices to taste. **Related edible species:** field mustard *(B. rapa),* Chinese mustard *(B. juncea),* and others. **Poisonous look-alikes:** none.

Marsh marigold, Cowslip *Caltha palustris*

Habitat: freshwater swamps, wet meadows, along streams, ponds, lakes. **Identification:** ***perennial herbs*** to 70 cm (28 in) high; stems partially spreading to upright, hollow, smooth. ***Basal leaves long-stalked, blade rounded to almost kidney-shaped, 1–2.8 cm*** (0.4–1.1 in) ***long, 0.4–2.2 cm*** (0.2–0.8 in) ***wide,*** rounded at tip, toothed along margin, heart-shaped at base; stem leaves smaller, lacking stalks. ***Flowers large, showy,*** 2.5–4 cm (1–1.6 in) across, ***with 5 bright yellow petallike sepals.*** Fruits are elongate, somewhat rounded, 1–1.7 cm (0.4–0.7 in) long, splitting open along one side when mature to release small seeds. **Harvest:** Cut leaves from plant when young, best before flowers open. Pick tightly closed buds for pickling. **Preparation:** *Raw leaves and buds are poisonous until properly treated!* Wash leaves and cover with boiling water. Reheat to boiling, then drain. Repeat 2 or 3 times, then cook in very little water until tender. Drain and serve with butter and seasonings or with cream or cheese sauce. For pickles, treat buds with boiling water as described for leaves. Do not boil. Drain and pack in jars. Cover with hot pickling liquid and seal. Store for at least a month before eating. Do not consume used pickling juice. To make pickling liquid, slowly add mix of ¼ cup salt, ½ cup sugar, 1 tbsp ground mustard, and 1 tbsp celery seed to 2 cups vinegar and 1 cup water. Boil 10 min with stirring. **Related edible species:** none. **Poisonous look-alikes:** Flowers resemble COMMON BUTTERCUPS yet leaves are very different.


Introduced and grows wild. Widespread.

Black mustard: entire plants (NYBG).

Marsh marigold: plants in typical streamside habitat and entire plant (Dykeman).



Cosmic Self-Massage

Taoist Way of Rejuvenation

Mantak Chia



Evening primrose: basal leaves (Dykeman). Flowering stalks (Pawloski).

Sow thistle: fruiting head, left, and flower (Mathisen).



Evening primrose *Oenothera biennis*

Also edible autumn, winter

Habitat: disturbed sites, along roads, prairies, fields. **Identification:** biennial herb of 1.6 m (5.3 ft) high, from elongated taproot; stems upright, hairy. Leaves of first year in low rosette; second year leaves on flower stalk, alternate, lance-shaped to broadest near middle, 8–18 cm (3.2–7 in) long, 2–6 cm (0.8–2.4 in) wide, pointed at tip, entire to toothed along margin, tapering at base, hairy. ***Flowers second year, many in terminal, elongated cluster, each flower with narrow, tubular calyx 1.5–3 cm*** (0.6–1.2 in) ***long, 4 large spreading, bright yellow petals 1.5–3 cm*** (0.6–1.2 in) ***long. (Flowers open after dusk and often close by midmorning.) Fruits are cylinder-shaped, angled capsules 1–4 cm*** (0.4–1.6 in) ***long,*** containing many small, reddish seeds. **Harvest:** Dig taproots of first year growth between autumn and early spring. Pick leaves from rosettes in early spring or even earlier from areas clear of snow. **Preparation:** Peel taproots and boil in 2 changes of water for 20–30 min. Serve with butter and seasonings or slice and fry. Cook sliced roots with meat or in stews, partially boiling roots first if flavor is too strong. Simmer boiled roots in sugar syrup for 20–30 min until candied. Peel leaves and use sparingly in salads. Or boil leaves 15–20 min in 2 changes of water and serve with butter or vinegar. **Related edible species:** other species of this large genus. **Poisonous look-alikes:** none, but don't confuse leaves with those of other early-blooming species.

Sow thistle *Sonchus arvensis*

Habitat: disturbed sites such as roadsides, fields, railroad right-of-ways, gravel banks; introduced weed from Europe. **Identification:** Not to be mistaken for the more common and generally more palatable thistles of the *Cirsium* genus, sow thistle is a ***perennial herb*** to 1 m (3.2 ft) high with deep vertical and spreading horizontal coarse roots; stems upright, smooth, with milky sap. ***Leaves*** alternate, simple, broadest near or above middle, 10–35 cm (4–14 in) long, 4–14 cm (1.6–5.5 in) wide, ***deeply lobed along margin, upper leaves less so, spiny-toothed, lobed leaf bases clasping stems,*** usually smooth. ***Flowering heads*** produced in loosely branched, elongated, erect cluster, each head ***3–5 cm*** (1.2–2 in) ***across,*** with lance-shaped bracts on the outside and many small ***yellow flowers*** within. Fruits are small, dark-brown nutlets 2.5–3 mm (0.1 in) long. **Harvest:** Locate by noting concentrations of mature plants the previous year. Pick when only a few inches tall; leaves become increasingly bitter with age. *Caution: Sow thistle occasionally contains toxic levels of nitrates.* **Preparation:** If not too bitter, cut and mix leaves with other, blander salad greens. Boil in very little water for 3–4 min, change water, and then boil until tender. Serve with butter and seasonings or vinegar. If too bitter, mix with blander greens such as LAMB'S QUARTERS. **Related edible species:** Several species of the *Sonchus* genus are variously distributed and edible when very young. Some have leaf spines that must be removed. **Poisonous look-alikes:** none.

Prickly lettuce *Lactuca serriola* (synonym: *L. scariola*)
Habitat: disturbed sites such as fields, roadsides, vacant lots; introduced weed from Europe. **Identification:** ***annual or biennial herb*** to 2 m (6.6 ft) high, ***with milky juice in stems and leaves,*** stems upright, slender, usually armed with spreading prickles. Stem ***leaves*** alternate, ***lance-shaped,*** 5–25 cm (2–10 in) long, 1.5–12 cm (0.6–4.7 in) wide, ***with several deep lobes or lobeless, toothed and spiny along margin*** and spiny along main vein on lower leaf surface, with pointed lobes at base and often clasping stem. ***Flowering heads*** sparingly produced in branched clusters, each head ***1–1.5 cm*** (0.4–0.6 in) ***long,*** 3–6 mm (0.1–0.2 in) ***across, containing 6–12 yellow flowers.*** Fruits are tiny gray to brown nutlets 3–4 mm (0.1 in) long. **Harvest:** Like other wild lettuce species, prickly lettuce is good only when very young. Pick leaves when plants are less than 20 cm (8 in) tall. **Preparation:** Use alone or with other greens in tossed salad. Boil leaves in very little water for 2–3 min. Serve with butter and seasonings. For wilted lettuce pour boiling water over lettuce leaves and let sit for 5 min. Drain. Make dressing of 3 slices of crisp bacon crumbled into ¼ cup hot vinegar with 1 tsp sugar and ½ tsp salt. Pour over hot lettuce. *Caution: Large quantity of raw young leaves may cause digestive upset.* **Related edible species:** many species of the *Lactuca* genus widely distributed; most noticeable of these is wild lettuce *(L. canadensis),* which lack prickles on leaves and lower stem. **Poisonous look-alikes:** none.

Dandelion *Taraxacum officinale*
Also edible autumn, winter

Habitat: lawns, yards, disturbed sites; common weed introduced from Europe. **Identification:** ***perennial herb, with large,*** sometimes branched ***taproot. Leaves all basal,*** 8–40 cm (3.2–16 in) long, 0.8–14 cm (0.3–5.5 in) wide, widest near tip, rounded to pointed at tip, ***variously and irregularly lobed along margin,*** tapering to narrow base, hairy beneath, ***with milky juice.*** Flowers produced throughout spring in large heads at tip of hollow stalks. ***Flowering heads 2–5 cm*** (0.8–2 in) ***across, composed of numerous, small, narrow, orange-yellow flowers, remaining closed on cloudy days. Fruits*** on elongated, upright hollow stalks, ***forming delicate ball*** composed of many tiny seeds each tipped with white featherlike tuft (pappus) easily dispersed by wind. **Harvest:** Best lawn areas are those with taller grass. Dig roots with crown at top of root and leaves attached from time leaves (rich in vitamin A) appear until they are too bitter to use. Dig older roots in fall and winter. Cut out developing bud clusters and pick fully opened flowers in spring. **Preparation:** For flowers, leaves, and older roots, see CHICORY. Peel young roots, slice thin, and boil in 2 changes of water for about 20 min, adding pinch of baking soda to first water. Serve with butter and seasonings or saute cooked slices in butter until brown. Season with paprika. Boil buds just a few minutes, butter and serve. Dip blossoms in fritter batter; fry in oil and serve with syrup or garlic salt. **Related edible species:** several other species of *Taraxacum,* all similar to common dandelion in appearance/preparation. Also, CHICORY in early growth. **Poisonous look-alikes:** none.


Introduced and
grows wild.
Widespread.

Prickly lettuce: flowering branch and entire plant (Kavasch). Leaves (Dykeman).

Dandelion: flowering plant (Elias).

Introduced and
grows wild.
Widespread.

Goat's beard *Tragopogon pratensis*

Habitat: roadsides, fields, other disturbed sites; introduced from Europe. **Identification:** ***perennial*** or biennial ***herb*** to 76 cm (30 in) high with taproot and milky juice; stems upright. ***Leaves*** alternate, linear, ***grasslike, 15–30 cm*** (6–12 in) ***long, 1–2 cm*** (0.4–0.8 in) ***wide,*** pointed at tip, entire along margin, base partially circling stem, smooth. ***Flowering heads*** produced singly at tip of stems, ***resembling dandelion, with 8 lance-shaped outer bracts, many yellow flowers.*** Fruiting heads globe-shaped, light, fluffy, consisting of numerous small nutlets, each tipped with light, featherlike bristles. **Harvest:** See SALSIFY (preceding). Roots of goat's beard may be smaller, tougher, less palatable. **Preparation:** Same as SALSIFY. Cool boiled roots and saute in oil until browned or prepare like potatoes. Roasted and ground roots make coffee substitute. Use very young leaves in salad if not bitter or boil for 5–10 min and serve with butter and seasonings. **Related edible species:** SALSIFY, yellow goat's beard *(T. dubius)*. **Poisonous look-alikes:** none in the flowering stage.

Common milkweed *Asclepias syriaca*

Also edible summer

Habitat: fields, meadows, roadsides, woodland margins. **Identification:** ***perennial herb*** to 1.8 m (6 ft) tall; stems upright, usually unbranched, hairy. ***Leaves opposite,*** broadest near base or middle, ***10–28 cm*** (4–11 in) ***long, 4–12 cm*** (1.6–4.7 in) ***wide,*** pointed at tip, entire to wavy along margin, ***thick, leathery, hairy above, with milky sap. Flowers in dense, rounded heads 6–10 cm*** (2.4–4 in) ***across, each flower rose, dull purple to greenish-white,*** 8–12 cm (3.2–4.7 in) long, with 5 reflexed petals. ***Fruits are elongated pods,*** broadest near base and gradually tapering to curved point, 8–14 cm (3.2–5.5 in) long, covered with small, soft, green projections. Seeds small, each with conspicuous, soft, featherlike hairs at one end. **Harvest:** Cut new shoots when less than 20 cm (8 in) tall. Pick newly opened leaves until buds are formed; then pick clusters of buds and flowers. Later pick firm pods 2–3 cm (0.8–1.2 in) long. **Preparation:** To remove bitterness from all parts, cover with boiling water and bring back to boil. Discard water and repeat 2–3 times with boiling water. Do not use cold water in process. Cook treated shoots like ASPARAGUS. After treatment boil young leaves, bud clusters, and pods until tender, usually 10–15 min. Serve with butter and seasonings or with sauce. Use treated pods in soup like okra *(Hibiscus esculentus)*. **Related edible species:** Showy milkweed *(A. speciosa)* is good. **Poisonous look-alikes:** all narrow-leaved milkweed species, especially BUTTERFLY WEED; some are more toxic than others. Young DOGBANE, also with milky sap, has branches (common milkweed does not) and its young shoots lack hairs.



Goat's beard: fruiting head, flower bud, rootstock (Dykeman).

Common milkweed: flowering head and entire plant (Elias).





Fireweed: flowering stalk (Elias). Flowers (NYBG).

Alfilaria: entire plant with flowers and fruits (Ross).


Introduced and grows wild. Widespread.

Fireweed *Epilobium angustifolium*

Also edible summer

Habitat: woodlands, ravines, clearings; commonly grows after fires. **Identification:** ***perennial herb*** 1–2 m (3.2–6.5 ft) high; stems erect, usually single, smooth. Leaves alternate, narrow and broadest near base, 5–20 cm (2–8 in) long, to 3 cm (1.2 in) wide, nearly stalkless, long-pointed at tip, entire or nearly so along margin. ***Flowers*** many on elongate spikes; each flower stalked, spreading, ***with 4 pink to purple, rarely white, clawed petals*** 1–2 cm (0.4–0.8 in) long. ***Fruit a narrow capsule 3–8 cm*** (1.2–3.2 in) ***long,*** with reddish or purplish cast, 4-parted. **Harvest:** Cut young shoots in spring; new leaves, flower bud clusters, and mature stems later. Older leaves are good for tea but too bitter for potherb. **Preparation:** Not a very tasty food plant but widespread, abundant, easy to identify, and has several edible parts. Cook young shoots like ASPARAGUS and season with butter, hollandaise, or cheese sauce. Use young leaves and later flower-bud clusters in salad with other greens. For potherb, stir 4 cups small leaves and 3 tbsp water into 2 tbsp melted butter in skillet over high heat. Cover and cook 2–3 min, season and serve. Boil flower bud clusters 10–15 min and serve with butter, salt and pepper. Peel stems too old for cooking and chew on raw pith or use pith in soups. Dry mature leaves and blend with other suitable leaves for a tea. **Related edible species:** dwarf fireweed *(E. latifolium)* and other related but smaller species. **Poisonous look-alikes:** none.

Alfilaria, Filaree, Storksbill *Erodium cicutarium*

Habitat: fields, pastures, roadsides, other disturbed sites; common weed introduced from Europe. **Identification:** ***annual or biennial herb*** with 1 to several spreading stems, hairy. ***Leaves*** emerge at base and along stem, alternate, ***2–10 cm*** (0.8–4 in) ***long, featherlike (pinnate) compound, leaflets (pinnae) cleft and coarsely toothed. Flowers*** 2–10 in small, branched, rounded-headed cluster at tips of shoots; each flower about 2.5 cm (1 in) across, ***with 5 rose-purple petals.*** Fruits are narrow, elongate capsules 2–4 cm (0.8–1.6 in) long, opening from base toward tip. **Harvest:** Gather young, overwintered leaves in early spring when other wild foods are scarce. Be certain leafstalks are hairy. **Preparation:** Chop leaves for salad with other greens. Boil leaves in lightly salted water until tender, about 10–20 min. Serve with butter, lemon juice, and herbs. **Related edible species:** none recommended. **Poisonous look-alikes:** Leaves resemble those of the parsley family including POISON HEMLOCK. Picking only hairy-stemmed leaves very early in spring should help you avoid errors. Be sure of identification!

Live-forever, Orphine *Sedum purpureum*

Also edible autumn, winter

Habitat: roadsides, open slopes, woodlands, and disturbed sites; introduced European weed. **Identification:** ***perennial herb*** to 80 cm (32 in) tall, from fleshy tubers. ***Stems upright, succulent; leaves*** alternate or whorls of 3, simple, ***fleshy, 3–6 cm*** (1.2–2.4 in) ***long***, 1–3 cm (0.4–1.2 in) wide, pointed or blunt at tip, entire or toothed along margin, green to bluish-green. ***Flowers*** produced in a compact, branched cluster at tips of branches, each flower bisexual, 6–10 mm (0.2–0.4 in) across, ***with 5 reddish-purple to deep pink petals.*** Fruits small capsules 4–6 mm (0.2 in) long, splitting open along 1 side only. **Harvest:** young leaves in spring and tubers from fall through spring, as long as they are firm and crisp. **Preparation:** Add raw, very young leaves to salads. Boil leaves gathered through early summer for 5–10 min and serve as cooked green. Pour hot pickling liquid over tubers and leave for several days before eating. For pickling liquid boil 2 tbsp mixed pickle spices in cloth bag in solution of 1 qt vinegar and 1 cup sugar. Boil tubers like those of COMMON DAY LILY for about 20 min. Serve with butter and seasonings. **Related edible species:** Other *Sedum* species provide edible leaves; some are more pungent than others. Roseroot *(S. rosea)* is the most frequently used. **Poisonous look-alikes:** none.

Lady's thumb *Polygonum persicaria*

Also edible summer

Habitat: disturbed sites, especially low wet ground, along roadsides, lakes, streams, ponds; widespread weed introduced from Europe. **Identification:** ***annual herb*** to 1 m (3.2 ft) high; stems soon branching, spreading to upright, smooth. ***Leaves*** alternate, ***narrowly lance-shaped,*** 4–12 cm (1.6–4.7 in) long, 0.6–3 cm (0.2–1.2 in) wide, ***often with irregular or triangular purplish spot above,*** pointed at tip, wavy along margin, tapering at base, ***enclosed at base by membranous sheath that also surrounds stem.*** Mature stems reddish. ***Flowers*** numerous, dense ***in cylinder-shaped spikes*** 2–4 cm (0.8–1.6 in) long, each flower ***pink to rose.*** Fruits are tiny, broadly egg-shaped nutlets 2–2.5 mm (0.1 in) long. **Harvest:** Gather young leaves, mainly in spring but later if not too peppery. **Preparation:** Add chopped raw leaves to tossed salad. Boil leaves in small amount of water for 5–10 min. Serve with vinegar. **Related edible species:** ALPINE BISTORT, JAPANESE KNOTWEED. Known as the smartweeds, other *Polygonum* species may be as good as lady's thumb, and none are known to be poisonous. *Caution: Some species may cause light-sensitive reactions.* **Poisonous look-alikes:** none.



Live-forever: flowering head (Kavasch). Entire plant (Speas).

Lady's thumb: entire plant and stem (Dykeman).


Introduced and
grows wild
in moist soils

Cosmic Self-Massage

Taoist Way of Rejuvenation

Mantak Chia

Edited by:

Dena Saxer

Common burdock *Arctium minus*
Also edible summer, autumn

Habitat: roadsides, vacant lots, disturbed sites; introduced from Europe and Asia. **Identification:** ***biennial herb*** to 1.8 m (6 ft) high; stems upright, often branched, usually smooth. ***Leaves*** alternate, ***basal leaves large, 30–50 cm*** (12–20 in) ***long, 20–30 cm*** (8–12 in) ***wide,*** widest near base, ***deeply lobed at base,*** with conspicuous hollow stalk; upper-stem leaves smaller and not lobed at base. ***Flowering heads produced during second year along upper stems*** or in branched elongated clusters; heads 1.7–2.8 cm (0.7–1.1 in) across, outer bracts spine-tipped; ***flowers pink to purple***. Seeds small, hard nutlets 4–6 mm (0.2 in) long. **Harvest:** Dig roots of first-year plants during summer, later if necessary. Pick first-year basal leafstalks and young flower stalks of second year. **Preparation:** Peel roots, slice ½-in thick and boil 20 min with pinch of baking soda. Change water and boil until tender. Serve with butter and seasonings, or mash pieces and make fried patties. Peel flower stalk, removing all green rind. Eat like celery, slice into salad, or boil until tender. Good in casseroles and many other recipes. Simmer pieces of cooked flower stalk in maple syrup to make candy. Eat peeled leafstalks raw or boiled, but since they are hollow, there's not much left after peeling. **Related edible species:** Just as good, great burdock *(A. lappa)* is larger, with larger burrs on solid leafstalks. **Poisonous look-alikes:** Leaves resemble rhubarb leaves but flowers are greatly different.

Salsify, Oyster plant *Tragopogon porrifolius*

Habitat: roadsides, fields, railroad right-of-ways, other disturbed sites; introduced weed from Europe. **Identification:** ***biennial or perennial herb*** to 1 m (3.2 ft) with long taproot and milky juice; ***stems*** upright, ***swollen just below flowering heads.*** Leaves alternate, lance-shaped, 18–32 cm (7–12.6 in) long, to 2 cm (0.8 in) wide, long-pointed at tip, entire along margin, base circling stem. ***Flowering heads*** solitary, ***usually 3–4 cm*** (1.2–1.6 in) ***long, with 6–11 lance-shaped outer bracts and numerous purple flowers.*** Fruiting heads globe-shaped, fluffy, consisting of many small nutlets, each tipped with featherlike bristles. **Harvest:** This is the cultivated species of salsify or oyster plant that also grows wild. Roots and leaves must be harvested before plant produces flowerstalk. This is a problem since grasslike leaves grow among leaves of many other plants. Learn to recognize leaves so you can harvest them and dig roots while still palatable. **Preparation:** Scrub and scrape roots as you would carrots, putting them in cold water to prevent discoloring. Cut into ½-in slices. If they are tough, add pinch of baking soda to cooking water and boil for 10 min, then change water and cook until tender. Drain and serve with butter and seasonings or with white sauce. For other uses see GOAT'S BEARD (next). **Related edible species:** GOAT'S BEARD. **Poisonous look-alikes:** none in flowering stage.



Common burdock: flowering stalk (Speas). Basal leaves (Dykeman).

Salsify: flowers, side view (NYBG). Flower (Ross).




Introduced and
grows wild.
Widespread.

Bull thistle: young plant (Dykeman). Flowering head (Elias).

Chicory: basal leaves and young plants (Dykeman). Flowers (NYBG).


Introduced and
grows wild.
Widespread.

Bull thistle *Cirsium vulgare*

Habitat: fields, meadows, roadsides, disturbed sites; introduced from Europe and Asia. **Identification:** ***biennial herb*** to 1.8 m (6 ft) high, from taproot; ***stems*** upright, hairy, ***winged, wings lobed and armed with spines. Leaves*** alternate, broadest near or above middle, ***deeply and variously dissected along margin,*** 8–30 cm (3.2–12 in) long, 4–12 cm (1.6–4.7 in) wide, ***stiff, spiny,*** stiffly hairy above, with soft white to green hairs below, leaf bases extending onto stem. ***Flowering heads*** second year, several, outer bracts spiny, 2–4 cm (0.8–1.6 in) long; flowers ***purple.*** Seeds are hard, 3–4 mm (0.2 in) long and tipped with bristles. **Harvest:** Dig roots of first-year growth (thistles without stems). With gloves and knife, harvest leaves and young second-year stems at top of root early in growing season. **Preparation:** Peel young stems and remove spines from leaves before using raw in salad or boiling until tender for green vegetable. Remove all spiny covering from core of leaf bases. Boil cores with washed, peeled roots for about 15 min, changing water if necessary to remove bitterness. Serve salted with butter or vinegar. Slice boiled roots and fry until browned. Boil roots several hours until mushy, dry and grind into flour. Because of spines, you may prefer to use thistles only as survival food. **Related edible species:** Many species of thistles are available; some are more palatable than others. **Poisonous look-alikes:** HORSE NETTLE is a low herb with prickly stems but no spines on leaves.

Chicory *Cichorium intybus*

Also edible autumn, winter

Habitat: roadsides, fields, vacant lots, other disturbed sites; introduced weed from Europe. **Identification:** ***perennial herb*** to 1.5 m (5 ft) high, ***with large deep taproot;*** stems erect or nearly so, often branching. ***Leaves*** alternate, lance-shaped to broadest above middle, ***10–32 cm*** (4–12.6 in) ***long,*** 2–8 cm (0.8–3.1 in) wide, upper leaves reduced, ***toothed and often lobed along margin,*** sap milky. ***Flowering heads produced along upper part of stems in junctions of upper smaller leaves; each head*** 1–1.6 cm (0.4–0.6 in) long, ***3–4 cm*** (1.2–1.6 in) ***across in flower, containing many bright blue, rarely pink or white, 5-lobed flowers.*** Fruits are tiny, brown or black nutlets 2–4 mm (0.1 in) long. **Harvest:** Pick leaves, including crown at top of root, as early as possible. Dig root, fall through spring. Chicory leaves are similar to those of DANDELION; collect and use leafy parts of the two together. **Preparation:** Slice bleached underground portion of leaf crown for use raw in salad, along with oil and vinegar or with other spring edibles. Boil crown bases about 5 min and serve with butter and seasonings. Same for leaves but water changes may be needed to remove bitterness, especially later in spring. For coffee substitute, scrub roots and roast slowly in oven until brown throughout. Grind and brew like coffee. **Related edible species:** none, but similar to DANDELION in early stages. **Poisonous look-alikes:** none.

Henbit *Lamium amplexicaule*

Habitat: fields, yards, vacant lots, disturbed sites; introduced from Eurasia, common and widespread. **Identification:** small ***annual herb*** to 40 cm (16 in) tall; ***stems*** usually branching with upper parts upright, ***4-sided. Leaves opposite,*** mainly on lower half of stem, 0.7–3.4 cm (0.3–1.3 in) long, ***nearly rounded, coarsely round-toothed along margin,*** heart-shaped at base, hairy above, lower leaves long-stalked. ***Flowers purple,*** produced near tip, each ***narrow, funnel-shaped,*** 12–18 mm (0.5–0.7 in) long, ***2-lipped,*** lower lip 2-lobed, upper lip 3-lobed, hairy on outer surface. Fruits are 4 small nutlets, partially enclosed by persistent calyx. **Harvest:** young leaves and shoots in spring. **Preparation:** Combine with other greens in salads; use young leafy shoots as potherb. For spiced henbit, chop 4 cups shoots, cover with water, and boil 10 min. Separately melt 3 tbsp butter or margarine, add 1 tsp curry powder, 2 whole cloves, and ¼ tsp ground cinnamon. Stir and cook 1 min. Stir in 2 tbsp flour and cook 1 more min. Add ½ cup water from boiling henbit and stir until smooth. Add cooked henbit and ¾ cup sour cream. Simmer 15 min gently. **Related edible species:** Henbit *(L. purpureum),* with the same distribution, is very similar except leaves are stalked. **Poisonous look-alikes:** none.

Wood violet *Viola palmata*

Also edible summer

Habitat: wooded floodplains, rich deciduous forests, especially on slopes and ledges. **Identification:** ***perennial herb*** from thick, elongated underground stem (rhizome); above ground stem absent. ***Leaves*** simple, ***6–12 cm*** (2.4–4.7 in) ***long,*** often wider, broadest near base, ***blade deeply 5- to 11-lobed,*** lobes variously toothed, smooth or hairy, leafstalks long, to 20 cm (8 in); with linear to narrowly lance-shaped bracts (stipules) at base of each leaf. ***Flowers produced singly at tip of stalk as long as leaves, deep reddish-violet to violet,*** 1.7–4 cm (0.7–1.6 in) across, petals 5, lateral ones bearded, with short spur in back. Fruits are egg-shaped capsules 6–12 mm (0.2–0.5 in) long. **Harvest:** Gather flowers, leaving stems behind. Give preference to bright-green, young, tender leaves; but older darker-green summer leaves are edible too. **Preparation:** Use fresh flowers as trail snack or for jelly, jam, syrup, candy. For jelly, cover 2 cups flowers with boiling water in jar and leave overnight. Then strain and discard flowers. Add juice of 1 lemon and 1 pkg pectin. Bring to boil and add 4 cups sugar. Boil again for 1 min. Pour into sterilized jars and seal. For syrup, pour 2 cups boiling water over 6 cups flowers and leave overnight. Strain and discard flowers. Combine liquid with 2 cups sugar. Boil until syrup thickens. Store in covered jars in refrigerator. For other uses, see CANADA VIOLET. **Related edible species:** CANADA VIOLET, PALE VIOLET, western mountain violet, *(V. purpurea),* and southern wood violet *(V. hirsutula).* It is likely that all of the violet species are edible, with some more palatable than others. Some may have a cathartic effect. **Poisonous look-alikes:** Violet leaves resemble leaves of other wildflowers, some of which are toxic. So it's safest to collect leaves only when flowers are in bloom.


Introduced and
grows wild.
Widespread.

Henbit: flowering stock (Elias).

Wood violet: flowering plant (Elias).





Orange-flowered jewelweed: flowering plant (Dykeman). Young plant (Elias).

Yellow-flowered jewelweed: flowering stalks (Elias).



Orange-flowered jewelweed, Spotted touch-me-not *Impatiens biflora*

(synonym: *I. capensis*)

Habitat: widespread in wet areas, along streams, ponds, springs, swamps, low moist woodlands, floodplains, bottomlands. **Identification:** annual herb; ***stems*** upright, to 1.5 m (5 ft) high, branched, ***very juicy,*** smooth. Leaves alternate, 4–12 cm (1.6–4.7 in) long, 3–7 cm (1.2–2.8 in) wide, broadest at or below middle, blunt- or round-toothed along margin, long-stalked. Flowers showy, in few-flowered, spreading clusters; each ***flower*** stalked, ***with conspicuous saclike spur in rear, orange to orange-yellow spotted with reddish, yellow, or white spots on face. Fruit*** elongate, cylinder-shaped capsule 1.5–2.5 cm (0.6–1 in) long, at maturity ***exploding suddenly when touched to scatter seeds.*** **Harvest and preparation:** For potherb, pick ***young shoots*** to 15 cm (6 in) high; wilts quickly, so use immediately. Cover with water; boil 10–15 min, draining and adding fresh boiling water twice. Season and butter. *Caution:* Frequent use as a potherb is not recommended because of abundance of calcium oxalate crystals. Seeds: As pods ripen, shake plant over fine net; separate seeds from rest of fruit. Tastes like BUTTERNUTS; eat as gathered or use as topping for desserts. Medicinal use: Applied to skin, juice prevents and relieves symptoms of POISON IVY, NETTLES, and fungal dermatitis. Apply raw juice or concentrated boiled juice of crushed stems. Extract spoils quickly, but frozen extract retains medicinal properties. Antifungal agent is 2-methoxy-1, 4-naphthoquinone. **Related edible species:** YELLOW-FLOWERED JEWELWEED (next). **Poisonous look-alikes:** none.

Yellow-flowered jewelweed, Pale touch-me-not *Impatiens pallida*

Habitat: moist woodlands, wet meadows; not as abundant and usually occurring in slightly drier sites than ORANGE-FLOWERED JEWELWEED. **Identification:** annual herb; ***stems*** upright, to 2 m (6.6 ft) high, freely branched, ***very juicy,*** smooth. Leaves alternate, long stalked, blades 4–14 cm (1.6–5.5 in) long, 3–8 cm (1.2–3.2 in) wide, broadest at or below middle, blunt or round toothed along margin. ***Flowers showy, in few-flowered clusters*** in junctions of upper leaves; ***each flower*** stalked, ***with conspicuous saclike spur in rear, pale yellow with reddish spots on face. Fruit elongate, cylinder-shaped capsule 2–2.6 cm (0.8–1 in) long, at maturity exploding suddenly when touched to scatter seeds.*** **Harvest and preparation:** same as for ORANGE-FLOWERED JEWELWEED (preceding). **Related edible species:** ORANGE-FLOWERED JEWELWEED. **Poisonous look-alikes:** none.



Sheep sorrel: flowering stalk (Elias). Basal leaves and leaf (Dykeman).

Sour dock: flowering stalks (Elias).


Introduced and
grows wild.
Widespread.

Sheep sorrel *Rumex acetosella*

Also edible summer, autumn

Habitat: disturbed sites, gardens, old fields, mainly on acid soils. **Identification:** annual or perennial ***herb*** to 50 cm (20 in); stems upright, 4-sided, unbranched or branched. Basal leaves present, shaped like a narrow arrowhead. ***Stem leaves 2.4–5 cm*** (1–2 in) ***long,*** 0.5–2 cm (0.2–0.8 in) wide, ***narrow arrowhead-shaped,*** pointed at tip, ***with slender pointed lobes at base,*** with papery sheath around stem where leaves are attached. ***Flowers tiny,*** green, yellow, red to purple, ***clustered on narrow elongate spikes.*** Fruits are tiny nutlets 1.2–1.8 mm (less than 0.1 in) long, 3-angled, shiny yellow-brown, enclosed by persistent calyx. **Harvest:** Pick or cut leaves from healthy, deep green clumps from spring until autumn, but flowering clumps may be tough. **Preparation:** Sour taste makes sheep sorrel leaves an excellent thirst-quenching trail nibble. Use leaves liberally with bland greens in tossed salad. For beverage boil 1 cup loosely packed leaves in 1 qt water for 2–3 min; then cover and steep for at least 15 min. Strain, add sugar or honey to taste, and serve hot or cold. Boil leaves in 2 changes of water for pleasantly sour potherb or mix with other cooked greens. Use leaves with chicken broth to make soup or sauce to use with fish, rice, or vegetables. *Caution: Large quantity may cause stomach upset.* **Related edible species:** Many species of dock, including SOUR DOCK (next), are edible; sheep sorrel has the most distinctive sour flavor. **Poisonous look-alikes:** none.

Sour dock, Curled dock, Yellow dock *Rumex crispus*

Also edible summer, autumn, winter

Habitat: common in disturbed sites, fields, roadsides, vacant lots. **Identification:** ***large herb,*** usually biennial, to 1.5 m (5 ft) tall; stems upright, smooth, ribbed. ***Leaves*** 14–24 cm (5.5–9.4 in) long, 2–6.5 cm (0.8–2.5 in) wide, uniformly wide to widest near base, pointed at tip, ***strongly wavy and curled along margin,*** rounded to heart-shaped at base, dark green, ***with papery, straw-colored sheath around stem where leaves are attached.*** Flowers small, usually greenish, stalked, densely clustered on 1 to several narrow, elongated stalks. ***Fruits 3-parted,*** 4–6 mm (0.2 in) across, dark red to reddish-brown, each ***enclosing*** 3 ***nutlets*** 1.5–3 mm (0.1 in) in diameter. **Harvest:** leaves in early spring, or even through late winter when they may be tinged with red and yellow. Strip seeds from stalks in late summer and autumn. **Preparation:** Young leaves cooked for about 10 min in small amount of water taste like young beet greens. Older leaves may need longer cooking with 1–2 water changes to make them tender and remove bitterness. Cook with other wild greens of season. Serve with butter, bacon, hard-boiled egg, seasonings. *Caution: Large quantity may cause stomach upset.* With much effort seeds can be hulled, winnowed, ground, and sifted to produce palatable flour. Use half and half with regular flour. **Related edible species:** While most species of dock are likely edible, sour dock is one of the most flavorful. **Poisonous look-alikes:** none.

Editor: Dena Saxer

Design and Publishing Consultant: Cathy Umphress

Illustrations: Juan Li

Computer Graphics: Saisunee Yongyod

Layout: Siriporn Chaimongkol

Production Manager: Saniem Chaisarn

Final Editing: Jean Chilton

Project Manager: W.U. Wei

© *North Star Trust*

First published in 2003 by:

Universal Tao Publications
274 Moo 7, Luang Nua,
Doi Saket, Chiang Mai 50220 Thailand
Tel: (66)(53) 495-596 Fax: 495-853
Email: universaltao@universal-tao.com
Web Site: universal-tao.com

Manufactured in Thailand

ISBN: 0-9671718-5-7

All rights reserved. No part of this booklet may be used or reproduced in any manner whatsoever without the express written permission from the author, with the exception of brief quotations embodied in critical articles and reviews. Anyone who undertakes these practices on the basis of this booklet alone, does so entirely at his or her own risk.

Eastern hemlock *Tsuga canadensis*

Habitat: cool moist ravines, protected valleys, lowlands. **Identification:** medium or large ***evergreen tree*** to 25 m (82 ft), rarely taller, with deeply furrowed, reddish-brown or cinnamon red bark. ***Leaves small,*** 0.7–1.6 cm (0.3–0.6 in) long, 1–2 mm (less than 0.1 in) wide, ***linear, arranged in 1 plane horizontal to ground, flattened,*** dark yellowish-green ***with 2 whitish bands underneath.*** Male flowering cones tiny, yellowish, at tips of branches; female cones small, green, leathery. ***Fruiting cones 1.2–1.9 cm*** (0.5–0.7 in) ***long,*** hanging, widest near middle, rounded or pointed at tip, ***light brown;*** cone scales nearly rounded; seeds tiny, egg-shaped, winged. **Harvest:** needles any time but preferably young ones in spring. Inner bark best in winter and early spring. **Preparation:** For tea, boil needles in covered pot and steep about 10 min. Tea is high in vitamin C. To avoid damage to tree, use inner bark only in emergency. It may be eaten raw or boiled, or dried and ground to mix with flour. **Related edible species:** Carolina hemlock *(T. caroliniana),* western hemlock *(T. heterophylla),* mountain hemlock *(T. mertensiana).* **Poisonous look-alikes:** AMERICAN YEW is a commonly cultivated shrub that has longer needles and bright red, fleshy pulp surrounding seeds.

Yellow birch *Betula alleghaniensis*
Also edible autumn, winter (synonym: *B. lutea*)

Habitat: rich woodlands, lower slopes, and occasionally cool marshlands, usually below 1,000 m (3,300 ft) elevation. **Identification:** medium-size tree with rounded crown and peeling ragged-edged, reddish-brown ***bark*** turning ***dull yellow or yellowish-brown. Broken twigs have mild wintergreen fragrance.*** Leaves alternate, deciduous, simple, 7–11 cm (2.8–4.3 in) long, 3–5 cm (1.2–2 in) wide, usually broadest near base, with double row of sharp-pointed teeth along margin. Male and female flowers in separate catkins on same tree in spring. ***Fruits broad, upright cones 2.5–3.5 cm (1–1.4 in) long,*** with numerous 3-lobed scales and tiny winged seeds. **Harvest:** For sap, tap like SUGAR MAPLE, 3–4 weeks after maple sap flow begins. Flow copious but sugar content lower than from maple. For use of twigs and inner bark, see instructions under more flavorful SWEET BIRCH (next). **Preparation:** Boil sap in shallow open container outdoors, adding more as volume decreases, until evaporation leaves viscous, molasses-flavored syrup with temperature about 104°C (220°F). Ratio of sap to ultimate syrup is far greater than for SUGAR MAPLE. Store in sterilized, filled, sealed jars. **Related edible species:** SWEET BIRCH. **Poisonous look-alikes:** none.

Sweet birch, Black birch *(Also edible summer, autumn, winter)* *Betula lenta*

Habitat: forest or open woods, especially moist, north-facing, protected slopes, in deep, rich, well-drained soils. **Identification:** medium-size tree with rounded crown and ***smooth, dark red to almost black bark. Broken twigs have wintergreen fragrance.*** Leaves alternate, deciduous, simple, 6–15 cm (2.4–6 in) long, 4–8 cm (1.6–3.2 in) wide, broadest near base, ***with double row of fine, sharp-pointed teeth along margin.*** Male and female flowers in separate, small catkins on same tree in spring. Fruits in erect, brownish cones 2.5–3 cm (1–1.2 in) long, containing many tiny, winged seeds. Fruits maturing in late summer and early



Eastern hemlock: branch with young leaves and branch with mature cones (Elias).



Yellow birch: trunk (Dykeman). Branch with fruits (Elias).

Sweet birch: spring branch with male flowers (Dykeman). Fruit in summer (Elias). Trunk (Dykeman).





Sassafras: summer branch with fruits (Elias). Spring branch with flowers (NYBG).

Sugar maple: fruiting branch (Soderstrom).



fall. **Harvest:** twigs, red inner bark, larger roots: year-round but best in spring. For sap in spring, 3–4 weeks later than SUGAR MAPLE. See instructions under YELLOW BIRCH (preceding). **Preparation:** inner bark raw as emergency food, boiled like noodles, or dried and ground into flour. Dry inner bark at room temperature; store in sealed jars. For tea, steep (do not boil) twigs or fresh or dried inner bark in water or, preferably, birch sap. Boiling destroys volatile wintergreen oil. For birch beer, pour solution of 4 gal birch sap and 1 gal honey (or 5 gal sap and 3 lb sugar), which has been boiled 10 min, over 4 qt fine twigs in crock. Cool, strain to remove twigs, add 1 cake yeast. Cover; ferment about 1 week, until cloudiness starts to settle. Bottle and cap tightly. For birch syrup, see YELLOW BIRCH. **Related edible species:** YELLOW BIRCH. **Poisonous look-alikes:** none.

Sassafras *(Also edible summer, autumn, winter)* *Sassafras albidum*

Habitat: bottomlands, moist soil of open woodlands, lower slopes. **Identification:** small to medium-size tree with open, flat-topped crown and smooth to deeply and irregularly furrowed, reddish-brown bark on older trees. Leaves alternate, deciduous, simple, ***in 3 shapes (entire or with 2 or 3 lobes), 10–15 cm (4–6 in) long,*** 5–10 cm (2–4 in) wide, broadest near base, ***bright green, with spicy odor when crushed.*** Flowers produced in clusters in spring, each small, yellow, and either male or female (each tree male or female). Fruits egg-shaped 1–1.5 cm (0.4–0.6 in) long, dark blue, stalked, enclosed at base by small red cup. **Harvest and preparation:** year-round. Carefully pull several suckers near base of parent tree to obtain small roots. For larger harvest, brittle roots require digging. Flavor is in root bark. Boil washed roots or root bark in water (or maple sap) until liquid is red. Sweeten to taste; drink hot or cold. Roots may be reused. Dried, pulverized root bark is pungent meat spice. Dried, pulverized leaves flavor and thicken soups and gravies. Use green winter buds and young leaves in salads. *Caution:* Sassafras reportedly has carcinogenic properties. Basic jelly recipe: Make jelly with 3 cups strong sassafras tea, 3 oz powdered pectin, ½ tsp citric acid, 4 cups sugar; or use 2 cups tea, 1 pkg pectin, 3 cups honey, powdered root bark to taste. **Related edible species:** SPICE BUSH. **Poisonous look-alikes:** none.

Sugar maple *(Also edible summer, winter)* *Acer saccharum*

Habitat: eastern deciduous forest, common and widespread, especially at lower elevations. **Identification:** medium-size to tall ***tree*** to 30 m (98 ft) with rounded crown, slightly fissured to furrowed dark gray bark. ***Leaves opposite,*** simple, 7.5–20 cm (3–8 in) long and broad, broadest near base, ***3- to 5-lobed, lobes with a few coarse teeth along margin,*** bright green, smooth above and below. Flowers small, bisexual, produced in slender hanging clusters before leaves emerge. ***Fruits are winged (samaras), 3–3.5 cm*** (1.2–1.4 in) ***long,*** wings spreading at 60° angle. **Harvest:** Obtain sap from first spring flow, until buds swell. Good sap flow requires freezing nights and warm days. Drill hole [11 mm (7/16 in) for commercial spile] slightly upward and 5–8 cm (2–3 in) into trunk. Drive spile in far enough to hold bucket, not so hard to split wood. Collect sap and store cold until you have 25–30 gal. Collect winged seeds before fully ripe, usually from June to September. **Preparation:** Boil sap outdoors, indoors only if you like sticky walls. Use large surfaced, open pan, adding sap as water boils off. After adding all sap, continue boiling until temperature is 4°C (7°F) above that of boiling water on that particular day. You may wish to boil for the last two degrees on a controllable stove. Pour syrup through milk filter, filling sterilized canning jars, and seal. Yields about 3 qt. For maple sugar, boil 1 pt syrup in saucepan with frequent stirring until temperature is at least 110°C (230°F). Remove from heat, cool and stir until surface loses sheen. Pour quickly onto foil or waxed paper. When partially hardened, score into pieces with knife. Use sap fresh as beverage, fermented to form mild vinegar, or reduced by boiling to ¼ original volume as base for teas. Soak seeds and remove wings. Boil until tender, drain, season, and roast for 10–15 min. **Related edible species:** Sap of all native maples may be used for syrup. Sugar maple is sweetest. **Poisonous look-alikes:** none; avoid Norway maple *(A. platanoides),* which has milky sap.

Summer

By summer most of the leafy edibles that were tender in spring have toughened and become unpalatable. Yet many late-starting plants are usable through the summer and include the mints of fields and water's edge as well as purslane from the untended garden. Spring strawberries are succeeded by a host of other delicious fruits including raspberries, mulberries, blueberries, blackberries, serviceberries, and beach plums. So summer is the prime season for pies, jams, jellies, and juices, as well as food-drying projects.

As the days grow shorter in late August and September, fewer and fewer shrubs and trees yield juicy, flavorful fruits. Yet this slow period before the fall fruit and nut season can still keep a forager busy. Now you can find ripe seed clusters from many of the same plants whose greens served as edibles in spring; some of these include lamb's quarters, amaranth, plantain, and dock. Threshed, winnowed, and ground, these seeds provide tasty and nutritious flour supplements.

Of course, summer is also the season to beware of stinging nettles, poison ivy, and pesky briars, the briars coming in many disguises.

Additional summer edibles

Plants listed below have parts that are edible in summer and at least one additional season. Descriptions and photos of these plants appear in a seasonal section other than "Summer," as indicated.

Allegheny chinkapin (*Castanea pumila*), p. 234
Arrowhead (*Sagittaria latifolia*), p. 212
Black mustard (*Brassica nigra*), p. 100
Bullbrier (*Smilax bona-nox*), p. 66
Butternut (*Juglans cinerea*), p. 246
California grape (*Vitis californica*), p. 216
California rose (*Rosa californica*), p. 220
Canada violet (*Viola canadensis*), p. 94
Carrion flower (*Smilax herbacea*), p. 66
Cattail (*Typha latifolia*), p. 68
Common burdock (*Arctium minus*), p. 112
Common chickweed (*Stellaria media*), p. 84
Common greenbrier (*Smilax rotundifolia*), p. 64
Common milkweed (*Asclepias syriaca*), p. 106
Eastern camass (*Camassia scilloides*), p. 64
Fireweed (*Epilobium angustifolium*), p. 108
Frost grape (*Vitis vulpina*), p. 214
Garlic mustard (*Alliaria officinalis*), p. 84
Glasswort (*Salicornia europea*), p. 76
Great bulrush (*Scirpus validus*), p. 70
Green pigweed (*Amaranthus hybridus*), p. 72
Hard-stem bulrush (*Scirpus acutus*), p. 70
James chickweed (*Stellaria jamesiana*), p. 84
Lady's thumb (*Polygonum persicaria*), p. 110
Lotus lily (*Nelumbo lutea*), p. 210
Miner's lettuce (*Montia perfoliata*), p. 94
Narrow-leaved cattail (*Typha angustifolia*), p. 68
Pale violet (*Viola striata*), p. 96
Pigweed (*Amaranthus retroflexus*), p. 72
Plantain (*Plantago major*), p. 78
Riverside grape (*Vitis riparia*), p. 214
Russian thistle (*Salsola kali*), p. 76
Sassafras (*Sassafras albidum*), p. 124
Sheep sorrel (*Rumex acetosella*), p. 120
Sour dock (*Rumex crispus*), p. 120
Spice bush (*Lindera benzoin*), p. 218
Squashberry (*Viburnum edule*), p. 226, 252
Sugar maple (*Acer saccharum*), p. 124, 256
Sweet birch (*Betula lenta*), p. 122, 252
Sweetbrier rose (*Rosa eglanteria*), p. 222
Wild garlic (*Allium canadense*), p. 60
Wild leek (*Allium tricoccum*), p. 60
Wild onion (*Allium cernuum*), p. 58
Wild potato vine (*Ipomoea pandurata*), p. 216
Wild rose (*Rosa carolina*), p. 222
Wild strawberry (*Fragaria virginiana*), p. 90
Wintercress (*Barbarea vulgaris*), p. 98
Wood violet (*Viola palmata*), p. 116
Wrinkled rose (*Rosa rugosa*), p. 222
Yellow pond lily (*Nuphar advena*), p. 212



Reed grass: flowering plants (Feldman). Flowers (Mohlenbrock).

Wild rice: flower stalk with male flowers topmost and stalks with female flowers (Elias).



Reed grass, Phragmites *(Also edible autumn, winter, spring)* *Phragmites communis*

Habitat: margins of streams, lakes, ponds, marshes, springs, ditches. **Identification:** ***tall perennial grass,*** with long, spreading underground stems (rhizomes), often forming dense clumps; ***stems upright, 2–4 m*** (6.6–13 ft) ***high,*** stout; ***leaf blades*** flat, long, ***18–60 cm*** (7–24 in) ***long,*** narrow, 1–6 cm (0.4–2.4 in) wide, smooth, base of leaf sheathing part of stem. ***Flowers many in large, dense, elongated, branched, plumelike clusters 15–40 cm*** (6–16 in) ***long,*** purplish at first, turning tan to whitish at maturity, side branches ascending, each spikelet (small simple cluster of flowers sharing the same stalk) 1–1.6 cm (0.4–0.6 in) long, ***with numerous long, silky hairs.*** Fruits are tiny, hard, reddish grains (seeds) many people overlook. **Harvest:** Gather new shoots (at base of old stalks) and leaves early in growing season. Collect hardened sap from wounded stems. Cut whole stems before blooming. Gather seed heads in late summer and autumn. Failure to produce seed is common. Dig roots and underground stems all year. **Preparation:** Eat early shoots raw, or boil or steam until tender; serve as vegetable. Eat hardened gum fresh or toast near fire. Dry stems in sun, beat or grind, sift out fine powder. Moisten powder and place near fire to swell and toast like marshmallows. For gruel, remove seeds by hand. Crush seeds with hulls and mix with spicy berries. Add boiling water and cook until thin reddish gruel, about 30 min; add sweetener. For use of roots and underground stems, see CATTAIL. **Related edible species:** none. **Poisonous look-alikes:** none, but avoid roots and shoots of iris (YELLOW FLAG, BLUE FLAG) and other inedibles.

Wild rice *(Also edible autumn)* *Zizania aquatica*

Habitat: marshes, shallow ponds, lakes, streams, or bays of fresh and brackish water. **Identification:** ***tall annual grass;*** stems upright, usually 1–3 m (3–10 ft), stout; leaf blades long, narrow 0.3–1 m (12–39 in) long, 2–5 cm (0.8–2 in) wide, soft. ***Flowers many, in large, open, branched, elongate, plumelike clusters to 60 cm (2 ft) high,*** side branches 15–20 cm (6–8 in) long, ***lower branches*** spreading to ascending and ***only with male flowers; upper branches erect, bearing only female flowers,*** each about 2 cm (0.8 in) long; seed case tipped with long, stiff, hairlike structures; seed narrow, hard, brown. **Harvest and preparation:** Grains ripen in late summer to early fall. Timing is critical; ripe seeds easily fall from plant. Small, shallow-draft boat or canoe provides best harvesting container. Carefully bend stalks over boat and knock ripe grains into it. Several visits days apart needed for maximum harvest. Spread grains to dry; then parch, stirring occasionally, for 3 hr at 175°C (350°F). Thresh husks from grains by pounding or rubbing. Winnow by pouring from one container to another in natural or fan-generated breeze. Wash grains in cold water to eliminate smoky flavor. Use like cultivated rice. Cooking: Bring 3 cups water and 1 tsp salt to boil. Stir in 1½ cups rice grains and return to boil. Cover and simmer until tender, 30–45 min. Serve buttered or with sweetener. For flour, substitute ground rice for part of wheat flour in baking recipes. **Related edible species:** Texas wildrice *(Z. texana)*. **Poisonous look-alikes:** none, but poisonous pink or purple fungus (*Claviceps* species) occasionally replaces some grains. Learn to recognize and avoid it.

Chufa, Yellow nut grass *Cyperus esculentus*

Also edible autumn, winter, spring

Habitat: ditches, margins of ponds and streams, low wet soils, waste places. **Identification:** ***perennial herb with*** slender underground stems (rhizomes) and ***nearly rounded tubers*** 6–10 mm (0.2–0.4 in) in diameter; ***stems triangular in cross section,*** upright, 20–90 cm (8–36 in) tall, stout, smooth; stem leaves narrow, 5–10 mm (0.2–0.4 in) wide; ***with 3–10 leaves at base of flowering clusters*** but much longer than flower clusters. ***Flowering clusters broadly cylinder-shaped to almost globe-shaped,*** composed of numerous spikelets (small simple cluster of flowers on same stalk); spikelets narrow, elongate, 0.5–3 cm (0.2–1.2 in) long, 4-sided, many-flowered. Fruits are small ***nutlets, 1–1.5 mm*** (less than 0.1 in) ***long, triangular-shaped, yellowish.*** **Harvest:** Gather tubers best from loose or sandy soil where whole plant with tubers is easily pulled or dug from depth of less than a few inches. Gather any time ground is not frozen. **Preparation:** Tubers palatable and useful raw, boiled, candied, dried, and ground into flour, and as beverage base. For flour, dry slowly until tubers break apart instead of mash when hammered lightly. Grind fine in blender or food mill. Use flour half and half with wheat flour. For beverage soak 1½–2 cups tubers for 2 days. Drain and mash or blend in 1 qt water with ¼ cup sugar or honey. Strain out solids before drinking. For coffee substitute, roast tubers until dark brown throughout. Grind and brew 1 tbsp per cup. **Related edible species:** Several species of *Cyperus* have tubers or tuberlike structures. **Poisonous look-alikes:** none.

Pickerelweed *Pontederia cordata*

Also edible autumn

Habitat: along shores or in shallow water of lakes, ponds, slow moving streams, bays. **Identification:** ***perennial herb*** to 1 m (3.2 ft) high, with short, thick underground stem. ***Leaves basal, blade*** 6–20 cm (2.4–8 in) long, 2–12 cm (0.8–4.7 in) wide, broadest near base to very narrow, shape variable but usually ***arrowhead-shaped,*** smooth; ***leafstalk stout, 6–32 cm*** (2.4–13 in) ***long.*** Flowering stalk slightly taller than leaves, bearing 1 or 2 leaflike bracts, ***attractive blue flowers densely clustered on spike 5–16 cm*** (2–6.3 in) ***long, each flower funnel-shaped, 2-lipped.*** Fruits are stiff, egg-shaped capsules 4–10 mm (0.2–0.4 in) long, enclosed by persistent ragged remains of flower. **Harvest:** Pick young leafstalks in early summer before leaves are fully unfurled. Strip fruits off spikes as they ripen in early autumn. **Preparation:** Wash, chop, and add young leafstalks to salads. As potherb boil leafstalks about 10 min, drain, and season. Fruits each contain a solid seed, edible as trail snack or dried and ground like grain. **Related edible species:** LANCE-LEAVED PICKERELWEED (next), used the same as this species. **Poisonous look-alikes:** none.



Chufa: fruiting cluster (Mohlenbrock).

Pickerelweed: flowering stalk (NYBG). Plants (Dykeman).



Contents

Healing Hand 1
  Palms 1
  Pericardium 1
  Large Intestine 1
Major Palm Lines 3
  Fingers have Corresponding Bodily Functions..................... 3
  Fingers Correspond to Emotions, Elements and Organs 8
  Head 10
  Face 14
  Temples 15
  Mouth 16
  Eyes 17
    A. Bring Chi Energy to the Hands and Eyes 18
    B. For the Eyeballs and Surrounding Area 20
    C. Pull up the Eyelids 20
    D. For the Eye Sockets 21
    E. For getting a Tear out 21
    F. Pull in the Eyeballs 23
    G. Learn to Maintain Eye Contact 25
  Nose 25
  Ears 26
    A. Outer Ear 26
    B. Inner Ear 29
  Gums, Tongue, Teeth 30
    A. Bring Chi Energy to the Hands 31
    B. Gums 31
    C. Gums and Tongue 31
    D. Tongue 32
    E. Teeth Clenching 34
    F. Energy to Teeth 34



Lance-leaved pickerelweed: plant and flowering stalk (NYBG).

Sweet flag: leaves (Dykeman). Flowering spike (Elias). Rootstock (Dykeman).



Lance-leaved pickerelweed *Pontederia lanceolata*

Also edible autumn

Habitat: shallow water along shores of lakes, ponds, streams, marshes. **Identification:** perennial herb to 1 m (3.2 ft) tall with thick, creeping underground stem (rhizome). ***Leaves mainly basal,*** blade 6–20 cm (2.4–8 in) long, 2–12 cm (0.8–4.7 in) wide, variable in shape but usually narrowly heart-shaped to arrowhead-shaped, smooth; ***leafstalk stout, 8–30 cm*** (3.2–12 in) ***long.*** Flowering stalk as tall or slightly taller than leaves, usually with a leaflike bract about midway; flowers densely clustered on narrow spike 6–18 cm (2.4–7 in) long, ***each flower blue to purple,*** funnel-shaped, 2-lipped, ***covered with short glandular hairs. Fruits*** stiff, ***egg-shaped capsules 4–8 mm*** (0.2–0.3 in) ***long, usually as broad or broader than long.*** **Harvest and preparation:** See PICKERELWEED (preceding). **Related edible species:** PICKERELWEED. **Poisonous look-alikes:** none.

Sweet flag, Calamus *Acorus calamus*

Habitat: ditches, swamps, pond edges, lakes, and streams; may grow with BLUE FLAG, water flag, and CATTAILS. **Identification:** perennial herb with large, stout, aromatic underground stem (rhizome). ***Leaves*** crowded near base, erect, narrow, ***linear, swordlike but flexible, usually 1–1.5 m*** (3–5 ft) ***long,*** rarely to 2 m (6.6 ft), 1–3 cm (0.4–1.2 in) wide, ***midvein off-center, greenish-yellow, with aromatic, almost spicy, odor when cut.*** Underground stem portions red. ***Flowers*** tiny, bisexual, ***numerous on narrow, tapering spike (spadix) produced about ⅓ of way up leaflike stalk;*** spikes often overlooked. Fruits inconspicuous, borne on flowering spike. **Harvest and preparation:** Harvest tender young stalks when less than 30 cm (1 ft) tall with short underground stems. Grasp and pull firmly. Vertical stem usually breaks off at rhizome. To obtain underground stem, dig with trowel to sever anchoring roots. Inner portions of tender young stems provide spicy trail snack or salad ingredient. For candy, use especially red underground part of stem. Remove roots, wash, peel, slice into 1 cm (0.4 in) long pieces. Cook in several changes of boiling water until pungency is tolerable. Simmer 20 min in syrup of 1 cup water to 2 cups sugar. Drain, dry, roll in sugar. **Related edible species:** none. **Poisonous look-alikes:** Irises (YELLOW FLAG, BLUE FLAG) cause severe digestive upset. Iris leaves lack spicy odor when cut. Flowers are showy.

Spanish bayonet, Datil *(Also edible spring)* *Yucca baccata*

Habitat: dry slopes, usually in sandy or rocky soils from 920–2,440 m (3,000–8,000 ft). **Identification:** ***long-lived perennial*** with short inconspicuous trunk, sometimes in clumps. ***Leaves clustered near base, blade lance-shaped, 50–76 cm*** (20–30 in) ***long, 3–7 cm*** (1.2–2.8 in) ***wide,*** stiff, tip sharp-pointed and ending in stout spine, with coarse, recurved fibers along margin, flattened or concave, grayish-green. Flowering stalk in spring, upright 1–1.5 m (3.2–5 ft) high, densely flowered along upper half, flowers showy, fleshy, sepals 3, reddish-brown on outer surface, petals 3, cream-white, 6–12 cm (2.4–4.7 in) long. ***Fruits are fleshy capsules, 14–18 cm*** (5.5–7 in) ***long,*** broadest near the middle, 3-parted, turning reddish brown at maturity and splitting open to release seeds. **Harvest:** young flower stalks before buds expand and fruits as they are available late spring through summer. Use buds and flowers as described for SOAPWEED (next), but not as good. **Preparation:** Cut young flower stalks into sections, boil 25–30 min or roast until core is tender. Peel off tough rind. Serve with butter, lemon juice, and seasonings. Eat fruit raw or cooked. Roast whole fruits until tender, scrape out pulp and separate from seeds. Sweeten if desired. Use raw pulp for pie. Strain pulp and dry by boiling to paste and finishing in oven as thick sheet. Eat dry or dissolve for beverage. Roast seeds at 190°C (375°F) until dry and crisp. Grind coarsely and boil as vegetable until tender. **Related edible species and poisonous look-alikes:** See SOAPWEED.

Soapweed *(Also edible spring)* *Yucca glauca*

Habitat: prairies, roadsides, pastures—usually in dry, well-drained sandy or rocky soils. **Identification:** perennial with short stem. ***Leaves densely clustered near base*** and covering stem, ***blade linear, 38-60 cm*** (15-24 in) ***long, 0.8-1.2 cm*** (0.3-0.5 in) ***wide,*** stiff, hard and sharp-pointed at tip, with narrow white band and occasional loose threadlike strands along margin, concave, gray-green. Flowering stalk in spring, upright to 1 m (3.3 ft), with stalked flowers along upper half, flowers bowl-shaped, showy, with 3 greenish-white sepals, 3 white petals 4.5–5.5 cm (1.8–2.2 in) long. ***Fruits are cylinder-shaped dry capsules 5–8 cm*** (2–3.2 in) ***long,*** 3–4.5 cm (1.2–1.8 in) in diameter, turning brown, 3-parted and splitting open at maturity to release seeds. **Harvest:** Pick young flower stalks before buds expand. Pick flowers and buds as available. **Preparation:** Cover 1 cup flowers or buds with water and boil until tender, 15–20 min. Drain and chop coarsely. Add with pimento or green pepper to several eggs and little milk. Cook like scrambled eggs. For salad boil 1 cup flowers and buds as above. Drain, chop, and cool. Add celery, chopped apple, raisins, nutmeats, cabbage, and mayonnaise as in Waldorf salad. For flower stalks see SPANISH BAYONET (preceding). Unripe fruits are bitter but can be made palatable by boiling or baking. **Related edible species:** all *Yucca* species including SPANISH BAYONET. Flower and bud uses apply best to dry-fruited species, fruit uses to fleshy-fruited species. Spiny leaved *Agave* looks similar and is also edible. **Poisonous look-alikes:** none.



Spanish bayonet: plants (NYBG).

Soapweed: flowering stalk (NYBG). Plants (NYBG).



Common day lily *Hemerocallis fulva*

Also edible autumn, spring

Habitat: garden plant that commonly grows wild in abandoned home sites, vacant lots, along roads. **Identification:** large perennial herb from a fibrous root system with short, fingerlike tubers, with numerous ***long, narrow basal leaves.*** Each leaf 0.5–1.5 m (1.7–5 ft) long, 1.5–3 cm (0.6–1.2 in) wide, gradually tapering to long narrow tip, tapering with edges folded inward at base, light green to greenish-yellow. Flowers in clusters of 3–5 at tip of upright stalks, stalks to 2 m (6.6 ft); flower buds narrow, tubular; each ***flower 10–15 cm*** (4–6 in) ***long,*** narrowly tubular at base, ***funnel-shaped*** above, ***with 6 large, showy petallike segments, orange to tawny-orange,*** darker inside, flowering from late May to July, each flower open 1 day only. Fruits fleshy, 3-parted capsules. **Harvest:** tubers 1 cm (0.4 in) × 2–3 cm (0.8–1.2 in). Spade roots over; pick only firm tubers all year. Replant roots. Tubers regenerate rapidly. Pick buds when half to nearly full size. Pick flowers when fully opened or wilting. **Preparation:** Raw tubers give sweet nutty flavor to salads, or boil in salted water until tender, season. Excellent potato substitute. Boil buds a few minutes, butter, and season. Great cooked vegetable; raw they irritate the throat. Dip buds or flowers in egg batter and fry in hot oil or add them to soups at end of preparation for gelatinous quality. Dry buds and flowers at air temperature about a week; store in sealed jars for later use in soups or other recipes. *Caution: Eat in moderation to avoid laxative effect.* **Related edible species:** none. **Poisonous look-alikes:** Leaves slightly resemble those of iris (YELLOW FLAG, BLUE FLAG), but common day lily leaves arch over with tip pointed to ground; iris leaves are upright and darker.

Western camass, Camass lily *Camassia quamash*

Also edible autumn, winter, spring

Habitat: coastal mountain forests, wet meadows of interior mountains. **Identification:** ***perennial herb*** to 80 cm (32 in) high, from bulb 2–3 cm (0.8–1.2 in) across; ***grasslike leaves*** several from base, narrowly lance-shaped, 20–50 cm (8–20 in) long, 0.6–1.8 cm (0.2–0.7 in) wide, pointed at tip. Flower stalk 20–80 cm (8–32 in) high, ***flowers several, stalked, showy, with 6 blue to bluish-violet petals*** or petallike structures, each 2–3.6 cm (0.8–1.4 in) long. Fruits are dry capsules 0.8–2.4 cm (0.3–1 in) long, egg-shaped, splitting open at maturity to release seeds. **Harvest:** Dig or pull bulbs any season, safest when blue flowers distinguish it from DEATH CAMASS. Dig and transplant to safe place where you know there is no DEATH CAMASS. *Be certain of identification!* **Preparation:** Raw bulbs are palatable potato substitute. May be boiled 25–30 min or baked in foil for 45 min at 175°C (350°F). Indians baked bulbs in pit up to 3 days, the resulting product being very dark and sugary. Slice pit-baked or boiled bulbs, dry in sun or warm oven, store in paper bag in dry place. **Related edible species:** EASTERN CAMASS. **Poisonous look-alikes:** DEATH CAMASS (*Zigadenus* species), narrow-leaved plants with green, white, or bronze flowers, single or several in narrow stalk.

Common day lily: flowers (Dykeman).

Western camass: field of camass (Ross). Flowering stalks (NYBG). Flowers (Ross).





Indian cucumber: leaves and root (Dykeman). Flowering plant (NYBG).

Indian fig: plant (Folkerts).



Indian cucumber *Medeola virginiana*

Habitat: rich moist woodlands, protected slopes, margin of bogs and swamps. **Identification:** ***perennial herb, with*** swollen ***tuberlike white underground stems (rhizomes)*** horizontal to ground; stem erect, to 80 cm (2.8 ft), usually about 30 cm (1 ft), slender, covered with wooly hairs when young, ***bearing a whorl of 5–10 leaves about midway and another whorl of 3 leaves near top.*** Leaves simple, parallel-veined, to 10 cm (4 in) long, and uniformly wide to broadest near tip; upper leaves smaller and broadest near base. ***Stalked flowers 3–9 in cluster at tip of stem, some flowers hanging beneath upper leaves,*** in May and June, each flower with 6 pale greenish-yellow petals 6–10 mm (0.2–0.4 in) long. ***Fruits*** small, rounded, dark purple berries 6–8 mm (0.2–0.3 in) in diameter, ***not edible.*** **Harvest:** common, easily identified plant a reliable source of limited quantity of tubers for trail food. Digging destroys plant, but any remaining tubers will produce new growth. **Preparation:** Wash and eat tubers raw as trail snack or in salad. Has delicate cucumber flavor. For pickles combine 1½ cups tubers, ½ cup water, ½ cup vinegar, 1 tbsp salt, 2 tsp sugar, 1 clove garlic, ¼ small, chopped red pepper, 1 tsp pickling spice. Bring to boil, place in small hot sterilized jars, covering tubers with liquid, and seal. Store at least 2 months. **Related edible species:** none. Unrelated, inedible starflower *(Trientalis borealis)* looks similar except for net-veined leaves. **Poisonous look-alikes:** none.

Indian fig, Prickly pear *(Also edible spring, autumn)* *Opuntia humifusa*

Habitat: rocky bluffs, sand dunes, dry rocky or sandy grasslands. **Identification:** perennial herb with fibrous root system, sprawling along ground, often forming clumps. ***Fleshy segments or joints nearly circular*** to broadest above middle, sometimes uniformly wide, ***5–20 cm*** (2–8 in) ***long, strongly flattened,*** pale to dark green, dotted with small reddish-brown bumps containing numerous tiny, barbed hairs; spines absent or occasionally 1. ***Flowers*** produced June–July on upper part of segments, ***showy, yellow with red center,*** 5–9 cm (2–3.5 in) across, usually with 10–12 petals. ***Fruit*** broadest above middle to nearly club-shaped, ***3–6 cm*** (1.2–2.4 in) ***long, red to purple, becoming fleshy,*** containing many flattened, nearly circular seeds. **Harvest:** Wear leather gloves to ward off spines and barbed hairs. Cut young segments during spring and summer. Pick fruits as they ripen in late summer and autumn. **Preparation:** Flame segments to remove spines, roast segments over fire, then peel or peel first, then slice and use like string beans. Edible but somewhat sticky. Also, deep fry like onion rings. Dry pulp for later use. To eat fruits fresh, chill if possible, trim off both ends, cut skin lengthwise, scoop out sweet pulp. Or, dip 1–2 min in boiling water and peel. Be careful, fruits also have fine, spiny bristles. Dry fruit pulp for later use, stew it for dessert, or boil it down and strain out seeds to make syrup or to prepare jelly. Briefly roast seeds and grind into meal for soup thickener or flour. For emergency water, peel and chew leafy segments. **Related edible species:** Fleshy fruits and segments of all flat-stemmed *Opuntia* species are edible. **Poisonous look-alikes:** none.

Prickly pear, Indian fig *Opuntia phaeacantha*

Also edible autumn, spring

Habitat: hills, canyons, valleys, usually in rocky or sandy soils. **Identification:** shrub to 1 m (3.2 ft), sometimes sprawling or forming clumps to 6 m (19.7 ft) in diameter. ***Fleshy cactus segments or joints rounded or nearly so,*** sometimes widest above middle, ***10–25 cm*** (4–10 in) ***long, flattened, bluish-green; cacti spines usually on upper half, 1–6 per cluster, 2.5–7.5 cm*** (1–3 in) ***long, straight or curved. Flowers*** produced near top of upper segments, ***showy, yellow,*** 6–8 cm (2.4–3.2 in) long, to 8 cm (3.2 in) in diameter, with many petallike structures. ***Fruits elongate,*** usually broadest above middle, ***3–6 cm (1.2–2.4 in) long, to 3.8 cm (1.5 in) in diameter, fleshy, red,*** depressed at tip, containing numerous, flattened and rounded seeds. The several varieties of this prickly pear differ primarily in segment shape, spine distribution, color, and length. **Harvest and preparation:** INDIAN FIG (preceding). **Related edible species:** all flat-stemmed prickly pear cacti. **Poisonous look-alikes:** none.

May apple, Mandrake *Podophyllum peltatum*

Habitat: rich deciduous woodlands, meadows, moist shaded road banks. **Identification:** ***perennial herb*** to 50 cm (20 in) tall, frequently in large dense patches with creeping underground stems and thick, fibrous roots, short stem, first-year plant with 1 leaf, second-year flowering plants with 2. ***Leaves*** large, umbrellalike, ***12–36 cm*** (4.7–14 in) ***in diameter, nearly circular in outline, deeply 5–9-parted,*** toothed; ***leafstalk attached at center of leaf. Flowers solitary, produced in junction of 2 leaves,*** stalked, nodding, each with 6 sepals, 6–9 waxy white petals 2.5–4 cm (1–1.6 in) long. Fruit an egg-shaped berry 2.5–5 cm (1–2 in) long, usually yellow, but red in one form. **Harvest:** Gather fruit when yellow; practically falls from plant into your hand. Leaves will be turning yellow by this time. Unripe fruit and other parts of plant contain poison podophyllin. The root has a long history of medicinal use. **Preparation:** Eat ripe fruit fresh; taste sensation varies from person to person. For preserves, jam, or pie filling, remove both ends, quarter fruit, and force through food mill to remove seeds before cooking. If skins are desired in final product, squeeze pulp from quartered fruit before removing seeds. Chop skins and add to pulp later. See recipes for jam and pie early in book. Also combine juice with lemonade, sumac ade, or other juices for new flavors. **Related edible species:** none. **Poisonous look-alikes:** none; do not attempt to use unripe May apples or any other part of the plant.



Prickly pear: plant (Elias). Fruits (Dykeman).

May apple: flowering plant (Dykeman). Fruit (NYBG).



Neck 36
- A. Thyroid and Parathyroid: Site of Courage, the Power of Speech 36
- B. Bring Chi Energy to the Hands 37
- C. Whole Neck 37
- D. Middle Neck 37
- E. Turtle Neck 38
- F. Crane Neck 38
- G. Massage the Neck 38

Shoulders 40

Detoxifying Organs and Glands 41
- I. Thymus Gland 41
- II. Heart 42
- III. Lungs 42
- IV. Liver 43
- V. Stomach, Spleen, Pancreas 43
- VI. Large and Small Intestines 44
- VII. Kidneys 45
- VIII. Sacrum 46

Knees and Feet 47
- I. Knees and Feet 47
- II. Feet: Roots of the Body 48

The meditations, practices and techniques described herein are ***not*** intended to be used as an alternative or substitute for professional medical treatment and care. If any readers are suffering from illnesses based on mental or emotional disorders, an appropriate professional health care practitioner or therapist should be consulted. Such problems should be corrected before you start training. This booklet does not attempt to give any medical diagnosis, treatment, prescription, or remedial recommendation in relation to any human disease, ailment, suffering or physical condition whatsoever.



Bunchberry: flowers and fruiting plants (Elias).

Peppermint: flowering stalks (Speas).


Introduced and grows wild. Widespread.

Bunchberry *Cornus canadensis*

Habitat: northern moist woods, bogs, woodlands, mountains especially in southern part of range. **Identification:** perennial, forming mats from spreading underground stems (rhizomes); aboveground stems 8–24 cm (3.2–9.4 in) high, ***each stem with whorl of 4–6 leaves near top*** and 1–2 pair smaller leaves below. Leaves 4–7 cm (1.6–2.8 in) long, 1.5–3.5 cm (0.6–1.4 in) wide, broadest near base or tip, pointed at tip, with 2–3 pair lateral veins. ***Flowers*** produced in May or June, ***tiny, in tight, dense clusters surrounded by 4 conspicuous, white, petallike bracts*** (flower clusters plus bracts resemble a single flower). Fruit produced in midsummer to autumn, in dense clusters, each a fleshy stone-fruit, globe-shaped, 6–8 mm (0.2–0.3 in) in diameter. **Harvest:** Berries ripen through July in clusters of a few to 12. Ripe when scarlet; usually plentiful and easily picked in quantity. **Preparation:** Eat nearly tasteless berries raw, but pulp is difficult to separate from seeds. Better cooked and strained for use with more flavorful fruits or for pudding. **Related edible species:** Swedish bunchberry *(C. suecica)* in northern regions has sweeter and more acid fruits. Laplanders make pudding from this species by boiling fruits with whey until thick. **Poisonous look-alikes:** none.

Peppermint *Mentha piperita*

Habitat: wet places, especially ditches, along streams, wet meadows. **Identification:** perennial herb, stems erect, 0.6–1.1 m (2–3.6 ft) tall, ***4-sided,*** purplish, smooth to slightly hairy. ***Leaves opposite,*** each pair alternating along stem, ***each with short leafstalk,*** blade 3.2–6.4 cm (1.3–2.5 in) long, 1–1.6 cm (0.4–0.6 in) wide, usually broadest near base, sharply toothed along margins, ***with distinct peppermint smell when broken or crushed.*** Flowers tiny, light purple, crowded together in dense, many-flowered, interrupted spikes at tips, June–October. Fruits with 4 tiny nutlets enclosed by persistent calyx. **Harvest and preparation:** Pick leaves at any stage. Great variation in flavor among populations from different areas. Collect leaves on dry day and dry on paper in warm area. Store in tight container. Jelly: Add 2 cups boiling water to 2 cups crushed fresh leaves in saucepan. Place inverted lid on saucepan, with small amount of ice and water in lid to condense water vapor and flavorful oils. Bring mint mix to simmer, remove from heat, steep 10 min. Strain; add 4 cups sugar and ¼ cup cider vinegar to 2 cups mint flavored water. Add green food coloring, if desired. Stir until sugar is dissolved. Dissolve 1 pkg powdered pectin in ¾ cup water, heat and boil hard 1 min. Add pectin solution to mint syrup, stir, pour into sterilized glasses, and seal. For other uses, see SPEARMINT (next). **Related edible species:** SPEARMINT, several hybrids of native and introduced species. **Poisonous look-alikes:** none.

Spearmint *Mentha spicata*

Habitat: grows in wild, especially in wet areas along roads, ditches, streams. **Identification:** perennial, spreading by creeping rootstock; ***stems*** erect to 1 m (3.2 ft), ***4-sided,*** smooth or nearly so. ***Leaves opposite,*** each pair alternating along stem, leafstalks absent or nearly so, blade 2.5–7.5 cm (1–3 in) long, 0.8–2.4 cm (0.3–1 in) wide, broadest at or below middle, toothed along margin, with ***strong smell of spearmint when crushed or broken.*** Flowers tiny, light purple to near white, produced in dense, elongate, many-flowered clusters 4–12 cm (1.6–4.7 in) long, at growing tips. Fruits tiny nutlets enclosed in persistent calyx. **Harvest and preparation:** Pick leaves at any stage. Great variation in flavor among plants from different areas. Collect leaves on dry day and dry on paper in warm area. Store in tight container. For tea pour 1 cup boiling water over ½ tsp crumbled, dried leaves or ¼–½ cup fresh leaves. Cover; steep 5 min. Do not boil. Strain, add sweetener and lemon to taste. High in vitamin C. Chop fresh leaves in green salad. Crush fresh leaves in iced tea. For candy wash and pat dry 2 doz fresh leaves. Beat 1 egg white until stiff. Dip leaves, one at a time in egg white, then in confectioner's sugar. Dry in oven at low heat, about 100°C (210°F), for 30 min or until crisp. Real mint-leaf candy! For jelly recipe see PEPPERMINT (preceding). **Related edible species:** PEPPERMINT, several other *Mentha* species, and many hybrids between native and cultivated species. **Poisonous look-alikes:** none.

American brooklime *Veronica americana*

Also edible spring

Habitat: common, along stream banks, swamps, clear ponds, springs, often with watercress. **Identification:** ***Perennial herb, usually creeping*** or sprawling; stems smooth, fleshy. ***Leaves opposite,*** lanceshaped to broadest near base, 3–8 cm (1.2–3.2 in) long, 1–4 cm (0.4–1.6 in) wide, pointed at tip, toothed along margin, stalked. ***Flowers stalked, produced along terminal, elongated spikes;*** each ***flower with 4 pale violet to lilac petals, 4–8 mm (0.2–0.3 in) across.*** Fruits are small, nearly round capsules, 3–5 mm (0.1–0.2 in) across, almost as long. **Harvest:** young growth tips from unpolluted water during late spring and summer. If water quality is questionable, wash tips in clean water to which iodide purifying tablets sold in camping stores have been added. Rinse with potable water. **Preparation:** Use like WATERCRESS in salads or as potherb with bland greens to offset bitterness of brooklime. **Related edible species:** several other species of speedwells (*Veronica* spp.), some widely distributed. **Poisonous look-alikes:** none.


Introduced and grows wild. Widespread.

Spearmint: (Elias photo).

American brooklime: flowering stalk (Dykeman).



Marsh mallow *(Also edible autumn, winter)* *Althaea officinalis*

Habitat: edges of brackish and salt marshes; introduced from Europe and now grows wild. **Identification:** ***perennial herb*** from 0.6–1.2 m (2–4 ft) tall, from thick, large taproot; stems upright, often branched, stout, hairy. ***Leaves*** alternate, simple, broadest near base, 6–12 cm (2.4–4.7 in) long, about ⅔ as wide, ***often shallowly 3-lobed,*** short-pointed at tip, rounded at base, ***irregularly and coarsely toothed along margin,*** densely hairy. ***Flowers*** several ***in cluster at base of upper leaves in summer; each with 5 pink, spreading petals*** 2–3 cm (0.8–1.2 in) long. ***Fruit is dry, flattened disc, divided into 15–20 segments.*** **Harvest:** leaves in early summer, flower buds in summer, and roots from late summer through winter. **Preparation:** whole plant contains mucilagelike material; roots are best source. Use young leaves in early summer as okra-like soup thickener or as potherb. Pickle flower buds. Boil thin sliced, peeled roots for 20 min in enough water to cover them. Strain off roots; for candy sweeten the liquid and boil until very thick. Beat and drop spoonfuls on waxed paper to cool. Roll pieces in confectioner's sugar. For vegetable, fry boiled root slices with butter and chopped onion until browned. Use water from boiling any parts of plant as substitute for egg white in meringue or chiffon pies. Also used for hand lotion and cough syrup. Use leaves for poultices for infected wounds. **Related edible species:** other Mallow family species, especially those of genus *Malva*. Eat *Malva* fruits raw or substitute roots for meringue. **Poisonous look-alikes:** none.

Watercress *Nasturtium officinale*
Also edible autumn, winter, spring (synonym: *Rorippa nasturtium-aquaticum*)

Habitat: slow moving clear water, especially springs, cool streams; introduced from Eurasia. **Identification:** ***perennial herb, growing in shallow water*** or mud; stems weak, partially floating in water or lying flat in mud with white roots growing from floating stems. ***Leaves alternate,*** 4–16 cm (1.6–6.3 in) long, 2–5 cm (0.8–2 in) wide, ***dissected into 3–11 lobed and usually rounded dark green leaflets;*** upper leaves nearly rounded. ***Flowers numerous in narrow, elongate clusters,*** each flower stalked, with ***4 white petals,*** 3–5 mm (0.2 in) long. Fruits narrow, slender, capsulelike, 1–2.5 cm (0.4–1 in) long, beaked, containing several tiny reddish-brown seeds. **Harvest:** Collect young growth nearly all year from unpolluted water sources. Removal does not hurt plant. If water quality is questionable and plant is to be eaten raw, disinfect shoots by washing in water with iodide purifying tablets sold in camping stores. Rinse in potable water. **Preparation:** As potherb, cook and serve just like spinach or add to more bland potherb greens, or stir-fry 4–5 min in skillet with 2 tbsp cooking oil and 1 tbsp fresh grated ginger root. Serve with soy sauce. Watercress is an excellent soup ingredient. Use radish-tasting stems and blossoms as garnish or as main salad ingredient. For nasturtium salad: Make slightly sweetened oil and vinegar dressing. Mix 1 cup young watercress leaves, 1 cup watercress buds and blossoms, 2 cups mixed mild greens, and 1 chopped scallion in large bowl. Add dressing, toss and serve. Vary ratio of watercress to other greens to get desired taste. High in vitamins and minerals. **Related edible species:** none. **Poisonous look-alikes:** none.



Marsh mallow: flowering stalk (Speas).

Watercress: flowering plant (Mohlenbrock).





Ground cherry: flowering plant (NYBG). Flower and fruits (Pawloski).

Ground nut: flowering plant (NYBG). Underground tuber (Kavasch).



Ground cherry *Physalis pubescens*

Habitat: moist sites, open woodlands, recently cultivated fields, disturbed sites. **Identification:** ***annual herb*** to 60 cm (24 in) high; ***stems*** weak, wide branching, ***often trailing,*** hairy. ***Leaves*** alternate, simple, broadest near base, 3.5–8 cm (1.4–3.2 in) long, 1.7–6 cm (0.7–2.4 in) wide, pointed at tip, variably rounded at base, nearly entire, ***thin, pale green, hairy,*** long stalked. ***Flowers*** stalked, in junction of upper leaf stems, 5–10 cm (2–4 in) across, ***yellow with dark center. Fruit a sweet yellow berry*** 1.2–1.8 cm (0.5–0.7 in) in diameter, ***enclosed by 5-sided inflated persistent calyx resembling paper lantern 2–3 cm*** (0.8–1.2 in) long, ***angled,*** with conspicuous veins. **Harvest:** Fruits fall before fully ripe. So pick mid to late summer and ripen in husks a few weeks until fruits are yellow and sweet. Unripe fruit and green plant parts are strong flavored and somewhat poisonous. **Preparation:** excellent trail snack and dessert. For pie recipe, see book's Introduction. To preserve fruits boil until clear and tender in syrup of 1 cup sugar, 2 cups water, 3 tbsp lemon juice. Seal in sterilized jars. For jam boil for 5 min 1 qt crushed fruits, ¼ cup lemon juice, ½ cup water, and 1 pkg pectin. Add 3 cups sugar, boil again to reach jelly point, 115°C (240°F). Seal in sterilized jars. Use cherries in relishes. **Related edible species:** Several *Physalis* species are distributed throughout North America. Ripe fruits yellow, red, purple, or blue-black according to species; all are identifiable by lanternlike husk. Use only ripe fruit! **Poisonous look-alikes:** Learn to distinguish species of *Physalis* from poisonous nightshades *(Solanum)* (see JIMSON WEED and HORSE NETTLE).

Groundnut *(Also edible autumn, winter, spring)* *Apios americana*

Habitat: moist woodlands, bottomlands, thickets. **Identification:** ***perennial vine*** from 1 or more fleshy tubers arranged in a row, the tubers 1–2 cm (0.4–0.8 in) thick; stems smooth, twining around nearby plants; very white and easy to spot when mature, milky juice. ***Leaves*** alternate, ***featherlike compound*** (pinnate), 10–20 cm (4–8 in) long, ***composed of 5–9 leaflets,*** rarely less, leaflets usually 3–6 cm (1.2–2.4 in) long, lance-shaped, pointed at tip, rounded at base, smooth to hairy. ***Flowers*** July-September, densely clustered on short stalk 5–15 cm (2–6 in) long, each flower ***with 5 brownish-purple petals, resembling pea flower;*** fragrance resembles that of the violets. Fruits are dry, linear pods 5–12 cm (2–4.7 in) long, 4–7 mm (0.2–0.3 in) broad, containing 2 to several seeds, splitting open lengthwise into 2 spirally twisting valves. **Harvest:** Pick pods in midsummer to autumn as seeds mature; pods seldom abundant though. Dig tubers, starting at base of stem, working along root to obtain whole string. Good all year. **Preparation:** Roast pods at 190°C (375°F) for 20–25 min. Cool; remove seeds and brown in oil over low heat. Boil tubers in heavily salted water until tender. Season. Slice and fry leftovers, or grease and roast to regain tenderness, flavor. Also thinly slice raw tubers and fry like potatoes in butter or pork; season. Or bake at 175°C (350°F) 45–60 min until tender. Flavor turnip-like. **Related edible species:** groundnut *(A. priceana)* with 1 large tuber. **Poisonous look-alikes:** species of vetchlings *(Lathyrus),* rattlebox *(Crotalaria),* milk vetches *(Astragalus),* and point locoweeds *(Oxytropis).*

Common breadroot *Psoralea esculenta*

Habitat: prairies, plains, dry rocky woodlands. **Identification:** ***perennial herb*** to 38 cm (15 in) tall, ***developing from 1 or more swollen, elongated taproots*** 4–10 cm(1.6–4 in) long; stems short, stout, frequently branched, hairy. ***Leaves*** alternate, ***handlike (palmate) compound,*** long-stalked, ***composed of 5 leaflets,*** each 3–6 cm (1.2–2.4 in) long, uniformly wide to widest above middle, covered with long hairs. ***Flowers produced in dense elongate clusters 3–8 cm (1.2–3.2 in) long,*** each flower with leaflike bract, flowers ***blue,*** composed of 5 petals shaped like clover flower. Fruits are small pods 5–8 mm (0.2–0.3 in) long, broadest near base, long beaked, splitting open lengthwise along 2 valves. **Harvest:** Dig taproot from its hard prairie soil in early summer as stems and leaves begin to turn brown. Later above-ground parts dry and blow away making roots nearly impossible to locate. **Preparation:** important wild food staple. Peel and eat root raw, roast in campfire or boil until tender. Season like potatoes. For storage, peel and dry slowly. Grind dried root into flour or meal and use for baking. Indians cooked meal with meat and corn. Reconstitute with water to use as vegetable. **Related edible species:** *P. hypogala,* also of the plains region, produces a smaller but similar taproot. **Poisonous look-alikes:** Scurf pea *(P. tenuifolia)* and other *Psoralea* species have been toxic to horses and cattle, and so should not be eaten.

Wintergreen, Checkerberry *Gaultheria procumbens*

Also edible autumn, winter, spring

Habitat: woodlands, clearings, usually in poor acid soils. **Identification:** small herb with slender stems creeping along soil surface and erect leafy stems to 18 cm (7 in). ***Leaves*** crowded near top, each widest near or above middle, 2–5 cm (0.8–2 in) long, entire or with tiny rounded teeth along margin, ***leathery texture, shiny, with wintergreen smell when crushed. Flowers usually solitary on short drooping stalk, white,*** urn-shaped to cylinder-shaped, 5-parted at tip, 6–10 mm (0.2–0.4 in) long. ***Fruits bright red berries 6–10 mm (0.2–0.4 in) in diameter,*** globe-shaped to elongate. **Harvest:** leaves any time of year; berries from fall through winter. **Preparation:** Use leaves as trail nibble or brew into tea. Cover 1 qt young leaves with boiling water, cover container loosely and steep 1–2 days. Reheat gently, sweeten, and enjoy. Wintergreen oil concentration in tea increases with prolonged steeping. Berries ripen in fall but improve with freezing so look for them in winter and spring and use as trail nibble; add to pancakes and muffins, or, if plentiful, make uncooked jam. Combine in blender 2 cups fresh berries, 1 oz lemon juice, 1 cup strong wintergreen tea. Blend until smooth, pour into mixing bowl, add 4 cups sugar. In saucepan bring to hard boil 1 pkg pectin and ¾ cup water. Boil 1 min and stir into berry mix. Mix thoroughly, ladle into sterile jars, and seal. Store in refrigerator or freezer. Leaves and fruits contain aspirin like methyl salicylate and effectively reduce fevers and minor aches and pains. **Related edible species:** CREEPING SNOWBERRY (next). **Poisonous look-alikes:** none.



Common breadroot: July plant with remnant flower cluster on right (Young).

Wintergreen: fruiting plant, top (Dykeman). Flowering plant (Elias).



Healing Hand

Humans can build all kinds of sophisticated instruments because of the magnificence of the hands and the fingers. Another higher function of the hands is the power of healing. Knowing the major points of the hands and fingers will enable you to stimulate and maintain the organs in good function.

Palms

The palms are where all major energies of Chi join. The palm can be the place from which the life-force is sent out to heal others or yourself. The palm also is the place where energy can be received and enter into the bone structure and into the major organs.

Pericardium

The pericardium (P-8) is the main place of energy concentration. You can collect the energy in this point and transmit stronger energy from this point.

Large Intestine

The large intestine (LI-4) is the major point which controls all the pain in the body, especially in the sense organs (eyes, ears, nose) and headaches.



Creeping snowberry: fruiting plant (Elias).

Mountain sorrel: fruiting plant (Elias).



Creeping snowberry *Gaultheria hispidula*

Also edible autumn, winter, spring

Habitat: northern coniferous forests, mountains in subalpine and alpine zone. **Identification:** *small creeping herb* with very leafy stems; *leaves* alternate, simple, *evergreen,* broadest near base, to *almost round, 0.5–1 cm (0.2–0.4 in) long,* entire, bright green and smooth above, paler with long stiff hairs beneath. Flowers May-June, solitary in junction of leaves, each tiny, white, bell-shaped, 2–3 mm (0.1 in) long, on short drooping stalk. *Fruits are fleshy bright white berries 6–10 mm (0.2–0.4 in) long,* slightly longer than wide, with spicy aromatic smell when crushed, bristly. Ripen by August. **Harvest and preparation:** leaves same as WINTERGREEN (preceding). Also prepare as cooked green vegetable. Fruits ripen mid through late summer. Excellent fresh and in baked goods, jam (see WINTERGREEN), and preserves. For no-cook preserves wash and smash or grind fruit thoroughly. Add equal amount of sugar slowly with constant stirring. Pack in sterile jars and seal. **Related edible species:** WINTERGREEN, CREEPING WINTERGREEN, SALAL, and *G. ovatifolia,* also called salal, of northwest U. S. **Poisonous look-alikes:** none.

Mountain sorrel *Oxyria digyna*

Habitat: high mountains, subalpine and alpine fields, usually in rocky places 2,450–3,950 m (8,000–13,000 ft). **Identification:** perennial herb to 40 cm (16 in) high; stems upright, simple or sparingly branched, smooth. *Leaves* alternate, sometimes kidney shaped, simple, *mostly basal, blades usually rounded,* 1.6–3.2 cm (0.6–1.3 in) across, entire, smooth, long-stalked, stalk 6–12 cm (2.4–4.7 in) long. *Flowers* small, *arranged in densely flowered, elongate, compact clusters;* each flower stalked, bisexual, with 4 red to greenish sepals that persist in fruiting. *Fruits* flattened, *broadly winged, rounded, dark red, small, dry, hard, 1-seeded,* not splitting open at maturity. **Harvest:** leaves while still tender, before plant flowers. **Preparation:** Use fresh leaves as trail nibble or in salad. Combination of sour mountain sorrel and pungent species such as WATERCRESS works well with other, more neutral greens. Use a plain oil dressing. Add leaves to other greens for added flavor when cooked. In arctic regions, natives ferment mountain sorrel as sauerkraut. For puree, mash greens with food mill or blender and add to small amount of boiling water. Boil 5–10 min. Add 3 cups puree to 1 qt hot milk (or 1 cup milk and 3 cups chicken stock). Salt and pepper to taste. Bring to boil and simmer 5–10 min with stirring. Slowly add 3 beaten egg yolks. Add flour paste for desired thickness. Blend in 4 tbsp melted butter. For other uses see SHEEP SORREL. **Related edible species:** none, but SHEEP SORREL and SOUR DOCK are used similarly. **Poisonous look-alikes:** Some species of dock (RUMEX) accumulate sour-tasting oxalates.



American bistort: flowering plants (NYBG).

Alpine bistort: flowering stalks (NYBG).



American bistort, Western bistort *Polygonum bistortoides*

Also edible autumn, spring

Habitat: along streams, wet meadows, subalpine meadows. **Identification:** ***perennial herb*** to 70 cm (28 in) high, from ***thick, fleshy, horizontal rootstock;*** stems erect, slender, smooth. Leaves alternate, entire, mostly basal, 10–25 cm (4–10 in) long, 2–5 cm (0.8–2 in) wide, lower leaves uniformly wide to broadest near tip, upper ones lance-shaped and smaller, stalked, each sheathing stem at base. ***Flowering spikes cylinder-shaped at end of stem, 2–6 cm*** (0.8–2.4 in) ***long,*** to 1.5 cm (0.6 in) thick, ***pink to white,*** individual flowers tiny, lacking petals. Fruits are small, shiny brown nutlets 3–4 mm (0.1–0.2 in) long. **Harvest and preparation:** Use rootstocks and young leaves as for ALPINE BISTORT (next). Rootstock larger in American bistort, but edible bulblets are absent from flower stalks. Both species provide valuable survival fare in mountain regions where other wild foods may be unavailable. **Related edible species and poisonous look-alikes:** See ALPINE BISTORT.

Alpine bistort, Alpine smartweed *Polygonum viviparum*

Also edible autumn, spring

Habitat: arctic regions, alpine and subalpine slopes, gravelly and rocky soils. **Identification:** ***perennial herb*** to 45 cm (18 in) high, ***from short, thickened, usually twisted, underground stem;*** stem upright, sheathed at base of leaves. ***Lower leaves*** alternate, simple, ***3–10 cm*** (1.2–4 in) ***long, to 2.5 cm*** (1 in) ***wide, narrowly lance-shaped,*** pointed at tip, tapering at base, long stalked, upper leaves much smaller. Flowering spike 3–8 cm (1.2–3.2 in) long, ***upper flowers pink or white,*** tiny, lacking petals, lower flowers producing tiny reddish or purple bulbils. Fruits are small, reddish-brown, 3-angled nutlets 2–4 mm (0.1–0.2 in) long. **Harvest and preparation:** Strip tiny bulbils from lower part of flower stalks and eat raw. Dig rootstocks (easiest to find during growing season) and eat raw, boil, or roast. Young roots tender but older ones may require cooking. Boil 40 min or bake at 165°C (330°F) for 40 min. Season like potatoes. Though appearance of unpeeled roots may not be inviting, flavor is good. Use young leaves in salad with other greens or prepare as cooked greens. Boil until tender and season with butter, salt and pepper. **Related edible species:** AMERICAN BISTORT (preceding) and LADY'S THUMB used as cooked or salad green. Also JAPANESE KNOTWEED, giant knotweed *(P. sachalinense),* Alaskan knotweed *(P. alaskanum),* and others. **Poisonous look-alikes:** No species of *Polygonum* are known to be poisonous. But some may cause light-sensitive skin reaction. They vary in usefulness as cooked or salad greens, some being very peppery or acid; some, like tartary buckwheat *(P. tataricum),* produce edible seeds.

Purslane, Pusley *Portulaca oleracea*

Habitat: fields, vacant lots, waste sites; common garden weed. **Identification:** annual ***herb, lying flat on ground*** or nearly so and ***forming mats to 1 sq ft, stems smooth, fleshy, shiny, often reddish purple. Leaves*** alternate and opposite, 2–5 cm (0.8–2 in) long, 1–2 cm (0.4–0.8 in) wide, ***fleshy, broadest near the rounded tip,*** entire along margin. ***Flowers*** single, or few clustered at tips of branches, flower 0.5–1 cm (0.2–0.4 in) wide, ***with 5 yellow petals. Fruits are capsules,*** 4–8 mm (0.2–0.3 in) long, broadest near base and rounded at tip, ***top portion falling away at maturity*** to expose dark red to black seeds. **Harvest:** Pinch or cut young leafy tips June–September. Pick larger stems in midsummer for pickles. To gather seeds, spread whole mature plants on sheet to dry for 2 weeks, then sieve and winnow. **Preparation:** One of best wild shoots cooked or in salad. Common and nutritious; acid taste; high in iron. For tossed salad combine raw shoots with other ingredients. Use oil and vinegar dressing. Cook young plants as potherb 10 min and season with butter and salt. For casserole chop cooked shoots, stir in 1 beaten egg and enough bread crumbs to make damp mix. Add salt and pepper, bake in moderate oven. Pickle stems same as cucumbers. Blanch and freeze tips for later use. To dry, boil thick stems in a little water for 20 min. Drain, dry in warm shady area, store in paper bag for later use in soups or stews as thickener. Dry seed 1 week in shade, store in paper bag. Grind and use half and half with flour. **Related edible species:** at least 2 *(P. neglecta* and *P. retusa)* which are very similar. **Poisonous look-alikes:** none.

Sunflower *(Also edible autumn)* *Helianthus annuus*

Habitat: prairies, plains, roadsides, disturbed sites. **Identification:** ***perennial herb 1–2.5 m (3.2–8.2 ft) high,*** from large taproot; stem upright, unbranched to branched, with stiff hairs. ***Leaves*** mostly alternate, simple, ***6.5–30 cm*** (2.6–12 in) ***long,*** nearly as wide at base, ***broadly to narrowly triangular,*** tapering to short- or long-pointed tip, toothed near tip, heart-shaped at base, with stiff hairs on both surfaces. Flowers produced in heads to 15 cm (6 in) across, single, stalked, base of head cup-shaped, ***ray flowers with yellow petals 2.5–5 cm*** (1–2 in) ***long,*** central disc flowers lacking showy petals, brown. Fruit flattened, dry, 1-seeded, 4–6 mm (0.2 in) long. **Harvest:** Gather seed heads in late summer to early autumn before seeds are dry enough to be released. Hang in warm, dry place. **Preparation:** Indians parched then ground unshelled seeds into fine meal. Meal was added to water and drunk or mixed with marrow to form dough and eaten. To separate nutmeats from shells, break hulls with chopper, very coarse grinder, or food mill. Pour broken seeds into water, stir vigorously, let settle. Nutmeats will sink and shells will rise to top. Skim shells for making coffee. For use in nut recipes, drain, dry, and roast nutmeats. Grind nutmeats into meal and use for part of flour in muffin and bread recipes. For nut butter grind raw nutmeats into paste; add honey or maple syrup if necessary to improve flavor. To produce oil, thoroughly crush or grind raw seeds. Boil in water. Skim oil off broth. **Related edible species:** All of the nearly 60 species in North and South America are edible. **Poisonous look-alikes:** none.


Introduced and
grows wild.
Widespread.

Purslane: flowering plant (NYBG).

Sunflower: flowering stalks (Elias). Cultivated form with larger flowering head (Feldman).


Native
in West


Introduced and grows wild. Widespread.

Quickweed: flowering plant and flowers (NYBG).

Bearberry: fruiting branches (Elias).



Quickweed, Galinsoga *Galinsoga parviflora*

Habitat: disturbed sites, roadsides, yards; also garden weed. **Identification:** annual herb to 70 cm (28 in) high, often bushy, stems usually spreading, smooth to slightly hairy. ***Leaves opposite,*** simple, usually lance-shaped, 2.5–8 cm (1–3.1 in) long, 1.2–4 cm (0.5–1.6 in) wide, pointed at tip, small blunt teeth along margin, tapering to rounded at base, with 3 principal veins, papery, usually stalked. ***Flowers tiny, produced in heads, 4–5 outer scale-like bracts (involucre) 2–3 mm (0.1 in) high, green; outer (ray) flowers white, inner (disc) flowers yellow.*** Fruits small hard nutlets 1–1.5 mm (0.1 in) long, nearly black, hairy. **Harvest:** young plants during middle of growing season. **Preparation:** Discard roots. Boil tops about 15–25 min and serve with salt, pepper, and butter. Add more flavorful greens and vinegar to compensate for quickweed blandness. **Related edible species:** *G. ciliata* (also called quickweed) plus a few other *Galinsoga* species, all introduced from southwest U.S., Mexico, and points south. **Poisonous look-alikes:** none.

Bearberry, Kinnikinick *Arctostaphylos uva-ursi*

Habitat: circumboreal, subarctic; sandy or rocky soils, higher elevations in southern part of range. **Identification:** ***low spreading shrub, forming mats*** with tough flexible twigs. ***New twigs hairy and sticky; mature ones*** dark reddish-brown or gray, ***papery and peeling. Leaves*** alternate, simple, ***evergreen, 1–3 cm*** (0.4–1.2 in) ***long,*** broadest near rounded tip, entire, shiny above, leathery. Flowers tiny, 5–12 per elongated cluster, each white to pale pink, urn-shaped, 4–6 mm (0.2 in) long. ***Fruits bright or dull red berries 4–10 mm (0.2–0.4 in) in diameter, mealy,*** not tasty. **Harvest and preparation:** leaves called *kinnikinick,* an Indian tobacco substitute also used by frontiersmen. For smoking, leaves are mildest in summer; dry in sun or near fire, crumble, and light up. Dried leaves make medicinal tea, good for indigestion. Fruits ripen late in growing season. Raw, they are bland and dry, but cooked they become palatable with cream and sugar. Not great snack but useful survival food. **Related edible species:** alpine bearberry *(A. alpina)* and several manzanitas plus many species in other genera in heath family. **Poisonous look-alikes:** none.

Salal, Western wintergreen *(Also edible autumn)* *Gaultheria shallon*

Habitat: woods, clearings, brushy areas below 800 m (2,630 ft), from West Coast to west slope of Cascades. **Identification:** ***upright, many branched shrub*** 0.3–2.5 m (1–8.2 ft) tall, frequently forming dense thickets. ***Leaves evergreen,*** alternate, simple, uniformly wide to broadest near middle, 3–10 cm (1.2–4 in) long, finely toothed, dark, shiny above, paler beneath. Flowering clusters narrow, elongate, composed of 5–15 stalked flowers, each urn-shaped, white or pink, 8–10 mm (0.3–0.4 in) long; prominent leaflike bract and 2 bractlets at base of flower stem. ***Fruits dark-purple berries,*** 7–8 mm (0.3 in) in diameter, nearly round, thick skinned, star-shaped depression on end, with several seeds. **Harvest:** Fruits ripen in summer and persist several weeks. **Preparation:** edible fresh but sometimes quite spicy and not juicy; better cooked. Also dry in sun or warm attic. Good in jam, jelly, pies, baked goods. See basic jelly and jam recipes, in book's Introduction. For beverage crush and boil berries, extract juice, and add equal amount of water. Sweeten, if necessary. **Related edible species:** WINTERGREEN, CREEPING WINTERGREEN (next), CREEPING SNOWBERRY, and *G. ovatifolia,* also called salal, of northwest U.S. **Poisonous look-alikes:** none.

Creeping wintergreen *(Also edible autumn, winter)* *Gaultheria humifusa*

Habitat: subalpine and alpine zones and moist slopes of western and Pacific Northwest mountains. **Identification:** low shrub with short spreading branches along ground. ***Leaves*** alternate, simple, ***evergreen,*** broad, ***broadest near base or middle, 1–2 cm (0.4–0.8 in) long, almost as wide,*** entire or with tiny teeth along margin, leathery. Flowers solitary in junction of leaves, each white, urn-shaped, 3–4 mm (0.1–0.2 in) long. ***Fruits are dry berries 4–8 mm*** (0.2–0.3 in) ***in diameter,*** rounded, ***red at maturity.*** **Harvest and preparation:** same as WINTERGREEN. Dryness makes fruit less palatable than other *Gaultheria* species. **Related edible species:** See SALAL (preceding). **Poisonous look-alikes:** none.

Labrador tea *(Also edible autumn, winter, spring)* *Ledum groenlandicum*

Habitat: bogs, fens, heaths, northern woods, exposed bluffs. **Identification:** low shrub up to 1 m (3.2 ft) high, with erect, reddish-brown branches, densely hairy when young. ***Leaves*** alternate, simple, ***evergreen,*** fragrant, crowded near tip of twigs, 1.5–5 cm (0.6–2 in) long, 4–12 mm (0.2–0.5 in) wide, uniformly wide to slightly wider at middle, rounded at tip, ***margin entire and rolled under, leathery,*** dull dark green above, ***densely hairy beneath, white at first, turning rusty.*** Flowers produced in late spring or summer in rounded clusters, each with 5 cream-white petals, stalked. Fruits are dry capsules 4–6 mm (0.2 in) long, slender, long-stalked, splitting open from base. **Harvest:** any time but least good in midwinter. Pick leaves when dense pile beneath is rust colored. Dry in sun, over low fire, or in oven. **Preparation:** Steep 1 tbsp dried leaves in 1 cup boiling hot water for 10 min. Do not boil water with leaves in it, which may release a harmful alkaloid. Serve hot or cold. **Related edible species:** northern Labrador tea *(L. palustre).* **Poisonous look-alikes:** mountain Labrador tea *(L. glandulosum)* is described by some sources as poisonous.



Salal: fruiting and flowering branches (Ross).



Creeping wintergreen: fruiting plants (Mulligan).

Labrador tea: flowering plant (Elias).




Heart Governor (HG-9)
Heart (HT-9)
Lung (LG-11)
Pericardium (P-8)

Fig. 1 *Pericardium*


Triple Warmer (TW-1)
Large Intestine (LI-1)
Small Intestine (SI-1)
LI-4
SI
TW
LI

Fig. 2 *Large Intestine*



Mountain cranberry: flowers (NYBG). Fruiting plant (Elias).

Cranberry: flowering plants (NYBG). Fruit (Elias).



The BLUEBERRY and CRANBERRY GENUS *Vaccinium*

Blueberries, cranberries, huckleberries, and bilberries are all closely related groups of species of the *Vaccinium* genus. There are perhaps 35 species in North America, but hybridization is common. Fruits of most species are edible and range in taste from tart to sweet. The domesticated blueberries are selections of the highbush blueberry *(V. corymbosum)*. Wild blueberries sold commercially are commonly obtained from late sweet blueberry *(V. angustifolium)* or velvet-leaved blueberry *(V. myrtilloides)*. The supermarket cranberry *(V. macrocarpon)* is the same as the wild. Berries are rich in vitamin C.

Mountain cranberry, Lingenberry, Foxberry *Vaccinium vitis-idaea*

Also edible autumn, winter

Habitat: widespread subarctic and alpine plant, bogs, cold seepage areas, rocky acid soils. **Identification:** ***small, creeping plant,*** to 15 cm (6 in) with slender stems; ***leaves*** alternate, simple, ***evergreen,*** broadest above middle, ***0.6–1.8 cm (0.2–0.7 in) long, 4–10 mm (0.2–0.4 in) wide,*** entire, leathery, with scattered black glandular hairs beneath, midrib furrowed. Flowers tiny, pink to reddish, 6–8 mm (0.2–0.3 in) long, narrowly bell-shaped. ***Fruits red berries, rounded, 6–10 mm (0.2–0.4 in) in diameter,*** often persisting over winter, slightly acid tasting. **Harvest and preparation:** Fruits ripen August and September; many persist on plant through winter. Tart to bitter at first; flavor improves after frost. Good trail snack, better used in any cooked cranberry recipes. **Related edible species:** CRANBERRY (next). **Poisonous look-alikes:** none.

Cranberry *(Also edible autumn, winter)* *Vaccinium macrocarpon*

Habitat: widespread northern plant; bogs, swamps, shores of cold acid lakes. **Identification:** ***low, trailing shrub*** with slender brown, flaky-barked stems; ***leaves*** alternate, simple, ***evergreen,*** uniformly wide to broadest near middle, ***5–16 mm (0.2–0.6 in) long,*** rounded at tip, leathery, whitish beneath. Flowers single or in few-flowered clusters on long stalks in junction of upper leaves, each stalk with 2 leaflike bracts, each flower pink, urn-shaped, 4 petals bent back, 6–10 mm (0.2–0.4 in) long. ***Fruits*** are ***berries 1–2 cm (0.4–0.8 in) in diameter,*** globe-shaped, green turning ***bright red at maturity,*** each on long slender stalk. **Harvest:** Fruits ripen September through October and persist into winter in protected areas. Fruits may be harvested with toothed scoop. **Preparation:** Fresh acidic fruits keep well in cool storage. Freeze or dry for long storage. To dry berries, spread on tray or foil in oven for 4 hr at 110°C (230°F). Experiment with substituting dried, powdered berries for part of flour in baking recipes. Most common use of fresh and frozen berries is in sauce served with roast turkey. Bring to boil 2 lb fresh cranberries, 2 cups sugar, 1 cup water (or berries plus 1 cup maple sugar and 1 cup cider). Reduce heat and simmer until all berries pop, and mix looks glassy. For storage, ladle into sterile jars and seal. Check recipe books. **Related edible species:** MOUNTAIN CRANBERRY (preceding); small cranberry *(V. oxycoccos)* is similar but smaller. HIGHBUSH CRANBERRY is not related but has almost identical fruits. **Poisonous look-alikes:** none.

Bog bilberry *Vaccinium uliginosum*

Habitat: widespread boreal and arctic plant; bogs, rocky outcrops, high mountain slopes. **Identification:** ***low shrub to 0.6 m*** (2 ft) high; branches stout, usually spreading; ***leaves*** alternate, simple, ***deciduous, broadest near tip or middle to uniformly wide, 0.5–2 cm*** (0.2–0.8 in) ***long,*** rounded at tip, entire, firm to leathery texture, dull green. Flowers ***solitary or in clusters of 2–4 on short stalks*** in junctions of leaves; each pink to whitish, urn-shaped. ***Fruits fleshy berries 5–8 mm (0.2–0.3 in) in diameter, dark blue to black,*** sweet, with many tiny seeds. **Harvest and preparation:** same as LATE SWEET BLUEBERRY. **Related edible species:** See LATE SWEET BLUEBERRY. **Poisonous look-alikes:** none.

Highbush blueberry, Swamp blueberry *Vaccinium corymbosum*

Habitat: widespread in eastern North America; bogs, low wet woodlands, swamps, occasionally drier soils. **Identification:** ***shrubs,*** variable in shape, ***1–4.5 m*** (3.2–14.8 ft) ***high; leaves*** alternate, simple, ***deciduous,*** broadest near base or middle, sometimes narrowly so, ***3–8 cm (1.2–3.2 in) long,*** 2–3 cm (0.8–1.2 in) wide, usually entire, greenish-yellow. ***Flowers densely clustered,*** each tubular to urn-shaped, white to pink, 5–10 mm (0.2–0.4 in) long. ***Fruits fleshy berries, rounded, 6–12 mm (0.2–0.5 in) in diameter, dark blue to bluish-black, sweet,*** containing many tiny seeds. **Harvest:** Gather ripe fruits in late summer. They can be eaten as trail snack or stored for later use. Fruits ripen as do those of LATE SWEET BLUEBERRY (next), but are easier to gather. Hand pick or shake berries onto blanket or plastic tarp spread beneath bush. **Preparation:** Same as LATE SWEET BLUEBERRY. Also see basic recipes early in book. Add cup dried blueberries to favorite stew recipe. For fritters prepare batter from 1 cup biscuit mix, 3 tbsp sugar, ⅓ cup milk, 1 beaten egg, 1 cup fresh blueberries. Drop spoonfuls into hot cooking oil; brown both sides. Drain; dust with sugar. **Related edible species:** See LATE SWEET BLUEBERRY. **Poisonous look-alikes:** none.

Late sweet blueberry *Vaccinium angustifolium*

Habitat: dry rocky soils, barrens, mountain slopes, occasionally bogs; northcentral and northeastern North America. **Identification:** ***low shrub to 0.3 m*** (1 ft), much branched, often forming thickets. ***Leaves*** alternate, simple, deciduous, ***narrow*** and broadest at or below middle, 1–3 cm (0.4–1.2 in) long, ***finely toothed along margins,*** bright green, smooth. ***Flowers produced in short tight clusters,*** each nearly cylinder-shaped, white to pinkish tinged, 5–6 mm (0.2 in) long. ***Fruits*** are ***fleshy berries 5–12 mm*** (0.2–0.5 in) ***in diameter,*** rounded, ***bright blue,*** white bloom, sweet. **Harvest:** This and other blueberry species ripen in summer, generally after raspberries (RED RASPBERRY) and before blackberries (COMMON BLACKBERRY) where those berries grow. Pick by hand. **Preparation:** Blueberries were probably the most important fruit to American Indians. Excellent dried like raisins and fresh, both raw and in most berry recipes, especially pies, jams, and breads (see basic recipes early in book). Dry thoroughly in sun or warm attic about 10 days or in 100°C (210°F) oven for 4–5 hr; store in sealed containers. For bannock, blend 2 cups sifted flour, 3 tsp baking powder, ½ tsp



Bog billberry: fruiting plant (Elias).



Highbush blueberry: flowering branch (NYBG). Fruiting branch (Elias).

Late sweet blueberry: flowering and fruiting branches (Speas).





Black huckleberry: fruiting branch (Elias).

Beach plum: fruiting branches (Elias).



salt, 6 tbsp shortening, 4 tbsp powdered milk. Mix in 1 cup blueberries, then ⅓ cup water. Shape into 1 in thick cake, dust with flour, place in heated frying pan. Cook over coals until bottom is crusty. Turn with spatula and bake until done; test with straw or sliver. See HIGHBUSH BLUEBERRY (preceding) for other uses. **Related edible species:** Other *VACCINIUM*. **Poisonous look-alikes:** none.

Black huckleberry

Gaylussacia baccata

Habitat: woodlands, clearings, dry to moist soils. **Identification:** shrub to 1.2 m (4 ft), often forming low thickets; branches numerous, stiff, resembling blueberry bush. ***Leaves*** alternate, simple, deciduous, ***3–6 cm*** (1.2–2.4 in) ***long,*** uniformly wide to broadest near or below middle, entire, ***gland-dotted above and below. Flowers few on short elongated clusters, each white,*** small, cone-shaped to almost tubular, 4–7 mm (0.2–0.3 in) long. ***Fruits fleshy berries 6–9 mm*** (0.2–0.4 in) ***in diameter, black at maturity,*** containing 10 tiny seeds, sweet. **Harvest and preparation:** Pick berries as they ripen in late June in south to September in far north. Eat as fresh fruit or use in desserts, pancakes, jam, and jelly. For pancakes add 1 cup berries to 3–4 cups batter. To dry, spread berries in single layer on tray, foil, or paper in warm attic; dry about 10 days or until squashed berry releases no juice. Store in sealed container. Use dried berries in baking or pemmican. Or add ½–1 cup dried berries to beef stew. See LATE SWEET BLUEBERRY and HIGHBUSH BLUEBERRY for other recipes. **Related edible species:** Dwarf huckleberry *(G. dumosa),* box huckleberry *(G. brachycera),* and dangleberry *(G. frondosa)* all yield berries edible but inferior to blueberries. **Poisonous look-alikes:** none.

Beach plum

Prunus maritima

Also edible autumn

Habitat: coastal regions, sandy soils. **Identification:** shrub to 2.5 m (8 ft) or low and straggling; branches hairy when young, smooth later. ***Leaves*** alternate, simple, deciduous, ***3–7 cm*** (1.2–2.8 in) ***long,*** 1.5–3.5 cm (0.6–1.4 in) wide, broadest at or below middle, rarely widest above middle, pointed at tip, ***sharply toothed along margin,*** dull green and smooth above, softly hairy beneath. ***Flowers 2–4 per cluster, each 1–1.5 cm*** (0.4–0.6 in) ***across,*** with 5 ***white*** petals. ***Fruits rounded*** or nearly so, ***1.5–2.5 cm*** (0.6–1 in) ***in diameter, deep purple to reddish-black at maturity,*** fleshy, sour tasting, enclosing large stone. **Harvest:** Pick fruit from August through October, depending on location. Slightly unripe fruit best for jelly. **Preparation:** similar to AMERICAN PLUM but fruit is more tart. Use jelly and jam recipes early in book. Also, make jellies and jams from blend of plum and other fruits. Combine with peaches or other sweet pulpy fruit for pie filling; see basic plum pie recipe early in book. To dry fruit for later use, slit skin and remove pit. Pits contain toxic hydrocyanic acid. Spread fruit in sun or warm oven until no juice can be squeezed from them, about 4–6 hr. Makes tart trail snack. **Related edible species:** AMERICAN PLUM, FLATWOOD PLUM, and several others. **Poisonous look-alikes:** none.

CURRANT or GOOSEBERRY GENUS *Ribes*

This large group of about 120 species is centered in western North America and the Andes Mountains of South America. They are shrubs, sometimes armed with spines, with simple, maplelike, alternate leaves, flowers in small clusters, and a 1-celled pulpy berry, sometimes transparent, variously colored, containing several seeds. North American species are sometimes difficult to distinguish. Fortunately, none is known to be poisonous. We recommend 2 common yellow-flowered species with smooth fruits and 2 pink- to purple-flowered species with glandular hairy fruits. **Harvest:** Pick fruits in summer as they ripen. **Preparation:** Sweetness and juiciness vary greatly among species. Some fruits can be eaten fresh. Some are spiny and so require cautious eating. Adapt recipes to berry characteristics. For no-cook currant or gooseberry preserves, wash and mash fruits thoroughly. Slowly mix in sugar equal to volume of crushed fruit. Pour into sterilized jelly glasses and seal. For preserves wash and stem 1 lb currants; add ¾ lb sugar and let stand overnight. Bring slowly to boiling point and boil 3–5 min. Let stand overnight, pour into jelly glasses, and seal. To make

Golden currant: flowers (NYBG). Fruiting branches (USDA).



currant/gooseberry conserve, wash and stem 3 lb berries. Grate rind of 3 oranges and cut up pulp. Mix berries, orange rind and pulp, 1 lb seeded raisins, and 3 lb sugar, cook slowly until thick. Pour into sterilized jars and seal. For simple currant/gooseberry pie wash and stem 1 pt berries. Cook in saucepan with 1 cup sugar and small amount of water about 15 min until berries soften. Pour into pie crust, add top crust, bake at 175°C (350°F) oven until crust is done. Add fresh or dried berries to kuchen dough and muffins. To dry whole or mashed berries spread in thin layer on baking sheet; place in sun or 105°C (220°F) oven until dry. Store in paper bag in dry place. To make pemmican mix 1 lb dried and finely ground or pounded meat with ¼ cup brown sugar and ½ cup dried berries. Add ¾ lb melted suet and blend into paste. Form into bars and store dry. Eat as is, boil, or fry. For pie and cooked jelly see recipes early in book. **Related edible species:** many in addition to the four described; widely distributed. **Poisonous look-alikes:** Sticky currant *(R. viscosissimum)* is reported to be a strong vomitory. It has a sticky substance on the leaves, twigs, and fruit. Some fruits are covered with short, bristly hairs.

Golden currant *Ribes aureum*

Habitat: along streams, ravines, washes, mountain slopes, mainly between 750–2,380 m (2,460–7,800 ft) elevation. **Identification:** shrub, erect, open, to 2 m (6.6 ft); branches stiff, nearly smooth. ***Leaves*** alternate, deciduous, 1.2–4.5 cm (0.5–1.8 in) long, 1.5–5 cm (0.6–2 in) wide, ***broadly rounded to widest near base, 3-lobed,*** rounded at tip, entire to coarsely toothed along margin, ***light green,*** smooth, stalked. ***Flowers*** produced in drooping, 5–15-flowered, elongated clusters in late spring, each flower ***bright yellow,*** 5-parted, 6–10 mm (0.2–0.4 in) long, ***smooth. Fruits stalked berries,*** rounded, 6–9 mm (0.2–0.4 in) in diameter, ***red*** or occasionally black, ***smooth, beaked*** (persistent floral parts), produced in summer. **Harvest and preparation:** See CURRANTS, GOOSEBERRIES (preceding). This species both wild and cultivated was much used by western Indians; one of the best flavored species.

Wax currant *Ribes cereum*

Habitat: canyons, dry ravines, hillsides, prairies, open woodlands. **Identification:** open spreading shrub to 1 m (3.2 ft) high; branches stiff, crooked. ***Leaves*** alternate, simple, deciduous, 2–2.5 cm (0.8–1 in) long, 2.5–3 cm (1–1.2 in) wide, ***broadly rounded, wider than long, shallowly 3-lobed,*** rounded at tip, irregularly ***round toothed along margin,*** yellowish-green, glandular hairy on both surfaces, leafstalk 8–15 mm (0.3–0.6 in) long. ***Flowers*** in drooping, 1–6-flowered, elongated clusters in late May or June, each flower ***white to pinkish,*** 5-parted, 6–10 mm (0.2–0.4 in) long. ***Fruits stalked berries, globe-shaped,*** 8–12 mm (0.3–0.5 in) in diameter, ***dull to bright red, with stalked glandular hairs,*** beaked (the persistent floral parts), produced in July or August. **Harvest and preparation:** See CURRANTS, GOOSEBERRIES (preceding). Wax currant is native in West, though frequently cultivated in East.

Subalpine prickly currant *Ribes montigenum*

Habitat: along streams, wet forests, ravines, washes, mainly in subalpine zone 2,140–3,800 m (7,000–12,500 ft) elevation. **Identification:** ***shrub,*** open, spreading, sometimes straggling, to 0.7 m (28 in) high; branches tough, ***densely covered with glandular hairs, stiff bristlelike prickles with small spines at leaf bases. Leaves*** alternate, deciduous, simple, 0.8–3 cm (0.3–1.2 in) long, as wide or wider, almost circular in outline, ***deeply 5-lobed,*** pointed at tip, sharply toothed along margin, glandular hairy on both surfaces, stalked. Flowers produced in drooping, few-flowered clusters in late spring or early summer, each ***flower*** stalked, ***purplish,*** 5-parted, 4–8 mm (0.2–0.3 in) long, ***covered with glandular hairs. Fruits*** stalked ***berries,*** rounded, 4–6 mm (0.2 in) in diameter, ***red, covered with glandular hairs,*** produced in summer. **Harvest and preparation:** See CURRANTS, GOOSEBERRIES (preceding).

Fragrant golden currant *Ribes odoratum*

Habitat: prairies, open woodlands, bluffs, ledges, ravines. **Identification:** ***shrub,*** upright, open, to 1.5 m (5 ft); branches tough, reddish-brown, hairy, ***spineless. Leaves*** alternate, simple, deciduous, 3–6 cm (1.2–2.4 in) long, slightly wider, broadly rounded to widest near base, ***3–5-lobed,*** pointed to blunt at tip, coarsely toothed along margin, hairy, stalked. ***Flowers*** produced in drooping, few-flowered clusters from older wood in spring, each flower ***pale yellow,*** 5-parted, 12–16 mm (0.5–0.6 in) long, smooth. ***Fruits, produced in summer, stalked berries, globe-shaped, 9–12 mm*** (0.4–0.5 in) ***in diameter, purplish-black, smooth,*** with beaked persistent floral parts. **Harvest and preparation:** See CURRANTS, GOOSEBERRIES (preceding).



Wax currant: fruiting branches (Ross).



Subalpine prickly currant: fruiting branch (Dykeman).

Fragrant golden currant: fruiting branches (Kavasch).



Major Palm Lines

The three major palm lines are the Life Line, the Line of Intellect and the Line of Emotion.

Fingers have Corresponding Bodily Functions

The fingers are connected to the organs' meridians. The joints of the finger bones are also related to parts of the organs and their corresponding senses and emotions.


Circulatory and Excretory Systems (Line of Emotion)
Nervous System (Line of Intellect)
Digestive and Respiratory Systems (Life Line)

Fig. 3 *Three Major Palm Lines*



American hazelnut: fruiting branches (Elias).

Beaked hazelnut: fruits (Speas).



American hazelnut *Corylus americana*

Also edible autumn

Habitat: widespread, dry to moist woodlands, thickets. **Identification:** shrub to 5 m (16.4 ft) with rounded head and glandular hairy twigs. ***Leaves*** alternate, simple, deciduous, 5–15 cm (2–6 in) long, 3–12 cm (1.2–4.7 in), broadest below or above middle, long-pointed at tip, ***doubly toothed*** along margin, usually hairy beneath. Male flowers in dense slender catkins in early spring. Female flowers usually solitary or paired, tiny, inconspicuous in early spring. ***Fruits are hard-shelled nuts, broader than long,*** 1–1.5 cm (0.4–0.6 in) across, ***partially enclosed by 2 ragged-edged leaflike bracts,*** nutmeat sweet. **Harvest:** Nuts mature in late summer or autumn. **Preparation:** Remove husk, shell, and eat as is, or use in any recipe calling for nuts. For no-cook candy, mix 1 egg white with 2 cups confectioner's sugar. Add 2 tsp butter or margarine and blend until smooth. Work in 2 cups chopped hazelnuts and form into balls. Eat and enjoy. For hazelnut hot cakes, finely grind 0.2 kg (½ lb) dried hazelnuts. Boil in 2 cups water until mushy, about 30 min. Add 1 tsp maple syrup and ⅓ cup fine cornmeal, stir well, let stand for 20 min or until thick. Heat ⅓ cup frying oil in skillet. Drop batter by tablespoonfuls into hot oil. Brown on one side, flip, flatten, brown on other side. Drain and serve hot or cold. See also BEAKED HAZELNUT (next). **Related edible species:** BEAKED HAZELNUT. **Poisonous look-alikes:** none.

Beaked hazelnut *Corylus cornuta*

Also edible autumn

Habitat: dry or moist woodlands, hills or mountain slopes, absent on Coastal Plain. **Identification:** shrub to 3 m (9.8 ft), often forming thickets; twigs hairy when young. Leaves alternate, simple, deciduous, 3–10 cm (1.2–4 in) long, 2–8 cm (0.8–3.2 in) wide, broadest near base, long-pointed at tip, doubly toothed along margin, hairy beneath. Male flowers in dense, slender catkins in early spring. Female flowers solitary or few per cluster, tiny, inconspicuous. ***Fruits*** are ***thin-shelled nuts,*** broadest near base, 1–1.5 cm (0.4–0.6 in) in diameter, ***enclosed by 2 bristly leaflike bracts 4–7 cm*** (1.6–2.8 in) ***long which form narrow beak;*** nutmeat sweet. **Harvest:** Nuts mature in late summer or autumn. **Preparation:** Remove husk. Shell and eat as is or use in recipes calling for nuts or grind into meal to use as flour. For hazelnut torte preheat moderate oven 175°C (350°F). Beat 11 egg yolks well, add 0.5 kg (1 lb) confectioner's sugar, continuing to beat. Add 0.5 kg (1 lb) ground hazelnuts and 1 tsp instant coffee. Fold in 11 stiffly beaten egg whites. Bake in 30 cm (12 in) greased and floured spring baking form for 50–60 min. See also AMERICAN HAZELNUT (preceding). **Related edible species:** AMERICAN HAZELNUT. **Poisonous look-alikes:** none.

Sweet fern *Comptonia peregrina*

Also edible winter, spring

Habitat: dry rocky, sandy, or gravelly soils of clearings, pastures, poor open woodlands. **Identification:** small shrub 0.4–1.2 m (1.3–4 ft) high, with rounded shape; young branches hairy. ***Leaves*** in fernlike pattern, alternate, simple, deciduous, ***6–14 cm*** (2.4–5.5 in) ***long, 0.8–1.2 cm*** (0.3–0.5 in) ***wide,*** widest near middle or base, ***deeply lobed along margin, fragrant due to numerous resinous glands*** on leaves and twigs. Male and female flowers produced in separate small catkins on same bush in spring. ***Fruits small, green burrs 1–2 cm*** (0.4–0.8 in) ***in diameter,*** each partially or totally enclosing 1–4 nutlets, maturing in mid to late summer. **Harvest:** leaves any time for fragrant tea. Immature nutlets during June and July while still tender. **Preparation:** For tea add 1 tsp dried or 2 tsp fresh leaves per cup boiling water; steep. When camping, put 8 tsp fresh, chopped leaves per qt of water in glass jar. Cap and place in sun 3 hr or until water is dark. Strain, dilute to taste, sweeten if desired. Not bitter like many brewed teas. Strong tea (infusion) has been used to alleviate dysentery. Using thumbnail, separate nutlets from burrs when immature and eat raw. **Edible related species:** northern bayberry *(Myrica pensylvanica),* SOUTHERN BAYBERRY and SWEET GALE (next). **Poisonous look-alikes:** none.

Southern bayberry, Wax myrtle *Myrica cerifera*

Also edible autumn, winter

Habitat: coastal plain, swamps, along ponds and lakes, pine barrens, wet sandy soils. **Identification:** shrub or small tree to 8 m (26 ft) with rounded crown and slender, hairy, ***gland-dotted twigs. Leaves*** alternate, simple, deciduous but often persisting until second year, ***3.5–10 cm*** (1.4–4 in) ***long,*** 0.6–1.2 cm (0.2–0.5 in) wide, ***narrow*** but broadest near tip, ***coarsely toothed along margin, yellow-green, gland-dotted, fragrant when rubbed.*** Male and female flowers on separate bushes in spring; male flowers in slender catkins 1.2–1.9 cm (0.5–0.7 in) long; female flowers in broader catkins 0.6–1.2 cm (0.2–0.5 in) long on older twigs. ***Fruits few to several clustered on short spikes, each rounded, 2–4 mm (0.1 in) in diameter, covered with light blue waxlike coating.*** **Harvest and preparation:** Pick leaves any time available but best in early summer. Wash and spread to dry thoroughly in warm shaded area. Store in sealed jars in dark place. Crumble and blend into stews and sauces for cooking and serving meats. Also use berries picked from late summer into winter as seasoning and to provide wax used in candles. **Related edible species:** northern bayberry *(M. pensylvanica)* and other wax myrtle species are used the same way. Also SWEET GALE (next) is used for seasoning but fruits lack wax. **Poisonous look-alikes:** none.



Sweet fern: mature plant and branch with fruit (Elias).

Southern bayberry: fruiting branches (NYBG).



Sweet gale *Myrica gale*

Also edible autumn, winter

Habitat: swamps and shallow water along ponds and streams. **Identification:** shrub 0.3–2 m (1–6.6 ft) tall with upright brown branches. ***Leaves*** alternate, simple, ***deciduous, wedge shaped,*** rounded, ***broadest near tip,*** toothed near tip, ***dark green above, pale beneath, downy on veins,*** 2–7 cm (0.8–2.8 in) long, ***aromatic*** when crushed. ***Male flowers in spikelike catkins at end of twigs; female flowers usually on separate plants,*** about 8 mm (0.3 in) long, ***at base of leaves. Fruit small nutlike, not waxy,*** resin dotted, aromatic, with 2 winglike scales, ***in small conelike clusters.*** **Harvest:** Pick leaves as described for SOUTHERN BAYBERRY (preceding) and aromatic nutlets from summer through winter. **Preparation:** Dry and use leaves as described for SOUTHERN BAYBERRY and for making hot tea. Use nutlets like dried leaves for seasoning. **Related edible species:** See SOUTHERN BAYBERRY. **Poisonous look-alikes:** none.

New Jersey tea *Ceanothus americanus*

Habitat: open woodlands and prairies, in well-drained rocky, gravelly, or sandy soils. **Identification:** ***shrub*** to 1 m (3.2 ft) with slender, reddish-brown, densely hairy twigs. ***Leaves*** alternate, simple, 3-ribbed, deciduous, ***4–8 cm*** (1.6–3.2 in) ***long,*** 2–4 cm (0.8 –1.6 in) wide, broadest near base, rounded at tip, ***finely toothed along margin,*** green above, gray and hairy beneath. ***Flowers tiny, white, produced in dense, short cylinder-shaped, branched clusters in spring,*** each with 5 white petals shaped like tiny tobacco pipes. Clusters from leaf junctions. ***Fruits*** produced in rounded clusters in late spring or early summer, each ***capsulelike, 5–6 mm*** (0.2 in) ***long,*** splitting open to release tiny, reddish-brown seeds. **Harvest:** Gather fresh leaves in summer, best when bushes are flowering. Dry leaves thoroughly in sun, by fire, or in warm oven. **Preparation:** For tea, steep 1 tbsp fresh or 1 tsp dried leaves in 1 cup boiling water for 15 min. Sweeten to taste. Caffeine free. Dried root bark tea was used as sedative by Indians. **Related edible species:** Red root *(C. ovatus)* is also known as New Jersey tea. *C. americanus* has wider leaves and flower clusters at leaf junctions instead of at end of twig. **Poisonous look-alikes:** none.



Sweet gale: fruiting branch and fruits (Elias).

New Jersey tea: flowers (Mohlenbrock). Flowering branch (NYBG).





Silver buffaloberry: fruiting branches (Elias). Flowering branch (NYBG).

BRAMBLES, BLACKBERRIES, RASPBERRIES *Rubus*

This is a large and variable group of approximately 300 to 400 species in the temperate regions of the world. Members of this genus are shrubs or trailing, often prickly, vines, collectively known as brambles. Fruits may or may not separate from the spongy core of the fruit base when picked. The genus normally is divided into subcategories; one containing blackberries and dewberries, another containing thimbleberries, another raspberries. Most of the species have edible fruits; many have delicious fruits. Six of the more common species are treated on the following pages. **Harvest and preparation:** Pick fruit as it ripens. Berries of most species are excellent fresh, except for thimbleberries which have a rather dry taste and may require mixing with other berries. The berries are good with cream and sugar, in pancakes, on cereals, and in jams, jellies, and pies. To make berry bannock over campfire, mix 2 cups flour, 3 tsp double-acting baking powder, ½ tsp salt, 6 tbsp margarine or butter, and 4 tbsp powdered milk until uniformly mixed into mealy texture. Add 1 cup washed damp berries; mix gently to coat fruit. Add ⅓ cup water to make workable dough. Shape into 1-in-thick

Silver buffaloberry *Shepherdia argentea*

Also edible autumn

Habitat: riverbanks, low meadows, plains, canyons. **Identification:** spreading shrub or small tree to 5 m (16 ft) with dull gray bark shredding in long strips; ***branches*** stout, ***covered with silvery-white scales,*** usually ***thorny. Leaves opposite,*** simple, deciduous, 3–5 cm (1.2–2 in) long, 7–10 mm (0.3–0.4 in) wide, uniformly wide to widest near middle, entire, ***leathery, densely covered with silvery scales on both surfaces.*** Male and female flowers on separate trees; flowers small, inconspicuous, lacking petals. ***Fruits berrylike, rounded,*** 6–9 mm (0.2–0.4 in) long, smooth, ***bright red,*** slightly fleshy, enclosing single flattened seed. **Harvest:** late summer fruits pleasantly tart, better after frost has sweetened them. Shrub is frequently prolific fruit producer. Handpick or spread tarp beneath shrub and shake branches. **Preparation:** Use fruit fresh or dry thoroughly in sun. Use prefrost berries for jelly. Eat ripe fruit fresh or dried; add sugar as desired. Seeds are chewable. For beverage crush 1 cup fresh berries with 1 cup sugar in 3 cups hot water or mash 1 cup dried berries in 1 pt water. Add sugar to taste. Strain and drink. Cook berries with meat or prepare like CRANBERRY sauce for use with meat. For dessert mash fresh fruits and whip or blend into froth. Blend in sugar if needed. **Related edible species:** Canadian buffaloberry *(S. canadensis)* and silverberry *(Elaeagnus argentea)* are edible but less flavorful, and are improved by cooking and adding sugar. **Poisonous look-alikes:** none.

cake, dust with flour, place in warm, greased fry pan. Cook over moderate heat until crust forms on bottom. Turn over with spatula and cook until browned and no dough sticks to fork inserted into center of dough. Adapt other berry recipes from your favorite cookbooks. Tender growth tips of many species are edible, and leaves of many are good for tea. **Related edible species:** See above. **Poisonous look-alikes:** none.

Red raspberry *Rubus idaeus* var. *strigosus*
(synonym: *R. strigosus*)

Habitat: margins of woodlands, clearings, roadsides, abandoned fields. **Identification:** subshrub to 2 m (6.6 ft) high; ***branches*** spreading to trailing along ground, often with a whitish cast, ***armed with usually numerous prickles*** and stiff hairs. ***Leaves*** alternate, deciduous, compound on nonflowering canes, ***with*** *3–7* ***leaflets,*** each leaflet broadest near base, 2–10 cm (0.8–4 in) long, long-pointed at tip, coarsely and sharply toothed along margin, ***pale green to whitish and hairy beneath.*** Flowers white to greenish-white, 1.2–1.8 cm (0.5–0.7 in) across, produced June–July in small clusters of 2–5 flowers along upper part of canes. ***Fruits globe-shaped or nearly so, 1.2–2 cm*** (0.5–0.8 in) ***in diameter, bright red,*** juicy, ***separating easily from fruiting stalk and base,*** maturing from July–September. **Harvest and preparation:** See BRAMBLES (preceding).

Wineberry *Rubus phoenicolasius*

Habitat: introduced from Asia; grows wild in disturbed sites, along streams, rivers, roads, especially in coastal eastern U.S. **Identification:** shrub to 2.5 m (8 ft) high; ***branches*** spreading, often arching over, ***lacking spines but with dense, red, gland-tipped hairs. Leaves*** alternate, deciduous, ***3-parted*** (trifoliolate), ***broadest near base and often as broad as long, 4–10 cm (1.6–4 in) long and wide,*** often lobed, toothed. ***Flowers white,*** produced in elongate, many-flowered clusters; ***each 2–3 cm (0.8–1.2 in) across (including calyx lobes), petals shorter than the narrow, pointed, calyx lobes. Fruits globe-shaped, 0.8–1.2 cm (0.3–0.5 in) in diameter, bright red*** at maturity, juicy, maturing from midsummer to early autumn. **Harvest and preparation:** See BRAMBLES (preceding).

Thimbleberry *Rubus parviflorus*

Habitat: widespread from sea level to mountains; woodlands, canyons, open areas, along roads, trails, streams. **Identification:** shrub to 2 m (6.6 ft) high with ***upright to spreading branches, without spines*** but with glandular hairs. ***Leaves*** alternate, deciduous, ***simple, 5-lobed, 5–15 cm (2–6 in) long and wide,*** sharply toothed along margin. ***Flowers*** large, ***white to pink, 2–5 cm (0.8–2 in) across,*** produced in loose, 2–9-flowered, spreading clusters. ***Fruits large,*** globe-shaped, *1.2–1.8 cm* ***(0.5–0.7 in) across, bright red to scarlet,*** sweet, juicy, maturing throughout season. **Harvest and preparation:** See BRAMBLES (preceding).



Red raspberry: fruiting branch (Elias).



Wineberry: fruiting branch (Elias).

Thimbleberry: fruiting branch (McNeal).




Eye
Eye
Pharynx
Mouth
Teeth
Jaw
Ear
Ear
Pineal Gland
Pituitary Gland
Medulla
Cerebellum
Neck-
Throat
Parathyroid
Gland
Pancreas
Stomach
Thyroid
Gland
Spleen
Bronchial
Tubes
Lungs
Heart
Kidney
Descending
Colon
Diaphragm
Ureters
Sigmoid
Flexure
Sciatic
Nerve
Rectum
Prostate/
Uterus

Fig. 4 *Fingers and Their Corresponding Bodily Functions Through the Organs' Meridians*



Common blackberry: mature fruits (Elias).

Black raspberry: fruiting branch (Elias). Flowering branch (Dykeman).



Common blackberry *Rubus allegheniensis*

Habitat: margins of woodlands, old fields, fencerows; also roadsides, thickets, mountain slopes. **Identification:** shrub, sometimes to 3 m (9.8 ft), branches upright to spreading, sometimes trailing, with scattered straight spines. ***Leaves*** alternate, deciduous, palmately compound, ***usually with 5 leaflets,*** sometimes 3, variable, typically broadest near or just below middle, long-pointed at tip, usually 10–18 cm (4–7 in) long, with numerous sharp-pointed teeth along margin, ***pale green beneath. Flowers white,*** 1.7–2.5 cm (0.7–1 in) across, produced in May, June, or early July (usually about 2–3 weeks later than black raspberry) ***in elongated 6–15-flowered clusters. Fruits globe- to short cylinder-shaped, to 2 cm (0.8 in) long,*** juicy, sweet, black at maturity; maturing in late July or August. **Harvest and preparation:** See BRAMBLES (preceding).

Black raspberry *Rubus occidentalis*

Habitat: disturbed areas, especially margins of woodlands, ravines, fields, thickets; sometimes in full shade. **Identification:** shrub with upright to spreading ***branches, sometimes arching to ground; stems with scattered, straight or curved, stout spines. Leaves*** alternate, deciduous, compound, each leaf ***with 3–5 leaflets,*** terminal leaflets broadest near base, pointed at tip, sharp and irregularly toothed along margin; lateral leaflets smaller, ***whitish beneath.*** Flowers white, produced in May or June in 3- to 7-flowered nearly flat clusters. ***Fruits purplish-black to black, 0.8–1.2 cm (0.3–0.5 in) across,*** rounded or nearly so, ***easily separated as a unit*** from fruiting stalk and base, juicy, sweet, maturing in June or July. **Harvest and preparation:** See BRAMBLES (preceding).



California blackberry: fruits (Ross).

Smooth sumac: fruiting branch (Dykeman). Fruits (Elias).



California blackberry *Rubus ursinus*

Habitat: disturbed sites, along trails, roads, canyons, fields, open woodlands; common at lower elevations, below 1,000 (3,200 ft). **Identification:** ***shrub, often low; branches spreading to trailing along ground;*** armed with slender, slightly flattened spines. ***Leaves*** alternate, deciduous, ***usually 3-parted (trifoliolate),*** sometimes simple; ***leaflets broadest near base, 6–12 cm (2.4–4.7 in) long, 4–10 cm (1.6–4 in) wide,*** coarsely toothed, occasionally shallowly lobed. Flowers white, produced in elongate, loose, 3–12-flowered clusters; each 1–3 cm (0.4–1.2 in) across. ***Fruits short cylinder-shaped to nearly cone-shaped, 1–2 cm (0.4–0.8 in) long, black at maturity,*** juicy, sweet. **Harvest and preparation:** See BRAMBLES (preceding).

Smooth sumac *Rhus glabra*

Also edible autumn

Habitat: common and widespread; abandoned farmlands, fields, margins of woodlands, along streams. **Identification:** shrub or small ***tree*** to 7 m (23 ft) ***with smooth stout branches*** and open rounded crown. ***Leaves*** alternate, deciduous, ***featherlike (pinnate) compound, with 11–31 leaflets,*** leaflets usually lance-shaped, 5–9.5 cm (2–3.7 in) long, 1.2–3 cm (0.5–1.2 in) wide, long pointed at tip, sharply toothed along margin, dark shiny green above, whitish beneath. Male and female flowers on different plants, produced in dense, cone-shaped clusters 10–25 cm (4–10 in) long. ***Fruits produced in autumn in large cone-shaped clusters, each fruit berrylike, rounded, 3–5 mm (0.1–0.2 in) in diameter, dark red, fuzzy.*** **Harvest:** Pick fruit clusters when glazelike bloom appears on bright red berries. Lick like lollipop for delicious lemony thirst quencher. Flavor is washed out by rains more quickly than in STAGHORN SUMAC. **Preparation:** same as STAGHORN SUMAC. Make delicious jelly from 2 cups sumac extract (see beverage under STAGHORN SUMAC) and 2 cups elderberry juice. Boil juice and extract with 1 pkg powdered pectin. Add 5 cups sugar. Bring to hard boil, boil 1 min, remove from heat, skim, pour into jars, seal. For other recipes, see SQUAWBUSH and STAGHORN SUMAC (next). See *caution* under STAGHORN SUMAC. **Related edible species:** STAGHORN SUMAC, SQUAWBUSH, plus lemonade sumac *(R. integrifolia)* of southern California and sugar bush *(R. ovata)* of the Southwest. **Poisonous look-alikes:** Poison sumac *(Toxicodendron vernix)* grows in wet areas and has white fruits. Avoid white fruited sumacs. POISON IVY and poison oak *(T. diversiloba)* are in the sumac genus.

Squawbush *Rhus trilobata*

Also edible autumn

Habitat: foothills, canyons, slopes, washes, often in dry rocky soils. **Identification:** ***shrub*** to 2 m (6.6 ft) with numerous spreading branches and ***densely hairy twigs, with strong odor when broken. Leaves*** alternate, deciduous, ***with 3 leaflets*** (trifoliolate), occasionally 1 leaflet, leaflets broadest near base or tip, 1–3 cm (0.4–1.2 in) long, nearly as wide, ***with large rounded teeth along margin,*** rounded at tip, hairy. Flowers yellow, small, densely clustered in short spikes in spring. ***Fruits berrylike, rounded, 4–6 mm (0.2 in) in diameter, red, hairy, sticky.*** **Harvest:** Gather fruits from end of August. **Preparation:** Suck on fresh fruits for refreshing sour taste. For beverage and jelly see SMOOTH SUMAC (preceding) and STAGHORN SUMAC (next). For syrup combine ½ cup dried, ground, sifted berries with 1⅓ cups water and ¾ cup honey (or 1 cup sugar). Cover, boil mix 30 sec, reduce heat, simmer 15 min. Uncover and boil until mix thickens, stirring constantly. Pour into jar and refrigerate for further thickening. Good dessert topping or spread on bread. If fresh berries are used, crush, simmer, and strain before adding honey or sugar. Then boil and complete process as above. See *caution* under STAGHORN SUMAC. **Related edible species:** See SMOOTH SUMAC. **Poisonous look-alikes:** Leaves resemble those of poison oak *(R. diversiloba)* and POISON IVY, both with white fruits. See also SMOOTH SUMAC.

Staghorn sumac *Rhus typhina*

Also edible autumn, winter

Habitat: woodland margins, fencerows, roadsides, old fields, streambanks. **Identification:** shrub or small ***tree*** to 10 m (33 ft) ***with thick densely hairy branches and twigs.*** Leaves alternate, deciduous, featherlike (pinnate) compound, 40–60 cm (16–24 in) long, with 11–31 leaflets, leaflets usually lance-shaped, 5–12 cm (2–4.7 in) long, 2–4 cm (0.8–1.6 in) wide, sharply toothed along margin. Male and female flowers on same or separate trees, produced in crowded cone-shaped clusters. ***Fruits produced in dense, cone-shaped clusters 10–20 cm (4–8 in) long; each fruit berrylike, rounded, 3–5 mm (0.1–0.2 in) in diameter, densely covered with dark red hairs.*** **Harvest:** Pick fruit clusters late summer to autumn when deep red and fruits have developed strong lemony taste. Dense hairs on fruits prevent rain from penetrating cluster and washing out all malic acid flavor so fruits are usable though less potent through winter. Dry some clusters for winter use. **Preparation:** For beverage separate fruits from twigs. Steep in near boiling water (no less than 1 cup fruits to 1 qt water) for at least 15 min. Strain through cloth, dilute, sweeten to taste. Drink hot or cold but in moderation; some people show allergic reaction. Using whole heads of fruits will include small arthropods within them, and twigs may add slight bitterness. See other uses under SMOOTH SUMAC and SQUAWBUSH (preceding). **Related edible species:** SMOOTH SUMAC and SQUAWBUSH, and lemonade berry *(R. integrifolia)*. **Poisonous look-alikes:** See SMOOTH SUMAC.



Squawbush: fruiting branch (Dykeman).

Staghorn sumac: fruiting branch, left (Dykeman). Fruits (Elias).





Screwbean mesquite: fruiting branch (Feldman).

Glandular mesquite: fruiting tree (Feldman). September branches (Hutchins).



Screwbean mesquite *Prosopis pubescens*

Also edible autumn

Habitat: gullies, washes, stream banks, riverbottoms, floodplains. **Identification:** shrub or ***small spreading tree*** to 10 m (33 ft) with slender ***branches armed with pair of sharp spines at each leaf base. Leaves*** alternate, deciduous, ***twice compound and featherlike*** (bipinnate), with 1 or 2 pairs of side branches (pinnae), each 3.8–5 cm (1.5–2 in) long, composed of 5–8 pairs of small leaflets. Flowers produced in densely flowered cylinder-shaped spikes 5–7.5 cm (2–3 in) long, each flower greenish-white to yellow, 3–4 mm (0.2 in) long. ***Fruits*** are ***spiral twisted pods 3–5 cm*** (1.2–2 in) ***long,*** brown, hairy, becoming hard and tough at maturity. **Harvest:** Gather and clean immature pods, the younger the tenderer. **Preparation:** Boil until soft or cook with other vegetables. The pods can be boiled down to make a sweet syrup with many uses. **Related edible species:** GLANDULAR MESQUITE (next) and mesquite *(P. veluntina)*. **Poisonous look-alikes:** slightly similar to CORALBEAN, which has poisonous seeds.

Glandular mesquite *Prosopis glandulosa*

Also edible autumn

Habitat: desert valleys, open range, grazing lands where plant becomes a pest. **Identification:** shrub or small spreading tree to 8 m (26 ft) with slender ***branches*** that ***have paired, sharp-pointed spines where each leaf is attached. Leaves*** alternate, deciduous, ***twice compound and featherlike*** (bipinnate), with 1 pair of side branches (pinnae), each 12–20 cm (4.7–8 in) long and composed of 7–18 pairs of leaflets. Flowers produced from May to August in densely flowered, narrow, cylinder-shaped clusters; each flower yellow, 3–4 mm (0.2 in) long. ***Fruits long, narrow, straight pods 10–25 cm*** (4–10 in) ***long,*** rounded, slightly constricted between seeds. **Harvest:** Gather flower clusters as they open and fruits as they ripen during summer. **Preparation:** Suck sugar-rich nectar from newly open flowers. The yellowish gelatinous to mealy pulp surrounding seeds in mature pods contains up to 30% sugar and can be eaten fresh. Make beverage by boiling clean pods in fresh water and straining off residue. Dry pods, grind, mix with little water to form dry, mealy dough; bake in sun for several hours or over very low heat. Soak seeds in water several hours for lemon-flavored drink or grind dry seeds into meal and use to make porridge. Discard those seeds infested with larvae of bean beetle. **Related edible species:** SCREWBEAN MESQUITE (preceding) and mesquite *(P. veluntina)*. **Poisonous look-alikes:** may resemble CORALBEAN, which has toxic seeds.

American elder, Common elder *(Also edible spring)* *Sambucus canadensis*

Habitat: rich moist soil of woodland margins, stream and river banks, fencerows and right-of-ways. **Identification:** mainly shrubby, 1–4 m (3–13 ft), with upright to spreading branches and broad rounded crown. ***Leaves opposite,*** deciduous, featherlike (pinnate) ***compound,*** 15–25 cm (6–10 in) long, composed of *5–11 **leaflets,*** each leaflet broadest near base to uniformly wide, 6–12 cm (2.4–4.7 in) long, 2–4 cm (0.8–1.6 in) wide, pointed, toothed, dark shiny green. ***Twigs*** with prominent ***white pith. Flowers*** white, small, in branched, ***round or flat-topped showy clusters*** in late spring or early summer. ***Fruits berrylike,*** rounded, 4–6 mm (0.2 in), ***deep purple,*** juicy, 3-seeded, in large clusters, maturing in mid to late summer. **Harvest:** When flowers are fully open, pick whole clusters or shake petals of old flowers into container. When fruit is deep purple, pick whole clusters or strip berries from bush. **Preparation:** Dip flower cluster in fritter batter and deep fry; dust with sugar and sprinkle with orange juice. Add cup of blossoms to pancake batter. Extract juice from fresh fruit by simmering mix of 1 cup water per 1 qt mashed berries 20–25 min; strain through cloth. Sweetened juice good with tart juices. Use juice with (STAGHORN SUMAC) extract in jelly. Fresh fruit has rank flavor; improves with drying; use dried fruit for pies and breads. Dry fruit in sun or warm attic; before using stew in little water. Flowers and fruit excellent for wine. Fruits high in vitamin C. *Warning:* Roots, stems, leaves, unripe fruits are somewhat toxic. **Related edible species:** BLUE ELDER (next). **Poisonous look-alikes:** See BLUE ELDER.

Blue elder *(Also edible spring)* *Sambucus cerulea*

Habitat: stream banks, gullies, washes, margins of fields, woodlands, pastures. **Identification:** shrub or small tree with broad rounded crown. Leaves ***opposite,*** deciduous, featherlike (pinnate) ***compound,*** 12–18 cm (4.7–7.1 in) long, composed of *5–9 **leaflets,*** leaflets broadest at middle to uniformly wide, 5–15 cm (2–6 in) long, 1.2–5 cm (0.5–2 in) wide, long-pointed at tip, coarsely-toothed, bright green above. ***Flowers*** tiny, yellowish-white, produced in spreading, ***many-flowered, flat-topped clusters*** in late spring or early summer. ***Fruits*** in clusters, each ***berrylike,*** rounded, 6–10 mm (0.2–0.4 in), ***dark blue to nearly black,*** juicy, maturing in mid to late summer. **Harvest:** Flowers in early summer, fruits in late summer, can be eaten raw or dried like raisins. **Preparation:** Prepare tea from blossoms. For jelly, wash berries, partially crush, cover with water, cook over low heat 10 min. Pour contents into wet jelly bag and collect juice; do not squeeze bag. Add 2 cups elderberry juice to 3 cups apple juice prepared in similar manner. Heat to boil, add 1 pkg pectin; stir until dissolved. Bring to rapid boil, add 6 cups sugar. Stir until rolling boil cannot be stirred down; continue for 1 min. Pour mix into prepared jelly jars; cover with ¼ in paraffin; seal with lid. For other uses see AMERICAN ELDER (preceding). **Related edible species:** AMERICAN ELDER, Mexican elder *(S. mexicana),* and black berried elder *(S. melanocarpa).* **Poisonous look-alikes:** Red fruited elder *(S. pubens)* of East and Midwest somewhat toxic. Pacific elder *(S. callicarpa)* bitter but not poisonous.



American elder: fruiting branches (Elias). Flowers (NYBG).

Blue elder: fruiting bush and fruits (Kavasch).



Massage the Hands

Always start by rubbing your hands until they are warm.

1. Massage the pericardium (P-8). Use the thumb to press the middle of the palm with a circular motion.





Fig. 5 *Massaging the Pericardium with fingers cupped in the palm in a half-fist, the pericardium is the point at the tip of the middle finger.*



Singleleaf pinyon pine: branch with immature cone (Dykeman).



Sugar pine: branches with cones (McNeal).

Digger pine: leader and cones (McNeal).



Singleleaf pinyon pine *Pinus monophylla*

Habitat: lower mountain slopes, foothills, canyons from 650–2,350 m (2,100–7,800 ft) elevation; often growing with junipers. **Identification:** small, spreading tree with rough, irregularly furrowed, dark brown bark. ***Leaves (needles) 1 per sheath, 2.5–5 cm (1–2 in) long, sharp-pointed, stiff, often curved toward branches,*** yellowish-green to gray-green; only native North American pine with single leaves. Fruits hard, egg-shaped cones 5–7.6 cm (2–3 in) long, composed of thick, stiff, light brown, blunt scales, each scale bearing 2 large, ***egg-shaped, brown, wingless seeds 1.8–2 cm*** (0.7–0.8 in) ***long.*** Trees produce moderate to large cone crops every 2–3 yr. Each cone requires 2 growing seasons to mature. **Harvest and preparation:** Gather second year cones in August or September. Oily seeds, rich in protein and oils, have nutty taste and can be eaten fresh. Thin shell can be cracked with teeth. Roast nearly ripe cones to facilitate seed removal and improve flavor. Store cones or seeds for later use, especially after roasting. Several cones tossed into campfire coals 10–20 min yield an excellent snack. Carry roasted cones or seeds in backpack for trail snack. If large numbers of seeds are available, roast and grind into meal and use in breads, soups, or mixed with cornmeal or flour. **Related edible species:** SUGAR PINE, DIGGER PINE, PINYON PINE, Mexican pinyon pine *(P. cembroides).* **Poisonous look-alikes:** none.

Sugar pine *Pinus lambertiana*

Habitat: mountain slopes from 750–3,000 m (2,500–9,850 ft) elevation. **Identification:** tall trees to 65 m (213 ft) with tall, straight trunk and thick, deeply, irregularly furrowed, dark, reddish-brown to purplish-brown bark. ***Leaves*** (needles) ***5 per sheath, 8.8–10 cm*** (3.5–4 cm) ***long, stout, stiff, deep bluish-green and marked with silvery lines. Fruits large woody cones, 27–46 cm*** (10.6–18 in) ***long,*** to 12 cm (4.7 in) in diameter; seeds nearly egg-shaped to football-shaped, 1.2–1.5 cm (0.5–0.6 in) long, dark chocolate-brown, nearly black, winged. **Harvest:** See SINGLELEAF PINYON PINE (preceding). *Note:* Cones with seeds are difficult to obtain because of height of the trees. **Preparation:** same as for SINGLELEAF PINYON PINE. **Related edible species:** Coulter pine *(P. coulteri),* DIGGER PINE (next), and the PINYON PINES. **Poisonous look-alikes:** none.

Digger pine *Pinus sabiniana*

Habitat: foothills, lower mountain slopes from 20–1,000 m (66–3,300 ft) elevation, often found with BLUE OAK. **Identification:** medium-size spreading tree to 15 m (50 ft) with short, thick trunk, soon branching, with irregular, scaly, dark brown to almost black bark. ***Leaves*** (needles) ***3 per sheath, 17–43 cm*** (6.7–17 in) ***long, slender, flexible, dull blue-green. Fruits large 15–25 cm*** (6–10 in) ***long,*** to 18 cm (7 in) broad, light reddish-brown, ***scales thick, each armed with clawlike spine;*** seeds 1.7–2 cm (0.7–0.8 in) long, egg-shaped, with hard, dark brown to almost black shell. **Harvest and preparation:** same as for SINGLELEAF PINYON PINE. **Related edible species:** PINYON PINES, Coulter pine *(P. coulteri),* SUGAR PINE (preceding). **Poisonous look-alikes:** none.

JUNIPER GENUS *Juniperus*

The 13 species of junipers native to North America are mostly common widespread trees and shrubs. These evergreen conifers are more abundant in the drier western states, although eastern redcedar and southern redcedar are prevalent in the eastern U.S. All junipers provide excellent cover for small game and food for many birds. Only three species, all western, are recommended for their edible fruits and then primarily as a survival food. The stems, leaves, and fruits contain varying amounts of resins which affect fragrance and taste.

Rocky Mountain juniper *Juniperus scopulorum*

Also edible autumn, winter

Habitat: bluffs, ridges, cliffs, dry rocky hillsides from sea level to 3,000 m (9,850 ft) elevation. **Identification:** large evergreen shrub or small tree to 15 m (49 ft) with reddish-brown to gray scaly bark separating in long narrow strips. ***Leaves tiny, scalelike, opposite each other,*** closely pressed against branchlets, 2–4 mm (0.1 in) long with tiny gland on back, ***pale green to grayish green,*** resinous. Male and female flowers on separate trees in spring, inconspicuous and easily overlooked. ***Fruits small, fleshy, sweet, berrylike cones, nearly rounded, 6–9 mm*** (0.2–4 in) ***in diameter, bright blue, maturing in 2 seasons,*** containing 1–2 seeds. **Harvest:** Gather ripe berries from summer to early winter. Use fresh or dry and store for later use. **Preparation:** Although high in sugars, ripe fruits have an unpleasant resinous taste, so fresh fruits become strictly survival fare. Use a few fresh berries as substitute for sage in flavoring meats. Roast dried fruits, grind, and use as coffee substitute. **Related edible species:** UTAH JUNIPER and CALIFORNIA JUNIPER (next). **Poisonous look-alikes:** Take care in identification of junipers. Fruits of most species have such high resin content that they are unpalatable or may cause stomach upset.

California juniper *Juniperus californica*

Also edible autumn, winter

Habitat: dry slopes, canyons, desert slopes from 125–1,350 m (410–4,500 ft) elevation. **Identification:** large shrub or small tree with fluted and ridged trunk and reddish-brown to ash-gray bark that splits into long, loose, shredding strips. ***Leaves tiny, scalelike, arranged in 3s,*** overlapping and closely pressed against branchlets, 2–4 mm (0.1 in) long, with tiny gland on back, light yellowish-green. Male and female flowers on separate trees in spring, inconspicuous and easily overlooked. ***Fruits*** are ***leathery, berrylike cones, almost rounded, 10–16 mm*** (0.4–0.6 in) ***in diameter, dry, sweet, not resinous, light reddish-brown,*** maturing in 2 seasons, each containing 1–3 seeds. **Harvest and preparation:** same as for ROCKY MOUNTAIN JUNIPER (preceding) except that nonresinous fruits are superior to those of other junipers as wild food source. **Related edible species:** UTAH JUNIPER (next), ROCKY MOUNTAIN JUNIPER. **Poisonous look-alikes:** same as for ROCKY MOUNTAIN JUNIPER.



Rocky mountain juniper: fruiting branch (Dykeman).

California juniper: fruiting branch (Webber, Jepson Herbarium).





Utah juniper: fruiting branch (Pawloski).

Sea grape: fruiting and flowering branches (Elias).



Utah juniper *Juniperus osteosperma*

Also edible autumn, winter (synonym: *J. utahensis*)

Habitat: mesas, mountain slopes, high plains, principally from 1,000–2,650 m (3,300–8,700 ft) elevation in dry rocky or gravelly soils. **Identification:** large ***shrub*** or small ***bushy tree*** to 8 m (26 ft) high with ***furrowed ash-gray bark that shreds in long, loosely attached strips. Leaves*** tiny, ***scalelike, opposite and overlapping one another in 2s, closely pressed against branchlets,*** 3–4 mm (0.1–0.2 in) long, usually gland-dotted on back, ***sharp-pointed at tip, yellowish-green.*** Male and female flowering cones usually produced in spring on separate trees, inconspicuous and usually overlooked. ***Fruits small, leathery berries*** ***6–9 mm*** (0.2–0.4 in) ***in diameter, nearly globe-shaped, reddish-brown, resinous, sweet,*** with mealy texture, containing 1, rarely 2, seeds. **Harvest and preparation:** same as for ROCKY MOUNTAIN JUNIPER. **Related edible species:** CALIFORNIA JUNIPER and ROCKY MOUNTAIN JUNIPER (preceding). **Poisonous look-alikes:** same as for ROCKY MOUNTAIN JUNIPER.

Sea grape *Coccoloba uvifera*

Habitat: beaches, along sea shores; Southern Florida, Bermuda, Bahama Islands, the West Indies. **Identification:** very distinctive large shrub or tree to 15 m (50 ft) with compact rounded crown, trunk short, covered with pale blotchy bark. ***Leaves*** alternate, simple, ***persistent and appearing evergreen, 10–27 cm*** (4–10.6 in) ***long, 12–25 cm*** (4.7–10 in) ***wide, almost circular in outline,*** rounded at tip, entire, heart-shaped at base, ***thick, leathery,*** dark shiny green above. Flowering clusters produced along narrow, elongate stalks to 30 cm (12 in) long. ***Fruits crowded together in long, hanging clusters,*** each fruit nearly rounded, 1.8–2.5 cm (0.7–1 in) long, greenish-white to purple, with thin, juicy flesh; seed hard, nutlike. **Harvest:** Since fruits do not ripen uniformly, spread sheet under bush and shake branches vigorously. Ripe fruits will fall while green ones persist in cluster. **Preparation:** best used for jelly. Partially crush 2 qt clean ripe fruits with ½ cup water and cook for 20 min. Strain juice through jelly bag. Boil juice with equal amount of sugar until jelling point is reached. Skim off foam, pour into sterilized jars, seal with paraffin. **Related edible species:** dove plum *(C. diversifolia)* of coastal southeastern Florida, but not a recommended substitute for sea grape. **Poisonous look-alikes:** none.

California laurel, California bay *Umbellularia californica*

Also edible autumn, spring

Habitat: lower mountain slopes, hillsides, flatlands, in variety of soils; Pacific coastal regions and western slopes of Sierra Nevada. **Identification:** small to medium-size tree to 20 m (66 ft) with thin, dark brown bark. ***Leaves*** alternate, simple, ***evergreen,*** 8.6–13 cm (3.4–5.1 in) long, lance-shaped to broadest near middle, usually pointed at tip, ***entire, dark green and shiny, leathery, with spicy odor when crushed.*** Flowering clusters flat-topped, containing 4–9 flowers, each small, 1–1.4 cm (0.4–0.6 in) across, yellow. ***Fruits resembling an olive,*** globe-shaped to broadest near base, ***2–2.6 cm*** (0.8–1 in) ***long,*** slightly fleshy, green turning yellowish-green or purplish-green at maturity, containing single large seed. **Harvest:** Pick young unblemished leaves, wash and leave in sun until thoroughly dry. Store in cool dry place for later use. Pick ripe fruits in late summer or autumn, remove and clean seeds. **Preparation:** Use dried leaves as substitute for bay leaves. California laurel is more potent, so cut recipe amount by ⅓ unless stronger flavoring is desired. Good in stews, chili, spaghetti sauce, soups. Roast seeds in campfire, split open, and eat or grind into flour for bread and other recipes. Indians of California used leaves in lodges to repel fleas. **Related edible species:** none. **Poisonous look-alikes:** none.

Pawpaw, Papaw *Asimina triloba*

Also edible autumn

Habitat: river valleys and bottomlands, usually in deep, rich, moist soils; grows in association with sweetgum, swamp chestnut, black gum, cherrybark oak. **Identification:** large shrub or small tree with thin, smooth bark (dark brown with gray blotches) 3–12 m (10–40 ft) tall. Leaves alternate, deciduous, simple, 18–30 cm (7–12 in) long, 8–14 cm (3.2–5.5 in) wide, usually broadest near tip, entire along margin, papery textured, light green. Flowers ***green turning deep purple, produced in spring along stems of previous year, bell-shaped,*** with 3 sepals, 6 thick, almost rounded petals 2–2.6 cm (0.8–1 in) long. Fruits irregular, cylinder-shaped, 4–10 cm (1.6–4 in) long, aromatic, green turning yellow then black and fleshy at maturity; mature in late summer or early autumn. **Harvest:** when fruits mature or while still green but full size; store in cool place (safe from small animals) until ripe. **Preparation:** Tasty sweet pulp of fruit can be eaten raw. Cook creamy, custardlike pulp, minus seeds and skin, and use in puddings, breads, ice cream. *Caution:* Fruits disagree with some people. **Related edible species:** dwarf pawpaw *(A. parviflora)*. **Poisonous look-alikes:** none.



California laurel: flower and fruiting branch (U. of Cal., Davis).

Pawpaw: flowering branch (Folkerts). Fruiting branch (Elias).



White mulberry *(Also edible spring)* *Morus alba*

Habitat: introduced and cultivated tree that now grows wild along fencerows, roadsides, margins of abandoned fields, and in woodlands. **Identification:** medium-size tree with widespreading, rounded crown and thick, irregularly furrowed, light to dark gray to yellowish-brown bark and ***milky sap. Leaves*** alternate, deciduous, simple, ***6–16 cm (2.4–6.3 in) long, 3–8 cm (1.2–3.2 in) wide, broadest near base,*** pointed at tip, ***unlobed or 2–3 lobed, sharply toothed along margin.*** Male flowers tiny, clustered on short spikes; female flowers tiny, clustered in round heads, both appearing in spring on new growth. ***Fruits globe-shaped to short cylindrical, 1–2 cm (0.4–0.8 in) long, blackberrylike, fleshy, white to pinkish at maturity*** (June–July). **Harvest and preparation:** Pick fruits as they ripen from late May through July. Fully ripe berries may be shaken from tree onto plastic sheets but tend to be very syrupy and too sweet for most palates. Dry like raisins for breads, cookies, and puddings. Use plastic or aluminum screen supported so air can reach all sides of fruit. If solar drying, protect from dew condensation at night. Dry until crushed fruit lacks any watery juice. Drying time: bright sun, 2 days; warm attic, 4 days; warm oven, 10–15 hr. Store dried berries in sealed containers. Afghans grind dried fruit with almonds for nutritious combination. Substitute any other type of nut, roll small balls of ground mix in confectioner's sugar, eat as candy. Pick shoots and prepare as RED MULBERRY (next). **Related edible species:** RED MULBERRY, Texas mulberry *(M. microphylla),* black mulberry *(M. nigra).* **Poisonous look-alikes:** none; see RED MULBERRY caution.

Red mulberry *(Also edible spring)* *Morus rubra*

Habitat: river valleys, floodplains, lower slopes of hills, usually in rich, moist soils. **Identification:** small to medium-size tree with broad, rounded crown and irregularly fissured, dark reddish-brown bark and ***milky sap. Leaves*** alternate, deciduous, simple, ***7.5–10 cm (3–4 in) long, 5–5.8 cm (2–2.3 in) wide, broadest near base to almost rounded, unlobed or 1–3-lobed, heart-shaped at base, pointed at tip, with coarse teeth along margin, with whitish hairs on lower surface.*** Male flowers tiny, crowded together in slender, hanging clusters; female flowers tiny, crowded in broader, elongated clusters. ***Fruits cylinder-shaped, blackberrylike, 2.2–3 cm*** (1–1.2 in) ***long, fleshy, red turning dark purple to almost black, sweet,*** maturing from May to July. **Harvest and preparation:** Pick ripe fruit from ladder, or spread tarps beneath tree and shake limbs. Delicious as picked or with cream. Do not let persistent small stem and axis of fruit bother you. For beverage mash and squeeze fruit through cheesecloth or use electric juicer or blender. Add sweetener and lemon juice to taste. Serve with ice and, if desired, club soda. Also good for pies, jams, jellies. Use like other berries in breads, muffins, cakes. Pick shoots as leaves are beginning to unfold. Boil 20 min, drain, add butter and seasoning. *Caution:* Raw shoots and unripe fruits contain hallucinogens. **Related edible species:** WHITE MULBERRY (preceding), Texas mulberry *(M. microphylla),* black mulberry *(M. nigra).* **Poisonous look-alikes:** none.


Introduced and grows wild. Widespread.

White mulberry: flowering branch (NYBG). Fruiting branch (Elias).

Red mulberry: fruiting branch (Elias).



2. Massage the hegu (LI-14). Press the thumb around the point in a circular motion, and press more at the index finger bone. Find the pain point and massage it away.


Large Intestine Point (LI-14)

Fig.6 *Massaging LI-14*



American plum: flowering branch (Weber). Fruiting branch (Elias).

Flatwood plum: flowering and fruiting branches (Anderson).



American plum, Wild plum *Prunus americana*

Habitat: common, mixed deciduous woodlands, along streams, fencerows, margins of fields. **Identification:** shrub or small tree to 11 m (36 ft) with spreading crown and ***spiny*** branches. ***Leaves*** alternate, simple, deciduous, ***6–10 cm*** (2.4–4 in) ***long, 3.5–4.5 cm*** (1.4–1.8 in) ***wide, with double row of sharp pointed teeth along margin,*** dark green and smooth. ***Flowers produced 2–5 per cluster*** in early spring, like cherry blossoms, each with 5 rounded, ***white*** petals 9–12 mm (0.4–0.5 in) long. ***Fruits*** solitary or 2–4 per cluster, each ***rounded or nearly so, 1.8–2.5 cm*** (0.7–1 in) ***in diameter, orange to red,*** juicy. **Harvest:** ripe fruits in mid to late summer. **Preparation:** Boil unripe fruits with sugar for emergency food. Use fresh ripe fruits in any cultivated plum recipes. Especially good in jams and jellies. For plum butter, puree pulp and skins after extracting juice for jelly. Blend with equal amount of maple sugar or honey in crock or bean pot and bake at 165°C (330°F) for 3 hr with occasional stirring. Seal in hot, sterilized jars. For jam add ½ cup water to each 2 cups raw pitted fruit. Boil until skins are tender, 10–15 min. Add 1 cup sugar for each cup of fruit pulp. Mix and cook about 15 min to jelly stage with constant stirring. Pour into sterilized jars and seal. For pie, use plums with equal volume of sweeter fruit such as peaches and use basic pie recipe. **Related edible species:** several throughout the country, including BEACH PLUM, FLATWOOD PLUM (next), and cherries. **Poisonous look-alikes:** none. Pits and seeds contain hydrocyanic acid which can react with stomach acids to release highly poisonous cyanin.

Flatwood plum *Prunus umbellata*

Habitat: coastal plain, piedmont; along rivers, in swamps and hammocks. **Identification:** small tree to 6 m (20 ft) with irregular rounded crown and reddish bark. ***Leaves*** alternate, simple, deciduous, ***5–7 cm (2–2.8 in) long, 2.5–4 cm (1–1.6 in) wide, broadest at or above middle,*** rounded to slightly heart-shaped at base, ***with fine, sharp-pointed teeth along margin,*** dark green and smooth. ***Flowers 2–4 per cluster*** in early spring before leaves appear, each with 5 ***white*** rounded petals. ***Fruits*** solitary or in small clusters, ***rounded, 1.2–1.5 cm*** (0.5 in) ***in diameter, dark red to almost black,*** sour, containing flattened stone. **Harvest:** Handpick fruits as they mature from June to September. **Preparation:** See AMERICAN PLUM (preceding), but use additional sugar as with BEACH PLUM. **Related edible species:** BEACH PLUM, AMERICAN PLUM, and several other species. **Poisonous look-alikes:** none.

Black cherry *Prunus serotina*

Habitat: widely distributed; mixed hardwood forests, woodlands. **Identification:** tree to usually 20 m (66 ft), rarely taller, with rounded crown and dark reddish-brown to nearly black bark; inner bark with odor of almond extract. ***Leaves*** alternate, simple, deciduous, 5–15 cm (2–6 in) long, 2.5–4 cm (1–1.6 in) wide, narrow but widest near base to uniformly wide, ***with numerous blunt teeth along margin,*** dark green and shiny. ***Flowers and fruits produced in narrow elongated clusters 10–15 cm*** (4–6 in) ***long,*** each flower with 5 white rounded petals. ***Fruits fleshy, rounded, 8–10 mm*** (0.3–0.4 in) ***in diameter, dark red to black at maturity*** (late summer), juicy, enclosing egg-shaped stone, slightly bitter tasting. **Harvest:** Handpick fruit or if fully ripe shake loose onto tarp August through September. **Preparation:** Eat fresh as trail snack or with sugar and cream as dessert, though pits make eating an effort. Prepare jelly as described under COMMON CHOKECHERRY (next) but use 2 cups each of apple and cherry juice. Also use black cherries for brandied cherries, breads, beverages, pies, wine. For pie add 1½ cups sugar, 2 tbsp cornstarch or flour, and ¼ tsp salt to 1 qt pitted cherries (a pitter makes the task easier). Mix and pour into uncooked 9-in piecrust. Add top crust or lattice of pastry. Bake at 230°C (450°F) for 20 min, then reduce heat to 190°C (375°F) and bake 10 more min. Indians prepared and used dried black cherries as described under COMMON CHOKECHERRY. **Related edible species:** See COMMON CHOKECHERRY. **Poisonous look-alikes:** See COMMON CHOKECHERRY for details.

Common chokecherry *(Also edible autumn)* *Prunus virginiana*

Habitat: common and widespread; moist soils of roadsides, fencerows, woodland margins. **Identification:** shrub or small tree to 8 m (26 ft) with smooth usually reddish-brown bark. ***Leaves*** alternate, simple, deciduous, 5–10 cm (2–4 in) long, 2.5–5 cm (1–2 in) wide, uniformly wide to broadest near base, pointed at tip, ***with numerous sharp teeth along margin,*** dark green and smooth. ***Flowers produced in short cylinder-shaped clusters 8–15 cm*** (3.2–6 in) ***long,*** each with 5 white, rounded petals. ***Fruits fleshy, rounded, 8–10 mm*** (0.3–0.4 in) ***in diameter, usually dark red or black,*** juicy, enclosing egg-shaped stone. **Harvest:** Pick fruit from midsummer to October, depending on location. **Preparation:** Best use, aside from trail thirst quencher, is for jelly. Prepare juice by crushing 1 qt unpitted cherries in 1 cup water. Simmer, stirring about 30 min and strain out juice. Quarter several whole apples, cover with water, simmer until tender. Strain off juice. Combine 2 cups apple juice with 1 cup cherry juice. Add 4 cups sugar and stir until dissolved. Boil rapidly until jelly temperature is reached. Pour into sterilized jelly glasses and seal. Or use sour cherry jelly recipe accompanying pectin package. Indians ground whole fruits, leached poison from seeds, formed pulp into cakes, and dried them in sun for sauce and pemmican. **Related edible species:** BLACK CHERRY (preceding) and several other sweet and sour fruited species, with various ranges. **Poisonous look-alikes:** Autumn and wilted leaves and pits of fruits contain hydrocyanic acid. Do not eat them! Also, Carolina laurelcherry *(P. caroliniana)* fruits are somewhat toxic.



Black cherry: flowering branch (Dykeman). Fruiting branch (Elias).

Common chokecherry: fruiting branch (Elias).





Downy serviceberry: fruiting branch (Elias). Flowering branch and tree (Dykeman).

Saskatoon serviceberry: flowering and fruiting branches (Ross).



SERVICEBERRY GENUS *Amelanchier*

There are about 25 species of serviceberries native to North America, Europe, Northern Africa, and Asia. In North America, they are small trees or shrubs that occur in deciduous forests and mountains, where their attractive white flowers announce spring. Many birds and wildlife eat the small fruits produced in summer.

Downy serviceberry *Amelanchier arborea*

(synonym: *A. laevis*)

Habitat: woodlands, rocky slopes, river banks, and along swamps; often growing with OAK, hickory, tulip tree, SWEET BIRCH. **Identification:** shrub or ***small tree*** with rounded crown and thick, slightly ridged and furrowed, ash-gray to nearly black bark. ***Leaves*** alternate, deciduous, simple, 5–9 cm (2–3.5 in) long, 2.5–3.5 cm (1–1.4 in) wide, widest at or near middle, ***finely toothed along margin. Flowers white, attractive,*** produced in spring (February in South to May in North), each ***with 5 strap-shaped petals 1–1.4 cm (0.4–0.6 in) long.*** Fruits in clusters, each rounded, 6–10 mm (0.2–0.4 in) in diameter, red to dark purple, fleshy, containing 5–8 black seeds. **Harvest and preparation:** Pick berries when ripe, usually mid to late summer. Eat as picked. Use fresh in recipes for jelly, jam, pie; fresh or dried in breads. For fruit sauce, stew 3 cups berries with 1 cup sugar for about 20 min. Mix dried berries with dried beef and suet to form pemmicanlike product. **Related edible species:** SASKATOON SERVICEBERRY (next) and other less common species. **Poisonous lookalikes:** none.

Saskatoon serviceberry *Amelanchier alnifolia*

(synonym: *A. florida*)

Habitat: mountain slopes, moist hillsides, prairies, margins of lakes and streams. **Identification:** shrub or small tree, sometimes forming thickets, with rounded crown and thin, smooth, or finely furrowed, brown bark. ***Leaves*** alternate, deciduous, simple, 2–6 cm (0.8–2.4 in) long, 2.5–4 cm (1–1.6 in) wide, broadest near base to uniformly wide, ***entire near base, sharply and coarsely toothed along upper margin. Flowers showy, white, produced in early spring,*** each with 5 ***strap-shaped petals 0.9–1.5 cm*** (0.4–0.6 in) long. Fruits in clusters, each rounded to egg-shaped, 6–11 mm (0.2–0.4 in) long, dark reddish-purple to almost black. **Harvest and preparation:** Fruits ripen in mid to late summer; eat raw or dried but better cooked. Use fruits in recipes calling for fruit, as in cakes, pies, jellies, puddings. To make jelly, wash fruits thoroughly, drain, partially crush, cover with water, and cook over low to medium heat until soft. Pour contents into wet jelly bag. For clear jelly do not squeeze bag. Simmer juice 5 min, removing any surface foam. Add sugar while stirring (1 cup juice to ⅔ cup sugar). Simmer 10–15 min or until mix shows sign of jelling. Pour mix into properly prepared jelly jars to within ¼ in of top. Cover with ¼ in melted paraffin. **Related edible species:** DOWNY SERVICEBERRY (preceding) and other less common species. **Poisonous look-alikes:** none.

Autumn

Autumn is the season for fruits and nuts. These come mainly from trees and shrubs that require a full growing season before flowers transform into mature seeds and fruits. Oaks, beech, hickories, walnuts, hawthorns, viburnums, and grapes are common sources and easy to identify. In autumn you can gather large quantities of edibles and consume them then or store them. The oaks, beech, walnuts, and hickories are cyclic in nut production, or mast crop. That is, a large mast crop is normally followed by two or three years of smaller crops. So one year you may encounter a large crop of hickory nuts and the next year run into the acorn bounty of oaks instead.

This is also the time to note or even map populations of native edible plants (other than nuts) for harvest the next year. Keep track of the edible populations, especially immature ones; and avoid overharvesting them. Many plant species have been seriously depleted by greedy collectors. On the other hand, if you harvest fruits and nuts, you don't destroy the trees and shrubs. They will live to produce again, and their offspring will eventually be producers too—especially if you plant a fruit or nut now and then.

Additional autumn edibles

Plants listed below have parts that are edible in autumn and at least one additional season. Descriptions and photos of these plants appear in a seasonal section other than "Autumn," as indicated.

Alpine bistort (*Polygonum viviparum*), p. 154
American bistort (*Polygonum bistortoides*), p. 154
American hazelnut (*Corylus americana*), p. 172
Beach plum (*Prunus maritima*), p. 166
Beaked hazelnut (*Corylus cornuta*), p. 172
Bugleweed (*Lycopus uniflorus*), p. 88
California juniper (*Juniperus californica*), p. 194
California laurel (*Umbellularia californica*), p. 198
Cattail (*Typha latifolia*), p. 68
Chicory (*Cichorium intybus*), p. 114
Chufa (*Cyperus esculentus*), p. 130
Common burdock (*Arctium minus*), p. 112
Common chickweed (*Stellaria media*), p. 84
Common chokecherry (*Prunus virginiana*), p. 204
Common day lily (*Hemerocallis fulva*), p. 136
Cranberry (*Vaccinium macrocarpon*), p. 162
Creeping snowberry (*Gaultheria hispidula*), p. 152
Creeping wintergreen (*Gaultheria humifusa*), p. 160

Dandelion (*Taraxacum officinale*), p. 104
Eastern camass (*Camassia scilloides*), p. 64
Edible valerian (*Valeriana edulis*), p. 88
Evening primrose (*Oenothera biennis*), p. 102
Glandular mesquite (*Prosopis glandulosa*), p. 188
Glasswort (*Salicornia europea*), p. 76
Great bulrush (*Scirpus validus*), p. 70
Green pigweed (*Amaranthus hybridus*), p. 72
Groundnut (*Apios americana*), p. 148
Hard-stem bulrush (*Scirpus acutus*), p. 70
Indian fig (*Opuntia humifusa*), p. 138
James chickweed (*Stellaria jamesiana*), p. 84
Labrador tea (*Ledum groenlandicum*), p. 160
Lamb's quarters (*Chenopodium album*), p. 74
Lance-leaved pickerelweed (*Pontederia lanceolata*), p. 132
Live-forever (*Sedum purpureum*), p. 110
Marsh mallow (*Althaea officinalis*), p. 146
Mountain cranberry (*Vaccinium vitis-idaea*), p. 162
Narrow-leaved cattail (*Typha angustifolia*), p. 68
Pawpaw (*Asimina triloba*), p. 198
Pickerelweed (*Pontederia cordata*), p. 130
Pigweed (*Amaranthus retroflexus*), p. 72
Plantain (*Plantago major*), p. 78
Poverty weed (*Monolepis nuttalliana*), p. 74
Prickly pear (*Opuntia phaeacantha*), p. 140
Reed grass (*Phragmites communis*), p. 128
Rocky Mountain juniper (*Juniperus scopulorum*), p. 194
Salal (*Gaultheria shallon*), p. 160
Sassafras (*Sassafras albidum*), p. 124
Screwbean mesquite (*Prosopis pubescens*), p. 188
Sheep sorrel (*Rumex acetosella*), p. 120
Silver buffaloberry (*Shepherdia argentea*), p. 178
Smooth sumac (*Rhus glabra*), p. 184
Sour dock (*Rumex crispus*), p. 120
Southern bayberry (*Myrica cerifera*), p. 174
Squawbush (*Rhus trilobata*), p. 186
Staghorn sumac (*Rhus typhina*), p. 250
Sunflower (*Helianthus annus*), p. 156
Sweet birch (*Betula lenta*), p. 122, 252
Sweet gale (*Myrica gale*), p. 176
Utah juniper (*Juniperus osteosperma*), p. 196
Watercress (*Nasturtium officinale*), p. 146
Western camass (*Camassia quamash*), p. 136
Wild garlic (*Allium canadense*), p. 60
Wild leek (*Allium tricoccum*), p. 60
Wild onion (*Allium cernuum*), p. 58
Wild rice (*Zizania aquatica*), p. 128
Wild strawberry (*Fragaria virginiana*), p. 90
Wintergreen (*Gaultheria procumbens*), p. 150
Yellow birch (*Betula alleghaniensis*), p. 122, 254

Jerusalem artichoke *Helianthus tuberosus*

Also edible winter, spring

Habitat: damp or rich thickets, waste areas, roadsides; often cultivated today as by Indians in past. **Identification:** perennial herb to 3 m (9.8 ft) tall, forming colonies; stems upright, rough-hairy, from a root system with elongated, fleshy, edible tubers 7.5–12.5 cm (3–5 in) long. ***Leaves opposite or in whorls of 3 on lower part of stems, alternate above,*** broadest near base, ***to 25 cm*** (10 in) ***long, 6–15 cm*** (2.4–6 in) ***wide,*** tapered at tip and base, ***hairy above, rough, leathery. Flower heads yellow*** with rounded central disc 1–2.5 cm (0.4–1 in) across, ***10–20 ray flowers,*** each about 4 cm (1.6 in) long, ***several flower heads per plant, on slender stems from leaf bases on upper part of stems.*** **Harvest:** Identify colonies in summer when in bloom; dig tubers from first frost through winter. **Preparation:** Peel or scrub tubers before using. Slice raw in salad, make potato salad, boil and mash, roast with meat, slice and fry. For pickles, peel and boil 3–4 min, cover with wine vinegar, age 3–5 weeks. Adapt to many potato and carrot recipes. Food value equal to potato. The carbohydrates are mostly inulin and suitable for low starch diets. **Related edible species:** other SUNFLOWERS (*Helianthus* species) produce edible seeds. **Poisonous look-alikes:** none.

Lotus lily, American lotus *Nelumbo lutea*

Also edible spring, summer

Habitat: lakes, ponds, slow-moving streams, bays and tidal waters. **Identification:** ***aquatic perennial herb;*** roots large, thick with swollen tubers. ***Leaves large,*** 20–70 cm (8–28 in) across, circular, often ***rising above water level, center depressed,*** bluish-green; ***leafstalk attached at center of blade,*** variable in length, strong but flexible. ***Flowers*** solitary on long stalks, ***showy,*** 14–26 cm (5.5–10.2 in) across, ***with numerous pale yellow petals*** or petallike structures. ***Fruits produced in large cone-shaped, flat-topped receptacles*** raised above water level; each fruit dry, hard, nutlike, globe to egg-shaped, 1–2 cm (0.4–0.8 in) long. **Harvest:** Some part edible most of year. Pick unopened leaves and young stalks in spring. Pick seed receptacle either before or after seeds ripen during summer through autumn. Dig up tuberous root in autumn or early spring if you can overcome the difficulty of its deep water bed. **Preparation:** Leaves and young stalks are edible, but not exceptional, potherbs. Immature seeds are excellent raw, boiled, or roasted. Mature seeds are hard-shelled; crack shells before boiling to soft chestnutlike texture. Or roast *fresh* mature seeds, crack, and remove shells. Eat like nuts, or grind into meal and substitute for part of flour in bread and muffin recipes. Bake or boil tubers like sweet potatoes until tender. Peel and mash. To every cup add 1 tbsp butter, ¼ tsp salt, and a little hot milk. Beat to smooth texture. **Related edible species:** various species of YELLOW POND LILY (next) and water lily *(Nymphaea)*. **Poisonous look-alikes:** none.



Jerusalem artichoke: flowers and tubers (Elias).

Lotus lily: receptacle with protruding fruits and flower (Feldman).



3. Massage the major palm lines. Use the thumb to massage along the palm lines. Massage more towards the thumb bone and along that bone. When a lot of emotion is held inside, find the sore point and massage it.

4. Massage the back of the hand. Use the thumb to press along the bones on the back of the hand. When you find a tender spot, take more time to work on it.

5. Massage the fingers. Always rub your hands until warm. Use the right hand's fingers to wrap around the left thumb, and then, one by one, squeeze, hold and release each finger on the left hand three to six times. Start with the left hand and continue to the right hand's fingers, according to the elements of the finger. This will greatly help to control emotions.



Fig. 7 *Massaging the Palm Lines*



Yellow pond lily: flower prior to seed development (Elias).

Arrowhead: flower and whole plant (NYBG).



Yellow pond lily, Spatterdock *Nuphar advena*

Also edible winter, spring, summer

Habitat: lakes, ponds, slow streams, swamps, tidal waters. **Identification:** ***aquatic perennial herb;*** roots (actually stems or rhizomes) large, thick, to 13 cm (5 in) in diameter, elongate, branching, covered with leaf scars. ***Leaves large,*** 10–40 cm (4–16 in) long, 5–16 cm (2–6.3 in) wide, broadest below middle, ***deeply lobed at base to form U- or V-shaped cleft,*** shiny green, ***usually raised above water level,*** sometimes floating; leafstalk thick, stout, attached at base of cleft. ***Flowers*** solitary on long stalks, ***showy,*** 3–10 cm (1–4 in) across, ***with numerous yellow, green-tipped petals. Fruits broadly urn-shaped,*** 2–5 cm (0.8–2 in) long, with short thick neck and flattened top, ***ribbed,*** green, containing numerous, yellowish-brown, small, egg-shaped seeds. **Harvest:** Cut fruits free of stalk as they ripen (late summer or fall). Air-dry until fruits pull apart to separate seeds. Dump seeds in bucket of water. After 5–6 hr good ones sink; dry in sun or warm oven. Loosen tuberous roots from mud in bottom of pond from autumn to spring. Indians used their toes. **Preparation:** Seeds store well. Pop seeds like popcorn or remove shells by parching over coals or in oven, pounding lightly to crack shells, and winnowing. Then boil nutmeats like rice or grind and use like cornmeal. Peel, slice, and boil roots in 2 water changes. Mash, season, and serve like potatoes or dry and use like flour. **Related edible species:** several other species of yellow pond lilies *(Nuphar)*, most important is cow lily *(N. polysepalum)* in West. **Poisonous look-alikes:** none.

Arrowhead, Duck potato, Wapato *Sagittaria latifolia*

Also edible winter, spring, summer

Habitat: shores of lakes, ponds, streams, ditches, bogs, wet meadows; common and widespread. **Identification:** ***perennial herb*** 0.6–1.2 m (2–4 ft) high, with fibrous roots developing small tubers (potatolike) 0.5–5 cm (0.2–2 in) in diameter. ***Leaves all at base,*** blades 10–25 cm (4–10 in) long, 1–25 cm (0.4–10 in) wide, ***arrowhead-shaped with long pointed lobes at base, leaf shape highly variable*** from extremely narrow to very broad, smooth or hairy; leafstalks flexible, to 1 m (3.2 ft) long. Flowering stalk taller than leaves; ***flowers in clusters of 3s along upper part of spike, each flower with 3 delicate, white petals.*** Fruiting heads globe-shaped or nearly so, containing numerous flat, winged seeds. **Harvest:** Collect tubers from late summer through early spring, whenever there is no ice. Dislodge tubers from roots in mud beneath water with rake or hoe, or wade in as the Indians did and loosen them with your toes. Tubers will float to surface and are easily collected. **Preparation:** Tubers are edible but not always tasty raw; better cooked like potatoes. Bake or boil about 30 min until tender; peel after cooking. Serve topped with mixture of butter and lemon juice or STAGHORN SUMAC extract. Use in potato recipes. To dry tubers for storage, boil until tender, drain, slice about ½-in thick, dry thoroughly in sun or warm oven. Store in warm dry place. Before using soak 20 min; allow 20 min cooking time. **Related edible species:** several other arrowhead species *(Sagittaria)*; all have arrowhead leaves; PICKERELWEED has similar leaves but lacks tubers. **Poisonous look-alikes:** none.

WILD GRAPES *Vitis*

North America has about 50 native species of grapes along with several introduced ones that now grow wild. While it is easy to identify a grape vine, determining grape species can be challenging. It is best to familiarize yourself with the grapes in your region and the variation in fruit quality. Grapes are climbing vines with large lobed or toothed leaves, numerous small flowers in elongate clusters, and then fruit bunches. Three of the more common grapes are described here. **Harvest:** Gather leaves in spring when young and tender but full grown. Collect fruits between August and October, depending upon species and region. **Preparation:** Boil leaves until tender, and serve with other vegetables. Check cookbook recipes for stuffed grape leaves. Most fresh grapes are too acid to eat in quantity. Best to make juice, jelly, preserves, pie, and wine. For jelly, use mixture of ripe and unripe (for pectin) fruits. Wash, drain, remove stems, and mash in kettle. Add small amount of water and cook until fruit comes apart, about 15–20 min. Strain juice through jelly bag. Prevent crystallization in jelly by letting juice sit overnight or cooking 1 cup tart apples with each 4 cups of grapes. Boil 4

Riverside grape *Vitis riparia*

Also edible spring, summer

Habitat: stream and river banks, margins of woodlands, thickets. **Identification:** *large vine,* usually climbing; branches tough, rounded, becoming smooth, pith chambered. ***Leaves*** alternate, simple, deciduous, ***12–20 cm*** (4.7–8 in) ***long,*** 8–16 cm (3–6 in) wide, nearly circular in outline to broadest near base, ***usually 3-lobed, long-pointed at tip,*** coarsely toothed along margin, heart-shaped at base, smooth above, ***hairy beneath.*** Flowers tiny, produced in many-flowered, elongate clusters to 10 cm (4 in) long. Fruits are dense bunches of ***berries,*** each ***rounded, 8–14 mm*** (0.3–0.6 in) ***in diameter, black with whitish bloom,*** sour tasting. **Harvest and preparation:** See WILD GRAPES (preceding).

Frost grape *Vitis vulpina*

Also edible spring, summer

Habitat: streams and river banks, low wetlands, thickets. **Identification:** ***large vine,*** often climbing; branches stout, rounded, becoming smooth, pith chambered. ***Leaves*** alternate, simple, deciduous, ***10–18 cm*** (4–7 in) ***long, almost as wide,*** very broad, widest near base to almost round, ***usually unlobed or slightly 3-lobed,*** pointed at tip, coarsely toothed along margins, heart-shaped at base, smooth above, smooth below except for junctions of major veins. Flowers tiny, produced in many-flowered, elongated clusters to 18 cm (7 in) long. Fruits are clusters of ***berries,*** each ***rounded, 4–10 mm*** (0.2–0.4 in) ***in diameter, black,*** sour tasting until frost, then sweet. **Harvest and preparation:** See WILD GRAPES (preceding).

cups juice with 4 cups sugar until jelling point is reached. Skim off foam, pour into sterilized jars, seal with paraffin. For pie, squeeze skins from 4 cups ripe grapes. Simmer pulp until it comes apart; sieve to remove seeds. Chop skins and combine with strained pulp, 1½ cups sugar, 2 tbsp flour, ¼ tsp salt, 1 tbsp lemon juice, 2 tbsp melted butter. Mix well and pour into unbaked pie shell. Fit and slit top crust. Bake at 205°C (400°F) for 30–40 min until crust is browned. For juice, use ripe fruit. Crush in kettle, heat and simmer for 30 min, but do not boil. Press through sieve and strain through jelly bag. Sweeten to taste. For wild grape butter, puree remaining pulp. Add equal amount to maple sugar or honey and blend in bean pot. Bake in preheated 160°C (320°F) oven, stirring occasionally, for 3 hr. Seal in sterilized jars. For emergency water source, cut off large vine and drain sap. **Poisonous look-alikes:** moonseed *(Memispermum canadense)* is a vine with simple entire or shallowly lobed leaves and clusters of black fruits resembling a bunch of grapes. The leafstalk is attached on the lower surface of the blade above the base (peltate) and the leaves are not coarsely toothed as those of most grapes. Single seed a flat crescent.

Riverside grape: fruiting branch (Elias).



Frost grape: fruiting branch (Elias).



California grape *Vitis californica*
Also edible spring, summer

Habitat: stream and river banks, moist canyons, margins or clearings of forests. **Identification:** large ***woody vine,*** climbing; branches stout, rounded, with shredding bark, pith chambered. ***Leaves*** alternate, simple, deciduous, ***6–14 cm*** (2.4–5.5 in) ***long,*** nearly as wide, ***circular in outline, nearly unlobed to 3-lobed,*** short-pointed at tip, coarsely toothed along margin, deeply lobed at base, hairy above, dense cobweblike hairs beneath. Flowers tiny, produced in many-flowered, branched, elongated clusters. ***Fruits*** are dense bunches of ***berries,*** each rounded, ***6–10 mm*** (0.2–0.4 in) ***in diameter, dark purple and covered with whitish bloom.*** **Harvest and preparation:** See WILD GRAPES (preceding).

Wild potato vine *Ipomoea pandurata*
Also edible spring, summer

Habitat: fields, fencerows, roadsides; dry, open or partly shaded areas. **Identification:** ***perennial*** trailing or slightly twining ***vine,*** 0.9–3.6 m (3–12 ft) long, ***often purplish along stem,*** branching, ***from a large tuberous root to 9 kg*** (20 lbs), ***vertical, deep, slightly milky,*** resemble a yam. ***Leaves 4–8 cm*** (1.6–3.2 in) ***long, 3–8 cm*** (1.2–3.2 in) ***wide, heart-shaped, pointed at the tip, entire along the margins. Flowers*** to 7.5 cm (3 in) across, with a ***white*** (sometimes purple-centered), ***funnel-shaped*** corolla, like a morning glory flower. Fruit a 2-chambered capsule 0.8–1.2 cm (0.3–0.5 in) long, broadest near the base and tapering to a tip. **Harvest:** Dig deep root any time when ground is not frozen, but best not in summer when starch level is low. Young roots are preferred to older, woody ones. **Preparation:** Boil or bake roots like sweet potatoes. When boiling, change water 2 or 3 times for bitter ones; others will not need changing. All roots have tough outer skins and require peeling. Serve with butter and seasonings. Some older roots may be too woody to use. Dry peeled slices of root for later use. **Related edible species:** Bush morning glory *(I. leptophylla)* of the West is variously described from excellent to nearly inedible. Edibility of other species has not been reported. **Poisonous look-alikes:** Flowers may resemble those of JIMSON WEED; however, JIMSON WEED is an upright herb with large, coarsely toothed leaves.



California grape: fruiting branch (Ornduff).

Wild potato vine: flower (Mohlenbeck).





Common barberry: fruiting branch (Dykeman).

Spice bush: fruiting branch (Elias). Flowers (NYBG).



Common barberry *Berberis vulgaris*

Habitat: widely planted European shrub; also grows wild, the seeds spread by birds; disturbed woodlands, fencerows, fields, roadsides. **Identification:** shrub 1–3 m (3–10 ft) high, with rounded crown. Branches grooved, yellowish-red, turning gray by second season, with ***3-forked sharp-spines. Leaves*** alternate, simple, deciduous, ***often crowded together on short shoots,*** 2–4.8 cm (0.8–2 in) long, 0.8–2.4 cm (0.3–1 in) wide, ***broadest above middle, rounded at tip, finely sharp-toothed along margin.*** Flowers produced in spring, stalked, in 10–20-flowered, elongated, narrow clusters, each flower greenish-yellow. ***Fruits in drooping clusters*** in late summer or early autumn, ***berries 8–12 mm*** (0.3–0.5 in) ***long, orange-red to scarlet.*** **Harvest and preparation:** Pick fruits in autumn when full color has developed. For jelly, 4 cups crushed barberries, 2 whole oranges, chopped, 2 cups water, 1½ cups sugar, 1 pkg pectin. Combine berries, oranges, and water. Bring to boil, simmer until tender, about 20 min. Strain juice through cloth or jelly bag. Combine juice and sugar; bring to rolling boil. Add pectin; bring to boil. Pour into hot, sterilized jars; seal. Yields 3 pt. For straight barberry jelly, cook berries and extract juice. Boil juice to 105°C (200°F); pour into hot, sterilized jars; seal. Needs no pectin, very tart. Juice also good in sauces and beverages where tartness is needed. To relieve thirst, chew a few leaves. **Related edible species:** red-fruited barberry *(B. haematocarpa),* southwestern U.S.; American barberry *(B. canadensis)*, southeastern U.S.; and other species. **Poisonous look-alikes:** none.

Spice bush *Lindera benzoin*

Also edible winter, spring, summer

Habitat: rich woodlands, stream banks, especially in moist soils. **Identification:** shrub to 5 m (16.4 ft) high, with numerous, spreading to upright, smooth ***branches, with spicy fragrance when broken.*** Leaves alternate, simple, deciduous, 6–14 cm (2.4–5.5 in) long, 3–6 cm (1.2–2.4 in) wide, broadest near or above middle, long-pointed at tip, entire along margin, thin, smooth, bright green, stalked. ***Flowers in early spring before leaves appear, yellow, small, produced in dense clusters along previous year's twigs. Fruits*** produced in clusters, each ***a berry,*** widest at middle, rounded at end, ***6–10 mm (0.2–0.4 in) long,*** green turning ***bright red at maturity.*** **Harvest:** young leaves in spring; bark and twigs all year; fruits in late autumn before migrating flocks of birds eat them all. **Preparation:** For tea steep 15 leaves or handful of fresh twigs and bark in 4 cups boiling water for 15 min. Strain if necessary; serve with honey and milk for best flavor. Dry fruits thoroughly in warm oven. Grind and use as substitute for allspice. **Related edible species:** none. **Poisonous look-alikes:** none.

Desert hackberry, Spiny hackberry *Celtis pallida*

Habitat: desert foothills and mesas at 450–1,050 m (1,500–3,500 ft). **Identification:** ***shrub or small tree,*** to 5 m (16 ft) tall, single or in thickets, ***densely branched, twigs with many single or paired spines at base of leaves. Leaves simple, alternate, evergreen, broadest near or below the middle,*** 2.5–7.5 cm (1–3 in) long, ***unequal at base, toothed from mid margin to tip, rough upper surface.*** Flowers in spring, small, greenish white, in long clusters at base of younger leaves. ***Fruits single, fleshy,*** 6–8 mm (0.2–0.3 in) diameter, ***yellow to red-orange, sweet, containing 1 large seed.*** **Harvest:** fruits in late September and October; crop frequently abundant if rain was sufficient. **Preparation:** Eat fresh or dried as snack. Dry whole or mashed and formed into small cakes; dry in sun or 100°C (212°F) oven. Store in dry place. For seedy jam, mash 6 cups fresh berries in saucepan with 2 cups sugar, 3 tbsp lemon juice, and ½ cup water. Bring to boil; reduce heat and simmer with stirring until thick. Ladle into sterilized jars and seal with paraffin. If seeds are annoying, grind fruit fine before cooking. Use fresh or dried fruits in baking. **Related edible species:** American hackberry *(C. occidentalis)* and several other species are edible; palatability depends on species and weather. **Poisonous look-alikes:** none.

ROSES *Rosa*

There are about 35 species of roses native to North America and several introduced species that now grow wild on roadsides and disturbed sites. While it's easy to distinguish roses from other groups of plants, the distinctions among individual species are often difficult. Fortunately, all roses have edible parts although quality and size vary greatly. Roses are shrubs normally with spiny branches, and alternate featherlike (pinnate) compound leaves. The large attractive flowers have 5 petals, and many stamens and pistils. Four of the more common species are treated on upcoming pages. **Harvest and preparation:** Gather fruits (hips)

California rose *Rosa californica*

Also edible winter, summer

Habitat: along streams, rivers, washes, and in moist canyons. **Identification:** shrub to 3 m (9.8 ft) tall with coarse, erect to nearly erect branches, armed with stiff, flattened, usually curved spines. Leaves alternate, deciduous, compound, each with 5–7 leaflets, leaflets broadest near base and gradually tapering to a pointed to blunt tip, 1.2–3.6 cm (0.5–1.4 in) long, about half as wide, with 1 or 2 rows of sharp teeth along margin, hairy. ***Flowers in few-flowered clusters*** in spring or summer, each with green smooth floral tube (hypanthium), narrow lance-shaped sepals, ***5 white or pink petals 1.2–2.5 cm*** (0.5–1 in) ***long. Fruits*** (hips), fleshy, ***egg- to globe-shaped, 1.2–1.8 cm*** (0.5–0.7 in) ***in diameter, with distinct neck,*** red, smooth. **Harvest and preparation:** See preceding. **Related edible species:** all native roses. **Poisonous look-alikes:** none.



Desert hackberry: fruiting branch (Cramer).

as they ripen in autumn (after frost) or during winter, wash and remove dried persistent flower parts from top of hips, then split open and remove seeds. Eat pulpy portion fresh or in jellies or sauces. Dry whole or halved cleaned fruits for later use (soak overnight in warm water) or finely grate or grind dried hips to yield a slightly fragrant powder rich in vitamin C and essential minerals. Sprinkle on hot breakfast cereals or use to make hot tea. Also wash young leaves, cut into small pieces, and dry for hot rose tea. Flower petals can be used in candy, tea, and jellies, but fruits are more nutritious.

California rose: fruits and flower (McNeal).



Fingers Correspond to Emotions, Elements and Organs

A. Thumb corresponds to the element earth and is associated with the stomach. The corresponding emotion is worry.

B. Index finger corresponds to the element of metal and is associated with the lungs and large intestine. It links with the emotions of sadness, grief and depression.

C. Middle finger corresponds with the element of fire and is associated with the heart, small intestine, circulatory system and the respiratory system. It links with the emotions of impatience and hastiness.

D. Ring finger corresponds to the wood element and is associated with the liver, gall bladder and the nervous system; it corresponds to the emotion of anger.

E. Pinky finger corresponds to the water element; it is associated with the kidneys, and corresponds with the emotion of fear.



Wild rose: flowers (NYBG).


Introduced and
grows wild.
Widespread.

Sweetbrier rose: flower (Speas).

Wrinkled rose: fruits (Crow). Flower (Hardin).



Wild rose, Pasture rose *(Also edible winter, summer)* *Rosa carolina*

Habitat: open woodlands, margins of woodlands, fields, pastures, rocky outcrops. **Identification:** low shrub to 1.5 m (5 ft) high, with slender arching branches, with stiff hairs and armed with broad-based straight or curved spines, especially on lower half. Leaves alternate, deciduous, compound, each with 3–7, rarely 9, leaflets, leaflets usually broadest near middle to almost rounded, 1.6–3.8 cm (0.6–1.5 in) long, about half as wide, pointed to blunt at tip, ***coarsely sharp-toothed along margin. Flowers*** usually solitary and produced in spring or early summer, each ***with glandular-hairy floral tube*** (hypanthium), narrow lance-shaped sepals, and 5 ***pink petals*** 2–3.2 cm (0.8–1.3 in) long. ***Fruits (hips)*** fleshy, ***nearly globe-shaped, 6–10 mm*** (0.2–0.4 in) ***in diameter,*** red, containing several seeds. **Harvest and preparation:** See roses. **Related edible species:** all native roses. **Poisonous look-alikes:** none.

Sweetbrier rose *(Also edible winter, summer)* *Rosa eglanteria*

Habitat: disturbed sites such as roadsides, abandoned pastures and fields, edges of woodlands, fencerows. **Identification:** shrub to 3 m (9.8 ft) high, with large arching coarse branches, new branches with laterally flattened, broad-based, spines curved or straight. Leaves alternate, deciduous, compound, apple odor when crushed, each leaf with 7–9 leaflets, ***leaflets*** broadest near or above middle, 1–4 cm (0.4–1.6 in) long, pointed or blunt at tip, ***doubly toothed and glandular along margin,*** hairy. ***Flowers*** solitary or in few-flowered clusters from May to July, each with green, ***smooth or sparsely hairy floral tube*** (hypanthium), ***featherlike*** (pinnate) ***glandular sepals,*** and 5 pink petals 1.4–2.4 cm (0.6–1 in) long. ***Fruits*** (hips) fleshy, ***elongate and broadest near middle, 1.5–2 cm*** (0.6–8 in) ***long,*** red, containing several seeds. **Harvest and preparation:** See roses. **Related edible species:** all native roses. **Poisonous look-alikes:** none.

Wrinkled rose *(Also edible winter, summer)* *Rosa rugosa*

Habitat: introduced from Asia; grows wild along roadsides, in dunes, and near seashores. **Identification:** shrub to 2 m (6.6 m) tall, with coarse, arching ***branches, densely covered with stiff hairs and stiff needle-shaped spines.*** Plants forming dense clumps. ***Leaves*** alternate, deciduous, compound, each leaf with 5–9 leaflets, leaflets widest near or above middle, 2–5 cm (0.8–2 in) long, about half as wide, pointed to rounded at tip, with teeth curving downward (recurved) along margin, ***dark green, deeply furrowed or wrinkled. Flowers*** solitary or in few-flowered clusters in spring, summer, or early fall, each ***with green, smooth floral tube*** (hypanthium), ***narrow spoon-shaped sepals, and 5 rose-purple to white petals*** 2.5–5 cm (1–2 in) long. ***Fruits*** (hips) fleshy, ***globe-shaped but depressed at top and bottom, 2–2.5 cm*** (0.8–1 in) ***in diameter,*** red, ***smooth,*** containing many seeds. **Harvest and preparation:** See roses. **Related edible species:** all native roses. **Poisonous look-alikes:** none.

Highbush cranberry *Viburnum trilobum*

Also edible winter

Habitat: stream banks, wet thickets, moist woodlands. **Identification:** Not a real cranberry, this is a ***shrub,*** upright, to 5 m (16.4 ft) high; branches upright to spreading, ash-gray with age. ***Leaves*** opposite, simple, deciduous, ***6–12 cm*** (2.4–4.7 in) ***long, almost as wide,*** broadest near base, ***deeply 3-lobed,*** long pointed at tip, coarsely toothed along margin, rounded to squared at base, dark green and sparsely hairy above, hairy beneath; ***leafstalks with 1 or 2 small glands. Flowers produced in dense, many-flowered, round-topped clusters, with showy white sterile flowers on margin of flower cluster;*** small sterile flowers in center. ***Fruits berrylike,*** rounded to egg-shaped, 8–14 mm (0.3–0.6 in) long, ***bright red, translucent*** when ripe, juicy, containing single flattened stone. **Harvest:** Fruits ripen in late summer but persist on shrub and become less sour through winter. To make sure your shrub is highbush cranberry and not its bitter look-alike, the introduced guelder rose *(V. opulus),* make a harmless taste test. Pick in fall and winter. **Preparation:** much the same as CRANBERRY except large seeds must be removed. While cooking add lemon or orange peel shavings to eliminate bad odor of berries. For sauce, cover several quarts of berries with water in kettle. Add outer peels of 2 lemons or oranges. Bring to boil and simmer 5 min. Mash thoroughly and simmer another minute or two. Force juice and pulp through coarse strainer to remove seeds. Add 1 pkg pectin to 4 cups strained fruit, bring to boil, and add 5 cups sugar. Boil again for 1 min and seal in sterile jars or refrigerate. If fruits are picked before first frost, pectin may not be needed. For juice and jelly, cook berries as above but strain through jelly bag. For juice, dilute and sweeten to taste. For jelly, proceed with 4 cups juice as for sauce. **Related edible species:** HOBBLEBUSH, NANNYBERRY, and SQUASHBERRY (next), and in the Pacific Northwest the cranberry tree *(V. pauciflorum).* **Poisonous look-alikes:** none.

Hobblebush *Viburnum alnifolium*

Habitat: stream banks, moist woodlands, ravines. **Identification:** ***shrub,*** often spreading, to 3 m (9.8 ft) high, ***branches spreading, some drooping and rooting in ground. Leaves*** opposite, simple, deciduous, 10–24 cm (4–9.4 in) long, almost as wide, ***broadest near base,*** short-pointed at tip, heart-shaped at base, finely double toothed along margin, hairy beneath. ***Flowers produced in many-flowered, round-topped clusters, with sterile flowers, each with showy pink or white petals 2–3.8 cm (0.8–1.5 in) wide on margin of flower cluster;*** tiny fertile flowers in center. ***Fruits berrylike, slightly flattened,*** egg-shaped, 6–12 mm (0.2–0.5 in) long, ***black,*** containing single flattened stone. **Harvest:** fruits in autumn, generally only on shrubs in open area, not in dense woods. **Preparation:** same as NANNYBERRY (next). **Related edible species:** See NANNYBERRY. **Poisonous look-alikes:** none.



Highbush cranberry: fruiting branches (Elias). Flower cluster (Stevenson).

Hobblebush: flower cluster (NYBG). Fruiting branch (Elias).





Nannyberry: fruits and flower cluster (Dykeman).

Squashberry: fruiting branch (Clawson).



Nannyberry

Viburnum lentago

Habitat: swamps, stream banks, rocky hillsides, margins of woodlands. **Identification:** ***shrub*** or small tree to 10 m (33 ft) with short branching trunk and slender tough, dark reddish-brown branches. ***Leaves opposite,*** simple, deciduous, 5–10 cm (2–4 in) long, 2.5–4 cm (1–1.6 in) wide, ***broadest near base or middle,*** occasionally rounded, with many fine, sharp teeth along margin, bright shiny green and smooth. ***Flowers produced in dense, many-flowered, rounded heads to 12 cm (4.7 in) in diameter,*** each flower white to cream, 5-lobed. ***Fruits berrylike, rounded,*** 8–12 mm (0.3–0.5 in) in diameter, ***dark blue to black,*** sweet, juicy, containing single flattened seed. **Harvest:** fruits when ripe in autumn as leaves are falling. **Preparation:** fruits good for trail snacks; flavor excellent, seeds a nuisance. For pudding add 1½ cups water to 1 qt fruits, boil for 5 min. Mash and work pulp through food mill. If pulp remains with seeds, scrape residue into small pan and add ½ cup water. Stir, mash, mill again. Yields about 1 cup pulpy syrup. Add 1 tbsp lemon rind, juice of ½ lemon, 1 cup sugar, ⅛ tsp cinnamon, ¾ cup water. Bring to boil and simmer 15 min. In separate pan combine ⅓ cup cornstarch with 1 cup cold water. Blend into fruit mixture. Cook slowly 15 min, pour into mold, and cool. Serve plain or with whipped cream. **Related edible species:** black haw *(V. prunifolium)*, northern wild raisin *(V. cassinoides)*, and HOBBLEBUSH (preceding); use fruits in same ways as for nannyberry. **Poisonous look-alikes:** none.

Squashberry

Viburnum edule

Also edible winter, summer

Habitat: stream banks, wet thickets, margins of woodlands, moist low woodlands. **Identification:** ***shrub,*** often sprawling, to 2.5 m (8 ft) high; stems usually spreading, smooth. Leaves opposite, simple, deciduous, 4–11 cm (1.6–4.3 in) long and wide, ***broadly circular in outline, with 3 shallow lobes,*** sharply and irregularly toothed along margin, squared to slightly heart-shaped at base, sometimes hairy beneath. ***Flowers produced in loose, round-headed clusters 4–6 cm (1.6–2.4 in) across,*** each flower milky white, 5-lobed. ***Fruits berrylike, rounded,*** 6–10 mm (0.2–0.4 in) in diameter, ***red,*** containing single flattened seed. **Harvest:** fruits similar to HIGHBUSH CRANBERRY but smaller and less acid. Pick in late summer through winter. **Preparation:** same as HIGHBUSH CRANBERRY, except juice does not require dilution for use as beverage. **Related edible species:** See HIGHBUSH CRANBERRY. **Poisonous look-alikes:** none.

Pinyon pine *Pinus edulis*

Habitat: mesas, plateaus, lower mountain slopes, and foothills from 825–2,350 m (2,700–7,700 ft) elevation. Often occurs with JUNIPERS, GAMBEL'S OAK, and ponderosa pine. **Identification:** small, spreading, bushy tree with thin, irregularly furrowed, scaly ridged, gray to reddish-brown bark. ***Leaves (needles) 2 per bundle*** (rarely 1 or 3), ***1.2–5 cm*** (0.6–2 in) ***long,*** stiff, sharp-pointed, curved inward toward branches, bluish-green when young, turning yellowish-green with age. Fruits hard, short, egg-shaped cones 3.8–5 cm (1.5–2 in) long, composed of thick, blunt, yellowish-brown scales, each scale with 2 seeds. ***Seeds egg-shaped, 1.2–1.4 cm*** (0.5–0.6 in) ***long, wingless,*** pale yellow with reddish-brown markings, oily, sweet. **Harvest and preparation:** large cone crops produced every 3–4 yr. Gather ripe, almost open, cones in autumn. Store dry so that scales will separate to release seeds. Eat seeds fresh or after roasting 20–30 min. Roasting dries cones, facilitates seed removal, improves nutty flavor of seeds, and permits longer storage. Grind roasted nuts into meal. Seeds are rich in protein (14.5%) and fats and have high caloric content. **Related edible pines:** SINGLELEAF PINYON PINE, Mexican pinyon *(P. cembroides),* Parry pinyon *(P. quadrifolia)*. **Poisonous look-alikes:** none.

OAKS *Quercus*

This large genus of about 55 native trees and shrubs north of Mexico offers important food sources to wildlife and provides nuts edible to people as well. North American oaks are divided into two subgenera: the white oak group and the red/black oak group.

White Oak Group *Quercus* subgenus *Quercus*

This large group of related oaks occurs in the Americas, Europe, and Asia. There are 32 native species north of Mexico. They are distinguished from other oaks by a combination of characteristics: leaves entire, toothed, or lobed but never bristle-tipped; acorns maturing at end of first growing season on current year's twigs, and inner surface of acorn shell lacking hairs. Four of the most common species are discussed on upcoming pages. **Harvest and preparation:** Gather acorns in autumn as they turn brown and fall. They are usually sweet and need no leaching to remove tannins (if any bitterness exists, process as NORTHERN RED OAK acorns). Store nuts in cool dry place or shell for immediate use. For grits, dry nutmeats in air or warm oven and grind coarsely. Use like chopped nuts. For meal, regrind grits to finer texture and redry in warm oven, stirring occasionally. Use in recipes under RED OAK group. For candy combine 2 cups sugar, 1 cup water, ⅛ tsp cream of tartar, and pinch of salt in small pan and boil until carmelization begins. Maintain liquid by placing in larger pan of boiling water. Dip dried whole nutmeats in syrup and place on wax paper to harden.

White oak *Quercus alba*

Habitat: mixed deciduous forest in sandy, gravelly, loamy soils; widespread, often growing with hickories or other oaks. **Identification:** medium-size to tall



Pinyon pine: immature cones (Pawloski).

White oak: immature acorns (Elias).





Chestnut oak: immature acorn and flowering branch (Elias).



Gambel's oak: fruiting branch and tree (Dykeman).

Blue oak: mature acorns with dried leaves (Dykeman). Normal blue oak form foreground; weeping form background (Kruckeberg).



tree with broad round crown and thick, shallow to deeply furrowed, light ash-gray bark. *Leaves* alternate, deciduous, simple, *12–22 cm (4.7–8.7 in) long, 5–10 cm (2–4 in) wide, with 7–10 shallow to deeply rounded lobes along margin, bright green,* smooth. Fruits are *acorns* on current year's twigs, *1.2–2 cm (0.5–0.8 in) long,* widest near middle or base, light brown at maturity, *acorn cup bowlshaped, 8–12 mm (0.3–0.5 mm) deep, enclosing about ¼ of nut,* cup scales thick, warty; nutmeat sweet. **Harvest and preparation:** See WHITE OAK GROUP (preceding).

Chestnut oak *Quercus prinus*

Habitat: mixed deciduous woodlands, especially dry to moist well-drained slopes and ridges. **Identification:** medium-size tree with broad, open, rounded crown and thick, *deeply furrowed,* dark brown to reddish-brown *bark. Leaves* alternate, deciduous, simple, *12–25 cm* (5–10 in) *long, 3.6–7.5 cm* (1.4–3 in) *wide,* broadest above middle, *coarsely and irregularly round-toothed along margin,* greenish-yellow. Fruits are *acorns 2.5–3.8 cm* (1–1.5 in) *long,* uniformly wide to broadest near base, acorn *cup deeply bowl-shaped to top-shaped, enclosing about half of nut;* cups scales thick, warty; nutmeat sweet. **Harvest and preparation:** See WHITE OAK GROUP (preceding).

Gambel's oak *Quercus gambelii*

Habitat: dry foothills, canyons, lower mountain slopes, usually from 1,350–2,800 m (4,400–9,200 ft) elevation. **Identification:** shrub or small tree with rounded crown and thin, light gray to grayish-brown, rough, scaly bark. *Leaves* alternate, deciduous, simple, *8–16 cm* (3.2–6.3 in) *long,* 4.5–7.6 cm (1.8–3 in) wide, broadest above middle to uniformly wide, *with 5–9 moderately deep to deep lobes along margin,* leathery, *yellowish-green.* Fruits are *acorns* on current year's twigs, *2–2.5 cm* (0.8–1 in) *long,* nearly globe-shaped, *acorn cup* shallow to deeply bowl-shaped, *enclosing ¼ to ⅓ of nut,* scales thick; nutmeat sweet. **Harvest and preparation:** See WHITE OAK GROUP (preceding).

Blue oak *Quercus douglasii*

Habitat: interior valleys, rolling hills, lower mountain slopes to 1,350 m (4,400 ft) elevation. **Identification:** small to medium-size tree with rounded crown and thick, checkered, light gray bark. *Leaves* alternate, deciduous, simple, 3.8–10 cm (1.5–4 in) long, 1.9–5 cm (0.7–2 in) wide, uniformly wide to broadest above middle, *entire to shallowly and irregularly lobed along margin, bluish-green.* Fruits are acorns on current year's branches, 1.6–3.1 cm (0.6–1.2 in) long, broadest near base; *acorn cup saucer-shaped, enclosing only base of nut,* cup scales small, warty; nutmeat somewhat sweet. **Harvest and preparation:** See WHITE OAK GROUP (preceding).



Worry

Sadness

Impatience

Anger

Fear

Fig. 8 *Fingers' corresponding emotions, elements and organs*



Northern red oak: acorn with cap and without. Summer branch. (Elias photos)

American beech: fruiting branch (Elias).



Red/Black Oak Group *Quercus* subgenus *Erythrobalanus*

The red oak species and black oak species and the numerous relatives in this subgenus occur only in the Americas. This group is characterized by leaves entire, toothed, or lobed and always with bristlelike tips extending beyond the margin of the leaf; acorns maturing at end of second year on the previous year's twigs, and the inner surface of the acorn shell hairy. Acorn nutmeats are nearly always bitter. Because of this, only 1 species is discussed here as edible, although most species can be utilized after the bitter properties have been removed.

Northern red oak *Quercus rubra*

Habitat: valleys, ravines, lower and mid slopes of hills and mountains. **Identification:** medium-size tree to 20 m (66 ft), rarely taller, with open, irregular crown and shallowly furrowed, checkered bark. ***Leaves*** alternate, deciduous, simple, ***10–22 cm*** (4–8.7 in) ***long,*** 6–12 cm (2.4–5 in) wide, widest above middle, ***with 7–9 moderately deep lobes,*** dull green and smooth above, paler beneath and with occasional tufts of hairs in junction of principal veins. Fruits are ***acorns on previous year's twigs, 1.2–2.5 cm (0.5–1 in) long, acorn cup*** saucer-shaped, ***enclosing about 1/4 of nut,*** cup scales thin, overlapping; nutmeat bitter. **Harvest and preparation:** Gather acorns in autumn as they turn brown and fall. Store in cool dry place or shell for immediate use. Place whole, chopped, or coarsely ground nutmeats in cloth (clean T-shirt will do) and tie with string. Place in boiling water until water turns brown, drain, add more boiling water. Repeat many times until water remains clear. In the field, place bag filled with nutmeats in clear running stream until nutmeats are no longer bitter, from 1 to several days. Spread leached acorns in pan and dry in sun or warm oven. Use whole nutmeats or prepare and use as grits or meal as described under WHITE OAK GROUP. For acorn muffins, cream ¼ cup butter with ½ cup sugar or molasses. Add alternately and blend 2 eggs, 1 cup milk, and dry mix of 1 cup acorn meal or grits, 2 cups flour, 4 tsp baking powder, ¾ tsp salt. Beat thoroughly. Bake in greased muffin pan at 200°C (390°F) for about 20 min. For pancake batter, repeat muffin recipe but add 1 more egg plus milk. For acorn coffee, roast acorn meal at 175°C (350°F) until dark and crisp, about 30 min. Use ½ cup roasted meal to 4 cups water. Combine, boil 15 min, strain, and serve.

American beech *Fagus grandifolia*

Habitat: river valleys, lower mountain slopes, mixed deciduous forests, usually in rich, moist soils. **Identification:** medium-size to tall tree with narrow to spreading, rounded crown and ***thin, smooth, light gray to bluish-gray bark.*** Leaves alternate, deciduous, simple, 6–14 cm (2.4–5.5 in) long, 2.5–7.2 cm (1–3 in) wide, broadest just below middle, sharply toothed along margin, leathery texture at maturity. Male flowers tiny, in globe-shaped, hanging heads; female flowers tiny, usually paired at or near tips of branches. ***Fruits consist of 2 triangular nuts enclosed in 2 spiny bracts, bracts 1.6–2.2 cm (0.6–1.9 in) long,***

opening in late summer to release oily nuts. **Harvest and preparation:** Gather nuts as they drop from trees following hard frost. Separate burrs from nuts by shaking and winnowing or singly by hand. Dry in open, warm area. Crack brown shells by heating in oven; remove shells by beating or rubbing in hands and winnowing. Nutmeats are edible raw. Grind and air dry nutmeats for flour; crush and boil in water; skim off excellent oil for cooking. Roast nutmeats at 160°C (320°F) 30–40 min and grind for coffee substitute. For beechnut pie, substitute 1½ cups beechnuts for pecans in PECAN pie recipe. Thoroughly whip 3 eggs. Slowly beat into them ½ cup melted butter or margarine, 1 cup white corn syrup, and ¾ cup sugar. Turn into unbaked 9-in pie shell and bake at 150°C (300°F) 35 min. Remove pie long enough to cover quickly with nuts. Return to oven, turn up heat to 175°C (350°F), and bake another 15 min. **Edible related species:** none. **Poisonous look-alikes:** none.

Allegheny chinkapin *Castanea pumila*

Also edible summer

Habitat: widespread; dry woodlands and mountain slopes or along coast in dry sandy soils. **Identification:** shrub or small tree to 8 m (26 ft) with a rounded crown and light reddish-brown bark. Twigs densely hairy when young. ***Leaves*** alternate, simple, deciduous, ***6.8–16 cm*** (2.7–6.3 in) ***long, 3.8–5 cm*** (1.5–2 in) wide, ***broadest near middle, with numerous large teeth along the margin,*** whitish and hairy beneath. Male flowers numerous on the upper ⅔ of semi-erect spikes; female flowers fewer on the lower ⅓ of flowering spike. ***Fruits are spiny burrs 3–4 cm (1.4 in) in diameter, enclosing 1, rarely 2, nuts;*** nuts broadest near the base and pointed at tip, nutmeat sweet. **Harvest and preparation:** Gather nuts as they ripen in late summer or early autumn. Separate nuts from burs and store whole, or shell, blanch, and dry nutmeats. To shell and blanch the nuts, cover with boiling water and boil until shell and skin can be easily removed. Then place nutmeats in shady place about 1 week until dry and shriveled. Store shelled and dried or unshelled nuts in porous bag in dry place. Before using nuts, soak in water for 30 min. Use chestnuts in stuffings, soups, desserts, as a vegetable, and as a coffee substitute. Nuts can be eaten directly by slitting shells and roasting over coals or in hot oven. For soup, combine 1½ cups dried ground chestnuts, 2 sliced carrots, 1 cup sliced acorn or butternut squash, 2 tbsp chopped fresh parsley, ½ tsp oregano or native plant seasonings, and 5 cups water. Cook until tender, about 40–50 min. For coffee, chop freshly shelled chestnuts, spread on foil, and roast at 190°C (375°F) until dark and dry. Grind to a powder as needed. Boil gently 28 grams (1 oz) powder per cup of water for 15 min. Strain and serve. **Related edible species:** American chestnut *(C. dentata)* produces large sweet nuts but the persistent chestnut blight has literally eliminated it from its native range. **Poisonous look-alikes:** Do not confuse poisonous horsechestnuts with true chestnuts. Horsechestnuts (*Aesculus* species) have compound (palmate) leaves and nuts with a large circular scar, and belong to the family Hippocastanaceae. Allegheny chinkapin and true chestnuts have simple leaves and belong to the beech family (Fagaceae).

Allegheny chinkapin: fruiting branch (Elias). Flowering branch (NYBG).





Washington hawthorn: unripe fruits (Elias). Flower clusters (Feldman).

Downy hawthorn: fruiting branch (Speas).



HAWTHORNS *Crataegus*

This large group of trees and shrubs contains highly variable species that are often difficult to distinguish. Nearly all of the 26 distinguishable North American species of hawthorns have edible fruits. They are mostly small spreading trees with dense branches often armed with long sharp spines. The toothed leaves may be entire, shallowly or deeply lobed. Bisexual flowers are generally white, with 5 petals and the rounded to pear-shaped fruits yellow, green, red, orange, or nearly black at maturity. Four common species are discussed on upcoming pages. **Harvest:** Most fruit ripens in autumn and may persist for several months, but some southern species, including May hawthorn *(C. aestivalis)*, have fruit ripening in late spring. The fruits vary greatly in flavor from sweet to bitter. Sample the fruits from each plant and harvest the best, but be careful of the vicious thorns. **Preparation:** Eat sweetest fruits fresh. For jelly, crush 1.4 kg (3 lb) fruit or 1 kg (2 lb) if a juicy type, cover with water, and cook until soft. Add more water if necessary. Strain juice through jelly bag. Bring 4 cups juice to boil. Unless fruits are unripe, add 1 pkg pectin, stir, add 6–7 cups sugar, stir, and bring to rolling boil. If no pectin is added, boil to 115°C (239°F). Remove from heat, skim, pour into sterilized jelly glasses, and seal. If fruits do not seem acid enough, add juice of 1 or 2 lemons. For tea, steep 2–3 tbsp crushed fruits and sprig of mint in cup of boiling water for 5–10 min. Fruits can be dried and stored for winter use. Substitute hawthorn fruits in recipes calling for rose hips. The fruits were used by Indians to some extent in pemmican. **Related edible species:** many *Crataegus* species. **Poisonous look-alikes:** none.

Washington hawthorn *Crataegus phaenopyrum*

Habitat: stream banks, old fields, openings in woodlands. **Identification:** small tree to 12 m (40 ft), with rounded, spreading crown; branches dark reddish-brown, zigzagging, ***armed with slender sharp-pointed spines 3–5 cm*** (1.2–2 in) ***long. Leaves*** alternate, simple, deciduous, 2–6 cm (0.8–2.4 in) long, 2–5 cm (0.8–2 in) wide, broadest near base, ***with 1–4 pairs of shallow lobes,*** pointed at tip, broadly rounded at base, sharply toothed along margin, dark green, shiny, smooth. ***Flowers white, attractive,*** produced in branched, spreading many-flowered clusters. ***Fruits*** are ***dry, berrylike, globe-shaped,*** 5–8 mm (0.3 in) in diameter, ***bright red.*** **Harvest and preparation:** See HAWTHORNS (preceding).

Downy hawthorn *Crataegus mollis* (syn.: *C. arnoldiana, C. canadensis, C. submollis*)

Habitat: along streams and rivers, bottomlands, lowland fields, clearings. **Identification:** small tree to 12 m (40 ft) high, with dense, wide-spreading crown; ***branches*** covered with dense white hairs when young, ***almost thornless,*** occasionally with sharp, slender dark reddish-brown spines to 5 cm (2 in) long. ***Leaves*** alternate, simple, deciduous, 3.5–10 cm (1.4–4 in) long, 3–8 cm (1.2–3.2 in) wide, usually broadest near base, sharp-pointed along margin, ***dark yellowish-green, hairy on lower surface.*** Flowers white, attractive, produced in branched, spreading clusters in spring. Fruits stalked, dry, berrylike, globe-shaped, 9–16 mm (0.4–0.6 in) in diameter, red. **Harvest and preparation:** See HAWTHORNS (preceding).

Fleshy hawthorn *Crataegus succulenta*

Habitat: along coast, hillsides, abandoned fields, usually in rocky or gravelly soils. **Identification:** shrub or small tree to 8 m (26 ft) high, with irregular, usually rounded, crown; branches stout, slightly zigzagging, gray, ***armed with frequent, stiff, slightly curving, dark reddish-brown spines*** 3–4.5 cm (1.2–1.8 in) long. ***Leaves*** alternate, simple, ***3–7 cm*** (1.2–2.8 in) ***long, 2–5.2 cm*** (0.8–2 in) ***wide,*** broadest above or below middle, ***shallowly lobed near tip, pointed*** at tip, tapering at base, ***sharply pointed*** and ***double-toothed along margin,*** dark green, shiny. Flowers white, attractive, produced in branched, spreading clusters in spring. ***Fruits*** stalked, dry, berrylike, ***globe-shaped, 0.8–1.6 cm*** (0.3–0.6 in) ***in diameter, bright red.*** **Harvest and preparation:** See HAWTHORNS (preceding).

Cockspur hawthorn *Crataegus crus-galli*

(synonyms: *C. acutifolia, C. canbyi, C. regalis, C. pyracanthoides*)

Habitat: hillsides, lower mountain slopes, river valleys, abandoned fields. **Identification:** small tree to 8 m (26 ft) high, with broad spreading, ***nearly flat-topped crown;*** branches stiff, light brown to gray, armed with stout, slender, straight to slightly curved, sharp-pointed spines. ***Leaves*** alternate, simple, deciduous, ***2–6 cm*** (0.8–2.4 in) ***long, 1–3.2 cm*** (0.4–1.3 in) ***wide, usually broadest above middle*** or near middle, ***unlobed,*** rounded to pointed at tip, gradually tapering at base, sharply toothed along upper ⅔ of margin, ***glossy, dark green. Flowers white, pink, or red,*** attractive, produced in branched, spreading clusters in spring. ***Fruits*** stalked, ***dry, berrylike,*** globe-shaped, ***0.7–1 cm*** (0.4 in) ***in diameter, dull red to green.*** **Harvest and preparation:** See HAWTHORNS (preceding).

Common persimmon *Diospyros virginiana*

Also edible winter

Habitat: rich bottomlands, especially Mississippi River Valley, margins of woodlands and fields, rocky hillsides, along fencerows and highways. **Identification:** large shrub or small to medium-size tree with thick dark gray to grayish-brown bark that forms small square blocks. ***Leaves*** alternate, deciduous, ***7–13 cm*** (2.8–5.1 in) ***long, 3.5–8 cm*** (1.4–3.2 in) ***wide,*** broadest near base or middle, entire, dark green and shiny. ***Male and female flowers on separate trees,*** produced at bases of leaves along younger branches, ***each flower tubular or urn-shaped,*** greenish-yellow to cream-white. ***Fruits are globe-shaped, 2–6 cm*** (0.8–2.4 in) ***in diameter, orange to orange-purple, fleshy,*** containing a few flattened seeds 1.2–2 cm (0.5–0.8 in) long. **Harvest:** Fruits mature in early autumn and persist on trees into early winter. Best collected after first frost when soft and skin becomes slightly wrinkled. Prior to that fruits will be very sour. To obtain many fruits, shake branches. **Preparation:** Delicious as fresh fruit. The pulp, strained to remove seeds and skin, can be used to make bread, pie, pudding, jam, even frozen for later use. See jam recipe early in book. A tea can be made from clean dried leaves. **Related edible species:** Texas persimmon *(D. texana).* **Poisonous look-alikes:** none.



Fleshy hawthorn: fruiting branch (Elias).



Cockspur hawthorn: fruiting branch (Elias).

Common persimmon: fruiting and flowering branches (Speas).



American mountain ash *Sorbus americana*

Also edible winter

Habitat: rocky slopes, seepage areas along ridges, at higher elevations. **Identification:** shrub or small tree to 9 m (30 ft) with open, rounded crown and thin, light gray smooth bark. ***Leaves alternate,*** deciduous, ***featherlike (pinnate) compound, 12–25 cm (5–10 in) long, with 9–17 leaflets, each leaflet*** 3–8 cm (1.2–3.2 in) long, lance-shaped to uniformly wide, ***finely toothed along margin,*** dull green. ***Flowers in dense, many-flowered, flat-topped clusters*** to 15 cm (6 in) across, each flower tiny, with 5 white petals. ***Fruits in large, dense clusters, persisting into winter, each fruit*** 4–8 mm (0.2–0.3 in) in diameter, ***bright orange-red, shiny,*** slightly fleshy, containing 1 or 2 seeds. **Harvest and preparation:** Fruits become palatable in winter after 1 or more freezings and are easily stripped from twigs. Edible raw but better cooked. For sauce, stew like CRANBERRIES; bring to boil 2 lb fruits and 2 cups sugar in 1 cup water, or berries plus 1 cup maple sugar (SUGAR MAPLE) and 1 cup cider. Reduce heat and simmer until berries mash easily and a drop of the sauce gels on cold plate. Pour into mold or storage jars. For pie, to sauce (above) add rind of ½ lemon and ⅛ tsp cinnamon. Line pie plate with crust, put in sauce, cover with crisscross strips of crust, leaving spaces between. Bake at 230°C (450°F) 20 min. Try basic jelly recipe with vinegar replacing about ¼ of water for sauce to serve with game. Also use regular jelly recipe. Berries keep well but must be dry for prolonged storage. **Related edible species:** European mountain ash *(S. aucuparia)*, Greene mountain ash *(S. scopulina)*, Sitka mountain ash *(S. sitchensis)*. **Poisonous look-alikes:** none.

Pecan *Carya illinoensis*

Habitat: bottomlands, rich moist soils; also extensively cultivated. **Identification:** tall tree with open round crown and thick, irregularly furrowed, dark reddish-brown bark. ***Leaves*** alternate, deciduous, ***featherlike (pinnate) compound,*** 32–52 cm (13–21 in) long with ***9–17 leaflets; leaflets*** 8–20 cm (3.2–8 in) long, 2.5–7.5 cm (1–3 in) wide, ***lance-shaped,*** coarsely toothed along margins. Male flowers in slender hanging catkins; female flowers short, inconspicuous, at tips of branches; flowers occur in early spring as leaves unfold. ***Fruits*** in clusters of 3–6, each large, uniformly wide, 3.5–5 cm (1.4–2 in) long, ***husk splitting into 4 thin sections to expose nut.*** Nuts cylinder-shaped to broadest near base, pointed at tip, light brown to reddish-brown, shell thin, meat oily, sweet. **Harvest:** Gather nuts in autumn as leaves turn and begin to fall. **Preparation:** Excellent eaten directly from shell, or use in any recipes calling for nuts. For pecan pie filling, beat 3 eggs, add ½ cup sugar, 1 cup dark corn syrup or molasses, ¼ tsp salt, 1 tsp vanilla, ⅓ cup melted butter. Spread 1 cup pecans over bottom of 9-in pie shell. Pour above ingredients over pecans and bake 10 min in 230°C (450°F) oven, then reduce heat to 175°C (350°F) and bake 35 min longer. **Related edible species:** BIG SHELLBARK HICKORY, SHAGBARK HICKORY, and MOCKERNUT HICKORY (following). **Poisonous look-alikes:** none.



American mountain ash: fruiting and flowering branches (Elias).

Pecan: summer branches and nuts with splitting husks (Elias/Dykeman).


Cultivated range
Native range

Head

A. Crown Point

This is located in the center of the crown; in the fontanelle area of an infant's skull there may still be a slight depression. The crown point is the junction of one hundred channels through which the energy of the body passes. Massage this area with both your middle fingers. This will relieve dizziness and headaches, which result from too much energy in the head. It also relieves high blood pressure and stimulates the nervous system.



Fig. 9 *Crown Point is the junction point of one hundred energy channels.*



Big shellbark hickory: immature fruits (Clawson).

Shagbark hickory: flowering and fruiting branch (Elias). Bark (Dykeman).



Big shellbark hickory *Carya laciniosa*

Habitat: deep rich soils of floodplains and bottomlands, especially of Ohio and Mississippi River valleys. **Identification:** large tree with rounded crown and ***light gray, somewhat shaggy bark. Leaves*** alternate, deciduous, featherlike (pinnate) compound, 25–60 cm (10–24 in) long, ***with 5–9 leaflets, usually 7;*** leaflets 6–25 cm (2.4–10 in) long, 3.7–12.5 cm (1.5–5 in) wide, lance-shaped to broadest near base, sharp-pointed at tip, with numerous tiny teeth along margin. Male flowers in slender hanging catkins; female flowers short, inconspicuous, at ends of branches; both produced in early spring as leaves unfold. Fruits solitary or in pairs, globe- to egg-shaped, 3.5–7 cm (1.4–2.8 in) long, thick husk splitting lengthwise into 4 parts to expose nut. ***Nut egg-shaped,*** usually ridged, ***shell thick, hard, nutmeat sweet.*** **Harvest:** Gather nuts in autumn as leaves turn and fall; PECAN (preceding) and SHAGBARK (next) nuts are superior because they have thinner shells. **Preparation:** Remove nutmeats from shells; see SHAGBARK HICKORY. Use in any nut recipes. For nut-corn pudding, combine thoroughly 1½ cups cooked corn, ½ cup shelled, dried hickory nuts, 2 tbsp nut butter or oil, 1 cup boiling water, 2 beaten eggs, 2 tbsp honey, 2 tbsp fine cornmeal, ¼ cup seeds, raisins, or edible blossoms. Pour into well-greased casserole. Sprinkle top with more hickory nutmeats. Bake in preheated 175°C (350°F) oven for 1 hr. Serve hot. See other hickory species for additional uses. Trees can be tapped in late winter for sap. Prepare syrup as with SUGAR MAPLE. **Related edible species:** PECAN, SHAGBARK HICKORY, MOCKERNUT HICKORY. **Poisonous look-alikes:** none.

Shagbark hickory *Carya ovata* (synonym: *C. carolinae-septentrionalis*)

Habitat: dry upland slopes, well-drained soils of lowlands and valleys. **Identification:** medium-size to tall tree with open rounded crown and ***light to dark gray, shaggy bark.*** Leaves alternate, deciduous, featherlike (pinnate) compound, 20–36 cm (8–14.2 in) long, ***usually with 5,*** sometimes 7, ***leaflets;*** leaflets broadest near middle or tip, 8–18 cm (3–7 in) long, 1.5–6 cm (0.6–2.4 in) wide, ***with fine, sharp-pointed teeth along margin.*** Male flowers in slender, hairy catkins 10–13 cm (4–5.1 in) long; female flowers short, inconspicuous, at tips of branches; flowers occur in spring as leaves unfold. Fruits produced singly or in 2s, egg- to globe-shaped, 3–5 cm (1.2–2 in) long, husk thick, splitting lengthwise into 4 equal parts to expose the egg-shaped, ***4-sided nuts.*** Nuts with thin shell and sweet nutmeat. **Harvest and preparation:** Gather nuts in early autumn as they fall with leaves. Crack nuts with hammer and remove meats with nutpick. For efficient extraction, crack nuts enough to identify and eliminate wormy ones. Then smash enough to loosen meats. Place pounded nutmeats in pot, cover with water, and bring to boil. Most of meats will rise and can be skimmed off if desired. Indians boiled mix slowly and skimmed oil from surface to use as butter; then meats were skimmed and mixed with potatoes or meal, or dried into cakes. Boiled mix separated from shells is nutritious soup Indians called *powcohicora*. For hickory pie, use PECAN pie recipe, but increase amount of nuts to 1½ cups. See other hickory recipes. **Related edible species:** PECAN, BIG SHELLBARK HICKORY (preceding), MOCKERNUT HICKORY (next). **Poisonous look-alikes:** none.

Mockernut hickory — *Carya tomentosa* (synonym: *C. alba*)

Habitat: ridges, hills, slopes, river valleys. **Identification:** large tree with rounded crown and dark gray, shallowly furrowed bark. ***Leaves*** alternate, deciduous, featherlike (pinnate) compound, 14–32 cm (5.5–12.6 in) long, ***with 5 or 7 leaflets; leaflets 8–22 cm (3–9 in) long, 6–12.5 cm (2.4–5 in) wide, narrow, broadest above middle,*** pointed at tip, toothed along margin. Male flowers in slender, stalked, 3-clustered catkins; female flowers small, 2–5 at tips of branches. Fruits solitary or few-clustered, globe- to egg-shaped, 4–8 cm (1.6–3.2 in) long, almost as wide, husk splitting lengthwise to expose nutmeat. ***Nut nearly rounded, often 4-sided, shell thick, hard, nutmeat sweet.*** **Harvest:** Gather nuts in autumn as leaves turn; PECAN and SHAGBARK HICKORY (preceding) are superior because of thin shells. **Preparation:** Remove nutmeats from shell; see SHAGBARK HICKORY instructions. Use any nut recipe including those for other hickories. For salad dressing, combine ½ cup ground hickory nuts, 1¼ cups vegetable oil, 3 tbsp lemon juice or STAGHORN SUMAC extract, 2 tbsp vinegar, ¼ tsp pepper, 1 chopped clove garlic. Shake well and use on salads. Tap trees in late winter for sap and prepare syrup as with SUGAR MAPLE. **Related edible species:** PECAN, SHAGBARK HICKORY, BIG SHELLBARK HICKORY. **Poisonous look-alikes:** none.

Black walnut — *Juglans nigra*

Habitat: bottomlands, floodplains, rich low mixed deciduous forest, especially in well-drained soils. **Identification:** large tree with open rounded crown and thick, deeply furrowed, light to grayish-brown to almost black bark. ***Leaves*** alternate, deciduous, ***featherlike*** (pinnate) ***compound,*** 20–60 cm (8–24 in) long, ***with 15–23 leaflets;*** leaflets 4–9 cm (1.6–3.5 in) long, 2–3.5 cm (0.7–1.4 in) wide, broadest near base to broadly lance-shaped, with numerous fine, sharp-pointed teeth along margin. Male and female flowers separate, appearing in spring. ***Fruits large, rounded, 4–6 cm*** (1.6–2.4 in) ***in diameter, with thick husk enclosing globe-shaped nut,*** nut 3–4 cm (1.2–1.6 in) in diameter, ***shell irregularly and deeply furrowed,*** thick, nutmeat 4-lobed at base, sweet. **Harvest:** Gather nuts in autumn as they fall from trees. Remove thick brown-staining husks immediately by partially crushing, then rubbing with gloved hands or scrubbing with stiff brush to remove all remaining husk material. (Indians first suspended nuts in mesh bag in running water for several days.) Allow hulled nuts to dry thoroughly before using. **Preparation:** Crack shell with hammer, rock, or vise, applying blow or pressure at right angles to seam. Use nutpick. Indians crushed shells well to obtain oil and meats. See SHAGBARK HICKORY. After boiling crushed nuts for 30 min or more, allow shells and nutmeats to settle; then skim off oil. Boil again and use sieve to skim nutmeats as they rise above shells. Remove coarse shell pieces, dry and grind nutmeats. Use oil like that of hickories. Use nutmeats in baking or grind with honey or herbs to make nut butter. Use sap under SUGAR MAPLE. For other uses, see BUTTERNUT, hickory species, and book's Introduction. **Related edible species:** BUTTERNUT, CALIFORNIA WALNUT (next), Texas black walnut *(J. microcarpa)*, Arizona walnut *(J. major)*, Hinds walnut *(J. hindsii)*. **Poisonous look-alikes:** none.



Mockernut hickory: immature fruits, male flowers, bark (Eye).

Black walnut: nearly mature fruits (Elias).





California walnut: male flowers and immature fruits (Shevock).

Butternut: nearly mature fruits (Elias).



California walnut *Juglans californica*

Habitat: stream and river banks, bottomlands, often in gravelly soils at lower elevation, usually below 1,000 m (3,200 ft). **Identification:** small to medium-size tree with open rounded crown and thick deeply furrowed dark brown to almost black bark. ***Leaves*** alternate, deciduous, ***featherlike (pinnately) compound, 15–25 cm*** (6–10 in) ***long, normally with 9–15 leaflets;*** leaflets 2.5–7.5 cm (1–3 in) long, 1–2 cm (0.4–0.8 in) broad, lance-shaped to uniformly wide, with fine sharp-pointed teeth along margin. Male flowers in slender, hanging catkins; female flowers small, 1–4 at tips of new branches, both produced in early spring as leaves unfold. ***Fruits small, globe-shaped, 1–2 cm (0.4–0.8 in) in diameter, with thin husk surrounding nut; nuts rounded, with few shallow grooves,*** shell thin, nutmeat large, sweet. **Harvest:** Gather ripe nuts in autumn as they fall from tree. Remove brown-staining hulls immediately as described for BLACK WALNUT (preceding). Air dry before using. **Preparation:** Crack shells of dried nuts and remove meats with nutpick; easier to extract than some other walnuts. For Indian method, see BLACK WALNUT instructions. For uses, see other walnuts, hickories, and the book's introductory section. **Related edible species:** BLACK WALNUT. **Poisonous look-alikes:** none.

Butternut *(Also edible summer)* *Juglans cinerea*

Habitat: bottomlands, floodplains, mixed deciduous forests. **Identification:** medium-size tree with open, broadly rounded crown and thick, deeply furrowed, light gray to light brown bark. ***Leaves*** alternate, deciduous, ***featherlike*** (pinnate) ***compound,*** 30–60 cm (12–24 in) long, ***with 11–17 leaflets;*** leaflets 5–11 cm (2–4.3 in) long, 2–6 cm (0.8–2.4 in) wide, lance-shaped to widest above middle, finely toothed along margin. Male and female flowers separate, both appearing in early spring. ***Fruits large, egg-shaped, 5–8 cm*** (2–3.2 in) ***in diameter,*** often 4-sided, husk not splitting open at maturity. Nut egg-shaped, 3–6 cm (1.2–2.4 in) in diameter, 4-ribbed, shell deeply furrowed, thick, nutmeat sweet. **Harvest:** Pick partly grown nuts in summer for pickling when needle will penetrate husk. Gather ripe nuts in autumn as they fall from trees. Remove brown-staining hulls immediately as described for BLACK WALNUTS. Dry thoroughly before using. **Preparation:** Crack like BLACK WALNUTS or hold nut in vertical position and hammer on end until well cracked. Remove nutmeats with nutpick or use Indian method described under BLACK WALNUT to prepare oil and nut butter. For pickling, scald immature nut and remove all outer fuzz. Place nuts in kettle; cover with water and boil until water discolors. Change water and continue boiling. Repeat water changing and boiling until water remains clear. Pack nuts in canning jars with 1 dill flower, 3 walnut leaflets, 1 heaping tsp pickling spices, 1 tsp salt, ¼ tsp alum. Fill jar with boiling cider vinegar and seal. Age at least 1 month. For other uses see BLACK WALNUT, hickories, and book's introductory section. **Related edible species:** BLACK WALNUT, CALIFORNIA WALNUT (preceding), Arizona walnut *(J. major)*, Hinds walnut *(J. hindsii)*, and Texas black walnut *(J. microcarpa)*. **Poisonous look-alikes:** none.

Winter

Winter is hardly the season for wild plant foraging—especially in colder climates. Aboveground, edibles are basically limited to berries that persist into winter, twig bark for tea, and the inner bark of some trees. The most nutritious plant parts are underground; these are the starch-rich roots and tubers of perennials and biennials. But, in winter, roots and tubers are difficult to locate and identify, even if there's no snow cover. Besides, digging them in frozen ground would cost you more calories than the plants would return.

What about survival foods? You can survive many days without food, provided you stay warm and reasonably dry, and drink sufficient water to prevent dehydration. If you decide to stay put until help arrives, choose or fashion a shelter you can heat with a reflected campfire. In selecting a site, consider access to firewood, water, and an open area for distress signalling. Expend as little energy as possible. If you expect a long wait, consider passive means of obtaining meat: fishing with set lines or setting snares on small-game trails. If you have a firearm, you could

watch game trails from your shelter or attempt to call predators to you by imitating the squeal of an injured rabbit.

In winter, Indians sometimes raided the nut caches of squirrels and arrowhead tubers cached by muskrats. But such raids are strenuous. Besides, getting into a muskrat's house can be a wet, cold ordeal.

Some northern Indians made the inner bark of trees their major winter food staple. Since bark stripping kills trees, today it should be done only for survival.

You can also partake of wild edibles in winter by manipulating the seasons. That is, you can feast on wild preserves you harvested earlier. Or, if you are highly dedicated, you can in autumn dig up the whole roots of dandelion, chicory, dock, and pokeweed. Then plant the roots in a deep, soil-filled container until after a hard freeze. Bring the container into a dark cellar. Watered and kept at 13°C (55°F), the roots will produce several crops of blanched, tender, and mild leaves for salads or cooking.

The plant species shown in upcoming pages provide berries you can eat raw, berries and twigs for beverage flavoring, inner bark for gruel and flour, and sap for pure water or boiling down to syrup and sugar. These plants are shown as they look in winter, though most of them are also shown elsewhere in this book. Many other winter-edible plants are difficult to locate and identify in winter and so are not described in this winter section. In some regions, edible plants normally harvested in autumn may also be gathered in early winter.

(Dykeman)

Staghorn sumac *Rhus typhina*

Also edible summer, autumn

Habitat: common; woodland margins, fencerows, roadsides, and along streams. **Identification:** shrub or small tree to 10 m (33 ft) with thick, ***densely hairy branches and twigs with large orange to olive pith.*** Leaf scars C-shaped, nearly surrounding ***bluntly conical, hairy buds.*** No end bud. ***Fruits persist into winter in dense, cone-shaped clusters 10–20 cm (4–8 in) long; each fruit berrylike, rounded, 3–5 mm (0.1–0.2 in) in diameter, densely covered with dark red hairs.*** See also p. 186. **Harvest:** Fruits ripen in late summer to autumn and have strong lemony taste. Dense hairs on fruits prevent rain from penetrating cluster and washing out all flavor, so fruits are edible although less potent in winter. **Preparation:** For beverage, steep berries, with all twigs removed, in near boiling water for at least 15 min (at least 1 cup fruit to 1 qt water). Strain through cloth, dilute and sweeten to taste. Drink hot or cold but in moderation; some people show allergic reactions such as hives and cramps. To make jelly prepare extract as for beverage. Bring to boil 4 cups extract with 1 pkg powdered pectin. Add 5 cups sugar, boil hard 1 min, remove from heat, skim, pour into sterilized jars and seal with paraffin. **Related edible species:** SMOOTH SUMAC and SQUAWBUSH, and lemonade berry *(R. integrifolia)*. **Poisonous look-alikes:** Poison sumac *(R. vernix)* has white fruits and grows in swampy areas.

Highbush cranberry *Viburnum trilobum*

Also edible autumn

Habitat: along streams, wet thickets, moist woodlands. **Identification:** ***shrub,*** upright, to 5 m (16.5 ft) high; branches upright to spreading. Twigs light reddish-brown turning ash-gray with age. Buds opposite; no end bud. ***Fruits berrylike, in clusters of 10 or more, rounded to egg-shaped, 8–14 mm (0.3–0.5 in) long, bright red, translucent*** when ripe, juicy, sour, containing a single flattened stone. See also HIGHBUSH CRANBERRY on page 224. **Harvest:** Fruits ripen in late summer but persist on shrub and become less sour in winter. Make sure your shrub is highbush cranberry and not its bitter look-alike, the introduced guelder rose, *V. opulus.* Tasting will tell you. Best to pick in fall and winter. **Preparation:** much the same as CRANBERRY *(Vaccinium macrocarpon)*, except large seeds must be removed. While cooking add lemon or orange peel shavings to eliminate bad odor of berries. For sauce cover several quarts of berries with water in a kettle. Add outer peels of 2 lemons or oranges. Bring to boil and simmer 5 min. Mash thoroughly and simmer another minute or two. Force juice and pulp through coarse strainer to remove seeds. Add 1 pkg pectin to 4 cups strained fruit, bring to boil, and add 5 cups sugar. Boil again for 1 min and seal in sterile jars or refrigerate. Before first frost, pectin may not be needed. For juice and jelly, cook as for sauce above but strain through jelly bag. For juice, dilute and sweeten to taste. For jelly, proceed with 4 cups juice as for sauce. **Related edible species:** SQUASHBERRY (next), HOBBLEBUSH, NANNYBERRY, and the cranberry tree *(V. pauciflorum)*, of Pacific Northwest. **Poisonous look-alikes:** none, but the guelder rose *(V. opulus)* has bitter fruits.



Staghorn sumac: winter fruit cluster and fruiting branches (Dykeman).

Highbush cranberry: early autumn branches (Elias). In winter berries look like this and are sweeter, though leaves will have fallen.



B. Bring Chi Energy to the Hands and Face

Inhale, contract the sexual organ, buttocks and middle of the anus. Rub the hands, clench the teeth, and put the tongue to the roof of the mouth. When the face, head, and hands are hot, breathe normally and begin to massage.

C. Knock the Head

Hit the head with the knuckles of the hand, knocking all around the head. Knocking the head lightly can help to clear your head, eliminate stubbornness and make your thinking sharper. Many of our students use this knocking of the head to release the pressures that they have from today's life of fast, advanced technology and the feeling of always having to keep up. This is especially true of those graduate students who feel a great deal of pressure and stress in keeping up with their studies. Each year students commit suicide because the pressures and stress accumulate too much in their heads, making them unable to think clearly: they start to feel everything in their society as too much pressure, which leads to worry, fear, sadness, and many, mixed emotions. The simple knocking of the head can release pressure and stress that accumulate there.



Fig. 10 *Knocking the Head*



Squashberry: early autumn branch (Clawson). In winter, berries look like this and are sweeter, though leaves will have fallen.

Sweet birch: winter treetop, trunk bark, and immature male catkins (Dykeman).



Squashberry *Viburnum edule*

Also edible summer, autumn

Habitat: along streams, wet thickets, margin of woodlands, moist low woodlands. **Identification:** ***shrub,*** often sprawling, to 2.5 m (8.1 ft) high; stems usually spreading, smooth. New branches reddish brown, older ones gray. ***Buds opposite, dark red, shiny, 2-scaled;*** both ***side and end buds present. Fruits in small clusters, berrylike, rounded,*** 6–10 mm (0.2–0.4 in) in diameter, ***red, containing a single flattened seed.*** See also SQUASHBERRY on page 226. **Harvest:** Fruits are similar to HIGHBUSH CRANBERRY but smaller and less sour. They ripen in August but persist through winter so are listed here. **Preparation:** See HIGHBUSH CRANBERRY (preceding), except juice does not require dilution for use as beverage. Makes excellent jelly. **Related edible species:** HIGHBUSH CRANBERRY. **Poisonous look-alikes:** none; the introduced guelder rose *(V. opulus)* is bitter but not toxic.

Sweet birch, Black birch *Betula lenta*

Also edible spring, summer, autumn

Habitat: forest or open woods, especially moist, north facing, protected slopes; in deep, rich, well-drained soils. **Identification:** medium-size tree with rounded crown and smooth, dark red to almost black bark. ***Broken twigs have wintergreen fragrance.*** Buds alternate, both side and end buds present, 5–7 mm (0.2–0.3 in) long, light brown, broadest near base and tapering to a point. Fruits in erect, ***brown cones, 2.5–3 cm (1–1.2 in) long, containing many tiny, winged seeds.*** Fruits mature in late summer and early fall. Cones persist into winter. ***New male flower catkins 2–3 cm (0.8–1.2 in) long at tips of twigs in winter.*** See also p. 122. **Harvest:** twigs, red inner bark, and bark of larger roots year round but best in late winter and spring. Sap in early spring, 3–4 weeks later than SUGAR MAPLE. **Preparation:** Eat inner bark fresh as emergency food, boiled like noodles, or dried and ground into flour. Dry inner bark at room temperature; store in sealed jars for later use. For tea, steep (do not boil) twigs or fresh or dried inner bark in water or, preferably, birch sap. Boiling removes volatile wintergreen oil. Sweeten to taste. For birch beer pour solution of 4 gal birch sap and 1 gal honey (or 5 gal sap and 3 lb sugar), which has been boiled 10 min, over 4 qt fine twigs in a crock. Cool, strain to remove twigs, add 1 cake yeast. Cover, ferment about 1 week, until cloudiness starts to settle. Bottle and cap tightly. For birch syrup, see instructions under YELLOW BIRCH (next). **Related edible species:** YELLOW BIRCH. **Poisonous look-alikes:** none.

Yellow birch *Betula alleghaniensis*

Also edible spring, autumn (synonym: *B. lutea*)

Habitat: rich woodlands, lower slopes and occasionally cool marshlands, usually below 1,000 m (3,300 ft) elevation. **Identification:** medium-size tree with rounded crown and peeling, ragged-edged, reddish-brown bark turning ***grayish dull yellow or yellowish-brown.*** Buds alternate, end bud absent, side buds 5–7 mm (0.2–0.3 in) long, brown, broadest near base and tapering to sharp point, somewhat sticky, with several scales. ***New male flower catkins 2–3 cm (0.8–1.2 in) long at tips of twigs.*** See also YELLOW BIRCH on page 122. **Harvest:** For syrup, tap as with SUGAR MAPLE beginning 3–4 weeks after maple sap flow begins. Drill $^{7}/_{16}$-in hole (just over 11 mm) slightly upward about 7 cm (3 in) into a mature tree. Hammer in metal or wood spile only until firmly anchored; driving spile too far may split wood. Hang bucket and wait. Flow of sap copious but sugar content lower than from maple. For use of twigs and inner bark, see SWEET BIRCH (preceding); wintergreen flavor is milder in yellow birch. **Preparation:** Boil sap in open container, outdoors, adding more as volume decreases, until evaporation leaves a viscous, molasses flavored syrup with boiling temperature of about 104°C (220°F). Store in sterilized, completely filled, sealed jars. **Related edible species:** SWEET BIRCH. **Poisonous look-alikes:** none.

American mountain ash *Sorbus americana*

Also edible autumn

Habitat: rocky slopes, seepage areas along ridges at higher elevations. **Identification:** shrub or small tree to 9 m (30 ft) with open, rounded crown and thin, light-gray smooth bark. ***Leaf scars alternate, slightly raised on twig surface.*** Buds rather conical, ***end bud 6–12 mm (0.2–0.5 in) long, curved and gummy;*** side buds smaller, flattened and pressed against twig. ***Fruits in large, dense clusters, persisting into winter,*** each fruit 4–8 mm (0.2–0.3 in) in diameter, ***bright orange-red, shiny, slightly fleshy, containing 1 or 2 seeds.*** See also AMERICAN MOUNTAIN ASH on page 240. **Harvest and preparation:** Fruits become palatable in winter after one or more freezings and become easy to strip from twigs. Edible raw but better cooked. For sauce, stew like CRANBERRIES; bring to boil 4 cups berries and 2 cups sugar in 1 cup water (or berries plus 1 cup maple sugar and 1 cup cider). Reduce heat and simmer until berries mash easily and a drop of sauce gels on a cold plate. Pour into mold or storage jars. For pie, add to sauce (above) a rind of ½ lemon and ⅛ tsp cinnamon. Line pie plate with crust, put in sauce, cover with crisscross strips of crust leaving spaces between them. Bake at 230°C (450°F) for 20 min. For jelly, see the book's introductory section. For meat sauce substitute 1 cup vinegar for 1 cup water in jelly recipe. Berries keep well; but for prolonged storage, dry them to prevent mold. **Related edible species:** European mountain ash *(S. aucuparia)*, Greene mountain ash *(S. scopulina)*, and Sitka mountain ash *(S. sitchensis)*. **Poisonous look-alikes:** none.



Yellow birch: winter immature male catkins, trunk bark, and tree (Dykeman).

American mountain ash: ripening autumn fruits (Elias). In winter, berries are brighter orange-red, and leaves will have fallen.





Sugar maple: trunk bark, winter twigs and tree. Metal spile with sap dripping into bucket. (Dykeman photos)

Sugar maple *Acer saccharum*

Also edible spring, summer

Habitat: eastern deciduous forest, common and widespread, especially at lower elevations. **Identification:** medium-size to tall ***trees*** to 30 m (98 ft) with a rounded crown, slightly ***fissured to furrowed dark-gray bark. Buds opposite,*** end and side buds present, ***light brown,*** scaly; ***end bud 6–12 mm (0.2–0.5 in) long,*** cone shaped; side buds smaller. See also SUGAR MAPLE on page 256. **Harvest:** Obtain sap from first spring flow until buds swell. Good sap flow requires freezing nights and warm days. Drill $^{7}/_{16}$-in hole (just over 11 mm) for commercial spile, slightly upward and 5–8 cm (2–3 in) into trunk. Drive spile just far enough to hold bucket, not so hard that you split wood. Collect sap and store cold until you have 25–30 gal. Collect winged seeds before fully ripe, usually from June to September. **Preparation:** Boil sap outdoors, indoors only if you like sticky walls. Use large surfaced, open pan, adding sap as water boils away. When 25 gal or so of sap has been added, continue to boil liquid until temperature is 4°C (7°F) above that of boiling water on that particular day. You may wish to boil for the last two degrees on a regulated stove. Filter syrup through milk filter into sterilized canning jars. Fill jars completely and seal. Yields about 3 qt. For maple sugar, boil 1 pt of syrup in saucepan with frequent stirring until temperature is at least 110°C (230°F). Remove from heat, cool, and stir until surface loses sheen. Pour quickly onto foil or waxed paper. When partially hardened, score into pieces with knife. Use sap fresh as a beverage, fermented to form a mild vinegar, or reduced by boiling to 25% its original volume as a base for teas. Soak seeds and remove wings. Boil until tender, drain, season, and roast for 10–15 min. **Related edible species:** Red maple *(A. rubrum)*; sap of all native maples may be used for syrup but sugar maple is best. **Poisonous look-alikes:** none; but avoid Norway maple *(A. platanoides)*, which has milky sap.

Poisonous plants

Plants that are inedible and even poisonous to varying degrees grow among the edible ones. So it's wise to learn to recognize poisonous plants, especially those that may resemble the edibles. In this section, you'll find full coverage of 20 plants that are particularly toxic, and you'll also find mention of many more related toxic species. To learn more about poisonous plants not fully covered here, consult a guidebook for your region.

Unfortunately, there are no general rules for recognition of poisonous plants. Even though birds or mammals eat a particular plant, that plant may still be poisonous to humans. For example, birds readily consume the fruits of poison ivy with no ill effects. But if you tried this, you'd be in serious trouble. Ironically, sometimes the most toxic plants are among the most beautiful. Some toxic beauties include blue flag, yellow flag, star of Bethlehem, and butterfly weed.

The more field experience you gain identifying plants, the easier you'll sort the edibles from the inedibles. Try to identify at least a few new poisonous plants each season.

Star of Bethlehem *Ornithogalum umbellatum*

Habitat: fields, grassy areas, roadsides, and open woodlands. **Identification:** ***small perennial herb*** to 35 cm (13.8 in) high, from an egg-shaped bulb 3–4 cm (1.2–1.6 in) long. ***Leaves mainly basal, long, narrow, 15–40 cm (5.9–15.7 in) long, 3–6 mm (0.1–0.2 in) wide, channeled, main vein almost white.*** Flowering stem erect, bearing several, short- to long-stalked flowers at the tip; ***each flower showy, bisexual, with 6 spreading petallike segments, white with a green stripe on lower side, each segment 1.5– 2.5 cm (0.6–1 in) long.*** Fruits are a 3-lobed, egg-shaped capsule 5–10 mm (0.2–0.4 in) long containing a few, nearly globe-shaped, black seeds. **Poisonous constituents:** Bulbs contain one or more alkaloids that have killed grazing animals. **Related poisonous species:** An introduced species, *O. nutans*, also has poisonous bulbs.

Death camass *Zigadenus venenosus*

Habitat: meadows, fields, scrubby woodlands along coast, in foothills, and coniferous forests. **Identification:** ***perennial herb from an egg-shaped bulb 1.2–2.5 cm (0.5–1 in) long, with dark outer scales;*** stems upright, 24–60 cm (9.4–24 in) high, slender, smooth. ***Leaves around base and on lower stem; basal leaves very narrow (linear), 15–30 cm (6–12 in) long, 5–10 mm (0.2–0.4 in) wide;*** stem leaves usually shorter and sheathing the stem. ***Stalked flowers numerous along an upright, unbranched, elongate cluster (lower-most flowers opening***

first), each flower with 6 petals or petallike structures, whitish, broadest near base, pointed at tip, bisexual. Fruit a small, egg-shaped capsule 1–1.5 cm (0.4–0.6 in) long, splitting open at maturity to release tiny, brown seeds. **Poisonous constituents:** All plant parts, especially the bulbs, contain alkaloids that can cause gastrointestinal distress, weakness, loss of motor function, and death. This plant and its relatives have killed many horses and cattle. **Related poisonous species:** All 12 native *Zigadenus* species should be considered *extremely* poisonous.



Star of Bethlehem: flowering plants (NYBG).

Death camass: flowering plant (NYBG).




Introduced and grows wild.

Yellow flag: flowers (Elias).



Atamasco lily: flowering plants (Speas).

Blue flag: flower (Elias).



Atamasco lily *Zephyranthes atamasco*

Habitat: floodplain and low wet woodlands, wet fields and meadows, coastal plain and lower piedmont. **Identification:** perennial herb to 30 cm (12 in) high, from a small onionlike bulb 2–3 cm (0.8–1.2 in) in diameter. ***Leaves all basal, long, narrow (linear), 20–40 cm (8–16 in) long, 4–8 mm (0.15–0.3 in) wide,*** channeled, bright-green to bluish-green, shiny. ***Flowering stalk upright, to 30 cm (12 in) high, bearing a single flower at the tip; flowers white, rarely pink, showy, 6–10 cm (2.4–3.9 in) long, funnel-shaped with the 6 lobes spreading.*** Fruits are papery to leathery, nearly globe-shaped capsules, each 3-lobed and splitting open at maturity to release the shiny, black seeds. **Poisonous constituents:** Toxic compounds in the bulbs have produced staggering, collapse, and death in grazing animals. Thus, they should be regarded as *extremely* poisonous. ☠ **Related poisonous species:** All 12 native species of *Zephyranthes* should be considered extremely poisonous.

Yellow flag *Iris pseudoacorus*

Habitat: swamps, ditches, borders of ponds, lakes, and streams; common, introduced from Europe. **Identification:** large perennial herb 0.6–1.2 m (2–3.9 ft) high, from spreading, underground stems (rhizomes). ***Leaves long,*** narrow, ***sword-shaped,*** 0.4–0.8 m (1.3–2.7 ft) long, 2–4 cm (0.8–1.6 in) wide, flattened, erect, pale green, sheathing the flowering stalks. Flowering stalks usually shorter than the leaves, bearing a ***large, showy flower;*** flowers usually ***bright yellow,*** with 3 spreading, petallike sepals each crested with brownish, irregular spots and 3 narrower, upright petals. Fruits are elongate, slightly angled capsules 5–10 cm (2–4 in) long, splitting open lengthwise to release the seeds. **Poisonous constituents:** leaves and roots; see BLUE FLAG (next). **Related poisonous species:** All native and introduced species of irises should be considered poisonous. ☠

Blue flag *Iris versicolor*

Habitat: wet meadows, ditches, swamps, marshes, along ponds and streams, native. **Identification:** ***large perennial herb*** to 1 m (3.3 ft) high, ***from thick, spreading, underground stems*** (rhizomes). ***Leaves long, narrow, sword-shaped,*** 0.4–1 m (1.4–3.3 ft) long, 1–3 cm (0.4–1.2 in) wide, flattened, erect, pale green to grayish-green, sheathing the stalks. Flowering stalks with 1 to 3 large, showy flowers; ***flowers bluish-purple to violet,*** with 3 broadly spreading, petallike sepals with conspicuous white veins and yellowish near base, petals 3, erect, narrow, ¼ to ½ as long as sepals. ***Fruits are elongate, 3-angled capsules 3.4–5.6 cm*** (1.4–2.2 in) ***long.*** **Poisonous constituents:** Leaves and roots are toxic and can cause an inflammation of the mucous membrane of the stomach and intestine. Most grazing animals avoid wild irises, but calves have been fatally poisoned by them. **Related poisonous species:** All native and introduced species of irises should be considered poisonous. ☠

D. Hold your Breath to Increase Chi Flow

Holding your breath will increase the Chi flow to the face. The head has many channels that join in the skull, especially in the crown point.

E. Scalp

Prepare your hands, head and scalp by warming up. Using both hands like a comb, press hard and move slowly, massage the scalp, going straight back from the hairline to the base of the skull. As you do this, mentally direct your energy from the back of the skull to your feet. Repeat 6-9 times. Massage more in any places in which you feel pain, until the pain goes away.



Fig. 11 *Massaging the Scalp*

Common buttercup *Ranunculus acris*

Habitat: yards, fields, clearings, and other disturbed sites. **Identification:** ***slender perennial herb*** to 1 m (3.3 ft) high, from a short, thick underground stem (rhizome); stem upright, branched, usually with spreading hairs. ***Basal leaves rounded in outline, 4–10 cm (1.6–3.9 in) across, deeply 5–7 lobed,*** each lobe coarsely toothed or with narrow lobes, softly hairy, with long leafstalks; stem leaves similar to other leaves except smaller and gradually becoming stalkless. Flowers several in a branched, open, spreading cluster; ***each flower with 5 bright glossy, yellow to whitish petals*** 7–14 mm (0.25–0.5 in) long, broadest near the tip. Fruits are clusters of flattened, broad, beaked, thin-walled nuts about 2–3 mm (about 0.1 in) long. **Poisonous constituents:** Leaves and stems are bitter tasting, possibly due to oils. These oils can cause abdominal pains from an irritated stomach and intestines. Fresh buttercups have caused diarrhea and blindness in grazing animals. **Related poisonous species:** All native species of buttercups contain toxic or otherwise irritating oils and should not be eaten.

Jimson weed *Datura stramonium*

Habitat: disturbed sites and waste grounds, old fields, roadsides, barnyards. **Identification:** ***coarse annual herb*** to 1.5 m (5 ft) high, from a short taproot; stems upright, branched, usually smooth. ***Leaves broadest near the base, 8–16 cm (3.2–6.4 in) long, 4–12 cm (1.6–4.7 in) wide, coarsely and irregularly large-toothed along the margin. Flowers large, 5–8 cm (2–3.1 in) long, showy, white to light purple, upright,*** produced singly on upper stem; petals fused and narrowly funnel-shaped, the lobes spreading, with a heavy fragrance. ***Fruits upright, egg-shaped capsules 3–5 cm (1.2–2 in) long, usually with short spines,*** splitting open along 4 valves to release dark pitted seeds. **Poisonous constituents:** All plant parts, including seeds, are poisonous. Alkaloids will cause impaired vision, thirst, delirium, unpredictable movements, possibly coma and death. **Related poisonous species:** All *Datura* species.

May apple *Podophyllum peltatum*

Habitat: rich and open woodlands, wet fields and meadows, pastures, occasionally roadsides. **Identification:** attractive perennial herb to 50 cm (20 in) tall, from a fleshy, spreading, underground stem (rhizome); stem single, short, producing single or paired leaves and single blossom between. ***Leaves large, nearly circular in outline, 15–40 cm (5.9–15.7 in) in diameter, deeply 5–9 parted, margins with a few coarse teeth or lobes; leafstalk attached to center of blade.*** Flower somewhat showy, cup-shaped, with 6–9 white petals, each 3–5 cm (1.2–2 in) wide, produced on a nodding stalk. ***Fruit an egg-shaped, fleshy, yellow (rarely red) berry 2.5–5 cm (1–2 in) long,*** containing several seeds. **Poisonous constituents:** Leaves and particularly the roots contain a resinous compound known as podophyllin that can cause violent cathartic reactions. Consumption of small quantities will produce severe gastric upset and vomiting. Death may occur from larger quantities. The fleshy pulp of the fruit is edible, although the seeds should not be eaten. See MAY APPLE on page 140. **Related poisonous species:** none in North America.



Common buttercup: flowering plants (NYBG).


Introduced and
grows wild.
Widespread.

Jimson weed: fruiting branch after frost (Dykeman).

May apple: plants in early spring and flowering plant in May (NYBG).





Horse nettle: flower and immature fruits, above (NYBG).







White hellebore: young plant, upper left (Elias). Top half of flowering plant, left (NYBG).

Yellow sweetclover: flower clusters, bottom left. Flower stalk, below. (NYBG photos)


Introduced and grows wild. Widespread.



Horse nettle *Solanum carolinense*

Habitat: disturbed sites, fields, vacant lots, roadsides, and sandy waste areas. **Identification:** coarse perennial herb to 1 m (3.3 ft) high, from spreading underground stems (rhizomes); ***stem and leaves with branched hairs and slender spines. Leaves*** alternate, simple, broadest near base, 6–12 cm (2.4–4.7 in) long, 3–6 cm (1.2–2.4 in) wide, ***coarsely and irregularly large-toothed along margin, rough to touch.*** Flowers few on elongated terminal cluster; ***each flower white to light purple, 2–3 cm (0.8–1.2 in) across,*** five-parted petals spreading and even bending backward, broadest near base. ***Fruit a yellow fleshy berry*** 1–1.6 cm (0.4–0.6 in) in diameter, smooth. **Poisonous constituents:** Leaves and fruits contain the alkaloid solanine, which can cause vomiting, nausea, abdominal pains, and other gastrointestinal problems. **Related poisonous species:** Many species of the genus *Solanum* contain the solanine alkaloid in varying amounts. Among species to avoid are European nightshade *(S. dulcamara)*, black or deadly nightshade *(S. nigrum)*, and silverleaf nightshade *(S. elaeagnifolium)*. ☠

White hellebore, False hellebore *Veratrum viride*

Habitat: wetlands, swamps, floodplains, near streams and rivers, low wet sites in woodlands. **Identification:** ***large perennial herb*** to 2 m (6.6 ft) high, from thick, fibrous roots; stems upright, stout, unbranched. ***Leaves*** numerous along stem, ***broadest near base or middle, 15–32 cm (5.9–12.6 in) long, about half as wide,*** entire along margin and pointed at tip, nearly stalkless and almost clasping stem, with conspicuous, slightly sunken ribs. ***Flowers numerous in large, erect, branched clusters*** 20–50 cm (7.8–19.7 in) high, hairy; each flower yellowish-green, with 6 spreading, petallike segments. Fruits are egg-shaped capsules 1.8–2.6 cm (0.7–1 in) long, containing numerous seeds. **Poisonous constituents:** Several alkaloids from white and other hellebores have been used in medicines and insecticides. While all plant parts contain alkaloids, the roots concentrate them. Eating this plant can cause depressed heart activity, headaches, a burning sensation in the mouth and throat, and prostration. **Related poisonous species:** All 12 native *Veratrum* species should be considered poisonous. ☠

Yellow sweetclover *Melilotus officinalis*

Habitat: disturbed sites and waste areas, roadsides, fencerows, old fields; introduced weed from Europe and Asia. **Identification:** biennial herb to 2 m (6.6 ft) high, stems sparingly branched and weakly upright, usually smooth. ***Leaves compound, composed of three leaflets (trifoliolate);*** leaflets broadest near or above middle, 1.2–2.5 cm (0.5–1 in) long, 5–15 mm (0.2–0.6 in) wide, finely toothed along margin, greenish-yellow, usually smooth; leafstalks with conspicuous leaflike bract (stipule) at junction of stalk and stem. ***Flowers numerous on slender, elongated clusters 4–12 cm (1.6–4.7 in) long, each flower yellow, resembling tiny pea blossom.*** Fruits are egg-shaped pods 2–4 mm (0.1–0.2 in) long, smooth, stalked. **Poisonous constituents:** Improperly dried sweetclover will easily mold and in the process produce coumarin, an anticoagulant that can cause severe internal bleeding and death. Moldy sweetclover mixed in hay has killed many cattle. Thus, avoid this plant when gathering green leafy edibles. **Related** ☠



Pokeweed: flower cluster (NYBG). Fruit cluster with immature fruits at tip, bottom third; ripe fruits, middle; and stalks after fruits have fallen, upper third (Crow).



Dogbane: flowering branch (NYBG).

Butterfly weed: flowering plant top and fruit capsules (NYBG).



poisonous species: Also introduced from Europe, white sweetclover *(M. alba)* is equally dangerous.

Pokeweed *Phytolacca americana*

Habitat: woodland margins, disturbed sites, waste ground, roadsides, fencerows. **Identification:** ***large, perennial herb*** to 3 m (9.8 ft) tall with thick, fleshy roots; stems branched, upright, smooth, ***with disagreeable odor when broken.*** Leaves alternate, 9–30 cm (3.5–11.8 in) long, 3–12 cm (1.2–4.7 in) wide, broadest near base, pointed at tip, entire along margin; leafstalks to 5 cm (2 in) long. ***Flowers greenish to white, produced in narrow, elongate clusters*** (racemes); each flower 2–4 mm (0.1 in) long, petals absent. ***Fruits are 5–12-parted berries, wider than long, 6–10 mm (0.2–0.4 in) in diameter, green turning purplish-black at maturity.*** **Poisonous constituents:** Toxins are more prevalent in mature leaves, stems, and particularly in roots than in young growth and berries. Diarrhea, vomiting, cramps, sweating, reduced breathing capacity, or even death can occur from eating this plant. You can eat young cooked shoots if you discard the cooking water. See also POKEWEED on page 96. **Related poisonous species:** none. There is only one species of pokeweed in North America. ☠

Dogbane *Apocynum androsaemifolium*

Habitat: open woodlands, margins of woodlands, fields, roadsides, usually drier sites. **Identification:** ***perennial herb*** to 50 cm (19.7 in) high; stems upright, branching, ***with milky juice in all parts. Leaves opposite, broadest near base to almost uniformly wide, 4–8 cm (1.6–3.2 in) long, 2–4.5 cm (0.8–1.8 in) wide,*** entire along margin, pointed at tip, dark green above, hairy beneath, sometimes drooping, with slender leafstalk. Flowers several in branched, round-topped clusters at top or upper part of stems; each flower bell-shaped, 5–10 mm (0.2–0.4 in) long, white to pink, 5-parted, spreading to drooping. ***Fruits are narrow, cylindrical, capsulelike pods 6–18 cm (2.4–7 in) long, slender pointed at tip, containing numerous small seeds, each tipped with long silky hairs.*** **Poisonous constituents:** All plant parts contain resins and glycosides capable of affecting the cardiovascular system of mammals. **Related poisonous species:** All of the 6 or 7 native species of dogbane *(Apocynum)* contain milky sap and probably the glycosides. Thus, all should be considered poisonous. ☠

Butterfly weed *Asclepias tuberosa*

Habitat: fields, meadows, prairies, open woodlands, margins of woodlands. **Identification:** perennial herb, upright, 30–80 cm (11.8–31.5 in) tall; stems single or branched, stout, hairy. ***Sap not milky, leaves alternate on stems and opposite on branches,*** variable in shape but often very narrow and widest near base or tip, 5–10 cm (2–4 in) long, 0.4–2.5 cm (0.1–1 in) wide, pointed at tip, ***usually without leafstalk,*** hairy, especially beneath. ***Flowers produced in showy, branched, flat-topped clusters;*** each flower ***orange to red or yellow,*** 5-parted, petals (corolla) deeply lobed. Fruit a dry, narrowly egg-shaped capsule 8–14 cm (3.1–5.5 in) long, splitting open only along 1 side to release tiny, flattened seeds tipped with numerous, long, silky hairs. **Poisonous constituents:** Plant ☠

parts contain some glycosides, alkaloids, and resinoids that can cause weakness, staggering, and even seizures. The various species of *Asclepias* have killed sheep, cattle, horses, and goats. **Related poisonous species:** All 30 native species should be considered potentially poisonous.

Poison hemlock *Conium maculatum*

Habitat: disturbed sites such as fencerows, roadsides, stream and river banks, old fields and vacant lands; introduced from Europe. **Identification:** ***large, biennial herb*** to 3 m (9.9 ft) high, from large, white, carrotlike taproot; ***stems*** upright, branching, purple-spotted, hollow, ***smooth. Leaves basal,*** repeatedly branched, irregularly divided and highly dissected, ***resembling parsley leaves,*** broadly triangular in outline, smooth, dark green, ***with odor of parsnips when crushed.*** Tiny ***white flowers*** produced ***in*** compound, ***flat-topped clusters (umbels)*** 4–8 cm (1.6–3.1 in) wide; flower cluster stalks 4–10 cm (1.6–3.9 in) long. Fruits dry, egg-shaped, 3–4 mm (0.1 in) long, flattened on inner surface, conspicuously ribbed, grayish-green. **Poisonous constituents:** All plant parts, especially the stem, leaves, fruits, and root are extremely poisonous. The toxic alkaloids cause nervousness, trembling, reduced heartbeat, coma, and even respiratory failure. **Related poisonous species:** A related genus, *Cicuta,* contains several species, commonly called WATER HEMLOCK (next), which are also extremely poisonous.

Water hemlock *Cicuta maculata*

Habitat: wet sites such as swamps, stream and river banks, ditches and bottomlands. **Identification:** ***large biennial or perennial herb*** to 2 m (6.6 ft) high, from one to a cluster of several, thick, fleshy, tuberlike roots; stems upright, branched, often purple spotted, smooth, exuding yellow liquid when cut. ***Leaves large,*** bi- or tripinnately compound on lower stem, upper stem leaves less dissected, leaf segments usually 4–8 cm (1.6–3.1 in) long, 0.5–3 cm (0.2–1.2 in) wide, toothed, smooth, ***with odor of raw parsnips when crushed. Small white flowers numerous in large, compound, flat-topped clusters (umbels).*** Fruits brown, dry, egg-shaped, 3–4 mm (0.15 in) long, with conspicuous ribs. **Poisonous constituents:** All parts of this plant are extremely poisonous. A resinlike cicutoxin causes severe abdominal pains, excessive salivation, vomiting within minutes of consumption, and can cause death. One of the most deadly poisonous North American plants! **Related poisonous species:** All 10 native species of *Cicuta* are extremely poisonous. Also see POISON HEMLOCK (preceding).





Poison hemlock: flowering stalks (Speas).

Water hemlock: flowering stalk (NYBG).

Introduced and
grows wild.
Widespread.





Southwestern coral bean: seeds and dried pods, flower cluster, and fruiting plant (Bernard).

American yew: mature fruits (Bogel). Fruiting branches (NYBG).



Southwestern coral bean *Erythrina flabelliformis*

Habitat: canyons, washes, desert grasslands, open oak woodlands. **Identification:** large spiny shrub or small tree to 5 m (16.4 ft); ***stems leafless except in summer,*** thick, brittle, armed with short spines. ***Leaves alternate, featherlike (pinnately) compound with 3 leaflets, the leaflets broadly triangular*** and tapering to a point, 2.5–7.5 cm (1–3 in) long, 4–8.7 cm (1.5–3.5 in) wide, grayish green; main leafstalk long, armed with several short, hooked spines. ***Flowers in large, showy clusters usually in spring, each narrow, elongated, pea-shaped, with 5 bright red to scarlet petals.*** Fruits are long, leathery pods 10–25 cm (4–10 in) long, constricted between the seeds; seeds hard, bright red, 1–2 cm (0.4–0.8 in) long. **Poisonous constituents:** Seed wall contains highly poisonous alkaloids that can cause death, even when consumed in small amounts. The seeds are sometimes used to make necklaces, which some wearers unfortunately have played with between their teeth. **Related Poisonous Species:** All species of *Erythrina* are poisonous. Eastern coral bean *(E. herbacea)* is native to the Coastal Plain from North Carolina to Texas. ☠

American yew *Taxus canadensis*

Habitat: rich woodlands, pine forests, bogs, thickets. **Identification:** ***shrub, usually low, spreading and straggly,*** occasionally upright, up to 2 m (6.6 ft) high, branches turning reddish-brown with age. ***Leaves spirally arranged and spreading in 2 ranks along stems, narrow (linear), 1–2 cm (0.4–0.8 in) long, about 2 mm (0.1 in) wide, abruptly fine-pointed at tip, dark yellowish-green above, with 2 pale-green bands beneath,*** leafstalk short. Flowers tiny cones, either male or female. ***Fruits consist of a hard, dark, egg-shaped seed about 1 cm (0.4 in) long, enclosed in bright red to reddish-orange, fleshy disc.*** **Poisonous constituents:** Leaves and seeds contain one or more alkaloids called taxine, which can cause sudden death in people as well as horses and cattle. The fleshy red disc around the seed is edible but is better avoided because of the highly toxic seeds. **Related poisonous species:** Leaves and seeds of all species of yew *(Taxus)* are extremely poisonous. The introduced English yew *(T. baccata)* and the Japanese yew *(T. cuspidata)* are widely planted as ornamentals. ☠

F. Crest

Using your thumbs, massage the crest (the edge) at the base of the skull until you feel no pain there. This will help you reduce headaches and eye aches and will increase vision. This place in Tao tradition is called the Pool of Wind which tends to collect the “evil wind”, the major cause of all the pain in the senses.



Fig. 12 *Crest - Edge of the Skull*



***Fig. 13** Go straight back from the hairline to the base of the skull.*

Poison ivy

Toxicodendron radicans
(synonym: *Rhus radicans*)

Habitat: woodland margins, pastures, streams and river banks, fencerows, and disturbed sites. **Identification:** low shrub or vine, often climbing, with hairy, light-brown twigs. ***Leaves*** alternate, deciduous, ***compound of three leaflets*** (trifoliolate), leaflets broadest near base, 10–16 cm (3.9–6.3 in) long, 5–10 cm (2–3.9 in) wide, pointed at tip, ***entire or with a few coarse teeth along margin,*** yellowish-green, dull, often smooth, ***leafstalks reddish near junction with blade.*** Plants either male or female. Tiny male flowers produced in elongated, branched clusters 5–10 cm (2–3.9 in) long on new growth; small female flowers produced in smaller branched clusters 4–6 cm (1.6–2.4 in) long. ***Fruits are rounded,*** 4–6 mm (0.1 in) in diameter, ***creamy white,*** smooth, ***produced in clusters like grapes.*** **Poisonous constituents:** All parts of the plant have an oily resin containing urushiol. Contact with urushiol can cause minor to severe dermatitis, consisting of a rash and blisters. This affliction can be serious and most uncomfortable in the mouth, throat, and nasal passages as a result of eating berries or breathing smoke produced from burning plants. **Related poisonous species:** Poison oak *(Rhus toxicodendron)*, of sandy soils, pine forest, or barrens in the eastern U.S., and *Rhus diversiloba,* also called poison oak, of the Pacific coastal states, both contain oily resin capable of producing dermatitis like that caused by poison ivy.

Ohio buckeye, Horsechestnut

Aesculus glabra

Habitat: woodlands, hillsides, especially riverbottoms and stream banks. **Identification:** broad spreading tree with open, rounded crown and dark-brown, deeply furrowed bark. ***Leaves opposite,*** deciduous, ***hand-shaped compound*** (palmate) ***with 5 or 7 leaflets,*** leaflets usually widest near middle, 10–15 cm (4–6 in) long, 3.5–6 cm (1.4–2.4 in) wide, pointed at tip, finely toothed along margin, yellowish-green, leafstalks long. Flowers produced in large, erect clusters 12.5–15 cm (5–6 in) long, pale yellowish green, with 5-lobed calyx, 4 petals sometimes with red stripes. ***Fruits a leathery, 3-parted capsule 2.5–5 cm*** (1–2 in) ***long, with short blunt spines on outer surface*** of husk, ***containing 1 or 2 large, shiny, dark reddish-brown seeds.*** **Poisonous constituents:** All plant parts, especially the large seeds, contain aesculin, a glycoside. If ingested, this toxin can cause vomiting, stupor, twitching, paralysis, and possibly even death. Seeds of buckeyes or horsechestnuts resemble those of edible chestnuts. **Related poisonous species:** All native species of the buckeye genus *(Aesculus)* should be considered poisonous. Compounds from some species have been used medicinally. A coumarin glycoside, esculoside, obtained from the European horse chestnut *(A. hippcastanum)*, has been used to treat hemorrhoids.



Poison ivy: immature plant with bronze leaves and fruiting branch with shiny green leaves and light-green female flower clusters (NYBG).

Ohio buckeye: Fruiting branch (Clawson).



Nutritional Contents of Selected Foods

Per 100 gram portion (about 3.5 ounces)

		ENERGY BUILDING BLOCKS			MINERALS					VITAMINS				
Food	*Calories*	*Protein (g)*	*Fat (g)*	*Carbohydrates (g)*	*Calcium (mg)*	*Phosphorus (mg)*	*Iron (mg)*	*Sodium (mg)*	*Potassium (mg)*	*Vitamin A (IU)*	*Thiamine (mg)*	*Riboflavin (mg)*	*Niacin (mg)*	*Ascorbic acid (mg)*
Apples, raw	58	0.2	0.6	14.5	7	10	0.3	1	110	90	.03	.02	.1	4
Asparagus, raw	26	2.5	0.2	5.0	22	62	1.0	2	278	900	.18	.20	1.5	33
Bananas, raw	85	1.1	0.2	22.2	8	26	0.7	1	370	190	.05	.06	.7	10
Beans, lima, boiled, and drained	111	7.6	0.5	19.8	47	121	2.5	1	422	280	.18	.10	1.3	17
Beef, broiled	207	32.2	7.7	0.0	13	261	3.9	60	370	10	.09	.25	6.4	0
Beverages: Beer	42	0.3	0.0	3.8	5	30	tr	7	25	0	tr	.03	.6	0
Wine	85	0.1	0.0	4.2	9	10	0.4	5	92	0	tr	.01	.1	0
Blackberries, raw	58	1.2	0.9	12.9	32	19	0.9	1	170	200	.03	.04	.4	21
Bread, whole wheat	243	10.5	3.0	48.0	99	228	2.3	527	273	tr	.26	.12	2.8	tr
Broccoli, raw	32	3.6	0.3	5.9	103	78	1.1	15	382	2,500	.10	.23	.9	113
Carrots, raw	42	1.1	0.2	9.7	37	36	0.7	47	341	11,000	.06	.05	.6	8
Cauliflower, raw	27	2.7	0.2	5.2	25	56	1.1	13	295	60	.11	.10	.7	78
Chicken, white meat, roasted	182	32.3	4.9	0.0	11	272	1.3	66	422	110	.08	.10	11.8	0
Chicory greens, raw	20	1.8	0.3	3.8	86	40	0.9	0	420	4,000	.06	.10	.5	22
Cucumbers, raw	15	0.9	0.1	3.4	25	27	1.1	6	160	250	.03	.04	.2	11
Dandelion greens, raw	45	2.7	0.7	9.2	187	66	3.1	76	397	14,000	.19	.26	.0	35
Dock & sheep sorrel, raw	28	2.1	0.3	5.6	66	41	1.6	5	338	12,900	.09	.22	.5	119
Eggs, raw or boiled	163	12.9	11.5	0.9	54	205	2.3	122	129	1,180	.11	.30	.1	0
Grapes, raw	69	1.3	1.0	15.7	16	12	0.4	3	158	100	.05	.03	.3	4
Hazelnuts	634	12.6	62.4	16.7	209	337	3.4	2	704	0	.46	.00	.9	tr
Hickorynuts	673	13.2	68.7	12.8	tr	360	2.4	0	0	0	.00	.00	.0	0
Jerusalem artichoke, raw, fresh	7	2.3	0.1	16.7	14	78	3.4	0	0	20	.20	.06	1.3	4

Nutritional Contents of Selected Foods (continued)

Food	*Calories*	*Protein* (g)	*Fat* (g)	*Carbohydrates* (g)	*Calcium* (mg)	*Phosphorus* (mg)	*Iron* (mg)	*Sodium* (mg)	*Potassium* (mg)	*Vitamin A* (IU)	*Thiamine* (mg)	*Riboflavin* (mg)	*Niacin* (mg)	*Ascorbic acid* (mg)
Lamb's-quarters (Pigweed), raw	43	4.2	0.8	7.3	309	72	1.2	0	0	11,600	.16	.44	1.2	80
Leeks, bulb & lower leaf, raw	52	2.2	0.3	11.2	52	50	1.1	5	347	40	.11	.06	.5	17
Lettuce, raw	14	1.0	0.2	2.9	35	26	2.0	9	264	970	.06	.06	.3	8
Milk, cows, whole	65	3.5	3.5	4.9	118	93	tr	50	144	140	.03	.17	.1	1
Mustard greens, raw	31	3.0	0.5	5.6	183	50	3.0	32	377	7,000	.11	.22	.8	97
Onions, bulb, raw	38	1.5	0.1	8.7	27	36	0.5	10	157	tr	.03	.04	.2	10
Papaw, raw	85	5.2	0.9	16.8	0	0	0.0	0	0	0	.00	.00	.0	0
Parsnips, raw	76	1.7	0.5	17.5	50	77	0.7	12	541	30	.08	.09	.2	16
Peanuts, with skins	564	26.0	47.5	18.6	69	401	2.1	5	674	0	1.14	.13	17.2	0
Pears, raw	61	0.7	0.4	15.3	8	11	0.3	2	130	20	.02	.04	.1	4
Peas, green, immature, raw	84	6.3	0.4	14.4	26	116	1.9	2	316	640	.35	.14	2.9	27
Pecans	687	9.2	71.2	14.6	73	289	2.4	tr	603	130	.86	.13	.9	2
Persimmons, raw	127	0.8	0.4	33.5	27	26	2.5	1	310	0	.00	.00	.0	66
Plums, raw	66	0.5	0.0	17.8	18	17	0.5	2	299	300	.08	.03	.5	0
Potatoes, raw	76	2.1	0.1	17.1	7	153	0.6	3	407	tr	.10	.04	1.5	20
Prickly-pears, raw	42	0.5	0.1	10.9	20	28	0.3	2	166	60	.01	.03	.4	22
Purslane, leaves & stems, raw	21	1.7	0.4	3.8	103	39	3.5	0	0	2,500	.03	.10	.5	25
Raspberries, raw	57	1.2	0.5	13.6	22	22	0.9	1	168	130	.03	.09	.9	25
Rice, brown, raw	360	7.5	1.9	77.4	32	221	1.6	9	214	0	.34	.05	4.7	0
Salsify, fresh, raw	13	2.9	0.6	18.0	47	66	1.5	0	380	10	.04	.04	.3	11
Strawberries, raw	37	0.7	0.5	8.4	21	21	1.0	1	164	60	.03	.07	.6	59
Sunflower seed kernels, dry	560	24.0	47.3	19.9	120	837	7.1	30	920	50	1.96	.23	5.4	0
Walnuts, black	628	20.5	59.3	14.8	tr	570	6.0	3	460	300	.22	.11	.7	0
Watercress, leaves & stems, raw	19	2.2	0.3	3.0	151	54	1.7	52	282	4,900	.08	.16	.9	79

Source: *Handbook of the Nutritional Contents of Foods,* U.S. Department of Agriculture, Dover Publications Inc., New York 1975.

g = grams, mg = milligrams, IU = international units, tr = trace

General Index

Autumn, edibles characteristics of, 12, 208
Baking soda (tenderizer), 13
Beverages, 14–15
Bitterness. *See* Toxicity
Brambles, blackberries, raspberries, harvest and preparation of, 178–179

Coffee substitutes, 15
Currants and gooseberries, harvest and preparation of, 168–169
Dicots. *See* Monocots and dicots
Diet and wild edibles, 27
Flour substitutes, 14, 22
Food value of wild edibles, 274–275
Foraging for plants, 10–11
Fruit
  drying, 15–16
  handpicking, 15
  solar drying, 16

Gooseberries. *See* Currants
Grains, nuts, and seeds
  as flour substitute, 22
  winnowing methods for, 22
Grapes. *See* Wild grapes

Harvest and preparation of plants, 12–22
  boiling, 12–13
  edibility through growing season, 12
  handpicking, 12, 15
  pit-roasting, 14
  roots and tubers, 13–14
  shoots and leaves, 12–13
Harvest dates, regional calendar for, 12
Hawthorns, harvest and preparation of, 237

Indian: wild food harvesting, 22–24; food preparation, 23–24; survival techniques, 249

Jams, 18–20
  without pectin, 20
  recipes (table), 18–19
  uncooked, 20
Jellies, 16–18
  and pectin, 16
  recipes (table), 17

Leaves. *See* Plant parts, aboveground

Maple sugaring, 24
Mapping populations of edible plants, 208
Mast crop, 208
Medicinal use of plants, 15
Monocots and dicots, contrasting features of (table), 6

Nutrition and wild edibles
  carbohydrates, 26
  fats, 26
  Nutritional Contents of Selected Foods (appendix), 274–275
  vitamins and minerals (table), 26–27
Nuts. *See* Grains, nuts, and seeds

Overharvesting, 9, 208

Pemmican (recipe), 169
Pies, 20–22
  recipes (table), 20–21
Plant guides, 28
Plant habitats, 10–11
Plant names, 6
Plant parts, aboveground, 12
Plant parts, underground, 13–14
  difficulty in harvesting, 13, 248
  as trail nibbles, 14
Plant reproduction, 7–8
Plants, defensive structures of, 8–9
Plants, introduced, 9–10

Plant taste, factors influencing, 9
Poisonous plants, recognition of, 258
Potato substitutes, 13
Powcohicora, 243

Raspberries. *See* Brambles, blackberries, raspberries
Rennet substitute, 79
Roots. *See* Plant parts, underground
Roses, harvest and preparation of, 220–221
Sap, use of in beverages, 16, 249
Seeds, dispersal of, 9. *See also* Grains, nuts, and seeds
Shoots. *See* Plant parts, aboveground
Spring, edibles characteristics of, 11, 56
Stone grinding, 24
Summer, edibles characteristics of, 11, 126
Survival foods, 248–249

Tea from wild edibles, 14–15
Toxicity, removal of, 9
  by boiling, 12–13
  by drying, 14
Vitamin C, 14
Vitamins
  and baking soda, 13
  loss and retention of in cooking, 12, 14
White Oak Group, harvest and preparation of, 228
Wild grapes, harvest and preparation of, 214–215
Winnowing. *See* Grains, nuts, and seeds
Winter, edibles characteristics of, 248
Winter foraging, 12, 249

Index to plant names

Bold face type is used for common names and pages where you'll find plants both described and illustrated. ***Boldface italic*** is used for scientific names of described and illustrated plants. The thinner typeface (normal and *italic*) is used for plants mentioned incidentally, for example, when they resemble a plant covered in full detail.

Acer platanoides, 126, 257
Acer rubrum, 257
Acer saccharum, **125, 257**
Acorus calamus, **133**
Aesculus species, 234
Aesculus glabra, **272**
Aesculus hippocastanum, 272
Agave species, 134
Alaskan knotweed, 99, 155
alfilaria, 109
Allegheny chinkapin, 234
Alliaria officinalis, **85**
Allium canadense, **61**
Allium cernuum, **58**
Allium tricoccum, **61**
Allium vineale, 58
alpine bearberry, 159
alpine bistort, 155
alpine smartweed, 155
alpine spring beauty, 92
Althaea officinalis, **146**
Amaranthus hybridus, **72**
Amaranthus retroflexus, **72**
Amelanchier, **207**
Amelanchier alnifolia, **207**
Amelanchier arborea, **207**
Amelanchier florida, **207**
Amelanchier laevis, **207**
American barberry, 219
American beech, 233
American bistort, 155
American brooklime, 144
American chestnut, 234
American elder, 190
American hackberry, 220
American hazelnut, 173
American lotus, 210
American mountain ash, 240, 254
American plum, 203
American yew, 271
Apios americana, **149**
Apios priceana, 149
Apocynum androsaemifolium, **267**
Arctium lappa, 112
Arctium minus, **112**
Arctostaphylos alpina, 159
Arctostaphylos uva-ursi, **159**
Arizona walnut, 244, 247
arrowhead, 213
artichoke, Jerusalem, 210
Asclepias speciosa, 106
Asclepias syriaca, **106**
Asclepias tuberosa, **267**
Asimina parviflora, 198
Asimina triloba, **198**
asparagus, 62
Asparagus officinalis, **62**
Astragalus species, 149
atamasco lily, 261

Barbarea verna, 99
Barbarea vulgaris, **99**
barberry: American, 219; **common, 219;** red-fruited, 219
basswood, 15
bayberry: northern, 174; **southern, 174**
bay, California, 198
beach plum, 167
beaked hazelnut, 173
bearberry, 159; alpine b., 159
bedstraw, 86; northern b., 86
beech, American, 233
Berberis canadensis, 219
Berberis haematocarpa, 219
Berberis vulgaris, **219**
Berlandier's lamb's quarters, 75
Betula alleghaniensis, **122, 254**
Betula lenta, **122, 253**
Betula lutea, **122, 254**
big shellbark hickory, 243
bilberry, bog, 164
birch: sweet (black), 122, 253; yellow, 122, 254
bistort: alpine, 155; American, 155; western, 155
black berried elder, 190
Blackberries, 178
blackberry: California, 185; common, 183

black birch, 122, 253
black cherry, 204
black haw, 227
black huckleberry, 167
black mulberry, 200
black mustard, 100
black nightshade, 265
black raspberry, 183
black walnut, 244; Texas b.w., 244, 247
Blueberry and Cranberry Genus, 163
blueberry: highbush, 164; late sweet, 164; swamp, 164; velvet-leaved, 163
blue elder, 190
blue flag, 261
blue oak, 231
bog bilberry, 164
box huckleberry, 167
bracken fern, 58
Brambles, Blackberries, Raspberries, 178
Brassica juncea, 100
Brassica nigra, 100
Brassica rapa, 100
breadroot, common, 150
brooklime, American, 144
buckeye, Ohio, 272
buckwheat, tartary, 155
buffaloberry: Canadian, 179; silver, 179
bugleweed, 89
bullbrier, 66
bull thistle, 115
bulrush: great, 70; hard-stem, 70
bunchberry, 143; Swedish b., 143
burdock: common, 112; great, 112
bush morning glory, 216
buttercup, common, 262
butterfly weed, 267
butternut, 247

cactus, saguaro, 5
calamus, 133
California bay, 198
California blackberry, 185
California grape, 216
California juniper, 194
California laurel, 198
California rose, 220
California walnut, 247
Caltha palustris, 100
camass: death, 258; eastern, 65; western, 136
camass lily, 65, 136
Camassia quamash, 136
Camassia scilloides, 65
Canada violet, 95
Canadian buffaloberry, 179
Capsella bursa-pastoris, 81
Capsella gracilis, 81
Capsella rubella, 81
Carolina hemlock, 122
Carolina laurelcherry, 204
Carolina spring beauty, 92
carrion flower, 66
Carya alba, 244
Carya carolinae-septentrionalis, 243
Carya illinoensis, 240
Carya laciniosa, 243
Carya ovata, 243
Carya tomentosa, 244
Castanea dentata, 234
Castanea pumila, 234
catbrier, 65
cattail, 69; narrow-leaved c., 69
Ceanothus americanus, 176
Ceanothus ovatus, 176
Celtis occidentalis, 220
Celtis pallida, 220
Cerastium vulgatum, 85
Cereus giganteus, 5
checkerberry, 150
cheese mallow, 146
Chenopodium album, 75
Chenopodium berlandieri, 75
Chenopodium fremontii, 75
cherry: black, 204; ground, 149
chestnut, American, 234
chestnut oak, 231
chickweed: common, 85; James, 85; mouse-ear, 85; star, 85
chicory, 115
China-root, 66
Chinese mustard, 100
chinkapin, Allegheny, 234
chokecherry, common, 204
chufa, 130
Cichorium intybus, 115
Cicuta maculata, 268
cinnamon fern, 58
Cirsium vulgare, 115
Claviceps species, 129
Claytonia caroliniana, 92
Claytonia lanceolata, 92
Claytonia megarhiza, 92
Claytonia perfoliata, 95
Claytonia virginica, 91
cleavers, 86
Clintonia borealis, 62
Clintonia umbellata, 62
clintonia, white, 62
Clinton's lily, 62
clover, 15

Coccoloba divarsifolia, 197
Coccoloba uvifera, 197
cockspur hawthorn, 238
common chokecherry, 204
common barberry, 219
common blackberry, 183
common breadroot, 150
common burdock, 112
common buttercup, 262
common chickweed, 85
common day lily, 136
common elder, 190
common greenbrier, 65
common milkweed, 106
common persimmon, 238
Comptonia peregrina, 174
Conium maculatum, 268
coral bean: eastern, 271; southeastern, 271
corn lily, 62
Cornus canadensis, 143
Cornus suecica, 143
Corylus americana, 173
Corylus cornuta, 173
Coulter pine, 193
cow cress, 82
cow lily, 213
cowslip, 100
cranberry, 163; highbush c., 224, 250; mountain c., 163; small, 163
cranberry tree, 224, 250
Crataegus, 237
Crataegus acutifolia, 238
Crataegus aestivalis, 237
Crataegus arnoldiana, 237
Crataegus canadensis, 237
Crataegus canbyi, 238
Crataegus crus-galli, 238
Crataegus mollis, 237
Crataegus phaenopyrum, 237
Crataegus pyracanthoides, 238
Crataegus regalis, 238
Crataegus submollis, 237
Crataegus succulenta, 238
creeping snowberry, 153
creeping wintergreen, 160
cress: cow, 82; field, 82
Crotalaria species, 149
Cruciferae, 82
cucumber, Indian, 139
curled dock, 121
currant, fragrant golden, 170; golden, 169; sticky, 169; subalpine prickly, 170; wax, 170
Currant or Gooseberry Genus, 168
Cyperus esculentus, 130

dandelion, 104
dangleberry, 167
datil, 134
Datura stramonium, 262
deadly nightshade, 265
death camass, 258
Dentaria laciniata, 81
desert hackberry, 220
digger pine, 193
Diospyros texana, 238
Diospyros virginiana, 238
dock: curled, 121; sour, 121; yellow, 121
dogbane, 267
dove plum, 197
downy hawthorn, 237
downy serviceberry, 207
duck potato, 213
dwarf fireweed, 109
dwarf huckleberry, 167
dwarf mallow, 146
dwarf pawpaw, 198

early wintercress, 99
eastern camass, 65
eastern coral bean, 271
eastern hemlock, 122
edible valerian, 89
Elaeagnus argentea, 179
elder: American, 190; black berried, 190; blue, 190; common, 190; Mexican, 190; Pacific, 190; red-fruited, 190
English yew, 271
Epilobium angustifolium, 109
Epilobium latifolium, 109
Erodium cicutarium, 109
Erythrina flabelliformis, 271
Erythrina herbacea, 271
European horse chestnut, 272
European mountain ash, 240, 254
European nightshade, 265
evening primrose, 103

Fagaceae, 234
Fagus grandifolia, 233
false hellebore, 265
fern: bracken, 58; cinnamon, 58; ostrich, 58; sweet, 174
field cress, 82
field garlic, 58
field mustard, 100

field pennycress, 82
fig, Indian, 139, 140
filaree, 109
fireweed, 109; dwarf f., 109
flag: blue, 261; sweet, 133
flatwood plum, 203
fleshy hawthorn, 238
foxberry, 163
***Fragaria virginiana,* 91**
fragrant golden currant, 170
Fremont's lamb's quarters, 75
Fremont's peppergrass, 82
frost grape, 214

galinsoga, 159
Gallinsoga ciliata, 159
***Galinsoga parviflora,* 159**
***Galium aparine,* 86**
***Galium boreale,* 86**
Gambel's oak, 231
garlic: field, 58; **wild, 61**
garlic mustard, 85
Gaultheria hispidula, 153
***Gaultheria humifusa,* 160**
Gaultheria ovatifolia, 153, 160
***Gaultheria procumbens,* 150**
***Gaultheria shallon,* 160**
***Gaylussacia baccata,* 167**
Gaylussacia brachycera, 167
Gaylussacia dumosa, 167
Gaylussacia frondosa, 167
giant knotweed, 99, 155
glandular mesquite, 189
glasswort, 76
goat's beard, 106; yellow g.b., 106
golden currant, 169
Gooseberry Genus, 168
goosegrass, 86
grape: California, 216; frost, 214; riverside, 214; sea, 197
grass: reed, 129; yellow nut, 130
great bulrush, 70
great burdock, 112
greenbrier, 66; common g., 65
Greene mountain ash, 240, 254
green pigweed, 72
Grindelia species, 8
ground cherry, 149
groundnut *(Apios americana),* 149
groundnut *(Apios priceana),* 149
guelder rose, 224, 250, 253

hackberry: American, 220; **desert, 220; spiny, 220**
hard-stem bulrush, 70
haw, black, 227
hawthorn: cockspur, 238; downy, 237; fleshy, 238; May, 237; **Washington, 237**
Hawthorns, 237
hazelnut: American, 173; beaked, 173
***Helianthus annus,* 156**
***Helianthus tuberosus,* 210**
hellebore: false, 265; white, 265
***Hemerocallis fulva,* 136**
hemlock: Carolina, 122; **eastern, 122;** mountain, 122; **poison, 268; water, 268;** western, 122
***henbit (Lamium amplexicaule),* 116**
henbit *(Lamium purpureum),* 116
Hibiscus esculentus, 106
hickory: big shellbark, 243; mockernut, 244; shagbark, 243
highbush blueberry, 164
highbush cranberry, 224, 250
Hinds walnut, 244, 247
Hippocastanaceae, 234
hobblebush, 224
horehound, water, 89
horsechestnut, 234, 272
horse chestnut, European, 273
horse nettle, 265
huckleberry: black, 167; box, 167; dwarf, 167

***Impatiens biflora,* 119**
***Impatiens capensis,* 119**
***Impatiens pallida,* 119**
Indian cucumber, 139
Indian fig, 139, 140
Ipomoea leptophylla, 216
***Ipomoea pandurata,* 216**
***Iris pseudoacorus,* 261**
***Iris versicolor,* 261**

jack-in-the-pulpit, 14
James chickweed, 85
Japanese knotweed, 99
Japanese yew, 271
Jerusalem artichoke, 210
jewelweed: orange-flowered, 119; yellow-flowered, 119
jimson weed, 262
Joshua tree, 5
***Juglans californica,* 247**
***Juglans cinerea,* 247**
Juglans hindsii, 244, 247
Juglans major, 244, 247
Juglans microcarpa, 244, 247

Face

Natural Beauty

Massaging your face with Chi is a far more effective beauty treatment than the most expensive cream or cosmetic, Your skin will glow brightly and eventually become less wrinkled. There are many meridians passing through or ending at the face. When blocked, they result in reduced flow of Chi energy and circulation. The face is the first impression imprinted in other people's minds. Chi circulation provides it with attractive personal energy.


Throat
Lung
Ear
Heart
Breast
Elbow Shoulder Hand
Neck-Upper Back
Liver
Gall Bladder
Lumbar Vertebrae
Stomach
Spleen
Large Intestine
Upper Limb
Thigh-Hip
Bladder-Uterus
Kidney Navel
Knee-Lower Leg
Back Knee
Foot-Toes
Thigh Leg Foot

Fig. 14 *Head and Face*

Juglans nigra, 244
juniper: California, 194; Rocky Mountain, 194; Utah, 197
Juniper Genus, 194
Juniperus, 194
Juniperus californica, 194
Juniperus osteosperma, 197
Juniperus scopulorum, 194
Juniperus utahensis, 197

kinnikinick, 159
knotweed: Alaskan, 99, 155; Japanese, 99; giant, 99, 155

Labrador tea, 160; northern L.t., 160
Lactuca canadensis, 104
Lactuca scariola, 104
Lactuca serriola, 104
lady's thumb, 110
lamb's quarters, 75; Berlandier's l.q., 75; Fremont's l.q., 75
Lamium amplexicaule, 116
Lamium purpureum, 116
lance-leaved pickerelweed, 133
Laporta canadensis, 79
late sweet blueberry, 164
Lathyrus species, 149
laurel, California, 198
laurelcherry, Carolina, 204
Ledum glandulosum, 160
Ledum groenlandicum, 160
Ledum palustre, 160
leek, wild, 61
lemonade berry, 186, 250
lemonade sumac, 185
Lepidium campestre, 82
Lepidium fremontii, 82
Lepidium virginicum, 82
lettuce: miner's, 95; prickly, 104; wild, 104
lily: atamasco, 261; camass, 65, 136; Clinton's, 62; common day, 136; corn, 62; cow, 213; lotus, 210; water, 210; yellow pond, 213
Lindera benzoin, 219
lingenberry, 163
live-forever, 110
locoweed, point, 149
lotus, American, 210
lotus lily, 210
Lycopus amplecteris, 89
Lycopus uniflorus, 89

mallow: cheese, 146; dwarf, 146; marsh, 146
Malva neglecta, 146
Malva rotundifolia, 146
mandrake, 140
maple: Norway, 126, 257; red, 257; sugar, 125, 257
marigold, marsh, 100
marsh mallow, 146
marsh marigold, 100
Matteucia pensylvanica, 58
Matteucia struthiopteris, 58
May apple, 140, 262
May hawthorn, 237
Medeola virginiana, 139
Melilotus alba, 267
Melilotus officinalis, 265
Memispermum canadense, 215
Mentha piperita, 143
Mentha spicata, 144
mesquite, 189; glandular, 189; screwbean m., 189
Mexican elder, 190
Mexican pinyon, 193, 228
milkweed, common, 106; showy, 106
milk vetch, 149
miner's lettuce, 95; Siberian m.l., 95
mockernut hickory, 244
Monolepis nuttalliana, 75
Montia perfoliata, 95
Montia sibirica, 95
moonseed, 215
morning glory, bush, 216
Morus alba, 200
Morus microphylla, 200
Morus nigra, 200
Morus rubra, 200
mountain ash: American, 240, 254; European, 240, 254; Greene, 240, 254; Sitka, 240, 254
mountain cranberry, 163
mountain hemlock, 122
mountain Labrador tea, 160
mountain sorrel, 153
mouse-ear chickweed, 85
mulberry: black, 200; red, 200; Texas, 200; white, 200
mustard: black, 100; Chinese, 100; field, 100; garlic, 85
Myrica cerifera, 174
Myrica gale, 176
Myrica pensylvanica, 174
myrtle, wax, 174

nannyberry, 227
narrow-leaved cattail, 69
Nasturtium officinale, 146

Nelumbo lutea, 210
nettle, 79; horse n., 265; slender n., 79; **stinging n., 79;** wood n., 79
New Jersey tea, 176
nightshade: black (deadly), 265; European, 265; silverleaf, 265
nodding onion, 58
northern bayberry, 174
northern bedstraw, 86
northern Labrador tea, 160
northern red oak, 233
northern wild raisin, 227
Norway maple, 126, 257
Nuphar advena, 213
Nuphar polysepalum, 213
nut grass, yellow, 130
Nymphaea species, 210

oak: blue, 231; chestnut, 231; Gambel's, 231; northern red, 233; white, 228
Oaks, 228
Oenothera biennis, 103
Ohio buckeye, 272
okra, 106
onion: nodding, 58; wild, 58
Opuntia humifusa, 139
Opuntia phaeacantha, 140
orange-flowered jewelweed, 119
Ornithogalum nutans, 258
Ornithogalum umbellatum, 258
orphine, 110
ostrich fern, 58
Osumunda cinnamomea, 58
Oxyria digyna, 153
Oxytropis species, 149
oyster plant, 112

Pacific elder, 190
pale touch-me-not, 119
pale violet, 96
papaw, 198; dwarf p., 198
Parry pinyon, 228
pasture rose, 223
pawpaw, 198
pear, prickly, 139, 140
pea, scurf, 150
pecan, 240
pennycress, 82; **field p., 82**
peppergrass, 82; Fremont's p., 82
peppermint, 143
persimmon: common, 238; Texas, 238
phragmites, 129
Phragmites communis, 129
Physalis pubescens, 149
Phytolacca americana, 96, 267
pickerelweed, 130; lance-leaved p., 133
pigweed, 72; green p., 72
pine: Coulter, 193; **digger, 193; pinyon, 228; singleleaf pinyon, 193; sugar, 193**
Pinus cembroides, 193, 228
Pinus coulteri, 193
Pinus edulis, 228
Pinus lambertiana, 193
Pinus monophylla, 193
Pinus quadrifolia, 228
Pinus sabiniana, 193
pinyon: Mexican, 193, 228; Parry, 228
pinyon pine, 228
Plantago juncoides, 79
Plantago major, 79
plantain, 79; seaside p., 79
plum: American, 203; beach, 167; dove, 197; **flatwood, 203; wild, 203**
Podophyllum peltatum, 140, 262
point locoweed, 149
poison hemlock, 268
poison ivy, 272
poison oak, 185, 186, 272
poison sumac, 185, 250
pokeweed, 96, 267
Polygonum alaskanum, 99, 155
Polygonum bistortoides, 155
Polygonum cuspidatum, 99
Polygonum persicaria, 110
Polygonum sachalinense, 99, 155
Polygonum tataricum, 155
Polygonum viviparum, 155
Pontederia cordata, 130
Pontederia lanceolata, 133
Portulaca neglecta, 156
Portulaca oleracea, 156
Portulaca retusa, 156
potato, duck, 213
potato vine, wild, 216
poverty weed, 75
prickly lettuce, 104
prickly pear, 139, 140
primrose, evening, 103
Prosopis glandulosa, 189
Prosopis pubescens, 189
Prosopis veluntina, 189
Prunus americana, 203
Prunus caroliniana, 204
Prunus maritima, 167
Prunus serotina, 204
Prunus umbellata, 203
Prunus virginiana, 204
Psoralea esculenta, 150

Psoralea hypogala, 150
Psoralea tenuifolia, 150
***Pteretis nodulosa,* 58**
Pteridium aquilinum, 58
purslane, 156
pusley, 156

***Quercus alba,* 228**
***Quercus douglasii,* 231**
***Quercus* subgenus *Erythrobalanus,* 233**
***Quercus gambelii,* 231**
***Quercus prinus,* 231**
***Quercus rubra,* 233**
quickweed, 159

raisin, northern wild, 227
ramp, 61
***Ranunculus acris,* 262**
Raspberries, 178
raspberry: black, 183; red, 180
rattlebox, 149
Red/Black Oak Group, 233
red-fruited barberry, 219
red-fruited elder, 190
red maple, 257
red mulberry, 200
red oak, northern, 233
red raspberry, 180
redroot (*Amaranthus retroflexus*), 72
red root (*Ceanothus ovatus*), 176
red shepherd's purse, 81
reed grass, 129
Rhus diversiloba, 186, 272
***Rhus glabra,* 185**
Rhus integrifolia, 185, 186, 250
Rhus ovata, 185
***Rhus radicans,* 272**
Rhus toxicodendron, 272
***Rhus trilobata,* 186**
***Rhus typhina,* 186, 250**
Rhus vernix, 250
***Ribes,* 168**
***Ribes aureum,* 169**
***Ribes cereum,* 170**
***Ribes montigenum,* 170**
***Ribes odoratum,* 170**
Ribes viscosissimum, 169
rice, wild, 129
riverside grape, 214
Rocky Mountain juniper, 194
root, red, 176
***Rorippa nasturtium-aquaticum,* 146**
***Rosa,* 220**
***Rosa californica,* 220**
***Rosa carolina,* 223**
***Rosa eglanteria,* 223**
***Rosa rugosa,* 223**
rose: California, 220; guelder, 224, 250, 253; pasture, 223; sweetbrier, 223; wild, 223; wrinkled, 223
roseroot, 110
Roses, 220
***Rubus,* 178**
***Rubus allegheniensis,* 183**
***Rubus idaeus* var. *strigosus,* 180**
***Rubus occidentalis,* 183**
***Rubus parviflorus,* 180**
***Rubus phoenicolasius,* 180**
***Rubus strigosus,* 180**
***Rubus ursinus,* 185**
***Rumex acetosella,* 121**
***Rumex crispus,* 121**
Russian thistle, 76

***Sagittaria latifolia,* 213**
saguaro cactus, 5
salal, 160
***Salicornia europaea,* 76**
Salicornia virginica, 76
salsify, 112
***Salsola kali,* 76**
saltwort, 76
Sambucus callicarpa, 190
***Sambucus canadensis,* 190**
***Sambucus cerulea,* 190**
Sambucus melanocarpa, 190
Sambucus mexicana, 190
Sambucus pubens, 190
Saskatoon serviceberry, 207
sassafras, 125
***Sassafras albidum,* 125**
***Scirpus acutus,* 70**
***Scirpus validus,* 70**
screwbean mesquite, 189
scurf pea, 150
sea grape, 197
seaside plantain, 79
***Sedum purpureum,* 110**
Sedum rosea, 110
Serviceberry: downy, 207; Saskatoon, 207
Serviceberry Genus, 207
shagbark hickory, 243
sheep sorrel, 121
***Shepherdia argentea,* 179**
Shepherdia canadensis, 179
shepherd's purse, 81; red s.p., 81; slender s.p., 81
showy milkweed, 106

Siberian miner's lettuce, 95
silverberry, 179
silver buffaloberry, 179
silverleaf nightshade, 265
singleleaf pinyon pine, 193
Sitka mountain ash, 240, 254
skunk cabbage, 14
slender nettle, 79
slender shepherd's purse, 81
small cranberry, 163
smartweed, alpine, 155
***Smilax bona-nox,* 66**
***Smilax californica,* 66**
***Smilax herbacea,* 66**
***Smilax rotundifolia,* 65**
Smilax tamnoides, 66
smooth sumac, 185
snowberry, creeping, 153
soapweed, 134
***Solanum carolinense,* 265**
Solanum dulcamara, 265
Solanum elaeagnifolium, 265
Solanum nigrum, 265
***Sonchus arvensis,* 103**
***Sorbus americana,* 240, 254**
Sorbus aucuparia, 240, 254
Sorbus scopulina, 240, 254
Sorbus sitchensis, 240, 254
sorrel: mountain, 153; sheep, 121
sour dock, 121
southern bayberry, 174
southern wood violet, 116
southwestern coral bean, 271
sow thistle, 103
Spanish bayonet, 134
spatterdock, 213
spearmint, 144
spice bush, 219
spiny hackberry, 220
spotted touch-me-not, 119
spring beauty, 91; alpine s.b., 92; Carolina s.b., 92; **western s.b., 92**
squashberry, 227, 253
squawbush, 186
staghorn sumac, 186, 250
star chickweed, 85
starflower, 139
star of Bethlehem, 258
***Stellaria jamesiana,* 85**
***Stellaria media,* 85**
Stellaria pubera, 85
sticky currant, 169
stinging nettle, 79
storksbill, 109
strawberry, wild, 91
subalpine prickly currant, 170
sugar bush, 185
sugar maple, 125, 257
sugar pine, 193
sumac: lemonade, 185; **smooth, 185; staghorn, 186, 250**
sunflower, 156
swamp blueberry, 164
Swedish bunchberry, 143
sweet birch, 122, 253
sweetbrier rose, 223
sweetclover, white, 267; **yellow, 265**
sweet fern, 174
sweet flag, 133
sweet gale, 176

***Taraxacum officinale,* 104**
tartary buckwheat, 155
tarweed, 8
Taxus baccata, 271
***Taxus canadensis,* 271**
Taxus cuspidata, 271
tea: Labrador, 160; mountain Labrador, 160; **New Jersey, 176;** northern Labrador, 160
Texas black walnut, 244, 247
Texas mulberry, 200
Texas persimmon, 238
Texas wildrice, 129
thimbleberry, 180
thistle: bull, 115; Russian, 76; sow, 103
***Thlaspi arvense,* 82**
Thlaspi perfoliatum, 82
toothwort, 81
touch-me-not, pale, 119; spotted, 119
Toxicodendron diversiloba, 185
***Toxicodendron radicans,* 272**
Toxicodendron vernix, 185
Tragopogon dubius, 106
***Tragopogon porrifolius,* 112**
***Tragopogon pratensis,* 106**
Trientalis borealis, 139
***Tsuga canadensis,* 122**
Tsuga caroliniana, 122
Tsuga heterophylla, 122
Tsuga mertensiana, 122
tule, 70
***Typha angustifolia,* 69**
***Typha latifolia,* 69**

***Umbellularia californica,* 198**
***Urtica dioica,* 79**
Urtica gracilis, 79
Utah juniper, 197

Vaccinium, 163
Vaccinium angustifolium, 164
Vaccinium corymbosum, 164
Vaccinium macrocarpon, 163
Vaccinium myrtilloides, 163
Vaccinium oxycoccos, 163
Vaccinium uliginosum, 164
Vaccinium vitis-idaea, 163
Valeriana edulis, 89
valerian, edible, 89
velvet-leaved blueberry, 163
Veratrum viride, 265
Veronica americana, 144
vetchling, 149
vetch, milk, 149
Viburnum alnifolium, 224
Viburnum cassinoides, 227
Viburnum edule, 227, 253
Viburnum lentago, 227
Viburnum opulus, 224, 250, 253
Viburnum pauciflorum, 224, 250
Viburnum prunifolium, 227
Viburnum trilobum, 224, 250
Viola canadensis, 95
Viola hirsutula, 116
Viola palmata, 116
Viola purpurea, 116
Viola striata, 96
violet: Canada, 95; pale, 96; southern wood, 116; western mountain, 116; **wood, 116**
Vitis, 214
Vitis californica, 216
Vitis riparia, 214
Vitis vulpina, 214

walnut: Arizona, 244, 247; **black, 244; California, 247;** Hinds, 244, 247; Texas black, 244, 247
wapato, 213
Washington hawthorn, 237
watercress, 146
water hemlock, 268
water horehound, 89
water lily, 210
wax currant, 170
wax myrtle, 174
western bistort, 155
western camass, 136
western hemlock, 122
western mountain violet, 116
western spring beauty, 92
western wintergreen, 160
white clintonia, 62
white hellebore, 265
white mulberry, 200
white oak, 228
white sweetclover, 267
wild garlic, 61
Wild Grapes, 214
wild leek, 61
wild lettuce, 104
wild onion, 58
wild plum, 203
wild potato vine, 216
wild raisin, northern, 227
wild rice, 129
wildrice, Texas, 129
wild rose, 223
wild strawberry, 91
wineberry, 180
wintercress, 99; early w., 99
wintergreen, 150; creeping w., 160; western w., 160
wood nettle, 79
wood violet, 116; southern w.v., 116
wrinkled rose, 223

yellow birch, 122, 254
yellow dock, 121
yellow flag, 261
yellow-flowered jewelweed, 119
yellow goat's beard, 106
yellow nut grass, 130
yellow pond lily, 213
yellow sweetclover, 265
yew, American, 271; English, 271; Japanese, 271
Yucca baccata, 134
Yucca brevifolia, 5
Yucca glauca, 134
Zephyranthes atamasco, 261
Zigadenus venenosus, 258
Zizania aquatica, 129
Zizania texana, 129

A Sacred Lotus Arts Publication
Traditional Chinese Medicine
www.sacredlotus.com

治

Visual

Materia Medica

OF Chinese Herbs

Copyright © 2009 Sacred Lotus Arts, Inc. • Do Not Duplicate

治

Visual Materia Medica of Chinese Herbs

Sacred Lotus Arts, Inc.

1st Edition

Revision 1.1

No part of this book may be reproduced, transmitted, or stored in any form, by electronic or mechanical means (including but not limited to, photocopying, scanning, photographing, or any other recording or storage medium) without the prior written permission from the publisher.

Copyright © 2009, by Sacred Lotus Arts, Inc.

All Rights Reserved.

Visual Materia Medica of Chinese Herbs

Table of Contents

Warm, Spicy Herbs that Release the Exterior 01
Cool, Spicy Herbs that Release the Exterior 02
Herbs that Drain Fire 03
Herbs that Cool the Blood 04
Herbs that Clear Heat and Dry Dampness 05
Herbs that Clear Heat and Eliminate Toxins 06
Herbs that Clear and Relieve Summerheat 07
Purgatives 08
Moist Laxatives 09
Harsh Expellants 10
Herbs that Regulate Water and Drain Dampness 11
Herbs that Dispel Wind-Dampness 12
Herbs that Cool and Transform Phlegm-Heat 13
Warm Herbs that Transform Phlegm-Cold 14
Herbs that Relieve Coughing and Wheezing 15
Aromatic Herbs that Transform and Dissolve Dampness 16
Herbs that Relieve Food Stagnation 17
Herbs that Regulate the Qi 18
Herbs that Stop Bleeding 19
Herbs that Invigorate Blood and Remove Stagnation 20
Herbs that Warm the Interior and Expel Cold 21
Herbs that Tonify Qi 22
Herbs that Tonify Blood 23
Herbs that Tonify Yang 24
Herbs that Tonify Yin 25
Herbs that Astringe, Stabilize, Bind 26
Substances that Anchor, Settle, and Calm the Spirit 27
Herbs that Nourish the Heart and Calm the Spirit 28
Aromatic Substances that Open the Orifices 29
Substances that Extinguish Wind and Stop Tremors 30
Herbs that Expel Parasites 31
Substances for External Application 32



Fig. 15 *Massage the Whole Face*



Fig. 16 *Massage the Mid Forehead*

Temples

Use your index fingers to massage the temples in a circular motion, first clockwise, then counterclockwise. Massage the forehead and the temples; use the knuckle rub from the middle of the forehead all the way to the temples ten to twenty times. These exercises will reduce headaches in the front and in the temples. Find the painful point and massage it until the pain is gone.

bái zhǐ (Angelica Root)



白芷

CHANNELS

LU
ST

Radix Angelicae Dahuricae
spicy, warm

fáng fēng (Ledebouriella Root)



防风

CHANNELS

BL
LIV
SP

Radix Ledebouriellae Divaricatae
spicy, sweet, slightly warm

gǎo běn (Straw Weed, Chinese Lovage Root)



藁本

CHANNELS

BL

Radix et Rhizoma Ligustici Chinensis
spicy, warm

guì zhī (Cinnamon Twig, Cassia Twig)



桂枝

CHANNELS

HT
LU
BL

Ramulus Cinnamomi Cassiae
spicy, sweet, warm

jīng jiè (Schizonepeta Bud or Stem)



荆芥

CHANNELS

LU
LIV

Herba Seu Flos Schizonepetae Tenuifoliae
spicy, aromatic, slightly warm

má huáng (Ephedra Stem)



麻黄

CHANNELS

LU
BL

Herba Ephedrae
spicy, slightly bitter, warm

DO NOT DUPLICATE

Warm, Spicy Herbs that Release the Exterior

qiāng huó (Notopterygium Root)



羌活

CHANNELS

BL
KI

Radix Et Rhizoma Notopterygii
spicy, bitter, aromatic, warm

xì xīn (Chinese Wild Ginger, Asarum)



细辛

CHANNELS

LU
KI

Herba Asari Cum Radice
spicy, warm

xīn yí (Magnolia Flower)



辛夷

CHANNELS

LU
ST

Flos Magnoliae Lilliflorae
spicy, warm

shēng jiāng (Fresh Ginger Rhizome)



生姜

CHANNELS

LU
SP
ST

uncooked Rhizoma Zingiberis
spicy, warm

xiāng rú (Aromatic Madder, Elsholtzia)



香薷

CHANNELS

LU
ST

Herba Elsholtziae
spicy, aromatic, slightly warm

zǐ sū gěng (Perilla Stalk)



紫苏根

CHANNELS

LU
ST

Perillae Ramulus
spicy, warm

DO NOT DUPLICATE

zǐ sū yè (Perilla Leaf)



紫苏叶

CHANNELS

LU
SP

Perillae Folium
spicy, aromatic, warm

DO NOT DUPLICATE

bò he (Field Mint, Mentha)



薄荷

CHANNELS

LU
LIV

Herba Menthae Haplocalycis
spicy, aromatic, cool

chái hú (Thorowax Root , Bupleurum)



柴胡

CHANNELS

GB
LIV
PER
TB

Radix Bupleuri
bitter, spicy, cool

chán tuì (Circada Moulting)



蝉蜕

CHANNELS

LU
LIV

Periostracum Cicadae
sweet, salty, slightly cold

dàn dòu chì (Prepared Soybean)



淡豆豉

CHANNELS

LU
ST

Semen Praeparatum Sojae
sweet, slightly bitter, neutral

fú píng (Duckweed or Spirodela)



浮萍

CHANNELS

BL
LU

Herba Lemnae Seu Spirodelae
spicy, cold

gé gēn (Pueraria, Kudzu Root)



葛根

CHANNELS

SP
ST

Radix Puerariae
sweet, spicy, cool

DO NOT DUPLICATE

Cool, Spicy Herbs that Release the Exterior

jú huā (Chrysanthemum Flower)



菊花

CHANNELS

LIV
LU

Flos Chrysanthemi Morifolii
sweet, bitter, slightly cold

mù zéi (Shave Grass, Scouring Rush)



木贼

CHANNELS

LIV
LU

Herba Equiseti Hiemalis
sweet, bitter, neutral

sāng yè (White Mulberry Leaf)



桑叶

CHANNELS

LIV
LU

Folium Mori Albae
sweet, bitter, cold

màn jīng zǐ (Vitex Fruit)



蔓荆子

CHANNELS

BL
LIV
ST

Fructus Viticis
bitter, spicy, cool

niú bàng zǐ (Great Burdock Fruit)



牛旁子

CHANNELS

LU
ST

Fructus Arctii Lappae
spicy, bitter, cold

shēng má (Black Cohosh Rhizome, Bugbane Rhizome)



升麻

CHANNELS

LI
LU
SP
ST

Rhizoma Cimicifugae
sweet, spicy, cool

DO NOT DUPLICATE

dàn zhú yè (Lophatherum Stem and Leaves)



淡竹叶

CHANNELS

HT
SI
ST

Herba Lophatheri Gracilis
sweet, bland, cold

hán shuǐ shí (Calcitum)



寒水石

CHANNELS

HT
ST
KI

Calcitum
spicy, salty, cold

lián zǐ xīn (Lotus Plumule)



连子心

CHANNELS

HT
PER

Plumula Nelumbinis Nuciferae
bitter, cold

gǔ jīng cǎo (Inflorscence or Pipewort Scapus)



谷精草

CHANNELS

LIV
ST

Scapus Et Inflorescentia Eriocaulonis Buergeriani
sweet, neutral

jué míng zǐ (Cassia or Foetid Cassia Seeds)



决明子

CHANNELS

LIV
KI
LI.

Semen Cassiae Torae
bitter, sweet, cool

lú gēn (Reed Rhizome)



芦根

CHANNELS

LU
ST

Rhizoma Phragmitis Communis
sweet, cold

DO NOT DUPLICATE

mì Méng huā (Buddleia Flower Bud)



密蒙花

CHANNELS

LIV

Flos Buddleiae Officinalis Immaturus
sweet, cool

qīng xiāng zǐ (Celosia Seeds)



青箱子

CHANNELS

LIV

Semen Celosiae Argentae
sweet, cool

shí gāo (Gypsum)



石膏

CHANNELS

LU
ST

Gypsum Fibrosum
sweet, spicy, very cold

xià kū cǎo (Prunella or Selfheal Spike)



夏枯草

CHANNELS

GB
LIV

Spica Prunellae Vulgaris
bitter, spicy, cold

yè míng shā (Bat Feces)



夜明砂

CHANNELS

LIV

Excrementum Vespertilionis Murini
spicy, cool

zhī mǔ (Anemarrhena Rhizome)



知母

CHANNELS

LU
ST
KI

Rhizoma Anemarrhenae Aspheloidis
bitter, cold

DO NOT DUPLICATE

zhī zi (Gardenia, Cape Jasmine Fruit)



栀子

CHANNELS

HT
LIV
LU
ST
TB

Fructus Gardeniae Jasminoidis
bitter, cold

DO NOT DUPLICATE

bái wēi (Swallowwort Root)



白薇

CHANNELS

LU
ST
KI

Radix Cynanchi Atrati
bitter, salty, cold

chì sháo (Red Peony Root)



赤芍

CHANNELS

LIV
SP

Radix Rubrus Paeoniae Lactiflorae
sour, bitter, slightly cold

dì gŭ pí (Cortex of Wolfberry Root or Lycium Bark)



地骨皮

CHANNELS

LU
LIV
KI

Cortex Radicis Lycii Chinensis
sweet, cold

mŭ dān pí (Cortex of the Peony Tree Root)



牡丹皮

CHANNELS

HT
LIV
KI

Cortex Radicis Moutan
spicy, bitter, cool

shēng dì huáng (Chinese Foxglove Root, Rehmannia)



地黄

CHANNELS

HT
KI
LIV

Radix Rehmanniae Glutinosae
sweet, bitter, salty, cold

xī jiăo (Rhinoceros Horn)



犀角

CHANNELS

HT
LIV
ST

Cornu Rhinoceri
bitter, salty, cold

DO NOT DUPLICATE



Fig. 17 *Massage the Temples*

Mouth

Depression makes the corners of the mouth drop. Looking cheerful, delightful, more attractive and happy are dependent so much on the eyes and the corners of the mouth. When the muscles of the mouth are loose because of stress, depression, or sadness, the corners of the mouth drop and the energy system is depressed and in low key. No one likes to look at a sad face or a depressed face; it makes other people feel sad and depressed, too.

The flow of energy in the body and the expression of the face are the main attractive powers of a person. Massaging the mouth muscles up will help to lift the corners of the mouth. The Inner Smile and lifting up the corners of the mouth are very important to building up attractive energy.

xuán shēn (Ningpo Figwort Root)



玄参

CHANNELS

KI
LU
ST

Radix Scrophulariae Ningpoensis
salty, sweet, bitter, cold

yīn chái hú (Stellaria Root)



阴柴胡

CHANNELS

LIV
ST

Radix Stellariae Dichotomae
sweet, cool

zǐ cǎo (Groomwell Root or Arnebia or Lithospermum)



紫草

CHANNELS

HT
LIV

Radix Arnebiae seu Lithospermi
sweet, cold

DO NOT DUPLICATE

hú huáng lián (Picrorhiza Rhizome)



胡簧莲

CHANNELS

LIV
ST
LI.

Rhizoma Picrorrhizae
bitter, cold

huáng bǎi (Phellodendron or Amur Cork tree Bark)



黄柏

CHANNELS

KI
BL

Cortex Phellodendri
bitter, cold

huáng lián (Coptis Rhizome)



黄连

CHANNELS

HT
LI
LIV
ST

Rhizoma Coptidis
bitter, cold

huáng qín (Baical Skullcap Root)



黄芩

CHANNELS

GB
LI
LU
ST

Radix Scutellariae Baicalensis
bitter, cold

kǔ shēn (Sophora Root)



苦参

CHANNELS

BL
HT
LIV
LI
SI

Radix Sophorae Flavescentis
bitter, cold

lóng dăn căo (Chinese Gentian Root)



龙胆草

CHANNELS

GB
LIV
ST

Radix Gentianae Longdancao
bitter, cold

DO NOT DUPLICATE

qín pí (Korean Ash Branch Bark)



秦皮

CHANNELS

GB
LI
LIV
ST

Cortex Fraxini
bitter, cold

DO NOT DUPLICATE

bái huā shé shé cǎo (Oldenlandia or Heydyotis)



白花蛇舌草

CHANNELS

LIV
ST
LI.

Herba Hedyotidis Diffusae
bitter, sweet, cold

bài jiàng cǎo (Patrinia, Thiaspi)



败酱草

CHANNELS

LI
LIV
ST

Herba cum Radice Patriniae
spicy, bitter, slightly cold

bái tóu wēng (Chinese Anemone Root or Pulsatilla)



白头翁

CHANNELS

LI
LIV
ST

Radix Pulsatillae Chinensis
bitter, cold

bái xiǎn pí (Cortex of Chinese Dittany Root)



白鲜皮

CHANNELS

SP
ST

Cortex Dictamni Dasycarpi Radicis
bitter, cold

bǎn lán gēn (Woad Root or Isatis Root)



板蓝根

CHANNELS

HT
LU
ST

Radix Isatidis seu Baphicacanthi
bitter, cold

bàn zhī lián (Barbat Skullcap or Scutellaria)



半枝莲

CHANNELS

LI
LIV
LU
ST

Radix Scutellariae Barbatae
spicy, bitter, cold

DO NOT DUPLICATE

chuān xīn lián (Green Chiretta or Kariyat or Andrographis)



穿芯连

CHANNELS

LI
LU
SI
ST

Herba Andrographitis Paniculatae
bitter, cold

hóng téng (Sargentodoxa Vine)



红藤

CHANNELS

LI
LIV

Caulis Sargentodoxae
bitter, neutral

lián qiáo (Forsythia Fruit)



连翘

CHANNELS

HT
LIV
GB

Fructus Forsythiae Suspensae
bitter, slightly spicy, cool

dài qīng yè (Indigo or Woad Leaf)



大青叶

CHANNELS

HT
LU
ST

Folium Daqingye
bitter, very cold

jīn yín huā (Honeysuckle Flower or Lonicera)



金银花

CHANNELS

LI
LU
ST

Flos Lonicerae Japonicae
sweet, cold

lòu lú (Echinops Root or Rhaponticum)



漏芦

CHANNELS

LI
ST

Radix Rhapontici seu Echinopsis
bitter, salty, cold

DO NOT DUPLICATE

mă bó (Fruiting Body of Puffball or Lasiosphaera)



马勃

CHANNELS

LU

Fructificatio Lasiosphaerae seu Calvatiae
spicy, neutral

mă chĭ xiàn (Purslane or Portulaca)



马齿苋

CHANNELS

LI
LIV

Herba Portulacae Oleraceae
sour, cold

pú gōng Yīng (Dandelion)



蒲公英

CHANNELS

LIV
ST

Herba Taraxaci Mongolici cum Radice
bitter, sweet, cold

qīng dài (Indigo)



青黛

CHANNELS

LIV
LU
ST

Indigo Maturalis
salty, cold

rĕn dōng téng (Honeysuckle Stem)



忍冬疼

CHANNELS

LU
ST

Caulis Lonicerae
sweet, cold

shān dòu gēn (Sophora Root or Subprostrate)



山豆根

CHANNELS

LI
LU

Radix Sophorae Subprostratae
bitter, cold

DO NOT DUPLICATE

shè gàn (Belamcanda Rhizome)



射干

CHANNELS

LU

Rhizoma Belamcandae
bitter, cold

tŭ fú líng (Smilax or Glabrous Greenbrier Rhizome)



土茯苓

CHANNELS

LIV
ST

Rhizoma Smilacis Galbrae
sweet, bland, neutral

niú xī (Tuniuxi Root)



牛膝

CHANNELS

LIV
KI

Radix Achyranthis
bitter, sour, neutral

yā dàn zĭ (Java Brucea Fruit)



鸭蛋子

CHANNELS

LI
LIV

Fructus Bruceae Javanicae
bitter, cold ,toxic

yĕ jú huā (Wild Chrysanthemum Flower)



野菊花

CHANNELS

LU
LIV

Flos Chrysanthemi Indici
bitter, spicy, slightly cold

yú xīng căo (Houttuynia)



鱼腥草

CHANNELS

LI
LU

Herba cum Radice Houttuyniae Cordatae
spicy, cool

DO NOT DUPLICATE

zǐ huā dì dīng (Viola or Yedeon's Violet)



紫花地丁

CHANNELS

HT
LIV

Herba cum Radice Violae Yedoensitis
spicy, bitter, cold

DO NOT DUPLICATE

bái biăn dòu (Hyacinth Bean, Dolichos)



白扁豆

CHANNELS

SP
ST

Semen Dolichoris Lablab
sweet, neutral

hè yè (Lotus Leaf)



荷叶

CHANNELS

HT
LIV
SP

Folium Nelumbinis Nuciferae
bitter, slightly sweet, neutral

qīng hāo (Wormwood)



青蒿

CHANNELS

KI
LIV
GB

Herba Artemisiae Apiaceae
bitter, cold

dà dòu juăn (Young Soybean Sprout)



大豆卷

CHANNELS

ST

Semen Glycines Germinatum
sweet, neutral

lù dòu (Mung Bean or Phaseolus)



录豆

CHANNELS

HT
ST

Semen Phaseoli Munginis
sweet, cool

DO NOT DUPLICATE

Beautify the Mouth Massage

Using the thumb and the index finger of the right hand, touch both corners of the mouth and feel the Chi from the thumb and index finger pass to the corners of the mouth. Slowly press and push up about one inch, release and start again at the corners, pressing up ten to twenty times each day.



Cheerful Delight

Mouth Corners Drop

Fig. 18 *Beautifying the Mouth Massage*

Eyes

The eyes are the windows of the spirit. In Taoism we regard the eyes as Yang energy which will guide all Chi flow in the body. The eyes can greatly affect your personality Some people are born with a lot of white in their eyes--three portions of white to one portion of iris—sometimes called “thief eyes” or “danger attack eyes.” Such eyes can result in a suspicious look, portending unpleasant things. Through the exercises, you can gradually correct the white portion of the eyes.

dà huáng (Rhubarb Root and Rhizome)



大簧

CHANNELS

HT
LI
LIV
ST

Radix Et Rhizoma Rhei
bitter, cold

fān xiè yè (Senna Leaf)



番泻叶

CHANNELS

LI.

Folium Sennae
sweet, bitter, cold

máng xiāo (Sodium Sulfate, Mirabilite, Glauber's Salt)



芒硝

CHANNELS

ST
LI.

Natrii Sulfas
salty, bitter, very cold

lú huì (Aloe Leaf - Dried juice Concentrate)



芦荟

CHANNELS

LI
LIV
ST

Herba Aloes
bitter, cold

DO NOT DUPLICATE

huǒ má rén (Hemp Seeds or Cannabis Seeds)



火麻仁

CHANNELS

LI
SP
ST

Semen Cannabis Sativae
sweet, neutral

yù lǐ rén (Bush Cherry Pit)



郁李仁

CHANNELS

LI
SI
SP

Semen Pruni
spicy, bitter, sweet, neutral

DO NOT DUPLICATE

bā dòu (Croton Seed)



巴豆

CHANNELS

ST
LI
LU

Crotonis Fructus
spicy, hot, toxic

gān suì (Kansui Root)



甘遂

CHANNELS

KI
LI
LU

Radix Euphorbiae Kansui
bitter, sweet, cold, toxic

hóng dà jĭ (Peking Spurge Root or Euphorbia)



红大戟

CHANNELS

KI
LI
LU

Radix Euphorbiae seu Knoxiae
bitter, spicy, cold, toxic

Shāng lù (Poke Root or Phytolacca)



商陆

CHANNELS

BL
KI
LI
SP

Radix Phytolaccae
bitter, cold, toxic

yuán hu (Genkwa Flower)



芫花

CHANNELS

KI
LI
LU

Flos Daphnis Genkwae
bitter, spicy, warm, toxic

DO NOT DUPLICATE

bā yuè zhá (Akebia Fruit)



八月札

CHANNELS

LIV
ST

Fructus Akebiae Trifoliatae
bitter, neutral

bàn biàn lián (Chinese Lobelia, Lobelia)



半遍莲

CHANNELS

HT
LU
SI

Herba Lobeliae Chinensis Gum Radice
sweet, neutral

bì xiè (Fish Poison Yam Rhizome, Tokoro)



萆解

CHANNELS

BL
LIV
ST

Rhizoma Dioscoreae Hypoglaucae
bitter, neutral

biǎn xù (Knotweed, Polygonum)



扁蓄

CHANNELS

BL

Herba Polygoni Avicularis
bitter, slightly cold

chē qián zǐ (Plantago Seed, Plantain Seed)



车前子

CHANNELS

KI
BL
LIV
LU

Semen Plantaginis
sweet, cold

chì xiǎo dòu (Aduki Bean, Phaseolus)



赤小豆

CHANNELS

HT
SI

Semen Phaseoli Calcarati
sweet, sour, neutral

DO NOT DUPLICATE

dēng xīn cǎo (Rush Pith, Juncus)



灯心草

CHANNELS

HT
LU
SI

Medulla Junci Effusi
sweet, bland, slightly cold

dì fū zǐ (Broom Cypress, Kochia Fruit)



地肤子

CHANNELS

BL

Fructus Kochiae Scopariae
sweet, bitter, cold

dōng guā zǐ (Winter Melon, Wax Gourd Seed, Benincasa)



冬瓜子

CHANNELS

LU
ST
LI
SI

Semen Benincasae Hispidae
sweet, cold

dōng kuí zǐ (Musk Mallow Seeds, Abutilon Seeds)



冬葵子

CHANNELS

BL
LI
SI

Semen Malvae
sweet, cold

fú líng (Sclerotium of Tuckahoe, China Root, Poria, Hoelen)



茯苓

CHANNELS

HT
SP
LU

Scierotium Poriae Cocos
sweet, bland, neutral

fú líng pí (Poria Skin)



茯苓皮

CHANNELS

HT
SP
LU

Sclerotii Poriae Cocos
sweet, bland, neutral

DO NOT DUPLICATE

fú shén (Poria Spirit)



茯神

CHANNELS

HT
SP
LU

Scierotium Pararadicis Poriae Cocos
sweet, bland, neutral

hàn fáng jǐ (Stephania Root)



防己

CHANNELS

BL
SP
KI

Radix Stephaniae Tetrandrae
bitter, spicy, cold

jīn qián cǎo (Lysimachia)



金千草

CHANNELS

BL
GB
KI
LIV

Herba Desmodii Styrachifolii
sweet, bland, neutral

hǎi Jīn shā (Spores of Japanese Fern)



海金沙

CHANNELS

BL
SI

Spora Lygodii Japonici
sweet, cool

huá shí (Talcum)



滑石

CHANNELS

ST
BL

Talcum
sweet, bland, cold

mù tōng (Akebia Caulis)



木通

CHANNELS

BL
HT
SI

Caulis Akebiae
bitter, cool

DO NOT DUPLICATE

Herbs that Regulate Water and Drain Dampness

qú mài (Aerial Parts of Fringed Pink or Chinese Pink Dianthus)



瞿麦

CHANNELS

BL
HT
SI

Herba Dianthi
bitter, cold

shí wěi (Pyrrosia Leaves)



石苇

CHANNELS

BL
LU

Herba Pyrrosiae
bitter, sweet, slightly cold

tōng cǎo (Rice Paper Pith, Tetrapanax)



通草

CHANNELS

LU
ST

Medulla Tetrapanacis Papyriferi
sweet, bland, slightly cold

yì yǐ rén (Seeds of Job's Tears)



薏苡仁

CHANNELS

SP
LU
KI

Semen Coicis Lachyrma-jobi
sweet, bland, slightly cold

yīn chén (Yinchenhao Shoots and Leaves, Capillaris)



茵陈

CHANNELS

LIV
SP
GB
ST

Herba Artemisiae Yinchenhao
bitter, spicy, cool

yù mǐ xū (Cornsilk)



玉米须

CHANNELS

BL
GB
LIV

Stylus Zeae Mays
sweet, neutral

Since the eyes are connected to the entire nervous system, they have a special importance. The eyes reveal the health of your entire body. Through the eyes we can tell which organs are weak and/or toxic. Massaging the eyes will remove stress from the vital organs. Nowadays people use their eyes much more than in the past to read, watch television, and work with computers, electronics and microscopes. This strains them a great deal and makes the openings of the organs loose, so that much of the organ energy is drained out. In Taoism, we regard the eyes as the doorways to the soul as well as the opening of the liver.

A. Bring Chi Energy to the Hands and Eyes

Repeat the procedure for bringing energy to the hands by inhaling; holding the breath; and contracting the sexual organ, buttocks and middle of the anus and both the left and right sides of the anus. Direct the Chi to both eyes. Rub the hands, clench the teeth, place the tongue on the roof of your mouth. Direct the energy to the face and then the hands. When your hands are hot, focus on your eyes until you feel them filled with energy.


Brain
Sinus—Ear
Cerebellum
Lymph Fluid
Blood
Mucous Membrane
Cellular Tissue
Urinary Bladder
Uterus/Prostate
Ovary/Testicle
Kidney (Genitals)
Lumbar Region
Appendix
Transverse Colon
Vein
Liver
Ascending Colon
Portal
Stomach—Pylorus
Heart
Lung
Pleura
Chest
Breast
Trachea Thyroid Gland
Pharynx
Larynx
Brain
Ear—Sinus
Cerebellum
Larynx
Pharynx
Thyroid—Esophagus
Chest
Breast
Lung Pleura
Left Heart
Pancreas
Aorta
Spleen
Transverse Colon
Descending Colon
Lumbar Area
Kidney (Genitals)
Groin
Anus
Urinary Bladder
Cellular Tissue
Mucous Membrane
Blood
Lymph Fluid

Fig. 19 *Eyes are the Windows of the Spirit*

zé xiè (Water Plantain Rhizome, Alisma)



泽泻

CHANNELS

KI
BL

Rhizoma Alismatis
sweet, bland, cold

zhū líng (Polyporus Sclerotium)



猪苓

CHANNELS

SP
KI
BL

Sclerotium Polypori Umbellati
sweet, bland, cool (or neutral)

DO NOT DUPLICATE

cán shā (Silkworm Feces)



蚕沙

CHANNELS

LIV
SP
ST

Excrementum Bombycis Mon
sweet, spicy, warm

dú huó (Pubescent Angelica Root)



独活

CHANNELS

KI
BL

Radix Angelicae Pubescentis
bitter, spicy, warm

hǎi tóng pí (Coral Bean Back)



海桐皮

CHANNELS

LIV
SP
KI

Cortex Erythriniae
bitter, spicy, neutral

cāng ěr zǐ (Cocklebur Fruit)



苍耳子

CHANNELS

LU

Fructus Xanthii Siberici
sweet, bitter, warm, toxic

hǎi fēng téng (Kadsura Stem)



海风藤

CHANNELS

LIV
KI

Caulis Piperis Futokadsurae
spicy, bitter, slightly warm

hǔ gǔ (Tiger Bone)



虎骨

CHANNELS

LIV
KI

Os Tigris
spicy, sweet, warm

DO NOT DUPLICATE

Herbs that Dispel Wind-Dampness

kuān jīn téng (Chinese Tinospora Stem)



CHANNELS

LIV

Ramus Tinosporae Sinensis
bitter, slightly cold

luò shí téng (Star Jasmine Stem)



络石藤

CHANNELS

LIV

Caulis Trachelospermi Jasminoidis
bitter, slightly cold

mù guā (Chinese Quince Fruit)



木瓜

CHANNELS

LIV
SP

Fructus Chaenomelis Lagenariae
sour, slightly warm

qiān nián jiàn (Homalomena Rhizome)



千年健

CHANNELS

KI
LIV

Rhizoma Homalomenae Occultae
spicy, bitter, warm

qín jiāo (Gentiana Macrophylla Root)



秦艽

CHANNELS

GB
LIV
ST

Radix Gentianae Macrophyllae
bitter, spicy, slightly cold

sāng zhī (Mulberry Twig)



桑枝

CHANNELS

LIV

Ramulus Mori Albae
bitter, sweet, slightly cold

DO NOT DUPLICATE

wēi líng xiān (Chinese Clematis Root)



威灵仙

CHANNELS

BL

Radix Clematidis Chinensis
spicy, salty, warm

wǔ jiā pí (Acanthopanax Root Bark)



五加皮

CHANNELS

KI
LIV

Cortex Radicis Acanthopanacis Gracistyli
spicy, bitter, warm

xī xiān cǎo (Siegesbeckia)



希莶草

CHANNELS

KI
LIV

Herba Siegesbeckiae
bitter, cold

DO NOT DUPLICATE

chuān bèi mŭ (Tendrilled Fritillaria Bulb)



川贝母

CHANNELS

HT
LU

Bulbus Fritillariae Cirrhosae
bitter, sweet, cool

dăn nán xīng (Jack-in-the-Pulpit Rhizome & Bile)



胆南星

CHANNELS

LIV
LU
SP

Rhizoma Arisaematis (Processed with Bile)
bitter, cool

fú hăi shí (Pumice)



浮海石

CHANNELS

LU

Pumice
salty, cold

guā lóu (Trichosanthes Fruit)



栝楼

CHANNELS

LI
LU
ST

Fructus Trichosanthis Kirlowii
sweet, cold

guā lóu pí (Trichosanthes Peel, Snake Gourd Peel)



栝楼皮

CHANNELS

LI
LU
ST

Pericarpium Trichosanthis Kirlowii
sweet, cold

guā lóu rén (Trichosanthes Seeds)



栝楼仁

CHANNELS

LI
LU
ST

Semen Trichosanthis Kirlowii
sweet, cold

DO NOT DUPLICATE

hǎi zǎo (Seaweed, Sargassum)



海藻

CHANNELS

KI
LIV
LU
ST

Herba Sargassii
bitter, salty, cold

kūn bù (Kelp, Eckloniae Thallus)



昆布

CHANNELS

KI
LIV
ST

Ecklonia Kurome
salty, cold

qián hú (Hogfennel Root)



前胡

CHANNELS

LU

Radix Peucedani
bitter, spicy, slightly cold

huáng yào zǐ (Dioscorea Bulbifera Tober)



CHANNELS

HT
LIV
LU

Tuber Dioscoreae Bulbiferae
bitter, neutral

pàng dà hǎi (Boat Sterculia Seed)



胖大海

CHANNELS

LI
LU

Sterculiae lychnophorae Semen
sweet, cold

tiān huā fěn (Trichosanthes Root)



天花分

CHANNELS

LU
ST

Trichosanthis Kirlowii Radix
bitter, slightly sweet, cold

DO NOT DUPLICATE

tiān zhú huáng (Siliceous Secretions of Bamboo, Tabasheer)



天竺黄

CHANNELS

GB
HT
LIV

Bambusae Concretio Silicea
sweet, cold

Zhè bèi mŭ (Thunberg Fritillaria Bulb)



浙贝母

CHANNELS

HT
LU

Fritillariae Thunbergii Bulbus
bitter, cold

zhú rù (Bamboo Shavings)



竹茹

CHANNELS

GB
LU
ST

Bambusae Caulis In Taeniam
sweet, slightly cold

DO NOT DUPLICATE

bái fù zǐ (Typhonium Rhizome)



白附子

CHANNELS

SP
ST

Rhizoma Typhonii Gigantei
spicy, sweet, warm, toxic

bái jiè zǐ (White Mustard Seed)



白芥子

CHANNELS

LU

Semen Sinapis Albae
spicy, warm

bái qián (Root and Rhizome of Cynanchum)



白前

CHANNELS

LU

Radix Et Rhizoma Cynanchi Baiqian
spicy, sweet, neutral (or slightly warm)

bàn xià (Pinellia Rhizome)



半夏

CHANNELS

LU
SP
ST

Rhizoma Pinelliae Tematae
spicy, warm, toxic

jié gěng (Root of the Balloon Flower)



桔梗

CHANNELS

LU
(ST)

Platycodi Radix
bitter, spicy, neutral

xuàn fù huā (Inula Flower)



旋覆花

CHANNELS

LIV
LU
ST
SP

Inulae Flos
bitter, spicy, slightly warm

DO NOT DUPLICATE

zào jiăo cì (Spine of Chinese Honeylocust Fruit)



皂角刺

CHANNELS

LIV
ST

Gleditschiae Sinensis Spina
spicy, warm

zhì tiān nán xīng (Prepared Jack in the Pulpit Rhizome)



制天南星

CHANNELS

LIV
LU
SP

Arisaematis Rhizoma preparatum
bitter, spicy, warm, toxic

DO NOT DUPLICATE

bǎi bù (Stemona Root)



百部

CHANNELS

LU

Radix Stemonae
sweet, bitter, slightly warm (or neutral)

mǎ dōu líng (Birthwort Fruit)



马兜铃

CHANNELS

LI
LU

Aristolochiae Fructus
bitter, slightly spicy, cold, toxic

pí pa yè (Loquat Leaf)



枇杷叶

CHANNELS

LU
ST

Folium Eriobotryae Japonicae
bitter, cool

kuǎn dōng huā (Coltsfoot Flower)



款冬花

CHANNELS

LU

Tussilaginis Farfarae Flos
spicy, warm

mù hú dié (Oroxylum Seeds)



木蝴蝶

CHANNELS

LIV
LU

Oroxyli Semen
sweet, bland, cool

sāng bái pí (Bark of Mulberry Root)



桑白皮

CHANNELS

LU
SP

Cortex Radicis Mori Albae
sweet, cold

DO NOT DUPLICATE


Eyeball
Optic Nerve
Pituitary Gland
Thalamus

Fig. 20 *Eyes are the Doorways to the Soul*



Fig. 21 *Use the Fingertips to Gently Massage the Eyeballs*

tíng lì zǐ (Descurainia Seeds)



葶苈子

CHANNELS

LU
BL

Semen Descurainiae Seu Lepidii
spicy, bitter, very cold

xìng rén (Apricot Seed or Kernel)



杏仁

CHANNELS

LI
LU

Semen Pruni Armeniacae
bitter, slightly warm, slightly toxic

zǐ sū zǐ (Purple Perilla Fruit, Perilla Seed)



紫苏子

CHANNELS

LI
LU

Fructus Perillae Frutescentis
spicy, warm

zǐ wǎn (Purple Aster Root)



紫菀

CHANNELS

LU

Radix Asteris Tatarici
bitter, slightly warm, sweet

DO NOT DUPLICATE

bái dòu kòu (Round Cardamom Fruit)



白豆寇

CHANNELS

LU
SP
ST

Fructus Amomi Kravanh
spicy, aromatic slightly warm (or neutral)

cāng zhú (Black Atractylodes Rhizone)



苍术

CHANNELS

SP
ST

Rhizoma Atractylodis
spicy, bitter, warm, aromatic

cǎo dòu kòu (Katsumada's Galangal Seeds)



草豆蔻

CHANNELS

SP
ST

Semen Alpiniae Katsumadai
spicy, warm, aromatic

cǎo guǒ (Tsaoko Fruit)



草果

CHANNELS

SP
ST

Fructus Amomi Tsao-ko
spicy, warm

hòu pò (Magnolia Bark)



厚朴

CHANNELS

LI
LU
SP
ST

Cortex Magnoliae Officinalis
bitter, spicy, warm, aromatic

huò xiāng (Patchouli, Agastache)



藿香

CHANNELS

LU
SP
ST

Herba Agastaches Rugosus, Herba Pogostemonis
spicy, slightly warm

DO NOT DUPLICATE

Aromatic Herbs that Transform and Dissolve Dampness

pèi lán (Eupatorium)



佩兰

CHANNELS

SP
ST

Herba Eupatorii Fortunei
spicy, neutral

shā rén (Cardamom (Grains of Paradise Fruit))



砂仁

CHANNELS

SP
ST

Fructus Amomi
spicy, warm, aromatic

DO NOT DUPLICATE

gǔ yá (Rice Sprout)



谷芽

CHANNELS

SP
ST

Fructus Germinatus Oryzae Sativae
sweet, neutral

jī nèi jīn (Chicken Gizzard's Internal Lining)



鸡内金

CHANNELS

BL
SI
SP
ST

Endothelium Comeum Gigeriae Galli
sweet, neutral

lái fú zǐ (Daikon, Radish Seed)



莱菔子

CHANNELS

LU
SP
ST

Semen Raphani Sativi
spicy, sweet, neutral

mài yá (Barley Sprout, Malt)



麦芽

CHANNELS

LIV
SP
ST

Fructus Germinatus Hordei Vulgaris
sweet, neutral

shān zhā (Hawthorn Fruit)



山楂

CHANNELS

LIV
SP
ST

Fructus Crataegi
sour, sweet, slightly warm

shén qǔ (Medicated Leaven)



神曲

CHANNELS

SP
ST

Massa Medica Fermentata
sweet, spicy, warm

DO NOT DUPLICATE

chén pí (Orange Peel, Citrus Peel, Tangerine Peel)



陈皮

CHANNELS

LU
SP
ST

Pericarpium Citri Reticulatae
spicy, bitter, warm, aromatic

chén xiāng (Aloeswood, Aquilaria)



沉香

CHANNELS

KI
SP
ST

Lignum Aquilariae Agallochae
spicy, bitter, warm

chuān liàn zǐ (Sichuan Pagoda Tree Fruit)



川楝子

CHANNELS

LIV
SI
ST
BL

Fructus Meliae Toosendan
bitter, cold, slightly toxic

dà fù pí (Betel Husk)



大腹皮

CHANNELS

LI
SI
SP
ST

Pericarpium Arecae Catechu
spicy, slightly warm

fó shǒu (Finger Citron Fruit)



佛手

CHANNELS

LIV
LU
ST
SP

Fructus Citri Sacrodactylis
spicy, bitter, slightly warm

ju he (Citrus/Tangerine Seeds)



Semen Citri Reticulatae
bitter, neutral

DO NOT DUPLICATE

jú hóng (Outermost Citrus Peel, Tangerine Peel, Orange Peel)



橘红

CHANNELS

LU
ST

Exocarpium Citri Rubrum
spicy, bitter, warm

méi guī huā (Young Flower of Chinese Rose (Bud))



玫瑰花

CHANNELS

LIV
SP

Flos Rosae Rugosae
sweet, slightly bitter, warm

qīng pí (Immature Tangerine Peel)



青皮

CHANNELS

GB
LIV
ST

Pericarpium Citri Reticulatae Viride
bitter, spicy, warm

lì zhī hé (Leechee Nut)



荔枝核

CHANNELS

LIV
ST

Semen Litchi Chinensis
sweet, astringent, warm

mù xiāng (Costus Root, Saussurea)



木香

CHANNELS

GB
LI
SP
ST

Radix Auklandiae Lappae
spicy, bitter, warm

shì dì (Persimmon Calyx)



柿蒂

CHANNELS

ST

Calyx Diospyri Kaki
bitter, astringent, neutral

DO NOT DUPLICATE

tán xiāng (Sandalwood (Heartwood))



檀香

CHANNELS

LU
SP
ST

Lignum Santali Albi
spicy, warm, aromatic

wū yào (Lindera Root)



乌药

CHANNELS

BL
KI
LU
SP

Radix Linderae Strychnifoliae
spicy, warm

xiāng fù (Nut Grass Rhizome)



香附

CHANNELS

LIV
SJ
SP

Rhizoma Cyperi Rotundi
spicy, slightly warm, slightly sweet, neutral

xiè bái (Bulb of Chinese Chive)



薤白

CHANNELS

LI
LU
ST

Bulbus Allii
spicy, bitter, warm

zhǐ ké (Bitter Orange Peel)



枳壳

CHANNELS

SP
ST

Fructus Citri Aurantii
bitter, cool

zhǐ shí (Immature Fruit of the Bitter Orange)



枳实

CHANNELS

LI
SP
ST

Fructus Immaturus Citri Aurantii
bitter, spicy, slightly cold

DO NOT DUPLICATE

ài yè (Mugwort Leaf, Artemisia)



艾叶

CHANNELS

SP
LIV
KI

Artemisiae Argyi Folium
bitter, spicy, warm

bái jí (Bletilla Rhizome)



白芨

CHANNELS

LU
ST
LIV

Rhizoma Bletillae
bitter, sweet, cool, astringent

bái máo gēn (Woolly Grass Rhizome)



白茅根

CHANNELS

LU
ST
SI
BL

Rhizoma Imperatae Cylindricae
sweet, cold

cè băi yè (Biota Leaves, Leafy Twig of Arborvitae)



侧柏叶

CHANNELS

LU
LIV
LI.

Cacumen Biotae Orientalis
bitter, astringent, slightly cold

dài jì (Japanese Thistle, Cirsium)



大蓟

CHANNELS

LIV
SP
HT

Herba Cirsii Japonici
sweet, cool

dì yú (Burnet Bloodwort Root)



地榆

CHANNELS

LIV
LI
ST

Radix Sanguisorbae
bitter, sour, slightly cold

DO NOT DUPLICATE

fú lóng gān (Ignited Yellow Earth)



伏龙肝

CHANNELS

SP
ST

Terra Flava Usta
spicy, warm

huái huā mǐ (Pagoda Tree Flower Bud)



槐花米

CHANNELS

LIV
LI.

Flos Immaturus Sophorae Japonicae
bitter, cool

pú huáng (Catail Pollen)



蒲黄

CHANNELS

LIV
HT
PER
SP

Pollen Typhae
sweet, spicy, neutral

huā ruǐ shí (Ophicalcite)



花蕊石

CHANNELS

LIV

Ophicalcitum
sour, astringent, neutral

ǒu jié (Node of the Lotus Rhizome)



藕节

CHANNELS

LU
ST
LIV

Nodus Rhizomatis Nelumbinis Nuciferae
sweet, astringent, neutral

qiàn cǎo (Madder Root, Rubia Root)



茜草

CHANNELS

HT
LIV

Radix Rubiae Cordifoliae
bitter, cold

DO NOT DUPLICATE

sān qī (Notoginseng Root, Pseudoginseng Root)



三七

CHANNELS

LIV
ST
LI.

Radix Pseudoginseng
sweet, slightly bitter, warm

xiān hè cǎo (Agrimony)



仙鹤草

CHANNELS

LU
LIV
SP

Herba Agrimoniae Pilosac
bitter, spicy, neutral

xiě yú tàn (Charred Human Hair)



血余炭

CHANNELS

HT
LIV
KI

Crinis Carbonisatus
bitter, neutral

DO NOT DUPLICATE

B. For the Eyeballs and Surrounding Area

Close your eyes. Use your fingertips to gently massage your eyeballs through your closed eyelids, six to nine times clockwise, then six to nine times counterclockwise. Then gently massage the area around the lids the same number of times. Be aware of painful spots and massage those places until the pain goes away. Pay special attention to the inner and outer corners of the eyes. These are points of the gall bladder meridian and will relieve eye ailments if massaged.

C. Pull up the Eyelids

Pulling up the eyelids will increase the fluid. Use the thumb and index finger to pinch, pull up and release the eyelids six to nine times.



***Fig. 22** Pull Up the Eyelids*

chuān niú xī (Cyathula Root)



川牛膝

CHANNELS

LIV
KI

Radix Cyathula Officinalis
bitter, sour, neutral

dān shēn (Salvia Root)



丹参

CHANNELS

HT
PER
LIV

Radix Salviae Miltiorrhizae
bitter, slightly cold

hóng huā (Safflower Flower)



红花

CHANNELS

HT
LIV

Flos Carthami Tinctorii
spicy, warm

chuān xiōng (Szechuan Lovage Root)



川芎

CHANNELS

LIV
GB
PER

Rhizoma Ligustici Chuanxiong
spicy, warm

é zhú (Zedoary Rhizome)



莪术

CHANNELS

LIV
SP

Rhizoma Curcumae Zedoariae
bitter, spicy, warm

hú zhàng (Bushy Knotweed Root and Rhizome)



胡杖

CHANNELS

LIV
GB
LU

Radix Et Rhizoma Polygoni Cuspidati
bitter, cold

DO NOT DUPLICATE

huái niú xī (Achyranthes Root)



懷牛膝

CHANNELS

LIV
KID

Radix Achyranthis Bidentatae
bitter, sour, neutral

jiāng huáng (Tumeric Rhizome)



姜黄

CHANNELS

SP
ST
LIV

Rhizoma Curcumae Longae
spicy, bitter, warm

lù lù tōng (Sweetgum Fruit)



路路通

CHANNELS

LIV
ST

Fructus Liquidambaris Taiwaniae
bitter, neutral

jī xiě téng (Spatholobus, Millettia Root and Vine)



鸡血藤

CHANNELS

HT
LIV
SP

Caulis Milletiae Seu Spatholobi
bitter, sweet, warm

Liú jì (Artemesia)



刘寄

CHANNELS

HT
SP

Herba Artemisiae Anomalae
bitter, warm

mò yào (Myrrh)



没药

CHANNELS

HT
LIV
SP

Resina Myrrhae
bitter, neutral

DO NOT DUPLICATE

rǔ xiāng (Frankincense Resin)



乳香

CHANNELS

HT
LIV
SP

Resina Olibani
spicy, bitter, warm

sān léng (Bur Reed Rhizome)



三棱

CHANNELS

LIV
SP

Rhizoma Sparganii
bitter, spicy, neutral

shuǐ zhì (Leech)



水蛭

CHANNELS

LIV
BL

Hirudo seu Whitmania
salty, bitter, neutral, slightly toxic

sī guā luò (Dried Skeleton of Vegetable Sponge)



丝瓜络

CHANNELS

LU
ST
LIV

Fasciculus Vascularis Luffae
sweet, neutral

sū mù (Sappan Wood)



苏木

CHANNELS

HT
LIV
SP

Lignum Sappan
sweet, salty, neutral, slightly spicy

táo rén (Peach Kernel)



桃仁

CHANNELS

HT
LI
LIV
ST

Semen Pruni Persicae
bitter, sweet, neutral

DO NOT DUPLICATE

wǎ lèng zǐ (Cockle Shell, Ark Shell)



瓦楞子

CHANNELS

LIV
SP

Concha Arcae Inflatae
sweet, salty, neutral

wáng bù liú xíng (Vaccaria Seeds)



王不留行

CHANNELS

LIV
ST

Semen Vaccariae Segetalis
bitter, neutral

wǔ líng zhī (Flying Squirrel Feces)



五灵脂

CHANNELS

LIV
SP

Feces Trogopterori Seu Pteromi
bitter, sweet, warm

xuè jié (Dragon's Blood Resin)



血竭

CHANNELS

HT
LIV

Sanguis Draconis
sweet, salty, neutral

yán hú suǒ (Corydalis Rhizome)



延胡索

CHANNELS

HT
LIV
LU

Corydalis Rhizome
spicy, bitter, warm

yì mǔ cǎo (Chinese Motherwort)



益母草

CHANNELS

HT
LIV
BL
PER

Herba Leonuri Heterophylli
spicy, bitter, slightly cold

DO NOT DUPLICATE

yù jīn (Tumeric Tuber)



郁金

CHANNELS

HT
LU
LIV
GB

Tuber Curcumae
spicy, bitter, cold

zé lán (Bugleweed)



泽兰

CHANNELS

LIV
SP

Herba Lycopi Lucidi
bitter, spicy, slightly warm, aromatic

DO NOT DUPLICATE

bì bá (Long Pepper Fruit)



荜茇

CHANNELS

ST
LI.

Fructus Piperis Longi
spicy, hot

chuān jiāo (Fruit of Szechuan Pepper)



川椒

CHANNELS

KI
SP
ST

Pericarpium Zanthoxyli Bungeani
spicy, hot, slightly toxic

dīng xiāng (Clove Flower Bud)



丁香

CHANNELS

KI
SP
ST

Flos Caryophylli
spicy, warm

fù zi (Processed Aconite)



附子

CHANNELS

HT
KI
SP

Radix Lateralis Praeparatus Aconiti Carmichaeli
spicy, hot, toxic

gān jiāng (Dried Ginger Rhizome)



干姜

CHANNELS

HT
LU
SP
ST

dry Rhizoma Zingiberis
spicy, hot

gāo liáng jiāng (Lesser Galangal Rhizome)



高良姜

CHANNELS

SP
ST

Rhizoma Alpiniae Officinari
spicy, hot

DO NOT DUPLICATE

hú jiāo (Black Pepper)



胡椒

CHANNELS

LI
ST

Fructus Piperis Nigri
spicy, hot

ròu guì (Inner Brack or Saigon Cinnamon)



肉桂

CHANNELS

HT
KI
LIV
SP

Cortex Cinnamomi Cassiae
spicy, sweet, hot

wú zhū yú (Evodia Fruit)



吴茱萸

CHANNELS

KI
LIV
SP
ST

Fructus Evodiae Rutaecarpae
spicy, bitter, hot, slightly toxic, very dry

xiǎo huí xiāng (Fennel Fruit)



小茴香

CHANNELS

LIV
KI
SP
ST

Fructus Foeniculi Vulgaris
spicy, warm

DO NOT DUPLICATE

bái zhú (White Atractylodes Rhizome)



白术

CHANNELS

SP
ST

Rhizoma Atractylodis Macrocephalae
bitter, sweet, warm

dà zǎo (Date, Jujube)



大枣

CHANNELS

SP
ST

Fructus Zizyphi Jujubae
sweet, warm

dǎng shēn (Codonopsis Root)



党参

CHANNELS

LU
SP

Radix Codonopsitis Pilosulae
sweet, neutral

fēng mì (Honey)



蜂蜜

CHANNELS

SP
ST
LI.

Mel
sweet, neutral

gān cǎo (Licorice Root)



甘草

CHANNELS

All

Radix Glycyrrhizae
sweet, neutral

huáng jīng (Siberian Solomon Seal Rhizome, Polygonatum)



黄精

CHANNELS

KI
LU
ST

Rhizoma Polygonati
sweet, neutral

DO NOT DUPLICATE

huáng qí (Astragalus)



黄芪

CHANNELS

LU
SP

Radix Astragali Membranacei
sweet, slightly warm

rén shēn (Ginseng Root)



人参

CHANNELS

LU
SP

Radix Ginseng
sweet, slightly bitter, slightly warm

shān yao (Chinese Yam Rhizome, Dioscorea)



山药

CHANNELS

KI
LU
SP

Radix Dioscoreae Oppositae
sweet, neutral

tài zǐ shēn (Pseudostellaria)



太子参

CHANNELS

LU
SP

Radix Pseudostellariae
sweet, slightly bitter, neutral

yí táng (Barley Malt Sugar, Maltose)



饴糖

CHANNELS

LU
SP
ST

Saccharum Granorum
sweet, slightly warm

zhì gān căo (Honey Fried Licorice Root)



炙甘草

CHANNELS

All

Radix Glycyrrhizae
sweet, warm

DO NOT DUPLICATE

bái sháo (White Peony Root)

白芍

CHANNELS

LIV
SP



Radix Albus Paeoniae Lactiflorae
bitter, sour, cool

ē jiāo (Ass Hide Glue, Donkey Hide Gelatin)

阿胶

CHANNELS

KID
LIV
LU



Gelatinum Corii Asini
sweet, neutral

hé shǒu wū (Fleeceflower Root, Ho Shou Wu, Polygonum)

何首乌

CHANNELS

LIV
KI



Radix Polygoni Multiflori
bitter, sweet, astringent, slightly warm

dāng guī (Chinese Angelica Root)

当归

CHANNELS

HT
LIV
SP



Radix Angelicae Sinensis
sweet, spicy, bitter, warm

gǒu qǐ zǐ (Chinese Wolfberry Fruit, Matrimony Vine Fruit)

枸杞子

CHANNELS

LIV
LU
KI



Fructus Lycii Chinensis
sweet, neutral

lóng yǎn ròu (Flesh of the Longan Fruit)

龙眼肉

CHANNELS

HT
SP



Arillus Euphoriae Longanae
sweet, warm

DO NOT DUPLICATE

D. For the Eye Sockets

Bend your index fingers and use the lower section (second phalanx) of each thumb to rub the upper and lower bones of the eye sockets six to nine times.



Fig. 23 *Massage the Eye Sockets*

E. For getting a Tear out

Hold an index finger up about eight inches from the eyes, or put a dot on the wall five or six feet away from you. Stare at it intently without blinking your eyes until you feel like a fire is burning in them. The Taoists believe that the toxins will burn out of the body through the eyes. They will begin to tear. Do this to strengthen your eyes. Then, rub your hands until warm; close your eyes and cover your eye sockets with your palms. Feel the Chi from the hands absorbed into the eyes. Rotate your eyes six to nine times, first in a clockwise direction, then counterclockwise.

sāng shèn (Mulberry Fruit Spike, Morus Fruit)



桑葚

CHANNELS

HT
LIV
KI

Fructus Mori Albae
sweet, cold

shú dì huáng (Chinese Foxglove Root, Steamed with Water or Alcohol)



熟地黄

CHANNELS

LIV
KI
(HT)

Processed Radix Rehmanniae
sweet, slightly warm

DO NOT DUPLICATE

bā jǐ tiān (Morinda Root)



巴戟天

CHANNELS

KI
LIV

Morindae Officinalis Radix
spicy, sweet, warm

bǔ gǔ zhī (Psoralea Fruit)



补骨脂

CHANNELS

KI
SP

Fructus Psoraleae Corylifoliae
spicy, bitter, very warm

dōng chóng xià cǎo (Cordyceps, Chinese Caterpillar Fungus)



冬虫夏草

CHANNELS

LU
KI

Cordyceps Chinensis
sweet, warm

dù zhòng (Eucommia Bark)



杜仲

CHANNELS

KI
LIV

Cortex Eucommiae Ulmoidis
sweet, slightly spicy, warm

gǒu jǐ (Chain Fern Rhizome)



狗脊

CHANNELS

KI
LIV

Rhizoma Cibotii Barometsis
bitter, sweet, warm

gǔ suì bǔ (Drynaria Rhizome)



骨碎补

CHANNELS

KI
LIV

Radix Drynariae
bitter, warm

DO NOT DUPLICATE

hăi mă (Sea Horse)



海马

CHANNELS

KI
LIV

Hippocampus
sweet, salty, warm

lù jiăo jiāo (Deer Horn Gelatin)



鹿角胶

CHANNELS

LIV
KI

Gelatinum Cornu Cervi
sweet, salty, warm

shā yuàn zĭ (Astragalus Seed, Flattened Milkvetch Seed)



沙苑子

CHANNELS

KI
LIV

Semen Astragali Complanati
sweet, warm

jiŭ cài zi (Chinese Leek/Onion Seed)



韭菜子

CHANNELS

KI
LIV

Semen Allii Tuberosi
spicy, sweet, warm

ròu cōng róng (Fleshy Stem of the Broomrape)



肉苁蓉

CHANNELS

LI
KI

Herba Cistanchis Deserticolae
sweet, salty, warm

suŏ yáng (Fleshy Stem of Cynomorium)



锁阳

CHANNELS

LI
KI
LIV

Herba Cynomorii Songarici
sweet, warm

DO NOT DUPLICATE

tù sī zǐ (Chinese Dodder Seeds)



菟丝子

CHANNELS

KI
LIV

Semen Cuscutae Chinensis
spicy, sweet, neutral

xù duàn (Japanese Teasel Root)



续断

CHANNELS

KI
LIV

Radix Dipsaci
bitter, spicy, slightly warm

yīn yáng huò (Aerial Parts of Epimedium)



阴阳藿

CHANNELS

KI
LIV

Herba Epimedii
spicy, sweet, warm

xiān máo (Golden Eye Grass Rhizome)



仙茅

CHANNELS

KI
LIV

Rhizoma Curculiginis Orchioidis
spicy, hot, toxic

yì zhī rén (Black Cardamom, Alpinia Oxyphylla Fruit)



益知仁

CHANNELS

KI
SP

Fructus Alpiniae Oxyphyllae
spicy, warm

zǐ hé chē (Human Placenta)



紫河车

CHANNELS

LIV
LU
KI

Placenta Hominis
sweet, salty, warm

DO NOT DUPLICATE

bǎi hé (Lily Bulb)



百合

CHANNELS

HT
LU

Bulbus Lilii
sweet, slightly bitter, slightly cold

biē jiǎ (Chinese Soft Shelled Turtle Shell)



鳖甲

CHANNELS

LIV
SP

Carapax Amydae Sinensis
salty, cold

guī bǎn (Fresh Water Turtle Shell, Testudinis)



龟板

CHANNELS

HT
KI
LIV

Plastrum Testudinis
salty, sweet, cold

hàn lián cǎo (Eclipta)



旱莲草

CHANNELS

KI
LIV

Herba Ecliptae Prostratae
sweet, sour, cool

hēi zhī ma (Black Sesame Seeds)



黑芝麻

CHANNELS

KI
LIV

black Semen Sesame Indici
sweet, neutral

luó hàn guǒ (Momordica Fruit)



罗汉果

CHANNELS

LU
LI
(SP)

Fructus Momordicae Grosvenori
sweet, cool (or neutral)

DO NOT DUPLICATE

mài mén dōng (Ophiopogon Tuber)



麦门冬

CHANNELS

SP
ST
HT
(LU)

Tuber Ophiopogonis Japonici
sweet, slightly bitter, slightly cold

nu zhēn zǐ (Privet Fruit, Ligustrum)



女真子

CHANNELS

KI
LIV

Fructus Ligustri Lucidi
bitter, sweet, cool (or neutral)

sāng jì shēng (Mulberry Mistletoe Stems)



桑寄生

CHANNELS

KI
LIV

Ramulus Loranthi Seu Visci
bitter, neutral

shí hú (Dendrobium Stem)



石斛

CHANNELS

KI ST

Herba Dendrobii
sweet, slightly salty, bland, cold

tiān mén dōng (Asparagus Tuber)



天门冬

CHANNELS

KI
LU

Tuber Asparagi Cochinensis
sweet, bitter, very cold

xī yáng shēn (American Ginseng Root)



西洋参

CHANNELS

HT
KI
LU

Radix Panacis Qinquifolii
sweet, slightly bitter, cold

DO NOT DUPLICATE

yín ěr (Fruiting Body of Tremella, Wood Ear)



银耳

CHANNELS

LU
ST

Fructificatio Tremellae Fuciformis
sweet, bland, neutral

yù zhú (Solomon's Seal Rhizome, Polygonatum)



玉竹

CHANNELS

LU
ST

Rhizoma Polygonati Odorati
sweet, slightly cold

Missing Sha Shen

DO NOT DUPLICATE

bái guǒ (Ginkgo Nut)



白果

CHANNELS

LU

Semen Ginkgonis Bilobae
sweet, bitter, astringent, neutral, slightly toxic

chì shí zhī (Halloysite, Kaolin)



赤石脂

CHANNELS

ST
LI.
(SP)

Hallyositum Rubrum
sweet, sour, astringent, warm

chūn pí (Ailanthus Bark or Root Bark)



椿皮

CHANNELS

LI
ST
LIV

Cortex Ailanthi Altissimae
bitter, astringent, cold

fù pén zǐ (Chinese Rasberry)



覆盆子

CHANNELS

KI
LIV

Fructus Rubi Chingii
sweet, astringent, slightly warm

fú xiǎo mài (Wheat Grain (Not Yet Ripe))



浮小麦

CHANNELS

HT

Fructus Levis Tritici Aestivi
sweet, salty, cool

hǎi piāo xiāo (Cuttlefish Bone, Cuttlebone)



海螵蛸

CHANNELS

KI
LIV
ST

Os Sepiae Seu Sepiellae
salty, astringent, slightly warm

DO NOT DUPLICATE

hè zǐ (Myrobalan Fruit)



荷子

CHANNELS

LU
ST
LI.

Fructus Terminaliae Chebulae
bitter, sour, astringent, neutral

jīn yīng zǐ (Cherokee Rosehip)



金櫻子

CHANNELS

BL
KI
LI.

Fructus Rosae Laevigatae
sour, astringent, neutral

lián xū (Lotus Stamen)



莲须

CHANNELS

HT
KI

Stamen Nelumbinis
sweet, astringent, neutral

lián zǐ (Lotus Seed)



连子

CHANNELS

HT
KI
SP

Semen Nelumbinis Nuciferae
sweet, astringent, neutral

má huáng gēn (Ephedra Root)



麻黄根

CHANNELS

LU

Radix Ephedrae
sweet, neutral

nuò dào gēn xū (Glutinous Rice Root)



糯稻根鬚

CHANNELS

KI
LIV
LU

Radix Oryzae Glutinosae
sweet, neutral

DO NOT DUPLICATE



Fig. 24 *Getting a Tear Out*



Fig. 25 *Absorbing the Chi into the Eyes*


Cerebrum
Tear Gland
Tear Duct
Inner Eye
Eustachian Tube
Auditory Nerve
Salivary Glands

Fig. 26 *Parts of the Eyes Connect with Senses and Brain*

qiàn shí (Euryale Seeds)



芡实

CHANNELS

KI
SP

Semen Euryalis Ferocis
sweet, astringent, neutral

ròu dòu kòu (Nutmeg Seeds)



肉豆蔻

CHANNELS

LI
SP
ST

Semen Myristicae Fragrantis
spicy, warm

sāng piāo xiāo (Mantis Egg Case)



桑螵蛸

CHANNELS

KI
LIV

Ootheca Mantidis
sweet, salty, neutral

shān zhū yú (Asiatic Cornelian Cherry Fruit, Cornus)



山茱萸

CHANNELS

KI
LIV

Fructus Corni Officinalis
sour, slightly warm

wǔ bèi zǐ (Gallnet of Chinese Sumac)



五倍子

CHANNELS

KI
LI
LU

Galla Rhois
sour, salty, cold

wū méi (Mume Fruit)



乌梅

CHANNELS

LI
LIV
LU
SP

Fructus Pruni Mume
sour, warm

DO NOT DUPLICATE

wǔ wèi zǐ (Schisandra Fruit)



五味子

CHANNELS

HT
KI
LU

Fructus Schisandrae Chinensis
sour, warm

DO NOT DUPLICATE

cí shí (Magnetite)



磁石

CHANNELS

KI
LIV

Magnetitum
spicy, salty, cold

dài zhě shí (Hematite)



代赭石

CHANNELS

HT
LIV
PER

Haematitum
bitter, cold

hŭ pò (Amber)



琥魄

CHANNELS

BL
HT
LIV

Succinum
sweet, neutral

lóng chĭ (Fossilized Mammal Teeth)



龙齿

CHANNELS

HT
KI
LIV

Dens Draconis
astringent, cool

lóng gŭ (Fossilized Mammal Bones)



龙骨

CHANNELS

HT
KI
LIV

Os Draconis
sweet, astringent, neutral

mŭ lì (Oyster Shell)



牡蛎

CHANNELS

LIV
KI

Concha Ostreae
salty, astringent, cool

DO NOT DUPLICATE

zhēn zhū mǔ (Mother of Pearl)



珍珠母

CHANNELS

HT
LIV

Concha Margaratiferae
sweet, salty, cold

zǐ shí yīng (Flourite)



紫石英

CHANNELS

HT
LIV

Fluoritum
sweet, warm

DO NOT DUPLICATE

bǎi zǐ rén (Arbor Vitae Seed, Biota Seed)



柏子仁

CHANNELS

- HT
- KI
- LI.

Semen Platycladi
sweet, neutral

hé huàn huā (Mimosa Tree Flower)



合换花

CHANNELS

- HT
- LIV

Flos Albizziae Julibrissinis
sweet, neutral

hé huān pí (Mimosa Tree Bark)



合欢皮

CHANNELS

- HT
- LIV

Cortex Albizziae Julibrissinis
sweet, neutral

suān zǎo rén (Sour Jujube Seed, Zizyphus - Raw Herb Shown)



酸枣仁

CHANNELS

- GB
- HT
- LIV
- SP

Semen Zizyphi Spinosae
sweet, sour, neutral

yè jiāo téng (Fleeceflower Vine, Polygonum Vine)



夜交藤

CHANNELS

- HT
- LIV

Polygoni Multiflori Caulis
sweet, slightly bitter, neutral

yuán zhì (Chinese Senega Root)



元志

CHANNELS

- HT
- LU
- LIV

Radix Polygalae Tenuifoliae
bitter, spicy, slightly warm

DO NOT DUPLICATE

bīng piàn (Borneol)



冰片

CHANNELS

HT
LU
SP

Borneolum
spicy, bitter, cool

shí chāng pú (Sweetflag Rhizome)



石菖蒲

CHANNELS

HT
ST

Rhizoma Acori Graminei
spicy, slightly warm, aromatic

DO NOT DUPLICATE

bái jí lí (Caltrop Fruit, Tribulus)



白蒺藜

CHANNELS

- LIV
- LU

Fructus Tribuli Terrestris
spicy, bitter, warm

dì lóng (Earthworm)



地龙

CHANNELS

- BL
- LIV
- LU
- SP

Lumbricus
salty, cold

gōu téng (Gambir Vine Stems and Thorns)



钩藤

CHANNELS

- HT
- LIV

Ramulus Uncariae Cum Uncis
sweet, cool

jiāng cán (Body of Sick Silkworm)



僵蚕

CHANNELS

- LIV
- LU

Bombyx Batryticatus
spicy, salty, neutral

líng yáng jiāo (Antelope Horn)



羚羊角

CHANNELS

- HT
- LIV

Comu Antelopis Saiga-tatarici
salty, cold

quán xiē (Scorpion, Buthus)



全蝎

CHANNELS

- LIV

Buthus Martensis
salty, spicy, neutral, toxic

DO NOT DUPLICATE

Substances that Extinguish Wind and Stop Tremors

shí jué míng (Abalone Shell)



石决明

CHANNELS

KI
LIV

Concha Haliotidis
salty, cold

tiān má (Gastrodia Rhizome)



天麻

CHANNELS

LIV

Rhizoma Gastrodiae
sweet, neutral

wú gōng (Centipede)



蜈蚣

CHANNELS

LIV

Scolopendra Subspinipes
spicy, warm, toxic

DO NOT DUPLICATE

F. Pull in the Eyeballs

The eyes are divided into five parts. Each part is closely connected with the organs and nerves. Become aware of the eyes.

Pulling and pressing the eyeballs will exercise the organs, sense, glands and the brain. This is also the best exercise for the eye muscles. The eyes have many muscles which we do not exercise very much and, thus, they become weak, contributing to poor eyesight.

1. With the eyes still closed and cupped by the palms, inhale, contract the anus and sexual organ, and pull the eyeballs back into the sockets.
2. Contract the middle of the anus and the middles of the eyeballs.
3. Contract the front of the anus and the tops of the eyeballs.
4. Contract the back of the anus and the bottoms of the eyeballs.
5. Contract the right side of the anus and the right sides of the eyeballs.
6. Contract the left side of the anus and the left sides of the eyeballs. This exercise not only strengthens the eyes but also the pituitary and pineal glands and the inner ear including the ear drum and canals. When you pull the eyeballs in and upward and look toward the crown, you are exercising the upper muscles and stimulating the pituitary gland and pineal gland.

When you contract and pull in the middle of your eyeballs, you are exercising the back of the eye muscles and the inner ear.

When pulling in the outer corners of the eyes, you are strengthening the side eye muscles as well as the ear canals end the ear drums.

When pulling in the inner corners of the eyes, you are strengthening the inner side muscles, the tear ducts and the nose.

When pulling in the lower parts of the eyes, you are pressing the lower part of the ear canals and the nervous system.

bīng lang (Betel Nut)



槟榔

CHANNELS

LI
ST

Semen Arecae Catechu
spicy, bitter, warm

fěi zi (Torreya Seeds)



榧子

CHANNELS

LI
LU
ST

Semen Torreyae Grandis
sweet, astringent, neutral

hè shī (Carpesium Fruit)



鹤虱

CHANNELS

LIV

Fructus Carpesii Seu Dauci
bitter, spicy, neutral, slightly toxic

cháng shān (Dichroa Root)



常山

CHANNELS

HT
LIV
LU

Radix Dichroae Febrifugae
bitter, spicy, cold, toxic

guàn zhòng (Dryopteris Root)



贯众

CHANNELS

LIV
SP

Rhizoma Guanchong
bitter, cold

léi wán (Fruiting Body of Omphalia)



雷丸

CHANNELS

LI ST

Scierotium Omphaliae Lapidescentis
bitter, cold, slightly toxic

DO NOT DUPLICATE

shĭ jūn zĭ (Rangoon Creeper Fruit with Seeds)



使君子

CHANNELS

SP
ST

Fructus Quisqualis
sweet, warm

DO NOT DUPLICATE

ér chá (Paste from Dried Conc. Decoction of Black or Brown Cutch)



儿茶

CHANNELS

LU

Pasta Acaciae Seu Uncariae
bitter, astringent, neutral

liú huáng (Sulpher)



硫磺

CHANNELS

KI LI
PER

Sulphur
sour, hot, toxic

mǎ qián zǐ (Nux Vomica Seeds)



马钱子

CHANNELS

LIV
SP

Semen Strychnotis
bitter, cold, toxic

míng fán (Alum)



明矾

CHANNELS

LI
LIV
LU
SP
ST

Alumen
sour, astringent, cold

péng shā (Borax)



硼砂

CHANNELS

LU
ST

Borax
sweet, salty, cool

shān cí gū (Bulb of Chinese Tulip)



山茨菇

CHANNELS

LIV
ST

Pseudobulbus Shancigu
sweet, cold, slightly toxic

DO NOT DUPLICATE

shé chuáng zĭ (Cnidium Seeds)



蛇床子

CHANNELS

KI
SP

Fructus Cnidii Monnieni
spicy, bitter, warm

xióng huáng (Realgar)



雄黄

CHANNELS

HT
LIV
ST

Realgar
spicy, bitter, warm, toxic

zhāng năo (Camphor)



樟脑

CHANNELS

HT

Camphora
spicy, hot, toxic

DO NOT DUPLICATE

Pinyin Name Index

ài yè 19
bā dòu 10
bā jǐ tiān 24
bā yuè zhá 11
bái biǎn dòu 07
bǎi bù 15
bái dòu kòu 16
bái fù zǐ 14
bái guǒ 26
bǎi hé 25
bái huā shé shé cǎo 06
bái jí 19
bái jí lí 30
bài jiàng cǎo 06
bái jiè zǐ 14
bái máo gēn 19
bái qián 14
bái sháo 23
bái tóu wēng 06
bái wēi 04
bái xiǎn pí 06
bái zhǐ 01
bái zhú 22
bǎi zǐ rén 28
bàn biàn lián 11
bǎn lán gēn 06
bàn xià 14
bàn zhī lián 06
bì xiè 11
bì bá 21
biǎn xù 11
biē jiǎ 25
bīng lang 31
bīng piàn 29
bò he 02
bǔ gǔ zhī 24
cán shā 12
cāng ěr zǐ 12
cāng zhú 16
cǎo dòu kòu 16
cǎo guǒ 16
cè bǎi yè 19
chái hú 02
chán tuì 02
cháng shān 31
chē qián zǐ 11
chén pí 18
chén xiāng 18
chì sháo 04
chì shí zhī 26
chì xiǎo dòu 11
chuān bèi mǔ 13
chuān jiāo 21
chuān liàn zǐ 18
chuān niú xī 20
chuān xīn lián 06
chuān xiōng 20
chūn pí 26
cí shí 27
dà dòu juǎn 07
dà fù pí 18
dà huáng 08
dài jì 19
dài qīng yè 06
dà zǎo 22
dài zhě shí 27
dàn dòu chì 02
dǎn nán xīng 13
dān shēn 20
dàn zhú yè 03
dāng guī 23
dǎng shēn 22
dēng xīn cǎo 11
dì fū zǐ 11
dì gǔ pí 04
dì lóng 30
dì yú 19
dīng xiāng 21
dōng chóng xià cǎo 24
dōng guā zǐ 11
dōng kuí zǐ 11
dú huó 12
dù zhòng 24
ē jiāo 23
é zhú 20
ér chá 32
fān xiè yè 08
fáng fēng 01
fěi zi 31
fēng mì 22
fó shǒu 18
fú hǎi shí 13
fú líng 11
fú líng pí 11
fú lóng gān 19
fù pén zǐ 26

Pinyin Name Index

fú píng 02
fú shén 11
fú xiǎo mài 26
fù zi 21
gān cǎo 22
gān jiāng 21
gān suì 10
gǎo běn 01
gāo liáng jiāng 21
gé gēn 02
gǒu jǐ 24
gǒu qǐ zǐ 23
gōu téng 30
gǔ jīng cǎo 03
gǔ suì bǔ 24
gǔ yá 17
guā lóu 13
guā lóu pí 13
guā lóu rén 13
guàn zhòng 31
guī bǎn 25
guì zhī 01
hǎi fēng téng 12
hǎi Jīn shā 11
hǎi mǎ 24
hǎi piāo xiāo 26
hǎi tóng pí 12
hǎi zǎo 13
hàn fáng jǐ 11
hàn lián cǎo 25
hán shuǐ shí 03
hé huàn huā 28
hé huān pí 28
hè shī 31
hé shǒu wū 23
hè yè 07
hè zǐ 26
hēi zhī ma 25
hóng dà jǐ 10
hóng huā 20
hóng téng 06
hòu pò 16
hǔ gǔ 12
hú huáng lián 05
hú jiāo 21
hǔ pò 27
hú zhàng 20
huā ruǐ shí 19
huá shí 11
huái huā mǐ 19
huái niú xī 20
huáng bǎi 05
huáng jīng 22
huáng lián 05
huáng qí 22
huáng qín 05
huáng yào zǐ 13
huǒ má rén 09
huò xiāng 16
jī nèi jīn 17
jī xiě téng 20
jiāng cán 30
jiāng huáng 20
jié gěng 14
jīn qiān cǎo 11
jīn yín huā 06
jīn yīng zǐ 26
jīng jiè 01
jiǔ cài zi 24
jiǔ dà huáng 08
ju he 18
jú hóng 18
jú huā 02
jué míng zǐ 03
kǔ shēn 05
kuǎn dōng huā 15
kuān jīn téng 12
kūn bù 13
lái fú zǐ 17
léi wán 31
lì zhī hé 18
lián qiáo 06
lián xū 26
lián zǐ 26
lián zǐ xīn 03
líng yáng jiǎo 30
liú huáng 32
Liú jì 20
lóng chǐ 27
lóng dǎn cǎo 05
lóng gǔ 27
lóng yǎn ròu 23
lòu lú 06
lù dòu 07
lú gēn 03
lú huì 08

lù jiāo jiāo 24
lù lù tōng 20
luó hàn guǒ 25
luò shí téng 12
mǎ bó 06
mǎ chǐ xiàn 06
mǎ dōu líng 15
má huáng 01
má huáng gēn 26
mǎ qián zǐ 32
mài mén dōng 25
mài yá 17
màn jīng zǐ 02
máng xiāo 08
méi guī huā 18
mì Méng huā 03
míng fán 32
mò yào 20
mǔ dān pí 04
mù guā 12
mù hú dié 15
mǔ lì 27
mù tōng 11
mù xiāng 18
mù zéi 02
niú bàng zǐ 02
nǚ zhēn zǐ 25
nuò dào gēn xū 26
ǒu jié 19
pàng dà hǎi 13
pèi lán 16
péng shā 32
pí pa yè 15
pú gōng Yīng 06
pú huáng 19
qiàn cǎo 19
qián hú 13
qiān nián jiàn 12
qiàn shí 26
qiāng huó 01
qín jiāo 12
qín pí 05
qīng dài 06
qīng hāo 07
qīng pí 18
qīng xiāng zǐ 03
qú mài 11
quán xiē 30
rěn dōng téng 06
rén shēn 22
ròu cōng róng 24
ròu dòu kòu 26
ròu guì 21
rǔ xiāng 20
sān léng 20
sān qī 19
sāng bái pí 15
sāng jì shēng 25
sāng piāo xiāo 26
sāng shèn 23
sāng yè 02
sāng zhī 12
shā rén 16
shā yuàn zǐ 24
shān cí gū 32
shān dòu gēn 06
shān yao 22
shān zhā 17
shān zhū yú 26
Shāng lù 10
shé chuáng zǐ 32
shè gàn 06
shén qǔ 17
shēng dì huáng 04
shēng jiāng 01
shēng má 02
shí chāng pú 29
shì dì 18
shí gāo 03
shí hú 25
shí jué míng 30
shǐ jūn zǐ 31
shí wěi 11
shú dì huáng 23
shuǐ zhì 20
sī guā luò 20
sū mù 20
suān zǎo rén 28
suǒ yáng 24
tài zǐ shēn 22
tán xiāng 18
táo rén 20
tiān huā fěn 13
tiān má 30
tiān mén dōng 25
tiān zhú huáng 13

Pinyin Name Index

tíng lì zǐ 15
tōng cǎo 11
tǔ fú líng 06
niú xī 06
tù sī zǐ 24
wǎ lèng zǐ 20
wáng bù liú xíng 20
wēi líng xiān 12
wǔ bèi zǐ 26
wú gōng 30
wǔ jiā pí 12
wǔ líng zhī 20
wū méi 26
wǔ wèi zǐ 26
wū yào 18
wú zhū yú 21
xī jiǎo 04
xī xiān cǎo 12
xì xīn 01
xī yáng shēn 25
xià kū cǎo 03
xiān hè cǎo 19
xiān máo 24
xiāng fù 18
xiāng rú 01
xiǎo huí xiāng 21
xiè bái 18
xīn yí 01
xìng rén 15
xióng huáng 32
xù duàn 24
xuàn fù huā 14
xuán shēn 04
xuè jié 20
xiě yú tàn 19
yā dàn zǐ 06
yán hú suǒ 20
yè jiāo téng 28
yě jú huā 06
yè míng shā 03
yì mǔ cǎo 20
yí táng 22
yì yǐ rén 11
yì zhī rén 24
yīn chái hú 04
yīn chén 11
yín ěr 25
yīn yáng huò 24
yù jīn 20
yù lǐ rén 09
yù mǐ xū 11
yú xīng cǎo 06
yù zhú 25
yuán hu 10
yuán zhì 28
zào jiǎo cì 14
zé lán 20
zé xiè 11
zhāng nǎo 32
Zhè bèi mǔ 13
zhēn zhū mǔ 27
zhì gān cǎo 22
zhǐ ké 18
zhī mǔ 03
zhǐ shí 18
zhì tiān nán xīng 14
zhī zi 03
zhū líng 11
zhú rù 13
zǐ cǎo 04
zǐ hé chē 24
zǐ huā dì dīng 06
zǐ shí yīng 27
zǐ sū gěng 01
zǐ sū yè 01
zǐ sū zǐ 15
zǐ wǎn 15

Common English Name Index

Abalone Shell 30
Acanthopanax Root Bark 12
Achyranthes Root 20
Aduki Bean, Phaseolus 11
Aerial Parts of Epimedium 24
Aerial Parts of Fringed Pink or Chinese Pink Dianthus 11
Agrimony 19
Ailanthus Bark or Root Bark 26
Akebia Caulis 11
Akebia Fruit 11
Aloe Leaf - Dried juice Concentrate 08
Aloeswood, Aquilaria 18
Alum 32
Amber 27
American Ginseng Root 25
Anemarrhena Rhizome 03
Angelica Root 01
Antelope Horn 30
Apricot Seed or Kernel 15
Arbor Vitae Seed, Biota Seed 28
Aromatic Madder, Elsholtzia 01
Artemesia 20
Asiatic Cornelian Cherry Fruit, Cornus 26
Asparagus Tuber 25
Ass Hide Glue, Donkey Hide Gelatin 23
Astragalus 22
Astragalus Seed, Flattened Milkvetch Seed 24
Baical Skullcap Root 05
Bamboo Shavings 13
Barbat Skullcap or Scutellaria 06
Bark of Mulberry Root 15
Barley Malt Sugar, Maltose 22
Barley Sprout, Malt 17
Bat Feces 03
Belamcanda Rhizome 06
Betel Husk 18
Betel Nut 31
Biota Leaves, Leafy Twig of Arborvitae 19
Birthwort Fruit 15
Bitter Orange Peel 18
Black Atractylodes Rhizone 16
Black Cardamom, Alpinia Oxyphylla Fruit 24
Black Cohosh Rhizome, Bugbane Rhizome 02
Black Pepper 21
Black Sesame Seeds 25
Bletilla Rhizome 19
Boat Sterculia Seed 13
Body of Sick Silkworm 30
Borax 32
Borneol 29
Broom Cypress, Kochia Fruit 11
Buddleia Flower Bud 03
Bugleweed 20
Bulb of Chinese Chive 18
Bulb of Chinese Tulip 32
Bur Reed Rhizome 20
Burnet Bloodwort Root 19
Bush Cherry Pit 09
Bushy Knotweed Root and Rhizome 20
Calcitum 03
Caltrop Fruit, Tribulus 30
Camphor 32
Cardamom (Grains of Paradise Fruit) 16
Carpesium Fruit 31
Cassia or Foetid Cassia Seeds 03
Catail Pollen 19
Celosia Seeds 03
Centipede 30
Chain Fern Rhizome 24
Charred Human Hair 19
Cherokee Rosehip 26
Chicken Gizzard's Internal Lining 17
Chinese Anemone Root or Pulsatilla 06
Chinese Angelica Root 23
Chinese Clematis Root 12
Chinese Dodder Seeds 24
Chinese Foxglove Root, Rehmannia 04
Chinese Foxglove Root, Steamed with Water or Alcohol 23
Chinese Gentian Root 05
Chinese Leek/Onion Seed 24
Chinese Lobelia, Lobelia 11
Chinese Motherwort 20
Chinese Quince Fruit 12
Chinese Rasberry 26
Chinese Senega Root 28
Chinese Soft Shelled Turtle Shell 25
Chinese Tinospora Stem 12
Chinese Wild Ginger, Asarum 01
Chinese Wolfberry Fruit, Matrimony Vine Fruit 23
Chinese Yam Rhizome, Dioscorea 22
Chrysanthemum Flower 02
Cinnamon Twig, Cassia Twig 01
Circada Moulting 02
Citrus/Tangerine Seeds 18
Clove Flower Bud 21
Cnidium Seeds 32

Common English Name Index

Cockle Shell, Ark Shell 20
Cocklebur Fruit 12
Codonopsis Root 22
Coltsfoot Flower 15
Coptis Rhizome 05
Coral Bean Back 12
Cordyceps, Chinese Caterpillar Fungus 24
Cornsilk 11
Cortex of Chinese Dittany Root 06
Cortex of the Peony Tree Root 04
Cortex of Wolfberry Root or Lycium Bark 04
Corydalis Rhizome 20
Costus Root, Saussurea 18
Croton Seed 10
Cuttlefish Bone, Cuttlebone 26
Cyathula Root 20
Daikon, Radish Seed 17
Dandelion 06
Date, Jujube 22
Deer Horn Gelatin 24
Dendrobium Stem 25
Descurainia Seeds 15
Dichroa Root 31
Dioscorea Bulbifera Tober 13
Dragon's Blood Resin 20
Dried Ginger Rhizome 21
Dried Skeleton of Vegetable Sponge 20
Drynaria Rhizome 24
Dryopteris Root 31
Duckweed or Spirodela 02
Earthworm 30
Echinops Root or Rhaponticum 06
Eclipta 25
Ephedra Root 26
Ephedra Stem 01
Eucommia Bark 24
Eupatorium 16
Euryale Seeds 26
Evodia Fruit 21
Fennel Fruit 21
Field Mint, Mentha 02
Finger Citron Fruit 18
Fish Poison Yam Rhizome, Tokoro 11
Fleeceflower Root, Ho Shou Wu, Polygonum 23
Fleeceflower Vine, Polygonum Vine 28
Flesh of the Longan Fruit 23
Fleshy Stem of Cynomorium 24
Fleshy Stem of the Broomrape 24
Flourite 27
Flying Squirrel Feces 20
Forsythia Fruit 06
Fossilized Mammal Bones 27
Fossilized Mammal Teeth 27
Frankincense Resin 20
Fresh Ginger Rhizome 01
Fresh Water Turtle Shell, Testudinis 25
Fruit of Szechuan Pepper 21
Fruiting Body of Omphalia 31
Fruiting Body of Puffball or Lasiosphaera 06
Fruiting Body of Tremella, Wood Ear 25
Gallnet of Chinese Sumac 26
Gambir Vine Stems and Thorns 30
Gardenia, Cape Jasmine Fruit 03
Gastrodia Rhizome 30
Genkwa Flower 10
Gentiana Macrophylla Root 12
Ginkgo Nut 26
Ginseng Root 22
Glutinous Rice Root 26
Golden Eye Grass Rhizome 24
Great Burdock Fruit 02
Green Chiretta or Kariyat or Andrographis 06
Groomwell Root or Arnebia or Lithospermum 04
Gypsum 03
Halloysite, Kaolin 26
Hawthorn Fruit 17
Hematite 27
Hemp Seeds or Cannabis Seeds 09
Hogfennel Root 13
Homalomena Rhizome 12
Honey 22
Honey Fried Licorice Root 22
Honeysuckle Flower or Lonicera 06
Honeysuckle Stem 06
Houttuynia 06
Human Placenta 24
Hyacinth Bean, Dolichos 07
Ignited Yellow Earth 19
Immature Fruit of the Bitter Orange 18
Immature Tangerine Peel 18
Indigo 06
Indigo or Woad Leaf 06
Inflorscence or Pipewort Scapus 03
Inner Brack or Saigon Cinnamon 21
Inula Flower 14
Jack-in-the-Pulpit Rhizome & Bile 13



Pressing into the Inner Ear

Left Eye Pressing into the Ear Canal. Right Eye Pressing into the Eustachian Tube



Pressing into the Pituitary Gland



Right Eye Pressing into the Ear Canal. Left Eye Pressing into the Eustachian Tube

Pressing into the Eustachian Tube

Fig. 27 *Moving the Eyes*

Japanese Teasel Root 24
Japanese Thistle, Cirsium 19
Java Brucea Fruit 06
Kadsura Stem 12
Kansui Root 10
Katsumada's Galangal Seeds 16
Kelp, Eckloniae Thallus 13
Knotweed, Polygonum 11
Korean Ash Branch Bark 05
Ledebouriella Root 01
Leech 20
Leechee Nut 18
Lesser Galangal Rhizome 21
Licorice Root 22
Lily Bulb 25
Lindera Root 18
Long Pepper Fruit 21
Lophatherum Stem and Leaves 03
Loquat Leaf 15
Lotus Leaf 07
Lotus Plumule 03
Lotus Seed 26
Lotus Stamen 26
Lysimachia 11
Madder Root, Rubia Root 19
Magnetite 27
Magnolia Bark 16
Magnolia Flower 01
Mantis Egg Case 26
Medicated Leaven 17
Mimosa Tree Bark 28
Mimosa Tree Flower 28
Momordica Fruit 25
Morinda Root 24
Mother of Pearl 27
Mugwort Leaf, Artemisia 19
Mulberry Fruit Spike, Morus Fruit 23
Mulberry Mistletoe Stems 25
Mulberry Twig 12
Mume Fruit 26
Mung Bean or Phaseolus 07
Musk Mallow Seeds, Abutilon Seeds 11
Myrobalan Fruit 26
Myrrh 20
Ningpo Figwort Root 04
Node of the Lotus Rhizome 19
Notoginseng Root, Pseudoginseng Root 19
Notopterygium Root 01
Nut Grass Rhizome 18
Nutmeg Seeds 26
Nux Vomica Seeds 32
Oldenlandia or Heydyotis 06
Ophicalcite 19
Ophiopogon Tuber 25
Orange Peel, Citrus Peel, Tangerine Peel 18
Oroxylum Seeds 15
Outermost Citrus Peel, Tangerine Peel, Orange Peel 18
Oyster Shell 27
Pagoda Tree Flower Bud 19
Paste from Dried Conc. Decoction of Black or Brown Cutch 32
Patchouli, Agastache 16
Patrinia, Thiaspi 06
Peach Kernel 20
Peking Spurge Root or Euphorbia 10
Perilla Leaf 01
Perilla Stalk 01
Persimmon Calyx 18
Phellodendron or Amur Cork tree Bark 05
Picrorhiza Rhizome 05
Pinellia Rhizome 14
Plantago Seed, Plantain Seed 11
Poke Root or Phytolacca 10
Polyporus Sclerotium 11
Poria Skin 11
Poria Spirit 11
Prepared Jack in the Pulpit Rhizome 14
Prepared Soybean 02
Privet Fruit, Ligustrum 25
Processed Aconite 21
Prunella or Selfheal Spike 03
Pseudostellaria 22
Psoralea Fruit 24
Pubescent Angelica Root 12
Pueraria, Kudzu Root 02
Pumice 13
Purple Aster Root 15
Purple Perilla Fruit, Perilla Seed 15
Purslane or Portulaca 06
Pyrrosia Leaves 11
Rangoon Creeper Fruit with Seeds 31
Realgar 32
Red Peony Root 04
Reed Rhizome 03
Rhinoceros Horn 04
Rhubarb Root and Rhizome 08
Rice Paper Pith, Tetrapanax 11

Common English Name Index

Rice Sprout 17
Root and Rhizome of Cynanchum 14
Root of the Balloon Flower 14
Round Cardamom Fruit 16
Rush Pith, Juncus 11
Safflower Flower 20
Salvia Root 20
Sandalwood (Heartwood) 18
Sappan Wood 20
Sargentodoxa Vine 06
Schisandra Fruit 26
Schizonepeta Bud or Stem 01
Sclerotium of Tuckahoe, China Root, Poria, Hoelen 11
Scorpion, Buthus 30
Sea Horse 24
Seaweed, Sargassum 13
Seeds of Job's Tears 11
Senna Leaf 08
Shave Grass, Scouring Rush 02
Siberian Solomon Seal Rhizome, Polygonatum 22
Sichuan Pagoda Tree Fruit 18
Siegesbeckia 12
Siliceous Secretions of Bamboo, Bamboo Sugar, Tabasheer 13
Silkworm Feces 12
Smilax or Glabrous Greenbrier Rhizome 06
Sodium Sulfate, Mirabilite, Glauber's Salt 08
Solomon's Seal Rhizome, Polygonatum 25
Sophora Root 05
Sophora Root or Subprostrate 06
Sour Jujube Seed, Zizyphus - Raw Herb Shown 28
Spatholobus, Millettia Root and Vine 20
Spine of Chinese Honeylocust Fruit 14
Spores of Japanese Fern 11
Star Jasmine Stem 12
Stellaria Root 04
Stemona Root 15
Stephania Root 11
Straw Weed, Chinese Lovage Root 01
Sulpher 32
Swallowwort Root 04
Sweetflag Rhizome 29
Sweetgum Fruit 20
Szechuan Lovage Root 20
Talcum 11
Tendrilled Fritillaria Bulb 13
Thorowax Root , Bupleurum 02
Thunberg Fritillaria Bulb 13
Tiger Bone 12
Torreya Seeds 31
Trichosanthes Fruit 13
Trichosanthes Peel, Snake Gourd Peel 13
Trichosanthes Root 13
Trichosanthes Seeds 13
Tsaoko Fruit 16
Tumeric Rhizome 20
Tumeric Tuber 20
Tuniuxi Root 06
Typhonium Rhizome 14
Vaccaria Seeds 20
Viola or Yedeon's Violet 06
Vitex Fruit 02
Water Plantain Rhizome, Alisma 11
Wheat Grain (Not Yet Ripe) 26
White Atractylodes Rhizome 22
White Mulberry Leaf 02
White Mustard Seed 14
White Peony Root 23
Wild Chrysanthemum Flower 06
Wine Treated Rhubarb Root, Rhizome - Raw Herb Shown 08
Winter Melon, Wax Gourd Seed, Benincasa 11
Woad Root or Isatis Root 06
Woolly Grass Rhizome 19
Wormwood 07
Yinchenhao Shoots and Leaves, Capillaris 11
Young Flower of Chinese Rose (Bud) 18
Young Soybean Sprout 07
Zedoary Rhizome 20

Latin Name Index

Alumen 32
Arillus Euphoriae Longanae 23
Arisaematis Rhizoma preparatum 14
Aristolochiae Fructus 15
Artemisiae Argyi Folium 19
Bambusae Caulis In Taeniam 13
Bambusae Concretio Silicea 13
black Semen Sesame Indici 25
Bombyx Batryticatus 30
Borax 32
Borneolum 29
Bulbus Allii 18
Bulbus Fritillariae Cirrhosae 13
Bulbus Lilii 25
Buthus Martensis 30
Cacumen Biotae Orientalis 19
Calcitum 03
Calyx Diospyri Kaki 18
Camphora 32
Carapax Amydae Sinensis 25
Caulis Akebiae 11
Caulis Lonicerae 06
Caulis Milletiae Seu Spatholobi 20
Caulis Piperis Futokadsurae 12
Caulis Sargentodoxae 06
Caulis Trachelospermi Jasminoidis 12
Comu Antelopis Saiga-tatarici 30
Concha Arcae Inflatae 20
Concha Haliotidis 30
Concha Margaratiferae 27
Concha Ostreae 27
Cordyceps Chinensis 24
Cornu Rhinoceri 04
Cortex Ailanthi Altissimae 26
Cortex Albizziae Julibrissinis 28
Cortex Cinnamomi Cassiae 21
Cortex Dictamni Dasycarpi Radicis 06
Cortex Erythriniae 12
Cortex Eucommiae Ulmoidis 24
Cortex Fraxini 05
Cortex Magnoliae Officinalis 16
Cortex Phellodendri 05
Cortex Radicis Acanthopanacis Gracistyli 12
Cortex Radicis Lycii Chinensis 04
Cortex Radicis Mori Albae 15
Cortex Radicis Moutan 04
Corydalis Rhizome 20
Crinis Carbonisatus 19
Crotonis Fructus 10
Dens Draconis 27
dry Rhizoma Zingiberis 21
Ecklonia Kurome 13
Endothelium Comeum Gigeriae Galli 17
Excrementum Bombycis Mon 12
Excrementum Vespertilionis Murini 03
Exocarpium Citri Rubrum 18
Fasciculus Vascularis Luffae 20
Feces Trogopterori Seu Pteromi 20
Flos Albizziae Julibrissinis 28
Flos Buddleiae Officinalis Immaturus 03
Flos Carthami Tinctorii 20
Flos Caryophylli 21
Flos Chrysanthemi Indici 06
Flos Chrysanthemi Morifolii 02
Flos Daphnis Genkwae 10
Flos Immaturus Sophorae Japonicae 19
Flos Lonicerae Japonicae 06
Flos Magnoliae Lilliflorae 01
Flos Rosae Rugosae 18
Fluoritum 27
Folium Daqingye 06
Folium Eriobotryae Japonicae 15
Folium Mori Albae 02
Folium Nelumbinis Nuciferae 07
Folium Sennae 08
Fritillariae Thunbergii Bulbus 13
Fructificatio Lasiosphaerae seu Calvatiae 06
Fructificatio Tremellae Fuciformis 25
Fructus Akebiae Trifoliatae 11
Fructus Alpiniae Oxyphyllae 24
Fructus Amomi 16
Fructus Amomi Kravanh 16
Fructus Amomi Tsao-ko 16
Fructus Arctii Lappae 02
Fructus Bruceae Javanicae 06
Fructus Carpesii Seu Dauci 31
Fructus Chaenomelis Lagenariae 12
Fructus Citri Aurantii 18
Fructus Citri Sacrodactylis 18
Fructus Cnidii Monnieni 32
Fructus Corni Officinalis 26
Fructus Crataegi 17
Fructus Evodiae Rutaecarpae 21
Fructus Foeniculi Vulgaris 21
Fructus Forsythiae Suspensae 06
Fructus Gardeniae Jasminoidis 03

Latin Name Index

Fructus Germinatus Hordei Vulgaris 17
Fructus Germinatus Oryzae Sativae 17
Fructus Immaturus Citri Aurantii 18
Fructus Kochiae Scopariae 11
Fructus Levis Tritici Aestivi 26
Fructus Ligustri Lucidi 25
Fructus Liquidambaris Taiwaniae 20
Fructus Lycii Chinensis 23
Fructus Meliae Toosendan 18
Fructus Momordicae Grosvenori 25
Fructus Mori Albae 23
Fructus Perillae Frutescentis 15
Fructus Piperis Longi 21
Fructus Piperis Nigri 21
Fructus Pruni Mume 26
Fructus Psoraleae Corylifoliae 24
Fructus Quisqualis 31
Fructus Rosae Laevigatae 26
Fructus Rubi Chingii 26
Fructus Schisandrae Chinensis 26
Fructus Terminaliae Chebulae 26
Fructus Tribuli Terrestris 30
Fructus Trichosanthis Kirlowii 13
Fructus Viticis 02
Fructus Xanthii Siberici 12
Fructus Zizyphi Jujubae 22
Galla Rhois 26
Gelatinum Corii Asini 23
Gelatinum Cornu Cervi 24
Gleditschiae Sinensis Spina 14
Gypsum Fibrosum 03
Haematitum 27
Hallyositum Rubrum 26
Herba Agastaches Rugosus, Herba Pogostemonis 16
Herba Agrimoniae Pilosac 19
Herba Aloes 08
Herba Andrographitis Paniculatae 06
Herba Artemisiae Anomalae 20
Herba Artemisiae Apiaceae 07
Herba Artemisiae Yinchenhao 11
Herba Asari Cum Radice 01
Herba Cirsii Japonici 19
Herba Cistanchis Deserticolae 24
Herba cum Radice Houttuyniae Cordatae 06
Herba cum Radice Patriniae 06
Herba cum Radice Violae Yedoensitis 06
Herba Cynomorii Songarici 24
Herba Dendrobii 25
Herba Desmodii Styrachifolii 11
Herba Dianthi 11
Herba Ecliptae Prostratae 25
Herba Elsholtziae 01
Herba Ephedrae 01
Herba Epimedii 24
Herba Equiseti Hiemalis 02
Herba Eupatorii Fortunei 16
Herba Hedyotidis Diffusae 06
Herba Lemnae Seu Spirodelae 02
Herba Leonuri Heterophylli 20
Herba Lobeliae Chinensis Gum Radice 11
Herba Lophatheri Gracilis 03
Herba Lycopi Lucidi 20
Herba Menthae Haplocalycis 02
Herba Polygoni Avicularis 11
Herba Portulacae Oleraceae 06
Herba Pyrrosiae 11
Herba Sargassii 13
Herba Seu Flos Schizonepetae Tenuifoliae 01
Herba Siegesbeckiae 12
Herba Taraxaci Mongolici cum Radice 06
Hippocampus 24
Hirudo seu Whitmania 20
Indigo Maturalis 06
Inulae Flos 14
Lignum Aquilariae Agallochae 18
Lignum Santali Albi 18
Lignum Sappan 20
Lumbricus 30
Magnetitum 27
Massa Medica Fermentata 17
Medulla Junci Effusi 11
Medulla Tetrapanacis Papyriferi 11
Mel 22
Morindae Officinalis Radix 24
Natrii Sulfas 08
Nodus Rhizomatis Nelumbinis Nuciferae 19
Ootheca Mantidis 26
Ophicalcitum 19
Oroxyli Semen 15
Os Draconis 27
Os Sepiae Seu Sepiellae 26
Os Tigris 12
Pasta Acaciae Seu Uncariae 32
Pericarpium Arecae Catechu 18
Pericarpium Citri Reticulatae 18
Pericarpium Citri Reticulatae Viride 18

Pericarpium Trichosanthis Kirlowii 13
Pericarpium Zanthoxyli Bungeani 21
Perillae Folium 01
Perillae Ramulus 01
Periostracum Cicadae 02
Placenta Hominis 24
Plastrum Testudinis 25
Platycodi Radix 14
Plumula Nelumbinis Nuciferae 03
Pollen Typhae 19
Polygoni Multiflori Caulis 28
Processed Radix Rehmanniae 23
Pseudobulbus Shancigu 32
Pumice 13
Radix Achyranthis 06
Radix Achyranthis Bidentatae 20
Radix Albus Paeoniae Lactiflorae 23
Radix Angelicae Dahuricae 01
Radix Angelicae Pubescentis 12
Radix Angelicae Sinensis 23
Radix Arnebiae seu Lithospermi 04
Radix Asteris Tatarici 15
Radix Astragali Membranacei 22
Radix Auklandiae Lappae 18
Radix Bupleuri 02
Radix Clematidis Chinensis 12
Radix Codonopsitis Pilosulae 22
Radix Cyathula Officinalis 20
Radix Cynanchi Atrati 04
Radix Dichroae Febrifugae 31
Radix Dioscoreae Oppositae 22
Radix Dipsaci 24
Radix Drynariae 24
Radix Ephedrae 26
Radix Et Rhizoma Cynanchi Baiqian 14
Radix et Rhizoma Ligustici Chinensis 01
Radix Et Rhizoma Notopterygii 01
Radix Et Rhizoma Polygoni Cuspidati 20
Radix Et Rhizoma Rhei 08
Radix Euphorbiae Kansui 10
Radix Euphorbiae seu Knoxiae 10
Radix Gentianae Longdancao 05
Radix Gentianae Macrophyllae 12
Radix Ginseng 22
Radix Glycyrrhizae 22
Radix Isatidis seu Baphicacanthi 06
Radix Lateralis Praeparatus Aconiti Carmichaeli 21
Radix Ledebouriellae Divaricatae 01
Radix Linderae Strychnifoliae 18
Radix Oryzae Glutinosae 26
Radix Panacis Qinquifolii 25
Radix Peucedani 13
Radix Phytolaccae 10
Radix Polygalae Tenuifoliae 28
Radix Polygoni Multiflori 23
Radix Pseudoginseng 19
Radix Pseudostellariae 22
Radix Puerariae 02
Radix Pulsatillae Chinensis 06
Radix Rehmanniae Glutinosae 04
Radix Rhapontici seu Echinopsis 06
Radix Rubiae Cordifoliae 19
Radix Rubrus Paeoniae Lactiflorae 04
Radix Salviae Miltiorrhizae 20
Radix Sanguisorbae 19
Radix Scrophulariae Ningpoensis 04
Radix Scutellariae Baicalensis 05
Radix Scutellariae Barbatae 06
Radix Sophorae Flavescentis 05
Radix Sophorae Subprostratae 06
Radix Stellariae Dichotomae 04
Radix Stemonae 15
Radix Stephaniae Tetrandrae 11
Ramulus Cinnamomi Cassiae 01
Ramulus Loranthi Seu Visci 25
Ramulus Mori Albae 12
Ramulus Uncariae Cum Uncis 30
Ramus Tinosporae Sinensis 12
Realgar 32
Resina Myrrhae 20
Resina Olibani 20
Rhizoma Acori Graminei 29
Rhizoma Alismatis 11
Rhizoma Alpiniae Officinari 21
Rhizoma Anemarrhenae Aspheloidis 03
Rhizoma Arisaematis (Processed with Bile) 13
Rhizoma Atractylodis 16
Rhizoma Atractylodis Macrocephalae 22
Rhizoma Belamcandae 06
Rhizoma Bletillae 19
Rhizoma Cibotii Barometsis 24
Rhizoma Cimicifugae 02
Rhizoma Coptidis 05
Rhizoma Curculiginis Orchioidis 24
Rhizoma Curcumae Longae 20
Rhizoma Curcumae Zedoariae 20

Latin Name Index

Rhizoma Cyperi Rotundi 18
Rhizoma Dioscoreae Hypoglaucae 11
Rhizoma Gastrodiae 30
Rhizoma Guanchong 31
Rhizoma Homalomenae Occultae 12
Rhizoma Imperatae Cylindricae 19
Rhizoma Ligustici Chuanxiong 20
Rhizoma Phragmitis Communis 03
Rhizoma Picrorrhizae 05
Rhizoma Pinelliae Tematae 14
Rhizoma Polygonati 22
Rhizoma Polygonati Odorati 25
Rhizoma Smilacis Galbrae 06
Rhizoma Sparganii 20
Rhizoma Typhonii Gigantei 14
Saccharum Granorum 22
Sanguis Draconis 20
Scapus Et Inflorescentia Eriocaulonis Buergeriani 03
Scierotium Omphaliae Lapidescentis 31
Scierotium Pararadicis Poriae Cocos 11
Scierotium Poriae Cocos 11
Sclerotii Poriae Cocos 11
Sclerotium Polypori Umbellati 11
Scolopendra Subspinipes 30
Semen Allii Tuberosi 24
Semen Alpiniae Katsumadai 16
Semen Arecae Catechu 31
Semen Astragali Complanati 24
Semen Benincasae Hispidae 11
Semen Cannabis Sativae 09
Semen Cassiae Torae 03
Semen Celosiae Argentae 03
Semen Citri Reticulatae 18
Semen Coicis Lachyrma-jobi 11
Semen Cuscutae Chinensis 24
Semen Descurainiae Seu Lepidii 15
Semen Dolichoris Lablab 07
Semen Euryalis Ferocis 26
Semen Ginkgonis Bilobae 26
Semen Glycines Germinatum 07
Semen Litchi Chinensis 18
Semen Malvae 11
Semen Myristicae Fragrantis 26
Semen Nelumbinis Nuciferae 26
Semen Phaseoli Calcarati 11
Semen Phaseoli Munginis 07
Semen Plantaginis 11
Semen Platycladi 28
Semen Praeparatum Sojae 02
Semen Pruni 09
Semen Pruni Armeniacae 15
Semen Pruni Persicae 20
Semen Raphani Sativi 17
Semen Sinapis Albae 14
Semen Strychnotis 32
Semen Torreyae Grandis 31
Semen Trichosanthis Kirlowii 13
Semen Vaccariae Segetalis 20
Semen Zizyphi Spinosae 28
Spica Prunellae Vulgaris 03
Spora Lygodii Japonici 11
Stamen Nelumbinis 26
Sterculiae lychnophorae Semen 13
Stylus Zeae Mays 11
Succinum 27
Sulphur 32
Talcum 11
Terra Flava Usta 19
Trichosanthis Kirlowii Radix 13
Tuber Asparagi Cochinensis 25
Tuber Curcumae 20
Tuber Dioscoreae Bulbiferae 13
Tuber Ophiopogonis Japonici 25
Tussilaginis Farfarae Flos 15
uncooked Rhizoma Zingiberis 01
Wine Treated Radix Et Rhizoma Rhei 08

Visual Materia Medica of Chinese Herbs

info and samples at www.sacredlotus.com

A Sacred Lotus Arts Publication

SAVE 20% WHEN YOU ORDER 10 OR MORE

$52* per book when 10 or more books are ordered (discount applied at checkout - www.sacredlotus.com)



BOOK FEATURES

- 32 Categories, 112 Pages
- Over 350 hi-res photos of the most common herbs
- Table of Contents - quickly locate herb categories
- Indexed - Pinyin, English/Common, and Latin
- Coil/Spiral bound - lays flat when studying
- Thick transparent covers - durable in a backpack/book bag
- Rounded Corners - durable in a backpack/book bag
- High quality glossy heavyweight paper

HERB FEATURES

- Pinyin Name with tone marks
- Common English name
- Latin/Pharmaceutical name
- Chinese name (Chinese characters)
- Temperature scale
- Channels entered
- Herb properties

Contact Person (place order, collect fees, distribute books)

FULL NAME	PHONE	EMAIL	QTY

* Does not include shipping. Please use the website to calculate shipping for your order. CA residents pay sales tax.

G. Learn to Maintain Eye Contact

Some people in eye to eye contact with other people feel nervous and frightened, and their voices become very low and hard to hear because of weak organs. Some people will look around and not look into your eyes when you talk to them. This can be caused by weakness of the gall bladder and kidneys. To improve this, you can use the Inner Smile, Six Healing Sounds and Tao Rejuvenation, plus the practice of staring.

Look at your face in a mirror for two to five minutes each day for the first week. After ten days you can begin to stare at your eyes and increase your confidence by looking at your irises. Gradually you will lose the fear of looking into other people's eyes.

Nose

The nose has several important functions. When we breathe properly through the nose and not through the mouth, the nose filters out dirt, preventing it from reaching the lungs. It also regulates the temperature of the air: when the air is too cold, the nose will warm it up first. Without this regulating action, extreme temperatures could injure the lungs, make us susceptible to upper respiratory illnesses and subject to getting colds easily. One great advantage about people who practice the Tao System is that they seldom get colds.

The nose has three meridians running through it: the large intestine, the stomach, and the Governor or back Channel. Rubbing the nose strengthens the temperature regulator stimulates the above organs, and increases hormone secretion. In China just a few needles inserted in the nose serve as a general anesthetic for any part of the body to be operated on.

An unhealthy nose affects the personality. A thin, flat and unhealthy looking nose, or a badly shaped nose, can make you less attractive to other people. A strong nose can help you to have good Chi. The nose is the first place into which the breath of life enters.

A weak nose usually will be infected, and a lot of mucous can leak into the sinuses. A weak nose also can affect the voice. A good singer always has a good nose. Rubbing and massaging the nose will increase the Chi and will improve circulation around the nose.

Ears

In China we believe that a person with thick, long ears will have a long, healthy life and that the personality will be more attractive.

The following exercises can prevent hearing loss which occurs gradually as we age. The ears are acupuncture maps of the whole body, containing 120 points. Many acupuncturists now use only the ear points to cure many ailments as well as for weight control.

A. Outer Ear

Repeat the method for bringing energy to the hands, contracting the left and right sides of the anus.

1. Front and back: Make a space between your index and ring fingers and simultaneously rub in front and in back of the ears.

2. Ear shells: Rub the ear shells with all your fingers. This will stimulate the autonomic nervous system and warm up your whole body, especially in the cold weather.

3. Ear lobes: Using your thumb and index finger, pull down on the ear lobes.



Rub in Front and Back of Ears



Rub the Ear Shells

Pull Down on the Ear Lobes

***Fig. 28** Rubbing the Ear*

4. Ear drum exercises: For the outer ear drum, repeat the method for bringing energy to the hands, contracting the left and right sides of the anus. Inhale and then exhale completely. Put your index fingers in your ears; it should feel as if there is a vacuum in the ears. If it does not, then exhale more. Move your index fingers back and forth six to nine times at your own pace until you can feel that the insides of the ears are moving, and pull out the fingers with a quick movement. You should hear a “pop” sound, and you will feel that you can hear better and that your mind is clearer.



Fig. 29 *Outer Ear Drum Exercise*

B. Inner Ear

Repeat the method for bringing energy to the hands, contracting the left and right sides of the anus.

The inside of the inner ear, being inaccessible, is usually not exercised and grows weaker with age. These two exercises use air pressure and vibrations to strengthen the inner ear. The ear canals, the nose canal, and the mouth are connected together, so in this exercise we are using the pressure that builds in the lungs and bringing it back up to the mouth, thus adding pressure to the inner ear drums. This is how to exercise the inner ear drums.


Anvil
Stirrup
Nerve to Brain
Wax Producing Gland
Hammer
Canals of Cochlea
Eardrum
Ear Canal
Eustachian Tube
Middle Ear

Fig. 30 *Diagram of Inner Ear Drum*



Fig. 31 *Inner Ear Drum Exercise*

Gums, Tongue, Teeth

Healthy teeth require healthy gums as their foundation. These exercises will strengthen both the gums and teeth. Teeth are the excess energy of the bones, and when the teeth get stronger, so do the bones. When the teeth and tongue are strong, your breath improves as well, eliminating bad breath.

We regard saliva as an essential form of energy which can lubricate the organs and digestive system. The tongue is the opening of the heart, and both are made of similar tissue. A healthy and clean tongue will strengthen the organs, especially the heart. You should clean your tongue twice a day with a brush or scrape it with a tongue scraper, and massage your tongue with a tongue depressor or a clean finger. Find the painful spots and massage there until the pain goes away.

A. Bring Chi Energy to the Hands

Repeat the procedure for bringing energy to the hands, contracting the middle of the anus.

B. Gums

Open your mouth and stretch your lips tautly over your teeth. Use three fingertips (index, middle, and ring fingers) to tap the skin around the upper and lower gums. Hit around until you feel warmth in the area.

C. Gums and Tongue

Massage your upper and lower gums with your tongue. Then suck in some saliva, press your tongue tightly against the roof of your mouth, and try to exercise the tongue. When you strengthen your tongue, you are strengthening your heart. Press around. Press the tongue to the roof of your mouth, tighten your neck muscles and swallow the saliva. This lubricates the digestive glands and organs.



Fig. 32 *Hitting the Gums Exercise.Using the Tongue, Massage the Upper and Lower Gums.*

D. Tongue

In a sitting position place the hands on the knees, palms down. Exhale and straighten the arms, spreading the fingers apart and keeping the hands on the knees. Open the mouth as wide as possible and thrust the tongue out and down, focused on the throat. With the tongue out as far possible, gaze at the tip of the nose. The whole body should be tense. Hold the breath for as long as you feel comfortable. Relax with inhalation and regulate the breath. This will help to strengthen the throat, the tongue and the power of speech. These exercises will help to improve foul breath and to clarify speech.


Kidneys
Liver and Gall Bladder
Stomach
Liver and Gall Blad-der
Heart-Lungs

***Fig. 33** Diagram of Tongue Parts and Corresponding Organs*



***Fig. 34** Tongue*



***Fig. 35** Press Tongue to the Roof of the Mouth*

Inhale, then exhale as you press your tongue out and down as far as you can. Follow by pulling the tongue in and curling it. Press your tongue to the roof of your mouth as hard as you can, contracting the middle of the anus and the esophagus to help the tongue. With more practice you will know how to use the inside force, the force from the organs, to press your tongue up. Even though the tongue has no bones to exert force, you will still be able to exercise the tongue well.

E. Teeth Clenching

Relax your lips. Click the teeth together lightly and then clench them hard, as you inhale and pull up the middle of the anus. Do this six to nine times. Move your tongue and mouth to create a lot of saliva. The technique of swallowing the saliva is to put the tongue up to the palate and swallow quickly with a hard gulp, sending the saliva down the esophagus to your stomach.

F. Energy to Teeth

Close your mouth and let your teeth touch lightly. Direct the energy to your teeth. Gradually feel the electrical flow of energy there.



Fig. 36 *Click the Teeth Together Lightly*



Fig. 37 *Clench the Teeth Together Hard*


Parathyroid Gland
Thyroid Gland
Trachea

Fig. 38 *Throat Glands*

Neck

A. Thyroid and Parathyroid: Site of Courage, the Power of Speech

The neck carries the busiest traffic in the body and is the seat of the thyroid and parathyroid glands. When you massage here, you increase the body's metabolism. Neck tension can also be caused by emotional imbalance. When we are tense and nervous, we are responding to negative emotions, such as anger, fear and sadness. The neck is similar to a traffic bottleneck. All of the signals, as well as the emotions, have to pass through it. When under stress and under emotional strain, the neck starts to accumulate and jam the tension. Unconsciously, the neck muscles tighten, attempting to block out pain. Keeping the neck soft will help Chi flow to the higher center that is located in the brain, keeping the mind and body in harmony together.

Tension in the neck can make you less courageous. When the neck is tense, it will block self expression in the throat. With proper flow of Chi energy, we can express ourselves appropriately at the proper time, place, and in a proper way.

The neck is the passageway of many meridians and is the channel of the Chi energy of the organs. In the middle is the Governor meridian. On the sides are the bladder meridian, the triple warmer meridian and the large intestine meridian. The emotions passing through the meridians of the neck may tense and jam up there.

Emotion:	Organ/Associate Organ:
Anger	Liver/Gall Bladder
Fear	Bladder/Kidneys
Grief	Large Intestine/Lungs
Hastiness	Heart/Small Intestine/Triple Warmer
Worry	Spleen/Stomach/Pancreas

B. Bring Chi Energy to the Hands

Do the procedure for bringing energy to the hands and contract the front of the anus.

C. Whole Neck

Spread your thumbs apart from your other fingers. Alternating hands, rapidly wipe the neck from the chin to the base nine to thirty-six times.

D. Middle Neck

Alternating hands, use the middle three fingers to rapidly wipe down the middle of the neck from the chin to the base nine to thirty-six times. The thyroid and parathyroid glands are in the front section of the neck. Use your thumb and the three other fingers to massage these glands. Find the painful points and massage them until you feel them open. Massaging this area will help to increase metabolism and the power of speaking.



Fig. 39 *Wipe the Neck from the Chin to the Base*

E. Turtle Neck

Sink your chin down, then out and up. Feel your spine press down and then expand. This will help loosen the vertebrae and discs of your neck.

F. Crane Neck

Move your chin forward, circling out, then down, then up, and out again. Feel your spine expand and then contract.

G. Massage the Neck

Massage the points along the back of the neck and on the back along the cervical vertebrae. Start from the shoulders and go up to the base of the skull. Use your fist to hit along the neck. Find any painful spots and any tense spots and massage until they are released. This will greatly help to release the tension of the neck and help to detoxify the toxic accumulations in the neck area, the causes of many headaches.



Fig. 40 *Turtle Neck*



***Fig. 41** Crane Neck*


Large Intestine
Large Intestine
Triple Warmer
Triple Warmer
Gall Bladder
Gall Bladder
Bladder
Bladder
Governor Vessel

***Fig. 42** Massage the Points Along the Neck*

Shoulders

Many people feel tense and worried, and their shoulders are tight and held up. The way to release the tension is by pulling up your shoulders to press against the neck, tightening the muscles of the neck and shoulders. Hold for a while, exhale deeply, and let them drop down, pulled by gravity like a sack of potatoes. Feel the burden, worry, and stress drop down to the feet and out to the ground. Feel yourself grounded. Do this three to nine times, and the tension and worry will go away.

Relax your shoulders and chest, exhale and release more, until you feel the tenseness gone.



Fig. 43 *Dropping the Shoulders will Help to Release Tension and Worry.*

Detoxifying Organs and Glands

Lightly slapping and tapping over the organs and glands help to shock the toxic sediment and increase the circulation and Chi flow to these areas. Our practitioners claim they are able to heal themselves from many chronic illnesses which are very hard to heal by conventional medicine.

I. Thymus Gland

The thymus gland controls the immune system and is related to longevity. Normally the thymus gland atrophies after childhood. In the higher levels of Taoist practice, the thymus gland can be regrown. This helps maintain health and vitality and supports greater spirituality. Thumbing the thymus gland can help increase the activity and release more hormones.

A. Bring energy to your hands by the usual procedure, contracting the front of the anus and bring the Chi toward the thymus.

B. Make a fist, inhale and thump down the middle of the upper chest from the collar bone to the nipples six to nine times. Do not talk while you are doing this or you might harm yourself.



Fig. 44 *Hitting the Thymus Gland*

II. Heart

Lightly slapping an organ stimulates the release of toxins, which allows the organ to rebuild and repair itself. In doing these exercises, be aware that the slapping or tapping should be adjusted by you so as not to use excessive force which may be harmful.

A. Do the energy to hands procedure, contracting the left side of the anus and bringing Chi toward the heart.

B. Slap your heart lightly with your palm six to nine times. Don't speak.

III. Lungs

A. Bring energy to your hands, contracting the right side of the anus and bringing Chi to the lungs.

B. Using your palm, slap up and down your right lung, hitting only as hard as is comfortable. Do not talk. Contract the left side of your anus and slap your left lung. This can help to clean out the mucous and to clean out the lungs.



Fig. 45 *Slap at Heart, Lungs and Liver Areas*

IV. Liver

A. Bring energy to the hands, contracting the right side of the anus and bringing Chi to the liver.

B. Using your palm, slap below the rib cage on the right side. Don't speak. This can help to detoxify the liver.

V. Stomach, Spleen, Pancreas

A. Bring energy to your hands, contracting the middle of the anus.

B. Contract the anus at the left side, and slap at the spleen, pancreas and stomach. Place one palm on top of the other and rub below the rib cage, from center to left, then left to center.



Fig. 46 *Rub the Stomach, Spleen and Pancreas*



Fig. 47 *Rub Back and Forth over the Liver, Stomach and Spleen*

VI. Large and Small Intestines

A.Bring energy to the hands, contracting the entire anus.

B. Small intestine: With palms together, rub a small circle around your navel, first clockwise, then counterclockwise.

The small intestine is one of the longest tubes in the digestive system. A careless diet, too much hot food or dairy products, or too little fibrous food will create mucous that will stick to the walls of the intestine, block the absorption of nutrients and slow down digestion. Once mucous accumulates, it is like a snow ball that will get bigger and bigger, eventually becoming a lump which slows down the traffic of the digestive system.

C. Large intestine: Place one palm on top of the other and rub your abdomen in a large circle. Start on the lower right side and rub up and around in a clockwise direction. This will move the energy in the intestine and relieve constipation. For diarrhea, rub counterclockwise. If you have normal elimination, rub in both directions. These exercises increase the absorption and dissolve the accumulations that stick to the large intestine's wall.



Fig. 48 *Hitting the Sacrum Can Help in Strengthening the Sciatic Nerves*

VII. Kidneys

The kidneys act as helping to filter out waste material from the blood. If there is too much waste in the system, the kidneys cannot filter it all. The waste will tend to collect in the ducts and tubules of the kidneys, impairing their health. By hitting the kidneys' area, we shake out the harmful sediment and help prevent kidney malfunction.

A. Bring energy to the hands, contracting the left and right sides of the anus.

B. Locate the kidneys just above the lowest, or floating, rib in the back on either side of the spine. Make a fist and hit the kidneys with the back of the fist between the wrist and knuckles. Alternate hands and hit only as hard as is comfortable. This will help to shake loose the sediment, crystals, and uric acid that get caught in the kidneys. This will also strengthen the kidneys and relieve back pain.

C. Rub your hands together to warm them. Then rub your palms up and down over the kidneys until they feel warm.

VIII. Sacrum

In the Taoist system the sacrum is regarded as extremely important. It is a pump which helps to bring spinal fluid and energy (Chi) to the brain. It is also the junction where the sexual organs, rectum, and legs meet. Sciatic pain, which shoots down the legs, originates in the sacrum; therefore, strengthening it will release this intense pain.

A. Bring energy to the hands, contracting the back of the anus to the sacrum.

B. Make a fist and use your knuckles alternately to hit both sides of the sacrum. First hit in the area of the eight sacral holes, and then the hiatus, the depression at the bottom of the sacrum.



Fig. 49 *Hitting the Kidneys will help to Shake Out Sediment*

Knees and Feet

I. Knees are Toxin Collectors

Toxins tend to collect in the lower limbs because of the slowdown of the circulation due to gravity. The most common places are the back parts of the knees. Slapping at these places will break down the toxins. The body will then eliminate the toxins out of the body by urine, bowel movements and sweat.

A. Bring Chi Energy to the Hands

Bring energy to the hands; do no contractions.

B. Behind the Knees

Prop your leg up on a chair or low table so the knee is straight. Then slap smartly behind the knee nine to eighteen times. Although it hurts, it is extremely beneficial in releasing toxins which accumulate there. This release may be indicated by the appearance of a purple dot. Use discretion as to how hard you slap, since it can be overdone. Repeat this exercise on the other knee.



Fig.50 *Slapping Smartly behind the Knee Helps to Release Toxins*


Move Knee Cap Up and Down

Fig. 51 *Massaging the Knee Cap*

C. Knee Cap Massage

Massage the knee cap until it is warm, There is very little blood flowing to it and it tends to be quite vulnerable. This practice strengthens it. Massage the other knee cap.

D. Move the Knee Caps

Relax the knee caps, then move them up and down to the left and right and around both clockwise and counterclockwise.

E. Massage the Knees

Falling down is often caused by weak knees. Massaging the knees will improve your stability and flexibility.

II. Feet: Roots of the Body

Strong feet and tendons increase your stability by connecting you to the healing energy of the earth. Feet are the reflexes of the whole body's organs, glands and limbs. (They are like remote controls. Massaging will help to stimulate the organs and glands and increase the circulation.

A. Bring Chi Energy to the Hands

Bring energy to the hands; do no contractions.

B. Massage the Feet

Take off your shoes and stockings and massage the tops and bottoms of each foot with your thumbs and fingers. Be sure to massage the kidney point, the sore spot in the center between the ball of each foot and the adjoining pad. If you are in a hurry, massage the whole of each foot once by rubbing the sole of the foot vigorously and carefully across the top of the other foot, going from the heel to the arch to the toes. The soles of the feet have energy meridians to the entire body. Massage the feet, and when you find painful points massage them until the pain goes away. This will help to clear any blockage of Chi channel flow


Sinuses
Pituitary Gland
Neck
Eye
Throat, Tonsils
Lungs
Thyroid area
Solar Plexus
Stomach
Adrenal Gland
Kidney
Transverse Colon
Waist
Spine
Ureter Tube
Small Intestine
Bladder
Coccyx
Sciatic Nerve
Ear
Shoulder
Pancreas
Liver
Gall Bladder
Appendix
Hip Area
Ear
Shoulder
Heart
Pancreas
Spleen
Descending Colon
Right
Left

***Fig. 52** Feet are the Reflexes of the Whole Body's Organs, Glands and Limbs*

C. Spread Out the Toes

Spread out and separate all the toes, especially the little toes, and then release. Repeat six to nine times. This is especially good for the tendons of the feet.



Fig. 53 *Separate all the Toes by Spreading them out.*

D. Big and Second Toes

Rub the big toes and second toes together rapidly. This a good exercise to do at odd moments during the day.

E. Rub Feet Together

Keep the feet warm by rubbing them together. This will help to stimulate all the body's organs.

For further information about Universal Tao Centers, courses, or other resources, contact:

Universal Tao Instructor Associations

North America Instructors Association (NAIA)

c/o Loretta Robb, Treasurer
13 Plymouth Drive, Newark, Delaware 19713 USA
Tel: (1)(888) 444-7426 (Toll Free) or (1)(212) 330-7876
Email: info@taoinstructors.org Website: http://taoinstructors.org

European Instructors Association (EIA)

c/o Zentrum Waldegg
3823 Wengen, SWITZERLAND
Tel: (41)(33) 8554422 Fax: (41)(33) 8555068
Email:info@waldegg.ch Website: www.waldegg.ch

To order English books, and for your local Insructors use our Web Sites: www.universal-tao.com and www.taogarden.com

Universal Tao World Fulfillment Center

274 Moo 7, Luang Nua, Doi Saket, Chiang Mai, 50220 Thailand
Tel: (66)(53) 495-596 & 865-034 Fax: (66)(53) 495-852
North America Fax (1)(212) 504-8116 Europe Fax (31)(20) 524-1374
Email: universaltao@universal-tao.com **or** info@tao-garden.com

The Universal Tao is not and cannot be responsible for the consequences of any practice or misuse of the information in this book. If the reader undertakes any exercise without strictly following the instructions, notes, and warnings, the responsibility must lie solely with the reader.



$6.95

Cosmic Self-Massage

Taoist Way of Rejuvenation

Mantak Chia

Illustrations by Udon Jandee

Cosmic Self-Massage

In this booklet Virtually all Western massage is massage primarily of the muscles. Whatever its virtues, Western massage is altogether different from Chi Massage. Tao Rejuvenation employs one's own internal energy, Chi energy, to strengthen and rejuvenate the sense organs—eyes, ears, nose, tongue, teeth and skin—and the inner organs.

The techniques used by Taoists are some five thousand years old and, until very recently, were closely guarded secrets passed on from a Master to a small group of students. Often, too, each Master knew only a small part. Now Master Chia has pieced together the entire system of Chi Massage in a logical sequence in such a way that once you have it shown to you, you need only five or ten minutes of practice daily.

In short order you will note improvement in complexion, taste, vision, hearing, sinuses, gums, teeth, tongue, the internal organs and general stamina.

ISBN 0-9671718-5-7
9 780967 171852

Universal Tao Publications
274 Moo 7, Luang Nua, Doi Saket,
Chiang Mai 50220, Thailand
Tel: (66)(53) 495-596 Fax: 495-852
Email: universaltao@universal-tao.com
Web Site: www.universal-tao.com



Cosmic Sounds

Sounds that Heal

Mantak Chia

Cosmic Sounds

Sounds that Heal

Mantak Chia

Edited by:

Annette Dersken

Editor: Annette Dersken

Assistant Editors: Valerie Meszaros, Lee Holden, Bastiaan Anink

Illustrations: Juan Li, Udon Jandee

Computer Graphics: Saisunee Yongyod

Layout: Siriporn Chaimongkol

Production Manager: Saniem Chaisarn

Final Editing: Jean Chilton, Colin Campbell

Project Manager: W.U. Wei

© *North Star Trust*

First published in 2002 by:

Universal Tao Publications
274 Moo 7, Luang Nua,
Doi Saket, Chiang Mai 50220 Thailand
Tel: (66)(53) 495-596 Fax: 495-853
Email: universaltao@universal-tao.com
Web Site: universal-tao.com

Manufactured in Thailand

ISBN: 0-935621-32-6

All rights reserved. No part of this booklet may be used or reproduced in any manner whatsoever without the express written permission from the author, with the exception of brief quotations embodied in critical articles and reviews. Anyone who undertakes these practices on the basis of this booklet alone, does so entirely at his or her own risk.

Contents

Six Universal Sounds 1
- Theory 1
- Practice 3
  - A. Lung Sound 3
  - B. Kidney Sound 10
  - C. Liver Sound 16
  - D. Heart Sound 22
  - E. Spleen Sound 30
  - F. Triple Warmer Sound 36
- Daily Practice 43

The meditations, practices and techniques described herein are ***not*** intended to be used as an alternative or substitute for professional medical treatment and care. If any readers are suffering from illnesses based on mental or emotional disorders, an appropriate professional health care practitioner or therapist should be consulted. Such problems should be corrected before you start training. This booklet does not attempt to give any medical diagnosis, treatment, prescription, or remedial recommendation in relation to any human disease, ailment, suffering or physical condition whatsoever.


H-S-S-S-S The Sound of the LUNGS
HO-O-O-O The Sound of the HEART
SH-H-H-H The Sound of the LIVER
WHO-O-O-O The Sound of the STOMACH & SPLEEN
HE-E-E-E The Sound of the TORSO
WH-H-H-H The Sound of the KIDNEYS

Cosmic Healing Sounds as taught by Mantak Chia
Artist: Juan Li

Cosmic Six Healing Sounds

Theory

Having accessed the knowledge of the universe through internal practices, the Taoist masters discovered that each healthy organ is associated with a particular sound, color, and quality of energy. Emotional problems, pollution, poor food, injuries, and overly strenuous exercise can overheat the internal organs. causing them to weaken. This changes the state of each organ's sound frequency, color, and energetic quality. The Six Healing Sounds practice help to restore, balance, and cleanse the vital organs by correcting these factors. They also stimulate the Chi flow throughout the body to enhance one's overall health and vitality.

The Cosmic Six Healing Sounds help to release any excess heat that may be trapped in the cooling sacs which surround each organ. As you assume the postures and produce the sounds sub-vocally, their vibrations redistribute any excess heat into cooler regions of the body where this can safely be stored or used. Once the organ energies are balanced, you have a good foundation for establishing and nurturing the virtue energies. This will help to maintain the Chi balance throughout the system.

What causes an organ to malfunction? There are many causes. Urban society creates a life full of physical and emotional stresses such as overcrowding, pollution, radiation, junk food, chemical additives, anxiety, loneliness, bad posture, and sudden or overly vigorous exercise. Separately and together, these stresses produce tension and start to block the free passage of enegy flow in the body, thus the organs overheat. In addition, the concrete jungle that we live in lacks the safety valves provided by nature: trees, open spaces, and running water, which give forth a cooling, purifying energy. Continued overheating causes an organ to contract and harden. This impairs its ability to function and results in illness. One of the surgeons working with the Universal Tao Center in New York reports that the hearts of patients who have died of heart attacks look as if they've been cooked! And the ancient Taoists have a saying: "Stress cooks your brain".

Chinese medicine teaches that each organ is surrounded by a sac or membrane, called fascia, which regulates its temperature. Ideally, the membrane releases excess heat out through the skin, where it is exchanged for cool life force enegy from nature. An overload of physical or emotional tension causes the membrane, or fascia, to stick to the organ so that it cannot properly release heat to the skin nor absorb cool energy from the skin.

The skin becomes clogged with toxins and the organ overheats. The Sounds speed up the heat exchange through the digestive system and the mouth. The digestive system is more than 20 feet long and runs from the mouth to the anus as one pipe in the middle of the body in between all the organs. It helps release excess heat from the fascia, cooling and cleansing the organs and skin. When all the sounds and postures and done in the proper order, body heat is evenly distributed by the intestinal tract throughout the whole body, and each of the organs is at its correct temperature.

Daily practice of the Six Healing Sounds wil restore and maintain calmness and good health. Greater sexual pleasure and improved digestion will occur. Minor ailments, such as cold, flu, and sore throats, can be prevented or thrown off easily. Many students of The Universal Tao have overcome their long-standing dependence on sleeping pills, tranquilizers, aspirin, and antacids. Heart attack victims have prevented further attacks. Several psychologists have taught some of their patients to use the Six Healing Sounds to relieve depression, anxiety or anger; and body work oriented healers have used the Six Healing Sounds to help speed up healing, and the healer spends less of his own life force energy.

Each of the six organs in the practice has an associate organ which responds together with it and in the same manner. When an organ is weak or overheated, its paired organ is similarly affected. Likewise, practicing the appropriate healing sound and posture improves the organ and its associate.

***Note**:* Typical side effects of these practices are yawning. burping, or passing wind, all of which are beneficial as indicators of moving energy.

Practice

First Cosmic Healing Sound: Lung Sound

The Lung Sound is a metal sound. It sounds like the vibration of a bell and activates the lung Chi.

Associated Organ: Large Intestine
Element: Metal
Season: Autumn
Color: White
Emotions: Grief and Sadness
Virtues: Courage and Righteousness
Related Senses: Smell (Nose) and Touch (Skin)
Taste: Pungent
Related Parts of the Body: Chest, Inner Arms, Thumbs
Sound: ***Sssssss*** (Tongue behind Teeth)

Exercise:

1. Sit with your back straight, your hands resting on your lungs, and your eyes closed. Smile down to your lungs. Be aware of the quality of the energy in the lungs. Picture a white light, fresh and pure like the energy of the mountains and hear the metal sound.

2. Take a deep breath, open the eyes and raise your arms out in front of you with the palms facing the lungs. When the hands are at eye level, begin to rotate the palms, bringing them above your head until they face up and are pushing outwards. Point the fingers toward those of the opposite hand. Keep the elbows rounded out to the sides, and do not straighten your arms.

Close the jaws so that the teeth gently meet and part the lips slightly as you slowly exhale through your teeth the sound *“**Sssssss**”*. In the beginning, you can produce the Lung Sound out loud, but eventually you should practice it sub-vocally.



Fig. 1 *Become aware of the Lungs.*

Feel that the sound starts to move the Chi in the lungs, and that any excess heat and toxins are expelled from the lungs as the sacs surrounding the lungs are compressed.



***Fig. 2** Gather the energy into the Lungs.*

Note: “Sub-vocally” means that you are vocalizing so softly that only you can hear the sound and feel the vibration inside the lungs. You must exhale slowly and fully. Also, the word “sacs” refers to the layers of tissue called fasciae, that surround every organ.



Fig. 3 *Do the Lung Sound.*

3. When you have exhaled completely, rotate the palms and scoop up the white light. Pour this light from the crown down into the lungs. Lower the arms and hold your hands before the lungs and radiate the bright white light, and courage into the lungs.



Fig. 4 *Bring the energy down to the Lungs.*

4. Rest, close your eyes and be aware of your lungs. Smile into them, and imagine that you are still making the Lung Sound. Feel the vibration of the sound moving and cleaning the energy in the lungs. Breathe normally, and see your lungs glowing with a bright white light. This will strengthen your lungs and activate courage in the lungs. With each breath, try to feel that fresh white metal energy is replacing the excess hot, toxic, and depressed energy.



Fig.5 *Cover the Lungs.*

5. Nurture good emotions. This is the most important part of this practice. Take as much time as you need to get in touch with the organs. When you get rid of the excess heat and let the white metal energy expand in the lungs, good emotional qualities will have room to grow. Concentrate on the feelings of righteousness and courage as you transform any sadness or grief. Sit up straight and tall so you can feel courage, and try to maintain the feeling of the Lung Sound for increasingly longer periods after each practice, and in your daily life.

6. Repeat the Lung Sound three to six times. For sadness, depression, colds, flu, toothaches, asthma, emphysema, or depression, you may repeat this exercise 6, 9, 12, or 24 times.



Fig. 6 *Mouth Position for Lung Sound. Close the jaws so that teeth meet. Draw the corners of the mouth back.*

Second Cosmic Healing Sound:Kidney Sound

The Kidney Sound is a water sound and it activates the kidney Chi.

Associated Organ: Bladder
Element: Water
Season: Winter
Color: Dark Blue
Emotion: Fear
Virtue: Gentleness, Calmness and Stillness, Alertness
Parts of the Body: Sides of the Feet, Inner Legs, Chest
Senses: Hearing (Ears), Bones
Taste: Salty
Sound: ***Choooooooooo*** (As when blowing out a candle: lips forming an “0”)

Exercise:

1. Sit with your back straight, your hands resting on your kidneys, and your eyes closed. Smile down to your kidneys. Be aware of the quality of the energy in the kidneys. Picture a blue light, the sun shining on the ocean.

2. Take a deep breath, open the eyes and put your legs together, ankles and knees touching. Lean forward and clasp the fingers of both hands together around your knees. Pull your arms straight from the lower back while bending the torso forward (This allows your back to protrude in the area of the kidneys). Simultaneously tilt your head up as you look straight ahead, maintaining the pull on your arms from the lower back. Feel the pull on your spine. Round the lips, and slightly exhale with the sound “***Chooooooo***” as if you were blowing out a candle.

Simultaneously contract your abdomen pulling it in toward your kidneys. At first you can produce the Kidney Sound out loud, but eventually you should practice it sub-vocally. Feel that the sound starts to move the Chi in the kidneys; any excess heat and toxins are expelled from the kidneys as the sacs surrounding the kidneys are compressed.



Fig. 7 *Smile to the Kidneys.*

3. After you have fully exhaled, sit erect, separate the legs and move your arms up to the crown and scoop up the blue light. Pour this light over the body and into the kidneys. Lower your arms and hold the palms on the kidneys. Radiate the blue light, the gentleness, and stillness into the kidneys.



Fig. 8 *Do the Kidney Sound.*

4. Return your hands to your kidneys. Rest, close your eyes, and be aware of your kidneys. Listen to your kidneys. Smile to them, and imagine that you are still making the Kidney Sound. Feel the vibration of the sound is moving and cleaning the energy in the kidneys.



Fig. 9 *Bring the energy down to the Kidneys.*

Breathe normally, and see your kidneys glowing with a cool blue light. This will strengthen your kidneys and activate the gentleness and stillness in the kidneys. With each breath, try to feel that bright blue water energy is replacing the excess hot, toxic, and fear energy.



Fig. 10 *Gather the energy into the Kidneys.*

5. Nurture good emotions. This is the most important part of this practice. Take as much time as you need to get in touch with the kidneys. When you get rid of the excess heat and let the cool blue water energy expand in the kidneys, good emotional qualities will have room to grow.

Concentrate on the feelings of gentleness, stillness, and alertness as you transform any fear. Feel the gentleness relaxing also the lower back. Try to maintain the sensation of this energy for increasingly longer periods after each practice, and in your daily life.

Repeat the steps from three to six times. You may repeat this exercise more times to alleviate fear, fatigue, dizziness, ringing in the ears, or back pain.



Fig. 11 *Round the lips, making the sound one makes when blowing out a candle.*

Third Cosmic Healing Sound: Liver Sound

The Liver Sound is a wood sound and it activates the liver Chi.
Associated Organ: Gall Bladder
Element: Wood
Season: Spring
Color: Green
Emotion: Anger
Virtue: Kindness
Parts of the Body: Inner Legs, Groin, Diaphragm, Ribs
Senses: Sight (Eyes), Tears
Taste: Sour
Sound: ***Shhhhhhh*** (Tongue near Palate)

Exercise:

1. Sit comfortably with your back straight, your hands resting on your liver and your eyes closed. Smile down to your liver until you feel you are in touch with your liver. Be aware of the quality of the energy in the liver. Picture a forest, a big green forest. See the sun shining on the forest creating life force and green light.

2. Take a deep breath, open the eyes and extend your arms out to your sides, palms up. Slowly raise the arms from the sides to the crown, following this action with your eyes. Intertwine the fingers, and rotate your joined hands over to face the ceiling, palms up. Push up and out with the heels of the hands and stretch the arms out from the shoulders; the elbows should be pushing to the back.

Bend slightly to the left, exerting a gentle pull on the liver. Open your eyes wider because they are the openings of the liver. Slowly exhale out the sound "***Shhhhhhh***" loud and eventually sub-vocally. Feel the sound start to move the energy in the liver and that all excess heat and toxins are expelled from the liver as the sac around it is compressed.



Fig. 12 *Smile to the Liver.*

3. After you have fully exhaled, sit erect, separate the hands and scoop up the green light. Pour this light over the body and into the liver. Slowly bring your arms down, palms facing out, and scoop up more green light and hold both hands before your liver. Radiate the green light, the forest energy, and kindness in the liver.



Fig. 13 *Do the Liver Sound.*

4. Return your hands to your liver. Rest. Close your eyes and be aware of your liver. Smile and look in your liver and imagine that you are still making the Liver Sound. Feel the vibration of the sound is moving and cleaning the energy in the liver.



Fig. 14 *Scoop green light as the hands return to the Liver.*

Breathe normally, and see your liver glowing with the green rejuvenating light. This will strengthen your liver and activate kindness in the liver. With each breath, try to feel that bright green wood energy is replacing the excess hot, toxic, anger, aggression and frustration energy.



Fig. 15 *Gather energy into the Liver.*

5. Nurture good emotions. This is the most important part of this practice. Take as much time as you need to get in touch with the liver. When you get rid of the excess heat and let the warm, moist, green wood energy expand in the liver, kindness will have room to grow.

Concentrate on the virtue of kindness and forgiveness as you transform any anger and aggression. Feel warm and energetic, and maintain this feeling for as long as you can after practice.

6. Repeat the steps from three to six times. Practice more to expel anger, to clear red or watery eyes, to remove a sour or bitter taste, and to detoxify the liver.



Fig. 16 *Exhale on the sound “**Shhhhhhh**”*

Fourth Cosmic Healing Sound: Heart Sound

The Heart Sound is the fire sound and activates the heart energy.

Associated Organ: Small Intestine
Element: Fire
Season: Summer
Color: Red
Emotions: Hastiness, Arrogance, Cruelty
Virtues: Joy, Honor, Sincerity
Parts of the Body: Armpits, Inner Arms
Senses: Tongue, Speech
Taste: Bitter
Sound: ***Hawwwwww*** (Mouth wide Open)

Exercise:

1. Sit comfortably with your back straight, your hands resting on your heart, and your eyes closed. Smile down to your heart until you feel you are in touch with your heart. Be aware of the quality of the energy in the heart. Picture a sunset on the ocean, a red light.
2. Take a deep breath, open the eyes and take the same position as for the Liver Sound. Unlike the former exercise, however, you will lean slightly to the right to pull gently against the heart, which is located just left of the center of your chest.

Focus on your heart, and feel the tongue's connection to the open mouth, round the lips, and slowly exhale the sound "***Hawwwwww*** " out loud and eventually sub-vocally. Feel the sound start to move the energy in the heart and that excess heat and toxins are expelled from the heart as the sac around it is compressed.



Fig. 17 *Do the Heart Sound.*

3. After you have fully exhaled, sit erect, separate the hands and scoop up the red light. Pour this light over the body and into the heart. Slowly bring your arms down, palms facing out. Scoop up more red light and hold both hands before your heart. Radiate the red light, the love, and inner joy into your heart.



Fig. 18 *Gather energy into the Heart.*

4. Return your hands to your heart. Rest, close your eyes and be aware of your heart. Smile to your heart and imagine that you are still making the Heart Sound. Feel the vibration of the sound is moving and cleaning the energy in the heart. Breathe normally, and see your heart glowing with a red fire light.



Fig. 19 *Smile into the Heart.*

This will strengthen your heart and activate love, inner joy, and sincerity in your heart. With each breath, try to feel that the warm red light is replacing the excess hot, toxic energy and any hastiness, arrogance, and hate in the heart.



Fig. 20 *Turn the senses into the Heart.*

5. Nurture good emotions. This is the most important part of this practice. Take as much time as you need to get in touch with the heart.



Fig. 21 *Loving energy grows in the Heart.*



Fig. 22 *When the heart is relieved of its daily load and stress, all the organs smile!*

When you get rid of the excess heat and let the red fire energy expand in the heart, good emotional qualities will have room to grow. Feel love, joy, honor, and respect radiate outwards.

Feel any hatred, arrogance, or impatience transform into loving energy as sincerity, honor, and respect grow in your heart. Try to maintain the feeling of the Heart Sound as long as you can after practice.

6. Repeat the steps from three to six times. Practice more to relieve sore throats, cold sores, swollen gums or tongue, jumpiness, moodiness, and heart disease.



***Fig. 23 "Hawwwwww"** Sound*

Fifth Cosmic Healing Sound: Spleen Sound

The Spleen Sound is the earth sound, activating the energy of the stomach, the pancreas, and the spleen.

Associated Organs: Pancreas, Stomach
Element: Earth
Season: Indian Summer
Color: Yellow
Emotion: Worry
Virtues: Fairness, Openness
Parts of the Body: Lips, Mouth
Senses: Taste
Taste; Sweet, Neutral
Sound: ***Whoooooo*** (From the Throat, Guttural)

Exercise:

1. Sit comfortably with your back straight, your hands resting on your spleen, and your eyes closed. Smile down to your stomach and spleen until you feel you are in touch with them. Be aware of the quality of the energy in the stomach and the spleen. Picture a yellow light, the golden satiated light of the Indian Summer, a stable light.
2. Take a deep breath, open the eyes, move the arms to the front and place the three middle fingers of both hands just beneath the sternum on the left side of the rib cage.

Look up and gently press your fingers under the rib cage, pushing your stomach or spleen to the back and your middle back out wards you exhale out loud, eventually sub-vocally, the sound "***Whoooooo***" This is more guttural, or "throaty" than the kidney Sound. Unlike blowing out a candle, this sound originates from with in the chest, rather than from the mouth.



Fig. 24 *Smile to the Spleen.*

Feel the Spleen Sound vibrate the vocal cords. Feel the sound start to move the energy in the stomach and the spleen and that all excess heat and toxins are expelled from the stomach and the spleen as the sac around them is compressed.



Fig. 25 *Fingers under the left Rib Cage Preparing to press on Spleen, Pancreas and Stomach.*

3. After you have fully exhaled, move the arms outwards, embracing the earth and scoop up the yellow light. Pour this light into the stomach and spleen. Bring the arms and the hands to the stomach and/or the spleen. Radiate the yellow light, the fairness, openness, and stability into the stomach and the spleen.



Fig. 26 *Feel the Spleen Sound Vibrate.*

4. Rest, close your eyes and be aware of your stomach and spleen. Smile to them and imagine that you are still making the Spleen Sound. Feel the vibration of the sound is moving and cleaning the energy in the stomach and the spleen.



Fig. 27 *Openesss and Fairness Grow in the Spleen.*

Breathe normally, and see your stomach and spleen glow with a yellow light. This will strengthen these organs and activate openness, fairness, and stability in your stomach and spleen. With each breath, try to feel that the warm yellow light is replacing the excess hot, toxic energy and any worries in these organs.

5. Nurture good emotions. This is the most important part of this practice. Take as much time as you need to get in touch with the stomach and the spleen.

When you get rid of the excess heat and let the yellow earth energy expand in the stomach and the spleen, good emotional qualities will have room to grow. Feel the fairness, openness, balance, and harmony grow in these organs, transforming any worry in them. Try to maintain the feeling of the Spleen Sound as long as you can after practice.

6. Repeat the steps from three to six times. Practice more to eliminate indigestion, nausea, and diarrhea.



Fig. 28 *Exhale on the sound "**Whoooooo**"*

Sixth Cosmic Healing Sound: Triple Warmer

The Triple Warmer refers to the three energy centers of the body: The upper section (brain, heart, and lungs) is hot; the middle section (liver, kidneys, stomach, pancreas, and spleen) is warm; and the lower section (large and small intestines, bladder, and sexual organs) is cool.

The sound "***Heeeeeee***" serves to balance the temperature of the three levels by bringing hot energy down to the lower center and cold energy up to the higher center. Specifically, hot energy from the area of the heart is moved to the colder sexual region, and cold energy from the lower abdomen is moved up to the heart's region.

Exercise:

1.Lie on your back or lean back in the chair. Smile, move your arms up and gather the Chi, and bring your arms and hands to your face. As you make the *"**Heeeeeee**"* sound on exhalation, let the arms slowly move down the body bringing the energy down from the crown to the feet.

2. Inhale fully into all three cavities: chest, solar plexus, and lower abdomen, and then exhale completely. Exhale with the sound "***Heeeeeee***" sub-vocally, first flattening your chest, then your solar plexus, and finally your lower abdomen. Imagine a large, roller pressing out your breath and move the hot energy down as the arms move from your head down to your lower Tan Tien.

3. Rest, and concentrate. When you have fully exhaled, focus on the entire digestive tract.

4. Repeat the steps from three to six times. Practice more to relieve insomnia and stress.

***Note*:** The Triple Warmer can be done lying down to facilitate falling asleep.



Fig. 29 *Rest by breathing normally and focus on the Triple Warmer Sound.*



Fig. 30 *Gather the energy from all three Levels.*



Fig. 31 *Send the energy down the body.*



***Fig. 32** Upper Level*



***Fig. 33** Middle Level*



***Fig. 34** Lower Level.*



Fig. 35 *Excess heat flows out of the fingertips and toes into the Earth.*



Fig. 36 *Do the Triple Warner Sound.*



***Fig. 37** All the way down the body with the **"Heeeeeee"** Sound.*



***Fig. 38** "**Heeeeeee**" Sound*



Fig. 39 *Rest and absorb the Cosmic Forces.*

Daily Practice

1. We recommend that you practice the Six Healing Sounds before going to bed at night to relax the body, promote good sleep, and cool down any organs that are overheated. You may also do these sounds to enhance any of the other Taoist exercises whenever you feel like practicing. Do three rounds of each sound to prevent illness and maintain good health. Once learned, the procedures take only ten to fifteen minutes to complete.

2. Clear out any negative emotions, and let positive emotions grow before you go to sleep. You may feel a sense of emptiness as you disengage from your own mental activity to connect with the Universal Consciousness. This will also help you to avoid bad dreams while sleeping, as your body recharges through its connection with the Universal Force. If you have any problems, stress, or illnesses this is the best time to allow the Universal Consciousness to help you find the solution or cure. When you awaken after sleep, smile inwardly, and look for answers within.

3. You can devote extra time to an organ when you feel troubled by it or its associated emotions. You may also emphasize extra practice for an organ during its particular season. For example, in spring you would spend more time on the Liver Sound.

4. The order of the Six Healing Sounds follows the progression of the seasons.

Starting with autumn, practice the Lung Sound, followed by the sounds of the kidneys, liver, heart, and spleen. Finish with the Triple Warmer Sound.

5. When you are feeling tired or depressed at work, practice the Six Healing Sounds. If you do not have time to do them all, just practice the Lung Sound and the Kidney Sound.

For further information about Universal Tao Centers, courses, or other resources, contact:

Universal Tao Instructor Associations

North America Instructors Association (NAIA)

c/o Loretta Robb, Treasurer
13 Plymouth Drive, Newark, Delaware 19713 USA
Tel: (1)(888) 444-7426 (Toll Free) or (1)(212) 330-7876
Email: info@taoinstructors.org   Website: http://taoinstructors.org

European Instructors Association (EIA)

c/o Zentrum Waldegg
3823 Wengen, SWITZERLAND
Tel: (41)(33) 8554422 Fax: (41)(33) 8555068
Email:info@waldegg.ch   Website: www.waldegg.ch

To order English books, and for your local Insructors use our Web Sites: www.universal-tao.com and www.tao-garden.com

Universal Tao World Fulfillment Center

274 Moo 7, Luang Nua, Doi Saket, Chiang Mai, 50220 Thailand
Tel: (66)(53) 495-596 & 865-034 Fax: (66)(53) 495-852
North America Fax (1)(212) 504-8116   Europe Fax (31)(20) 524-1374
Email: universaltao@universal-tao.com **or** info@tao-garden.com

The Universal Tao is not and cannot be responsible for the consequences of any practice or misuse of the information in this booklet. If the reader undertakes any exercise without strictly following the instructions, notes, and warnings, the responsibility must lie solely with the reader.



$6.95

Cosmic Sounds

Sounds that Heal

Mantak Chia

Illustrations by Udon Jandee

Cosmic Six Healing Sounds

The Sounds that Heal are the Six Healing Sounds and related postures helping to restore, balance, and cleanse the vital organs. They also stimulate the Chi flow throughout the body to enhance one's overall health and vitality. The Cosmic Six Healing Sounds and their postures help to release any excess heat that may be trapped in the cooling sacs which surround each organ. This booklet will show you how to assume the postures and produce the sounds sub-vocally; their vibrations redistribute any excess heat into cooler regions of the body where it can safely be stored or used. Once the organ energies are balanced, you have a good foundation for establishing and nurturing the virtue energies. This will help to maintain the Chi balance throughout the system.

Practice of the Cosmic Six Healing Sounds will restore and maintain your calmness and good health. Greater sexual pleasure and improved digestion will occur. Minor ailments, such as colds, flu, and sore throats, can be prevented or thrown off easily. Several psychologists have taught some of their patients to use the Cosmic Six Healing Sounds to relieve depression, anxiety or anger; and body work oriented healers have used the Six Healing Sounds to help speed up healing, and the healer spends less life force energy.

ISBN 0-935621-32-6

9 780935 621327

Universal Tao Publications
274 Moo 7, Luang Nua, Doi Saket,
Chiang Mai 50220, Thailand
Tel: (66)(53) 495-596 Fax: 495-852
Email: universaltao@universal-tao.com
Web Site: www.universal-tao.com



Fusion of the Five Elements

Basic and Advanced Meditations for Transforming Negative Emotions

Mantak Chia

Fusion of the Five Elements

Basic and Advanced Meditations for Transforming Negative Emotions

---

Mantak Chia

Edited by:

Valerie J. Meszaros

Editor and Designer: Valerie J. Meszaros

Design and Publishing Consultant: Joel Friedlander

Editorial Contributors: Chuck Soupios, Michael Winn

Illustrator: Juan Li

Cover Designer: Ivan Salgado

Revised Design and Production: Soraya Kongnguen

Final Editing: Jean Chilton

Copyright ©1989 Mantak and Maneewan Chia

Universal Tao Publications
274/1 Moo 7, Luang Nua,
Doi Saket, Chiang Mai, 50220 Thailand
Fax (66) (53) 495-853
Email: universaltao@universal-tao.com
Web Site: www.universal-tao.com

ISBN: 0-935621-18-0
Library of Congress Catalog Card Number: 89-083350

Manufactured in Thailand
Fourth Printing, 2002

All rights reserved. No part of this book may be used or reproduced in any manner whatsooever without the expressed writted permission from the author except for brief quotations embodied in critical articles and reviews.

Contents

Contents.. i
About the Author.. x
Acknowledgments.. xvi
Words of Caution.. xvii

Introduction to Fusion of the Five Elements.................... 1
A. Foundation for Transformation 1
  1. External and Internal Alchemy 1
  2. Natural Connections of the Inner Universe and the Outer Universe 1
  3. Universal Force, the Cosmic Particle Force, and the Earth Force.. 2
  4. Humans Depend on Vegetables, Animals, and Minerals as Sources of Universal Force....................... 3
  5. Five Elements' Forces of the Universe, Earth, and Humans... 5
  6. Fusion of the Five Elements Practice.......................... 7
  7. Pearl- Essence of the Human Body and the Energy Body... 10
  8. Universal Tao divides Fusion into Three Parts 11

Description of Fusion 1 13
Part One: Basic Practice
  Chapter 1.. 13
  Chapters 2 through 3... 14
  Chapters 4 through 5 15
Part Two: Advanced Practice
  Chapter 6... 16
  Chapters 7 through 9... 17

Fusion I Meditation—Part One
Basic Practice of Fusion I...................................... 18

Chapter 1
Formula 1: Forming the Four Pakuas, Blending Energy, and Forming the Pearl at the Center of Control 19

A. Theory: Four Pakuas and the Cauldron 19
- 1. Construction of the Pakua 20
- 2. Location of the Four Pakuas.. 20
- 3. Location of the Cauldron (the Central Point of a Human Being-the Point of Control)................................. 21

B. Practice of Formula 1... 22
- 1. Assume the Position... 22
- 2. Practice the Inner Smile.. 22
- 3. Form the Front Pakua... 24
- 4. Form the Back Pakua 24
- 5. Spiral the Front and Back Pakua Energy to the Cauldron... 25
- 6. Construct the Right Side Pakua.................................... 25
- 7. Construct the Left Side Pakua...................................... 26
- 8. Spiral the Left and Right Pakua Energy into the Cauldron 27
- 9. Form a Pearl 26
- 10. Anchor and Program the Pearl through Verbal Affirmations.. 28
- 11. Move the Pearl into the Microcosmic Orbit 28
- 12. Collect the Energy.. 30
- 13. Finish with Chi Massage... 30

C. Purpose of Centering Awareness in the Pearl.................. 33

Chapter 2

Formula 2: Balancing the Organ Energy to Experience Inner Peace and Harmony 34

A. Theory: Collection Points for Each Organ

- 1. Kidney (Bladder’s) Collection Point 34
- 2. Heart/Thymus (Small Intestine’s) Collection Point 36
- 3. Liver (Gall Bladder’s) Collection Point........................... 34
- 4. Lungs (Large Intestine’s) Collection Point 35
- 5. Spleen/Pancreas (Stomach’s) Collection Point............. 35

B. Procedure for Balancing the Organ Energy....................... 35

C. Practice of Formula 2... 36
- 1. Begin with the Inner Smile Meditation 36
- 2. Form the Front Pakua.. 36
- 3. Balance the Energies of the Kidneys and Heart............ 36
- 4. Spiral and Draw the Heart’s and Kidneys’ Energies

to the Front Pakua 38
5. Balance the Energies of the Lungs and Liver 38
6. Spiral and Draw Liver's and Lungs' Energies
to the Front Pakua 43
7. Pull the Spleen's Energy into the Front Pakua 43
8. Form the Back Pakua and Blend the Energy from
the Back Collection Points 44
9. Draw the Energies from the Front and Back Pakuas
into the Cauldron 46
10. Form the Right Side Pakua and Blend theEnergies 46
11. Form the Left Side Pakua and Blend the Energies
from the Left Side Collection Points 46
12. Draw the Energies from the Right and Left Pakuas
into the Cauldron 46
13. Condense the Energies into a Refined Pearl 48
14. Anchor the Feelings of Peace and Harmony
to the Pearl 49
15. Move the Pearl into the Microcosmic 49
16. Collect the Energy and Practice Chi Massage 49

Chapter 3
Formula 3: Connecting the Senses with the Organs; Self-Control of the Senses; Sealing he Openings; Overcoming Temptations 50
A. Theory 50
1. Ears—Kidneys 50
2. Tongue—Heart 50
3. Eyes—Liver 52
4. Nose—Lungs 52
5. Mouth—Spleen 52
B. Procedure of Connecting the Senses with the Organs 54
C. Practice of Formula 3 55
1. Assume the Position 55
2. Practice the Inner Smile 55
3. Massage the Senses and the Organs 55
4. Concentrate on the Ears and the Kidneys 55
5. Concentrate on the Tongue and Heart 55
6. Spiral and Blend the Essence Energies
in the Front Pakua 57
7. Concentrate on the Eyes and Liver 57

8. Concentrate on the Nose and Lungs 57
9. Blend the Essence Energies of the Eyes/Liver and Nose/Lungs in the Front Pakua.............................. 59
10. Concentrate on the Mouth and Spleen......................... 59
11. Form the Back, Right, and Left Pakuas and Draw their Collected Energies into the Cauldron................... 60
12. Form a Pearl.. 60
13. Affirm your Self-Control by Anchoring and Programming the Pearl with Verbal Affirmations... 61
14. Move the Pearl to the Perineum.................................. 61
15. Collect the Energy and Practice Chi Massage............ 61

Chapter 4
Formula 4: Transforming the Negative Emotions of Each Organ into Useful Energy....................................... 62
A Theory: Relationships between Organs and Emotions 62
B. Practice of Formula 4.. 63
1. Smile Down... 63
2. Form the Front Pakua... 63
3. Be Aware of Fear in the Kidneys 65
4. Be Conscious of Impatience in the Heart 66
5. Spiral, Blend, and Transform the Energy of the Heart and Kidneys at the Front Pakua 67
6. Perceive Anger in the Liver 67
7. Be Aware of Sadness and Depression in the Lungs.. 68
8. Spiral, Blend, and Transform the Energy of the Liver and Lungs at the Front Pakua 69
9. Be Conscious of Worry in the Spleen............................ 69
10. Spiral All Remaining Negative Energy to the Front Pakua.. 70
11.Practice Inner Observation.. 73
12. Clean Out the Negative Energy to Make Room for Positive Energy... 73
13. Allow Virtue Energy to Grow in the Organs 73
14. Transform the Negative Energy as the Most Powerful Act of Forgiveness... 73

15. Project Inner Virtue Outwardly to Increase Virtue Energy........ 74
16. Practice External Observation and Develop the Art of Non- Attachment........ 74
17. Prepare the Body to Receive the Universal Force........ 75
18. Increase the Psychological Properties of the Organs........ 77
19. Form the Back, Right, and Left Pakuas and Draw their Collected Energies into the Cauldron........ 78
20. Form a Pearl........ 78
21. Circulate the Pearl in the Microcosmic Orbit........ 78
22. Practice Chi Massage........ 78

Chapter 5
Formula 5: Creating the Pearl that Forms the Energy Body........ 80
A. Procedure to Create a More Advanced Pearl........ 80
B. Practice of Formula 5 to Create the Pearl........ 80
  1. Form the Front Pakua and Blend the Energy from the Front Collection Points........ 80
  2. Form the Back, Right, and Left Pakua and Draw their Collected Energies into the Cauldron........ 80
  3. Condense the Energies into a Refined Pearl........ 81
C. Working with the Pearl........ 81
  1. Circulate the Pearl in the Microcosmic Orbit........ 82
  2. Activate the Cranial and Sacral Pumps to Open the Crown........ 82
  3. Look for the Lead Light........ 82
  4. Extend the Pearl above the Crown........ 82
  5. Reactivate the Cranial Pump; Draw the Pearl Back into the Microcosmic Orbit of the Physical Body........ 82
  6. Advanced Stage........ 82
  7. Finish the Practice........ 82
D. Creating the Yin and Yang Bodies (the Soul Body or Energy Body and the Spirit Body) for Space Travel........ 88
  1. Energy Body is Born from the Original Force—*Born Again*........ 88
  2. Energy Body is Like a Newborn Infant........ 89

3. Yin Body's Transformation to a Yang Body Marks the Beginning of the Transference of Consciousness......... 89
    4. Purpose of Traveling in Space..................................... 89
E. How to Develop the Energy Body....................................... 90
    1. Using a Pearl to Create the Energy Body...................... 90
    2. Creating the Energy Body 90
    3. Transferring the Microcosmic Orbit to the Energy Body.. 97
    4. Forming a Protective Shield Around the Energy Body... 97
    5. Forming a Great Bubble Encasing Both Bodies as a Protective Shield.. 101
    6. Drawing in the Energy Body and the Big Protective Bubble to Finish the Practice... 101

Fusion I Meditation—Part Two

Advanced Practice of Fusion I....................................... 103

Chapter 6

Formula 6: Forming the Virgin Boy or Girl and Their Animal Offspring to Connect to the Universal, Cosmic Particle, and Earth Forces.................. 104
    A. Using Images of Children and Animals to Give Form to Pure Energy.. 104
    B. Practice of Forming the Virgin Boys or Girls and their Offspring in the Forms of Animals............................ 105
        1. Pure Energy from the Kidneys Produces the Blue Virgin Child and the Deer...105
        2. Essence of the Heart Produces the Red Virgin Child and the Pheasant.. 106
        3. Pure Energy from the Liver Produces the Green Virgin Child and the Dragon...................................... 107
        4. Lungs' Essence Produces the White Virgin Child and a Tiger.. 108
        5. Pure Energy of the Spleen Produces the Yellow Virgin Child and the Phoenix 109
C. Use the Virgin Boy or Girl and the Animals to Form Protective Rings Inside the Body....................................... 110

D. Pearl Connects with the Universal, Cosmic Particle, and Earth Forces to Supply Energyto the Children and Animals 111
E. Finish the Meditation 111

Chapter 7

Formula 7: Call Forth the Earth Force to Empower and Protect

Chapter 7 Formula 7: Call Forth the Earth Force to Empower and Protect 112
A. Pure Kidneys' Energy Attracts the Earth Force in the Image of a Big, Blue/Black Turtle 112
B. Pure Heart's Energy Attracts the Earth Force in the Shape of a Red Pheasant 114
C. Pure Liver's Energy Attracts the Earth Force in the Image of a Green Dragon 115
D. Pure Lungs' Energy Attracts the Earth Force in the Image of a White Tiger 116
E. Pure Spleen's Energy Attracts the Earth Force in the Image of a Yellow Phoenix 117
F. Form the Earth Force Animals into a Protective Ring and Dome of Fire 117
G. Create the Energy Body 120
H. Finish the Meditation 120

Chapter 8 Formula 8: Call Forth the Planets' and Stars' Forces for Empowerment and Protection 122
A. Pearl is the Product of your Successful Practice 122
B. Create a Fully Developed Pearl; Extend and Maintain the Pearl above the Crown 122
C. Call Forth the Force of the Planets 123
  1. Summon Mercury's Force to the Energy Body 123
  2. Summon the Force of Mars to the Energy Body 127
  3. Summon Jupiter's Force to the Energy Body 127
  4. Summon the Force of Venus to the Energy Body 129
  5. Summon the Force of Saturn to the Energy Body 129
  6. Be Conscious of the Five Planets Surrounding the Energy Body 130
D. Set the Planets into Orbit Around, and Absorb their Forces into, the Energy Body 130

1. Start the Orbit of Mars Around the Energy Body 130
    2. Movement of Mars Activates the Orbit of the Other Planets Around the Energy Body 130
    3. Saturn Provides the Protective Dome over the Crown 131
    4. Absorb the Planets' Forces into the Energy Body...... 131

E. Energy Body Beams the Planets' and Stars' Forces into the Crown... 131
    1. Crystal Room under the Crown Serves as a Prism of the Planets' Forces 131
    2. Forces of the North Star and the Big Dipper Shine into the Crown... 131
    3. Condensed Essential Forces Revert to the Original Forces... 131

F. Earth Force in the Virgin Children's and Animals' Forms Interconnects with the Forces of the Planets and Stars.. 133
    1. Be Aware of the Virgin Children, the Internal Animals, and the Planets and Stars.. 133

G. Finish the Exercise 136
    1. Condense the Energy Body into a Pearl 136
    2. Draw the Pearl in and Move it in the Microcosmic Orbit... 136
    3. Absorb the Forces of the Planets, Stars, and Earth.. 136
    4. Collect the Energy.. 136
    5. Practice Chi Massage... 136

Chapter 9
Formula 9: Transfer of Consciousness to the Energy Body in this Life Brings Immortality

Chapter 9 Formula 9: Transfer of Consciousness to the Energy Body in this Life Brings Immortality 137

A. Transfer the Microcosmic Orbit to the Energy Body...... 137

B. Form a Protective Shield.. 140

C. Form a Great Bubble Encasing Both Bodies as a Protective Shield 140

D. Absorb All Forces into Both Bodies............................... 140

E. Draw in the Energy Body and the Big Protective Bubble 144

F. Protective Shield Remains 145

G. Absorb the Forces into the Pearl or Directly into the Organs of their Origin...146

H. Finish the Practice...146

Chapter 10

Formula 10: Summary of the Entire Fusion I Practice...... 147
All Formulas 1 through 9
A. Create a Pearl 147
B. Form the Virgin Children and the Protective Animals..... 147
C. Call Forth the Earth Force as a Protector and Source of Energy...148
D. Circulate the Pearl in the Microcosmic Orbit..................149
E. Form the Energy Body..150
F. Call Forth the Planets' Forces.. 150
G. Transfer the Microcosmic to the Energy Body 153
H. Form a Protective Shield and a Larger Protective Bubble around the Physical and Energy Bodies........................153
I. Condense and Collect the Energy....................................153
J. Finish the Exercise...154
K. Practice Fusion Daily..154
Advanced Practice Summary..154
More Advanced Practice Summary 155
Most Advanced Practice Summary 155

Daily Usage of Fusion of the Five Elements..................... 157

Five Element/Organ Correspondences Tables

Table 1.. 64
Table 2.. 71
Table 3.. 72
Table 4.. 119
Table 5.. 135

Universal Tao System Overview........................ *Overview 1-35*

About the Author

Mantak Chia

Master Mantak Chia is the creator of the Universal Tao System and is the director of the Universal Tao Center and Tao Garden Health Resort and Training Center in the beautiful northern countryside of Thailand. Since childhood he has been studying the Taoist approach to life. His mastery of this ancient knowledge, enhanced by his study of other disciplines, has resulted in the development of the Universal Tao System which is now being taught throughout the world.

Mantak Chia was born in Thailand to Chinese parents in 1944. When he was six years old, Buddhist monks taught him how to sit and “still the mind”. While still a grammar school student, he learned traditional Thai boxing. He was then taught Tai Chi Chuan by Master Lu, who soon introduced him to Aikido, Yoga and broader levels of Tai Chi.

Years later, when he was a student in Hong Kong excelling in track and field events, a senior classmate named Cheng Sue-Sue introduced him to his first esoteric teacher and Taoist Master, Master Yi Eng (I Yun). At this point, Master Chia began his studies of the Taoist way of life in earnest. He learned how to circulate energy through the Microcosmic Orbit and, through the practice of Fusion of the Five Elements, how to open the other Six Special Channels. As he studied Inner Alchemy further, he learned the Enlightenment of the Kan and Li, Sealing of the Five Senses, Congress of Heaven and Earth and Reunion of Heaven and Man. It was Master Yi Eng who authorized Master Chia to teach and heal.

When Mantak Chia was in his early twenties he studied with Master Meugi in Singapore, who taught him Kundalini, Taoist Yoga and the Buddha Palm. He was soon able to clear blockages to the flow of energy within his own body. He learned to pass the life force energy through his hands also, so that he could heal Master Meugi’s patients. He then learned Chi Nei Tsang from Dr. Mui Yimwattana in Thailand.

A while later, he studied with Master Cheng Yao-Lun who taught him the Shao-Lin Method of Internal Power. He learned the closely guarded secret of the organs, glands and bone marrow exercise known as Bone Marrow Nei Kung and the exercise known as Strengthening and Renewal of the Tendons. Master Cheng Yao-Lun’s system combined Thai boxing and Kung Fu. Master Chia also studied at this time with Master Pan Yu, whose system combined Taoist, Buddhist and Zen teachings. Master Pan Yu also taught him about the exchange of Yin and Yang power between men and women, and how to develop the Steel Body.

To understand the mechanisms behind healing energy better, Master Chia studied Western anatomy and medical science for two years. While pursuing his studies, he managed the Gestetner Company, a manufacturer of office equipment and became well acquainted with the technology of offset printing and copying machines.

Using his knowledge of Taoism, combined with the other disciplines, Master Chia began teaching the Universal Tao System. He eventually trained other Instructors to communicate this knowledge and he established the Natural Healing Center in Thailand. Five years later, he decided to move to New York, where in 1979, he opened the Universal Tao Center. During his years in America, Master Chia continued his studies in the Wu system of Tai Chi with Edward Yee in New York.

Since then, Master Chia has taught tens of thousands of students throughout the world. He has trained and certified over 1,500 instructors and practitioners from all over the world. Living Tao Centers, Chi Nei Tsang Institutes, Cosmic Healing Forums and Immortal Tao Mountain Sanctuaries have opened in many locations in North America, South America, Europe, Asia, Africa and Australia.

In 1994, Master Chia moved back to Thailand, where he had begun construction of Tao Garden and the Universal Tao Training Center fifteen miles outside of Chiang Mai.

Master Chia is a warm, friendly and helpful man who views himself primarily as a teacher. He presents the Universal Tao System in a straightforward and practical manner, while always expanding his knowledge and approach to teaching.

Master Chia estimates that it will take thirty five books to convey the full Universal Tao System. In June 1990, Master Chia was honored by the International Congress of Chinese Medicine and Qi Gong (Chi Kung), who named him the Qi gong Master of the Year. He is the first recipient of this annual award.

In December 2000, the Tao Garden Health Resort and Universal Tao Training Center was completed with two Meditation Halls, two open air Simple Chi Kung Pavilions, indoor Tai Chi, Tao Yin and Chi Nei Tsang Hall, Tai Chi Natural Swimming Pool, Pakua Communications Center with a complete Taoist Library, Internal World Class Weight Lifting Hall and complete 8 Court Recreational Facilities.

In February 2002, the Immortal Tao practices will be held at Tao Garden for the first time using Dark Room technology, creating a complete environment for the higher level Taoist practices.

Master Mantak Chia has previously written and published these Universal Tao books:

Awaken Healing Energy of the Tao - 1983
Taoist Secrets of Love: Cultivating Male Sexual Energy co-authored with Michael Winn - 1984.

Taoist Ways to Transform Stress into Vitality -1985
Chi Self-Massage: the Tao of Rejuvenation - 1986
Iron Shirt Chi Kung I - 1986
Healing Love Through the Tao: Cultivating Female Sexual Energy - 1986
Bone Marrow Nei Kung - 1989
Fusion of the Five Elements I - 1990
Chi Nei Tsang: Internal Organ Chi Massage - 1990
Awaken Healing Light of the Tao - 1993
The Inner Structure of Tai Chi co-authored with Juan Li - 1996
Multi-Orgasmic Man co-authored with Douglas Abrams 1996 - published by Harper Collins
Tao Yin - 1999
Chi Nei Tsang II - 2000
Multi-Orgasmic Couple co-authored with Douglas Abrams 2000 - published by Harper Collins
Cosmic Healing I - 2001
Cosmic Healing II co-authored with Dirk Oellibrandt - 2001
Door of All Wonders co-authored with Tao Haung - 2001
Sexual Reflexology co-authored with W. U. Wei - 2002
Elixir Chi Kung - 2002

Many of the books above are available in the following foreign languages:

Arabia, Bulgarian, Czech, Danish, Dutch, English, French, German, Greek, Hebrew, Hungarian, Indonesian, Italian, Japanese, Korean, Lithuanian, Malaysian, Polish, Portuguese, Romania, Russian, Serbo-Croatian, Slovenian, Spanish, & ***Turkish*** editions are available from the Foreign Publishers listed in the Universal Tao System Overview in the back of this book.

Acknowledgments

I wish to thank foremost those Taoist Masters who were kind enough to share their knowledge with me, never dreaming it would be so enthusiastically received by the Western world.

I thank the artist, Juan Li, for his informative illustrations. I thank Valerie Meszaros, the editor of this book, for her dedication and thoroughness, as well as her skill in design and production on our new desktop publishing system. I thank Charles Soupios for his editorial assistance in the technical aspects of this practice, and Michael Winn for his general editorial contributions. I thank Ivan Salgado, the designer of this book's cover. I also want to extend my thanks to our publishing consultant, Joel Friedlander. His advice in establishing our new state of the art desktop publishing system and in contributing to the design of this book has been invaluable.

Further, I wish to express my gratitude to all instructors and students who have offered their time and advice to enhance the communication of this practice and this system.

Without my mother and my son Max, my continued efforts in bringing you the Universal Tao System would be academic. For their gifts, I offer my eternal gratitude and love.

A special thank you goes to our ***Thai Production Team*** for their cover illustration and book design and layout: Raruen Keawpadung, Computer Graphics; Saysunee Yongyod, Photographer; Udon Jandee, Illustrator; and Saniem Chaisarn, Production Designer.

Words of Caution

The practices described in this book have been used successfully for thousands of years by Taoists trained by personal instruction. Readers should not undertake the practice without receiving personal transmission and training from a certified instructor of the Universal Tao, since certain of these practices, if done improperly, may cause injury or result in health problems. This book is intended to supplement individual training by the Universal Tao and to serve as a reference guide for these practices. Anyone who undertakes these practices on the basis of this book alone, does so entirely at his or her own risk.

The meditations, practices and techniques described herein are ***not*** intended to be used as an alternative or substitute for professional medical treatment and care. If any readers are suffering from illnesses based on mental or emotional disorders, an appropriate professional health care practitioner or therapist should be consulted. Such problems should be corrected before you start training.

Neither the Universal Tao nor its staff and instructors can be responsible for the consequences of any practice or misuse of the information contained in this book. If the reader undertakes any exercise without strictly following the instructions, notes and warnings, the responsibility must lie solely with the reader.

This book does not attempt to give any medical diagnosis, treatment, prescription, or remedial recommendation in relation to any human disease, ailment, suffering or physical condition whatsoever.

Introduction

Fusion of Five Elements

A. Foundation for Transformation

1. External and Internal Alchemy

For more than five thousand years, Taoist masters researched and developed various methods to attain such desirable achievements as long life and happiness. Some of the methods were called External Alchemy, and these included the Immortal Pill, magic potions, crystals, crystal essences, flower essences, precious stones, etc. The highest Taoist masters realized external methods offered only limited help while building dependencies on materials that were difficult to come by.

In their continued search for an unlimited source of energy, they turned their attention inwardly to uncover the mysteries surrounding their life-forces. In their search they discovered a universe within and found it to be identical to the outer universe. They knew that the outer universe harbored a tremendous force, and that the inner universe of a human being could benefit from that force, if the two could somehow be connected.

The Taoist masters reasoned that to become connected to the outer universe, one first needs to gain control of his or her own inner universe. They experienced this inner universe as a flow of energy, or Chi, through their bodies. The Microcosmic Orbit, running up the spine and down the front of the body, was uncovered as the pathway through which the distilled essence of this energy flows. They perceived that the Microcosmic Orbit connects three bodies--physical, soul, and spirit--within each individual and ultimately fuses them into one immortal body. It was with this perception that the study of Internal Alchemy began.

2. Natural Connections of Inner and Outer Universes

In turning their attention toward understanding the nature and connection between the forces of the outer universe and the forces of the human body, the Taoist masters made another discovery. Each life born into the human form is developed, structured, and influenced by a group of stars. This group of stars, which includes the planets and cosmic particles within its configuration, controls the life-force, the good and bad fortune, and the birth and death of the individual.

Each day of a person's life reflects a continuing need to absorb energy from the stars and planets and from the cosmic particles. To explore the patterns of star energy in detail, ancient Taoists developed the science of astrology to a very high level.

In addition to the energy from the stars, the Taoist masters found that humans require another source of natural energy: the energy supplied by the Earth's force. It is the absorption of all natural forces that nourishes the nervous system, organs, glands, senses, soul, and spirit of a human being. To facilitate their understanding of the forces of nature, the Taoists divided them into three classifications.

3. Universal Force, Cosmic Particle Force and Earth Force

a. The first force is called the Universal or Original Force, and is also known as Heavenly Energy. It manifests as the energy of all the stars, planets, and galaxies. This vast, all-pervading force nourishes the mind, soul, and spirit of each individual and everything else in the universe that is manifest.

The Universal Force is drawn to our planet because of the unique relationship between the Earth and its Moon. The combined forces of the Earth and the Moon create a very strong, magnetic power that attracts and beams down to Earth the energies of all the stars in our galaxy.

b. The Cosmic Particle Force, or Human Plane Energy, is the second force of nature. Cosmic particles are a part of the Original Force that flows in space. They are the result of exploded stars that have come to the end of their life cycles, drifting in space as very fine particles. As the strong, magnetic power created by the Earth and Moon attracts many of these particles, they then drift through the Earth's atmosphere as dust, and eventually become soil.

It is the Taoists' belief that human flesh is formed from the fallen cosmic dust of the universe. These particles, or dust, nourish the essences of the organs, glands, and senses of all humans. Humans are the highest manifestation of Cosmic Particle Force, gathering this energy into their bodies through meditation and ultimately returning it to its primordial source.

c. As the third force of nature, the Earth Force includes the energy of plants, animals, water, and all the natural occurrences of the planet Earth. The Taoists observed that plants and trees, in their upward growth, are ever extending themselves to absorb the energy necessary to process their food. Stretching themselves to the sun and stars, and to the cosmic particles above, the plants and trees use the Universal Force for sustenance and growth. The animals, in turn, consume the vegetation, profiting from the cosmic energy as they do so.

Together these three forces represent the energies of Heaven, Humans, and Earth working in harmony to sustain all existence. The ancient Taoists called the Rulers of these forces the Three Pure Ones, for theirs were the first energies to emerge from the Wu Chi, the Great Emptiness. (Fig.1)

Traditionally, the Three Pure Ones were visualized as Three Emperors residing in the three palaces or centers of the body called the Upper, Middle, and Lower Tan Tiens. They govern the development of the three bodies--physical, soul (or energy), and spirit—within an individual by cultivating three forces manifest in the human body as Ching, Chi, and Shen, respectively.

4. Humans Depend on Vegetables, Animals, and Minerals as Sources of Universal Force

Humans originally were created with body cells capable of consuming and absorbing 90 percent of the cosmic forces and light to which they were exposed. However, our cells began to deteriorate to a five to ten percent capability of consumption and absorption when we began to expend and lose our sexual energies. All plants, trees, and vegetation continue to retain their ability to consume and absorb the cosmic forces and light to an 80 percent capacity, with water and nutrients supplying the remaining twenty percent of their food.

Without any consciousness about these forces, and without any practice, humans automatically continue to receive a minute amount of life-force energies naturally. This is particularly true of the Earth Force that provides Yin and Yang energy (negatively and positively charged Universal Energy) to all the organs, glands, and senses, and provides nourishment and enhancement to the sexual organs and sexual energy of humans.

Since our body cells no longer enable us to more fully receive life-force from the Universal, Cosmic Particle, and Earth Forces, we must depend heavily on the vegetation, animals, and minerals comprising the Earth Force to do so. Since they predigest the Universal Force, efficiently absorbing it directly themselves, humans can depend on them to supply necessary life-force energy. Humans consume the vegetation, animals, and minerals and absorb the three main forces slowly through them. The consumption and absorption coincides with the movement of the Earth in its 365 day orbit around the Sun, with the seasons of the year greatly affecting the foods consumed and the energy absorbed.

Through the practice of Fusion of the Five Elements, humans can learn about the original source of all power. They can increase their ability to absorb and transform this force directly and easily, relieving their dependence on plants and animals to convert the force for them.

5. Five Elements' Forces of Universe, Earth, and Human

The Taoists further classified all things in the universe making up the Universal Force, the Cosmic Particle Force, and the Earth Force as correspondences of the "five elements," "five phases," or "five interacting" forces of nature. That is, each force originates from and is controlled by the Five Elements of Nature. These are earth, metal, fire, wood, and water.

a. Origins of the Five Elements of Nature

Taoists believe that the Five Elements of Nature originated as five huge stars, given birth by the Three Pure Ones out of the Wu Chi. These five stars (or five elements), in turn, gave birth to the entire universe, including trillions of stars. They created the North which created smaller stars, including five major constellations. From the constellations, the planets arose, including the Earth. The five constellations have a direct relationship with five planets, five seasons of the Earth, five directions of the Earth, and five major organs of the human body. (Fig.2)

.

Original
Emptiness

Triple Unity,the 3 Pure Ones

Grand Force of the 5 Elements

Pole Star

Big Dipper

28 Constellations

Planets

Sun

Moon

Fig. 2. *The Universe*

The Taoists consider the Five Elements' Forces to be Grand Forces, and sometimes refer to them in this way.

1. The Grand Force of Water created the Northern Constellation and the planet Mercury. It manifests as the northern direction of the Earth Force and the Winter season. It corresponds to the human water force of the kidneys and bladder. Its energy has an inwardly gathering quality.
2. The Grand Force of Fire created the Southern Constellation and the planet Mars. It manifests as the southern direction of the Earth Force and the Summer season. It corresponds to the human fire force of the heart and small intestine. Its energy has an expanding, developing quality.
3. The Grand Force of Wood created the Eastern Constellation and the planet Jupiter. It manifests as the eastern direction of the Earth Force and the Spring season. It corresponds to the human wood force of the liver and gall bladder. Its energy has a generating quality.
4. The Grand Force of Metal created the Western Constellation and the planet Venus. It manifests as the western direction of the

Earth Force and the Fall season. It corresponds to the human metal force of the lungs and large intestine. Its energy has a contracting quality.

5. The Grand Force of Earth created the Central Constellation and the planet Saturn. It manifests as the central direction of the Earth Force and the Indian Summer season. It corresponds to the human earth force of the spleen, stomach, and pancreas. Its energy has a stabilizing quality.

6. Fusion of Five Elements Practice

To make connections between and to gain control of the inner and outer universes, the Taoists developed the Fusion of the Five Elements practice. Fusion begins with understanding the dynamics of the universe, the planet Earth, and the human body with respect to their relationships to the Five Elements of Nature.

Fusion of the Five Elements, marking the beginning of the Taoist practice of Internal Alchemy, focuses on the interaction and fusion of all five elements and their correspondences, and their transformation into a harmonious whole of high quality energy. During this process the essence of life-force energy found in the organs, glands, and senses is transformed, purified, condensed, and combined with the Universal Force. The new form of energy that emerges through this process can effect positive changes in the human body.

To effect positive changes in the human body, the Taoists first focus on the negative aspects or weaknesses to transform them into strengths. The weaknesses are uncovered by focusing on what is known as the counteracting or controlling forces of the Five Elements. This means studying the effects of the five elements upon each other,

In studying the energy of the liver, for example, the organ associated with the planet Jupiter and the wood element, it was discovered that its energy can be counteracted or controlled by the energy of the lungs, associated with the planet Venus and the metal element. That is, the metal element controls the wood element, and the lungs control the liver. Similarly, the energy of the kidneys, associated with the planet Mercury and the water element, can be counteracted by the energy of the heart, associated with the planet Mars and the element fire. This means the water element controls the fire element, and the kidneys control the heart. All five elements have a counteracting force. (Fig.3)


Metal
Lungs
Sadness
Depression
Water
Kidneys
Fear
Earth
Spleen/
Stomach
Worry
Wood
Liver
Anger
Fire
Heart
Cruelty
Hastiness

Fig. 3. *Counteracting Cycle*

The interaction of the two elements of water and fire is an easy one to comprehend. The heat of fire can evaporate water, thereby controlling it. If this is true, then the reverse is also true--fire can be counteracted or controlled by the water element. Water can extinguish a fire. The Taoists considered the interactions of the five elements as two distinct cycles existing in nature--the Creative Cycle and the Counteracting or Controlling Cycle. Both are equally important in sustaining life, but need to be balanced and in control if things are to be kept running smoothly. Both cycles help determine which of your organs are weak and which are strong. They are studied in depth in the Fusion practice, beginning with the Counteracting or Controlling Cycle and your negative emotions in Fusion I.

To utilize the two cycles effectively, it is important to determine your strengths and weaknesses. The planetary associations can play a major role in your conceptualization because there are months or years in which certain stars and/or planets can come very close to Earth and can greatly influence your behavior. For example, if you have a weak liver, when the planet Venus (the metal star associated with the lungs) comes close to Earth, your liver energy can be depleted. This can cause emotional outbursts of anger and indecisiveness, the negative emotions of the liver. If you do not know you need to strengthen the liver energy at these times and how to find a balance to your energy, you will be affected by such planetary events. This will affect all phases of your life. Eventually you will be overcome. When the liver is overly depleted by the intervention of the stars, planets, Earth, and other forces, recharging itself with energy will become very difficult. This is because it is in a weakened state. Then, when a charge of energy does come, the liver will not be able to fully utilize it. If the cycle continues and the counteracting forces of the stars, planets, Earth, and other sources approach again, the liver will be further depleted, now retaining little or no energy. This can cause tremendous suffering in all aspects of your life.

Using the Chapters of Fusion I helps you to create balance before delving into what star or planet influences you. The Chapters of Fusion I will provide a degree of creative and counteracting balances automatically. You will discover how wood and metal (liver and lungs) counteract each other, and will feel how they can be balanced automatically by the Earth Force. The weaker one will be strengthened. The overly strong one will be toned down by its opposing force. With neither one too weak nor too strong, they will become harmonious and not enemies of each other. In Fusion II you will delve deeper as you conscientiously search for your influencing stars and planets and use the cycles to promote greater strengths for your weaknesses.

The negative emotions associated with each organ, and, so, each element, are drawn out of the organs during the Fusion practice for transformation into a neutralized energy, thereby “balancing the weather” of the body’s total energies. This neutralized energy can be blended with positive energies, also residing in the organs, and transformed into pure life-force energy. The Taoists have a saying: “Refined red sand turns into silver.” This means if you fuse all the different kinds of emotional energy together, they will adhere into a harmonious whole. However, unrefined, “unfused” energy will have the quality of sand, scattered about and unable to stick together.

7. Pearl— Essence of Human Body and Energy Body

The pure life-force energy derived from the organs and fused together during the Fusion practice is crystallized into an energy ball. This energy ball can be perceived as a crystal or diamond, but is perceived most commonly as a radiant pearl. Forming the pearl is the first step toward transferring consciousness to a new realm.

Not all people perceive the pearl in the same way. Some might not see a pearl, but might recognize it as an acute feeling of awareness or as an intensified ability to concentrate. Some may feel a concentration of heat. All are experiencing the pearl as the essence of life-force energy.

This pearl is then circulated in the Microcosmic Orbit. During circulation the pearl activates and absorbs the Universal and Earth Forces. It also uses them to strengthen and purify the physical body, particularly the organs, glands, and senses. Later, the pearl plays a central role in developing and nourishing the soul body or energy body. It is developed further in the higher level Kan and Li Meditations.

Balanced energy not only is very desirable for the health of the organs, glands, and senses, but also is basic to the formation of a pearl. Thus, balanced energy is a very important element of Fusion. Also of great importance to the Fusion practice is the function of the pearl in opening, cleansing, purifying, and protecting specific channels that run through the body. These channels are called the Thrusting Channels (cleansing and protecting channels), the Belt Channel (a protecting channel), and the Great Regulator and Great Bridge Channels (channels binding together and regulating, respectively, energy flow through all the body’s acupuncture meridians.)

8. Universal Tao Divides Fusion into Three Parts

All Fusion levels of practice clean and purify the organs and the body.

a. Fusion of the Five Elements I

Fusion I makes use of pakuas and energy collection points to balance, connect, and draw out negative emotional energies found in the organs. These energies, along with their corresponding glands' and senses' energies, are then fused and transformed into pure life-force energy.

The purity of this energy has an adhering and magnetizing quality which enables it to condense into a pearl of refined energy. The pearl is then used to form the soul or energy body that will connect to the Universal, Cosmic Particle, and Earth Forces whose energies become part of the pearl.

Collecting the organs' energies in no way diminishes their strength. In fact, each time you practice Fusion, the essence energies collected from the organs are fused, purified, and transformed into an improved quality of life-force energy. Each time you finish the practice, the improved quality energy in the form of the pearl disperses. This energy returns to enhance all of the organs and glands, particularly those that require additional energy. The dispersed energy also provides protection to the physical and soul body.

b. Fusion of the Five Elements II

Fusion II focuses on using the pearl to grow or intensify the energy of good virtue. It uses the Creative Cycle to circulate the positive Chi of virtuous energy through the major organs. All the energy gathered during this cycle combines to form a pearl of compassion energy. This pearl is then used to open and cleanse the Thrusting Channels, and to open the protective Belt Channel that surrounds the Thrusting Channels.

c. Fusion of the Five Elements III

Fusion III opens the Great Regulator and Great Bridge Channels, combines all (eight) special channels together and sets them all into motion. More physical protection is developed through this process.

The entire Fusion practice is a step by step procedure of purifying yourself and controlling your own inner force. By creating the pure energy pearl and fusing the Five Elements' Forces to create a new, better, and purer life-force, you will gain the power of self-mastery.

You can use this energy externally to call forth directly the Universal and Earth Forces to empower and protect you. In this way the organs, glands, and senses comprising and supplying the life-force to the human body finally are reconnected to the stars, the planets, and the cosmic particles from which they emerged.

Description of Fusion I

Part One: Basic Practice

The Fusion practice is a meditation consisting of nine Chapters. Part One contains Chapters 1 through 5, the basic Fusion I practice, in which the five elemental forces of humans are worked with. Part Two contains Chapters 6 through 9, the methods of advanced practice, in which the work is continued with the five elemental forces of the Earth and the five elemental forces of the Universe. Although you can practice Fusion I by successfully completing the basic practice, the full benefit of Fusion I is attained by continuing through the advanced procedures.

Chapter 1: Forming the Four Pakuas, Blending Energy and Forming the Pearl at the Center of Control

The word pa means eight; kua means symbol. The pakua is an eight-sided, three dimensional crystal that draws energies from the organs, glands, and senses to be refined, transformed, condensed, and stored.

1. You begin this process by building four pakuas to refine, condense, and store the energy.
2. At the center of the body between the four pakuas, you create a self-center, center of being, or center of control called the cauldron.
3. As the energy is drawn by the four pakuas into the cauldron at your center of being, it is fused or crystallized into a life-force energy sphere or ball, a pearl of condensed energy. (The pearl is sometimes referred to as the inner pill or human pill.) This pearl then is circulated in the Microcosmic Orbit.

Chapter 2: Balancing the Organ Energy to Experience Inner Peace and Harmony

1. To balance the organ energy, you first form the collection points for the organs.
2. Then you draw, collect, and blend the different qualities

(kidneys [cold/wet], heart [hot], liver [warm, moist], lungs [cool, dry], and spleen [mild] into the collection points. This energy is moved to the front pakua which is considered the controlling pakua.

3. Form the back pakua and blend and refine the residual energies of the organs in the back collection points.

4. Spiral, draw, and condense all the energies from the front and back pakuas into the cauldron.

5. Similarly form the right and left side pakuas to collect any remaining organ energy. Blend and refine the energy in these pakuas, and then bring their combined energies into the cauldron.

6. In the cauldron all the energies are condensed into a pearl again. Then the pearl is moved to the Microcosmic Orbit for circulation.

Chapter 3: Connecting the Senses with the Organs; Self-Control of the Senses; Sealing the Openings; Overcoming Temptations

1. To strengthen and control the senses and prevent the sense energy from scattering, you will learn that the relationship between each of the organs and senses is like the relationship of parents and children.

2. You will turn the senses inward and draw them into the organs and their collection points. As in Chapter 2, the energy is moved into all four pakuas. In the pakuas, the energy is refined, and then it is condensed into the cauldron, the center of control, where the pearl is formed. The pearl now consists of the crystallized essences of the senses and organs, and again can be moved to and circulated in the Microcosmic Orbit.

Chapter 4: Transforming the Negative Emotions of Each Organ into Useful Energy

1. During thousands of years of exploring philosophy and psychology, the Taoists realized the need to explore basic human emotions. They observed that certain emotions, if not understood and dealt with, will attract or create other undesirable emotions. The Taoists believe that all emotions originate from the organs, and that the mind regulates and determines their use. Although the

emotional energies that can be sensed within an organ are not limited, certain specific, basic negative emotions are associated with each organ and are worked with in Chapter 4:

a. Kidneys-fear;
b. Heart-impatience, hastiness;
c. Liver-anger;
d. Lungs - sadness, depression; and
e. Spleen-worry.

2. As in Chapters 2 and 3, you blend and transform these energies in the front pakua, and create the back, left, and right side pakuas. In these four pakuas you will refine the energy, condense it into the cauldron to form a pearl, and circulate the pearl in the Microcosmic Orbit.

Chapter 5: Creating the Pearl that Forms the Energy Body and the First Transference of Consciousness

1. In Chapter 5 you will combine all the Chapters above. First you put the senses in contact with the organs and collect the organ and emotional energy in the collection points. You bring this energy to all four pakuas, and blend the energies there. This energy then is refined and condensed into the cauldron to form a pearl.

2. The pearl you create is projected from the physical body and controlled in the space above you. In its out-of-body condition, the pearl is formed into the energy body.

3. The energy body is formed into an image that you would like your physical body to be. You can give it a name at this time to make it easier to summon as you continue your practice.

4. The Microcosmic Orbit is transferred to the energy body from the physical body as the first experience of a transference of consciousness.

5. A protective shield is formed around the energy body, and a great bubble is formed encasing both the energy and physical bodies. At the end of this Chapter, the protective shield is reabsorbed while the great bubble shrinks down over the physical body to protect it. This layer then can be built upon with subsequent layers of protection as your practice continues.

Part Two: Advanced Practice

The advanced practice of Fusion I incorporates the five Chapters learned in the basic practice, and so it involves working with the five elemental forces of humans. However, after completing Chapter 4, and before proceeding with forming the energy body, in Chapter 5, you first practice Chapters 6 and 7 of the advanced practice to create a more powerful pearl to work with. Then, using the greatly refined and radiant energy of this pearl, you can create an energy body that now benefits from three additional sources of energy, the Earth, Cosmic Particle, and the Universal Forces. Then you proceed with this energy body to experience the remaining formulas.

The advanced practice formulas make use of images that enhance the organs' energies as you continue to refine the pearl.

Chapter 6: Forming the Virgin Boys or Girls and their Animal Offspring to Connect to the Universal, Cosmic Particle and Earth Forces

When the organ energy is very pure, you can project it and crystallize it into the image of a virgin boy or girl as the purest form of the virtue energy of the organs. Each virgin child's breath, in turn, creates an animal as its offspring. The children and animals can be used as protection for the physical body by connecting them to form protective rings. The pearl is the center of the gathering of the children and animals. Other images from your personal mythology may be substituted, such as a ring of saints, warrior-heroes, jewels, etc. If you circulate a pearl in the Microcosmic Orbit while under the protection of the children and animals' rings, and connect the pearl to the Universal, Cosmic Particle, and Earth Forces, you can bring those energies to the children and animals. They, in turn, can deliver this energy to the organs, glands, and senses for increased life-force.

Chapter 7: Call Forth the Earth Force to Empower and Protect

Once you have established a very pure organ energy, you can project it out of the body to call forth or attract the Earth Force to you. Once you have attracted this force, you form the animal or other earth images, such as flowers or trees, that will help you retain it. Then you use the animals to form a ring of fire to empower the organs and protect them. At this point refer again to Chapter 5 and create a more powerful energy body.

Chapter 8: Call Forth the Planets' and Stars' Forces for Empowerment and Protection

In this formula you will form pearls of pure organ energy to attract the planet that corresponds to each organ. The purpose is to draw on the planets' forces and add it to the forces of the virgin children, the internal animals, and the animals formed from the Earth elemental forces for empowerment and protection.

Chapter 9: Transference of Consciousness to the Energy Body in this Life Brings Immortality

The energy body serves as vehicle for consciousness,tapping on a higher source of energy and bringing this higher energy back into the physical body. In the physical body it can be transformed into a more usable energy.

1.Transfering the life-force energy or Chi, to the energy body will enable you to use the energy body to support the spirit body.

The Physical Body—is like a boat and its engine.
The Energy (Chi) Body—is the fuel, or steam (providing force.)
The Spirit Body—is the captain (who commands.)

2. The functions of the energy body are to transfer the essence of life (organs', glands', and senses' energies) consciously into the spirit body and to push the spirit body into the Mid-Plane.

Fusion I Meditation

Part One

Basic Practice of Fusion I

Formula 1 through 5

Chapters of Part One describe how to transform emotional energy into a useful energy, and in the process, how to achieve a balanced state of inner peace and harmony. Developing your awareness of the pearl of energy you create is your goal in practicing the basic steps of the Fusion I meditation.

Chapter 1

Formula 1: Forming the Four Pakuas, Blending Energy and Forming Pearl at the Center

A. Theory: Four Pakuas and the Cauldron

The eight sides that form a pakua represent the eight natural forces of the universe. These are the forces of (1) wind, (2) thunder, (3) mountains, (4) water, (5) the heavens, (6) lakes, rain, (7) earth, (8) fire. (Fig.1.1)


Li, South, Summer, Heart/ Small Intestine,
Fire Force, Love/ Hate, MiddleYin
Sun,Sou
Wind Fo
Strong Y
Kun,Southwest
h Force
nplete Yin
Chen
East
Spirit
Liver,Gall
Bladder
Thunder
and Wood
Force
Kindness/
Anger
Strong Yan
Tui
West
Autumn
Lungs/
Large
Intestine
Lake, Rain
Metallic
Force
Courage/
Sadness
Less Yin
Ken
Northe
Mountain
Lesser Yang
west
Heavenly Force
Complete Yang
North, Winter, Water
Kidneys/Bladder, Water

***Fig.1.1** (Later Heaven) Sequence of the Pakua*

1. Construction of the Pakua

A pakua may be perceived as an octagon formed from eight trigrams. However, to simplify the creation of a pakua for meditation, a simple web pattern is envisioned to form an image. This image consists of three eight-sided layers, with spokes connecting each layer, similar to the eight-sided, multi-layered cut of a normal diamond. The largest layer of the pakua is three inches (7.62 centimeters) in diameter. At the center is a Tai Chi (Yin/Yang) symbol that spirals to blend and transform the force. Behind the pakua, the diamond-shape of the image is realized further as all eight sides of the pakua create a funnel-like shape that converges at one central point.

The pakua, traced with the mind in meditation, is drawn in layers, beginning with the outer, three-inch octagon, then continuing with levels two and three. All are drawn in either a clockwise or counterclockwise direction. Then the eight spokes are created to connect the layers. These spokes combine at the Tai Chi symbol placed at the center of the pakua. After the shape is memorized well, it can be recreated simply by visualization. (Fig.1.2)

2. Location of the Four Pakuas

The four pakuas are located:

a. Front (or Navel) Pakua: Behind the navel, about one and a half inches inside.

b. Back Pakua: At the Door of Life, on the back opposite the navel between Lumbar 2 and 3, and about one and a half inches in.

c. Left Pakua: On the left side of the body, at the intersection of a mentally drawn line extending vertically downward from the left armpit, and a line drawn horizontally across the left side from the navel to the Door of Life. The pakua is about one and a half inches (3.8 centimeters) in from this intersection point.

d. Right Pakua: On the right side of the body, at the intersection of a visualized line drawn down from the right armpit,and a horizontal line from the navel to the Door of Life, about one and a half inches in.

Energy is brought into these pakuas, where it is then blended and transformed.



Fig. 1.2 *Simple Pakua for Beginning the Practice*

3. Location of the Cauldron (the Central Point of a Human Being—the Point of Control)

The cauldron isconsidered the center of the body. It is located in a space between the navel and the Door of Life, but is more toward the back of the body, in front of the kidneys. It is the place where prenatal force, as part of the Universal or Original Force, was formed. It is also the place where all of the five elemental forces combine and transform into a very refined energy.

a. The energy from the four pakuas is balanced and condensed at their Tai Chi centers, and these centers can glow with white or golden light.

b. The Tai Chi centers of the four pakuas spiral and blend this energy and direct it through the funnel-like backs of the pakuas into the cauldron. The center of the cauldron's three inch diameter is usually at a point level with the Door of Life, although the center can vary with each person as much as an inch and a half up or down. In men who are top-heavy, the center can be lower. Women who are bottom-heavy can have a higher center. It seems the thinner the person, the greater the chance the center point will be at the level of the Door of Life and the navel. Once it is found you will readily know it is your center of awareness.

c. The front and back pakuas function as a pair in spiraling, drawing, refining, and condensing the energy into the cauldron.

d. The two side pakuas constitute a second pair to spiral, draw, refine, and condense the energy into the cauldron.

e. At the cauldron, energies are mixed further, blended, and condensed, and the pearl is formed. (Fig.1.3)



Fig. 1.3 *Four Pakuas and Condensing Energy into a Pearl*

B. Practice of Formula 1

1. Assume the Position.

Sit up properly. Feel the feet touching the ground, the hands holding together, and the tongue touching the palate.

2. Practice the Inner Smile.

Practice the Inner Smile meditation to relax the mind and the body.

a. Smile down and feel the sunshine-like smiling energy collect in the eyes and Third Eye. Feel the outer corners of your eyelids and mouth uplift. Feel the smiling energy slowly flow down to the neck, thymus gland, and heart. Feel the heart open. Create a state of love, joy, and happiness in the heart.

b. Smile down to the organs and become aware of the virtues of each organ as you smile down: smile to the heart, and generate a sense of honor and respect, as you increase the feelings of love, joy, and happiness; smile to the lungs, and generate the feelings of courage and righteousness in the lungs; smile to the liver, and generate kindness in it; smile to the pancreas and spleen, and generate fairness and openness in those organs; smile to the kidneys, and generate gentleness in the kidneys. Feel the positive effect on each organ as you smile to it. Be aware of the positive emotions you are generating. (Fig.1.4)



Fig. 1.4 *Smile Down to the Organs*

c. Smile to the sexual organs. Smile down to the digestive system. Generate a creative energy. Feel the energy flow all the way down with the saliva as you swallow to your stomach, small intestine, and large intestine.

d. Return to the eyes, Smile to your pituitary and pineal glands. Smile into the left and right hemispheres to balance the brain, and then smile all the way down the spinal cord.

e. Return to the eyes again, and smile down the front, middle, and back line. Well-trained students can practice the Inner Smile at a fast pace.

3. Form the Front Pakua.

a. Turn your awareness and senses inward toward the navel. Concentrate on the navel, and bring all the above energies there. Feel their warmth. As you smile to the navel, blend and condense these energies into a ball of energy inside the navel area.

b. Look inwardly. Turn all the senses inward in preparation for constructing the pakua.

c. Beginning at a point one and a half inches (3.8 centimeters) inside and above the navel, draw with the mind the first line of the pakua. (Those who have visualization or kinesthetic problems can trace the lines of the pakua with a finger.)

d. Continue constructing all eight lines of the outer layer of the pakua.

e. Begin the second layer, constructing one line at a time.

f. Begin the third layer, drawing eight lines again.

g. Now, one at a time, draw the eight spokes from the outer layer to the inner layer. Picture the Tai Chi symbol in the middle, and as you draw each spoke, continue it into the Tai Chi. (See Fig.5)

h. Lastly, let the Tai Chi symbol spiral in either direction (but preferably clockwise) as it gradually blends and transforms the energy. Now the pakua can glow with white light. Some people will sense a stronger ability to concentrate at this time.

i. Rest and experience this glowing light and warmth.

4. Form the Back Pakua.

a. Beginning at a point about one and a half inches in and one and a half inches up from the Door of Life, mentally trace the first layer.

b. Construct the second layer.

c. Construct layer three.

d. Draw the eight spokes through the three layers toward the Tai Chi visualized at the center of the pakua.

e. Spiral the Tai Chi at the center, and sense the center glowing with white light.

f. Rest and experience the glowing light.

Notice that the back pakua is identical to the front pakua. Future references to forming the back pakua mention a simpler procedure of copying the front pakua to the back.

5. Spiral the Front and Back Pakua Energy to the Cauldron.

a. Divide your concentration between the front and back pakuas.

b. Spiral the two pakuas, especially their Tai Chi centers. Initially you can spiral without worrying about moving in a particular direction. Eventually, you can use your mind to train the spirals of each of the pakuas to spin in the direction you choose. With the inner eye direct the energy along the road or pathway of the spiral.

Become aware of the funnel-like shape of the backs of the pakuas. As you spiral feel the force being drawn in from the pakuas through their funnel-like backs toward the cauldron. Then concentrate more on the cauldron end of the spiral to help draw the energy into the cauldron. When you feel the energy at the cauldron, condense it and stop spiralling.

c. The condensed energy can glow with white light. Some people will simply feel a greater awareness of the navel area.

6. Construct the Right Side Pakua.

a. Concentrate on the point on the right side of the body, below the armpit, level with the navel, and approximately one and a half inches in. Trace the first layer of this pakua.

b. Draw the eight lines of the second layer.

c. Draw the eight lines of the third layer.

d. Draw the eight spokes into a Tai Chi symbol at the middle of the pakua. Spiral the symbol, and it should glow with light.

7. Construct the Left Side Pakua.

a. Concentrate on the point on the left side of the body, below the armpit, level with the navel and the Door of Life, and approximately one and a half inches in. Trace the first layer of this pakua.

b. Follow the directions in 6(b) through (d) above.

Notice that the right and left pakuas are identical to the front and back pakuas. Future references to forming the right and left pakuas mention a simpler procedure of copying the front and back pakuas to the right and left sides.

8.Spiral the Left and Right Pakua Energy into Cauldron.

a. Spiral to draw the glowing energy into the cauldron at the center of the body from the right and left side pakuas. You can direct the spirals clockwise, counterclockwise, or simply let the spirals move in any direction. Increase the spirals at the cauldron to draw within it the energy of the left and right pakuas. At the cauldron join this energy with the energy from the front and back pakuas. Although the cauldron may not necessarily be exactly at the center of the four points, it is considered the center of your body, or your center of being. The cauldron can glow brighter as more energy condenses and fuses together, or you may feel more centered and have stronger concentration.

b. Divide your concentration amongst the cauldron, the front and back pakuas, and the left and right side pakuas. (Fig.1.5)

c. Continue to spiral more energy to the cauldron.

9. Form a Pearl.

In a mild and relaxed manner, mentally concentrate to turn all the senses downward to the cauldron while continuing to spiral. There should be no tension, but rather a simple awareness of the energy that is condensing there. Form the pearl that is the highly condensed essence of your life-force energy. It is the essence of your organs, glands, senses, and mind that will absorb the impure energy of the organs and glands, purify it and return it to them as a higher form of energy. The pearl can control the organs and glands, and helps to establish the cauldron firmly.


Navel
Navel
L-2 and L-3
Left
Right
Door of Life
(L-2 and L-3)

Fig. 1.5 *Four Pakuas: Spiraling to Form the Pearl*

10. Anchor and Program the Pearl through Verbal Affirmations.

When you begin to feel the energy condensing at your center, relax a bit more and turn all your senses, attention, and awareness into the pearl. As you relax sufficiently you will feel your energy stabilizing and the pearl becoming stronger and clearer in your awareness. At the peak of these sensations of centeredness and stability, anchor-in and program this experience with the pearl. Use a verbal affirmation such as: I feel deeply centered, clear and calm; external forces do not move me. I am under my own control; I feel grounded and centered. My energy is stable and clear; I am emotionally balanced. Associating yourself with your center anchors your center to the pearl.

11. Move the Pearl into the Microcosmic Orbit.

As the pearl moves in the Microcosmic, you will feel three sources of energy. The Universal Force of the North Star (Polaris) and the Big Dipper constellation supply energy through your crown. Cosmic Particles fall to Earth, and this energy (Cosmic Particle Force) combines with the smiling energy supplied at the mideyebrow. The third source of energy is the Earth Force, and it is supplied at the perineum through the soles of the feet. Be aware of the combined energy from these three sources as you circulate the Microcosmic Orbit (sometimes more simply referred to as the Microcosmic, running up the Governor Channel (along the spine of the body), over the crown of the head, and down the Functional Channel (along the front, center of the body.)

Note: Drawing the energy into and running it through the pathway of the Microcosmic Orbit are crucial steps in Fusion of the Five Elements and all Universal Tao practices. It is also very helpful to your Fusion practice to know the Healing Love and Iron Shirt exercises. They will help you generate more energy and ease and strengthen the flow of energy.

a. Move the pearl down to the perineum, the Gate of Life and Death, by concentrating on, lightly contracting, and pulling up the perineum. Feel the downward pull on the pearl.

b. Sense the pearl as a bright star shining in the dark at the bottom of your body’s trunk. The pleasant, cool, blue energy of the Earth now enters through the perineum. Some will see the blue color while others will feel a gentle, soft, kind energy. This energy enhances the feeling of grounding. At this point you may anchor-in feelings of security, safety, and grounding by using a verbal affirmation. For example: I am safe, secure, and grounded in my daily life.

c. Pull up on the back part of the anus toward the sacrum and move the pearl from the perineum to the coccyx.

d. Tilt the sacrum to adjust the alignment of the coccyx with the Earth Force until you feel more centered and grounded. Feel the coccyx shine with light as the pearl reaches, and then passes through it. Again, use a verbal affirmation of the feelings of being centered and grounded.

e. Move the pearl to the Door of Life and feel it glow, enhancing the feeling of softness and gentleness.

f. Now move the pearl up to T-11 and feel it radiate with light.

g. Move the pearl to C-7. Let C-7 glow and burn off any burdens that may be felt. Now use an affirmation to program your feelings of lightness and well-being.

h. Move the pearl to the base of the skull (Jade Pillow). Let this point glow with bright light.

i. Move the pearl to the crown, and fill the crown with light. Feel the warmth of the Universal Force of the North Star and the Big Dipper as that energy now enters through the crown. If you have the capacity to see colors, the color of the North Star is purple, while the Big Dipper has a red light in its center. Feel the loving, strong force.

j. Continue to be aware of the pathway of the Microcosmic as you move the pearl down to the Third Eye point at mideyebrow. Feel the gentle, smiling energy combine with the Cosmic Particle Force as it is drawn in through the mideyebrow. If you can visualize color, see this force as golden. Feel its firm, strong, determined force.

k. Feel the mideyebrow point glow with light, and feel a sense of purpose. Use another verbal affirmation to program the pearl with your sense of purpose and vision.

l. Move the pearl down to the throat, and burn off any negative energy you may find.

m. Move the pearl to the heart and feel love, joy, and happiness. The heart is an excellent point to use a verbal affirmation expressing greater love and joy in your life.

n. Move the pearl to the solar plexus point, and then down to the navel.

o. Beginners may lose the pearl by losing their concentration. If your pearl is lost or diminishes at any time during the Fusion practice, start over and form a new pearl. Once again become aware of the four pakuas, and condense the energy into a pearl. At first, forming a new pearl will take time, but as your practice continues, you will build up larger amounts of residual energy. The more energy you have readily available, the easier and faster it is to form a pearl. Bring the new pearl to the perineum, and circle it in the Microcosmic. Be very aware of the pearl as it moves.

p. Turn a portion of your consciousness to the four pakuas as the pearl moves through the Orbit. Feel the energy flow through the spirals to the cauldron at the center of the pakuas and continually enhance the pearl.

q. Now circulate the pearl in the Microcosmic a little faster. Be aware of the pathway the pearl follows. (Fig. 1.6 (a))

r. Be aware of the Universal Force, the North Star with purple light, and the Big Dipper with red light above your head, the Cosmic. Particle Force in front of you, and the Earth Force under your feet. Feel these energies as they are supplied to you. (Fig.1.6 (b))

s. This is the time to balance the energy that you feel flowing through the Microcosmic. If you feel the flowing energy is too warm, draw in more Earth energy through the perineum. If you feel that the energy is too cool, draw in more Universal energy through the crown. If you feel you are losing concentration, draw in more of the fallen Cosmic Particle energy through the mideyebrow.

12. Collect the Energy.

Bring the energy to the navel, hold the energy here for a while, and bring the energy behind the navel to the cauldron. Feel its warmth, and then collect the energy at the cauldron.

13. Finish with Chi Massage.

End the exercise with Chi Massage. Rub the hands together, and then use the warmed hands to rub the face, throat, etc. (You can review Chi Massage in the Universal Tao book, *Chi Self-Massage: Taoist Way of Rejuvenation.*)


Crown
Pituitary Gland
Cranial Pump
Ta Chui
Hsuan Chi (Throat)
Gia Pe
Shan Chung
Chi Chung (T-11)
Chung Wan
Navel
Ming Men (Door of Life)
Male: Sperm Palace
Female: Ovarian Palace
Chang-Chang (coccyx)
Heding
Wei Chung
Hui Yin (Perineum)
Yung Chuan (K-1)

Fig. 1.6 (a) *Pathway of the Microcosmic Orbit*



Fig. 1.6 (b) *Microcosmic Orbit-Universal,Earth,and Human Forces*

c. Purpose of Centering Awareness in the Pearl

The immediate, practical use of the pearl in daily life is to help center your awareness so that your environment does not throw you out of balance. The deeper purpose of mastering the first formula is to lay an unshakable foundation for achieving oneness with the Universal Force.

To center awareness in the pearl is to find the center, or control point, of your soul. The shining pearl, as the essence of your soul, is always in touch with the source of Universal Force within yourself. Centering your awareness in the pearl places you in the position of mastery of your inner spiritual life as well as mastery of the outer Earth and Cosmic Forces that contribute to your daily life.

As you more frequently practice the Fusion meditation and strengthen your ability to center your awareness in your pearl, you will discover that you can tune in to your higher energies during your spare moments each day. You will find your intuitive mind growing sharper and clearer, more creative ideas will pop up in your work, and your capacity to love your family and friends will increase dramatically.

Negative patterns in your life that mindlessly disperse your life energy, such as daydreaming, the distraction of television, or negative emotional ruminations, can be defeated. The deep feelings of longing, loss, jealousy, or hostility that emerge from the negative patterns can be overcome.

As you use your idle moments throughout the day to engage in the Fusion practice, your awareness maintains the presence of your pearl. Your soul essence is busy giving birth to creative thoughts, realistic goals, and spontaneous feelings appropriate to the immediate moment. At the same time negative input from your vital organs or from your environment dissolves in the center cauldron and is greeted with fresh, strong energy from the Universe. Your life will begin to overflow with radiance and a surplus of energy that can become joy, kindness, creativity, and love.

It is wise to keep a steady contact with the Universal Force by regularly calling upon your pearl/soul essence. If you remain continuously aware of the pearl in your daily life, your connection to the Tao will become more powerful, making your life happy, harmonious, and effortless.

Chapter 2

Formula 2: Balancing the Organ Energy to Experience Inner Peace and Harmony

A. Theory: Collection Points for Each Organ

Each organ (and its secondary organ, below in parentheses) has a collection point for its particular quality of energy. Keep in mind the organs' correspondences to the five elements and to the seasons of the Universal and Earth Forces.

1. Kidneys' (Bladder's) Collection Point

a. The kidneys (and bladder's) collection point is at the perineum.

b. A sphere approximately three inches (7.62 centimeters) in diameter is created at the perineum which acts as a container for the kidneys' energy.

c. Kidneys' energy is cold/wet in quality. It is associated with the Winter season, the water element, and a deep blue color.

2. Heart/Thymus (Small Intestine's) Collection Point

a. The heart/thymus (and small intestine's) collection point is located between the nipples (in men), or approximately one inch up from the bottom tip of the sternum (in women).

b. A three-inch diameter sphere is formed there to collect heart and thymus energy.

c. The heart's energy is hot, and its season is Summer. Its element is fire, and its color is a bright red.

3. Liver (Gall Bladder's) Collection Point

a. The liver (and gall bladder's) collection point is located on the right side just below the rib cage and level with the navel. It is at the point of intersection of a line mentally drawn vertically down from the nipple and a line extending horizontally across to the right side from the navel.

b. A three-inch diameter sphere is formed at this spot to collect the liver's energy.

c. The liver's energy is warm and moist in quality. It is associated with the Spring season. Its element is wood, and its color is bright green.

4. Lungs' (Large Intestine's) Collection Point

a. The lungs (and large intestine's) collection point is located on the left side just below the rib cage. It is level with the navel at the intersection of a line mentally drawn down from the nipple and a line extending across to the left side from the navel.

b. A three-inch diameter sphere is formed at this spot to collect the lungs' energy.

c. The lungs' energy is cool and dry in quality. It is associated with the Fall season, the element metal, and a radiant white color.

5. Spleen/Pancreas (Stomach's) Collection Point

a. The spleen/pancreas (and stomach's) collection point is directly behind the navel (at the center of the front pakua.)

b. A three-inch diameter sphere is formed at this spot to collect the spleen's energy.

c. The energy of the spleen is mild, and its season is Indian Summer. Its element is earth, and its color is a brilliant golden yellow.

B. Procedure for Balancing the Organ Energy

To blend the organ energy, you first form the kidneys' and heart's collection points. Then you blend the kidneys' (cold) energy with the heart's (hot) energy at the front pakua. Next you form the liver's and lungs' collection points, and then add and blend the liver's (warm, moist) and lungs' (cool, dry) energy at the front pakua.

Finally, you add the spleen's (mild) energy gathered into its collection point located at the center of the front pakua.

C. Practice of Formula 2

1. Begin with the Inner Smile Meditation.

As you proceed with each step and smile to each organ, concentrate on the positive emotion associated with the organ. Sit up properly, hands together, and stick the tongue up to the roof the mouth. Smile down.

2. Form the Front Pakua.

Form the front pakua as described in Formula I, and feel the pakua glow with light.

3. Balance the Energies of the Kidneys and Heart.

a. Form the Kidneys' Collection Point.

(1) Be aware of the kidneys.

(2) Do the Kidneys' Sound: ***Choooooo*** (as when blowing out a candle). (You can review the Six Healing Sounds in the Universal Tao book, *Taoist Ways to Transform Stress into vitality.*) Practice a few times until you can feel the kidneys.

(3) Using the Packing Process Breathing technique, slightly contract the left and right sides of the anus to squeeze the kidneys. Use the power of the mind rather than tension on the muscles to do so. Then release the contraction to sharpen your awareness. (To review the Packing Process Breathing technique, see the Universal Tao book, *Iron Shirt Chi Kung I.*)

(4) Form a sphere at the perineum, the kidneys' collection point, by inhaling, pulling up the perineum, and pushing the lower abdomen down to the perineum.

(5) Exhale and relax. Mentally perceive the formation of a sphere and let it glow with a blue color.

(6) Spiral the energy in both kidneys and in their collection point in either direction. Increase your awareness of the collection point and intensify the spiral there until you a feel a force drawing the kidneys' (cold) energy into it. (Fig.2.1)

b. Form the Heart's Collection Point.

(1) Be aware of the heart and the thymus gland.

(2) Do the Heart's Sound: ***Hawwwwww.***

(3) Inhale and gently pull up the anus toward the heart, continuing

Notes: Use the power of the mind more than muscle power to gather the energy.


1. Become aware of the kidneys.
2. Do the kidneys' Sound (***Choooooo***) subvocally.
5. Relax and draw the cold energy to the collection point from the kidneys.
4. Pull up the perineum and push the energy ball out. Form the kidneys' collection point.
Kidneys' Collection Point
Right Side
Left Side
3. Pull up the left and right sides of the anus. Send the energy to the kidneys.
Anus.

Fig. 2.1 *Forming the Collection Point to gather Kidneys' Energy.*

to pull up until the heart is reached. Then, using the power of the mind, gently squeeze or contract the heart area. Do not use too much physical force; it is better to use a gentle muscle contraction and the power of the mind.

(4) Mentally perceive the formation of the sphere that is the heart's collection point. Let it glow with a red color.

(5) Spiral the energy at the heart toward the heart's collection point. Intensify the spiral at the heart's collection point until the force of the spiral is strong enough to draw the hot energy of the heart and thymus into it.

4. Spiral and Draw the Heart's and Kidneys' Energies to the Front Pakua.

a. Divide your attention between the kidneys' and heart's collection points.

b. Feel the hot and cold energy.

c. Also be aware of the front pakua. Spiral the heart's and kidneys' collection points and spiral the front pakua. Increase the spiraling force in the front pakua by using the eyes and the mind. Physically creating a slight circling body movement at the same time also will help increase the spiraling force. (Fig.2.2) Spiral until enough force is created to pull the cold (blue) energy (of the kidneys) and hot (red) energy (of the heart) into the front pakua. On each breath inhale and draw up the cold, blue kidneys' energy to the pakua. Then exhale, and draw down the hot, red heart's energy. Feel the energy blend. Moderate the temperature so that it is not too hot or cold. (Fig.2.3)

5. Balance the Energies of the Lungs and Liver.

a. Form the Liver's Collection Point.

(1) Be aware of the liver.

(2) Do the Liver's Sound: ***Shhhhhhh.***

(3) Inhale, and contract the right side of the anus to the liver. then contract the liver.

(4) Form the liver's collection point by inhaling, pulling up the right side of the anus,and pushing down on the right side of your body under the rip cage. Contract the muscles in this area.

(5) Relax, and mentally perceive the formation of a green colored sphere that is the liver's collection point.

(6) Spiral and draw the moist, warm liver energy into its collection point. (Fig.2.4)



Fig. 2.2 *Use the eyes,mind, and body to create a spiraling motion that will draw the energy into the spiral. Spiral until a pearl forms at its center. It was a spiral of energy that originally formed the Universe.*


1.Become
aware of the
heart.
2. Do the
Heart's
Sound
(***Hawwwwww***)
subvocally.
4.Pull the
heart and
thymus's
energy into
the heart's
collection
point.
6. Pull the
heart energy
into the front
pakua. Use
your mind
and eye to
blend the
hot
and cold
energies.
5. Pull the
kidneys'
energy
from the
perineum
into the front
pakua.
3. Pull up
the anus
toward the
heart and
form the
heart's
collection
point.

Fig. 2.3 *Form the Heart's Collection Point. Blend the Heart's Energy with Kidneys' Energy in the Pakua.*


1.Become aware of the liver.
2. Do the Liver's Sound ***(Shhhhhh)***
4. Form the liver's collection point by pulling up on the right side, under the ribs, and forming a green sphere. Gather the liver's energy.
3. Pull up the right side of the anus toward the liver.
Right Side.
The Anus.

Fig. 2.4 *Forming the Liver's Collection Point to Gather the Liver's Energy.*

b. Form the Lungs' Collection Point.

(1) Be aware of the lungs.

(2) Do the Lungs' Sound: ***Sssssss.***

(3) Inhale, pull up the left and right anus to the lungs under the rib cage. Contract the lungs.

(4) Form the lungs' collection point by inhaling again, pulling up the anus to the level of the navel, and mentally drawing a line down from the left nipple. Feel an expansion in this area.

(5) Exhale, relax, and mentally perceive the formation of a metallic white, three-inch sphere under the left rib cage that is the lungs' collection point.

(6) Spiral and draw the dry, cool lungs' energy to its collection point. (Fig 2.5)


1.Become aware of the Lungs.
2. Do the Lungs' Sound (Sssssss) subvocally.
4. Form the lungs' collection point by pulling up on the left side and forming a white sphere. Gather the lungs' energy.
3. Pull up the right and left sides of the anus to the lungs.
Anus

Fig. 2.5 *Forming the Lungs' Collection Point to Gather Lungs' Energy.*

6. Spiral and Draw Liver's and Lungs' Energies to the Front Pakua.

Divide your attention between the liver's and lungs' collection points and spiral them both. Distinguish the warm, moist energy of the liver and the dry, cool energy of the lungs. Be aware of the front pakua. Spiral and draw the liver's and lung's energy into this pakua. Blend the energies so that they are not too warm and moist, or too cool and dry. (Fig. 2.6)


Use your mind and eyes to draw the liver's energy into pakua.
Use your mind and eyes to draw lungs' energy into the pakua.

Fig. 2.6 *Blending the Liver's and Lungs' Energies the Front Pakua.*

7. Pull the Spleen's Energy into the Front Pakua.

a. Be aware of the spleen on the left side, slightly toward the back.
b. Do the Spleen's Sound:***Whoooooo*** (subvocally, but felt in the vocal cords).

c. Inhale and pull up the left side of the anus toward the spleen. Use your mind to lightly squeeze the muscles on your back, and feel the spleen. Exhale, relax, and heighten your awareness of the spleen. Form the spleen's collection point which is at the center of the front pakua itself.

d. Divide your attention between the spleen and front pakua. Spiral and draw the spleen's mild energy into the pakua. Visualize the color yellow at the pakua. (Fig.2.7)


Spleen
The collection point of the spleen's energy is the center of the front pakua.

***Fig. 2.7** Gathering the Spleen's Energy Directly into the Pakua.*

8. Form the Back Pakua and Blend the Energy from the Back Collection Points.

Form or copy the back pakua one and a half inches in from the Door of Life as described in Chapter1. When you have done so and definitely can perceive the back pakua, spiral and collect theenergies from the following locations. (Note that the location of the collection points you will create now will not be the same as the designated organ collection points described above. Rather they are located near the organ collection points, and their function is to draw in any remaining energies that may be present in the areas of the nearby organs. The actual source of these energies may be unclear.)

a. Make a sphere at the sacrum, and collect the cold kidneys' energy.

b. Make a sphere behind the heart between T-5 and T 6. Spiral and collect the heart's hot energy.

c. Spiral and blend the hot and cold energies that you have gathered from these spheres at the back pakua.

d. To the right rear of the back pakua make a sphere. Spiral and collect the liver's warm, moist energy.

e. To the left rear of the back pakua, make a sphere. Spiral and collect the lungs' dry, cool energy.

f. Spiral and blend the energies of the right and left spheres into the back pakua. (Fig.2.8)


Hot Energy from the Back of the Heart.
Dry, Cool Energy from the Back of the Lung.
Warm Energy from the Back of the Liver.
Cold Energy from the Back of the Kidneys.

Fig. 2.8 *Back Pakua Collection Points.*

9. Draw the Energies from the Front and Back Pakuas into the Cauldron.

Spiral, draw, and condense the energies from the front and back pakuas into the cauldron. Blend them together.

10. Form the Right Side Pakua and Blend the Energies from the Right Side Collection Points.

Form the right side pakua. Spiral and draw energy from the following locations:

a. Form a sphere at the right hip at the same level as the perineum. Spiral and draw any residual cold energy into the sphere.

b. Round the scapula to open the armpit, and create a sphere at the right armpit to collect residual hot energy.

c. Spiral and blend the hot and cold energies in the right side pakua. d. Form a sphere toward the front of the right pakua. Spiral and collect residual warm, moist energy.

e. Form a sphere toward the back of the right pakua, and collect residual cool, dry energy.

f. Spiral and blend the warm, moist and cool, dry energies in the right side pakua. (Figure 2.9)

11. Form the Left Side Pakua and Blend the Energies from the Left Side Collection Points.

Form the left side pakua and draw energy from the following locations:

a. Form spheres, and collect the energies at the left hip and armpit as above. Spiral and blend the hot and cold energies in the left pakua.

b. Form spheres to the front and back of the left pakua, as above. Spiral and collect mild energy at the front sphere. Spiral and collect cool, dry energy at the back sphere. Spiral and blend the mild and cool, dry energies in the left pakua. (Fig 2.10)

12. Draw the Energies from the Right and Left Pakuas Into the Cauldron.

Pull the energies now in the right and left side pakuas into the cauldron. Spiral and blend them together with the energies already drawn there from the front and back pakuas.


Hot Energy
Cool and Dry Energy
Warm, Moist Energy
Cold Energy

Fig. 2.9 *Right Side Pakua and its Collection Points*


Hot Energy
Warm, Moist Energy
Cool and Dry Energy
Cold Energy

Fig. 2.10 *Left Side Pakua and its Collection Points*

13. Condense the Energies into a Refined Pearl.

Now condense all the energies that have been pulled from the front, back, and side pakuas into a pearl. This pearl, created from the essence of your organs and your whole body, is very refined and not scattered. It may be perceived as a point of light or condensed energy. (Fig.2.11)


Pearl, Your Essence
Navel
Navel
Left
L-2 and L-3
ght
Door of Life
(L-2 and L-3)

Fig. 2.11 *Four Pakuas and their Collection Points*

14. Anchor the Feelings of Peace and Harmony to the Pearl.

At the height of feeling centered, at peace, and in inner harmony, anchor these feelings to the pearl by giving yourself a strong affirmation.

15. Move the Pearl into the Microcosmic Orbit.

Send the pearl down to the perineum, and circulate it in the Microcosmic. Be aware of the Universal, Cosmic Particle, and Earth Forces as they are drawn to the pearl.

16. Collect the Energy and Practice Chi Massage.

Circulate the energy to the navel, and spiral it at the navel nine times (men, clockwise; women, counterclockwise). Then reverse it six times. Rub your hands together, and practice Chi Massage. If you plan to continue without stopping at this point, you can spiral the energy at the navel and continue to the next chapter.

Chapter 3

Formula 3: Connecting Senses with Organs; Self-Control of Senses; Sealing the Openings; Overcoming Temptations

A.Theory

As a parent to a child, each of your senses relates to a specific organ. If, like undisciplined children, the organs expel negative energy, they need to be controlled or given balance and harmony by the senses, their parents. If either the senses or the organs are weak or sick, greater amounts of negative emotions will be created since there will be no discipline. By recognizing the parent/child relationships and strengthening them, you will be able to increase your energy.

1. Ears—Kidneys

The ears are the openings of the kidneys. By listening to and increasing your awareness of the kidneys, the sense of hearing is drawn within where it will eventually be controlled. You will eventually feel internal balance, peace, and harmony since the ears will enable you to hear a heavenly music that is very unlike earthly music. (Fig. 3.1)

2. Tongue—Heart

The tongue is the opening of the heart. By connecting the tongue with the heart, the speech center is drawn within, and the temptation of senseless speech can be controlled. The tongue and the heart will feel at peace. (Fig.3.2)



Fig. 3.1 *Connect the Ears with the Kidneys.*



Fig. 3.2 *Connect the Tongue with the Heart.*

3. Eyes—Liver

The eyes are the openings of the liver. By looking into the liver, the sense of sight is drawn within, and visual temptations can be controlled. (Fig. 3.3)

4. Nose—Lungs

The nose is the opening of the lungs. By connecting the nose with the lungs, the sense of smell is drawn within, and the temptations of scents can be controlled. (Fig.3.4)

5. Mouth—Spleen

The mouth is the opening of the spleen. By connecting the mouth with the spleen, the sense of taste is drawn within, and the temptations of appetite can be controlled. (Fig.3.5)



Fig. 3.3 *Connect the Eyes with the Liver.*



Fig. 3.4 *Conect the Nose with the Lungs.*



Fig. 3.5 *Conect the Mouth with the Spleen.*

B. Procedure of Connecting the Senses with the Organs

You will connect each sense with its corresponding organ by connecting them in pairs. (Figure 3.6)


Ears-Kidneys
Eyes-Liver
Mouth-Spleen
Tongue-Heart
Nose-Lungs

Fig. 3.6 *Connections between the Senses and the Organs*

1. The ears connect to the kidneys (cold energy) and the tongue to the heart (hot energy).

2. The eyes connect to the liver (warm/moist energy) and the nose to the lungs (cool/dry energy).

3. The mouth connects to the spleen (mild energy) and the front pakua.

C. Practice of Formula 3

1. Assume the Position.

Sit up properly, hold the hands together, and press the tongue to the palate.

2. Practice the Inner Smile.

Smile down. Feel the energy flow down through the face to the organs. Feel the positive emotions in each organ. Smile to the navel, and form the front pakua.

3. Massage the Senses and the Organs.

You can massage the senses by practicing the Chi Self-Massage exercise on them while massaging and exercising the organs.

4. Concentrate on the Ears and Kidneys.

a. Concentrate on the ears by spiraling the energy there. Listen, turn your awareness inwardly to the kidneys, and direct the spiral you have created at the ears to the kidneys. With this connection draw the essence of the ears to the kidneys by emphasizing the spiral at the kidneys, thereby making the energy at the kidneys stronger. Then collect at the kidneys the hearing energy of the ears and the cold energy that is the kidneys' essence.

b. Create a sphere at the perineum (the kidneys' collection point), and spiral at the perineum to draw and collect the cold energy that is the kidneys' essence and the hearing energy that is the ears' essence into this sphere. (Fig.3.7)

5. Concentrate on the Tongue and Heart.

a. Concentrate on your tongue. Move the tongue around to generate saliva and massage the heart. Spiral the energy at the tongue. Swallow the saliva you have created, and spiral the tongue's essence toward the heart. With this connection turn your awareness



Fig. 3.7 *Spiral and Collect the Ears and Kidneys' Energy.*



Fig. 3.8 *Spiral and Collect the Tongue and Heart's Energy.*

toward the heart. Emphasize the spiral at the heart, and collect at the heart the tasting energy of the tongue and the hot energy that is the essence of the heart.

b. Make a sphere at the heart's collection point, and create a strong spiral there. Draw in and collect the hot energy that is the heart's essence and the tasting energy that is the tongue's essence. (Fig.3.8)

6. Spiral and Blend the Essence Energies In the Front Pakua.

Spiral from the two collection points to the front pakua, and blend the kidneys' and heart's energies. Feel the hot and cold essence energies blend together. Notice the senses being pulled within.

7. Concentrate on the Eyes and Liver.

a. Concentrate on the eyes. Move the eyes around, and massage the eyes and liver. Look inwardly to the liver, and make a connection between your eyes and your liver by spiraling between the eyes and the liver. Create a stronger spiral at the liver, and let it draw in the seeing energy of the eyes. Collect in the liver the moist, warm energy that is the liver's essence.

b. Make a sphere at the collection point below the liver. Spiral and collect the blended warm/moist energy of the liver's essence and the seeing essence of the eyes into the collection point. (Fig.3.9)

8. Concentrate on the Nose and Lungs.

a. Focus your attention on the nose. Inhale and exhale, and massage the nose and lungs. Inhale to the lungs, and feel the connection between the lungs and nose by spiraling the energy between them. Spiral and collect the dry/cool energy of the lungs and the smelling energy of the nose.

b. Make a sphere at the collection point below the left lung. Spiral and collect the dry/cool energy that is the lungs' essence and the smelling essence of the nose into the collection point. (Fig.3.10)



Fig. 3.9 *Spiral and Collect the Eyes and Liver's Energy.*



Fig. 3.10 *Spiral and Collect the Nose and Lungs' Energy.*

9. Blend the Essence Energies of the Eyes/Liver and Nose/Lungs in the Front Pakua.

Concentrate on the front pakua. Spiral and blend the eyes/liver's and nose/lungs' energies from their collection points. As you spiral feel their moist/warm and dry/cold energy blend together at the front pakua. Feel the senses becoming increasingly focused.

10. Concentrate on the Mouth and Spleen.

Concentrate on your mouth and establish a connection with the spleen by spiraling between them. Collect the mild energy that is the essence of the spleen and the mouth in the front pakua. The senses should feel secure as the energies blend. (Figure 3.11)



Fig. 3.11 *Spiral and Collect the Mouth and Spleen's Energy.*

11. Form the Back, Right, and Left Pakuas and Draw their Collected Energies Into the Cauldron.

Be aware of the back pakua, its collection points, and the energy that has been gathered. Spiral the front and back pakuas to draw into, and combine their collected energies in, the cauldron. Be aware of the left pakua and its collection points. Similarly, be aware of the right pakua and its collection points. Spiral the left and right pakuas to draw into, and combine their collected energies in, the cauldron. (Figure 3.12)



Fig. 3.12 *Draw and combine the energies of all the senses and organs in the cauldron.*

12. Form a Pearl.

Spiral and blend all the condensed energies in the cauldron to form a pearl.

13. Affirm your Self-Control by Anchoring and Programming the Pearl with Verbal Affirmations.

Once you feel that the senses and organs are connecting and are all moving into one place—the cauldron—you will feel a sense of control. You will feel as though everything is under one roof or under one center of control. This feeling can make you stronger and increase your power to overcome temptations because your senses and organs will be stronger. At the height of the feeling of self-control, program yourself by anchoring this feeling into the pearl so that you can recall the feeling at any time. I am calm, clear, at peace, centered, in physical and emotional balance, and under self-control.

14. Move the Pearl to the Perineum.

Move the pearl to the perineum and circulate the energy in the Microcosmic. Keep the senses and your awareness focused inward. As the pearl circulates in the Microcosmic, sense the three sources of energy supplied: the Universal, the Cosmic Particle, and the Earth Forces.

15. Collect the Energy and Practice Chi Massage.

Bring the pearl of energy to the cauldron, and end with Chi Massage.

Chapter 4

Formula 4: Transforming the Negative Emotions of Each Organ into Useful Energy

A. Theory: Relationships between Organs and Emotions

Taoists reason that negative emotions can be transformed to utilize their life-force energy. Therefore, to expel or suppress unwanted, negative emotions is to expel or suppress life-force. Rather than suppress negative emotions in the Taoist system, you benefit more by experiencing them. (Fig.4.1) This means you permit them to emerge, but do not let them run wild or trigger other negative emotions. Instead, put yourself in control of them so that you may transform them not only into useful life-force energy, but also into the higher consciousness that is your spiritual energy.

When connecting the senses with the organs in Chapter 3, you may have noticed your emotions beginning to emerge. You can control them. Review Table 1 in this chapter to note the negative emotions you will want to transform. After you have cleared the negative emotions from the organs, study Table 2 also within this chapter. Table 2 is more detailed, noting the negative and positive aspects of each modality—shape, color, smell, temperature, etc. You may be stronger in one representational system than another depending on your visual, auditory, and kinesthetic perceptions. You should be able to relate to at least one of the modalities.

Some people have repressed their emotions and react strongly to this practice as their emotions surface. If you are one of these people, spend more time practicing the Healing Sounds and the Inner Smile. Work with healing the organs before attempting to transform the deeply buried emotions within them.

As you transform the negative emotions of each organ into useful energy, use the Counteracting or Controlling Cycles to help balance the energy. (Fig.4.2)


Cruelty,
Hastiness,
Impatience in
the Heart
Sadness,
Grief in
the Lungs
Worry
or
Anxiety
in the
Spleen
Anger in
the Liver
Fear in the
Kidneys

Fig. 4.1 *Negative Emotions and the Organs*

B. Practice of Formula 4

1. Smile Down.

Smile down, and generate the qualities of loving energy in each organ.

2. Form the Front Pakua.

As in the previous Chapters, create the front pakua.

Five Element Organ Correspondences

	Wood	Fire	Earth	Metal	Water
Yin Organs	Liver	Heart	Spleen	Lungs	Kidneys
Yang Organs	Gall Bladder	Small Intestine	Stomach, Pancreas	Large Intestine	Bladder
Openings	Eyes	Tongue	Mouth, Lips	Nose	Ears
Positive Emotions	Kindness	Love, Joy	Fairness, Openness	Righteous, Courage	Gentle
Negative Emotions	Anger	Hate, Impatience	Worry, Anxiety	Sadness, Depression	Fear, Stress
Psycho-Logical Qualities	Control, Decisiveness	Warmth, Vitality, Excitement	Ability to Integrate, Stabilize, Feel Centered and Balanced	Strength, Substantiality	Ambition, Willpower

Table 1


Metal
Lungs
Sadness
Depression
Water
Kidneys
Fear
Earth
Spleech
Stomach
Worry
Wood
Liver
Anger
Fire
Heart
Cruelty
Hastiness

Fig. 4.2 *Counteracting or Controlling Cycle*

3. Be aware of Fear in the Kidneys.

Turn your consciousness toward the ears, and listen to the kidneys. Become aware of fear or any sensation that you do not like as it manifests in the form of a sound, taste, color, shape, or feeling. The energy may be chilling and cold, cloudy blue, contracting, or it may be emitting awkward shapes. Spiral and breathe the fear and any other emotion you do not like out of the kidneys, and collect it at the kidneys' collection point. (Fig. 4.3)



Fig. 4.3 *Collecting Fear in the Kidneys' Collection Point*

4. Be Conscious of Impatience in the Heart.

Move the tongue, connect the tongue with the heart, and become conscious of impatience, hastiness, cruelty, or any sensation that you do not like deep within the heart. It may manifest as a feeling, shape, sound, or image. The feeling can be of energy rushing out, and you can see and feel something wrapping and pressing in a bad way into the heart. The negative feelings of the heart can be sensed as a very muddy, red color, or can be hot, unsteady, small, noisy, or acidic. Spiral and breathe these emotions out of the heart, and collect them at the heart's collection point. (Fig.4.4)



Fig. 4.4 *Collecting Cruelty, Hastiness,and Impatience in the Heart's Collection Point*

5. Spiral, Blend and Transform the Energy of the Heart and Kidneys at the Front Pakua.

Spiral and breathe the negative energies out from the heart's and kidneys' collection points to the front pakua. Spiral and blend them at the front pakua. The pure energy trapped in these negative feelings will be freed and released to the center of the pakua. Spiral the heart's and kidneys' energies until they become a bright, golden energy. This energy radiates love and gentleness from the center of the pakua and your being.

6. Perceive Anger in the Liver.

Move the eyes, connect the eyes with the liver, and be aware of anger or any sensation that you do not like deep within the liver. The anger energy can be sensed as a sharp-edged spear, hot, painful, red, cloudy, or pungent. It can be a destructive, expanding kind of energy. Spiral the anger and any other energy you do not like from the liver, and move it out to the liver's collection point. (Fig.4.5)



Fig. 4.5 *Collecting Anger in the Liver's Collection Point*

7. Be Aware of Sadness and Depression in the Lungs

Inhale and exhale. Then inhale again, and establish a connection between the nose and lungs. The negative energy of the lungs can take the form of sadness, grief, and depression, but can be represented by other sensations that you do not like. When you are sad, you can have a sense of being down, collapsed, deflated, and low in energy. Sadness or any negative energy in the lungs can be gray, cold, musty, or salty. Spiral and breathe out the sadness and any other energy you do not like from the lungs. Bring it to the lungs' collection point.(Fig.4.6)

8. Spiral, Blend, and Transform the Energy of the Liver and Lungs at the Front Pakua.

Spiral and breathe the negative emotional energies from the liver's and lungs' collection points to the front pakua. Spiral and blend them at the front pakua, using the power of the pakua to balance and neutralize the sadness and anger. Nurturing the kindness and courage will help to transform them into a golden light at the center of the pakua.



Fig. 4.6 *Collecting Sadness and Grief in the Lungs' Collection Point*

9. Be Conscious of Worry in the Spleen.

Connect the mouth with the spleen, and be aware of worry or any other emotion you do not like in the spleen. The negative energy of the spleen can be sensed as cloudy, sour, shaky, uncertain, and sticky. As a result, you might feel limited, small, and uneasy. Spiral and breathe the worry and any other energy you do not like out of the spleen. Bring it to the front pakua to blend it with the energy that is already there. (Fig.4.6)



Fig. 4.7 *Collecting Worry and Anxiety in the Spleen's Collection Point*

10. Spiral all remaining Negative Energy to the Front Pakua.

Return to all the organs and their collection points, and spiral and breathe to draw out any remaining negative energy. Blend and neutralize it with the energy in the front pakua.

If you feel you do not have enough energy to transfer the negative emotions, you can call upon another source of energy within you to help. Become aware of the love and joy in your heart. Bring these emotions into the pakua and they can help transform the negative energy.

Emotional Transformation Processes: Characteristics of Positive and Negative Emotions

This table demonstrates emotional characteristics as might be perceived by an individual and not elemental characteristics. These are personal experiences. One might feel differently according to his or her visual, auditory and kinesthetic perceptions.

Emotion		Righteous Courage		Gentleness
	Collapsed, Flattened Ball	Tall, Straight	Awkward Compressed	Round,Full, Expensive
Color	Grey	Bright White	Dark Grey, Cloudy	Bright Sky Blue
Smell	Musty	Pure, Fresh	Foul, Urine	Fresh
Temperature		Comfortable, Warm	Cold, Chilly	Cool, Comfortable
Sound	Low, No Force	Strong, Firm Resonant	High-pitched Shrill	Whisper, Pleasant to Ear
Feeling	No Energy, Exhausted	Uplifted	Tight, Closed In	Relaxed, High, Centered
Texture		Firm but Comfortable	Slippery	Velvety
Size	Deflated, Low	Expanding Upward		
Taste				
Direction				

Table 2

Modality	**Liver**		**Heart**		**Spleen**	
Emotion	Anger	Kindness	Impatience, Cruelty, Hate	Love,Honor, Respect	Worry	Fairness, Openness
Shape	Spear-like, Sharp	Round, Smooth	Moving, Spiny	Straight, Open	Irregular	Open, Wide, Big
Color	Red Cloudy	Soft Green	Orange, Muddy	Bright Red	Cloudy	Mellow Yellow
Smell	Pungent	Sweet, Fragrant	Sharp, Burnt	Aromatic Incense	Sour	Clean, Dry
Temperature	Hot, Explosive	Warm, Pleasant	Unsteady	Warm, Full	Humid	Warm, Mid-range
Sound	Flashing, Loud	Melodious	Noisy, Irregular	Stable, Steady, Solid	Shaky	Clear, Soft, in Tune
Feeling	Pain, Tough, Rough	Nurtured	Irritated	Stable, Protected	Uncertain	Balanced, Even
Texture	Rough	Soft	Cactus -like	Comfort Secure	Sticky	Smooth, Firm
Size	Expand Explode	Expand, Gently	Small, Pointed	Expanding	Out of Proportion	Big, Deep
Taste	Bitter	Sweet	Acetic	Satisfying	Sour	Smooth, Clean
Direction	Attacking, Out	Enfolding	Scattered	Open, Steady	Constrict	Horizontal

Table 3

11. Practice Inner Observation.

Turning the senses inwardly initiates the training process of inner observation. In developing the ability to focus inward—to smell, listen, taste, see, and hear the organs and their activities—and to observe your negative emotions without predetermined judgments, you have the opportunity to develop your true nature.

12. Clean Out the Negative Energy to make Room for Positive Energy.

In the same way that turning garbage into compost makes it useful, transformed negative energy also becomes useful. You are increasing your life-force rather than throwing it away. By making room for positive energy to grow, your life-force will continue to increase.

13. Allow Virtue Energy to grow in the Organs.

Growing virtue energy is an essential part of both the Fusion I and II practices. Gentleness can grow in the kidneys. Love, happiness, and joy can grow in the heart. Kindness can grow in the liver. Righteousness and courage can grow in the lungs. Fairness and openness can grow in the spleen.

Check the color of each organ as a reflection of its increasing virtue energy. The kidneys now might be a brilliant blue; the heart, a brilliant red; the lungs, a brilliant white: the liver, a brilliant green; and the spleen, a brilliant yellow. (See Table 2.)

Organs made stronger with the growth of virtue energy will gradually strengthen the senses. During the process you will develop a very· real sense of knowledge and true wisdom. Once you observe these qualities within yourself, you are prepared to observe and experience the outside world.

14. Transform the Negative Energy as the Most Powerful Act of Forgiveness.

Recall a time when you have had a conflict or argument with someone. Finally there came a time when you both sat down to talk things over and to try to understand each other. You said, “I forgive you,” and the other person also forgave. At that moment the feeling was as though a heavy load or burden was removed. You felt open, happy, and warm.

When you can transfer anger into kindness, you are performing the act of forgiveness. Forgiveness is one of the most important practices of the Taoist system. Feel the anger of others. Do not suppress it. Do not be afraid of it. Make friends with it. Understand it and draw its energy into your pakua. Spiral it with your other emotions and add more of your love energy. Transform the combined energies into life-force.

At the moment the energy transforms into life-force, you feel a sense of release, a sense of opening. Experience the feeling. Remember that it will help you to transform more energy easily.

15. Project Inner Virtue outwardly to increase Virtue Energy.

TheTaoist way emphasizes helping the world without anyone noticing. Once you have grown love, joy, kindness, and gentleness internally, it can be projected outwardly toward others. The more virtue energy you project outwardly, the more you grow inwardly. The more you give, the more you receive without ever asking for reward.

You can help sad and angry people with your good virtue. Extend your help to them daily and you will touch their hearts with love, joy, and kindness. You, in turn, will feel the Universal Force pouring out from the heavens. The New Testament of the Bible relates a narrative of Jesus regarding donations to the Temple. He told us not to let the left hand know what the right hand gives. It is only for the Heavenly Father to know.

As the organ virtue energy increases, it becomes useful energy for transferring your consciousness. Therefore, it becomes valuable for all eternity. The consciousness created and transferred by virtue energy can be thought of as money in a savings account, an account held by the Universe.

16. Practice External Observation and Develop the Art of Non-Attachment.

Another important Taoist discipline to realize at this time is the art of non-attachment to the material and social elements of your physical world. It is an important concept to embrace when observing the outside world because it prepares you for your destiny.

Observe the necessities of life—food, clothing, shelter—simply as vehicles to help you reach your goal. Try to walk through your home, for example, and determine what it is possible to live without. Would you feel deprived if suddenly all your material things were taken away? If you were abandoned by your loved ones, would you be able to carry on?

The fact is that when, through death, you finally leave this world, you cannot take anything with you. The spirit is all that survives.

17. Prepare the Body to Receive the Universal Force.

Clearing out negative emotions and blockages is important for another reason—to prepare the body and make room to receive the higher Universal Force and a higher consciousness. The Universal Force supplies useful energy for healing, additional life-force energy, spiritual work, and for working on new projects when additional energy is required to make decisions or to solve a crisis.

You might think of the process as “cleaning the house” to make it ready. This means you try to feel clean internally. The first step is to clean all the “rooms”; that is, to clear the negative energies from the organs. Next it is particularly important to “clean the bathroom.” This means to clear the intestines, especially the large intestine, since constipation is a serious prevention to the flow of energy. Consume a higher fiber diet, including fruits and vegetables, to keep the body clean.

A clean “house” makes you feel very good internally and externally. You feel as though you know yourself better. You are better able to determine your weak and strong points. The Fusion practices help you to replace automatically your weak points with stronger points. It also helps you to control the overly strong ones. When you feel this strength and control, you will feel clean inside. This feeling of cleanliness is very important because it opens you up to attract and receive the higher force.

After your Fusion practice, and before you go to sleep, feel the emptiness the clean feeling creates inside. At this time ask the Universe with a good heart and in a virtuous way for what you need to fill the emptiness. The Universe will fill your need. When you arise in the morning, get in touch with yourself and any problem you may have and you might find the answer has already arrived.



Fig. 4.7 *The brain is the computer; the organs are the software.*

18. Increase the Psychological Qualities of the Organs.

TheTaoists regard the organs as storage places for general information and data, while the brain uses this stored information and data for processing. You might consider this process to work much like the operation of a computer. The organs are the software, and the brain is the computer hardware. Without the software to feed information and data, the computer will not be able to exercise its function. (Fig. 4.7)

Once you recognize this connection you can understand the brain's function in strengthening and activating the advantageous psychological qualities of the organs, after they have been cleared of their negative energies.

Good psychological qualities associated with the organs are as follows:

a. The kidneys and bladder—ambition and willpower.

b. The heart and small intestine—warmth, vitality, and excitement.

c. The liver and gall bladder—control and decisiveness.

d. The lungs and large intestine—strength and substantiality.

e. The spleen and the stomach—ability to integrate, stabilize, and feel centered and balanced. (See Table 1.)

The lungs are associated with the metal element. A person influenced by anger, sadness, and depression, negative emotions of the lungs, can experience a weakened liver. The liver is associated with the metal element. A weakened liver will encourage anger and affect decision making. An extremely angry person will make wrong decisions. While a person who is sad and depressed can lose courage and a clear viewpoint. A hasty, impatient person, experiencing the negative emotions of the heart, can lose warmth and vitality.

By cleaning negative emotions from the organs and transforming them to good energy, you are able to experience the vitality of the organs' good psychological qualities. These good psychological qualities play a major role in our daily life, providing decision making capabilities, a sense of direction, and sound judgment.

The Taoists believe that clean organs, emptied of their negative energies, permit good sense and real knowledge to come forth. Otherwise you can harbor a false knowledge that confuses real knowledge and good.

When a Taoist says he feels fine, this means all his or her organs are in agreement, working together in a positive way and controlling all actions. They are free of domination by the mind.

19. Form the Back, Right, and Left Pakuas and draw their Collected Energies into the Cauldron.

Be aware of the back pakua, its collection points, and all the energies you have collected from the connected senses and organs. Spiral the front and back pakuas to draw into, and combine their collected energies in, the cauldron. Be aware of the left pakua, its collection points, and all of the energies gathered there. Similarly, be aware of the right pakua, its collection points, and all of the energies now present there. Spiral the left and right pakuas to draw into, and combine their collected energies in, the cauldron.

20. Form a Pearl.

Fuse together and condense the energies from all four pakuas in the cauldron, and form a pearl. With the addition of the organs' and purified emotions' energies, the pearl now glows a brilliant golden color.

21. Circulate the Pearl in the Microcosmic Orbit.

Bring the pearl down to the perineum. Circulate it in the Microcosmic. As the pearl moves through the Microcosmic, feel the Universal, Cosmic Particle and Earth Forces supplied to you. (Fig. 4.8)

22. Practice Chi Massage.

Collect the energy, and practice Chi Massage.



Fig. 4.8 *Once you have established the energies in all four pakuas and begin circulating the Microcosmic Orbit,simply be aware of the Earth Force, the Universal Force, and the Forces of the North Star and Big Dipper.*

Chapter 5

Formula 5: Creating the Pearl that forms the Energy Body

A. Procedure to create a more Advanced Pearl

Formula 5 incorporates Formulas 1 through 4 of Fusion I, and then continues to draw more energy into specific pakuas. The energies that have been brought to the front and back, and left and right pakuas are blended together. Then they are pulled into and condensed in the cauldron to create a more powerful pearl. The greatly refined and radiant energy of this pearl will be used to grow your soul or energy body.

B. Practice of Formula 5 to Create the Pearl

Smile down, and create the front pakua using what you have learned in Chapters 1 through 4.

1. Form the Front Pakua and Blend the Energy from the Front Collection Points.

Connect the senses to the organs, collect the energy in the organs' collection points, and blend the organs' energies and emotions in the front pakua. Begin with the kidneys' and heart's energies, then blend the liver's and lungs' energies, and follow with the spleen's energies.(Fig 5.1)

2. Form the Back, Right, and Left Pakuas and draw their Collected Energies into the Cauldron.

Be aware of the back pakua, its collection points, and all the energies you have collected from the connected senses and organs. Spiral the front and back pakuas to draw into, and combine their collected energies in, the cauldron. Be aware of the left pakua, its collection points, and all of the energies gathered there. Similarly, be aware of the right pakua, its collection points, and all of the energies now present there. Spiral the left and right pakuas to draw into, and combine their collected energies in, the cauldron.


Hot Heart and Thymus' Energy
Warm Liver's Energy
Dry, Cool Lungs' Energy
Cold Kidneys' Energy
Mild Spleen's Energy

Fig. 5.1 *Front Pakua Collection Points*

3. Condense the Energies into a Refined Pearl.

Fuse together and condense the energies from all four pakuas in the cauldron to form the purified pearl of a brilliant, golden color.

C. Working with the Pearl.

Practice with the pearl is very advanced procedure.For some, it may take a long time simply to create one. Do not rush--impatience will dissolve your pearl. Each of the following stages must be mastered before going on to the next. (Such mastery becomes especially important when working with the pearl above the crown in the Fusion II practice.)

1. Circulate the Pearl in the Microcosmic Orbit.

Bring the pearl down to the perineum. Circulate it in the Microcosmic Orbit. As the pearl moves through the Microcosmic, feel the Universal, Cosmic Particle, and Earth Forces as sources of the energy supplied to you. Build up the momentum of the pearl.

2. Activate the Cranial and Sacral Pumps to open the Crown.

a. Cranial Pump (the Palatine Processes of the Maxillae)

To activate the Cranial Pump, press the tip of the tongue against the lower teeth and the flat of the tongue against the palate. Clench the teeth, tilt the chin toward the neck to straighten the cervical vertebrae, pull the eyes in, turn the ears, nose, and tongue toward the back of the head and turn all the senses upward to the crown. Feel the pulsation of the activated Cranial Pump. (Fig.5.2) (If you are a beginner, it may be easier to feel the pulsation at the crown by touching the pulse at your wrist.)

b. Sacral Pump

Activate the Sacral Pump by inhaling, pulling up the perineum, then inhaling again, and pulling up the back of the anus toward the sacrum. Inhale more, and pull the pearl from the perineum to the sacrum, up to T-11, C-7, the base of the skull, and the crown. moment you might feel a strong sensation, like a shiny wave of light, called the lead light, emerge from the crown.

NOTE: If you suffer from heart disease or have difficulty breathing, hold your breath only as long as you feel comfortable.

c. Inhale, and swallow your saliva. This action will help you push the pearl upward toward the crown.

d. Feel the crown open.

e. Be aware of the crown and its opening. Swallow the saliva upward and feel a push up to the crown. Exhale forcefully toward the crown, and shoot the pearl out through the crown to approximately six inches (15.24 centimeters) above the head. When your practice is more advanced, you can move it higher.

Note**:** Use the power of the mind more than muscle power to activate the Cranial Pump.


Upper Teeth
Lower Teeth

2.Clench the teeth to activate the temporal bone.

3. Press the chin toward the back to activate the occipital bone.


Temporal Bone
Clench the teeth.
Occipital Bone
Press the chin back.

Fig. 5.2 *Activating the Cranial Pump*


4. Pull the
the eyes

Fig. 5.2 *(Cont'd.) Turn all the senses upward toward the crown.*


2. Inhale again and pull the pearl up to the crown.
Tilt the sacrum.
1. Activate the Sacral Pump by inhaling and by pulling up the anus to the coccyx and sacrum.

Fig. 5.3 *Activating the Sacral Pump*

3. Look for the Lead Light.

The lead light is the guiding light that can be felt through the crown. When in the advanced stages of practice you send the pearl out from the body to form the energy body, the light can be used by the energy body to communicate with the physical body. It can also be used as a compass to guide the energy body into the next world. (Fig.5.4)

4. Extend the Pearl above the Crown.

The senses now become the wireless control of the pearl. Begin by concentrating on moving the pearl up and down. With greater control, move it around in other directions.

5. Reactivate the Cranial Pump; Draw the Pearl Back into the Microcosmic Orbit of the Physical Body.

Inhale and reactivate the Cranial Pump. When the crown is open, inhale, and bring the pearl back into the Microcosmic Orbit. Collect the energy in the navel and bring it to the cauldron. Finish with Chi Massage.

6. Advanced Stage.

a. Controlling the Pearl above the Physical Body

Move the pearl up in increments of one foot (30.48 centimeters) at a time, and practice at each level until control is mastered. Ultimately you can bring it up to a level equal to the height of your body. At each level, first move the pearl up and down, then experiment with different directions: left and right, front and back. Then spiral it left and right, fast and slow, etc. Once you have reached a certain proficiency at moving the pearl at one level, continue to the next. (Fig.5.5)

7. Finish the Practice.

You can finish your practice now, or continue to the next exercise. If you decide to finish now, you can condense the pearl again, and activate the Cranial Pump. Inhale, pull the pearl in, and circulate it in the Microcosmic Orbit. Collect the energy in the navel, bring it to the cauldron, and finish with Chi Massage.



Fig 5.4 *The Lead Light*

D. Creating the Yin and Yang Bodies (the Soul Body or Energy Body and the Spirit Body) for Space Travel.

1. Energy Body is Born from the Original Force — Born Again.

The new Chi body that you will create in this Chapter is known as your energy or soul body, the body that will last forever. Most people are afraid of death, but need not be. The Taoist belief is that death is the spirit changing residence. Your physical body will return to the dust from which it came, but Chi, soul, and spirit come from the planets and stars and from the Original Force, the Wu Chi. In separating the soul and spirit from the physical body, you are practicing death and your return to the Wu Chi. In learning how to condense and transfer this energy, and send it back to the planets and stars and to the Original Force, you can be assured that your energy will continue as part of the universe.



Fig 5.5 *Controlling the Pearl above the Physical Body*

2. Energy Body is like a Newborn Infant.

During the course of a few thousand years of developing the energy and spirit bodies, the Taoists realized that the process could not be rushed. Developing the soul and spirit bodies is similar to taking care of a newborn infant. The infant needs to be nourished and cared for. As he or she grows up, the child needs to be educated and trained to the fullest potential. The child also needs to be equipped with the power to protect himself or herself.

The early, undeveloped stage in the creation of the energy body was regarded by the Taoists as the Yin body or infant stage.
In this infant stage,you do not let your energy body roam about without control, just as you would not allow a baby to crawl about unsupervised.

3. Yin Body's Transformation to a Yang Body marks the Beginning of the Transference of Consciousness.

With practice the Yin body can gradually change into more of a Yang body. The transformation into a Yang body is initiated by a transference of consciousness. The process begins in Chapter 5 of Fusion I with the transference of the Microcosmic Orbit into the energy or soul body. The process continues with the practice of Fusion II and III in which the virtue energies from the organs, the Belt Channel, the Thrusting Channels, and other channels are extended from the Yin physical body up into the energy body. During this process the soul takes on a Yang quality. As your practice continues a spirit body is formed that is also a Yang body, capable of traveling in space and capable of self-care.

4. Purpose of Traveling in Space

The main goal of your practice with the UniversalTao is to travel a higher plane of energy:

a. The energy needed for absorption that helps develop the soul and spirit bodies is not available on the human plane.

b. By traveling to a higher plane of energy, you are practicing your return to the Wu Chi, the Original Source from which you came.

c. In space traveling the combined soul and spirit bodies you have developed can travel very fast. The speed is believed to be faster than the speed of light. It now becomes possible to encounter the souls and spirits of people who already have passed from their human lives.

d. Some people travel to a different time, such as the time before they were born into their Earthly lives. This ability also enables them to see into the future.

In Taoism and other systems, practitioners try to avoid those elements that in the past or future comprise their Earthly lives.Their aim is to try to return to the place of their origin, a place they would like to be. If, as in normal Earthly traveling, you continuously stop to talk to people, it will take much longer to arrive at your destination, or you may never arrive at all.

E. How to Develop the Energy Body.

1. Using a Pearl to Create the Energy Body.

a. The energy body is created by using the pearl. You can continue to use the pearl you have already developed, or, if you are starting fresh, create a pearl by practicing Chapters 1 through 5 again.

b. Circulate the pearl in the Microcosmic Orbit.

c. Inhale, activate the Cranial and Sacral Pumps, and shoot the pearl through the crown of the physical body. Bring the pearl to a level above and equal to the height of your physical body.

2. Creating the Energy Body.

a. Relax the senses and the mind, and then use them to expand the pearl. (Fig. 5.6) Begin to shape the pearl into a form similar to your own body, or into the image you would like your body to be. Initially it might feel like a great mass of energy. (Fig. 5.7) Use your senses like carving tools to shape the head, body, hands, and legs. (Fig. 5.8)

If you prefer a religious conceptualization, your goal may be to form the image in the likeness of God, or perhaps the founder of your religion, such as Buddha. Taoists believe all humans are built in the image of God, since all people come from the Original Force.

b. Once you sense the body is in good shape, use your senses again to carve the face.


Relax the
Senses and
the Mind

Fig. 5.6 *Relax the Senses and Mind; Let the Pearl expand.*



***Fig. 5.7** The Pearl might feel like a Great Mass of Energy.*



Fig. 5.8 *Continue expanding the Pearl into an Energy Body.*



Fig. 5.9 *Forming the Energy Body's Eyes.*



Fig. 5.10 *Forming the Energy Body's Eyes.*



Fig.5.11 *Forming the Energy Body's Nose.*



Fig. 5.12 *Forming the Energy Body's Mouth.*

(1) To form the eyes, focus on the eyes of the physical body. When you feel a very strong awareness of these eyes, condense their essence into a ball. Activate the crown, and exhale the ball to the place on the face of the energy body where the eyes will be positioned. Feel and affirm that the eyes of the energy body have been formed. (Fig. 5.9)

(2) Be aware of the ears. When you feel the essence of the physical body's ears is condensed into an energy ball, transfer it to the energy body's ears. (Fig.5.10)

(3) Be aware of the nose, and. in a similar way, transfer it up to the energy body. (Fig.5.11)

(4) Be aware of the mouth, and similarly transfer it up to the energy body. (Fig.5.12)

(5) Be aware of the tongue, and also transfer it up to the energy body.

c. Now you can form and arrange the senses of the energy body into shapes you like. You can make the nose longer or higher on the face, the eyes smaller or bigger, or the mouth wider or smaller.

d. Copy the cauldron within the physical body to the energy body by ating on it. When you feel the energy is very condensed, shoot it up through the perineum of the energy, body.

e. Now you can make the energy body the sex of your choice.

f. When you feel the energy body is fully grown, or formed into a very sharp image, you can give it an inner name and associate this name with it in the future. Then, in later practice, simply call the name of the energy form, and the whole process will take place instantly. It is best to keep the soul or energy body name to yourself, so that you will be the only one who can activate it. This is important because in more advanced stages of practice, a person with bad intentions who knows your soul name can activate it and make use of it. This means that person can steal energy from the energy body, or tell the soul to do something that is bad or evil. If this happens, you will have to change to a new name or code for your energy body.

g. In addition to associating the energy body with an inner name, you can also associate the energy body with an inner voice or inner voices.The inner voice (or voices) will give you advice to help you make decisions.The more you listen to the voice(s),the clearer it (or they) will become. As You begin to develop more virtue energy, the voice(s) will become more distinct. This will help you make choices between good or bad, help you to choose friends, etc.

3.Transferring the Microcosmic Orbit to the Energy Body.

The energy body is a Chi body that offers no resistance, and so it is very easy to open its Microcosmic Orbit. Creating the energy body and transferring the Microcosmic from the physical body to the energy body is the first transference of consciousness you will experience in your practice.

Each day as you work on this stage of Fusion, you transform more consciocness to the energy body. At this stage, the energy body is simply a powerful projection of your mind and your physical body. At higher levels of practice, this energy body is crystallized into a permanent spiritual body.

a. Create another pearl in the cauldron and circulate it in the Microcosmic of the physical body.

b. Inhale, activate the Cranial and Sacral Pumps, activate the lead light, and aim the lead light at the perineum of the energy body. Shoot this pearl through the crown of the physical body and penetrate the perineum.

c. Use the senses to move the pearl up to he energy body's sacrum. Stop for a while and feel the pearl establish itself at the sacrum point.Then move the pearl up to the Door of Life, T-11, C-7, base of the skull, crown, Third Eye, tongue, throat, heart, solar plexuus, navel, sexual center, and perineum, completing the Microcosmic Orbit of the energy body. Another way to transfer the Microcosmic is simply to copy the Microcosmic of the physical body. (Figure 5.13)

4. Forming a Protective Shield Around the Energy Body.

a. Form another pearl in the physical body, and circulate it in the Microcosmic Orbit of the physical body until it gains momentum.Once it has gained momentum, and upon its return to the perineum of the physical body, begin to move the pearl up again through the physical body as follows:

(1) Inhale and activate the Cranial Pump. Contract the perineum the anus, and the back of the anus. Pull the pearl up to the sacrum, Door of Life, T-11, C-7, base of the skull, and toward the back of the crown to a point about one and a half inches behind the crown. Hold at this point.

(2) Feel the pulsation at the back of the crown. Exhale and shoot the pearl out. Use the pearl to form a bubble to cover the entire energy body.

5. Forming a Great Bubble Encasing Both Bodies as a Protective Shield

a. Form one more pearl. Circulate this pearl in the Microcosmic Orbit of the physical body to gain momentum. Stop again at the perineum of the physical body.

b. As above, pull the pearl all the way up the Governor Channel of the physical body to the point one and a half inches behind the crown. Shoot it out from this point to encircle the energy body', bringing it all the way down to cover the physical body as well. You now have formed a great bubble encasing both bodies and the protective shield of the energy body. (Fig.55)

c. Be aware of the energy body, the physical body, and the bubbles that form the protective shields around both bodies. Also be aware of the energy above the energy body and below the physical body.

6. Drawing in the Energy Body and the Big Protective Bubble to Finish the Practice

a. When you are ready to finish this practice, first absorb as much as possible of the Heavenly Force once more.

b. Condense the energy body into a pearl still surrounded by the bubble that serves as its protective shield. Notice that the color of the pearl may now be brighter, or the pearl may have grown larger.

c. Be aware of the Big Bubble that continues to protect the physical and energy bodies and the energy body's bubble as a great protective shield.



Fig. 5.13 *Shoot the pearl to the perineum of the energy body to open its Microcosmic Orbit. Circulate both Microcosmic Orbits.*



***Fig. 5.14** Forming an Energy Body, its Protective Shield, and a Great Bubble to protect all.*



***Fig. 5.15** Shrinking and Drawing in to the crown and into the navel of the Energy Body's Bubble.*

5. Forming a Great Bubble encasing Both Bodies as a Protective Shield.

a. Form one more pearl. Circulate this pearl in the Microcosmic Orbit of the physical body to gain momenum. Stop again at the perineum of the physical body.

b. As above, pull the pearl all the way up the Governor Channel of the physical body to the point one and a haft incches behind the crown. Shoot it out from this point to encircle the energy body, bringing it all the way down to cover the physical body as well. You now have formed a great bubble encasing both bodies and the protective shield of the energy body. (fig. 5.14)

c. Be aware of the energy body, the physical body, and the bubbles that form the protective shields around both bodies. Also be aware of the energy above the energy body and below th physical body.

6.Drawing in the Energy Body and the Big Protective Bubble to Finish the Practice.

a. When you are ready to finish this practice, first absorb as much as possible of the Heavenly Force once more.

b. Condense the energy body into a pearl still surrounded by the bubble that serves as its protective snield. Notice that the color of the pearl may now be brighter, or the pearl may have grown larger.

c. Be aware of the Big Bubble that continues to protect the physical and energy bodies and the energy body's bubble as a great protective shield.

d. Inhale and activate the Cranial Pump. Feel the pulsation. Feel the lead light extend out from the crown point.

e. Inhale and slowly use the mind and senses to draw in the pearl. Inhale again and use your mind to guide the pearl to land on the opening of the crown where the lead light emerges. Inhale once more with force to pull the pearl down from the crown through the front channel.

f. Circulate the pearl in the Microcosmic Orbit. As the enhanced pearl moves around the Orbit, it will bring its heightened energy to the organs and glands. Any part of the body that requires it will absorb it.

g. Be aware of the energy body's protective bubble remaining above the physical body and within the big protective bubble. Be aware of the crown and the point one and a half inches behind the crown. Inhale and draw the energy body's bubble through the crown and the point one and a half inches behind it. Inhale and draw the energy body's bubble through the crown and the back of the crown into the Microcosmic Orbit, and add this energy to the pearl that is already circulating.

The energy that now circulates in the Microcosmic is the combined energy body and protective bubble energy that has been drawn into the physical body. The great bubble that surrounded both the energy and physical bodies and the energy body's bubble remains and continues to surround and protect the physical body.

h. Begin slowly to trim down the big bubble that continues to surround the physical body by condensing or shrinking it and drawing it in through the point one and a half inches behind the crown. Add this energy to the pearl that is circulating in the Microcosmic Orbit.(Fig.5.15)

i. Bring the pearl down the front channel to the navel.

j. The remaining protective shield can be drawn in closer and tighter to the physical body by drawing this energy in through the navel. Feel the energy remaining as the bubble on the outside of the physical body as it pulls in tightly to cover the body. You are now protected from within and from without by this protective shield. As your practice continues, you can continue to form new pearls and additional protective shields.

k. Return the pearl to the cauldron. Spiral and condense the energy.

l. Practice Chi Massage.

Chapter 6

Part Two: Fusion I Meditation
Advanced Practice of Fusion I

Chapters 6 through 9

The chapters of Part Two describe energy in images. These images are used to enhance, empower, and protect the organs' energies as you create a more powerful pearl and form a stronger energy body.

The Taoists theorized that, like water, energy is formless. Without giving energy a form, it is difficult to capture its force. Just as water takes on the shape of the jar or pot that contains it, energy can take on the shape of the vessel into which it is placed. Regardless of the vessel's shape, the qualities of the water remain unchanged. Yet, by being contained in the vessel, it becomes easier to use. For example, because you can carry the water, you now can pour the water into a specific place. In doing so you are establishing a connection between the water and that place. Similarly, giving energy a form while retaining its purity helps to establish connections for usage.

Consider religious statues of gods or saints. To help religious devotees form a picture and establish a connection between themselves and a power greater than themselves, an image is created representing and giving form to that power. Once a more understandable picture is formed in the individual's mind of that power, that person can more readily connect with its positive energy. This is the secret power of visualization behind all the world's religions, whether it be the image of Jesus, the Virgin Mother and Holy Child, Buddha, the sacred geometry of Islam, or the numerous gods and goddesses of Hinduism, the Greeks, the Romans, or the ancient Egyptians.

Formula 6

Forming the Virgin Boys or Girls and their Animal Offspring to Connect to the Universal, Cosmic Particle, and Earth Forces

A. Using Images of Children and Animals to give Form to Pure Energy.

It is desirable to connect with the positiveness and usefulness of energy, and the pictures and images established by the early Taoists become very helpful in making this connection. As a cup or bowl becomes a container to hold water, and as the religious statues, structures, or vessels made from wood, rock, gold, or silver contain a certain power or force, the Taoist images of children and animals also contain energy. Regardless of the shape and material of the container, no one is better than another. All hold the same energy.

The Taoists images of the innocent virgin boy or girl used in association with an emotion are readily acceptable images for most people. This is probably because most people have had experiences dealing with youth or an innocent child.

The Taoist animal associations may seem a little unusual since modern people associate more with domestic animals—dogs, cats, birds. Further, different countries tend to associate themselves with different animals. Below are the animal associations the early Taoists used. You may choose to use different animals or different images, such as a ruby at the heart, an emerald at the liver, etc.

Usually people are more observant of the problems of other people or animals than they are of their own. When a child, another person, or an animal gets sick, they need care. When they feel depression, fear, or anger, it is a reflection of their inner state. You have to care for them until they heal or overcome such negative emotions. Be aware of the virgin children and animals and keep them in good spirit, and you will be taking care of your internal self.

B. Practice of Forming the Virgin Boys or Girls and their Offspring in the Forms of Animals

1. Pure Energy from the Kidneys produces the Blue Virgin Child and the Deer.

a. Return your attention to the kidneys and the kidneys' collection point. Sense if the kidneys are cleansed of all negative emotion. This can be clearly indicated by a bright, illuminating blue color, or a strong feeling of calmness and gentleness. Spiral the kidneys' essence to their collection point until the collection point glows with bright light as the feeling of gentleness intensifies.

b. Once the intense, bright color and the sensation of gentleness peak, form the blue light into the image of a virgin boy or girl dressed in the blue color. This image represents the purest form of gentleness. Picture the boy or girl breathing out a blue breath. When enough of the blue breath accumulates, watch it transform into a beautiful deer with antlers. The deer represents a more refined, purer energy of the gentleness virtue. It is the pure essence and consciousness of the kidneys, and can be transformed for the creation of and use by the soul and spirit bodies. Make a strong connection with the virgin child and the deer, and instantly, at any time, you can restore a sense of calmness and gentleness within yourself. (Fig.6.1)



Fig. 6.1 *Blue Virgin Child and Deer from the Kidneys*



Fig. 6.2 *Red Virgin Child and Pheasant from the Heart*

2. Essence of the Heart produces the Red Virgin Child and the Pheasant.

a. Be aware of the heart and its collection point. Picture the heart's collection point illuminating with bright, red light and feel a strong sensation of love and joy, the virtues of the heart.

b. At the most intense moment of color and feeling, form the glowing red light into a virgin boy or girl, dressed in the red color. Watch the boy or girl breathe out a red breath, or sense the love, joy, and happiness. Form the breath or the feeling into a red pheasant.

Make a strong connection with the virgin child and the pheasant, and instantly, at any time, you can restore a sense of love, joy, and happiness within yourself. (Fig. 6.2)



Fig 6.3 *Green Virgin Child and Dragon from the Liver*

3. Pure Energy from the Liver produces the Green Virgin Child and the Dragon.

a. Concentrate on the liver and its collection point until you can picture the liver's collection point illuminating with a green light or feel an overwhelming sense of kindness.

b. When the green color is its brightest, or when the feeling of kindness peaks, form the color or feeling into a virgin boy or girl wearing the color green. Watch the boy or girl breathe out a green breath, or feel the intense kindness, and form it into a green dragon.

Make a strong connection with them, and instantly, at any time, you can restore a sense of kindness within yourself. (Fig.6.3)



Fig. 6.4 *White Virgin Child and Tiger from the Lungs*

4. Lungs' Essence produces the White Virgin Child and a Tiger.

a. Be aware of the lungs and their collection point. Make the collection point luminous with a bright white or metallic color or feel the powerful virtue of courage.

b. When the vision of color or sensation of courage is strongest, form it into a virgin boy or girl dressed in the color white. See the virgin boy or girl breathe out a white breath, or feel the sensation of intense courage. Change it into a white tiger.

Make a strong connection with them, and instantly, at any time, you can restore a sense of courage within yourself. (Fig. 6.4)



***Fig. 6.5** Yellow Virgin Child and Phoenix from the Spleen*

5. Pure Energy of the Spleen produces the Yellow Virgin Child and the Phoenix.

a. Concentrate on the spleen and its collection point at the front pakua, Observe as the spleen and the front pakua illuminate with a yellow light or sense the strong feelings of openness and fairness.

b. When the color yellow, or the feelings of openness and fairness are very intense, transform the color or feelings into a virgin boy or girl dressed in yellow. The virgin breathes out the yellow breath or the feeling of openness or fairness increase, and the transformation into a phoenix occurs.

Make a strong connection with them, and instantly, at any time, you can restore a sense of openness and fairness within yourself. (Fig. 6.5)

The brighter the colors, or the more intense the feelings of virtue, the purer the indication of virtue and, so, good health.

C. Use the Virgin Boy or Girl and the Animals to form Protective Rings inside the Body.

Beginning at the liver's collection point with the virgin child and the green dragon, begin a circle up to the virgin child and red pheasant of the heart's collection point. Then continue the circle down to the virgin child and the white tiger at the lungs' collection point, and down to the virgin child and the blue deer at the kidneys' collection point. The virgin child and the yellow phoenix are at the front pakua which is in the middle of the four points of the circle.



Fig. 6.6 *Protective Ring of the Organs' Earth Animals*

These "power animals" form a protective outer ring around your organs. (Fig. 6.6) In the inner ring are your virtue energies crystallized into the different colored virgin boys or girls.

You may choose to create different "power animals" to protect yourself. While meditating on each organ, you can simply ask, Is there a protective animal that is willing to defend my kidneys-water energy? , etc. If no animal appears you may ask for a "power crystal" or a "powerful warrior(s)" to serve you in your spiritual work.

D. Pearl connects with the Universal, Cosmic, and Earth Forces to supply Energy to the Children and Animals.

The pearl will be the center of the gathering of the children and the animals and is enhanced by them. If the pearl dims or disappears, the children and the animals become hard to form.

a. Be aware of the pearl at the cauldron. Feel it shine with the bright light of the silvery or bluish-white color of a pearl.

b. Be aware of the four pakuas, the organs' collection points, the organs, senses, and their energies.

c. Move the pearl down to the perineum and into the Microcosmic Orbit. As the pearl moves through the Microcosmic, feel the Universal, Cosmic Particle, and Earth Forces supplied to the pearl. As the pearl moves, the children and the animals can take energy from the pearl as they need it. This energy, in turn, will help to strengthen the organs physically and spiritually.

d. If you wish to continue to the next chapter, there is no need to collect the energy now.

E. Finish the Meditation.

1. To finish, collect the energy, move the pearl into the cauldron, and spiral to condense the energy there.
2. Be aware of the animals and absorb them into the child to which each belongs; the deer to the blue child, the pheasant to the red child, the dragon to the green child, the tiger to the white child, and the phoenix to the yellow child.
3. Be aware of the organs and the child belonging to each one: the blue child to the kidneys, the red child to the heart, the green child to the liver, the white child to the lungs, and the yellow child to the spleen. As you absorb the children into the organs, sense each organ illuminating with a brighter light. This bright light indicates a healthier organ containing a good energy.
4. Practice Chi Massage.

Chapter 7

Formula 7: Call forth the Earth Force to Empower and Protect

When the impure organ energy (negative emotional energy) has been cleared from the organs and their collection points, they will illuminate with a light that will project outward and attract the Earth Force. Once you clearly feel the Earth Force and are able to formulate a very intense picture of the traditional Taoist animals, these images can serve as vessels to make it easier to capture and retain the Earth Force. This is especially true when you are well-practiced. Again, you might have chosen a ring of different magnificent colored flowers or a ring of mighty trees to serve as your Earth Force guardians.

A Pure Kidneys' Energy attracts the Earth Force in the Image of a Big, Blue/Black Turtle.

1. Sit facing South.

2. Be aware of the kidneys and the kidneys' collection point as they illuminate with bright blue light.

3. Sense the virgin child and the deer. When you experience them very intensely, spiral at the collection point. Then exhale through the point. Use the mind and the power of the senses to project an intense wave of gentleness forward to the front, or South, side of the body.

The elemental forces are omnipresent. This means that the Five Elements of the Earth Force exist everywhere on Earth. Therefore, you can project the force out in any direction, although in the beginning you will find that it is much easier to project the force to the front. (***Note:*** Illustrations 7.1 through 7.6 demonstrate projecting the force to the front of the body.) When you are well-trained, it is possible to project the force to a specific direction associated with the force you want to attract. For example, the force of gentleness can be projected backward, to the North.

The important thing to remember is that whatever kind of force you project out of the body will be the kind you will call forth, regardless of the direction. Just like casting out a baited fishing line to catch a fish, your success will depend on the size of the bait (or your own force) that you project.

4. The greater the force you can project, the greater the amount of watery Earth Force you will attract.

5. You can sense the force. If you are a more visual type of person, you might see a bright blue force. If you are a more kinesthetic type of person, you might feel the gentleness or calmness of the force.

6. The turtle is the Earth Force of the North. Once you feel the Earth Force very intensely, picture the form of a big turtle (also known as the Black Warrior). Put it on your back to protect your back, or North, side. (Fig.7.1)



Fig. 7.1 *Kidneys, shown projecting to the Front, attract the Turtle Earth Force of the North.*

B. Pure Heart's Energy attracts the Earth Force in the Shape of a Red Pheasant.

1. Continue facing South in a seated position.

2. Become conscious of the heart and the heart's collection point.

3. Sense the organs as they illuminate with red light until the virgin child and the pheasant are perceived clearly.

4. Spiral the force at the heart and heart's collection point. Project your force out of the body to its front or South side to call forth and attract the fiery force of Earth.

5. The pheasant is the Earth Force of the South. When you sense the bright red color, or sense love and joyful energy very intensely, form a pheasant to capture the fire force of the Earth. Place the pheasant on your front or South side for protection. (Fig.7.2)



Fig 7.2 *Heart, shown projecting to the Front, attracts the Pheasant Earth Force of the South.*

C. Pure Liver's Energy attracts the Earth Force in the Image of a Green Dragon.

1. Continue to sit facing South. Be aware of the liver and the liver's collection point.

2. Sense the organ's illumination with green light until the virgin child and the green dragon are perceived clearly.

3. Spiral the force at the liver and the liver's collection point. When you feel the energy very intensely at the collection point, project your force out of the body to the front side to attract the wood force of the Earth. (If you are able, project the force to the body's East or right side.)

4. When you sense this green force; or sense kindness very intensely, form a green dragon to retain the wood force of the Earth. Move the dragon to the body's East or right side for protection. (Fig. 7.3)



Fig 7.3 *Liver, shown projecting to the Front, attracts the Dragon Earth Force of the East.*

D. Pure Lungs' Energy attracts the Earth Force in the Image of a White Tiger.

1. Continue to sit facing South. Become conscious of the lungs and the lungs' collection point.

2. Sense this organ's illumination with a white light until the virgin child and the white tiger are clearly sensed.

3. Spiral the force at the lungs and the lungs' collection point. When you feel the energy intensify at the collection point, project your force out of the body to the front, or South, side to attract the metal force of the Earth. (If you are able, project the force out to the body's West or left side.)

4. When you have a strong sense of the white force of the Earth's metal energy, or sense courage strongly, form a white tiger. Move the tiger to the West, or left side of the body for protection.(Fig.7.4)



Fig. 7.4 *Lungs,shown projecting to the Front, attract the Tiger Earth Force of the West.*

Note: When there is a need for balance in the liver or the lungs, it is possible to call forth their two Earth animals to each other's internal animals. For example, the green dragon of the liver, found internally on the right side of the body, can attract the Earth tiger force associated with the lungs. The Earth tiger force would then be placed on the left side of the body to attain balance in the liver. The same is true of the internal white tiger of the lungs and the dragon Earth force, with the Earth dragon placed on the right side to give balance to the lungs. This method of balance applies only to these two forces.

E. Pure Spleen's Energy Attracts the Earth Force in the Image of a Yellow Phoenix.

1. Continue to sit facing South. Be aware of the spleen and the spleen's collection point.

2. Sense the spleen's illumination with a bright yellow color, or experience a strong sense of fairness and openness.

3. Spiral the force at the spleen and the spleen's collection point. Once you feel an intense energy at the collection point, project your force out of the body to the front, or South, side to attract the Earth Force. (If you are able, project the force up through the center of the body through the top of the head.)

4. When you strongly sense the yellow force of the Earth's energy, or intensely sense fairness and openness, form a phoenix. Move it to the middle of the top of the head for protection. (Fig. 7.5)



***Fig. 7.5** Spleen, shown Projecting to the Front, attracts the Phoenix Earth Force.*

F. Form the Earth Force Animals into a Protective Ring and Dome of Fire.

1. Reinforce the Earth Force animals. See them, feel them or in any way sense the presence of their force and the virgin energy of the Earth Force.

2. Form a ring of fire connecting the four animals together: the red pheasant, the green dragon, the big, blue/black turtle, and the white tiger. The yellow phoenix at the top of the body forms a fiery dome that touches and connects the circle. (Fig.7.6)



***Fig 7.6** Protective Ring and Dome of the Earth Animals.*

Five Element Organ Correspondences

	Wood	**Fire**	**Earth**	**Metal**	**Water**
Yin Organs	Liver	Heart	Spleen	Lungs	Kidneys
Yang Organs	Gall Bladder	Small Intestine	Stomach, Pancreas	Large Intestine	Bladder
Openings	Eyes	Tongue	Mouth, Lips	Nose	Ears
Positive Emotions	Kindness	Love, Joy	Fairness, Openness	Righteous, Courage	Gentle
Negative Emotions	Anger	Hate, Impatience	Worry, Anxiety	Sadness, Depression	Fear, Stress
Transform Pure Organ Energy into a Virgin Child Dressed in	Green	Red	Yellow	White	Blue
Transform Pure Child Energy into a Animal	Green Dragon	Pheasant, Red Bird	Phoenix, Yellow on Red	White Tiger	Blue Deer
Earth Force takes the Form of	Green Dragon	Pheasant, Red Bird	Phoenix, Yellow on Red	White Tiger	Black Tortoise
Directions	East	South	Center	West	North

Table 4

3. The dome of fire can protect the physical body by strengthening the organs. It can protect the soul body as well. Spiral the dome and the pakuas in either direction.

4. As you continue to face South, be aware of the relationship of the four pakuas to the four animals: the front pakua to the pheasant, the back pakua to the blue/black turtle, the left pakua to the white tiger, and the right pakua to the green dragon. Absorb the phoenix force through the crown and down to the cauldron. Absorb the forces of the Earth animals into the pakuas and then to their corresponding organs. Their energy will help to strengthen all the organs and glands. (See Table 3.)

5. At this point return to Chapter 5 and create a more powerful pearl. Continue to draw energy, including the five Earth Animals' Forces, into the front, back, left, and right pakuas and blend it together. Pull their energies into the cauldron to create the greatly refined and radiant pearl that is used to create a more powerful soul or energy body.

6. Be aware of the cauldron as the pearl is enhanced. You can feel the pearl growing bigger and heavier. Move the pearl in the Microcosmic. Be aware of the Universal Force from the stars and planets above, the Cosmic Particle Force before you, and the Earth Force below. The Earth Force of the animals is absorbed into the pearl.

G. Create the Energy Body.

Following Chapter 5 create the energy body this time using the greatly enhanced pearl. Once the body is formed and if you decide to continue, proceed to Chapter 8.

H. Finish the Meditation.

If you wish to finish:

1. First absorb the stars' forces as much as possible once more.

2. Condense the energy body into a pearl. Notice that the color of the pearl is intensely bright and the size is larger.

3. Inhale and activate the Cranial Pump. Feel the pulsation. Feel the lead light extend out from the crown point.

4. Inhale and slowly use the mind and senses to draw in the pearl. Inhale again, and use your mind to guide the pearl to land on the opening of the crown where the lead light emerges. Inhale once

more with force to pull the pearl down from the crown through the front channel.

5. Circulate the pearl in the Microcosmic Orbit. As the enhanced pearl moves, it will enhance the organs and glands. Any part of the body that requires its energy will absorb it.

6. Bring the pearl down to the navel and return it to the cauldron. Be aware of the four pakuas and the crown continually absorbing the Earth Force. Spiral the four pakuas and the pearl, and absorb the Earth Force into the pearl. Collect the energy in the cauldron.

7. Practice Chi Massage.

8. Now the Earth Animals' Force can return to its origin, or it can remain where it is for continued protection. This depends on your proficiency of practice.

Remember the Universal Tao practice is not solely a visualization process. You must sense the force, and not simply picture it in your mind.

Chapter 8

Formula 8: Call Forth the Planets' and Stars' Forces for Empowerment and Protection

A. Pearl is the Product of your Successful Practice.

Begin Chapter 8 by practicing Chapters I through "Create the Energy Body" in Chapter 7. With time and continued practice, everything will become easier and faster. Once your mind is trained, you will be able to control all the four pakuas, the collection points, the weather, the senses, and the emotions easily. As you spiral the energy, you will perceive all of these as balanced and in harmony, ready to be transformed and condensed into a pearl. All will take place in a few minutes.

In your later practice, upon being well-trained, all you will need to do is concentrate on the center of control (the cauldron). Then you will use the mind to turn all the senses inward and condense the pearl. This will require a simple awareness of the four pakuas and all the collection points, organs, and senses.

If the pearl formed has a good, shining light, you will be successful in your practice of balancing the energy and transforming the negative emotions. Then, like a factory that is set up properly, all you need do is check the finished product. If the finished product is right, the factory is running smoothly. The pearl is the finished product of your practice.

B. Create a Fully Developed Pearl; Extend and maintain the Pearl above the Crown.

1.Once the pearl has been fully developed and is well-positioned at the cauldron, be aware of the Earth animals supplying the force to it. Move the pearl down to the perineum, and then move it into the Microcosmic until you feel it gain momentum. Be aware of all the sources supplying energy to the pearl. Stop the pearl at the perineum, and feel the full charge of the force at the perineum.

2. Activate the Cranial Pump, and pull the pearl up to the crown. Totally concentrate your mind and senses on the crown, and feel the pulsation there. Feel the crown breathing, opening and closing. Feel the lead light go out through the opening like a fine string. Check for proper timing, and then inhale once more. Swallow the saliva, and feel the pearl pushing upward toward the crown. Feel the crown open.

3. Exhale forcefully toward the crown to shoot the pearl out. The pearl serves as the connection between yourself and heaven. It will enable you to absorb the higher, purer, Universal Force by bringing it down to your physical body. There it can be processed to a more refined energy you can use.

4. Maintain the pearl about three to six feet (one to two meters) above the crown of the energy body. Use the mind and senses as though they were a wireless control determining the movement of the pearl, moving it up and down, right and left, and in a spiral.

C. Call forth the Force of the Planets.

Form as many pearls as necessary to complete this exercise.

1. Summon Mercury's Force to the Energy Body.

a. Be aware of the physical body, the cauldron, and the kidneys. Sense the blue color or the gentleness force generating from the kidneys.

b. Form a blue or gentleness pearl and bring this pearl to the perineum.

c. Move it into the Microcosmic Orbit to gain momentum and absorb the forces from all sources. Stop at the perineum and activate the Cranial and Sacral Pumps.

d. Draw the pearl up to the crown, and activate the lead light. Look up with the inner eyes, and sharpen your awareness of the space above you and your energy body into which you will shoot the pearl.

e. Inhale, swallow the saliva upward, and exhale forcefully up toward the crown. Shoot the pearl as high as you can into the space above you. (Fig. 8.1)



Fig 8.1 *Shoot the Pearl high up into the Space above you.*

f. Exhale.Relax totally, and do the Heart Sound (***Hawwwwww***) to attract the Universal Force and to collect the force as it falls. Feel the Universal Force fall like blue snow. (Fig. 8.2)

g. Concentrate your mind and your senses to condense the falling blue snow into the blue planet representing the water force, Mercury. This force will enhance the soul and spirit of the kidneys.

h. Place this force at the back of the energy body. (Fig. 8.3)



Fig. 8.2 *Do the Heart Sound-**Hawwwwww** to attract the Universal Force.Sense the force falling down as blue snow.*



Fig. 8.3 *Condense the falling blue snow into the planet Mercury and place it behind the energy body.*

2. Summon the Force of Mars to the Energy Body

a. Be aware of the physical body, the cauldron, and the heart. Sense the red color or force of love, joy, and happiness generating from the heart.

b. Form a red pearl or pearl of joy, and bring it to the perineum.

c. Move this pearl into the Microcosmic Orbit to gain momentum and absorb the forces from all sources. Stop at the perineum and activate the Cranial and Sacral Pumps.

d. Draw the pearl up to the crown, and activate the lead light. Look up with the inner eyes, and sharpen your awareness of the space above you into which you will shoot the pearl.

e. Inhale, swallow the saliva upward, and exhale forcefully up toward the crown. Shoot the red pearl as high as you can into the space above you.

f. Exhale. Relax totally, and do the Heart Sound (***Hawwwwww***) to attract the Universal Force and to collect the force as it falls. Feel the heavenly, Universal Force fall like red snow.

g. Concentrate your mind and your senses to condense the falling red snow into the red planet representing the fire force, Mars. This force will enhance the soul and spirit of the heart.

h. Place this force at the front of the energy body. (Fig. 8.4)

3. Summon Jupiter's Force to the Energy Body

a. Be aware of the physical body, the cauldron, and the liver. Sense the green color or force of kindness generating from the liver.

b. Form a green or kindness pearl and bring it to the perineum.

c. Move this pearl into the Microcosmic Orbit to gain momentum and absorb the forces from all sources. Stop at the perineum and activate the Cranial and Sacral Pumps.

d. Draw the pearl up to the crown and activate the lead light. Look up with the inner eyes and sharpen your awareness of the space above you into which you will shoot the pearl.

e. Inhale, swallow the saliva upward, and exhale forcefully up toward the crown. Shoot the green pearl as high as you can into the space above you.

f. Exhale. Relax totally and do the Heart Sound (***Hawwwwww***) help attract the Universal Force and to collect the force as it falls. Feel the heavenly, Universal Force fall like green snow.



Fig. 8.4 *Shoot the pearl up as high as you can into space to connect with the force of Mars. Place Mars' Force at the Energy Body's Front.*

g. Concentrate your mind and your senses to condense the falling green snow into the green planet representing the wood force, Jupiter. This force will enhance the soul and spirit of the liver.

h. Place this force on the left side of the energy body.

4. Summon the Force of Venus to the Energy Body.

a. Be aware of the physical body, the cauldron, and the lungs. Sense the white color or force of courage generating from the lungs.

b. Form a white pearl or pearl of courage and bring it to the perineum.

c. Move this pearl into the Microcosmic Orbit to gain momentum and absorb the forces from all sources. Stop at the perineum and activate the Cranial and Sacral Pumps.

d. Draw the pearl up to the crown and activate the lead light. Look up with the inner eyes and sharpen your awareness of the space above you into which you will shoot the pearl.

e. Inhale, swallow the saliva upward, and exhale forcefully up toward the crown. Shoot the white pearl as high as you can into the space above you.

f. Exhale. Relax totally and do the Heart Sound (***Hawwwwww***) to attract the Universal Force and to collect the force as it falls. Feel the heavenly, Universal Force fall like white snow.

g. Concentrate your mind and your senses to condense the falling white snow into the white planet representing the metal force, Venus. This force will enhance the soul and spirit of the lungs.

h. Place this force on the right side of the energy body.

5. Summon the Force of Saturn to the Energy Body.

a. Be aware of the physical body, the cauldron, and the spleen. Sense the yellow color or force of fairness and openness generating from the spleen.

b. Form a yellow pearl or pearl of fairness and openness, and bring it to the perineum.

c. Move this pearl into the Microcosmic Orbit to gain momentum and absorb the forces from all sources. Stop at the perineum and activate the Cranial and Sacral Pumps.

d. Draw the pearl up to the crown and activate the lead light. Look up with the inner eyes and sharpen your awareness of the space above you into which you will shoot the pearl.

e. Inhale, swallow the saliva upward, and exhale forcefully up toward the crown. Shoot the yellow pearl as high as you can into the space above you.

f. Exhale. Relax totally and do the Heart Sound (***Hawwwwww***) to attract the Universal Force and to collect the force as it falls. Feel the heavenly, Universal Force fall down like yellow snow.

g. Concentrate your mind and your senses to condense the falling yellow snow into the yellow planet representing the earth force, Saturn. This force will enhance the soul and spirit of the spleen.

h. Place this force on top of the energy body.

6. Be Conscious of the Five Planets surrounding the Energy Body.

Be aware of the five planets that you have placed around the energy body to empower and protect it. Sense the glowing light of the planets.

D. Set the Planets into Orbit around and absorb their Forces into the Energy Body.

1. Start the Orbit of Mars around the Energy Body.

Be aware of the planet Mars moving in its orbit around the Sun. Similarly, start to move Mars into orbit around the energy body.

2. Movement of Mars activates the Orbit of the Other Planets Around the Energy Body.

As Mars moves into orbit, it will activate the movement of Venus, Mercury, and Jupiter into orbit. Their orbits form rings of light surrounding and protecting the pearl. These rings of light also are used in later practice to expand the pearl into an energy body.

3. Saturn provides the Protective Dome over the Crown.

Move Saturn into orbit around the top of the crown to form a dome of protective light over the crown.

4. Absorb the Planets' Forces into the Energy Body.

Be aware of the energy body and use your mind and senses to help the energy body absorb the planets' forces. Notice the pearl changing color or growing larger or heavier.

E. Energy Body Beams the Planets' and Stars' Forces into the Crown.

1. Crystal Room under the Crown serves as a Prism of the Planets' Forces.

When the crown of the energy body receives the forces from the planets, it will beam their forces down through the crown of the physical body to the crystal room under its crown. The crystal room, also known as the third vertical room, is situated in the middle of the brain. It is considered the control center for information processing of the pineal gland, pituitary gland, and all other glands of the body. During the Fusion Meditation practice, the crystal room functions as a prism to reflect the rainbow colors down to the organs. You can sense the organs glowing with light. (Fig. 8.5)

2. Forces of the North Star and the Big Dipper shine into the Crown.

Be aware of the purple light of the North Star and the red light of the Big Dipper shining into the, crown of the energy body, and then down to the crown of the physical body. Feel the light enter into the crystal room.

3. Condensed Essential Forces revert to the Original Force.

The forces of these five planets, the North Star, and the Big Dipper will help to purify and enhance the organs further. The pure essence of the organs that now exists can easily condense at the crown. The Taoists say that when the five essential forces condense at the crown, they are returning into the Original Force.


SATURN
MARS

Fig. 8.5 *The Planets' Forces Beam Down to the Crystal Room.*



***Fig. 8.6** Interconnection of All Forces*

Five Element Organ Correspondences

	Wood	Fire	Earth	Metal	Water
Yin Organs	Liver	Heart	Spleen	Lungs	Kidneys
Yang Organs	Gall Bladder	Small Intestine	Stomach, Pancreas	Large Intestine	Bladder
Openings	Eyes	Tongue	Mouth, Lips	Nose	Ears
Positive Emotions	Kindness	Love, Joy	Fairness, Openness	Righteous, Courage	Gentle
Negative Emotions	Anger	Hate, Impatience	Worry, Anxiety	Sadness, Depression	Fear, Stress
Transform Pure Organ Energy in Virgin Child Dressed In	Green	Red	Yellow	White	Blue
Transform Pure Child Energy in an Animal	Green Dragon	Pheasant, Red Bird	Phoenix, Yellow on Red	White Tiger	Blue Deer
Earth Force takes the form of	Green Dragon	Pheasant, Red Bird	Phoenix, Yellow on Red	White Tiger	Black Tortoise
Directions	East	South	Center	West	North
Planets	Jupiter	Mars	Saturn	Venus	Mercury
Universal Energy Force	Generate	Prosper	Stabilize	Contract	Gather

Table 5

G. Finish the Exercise.

If you wish to finish, absorb the forces of the planets and stars once more into the energy body.

1. Condense the Energy Body into a Pearl.

When you want to finish, activate the Cranial and Sacral Pumps to reopen the crown. Feel the crown open, and land the pearl at the crown opening.

2. Draw the Pearl in and move it in the Microcosmic Orbit.

Inhale, draw the pearl into the crown and let it start to circulate in the Microcosmic Orbit.

3. Absorb the Forces of the Planets, Stars and Earth.

Absorb the Earth Forces into the four pakuas and the crown. Any remaining energy of the planets, stars, and earth will return to where it came from.

4.Collect the Energy.

Collect the Energy in the cauldron.

5. Practice Chi Self-Massage.

End the exercise with Chi Self-Massage.

Chapter Nine

Formula 9: Transfer of Consciousness to the Energy Body in this Life brings Immortality.

The energy body is a Chi body that offers no resistance, and so it is very easy to open its Microcosmic Orbit. Creating the energy body and transferring the Microcosmic Orbit from the physical body to the energy body is the transference of consciousness first experienced in Chapter 5 of your basic practice and experienced again in Chapter 9 of your advanced practice.

Each day as you work on this stage of Fusion, you transform more consciousness to the energy body. At this stage of practice, this energy body is simply a powerful projection of your mind and your physical body. At higher levels of practice, this energy body is crystallized into a permanent spiritual body.

A. Transfer the Microcosmic Orbit to the Energy Body.

1. Create another pearl in the cauldron and circulate it in the Microcosmic of the physical body.

2. Inhale, activate the Cranial and Sacral Pumps, activate the lead light, and aim the lead light at the perineum of the energy body. Shoot this pearl through the crown of the physical body and penetrate the perineum.

3. Use the senses to move the pearl up to the energy body's sacrum. Stop for a while and feel the sacrum point become established. Then move the pearl up to the Door of Life, T-11, C-7, base of the Skull, Crown, Third Eye, Tongue, Throat, Heart, Solar Plexus, Navel, Sexual Center, and Perineum completing the Microcosmic Orbit of the energy body. Offering no resistance, the Microcosmic of the energy body is easy to open. Another way to transfer the Microcosmic is simply to copy the Microcosmic of the physical body. (Fig. 9.1)

4. Now begin to move the Microcosmic in both the energy and physical bodies as one unit by bringing the pearl all the way down the Functional Channel of the physical body. Continue to circulate the Microcosmic; one cycle should include both bodies. (Fig. 9.2)



Fig. 9.1 *Shoot the pearl to the perineum of the energy body to open its Microcosmic Orbit. Circulate both Microcosmic Orbits.*



***Fig. 9.2** Use the senses and the mind to circulate both Microcosmic Orbits as one cycle.*

B. Form a Protective Shield.

1. Form another pearl in the physical body, and this time circulate it in the Microcosmic Orbit of the physical body only until it gains momentum. Once the pearl has gained momentum, and upon its return to the perineum of the physical body, begin to move the pearl up again through the physical body as follows:

a. Inhale, and activate the Cranial Pump. Contract the perineum, the anus, and the back of the anus. Pull the pearl up to the sacrum, Door of Life, T-11, C-7, base of the skull, and toward the back of the crown to a point about one and a half inches behind the crown. Hold at this point.

b. Feel the pulsation at the back of the crown. Exhale, and shoot the pearl out. Use the pearl to form a bubble to cover the entire energy body.

C. Form a Great Bubble encasing Both Bodies as a Protective Shield.

1. Form one more pearl. Circulate this pearl in the Microcosmic Orbit of the physical body to gain momentum. Stop again at the perineum of the physical body.

2. As above, pull the pearl all the way up the Governor Channel of the physical body to the point one and a half inches behind the crown. Shoot it out from this point to encircle the energy body, bringing it all the way down to cover the physical body as well. You now have formed a great bubble encasing both bodies and the protective shield of the energy body. (Fig. 9.3)

3. Be aware of the energy body, the physical body, and the bubbles that form the protective shields around both bodies. Also be aware of the energy above the energy body and below the physical body.

D. Absorb All Forces into Both Bodies.

1. Up to this level of practice, the energy body is still regarded as a Yin body with a negative charge, enabling it to absorb the Yang Universal Force. As your practice advances, the Yin body can change into more of a Yang body.

2. The physical body is regarded as a positively charged Yang body. This enables the physical body to help channel the Yin force from the Earth upward to balance the Universal Force.



Fig. 9.3 *The Energy Body, its Protective Shield, and the Great Bubble that Protects all.*

3. When you are well-practiced, all that is necessary to activate all forces is an awareness of them. As an empty vase can be filled, so can the energy body most effectively be filled with, and be a container for, the forces.

4. Be aware of the forces of the virgin children, the internal animals, the external Earth animals, and the planets and stars as they are absorbed into the energy body and the physical body. (Fig. 9.4)

a. Be aware of the Earth Force from below emanating a blue force. Sense the force of gentleness and kindness coming up into the feet.

b. Be aware of the forces of the virgin children, the internal animals, and the Earth animals, and absorb them into the pakuas and into the cauldron.

c. Be aware of the energy body and the crown.

d. Be aware of the five planets and their colors. Absorb the planets' forces into the energy body. Draw the forces into the cauldron of the energy body.

e. Be aware of the North Star and its purple light.

f. Be aware of the Big Dipper and its red light shining at the crown.

g. Breathe in the purple and red light through the nose and crown of the energy body. Beam this light down to the cauldron of the energy body. These star forces will enhance the soul and spirit essences of both bodies.

h. From the crystalline cauldron of the energy body, beam down the rainbow force to the crown of the physical body, and then down to the cauldron of the physical body.

i. Channel the Earth Yin force through the physical body to the energy body to balance the energy in it and to prevent excessive heat buildup. The Yin force's negative charge drawn from the Earth keeps the energy body's charge in balance.

j. Practice for five to ten minutes.



Fig. 9.4 *Be aware of all sources of energy.*

E. Draw in the Energy Body and the Big Protective Bubble.

1. When you are ready to finish this practice, first absorb the planets' and stars' forces as much as possible once more. You can leave the remaining energies of the planets and stars. They will return to the Original Force, or will remain to protect you to the extent you need them.

2. Condense the energy body into a pearl still surrounded by the bubble that serves as its protective shield. Notice that the color of the energy of the pearl may now be brighter, or the pearl may have grown larger.

3. Be aware of the big bubble that continues to protect the physical and energy bodies and the energy body's bubble as a great protective shield.

4. Inhale and activate the Cranial Pump. Feel the pulsation. Feel the lead light extend out from the crown point.

5. Inhale and slowly use the mind and senses to draw in the pearl that was the condensed energy body. (Fig. 9.5) Inhale and use your mind to guide the pearl to land on the opening of the crown where the lead light emerges. Inhale once more with force to pull the pearl down from the crown through the front channel.

6. Circulate the pearl in the Microcosmic Orbit. As the enhanced pearl moves around the Microcosmic, it will enhance the organs and glands. Any part of the body that requires it will absorb it.

7. Be aware of the energy body's protective bubble remaining above the physical body and within the big protective bubble. Be aware of the crown and the point one and a half inches behind the crown. Inhale and draw the energy body's bubble through the crown and the back of the crown into the Microcosmic Orbit, and add this energy to the pearl that is already circulating.

The energy that now circulates in the Microcosmic is the combined energy body and protective bubble energy that has been drawn into the physical body. The great bubble that surrounded both the energy and physical bodies and the energy body's bubble remains and continues to surround and protect the physical body.



Fig. 9.5 *Shrinking and drawing in the Energy Body's Bubble to the Crown and to the Navel.*

F. Protective Shield Remains.

1. Begin slowly to trim down the big bubble that continues to surround the physical body by condensing or shrinking it and drawing it in through the point one and a half inches behind the crown. Add this energy to the pearl that is circulating in the Microcosmic Orbit, and bring this energy down the front channel to the navel.

2. The remaining protective shield can be drawn in closer and tighter to the physical body by drawing this energy in through the navel. Feel the energy remaining as the bubble on the outside of the physical body pulls in tightly to cover the body.

3. You are now protected from within and from without by this protective shield. The protective shield that remains on the outside of the body will be built upon with subsequent layers of bubbles when, as your practice continues, you continue to form new pearls and additional protective shields.

G. Absorb the Forces into the Pearl or directly into the Organs of their Origin.

1. Be aware of the external Earth Force animals and of the four pakuas. Absorb the red pheasant through the front pakua, the blue/black turtle through the back, the green dragon through the left pakua, the white tiger through the right, and the phoenix through the crown. Let whatever force remains return to where it originated.

2. Absorb the virgin children and internal animals back into the pearl, or directly to the organs where they belong. The virgin children and animals are the purest forms of the organs' energies. Virtue energy in its purest form can be combined and transformed, and this energy is the consciousness that is transferred to the energy body.

H. Finish the Practice.

1. Condense and draw the pearl that has moved down the front channel into the navel.

2. Bring the pearl to the navel and back to the cauldron. Spiral, collect, and condense the energy at the cauldron. As your practice progresses and the organs' energies become stronger and purer, the pearl will remain condensed longer. When the pearl finally is released, it will separate and go to the organs and glands that need it as a more refined, more enhanced energy that will heal and strengthen them.

3. Practice Chi Massage.

Chapter 10

Summary: Entire Fusion I Practice

All Chapters: 1 through 9

A. Create a Pearl.

1. Smile down to the face and organs; generate a positive emotional state.

2. Smile to the navel and form the front pakua behind the navel.

3. Fuse the senses, organs' energies, and emotions into the front pakua.

4. Form the back pakua, and collect the energy.

5. Spiral the energy or force at the front and back pakuas. Direct the spiral of energy from the two pakuas into the cauldron at the center of the body.

6. Form the right side pakua, and collect the energy.

7. Form the left side pakua, and collect the energy.

8. Spiral the force at the pakuas, direct the energy of the right and left pakuas into the cauldron, and condense the energy to create a pearl there. The pearl will shine with light and glow brighter as more energy continues to fuse from the four pakuas into the cauldron.

B. Form the Virgin Children and the Protective Animals.

1. Recheck the kidneys and their collection point. Sense the collection point and the kidneys illuminating with a bright, blue light. Feel the virtue energy of gentleness in the kidneys, and form it into a virgin boy or virgin girl. Sense the child breathing out a blue breath that changes into the form of a deer. Place the child and the deer at the kidneys' collection point.

2. Recheck the heart and its collection point. Sense the collection point and the heart illuminating with a bright, red light. Feel the virtue energy of love, joy, and happiness in the heart. Form it into a virgin child, and sense the child breathing out a red breath that changes into the form of a red pheasant. Place both in the heart's collection point.

3. Recheck the liver and its collection point. Sense the collection point and the liver illuminating with a bright, green light. Feel the virtue energy of kindness in the liver. Form it into a virgin child, and sense the child breathing out a green breath that changes into a green dragon. Place both in the liver's collection point at the right side.

4. Recheck the lungs and their collection point. Sense the collection point and the lungs illuminating with a bright, white light. Feel the virtue energy of courage in the lungs, and form it into a virgin child. Sense the child breathing out a bright, white breath that changes into a white tiger. Place both in the lungs' collection point on the left side.

5. Recheck the spleen and its collection point. Picture the collection point and the spleen illuminating with a bright, yellow light. Feel the virtue energy of fairness and openness in the spleen, and form this energy into a virgin child. Sense the child breathing out a bright, yellow breath that changes into a yellow phoenix. Place both in the front pakua.

6. Form protective rings by connecting the inner animals and virgin children in two circles. Starting from the kidneys, the virgin child and the blue deer make rings of fire to the green virgin child and dragon at the liver's collection point, to the red virgin child and pheasant at the heart's collection point, to the white virgin child and tiger at the lungs' collection point, and back to the blue virgin child and deer at the kidneys' collection point. The yellow virgin child and phoenix remain in the middle at the front pakua.

C. Call forth the Earth Force as a Protector and Source of Energy.

1. Be aware of and spiral the energy at the kidneys and their collection point. When you sense the force very intensely, project it from the collection point far out to the front of the body to attract the water element force of the Earth. When this force comes to you, and you feel it very intensely, form the image of the big, black or dark blue turtle (the Black Warrior) to capture it. Place the turtle on the back of the body as protection.

2. Be aware of and spiral the energy at the heart and the heart's collection point. When you sense the force intensely, project it from the collection point far out to the front of the body to attract the fire element force to you. When you feel this force very intensely, form

the image of the red pheasant to catch the force. Place the red pheasant on the front of your body as protection.

3. Be aware of and spiral the energy at the liver and the liver's collection point. When you sense the force very intensely, project it from the collection point far out to the front of the body to attract the wood element force. When this force comes to you, and you feel it very intensely, form the image of a green dragon to capture it. Place the dragon on the right side as protection.

4. Be aware of and spiral the energy at the lungs and the lungs' collection point. When you sense the force very intensely, project it from the collection point far out to the front of the body to attract the metal element force. When this force comes to you, and you feel it very intensely, form the image of a white tiger. Place the tiger on the left side to protect that side.

5. Be aware of and spiral the energy at the spleen and the spleen's collection point. When you sense the force very intensely, project it from the collection point far out to the front of the body to attract the Earth element force. When this force comes to you, and you feel it very intensely, form the image of a yellow phoenix. Place the phoenix in the middle of the top of the head as protection.

6. Form a ring of fire to link all the animals' forces together. Include the phoenix at the top to form a dome-like covering.

D. Circulate the Pearl in the Microcosmic Orbit.

1. Direct the pearl to the perineum by contracting the perineum, the anus, and then the back part of the anus. Move the pearl into the Microcosmic Orbit. At each point-perineum, Door of Life, T-11, C-7, back of the skull, crown, Third Eye, throat, heart, solar plexus, and navel-let the pearl illuminate with light. Build up the momentum of the pearl.

2. Bring the pearl back to the perineum, contract the perineum and back part of the anus, and bring the pearl up to the sacrum. Activate the Cranial and Sacral Pumps, and bring the pearl to the crown. Exhale through the crown and project the pearl up approximately six inches (15.23 centimeters) above the head.

a. Use your mind and the senses to move the pearl up and down. Gradually move the pearl higher to approximately twelve inches (30.48 centimeters) above the head.

b. Move it up and down using the senses to control it.

c. Move the pearl up two feet (60.96 centimeters) above the head.

d. Move it up and down again.

e. Continue to move it up to approximately your body's height above your head.

E. Form the Energy Body.

Focus your attention on forming the pearl into an energy body that looks like you, or into the perfect image you would like to have.

F. Call forth the Planets' Forces.

1. Form a new, bright, blue pearl.
2. Move the blue pearl in the Microcosmic Orbit to gain momentum.
3. Stop at the perineum, activate the Cranial Pump, and project the pearl up through the crown of the energy body as far as you can.
4. Wait for the water element force of the planet Mercury.
5. Picture the planet Mercury to capture its force. Place it on the back of the energy body to supply the force to the kidneys and to protect the back.
6. Form a new, bright, red pearl. Move the red pearl in the Microcosmic Orbit to gain momentum.
7. Stop at the perineum, activate the Cranial Pump, and project the pearl up through the crown of the energy body as far as you can. Wait for the fire element force of the planet Mars.
8. Picture the planet Mars to capture its force. Place it on the front of the energy body to supply the force to the heart and to protect the front.
9. Form a new, bright, green pearl. Move the green pearl in the Microcosmic Orbit to gain momentum.
10. Stop at the perineum, activate the Cranial Pump, and project the pearl up through the crown of the energy body as far as you can.
11. Wait for the wood element force of the planet Jupiter.
12. Picture the planet Jupiter to capture its force. Place it on the right side of the energy body to supply the force to the liver and to protect the right side.
13. Form a new, bright, white pearl. Move the white pearl in the Microcosmic Orbit to gain momentum.

14. Stop at the perineum, activate the Cranial Pump, and project the pearl up through the crown of the energy body as far as you can.

15. Wait for the metal element force of the planet Venus.

16. Picture the planet Venus to capture its force, and place it on the left side of the energy body to supply the force to the lungs and to protect the left side.

17. Form a new, bright, yellow pearl. Move the yellow pearl in the Microcosmic Orbit to gain momentum.

18. Stop at the perineum, activate the Cranial Pump, and project the pearl up through the crown of the energy body as far as you can.

19. Wait for the earth element force of the planet Saturn.

20. Picture the planet Saturn to capture the force. Place it in the middle of the top of the head of the energy body to supply the force to the spleen and to protect the center of the body.

21. Be aware of the energy of the stars and the planets and absorb their force into the energy body. Beam it down from the crown of the energy body to the crown of the physical body. Absorb the energy of the Earth into the physical body. (Fig.10.1)



***Fig.10.1** Star and Earth Energy--the Pakuas and Cauldron*

G. Transfer the Microcosmic to the Energy Body.

1. Circulate the Microcosmic in the physical body, inhale, and bring it up to the energy body.

2. Move both Microcosmic Orbits separately in the physical and energy bodies.

3. The Microcosmic Orbit can also be run together as one circuit of the energy body and physical body.

H. Form a Protective Shield and a Larger Protective Bubble around the Physical and Energy Bodies.

Form the bubble of the protective shield around the energy body. Then form another, bigger bubble to surround and protect both the energy and physical bodies and the energy body’s bubble. The large bubble surrounds you with an aura.

I. Condense and collect the Energy.

1. Condense the energy body into a pearl.

2. Absorb once more the Universal Force from above, the Earth animals’ energies, and the Earth energy from the ground under your feet. Inhale and activate the Cranial Pump. When you feel the crown point of the physical body open, draw the pearl down into the body, and run it in the Microcosmic Orbit.

3. The pearl may feel clearer now, since it has absorbed energy from the heavens and the Earth.

4. Condense the energy body’s protective shield (above the physical body and within the great bubble surrounding both) into a pearl.

5. Inhale, activate the Cranial Pump, and draw in the energy body’s protective shield. Add this energy to the pearl that is circulating in the Microcosmic.

6. The great bubble continues to provide an aura around the outside of the physical body. Condense and slowly begin to draw in through the crown the big bubble. Add it to the pearl and move it down the front channel of the Microcosmic.

7. Draw it into the navel and bring it to the cauldron. As you do so, the protective shield that continues to surround the physical body is drawn closer and tighter to the body. You are now protected from within and from without by this protective shield. It will be built upon by new pearls and additional layers of protective shields.

J. Finish the Exercise.

1. To finish, collect and condense the energy in the cauldron at the center of the body where the four pakua energies intersect.

2. End with the Chi Massage.

K. Practice Fusion Daily.

Fusion should be done each day to refine your emotional tone. This will result in the purified energy that is so essential to the higher stages of the Taoist practice. Do not rush the practice; it takes time to grow in your Fusion practice, but eventually you will see good results.

Advanced Practice Summary.

In advanced practice the mind is programed to project the power out, permitting the entire practice to happen at once.

1. Be aware of the cauldron at the center of the body. Spiral the energy using the mind and body. Use the inner eye to direct the energy along the road or pathway of the spiral. To draw the energy inward spiral very intensely at the cauldron as you also spiral the pakuas. Condense the energy into a pearl. Once the pearl is formed, you can stop spiraling. Be aware of the pearl, the four pakuas, the collection points of the organs, the senses, the emotions, and the balance of all internal energy. If the pearl formed is bright and firm, then all the internal energy is balanced and in good condition. If not, check each area to correct or adjust the imbalance.

2. Be aware of the virgin children, the animals, and the ring formed internally to protect the body.

3. Be aware of the Earth Force and the Earth animals forming the protective ring and the dome.

4. Move the pearl in the Microcosmic Orbit and project it out through the crown to form the energy body.

5. Be aware of or call forth the planets' forces and form an outer protective ring.

6. Connect with the North Star and the Big Dipper and absorb all the forces through the crown and into the energy body. Beam the forces down through the crown and into the physical body.

7. Form the energy body's protective shield and the big bubble protective shield to protect both bodies.

8. Condense the energy body into a pearl and inhale it into the physical body and down to the navel. Absorb the protective shield into the crown and bring its energy down to the navel. Absorb the big bubble into the crown and as you bring its energy down to the navel, feel the big bubble tighten around the physical body in a protective layer. Condense the energies into the cauldron.

9. Practice Chi Massage.

More Advanced Practice Summary.

1. Be aware of the pearl in the cauldron, the four pakuas, the collection points, the organs, the senses, the virgin children, and the animals. Feel centered, at peace, calm, and filled with love, joy, and confidence.
2. Use your mind and the senses to project the pearl out to form the energy body. Move the energy body as far as the lead light projects. Be aware of the planets, the stars' forces, and the protective shields. Absorb all the energy into both the energy and physical bodies.
3. Condense the energy and the protective shields, and absorb this energy into the physical body.
4. Condense the energy in the cauldron.
5. Practice Chi Massage.

Most Advanced Practice Summary.

1. Be aware of the cauldron as the center point of the body. Use the mind, eyes, head, and body to spiral. Continue to spiral and simply be aware of the four pakuas and the collection points. Spiral until you feel the pearl form. (Fig.10.2) Be aware of the pearl in the cauldron and move it into and through the Microcosmic Orbit. Project the pearl out to form the energy body. Move the energy body up as far the lead light extends.
2. Be aware of the physical body and the force around it. Be aware of the Universal Force. Absorb these energies into both the energy and physical bodies.
3. When you are ready to finish, simply condense all the energy.
4. Practice Chi Massage.



***Fig 10.2** The power of the spiral will help draw the energy into the cauldron untill the pearl forms.*

$13.95

Fusion of the Five Elements

Basic and Advanced Meditations for Transforming Negative Emotions

Mantak Chia

Illustrated by Juan Li

Fusion of the Five Elements is the first level of meditation in a Taoist practice also known as Fusion of the Five Forces in the Universe. It is the beginning of Inner Alchemy, a scientific process by which you gain control over the energies of your inner universe so that a connection can be made to the tremendous energy of the universe beyond the body. This energy becomes useful for self healing, day-to-day living and reaching spiritual goals. The Fusion meditation is the first step in learning to control the generation and flow of emotional, mental and physical energies within your body. The practice teaches you how to locate and dissolve the negative energies hidden inside your body. Using the Taoist Five Element Theory, a connection is made between the five outer senses - eyes, tongue, mouth, nose, ears - and the Five major emotions - anger, hate, worry, sadness, and fear. Once the negative emotion is identified with the organ it is stored in, it can be controlled.

The Fusion meditation shows you step by step how the negative emotions are removed from the organs. Negative emotions are neither suppressed nor expressed. Instead, their negative energy is brought to specific points in the body where it is easily neutralized, purified, and then transformed back into your original positive, creative energy. The great secret of crystallizing and storing your original positive energy in a mysterious pearl is revealed for the first time in the Fusion alchemical formula. This pearl is the essence of our life force energy, or Chi. It is central to nourishing the physical body, and later to nourishing the soul, or energy body. In more advanced Fusion practice, your soul/energy body becomes very controllable and its power can be balanced, strengthened and expanded to connect with the essence of the Earth and Star energies. The Fusion of 'the Five Elements practice is the essential first step toward complete emotional and spiritual development. In this useful and informative work, Master Mantak Chia leads you step by step to becoming an emotionally balanced, controlled and strong individual while offering you the key to an Immortal existence.

ISBN 0-935621-18-0

9 780935 621181

Universal Tao Publications

Sealing of the Five Senses

Opening the Crystal Room

Mantak Chia

Sealing of the Five Senses

Opening the Crystal Room

Mantak Chia

Edited by:

Saumya Comer

Editor: Saumya Comer

Assistant Editors: Lee Holden

Illustrations: Udon Jandee

Production Manager: Saniem Chaisarn

Final Editing: Jean Chilton

Editorial Assistance: Daniel George Dubie

Project Manager: W.U. Wei

© North Star Trust

First published in 2005 by:

Universal Tao Publications
274 Moo 7, Luang Nua,
Doi Saket, Chiang Mai 50220 Thailand
Tel: (66)(53) 495-596 Fax: 495-853
Email: ip@universal-tao.com
Web Site: universal-tao.com

Manufactured in Thailand

ISBN: 0-935621-51-2

All rights reserved. No part of this booklet may be used or reproduced in any manner whatsoever without the express written permission from the author, with the exception of brief quotations embodied in critical articles and reviews. Anyone who undertakes these practices on the basis of this booklet alone, does so entirely at his or her own risk.

Contents

Sealing of the Five Senses 1
- A. First Formula Strengthening the Senses 3
- B. Practice Formula Two 9
- C. Practice Formula Three Sealing of the Five Senses.. 12
- D. Practice Formula Four Sealing of the Five Senses 17
- E. Practice Formula Five Sealing of the Five Senses 28
- F. Practice Formula Six Sealing of the Five Senses 33
- G. Practice Formula Seven Sealing of the Five Senses 36
- H. Practice Formula Eight Sealing of the Five Senses 39

The meditations, practices and techniques described herein are ***not*** intended to be used as an alternative or substitute for professional medical treatment and care. If any readers are suffering from illnesses based on mental or emotional disorders, an appropriate professional health care practitioner or therapist should be consulted. Such problems should be corrected before you start training. This booklet does not attempt to give any medical diagnosis, treatment, prescription, or remedial recommendation in relation to any human disease, ailment, suffering or physical condition whatsoever.

Sealing of the Five Senses

Our senses are like antennas which receive waves of vibration, sound and light that come to us. If that wave makes sense, our brains will start to think. Thinking consumes more energy than any other bodily activity. As humans we can not stop thinking, looking and listing nor stop fantasizing. This sensory-linked brain function in reaction to the external world is known as the monkey mind.

Our mind connects with the heart. When the mind is disturbed, the heart too will become disturbed. The good-minded good heart is the compassionate heart (harmony), therefore its good intention connects to the earth and nourishes it. When the wood meets the earth, the wood will grow. When the water meets the earth, the water will gather. When the metal meets the earth, the metal will condense. When the fire meets the earth, the fire will tone down.

If we can make the senses stronger, and seal the senses with external and internal force, we can accumulate profound energy.



Fig. 1 *Waves of Vibration Coming into Senses*

1. First, we will strengthen the senses.
2. Second, we will make the connection.
3. Third, we will seal the senses.

The formula of Sealing the Five Senses effects a literal transmutation of the warm current or Chi into spiritual energy or energy of the soul. To do this, we must seal the five senses, for each one is an open gate of energy loss. The power flows out from each of the sense organs unless there is an esoteric sealing of these doors of energy. They must release energy only when specifically called upon to convey information.

Abuse of the senses leads to far more energy loss and degradation than people ordinarily realize. Examples of misuse of the senses are as follows: if you look too much, the seminal fluid is harmed; listen too much the mind is harmed; cry too much, and the blood is harmed; have sexual intercourse too much, and the marrow is harmed.



***Fig. 2** Sense Energy Turning inward. Content Person sitting in Meditation. Vibration turned Inward.*

A. First Formula Strengthening the Senses

The first step of strengthening our senses is very important. When the senses are strengthened we will be less affected by the stimuli coming from the outside world as criticism or praise. This strength leads to a connection with our center, where the mind becomes still, and the thoughts rest. A great deal of energy is spent thinking warring. Sealing the senses conserves this energy to be used for spiritual development.

Turning the senses inwardly to the center of the brain and down to the navel, and use the three cauldron coupling to help the suck in the natural and universal force.

1. The left ear corresponds to the metal element force.
2. The right ear corresponds to the wood element force.
3. The chin and the mouth correspond to the water element.
4. The nose corresponds to the earth star; this will tonify the earth.
5. The left eye corresponds to the sun.
6. The right eye corresponds to the moon.
   (Raise the water and lower the fire, and let it couple on the tip of nose.



Fig. 3 *Elements Connected to Senses*

Practice Formula One

a. Be aware of the left ear and the metal force.
b. Be aware of the right ear and the wood force.
c. Draw these two forces together into the crystal room, combine them into the fire force.



Fig. 4 *Metal and Wood Transforming to Fire Crystal Room*

d. Be aware of the mouth and breath into the throat center and the lower abdominal suction and the tiger and the dragon breath to create the suction, and feel the Chi entering the mouth and gathering the water force into the Chi Ball.

e. Create the collection points to contain the water in the mouth.



Fig. 5 *Coupling of Five and Water*


Exhale
Press

Fig. 6 *Dragon and Tiger breath. Exhale and compress the Chi down to lower abdomen.*

f. Let the water rise up, and lower the fire down and couple at the tip of the nose. Turn the awareness inward and feel the three-cauldron coupling at the same time.



Fig. 7 *Coupling of Five and Water*

g. Let it steam to the crystal room. The lower cauldron steams to the organs and the glands.



Fig. 8 *Steam to the Crystal Room*

h. Feel the four cauldrons couple at the same time, the normal breath stop and the true breath begin. Let the skin start to breath first, and the bones in the arms and the legs.



Fig. 9 *Skin, Bones Breathing*

i. Suck in the crown and expand to the nature and the universe. Suck in the mideyebrow, the third eye, the palms the soles of the feet, the perineum, the sacrum and the Door of Life. Eventually the whole body is breathing.


Crown Suction
Mideyebrow Suction
Sole of Foot Suction
Palm Suction

Fig. 10 *Whole Body Breathing*

B. Practice Formula Two

a. Be aware of the left eye as sun power.

b. Be aware of the right eye as moon power.

c. Combine these two forces into the bridge of the nose and let them become fire force.



Fig. 11 *Combine to Nose*

d. Be aware of the Chi in the mouth, use the throat center and the lower abdominal and the Tiger and Dragon breath to create the suction to breathe in the external Chi to form a chi ball in the mouth.

e. Raise the water and lower the fire and let them couple at the tip of the nose.



Fig. 12 *External Chi*

f. Feel the four cauldrons couple at the same time, the normal breath stop and the true breath begin. Let the skin start to breath first and the bones in the arms and the legs.


Breath Steps
Skin Breathing
Bones Breathing

Fig. 13 *Skin and Bones start to breathe.*

g. Suck in the crown and expand to the nature and the universe. Suck in the mideyebrow, the third eye, the palms the soles of the feet, the perineum, the sacrum and the Door of Life. Eventually the whole body is breathing.


Expand to Universe
Suction in the Crown
Suction in the Mideyebrow
Sacrum-Hole Suction

Fig. 14 *Eventually the whole body is breathing.*

C. Practice Formula Three: Sealing of the Five Senses

a. The left ear connects to the left kidney, known as the true kidney, the activator of the stored energy of the kidneys.



Fig. 15 *Stored Energy of the Kidneys*

b. The right car connects to the right kidney, which is yin, and is represented by a Weaving Maiden who stores the essence of the sexual energy (sperm and ovum), as well as the inner yang that attracts the active yang known as the Gate of Life.


Weaving Maiden
Inner Yang
stores the essence
of the sexual energy

Fig. 16 *Weaving Maiden who stores the essence of the sexual energy.*

c. Be aware of the left kidney as fire force and let it gradually rise up to the left ear, creating a collection point to contain the fire force.



Fig. 17 *Left ear creating a collection point to contain the fire force.*

d. Be aware of the lower cauldron. Feel the fire start to warm the abdomen. The fire and steam power goes down to the sexual organs to transform the sexual energy into Chi or arousal sexual energy. Let this energy rise to the right kidney to activate the stored essence of sexual energy, the inner yin. Feel the connection of the right kidney to the right ear and let the essence yin energy rise up the ear. Create a collection point to contain the energy.



Fig. 18 *Create a collection point to contain the energy.*

e. Let the left and right ear, fire and water couple in the crystal room (middle of the ear).



Fig. 19 *Fire and water couple in the crystal room*

f. Be aware of the mouth and gather the water force into a Chi Ball.

g. Let the water and fire couple at the nose, the earth.



Fig. 20 *Connecting to Earth*

D. Practice Formula Four: Sealing of the Five Senses

1. Clean out the Thrusting Channels. Be aware of the sole of the feet and feet, the universe force and earth force, rising up to the left side of the sexual organ and up the left thrusting channel and up to the left side of the crown.
2. Activate the Sexual Energy in the Lower Tan Tien.



Fig. 21 *Activate Sexual Energy*

3. Turn the Wheel.
    a. Up the spine to the T-11 and then down to the Lower Tan Tien.
    b. Up the spine to the C-7 and then down to the solar plexus.
    c. Up the spine to the brain and then down to the heart.



Fig. 22 *Turn the Wheel*

4. Build the Aura
    a. Breathe red mist into the heart.
        1. Breathe out any gray color.
        2. From the heart, send out the red mist to create an aura around the body.


Breathe Red Light
Exhale Gray Color

Fig. 23 *Breathe into the heart.*

b. Breathe yellow mist into the spleen.

1. Breathe out any gray color.
2. From the spleen, send the yellow mist to all over the body and send radiance out around the body.
3. From the mouth, breathe out the yellow mist to create an aura.



***Fig. 24** Breathe into the Spleen.*

c. Breathe white mist into the lungs.

1. Breathe out any gray color.
2. From the lungs, send the mist to the nose and out the nose and the skin.
3. From the nose, breathe out the white mist to create an aura.



Fig. 25 *Breathe into the Lungs.*

d. Breathe blue mist into the kidneys.

1. Breathe out any gray color.
2. From the kidneys, send the mist to the ears and send radiance out for whole body radiance.
3. From the ears, breathe out the blue mist to create an aura.



Fig. 26 *Breathe into the Kidneys.*

e. Breathe green mist into the liver.
  1. Breathe out any gray color.
  2. From the liver, send the mist to the eyes.
  3. From the eyes, breathe the green mist out to create an aura.



Fig. 27 *Breathe into the Liver.*



Fig. 28 *Finish building the Aura.*

4. Bring the sun down to the left eye to be the fire.
5. Bring the moon down to the right eye to be the water.



Fig. 29 *Sun and Moon down to the Eyes*

6. Bring the fire from the left eye to the bridge of the nose.
7. Bring the water from the right eye to the mideyebrow.


Mideyebrow
Right
Left
Fire
Water
Bridge of the Nose

Fig. 30 *Sun and Moon down to the Eyes*

8. Start the coupling (this differs from practice formula#2 where we just combined the sun and moon to create one fire energy, now we couple two different energies).
9. The steam will come out the third eye.



Fig. 31 *Combine the Sun and Moon*

10. Gather the sexual Energy from the sexual organs and bring it to the collection point in the mouth.



Fig. 32 *Gather the Sexual Energy.*

11. The steam produced from the sun and moon coupling will now become the fire for the coupling at the tip of the nose. Bring the fire energy down to the upper lip.



Fig. 33 *Energy down to Upper Lip.*

12. Bring the water energy from the mouth up to the bridge of the nose.



Fig. 34 *Energy up to the bridge of the nose*

13. Start the Coupling at the tip of the nose.



Fig. 35 *Coupling Tip of the Nose*

14. This coupling does not produce steam, yet you will clearly feel the suction.
15. Let the fire cool.
16. Bring the energy down to the Lower Tan Tien.

E. Practice Formula Five: Sealing of the Five Senses

The harmonizing of the four forces (stopping the draining of the essence)

1. When the eyes (green dragon, east, wood) are not seeing, the eternal soul will stay in the liver. Turn the eye power inward.
2. When the ears (Tortoise, north, water) are not hearing, the sexual essence stay in the kidneys. Turn the ears inward.
3. When the tongue (red pheasant, south, fire) is not speaking the spirit stays in the heart.
4. When the nose (white tiger, west, metal) is not smelling, the corporal soul (pui) stays in the lungs. Holding the tongue power inward regulates the breath.
5. When all four are not moving, these four essences will harmonise at the earth and will be nourished, strengthened, and sealed.



Fig. 36 *Five Sealing of the Five Senses*

When all the four essences are not draining out, sexual essence - water, spirit - fire, eternal soul - wood, and the corporal soul (pui) - metal all will gather at the earth, at the tip of the nose.

When there is no desire in the heart - fire is not activated, the green dragon in the liver will sound, the red pheasant will close its wings, and the sexual essence stays and gathers. Wood burns to become fire, and thus gives birth to the heart energy. The white tiger (Lung) gives energy to the water (kidney) which is the life essence (body). If we do not drain out the life essence (take care of our body) the white tiger will sound, the wind will start to move. The tortoise will stay dormant, the sexual essence will be conserved and stay in. When the sexual essence and the Chi stays in us, the metal, wood, water, fire forces will harmonize together and not leak to the earth. So the sexual essence, spirit, eternal soul will gather in the good intention.

1. Clean out the Thrusting Channels.
2. Activate the Sexual Energy in the Lower Tan Tien.
3. Turn the Wheel.
    a. Up the spine to the T-11 and then down to the Lower Tan Tien.
    b. Up the spine to the C-7 and then down to the solar plexus.
    c. Up the spine to the brain and then down to the heart.
4. Build the Aura
    a. Breathe red mist into the heart.
        1. Breathe out any gray color.
        2. From the heart send out the red mist to create an aura around the body.
    b. Breathe yellow mist into the spleen.
        1. Breathe out any gray color.
        2. From the spleen, send the yellow mist to the nose.
        3. From the nose, breathe out the yellow mist to create an aura.
    c. Breathe white mist into the lungs.
        1. Breathe out any gray color.
        2. From the lungs, send the mist to the nose.
        3. From the nose, breathe out the white mist to create an aura.

d. Breathe blue mist into the kidneys.
   1. Breathe out any gray color.
   2. From the kidneys, send the mist to the ears.
   3. From the ears, breathe out the blue mist to create an aura.

e. Breathe green mist into the liver.
   1. Breathe out any gray color.
   2. From the liver, send the mist to the eyes.
   3. From the eyes breathe the green mist out to create an aura.



Fig. 37 *The Pill Connecting to the Dipper*

4. Send out the pill to connect with the Big Dipper.
5. Bring the Big Dipper down and connect it to the left and right temples, left and right mastoid, the chin, the base of the skull, and the crown.
6. Bring the North Star into the crystal room.
7. See the Big Dipper full of violet light; that light is now pouring into your crown.

8. Draw the Sun down to the left eye to collect the fire energy.
9. Draw the Moon down to the right eye to collect the water energy.
10. Bring the fire to the bridge of the nose.
11. Bring the water to the mideyebrow.
12. Draw the fire and water together and begin the coupling and simmer slowly and send the steam up to the third eye.
13. Draw the fire energy up from the left kidney to the left ear collection point.
14. Draw the Sexual Energy up from the sexual organs and the right kidney to the right ear collection point.



Fig. 38 *Sexual Energy Rising Up*

15. Draw the fire and water into the crystal room and begin the coupling. The steam produced here will become the fire for the next coupling.
16. Bring the Sexual Energy up to the Pineal Gland and allow it to drip down to the mouth. Mix it with the Saliva and fill the mouth with the sexual energy.
17. Draw the Fire Energy down from the Crystal Room to the upper lip.
18. Draw the Water Energy up from the mouth to the bridge of the nose.
19. Couple at the tip of the nose.
20. Be aware of the ears. Feel the blue energy turning into the tortoise in each ear to seal and protect the ears.
21. Be aware of the nose. Feel the white energy turning into the white tiger in the nose to seal and protect the nose.
22. Be aware of the eyes. Feel the green energy turning into the green dragon in the eyes to seal and protect the eyes.
23. Be aware of the tongue. Feel the red energy turning into the red pheasant at the tongue and in the mouth to seal and protect them.
24. Draw the green, wood energy of the eyes down to the tongue (fire) and combine the two to create one fire energy. Send the fire to the crystal room.
25. Draw the white, metal energy from the nose over to the ears (water) and combine the two to create one water energy. Send the water to the crystal room.
26. Start the coupling in the crystal room.
27. Slowly simmer for a long time.
28. Empty your mind into the Lower Tan Tien anytime thoughts arise. Feel the stillness of your senses. Feel how they are sealed.
29. Slowly let the fire cool down.
30. Gather the energy in the Lower Tan Tien.

F. Practice Formula Six: Sealing of the Five Senses

1. Clean out the Thrusting Channels.
2. Activate the Sexual Energy in the Lower Tan Tien.
3. Turn the Wheel.
    a. Up the spine to the T-11 and then down to the Lower Tan Tien.
    b. Up the spine to the C-7 and then down to the solar plexus.
    c. Up the spine to the brain and then down to the heart.
4. Build the Aura
    a. Breathe red mist into the heart.
        1. Breathe out any gray color.
        2. From the heart send out the red mist to create an aura around the body.
    b. Breathe yellow mist into the spleen.
        1. Breathe out any gray color.
        2. From the spleen, send the yellow mist to the nose.
        3. From the nose, breathe out the yellow mist to create an aura.
    c. Breathe white mist into the lungs.
        1. Breathe out any gray color.
        2. From the lungs, send the mist to the nose.
        3. From the nose, breathe out the white mist to create an aura.
    d. Breathe blue mist into the kidneys.
        1. Breathe out any gray color.
        2. From the kidneys, send the mist to the ears.
        3. From the ears, breathe out the blue mist to create an aura.
    e. Breathe green mist into the liver.
        1. Breathe out any gray color.
        2. From the liver, send the mist to the eyes.
        3. From the eyes, breathe the mist out to create an aura.
        5. Send out a pill to connect with the Big Dipper.

6. Connect the Big Dipper to the various points on the head (L&R mastoid, L&R temples, chin, base of skull, and crown), bring the North Star to the crystal room.
7. See the Big Dipper pouring violet light down into your crown.
8. Wash the whole body and especially the marrow with the violet light.
9. Bring the left kidney up to the left ear and make a collection point in the ear for the fire energy.
10. Bring sexual energy from the sexual organs and up from the right kidney to the right ear. Make a collection point in the right ear for the water energy.
11. Bring and fire and water energies into the crystal room.
12. Start the coupling in the crystal room.
13. Bring the Sun down to the left eye to collect the fire energy.
14. Bring the Moon down to the right eye to collect the water energy.
15. Bring the fire energy from the left eye to the bridge of the nose.
16. Bring the water energy from the right eye to the mideyebrow.
17. Bring the fire and the water together and start the coupling.
18. Draw the sexual energy up to the collection point in the mouth.
19. The steam from the crystal room coupling will now be used as the fire energy for the coupling at the tip of the nose. Bring the fire energy down to the upper lip.
20. Bring the water energy from the mouth to the bridge of the nose.
21. Bring the water and fire together at the tip of the nose and start the coupling.
22. Be aware of all three couplings simultaneously, the steam at the crystal room will form a pearl and open the third eye.

23. Send the liver energy out to draw in the green planet, Jupiter.
24. Bring Jupiter in to seal and protect the eyes.
25. Send the heart energy out to draw in the red planet, Mars.
26. Bring Mars in to seal and protect the tongue (mouth).
27. Bring the eyes down to the mouth and combine the eyes and tongue to create one fire energy.
28. Draw the fire energy up to the crystal room.
29. Send out the kidneys to draw in the planet Mercury.
30. Bring Mercury in to seal and protect the ears.
31. Send out the lungs to draw in the planet Venus.
32. Bring Venus in to seal and protect the nose.
33. Bring the ears to the nose and combine them to form one water energy.
34. Draw the water energy up to the crystal room.
35. Start the coupling of the fire and water at the crystal room.
36. Let go of all thoughts, send them down to the Lower Tan Tien.



Fig. 39 *The Planets connect to the Organs.*

37. Feel the stillness of all the essences as they are not being used to spend energy. Feel their energy staying with you. (eternal soul, spirit, corporal soul and the sexual essence)
38. Set the fire cool down.
39. Bring the energy down to the Lower Tan Tien.

G. Practice Formula Seven: Sealing of the Five Senses

1. Do the Bellows Breathing.
2. Connect with the Lower Tan Tien.
3. Build the Aura:
    - a) Red mist from the heart.
    - b) Yellow mist from the spleen.
    - c) White mist from the lungs.
    - d) Blue mist from the kidneys.
    - e) Green mist from the liver.



Fig. 40 *Big Dipper and North Star*

4. Send out the pearl to connect to your own personal star and to attract the Big Dipper.
5. Look for the light.
6. Draw the Big Dipper in and connect it to the head (L&R temples, L&R mastoid, chin, base of the skull, and the crown). Bring the North Star to the crystal room.
7. See the Big Dipper pouring out violet light down into your crown and through your whole body. Wash your body in the violet light and especially the marrow.
8. Feel your body so full of violet light it starts to overflow and create and aura around your whole body.
9. Be aware of the coupling at the mideyebrow, crystal room, and the tip of the nose.
   Give yourself plenty of time to feel the suction in each place.
10. Now expand your mind outward to the constellations.



Fig. 41 *Violet Light and Aura*

11. Feel the connection of the constellations to your organs to the elements.
    a) The east constellations connect to the liver (wood).
    b) The south constellations connect to the heart (fire).
    c) The west constellations connect to the lungs (metal).
    d) The north constellations connect to the kidneys (water).
    e) The crystal room is in the center.
12. Combine the South Constellation (fire) and the East. Constellation (wood) to create one fire energy.
13. Combine the North Constellation (water) and the West Constellation (metal) to create one water energy.
14. Couple the two at the crystal room.
15. Now, feel your aura as another layer of your skin. Feel it move in and out with each breath. Take in the refined energies from the constellations.
16. Let the fire cool.
17. Gather the energy at the Lower Tan Tien.


NORTH
PERSEUS
CAMELOPARDALIS
LITTLE DIPPER
DRACO
BIG DIPPER
COMA BERENICES
CORONA BOREALIS
Arcturus
Alphecca
EAST
WEST
ARIES
SEPT
ANDROMEDA
PEGASUS
CEPHEUS
MARS
AUG 28
LYRA
HERCULES
OPHIUCHUS
AQUILA
SAGITTARIUS
SATUM
SCORPIUS
LIBRA
VIRGO
CAPRICORNUS
CORONA AUSTRALIS
SOUTH

Fig. 42 *Star Constellations*

H. Practice Formula Eight: Sealing of the Five Senses

1. Clean the Thrusting Channels.
2. Turn the Wheel.
3. Create the Auras.
4. Send a pill out to connect with the Big Dipper.
5. Connect with the Big Dipper at the L&R Mastoids, L&R Temples, Base of the skull, Chin, and Crown. Feel the Dipper pouring violet light into your crown and washing your whole body.
6. Create the 3 cauldrons (Bridge of nose, Crystal Room, Tip of nose).
7. Feel your aura as an extra layer of skin. Feel it move in and out with each breathe. Feel your breathe drawing in chi through your skin to your whole body.
8. Be aware of the Planets and Animals protecting and sealing your senses.



Fig. 43 *Energy Body Going Out and Growing.*

9. Shoot your energy body out and make yourself very large.
10. Connect with the constellations: Liver, Wood, East
    - Heart, Fire, South
    - Lungs, Metal, West
    - Kidneys, Water, North
11. Combine the East and South Constellations (wood and fire) to create one fire energy.
12. Combine the West and North Constellations (metal and water) to create one water energy.
13. Start the coupling and feel the vast amounts of energy.
14. Beam the energy down to your crystal room, to your heart and see the rainbow beams coming out from your heart to the rest of the body wherever they is needed.
15. Bring your awareness to the Lower Tan Tien and start the coupling there.
16. Bring the energy from above, now into the Lower Tan Tien.
17. Use this energy to heal any part of the body or mind that is in need.
18. Slowly allow the fire to cool.
19. Gather the energy in the Lower Tan Tien.



Fig. 44 *Rainbow Beams Healing Body*

Notes:

1) The laboratory, inside and outside. The microcosm and the macrocosm.
2) Clearing the trusting channel.
3) Turning the wheel.
4) Building the aura.
5) Breathing.
6) Connecting to the Big Dipper.
7) Sun and Moon.
8) Kidney energy, left is fire essence, right is water essence. Ear collection.
9) Mixing and collecting the water in the mouth.
10) Section on coupling.
11) Energy from the four constellations, violet light into the body, North Star.
12) Sealing the senses with animals or planets.
13) Beginning and ending the meditation.
14) Energies of the organs (hun, po, shen, yi,…).

Master School

of the Healing Tao, Tao Yoga,
Universal Healing Tao Center
at Tao Garden Health Spa & Resort

For Worldwide of North & South America, Europe & Asia information
For Center, Courses, Books, Product, Retreat and
other Resources Contact:

Universal Healing Tao Center
274 Moo 7, Luang Nua, Doi Saket, Chiang Mai, 50220 Thailand
Tel: (66)(53) 495-596 Fax: (66)(53) 495-852-3
Email: ***universaltao@universal-tao.com***
*Website:****www.universal-tao.com***

For ***Retreats and Health Spa information***

Tao Garden Health Spa & Resort
Emails: ***info@tao-garden.com*** *and* ***taogarden@gmx.net***
Website: ***www.tao-garden.com***

For ***Products Order***

Email: ***orders@universal-tao.com***

Tao Garden Health Spa and Resort is Mantak Chia's home, school and training center. The Resort is a perfect place to heal, relax and get away from the pressures of every day life for groups and individuals. Please look into our Web Site: ***www.tao-garden.com***

*Good Chi * Good Heart * Good Mind*

The Universal Healing Tao is not and cannot be responsible for the consequences of any practice or misuse of the information in this booklet. If the reader undertakes any exercise without strictly following the instructions, notes, and warnings, the responsibility must lie solely with the reader.

$6.95

Sealing of the Five Senses

Opening the Crystal Room

Mantak Chia

Illustrations by Udon Jandee

Sealing of the Five Senses

In this booklet for the first time ever Master Chia has revealed the final level of the Immortal Tao Practices of the Universal Tao System. You can divide your practice into several sections starting with the Three Levels of Kan & Li to set up the alignment of the body for the Opening of the Crystal Room in the Sealing of the Five Senses practices. Your training should be progressive; that is, once you have mastered one section, you can progress on to the next. Be sure to spend at least one or two weeks on each section as shown in this booklet, allowing enough time to thoroughly master each part before adding on the next section. Remember that you should always do the Chi Kung Warmups before going on into the meditation; it is very important to loosen the spine before meditation that helps your focus.

In this booklet we have divided the entire Microcosmic Orbit practice into Eight Formulas: Strengthening the Senses, Activating Sun & Moon, Connecting Senses to Organs, Activating Thrusting Channels, Opening the Virtuous Animals, Clearing the Conception Vessel with the Three Tan Tiens, Clearing the Planets, Building the Aura and Connecting with the Big Dipper and North Star. This booklet explains and reveals how to activate the Sealing of the Five Senses by spiraling, touching, coloring and small air sipping techniques.

This booklet is designed so you can use it to do your practice at your home or a cave anywhere in the world. We are happy to welcome you to the Advanced Level of the Universal Tao System and to join the Universal Tao family as a Advanced practitioner.

ISBN 0-935621-51-2

9 780935 621518

Universal Tao Publications
274 Moo 7, Luang Nua, Doi Saket,
Chiang Mai 50220, Thailand
Tel: (66)(53) 495-596 Fax: 495-852
Email: ip@universal-tao.com
Web Site: www.universal-tao.com



Lesser Kan and Li

Enlightenment and Birth of the Immortal Fetus

Mantak Chia

Lesser Kan and Li

Enlightenment and Birth of the Immortal Fetus

Mantak Chia

Edited by:

Colin Campbell

Editor: Colin Campbell

Illustrations: Juan Li, Udon Jandee

Computer Graphics: Saisunee Yongyod

Final Editing: Jean Chilton

Final Layout: Siriporn Chaimongkol

Production Manager: Saniem Chaisarn

Project Manager: W.U. Wei

© *North Star Trust*

First published in 2002 by:

Universal Tao Publications
274 Moo 7, Luang Nua,
Doi Saket, Chiang Mai 50220 Thailand
Tel: (66)(53) 495-596 Fax: 495-853
Email: universaltao@universal-tao.com
Web Site: universal-tao.com

Manufactured in Thailand

ISBN: 0-935621-45-8

All rights reserved. No part of this booklet may be used or reproduced in any manner whatsoever without the express written permission from the author, with the exception of brief quotations embodied in critical articles and reviews. Anyone who undertakes these practices on the basis of this booklet alone, does so entirely at his or her own risk.

Contents

Taoist Cosmology 1
North Star and Big Dipper 1
Nine Sacred Mountains 3
Nine Palaces 6
Darkness Practice 13
Big Dipper Practice 13
Nine Palaces Practice 21

Preparations for Lesser Kan and Li:
Fusion of Five Elements/Creation Cycle 27
Foundations of Spiritual Practice 27
Kan and Li Characteristics 28
Kan: Lead, True Sense, Life Essence, Orgasm Energy 30
Li: True Mercury, Spiritual Essence,
the Heart of Compassion 31
Afternoon or Evening Meditation 32
A. Reversing the Hot and Cold Energy 32
B. Steaming the Glands and Organs.............................. 34
C. Spinal Cord Steaming 35
D. Lymphatic System 36
E. Nervous System/Spine 37
F. Thymus/Pituitary/Pineal 38
G. Opening the Twelve Channels 39
H. Increasing the Pulses 51
I. Inner Eye 52
J. Self Intercourse 53
K. Virtuous Animal Pure Inner Child and
Planet Protection 54
L. Gather the Pill 55
M. Transfer of the Organ's Essence................................ 56
N. Ending the Meditation: Turning the Wheel.................. 57

The meditations, practices and techniques described herein are ***not*** intended to be used as an alternative or substitute for professional medical treatment and care. If any readers are suffering from illnesses based on mental or emotional disorders, an appropriate professional health care practitioner or therapist should be consulted. Such problems should be corrected before you start training. This booklet does not attempt to give any medical diagnosis, treatment, prescription, or remedial recommendation in relation to any human disease, ailment, suffering or physical condition whatsoever.

Taoist Cosmology

North Star and Big Dipper

Taoists regard the three largest known stars – Polaris (the North Star), Thuban, and Vega – as the collective center of our galaxy (Fig. 1). The earth's axis shifts toward a different one of these stars every 2,150 years as a result of the gravitational pull from the sun and moon. The axis currently tilts toward the North Star, which is therefore referred to as the Pole Star. In other words, if one were to observe the sky from the North Pole, the entire galaxy would appear to be moving around the North Star. As the earth's axis is influenced by its mass, the North Star controls the earth's energy fields, thereby affecting our health and emotional states.

The three stars are known as the Violet Stars because they emanate violet rays throughout the galaxy, which affect every living cell of nature on our planet. Taoists believe that a human's heart tilts 45 degrees toward the North Star, just as the earth tilts 23.5 degrees toward it to receive its energy. They also believe that every planet in the galaxy tilts toward these Violet Stars in the same way, and that the North Star is presently controlling them as well (Fig. 2).



Fig. 1. *Violet Stars*


Axis of Rotation
23.5°
Sun
Orbital Plane

Fig. 2. *Earth tilts 23.5 degrees towards the North Star.*



Fig. 3. *Infra-red emanations of the Big Dipper*

The Big Dipper revolves around the North Star, as do other constellations, reflecting the earth's seasonal changes. The Big Dipper is a major source of red and infra-red light, or radiant energy (Fig. 3). Taoists believe that the cup of the Big Dipper gathers all the violet light from the universe. The emanation of infra-red light of the Big Dipper, combined with the violet rays of the Violet Stars (especially Polaris), has a positive, nurturing effect upon the bodies and minds of those who know how to access it. Taoists believe that the Violet Stars, the Southern Cross constellation, and other constellations form the "Gates of Heaven." All living things must pass through these gates to return to their source of origin, the Wu Chi, which is the state of oneness with the Tao.

Taoists believe that the soul and spirit come from the stars and ultimately must return to them to find their origins. To do this, one must first gather and refine the energies of soul and spirit until they are as pure as the stars, and eventually as pure as the Original Force. This is the way to achieve oneness with the Tao. The first step is to refine the force internally while practicing detachment from worldly things. This helps to break the bonds that hold us to this world. The second step is to draw in the forces of the planets to enhance our own internal force. This gives us spiritual power in the form of energy to use as fuel for travel to the planets, the constellations (especially the Big Dipper), and finally to the North Star, which points to Heaven. Taoists refer to this process of absorbing, transforming, and combining our soul and spiritual energies as "marrying the force," which means that we purify our energies to merge with the stellar forces.

Nine Sacred Mountains

In the Taoist tradition, the human body is a microcosm of the natural world. Our physical anatomy is an inner landscape with its own rivers, forests, mountains, and lakes that reflect their harmony with the outer landscape of the planet Earth. Fig. 4 is an ancient rendering of the inner alchemy practice of the Tao, probably originally drawn by a highly achieved Taoist from China's Tang Dynasty period (7th century C.E.). These mountain peaks function as funnels guiding Universal Energy downward. This energy is then concentrated in the mountain caves. Taoist adepts go to these caves for initiation. In the human head there are nine different energy centers (peaks or points), which are able to extend to Heaven to connect to the Cosmos. The brain marrow cavities, as well as the various energy centers of the body, are like caves in a mountain in which you can concentrate, store, and transform energy.

(16) Top of the Great Peak is located at the back of the head. When we tilt our head and push our chin back, our head reaches its highest point. This peak connects the North Star to the Pineal Gland; it is where we receive the descending Universal Energy.

(17) High Place of Many Veils lies between the Muddy Pool and the Great Peak. It is where the spirit and soul bodies can leave and enter in horizontal flight.

(18) Muddy Pool is located in the center of the crown (Bai Hui or the hundredth meeting point). When it is open it feels like soft mud. This crown point connects the Big Dipper to the Hypothalamus Gland. It is through this center, which functions as a two-way street, that you can project your energy (soul or spirit) upward or receive the energy flowing downward.

(19) House of Rising Yang is the third eye. Located slightly above the middle of the forehead, this center is able to receive the energies of the sun and moon, which it uses to project the soul and spirit bodies into space.

(20) Nine Sacred Realms are directly connected to the mid-eyebrow and have a close connection to the Pituitary Gland. This center is used to receive the Cosmic Force and to launch the soul and spirit bodies into the earthly or human plane for traveling.

(21) Immortal Realm is located in the center just in front of the crown point. It is here that our energy is able to make a connection with the heavens to draw down even more powerful Universal Energies.


16. Top of Great Peak
18. Muddy Pool

Fig. 4. *On the left, an ancient rendering of the inner alchemy practice of the Tao. On the right, two of the nine mountains (16 and 18) correspond to Nine Palace points in the brain.*

Nine Palaces

Nine is one of the most commonly used numbers in Taoism being the highest cardinal order in numerical calculation. Lao Tzu once referred to a nine-story-building rising from a clod of earth. A nine-story-building has both architectural significance and spiritual implication. The architectural significance is based upon the order of nine, which implies the highest structure of mental calculation and manipulation. In Chinese architecture, the steps and stories of a building are designed within the function of nine. The nine-story-building refers spiritually to the nine mountain-like palaces crowning the brain (Fig. 5). The cortex will gather all the elixir-making fluid needed for crystallizing into mystic elixir. Lao Tzu's statement also refers to the nine-story tower of vocal cords.

In Chinese, nine means literally the change of yang, which depicts the crawling position and extreme end. This nine-yang is the highest order in heaven and on earth, and it is the power representation of all. Beginning from nothing (zero), at nine we reach the peak stage of performance and begin to return to the original state of inactivity, for either a new beginning or a complete change. As life evolves and changes, there will be nine significant crises to be conquered. These can be referred to as the crises of merging within the structural and dynamic trinity. The nine crises determine nine deaths of old conditioning and established habits that one must walk through. Nine deaths bring about the final new birth, or the returning of pure spirit. When a person consciously dies nine times, the last death must be the spiritual birth of self into cosmic void.

In the beginning of life, we have nine holes that open and close to life in the body: the life of breath, love, and harmony. Seven of these are charged by seven powers of light. The eighth and ninth discharge the water and concrete wastes externally, or internalize the thrusting power of spirit and its mating partner, the sexual fluid, or the holy water in its earthly matured form. Among these nine holes, two form visual receptors and process the maximum on the information highway. As the receptors collaborate with the visual center in the rear of the brain, the neutralized energy activates the single most powerful interior organ: the pineal gland (Fig. 6).


内經圖
INNER ALCHEMY OF THE TAO

Fig. 5. *In Taoist Inner Alchemy, nine mountain-like palaces crown the brain.*



Fig. 6 *Brain includes the organs: cerebellum, thalamus, hypothalamus, pineal gland, pituitary gland.*

The pineal gland stands side by side with the limbic system and helps the cerebral-spinal-abdominal fluid to form the whitish matter by releasing melatonin and other chemicals. Melatonin is the essential substance required to maintain the hibernation state where spiritual consciousness sustains a peaceful, healthy, loving, and long life. The spiritual vitality producing the biological Jing will be preserved. The person then retains a child-like biological condition where no matured melatonin is wasted in biological continuation. When this substance works together with the yellow marrow in the bone, the reddish firing reaction of the biological process will be converted into a gentle cooking interaction between the holy water and light.

The sacred water refers to the inner fluid that is responsible for producing bone marrow and other bodily fluids. When the light activates this sacred water, one experiences a born-again mentality. When sacred water and light merge, the faithful mustard seed is planted, and the true teaching and living begin.

The sacred water runs not only in the center of the bones, but also in the midst of the body connecting the Crown and Perineum Points (Fig. 7). The Crown Point emits the fire as the Perineum Point secretes the glacial water. The glacial water is the primordial yang Chi that carries the gender-producing substances. The conscious fire in the brain utilizes the unconscious water in the abdomen as elixir or white horse: a completed product.



Fig. 7 *Crown Point is connected to the Perineum.*

Under this condition, the nine structural ligaments that form the vocal cords speak with the power of nine kings being guided by the master king, the tenth king of Miphkad. The nine bodily parts and holes are integrated into nine palaces echoing the power of nine teachings. The sacred water and light unify the seven firmaments. The vocal cords no longer resound with the activation of mouth and teeth, but vibrate directly through the pineal gland and the Crown Point. When the nine vibrations activate the pineal gland, the Crown Point will resonate in the universal and cosmic behavior. The visible biological nine holes in the body will harmonize with the invisible nine holes in the brain. The active nine bodily parts will speak through the inactive nine vocal ligaments. The cerebral cortex becomes the cosmic mud upon which the spiritual elixir can be produced through the activation of the mighty cerebellum. (Fig. 8).



Fig. 8 *Nine Palaces*

When the cerebellum is totally awakened, the instinctive mind behaves through the supervision of eternal peace. Daily activity will unify with nightly rest; the thinking mind will collaborate with the dreaming mind; biological water will balance with sacred water; lustful drive will merge into blissful flow. The inner drumming practice is about to begin. When the glacial thalamus and hypothalamus glands are activated by the holy well of brain fluid under the cave of the corpus collasum, elixir is produced through the interaction of the pituitary and pineal glands. The elixir then travels through the calcarine and parieto-occipital sulcus to nourish the entire cortex and cerebrum (Fig. 9). When the time is right, the spirit-elixir will shoot through the central sulcus, the “Crown Point”, its heavenly home. Souls are shocked by this drumming power, and spirit is aroused by the drumming frequency of vibration balancing the entire universe. The body is scorched, the souls are sold, and spirit returns to its original home.

As the vocal cords produce sound, the nine special areas in the body/mind are opened. Among these nine areas, three represent the Tan Tiens, three the “guans” or passes of fire, and three for “qiao”. The three Tan Tiens are located in the third eye area, the Yellow Court area, and the cauldron area respectively (Fig. 10). They charge the frontal body by managing the water-Qi circulation. The lower Tan Tien awakens the Kundalini power for the frozen Jing-Qi to become internalized into sweet dew. The middle Tan Tien expresses love through the falling of sweet dew, while upper Tan Tien reviews the cosmic wisdom with its fresh single eye. In Biblical tradition, the lower Tan Tien constructs the Old Gate. The upper Tan Tien forms the Sheep Gate. The middle Tan Tien manifests the Christ Love. These three Tan Tiens belong to the wood element. They possess the power of restoration and charge the power of growth.


Poscentral Gyrus
Parietal Lobe
Parieto-Occipital Sulcus
Occipital Lobe
Transverse Fissure
Cerebellum
Central Sulcus
Precentral Gyrus
Frontal Lobe
Insula (Projected to Surface)
Lateral Cerebral Sulcus
Temporal

Fig. 9 *Brain Sulci: Parieto-Occipital and Central Sulci of the Skull*



Fig. 10 *Three Tan Tiens*

Corresponding to these Tan Tiens are the three "Guans," the passes of fire. These passes circulate in the back, facing the three Tan Tiens directly. The Lower Guan opens the life-gate pressure or the Water Gate. The Middle Guan empowers the spirit-platform or the Horse Gate that fires the hands. The Upper Guan, called the Jade Pillow, is located in the center of visual cortex. It is the power of the Master Gate, or the Gate of Miphkad. These three Guans belong to the golden element. They possess the power of openness and initiate the circulation of change.

Circulating between these six special areas are the powers of the three "Qiao" or three Knacks. Each knack constitutes a "gong" or palace. The Yin Gong is the perineum point, and the Yang Gong is the Crown Point. The Central Gong utilizes the cortex as the cosmic earth. The yin qiao/gong belongs to the water element and possesses the quality of peace. The yang qiao/gong belongs to the fire element and has the quality of action. The Central Qiao/Gong belongs to the earth element and pertains to the quality of harmony.

When these nine special areas are unified in the brain the Nine Palaces are flung open, emitting elixir into the cosmos through nine mountain-like openings. Among them, seven connect with star lights of the Big Dipper. The Moon shadows the eighth through the North Star. The ninth is charged by the Sun, which is controlled by the Southern Star. Allowing the Jade Moon and Golden Flower lights to become the basic nutrients, rather than consuming food and water, the meditative mind and fasting body create their own wonder. At a higher level, the eighth is milked by the cosmic holy water and the ninth is clothed by the cosmic white light. The seven teachings are produced through seven sacred body parts, called churches.

Darkness Practice

The Big Dipper and Nine Palaces are practiced interchangeably: meaning the Big Dipper exercises are done actively as “Wuhuo” or “Military Fire” and the Nine Palaces are exercised passively as “Wenhuo” or “Intellectual Fire.” During the active meditation in the early morning and before midnight while in complete darkness using Darkness Technology (UTS - Booklet), all participants must exercise Big Dipper. During relaxed or sleeping meditation practice, Nine Palaces will be used. Also, practice the Big Dipper first and then the Nine Palaces.

Big Dipper Practice

The names of the seven stars are as followings. 1) Supreme Star-Jing, Mystic axis, or Bright Yang; 2) Prime-star, North Platform, Yin Essence; 3) Truth-Star, Nine extremity, Pure Person; 4) Network-Star, Orbiting Root, Mystic Subtlety; 5) Principal-Star, Supreme Peace, Prime Elixir; 6)Disciple-star, Mechanical Spirit, North Pole; 7) Guard-Star, Mystic Yang, Heavenly Guard (Fig. 11). The names from western Astronomy are in Fig. 12.

The first two stars belong to Hun-Soul, the third and fourth stars are controlled by Po-Soul, and fifth and sixth stars generate Spirit-elixir, the seventh star illuminates for all (Fig. 13). The others names are 1) Hungry Wolf, 2) Huge Gate, 3) Prosperity Storage, 4) Intellectual Art, 5)Honest Chastity, 6) Martial Art, 7) Destructive Army.


6. Martial Art, Disciple-Star, Mechanical
4. Network-Star, Orbiting Root, Mystic
7. Destructive Army, Guard-Star
1. Supreme Star-Jing,
2. Prime-Star, North
3. Truth-Star, Nine
5. Honest Chastity. Principle-Star

Fig. 11 *Taoist names of the seven stars.*


Alcor
(519 trillion miles)
Alioth
(411 trillion miles)
Mizar
(517 trillion miles)
Megrez
(382 trillion miles)
Dubhe
(617 trillion miles)
Phecda
(529 trillion miles)
Merak
(479 trillion miles)

Fig. 12 *Stars and their distances from earth.*



Fig. 13 *Soul names of the stars.*

According to the Chinese Calendar, each two hours is one time period (Fig. 13). Each person has a birth star, depending on the specific time period: first star 11:00 pm-1:00 am; second star 1:00-3:00 am/pm; third star 3:00-5:00am/pm; fourth star 5:00-7:00 am/pm; fifth star 7:00-9:00 am/pm; sixth star 9:00-11:00 am/pm; and seventh star 11:00 am-1:00 pm. Before any person goes to the darkroom, he or she must know his or her star. Without connecting to the birth star, Big Dipper practice cannot be practiced successfully. The names are given orally. The normal names that are used are Bright Yang/Hungry Wolf; Yin Essence/Huge Gate; Pure Person/Prosperity Storage; Mystic Subtlety/Intellectual Art; Prime Elixir/Honest Chastity; North Pole/Martial Art; and Heavenly Guard/Destructive Army.


12 1 2 3 4 5 6 7 8 9 10 11
9:00-11:00 am/pm
7:00-9:00 am/pm
:00-1:00 am/pm ⑦
⑥
④
3:00-11:00 am/pm
①
⑤
7:00-9:00 am/pm
③
②
3:00-11:00 am/pm
1:00-3:00 am/pm

Fig. 14 *Times for each Star*

Exercises

1. The first exercise, the Big Dipper, should be practiced only during nighttime and sleep. Practice the Big Dipper only in the brain. Each star three times with each breath (Fig. 15).

   a. The first star is located in the Jade Palace, the power of cerebellum. Visualize it as the purple light, inhale gather the purple light into the cerebellum. Hold the breath, condense the light inside the cerebrum, and exhale, relax and observe the energy circulation in the cerebrum.
   b. Then concentrate on the memory center in the brain by inviting the second star. Visualizing it with dark-blue light during inhalation. Hold the breath, let the light circulate around the memory center. Exhale, observe the Chi circulation.
   c. Then concentrate on the pineal gland by inviting the third star with the light-blue light.


Olfactory Lobes
⑤
Posterior Hypothalamus
⑥
④
Thalamus
①
⑦
Third Eye
③
Pineal Gland
②
Memory Center

***Fig. 15** Big Dipper Stars and the Brain*

d. Fourthly, concentrate on the thalamus glands by inviting the fourth star and green light. This star is the division between the left-brain and right-brain, or animal brain and human cortex.
e. Then concentrate on the hypothalamus and pituitary glands by inviting the firth star and yellow light. This star connects to human smell and balance.
f. The sixth star connects to the olfactory gland and orange light and temples above the and in front of ears. Hearing-palace and Ear Gate pressure points are located here connecting the Small Intestine and Triple warmer.
g. The seventh star gives ultimately the birth of red fire, the solar light, and passion of sixth sense to mystic awareness. It is located on the yang third eye, or Spirit-hall pressure point.

h. After meditating on each star three times, then visualize all the rainbow colors/lights showing into the brain. Above the rainbow colors the mystic black light, and below is the white (Fig. 16).
i. This star exercise connects to the Spleen and planet Saturn, in the sense that the brain becomes the cosmic soil.



Fig. 16 *Rainbow color lights in the brain.*

2. The second exercise connects to the south and planet Mars (Fig. 17). During the night time the practitioner must focus on the brain to gather the star power and solar light. The exercise is: 1) The first star connects to the yang-third-eye; 2) second star/Jade palace;3) third star/C-7; 4) fourth star/thymus gland; 5) Fifth star/ Yellow Court;) Sixth Star/umbilical cord; and 7) seventh star; Lower Tan Tien. Use the same colors and same format as the first exercise.


5. Yellow Court
Solar Plexus
4. Thymus Gland
Umbilical Cord
1. Yang-Third Eye
⑤
④
①
⑦
⑥
②
3. C-7
2. Jade Palace
Lower Tan Tien
③

Fig. 17 *Gathering star power and solar light.*

3. During the daytime, focus on the Lower Tan Tien and moon practice (Fig. 17). The exercise is: 1) first star/tailbone; 2) second star/pubic bone; 3) third star/umbilical cord; 4) fourth star/life-gate point; 5) fifth star/Yellow Court; 6) sixth star/thymus gland; 7) and seven star/vocal cords. The third exercise relates to the north and planet Mercury.

4. The fourth exercise is about the sleeping practice. Lie down on the right side to avoid the pressure exerting on the heart. The thumb and index fingers of the right hand cover the right ear; with the elbow serving as the pillow. The left big toe touches the right inner ankle, to connect the yinqiao/wei points. The left hand is placed either on the left hip or in between the legs. The seven star arrangements are the same as the fourth exercise.


7. Vocal Cord
4. Life-Gate
7
6
5
1
6. Thymus
4
3. Umbilical Cord
1. Tailbone
3
2
2. Pubic Bone
5. Plexus Yellow Court

Fig. 18 *Bigger Dipper Stars and Related Body Parts*

Exercise four alternates between the first star and seventh one, meaning the practitioner can either begin with the brain for descending practice, and gathering the cosmic power; or start with the ascending practice, gathering water-earth-Chi. The standing exercise represents east direction or sunrise, and planet Jupiter. The sleeping exercise represents west direction or sunset, and planet Venus.

After each of these exercises, the practitioner can start with the Nine Palace practice, beginning with the kidney Qi-sound, and observing the vibration in four tones and upper four palaces.

Begin from the standing exercise, then the sun, moon, sleeping and ending up with the brain exercise, to finally gather and condense the five Chi between the body/mind and universe.

After the seven-star and nine-palace practices are completed, the seven stars will connect to the North Star via Vega, the Girl Weaver, the eighth power. The seven-star practice is completed as Cowherd, the Cowboy, the seventh power.

Nine Palaces Practice

In Taoist tradition, the Nine Palaces of the brain (Fig. 19) connect with nine sacred caves and nine sacred mountains, intersecting the nine sacred power lines of Mother Earth. Each Palace serves as a cosmic antenna, and each mountain transmits the vibration circulating in that region. In order to receive these nine power lines, one must travel across the nine sacred mountains and sit finally on the middle one, the crowning mountain, to practice enlightenment. The caves are the Mother's energy lines. Like the hollowing bones, caves contain the earliest information of life stored inside the Earth. The caves contain the vital essence of the Earth Power. When nine special bodily areas are unified in the brain, the Nine Palaces are flung open, emitting elixir into the cosmos.


8. Mystic Elixir
7. Ultimate Purity
9. Heavenly Emperor
6. Heavenly Hall
4. Illuminating Pearl
1. Bright Hall
2. Cave House
5. Jade Emperor
3. Elixir Field
8. Mystic Elixir
7. Ultimate Purity
9. Heavenly Emperor
6. Heavenly Hall
4. Illuminating Pearl
1. Bright Hall
5. Jade Emperor
2. Cave House
3. Elixir Field

Fig. 19 *Nine Palaces of the brain connect with the nine sacred mountains.*



Fig. 20 *Brain areas. Functional areas of the brain and the corresponding nine palace points.*

1. The first palace is called the Bright Hall and corresponds to the Third Eye (Fig. 19). The Bright Hall connects with the power of speech (Fig. 20). The Bright Hall vocalizes God's power of the Word. [Corresponds with Peak 19, House of Rising Yang, Fig. 4.]
2. The Cave House, the second palace, is about one inch behind the Bright Hall (Fig. 21). It is centered in the optic, auditory and olfactory bulbs, occupied with seeing, hearing, and smelling. The Cave House is the primary sensory power, whether in the cave under the ocean (the fetus stage) or in the cave of darkness (night and advanced spiritual work).
3. The Elixir Field, the third palace, is about one inch behind the Cave House. The Elixir Field generates the crystallized fluid in the brain, making biological and spiritual functioning available. It is the principal field of all bodily glandular functioning as well. This field works directly with the eighth palace of the Mystic Elixir (below). Beneath the cave, the thalamus and hypothalamus glands (Fig. 21) can then generate the bluish crystal glacier to form the basic brain fluid. [Corresponds with Peak 18, Muddy Pool, Fig. 4.]

4. The Illuminating Pearl, the fourth palace, is about one inch behind the Elixir Field. The Illuminating Pearl connects with the cerebellum (Fig. 21), connecting with ultimate arousal, uplifting bliss, and the precious momentary joy.


Central Sulcus
(8. Mystic Elixir)
Touch & Taste
(7. Ultimate Purity)
Forebrain
(6. Heavenly Hall)
Parieto-Occipital Sulcus
(9. Heavenly Emperor)
Speech Area
(1. Bright Hall)
Auditory Area /
Olfactory Area (Hidden)
(2. Cave House)
Optic Area
(5. Jade Emperor)
Hypothalamus
(3. Hidden)
Cerebellum
(4. Illuminating Pearl)

Fig. 21 *Brain areas and associated Palaces*

5. The Jade Emperor, the fifth palace, is about one inch behind the Illuminating Pearl. The Jade Emperor sees and directs all activities. (Fig. 20)
6. The Heavenly Hall, the sixth palace, is about one inch above the Cave House. The Heavenly Hall circulates within the dipole of the forehead.
7. The Ultimate Purity, the seventh palace, is about one inch above the Elixir Field. The Ultimate Purity controls the frontal operculum. Its power connection is the frontal fontanels. It controls the bodily and cosmic movements of touching and tasting (lightning and rain) (Fig. 20). The energetic power of touching and tasting also come from the Mystic Elixir, the ground base (below).
8. The Mystic Elixir, the eighth palace, is about one inch above the Illuminating Pearl. The Mystic Elixir gathers the elixir-making fluid from the central sulcus. This is the most refined spiritual fluid in the body, ready to evaporate the spirit into the sky. Which corresponds with Peak 16, Top of the Great Peak, Fig. 4.]
9. The Heavenly Emperor, the ninth palace, is about one inch above the Jade Emperor. The Heavenly Emperor occupies the parietal operculum, behind which, heavenly light shoots into the conscious mind through the parieto-occipital sulcus (Fig. 11).

All together, the Jade Emperor supervises all, the Bright Hall sees all, the Cave House hears and smells all, the Elixir Field waters all, the Illuminating Pearl experiences all, the Heavenly Hall idealizes all, the Ultimate Purity balances all, the Mystic Elixir glorifies all, the Heavenly Emperor seals all. Through the cerebral cortex and cerebellum, the Eternal Life and Mystic Elixir give birth to the final end product, Spirit, which is the tenth of all. The cerebral cortex and the cerebellum are the cosmic land in the body / mind.

Exercises

The detailed meditation practice of these nine palaces has to do with the five sonic vibrations purified from the five organs and the four tones within each.

1. To begin with, the yin third eye watches downward to connect the true and false vocal cords as well as the thyroid and parathyroid glands. The distance is about seven inches in between.
2. As the meditator inhales, the true vocal cord generates the green color, while the false vocal cord produces the purple color.
3. While sustaining the breath, the mind gathers the condensed vibration to the corresponding five palaces: the fifth palace connects to the kidney sound, the fourth the liver sound, the third to the heart sound, the second to the spleen and the first to the lungs.
4. Exhale, mentally connecting the sonic vibration from the organs below and the two colors generated by the vocal cords to the four tones of the four upper palaces, then letting the tones vibrate through the left and right brain. The left-brain connects to the blue color, while the right brain to the purple color. Doing so connects the power of the Moon and Sun correspondingly.

Each sound is produced five times. Starting with the kidney sound, the two emotional powers ”will and fear” will be balanced and will resonate at the same time. Next is the liver sound, the power of passion and rage; then heart sound, the power of love and hate; then the spleen sound, the power of worry and giving; and finally the lung sound, the power of happiness and sadness.

It is through these sonic vibrations that the person engaging in fasting practice will sustain the power of breath, and the power of mental wakefulness. Even going through the dying process, the spirit mind must be alert all the time. Otherwise, the souls will die into ghost world.

Normally, this set of exercises must be practiced together with the Big Dipper exercise. As the seven emotions are purified through the Big Dipper exercise, the five sonic vibrations will reach to their purest state. The nine palaces will then be fully open.

Preparations for Lesser Kan and Li: Fusion of Five Elements/Creation Cycle

It is important to cleanse the emotions each day so the energies will be pure for the Kan and Li practice. Connect the senses to the organs as you form a pearl and circulate it through the Microcosmic Orbit. Then send the pearl through the organs in the Creation Cycle for at least three rounds. You may use the same pearl or form a new one to send through the thrusting and belt channels (Cosmic Fusion). Finally, if time allows, send the energy through the Bridge and Regulator Channels (Fusion of Eight Psychic Channels).

As you create the pearl, distinguish any negative emotions that may be present within each organ. Look for fear in the kidneys, impatience in the heart, anger in the liver, sadness in the lungs, and worry in the spleen. Transform those negative energies by recycling them in the Creation Cycle, nurturing the virtue energies associated with each organ. Enhance the virtues of gentleness in the kidneys, kindness in the liver, respect in the heart, fairness in the spleen, and righteousness in the lungs.

Foundations of Spiritual Practice

Lesser Enlightenment Kan and Li; Opening of the Twelve Channels; Raising the Soul and Developing the Energy

Lesser Enlightenment of Kan and Li (Yin and Yang Mixed): This formula is called Siaow Kan Li in Chinese and involves a literal steaming of the sexual energy (Ching or creative) into life-force energy (Chi) in order to feed the soul or energy body. One might say that the transfer of the sexual energy power throughout the whole body and brain begins with the practice of Kan and Li. The crucial secret of this formula is to reverse the usual sites of Yin and Yang power, thereby provoking liberation of the sexual energy.

This formula includes the cultivation of the root (the Hui-Yin) and the heart center and the transformation of sexual energy into pure Chi at the navel. This inversion places the heat of the bodily fire beneath the coolness of the bodily water. Unless this inversion takes place, the fire simply moves up and bums the body out. The water (the sexual fluid) has the tendency to flow downward and out. When it dries out, it is the end. This formula reverses normal wasting of energy by the highly advanced method of placing the water in a closed vessel (cauldron) in the body and then cooking the sperm (sexual energy) with the fire beneath. If the water (sexual energy) is not sealed, it will flow directly into the fire and extinguish it or itself be consumed.

This formula preserves the integrity of both elements, thus allowing the steaming to go on for great periods of time. The essential formula is to never let the fire rise without having water to heat above it and to never allow the water to spill into the fire. Thus, a warm, moist steam is produced containing tremendous energy and health benefits, to regrow all the glands, the nervous system and the lymphatic system and to increase pulsation.

Kan and Li Characteristics



Kan (Water): Broken Lines are Yin, Darkness. Solid Line is Yang-Light. The Trigram is Light within Darkness or Fire within Water (Yang within Yin).



Li (Fire): Broken Line is Yin, Darkness. Solid lines are Yang, Light. The Trigram is Darkness within Light or Water within Yin (Yin within Yang).

Kan	***Li***
	
Lead, Life Essence, Sexual Energy, Real Knowledge True Sense, Real Wisdom Tama the Tiger	Mercury, Spiritual Essence Temper, Ground the Dragon, Heart of Compassion
1. The Yang within Yin	1. The Yin within Yang
2. True Lead, True Sense	2. True Mercury, Spiritual Essence and Virtual
3. The Lad of the Kan in the Moon	3. The Maiden of the Li in the Sun
4. North, Moon	4. South, Sun
5. Water	5. Fire
6. White Tiger	6. Green Dragon
7. Female	7. Male
8. Kidney	8. Heart
9. Saliva	9. Chi
10. Semen, Sperm	10. Blood, Menstruation
11. Black	11. Red
12. Self	12. Other
13. True Sense mixed with arbitrary Feeling.	13. Spiritual Essences become adulterated with Temper.



Kan: Lead, True Sense, Life Essence, Orgasm Energy

1. Lead is dense and heavy
2. True sense of real knowledge; when sexual energy cannot be moved senses will be restored.
3. True sense is outwardly dark but inwardly bright Strong and unbending, able to ward off external afflictions. The Black Tiger's strength and vigor are within.
4. The White Tiger's energy is associated with metal.
5. Iron Man is not constrained by anything.
6. Golden Flower- pivot of creation.
7. North Star-it conceals brightness within darkness and metal within water.
8. Rabbit in the Moon-masculinity within femininity.
9. When sexual energy rises (does not leak out) it gets transformed into bliss.
10. Total Body Orgasm: First: Brain; Second: the Senses; Third: the Kidneys; Fourth: the Liver; Fifth: the Spleen; Sixth: the Lungs; Seventh: the Heart; Eighth: the Soul; Ninth: the Spirit.
11. The Orgasm comes from the material
    a. The material- the sexual organs, the senses, the glands, the organs
    b. When sexually aroused it transforms the aroused sexual energy into immaterial.
    c. When it is aroused to the higher level of force, the orgasm has the power to connect with Universal Force (God) and bring the Earth Energy up to human body.



Li: True Mercury, Spiritual Essence, the Heart of Compassion

1. Mercury: Lively and active, bright and buoyant, soft and yielding. It easily runs oft like the spiritual essence of conscious knowledge in the human body.

2. Spiritual essence is outwardly firm yet inwardly flexible. Call and it responds; touch and it moves. True Mercury goes in and out unpredictably.

3. Green Dragon- when passing through or tempering by fire it changes to the Black Tiger.

4. The Woman: Yang on the outside and Yin on the inside.

5. The Man: Yin on the outside and Yang on the inside.

6. Wood Mother- Soft and Loving.

7. Raven in the Sun- Femininity within Masculinity.

8. Mercury Within Cinnabar- Its reality is hidden within fire.

9. Flowing Pearl- Its light is penetrating.

10 The Firs of heart compassion come from the material into the immaterial.

  a. The material- the Organs: Heart, Kidneys, Liver, Spleen, Lungs.
  b. Their pure energy transforms into virtue, the immaterial such as love, joy happy, gentleness, kindness, fairness, cour age. Which we can not see, cannot touch, but we can feel its reality.
  c. When all these virtues combine at the heart they become the heart of compassion.
  d. When it rises up to the mideyebrow it becomes the spiritual essence.

Afternoon or Evening Meditation

Kan and Li Formulas:

Do each formula for two weeks, then combine them if time permits.

A. Reversing the Hot and Cold Energy

These procedures should be done at the beginning of each meditation.

1. Smile down.
2. Listen to the kidneys - feel gentleness and coolness.
3. Distinguish their cold energy from the hot energy of the adrenals, which are located on top of the kidneys.
4. Form a sphere at the perineum in which to collect the cold energy of the kidneys. Collect the hot energy of the adrenal at T-11 on the spine, and send it up the spinal cord to the crown. From there bring it down the middle Thrusting Channel to the heart center, and combine it with the energies of the heart and the thymus.
5. Pull the hot energies from the adrenals, heart, and thymus into the heart collection point and mentally establish the pulse there.
6. Divide your attention between the hot and cold energies at the two collection points. Bring the hot energy down either the front or the left Thrusting Channel to the lower abdomen. Simultaneously bring the cold energy up the back or the right Thrusting Channel to the solar plexus. Do not allow the energies to shift or move as you slowly reposition them. Think of the hot and cold energies as fire and water contained in two separate cups, both of which must not be spilled.
7. Move the hot and cold energies into the middle Thrusting Channel and carefully couple them at the navel. The fire is the stove, and the water is the cauldron. Be careful not to spill the cold energy into the stove.

8. Establish the heartbeat in the cauldron, and allow the kidneys to pulse with the heart as you pull up the sex organs.

9. Seal the senses down into the cauldron as this will help you establish the automatic pulsing there.

10. Stir the cauldron with your inner eye, and feel the steam arise from the cauldron.



Fig. 22 *Reversing the Hot and Cold Energy*

B. Steaming the Glands and Organs

As the steam comes out of the cauldron, direct the colored steam or vapor to the following glands and organs for a few minutes each. You may feel each organ soften, expand like a flower blossom, and become cool as the steam surrounds it.

1. Kidneys - Bladder - Blue Steam
2. Liver - Gall Bladder - Green Steam
3. Spleen - Pancreas - Yellow Steam
4. Heart - Small Intestine - Red Steam
5. Lungs - Large Intestine - White Steam



Fig. 23 *Steaming the Glands and Organs*

C. Spinal Cord Steaming

- If starting fresh, complete the steps in A (one to ten).
- If continuing from B, reestablish the automatic beating at the cauldron.

1. As you stir the cauldron with the eyes and pull up the sex organs, move the cauldron and stove back toward the spine.
2. Direct the energy of the steam into the spine. The abdomen may pull in, and the breathing may stop momentarily.
3. As you feel the steam in your back, breathe the energy up and down the spine.



Fig. 24 *Spinal Cord Steaming*

D. Lymphatic System

- If starting fresh, complete the steps in A.
- If continuing, reestablish the pulse in the cauldron.

This exercise requires knowledge of the lymphatic system's locations in the body.

1. Direct the steam into the lymph nodes in the navel area.
2. In time, each node will begin to flower or open one by one.
3. Allow each to open, moving your concentration from the navel area into the chest, neck, armpits, etc., following the pathways of the lymphatic system.



Fig. 25 *Lymphatic System*

E. Nervous System/Spine

- If starting fresh, follow the procedures in A.
- If continuing, reestablish the pulse at the cauldron.

1. Move the stove and cauldron down to the perineum.
2. Move it carefully to the sacrum and steam up the spinal cord.
3. Eventually the steam will flow out of the spinal cord into the nerves throughout the body.

Note: Focus on dry areas and moisten them.



Fig. 26 *Nervous System/Spine*

F. Thymus/Pituitary/Pineal

- If beginning fresh, follow the procedures in A.

- If continuing, reestablish the pulse at the cauldron.

1. Steam the thymus gland located behind the sternum.

Note: Spend less time on the thymus. Calculate before you steam this and the pituitary gland so that the thymus only receives two-thirds as much steam. In other words, if you plan to steam the pituitary for three minutes, steam the thymus for only two.

2. Turn the eyes up to the point between the eyebrows, and direct the steam into the pituitary gland.

3. Turn the eyes up to the top of the head, and steam directly into the pineal gland.

Note: After the pineal gland has been steamed, the energy may spread into any one of a number of routes: eight psychic channels, twelve channels in arms or legs, or any of the routes in *Fusions of the Five Elements, Cosmic Fusion* and *Fusion of Eight Psychic Channels.*



Fig. 27 *Thymus/Pituitary/Pineal*

G. Opening the Twelve Channels

- If starting fresh, follow the procedures in A.

- If continuing, reestablish the pulse at the cauldron.

Note: Be sure to steam each organ before passing the steam through the associated channels. Each channel connects to the next in sequence. After opening each channel the steam will automatically be at the starting point for the next. You may feel a numbness as it passes through each.

1. Lungs: Steam the lungs and their channel as you hold the lung points on the inside edges of your thumbs.

The Lung Channel originates at the middle of the abdomen and travels through the arms to connect with the Large Intestine Channel. From near the cauldron, it runs along the upper orifice of the stomach, passes through the diaphragm, and enters the lungs. At the portion of the lungs nearest the throat, it separates and descends along the inner aspects of the upper arms, through the forearms, and ends at the inside edges of the thumbs. A branch runs directly to the inside tip of each index finger where it links with the Large Intestine Channel.



Fig. 28 *Steaming the Lungs Meridian with Holding Point*

Holding Point: Use the index finger of each hand to reach over its respective thumb and press a point on the inside edge facing the centerline of your body where the thumbnail begins.

2. Large Intestine: Steam the large intestine and its channel as you hold the related points on your index fingers.

The Large Intestine Channel starts at the inside tips of the index fingers, running up between the first and second metacarpal bones of each hand. Following the outer length of the forearms, it reaches the outside of the elbows, ascending along the upper arms to the highest point of the shoulders. It travels along the outer border of the acromion and culminates briefly at the C-7 point. From there it descends over the shoulders as it again separates. Each half splits: one part of each route descends to connect with the lungs and diaphragm, entering the large intestine; the other part branches upward through the neck and cheek. The ascending portions travel up the sides of the mouth, partially connecting at the upper lip as they extend upward through both sides of the nose to link with the Stomach Channel.



***Fig. 29** Steaming the Large Intestine Channel with Holding Point*

Holding point: Use the tip of each thumb to press a point on inside edge of each index finger facing the thumb where the fingernail begins.

3. Stomach: Steam the stomach and its channel as you mentally hold the related points on the second toes of the feet. (These are the longest toes.)

The Stomach Channel starts on both sides of the nose, extending almost to the inside corner of each eye. From the sides of the nose it descends over the mouth, connecting at the chin. It again separates as two branches run across the lower portion of the jaw on both sides of the head, ascending by the front of each ear along the hairline to the forehead.

Parts of these branches descend along the sides of the throat and split again near the collar bone. Two extensions pass through the diaphragm and the stomach as they travel to the groin. (The left side connects with the spleen.) The other extensions run outside, descending through the nipples and near the umbilicus on the inner sides of the lower abdomen. Four branches connect at the middle of the groin, and then divide into two branches which travel down the front of the legs to the dorsal areas of the feet. These branches again split within each foot. One part extends to the outer tip of the second toe (the holding point), and the other to the inside edge of the big toe as it connects with the Spleen Channel.



Fig. 30 *Steaming the Stomach Channel with Holding Point*

Holding Point: As you hold the lung points with your fingers, focus your attention on points at the outside edges of the second toes facing the middle toes where the toenails begin.

4. Spleen: Steam the spleen and its channel as you mentally hold points located on the inside edges of the big toes facing the centerline where the toenails begin.

The Spleen Channel starts from the tips of the big toes, running along the insides of the feet and ascending up the legs through the inner knees and thighs. The two branches curve around the lower abdomen, combining at the navel before they split into four. One extension connects with the spleen; another flows through the stomach and into the heart to link with the Heart Channel. Two remaining branches ascend through the diaphragm and along the sides of the esophagus until they reach the root of the tongue where they culminate.



Fig. 31 *Steaming the Spleen Channel with Holding Point*

Holding Point: As you hold the lung points with your fingers, concentrate on the inside edges of the big toes behind the toenails.

5. Heart: Steam the Heart and its channel as you use your thumbs to hold the heart points on the inside edges of the pinky fingers facing the fourth fingers where the fingernails begin.

The Heart Channel originates at the heart and spreads over the surrounding area, flowing down through the diaphragm to connect with the small intestine. One ascending portion of the channel runs along the center of the esophagus to connect with the eye system. Another two branches flow upward to the lungs, curving around to the insides of the forearms and flowing down through the inside edges of the pinky fingers. Here the branches link with the Small Intestine Channel.



***Fig. 32** Steaming the Heart Channel with Holding Point*

Holding Point: Hold the heart points at the inside edges of the pinky fingers using the tips of the thumbs.

6. Small Intestine: Steam the small intestines and their channel as you use your thumbs to hold the points on the outsides of the pinky fingers where the finger nails begin. (Curl the pinky fingers to access the points.)

The Small Intestine Channel starts at the outer side of the tips of the pinky fingers. Following the edges of the hands, its branches ascend up the outer sides of arms to the shoulder joints. Then they curve through the scapulae and traverse the sides of the lower neck to the front of the body where the two branches split. Their lower extensions connect at the heart and descend as one channel, passing through the diaphragm, the stomach, and finally the small intestines. The ascending branches extend from the collar bone up the sides of the neck to the cheeks where they also split. Two extensions end at the sides of the nose near the inside corners of the eyes where they connect with the Urinary Bladder Channel. The other two extensions split further at the outside corners of the eyes and cross the cheeks to end at the ears.



***Fig. 33** Steaming the Small Intestine Meridian with Holding Point*

Holding Points: Use the tips of the thumbs to depress the small intestine points located on the outside edges of the pinky fingers behind the fingernails.

7. Urinary Bladder: Steam the bladder and its channel as you mentally hold points at the outer edges of the pinky toes where the toe nails begin. The Urinary Bladder Channel starts at the nose near the inside corners of the eyes. The two branches ascend to the forehead, joining at its apex, then split and run across the top of the cranium. On the back of the head the branches split again: routes descend behind the ears and converge at the back of the skull, enter the brain, reemerge, and bifurcate into two extensions of each branch. Near the base of the skull, the channel appears as four separate lines. Two of these run vertically down the insides of the scapulae, descending into the lumbar region as they enter the body cavity and connect with the kidneys and the urinary bladder. They swing back to the sacrum and descend down the inner thighs to join two other branches of the Urinary Bladder Channel at the knees. The other two branches descend vertically from the back of the neck along the edges of the scapulae parallel to the inside channels. Passing downward through the buttocks, they cut outward and descend along the backs of the legs. From where these meet with the inside branches at the knees, the recombined lines descend along the lower legs to the outer edges of the feet, ending at the outside edges of the pinky toes. Here the branches link with the Kidney Channel.



***Fig. 34** Steaming the Urinary BladderChannel with Holding Point*

Holding Point: As you hold the lung points with your fingers, mentally hold the urinary bladder points on the outer edges of the smallest toes.

8. Kidneys: Steam the kidneys and their channel as you mentally hold points located on the undersides of the pinky toes.

The Kidney Channel starts at the underside of the little toes and runs across the soles of the feet. From the soles, the branches emerge and circulate around the protruding inner ankle bones and ascend along the inner legs and thighs toward the coccyx. From the coccyx, the channel follows the spine up to enter the kidneys. From the kidneys, two branches run down to the bladder and up through the liver and diaphragm to enter the lungs. The branches terminate at the root of the tongue. A small branch also joins the heart and links with the Pericardium Channel.



Fig. 35 *Steaming the Kidneys Meridian with Holding Point*

Holding Points: As you hold the lung points with your fingers, concentrate on the bottom of each pinky toe.

9. Pericardium: Steam the area around the heart and its related channel as you hold points on the tips of the middle fingers using the tips of the thumbs. (Curl the middle fingers to access the points with the thumbs.)

The Pericardium Channel originates in the chest around the heart. It enters the pericardium, then it descends through the diaphragm to the abdomen. Other branches run inside the chest toward the nipples, curving up, and then running down the insides of the arms to the palms. The channel ends at the tips of the middle fingers where branches arise from the palms to connect with the Triple Warmer Channel, which begins at the fourth fingers.



Fig. 36 *Steaming the Pericardium Meridian with Holding Point*

Holding Point: Hold the pericardium points on the middle fingertips using the tips of your thumbs.

10. Triple Warmer: Steam up the torso upper, middle, and lower abdomen and its channel as you hold points on the tips of your ring fingers with your thumbtips. (Curl the fourth fingers.)

The Triple Warmer Channel originates at the tip of the ring fingers, flowing across the back of each hand and ascending up the outer sides of the arms to the backs of the shoulders. Its branches wind over the shoulders to the supraclavicular fossa where they recombine and split again, spreading in the chest to connect with the pericardium before they descend through the diaphragm to the upper, middle, and lower abdomen.

A branch ascends to the supraclavicular fossa from the chest and continues over the shoulders and up the sides of the neck toward the ears. This channel splits on both sides of the neck. One branch extends around the back of the ear, up to the temple, and down to the cheek, ending at the inside corner of the eye. The other enters the ear, emerges in front of the ear, and crosses to the outer edge of the eyebrow to link with the Gall Bladder Channel.



Fig. 37 *Steaming the Triple Warmer Meridian with Holding Point*

Holding Point: Depress the triple warmer points on the tips of the ring fingers of each hand using the tips of the thumbs.

11. Gall Bladder: Steam the gall bladder and its channel as you mentally hold a point on the outside edge of the fourth toe of each foot facing the pinky toe where the toenail begins.

The Gall Bladder Channel originates in the outer canthus, flowing toward the ears, up to the corners of the forehead, and back down to the tips of the ears. Then its branches curve back around the ears, up over the cranium to the forehead, and back down the neck. They traverse the shoulders and join the other branches descending from the infraorbital regions and the cheeks at the supraclavicular fossa region.

From the supraclavicular fossa region, one branch descends into the chest and passes through the diaphragm to connect with the liver and the gall bladder. From there it runs down the abdomen, superficially along the margin of the pubic hair, and then into the hip region. The other branch runs downward along the lateral aspect of the chest and the free ends of the floating ribs to the hip where it joins the other branch. The channel splits again and descends along the lateral aspects of the thighs, knees, and lower legs to the outside tips of the fourth toes. Branches also run to the big toes where they link with the Liver Channel.



Fig. 38 *Steaming the Gall Bladder Meridian with Holding Point*

Holding Point: As you hold the lung points with fingers, focus your attention on point at the inside edges of the big toes.

12. Liver: Steam the liver and its channel as you mentally hold a point on the outside of the large toe of each foot facing the second toe where the toenails begin.

The Liver Channel starts at the dorsal region of the big toes and ascends up the inner sides of the knees and thighs to the pubic region. It curves around the genitalia and up through the diaphragm to curve around the chest. Then its branches ascend along the posterior aspects of the throat, crossing the cheeks to connect with the eye system. They continue upward, emerging from the forehead above the eyebrow, and pass over the head. A branch comes down from the eye system to curve around the inner surface of the upper and lower lips. Another branch arising from the liver passes through the diaphragm and lungs to link with the Lung Channel.



Fig. 39 *Steaming the Liver Meridian with Holding Point*

Holding Point: As you hold the lung points with fingers, focus your attention on point at the inside edges of the big toes.

H. Increasing the Pulses

- If starting fresh, follow the procedures in A.

- If continuing, reestablish the automatic pulsing as you move the stove and cauldron back to the coupling point behind the navel.

1. Mentally allow the heart rate to decrease.
2. Amplify the strength of the pulse at the crown and perineum points. This will assist the heart by moving the blood with Chi energy.
3. Amplify the pulse at the navel, groin, inner ankles, and feet.
4. Amplify the pulse at the neck, temple, back of skull, arm pits, inside elbows, and wrists.
5. As you become familiar with this exercise, begin to synchronize all pulses. By recreating the pulse in other areas, you will eventually be able to transfer the heartbeat up to the energy body.



Fig. 40 *Increasing the Pulses*

I. Inner Eye

- If beginning fresh, follow A (one to ten).

- If continuing, return to the stove and cauldron.

1. In the junction point between the stove and cauldron, make the eye. You may begin with it as a point of light.

2. Allow it to grow and strengthen and begin to move it out of the stove/cauldron.

3. Eventually begin to direct the inner eye on exploratory missions throughout the various routes: microcosmic, thrusting, belt, etc.



Fig. 41 *Inner Eye*

J. Self Intercourse

- If starting fresh, follow the procedures in A.

- If continuing, reestablish the pulse at the cauldron.

1. Concentrate on the sexual organs and the pineal gland.

2. Practice the Power Lock for several rounds to draw sexual energy up to the pineal gland.

3. In a separate step, draw sexual energy into the perineum.

4. Using the middle thrusting channel, feel the connection between the genitals through the perineum and the pineal gland.

5. Draw sexual energy up from the perineum as you bring down energy from the pineal gland, compressing them both into the cauldron at the navel. As you establish their connection at the cauldron, an orgasm may occur in the navel area extending out to the organs.

6. When the orgasm reaches what feels to be its peak, seed the cauldron with energy from the liver or the liver collection point.

Note: The cauldron may be seeded either from the top or directly into the coupling point.



Fig. 42 *Self Intercourse*

K. Virtuous Animal Pure Inner Child and Planet Protection

Spiral Kidney Essence to Kidney Collection Pt.-Feel Blue Light form Virgin Child & Antlered Deer (Earth Force)-Breathe out Blue Light of Gentleness forming Blue Turtle behind(N) connecting above with Mercury. Spiral Heart Essence to Heart Collection Pt.-Feel Red Light form Virgin Child & Pheasant (Earth Force)-Breathe out Red Light of Joy forming Red Pheasant in Front (S) of Body connecting above with Mars. Spiral Liver Essence to Liver Collection Pt.-Feel Green Light form Virgin Child & Dragon (Earth Force) Breathe out Green Light of Kindness forming a Green Dragon Right (E) connecting above with Jupiter. Spiral Lung Essence to Lung Collection Pt. -Feel White Light form Virgin Child & Tiger (Earth Force) Breathe out White Light of Courage forming a White Tiger Left (W) of Body connecting above with Venus. Spiral Spleen Essence to Spleen Collection Pt.-Feel Yellow Light form Virgin Child & Phoenix(Earth Force) Breathe out Yellow Light of Fairness forming a Yellow Phoenix Above (C) of Body connecting with Saturn. Form protective Outer Ring around Organs with Virgin Children & Power Animals then form Protective Ring & Fiery Dome around Physical Body with Earth Force Animals North-South-East-West-Center interconnecting with Planets & Stars (RS).



Fig. 43 *Animal Protection*

L. Gather the Pill

Breathe in through the mideyebrow connecting with an outer light by blinking the eye. Draw and gather the light into a pill and move it down to the Solar Plexus. The pill is the essence and nutriment for the Immortal Fetus. Feel the growth of the Immortal Fetus as you draw in the light.



Fig. 44 *Gather the Pill*

M. Transfer of the Organ's Essence

Feel the organ energy and essence and transfer into the organs of the Energy Body with each of the vital organs: Heart Essence into Energy Body's, Lungs Essence into Energy Body's, Spleens Essence into Energy Body's, Liver Essence into Energy Body's, Kidneys Essence into Energy Body's.



Fig. 45 *Transfer of the Organ's Essence*

N. Ending the Meditation: Turning the Wheel

Each Kan and Li meditation should be ended with this formula which is a process of collecting refined energy in the navel cauldron to be used in future meditations, including the higher levels.

- If beginning fresh, follow the procedures in A.

- If continuing from I above, reestablish the cauldron and stove, moving them back to the sacrum.

At this stage, the eyes are used to direct the energy produced by the meditation into the Microcosmic Orbit, guiding it into the cauldron behind the navel.



Fig. 46 *Ending the Meditation: Turning the Wheel*

1. Form a pool of sexual energy at the perineum. Looking straight ahead with your eyes closed, form a mental image of a clock with your eyes focused on its center.

2. Look down into the pool (6:00), and draw sexual energy up into the spine. The steam will travel up the spine drawing sexual energy with it.

3. Look from the perineum up to the right (3:00), drawing the energy up to T-11 as it is refined at that point.

4. Look from the right up to the crown (12:00), and draw the energy there to further refine it at the pineal gland.

5. Look from the crown down to the left (9:00), and draw the energy down either through the tongue or the thrusting routes into the cauldron at the navel. The energy is then stored in the cauldron. (These four directions constitute one round.)

6. Follow the above procedures J (two to five) for at least 36 revolutions. You may do them in four rounds of six revolutions with three counts resting in between; or you may do two rounds of twelve revolutions with six counts resting in between. In any sequence, the revolutions and resting counts must add up to 36. The rising steam will eventually flow independently of your counting, but maintain the mental revolutions to be sure it reaches the cauldron.

7. If you have time, do four rounds of 75 revolutions, resting for fifteen counts in between rounds; or do two rounds of 150 revolutions, resting for 30 counts in between rounds; or do 360 revolutions straight through. (All of these methods add up to 360, which is the maximum number of revolutions used to end this practice.)

For further information about Universal Tao Centers, courses, or other resources, contact:

Universal Tao Instructor Associations

North America Instructors Association (NAIA)

c/o Loretta Robb, Treasurer
13 Plymouth Drive, Newark, Delaware 19713 USA
Tel: (1)(888) 444-7426 (Toll Free) or (1)(212) 330-7876
Email: info@taoinstructors.org Website: http://taoinstructors.org

European Instructors Association (EIA)

c/o Zentrum Waldegg
3823 Wengen, SWITZERLAND
Tel: (41)(33) 8554422 Fax: (41)(33) 8555068
Email:info@waldegg.ch Website: www.waldegg.ch

To order English books, and for your local Insructors use our Web Sites: www.universal-tao.com and www.tao-garden.com

Universal Tao World Fulfillment Center

274 Moo 7, Luang Nua, Doi Saket, Chiang Mai, 50220 Thailand
Tel: (66)(53) 495-596 & 865-034 Fax: (66)(53) 495-852
North America Fax (1)(212) 504-8116 Europe Fax (31)(20) 524-1374
Email: universaltao@universal-tao.com **or** info@tao-garden.com

The Universal Tao is not and cannot be responsible for the consequences of any practice or misuse of the information in this booklet. If the reader undertakes any exercise without strictly following the instructions, notes, and warnings, the responsibility must lie solely with the reader.



$6.95

Lesser Kan and Li

Enlightenment and Birth of the Immortal Fetus

Mantak Chia

Illustrations by Udon Jandee

Lesser Kan and Li

Kan and Li literally means water and fire. The Chinese formula Siaow Kan Li (Yin and Yang Mixed) literally steams the sexual energy (Jing) into life force energy (Chi) in order to feed the soul or energy body.

The Birth of the Soul

The formulas in the lesser Enlightenment help to give birth to the soul body, an awakening of that part of yourself, which is free from environmental and karmic conditioning. The birth of the soul is not metaphor. It is an actual process of converting energy into a subtle body.

Overcoming Reincarnation

The newborn soul matures in relation to your energy skills. If you were to die, the energy gathered in the soul body will not simply dissipate. The Lesser Enlightenment of Kan and Li leads to the first steps of overcoming reincarnation.

Preparing for the Spirit Body

Developing the soul body is the preparation for the growth of the Spirit Body in the Greater Enlightenment of Kan and Li. Come! Experience the mystery. "Begin it now." As Goethe said: "Boldness has genius and magic in it."

ISBN 0-935621-45-8

9 780935 621457

Universal Tao Publications
274 Moo 7, Luang Nua, Doi Saket,
Chiang Mai 50220, Thailand
Tel: (66)(53) 495-596 Fax: 495-852
Email: universaltao@universal-tao.com
Web Site: www.universal-tao.com

CHINESE MEDICAL QIGONG THERAPY:

A Comprehensive Clinical Text

中国气功医疗

DR. JERRY ALAN JOHNSON PH.D., DTCM, DMQ (CHINA)

CHINESE MEDICAL QIGONG THERAPY:

A COMPREHENSIVE CLINICAL TEXT

JERRY ALAN JOHNSON, PH.D., D.T.C.M., D.M.Q. (CHINA)

EDITED BY
JAMPA MACKENZIE STEWART, D.O.M., L.AC.
AND
MADELEINE H. HOWELL, M.F.T., M.Q.T.

First published in May 2000 by:
The International Institute of Medical Qigong
P.O. Box 52144
Pacific Grove, CA 93950
U.S.A.

© 2000 Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)

All rights reserved under the International and Pan-American copyright conventions. No part of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording or otherwise, without the prior written permission of the publisher (The International Institute of Medical Qigong). Reviewers may quote brief passages.

ISBN# 1-885246-08-0
Printed in the United States of America.

Disclaimer:

Qigong medicine is not intended to replace orthodox medicine, but rather to complement it. The meditations, practices, techniques and prescriptions described herein are powerful and may be too mentally and physically demanding for some people. The readers should therefore use their own discretion and consult a doctor of Medical Qigong therapy, an acupuncturist, medical doctor, or mental health professional before engaging in these exercises and meditations. The author, the International Institute of Medical Qigong, and the publishers are neither liable or responsible to any person or entity with respect to any loss or damage caused, or alleged to be caused, directly or indirectly by reading or following the instructions for any condition, or interpreting information provided in this text. The treatments mentioned in this book are not meant to be used as symptomatic prescriptions. The treatment of specific organs, channels, channel points, and prescriptions must always be selected based on the thorough understanding of the origin of the patient's disease. If an ailment is severe, or if symptoms persist, please consult a medical professional immediately.

Throughout the text I will refer the doctor to prescribe herbs for certain conditions along with Medical Qigong therapy. All Medical Qigong prescriptions, exercises and "homework" assigned to patients in Section X "Treatment of Internal Diseases with Qi Emission Therapy" and Section XI "Specialized Qi Emission Therapy for Pediatrics, Geriatrics, Gynecology, Neurology, Psychology, Oncology, and Surgery" should also be included with herbal prescriptions, as well as the regulation of the patient's diet and living environment. Herbal prescriptions will vary according to the patient's constitution, condition and specific illness, and must be treated accordingly only by a doctor or herbalists qualified to prescribe Chinese medical herbs.

Throughout the text I have used the term *doctor* when referring to professional practitioners who use energetic medicine to treat patients. The word "doctor" means "to teach". I believe that the foremost duty of any doctor of medicine (Western or Chinese) should be as educator, to teach his or her patients knowledge and skills for the prevention and treatment of disease and injury. Currently, the official title, *Doctor of Medical Qigong Therapy* is only licensed and used in China.

TABLE OF CONTENTS

FORWARD XXIII

PREFACE XXXI

ACKNOWLEDGMENTS XXXV

INTRODUCTION XXXVII

SECTION I

FOUNDATIONS OF CHINESE ENERGETIC MEDICINE 1

CHAPTER 1 INTRODUCTION TO MEDICAL QIGONG 3
- THE FIVE DOMINIONS OF ENERGY 3
- DEFINING THE ENERGY OF YIN AND YANG 5
- UNDERSTANDING THE CONCEPT OF QI 5
- DIFFERENT SCHOOLS OF QIGONG 5
- MEDICAL QIGONG DEFINED 6
- MEDICAL QIGONG TRAINING IN CHINA 7
- MEDICAL QIGONG TRAINING IN THE UNITED STATES 8
- TRADITIONAL CHINESE MEDICINE AND MEDICAL QIGONG THERAPY 14
- ACUPUNCTURE THERAPY 15
- HERBAL THERAPY 18
- CHINESE MASSAGE THERAPY 19
- MEDICAL QIGONG THERAPY 22

CHAPTER 2 ENERGETIC FORMATION OF THE HUMAN BODY 25
- ENERGETIC EMBRYOLOGICAL DEVELOPMENT 25
- ENERGY, MATTER, AND SPIRITUAL INTERACTIONS 26
- UNDERSTANDING FETAL TOXINS 26
- DEVELOPMENTAL SEQUENCE 27
- THE TEN LUNAR MONTHS OF CREATION 29
- POSTNATAL ENERGY DEVELOPMENT 41
- ENERGETIC EMBRYOLOGICAL OVERVIEW 41
- THE ETERNAL SOUL 42
- SUMMARY 51

CHAPTER 3 PHYSICAL DEVELOPMENT AND STRUCTURAL FORMATION 53
- FASCIAL DEVELOPMENT AND ENERGY FLOW 53
- YIN AND YANG STRUCTURAL FORMATION 53
- THE YIN AND YANG OF BODY ASPECTS 55
- THE FIVE ELEMENTS 56
- CONGENITAL CONSTITUTIONS 57
- CLASSIFICATION OF THE FIVE CONSTITUTIONS 57
- THE WOOD CONSTITUTION 58
- THE FIRE CONSTITUTION 60
- THE EARTH CONSTITUTION 61
- THE METAL CONSTITUTION 62
- THE WATER CONSTITUTION 63

COMBINED CONSTITUTIONS 64
PERSONALITY CONSTITUTIONS OF THE EIGHT EXTRAORDINARY VESSELS 65
THE YAO IMAGE AND PHYSICAL ANATOMY 66
IDENTIFYING INTROVERTED AND EXTROVERTED STRUCTURES 71
CONGENITAL AND ACQUIRED CELLULAR PATTERNS 73
SUMMARY 73

CHAPTER 4 THE FIVE ENERGIES OF THE HUMAN BODY 75
SOUND ENERGY RESONANCES 75
LIGHT ENERGY 77
MAGNETIC ENERGY 82
GENERATED HEAT 84
ELECTRICITY 86

CHAPTER 5 THE THREE DANTIANS AND THE TAIJI POLE 89
THE THREE DANTIANS 89
THE LOWER FIELD OF ELIXIR 90
THE MIDDLE FIELD OF ELIXIR 95
THE UPPER FIELD OF ELIXIR 98
THE FUNCTIONAL ASPECTS OF THE THREE DANTIANS 102
THE DANTIAN'S YIN AND YANG ENERGETIC CHAMBERS 104
THE DOCTOR'S PROJECTED AURA FIELDS 105
THE TAIJI POLE 105
THE TWELVE GATES OF THE CHAKRA SYSTEM 109
TAKING PRECAUTIONS 115
THE TWELVE EARTHLY BRANCHES AND THE TWELVE CHAKRA GATES 115

CHAPTER 6 THE TWELVE PRIMARY CHANNELS AND ORGANS 117
INTRODUCTION 117
CLASSIFICATION OF CHANNELS 118
THE CHANNELS' RELATIONSHIP TO QI AND BLOOD 121
FUNCTION OF THE CHANNELS 122
INTERNAL AND EXTERNAL CHANNEL FLOW 122
ORGAN AND CHANNEL FUNDAMENTALS 123
THE GALL BLADDER CHANNELS 124
THE LIVER CHANNELS 126
THE LUNG CHANNELS 128
THE LARGE INTESTINE CHANNELS 130
THE STOMACH CHANNELS 132
THE SPLEEN CHANNELS 134
THE HEART CHANNELS 136
THE SMALL INTESTINE CHANNELS 138
THE BLADDER CHANNELS 140
THE KIDNEY CHANNELS 142
THE PERICARDIUM CHANNELS 145
THE TRIPLE BURNER CHANNELS 147
UNDERSTANDING CHANNEL PATHOLOGY 151

CHAPTER 7 THE EIGHT EXTRAORDINARY VESSELS AND COLLATERALS 155
THE EIGHT EXTRAORDINARY VESSELS 155
THE FUNCTION OF THE EIGHT EXTRAORDINARY VESSELS 155
THE EIGHT EXTRAORDINARY VESSELS AND MEDICAL QIGONG THERAPY 157

CLINICAL USE OF THE EIGHT EXTRAORDINARY VESSELS 157
ENERGETIC FUNCTIONS OF THE EIGHT EXTRAORDINARY VESSELS 158
THE GOVERNING AND CONCEPTION VESSELS 158
THE GOVERNING VESSEL OR DU VESSEL 159
THE CONCEPTION VESSEL OR REN VESSEL 162
THE THRUSTING VESSELS AND THE BELT VESSELS 164
THE BELT VESSEL OR DAI VESSEL 166
THE YIN AND YANG HEEL VESSELS OR QIAO VESSELS 168
THE YIN HEEL VESSELS 168
THE YANG HEEL VESSELS 169
THE YIN AND YANG LINKING VESSELS OR WEI VESSELS 171
THE YIN LINKING VESSEL 171
THE YANG LINKING VESSELS 172
SUMMARY OF EIGHT EXTRAORDINARY VESSEL PATHOLOGY 173
THE FIFTEEN MAJOR COLLATERALS (CONNECTING VESSELS) 175
THE TWELVE DIVERGENT CHANNELS 180
THE TWELVE MUSCLE/TENDON CHANNELS 186
THE TWELVE SKIN ZONES 197
THE CONNECTIVE TISSUE OF THE TWELVE SKIN ZONES 197
CHANNEL AND COLLATERAL THERAPY 200
CONTROLLING QI EXTENSION THROUGH THE CHANNELS 201

CHAPTER 8 THE BODY'S ENERGETIC POINTS 203
INTRODUCTION TO ENERGETIC POINTS 203
THE FOUR WAYS POINTS ARE FORMED 203
SCIENTIFIC RESEARCH OF ACUPOINTS 203
THE FOUR CATEGORIES OF ENERGETIC POINTS 204
THE TWO GATES OF ENERGETIC POINTS 204
THE THREE FUNCTIONS OF ENERGETIC POINTS 205
POINT NAMES 207
CLASSIFICATION OF ENERGETIC POINTS 207
SUMMARY OF POINTS 212

CHAPTER 9 THE EXTRAORDINARY YANG ORGANS 215
THE UTERUS 215
THE BRAIN 217
THE GALL BLADDER 218
THE MARROW 218
THE BONES 218
THE BLOOD VESSELS 221

SECTION II
THE THREE OUTER FORCES: HEAVEN, EARTH & MAN 223

CHAPTER 10 INTRODUCTION TO THE THREE OUTER FORCES 225
THE NATURAL POWER OF THE THREE OUTER FORCES 225
THE THREE OUTER FORCE'S NINE TREASURES 225
THE THREE OUTER FORCES AND CHINESE ALCHEMY 225
HEAVENLY QI 226
EARTHLY QI 228
MAN'S QI 229

CHAPTER 11 THE THREE TREASURES OF HEAVEN: SUN, MOON, AND STARS 231
- DEFINING HEAVEN QI 231
- INFLUENCES OF HEAVENLY QI ON THE HUMAN BODY 232
- BODY RHYTHMS AND ENERGETIC PATTERNS 232
- CYCLES OF THE SUN 234
- THE TWELVE PI HEXAGRAMS 234
- THE FOUR PRINCIPAL TIME PERIODS OF QIGONG PRACTICE 236
- THE FOUR SEASONAL PEAK TRANSITIONS 237
- THE SIX PRINCIPAL SEASONS OF TRANSITION 239
- THE DAILY QI, BLOOD, AND HEAT CYCLE 239
- GATHERING THE SUN'S ESSENCE MEDITATION 240
- CYCLES OF THE MOON 242
- PRENATAL EIGHT TRIGRAMS AND THE MOON 244
- CHOOSING THE PROPER DIRECTION FOR TRAINING QI 244
- CYCLES OF THE STARS 248
- EARTHLY BRANCHES, HEAVENLY STEMS, AND NINE PALACES 254
- SUMMARY 255

CHAPTER 12 THE THREE TREASURES OF EARTH:EARTH, WATER, AND WIND 259
- INTRODUCTION TO THE THREE TREASURES OF EARTH 259
- GATHERING ENERGY FROM THE EARTH'S ENERGETIC FIELDS 260
- TECHNIQUES FOR CULTIVATING EARTH QI 260
- GATHERING QI FROM TREES, BUSHES, AND FLOWERS 261
- GATHERING QI FROM MOUNTAINS, VALLEYS, AND DESERTS 263
- GATHERING QI FROM OCEANS, LAKES, AND STREAMS 263
- GATHERING QI FROM THE SIX DIRECTIONS 264
- ADDITIONAL TECHNIQUES FOR TRAINING EARTH QI 265
- THE EARTHLY TREASURE OF FOOD 266
- UNDERSTANDING THE YIN OR YANG ASPECT OF FOOD 266
- UNDERSTANDING THE YIN OR YANG ASPECT OF HERBS 266
- ENERGY, FOOD, AND DIET 267
- USING THE FIVE FLAVORS OF FOOD 268
- GUIDELINES FOR THE FIVE ELEMENTAL TASTES 270
- OVERVIEW OF THE FIVE ELEMENTAL TASTES 271
- SUMMARY 271

CHAPTER 13 THE THREE TREASURES OF MAN: JING, QI, AND SHEN 273
- PRENATAL AND POSTNATAL JING, QI, AND SHEN TRANSFORMATIONS 274
- JING: ESSENCE OF LIFE 276
- THE YIN AND YANG ASPECTS OF JING 276
- PRENATAL JING 276
- POSTNATAL JING 277
- THE INTERACTION OF PRENATAL AND POSTNATAL JING 277
- QI: VITAL LIFE-FORCE ENERGY 278
- EIGHTEEN CLASSIFICATIONS OF QI 279
- THE SIX FUNCTIONS OF QI 281
- QI AND ENERGETIC MEDICINE 283
- QI AND THE BODY'S ENERGETIC STRUCTURE 283
- SHEN: THE SPIRIT OF LIFE 290
- SHENGONG SCHOOLS OF MEDITATIONS AND TRAINING 290
- PRENATAL AND POSTNATAL SHEN 291

THE FIVE SPIRITUAL ASPECTS AND YIN ORGAN COMPONENTS OF SHEN 291
THE LIVER STORES THE ESSENCE SPIRIT "HUN" 292
THE HEART STORES THE ESSENCE SPIRIT "SHEN" 295
THE SPLEEN STORES THE ESSENCE SPIRIT "YI" 296
THE LUNGS STORE THE ESSENCE SPIRIT "PO" 296
THE KIDNEYS STORE THE ESSENCE SPIRIT "ZHI" 298
THE FIVE YIN ORGAN CULTIVATION OF SHEN 298
SHENGONG CULTIVATION METHODS 300
THE SIX TRANSPORTATION'S OF SHEN 301
THE EIGHT SUPERNATURAL POWERS 304
SOUL PROJECTION, SPIRIT PROJECTION AND ENERGY PROJECTION 306

SECTION III

DAO YIN TRAINING 311

CHAPTER 14 INTRODUCTION TO DAO YIN TRAINING 313
STATIC QIGONG TRAINING 314
DYNAMIC QIGONG TRAINING 314
PRINCIPLES OF YIN AND YANG IN DAO YIN TRAINING 314
THREE FOUNDATIONAL METHODS OF DAO YIN TRAINING 315

CHAPTER 15 POSTURAL DAO YIN TRAINING 317
STATIC POSTURE DAO YIN TRAINING 317
CHOOSING THE PROPER POSTURE 318
PRIMARY AND SECONDARY POSTURES 318
THE EIGHTEEN RULES OF PROPER MEDICAL QIGONG STRUCTURE 321
DYNAMIC POSTURE DAO YIN TRAINING 330
USING THE ENERGY OF THE HANDS TO LEAD QI 332
MEDICAL QIGONG WALKING THERAPY 334
WALKING COMBINED WITH COLOR THERAPY 338
WALKING COMBINED WITH SOUND THERAPY 338
THE THERAPEUTIC EFFECTS OF MEDICAL QIGONG WALKING THERAPY 338
THREE STEPPING METHODS USED TO TREAT CANCER 342
ENDING AND CLOSING THE WALKING THERAPY 344

CHAPTER 16 RESPIRATORY DAO YIN 349
THE PURPOSE OF RESPIRATORY DAO YIN 349
THE ROLE OF THE LUNGS IN QI CULTIVATION 349
DEEP INHALATION AND EXHALATION BREATHING METHODS 349
SEVEN DAO YIN BREATHING TECHNIQUES 350
RESPIRATORY GUIDING AND REGULATING 353
RESPIRATORY TONIFICATION AND PURGING METHODS 354
BASIC ESSENTIALS OF RESPIRATORY TRAINING 354
BREATHING PATTERNS FOR COLLECTING AND REGULATING QI 355
THE FOUR PROGRESSIVE STAGES OF RESPIRATION 356
DURATION TIME FOR RESPIRATION THERAPY 357
EMOTIONAL EFFECTS ON BREATHING PATTERNS 357
RESPIRATORY DAO YIN CANCER PRESCRIPTIONS 357

CHAPTER 17 MENTAL DAO YIN TRAINING 359
INTRODUCTION 359
THE PRENATAL AND POSTNATAL MIND 360

BENIGN AND MALIGNANT THOUGHT PATTERNS 361
THE IMPORTANCE OF MIND CONCENTRATION 361
REGULATING THE MIND 362
THE THREE CATEGORIES OF MENTAL CONCENTRATION 363
ESSENTIALS OF TRAINING MIND CONCENTRATION 364
CONCENTRATIVE MEDITATION AND INSIGHT MEDITATION 365
THE THREE STAGES OF MENTAL TRANQUILITY 366
THE THREE PROCESSES OF THE MIND 366
CREATING THE BRIDGE OF LIGHT 367
REPROGRAMMING THE MIND TO HEAL 369
USING THE IMAGINATION 369
TWELVE STAGES TO TRANSCEND AND TRANSFORM 370
SUMMARY 374

SECTION IV
QI DEVIATIONS IN QIGONG TRAINING 375

CHAPTER 18 INTRODUCTION TO QI DEVIATIONS 377
THE MAIN CAUSES OF QI DEVIATIONS 377
CORRECTING QI DEVIATIONS 379
SHEN DISTURBANCES AND EMOTIONAL DYSFUNCTIONS 386
UNCONTROLLABLE MUSCLE DEVIATIONS 391
RECTIFYING QI DEVIATIONS USING TAIJI RULER 391

CHAPTER 19 DISORDERS AND DEVIATIONS OF THE SOUL AND SPIRIT 393
INTRODUCTION TO SPIRITUAL DIMENSIONS 393
EVIL STATES AND MENTAL DELUSIONS 395
PROJECTED SPIRIT DEMONS FROM THE SUBCONSCIOUS MIND 397
ACTUAL ENCOUNTERS WITH SPIRIT DEMONS 397
OVERVIEW 399
MULTIPLE PERSONALITY DISORDER (DISSOCIATIVE IDENTITY DISORDER) 400
SOUL RETRIEVAL AND MEDICAL QIGONG THERAPY 401
WOUNDING AND CLOSING THE SPIRIT 403
HEALING THE SPIRIT 405
EMOTIONAL REBIRTHING PATTERNS 406
SOUL RETRIEVAL MEDITATION 406
THE DOOR TO THE CHAMBER OF MEMORIES 411
FINDING THE LIFE PURPOSE 411

SECTION V
DIFFERENTIAL DIAGNOSIS OF ENERGETIC PRINCIPLES 413

CHAPTER 20 INTRODUCTION TO DIFFERENTIAL DIAGNOSIS 415
DIAGNOSIS IN ENERGETIC MEDICINE 415
ETIOLOGY IN MEDICAL QIGONG THERAPY 415
THE GROWTH AND PEAK CYCLES OF JING, QI AND SHEN 416
DISORDERS OF THE HUMAN BODY 417
THE DIFFERENTIATION OF SYNDROMES 419
THE CATEGORIZATION OF SIGNS AND SYMPTOMS 420
DIAGNOSIS AND TREATMENT OF THE PATIENT 420
UNDERSTANDING THE THEORY OF ENERGETIC COUNTERACTION 422

CHAPTER 21 DIAGNOSIS ACCORDING TO THE EIGHT ENERGETIC PRINCIPLES 423
INTERNAL AND EXTERNAL PATHOGENIC FACTORS 423
HOT AND COLD 428
EXCESS AND DEFICIENT 430
YIN AND YANG THEORY 431
DIAGNOSING YIN AND YANG IN THE BODY 432
SIGNS OF YIN AND YANG 435
YIN AND YANG CATEGORIZATION OF TRAINING 436
PULSE DIAGNOSIS OF THE EIGHT ENERGETIC PRINCIPLES 436
PULSE QUALITIES AND CLASSIFICATIONS 437
THE CLASSICAL PULSE DIAGNOSTIC POSITIONS AND DEPTH 438
OVERVIEW 439

CHAPTER 22 DIAGNOSIS ACCORDING TO QI, BLOOD, AND BODY FLUID DYSFUNCTIONS 441
INTRODUCTION 441
DISORDERS OF THE QI 441
LEAKAGE AND LOSS OF QI 442
EXCESS QI DISORDERS 444
QI STAGNATION DISORDERS 444
REBELLIOUS QI DISORDERS 445
TURBID QI 445
RECTIFYING QI DISORDERS 446
DISORDERS OF THE BLOOD 447
DEFICIENCY OF BLOOD 447
THREE DISORDERS OF BODY FLUIDS 448
TYPES OF PHLEGM 450

CHAPTER 23 DIAGNOSIS ACCORDING TO THE FIVE-ELEMENT THEORIES 451
INTRODUCTION TO THE FIVE ELEMENTS 451
THE FIVE ELEMENTS AND YIN AND YANG THEORY 451
THE CREATIVE OR GENERATIVE CYCLE 453
THE CONTROLLING OR RESTRICTIVE CYCLE 453
THE INVADING OR OVERACTING CYCLE 454
THE INSULTING OR COUNTERACTING CYCLE 455
THE FIVE ELEMENTAL TONIFICATION CYCLE 456
FIVE YIN ENERGETIC ORGAN MANIFESTATIONS 456

CHAPTER 24 OTHER DIAGNOSTIC SYSTEMS AND TECHNIQUES 459
DIAGNOSIS ACCORDING TO THE SIX STAGES 459
DIAGNOSIS ACCORDING TO THE FOUR LEVELS 460
DIAGNOSIS ACCORDING TO THE TRIPLE BURNERS 462

CHAPTER 25 CLINICAL EXAMINATION AND DIAGNOSIS 465
SENSORY, INTUITIVE AND PERCEPTUAL DIAGNOSIS 465
SENSORY DIAGNOSIS 465
CLINICAL INTAKE, EXAMINATION AND EVALUATION 465
EXAMINATION FOR DIAGNOSIS 467
DEVISING A TREATMENT PRINCIPLE 468
TREATMENT STRATEGY 468
TREATMENT 469
AFTER THE TREATMENT 469

ALTERNATIVE TREATMENT STRATEGIES 470
INTUITIVE AND PERCEPTUAL DIAGNOSIS 470
THE METAPHYSICAL DIMENSIONS OF MEDICAL QIGONG HEALING 470
THE AWAKENING 471
LEARNING INTUITIVE AND PERCEPTUAL DIAGNOSIS 471
RECEIVING AND INTERPRETING THE PATIENT'S FIELDS OF BIO-INFORMATION 472
ACCESSING THE KNOWLEDGE STORED WITHIN THE WUJI 473
UNDERSTANDING PAST-LIFE REGRESSION 474
LEARNING MEDICAL QIGONG TECHNIQUES 476
PERCEPTUAL COMMUNICATION TRAINING 477
APPLICATIONS OF INTUITIVE AND PERCEPTUAL QI DIAGNOSIS 479
DIAGNOSIS BASED ON FLAT-PALM DETECTION (HAND SENSING) 479
DIAGNOSIS BASED ON KINESTHETIC AND EMPATHIC QI ABSORPTION 480
HAND DIAGNOSIS BASED ON BODY ASSOCIATION 481
DIAGNOSIS BY OBSERVING AURA FIELDS 483
DIAGNOSIS BASED ON INTENTION 487
LONG DISTANCE MEDICAL QIGONG THERAPY 487
FAITH PROJECTION AND MEDICAL QIGONG THERAPY 490
AUXILIARY MEDICAL QIGONG HEALING MODALITIES 492
USING MEDICAL QIGONG TO HEAL BY PROJECTING CHINESE CHARACTERS 492
USING MEDICAL QIGONG WITH SUPPLEMENTARY APPARATUSES 492

SECTION VI
ESTABLISHING THE MEDICAL QIGONG CLINIC 497

CHAPTER 26 TREATING THE PATIENT 499
SETTING A SPACE/TIME FOUNDATION 499
ESTABLISHING THE MEDICAL QIGONG TREATMENT ROOM 500
ESTABLISHING A RAPPORT WITH THE PATIENT 500
THE FOUR MAJOR PRIORITIES OF CLINICAL QIGONG HEALING 503
PREPARING THE SELF TO TREAT THE PATIENT 504
TREATING THE PATIENT 509
MEDICAL QIGONG TREATMENTS 515
TREATING MULTIPLE PATIENTS 519
ENDING THE TREATMENT 520

CHAPTER 27 COMBINING MEDICAL QIGONG THERAPY WITH OTHER HEALING MODALITIES .. 523
COMBINING MEDICAL QIGONG THERAPY WITH TCM MODALITIES 523
COMBINING MEDICAL QIGONG THERAPY WITH WESTERN MEDICAL MODALITIES 525

CHAPTER 28 PRECAUTIONS AND ETHICAL CONSIDERATIONS FOR THE QIGONG DOCTOR 527
AVOIDING ENERGETIC DEPLETION 527
PREVENTING THE INVASION OF TURBID QI 528
GUIDELINES FOR THE MEDICAL QIGONG DOCTOR 529
WU ZANG (FIVE ORGAN) MEDITATION FOR ENERGETIC PROTECTION 530
CREATING A PROTECTIVE ENERGETIC FORCE FIELD 533
CLINICAL ETHICS 534
CONSCIOUS AND SUBCONSCIOUS CLINICAL INTERACTIONS 535
ESTABLISHING DOCTOR AND PATIENT AGREEMENTS 536
POWER DYNAMICS AND ETHICAL BEHAVIOR 537
PITFALLS 538

CLINICAL BURNOUT AND MEDICAL QIGONG THERAPY 538
ENERGETIC BOUNDARY INVASION 539
STRENGTHENING THE DOCTOR'S ENERGETIC BOUNDARIES 540
CAUSES OF SPIRITUAL DRYNESS 540

SECTION VII
THE TREATMENT PRINCIPLES OF MEDICAL QIGONG THERAPY 543

CHAPTER 29 PRINCIPLES AND PARAMETERS OF MEDICAL QIGONG THERAPY 545
THE FIVE METHODS FOR TREATING PATIENTS 545
THE NINE STAGES OF TREATMENT 545
THE THREE WONDERS OF MEDICAL QIGONG THERAPY 546
CONTRAINDICATIONS FOR MEDICAL QIGONG THERAPY 548

CHAPTER 30 BALANCING THE BODY'S ENERGETIC SYSTEM 551
PURGING, TONIFYING, AND REGULATING 551
THE THREE TREATMENT MODALITIES 551
PURGATION TECHNIQUES 552
TONIFICATION AND PURGATION METHODS 552
TONIFICATION AND PURGATION GUIDELINES 554
UNDERSTANDING MEDICAL QIGONG REGULATION 554
QI REGULATION AND GUIDING PRINCIPLES 555
ENERGY BALANCING PROCEDURES 555
CLINICAL OBSERVATIONS OF PATHOLOGICAL ENERGETIC PATTERNS 556
LOCATIONS OF ENERGETIC BLOCKAGES 556
TYPES OF ENERGETIC COMPLICATIONS 559
PATIENT'S ENERGETIC FACIAL DISTORTION 562
PATIENT RESISTANCE TO ENERGETIC THERAPY 562
UNBLOCKING THE FIVE PASSES 562
FURTHER COMPLICATIONS 564

CHAPTER 31 THE MAGIC SQUARE OF THE YELLOW RIVER 565
THE MAGIC SQUARE AND EIGHT TRIGRAMS 568
THE MAGIC SQUARE AND THE EIGHT EXTRAORDINARY VESSELS 569
UNDERSTANDING THE METAPHYSICAL ASPECT OF NUMBERS 569
THE FIVE ELEMENT ENERGETIC FLOW OF THE MAGIC SQUARE 570
CROSSOVER ENERGY PATTERNS 570

CHAPTER 32 HEALING THE PATIENT'S EMOTIONAL TRAUMAS 573
INTRODUCTION 573
THE PHYSIOLOGICAL EFFECTS OF BENIGN AND CHRONIC EMOTIONS 573
FIVE LEVELS OF FEELING AND THEIR GOVERNING ORGANS 573
STAGES OF EMOTIONAL HISTORY AND RESOLUTION 576
ASSISTING THE PATIENT IN ESTABLISHING HEALTHY BOUNDARIES 578
REJECTION, BETRAYAL, AND ABANDONMENT 578
EMOTIONAL SECURITY 579
HEALING EMOTIONAL TRAUMAS 580
PULLING OUT THE PAIN MEDITATION 581
UNDERSTANDING WHY A PATIENT WON'T HEAL 582
FACING THE DEATH OF A PATIENT 583
SUMMARY 585

SECTION VIII
QI EMITTING METHODS 587

CHAPTER 33 ENERGY EXTENSION AND QI MANIPULATION TECHNIQUES 589
ENERGY PROJECTION 589
TYPES OF ENERGY EXTENSION 589
CONTROLLING ENERGETIC PROJECTIONS 591
HAND POSTURES FOR QI EMISSION 592
THE EXTENDED FAN PALM 592
THE SWORD FINGERS 594
THE ONE FINGER SKILL 595
THE INVISIBLE NEEDLE PALM 597
THE DRAGON'S MOUTH PALM 598
THE KNEADING TIGER PALM 598
THE FIVE THUNDER FINGERS 599

CHAPTER 34 QI EXTENSION, GUIDANCE, AND REGULATION TECHNIQUES 601
QI EXTENSION TECHNIQUES 601
GUIDING THE LINEAR FLOW OF ENERGY 601
CIRCULATING THE QI IN A CIRCLING PATTERN 603
SPIRALING ENERGY FLOW 605
ENERGETIC CUPPING 607
GUIDING THE STATIONARY FLOW OF ENERGY 607
GUIDING THE HOT AND COLD FLOW OF ENERGY 610
CLINICAL APPLICATION OF YIN AND YANG ENERGY EXTENSION 612
GUIDING THE ENERGETIC FLOW OF THE FIVE ELEMENTS 612
SUMMARY OF QI EMITTING METHODS 616

CHAPTER 35 THE INVISIBLE NEEDLE THEORY AND APPLICATION 619
INTRODUCTION 619
PREPARATION 619
ANGLE OF INSERTION FOR TONIFICATION OR SEDATION 620
THE HAND POSTURES OF THE INVISIBLE NEEDLE 621
TIME AND DURATION OF TREATMENT 622
REMOVING THE INVISIBLE NEEDLES AND ENDING THE TREATMENT 622

CHAPTER 36 ENERGETIC POINT THERAPY 623
CHANNEL POINT TREATMENTS AND PRESCRIPTIONS 623
CONTRAINDICATIONS 627
CHANNEL POINT MEDITATION 627

CHAPTER 37 MEDICAL QIGONG MASSAGE 631
INTRODUCTION TO TISSUE FUNCTION 631
TWO APPROACHES IN TREATMENT 632
TISSUE REGULATION THROUGH MEDICAL QIGONG MASSAGE 633
THE FIVE ELEMENTAL QI MASSAGE THERAPY 633
YIN AND YANG ENERGETIC POINT MANIPULATION 636
TREATING THE TISSUE AREA OR ENERGETIC POINT 637
ADDITIONAL GUIDELINES 637

SECTION IX

MEDICAL QIGONG EXERCISES AND PRESCRIPTIONS 639

CHAPTER 38 INTRODUCTION TO MEDICAL QIGONG PRESCRIPTIONS AND REGULATION EXERCISES 641
HISTORY OF MEDICAL QIGONG PRESCRIPTIONS 641
THE FUNCTION OF MEDICAL QIGONG PRESCRIPTIONS 641
MEDICAL QIGONG AND THE IMMUNE SYSTEM 642
THE FIVE STAGES OF HEALING 645
THE THREE CATEGORIES OF MEDICAL QIGONG PRESCRIPTIONS 645
CHOOSING PRESCRIPTIONS ACCORDING TO THE PATIENT'S QI CIRCULATION 646
MEDICAL QIGONG PRESCRIPTIONS FOR GENERAL SYNDROMES 647
NUMBER OF BREATHS REQUIRED IN MEDICAL QIGONG PRESCRIPTIONS 647

CHAPTER 39 SPECIFIC ORGAN SELF-MASSAGE PRESCRIPTIONS 649
INTRODUCTION 649
HEART MASSAGE 649
LIVER MASSAGE 651
LUNG MASSAGE 652
SPLEEN & STOMACH MASSAGE 652
KIDNEY MASSAGE 653

CHAPTER 40 HEALING SOUND THERAPY AND PRESCRIPTIONS 657
INTRODUCTION AND HISTORY 657
SOUND VOLUME RESONATION 657
HIGH-, MIDDLE-, AND LOW-PITCHED SOUND 658
BREATH AND MIND CONTROL 658
AUDIBLE AND INAUDIBLE SOUND RESONATION 659
THE SIX HEALING SOUND PRESCRIPTIONS 660
THE PROPER NUMBER OF BREATHS FOR HEALING SOUND PRACTICE 665
COMBINING MULTIPLE ORGAN SOUNDS 666
OLD MAN SEARCHING FOR THE REFLECTION OF THE MOON AT THE BOTTOM OF TIDE POOL 666
CONTRAINDICATIONS FOR THE SIX HEALING SOUND THERAPY 668
SOUND RESONATION THERAPY FOR TUMOR AND CANCER 668
PREPARATION FOR TUMOR AND CANCER SOUND THERAPY 668
THE PROPER AMOUNT OF TONE REGULATIONS 669
SPECIALIZED PRESCRIPTIONS FOR TUMORS AND CANCER 669
CONTRAINDICATIONS FOR TUMOR AND CANCER SOUND THERAPY 673

CHAPTER 41 MEDICAL QIGONG REGULATION EXERCISES 675
INTRODUCTION 675
STARTING AND ENDING THE PRESCRIPTIONS 675
MEDICAL QIGONG CULTIVATION EXERCISES 676
EXTERNAL QI CULTIVATION 676
INTERNAL QI CULTIVATION 677
REGULATING THE BODY'S QI 678
THE FIRE PATH OF THE MICROCOSMIC ORBIT 678
THE WATER PATH OF THE MICROCOSMIC ORBIT 681
THE WIND PATH OF THE MICROCOSMIC ORBIT 681
MEDICAL QIGONG PRESCRIPTIONS 682
DESCEND THE QI AND CLEANSE THE ORGANS 682

GATHERING QI IN THE UPPER AND LOWER DANTIANS 684
ROLLING THE BALL WITH BOTH PALMS 686
OPENING AND CLOSING THE UPPER, MIDDLE, AND LOWER BURNERS 687
SUN AND MOON ROTATING TECHNIQUE 689
EXPANDING AND CONTRACTING THE RINGS 691
DESCENDING THE YANG AND ASCENDING THE YIN TECHNIQUE 691
TURNING AND WINDING THE BELT VESSEL TECHNIQUE 693
OPENING AND CLOSING THE HEAVEN AND EARTH TECHNIQUE 695
COLLECT THE QI AND RETURN TO THE LOWER DANTIAN TECHNIQUE 697
QIGONG SELF-HEALING MASSAGE AND POINT THERAPY 698
WASH THE FACE 698
MASSAGE THE HEAD 698
BEATING THE HEAVENLY DRUM 699
PRESSING THE EARS 699
RUBBING THE EYES 699
MASSAGING THE NOSE 700
CLICKING THE TEETH 700
WAGGING THE TONGUE 701
SWALLOWING THE SALIVA 701
WHIRLING THE NAPE AND TURNING THE NECK 701
MASSAGING THE CHEST AND ABDOMEN 702
MASSAGE TAPPING THE HANDS (LI-4) 702
MASSAGE TAPPING THE FOREARMS (PC-6) 702
MASSAGE TAPPING THE ELBOWS (LI-11) 702
MASSAGING UNDER THE ARMS (HT-1) 703
MASSAGE TAPPING THE UPPER SHOULDERS (GB-21) 703
MASSAGING THE ARMS 703
MASSAGE TAPPING THE LOWER DANTIAN (CV-6) 703
MASSAGE TAPPING THE BACK OF THE WAIST (GV-4) 704
MASSAGE TAPPING THE SIDES OF THE HIPS (GB-30) 704
MASSAGE TAPPING THE THIGHS (GB-31) 704
MASSAGE TAPPING THE OUTSIDE OF THE KNEES (GB-34) 704
MASSAGE TAPPING THE INSIDE OF THE KNEES (SP-9) 705
MASSAGE TAPPING THE BACK OF THE KNEES (BL-40) 705
MASSAGE TAPPING BELOW THE KNEES (ST-36) 705
MASSAGE TAPPING ABOVE THE MEDIAL MALLEOLUS (SP-6) 706
MASSAGE TAPPING THE HEELS (KD-1) 706
TREMBLING THE KNEES 706
CIRCLING THE ABDOMEN 706
COMPLETING THE EXERCISE 707

CHAPTER 42 DAOIST QIGONG REGULATION EXERCISES 709
DAOIST FIVE YANG ORGAN REGULATION EXERCISE 709
DAOIST FIVE YIN ORGAN TONIFICATION AND REGULATION EXERCISES 710

SECTION X

TREATMENT OF INTERNAL DISEASES WITH QI EMISSION THERAPY 723
INTRODUCTION 724

CHAPTER 43 QI EMISSION THERAPY FOR LIVER DISEASES 725
INTRODUCTION 725
LIVER COMPLICATIONS AND SYMPTOMS 726

GENERAL TREATMENT FOR LIVER DISEASES 726
MEDICAL QIGONG THERAPY FOR LIVER QI DYSFUNCTION 726
LIVER QIGONG PRESCRIPTIONS 728
MEDICAL QIGONG THERAPY FOR SPECIFIC LIVER DISEASES 730
DISORDERS OF THE BILIARY TRACT 730
GALLSTONES 731
CIRRHOSIS 732
CHOLECYSTITIS 733
HYPOCHONDRIAC PAIN 734

CHAPTER 44 QI EMISSION THERAPY FOR HEART DISEASES 735
INTRODUCTION 735
HEART COMPLICATIONS AND SYMPTOMS 735
GENERAL TREATMENT FOR HEART DISEASES 736
MEDICAL QIGONG THERAPY FOR HEART QI DYSFUNCTION 737
HEART QIGONG PRESCRIPTIONS 737
SPECIFIC MEDICAL QIGONG THERAPY FOR HEART DISEASES 738
HYPERTENSION 738
PALPITATION 742
RHEUMATIC HEART DISEASE 743

CHAPTER 45 QI EMISSION THERAPY FOR SPLEEN/STOMACH DISEASES 745
INTRODUCTION 745
SPLEEN COMPLICATIONS AND SYMPTOMS 745
GENERAL TREATMENT FOR SPLEEN DISEASES 746
MEDICAL QIGONG THERAPY FOR SPLEEN QI DYSFUNCTION 747
SPECIFIC MEDICAL QIGONG THERAPY FOR SPLEEN DISEASES 749
DIABETES 749
MEDICAL QIGONG THERAPY AND STOMACH DISEASES 750
STOMACH COMPLICATIONS AND SYMPTOMS 750
GENERAL TREATMENT FOR STOMACH DISEASES 751
SPECIFIC MEDICAL QIGONG THERAPY FOR STOMACH DISEASES 751
ABDOMINAL PAIN 751
CHRONIC GASTRITIS 754
GASTRIC AND DUODENAL ULCERS 755
CHRONIC CONSTIPATION 756

CHAPTER 46 QI EMISSION THERAPY AND LUNG DISEASES 759
INTRODUCTION 759
LUNG COMPLICATIONS AND SYMPTOMS 759
GENERAL TREATMENT FOR LUNG DISEASES 761
MEDICAL QIGONG THERAPY FOR LUNG QI DYSFUNCTION 761
LUNG QIGONG PRESCRIPTIONS 761
SPECIFIC MEDICAL QIGONG THERAPY FOR LUNG DISEASES 762
TREATING THE COMMON COLD AND INFLUENZA 762
CHRONIC BRONCHITIS 764
ASTHMA 764
BRONCHIECTASIS 766
SINUSITIS 767

CHAPTER 47 QI EMISSION THERAPY FOR KIDNEY DISEASES 769
INTRODUCTION 769
KIDNEY COMPLICATIONS AND SYMPTOMS 770
GENERAL TREATMENT FOR KIDNEY DISEASES 770
MEDICAL QIGONG THERAPY FOR KIDNEY QI DYSFUNCTION 771
KIDNEY QIGONG PRESCRIPTIONS 772
SPECIFIC MEDICAL QIGONG THERAPY FOR KIDNEY DISEASES 773
TINNITUS AND DEAFNESS 773
LUMBAGO 774
INSOMNIA 775
PYELONEPHRITIS 776
IMPOTENCE 777

CHAPTER 48 QI EMISSION THERAPY FOR MISCELLANEOUS DISEASES 781
INTRODUCTION 781
DEFICIENT DANTIAN QI 781
PRESCRIPTIONS FOR REGULATING THE THREE DANTIANS 781
IMPROPER YIN AND YANG ENERGY BALANCE 782
DISORDERS OF THE QI 783
REBELLIOUS QI DISORDERS 784
ARTHRITIS 784
VERTIGO 786
HEADACHES 787
MIGRAINE HEADACHES 789

SECTION XI
SPECIALIZED QI EMISSION THERAPY FOR PEDIATRICS, GERIATRICS, GYNECOLOGY, NEUROLOGY, PSYCHOLOGY, ONCOLOGY, AND SURGERY 793

INTRODUCTION 794

CHAPTER 49 QI EMISSION THERAPY FOR PEDIATRICS 795
INTRODUCTION 795
EARLY STAGES OF CHILD GROWTH AND DEVELOPMENT 795
PATHOLOGY 796
DEFICIENT LUNGS 796
DEFICIENT SPLEEN 796
DEFICIENT KIDNEYS 796
LIVER YANG EXCESS 796
HEART (SHEN) IMBALANCE 796
HOT AND COLD EXOGENOUS FACTORS 797
THERAPY 797
ENERGETIC MOVEMENT AND FLOW 797
MEDICAL QIGONG EXERCISE PRESCRIPTIONS FOR CHILDREN 797

CHAPTER 50 QI EMISSION THERAPY FOR GERIATRICS 801
TREATING THE PATIENT'S EMOTIONAL STABILITY 802
ENERGIZING THE PATIENT'S QI CIRCULATION 802
TAPPING THE KNEES TO PREVENT SENILITY 803
CULTIVATING THE PATIENT'S YUAN QI BY ABSORBING ENERGY FROM NATURE 803
FURTHER OBSERVATIONS AND INSIGHTS ON GERIATRIC PATIENTS 804

- Chapter 51 Qi Emission Therapy for Gynecology 807
  - Introduction 807
  - Menstrual Flow 807
  - Qi and Blood Regulation 807
  - Etiology and Pathology of Gynecological Diseases 808
  - Vaginal Discharge 809
  - Menstrual Complications 810
  - Dysmenorrhea 810
  - Menoxenia 812
  - Cysts and Tumors 812
  - Breast Cysts and Benign Tumors 812
  - Level-1 Breast Cysts (Benign Lumps, Nodules or Fibroadenoma) 813
  - Level-2 Breast Cysts (Mastitis or Carbuncle) 813
  - Level-3 Breast Tumors 813
  - Overview of Treatment 814
  - Ovarian Cysts and Uterine Tumors 815
  - Uterine Complications 816
  - Miscarriage 816
  - Uterine Complications Due to Abortions 818
  - Understanding Energetic Abortions 819

- Chapter 52 Qi Emission Therapy For Neurology (Stroke, Coma, Paralysis, and Multiple Sclerosis) 821
  - Introduction 821
  - Stroke (Wind-Stroke) 821
  - Coma 823
  - Facial Paralysis (Bells Palsy) 824
  - Multiple-Sclerosis (MS) 825

- Chapter 53 Qi Emission Therapy for Psychology 827
  - Introduction to Energetic Psychology 827
  - The Emotional Energy Stored within the Five Yin Organs 828
  - Excessive Anger Injures the Liver (Wood) 829
  - Excessive Joy Injures the Heart (Fire) 830
  - Excessive Worry Injures the Spleen (Earth) 831
  - Excessive Sadness and Grief Injures the Lungs (Metal) 832
  - Excessive Fear Injures the Kidneys (Water) 834
  - Five Yin Organ Emotional Responses 835
  - Emotional Disharmony 836
  - Emotional Frequency Resonation 838
  - Differentiation of Psycho-Emotional Disorders 839
  - Self-Treatment Prescriptions for Psycho-Emotional Disorders 840
  - Treating Emotional Anxieties, Phobias, and Addictions 840
  - Treating Phobias and Depression Using "The Windows of the Sky" Points 844
  - Treating Psycho-emotional Disorders Related to Stress 848
  - Treating Stagnant Lung Qi and the Repression of Grief 850

- Chapter 54 Qi Emission Therapy for Oncology 853
  - History of Cancer Treatments 853
  - Categorization of Tumors 853
  - Three Formations of Cancer Growth 854

ETIOLOGY, THE SIX PATHOGENIC EVILS THAT CAUSE CANCER 855
EMOTIONAL COMPONENTS OF CANCER FORMATION 856
CANCER FORMATION AND THE PATIENT'S MIND, EMOTIONS, AND SPIRIT 857
STRESSFUL LIFE ACTIVITIES AND THE IMMUNE SYSTEM 858
USING MEDICAL QIGONG TO STRENGTHEN THE IMMUNE SYSTEM 859
CANCER TREATMENT METHODS 860
SOCIAL ONCOLOGY—ESTABLISHING A CANCER SUPPORT GROUP 861
SOCIAL ONCOLOGY WITHIN THE HOSPITALS 861
CANCER RESEARCH 862
MEDITATIONS FOR CANCER PATIENTS 862
SUMMARY 864
TREATING TUMORS AND CANCER WITH MEDICAL QIGONG THERAPY 864
BRAIN TUMORS 864
BREAST CANCER 865
UTERINE CANCER 866
CERVICAL CANCER 867
PROSTATE CANCER 869
LUNG CANCER (PULMONARY CARCINOMA) 871
LIVER CANCER 871
ESOPHAGEAL CANCER 872
STOMACH CANCER 873
PANCREATIC CANCER 873
COLON AND RECTUM CANCER 874

CHAPTER 55 QI EMISSION THERAPY FOR RADIATION AND CHEMOTHERAPY 877
MEDICAL QIGONG THERAPY AND RADIATION THERAPY 877
MEDICAL QIGONG THERAPY AND CHEMOTHERAPY 877
RELIEVING SYMPTOMS ASSOCIATED WITH RADIATION AND CHEMOTHERAPY 878

CHAPTER 56 QI EMISSION THERAPY FOR SURGERY 879
MEDICAL QIGONG AND PREOPERATIVE THERAPY 879
USING MEDICAL QIGONG FOR ANESTHESIA 880
MEDICAL QIGONG THERAPY AND SURGERY 882
MEDICAL QIGONG AND POSTOPERATIVE THERAPY 882
MEDICAL QIGONG THERAPY AND RECREATING ORGAN ENERGY 883
MEDICAL QIGONG THERAPY AND ORGAN TRANSPLANTATION 885
FOLLOW-UP AND REMEDIAL PRESCRIPTIONS 885
PHANTOM PAINS OF AMPUTATED ORGANS 887
MEDICAL QIGONG THERAPY AND THE TREATMENT OF SCAR TISSUE 887

SECTION XII
MEDICAL QIGONG APPENDICES 889

INTRODUCTION TO THE APPENDICES 890

APPENDIX 1A MEDICAL APPLICATIONS OF QIGONG 891
ABSTRACT 891
INTRODUCTION TO MEDICAL QIGONG 891
EXAMPLES OF MEDICAL APPLICATIONS OF QIGONG 892
THERAPEUTIC BALANCING OF THE CHANNELS AND FUNCTIONS OF THE BODY 892
HYPERTENSION 893
PREVENTION OF STROKE AND MORTALITY 893

IMPROVEMENTS IN HEART FUNCTION AND MICROCIRCULATION 894
IMPROVEMENT IN SEX HORMONE LEVELS 895
INCREASED BONE DENSITY 895
CANCER 896
REVERSING SENILITY 897
MIND-BODY REGULATION 898
BRAIN WAVES 898
BLOOD FLOW TO THE BRAIN 898
EFFECT OF RAPID AND LARGE CHANGES IN ALTITUDE 898
CARDIAC FUNCTION 898
MICROCIRCULATION DISORDERS 899
STUDY OF LUNG FUNCTION 899
SUMMARY AND CONCLUSIONS 899
REFERENCES 900

APPENDIX 1B ANTI-AGING BENEFITS OF QIGONG 903
INTRODUCTION 903
CLINICAL STUDIES INDICATING THE ANTI-AGING BENEFITS OF QIGONG 903
THERAPEUTIC BALANCING OF THE CHANNELS AND FUNCTIONS OF THE BODY BY QIGONG 904
BLOOD PRESSURE 904
MORTALITY AND STROKE 904
IMPROVEMENTS IN HEART FUNCTION AND MIRCROCIRCULATION 905
ENHANCED ACTIVITY OF ANTI-AGING ENZYME SOD 905
CARDIOVASCULAR FUNCTION 905
COMBINATION OF MEDICAL QIGONG AND DRUGS THERAPY 906
CONCLUSIONS 906
REFERENCES 907
ENDNOTES 907

APPENDIX 1C THE EFFECT OF QIGONG ON THERAPEUTIC BALANCING MEASURED BY ELEXTROACUPUNCTURE ACCORDING TO VOLL (EAV): A PRELIMINARY STUDY 910
ABSTRACT 910
INTRODUCTION 910
MATERIALS AND METHODS 911
RESULTS AND DISCUSSION 911
CONCLUSIONS 913
ACKNOWLEDGEMENTS 913
REFERENCES 913

APPENDIX 2 SCIENTIFIC INVESTIGATIONS INTO CHINESE MEDICAL QIGONG THERAPY 917
INTRODUCTION 917
QIGONG MASTERS AND ENERGETIC MEDICINE 918
THE SCIENCE OF CHINA 918
QIGONG'S LONG HISTORY 919
SIMULATION OF EMITTED QI 920
SCIENTIFIC PLAUSIBILITY OF QI, THE HUMAN ENERGY FIELD 920
REFERENCES 921
THE FUTURE OF QIGONG 921
INFRASONIC QIGONG RESEARCH 922
INFRASONIC SIMULATION OF EMITTED QI FROM QIGONG MASTERS 922
SUMMAY OF RESEARCH 922
DOUBTS ABOUT EMITTED QI 922

BACKGROUND 923
THE BRAIN AS A DETECTOR OF EMITTED QI 923
SCIENTIFIC CONTROLS 924
INFRASONIC VS. ELECTROMAGNETIC INTERFERENCE 925
SUMMARY 925
SECONDARY ACOUSTIC BIOLOGICAL RESPONSE 925
MEASUREMENT AND ANALYSIS OF INFRASONIC WAVES FROM EMITTED QI 927
NEURO SCIENCE—NERVE IMPINGEMENT AND EMITTED QI 928
INFRASONIC TREATMENT OF ASTHMA 929
TREATMENT METHOD 930
OBSERVATION CRITERIA—FOUR GRADES 930
THERAPEUTIC RESULTS 930
LABORATORY RESULTS 930
THE INFRASONIC SIGNAL FROM THE QIGONG PERSPECTIVE 931
MECHANISMS OF THE QGM 931
RELIEVES PAIN AND EDEMA 931
STRENGTHENS IMMUNE FUNCTION AND REDUCES INFLAMMATION 931
NORMALIZES AUTONOMIC NERVOUS SYSTEM 931
RELIEVES SOME SYMPTOMS OF HEART DISEASE 932
EMITTED QI TRAINING INCREASES INFRASONIC SOUND EMISSION OF HEALERS 932
SCIENTIFIC QIGONG RESEARCH 933
EFFECTS OF THE EMITTED QI ON HEALING OF EXPERIMENTAL FRACTURE 934
MEASURING QI IN THE BLOOD 935
EFFECTS OF QIGONG ON NEUROTRANSMITTERS 936
PHYSICAL CHARACTERISTICS OF EMITTED QI 937
RESULTS 938
SUPERCONDUCTING MAGNETOMETER MEASURES CHANGES DURING QIGONG 938
QIGONG AND CANCER 938
THE EFFECT OF THE EMITTED QI ON CARCINOMA CELLS 939
THE EFFECT OF EMITTED QI ON THE GASTRIC ADENOCARCINOMA CELLS: 939
SUMMARY: 940
QIGONG AS A THERAPEUTIC AID FOR ADVANCED CANCER PATIENTS 940
THE EFFECT OF EMITTED QI ON LEUKEMIA IN MICE 941
EFFECTS OF QIGONG ON MALIGNANT TUMOR 942
EFFECTS OF PATIENT TUMORS ON KIRLIAN IMAGES OF HEALTHCARE PROVIDERS 943
CHAOS AND CONSCIOUSNESS 945
LOW DIMENSIONAL CHAOS IN PRACTICING QIGONG 945
QIGONG TRAINING AND COHERENCE OF EEG 946
VIBRATIONAL TREMBLING, CHAOS, AND EEG 946
LABORATORY TESTING 947
CHAOS AND THE COLLEGE ENTRANCE EXAM 947
SEARCHING FOR JING, QI, AND SHEN IN WESTERN SCIENCE 948
CONCLUSION 949
THE ROLE OF CHAOS IN DISEASE AND HEALING 950
THERAPEUTIC CHAOS 951
IMPLICATIONS OF SCIENTIFIC QIGONG RESEARCH 952

APPENDIX 3 THE PSYCHOLOGICAL AND ENERGETIC MECHANISMS TRIGGERED IN THE HUMAN SYSTEM BY THE SELF-APPLIED HEALTH ENHANCEMENT METHODS QIGONG, TAIJI, AND YOGA 957
OXYGEN 957
LYMPH SYSTEM FUNCTION 960
BRAIN AND NERVOUS SYSTEM FUNCTION 964
ENERGETIC MECHANISMS 967
CONCLUSION 968
REFERENCES 970

GLOSSARY OF TERMS 973

BIBLIOGRAPHY 1003

CLINICAL REFERENCES 1009

INDEX 1011

ABOUT THE AUTHOR 1029
MEDICAL BACKGROUND 1029
MARTIAL ARTS BACKGROUND 1031

ADDITIONAL BRANCHES OF THE INTERNATIONAL INSTITUTE OF MEDICAL QIGONG 1033
BRANCHES WITHIN THE UNITED STATES 1033
INTERNATIONAL BRANCHES 1035

FORWARD

Dr. Jerry Alan Johnson's book on Medical Qigong and its clinical practices provides an important and necessary guide for students and advanced practitioners of Medical Qigong and Traditional Chinese Medicine.

The relevance of Dr. Johnson's Medical Qigong textbook can be seen against the larger back drop of alternative medicine. Alternative Medicine (also called complementary medicine) has become a catch word in the West and an increasingly important factor in health care. An article authored by David Eisenberg and others of the Harvard Medical School reported that in 1993, 30% of a group of people used some kind of Alternative Medicine for which they paid out of their own pockets. Extrapolated to the United States population, this group spent about $14 billion dollars, which was more than the amount spent on conventional Western care that year.

Among alternative medical therapies, Medical Qigong has blossomed explosively in Western countries during the past few years. Awareness of Medical Qigong in the United States was heightened by two international conferences on Qigong in 1990. In 1997, there were three conferences on Medical Qigong, in San Francisco, Minneapolis, and New York. Another catalyst was Bill Moyer's television documentary, "Healing and the Mind," which had a segment on Medical Qigong and Chinese medicine. In more recent years, dozens of books have been published on Qigong in English and presently there are at least 15 web sites on the World Wide Web devoted to Qigong. At this writing, many articles on Qigong have appeared in the newspapers and magazines, and several documentaries have been videotaped and others are in progress.

In China, almost everyone knows about Qigong and about 100 million people are said to practice it daily. Qigong dates back thousands of years. Many believe that it was responsible for the early development of Chinese medicine, which now includes therapy by acupuncture, herbs, massage, and nutrition.

Medical Qigong therapy was a secret art that was passed on from a master to selected persons. In the 1970s, Qigong became more accessible to the people when the Chinese government ordered that Medical Qigong be made public and serve alongside Western medicine to improve national health care. During the Cultural Revolution, Medical Qigong was suppressed because the government suspected that Qigong had religious and superstitious roots incompatible with communism. In the early 1980s, scientist in China were encouraged to carry out experimental and clinical studies into almost every aspect of how Medical Qigong affected the human body and contributed to healing. Starting in 1986, research findings were reported at international conferences on Medical Qigong held mostly in China but also in Japan, Canada, and the United States. The substance of the research studies are available in English in the Computerized Qigong Database, which was developed by the Qigong Institute. This database has provided a basis for the preparation of at least five books, three dissertations, and several research projects on Medical Qigong.

In 1992, the United States Congress recognized the potential of alternative / complementary medicine by mandating that the National Institutes of Health develop programs to evaluate the validity of selected alternative therapies. Since that time, the Office of Alternative Medicine has funded many research programs and disseminated valuable information to medical practitioners, scientists, and the public.

The swell in the interest in Medical Qigong and the recognition of its health and healing benefits have been recognized by schools of Traditional Chinese Medicine, many of which mandate that Qigong be a required course. The Qigong taught at these schools is still on a basic level and needs to be expanded to include the medical aspects of Qigong, such as described in this book.

The future of Medical Qigong and Chinese medicine appears bright. However, the need for well-trained and qualified teachers and practitioners is paramount to meeting the growing demand. Dr. Johnson's book provides the first guide in English for teachers, students, and practitioners.

Kenneth M. Sancier, Ph.D.
President Qigong Institute

FORWARD

In 1998, the Academy of Oriental Medicine at Austin gave me the opportunity to establish one of the first formal Medical Qigong training programs in the country to be offered within the context of a college of Oriental medicine. My greatest difficulty was in finding a reliable textbook for my classes. Of the numerous books on Qigong available in English, most devote only a few pages, at best, to Medical Qigong. Over the past few years, several books from China on Medical Qigong have been translated into English. Although presenting much new and valuable information, they are poorly translated and fraught with errors, making them unreliable as textbooks.

Therefore, it has been a great pleasure for me to have collaborated with Dr. Jerry Alan Johnson to some small extent on this book. Jerry Alan Johnson is one of the world's foremost authorities on the subject of Medical Qigong. This work distills several decades of his personal study, practice, and clinical experience in the United States and the People's Republic of China into an in-depth practical manual for all levels of Qigong healers.

Currently China is in the midst of what can only be called a Qigong renaissance. Today, more people are studying and practicing Qigong than in any previous time in Chinese history. In the not too distant past, Qigong was only available to monks and priests, nobles and the wealthy. Now Qigong is taught in China's primary schools and colleges, parks, temples, clinics, and hospitals to anyone who wants to learn.

China's literacy rate has increased exponentially since 1949, and now there are thousands of books, tapes, videos, and magazines on every aspect of Qigong, systems both ancient and modern, all available for general public consumption. Many regional, national, and international Medical Qigong associations have been formed, with an unprecedented exchange of information.

Although Medical Qigong has been a part of Traditional Chinese Medicine since the time of the Yellow Emperor, it has only been since 1982 that Medical Qigong hospitals and clinics have begun to spring up all over China. In the early days after the Communist Revolution of 1949, Qigong was more or less a state secret, and the Medical Qigong clinics were, for the most part, only available to high party officials. Over the past two decades, China has also devoted a great deal of effort to Qigong research and education. There are now large Medical Qigong hospitals in all of China's major cities, some of which have over 300 beds and 40 or more Qigong specialists and nurses on staff. There are hundreds of medium-and small-sized Medical Qigong clinics throughout the country, some treating inpatients and others treating only outpatients.

Before the revolution, the miracles of modern Western medicine, with its wonder drugs and surgical procedures, had caused many Chinese to see their own native traditional medicine as old-fashioned and outdated. The government encouraged the development of Western medical schools and hospitals. After the revolution, Chairman Mao recognized that with China's huge population they would need to take advantage of every form of medicine available even to begin to meet the nation's fundamental health care needs.

China is the only county in the world where Medical Qigong has been truly integrated and enthusiastically accepted as part of the national health care delivery system. According to current estimates, Medical Qigong doctors are now meeting 15% of China's national medical needs. That percentage is still growing. For decades, Chinese hospitals have successfully offered Traditional

Chinese Medicine alongside of Western medical services. Patients may receive Qigong or acupuncture anesthesia during Western surgical procedures and be treated by Medical Qigong, acupuncture, and Chinese herbal medicines during recovery. Chronic patients may be diagnosed by Western physicians, sent to Medical Qigong clinics for treatment, and have their Western doctors monitor their progress. In this respect, China has truly set the standard for the twenty-first century medicine.

Medical Qigong training and practice takes many forms in China. Some practitioners/healers are thoroughly trained in both Traditional Chinese Medicine and Western medicine, in addition to Medical Qigong. Others are heirs of family Medical Qigong systems, some dating back over a thousand years. Not all of these family practitioners have received additional training in either traditional Chinese medicine or Western medicine, yet they have been very efficient in treating disease and disorders that these conventional medicines have given up on. Still other practitioners come from martial arts backgrounds, such as Shaolin Gongfu or Daoist martial Qigong, with their own effective and unique blend of warrior training, spiritual discipline, Qigong and healing arts. Each of these categories contributes to the richness and diversity of the art of Medical Qigong.

Jerry Alan Johnson presents for us the art of Medical Qigong as it is being taught in two of the major Medical Qigong training centers in China today: the Xi Yuan Hospital of Traditional Chinese Medicine and its associated Hai Dian Medical Qigong College. Although each Qigong hospital in China defines its own program of training and practice, the material Johnson includes in this work represents the mainstream curriculum of study and practice widely accepted nationwide as a high standard of competence in Medical Qigong.

In addition to sharing the high-level protocols of Medical Qigong training in China, Johnson also draws from the reservoirs of his own decades of personal training and teaching in the internal martial arts to further enrich this work. Martial Qigong is generally practised to improve one's martial arts prowess. It includes Qigong exercises for strengthening the body; increasing power of one's strikes by emitting Qi; mind and will training; learning the vulnerable points to strike on an opponent's body to cause pain and paralysis; learning to cause serious injury or death by disrupting or destroying an opponent's internal organs, Qi and blood vessels, joints or bones; and toughening the body to withstand strikes and blows.

In what might at first seem a case of strange bedfellows, the martial Qigong tradition also has its medical side. Martial artists need to learn how to set bones and dislocations, as these injuries are commonly encountered in training and combat. Martial artists who train in the more secret arts of tien xue (vital point striking) and dim mak (death touch) are also taught how to heal the injuries that they have caused, both to heal themselves if struck by someone and to heal their opponents if the opponent is penitent. Furthermore, the martial artist who learns the methods for destroying the internal organs by emitting Qi can effectively adapt the same method to destroying pathogens and tumors in a patient for healing. Internationally recognized by his peers for his mastery of the most esoteric aspects of the internal martial arts, Johnson is eminently qualified to present its healing traditions, which he generously and openly does in this work.

I am grateful to know Dr. Jerry Alan Johnson as a colleague, teacher, and friend, and am happy to recommend this work to all students of Medical Qigong with confidence. Johnson's contribution contained herein represents the most thorough and comprehensive presentation of the art and science of Medical Qigong in the world to date. It is sure to become a modern standard of reference for anyone seeking knowledge of Medical Qigong.

Jampa Mackenzie Stewart, D.O.M.
Dean of Medical Qigong
Academy of Oriental Medicine at Austin

FORWARD

In the summer of 1995, I was sitting on the floor of Dr. Johnson's studio waiting for the start of the intermediate class in Medical Qigong. David Nakahara leaned over to introduce himself and asked me if I was a healer. Wow! It was one of those seminal moments in one's life. I considered all the implications of this question and the only relevant reply I, as a medical doctor, could muster was an ironic chuckle.

That question speaks to the heart of the current crisis in health care. Allopathic medicine lends itself to standardization of care and computer algorithms, since the structure of the clinical visit is based on protocol-derived diagnosis and treatment. The challenge is the diagnosis, but the treatment, especially high-tech treatment, gets all the press. It is incredibly satisfying to take care of people in this manner since the issues are clear and everyone gets better, unless they fail treatment; in this paradigm, the patient fails the treatment, the treatment does not fail the patient.

However, over time, you accumulate a number of patients for whom your therapeutic protocol fails, and I think that all thoughtful physicians recognize that it is these patients that teach us the most. There are women who have serious difficulty with PMS, infertility, and menopause. The cancer patients often wonder what caused the cancer to occur, what supports it, and what the meaning of this potentially fatal illness is for them. As physicians, once we emerge from the narcosis of fatigue and busyness that accompanies the daily practice of medicine in the late twentieth century, we also ask these same questions.

And we seek answers. Each physician develops his or her own rationale for treatment failures. They may rely on an unshakable faith in the scientific method, their religious upbringing or in their cultural ideals, or perhaps close themselves off entirely. I inadvertently found my answer within the martial arts.

It was clear to me from my Aikido practice that the superior martial artist must understand Qi in all its manifestations. This quest for deeper knowledge and experience of Qi led me to study Qigong with Dr. Johnson.

In my earliest lessons with Dr. Johnson, I was told that a Qigong therapist must observe and treat patients' *three treasures*: the physical body (jing or essence), their energy (Qi), and their mind/spirit/intention (shen). These three form the whole of a human being, and the parts can only be understood within the context of the whole. Furthermore, I learned that in life these three are so interrelated that it is difficult to tell where one leaves off and the other begins. Over 2,000 years ago, the Chinese philosopher Lie Zi described this by saying, "The mind leads and the Qi follows; the Qi leads and the body follows."

As a scientist, I could not help but draw the parallel between these fundamental Qigong principles and the revolutionary views of advanced modern physics: that at the deepest sub-atomic levels, matter, energy, and the person viewing them are so inextricably intertwined that they are seen as virtually one and the same, merely different manifestations of the same pattern. No longer is energy defined as a wave while matter is composed of particles. In quantum physics they have coined the term *wavicle* beause particles act as waves in one situation and as particles in another, as "probabilities" rather than concrete fixed entities and as subjective reality rather than objective.

The application of the discoveries of quantum physics to biology is just beginning. It is starting not only in the laboratory but also in many consulting rooms across the United States, as physicians search for the answers to help their patients.

I think that quantum physics is the only "hard" science that you can research just by thinking about it. As one observes the processes of nature, the thoughtful observer comes to the conclusion that there must be something else that accounts for the medical journey of the exceptional patient. The early practitioners of Ayurvedic and Chinese Medicine were careful observers of nature and through observation formulated the basic principles of Indian and Asian medical systems that are also corollaries of the principles of quantum physics.

Western awareness of the potential for the integration of the East and West began in 1971 when Nixon first went to China. James Reston, a *New York Times* correspondent covering the historic visit, developed acute appendicitis. After his emergency appendectomy, he was successfully treated with acupuncture for post-surgical pain.

Despite the dynamic nature of the penultimate Western nonbeliever confronting a totally novel experience ("only Nixon could go to China"), nothing much shifted or changed in medical practice at that time. What was missing was the readiness and ability to experience a paradigm shift in the conceptual basis of the causation of disease. Paradigm shifts in basic research have been eloquently discussed in Thomas Kuhn's landmark book, *The Structure of Scientific Revolutions*. Kuhn's brilliant analysis of the development of knowledge has recently been applied to medical science in a new book, *From Doctor to Healer: The Transformative Journey*, by Robbie Davis-Floyd and Gloria St. John. After 30 years, we are finally mature enough to begin to reassess the structure of our medical belief systems and to incorporate both world medicine and the principles of quantum physics. I have no doubt that this will take decades, but there is no doubt that the shift is beginning to occur.

Dr. Jerry Alan Johnson's book represents a major advance in this journey. This textbook is the first comprehensive treatise on the principles of Chinese energetic medical practice available to the Western medical practitioner. It also forms a bridge for the Western trained practitioner of Traditional Chinese Medicine and the allopathic (Western) practitioner. Dr. Johnson's book represents decades of research and study, and a nonjudgmental openness to any healing modality that is in the patient's best interest. I have no doubt that this book will represent a significant advance in that long awaited paradigm shift. I look forward to that time because it will address the deeper human values that have been neglected in protocol-based medicine and will bring a new depth of engagement and satisfaction to patient care.

Stephanie S. Taylor M.D., Ph.D.

Footnotes:

Kuhn, Thomas S., *The Structure of Scientific Revolutions*, University of Chicago Press, Chicago, Illinois 1962.

Davis-Floyd and Gloria St. John, *From Doctor to Healer: The Transformative Journey*. Rutgers University Press, New Brunswick, N.J., available March 1998.

FORWARD

In the Western nations at the turn of the millennium, following a century of remarkable medical breakthroughs, there still remains a major list of unsolved medical mysteries and health care challenges. Chronic disease has not been alleviated (asthma, arthritis, etc.); stress has been recognized as a major cause in many diseases; tumors and cancers are being diagnosed in exponentially growing numbers; AIDS is a world wide epidemic; negative (Western) drug interactions have grown to become the fourth leading cause of death, and medical error has emerged as the eighth cause of death. According to the Department of Health and Human Services, over 70% of medical visits are for symptoms and illnesses that are preventable, yet the health care system is still primarily focused on treatment of the symptoms rather than health maintenance or prevention.

The public, the government, and health care providers all agree that there is a crisis in Western medicine and health care. Fortunately, at the same time, there is increasing support for innovative and alternative solutions. Among the many powerful strategies for solving this crisis, Chinese Medical Qigong (Chi Kung) and its offspring Taijiquan (Tai Chi Chuan), meditation, and focused breath practice, are probably the most comprehensive systems of self-care and healing available to compliment both conventional Western and alternative medical therapies.

The public hunger for natural healing, safety from medical side effects, lower medical costs, and health self-reliance is triggering powerful and profound changes in health care. It has become obvious that in the near future the benefits of Chinese medicine will be as fully integrated here in the U.S., as the benefits of Western medicine are in China. Through this global exchange of health care wisdom and practical applications, we are entering an unprecedented era of new possibilities to resolve suffering and foster well-being.

This definitive work on Medical Qigong, the remarkable healing art from Chinese traditional medicine, will play a significant role in the immense and profound transformation in health care that is now occurring with tremendous social and economic force.

Like the revolution in training and licensing acupuncturists that quickly unfolded in the final years of the 20th century, the momentum of training and licensing Medical Qigong Therapists is rapidly increasing in the beginning of the 21st century. Clinical Qigong, including both Medical Qigong Prescriptions and Medical Qigong Therapy, will arise in America as it has done so robustly in China.

There are a number of excellent books on various aspects and methods of Qigong. However, there has not been, in English, a comprehensive exploration of Medical Qigong. Dr. Johnson has created a breakthrough work on Medical Qigong, which is a clear and useful revelation of the Medical Qigong curriculum at the Hai Dian University Medical Qigong College of Beijing, China, and an excellent synthesis of Medical Qigong theory from throughout China. This textbook will very likely remain the definitive compendium of Medical Qigong in the West for many years, and become the foundation from which the field of Medical Qigong will evolve in Western society.

Roger Jahnke, O.M.D.
Chair, Department of Medical Qigong
Santa Barbara College of Oriental Medicine

PREFACE

As we enter the new millennium, a new era of medical therapy is beginning to blossom. Alternative medicine is now capturing an estimated $14 billion in out-of-pocket health care revenues from Americans each year, according to a 1993 study published in the *New England Journal of Medicine.* By 1997, according to the *Journal of American Medical Association,* that figure had more then doubled. What this trend means in real terms, is that despite the historical lack of official recognition by the American Medical Association, despite the lack of endorsement and coverage by Medicare and the majority of health insurance plans, men and women, in ever increasing numbers, are going to acupuncturists, energetic healers, herbalists, chiropractors, massage therapists, ayurvedic specialists, homeopathic doctors, and other traditional "healers" to meet some portion of their health care needs.

This growth of public reliance on alternative medicine has caused the Western medical establishment to sit up and take notice. In fact, some of the most vocal proponents of combining alternative medical traditions with Western medicine are medical doctors. Visionary physicians such as Deepak Chopra, Andrew Weil, Larry Dossey, Dean Ornish, and Bernie Seigel have led the way toward creating a new climate of respect for ancient medical philosophies and modalities. They have pioneered the advent in the West of health care facilities where Western medical and alternative health modalities are available under the same roof, with the goal of providing patients with the best of both worlds. This combination of ancient and modern medical traditions has been dubbed *integrative* or *complementary* medicine.

In comprehending the full implications of this unlikely marriage, one must understand the divergent approaches to healing between conventional Western medicine and traditional Eastern medicine.

Contemporary Western medicine grew out of the scientific revolution of the seventeenth century. The philosophy of science, rooted in Aristotle's "empirical materialism," was given a new spin by the French mathematician, Descartes. Viewing reality as that which could be substantiated materially, Descartes applied an analytical reductionist logic to penetrating the secrets of nature, including biology. These views were echoed in the physics of Sir Isaac Newton, applying a linear cause-and-effect model to explain the workings of a material universe.

Man was seen as being separate from nature, mind was seen as separate from body, and all of these processes, in nature and in humans, were seen as similar to the workings of a machine composed of discreet parts. Mechanical laws were seen to govern all processes. Structure determines function; therefore, the physician's role developed into that of a mechanic: repairing, removing, transplanting, and replacing broken down-parts. Diseases had isolated causes, which need to be removed from the rest of the parts. Because of this approach, Western medicine has the most highly developed pharmaceuticals to kill specific organisms and the finest surgical procedures in the world today.

By contrast, Eastern medicine grew out of the empirical observation of nature, beginning at least 4,700 years ago. Oriental philosophy, from the Vedas of India to the Yellow Emperor of China, views reality as an interdependent whole. This "prescientific" understanding equates to the broader view of modern quantum physics and the general systems theory. Rather than limiting reality to that which is material, the Eastern philosophers recognized the interdependence of mind and body, the nonlinear nature of time and space, and the interweaving patterns of relationship between man and nature; in fact, they believed, we *are* nature. Anatomy, the study of human structure, takes a back seat to physiology, the study of human function. Thus, the Orientals formulated a general systems theory, in which the patterns of change that exist in nature are the same patterns that govern human biology, wherein function is viewed from a holographic perspective, and each part reflects the whole. Rather than being fixed and stable, the whole is in a dynamic process of constant change. For the whole to function harmoniously, every part must remain in balance. Therefore, the role of the Oriental physician is more similar to a gardener, following the patterns of change, diagnosing functional disharmony and restoring overall balance. Because of this approach, Oriental medicine has some of the most highly developed procedures for preventative medicine and for treating chronic diseases in the world today.

Western medical science, with its fundamental distrust of subjective diagnostic reliability, has progressed toward developing more and more expensive high-tech laboratory tests and diagnostic equipment. Thus we have the modern miracles of x-rays, MRI's, and ultrasound. Eastern medicine, trusting in human capacity, has progressed in a low-tech direction toward ever deeper training of the physician's sensory and spiritual diagnostic tools. Thus, we have the miracles of pulse diagnosis, tongue reading, and Qigong hand scanning.

With such fundamental divergencies in philosophy and technique, it is almost inconceivable that these two medical systems could ever operate together in the same setting. The fact is that they do function together, and quite effectively, too. We can thank Mao Zedong for the union of these two unlikely bedfellows.

Recognizing that there were far too few Western trained physicians and nurses to meet the primary health care needs of China's vast population, from the outset of his leadership Mao advocated the systemization of Traditional Chinese Medicine (TCM), and advocated its implementation alongside Western medicine in China's hospitals and clinics. The results of this integration have been astonishing, as witnessed in the effective use of acupuncture anesthesia during surgery.

Nonetheless, in his efforts to create a "modern" Chinese medicine, Mao shunned some of the traditional theoretical aspects of Chinese medicine, such as the concept of Qi, which he considered as feudalistic and counterrevolutionary. For this reason, he actively discouraged Medical Qigong practice as superstitious. It was not until the end of the Cultural Revolution in 1975 that Qigong reclaimed its rightful place as one of the major branches of Chinese medicine.

A high party official in Beijing was suffering from an "incurable" disease. Both Western medicine and TCM had failed to alleviate his suffering. In desperation, he went to one of the few Medical Qigong clinics operating in the country and was cured. The official then lent his support to the promotion of Medical Qigong for the benefit of the Chinese people. Before long, there were hundreds of Medical Qigong hospitals and clinics throughout China.

Since that time, Qigong has experienced an unprecedented growth in China. Qigong is now available to the general populace for the first time in history. Qigong is now taught in the public education system, beginning at the elementary school level. Qigong departments have been added to large urban hospitals. Colleges of Traditional Chinese Medicine have developed Medical Qigong training programs. According to one recent survey, one third of the population of Beijing, China's capital city, practices Qigong daily.

It has taken acupuncture and Chinese herbology nearly 20 years to develop into a respected profession in the United States. As this book goes to press, 37 states now have legislation licensing professional acupuncture practice, with an additional 10 states in which legislation has currently been introduced. Medical Qigong is still at the very early stages of public recognition, understanding, and acceptance by comparison. Oriental medical schools around the United States, as well as independent Medical Qigong masters, are only now beginning to establish comprehensive

Medical Qigong training programs. I am heartened by this development.

Traditional Chinese medical therapy is divided into four main branches: acupuncture, herbs and diet, massage therapy, and Medical Qigong. It is important for TCM practitioners to have exposure to all four branches to be able to understand the relative strengths and limitations of their particular field of expertise, so that they will be able to select the most effective and appropriate treatment modality for their patients. Until very recently, most schools in America have been relatively unaware of the extent to which Medical Qigong therapy has developed in China, and have been lacking in presenting Medical Qigong as a significant part of their training programs for students of Oriental medicine.

The purpose of this book is twofold. The first purpose is to apprise the reader of the professional standards of knowledge and skill required in contemporary China for licensing a "Doctor of Medical Qigong Therapy" (D.M.Q.). The second purpose is to describe how to effectively diagnose and treat patients with Medical Qigong therapy as set forth by the Hai Dian Medical Qigong College of Beijing and to provide a textbook for training to that standard under the guidance of a qualified instructor. Hai Dian is recognized as one of the top Medical Qigong colleges in China.

Although this book is primarily written for students and practitioners of Oriental medicine, it is also my hope that practitioners and students of Western medicine and other forms of alternative healing will benefit from the information contained herein, and that it may serve to enrich their practice in the healing arts.

This book is divided into twelve sections. The first four sections focus on building a comprehensive foundation in energetic medicine. The second four sections focus on guidelines for establishing a Medical Qigong clinic, as well as for diagnosing and treating problems of Qi deviations. The last four sections focus on treatment modalities, Medical Qigong prescriptions, Medical Qigong regulation exercises and scientific research in Medical Qigong clinical therapy.

I have done my best to present the knowledge and wisdom of this ancient Chinese art as it was passed onto me personally by my respected teachers, to whom I owe undying gratitude. Qigong has survived nearly five thousand years of growth and refinement and is now available to you, the reader, for your own personal and professional benefit. I sincerely hope that this book may serve to further bridge the partnership between Eastern and Western medicine, that all humanity may be the beneficiary of the interchange between these two great schools of healing. May all doctors and healers, Western and alternative, return to the "heart" of medicine, that each may view the patient as a complete integration of body, mind, emotion, energy, and spirit. May we support each other's skills and techniques in alleviating our patients' suffering.

Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
Dean of Medical Qigong Science
Director of Medical Qigong Clinic
Five Branches Institute, College & Clinic of TCM
Santa Cruz, California
May, 2000

ACKNOWLEDGMENTS

I would like to express my sincere gratitude to my many friends and colleagues who helped encourage and support me in writing this book: Roger Jahnke, O.M.D.; Hu Jiting, D.T.C.M.; Zhang Jingchuan, D.T.C.M.; Xu Zhuoqun, D.T.C.M.; Guo Xianhe, D.T.C.M.; Wan Taowang, D.M.Q.; William H. Lewington, L.Ac., M.Q.T.; Adam Atman, L.Ac. M.Q.T.; Tim M. Haun, D.C.; Kerrean D. Smith; Geoffrey Greenspahn M.Q.T.; Michael Winn; Mark Johnson; and my good friend Joseph Crandall.

I am also indebted to Dr. Pang Donghui, the Executive Deputy President of the Hai Dian Qigong College of Beijing, China, and to Li Fudong, D.M.Q. the university's chief director of Medical Qigong Science, and his assistants, Lu Guohong, D.M.Q. and Niu Yuhua, D.M.Q. for their constant support and encouragement, and for sharing their innermost secrets on Medical Qigong therapy.

I am very grateful to Dr. Teng Yingbo, D.M.Q., president and secretary general of the Beijing Western District Qigong Science and Research Institute, for his constant support and openness in sharing the knowledge of the Institute's clinical modalities.

A special thanks to Doctor Bi Yongsheng, D.M.Q.; Yu Wenping, D.M.Q.; and the Shandong Provincial Qigong Association for their wealth of knowledge and enthusiastic support, in sharing their clinical Qigong modalities, and to Dr. He Sihai, D.M.Q., of the Zhe Jiang Qigong Hospital for his openness and kindness in sharing his knowledge.

A special thanks to Qigong Master Zheng Zhanding, D.M.Q., for being my mentor, taking me under his wing, and teaching me advanced clinical modalities of energetic diagnosis and treatments, and to Qigong and Taiji Master Zhang Yufei for teaching, supporting, and encouraging my energetic and healing practice.

I am also indebted to Professor Lu and doctors Xu Hongtao, D.M.Q.; Ren Shuntu, D.M.Q.; Xu Zongwei, D.M.Q.; and the directors, teachers, interpreters and staff at the Xi Yuan Hospital of Traditional Chinese Medicine for their help and support.

I am very grateful to Sun Shuchun, D.T.C.M., the assistant professor and dean of the Beijing Academy of Acupuncture, Orthopedics, and Traumatology and the Hu Guo Si Hospital of Traditional Chinese Medicine for his assistance and support.

I would like to thank Doctor Meng Xiantong and Tara Peng, D.M.Q., of the Beijing Chengjian Integrated Traditional Chinese Medicine and Western Medical Experts Clinic for sharing their clinical modalities and their support.

I am very grateful to Madame Wang Yan of the China, Beijing International Acupuncture Training Center, the Acupuncture Institute of China Academy of Traditional Chinese Medicine, and the World Health Organization Collaborating Center for Traditional Medicine for supporting and believing in me.

I would also like to thank President Yue Licui, D.T.C.M., of the World Academic Society of Medical Qigong and all my friends and colleagues at the Beijing College of Traditional Chinese Medicine for their help and support.

A special thanks to Stephanie Taylor, M.D., Ph.D., whose encouragement and support has enabled Chinese Medical Qigong therapy to expand far into the terrain of conventional Western medicine, bridging the gap between these two schools with complementary modalities of healing.

A special thanks to Jason Gill, L.Ac., for his unselfish heart of giving and his invaluable help and technical input on Traditional Chinese Medicine, and his own personal experiences with Medical Qigong therapy.

A special thanks to Kenneth M. Sancier, Ph.D., and the Qigong Institute of Menlo Park, CA. Dr. Sancier's extensive research in Medical Qigong therapy, and the validity of its effect as a clinical modality is disclosed in Appendix 1 at the back of this text. Dr. Sancier is a council board member of the World Academic Society of Medical Qigong, sanctioned in Beijing, China.

A special thanks to Richard H. Lee. and the China Healthways Institute of San Clemente, CA. Mr. Lee's extensive research in the scientific investigations into Medical Qigong therapy and the validity of its effect as a clinical modality is disclosed in Appendix 2 at the back of this text. Mr. Lee is also a council board member of the World Academic Society of Medical Qigong, sanctioned in Beijing, China.

I greatly appreciate the assistance of Robert Collier, Jed Friedland, Stephanie Hensey, Terri Vandercook and Rose Mary Stewart, who spent many painstaking hours typing and deciphering my personal notes and course manuals. I would especially like to thank Jampa Mackenzie Stewart, D.O.M., L.Ac., Gaeir L. Dietrich, and Jean Vlamynck, M.Q.T., L.Ac., for their invaluable help and contribution in editing this textbook.

A special thanks to Madeleine H. Howell, M.F.T., as the senior editor of this manuscript for publication. Her keen eye for detail and constant encouragement to rewrite, explain and expound on the contents within this textbook, has resulted in a more comprehensive resource for future Medical Qigong students and Western medical professionals.

A special thanks to Robert Blaisdell and Tomo Y. for their excellent artwork and graphics, and to Y. S. Lim for his many painstaking hours of Translating Chinese Medical Qigong texts, which enabled me to draw from more comprehensive and clinical resources.

I am grateful to Willis Campbell and Niki Norrell, L.Ac., Dipl.Ac. (NCCA), M.T.C.M. for taking several of the photos.

A special thanks to Irene Morris for her excellent work on designing the front and back cover of this textbook.

Above all, I would like to express my love, gratitude, and respect to my parents Antoinette and Lt. Cdr. (Rt.) Perry E. J. Johnson for their years of love, understanding, encouragement, and support.

Finally, to my three beautiful daughters Laura, Leah, and Hannah, whom I will love forever.

INTRODUCTION

The Eastern approach in explaining medical concepts is generally expressed through a three dimensional convergence, seeing the physical body as an energetic hologram, and observing the physical, mental, emotional, energetic and spiritual reality of the tissues. By stimulating any one of these five energetic matrices, you affect the other four, and influence the body to initiate either health or disease. Diagnosis and treatment is therefore approached in a nonlinear progression, working towards the health and healing of the whole person.

The Western mind, however, is taught to view the physical body on a linear progression of cause and affect, separating the reactions of the tissues from the effect of the mind and emotions, as well as the universal and environmental influences. In order to help the Western mind understand the concept of Chinese energetic medicine, this Medical Qigong textbook was written with the goal of instructional comprehension and practical application of Chinese energetic medicine. It embraces the concepts of traditional Chinese medicine, in particular Medical Qigong therapy, from a progressive linear format. Beginning with Energetic Embryology in Section 1, it provides a basic understanding of complex energetic structure, theory, and practical application, ending in advanced clinical treatments in Section 11. The final chapters of this textbook, consists of scientific research collected from various doctors and research scientists which validate the claims made of Medical Qigong therapy being an effective clinical modality, in Section 12.

Chinese medical terminology is extremely metaphoric and is used to describe the many aspects of the human body through physical, mental, emotional, energetic, and spiritual domains of existence. Many technical terms in Traditional Chinese Medicine have numerous meanings, depending on the context of the subject.

For clarity, the Chinese terms in this book are capitalized along with the English words for which Traditional Chinese Medicine assigns a special meaning. Such words include, but are not limited to, the following: Gall Bladder, Small Intestine, Spleen, Pericardium, Bladder, Liver, etc. There is one exception to this rule; the word "energy" meaning Qi, is capped only in the first few chapters of this book for the sake of easier legibility, as it appears so often within each chapter.

When you see words such as Blood, Heart, and Marrow capitalized, assume that their meaning differs from that ascribed by Western medicine. In Traditional Chinese Medicine, the word Marrow, for instance, does not refer to bone marrow as it is traditionally recognized in the West, but rather describes the substance which is the common matrix of bones, bone marrow, the brain and spinal cord. Non-capitalized terms retain their traditional Western meanings.

One decision I have made when writing this textbook is to use the term "divine" when expressing the energy of the Dao or God. In China, many of the Qigong doctors and masters that I have trained with asked me to keep these spiritual theories in confidence for fear of governmental reprisal. Therefore, having decided to openly share these ancient energetic theories concerning the interactions of the spirit, soul and divine, I have done so without revealing my sources.

Finally, many of the energies used to describe the natural forces of nature (existing within Heaven, Earth, and Man) were historically changed into "gods" or "spirits" in order to compete with the colorful deities imported into China from India. Therefore, when reading this textbook, the reader should not become confused by certain terminologies describing "deities" which govern specific energetic principles. For example, when reading the section on the Eternal Soul, the title "Lords of the Three Dantians" implies the fact that the soul has three primary, separate, yet interconnected, energetic properties, rooted, divided and sustained within each of the Three Dantians.

Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)

SECTION I

FOUNDATIONS OF CHINESE ENERGETIC MEDICINE

CHAPTER 1
INTRODUCTION TO MEDICAL QIGONG

More than 5000 years ago, Chinese physicians came to understand that everything is composed of the same energetic substance called Qi (pronounced "chee"). These ancient masters concluded that there is a oneness and wholeness in all existence, and that energetically everything is interconnected as one body, although energy may appear to take on many different forms. All things in nature and, in fact, all things in the universe are woven together so that we are, quite literally, all symbiotically one with the universe through the system of Qi. Qi is always in motion within all things, and is the catalyst for everything to relate and interrelate within the universe.

In modern times, the laws of physics have demonstrated that matter and energy are interchangeable, and that matter is simply another form of energy. Matter is constantly vibrating in the form of tangible solids and intangible gases, and is constantly altering, being affected by, or interacting with energy. Energy is inherent in the living human body, and the human body is sustained by energy (Figure 1.1).

The ancients mastered techniques to balance the body's energy (Qi) in order to live in harmony with the environmental (Earthly) Qi as well as the universal (Heavenly) Qi. Traditional Chinese Medicine maintains that when living things start to lose their Qi, they lose their vitality. An ancient Chinese saying states, "Life comes into beginning because Qi is amassed; when Qi is scattered, the person dies."

Qi is stored within the body in the form of pools, creating the structures of the internal organs. From these internal pools, the body's life-force energy flows in the form of rivers and streams. These energetic rivers and streams form the body's vessels, channels, and collateral systems.



Figure 1.1. The Body's External Qi Field

THE FIVE DOMINIONS OF ENERGY

The ancient masters observed that Qi can be divided into five manifestations of matter and energy: mineral, plant, animal, human, and divine. Each form draws on the energy of the next, resonating and interacting with the divine through the form's relationship in Wuji (infinite space). The five manifestations of matter and energy are explained as follows.

1. The mineral's energetic field is considered the densest (i.e., the slowest) or lowest form of energetic vibration. The disintegration or division of the mineral's particles combine with the elements of air and water to form the Earth's soil. Every particle in the soil still retains the original primordial energy force of the mineral, which interacts with the energy of the divine.
2. The plant's energetic field is considered the next higher form of energetic vibration. All of

the Earth's vegetation (trees, bushes, flowers, herbs, etc.) absorbs a part of its life-energy from the mineral's energetic field, increasing and multiplying its energetic potential. The plant's energetic field is considered the next higher step in energetic evolution towards the divine energetic field.

3. The animal's energetic field is considered the next higher form of energetic vibration. The animal consumes and absorbs the energy from the plant's energetic field, further increasing and multiplying its energetic potential, bringing it one step closer towards the divine energetic field. Within each higher frequency of vibration there is also an increase in consciousness and level of awareness.
4. The human energetic field is considered the next highest form of energetic vibration. Mankind stands between Heaven and Earth, partaking of both energy fields. Through diet, Qigong practice, prayer, and meditation, humans can further refine and multiply their energetic potential.
5. The divine energetic field is the highest vibrational expression of energy known. As it envelops and becomes active within the human body, it further increases and multiplies the body's energetic potential, allowing man to attain divine consciousness.

All these energetic fields originate from one source, and all contain the vibrations of the one divine life-force. Likewise, with an attitude of deep respect for plants and animals that give up their life-force energy for our consumption, it is possible to enhance the nutritional value of the substances they provide us with. The blessing of food, and food prepared with a loving attitude, allows for the absorption of not only the vitamins and minerals contained therein, but also the absorption of the higher vibrations of the one divine energy inherent in all things. This is why many ancient cultures, often referred to as "primitive," prayed before hunting so that the animal spirit would willing give itself for sacrifice. Prayers were also given after the kill to free the animal's spirit so that it could return back to the divine.

Yang .	**. Yin**
active .	. passive
creative .	. receptive
masculine .	. feminine
front .	. back
left .	. right
fire .	. water
hot .	. cold
dry .	. wet
hard .	. soft
light .	. heavy
bright .	. dark
heaven .	. earth
sun .	. moon



Figure 1.2. The table above shows some characteristics of Yang and Yin. Below is the Yin/Yang symbol: white represents Yang and black represents Yin. The small circles, one white and the other black, symbolize the fact that Yin is always transforming into Yang and Yang into Yin. (For more on Yin and Yang, see Chapter 3.)

Once individuals becomes aware of the divine energetic field, they begin to experience the refined vibrational energy fields of minerals, plants, animals and human beings. This increased awareness of the divine life-force energy strengthens the awareness of one's own energetic fields and that of others. This in turn can deepen the conscious and unconscious energetic connections between ourselves and others, be they human, animal, plant or mineral.

DEFINING THE ENERGY OF YIN AND YANG

Each of the five energetic fields can be further divided into Yin and Yang aspects. In Traditional Chinese Medicine (TCM), the theory of Yin and Yang energy represents the duality of balance and harmony within the body, as well as within the universe (Figure 1.2). Earth energy is Yin, while Heaven energy is Yang.

Yin exists within Yang, and Yang within Yin. Yang manifests as active, creative, masculine, hot, hard, light, and bright. Yin manifests as passive, receptive, feminine, cold, soft, and dark. The dynamic balance of Yin and Yang always changes and transforms the body's life-force energy. (See Chapter 3 for more on Yin and Yang energy.)

Successful practitioners in balancing the body's Yin-Yang energies were considered masters or "immortals," able to harmonize the body with the mind, the mind with the will, the will with the breath, the breath with the spirit, the spirit with motion, and finally, motion with the surrounding environment (Earth), the universe (Heaven), and the divine (Dao).

UNDERSTANDING THE CONCEPT OF QI

While the concept of Qi may seem complicated, it is actually very simple. Matter progresses to energy and energy to spirit. Qi is the medium, or bridge, between matter and spirit. Once we become aware of the reality of Qi, it becomes easily recognized.

Through observation and study, Chinese Qigong (pronounced chee-gung) masters discovered that each organ in the human body has a different function and a different speed of energetic vibration. By tracing the pathways (channels) Qi takes through each organ and observing the effects on bodily functions, the Chinese developed the basic theories upon which Qigong practice is founded. For thousands of years, Chinese medicine has successfully cured serious illnesses by stimulating the body's energy in very specific ways.

Through the study of Qigong, anyone wishing to cultivate awareness of the energy vibrations and their own individual pathways can learn to influence and even control them. Qigong practitioners use these skills to heal and strengthen the immune system, and to improve the functioning of various organ systems within the body. China Healthways International estimates that in Beijing alone more than 1.3 million people practice some form of Qigong every day, whereas, in China as a whole, around 80 million people practice Qigong.

DIFFERENT SCHOOLS OF QIGONG

Qi means "life-force energy" and gong means "skill," so Qigong is the skillful practice of gathering, circulating, and applying life-force energy. In China today, Qigong practice is divided into three main schools: medical, martial, and spiritual. The three schools are all based on the same philosophical system and share many of the same meditations and techniques. The schools differ primarily in focus. Students choose a school based on the use to which they want to put their Qigong training. Briefly, each school focuses on one of the following specialties:

1. The medical school trains doctors and healers in special Qigong methods for health maintenance and longevity, disease prevention, and the diagnosis and treatment of diseases and disorders. The three primary techniques of Medical Qigong therapy include the following.
    a. Purging to detoxify the body of pathogens,
    b. Tonifying to strengthen the body's internal organs and systems, and
    c. Regulating to balance the body's internal energy.
2. The martial school trains martial artists to

build their strength and power for performing martial arts applications. The three primary techniques of martial Qigong training include the following.

   a. Obvious Power (Ming Jing) techniques emphasize the training and conditioning of the muscles, strengthening the bone structure, and increasing the individual's overall stamina. This school also includes such techniques as pounding the body (arms, hands, legs, and torso) to strengthen and toughen the tissues.
   b. Hidden Power (An Jing) techniques emphasize stretching and twisting the tendons and ligaments (known as Reeling and Pulling the Silk) to cultivate resonant vibration within the body for striking and issuing power.
   c. Mysterious Power (Hua Jing) techniques emphasize the training and conditioning the mind's imagination and intention, to project and utilize the power of the individual's Shen (Spirit).

3. The spiritual school trains practitioners who seek spiritual transformation and enlightenment (Daoism, Buddhism, and Confucianism each have their own unique techniques). Their techniques include meditations for fusing, as well as releasing the Three Ethereal Souls (Hun). These souls can best be understood as personifications of moral qualities (or archetypes). When the Hun are fully developed, the practitioner acquires certain extraordinary powers and abilities, such as soul travel. The goal however, is to achieve transformation and a state of enlightenment, and not be led astray by the glamor of extra powers. The three primary techniques of spiritual Qigong training include the following:
   a. Nourishing the Spirit (Shen), to strengthen and refine the power of the individual's Shen,
   b. Housing the Shen by disciplining both thoughts and emotions, to relax and tranquilize the individual's Shen, and to become more receptive to divine energy and guidance, and
   c. Combining the Shen with the Qi, to coordinate the breath and intention for directing the spirit to guide the body's life-force energy.

Qigong training involves all of the individual's physical senses. The concentration is focused on breathing, hearing, visualizing, and muscle relaxation. Massage, and movement are also used to develop and control the body's intrinsic energy. Studying Qigong requires not only comprehending the immeasurable wisdom gathered for medical, martial, or spiritual development but also studying the ancient Chinese culture inherent within these systems.

MEDICAL QIGONG DEFINED

All living bodies generate an external field of energy called Wei Qi (pronounced "whey chee"), which translates as "protective energy." The definition of Wei Qi in Medical Qigong is slightly different than that of Traditional Chinese Medicine (TCM). In classical TCM texts, the Wei Qi field is seen to be limited to the surface of the body, circulating within the tendon and muscle tissues. In Medical Qigong, however, the Wei Qi field also includes the three external layers of the body's auric and subtle energy fields. This energy originates from each of the internal organs and radiates through the external tissues. There the Wei Qi forms an energy field that radiates from the entire physical body. This field of Qi protects the body from the invasion of external pathogens and communicates with, as well as interacts with, the surrounding universal and environmental energy fields.

Both internal and external pathogenic factors affect the structural formation of the Wei Qi. The internal factors include suppressed emotional influences (such as anger and grief from emotional traumas); The external factors include environmental influences when they are too severe or chronic, such as Cold, Damp, Heat, or Wind, etc. Physical traumas also affect the Wei Qi field.

Any negative interchange affects the Wei Qi by literally creating holes within the matrix of the individual's external energetic fields. When left unattended, these holes leave the body vulnerable to penetration, and disease begins to take root in the body. Strong emotions, in the form of toxic energy, become trapped within the body's tissues when we hold back or do not integrate our feelings. These unprocessed emotions block the natural flow of Qi, thus creating stagnant pools of toxic energy within the body.

Medical Qigong consists of specific techniques that use the knowledge of the body's internal and external energy fields to purge, tonify, and balance these energies. Medical Qigong therapy offers patients a safe and effective way to rid themselves of toxic pathogens and years of painful emotions that otherwise, can cause mental and physical illness. This therapy combines breathing techniques with movement, creative visualization, and spiritual intent to improve health, personal power, and control over one's own life.

MEDICAL QIGONG TRAINING IN CHINA

There are numerous colleges of Traditional Chinese Medicine throughout China today that focus on Medical Qigong training. The majority support the scientific study and expansion of Medical Qigong applications and Traditional Chinese Medicine treatments.

According to Qigong master and doctor of Traditional Chinese Medicine, Professor Zhou Qianchuan, all of the most famous Chinese doctors of acupuncture and moxibustion, herbal medicine, bone setting, and massage therapy, either practiced Qigong or incorporated Qigong into their clinical practices.

Major traditional Chinese medical colleges in China offer comprehensive, government-sponsored, three-year programs in Medical Qigong therapy. Programs include classes, labs, and seminars on traditional Chinese medical theory. These studies include: The foundations of Chinese medicine for internal diseases according to *the Yellow Emperor's Inner Canon, Spiritual Axis, Essential Questions,* and *the Canon of Perplexities*. The Medical Qigong classes also include energetic anatomy and physiology, diagnosis and symptomatology, energetic psychology, Qigong pathology, Medical Qigong therapy, as well as a survey of other related medical modalities. The other related modalities include: a comprehensive understanding of herbal medicine, acupuncture therapy, and Chinese massage. Classes of Western anatomy and physiology, Western internal diseases, and health and recovery, are also required.

During the certification program, three to five training hours a day accompany the standard six-day-a-week classroom curriculum. Course content, personal mastery of energy extension, and diagnosis techniques are rigorously tested each week. Upon completing the required courses and passing the final exams, the student receives a certificate of completion. Next, a six-month to one-year internship is required at a program-affiliated hospital or clinic. Upon successful completion of this internship, the new doctor is licensed as a doctor of Medical Qigong therapy by the People's Republic of China's Bureau of Scientific Technology.

Each internship program is assigned a separate wing in the selected Chinese hospitals. Both inpatient and outpatient facilities are available to the public. Each branch has specific approaches to healing a patient, with its own unique set of ground rules for diagnosis and treatment.

There are three distinct supervisory levels working within each clinical branch of Traditional Chinese Medicine in China. The first and lowest position is that of a "doctor of Medical Qigong," who is responsible for the treatment of all clinical patients (including patients in both the inpatient and outpatient clinics). The positions of Medical Qigong doctor are generally filled by the medical college graduates who have spent four to five years in clinical study and practice. The next level is called a "physician or doctor in-charge," and denotes a senior position within the clinic. This individual is responsible for the supervision of all the Qigong doctors' clinical procedures. This position is usually obtained after spending a minimum of five years as a Qigong doctor. The final and highest level is called a "director or professor;" this position requires overseeing the doctors in-charge, as well as teaching, treating, and training of other doctors to pass on Qigong clinical knowledge to future generations. This position is usually obtained after spending a minimum of five to six years as a doctor in-charge.

The licensing is reviewed and issued by either the People's Republic of China's Bureau of Scientific Technology (that issues a license in local city hospitals) or by the Ministry of Scientific Technology (that licenses to practice in any clinic or hospital throughout China). The Qigong doctor's skills are tested through oral, written and practical examinations, and a license is issued accordingly. In China today, there are five positions available for a doctor of Traditional Chinese Medicine. These five positions are described as follows.

1. A Doctor of Acupuncture Therapy (D.Ac.) specializes in the five main modalities of Chinese acupuncture.
2. A Doctor of Herbal Medicine (D.H.M.) specializes in the five main modalities of Chinese herbology.
3. A Doctor of Massage Therapy (D.M.T.) specializes in the five main modalities of Chinese massage and tissue regulation.
4. A Doctor of Medical Qigong Therapy (D.M.Q.) specializes in the five main modalities of Chinese Medical Qigong.
5. A Doctor of Traditional Chinese Medicine (D.T.C.M.) is a doctor who has trained in all four branches of Traditional Chinese Medicine (acupuncture, herbs, massage, and Medical Qigong).

MEDICAL QIGONG TRAINING IN THE UNITED STATES

The Five Branches Institute, College and Clinic of Traditional Chinese Medicine became the first TCM / Acupuncture College in the United States to open a Medical Qigong Clinic on April 7th., 2000. This clinic not only serves as an invaluable teaching resource for the Five Branches acupuncture students, but also serves as an affordable alternative medical clinic for the general public.

Founded in 1984, the Five Branches Institute has been known not only for its leadership in TCM education, but also as an academic innovator as well. It was the first, and remains the only, TCM College to establish a Neurology Center (founded in 1995) for the specialized treatment of paralyzed patients, under the directorship of the world-famous Chinese physician Doctor Ming Qing Zhu, L.Ac., Dipl. Ac. (NCCA), M.D. (China).

THE FIVE BRANCHES MEDICAL QIGONG CLINIC

The Five Branches Medical Qigong Clinic is currently divided into 3 treatment areas. The main area (Clinic A) is used to treat patients with less severe conditions; the second area (Clinic B) is used specifically for the treatment of cancer patients. The third treatment area is designed for video taping the patient's Medical Qigong prescription exercises and meditations.

Clinic A is the primary care facility of all patients. The patients are first assessed, and then assigned to a treatment team. Each team is comprised of at least one senior intern and several clinical students. Each team diagnoses, treats, and then prescribes Medical Qigong exercises and meditations for each patient. Some patients with potentially terminal illnesses (cancer, tumors etc.) may require specialized treatments, and are referred to the Clinic B.

The main goal of the Clinic B is to specialize in Oncology, and to work closely with the Academic Dean and Clinical Medical Director Dr. Joanna Zhao, L.Ac., Dipl. Ac. (NCCA), D.T.C.M. (China), who prescribes herbal therapy to complement the Qi Emission therapy and Medical Qigong prescriptions.

The Director of the Medical Qigong Clinic is Dr. Jerry Alan Johnson, whose duty is to oversee the "Doctors in Charge" of the 3 treatment areas, as well as regulate the patient load between Clinics A and B.

The Doctors in Charge of the Medical Qigong Clinics are: Jean Ruth Vlamynck, L.Ac., Dipl.Ac., M.T.C.M., M.Q.T., and Adam Atman, L.Ac., Dipl.Ac., M.T.C.M., M.Q.T. Their duty is to oversee the Medical Qigong doctors on staff within the three treatment areas, supervise the current interns, and make themselves available for consultations when needed.

The front entrance of the Medical Qigong College at the Hai Dian University in Beijing, China.



Dr. Lu Guo Hong, Director of the Hai Dian Medical Qigong College, treats a patient suffering from hypertension by dispersing Excess Heat from her body.

Right: The graduate students of the Hai Dian Medical Qigong College intern at the Xi Yuan Hospital in Beijing, China, for a period of 6 months to a year. They are licensed through the government's Medical Qigong Science and Research Institutes, which monitor the student programs.



Left to right: Dr. Li Fu Dong, Associate Professor and Chief Director of Medical Qigong Science, Dr. Jerry Alan Johnson the author and director of the International Institute of Medical Qigong, and Dr. Pang Dong Hui, Executive Deputy President of the Hai Dian University.



Dr. Niu Yu Hua, Assistant Director of the Hai Dian Medical Qigong College, treats a patient by regulating the Qi of her Upper and Lower Dantian.



The Xi Yuan Hospital in Beijing, China, is the equivalent of the Stanford or Harvard Medical Center in the United States; it specializes in five distinct branches of healing therapies: Medical Qigong, acupuncture, herbs, Chinese massage, and Western medicine.



Three Americans completed their internships at the Xi Yuan Clinic in 1995. They are shown here posing with Dr. Xu Hongtao, the Xi Yuan Hospital staff supervising physician. *Left to right:* Dr. Seth Lefkowitz, the author Dr. Johnson, Dr. Xu Hongtao, and Dr. Arnold Tayam.

Right: The China Beijing International Acupuncture Training Center is a facility in which doctors from around the world culminate their training in Chinese medicine with Chinese doctors who are experts in their medical specialties.



The Xi Yuan Hospital is equipped with both inpatient and outpatient Qigong clinics. Here, Dr. Xu Hongtao administers "distance" Qigong therapy to patients in one of the many Medical Qigong wards.

Left to right: Qigong Master Zheng Zhanding, Jonathan Liu, and the author discussing advanced Medical Qigong theories and modalities.

CHINA BEIJING INTERNATIO
ACUPUNCTURE TRAINING CE



Dr. Teng Yingbo (*left*), the president and secretary general of the Beijing Western District Qigong Science and Research Institute, with the author treating a patient.



Left: The International Institute of Medical Qigong is one of the few American Medical Qigong colleges that maintains the same strict standards as the Medical Qigong Universities in China. The initial training programs generally require three to four years of training.

The 1999 graduating class of the International Institute of Medical Qigong (*left to right*):

Back row: Matthew B. Weston, William H. Lewington, William H. De Groat, Paul E. Miller.

Middle row: Katy Reed, Madeleine H. Howell, Brooks M. Fiske, Diane de Terra.

Front row: Michael J. Finch, Jean R. Vlamynck, Dr. Johnson, Dennis M. Earnest.

Not pictured: Todd Mathew Gedryn, Luc Arnauld Logan, Geoffrey Greenspahn and Rose Mary Stewart.

WORLD CONFERENCE ON MEDICAL
WORLD ACADEMIC SOCIETY OF MEDICAL QIGONG

The author lecturing at the World Academic Society of Medical Qigong 1996 World Conference, on the psychophysical manifestations associated with tumor formation.

The 1997 graduating class of the International Institute of Medical Qigong (*left to right*):

Back row: Dr. Stephanie Taylor, Pamela Lee Espinoza, Anne Elderfield, and Dr. Carole Marie Kelly.

Front row: Dr. Arnold E. Tayam, Dr. Johnson (director of the institute), Shannon K. Brown, and Dr. Seth Lefkowitz.



The Five Branches Institute, College and Clinic of Traditional Chinese Medicine became the first TCM/ Acupuncture College in the United States to open a Medical Qigong Clinic on April 7th., 2000.



In the main treatment area (Clinic A), patients are categorized according to the severity of their condition. For serious conditions (e.g., multiple sclerosis) patients are encouraged to lie on the treatment tables.

The resident Doctors in Charge of the Five Branches Medical Qigong Clinic are Adam Atman L.Ac., Dipl.Ac., M.T.C.M., M.Q.T. (positioned on the left), and Jean Ruth Vlamynck L.Ac., Dipl.Ac., M.T.C.M., M.Q.T. (located in the middle). They are seen here is discussing the current patient load with Dr. Arnold Tayam D.M.Q. (China).



Pictured from left to right are the Five Branches President and CEO Ron Zaidman, M.B.A., M.T.C.M.; the Academic Dean and Clinical Medical Director Dr. Joanna Zhao L.Ac., Dipl. Ac (NCCA), D.T.C.M. (China); and the Dean of Medical Qigong Science and Director of the Medical Qigong Clinic Dr. Jerry Alan Johnson.



In Clinic A of the Five Branches Medical Qigong Clinic, patients with less serious conditions (e.g., hypertension and migraine headaches) are encouraged to relax on one of the treatment chairs.





The second treatment area (Clinic B), is used specifically for the treatment of tumor and cancer patients.

The Five Branches Medical Qigong students are also taught Energetic Psychology and how to deal with the emotional discharges coming from their patients.





Doctors of the Five Branches Medical Qigong Clinic combine their energies to treat a specific type of cancer, observed here, in Clinic B.



Within the first semester, the Medical Qigong students at the Five Branches TCM College have learned and experienced basic applications of Medical Qigong purgation, tonification and regulation exercises. They have also been taught the underlying principles for each exercise and meditation. Furthermore, they are able to discriminate when to assign these prescriptions to patients, and when not to.

In the first phase of internship, the Medical Qigong students work as part of a Qigong treatment team, assisting a senior intern.

The Medical Qigong Clinic also includes a psychotherapist, Madeleine Howell, L.M.F.T., M.Q.T., who is trained in Medical Qigong therapy. She is available to patients who may need professional consultation after undergoing Medical Qigong treatments, as these may bring painful emotions to the surface as part of the healing process.

On the first official day of the clinic, 15 Qigong interns and doctors from the International Institute of Medical Qigong performed Qi Emission through Distance therapy on more than 80 patients. Treatments ranged from a general treatment (purging excess, tonifying deficiencies and dispersing stagnations) to the treatment of several potentially terminal cancer patients.

THE FIVE BRANCHES MEDICAL QIGONG COURSE AND CLASSES

The Medical Qigong students at the Five Branches college learn and experience basic applications of Medical Qigong purgation, tonification and regulation exercises during the first semester. Classes, include lectures and labs. They are also taught to understand the underlying principles of each Medical Qigong exercise and meditation, and learn when and when not to assign these exercises in cases for clinical application. The students are also taught Energetic Psychology and how to deal with the emotional discharges coming from their patients.

In the second semester the Medical Qigong students are led through a progressive series of advanced Shengong meditations and exercises, for developing advanced intuitive diagnostic skills. The students also learn basic Medical Qigong treatment protocols, and begin the initial phase of clinical internship. During this phase they assist the senior interns.

From the third semester on, the students begin an in depth study in Medical Qigong theory and its application. The goal is to complete a three year certification program in Medical Qigong Therapy.

MEDICAL QIGONG CLINICAL THEATRE

Conducted in a small class setting, the Medical Qigong Clinic gives the students exposure and first hand experience at Medical Qigong diagnoses and treatments. This is a hands on experience where the different aspects of energetic dysfunctions and symptom manifestations are studied, treated and observed by the Medical Qigong students. Through the careful guidance of the instructor, the Medical Qigong students are allowed to assist in all phases of diagnosis and treatment.

After completing the Clinical practicum, Medical Qigong students at the Five Branches TCM College will be qualified to diagnose and treat patients, as well as document and maintain accurate clinical records.

CLINICAL INTERNSHIP

In the first phase of internship, the Medical Qigong students work as part of a Qigong treatment team, assisting a senior intern.

In the second phase of internship, the Medical Qigong students work with their own patients, under the supervision of the instructor.

By the end of their Clinical Internship, the Medical Qigong therapists will receive their Masters degree, and will be fully qualified to diagnose and treat patients without supervision.

TRADITIONAL CHINESE MEDICINE AND MEDICAL QIGONG THERAPY

Medical Qigong therapy is the oldest of the four branches of Traditional Chinese Medicine and provides the energetic foundation from which acupuncture, herbal healing, and Chinese massage originated. It is through the understanding of Qigong that the other branches of Traditional Chinese Medicine are elevated to a spiritual path of self-realization and internal transformation. Doctors of Traditional Chinese Medicine address the patients' physical, energetic, and spiritual needs simultaneously. According to the principles of Traditional Chinese Medicine, the root cause of all disease can be traced to a critical imbalance within the body's vital energies. Therefore, the best way to prevent or cure disease requires establishing a healthy energetic balance and harmony between the body's energy field and the forces of nature and the cosmos.

Traditional Chinese Medicine is divided into four branches of clinical healing: Acupuncture


Needling Therapy
Cupping
Bloodletting
Moxa
Magnetic Therapy
Tea & Soups
Tinctures & Wines
Oils, Balms & Liniments
Compresses, Powders & Pills
Nutritional Education
Jie Gu—Bone Setting
Tui Na—Muscle Manipulation
Gua Sha—Scraping Therapy
An Mo—Visceral Manipulation
Jing Point Therapy
Distance Therapy
Self-regulation Therapy
Energetic Massage Therapy
Energetic Point Therapy
Invisible-needle Therapy
Acupuncture Therapy
(1)
Herbal Therapy
(2)
Chinese Massage Therapy
(3)
Medical Qigong Therapy
(4)
4 Main Branches of Traditional Chinese Medicine
5 Main Roots
Six Stages
Five Elements
Eight Principles
Triple Burners
Four Levels
Tai Yang
Yang Ming
Shao Yang
Tai Yin
Shao Yin
Jue Yin
Wood
Fire
Earth
Metal
Water
Deficient & Excess
Internal & External
Cold & Heat
Yin & Yang
Lower Burner
Middle Burner
Upper Burner
Lg Intestine
Kidneys
Bladder
Liver
Spleen
Stomach
Heart
Lungs
Blood Level
Qi Level
Ying Qi Level
Wei Qi Level
River of Blood
Core of Light
Sea of Marrow
Wind of Nurturing Energy
Body Energy
Emotional Energy
Spiritual Energy

Figure 1.3. The Four Main Branches of Traditional Chinese Medicine

therapy, Herbal therapy, Chinese Massage therapy, and Medical Qigong therapy. All of the four main branches are built on the same foundation of energetic diagnosis known as the Five Main Roots of Traditional Chinese Medicine. The five main roots are used for internal organ diagnosis according to the Six Stages, Five Elements, Eight Principles, Triple Burners and Four Levels theories (Figure 1.3).

ACUPUNCTURE THERAPY

By inserting very thin metal needles into specific points, the acupuncturist manipulates the patient's energy (Qi) to achieve an overall physical balance. In an acute or emergency situation, a patient's symptoms are treated first, after which the focus is directed to rerouting Qi Deviations or removing the original cause of the symptoms (e.g., stagnations).

The energetic points are specific areas both on and in the body where Qi emerges from deep within the body's organs and tissues, or submerges to travel deep within the body. The Qi moves along specific pathways known as channels and collaterals. Collaterals are the smaller streams of Qi that branch off from the main ener-



Figure 1.4. The Five Main Branches of Chinese Acupuncture Therapy

getic rivers (channels). Each Primary Channel takes its name from one of the six Yin or six Yang organs to which it corresponds. Each organ has two channels, one on each side of the body.

Often in Chinese medical diagrams and procedures, you will see abbreviations referring to specific energetic points. Traditional Chinese Medicine names the points based upon the channel on which the point lies and its distance along the channel. The first points on each side of the Gall Bladder Channels (GB), for example, are GB-1. Some channels contain over 60 points, each numbered sequentially from beginning to end. These points are also given descriptive names according to their location and energetic affect upon the body when treated. The GB-1 points, for example, are located next to the eyes, on the outer canthus, level with the pupils, and are called the Pupil's Seam.

Acupuncture therapy includes five major treatment techniques (Figure 1.4): needling, cupping, bloodletting, moxa burning, and magnet healing.

1. Needling uses acupuncture needles of various sizes that are inserted into channel points. These points are tiny areas where the Qi pools along the streams of an energy channel (Figure 1.5). The needles stimulate the nerves and energy flow to tonify or reduce Excess Qi.
2. Cupping uses wooden, clay, or glass cups that adhere to the patient's skin by suction (Figure 1.6). This suction drains, or removes, pathogenic Qi from the body's pores. This technique can also be used to tonify specific areas of the body. This modality of treatment has been successfully combined with bloodletting to treat acute sprains accompanied by Blood stagnation.
3. Bloodletting is done with instruments such as blood needles or seven- and five-star hammers to remove Toxic Qi, Blood stagnation, Heat, and other pathogenic factors (Figure 1.7). The hammer has five to seven sharp projections that pierce the skin and cause slight bleeding. The acupuncturist diagnoses and then monitors the patient's condition by the



Figure 1.5. A doctor is inserting an acupuncture needle into the patient's Channel Point. Acupuncture needles of various sizes are used to stimulate nerve and energy flow for the tonification of Deficient Qi or the reduction of Excess Qi.



Figure 1.6. In Cupping, heated air is directed into wooden, clay, or glass cups, which are then placed on the patient's skin. The cooling air creates suction that drains, or removes, pathogenic Qi from the body's pores.



Figure 1.7. The doctor is lightly tapping with the Five-Star Hammer that has five sharp projections to pierce the skin and cause slight bleeding. The color of the patient's Blood provides the doctor with information about the patient's condition.

different shades of the patient's Blood. Trapped or diseased Blood is released until a healthy color is observed. This therapy is considered useful for treating disorders of the nervous system, physical trauma, and extremely serious febrile diseases.

4. Moxa Burning employs lighted herbal cones or sticks that are inserted on top of acupuncture needles (or held over specific channel points) to infuse heat and Qi into specific body areas for tonification (Figure 1.8). This technique is also used to expel Cold in order to disperse Blood stagnation.
5. Magnets use magnetic patches or strips that are attached to various channel points of the patient's body to stimulate a response in the electromagnetic field (Figure 1.9). Magnet therapy has been used since the Tang Dynasty (618–907 A.D.). The magnets are applied to specific points for a period of 3–5 days, removed for one day, then reapplied. Whether used for tonification or sedation, this therapy facilitates constant treatment of the channel point.



Figure 1.8. The doctor has inserted a needle with burning Moxa (herbal cones/sticks) on top of it. Burning moxa may also be held over specific channel points or placed directly on the skin.



Figure 1.9. A Magnetic Patch is being worn on the Wrist. Magnets may be attached to various parts of the body or may be worn in shoes or wristbands.



Figure 1.10. The Five Main Branches of Chinese Herbal Therapy

HERBAL THERAPY

Herbal formulas have been used successfully to treat a variety of illnesses for over 5000 years. Historically, herbal medicine has been the worldwide basis for pharmaceuticals used in most cultures, prior to modern times. Today, herbs provide the source for many of the pharmaceuticals used in contemporary Western medicine, especially for the treatment of viral and bacterial diseases, pain, tumors, chronic diseases, internal and external tissue regeneration, and many other medical problems.

Herbology is both a science and an art. An herbalist spends many years studying the herbs used to create herbal formulas. The herbalist must understand the effects of individual herbs, as well as their synergistic effects when combined.

Herbs are used for tonifying, purging, dispersing, warming, cooling, nourishing the Yin, nourishing the Yang, and clearing Heat, as well as moving Qi, Blood, Phlegm, and Fluids within the body. They cause the Qi in the body to either ascend or descend, affecting the upper or lower parts of the body.

Chinese medicine prescribes specific parts of plants (leaves, roots, bark, etc.) for particular medicinal purposes. Parts of trees, shrubs, herbs, vines, and flowers are selected for their specific properties (Hot, Cold, Warm, Cool) and taste (Sweet, Bitter, Pungent, Sour, and Salty). These properties either tonify or disperse Qi and Blood.

Chinese medical herbology not only includes the cultivation and gathering of seeds, fruits, flowers, leaves, barks, stems, and roots but also prescribes non-herbal components (such as minerals, animal or insect parts) that are sometimes added to enhance the herbs' healing effect.

Chinese herbs cure energetically by moving Qi in the channels. Different herbs enter different channels and affect different internal organs. Herbs are extremely powerful. The herbalist uses herbs to tonify (strengthen) and move Qi and Blood as well as eliminate Heat from the patient's Blood. When tailored to an individual's constitution or combined into a formula for specific symptoms, herbs can greatly help the body; however, taking the improper herbal formula can have deleterious effects.

Chinese herbal therapy includes five major clinical applications (Figure 1.10): nutritional education (food and diet); teas and soups (tang); tinctures and wines (jin); oils, balms, and liniments (you and gao); and compresses, powders (san), and pills (wan).

1. Nutritional education is stressed to assist patients in choosing foods for the body's nourishment and optimum health, as well as for the treatment of disease. Foods have many similar properties to herbs. An old Chinese saying asks, "Are herbs food or food herbs?", thus stressing the importance of a good diet
2. Teas and Soups are water-based herbal formulas traditionally prepared from raw or processed herbal ingredients. These are traditionally ingested for the treatment of internal and external disorders of both acute and chronic natures.
3. Tinctures and Wines are both alcohol-based herbal formulas. Tinctures are a concentrated alcohol-based formulas prepared from raw herbs that are used similarly to teas and soups. Wines are traditionally applied externally to alleviate pain, or ingested as a tonic, depending on the specific formula and the disease being treated.
4. Oils, Balms, and Liniments are oil-based herbal formulas usually applied externally for the treatment of muscle, tendon, and ligament trauma, to alleviate pain, disperse Excess Qi, or to draw Qi into specific areas for tonification.
5. Compresses, Powders, and Pills consist of herbs that have been pulverized into a paste, powder, or poultice and are then applied externally for the treatment of acute or chronic injuries. They can also be ingested for internal organ tonification and the rebalancing of the body's energy system. Pills are herbs specifically prepared from traditional formulas, rolled into little balls, and orally ingested for the treatment of Internal disorders.

CHINESE MASSAGE THERAPY

Chinese Massage Therapy is a generic term used for all tissue manipulation techniques currently used in China. This particular branch of Traditional Chinese Medicine consists of five popular systems that include manipulation of not only external skin, muscles, tendons, joints, nerves, and inner fascia but also the internal organs and organ systems.

This ancient therapy is used as a preventative treatment as well as a healing modality. By applying specific methods of tissue manipulations, obstructions in the channel's pathways can be removed, promoting and increasing both Qi and Blood circulation.

This therapy focuses on improving the structural alignment of the body and on healing soft-tissue injuries. It also corrects any deviant functions of the internal organs, nerves, and joints. Chinese bodywork and tissue therapy are the foundational source for modern Swedish massage, myofascial trigger point therapy, reflexology, and therapeutic neuromuscular therapy.

Chinese massage therapy is divided into five different schools of instruction: Jie Gu, Tui Na, Gua Sha, An Mo, and Jing Point therapy (Figure 1.11). Jie Gu, Tui Na, and Gua Sha employ external tissue manipulations. These three external manipulations are used to treat the bones, muscles, ligaments, and tendons, and also to treat fevers. An Mo and Jing Point therapy utilize soft-tissue manipulation. These treatment modalities are similar to those used in chiropractic, osteopathy, Western physical therapy, and massage therapy.

1. Jie Gu Therapy is used for bone setting and



Figure 1.11. The Five Main Branches of Chinese Massage

to adjust the patient's body alignment (Figure 1.12). The literal translation for Jie Gu is "knotted bone," which describes the art of manipulating the bones and ligaments to unravel the trapped junctions of Blood and Qi channels in the patient's joints.

2. Tui Na Therapy focuses on external tissue manipulation and adjustment of the muscles and tendons to adjust abnormal Qi circulation within the body's muscular system (Figure 1.13). The translation for Tui Na is to "push and grasp." It was developed primarily for correcting the misalignment of the body's bones and muscles due to traumatic physical injuries. Reflexology is historically rooted in the use of Tui Na therapy in Chinese pediatric care.
3. Gua Sha Therapy is used to regulate febrile conditions, such as flu, cholera and malaria, and to treat musculoskeletal conditions. The translation for Gua is "to scrape or scratch" and Sha is defined as "cholera," or sand-like maculae (referring to the red discoloration that is raised on the skin by the application of scraping). This therapy focuses on external surface tissue scraping, usually around the neck and thorax areas (Figure 1.14). It is commonly used for promoting Qi and Blood circulation, removing toxins, clearing Heat, cooling the Blood, removing stagnation, and dissolving masses. A jade scraper (coin, bowl, or spoon) is used for purifying the Qi and transforming the Shen (Spirit). A water buffalo horn is commonly used for pulling Heat and toxins from the patient's body (occasionally ceramic is used, but never glass or plastic).

The two internal manipulations are used to treat the organs and nerves.

4. An Mo Therapy is used for internal organ



Figure 1.12. Jie Gu Therapy is used to set the bones and ligaments in order to unravel the trapped junctions of Blood and Qi channels at the patient's joints.



Figure 1.14. Gua Sha Therapy is commonly used for clearing Heat, cooling the Blood, removing stagnation, and dissolving masses.

regulation. An Mo focuses primarily on Qi extension and soft-tissue and internal organ manipulation (Figure 1.15). Although the literal translation means to "press and rub," this therapy focuses primarily on internal visceral regulation, concentrating directly on the treatment of specific Internal diseases.

5. Jing Point Therapy is employed for channel and internal organ regulation. Jing point therapy uses pressing, pinching, clapping, and tapping techniques on specific energetic points and energetic channels. These techniques are employed to promote Qi and Blood circulation, balance the body's Yin and Yang energy, tonify weak organs, dredge the channels, and expel pathogenic factors (Figure 1.16).



Figure 1.13. Tui Na Therapy is used to adjust the muscles and focuses on external tissue manipulation and adjustment of the muscles and tendons in order to correct abnormal Qi circulation within the body's muscular system.



Figure 1.15. An Mo Therapy allows organ manipulation for internal visceral regulation and concentrates directly on treating specific Internal diseases.



Figure 1.16. Jing Point Therapy is used to promote Qi and Blood circulation, balance the body's Yin and Yang energy, tonify weak organs, dredge the channels, and expel pathogenic factors.



Figure 1.17. The Five Main Branches of Chinese Medical Qigong Therapy

MEDICAL QIGONG THERAPY

The objective for healing disease in Medical Qigong training is threefold:

- First, eliminate Internal pathogenic factors (the accumulation of Excessive emotions such as anger, grief, worry, fear, etc.) as well as External pathogenic factors (the invasion of Cold, Hot, Damp, etc., from the environment).
- Second, increase or decrease the patient's Qi as needed to counteract the Deficient or Excess condition within the internal organs and channels.
- Third, regulate and balance the patient's Yin and Yang energy to bring it back into harmony.

This unique therapy consists of regulating the body's three external Wei Qi fields (physical, mental/emotional and spiritual), and the four Internal fields of life-force energy (Ying Qi, Sea of Blood, Sea of Marrow, and the Taiji Pole). Some of the most common diseases treated in Medical Qigong clinics are: diabetes, arthritis, high blood pressure, breast and ovarian cysts and tumors, migraine headaches, fibromyalgia, insomnia, acute abdominal pain, irritable bowel syndrome, deep tissue obstruction, muscle atrophy, brain tumors, stroke, coma retrieval, and certain types of cancer. The medical treatment focuses on relieving pain, detoxifying the body of toxic emotions (e.g., excessive anger, fear, worry, etc.), correcting internal organ dysfunctions, and balancing Excess or Deficient Qi and Blood conditions.

Medical Qigong therapy uses five major clinical modalities (Figure 1.17): Distance therapy, Self-

Regulation therapy, Qigong Massage therapy, Energetic Point therapy, and Invisible Needle therapy.

1. Distance Therapy (also called Qi Emission) requires the Qigong doctor to manipulate a patient's Qi by focusing on the energetic properties of the patients' channels, collaterals, and points, as well as internal organs, from a distance of several inches, several feet, or even several miles away (Figure 1.18).
2. Self-Regulation Therapy (also called Qigong Prescriptions and Patient Homework) are Qigong exercises (postures, movements, sound vibrations, visualizations, etc.) given to patients by a doctor (Figure 1.19). Patients can use these Qigong techniques to regulate their own health, using various lying, sitting, moving, and standing postures. The patients may also use their own spiritual belief system as a healing tool.
3. Qigong Massage Therapy, a soft-tissue regulation technique, differs from Tui Na or An Mo (Chinese External Massage Therapy), in that the doctor's hand skims the patient's body as lightly as a feather, never exceeding the pressure one would place on an eyeball (Figure 1.20). The light skimming action is used to dredge the patients' external channel Qi, causing energy to be released from the internal channels themselves, which serve as pathways for Qi transference.
4. Energetic Point Therapy is used by the doctor to extend Qi into specific internal and external areas of the patient's body to lead and direct the Qi. This type of therapy requires the doctor and the patient to focus their attention onto a specific energetic point (Figure 1.21). This therapy demonstrates the power of the mind as an active tool in healing, and is used for purgation, tonification, and regulation.
5. Invisible Needle Therapy involves the visualization of imaginary needles of light being inserted into specific points on the patient's body. The needles of light are used to stimulate and direct the patient's Qi (Figure 1.22).



Figure 1.18. In Distance Therapy, the Qigong doctor manipulates a patient's Qi by focusing on the energetic properties of the patient's external channels, collaterals, and points from a distance of several inches, several feet, or even several miles.



Figure 1.19. In Self-Regulation Therapy, the patients are required to self-regulate by performing Qi Qigong "prescriptions" or "homework" (postures, movements, chants, visualizations, etc.). Here the patient regulates his own *Liver Qi*.



Figure 1.20. In Qigong Massage Therapy, the doctor softly dredges the patient's external channels in order to release energy from the internal channels themselves, which serve as pathways for Qi transference.



Figure 1.21. In Energetic Point Therapy, the doctor extends energy into the patient's body as both the doctor and the patient focus their attention on a specific channel point, in this case the Kd-1 point.



Figure 1.22. In Invisible Needle Therapy, the doctor visualizes inserting energetic acupuncture needles into the patient's channel points in order to stimulate the patient's Qi.

CHAPTER 2
ENERGETIC FORMATION OF THE HUMAN BODY

In 1993 when I began my internship at the Xi Yuan Hospital in Beijing, China, I became aware that most Qigong doctors had a limited understanding of basic anatomy and physiology as we teach it in the West. When I asked why more attention was not paid to the subject, I was told, "The perspective and priority we place on gross physical anatomy and physiology is quite different from yours -- Westerners only study the dead -- we study life, the living pools, rivers, and currents of life-force energy that can only be found in the living body."

Eastern medicine believes that when the body dies, the substance, or energy, that gave the body life returns to its original source (Heaven and Earth) and all that remains of the individual is a mass of lifeless tissue. They believe that the tangible and the energetic exist in a twofold, cohesive relationship. A Qigong doctor must understand this concept of energy in order to comprehend and prescribe appropriate Medical Qigong therapy for the patient.

The concept of the energetic formation of the human body is new to Western thought with its primary focus on the physically tangible. The philosophical foundation of Traditional Chinese Medicine, on the other hand, includes studying the whole human being in all of his or her aspects, physical, mental, emotional, energetic, and spiritual. The conception results not only in the tangible physical form of a new human being but also in various contributing energies and energetic fields. Medical Qigong studies these energies, as well as the interplay between the Heavenly and Earthly influences.

ENERGETIC EMBRYOLOGICAL DEVELOPMENT

The study of the embryological development of the body's inner fascia and connective tissues explains many of the traditional Chinese medical ideas about energy, health, and disease. The cells, tissues, and organs of the human body interrelate as a result of the "energetic patterning" that occurs at conception.

Heaven (which the ancient Chinese considered a state of subtle and non-material energies and beings) and Earth both have energetic fields that influence life. If we consider Heaven Qi (the universal energy related to the sun, moon, and stars) to be electro-positive and Earth Qi (the environmental energy related to the earth, water and wind) to be electro-negative, we can begin to understand the duality of the energetic fields and their pull on the human body.

Think of the body as being suspended between two enormous fields of energy (Figure 2.1): the sun extends its energetic field down, and the Earth's small "sun," i.e. its core, extends its energetic field upwards through the Earth's crust. Man is, therefore, suspended between the electrically positive energy field of Heaven and the electri-



Figure 2.1. Man's energetic field is suspended between the two energy fields of Heaven and Earth.

cally negative energy field of Earth and is affected by both celestial and environmental phenomena.

ENERGY, MATTER, AND SPIRITUAL INTERACTIONS

The *Yellow Emperor's Classic of Internal Medicine* states that the woman's physiology is dominated by Blood, which serves as the foundation of her menstrual cycle, fertility, conception, pregnancy, and childbirth. A man's physiology is dominated by Qi, which serves as the basis of his physical interactions.

At conception, a myriad of energetic interactions begin. The mother, father, Heaven, and Earth all contribute energetically to conception. These four energies condense upon impact and form the nucleus of the energetic cellular patterning of the new life (Figure 2.2). Every part of the resulting human body is affected by this energetic patterning.

An old Chinese saying in Medical Qigong states that, "When people are born, Heaven gives them Jing (Essence) and Shen (Spirit) -- which align to form the mind -- and Earth gives them bones and shape, which unite to form the body. Joined together, these sources of energy cause human beings to develop. When people die, their Essence and Spirit return to Heaven, and their bones and shape go back to Earth."



Figure 2.2. The blending of Heaven (universal energy) and Earth (environmental energy) as well as father and mother energies creates a fusion of Yin and Yang energies within the body's tissues and cells during creation. These energies are responsible, on a psychophysical level, for transferring talents and traits from generation to generation.

Pairs of channels from the mother's internal organs carry Qi that creates and nourishes the baby at each stage of development. As the baby develops, sustained through the umbilical cord, the child's navel, Kidneys, and lower abdominal area become the collection points for Prenatal Qi (energy stored within the baby's body before it is born).

Every life begins with inherent strengths and weaknesses. It is believed that when conception occurs, if the mother achieves orgasm, the child's inherent energy will become very strong. However, if the mother does not achieve orgasm during conception, the results will be a normal or weak energetic constitution. Prenatal care is mandatory for the healthy formation of the embryo. Before cell division, the DNA mass must be duplicated exactly in order to transfer normal genetic characteristics to the next generation. Although heredity plays a large part in the transference of both parents' genetic history, a weakness in the mother's channels can result in congenital problems, or toxins, that the fetus can acquire during one of the corresponding stages of development.

UNDERSTANDING FETAL TOXINS

The External invasions of pathogenic toxins (known as fetal toxins) can penetrate the zygote with latent Heat that can cause diseases during early childhood development. It is, therefore, important for both parents, especially the mother, to take responsibility for being strong and healthy at the time of conception and for the duration of the pregnancy. Toxins can be transferred into the embryo in utero in one of two ways:

- First, from either the mother or father at the moment of conception. Toxins transferred from the parents can create an inherited toxicity due to a retention of Hot Evil stored from within either of the parents' Essence and Blood; or
- Second, from Internal Heat generated by the

mother during pregnancy due to improper diet or life-style.

During pregnancy, a fetus is aware of light and sound and of the mother's reaction to the surrounding influences of her environmental energy fields. The fetus is strongly influenced by its mother's physical activities, as well as her mental, emotional, and spiritual states.

Regulating the mother's behavior to improve her child's physical, emotional, and mental health is called "fetal education" in Traditional Chinese Medicine, and is important in the development of the child's Prenatal Essence, Energy, and Spirit. This viewpoint is based on the fact that the mother's Heart and uterus are connected via the mother's internal channels, allowing Qi and Blood to flow into the uterus. Anything that influences the mother's mind, emotions, and spirit affect her Heart, which in turn, affect the fetus via the internal channels.

DEVELOPMENTAL SEQUENCE

The following description of the body's developmental sequence is but one of many theories used in order to explain Chinese energetic embryology. The ancient Chinese did not have a conception of the body's cells and cellular division; however, modern theories have postulated that the channels were formed at the earliest stages of cell division, creating an energy matrix for the developing fetus. This particular theory is being taught at the Hai Dian Medical Qigong College in Beijing, China.

Three important energies (Figure 2.3) combine in the developing fetus: Jing (Essence), Qi (Energy), and Shen (Spirit). Jing is the body's foundational substance, responsible for nourishing the tissues. Qi emerges out of Jing circulating through the tissues and promotes the body's metabolism. Shen governs the body. (see Chapter 11, "The Three Treasures of Man," for more on Jing, Qi, and Shen.)

Both parents contribute energetically to the baby's conception (Figure 2.4). The father's sperm and the mother's egg consist of Jing (Essence), Qi (Energy), and Shen (Spirit). This combination of Jing, Qi, and Shen is referred to collectively as fa-

Prenatal Energies—The Three Treasures		
Substance	**Physical Function**	**Energetic Prenatal Function**
Shen (Spirit)	governs the body	the Original Spirit
Qi (Energy)	promotes metabolism	body's Energy extending into Infinite Space (also called Wuji, or the Void)
Jing (Essence)	nourishes the tissues	body's innate true Essence, the foundational substance

Figure 2.3 Qi is the medium between matter (Jing) and Spirit (Shen) and is responsible for the embryo's transformational processes.



Figure 2.4. The human body is composed primarily of water. The Essence of man (sperm) and woman (egg) unite in the uterine sea to form the fetus. The ova is polarized at the entry point of the sperm, creating the original polar axis (the *Taiji Pole*) that determines the complex pattern of cellular division that occurs along the polar axis throughout development.

ther Qi and mother Qi. The combination of father Qi and mother Qi is known as Yuan Qi or Original Qi.

The quality and quantity of Original Qi that the baby receives at birth depends on three main factors:

- First, the purity and potency of both parents' genetic plasma (sperm and egg);
- Second, the condition of both parents' health and vitality and the state of their physical, mental, emotional and spiritual relationship at the time of conception; and
- Third, the spiritual factors surrounding the conception (i.e., karma that is brought into this life by the incoming spirit/soul).

As the sperm (containing the father's Qi) fertilizes the egg (containing the mother's Qi), Heaven (universal) Qi and Earth (environmental) Qi blend together within the zygote. The swirling and blending of these four energies form energetic pools (which will later evolve into organs), rivers (which later evolve into channels), and streams (which later evolve into collaterals).

When the sperm enters the ovum, it produces a polar axis that creates an energetic vortex. This vortex not only forms the central Taiji Pole, but also draws Qi from Heaven and Earth and the Eternal Soul into the fetus's body. This polarization also determines a ventral and dorsal surface, which become the embryo's Conception and Governing Vessels, respectively, at the first cell division (Figure 2.5). The Governing Vessel controls the cell division that eventually forms the back of the body, while the Conception Vessel controls the cell division of the body's front. This first cell division also establishes a right and left side. The Heel Vessels control the balance of Yin and Yang energy development in the two sides of the body.

The Belt Vessel and Thrusting Vessels form at the time of the second cell division. The four vessels formed at this point (Governing Vessel, Conception Vessel, Thrusting Vessels, and Belt Vessel) are interlinked for the production, circulation, and regulation of the body's Jing-Essence. The body's entire energy system becomes established and maintained within these four vessels when cell division occurs (Figure 2.6).


Left Yin and Yang Heel Vessels
Right Yin and Yang Heel Vessels
Conception Vessel
Governing Vessel

Figure 2.5. The electrical polarity and field of energy in the polar axis is related to the Original or Yuan Qi from which the Conception and Governing Vessels form the seas of Yin and Yang energy during the first cellular division. The Yin and Yang Heel Vessels are also established, forming the left and right sides. The exterior of the egg is determined by the Yang Linking Vessels. The interior of the egg by the Yin Linking Vessels.



Figure 2.6. The second cellular division is caused by the development of the Belt Vessel and the Thrusting Vessel. The Eight Extraordinary Vessels have now formed.

While the embryo is forming, both the Yang and Yin Linking Vessels are respectively responsible for the exterior and interior development of the embryo (see Chapter 3 for more on Yang and Yin energy). Each of the Eight Extraordinary Vessels has a specific role in the development of the embryo.

1. The Governing Vessel (Yang) controls development of the body's back.
2. The Conception Vessel (Yin) controls development of the body's front.
3. The Thrusting Vessels carry energy through the center of the body and controls the body's center core.

4. The Yang Heel Vessels control the development of the body's right and left Yang energy.
5. The Yin Heel Vessels control the development of the body's right and left Yin energy.
6. The Yang Linking Vessels control the development of the exterior of the body (and correlates to Heaven energy).
7. The Yin Linking Vessels control the development of the interior of the body (and correlates to Earth energy).
8. The Belt Vessel binds all the channels together.

These eight vessels—Governing, Conception, Thrusting, Yang Heel, Yin Heel, Yang Linking, Yin Linking, and Belt—are also known as the Eight Extraordinary Vessels or Eight Prenatal Vessels.

The Eight Extraordinary Vessels form a vortex of energy at the center of the embryo's body—from the area between what will become the Kidneys. The Taiji Pole and Thrusting Vessels are at the center of this vortex and will form the Sea of Five Yin and Six Yang Organs, the Sea of Twelve Primary Channels, and the Sea of Blood (see Chapter 13). From the Taiji Pole and Thrusting Vessels, the body's Qi and Blood are distributed at the energetic level through small channels, or rivers of energy. This energetic vortex creates the energy for the growth of the embryo's physical form.

After the initial cell division is complete, the embryo's ten Yang channels and ten Yin channels begin the development and formation of the embryo's tissues and organs. These twenty channels are divided into two separate groups of energetic rivers known as the Eight Extraordinary Vessels and Twelve Primary Channels. As the embryo develops into a fetus and continues to grow, the twenty channels also continue to develop.

During the formation of the embryo, nine Yang channels begin to flow out of the Governing Vessel (Sea of Yang Qi) and form the nine Yang rivers known as: the Bladder Channels, Gall Bladder Channels, Stomach Channels, Small Intestine Channels, Triple Burner Channels, Large Intestine Channels, Yang Heel Vessels, Yang Linking Vessels, and Belt Vessel.

Consecutively, the nine Yin channels begin to flow out of the Conception Vessel (Sea of Yin Qi) and form the nine Yin rivers known as: the Kidney Channels, Liver Channels, Spleen Channels, Heart Channels, Pericardium Channels, Lung Channels, Yin Heel Vessels, Yin Linking Vessels, and Thrusting Vessels (see Chapter 8).

THE TEN LUNAR MONTHS OF CREATION

The following description of the sequence of embryological development was established by the late Chinese Medical Qigong expert Dr. Chao Yuan Fang during the Sui Dynasty, around 610 A.D. The months that Dr. Chao refers to are the ten lunar

Lunar Month	**Mother's Channels**	**Channel's Activity**	**Energetic Activity**
Month 1	Liver Channels	stop menses, begin embryonic growth	energies combine at conception, channels develop
Month 2	Gall Bladder Channels	saturate embryo with Jing	embryonic Qi transforms into amniotic fluid
Month 3	Pericardium Channels	mother's Qi and Body Fluids purify and cleanse the fetal Shen	Hun and Po establish in the fetus's internal organs
Month 4	Triple Burner Channels	the Yin organs develop	Water Jing accepted into fetus's body
Month 5	Spleen Channels	the Five Agents enter the Five Orbs (Yin organs)	Fire Jing accepted into fetus's body
Month 6	Stomach Channels	Six Pitches established within the Six Storage Areas	Metal Jing accepted into fetus's body
Month 7	Lung Channels	Seven Essential Stars open orifices to the light from Heaven and Earth	Wood Jing accepted into fetus's body
Month 8	Large Intestine Channels	Heart is harmonized and breath is quieted	Earth Jing accepted into fetus's body
Month 9	Kidney Channels	Kidney Channel controls the energetic intake from the umbilicus	energetic boundaries completed
Month 10	Bladder Channels	spatial cavities surrounding major organs are completed	Heaven & Earth Qi settle into baby's Lower Dantian and birth begins

Figure 2.7. Prenatal Energy Development

months. These months compose the 40 weeks of a normal pregnancy (Figure 2.7).

MONTH ONE

The first lunar month of pregnancy is traditionally called the Beginning of Form. This stage covers conception and early cell division.

At conception, the mother's Liver Channels stop her menses and begin to nourish the growth of her embryo (Figure 2.8). During pregnancy, the mother's Blood is transformed into Jing-Essence, that nourishes the mother's body as well as the embryo's. The mother's Liver Channels cause Essence and Blood to coagulate in her womb. This Blood coagulation continues after the initial cellular division.

At this stage the mother's Shen (Spirit) becomes part of a threefold activity:

- First, the mother's Shen projects through the umbilical cord like a light reflecting off a prism, sustaining and energizing the production of Jing (see Chapter 13), Qi, and Blood for the embryo (Figure 2.9).
- Second, the mother's Shen influences the embryo's Qi and Blood, and the embryo's Shen (Spirit) is stimulated, bringing it into active being (see Chapter 12).
- Third, the embryo's Original Jing combines with the embryo's Original Qi to create the embryo's Original Shen (Prenatal Spirit), which appears as multicolored light and contains the inherited knowledge of the fetus's ancestors, including talents, skills, and natu-



Figure 2.9. Sustained through the umbilical cord, the embryo absorbs the mother's Blood, Essence, Energy, and Spirit.



The energy of the Liver Channels flows up the inside of both legs into the uterus, stopping menses as the growth cycle begins.

Figure 2.8. The mother's and father's Essence (Jing), Energy (Qi), and Spirit (Shen) blend with the Heaven and Earth energies during the fusion of the sperm and egg. During the first lunar month, the mother's Liver Channels stop her menses and begin the embryonic growth cycle. After the initial cell division, the ten Yin and ten Yang Channels develop within the embryo.

ral abilities. This knowledge is stored deep within the fetus's cells, tissues, and consciousness.

MONTH TWO

The second lunar month of pregnancy is traditionally called the Beginning to Gel stage. During this period, the responsibility of the mother's Gall Bladder Channels is to create the environment for the development of the mesenteric membrane sac (Figure 2.10). The Gall Bladder Channels will also saturate the embryo, uterus, and placenta with Jing, causing the embryonic Qi to become denser, until it transforms into a thick liquid (amniotic fluid). The embryonic fluid will regulate the embryo's Body Fluids. At this stage, the embryo begins to take shape inside the uterine lining (Figure 2.11). The Lungs, Liver, Kidneys and major blood vessels are forming.

With the formation of the major blood vessels, the Yin and Yang energies begin to occupy the embryo's channels. As the Yin and Yang energies actively balance themselves:

- Energy that will later coalesce into Lung Qi moves to the upper part of the body;
- Original Qi (Yuan) of the Kidneys begins to collect deep in the center of the body;
- Earth Qi (the energy absorbed by the embryo from the mother's exposure to the outside environment) begins to collect in the lower front and upper back areas of the embryo's body.

All of these energies seek their own location



Figure 2.11. During the second month, the embryo begins to take shape as the energetic boundaries begin to form.



The energy of the Gall Bladder Channels flows down the outside of the mother's body, saturating the embryo with Jing.

Figure 2.10. The mother's Gall Bladder Channels saturate the embryo with Jing during the second lunar month, causing the embryonic Qi to transform into amniotic fluid. The embryo begins to take shape as the energetic boundaries, pools, spatial cavities, and energetic channels and collaterals create internal and external form.

within the embryo's developing body, creating their own pools of Qi with their own discrete energetic boundaries. These boundaries will later form the spatial cavities that surround the major organs. The areas where the energetic pools settle and begin to create a balance within themselves, will be called the organ's place of origin. This flux and movement creates tiny energy currents, eddies, and whirlpools that flow within the body. As the energy shifts, seeking balance, the larger pools of energy begin to form the major organs. This process continues, creating the brain, bones, and skin.

Once the energetic pools and rivers have formed, all of the currents and eddies evolve to form the energetic channels and collaterals, through which energy will flow continuously. These energetic currents will move in accordance with the mother's energetic respiratory patterns and will later (after birth) follow the rhythmic patterns of the child's respiration. As the energy currents continue to spiral within the channels, energetic points are established, following the body's energetic blueprint. Some of these areas spiral outward to form energetic exit points, while others spiral inward to form entry points.

MONTH THREE

The third lunar month of pregnancy is traditionally called the Beginning of the Pregnant uterus. During this period, the embryo becomes a fetus and begins micro-movement. Its heartbeat can now be detected.

The mother's Pericardium Channels control the presence and amount of Jing and Shen in the fetus's vessels, channels, and collaterals (Figure 2.12). The Jing and Shen that flow from the mother are ultimately rooted (firmly established) in the energy of her Blood. The combination of the mother's Qi and Body Fluids purifies and cleanses the Shen of the fetus, which was formed at conception. This purifying action transforms into Heat, causing the Yang energy to arouse the Hun-Three Ethereal Souls (the energy of the fetus's spirit), into life. The Five Agents, energies that stem from the Three Ethereal Souls, are currently in a state of awakening and will later reside in the organs.



The energy of the Pericardium Channels flow from the Heart down the center of the mother's body into the uterus cleansing the fetus's Shen.

Figure 2.12. The mother's Pericardium Channels control the third lunar month of creation. The mother's Qi and body fluids purify and cleanse the fetus's Shen (Spirit). The Hun from Heaven and the Po from Earth are established within the fetus's internal organs.

The Five Agents are energies that are linked to a person's moral qualities and can be categorized as the five virtues of the Five Yin Organs. The Five Agents are also categorized into Five Elements. The psycho-emotional components of the Prenatal Five Agents and Postnatal Five Emotions are both stored within the body's Five Yin Organs, and are expressed as the child grows into adulthood (Figure 2.13). When one of the internal organs is stimulated, a Yin or Yang psycho-emotional reaction is created. Psycho-emotional energetic interactions are feeling manifestations expressed through either the positive moral qualities of the congenital Five Agents (Yang - kindness, order, trust, integrity, and wisdom) or the negative developed emotional experiences of the Acquired Five Emotions (Yin - anger, joy, worry, grief, and fear).

The Five Agents are connected to the Wu Jing Shen-Five Essence Spirits (Hun, Shen, Yi, Po, and Zhi), and stored within the energetic elemental nature of the body's Essence (Jing) of Wood, Fire, Earth, Metal, and Water. The Five Elemental Energies however, encompass not only the body, but all of the myriad phenomena of the body and nature, combining and recombining in infinite ways to produce manifested existence.

1. The Wood Agent (the Virtue of Kindness) represents benevolence and compassion. This agent is connected to the Hun-Three Ethereal Souls, and stored in the Liver. Wood affects the energetic channels' flow, tendons, ligaments, small muscles, peripheral nerves, iris of the eyes, vision, tears, bile, nails, and external genitalia. After birth, the Liver will also store the emotions of anger, irritability, blame, rage, resentment, and jealousy. When excess anger is eliminated, benevolence, compassion, and love for others is allowed to flourish.
2. The Fire Agent (the Virtue of Order) represents peace and boundary setting to foster social harmony. This agent is connected to the Shen-Spirit, and stored in the Heart, affecting the energetic channels' flow, blood vessels, complexion, perspiration, and the tongue. After birth, the Heart will also store the emotions of shock, nervousness and excitement. Eliminating excess nervousness allows love, forgiveness, and joy to be experienced. The environment is then conducive for peace, contentment, and orderliness, which allow self-esteem to grow.
3. The Earth Agent (the Virtue of Trust) represents faith, honesty, openness, acceptance, and truthfulness. This agent is connected to the Yi-Intention (thoughts and ideas) and stored in the Spleen, affecting the energetic channels' flow, large muscles, lymph and saliva secretions, mouth, lips, and taste. After birth, the Spleen will also store the emotions of worry, remorse, regret, obsessiveness, and self-doubt. Eliminating excess worry allows trust and peace of mind to exist.
4. The Metal Agent (the Virtue of Integrity) represents righteousness and dignity. This agent is connected to the Po-Seven Corporeal Souls (the material aspect of the spirit) and stored in the Lungs, affecting the energetic channels' flow, skin and mucous membranes, body hair, nose, and the sense of smell. After birth, the Lungs will also store the emotions of grief, sorrow, anxiety, sadness, shame, disappointment, and guilt. Once excess sorrow is relieved, a deeper sense of righteousness, integrity, dignity, and social responsibility exists.

The Five Elements	Congenital Agents	Acquired Emotions
Wood	Kindness	Anger
Fire	Order	Joy
Earth	Trust	Worry
Metal	Integrity	Grief
Water	Wisdom	Fear

Figure 2.13. The Five Agents

5. The Water Agent (the Virtue of Wisdom) represents rationality, clear perception, and self-understanding. This agent is connected to the Zhi-Will (mental drive and determination) and stored in the Kidneys, affecting the energetic channels' flow, brain, inner ear, hearing, spinal cord, cerebrospinal fluid, bones, bone marrow, ovaries, testes, head and pubic hair, anus and urethra, and sexual fluids. After birth, the Kidneys will also store the emotions of fear, loneliness, and insecurity. Once excess fear is eliminated, the mind becomes rational and, therefore, wise.

The energy of the Three Ethereal Souls (Hun) is composed of three separate parts and flows with the Blood as it moves. The energy of the Corporeal Souls (Po) is composed of seven separate parts and follows the Jing as it moves. The Hun and the Po are characterized by their movements. The Po are also referred to as the supernatural Ling (A Moving Spirit). The Hun are also referred to as the supernatural Shen (Mind / Spirit). The Shen is the "active impulse" and Ling is the "active, enabling mover." As the Jing and Blood combine, the fetus's Shen continues to be created.

At the end of the third month, the internal organs, limbs, and external sex organs of the fetus are fully formed, and the nails have developed.

MONTH FOUR

During the fourth lunar month, the mother's Triple Burner Channels, which are connected with the Yang organs, stabilize the fetus's blood vessels (Figure 2.14). The Water Jing is beginning to be accepted by the fetus's body allowing the Yin organs to develop normally.

Beginning in the fourth month and continuing throughout the ninth month, each of the Five Element's energetic nature and the specific characteristics of each element's Essence will be progressively activated and developed within the fetus's body. The first to enter is the Water Jing.

The Water Jing energy supervises the genetic developmental phase of the fetal growth. This energy encompass the fetus's unconscious reservoir of innate and intuitive intelligence, will, and life-force energy, relating to divine love, power,



The energy of the Triple Burners Channels flows up both arms into the Heart and down the center of the body into the uterus, directing the development and formation of the fetus's connective tissue and fascial surfaces.

Figure 2.14. The mother's Triple Burners Channels are responsible for the changes in the fourth lunar month of creation. The Water Jing (Essence) is beginning to be accepted by the fetus.

and spirit. Any faltering of this energy (due to the influence of fetal toxins) is associated with both pervasive and subtle neurological disorders, and a predisposition to severe psychological disorders (e.g., schizophrenia).

As the fetus develops, the mother's Triple Burners will direct the development of the connective tissues and fascial surfaces. This process is referred to as "the development of Blood and Qi penetrating to the ears and eyes and circulating throughout the fetus's channels and connecting vessels."

Through the later stages of fetal development the embryo's seemingly homogenous tissues transform into the fetus's differentiated tissues of muscles, bones, and organs (an important part of which is connective tissues). A very large part of the body consists of connective tissues and membranes functioning in such a way as to hold together and maintain the body's external and internal structures.

From a gross anatomical level, the body's structures connect not only through the fascial planes but microscopically through the connective tissues. This internal network facilitates the body's intercellular communication. These structures, both energetic and physical, connect the fetus's body, forming a vast reservoir capable of regulating and transferring the body's Jing-Essence, Qi-Energy, and Shen-Spirit.

MONTH FIVE

During the fifth lunar month, the Spleen Channels become responsible for completing the development of the four limbs (Figure 2.15). The fetus begins its own respiratory movement along with the mother's respiration. The Fire Jing is accepted into the fetus, creating Internal Qi, that stabilizes the fetus's Five Yin Organs' Qi.

The Fire Jing energy generates and controls, protects and integrates, divides and harmonizes the fetus's internal energies to promote emotional/spiritual well-being. Any faltering of the Fire Jing energy is associated with problems of right (Yin) and left (Yang) brain communication (e.g., the correct balance of male/rational and female/intuitive energies).


The energy of the Spleen Channels flows up the inside of both legs into the uterus, developing the fetus's extremities.

Figure 2.15. The mother's Spleen Channels are responsible for the fifth lunar month of creation. The development of the fetus's four limbs is completed. The Five Agents are distributed within the fetus's Five Orbs (Five Yin Organs). The Fire Jing is beginning to be accepted by the fetus.

At this stage of development, the Five Agents are distributed to the Five Orbs. These Orbs are energetic spheres of influence or energetic spatial cavities (i.e., internal organ tissue chambers). These Orbs pertain to the Essence, Blood, Qi pools and channels of the Five Yin Organs. The Five Orbs also pertain to and encompass all of the areas in the body that the Five Yin Organs influence. The Five Agents are distributed as follows: Kindness to the Liver, Order to the Heart, Trust to the Spleen, Integrity to the Lungs, and Wisdom to the Kidneys. This distribution causes the Hun to stabilize within the fetus's organs, which contributes to keeping the fetus's Shen at peace.

At the end of the fifth month the fetus's body systems develop rapidly. Its head is less disproportionate to the rest of the body, and its spontaneous muscular movements are commonly felt by the mother.

MONTH SIX

In the sixth lunar month of creation, the mother's Stomach Channels create the fetus's muscles. The Metal Jing is established in the fetus's body, stabilizing the sinews and connective tissues (Figure 2.16).

The Metal Jing energy is also responsible for fetal formation and the ability to form and maintain emotional bonding with others. Any faltering of the Metal Jing energy is associated with problems of emotional attachment (e.g., autism).

During the sixth month the Yang organs are in the process of developing. The Essence of the Yang organs receives, moves, transforms, digests, and excretes substances. The Six Storage Areas of the body's Yang organs constantly fill and empty, and include the Bladder, Gall Bladder, Stomach, Large Intestine, Small Intestine, and Triple Burners.

1. The Bladder controls, stores, and releases the urine. This Yang organ is responsible for receiving, storing, and releasing urine at the proper time.
2. The Gall Bladder stores and secretes bile. This Yang organ is responsible for storing and releasing bile at the proper time.
3. The Stomach stores the food. This Yang or-


The energy of the Stomach Channels flows down from the head and torso into the uterus, developing the fetus's muscles and connective tissues.

Figure 2.16. The mother's Stomach Channels are responsible for the sixth lunar month of creation. The Six Pitches are established within the body's storage areas. The Metal Jing is beginning to be accepted by the fetus's body.

gan is responsible for the receiving, storing, rotting, and ripening of food at the proper time.

4. The Large Intestine stores the solid waste. This Yang organ receives, stores and absorbs food and releases waste at the proper time.
5. The Small Intestine stores and transforms liquid matter. This Yang organ receives, stores, transforms, and digests food, and releases its waste products at the proper time.
6. The Triple Burners store the body's Qi. This area of the body receives, stores, absorbs, and moves Qi.

At this stage of development, the Six Pitches which support and stabilize the Lower Burners (see Chapter 6) and nourish the Qi are established in the organs known as the Six Yang Organs, also called the Six Storage Areas.

The Six Pitches are six specific tone resonances (notes) that vibrate within the body's internal organs and stimulates specific organ and tissue areas. These Six Pitches relate to the Five Prenatal (Heaven) Elemental Sounds of Jue-Wood, Zhi-Fire, Gong-Earth, Shang-Metal, and Yu-Water. The sixth note Xi relates to the Postnatal (Earth) Fire Element and corresponds to the Pericardium and Triple Burners. The ancient Chinese used these Six Pitches for specific clinical treatments. The sound "Yu" for example, spoken in a low tone, will vibrate the lower abdominal area and is used for the treatment of Kidney and Bladder problems.

In the sixth lunar month of formation, the fetus's eyelids separate and eyelashes form, and its skin is wrinkled.

MONTH SEVEN

During the seventh lunar month, the mother's Lung Channels create the bones, skin, and hair (Figure 2.17). The Wood Jing is beginning to be accepted by the fetus's body.

The Wood Jing energy supervises the assertion and direction of the fetus's emotional/spiritual aspects. Any faltering of the Wood Jing energy is associated with severe psychological problems (e.g., passive-aggressive personality disorder).

In the seventh lunar month, the fetus's Stom-


The energy of the Lungs' Channels flows down from the center of the torso into the uterus, creating the fetus's bones, skin, and hair.

Figure 2.17. The mother's Lung Channels are responsible for the seventh lunar month of creation. The Seven Essential Stars open the orifices to let in the light from Heaven and Earth. The Wood Jing is beginning to be accepted by the fetus's body.

ach and Intestines are stabilized, and the Seven Essential Stars open the body's orifices to absorb the light from Heaven and Earth. These stars consist of the sun, moon, and five planets: Mars, Venus, Mercury, Saturn, and Jupiter. Each star is associated with one of the body's orifices: eyes, ears, nostrils, mouth, anus, and urethra. These orifices serve as receiving and projecting energetic portals for Jing-Essence, Qi-Energy, and Shen-Spirit. They also serve as messengers of the body's Five Yin Organs. Thus the Liver receives messages through observation, the Heart through speech, the Spleen through taste, the Lungs through smell, and the Kidneys through hearing.

These energetic messages are received by the body's Wu Jing Shen and emotionally and energetically interact through the body's Six Openings.

1. The eyes absorb images into the Liver which affect the Hun (The Three Ethereal Souls).
2. The ears absorb sounds into the Kidneys which affect the Zhi (Will Power).
3. The nose absorbs smells into the Lungs which affect the Po (The Seven Corporeal Souls).
4. The tongue absorbs tastes into the Spleen which affect the Yi (Intent / Intellect).
5. The physical body absorbs sensations into the tissues which affect the Shen.
6. The spirit (along with the physical body) absorbs sensations into the Heart which also affect the Shen (Spirit).

Physically, during this lunar month, there is a substantial increase in the fetus's weight and its head and body are more proportionate. The fetus can survive if born prematurely (between 27 and 28 weeks); however, its hypothalamic temperature regulation and the Lungs' production of surfactant (a phospholipid substance important in controlling the surface tension of the air-liquid emulsion present in the lungs) are still inadequate.

MONTH EIGHT

In the eighth lunar month, the mother's Large Intestine Channels complete the formation of the fetus's skin, harmonizing the Heart (the Shen), and quieting the breathing. As the fetus receives the Zong Qi-Essential Qi (energy collected from Heaven and Earth and accumulated within the


The energy of the Large Intestine Channels flows up the arm and down the center of the torso into the uterus, completing the formation of the skin, harmonizing the Heart, and quieting the breathing.

Figure 2.18. The mother's Large Intestine Channels are responsible for the eighth lunar month of creation. The Earth Jing is beginning to be accepted by the fetus's body.

chest) from the mother's Spleen, the Earth Jing begins to be accepted by the fetus's body, completing the formation of the skin (Figure 2.18)

The Earth Jing energy supervises the quality and maturation of the fetus's emotional and spiritual bonding and boundaries. Any faltering of the Earth Jing energy is associated with problems of severe psychological disturbances (e.g., schizophrenia). These psychological disturbances may be evident at birth or develop later in life.

The mother's Large Intestine Channels control the fetus's orifices. At this stage in development, the fetus's muscles and flesh are formed. The formation and consolidation of the fetus's Jing is now completed, along with the fetus's developing Zhen Qi-True Qi (energy that circulates in the body's channels and collaterals which nourishes the Yin and Yang organs and fights disease).

At the end of the eighth month, the bones of the fetus's head are soft, its skin is less wrinkled, and there is subcutaneous fat deposited throughout its body. If it is a male child, its testes will now descend into the scrotum.

At this stage, the fetus will normally assume an upside-down position to prepare for its birth descent. If the fetus is born prematurely, its chances for survival are now much greater.

MONTH NINE

During the ninth lunar month, the mother's Kidney Channels control the amount of energetic intake the fetus absorbs through its connection to the umbilicus (Figure 2.19). Qi, Blood and food nutrition are absorbed into the fetus's body, after they pass through the umbilical vein to the fetus's Liver. From the Liver, the nutrients are processed and absorbed into the Blood to be distributed throughout the fetus's body.

The flexible structure of the umbilical cord is attached to the placenta. The placenta, which formed on the uterine wall after the first week of pregnancy, consists of tissues from both the mother and the embryo. The function of the umbilical cord is to carry away the baby's waste products and pass food, energy, and oxygen from the mother's blood stream to the embryo. The mother's Kidney Channels will regulate the re-



The energy of the Kidney Channels flows up the inside of the legs and into the uterus, stabilizing the fetus's energetic boundaries.

Figure 2.19. The mother's Kidney Channels are responsible for the ninth lunar month of creation. All the fetus's spatial cavities and energetic boundaries are now established.

lease and absorption of Qi and Shen flowing into the fetus's Liver through the umbilical cord.

After the umbilical cord has been severed, the baby's umbilical veins still remain. These umbilical veins eventually become the ligamentum teres that connect from the umbilicus, up along the interior surface of the abdominal wall, through the free margin of the falciform ligament, to the right and left lobes of the Liver. This maintains the baby's connection between its Liver and its Lower Dantian (navel).

At this stage in development, all the fetus's energetic spatial cavities (internal organ tissue chambers) and energetic boundaries are arranged to keep the fetus safely prepared for its birth journey.

Also in this month, the Internal Palaces and Nine Dantian Chambers (the nine internal cavities established within the fetus's Three Dantians (the body's three energetic reservoirs) are arranged and securely established to keep the fetus's Jing-Essence safe.

In the ninth month, additional subcutaneous fat accumulates throughout the fetus's body. Externally, the fetus's fingernails will extend to the tips of the fingers and sometimes beyond.

MONTH TEN

At the tenth lunar month, the mother's Bladder Channels control all Five Yin Organs (Liver, Heart, Spleen, Lungs, and Kidneys) and Five Yang Organs (Gall Bladder, Small Intestine, Stomach, Large Intestine, and Bladder) (Figure 2.20). The baby's energetic reservoirs (the Three Dantians)



Figure 2.21. Heaven and Earth Qi settle into the baby's Lower Dantian and the process of birth begins.



The energy of the Bladder Channels flows down the back of the head and back and into the uterus, securing the fetus's Dantians and the spatial cavities surrounding the major organs.

Figure 2.20. The mother's Bladder Channels are responsible for the tenth lunar month of creation. The baby's Dantians, and spatial cavities surrounding the major organs are completely developed to maintain the safety of the baby's Jing. Heaven and Earth Qi settle into the baby's Lower Dantian and birth begins.

and the internal spatial cavities that surround the major organs are developed to maintain the safety of the baby's Jing. The child is ready to be released into the world. The process of birth begins when Heaven Qi and Earth Qi settle into the baby's Lower Dantian (Figure 2.21).

The energy of the Seven Corporeal Souls (Po) is responsible for the first physiological processes after birth, allowing the child's eyes to see, ears to hear, and Heart to perceive. The Po are also responsible for the movements of the hands and feet and the breathing pattern.

The purpose for the Qigong doctor's study of the ten lunar month developmental process, is to create a foundation for understanding the patient's physical development. This knowledge of the patient's physical development establishes a comprehension of the structural formation of the Five Elemental Constitutions. The Five Elemental Constitutions are described in the next chapter.

POSTNATAL ENERGY DEVELOPMENT

Throughout prenatal development, the Eight Extraordinary Vessels (see Chapter 7) were responsible for transporting, transforming, and producing Qi and Blood for the fetus, while the Twelve Primary Channels (see Chapter 6) were still in the process of gradual development. The focus of energetic activity generated from the fetus's Lower Dantian and Eight Extraordinary Vessels, resonates throughout the fetus's body creating tissue development.

Once the umbilical cord is severed, the primary focus of energy shifts, becoming diverted from the Lower Dantian to the Middle Dantian (located in the baby's chest area). After birth, Gu Qi (food energy) flows into the baby's Stomach while it nurses and begins the movement of Blood and Qi within the Twelve Primary Channels. These Twelve Primary Channels will now assume the responsibility of circulating Qi and Blood throughout the baby's entire physical and energetic structure. The Eight Extraordinary Vessels shift their function to regulating the baby's channel Qi. The Taiji Pole (which has been in the process of dropping from the fetus's Mingmen area to the Huiyin area) is now stabilized in the perineum.



Figure 2.22. As the child develops, the energetic rivers and pools regulate the formation and production of his or her growth.

The natural resonant vibration of the baby's Taiji Pole (energetic core) causes an energetic expansion and contraction, projection and reception that simultaneously affects the baby at five distinct levels: physical, mental, emotional, energetic and spiritual. Balanced physical growth will only occur when all five levels are in equilibrium. The physical body is generally the slowest realm to respond to physical growth. Matter does not develop at the same rate as energy, mind, or spirit. This being the case, the energy, mind, and spirit must wait patiently for the physical body to evolve before progressing as a whole (Figure 2.22).

ENERGETIC EMBRYOLOGICAL OVERVIEW

Understanding the energetic process of fetal development provides the Qigong doctor with an overview of the energetic factors in tissues, organs, and channel function. This understanding is essential for diagnosing the origin and causes of disease as being either congenital or acquired. Unlike Western medicine, Chinese medicine treats the root of the illness, not just its symptoms. In Medical Qigong therapy, cases of congenital insufficiency of Qi or congenital disorders of Qi activities, are treated by either tonifying (strengthening) the Eight Extraordinary Vessels or purging (eliminating) the pathogenic energy from the Eight Extraordinary Vessels. This consolidates and regulates the patient's Prenatal Qi.

For acquired diseases, the patient can only be cured when a selection of points and the methods of emitting Qi for purgation or tonification are determined according to the imbalances of Qi circulation in the Twelve Primary Channels. Both congenital and acquired factors should be considered in every case because both the origination and development of diseases may result from either source, or a combination of both sources.

THE ETERNAL SOUL

In Chinese energetic medicine, the Original Spirit differs from the body's Eternal Soul. The Original Spirit (Yuan Shen) is rooted in the combined Jing, Qi, and Shen of the mother and father. Later the Yuan Shen is integrated and sustained through the embryo's own Five Spiritual Essences or Wu Jing Shen (see Chapter 13), which are created from the energy of the Five Yin Organs. The Eternal Soul, however, is absorbed into the mother's egg at the time of conception, as the sperm enters.

The Eternal Soul is rooted into the Heart and Middle Dantian area by a silver cord, which is additionally rooted within the body's Taiji Pole. When the Eternal Soul becomes rooted within the body's Taiji Pole, it is described as "emitting the spark of the supreme fire" (Light of God), and is considered a divine fragment of God, or the Dao. It is from this divine resonating light that the body's Taiji Pole becomes energized and all Three Dantians become interconnected. The rooting of the Eternal Soul is therefore considered the first emanation from the divine source within the human body.

To travel, and receive spiritual guidance and insight, the Eternal Soul can leave the body in the form of an "Astral Body," departing through the Baihui point at the crown of the head. The silver


Tai Yi
"Great
Divinity"
Resides in
the head
(Light)
Upper Dantian
(Intuitive
Communication)
Resides in
the Heart
(Vibration)
Si Ming
"Administer of
Destiny"
Middle Dantian
(Empathic
Communication)
Bai Yuan
Regulates the
Seven Po
Wu Ying
Regulates the
Three Hun
Xia Tao Kang
"Below Healthy
Reach" (Life)
Resides in
the Navel
(Heat)
Lower Dantian
(Kinetic
Communication)

Figure 2.23 The Lords of the Three Dantians: Tai Yi, Si Ming, and Xia Tao Kang

cord, which is connected to the Astral Body, is located at the fifth and sixth thoracic vertebrae. This physical area is the place on the spine where the silver cord lifts off when an individual astral travels. This area also corresponds to the back of the Heart center, between Ling Tai GV-10 (Spirits Platform) and Shen Dao GV-11 (Spirits Gate). The astral travels of the Eternal Soul are generally to one of the nine higher spiritual planes.

The Eternal Soul becomes the intermediator between the divine, the Original Spirit (Yuan Shen), the Acquired Spirit (Zhi Shen), and the body's Soul Extensions (various traits and characteristics). These Soul Extensions manifest in the energetic field, and influence behavior and perception.

Once the Eternal Soul has established its residence, it separates its Yin and Yang spiritual energy into three spiritual energies which are the energizing forces of the body's Three Dantians, and are called Tai Yi, Si Ming, and Xia Tao Kang. These three spiritual energies are referred to as the Lords of the Three Dantians, and are named according to their function: Tai Yi translates to mean Great Divinity, Si Ming translates as The Administrator of Destiny, and Xia Tao Kang translates as Below Healthy Peach (Life).

The Chinese medical terminology, which describes the Eternal Soul as consisting of three spiritual energies called the Lords of the Three Dantians, is extremely metaphoric and is used to describe the many energetic aspects of the human soul.

The Eternal Soul radiates through the physical, energetic, and psycho-emotional domains of human existence (Figure 2.23). Whole-body consciousness is the main characteristic of the Eternal Soul. Without the interactive process of the Eternal Soul, energy would have no specific direction and would remain in meaningless activity. The Eternal Soul radiates energy in all directions throughout the body and is responsible for life and health, as well as the formation and growth of the body.

In the scope of energetic manifestations, the Eternal Soul expresses its innate qualities as energetic movement, functioning through the physical form. It is led by the Shen and is connected to all parts of the body. The light of the Eternal Soul is revealed through the light or energy of the eyes. Through the influence of the Eternal Soul, all of the body's energetic processes seek wholeness. The Eternal Soul knows exactly what is needed in every situation for survival and health preservation.

The distinction between the Eternal Soul and the Yuan Shen is that the Eternal Soul, although spiritual in nature and connected to the Wuji (infinite space), is still considered individuated. The Yuan Shen, however, although individual in its conditioned state, can also be universal. The connection between you and others, for example, is considered a spirit connection (kindred spirits uniting). The connection between you and the divine is considered a soul connection (your true innate nature reconnects with its origin), and relates only to the connection between one's self and the divine.

When the Qigong doctor meditates, the Eternal Soul consciously enters a spiritual realm wherein the doctor perceives the ideal of things rather than the things themselves. The doctor no longer depends on the senses, but upon a clear inner-vision that perceives the whole picture. It is here, within this spiritual state, that the higher knowledge of things unfolds through divine intelligence and all things reveal their true nature.

When conserved and amplified through practice, the energy of the doctor's Eternal Soul reveals a bright radiant quality, which permeates and penetrates the cells, tissues, organs, and external energy fields. These energetic fields create for the Qigong doctor a strong luminous shield of energy, capable of guarding the body against an attack of hostile energy by enabling it to:

- ward off the invasion of External pathogens and harmful electromagnetic fields,
- ward off the negative influences of malevolent spirits,
- ward off ill intentions and spiritual malice projected unconsciously or deliberately by others, and
- ward off the parasitic influences of demonic forces.

At conception, when the sperm enters the ovum, a polar axis that forms the embryo's Taiji Pole is created. The energetic vortex thus created draws spiritual energies into the body from Heaven and Earth. After birth, the degree to which an individual can draw upon, and absorb, spiritual energy depends on his or her karma (previous thoughts, actions and level of consciousness), and course of destiny.

During conception, three spiritual energies are given to each individual from the divine to create and maintain the existence of the Eternal Soul. These three spirit energies, called the Lords of the Three Dantians, reside in the innermost subtle aspect of the body and are described as follows:

1. The Tai Yi (Great Divinity) resides in the head and Upper Dantian, and is considered the Lord of the Nei Wan (Innermost Palace). It governs a multitude of the body's spirits, causing man's Yuan Shen to shine externally. The Tai Yi facilitates awareness of the Three Ethereal Souls (Hun), and advocates for personal spiritual enlightenment.
2. The Si Ming (The Administrator of Destiny) resides in the Heart and Middle Dantian, regulates the body's Qi, and is the source of the mind and its emotional connections. The Si Ming is considered the Eternal Soul (some believe that this soul reincarnates). The Si Ming controls the spirits Wu Ying and Bai Yuan, that directly affect the body's Jing, Qi, and Shen. The Si Ming challenges our reactions to various internal and external obstacles.
    a. The Spirit Wu Ying (Without Excess) occupies the left side of the body, and regulates man's Three Ethereal Souls (Hun), which are called:
        (1) Tai Guang (Eminent Light),
        (2) Shang Ling (Pleasant Soul) and the Five Agents, and
        (3) Yu Jing (Hidden Essence).
    b. The Spirit Bai Yuan (Pure Origin) occupies the right side of the body, regulates the Seven Corporeal Souls (Po), which are called:
        (1) Flying Poison
        (2) Unclean Evil
        (3) Stinking Lungs
        (4) Corpse Dog
        (5) Fallen Arrow
        (6) Yin Bird
        (7) Devouring Robber

Both the Hun (that come from Heaven) and the Po (that come from Earth) are established within the fetus's internal organs at conception but lie dormant until the third month. This is because, at the third lunar month, the fetus's Orbs are sufficiently formed. One belief maintains that the Hun and Po, although residing in the energetic form of the fetus, frequently leave and return to gather and absorb universal and environmental Qi. The Hun will connect with divine spiritual beings, as well as with God. The Po will connect with surrounding environmental spirits.

Note: The Three Ethereal Souls are traditionally referred to as the "Hun" with the assumption that this term depicts all three Hun, thus in Traditional Chinese Medicine the Hun are sometimes referred to in the singular case. The Seven Corporeal Souls are traditionally referred to as the "Po" with the assumption that this term depicts all seven Po, thus in Traditional Chinese Medicine the Po are sometimes also referred to in the singular case.

3. The Xia Tao Kang (Below Healthy Peach/Life) resides in the navel and Lower Dantian and preserves the root of the body's Jing-Essence.

Upon the death of the body, the Hun return to Heaven, the Po return to Earth, and the spiritual energies of Tai Yi and Xia Tao Kang combine with the Eternal Soul stored in the Si Ming (Administrator of Destiny). These three spiritual energies (Tai Yi, Xia Tao Kang, and Si Ming) blend together, combining into one energy that completes the integration of the Eternal Soul. This soul leaves the body and returns back through the tunnel of light to the divine light for judgement, or wanders the Earth becoming a Gui (ghost).

In Western culture, our internal dialogues are sometimes associated with encounters with good or evil spiritual influences. In Chinese medicine the internal dialogues that influence the patient's psyche are also divided into good and evil; these spiritual / emotional influences are considered to be specific good and evil characteristics in man's Hun and Po. The spiritual components and influences of the Hun and Po are considered to be separate entities, or archetypes, acting upon man's Shen, which in turn affects the Eternal Soul.

These archetypes are regarded as spirit souls that can exert a positive or negative influence on a individual's life depending on the nature of the individual's Eternal Soul. The good internal influences manifest through the Hun. The evil internal influences manifest through the Po. The Hun or Po can motivate personal growth, or can hinder it and cause illness, and even the demise of the body.

THE THREE ETHEREAL SOULS (HUN)

The Three Ethereal Souls are the spiritual part of man that ascends to Heaven upon the death of the body. The Three Ethereal Souls are composed of the Three Hun, that originate from Heaven, reside in the Liver, and resonate from the Three Dantians. The Hun have the following associations: light, Yang, Heavenly soul, Shen, as well as positive emotions and feelings (Figure 2.24). The Three Ethereal Souls are the Tai Guang, Shang Ling, and Yu Jing. They are described as follows:



Figure 2.24. The Three Ethereal Souls are composed of the three Hun, that originate from Heaven and reside in the Liver. The Hun represent spiritual consciousness, provide the energetic movement of the mind, and are associated with Heaven Qi and the Five Agents. The Hun are the spiritual part of man which ascends to Heaven after death. The Hun are associated with positive emotions and feelings, light, Yang, Heaven, and Shen.

The Three Ethereal Souls are named (1) Tai Kuang, (2) Shang Ling, and (3) Yu Jing.

1. The Tai Guang resonates within the Upper Dantian, and is situated in the cranial cavity, just below the Baihui GV-20 (Meeting of Yin) point. This Hun's name means "eminent light," and it is considered the ultimate balance of pure Yin and Yang energy in harmony. It is connected energetically with the Upper Dantian and Heaven, and always strives for physical, mental, emotional, and spiritual purity.
2. The Shang Ling resonates with the Middle Dantian and is situated in the Heart and corresponding vessels and is linked to the body's Five Agents. This Hun's name translates to "pleasant soul," and it is considered changed (or transformed) Yin energy. It is connected with the Middle Dantian and is a soul that is concerned for others. It is associated with the Five Agents, and produces our desire to be involved in a diversity of social interests and responsibilities.
3. The Yu Jing resonates with the Lower Dantian. Translated, the name means "hidden essence." This Hun is considered mixed (or combined) Yin energy. It is connected with the Lower Dantian and is associated with the Earth, producing our desire for enjoying life's pleasures and comforts, as well as the pure passions of life.

The Hun are classified as Yang spirits and are to be cultivated and refined. Imagination, visualization, and positive affirmation in the form of prayer and meditation are needed to awaken and establish an active relationship with the Three Ethereal Souls.

The Hun can be accessed through the Hunmen Bl-47 (Gate to the Hun) point on the back of the body (below the shoulders). It is used clinically to spread Liver Qi and harmonize the Middle

Burner. The Hun respond to Heaven's energetic grids (universal energetic fields). The stars and planets within these Heavenly grids exert an influence on the Hun causing each individual's body to react to certain astrological configurations. The positive or negative reaction is based on the affinity of the vibrational rate of the Hun and the energies of a particular astrological alignment.

THE SEVEN CORPOREAL SOULS (PO)

The Seven Corporeal Souls are closely linked to our body's Jing-Essence. The Po manifest the body's Essence in the form of hearing, sight, and tactile sensations.

The Po pertain to the animal nature of man's instincts and drives and are considered inferior souls to the Hun (Figure 2.25). The Po are passionate and advocate experiencing life in its fullest measure. They are, however, in a constant state of dying. The Po will return to the Earth with the body after death. The Po have the following associations: heavy, Yin, Earthly Spirit, Essence, and negative emotions and feelings.

The Po are a composite of Seven Corporeal Souls, which originate from Earth, reside in the Lungs, and resonate from specific areas in the body. The Po can be accessed through the Pohu Bl-42 (Door to the Po) point on the back of the body (between the shoulders). This point is used clinically to treat energetic imbalances of the Lungs. The Po respond to the Earth's energetic grids (see Chapter 10) and cause each of us to resonate in harmony or disharmony to certain ecological configurations. An individual's attraction, or feeling of not belonging, depends on the vibratory affinity, or lack thereof, between the body's Po and the environmental energy of a particular area.

When the fetus begins its movement, its Yin energy tranquilizes the Po, which act as guardians of the fetus's body. The Po's nature is one of survival, and their energies can be directed towards self-preservation or self-destruction (devouring and robbing the body of life-force energy).

The Seven Po are located along the line between the Huiyin CV-1 and the Baihui GV-20 points, embracing the body's Taiji Pole (also called the Center Thrusting Channel) at the following locations:

Figure 2.25. The Seven Corporeal Souls are composed of the Seven Po, which originate from Earth and reside in the Lungs. The Po are regarded as the animal nature or drive. They provide energetic movement to the body's Essences, and are considered inferior Souls. The Po will return to the Earth with the body after death, and are associated with negative emotions and feelings, heaviness, Yin, Earth, and Jing.

The negative thoughts and emotions of the Seven Corporeal Souls are named (1) Flying Poison, (2) Unclean Evil, (3) Stinking Lungs, (4) Corpse Dog, (5) Fallen Arrow, (6) Yin Bird, (7) Devouring Robber.

1. The Po of Essence (Soul of the Five Element Earth) is located at the midpoint of the Taiji Pole. This Po is the counterpart to the Hun's Earth Agent (the Virtue of Trust). This Po manifests through the acquired emotions of worry, regret, remorse, obsessiveness, and self-doubt.
2. The Po of Qi (Soul of the Five Element Wood) is located below the diaphragm. This Po is the counterpart to the Hun's Wood Agent (the Virtue of Kindness). This Po manifests through the acquired emotions of anger, irritability, blame, rage, resentment, and jealousy.
3. The Po of the Spirit (Soul of the Five Element Metal) is located posterior of the Tanzhong (CV-17) point, inside the mediastinum, near the Middle Dantian. This Po is the counterpart to the Hun's Metal Agent (the Virtue of Integrity). This Po manifests through the acquired emotions of grief, anxiety, sadness, shame, disappointment and guilt.

4. The Po of Yin (Soul of the Five Element Water) is located posterior of the navel, in front of the Taiji Pole. This Po is the counterpart to the Hun's Water Agent (the Virtue of Wisdom). This Po manifests through the acquired emotions of fear, loneliness, and insecurity.
5. The Po of Yang (Soul of the Five Element Fire) is located anterior of the Mingmen (GV-4) point behind the Taiji Pole. This Po is the counterpart to the Hun's Fire Agent (the Virtue of Order). This Po manifests through the acquired emotions of nervousness, shock and excitement.
6. The Po of Sex (Soul of Heaven) is located below the Baihui (GV-20) point in the Ni Wan (Upper Dantian) area.
7. The Po of Life (Soul of Earth) is the only one not located on the Taiji Pole, but is located at the bottom of the feet in the Yongquan (Kd-1) points and is considered a neighbor of the Soul of Essence.

The Seven Corporeal Souls (Po) are also called the "seven animals," or "sentient souls of the body," and "seven turbid demons." When afflicted or restless, the animal nature of the Seven Po quickly becomes hostile, and their names change to express the different negative thoughts and emotions expressed from each Po soul. Each Po has a favorite mantra that it whispers inside a person's mind to influence the individual. The Po's Seven Turbid Demon Natures are described as follows.

1. The Flying Poison (or Quick Evil) suddenly explodes with rage and venomous thoughts of evil intention (e.g., "I'll kill you for that!" "How dare they!").
2. The Unclean Evil (or Shame) entices by tempting and luring an individual into a place or situation from which escape is difficult, and then creates distress in the form of guilt, which generates shame. This spirit creates a feeling of being discredited, dishonored, or disgraced (e.g., "I'm worthless;" "No one has or will ever love me.").
3. The Stinking Lungs (or The Smell of Death) destroys hope, which can lead to a sense of despair (e.g., "I just want to die;" "Just kill me and get it over with!").
4. The Corpse Dog (or Being Scorned) is like a dog that has been beaten and starved, the presence of this spirit intensifies depression by despising itself and holding itself in contempt to a point of no return (e.g., "I'm not worth keeping alive;" "Leave me alone to die!").
5. The Fallen Arrow generates the foregone conclusion that attempting goals is fruitless (e.g., "I'll never be able to accomplish that." "Why even try? I'll never make it.").
6. The Yin Bird (or Night Tormentor) harasses the individual, causing him or her to experience extreme pain and severe anguish (e.g., nightmares and restless sleep).
7. The Devouring Robber (or Sipping Thief) steals the individual's life-force energy by devouring it through negative emotions such as jealousy, envy, and bitterness (e.g., "You love him/her more than you do me;" "I'll never forgive you!").

The Seven Po help in developing the growth of consciousness by providing obstacles to test the individual's faith and devotion. Many times the Seven Corporeal Souls will work in conjunction with outside spiritually hostile forces to test the individual's spiritual endurance.

After the child has been born, enlightened parents can assist the child in facing his or her own internal demons. Once the child is self-aware, he or she can be taught to restrain and control the Seven Po so as to prevent them from taking control. To minimize the effects of these souls on the body, one can learn special meditations, involving visualization, imagination, positive affirmation, and mantras (literally "protections of the mind" or "mind protectors").

A mantra is a word, phrase, or sound, repeated silently or aloud, that one can consciously use as a tool to guide one's own mental, physical, and emotional states. People naturally repeat both positive (self-affirming) mantras and negative (self-destructive) mantras as part of their internal self-talk. When positive mantras are used by an


The Eternal Soul
The 12 Soul Extensions of the Yuan Shen
Extensions or Personality Characteristics

Figure 2.26. The Eternal Soul, Yuan Shen and 144 Soul Extensions

individual who holds them in high regard, they enable that individual to combat the Seven Corporeal Souls' mantras. These mantras also facilitate connecting the individual to the divine. Used consciously, mantras and/or prayers can uplift and maintain the individual's self-esteem.

The Chinese view meditation as a deep spiritual contemplation that results in openness to the divine. They view prayer as energy focused towards the divine. Individuals choose what to focus their attention on; therefore, any chronic detrimental thoughts can be countered with positive affirmations to change self-destructive habits.

THE ORIGINAL SPIRIT (YUAN SHEN)

The Original Spirit (Yuan Shen) radiates and extends from the interior of the Eternal Soul. This spiritual light crystallizes a spiritual body, gradually becoming consciously effective and moving into action. It envelops the body and communicates through innermost thoughts, sensory feelings, and emotions. Although the body's Jing and Qi will degenerate, the Original Spirit is immortal, as it is the expression of the Eternal Soul.

The Shen develops and contains Twelve Soul Extensions. These Twelve Soul Extensions contain the body's different personality characteristics (Figure 2.26). Although Si Ming controls the residence of the Eternal Soul, the body's Shen is free to make decisions that affect life and health based upon the individual's free will (the interaction between the Yuan Shen and the Zhi Shen), which then manifests through the Twelve Soul Extensions.

THE EFFECT OF THE HUN AND PO ON THE YUAN SHEN

The Yuan Shen is a manifestation of the Eternal Soul and is primary to the Hun and Po. The combination of the Seven Corporeal Souls (Yin Souls) and the Three Ethereal Souls (Yang Souls) creates the sustaining energy for the body's Original Spirit (Yuan Shen). The Yuan Shen also controls and organizes the psycho-emotional aspect of the body's Five Yin Organs, called the Wu Jing Shen or Five Essence Spirits.

The ancient Chinese viewed the Shen as an Emperor, seated within the Heart; the Hun are viewed as a Loyal Minister, seated within the Liver; and the Po are viewed as a Violent General, seated within the Lungs. If the General (Po), is left in control (being only concerned with the survival of self and the body), he will start to dominate (a condition referred to as a rebellious General and a weak Emperor). At the point when the General (Po) dominates, the individual's acquired mind takes over and the individual becomes concerned only with his or her own survival, and thus becomes self-absorbed. The goal for spiritual cultivation is to control the rebellious General, making him into a servant. Once the inner government is orderly, the strong and violent nature becomes tame. Then, through the wise council of the Loyal Minister (Hun), the individual can walk a path of virtue. Virtue is the path that leads the individual's Shen so that even his or her human consciousness is dominated by the Hun and the Yuan Shen.

When the Hun control the energy body and are nourished by the virtues, the energy body then becomes a vehicle for the Heart's Shen, which is non-local and non-linear in terms of time and space.

When the Heart's Shen is no longer dominated by the Yin and Yang souls (Hun and Po) and the Five Element energies of the lower energetic plane (Wu Jing Shen), the individual returns to an awareness of his or her connection to the universe (Wuji) and the divine. This state of consciousness is sustained through prayer and meditation.

When beginning to develop the Heart's Shen, the first separation of the individual's energetic spirit body or "dream body" from the physical body generally leaves the Shen in a weakened state (referred to as Yin Shen). The weakened Yin Shen must be protected. This Yin Shen is part of the Hun, and leaves the body naturally whenever the patient is weak, sick, in shock, or asleep. It may also leave during the early stages of Qigong meditation or Taijiquan practice. The astral travels of the Yin Shen are generally confined to the lower spiritual planes, and it sometimes needs to be reclaimed through "soul retrieval" (see Chapter 19). Once the Shen has been cultivated, refined, strengthened, fortified, and controlled through the development of the energy body, it is then referred to as a Yang Shen. When the energy body spiritually travels, the developed Yang Shen can transverse the Nine Levels of Heaven or the Nine Levels of Earth in an instant.

The Nine Levels of Heaven are nine spiritual planes which exist within Heaven's energetic grids. Within the lower levels there exists enlightened beings coexisting with other spiritual entities. The Nine Levels of Earth are nine spiritual planes which exist within Earth's energetic grids. Within these levels of Earthly spiritual planes there exists various dimensions of animal, vegetable and mineral powers, as well as Earthly spiritual beings.

YIN AND YANG ASPECTS OF THE ETERNAL SOUL

The human soul has an endless source of vitality from the infinite high-frequency force of the divine. This divine energy descends from the Heavens into the body's Taiji Pole, taking up residence and interacting on the physical plane. The body serves as a medium of transformation for the Eternal Soul. The soul's activity extends and expresses its essence through the physical form and through consciousness. As we grow and change, the Eternal Soul maintains stability by providing the energetic blueprint for orderly development. On the spiritual plane, when referring to the energetic dynamics of the Eternal Soul, there are two basic movements: (1) Yin - the downward movement and (2) Yang - the upward movement.

1. The Yin aspects of the Eternal Soul spirals downward. The spiralling movement of the energetic soul results in the energy transforming from the highest divine energetic frequencies to the lowest. Within this spiritual transformation process, there is a parallel gradual decrease in levels of consciousness. The lowest frequency creates matter, and is the bases for all the prenatal transformations. At the higher frequencies, the principles by which Qi operates are difficult to perceive because our lower state of consciousness does not resonate in harmony with the information being

Spiritual Energy	Resides in...	Associated Dantian	Purpose	
Tai Yi Great Divinity	the head as light	Upper Dantian (intuitive communication)	Governs the body's Spirits, makes life shine forth, and encourages man to know the spirits of his Ethereal Soul	
Si Ming Administrator of Destiny	the Heart as vibration	Middle Dantian (empathic communication)	The Eternal Soul—regulates the prime energy of life (Qi) and is the source of the emotions and mind Controls the Wu Ying and Bai Yuan Spirits	Wu Ying (Without Essence), occupies the left side of the body and regulates the Three Hun (Ethereal Souls), associated with the Liver
				Bai Yuan (Pure Origin) occupies the right side of the body and regulates the Seven Po (Corporeal Souls), associated with the Lungs
Xia Tao Kang Below Healthy Peach (life)	the navel as heat	Lower Dantian (kinetic communication)	Preserves the root of the body's Essence (Jing)	

Figure 2.27. The patient's soul resides in the body's Taiji Pole, connected with Si Ming, the Administrator of Destiny. Upon the death of the physical body, the Three Hun return to Heaven, the Seven Po return to Earth, and the energy of Tai Yi and Xia Tao Kang envelope the Eternal Soul (stored in Si Ming) becoming one energy. The Eternal Soul leaves the body through the specific gate (solar plexus, third eye, or top of the head) associated with the patient's degree of spiritual evolution, returning back through the tunnel of light to the divine.

presented. As energy slows down its resonance, it is more readily perceived by our five senses; this gives matter the quality of hardness, form, and smell, and allows us to observe its energetic patterning.

2. The Yang aspects of the Eternal Soul spirals upward. The spiraling movement of the energetic soul results in energy transforming from the lowest level of consciousness to the highest divine energetic frequencies during postnatal transformation. Spiritual evolution involves a progressive opening up of all of the body's energy centers (Three Dantians) along the Taiji Pole, until a state of absolute unity of body, mind, emotion, energy, and spirit is achieved (known as enlightenment).

In the evolutionary process of the soul, both stability and change become as one when there is a deep connection to wholeness. This soul serves as a pivotal point for the body's Jing, Qi, Shen, Body Fluids, connective tissues, and emotions, all of which express wholeness. Without this connection the patient experiences a serious psychic splitting of his or her energies. The part that is open to change will experience resistance from the part that demands stability.

THE FINAL EXIT OF THE ETERNAL SOUL

As the body begins to die, the Yuan Shen begins to prepare the Eternal Soul for its final journey home. This change of residence for the patient's spiritual energies is crucial. At the time of death the Eternal Soul must disconnect from the Heart and Middle Dantian area, and the soul must exit the dying patient through one of the Nine Orifices. The lower orifices include the anus and urethra, while the upper orifices include the eyes, ears, nostrils, mouth, as well as the Yintang and Baihui areas (Figure 2.27). It is believed that the area from which the patient's soul exits the body determines the state of its spiritual evolution and to which area the patient is most attached (i.e., if the patient is attached to vision, they are more inclined to leave through the eyes, etc.).

When the Medical Qigong doctor is assisting a terminally ill patient, treatment focuses primarily on purging stagnant spiritual energy from the patient's body. Spiritual purging is required to purify and cleanse the patient's Eternal Soul. Once the patient's soul has been cleansed, the patient becomes peaceful as all material, emotional, and spiritual attachments to this life are released. The patient attains a sense of completion and welcomes the final adventure of going home. The last rites performed by various clergy and ministers in Western culture serve a similar purpose.

The Qigong doctor then guides and encourages the patient's Eternal Soul into leaving the body through the top of the head (Baihui). Souls that are more highly evolved exit the body through this area (at the top of the head), while souls of lesser evolution exit the body through lower portions of the physical structure.

The formation of a Gui or ghost is said to derive from the untransformed energy of the Eternal Soul (see Chapter 19).

SUMMARY

One of the unique aspects of Traditional Chinese Medicine is that it addresses all aspects of the body's energy and spirit. It explores in great detail the spiritual transformations in the body's prenatal state, their relationship to the formation of the body, and to the dying and after-death states. Traditional Chinese Medicine further addresses the potential of spiritual involvement as a cause or cure of specific psychophysical diseases. It is through the complete study of the body's physical, mental, emotional, energetic, and spiritual aspects that doctors of Medical Qigong therapy comprehend when and how to treat their patients.

CHAPTER 3
PHYSICAL DEVELOPMENT AND STRUCTURAL FORMATION

FASCIAL DEVELOPMENT AND ENERGY FLOW

According to the *American Medical Association Encyclopedia of Medicine*, "fascia is the fibrous connective tissue that surrounds many structures in the body. One layer of the tissue, known as the superficial fascia, envelopes the entire body just beneath the skin. Another layer, the deep fascia, encloses muscles, forming a sheath for individual muscles, and also separates them into groups. The deep fascia also holds in place the soft organs, such as the Kidneys. The thick fascia in the palm of the hand and sole of the foot have a cushioning, protective function."

In Traditional Chinese Medicine, the fascia is referred to as Huang (meaning any membranous tissue). Fascial development is divided into two stages: prenatal (congenital) and postnatal (acquired). The prenatal fascia is fixed and determined by the combination of the parents' Jing, Qi, and Shen. The postnatal fascia is formed through diet, exercise, and environmental stresses.

Qi is stored within the tissues and inner fascia layers, where it envelops and protects the internal organs. Energy (that has been stored within the body's organs) is available through the fascia for transformation to nourish the patient's body, mind, emotions, energy, and spirit.

The body consists of three tissue layers:

1. The first and innermost layer is made up of the internal organs, which produce and transform Qi.
2. The second layer consists of the body's fascia, tendons, ligaments, and bones, which assist in transporting Qi to the extremities.
3. The third and outermost layer of tissue consists of the muscles and skin, where Wei (Protective) Qi circulates to protect the organism from invasion of external pathogens (Cold, Heat, Wind, and Dampness, etc.).

After being generated within the body's internal organs, Qi is distributed throughout the body's entire energetic network through the channels and collaterals, via the fascia. Each organ has its own layer of weblike fascia, that covers, connects, protects, and nourishes the tissues. The fascia forms the energetic chambers of the body's organs and channel systems. Qi within the body flows between the fascial sheaths and along the channel system. Through trauma, infection, surgery, disease, or chronic muscular tension, areas of the fascia can become stuck together, inhibiting the flow of Qi and Blood.

Our constitutions are formed, in part, by conditions from the environment that affect the innermost layers of fascial development. Traditional Chinese Medicine divides the observation and diagnosis of the physical developments of these inner fascia into Yin and Yang structures and Five Elemental Constitutions.

YIN AND YANG STRUCTURAL FORMATION

Chinese philosophy teaches that the universe is composed of a pair of opposite forces or energies -- Yin and Yang. Everything in the natural world contains both Yin and Yang. Yin and Yang are interdependent; without Yang, Yin cannot grow; without Yin, Yang cannot develop. The energetic transformation of Yin into Yang and Yang into Yin produces the various observable changes of form and matter (see Chapter 21).

Yin and Yang are the principles governing all things within the human body. Life and death originate from the energies of Yin and Yang, and they are the forces that create all physiological change. In Medical Qigong therapy, the physical structure of the human body is divided into Yin and Yang organs and substances, as well as Yin and Yang energetic functions (e.g., Qi that expands and flows outward is Yang, while Qi that contracts and flows inward is Yin).

Yin and Yang are in a constant state of waxing and waning (Figure 3.1). If this waxing and waning exceeds the body's normal energetic limits and loses its dynamic equilibrium, Deficient or Excess Yin and Yang will occur, leading to the development of abnormalities and illness.

Yin Qi naturally ascends (e.g., Spleen Qi ascends the Clear Qi). When Yin Qi becomes pathological or destructive, it moves downward, descending like cascading water (e.g., descending Spleen Qi causes diarrhea or prolapse of the viscera). Another example of the effects of pathogenic Yin Qi descending would be edema.

Yang Qi naturally descends (e.g., Stomach Qi flows downward). When Yang Qi becomes pathological or destructive, it ascends like the flames of a fire, moving upward (e.g., Rebellious Stomach Qi ascends, causing nausea and vomiting). An-



Figure 3.2. The superior aspect of the body's structure is Yang; the inferior portion is Yin. Think of the sun shining on the upper torso, illuminating the body from the waist to the head, while from the hips downward the lower torso is in the shade.

	Yang	**Yin**
Attributes	active, creative, masculine, Fire, Hot, Heaven, light	passive, receptive, feminine, Water, Cold, Earth, heavy
Organs	the six hollow organs (Gall Bladder, Small Intestine, Stomach, Large Intestine, Bladder, and Triple Burners)	the five solid organs (Liver, Heart, Spleen, Lungs, and Kidneys), along with the Pericardium
Respiration	exhalation	inhalation
Time of Day	the 12 hour cycle from 11 p.m. (before midnight) to 11 a.m. (before high noon)	the 12 hour cycle from 11 a.m. (before noon) to 11 p.m. (before midnight)
Seasons	spring and summer	autumn and winter
Normal Movement	outward	inward

Figure 3.1 Yin and Yang are the Principles Governing All Things Within the Body



Figure 3.3. The posterior portion (back side) of the body is Yang; the anterior portion (front side) is Yin. Think of the sun shining on the back, while the abdomen is in the shade.



Figure 3.4. The superficial aspect (exterior) of the body is Yang; the deep portion (interior) of the body is Yin. Think of the sun shining on the external surfaces of the body, while the internal organs remain in the dark.



Figure 3.5. The left side of the body is Yang; the right side is Yin. Think of facing south in the morning, while performing medical Qigong practice. The sun will rise in the east, illuminating the left side (Yang) while the right side remains shaded (Yin).

other example of the effects of pathogenic Yang Qi ascending would be the temperature of a rising fever.

THE YIN AND YANG OF BODY ASPECTS

Comparable to Western anatomy, Traditional Chinese Medicine also divides the body into aspects or planes. In TCM, these classifications are divided into Yin and Yang physical planes and anatomical directions. These divisions assist the Qigong doctor in defining and categorizing the patient's external tissues, and in determining the collection and movement of Qi (i.e., energy moving into and coalescing in the patient's Yin or Yang areas of the body). The structural aspects are categorized as follows.

- The cranial or superior aspect (towards the head) of the body's structure is considered Yang; the caudal or inferior portion of the body (towards the feet) is considered Yin (Figure 3.2).
- The posterior or dorsal portion (back side) of the body is Yang; the anterior or ventral portion (front side) is Yin (Figure 3.3).
- The superficial aspect (exterior) of the body is Yang; the deep portion (interior) of the body is Yin (Figure 3.4).
- The left side of the body is Yang; the right side is Yin (Figure 3.5).

Aspect	Yang	Yin
upper/lower surface	superior (upper)	inferior (lower)
front/rear surfaces	posterior (back)	anterior (front)
position from midline/middle	lateral (away from center)	medial (middle)
near to/far from the surface	superficial (external)	deep (internal)
sides	left	right

Figure 3.6. A Summery Diagram of the Yin and Yang Aspects of the Body

The Essential Wild Food Survival Guide

Linda Runyon

WELCOME
to the eBook version of *The Essential Wild Food Survival Guide!*

We have extras for you!

When you go into the kitchen to try the fabulous recipes contained in this book, you very well may not want to drag your computer with you! Printing is disabled in this eBook, but we have the whole printable Recipe Section waiting for you, as well as a free Subscription to Linda Runyon's Newsletter!

Just go here and we'll send them to you. (If your computer can't handle the direct link, please type the web address below into your browser's address bar and fly over to Linda's site.)

http://www.ofthefield.com/eBookSpecialOffers.htm

This is a secret back door for eBook owners like you ONLY, and can't be found by coming in the front door of the site.

Your email address is never given to third parties.
It is our strict policy.
You may opt out at any time.

The Essential Wild Food Survival Guide

Copyright © 2002, 2007 by Linda Runyon
original title *From Crabgrass Muffins to Pine Needle Tea*

Linda Runyon
Wild Food Company
PO Box 83
Shiloh, NJ 08353-0083
lrunyon8@yahoo.com
www.OfTheField.com

ISBN 0-936699-11-6 eBook

All Rights Reserved, including the right to reproduce this book, or parts thereof, in any form, except for the inclusion of brief quotations in a review.

All Art by Linda Runyon unless otherwise noted

Photo Credits:
Ruth Demers Executive Director of Rome Sports Hall of Fame of Rome, NY – all photos except the following:
Kerin A. Denser-Fuzy – sow thistle
Paul A. Runyon, Jr. of Seattle, WA – prickly pear, saguaro, cholla, lamb's quarters, malva neglecta, sunflower & shepherd's purse.

Main Cover Art by Linda Runyon
Cover Design by Eric & Todd Conover
Layout and Final Production by Eric Conover

Disclaimer

This book is intended to be an educational tool for gathering and cooking wild plants. The information presented is for use as a supplement to a healthy, well-rounded lifestyle. The nutritional requirements of individuals may vary greatly, therefore the author and publisher take no responsibility for an individual using and ingesting wild plants.



Steps with lamb's quarter seedlings.

Waste ground plantain dandelion.

Dedication

I dedicate this manuscript to Ruth and Paul Runyon who gave me the feeling of unconditional love. Thank you, Mom and Dad. You made it all happen!

Thank you, my beautiful children whose understanding of Mom kept me on the “wild” path. Without my son Eric it would not be possible to bring you this revised edition. Over the years the help has been invaluable. My grandchildren Ceri & Alec, Jason, and Lee, who have been my guinea pigs with spearmint gum and dandelion fluff popsicles.

The homestead years were wonderful and difficult. Thanks to Ken Heitz, who spent them supporting us and our homestead! Deepest thanks to the late Dorothy and Lynn Galusha, Gert and Dick Frulla, Indian Lake, and dozens of friends: especially Nancy & Pete, Nicole, Colleen & Jenny, Jean, Terry, Shirley and Eric & Rose. I couldn’t have done it without you. Thanks to Gary for computer help.

A special acknowledgment to Cristina, one of my teachers, and her mom, Melinda. Out of the woods, the Runyon Institute began. Thank you, Walt Johnson, you taught me the business world! My deepest gratitude to Mae Charon, without whose friendship and business guidance I never would have completed this manuscript. Bruce & Larry, your faith, love and encouragement are monumental! Alice & the late Walt Sherman, your love is my port in the storm. This book was conceived in the lamb’s quarter patch behind the barn. Ruth Demers, you crawled on your tummy, festooned with black flies to take these photos, thank you. Your faith became mine. Paul, my “bro”, you stood supporting me in 110 degrees while you took the western slides! Thank you!

So many people, thank you all!!! Thanks especially Dr. Edward Glenn and the Environmental Research Lab in Tucson for your library, approval and guidance along the path to the Environmentarian Way. Susan Lake and Nancy Sprague gave me their invaluable library skills. Steve “Wildman” Brill is the foraging cohort I trust implicitly. Your advice is well taken. Joan & David Schultz, Kathy & Mel, Richard & Stephanie Bond, Tess and Michael Morearty, you all give me a tremendous feeling of support here in Arizona.

The Wild Food Walks were the result of gracious offers for the use of private lands. Thank you Rose and Bruce Burke, the Nanticote Lenni Lenape tribe of South Jersey, Jim Ridgeway; Kathy Weaver Warrensburg; Lenore Yalisloff and Hazel McManus in Phoenix, Glendale Public Library and David Schultz's direction here in Arizona.

Thanks to Dr. James Duke, Ph.D. you are the database for my manuscript! Steve "Wildman" Brill edited professional to professional. Althea Dixon, your generosity kept my newsletter going...Wanda Wilde, secretary for Wild Foods Co., thank you for your help and hello to your 6 kids (including the triplets)! I know there is a list of hundreds over the years—you all know who you are!!! Thank you! An abundant green year awaits us all.

Misi Linda Runyon



Todd's special place - the cave!

Table of Contents

Page No.

Dedication i
Foreword iv
Preface vi
Acknowledgements viii

PART I AN ENVIRONMENTARIAN LIFESTYLE

Living off the Land 1
An Introduction to Edible Wild Plants 17

PART II FIELD GUIDE TO WILD FOODS

Edible Plants 49
Photos of the Plants 141
Nutrient Value of Wild Foods 173

PART III WILD FOOD RECIPES 195
Soups and Salads 198
Vegetable Dishes & Light Meals 205
Muffins, Breads, Biscuits, and Pancakes 225
Sweets 233
Teas and Other Hot and Cold Drinks 240
Preserving Wild Foods 250
Sundries 255

PART IV REFERENCE SECTION

Cultivation of Wild Edibles 259
Public Wild Food ID Walk Ways 270
A Forager's Research Diary 283

PART V POISONOUS LOOK-ALIKES 290
Appendix Glossary of Scientific & Botanical Terms 302
References 305
Suggested Reading 306

Foreword —by Joe Gang

Linda Runyon is a child of the Adirondack wilderness. It is there that, at a tender age, she discovered that wild clover, yarrow, and wintergreen were edible. As she grew, so grew her knowledge of the abundant wild flora in her beloved mountains.

In 1972 she decided to homestead in the wilderness. Her ability to recognize and use wild plants added immeasurably to her successful survival. By adapting to a diet of wild vegetables, herbs, fruits, and nuts, Linda carved out a niche for herself among women pioneers who relied on Nature. Linda Runyon has gone on to share her wide-ranging experiences and knowledge of wild foods with a growing following: visitors to several plant identification walks (called *Survival Acres*), readers of her books, (*A Survival Acre, Lawn Food Cookbook,* and *Wild Food and Animal Coloring Book*), users of her fantastic plant identification card game ("Wild Cards"), and subscribers to her (now out of print) Environmentarian Newsletter, and the "Wild Foods Nutritional Wheel", added later. Linda Runyon's valuable *From Crabgrass Muffins to Pine Needle Tea* opened a vast fund of knowledge on nature's own foodstuffs, which often can be found close to home, in an environment unsoiled by insecticides, herbicides, or fungicides. Here is the key to the preparation of wild foods without the use of preservatives, invasive chemicals or factory processing.

And now we present a new edition of that book renamed to *The Essential Wild Food Survival Guide,* with all the sustaining data from the first edition. This book will continue to be your valuable companion on the path to healthful living.

The author offers a new way to view the world.

Poem

MY LAWN

As I walked across the grass,
I noticed clover, dandelion, plus
a few plantains.
The thought came to me that
I should graze on all four.
All other modes of feeding
now seem so inefficient,
even wasteful.
When I go out to graze,
I'll carry a bottle of salad dressing,
and sprinkle liberally in front of me,
as I munch my way across the lawn.

By Joe Gang Environmentalist, master of Economics and finances, chemist, small business consultant, Indian Lake, New York.



A typical Eastern lawn smorgasbord

Preface

I am called an environmentarian, or a forager in common terms. I enjoy foraging in fields, woods, and even backyards for the wild plants that make up as much as 30 percent of my daily diet.

The knowledge that led me to this way of life did not come overnight. Walking eight and a half miles to work each day one summer taught me the value of knowing the energy in a single clover leaf; after 15 years of homesteading, (living without any power or electricity in cabins and tents) I learned the tricks of gathering and cooking nature's food. It is quick growing, accessible, nutritious, and free!

Many years of this experience taught me not only how to forage, what to eat, and how to prepare it, but it has also confirmed my decision to stay in touch with my primal rights to live a free life. Now that I'm almost 70 years old, my goal is to share this knowledge with others from a comfortable retirement area.

I have divided this book into four major parts, and I've also included some backup information in a resource section and glossary. Part I describes my environmentarian lifestyle, including how I came to adopt this way of life and how I learned and acquired the wilderness skills that helped me survive. In this section, I also provide information on gathering wild plants as well as how to store them for later use—drying, freezing, and the like.

Because properly identifying wild foods in the field is critical, I have provided a small Field Guide in Part II, which pictures and describes over 50 wild plants, including grasses, herbs, brambles, and trees, plus their nutritional values.

In Part III, I provide more recipes that use wild foods as the major ingredients—tasty and easy-to-prepare soups, salads, casseroles, breads and crackers, sweets, teas, jams & jellies.

In Part IV, I offer tips for growing a wild food garden and for creating "wilderness" walks. I also explain how to grow certain varieties as potted plants, should you live without space for a garden or want to bring your plants indoors. This section also contains my foraging research notes, which tell how I investigated the edibility of wild plants.

Part V discusses Poisonous Look-Alikes and the Glossary defines the terms—mostly medical and botanical—that I use in this book. The book concludes with a listing of useful sources for additional information on wild foods.

It is my hope that this book will help you begin to seek out your own free life, should you wish to do so.

Remember, the process of living free does not happen overnight. In fact, the changes in my lifestyle came very slowly, with gradual adaptation. Try it yourself. If you cannot make it one way, adapt. If you cannot find the food you need, change. If you cannot find shelter, make it. If you are cold, build a fire. If you cannot take a bath, adjust! Such adaptations brought about the changes necessary for me to adopt a free lifestyle.

These changes meant being free of monetary need, not free from constant building, splitting wood, and food seeking. Meeting these needs took up a 24-hour period, with occasional days or hours in between to enjoy the lifestyle. As with any endeavor, you need to enjoy the project. I love projects—they fulfill my day. I always set a goal: move a cord of wood, trim that maple tree, re-screen the windows where the raccoon came in, bathe the mule, clean out the stalls, milk the goats, gather some food for dinner, can the tomatoes.

I plan each day and finish the job when I reached my goals. In between, I feel "on vacation" while I gather food for wild food salads, soups, or casseroles. And, as tired as I am, I have enjoyed every minute of every day.



Linda's Surprise Encounter with a Black Bear

(See page 118)

Acknowledgments

Because of my geographic locations, I use Cherokee and Algonquin language as well as Chippewa throughout the text. For Cherokee translations I have used the CHEROKEE-ENGLISH DICTIONARY, Cherokee Nation of Oklahoma, 1975, Commemorative Edition, edited by William Pulte, Southern Methodist University Press, Dallas, Texas. The dictionary was graciously lent to me by my friend, Joseph Tenderfoot Hill, an Iroquois Elder. I am also privileged to have worked with my friend, a mixed-blood Dijalaga (Cherokee) teacher, Willy Whitefeather.



A Typical Western Smorgasbord

Part I: Environmentarian Lifestyle

Living off the Land

It seems that the Adirondacks Mountains and their way of life have been a part of my life for as long as I can remember. For this, I have deep gratitude for my parents, Ruth and Paul Runyon. While growing up, I worked on the girl's staff of Gavetts Camp on Indian Lake in upstate NY, now called Timberlock. From the time I was ten years old until I was eighteen, I ran between cabins and tents, carrying army blankets, making beds, and serving 100 guests three meals a day. The dishes and campfire sing-along became a nightly routine for three months of every year. Six A.M. lake dips, canoe races, island campfires, and mountain climbing all led the way to my eventual homesteading experiences. Each year, the return to school in North Plainfield, New Jersey became more and more difficult. Smelling a souvenir balsam pillow linked the mountains to the city for me, and even the taste of wintergreen became a symbol of freedom.

My high school years flew by quickly, and soon I had attended and graduated from Monmouth Medical Center in Long Branch, New Jersey, as a registered nurse. Not long after I married, the first of my family arrived: Eric taught me the wonders of motherhood. I don't have to tell anyone how close your firstborn is to your heart. Then within two years, a daughter arrived—Kim, my beautiful daughter, heralded a different bonding in my life. A few years later a second son, Todd, was born. He was to share my entire homesteading experience.



We spent 6 months in a tent.

For many years, all my family thrived in a large housing development in Howell Township, New Jersey. Eventually, my husband Frank and I divorced, and a year or so later I met Ken Heitz. Todd, Ken, and I left New Jersey with an ax, sleeping bags, and great anticipation for the Adirondack wilderness. Kim and Eric remained with their father, but would join us in the summers. Thus my homesteading experience, wild foods, winter survival, and just plain Adirondack life began.

It wasn't long before ideas of an environmentarian lifestyle became a reality. I began to develop the strong bond I feel with Mother Earth. My life was plants, water, shelter, earth, life—"the basics," as someone once said.

Instinct and Ingenuity

One day, in the middle of the winter, I was taken to see a cabin for rent across Lewey Lake. Peering through the cabin's frosty windows, I took less than a minute to shout, "Yes, we'll take it!" An unwinterized cabin, isolated from other summer cabins and framed in black against the mountains, looked like heaven to me. At twenty below, I moved in with Ken and my son Todd, who was age five. We bobsledded the furniture down a moonlit icy path and over twelve-foot snowdrifts to our new home.



Log cabin. Note water hole in frozen lake.

My very first job was to make a pot of coffee. Ken gave me an ax and a pot, and shoveled a path to the frozen lake. Two hours later, time seemed frozen. A two-foot-wide hole grew before me. As I broke through the ice, I felt as if it was ten thousand years ago. Just as folks at the dawn of time had to learn, I, too, soon discovered my ignorance. When the vacuum was released through the newly dug hole, the water rushed up and quickly disappeared below the ice, dragging everything with it. I dove for the coffee pot, only my arm was not long enough to reach deep enough into the water. With tears streaming down my cheeks, I realized my great need for a friend, a tool, and better instincts! Ken provided the first two, and my own instinct led me to my idea for a rope dipper. To this day I can find no words to describe that first cup of coffee!



Water hole tap

Years later, my friend Willie Whitefeather would show me how to gather water in the desert, at the base of a cottonwood tree. Perhaps his Cherokee words, “adline” or “draw liquid,” describe that coffee.

Due to a series of events, I learned to respect the Adirondack winter. The first incident occurred when I opened my eyes after a night’s sleep. My head seemed stuck to the pillow—my hair had frozen to the frost on the cabin wall! Frosted walls are a feature of life in the far north. A layer of ice 1/4 inch thick covers the walls most of the winter, brought about by intense cold, uninsulated buildings and potbelly heat. My side of the bed was against the wall, and that morning I was literally stuck to the wallboards. Warm water might have solved the problem, but one doesn’t always think clearly in a panic! Instead, a haircut solved the problem.

Another morning I awoke and felt a layer of frost on my upper lip and under my nose. I saw my breath as white as smoke, and I knew the stove had gone out during the night. I put my slipper socks over my thermal underwear and hopped to the stove, stirred the coals, heaved in a few pieces of beech, and dove back under the covers. Hearing the crackle of the wood as it flames became my security signal on cold winter mornings.

As I began to learn more about winter, I decided to can my wild foods during the summer for use later in the year. We had a seven-and-a-half-foot insulated refrigerator pit where they would keep well, according to a book I read. I trusted my judgment on this, for I had canned many times in my "city life." So after a long canning season I had 420 jars of campfire-canned foods in my storehouse.

When winter came, we were thrilled to eat our canned foods—cattails, milkweed, lamb's quarters, blueberries, and strawberries. Everything was delicious. Then three weeks of twenty to forty-below zero temperatures began. One night a blizzard snowed us in, but I knew we had plenty of food. The winds howled, the snow swirled, and when morning came, the refrigerator pit had to be dug out. When the roof was uncovered, I opened the pit and climbed down the ladder with my lantern in hand. My eyes blinked in disbelief. Almost every one of the jars had exploded. I was in a complete panic. I grabbed the snow shovel and began to scoop the jars off the shelves to find ones that had just begun to freeze. Alas, there were but a few jars with small cracks or pushed-up lids.

Reconstituted dried leaves, vegetables and flour became our immediate food sources. We even ground bark into flour or brewed it for teas. Somehow, we survived. As I look back, I would say that it was this experience that led me to write this book.

Deer are My Teachers

The first time I looked for food in the woods, I took time to become attuned to the deer's world. I followed deer tracks and saw where and what they had eaten. I found out where they appeared to move quickly, where they moved slowly, and where they stood and relaxed. And when they relaxed, I discovered they were almost always eating.



Well fed fawn

Although not every food eaten by deer is safe for humans, much is.

It became a simple matter to find holes deer had pawed in the snow. These snow diggings yielded wintergreen, ferns, and mosses. I noticed the deer bit off the tips of balsam fir needles. Dried goldenrod tops jutting above the snow line were also nibbled.

Dried-up apples and rosehips also helped to sustain the deer population in the dead of winter. In early spring, the new growth on blackberries, raspberries, willow, and birch added to the deer's diet.



Deer apples

I loved to find an apple tree in winter, naked of apples only as high as the deer can reach on their hind legs. I took the frozen apples from the tops of these small trees back to the cabin, where I boiled, simmered, dried, crushed, and otherwise experimented with them.

Frozen streams also held many secrets. The deer knew where the water dropped over a rock at fantastic speed, deep beneath the snowdrifts. They would break through there for an icy drink, and then steam would rise from these holes because of the difference between water and air temperatures. Todd and I dipped a long, dry stick into the hole to make an instant popsicle. But we discovered that the ice would freeze solid to our tongues—a lesson hard learned.



Waterfall

In the spring, lamb's quarters was a favorite bedding for the deer. I also learned that jewelweed is a poison ivy antidote and as luscious a vegetable as lamb's quarters. Near the camp was a hundred-square-yard patch of jewelweed in which the deer fawned. What a place to give birth! Drops of crystal-clear water hung from the emerald-green stalks of the jewelweed as the deer gorged themselves on this plant. Level weed patches grew uniformly, so I could often tell where the deer have been by the scalloped designs of the weed tops.

The deer were sometimes invisible in this patch. As I crossed the area one day, a buck rose beside me, covered with cascading jewelweed stalks. We stared at each other, not more than three feet apart. For a long moment his antlers had looped over me like branches on a tree. I smelled his breath as he turned and walked away slowly. Through my eye contact, I apologized for my intrusion and swore I would call out loud before entering the area in the future.

Here's Mud in Your Eye

The homesteader in the Adirondacks needs to utilize both modern and ancient methods of survival when it comes to the insect world. For example, insects are particularly fierce during the short summer in the far north. Early in the day, black flies were biting even the corners of my eyes by 9:00 A.M. By noon, my upper arms were filled with itching lumps, the back of my neck was bleeding from my scratching, and I had swallowed at least four of the beasts.

I had literally used bottles of insect repellent, but even the heavy-duty spray from the Grand Union in Indian Lake was not working. The black fly problem was so great that all of us were sick from the toxins in our body from both the flies and the chemicals.

One time I came home to a prostrate husband, bloated and swollen from at least 400 black fly bites and sporting a temperature of over 103 degrees. A trip to the town doctor was in order. Since that time, we discovered the use of smudge pots. In fact, smudges soon became a skill we excelled in! Smoke wafted from our campfires, pails, upside down wastepaper baskets—you name it. The black flies were kept at bay.

Building a Smudge Pot

In the neighborhood dump area we were able to remove lidded tin cans, the 20-gallon type. Manufacturers distribute products in them. In the city I would ask local garages for oil cans, and restaurants for old lard cans. If all else fails, use an old wastepaper basket and make a thin lid to fit.

The can must be washed thoroughly and pre-burned for safety. Build a fire using paper kindling. Cover and wait until this burns out. The "clean" smudge pot needs a door in the base. Cutting would be simple using modern tools, but in the "homestead times" we used a nail and a rock. We placed holes side by side, much like you might open a can without a can opener. The door to a 20-gallon container might be 6 by 8 inches or even smaller. Don't cut the fourth side of the rectangle, and bend out the door. Smudge cans last for a season or more according to how much use the "hinge" side gets.



Smudge pot. Metal container with lid, rolls of moss.

Be sure the lid fits if you use a makeshift wastepaper basket or thin pail. Control your airflow by leaving the lid off, opening your door a couple of inches, and experiment with keeping a fire going. When you have coals, place a moist material over them and stand back. Your smudge is smudging. After a while, from the size of smoke, you can tell when to add more wood, open door and lid, or add more smudge material. When you go away, simply put the lid on and shut the door.

Smudge Materials

- Grass clippings (be sure you don't use toxic plants like poison ivy, oleanders or chemical sprayed lawn clippings).
- Moss- any kind works well.
- Wet Sawdust.
- Other material, such as newspapers soaked with water, wrung out and tightly waded up. the tighter the wad, the longer the smudge.

The Last Hunt

The transition from meat eater to vegetarian was a difficult one. Nevertheless, it seemed the best way to follow through on an environmentarian lifestyle.

One day my son Todd accompanied me hunting, the first time for him. I know now that hunting was probably a mistake, but I hadn't suspected the eight-year-old did not know where his meat came from. I performed my usual stone-throwing act, and shot the first rabbit that ran out from behind the lumber pile. Unfortunately, the rabbit rolled over, righted himself, and to my horror continued to run straight for us. I took careful aim and shot it just a few yards from where we stood. The rabbit fell, twitched, and then was still. Todd screamed, horrified at me. "Why did you do that?"

I heard myself saying, "We eat them for dinner. That's why we grow them."

He stood defiant and drew himself up into a proud, straight position and said vehemently, "Well, I don't have to eat them again, and I won't—ever!" Todd walked off in a rage. He meant every word he said, and that was the last kill I made for food from the mammal world. As it says in Genesis 1:29, "Behold, I have given you every herb bearing seed, which is upon the face of all the earth, and every tree, in which is the fruit of a tree yielding seed; to you it shall be for meat."

My theory now is that if we could see the reality of taking life, we would all be vegetarians. Happily, many youngsters are being introduced to this thought by activists or through the animal rights movement. This may well change people's eating habits in the future.

Foraging on the Way Home from Work

Although we were still learning to survive on our own, we needed to continue earning money for a while. The eight-and-a-half-mile stretch of Cedar River Road became a pathway for me to a job at the Cedar River House: a famous hotel often visited by dignitaries. The hotel needed housekeepers, so to earn extra money I worked there one challenging summer. The hotel no longer exists, but the trip to and from work is a treasured memory.

Sometimes I asked for a ride, but usually I welcomed the long trek home in order to sample the food along the way. I would consume large amounts of red clover, crabapples, and dandelions on these trips. Indeed, endurance and energy were sustained by these wild foods.

The deer became accustomed to my ways; and as I passed by them, they made no more than a faster twitch of their tails to acknowledge my presence.

I once saw a large bear along the road eating crabapples. He raked the apples from the branches of the tree with ease, then dropped down on all fours and pulled them up into his mouth. I watched him from a distance of a hundred yards, feeling very exposed. I waited more than twenty minutes for him to get his fill before I walked on. There was no need to disturb the feeding animal when I could avoid doing so, even though my family was waiting for their dinner.

Fire Making

I became an expert fire maker through daily repetition. We gathered kindling from around the area and found twigs for tinder underneath the branches of a balsam or pine tree. Birch bark became a favorite fire starter. Even through torrential rains and high winds, the birch bark always burned steadily.

There are many types of outdoor fires. My favorite fire pit was dug where there were no roots or rocks. It was located near our old homestead, with a rain barrel within a few feet in case of emergency. I used a shovel to sprinkle dirt over the fire when I had to leave it quickly.



The shanty, fire pit & wood pile.

After a few months, the dirt had been dug out and reused so many times that the ashes and dirt were a fine powder. Afraid of breathing the lye of hardwood ashes and dirt, I began to use a large piece of sheet metal, throwing it over the fire quickly. It wasn't long before I discovered this metal was a stove like the most modern type. I began to make roaring fires with the sheet metal on top, and I would simmer, boil, and fry all on one safe surface. In pouring rain or blizzards this method worked exceptionally well.

I found that a piece of sheet metal also served as a cover for a banked hardwood fire, and the coals would last until morning. If we went on a long foraging trip, the sheet metal cover helped prevent our coming back to a cold fire pit at dinnertime.

A fire pit holds a dug-out below-ground fire. A fire ring is an above ground safety rock ring around a fire area.

After a deep snowfall, we dug out the fire pit to prepare our meal and cooked in the middle of a snowstorm. During spring and early summer, we would cover ourselves with mud while cooking to protect ourselves from insects.



Fire ring and cooking.
Open-end fire, with logs that are rolled over to control heat level.

Scanning the coals using my hands, I could determine which areas of the fire would be used for cooking each dish. To control the boiling level I added twigs or hardwood to the fire. Since tending the fire and stirring the food are a constant chore when using an open fire, the children were often called into action. On Thanksgiving they spent eight hours turning a well-stuffed turkey over our fire pit.

My favorite type of fire ring was open on one end. I pushed the long logs in as I needed them; putting a new log on the fire means fresh fire or flames in the surrounding area. I made hotter areas for simmering or boiling by adding new twigs or fresh logs. The hot rocks on the sides were used for toast or baking cakes. I greased the rock for best results as I would a pan.

To cook on our campfire, I used a spit for long-term roasting, coals for baking, and hot rocks for making toast. I baked main meals in coals (casseroles). Hot rocks and back burner held breads, which were unleavened, pita-like cakes throughout the wilderness years. Toast in particular tasted fantastic when done on the open fire. I would turn the bread when I saw the tiny coils of smoke appear at the edges, and I learned to keep the bread to front edge of the grill to avoid burning the hair on my arms.

In the dead of winter I especially enjoyed cooking over the open fire. There were times when my back was thick with snow, but I was oblivious to discomfort. I would squat in front of the fire and relish preparing my family's meal. The personal challenges of foraging for and cooking our wild foods over our campfire gave us all a special appreciation of our daily meals.

Swamping

Our camp was bounded on the east by a vast cattail swamp and so the food became a mainstay.

"Swamping" brings out fantastic feelings. The marsh odors and insect life opens my senses and I feel animal-like. I made the mistake of wearing sneakers the first time I went out. "A little mud won't hurt me," I thought. Unfortunately, swamps and marshes have a tendency to suck the sneakers from your feet. As you step up, your shoe stays behind. And to retrieve it from the muck is no small feat. Marsh mud is thick, gooey, and smelly at the least.

Detractions aside, a number of edible plants can be found in marshes. All the plants described in this guide are fresh water plants. Mint and arrowhead are prolific, while meadowsweet and black birch also grow among the cattails.

When you go swamping, wipe a thin layer of mud on your face (temples to cheeks).



Swamp Grasses.

In fact, smear mud on as much skin surface as you can. This gives you a neutral marsh odor and bugs won't pay as much attention to you.

I would lay boards down on the marsh one in front of the other as a stabilizer. When I was ready to move on, I would pick up the first board and lay it down again in front of the second. You get to keep your shoes this way.



Using the stream to wash cattails

Water Hauling

Water is a basic need for all of us, but when you live in the city, you take it for granted. Our transition from city water to wilderness water was a monumental adjustment.

Ken did most of the water hauling, but there were many days when I shared the burden, carrying the five-gallon container on my back. The feeling was one of extreme satisfaction—filling, hefting, and toting the container to camp to supply our water needs for several days. I would use the drinking water one day and



The Wash Rock



A wash ring

then use the leftover water for cooking, washing, and preparing food. We also placed rain barrels in strategic places and washed ourselves with biodegradable soap when saponin (lather-producing) plants weren't available. At the river, everyone had his or her favorite spot to bathe in privacy. It was easiest to wash our clothes there, too.

Icicles

Under our uninsulated roof were the largest icicles I have ever seen. We used them for water. If we dropped one indoors, we squealed with delight as we chased the broken sections all around the linoleum floor of the camp kitchen. The average icicle was about four to six feet long and sometimes 12" or more in diameter. I could not leave them alone.

My son Todd helped me with this chore. Ice and snow melt at a great rate of speed in a bucket that is set into the top hole of the wood stove. A giant icicle might make four pails of water when melted. It was a true gift to the person washing clothes, dishes, wild foods or themselves.



Icicles

Reverance for the Wilds

The following poem was given to me by my mother, Ruth. It expresses my feelings for my time spent in the Adirondack Mountains. Its author is unknown, but the poem is from the early nineteenth century, reprinted from *Nirvana Lodge Log Book*, Indian Lake, New York.

A Camper's Prayer

God of the Hills, grant me Thy strength
to go back to the cities without faltering.
Strength to do my daily tasks
without tiring and with enthusiasm.
Strength to help my neighbor,
who has no hills to remember.
God of the Lake, grant me thy peace,
and Thy restfulness.
Peace to bring into the world of hurry and confusion.
Restfulness to carry to the tired ones,
whom I shall meet every day.
Content to do small things from littleness,
Self control for the unexpected emergency
and patience for the wearisome tasks.
With deep depths within my soul
to bear with me through crowded plans.
The brush of the night time where the pine trees
are dark against the sky.
The humbleness of the hills
who in their rightness know it now,
the laughter of the sunny days
to brighten the cheerless spots in a long winter.
Fill me with the breadth and depth and
height of "Thy Wilderness."
Thou has taught me by every thought
and word and deed.



The Simple Life

The following was written by Mrs. Barbara Jennings of Long Lake, New York, and is included here with permission.

Living amid the splendor and protection of the mountains, the people lead comparatively quiet lives. From year to year, very few changes take place, and everyone becomes accustomed to a routine. Consequently, the members of these small communities are independent and fixed in their ways. They keep well informed through television and newspapers, but because of the distance to be traveled, they don't often venture away from the local scene. The tourists are accepted as a necessary intrusion and the tourist season brings enough turmoil to last the entire year. Every man prefers to live according to his own pace, no one setting a very fast one. Those who maintain a carefree existence somehow seem to manage nearly as well as those who do work steadily and live moderately. Many prefer to have less, rather than submit to the shackles of a time clock.

On the occasions when we leave our towns, we are startled into a realization of how naive and backward we must seem. We may have read that skirts are shorter this season, but complete shock is in store when we arrive in the big city and discover how really short or long they are.

A friend and I felt quite at ease and well dressed when we arrived in Utica for a shopping trip, but a shoe salesman soon squelched me as he removed one of my best shoes and remarked, "Say, these are real old-timers, aren't they?" I spent the rest of the day trying to get lost in the crowds.

Even the ever-present desire of women to get out and explore the bargains and varieties offered in the large department stores soon diminish once they are there. They become entangled in the confusion of clutching hands at the sales counters and in the hopeless attempts to attract the attention of tired and bored sales ladies. Even the latest methods of self-service result only in standing in long lines waiting to be checked out. More often than not they return home weary and empty handed, resolving to remain a slave to the mail order catalogs and corner grocer rather than submit to such indignities.

Periodic trips to the bustling city are sufficient for anyone claiming to be a mountaineer by birth or by choice. They are ready to return to their towns where the roads may wind endlessly, but stoplights and traffic cops are nonexistent. No one waits in a booth ready to extract a toll. Even in this highly complicated and sophisticated age, the values of a simple life cannot be denied.



Left: Violets Right: Cattails



Foreground: lambs quarters

An Introduction to Edible Wild Plants

My life has been spent in two geographically opposite environments, giving rise to an environmentarian diet mixing woods & wilderness with Arizona desert. This experience is reflected here in the wild plants I choose to write about and the uses I've made of nature's bounty.

In many ways, the history of the United States documents people's efforts to survive. This is especially true of Native Americans, who spent long years establishing roots in this soil. In the Eastern wilderness, the Iroquois were bark eaters. Intense cold gave rise to the habit of eating fern roots, balsam needles, and pine bark, and of chewing black and white birch pith. Native Americans invented ways to dig roots from under the snow, such as for ferns and wintergreen.

In the West, specifically in what today is southern and central Arizona, the Hohokam were the nation's prehistoric people. From 300 BC to 1450 AD, they were hunters and gatherers. Wild foods were their diet, including cholla, lamb's quarters, amaranth, purslane, and saguaro.


TOP VIEW
HOPI
PHOENIX
YUMA
THE TURQUOISE TRIANGLE
1½ MILES ABOVE SEA LEVEL
Hopi
Pine
FLAGSTAFF
PINYON PINE
JUNIPER
YUCCA
YUCCA
AGAVE
PRICKLY PEAR
SAGUARO
HEDGEHOG
YUCCA
JUNIPER
PRICKLY PEAR
PALO VERDE
COTTONWOOD
MESQUITE
SAGUARO
PRICKLY PEAR
CHOLLA
JOJOBA
CHAPPARALL
DESERT WILLOW
EL CENTRO
CALIFORNIA
BELOW SEA LEVEL
YUMA
JOJOBA
PRICKLY PEAR
PHOENIX
TUCSON
ARIZONA
COLORADO RIVER
MEXICO
SIDE VIEW
Willy Whitefeather
please don't litter

Cross section of Arizona Desert by Willie Whitefeather

From these people came the desert Pimas, Navajos, and Hopis of the Southwest. Even today wild foods are a large part of the Papago Indian's diet, which includes milkweed, bulrushes, cattails, phragmities, amaranth, sumac, asters, thistle, sunflower, wild lettuce, chickweed, mustard, shepherd's purse, mint, plantain, sheep sorrel, purslane, willow, and rose (Hodgson 1982).

Just as Native Americans followed the patterns set by their environment, I found myself doing the things that nature made most obvious for me. I also studied the ways of people who had come before me.

Some specific foraging heritages I learned about are:

- Abanakee (People of the Bark)-eaters of birch, balsam, and willow
- Algonquin (People of the Coast)-eaters of amaranth and lamb's quarters
- Blackfoot, Chippewa (People of Canada)-rice eaters
- Cayuga (People at the Landing)-vegetable eaters
- Oneida (People of the Standing Rock)-vegetable eaters
- Objibwa (People above the Climate Line)-rice eaters
- Iroquois, Eastern Mohawk (People of the Flint & Keepers of the Eastern Door)-bark eaters
- West Seneca (People of the Great Hill & Keepers of the Central Fire)-bark and vegetable eaters

The point is, no matter where you live, you are going to draw upon the heritage of those who went before you. We can learn an immense amount from Native Americans. Climate, terrain, existing plant life, and economical use were all considerations of native peoples. The same plant might be used quite differently in different regions. To make use of the wild foods in your area, study your local Native American heritage. You'll find the information in local museums and libraries. Also, native teachers are often available, reached via earth gatherings, through organizations, at powwows, and such.

A Basic Food Source

Although some wild foods are best utilized in one particular way, such as steeped for tea, others have multiple uses and applications. In fact, it sometimes seems as if a single plant can meet just about all our needs. Such is the case with clover. We can eat it fresh or raw, or we can cook it, dry it, freeze it, or grind it into flour and bake it.



Clover: raw, cooked, dried, frozen or ground into flower.

The same can be said for amaranth, aster, chickweed, dandelion, dock (with some restrictions), lamb’s quarters, mallow, nettles, plantain, purslane, shepherd’s purse (with some restrictions), sow thistle, tumbleweed, and wild lettuce.



Gathering

The chart on the following pages delineates the uses of the wild foods discussed in this book.

Properties Of Wild Edible Foods

	Type			Origin		Harvest Time	Edible Parts							Storage		Uses				Field Guide Page
	Annual	Biennial	Perennial	Native to N.A.	Naturalized		Leaves/needles	Stems	Buds	Flowers/Catkins	Fruit	Seeds	Roots	Freezes	Dries	Vegetable/Fruit	Herb	Tea	Flour	
Aloe Vera					❂	Spring/Summer	❂		❂	❂				❂		❂	❂	❂		52
Amaranth	❂			❂		Summer	❂	❂		❂		❂		❂	❂	❂			❂	54
Arrowhead			❂	❂		Fall							❂	❂	❂	❂				55
Aster			❂	❂		Fall	❂	❂	❂	❂		❂		❂	❂	❂		❂	❂	57
Balsam Fir				❂		Year-round	❂	❂		❂		❂	❂		❂	❂	❂	❂	❂	58
Birch				❂		Year-round		❂	❂	❂		❂			❂	❂	❂	❂	❂	60
Blackberry			❂	❂		Year-round		❂		❂	❂	❂		❂	❂	❂		❂		62
Blueberry			❂	❂		Summer	❂	❂			❂	❂		❂	❂	❂		❂		64
Bulrush			❂	❂		Summer/Fall		❂	❂	❂		❂			❂	❂			❂	65
Burdock		❂			❂	Year-round	❂	❂			❂	❂	❂	❂	❂	❂	❂	❂	❂	67
Cattail			❂	❂		Year-round	❂	❂	❂	❂		❂	❂	❂		❂		❂	❂	69
Chamomile	❂			❂	❂	Spring/Summer	❂	❂	❂	❂		❂		❂	❂	❂	❂	❂		72
Chickweed	❂			❂	❂	Year-round	❂	❂	❂	❂		❂		❂	❂	❂	❂	❂		73
Chicory			❂		❂	Spring	❂	❂		❂		❂	❂	❂	❂	❂	❂	❂		75
Cholla			❂	❂		May			❂	❂	❂	❂			❂	❂				76
Clover			❂		❂	Year-round	❂	❂	❂	❂		❂	❂	❂	❂	❂	❂	❂	❂	78
Crabgrass			❂		❂	Year-round	❂	❂	❂	❂		❂			❂			❂	❂	80
Daisy			❂		❂	Year-round	❂	❂		❂				❂	❂	❂		❂	❂	81
Dandelion			❂		❂	Year-round	❂		❂	❂		❂	❂	❂	❂	❂	❂	❂	❂	83
Dock			❂		❂	Spring/Fall	❂	❂	❂	❂		❂	❂	❂	❂		❂	❂	❂	85
Evening Primrose		❂		❂		Summer/Fall			❂	❂		❂	❂	❂	❂	❂	❂			86
Filarie		❂				Winter/Spring	❂	❂					❂	❂	❂	❂		❂		87
Fireweed			❂	❂		Spring/Summer	❂	❂	❂	❂		❂		❂	❂		❂	❂		89
Goldenrod			❂	❂		Spring/Sum/Fall	❂	❂	❂	❂		❂	❂		❂		❂	❂		90
Grape			❂	❂		Fall	❂	❂		❂	❂	❂		❂	❂	❂				92

Lamb's Quarters	✪			✪		Summer/Fall	✪	✪	✪	✪		✪		✪	✪	✪			✪	93
Malva			✪	✪		Winter/Spring	✪	✪	✪	✪		✪	✪	✪	✪	✪	✪	✪	✪	95
Maple			✪	✪		Summer	✪	✪	✪	✪		✪		✪	✪			✪	✪	97
Meadowsweet			✪	✪		Summer	✪	✪	✪	✪		✪			✪		✪	✪		98
Milk Thistle		✪		✪		Spring/Summer	✪	✪		✪	✪	✪		✪	✪	✪	✪	✪	✪	99
Milkweed			✪	✪		Spring/Sum/Fall	✪	✪	✪	✪		✪		✪	✪	✪				101
Mint			✪	✪		Spring/Fall	✪	✪	✪	✪		✪	✪	✪	✪		✪	✪		103
Mullein		✪			✪	Spring/Fall	✪	✪	✪	✪		✪	✪		✪		✪	✪		105
Mustard	✪				✪	Spring	✪		✪	✪		✪		✪	✪	✪	✪			107
Nettles			✪		✪	Spring/Fall	✪	✪		✪		✪		✪	✪	✪	✪	✪		108
Phragmities			✪	✪		Summer		✪		✪		✪	✪		✪	✪			✪	109
Pine						Year-round	✪	✪	✪	✪	✪	✪	✪		✪			✪		110
Plantain			✪	✪		Year-round	✪	✪				✪	✪	✪	✪	✪	✪	✪		111
Prickly Pear			✪			Summer	✪		✪	✪	✪	✪		✪	✪	✪		✪		113
Purslane	✪				✪	Summer	✪	✪	✪	✪		✪	✪	✪	✪	✪			✪	115
Queen Anne's Lace		✪			✪	Summer	✪	✪	✪	✪		✪	✪	✪	✪	✪	✪	✪		116
Raspberry			✪	✪	✪	Summer	✪	✪	✪	✪	✪	✪		✪	✪	✪	✪	✪		117
Rose			✪	✪	✪	Spring/Fall	✪	✪	✪	✪	✪	✪		✪	✪	✪	✪	✪		118
Saguaro				✪		Summer			✪	✪	✪	✪		✪	✪	✪				120
Sheep (Garden) Sorrel	✪					Spring/Summer	✪	✪	✪	✪		✪	✪	✪	✪	✪	✪	✪		121
Shepherd's Purse	✪				✪	Summer	✪	✪	✪	✪		✪	✪	✪	✪	✪	✪			122
Sow Thistle	✪				✪	Winter/Spring	✪	✪	✪	✪		✪	✪	✪	✪	✪			✪	124
Strawberry			✪	✪		Spring	✪	✪	✪	✪	✪	✪	✪	✪	✪	✪	✪	✪	✪	125
Sumac			✪	✪		Summer				✪	✪	✪			✪			✪		126
Sunflower	✪			✪		Spring/Summer		✪		✪		✪			✪			✪		127
Thistle		✪		✪		Spring/Fall	✪			✪		✪	✪	✪	✪	✪		✪		128
Thyme			✪		✪	Summer/Fall	✪		✪	✪		✪		✪	✪		✪	✪		129
Tumbleweed	✪				✪	Spring/Summer	✪	✪	✪	✪		✪		✪	✪	✪		✪	✪	131
Violet	✪					Spring/Summer	✪	✪	✪	✪		✪	✪	✪	✪		✪	✪		132
Wild Lettuce			✪	✪		Spring/Summer	✪	✪	✪	✪		✪		✪	✪	✪	✪	✪		133
Willow				✪		Year-round	✪	✪	✪	✪		✪			✪		✪	✪	✪	134
Wintergreen			✪	✪		Spring/Summer	✪	✪		✪		✪			✪			✪		135
Wood Sorrel			✪		✪	Spring/Fall	✪	✪	✪	✪		✪		✪	✪	✪				137
Yarrow			✪		✪	Spring/Fall	✪	✪	✪	✪		✪		✪	✪		✪	✪		138

Picking Wild Foods

State and local regulations on picking wild plants vary, but mostly there are restrictions against taking plants or plant parts on public land. You should always check with park officials before foraging anywhere but on your own land.

In gathering plants, pick only on lands off non-posted access roads or from fields with owner's permission. Move from place to place, picking sparingly and only when there is several of any one plant. In addition: due to nature's changes and people's advances, many plants are now endangered. Even though this guide's plants are not endangered now, they may be in the future. Check your Local State library or Department of Agriculture for updates. Do not pick any endangered plants on private property.

FORAGING RULES

1. ***DO NOT*** collect plants closer than 200 feet from a road.
2. ***NEVER*** collect from areas sprayed with herbicides, pesticides, or other chemicals.
3. ***ALWAYS*** be familiar with all dangerous plants in the area.
4. ***POSITIVELY IDENTIFY*** all plants you intend to use for food or medicine. Check against three good field references with excellent illustrations.

If you are trying a plant for the first time, after checking your field guides, do the following:

1. Snip a piece of the plant and roll between your fingers and sniff. Discard if objectionable. If you like the smell, then rub the tiny piece on your GUMS, above your teeth.
2. Wait twenty minutes.
3. CHECK For burning, nausea, stinging, itching (all allergy results). Poisonous plants USUALLY produce one or more of these symptoms.
4. If no untoward reaction results, take another tiny bit of the plant and make a weak tea. (Place piece in teacup, pour boiling water over, cover, and steep for 10 minutes. Ingest a small amount.)

5. Wait another twenty minutes! Check for signs of irritation. If none, then reheat the tea and sip slowly.
6. Keep all samples away from children and pets. Keep edibles separate from samples to be identified—poisons will give their bad qualities to food through contamination. Bag foods, poisons, and samples separately.
7. Be aware that heating or boiling does not always destroy toxicity.

In general, it's a good idea to store all seeds and bulbs away from children and pets. Tape down the lids or use a locked closet for any questionable foods so children cannot reach them. Likewise, teach children to keep all plants away from their mouths. Do not let children chew on or suck nectar from unknown plants.

Avoid smoke from burning plants. Smoke may irritate the eyes or cause allergic reactions. Also, be aware of your neighbor's habits with regard to chemicals, pesticides, and herbicides. Ask questions! Call and report any chemical spills, contaminated areas, or other situations that may negatively affect your gathering safety.

Growing up with Wild Foods

"As a child, I always mashed and ate wild plants. This worried my Daddy. He began to teach us what not to eat and what good plants to enjoy. He showed us how to pick flowers from the top of ocotillo plants while on horseback. We sucked the honey from the bottom of each flower, much as Easterners used honeysuckle. The ocotillo flowers are just delicious. Our parents ran a cow ranch in Mohave County for fifty years, and we picked our ocotillo flowers often from horseback. A lovely life!"—Danielle Stephens, Kingman, Arizona.

Gathering

Decide which plant you will harvest on a particular day and take along a basket, a bag, or a sheet. Burlap is excellent if you are going to dry the plants, but biodegradable plastic bags generally are better for gathering because burlap gets heavy when wet.

Do any aquatic plant gathering in the morning, as the cool air and water will keep your collection fresher. Plastic bags are waterproof and lightweight, but remember to use biodegradable bags, and reuse them as often as possible. (Do not leave wild food in the sun, especially inside a plastic bag, because the food will wilt quickly; I have spoiled hundreds of milkweed buds this way!)

A flat, round tray also works well for gathering in tall grass, especially when gathering fireweed. It can be great fun wading through a field of these magenta flowers, snapping off the tips and tossing them onto a tray held above your head.

For most gathering, I use a clean sheet and a two-foot section of string. A small amount of wild food will fit in your basket or bag, while a winter's supply will fill a clean sheet. When the sheet is folded up and tied with a string, it can be hung up easily in a warm, airy spot to dry. The sheet method of collection also allows the bugs to crawl out of the food and provides an easy view of how much you have gathered.

When gathering wild foods, remember that certain plants snap off easily while others are better cut cleanly with a knife or scissors. If the plant gives you any resistance to a snap, give way to a tool immediately. A clean cut will help the plant recover quicker and you'll have greater gathering speed and accuracy.

Cutting a batch of leaves on the stem is simple when you hold the stem with one hand and with the other cut the stem with a sharp knife. When I gather with a penknife or scissors, I slide my fingers into the middle of the clump and go for inside growth. The plant then folds up around what I took and rejuvenates nicely. Goldenrod, asters, yarrow, and Queen Anne's lace work especially well this way.

If you're using the sheet method, you may want to strip the leaves off the stems while gathering for ease in drying. At this time you can also separate your favorite flowers for tea. Don't forget to save the stems, though, as they can be valuable, especially mint, spearmint, yarrow, and thyme.

When you've gathered enough, pull the corners of the sheet together, and use the twine to tie it closed. I often hang the bundle from a tree or other obvious spot and retrieve it later. This method also helps mark the trail. (I use a cactus in the desert since trees are sparse.)



A Food Tree



Saguaro as a food tree

Tie enough stems together to make a bunch, but be sure the leaves aren't packed too tight, lest you prevent air penetration. As a rule, when you swish the bundle in the air you should "feel" and hear the air moving through it.

Waists and belt loops also work well for carrying bundles of plants. You can also use burdock leaves or mullein to roll up several smaller items. Roll up nuts inside large leaves and put them in your pockets as you go. Fruits, twigs, nuts and flowers all wrap well in large leaves.



Leaf Bundles: A) White birch bark waterproof container, B) A bark tray, C) Hollow bark, D) Burdock leaf wrapping for small foods, E) Mullein leaf wrapping for small objects, F) Kit of white birch strings, and G) Bundle of foods, grasses or twigs.

In summary, here is a list of tools I generally use for gathering:
- A sheet
- Scissors
- 2-foot length of string
- Biodegradable plastic bags
- Penknife and Bowie knife
- Gloves
- Snake stick with fluorescent handle (in the West)
- Hand axe (in the East)
- Burlap bag

Washing the Foods

Certain plants attract aphids, ants, and "no-see-ums," as well as collect the usual dirt and dust. In the Adirondacks a nearby stream is always available, so washing large quantities of plants is always easy, no matter how dirty they are. But in Arizona, apartment living demands the use of a bathtub—it's the easiest way to wash a large quantity of food. Of course, it's always best to use a hose first, especially for roots, eliminating most of the soil before taking them into the house.

When cleaning small plants or bunches of leaves that aren't too dirty, it's a good idea to use a drainable container such as a colander. Some containers can be made to drain by poking holes in the bottom. Some plants may need more soaking, however, and may even need to soak overnight. In this case, soak in 1/4 cup vinegar to a tubful of water. In any case, it's best not to put too many types of plants in the same tub, since you may have difficulty separating them later.

Finally, here's a quick tip that will make it easier to clean your tub and prevent a clogged drain: Before filling the tub, place a piece of cheesecloth over a rubber stopper and use it as the plug. When you're ready to drain the tub, pull the stopper, but hold the cheesecloth in place. When the water is drained, just shake out the cheesecloth and save it for the next time!

Edible Wild Flowers

The following are common wild flowers I utilize often.

Birch catkins—unopened catkins eaten raw or brewed as tea. Dried or frozen for storage. Also cooked.

Blue Asters—All wild asters and flower buds may be eaten raw, cooked or dried and ground for flour.

Cattails—Flowers and flower buds are eaten raw, cooked, or dried and ground for flour. Used in tea.

Chamomile—White flowers and flower buds may be eaten raw, cooked, steeped for tea, or dried for storage.

Clover, Red or White—Flowers and flower buds are eaten raw, cooked, dried for tea, & frozen in ice cubes.

Dandelions—Whole flower and flower buds may be eaten raw in salads, stir-fried in garlic, frozen for use later. Used in tea.

Fireweed—Whole flower and flower buds are eaten raw, cooked, or dried for storage.

Goldenrod—Whole flower and flower buds are eaten raw as a tonic, and dried for tea. Frozen for storage; used in tea.

Maple—Flower buds are eaten raw, cooked, or dried for tea and storage. Can also be frozen.

Meadowsweet—Flowers and buds are eaten raw, cooked, or dried for a sugar substitute or tea.

Milkweed—Eastern flower is cooked as a vegetable, or frozen or dried for storage. Western varieties are caustic from desert sand.

Mint—Flowers and flower buds are eaten raw or cooked, or dried for storage; frozen in ice cubes; used in tea.

Mustard—Flowers and flower buds vary in intensity; may be cooked or eaten raw, and frozen.

Pine—Pine flowers or young cones are called catkins and are eaten raw, cooked, and dried for tea; also frozen.

Prickly Pear—Flowers are eaten raw in salads, and cooked; frozen for storage.

Queen Anne’s Lace—Flowers and buds are eaten raw, cooked, frozen, and dried for storage.

Roses—Flowers and flower buds are eaten raw in salads, cooked, also frozen in cubes for storage.

Thyme—Flowers and buds are eaten raw, cooked, or dried for tea; also frozen.

Violets—Flowers and flower buds are eaten raw in salads, cooked, and dried or frozen for storage and tea.

Wintercress—Flowers and buds are eaten raw, cooked, and dried.

For information sections on drying and freezing flowers, see pages 33, 37, 39, 42 and 43 respectively.



Wild Popsicles

Edible Roots

During my homesteading days I became interested in the many uses of plant roots. A particular experience gave me a lasting respect for the roots of wild plants.

In mid-winter, the ground was frozen and a snow-encrusted world was our environment. My son Todd had developed a bad cough. Soon Todd's condition worsened and he was coughing steadily. He needed more than the usual remedy of pine tea and honey. I knew about the antihistamine properties of mullein root. I could see the tall brown spikes of mullein poking above the snow like sentries standing beyond our camp. But the temperature was 20 degrees below zero and the ground was frozen solid.

The woodstove was filled with hardwood coals. I collected a pail of coals, put on my snowshoes, and went out to make a path to the closest mullein plant I could find. I scraped away as much snow as I could from around the plant and poured the hot coals on the icy crust at its base. (A very heavy pail is necessary for this, as coals will burn through a thin pail very quickly.) Sizzle, sizzle. The coals sunk quickly into the crusty ice. I returned to the house and fetched more coals. Pausing a few minutes between pailfuls, I scraped away each layer of slush until I reached mud. I placed a circle of dry wood around the base of the plant and made a large campfire inside the circle. With the wood concentrating the heat at the plant's base, the fire became hot in no time. I used birch bark to keep it very hot, adding a large sheet or two at a time. We were lucky to live next to a sawmill that cut white birch logs, and sheets of bark were plentiful. Never cut birch strips off a live tree.

After a long, cold hour, I scraped the remaining coals out from the circle and easily dug out a foot-long mullein root. It was partly decomposed, but there was more than enough root to brew a concentrated tea for Todd. He drank 2 tablespoons every hour, and his cough was calmed. Mullein root tea is an effective expectorant, helping Todd discharge mucus from his throat and bronchial tubes. This wintertime experience gave me untold security, knowing that mullein roots were out there if we needed them for medicine or food. This “underground farm” took on new meaning: it was available to us even through several feet of snow and in 20 below temperature.

The following edible roots are ones I use:
Amaranth—Used as a vegetable; dried & ground for flour.
Arrowhead—Tuber used as potatoes.
Balsam fir—Used for medicinal purposes (sedative), & tonic.
Burdock—Used as a vegetable, dried and ground for flour.
Cattail—Dried and ground for flour.
Chicory—Used as a coffee substitute.
Dandelion—Used as a vegetable and tonic.
Evening Primrose—Used as a vegetable flour.
Fireweed—Used as a medicine and a food.
Goldenrod—Used for a blood tonic tea.
Malva neglecta—Used as vegetable; dried & ground for flour.
Pine—Used for tonic and stimulant as well as rope making.
Plantain—Used for vegetable and as an antiseptic
Purslane—Used as a vegetable; dried and ground for flour.
Queen Anne’s Lace—Used as a vegetable and dried food.
Strawberry—Used as a vegetable, a medicine and as an appetite stimulant.
Wild lettuce—Used as a vegetable.

Plant roots are greatly under utilized, and their magnificent properties barely understood. For example, many are aromatics.

Roses, for instance, have an aromatic root that can be reused many times, until the scent and color are gone. Scrub off any mold or black spots before use. Mullein root can be reused many times for tea, as can mint roots.

Clip newly gathered roots from the plant and scrub with a toothbrush. Then use fresh, or dry and store.

To use fresh, peel the root as you would a carrot or parsnip and slice crosswise or lengthwise. To dry the roots, place in a paper bag and label carefully with the name of the plant and the year you collected. Hang to dry. Reconstitute in boiling water or place in a grinder and grind to flour.



Harvesting roots: peel & slice either crosswise or lengthwise.



Storing roots: A) hang on wall B) dry & store in paper bag C) store dried slices in glass jars

Edible Parts of Trees and Shrubs

Many trees and shrubs have edible parts and can be a major source of food in the wilderness. The chemical content, vitamins and minerals are found in leaves and flowers, but in concentrated form in shrubs and tree bark. Inner bark, the layer underneath bark, is the “meat” of a tree. Twigs have both bark and inner bark. For example, pine or balsam fir bark strips, cut 1/3 inch to 1 inch wide, to fill a 2-quart glass container will yield a winter’s supply of tea. One small shrub, such as a rose bush, can yield a winter’s supply of tea.

In calculating your yield, figure one twig, 6 to 8 inches long, yields a moderately strong cup of tea. This tea could be used as a soup base. To prepare for cooking or tea, break the twig several times to release the flavor and steep or boil as intended. To store twigs and stems, place in dark paper bag. Or, place in glass jar and cap tightly. Wrap with opaque paper or foil to keep it dark. And, of course, label with the collection date.

The following diagram shows two different methods of peeling bark. Method A shows types of plants which will allow big pieces to be peeled. Method B makes smaller wispy pieces by first splitting along the length, then peeling small pieces around the girth from one side of the split to the other.



Peeling bark in strips.

The following are trees and shrubs and commonly harvested for their edible parts:

- Balsam fir—Parts of the entire tree are edible, especially the inner bark, sap, twigs, needles, and flower buds and seeds.
- Birch—Entire tree is high in mineral content and medicinal value; sap, buds, catkins and seeds are edible. Birch catkins, buds, twigs and bark, as well as inner bark, are all loaded with trace minerals, and beta-carotene.
- Blackberry—Inner bark, twigs, flowers, fruits and seeds are edible.
- Blueberry—The twigs, bark and roots are edible as well as fruits.
- Maple—Entire tree is edible, especially inner bark, sap, twigs, buds, young leaves, and seeds.
- Meadowsweet—Entire plant is high in minerals and medicinal value; inner bark, twigs, buds and flowers, leaves and seeds are not to be eaten in bulk.

- Pine—Entire tree is edible; inner bark, sap, twigs, needles, catkins, and in one species, Pinon pine nuts.
- Prickly pear—Buds, flowers, pads and fruits of plant are edible.
- Raspberry—Entire shrub is edible, including inner bark, sap, twigs, buds, flowers, fruits and seeds.
- Rose—Entire shrub is edible, especially inner bark, sap, twigs, buds and flowers, leaves and seeds (hips).
- Saguaro—Buds, flowers and fruits, and seeds are edible.
- Sumac—Flowers, fruits and seeds are edible.
- Tumbleweed—Twigs, buds, and leaves are edible.
- Willow—Entire tree has high mineral content or medicinal value and should not be eaten in bulk. Inner bark, sap, twigs, buds and catkins, leaves and seeds are eaten in moderation.

Teas from Wild Plants

Gathering and preparing teas from wild plants is simple and rewarding. For example, a large supply of thyme for tea can be harvested in just two minutes with scissors. Drying requires no more than a screen and takes but a few hours. Using the back shelf of my car, I can have it dried and ready for storage in a few hours. In a few days, the patch grows back and I can harvest it again. This is true for most tea plants.

Plants commonly gathered for tea include:

- balsam fir
- birch
- blackberry
- blueberry
- chamomile
- chicory
- clover
- dandelion
- fireweed
- goldenrod
- meadowsweet
- mint
- mullein
- raspberry
- strawberry
- thyme
- violet
- willow
- wintergreen.

(See Part II, the Field Guide, for information on individual plants.)

Picking Nettles

Do you want to try nettles but are afraid to pick them? Take your gloves, a pair of scissors, and a container and head for the nettle patch. Cut the leaves directly into the container, holding the plant with your gloves. Or, to take home the entire nettle plant, cut two individuals of a plant that is long and straight, such as goldenrod. Lay them on the ground parallel like railroad tracks. Cut the nettle, using your gloves and scissors, pile them across the top. Then pull the goldenrod stems up and fold over so you can carry your bundle home without getting pricked by stickers.

Storing Teas

You might enjoy fresh tea brewed from raw materials. Remember that raw material is a bit less effective and tastes weaker than dried.

Wild plants or leaves that have dried until crisp can easily be stripped clean for storage. Place a clean sheet on a counter and put bundles on top. Using gloved hands, pull the dried leaves, seeds, or flowers down gently, then scoop up and crumble by twisting the sheet and wringing it. This is what is known as a rough grind. In some cases you can obtain the same results by using your hands. Store rough ground teas in glass jars.

You may store twigs in “tea sizes”, such as six inch sections of willow equals approximately 2 aspirin. Six inches of a rose stem equals 1 cup of tea. Four inches of goldenrod stem equals one cup of tea. If you use a mayonnaise or quart size jar many cups of tea are easily stored.



Window food dryer with removable racks.

Flour from Wild Grains

Bulrushes and phragmities grow prolifically in wet lands. They are a familiar sight to most of us, yet few people realize what a valuable food source they are. In both the East and West, I have gathered and ground bulrushes to make flour. The flour makes delicious muffins, cookies, and breads. What's more, there are common grasses growing in most people's lawns that can likewise be harvested for flour. My favorites are listed on page 35.


Bullrush

Gathering bulrush stalks is an easy task, so long as the water is clean. Know where the water comes from and look carefully at the stems as you cut them. It is a good idea to wear gloves until you are well used to spotting the stems of the rushes. Poison hemlock may be in the same marsh, so be careful! (see Part II, Field Guide, and Part V, Poisonous Look-Alikes).

Cut one of the two stems of a bulrush plant at a time, sliding your gloved finger down the stem, cutting, and placing the rush up and under your armpit. As you move along, the batch of plants under your arm will grow. When you have enough, stop and tie them into a bundle. Hang the bundle in a tree or make a yoke for around your shoulders. Pick from the centers of the bulrush clumps, so the plant will grow back quickly.

Dry bulrush in an attic, car, or other warm and dry area. Let dry thoroughly. They may appear to be dry, but check. The stems break, crack or snap easily when dry. Place in glass containers until you can grind the grain to flour.

When you are ready to grind to flour, check bulrushes for tiny black dots. These may represent ergot, a poisonous fungus. If present, discard the plants.

Each bulrush stem yields several teaspoons of flour, and a screen full of stems and flowers yields approximately 1 cup of finely ground flour. The color of the flour depends on the bulrush: it will be green if bulrushes are picked early in the season, tan if picked later.

> *"He causeth the grass to grow for the cattle, and the herbs for the service to man; that he may bring forth food out of the earth."*
> Psalm 104:14
>
> *"Also, to every beast of the earth, to every bird of the air, and to everything that creeps on the earth, in which there is life, I have given every green herb for food, and it was so."*
> Genesis 1:30

Harvesting Grasses

The following are common lawn grasses that make excellent flour. They are also known as Graminae, since they are in that family of plants. Since these plants are not described in Part II, check identification in several other reliable field guides. The grains may also be cooked whole for granola, cereal, and other uses.

Barnyard grass— *Echinochloa crus-galli, Graminae* Family
Barley grass— *Hordeum pusillum nott, Graminae* Family
Broomsedge— *Andropogon virginicus, Graminae* Family
Crabgrass— *Digitaria sanguinalis, Graminae* Family
Foxtail grass— *Setaria italica, Graminae* Family
Goosegrass— *Eleusine indica, Graminae* Family
Jungle grass— *Echinochloa colonum, Graminae* Family
Quackgrass— *Agropyron repens, Graminae* Family
Rye grass— *Lolium temulentum, Graminae* Family
Wild oats— *Avena fatua, A. barbara, Graminae* Family
Wild rice— *Zizania palustris, Graminae* Family
Wheat grass— *Triticum aestiuum, Graminae* Family
Yellow nutsedge—*Cyperus esculentus, Graminae* Family

Some grains are better sheared with scissors, such as crabgrass. Others are easily collected using a pillow case. If the seeds come off the stem easily, just put the pillow case over the tops, bend the grasses over, and wring the seeds off. This method is especially good for marsh grasses. I've happily spent many an evening gathering a quart or two of seed heads while watching the dragonflies in the setting sun.



Barnyard Grass, Goose Grass & Wild Oats

After the grains are dried, they can be ground to flour. Use your own method; grinders, processors, and mortar and pestle are all successful.

I usually clip stems to six inches from the grain. Grinding a bit of the stem adds to the fiber content.

Grains contain protein, and protein is one of the building blocks of life. Unrefined grains are best because the natural elements have not been processed out. Much of wheat's protein and vitamins E and B^{6} are lost in the refining process. As a result we have "enriched" bread, which tries to make up for the loss. Isn't it a better idea to keep those nutrients to begin with? This is why whole wheat flour and whole natural grains are the wise nutritional choice today. Also, fiber is lost in the processing of wheat flour. Yet the higher the fiber content of our food, the better for our digestive system. Unrefined, natural grains are truly the only answer to better health.

Blend one-half cup of assorted wild grains putting them into a wide-mouth thermos and then pour boiling water over them. Cap tightly and let sit overnight to create an instant hot cereal for the morning or the ingredients for a rough bread dough or wild "pancake." Add a little vegetable flour such as amaranth or clover for a high-energy meal!

Preserving Nature's Bounty

Drying for tea or grinding to flour, as the preceding sections describe, are major ways to preserve and enjoy wild food, but there are other possibilities as well. You can collect roots, branches, needles, and flowers in season and either dry them or freeze them for later use in a variety of ways.

In the Adirondacks, my pantry was full of wild foods preserved for winter. The assortment varied from year to year, and when I moved West, there were many substitutes. Tumbleweed took the place of fireweed. Malva neglecta was used instead of arrowhead for flour. The caption to the illustration on the next page tells what wild foods I commonly had in my pantry, East and West.

Typical Pantry Storage

Eastern cupboards were always filled with certain staples. I did not own a freezer in those years. All staples were dried.

Plants hanging in storage pantry.



Car drying racks.



The Pantry

Gallon jars of leaves included: Amaranth, asters, lamb's quarter, strawberry, clover, red and white clover, chicory, daisy leaves, dandelion, dock & malva neglecta. Western jars also included tumbleweed, mesquite beans, palo verde beans & chaparral.
Gallon jars of twigs for teas included: Rose, meadowsweet, pine, balsam, birch, maple & willow, and, in the West, ephedra (Mormon tea).
Separate jars of dried flowers: Aster, clover, chamomile, chicory, dandelion and rose, both in the East and West.

My closets always had a few choice branches stored whole: pine, balsam, willow, and maple. Closets in both East and West are filled with paper cartons of grasses for future use as flour and, of course, the Christmas tree and wreath from year to year!

Preparing Food for Storage

Once you've gathered your bounty, shake off any soil and wash plants, leaves or roots gently under running water. Wash all foods except cattail pollen. Scrub roots with a toothbrush.

Trim off any dead leaves or parts. Remove and separate leaves, seeds, flowers, and roots for separate drying; or leave plant whole (as you might dry lamb's quarters or amaranth for flour). Cut stems to storage-container lengths.

Drying Methods

There are a few basic "don'ts" about drying food that you should know before you begin. Don't dry leaves in direct sunlight; find a warm, airy place out of the sun. Never dry foods near a road or garage, or you'll taste exhaust fumes. Lastly, don't dry pine needles in an oven or microwave. They are very volatile and may explode.

The best indoor drying apparatus I know is a window screen, convenient for either an apartment or a home. You simply bring home your favorite wild foods, wash them well, trim, and shake off excess water. Lay the foods on the screens, keeping any branches apart somewhat. Slide the screen into bracket and start the next screen. (See page 33 for an illustration of screen assembly.)

When you feel that food is as dry as it can be, preheat the oven to 300 degrees and turn off. Heat the foods for five minutes, then put in hot clean jars, or put the gatherings in the jar, without the lid and heat jar, foods, and all for five minutes at 300 degrees. Often I simply turn the oven to 300 for a while, put the food in, and turn off the oven, leaving it to cool slowly. I take the jar out when the oven is partly cool, then cap tightly for storage.

There is another method. Although you may feel odd driving around town with a rack of "weeds" in the back of your car, it is by far the most efficient drying rack! In July and August, one day on the back window shelf of your car will thoroughly dry most leaves. Just think, while spending money driving around town, you are performing an energy-saving task and making a step toward long-term food storage, ultimately saving dollars. The car doesn't have to be in the hot sun all the time. Park in the shade if you wish.

Caution: Don't dry foods in a car when the outside temperature is over 80 degrees—toxic fumes may arise from plastic or vinyl seats.

The Drying Roof

There are more ways to dry wild plants. Here's a simple method I used.

Looking around for a flat place to put the screens I used to dry plants on, I noticed that the roof seemed to take up a lot of space—space that didn't do much other than keep the rain out. So I climbed a ladder and began to place the screens on the roof. Since there were poplars surrounding the cabin, the shade was perfect for drying apples and berries. We even nailed on boards as scaffolding to create a large accessible drying space. You may not want to go this far, but with a little ingenuity you'll find almost any place can be used to dry fruits, berries, and such.

We dried several types of wild apples. We did this every year using the larger varieties, choosing about half the normal size apple. We also dried crabapples on the roof. We gathered the crabapples by spreading a sheet under the tree and shaking the limbs, making fruit fall. We cored the apples and then sliced them crosswise about 1/3 inch thick. We threaded these slices on old broom handles, then hoisted them up to the roof. After a few days, the crabapples had shriveled and became leathery. After a 5-minute baking in the oven to dry them completely (oven preheated to 300 F. then turned off), we stored them in glass jars. In winter we used them in everything from cereal to cobblers, pies, and snacks.

> ***Linda says-*** You can also string the dried apple slices together with a needle and string. Not unlike the garlic and hot peppers in the Southwest, your wild foods can decorate your kitchen. I even string roots this way.

Label the jars with the date of drying before storing. The storage place is important. Closets work best. You need darkened spaces for dried foods, out of direct sunlight.

Store whole leaves and grind them into flour as you need it. For long-term storage, grind and place the flour in a shallow 1-inch pan and toast for five to ten minutes in a preheated 300 degree oven turned off. Store in glass for up to several weeks. Vegetable flour does not have a long life, so avoid storing for more than six months at a time.

Rinse dried branches to clean off any dust before you use them. Rose or raspberry vines, pine or balsam branches, and weeping willow can be stored for years, but will accumulate dust.

Containers for Dried Foods

Generally, I'll save just about any glass jar and use it to store dried foods. As long as they are in glass with a tight-fitting lid, wild foods can be stored for long periods of time. My friends bring me their glass jars: in fact, I have begun to consider myself a recycling center! Of course, brown glass is best because it lets in less light, but it is not readily available. You can find green jars with narrow screw tops, however, and these are ideal for storing seeds, nuts, and berries—things that pour well from a narrow top.

The best container for large amounts of stored leaves, twigs, branches, and such are the half-gallon glass containers that deviled eggs, pickles, and mayonnaise come in. Restaurants or convenience stores might save them for you.

Devices that seal plastic bags, removing the air, work almost as well for long-term storage. Roots store well in paper bags, as well as nuts, twigs, barks, and branches to a lesser degree. As long as food is as dry as possible, long-term storage is possible.



Storage Jars: #1 vegetables, #2 flowers, #3 twigs, #4 roots, #5 stems, #6 nuts, #7 corms, #8 buds, #10 flour

Storage Problems and Solutions

Problem: Pine needles that are stored in glass begin to display black spots or black mold.

This is known as ergot and develops on incompletely dried wild foods which are then sealed in airtight containers. Discard the contaminated foods as these molds are highly toxic. Similarly, grain that was incompletely dried also hosts this toxic black mold. Willow branches stored in a damp area outside develop black spots, also recognized as a poisonous mold.

Freezing Your Wild Foods

Freezer packages of vegetable matter have a life of six months. Roots, twigs and tubers last a bit longer as a rule. When I find freezer crystals throughout the freezer package, it's time for a massive green soup! Then you may re-freeze the soup.

The following are the wild foods successfully frozen. All must be steamed the indicated time before freezing.

Food	**Steam Time**
Aloe Vera	raw
Amaranth	1-2 minutes
Arrowhead	1-2 minutes
Aster	3 minutes
Blackberry	2-3 minutes
Blueberries	1-2 minutes
Burdock	3 minutes
Cattail	3 minutes
Chamomile	1-2 minutes
Chickweed	1 minute
Chicory	3 minutes
Clover	1-2 minutes
Daisy leaves	1-2 minutes
Dandelion	3 minutes
Dock	3 minutes
Evening primrose root	1 minute
Filarie	1-2 minutes
Fireweed	3 minutes
Goldenrod	1-2 minutes
Grape	2 minutes
Lamb's quarters	3 minutes
Mustard	1-2 minutes
Nettle leaves	2 minutes

Food	**Steam Time**
Plantain	1-2 minutes
Prickly pear	2-3 minutes
Purslane	1-2 minutes
Malva neglecta leaf	1-2 minutes
Maple	2-3 minutes
Milkweed	
heads	3 minutes
leaves	2 minutes
Mint	1-2 minutes
Queen Anne's	1 minute
Raspberry	2-3 minutes
Rose	1 minute
Saguaro buds	3 minutes
Shep.'s purse	1-2 minutes
Strawberry leaves	2 minutes
Thistles (all)	1-2 minutes
Thyme	1 minute
Tumbleweed	1 minute
Violets	1 minute
Wild lettuce	1 minute
Wood sorrel	1 minute
Yarrow	1 minute

Some inexpensive freezing tools you'll need are:

- Plastic wrap
- Large plastic bags
- Labels or marker pen

To freeze vegetables, steam and drain the vegetable in a sieve; save the liquid for stock if desired. (See Soup Recipes starting on page 198.) Place one-foot-long piece of plastic wrap on the tray. Add 1/2 pieces of steamed vegetable and fold the edges in. Roll package tightly to seal. Any remaining liquid will seep out of package. Place the package in a large plastic bag and label with contents and date of freezing.



Vegetable Wraps



Freezing rolls of vegetables, flowers in blocks.

Freezing wildflowers is a simple matter of freezing whole flowers in solid blocks of ice. A frozen whole rose looks fantastic in a punch bowl. Use an ice cube with a rose inside instead of plain ice. As long as you use a container that will take freezing, you can create a bunch of frozen roses that looks like a crystal dream. My favorite luncheon surprise is layering a selection of flowers in different colors in a large, round bowl. I put in the bottom layer, add a little water, and freeze. A day later, I add another layer, add water, and freeze. And I repeat this until the display is to my liking.

To freeze whole roses, for instance, put a few inches of water in your containers, so that the flower does not float. Keep the pitcher of water handy so that you can reach it easily with one hand. Hold the stems in your other hand, and arrange the colors and shapes to suit you. (I cut the stems to uniform lengths first, making the job of holding them easier.) Then pour some water slowly around the sides, holding down the stems. Put on a lid or plate to hold the arrangement and freeze.

Whole heads of roses opened moderately and without the stems can be layered easily. The more roses in the container, the better. They won't remain in exactly the same position as you put them once you pour in the water, but if they don't float around a lot, the layers will be moderately undisturbed.

Pansies are relatively simple to freeze. Layer them in a sandwich bag and add a little water, then seal the bags. To freeze Queen Anne's lace flowers, spread plastic wrap or wax paper on a flat surface. Place the flowers face down on the wrap and roll up the wrap like a rug. If you have difficulty rolling a single piece of wrap with flowers, place cover sheet of wrap over the flowers and roll. Freeze the roll. Whenever you want some flowers, unroll the wrap take what you need, re-roll and return to the freezer. Queen Anne's lace flowers will turn brown when frozen, but they retain their delicious carrot taste and apparently their nutrition as well.



Freezing Queen Anne's Lace flowers.

Besides vegetables and fruits, you can successfully freeze vegetable stock and leftover fruits. Save all liquid from steaming or boiling vegetables or from leftover tea. The stock is best stored in freezer containers, ice cube trays, or heavy duty plastic bags. Soup stock can be frozen in layers until the container is full.

To freeze fruits, possibly for a mixed juice, layer the fruits in a large container as they are available. You might have a cup of raspberries—not quite enough to make jelly. Freeze in a large plastic container. Are there blueberries left over from making a pie? Add these to the fruit cache. When you have filled your container, you'll have the makings for a mixed fruit jelly or juice.

Decorations Can Be Edible Too

A blustery winter wind whistles outside the door, and my spirit needs a cup of hot rose tea—rose tea is filled with vitamin C, for muscle repair and vitality, nerve restoration, and a general feeling of well-being. From the rose-stem wreath on the north wall of my home, I break off a bunch of twigs, a few leaves, and one small dried flower. After rinsing and placing them in a tea pot, I cover the rose stems, leaves, and buds with boiling water. I let it steep for five minutes savoring the bouquet, and then serve myself tea from my old china teapot. Nature's bounty!

I had ventured out to a spot in the woods where wild roses grew. There they were, inviting me to make lush wreaths from the green shoots.

I took my loppers, and a big bag or length of twine, and began clipping off a few vines. I wound two vines together to make a circle, then added string to the overlapping ends to secure the wreath. I twisted more vines on the base, poking the ends through. When I finished, my decorative rose wreath was hung on the wall to provide a winter's supply of tea as well as to be a feast for my eyes and nose.

My home abounds with wild food wreaths. Circular, heart-shaped, sprays—all wreaths are either leaves or flowers for teas, grains for bread flour, vines or leaves for vegetables, and twig spices for herbal teas. I decorate every nook and cranny with food wreaths.

Wreaths made from wild grains are not only beautiful but practical. Since prehistoric days, people have twisted vines into coils and wreaths, combining craft with foraging. The Chippewa nation still does this today with wild rice hoops or wreaths.

What plants make the best food wreaths? Here’s a list.

Food Wreaths
- Amaranth
- Aster
- Chicory
- Cholla
- Clover
- Daisy
- Dock
- Fireweed
- Grape
- Lamb’s quarters
- Malva neglecta
- Queen Anne’s Lace
- Rose

GrainWreaths
- Bulrush
- Crabgrass
- Phragmities
- Spice wreaths
- Catnip
- Chamomile
- Clover
- Mints
- Strawberry
- Thyme
- Wintergreen
- Yarrow

Tea Wreaths
- Balsam fir
- Birch
- Blackberry
- Maple
- Meadowsweet
- Pine
- Raspberry
- Rose
- Sumac
- Willow



Food Wreaths (from left to right, top to bottom): Yarrow tea, Grape vine with tendrils for food, Raspberry canes for food and tea, Rosemary sprig for spice, Spice rope of thyme, mint & chamomile, (2nd row) Balsam fir & meadowsweet flowers for tea and food, Balsam sprig, Grasses, oats & dock seeds for food and flour, and Rose hoop for tea.

If you grow your own roses, treat them with a spray of mild soap and water instead of pesticides and herbicides to ensure their future edibility. Be sure your bush is at least 100 feet away from any busy street. And be aware of your neighbor's habits with sprays and wait a season to eat transplanted nursery stock.

When the time comes to buy your holiday tree, make sure it is organic. Christmas trees are often sprayed for insects and sometimes sprayed green to darken the needles. Find an organic dealer or cut your own tree. When the holidays are over and your tree is dry, spread a sheet around the base and shake off the dry needles. Place needles in a large oven container (a roaster, for example). Heat the oven to 300 degrees and then turn it off. Place the roaster with the pine needles in the oven and remove when the oven has cooled. Do not try to bake the needles! The resin is combustible. Put the completely dry needles into glass containers and enjoy five years more of your Christmas tree as tea.

The trimmings from your tree also make fantastic tea wreaths. Collect them before they are completely dry, rinsing and swishing any dust off the needles. Shape into wreaths and hang in your home for a source of fresh tea for weeks.



Notes



Left: garden sorrel Right: wintergreen

Part II: Field Guide to Wild Foods

Edible Plants

This Field Guide section provides illustrations and descriptions of the fifty-nine foods discussed in this book. It is not intended to substitute for a comprehensive field guide to wildflowers, trees, or plants. Rather, it should be used in conjunction with three well-illustrated, comprehensive guides to the plant life of your region. Also please note that plant sizes vary with environment, and measurements given here are intended as general guidelines only.

The material that follows is organized as following, information where applicable:

Common name.
Scientific (Latin) name of species, or genus, only if the entry describes a group of related plants.
Family to which the plant belongs.
Other Names: Other common names by which the plant is known; also, types are described if the entry deals with a group of plant rather than a species.
History: Brief background information on the origin of the plant and a notation if used by Native Americans.
Habitat: General growing requirements—where the plant is likely to be found.
Characteristics: Whether the plant is a tree, shrub, or herbaceous plant; whether annual, biennial, or perennial; major physical characteristics to help you identify it in the field.
Primary Uses: Whether used for food, medicine, or as a cosmetic; some mention of the uses the plant has been put to (not meant to be comprehensive).
Nutritional Value: When applicable, a general indication of the plant's value to human nutrition. See also the Nutritional Value tables at the end of Part II for further information on the nutritional value of these plants.
Medicinal Value: When applicable, information on medicinal uses of the plant. See the Appendix for explanations of these medical terms.
Cosmetic Value: When applicable, an indication of how the plant is used as external treatment or otherwise.
Collection and Storage: Tips on harvesting and preparation for immediate use or long-term storage.
Caution: There are some wild plants that can be mistaken for these edible plants. See the section on Poisonous Look-Alikes,

Part V. Note also that entries in the Field Guide include occasional cautions or warning notices about collecting and handling some plants. Be sure to heed these cautions.

Comments: Personal remarks and additional information on the plant and its uses for us all.



Foreground: fiddleheads

Legend to the Uses of Wild Foods

These symbols appear in the description of each wild food and indicate the main uses of that plant at a glance

Beverage 

Bread 

Casserole 

Cereal 

Flour 

Jam 

Medicine 

Pickles 

Salad 

Soup 

Sweets 

Tea 

Toothpaste 

Vegetable 

Wine 

These symbols are used later in the poisonous look-alike section.

Edible ☺

Poisonous ☠

Aloe Vera

Aloe perfoliata vera
Family: *Liliaceae*



Other Names Medicinal aloe, Barbados aloe.

History: Probably native to Mediterranean. Used by Native Americans.

Habitat: Temperate zones, desert, arid regions.

Characteristics: Bushy succulent. Green fleshy leaves, called spikes, are filled with clear gelatinous liquid. Mature plant has spikes up to 3 feet high with dense, arrow-shaped clusters of yellow or orange flowers.

Primary Uses: Flowers, edible raw. Medicinal, cosmetic. In tea as an antispasmodic, antihistamine (asthma, colds, congestion), anodyne, or as tranquilizer or diuretic. Crushed leaves yield gel which is applied as poultice for burns or sores, promoting growth of new tissue.

Medicinal Value: An antibiotic, astringent (to accelerate wound healing), coagulating agent, biochemical bandage, pain inhibitor, growth stimulator, “wound hormone”, demulcent, antihistamine, mild laxative, burn healer.

Cosmetic Value: Skin conditioner, astringent. Also aloe has bacteria- inhibiting qualities that make it an excellent underarm deodorant.

Collection and Storage: Harvest in summer; buds, flowers, young leaves. For external use, slice leaf in half and place directly where needed. For internal use, remove gel and place in water. Refrigerate or freeze. Freezes well. Where aloe grows naturally, both young and old leaves are thick. Since old leaves are tough and the gel is bitter, harvest the new, thinner leaves.

Caution: Do not use as bulk food. Use sparingly for medicinal purposes only.

Linda Says- Aloe vera is the most important native plant in the West. Preparing aloe is fun. I take a leaf, turn the flat side down, and lay it on a flat surface. The skin comes off easily by slicing under the skin from tip to larger end. The gel scrapes off quickly with a spoon, Then I scoop the gel into a bowl, whip it thoroughly with an egg beater, and put it into an ice cube tray to freeze. I use one cube to a 6-ounce glass of orange juice for a tonic. One cube also works wonders for immediate application on sunburns.

While aloe is a Western plant, mullein in the East has many of the same properties.

Different Plants, Similar Uses

ALOE VERA	MULLEIN
Antihistamine	Antihistamine
Burn healer, pain reliever	Burn healer, pain reliever
Growth stimulator	Growth stimulator, reduces swelling
Wound hormone	Wound healer-promotes quick healing
Pain inhibitor	Pain inhibitor
Astringent, accelerated wound healing	Whole leaf bandage, antiseptic
Demulcent	Antispasmodic
Coagulating agent	Tranquilizer, biochemical bandage
Antibiotic	Mild sedative
Deodorant, inhibitor of bacteria	
Mild laxative	Anadyne, a medicine that relieves pain
Cosmetic, skin softener	Cosmetic, skin softener

Amaranth

Amaranthus retroflexus
Amaranth family, *Amaranthaceae*



Common Amaranth (Western U.S.)

Other Names: Green amaranth, Pigweed, red root, carelessweed, choohugia (Pima name).
History: Native to tropical America; naturalized throughout the world. A staple food of the Zapotec Indians of Mexico. (Sturtevant 1972) Coastal Algonquins collected amaranth for a vegetable and used its ashes as salt. The plant is naturalized in Asian countries. It is cultivated in tropical Africa and Jamaica as a potherb. Seeds are used for flour in India and Nepal. Amaranth yields 8 ounces of seed from plants covering 1 square yard of ground.
Habitat: Cultivated soil.
Characteristics: Annual herb. Averages 2 foot, but may reach 6 feet or more. With bristly seed heads, clustered on multi-branch stems from a central stalk. Flower seeds are black and shiny; leaves are smooth and veined with slightly toothed margins. Eastern amaranth seed heads or "flowers" are denser and shorter than the Western species. Western varieties may have long, spindly, bristly seed heads, and white seed pods with black seeds inside.
Primary Uses: Culinary, cosmetic. Use leaves and stems like spinach, eaten raw, steamed, sautéed, cooking liquid is drunk. Leaves are also dried and ground for flour. They are used in soups and stews. Seeds are used raw or dried for baked goods, cereal, mush.



Common Amaranth (Eastern U.S.)

Nutritional Value: High in vegetable protein. High calcium and vitamin E.
Cosmetic Value: Astringent, wrinkle cream.
Collection and Storage: Use entire plant. Harvest lower leaves and branches in summer as vegetables. Refrigerate or freeze; dry. Wait until plant is full grown for large seed heads. Amaranth seeds are easily collected in autumn by tapping the seed head over a bowl, even in summer on the desert.



Linda Says- The first time I saw amaranth I couldn't believe my eyes! Tall, wondrous plants heavy with seeds bordering pasture and barn areas. There were hundreds of these "weeds" some bent over from the weight of their seeds. In less than 20 minutes I bundled enough amaranth for a week's supply of fresh vegetable and almost a winter's supply of flour. It did not take long to discover the wonders of amaranth in brownies, as a cooked green, or as a gruel.

Arrowhead

Sagittaria species, *S. chinensis*
Water Plantain Family, *Alismataceae*

Other Names: Duck potato, wild potato, Wapatoo (Indian).
History: Native to North America. Lewis and Clark used Arrowhead for food, taught by Native Americans. The explorers wrote, "(they) can be ground fine. A flair for pudding, cakes, etc. They are nearly equal to Irish potatoes, and are a bread substitute." Chinese sell it in marketplaces for food.



Habitat: Widely distributed. Marshes, wet bogs, mud flats.
Characteristics: Aquatic perennial with tubers. Grows in swamp water to a height of about 10 inches. Arrowhead-shaped leaves and filmy white-petal flowers. Roots have walnut-size tubers.
Primary Uses: Culinary. Root corms: Used as potatoes, sliced or whole, boiled, sautéed, or raw. Strung and dried then ground for flour.

Nutritional Value: Easily digestible; a nutritious food, especially for convalescents.
Collection and Storage: When harvesting arrowhead tubers, use a pitchfork and lift gently. The tubers tend to snap off in the mud and the pitchfork creates less tension. Freezes and dries well. Scrub the small tubers thoroughly and string with a needle and thread. Hang the strings to dry, then store in glass.
Caution: If water purity is in doubt, use purification tablet and soak tubers in water purifying solution.
Comments: There aren’t too many arrowheads in my area of northern New York, but southern New York and areas of New Jersey have immense quantities in marshes and wetlands; they are also in wetlands in the West.

Linda Says- My marshes do have a few "secret" areas for Arrowheads. Misty, boggy, muddy, slimy, and mossy, the marsh's loam logs rot away to the richest, blackest soil I have ever seen. Mosquitoes are an inch long where the arrowheads poke up above the mud! I pray silently, dip my pitchfork under the plant, and lift slowly. I used a needle and thread to string the tubers in the cabin, drying them for the winter. Easily reconstituted in water, the tubers make delicious soups and stews.

Aster

Aster nemoralis
Composite Family, *Asteraceae*



Other Names: Blue, pink, lavender, white & yellow aster.
History: Native to North America. Staple of the Iroquois Indians in the Northeast; food of tribes in the Midwest and West. Used in sweat lodges by Objibwa Indians to revive consciousness by putting on the hot rocks. Used as a food in South America.
Habitat: Fields and meadows, roadsides.
Characteristics: Perennial herb. Many varieties. Height varies, average 24 inches; may reach 40 inches. Numerous extensions jutting with multi-petaled flowers from a central stem. Petals are layered in flat, 1/2-inch-long sections. Colors vary from white to pink, yellow, blue, and purple.
Primary Uses: Culinary, Medicinal. Leaves eaten raw, steamed, boiled, sautéed, cooking liquid is drunk. Flowers stewed or steamed whole; chopped fine and stewed or steamed. Entire plant is dried, then stripped and ground for flour. Sprinkled on dishes, especially tomato-based dishes such as lasagna. The pith of the aster stem is edible, even in mid-winter. As emergency food, eat raw or cook in soup.
Medicinal Value: Dried stems and flowers are used as a wash for rheumatism; also excellent blood tonic tea. Roots of dwarf purple aster used for diarrhea control.
Collection and Storage: Snip the long stems at ground level and bundle together with string. I carry 2-foot lengths of string around my shoulders, and harvest the flowers until I have a bundle 10 to 15 stems thick. Stop bundling stems together when the flowers are too tight to be airy for drying. Take only a few plants from each

area (or 1 out of 4). Hang bundles upside down on a clothesline to dry. When dry, strip down onto sheet, crumble, and store. Also, leaves can be frozen.
Caution: Do not eat domestic asters.

Linda Says- Nature's abundance is particularly clear to me when I harvest the Iroquois staple, the wild aster. There are 250 varieties of wild aster in the United States: blue, lavender, yellow, and white prevail in the Adirondacks; blue, lavender and yellow in Western states. Field may have flowers as far as the eye can see. In less then 15 minutes I have enough to make a winter's supply of wild aster flour. I grind this bounty into flour for baking from dried storage food. The flour is particularly strong, nutritious. I recommend adding a small amount to regular recipes. This Iroquois staple remains one of my favorites.

Balsam Fir

Abies balsamea
Pine Family, *Pinaceae*



Other Names: Christmas tree.
History: Native to North America. Soft inner bark was used as emergency food at Valley Forge. Native American usage.
Habitat: Grows in cool, moist, acidic soil along roadsides, woods, or lawns and in softwood forests.
Characteristics: Evergreen tree. Has small, short needles growing alternately from under stem, 1 to 1-1/2 inches long. Grows to height of 40 to 60 feet.
Primary Uses: Culinary, medicinal, cosmetic. Bark is chewed, ground or dried for flour. Sap is chewed as gum. Branches and

twigs are stripped and ground for flour. Needles are used raw for food; steeped raw or dried for tea. Used in wine. Ground raw or dried for emergency flour. Dried needles are used to fill balsam pillows and sachets. They lend a fresh scent to drawers and closets.
Nutritional Value: Good source of vitamin C.
Medicinal Value: Roots used as a poultice to soothe syphilitic sores and gonorrhea. Sap (pitch) is a “glue” for cuts, scratches, bites, and sores. Dried sap is chewed for colds, bronchitis, influenza, pneumonia, upper respiratory diseases.
Cosmetic Value: Oil used for flavoring, scents, perfumes, soaps.
Collection and Storage: One branch yields a winter’s supply. Balsam fir tips are a lighter green, indicating newer growth. I snip off needles here and there, filling a bag with dozens of twigs. Needles dry easily and quickly indoors in a sunny spot. For tea, simmer 1 cup needles until water is dark green. You may reuse needles or bark several times, adding water and simmering. Poke sap blister and gather liquid for emergency glue; store in glass if possible.

Linda Says- Rather than throw away your Christmas tree, use it for nutrition as well as a room refresher. For a wonderful aroma throughout the winter, simmer needles in water until they reach a thick, gummy state. Use twigs and parts of older branches as a fresh-smelling incense. To dry sap for medicine, make small flat cakes of sap and dry in a thin layer at the back of a wood stove or above the pilot light of a gas stove.

Birch

Betula species
Birch Family, *Betulaceae*



Other Names: White birch, paper birch, yellow birch, golden tree.
History: Native to North America. Scandinavians boiled, baked and added birch sawdust to their breads. Loggers say that their white birch sawdust used to be taken to American bread companies. Native Americans used birch dust for tea, and the strong inner bark was fashioned into many crafts. The Cree Indians folded birch bark and bit patterns into it, then unfolded it. Hundreds of Confederate soldiers were saved during their retreat to Monterey, Virginia, when they used birch bark as food[1] (Harris 1973).
Habitat: Woods, roadsides.
Characteristics: Deciduous tree. Alternate simple saw-toothed leaves. Papery bark of white and yellow birch peels in curls.
Primary Uses: Birch is an excellent cabinet-making wood; it makes strong hardwood furniture. Culinary, medicinal, cosmetic. Inner bark, sap, twigs, buds, and young leaves eaten raw as emergency food; dried and ground for flour. Sap is drunk raw for nutritious liquid. Twigs are used to make wines, dried for tea or crispy treat. Buds eaten raw. Young leaves steamed, sautéed, cooking liquid drunk.
Nutritional Value: High in minerals, calcium and phosphorous. High in potassium and beta carotene.

FLOUR 🍷 ☕

---

[1] Ben Charles Harris, p. 444

Medicinal Value: Buds are a tonic, since birch bark contains salix, or acetylsalicylic acid. A strong tea made from the bark has been used as an aspirin substitute.

Cosmetic Value: Birch bark used for skin problems, eczema, skin eruptions, pimples, dandruff, and scalp disorders. Dried, powdered leaves used for chaffed skin; birch oil for hair tonic or body oil.

Collection and Storage: Use the bark of downed trees, or follow a logging trail and gather the sheets of bark left behind. You can also peel the bark off firewood in the spring. Strips of birch bark make a quick, sure fire. Four 5 1/2 inch strips = 2 cups fine flour (a winter's supply). One branch approximately 4 feet long = winter's supply for 4 people.

Tap the trunks in spring (April-June) like maple trees. One tree yields an average of 1 gallon of syrup in a few hours. Twigs, inner bark, and sap can be used all year. Buds and twigs have a wintergreen taste. The sap can be boiled down and used as a syrup or in birch beer. Boil down birch syrup further to make birch molasses. Store dried and ground inner bark in glass as an emergency food. The inner bark makes a delicious mineral tea; carry a chunk with you when doing hard physical work. The inner bark dries to a breakable sheet ready to be used as tea; store in glass containers.

Caution: People allergic to aspirin may have a reaction to salix wild foods such as birch.

Caution: Peeling the bark of a living birch will kill the tree. This is called girdling a tree. The bark is literally the skin of the tree, and without it the birch will die.

Linda Says- Birch bark is one of my most precious possessions. I use it in every season for tinder and generally keep sheets of it in quantity. In the middle of one winter I received an order for birch-bark baskets. Since I had no bark on hand, I got permission to go up a logging trail with Ken and Todd. What a day-20 degrees below zero, with 4 feet of snow and no snowshoes! As I peeled bark off stumps of white birch with my knife and hatchet, Todd played in the drifts. That night my back ached in remembrance of the work, but I had enough bark for hundreds of baskets, with plenty left over for Christmas cards and for starting fires.

Blackberry

Rubus villosus and other bramble berry species
Rose Family, *Rosaceae*



Other Names: Creeping blackberry, cloudberry, wine-berry, dewberry.
History: Native to North America and elsewhere. Used as a fruit in all countries where found
Habitat: Roadsides, fields, meadows.
Characteristics: Biennial trailing stems. Bush varies in size, up to 5 or 6 feet tall. Saw-toothed leaves in groups of 3 to 5; thorns on angular, arching stem; fruit pebbly and black when ripe. Canes produce fruit on second year's growth. Fruit does not separate from receptacle when picked.
Primary Uses: Culinary, medicinal, cosmetic. Young stems and shoots eaten raw or cooked; used fresh or dried for tea. Fruit is eaten raw, and cooked for jellies, jams, syrups; also juices and wines. Flowers entirely edible raw. Young leaves are edible as a cooked vegetable in the spring.
Nutritional Value: Young stems and fruit are good source of vitamin C.
Medicinal Value: Bark of stem helpful for intestinal problems. Tea made from blackberry root helps control diarrhea. This tea is also an astringent, a mouthwash for mouth sores. As a strong tea or eaten raw, all parts of this plant can be used to relieve diarrhea or as a blood cleanser.
Cosmetic Value: Leaves are good for facials, masks, lotions, and astringents. In an extract, clears blemishes, eases scalp itches, and heals scales.
Collection and Storage: Tie a lightweight receptacle around your waist and use both hands to pick berries. Hand-pick young leaves in early summer.

Picking Blackberries in Adirondack Bear Country

The dirt road next to the shanty led down to an old log bridge. The bridge spanned the Cedar River, and there was nothing but private wilderness for several miles. I crossed the river and climbed the wooded path for one mile. In another half-mile, I came to the largest blackberry patch I had ever seen. I was equipped with lightweight containers for the berries and fly repellent made of olive oil and pennyroyal.

I whistled a tune as I approached the patch, wary of the bears known to be in the area. I knew if I blended in too much, the bears might resent it. This philosophy had worked for me before-either I was allowed into their domain or I was not. Then I became aware of a very large body up ahead. I could hear and smell the bear shuffling slowly through the woods. I waited. Testing the wind for the bear smell and listening with my ears as I whistled, I knew the bear shuffled away.

I picked blackberries with both hands, dumping them into a plastic bottle and then into a large bucket. I worked my way around the path from left to right. Experience told me that I needed two hours to obtain eight quarts of juicy blackberries, and this particular day I picked eight quarts and then left the patch to the bears again.

When I worked with my son, Todd, we had our two coffee cans filled in moments and proceeded to dye our sweatshirts blue-black with the weight of the juicy fruit. With over a gallon of ripe blackberries we made jelly that night over an evening campfire. Breakfast was a treat!



Blueberry



Vaccinium myrtillus
Heath Family, *Ericaceae*

Other Names: Bilberry.
History: Native to North America. Used by Native American tribes.
Habitat: Acid soil, fields, roadsides, waste areas, bogs, marshes, woods.
Characteristics: Low spreading plant or woody shrub. Many varieties, from ground-hugging plants to high bushes. Fruit is in clusters in groups of 2 to 10. (Huckleberry often grows near blueberry; edible fruit looks similar, but huckleberry has stony pit and tart taste.) Wild blueberry looks like bilberry: both are edible, although true bilberry is not very tasty.
Primary Uses: Culinary, Medicinal. Fruit is eaten raw or cooked for jellies, jams, syrups; also wines.
Nutritional Value: High source of Vitamin C.
Medicinal Value: Blueberry leaves used medicinally in a tea. Because they contain myrtillin, an antispasmodic and relaxant, blueberries were used as a drink during childbirth to relax the mother. Leaves, fruit, and twigs can be made into an infusion and drunk for kidney problems. Dried berries are chewed slowly and thoroughly to aid control of diarrhea. Leaves and twigs can be used separately or together as teas, tisanes, and throat gargle.
Collection and Storage: Blueberries are best picked by first pulling sections with both hands rather roughly and letting berries fall on to a sheet spread around the bushes. After rough-picking a few bushes, rustle the branches for the many berries caught between the leaves. Gently gather up the sheet and pour the berries on a tray.

- 4 cups fresh berries = 8 jars jelly
- 4 cups fresh berries = 2 cups dried berries
- 4 cups fresh berries = 1 quart frozen berries

Twigs can be dried or dug up under the snow. Berries are placed in cold water. The immature berries and leaves float to the top for easy removal. To dry, spread on a tray; cover with a screen or cloth. For storage, berries can be dried until they rattle, or frozen.
Caution: Positively identify; crush fruit for characteristic blueber-

ry smell. Blueberries have a slight frill and an opening on the side away from the stem. A species of buckthorn, which is poisonous, has blue berries without a crown or frills.



Linda Says- The fields behind the old McConnel place were filled with ripe berries, and became my favorite place to pick. I'd place a sheet around the bushes, and use both hands for picking. With a sheet you can become lightning fast, but it is still a challenge to pick enough berries for a pie before the blackflies find you. I usually made smudges before the clouds of flies found me if I wanted to take my time picking. Then I'd dry blueberries on screens covered with a cheese cloth. Those berries in my cereal on a winter's morning made it seem like spring.

Bulrush

Scirpus validus and other sedge varieties
Sedge Family, *Juncaceae*



Other Names: Sedge, tule, great bulrush, nupiaskun (Crow Indian)
History: Found nearly throughout the world. Used as food from Moses' time including use by all Native Americans. The Crow made mats by sewing together bulrushes with basswood string and a bone needle.
Habitat: Wet areas, drainage spots, bogs, swamps; alongside waterways and ocean bays.

Characteristics: Grasslike herb. Many varieties with height to 24 inches or more. Stems smooth, round, with pith; head of flower spike full of seeds and pollen.
Primary Uses: Culinary, medicinal. Roots cooked as potato. Early shoots eaten raw, steamed, boiled, sautéed; cooking liquid drunk. Flower clusters dried and ground for flour. Bulrush flour is sweet and nutty—it has the most branlike taste of all the grains. Pollen used as flour. Seeds ground and roasted.
Nutritional Value: Highly nutritious, roots rich in complex carbohydrates.
Medicinal Value: A plaster or poultice for aches and pains.
Collection and Storage:

- 6-8 bulrush plants = up to 1 cup leaves
- 1 cup leaves = 1/2 cup bulrush flour
- 1 teaspoon powdered bulrush leaves = 1 cup tea

See page 34 for collection details.

Dry the bulrushes whole, bundle the long stems and hang them upside down in a warm, airy spot out of the sunshine. To ensure dryness, dry in a 300° F. oven for 5 minutes, then turn oven off and wait until cool. Follow this drying procedure even if using the bulrush strictly for decorative purposes.

Linda Says- I have spent many wonderful mornings watching dragonflies and frogs playing in the swamp while I gathered bulrushes. Swamping is not only fun, but profitable-I've fed many people on bulrush bread.

Insects love to lay tiny eggs in bulrush tops, so even if I am using the bulrushes for decoration, I leave them outside for 24 hours so the bugs can leave. After drying, I use them in lovely arrangements or grind them to a fine, delicious flour for baking.

Burdock

Arctium lappa
Sunflower Family, *Asteraceae*



Other Names: Beggar's buttons, burs.
History: Native to Europe and Asia; widely naturalized in North America.
Habitat: Fields, roads, most waste areas.
Characteristics: Bush like, large green leaves over a foot wide, and many veined. Tubular, purple or white flowers followed by spherical burrs, 3/4“ diameter. In the fall, burs dry to brown, sticky seed pods.
Primary Uses: Culinary, medicinal. Roots are boiled; dried and powdered for nutrient additive. Stem pith is baked, boiled; eaten as pickle, candy. Early leaves are eaten raw, steamed, boiled, sautéed; cooking liquid drunk. Large leaves are used as trays and receptacles for small plants. Burs when young and still pliable are steamed and eaten; when mature, broken in half and white pith eaten raw.
1 large leaf holds 2 cups green burs
1 8-inch root = enough raw root for 2 or 3 people
Nutritional Value: High in vegetable protein. Contains inulin, the chemical source of insulin.
Medicinal Value: Tea used to heal infections. Root is a diaphoretic; as wash infusion, for poultice, bruises, sore or tired feet.
Cosmetic Value: Seeds for skin problems, eczema, cleansing. For pet's fleas, simmer a small handful of brown burs, strain, and cool. Wash your pets with the decoction. Kills fleas quickly!
Collection and Storage: When you can, harvest the young roots before the flower stalk develops (usually the second year of

growth). When digging roots, slide the shovel thoroughly down one side, then another, until all 4 sides have been deeply cut. Keeping the shovel in one side, pry up the root without breaking it off. You will feel the pop when the root releases from the earth. If the tip remains, the plant will grow again. Steam and wrap burs individually to freeze. Slice and fry or simmer and then freeze roots. Gather burdock in any season. Similar in size to rhubarb leaves, the gigantic burdock leaf forms its own carrier. In spring, place tiny new burs on a leaf, roll the leaf, tuck in the ends, and put the leaf in your pocket. In winter the burs are brown. I take a few brown burs, stroke the bushes, and gather a ball in no time. I stick the burs together in a large ball and carry them on my shoulder, freeing both hands for further picking.



Carrying Burs

Linda Says- When harvesting, cut over the joint of the root where the stem begins. Scrub the root with a brush then peel root until you reach fiber. The fiber will turn from white to brown very quickly; this is normal oxidizing. You can peel the brown off again when serving, but I just steam the burdock pieces and freeze for a winter's meal. Drying the peels makes a crunchy, chewy root food.

Cattail

Typha latifolia
Cattail Family, *Typhacerae*



Other Names: Supermarket of the swamp, punk, upakiotipa (Crow Indian).
History: Native to North America, Europe, Asia. Cattail has been used for food throughout recorded history by people in all countries where it is found.
Habitat: Bogs, swamps, wet areas.
Characteristics: Perennial herb. Grows in wet areas to a height of 10 feet or more. Stalks have hot dog-shape heads, pollen flag in early spring. Very tall slender leaves with 1 vein.
Primary Uses: Culinary, medicinal. Roots are dried and ground for flour. Early shoots are eaten raw. Stem pith is eaten raw, boiled, and pickled. Early green heads are eaten raw, cut and cooked as ear of corn. Early brown heads are ground for flour. Pollen is used as nutrient additive. Leaves are used for basket weaving, mats, other crafts.
Nutritional Value: Plant holds about 30 percent complex carbohydrates; highly nutritious.
Medicinal Value: Flower heads used in tea for diarrhea control.
Collection and Storage: Pollen collected in spring; shake into a paper bag. Stems harvested before the cattail flowers, whenever possible. Roots dug from winter to early spring. Gather fluff from mature heads for excellent insulation or stuffing for jackets. The fluff floats and is waterproof, and serves as excellent tinder and torch. Can be used as cotton.
Caution: If water purity is in doubt, use purification tablet and soak plant in solution.
Caution: Pollen fluff may cause skin to break out in hives.

Cattailing Seasons

The morning is misty and cool. The Adirondack. ice has finally left the swamp and the crystals have melted along the edges of the mossy mats. The cattail shoots will soon be through. Water is beginning to show the spring signs of life. I saw bugs skating yesterday and heard a frog peep. Steam is rising from the invisible shield above the water. The old, dried stalks of cattails, left after winter's fury, lay bent and crooked, disheveled. The matted fuzz of the old tails looks pathetic as the new growth heads toward the surface of the shield.

There are blades-green shoots-poking up from the swamp. I take my trusty shears, long boots, plastic garbage bag, 4-foot board, and towel (should I fall in the boggy mud), to gather cattail shoots to can for winter. Laying the board from mat to mat, I gingerly move the length, clipping the shoots and dragging my filling bag behind me. Glancing back into the swamp, I can tell where I have harvested. The shoots will come again, reaching toward the sun of summer.

Later in spring, green plumes meet my eyes. The heads are like corn on the cob. I can taste and smell the meaty, nutritious flesh. My board goes down gingerly now. The swamp is dotted with thousands of green spikes. Gathering carefully, I pick only cattails with a full cob. Making piles of 8 to 10 stems, I bunch them in a pattern behind me, then I wrap each bundle with the leaves, winding them round.

Though the water is much warmer now, steam rises as dozens of insects zoom through. Mosquitoes glide by, legs tucked up underneath, looking like tiny planes with their landing gear drawn for a landing. Frogs and peepers croak and splash off their pads. I have cut the largest harvest ever. Now winding my way back I pick 10, 20, 30 tails at once. I'm coming back to camp with a supply of cobs to savor.

Summer is here and the murky mud is tough going. The cattails have filled the swamp with heavy bushy stems and blades rich with brown cobs. They are ready for harvest. Flour time! Bread time! Pancake time!

The cattail stems have swelled to 1 inch, sometimes 1 1/2 inches thick. Inside lies a creamy white pith that makes delicious pickles. Sweet and highly nutritious, they will supply a winter's fat. The cattail is heaviest now so I gather only a few, counting up to 10. I need 20 to 30 to make a loaf of bread. The mosquitoes are merciless, and the 90 degree August heat is causing the brackish water to make a stench. Under the cattails grow pennyroyal, mint, and other grasses. The harvest is half done for the winter. Another day and I will have seven or eight gallon containers filled with the pure starch piths.

Fall is here and my last trip for the year to the swamp is a sad one. Most mosquitoes have disappeared when the temperature dipped to 50 degrees. Ice crystals will form soon. Soon 40 mile per hour wind will swirl snow. Life will be in a dormant stage for many months now, but the precious cobs will be our insulation, our stuffing for pillows, blankets, and winter jackets. This collection is the easiest. As fast as I cut a cob, the pollen pops out and my bag fills with creamy fluff. The tough brown skin holds some heads together, awaiting a twist by both hands to rip open and fluff out the rich pollen.

The mud has an almost fishy odor, and it is full of algae and frogs. At this last harvest of the year, the rewards come in floods, and the swamp holds my deepest respect. I have reaped its finest fruit-the supermarket plant of the swamp: the aquatic cattail.



Cattails and Cobweb

Chamomile



Matricaria chamomilla
Composite Family,
Asteraceae

Other Names: Ground apple, Roman chamomile, mayweed, German chamomile, pineapple weed.
History: Some varieties native to North America; many naturalized from Europe. Used throughout Europe. Also cultivated for commercial use, such as in shampoos and teas. Oil is extracted for many products, including hair rinse and insect repellents. The fragrance is called mananilla in Spain. Used especially in Italy, England, and Germany.
Habitat: Roadsides, “people places,” walkways, gardens.
Characteristics: Biennial herb. Height average of 3 inches; may reach 12 inches or more. Tight-budded flowers, tiny yellow daisy; sweet, pineapple-like smell.
Primary Uses: Culinary, medicinal, cosmetic. Twigs are dried for crispy treat. Leaves are eaten raw; steamed; sautéed; cooking liquid drunk. Steeped raw or dried for tea. Flowers are eaten raw; steamed; sautéed; cooking liquid drunk. Entire plant is steamed; boiled; used in soups and stews. Steeped raw or dried for tea.
Nutritional Value: High in minerals; calcium, iron, potassium, and niacin.
Medicinal Value: Stomatic, diuretic, chapped skin ointment,. root used for toothache.
Cosmetic Value: Compress for eyes, shampoos, rinses for hair luster.
Collection and Storage: Grows near pathways, and a winter’s supply can be picked in a few minutes. Shear with scissors.



Linda Says- The smell of chamomile tea means fields, sunshine, and peace for me. I especially like to dry the flowers for tea, but any part of the plant will serve just as well. This lovely plant has more uses than tea, though. I eat the plant raw as a mild tranquilizer. The plant's parts make a delicious addition to salads. Chamomile flowers frozen in ice cubes bring a touch of spring to a drink on a cold winter's day.

To use as a hair rinse, simmer the entire plant -leaves, roots, and flowers-in water. Simmer until water is green, about 15 minutes. Cool the water, strain, and apply. Let this sit on your hair for a while, then rinse again. It will give your hair amazing vitality.

Try seeding chamomile in your garden or lawn and let it go wild.

Chickweed



Stellaria media (common chickweed), *Cerastium* (mouse ear chickweed)
Pink Family, *Caryphyllea*

Other Names: Star flower, chickweed, stitchwort, starwort.
History: *Stellaria* native to Europe and Naturalized in North America; *Cerastium* native to North America. Widely distributed; used by Native Americans.
Habitat: Fields, lawns, roadsides, waste places.
Characteristics: Annual or perennial. Flowers petaled, 5 pairs, deeply cleft in half. Tiny and white above long stalk 4 to 6 inches. Leaves ovate and smooth. All types of chickweed are small ground plants with some parts erect but mostly prostrate. Prolific, seen year-round in some areas, even under the snow. Flowers

can be found most months of the year. Mouse-ear chickweed has minute hair on all leaves and stems.

Primary Uses: Culinary, medicinal. Whole plant is edible raw. Used as a vegetable or salad green. Also stewed, stir-fried, dried or frozen for later use. Mouse-ear chickweed is cooked to remove hairs.

Nutritional Value: High in calcium, potassium, and ascorbic acid; trace minerals.

Medicinal Value: Soothing effect; upper respiratory; externally for poultices on inflamed skin.

Collection and Storage: The tiny star-shaped flower petals have a tiny notch at the end. Leaves are easily twisted and picked from stems. Gather as you would dandelion leaves (see page 24). Young leaves are best. I have always identified them by this.

Linda Says- A bit of garlic and steaming hot chickweed make a nutritious meal for the forager because it is high in calcium, potassium, ascorbic acid, and trace minerals. I once found myself sitting on a hillside, pulling handfuls of chickweed and eating them with gusto! The most amazing feeling is the delicate leaves of chickweed. When I put my fingers down into the thick mat of tiny nourishing leaves to pull up a handful, my contact with this plant always is one of delicacy and gentleness. A little washing, oil and vinegar and the feeling is easily transferred to my mouth!!!

Chicory

Cichorium intybus
Composite Family, *Asteraceae*



Other Names: Blue sailor, blue daisy, coffee weed, wild succory, Barbe de capuchin, whitloff, ragged sailor, wild bachelor button, blue dandelion, blue daisy.
History: Native to Europe, naturalized throughout much of North America. Used by Native Americans and a staple European food. Each year the United States imports tons of chicory root for use as a coffee substitute, coffee flavor, and coffee extender.
Habitat: Roadsides, fields, dry sandy areas.
Characteristics: Perennial herb. Grows to height of 2 feet but may reach 4 feet. Has deep taproot and milky juice. Red-veined, deep-cleft leaves are thicker than dandelion to touch. Stem has many star-blue ray flowers. When broken, root exudes a white milky sap, as do the stem and leaves. Plant begins in a lettuce-like whorl of leaves on the ground, heads up in a bunch, then shoots a stalk upwards from the center. Roadsides show bunches of deep green, deeply indented leaves; not unlike dandelion, but a bit more uniform in clusters before the stalk appears.
Primary Uses: Culinary and medicinal. Roots are dried and ground to coffee. Leaves are eaten raw in salads and sandwiches. May be steamed, stir-fried, boiled as a vegetable, sautéed; cooking liquid drunk. Stems are entirely edible as are the flowers and seeds.
Nutritional Value: Roots are rich in beta-carotene and niacin as well as carbohydrates.
Medicinal Value: For stomach and kidney disorders.
Collection and Storage: Gather roots in early spring. Roots may be stored in strips for easier grinding (see page 30 for illustration on stripping roots). Store whole roots in paper bags in a warm, dry area for future pulverizing or boiling.

- 1/2 paper grocery bag of dried leaves = 1 quart rough ground flour
- 1/2 paper grocery bag of dried chicory roots = 1 quart ground coffee substitute

To collect pull up entire plant by grasping stem as close to root as possible and pull straight up. Hack off the root (I use an ax), gather and wash the leaves, and scrub the root with a toothbrush. When the roots are clean, slice lengthwise into strings. These dry easily on a screen or may be strung over a wood stove to dry.

Linda Says- Chicory roots pull up easily from sandy soil. I put my bounty in a rain barrel to keep the entire plant fresh until I can work on it. All summer, Todd mows the lawn where there is chicory. The reddish vein makes it easy to identify the plant. To tell chicory from the common dandelion, just feel both leaves. Chicory leaves are thicker and not shiny. Dandelion is softer and shiny.

Cholla

Opuntia fulgida
Cactus Family, *Cactaceae*



Other Names: Jumping cactus.
History: Native to North America. Used by Hohokam, prehistoric desert people. Indian women used baskets, sticks, and wooden tongs made from saguaro ribs to gather the buds. A firepit was dug in the desert floor, and the buds and joints were placed in a mesquite fire, roasted, and split in two to eat the succulent insides.

Habitat: Desert.
Characteristics: Treelike cactus with many branches. Cholla cactus has dozens of individual egg-shaped barbarous sections extending from tree-like stems reaching heights of 3 feet or more. Flower is light rose color, fruit is green and smooth.
Primary Uses: Culinary, medicinal, cosmetic. Edible flowers, seeds, fruits, and bud extensions. Fruits are eaten raw, boiled, or baked. Dried for long-term storage. Fruits used in soups, casserole.
Nutritional Value: High in calcium and iron.
Medicinal Value: Gel applied on skin burns.
Cosmetic Value: Gel used as skin softener.
Collection and Storage: Use tongs and paper bags to collect fruit, leaves, and flowers of cholla. Spines and glochids are removed in any of several methods. Indians used flash fire, holding a flame under the burr to remove the glochids, so that they could be opened easily and handled with the fingers. Another method is to place burrs in one paper bag and transfer to another several times. Dry cholla buds on screens in the sun. Cover with cheesecloth if birds pick at them. Dried buds are stored in paper bags until needed. When needed, reconstitute in water about 3 to 4 hours, then boil for one-half hour.

Evelyn Neithammer (1974) found that the easiest way to clean cholla buds is to fill each of 2 saucepans one-third full of clean gravel. The buds are added and the gravel and buds poured from one pan to the other four or five times, or until rid of spines and glochids. (Glochids are minuscule, dense pockets of small barbs which protrude from the pads of prickly pear cactus. They are small but mighty protection against antelope, deer, and cattle of the Western plains.)

Caution: Spines and glochids will penetrate skin with a voracious sting and burning sensation. Do not touch the cactus with bare skin.
Caution: All cholla, prickly pear, and saguaro cactus is "protected plant, by State of Arizona," but it is legal to pick fruits and buds of the species in this field guide for food. The rare crested saguaro is completely protected, so NO fruits or parts may be taken. Be sure to check the regulations in your state.



Teddy Bear Cholla

My first introduction to cholla is a painful, clear memory. My brother, Paul, and I were taking a first tour of the desert together. I was listening to him carefully. "Walk behind me, check your shoes carefully for the cholla burrs, and never step over the bushes here...walk around in the bare spaces." I was trying to listen, but the 100 degree temperature became a problem and I began doing my Adirondack way of walking. I stepped over a bush, but never put my other foot down. It was stuck to my rear with a thousand fire barbs. (The burrs were attached to my sneaker heel, which brushed my rear closely enough to get the burrs attached to my skin.) Screaming, I stood an embarrassed 20 minutes while Paul picked out the hundreds of minute hairs with tweezers. Needless to say, I remember the rules now and thank him for a lesson well learned!

Clover

Trifolium pratense (red clover)
Trefolium repens (white clover)
Legume Family, *Leguminosae*



Red Clover

Other Names: Long stalk, strawberry clover (red clover); common, sweet, short stalk clover (white clover).
History: Naturalized from Europe. With over 300 species, clover has been used by all cultures throughout history. Native Americans used it widely as a vegetable or cure for chest congestion.
Habitat: Roadsides, fields, lawns.
Characteristics: Biennial or perennial herb. Red clover reaches height of 10 inches or more, with hairy stems. Red or purple blossom with oval nectar sections; elongated leaves form trefoil with white vein when mature. White clover reaches height of 2 inches or more. White blossoms have dozens of nectar filled sections; round leaves form trefoil at end of stem.
Primary Uses: Culinary, medicinal, cosmetic. Leaves are eaten raw; steamed; boiled; sautéed; cooking liquid drunk. Dried and



White Clover

ground for flour. Flowers eaten raw; steamed; sautéed; fried; cooking liquid drunk. Dried for tea; used for wines. Seeds crushed for cereal; sprouted. Entire plant is steamed or boiled and used in soups and stews; cooking liquid is drunk.

Nutritional Value: High in calcium, potassium, niacin and vegetable protein.

Medicinal Value: Red clover is used as tea for cough, whooping cough; blood tonic or purifier. Clover syrup used for chest congestion and bronchitis.

Cosmetic Value: Cosmetics, facial creams, rinses, shampoos, wash for pimples, poultices for athlete's foot fungus.



Sheering Clover

Collection and Storage: Plants are most succulent in spring and early summer. Gathering a winter's supply of clover takes only a few minutes. Clover can be frozen by placing it in a single layer on freezer wrap, folding over 2 sides to hold the clover in place, and freezing. After the clover is frozen, roll the paper to make a compact package, fasten, and label. Dry seed heads separately for an attractive potpourri.

Linda Says - White clover has a particularly different flavor from red clover, with a smaller flower and leaf. The white clover leaves are easily sheared for food as they grow close to the ground in patches. One clover patch 3 feet wide will provide dozens of servings in one season. One summer I conducted an experiment. Shearing a 3-foot patch every morning for 3 weeks, I successfully fed 200 people several different dishes of clover: clover with rice or potatoes, clover casserole, breaded clover heads, clover tea, candied clover heads. The clover flowers went well in spaghetti sauce for meatballs too!



A Protection Powerhouse

Red clover borders almost every road edge. It appears to grow on all lawns, & is found in dozens of varieties throughout the world. When I discovered that the plant leaves were vegetable protein, I was ecstatic. I had been walking into town every two weeks for supplies, including cheese. My biggest nutritional concerns were protein and calcium,. & then I read that clover has tremendous amounts of protein. Indeed, five large clover leaves provided the same amount of vegetable protein as 1 ounce of cheese. That did it! I began to put clover leaves between two pieces of whole wheat bread, calling it cheese. Within three days I was eating the leaves raw, saying "I need energy." I would forage freely on a small amount of raw leaves.

A vegetable, a tea, a vegetable flour, clover has become one of my staples. I add clover to rice dishes, simmer clover soup, & steam casseroles with clover as an ingredient.

Crabgrass

Digitaria sanguinalis L.
Grass Family, *Gramineae*



Other Names: Finger grass (Horizontalis, ischaemun (smooth); serotina (creeping); longiflora; simpsoni; filiformis, and more.)
History: Native to North America, Asia, Mediterranean and North Atlantic coast as well as Europe. A drink called Mannagrit is a popular recipe. Used in most areas of the Mediterranean as flour for pita cake.
Habitat: Lawns, roadsides, waste places, edges of fields. The large crabgrass prefers moist soil, streams, ditch banks.
Characteristics: Grasslike, many varieties reaching heights from 3 to 24 inches or more. Summer annual and perennial, the bract or seed tips may vary in amounts and thickness, as well as smooth seeds or heavy bracts.

Primary Uses: Seed bracts as well as leaves are dried and ground to flour. Used raw, steamed, boiled, sautéed, and cooking liquid drunk. Pollen used as flour; seeds are sautéed; stir-fried, or ground and used as flour.
Nutritional Value: Highly nutritious; roots rich in complex carbs.
Medicinal Value: Used as a poultice for aches and pains.
Collection and Storage: Shear bracts and leaves, as if mowing lawn. Dry thoroughly, store whole in glass. Grind to flour when needed.

Linda Says- I'll never forget the feeling when I realized that a 2-foot section of crabgrass would yield a batch of muffins every 2 weeks or so. When I read that the Bedouins pulverized crabgrass to a rough flour and made a cake the same as I did, I knew then that my cakes were a universal recipe.

Daisy

Chrysanthemum leucanthemum
Composite Family, *Asteraceae*



Other Names: She loves me, she loves me not; ox-eye daisy.
History: Native to Europe and Asia, widely naturalized throughout North America.
Habitat: Fields, roadsides, lawn, waste places.
Characteristics: Biennial herbs. White petaled flower about a long, erect stem 18 to 20 inches tall. Flower center has a yellow pebbly disk of seeds. Flower ranges from 1 1/2 to 2 inches in circumference. Petal number varies. Leaves are dark green and

irregularly lobed in a scalloped design. Smooth and succulent, they form a thick basal rosette the first year of growth, sending the stem up with flower the 2nd year.
Primary Uses: Culinary. Petals eaten raw; used as tea. Stem and leaves edible as a salad green, vegetable. Dried stems are added to soups or stews. Leaves eaten raw, put in sandwiches or soups.
Nutritional Value: Leaves very high in beta-carotene, riboflavin, niacin and potassium. Low in carbohydrates and calories. Petals are very high in beta-carotene and niacin.
Collection and Storage: Gather petals only, leaving yellow centers.
Caution: Do not eat the yellow center, as it may cause indigestion. Collect clumps of new spring leaves for salads. Chew leaves or stems while hiking for a taste treat. Dries and freezes well.

Daisy
"She loves me, she loves me not!" We all enjoy and play this game, but think of how much more fun if you popped the succulent white petals in your mouth! Why not make a treat of the petals in salad or gelatin, or even in chocolate ice cream. I have put them in popsicles for kids.

Using the petals for food became a real survival tool when I spent hours picking blueberries or raspberries. They usually grow nearby, and when I found the petals edible, I could vary my diet from fruit to flowers. Then I discovered that daisy leaves are fantastic. From that moment on, Todd and I ate them while walking, playing, and working in the mountains of the Adirondacks. I can never look at a daisy and not remember the freedom of this period of my life!

Dandelion

Taraxacum officinale
Composite Family, *Asteraceae*



Other Names: Dent-de-lion, wild spinach, wild lettuce, red-seeded dandelion, wasanswak (Crow Indian).
History: Probably native to Europe, but widely distributed through the world. Used by many different cultures. Cultivated on the Mediterranean island of Minorca after locusts destroyed vegetation.
Habitat: Moist areas, lawns, roadsides, fields.
Characteristics: Perennial herb. Grows to height of 2 inches or more; clumped. Leaves saw-toothed; whorl from center. Yellow sectioned flowers mature to fluffy “pompoms” with seeds that blow in the wind.
Primary Uses: Culinary, medicinal. Early roots are eaten raw. Dried whole roots are pulverized or boiled. Leaves are eaten raw; steamed; boiled; sautéed; cooking liquid is drunk. Steeped for tea. Dried and ground for nutrient additive or flour. Flowers are eaten raw; sautéed; fried. Used for wine. Entire plant is steamed; boiled; sautéed; cooking liquid is drunk. Used in soups and stews.
Nutritional Value: High in protein, calcium, and vitamin A.
Medicinal Value: Use as tea for jaundice and other liver problems; a tonic, blood cleanser, purifier, stomatic, diuretic, laxative; for swellings, sores. Also effective for nervousness and hypochondria: an effective relaxant.



To reduce swelling and cleanse a wound, grind fresh leaves to a paste and spread over wound or fracture. Use dandelions as a bandage to bind wounds. Use as blood tonic by pulverizing either roots or leaves and mix 50-50 with whole wheat or rice flour. Make bread.

Cosmetic Value: Facials, wash for eczema; any external cosmetic skin treatments.

Collection and Storage: Gather flower heads in season. Yellow petals are very sweet. Twist the green base from the yellow flower petals and eat the petals raw. Roots can be dug year-round, even under the snow. Young leaves and stems are tastiest. Collect roots in early spring when most succulent and not bitter; dry and grind to coffee. Roots may be stored in strips (see page 30 for illustration on stripping roots). Store whole roots in paper bags in a warm, dry area.

Leaves
- 1/4 grocery-size bag = 8 cups leaves
- 8 cups raw leaves = 10 servings
- 8 cups steamed and frozen leaves = 4 servings
- 8 cups fresh leaves, dried on a screen = 1/2 cup flour

Flowers
- 1/4 grocery-size paper bag = 8 to 10 meals

Linda Says- Security—that is the only word I use for dandelion. Dandelion is always there, even frozen green under the snow, easily found, along edges of tree trunks or rocks. Ruth Spring taught me to core down the root, then peel the white succulent core for the first taste of a spring thaw. "As a tonic," she said, "the body will grab at it."

The former mayor of Vineland, New Jersey, started a large business growing and harvesting dandelions for the gourmet markets of Europe. The annual dandelion dinner he gave was nothing short of a gala feast.

Dock

Rumex crispus
Buckwheat Family, *Portulaceae*



Other Names: Curly dock, yellow dock.
History: Native to Europe, widespread in North America. Pima Indians use roots, stems, and leaves.
Habitat: Fields, roadsides, rich soil.
Characteristics: Perennial herb. Grows to height of 14 inches, may reach 24 inches. Elongated leaves curl; seeds turn dark brown when dry.
Primary Uses: Culinary, medicinal, cosmetic. Roots cooked as carrot. Leaves eaten raw; steamed; boiled; sautéed; cooking liquid is drunk. Stems eaten raw or cooked. Seeds ground for flour. Entire plant makes excellent yellow dye. Seeds are a decorative craft material, useful in flower arranging.
Nutritional Value: High in vitamin A, minerals, and protein.
Medicinal Value: Roots used for skin infections or itches, and for healing wounds and sores. Stems and roots are laxative and tonic. Pulp of leaves used as a poultice for bruises, burns, and swellings. Boiled and mashed, bound on boils and swellings.
Collection and Storage: You can spot dock easily in a field by its deep chocolate-colored tops. Several stands of dock are often in a field; the dark brown tops stand out in peaked clusters, especially above a winter's snow. Gather seeds when rust brown. Leaves are collected in early spring or when young. Roots are gathered in early spring for medicinal storage. Dries and freezes well.

The Department of Agriculture suggests collecting roots in the late summer and splitting while green for drying and grinding.

Linda Says- I remember the summer Ruth Spring showed me dock. When I saw how many thick clusters of seeds there were on just one plant, I decided dock would be a main source of flour. I am constantly amazed at how many quarts of flour can be derived from one clump of dock. Because of the high vitamin A content of curly dock, this flour should be used sparingly only with another flour such as whole wheat. Curly dock seeds have 20,000 units of vitamin A per 1/2 cup. A few teaspoons in your recipe is adequate for vitamin content.

Evening Primrose

Oenothera biennis
Evening Primrose Family,
Onagraceae



Other Names: Meadow rose.
History: Native to North Americas. Used by Native Americans.
Habitat: Gravelly dry soil, roadsides, waste areas.
Characteristics: Biennial night-flowering herb. Has pinwheel rosette of leaves that are toothless with whitish midrib. Basal leaves brown in spring, hugging the ground. Stalk shoots upward, with 4-petaled flowers on top of multiple branches. With 4 petals, the flowers are not unlike a rose, exceptionally sweet smelling and waxy. Hairy stem. Between stalk bottom and root underground is a strip of red or pink to scarlet indicative of primrose. Single root with many hair-like extensions.
Primary Uses: Culinary, medicinal, cosmetic. Young leaves are eaten as a vegetable or salads. Dried and frozen for storage. Buds edible before flowering. Seeds edible. Roots look and taste like parsnip (peppery flavored), may be eaten raw or cooked.

Dried for long-term storage.
Medicinal Value: Evening primrose oil used for soothing the central nervous system as well as relieving stomach and gastrointestinal stress. See below.
Cosmetic Value: Creams, skin preparations.
Collection and Storage: Pick young leaves in early spring. Pinch flowers off stem. Dig roots and scrub. Roots can be dug in winter.

Linda Says- Rumor has it that oil from this delectable wildflower is one of the most expensive, as well as most beneficial for human beings. Its composition close to the constituents of mother's milk, evening primrose offers many medicinal remedies.

I began picking and eating the flowers in quantity. I use olive oil to make evening primrose oil, just press the flowers into a small jar and add boiling olive oil. (Be careful to avoid splatters.) Press the flowers down with a spoon and pour in oil until flowers are saturated and air has bubbled up. Cap tightly and shake every day or so for a week. Strain the oil and refrigerate. It's a potent tonic when added to your salads.

Filarie

Erodium circutarium
Cranesbill Family, *Geraniaceae*



Other Names: alfilaree, alfilaria, redstem, stork's bill, pin clover.
History: Native to Europe and probably introduced to North America by the Spaniards; Native American use.

Habitat: Dry areas, desert areas with a little moisture, particularly clay soils.

Characteristics: Annual or biennial, reproducing via seeds at the base of stork's bill-shaped shoots. Flowers on long stalks shoot up from fern-like leaves lying in thick mats. Minute hair on stalks and stems. Stalks have purple flowers, then seed buds. Seed has a corkscrew tail, driving it into the soil for propagation.

Primary Uses: Culinary. Fern-like leaves are eaten raw like celery. Used in soups, stems, sandwiches. May be steamed and frozen for summer vegetable. Roots are like celery, delicious raw or in soups; steamed or pickled. Both roots and leaves are dried and ground to a flour.

Nutritional Value: Leaves are very high in calcium, potassium and beta carotene, niacin and vitamin C.

Collection and Storage: In the westI used a gloved hand, taking the most succulent leaves only up into your hand, pulling them upwards, and with a twist of your wrist, twist the leaves off the root. This leaves the root and flower stems.

Caution: Do not ingest flowers or stork's bill fruits, as they are known to be toxic. It is generally safe to ingest a large amount of filarie leaves if the vein in the center of the leaf is not pink or red. Filarie tends to pick up nitrates from the desert soil, turning the vein of the leaf as well as the stem of the flower red. Look carefully for healthy plants, green and luscious before eating.



Linda Says- A winter's filarie sandwich has become a ritual. The greens appear after the rains on the Arizona desert. I clip them with scissors, wash them, and make a mild, nutritious raw vegetable served with a dip. Pickled in apple cider vinegar, they make a delicious salad ingredient.

Fireweed

Epilobium angustifolium
Evening-Primrose Family,
Onagraceae



Other Names: Great willow herb, deerthorn, wild asparagus, wickup ocacadii (Potawatomi).
History: Native to North America. Staple food in Northern Asia and Iceland. First plant to re-seed itself after all wars of wasteland or defoliation. Grew on sides of Mt. St. Helen 3 weeks after volcano covered area in potash. Grows back first after fires. The Potawatomi Indians used its root as a soap by lathering it in water.
Habitat: Areas where there has been fire, waste areas, areas of regrowth, roadsides, fields.
Characteristics: Perennial herb with unbranched tall spikes up to 2-6 feet and willowlike. Spikes not unlike upside down asparagus. Stems hollow with white pith.
Primary Uses: Culinary. Pith is eaten raw or boiled; used in soups and stews; steeped for tea. Buds are eaten like asparagus; tips picked before they flower are eaten raw or used in soups and stews. Flowers may be eaten, but buds are more palatable. Young leaves eaten raw or prepared as spinach; dried for tea. The fluff makes excellent winter tinder; used as cotton.
Nutritional Value: Exceptionally high in beta carotene and potassium as well as most minerals.
Collection and Storage: Perennial herb. Reaches height of 2 feet or more. Spike of magenta or pink 4-petaled flowers; elongated top of buds.

Linda Says- The best way to see the old fireweed beds is when it is snowy. The plants' spiral top, tall and fuzzy, swirls with cotton fuzz. In season, fireweed shows a magenta top with flowers. Above the flowers are asparagus-like tips that I harvest as a delicious vegetable. They taste best fresh.

Goldenrod



Solidago odora
Sunflower Family, *Compositae*

Other Names: Golden elixir, sweet goldenrod, asawush (Ojibive Indians). Poco moonshine is yet another species, *augustifolum*.
History: Native of North America. Used by pioneers. Ojibive Indians used it in tea as a carminative, antispasmodic, and intestinal astringent (Smith 1932).
Habitat: Dry, open fields, woods, road banks, pine barrens; acidic soil.
Characteristics: Perennial herb. Grows to height of 24 inches or more. Hundreds of tiny fluffy yellow flowers on top stalk. Flowers smell like anise.
Primary Uses: Culinary, medicinal, cosmetics.
Roots eaten raw; dried and pulverized for tonic powder. Stems dried for tonic nibble. Leaves picked and eaten fresh. Dried for tonic tea. Stems, buds, flowers, and seeds eaten or used as tea.
Medicinal Value: Energizer and tonic. As a tea, for diarrhea, bladder tone, colic. Mashed leaves for a poultice, raw flowers

chewed for sore throat. Leaves and roots are tonic for colds and upper respiratory problems. Powdered leaves are sprinkled in sores and wounds because goldenrod is an astringent. Helps stop internal hemorrhaging as a strong tea.

Cosmetic Value: Shampoo, astringent with diaphoretic qualities; aromatic and stimulating.

Collection and Storage: Gather the entire plant, bundle it, and hang it upside down until dry in a warm, airy place out of the sunlight. The bundles are dry when the stems snap easily. Place a clean sheet under the bundles. Hand strip and gather up the bounty. To store a winter's supply of tea, gather the stripped and dried goldenrod parts in a pillowcase or other cloth bag, then wring to crush the leaves. A handful of flowers and leaves will brew 6 to 8 cups of tea.

Caution: Do not use as bulk food. Use sparingly for medicinal purposes.

Linda Says- So easy to gather and bundle, the golden elixir grows thick and bountiful. Although its tonic qualities are present any time, the goodness is strongest just before the pollen forms in the flower head. If you choose to collect at this time, watch out for the bees! They love the flowers and frequently hide in the caps or rest in them.

For a perfect yellow tea, snip off the blossoms. Dry separately on a screen and store in glass bottles.

Grape

Vitis arizonica (Western)
Vitis labrusca (Eastern)
Vitis rotundifolia (South)
Vitis Family, *Vitacere*



Other Names: Wild grape.
History: Native to North America.
Habitat: Thickets, edges of woods.
Characteristics: Deciduous vine. Forked tendrils at end and joints of high-climbing vines. Branches have a brown pith. Leaves tiny to large, coarse, saw-toothed, lobed, heart shaped. Fruit round, fleshy. One to 4 pear-shaped seeds in several colors from purple or black to amber.
Primary Uses: Culinary. Fruit cooked to make jellies, jams, juice, syrups, and flavorings. Leaves are used as a wrapper for main dishes. Leaves may be eaten raw, stir-fried, or steamed. Tendrils are pickled.
Nutritional Value: Fruit is high in vitamin C.
Collection and Storage: Pick tendrils all year; clip with scissors. Grapes in season may be gathered by hand. Young leaves are picked at any time. Freeze leaves for stuffing; laying between sheets of wax paper, folding paper after each layer.

Linda Says- I wandered the hills of Syracuse, New York, with a famous gourmet cook looking for grape tendrils. There they were, curling down from yards of grape vines. I rolled and sniffed them first for their characteristic grape smell, then used scissors to clip hundreds of tendrils into a bowl. Later, my friend and I stir-fried the tendrils into delicacies, as well as froze them for use later in the year. The tendrils make me pucker.

Lamb's Quarters

Chenopodium album
Goosefoot Family, *Chenopodiaceae*



Other Names: Pigweed, goosefoot, wild spinach, chiciquelite, hwahai (Pima Indian). (Toakush Crow Indian).
History: Used in most countries and most civilizations. Recent archaeological findings in Denmark show it was an early food there. Now cultivated by Navaho and Mexicans. The Zapotec Indians use the flour as a staple food.
Habitat: Native to North America, Europe, Asia.
Characteristics: Annual herb. Grows to height of 18 inches or more. Leaf shaped like goose's foot, dark green with whitish underlay. New leaves have white or lavender-tinged powder near center whorl. Leaf beads with water when wet. Green seed-like flower clusters.
Primary Uses: Culinary, medicinal. Young shoots are boiled, cooking water is drunk. Leaves are spinach-like; eaten raw; steamed; boiled; sautéed; cooking liquid is drunk. Dried and ground for flour. Flower and seeds are ground for mush or cereal; sprouted, dried and ground for flour. Seed is excellent food for wild birds and canaries. Roots can be used as a soap substitute; wet hands and rub cleaned root. Young stems eaten raw or cooked.
Nutritional Value: High in nutrition, vitamins, calcium.
Medicinal Value: All parts used as a poultice for swelling, rheumatism, arthritis. Chewed raw for toothaches. Also, gelatin capsules filled with lamb's quarters are a potent vitamin.

Collection and Storage: Harvest large amounts with a long knife or small amounts with scissors and bag. Hang large bunches upside down to dry. When crispy dry store in glass for longevity or steam and freeze.

- 1 large bunch (stems bunched together to about 1 inch thickness) = 2 cups flour when dried and stripped.
- 1 large screen of leaves and seeds = 2 cups flour
- 1 large bunch chopped and steamed = approx. 12 to 14 sandwich sized plastic bags.

Caution: The lamb's quarters' leaf resembles poisonous, malodorous look-alike, nettleleaf goosefoot, which has a tough cardboard-like leaf. Crush and smell leaf. The rank odor will tell you immediately if you have this look-alike. Identify carefully. See page 294.

Comments: Chenopodium ambrosiodes; also known as Jerusalem oak, wormseed or Mexican goosefoot, is a type of lamb's quarters found in Arizona and other Western states. A sprig added to beans renders them anti-flatulent.

Lamb's Quarters

During World War II, the US government gave out information that garden weeds were good food. The top weeds included amaranth and lamb's quarters. Not only are these plants nutritious, but they are not bothered by cutworms or aphids.

Lamb's quarters grows phenomenally fast. In fact, just one plant yields all I need for a summer's meals for me! To gather, I pinch the tops and tips of each branch. I wait two or three days, then repeat; for each top taken, two or three will grow in its place. So just a few plants can yield an entire fall and winter supply.

Dried leaves make a delicious and nutritious flour. Mix it with a bit of water to make a tortilla, or combine with wheat flour to make an enriched pita bread or fry bread.

To make the flour, I pound the dried leaves with my favorite rock, but you can feed the leaves through a hand grinder for the same results. You can also place the crispy dried leaves in a pillow case and wring.

Malva

Malva Neglecta
Mallow family, *Malvaceae*



Other Names:
Cheeseweed, button weed, cheeses, mallow.

History: Introduced from Europe; sold in the marketplaces of China and Japan.

Habitat: Fields, roadsides, waste areas.

Characteristics: Perennial or biennial herb. A stout, bushy plant branched and spreading from its base. Reaches height from 2 feet to 4 feet.

Primary Uses: Culinary, medicinal. Leaves used in soups, main dishes, stir-fried. Stems are vegetable stir-fried in garlic and olive oil. Flowers, buds and stems, and cheeses (seed cases) are all edible raw, steamed, sautéed, or dried and stored.

Nutritional Value: Very high in iron and calcium.

Medicinal Value: A mucilagenic, increasing the flow of saliva. Chewed for sore throats, upper respiratory problems.

Collection and Storage: Clip whole stems, pick off buds and leaves. Cut stems into sections for stir-fry or freezing. Cut leaves as large as you can for rolling around tofu, fried beans, potatoes, rice. Collect in bunches for abundance. Do not pick malva with red stems. Red stems may depict nitrate from the soil; pick fresh young plants when possible. Mince malva leaves and marinate in oil and vinegar before cooking.

Add 1 cup salsa to ice cube trays, a spoonful of fried beans, roll tightly in malva leaves and freeze. Easy to defrost and bake at a later date. (See recipe for Malva Rice Roll-Ups.)



Stuffed Malva Leaves

Linda Says- Malva has cheese-wheel seeds. I love to gather them and dry them for potato salads, stir-fries, or eat them as they are.

Seeds are dried to use as "nuts" in winter. Large leaves used for wrapping foods. Stems are used for delicate sautéed vegetable, and younger leaves for salads and sandwiches. Once dried, all parts of malva can be ground for flour! I cook with malva flour a lot. As a general rule, I use 1 cup malva flour to 3 cups of wheat or other gluten flour.

Maple

Aceraceae Family



Other Names: Sugar, silver, soft, rock and red maple.
History: Many species native to United States. Native Americans were early users of the tree's products. Chippewa Indians pressed the seeds into cakes calling them maple cakes.
Habitat: All environments except lower Rocky Mountains and the Plains states; areas with rich, well drained soil.
Characteristics: Deciduous tree. Most leaves have 5 pointed lobes, are irregular toothed, and are opposite on branches. Leaves turn golden yellow to scarlet in early fall. Seeds have brown wings and occur in pairs. All have sweet sap to a varying degree.
Primary Uses: Culinary. Sap used for syrup, candy, flavorings. Seeds eaten raw or pressed into cakes. Twigs and young leaves used for tea and emergency food.
Nutritional Value: Leaves high in minerals, beta carotene and vegetable protein.
Collection and Storage: Cut the seed off the wing with scissors, dry on a screen, and put through the grinder. Twigs, inner bark, and sap can be collected and used in winter. Collections of twigs is simple because they snap off easily by hand. Syrup collection is through a tap drilled into tree using a collector pail. (Author used plastic milk bottles from a nearby dump.) Please refer to other references to details of syrup collection.



Maples in Winter

I was relaxing in front of a fire in the crispness of early morning when Crack! A sound like an explosion came from behind me in the woods. I scanned the trees and saw that a maple tree had "exploded." The explosion caused a big crack in the tree about three feet high. When a winter wind stirs the frozen trees, they sometimes appear to burst vertically. When it was 40 degrees below zero at night, I lay awake and listened to trees explode. That's a true wilderness thermometer!

Meadowsweet

Filipendula ulmaria
Rose Family, *Rosaceae*



Other Names: Queen-of-the-meadow, meadow sweet.
History: Native to North America, used by native Americans.
Habitat: Meadows, old pastures from Nova Scotia and New Brunswick to North Carolina and west to Minnesota and Arkansas.
Characteristics: Perennial herb. Bush with symmetrical branches, 30 inches long or more. Flower spires, shaped like church steeples, are white and fluffy in spring. The steeples turn seedy and chocolate brown in the winter, giving it a characteristic look against the snow. Twigs have hundreds of tiny nodes between the branches and are characteristic of meadowsweet, not other hardhacks.
Primary Uses: Culinary. Twigs chewed or steeped as tea. Dried and stored for winter. Flowers are dried as a sugar substitute; sweet enough for teas & cereals, but flower must be dried. Used in wines. Seeds are also edible. Leaves used for tea.
Nutritional Value: High in vitamins and minerals. Also high in beta carotene, potassium, and niacin.
Medicinal Value: Mineral tonic. Flu and Rheumatic pains. (contains salicylates.) Twigs, inner bark and sap can be used in winter.
Collection and Storage: Collect twigs by breaking off when young and store in paper bag. Collect flowers by pinching off easily with fingers. Dry on screens.

☕ 🥤 🍷

Linda Says- Shearing meadowsweet flowers with scissors is by far the quickest way to harvest them. Pick with both hands, breaking brittle twigs. Swing a handful from your right hand up under your left armpit. Hold tight and continue until bunch is cumbersome, then tie and set aside. Gather bunches and tie together.

Milk Thistle

Silybum marianum
Composite Family,
Compositae



Other Names: Horse thistle, marian, holy thistle.
History: Native to the Mediterranean, also hot regions of North America, including Southern Arizona. Cultivated and dried in Europe. Used by Native Americans.
Habitat: In west, commonly found in ditches; waste places.
Characteristics: Annual herb. Grows 3 to 6 feet tall. White milk splotches on prickly leaves, named “Mother Mary’s milk.” Large prickly, fuzzy thistle flower with long prickers from central stem. Vigorous grower; 1 plant will quickly spread to a bed 3 feet around.
Primary Uses: Culinary, medicinal. Young leaves parboiled to remove prickers, for soup or stir-fry. Cooking liquid is drunk. Leaves dried and ground for extract.
Nutritional Value: High in vitamins and minerals. High in phosphorous, vitamin K, and thiamin and niacin.
Medicinal Value: For treatment of liver disease. A valuable source of the chemical silymarin. Mineral tonic, flu and rheumatic pains (contains salycylates).
Collection and Storage: Use a long blade or sharp machete to cut off prickly leaves. Extract young leaves from center of plant with long knife and tongs. Plant tends to pull up nitrates from the soil, so harvest young leaves. I dry the leaves by placing them face down on a screen. You can handle prickly leaf safely by pinching the back vein of the leaf.

Linda Says- The gigantic prickles on the milk thistle once scared me. I was aware of the multiple benefits of these ominous leaves, but how to gather them? Gloves did not help. The best tools are a long-handled tongs and a long kitchen knife. Slice the leaf off with the knife and pick it up with your tongs and bag it. Washing them becomes the next challenge, and cooking to a safe texture is yet another. The leaves fairly "melt" in cooking; even the barbs become tender if the leaf is simmered long enough. I cut off the barbs with scissors, then simmer a few minutes and drink the broth.



Milk Thistle

Milkweed

Asclepias species
Milkweed Family,
Aslepiadaceae



Other Names: Silkweed, butterfly weed, cotton tree, pleurisy root.

History: Native perennial with many species. Known since ancient times, used during World War II in rubber experiments, fluff considered for life preserver stuffing.

Habitat: Fields, roadsides, gardens.

Characteristics: Perennial herb. Single stem 2 to 5 feet high. Leaves opposite in pairs from 4 to 9 inches long. Heavily veined, smooth leaf with white milky sap throughout plant. Flowers are round clusters of pleasantly fragrant single stars at end of dozens of branches, making a round ball of blossoms. Flowers give rise to a green bristly pod, in which fluff-bearing seeds form. White sap exudes from all parts, including roots.

Primary Uses: Culinary and medicinal. Flowers and seeds are edible. New sprouts are used as vegetable, cooked. Young leaves and buds are cooked as vegetable. Stalks are peeled for strong fibers; used for fishing line, especially if braided. Bark is braided into ropes of varying thickness. Pods picked young are used in soups and stews.

Nutritional Value: Shoots high in niacin, potassium and vegetable protein.

Medicinal Value: Milky sap used in wart removal.

Collection and Storage: Break off buds, young leaves, and flowers by hand. Use a paper bag. The milk tends to turn the plant sour if kept in plastic bags. Strip stem fibers and braid for emergency fishing line or rope, as well as shoelaces (in the wild).

As a vegetable; young leaves and buds can be dried or frozen. Sprouts can be frozen. Buds should be simmered twice for 3 to 4 minutes, changing water in between. Roll any wide leaf with goodies and bake in salsa for a wild Mexican delight.



Wild Mexican delight!

Milkweed Abundance

Gathering milkweed is by far the easiest way to find food for my family. The abundant pebbly tops beckon to me. I move from every fourth plant or so with ease. I fill a large bag and then go to the Cedar River log bridge to wash them. The time spent swishing the milkweed buds in the cool water are some of the most precious moments of homesteading.

Mint

Mentha species
Labiatae family



Other Names: Spearmint, peppermint, horehound, giant hyssop, wild bergamont, bee balm, oswego tea.
History: Mostly native to North America and widely distributed throughout the world. Used since ancient times in scents, cosmetics, flavorings, food and medicines.
Habitat: Found in most areas from swamps to fields, gardens to lawns.
Characteristics: Perennial herb. All mints are aromatic. Most mints have square stems; leaves are opposite with usual unevenly saw-toothed edge. Prominent veins; leaves may be smooth or coarse, sharply pointed in most species. Characteristic fuzzy leaves in wild varieties, especially swamp mints. Plants range from 5 inches to 2 feet high.
Primary Uses: Culinary, medicinal, cosmetic. Leaves, flowers, stems and roots eaten raw in salads, candies; leaves steeped for tea. Flowers dried for teas. Whole plant ground for aromatic tea.
Nutritional Value: High in vitamin C and iron.





Medicinal Value: Well known as a stomachic, or stomach soother. Also used for insomnia, stomach ache, fevers and colds.
Cosmetic Value: Aromatic stimulant, astringent, restorative; used for scents, in soups and potpourris.
Collection and Storage: Cut stems where desired, as plant rejuvenates quickly. I used to pick and wind one plant into a bunch, then string bunches together for ease of harvesting as well as drying. Also, freeze flowers in ice for pretty edible cubes. Mints transplant easily and have characteristic prolific growth in an herb garden.

Linda Says- The camp always smelled good when the mint was drying for winter. Our family eats the leaves often. Since a leaf holds a whopping amount of iron, it is understandable why I eat at least 1/2 cupful every time I go out to pick it.

Mint Aromas

Lightning flashing all around me, I lay prostrate in a large patch of mint. The air was blue-black. Tired and clutching my bundle of freshly picked plants, I almost welcomed the respite, though I was a bit nervous.

Mint picking is always done around swamps, streams, and riverbeds, and this day I was able to gather a six-week supply before a typical Adirondack thunderstorm kept me waiting for 30 minutes.

Mullein

Verbascum thapsus
Snapdragon Family,
Scrophulariaceae



Other Names: Candlewick, flannel leaf, Aaron's rod, feltwort, hare's beard; velvet plant, velvet dock, blanket leaf.
History: Native to Europe, naturalized throughout pasture land of United States. Plant also known in Roman and Greek history; Quakers, Native Americans.
Habitat: Waste wet areas as well as roadsides, gravel-filled fields.
Characteristics: Biennial herb. Tall spikes with yellow flowers, velvety leaves whirl around spike. Grows up to 10 feet tall. Produces basal leaves in first year, then spike the second year. Leaves furry or velvety, ranging from 3 inches to 2 feet long. Flowers are succulent and sweet smelling, attracting bees.
Primary Uses: Culinary, medicinal, cosmetic. Root used for medicinal tea, leaves and flowers dried for tea and medicine. A normal root, up to 1 foot long, may be reused dozens of times. I put large leaves in my sneakers when walking long distances; they help soothe tired feet, and prevent blisters. Native Americans put leaves on cradle boards to heal elbows and shoulder blades. Antiseptic, mullein is invaluable for inflammation.
Medicinal Value: All parts of mullein, from single tap root to flowers have an antihistamine quality among other qualities. (See chart page 53 for comparing mullein to aloe vera.)
Cosmetic Value: Astringent and emollient properties, decoction of flowers for hair rinses to lighten hair color; flowers steeped in olive oil used as application for sores or massaging oils.

Collection and Storage: Second-year leaves may be harvested from the spike individually, flowers harvested individually, and root harvested at any time, any season. I harvest single leaves, roll them up, and dry them on a screen. These rolls may be kept in glass containers and taken along when hiking.

Floated in olive oil, mullein wicks will burn cleanly & clearly for 3 hours or more or until the olive oil is used up. Pour a tablespoon of olive oil on the top of a glass of water. (You must float the mullein by crossing 2 toothpicks, poking the ends of the toothpicks in a tiny piece of foam or buoyant material.) Place the wick in the center, letting a piece touch the oil you have poured on the top of the water.



Figure 48 Rolling and Drying Mullein leaves.

Linda Says- I used mullein for lamp wicks when snowed in. A small piece of the flannel leaf cut to size, dried, and soaked in oil will burn for quite a while.

Mullein

I feel as if the 6-foot high plant were a person. I address the mullein and ask to pick its flannel leaves and flowers!

One summer, my Girl Scout Troop was horseback riding on a field trip in Indian Lake, New York. One of the horses moved too close to the one in front and the forward horse kicked, clipping the child on the ankle. It was obvious she had a bad injury. Removing her shoe, I shouted to get mullein, quick! The scouts came running with fresh mullein. "Roll the leaves and crush them quickly with a rock, girls." Poultices were made and applied on the swollen ankle. The mullein stalks became splints and the leaves became bandages until we could get the small scout to a hospital. Soon thereafter a doctor called to ask "What was that plant around the scout's ankle? She had a chip fracture but no swelling or pain!" Mullein, sir!

Mustard

Brassica species
Mustard Family, *Brassicerceae*



Other Names: Charlock mustard, field mustard, yellow mustard.
History: Native to Europe, pasture land in North America. Used medicinally in Greek, Anglo-Saxon history. A pot herb in English history.
Habitat: Fields, roadsides in cooler regions.
Characteristics: Annual herb. Grows to height of 10 feet or more. Leaves rounded, with extra protuberances of tiny leaves below main part of leaf. Crushed leaf yields herby pungent smell. Four-petaled yellow flower; petals in form of cross. Black seeds in pod.
Primary Uses: Culinary. Stems used raw as pungent spice. Leaves all eaten raw, used as pungent spice; steamed, boiled in soups, stews. Flowers are eaten raw; steamed. Seeds dried and used as spice; ground for mustard.
Nutritional Value: High in beta-carotene, minerals, vegetable protein.
Medical Value: Dried leaves and flowers used as a poultice, or mustard plaster for respiratory distress.
Collection and Storage: Collect young leaves by snipping off stalk with fingers. Collect pods separately in season when seeds are mature, pods almost dry.

Linda Says- When eating mustard greens boil in water for 15-20 minutes. Mustard is a very pungent vegetable.



Mustard

As soon as the temperature rose to between 32 and 40 degrees, I would make a beeline to the back of Alice and Walt Sherman's barn. The mustard plants were always green, growing beneath the snow against the warm barn boards. There are no words to describe the taste of the first mustard leaves of the season. My body fairly roars with energy for days to follow!

Nettles

Urtica species
Urticaceae Family



Other Names: Stinging, slender, great, dwarf, nettle.
History: Native to Europe, widely naturalized in North America. Used worldwide.
Habitat: Fields, fertile soil from Alaska throughout continental US.
Characteristics: Perennial herb. Leafy plant. Leaves opposite in pairs, coarsely veined, oblong tapered to tip with rough, sharp saw-toothed edges. Entire plant fuzzy with tiny stinging bristles or minute hairs. Flowers are tiny green seed-like clusters between stalk and branches.
Primary Uses: Culinary, medicinal, cosmetic. Leaves and flowers boiled for soups and stews, cooked in stir-fries. Seeds are used in herbal teas. Excellent tea!
Nutritional Value: High in protein, iron and vitamin C.
Medicinal Value: Tea well known as a nutritious restorative tonic.
Cosmetic Value: Commercial uses: nettle shampoo, herb wraps.
Collection and Storage: Use leather gloves when collecting nettles. When harvesting for vegetable, hold a bag or bowl under separate leaves and clip off with a pair of scissors. A few plants sustain a whole family, since several nettle leaves grow where pruned.

Clip seeds separately if desired, plant will continue to produce until mature. Place nettles in water to simmer away hair and leave a nutritious main dish.



Linda says- I can still feel that prickly burn on my leg from each tiny hair as I approach the tall, stately plants. I learned my lesson. Blessing the "armored" leaves, I soon practiced safe collection. My young scout troop once gathered a bunch of nettles and presented a "bouquet" to Utica's city scouts; I'm sure their lesson became the same painful memory.

Phragmities

Phragmities communis
Grass Family, *Graminae*



Other Names: Reed, giant reed.
History: Native to Europe and North America. An ancient food, craft material, fiber. The Gosiute Indians gathered a sweet secretion formed on the leaves by aphids and used it as sugar (Chamberlain 1911). The Panamint Indians dried the entire reed, ground it, and sifted out the flour (Colville 1892). This moist and sticky substance was then set near a fire until it swelled and browned, when it would be eaten like taffy. The best time to gather the culms (stalks) was spring.
Habitat: Grows throughout the United States except inland areas of South Atlantic and south-central states; also Europe, Asia. Likes marshes, swamps, wet areas, roadsides.
Characteristics: Tall, reed-like stalks with feathery seed tips. Up to 6-8 feet tall.
Primary Uses: Culinary. Stalks are dried and ground to flour. Gummy substance in the stalk can be used as gum or in drinks. Stems woven for mats, bedding, thatching, grass huts. Excellent tinder. Fibers in stalk made into ropes by twisting together. Seed heads are made into a gruel, cereal, or flour. Used in cellulose, arrow shafts. If seeds are not present, chaff is ground into flour. Roots or rhizome (underground stems) are gathered and ground into flour. Eaten raw, roasted, or boiled into a sweet, gummy confection not unlike candy or marshmallow.
Collection and Storage: Study the cycle of head (seed) maturation. There is a 2-week period when seed head is full and ripe. Past that stage the seeds drop and blow away. Clip heads with scissors in the middle of summer, before seeds mature and fall out of seed head.
Caution: The water in which phragmities grows is often polluted, so test the water before eating the plant.





Linda says- Imagine my surprise when told that the waving reed was edible and could be ground to flour! It wasn't long before I began to experiment. The thought that such a tremendous proportions of the world was home to this plant, but few people were baking with it became another reason for this book. (The water in which phragmities grows is often polluted, so test the water before eating the plant.)

Pine

Pinus species
Pine Family, *Pinaceae*



Other Names: Too numerous to mention, but including white pine in East and pinyon in West.
History: Native to most parts of the world. Used by Native Americans.
Habitat: Woods, forests, landscaped area; soil varies from dry to moist.
Characteristics: Evergreen tree. Cone-bearing. Needles vary in length, usually long and slender occurring along the twigs. Bundles of 2 to 5 needles common. (White pine with 5 needles shown in picture.)
Primary Uses: Culinary, medicinal, cosmetic. Needles eaten raw or cooked as vegetable; tea, flour. Catkins eaten as candy; raw, dried for tea, salads. Cone and nuts (seeds) are eaten as snack; ingredient in baked goods. Bark is emergency food, roots are eaten raw, steeped for tea. Sap has medicinal application for small cuts, scrapes, blisters.
Nutritional Value: High in Vitamin C.
Medicinal Value: Colds, flu; as a tea, mixed with honey.
Cosmetic Value: Deodorant, air freshener; soaps, lotions, cleansing oils.
Collection and Storage: Gather needles, twigs, and bark. Using a knife, peel a section of bark lengthwise from a young branch; this may be chewed for a long time. (See “Peeling bark in strips” on page 31.) To harvest needles, let branches dry thoroughly

until needles fall. Gather needles in a sheet, then break up twigs into small sections. Place needles in glass jars. Preheat oven to 300 degrees, then turn off! Place jar with needles in oven and leave until the oven is cool. Cap immediately and store.
To do twigs, place them in a glass jar, leaving the cap off. Put in a turned off 300° F. oven, leaving until cool. Put in a sunny area for further drying, if needed (until they snap easily). Cap for storage.

Caution: Needles are volatile and catch fire easily.

> ***Linda says-*** Many was the time I ploughed through snowdrifts looking for meadowsweet, maple and beech twigs, and succulent fresh pine needles. Pine provides the energy to go on! It is the taste and smell of the forest. Save every bit of your Christmas tree for pine tea if it has not been sprayed or dyed a darker green.



Plantain

Plantago major (common plantain)
P. Juncoides (Long-Leafed Plantain)
Plantain Family, *Plantaginaceae*



Common Plantain

Other Names: Turnip leaf, cart-tract plant, cuckoo's bread, English plantain, goosetongue, Indian wheat, pale plantain, ribwort, rippleseed plantain, seaside plantain, seashore plantain, snake weed, soldiers herb, White man's footprint.



Long-leaf Plantain.

History: Many types native to Europe and naturalized in North America. Used as vegetable in France; cultivated in England. Some varieties native to Asia.
Habitat: Lawns, roadsides, fields, waste areas.
Characteristics: Biennial or annual herb. Turnip-like flat roundish leaves, with prominent parallel veins. Center stalk lined with seeds. Considered a pot herb in Europe, this plant has many species. Common plantain has spade-like flat leaves, whorling on the ground from a center point, with tall stalk in center with many seeds around stalk up to tip. Long-leafed plantain has long narrow leaves with heavy vein and similar texture, taste, and smell. Stalk has seeds at only top inch or so.

Primary Uses: Culinary, cosmetic. Young leaves are eaten raw or cooked. Stalks are dried for vegetable chewies. Seeds are eaten as sprouts. Entire plant is edible.
Collection and Storage: Turnip-like leaves are easily twisted from the ground by hand. The stalks are clipped and dried in a day or so. Use scissors. Leave stalks until the seeds are easily removed. Save stalks for a crispy stick food.

Linda says- The plantain leaf I eat is also a fantastic underarm deodorant! Prepare the leaves by placing 3 leaves together, then crush with a rock or hammer until the juices flow. Remove the inside leaf and wipe juice on underarm. Free supply abounds under my feet. Plantain has surrounded all the camps I have lived in throughout my homestead years.

Prickly Pear

Opuntia megacantha and other species
Cactus Family, *Cactaceae*



Other Names: Devil's tongue, beavertail, Indian fig, tuna.
History: Native to North and South America. Used by Native Americans.
Habitat: Hot, dry, well drained soil.
Characteristics: Fleshy, low-spreading cactus. Has flat stems and pads with long needles. Thorny fruits are preceded by waxy flowers, yellow or red. Fruits ripe for harvesting are yellow-green to purplish black.
Primary Uses: Culinary, cosmetic. Pads are cut up for food; strips parboiled and french-fried; simmered for hair tonic and softener. Flowers eaten raw, cooked to candy, jelly; also frozen in cubes for drinks. Buds cooked for jellies, jams, syrups, deserts, candies; juices also made. Water from fruit and young pads may be used as a liquid in an emergency. Seeds may be dried and ground to flour; used as a soup thickener.
Nutritional Value: High in carbohydrates and calories.
Medicinal Value: Pads split open for soothing gel for burns, wounds, sunburn.
Cosmetic Value: Hair tonic, softener.
Collection and Storage: Handle pads only with leather gloves and tongs. To harvest, use a long stick, handle, or shovel to knock off each pad. With a deliberate touch-and-push movement, the pads break off and fall to the ground with ease. When you pick them up, slide a board underneath or use tongs, and put them in a container. One pad is a large filet, or 2 servings. It can be cut up and frozen in cubes for drinks.





One hair rinse pad is good for several shampoos. Fruit and seed pulp also harvested with tongs. Flowers are easily removed by hand, petal at a time. Petals eaten raw, cooked to candy, jelly.

To prepare pads as poultice, hold gingerly with thumbs and forefinger. Using point of a knife, poke first, then slice carefully in half. Spread out and scrape off watery meat for use as a poultice.

Caution: Prickly pear is a protected plant. OK to harvest pads, flowers, buds as a survival food on the desert. Do not remove whole plants.



Preparing Prickly Pear.

Linda says- My personal attachment to this plant came in a way different from the usual. I led a wild food field trip to the desert in Black Canyon City. The temperature was only 90 degrees, but the sun was vicious to my fair, sensitive skin. I knew my sun block was not working so well. I scraped the needles off some prickly pear and cut the pad in half, applied the cactus meat to my sunburned face. The prickly pear and I became good friends from then on!

Purslane



Portulaca species
Purslane Family, *Portulacaceae*

Other Names: Low pigweed, pusley.
History: Native to Europe, widely naturalized in United States.
Habitat: Fertile soil, topsoil.
Characteristics: Annual herb. Prostrate peddle-shaped succulent leaves on branching fleshy vines. Forms mats in masses of growth. Five to 7 petaled tiny yellow or red flowers are prolific. Multitudes of tiny black seeds produced on each plant.
Primary Uses: Culinary. All parts edible, raw or cooked. Purslane also pickled.
Nutritional Value: Shoots contain a balance of minerals for only l6 calories per half a cup.
Medical Value: A succulent that quenches thirst as well as puts a quantity of minerals in the body of an active person. Contains a high mineral content.
Collection and Storage: Gather mats, snapping off branches, and leave root for rejuvenation. Gather succulent young branches for raw treats. Also grows well indoors.



Linda says- My first harvest of purslane yielded 34 jars of pickles. Since then I have picked and pickled virtually hundreds of jars of purslane.

Queen Anne's Lace

Daucus carota
Parsley Family,
Umbelliferae



Other Names: Wild Carrot.

History: Native to Europe, especially common in England; widespread in United States. Used by pioneers and Native Americans.

Habitat: Fields, waste areas.

Characteristics: Biennial herb. Reaches height of 2 feet or more. Carrot-like odor in stem and leaves as well as seeds. Flower clusters flat-topped, umbrella-like, lacy and often have single purple flower in the center. Old flowers "bird cage up" and turn brown. Leaves are parsley-like, feathery and smell like a carrot. All parts of stems have tiny fuzz, essential for proper identification.

Primary Uses: Culinary. Stems may be cut into sections and used for flavoring in stews & soups. Buds may be sautéed in oil.

Nutritional Value: Beta-carotene is exceptionally high, as is niacin.

Medicinal Value: The brown dried seeds are an excellent salt substitute.

Collection and Storage: Leaves are gathered in early spring and young leaves all season. Gather roots as carrots in early spring or fall; may be dug under leaves or hay even after winter snow. Gather flowers in summer. Collect seeds in fall.

Caution: Seeds of the wild carrot have a high content of vitamin A and shouldn't be eaten in excess.

Caution: Easily confused with Poison hemlock, resulting in severe burns of the fingers and hands as well as almost certain death if ingested. Check for the fuzz on the stem, as well as sandpaper-like feeling on dried stems from old dried fuzz. Use the foraging rule and crush, roll, and smell first; do not ingest. Determine the carrot smell and then look for the hair or fuzz.

Comments: In the fall, the flowers of wild carrot curl up; I call this "bird caging." At this time, I gather the seeds and a few seeds go a long way! I get a winter's supply of "salt" from a few flowers.



Queen Anne's Lace Chips

I will always remember my switch from potato chips to Queen Anne's lace flowers. In the wilderness, potato chips are a rare commodity, but Queen Anne's lace flowers crisp to a "chip" of carroty crispy flavor. I dip the flowers in hot oil and then put the brown crispy delights on hot rocks to cool. Todd loved to fly by and grab a few crispy flowers and pop them in his mouth using the stems as a handle.

Raspberry



Species
Rose Family, *Rosaceae*

Types: Cloudberry, Thimbleberry, wild red.
History: Some varieties native to North America, others naturalized from Europe, Asia. Used as a fruit in all countries where raspberries are found, especially Europe.
Habitat: Roadsides, rocky fields, thickets.
Characteristics: Hardy shrub, biennial canes from perennial roots. Varies in size to average of 5 feet high. Saw-toothed leaves in groups of 3. Round, erect stem with short thorns. Stems have a white powder on them. Flower white; fruit pebbly and red or purple when ripe, pulls away from receptacle.
Primary Uses: Culinary, medicinal, cosmetics. Early leaves used fresh or dried for tea. Buds and flowers are edible. Frozen in ice for drinks. Fruit eaten raw, cooked for jellies, jams, syrups, fresh for juices, wines. Stem peeled and chewed, tea made from young twigs.

Nutritional Value: High in vitamin C.
Medicinal Value: Tea from leaves good for control of diarrhea. Relaxes muscles of the uterus, beneficial for menstrual cramps and strengthening the reproductive system.
Cosmetic Value: Stimulating astringent in herbal hair rinses and bath mixtures.
Collection and Storage: For quick, efficient berry harvesting, hang a container around your waist and pick using both hands. When drying berries, spread a fine cloth over trays of berries to keep flies and birds away. Harvest young leaves.

Caution: Reddish-tinged mature leaves may be toxic. Use only young green leaves.



> ***Linda says-*** The Adirondacks are inundated with black bears during berry season. One time I came upon a huge mama bear lying on her back under a thicket of raspberry. She was stupefied from gorging on the fermented, overripe berries. As she rolled over, she hiccuped and burped, then waddled off. See page vii.

Rose

Rosa rugosa, R. Caroline
Rose Family, *Rosaceae*



Other Names: Garden rose, wild rose.
History: R. Caroline native to North America; R. rugosa native to Asia but naturalized in United States. The symbol of love and beauty in ancient mythology. In Middle Ages, rose was symbol of secrecy (Subrosa). Also a heraldic symbol (War of Roses). Native Americans used all parts of plant. Europe and Asia (Sturtevant).
Habitat: Meadows, fields, woods, and coastal beaches.
Characteristics: Perennial or hardy shrub. Usually 5-petal flower,

yellow, pink, red or purple. Thorny stems, particularly central stem. Fruit is called rose hip and has prominent calyx lobes.



Rose Hip.

Primary Uses: Culinary, medicinal, cosmetic. Petals eaten raw or cooked, in salads, as a garnish. Petals are used for teas for rose ice cubes or popsicles. Rosehips remain at end of stem after the petals fall off. This bulbous end is edible raw or cooked, sliced in salads. Leaves used raw in salads; dried for leaf tea. Stems peeled and brewed as tea; roots peeled and chewed; brewed as tea. Hips used in jam, jellies, tea, candy, or confections. Brewed as tea; dry and reuse, or store in glass jars. Also used in incense & lamp oil.

Nutritional Value: Rose hips are high in vitamin C.

Medicinal Value: Known to help with colds and coughs. All parts, including roots, pounded and powdered as snuff to clear sinuses. In the past, the bark was mashed and applied to boils, wounds, sores. Today, rose oil is used to soothe headaches and as a healing ointment.

Cosmetic Value: Soaps & perfumes.

Collection and Storage: Gather all parts. Early rose shoots are easily clipped with scissors. Save all parts. Leaves may be clipped at any time and wear gloves and use a canvas bag or paper bag, one for leaves, one for roses and hips. Full roses snip 1 inch below hip. Pull petals off and use hips later.

Sauté rose petals in light oil for delicious treat. Roll in confectioner’s sugar and refrigerate for candy.

Make rose oil by adding 1 ounce of rose powder (ground petals) to 4 tablespoons olive oil and store for a few weeks.



Linda says- Imagine what it's like to find yourself in a field of wild roses. Wandering among the bushes, I felt I was in the Garden of Eden. I wore gloves, dungarees and a long sleeve shirt for this experience. Nearby the Hudson River flowed past. Dragonflies and birds flew around me. When I tired of stuffing bags with petals for drying, I took a dip in the clean upper Hudson.

Saguaro

Carnegiea gigantea
Cactus Family, *Cactaceae*



Other Names: Monument of the desert.
History: Native to North American desert. Used by desert dwellers, Native Americans. Papago Indians make heavy syrup and intoxicating wines.
Habitat: Rocky, gravel soil; hills, canyons, and dry washes.
Characteristics: Treelike cactus. Has one or more founded arms extending branch-like from a single, thick trunk. Shallow root system with small roots radiating out the height of the cactus and then some; no taproot. Long thick trunk can be 2 1/2 feet wide and 50 feet high. Large, thick grooves running laterally on all parts; glochids and thick fishhook barbs on all parts of the cactus. Circle of white flowers on top branch. Fruit is egg shaped, 2 to 3 inches long.
Primary Uses: Culinary. Flower buds and seeds are eaten. Flowers are seen first, then buds with seeds inside. Fruit is eaten raw; husks and seeds are boiled, baked; fruits, husks and seeds used for syrup or jam. Dehydrated pulp used for flour, also oil, soft drinks, wine, and vinegar.
Nutritional Value: Buds, or fruits are high in niacin, fiber, carbohydrates as well as ash.
Collection and Storage: Harvest fruit in July and monthly thereafter by using a long stick to knock off bulbs. The skin splits and bark curls back when fruit is mature. May be dried for storage or be cut in half and soaked in water for about 1 hour after removing seeds.
Caution: Saguaro is a protected cactus tree. The Department of Agriculture must give permission to remove cactus from the desert. Fruits, buds may be used for food in a survival way, but permission must be noted in larger quantities. No permission will be granted to remove a rare crested specie of saguaro.



Linda says- The saguaro is a monument to desert life, protecting myriads of insects, mice, fruit-eating bats, owls, and other creatures of the desert. During a field walk with Willie Whitefeather, my Cherokee friend, I saw the buds of the giant saguaro harvested correctly. Willie fashioned the dried ribs of an old saguaro hulk together, lashed a hook-like end on the tip. The tool was 16 feet long and bent like a giant fishing rod in the desert wind. Deftly, he pulled the saguaro buds to the waiting crowd below.



"Desert Saguaros" by Paul Runyon, Linda's brother.

Sheep Sorrel



Rumex acetosella
Buckwheat Family *Polygonaceae*

Other Names: Garden sorrel, field sorrel, R. acetoea.
History: Native to Europe and Asia, naturalized throughout North America. Garden sorrel is cultivated for use as cooked green.
Habitat: Waste areas, roadsides.
Characteristics: Perennial herb. Reddish-tinged grassy tops. Mature seeds grow in spreading areas, standing out easily. The arrow shaped leaves are sour in taste.

Flowers are tiny and give way to seed quickly.
Primary Uses: Culinary. Leaves or stalks, eaten raw in salads or cooked as vegetable. Can be used in cold drinks.
Nutritional Value: High in vitamin C.
Medicinal Value: Juice has mild antiseptic effect (crush and place on wound as a poultice). Juice acts as laxative.
Collection and Storage: Use scissors and shear clumps of seeds easily, collecting in a bag or basket. Strip leaves off separately for soups, drinks. Seeds dried and stored in glass jar for use as spicy food additive.
Caution: All parts contain oxalic acid crystals. These may inhibit the absorption of calcium in the body. Place in boiling water for a minute or so to destroy the crystals.

Linda says- I was amazed to taste the arrow head shaped leaves and find they were the same bitey, sour lemony taste as wood sorrel. (See page 137.)

Shepherd's Purse

Capsella bursa-pastoris
Mustard Family, *Brassicacae*

Other Names: Heart seed, field cabbage, purse seed, pick purse.
History: Native to Europe, widely naturalized in North America. Used by Native Americans.
Habitat: Waste areas, roadsides.
Characteristics: Annual herb. Erect plant from 3 inches to 1 1/2 feet high. Slender stem comes up from a spreading rosette of leaves formed flat on the ground. Deeply lobed leaves resemble wild lettuce or dandelion, but are more symmetrical. Has small white flower



with petals only 1/12 to 1/8 inch long, jutting out from the branches on a single stalk. Flowers give rise to seeds that resemble upside-down hearts.

Primary Uses: Culinary, medicinal. Basal leaves eaten in sandwiches, salads, soups, vegetable. Stalk is stir-fried, eaten raw. Buds and flowers eaten raw. Seeds are stir-fried and used as pepper, spice, seasoning. Roots are used fresh or dried as substitute for ginger or candied in syrup.

Nutritional Value: High in vitamin K, vegetable protein, potassium, calcium as well as beta-carotene and minerals.

Medicinal Value: Dried to use as blood-clotter and valuable taken in quantity for internal bleeding.[1]

Collection and Storage: Look for upside-down heart shaped seeds to distinguish plant from other wild mustards and pepper grasses. Gather leaves at any stage. Gather seeds when ripe. Entire plant may be gathered and chopped for vegetable, as well as dried for additive. Add seed pods to soups and stews for a pepper-like flavor.

[1] (Harrington 1967)

Linda says- In the East I ate the little heart-shaped seedpods with gusto, but in the West I seek them with a vengeance. Shepherd's purse is known to help relieve strong menses and internal bleeding. According to Peter Bigfoot in his book *Arizona Wild Herbs,* pick the mature, flowering plants in the Arizona Desert foothills in springtime. Dosage: 1 teaspoon dried herb per cup of hot water. Steep 15 minutes and drink the tea cool. Take 2 or more cups full per day as needed. Drink it quickly, do not sip for best effect with internal bleeding.

Sow Thistle

Sonchus oleraceus
Composite Family, *Compositae*



Other Names: Hoitgamivakhi (Pima Indian).
History: Native to North Africa, Europe, and western Asia; introduced to the United States and now found throughout most of Arizona. Used by Native Americans as greens.
Habitat: Roadsides, damp fields, waste areas.
Characteristics: Annual herb. Dandelion-type deeply lobed leaves begin from a central stem on the ground, clasping around stalk to a sharp point, like a sow's ear. Top of stalk bears branches, at the end of each grows a yellow flower that looks somewhat like a dandelion flower. After seeding, a white fuzz appears with single seeds on the end of the fluff.
Primary Uses: Culinary. Buds, flowers, and seeds edible raw or cooked. Stems may be cut into inch long pieces with scissors and stir fried or sautéed in oil as beans. Roots may be scrubbed and stewed in crock pot. Young leaves gathered and eaten as spring green, also eaten raw. Flowers stir-fried as vegetable or dried as well as frozen.
Nutritional Value: Very high in minerals.
Medical Uses: Milk reported to be somewhat diuretic.
Collection and Storage: One may trim leaves off long stems easily by leaving plant in ground and trimming off with a long knife. Use long handled knife or scissors, and wear gloves. Cut leaves over a basket or bag. To harvest large amounts, cut 2 long goldenrod or wild lettuce stalks and lay parallel to each other. Using a gloved hand, place the thistle plants across the parallel stalks. When a bundle is accumulated, pull golden rod stalks up and wrap around. Carry by holding both ends of the goldenrod together.

Linda says- My introduction to sow thistle was an experience. Early in the morning, when the dew was still on the grass, I wandered through a field of barley grass. The sow thistle was a succulent emerald green amid the grasses. Since I carry water with me; I rinsed off the leaves and munched on the sweetest breakfast I ever had in the West.

Strawberry



Fragaria virginiana
Rose Family, *Rosaceae*

Other Names: Heartberry, wood strawberry.
History: Native to North America; Used in early European cultures, especially popular in France. Grows throughout Northern Hemisphere, excluding tropics. Native Americans steeped wild strawberries in warm water, then strained and cooled the liquid. The resulting lotion was a wash for irritations and skin ulcers.
Habitat: Fields, roadsides, meadows.
Characteristics: Low perennial, reaching height of 2 inches to 8 inches. Lobed saw-toothed basal leaves in groups of 3. Tiny, heart-shaped strawberry fruits. Small white flowers.
Primary Uses: Culinary, medicinal, cosmetic. Flowers are edible raw. Leaves eaten raw, dried for tea. Fruit eaten raw; cooked for jellies, jams, syrups; raw for juices, wines. Entire plant is steamed, boiled, used in soups and stews; cooking liquid is drunk.
Nutritional Value: Leaves and fruit high in vitamin C.
Medicinal Value: Leaves infused and used for sore throats. Juice is mixed with water for eye wash. Historically, roots are infused for gonorrhea remedy. Fruits are dried for stomach problems, diarrhea, dysentery, liver pain, jaundice. To juice, put a nylon stocking over a bowl. Place washed berries in stocking, then squeeze the juice into the bowl.
Cosmetic Value: Astringent and facial cleanser, useful for oily skin. Fruit is tartar remover for teeth; crush fruit, rub on, and rinse.

Collection and Storage: Pick fruits as you would cultivated strawberries With container around your waist, pick fruit and leaves easily using both hands.
Caution: Dry leaves thoroughly for tea. Partially dried leaves can cause a toxic reaction.



> ***Linda says-*** Picking wild strawberries in the Adirondacks is difficult because the berries are very small and they ripen in blackfly season. The hardiest folk pick them in the wee morning hours or at night or in a rain. Snapping turtles eat the berries, as do other critters. I enjoy finding berries with chunks missing, and speculate what had breakfasted before me—insect, turtle, or mouse.

Sumac

Rhus species
Cashew Family, *Anacardiaceae*



Other Names: Staghorn, smooth, scarlet, dwarf, shining, mountain, hairy, velvet, fragrant, virginian, and winged sumacs; lemonade tree.
History: Mostly native to North America. Used by Native Americans and colonists.
Habitat: Roadsides, field edges.
Characteristics: Deciduous tree or shrub. Bushes or shrubs with some varieties to height of 20 feet. Fern-like leaves 14 to 24 inches long. Flaming red fuzzy berry clusters, hairy and lemonade tasting. Stems and branches exude white milk when broken. Plants need heavy sunshine to produce berry clusters.

Primary Uses: Culinary. Flowers and seeds are the fruits. Fruits eaten raw or crushed in water as lemonade. Frozen in ice cube trays for popsicles.
Nutritional Value: High in vitamin C.
Collection and Storage: Collect fruit before completely mature, when spires turn dark red. Collect spires by breaking off stems. For tea, strain out hairs by overlapping balsam branches as a sieve or use cheesecloth. Look carefully at the whole tree to avoid accidental contact. I once pulled down a poison sumac branch growing in the midst of an edible sumac tree.

Caution: Poison sumac has white or greenish-brown clusters instead of red spires. When dried, a tan spire is evident. See Part V.

> ***Linda says-*** There is nothing more beautiful than a glass decanter filled with sumac berries. Scarlet tea! Sumac lemonade is a year-round treat. Collect and rinse the heads early in the season. Do not wait until fall, when insects have made their nests in them! Summer seed heads may be dried and stored in glass, or bagged and frozen.

Sunflower

Helianthus species
Composite Family, *Compositae*



Types: Annual, wild, Western, common, tall, giant, weak, saw-toothed, swamp, little, aspen, showy, and woodland sunflower; Marigold of Peru.
History: Native to the Americas, probably originated in Peru. Used by Native Americans.
Habitat: Widespread but more common in West. Gardens, fields, sunny open areas.

Characteristic: Annual herb. Composite flowers on plants from 3 to 14 feet high. Yellow ray flowers with purplish red to brown disk flowers in center. Stems may be smooth or hairy. Leaves opposite or alternate, characteristically narrow, long, rough, and saw-toothed.
Primary Uses: Culinary, cosmetic. Seeds crushed and boiled; oil skimmed off top and eaten. Pith edible raw and cooked in soups. Used for paper making, organic fertilizer, oil, lubricants, candles. Petals used for yellow dye.
Nutritional Value: Seeds high in protein.
Cosmetic Value: Oil, soaps.
Collection and Storage: After flower matures and petals fall off, gather seeds. Snap off dried center and dry seeds on screen, then bottle. Large heads dried in a closed paper bag will mature eventually. Scrape the heads across a sieve with holes sized such that the seeds can drop through. Place seeds on cookie sheet and roast in dry, low oven. Bottle in glass for long-term storage. Pith is collected by peeling outer fresh stem when plant is dry and pulling out white pith.

Linda says- Snapping off the tiny dried heads of desert sunflowers is fun and very profitable for my table. A few crushed heads and a bit of water yielded a nutritious gruel with an obvious energy boost. Storage is simple: I put the dried sunflower heads in a glass jar.

Thistle

Circium species
Composite Family, *Compositae*



Other Names: Bull thistle, yellow thistle, plumed thistle, swamp thistle, field thistle.
History: Native to North America. Used since colonial times and by Native Americans.

Habitat: Roadside, fields, waste areas.
Characteristics: Biennial plant with dozens of varieties. Reaches height of 2 to 6 feet. Leaves and stems have sharp spines (bulbs) on all parts. One to 3 large, purplish flower heads with spines around base produced second year.
Primary Uses: Culinary. Flowers steamed and eaten raw much like an artichoke. Leaves dried and ground to a fine, green flour. Dried leaves also used for tea. Steamed leaves eaten as a vegetable. Stems peeled, sliced, and cooked as a vegetable. Roots boiled for tea.
Nutritional Value: High in potassium, phosphorus, and vegetable protein.
Medicinal Value: Roots are used for restorative tonic. Roots can be harvested year round, but early summer is best.
Collection and Storage: Early in the spring, use a penknife to cut beneath the basal leaves as you would a head of lettuce, being careful not to disturb the root. Cut leaves off central stem, holding a bag underneath. Use tongs and strainer to wash. Dries and freezes well.

Linda says- The beginnings of a thistle plant are succulent. Its thorny whorls are clear blue-green. The trick is to get as much of the core as possible, leaving the basal root. The thistle will grow again if you carefully take the upper part of the root along with the leaves, leaving the deeper root alone. The first time I did this I wondered if it was worth the effort. Now I use tongs and a strainer, and find the preparation time negligible while the taste is lasting!

Thyme

Thymus vulgaris
Mint Family, *Labiatae*



Other Names: Bee plant, wild thyme, mountain thyme, creeping thyme.
History: Native to Europe; in North America gardens vari-

ety has expanded to woods and fields. Adapted and used by Native Americans.
Habitat: Fields, roadsides, roadbanks, lawns.
Characteristics: Woody perennial. Prostrate herb growing to height of about 4 inches. Several varieties, all with pepper-like smell. Many spikes of leaves and lavender spike flowers. Grows in thick patches.
Primary Uses: Culinary, medicinal, cosmetic. All parts edible. Ground to powder; twigs, leaves, and flowers simmered for stimulant tea. Added as seasoning to soups, stews, fish, meat dishes.
Nutritional Value: Has a high count of vitamin C, iron and niacin.
Medicinal Value: For headaches, stimulant, antiseptic, aromatic, carminative, diuretic, diaphoretic, emenogogic, and antispasmodic. Treatment for sore throats.
Cosmetic Value: Oil is aromatic, antiseptic, diaphoretic, stimulant, disinfectant, and used in cosmetic lotions. An effective deodorant, mouthwash, aftershave lotion, and wash.
Collection and Storage: Easily sheared with scissors. Mow thyme patches regularly for a winter supply. For best results, rub dried thyme through a screen to remove stems and twigs.

It's Thyme Time

Lying next to a patch of lavender thyme flowers and nibbling the pungent, peppery twigs and flowers soon became a favorite activity after a busy day. My favorite patch was near Cedar River Road in the Adirondacks. Those days were spent building structures, gathering large amounts of food, experimenting with storage and cooking methods, and just plain surviving. I would lay full length next to the bees working the thyme. The bees never minded, lifting off and moving as I raised my hand to pluck a stem to munch on. The thyme was a perfect stimulant. I returned to finish the evening renewed.

Tumbleweed



Salsola kali
Goosefoot Family,
Chenopodiaceae

Other Names: Russian thistle.
History: Native to Russia, brought to United States in flaxseed 100 years ago.
Habitat: Open desert, fields, roadsides, hot dry country.
Characteristics: Annual herb. Reaches height of 2 feet in bushy and roundish intricately branched plant. Often reddish with ridged stems and many tiny ends. Late in season, plant breaks off at base and rolls around freely, dropping its many seeds.
Primary Uses: Culinary. Tips eaten cooked as vegetable or in soups and stir-fries.
Nutritional Value: High in calcium, vegetable protein, carbohydrates, fiber, potassium and *extremely* high in niacin.
Collection and Storage: Choose tumbleweed that does not have many buds and flowers, and harvest young seedlings whenever possible. If you don't have time to stand and clip the bush, remove a few branches and let wilt naturally. Clip ends that wilt the most; this ensures getting the most succulent ends. Drop succulent ends in a bowl, wash well, or soak overnight in a large bowl of water and a teaspoon of vinegar. The more you clip the more the plant grows to maturation, producing many more branches.
Caution: Do not ingest raw except in extreme emergency, chewing thoroughly.

Linda says- Making tumbleweed soup is simple. I find a tumbleweed without prickly seeds and flowers, and shear the succulent ends into a basket. Wash the succulent tips well, quickly cook them in boiling water, then pack half-cup quantities into soup bags and freeze. You'll have a month's worth of delicious soup.

Violets

Viola species
Violet Family, *Violaceae*



Other Names: Heart leaf, baby face, wild violet.
History: World wide distribution, including North America. Used by Native Americans.
Habitat: Rich, moist woods, swamp sides, stream banks, damp lawns.
Characteristics: Annual or perennial herb. Smooth, heart-shaped leaves with little scalloping on edges. Single stem. Flowers on single stem from leaf base; five-petaled, arising from a center spur, usually yellow. Lower petal has heavy veins and there is a bearded design. Colors vary from white or yellow to purple or blue.
Primary Uses: Culinary, medicinal, cosmetic. Flowers used as little “fruits”, eaten raw and candied; also used in jam, jelly, wine. Buds, flowers, and leaves dried for tea. Leaves eaten raw in sandwiches or salads; cooked, as thickening agent. Roots of violets may be eaten raw or cooked in a crockpot. Stems may be snipped into 1 inch sections and added as “beans” to soups.
Nutritional Value: High in vitamins A and C.
Medicinal Value: Good for colds, flu. Eaten for dry, scratchy throat. Raw flowers eaten in quantity for varicose veins.
Cosmetic Value: An astringent; used in cold creams, oil lotions (infusion of flowers).
Collection and Storage: Clip violets easily with scissors, but use fingers when gathering leaves. Choose large leaves to wrap up tofu, rice, potatoes, beans.
Caution: Yellow wood violets may be cathartic; small, common lawn violets are not.

Linda says- Tiny faces peeping out of the dew-covered grass - violets are a favorite of mine, whether next to a stream in early spring or on the back lawn. The violet's face is a spring flag, heralding renewed life.

Todd loved the little faces in his ice cream. I would lightly stir a handful of violets into his vanilla ice cream.

Wild Lettuce



Lactuca canadensis
Composite Family, *Compositae*

Other Names: Milk lettuce, chicory lettuce, horseweed.

History: Native to North America. Used by Native Americans; The Menominees use wild lettuce as a sedative.[2]

Habitat: Fields, waste ground, roadsides.

Characteristics: Biennial herb. Deeply serrated leaves, coming off a central stalk. Tiny buds and extensions off of top stalk. Dozens of yellow dandelion-like ray flowers. White milk in stem. Stem veins are characteristic.

Primary Uses: Leaves eaten in salads. Flowers and buds are stir-fried. Flowers and seeds are eaten raw or cooked, sautéed in oil and garlic. Stems (young) cut to bean size and cooked. Leaves dried and ground for seasoning. Roots have been used as a gum.

Nutritional Value: High in beta-carotene, ascorbic acid, (vitamin C)

Medicinal Value: Tea from milky leaves is sedative. Sap induces sweating and is used as a fever reducer. Decoctions of sap are known to ease irritability and insomnia.

Collection and Storage: Collect leaves, stems, flowers as you would lettuce, use raw.

Linda says- The tops or buds of this great plant are delicious. Stir-fried with a little olive oil and garlic salt, wild lettuce makes a wild meal!

---

[2] Densmore, Francis. *How the Indians Use Wild Plants for Food.* New York: Dover, 1974.

Willow

Salix species
Willow Family, *Salicaceae*



Types: Beaked, black, blue, Canada, coastal plain, crack, Drummond's, ward, weeping willow.
History: Grows throughout the world but abundant in cooler parts of Northern Hemisphere. In North America, used by Eskimos, Native Americans. Eskimos dry inner bark, strip, and cook like spaghetti; Inner bark layer called keeleeyuk in Eskimo, meaning "the scrape."
Habitat: Damp areas, stream sides, swamps.
Characteristics: Deciduous shrubby tree. Over 100 species, many with drooping branches alternate 2 inch leaves, sectioned twig tendril. Flowers (catkins) are furry, present before leaves. Roots seek water; have thousands of white hair-like extensions.
Primary Uses: Culinary, medicinal, cosmetic. Inner bark eaten raw; may be dried and pounded to flour. Buds, flowers or catkins, seeds are brewed as tea. Leaves are emergency food, tea, but use sparingly as they contain "aspirin". Willow sprouts provide early spring food.
Nutritional Value: Very high in beta-carotene.
Medicinal Value: All parts have acetylsalicylic acid, or salix, an aspirin source. Ten to 15 catkins or one 6 to 8 inch tendril, equal approximately 2 aspirins.
Cosmetic Value: Astringent; used in lotions, creams, facial washes.
Collection and Storage: Break tendrils into 6-inch pieces and dry. Store in glass container. Collect catkins or leaves by running hand down tendril. Dry and store. A supply of aspirin was easily kept through the year by stripping catkins in the spring, drying, and placing in glass.

Beneath the Weeping Willow

I sit under my favorite weeping willow tree. My fingers fly as I make a supple willow basket. At the same time, the tiny catkins hanging from the twigs are irresistible. I first munch only four or five, remembering that these catkins are like aspirin. But the catkins are so delicious. I quickly down about 1/2 cup of them while I make the basket. When I stand up, my ears ring and I wobble, almost faint. I sit down immediately and put my head between my knees to stop the dizziness. I curl up and go to sleep. Much later, I awake with a gigantic headache that lasts almost two days. A hard-learned lesson about the potency of willow catkins!

Wintergreen



Gaultheria procumbens
Heath Family, *Ericaceae*

Other Names: Checkerberry.
History: Native to North America, especially East.
Habitat: Wooded areas, acid soils, under softwood trees.
Characteristics: Perennial herb. Drooping waxy white flowers hidden by flat shiny evergreen leaves. Has bright red berries.
Primary Uses: Culinary, medicinal, cosmetic. Leaves used fresh or dried, crush or steep for tea. Oils are distilled for flavorings. Buds, flowers, and seeds (berries) edible.
Nutritional Value: Fruit or berry, high in acetylsalicylic acid, or aspirin. Contains niacin.
Medicinal Value: Leaves contain acetylsalicylic acid (aspirin). Steeped for astringent. Boiled and applied to wounds or used as eyewash. Tea breaks a fever. Used as an anti-rheumatism gargle, to treat wounds or hemorrhages, as a poultice for insect bites and

bruises, or as vaginal douche (see page 138). Oils used for rheumatism or arthritis, sciatica.
Cosmetic Value: Aromatic oil used as flavoring for candies, toothpaste.
Collection and Storage: Snip leaves; dig roots, and collect berries. Wintergreen is known to grow under the snow; dig and eat during winter. Dried, powdered wintergreen leaves have more flavor than fresh leaves. Plant transplants easily, loves acid soil.
Caution: Contains acetylsalicylic acid (aspirin). Overdose of oil may produce drowsiness, congestion, and delirium.

Linda Says- Driving from Plainfield, New Jersey, to Indian Lake in upstate New York was a 17-hour drive in 1940. My frustration as a child was greatly relieved by chewing a wintergreen leaf I picked in the woods. I soon learned to recognize the flat, shiny, three-leafed plant growing close to the ground. If I was lucky enough to find a red wintergreen berry, I savored that berry for an hour of the drive!



Winter Harvest

It was the first time I trooped through snowdrifts looking for food. I thought it would be hard work, but balsam and pine trees were always within reach of the trail. Bushes of meadowsweet poked above the snow. I would never starve if I ate twigs and bark. But I did not know then that the Iroquois Abanake (bark eaters) did just that for centuries. Following the deer trail, I located the wintergreen. Reaching deep into the snow opening, I pulled out a few plants. The shiny green aromatic leaf never tasted so good!

Wood Sorrel

Oxalis species
Wood-Sorrel Family,
Oxalidaceae



Other Names: Clover sorrel, shamrock sorrel, lemon sorrel.
History: Eaten as spicy salad for centuries. Introduced to North America and used by Europeans and all Native American cultures except Crow and Menomini. George Washington Carver, of peanut fame, made pies and confections from wood sorrel; he even made a paint from sorrel.
Habitat: Fields, woods, moist places, under trees, or shrubs.
Characteristics: Low-growing perennial herb. Leaves alternate or basal, in 3 heart-shaped leaflets (a shamrock), sour lemon tasting. Grows from 2 inches to 8 inches in bunches or carpets. Flowers long, with 5 yellow, rarely green petals, sometimes red at the base. Leaves fold up sometimes when extremely warm or in sunshine.
Primary Uses: Culinary, cosmetic. Leaves cooked in soups, stews. Seeds cooked in soups, stews. Buds and flowers cooked in soups, stews. Many commercial uses. Stems are edible. Cut into inch pieces and add to soups, stews.
Nutritional Value: High in vitamin C. Because wood sorrel is high in oxalic acid, it hastens the elimination of calcium from the body and inhibits absorption of calcium. Therefore, limit intake of raw leaves to no more than 15 at most. Cook for safety. Drop entire plant in hot water. When color changes from bright emerald green to olive green, oxalic acid is neutralized.
Cosmetic Value: Antiseptic wash for skin and skin eruptions.
Collection and Storage: Gather seeds when they are red. Gather leaves year-round Collect flowers any time of year. Cut stems, leaves, and seeds to dry for soup or use as a salad ingredient.

Yarrow

Achillea millefolium
Composite Family, *Compositae*



Other Names: Milfoil, field hop, old man's pepper.
History: Native to Europe. Naturalized in North America.
Habitat: Old fields, roadsides.
Characteristics: Perennial herb. Grown to height of 2 1/2 feet. Creeping rootstock; fern-like, lacy leaves, slightly hairy. Flowers typically white in wild, but occur in red, rosy, yellow, and magenta in ornamental gardens. Flowers have 5 petal-like rays, dozens in flat top clusters. Each flower is on its own stem, originating from one stem.
Primary Uses: Culinary, medicinal, cosmetic.
Stimulant tea. Boil any part of plant in small amounts. Leaves used raw in salads, or cooked for green. Seeds and flowers crumpled for seasoning. First-year roots peeled and cooked as vegetable.
Nutritional Value: High in calcium, and potassium.
Medicinal Value: Moves fluids in the body. Diaphoretic; cleanses the blood; tonic, stimulant, antiseptic; soothes burns. Strengthens immune system.
Cosmetic Value: Astringent; cleansing herb in facial mixtures, vaginal douches, shampoos; for dandruff and baldness treatments. Mouthwash for toothaches.
Collection and Storage: Clip flowers with scissors or break off with fingers. Pull leaves down stalk.

Yarrow for Teeth Cleansing

A dentist appointment loomed ahead. I hated to leave the forest and drive the old truck to Indian Lake, but having no phone, I could not cancel. I picked a yarrow stem and stripped off the leaves. I placed a leaf under my forefinger and scrubbed my teeth with the yarrow. Very astringent and satisfying. Using the stem, I picked here and there. Then I drove the pickup to town. In the dentist chair, the doctor exclaimed, "Linda, you've been in the yarrow again!" I did not realize that the yarrow had dyed the inside of my mouth green, especially my teeth—temporarily, of course.

The author begins her exploration of wild food.

Notes



Aloe Vera
Aloe perfoliata vera *Cactus Family, Liliaceae*



Amaranth
Amaranthus retroflexus *Amaranth Family, Amaranthaceae*



Arrowhead
Sagittaria species, S. chinensis *Water Plantain Family, Alismataceae*



Aster
Aster nemoralis *Composite Family, Asteraceae*



Balsam Fir
Abies balsamea *Pine Family, Pinaceae*



Birch
Betula species *Birch Family, Betulaceae*



Blackberry
Rubus villosus and other bramble berry species *Rose Family, Rosaceae*



Blueberry
Vaccinium myrtillus *Heath Family, Erraceae*



Bulrush
Scirpus validus *Sedge Family, Juncaceae*



Burdock
Arctium lappa *Sunflower Family, Asteraceae*



Cattail
Typha latifolia *Cattail Family, Typhacerae*



Chamomile
Matricaria chamomilla *Composite Family, Asteraceae*



Chickweed
Stellaria media (common chickweed), *Pink Family, Caryphyllea*



Chicory
Cichorium intybus *Composite Family, Asteraceae*



Cholla
Opuntia fulgida *Cactus Family, Cactaceae*



Clover, red
Trifolium pratense *Legume Family, Leguminosea*



Clover, white
Trefolium Repens *Legume Family, Leguminosae*



Crabgrass
Digitaria sanguinalis *Grass Family, Graminea*



Daisy
Chrysanthemum leucanthemum *Composite Family, Asteraceae*



Dandelion
Taraxacum officinale *Composite Family, Asteraceae*



Dock
Rumex crispus *Buckwheat Family, Portulaceae*



Evening Primrose
Oenothera biennis *Evening Primrose Family, Onagraceae*



Filarie
Erodium circutarium *Cranesbill Family, Geraniaceae*



Fireweed
Epilobium angustifolium *Evening Primrose Family, Onagraceae*

Goldenrod
Solidago odora *Sunflower Family, Compositae*

Grape
Vitis arizonica (Western) Vitis labrusca (Eastern) Vitis rotundifolia (South)
Vitis Family, Vitaceae



Lamb's Quarters
Chenopodium album *Goosefoot Family, Chenopodiaceae*



Malva
Malva Neglecta *Mallow Family, Malvaceae*



Maple
Aceraceae Family

Meadowsweet
Filipendula ulmaria *Rose Family, Rosaceae*



Milk Thistle
Silybum marianum *Composite Family, Compositae*



Milkweed
Asclepias species *Milkweed Family, Aslepiadaceae*



Mint
Mentha species *Labiatae Family*



Mullein
Verbascum thapsus *Snapdragon Family, Scrophulariaceae*



Mustard, yellow
Brassica species *Mustard Family, Brassiacaceae*



Mustard, black
Brassica species *Mustard Family, Brassicerceae*



Nettles
Urtica species *Urticaceae Family*



Phragmities
Phragmities communis *Grass Family, Graminae*



Pine
Pinus species *Pine Family, Pinaceae*



Plantain
Plantago major (common plantain) *Plantain Family, Plantaginaceae*



Prickly Pear
Opuntia megacantha *Cactus Family, Cactaceae*



Purslane
Portulaca species *Purslane Family, Portulacaceae*



Queen Anne's Lace
Daucus carota *Parsley Family, Umbelliferae*



Raspberry
Species Rose *Family, Rosaceae*



Rose
Rosa rugosa, R. Caroline *Rose Family, Rosaceae*



Saguaro
Carnegiea gigantea *Cactus Family, Cactaceae*



Sheep Sorrel
Rumex acetosella *Buckwheat Family, Polygonaceae*



Shepherd's Purse
Capsella bursa-pastoris *Mustard Family, Brassicaceae*



Sow Thistle
Sonchus oleraceus *Composite Family, Compositae*



Strawberry
Fragaria virginiana *Rose Family, Rosaceae*



Sumac
Rhus species *Cashew Family, Anacardiaceae*



Sunflower
Helianthus species *Composite Family, Compositae*



Thistle
Circium species *Composite Family, Compositae*



Thyme
Thymus vulgaris *Mint Family, Labiatae*



Tumbleweed
Salsola kali *Goosefoot Family, Chenopodiaceae*



Violets
Viola species *Violet Family, Violaceae*



Wild Lettuce
Lactuca canadensis *Composite Family, Compositae*



Willow
Salix species *Willow Family, Salicaceae*



Wintergreen
Gaultheria procumbens *Heath Family, Ericaceae*



Wood Sorrel
Oxalis species *Wood Sorrel Family, Oxalidaceae*



Yarrow
Achillea millefolium *Composite Family, Compositae*

Linda building a walk.



Field in Pots

Home Health Aides Provided Lunch for Linda

Nutrient Value of Wild Foods

I do not advocate giving up one's daily diet, but rather supplementing it with wild foods. My homesteading days taught me the value of a balanced vegetarian diet. Note the following dated 1997 - Some variations have been noted to date.

Some USDA recommended daily dietary allowances for adults are:

- Vitamin A—1,000 micrograms (males) and 800 micrograms (females)
- Vitamin C—60 milligrams
- Vitamin D—5 micrograms
- Vitamin B1 (thiamin)—1.4 milligrams (males) or 1.0 milligrams (females)
- Vitamin B2 (riboflavin)—1.6 milligrams (males) or 1.2 milligrams (females)
- Vitamin B3—20 milligrams
- Vitamin B6—2 milligrams
- Vitamin B12—3 micrograms
- Calcium—1,200 milligrams
- Iron—18 milligrams
- Phosphorous—800 milligrams
- Potassium—1,875 milligrams
- Protein—56 grams (males) or 44 grams (females)

So, you can see from the above how well wild foods can boost the nutritional value of your meal.

The listings that follow show the nutritional values for 1/2 cup quantities of uncooked plant matter.

As much as possible, the data was derived from Duke and Atchley, 1986 *CRC Handbook of Proximate Analyses*, CRC Press, 1986. Duke's FNF database; or from Joseph Laferriere's Nutricomp database. When no other data were available we used Mark Pedersen's Nutritional Herbology (Pedersen Publishing, 1987).

When available data was not specific to the plant or plant part we used data from a related species, or genus, or similar species in a different family. When absolutely no pertinent data was uncovered—as, for example, for violet flowers—averages for flowers such as those published by Duke and Atchley, were used. Occasionally it was necessary to estimate the water content, back-calculating from dried to a fresh basis. Adjustments were then made for carbohydrate and/or fiber content, ensuring that the figures were within a normal range for the plant.

How to read the Nutritional Listings

All quantities given are amounts per 1/2 cup raw food item (≈100 grams).

The figure for Calories is number of Calories per 1/2 cup (100 g) raw food.

Column 1: Measurements are in grams (g) per 100 g (1/2 cup). (Because of the mathematical coincidence, this could also be expressed as a percentage of the whole.)
Abbreviations:
- Carbos. = Carbohydrates
- Tr. = trace amount.

Column 2: Measurements are in milligrams (mg) per 100 g (1/2 cup).
Abbreviations:
- Phos. = Phosphorus
- Ascorbic. = Ascorbic acid
- Tr. = trace amount.

Column 3: Measurements are in micrograms (µg) per 100 g (1/2 cup).
Abbreviations:
- β Carotene = Beta-carotene
- Tr. = trace amount.

No. 1 Aloe Juice

Amount of nutrient per 100g. (About ½ cup)				Calories: 1	
Water	99.5 g	Calcium	2 mg	β Carotene	Tr.
Protein	0.1 g	Phos.	2 mg	Thiamin	Tr.
Fat	Tr.	Iron	0.2 mg	Riboflavin	Tr.
Carbos.	0.4 g	Sodium	0.3 mg	Niacin	Tr.
Fiber	0.1 g	Potassium	0.4 mg		
Ash	Tr.	Ascorbic.	3.1 mg		

No. 2 Amaranth Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 35	
Water	91.6 g	Calcium	448 mg	β Carotene	4300 µg
Protein	2.9 g	Phos.	85 mg	Thiamin	65 µg
Fat	0.4 g	Iron	13 mg	Riboflavin	300 µg
Carbos.	4.5 g	Sodium	20 mg	Niacin	1300 µg
Fiber	1.1 g	Potassium	617 mg		
Ash	1.5 g	Ascorbic.	53 mg		

No. 3 Amaranth Seed

Amount of nutrient per 100g. (About ½ cup)				Calories: 358	
Water	12.3 g	Calcium	247 mg	β Carotene	0.0 µg
Protein	12.9 g	Phos.	500 mg	Thiamin	140 µg
Fat	7.2 g	Iron	3.4 mg	Riboflavin	320 µg
Carbos.	65.1 g	Sodium	33.5 mg	Niacin	1000 µg
Fiber	6.7 g	Potassium	52.5 mg		
Ash	2.5 g	Ascorbic.	3.0 mg		

No. 4 Arrowhead Tubers

Amount of nutrient per 100g. (About ½ cup)				Calories: 99	
Water	72.5 g	Calcium	10 mg	β Carotene	0 µg
Protein	5.3 g	Phos.	174 mg	Thiamin	200 µg
Fat	0.3 g	Iron	2.6 mg	Riboflavin	100 µg
Carbos.	20.2 g	Sodium	225 mg	Niacin	1700 µg
Fiber	0.8 g	Potassium	922 mg		
Ash	1.7 g	Ascorbic.	1 mg		

No. 5 Arrowhead Shoots

Amount of nutrient per 100g. (About ½ cup)				Calories: 62	
Water	85 g	Calcium	82 mg	β Carotene	1700 µg
Protein	2.6 g	Phos.	45 mg	Thiamin	200 µg
Fat	1.0 g	Iron	7 mg	Riboflavin	300 µg
Carbos.	9.9 g	Sodium	21 mg	Niacin	1500 µg
Fiber	0.9 g	Potassium	606 mg		
Ash	1.5 g	Ascorbic.	60 mg		

No. 6 Aster Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 39	
Water	87.2 g	Calcium	42 mg	β Carotene	3345 µg
Protein	4.2 g	Phos.	76 mg	Thiamin	180 µg
Fat	0.7 g	Iron	4 mg	Riboflavin	360 µg
Carbos.	6.4 g	Sodium	40 mg	Niacin	1100 µg
Fiber	1.1 g	Potassium	533 mg		
Ash	1.5 g	Ascorbic.	88 mg		

No. 7 Balsam Fir Needles

Amount of nutrient per 100g. (About ½ cup)				Calories: 35	
Water	88 g	Calcium	186 mg	β Carotene	5652 µg
Protein	2.8 g	Phos.	57 mg	Thiamin	110 µg
Fat	0.5 g	Iron	2.7 mg	Riboflavin	240 µg
Carbos.	6.5 g	Sodium	40 mg	Niacin	900 µg
Fiber	1.3 g	Potassium	382 mg		
Ash	2.1 g	Ascorbic.	64 mg		

No. 8 Birch Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 1	
Water	88.0 g	Calcium	186 mg	β Carotene	5652 µg
Protein	3.3 g	Phos.	57 mg	Thiamin	110 µg
Fat	1.0 g	Iron	2.7 mg	Riboflavin	240 µg
Carbos.	6.7 g	Sodium	40 mg	Niacin	900 µg
Fiber	2.0 g	Potassium	382 mg		
Ash	0.9 g	Ascorbic.	68 mg		

No. 9 Blackberry Fruit

Amount of nutrient per 100g. (About ½ cup)				Calories: 57	
Water	84.4 g	Calcium	29 mg	β Carotene	1000 µg
Protein	1.2 g	Phos.	26 mg	Thiamin	200 µg
Fat	0.7 g	Iron	1.3 mg	Riboflavin	500 µg
Carbos.	13.3 g	Sodium	1 mg	Niacin	600 µg
Fiber	3.7 g	Potassium	168 mg		
Ash	0.5 g	Ascorbic.	22 mg		

No. 10 Blueberry Fruit

Amount of nutrient per 100g. (About ½ cup)				Calories: 62	
Water	83.2 g	Calcium	15 mg	β Carotene	60 µg
Protein	0.7 g	Phos.	13 mg	Thiamin	30 µg
Fat	0.5 g	Iron	1 mg	Riboflavin	60 µg
Carbos.	15.3 g	Sodium	1 mg	Niacin	500 µg
Fiber	1.5 g	Potassium	81 mg		
Ash	0.3 g	Ascorbic.	14 mg		

No. 11 Bulrush Flowers

Amount of nutrient per 100g. (About ½ cup)				Calories: 16	
Water	94.8 g	Calcium	47 mg	β Carotene	400 µg
Protein	0.4 g	Phos.	86 mg	Thiamin	20 µg
Fat	0.1 g	Iron	1.0 mg	Riboflavin	110 µg
Carbos.	4.4 g	Sodium	18 mg	Niacin	600 µg
Fiber	1.2 g	Potassium	166 mg		
Ash	0.3 g	Ascorbic.	18 mg		

No. 12 Bulrush Seeds

Amount of nutrient per 100g. (About ½ cup)				Calories: 342	
Water	11.1 g	Calcium	24 mg	β Carotene	0 µg
Protein	10.7 g	Phos.	267 mg	Thiamin	450 µg
Fat	8.9 g	Iron	3.1 mg	Riboflavin	200 µg
Carbos.	67.7 g	Sodium	6 mg	Niacin	3800 µg
Fiber	2.6 g	Potassium	316 mg		
Ash	1.6 g	Ascorbic.	0 mg		

No. 13 Bulrush Shoots

Amount of nutrient per 100g. (About ½ cup)				Calories: 31	
Water	89.9 g	Calcium	50 mg	β Carotene	1166 µg
Protein	0.8 g	Phos.	18 mg	Thiamin	150 µg
Fat	0.2 g	Iron	1.1 mg	Riboflavin	190 µg
Carbos.	7.5 g	Sodium	9 mg	Niacin	1000 µg
Fiber	2.8 g	Potassium	283 mg		
Ash	1.4 g	Ascorbic.	41 mg		

No. 14 Burdock Root

Amount of nutrient per 100g. (About ½ cup)				Calories: 89	
Water	76.5 g	Calcium	50 mg	β Carotene	0 µg
Protein	2.5 g	Phos.	58 mg	Thiamin	250 µg
Fat	0.1 g	Iron	1.2 mg	Riboflavin	80 µg
Carbos.	20.1 g	Sodium	30 mg	Niacin	300 µg
Fiber	1.7 g	Potassium	180 mg		
Ash	0.8 g	Ascorbic.	2 mg		

No. 15 Cattail Roots

Amount of nutrient per 100g. (About ½ cup)				Calories: 73	
Water	79.7 g	Calcium	32 mg	β Carotene	568 µg
Protein	1.6 g	Phos.	54 mg	Thiamin	90 µg
Fat	0.6 g	Iron	1 mg	Riboflavin	50 µg
Carbos.	17.5 g	Sodium	14 mg	Niacin	800 µg
Fiber	1.0 g	Potassium	399 mg		
Ash	1.0 g	Ascorbic.	18 mg		

No. 16 Cattail Shoots

Amount of nutrient per 100g. (About ½ cup)				Calories: 31	
Water	81.3 g	Calcium	58 mg	β Carotene	2200 µg
Protein	1.8 g	Phos.	109 mg	Thiamin	300 µg
Fat	0.3 g	Iron	2 mg	Riboflavin	400 µg
Carbos.	15.0 g	Sodium	8 mg	Niacin	800 µg
Fiber	6.2 g	Potassium	639 mg		
Ash	1.6 g	Ascorbic.	76 mg		

No. 17 Chamomile Flowers

Amount of nutrient per 100g. (About ½ cup)				Calories: 56	
Water	81.2 g	Calcium	126 mg	β Carotene	41 µg
Protein	2.2 g	Phos.	60 mg	Thiamin	15 µg
Fat	0.7 g	Iron	3.2 mg	Riboflavin	80 µg
Carbos.	14.7 g	Sodium	48.5 mg	Niacin	2801 µg
Fiber	1.4 g	Potassium	248 mg		
Ash	1.2 g	Ascorbic.	5 mg		

No. 18 Chickweed Leaves

Amount of nutrient per 100g. (About ⅓ cup)				Calories: 28	
Water	91.7 g	Calcium	160 mg	β Carotene	200 µg
Protein	1.2 g	Phos.	49 mg	Thiamin	Tr.
Fat	0.2 g	Iron	29 mg	Riboflavin	100 µg
Carbos.	5.3 g	Sodium	82 mg	Niacin	500 µg
Fiber	1.7 g	Potassium	243 mg		
Ash	1.6 g	Ascorbic.	350 mg		

No. 19 Chicory

Amount of nutrient per 100g. (About ⅓ cup)				Calories: 30	
Water	92.0 g	Calcium	100 mg	β Carotene	2400 µg
Protein	1.7 g	Phos.	47 mg	Thiamin	100 µg
Fat	0.3 g	Iron	0.9 mg	Riboflavin	100 µg
Carbos.	4.7 g	Sodium	45 mg	Niacin	500 µg
Fiber	0.8 g	Potassium	420 mg		
Ash	1.3 g	Ascorbic.	24 mg		

No. 20 Chicory Roots

Amount of nutrient per 100g. (About ½ cup)				Calories: 73	
Water	80.0 g	Calcium	41 mg	β Carotene	Tr.
Protein	1.4 g	Phos.	61 mg	Thiamin	Tr.
Fat	0.2 g	Iron	0.8 mg	Riboflavin	Tr.
Carbos.	17.5 g	Sodium	50 mg	Niacin	400 µg
Fiber	2.0 g	Potassium	290 mg		
Ash	0.9 g	Ascorbic.	5 mg		

No. 21 Cholla Shoots

Amount of nutrient per 100g. (About ½ cup)				Calories: 31.0	
Water	77.8 g	Calcium	3 mg	β Carotene	Tr.
Protein	1.6 g	Phos.	1 mg	Thiamin	Tr.
Fat	0.5 g	Iron	1.1 mg	Riboflavin	Tr.
Carbos.	15.9 g	Sodium	0.4 mg	Niacin	Tr.
Fiber	1.7 g	Potassium	12 mg		
Ash	4.2 g	Ascorbic.	57 mg		

No. 22 Clover Flowers

Amount of nutrient per 100g. (About ½ cup)				Calories: 54	
Water	82.3 g	Calcium	232 mg	β Carotene	200 μg
Protein	2.0 g	Phos.	57 mg	Thiamin	100 μg
Fat	0.6 g	Iron	1 mg	Riboflavin	100 μg
Carbos.	13.5 g	Sodium	3 mg	Niacin	2200 μg
Fiber	1.8 g	Potassium	354 mg		
Ash	1.5 g	Ascorbic.	52 mg		

No. 23 Clover Shoots

Amount of nutrient per 100g. (About ½ cup)				Calories: 31	
Water	89.9 g	Calcium	142 mg	β Carotene	1166 μg
Protein	2.1 g	Phos.	32 mg	Thiamin	150 μg
Fat	0.5 g	Iron	1.1 mg	Riboflavin	190 μg
Carbos.	6.3 g	Sodium	4 mg	Niacin	1000 μg
Fiber	2.2 g	Potassium	345 mg		
Ash	1.1 g	Ascorbic.	57 mg		

No. 24 Daisy Flowers

Amount of nutrient per 100g. (About ½ cup)				Calories: 17	
Water	92.6 g	Calcium	56 mg	β Carotene	8800 μg
Protein	1.6 g	Phos.	32 mg	Thiamin	30 μg
Fat	0.2 g	Iron	3.1 mg	Riboflavin	20 μg
Carbos.	4.4 g	Sodium	52 mg	Niacin	860 μg
Fiber	0.9 g	Potassium	570 mg		
Ash	1.3 g	Ascorbic.	53 mg		

No. 25 Daisy Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 19	
Water	93.5 g	Calcium	63 mg	β Carotene	3160 µg
Protein	1.8 g	Phos.	34 mg	Thiamin	90 µg
Fat	0.3 g	Iron	2.5 mg	Riboflavin	190 µg
Carbos.	3.3 g	Sodium	106 mg	Niacin	600 µg
Fiber	0.9 g	Potassium	256 mg		
Ash	1.1 g	Ascorbic.	27 mg		

No. 26 Dandelion Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 45	
Water	85.6 g	Calcium	187 mg	β Carotene	800 µg
Protein	2.7 g	Phos.	66 mg	Thiamin	200 µg
Fat	0.7 g	Iron	3 mg	Riboflavin	300 µg
Carbos.	9.2 g	Sodium	76 mg	Niacin	900 µg
Fiber	1.6 g	Potassium	398 mg		
Ash	1.8 g	Ascorbic.	68 mg		

No. 27 Dock

Amount of nutrient per 100g. (About ½ cup)				Calories: 21	
Water	92.6 g	Calcium	74 mg	β Carotene	2770 µg
Protein	1.5 g	Phos.	56 mg	Thiamin	60 µg
Fat	0.3 g	Iron	5.6 mg	Riboflavin	80 µg
Carbos.	4.1 g	Sodium	5 mg	Niacin	400 µg
Fiber	0.9 g	Potassium	338 mg		
Ash	1.5 g	Ascorbic.	30 mg		

No. 28 Dock Seeds

Amount of nutrient per 100g. (About ½ cup)				Calories: 342	
Water	14.3 g	Calcium	35 mg	β Carotene	0 µg
Protein	12.9 g	Phos.	305 mg	Thiamin	450 µg
Fat	3.8 g	Iron	3.4 mg	Riboflavin	200 µg
Carbos.	66.9 g	Sodium	4 mg	Niacin	3800 µg
Fiber	19.3 g	Potassium	339 mg		
Ash	2.8 g	Ascorbic.	0 mg		

No. 29 Evening Primrose Seeds

Amount of nutrient per 100g. (About ½ cup)				Calories: 342	
Water	7.0 g	Calcium	1422 mg	β Carotene	0 µg
Protein	15.1 g	Phos.	533 mg	Thiamin	450 µg
Fat	2.2 g	Iron	22 mg	Riboflavin	200 µg
Carbos.	50.4 g	Sodium	16 mg	Niacin	3800 µg
Fiber	3.6 g	Potassium	542 mg		
Ash	5.3 g	Ascorbic.	0 mg		

No. 30 Filarie Shoots

Amount of nutrient per 100g. (About ½ cup)				Calories: 31	
Water	81.5 g	Calcium	464 mg	β Carotene	1166 µg
Protein	2.4 g	Phos.	87 mg	Thiamin	150 µg
Fat	0.4 g	Iron	1.1 mg	Riboflavin	190 µg
Carbos.	12.2 g	Sodium	4 mg	Niacin	1000 µg
Fiber	4.5 g	Potassium	622 mg		
Ash	3.5 g	Ascorbic.	57 mg		

No. 31 Filarie Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 32	
Water	85.8 g	Calcium	140 mg	β Carotene	4000 µg
Protein	4.0 g	Phos.	50 mg	Thiamin	100 µg
Fat	0.4 g	Iron	2.5 mg	Riboflavin	200 µg
Carbos.	7.3 g	Sodium	60 mg	Niacin	700 µg
Fiber	1.4 g	Potassium	410 mg		
Ash	2.5 g	Ascorbic.	63 mg		

No. 32 Fireweed Greens

Amount of nutrient per 100g. (About ½ cup)				Calories: 35	
Water	88.0 g	Calcium	186 mg	β Carotene	5652 µg
Protein	2.8 g	Phos.	57 mg	Thiamin	110 µg
Fat	0.7 g	Iron	2.7 mg	Riboflavin	240 µg
Carbos.	8.2 g	Sodium	40 mg	Niacin	900 µg
Fiber	1.3 g	Potassium	382 mg		
Ash	0.8 g	Ascorbic.	68 mg		

No. 33 Goldenrod Shoots

Amount of nutrient per 100g. (About ½ cup)				Calories: 31	
Water	89.9 g	Calcium	113 mg	β Carotene	300 µg
Protein	0.9 g	Phos.	52 mg	Thiamin	150 µg
Fat	1.4 g	Iron	11 mg	Riboflavin	190 µg
Carbos.	7.0 g	Sodium	4 mg	Niacin	1000 µg
Fiber	1.3 g	Potassium	83 mg		
Ash	0.7 g	Ascorbic.	1000 mg		

No. 34 Grape Fruit

Amount of nutrient per 100g. (About ½ cup)				Calories: 63	
Water	81.3 g	Calcium	14 mg	β Carotene	Tr.
Protein	0.6 g	Phos.	10 mg	Thiamin	100 µg
Fat	0.4 g	Iron	0.3 mg	Riboflavin	100 µg
Carbos.	17.1 g	Sodium	2 mg	Niacin	300 µg
Fiber	0.8 g	Potassium	191 mg		
Ash	0.6 g	Ascorbic.	4 mg		

No. 35 Grape Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 68	
Water	79.2 g	Calcium	716 mg	β Carotene	5200 µg
Protein	4.8 g	Phos.	38 mg	Thiamin	200 µg
Fat	0.9 g	Iron	7 mg	Riboflavin	100 µg
Carbos.	13.5 g	Sodium	21 mg	Niacin	1200 µg
Fiber	2.1 g	Potassium	382 mg		
Ash	1.5 g	Ascorbic.	34 mg		

No. 36 Lamb's Quarters Seeds

Amount of nutrient per 100g. (About ½ cup)				Calories: 353	
Water	8.3 g	Calcium	1036 mg	β Carotene	0 µg
Protein	19.6 g	Phos.	340 mg	Thiamin	450 µg
Fat	4.2 g	Iron	64 mg	Riboflavin	200 µg
Carbos.	57.7 g	Sodium	9 mg	Niacin	3800 µg
Fiber	27.1 g	Potassium	1687 mg		
Ash	10.2 g	Ascorbic.	0 mg		

No. 37 Lamb's Quarters Shoots

Amount of nutrient per 100g. (About ½ cup)				Calories: 35	
Water	88.0 g	Calcium	324 mg	β Carotene	3800 µg
Protein	3.5 g	Phos.	48 mg	Thiamin	100 µg
Fat	0.8 g	Iron	1.5 mg	Riboflavin	200 µg
Carbos.	5.5 g	Sodium	4 mg	Niacin	1000 µg
Fiber	2.0 g	Potassium	684 mg		
Ash	2.4 g	Ascorbic.	40 mg		

No. 38 Mallow (Malva) Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 28	
Water	91.6 g	Calcium	90 mg	β Carotene	3315 µg
Protein	3.6 g	Phos.	42 mg	Thiamin	170 µg
Fat	1.4 g	Iron	3.7 mg	Riboflavin	290 µg
Carbos.	2.1 g	Sodium	60 mg	Niacin	500 µg
Fiber	0.9 g	Potassium	410 mg		
Ash	1.3 g	Ascorbic.	24 mg		

No. 39 Maple Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 1	
Water	88.0 g	Calcium	186 mg	β Carotene	5652 µg
Protein	3.3 g	Phos.	57 mg	Thiamin	110 µg
Fat	1.0 g	Iron	2.7 mg	Riboflavin	240 µg
Carbos.	6.7 g	Sodium	40 mg	Niacin	900 µg
Fiber	2.0 g	Potassium	382 mg		
Ash	0.9 g	Ascorbic.	68 mg		

No. 40 Meadowsweet Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 31	
Water	89.0 g	Calcium	140 mg	β Carotene	4000 µg
Protein	2.8 g	Phos.	50 mg	Thiamin	100 µg
Fat	0.4 g	Iron	2.5 mg	Riboflavin	200 µg
Carbos.	6.0 g	Sodium	60 mg	Niacin	700 µg
Fiber	1.2 g	Potassium	410 mg		
Ash	1.8 g	Ascorbic.	63 mg		

No. 41 Milk Thistle Seeds

Amount of nutrient per 100g. (About ½ cup)				Calories: 342	
Water	11.1 g	Calcium	35 mg	β Carotene	0 μg
Protein	16.9 g	Phos.	305 mg	Thiamin	450 μg
Fat	25.7 g	Iron	3.4 mg	Riboflavin	200 μg
Carbos.	44.7 g	Sodium	4 mg	Niacin	3800 μg
Fiber	2.6 g	Potassium	339 mg		
Ash	1.6 g	Ascorbic.	0 mg		

No. 42 Milk Thistle Shoots

Amount of nutrient per 100g. (About ½ cup)				Calories: 31	
Water	89.9 g	Calcium	65 mg	β Carotene	300 μg
Protein	1.4 g	Phos.	70 mg	Thiamin	150 μg
Fat	0.6 g	Iron	11 mg	Riboflavin	190 μg
Carbos.	7.2 g	Sodium	4 mg	Niacin	1000 μg
Fiber	0.6 g	Potassium	83 mg		
Ash	0.9 g	Ascorbic.	1000 mg		

No. 43 Milkweed Shoots

Amount of nutrient per 100g. (About ½ cup)				Calories: 31	
Water	89.9 g	Calcium	31 mg	β Carotene	1166 μg
Protein	3.5 g	Phos.	59 mg	Thiamin	150 μg
Fat	0.5 g	Iron	1.1 mg	Riboflavin	190 μg
Carbos.	5.2 g	Sodium	4 mg	Niacin	1000 μg
Fiber	0.6 g	Potassium	345 mg		
Ash	0.9 g	Ascorbic.	57 mg		

No. 44 Mint Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 51	
Water	84.0 g	Calcium	160 mg	β Carotene	3000 μg
Protein	2.6 g	Phos.	80 mg	Thiamin	80 μg
Fat	0.8 g	Iron	13 mg	Riboflavin	160 μg
Carbos.	10.9 g	Sodium	40 mg	Niacin	650 μg
Fiber	1.9 g	Potassium	360 mg		
Ash	1.7 g	Ascorbic.	24 mg		

No. 45 Mullein Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 62	
Water	78.6 g	Calcium	285 mg	β Carotene	900 µg
Protein	2.3 g	Phos.	122 mg	Thiamin	Tr.
Fat	0.3 g	Iron	50 mg	Riboflavin	Tr.
Carbos.	17.1 g	Sodium	16 mg	Niacin	2000 µg
Fiber	2.4 g	Potassium	282 mg		
Ash	1.8 g	Ascorbic.	16 mg		

No. 46 Mustard Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 31	
Water	89.5 g	Calcium	183 mg	β Carotene	4200 µg
Protein	3.0 g	Phos.	50 mg	Thiamin	110 µg
Fat	0.5 g	Iron	3 mg	Riboflavin	220 µg
Carbos.	5.6 g	Sodium	32 mg	Niacin	800 µg
Fiber	1.1 g	Potassium	377 mg		
Ash	1.4 g	Ascorbic.	97 mg		

No. 47 Mustard Seeds

Amount of nutrient per 100g. (About ½ cup)				Calories: 416	
Water	7.5 g	Calcium	320 mg	β Carotene	0.0 µg
Protein	22.2 g	Phos.	650 mg	Thiamin	540 µg
Fat	18.3 g	Iron	3.4 mg	Riboflavin	400 µg
Carbos.	45.6 g	Sodium	4 mg	Niacin	3800 µg
Fiber	15.9 g	Potassium	339 mg		
Ash	6.4 g	Ascorbic.	0 mg		

No. 48 Nettle Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 35	
Water	88.2 g	Calcium	34 mg	β Carotene	1100 µg
Protein	1.2 g	Phos.	5 mg	Thiamin	100 µg
Fat	2.7 g	Iron	5 mg	Riboflavin	100 µg
Carbos.	6.9 g	Sodium	1 mg	Niacin	600 µg
Fiber	1.3 g	Potassium	20 mg		
Ash	1.0 g	Ascorbic.	10 mg		

No. 49 Phragmities Shoots

Amount of nutrient per 100g. (About ½ cup)				Calories: 31	
Water	89.9 g	Calcium	48 mg	β Carotene	1166 µg
Protein	0.5 g	Phos.	6 mg	Thiamin	150 µg
Fat	0.1 g	Iron	1.1 mg	Riboflavin	190 µg
Carbos.	9.0 g	Sodium	4 mg	Niacin	1000 µg
Fiber	4.1 g	Potassium	345 mg		
Ash	0.4 g	Ascorbic.	57 mg		

No. 50 Pine Nuts

Amount of nutrient per 100g. (About ½ cup)				Calories: 634	
Water	3.7 g	Calcium	14 mg	β Carotene	20 µg
Protein	15.3 g	Phos.	515 mg	Thiamin	760 µg
Fat	61.3 g	Iron	4 mg	Riboflavin	230 µg
Carbos.	16.8 g	Sodium	72 mg	Niacin	9800 µg
Fiber	2.6 g	Potassium	628 mg		
Ash	2.9 g	Ascorbic.	1 mg		

No. 51 Pine Needles

Amount of nutrient per 100g. (About ½ cup)				Calories: 141	
Water	51.5 g	Calcium	186 mg	β Carotene	5652 µg
Protein	3.1 g	Phos.	57 mg	Thiamin	110 µg
Fat	4.5 g	Iron	2.7 mg	Riboflavin	240 µg
Carbos.	39.9 g	Sodium	40 mg	Niacin	900 µg
Fiber	14.1 g	Potassium	382 mg		
Ash	1.0 g	Ascorbic.	68 mg		

No. 52 Plantain Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 61	
Water	81.4 g	Calcium	184 mg	β Carotene	2520 µg
Protein	2.5 g	Phos.	52 mg	Thiamin	95 µg
Fat	0.3 g	Iron	1.2 mg	Riboflavin	280 µg
Carbos.	14.6 g	Sodium	16 mg	Niacin	800 µg
Fiber	2.0 g	Potassium	277 mg		
Ash	1.2 g	Ascorbic.	8 mg		

No. 53 Plantain Seeds

Amount of nutrient per 100g. (About ½ cup)				Calories: 342	
Water	11.2 g	Calcium	35 mg	β Carotene	0 µg
Protein	17.0 g	Phos.	305 mg	Thiamin	450 µg
Fat	7.6 g	Iron	3.4 mg	Riboflavin	200 µg
Carbos.	59.7 g	Sodium	4 mg	Niacin	3800 µg
Fiber	13.7 g	Potassium	339 mg		
Ash	4.5 g	Ascorbic.	0 mg		

No. 54 Prickly Pear Fruit

Amount of nutrient per 100g. (About ½ cup)				Calories: 67	
Water	81.4 g	Calcium	57 mg	β Carotene	100 µg
Protein	1.1 g	Phos.	32 mg	Thiamin	10 µg
Fat	0.4 g	Iron	1.2 mg	Riboflavin	20 µg
Carbos.	16.6 g	Sodium	1 mg	Niacin	300 µg
Fiber	1.1 g	Potassium	178 mg		
Ash	0.5 g	Ascorbic.	18 mg		

No. 55 Purslane Shoots

Amount of nutrient per 100g. (About ½ cup)				Calories: 16	
Water	93.9 g	Calcium	65 mg	β Carotene	100 µg
Protein	1.3 g	Phos.	44 mg	Thiamin	Tr.
Fat	0.1 g	Iron	2 mg	Riboflavin	100 µg
Carbos.	3.4 g	Sodium	45 mg	Niacin	500 µg
Fiber	0.8 g	Potassium	494 mg		
Ash	1.2 g	Ascorbic.	21 mg		

No. 56 Queen Anne's Lace Roots

Amount of nutrient per 100g. (About ½ cup)				Calories: 37	
Water	89.6 g	Calcium	36 mg	β Carotene	7000 µg
Protein	1.1 g	Phos.	38 mg	Thiamin	60 µg
Fat	0.3 g	Iron	1.2 mg	Riboflavin	50 µg
Carbos.	8.3 g	Sodium	70 mg	Niacin	700 µg
Fiber	0.9 g	Potassium	245 mg		
Ash	0.7 g	Ascorbic.	8 mg		

No. 57 Raspberry Fruit

Amount of nutrient per 100g. (About ½ cup)				Calories: 73	
Water	80.8 g	Calcium	30 mg	β Carotene	0 µg
Protein	1.5 g	Phos.	22 mg	Thiamin	30 µg
Fat	1.4 g	Iron	0.9 mg	Riboflavin	90 µg
Carbos.	15.7 g	Sodium	1 mg	Niacin	900 µg
Fiber	5.1 g	Potassium	199 mg		
Ash	0.6 g	Ascorbic.	18 mg		

No. 58 Raspberry Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 46	
Water	83.1 g	Calcium	204 mg	β Carotene	1900 µg
Protein	1.9 g	Phos.	40 mg	Thiamin	100 µg
Fat	0.3 g	Iron	17 mg	Riboflavin	Tr.
Carbos.	13.4 g	Sodium	1 mg	Niacin	6500 µg
Fiber	1.4 g	Potassium	3226 mg		
Ash	1.4 g	Ascorbic.	62 mg		

No. 59 Rose Flowers

Amount of nutrient per 100g. (About ½ cup)				Calories: 16	
Water	94.8 g	Calcium	47 mg	β Carotene	400 µg
Protein	1.4 g	Phos.	86 mg	Thiamin	20 µg
Fat	0.3 g	Iron	1.0 mg	Riboflavin	110 µg
Carbos.	2.7 g	Sodium	18 mg	Niacin	600 µg
Fiber	0.6 g	Potassium	166 mg		
Ash	0.8 g	Ascorbic.	18 mg		

No. 60 Rose Hips

Amount of nutrient per 100g. (About ½ cup)				Calories: 54	
Water	91.3 g	Calcium	19 mg	β Carotene	300 µg
Protein	0.8 g	Phos.	18 mg	Thiamin	Tr.
Fat	0.4 g	Iron	0.6 mg	Riboflavin	Tr.
Carbos.	7.0 g	Sodium	1.2 mg	Niacin	400 µg
Fiber	1.1 g	Potassium	178 mg		
Ash	0.5 g	Ascorbic.	23 mg		

No. 61 Saguaro

Amount of nutrient per 100g. (About ½ cup)				Calories: 122	
Water	37.5 g	Calcium	43 mg	β Carotene	634 µg
Protein	13.1 g	Phos.	41 mg	Thiamin	95 µg
Fat	1.0 g	Iron	1.4 mg	Riboflavin	97 µg
Carbos.	41.5 g	Sodium	2 mg	Niacin	906 µg
Fiber	13.4 g	Potassium	403 mg		
Ash	6.9 g	Ascorbic.	52 mg		

No. 62 Saguaro Seeds

Amount of nutrient per 100g. (About ½ cup)				Calories: 528	
Water	4.8 g	Calcium	95 mg	β Carotene	0 µg
Protein	15.5 g	Phos.	305 mg	Thiamin	450 µg
Fat	29.1 g	Iron	3.4 mg	Riboflavin	200 µg
Carbos.	47.7 g	Sodium	4 mg	Niacin	3800 µg
Fiber	2.6 g	Potassium	339 mg		
Ash	2.9 g	Ascorbic.	0 mg		

No. 63 Sheep Sorrel (Wood Sorrel) Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 28	
Water	90.0 g	Calcium	66 mg	β Carotene	7740 µg
Protein	2.1 g	Phos.	41 mg	Thiamin	75 µg
Fat	0.3 g	Iron	1.6 mg	Riboflavin	100 µg
Carbos.	5.6 g	Sodium	5 mg	Niacin	465 µg
Fiber	0.8 g	Potassium	338 mg		
Ash	1.1 g	Ascorbic.	119 mg		

No. 64 Shepherd's Purse Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 33	
Water	88.2 g	Calcium	208 mg	β Carotene	2590 µg
Protein	4.2 g	Phos.	86 mg	Thiamin	250 µg
Fat	0.5 g	Iron	4.8 mg	Riboflavin	170 µg
Carbos.	5.2 g	Sodium	40 mg	Niacin	400 µg
Fiber	1.2 g	Potassium	394 mg		
Ash	1.9 g	Ascorbic.	36 mg		

No. 65 Sow Thistle Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 31	
Water	31 g	Calcium	146 mg	β Carotene	4500 µg
Protein	0.5 g	Phos.	44 mg	Thiamin	100 µg
Fat	0.8 g	Iron	2 mg	Riboflavin	200 µg
Carbos.	6.6 g	Sodium	32 mg	Niacin	700 µg
Fiber	2.0 g	Potassium	299 mg		
Ash	1.5 g	Ascorbic.	13 mg		

No. 66 Sow Thistle Shoots

Amount of nutrient per 100g. (About ½ cup)				Calories: 20	
Water	92.0 g	Calcium	93 mg	β Carotene	116 µg
Protein	2.4 g	Phos.	35 mg	Thiamin	150 µg
Fat	0.5 g	Iron	8 mg	Riboflavin	190 µg
Carbos.	4.2 g	Sodium	4 mg	Niacin	1000 µg
Fiber	0.6 g	Potassium	67 mg		
Ash	0.9 g	Ascorbic.	32 mg		

No. 67 Strawberry Fruit

Amount of nutrient per 100g. (About ½ cup)				Calories: 37	
Water	89.9 g	Calcium	21 mg	β Carotene	36 µg
Protein	0.7 g	Phos.	21 mg	Thiamin	30 µg
Fat	0.5 g	Iron	1 mg	Riboflavin	70 µg
Carbos.	8.4 g	Sodium	1 mg	Niacin	600 µg
Fiber	1.3 g	Potassium	164 mg		
Ash	0.5 g	Ascorbic.	59 mg		

No. 68 Sumac Fruit

Amount of nutrient per 100g. (About ½ cup)				Calories: 230	
Water	4.8 g	Calcium	93 mg	β Carotene	1700 µg
Protein	11.9 g	Phos.	57 mg	Thiamin	300 µg
Fat	16.8 g	Iron	10 mg	Riboflavin	300 µg
Carbos.	63.2 g	Sodium	95 mg	Niacin	2500 µg
Fiber	27.8 g	Potassium	980 mg		
Ash	3.2 g	Ascorbic.	143 mg		

No. 69 Sunflower Seeds

Amount of nutrient per 100g. (About ½ cup)				Calories: 560	
Water	4.8 g	Calcium	120 mg	β Carotene	30 µg
Protein	24.0 g	Phos.	837 mg	Thiamin	1960 µg
Fat	47.3 g	Iron	7 mg	Riboflavin	230 µg
Carbos.	19.9 g	Sodium	30 mg	Niacin	5400 µg
Fiber	3.8 g	Potassium	920 mg		
Ash	4.0 g	Ascorbic.	0 mg		

No. 70 Thistle Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 63	
Water	80.9 g	Calcium	20 mg	β Carotene	0 µg
Protein	3.0 g	Phos.	79 mg	Thiamin	Tr.
Fat	0.1 g	Iron	8.5 mg	Riboflavin	Tr.
Carbos.	15.3 g	Sodium	65 mg	Niacin	200 µg
Fiber	1.5 g	Potassium	410 mg		
Ash	0.7 g	Ascorbic.	0 mg		

No. 71 Thyme Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 60	
Water	80.0 g	Calcium	27 mg	β Carotene	400 µg
Protein	2.0 g	Phos.	44 mg	Thiamin	100 µg
Fat	1.6 g	Iron	27 mg	Riboflavin	100 µg
Carbos.	13.9 g	Sodium	12 mg	Niacin	1100 µg
Fiber	0.4 g	Potassium	177 mg		
Ash	2.6 g	Ascorbic.	113 mg		

No. 72 Tumbleweed Seeds

Amount of nutrient per 100g. (About ½ cup)				Calories: 369	
Water	4.2 g	Calcium	830 mg	β Carotene	0 µg
Protein	27.4 g	Phos.	540 mg	Thiamin	500 µg
Fat	14.4 g	Iron	143 mg	Riboflavin	200 µg
Carbos.	46.3 g	Sodium	11 mg	Niacin	4100 µg
Fiber	30.2 g	Potassium	1140 mg		
Ash	7.7 g	Ascorbic.	0 mg		

No. 73 Tumbleweed Shoots

Amount of nutrient per 100g. (About ½ cup)				Calories: 113	
Water	60.6 g	Calcium	973 mg	β Carotene	3500 µg
Protein	4.8 g	Phos.	67 mg	Thiamin	100 µg
Fat	0.7 g	Iron	5 mg	Riboflavin	200 µg
Carbos.	27.9 g	Sodium	4 mg	Niacin	1000 µg
Fiber	12.5 g	Potassium	2545 mg		
Ash	6.0 g	Ascorbic.	40 mg		

No. 74 Violet Flowers

Amount of nutrient per 100g. (About ½ cup)				Calories: 16	
Water	94.8 g	Calcium	47 mg	β Carotene	400 µg
Protein	1.4 g	Phos.	86 mg	Thiamin	20 µg
Fat	0.3 g	Iron	1 mg	Riboflavin	110 µg
Carbos.	2.7 g	Sodium	18 mg	Niacin	600 µg
Fiber	0.6 g	Potassium	166 mg		
Ash	0.8 g	Ascorbic.	18 mg		

No. 75 Wild Lettuce Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 18	
Water	94.0 g	Calcium	68 mg	β Carotene	1000 µg
Protein	1.3 g	Phos.	25 mg	Thiamin	60 µg
Fat	0.3 g	Iron	1.4 mg	Riboflavin	60 µg
Carbos.	3.5 g	Sodium	9 mg	Niacin	400 µg
Fiber	0.7 g	Potassium	264 mg		
Ash	0.9 g	Ascorbic.	18 mg		

No. 76 Willow Leaves

Amount of nutrient per 100g. (About ½ cup)				Calories: 35	
Water	90.0 g	Calcium	92 mg	β Carotene	5652 µg
Protein	1.6 g	Phos.	25 mg	Thiamin	110 µg
Fat	0.3 g	Iron	2.7 mg	Riboflavin	240 µg
Carbos.	7.3 g	Sodium	40 mg	Niacin	900 µg
Fiber	1.6 g	Potassium	382 mg		
Ash	0.8 g	Ascorbic.	68 mg		

No. 77 Wintergreen Fruit



Amount of nutrient per 100g. (About ½ cup)				Calories: 68	
Water	81.7 g	Calcium	69 mg	β Carotene	280 µg
Protein	2.4 g	Phos.	18 mg	Thiamin	42 µg
Fat	0.9 g	Iron	0.6 mg	Riboflavin	43 µg
Carbos.	14.4 g	Sodium	1 mg	Niacin	400 µg
Fiber	1.3 g	Potassium	178 mg		
Ash	0.5 g	Ascorbic.	89 mg		

No. 78 Yarrow Leaves



Amount of nutrient per 100g. (About ½ cup)				Calories: 103	
Water	65.4 g	Calcium	460 mg	β Carotene	Tr.
Protein	4.5 g	Phos.	125 mg	Thiamin	Tr.
Fat	1.2 g	Iron	Tr.	Riboflavin	Tr.
Carbos.	25.2 g	Sodium	3 mg	Niacin	Tr.
Fiber	5.9 g	Potassium	616 mg		
Ash	3.7 g	Ascorbic.	23 mg		



The first "A Survival Acre" at Linda's home wild food tours.

Burke's Cottages Sabael, NY wild food walk.



Runyon Institute, Warrensburg, NY wild food walk.

Part III: Wild Food Recipes

These recipes incorporate wild foods as much as possible. As you will see, wild foods can be used in all types of dishes including those that use meat, fish, and dairy foods. Of course, dishes made entirely of wild foods are *my* environmentarian preference. Those included here use meats, fish, dairy foods, and other “nonwild” foods and are adapted from various cultures.

The important thing is to *try* wild foods. Fit them into your diet occasionally at first, increasing to a daily basis. Supplementing your meals with wild food saves money. Most of the recipes may seem unfamiliar, but dare to use wild foods in a creative way and you will be pleasantly surprised!



A typical campfire meal: Food simmering on edge, drying over hot coals, casserole on back, hot cookies or biscuits on back rock.

Some suggestions for substitutions:

1. Anise flavor: Goldenrod leaves, flowers, and roots.
2. Asparagus: Milkweed shoots, fireweed tops.
3. Bran: Bulrush, crabgrass.
4. Broccoli: Milkweed buds and flowers, wintercress, mustard flowers.
5. Cabbage: Shepherd's purse, dandelion, chicory, and wild lettuce.
6. Carrot: Queen Anne's lace roots, evening primrose roots, thistle roots, Shepherd's purse roots, and purslane roots.
7. Coffee: Chicory, dandelion roots, yarrow, clover buds.
8. Corn on the cob: Green cattail heads.
9. Cucumbers: cattail pith, fireweed pith, sunflower pith.
10. Endive: Dock.
11. Fruit: Blackberries, blueberries, dandelion flowers, mullein flowers, evening primrose flowers, raspberries, roses, strawberries, and violets.
12. Granola: Phragmities, amaranth, lamb's quarters, clover.
13. Gum: Sap from balsam fir or pine, milk of wild lettuce, dandelion sap, milkweed sap.
14. Lemonade: Sumac, wood sorrel, and sheep sorrel.
15. Lettuce: Sow thistle, dandelion, chicory, wild lettuce, milk thistle, amaranth, malva neglecta, and lamb's quarters leaves.
16. Nuts: Pine seeds, seeds from malva neglecta.
17. Okra: Milkweed shoots, flowers, pods, small leaves.
18. Orange juice: Pine tea, sumac tea, and balsam fir tea.
19. Pepper: Thyme leaves and flowers.
20. Potatoes: Arrowhead, ground pine nuts.
21. Salt: Queen Anne's lace seeds, ground dried clover with dried garlic.
22. Sugar: Dried meadowsweet flowers.
23. Turnip greens: Plantain leaves, sow thistle leaves.

Some medicinal and cosmetic substitutes.

1. Aspirin: Willow.
2. Lampwick: Mullein leaf, dried and cut in strips.
3. Mothballs: Dried white clover.
4. Sedative: Chamomile, mullein.

Some Wild Food Menus

During the Runyon Institute days, students from Rutgers University experimented with recipes. Some recipes are from homestead days while others are shared with us by students of wild food classes. Still others are delectable recipes from gourmet cooks. To help clarify which recipes fit these groups please see the following symbols listed below.

Food Group Symbols

***** From Institute students
! Homestead days
x Given to us by Arizona students and individual people over the last ten years.
~ Gourmet cooks

Because of my vegetarian habits, the following recipes do not use meat or fish. Wild food recipes can be combined in a variety of ways and still fit the traditional meals of breakfast, lunch and dinner. Here are some menu suggestions to get you started on the road to an environmentarian diet.



Soups & Salads

Burdock Stem Soup*

2 cups 1-inch sections of burdock stems, peeled and sliced
1 quart water
2 tablespoons lemon juice or vinegar
pinch of thyme pepper, Queen Anne’s lace seeds to taste

Place burdock stems in a medium pot and cover with 2 cups water. Bring to a boil and simmer for 5 minutes. Drain. Add remaining 2 cups water, thyme pepper, and seeds. Bring to a boil and simmer for 5 minutes. Season with lemon juice or vinegar and serve hot.

Serves 4

Slow Cooker Filarie Soup x

1 large filarie head and root
1 medium onion, thinly sliced
1 small potato, peeled and diced (can substitute parsnips or Queen Anne’s lace root)

Wash the filarie head well, pulling out the buds and fruit. Scrub the root with a toothbrush. Place the filarie in a slow cooker and cover with water. Add the onion and potato, cover with water and simmer on high for 1 ½ hours. Serve hot.

Serves 4

Clover Soup !

1 1/2 cups chopped onions
6 cups water
3 cups clover leaves and flowers washed
4 teaspoons tamari or soy sauce
1 teaspoon wild thyme
salt or Queen Anne’s lace seeds to taste
3 cups cooked brown rice (optional)

Simmer the onions in the water for 20 minutes. Add the remaining ingredients, except rice, and simmer 10 minutes. Eat as broth or stir in the brown rice and cook until the rice is done.

Variation: Add 2 cups chopped dandelion root and 1 cup sliced carrots to the water and simmer with the onion.

Serves 6

Lamb's Quarters Fat Hen Soup x

1 pound lamb's quarters leaves and seeds (6 to 8 cups), washed
1 large onion, chopped
1 teaspoon salt or Queen Anne's lace seeds
1/4 teaspoon freshly ground black or thyme pepper
1/4 teaspoon freshly grated nutmeg
1 garlic clove, crushed
2 tablespoons butter or olive oil
2 teaspoons whole wheat flour
1/2 cup milk or water
1/2 cup sour cream or water
2 teaspoons pine nuts

Boil the lamb's quarters in water to cover until tender, about 5 minutes. Add onion, salt or seeds, pepper, and nutmeg. Cover and simmer 10 minutes. Remove from the heat and cool.

Put the mixture in a blender and puree to a smooth, deep green. Add the garlic and blend again. Melt the butter in a medium saucepan over moderate heat. Stir in the flour and cook 1/2 minute. Add the milk, then sour cream or water to make a white sauce. Stir to blend, then serve lamb's quarters into bowls, top with white sauce and garnish with pine nuts.

Serves 6

Delicate Mallow Soup!

1 cup malva neglecta leaves, washed
2 cups water
1 small onion, thinly sliced
1/4 cup malva neglecta seeds

Combine the leaves and water in a medium pot. Bring to a boil over medium heat, then turn off heat, stir and cover. Cool for 10 minutes.

Strain the leaves if you wish, then add the onion and seeds. Serve hot.

Serves 2

Simple Nettle Soup!

3 cups nettles, washed and sliced (use any part of whole plant: leaves, flowers, seeds, or stems)
4 cups water
2 tablespoons butter
3 garlic cloves, crushed
salt or Queen Anne's lace seeds to taste

Combine all ingredients in a large pot and simmer for 20 minutes. Serve hot with whole-grain bread.

Serves 4

Nettle Chowder x

4 cups water
1 1/2 cups diced potatoes
1 cup sliced carrots (wild if available)
2 celery stalks, sliced
1 cup chopped onion
3 garlic cloves, crushed
1/2 teaspoon fresh or dried marjoram
1 teaspoon dried or fresh thyme leaves
Salt or Queen Anne's lace seeds to taste
4 cups nettles, washed and sliced (any part of whole plant: leaves, flowers, seeds, or stems)
2 cups soymilk

Combine the water, potatoes, carrots, celery, onion, herbs, and seeds in a large pot. Simmer 30 minutes, then add nettles and simmer another 20 minutes. Add soymilk and heat gently, but do not boil. Serve hot!

Serves 6

Sesame Thistle Soup*

3 tablespoons butter
1 cup chopped thistle root (any species)
3 cups water
2/3 cup sesame seeds
4 garlic cloves, crushed
1 cup dandelion flowers
Queen Anne's lace seeds or salt to taste
3 cups cooked brown rice

Melt the butter in a medium skillet. Sauté the thistle, sesame seeds, and garlic until the seeds are golden brown, about 2 minutes. Add the dandelion and cook another 5 minutes. Add the seeds or salt to taste, then serve over brown rice.

Serves 6

Milk Thistle Soup with Yellow Squash x

6-8 milk thistle leaves
1 cup cooked, pureed yellow squash
garlic bud (optional)

Place milk thistle leaves in water and simmer until soft and pliable (5-10 minutes). Puree in a blender. Place milk thistle puree and squash puree in two separate pots and heat. Pour in shallow soup dish, one side at a time so you have a dark half and a light half (ying and yang) in your bowl. Press garlic bud and sprinkle over the top.) Serve hot!

Serves 2

Sow Thistle Soup x

1 cup sow thistle tips
1 clove garlic
1 onion, thinly sliced

Place sow thistle tips in water to cover. Simmer 20 minutes on low heat. (Crock pot is excellent; simmer for 1 hour on low.) Add garlic, onion, and serve hot.

Serves 2

Tumbleweed Soup x

1 cup tumbleweed tips
1 clove garlic
1 thinly sliced onion

Place tips in water to cover. Simmer 20 minutes on low heat. Or use a crock pot for more flavor and cook at low heat for 1 hour. Add pressed oil from garlic and garnish with onion.

Serves 2

Greens Soup *

1 cup fresh sorrel leaves, flowers, stems
1 thinly sliced onion

Place sorrel in a pot and cover with water. Add onion and simmer for a few minutes. Leaves will turn from bright green to olive green. This is normal and ensures the oxalic acid crystals are destroyed. Serve hot. Delicious!

Serves 2

Creamed Sorrel Soup ~

4 cups washed sorrel leaves
2 teaspoons safflower oil or olive oil
2 teaspoons wheat germ
1 onion, chopped
4 cups non-fat dried milk, or goat's milk, or water

Place leaves in pot, cover with water and simmer slowly for 1/2 hour. Blend in remaining ingredients, simmer and strain.

Serves 4

Wild Lettuce Salad *

1 cup wild lettuce leaves, washed
1/2 cup wild lettuce buds and flowers, washed
1/2 cup shredded red cabbage
1 garlic clove, crushed
1 teaspoon wild thyme leaves fresh or dried
3 tablespoons oil, 3 tablespoons vinegar of choice

Combine all ingredients, toss gently, and serve.

Serves 4

Fresh Dandelion Salad !

4 cups fresh dandelion greens
clove of garlic, chopped, or garlic salt
pinch of thyme pepper

Drain the dandelion greens. Rub the garlic on a salad bowl. Add chopped garlic pieces to bowl, and place drained leaves in bowl. Add your favorite dressing.

Serves 3

Hot Dandelion Salad *

4 handfuls fresh (young, new) dandelion leaves
sesame oil or olive oil
thyme pepper

Wash dandelions. If desired, soak bitter leaves in salted water for about 1 hour then wash and drain. Place the leaves in a frying pan and add the oil. Heat slowly to a moderate heat while stirring the leaves until they are wilted. Remove, serve hot!

Serves 4

Daisy Petal Salad x

1 quart freshly picked daisy petals

Wash petals, place in salad bowl and add your favorite dressing. Or put petals in pita sandwiches with favorite garnish.

Serves 4-6

Spring Wild Coleslaw x

1/2 cup dandelion
1/2 cup plantain
1/2 cup clover
1/2 cup chickweed
1/4 cup curley dock
1/2 small peeled onion
2 tablespoons oil and vinegar

Wash all ingredients well and drain in a sieve. Process all parts plus onion in a processor until completely "slawed". Add oil and vinegar (or your favorite dressing). Serve as a side dish.

Chickweed Salad x

1 clove garlic
1 quart loosely packed chickweed, washed
2 eggs, hard-cooked
4 tablespoons favorite dressing

Peel clove of garlic and rub wooden salad bowl. Chop chickweed finely and add to salad bowl. Peel eggs, slice thin and add to bowl. Toss together with favorite salad dressing.

Serves 4

Star Chickweed Dressing x

2 cups star chickweed, washed
3/4 cup plain yogurt
3/4 cup mayonnaise
1/2 tablespoon garlic powder or 4 cloves fresh
1 tablespoon dried dill
salt to taste

Combine all ingredients in a blender or food processor. Blend on medium speed, then refrigerate for 30 minutes. Serve on your favorite salad or casserole. Sandwiches also taste delicious spread with this dressing.

Makes 2 cups of dressing

Evening Primrose Olive Oil*

1 cup evening primrose flowers, washed and dried
approx. 1\2 cup extra virgin olive oil (sunflower,
safflower, or corn oil can be substituted)

Fill a 10-ounce jar to capacity with evening primrose flowers. Add oil at room temperature or boiling to cover. (Be careful with hot oil in glass jars.) Repeatedly press down the flowers until all the air bubbles are out of the mixture. Cap and shake every day for or 1 week for sunflower, safflower, or corn oil, or 2 weeks for olive oil. Remove the flowers and discard. Refrigerate oil if you used sunflower, safflower, or corn oil. Use for salads.

Makes approximately 10 ounces

Vegetable Dishes & Light Meals



Linguine with Amaranth Cream Sauce~

2 tablespoons butter
4 garlic cloves, crushed
3 cups soymilk or cow's milk
4 tablespoons rice or wheat flour
1 cup crushed dried young amaranth
1 pound linguine, cooked until al dente

In a large frying pan, melt the butter and sauté the garlic over low heat for about 10 minutes. In a saucepan, mix the milk and flour to make a thin paste. Add the flour mixture and amaranth and heat until smooth and thickened, about 3 minutes. Serve over the linguine.

Serves 2 to 3 as a main course

Arrowhead Stew!

1 large onion, sliced
1 cup washed roots: thistle, dandelion, evening primrose, or filarie
12 to 14 arrowhead tubers, washed
1/2 teaspoon Queen Anne's lace seeds
1 teaspoon dried thyme leaves

Combine all ingredients in a slow cooker and add water to cover. Cook on low setting for 4 hours or until tender.

Serves 4 as a main course

Clover Noodles~

1 cup clover flour (See page 78)
3 to 5 cups unbleached white flour
5 eggs
1 tablespoon olive oil
1/2 teaspoon salt or Queen Anne's lace seeds

Put clover flour into bowl and add enough water to reconstitute to a moist consistency. Stir in eggs, oil, & salt. You should have a slimy green soup. Add white flour until you make a stiff dough. Remove and kneed till it won't tear when you stretch it. Let rest 30 minutes. Cut dough ball into about seven or eight equal sized balls, and run through pasta machine. Start on setting #1 and then press through 2, 3, and 5. Add flour with each run through the machine to avoid sticking.

Dry on racks of food dryer. Let cool, store in tightly sealed glass jars. Serve cooked to al dente and topped with butter or add your favorite vegetable.

Serves 8-10

In a pasta machine, clover noodles can be made by replacing 2 tablespoons of flour with 2 tablespoons of clover flour. Adjust the liquid as necessary to get the right texture, extrude and serve.

Makes approximately 4 servings

Clover Pasta with Beans and Basil x

1 pound clover pasta
4 tablespoons olive oil
4 to 6 garlic cloves
1 cup garbanzo beans (chickpeas)
6 tablespoons water or tomato puree
1/2 teaspoon freshly ground black pepper or
  1/4 teaspoon ground dried thyme
12 large basil leaves
1 tablespoon fresh parsley, chopped
1/4 cup grated Romano cheese (optional) or
  1 teaspoon Queen Anne's lace seeds or salt

Cook the pasta until al dente, then drain and set aside. In a food processor or blender, puree olive oil and garlic. Add garbanzos and water or tomato puree and blend. Blend in the pepper, basil, parsley, and cheese or seeds and blend quickly until mixture is a coarse paste. Toss with pasta and serve.

Serves 4 as a main course

Burdock Bur Casserole*

2 cups young burdock burs and leaves
1 teaspoon thyme leaves
1 teaspoon Queen Anne's lace seeds
1 cup nonfat dry milk or water
4 tablespoons butter or 2 teaspoons safflower, olive oil
1 cup whole wheat bread crumbs

Preheat the oven to 350 degrees. Wash the burs & leaves and place in a large saucepan. Add water to cover and simmer for 5 minutes. Drain.

Add the thyme and seeds, cover with water and simmer for 5 another minutes. Drain and save the water for soup stock.

Put the burs in a greased 1 1/2-quart casserole dish. Add the milk or liquid and oil. Top with bread crumbs and bake for 20 minutes.

Serves 4 as a main vegetable casserole

Cattail "Corn On The Cob" !

2 to 3 cattail heads
safflower, olive oil, or butter
salt or Queen Anne's lace seeds
thyme pepper to taste

Put the cattail in a large pot of boiling water and boil for 7 minutes. Remove and serve with oil or butter, salt or seeds, and thyme.

Serves 1 as a side dish

Note: When cutting, leave 2 inches of stem for holding the cob

Cattail Casserole!

2 cups cattail fluff, scraped from brown buds
1 cup bread crumbs
1 egg, beaten (optional)
2 to 3 teaspoons water
Queen Anne's lace seeds or salt to taste
1/4 teaspoon thyme leaves, fresh

Preheat the oven to 325 degrees. Combine all ingredients in a greased 1 1/2-quart casserole dish and bake for 25 minutes. Serve hot.

Serves 4 as a main dish

Chickweed Pita Pockets x

2 cups chickweed, washed
1/2 cup finely chopped tender lamb's quarters leaves, washed
1/2 cup sliced carrot
1/2 cup finely diced cucumber
1 tablespoon salad dressing of your choice
2 pita breads

Toss together the chickweed, lamb's quarters, carrot, cucumber, and dressing. Fill the pita pockets and serve.

Makes 2 sandwiches

Chickweed Mediterranean x

2 tablespoons olive oil
1 garlic clove, finely chopped
2 cups whole chickweed plant without roots, washed
1 teaspoon thyme leaves

Heat the olive oil in a medium frying pan. Sauté the garlic until browned, then add the chickweed and thyme. Stir-fry until piping hot, about 10 minutes.

Serves 3 as a side dish

Hot Clover and Rice with Butter Sauce x

4 cups cooked brown rice
4 cups washed clover leaves
1 cup milk or water
1/4 pound butter or soy butter
1 teaspoon finely minced garlic, or 2 teaspoons garlic powder

Preheat the oven to 350 degrees. Grease a 2-quart casserole dish. In the casserole, combine the rice, clover, and liquid.

Melt butter in a saucepan over low heat. Add garlic and cook for 3 minutes. Stir sauce into casserole and bake for 20 minutes until piping hot.

Serves 4 as a main course

Dandelion Greens Casserole !

2 cups dandelion leaves, washed
1 cup whole wheat bread crumbs
2 cups water

Preheat the oven to 350 degrees and grease a 1-quart casserole dish. Put the leaves in a 1-quart saucepan and add water to cover. Simmer gently for 20 minutes, then drain, reserving the liquid. Chop the leaves fine and pour into the casserole dish. Add the reserved liquid and top with the bread crumbs. Bake for 25 minutes or until brown on top.

Serves 3 to 4 as a main course

Southern Italian Dandelion Leaves ~

4 cups young 2 to 3-inch dandelion leaves, washed
1 medium potato or arrowhead tubers, peeled
2 teaspoons safflower or sesame oil
1 medium onion, cubed
1 large tomato or 1 8-ounce can whole tomatoes, chopped

Combine the dandelion leaves and potato in a medium pot and cover with water. Bring to a boil and simmer for 15 minutes. Remove the potato or arrowhead, then cube and set aside. Drain the leaves, squeezing out the water. (Save the liquid for soup stock.)

Heat the oil in a large frying pan and sauté the onion slowly until limp, about 5 minutes. Combine the dandelion leaves, potato or arrowhead, and tomato, and bring to a boil. Remove from the heat and stir.

Serves 4 to 6 as a main course

Dandelion Stir Fry ~

3 tablespoons olive oil
1 cup chopped onion
4 garlic cloves, crushed
1/4 cup chopped dandelion root, scrubbed
2 cups fresh dandelion leaves, washed
2 cups dandelion flowers, washed
1 teaspoon dried thyme or 1 sprig fresh thyme
1/2 teaspoon dried marjoram leaves or 1 fresh sprig
2 teaspoons sesame salt
2 tablespoons cider vinegar
2 cups cooked brown rice

Heat half the oil in a large wok or frying pan. Add the onion, garlic, and dandelion roots. Sauté for 5 minutes or until soft. Remove from the wok and set aside in a warm place.

Heat the remaining oil in the wok and add the dandelion leaves and flowers, thyme, marjoram, salt, and vinegar. Stir-fry for 10 minutes. Stir in the onion mixture and serve over brown rice.

Serves 6 as a main course

Dandelion Roots *

1/2 cup washed and peeled white dandelion roots,
    chopped into French fry sized pieces
1 cup favorite pancake butter
2 tablespoons safflower oil
1 chopped onion

Dip the roots in the pancake batter. French fry in hot safflower oil until brown. (A wok works perfectly.) Add the chopped onion as a garnish and serve.

Serves 2 as a side dish

Chamomile Vegetable !

Chop a whole chamomile plant into bite-sized pieces and simmer gently for 6-8 minutes. Serve hot with favorite garnish. A delicious broccoli substitute. Servings vary depending on plant size.

Tofu Scallopine with Dandelion Wine ~

1 pound firm tofu, weighted and drained for at least 1 hour
whole wheat flour
3 tablespoons olive oil
1 bay leaf
1/2 cup Dandelion Wine (Page 246) or marsala
10 large fresh mushrooms, sliced
1 large garlic clove, finely minced
1 teaspoon chopped chives
1 teaspoon chopped fresh parsley
juice of 1/2 lemon
1 teaspoon Worcestershire sauce
Queen Anne's lace seeds or salt to taste
Ground thyme or black pepper to taste
6 lemon wedges for garnish

Slice the tofu into 12 equal portions and coat each piece with flour. Heat the oil in a large frying pan and sauté the tofu with the bay leaf until tofu is light brown on both sides- about 6 minutes. Remove the tofu and set aside.

Add the wine and reduce the liquid by one-half. Add the mushrooms, garlic, chives, parsley, lemon juice, Worcestershire sauce, seeds or salt, and thyme or pepper. Cook for 3 minutes.

Add the tofu slices and simmer for 5 minutes, adding additional wine or water if necessary to keep mixture moist. Serve the tofu slices with pan juices and garnish with a lemon wedge and parsley

Serves 6 as a main course

Rosemary Tofu x

3 tablespoons butter or soy butter
1 pound firm tofu, weighted, drained and cubed
4 garlic cloves, crushed
1 1/2 teaspoons dried rosemary leaves
2 cups diced young lamb's quarters or amaranth leaves, washed
3 cups cooked brown rice

Melt the butter in a large frying pan. Sauté the tofu, garlic, and rosemary for 20 minutes, stirring often. During the last 5 minutes of cooking, add the leaves and sauté until tender. Serve hot over brown rice.

Serves 6 as a main course

Evening Primrose Stew !

5 to 6 Evening primrose roots
1 medium potato, halved
1 medium onion, quartered
1 teaspoon thyme leaves dried or fresh
1 teaspoon Queen Anne's lace seeds

Wash the roots and scrub with a toothbrush, trimming off any bruised parts. Combine the roots, potato, and onion in a slow cooker and add water to cover. Cook on low for 4 to 6 hours, then serve while hot.

Serves 2 as a main course

Dock Casserole *

2 large bunches dock, including leaves
4 to 6 tablespoons butter or safflower oil

Preheat oven to 350 degrees. Wash and drain the dock and steam in a pot until all parts are wilted, about 2 minutes. Discard the tougher stems and finely chop the leaves and short stems. Steam the chopped mixture for about 15 minutes more, stirring frequently. Pour the mixture into a 1-quart casserole dish, dot with butter or drizzle with oil, and bake for 20 minutes or until bubbly hot.

Serves 4-6 as a main course

Lemon Fireweed x

2 cups fireweed tips, washed
1 lemon wedge
4 to 5 thyme sprigs

Steam the fireweed tips until tender, about 2 minutes. Squeeze the lemon over the tips, then sprinkle on the thyme.

Serves 4 as a side dish

Filarie Sandwich x

1 handful filarie leaves, washed
pinch dried thyme leaves
1/4 teaspoon each of oil and vinegar
1 Bermuda onion, thinly sliced into rings
2 slices whole wheat bread

Layer the ingredients between the bread slices for a "desert sandwich" treat.

Makes 1 sandwich

Fireweed Casserole *

4 cups fireweed buds, washed
1 medium onion, chopped, or 1 cup chopped chives
bread crumbs

Preheat the oven to 350 degrees and lightly grease a 1 1/2-quart casserole dish. Mix the buds and onion or chives and place in the casserole dish. Add water to cover. Bake for 30 minutes or until bubbly. Top with bread crumbs.

Serves 4

Wild Sow Thistle Stir-Fry !

1 cup wild sow thistle leaves
1/2 cup wild sow thistle buds and flowers
1/2 cup red cabbage
1 clove garlic, pressed
1 teaspoon wild thyme
3 tablespoons oil and vinegar

Combine all ingredients in a salad bowl, toss gently and serve.

Serves 2

Aloe Vera Flowers x

Eat flowers raw and add to favorite sandwiches, salads. Dip flowers in favorite sauces.

Wild Greens Quiche ~

Crust

- 3 cups cooked brown rice
- 1 cup sesame seeds
- 2 tablespoons butter
- dash of salt

Filling

- 1 tablespoon butter
- 1 medium onion, chopped
- 8 ounces fresh mushrooms, sliced
- 4 garlic cloves, crushed
- 3 cups mixed wild greens (lamb's quarters, amaranth, clover, dandelion, curly dock, or plantain), washed
- 1/2 teaspoon salt
- 3 eggs, beaten
- 1 cup milk
- 1 teaspoon marjoram leaves
- 1 teaspoon chopped basil leaves
- 1/2 teaspoon thyme leaves

Preheat the oven to 350 degrees.

Mix the brown rice, sesame seeds, butter, and salt in a bowl and press into a 12-inch pie dish. Set aside. Melt the butter in a large skillet. Add the onion, mushrooms, garlic, greens, and salt and sauté until tender, about 10 minutes. Set aside.

Combine the eggs, milk, marjoram, basil, and thyme and sauté until tender, about 10 minutes. Combine with greens and pour into shell. Smooth top and bake for 45 minutes, or until brown and crispy on the top.

Serves 8 as a main course

Baked Purslane with Yogurt x

- 1 cup fresh purslane, washed
- 1 pint yogurt

Preheat the oven to 350 degrees. Mix the purslane and yogurt and pour into a greased 1-quart casserole. Bake 10 to 15 minutes or until hot.

Serves 2 as a side dish

Tabouli with Wild Greens ~

1 cup young dandelion leaves
1 cup daisy leaves
1 cup red clover leaves
1 cup chopped sheep sorrel leaves
1/2 cup violet leaves
1/4 cup chopped spearmint leaves
1/4 cup chopped fresh oregano, or 2 teaspoons dried
1 1/2 cups cooked brown rice
1 1/2 cups cooked bulgur
oil and vinegar to taste
1 cup daisy petals
1 cup violet and strawberry flowers or wild roses

Wash and drain all greens and tear into bite-size pieces. Place in a large salad bowl. Toss in the rice, bulgur, oil, vinegar. Arrange the daisies around the edge of the bowl and place the violets and strawberries or roses in the middle. Chill and serve.

Serves 6 to 8

Lamb's Quarters Calzone x

Dough

1/4 cup warm water
1 tablespoon active dry yeast
4 teaspoons honey
1 cup soymilk
2 eggs
3 cups unbleached all-purpose flour
1/4 cup lamb's quarters flour
1 1/2 teaspoons sea salt

Filling

1 cup pizza sauce
1 teaspoon chopped garlic
1 medium onion, chopped
1 cup chopped fresh mushrooms
1 green bell pepper, chopped
1/2 cup chopped ripe olives
1/4 cup chopped lamb's quarters
12 ounces fresh mozzarella cheese, shredded
3 tablespoons olive oil

Put the warm water into a small bowl and stir in the yeast and honey; let the mixture stand until foamy, 5 to 10 minutes. Whisk the soymilk and 1 egg into the yeast mixture.

In another large bowl, mix the flours and salt. Make a mound of flour then make a well in the middle. Gradually pour the yeast and milk mixture into the well, working the flour from the inside of the well into the liquid with your fingers. Continue until all the flour is absorbed, adding 1 tablespoon of water if needed. Knead until soft, velvety, strong, and elastic, 10 to 15 minutes. Place the dough in a lightly oiled bowl, cover with a damp cloth, and put in a warm place. Let the dough rise until doubled, about 2 hours.

Mix the ingredients for the filling and set aside.

Knead the dough briefly on a lightly floured surface. Cut the dough into 6 or 7 pieces. Shape each piece into a ball, flatten it hard with your hand, and roll it into a 1/4-inch thick oval with a rolling pin. Mix the remaining 1 egg with 1 tablespoon of water and brush the edge of each shaped oval with the mixture.

Preheat oven to 450 degrees, lightly oil a baking sheet.

Place 2 tablespoons of pizza sauce in the center of each dough oval. Add a little garlic, onion, mushrooms, green pepper, olives, and lamb's quarters to each and top with cheese. Fold over the dough to form a half-moon shape, crimping the edges with a fork. Place the calzones on the baking sheet and brush each with the oil. Bake for 20 to 25 minutes or until golden brown. Brush again with oil and serve hot.

Serves 6 to 7

Weed Pizza x

2 tablespoons butter or olive oil
3 cups mixed wild greens, such as clover, plantain, dandelion, lamb's quarters, washed
dash of salt
1 pound ready-made pizza dough, thawed if frozen, toppings of choice

Preheat the oven to 425 degrees. Heat the butter or oil in a large frying pan. Add the greens and salt, and sauté for 5 minutes or until tender. Roll out pizza dough according to package instructions. Spread the greens on the crust and sprinkle with toppings. Bake for 20 minutes or until crisp.

Makes 6 slices

Malva Neglecta and Lamb's Quarters Quiche x

6 eggs
1 tablespoon lemon pepper
1 cup chocolate flavored soymilk
1/4 cup chopped malva neglecta leaves
1/4 cup chopped lamb's quarters
1/4 cup grated carrot
2 tablespoons chopped onion
1 teaspoon chopped garlic
1 9-inch pie shell, unbaked

Preheat the oven to 350 degrees. Process the eggs, lemon pepper, and soymilk in a blender or food processor until thoroughly blended. Stir in the malva neglecta leaves, lamb's quarters, carrot, onion, and garlic. Pour the mixture into the pie shell and bake for 35 minutes or until a knife inserted in the center comes out clean. Serve hot.

Serves 5 to 6 as main course

Milkweed Pod Fritters *

12 milkweed pods, washed. Note: Pick the milkweed pods when they are young and not elastic, 2 to 3 inches in length.
1 to 1 1/2 quarts water
1 cup cornmeal
1 cup whole wheat flour
1/4 cup safflower or peanut oil

Place the pods in a large bowl and cover with the water. In a separate bowl, combine the cornmeal and flour. Roll the pods in this mixture.

Heat the oil in a frying pan. Fry the pods, turning them over, until they are cooked through and brown on all sides, about 5 minutes. Drain well.

Serves 4 as a main dish

Milkweed Casserole *

3 cups milkweed buds, washed
2 cups milk or water
1 cup whole wheat bread crumbs

Preheat the oven to 350 degrees. Grease a 2-quart casserole. Place the milkweed buds and milk or water in casserole. Sprinkle the bread crumbs on top. Cook for 20 to 30 minutes, or until bubbly and brown on top.

Serves 6 as a main course

Young Milkweed and Pasta Medley ~

1 pound assorted pasta (rigatoni, linguine, broken into thirds, small shells, bucatino broken into thirds)
2 tablespoons olive oil
1/4 cup chopped wild onions or yellow onion
3 garlic cloves, coarsely chopped
1/4 cup dry sherry
2 cups milkweed shoots and leaf buds, blanched
ground thyme or pepper, Queen Anne's lace seeds or salt
1/4 cup chopped fresh parsley or watercress
1/4 cup grated Pecorino Romano cheese (optional)

Cook the pastas until al dente; drain and set aside. Heat the oil in a frying pan and sauté the onions and garlic until lightly browned. Add the wine and cook until the liquid is reduced by half, about 9 to 10 minutes. Add the milkweed and sauté until tender, approximately 10 minutes. Add the pastas and toss, heating thoroughly. Season to taste with thyme and seeds as salt. Garnish with parsley or watercress and sprinkle with cheese.

Serves 4 as a main course

Daisy Leaves a la Mediterranean x

2 cups washed daisy leaves
2 tablespoons olive oil
1 clove garlic, chopped finely
1 teaspoon thyme

Heat frying pan and add olive oil and chopped garlic. Brown garlic and add washed daisy leaves. Stir until piping hot.

Serves 1

Mustard Greens Casserole *

2 big bunches wintercress greens stems, leaves, and flowers
4 to 6 tablespoons safflower oil or butter

Preheat the oven to 350 degrees. Wash and drain the wintercress. Steam until wilted, about 3 minutes. Remove the tougher stems and chop the leaves & short stems finely. Steam the chopped mixture for 15 minutes more, stirring frequently. (Keep the water used in steaming for soup stock; freeze if necessary.) Pour the greens into a casserole dish, dot with oil or butter, and bake for 8 minutes or until hot and bubbly.

Serves 4 as a side dish

Stir-Fried Mustard Flowers *

1 quart mustard flower heads
1 garlic clove, chopped
1 tablespoon olive oil

In a frying pan or wok, quickly stir-fry all ingredients over high heat until limp, about 2 to 3 minutes. Serve hot.

Serves 4 as a side dish

Mustard Flower Buds

4 cups mustard flower buds
1 quart boiling water
2 tablespoons olive oil

Wash the buds thoroughly and add to boiling water. Lower heat, and simmer 5 minutes. Drain, add oil, and serve hot.

Serves 4 as a side dish

Vegetarian Burger x

2 cups cooked lentils
1/2 onion, peeled
2 tablespoons sow thistle leaves

Steam then chop thistle leaves. Add other ingredients and mix until everything sticks together.

Makes 6 medium-size burgers

Nettle-Falafel Burgers x

1 cup cooked and finely chopped nettles
1/2 cup falafel mix (see box for recipe)
2 tablespoons olive or safflower oil

Place the nettles in a medium bowl and add the falafel mix slowly. Mix thoroughly. Add a bit of water at a time until a clay-like mixture results. Pat the mixture into 3-inch patties. Heat the oil in a medium frying pan and fry the burgers slowly until brown on both sides, about 6 minutes.

Serves 2 to 3 as a main course

Boiled Mustard Greens !

1 quart young mustard leaves
1 garlic clove, chopped
1 teaspoon lemon juice
1 teaspoon vinegar
1 tablespoon soy butter or regular butter.

Boil the leaves for 30 minutes in a large saucepan. Drain well and add the garlic, lemon juice, vinegar, and butter. Serve hot.

Serves 2 as a side dish

Purslane Casserole !

1 teaspoon peanut or olive oil
4 cups purslane (including stems), washed, drained, and chopped
1 egg, beaten, or violet leaf thickener, opposite page
1/2 cup fine bread crumbs

Preheat the oven to 325 degrees and grease a 1 1/2-quart baking dish with oil. To the purslane add the egg or violet thickener and the bread crumbs. Turn into the baking dish, and add your favorite seasoning. Bake for 20 minutes or until piping hot.

Serves 4 as a side dish

Mexican-Style Purslane ~ (Vertalogas)

The following recipe was given to me by a Mexican friend. It is a common dish in Arizona.

1/2 pound purslane leaves and tender stems
1 teaspoon baking soda
1/2 pound pork chops or ribs
1/4 medium onion, chopped
1 garlic clove, chopped
1 medium tomato, chopped
1/2 teaspoon chicken broth

Place the purslane in boiling water with a pinch of baking soda and cook until tender, about 2 to 3 minutes.

In a large skillet, brown the meat on both sides and set aside. In the same pan sauté' the onion, garlic, and tomato until tender. Stir in the broth, purslane, and meat, and simmer for 15 to 20 minutes or until meat is done.

Serves 5 as a main course

Violet Leaf Thickener x

a handful of violet leaves
1/4 cup boiling water f

Press leaves down under boiling water. Do this slowly and continue for about 20 minutes. Drain. Green water is slightly gooey-or thickened. Use as water substitute. For cassaroles, layer whole violet leaves throughout casserole. Water from other ingredients will draw thickener from the edible violet leaves.

Wild Lettuce Stir-Fry x

1 cup wild lettuce leaves
1/2 cup wild lettuce buds and flowers
1/2 cup red cabbage
1 clove garlic, pressed
1 teaspoon wild thyme
3 tablespoons oil

Stir-fry all ingredients the oil, serve hot.

Serves 4

Brown Rice and Lamb's Quarter Sprouts x

1 cup lamb's quarter sprouts (sprout seeds only
  1 1/2 to 2 days)
2 tablespoons corn oil or peanut oil
1 tablespoon chopped scallions or chives or onions
1/4 cup thin sliced canned or fresh mushrooms
1 cup cooked brown rice

Heat oil in heavy fry pan or wok. Add onion, mushrooms. Stir fry until lightly brown. Add soy sauce, rice and sprouts. Stir fry for 3 to 4 minutes. Cover and simmer for 5 more minutes.

Serves 3 to 4

Wild Malva Rice Roll-Ups x

1 cup water
12 large malva neglecta leaves
1 cup cooked wild rice
1/2 teaspoon thyme
1/2 teaspoon vegetable salt (of your choice)
small casserole dish, greased
1/4 cup salsa to your taste

Bring water to a boil. Wilt malva leaves by gingerly dipping each leaf separately into boiling water. Rearrange leaf on a paper towel to drain. Place wild rice in a bowl. Stir in thyme and 1/4 teaspoon vegetable salt.

Take a teaspoon of mixture and place in the middle of the leaf. Roll the leaf and mixture up to stem, then tuck stem end in to secure. Place whole roll-up face down in casserole dish. Sprinkle rest of vegetable salt over roll-up and bake in oven for 20 minutes at 350 degrees. Pour salsa over each and serve hot.

Serves 2

Malva Mexican Style

1 cup large Malva leaves
1/2 cup salsa sauce or spaghetti sauce
1 cup refried beans1 ice cube tray

Place ice cube tray on counter. Drip salsa sauce in tray as evenly as you can. Place a leaf into cube section over salsa. Take a teaspoon and place a spoonful of refried beans into the leaf. Place the ice cube tray into the freezer and freeze solid.

Pop sections out into a freezer bag with a ziplock top. When you cook a casserole, take a few ready-made sections out and place in a bean pot. Cook 350° for 20 minutes. Delicious!

Makes 1 tray full of stuffed Malva leaves



Stuffed Malva leaves. Cook freshly rolled or freeze in ice cube trays for future meals. Store in plastic bags.

Willie Whitefeather and Linda.
Note his handmade shirt, moccasins and flute.

Muffins, Breads, Biscuits & Pancakes

Basic Mix x

4 1/4 cups whole wheat flour
4 1/4 cups amaranth or triticale flour (see Note)
5 tablespoons baking powder
1 teaspoon baking soda
1 tablespoon ground dried Queen Anne's lace seeds
2 teaspoons cream of tartar
1 1/2 cups instant dry milk
1 1/2 cups olive or peanut oil

In a large bowl, sift together the flours, baking powder, baking soda, seeds, cream of tartar, and dry milk. Blend well. With a wooden spoon, stir in the oil until evenly distributed; the mixture will be only slightly damp. Put the mix in a large, airtight container and label. Store in a cool, dry place. Use within 10 to 12 weeks.

Makes 11 cups, enough for several batches of crackers.

Note: Triticale flour is made from a high-protein grain that is a hybrid between wheat and rye. The flour is available in some natural foods stores.

Amaranth Vegetable Bread x

1 package active dry yeast
1/4 cup warm water
6 cups all-purpose flour or 10 cups whole wheat flour
4 cups cooked, drained amaranth greens

Dissolve the yeast in the warm water. Place flour in a large bowl and mix in the yeast. Add the greens and mix by hand, kneading the dough for 3 minutes. Cover and let rise 1 hour, or until doubled in bulk.

Preheat the oven to 400 degrees. Punch dough down and form into 2 loaves. Place on a baking sheet and let rise again until doubled, about 45 minutes. Bake loaves for 40 minutes, or until they sound hollow when tapped. Serve hot. These loaves freeze well.

Makes 2 loaves

Mean Green Bread x

2 tablespoons active dry yeast
3 tablespoons honey
2 1/2 to 2 3/4 cups warm water
4 cups whole wheat flour
2 cups fresh greens (dandelion, plantain, clover, lamb's quarters)
1 teaspoon salt
2 tablespoons cold-pressed safflower oil
4 to 6 cups flour mixture half lamb's quarters and half rice flour, or clover and whole wheat flour

Mix the yeast, honey, and 2 cups warm water in a large bowl and let it sit for a few minutes until foamy. Add the whole wheat flour and beat for 2 to 3 minutes. Cover the mixture and let set until doubled in size. (approximately 1 hour).

Meanwhile, in a bowl combine the greens, remaining warm water, salt, and oil. Add to the flour a little at a time and blend, kneading for about 5 minutes. Grease a large bowl and let the dough rise until doubled in size, about 50 minutes.

Punch the dough down and let rise another 40 to 50 minutes.

Preheat the oven to 400 degrees. Bake for 35 to 40 minutes or until you hear a hollow sound when you tap the top with the flat side of a butter knife. Cool for 30 minutes before serving.

Makes 1 large loaf

Wild Malva Rolls x

1 cup water
12 large malva neglecta leaves, washed
1 cup cooked wild rice
1/2 teaspoon dried thyme leaves
1/2 teaspoon salt

Preheat the oven to 350 degrees and grease a 1-quart casserole dish.

In a small saucepan, bring the water to a boil. Wilt the malva neglecta leaves by carefully dipping each leaf separately into the boiling water. Place the leaves on a paper towel to drain.

Place the rice in a bowl. Stir in the thyme and half the salt. Place 1 teaspoon of the mixture in the middle of a leaf. Fold the sides toward center and roll from stem to tip of leaf.

Place rolls seam side down in the casserole dish. Repeat, making the remaining rolls.

Sprinkle remaining salt over rolls and bake 20 minutes or until bubbly hot. Serve piping hot.

Serves 2 as a main course

Italian Clover Rolls *

1 cup clover flour
3 cups whole wheat flour
1/2 cup clover leaves
1/8 cup vegetable oil
2 garlic cloves, chopped
1 6-ounce can tomato paste
garlic powder

Preheat the oven to 350 degrees. Combine the flours in a large bowl. Add the clover leaves, oil, garlic, and tomato paste. Using your hands, knead thoroughly, adding a small amount of water until a clay-like consistency is obtained.

Roll golf-ball size pieces of dough in your palms and place on an oiled baking sheet. Bake for approximately 20 minutes or until golden brown. Serve hot, sprinkled with garlic powder.

Makes 12 to 14 rolls

Crabgrass Muffins !

1 cup enriched flour
1 cup crabgrass flour
2 teaspoon baking soda
2 teaspoons ginger (optional as a variation)
3/4 cup water
2 eggs (egg replacement used by author)
1 teaspoon pure vanilla
1/4 cup sunflower or canola oil
1/2 cup raisins
2 teaspoon baking soda

Preheat oven to 350 degrees.

Place flours and baking soda in bowl, mix in water, eggs, vanilla, & oil. Fold in raisins thoroughly. Fill muffin tins 1/2 full or pour in 8-inch square baking pan.

Bake 20 to 25 minutes. Let cool and remove from pan.

Makes 6 muffins

Crabgrass Crackers x

1 cup basic mix (Page 225)
1 cup crabgrass flour
1 teaspoon salt
1/2 cup water

Preheat the oven to 400 degrees. Lightly grease a baking sheet. In a medium bowl, combine the mix, flour, and salt. Add water to form a dough. Knead about 12 times, or until the dough is smooth. Shape into pencil-like strands 1/2 inch thick, and place on baking sheet. Roll out as a single sheet onto the baking sheet. Use a fork to perforate the sections. Bake for about 5 minutes or until crisp.

Variations: Use another flour, such as from malva, mixed grain, or lamb's quarters. Substitute goat's milk or cow's milk for water.

Makes 24 to 36 crackers

Wild Waffles ~

Dry Mix 1 cup rice flour
1 cup barley flour
1 cup buckwheat flour
1 cup old-fashioned rolled oats
1/4 cup finely chopped lamb's quarters
1 cup mixed dried greens (clover, dandelion, violet leaves, curly dock, & amaranth)
4 tablespoons baking powder
1 1/2 teaspoons salt

Combine the flours, oats, lamb's quarters, mixed greens, baking powder, and salt. Store in the refrigerator.

Makes 4 cups

Batter 2 cups dry mix
2 cups soymilk, cow's milk, or water
4 tablespoons butter or cold-pressed oil

Combine the dry mix, liquid, and butter or oil. Grease a waffle iron well. Spoon about 3/4 cup batter onto hot iron. Cook each waffle until it is brown on both sides, about 6 minutes. Serve with maple syrup or honey butter.

Serves 6 to 8

Navaho Lamb's Quarters Fry-Bread ~

1 cup whole wheat flour
1 cup lamb's quarters flour
2 teaspoons baking powder (optional)
1/2 cup reconstituted nonfat dry milk or water
2 teaspoons safflower oil
1/2 cup ice water
Oil for frying

Combine the flours and baking powder (if using). Add the milk or water and oil, and using your hand, mix into a granular mixture. Add the ice water and form into a ball. Put a towel over the bowl and let the dough rise in a warm place for 2 hours. (Even without baking powder, the dough rises about 1/2 inch.)

Cut the dough into 2 parts, roll out each part until 1/4 inch thick, then score parallel lines 1/2 inch apart almost through each piece. Heat oil in a deep pan until very hot, then add 1 piece of dough. Deep-fry until both sides are brown, approximately 2 minutes. Drain on paper towels and repeat for the other piece of dough. Serve hot. Can be frozen and reheated in a microwave.

Makes 2 breads

Mallow Vegetable Bread ~

5 cups warm water
12 to 14 cups whole wheat flour, ground fresh from
  whole wheat berries, if possible
2/3 cup olive oil
2/3 cup rice syrup
2 teaspoons sea salt
3 tablespoons active dry yeast
3 tablespoons vitamin C crystals (for dough
  consistency), vailable in health food stores.
2 medium onions, chopped
1/2 cup chopped mallow
3 medium carrots, chopped
4 garlic cloves, chopped

In a large bowl, combine the flour, water, oil, rice syrup, salt, yeast, and vitamin C crystals and mix thoroughly. Add the onions, mallow, carrots, and garlic. Mix thoroughly by hand, then knead for 10 minutes. Form into loaves, place in greased pans and cover. Let rise until dough rises above the pans, about 1 hour.

Preheat oven to 350 degrees. Bake loaves for 35 to 40 minutes, or until they sound hollow when tapped.

Makes 2 loaves

Phragmities Pancakes !

1 cup phragmities flour
water (approximately 1/4 cup)
oil for frying

Put the flour in a medium bowl, slowly add enough water to form a paste. Mold the paste into a pancake form. Grease a skillet and fry the cake slowly until golden brown and crispy, about 6 minutes.

Serves 1

Variation: Preheat oven to 350 degrees. Grease a baking sheet and bake the cake for 15 minutes or until brown and puffy.

Phragmities Drop Biscuits *

1 cup phragmities flour
1 cup wheat bran or whole wheat flour
2 tablespoons safflower oil
3 tablespoons baking powder
approximately 1/2 to 3/4 cups water

Preheat oven to 350 degrees. Blend the flours and oil. Add just enough water to make a paste. Spoon silver-dollar-size portions onto a greased baking sheet and bake for 10 to 15 minutes or until crisp.

Yields 18 biscuits

Variation: Add 1/2 cup honey to the recipe

Phragmities Pita Bread x

1 cup phragmities flour
1 cup whole wheat flour
1 teaspoon baking powder
1/4 teaspoon olive oil
approximately 1/2 to 3/4 cups water

Preheat the oven to 350 degrees. Combine the flours, baking powder, and oil in a large bowl. Mix slowly, adding water a little at a time until mixture is of bread dough consistency. Knead until smooth, then let the mixture sit, covered, for 10 minutes.

Form 1 inch balls into individual patties ¼ inch thick and put on a greased baking sheet. Bake until the edges of the pita breads are brown and crispy, about 30 minutes.

Makes 12 pita breads

Green Pancakes (made from any vegetable flour) !

1/4 cup flour
small amount of water

Add a tiny amount of water very slowly to the flour to form a paste. Make two 2" in diameter pancakes. These are powerful pancakes, so you want to make them small. Fry slowly on a greased fry pan or cooking sheet, or bake in the oven as you would a cookie. Instant energy boost!

Makes two 2" pancakes

Nutsedge Crackers ~

1 cup Basic Mix (page 225)
1 cup nutsedge flour or oat flour
1/2 cup water

Preheat oven to 400 degrees. Lightly grease a baking sheet. In a medium-sized bowl, combine Basic Mix and flour. Add water to form dough. Knead about 12 times, until dough is smooth. Shape into pencil-like strands 1/2" thick or roll out flat onto baking sheet. Bake about 5 minutes until crisp. Cut into small pieces while warm.

Makes 24 to 36.

Variations: Use any flour you have such as malva, mixed grain or lamb's quarters in place of nutsedge or oat. Use goat's milk or regular milk in place of water.

Breads and Flour

The following will make excellent flour. Refer to pages 35-40 for information on drying, grinding and storage.

- plantain leaves
- clover leaves
- dandelion leaves
- strawberry leaves
- cattail fluff, root
- curley dock seeds and root
- nutsedge (grainy top of plant)
- Lamb's quarter leaves
- pigweed leaves
- bulrush pollen
- thistle root
- inner bark of birch bark



Homemade Wild Pita Bread.
A. Drop round balls of dough
B. Bake until edges are brown
C. Slice and fill pocket

Sweets



Lamb's Quarters Granola !

1 cup dried lamb's quarters seeds
3 cups old fashioned rolled oats
1 egg
1/2 teaspoon ground cinnamon
dash of ground cloves
1/4 teaspoon salt
1 1/2 cups water
3 tablespoons maple syrup, honey, or rice syrup

Combine the seeds, oats, eggs, and spices in a large bowl. In a large saucepan, bring the water and sweetener to a boil. Add the oat mixture a little at a time while stirring. Reduce the heat to low and use a fork to mix the granola until it is moist, but not wet. Add additional water, if needed, to make moist. Press layer into greased pans or pie plates. Allow to cool.

Serves 4

Variation: Add 3/4 cup raisins or 1 1/2 cups diced apples to the mixture.

Baked Prickly Pears ~

6 large prickly pear fruits
1/2 cup honey
1/2 teaspoon ground cinnamon
1/4 teaspoon grated lemon peel
4 tablespoons butter or 2 teaspoons safflower oil

Preheat the oven to 350 degrees.

Use a fork to hold the fruits while peeling to prevent the hair-like barbs from going into your fingers. After the fruits are peeled, cut in half, and remove the seeds. Grease a 6" baking dish. Line the bottom of the dish with the fruit. In a separate bowl, combine the honey, cinnamon, lemon peel, and butter or oil and drizzle over the fruit. Bake until tender, 20 to 30 minutes. Serve warm.

Serves 3

Meadowsweet Apples !

4 large baking apples, washed and cored
1 cup meadowsweet flowers, washed
1/2 cup maple syrup

Preheat the oven to 350 degrees. Grease a 1-quart glass casserole dish. Place the apples in the dish and put flowers in core of each apple. Drizzle the maple syrup over the apples and bake for 30 minutes, or until soft.

Serves 4

Malva Neglecta Oatmeal Cookies x

1 egg
1/2 cup honey
1/4 cup vegetable oil
3/4 cup finely chopped malva neglecta
1 cup old-fashioned rolled oats
2 teaspoons baking powder
1 cup whole wheat flour
1/2 cup sunflower seeds
1 1/2 teaspoons vanilla extract
2 teaspoons water
1/2 cup raisins

Preheat the oven to 350 degrees. Mix the egg, honey, and oil in a blender. Stir in the malva neglecta.

In a large bowl, blend the oats, baking powder, flour, sunflower seeds, vanilla, water, and raisins. Add the malva mixture and stir well. Drop by teaspoons onto a greased baking sheet. Bake for 12 to 15 minutes, or until golden brown on both sides. Cool on a rack.

Makes 3 dozen cookies

Plantain Raisin Cookies x

2 cups whole wheat flour
3/4 cup dried or fresh plantain seeds
4 tablespoons baking powder
2 tablespoons molasses
1/2 cup carob-covered raisins

Preheat the oven to 350 degrees. Mix all the ingredients in a big bowl. Add water slowly to form a thick, paste-like batter. Roll a pinch of dough between your palms and press onto a greased baking sheet. Continue to form cookies, then bake for 15 minutes or until golden brown.

Makes 2 dozen small cookies

Red Sumac Gelatin x

3 cups sumac berries
2 cups hot water
1 envelope unflavored gelatin
sumac berries for garnish

Make a concentrated sumac tea by putting the berries into a medium saucepan. Add the hot water and steep for 15 to 20 minutes. Strain. Follow the package directions for the gelatin, using the sumac tea in place of water. Garnish with a few berries.

Serves 4

Pine Popsicles *

gather the pine twigs, then strip the needles off the twigs. Use the twigs for popsicle sticks!
1 1/2 cups pine needles
2 cups boiling water

Put the needles in a small pot and pour in boiling water. Cover and steep for 10 to 15 minutes. Stir the needles once or twice to liberate more pine taste. Cool, then strain and pour into popsicle molds. Add pine twigs for sticks and freeze. (Some people put a dash of honey into the mold before pouring in the liquid for a sweet flavor.)

Makes 6 popsicles

Aloe Vera Ice Cubes x

fresh aloe vera leaves

Place aloe vera leaves on the flat side and skim the skin off with a sharp knife. Scrape the gel with a spoon, holding on to end of leaf. Pour into ice cube trays and freeze.

Mint Popsicles x

1 handful mint leaves, washed
mint leaves for garnish

Place the mint in a pot and add boiling water to cover. Cover the pot tightly and steep for 10-15 minutes. Strain and pour the liquid into popsicle molds. Place a leaf in each mold and freeze.

Makes 6 popsicles

Children love this refreshing treat. If you don't have popsicle molds, freeze in ice cube trays, adding a mint leaf to each cube. This is delicious in iced tea and other beverages.



Rose Petal Candy x

4 tablespoons butter
2 cups rose petals
1/2 cup confectioners sugar

Melt the butter in a large frying pan. Fold the rose petals, one at a time, and coat with butter, flipping them over for a minute or so. The petals sometimes puff up. Remove as soon as crisp and brown, then drain on a paper towel. Roll fried petals in sugar and refrigerate until ready to serve.

Makes enough for 4 people

Fresh or dried, rose petals make delicious candy. Reconstitute dried petals by soaking them in water for an hour or so. Drain and use as fresh.

Wintergreen Candy x

3 cups dried wintergreen leaves
2 cups water
2 cups brown sugar
1 tablespoon distilled white vinegar

Slowly boil the leaves in the water for 20 minutes to make a strong tea. Strain. Add 6 tablespoons of tea to the brown sugar and boil until hard ball stage. Add the vinegar and boil for an additional minute or so. Pour the mixture onto a well-greased platter. It will harden as it cools and can be broken easily into pieces of candy.

Makes enough for 4

Blueberry Crumb Pudding x

Topping

1/4 cup sugar
1/3 cup flour
1/2 teaspoon cinnamon
1 tablespoon margarine
1 tablespoon shortening

Mix together and save for crumb topping.

Pudding

1/4 cup shortening
1/4 cup sugar
1 1/2 teaspoon baking powder
1 egg
1 cup sifted flour
1/8 teaspoon salt
1/3 cup milk
1/4 teaspoon vanilla
2 cups blueberries

Cream shortening and sugar. Add the egg, flour, baking powder, salt and milk. Spread this in an 8" square pan and spread 2 cups blueberries over this. Top with crumb spread. Bake at 350 degrees for 30 minutes.

Serves 4

Wild Plantain Cookies ~

2 cups whole wheat flour
3/4 cup plantain seeds (dried or fresh)
4 tablespoons baking powder
2 tablespoons molasses
1/2 cup carob covered raisins

Mix all ingredients well in a big bowl. Add tepid water slowly to form a thick, claylike paste. To form cookies, roll a pinch of dough between your palms and press onto a greased cookie sheet. Bake 15 minutes at 350 degrees or until golden brown.

Makes 18 to 20



**Right: Apprentice
Althea Dixon slices and dices a
nopales cactus.**

**Apprentice
Hazel McManus presents a
completely edible centerpiece
and meal.**

**Apprentice
Tracy Alderman Dockery
teaching homeschoolers,
Arizona.**



**Apprentice
Shirlee Pettipiece.**

Teas & Other Hot & Cold Drinks



Teas are an excellent way to develop your taste for wild foods. The wild ingredients in these teas are fresh unless otherwise stated. You may wish to use a tea infuser rather than strain the tea. As your taste for wild foods develops, you may even wish to eat the brewing grounds after drinking the tea.

Rule of Thumb: When you have fresh tea leaves, measure 2 cups of water per handful of leaves. Bring to a boil, cover and turn off heat. Let steep for 5-10 minutes. For dry ingredients (which cook more quickly), measure 1 cup of water per handful. Bring to a boil, cover and turn off heat. Let steep for 5 minutes. Generally, the flavor is more intense with dry herbs.

Aloe Vera Morning Tonic x

1 aloe vera ice cube (see Note)
3/4 cup fresh orange juice

Combine ice cube and orange juice in a glass. Let cube melt, then drink.

Serves 1

Note: To make cubes, place an aloe vera leaf on its flat side and peel the rounded skin off with a sharp knife. Scrape the gel with a spoon, holding on to one end of the leaf. Pour the gel into ice cube trays and freeze.

Balsam Tea !

1 inch tips balsam
1 cup water
honey (optional)

Place balsam tips in a small saucepan and add the water. Cover. Bring to a boil, then lower the heat and simmer for 10 minutes. Strain tea if desired, add water to taste if tea is too strong or sweeten with honey if desired.

Serves 1

Blackberry Bramble Tea !

1 6 inch blackberry shoot
1 cup boiling water
honey (optional)

Peel the shoot until most of the bark is off. Break into several sections to expose more of the surface. Place in a teapot, add water, cover pot and steep for 5 minutes. Strain if desired. Sweeten with honey, if desired, and serve hot or cold.

Serves 1

Balsam Toddy x

1 to 3 inches balsam twigs with needles
2 cups soymilk
dash of ground cinnamon

Place balsam twigs in a teapot. Bring the soymilk almost to a boil, remove from heat, and pour over balsam. Steep, covered, for 5 minutes. Strain, then add cinnamon and serve piping hot.

Serves 1 or 2

Goldenrod Tea !

1 sprig goldenrod flowers
2 cups boiling water
honey (optional)

Place flowers in a teapot. Add water, cover pot, and steep for 5 minutes. Sweeten with honey if desired. Serve hot.

Serves 1 or 2

Chamomile Tea !

1/4 cup chamomile leaves and flowers, washed
2 cups water
honey (optional)

Place chamomile in a small saucepan. Add water, bring to a boil, turn off heat, and cover. Steep 10 minutes, then strain and serve with honey if desired.

Serves 1 to 2

Wild Greens Tonic x

This tonic will keep in the refrigerator for 2 days or so. I freeze the brew as ice cubes for use in recipes or for a cup of tea.

1 cup willow leaves, washed
1 cup mint leaves, washed
1/2 cup red clover buds
2 quarts water

In a blender of food processor, blend all ingredients until green and smooth. Serve hot or cold.

Serves 8

Dandelion Root Coffee or Chicory Coffee !

1 teaspoon dandelion root or chicory root powder
  (see page 76)
1 cup water

In a medium saucepan, combine the powder and water. Bring to a boil and simmer, covered, for 3 to 4 minutes. Drink as a coffee substitute.

Serves 1

Hot Meadowsweet Tea !

4 white meadowsweet flower spires
4 to 6 meadowsweet leaves
1 cup water

Bruise the leaves and flowers, then pour boiling water over them and cover for 7 minutes. Strain. Serve hot, or add 1 teaspoon lemon juice and serve cold.

Serves 1

Maple Tea !

1/2 cup maple seeds, clipped from the wing
1 cup boiling water
2 teaspoons maple syrup (optional)

Place seeds in a teapot, add water, and steep for 5 minutes. Sweeten with maple syrup if desired.

Serves 1

Mullein Root Tea !

Mullein root is an antihistamine. When you feel a cold coming on, simmer the root in water and drink the liquid. The root can be used several times to make tea. After five or six uses, bruise the root with a hammer, or cut slits in the sides to release more nutrients.

1 large mullein root
honey (optional)

Scrub the root well and cut slits in several places with a strong knife. Place the root in a non-corrosive pot. Add water to cover, bring to a boil, and simmer, covered, for 5 minutes. Sweeten with honey if desired. Hang the root up to dry.

Serves 1

Willow "Aspirin" Tea !

For pain relief, chew the willow twigs raw as well.

1 6-inch willow tendril, including leaves and catkins
1 cup boiling water
honey (optional)

Using a knife edge, score and remove the bark. Slice the bark, leaves, and catkins into a teapot. Break up the twig into several sections and add to the teapot. Add water, cover, and steep for 5 minutes. Strain, and sweeten with honey if desired.

Serves 1

Pine Needle Tea !

A pine tree is filled with vitamin C, so pine tea is delicious and nutritious. Cold or hot, the flavor is wild. Perhaps in time you will develop a taste for *raw* pine needles. They are edible and so is the bark. Your backyard tree might hold several hundred cups of tea—perhaps thousands. Seasons make no difference; pine is green and succulent all year long.

1 cup fresh pine needles
1 cup boiling water
honey (optional)

Put the needles in a teapot and pour in the water. Steep for 5 to 7 minutes, then strain. Sweeten with honey if desired.

Serves 1

Wintergreen Tea !

Wintergreen tea is scrumptious. With this tea you can comfortably pass a cold winter's night. Gather the flat, shiny leaves and spread them on a screen to dry in a warm, airy spot. The back window ledge of a car is good. Let them dry slowly in the sun and watch that they don't dry too fast. This technique does not work in August when the sun is too hot. I use a hand grinder or old meat grinder to obtain the powder for this tea.

2 teaspoons ground dried wintergreen leaves
1 cup boiling water
honey (optional)

Put wintergreen into a cup and add water. Steep for 5 minutes. Sweeten with honey if desired.

Serves 1

Violet Tea !

a handful of violet flowers
2 cups of water

Pick flowers after dew has evaporated and dry on a screen for a day. Add flowers to the water and cover. Steep for 10 minutes. Skim flowers out or eat them!

Serves 2



A Choice of Blend of Herbs for Tea !

Gather a combination of lawn herbs. Examples: thyme, mint, red sorrel, yarrow, spearmint, goldenrod, rose hips, among a few. Arrange the herbs so the stems are the same length and bundle them together. Hang the bundle high in a warm kitchen. When the leaves are dry enough to crumble, rub the bundle between your palms over a tray. Then rub that mixture through a sieve. You can bottle this Fine Blend and store for future exquisite tea! Also, one tablespoon is adequate for a cup of soup.

Blackberry Bramble Wine !

1 gallon blackberry shoots or tips
1 pound raisins, chopped
1 gallon boiling water
3 1/2 cups sugar or 2 cups honey
1 tablespoon all-purpose wine yeast

Wash the blackberry shoots. Using scissors, clip shoots into 1-inch pieces and place in a sterilized 5-gallon container. Add the raisins, then cover with boiling water. Cover tightly. The next day, strain liquid and return it to the container. Add the sugar or honey and stir well. Prepare the yeast according to the package directions. When bubbly, add the yeast mixture. Cover tightly. In a few hours the mixture will begin to foam. Stir occasionally, until fermentation slows. When bubbling ceases (in about 6 weeks), siphon the liquid into sterilized bottles. Cork and let sit in a dark place. Serve in a year's time.

Makes about 5 bottles

Daisy Petal Wine !

1 gallon daisy heads with petals (no stems), washed
1 gallon boiling water
3 pounds sugar or 1 1/2 pounds honey
1 package all-purpose wine yeast

Pack the daisy heads into a sterilized 2-gallon crock. Pour the boiling water over the heads and stir. Cover tightly. Let the mixture stand for 1 1/2 weeks. Strain.

Bring the liquid to a boil and remove from the heat. Transfer to a sterilized 4-gallon container. Stir in the sugar or honey until it is dissolved. Let cool. Meanwhile, prepare yeast according to package instructions. Add to liquid and cover tightly. Let the mixture sit for a week while it foams. Let it sit until the fermentation clears, about another 6 weeks. Siphon into sterilized bottles and store for 4 to 6 weeks before serving.

Makes about 5 bottles.

Dandelion Wine !

1 gallon dandelion flowers
4 oranges
1 gallon water
5 pounds sugar
1 package all-purpose wine yeast

Remove the green parts and soak the flowers in boiling water. Peel oranges and save the juice. Pour boiling water over flowers and let stand for 2 days. Add orange peels, bring to a boil, then let simmer for 15 minutes. Strain liquid and parts through a fine strainer or use a jelly-bag. Add sugar to strained liquid and cool to room temperature. Add the juice of the oranges and yeast. Pour into a fermenting jug fitted with an airlock. When fermentation clears, siphon into sterilized bottles. Store at least 6 months before serving.

Makes 5 quarts

Prickly Pear Wine x

1 dozen prickly pear buds
2 quarts boiling water
4 cups honey
1 package all-purpose wine yeast

Hold the prickly pear buds with forceps in one hand and peel under water. Place pears in a sterilized 1-gallon crock and pour in boiling water. Cover tightly. Place mixture in a warm place for 4 or 5 days or until mixture "turns."

Strain liquid and return to gallon crock. Add honey. Prepare the yeast according to package directions and stir into the mixture. Cover it tightly, and let it sit in a dark warm spot for 1 more week or until foaming clears. If desired, transfer to a carboy fitted with an airlock. Let it sit until the fermentation ceases in about 6 weeks.

Siphon into sterilized bottles and cork tightly. Let rest for about 8 months.

Makes about 3 bottles.



Rose Petal Wine !

1 quart rose petals, washed
2 quarts water
2 cups honey
1 package all-purpose wine yeast

Simmer the rose petals in water for 5 minutes, stirring occasionally. Pour the liquid and petals into a sterilized 2-gallon glass container. Cover tightly and let the mixture sit for 1 week. The petals and water will turn almost rancid.

Strain the mixture and put the liquid in a clean pot. Bring to a boil, then turn off heat. Transfer to a sterilized 2-gallon container. While mixture is very warm, add the honey. Let it cool. Meanwhile, prepare the yeast according to package directions. When the mixture has cooled, add the yeast mixture, stir once, and cover tightly. If desired, after 1 week, transfer the mixture to a fermenting jug fitted with an airlock. When the fermentation ceases, in about 6 weeks, siphon the wine into sterilized bottles and cork tightly. Let rest for 4 months.

Makes about 3 bottles



Sugar Maple Twig Wine !

1 gallon tightly packed sugar maple twigs, washed
1 gallon boiling water
4 cups honey
1 package all-purpose wine yeast

Pack the twigs into a casserole. Pour in the water and simmer for 20 minutes. Transfer to a sterilized 2-gallon crock. Cover tightly. Let sit for 3 days.

Strain the liquid and add honey. Stir well. Prepare the yeast according to package directions and add to the mixture. Stir, then cover tightly. Mixture will foam for 1 week. If desired, at this point transfer to a sterilized fermenting jug fitted with an airlock. Keep covered until fermentation stops, in about 6 weeks. Siphon into sterilized bottles and cork. Store in cellar for 3 to 4 months before serving.

Makes about 5 bottles

Preserving Wild Foods



Dandelion Jelly x

Petals from 40 dandelion flowers
3 cups boiling water
1 package commercial pectin
3 3/4 cups sugar or 1 3/4 cups honey

Wash the petals and add them to the water. Steep for 10 minutes, then strain. Return the juice to the heat, bring to a boil, and immediately add the pectin. Boil mixture for 1 minute, then add sugar or honey and simmer until it makes a hard ball (260 degrees). Pour into hot, clean pint jars and seal with wax or process in hot water bath for 20 minutes.

Makes 2 pints

Cactus Lemon Marmalade x

1/4 cup thin lemon slices
1 cup prickly pear cactus pulp (Split the fruit and remove the tips & seedy centers.)
1/4 cup honey

Put the lemons in a small saucepan and cover with water. Soak overnight. The next morning add the cactus and honey and cook until the mixture is thick. Pour into a hot pint jar and cover with sealing wax or process in a hot water bath for 20 minutes.

Makes 1 pint

Saguaro Cactus Jelly x

16 to 24 saguaro fruits
1 package powdered pectin
1/4 cup lemon juice
2 1/2 cups honey

Split the fruit and remove the tips & seedy centers. Place the pulp in a pot, cover with water, and simmer until well-cooked, about 15 minutes. Strain the pulp using a fine colander. In a large pot, combine 3 1/4 cups saguaro puree, pectin, lemon juice,

and honey. Boil for 1 minute, stirring constantly, then pour into scalded pint jars. Cover with sealing wax or process in a hot water bath for 20 minutes.
Makes 4 pints

Rose Petal Syrup !

4 cups rose petals
1 quart water

Put the petals in a large saucepan and cover with water. Simmer for 20 to 25 minutes, stirring often, until it is thickened to syrup consistency. Cool, bottle, and refrigerate.

Makes 1 quart

Rose Hip Jam !

4 cups rose hips, washed
4 cups water
2 cups honey

Cook the hips in the water until tender, about 15 minutes. Put the hips through a meat grinder, food processor, or coarse sieve, then push the pulp through a fine sieve to obtain a smooth puree. Add 1/2 cup honey for each cup of pulp and cook until thick. Pour into scalded pint jars and seal with sealing wax or process in a hot water bath for 20 minutes.

Makes 4 pints

Queen Anne’s Lace Salt !

This salt substitute lasts for years and years. Caution: Be 100 percent certain on your identification. The fuzzy hairs on the stem of Queen Anne’s lace are dry at this stage. Running your finger down the dried stem feels like sandpaper.

Collect Queen Anne’s lace seeds in the early fall, when flowers have “birdcaged” and turn a light brown. When the seeds mature, the entire head naturally dries up. Pull on the dried seed top; the seeds are easily extracted in your hand, even without taking the “birdcage” off the stem. The remaining seeds will propagate new growth next season.

Place the seeds on a tray and put into a 250 degree oven for 5 minutes. You may put them on a tray on top of the stove's pilot light until completely dry. Bottle in glass jars for long-term storage.

Caution: Pregnant women should not use these seeds: medicinal field guides show that the seeds have abortive tendencies.

Herbal Vinegars !



Fantastic herbal vinegars can be made from the blossoms of red or white clover, roses, catnip, mint, goldenrod, blackberries, raspberries, violets, and lamb's quarters. You might enjoy adding other flavors, such as thyme, garlic, or Queen Anne's lace. My favorite vinegar is a combination of greens and spices. Experiment with different flavors to find your favorite. These vinegars make wonderful gifts.

Wash and drain the greens and flowers and place in a 2-quart glass container. Bring vinegar to a boil, then pour it slowly over the greens and flowers. Cap and store the container in a high place, out of direct sunlight. The vinegar will cook the greens a bit in the warmth. Shake it every day for best results. After 2 weeks, strain the mixture, cap tightly, date and label the container.

Makes 2 quarts

Lemon Pepper x

1 peel from lemon, scrubbed
1 2-ounce container garlic salt
1 3-ounce container celery salt
1 2-ounce container coarse black pepper

Dry lemon peel thoroughly, about 3 days on a plate or 1 to 1 1/2 hours in an 250-degree oven. Don't let it get brown. Pulverize dried peel in blender until powdered. Add the rest of the ingredients, mix thoroughly and refrigerate. Use as a spicy additive.

Makes about 1 cup

Cattail Pickles !

Harvest cattails at the height of summer, when they have large stems about 1/2 to 1 inch in diameter. Cut the cattails at water level, remove seed heads, then peel the stem to the inner white core. Wash this pith under running water. Lay out on counter or board and slice into 6-inch pieces. Place pith pieces in pint jars, add your favorite pickling recipe. (Use hot cider vinegar and 1 teaspoon pickling spices (commercial) to each 8-ounce jar of vinegar.)

Stems yield approximately 4 to 6 jars, depending on the diameter of the pith and the length of the stems.

Makes 4 pints

Cactus Pickles x

2 quarts prickly pear fruits
2 cups honey
2/3 cup cider vinegar
3 ounces red cinnamon candies Or
    1 small cinnamon stick, ground

Put cinnamon candies or stick in a cheesecloth bag. Place the fruit in pint jars. Mix the honey and vinegar in a saucepan and add spice bag or cinnamon candies to pan. Bring to a boil, then reduce heat and simmer for 5 minutes. Remove the bag and pour the liquid over the fruit to 1/4 inch from tops. Process in a hot water bath for 25 minutes.

Makes 2 pints

Pickled Mustard Flowers !

1 cup mustard flowers, washed
8 ounces cider vinegar
1 teaspoon pickling spices

Put flowers into a clean, wide-mouthed 8-ounce canning jar. In a non-corrosive saucepan, bring vinegar to a boil. Add pickling spices and simmer ‘till flavors mix, about 5 minutes. Remove spice bag and pour vinegar over the flowers to within 1/2 inch of top of jar. Loosely cap the jar and place in a 2-quart sauce pan filled with water. Bring to a boil and boil for 5 minutes.

Makes 1 jar

Rose Petal Butter x

1 cup rose petals, 2 cups
½ stick sweet butter

Alternate layers of petals with butter, so you get a "marble" layered appearance. Seal in a container and store in refrigerator. Blend when ready to spread on crackers or bread for a wonderful appetizer! Or, cut into little patties for another type of appetizer.



Milkweed Bud Pickles



Cattail Pickles

Desert Meal.

Sundries



Wild foods are fantastic vegetables and make great teas, but have you ever considered them as sundries or accessories? The following recipes give you more ways to use wild foods each day.

Nettle Hair Softener !

1 cup dried nettles
2 cups water

Simmer the nettles in the water for 20 minutes, then allow the mixture to cool. Strain.

Rinse your hair with the liquid. Let it stay in your hair for 2 to 3 minutes, then rinse with nettle liquid again. Then rinse with clear water.

Makes about 2 cups

Cactus Hair Softener !

1 cup cactus skins or pads, chopped
2 cups water

Simmer the cactus for approximately 30 minutes until almost dry. Pulp will turn water thicker. Cool and rinse hair with liquid after washing. Rinse again with clear water.

Makes 2 cups

Note: You may choose almost any type of pulpy cactus such as prickly pear, nopolitas, cow’s tongue.

Yarrow Tooth Powder or Paste !

1 piece of burnt toast
yarrow leaves, dried and ground

Scrape the charcoal off a piece of burnt toast. Make a mixture of half charcoal and half ground yarrow for a refreshing, cleansing tooth powder. Or add a small amount of water to form a paste.

Variation: Dry a thick, straight-stemmed yarrow plant. Remove and save the leaves for tea. Cut the desired stem toothbrush to size. Using a knife, cut into one end over and over to make a fuzzy tip.

In an emergency situation, cut a large raw yarrow leaf and scrub your teeth by pressing the leaf to them and rubbing. Rinse.

Wild Facial Lotion and Skin Softener !

1 cup wild lettuce leaves, washed
1 cup mullein leaves, washed
1 quart water

Combine the leaves and water in a 2-quart saucepan. Cover and bring to a boil, then simmer gently for 30 minutes. Strain.

Put the resulting liquid in a bottle for use as a skin softener.

Makes about 1 quart

Wildflower Punch Bowl x/~

1 large plastic cake dome to fit inside punch bowl
1 cup each violets, daisies, red rose petals, multi-colored hibiscus, and pansy flowers
several rose leaves
Several small ferns

Invert the cake dome and add 1 inch of water. Place the violets in the water and freeze solid. Repeat the procedure with each type of flower. Use the rose leaves and ferns for the last layer.

Cover and keep frozen until ready to use. When you are ready to use it, unmold and float in a punch bowl with your favorite punch recipe.





Flower Cake.

Barbeque Cactus Burrs.

Desert Snake Stick (top).

Typical Desert Walk.

Gathering Desert Tumbleweed.

Part IV: Reference Section

Cultivation of Wild Edibles

During our Adirondack homesteading years we made many attempts at gardening, using conventional methods. Indeed, experimenting with gardens was always a summer pastime.

The 175-foot strip garden worked best. I had found out when the electric company had last defoliated the areas, beneath a power line, and since it was many years ago, I chose the strip because it was already partly cleared. The garden was high, sunny, dry, and basically rockless, as Adirondack soil goes.

I enjoyed every moment of clearing the land, especially the weeds. As I seeded with vegetable seeds, I was able to supply the family's immediate food needs, harvesting a year's supply of lamb's quarters, chickweed, sheep sorrel, violets, strawberries, and dandelions. The amount of our wild stored food continued to grow, from dried to canned to pickled. The family enjoyed nutritious meals of vegetables, spices, and herbs that were both wild and cultivated.

But after two years of fixing fences and hunting predators, of purchasing cloth, saving newspapers, and recycling plastic as covers to beat the frost, I finally turned to wild foods exclusively. Long after the cultivated vegetables were gone in fall, the wild foods continued to grow under the snow, under hay, and in cold frames. I asked myself why I had spent all that time and energy gardening when wild foods grew with such abandon, untouched by predators, insects, and weather. The answer was simple; the problem *was* getting *used* to the change in eating patterns.

Over the years we learned to use the foods nature provided so readily, and in the process discovered a whole new culinary world rich in flavor and nutrition.

A Field of Wild Foods

Gardens as we know them are basically artificial, filled with introduced species and forced arrangements. We don't all have acres of wild land near home, however, from which to forage our daily meals. On the other hand, many of us can consider changing that backyard garden or lawn into a productive field of wild foods. Weeds are more natural, and can supply much of your food needs.

Your Private Wild Food Area

I recommend stringing off a special area—perhaps a 4 by 6-foot section—of rich loamy garden soil or area previously tilled. Don’t use herbicides on the soil; usually the weeds already there make great herbicide-resistant garden starters. (Only approximately one percent of all weeds are poisonous.)

For best results, transplant foraged weeds after a light rain, when young plants are more easily dislodged and the soil clings to the roots. I use a spoon for shallow-rooted types such as white clover, plantain and garden sorrel, planting them in the front rows about two to three inches apart. Experience has taught me that these plants will eventually mat and form a close-knit crop. Taller medium-rooted plants like milkweed and mustard are transplanted with a trowel and placed six to eight inches apart behind the “shorties.” As these larger plants grow, they’ll branch out, so to minimize encroachment on other more traditional plants, place rocks, peat moss or hardwood chips around the border of your wildfood crops. Pine needles are also excellent for this purpose. Even if you let only twenty feet of lawn return to its natural state, you have a productive food strip, or field.

This new food strip will be a natural field; eventually free of poisons.

For example, if you have been using a weed killer, the chemicals have been killing off sheep sorrel, dock, plantain, dandelion, and clovers. As wild “weeds” they will return almost immediately. At this point, harvest only the youngest leaves for minimal chemical content while your soil replenishes itself. Long-term lawn treatment requires more time. Visit a local hardware store or nursery, or call the US FDA or County Extension Service, for information on residuals for chemicals. Also, there are several books on replenishing your soil the natural organic way without pesticides.

Saltiness and High Concentrations of Nitrates

Liming the soil at the base of your plants corrects both the alkalinity and nitrates. Desert dwellers should also water more frequently since this will reduce the alkaline salt buildup.

Unless it's a rainy season, your weed garden should be watered as much as your traditional vegetable garden—about three times a week; more in arid desert areas. Keep the plants moist, but not soaked. I mist my wildfood strips with a spray attached to a hose.

Compared to plants like tomatoes, wildfoods respond twice as fast to water, fertilizer and light. And they're hearty; in a heavy frost you don't need to cover them.

Harvesting

After only a week, I'm usually able to pinch back or scissor off leaves and use them as food. In fact, cutting back a few branches or leaves generally stimulates greater growth.

In the cold Adirondack winters I allowed six inches of snow (plus hay, leaf composts or peat moss) to cover my garden. This created a hothouse effect. (Boards also can act as a winter greenhouse, especially for purslane.) In this way, I was able to harvest thyme, strawberry leaves, chicory and chickweed the whole year round.

Likewise, some common garden plants are poisonous. Especially if you have children, you'll want to eliminate or at least be aware of the dangers these plants hold. Some of these plants are listed below. See the books listed in Suggested Reading for more information.

Common Poisonous Plants

American bittersweet
American yew
Anemone
Azalea
Black locust
Bleeding heart
Bloodroot
Iris
Bouncing Bet
Buckthorn
Buttercup
Butterfly weed
Castor bean
Celandine
Choke cherry
Cowbane
Crown of thorns
Daphne
Deadly nightshade
Delphinium
Dogbane
False hellebore
Foxglove
Four o'clocks
Golden chain
Horse nettle
Horse chestnut
Horsetail
Jack-in-the-pulpit
Jack-o-lantern mushroom

Jimsonweed
Lantana
Larkspur
Lily of the valley
Marsh marigold
May apple
Mountain laurel
Narcissus
Nightshade
Poison hemlock
Pokeweed
Prickly poppy
Privet
Rhododendron
Rhubarb leaves
Scotch broom
Skunk cabbage
Snow on the mountain
Star of Bethlehem
Tansy
Tomato leaves
Trumpet flower
Virginia creeper
Water-hemlock
Wisteria
Yellow oleander

Do not let this list confuse or inhibit your foraging. The stress here is on identification. Know your own property. Other good field guides are found in the library or sold in book stores. There are too many poisons in the natural world to memorize. Therefore, (1) memorize your edibles, (2) identify the poisons nearby, and be absolutely sure before you try a new plant (see section on foraging, Part I, page 22).

Building a Wild Foods Garden

Wild plants will grow everywhere, in desert, valley, woods, and fields. Vacant lots and sidewalk cracks show evidence of the tenacity of common plants to live. Dandelions, plantain, yarrow, chicory and violets are common in many places. So begin by looking at your local edible landscape. View the surroundings with calm deliberation and a pencil. See the abundance already there and know the ease of creating a wild foods garden.

I cannot be specific here as to soil needs, moisture requirements, and the like. You have to consider your environment, your geographic location when working with these wild plants. The “gardening” I speak of is mostly one of transference, and *support*. You can move plants to where you want them (provided you haven’t taken them from a protected area) and you can provide conditions that they like. Peat moss may help keep the surrounding weeds from inundating your food strip. Mulch helps too—one food field has 6 inches of wood chips around the main plants. Leaves, rocks, pebbles also work. Sidewalks retain a lot of moisture. But even simple things like cedar chips or sawdust may increase the ability of eastern soil or add to the saltiness (alkali) of desert soil. In general, it is best to use indigenous soils and topsoil.

Use a spoon, trowel, or shovel to gently release the plant's grip on the soil. See the chart on the next page for guidance on plant reactions to being moved.

In developing your wild foods garden, you may want to move plants around a bit or bring in native plants that haven't otherwise appeared. Be sure to dig up all of the roots, then set in new place and pat soil in gently. Water well.

The Inside Garden

Starting a wildfood garden in your home isn't much harder than maintaining your outdoor one. Clay pots prevent the soil from becoming rancid, and positioning them away from heating or air conditioning units helps regulate temperature. Use potting soil and organic fertilizer, and don't forget to *mist* the plants three times a week.

In my Adirondacks log cabin, I transplanted dandelions and chicory into an old-fashioned wash tub, then placed it down in the cellar where the dark, damp conditions produced an amazing abundance.

Much of your indoor gardening depends on your climate, the temperature of your house, and the hours and strength of available sunlight. I sometimes put my plants in one big twig basket and relocate them to different areas. Artificial grow-lights are occasionally necessary for certain plants like clover, which requires at least 12 to 14 hours of high light per day. When introducing artificial light, at first leave it on only a few hours.

Indoor Garden.

Transplanting Wild Edibles

Plant Name	Planting Depth	Method	Ease of Adjustment
Aloe Vera	deep	trowel	perky
Amaranth	shallow	spoon	wilts
Aster	medium	trowel	wilts
Balsam fir	deep	shovel	perky
Birch	deep	shovel	wilts
Blackberry	deep	shovel	perky
Blueberry	deep	shovel	perky
Bulrush	deep	shovel	perky
Burdock	deep	shovel	wilts
Cattail	deep	saw, shovel	perky
Chamomile	shallow	spoon	perky
Chickweed	shallow	spoon	perky
Chicory	deep	shovel	wilts
Cholla	medium deep	shovel	perky
Clover	shallow	spoon	perky
Daisy	medium	trowel	perky
Dandelion	medium	trowel	wilts
Dock	deep	shovel	wilts
Evening Primrose	medium	shovel	perky
Field thistle	medium	spoon	wilts
Fireweed	medium	trowel	wilts
Goldenrod	deep	shovel	perky
Grape	deep	shovel	wilts
Lamb’s quarters	shallow	spoon	wilts
Mallow (Malva)	medium	trowel	wilts
Maple	deep	shovel	perky
Meadowsweet	deep	shovel	perky
Milk thistle	deep	shovel	perky
Milkweed	medium deep	trowel	wilts
Mint	shallow	spoon	wilts
Mullein	deep	shovel	wilts
Mustard	medium	trowel	wilts
Nettles	deep	shovel	perky
Phragmities	deep	shovel	wilts
Pine	deep	shovel	perky
Plantain	shallow	spoon	wilts
Prickly pear	deep	shovel	perky

Transplanting Wild Edibles (Continued)

Plant Name	Planting Depth	Method	Ease of Adjustment
Purslane	shallow	spoon	perky
Queen Anne's Lace	deep	shovel	wilts
Raspberry	deep	shovel	perky
Rose	deep	shovel	perky
Sheep sorrel	shallow	spoon	perky
Shepherd's Purse	shallow	spoon	perky
Sow Thistle	deep	shovel	wilts
Strawberry	shallow	spoon	perky
Sumac	deep	shovel	perky
Sunflower	medium	shovel	wilts
Thyme	shallow	spoon	perky
Tumbleweed	shallow	trowel	perky
Violets	shallow	spoon	perky
Wild lettuce	medium	trowel	wilts
Willow	deep	saw, shovel	perky
Wintergreen	shallow	spoon	perky
Wood sorrel	shallow	spoon	perky
Yarrow	medium	trowel	perky

Glendale Library Plants.
(See page 276)

Edge your wild foods garden both to keep out nonedible plants and to give it a sense of unity.



Edgings and Path Decorations

Top (left to right): crosscut circular slices of log, bricks, 2 by 4 ends buried in ground, smooth egg-shaped rocks with soil in between, straight limbs or poles.

Second row (left to right): Natural fences from wood, larger slate pieces, roundish stones, cut poles in a raised bed.

Third row (left to right): Cross fencing or picket sections, crosscut logs halved, 2 by 4's,

Bottom row, (left to right): large cut lumber boards, flagstones or bricks, decking or patio lumber, stones.



So much depended on wood.

Illustration from *A Glimpse of Peace* and *Flickering Free* written by Ken Heitz, illustrated by Linda Heitz (Runyon)

Linda's former husband Ken published two now rare books back in the early 70's now out of print.


DRY
ACIDIC
ALKALINE
WET
WOODS
WHITE BIRCH
MEADOWSWEETS
PINE
WINTERGREEN
BALSAM FIR
MAPLES
FIELD
RASPBERRY
BLACKBERRY
BLUEBERRY
STRAWBERRY
ASTERS
FIREWEED
GOLDENROD
YARROW
BURDOCK
THISTLES
RED SUMAC
NETTLES
DRY
SANDY
PRICKLY PEAR
CHOLLAS
QUEEN ANNE'S LACE
PLANTAIN
YELLOW DOCK
FILARIE
GRAVEL
ROADSIDES
CULTIVATED
FERTILE
SHEPHERD'S PURSE
PURSLANE
CHICKWEED
LAMB'S QUARTERS
WET
BULRUSH
CATTAILS
ARROWHEAD
MINTS
VIOLETS
FERNS

Soil-type matrix where wild foods are naturally found.

Legend:
A hypothetical complete Wild Foods Garden.

▨ **Woods.** . .Includes: wild & weeping willow, maples, white birch meadowsweet, pine, balsam, & wintergreen.

▨ **Field**. . . Includes: raspberry, blackberry, grapes, strawberry & blueberry.

▨ **Wet.** . .Includes: bulrush, , phragmities, cattails, arrowhead, ferns, violets & mints.

▨ **Dry**. . .Includes: red sumac, thistles, nettles, daisies, asters, fireweed, goldenrod, yarrow, tumbleweed & burdocks.

▨ **Sandy**. . .Includes: prickly pear, aloe vera, cholla & saguaro.

▨ **Fertile / Roadsides**. . .Includes: lamb's quarters, amaranth, purslane, mustards, wild lettuce, chickweed, dandelion, shepherd's purse, milkweed, plantain, malva neglecta, yellow dock, filarie, chamomile, Queen Anne's lace & thyme.



Left: lambs quarters Right: sheep sorrel

Public Wild Food Identification Walk Ways

Sabael Walk 1982-1983

Sabael, New York



A completely natural Garden.

After her homesteading years, Linda's first home became the first public wild foods identification walk.

First year: Added topsoil, made raised beds using railroad ties. No fertilizing done. Rocked the natural areas, built bridges over swamp into woods. Peat mossed individual plants, as well as used heavy hay over winter.
Second Year: Complete regrowth of every species except sparse wintergreen patch. Presence of red dots on leaves indicated overly acidic soil because of balsam trees close by (natural to area). All beds peat mossed for second summer.

> ***Linda says-*** I loved this first public walk around my cottage where I had electricity for the first time in 13 years. I maintained this walk for 2 years and then moved it to Rose & Bruce Burke's. This walk was studied by over 3000 people.

Burke's Cottage Garden 1983-1985

Sabael, New York

First Year: Rototilled a strip of lawn and transferred plants to rock-ringed sections. Added 6 inches of peat moss after one month's growth. Some harvesting and thinning necessary.
Second Year: Regrowth fantastic-100%.
Third Year: Good regrowth in most beds; poor regrowth of grape, meadowsweet, cattail (unattended).
Fourth Year: Plants assimilated back into mowed lawn.



Burke's Cottage Garden.

Linda says- Down the street from my home, Mr. and Mrs. Burke gave me an area to build a wild food walk. This was well marked and I gave a "tour" twice daily for two summers, before moving on to the Runyon Institute.

Note: All trees planted continued growth: birch, pine or maple. The rest returned to lawn. This walk was seen by over 3000 people.

Runyon Institute Walk

Warrensburg, New York 1986

The Runyon Institute ran for one year in Warrensburg, New York. This was the third food identification walk developed for public use. The strip was made up of common lawn plants, and the walk demonstrated the area's natural habitat.

First Year: Rototilled the strip of lawn. Added topsoil, gravel walkways, wood 2x4's in between plants transplanted from natural areas which exhibited rapid growth. Peat moss added on successive harvesting of most sections. No fertilizers used. Assimilated into lawn after first year.



Runyon Institute Walk.

Linda says- The Runyon Institute was founded by a businessman named Walter Johnson. The building was founded in my name, and it hosted over 6,000 people, showing them our wild food walk. Unfortunately, I needed to close the institute and move closer to home in North Creek where the white water rafting walks began. The Runyon Institute walk was maintained for two years. Hundreds walked the graveled paths. Trees remained and prospered.

Nantikote Lenni Lenape Walk

Bridgeton, New Jersey 1987-1988

The Nantikote Lenni Lenape developed this walk in 1987. Research done here has been invaluable for developing future food walks.

First Year: Rototilled a strip of lawn in Bridgeton City Park. Added garden topsoil. Tepee wood stays used for wheel design and plant separation. Applied 6 inches of peat moss after 2 to 3 weeks growth.
Second Year: Unattended garden prolific with growth. Largest leaf and seedling growth of all walks. Assimilated back into park after third year. I couldn't attend this one personally but once every 2 months.



Nantikoke Lenni Lenape Walk.

Linda says- I was asked to consider a wild food walk in Bridgeton City Park. This was Native American land, and I was pleased to work with Jim Ridgeway as well as other members of the Nantikote Lenni Lenape tribe. This walk was graciously maintained for 2 years by the Nantikote Lenni Lenapi Indian people. It closed in 1988.

"Rafting the Glenn" Walk

Warrensburg, New York 1985

First Year: Put peat moss 6 inches thick around transplanted seedlings. Natural watering. Occasionally harvested smaller "lawn foods." No fertilizers added. Some trimming done of raspberry, blackberry, roses.

Second Year: Unattended except to weed patches, add 6 inches more peat moss. All plants survived winter except for birch, pine, and cattails. Replanted more lamb's quarters.



"Rafting the Glenn" Walk.

> ***Linda says-*** Many of my students were young campers from white water rafting company. I particularly enjoyed the river a few yards away.

McManus Wild Food Walk

Sun City, Arizona 1990

First Year: Soil prepared to deal withcaliche (desert soil). Added in equal quantities peat moss, compost, topsoil. Used raised beds, wood sides. Plants easily transplanted with spoon and trowel. Irrigated with bubbler and hose twice a month, otherwise unattended.
Second Year: Unattended; temperatures of 110 degrees for two months. Harvested remaining plants, seedlings, and seeds. Strip assimilated into neighboring areas.



McManus Walk.

Apprentice Hazel McManus.

Linda says- A gourmet cook, Hazel of Sun City, Arizona, hosted many wild food luncheons for me. Our local television stations covered these wild food functions.

Glendale Library Walk

City of Glendale, Arizona 1995-1997

David Schultz, water conservationist, was instrumental in the planning and maintenance of this walk, working along with Linda Runyon.



Glendale Public Library Walk.

The public visited 11 squares open in the pavement each 10' x 10', and boasting 101 wild plants and grasses in total. An underground sprinkler system was used to maintain and control this mammoth "desert" walk of wild edibles. The squares were filled with potting soil and fine desert soil and laced with peat moss. Everything was kept natural, even the use of an insect deterrent made from gigantic batches of garlic, olive oil and dish soap. Mixed in equal parts of one third each, this concoction kept the Arizona whitefly from eating the succulent new young seedlings.

Linda gives a tour.

This walk had well planned sign information using a color coded safety system: Yellow—use caution, Red—use BIG caution, and green—may eat freely after individual testing. The signs also included botanical and common names, as well as other pertinent information on edibility.

Drilling into the hard Arizona soil.
Left: John Hunkele, right: Richard Bond.

My hat is off to the City of Glendale and David Schultz. Many factors contributed to the now closed project. My hope is to bring my experience to others.

Wild Food Plant Walk

Greenwich, New Jersey, at the Children of the Earth school, started 2004

First Year: Plants were easily potted separately in native soil. The size of the pots varied to accommodate anticipated eventual growth. (Mullein grew to be 6 feet tall!) All plants were clipped and eaten from time to time, especially when a Wild Food Walk Lecture was in progress. Children kept the plants watered.

Second Year: The pots were transported to my field for the winter, and were covered in snow from time to time.

Third Year: The plants were abundant, and even more dense than the first year. Seeds fell and the soil was full of each individual plant. The Walk was used by the school for another summer. The plants wintered with the owners of the school in southern New Jersey. As of this writing (July, 2007), the plants have grown tall and quickly in the pots, just like the second year.



New Jersey Walk

Fordville, New Jersey, 2005-2006

First Year: This very elaborate walk required several truckloads of 4 x 4's (cut into 2 x 2's) and several loads of mulch to complete. The entire walk was 75 feet long, Because the New Jersey farm soil is so fertile, individual plants became extremely lush, spilling over in some sections and being difficult to maintain. Mullein grew to a height of 7 to 8 feet, and the Queen Anne's lace flowers were the size of cup saucers. I was by myself on this one and found it so overwhelming that I closed it after the first year. However, were there to be a crew of caretakers, such as scouts or nature park people, this type of identification center could see thousands of interested visitors.

Second Year Research: I went back to the walk, and saw that everything was coming back up.



1. White Pine
2. Aloe Vera
3. Amaranth
4. Burdock
5. Chamomile
6. Chickweed
7. Chickory
8. Mullein
9. Clover
10. Plantain
11. Dandelion
12. Cattail
13. Evening Primrose
14. Queen Anne’s Lace
15. Curlydock
16. Wild Pepper
17. Sorrel
18. Blue Lettuce
19. Sassafras
20. Maple Tree
21. Nutsedge Grass
22. Dried Barley Grass
23. Crabgrass
24. Yarrow
25. Thistle
26. Goldenrod
27. Violets
28. Daylily
29. Sunflowers
30. Nettles
31. Mustard
32. Mints
33. Milkweed
34. Malva Neglecta
35. Lambs Quarters
36. Daisy
37. Willow Tree

Wild Foods Indoors

A house, apartment, roof garden, garage, or balcony are excellent areas to grow wild plants. Suitable containers for these indoor plants vary widely. Clay or plastic pots, pails, and washtubs all make ideal planters. You may even use half-gallon cans spaced evenly with a board placed on top to make an attractive shelf. There are many good books on container gardening and on growing plants indoors. Wild plants adapt easily to these ideas. Put your plants in areas of the house according to their outdoor environment. Many of them like water; the bathroom has steam, for example. Plants that like cold can thrive in a basement. I found that thyme loves heat and sun, dandelion loves the basement, near a window. Mint loves steamy areas.

The following are some plants that can be grown indoors:

Blackberry
Blueberry
Bulrushes
Daisies
Lamb's quarters (western variety)
Mallow
Phragmities
Purslane
Queen Anne's Lace
Raspberry
Roses
Sheep Sorrel
Shepherd's Purse
Tumbleweed
Violets
Yarrow

Use soil that is appropriate for the individual plants, with perhaps some rich potting soil added. Provide the suitable temperature and moisture level, and the plant will flourish. Ruth Spring, from Indian Lake, taught me to bring in dandelion, chicory, and wild lettuce for the winter. I planted them whole with their corresponding soil.

A Modest Proposal

Over 70 percent of the people in the United States live in an urban environment. More and more, urban parks are falling victim to surface pollutants, smog, ground water contamination, and, in some areas, apathy. It is harder and harder to find a clean urban area.

Potential sites for wild foods include fields, garden centers and private nurseries, environmental centers, camps, Boy or Girl Scout Centers, outdoor recreational centers and state or national parks and churches. The empty field in the middle of a city block is perfect for an urban garden. Waste areas seem to already have almost all the wild foods necessary. Add a few park benches, perhaps a water fountain, and a sandbox for the children. Plant a rototilled swatch with seedlings from nearby, edge it with wood or stones, and you have an instant identification center.

About 85 million people are added to the world population each year.[1] According to the U.S. Census Bureau, the global population doubled between 1959 and 1999, reaching 6 billion. Despite success in increasing global food production, the number of hungry people is growing. It is now thought to be 950 million—almost one fifth the world's population is underfed. Poverty is the cause. Every 24 hours, 25,000 human beings die as a result of hunger and starvation, 24 every minute, 18 of whom are children under five years of age. Acute human exposure to pesticides (such as that experienced by unprotected farm workers) is frequently fatal; 3,000-20,000 people die from pesticide poisoning annually. Human intervention to repair degraded lands takes two forms: restoration and rehabilitation. Of the two, only restoration aims to return a site to its natural state, complete with all the species that existed there before human disturbances. Rehabilitation is much more utilitarian. Its goal is to make the land productive for human use, employing whatever species and techniques which are most effective, regardless of whether they are indigenous or not. In the developing world, rehabilitation is likely to have a more prominent role than restoration because of the needs of growing population.

Perhaps the word *permaculture* is applicable here. What is permaculture? It is an attitude, a way of seeing what is before one's eyes, of enabling. It is a science, or study of natural systems such as water and plants. Permaculture focuses on *sustainable systems*, those with no pollution or waste. Permaculture is also an *ethic*. All systems of human activities support the earth's ability to sustain a diversity of life. Humans interact with their environment in mutually beneficial ways. Lastly, permaculture is a lifestyle that channels this knowledge and ethic into appropriate activities.

---

[1] World Resources, the World Resource Institute published by Oxford University, 1990.

Using wild food plants to restore the earth is the best way an individual can help at the local level. With very little help from us, the earth restores our food supply.

The urban food field is but a drawing board away. Wild foods can easily be incorporated into our educational system. Curriculum, books, tapes, videos, and newspaper articles as well as TV programs can bring this concept to the public. The environmentarian way of life is being born again!



A Forager's Research Diary

There are large gaps in our knowledge of wild foods, especially in how to incorporate them into our lives. I'm always conducting experiments with these plants, seeing how well they do in a garden, whether there are new ways to use these traditional foods, and how potent the seeds remain.

The following are my notes on such experiments, along with material from the work done by my students. Growing and using wild foods remains unexplored territory.

I hope to encourage you to do your own experimentation with wild and backyard foods—not just with growing and harvesting, but in creating interesting menus for you and your family.

Purslane Experiments

Question: will dried purslane reconstitute in water? If so, will it grow and sprout roots? Can it be used reconstituted for food? Dried purslane will reconstitute well soaked in water. The plant will not sprout roots as it grows from seed. Reconstituted for food only.

August 1 Picked a large amount of purslane. Filled a screen 1 by 3 foot. Placed screen in an inside open window receiving only afternoon sun (2:00 p.m. to 4:00 p.m.).

August 3 Purslane roots were cut off. Black seeds from the center of the leaf clusters dropped onto the screen. There are only a few green pods in the center of the leaves still filled with seeds. Pods were apparently immature at time of picking.

September 1 I cut off the dried, withered stem of a twig about 7 inches long and placed in water. The leaf part opened and filled with water, although the branch did not appear to grow any quicker than the one on the screen.

September 13 Purslane in water growing well. Stems and leaves on the screen are dried and crumbly. On top of the purslane mat and up through the dried stems a completely new growth is visible. On close examination, I saw a 7-inch stem with five extensions off the main stem. Healthy green leaves extend off tips of the top three branches, with 3 tiny leaf buds appearing between the leaf extensions and joints of stem. Average size leaf is 1/2 inch. Lower two stems are weak, partially dry, flaccid at base. Small leaves extend on the tips, green and apparently healthy. All leaves are thinner than normal, stretched toward the light and do not have the succulent appearance of purslane growing in a field. Taste same. Stems are crispy and solid, about 3 1/2 to 4 inches from tip to the base. The 4 inches of base stem are apparently weak, discolored reddish, deeply veined, devoid of succulence.

September 21 Clipped 1/4 inch off the thicker, central stem. Placed in a cup of water. Cells at the end look green and open under magnification. Stems are tightly veined and devoid of moisture. Color basically a red hue with a touch of green where the stem lay against the bottom plants on the screen. Leaves small, 1/2 inch as a norm, growing green and alert toward the western light of the window. Multiple branches tipped with green leaves have one or two small branches with small green leaves. Two necrotic twigs cut off cleanly with scissors. Cup, water, and twig placed out of direct light of window at 7:00 a.m.

Conclusion: Purslane dries in several days or weeks, according to moisture in the air. New growth can be seen throughout as old growth dries. Roots take in moisture from air and mat of purslane itself.

It appears that old dried purslane may be easily reconstituted in water, yielding edible food. In drought conditions, plant may be utilized with small addition of water. Purslane appears to be one of the hardiest of plants; after two months of drying, it was easily reconstituted in water.

Amaranth Experiments by Althea Dixon, student

Background: In 1992 Arizona experienced an unusually large rainfall. By May 1, we had received all the rain we usually get in a year. We had so much moisture in the adobe soil that mold was killing some of the clover and mushrooms were sprouting up. Amaranth appeared in the goat pen, thanks to these heavy rains which led to some experimentation.

August 13 I cut the first harvest from plants averaging 8 to 16 inches in height. Because of the abundant rain and rich soil, they grow with an umbrella of leaves, creating a mini-rain forest environment with lots of seedlings beneath. I remove the tops down to 4 inches above the ground.

August 17 The amaranth crop has grown from 8 to 12 inches in just four days!

August 18 Harvest two plastic grocery sacks full of tender amaranth tops. Crop is harvested to about 12" inches. Total fresh yield is 16.5 pounds.

After the harvest I notice that the soil is still well underneath, and the crop is growing without noticeable red on the stems, which is good. I can get another crop or two from this patch.

I also notice that amaranth growing in the direct sunlight does better than that growing in shade, the latter attacked by bugs causing leaf damage.

August 19 Dryers yielded 1.75 pounds of leaves and stems. After the major crop is dried, heavier stalks still have bulk and moisture enough to mold the rest of the batch. I cut stalks out with scissors and set them in an airy box for another week to finish drying. Further drying of whole batch would damage the already dry tender parts.

The high humidity is softening the tender leaves. I may have to put them in the dehydrator for an hour before whizzing them to flour. I don't know what effect this will have on nutritional value, but the color remains excellent.

August 20 Last night we had a heavy rain. I checked the progress of the amaranth and observed that undergrowth is now up to 12 inches. The day-old seedlings that were about 1/8 inch cotyledons are now between 1" and 2" seedlings, with primary leaves approximately 3/4 inches from stem to tip of the leaf.

August 24 Heavy rains over weekend. The cotyledons and primaries now have tertiary leaves and are approximately 3 inches tall. The undergrowth is now 12 inches high.

August 26 Harvested one shopping bag full. Do not weigh the green crop. Dryer yields 8 ounces of flour. By volume it makes 1 2/3 cups. Have lost only a small amount of chaff, which I sifted out of the flour as it comes from the high-impact grinder.

August 27 No rain since 8/24 in A.M. Crop has leveled off. Undergrowth continues to catch up with umbrella top at approximately 30 inches.

I harvest two more bags of tender tops this morning. These bags were the same volume as the batch on 8/18, however, they weigh only 6.5 and 5.5 pounds respectively. I fill the same number of dryer trays, but net weight of crop in dryers is 10.5 pounds. I use 1/2 pound of large stalks to make "beans."

The 4-inch seedlings are now averaging 7 to 9 inches tall with no further rain or water since 8/23. After harvesting four shopping bags of vegetable in four days, it appears there are at least 2 to 4 more harvests with no further need of water. Have not harvested red-stemmed plants; these are for seed.

August 28 Dry yield is 2 pounds 2 ounces, or 5 cups. Discarded 1 ounce of chaff plus one stem that had not dried Also lost powder in the air as it was moved from one container to another, as well as leaf fragments too small to handle.

September 12 After running it through high-impact grinder, I get 2 quarts of flour. Dry weight is 2.13 pounds, of which 1/4 inch of heavy stem chaff is discarded.

It is interesting to note that although the heavier stems had dried hard, the humidity had gone from 20 percent to 46 percent during the wet season in Arizona, and the batch gained moisture overall. Though the texture is less crisp (the leaves would bend without breaking), I have more trouble with chibbled leaves. The color is still excellent, but more on the olive side, which I believe is due to a higher percentage of stem content in the end product. Stems dry brown whereas leaves dry green.

Conclusions:

The best procedure for harvesting to flour is as follows: Bring crop directly from garden to dryers (wash the night before with gentle water from hose) and let dry 24 hours. Rearrange trays about halfway through if dryer is old-fashioned kind with no heat or air controls. When putting crop into dryers, trim stems thicker than 1/4 inch and cook as fresh beans. This way crop is completely dry at the same time. Place directly into high-impact grinder from dryer trays; doesn't hurt if still warm. Strain chaff with a fine sieve and set to one side. Rerun the chaff all together and then sift again. What little chaff is left can be thrown away. Put flour in tightly sealed glass jars. Wrap in foil to protect from the light, and label with name of product and date. Keep in cool dry place.

Time: It takes 45 minutes to process 18 dryer trays from dried leaves to vegetable powder. It takes 30 to 50 minutes to harvest two grocery bags of fresh vegetables.

Caution: After plants form seed pods, use gloves to harvest and process flour. When processing indoors, protect lungs from flour in air by using a mask.

Reconstituted Amaranth Leaves: Can dried leaves be reconstituted to produce a palatable food item? Yes. Dried green leaves were soaked in cool distilled water for one hour, and then simmered until tender, about 5 minutes. I used only enough water to cover the leaves. The texture was so good it was almost like fresh.

Additional Comments: Was not satisfied drying amaranth outdoors. One crop got rained on and the vibrant green leaves turned sickly gray. In a survival situation you do what you can, but if domesticating amaranth, why not get the best-quality, highest nutritional product possible?

The reason for not putting amaranth in water is that if you have to leave it for any reason it can very quickly take on a dark gray color from the iron, and the quality of the dried product is not appetizing.

Further Comments: In September, 1993, the amaranth flour was inspected for color. It had remained bright green, and flavor in breads was excellent. For even longer storage, vacuum pack in plastic and store in cool dark place.

Grinding greens to flour.

Lamb's Quarters for flour.

Notes



Left to right: wild mustard, chamomile, dandelion and thyme.

Part V: Poisonous Look-Alikes

Here are a few troublesome plants for wild food foragers to be aware of. These are by no means the only poisonous plants out there, but they are some of the most common and are most easily confused with the plants that have been covered in the edible plants section of this book.

See also "An Introduction to Edible Plants" in Part I, especially the section on picking wild foods (page 22).

Caution: It is sometimes not the close up that is confusing, but the same plants identified at a distance can fool you.

Please Note: There are many varieties of poison hemlock, geographically spaced in all countries. Please note all species have similar characteristics. Smooth purple striated or blotched stems. Flower clusters on single stems from main stem. Hollow, circulated banded roots. Always be sure of 100% identification.
Cross reference:
Queen Anne's Lace with any white top-flowered umbrella.

Water Hemlock—Poison

Spotted Cowbane
Circuta maculata

Habitat: Wetlands, wet meadows, swamps. Canada south to Texas. This fact was observed some years ago. Do not take the state perimeter too literally.
Characteristics: The MOST DEADLY plant. Any part will kill humans. White flowers, clustered in umbrella on single stems. Stem is smooth, streaked with purple. Stem, roots chambered. (See page 292 for illustration.) All parts may even simulate smell of mild parsnip or carrot.
Caution: DEADLY POISON.



Poisonous - Water Hemlock

Poison Hemlock—Poison ☠

Conium maculatum



Poisonous - Poison Hemlock

Habitat: Waste ground, Iowa to Quebec South, approximately. Other genus or types on West Coast, even wet desert areas.

Characteristics: Blooms May through August. Umbrella shaped flower cluster, lacy white flowers. Dried flower maintains its umbrella shape, develops rusty colored seeds. Stalks are hairless, stout, hollow and grooved with spots of purple stripes. Small amounts may cause paralysis and death. DEADLY. Roots look like a wild carrot, but are hollow. A deadly poison. (See illustration next page.)

Caution: Poison Hemlock Looks like Queen Anne's lace until flowers dry. Use 3 excellent picture references and make sure you identify Hemlock properly and DO NOT TOUCH OR INGEST. HEMLOCK IS DEADLY. (See illustration of Poison Hemlock.)

Queen Anne's Lace—Food ☺

Daucus carota

Wild Carrot



Edible - Queen Anne's Lace

Habitat: Waste ground fields

Characteristics: HAIRY-STEMMED biennial. Umbrella shaped flower cluster, lacy white flowers. All parts smell like a carrot. Old flower clusters "bird cage" into a seed cluster. Parsley-like leaves smell like a carrot. All stems are hairy, the root is SOLID & pithy. Smells like a carrot! (Also see page 116 in Field Guide for further description of this edible plant.)



A: Poison Hemlock Root

B: Poison Hemlock root in cross section

C: Queen Anne’s Lace root – food

Please note: Poison Hemlock (A and B) has hollow chambers with rings at the base of the stem and throughout the root. Queen Anne’s Lace (C, on right) has a solid twig-like pithy root with hairy stems.



Poison - Water Hemlock Root.

Poison Sumac—Poison

Rhus vermix ☠

Habitat: Wooded swamps.
Characteristics: Leaves, 6-12 inches long with 7-13 points, leaflets. First difference between sumac for food and poison sumac is that the poison variety has smooth leaflets. Poison berries are white. (See page 126 for description of the edible variety.)



Poisonous - Poison Sumac

Edible Sumac—Food

Rhus Species ☺

Habitat: Shrub or small tree found in all areas of the United States.
Characteristics: Twigs have milky sap. Fruit is red, hairy, and dry at maturity. Leaves: saw-tooth leaflets. (See page 126 for details.)



Edible - Sumac

Nettle Leaf Goosefoot—Poison

☠

Goosefoot family: Chenopodicea

History: Naturalized from Europe.
Habitat: Moist soil, roadsides, around crops such as alfalfa, citrus, vegetables.
Characteristics: Grows to height of 1 to 3 feet, smells rank.
Caution: All raw edible parts are toxic or poison to humans.



Poisonous - Nettle Leaf Goosefoot

Lamb's Quarters—Food

☺

Goosefoot family: Chenopodicea

History: Naturalized from Europe.
Habitat: Moist soil, roadsides, gardens, crops such as alfalfa, citrus, vegetables.
Characteristic: Grows to height of 1 to 3 feet. Smells similar to spinach. Leaves are soft and have a white powder underneath. All parts edible. Good food. (See page 93 for complete description.)



Edible - Lamb's Quarters

Field Horsetail—Poison

Equisetum Arvense ☠

History: Family over 400 million years old.
Habitat: Wet, moist areas, swamps, lakesides, river banks.
Characteristics: Jointed green, like grass. All parts contain silicon; are toxic to humans. Abrasive silica in all parts, so plants will scrub aluminum clean.
Medicinal Value: Folk medicine wound healer, diuretic in very small amounts.



Poisonous - Field Horsetail

Grass—Food

Graminae ☺

Characteristics: Curls and grows up like horsetail. Horsetail grows in longer grass areas. We need to examine all types of grasses carefully when choosing grass to be clipped for food. Pull out any field horsetail. (See section beginning on page 35 for complete description.)



Edible - Grass

St. Johnswort—Poison

Hypericareae ☠

Other Names:
Hypericum perforatum
History: Known for medicinal value since biblical days. Europe, herbalists.
Habitat: Fields, roadsides.
Primary Use: Leaves used as astringent and salves for bruises, wounds, anti-inflammatory.
Characteristics: Leaves shaped like lungs with many tiny holes in them. Plant grows to 1 1/2 to 3 feet. 5-petaled flowers. From a distance, plant shape is similar to the pocomoonshine variety of goldenrod.



Poisonous - St. Johnswort

Pocomoonshine—Food

☺

(Variety of Goldenrod)
Augustifolum (specific species in the *Compositae* family)

Other Names: Poco moonshine
History: Native to Europe, Asia. Naturalized in North America.
Primary Uses: Culinary, medicinal, commercial. Leaves dried for tea. Oils and extract used commercially in baking, ice cream, soft drinks, chewing gum.
Characteristics: Flowers at end of many branches 6 to 18 inches, considered an herb. The smell and uses are the same as other Canadian or sweet goldenrod species in field guide. See Goldenrod, page 90, for complete description.



Edible - Pocomoonshine

Spreading Dogbane—Poison

☠

Apocynum species

Habitat: Thickets, roadsides. Characteristics: Perennial herb. Wide spreading branches, opposite leaves 2 to 3 inches long. Pink nodding bell-like flowers with pink stripe in center of each lobe. Shoots of Dogbane are hairless and quickly branching.



Poisonous - Spreading Dogbane

Common Milkweed—Food

☺

Aslepias Syriaca

Habitat: Fields, roadsides. Characteristics: Downy stemmed shoots. Leaves from 3 to 6 inches, deeply veined. Flowers dome shaped, tight, drooping clusters. After flowering, buds give way to seed pods. Crescent shaped pods, when young, may be dipped in batter and deep fried or boiled. (See page 101 for culinary uses.)



Edible - Common Milkweed

Dallis Grass—Poison

Gramineae Family

☠

History: Native to South America, found on North American continent in the west.
Habitat: Arizona
Primary Uses: None for humans.
Caution: This grass is very susceptible to fungus attacks by paspalum ergot which is a DEADLY POISON to cattle; humans.
Characteristic: Grows to height of 1 1/2 inches. Has tight large seeds placed in a way as to attract black mold easily.



Poisonous - Dallis grass

Jungle Rice—Food

Echinochle colonum
Graminae Family

☺

Other Names: Water grass
History: Used for food in Asia, Africa.
Habitat: Fertile desert soils of the West around crops such as sorghum, cotton, alfalfa, melons, lawns.
Characteristics: Grows 1 to 1 1/2 inches high. A sedge, but dark spots of camouflage. Areas of stems are jointed.



Edible - Jungle Rice

Stink Grass—Poison

Gramineae Family ☠

Other Names: Lovegrass
History: Native to Europe.
Habitat: Found growing around base of crops such as Sorghum, Alfalfa, Citrus, gardens and waste areas.
Characteristics: Annual grows to heights of 4 inches to 2 feet. Whole plant has a cockroach like odor, rank and offensive. Flowering parts 2 to 10 inches long. Poison.



Poisonous - Stink Grass

Yellow Nutsedge—Food

Cyperus esculentus ☺
Sedge family

Other Names: Yellow nutgrass.
History: Introduced from Europe.
Habitat: Cultivated fields, edges of crops, wet areas, ditches, roadside, streams.
Characteristics: Umbrella-like flowering tops have a thread-like projection extending from seeds and flowers. Roots have small nut-like tubers which can be used as a highly nutritious food. (See page 35 for complete description.)



Edible - Yellow Nutsedge

Purslane—Food

Portulaca oleracea

☺

Note: Purslane can be confused with White Margin Spurge, Hyssopspurge or Puncture Vine.
Habitat: Rich, sandy soils, waste places.
Characteristics: Prostrate paddle-shaped succulent leaves, tiny 5-petaled yellow flowers open in sunlight. Purslane has no milk. Leaves and stems succulent and make delicious food. Plant has a shallow tap root. (See page 115 for details.)



Edible - Purslane

Please Note: The following 3 plants are look-alikes to Purslane. When viewed from a stand height, the look of the ground cover is similar for all of these plants.

White Margin Spurge—Poison

Euphorbia albomarginata

☠

Other Names: Rattlesnake weed
Habitat: Dry barren dirt areas along sidewalks, waste places.
Characteristics: All parts toxic, whitish milk in stem, leaves. Red blotches in each leaf.



Poison - White Margin Spurge

Hyssopspurge—Poison

☠

Euphorbia hyssopifolia

Habitat: Grass, fields, crops, irrigated areas.
Characteristics: Annual. Toxic plant contains silicon in all parts. Has a white sticky milk. Grows erect, stems hairless.



Poisonous - Hyssopspurge

Puncture Vine—Poison

☠

Caltrop zygophyllacea



Poisonous - Puncture Vine

Other Names: Bullhead, goathead
History: Native to Europe.
Habitat: Roadsides, gardens, fields, crops.
Characteristics: Prostrate plant has a shallow tap root, 5-petaled yellow flowers which open in sun. Seedpods contain a cluster of 5 spiny burs or nutlets that contain the seeds. Toxic to animals and humans.

Appendix: Glossary of Scientific & Botanical Terms

Alkaloid: Basic, bitter-tasting organic compound containing nitrogen and forming water-soluble salts and acids.
Anodyne: Soothes or allays pain.
Antiscorbutic: Prevents scurvy.
Antiseptic: Prevents infection; kills germs.
Anti-spasmodic: Calms nervous and muscular spasm.
Aphrodisiac: Increases sexual stimulation and excitement.
Astringent: Diminishes secretion, contracts tissues.
Areole: In cacti, a clearly defined small area that may bear felt, hair, spines, glocids, flowers, or new branches.
Bacteriostatic: Inhibits the growth of bacteria.
Balsamic: Soothes mucous inflammation, especially of respiratory and urinary tracts.
Calyx: Outer whorl of floral leaves (sepals), which may be separate or fused.
Carminative: Expels gas from the stomach and intestines.
Cathartic: Purgative.
Chibbled leaves: see Compound leaf.
Compound leaf: Divided into two or more leaflets. The leaflets can be further subdivided, twice compound, or even thrice compound.
Corm: Enlarged base of a stem; bulblike but solid, not layered like an onion.
Cotyledon: First two leaves emerging from embryo.
Decoction: Liquid prepared by boiling with water and straining the cold solution.
Demulcent: Protects and soothes the mucous membranes.
Diaphoretic: Increases perspiration.
Digestive: Aids digestion.
Diuretic: Increases the flow of urine.
Dysentery: Diarrhetic condition or disease.
Elixir: Alcoholic tincture with sugar.
Emetic: Substance that causes vomiting.
Emmenagogic: Brings on or regulates menstruation.
Emollient: Soothes and softens the skin.
Essential oil: Plant oil, usually scented, that evaporates at a low temperature. Also known as a volatile oil or ethereal oil.
Expectorant: Helps expel phlegm.

Extract: Dry, soft, or liquid preparation. A fluid extract may be prepared with alcohol, distilled water, or alcohol and water.
Febrifuge: Substance that lowers a high temperature or prevents fever.
Glocids: Thin barbed bristle, produced in the aereoles of chollas, prickly pears, and a few other cacti.
Glycoside: Compound combining sugar and nonsugar units.
Hemostatic: Arrests bleeding.
Hepatic: Beneficial to the liver.
Infusion: Liquid prepared by pouring on boiling water and later straining the cooled solution.
Laxative: Mild purgative.
Leaflet: Division of a compound leaf.
Macerate: Soak in liquid to soften and dissolve.
Mucilage: Gelatinous substance swelling, but not dissolving in water.
Narcotic: Induces sleep or drowsiness.
Nerve tonic, nervine: Stimulates the nervous system.
Ointment: Salve or unction for application to the skin.
Panicle: Loose, irregularly branched inflorescence with stalked individual flowers.
Pectoral: Relieves coughing and promotes expectoration.
Plaster: Preparation spread on material and stuck to the skin.
Potherb: Plant cooked as a green.
Poultice: Soft paste, hot or cold, wrapped in cloth and applied externally.
Pubescent: Covered with fine, soft hairs.
Salve: Unctuous adhesive substance applied to wounds or sores.
Sauté': To fry quickly, stirring constantly, until lightly browned.
Seed head: Part of plant that holds a group of seeds.
Sedative: Having a calming and soothing effect.
Stomatic: Aids in digestion and stimulates the appetite.
Stimulant: Excites the functions of various organs.
Stir-fry: To fry quickly in hot oil over very high heat, stirring until food is cooked.
Styptic: Astringent, checks bleeding.
Sundries: Accessories
Tertiary: Third set of leaves of seedling; may or may not display adult attributes of plant.

Tincture: Extract of drug, usually dissolved in alcohol.
Tisane: Dilute plant infusion or tea.
Tonic: Stimulates the activity of an organ.
Tubers: Modified, swollen root.
Unction: Soothing or healing salve, ointment.
Volatile oil: See essential oil.
Winnow: To place seed heads in basket, and move up and down to allow the chaff (inedible parts of the grain) to fly out of the basket, leaving the seeds.
Whole-leaf tea: Tea made with the whole leaf, not crushed; also tea made with whole twig, not pulverized.

Edible Centerpiece

References

References in the text to Cherokee, Algonquin, and Chippewa words are based on transliterations from the *Cherokee-English Dictionary*, edited by William Pulete (Dallas: Southern Methodist University Press, 1975).

Bigfoot, Peter. *Arizona Wild Herbs*.

Densmore, Frances. *How Indians Use Wild Plants for Food, Medicine and Crafts*. New York: Dover, 1974.

Duke, James, and Alan Atchley. *CRC Handbook of Proximate Analyses*. Boca Raton: CRC Press, 1986.

Harrington, H. D. *Western Edible Wild Plants*. Albuquerque: University of New Mexico Press, 1967.

Harris, Charles. *Eat the Weeds*. New Canaan Ct.: Keats Publishing, 1973.

Hodgson, Wendy Caye. *Edible Native and Naturalized Plants of the Sonoran Desert North of Mexico*. Arizona State University: Arizona, 1982.

Page, Nancy M. and Richard E. Weaver, Jr. *Wild Plants in the City*. New York: Quadrangle, 1975.

Pedersen, Mark. *Nutritional Herbology*. Bountiful, Utah: Pedersen Publishing, 1987.

Smith, Huron. *Ethnobotany of the Ojibve Indians*, Vol. 4. Milwaukee, Wis. 1883.

Sturtevant, E. Lewis, Dr., *Sturtevant's Edible Plants of the World*. Edited by Dr. U. P. Hedrick, New York: Dover, 1972.



Suggested Reading

Agricultural Research Service. *Common Weeds of the United States.* U. S. Department of Agriculture, Washington, D.C.: Government Printing Office, 1971.

Airola, Paavo. *Are You Confused?* Phoenix: Health Plus, 1971.

Angier, Bradford. *Field Guide to Edible Wild Plants*. Harrisburg, PA, Stockpole Books: 1974

Ball, Jeff. *The Self Sufficient Suburban Garden.* Emmaus, Pa.: Rodale Press, 1983.

Birdsey, Clarence, and Eleanor G. Birdsey. *Growing Woodland Plants.* New York: Oxford University Press, 1951.

Briggs, Jim. *Wild Foods.* Hamilton County, N.Y. Cooperative Extensions publisher, 1972.

Brookes, John. *A Place in the Country.* London: Thames and Hudson, 1984.

Brown, Lauren. *Weeds in Winter.* New York: W. W. Norton & Co., 1976.

Chase, Agnes, and L. E. Bailey. *The First Book of Grasses,* Rural Textbook Series. New York: Macmillan, 1982.

Coon, Nelson. *The Dictionary of Useful Plants.* Emmaus, PA: Rodale Press, 1977.

Cooper, Hewitt Museum, the Smithsonian Institute's National Museum of Design, 712 Fifth Ave., New York, N.Y. 10019, 1979.

Crockett, James Underwood. *Greenhouse Gardening.* New York: Time-Life Books, 1989.

Densmore, Frances. *How the Indians Use Wild Plants for Food.* New York: Dover, 1974.

Duffield, Mary Rose, and Warren D. Jones. *Plants For Dry Climates.* New York: H. P. Books, 1981

Elliot, Douig. *Roots: An Underground Botany and Foragers Guide.* Old Greenwich, CT: Chatham Press, 1976.

Evers, Robert A. and Roger P. Link. *Poisonous Plants of the Midwest & Their Effects on Livestock.* Spec. Publ. #24, College of Agriculture, University of Illinois at Urbana-Champaign, 1972.

Fairbanks, Bert L. *A Principle with Promise,* Salt Lake City: Bookcraft, 1978.

Gabel, Medard. *Energy, Earth, and Everyone.* Garden City, N.Y.: Anchoe Books, 1980.

Gaertner, Erika E. *Harvest Without Planting.* Montreal: Concordia University Press, 1967.

Gibbons, Euell. *Stalking the Wild Asparagus.* New York: David McKay, 1978.

Gilbertie, Sal, with Larry Sheehan. *Home Gardening at Its Best.* New York: Macmillan, 1977.

Goldstein, Jerome. *The New Food Chain. An Organic Link Between the Farm and City.* Emmaus, PA: Rodale Press, 1973.

Hardin, James W. *Human Poisoning for Native and Cultivated Plants.* Second Edition. Durham: Duke University Press, 1974.

Harrington, H. D. *Western Edible Wild Plants.* Albuquerque: University of New Mexico Press, 1967.

Harris, Ben Charles. *Eat the Weeds.* New Canaan, CT: Keats Publishing, 1973.

Hitchcock, Susan Tyler. *Gather Ye Wild Things.* New York: Harper and Row, 1980.

Hobson, Phyllis. *Food Drying.* Charlotte, VT: Garden Way Publishing, 1983.

Kingsbury, John M. *Common Poisonous Plants.* New York State College of Agriculture and Life Sciences, New York, 1976.

Kirschenew, H. E. *Nature's Healing Grasses.* H. C. White Publications, 1960.

Lappe, Frances Moore. *World Hunger: Twelve Myths,* New York: Grove Press, 1986.

Lappe, Frances Moore. *Diet For A Small Planet.* New York: Ballantine Books, 1971.

Lerzaa, Catherine, and Michael Jacobson, eds. *Food For People, Not For Profit; a Sourcebook on the Food Crisis.* New York: Ballantine, 1975.

Luenscha, Walter Conrad Leopold. *Poisonous Plants of the United States.* New York: Macmillan, 1961.

Life Seed Foundation, Box 72, Port Townsend, WA 98368 or Native Seed Search, Tucson, Arizona

Messegue, Maurice. *Of Men and Plants.* New York: Macmillan, 1973.

Michael, Pamela. *All Good Things Around Us—A Cookbook and Guide to Wild Plants and Herbs.* New York: Holt, Rinehardt and Winston, 1980.

Miller, Saul, and Jo Anne Miller. *Food For Thought.* New York: Prentice-Hall, 1979.

Morton, Julia F. *Herbs and Spices: A Golden Nature Guide.* New York: Golden Press, 1976.

Muramoto, Naboru. *Healing Ourselves.* New York: Swan House/Avon, 1973.

New Western Garden Book. Miami: Lane Publishing, 1979.

Niethammer, Carolyn. *American Indian Food and Lore; 150 Authentic Recipes.* New York: Macmillan, 1974.

Page, Nancy M. A., and Richard E. Weaver, Jr. *Wild Plants in the City*. New York: Quadrangle/New York Times Book Co., 1975.

Peterson, Lee Allen. *A Field Guide to Edible Wild Plants; East/Central North America*. New York: Houghton Mifflin, 1977.

Poisonous Plants of the United States and Canada. Englewood Cliffs, N. J.: Prentice Hall, 1964.

Public Health Service, *Typical Poisonous Plants*. Food and Drug Administration Booklet, #017-12-00177-7.

Scully, Virginia. *Treasury of American Indian Herbs*, Prineville, OR: Bonanza Publishing, 1974.

Simmonite-Culpepper. *Herbal Remedies*. Universal-Award House, 1970.

Sheffield, Charles. *Earthwatch*. New York: Macmillan, 1981.

Soltanoff, Jack. *Natural Healing*. D. C. Warner Books, 1988.

Sourcebook on Food and Nutrition. Chicago: Marquis Academic Media, 1978.

Stokes, Donald W. *A Guide to Nature in Winter*. Boston: Little, Brown, 1976.

Sweet, Muriel. *Common Edible and Useful Plants of the West*. Happy Camp, Calif.: Naturegraph Publishers, 1962.

Szeley, Edmond Bordeaux. *The Book of Herbs*. International Biogenic Society, 1971.

University of Alaska, *Wild Edibles and Poisonous Plants of Alaska*. Cooperative Extension Service, booklet #F-40, 1953.

U. S. Department of Agriculture and U. S. Department of Health and Human Services. *Dietary Guidelines*. Washington, DC: Government Printing Office, 1980.

Waisel, Yory. *Biology of Halophytes*. New York: Academic Press, 1972.

Western Society of Weed Science. *Weeds of the West*. PO Box 963, Newark, CA 94560, Rev. 1992

Whittle, Tyler. *The Plant Hunters*. Philadelphia: Clinton Book Co., 1970.

Linda Runyon

Don't Forget-

We have extras for you!

When you go into the kitchen to try the fabulous recipes contained in this book, you very well may not want to drag your computer with you! Printing is disabled in this eBook, but we have the whole printable Recipe Section waiting for you. If you act now, we will include a Free Subscription to Linda Runyon's Newsletter!

Just go here and we'll send them to you. (If your computer can't handle the direct link, please type the web address below into your browser's address bar and fly over to Linda's site.)

http://www.ofthefield.com/eBookSpecialOffers.htm

This is a secret back door for eBook owners like yourself ONLY, and can't be found by coming in the front door of the site.

Your email address is never given to third parties.
It is our strict policy.
You may opt out at any time.

Linda Runyon was raised in Plainfield and Watchung, New Jersey. As a child, she spent 3 months each year at her parents' camp in Indian Lake, New York. This wilderness setting was the background for her own wilderness experiences, homesteading on the outskirts of Indian Lake, NY. For 13 years she, her son, and husband lived without indoor plumbing, electricity or running water. This way of life blessed Linda with knowledge and many skills to live off of the land. She continues to enrich her life with these skills, even during her retirement in her comfortable log home.

Linda has written materials focusing on wild food products:

- A Survival Acre (50 Nationwide Wild Foods, Teas & Medicines)
- Wild Cards A Wild Food Card Deck
- Wild Food & Animals Coloring Book
- A Basic Middle Eastern Desert Guide of Edible Foods (Written for the Kurds)

Linda is a mother of 3, a Grandmother of 4, a registered nurse, an author, a lecturer and an artist.

www.OfTheField.com

Starvation is impossible with this book.



"This book shows how to identify, gather and prepare edible wild foods no matter where you live. This is one of the most empowering books I have ever read. There is no doomsday. Look down and eat up!"
--Reader in USA

"You'll never see the planet the same way after this survival guide!" -Biology student, ASU

"I feel safe everywhere I am with this food abundance!" - Peg, Ohio

"These plants are even in the sidewalks cracks in Manhattan. Just amazing!" -Evelyn, NYC

"Throw away all those other survival books on food - this one has it all!"
-Kevin, NY State

ISBN 093669910-8
9780936699103

Navigation Down Under

For
Northern-Hemisphere Tourists
Walkers and Scouts
Boating and Outdoor Orientation

1001 Ways to Extend

Your Navigational Know-How

2010

CONTENTS

Section page
1 BIG-PICTURE TOP-DOWN————————3
  Global Perspective
  Sun
  Stars
  Earth
  Moon
  Wind
  Clockwise Navigation
  Anticlockwise Systems
  Revision, Overview, Explanations
2 THE INSIDE STORY—Mental Manoeuvres—34
    Learn
    Think Interpret
    Look
    Integrate
  Orientation
  Disorientation
  Reorientation
  Lost?
    Miscellaneous: Angle; Night-time
3 REALLY INTERESTING STUFF
—Bush Navigation————————————56
  Nature's Norths
  Memory & Naming Skills
  Lie of the Land
  Tracks and Bends
4 DISTANCE————————————————90
  Progress
  Pace
  Range
MAP and/or COMPASS
  Map Use
  Magnetic Compass Use
  Mapmaking
5 Navigational Mnemonic————————110
6 Appendices———————————————116
  Tide and Moon Dial
  Star Charts; Zodiac
  Morse Code & Rhythm Mnemonics
  Semaphore Code & Mnemonics
  Symbols for Track-Notes & Mud-maps
  A List of Star Coordinates
  Great Circles; Calendars in the Sky
  Tropical Countries
7 Contents/Index——————————————128

Big-Picture Rule One: Locate a Distant Reference Direction First

Until you Orient yourself to the bigger picture, by finding an unchanging direction to latch on to,
•Small-scale pictures and large-scale mental layouts cannot come together. •And the local features won't fit into the bigger perspective.
•Your mental photographs will float around in chaos, like so many loose jigsaw pieces, or letters in an alphabet soup.
In choosing a Reference Direction, your first choice should be...
•ASTRONOMICAL — Sun, Moon, stars, planets, satellites—e.g. Locate the direction of the North Pole Star. There is an astronomical overview p32f
Then •GLOBAL — Compass or Botanical or Geomorphological North e.g. find Canada's North Magnetic Pole.
Next •CONTINENTAL — Weather Systems, radio transmitters, powerline networks, highways, sea-coast—e.g. notice the Sydney to Hobart flight path.
Then •DISTANT landforms — Lie, Lay, Lines, Hills; Lights, etc.—e.g. the direction of the main river valley draining to the sea.
Last of all comes: •What you can see in front of your nose! I.e. don't let your mind latch on to some unreliable or meaningless reference like how the car is parked, or where the wind is, or the initial direction of the track/the drive in/the main street, or uphill, or the way you got out of bed…
•If you can't see a thing beyond a few metres, and have no compass, you will need to "keep a straight line" (see p. 87b) by lining up markers.
Now that you have a reference direction, you can implement the other "Rule One"s...
•Match what you see in front of your nose to the reference;
•Predict your overall trend before you start; •Notice your start-off direction as you start.

Visualisation is your Key Skill

This is most especially relevant to orienting your nose, in your mind's eye, to the Bigger or Invisible Pictures, but is needed at all scales.

Imagine	where the Southern Cross is during the day;	or	where the cars are, now; how you got here.
Visualise	the Earth's invisible spin-axis	and	the weather map you saw, yesterday
Mentally picture	the Galactic spiral! — which clock-sense is it?	or	the turnoff you need — will it be uphill?
Remember	the tropical countries under the Sun	and	the way back
Describe	the path of a shadow-tip in mid-Winter	or	what makes this place recognisable
Picture	sunrise in Antarctica tomorrow morning	or	old blazes, in your mind, so you don't miss any
Interpret numbers, labels and words into reality	e.g. what the shape of the night-sky has to do with your global position		
Express visually	what each clue means	e.g.	what "high noon" means to you right now
Mentally photograph	the map as you study it beforehand	and	how the climb opened out onto the plateau
Mentally match	the invisible landscape trends to the reference direction and to what you see in front of your nose		

At night, and in the rain, navigation gets to be 'all in the mind'.

By recreating the reality you can't see, you can navigate what is in front of your toes, by intelligent imagination.

Big-Picture Orientation is a Mental Layout Acquired Beforehand

Because the invisible picture is so large, you can do your global and continental orientation at home before you start.
Travelling all day to go walking somewhere else, will hardly alter it.

You use: a globe; an atlas; a roadmap of the continent — to learn the lay beforehand. These are layout maps... The relative positions shown are fixed.
But layout views — as seen from above — will hardly ever be seen in your reality, first-hand.
(In contrast, when you come to putting yourself in the middle of the big-picture, you see the landscape first-hand, and you will need "Nose Navigation" — as seen from the ground — which is all about the apparent relative directions.)
The global constants won't change as you walk, e.g. the behaviour of the Sun and stars, because everything is so distant.

You need extra care to visualise the Big Picture, and its meaning, because it is (a) Round (global) (b) Layout (i.e. mental only) (c) Invisible (d) Big!
Do this before you attempt to nose your way through the local scenery.

Smaller-scale clues can then 'fit-in', sensibly, to the larger context.

Compass Navigation Robs You of a Global Perspective

Flat maps must distort the true picture. Only a globe is true. Mercator-projection maps (diagram 1) distort land areas and longitude lines, in order to "preserve the straightness" (!) of a compass course, which never was straight!
If you glue your nose to a compass needle, to follow a compass-course,
the course which looks straight on a flat Mercator map will actually take you on a spiral, into either the South or North Pole (as when you keep any landmark at a diagonal).
The sense of the spiral (turning to your right/left) changes as you cross the Equator...
Because you do need a big-picture approach, **you need a global perspective**.
(Here's a good place to set out the basics...
Remember: "Latitude **equates** to the distance from the Equator" — the short dimension.
"Longitude turns upon the time — how **long** has the globe turned since midnight")



Here's a test: Imagine the midsummer sunset from well Down Under, looking even further South. Do you think of a tropical country in that direction?
The following section — about Sun Moon Earth and Stars — aims to restore a true perspective to people who can hardly think except with a flat diagram, and can hardly visualise anything without divorcing it from the real landscape in front of their nose. (There is always a tropical country under the Sun.)
Think of this 'global orientation' section as a global **Re**-Orientation and don't forget, that... **Global means Round!**

The Big Picture is Invisible — Your Job is to Visualise It!

As a matter of principle, we should work top-down
i.e. from a framework down to the detail, from general to specific, large to small, overall to local, unchanging to changeable.
As a matter of fact, we are lazy. The point of doing "useless" grand-scale orientation exercises is to:
make global orientation second nature — easier next time around;
to make you forget flat pictures of a round Earth and to imagine it properly;
to give your struggling memory some comprehensive and relable framework to work within;
to integrate what you can't see with what you can, e.g. to link different walks and areas;
to orient to, and to understand, the Sun's movement, and to orient to the Moon and stars and planets as a bonus;
to make extra clues and techniques available, e.g. to open up astro-navigation techniques;
to work "top-down" — to avoid jumbling up your mind.

The idea is to read the following double-pages horizontally, as one topic, i.e. Sun-Sun; Stars-Stars; Clockwise-Anticlockwise.
To follow one topic through, flip over the pages and look in the corresponding positions.

Global Re-orientation — Light-Half/Dark-Half



Step 1. **Always Position Yourself on Top of the World.** ..whether in a diagram or mentally or in reality.
This makes your reorientation realistic, doesn't it?
Look at your feet and imagine you are standing on a huge basketball in the sunlight.
To visualise the light-half/dark-half of the globe, carry a real ball with you, preferably a globe of the world.
Imagine that everything which you see, this side of the horizon, is the tiny top-fraction of a huge ball.

Step 2. Face the Sun, but imagine it low down, setting, with horizontal rays coming to you.
Notice the circle which divides day from night, passing to left and to right underneath your feet.
"He divided light from darkness by a circle drawn on the face of the sea." Job 26:10

Step 3. 'Raise' the Sun, and its sunbeams, to their actual height.
And as you do, let the dark-half fall back behind you by the same amount
i.e. degree for degree around a round globe—one degree of fall-back for one degree of Sun-rising.

After this you can do your best to answer: (Help will follow soon) What countries are seeing the Sun as horizontal?
i.e. Which countries does the 'circle' pass through at the moment? Which ones are seeing the Sun rise?
Which ones see it setting? Which parts see a 24-hour sunset, with the Sun skimming the horizon? (Use a globe)

Your Best Reference Direction: Imagine the Sun at High Noon — Always

(This won't work so well in the tropics)

Night or day, your mental reference direction is North or South by the Sun. So imagine the Sun North of you (Southern Hemisphere) rain or shine.
It is the natural interpretation… of looking at your watch, and
of looking at the Sun, when it is not North of you. (Warning: Don't look directly at the Sun! It will blind you!)
of looking at the compass. (You don't want to locate 'Canada's magnetic pole', after all!)
of judging botanical North/South (p.74a);
of using a map in conjunction with the landscape,
and even when using the Moon

Imagine the *high-noon* Sun in a real landscape — this one here!
— at all times of day or night.
— at the correct height, on its circular path,
— which is tilted at its rise-set angle.
Warning:
You will get disoriented
when you cross the Equator!


set
rise
horizon
You
..North

Noon height (Southern Hemisphere)
i.e. your best guide to "North"

The 4 Bright Outer Stars of Orion Point out Where the Pot is Going

=Find N/S E/W & Equator


W
N
Hold this chart over your head
Rigel
Saiph
Equator
0630 hrs
Betelgeuse
6°N
Bellatrix
.:Meissa

Movement West
Anticlockwise around Polaris
The middle of Orion's belt will follow through the Arrow point.

The north-west star of the belt — 'Mintaka' — lies 'on the Equator' (i.e. over the real one)
The N-S position of a star is called its 'declination', equivalent to the latitude of a point on Earth closest to it.
This is a Southerner's view in Summer. The stars will be moving to your left
The Pot handle down through Meissa points to Polaris

Look for the Line Joining Sun, Moon, Planets & Zodiac Stars—the Ecliptic


2 planets are
always near the Sun
Venus (very bright white) *
Mercury (reddish)*
Sun
Asteroid
glow
THE
ECLIPTIC
Zodiacal Stars
Mars (Red)
*
O Moon
Jupiter (very bright white)
* * Saturn (Bright; yellowish)
The Earth is moving
through space, East-around the Sun,
away from this high point at sunset; (SH view is shown)
towards it, at sunrise. (e.g. if this is a NH view looking S)
N

The solar system — Sun and planets — is flat, and the Zodiac marks that plane, by design. It's **the 'edge-on' view, which we see, from within**.
The Moon orbits within 5° of that plane, and so is never far off line. **The line is called the Ecliptic** — a great circle.
(It looks as straight as the horizon, unlike the diagram. See 'Optical illusion' in the Moon box, p.8d)
During the day, you can orient, not by the Sun only or the Moon only, but by the line joining them. Sometimes Venus may be visible too.
You have to imagine the rotation of that line (more on this soon). It does not move in the same direction in which it points, but its path is up to 23°½ tilted from that.

Mnemonic: "Clock-wise Northern Hemisphere **SWiNES**"

top view



S to the noon Sun

Europeans make chronometers to follow their Sun.
They see, looking South (diagram top right)… rise in the East ; South at noon ; set in the West.
That's 'clockwise' (seen from above; East to South to West) for them
The swines! They force us, down under, to place our clocks on the southern wall and think behind us!
(We see, looking North: rise East, to North at noon, to West i.e. SH; anti-clockwise)……


NH
clockwise
East
West
South
W
N
E

clockwise top view



Anyway, changing your direction "Clockwise", as seen from above, is turning to your right, and, **i**gnoring the **i**, the mnemonic is:
South, to **W**est, to **N**orth, to **E**ast, to **S**outh or "clockwise: **SW**i**NES**"

Earth

A mnemonic for global orientation: **"True Polarity"**

"**True**" courses refer to the Earth's **Poles** — i.e. the axis of rotation of the Earth — **the single most directional thing on our spherical Earth**.
"True" bearings measure the angle between the course and the longitude line — a North/South line which connects the poles, and which passes through your location.





The angle is measured **clockwise from 'North'**
e.g. 065°T
"Oh Six Five degrees True (-polarity)"!

Remind yourself, whenever you use "True", by saying "True Polarity"!

Sun

Mnemonic: "**N**oon Sun Passes **N**orth of My **N**ose Down Under"— It Rhymes in ' **n** ' (dow-nun-der)
(Now, Keeping your **n**ose to **N**orth, say…) (The second parts work for both hemispheres provided you face North, not noon)
"Sun **Ri**ses on My **Ri**ght (to the right of North)" —It Rhymes in ' **ri** '
"Sun S**e**ts on My L**e**ft (in the W**e**st)" —It Rhymes in ' **e** '
"That's Anticlockwise around the North Pole Star, if you are facing North from the SH; [Clockwise around the South Pole Star", if facing S from NH]
"The **SH** ho**ri**zon **shi**fts to the **ri**ght"
"The **NH** ho**ri**zon **N**ever **H**eads **ri**ght, it moves left"

For Southerners, looking at the noon Sun i.e. from South of the tropics



West/Set/Left **North**/Nose/**Noon**/**Down Under** East/Rise/Right

Paper Diagrams aren't Enough.

Imagination isn't enough.

Go outside and take a look.
(You will need to shield your eyes from the Sun, e.g. with your hand)

Let the reality sink in.

Stars

The Two Brightest Stars Point out the **South** Pole Star

Canopus and Sirius line up almost South/North.
Use the star next to Sirius ('Mirzam') and the line-up is perfect.
The 'Dog Star' Sirius is the brightest star in the sky.
The Big Dog seems to have a front leg and back leg and a tail...



A**l**udra, in the tai**l**
Wezen, where he wees from
Ad**h**ara, the **h**ind leg
The Big Dog
Mirzam
This is the nearest bright star to Sirius



(Go another 37 degrees to South polestar)

A
GOOD
SOUTHERN
SUMMER
SIGN

Wind

Mnemonic: "Wind? Weather Map!"

For navigating by the wind, don't just leave it at the level of "The wind is from over there".

* Look at the skyline "from Bruce Valley"
* Look at the Sunshine "from 30° to the left of the Sun at the moment" (Don't look at the Sun!)
* Look at the Sun-path "a 'sunset' breeze" i.e. from sunset (Simply imagine its rise-set path.)
* Imagine the continent beyond the skyline "from the West Coast"
* Meld that reality to the weather map you remembered.

Don't stop interpreting the wind until you can fit it into a Big Invisible Picture connected to that skyline over there.

Anticlockwise

Mnemonic: Down Under, The Sun Moves **ANTI**-BigB**ENWiSE** **i.e. anti-clockwise**

Look at the 'ENWiSE' in the mnemonic.
Anticlockwise is **E**ast to **N**orth to **W**est to **S**outh to **E**ast.
Ignore the **i**. Look down from above onto the horizontal directions involved…
Anticlockwise is turning to your left. " Anti-clockwise is ENWISE "



(If you put a clockface on the north wall and look at the Sun's movement, (Don't look at the Sun!), you will see that the Southern Hemisphere's second-hands tick backwards! i.e. against the Sun's movement. So put it on the south wall facing North, and the clock hands will move 'with' the Sun.)



top view

In the tropics, the Sun will pass somewhere near overhead. To make it seem "anti-clockwise" anyway, face North.

Don't get mixed up and think of Big Ben wise as clockwise. Down here our Sun moves anti- , and that is ENWiSE.

Mnemonic: "Time Tells Turning"

What's the use of looking at your watch and spouting numbers! At least, glance at the Sun, or rather at its shadows (don't look directly at the Sun) and then, imagine the Sun's direction at high noon as a reference direction.

That's what time tells you! — the Sun's position relative to its noon direction, North/South, called the "meridian".
A.m. says "ante meridiem" i.e. "before noon", and p.m. says "post meri-diem" i.e. "after mid-day"
Midday = 12 noon (but only in an ideal world, because noon is only approximately at 12)
One pm = one hour past 12md, and so on.
24-hour time tells you how far around the Earth has turned, since the Sun was opposite you i.e. since midnight.
(And then don't forget that the local significance of the time is: progress — distance made good — "watch" your pace)
Mnemonic:

"Watch" the Sun (without looking at it) whenever you watch your watch (and "watch" your steps too, for progress)

Notice these, Yesterday — to Guess the Time Today

- Sunrise time (and direction) ..If you know the time, you can guess at the directions.
- Sunset time (and direction) ..These first 2 are symmetric around North.
- The horizontal angle of separation between sunrise and set
- Midday time (and direction, and height) ..This is halfway between. Memorise how short your shadow is.
- When did it get light enough? To see. To walk.
- When did it get too dark? To cook. To walk.
- How long is the usable daylight? ..The day-length, between dawn and dusk.
- How many hours of dark?
- When did the Sun reach due East and due West? (How high?) ..This won't happen in winter. They are symmetric around midday.
- Times for the Sun at magnetic East, noon, West? ..These don't depend on guessing or calculating the magnetic variation.

Update yourself every week.

The Spinning Earth Makes **Circular Paths** for the Sun, Moon, Etc.



Sun, Moon, stars, planets — they all move only slightly in relation to each other during 1 day/night — but they all zoom around at about 15° per hour from East to West.

Although I can draw this on flat paper as a circular path, the Equatorial path actually looks as straight as the horizon, in reality! (Southern Hemisphere view)

You can now guess at time or direction by your familiarity with the circular 'orbits' e.g...
The highest point of the path will be North-South of you, if you can guesstimate it
Latitude determines the rise/set angle of the Equatorial path.
Rising and setting places are symmetrical around North.



Although individual rising and setting is symmetrical about North, whole constellations that rise vertically in mid-latitude may set horizontally! and vice versa e.g. The Big Dog or Scorpio rise flat but dive vertically into the western horizon.



The Moon; Rule 4: Look for It

You have a 1 in 4 chance of finding it during the day. Provided you remember to look!

Rules 1 and 2 (like so many other navigational clues) are...

- PREDICT when and where it should be visible
- GUESS where to look And Rule 3 goes with the guess:
- LEARN from that mistake.

Keep looking for it. It's easy to miss. E.g. through the tree canopy; or rising through the horizon haze. Polaroid glasses help; you need to twist them

You will then have clues to…
North, East, and West
Time of night (i.e. later)
Ocean tides
Tomorrow's Moon — Phase; rise, set, direction, height
Upper-level winds, if there are clouds about.

Hint: Measure the Sun-Moon separation with a piece of string (Don't look directly or indirectly at the Sun!) so you know exactly where to look later.

"VEERING" with the Sun is "Clockwise" only in the Northern Hemisphere "BACKING", against the Sun's movement, is "Anticlockwise" — but only in the Northern Hemisphere.

(The terms refer to horizontal directions changing either with or against the Sun's movement)
"Veering and Backing" are Eurocentric images, so they can be very confusing Down Under. Don't use those words in the Southern Hemisphere!

Say "Clockwise" and "Anticlockwise" instead
..for both hemispheres, as a matter of habit. Although these meanings too are Eurocentric, they are not confusing!
(the terms refer to a bird's-eye view looking down from above as if onto a clock-face)
Meteorologists and mariners still use the terms 'veering' and 'backing' and they do mean 'clockwise' and 'anticlockwise'
But the Sun-based image is backwards, south of the tropics.

The sky turns **15° per hour** — Use your **thumb and forefinger**

Earth



The Earth rotates once a day. Yes? That's 360° in 24 hours, yes?
Well that works out at 15° per hour — the sky spins 15°/hour to the West.
That calls for **recognising 15°** E.g. (diagrams left, and right) "one hour of sunlight left" (SH)

For Accuracy:
(0) Measure each handspan along the Sun's 'circular' path, not horizontally.
(1) Use constant stretch — of arms and fingers — 'just strained' — for consistency.
(2) Use constant chest-arm geometry. It is best to use two hands squarely in front of you…
(3)**Test for 15°, horizontally,** against the full 360° horizon — **"24 spans go around the rim"**
Span off, 24 times, from point-to-point right around the horizon.
Adjust your hand configuration until you find one that fits the "24 Hours" recipe.
(4) Try gripping one hand with the other, or touching one, at a specified point, with the other
, or, (5) Look along your shoulder, sideways, at one hand.



My recipe for accuracy fits my arms:"4 spread fingers, wrist bent back fully (at arm's length in front=60cm or 1cm/degree")
What do your arms require for 24 spans = 360°?



Mnemonic: The Southern Summer Sun Sets Somewhat South

Sun

Surprising perhaps. (If you equate North with 'hot' you get caught on this.) (for Northern Hemisphere substitute 'North' for 'South')
When the Sun comes South for summer its sunrise and sunset places also shift South with it.
Memory hexagon for Mid-Winter and Mid-Summer Down-Under at 37° S…
(top view) N. (the Sun moves anti-clockwise through North)



300° T. 60° T. … In Mid-Winter, Down-Under, at 37°S., sunrise is at 60°T. and sunset is at 300°T. … A 9½ hour day.
In Winter the Sun will never show East or West of you.

W At Equinoxes — Mid-Autumn, and Mid-Spring — rise and set are East and West… a 12 hour day.

240° T. 120° T. … In Mid-Summer, Down-Under, at 37°S., sunrise is at 120°T., and sunset is at 240°T. … A 14½ hour day.
The Sun will be East and West at **mid**-morning and **mid**-afternoon respectively, and **mid**-high — about 45°.
180° T. **Your main aim is to get familiar with the Sun's circular path**.

Stars Leave Star-Trails ..if you photograph them with time-exposure...

Stars



Star-trails are bits of circles, because… ..stars circle around the North and South Pole-Stars...
i.e. the Earth rotates on an N-S axis, which points to the Pole-stars. The pole star stays fixed in position all night (if you do).
Southern Stars Circle Clockwise, once per night-and-day, around the South Pole Star.
Northern Stars Circle Anticlockwise, around the North pole star, Polaris. These clock senses are the same in both hemispheres.
But **Note**: low Southern stars will move anti-clockwise around you, (i.e. to your left around the horizon, anti-clockwise as seen from above you). (Clockwise — to your right in the NH) (More on this later)

It helps you with global orientation to use 'star compasses'.



One of the clearest compasses is to blur the star circles into full circles then take vertical tangents to those circles.
In the following diagram, the left-hand direction is "30°" to the left of the Earth's axis (or to 60° maximum latitude).
The right-hand one is "20°" to the right (or to 80° maximum latitude). They are global.
If you follow these star directions, they will take you right around the earth in a 'straight' line — a big circle.
You will pass through places equal in latitude to the star which is overhead (p.11c), so you can already *see* the maximum latitude that such a 'great circle course' would take you to; then it takes you back towards the equator.
HINT: You won't get far in star-navigation, without a detailed star list and star chart. See p. 123 for a list.

Mnemonic: "Wind in Your Face"

Wind

The Southern Hemisphere version of Buys Ballot's Law… [Try to use unobstructed wind i.e. not in a valley nor in a mountain eddy]

- "**Face** the Wind [N.H. rule uses 'Back to the wind, Sun-twist…]
- Sun-twist yourself 15°-30° [i.e. anti-clockwise in S. H.]
  — to counteract landscape friction on the surface winds.
  [When the winds are impeded, they slow down, and so stop circling around the pressure centres, and start to cross the isobars, toward the low pressure (a 'sink' hole) at an angle of 15°-30°, less at sea and over flat land; more over rough terrain.]
- Rhyme: **"Low on My Left** &/or **High on My Righ-t"**



S.H.



Top view of you, in the square, facing the top of the page.

Southerners Need **Anti**clockwise Systems

Anticlockwise

Our clocks seem to run backwards, compared to the Sun.
Our compass-bearings are measured 'backwards'. (see p.10e)
'Veering' and 'Backing' seem to mean the wrong clock-sense.
When the Sun moves forwards, all the other systems seem to push backwards.
We lose the global perspective.
And this section is all about aiming to put that right.
Consequently, we need a Southerner's viewpoint…

I hope you find that the anticlockwise systems which will follow soon are much more workable than Eurocentric systems.
Some of the other systems given on this right-hand side of the page, are universal — they can be used in either hemisphere.

Global Orientation: Latitude and Polar Distance



Step 1. Stand up on the globe again (in your mind and in reality).
Step 2. Put your left shoulder to the Equator i.e. Face East (sunrise).
(If you are in the northern hemisphere: face west, sunset.)
Step 3. Mnemonic: EQUATOR on My Left equals My LATITUDE is on My LEFT,
RISEN POLE on My RIGHT equals My POLAR DISTANCE is on My RIGHT.

Since the South Pole is 90° latitude, it is further South from the Equator than you are, and will be on your Right, as you face East.
Step 4. Measure the degrees of distance around the Earth's circumference as an angle at the centre of the Earth (by slicing the globe in two).
The two angles mentioned must add up to 90° i.e. they are "complementary" angles (spelt with an 'e').
If you are, say, 45° south of the Equator, then the closest pole must be 45° further south. The 'distance' to the Pole is 45°.
If you are 30° south, then the South Pole will be 60° away from you. Your '**colatitude'**—or *90° minus latitude*—or "Polar Distance"—is 60°.
The goal is to imagine those two angles — Latitude and Polar Distance — at the Globe's centre beneath your feet, and around the circumference.

Mnemonic: "Sun at High Noon — How High?"

When you navigate by the Sun, think: "Sun": the mnemonic is: "Sun at high noon — how high?".
You look: North, there, then up there, that high.— Southern Hemisphere (cf Noon will be South in NH) (Don't look at the Sun, if it is already there!)
It might be morning : "It is going up there"
It might be noon : "See how high it gets!"
It might be afternoon: "It came from up there"
Visualising the height and path of the Sun also helps you to interpret plants for 'bush noon' (p.74a).
"Walking Stick North" depends on knowing the Sun's maximum height. (See page 30b)

On Overcast Days, Average the Brightest Sky over 1/4 hour

If the clouds are moving fast enough, and not entirely uniform, sit still for long enough to see many clouds pass over. Keep pointing at the brightest patch of sky using some reference like a tree, and watch to see whether you can confidently locate the average position of brightness.

RISE and SET Directions for a (**Local**) STAR COMPASS



The star directions don't change night by night or with longitude, but they do change with latitude.

The circles in the diagram will rise from the horizon as you travel further south, and so change their intersections with the horizon.

This star rises here every night for the seasons when it is visible

You need to know your stars and visualise their circular paths

Stars which share the same star path indicate the same direction at staggered times during the night

Sun-set and Moon-set (examples only) can be fitted in to the scheme to span the day

Just make sure to mark sunset to a landmark on the skyline horizon and carry it over into night-time.

(SH view)

(Some stars stay up all night every night; these don't move far either, and so are good orientation value too)

From the Moon, Locate the Sun-Moon Direct Line, Carefully.



The line is the Approximate Ecliptic, and being a great-circle is a straight line.
OPTICAL ILLUSION!
The Moon seems to be lit from above the 'direct' line to the Sun.
But that may only prove that the Sun is "up" and shining down.



Bust the illusion with a piece of string…
Caution: Don't look directly at the Sun!





Prove it in 3 dimensions, by using a torch and a ball.
When the ball, in line with the Moon, looks right, the torch direction mimics actual sunlight.
Below horizontal = at night

By locating the Sun, you can guess the time of night, and guesstimate North more reliably, because the path of the Sun is more predictable and familiar than that of the Moon.

Mnemonic: (when you say) "COMPASS" (say) "CANADA"



Compass needles point to Northern Canada. That's where the North Magnetic Pole lives. Lat. 75° N.; long. 100° E.
E.g. from Australia, Canada lies to the East of North…

Check it out on a globe. Locate the Queen Elizabeth Islands.

To find the Southern Magnetic Pole, (but this doesn't work so well)
locate the Antarctic coast south of Adelaide, at Lat. 65° S.; long. 140° E.

The Angle of Rising and Setting — is Determined by Your Latitude

To post-dict sunrise or pre-dict sunset direction, you can use your latitude to visualise the tilt at which the Sun **rises** (or the rise-angle of a near-Equatorial Star/Moon/planet) and the deviation from straight down, at which it **sets**.
Remember to use vertical, not horizontal as the expected norm. (To judge vertical correctly, see p19c. To practise, see 30b)



This one is especially useful in Tasmania.

The Sun's path is very nearly a straight line, despite the illusion of being circular—see p.15a.
Hint: Whenever you see the shadow of your head, provided the Sun is not too high, you can make the "anti-Sun" rise or set positions obvious, by following up from that shadow, to the horizon at the correct angle. In midwinter the anti-Sun will be in a midsummer position and vice-versa.

High Noon — How High?


LAT
PD
S.P. and two parallel rays
Latitude angle…
Polar distance angle = elevation of the average Sun

Answer one: the same as last week. Take a look. It changes only slowly.
Answer two: **within 23½ degrees of your co-latitude (or 'polar distance') high**
i.e. 90° – Lat., plus or minus 23½ degrees, depending on the season.
Mid-Summer… co-lat+23.5° (very high in the sky)
Mid-Winter… co-lat–23.5° (very low in the sky)
Equinoxes… co-lat (average height).
Why? At 0° Latitude, i.e. at the Equator, the average Sun is 90° high at noon i.e. overhead. Yes?
At the Poles, 90° Lat., the Sun skims the horizon at equinoxes. Yes?
If you need further proof (that its height is 90° minus Lat.) draw it.

See how the height of the average Sun is 'latitude degrees below vertical'.
That's an angle of elevation of 90° minus lat, isn't it? Now adjust for the Sun's seasonal movement which is 23½ degrees each side of that.

Global Star-Compasses e.g. 'Perpendicular to' rise and set

This is one step harder and three steps better. It allows 'great-circle' course keeping.
A global Star-compass yields 'direct', global, 'straightest path' courses — ones which take you around the globe and back to your starting point.
E.g. You take a rise or set compass-point and head at right angles to it, and the new horizontal direction is global—no longer tied to one latitude.
That's easier to imagine by visualising the light half/dark half of the Earth: All who see the Sun on the horizon could point to it, but each would be pointing in a different "direction". But if they all pointed horizontally at right angles to the Sun, they would all be pointing in truly the same way —around the Great Circle which divides day from night. The same goes for any horizontal star. Imagine the star as a pole star, and use its "equator"
There are many alternative star appearances, besides rise or set & **you don't have to 'go at right angles to' these to set your course...**

E.g. aim at **one star above another**
The midpoint of One star **level with another**
One star **rising or falling vertically**.



Toward a star which has a 2nd star off to one side **at right angles** i.e. lower. You would pass *under* the point you kept aiming for.
You don't need a clear sea horizon — the stars are high, and a plumb-line will suffice.
These guides occur every night, in the same global direction, for several seasons, then disappear for a while due to daylight, but reappear.
They will occur at the same times next year. **They are always worth learning more of**, adding to your familiarity of favourite 'Star directions'.
These global directions are labelled by saying *how close to the poles* they would take you, and you can see or guess that from the stars, see p. 7c.

'Low' Clouds Come Clockwise Down Under

In the Southern Hemisphere

- Low-**pressure-system winds** spiral **clockwise** around. I.e. into your face from your left as you face their winds...
- 'Low **clouds**' (i.e. below freezing level) follow the surface level isobars i.e. the weather-map lines.



The double-meaning for ' Low ' in the mnemonic reminds you of this.
'Lows' cause more clouds than 'Highs', so you focus on 'Lows'.
I.e. when you see the low clouds; you say 'low clouds come clockwise' and automatically imagine………… '**L**ow On My **L**eft' Plus 'H**igh** On My R**igh**t'
The Alternative Southern Hemisphere version of Buys Ballot's law. This **new version goes like this** :
Face the low clouds (unaffected by friction—winds at 600m high are considered unimpeded),
then rhyme: L— L ;igh—igh. (Don't Suntwist yourself.)



[Cf "Face the wind, (In the northern hemisphere you have to say "back to the wind")
Sun-twist yourself up to about 30° to counteract friction (which makes the surface winds spiral inward to the low centre)]
Surface winds could also be expected to be half the speed of unimpeded winds, less impediment over sea, more over land—about one third.



A Compass-Needle Continent—Swinging the Continent

Mentally glue a miniature continent under the compass needle, to swing with it.

The idea is twofold:
1. To reprogram your mind — "The continent is not swinging, so... **I** must be!"
2. To orient yourself meaningfully — to the invisible picture
3. To remind yourself of compass variation

When using a compass you could: just stare at the compass-needle, like a lone night sailor in a fog.
Or: look at what the compass is pointing to — that bump!
Even better: also 'see' the needle lying across the whole continent
Keep going: pointing to Northern Canada
Don't forget: the map you are using — the real one, not this imaginary one — should also line up properly — twist it around until it does.

Global Orientation: Point to the South Pole… ..half its polar distance below horizontal



If you had to point "South" you need to point horizontally.
But when you have to point out "the South Pole", you must point below horizontal.
(It is similar when Northerners use the North Pole)
Imagine the true scale… you are on the circumference, not above it...

The question is: "What is the exact angle below horizontal?"
The answer is : "The South Pole is **HALF its polar distance** below South."
Example: at 45° S., you point 22½ degrees below the horizon. (90-45) /2
Example: latitude 30°; colatitude = 90–30 = 60°; half that equals 30°
Example: latitude 60°; polar distance 30°; 15° below horizontal.





Optical Illusion — Beware! — Use Your Shadow Not the Sun, For Direction



When the Sun is directly behind you, it seems to be behind on the left when you look over your left shoulder, and behind on the right when you look over your right shoulder! And when the Sun is exactly to the side, it nonetheless seems to be ahead of you. (Every sports coach knows that when you turn your head, your body follows it.) Don't rely on where the Sun seems to be… USE A SHADOW INSTEAD! It is also easier on your eyes.

And then don't get fooled by the shadow of your finger, when you throw a shadow onto your map to find the Sun's direction. It may look straight but it doesn't point to the Sun, until you line it up with your finger**tip** while looking from directly above. The shadows will always be parallel, but the Sun's rays will always join object to image, fingertip to fingertip-shadow… The first diagram is illuminated from behind you……
To avoid looking at the Sun, try this:
Point your walking stick from somewhere beneath your eyes, outwards, and rotate yourself until it is in line over its own shadow.



Right Around the Horizon, Stars Move to Your **Left**, Down South

Looking South, all the lower stars move left.

It is only the high Southern stars which move to your right.

Looking East all the stars rise to the left
(i.e. we see the bottom half of the circles
down at horizon level, looking South)

Looking West all the stars set to the left



Looking North, all the stars move left.
(we see the top of the circles)

The same goes for Sun, Moon, Planets.



Looking directly overhead, or behind your head, will not work!

(it is all opposite in the northern hemisphere)

Mentally Rotate the Sun-Moon Line Around Polaris

A whole line through the sky gives a better 'feel' for direction than a single point — than either the Sun or the Moon alone —
So join the two and watch them rotate together during the rest of the day.





(Southern Hemisphere view)

When you can see both, and you know where North is, you watch them.
When you see only the one, you look for the other, and so find north more exactly than by using either one's path by itself.
Add in any planets to continue the process at night, then from planet to planet or to Zodiac stars, after moonset.

"Bears Circle Clockwise"

Compass Bearings are **C**lockwise, A Full **C**ircle, and Euro**c**entric, **C**ee?

In Europe the Sun moves clockwise… from North (Where the Sun is at midnight—0 hours) = 0° as far as the horizontal angle involved is concerned.



Looking S. / from above

East is at about 06 hours (sunrise) or 90° True — Sun-wise or Clock-wise from North
South at about 12 hours or 180° T (noon)
West at about 18 hours or 270° T (sunset) — so you see, the bearings circle clockwise, from North, 360°.

A **Southerner**, of course, would prefer to go 360° **anti**-clockwise, from **South**, but they didn't get a vote.
Everyone in the world is expected to submit to the (NH) rule: compass bearings should be measured in degrees, up to 360°, from North, clockwise around through East — like the ancient Babylonians; like the Northern temperate Sun.
Not many people consider using 400 grads (4 right-angles of 100 grads make up the circle), or consider going left-around, through West,
Or even think of starting at South. So don't you dare (unless you **don't** call it "a compass bearing").



The North Pole is *Perpendicular to the South Pole*

Since the poles are 180° apart — opposite — you see them as 90° apart — half the arc distance.
The numbers can't work out any differently.

Example: 10° S. Lat. = Equator is 10° North of you. South Pole is 80° away — the "Polar Distance".
So S.P. = 40° below S.
North Pole is another 90° past the Equator.
So N.P. = (90 + 10)/2 = 50° below N. And the gap is 90°.

A simple way of looking at it is to say
"Diameters yield right-angles at the circumference"

Now go outside and point to the Poles.

The Dark-Blue Polarisation Band Perpendicular to the Sun

90° from the Sun there is a circle of darker sky. Bees navigate by this clue. The whole sky shows degrees of polarisation.
You can see it naked-eye, but since it is due to polarisation, it is much clearer through Polaroid sunglasses or a camera filter.
Point the top of your polaroid sunglasses toward the Sun for best effect.
The dark blue band is narrowest highest up (in the direction of your shadow, and perpendicular to that sunbeam) and varies with visibility and haze.
The sky is darkest away from the Sun and away from the horizon haze and 90° from the Sun.
You can always guess where the Sun is, from the gradations of blue. After sunset the band is caused by the brightest part of sky.
Example: You are in a forest at dusk. The sky is blue overhead, but the sunset direction is not visible. Find the Sun from the blue!
See the "Sunny Skies System" (p.19e) for how to use the ends of the dark blue band, and its trend.

The Centre of the Rainbow is Down-Sun

The shadow of your head coincides with the centre of the rainbow's circle. (Pilots often see the full circle of a rainbow)
The radius of this circle is two wide hand-spans — spread out your 10 fingers fully, thumbs touching.
Whenever you see a rainbow, treat it as a clue to 'shadow-South' (p.14b) i.e. relate its position to the time of day and to South.
The shadow of your head is on the end of the shadow of you, of course, but when you can't see it due to clouds, you might be able to see a rainbow.

Identify the Stars That Pass Directly Overhead

Each star has its own latitude, called "declination", which is very nearly constant.
So the same series of stars of the same latitude will pass overhead that latitude, each night, each in turn, each at some fixed star-time.
This is true anywhere on the globe.
Use a plumb-line. The top of the plumb-line points 'up' to overhead (when looked at from any side, so) where the 'up' lines cross is 'overhead'.
Look past it from 2 or 3 directions to find overhead, especially looking North/South for longitude-timing, and East/West for latitude-positioning.
Then use a star-chart to identify "exactly overhead", latitude-wise, at least. If you can do this, even without a watch, this will fix your **latitude**.
Plus or minus a few kilometres is the expected maximum accuracy from using a plumb-line.
For **longitude**, you need to determine the star-time at which one of these stars is overhead, or at least passing from East of you to West of you.
Greenwich (absolute) star-time, not Local (relative) star-time, that is. To the nearest 20 seconds is okay. See p30c. A 4 min error is 1° error in long.
Alternatively, set your reference star-time to some other longitude, e.g. home, or start, or destination, or a round number.
This time & position data is life-long, give or take a few kilometres of predictable precessional drift per decade.

You can get back to that place later — Match the appearance and timing. It's easy to tell which way to move in order to "match up" (p22a,c; 23c).
You need to know a star's longitude, so you need an almanac or list. Look down the list for bright stars with your latitude, and go look for them.
You will quickly learn about having to wait for the right 'star-time'!

Weather Fronts Distort The (Circular) Wind Circulation

Buys Ballot's law is only approximate, because of the sudden wind-shift at a cold front.
Cols, Ridges and Troughs are likewise noncircular. E.g. 'centres' will sometimes split into two…









In the trough, crossing the ridge, the winds are turning right.
This airstream is turning left (SH) around the High centre.

You can't accurately say that these winds are 'circulating' around the Low or High! But you can say that in right-turning winds the clouds are forming, under the influence of a Low or a trough (SH), and left-turning winds are under the influence of a High or a ridge—the clouds are dissipating. Swap left and right in NH.

Mnemonic: (Interpret a Compass Needle as) "RED HOT — WHITE FROST"



Southerners are looking North to the "red, hot, tropics, dripping with sweat, in the Sun"…

When southerners look South, it is to the "white, icy, Antarctica, frosty cold, in the shadow"…

So when you notice the red point of the compass needle you say to yourself "red-hot!"
and try to feel boiled on that side (as if by a bon-fire), and then visualise the invisible tropics North of you.
And when you notice the white point (e.g. during a back-bearing) you say to yourself "white-icy cold-frosty-Antarctica"
And then try to feel frozen on your 'Shadow-South side', and imagine the South Pole, e.g. point (down) to it.

You can also remember that the Canadian flag is red (but it is not hot in Canada).

Global Orientation: the South Pole Star, and Polaris

(In the Southern Hemisphere…)

Polaris is below the northern horizon, by exactly as much as your South latitude.
E.g. at 45°S. lat. Polaris is below North by 45° Around it the northern stars circle anticlockwise……

The equivalent "South Pole Star" (a dim pinprick in the midst of dim pinpricks) is **above the southern horizon by exactly as much as your South latitude**. E.g. 30° S. = 30° above South
Around it the Southern stars circle clockwise, once per day-night.
Locating the South Pole Star, helps you in the following...

- You can use the bright stars — Cross, Pointers, Achernar — as hour-hands on a 24-hour clockface.
- Star-paths Circle around the Pole Stars
- So do the horizon, the Sun, the Moon and the planets — You can predict all their positions.

Finding the Pole Stars is Fundamental to Visualising Rotation.



- Your Shadow Rotates with the **same clock-sense** as the Sun — not surprisingly!
- Shadow-Rise and Shadow-Set is **opposite direction** to the Sun — not surprisingly! } Together they can surprise you!
- Mnemonic: (Face the opposite direction as for the Sun mnemonic p.5b)

Face **Sh**adowy **S**outh for **S**outhern **H**emisphere (Face Su**nn**y South for **N**ortherners)

"Shadow **Ri**se is on the **Ri**ght; S**e**t is on the L**e**ft" (Same rhyme as for sunrise and sunset, but facing South, both hemispheres)
Your Shadow Passes **South** of Southerners At Southern Noon (compare: 'The Sun is North of Your Nose at Noon')
(North of Northerners at Noon)
Your Shadow Moves **Anti**clockwise — around to Your **Left** — Down Under
(Clockwise — Around to Your Right — in N. H.)
(The Southern Hemisphere Horizon still shifts to the right, in real terms. The Northern Hemisphere Horizon still Never Heads Right')

In addition, notice: **The shadow *tip* moves due East, at around noon,** and in a much straighter line than you expect, all during the day, as the shadow itself changes, from pointing to opposite sunrise, then to pointing to South of the object, then to lying opposite sunset.

---

15 Ways to Locate the **South** Pole Star Or the N./S. Meridian

1. Halfway between Achernar and Epsilon Centauri (located from the six bright stars near it)
2. Rigil Kentaurus to S., at right angles to Hadar…………
3. Beta Crucis to S., parallel to gamma-to-alpha Crucis, 5 Cross lengths … Use 2. and 3. together
4. Beta Hydri to alpha Crucis, as far as the beta-to-gamma-Hydri length … most accurate
5. Mirzam through Canopus
6. Suhail through the top half of the False Cross through Miaplacidus
7. Make a triangle out of the two Magellanic clouds toward R. K. — very crude but useful
8. Gamma Hydri to beta Triangulum Australe — the "back" star of the Triangle
9. Alpha Hydri to Hadar
10. Arcturus to between the two 'Pointers' (R. K. & Hadar) } These are used in reverse
11. Spica to between the Cross and Pointers } — to locate Arcturus
12. Middle of Corvus through middle of Cross } Spica and Corvus
13. Atria to the star between Canopus and Achernar, alpha Dorado
14. Peacock to Avior
15. 'Your Latitude' degrees above horizontal, due South



("Crucis" says "of the Crux" i.e. of the Cross)
(gamma looks a bit like a thin alpha twisted 90°)

"Cusp North" — Approximate Direction from the Moon

The Sun-Moon line marks the approximate Ecliptic.
The "centre" of that circle of Sun-planets-asteroids is located in "Draco", quite near "Polaris", the North Pole Star. For a start, ignore the difference…

- Join the Cusps, tip to tip
- Drop the line diagonally
- Keep going down to (near) Polaris (latitude degrees below horizontal)
- Come vertically back up to "Moon North" (in the worst-case +/-60° "accuracy"!)



You have to do this only once or twice a day. Compare it with True North and automatically adjust it for the rest of the day. (NH is similar)

Mariner's "Compass Points" work on Successive Halvings





Start with the nearest major point; add 'by'
'by' means 'come 11 1/4° towards' (or 'one point')
There are 32 points altogether on the compass.
One Point is approximately One Palm wide
(32 around the horizon—test it)

Make your own emergency protractor (e.g. as a compass, sextant or plotter) by folding any piece of paper, and folding it again and again, matching line to line so as to exactly halve it with every fold.
One more halving and you get 64 divisions, each of "100 mils" (so named and used because **1mil is approximately 1 in 1000 e.g. 1 m in 1 km**) i.e. 6400 mils around, clockwise, 17.7778 mils per degree.

Pole Star Locations — “(Latitude)° above and below, South and North”

Earth

Why? Think: at 0° Lat., they are 0° high. Yes? At 90° Lat., they are 90° above and below horizontal. Yes?
If you need further proof: Draw a Diagram of two parallel rays to South Pole Star...



The elevation of South Pole Star above the horizontal
= the latitude = the arc-distance of Equator to you...
(the angle, adding up to 90° with the PD, must occur twice in the 180°)

The Sun Passes Quickly Past North-South Nearer the Tropics

Sun

This pattern shows
the hourly change
in Sun or shadow direction
at 30° latitude, Mid-Summer...

The Sun is East/West
at (noon −/+ 2 hrs 44½ m.)
at 52.9° high.

This shows the
seven hours’ sunlight
(one side of North/South).



Don’t get caught misjudging the Sun’s horizontal direction near midday.
When it is high, it moves more than 15° per hour in horizontal direction.

At other latitudes the pattern will be different — more uniform
away from the Equator, and with a different day-length,
depending upon the season.
I.e. You need to calculate each particular pattern from the
Latitude and declination and season (as if calibrating a vertical stick sundial).


South Pole
Star Chart

Wind-Direction-Change Rule for Buys Ballot’s Law

Wind

If “the Low is on Your Left Or the High is on Your Right”...**and** the wind is gradually **changing**: Add in this new information as follows...

Imagine how the Low and High are moving across the ocean/continent as you **reenact the wind change**...
Exaggerate the change as you *twist yourself to follow the speeded-up movement* of the wind change in your face.
Point to the two choices (left & right) while you twist, then ask yourself which of your hands is moving to the east.
Usually only one of the two options above — ‘Low’ or ‘High’ — will make sense of the general movement of the weather systems to the East.

Temperate systems usually do move to the East from the West. (Both Hemispheres)
..From 0 knots (stationary highs) to 15 (average) up to 25 knots (Lows in winter).
Tropical cyclonic hurricanes move Westerly initially at 25-40 knots, then recurve to the pole, but the “re-enact” rule still works to show up its movement.
In this way you can decide: “These winds are from a Low” or “from a High”.
Don’t, of course, confuse local winds, e.g. a sea breeze, with the more general ‘synoptic’ circulation due to the large-scale pressure systems.
To further help you decide where the wind has travelled from —from your right or from your left— check out the temperature and absolute humidity — i.e. the air-mass characteristics. Is the air hot and dry, or cool and moist, or warm and humid — which one is supported by the geography?

Four Reference Directions — Name Them: “**Rise, Noon, Set, Midnight**”

AntiClockwise

..not E N W S

The trouble with “North” is that it is sometimes behind you... then you have to think backwards.
Use all four and you always have one in front of you... N., S., E., W.
Give them meaningful names as in the title... and you can picture the meaning.
Base it on the Sun’s daily movement and the effect is vivid.
To flesh out the meaning even more, **add in a second clue: “Rise/Start; Noon/Hottest; Set/End; Midnight/Coldest”**.

What this does is to take the outside picture inside with you, when you enter a new building, a hospital complex, a shopping centre.
E.g. “I’m now looking toward the mid-morning Sun direction, i.e. ‘after rise’ or ‘before noon’, which is ‘warming up’ ”.

It is then up to you to
1) get to know the Sun’s daily movement.
2) locate the Sun’s path outside, once.
3) *keep track* of your twists and turns when the Sun is not visible e.g. at night.

Ignore the time of day or night—it is the directions which you are imagining. You use the real Sun only as a start-up hint.

Point to 2 Places on the Equator — Halfway between the Poles

You can find the 2 Poles, apparently 90° apart, so that means you can point 45° — halfway — between the Poles, to find the Equator, then 90° to that for the opposite Equator (the "45°" is because the Equator is 90° from each Pole and we halve that arc).
It locates (1) the furthest point on the Equator from you e.g. Brazil then...
(2) the nearest point on the Equator from you e.g. New Guinea—ish.

From central Australia…



Farthest Equator. Notice that it lies to your South! (Brazil)

Shortest Shadow South — Opposite Highest Noon. Always Imagine "Shadow-Noon" on your "Shadow South" Side

i.e. Your shortest shadow is South of you at noon. Memorise how short it is (this week). S For the northern hemisphere use "North"
("shadowy-North")
(Shadow Noon is Opposite Direction to "Noon-North") .."Noon-South"
Imagine your shadow moving left around… ..right-around



In the morning: South must be "ahead" of my shadow ..North
At midday : Look — see how short it is! … **Due South at noon** **..North**
After noon : My shadow has "passed" South ..North

To guess North from your own shadow, see "Walking stick North". (p.30b)
Try to feel the icy South, freezing that side of you! ..North
(As on a cold night facing away from a campfire).
Mentally **visualise**: Antarctica below horizontal; an aurora above that horizon; Southern stars behind that blue sky. ..Arctic; Aurora Borealis
In the tropics, you'll have to be more observant, to know your shadow's expected movements more accurately. ..Northern stars

---

Find the Polar Axis by Star-Trail Bisection

You need to imagine the centre of the star-circle.
A Hypothetical Example: Lost in a stormy night! You want to find North-South.
You catch the occasional glimpses of unknown stars.

Lie down and line up one such star with a tree branch.
Maintain your exact position and wait for another glimpse.
It may only need a couple of minutes to see its direction of movement.
You can also point something straight at the star and fix it in place, to see the star's movement.
Bisect the result. It points to Polaris, or to the South Pole Star.
You now need to know your latitude, roughly, to locate Polaris or South Pole Star.
The higher the star the clearer the result — it will be moving West.
The only ambiguity is a low star moving horizontally (to your left).
The Southern stars will be moving slowly; northern ones, quickly
— so you may be able to guess which is which.
Northern Hemisphere is similar — but Polaris is visible.



South Pole Star (latitude above horizontal)
(This star is moving to your left
Anti clockwise around Polaris... ..Clockwise around South Pole Star)
Polaris
(latitude below horizontal)
(also polar distance or co-declination away from the star,
if you know its North latitude, called 'declination')

The Rabbit Looks up Ahead at Full Moon   Using the Ecliptic

When the 'cusps' disappear at full Moon, the Rabbit ears and face appear,
and let you know which way the Moon is moving.
These views are for the Southern Hemisphere — where the 'Rabbit' is upright.
In the first diagram, the cusps are difficult to distinguish, and so is the Rabbit.
In the second diagram, you don't need the cusps, because the ears show.
The dashed arrows point down to near Polaris.
As an alternative to cusp-North, you can use the Ecliptic perpendicular to the cusps.
The other, solid arrow, falls roughly along the Ecliptic, with the light side of the Moon pointing to the Sun and the dark side pointing to the anti-Sun.
Therefore you can judge approximate sunrise or anti-sunrise, sunset or anti-sunset, just as soon as you see the Moon, either from its cusps, or from the Full Moon.
Find the nearest horizon on the Ecliptic and picture which of those 4 directions it is.
A setting Moon in early daylight will show anti-sunrise, but after dusk will show up sunset.
An eastern Moon before dawn indicates sunrise, but in the p.m. will point to anti-sunset.



"E. W. N. South" **Of What**!?   Rule: **Say** What

- Say 'True' and you mean 'degrees East of True North' 270° T = due W.
- Write "Gee" and you mean: relative to the map **grid**. 270°G ≠ 270°T Both are clockwise around, but they start off from different directions
- S20°E means '(Start at)South(;come)20°(toward the)East' e.g.S20°E=20° to the right of the white end of the compass needle. (old system)

Clockwise/to the Right/East-around-from-North is standard if not otherwise specified.

- 270° M says 'Magnetic' — what a good compass should read.
- 270° C says 'Compass' — what this compass does read.

Note that these are standard: 'G' does not mean 'Geographical' or 'Great Circle' or 'Grads' but is recognised as 'Grid'.
'M' does not mean 'Map', 'Map grid' etc.
xyz° can not mean anti-clockwise.
The remaining problem is how to shift between different methods… See section 4: "East Least West Best" rule. (p.107b)

Earth Sun Stars Wind Anticlockwise

Perspective Distortion — The Sun Moves in a Straight Line!

The 'horizon' (at sea) seems "straight", yes? but joins to itself! This is because you see it from the centre of a circle. That's no problem yet.
Two different great-circles circling around you do cut twice, but *it certainly looks strange*, since looking at the gap between them, you see "parallel straight lines"; Yet to the left **and** right of that you will see them both join!
Great Circles Intersect Twice. **Nowhere does either circle seem to 'curve', yet they manage to meet.**
The Sun 'comes up and goes down' but is actually 'moving' in a nearly straight line—as straight as the horizon…



PUT YOUR HEAD INTO A HOOP; GET OUTSIDE; CHECK IT OUT; GET IT INTO YOUR HEAD: GET USED TO IT!
Caution: Don't look directly at the Sun. Watch your shadow and you will see that it moves in a nearly straight line from East to West.
The Sun's average path — the 'Equator' up in the sky — where the 'Saucepan' (Orion; the Pot) moves — is a great circle.
It intersects the horizon due East and due West. At times of year other than at Equinox, the Sun's path is still almost a great circle.
The Milky Way is another maximum sized circle; and the Zodiac (i.e. the Ecliptic) is another such 'Great Circle'.
They hit the horizon twice, in opposite directions (not E/W).
2 other 'great circles' you need to visualise are: Satellite paths; and the Dark Blue Band. (Star-trails are usually 'small' circles, and do look curved.)

Locate Polaris (and Find North) by Imagining the Centre of Circling



This works for the Sun, Moon, planets or stars.
You *find the centre of their circular paths by bisecting the chord*.
(Northerners locate the South Pole Star, South)

The **perpendicular bisector** of an arc or chord passes through the centre of a circle...



Moonrise varies quickly from day to day
— make sure you check its exact position.

Don't look directly at the Sun to do this!

Polaris is, in degrees, at 'your south latitude below horizontal' (not the horizon) — judge it carefully.
and/or, 'polar distance (co-declination) away from the Sun': 90°-N dec, e.g. dec=10°S 90-(-10)=100°

The Eagle Clips the Equator, South of Altair

Find the star 40% along the southwest side of the rhombus…

Finding the Equator helps you

find the Ecliptic (not shown)
and find where the Milky Way crosses the Equator…


Equator
AQUILA (The Eagle, in the Milky Way)
Galactic Plane
S
W
E
N
Altair (is flanked by two recognisable stars)
as seen from the southern hemisphere

Steering Winds

Mid-to-high-level (upper) winds tend to push sea-level pressure-systems along
at **half the speed of the upper winds, and in the same direction**.

This rule is said to work best with small, weak, less well-developed systems; and with hurricanes.

E.g. If the low is on your left And if the upper winds are coming from your left
Then the storm centre might pass straight over you.

Since the upper level winds often oscillate in the 'Rossby Wave', and tend to generate high and low pressure areas beneath them (because the 'wave' causes the upper winds to slow down or speed up) the High-pressure systems will on average be steered slightly toward the Equator, and the Lows will go slightly toward the Poles, as the systems move to the East — a rule of thumb worth remembering.

But this extra steering-wind rule will alert you to non-average situations.

"Rise-Noon-Set-Midnight" carries its meaning across the Equator! N.S.E.W. doesn't.

Name the directions according to the average outside picture…
This is a visual system and addresses the disorientation of turning around.
For back-bearings i.e. when you turn around: replace 'rise' with 'set',
'noon' with 'midnight' (start with end, & hottest with coldest)
e.g. if the old direction was "after setting" the new one will be "after rising".
When you turn right or left adjust by one of the four notches
e.g. 'after midnight' becomes 'after rising' if you turn 'with' the Sun.
Note: 'after the setting' (or 'before midnight') is a direction of the evening Sun
— S.W. — and can be bright sunlight, in midsummer !
And 'after midnight' ('before East') is the direction of the South-East Sun.
At Mid-Summer sunrise it can similarly be very much bright !



(The Northerner's version needs to go clockwise!)

Example: You enter a hospital with "setting" (i.e. due West) on your right, so you start at "midnight" (SH). You then navigate through look-alike wings, look-alike wards, and look-alike staircases, remaining oriented, and finally emerge, expecting "rise" on your right — having not looked out of a window for hours!

Global Sun Stars Moon Clockwise

Global Orientation: Half the Arc-Distance below Horizontal

Point out any country or place on Earth, by first finding the (arc-)distance there, and then pointing below the horizon…
The method works **from any place on Earth, in any direction, to any place on Earth**.
Step 1. Measure the angle around the circumference to it. E.g. guess from a globe of the world (This is an angle at the centre of the globe)
Step 2. **Halve** it. That is how far below horizontal it is.
E.g. South Pole from 30° S. Point 30° below since it is 60° away
E.g. Perth to Peking (which is directly North) is 32 S. to 40 N. Therefore the 'arc' to Peking/Beijing is 72°…



Try this (outside): Go through the motions of pointing out a whole circle of real places on earth, from the horizon ahead of you, to the horizon behind you, using your index finger.
E.g. point North, then down a bit to below horizontal e.g. New Guinea, now onto the North Pole.
Continue down until pointing down underneath you e.g. mid North Atlantic.
At this stage you have pointed through 90°, but have pointed out 180° around the Earth.
Turn around to continue, (Brazil, Antarctica) bringing your finger higher and higher until it is back to horizontal pointing at the hill on the Southern skyline.
Your index finger has pointed out a 360° circle (as measured from the centre of the Earth) by traversing only 180°!
Get Hold of a Globe. Go Outside. Point Out A Few Countries.

" Noon " is Not at 12 O'clock

' High Noon ' is at 'midday' i.e. in the middle, between sunrise & sunset. And that is **not '12 noon' or '12 midday'** but at North — Noon North. (SH)

- In summer-time 'high noon' may be near 1 or 1:15 p.m. or so. If you are on Summer Time, true noon is one hour late.

- Even in winter-time it may be over half an hour away from 1200 hrs. This is because we use a one-hour time zone to cover 15° of longitude.
  i.e. you may be near the next time-zone, longitude-wise, and therefore be up to one half an hour 'out'.
  You can check this up if you have a map with longitude on it. The middle of the time zone is at 7½°, 22½°, etc, in steps of 15°.
  Then it will take 4 minutes to travel an extra degree westwards. Work out how early or late the Sun will be in your longitude.

- Plus; the Sun speeds up in its 'orbit' 'around' the Earth when it is close in the Southern Summer, getting up to 20 minutes 'fast', by the end of summer; likewise it can be up to 20 minutes 'slow' at other times, in addition to the time zone effect. See the Equation of Time prediction opposite.

The best thing to do about this, to predict when, exactly, it will be at 'midday' today, is to look at the Sun yesterday.
(Don't! Use a shadow instead. Notice when it is due South.) Or see 26a.

Equatorial Stars Rise and Set Due East and West

Always

Globally

- The Sun at Equinox — about March 21st, September 22nd
- The Pot in Orion — Mintaka, the north-west star of Orion's belt — the one that sets first — is right on the Equator
- Various dull stars — like the one south of Altair
- A Half Moon at solstice — give or take 5° or so — It must be 90° from the Sun which is at the solstice position, so that the Moon is at the ecliptic equinox (Equatorial) position.
  Other phases can be worked out, e.g. Full Moon at Equinox, but see p. 29d on how to predict an equinoxial Moon every fortnight.
- Planets 90° from the Sun-at-solstice
- The equinoctial points, if you can identify them yet. One is between Spica and Regulus; the other is between Diphda and Markab.

The Moon Cusps Push and Pull the Hour Hand **Backwards**, Down South





Watch the Moon rotate during the day, and night. Tell the time from it. Update yourself once per day.
The Moon rotates like this about 14½ degrees or 15° per hour. So it is like a 24-hour clock hour-hand running "backwards".
The correct vertical to use as a reference is not at the Moon, but at the Pole Star, if you want to be accurate.

(NH — the Moon seems to turn clockwise)

Back-Bearings Killed Sleepy Pilots

Back-bearings are opposite directions — "going back home".
The Babylonian system of 360° in a circle has a lot to answer for, when you want to turn around!

What is required, is to add or subtract 180° (groan)!

But after an all-night mission, tired navigators can't be relied upon to come up with the right answer.
In World War II, many air-crews perished from following the wrong back-bearing back.
Happy, relaxed, but lost.
It was a problem requiring a solution, and a simple solution was found. What is it? (page 18e)

Half the Arc-Distance below Horizontal — 2 Explanations Why

1a.



A horizontal tangent

36° angle below horizontal

72° 'arc' around the circumference — twice the angle from the tangent — but why?

1b.



The angle at the centre (used for 'arc-distance') is always double the angle at the circumference…

1c.



..It doesn't matter which point on the circle you use, as long as it is on the one side —on the larger arc here— you get the same angle each time. The tangent point is one such acceptable point — the last one.

1d.



2. (Isosceles triangle angles… $(180 - 2\alpha)/2$)
$= 90 - a$



The "Equation of Time" Diagram

The real Sun moves quicker through the sky near Christmas because it is closer to the Earth (i.e. we orbit it quicker, elliptically!).
I.e. The Sun 'gets ahead of' its predicted average position, according to our clocks, in the New Year,
And doesn't come back to average until about the end of August.
After that, during September to December, it will be behind average. But then, in addition, the details are complicated by how it also zips quickly past (gaining on) our longitude lines near solstice — summer or winter — when it is near +/–23½° latitude.
Here the longitude lines crowd together, if only slightly, giving the maximum effect in June & December, super-imposing upon the preceding scheme.
The **overall result** may be graphed… (both hemispheres)
See the mnemonic on p. 86b



Note that when the astronomers say '+', the Sun is behind itself;
we look at the position of the Sun (not directly at it!); it comes up 'late'
and we have to add (about a ¼hr) to our guess at the apparent time,
to find the clock-time. We say our clocks are 'fast' at predicting
the Sun's position, but it is really the Sun which is lagging!
cf Australia is in a "**+**10 hr time-zone" = 10hrs ahead, or fast on Greenwich

---

Rigel-to-Capella is a good S./N. Pair



This pair points to Polaris (and hence to North, *when they are 'Upright'*) (this view is for the Southern Summer)

You can also see that the Pot handle points down through the middle of Orion's belt to Meissa and on to Polaris. The Pot 'handle' is actually the scabbard of Orion's sword—seen upside down (SH)

If you cannot see Capella, then Bellatrix to Elnath, right alongside, is also a good guide to Polaris.

Auriga, The Charioteer

....**The six o'clock stars are a useful N./S. pair** — they are upright at 6 a.m. local star time.

← 'Right Ascension', or star-time, in hours of longitude East of the first point of Aries

---

Atmospheric Pressure Changes

The air pressure falls before a front, and rises reasonably rapidly as the front passes. It falls in a trough; rises in a ridge; falls in a heatwave inland; falls with altitude (about one millibar per 10m).
The atmospheric pressure normally fluctuates by a couple of millibars every day in a twice-daily cycle tied to the Sun (3mb in the tropics) and the wind speed may vary with it. The daily pressure on average peaks around 10 a.m. and 10 p.m., being lowest at 4 a.m. and 4 p.m.; This on average, is said to vary the wind speed by a couple of knots, lowest at 9 a.m., peaking at 3 p.m., but all of this is usually masked by other weather changes in the temperate latitudes. Pressure fluctuation is much more significant in the tropics, with any fall (or flattening) more than a few millibars during summer/autumn warning you of a possible hurricane (You then look for long wavelength ocean swells preceding the storm centre). Because we can't feel atmospheric pressure changes, it is very helpful to use a barometer, to detect the longer-term pressure change trend. Test your barometer to see that it does not respond to temperature changes!

Watch the Clouds Cross the Moon

You can detect the upper wind direction most easily by watching clouds move past some fixed point in the sky.
Look during the night but don't forget to look during the day also.
The stars, high buildings, high trees and mountain tops also work well.

The **0, 1, 2, 3, 4** Reference Directions



Put these numbers onto the Rise-Noon-Set-Midnight System, so as to follow the Sun.

0 = midnight, South (Southern Hemisphere)
1 = rising, East
2 = noon, North (use South for northern hemisphere)
3 = setting, West
4 = midnight, South — use cycle 4 i.e. call it "0"

This corresponds to measuring anticlockwise! from South! in decimal degrees, that is, in grads!
100 grads = 90° so "1" = 100 grads; "4" = 400 grads or zero grads — add or subtract "4" at any time.
"0.1" in this system = 10 grads; 1/10 of a right angle; **one fist at arm's length**.
Example: In the thick bush, you see your destination but know you will soon lose sight of it. You can't keep a straight line, so you decide to keep track with the 0—1—2—3—4 system and your fist. With each change of direction you update e.g. "0.6, 1.6, 1.0, 0.9…"
For a **back bearing** — when you turn around — **add or subtract 2**.
Add 1.0 when you **turn with** the Sun (**left**), or **subtract 1.0** when you **turn against** the Sun (**right**). (S.H.)

Example: Point to Tahiti

It's 9 a.m. summer-time, the Sun is, say, 20° high and over Tahiti (see time-zone chart).
Firstly, point horizontally toward the Sun (not directly at the Sun!) — that is the direct path to Tahiti.
Secondly, point below the horizon, to locate the actual direction to Tahiti…

Step1. Make a perpendicular from a sunbeam. Perpendicular to the Sun is 'horizontal' in Tahiti…
Step2. Subtract its (present) height (20°) from 90°
The arc from you to Tahiti is 70°
Explanation:
(90° - the height of the Sun), the 'co-height', must be the arc-distance from you to underneath the Sun. Think of it like this...
If the Sun is 0° away from you, it will be 90° high — you are underneath it.
If the Sun is 10° away from you, it will be 80° high, overhead a point 10° away from you, and so on.
Step3. halve the remainder (70°/2=35°) Now add back on the 20° above the horizon…
"Tahiti is 55° below the Sun" from your point of view. You didn't need a globe or the arc-distance to find it.



The Sun Oscillates Seasonally between +/- 23½° Latitude

To approximate the Sun's "Declination"—or North Latitude—you approximate its variation as sinusoidal.
Using a 365 day cycle: You approximate 360° as 1° per day, so for ease and accuracy of calculation you can and should approximate the day-number as 30 days per completed month + day of the month.
E.g. **March 21st** is 2 lots of 30 days plus 21 = "81" days or degrees.

Then to use a sinusoidal curve, you need to run from Equinox to Equinox — i.e. starting at March 21, Day 81
Declination = 23.45° x sin (day number of the year – 81)
E.g. 0° in **September 21**, six months or 180 days or degrees later; uses day no. 261.
From solstice to solstice you can use a minus cosine curve...
Declination = 23.45° x –cos (day number of the year + 9)
..since the solstice is around 10 days earlier than the New Year.
Dec 21 solstice, is day no. 11x30 + 21 = 351 "–23°½ in December"
E.g. + 23½ degrees on **June 21**, day no. 171.
From this approximation you can predict noon-height (and, with the right formulae, sunrise & sunset time & direction and E./W. height, of the Sun).



Use the Southern Cross as an Hour Hand

You can visualise the rotation of the Southern Cross as a huge 24-hour clock hand.
It is correct on April Fool's Day i.e. upright at midnight (at 183°T), then it gains two hours a month, or 30°. (Use the correct vertical! — South.)
As a learning aid, mark the 'Southern Cross time' on your calendar every month
e.g. "two hours fast" at the start of May; and "four hours fast" at the end.
Then, anytime you are out at night, you can ask: **"What's the time — by the Cross?"**

Picture the Southern Cross during the Day

Yes it is there behind the blue sky… "If there were an eclipse now, it would show… there!"
When you are navigating by the 'spin' of the Earth, and by the Big Picture, the proper reference direction is the North-South rotation axis,
Which means: Polaris + South Pole Star.
In practice, what we Southerners see, is the Southern Cross.
So if you are imagining: sunrise — noon — set, or Moon position, or a star-compass course, or a shadow-south direction,
you ought to be thinking: "North — Polaris down there; South — South Pole Star up there", then you can picture the Southern Cross as well.

The Moon is Lit By the Sun



When the Moon is **opposite** the Sun, we must see its fully lit face… See diagram of the first man looking at the Moon, below.
e.g. a full Moon rising at Sunset; Setting at Sunrise; Overhead at Midnight or at least highest in the sky.
(A fortnight later…)
When the Moon is **near** the Sun, we see only its dark backside or at most a thin crescent… See the middle man below.
e.g. a crescent Moon is only ever seen near sunrise or sunset. Wait until the Sun is below the horizon — Don't look at the Sun!
At other times the Sun has set, taking the Moon with it, or has risen, outshining the pale crescent nearby.
(A week later…) When the Moon is **halfway** between, we see half of each side… See the third figure...
e.g. half a disk overhead — only at sunrise or sunset; half a disk setting — only at midday or midnight.
A half full Moon is misleadingly called a Quarter Moon… since it takes four weeks to move between the four "quarters".



Moonphase, Moon position and time of day are all tightly linked.

Back-Bearing: **Plus or Minus 200° Then Minus or Plus 20°**

(Or — for the very advanced sleepy student: adjust by 20° first (+/-20°) then -/+200°)

Examples: 10° is small, so make it big, 210°, adjust back to 190°
290° is big, so make it small, 090°, then back up to 110°
Advanced: 190° is middling, so boost it first, by 20°, to 210°, then remove 200° and use 10°
210° is middling, so try +20°, then –200° = 030°
When you end up with numbers greater than 360°, remove 360°. When less than zero, add 360°.
Difficult: -10° is small; first convert it, using +360° (= 350°)
350° is big so –200° +20° = 170°
185° + 200° -20° = 365°, so adjust it back to 005°

a simpler solution with a protractor compass, is to...



(see page 109b)

There is another solution to back-bearings — decimal degrees — but it hasn't taken on yet.

Use **Latitude** for a **Distance** Scale (Not 'Long'-itude, Despite the Name)

(Especially on marine charts, atlases and old maps—Newer maps are likely to have the mostly meaningless but well-scaled international map grid.)
Latitude means "distance" from the Equator. Remember the polar "distance" 90° complement to latitude? which measured arc-distance, in degrees!
1° of latitude = 60 nautical miles = 111 km The world is 360° around; or 360x60 = 21,600 nautical miles; or 40,000 km
The circumference of the Earth determines how long a kilometre or a nautical mile is — at least in the somewhat outdated original definitions.
(The N/S circumference of the Earth has proven to be closer to 40,007 km, and the E/W circumference is bloated by the Equatorial bulge.)
One 'kilometre', comes from the decimal system: whereby one circle equals 400 'grads'; one grad has 100 divisions… 40,000 km
Use the latitude scale on the left & right sides of a Mercator map to measure length or distance — but only at that latitude on the map.
But do not use the longitude scales running across the top and bottom of the map — since the spacing of longitude lines should vary with latitude. Longitude lines must converge towards the Poles, to nothing. They span a variable distance = 1° x cos (latitude), but a Mercator map will (falsely) show a constant separation for longitude lines (this is to make compass courses look straight). A Mercator projection will also show a variable separation for latitude parallels, even though they 'should' be constant. This is to preserve the shape of land areas—The latitude stretching must match the longitude stretching. Therefore any scaling shown on the E/W spacing is only valid for the latitude at which it is subdivided.
When a latitude scale says ½° or 30 n ml or 55 km, it means it, at that latitude, but when a longitude scale says ½°, the distance meaning is missing

---

Using the Declination of the Sun

- **Noon Height** = 90° – latitude + declination = (from horizontal) Convert "N." to + ; "S." to – e.g. 30° S. = –30
  E.g. Lat 30° S.; Decl. 20° N : Height = 90+30+20=140° or 40° (the two (opposite) heights must add up to 180°)
  i.e. The more the Sun 'declines' away from the Equator, and the more you decline on the other side of the Equator, the more the Sun drops in the sky. Alternatively, the colatitude (90–L) is the maximum height of the sky Equator... Then adjust for the declination.
- **Sunrise/Sunset** — time and direction prediction
  Cosine (angle from North/South) = sine (declination) / cosine (latitude) Try dec =23°.5; lat =37°.1; 55°.67; 62°.6, for a different hexagon
  Cosine (time in degrees from noon) = –Tan (Lat.) x Tan (dec.) 1° of longitude = 4 minutes of time.
  E.g. measure the time between sunrise & set; divide by 2; solve for Lat. (make sure to use horizontal, not horizon.)
- **East/West Sun** — Time and height prediction
  Cosine (E-W time in degrees, from noon) = Tan (dec.) / Tan (Lat.) e.g. 4 hrs each side of noon @ Lat 41° (Northern Tasmanian Summer)
  Sine (E-W height above horizontal) = sin (dec.) / sin (Lat.) e.g. 45° high E./W. from Lat 34 1/3°; +/– 3h21m; Mid-Summer

e.g. take the time when the Sun is E. & W. (opposites — you need to remember to carry 60, not 10, & to interpolate carefully) and then solve for Lat.
See p. 86b for a memorable laugh. Many more formulae and techniques are available, from books on astro-navigation.

Perspective Distortion — Use the Correct Vertical

Vertical is vertical, right? Wrong! To tell the time by the sky, take care.
The higher a pair of points (e.g. stars) gets in the sky, the more you have to choose which vertical is needed for a reference, to judge 'vertical' by.
Each different reference direction will give a different answer to "How vertical are those two points up there?" e.g. Moon cusps, Southern Cross
A side view makes this clearer....
..a straight line which looks horizontal when looking south,
looks diagonal in the East



The top view also makes it very clear… a line XY high up in the sky cuts each different vertical at a different angle..



Don't gauge the angle of rising/setting (p9a) at anywhere other than at the rise/set horizon in the rise/set direction.
Don't use the nearest horizon, as your reference for which way is up.
To visualise a constant 'rotation' of the stars, use Polaris or the South Pole Star as the 'centre' of rotation.
I.e. Use N-S longitude lines in the sky rotating in relation to vertical at North/South.

To Determine Upper Wind Direction from the Clouds



Walk in the reverse direction, while keeping a chosen cloud lined up
on a chosen high point. You must walk across level ground to be accurate.
Mark your starting point, then drag a line in the ground to mark your walking direction.
This method works well for very slowly moving clouds.

Other methods: Watch cloud shadows.
Use the Moon, Venus or the Sun (only when it is very well obscured).
Look in different directions at the moving clouds
until their motion seems neutralised—they are moving directly toward you.
Use binoculars, to magnify the movement (but never look towards the Sun).

The Sunny Skies Quadrant System

To orient yourself on a clear day...
Use the two ends of the dark blue band — where it hits the horizon — and the trend of the middle bit of the band,
in conjunction with the Sun (but don't look directly at the Sun!) and your shadow.



- No matter which way you are facing, you can detect one or two signs to orient yourself by,
  Or at least imagine them if you can't see the Sun just now.
  You don't have to look over your shoulder, which is misleading anyway.

The middle of the blue band is above your shadow, and at right angles to the sunbeams near you.
The whole system rotates, during the day.
If the **Moon** is up, add it into the system,
and **Moon-North** too, which is off to one side of North, and changes slowly during the day.
Combine this system with the fixed systems, of 0, 1, 2, 3, 4 and m.n., rise, a.m., m.d., p.m., set.
E.g. In the diagram, the Sun is to the left of North, so "the Sun is 'afternoon', the Moon is 'before noon'."

The Horizon Rotates to Your Right in the Southern Hemisphere

1.Face the High Noon Sun. (Imagine it, if you have to, when it is not midday.) It moves horizontally from Right to Left (S. H.)
2.Reverse your perspective — let the Sun stand still and the horizon move, from Left to Right.
Imagine the horizon sliding horizontally beneath the Sun (and you shifting sideways with it).
3.Now imagine the Sun rising from the eastern horizon — it moves up to your left — then reverse perspective...
Imagine the eastern horizon moving *diagonally down and away* from the Sun, twisting down on the right as it goes.
Face North. Grip the whole horizon on the East and on the West, and imagine a tilted steering-wheel, and rotate it around the Pole Stars. Imagine a "steer right" motion.
The invisible steering wheel faces you diagonally upwards, while the horizon, as if fixed (diagonally) to the steering wheel, starts off horizontal and then rotates out of its horizontal.
4. Keep rotating the horizon, sliding the northern horizon horizontally underneath the high noon Sun, and beyond, until the western horizon comes up diagonally to meet your now "setting" Sun.
You need to do this outside to appreciate it in three dimensions, to have any chance of visualising it easily.
So put your clock back on the Northern wall (see 5e) and say "See, we Southerners have it right, after all!
— the real movement — of the solid stuff — is clockwise"



Tell the Time by the Compass Protractor — Tilt It Toward the Equator

Take a **tilted bearing** of the Sun. The answer comes back as so many degrees to one side of noon-North (or noon-South in the N. H.).
You then use 15° per hour to convert that to hours before or after noon-time ('noon' will be nearer one o'clock during daylight savings time).

Step one: align the compass to True **North**
Step two: **tilt** it upward to the 'Equator' in the sky (the Sun's average path)
Step three: rotate the compass arrow to point toward the Sun
Step four: make the edge of the compass cast no shadow
This avoids looking at the Sun
Step five: measure the degrees away from high-noon North, on a tilt

It is more accurate than using a finger-span
to measure 15° per hour
i.e. Use the compass protractor to make a 24-hour clock face
To use the compass protractor as a 12-hr clockface, see the box opposite.

1. Top View 2. Side View



The reason for tilting is because
a level sundial/upright gnomon
will not give a 15°/hr linear reading
(See "The sun passes quickly")

The Southwest Corner of the Great Square is N. S. E. W.

The Great Square of Pegasus only has one really good right angle but it shows N. S. E. W. perfectly.
In the Southern Hemisphere, it is the first star of the Square to rise.

23 hours Right Ascension

Note: When you hold a star chart over your head
'East and West' reverse!

Equator — Double the Square,
to locate it

This is the view for the Southern Hemisphere…



The Moon Rises and Sets 50 Minutes Later Each Night

The Moon moves quickly to the West, but…
It progresses Eastward through the night skies, night by night, by 12½ degrees a day — it 'lags' the Sun or 'moves backwards' during the month.
So that after 29½ days it is back in the same place. It moves about 27 diameters' worth East through the stars, per 24 hours
or about a diameter an hour to the east in relation to the Sun. One 'diameter' is half a degree, and the same as the Sun's.
Sun, Moon, Planets and Stars rise in the Eastern half and set in the Western half, but some are quicker than others. The Moon is the slowest of all.
E.g. (twice-daily) tides get 25 minutes later each tide, on average — half a day + 25 mins apart.
E.g. the 12 month lunar year gains 11 days on the 12-calendar-month year, or "one day per month except for February, on average".
(a calendar month equals 30.4 days; a lunar year equals 354 days. Months 1,3,5,7,8,10,12 have 31 days—1½ extra; ½ extra in 30 day months)
The explanation for the Moon's "slowness" in rotating westwards with all the rest of the sky, i.e. from moonrise to moonset
(it rotates only 14½ degrees per hour, not 15° like the Sun) is that it slowly revolves around the Earth to the East,
in the same clock-sense as the Earth revolves around the Sun,
and so must complete 13 revolutions star-wise, to the East while we see only 12 Moon months.
By the next full Moon, its backside is toward a more easterly star…
For an anti-clockwise rotation system, viewed from the North...



1 month's change — the Moon goes full circle + 1/12, while the Earth orbits 1/12.

Turn 90°? "+/–100° –/+10°" !



Turning right is turning clockwise; turning left is turning anti clockwise.
Clockwise **increases** the count of degrees East of North. So that requires **+100°** -10°. E.g. 257° changes into 347°
Anticlockwise, when turning left needs **–100°** +10°. E.g. 257° changes into 167°
Or use +/-10° first, then -/+100° if that is easier (near 0°). Adjust by 360° if necessary.
There is no convenient choice as there was with a back-bearing, so you must remember whether to use + or – 100°.
Remember to look at the Sun's clock-sense to judge 'anti-clockwise'
— anticlockwise in the southern hemisphere — to your left. 'With' the Sun implies – 90° – 90° goes this way
— clockwise — to your right — ('With' the northern hemisphere Sun) implies + 90°.

Hint: When sailing, you can always temporarily head either towards or away from, or side-on to, on the left or the right, a landmark from which you want to take a bearing, without having to change tack. Therefore you can use +/–180° or +/–90° from the boat's compass-heading. In heavy weather this means that you do not need to leave the helm to use a hand-bearing compass, but merely sight along the lines of the boat, or cross-wise along the lines of the cockpit, stern or cabin. Simply remember that the more clockwise heading is bigger than the left-hand direction

Global Perspective — Rotation of the Horizon

Each point on the horizon rotates…

- In a circle
- Around in an Eastwardly sense, like all the real matter in our anticlockwise spiral galaxy
- Around the North-South Earth rotation axis
- Along a fixed sky-latitude circle (i.e. declination circle)
- At a fixed angle of rising/setting (one or the other) in relation to the fixed stars
- Once per day

Example: The "Sugarloafs" were on the left of the Sun at sunrise, but six hours later they had moved to be underneath it, by rotating around Polaris and now, at the end of the day, they have moved way over to its right, and will keep going around for the next 12 hours of night-time.

To further help you visualise the motion, remember that the ground under your feet is twisting you clockwise in relation to the sky, in the SH, so that the stars, etc, near the horizon all move only to the left as they rise or fall. For the Northern Hemisphere use "anti-clockwise… right".

Or Judge the Time By Sight — by Mirroring the Sun Around North (To Make an Hour Hand on a 12 Hr Clockface)



Sun = **'Noon'** position on the Clockface (i.e. ignore real Noon-North after you align the compass properly) (SH)
(Here, the 'hour hand' is showing 2½ hours until 'noon', judging it by sight)
(For the Northern Hemisphere, you have to reverse things… hour hand — Sun — South see p.28b)
Of course this method is really just helping you to GUESS!

Alternative: Line up a pencil tip with Polaris, while making the pencil cast no shadow. With your shadow-side hand, make your index finger ("The Hour Hand") touch the pencil tip, and look identical on the other side of Polaris.
You can make it work on the Moon or a star or a planet if you know when they are North/South of you.
You can make it work for magnetic noon, to avoid using magnetic variation.
It works because the Sun moves at half the speed of an hour hand,
but the doubled-angle shown, doubles that rate of change, to match a clock's hour-hand.
Don't forget to **tilt the compass**, so that its axis lines up with the Earth axis.

The Southern Summer Rectangle is Worth Looking for — since it has four N. S. E. W. guides

1. North: from Procyon, down through the Twins
2. North: from Bellatrix down through Nath
3. West to East: between Bellatrix and Betelgeuse to between Procyon and Gomeissa
4. West to East: Nath to between Pollux and Castor, closer to Pollux

(To remember the two Twins, say "Castor & Pollux, α & β, are North & South")



And a Triangle Pointing South

Betelgeuse, Procyon and Sirius.

Clouds and Con-trails and Their Winds

- Fog, which is cloud clinging to the ground, usually oozes downhill. Now, working upwards...
- Topographic cloud banks — may indicate e.g. the plateau edge or a mountain range. I.e. They cling to the topography.
  Also look for eagles soaring along otherwise invisible cliff edges.
- Low clouds — they follow the weather map isobars. Also look for sideslip of flying birds and aeroplanes.
  As a rule of thumb (clenched fist!) low cloud puffs are at least three knuckles wide, alto puffs are two, and cirro puffs are one, from sea level
- Middle ('alto') cloud — the puffs look smaller, the shading, less dense, but no 'iciness' seems apparent. The clouds obscure the Sun's outline somewhat. Their wind-direction is usually different from both higher and lower clouds. This wind will 'steer' low level pressure systems.
  (An 850 mb level chart helps) When a change is due, the middle clouds often betray what low wind direction to expect soon.
- High ('Cirrus') cloud — thinner; smaller puffs if puffy; icier i.e. fleecier, silky, filamentous; transparent, with halos & no shading.
  The Sun's outline remains crisp when seen through cirrus. Don't focus on the Sun!
  The cirrus-level cloud-direction in the subtropics is usually westerly +/−45°.
  Be sure to test this in your latitude. (A 500 mb chart helps) Try to catch glimpses of upper clouds through gaps in the low clouds.
- Jet Con(-densation) Trails — are usually in the high band. Look for them according to a timetable, each day.

The "SWEETHEART" Method of Orientation

We are human, and 'reference directions' are not. So make them more human, more personal, more emotional.
"Home" is not bad. "Sweetheart" is better.
Find something lovely about each cardinal direction. E.g. 'our favourite holiday spot on the coast'
Something you love or hate, want, or fear, about each reference direction…

You will find it easier to maintain awareness of bends
and to interpret meaning onto the skyline — what lies beyond and behind that horizon!

During one walk, these highlights are unlikely to change direction much.



How to Shift Your Horizon — Its Timing and Height in relation to the sky.

You can navigate by the "shape" of the sky, back to a spot where you have been before, by noticing the "position" of the moving horizon.
On a round earth you can shift your position and horizon 1°, or 360°, by travelling 1°, or 360°, around the circumference. (111 km, or 40,000 km)
The line where the horizon cuts across the sky, varies with the latitude & longitude & the time of day. Using the Sun as an example…
Note: The "1° for 1°" rule for your own movement, only applies after you neutralise the other motions, so as to be as if the sky is standing still.
E.g. You need to neutralise the Sun's daily motions, by looking at the same time of day — sunrise, noon, 6 a.m., or 12:22 a.m., or whatever.
E.g. You also need to neutralise the Sun's seasonal motion by looking at the same date every year — Christmas morning, June 25, or whatever.
(Leap years can only make a difference of up to 1° — you could improve accuracy by looking only every four years.)
Rule one: for West/East travel, remember that events like Moonrise seem to happen **later to an observer further west**, and…
Earlier in the **E**ast; **four minutes of time (early) for every 1° of longitude (East).** (these rules work in both hemispheres)
E.g. "Christmas Day Sunrise at camp 4 was at 6 a.m. last year, but now I see the Sun already up at 6 a.m., so to get to where we spent Christmas last year, we would have to go further west to make the Sun lower (the horizon higher) at 6 a.m." (Assume you are at the correct latitude)
Rule two: The horizon drops to reveal new sky as you travel onwards — **1° for every 1° of travel** — this works in any direction.
E.g. "The Sun rose to 75° high, but here it reaches only 74½ degrees — so I would need to travel a half-degree toward the Equator for it to be 75° again." (This example has deliberately chosen a North South change.)
Then you can shift your horizon, its timing and its height, by moving around the earth, in order to match a previous timed snapshot of the sky.

Walking in Phase with the Sun, Wind and Moon

Simple West-East Hairpin Daywalk.

- In a hot climate, walking into the **Sun** is unpleasant, hot and glary, especially in the afternoon, especially if you wear glasses, so...
- The morning **wind** can be very uncomfortably cold, and it is best to plan to walk away from it, too.
- Beach walks are more pleasant when you don't have to battle back into the afternoon sea breeze or prevailing wind; so assess the **forecast** before you choose a start point.
- Night walks and late camps are best done in bright **moonlight** — simply predict the phase.
- Spotlighting is the easiest on a waning Moon — since the **dark period** is in the evening, not before dawn.
- Spectacular pink full-Moons only rise at sunset, so it is best to predict such a **moonrise** and plan an early camp with a view.



E.g. Up in the afternoon **shade**; down in the morning warmth…
Similar considerations apply to sailing—e.g. aim to make landfall in the pre-dawn. You can identify the harbour, or the coast, by its light-houses, then soon after be able to enter the harbour in daylight.
E.g. Aim never to cross the sandbar on an outgoing tide—with steep breaking waves, in shallow water, getting shallower!
Coordinate Your Route, Pace, Campsites & Timetable To the Prevailing Conditions.

Navigating by the Shape of the Night Sky

Since the star-map — the background to our view of the sky — is unchanging, the 'shape' of the sky involves only the **position of the horizon** across the background of fixed stars, and the **rotation** of that horizon with time.
The sky gives a false impression that the sky itself is spinning, but it is we who are turning upside down! It is our horizon which is changing.

Just as you can neutralise the Sun's motion by looking at the *same time every day* (which will show up only its seasonal and longer term variations) and just as you could neutralise the Moon's motion, by looking at the same phase and Moontime every month (e.g. full moon rise), to show up its unpredictable motion, so too with the stars. You must **look at the same star-time every night**. If, in addition, you look at the stars from the same spot you will notice no change at all in the 'shape of the night sky' or the position of the horizon — star motion is all predictable, with no significant variations.
This makes the stars excellent for navigation — you simply locate the horizon in terms of the heights of the stars, the tilts of star groups, and the star-time of night. E.g. what star appears overhead and at what star time.
Thus, to find that spot again, even much later, you need to make your horizon look identical at the identical star time.
CAUTION: Don't go star-navigating; rather only imagine doing so, until you become an expert. Understanding it is more useful than doing it!
All figures, formulae and theories should be checked before you trust your safety to them.

The Moon is "in Phase" with the Sun — Watch for It

The Moon progresses (12½ degrees per day) contrary to the general rotation, so…
A **new** Moon, first seen after sunset, must grow from a crescent, in the **after sunset** part of the sky, as it separates from the Sun, Eastwards, night by night, more and more so after the new Moon. I.e. a 'waxing' (growing) Moon means Moonlit evenings. After full, the Moon continues Eastwards…
A **full** Moon must diminish, to a crescent, in the **before sunrise** time of night. I.e. a 'waning' Moon leaves the evenings dark, until Moonrise, predawn.
In other words, the predawns are moonlit for the second half of the Moon month, after Moonrise. In the first half, the predawns are dark, after Moonset.
The whole night is dark in the 'no Moon' changeover of months.
During the day, you ask "Is the Moon ahead of or behind the Sun?" I.e. Is the Moon predawn (waning) or post-sunset (waxing)?
Evening spotlighting — is best in the dark before the waning Moon rises — late in the Moon month.
Night-walking—is best in Moonlight after Sunset i.e. on a full Moon, or a waxing, almost full Moon. (early-mid month)
(Think of the Moon as prouder of its nighttime role as it moves away, and ashamed as the Sun gets closer)
Highest and lowest ('Spring') tides occur on or soon after a new or full Moon.
'Neap' tides occur (when the Sun and Moon pull at right-angles to each other) at "half full Moon".
(Shallow waters introduce a lag of a day or three, due to friction and resonance effects.)



Make it your aim to see these things all happen in phase with the Moon month.

The Clock-Face Method for Direction

Quicker than 360° — it only counts up to 12! — it communicates relative directions easily.
E.g. "3 o'clock high" = "on our right — up in the sky" "9:30 from Rigel" = to the left and just above (that star)
Or, for horizontal directions, " 5 o'clock from the Sun " = looking down-Sun, and slightly to the left "six o'clock true" = South
At 30° per "hour" it is easily compatible with 360° — both are Babylonian systems.
(But don't confuse it with a 24-hour clock face, which is only 15° per hour. Unfortunately our clocks do not use a 24-hour system, which would make them nicely travel around once per day — as fast as the Sun.)
For shifting between clock face directions and 360° directions…
— First convert to or from the hour: Multiply hours by 30, for degrees. Use 12hrs=0 : 0 30 60 **90**; 120 150 **180**; 210 240 **270**; 300 330 **360**
— "5° extra" = "add 10 minutes" e.g. 255° = 0830 hrs (240° = eight hours; 15° = +10+10+10)
— "1° extra" = "add 2 minutes" e.g. 258° = 0836 hrs
When using the clock-face for compass directions, for NE, SE, SW, NW use 1:30, 4:30, 7:30, 10:30.
Translate 1, 2 o'clock as "(roughly) NNE, ENE," etc.
Don't use the minute marks on the clock-face because every 6° is not very user-friendly

Latitude without Numbers

When all you want is the latitude, the shape of the sky can tell you, without numbers, without calculations, without a watch.
E.g. 'Canopus overhead', or 'the Pot sets at 30° off vertical'.

If all you want is to recognise appearances locally, you don't need to set your Star watch to Greenwich Time, or to know a star's longitude relative to Greenwich.
E.g. 'I set my watch to the Dog Star passing North, from home last month'.

If you don't want calculators and trigonometry, you don't need to use them.
E.g. 'The sky is behaving the same as last year, we must be within sight.'

I am about to give you the star time and star longitude information, only for those who wish to work with the easiest benefits from them.
E.g. 'That must mean that our longitude is 150° E.'


Advanced
Down-Sun
Circuit
Sunset
Summer
Sunrise

This Assumes Southern Hemisphere


predawn start
Winter
circuit starts
at the 2 pm
position
finish after dusk
'nice cool breeze'
in your face


or start at
the 3 o'clock
position away
from the wind
no 'nasty cold wind'
in your face
finish

Note that clockwise circuits and half-day walks must alternate between up-Sun and down-Sun.


How **not** to
circumnavigate
a lake —
from the
9 p.m.
position
The Sun shines in your eyes all day!


How **not** to climb a hill — at the end of the day
On a sunbaked hill face
Afternoon Sun in your eyes
Into the Sun


How to climb a hill
— with a morning-fresh climb
in the shade.
Dawdle on top
return in the twilight


How to climb a mountain
in the outback heat —
Up the west face; long lunch on top
You walk always in the shade.

Matching Sky to Sky — Move Only Your Horizon



A. Move **towards** a star and it will **climb**
e.g. move toward the pole star
to a higher latitude
and it is higher
For stars other than the pole star
Assume a certain fixed star time
or a very high-speed—to stop the stars moving.



The pole star is too low

B. Move **sideways** and your horizon **tilts** with you
e.g. a star pair
may not be upright
as expected —
move sideways.
Or perhaps
a star pair
sets before it becomes upright
You need to tilt your horizon
down to the right
by moving to your right..







C. Because the Earth spins to the **East**, it leaves the stars behind in the West.
If you move west with the star it will slow down, so…
Move **E**ast and the stars will *get there* ***E****arlier*
e.g. 2 stars become upright too late?
You need to move easterly.





You may need a combination of A., B. and C.

Prevailing Winds on Creek Banks

One of the two Creek banks will often have a mud- or rock- cliff due to prevailing wave-action, with the other bank being a mud flat.
E.g. If prevailing winds are westerly, the west bank will show less erosion.
For more on finding the prevailing wind direction when the wind is not blowing, see section 3: "Nature's Norths".
Because prevailing wind is almost continental in scale, navigating by it is a sort of Big Picture technique.

Tips for calm weather

1. Listen for the wind! Sounds will carry better downwind e.g. surf or traffic. Remember this, at night when all else is still and quiet.
2. Watch the angle of mist droplets falling. (Stop still for this one) Or smoke rising.
3. Huff into the air to make a fog.
4. Watch the flimsiest vegetation.
5. Look at the leaves which dangle down from the topmost leaf clusters of a tree.

Mnemonic: "North; Coast"

That's what you should say, whenever you say 'North'.
"North (Coast) is over there" — it reminds you to think,
or rather to picture, the invisible picture.
You should make it your business to name the North-Coast town north of you,
before you go, by consulting a roadmap
Then of course, there is the East Coast, and the South Coast and the West Coast.
Next, of course, the same must go for "North-West"
— think of the North-West Coast township, and so on.
You are not functioning properly unless you mean something when you talk!

Go Overseas!

This is a one-off effort, so go to the trouble of getting a globe,
to sort out what is truly "East" and "West" of you,
in a Great Circle straight line.
It will surprise you what East and West should mean to you.


Tokyo
India
Fiji
England!
Wellington N. Z.
South Africa!
Macquarie Island Aus.
South Georgia (UK)

e.g. from Australia...

Global Sun Stars Moon Clockwise

Mnemonic "The Sun Travels the Tropics"

I.e. Imagine the **tropical countries and oceans** which are **'underneath' the Sun** as it moves East to West during the day — The Equatorial band.
For Australia that means from Central America Across the Pacific Ocean Past New Guinea
On to the Indian Ocean And on toward Africa
When we in Australia see the Sun rise, it is past noon in the Americas. At our sunset, it is approaching noon in Africa.
See the Reference List of Tropical Places (for The Eastern Australian Time Zone) opposite. As a help to global orientation, make it your aim to memorise these time zones in sequence. Check it out with an atlas. See the tear-out clockface diagram in the appendix.
The same sequence holds for any planet, or star near the Equator e.g. for the stars listed 'opposite the Sun' (below), but with different timing.
You can also imagine which country the Sun is overhead while it is night-time near you,
or which country the star opposite the Sun is overhead while it is daytime near you.
Now, with this in mind name the general North/South directions, according to the height of the Sun: To the Sun = "Hot"; To noon = "Hottest"; and the Shadow direction = "Cold"; Shortest shadow = "Coldest".
•Although the Moon, by comparison with the Sun, has a "cold" feel to it, make sure you apply the same list of hot tropical countries to it also.
When you see any Zodiacal body, you should think: "That is a Hot direction; It is over a Hot country." and try to name the country.

Tell the Time of Night by the Star **Opposite the Sun**

Such a star will be **up all night** — whether the night is long in winter, or short in summer — look for it. Write them on your calendar.
This yields the solar time, i.e. with respect to local noontime, but not the daylight-savings or summer-time, so adjust by one hour in summer.

January	Sirius *Castor, Pollux*, Procyon
February	Suhail, Miaplacidus Alphard *Regulus*
March	Pointers (Dubhe-Merak) *Denebola* Phecda Southern Cross
April	Southern Cross Alioth *Spica* Arcturus, Pointers (R.K./Hadar)
May	*Zubenelgenubi*, Kochab Alphecca *Antares*
June	*Antares* Atria Rasalhague Scorpion Sting Kaus Australis Vega
July	Vega *Nunki* Altair (Aquila) Peacock Deneb
August	Deneb Enif (ε Pegasus) Alnair
September	Fomalhaut Middle of Great Square
October	Diphda Mirach Achernar Hamal-Almach
November	Mirfak
December	*Alderbaran* Capella-Rigel Saucepan Six O'clock Stars; Canopus

This list is arranged time-wise
the earlier stars are correct
at the beginning of the month,
the last stars, near the end.
Use each as a 24 hour-hand around the South Pole Star
The Zodiacal stars
(the ones on the Ecliptic)
are in italics.
Only they are truly opposite the Sun.
This chart is **true for**
both Hemispheres, permanently.

Two Different Back-and-Forth-Star-Directions Give You a Position Fix

..Yes, it's just like two bearings (which are not opposite each other) from two landmarks. But because these 'landmarks' are so distant, the accuracy is only to within seeing distance. For better accuracy you would need a theodolite or sextant.
E.g. when two stars look upright, that locates a global star-direction; a second upright pair gives you the second direction, and a position fix.
To fix your latitude. you have to **measure the time-lapse between the two star pairs**. (Simultaneous is simplest.) So you need a plumb-line and also a watch. And for accurate (Greenwich) longitude fixing, you need to work in (Greenwich) **star-time** — otherwise you have only latitude which is fixed. So you need either an almanac, or calculator, or star-watch, or a work-it-out-at-home-later approach.
This is equivalent to fixing which star is exactly overhead and when. To see this, look up past the top of the plumb-line to 'overhead' from the two different directions—one for each pair—to see that they must cross exactly overhead.
The 'fix' is repeated accurately over years, and every night at the same star-time, with some very small predictable drift in location and timing.
No one else on earth can see exactly what you see right now. That's what gives you a unique position fix.
People at the same latitude see something very similar earlier or later than you do.
The best two directions to cross are Northwest/Southeast and Northeast/Southwest. Top-view...
This is because East/West star directions are time-wastingly difficult to determine.
This method is most helpful, of course, at sea, or in the desert, or as a hobby, or when lost.



Predict the Full Moon Path According to the Time of the Year

The full Moon is **opposite the Sun**, and is near the **Ecliptic**, i.e. in the Zodiac (the Sun's path through the stars) so that…
When the Sun is in midsummer position—high, and up for a long time—the full Moon will be in a midwinter position—low, and setting again quickly
When the Sun is in the midwinter position—short days—the full Moon will be high and up for a long time — long nights.
The two complement each other, since when one comes up the other goes down, and when one goes down the other comes up.
Both Sun and Moon are on the Ecliptic—not usually on the Equator—but, at the Equinoxes, the Sun is on the Equator, so the full Moon is too.
Near Equinox, of course, the Sun and Full Moon will rise and set in almost the same positions — East and West — and follow similar paths — about 12 hours each, along the Equator. The Equator and the Ecliptic intersect in two opposite points — the equinoctial points.
In other words, you can **use the full Moon to visualise the Ecliptic**, and to guess where the Sun is, i.e. to guess the time of night,
Or you can use the Sun to visualise the Ecliptic, and to guess where the full Moon will be, how high, and for how long.

Finding North from the Moon, by its height & phase

The Moon will follow a Midsummer Sun's path, or a Midwinter Sun's path, or an average height path, according to where on the Ecliptic it lies. Because the phase of the Moon is determined by its relative position to the Sun, the combination of the time of day, the phase, and cusp-Ecliptic gives you an unmistakable sense of where North should be, when you see the Moon. When you see the Moon surprisingly low in the sky, and the cusps confirm that the Ecliptic lies fairly horizontal, you know that it is somewhere near North (SH), following a low and horizontal trajectory, rather than a Moon 'just now rising' on a high trajectory, like a summer Sun in the East.

One Degree is about One in Sixty

1 in 60



And **n° is about n in 60**. e.g. **10° is 1 in 6** (p96a), and **6° is 1 in 10** (3 fingers wide, or 3½ knuckle-centres, at arm's length, or 'blink your eye').
These are handy rules of thumb for navigators. If you use an isosceles triangle, **the rule is remarkably accurate for most acute angles**.
Example: "Oh I forgot magnetic variation! I've been **5° off**!! Oh well, I will simply adjust sideways. Isosceles



I have come 12 km; 1/60 of that = 0.2; times five = **1 km off**"
Actually 1° is 1 in 57.3 (1.75:100), predictably slightly more than 1 in 60, but as the angle increases so does the accuracy of the 1:60 rule.
The rule (n° = n across at 60 away) is based on: the third side of the **isosceles triangle** (is twice the sine of half the angle).
(If you don't like numbers, try this other "handy" rule...) 6 (equilateral) lots of 60°



Rule of Finger: point your index finger at something — the fingernail is 1°.
Why is 1° slightly more than one in 60?... 60°



Six equilateral triangles go all around the circle, but, as you know, 6 1/4 radii go around the circle.
This is because the circumference, longer than the hexagon, is 2pi times the radius, or 6.283r one radian=57.3°



So one 'radian' of arc, which is one radius long, but curved, will be slightly less than 60° i.e. 57.3°.
So if the radius is 60, one sixtieth of a radian will be "one in 60", and slightly less than 1°. 1/60 of 1^c = 1 in 60



377 of them go around the circle. For 360 degrees around the circumference, the radius needs to be **57.3**.
The equivalent is '5/3 across at 100' (5 at 300, 167 at 1000; above 10°) with the more exact figure for up to 10° = 7/4 in 100

Tropical Countries and Places Under the Sun — Arranged in Time Zones Relative to Eastern Australian Time — 10 hrs ahead of Greenwich

-12hrs. The mid North Atlantic (is opposite Australia)
-11hrs. Brasilia 16° Sao Paulo/Río de Janeiro 23½° S.
-10 hrs. Trinidad and Tobago 10° N.
-9 Cuba/Haiti 20° N.; Bogotá 5° N.
— Panama 8½ hrs ahead of Australia
-8 Galápagos 0°; Guatemala 15° N.
-7 Gomez 26° S.; Mexico 23½° N.
-6 Pitcairn Island — Easter Island 25 to 27° S. (L.A. 34°N).
— Tip of Californian Peninsula 23½°N; IDR Gigego 20°N
-5 Mangareva Tropic of Capricorn
-4 Tahiti 17°½ S.
—Cook Islands 11° S.
-3 Hawaii Island, Tropic of Cancer
-2 Fiji 15° S.
-1 Noumea 21° S. See pp 132f

0 Rockhampton, Tropic of Capricorn 23½° S. (Canberra 36° S.)
1 Alice Springs, Tropic of Capricorn
2 Sulawesi 0°; Manila 15° N.; Port Hedland 20° S.
3 Christmas Island 10° S.; Jakarta 7° S.; Singapore 1°N.
— Cocos Islands
4 Calcutta Tropic of Cancer 23½° N.
5 Maldives Equator
6 Gulf of Oman Tropic of Cancer
— Seychelles
7 Port of Aden 12° N.; Mogadishu 3°; Madagascar 23½° S.
8 The north of South Africa on the Tropic; Lake Victoria 0°; Sudan/Egypt on the Tropic; Aswan High Dam
9 Namibian Desert coast on the Tropic; Lake Chad 14° N.
10 Timbuktu 17° N.; Accra 5° N.
11 West Africa coastal bulge 15° N.

Tell North from The Time By Using a Protractor

Reverse the method for telling the time from the compass protractor and North. To make the zero point North...
Make the sundial (protractor) show the correct time (one side of 'noon' time). Simultaneously make sure the sundial face is tilted to be parallel to the Equatorial Plane… I.e. For best results the tilt of the protractor according to the latitude, needs to be accurate.
Consequently, you may find it an interesting exercise to mockup a large (bigger = better) cardboard multi-protractor
— e.g. by marking the sides of a cardboard carton.
Use a plumb-bob to **accurately tilt the protractor, according to your latitude**. E.g. pin the plumb-line to the top, side corner, and mark 90° on the flat face…
This instrument may be used to find North if you know the local time, or to find the local time if you know North.
One side of the carton is used for the latitude protractor in conjunction with the plumb-bob, a second side can be marked as a sundial protractor.
E.g. use another (long, straight, perpendicular) pin at the top corner of the side facing you, to cast a shadow across a 90 degree scale (— this is for accuracy, rather than make a full 180° or 360°).
Morning and afternoon then require separate scales; Winter-time requires that you face away from the Sun.



For Land-Navigation, Choose the Plumb-Line Star-Pair Method



- Use a smooth constant diameter line, preferably thick. Make the plumb-line tall and stand far back. Make the cord either white or black to stand out against the sky, then maybe flash a torch onto it.
- Pour sand around the plumb, to anchor it to the ground. Avoid wind, especially if you hang the line from a tree branch!
- " Blink " the stars "on" and "off" behind the plumb-line, both on its left and on its right, by moving your head.
- Average the "start" & "finish" times. I.e. "It seems to line up now for the first time"… "definitely finished now". One accurate set of measurements is better than several rough ones. One star will gradually move over the top of the other star, and you have to pick exactly when.
- Choose well-separated stars (e.g. Rigel & Capella)
- If you want the timing to give you your longitude immediately, choose a North/South pair (e.g. Rigel & Capella) — (you need to know the star's longitude or its timing elsewhere, i.e. from a known longitude).
- An East/West pair will give you your latitude (without the need for a watch). The observation here is not the time but **whether or not** the given pair will attain to uprightness, after the first glimpse or before the last glimpse. Beyond a certain latitude, a given star pair will always remain tilted, less than vertical. This latter process can be time-consuming. Use a hand-held plumb-line occasionally, to check the progress.

Predict the Moon Phases by " N minus M "

" N " is a number (you calculate) for one particular year (e.g. For 2004 it was "24", in Australia's time zone, for the New Moon)
" M " is the month number (e.g. April is "4")
" N – M " is the day of the month for a certain fixed phase (e.g. in April 2004: 24 – 4 = 20th April 2004 for the New Moon)
April 20 was dark all night. New Moon seems to show the most regularity. The 'new Moon' is more accurately 'no Moon'.
Other phases happen one week later, two weeks later, three weeks later — 'quarter' by quarter — 29½ days for the whole cycle.
(The number, N, in 2004, would be 2; 9; 17; 24, 32 approximately, for 1st; 2nd; 3rd; final and 1st quarters respectively.) You can add 29½ to N.
Then in 2005, the number, N, for the new Moon was 13... (i.e. in April 2005, 13 minus four equals… the ninth of April — no Moon).
And in 2006 I used N = 32; 21 in 2007. The number N for the New Moon must be close to any **New Moon date + M**, e.g. December New Moon+12
Check your diary's calendar each year for the Moon phases; test and tweak a number N which works to within plus or minus one or two days.
The prediction is fairly crude, but with trial and error you can come up with *the best number and phase combination* for that year. For 2010, it is 18.
—usually **11 days less than the year before** (12 for leap year) because the lunar year of 354 days is 11 days shorter than the ordinary solar year
I.e. a good mnemonic is: **the Moon gains one day a month for every month except February** (which has only 28 days).
Hints: *Subtract " M " twice for January and February,* for more accuracy on non-leap years. Alternatively, to cope better with leap years...
Start the year in March (after the short month, February). Call January & February "months 13 & 14", but subtract 1 more for their accuracy.
Note: The "Full Moon" is when the Moon is nearest to "opposite the Sun" and it may not be exactly on the horizon when the Sun is.

Walk across Australia!

(Substitute whatever continent is appropriate)

Mentally line up a wall-poster size map of the whole continent (or bigger) with the track.
When you approach a bend, place the map on the bend, then walk all over it!
It's hard to miss the meaning of the bend if you bother to do this.
Your mind may not believe that it is not still going 'straight ahead' until you force it to catch up with the facts!

English!

"East-around" from North, is West-around from South, in a horizontal clock-sense. An "Easterly" course means East-wards — moving **to** the East.
An "Easterly" motion means East-wards. E.g. an "Easterly spin"-motion = "orbiting in an Easterly sense" = moving E around the N/S spin-axis **But**…
An "East(erly)" **wind** means flowing Westwards, **from** the East. An "Easterly" **current** might be flowing Westwards, from the East, but
an easterly tidal "set" is an offset to the East. (Set is how far the tide "sets" you off track. The speed is called the tidal "drift".)
" Due " East means "exactly" East, as when a loan is "due" — "right now!" **Always double-check what someone means**!

North/South and Noontime by **Bisection (of Rise and Set)**

Rise and set are **symmetrical around North/South**, provided you use horizontal, and not the horizon.
In hilly country, instead of 'rise and set', you should use **equal height** of the Sun (e.g. in NE and NW).
"Equal height" translates as *equal length shadows* of an *upright*, *straight* stick or cord, onto *flat* ground…………
Or, better, use a bush sextant, p.27c, set to a fixed reading.



There are four ways to bisect two directions to find North/South — so don't muck it up by 90° or 180°!
The second diagram will work in both hemispheres — but double check the results for sense.
There are also two ways to **bisect the time** — so don't mix up 'just before midnight' with 'just after noon'.
It is also hard to 'bisect the time' to find noon, which of course, is not at 12 noon exactly, nor at 1300 hrs exactly in summer.
To work with hours, you need to **carry 60 minutes**, not 10 or 100! So be careful and crosscheck your figures.
Be accurate or your results will not be worth the effort.
E.g. rise: 0529 hrs; set: 1820 hrs Add… = 2349 hrs Halve… = 1100+(**60** +49)/2 = 1154½ hrs = noon.
Check: total elapsed time: 1820 –0529 = 1251 = 2x0625½; 0529 + 0625½ = 1154½ = correct
1820 – 0625½ = 1154½ = correct



Longitude and Latitude from the Sun

Longitude...
Try timing the Sun for **equal height** each side of noon e.g. NE & NW (SH) to calculate the time of noon.
This can tell you your Greenwich longitude, provided you know the Sun's longitude, that is, its G. H. A.— from an almanac or calculator.
The Sun shifts predictably at a rate of near 15°/hour westerly. Almanacs make it their business to predict its West longitude exactly.
Of course the Sun's longitude at the time of your noon is your longitude too — since it is north of you.

Now try timing the Sun in two **opposite directions** at the same heights i.e. East and West.
You could try using the shadow of a plumb-bob on flat and level ground. Mark the shadow carefully.
This will be most accurate in the season when the Sun reaches high — in the summer sky.
By a series of early observations you can guess at when to make a final observation.



Using a theodolite or bubble sextant allows you to graph the rise & fall of the Sun (or a star) and see when 'same height again' happens.
See the 'Bush Theodolite' for an alternative measuring method.
Latitude (There are easier ways!)...
You can now solve the E/W formulae for your latitude — e.g. try the formula that predicts the timing of East and West for the Sun.

Equal-Height Stars Can Be Useful When the Sea Horizon is Visible

(or with a bubble sextant)

For direction, use the mid-point, of two stars which appear to be of equal height. — a great circle direction
For longitude, the timing is the important bit. — these stars should be approximately north or south of you
For latitude, the test is whether or not the stars do attain to equal height. — these stars will be approximately East or West of you
For a position fix, try to get two pairs, one north-west, the other north-east of you, for instance.
A **bush quadrant** is easy to make with a string tied to a stick! — just pull the string to length to measure or compare star heights.
Rest your hand and chin on something solid if possible. Use your full arm's length for best accuracy.



You can fix your latitude by measuring the **timing** of **two** separate star-pair events
— the relative timing — e.g. '5¼ minutes apart' (is unique to that latitude).
Simultaneous events are simplest, but separated events are easier for one person to time.
You don't 'get on the map' with this simple method unless you have been there before.
Unless you want a lot of trigonometry no calculations are required,
only the observation of re-recognisable appearances.
You can fix your longitude, too, by measuring any absolute timing — an exact star time — and so get on the map.

Anticlockwise, to the East, is Your Best Spin-Reference Direction

Because we use our North-South axis as our reference direction, we have to learn the *spin-sense* as something *separate*. See 'Orientation' p 35a.
The standard viewpoint for any spiral system (e.g. a weather system, a clock-face) is 'from the top', "**as seen from above**". Horizontal directions are measured "clockwise around" as you look *down* on them. For our spiral galaxy & solar system, the correct viewpoint is therefore 'from the North'
Looked at 'from the top', i.e. from the North, our Galaxy spins anti-clockwise. Or more simply, 'to the East'. 'Up North' is 'on the left' of East.
This means that the real motions are East-around the North/South spin axis—opposite to the familiar idea that everything sets in the West.
Because Northerners have their back to the North Pole when they see the Sun Down South of them, they see their horizon spin anti-clockwise — that is, the hills and trees on the horizon move to the left of the Sun. They are looking "from the top" i.e. from the North further South.
Their Sun only appears to move clockwise (to their right, to the West), because it is their horizon moving—anti-clockwise (to their left, to the East).
To avoid confusion, always make the distinction between real mass movement and apparent virtual rotation. And think: We spin East.
Because we think of 'clockwise' and 'right-hand' motion as 'standard', and setting "in the West" as 'normal', it's a bit of a shock, to rethink!

When you are Down Under, on the South side, looking North at the noon Sun, you see the bottom of our Galaxy, and Solar System, and Earth.
The three 'North' spin-axes are all very roughly aligned together, all lying in our "Northern" Hemisphere — not too much tilted from each other or from our own spin-axis. You mentally lift yourself further out (not "up") into space to look at (but not really 'down' on) the spiral motions
Remember that from a 'standard' (Northerner's) point of view, the Southerner's view is really "a bottom view looking upwards" — from the South half, and you have moved out further South, for a better view — with the South Polestar behind you. You should see clockwise real movements.
Turn around and look Southwards at the Southern sky and you will see as if 'from the top'—or at least 'from within', but looking South. Anticlockwise
Remember to rethink "Up" as "to the *North* Pole of the spin".

- It should now be easy for you to visualise, in either hemisphere, your Southern horizon spinning anticlockwise.
- Look also at the Moon—visualise its orbit and its spin—'anticlockwise' from N.H., but clockwise-around if you are seeing it from e.g. Australia.
- Find the bright planets — can you 'see' them moving 'anticlockwise around the Sun' in orbit? The Ecliptic marks their path.
- And, go further, visualise the real Sun spinning much like the Earth does, on its own N-S axis. The Sun is North of you in the Southern hemisphere, spinning on its own axis 'clockwise from below', or in the Northern hemisphere, South of you 'anti-clockwise from above'. Use the Ecliptic's N-S spin axis as a good guide for the Sun's, or simply use the Earth's own axis as a rough guide — Don't look at it, but imagine its sunspots moving.
- Keep going: The Earth hurtles through space in orbit around the Sun 'to the left, while looking to the Sun, around a N-S axis of spin' (Down Under, looking North) 'to the right, relative to the Sun' (NH) '**anticlockwise**, looking South' (NH)—'with' the apparent movement of the Sun, in both cases. That makes the noon horizon move in opposition to the movement of the whole Earth through space. Like the slow 'inside' of a spinning ball circling.
- Imagine the whole Earth-orbit in the sky. It's easy when you get the hang of it. New Zodiac stars seem to emerge (invisibly) on the Sun's West side, in seasonal procession, because "the Sun is edging Eastward along the Ecliptic in a yearly cycle" i.e. we move to the West side of the Sun and see behind it to the background Zodiac stars. Don't look at the Sun, but you should be able to 'see' this happening as if there were a star chart behind the blue sky! Try just before dawn.
- Now, at night-time, find the centre (thickest part) of the Milky Way near Scorpio/Sagittarius and visualise the whole Solar System orbiting it perpendicular to that, the Sun/Earth/Moon all moving as a unit, to your left (SH) or right (NH) towards Suhail, away from Deneb.

The Milky Way marks the plane of the spiralling galaxy (from which you can determine its N-S axis, tilted differently from ours).

Finding Magnetic Variation by Bisecting Rise and Set

Accuracy is needed.

Measure the compass directions of the morning and evening Sun at equal heights e.g. rise & set on a flat Horizon
Bisect the result. E.g. Rise: 079° Compass Set: 271° Compass
Add: 350° Halve: 175° Use the Opposite: +200–20=355° (See p.18e)
So the Compass North must be 5° to the East of geographic North. **Draw diagrams to avoid getting confused.**
Check all numbers! E.g. 355°–271°=084° 355° to 360°=5° + 079° more=84° Correct.
Or 271 – 79 = 192° spanning = 2x96°
79+96 = 175°
= opposite to (375 – 20)°
Correct.
The compass readings are "Least", by 5° (see p 107b)
E.g. 079°C is really 084°T. (see p 14e)







Approximate Magnetic Variations iso– lines

A Bush Theodolite for Overnight Equal Height Observations

This is for accuracy in calculating... True **North**, Noon **time** and Compass **variation**
And for any equal-height paired observations — Sun/stars/etc.
Find a large bent stick. (Or bend it with a bowstring)
Hold it up by a loop-knot e.g. hang it on a twig.
(If it is early or late i.e. a long shadow, the stick will not need to be bent much.)
Late afternoon, at camp,
Mark where the shadow of the knot (or the other end of the stick) falls on the stick;
take the time; line up the landmark it points to; and find its compass direction.
Early morning, next day,
Hold it up (in reverse); wait until the shadow again falls in its proper place;
get the time, direction and compass reading again.
For a **Bush Bubble Sextant**, arrange a water filled clear tube on a triangle of lashed walking sticks so that there is a trapped bubble in a tube section with an ever so slight convex-upwards bend.
Make the bubble always stay at one marked place when you are using it.



Great-Circle Reference Star Directions

You need some familiar reference points. It's a simple matter of going out at night, waiting around, and tracking down a few of these...
Look for **stars which are closer to the pole than you are**, and see where they **rise and fall vertically**. It happens once or twice a night, per star.
This gives you a series of great-circle star directions, already labeled, because **the 'maximum latitude' is equal to that star's 'declination'**.
E.g. Acrux is about 30° from the pole, or "60° latitude". If you steered towards one of its vertical-motion directions you would end up underneath it.
So as it rises or falls vertically (once each per night, if visible at the time), as it circles the South Pole Star, it lures you to 60°S latitude.
E.g. A star overhead, as the extreme limiting case, is moving East to West, rising vertically from the East and falling vertically to the West, meaning that you are *already at* the maximum latitude of that course, if you had been heading towards that star guide, now travelling E-W also.
You then have to head directly *away from* it (e.g. the next night) to further pursue that course.
Heading away from that star either East or West would take you eventually back towards the Equator, like the way you travelled down there.
The **stars further from the pole, than you are from the Equator,** make a complementary set of reference directions, by using the horizontal direction 'at **right-angles** to where stars **rise and set**'. **The declination is a measure of *how close to the pole* you would pass**.
The stars close to the pole are unavailable. The co-declination labels 'the maximum latitude'.
E.g. Sirius is 17° South, so rising from the horizon, somewhere to the South of East, it would send you to within 17° to the left of the South Pole.
Turn around and it would guide you (part way) to cross the Equator and to within 17° of the left of the North Pole.

Make a Bush Psychrometer

..for absolute humidity and dew-point-temperature measurements

Carry a wettable piece of material — dip it in water — hang it up to dry (in the shade out of the breeze) — time how long it takes.
Measure the air temperature at the same time, and cross correlate the two, to find the absolute humidity. If you calibrate the method at home, by graphing the results for a whole range of different temperature and humidity conditions, you will get to recognise a dry air mass from a moist one.
The piece of material needs to be non-porous, non-rotting and dark coloured — to show the drying process clearly, and to yield repeatable results.
Night-time minimum temperature more or less bottoms out as soon as an air mass starts to dew. The ground then wets down further instead of cooling down further. The normal method of measuring absolute air humidity—the percentage of water vapour—is by evaporatively cooling a water drop in it. It requires wetting a thermometer bulb, fanning it vigorously (trying hard not to break it) and measuring how far you can make the "wet bulb temperature" "dip" below the "dry bulb (air-)temperature". The water temperature won't get all the way down to "dew point"—the temperature at which dew or frost will form in that air mass—unless it already is dripping wet outside. It may get a bit more than half-way, and then only when only dew is expected—DP above 3° C. **If frost is possible,** i.e. when the dew point temperature is 3° or less, **it will dip at most half way down to the dew point**. Why 3°? Well, when the air is very dry, dewing will further reduce the water vapour content of still, cold air, from a dew-point temperature of a few degrees above zero, down to 0°—resulting in 'frozen dew'. **Rule of thumb** for calculating dew-point from dip:
When the DP is 40°C/30°/20°/10°/5°/0° then add to the 'dip' 0/1/2/3/4/5 quarters of the dip, to get down to the real dew point.
If the night is long enough and calm enough to cool down enough, & the sky is clear enough, a DP near zero will result in a frost.
E.g. 15° to 10° = 5° dip, 5°DP. 15° to 13° = 2°dip, 11°DP. 19° to 18° = 1°dip, 17°½DP. (Remember that you can't go far wrong anyway.)

South is a Triply Better Reference Direction than North, in the South

1. The closest geographic Pole in the Southern hemisphere is just over the horizon in Antarctica. Globally seen, all directions pointing South are convergent, whereas directions pointing North are initially divergent, and lengthy and less meaningful... Travelling North you first cross the Equator before it gets colder — so the gut-feel meaning is less clear. The meaningful direction, when you are in South latitudes, is to go further South to get much colder. (It is the same as in the Northern hemisphere, where going further North makes it much colder.)
You may find that in a place like Tasmania for instance, the maps seem to be upside down, because although North is at the top of the map, the logical reference direction is toward the bottom of the map, where the cold place gets colder. You don't think: "This is a warm place. In which direction does it get warmer?".
As a result it is easy to get disoriented by 180°, if you insist on using North as your reference direction. In addition…
2. When you put South at the top, and look South, then the Sun will move to your right, as if seen from the N.H., across the map as time passes, for both hemispheres—and that will make the clock-to-Sun link obvious (like putting a Southern clock on the S. wall to match the Sun's motion). Northerners especially, would find that a more natural way to view any map—as if from further North, looking South, to the Sun moving right.
3. Putting South at the top, with the Sun & Tropics behind you, looking down onto a map, is the mathematically standard viewpoint
— like looking from the top of the Galaxy — from North to further South — the land South of you moves Anti-clockwise, to your left, to the East.
You can still orient your map normally and correctly, but there is no law against habitually viewing it from its Northern edge, looking South. Try it.

Find East/West By Delayed Bisection of the Sun and the Full Moon At Rise or Set

To find due East (+/–10°): **Bisect the sunrise and the full Moon rise** — since they are of opposite declination.

For due West (+/-10°): **Bisect the sunset and the full Moon set** — since they set each side of due West.

Obviously, you need to wait about 12 hours for this method — it is really just for your background comfort level about where things are.
There is a slop of 5°, since the Moon's plane of orbit is about 5° away from the Ecliptic.
There is also a slop of about 24 hours, since the full Moon occurs at some time other than Moonrise or Moonset,
plus it is hard to pick an exactly full Moon, and the Moon varies in declination, i.e. North/South position, from day to day.



Find North by your (non-digital) Watch-Hands

Point the noon on the watch (**not the 12!**) to the Sun.
Tilt the watch axis toward Polaris as best you can judge.
This tilt matters a lot, but is not usually mentioned!



Southern hemisphere: **North is in between the Sun and the hour hand**.
Northern hemisphere: The Sun is in between the hour hand and South.
Why?: Clocks Go Clockwise; at 30° per hour — twice around per day.
For the Southern Hemisphere that means: — twice as fast as the Sun and opposite.
So 'in between' moves neither clockwise nor anticlockwise — it stays N/S. At real noon-time, the hour hand and the Sun cross over.
For the Northern Hemisphere, the hour hand overtakes the Sun at noontime, at South.
It's easy to visualise in fast motion, once you catch the idea — it's like the hare overtaking the tortoise.
Remember to tilt the watch-face up to be parallel to the Sun's orbit, not horizontal, because a sundial shadow is not linear.
You could use the middle of sunrise/sunset times to find the local actual high-noon midday time, which is needed for "point noon at the Sun".
The same method can be applied to the stars, the Moon or the planets — provided you know when the one you want to use is north of you.

Leo the Lion Looks like a Lion or Sphinx Squatting
It Has Four Lines which Show N./S. E./W.

Two in the 'hindquarters'; one along the 'back'; one as the stem of the 'question mark' (Leo's mane).
(You have to turn the '?' around.) For the Southern Hemisphere, turn it all upside down.

This is a good sign in Northern spring/Southern autumn.



(NH view — LEO is upright)
Direction of movement →

To Predict the Moon's Path, Visualise the Ecliptic

For more clues on how to visualise the Ecliptic, first see the overview at the end of this section.
The Moon stays within 5° of the Ecliptic. That helps you see where the Ecliptic should be, or alternatively,
where the Moon should be. The Full Moon is easy, and has been covered on p. 24d.
A **half-Moon,** for example, is 90° from the Sun; so if one is on the Equator the other is not and vice versa.
E.g. a half Moon in mid-winter will rise and set due E./W. +/- 5° or so.
Secondly, recall that the Earth's spin-axis is tilted 23½ degrees from the solar system.
This is how it would look from Sydney (*), at midday, in Midsummer, i.e. at Southern Summer Solstice…
The two great circles intersect at 23°½. The whole double-circle rotates West over 24 hours. i.e. sunset is at X…
To visualise the Ecliptic (see also p. 30d & 33b), from the Sun...
..Since the Sun moves eastwards seasonally through the stars you can know that
the part of the Ecliptic which the Sun was recently on must 'lead' the Sun to the West.
E.g. after solstice in Southern Summer, the most Southerly part of the Ecliptic is ahead of the Sun
to the West, and so a waning crescent Moon (to the West of the Sun) will be higher in the sky, on average, than the Sun. (SH)
E.g. A crescent Moon at sunset at spring equinox will look extraordinarily high over the sunset glow, because of the 23°½ tilt.



Bearings & Tracks: "If it is Right, it is Big, in my sight"

= Anything on my **Right is Bigger than 'ahead'**. I.e. If I am heading 100°, something on the right has a bearing bigger than 100°, e.g. 200°.
And "Any track on my **Left is too Little to look at**" = Anything on my **Left is Less** than ahead, e.g. 20°.
These mnemonics compare fixed tracks or directions, and their 'Big and Little' measure in degrees, East-around-from-North i.e. clockwise bearings.

[The changeover from 360° to 0° can give you trouble. Where 'ahead' was say 355°, 15° bigger should be 'big' e.g. 370° but will look really small, 10°. Because it is nowhere near 355 in number, there should be no possible confusion, provided you think of 10° as 370°.
'Little' may look really big, if 360° gets in between. E.g. where 'ahead' was 005°, 15° smaller would be –10°, which is the same as 350°, which is nowhere near 5 in number.]

Furthermore, if A sees B on his right, relative to a fixed direction, B sees A on his right,
provided that they use **acute** angles, or they look in **opposite** directions e.g. facing each other.
This could all get **confusing if you don't remember those two provisos**. See p108c for how to put this mnemonic into practice.

Find North from the Combination of the Sun and the Moon

When you are familiar with the path of the Sun and of the Moon, and with their seasonal movements, and with the Equator and Ecliptic, then whenever you see the Moon up during the day, imagine where the Sun's path lies in relation to the Moon's, and vice versa.

This gives you two concentric circles to visualise, which of course allows you to locate Polaris (at the centre of those paths), and from there, North.



See box d/e below, to know where the Moon should be.

Find Any Other Direction Too — Using the Hour Hand

This method works, in theory (there are easier methods!), for any other body — star, Moon or planet — or for any other direction.
For instance, you may notice when the Sun is due East, and how high it is; or again, when it is in the direction in which you wish to head.
Or again, you may be following a star, and of course it will move and of course you will wish to compensate for its movement.
In these cases you substitute the time of that body being in the chosen direction for "noon", and substitute the chosen direction for "North".
Keep the watch axis pointed to Polaris as best you can judge it.
For example: you know the Sun is West at 4 p.m. At midday it will look like this… (SH version)



.."Point the four to the Sun; West (or the chosen direction) is between the Sun (or star etc) and the hour hand"
The catch here is that you must imagine the height of the body accurately, before the direction can be found.
This is because the method only shows the rotational position of the body — longitude wise, not its height declination wise — and with the clockface being tilted, the horizontal direction being pointed out is not obvious until you choose a height.
Of course, the accuracy of the method depends also upon aligning the clockface to the Equatorial plane.

String North

Carry a piece of string, about one metre long, to **measure the angular height of the Moon, planet or star** which you intend to use later.
You measure it once, as a matter of preparation, then use it many times. The Moon goes out of date the most quickly, but the stars are permanent

Put a loop knot at one end, to hold the bottom knot, level with the horizon or horizontal. You may have to wait, until the height is clear.
Hold the string at arms' length in a vertical plane to the North-South, which is where the star will reach its highest point.
Put a second knot to show the maximum height. This is equivalent to the 'noon' height for the Sun.

For the Sun you could use the shadow, and hold the string *down* from the horizontal. It will be accurate for a week.
Better still, use the shadow methods soon to be described, to avoid the temptation of looking at the Sun.

Now at *other* times of the day/ night, first hold the string in a vertical plane to reconstruct the expected height, then hold the string horizontally from that same high angle above you. Lastly, twist and turn, so that the horizontal string apparently points to the body used — Moon, star, planet.
You have to **twist yourself until the string is *horizontal*, and at the right *height*, and *points to* the chosen body**. Then you are facing N-S.
Actually the method approximates a slightly curved small-circle star-path with a great-circle straight course.
You can find approximate North with the string, then adjust it slightly by imagining the actual star-path as a small circle around the Pole Star.
The straight string will then appear to point to just above the star, but in your imagination, it curves down to match the guesstimated star-path.
This is the direct sighting equivalent to the 'shortest-shadow South' methods on the next page.

A 4 Week *Position Cycle* of Moonrise/set, to Find East/West

The Moon, like the Sun, lies close to the Ecliptic (in the Zodiac), and completes a cycle along it (within 5°) in 27¼ days (not quite 28 days). So...
The Moon changes position in **a four-week cycle, like *a speeded up year***. It spends a week in each 'seasonal' position: High; mid; low; mid; hi...
The Moon crosses the Equator every fortnight, rising due East and setting due West that day. Find it! Use p9c to find E/W on those days/nights.
In alternate weeks it will rise & set in the Midsummer then Midwinter positions *for the Sun*. Get to know them, and expect each one every 4 weeks.
• Its change of rise/set position day to day is most sensitive near the equinox position, due E/W (be careful), and is least critical a week later.
In between times, the rise/set **positions can be guessed by the day of the week**, by interpolation, as a good direction guide on any day.
The cycle runs fast by only 1 day in 37 1/3 days. So it is a continuous guide to E/W, **for a month at a time**, as it moves through 13 Zodiac signs.
• The best way to **set your Moon-watch is by observation**. If Moon-rise/set is too late at night, then look for Moon-set/rise during the day.
Sunset Full Moon is a good starting point for estimating the nightly-cycle; Sunrise New Moon, for the daytime. Midsummer or Midwinter or Equinoctial full Moon are very good starting points, because the Moon will be in the anti-Sun position. Visualise the Ecliptic (through the Sun and perpendicular to the Moon cusps joined) and its shape in relation to the Equator, and use a compass. Say the full Moon is opposite the Sun on Saturday, but by Monday the Moon sets due West. Every Monday for *up to* 5 weeks the Moonset will be in a recognisable position. E.g. W, N-W, W, S-W, W. On a later Monday, you will need to step back one day and say "every Sunday, for five weeks" the Moon will repeat those four positions. Adjust yourself by one day, *as it shows itself necessary*. You can simply say "It is a Thursday Moon at the moment", expecting to have the change to "a Wednesday Moon" in a fortnight or 2. Keep your finger on the Moon-pulse to keep up-to-date. E.g. Say: "It's a Spring-type Moon next Tuesday".
• To keep track of the weeks, here is a recipe: **Call the new year e.g. 'a Friday Winter Moon'** and adjust 1 day every 37 days, 10 days over 1 full year, or by **4/5 of the completed months**. 7, 8, 9, 10 days for *after* 7-, 8-, 9-, 10-ber, using the Latin names; 0-7 days while *in* the rest, 1-8.
• Perhaps you lose track of a 'Wednesday Moon' for a couple of months, and try to start again. Track the Moon's Motion along the Ecliptic.
The Moon overtakes the Sun at No Moon, gets one season ahead of the Sun within a week, at 'the first quarter', is opposite it in another week ('full'), and is one season behind the Sun in the 3rd quarter. There are 12 and a third months in a year, so the Moon is moving 12 1/3 times more quickly around than the Sun, in its seasonal cycle. **What takes the Sun one month will take the Moon only 2½ days**. (31=2.5x12.3).

Step 0: Visualise the cycle. — I.e. imagine where the **lines** of the Ecliptic and Equator must be in relation to the Sun and Moon.
Step 1: Place the *Sun* on the Ecliptic — I.e. estimate the time of year, and from that, the time before/after the next/last **solstice/equinox**.
Step 2: Try to **visualise where on the Ecliptic the *Moon* must be**, according to its phase.
Step 3: **Interpolate for the exact phase**, and label it a 'Monday Moon' or whatever. Check your guess with a compass if possible.

E.g. There was an eclipse of the Sun on Tues July 22 2009, 1 month after solstice. The 'Winter Moon' must have been 'Sat night'; and for 2009 'Mon'
E.g. 23 November is one month before the SH Summer solstice (2½ days worth of Moon motion through the stars). You can work out, for any phase, which phase and position to expect in 2½ days. For instance, Nov 23 is late Spring, almost Summer, Southern hemisphere (with the Sun South of the Equator and moving further South). The Sun is high and getting higher. Opposite that, is a *Full* Moon position (North of the Equator moving further N). It stays low in the N, getting lower. Or if it is a '*First–Quarter* half-moon' at that time, it will be in the 'late-Summer-almost-Autumn' position (approaching the Equator from the S, midhigh in the sky). Or if the Moon is a *third quarter* half-moon, it will be in an 'almost Spring' position (approaching the Equator from the N). You would therefore know that, taking the last example, over the next 3 weeks, a Waning Crescent/ New Crescent/ Waxing Gibbous/ Past-Full Moon, will rise E/SE/E/NE, and set W/SW/W/NW, in approximately 2½/9/16/23 days.

Sun Path Norths — Summary

- Noon-time: You look at your watch to see how far the Sun is away from apparent-noon-time, then look at how far your shadow must be from shadow-South. Near noon, the (untimed) shortest-shadow methods below aren't accurate, but this timed method can fill in the gap.

- Chord bisection: This works for any body e.g. the Moon.
- Sundial methods: You set the sundial to the right time. E.g. tilt the compass protractor to the equatorial plane.
- Shadow bisection: This can work for the Moon too. Just remember to use a vertical stick on level ground, e.g. a dry puddle.
- Equal-height: You can use an improvised sextant/quadrant/bubble sextant. Don't forget to bisect both the time and the direction, carefully.
- Sun at East/West: You need to be familiar with the height &/or the time when the Sun is East or West.

- Equinoctial sunrise/sunset: You keep track of how far off East/West the sunrise/sunset is, at this time of year.
- Equinoctial rise/set angle: You can extend the Sun's path to noon, rise or set, in a straight line, using the latitude angle.
- Equinoctial East: Where the shadow moves to, with slight adjustments at other times of year.
- The Noon-shadow path is always to due East. This is useful for anytime *near* noon, say +/- 2 hours.
- When the Sun is *very high* near noon, you *need* to see the direction of movement of any point shadow on flat ground — West to East.

Locating Anti-sunrise or Anti-sunset

Imagine a line from your head-shadow, *opposite the Sun's path*, cutting the horizon at the correct rise/set angle p.9a.
(The Sun's path is approximately a great-circle, so now imagine a plane, edge-on along that line, cutting the level ground.
Look for where the shadow would be closest to you. This approximates the Shortest Shadow South…)



Shortest Shadow Souths ..from calculating, memorising or knowing the angle of high noon shadows.

• Walking-Stick North: You lean your walking-stick, so that at noon it would cast no shadow, and so that right now it casts a shadow at right angles to itself, a direction which is nearly West-East. Adjust (all these methods) slightly for the season, afterwards.
• Body-shadow South: You use your own shadow tip joined at right angles to your shortest-shadow tip (guess at its length and position). This works best in the early morning and late afternoon, where a guess as to your shortest-shadow is sufficient.
• Cardboard Triangle East/West: You cut it to point to high-noon height, like the walking stick & body methods combined.
• Plumb-line North: You tie a string triangle instead, to the right shape, and maybe attach it to your walking stick.
• Notebook North: You flip open one page from horizontal, so that it casts no shadow, and also points straight to high-noon height simultaneously. I.e. the page should be held at the correct angle, mimicking the Sun's maximum height.
You can discover the correct angle by observation, yesterday,
or you can calculate that angle as "latitude degrees minus declination degrees away from vertical"



*on a horizontal surface,
perpendicular is approximately East/West*

"Star-Time" Gains Four Minutes a Day

3 minutes 56 seconds actually, by appearances; (3m 56.555s if you use the almanac, and 'the first point of Aries', because "Aries" as it is known for short, is not a real star, and it drifts slowly through the Zodiac)
Stars complete one extra orbit — 360° — than the Sun in one year — 366¼ in 365¼ days — so that's about 1° per day which is 4 minutes of time.

By "time" we mean Sun-time "15° per hour on average", in ordinary usage — a slightly varying rate in practice.
By "star-time" we mean "15 and a bit degrees per hour spin rate — a constant rate"

The stars outrun the Sun, night by night, by 1° on average, so the Sun seems to migrate 'backwards'—to the east—through the Zodiac belt of stars.
You could say: **"The Sun drags its future after it!"**, meaning that the Sun sets in the West, but its future star-position shows up just to the East.

You can zero your star-time, by timing when a bright star (preferably one near the Equatorial belt) passes overhead, or north or south of you on a particular night from a known particular longitude. You then calculate star-time from "Sun-Time plus 3m56s per day since then" including part-days in your detailed calculation, at a rate of 10 seconds' time per extra hour — 1 second per six minutes.
Your reference longitude becomes like Greenwich to you — or, alternatively, you can adjust everything back to Greenwich longitude and Greenwich star time. You can also buy quartz controlled star-watches or calculators.

Adjusted Moon-Cusp North: To the Left or Right, By Moving the Sun

"Cusp-North" can be improved, by mentally moving the Sun away from the Ecliptic *onto the sky Equator*. Do the adjustment once a day. Guess the declination of the Sun, from the season; then shift it onto the nearest bit of the Equator and the Sun-to-Moon illumination angle may tilt a little.
Instead of pointing to the pole star for the Ecliptic, in Draco, the new cusp-North will point more to the pole star for the Equator — Polaris.
E.g. the midwinter Sun needs to climb 23½ degrees higher — which would tilt the cusps of the Moon (due to the shift in illumination). Diagram 1.
Caution: The illumination angle of the Moon does not change much when the *Moon* is shifted onto the Equator, and not at all for a half-Moon.
E.g. a half Moon (90° from the Sun) at Equinox could be adjusted by 23½° to bring it onto the Equator (It is like the Sun at Solstice), (diagram 2) but cusp North does not change. Being 90° from the Sun the cusps outline one and the same great-circle.



Cusp North moves to the right.



Cusp North does not move to the right.
Beware of perspective tricks

For the Southern Hemisphere looking into the sky…



—The Winter Ecliptic 'leads' the Summer Sun.
Cusp North moves to the left.

"By the Nose" Navigation

Our Mental Map is a Nose-Eye View — not at all like the bird's-eye-view given by a layout map. (See "Strip Map Navigation" p.95c)
Oh yes, our mind eventually fills out a (spatially-solid) layout map, but initially we collect a set of (spatially confused) mental photographs from all different perspectives taken from ground level. Our mind doesn't deal in map symbols or contour lines!
Rather it has search images, image enhancement, image recognition, three-dimensional images, and memorised **relative angles**.
Consequently, a more natural method of finding your way is what I call 'Nose Navigation' — almost opposite to mapwork.
Nose navigation uses 'strip maps' (Section 4), relative angles, and a couple of special mnemonics…

"Because (my shadow) seemed to shift right just now; Therefore *I* must have turned left"

Now substitute in the (…): Ayer's Rock/Uluru; That distant cloud; The Sun; The Moon; Compass Needle; East Wind; The RDF Null; That bright star
In other words: "My Nose Turns EVERYTHING Away!" i.e. when I turn my nose, everything else seems to turn oppositely.

This simple rule attacks head-on your insistent illusion that you have been walking "straight" ahead!

And your illogical belief that "Ayer's Rock has moved"! Neither has your shadow 'turned right' just now, simply because your nose 'hasn't moved'!
It is not as easy as you think to apply, e.g. when you are reenacting where you thought you had gone, in your (already confused) head.
The second nose mnemonic is on the opposite page.

Seasonal Adjustments For Equinoctial East

Shadows move due East at Equinox, all-day. At other times of year, when sunrise/sunset is not due East/West, the Shadow path curves slightly at an angle away from sunrise/sunset, an angle which you should become familiar with each week. Start by assuming that the shadow is moving "East"… Verify this **Rule: Shadow Paths Bulge toward the Hot Pole**, even in the tropics, in both hemispheres. (The Sun crosses at Sept 22 & March 21.)
Adjustment: The first guess at **"Hot Pole" Needs to be Adjusted Slightly,** less near noon, little or none nearer equinox, to "un-bulge" the path.



Remember that "the Southern Sun Sets Somewhat South in Southern Summer", so that opposite-Sunrise & opposite-Sunset need to come back South to point out E & W correctly
E.g. You guess East (or West in the a.m.) from the shadow's movement over 1 minute,
(It will roughly be opposite sunset/sunrise direction if you are late/early in the day)
then twist your guess a little back to the true hot pole, and to due East (or West).
Let's say it is midwinter in the Southern Hemisphere, so your shadow is somewhere S of you. The 'hot pole' is the North Pole, so twist 'North', as gauged from your shadow tip, away from the shadow, back toward you (i.e. North, to the hot North pole)
Visualise the bulge, then straighten it out at each end, back toward the hot pole.



North-Finding from Two Paper Triangles

or even from only one

Cut out a back-to-back triangle shape and fold it along the join. Line it up as shown and 'N' will point to Polaris…

'1' is your South **latitude** (For the Northern Hemisphere use the North Latitude and swap N & S)
'2' is the **polar distance** of the Sun (from the 'depressed' pole, N)
i.e. its co-declination, or 90°-N dec. See p. 18b.
You can set it by observation or calculation; and can fold it to the correct angle, rather than cutting it.
('3' is a right-angle, but '1' and the horizontal is what really matters)
This two-triangle method works best away from noon, but nearer noon simply find the way shadows move
The 'N-S' edge is parallel to the Earth's axis and acts as a hinge around which the Sun revolves.
Sun and shadows move at right angles to that axis.
You only need **one** of the two angles if you find the direction of shadow movement
and swivel 'N-S' to be perpendicular to that. (You don't even need one angle, near noon)



E.g. Poke a straight stick into the ground, pointing at the Sun, casting no shadow; (Or use any point-shadow rotating around its point)
By waiting a short while, find the direction of movement at a half-way point, in mid-air, i.e. maintaining an equal distance to the tip,
and manoeuvre your 'N-S' axis (index finger), to be perpendicular to how shadows move, then at the correct angle to the Sun and/or Horizontal.

Working the Star-Longitude Numbers

The reference star point, a non–star, is 0°N/S;0°E/W, and is called "The First Point of Aries" or "the Vernal Equinox" where the 'northern spring' Sun crosses the ecliptic (on March 21). Other stars are measured from that (imaginary) star, like latitude and longitude are measured from 0,0 a nameless spot of ocean — each star has an almost fixed longitude in relation to Aries.
N/S 'latitude' is called +/- ' Declination '
E/W 'longitude' is called (a) Right Ascension — R.A. — or 'Star Time' — It is measured **Easterly**, in hours at 15° per 'hour', from "Aries"
Or (b) Hour-Angle — H.A. — It is measured **Westerly**, in degrees, like longitude, but 360° around, from "Aries".
The first, RA, is designed to tell us the time — **when** the star will show — since all the stars move around westward with Aries.
The second, HA, is designed to track the West **longitude** of the star in reference to the Earth, as the star progresses West around.
We need them both, but they are entirely equivalent to each other.
(The only trouble is that a star 'hour' of 15° is slightly faster than a Sun hour of 15° of progress to the West.)
Next you need to know that the first point of Aries was at 100° W. Earth longitude at the beginning of the millennium,
and at every turn of leap-year thereafter, at January 1.0 (midnight). Then it gains at a rate of 1.002737909, or about 1° per day on the Sun, (3m 56s time), so that the stars turn full circle during four seasons. "1°" is adequate accuracy in the short term for us but not for yacht navigators.
E.g. January 31.5= 100+30°+0.5° W., then you add the H.A. (or subtract 15 x the R.A. hours) for a particular star — that's the longitude where the star will be overhead. **For exact numbers consult an almanac**, but I am concerned here with giving you an overview.

Topographic-Level Winds

This is what you feel in your face at ground level, or close to it.
Fog; Smoke; Valley Winds; Sea Breeze; Eddies; Catabatic Winds; Forest Winds; Scree-Slope Winds; Mountain Winds; Glacier Winds; Lake Winds.
The various thermal winds listed will of course be very variable. The thermal winds flow from cooler areas, before rising in the warmer region.
Nevertheless they may betray the slope of the land, for instance at night. For example, fog forms on calm cold nights then drifts slowly downslope.
Being dense, fog will drift down-valley, down-stream, and off-shore. You can see the location of creek outlets from the early morning beach fog.

The ground-winds due to pressure systems, are affected by overall friction and therefore average out slower and less Sun-twisted than upper-winds.
Ground-level winds form waves, foam 'streets', sand ripples & dunes, drag marks, snow ripples & drifts, which all may persist beyond the winds, and they cause lopsided bushes and salt-spray-'cut' bushes. See Section 3 for more details.

Gusts are at different directions to lulls since upper winds penetrate to lower layers.



"Nose-Navigation Needs an 'Anti' Mnemonic": "Nor-West, Not-Least"

N.O.R. West: "North **on Right** = Going West" or "Needle on Right = Going **West**" i.e. going into the westerly **half** (top diagram)
N.O.T. L.East: "North **on the Left** = Going East" or "Needle on the Left = Going **East**" = to the easterly **half** (bottom diagram)

This is always true when you are relying on "Needle North". **You don't have to think any further.** But,
It is equivalent to ANTI-CLOCKWISE BEARINGS, which you can't read from a clockwise-marked protractor!
The following numbers refer to an ordinary compass — marked clock-wise, and set to 0° as straight ahead
(not North) so North swings left and right instead… The compass needle might point to "045° NE"
Example: in the rain or fog; the needle swings meaninglessly but your nose is pointing NW
Example: deep in a cave network
Example: on a yacht, with a fixed hand compass The compass protractor numbers say "North-West, 315°"
Example: with a fixed car-compass, not marked anticlockwise but your nose is pointing NE
Example: making a strip map; or using one
Example: using a compass-holder, which fixes 0° as straight ahead Interpret "Anti-clockwise, West from 0"



Top Down Orientation

The Big Bang **Universe** bloated over billions of years; and broke into bubbles of turbulence; all bits in each bubble orbiting each other; in millions of galaxies, with 20 or so galaxies in our little **local cluster**;

Local galaxies, like the Magellanic Clouds or Andromeda, glow milky (just as 'galact-ose' says 'milk-sugar').

Our galaxy is a great spiral, swirling slowly, anti clockwise from above i.e. Eastwards around its North-South spin-axis — flat like a fried egg — a 'great circle', glowing as the Milky Way. The thickest milkiness, in Sagittarius, marks the Galaxy Centre.

The Milky Way is like the 'Equatorial plane' for the whole spiral, seen from within, with its northern pole star in 'Berenice's Hair' (28° N. 168° W.) and its Southern pole star in 'Sculptor' (28° S. 348° W. 012° E.) and our milky galaxy is, in its own turn, full of spinning, gyrating gyroscopes.

You know how a spinning top will pirouette with a slow-motion gyration when it tilts slightly? Well, precession, as it is called, causes slow changes.

Stars are Suns, especially shiny in our own spiral arm of the galaxy (i.e. closest) and seemingly set solidly in space by their extremely slow motion. So the constellation shapes are chartable for centuries. Their apparent positions are gridded out in relation to the first point of Aries, which in turn is fixed each year by our Northern Spring Equinox—not a star in the sky, but a point which creeps along the Ecliptic, to the West.

Hint: When you are wondering whether a rule holds in both hemispheres or not, ask yourself whether you are down at the level of the spinning Earth or up beyond that in a larger scale. Try to imagine looking at the whole globe from an outside perspective. E.g. the appearance of the Moon — its phase, eclipses, tidal forces, etc — is mostly independent of where we look at it from Earth — and will be the same for both hemispheres. But it's apparent path — 'noon' direction; rise/set angle; etc — is seen down at Earth level — it changes with the hemispheres.

Closer to Home

The solar system is also spinning flat, anticlockwise, but slanted — tilted like a top, in relation to the Galaxy, and faster.

Its 'top' star is currently in Draco, in the North. Its bottom star, in the South, is the larger Magellanic cloud.

Its 'Equator' is called the 'Ecliptic' — marked by the stars in the Zodiac, and the planets. In our lifetime we won't notice the Ecliptic stars change.

Our Sun circles the centre of the galaxy every 225 million years—heading toward Suhail.

To our sight, because we orbit it Eastwards, i.e. around its N/S axis, not ours, it swings seasonally, and also edges Easterly along the Ecliptic circle, revealing new zodiac stars to the West of it, and placing itself diametrically opposite a series of anti-Solar stars, so giving us a star calendar to look for.

It also spins easterly, on its own axis, showing its sunspots for some days at a time.

The planets lie planar, 'wandering' (as the Greek word plan-et says), in the Zodiac plane, circling easterly around the Sun, over a timescale of decades, and only ever seen very close to the Ecliptic.

Mnemonic: Son, my very earnest mother 'as just served us 19 platefuls. Sun, Mercury, Venus, Earth, Mars, asteroids, Jupiter, Saturn, Uranus, Neptune, Pluto.

The earth is an inner planet, **circling the Sun**, easterly, so that the stars seem to out-run the Sun in setting West — star-time spins more speedily than solar time. Planets closer to the Sun than we are, are never seen far from the Sun, but outer planets can move right away from it.

The Moon

..moves mostly on the Ecliptic but might miss that mark by as much as 5°. This 5° slant causes a precessional change taking 19 years to cycle.

The Moon moves around the Earth monthly in an easterly ellipse, and ever eyeing us, each full Moon, is the Rabbit, because the Moon also spins easterly, on its own axis, exactly once a month, so it stays facing us.

The Moon moves slowest to set Westwards, since it migrates eastwards in the sky each day. 12°½. Or **50 minutes later per day**.

And as it pulls the tides with it, they too are later each day, almost an hour, on top of normal locally fixed delays due to friction.

A full Moon rises and sets fully opposite the Sun, give or take 5°.

The Moon is most responsible for tidal forces, but the Sun plays some part too, reinforcing or diminishing the Moon's effect and changing the timing.

Tidal force attracts the nearest water the most, and the farthest water the least, resulting in two tidal bulges...

When the Moon is eccentric from our Equator, there is one big Northern bulge every 24 hours, and a smaller high tide every 24 hours, as the Earth spins through the bulges.

There are equal bulges every 12 hours on the Equator. In between are the low tides, every 12 hours.

You should be able to tell which bulge is 'nearest' the Moon despite delays due to friction.

Southern latitudes will have one big bulge every 24 hours, and one 'small high tide' every 24 hours, offset by 12 hours from the NH.

Try to correlate the Moon's phase, declination and height with the local tides—timing, inequality, range—e.g. "The Full Moon rises with the tide"



The Moving Horizon

Since it is the Earth which is spinning, not the Universe, it is **the horizon** which rises, in the West — where it eclipses the Sun, so that the Sun only seems to set in the West.

The horizon slumps in the East, so that all the sky things — Sun, Moon, planets, stars — seem to 'rise' in the East.

Any spots on the Northern half of the horizon, circle to the east around Polaris — clockwise through the sky — i.e. 'seen from below'. Or, seen from above, that is from the North, looking South, spots on the Southern horizon circle anticlockwise around South Pole Star i.e. seen as if 'from the top' looking down on the Earth and its South Pole star. They hit the same stars each night, at the same angle, which is related to latitude, so that the fixed stars none-the-less seem to trail 'small circle' tracks through our sky, and they always hit their favourite horizon spots when they set, always at the same angle, and those same stars will rise later in mirror image to that around North/South, giving rise to **north-south-east-west finding by bisection**.

And Equatorial stars will rise/set due East/West.

The southern-hemisphere horizons move to the right, the northern-hemisphere ones to the left. Looking South though, from either hemisphere, it will be seen as the horizon circling anti-clockwise around the South-pole star. How come? Well, the southerners see the bottom of the star-circles, around an elevated pole-star, the northerners see the top of the same circles, around a depressed pole-star.

The Spinning Earth

The earth is **spinning like a top**, on its own axis, easterly, half as fast as a '12 hour' clock.

This gives us **the single most dominant direction clue on the otherwise uniformly round Earth—the North-South spin axis of the Earth.**

Spot its Equatorial Plane by the Pot. The 'top' is always pointed to Polaris. Spot the South Pole Star by the Seven Superstars surrounding it.

The spin generates a magnetic core more or less North/South — Find magnetic North in far northern Canada.

The magnetic field poles generate auroral displays, anywhere near the poles.

The earth is also tilted like a top, at 20 odd degrees.

The tilt gives rise to seasonal Sun height shifts, somewhat like a sinewave (just imagine the Earth's tilted spinaxis not changing as we orbit the Sun) and it turns on un-twinned top-of-the-tide bulges, twice in 24 hours. The Pole Stars are latitude° down/up @ 0°/180° T.

Any tilted top will precess the equinoxes — this generates a precessional gyration of 26,000 years, but this time, retrogradely, i.e. to the West, along the Ecliptic (3° in 200 years) — i.e. the stars 'move' to the East through our star-map-grid.

Longitude has a lot to do with spin-time, seen from above the spin-axis. E.g. West longitude is how long after Greenwich, a place meets the Sun.

When we want to mark the apparent place of the Sun in the sky, or anything else, at any particular time, we can just record the latitude and longitude of the point on Earth directly 'under' it i.e. closest to it.

But visualising that in reverse, we simply **project the Equator and poles, latitude and longitude up onto the heavens to grid them out**.

Revision, Overview and Explanations

Time is counted in cycles

The larger the distance scale of any motion — pulsation or precession, orbit or rotation — the larger the time scale of the cycle of change.
The Universe has been expanding its size and condensing its matter for many billions of years (and perhaps it will not 'cycle') It appears static to us.
Geological history spans billions of years, like the existence of our spiral arm. In our lives we see only a frozen frame of our spiralling Galaxy. It cycles, but we can't see it. The timescale of the rotation of the galaxy is in hundreds of millions of years.
In our lifespan we see only the slightest change in relative star positions, through telescopes, due to the 'proper' motions of the nearest stars.
It is in the nature of spiral turbulent motion that the larger rotation replicates itself in the smaller scale, but at a faster rate.
Each of the components of our solar system are also rotating and orbiting in the same rotation sense as the Galaxy. (Uranus is an exception)
For example, the Earth is rotating eastwards, orbiting the Sun eastwards, and has a Moon rotating eastwards and orbiting us eastwards.
"Anticlockwise, as seen from the North" is the single best spin you can put upon all that you see—including the N/S Earth spin-axis as 'the single best direction clue on our spherical Earth'. The tilt of the Earth's spin-axis gives us the year, and the Moon's orbit gives us the month, independent of our rotation. The Earth's rotation gives us our day. Star time outstrips solar time slowly. The Southern Cross clocks it correctly at the close of March, and the Centaur soon follows. The first point of Aries gains a touch over the stars, migrating 50 seconds of arc along the Ecliptic per year. The vernal equinox arrives 59 seconds late for its 366th "orbit", after 365 days, requiring 24 leap years in 100 years. 365.242 days per year.
Atomic time, used for astronomy, is independent of all these tilted rotations, orbits and precessions, which are all independent of each other too.

The Precession of the Equinoxes

The actual or 'proper' motions of the stars are only of cosmological interest, because they change relative positions only over centuries.
But history, actually our slowly gyrating Earth-spin axis, rewrites our star charts (**im**properly, as it were) with precessional revisionism, so that stars 'move' slowly easterly through our star-map-reference-grid—an Earth-centred way of seeing the sky — with 26,000 years needed to complete a full circle precessionary Earth-wobble. This artificial motion is called "the precession of the equinoxes"— which means that our reference grid readjusts just as quickly as our earth axis of spin precesses — by five arc minutes in six years. That's why we need an almanac to predict the 'fixed' star positions!! A good analogy would be the slow drift of the north magnetic pole, **if** we set our latitude and longitude by it — that would yield a false or 'improper' 'continental drift' in addition to the proper continental drift. See the appendix at p. 123.
To visualise the Ecliptic, consider the Equator in the heavens to be geostationary, although invisible, but the Ecliptic to be like a sinewave moving daily to the West along it, on the video display unit of the sky—as on a cathode ray oscilloscope—with a period of 24 hrs & an amplitude of 23°½.
The Sun appears fixed somewhere along the Ecliptic, creeping 'backwards' on it (against the setting sky)—to the East—during the whole year
To visualise the precession of 'the Equinoxes', imagine that *the points where the Ecliptic sinewave crosses the* Equator (the x-axis), move 'forwards' ('with' the setting sky) — to the West, very very slowly — during the millennium. At the moment these 'equinoctial points' are between Regulus & Spica (the Autumnal Equinox), and between Diphda & Markab (the Vernal or Spring Equinox, or the 1st point of Aries, (0,0) for the stars).
You might say that the Sun and the Moon and the outer planets all move West through our sky but East through the starry heavens.

Global Weather Patterns

The spinning globe makes the climate zones, and weather belts, follow the latitude bands. When the wind tries to blow, from a High, into a Low, in the Northern Hemisphere/Southern Hemisphere you see huge anticlockwise/clockwise spirals instead, by Coriolis force. E.g. the wind, tries to go straight ahead from the hot spin-equator to the cold spin-pole while the spinning Earth slows down beneath it (it moves slower nearer the Poles).
In the North the wind therefore seems to "move to the right" as we see it, and in the Southern hemisphere "to the left". Circulation is the result.
Note: Winds around a Low go against the Coriolis force. To visualise the pressure system winds at low level, imagine placing two flat-headed screws pointing up, one on Japan and one on Sydney, an ordinary right-handed screw for Japan but **a left-handed spiral screw for the Southern Hemisphere**. Run your fingers over the threads and a right-hand thread is like screwing a screw in or out, a left-hand thread is opposite.
High pressure system winds screw downwards and outwards; Low pressure system winds reverse that—up, converging.

Higher level wind circulation reverses itself from that
because the convergence/divergence is reversed.





The Spherical Earth

The earth is curved round, like a globe, 360° round — 40,000 km around (by definition of a kilometre) 21,600 nautical miles, by definition.

◆ at 400 grads in a circle that's 100 km/grad ◆ at 360° in a circle that's 111.1 km/degree.

The Equator is a 'great circle'. Longitude circles are 'Great Circles' — passing through opposite poles, and perpendicular to all latitude lines.
Longitude counts 360° around East or West, or 180° East and 180° West from Greenwich.
Its North/South dividing lines mark out 24 one hour time zones of 15° each, and those North-South lines must converge on the poles, so that longitude degrees are of unequal arc-length at different latitudes.
Latitude has 90 equal degrees from the Equator to pole around the surface, which, by definition of the nautical mile, as one minute of arc, makes 60 nautical miles per degree of 'arc-distance'. 21,600 nautical miles must be the same as 40,000 km, so that's 10 km to 5.4 nautical miles. (2 to 1)
Latitude circles are 'small circles'.
We use them to divide the polar regions from the temperate regions (with the Arctic Circle, for instance, marking the limits of 24-hour nights); and to divide the temperate regions from the tropics (for instance with the Tropic of Capricorn, which marks the limit of 'high noon' fully overhead).
'Polar Distance' complements the 'Latitude' and reminds us that arc-distance is real distance.

Moving the Horizon

At the spin-equator, on a globe, the polestars must lie horizontally, and the Equatorial spin-plane must pass East/West overhead.
But move north/south to another latitude, and the earth being round, the horizon — which follows you, like 'up' changing with you — must fall and rise latitude-degrees, so that one pole star falls latitude-degrees out of sight behind you and the other one, ahead, elevates latitude-degrees above the horizon. The Equatorial plane must also fall latitude-degrees, behind you as you move, from being overhead. Other star-latitude (declination) circles in the sky (e.g. star-trail circles) must also rise or fall the same amount — latitude degrees.
Now this same thing happens if you move in **any** direction, say ex degrees away, but for this let's just temporarily freeze the spinning of the globe.
'Horizontal' and 'up' must follow with you exactly ex degrees, and so the horizon now blocks out ex degrees of sky behind you, and reveals ex degrees of new sky ahead of you.
Looking side on, you will see the horizon **tilt** by ex degrees in relation to the old skyscape, lifting behind and falling ahead, of your direction of travel
Looking at the same star-time any night, will "temporarily freeze the nightly spinning of the Earth" for you, for star navigation.

Spherical geometry also means that if a place is 2° or 20° away from you, then it must also be 1° or 10° below your horizon — half the arc distance
E.g. the North Pole on Earth is ½ x (90° minus latitude°) below horizontal, and at 0° True.

END OF SECTION ONE

Navigation is More Than Navigating

Properly done, navigation is your chance to fit yourself in to the experience of walking through the land.
Why are you there walking?... Navigation zeroes in on the land. Do you want to see the landscape?... Navigation opens your eyes.
Don't you want to appreciate ecology and geography?... Navigate by them! Navigation stops you "drifting off" into mindless incompetence.
Do you want to remember the views and special places?... Navigation forces you to improve such memories.
So, achieve confidence when you are alone; tackle more difficult trips; lead others; call yourself "experienced"— navigation is the key.

Common Sense

Navigation skills invite you into the wilderness. The wilderness is a wild place! — a world of dangers. **Don't go**. But if you do...
..at least make sure your navigation skills are up to the task.
Likewise: Don't venture to sea with approximate star navigation techniques until you know exactly what you're doing.
Learn much more about standard astronavigation, before you experiment with new techniques.

Your Subconscious is Superior to Science!

Your natural abilities will do a better job at keeping you oriented. Your brain is a supercomputer.
That makes it subject to the "rubbish in; rubbish out" truism. Your job is to feed relevant data to your subconscious, not to feed, say, a calculator.

As far as important detail goes, your mind will 'go for the jugular'. Exact science will go for unimportant decimal places.

E.g. I can immediately guess "about 8 km away" far more quickly than any triangulation.
E.g. Will any numbers ever tell you how to recognise where you are? Or how to imagine what that peak might look like from behind?

So feed clues into your brain. It is portable, waterproof and teachable.

Don't leave your mental map behind.

Visual Assessment is Your Main Clue — Rely on It More

Since noone navigates well when they "can't see where they are going", we must be relying on visual assessment most of the time.
The idea is to run with that fact of life, and make sure you have a good look when you can
(e.g. from the lookout; while driving up; at the crest of a ridge; at the waterfall; on the bridge; in the riverbed)
Further, bring to conscious focus what is normally subconscious, in what you see.
And aim to remember what you saw. (Draw it; take notes; talk it out; use visual memory skills)

A What-to-Look-for Checklist: How far is it to the skyline? Where are the Sun, sunrise, Moon, wind and North in relation to the skyline?
How does the weather interact with the land — wind, cloud base, Sun shadow, wind shadow, cloud shadows, haze?
Talk the skyline through — name its features. What do you recognise already? What does it remind you of?
What landmarks are visible? What distances to landmarks? What sizes of hills? What is the strike or trend of the ridges, ranges & valleys?
What angles between landmarks? What alignments? What valleys will your current path take you through?
What lies in between? What slopes & shapes are showing, especially for your route? Can you see the path ahead? Is it curved?
What difficulties lie ahead? What easier paths are there? What clear lines of sight are there? What alignments will become visible?
Can anyone see where you have come from? Could you recognise 'here' again? Can you see your destination or departure point?
How many different vegetation types? How high is it to the skyline in each direction? How does what you see mesh with the map?

Integrate: Jetstream, Earth Rotation & Heaven Rotation

Imagine your global motion. Tilt yourself and try (futilely) to oppose the supersonic speed of the Earth's rotation, as if walking upon a treadmill.
Aim for a Big Picture 'feel' for each local direction.
The idea is to go outside and walk through each of these motions until you **know** what it feels like.

(Both hemispheres)

When you are............	**standing still**	**or moving Westwards**	**or Eastwards**	**or Northwards**	**or Southwards**
(read down these lists, each in turn)					
The **Earth** rotates	Eastwards	rotates against you	rotates with you	to your right	to your left
The **Heavens** move	Westwards	slowly forward	quickly upwards	to your left	clockwise
The **high clouds**	jet Eastwards	zoom toward you	creep ahead of you	move to your right	to your left
oppose the heavens					
outrun the Earth					
You are being **tilted**	to the East	backwards	forwards	to your right	to your left
Lean oppositely	to the West	forwards	backwards	to your left	to your right

---

Measuring angles at 1 cm per degree



Hold the loop-knot below your eyeball

Make the total distance 57cm to 60cm

Use a ruler marked in centimeters

57.3 works best for small angles
60 works best beyond 10°

Orientation = Direction Sense

Oriental means "the rising" i.e. in the East (i.e. East from Europe!). Occidental means "the setting" i.e. in the West.

Because most ancient temples faced the midyear sunrise and there were no North-pointing magnetic compasses, and since all the world can agree on where equinoctial sunrise is, most of the rest of the world has used East, for most of Time, as their method of "orientation" — as their cardinal direction. Imagine putting East at the top of maps, so the Sun "falls down" the page.

Before magnets, East was the sensible choice for a standard direction.

This is no coincidence: "To the East" is also the watchword for the spin-sense of all our solar system parts. "North" and/or "South" is inferior

The direction of the *axis* of rotation doesn't tell you the *sense* of rotation; But the *direction of rotation*, gives you the axis of rotation *as well.*

East was the more sensible choice. You didn't lose orientation when you crossed the Equator; the Sun still rose in the East.

I recommend that you concentrate on this when changing hemispheres, and even now, to maintain your global 'orientation'.

Orientation means direction sense, direction finding, direction recognition, placing yourself in relation to over-the-horizon landmarks,

Or twisting anything (e.g. your map) to the right orientation.

Then again, it means starting off by getting your bearings straight.

Orienteering means athletes running through the bush.

Disorientation means... possible death.

The Navigator's Top 10 Problems; and Band-aid Solutions

1.	Not staying **alert** to navigation; not doing all you need to do……	**Talk** navigation; love navigation; practise navigation; **interpret** all clues
2.	Few **Clues** — E.g. Rain/Fog/Blizzard/Nighttime/Tall grass or dense vegetation/Look-alike landscapes	**Sit** still, until you can see; **go prepared** e.g. with a contour map; a compass; learn how to keep consistent courses
3.	Getting **Lost**	Remember the **start direction**
4.	Getting **Disoriented**	Be able to reorient; imagine the **Sun** in all situations; work top-down
5.	**Forgetting** the Way, the bends, etc.	Take a **notebook** and pencil; talk it out loud
6.	Losing track of **direction**	**Predict** the trend; use a **compass**; a notebook; integrate all direction clues
7.	Losing track of **distance**	Predict the timing; use a **watch**; use the map scale; and notebook
8.	Inadequate **Map**-Work	**Learn** how to use a map; study it first
9.	Not learning how to navigate	Take this booklet. **Practise.**
	Not knowing what to look for e.g. bush north	Practise being observant, at the expense of other preoccupations.
	Not **understanding** e.g. the lie, contours, heavens	**Teach** what you do know
10.	Choosing a wrong or difficult **route** E.g. a long "shortcut" across a dense gully	Get **directions** Don't 'shortcut'.

Reorientation

Reorientation is not an automatic body sense — it is an ongoing action.

"Orientation" in navigation is a misnomer, since it suggests some sort of initialisation, not to be repeated, rather than a continuous reprocessing.

"Re-orientation" is a more accurate description of what the navigator is involved in. Continuous reorientation.

Whether it is subconscious or conscious, it is something which must be done and redone, or else you are simply not oriented, now.

It is not good enough simply to be "good at navigation (theory)" — you must be putting it into practice, continuously, or else each bend will disorient you.

The essence of reorientation is conscious interpretation of the meaning of what you are doing.

This is, at the best of times, a bit difficult — like mental arithmetic — but it must be done, or else your brain will remain confused.

You may hope that direction sense would "become automatic with practice", but the last step of conscious interpretation must remain conscious.

And that is the process which should become second-nature. You must be aware, or you are fooling yourself into a false sense of security.

Delegating to your subconscious, is abdicating your responsibility. So bring yourself up-to-date, continuously, and...

Do not be overconfident. You are not oriented when you think you know where you are and where other things are—but only when you are right!

There are so many ways to make silly mistakes: confusing alternative systems; mistakes in numbers; forgetting your lessons; optical illusions; instrument errors; flawed theories; trusting approximations; misidentifying a star; making a logical blunder; and, of course... being overconfident.

Lost? Rule One: Stop! ..getting More Lost

STOP — so that you don't get deeper into trouble. ("When you get yourself into a hole, stop digging")

DON'T PANIC — Look for reasons not to panic "I can always walk all night, or sleep under that ledge,
or wait out the weather, or go hungry, or enjoy it…"

PRAY — He really does want to help the helpless.

SIGNAL — Shout 'Help!', 'Cooee', Whistle, Smoky fire, Heliograph, 3 of anything, SOS, CQ, Fire at night, Flashlight

LISTEN — for a reply.

THINK p. 37d

RETHINK — your journey

SIT It Out — = The Simplest Way to Beat the Fog. Gather fuel for a fire. Don't try to move — you may not win.

CAMP — choose a place that will be a good 'base' for further exploration.

SLEEP ON IT

STAY — in the area, where you can be found, e.g. on the track, at a hut or intersection.

PLAN — Implement a pre-**thought-out plan** e.g. Stop, Think, Navigate, Camp, Retrace, EPIRB, Stay.

For a Start: Slow down — almost to a stop. Be slow, cautious and thoughtful, not impulsive.



360° SOS
Three quick turns
three slow turns
three quick turns
(with the stick vertical)

Point and Blink = 10% Shift

In the field you simply point and blink—If you focus in the distance, the shift is about 6 degrees, which is 10% sideways.

6° or 1 in 10 is a very useful angle to guesstimate. Point with one eye and finger, then swap eyes, to see what a 6° shift looks like in the distance.

For repeatability you should touch your two index fingertips as you point.

For accuracy, use a pencil tip, and know the exact figure. The instructions below will show you how to hold the pencil to get an exact result.

To put the Point and Blink method on an accurate footing, measure your Inter-Pupillary Distance at Arm's Length.

Stand behind a window, pointing through it at some distant mark on the horizon, with both your finger-tips just touching the windowpane.

Use one eye and the same-side finger; Press your fingerprint onto the window; Swap eyes and fingers, back and forth, moving only your eyelids;

Check your alignment—both your fingertips should appear to exactly overlap when focussed on the distant object. Press your second fingerprint onto the glass; Measure the separation carefully.

Because the pupil is not pinpoint, it matters that you measure the practical separation at the working distance. Measure that working distance carefully— from the corner of your eye to the window when your pointing fingers just touch it.

Compare the two distances; i.e. divide the interpupillary distance by the armslength; **expect about 1:10** or 6°; Find the arcsine of that ratio for better accuracy. Try it out on the length of the Southern Cross. Compare it with 3 fingers, and 4 knuckles, and your binoculars' field of view.

Measure again on a middle-ground object, as when measuring the sideslip of a yacht by pointing at the wake. Measure out the distances as a check

The "Good" Navigator. You.

If you like exploring, you can use that to advantage. Or maybe you are a good photographer, well then you will understand 'mental photos'.
Use your creative writing streak, in creating memorable names, or else, appreciate the action 'direct', carefree and spontaneously.

Perhaps you are the obsessive type — well then, it's map and compass detail which will suit you.

So whether you are the artistic type, using your visual dominance, or the cool calculating logical sort,
or maybe a 'thinker' doing a good job at planning, or a 'doer' doing, you already have many useful skills for navigation.
Don't talk yourself down.

Those handful of useful traits which are already within you, you can develop into an orientation sense.

Think out Loud

Your subconscious will be telling you "That's odd".
Your conscience will be whining "Something is wrong".
Your mind will notice, before you do, "That's new".

When you notice something talking inside you, you need to talk back. Out loud. Don't leave it 'inside'.

Internal Problem	**Antidote**
"Shouldn't we be there by now?"	Ask the others.
"Have we missed the junction?"	Discuss it.
"Why is the Sun over there now!"	Name the lurking enemy!

You Need Excuses to Stop and Have a Good Look

- If it is a local peak, say "Let's look for a minute while we have the opportunity"
- Declare a chocolate stop!
- Take off your pack, adjust the padding. Adjust your socks, air your feet, put on a Band-Aid.
- Get out the maps; Identify the landmarks. Draw the relative angles to other lookouts, for future reference.
- Get out the camera and tripod. Unpack your pack on any pretext — noone can move until you repack!
- Make a sketch, compose a poem. Start an interesting conversation.
- Go for a swim or wash some clothes.
- Cook your main meal at midday & keep the biscuits for the late meal.
- Camp there.

You Can't Easily Revisit Places Left Behind — unless you first spend memorable times there.

Visualise Familiar but Invisible Landscape in Relation to the Sun

You need to 'fill in the void' between the very distant reference, and what you can see, with what you know, but can't see.
I.e. When you get a clear view, mentally plot and remember the sky-to-land layout for later use. "If the hill disappeared, the hut would be *there.*"
Mentally reconstruct any view which is helpful. E.g. as seen from camp, or from the start, or the peak…
Concentrate on knowing and revisualising landscape direction trends. "If I were at home, I'd see the coast… *across there*"
Do this at various times of day, **paying particular attention to direction *trends* in relation to the Sun's path**.
After all, that's what our direction sense consists of—a confidence in the real directions just out of sight, based on what we can see.
Then, when you are 'bushed in' and you see the Sun through the canopy you can say…
"Ah! the road is running sideways to the Sun, the valley lies entirely off to the right, I must have swung around left, parallel to the ridge…"

Section 1 dealt with the Sun/noon/North in the global abstract—unrelated to the local detail.
Section 3 deals with the local detail in relation to the Sun.
"Land to Sky" (soon, p 38d) is specially for one time of day, and concerned mainly with particular landmarks, not whole trends.
But now catch up with the overall game—**the Sun's path, the local skyline, and the local layout are one piece for a substantial local area**, and you need to mentally integrate them, and carry them with you, to avoid disorientation.

Guesstimating Angles at 1 degree per cm

First find how to make your **arm's-length 57 cm**, e.g. by touching your fists together in front of you.
Next, start measuring in **centimetres**.
Find a 1cm wide fingernail—1°. Check that your fingers are 2° wide, for 2°, 4°, 6°. Are your knuckles 2 cm apart? 2½° for the big ones.
A small fist, with the thumb tucked in is 9°; 10° with the thumb showing; a palm is one 'point'.
15° and 16° may require experimentation. 20° can be spanned with the fingers.



The 'Blink of eye' method also yields 6° — point to something with your finger at arm's length or with something narrower, with one eye, and blink.
Larger horizontal angles can be visualised from between your feet of from overhead.

Initial Orientation is the Single Fundamental — The Get-Back Path

"Which way do I go?" is more important than "Where am I?/How far?/Where is North?"
"How do I get back to a familiar path home?" is the real need. That means you need to orient yourself **before** getting lost.
The single most important direction is **Start to Finish** i.e. Which way did you **leave** the car park? **From** what recognised point?
"Which way have I been **going**?" (if I had to backtrack)
Which direction did you **head off** in — **toward** what identifiable point?
E.g. "Downhill". The direction need not be horizontal. We function on 'paths' more than on straight lines.
E.g. "to the lake". The direction need not be relative to North; It does need to be something you can reverse.
E.g. "with the Moon ahead on the left" "the long way around" "to the opposite side" "away from the mid-morning Sun"

Taking a map and compass is good; A watch is nice; But the only really necessary bit of navigation you must take with you on a walk, to get you back when lost or disoriented, is... what direction you have travelled out.

Initial Orientation is the Single King Principle — and the rest may not be much help without it. See the mnemonic p. 111c for some help.
Which way you went is also the single biggest help for searchers—**tell someone** where you are going!

How I Manage to Get Lost or Disoriented

… **starting off** without paying attention … blindly following the track or the leader … taking a minor junction
… choosing a hard route — thick vegetation … going without a compass, or map … trapped by a peak or clearing (p.45b)
… falling asleep during a journey — a gap in my reckoning … waking up in a new place … not noticing the "end of track" marker
… inside a hospital complex, or a shopping centre; coming out … in look-alike landscape e.g. suburbs; losing the car on city streets.
… getting out of bed the wrong way or entering a town by a last-minute bend … talking; inattention; not noticing bends & junctions; losing track
… misinterpreting "directions"; forgetting them; being given wrong directions … hurrying; "short-cuts"; leaving the track
… on river-flats near river junctions and bends … preoccupied — with map-making! or any other task
… inadequate memory e.g. in caves, the way back, the many bends … stubborn psychological disorientation syndrome
… miscommunication between parties e.g. about how & when to meet … confusion; blunders (see list p. 39b)
… not enough knowledge of what to look for & how to interpret what you do see … visiting the Northern Hemisphere
… minimal input technique of navigation e.g. 'just follow the signs'; overconfidence … misinterpreting the map—especially the scale
… new tracks, not on a map … false identification of landmark features … losing confidence just short of my goal
… unsure of distance covered … navigating by creek junctions or minor dirt roads … blinkered by fog, darkness or thick forest
… wrong turnings; walking in an unintentional circle; overlooking junctions; not looking back … waking up on a dark night, 180° disoriented.
… too much new territory too quickly … negotiating thick bush without keeping orientation

---

Voice Your Thoughts — Don't Suppress Important Clues

When your silent auto-pilot notices something and tries to tell you… Say it out loud. That's the trick to it.
Tell someone. If you are alone, yes, talk to yourself. Bring it to light.
You can't remember the jigsaw bits later, unless you look at them now! **Subconscious thoughts flit away like dreams**, so express them first.

"Oh I didn't expect to reach this so soon!"	? Misidentified
"North seems to have changed. It shouldn't be out there!"	Disoriented!
"Hasn't the wind swung? Does anybody agree?"	? Are the others asleep!!
"The shape's not quite right"	Most probably because it's wrong!
"The markers have stopped"	? Off the main track

The same goes for run-of-the-mill clues. A forgotten clue is a missing jigsaw piece when you need it, so say them all out loud.
"We're crossing a divide — see — we are now going downhill"
"Creek number... four" "Marker!... Blaze!... Cut Branch!..."

Back-track in Your Mind before You Back-track on Your Steps

Lost?
"Don't Be Afraid to Think"
Spend time rethinking.
Try to reconstruct where you might have erred. Have I overrun my goal, or am I not there yet? Or am I simply off course to left or to right?
Did anything 'not make sense' on the way out?

- Work backwards from now, before you forget.
- Assess how successful back-tracking might prove.
- Don't ask "Where do you think…" but shoot for the details — ask "Why do you think…"
- Each of you should draw a mud-map separately, then come together, to compare recollections. Argue out the sequence.
- Back-track on your presumptions.

Detail the facts with a cool head and many problems will dissolve.

Distance using Apparent Size & 6°

The visual size of people, cars, houses, as measured at arm's length, varies with distance. You know how big they are already.
Blink your eye or otherwise guesstimate what fraction of 6° it makes, and multiply its size up by 10, plus for the fraction, to get the distance to it.
E.g. something one knuckle space wide is 3 times further away than if it were 6° big, and therefore is 30 times further away than its absolute size.

Visual Angle, Size and Distance

Find the angle, and multiply the size up by 60 in 1-per-degree. E.g. If something 1m wide looks 5° across, = it is 12m away. 0.5° means 120m.
Find the distance from the map, and work out the size from the apparent angle, by 1 in 60. Something 10km away, 10° wide is 10/6 km across.
Using 7/4 in 100, for accuracy because the angle is small, something 10km away and 10° across should be 1750m wide.

Side-wise Offset

Blink your eye at something in the distance, and it will shift across the background skyline.
Walk sideways, pacing out the distance, until it lines up with the new skyline mark. Multiply by 10 for the distance to the something.
Alternatively, mark the new position alongside the object, which the 'blink' indicates, then walk up to it and pace out the offset distance & ten-tuple

Don't Just 'Get By' and 'Make Do'

We all have a handful of techniques we feel comfortable with. We all get lost.

Most "How to" books necessarily are telling you how to battle uphill — against your natural incompetence.
This is doubly true for a "How to Improve" (your navigation) book!
E.g. 'Improve your memory skills'! Easily said; hard to digest.
Get used to the idea, and therefore embrace it — the idea that you, as a good navigator, should want to extend your familiar range.

Navigation is inherently a problem (of not being able to see around corners; of not having a magnetic sense; of not having excellent memory; etc.).
However humans inherently do have the potential skills to cope. But do you have the guts?

Memories are Made of Landscapes, Not Compass Needles!

What to look for is detailed later, but for now consider...
How to 'look' …

Use your compass and map vaguely! Approximately! Lightly!
It is safer to be aware of their meaning, rather than to be accurate but disoriented.

Imagine you had no map, no compass. No signposts. No highways.
"How did the pioneers do it!?" You learn how to not get lost; how to 'see' what you are looking at.

Once you get oriented, then you can bury yourself in the instructions on decimal places, for accuracy when you need it.
Otherwise numbers and recipes have an ability to preoccupy your mind and numb your thinking.

Treat your map and compass as shy — self-deprecating — and turn your piercing stare away from them to what they are pointing out to you.

You Need a Road-Map To Climb a Hill!

It is a waste of effort to realise your mistakes at the top of a hill.
"I wish we had brought binoculars" is all too common a regret.
"We must remember next time to bring all our maps"

You have few such opportunities to positively identify landmarks,
and so you should **take the chance to familiarise yourself with what each hill looks like from every other hill.**

But often, it is only your smallest-scale map — the roadmap — which will show you the big layout.

"Didn't anybody bring the compass??"

It's up to you to plan ahead, to plan on making the most of your efforts.

'Land to Sky — Sky to Land' Navigation



Step Zero: **Leave yourself out**, and your compass, of the scheme of things — so that the whole lifeless picture only changes slowly.
The result is simplicity itself — You see **how the Sun shines across the landscape**. Remember the angles.
Step One: "The Tower is ⋁ by angle, from the Sun as I see it"   Both change only slowly (or rather, seem to) as you move.
The Big Bonus is: You can keep track of all your bends, twists & turns, by the Sun & Land working in conjunction with each other.
You can locate a landmark easily through the vegetation — you know where to expect it when it shows itself occasionally.
i.e. You can always easily locate the tower/peak/etc, from kilometre to kilometre, in relation to the (now slightly shifted) Sun (or Moon, wind, cloud)
Step Two: "The Tower is < from my shadow" This allows you to walk away from the Sun, yet still stay oriented to the landmark.
Step Three: "**The Anti-Tower** is ⋀ ..from the Sun"   These allow you to walk away from the landmark,
Step Four: ..from my shadow"   yet still "see" where it is.
Step Five: Mnemonic: "The Landscape on the **Left** Lingers Longest in the Light" — its apparent movement as you walk, follows the Sun
& the Shadow's anticlockwise shift. (SH only) i.e. you don't need to worry much about time passing, and angles changing.
"But Landscape on the Right… soon goes wrong" — it 'moves' against the clock-sense of the Sun.   (Southern Hemisphere rules)
i.e. you need to **refresh your angles** more often during the day.   (NH: Left Loses the Light; Right is all right)
Step Six: Rule of Thumb: "**15 km away** changes at 15°/hour (i.e. at about the same rate as a low midday Sun) as you walk past it at **4 kph**".
The Sun shifts at less than 15°/hr when it is rising or setting — so try "20 km away/12°" to match it; and "10 km/25°" if the Sun is very high.
Yes, you should convert the angle to "ESE" or rename it "just S. of sunrise" for later, but **the idea is to use the Sun as it is now, not North.**

Grid-line Walk — Explore in a Square Grid Pattern



Guess the right-angles, well

This only adds 20% walking effort, but lets you know where you are, and how to get back,
and along a route of your choice, among many choices.
You need to judge a given distance, well, e.g. 100 double-paces; one minute; or 100m; or by pedometer.
Choose a **reference direction** as 'Up' or 'ahead'.   Sun-North; Compass Needle North.
Up-weather by clouds; down–clouds. A strong wind. Distant Hill. If needed, keep a straight line by marks.
Choose a **scale** to suit your ambitions, e.g. 100m squares (so that each 10m is an extra 0.1).
Try to cover a whole square at a time. Use 0.5, if needed, or you can cross at a diagonal, 140m long.
Count **forward and back progress** in whole chunks, as A-Z. G.5 means 7½ squares.
After Z comes AA, AB, AC. See p84b for making suitable mnemonics. **Don't lose count!** That's the worst of it.
Count **right and left progress** as +/- 0-10, etc. Minus simply means 'backwards' or 'to the left' of the reference.
When you have definitely decided to head back to base, remember the grid-reference. Stop counting.
Reset the count to Zero. This is easier than trying to count backwards, using subtraction, to get back.
Reverse the reference direction, e.g. to downwind, shadow South, compass South, and continue.
When you arrive at the original grid-count, you should be within sight of home-base.

Disorientation is More Dangerous than Being Lost

…because the same disorientation that will get you lost, may then get you more lost.
Orientation is primarily a mental picture — therefore **— Disorientation is a wrong mental picture.** It is one and the same principle.
So Disorientation really extends to cover more than direction sense, into bewilderment and logical debilitation!
You can be disoriented, deluded, bewildered and irrational about more than direction or position. E.g. You may misjudge which way is up/out/back.
E.g. you may be mistaken about the time of day, or the existence of a road, or whether the promised weather front has passed you or not.

'Lost' is 'I don't know where I am' which is different from disorientation, since position sense is independent of direction sense.
Again, you can know where you are on the map, but still be bewildered on the ground — not 'fitting in' even if direction-wise oriented.
Then again, you can be oriented, but lost — yet not necessarily worried or in difficulties — because you are oriented.
You can be disoriented unawares — even when you know where you are — i.e. not necessarily aware of the danger of loss of direction sense.
To be both disoriented and lost is most dangerous, but **it is orientation which stops you from getting lost**.

Orientation keeps your finger on the pulse. It stops you getting disoriented. In many ways it gives you a position sense too e.g. that you are in a particular catchment, downwind of a known landmark, up-Sun of the overall course. Orientation of the map puts the map onto the landscape—aligned to reality—so that the map can point out its riches to you. Orientation lets you know where you are, recognise places, & know the way back

---

Logical Blunders — Examples

Mistakes of category: "The last stream was flowing to the left" (Oops!)
"We have crossed the main road" (Now, the main access road is dirt, whereas the main through road is bitumen,
but you muddle them up. Or maybe you are unaware of a fork in the main road.)
Mistakes of number: "We have passed two lakes" (which were joined behind the intervening vegetation).
Mistakes of quantity: "We haven't changed direction" (except for one hairpin bend!)
Ironstone may have swung the compass, when you put the map and compass on the ground 'for extra certainty'!
Mistakes of quality: "From the peak to the lake was 090°" — but the false peak you were on, gave you a false sense of accuracy, in the mist!
"See those houses 'across' the river?" — Rather, see the bend on the left — they are on this side!
"The island should poke out from behind the far point. Why isn't it there?" (It is 'the far point', of course)
"But we have crossed the River" No, only a main tributary, or only onto an island.
Gaps in knowledge: "We haven't seen the junction" — because you short-cut past it; around one bush is enough!
Unexpected: E.g. there are sometimes two parallel roads — the old & the new. E.g. a stream sometimes goes underground "Mole Creek".
E.g. A water canal may cross catchments. E.g. "Remember the creek junction at the base of the hill" — The 'hill' was only an island.
Assumption: "That will be the ridge we want up ahead, let's turn off here" — Unproven!
"Ah, we are back to the road!" Yes, but not the same road!

Trust the Untrustworthy

It's like people. 'You can't trust anybody', but you have to trust your life to them sometimes.

A compass has dozens of potential faults, but in a fog, you trust it, implicitly.
You yourself are less trustworthy than a compass.
When all you have outside your own opinions are reasonably reliable external clues (like where the Sun is!) you had better trust your life to them, not to yourself.
For instance, sometimes that 'external clue' is someone else telling you that you are disoriented, when you don't think so — you had better listen!

A disoriented person may not want to trust the 'untrustworthy'. Don't let that be you.
E.g. You may find yourself twisting the map to make it line up with a mountain which doesn't really line up, except to your expectations.
You prefer to believe that the map may be distorted!
It takes practice to believe. I once spent a whole week wondering why all the trees were pointing too much to the sunset side of noon.
I was trusting myself, not the trees, and was simply wrong about where North was. I didn't realise which was the more trustworthy.

Lost? Rule 2: Start! Getting Unlost. Find yourself. Regain confidence.

(After you STOP getting lost — Rule 1) It is time to **START NAVIGATING** — Rule 2. (You can practise this ahead of time, without getting lost.)
E.g. What can I see & recognise? E.g. Can I interpret the wind or sky or trees or drainage for direction?

- First: Mark your spot e.g. tie up a hanky. Mark your Trail—so you can get back here, as 'base'. Retrace your steps, if that is the best option.

Act out a Search & Rescue, looking for your 'lost' starting point. (If you can see your surroundings, you don't have to feel 'lost'.)...

- Explore in all directions systematically.
- Make a map. 'You' in the centre. Locate yourself in the landscape. Climb a high point, to orient yourself; at night too, for lights.

Let others find you...

- Leave notes about your plans. Especially at 'findable' places e.g. a hill top.
- Leave clues so that searchers will not give up for 'lack of clues'. Make some marks visible from the air.

Search out a track...
Ask: "Where should there be a track?" E.g. to... that peak?, a fishing spot?, any low pass through the range?, the main access valley?

Mental Grid Map

This is the square grid method, where you simply walk, along a path of choice, and rather than following the grid lines,
guesstimate your decimal position in the grid scheme.
The beauty of it is that it constantly forces you to orient yourself to a reference *direction*, to notice *distance*, and to be aware of *position*,
yet it takes nothing more than mental equipment. You should aim to practice it properly, once, and you may not want to discard it.
It causes less mental strain if there are two or more of you. **Delegate** the left/right to one person; the forward/back to another.
The one person guesstimates distances by one method, their way; The other gauges perhaps a different distance and with different accuracy.
It doesn't really matter if your guesstimation mismatches, provided you remain consistent and imagine a rectangular grid.
In addition you need a feel for triangle lengths, for a 1 in 10 slope, up to a 10 in 10 slope, so you can guesstimate decimals.
~You need to divert 5 in 10 to add more than **10%** to the length walked. E.g. from Z0 to A0.5 takes 112m across 100m squares.
~Maximum extra length is a 45 degree diagonal, at **141%**. E.g. from Z0 to A1 takes 141m. These two set the feel for guessing distances
1 in 9 adds one third. For 6 in 10 to 8 in 10, triple the first figure as the extra %. E.g. from A0 to B0.7 takes 122m.
If in doubt draw a 10x10 square, draw in the diagonals to each of 18 opposite points, and label the lengths as the square root of $100+n^2$
This lets you see the direction of each n in 10 slope, and know its length.
~You could use degrees, up to 45, and call them percent extra distance, with fair accuracy, but there's no need for such figures.
When I simply guessed, by eyeballing distances and directions, it brought me back home without noticeable error, after a few kilometres.

Walk Where the Navigators Talk — if you want to learn navigation

Not out of earshot.
Navigation is a learning experience.
It works better when you can share the process of learning with someone.

Explore

Explore the unexpected — the side tracks. You walk to explore, usually, not to exercise.

It's No Fantasy

Navigational know-how is not "If I were lost I could do this…" but is "What I am doing right now, all the time, will stop me getting lost".
Learning new skills and how to interpret all the clues is the practice of navigation here and now.
Continuously pointing out new clues to yourself, and to others willing to listen, is the process of not losing yourself.

Feed Your Subconscious through Your Conscious Focus

E.g. To improve distance guesstimation, focus on the finest visible distant detail. Notice the haze level, the shadow hue, the sizes you can see.

To train your direction 'sense' (which is entirely lacking in humans) feed it all the clues you can —
Sun & shadows, wind & weather, compass & landmarks, trends & bends… Don't just look at them! Put words and meanings onto what you see.

To extend your memory of a sequence of turnings… use pencil and paper 'memory'.

A working rule of thumb: **Bring to conscious note**
what you hope to keep track of subconsciously.
Don't expect to be able to remember what you haven't noticed or thought about consciously.
So learn what to look for, and how to see it.

Look into the Far Distance

..for Trig. Points; Towers. They are there to be seen, by definition. ..for Roads; Houses
..at night, for City glow; Auroral Lights ..for the dip and strike of the underlying geology
Assess the difficulties ahead, whenever you glimpse them e.g. a steep bank on the other side of a lake. Use binoculars.

Look through the Haze

What are you looking for? You want to pick: intervening ridges, hidden gorges, distant cliffs, overhangs, false peaks, mountains or islands, the Moon, and the trail ahead. Those cloudy lumps are not always clouds. Those invisible peaks are there to be found.

If you don't see them right away… Wait ..it is the **changing light conditions** which show up the contours.

E.g. Look at night, when the whole emphasis shifts, and light sources show up.
E.g. Wait for the haze to shift — it moves with the Sun.
E.g. Wait for the haze to thicken — to show up the valleys — weather is changeable
A rain shower may show up a valley; a cold front might clear the air of haze.
E.g. Wait for a cloud shadow or patch of sunlight to drift across — it will disappear into any hollows, and highlight any foreground.

Join the Invisible Big Picture To the Visible Landscape

The Big Picture might be invisible — e.g. the South Pole Star is "Over the South Pole in Antarctica" — but geographic "South" is quite different and is visible — "that knoll there!". Join the two!
The first principle to practise, is to work top-down; but the second and more important need, is to integrate everything.

When you put a continental or global picture onto the landscape, you have a full-scale map of the world in front of you.
e.g. Point just beneath 'that Knoll' and put your imagination into gear...Down over that horizon are icebergs separating from glaciers with a huge splash! Can't you feel the chill? Up there is the night-time aurora. Down there, anti-polar bears look straight up and see the Southern Cross whirling around overhead! And we must be on the south side — the cold dark side — of this hill behind us.

You say: "The destination lies beyond that valley." "Mount Saddleback marks sunrise"
"The track winds around behind this hill." "The Sun skims those treetops"
"Porpoise Bay must be yonder; Melbourne that way; and my girlfriend, 50km in that direction…"
Integrate as you walk — in real time and place

Cyclical Motion Divided into 12ths

Any back-and-forth motions or cycles which are caused by circular orbits or sinusoidal oscillations are easily understood and followed *in units of 30°*.
This is because 30° of rotation will swing *half way across* a radius from top-dead-centre, or half-way up/down from right/left extremities.
E.g. quick rising for 4 twelfths, then *2 twelfths* in the *top half* of the swing, 4 quickly reversing itself, and wallowing for 2 at the bottom.
You may not *see* the 'circular' nature of a one-dimensional oscillation, yet it will still conform to this rule.

Tidal Height	Sun's Seasonal Latitude (or Moon's monthly position cycle; use 2½ days)
1 hour falling slowly from the top	1 month at Northern solstice slowly coming South
2 hours dropping rapidly to midway	2 months rapidly moving back to the Equator — to the South
2 hours dropping rapidly from midway	2 months rapidly moving South of the Equator
1 hour dropping slowly to minimum height	1 month slowly approaching Southern solstice
1 hour at bottom rising slowly	1 month slowly turning back to the North
2 hours rising rapidly to midway	2 months rapidly returning to the Equator — toward the North
2 hours rising rapidly from midway	2 months rapidly moving North of the Equator
1 hour rising slowly to top	1 month slowly approaching the Northern solstice



You can simplify that into sixths, saying: "1 sixth *at the extreme*; 2 *on each change*; 1 at the other extreme"
Or say: "*twice as long on the change*". That makes 'the change' sound 'slower' but it actually goes *faster* and *for longer*.

Which Way Did I Come In? Which Way Do I Go on?

Have you ever interrupted your pleasant journey at a roadside picnic area and driven out the wrong way — back the way you came — and not onwards? Or you turn left instead of right when you drive "out" of a local dead-end network, into another dead-end maze?
Or you sat down for a rest on the track and when it's time to go, both directions look identical to you?
It's embarrassing on the road. It's nerve-racking in the bush! You feel struck with insanity. But it's normal enough.

Or when you come back to visit a familiar place, it's on the 'wrong' side of the river! Every time you come back?!

An extra external clue, like the Sun, is needed, and needed to be believed, but it is really needed before you make a fool of yourself.

And you may have to undergo 're-orientation' to dis-illusion yourself.

Don't let it happen to you deep inside a cave system!

Logical Presumption Leads to Utter Delusion

Think about those example 'logical blunders', about your own fallibility, about the dependence of logic upon its basic assumptions.
Being twitted by a logical mistake leaves you with a horrible 'lost' feeling, plus a pathetic 'helplessness' about how to reorient.

These are not simply mistakes of guesstimation, subject to fine-tuning!
Once you subconsciously make a decision about how the world is, then your mind will close to the possibility of error.
False assumption is presumption, so I say "**Presumption Means Delusion**"
Such Left/Right, Yes/No, crossed/uncrossed, 2, or was it 1? -type mistakes lead to utter bewilderment, so I add
"and errors involving discrete categories can be especially indiscreet!"

Being aware of the phenomenon of logical blunders, is half the battle in overcoming them, when they bite.
Keep an Open Mind about the truth of your assumptions!

Trust Less and Prove More

Don't trust yourself At numbers
Or remembering accurately
At judging time or distance
Or walking in a straight line
At identifying landmarks properly,
Or walking back upstream, and so on.
Don't trust A compass to be dead accurate
A map to show North reliably
The weather forecast
Old track markers
A navigational 'fix'
Complicated or finely adjusted instruments. They can easily go out of adjustment, without letting you know.
The point is not so much to **double-check** and **cross-check**, as to: **back-up** with an alternative; **interpret** for sense; understand; and **be wary**.

The Simplest Way to Get Unlost is to Retrace Your Steps

The sooner you go back to where you went wrong, the sooner you can relax. Yes that might be uphill. Yes it might be a long way.
"Oh I wish I had retraced my steps earlier, while I had the chance!"
You still have the chance, you probably just don't want to.
For instance, if you have been pushing on, hoping to find the way, you should be doubly aware of exactly where you have come,
since you doubly anticipate the need to retrace, if you fail.
"Short" cuts have a habit of surprising you at just how long they can turn out to be, repeatedly.
A track naturally avoids gullies and obstacles, so a 'shortcut' is almost guaranteed to hit one square on!

Retracing your steps may be something you can't short-cut. It is the shortcut. It short-circuits many other possibilities.

Caution: Sometimes retracing your mistakes will only compound them—more of the same!
You may sort yourself out better if there is an alternative system to try e.g. to walk back upridge if you got lost going downstream.

Approximate Sine-Wave Values 97% accurate

(From school you could have memorised that sin 30° is 0.5 and sin 60° is 0.866, and perhaps sin 45° =0.707 ???)
The first twelfth of an oscillation takes something half-way (0.5) to its peak amplitude (1.0) from the middle ground (0), by the rule of twelfths.
~*The motion is virtually linear for that first 30 degrees*. So to convert those *first* 30 degrees to a sine-value, **Divide by 60**.
I.e. add at a rate of 0.5 in 30, or 1 in 60. E.g. 25°/60 = 5/12 (or 0.417). Sin 25° is actually 0.423, which means we had a –0.006 error.
Sin 15° is 0.259, but we get 0.25 (–.009 error). Sin 20° is 0.342, but we would guess 0.333. That's about the maximum error, 0.01 low
The next twelfth carries the motion from half-way to 86.6%, in a curve; The extra is 36.6% or a slope of 1.22 per degree. Let's use 87,36,1.2
A linear fit cuts the curve twice, and so is close to most of it. If we could add 36%, over 30°, to 0.51, to arrive at 0.87, we get +/– 0.01
~To the ***extra*** degrees, **Add 20% ; Add 1; Call it a percentage** (divide by 100). (*To add 20%, add 1 tenth, 2 times*, e.g. 55 + 5.5 + 5.5 = 66)
E.g. 60 degrees = 30 plus an extra 30; so start with 0.5 and add 0.3 then 0.03, 0.03, 0.01 to get 0.87, which is 0.004 too much.
E.g. 40 gives 0.5 + 0.1 + 0.02 +0.01 = 0.63, instead of 0.643, or a –0.013 error. Sin 45 is about 0.5 plus 0.15 + 0.04 =0.69 or –0.017
To make the next approximation, use 0.87 for the first 60 degrees, then worry about any extra degrees.
The last 12th is the flattish top of the curve, building up to the crest. It climbs only 13.6% from 0.866 to 1.00 in 30 degrees, in a curve.
We start at 0.87 and finish at 1.02 cut the curve twice and best-fit to within 2%.
~For the last 30° degrees **Divide by 2, then 100**, to gain 15%, from 0.87 to 1.02.
E.g. 80 degrees moves to 0.5 then to about 0.87, then an extra 20 degrees or 0.1, yielding 0.97, 0.015 below the real value, 0.985.
75 yields 0.5 + 0.37 + 0.075 = 0.945, 0.021 below the true value 0.966. 70 gives 0.87 + 0.05 = 0.92, 0.02 below 0.940. I.e. +/– 0.02

Self-Motivation is Fundamental

For a sense of direction to become "second nature" you need to **train** your second nature.
Improved navigational ability boils down to… *putting new ideas into practice*.
(Not perfecting old mistakes! Nor leaving the right technique on the shelf)

Don't just know about a good idea; make it yours.
For this you need to want to improve your skills.
to force yourself to practise your weaker points.
to push yourself to develop new habits.
Which is fun.

Enjoy the trip!

How to Feed Your Brain

When and where does the Sun get up?
Get up and look (not at it!). Don't make it an academic question.
You don't need an academic answer, either. You measure it with your eyeball. Perhaps draw it.
That doesn't mean "ignore the details" but "memorise the feel".
You do 'measure' it, but not with numbers.



There! This early!

Star navigation? It doesn't have to be a "trigonometrical nightmare".
For us it means: Find the Southern Cross.
Guess the time of night.
Find the Pot. Get to know the stars.
Project their movement forward into the daytime.

Let your brain do the calculations. Show it what to work on.

Wait for a Change in Perspective...

..to reveal the hidden shapes and layout.

As you drive up, keep **re**-examining the changing skyline. Continue the process as you walk. Look for ridges & valleys showing up through the vegetation as well as on the skyline.
E.g. Use parallax to reveal a deeper horizon behind a hidden valley...
Keep your eye on particular bumps on the skyline.
If there is a deeper background, i.e. more distant, then a lump on it will show up by moving with you —
more quickly than a 'foreground' horizon. You may have to look through the deep haze to even locate particular bumps.

Climb a tree, or a hill.
Use binoculars. Look especially for the trail ahead, in relation to the terrain.

It is the **Changing Parallax** which **Shows Up the Landform** and its Relative Distances.

Landmark to Landmark Network Navigation

This is a permanent, unchanging, top-down, whole-region method, **prepared at home**, for a large area, and for particular walks.
1. Choose only **prominent landmarks** from the map. e.g. peaks with transmitters.
Add in major ports, mouths & coastal extremities, lighthouses, around the coast.
Draw the network of triangles between them. ("Which one am I inside?")
Draw the circumscribed circle for each triangle. ("Am I inside or outside?")
Label each line in **kilometres**. ("What does 20km look like?")
Label each horizontal **angle** in degrees. ("Does it look larger (inside the circle) or smaller (outside)?")
Label each line with its **trend**-direction. ("Am I to left or to right of **track**? Which is this river **parallel** to?)
On the right of a line you will be looking to the left of its trend to see one of the landmarks.
2. Keep a **notebook** for local peaks — smaller but locally prominent lookouts.
The idea here is to navigate only by landmarks, not by (favourite) low spots.
You don't have to worry about whether one landmark is visible from another.
The idea is that **even when you can't see a landmark** (as well as when you can),
you can know where it is and how it lies in the land layout, how other trends line up with it and with other visible lines, and *how you fit in*.



Larger angles inside **Map** (**Part of the network**)
Smaller angles outside (See Section 4)



Notebook

Name Each Clue — with solid ground

"That's Pacific Sunlight shining" — a mid-morning Sun, for Australia
"I have an Anti-American Shadow at the moment" — pointing away from North America
"It's a West Coast Cloud Flow" — you can't lose your orientation
"I love a Tropical Moon" — when the Moon is North of you (SH)
"That wind would blow straight in our back door" — 'Back-Door Blow'
"Downstream from here is uphill from Port Stevens" — 'Steven's Stream'
"This cliff sees the Southern Lights" — 'Cold Cliff'
"Topple-Tree Trunk would take us to True North"

The next step is to add something in line with that — see the next page.

Disorientation — A Killer Syndrome

Pilots have been known to fly upside down, or rigidly leaning to one side according to their mistaken belief about "up"!
If even our natural senses are unreliable we certainly can't afford to believe in any 'sixth sense' of direction, or on any unproven magnetic inbuilt direction-sense in humans! A trudge can dull & distort our senses. Your mind tries valiantly to maintain mental orientation—that is the problem.
Several times each year pilots die, scuba divers get lost in sea caves, cavers fail to find the way up and out, boatmen falsely navigate the fog, and bushwalkers get lost in the bush, fatally. They were not just careless; they were probably trying hard, but in the wrong direction, stubbornly.
Belief is an irrational master. Its force is stronger than reason. The conflict, combined with physical tiredness and sensory deprivation, is stressful.

We prefer to get lost rather than to rethink wrong assumptions!
We become willfully blind to strong contrary clues in view (including signposts, instruments, buoy colours and numbers!).
We magnify weak clues, to justify our delusion. This heightens the stress, because our sub-subconscious knows that we are wrong.
We actually lie to ourselves about what the clues do say! (e.g. we change the number, colour, reading or wording in our mind!)

Such irrational behaviour is explained as defending our psyche from hurt pride and from being devastated by confusion, fear and panic.
Don't laugh it off as "Oh, that's only for the worst case" because it is the less obvious self-delusion which will likely trap you.
Being human includes you — you definitely are vulnerable to being even less sensible than trained pilots!

Casual Outings Catch You Out

..unprepared e.g. without a map or compass or weather forecast.
Casual outings also have a habit (because exploring is interesting) of "I'll go just a little bit further"; and turn into longer than expected full-scale safaris. Exploring is built into the genes of a small fraction of any animal population—it's a group-survival insurance. But don't let it catch you out.

Serious trips go more reliably because you know what is needed, but you rarely prepare well for a casual trip.
e.g. you have no pedometer or notebook and so don't keep a good enough log of distance or direction.
So **Lesson Zero: Make some precaution** (to avoid getting lost) **every time** you wander off.
Another unexpected casual mistake is to decide to leave the track without thinking what precautions may be required.
Try this. Look up and repeat after me: "God, have I forgotten anything? Is there anything I should do first?"
Let someone know the single biggest clue: "I'm going exploring that way",
but then don't forget the unobvious catch—that person might also go exploring & not tell anyone where you went.
(Being disabled by an injury is one thing, but dying of exposure or thirst or wild animals, simply because no-one knows where you are, is another whole added dimension—that is probably the strongest reason for bothering to let someone know.)
So before you go off, pass on any vital information about others, as well as about yourself.

Trust Yourself Less

..when the compass and you disagree, for example.
When the map shows the junction there, but you reckon it should be here, for some reason such as 'but we've come too far!'
Or similar cases, of confusion.

Your reasoning sense has holes in it, big enough to outsmart yourself.

In the end you will usually conclude "Well, I was wrong, due to this very good reason(!), and it was how the map and compass told me it was."
But you don't want to admit it, at the time, until you are proven wrong, yet again.
Your reasoning is not, despite your worship of it, the highest god in the Universe. You need to be able to criticise it freely.

Unreliable as map and compass can be, at times, it is better to trust them more and yourself less.

More is Better — Thought, Time Care

A simple principle to apply is to do a better job at what is marginal.

For instance, "flat" ground nevertheless does have a slope which you can determine with care.
The wind may be gentle but a little extra time could make the difference between success or failure at determining its direction.
You can always double-check a casual decision, e.g. about which way the dry creek-bed flows.
Instead of wandering in an unrecorded meandering fashion, you can mentally log your changes in direction by lining up pairs of marks.
Just before you leave the track, a quick checklist can bring a few necessaries to mind, but only if you take the trouble.

A little extra thought; an adequate time-allocation to each task; more faith; and that bit of extra care—will solve a lot of problems.

Moveable Position vs Fixed Orientation

• It helps to park the car in a cardinal direction, or pitch the tent North/South, since we all rely on such clues to revisualise what we left behind.

• But when you do try to orient yourself to something invisible such as how the car was parked when you walked off, there is a simple trap to avoid

Don't imagine the car/tent as 'behind' you and twist its imagined *orientation* to suit the Sun or compass;
Instead change its *position* — *move* it to somewhere other than 'behind'.
Mentally manipulate its placement, not its orientation only. Or else the 'correct' orientation will confuse you — nothing will make sense.

Don't let the Sun 'change its direction' — that is a tell-tale that you are keeping the reference position fixed *behind* you rather than *moving* it as you swing to left and right.
Because we have no good tools to log changes of position or distance, we tend to neglect that half of the story in favour of maintaining orientation.

• As another hint on how to use a fixed orientation, e.g. North-South, so as not to let it 'change' in your mind, imagine it as a long, huge, high, iron girder bridge overarching you and your car/campsite, in the appropriate direction. Whichever way you imagine it, e.g. through-bolted to the continent, or from one peak to another, make it so solidly fixed to the ground and impressively immovable that you feel so insignificant yourself that you feel *you* must *turn yourself around* in order to pass under it.

Learn Think Look Integrate Integrate

Routine Mind-Shut-Down Procedures

You know how you become dull and passive — when being over-taught, lectured at, just entertained, occupied in repetitive tasks, sitting in front of the television, failing to solve too-difficult maths problems, or being proved to be a perverse idiot against your own opinion…
Automatic self-defence from constant attack... involves shut-down — into a semi-hypnotic trance.

Similarly,
Walking becomes a "trudge" after about an hour without a break, depending on the load, the heat, and how many trudges have preceded on that day, and previous days.
Pain-relieving opiate levels rise. Conversation takes a dive. The path sliding under your feet gets stared at a lot.
Your mind is passive, plus your body is on auto. It is physiologically involved in the hypnotism.

Mental Torpor is a navigator's constant enemy.
Keep the Different-to-Same-Ratio up, for both yourself and your companions, so that you can stimulate each other into full consciousness!

Feed Your Subconscious Subconsciously

E.g. Open your Atlas to a map of the world. Orient it and leave it open, oriented, and in view.
E.g. Place a magnetic compass somewhere in view at home.
E.g. Develop a habit to Orient your watch N-S each night when you take it off, wherever you happen to sleep.
E.g. Sleep with your head to the north each night if possible.
E.g. Clearly visualise what direction your feet are facing before going to sleep each night.
E.g. Imagine your body lying across a map of the continent.



New Habits Open up New Horizons.

"Retracing is Re-preciating"

..This memory-aid is something you have to tell yourself — to avoid blinding yourself and missing the goodness of the walk back.

If you are only titillating your senses for the passing instant, by constantly seeking "new" experiences, you will develop the mind-deadly
"Bin there — Dun that" attitude
Familiarity breeds contempt… "I know the way" doesn't guarantee that you know much else about the way.
The return journey degenerates into a dull, silent, often over-fast, boring, mindless trudge, even if you drove all day to come and see this top-quality location! In effect, you have walked the track twice, but looked at it only once.

Two solutions:
Take an interest in your surroundings, to overcome passive mindlessness.
Questions on your mind overcome boredom. If you have asked questions about a new place, you should be able to answer them on the way back.

Remind yourself of the opportunity to "re-preciate".

Aim to Integrate…

- ..Integrate daytime clues with night-time orientation—use the Moon, the place of sunset, the sunset glow later (which is further South—SH), the twilight Blue Band, Venus, the Ecliptic, the skyline — anything to carry you over from daytime to night-time, during that awkward twilight changeover phase.
- ..Integrate invisible landscape with visible landscape—work out what lies behind each hill, to picture the outside world against that skyline.
- ..Read the "map check-list" and specify what each item means from your point of view—if you didn't have a map, for example.
- ..Integrate the changing, with the unchangeable. E.g. the Sun's daily rotation needs to be followed, by naming its current direction. Same with the track; and your nose; and the wind.
- ..Integrate one walk with another — don't just carry two separate mental maps, add a third overall view.
- ..Integrate each system with each other one. E.g. don't let the map be one "world", while the walk is another, and the night sky a third. Join them into one whole.
- ..Integrate each direction clue with each other direction clue — E.g. "The tower is just before magnetic noon from here" (3 pictures in 1)
  E.g. the boat-radar may fail in the heaviest weather, unable to penetrate the rain squalls—you need a boat-compass too.

It is the **combination** of clues which stops you getting disoriented — if you mistake one, the others will alert you.

Notice and Match Up

'Notice the clues' is the easy half of navigation.
Sometimes it is as simple as seeing that the track is curved.
However, a slight curve due to a river bend can turn you in a hairpin without you realising, even if you *do* notice the curve.
Until you also notice the *extent* of the curve, you are at the mercy of disorientation. Something more than looking is needed.
You need something to orient to, like the wind or clouds or landscape.
Again, it does you little good to have *seen* the clouds steaming by if you forgot to see where they came from.
'Notice *and Interpret*' is the catch-cry, which never stops.
But when the wind stops, will you know what direction you have been going? And 'heading for the mountain' is fine, unless you lose sight of it.
Something more than single-clue orientation and interpretation is needed.

Do Notice; Do Interpret; Do Orient; Then ***Match up***; Link it to something else. And to something else. E.g. the clouds are from the mid-morning Sun; The mountain is on my shadow's port bow; The river has bent from 'towards the coast' around to 'away from the coast'.
For special examples, see '3 in line', opposite

Un-Dis-Oriented

You don't need to be perfectly and continuously oriented!

In fact it is quite hard to maintain an exact direction-sense, as soon as you turn your head, move a few steps, divert a few degrees, etc.**

You only need to be realistically confident of position & direction.

Hence **it is better to be roughly aware of many clues, than to aim for perfection, say, in location or direction**.

E.g. 'Moon North' is approximate, +/-60°, but awfully comforting! — It adds to a complete picture.

E.g. You may not even look at your map again, after studying it once, if by now you already know what it is telling you.

Don't aim to be perfectly oriented — just undisoriented.

E.g. Hold the conversation on how to judge range; what's behind the hill; where to find moss; why you can't yet interpret lichens; and so on… and you can hardly miss seeing the walk.

E.g. Run through the Start—Stop—Rest Mnemonic, p.110, as a memory challenge to all… "What's next in it?"… which has the benefit of practising all its clues too.

**As an exercise, guess, from a distance, diagonally, where the side of your house or car points to on the horizon, then go and line it up to find out Or guess which point is opposite that hillock or tree, then establish how accurate your guess was. My results: +/– 10°; +/– 30° when not trying.

Trapped! By Not Looking Back

A fish funnelled into a fish trap may never again find the narrow entrance hidden somewhere in the large perimeter.

Converging tracks and sudden clearings trap bushwalkers too, when they walk through an irreversible change without noticing.

"Where did our small track join onto the main route?" "Where did we hit the fence/road/pipeline/track, and turn along it?"

E.g. stepping into the creekbed, to explore upstream, is a one-way move—you may not recognise it coming back, and could overshoot.

- **Beware of all sudden clearings**.
  "Where did we emerge from the bushes: out into the clearing, onto the peak, onto the riverbank, out onto the beach"?
  Look for footprints — anyone's, but especially your own.
- Remember the phenomenon — and mark those junctions in your mind! Or even mark the junction on the ground. E.g. place a rock there.
- "Which tributary did we follow down?"
  "Which ridge did we come up on?" More on p.63b
- Log the distance and directions involved at such changes/junctions/clearings, before you walk on and 'lose track'.

Disoriented? Stop. Say So. Reorient!

Be prepared to voluntarily switch from 'certainty' to uncertainty.
Learn to live with fallibility.
As soon as you suspect a disorientation episode, admit it. Say so, out loud. Don't miss the chance.
Tell your brain off!

"You know you're just guessing! You made some mistake and won't admit it! Let's work this thing out together"

If you don't know that you are disoriented, that can be worse than being lost but oriented.
You don't even have to be lost — Even if you know where you are now, if you are disoriented, you may walk on into trouble, rather than be looking to walk out of trouble.

Recall how often you have experienced a hard-to-shake feeling of disorientation.

Lost? Rule 3: Do a Good Job — of walking out or staying put

It may not be safer to stay. Well, if you decide not to stay, don't be aimless in what you do decide to do…

- E.g. Retrace your steps.
- Keep a straight course — e.g. downstream; along the road; toward the mountain; to night lights; to the traffic noise; a chosen direction
- Be single-minded — purposeful, but not stubborn
- Leave a Trail — you may need to retrace. Yes, it consumes valuable time, but "don't get more lost"
- Leave clues; notes — for others
- Walk quickly if you must, to cover sufficient ground, but 'rescuers' may not be able to keep up!
- Yes, your exit strategy may need to be aborted, but at least nominate an exit strategy for the exit strategy beforetime.

In-Line Integration

Put your preparation into something useful by using the '**3-or-more-in-line**' interpretation method…

"The wind is blowing *from* Port Bluster, *over* Hot Hill, *past* the carpark, *to* us, and on *towards* the Sun.
"The Pacific Moon is shining parallel to the highway"
"The Mountain has Montague behind it, that cleared paddock in front of it, and that hillock in the opposite direction"
"The compass needle points past the Northern airport to the mainland"
"My anti-American shadow is pointing past Penstock to Point West at the moment"
"The stream is flowing from Mt. Big, down over Lake Low towards Mersey Mouth"
"That Tropical Sun is over New Guinea, shining Past Alice Springs, over the intersection to me, and into the teeth of the wind"
"The Nor'Easter clouds are flowing from Noumea, over the Main range, to here"
"That persistent pigeon is cooing from behind camp"

The effect is to turn your reference orientation directions into fixed tracks (see p71bi), making interpretation easy.

Navigation is Mental Work — Stay Alert

The tools to work with may be "map and compass" "line and direction" "time and distance"

But any workman needs, and needs to practise…

Attention Observation Analysis Interpretation Preparation Concentration Memory Visualisation

Specialist knowledge Deft application Reliability Right attitudes A store of safe and useful habits Coordination

In other words: **you get lost by lapses in applying your skills, not through lack of skills**.

Mental Equipment is Very Light to Carry — You already have it; Don't forget to use it!

Instruments Instruct the Intelligent

Don't let the instruments — compass, clock, protractor, map — do the navigating for you.
Rather, let them teach you, how to get by without them.

E.g. practise finding North by everything except the compass; then check your guesses with the compass. Try bush North repeatedly.
E.g. Guess at "adjusted Moon North", then consult the compass.
E.g. with a watch you can practise telling the time by the Moon.
E.g. before you use a protractor, guess the angle.
E.g. gauge the distance by eye, then check it on the map.
E.g. attach a sundial compass to your magnetic compass, for the sole purpose of practising & checking your use of the sundial.

In general, predict and guess before observing, and learn from the results.
You should **always check** an observation for good sense, and check any instrument, or any calculation — but prediction forces you to think **first** (rather than the go-to-sleep-first alternative — which is to always check afterwards).
Control your instruments — don't put yourself onto auto-pilot — or you will hypnotise yourself into blindness.

Look Back Regularly

Look At how you got here — so that you can recognise the way back if you need it — and can make sense of your walk.
At the change from one terrain type to another i.e. at the link between natural sections of a walk — after you walk through the change.
At the directionality of the sky haze down low — the change in thickness and colour.
At the colours of the leaves, lichens & flowers — they change dramatically upsun/downsun, and therefore forwards/backwards.
Look Back… At tracks joining in at an acute angle — which otherwise you won't see until you come back — which will confuse you.
At the bending of the track.
At what you may have dropped or left behind! (Check each other. Anyone carrying loose items should walk in front.)
At the distance come, compared to the distance yet to go.
At the weather clouds stalking up on you from behind.
Can you see your starting point, and get a bearing on it? What is opposite that — i.e. the landmark which now shows you your exact trend to date?

Look Around

Since turning your head while concentrating forwards, taking your eye off the ball or turning a smooth corner are all enough to thwart your direction sense, the anti-dote is to deliberately turn your head! Keep looking around at the wider context, including behind, so you don't lose sight of it.

Imagine an Aerial Photograph of the Continent

Visualise exaggerated shadows lying parallel across your imagined photograph — connect those with your shadow and tree shadows.
Visualise the Sun shining like a flashlight upon your imagined continent map — connect that Sun with the Sun you see (Don't look at it!).
Visualise the cloud shadows moving across it — there's one! See?
Draw the isobars across it, lined up with the low clouds wind direction — feel it in your face.
Superimpose a huge compass needle across the continent map — look at your needle. You should be aligned.

Usually you avoid using any small-scale map, since it is the real and full-scale world you want to see or visualise.
But sometimes, imagining a map helps, e.g.…

1. Your navigational map (i.e. remember what you studied!)
2. The mental continent glued to your compass needle, to help you '(not) swing the map'
3. The continental map you walk over at bends, to help you take in the new orientation
4. The bird's eye/satellite view e.g. when reconstructing where you might have gone wrong and when re-enacting it in miniature
5. Sleeping on a map, with your atlas open, and your compass needle showing
6. The Road Map marked out in Regional Triangles from peak to peak.

Making a M.U.D. M.A.P.-m.a.p.-m.a.p.

For a more accurate job, see Mapmaking p101c,103c,106ab,109c.

Mudmap your trip onto paper, because paper remembers better than you do. Use any scrap of paper. Take a pencil and draw you meanderings.
Orient the paper to your expected trend (p51a Rhumb Line & p111c S.T.A.R.T.), so as to give you most room to map your journey.
Mark a dot where you start from — probably on the edge closest to you.
Up-arrow for a reference **D**irection; draw in a long one, Up-Sun is good. e.g. Up-wind; Up-shadow; Up-peak to a prominent landmark; Up-Weather **D**irection. (the Cloud flow); Up-North, by compass needle, or Up-Moon. *Interpret* the reference-orientation-**D**irection(s) before you leave.
U-p**D**-ate the arrow direction(s) or interpretation as needed, e.g. as the Sun shifts slowly, in relation to the wind, or as you walk past the peak.
Maintain a trend, a straight-line 'leg' p73b. Use the reference direction if possible. E.g. use the anti-peak.
Or pick a distant mark and walk up to it somehow; Or line up two points and keep them in line (p85e,87e,89e); Or just guess.
Align the **A**rrow when you stop (See Map Alignment 97a-105a, 103b). Turn **A**round to see where you have come from, to map the directions well.
If all other direction references fail you, **Align the next leg carefully to the last leg**. Be careful, because this will accumulate errors.
A-lignment is the magic ingredient. But it is the extra reference A-rrow which keeps you straight and avoids those accumulated errors.
Interpret the new alignment before you disorient yourself: "Where then is the starting-point now?" — or else you have a map but no sense.
Don't forget to use the map on the way back keeping track of the bends and where the start point is, and the finish point.
Pencil in the **P**rogress **P**arallel to the last leg; Pencil in the last leg *distance*. Turn around again and pencil in the *next* leg *direction.*
Guess at the distance, or pace it as you go, or use a pedometer, or a **stopwatch**. Add helpful notes as needed — p95c, 122 might help.
Repeat the m.a.p. for each new leg.

Avoid Disorientation: OverNavigate

Your aim is surely not: ‘how to read a compass’ etc. But: ‘how to avoid a disorientation episode’
Being ‘lost’ is no panic, although you try to avoid that. Being ‘disoriented’ is panic (even when there is no real need).
To avoid the psychological syndrome and the real dangers of being disoriented, and lost, the most sensible attitude is…
Avoid getting disoriented in the first place Maintain orientation
Navigate carefully e.g. learn ‘how to read your compass’ etc.! Overnavigate — don’t rely on one theory, one skill, one faculty
Don’t give in to panic, or even to anxiety.

Over-navigating when you can, makes it easier when you can’t, e.g. sea-sick or injured, bushed-in, exhausted or confused.

It is a rule in life (Murphy’s Law) that things go wrong very quickly, not just one thing at a time, but all at once, compounding the difficulty.
As soon as you realise you are disoriented, you’ll probably also realise that you also don’t know the time, the position of the sun, the direction of the wind, the direction of the clouds, or whether you can interpret the bushes for noon. Then it begins to rain, go dark, and out come the leeches, and you sprain your ankle too. You could learn this law the hard way, or take my advice and do your ‘emergency’ navigating before the emergency!

How to Get Lost — Follow the Track— A Track is a Trap-Door

A track will lure you into the middle of the wilds. You end up depending upon it completely.
I suppose tracks know where they are going, but you may not, and they can’t think. They are mute guides of the blind.

Antidote: Over-navigate. Do more than you need to. **Don’t just follow the track mindlessly. Don’t let it do the navigating for you.**

Keep your finger on the pulse e.g. How far have I come? What speed am I averaging? What landmarks can I see?
Have I checked the compass lately? The weather?
STAY ALERT
STAY SKEPTICAL

Reorientation; And a Fresh Start

Step 0. Admit it: “I am dis-oriented!”. Say So. Stop. Decide to ‘reorient’. Discuss it out loud.
Step 1. RETHINK where you might have gone wrong.
2. IMAGINE the true situation.
3. IMAGINE A BIRD’S EYE VIEW of how it ‘must’ be. Lay it all out, on the ground, in your re-enactment.
4. USE THE MAP; and all the clues — the time, the clouds, the distance…
5. ACT IT OUT on foot, in miniature. “I left this way, turned…”
6. SAY OUT LOUD a) Well that’s where I thought it was b) But it is really over there (e.g. that Sun there).
7. Imagine the stars circling where they ought to; the coasts trending the way the compass tells you; etc.
8. Aim for a NEW START “I don’t know what happened, but now I divorce the past”.

Only when ‘the ground shifts under your feet’, do you know that your brain has got hold of the new situation.

How to Leave a Message

- Put it in a prominent place (e.g. a hilltop; a campsite; a rock face) with a prominent marker — bright and colourful for instance.
- Make it helicopter-visible e.g. in a clearing; large
- Use international distress symbols e.g. ‘V’; Fire; 3 lots. At sea, a white flag or white stroboscopic (flashing) light.
- Any bit of metal may help you scratch out a message e.g. a zipper runner; a coin; a key; e.g. onto a tree trunk.
  If not, try a rock, or stick, to scratch with. Next time, have paper and pen with you.
- Use spittle, or urine, to make mud, then cover the mud message, but prominently — e.g. when searchers remove the coat from the tepee they see the message. E.g. make a flat mud pie; press in twigs to form letters; keep the rain off it.
- A freshly dead leaf is like paper, to write on.
- A piece of charcoal makes a handy black chalk.
- Brittle Yakka gum makes a bright orange powder splotch, to attract attention, and can also be used as a somewhat waterproof crayon.

Disorientation in new territory

Familiar territory does *not* disorient you, so you must *have* the mental faculties to ‘know where you are’ when you can ‘see where you are’.
The overload of *novel* surroundings must overwhelm your normal abilities to mentally keep track of small diversions and accumulated progress.
These suggestions aim to make an exploration more ‘familiar’ and less ‘new’. They come from all over this book. I suppose the message is:
‘Don’t just read about the methods, take extra time and care to put them into practice; extra ‘bother’. Slow down; try harder. Remember more’.
Look back *very* regularly, to increase your familiarity of already explored territory. If you had eyes in the back of your head, it should *all* look ‘familiar’. Walk back over that territory before continuing, p 68b. It will feel like old familiar ground if you bother. You could find your way through, and back through, an obstacle course at night without a torch, *if* you went forward three legs and back two as a matter of habit or necessity. That’s 5 whole journeys. Talk to the obstacles along the way, and use a mnemonic to recognise them, and what you did about them, and how you turned.
Leave visible markers behind you, so looking back is more helpful to orient you. Leave a trail. It boosts your confidence, even if you don’t use it.
Look through the foreground into the distance to **maintain contact with reference directions**. Fix what you can see, especially ahead, in your mind, in relation to the Sun, shadow, wind, etc, until you can point to them from behind visual obstacles. Remember more of what you see. Interpret each clue for its relationship with your memories of how things looked. Integrate the bits into a whole. Use some distance measure.
Maintain a straight line if convenient, so the interpretation of where you are is transparent. Use long straight ‘legs’ so you can interpret your accumulated path more easily. Notice and remember the angles *between* legs especially. Create a mudmap, so you remain oriented to your start position, and to your current position, and to landmarks sighted along the way. Practise these and other techniques, when it doesn’t matter, for later.

To Work Harder, Rest Harder

"Mental alertness" may involve

- A siesta nap!
- An early night (not a late-night campfire party or sing-song).
- Regular rests during the walk.

Tiredness, Exhaustion, Constancy — these stop you thinking efficiently, and affect your memory badly too. So do nicotine, alcohol and drugs.

- When you are in difficulties, sleep on the problem, or take your mind off it with a diversion, occasionally.
- For the sake of having stimulating conversation, the whole party ought to guard their mental alertness too.
- Navigation games do more than orient you, they wake you up.

Be alert to your biorhythms—daily, monthly, seasonal—they affect your alertness or make you depressed—all your mental faculties can be affected.

Minds Work Best with Intelligent Questions on Them

- Am I judging the scale on the map properly?
- How many creeks have we crossed? How many more to come?
- What direction will the next creek be flowing in?
- What is the nearest escape route? To where?
- What does this place remind me of?
- Will it frost tonight or not?
- Where would the animals drink, and shelter?
- What is this place's own special uniqueness, and why?

How high and steep is the next climb?
What is our next position-check landmark? How soon?
Could we see Mount X from here?
What side-trips would people make?
Why is it sandy soil?
How fast are those cloud shadows going?

Anticipate, with questions, the things you want answers to.

Look Through the Vegetation, to the Contours

- Bushes cloud your vision. If, for example, you want to 'stick to the ridge', or want to memorise a junction, then look for the more **permanent** clues…
  ..like slope, creeklines, direction trends, terrain, soil & rock types, alignments, distances, context.
  Of course, look at the vegetation too, but not only at the vegetation.
- Trees cloud the skyline. But there are gaps and lines of sight that open up as you pass by. Look through the forest for the ridgelines, slopes, and horizon. As you move sideways watch the parallax—to reveal otherwise hidden contours.
- Look through the trees, to the **most distant**, largest, tallest features to navigate by — you will undoubtedly catch glimpses of these much more often than you think, if you are looking. They may be other trees, so get used to recognising individual trees.
- Examine the height of the sky beneath the canopy.
  E.g. the lowest sky is 'downhill', but **the lowest sky uphill** is toward a pass or gap, & **the highest sky downhill** shows up the ridge.
- Forest-bound **river beds** are often clear of trees and give you a rare distant view.
  Stop in the middle of that rope bridge! And hang around, to look around.

Connections to the Outside World — You Don't Need to Feel Isolated

Ruins connect you to the past. Earthworks and mineworkings also. Even the landscape engraves its history for you to see. A **GPS** connects you to satellites; a **radio** to a radio transmitter direction; a TV antenna points to the transmitter; a **phone** connects to the grid. The Sun, Moon, stars, planets + time + vertical can give you an **astro-fix** to connect you to latitude and longitude — globally. The **magnetic field** connects you to magnetic poles, as do the aurorae. The deep blue polarisation band finds the Sun for you. So does a rainbow. Navigational antennae link to flight paths. Flight paths indicate airports; pipelines indicate water supplies; electricity lines go to substations. **Paths** point to points of interest. Recent tracks betray traffic. Track-markers put you on track; tracks connect to roads; roads to highways; to cities **Nightlights** betray townships and cities; traffic noise links you to highways; surf noise, to the beach. Tides tell you about the Sun and the Moon. River gravel shows up the upstream geology. East West gully shape shows up North; **rivers** connect you to the coast; **ridges** to peaks. Air pressure here depends upon altitude; and upon the polar front and the pressure systems. Air temperature relates to the size of the landmass. Absolute humidity tells about the proximity of oceans. **Cirrus clouds** show up the (westerly) upper winds. **Low clouds** and winds remind you of the isobars on the pressure map. Ground winds telegraph the topography. The radio links you to **weather information**. Waves, to distant storms. Fence lines connect you to farms; boundary lines to survey grids; trig points to **maps**. Smells to camp fires, marshes, farms, abattoirs, toilets, seaweed, water. Stock trails lead to water; seed eating birds lead to waterholes; the plant and insect types are tied to their range and the region. Vegetation is tied to altitude, latitude and aspect. **Bush north** indicates noon. Bush slant indicates the **prevailing wind**. Recent wind leaves tracks of yesterday. Deep soil temperature is related to altitude. Why feel "lost"?

OverNavigate: Equals Over-Familiarise

Overfamiliarise yourself with your route as you walk it, the first time you walk it.

Familiarity is the navigator's best friend, next time.
I.e. Years later you can more easily retrace your steps. Even when the track has overgrown.
It is an investment opportunity now, not to be wasted.
The extra time and effort will pay dividends, but like all good investments you must have an interest in the future.

E.g. Notice how and where you went wrong — mentally photograph it.
E.g. Lay to heart the most permanent features — the landscape and trends — not the track, its signposts, or bushes, which may change with time, or with a bulldozer.
E.g. Mentally photograph the lie of each junction, as if a fire might burn up the signpost.
E.g. Describe out loud your short-term memory about how you got here, lest that familiarity flits with the passing of the day.
E.g. Have your own 'track-notes' book.

How to Get Lost — Follow the Leader

A leader is like a track. You can follow him mindlessly. He ends up being a seeing guide for the willfully blind.
Ask yourselves, often, this hypothetical question: What would happen if the navigator dropped dead?
Could anyone else navigate competently?
Do others know where we are? On the map?
Could I find my own way back? Where are the cars?
If the 'leader' himself gets disoriented or lost, noone will know where they are!

Antidote: Teach. Learn. Test each other. Involve each other.
Demystify the magic art. Share it. Talk about it.
Listen to the debate. Look at the landmarks. Contribute.
Don't walk fourth in line. (Rotate regularly)

"Here, you find the way — I already know it"

"As Solid As the Rocks in My Head"

"Who am I to argue with the Sun? to say to it 'You should be over there — not where you are!' "

Telling your head off is the sort of attitude you need… when you find yourself walking uphill to the campsite which you know is down by the river!
… when the clues are shouting at you "Something is wrong here!!"

Navigators who are disoriented prefer to believe in such remote but real possibilities as a compass error or a mistake on the map, signpost or buoy, or to believe in the majority opinion being wrong, rather than to believe in the closer and more real possibility: "Perhaps it is ME who has made some mistake".

True, compasses & maps are notoriously prone to error, but your internal feelings, vague recollections, position/time/direction senses are more notoriously unreliable.

Lost? Rule 4: DON'T Do It Again!

Make resolutions. E.g. 'I will always take a compass.' (I tie a key ring compass to my hat string and I always take my hat.)
(I also tie a whistle to my keyring)
E.g. 'I will buy a map/mobile-phone/EPIRB'
E.g. 'I will always leave my itinerary with friends'
E.g. 'I will learn more about navigation; take pencil and paper; practise'
E.g. 'I will never go on a walk unless I have asked: "Which way am I leaving; Going in what direction?" '

Even better… Don't wait to be forced into a sensible habit. Declare your present attitudes to be 'not yet fit for human navigation' and put it right, now.

Learn Think Look Integrate Integrate

A Three-Track Mind

Here is a trick to avoid attention-deficit syndrome in your navigating:
Practise concentrating on two things at once.
Your feet find the path by themselves.
Your mouth talks about how good the meal will be.
Your mind sees the scenery without missing it.

Dual tracking your mind is like many other good things — just a little bit too hard to persevere with under normal circumstances, but possible to achieve, with extra dedication.

Don’t automatically get lost into only one train of thought.
Slate this down for practice, for the rest of your life.

Interpret!

E.g. If you wear a face mask in these days of extreme UV radiation, or sunglasses, you become aware of when you are walking into the Sun.
The obvious interpretation, hanging on to this piece of otherwise subconscious information, is: “I must be travelling toward the Equator”.
It’s a chance to orient yourself to the new orientation. Can you see your shadow ahead of you?—you are getting closer to the pole.
E.g. You might be in a deep dark forest and see a rare bit of sun-dapple piercing the dense canopy.
That means you can go over there and see the sunbeams for a direction check.
E.g. The ‘crunch crunch’ underfoot changes to a ‘clop clop’ — “Oh, if this is rocky, maybe I’ve passed a break of slope.”
E.g. Exotic plants betray human occupation — you could look for an old access track.
As a general rule: **Look for any asymmetry**, and interpret it — usually for direction. E.g. When swimming with goggles, twinkly bubbles mean “upSun” — dull ones, “down-Sun”. The wave and ripple pattern indicate wind direction. Sunbeams show up the down-Sun direction.
E.g. Scuba-diving: The anchor rope shows up-/down- current; alternating current is the swish/swash from the longest wavelength waves—note their direction. Direct current equates with “away from my starting point”. Bubbles show “up” (with some adjustment for current if needed).
Interpret the whole story of settlement: Valleys attract farms, dams, fences, boundary roads, houses, access roads. I.e. you see a lonely fence post on a mud flat, and you say “once several paddocks probably converged onto this old watering place—look for old tracks near the fence post”. Look for old nail-holes in the post, to find out the direction of the fenceline.

Play the Field-Scientist

Vary your **focus-distance**.
A herpetologist will see snakes at his feet & frogs at 10 metres.
A geologist will see the skyline, and the creekbed outcrops.
An ornithologist will look upwards, a botanist downwards.

Scientists see more, because they know what to look for, and how.
The more they look, the more they see, observe, discover, and learn i.e. the more they learn what to look for.
You can begin the self-reinforcing cycle in yourself by: wanting an explanation, by trying an interpretation.
And, of course, don’t forget to look into the topic, into books about it and field guides for instance.
Be interested in all levels, in all scales and directions.

Focussing keenly will improve your navigation.

Orientation is More Fundamental Than Position Sense

We all carry mental recollections of recognisable spots—like a mental photo album.

But try to mentally picture whole stretches of a country—roads, coast, range, river—with a sense of direction & relative location & linkage.

Better is to carry a library of whole mental maps—walks, paths & layouts—not just photos of isolated spots or isolated linear features.

But Best is to keep all those maps in right relation to each other in your mind.

As your ability improves, you focus less on spots and more on the links between spots;
less on position fixing and more on trend analysis;
less on separate techniques, more on integration.
Direction clues are only helpful if you can coordinate them with what else you need to locate.
Positions only make most sense if you can say how they lie, in distance & direction, in relation to other positions.

Think in Pairs, in lines, trends and tracks

Two landmarks lie on a line, of known direction, and fixed track.
We tend to see things individually, and not see the join between them.
So try instead to get to know
the *direction* of ‘camp to that moored boat’,
the *bearing* of ‘Mt Big to Tower Hill’,
the *angle between* ‘sunset and the headland’
the *trend* of ‘Razorback Ridge’
the *pointing* of ‘tree one to tree two’
the *line* from ‘start to finish’
the *track* from ‘Lake Low to River Junction’
the *tilt* of a star-pair
the *join* of two subsections

Needle-North, -South, -East & -West. Identify them on the Landscape

One of the major problems of navigating in bush, is keeping log of estimated side-slip, distance-wise, even if you are oriented, direction-wise.
But you can see your sideways movement, see p53a, if you plot known directions onto known points on the skyline, (E.g. Magnetic N,S,E,W require no numbers; E.g. your initial forward bearing is already there waiting to be used). Or better, use points in the middle foreground landscape — about as far away as you intend to walk. E.g. local hillocks, towers, houses—things which will be visible from time to time during the whole walk, the closer the better. Make a note of their directions. Use these spots later to find home or your starting point. When you see them later, in relation to compass, you can visualise how much distance out there you have moved and in what direction. Page 106c "Tom Thumb Parallax" shows you how.

Orientation to Your Start-Finish (Rhumb) Line—by sight or compass

Work out the start-to-finish visual bearing to the destination if it is prominent, or to a landmark or point on the skyline beyond the destination.
Whenever you can see that point, you can see your left-to-right sideways positioning, in relation to the fixed track from start to finish.
A simple way to keep track of your sideways movement, at least in open country, is to choose an approximate rhumb line compass course (from start to finish) and watch it move across the landscape in front of you. E.g. "The follow-me arrow is now pointing more to the *left* of that gulch".

Orientation to Your Finish Point, by the Parallax Method

If you are making a one-way journey, use the same "parallax method" as above, to keep a log of the estimated sideslip, but use your **destination**, not your start point, for your reference set of bearings. As the walk progresses, you can see yourself closing in on the correct destination.

Exponential Anxiety — the 11:59 syndrome

Your fear of being 'lost' rises in inverse proportion to the need for fear, as you approach your goal in unfamiliar terrain.
Will it be there as expected? Why haven't I got there already? Surely it should have shown by now!
Have I overrun it?? Maybe I just didn't recognise it? Has it disappeared?
When will this track ever end? Will it end at all?? Will I have to walk all the way back! And so on.

Now, obviously, if you have done your homework well, it will be there, where you thought it was, but maybe not exactly when you thought, so optimistically, you 'ought to' arrive.
Distance guesstimation is our weak point.

Don't add needless anxiety to your background worries. Wait and see it sort itself out.

Anxiety, fear and panic work against good navigation.

Explore Junctions, While You Can

It only adds a few minutes' pleasant diversion to travel the branch tracks which you don't want. (Especially if you can dump a heavy pack)
You may never get to find out about them any other way.
This includes natural junctions—of creeks & ridges—and canal junctions.

When you are exploring, you may never retrace those exact steps, so don't say "I'll explore that on the way back".
The other reason not to say that, is that you will be even more tired later.
When you are uncertain of your position, such exploration ought to be considered "essential", now — not later when you realise your mistake.
Later you may speculate about what it might lead to, but now you can prove it.

In any case, as a matter of principle, explore far enough so that you don't have to repeat the foray
E.g. walk left, until you are sure you should not go left.

"Meet back here in 10 minutes" is one way to investigate in all directions at once.

Separated? An Agreed Plan Helps

Example: Where did I park the car? Is it stolen or am I lost? Are the others worried yet? What will they expect me to do?
Example: Our driver has driven off! Why? What will we do? What will he do?
Example: She has not returned on time! She was exploring that way.

Try these out...
"We will, for at least one hour and at most two hours, try to rejoin each other before changing to panic-plan"
"Where we were last together, is the agreed rendezvous now"
"After that we check our intended destination for messages"
"We know to communicate via a 3rd party—a 3rd person, a 3rd place, or a message bank… "
"..the nearest post office/petrol bowzer/pub/police station/emergency service/Fire Brigade/bank/Red Cross/Salvation Army"

Concentrate Outwards

Both introversion and extroversion belong elsewhere.
If you cogitate inwardly, you become blind to the surroundings.
When you chatter away about other things, that's equally distracting.

Don't spoil the special time of being outdoors.

While it is there in front of you, look to see what is to be seen — and talk about that — about the history of the place, or something about it that helps to keep you oriented, to its unique nature.

Learn not to be distracted from the main game.

SPELL Out Numbers — Into Words

The idea is to express, in words, what numbers measure. Humans hate hearing numbers! So translate mathematics into user-friendly words.
e.g. 270° is "West". That's much more meaningful.
10 past One — "Oh, it's midday!" (in your locality, for summer-time)
45° South — "sub-tropical, even temperate; halfway to the Pole"
10.5 km — "almost half-way"
020°T — just to the right of magnetic North.

PAINT your Words — Into Pictures

E.g. To make it even more meaningful, "West" = "Sunset!" (a word-picture)…or even better……………………
"019°" = "Where the Sun is just before it reaches magnetic North"
(This translates numbers into a familiar and visual time of day.)
"Midday" = "High noon!" (How high?) "Half-way" = "Within sight of the Gorge"
"Halfway to the Pole" = "The Sun rises and sets at 45°. The pole star is halfway up"

'Meaning' usually means a 'picture'

Words without meaning are like looking at the brushstrokes of an oil painting through a magnifying glass, missing the painting!

Here!
(Picture it;
Don't look at it!)



Look at the Ground

- Soil types; rock types (p. 79a)
- Animal runs; animal footprints
- Fallen track markers; toppled-over cairns
- Human footprints e.g. yours, on the way back
  Examine each other's boot treads, then the boot prints. Talk them through — expressing the recognisable peculiarities.
  Practise also on car-tyre treads and prints. (p. 66b)
- If you see a deep trench or a dry mud-hole in Tasmania, that may mean 'an old track' i.e. where constant traffic had refused to let the vegetation grow back.

Look for Foreshortening & Overlap & Parallax

Looking flat on to a shoreline e.g. the other side of the lake, means that any slight inlet or headland is probably a major and very sinuous feature. Focus sharply on it, looking for clues to depth. Don't just run on past it. Move sideways e.g. 20m, to show up the depth, by parallax.

Make Common Sense of the Various Direction Clues

Maybe the navigator has his eyes glued to the compass — but you, you can say "Oh we're just going upwind".
Perhaps you can see six landmarks — but the sensible way to see them is e.g. "We are heading halfway between Mount William and our shadows".
Cloud direction is a good clue, but changeable from hour to hour, so there is no loss in saying "Diagonal to the Sun" which is also changeable.

Don't Degrade the Point of a Clue or System

E.g. The point of a watch, is to tell you where the Sun is. (Don't look at the Sun!)
The purpose of a mnemonic is to remind you to think, not just to remember or to recite.
The reason for a "midnight-rise-noon-set" system is to work with the full-circle—even when you turn corners or turn around. It images the sky
The benefit of a skyline method, is for when you can't see the skyline. You will glimpse it 10 times more often, if you are trying to use it.

The aim of a practical method, is to practise it, not just to know about it!

The Aurorae

The Southern and the Northern Lights are especially frequent during high sunspot years (maximum every 11 years.... 2000, 2011, …).
They are most prominent after midnight. They are best seen in 'high' latitudes (> 40°). One to three days after a solar magnetic storm is best.
The most common aurora is the most easily overlooked — it is dismissed as a 'pale glow' in the North or South, low above the horizon.
But it is not dawn — that is East. It is not from a city — because it changes. Sometimes the sky will be pale green below and rosy above (between the clouds) and pierced by 'searchlights' which move left and right, slowly but visibly. Sometimes 'curtains' appear, shimmer and disappear slowly.
All the rays seem to emanate from somewhere near the North or South Magnetic Pole, and it spans 30° each side or more.

It is an interesting direction guide.

You can estimate current magnetic activity by analysing sunspot activity. **Never look at the Sun**. Instead, throw only an **image** of the Sun onto white paper, as follows... Point your binoculars at the Sun, **without looking through them**! Then, as if you were throwing a minimum shadow of one binocular barrel onto paper, and as if you will **let the paper look at the Sun through the binoculars**, from a distance of say half a metre from the eyepiece, point the big lens at the Sun. Adjust its alignment until the sunbeams go right through it and come out at the other end where the smaller eyepiece lens is. Steady the binoculars properly, and focus the bright, circular, white, image of the Sun so produced, carefully on the paper, by using the focusing mechanism and/or altering the paper distance, so as to reveal tiny pairs of black dots, on the paper. The larger the dots the bigger the storm. Caution! Looking at the Sun will damage your eyes and even looking at the bright image on white paper requires sunglasses.

Orientation to Your Start Point, by the Parallax Method

Step 1: **Start off Aligned**: Make a note of Needle-NSEW, bearings of any other recognisable points, initial-bearing landmark, rhumb-line landmark.
Step 2: **"The Direction Has Changed Its Mountain!"** Instead of saying: "The landmark has changed its direction", first say: "The direction has changed its landmark". I.e. retain in your mind the initial bearing, then, whenever you glimpse that landmark again, you can see how far sideways you have moved off that track—by locating which landscape point that direction now points to. You estimate the sideways disparity across the land, because your compass needle now points to a certain distance to one side of the original mark. Your job is to estimate that distance out there.
Step 3: **"I'm moving through the landscape, out there".** Imagine a thousand of you dotted all over the landscape, all moving parallel, and at the same speed, say, at 4 km per hour. All your initial bearings to all those recognisable spots out there, are moving with you, leaving those spots behind at a rate of 4 km per hour, and now those bearings point to new spots a calculable distance ahead. In reverse, this lets you see how far you have moved sideways to any direction. Bring those distances back to your feet, and see how far away from "start" you are, and how to get back. (At 15 km range, if you are walking at 4 km per hour, you will leave the landscape each side of you, behind at a rate of 15° per hour, but...) From the satellite's point of view, you and your directions are (all) simply moving through the whole landscape at 4 km per hour, no matter at what distance. An alternative viewpoint is to say that every bit of the landscape always moves "equal, parallel and opposite" to your motion, relatively speaking.
Step 4: **Estimate the gap between parallel tracks**—See "Advancing Position Lines" p.108a. I.e. from the initial bearing (a track) to the new one. —by taking a new bearing & using sin(change in direction) x new range. This converts the distances you can see, to a number of kilometres.
The answer, if you want an answer in numbers, is how far you have to travel at right-angles to the original bearing to restore the original bearing.

Nervous Nellie Navigation — Not Necessary

Anticipate a problem. Do something crisp about it. Clear your mind.

Examples: Continually looking at a compass needle — can be short-circuited — by dividing the route into short legs, p. 73b.
Continually gauging the distance covered — can be short-circuited — by making one prediction before you start, and waiting for it, p92b
Getting lost trying to keep track of many bends — is a symptom of not knowing the overall trend in the first place.
Continually guessing where that junction might have led to, is avoided, by exploring it when you meet it.

You never know when you may be totally distracted from your normal pattern of thinking — it is then that you will need a cleared mind.
Plus, if you habitually allow your mind to move on to the next problem, by dealing with the last problem, you avoid ongoing confusion.
Forethought can see the normal problems coming, and pre-empt them.

Look for the Essentials — the 'Directions'

You can't afford to miss them!
E.g. 'Turn left at the Y-junction' means someone has to be looking for it!
E.g. 'Head uphill after you cross the creek' means: notice the creek bed!
E.g. 'If you hit the main road you have gone too far' means that you were talking about lunch instead!

Directions are worth writing down as soon as you hear them: "First right, third left, 6 km, look for the track"
Try to give directions more sensibly: e.g. "Up Fish River Valley from the Park Boundary"
Try to use fixed directions e.g. "North West" "from the lake to the Peak" "between sunrise & Mount William"
Not variable or relative ones e.g. 'turn left'

A Whistle-Code for Contact Calls

Example: The track splits. It's probably just a detour. "I'll go left; You go right". You keep in contact by whistling, cheerfully & tunefully.
Use your favourite tunes agreed between you...

To signal: "It's me" Try: "I did it My Way"
"You Come to me" "Oh Come All Ye Faithful"
"I'm coming" "I'm Coming; I'm Coming… ..Old Black Joe"

The rhythm is...
Radio **Morse**: CQ = Please Contact Me = " Dah-dit-dah-dit Dah-dah-dit-dah " "C is Seasick, Q Forms a Queue" "Calling Calling, All radiOs"
R = Roger — Received = " Dit-dah-dit " "An R dits"
Wait = " Dit-dah-dit-dit-dit " "aWait f'r a bit"
S&R: Come Back i.e. Recall of Party = Dah — Dah — Dah — Dah "Ree-Call-All-Souls"
Other: International Distress = XXX = Dah-dit-dit-Dah — 3 times. "all X's hurt, all ex's hurt, all ex's hurt"
SOS — real emergency — di-di-di-dah-dah-dah-di-di-dit — repeated "A bit of Save Our Souls isn't it?"
See appendix for the full code.

City Glow

From out in the bush you can usually see the direction of about three cities or towns, by their night-time glow.
This works best in hazy atmosphere — virtually any night! — and especially on overcast nights and when no skylight will show.

You need to check a map before you go — for the nearby townships — then check the theory against the facts,
then you can find it useful when you need it.
E.g. you can hold a straight line at night — relative to any recognised glow.

Don't confuse it with aurorae, sunset afterglow, predawn Sunglow, Milky Way, asteroid belt (Zodiacal lights), headlights, local floodlights, bushfires.

Just remember to get up and look for what you normally don't notice.

Come to your Senses

..And it will be surprising what comes to your senses.
Smell the air — for seaweed, marshes, farms, abattoirs, smoke, smog, civilisation, scent trails, fresh wombat dung, humid air, perfume.
Listen occasionally. To help you hear, cup your hands to your ears. Selectively tune out the high-frequency noises to listen to the low frequencies; and vice versa. Listen through the white noise, and through the silence of night.

For occasional vehicles, trailers bumping, boats thumping, jets overflying, thunder rumbling
For constant traffic rumble of a highway
For ocean rollers thumping on shore. You can also often hear the difference between high and low tide, from the wave noise.
For running water, frogs
For wind noise
For generators, pumps, machinery
For farm stock
For the crunch under your feet, changing

Look **carefully**. "It is amazing what you can see, if you look". It is a most important habit for the navigator and is very rewarding.
E.g. you read what others have scratched over the sign that says "5 hours" and discover "8 hours"; or find old track markers almost overgrown.

TRANSFER Your Pictures into Reality

E.g. "Sunset" = "THERE!" even after sunset!



Find the red glow afterwards, further to the left e.g. at 8:30 p.m.

"High noon" = Look at how short your shadow is.
"Within sight" = "Well, can you see it yet?"
"The Pole Star is halfway up" = Do you see how the Cross doesn't set?

Living in the realm of theory is like an absent-minded professor — who can't find his way home, or remember which way he was travelling.

Put That Experience in Your Memory Bank

E.g. "The Pot will go down behind "Pot Hill"."
"I didn't realise how high the Sun can get at 45° latitude!"
"You can see the Gorge from the halfway mark, provided you climb the ridge"
"The Southern Cross keeps correct time at the end of March" — the beginning of Winter. See opposite for the next step…

Look, with Vengeance Aforethought

A bird observer doesn't just stumble into birds, he runs them down.
A native tracker doesn't simply 'notice' the clues, he searches for them.
Your task is to track down navigational clues, then bail them up.

Your enemy is: losing conscious grip on your task i.e. when the trudge gets the better of your brain.

For Practice: Express the unexpressed. It's no good to be only half aware of what is going on.
Interpret the meaning of each clue. It is no good staring at a compass needle, unless you realise where you are going!
Look outwards, to see what you can see.
Change 'a cursory look' into a specific search.
But, what exactly should you be looking for (once you have exhausted your repertoire of clues)??
Answer: Find out! I.e. **Teach yourself**. Don't wait until someone tells you.

Preparation is the Key to Difficult Navigation

Marine navigators in rock-strewn waters, or battling seasickness in heavy weather, or short-handed, know that the only way to cope with seat-of-the-pants reflex navigation is to have **already prepared clear instructions** about danger-bearings; back-bearings; lines of sight and distances to run, so that they don't need to leave the helm.

It is the total picture, beforehand, which orients you, later.

They need to plan the entire passage (so as to make landfall just before dawn, for instance) according to the tidal streams and ocean currents that they expect to meet (since it is the current much more than the winds which affect boat-speed-made-good, even for yachts). Their key desire is to sail with the current, and preferably with the wind and the weather systems, avoiding the storm-season. See "Aiming-off" p96a.

An hour seem such a long time to spare when you are busy at home; But when you get out on foot, relaxed, with hours to walk but no opportunity for desk-work, it seems that every hour not spent in preparing what could have been prepared, was a wasted hour, as far as being useful now.

Helpful Symbols for Standardising your Chart–Work



"The Deduced Reckoning Position"
from course and distance information
("Ded. reckoning, or D.R.)



"The Estimated Position"
taking into account currents and leeway
to distinguish it from simple D.R.



A known position, or a Fix



Lines of possible position should have the arrow on the end
e.g. pointing to a landmark
A central arrow means a course. i.e. travelling, not pointing.
One Arrow signifies the course steered through the water
A Transferred Position Line, i.e. advanced across the chart
Two arrows is the course made good over the ground
(A doubly transferred position line, for a three-way fix)
Three arrows is for the stream or the current.

Look Backwards; Think Forwards.

You sometimes, with only a mud-map to go by, have to follow a straight line by compass or landscape, to a low-lying, invisible feature, e.g. a tarn, hoping to come across it without bypassing it. Well, success will often make you feel that that is the end of the matter; “Mission Accomplished”. Until next time!

But look back, if you can, to a recognisable starting point, then take a compass or landscape bearing, backwards to the start.

You then convert that to a forward bearing for next time. Place 2 pebbles on the ground in line, turn around and line up the landscape mark needed

The result is a “track”, not just a direction — see p.71b — a ‘can’t–go-wrong’ guide.

If your beginning point is not visible, turn around and take a forward bearing on the skyline feature you think you should have headed towards (and probably did). E.g. “One span to the left of Mt. Visible”. The result is only a direction from the start—a guessed-at track—but nearly right.

On p.42d I said only to use bearings from high points to high points, for a general navigational framework.

But add to that, a mental or notebook entry of the bearing from a low destination point back to visible possible starting points, when you arrive successfully, or of the forward course you used — preferably by the landscape itself. They are “How-to-get-to (a low point)” tracks.

(Interpret)

Extend Visible Reality into the Invisible Picture

E.g. “It’s boiling hot in Baghdad”
“The Sun is over Townsville”
“From the ridge the water flows down to the Gorge and eventually out to the Murphy Mouth”
“The Earth must be rotating Easterly, from West”

Don’t be satisfied with half a meaning.

Until the interpretation leaves you oriented, and able to remember something, you haven’t gone far enough.

See p. 71b(1) for the last word on interpreting 270T.

To Get There Quicker, Go Slower

We all prefer to run ahead of necessary preparations, i.e. we prefer instant gratification to wisdom.

We also prefer to get something unpleasant, finished, and quickly, once we have started, e.g. “can we make this bad “shortcut” work out?”.

Don’t rush! “More haste, less speed” = More care, less fluster.

Slight panic makes you hurry. Hurry is a recipe for carelessness in navigation, and for blunders.

- E.g. over-running the junction
- E.g. missing most of the clues
- E.g. taking a foolish “shortcut”

Common causes for hurry, other than anxiety, include…

- “Let’s beat the rain/the dark”
- “Let’s get back on time/for lunch”
- “Let’s sort this out quick-smart as to where we are”
- “Let’s explore one more kilometre before we admit we’re lost and turn back”

Search and Rescue Signals — Noises Repeated Regularly

One = We are searching for someone. (Is it you?)

Two = I acknowledge your signal. “Okay; Roger received-and-understood; I heard that”

Three = “Search for me. I need help.”

Four = Recall of Search Party

E.g. rifle shots; loud whistles or horns; two boards clapped together

---

End of Section 2.

Nature's Norths

Learn these when the sky — the astronomy Norths — is clear, so that you can **lean** on them later. (Assume S. Hemisphere 1,2,3,5,6)

1. "Dew" North — Dew, moist soil & roads stay wetter in the shade. Frost will persist in the shadiest places, e.g dew South-West.
2. Snow South — Snow remains higher on the shady side of an obstacle.
3. Mud North — Half-dried mud-crusts betray the hot, wind-exposed cracked edges, with the damp mud in the shadowed places.
4. Rock Noon — a whole mountain, or a crack in a rock, can show up the sunny and the shady sides. (See next box)
   — Also, in the evening, after a sunny day, you can feel the colder side of a boulder or gully.
5. **Gully South** — The shady bank of a creek is steeper than the sunny side, at least on average, all around the world.
   The side facing the noon Sun is flatter. The side facing the pole is steeper. This results in roads, railways and buildings etc, being more common on one side—the flatter side—of an East-West river than the other. In other words, creeks tend to cling to the Pole-facing slope of a ridge, as if they migrate equator-wards. Perhaps this is a remnant of a past geological age when the erosion was more marked e.g. hot days eroding the sunny side flat, with ultra-violet light; and constant moisture and icy nights eroding the shady base steeply; therefore suitable mnemonics are: "lying down flat sunbaking" or "steeped in ice" (i.e. South-facing in the S.H.). Lakeshores have steeper or flatter banks according to the same principle.
6. Animal Orientation — "**Barnacle South**" (SH), on dark intertidal rocks — it shows up the wetter i.e. shadier side.
   'Anthills' (Termite mounds) sometimes orient to avoid the heat, so the length of them is North-South.
   Insects prefer the warmer side of a trunk in winter e.g. spider cocoons, ant colonies, boring grubs.
   Some spiders spin their orbs to face noon, like satellite dishes but more vertical; others face sunrise.
   Migratory flight-paths may be North/South &/or upslope/downslope. Animals flee in predictable directions,
   e.g. inland, uphill, North, upwind e.g. when faced with a fire. They often lie with their backs to a cold wind.
   Siesta South: Farm animals find the midday shade in a paddock. You can smell the urea. You can see the dung piles.
   (7—10 will be expanded soon)
7. **Wind West** — part of the W in the 'WEATHER' mnemonic. It is designed for windswept places when the wind is not blowing.
   The prevailing wind leaves its signature in the visible growth history of the plants, and in the landscape.
8. Wave West — if, in the Roaring Forties, you can see the accumulated effect of ocean rollers.

9. Botanical Asymmetry — where you sort out the competing effects of wind, light, salt, exposure.
10. **Bush Noon** — you never need to be disoriented in the thick bush.
   This works best in temperate latitudes — where the sunlight is directional.

Of course, anything to do with nature, refers to **averaging continual observations**. The most variable signs are the least reliable.
Less Natural Norths

11. Magnetic North; And don't forget magnetic dip — the downward tilt of the magnetic lines of force, varying with latitude.
12. Solar Panel Noon — Observe how we set up solar panels, and verandahs. Nature gives us the Sun, and we all follow it.
13. Satellite Dish Noon — Geo-stationary satellites are, by nature, Equatorial.
14. Microwave dish to microwave dish — Peaks 'naturally' point to each other! See "landmark to landmark network navigation"p42d

Instead of feeling bored, or getting lost, or being 'bushed in', you can have the valuable bonus of feeling at home in the bush, having a hobby, and being oriented to the slope, Sun, vegetation, ecology, weather patterns…
Bush skills are a good investment for future bushwalks. So go for some experimental walks in the bush on overcast, foggy, rainy days.

Don't Forget to Remember, Your Way!

Long-term memory is your best friend — so feed it. You aim for recognition, years later, through familiarity now
e.g. Have you walked the track at night? both ways? twice?
e.g. Collect as much first-and-second-hand information as you can.
e.g. Reread your track-notes occasionally before you lose the memories.
Photographs, Maps, Track guides, Track notes, etc are all permanent on paper! but you aim for permanent memories, not records.
I.e. Mental photographs, Memorised records, What the locals call "knowledge".
Use memory methods so you don't waste your efforts. Use the paper records to help you consolidate your local knowledge.
To that end: Make drawings. Make your own map. Keep a diary. Make your own track directions, names & comments. Tell somebody.
Use biro not pencil. Make a neat copy of your notes and file it.
"Look at…" means "Notice…" means "Take note" means "Take notes" i.e. Take a notebook.

Unlock Memorable Chapters in Your Life

Memory is fundamental in navigation (alongside direction, distance, position sense, visualisation and alertness).
Medium-term memory is how you find your way back, but aim also for long-term recall.
We remember best in definite 'bites' — location by location.

> "Right, team; We have to remember this. Help me. We need to discuss it, describe it, mentally photograph it, draw its skyline, make it a memorable stop, time it, note it, put it in its logical place in sequence."

Go for the Jugular. Zero In on What Matters

Concentrate on the crucial and take-away information
— the crucial "directions" E.g. the sequence of junctions
— the details that have direct orientation value E.g. the visual angle between North and Start-off
— which give relevant memories E.g. the hill-top view laying it all out for you
— track notes e.g. the bearing to follow, the "directions"
— the overall trend — top-down, top priority pieces of information
— the perspectives that fit everything into the context. E.g. the surrounding trends in relation to Sun-North.

E.g. A mental map is better than a 'position' on paper. A map diverts you from the real picture.
Recognition outvotes names; Zero in on the most peculiar visual peculiarity
names outvote position fixes.
The overall details — What you need to know in three years' time, when you try again,
are the **time, distance and difficulty**.
The Sequence (of subsections & features) ought to be remembered... ..rather than e.g. 'bearing 035° magnetic'
Recognising Sections of the walk... ..is more relevant than having a series of map positions.
Surrounding landmarks last longer... ..than "turn left at the red tin-can-marker".

Appreciate the plants and animals; the soils, geology and climate. Instead of "Bin there; Dun that" you aim for familiarity.

The "Lie" of The Land

Think of this as the up-down part of geography. Think "Lie-Down" (versus "Lay-Out" i.e. a map layout).
Think of — Drainage, Watersheds, Catchments & Divides—the accumulated results of Ages of uplift, drainage, erosion & deposition.
— Geomorphology — it determines the shapes
— Ecology — it responds to the shapes, the slopes & drainage
— and how they all fit into each other.
E.g. "This north-facing slope supports warmth-loving vegetation"
"These foothills of the main range drain Westerly"
"The basalt uplift has generated these clayey mud flats"
"This is an isolated hillock within the main valley"
Think of the 'lie' as 'down toward what general direction?'
and 'rise' as 'up toward what encircling range?'
I.e. Put a general trend on major rivers and ridges. Imagine the coast, where all the (now nearly parallel) ridges & rivers run offshore.

Lift your eyes to the "Big Picture" scenery. Interpret it; Memorise its detail; Put it to good use.

Listen to the Pioneers

I.e. listen to the place-names

"The Great Dividing Range"	I suppose this one is obvious
"Blackbird Flat"	This means there is a river nearby
"Stockyard Creek"	A flat clearing is promised
"North Ridge"	This is related to the North Arm of the River
"Huon Valley"	It houses the longest tributary
"Boggy Plains"	Down on the flats!
"Eliza Plateau"	Up on the boggy flats!
"Bright Pass"	Means a change of catchment
"East Pillinger"	It ought to be East of West Pillinger
"Pelion Gap"	A saddle — between catchments
"StrathGordon"	It says "the Valley of" Gordon River
"-Dale"	Also says "Valley"
"Mole Creek"	Burrows underground

Lie Has To Do with Water Drainage

Look for dips in the skyline.
If you find a 'soak'—where water soaks out—look for a ridge-bound marsh uphill—where water soaks in.
Carry an artificial horizon, to reveal slight down-slopes, e.g. a flat plastic jar lid suspended on three strings, adjusted to horizontal.
Or lay your clear plastic drink bottle on the ground. Maybe even pour out some water to see where it runs off to. Listen for frogs!

Stick to the Track

- If you are waiting for the rescue party
- When a "shortcut" looks inviting
- If you have told someone exactly where you are going
- When you are nursing an ailment
- When sacred or heritage sites are at risk from tramping and erosion, rubbish, pollution, desecration, etc.
- When you are one more tourist in the constantly invading hordes, and "Please keep to the track" is aimed squarely at you
- When you are in a greedy hurry for more of the same elsewhere
- If you can't find your way out of a wet paper bag.

Reasons for Leaving the Beaten Track

- Tracks often fail to meet the needs of birdwatchers, botanists, photographers and bushwalkers. Remember why you are there. Talk to the ranger about whether the "No Camping" sign refers to drunken car-based parties, or to scientists and bushwalkers too.
- You sometimes want to search out the worst routes! Easy slopes have one sort of ecosystem/niche/microclimate; Difficult terrain has the more unusual biology.
- Interaction with a bare-dirt strip is not exciting. Fan out, Tread Carefully, Go Slowly, Keep your party size small — then you can appreciate the flowers, lizards, lichens. Each step is watchful — which forces you to see these things.
- A fast-track through a nice place robs you of appreciation-time. The experience passes just as quickly as the tramping to get there!
- Designed tracks will often steer you clear of exactly what makes a place interesting to see — cliff-edge views, water-edges, botanical hot-spots, refuge habitats,…

Isolated places often don't have tracks, and you will need to choose, navigate and negotiate your own route.

Cross-Country Routes

All routes are 'cross-country' but some don't have tracks to follow.
There are two sorts of tracks — Un-natural ones—artificial paths (man & animal made) which form a simple network,
and often stick close to the contours — gently upslope or gently downslope
And — natural routes (following the geomorphology) which cross the contours at right angles and
which form a double network.
I.e. Natural routes are determined by an interleaved network of ridges and rivers...
You are well advised to stick to these routes if only for ease of route finding.
Then there are three sorts of off-track navigation to consider…
— departing from the artificial paths
— departing from the natural routes (to follow a trend to a destination) and
— trying to keep a dead straight line cross-country...



Rock Noon

Rocks blister and crack in the heat. In addition, ultra-violet light hastens all other erosion processes. The top sunny sides erode easily.
Conversely, the shady side is subjected to lichen growth, icing, and moisture, especially at the base.
Differential erosion results in tilted rocks, in asymmetry of cracks and gullies, and in various light and vegetation effects.



On the hot, rounded side, look for fissures, cracks, furrows, blisters and pock-marking — as signs of heat stress resulting in more rapid erosion.
e.g. Blistered flakes leave a patch of bare rock with no lichens on it.
Such patches are hard to find on the shady side.
Algae grow in the protected fissure under an almost blistered-off flake of rock.
The green stain on the underside of the flake is greener on the sunny side!

Caution: This is **unreliable** unless the rocks show a clearly interpretable pattern.
Of course, **use bedrock** or larger boulders, since they are going to be in their original position — not shifted about regularly.



Examine the cracks — The shady side is sharp and steep; the sunny side is rounded.
Just like "Gully South" but in miniature.



Examine the steps — sharp step-downs indicate a 'dip' in the layers down to noon.



— rounded step-downs show a geological dip away from noon.



Examine the colours — looking down-Sun you see pale, bare rock (where it has recently blistered).
— looking up-Sun you see multicoloured lichens on a darker background.
— diffuse lichen grows better on crumbly rock. The sunny side will grow such lichens.
— thicker-bodied, textured lichens grow older on the shady, non-eroding side.

Feel the topside vs the backside for a difference in temperature.
Look for green grass and moss in the shade of the rock. These are often far more reliable than the rocks themselves.
Beware that a fire-storm will kill lichens, moss & grass, and will blister the rock, crumble it and split chunks off.
i.e. some of the effects you will notice may be due to a recent fire, e.g. a firestorm from a particular direction.
Rock noon only needs to be reliable enough to tell you which end of your improvised compass points North.

Don't Try to Memorise Details without an Overall Framework

It's a recipe for confusion — to try to keep track of every bend, every hillock, every weather change, every creek bed, every channel.
There are too many of them. They all look alike in close-up.
So start with the map: Learn the **major** rivers and the divides first.
Go for the big names, the overall trends.
Fit the details in by retrospect, after the big picture shows itself.

Don't Try to Remember Anything You Haven't Memorised

i.e. put the effort in first—don't fool yourself. There is a process to memorising something, e.g. establishing a framework first.
And...
Don't try to remember anything you haven't made memorable. Don't battle uphill—make it enjoyable or emotional and it will be easier.
And...Don't write down anything you haven't memorised. First make it memorable, then write it down.
Notes are not an excuse to forget to memorise something!
Like most short-cuts, they are an enticing alternative, but they, like shortcuts, short-change you as well. Memories are precious.
And...Don't try to remember anything you haven't expressed or named. It is a fact of life that we refer to memories by name, in words
And...Don't expect to remember details you haven't understood, or organised, structured, or reduced to a bare minimum—a prompt.
It always helps to interact with, analyse and process anything you want to remember. E.g. investigate it with questions on your mind; criticise it; teach it. It also helps to visually set it out in your notebook with colour, shape, balance and symmetry.

If you relax, because there is a track, or because you have a map, or you have 'directions' for the trip,
and maybe someone else is with you who is familiar with the area, then you cease to build up your own memories and familiarity.
Again you have short-changed yourself.

Write down What You Memorise!

Does that sound like over-kill? It isn't. It's just good sense.

- Memory isn't perfect. So help it along. Do so before you forget.
- You will want to write down your track notes, for years later, anyway.
- Writing helps your memory — it "involves" you more — it stimulates your expression, revises your experience, adds time spent thinking about it, involves your physical participation and your verbal and visual faculties.
- You never know when slight stress (I'm lost!) will distract and divert you for an unknown time.
- To write it all down clears your mind of the previous task — you can concentrate elsewhere.
- On the way back you can easily glance through your notes and then know what to look for.



E.g. DRAW a picture of where the Sun sets on the skyline. LABEL it e.g. "Sunset @239°T @5:29 p.m."
Or was it 229°C @5:39? That's why you write it down.

Set aside a notebook for a "TRACK DIARY" (SH)

Major Rivers & Ridges, vs Minor Ones

Obviously, all water, falling on one side of a catchment-dividing ridge, runs to the sea, via a single river mouth; Conversely, river-mouth headlands are dividing ridges. Followed inland, all headlands must reach right around the river catchment—they are the two ends of the dividing ridge. The rivers and ridges form a sort of geometrically inverse pair of systems.
The catchments with the shortest creeks occur between named River mouths, and are called 'coastal'.
I.e. All other coastal land rises to some different, more local, dividing ridge; you may have to undulate up and down along it on the way
Not all creek-lines from a 'major ridge' (a catchment divide), descend all the way i.e. although the water may go all the way to the sea, the creek carrying it may not: the creek might only be a tributary, ending where it empties into a river. Similarly not all ridges running off the catchment-dividing-ridge reach all the way to the coast—some are "dead ends"—they end in a "shoulder", cut off between two creeks joining, or at a river bend. All valley-dividers are ridges, but not all ridges divide whole valleys, or even minor catchments. Those that come to a dead-end before they reach the coast are not dividing ridges, and may be called "minor".
All creek lines do not necessarily start on a dividing ridge: The creek itself might attach to a minor ridge, within the valley area.
Those ridges and rivers that transect or divide whole catchments are called 'major'. The named river ought to be a major line.
Unless you look for them on the map you may not be able to notice anything special about them.
Major ridges & rivers do however tend to stay higher and lower for longer, and often provide you with the **gentlest climbs**,
And they attract roadways.
Main ridges also tend to run parallel to the main valleys and vice versa.

Sort it out on the Map

- You cannot see catchment layouts from ground level!
- If you walk around a slope, half-way up, e.g. following an aqueduct, then you cannot easily know when you cross a major catchment. There are many minor ridges to cross and any one of them could turn into a saddle which divides valleys.
- Around peaks and plateaus, valleys spawn in all directions — it is hard to identify the right ones. High marshes may drain in several directions.
- Near a major river junction, travelling along the dividing shoulder can give a confusing alternation of views, between one valley and then the other.

Catchment Divisions Snake from Coast to Coast

Ridgetops fit parallel to and between the two highest contours marked on your map, and can be very sinuous.
They mark neighbouring catchment edges; & so theoretically you can cross the continent on highest ground without crossing any creek.
Major catchment divisions must reach the coast at a point each side of the river mouth (except, of course, for inland salt lakes).

A Catchment-Division* Separates Whole Valleys

*called a "watershed" in Australia, unlike in USA

Hint 1: Mark catchment divisions on your map with a pink highlighter — pink is opposite to blue-green for creeklines.
Hint 2: Now forget about those new pink delineations on your map. They refer only to the layout, as seen from above.
You need to imagine real, high ridges inbetween deep valleys.
Hint 3: Now forget about those razor-back ridges in your mind. You need to know that they could be remarkably flat paddocks.
— not very eye-catching — look for them carefully.
A catchment division will follow the highest flattest ground and consequently have a few marshes and puddles on it
A metre-high bump in a paddock might separate two raindrops into two different 1000 km journeys in each direction.
So you can't simply "walk downstream" — not until you know where you might end up!

Tracks are like Naughty Children

If you take your eye off them for a moment, they will split as soon as they are out of your sight.

A shortcut is often the result of a junction.
This is because tracks often bend at a T or Y junction.
Shortcutting is constantly encouraged at any bend,
So there will likely be an inviting well-worn shortcut there.
You can always split the party to explore both routes.



The same is true for creeks & ridges

Unless you stick to the bank of the riverbed, you cannot count on seeing the tributaries, and if you do stick to one side you miss the other side tributaries. Also, where a stream is "braided" into parallel interconnecting branchlets, and you follow one gutter, you are easily blinded to its tributaries joining in from side-valleys.
If you don't stick to the main gutter or crown, you miss seeing junctions on the far side of the river or ridge and can follow a wrong one. But side ridges are harder to see from the crest, just like tributaries are hard to see from the central channel!

Explore Branches While You Can



As a matter of principle, it is easier to explore something if you are there, than if you are not!
Be quick to remember that before you walk on past.
Remember… that you are there to enjoy the country. So put down your pack & amble off for a minute or delegate someone to explore.
You may surprise yourself by discovering a helpful signpost at a second nearby junction or a new access point and car park,
Or even, that it is the track you should have taken just now. Bends Breed Shortcuts: A shortcut may look like 'the junction we don't take' which means that you may mistake the real junction anyway.
Avoid endlessly having to wonder later… "But if that other junction turned east, then it might have been the link…" etc.
When you are there, find out for certain.

Convergent Tracks Lead to Civilisation

For example, you get lost, stumble across the track and meet a T-junction — which branch do you take?
You can examine any Y-junction for signs of splitting into two or more minor branches.
The most acute angle of a Y-junction usually points to a focus point (e.g. downstream; car-park)



Down-Track vs Up-Track

This one is not obvious, and so it may trap you.
You seem to be following a well-worn path down, until you turn around and try to find your way back up.
It is then that you discover a multitude of other tracks joining into yours at an acute angle!
You see, people walking downhill, downstream, get channeled into the paths of least resistance, converging just like the creek lines do.
But people walking upstream or uphill are faced with choices and tend to spread out into all possibilities, until they find the right one.
The best path is worn in from down traffic, but that may not make it obvious to up-traffic.

Allow extra time when going up-stream, or climbing a steep peak, for eliminating false leads.

Wind West

Assume you are in a wind-swept place in medium to high latitudes e.g. southern Australia, where strong Westerlies prevail.

'W' in the 'WEATHER' mnemonic (p.114b) then reminds you
of the prevailing **W**esterlies in the high 30s, the Roaring 40s, the Furious 50s and the Screaming 60s.

'W' for '**Weather** systems come from the **West'** in temperate latitudes.
and '**Wind** in your face' locates these weather systems for you.
and 'Upper-level **Westerly Wave'** steers these systems to the E/NE/SE in a waving pattern.
A common pattern is to have a warm nor-westerly storm preceding a strong cold sou-westerly change (SH).
and '**Wind-West'** reminds you to look for the lower-level **prevailing Westerlies**, and their effect on the bushes, landscape, etc.

You don't have to be in the Roaring 40s to find a windy place and look for tell-tale signs of the prevailing wind.
— Onshore winds near the coast, being laden with salt, leave unmistakable clues imprinted in the bushes, and on the seashore.
— High plateaus and wide open clearings are usually windswept.
— Gullies produce up-gully breezes and down-gully gusts.
— Hilltops are windy. To get an undistorted picture of the prevailing wind direction, go to a hillock.

To navigate by the local prevailing wind may be more preferable locally, than to navigate by bush north.
The prevailing wind is not as universal or reliable as bush-noon, but it can be easily visible, audible and tangible.

In general, the **tallest trees** are the best tell-tales.
Look for wind-induced asymmetry**, especially at the tree tips** and the **oldest** tree trunks, when you are in a wind-sheltered zone.

Think Wind

Distinguish in your mind the various causes of wind damage…

- Storm Winds — brief but furious, as a weather change hits. They may uproot trees. They are often hot and dry.
- Fire-storms—from the hot dry inland, or sweeping uphill. They can leave a trail of dead black fallen trees lying parallel.
- Cold Change Winds — Cold, Gusty, Strong, Persistent for a day or three; Usually south to southwesterly (S. H.).
- Persistent Prevailing Winds — Westerlies 'Waving' between northwest and southwest in between 'changes'.
- Salt Laden Onshore Winds — They 'cut' the exposed vegetation back to size.
- Cold Blast Winds — These kill off the less hardy competitors.
- Hot Dry Blast Winds — These leave only the waxy/succulent/woody species.
- Sand Blast Winds — They remove vegetation, carve out sandstone sculptures, and remove lichens from the exposed side.
- Windy Season Winds — Ask the locals what to expect at each time of year.

Anything is Memorable

Make it personal	"Where I found the pocket knife!"
anticipated	Study the map beforehand to imagine the sections
active	Do something; involve yourself
important	Draw attention to why it should be remembered
associated	It looks like a … ; sounds like my middle name ; uphill from the mine
creative	Make up an enjoyable name
emotional	Expect to notice, then remember, decision points & anxious times
visual	e.g. symmetric, colourful, shapely
geometric	This triple-trunk matches the triangle of paths here
noticed	Draw attention to it "See how we have just entered tea-tree ?"
peculiar	That tree looks like a traffic policeman!
prominent	The tallest tree here, see?
liked	What aspect about it interests you?
named	e.g. "Midnight Junction"
fitting	"Power Point" where the electricity line crosses the lake
funny	'Willy Willy Waterhole' where we saw the dust-devil
human	"Betty's"

Make Individual Memories Memorable!

The problem is an excess of information, with a shortage of enough meaning to go with each detail.
e.g. hillocks and creeks have endless detail — you can't hope to remember all.
Visual memory is not the problem — pictures are perfect — but recall is difficult.
(And sorting pictures out later, into the original sequence is also hard.)
You need to add memory handles, worthwhile meanings, specific focus, etc.
Hint: Do something memorable there. Dance, Sing, Jump, Shout, Throw stones into the puddle.
Make a cairn. Sketch a tree. Have a meal — Chewing is said to aid memory!
Leave something of 'yours' there — something peculiar — e.g. lean a stick against a tree trunk; scratch the ground.
Insert it into a larger scheme — time & sequence; lie & surroundings; an acrostic poem.
Make a game of it. E.g. "Who can say what's peculiar about this creek?"
Make it 'yours' e.g. Discover it. Climb it. Explore it. Study it. Explain it. Draw it. Map it. Show it to someone. Name it.
Spend time there, looking.

Remembering Trees

Simply spend time looking. It may only be 10 seconds, but that is 2000% more than the usual ½ second!
Look at the branches, the shape, the trunk, until something strikes you
E.g. "Oh, these two branches grow across each other"
E.g. "The bark is right-hand spiral"
E.g. "See that ant-highway going up into the hollow—it might have water in it"
Walk around it, to see the shape from side-on. Characterise it & its context
E.g. "entirely shorter than that old stag's first branch"
E.g. "three tufts on top"

You get better with practice.

Ridges

Ridges have gentler slopes up/down ridge i.e. provided you stick to the crown.
The slope 'makes' rapidly on each flank. It is only the ridge-line which is flatter.
Ridges have nicer views. But these views are easily halved unless you walk right on the crest.
have nice breezes, provided you are right on the crest.
have more open and stunted vegetation plus shallower soil and more exposure to the elements.
are wider and flatter than a creek bed, and their rocks are firmer underfoot and dry.
Their run-off slides off downhill to each side.
These advantages are also lost as soon as you slip off the 'crown' of the ridge.
Off the ridge is steep, vegetated, narrow, loose, windless, hot, humid.
The steepest but best way up a ridge is... up the ridge because (1) it gets even steeper off the ridge & (2) contouring is 'easier' but it doesn't get you 'up' but only into more difficult terrain.

Ridge Names

Mountain to Mountain	e.g. Mount Ossa to Legges Tor (trace it on the map)
Mountain to Mouth	e.g. Mount Ossa to Arthur River South Head
Mountain to Headland	e.g. Mount Wellington to Wrest Point
Catchment Division	e.g. The Arthur-Pieman Divide
Tributary Divide	e.g. The South Arm Ridge

A ridge may not be "major" but if it divides your walk, you do want to know about it—so make up an appropriate name for it.

Mnemonic: "Ridges Rise"

Whenever you cross a ridge don't forget to ask: "Which way does this ridge rise, in trend terms — to the left or to the right?"
It is like asking which way water is flowing, but the truth can be obscured by local undulations in the ridge.
Ask: "Does this ridge, if followed to the (right), end further inland i.e. upstream, or further downstream?"
It must correlate with the overall corresponding drainage.

Uphill — Which Hill? Upstream — to which Divide?

To Which ridge? Which plateau? Which highest ground? Just as surely as rivers reach the sea, so ridges reach a peak.
Which peak? is the question which orients you.
Until you know which catchments you are climbing out of and in to, you don't have a grasp of where you are.

Sympathy and Understanding with Track Markers

Take time out to explore (e.g. leap-frog fashion) from one track marker to another.
Always guess where a track ought to go.
When you come across a marked trail—maybe poorly marked and/or difficult—the question arises: 'Should we follow it or not?'
Intelligent guesswork helps here

- Where would *I* put a track?
- What is the direction trend of the new trail?
- What is the slope trend of the trail?
- What tracks & routes might you expect?
- What alternative access routes exist?

E.g. uphill, heading West, may well mean: 'to Lake West from the lower car park'

If you leave the track behind, because it is unclear, you may never get back onto it.
But if you work with what you have (a bad track) it may be quicker in the long run.

Old Track Markers

Practise noticing them, before you need to.

- Old axe-cut blazes on tree-trunks — from the original surveyors
- Very old paint flecks in the blazes — search for them
- Blazes and markers on the far side of the tree — look back
- Old nail holes or nails or rust stains — the marker has fallen off
- Fallen markers — on the ground
- Fallen rock cairns — the rocks blend in, but show their pale underbellies
- Arrows on wet rock-faces — the wetness obscures the scratches
- Sawn branches, trunks and logs from when the path was cleared
- A clear line-of-sight through the trees
- Thick young growth — an unused road
- Smooth or shiny rocks with less lichen — worn smooth by feet
- Fallen trunks with a gutter worn across them — betraying foot traffic
- Broken branches of varying ages; bent stems e.g. bracken fronds
- Stumps cut off at ground- or eye-level.

Be Wind-Wise: Listen

Listen directionally — the wind-noise will be mainly from up-wind.
When you think you are navigating by the beach noise, you are probably navigating by the onshore wind, and should keep track of it.
Listen **through** the noise — You may distinguish three frequency bands, as the rumbles emerge from the hiss.
Listen through the **silence** — of night, in the stillness. Up-wind sounds carry a long way.
Listen to the **sounds** (birds, traffic, house, factories) — They carry clearly from up-wind only, especially the high frequencies (whistles)
Listen to the **beach** noise — The 'hiss' will be from a direction more up-wind, and closer, location-wise.
The 'rumble' will be from further away from you and further away from up-wind direction.
Listen to the **thunder** — Air temperature zones create directional effects, so that approaching storms, which are preceded by low level cold bursts of air, have their noises refracted up and out of earshot.
(See "Tips for Calm Weather" p.23d & "Topographic Level Winds" p.25d)

Obvious Tell-Tales: Landscape

- E/W coastal asymmetry e.g. Temperate West Coast ocean beaches might have a kilometre of surf, but East Coast beaches are narrower and calmer. Trade-wind East coasts are surf beaches, but headlands with West facing shorelines will be sheltered.
- Bays end in exposed points. Look for tall, steep, bare sandhills on the weather side. If there are tall sandhills at a narrow point, you will see sandhills from both sides, so ask 'am I seeing the green (sheltered) backside?'
- Sand dunes. There are variations, but bare dunes tend to be cross-wind and vegetated dunes tend to trend down-wind.
- Puddles, Lagoons, Lakes, Creeks, Beaches — Look for wind & wave action effects e.g. dark mudflats up-wind & white sand-steeps downwind. Shallow puddles often occur on the downwind end of a flat drainage.
- Sand ripples show steep backsides downwind, as the wind driven grains topple over the eroding crest.
- Clumps in sand-stretches show a long tail downwind. E.g. behind dead seaweed deposited on the dry beach.
- Grass-clump erosion is the reverse of sand ripples — look for steep bare dirt and exposed roots on the exposed side.
- Camps & campsites, picnic tables & fireplaces, bird nests & animal shelters all avoid the un-sheltered side of vegetation.
- Wind-shadow growth—plants grow taller in the lee of a mountain range, or of a pebble, sand ridge or house.

Obvious Tell-Tales: Windblown Objects

- Flotsam collects on the downwind side of a lake (but on the sheltered side of a coastal point!).
- Trunks fall downwind in storms; branches fall downwind in gales; leaves, nuts and flowers fall downwind in strong winds. Look for ribbon bark hanging in a tree downwind from its source.
- Rubbish (old dead twigs & leaves) collects behind a clump.
- Dead long leaf blades lie cross-wind when blown against an obstacle e.g. a clump...
- Dead long leaf blades lie down-wind when blown from a source e.g. a tussock...



- Broken off branchlets lie with their big spread-out twiggy end downwind. Meadow-grass tufts pulled up by grazing animals also.
- Feathers catch in bushes, usually on downwind branches, and mat against the up-wind side of those branches.

The Difference between Looking at, and Seeing

..has a lot to do with involvement.
e.g. a seed-collector will see the vigour of the plants and their stage of fruiting. Would you even see the plants!
e.g. a hunter will see a route for stalking from behind cover.
e.g. a photographer will see the contrast in light.

Would you as a navigator care to notice footprints, or their absence? What about the flight-paths & contrails, or gems in the river gravel?
Navigation is your opportunity to see more.

Search-Image

It is possible to stare at something obvious and not see it! e.g. the pattern of wind-blown grass stems, or the peculiar geometry of a tree. But after some practice, you can't miss it. So train your brain to the search images before you need them. When you are flustered and hurried you will not feel confident in your abilities to see something difficult, and will likely give up too soon.

We Recognise 'Sameness' But Need to Describe the Differences

A gum-tree is a gum-tree; but this gum tree has three trunks!
A 'bend on the road' is just a bend; but this one bends away from sunrise.
A 'hillside' looks much like all hillsides; but this one is regrowth with wattles dominant.

Don't just gaze at "the view" or "the landscape" or "vegetation". Look past the fuzzy 'sameness' to the unique peculiarities.

Unfortunately that often means: 'Focus on the boring detail'
e.g. 'This hillock has five dead tree trunks, totalling nine main branches' which makes this hillock recognisable and unique.
So. Hint: **When all else fails, COUNT!** (The same goes for botanical species identifications.)

There is often no way around a detailed look. There will not be anything unexpected to hit you in the face — you must keep looking until the interesting peculiarities emerge.
E.g. "No other dirt road junction I have seen has an Acacia sapling growing in each corner."

"Shoulders Stop"

A huge mountain range may end in a "shoulder" i.e. a 'shoulder' amounts only to a 'minor ridge' stopping within the valley.
You will not get to the coast by following it down. (If you are on the very last ridge next to the coast it would be called a headland).

There may also be isolated high ground within a valley, a lot like an island, and this too is doomed to end in only 'shoulders'.
Such high ground is drained by one river only, but via several tributaries.
It will have one, often low, flat connection (a saddle) 'uphill' to the main Divide.

Shoulders are Not Easy (like Ridges) To Walk on

1. They end a spur, and so are likely to be steep, as the ridgeline plunges down to the creek bend or junction below it.
2. They are wetter than ridge tops. Although they shed water, being convex, they are still fed with run-off from above, as on a hillside. So the vegetation can easily become very thick.

Saddle — A Flat between Hills, Sitting Astride a Ridge

They are so named for their resemblance to the two-bumps-two-gutter horse-saddle shape, designed for two legs astride a sway-back.
When a flat area is drained by three creeks and so has three ridges lifting from it, it is called a "monkey saddle".
The third gutter accommodates the tail. This can cause uncertainty-of-choice for navigators!

A "col" is a saddle.
A "pass" is usually a low point in a high ridge i.e. it is a saddle.
A "gap" however may simply be a river gorge.

Every undulation and flattening of a ridge leaves a saddle. In forest, there will be a puddle. It may also attract a campsite or a road.
A saddle may look like a valley crossing—a muddy dip in the path—but the two sides both drop away, if you look carefully through the wall of vegetation.

Weather maps show pressure 'saddles' between two High's and two Low's—p.11d.

You can also picture a saddle as a U-shaped valley going up and over a gap between two hills and continuing down the other side.
Saddles make creek sources, but not every creek source begins as a flat saddle—any ridge or slope may spawn drainage gutters without necessarily flattening out.

Track Markers

— Decode the colour-code. Separate tracks often have separate colours. Reverse track markers may be of a different colour.
— Successive generations of track marking may be evident, or several colour-coded tracks may share one leg of the journey.
— Triple marking, often means "End of Markers" or "End of Track".
— Big cairns mark junctions, campspots, features. Cairns with a stick may also indicate a junction.
— Side-tracks are marked with something extra or different.
— Sticks over the track, or especially crossed sticks say "No Entry. Wrong Way. Go Back".
At an unexpected junction, if you have to step over some branches you have probably missed the intended message.
— Un-needed signposts — often mark the entrance of disused tracks. They may (or may not) be at an unexplained bend in the route.

When You Lose the Track-Markers

Be suspicious! Start by over-navigating beforehand — search for all track markers as a habit, even when the track is well-worn and plainly visible. It gives you the practice for when the track marking does get patchy.
Also, only then will you notice whenever the track takes an unofficial shortcut (e.g. following vehicle tracks, not the walking track).
Or maybe you have taken a wrong turning off the marked track and need to realise it, no matter how good the new track is.
Whenever you lose the markers or whenever you lose the track, explore in these directions: **straight ahead and straight behind**.

One or two markers may simply have fallen off — so maintain the trend
You may be approaching a main track junction with the first few sidetrack markers removed to conceal the sidetrack you are on.
An unexplained bend, which deteriorates, may be explained by a missed junction/bend...

Where a tree has fallen nearby, try to pick up the trend of the old track, on the far side...
Backtrack to where you went wrong — to the last bend & from the last certain marker.
Next, explore the unexpected directions.
Very often a marker will be placed at a bend, because of the bend, or even because of a Y junction.
Then explore in all directions — "Meet back here in five minutes" might save 50 minutes.



Notice (with Alarm!) When...

..The track itself **deteriorates**. You may be on a false track, made by people doing just what you have done
e.g. you overran a junction or bend; you sidestepped a fallen tree without noticing.
..Boot prints, that were there before, cease. Especially on a 'through' track.
..The track gets **better**! This means that in back-tracking you may miss your small track and follow the other track which joins in there
..The country abruptly **clears** e.g. a beach, a peak, a clearing, a road. There may be no way to find the single small track you used.
By the time you remember to look back, you may have lost the way back out. There may be too *many* paths to choose from.
..Any **barrier** e.g. a beach, a road, a fence, a riverbank — clear or not.
When you hit the barrier you do a right-angled bend, but later you may not remember exactly where you met that barrier.
..Any **catchment change** i.e. crossing a ridge, or even a creek crossing—into "another part of the catchment".

Name the enemy: Be the first to say out loud **"Abaracadabara! Peek behind you! because it's a...(fill in the blank)"** A **B**arrier; A **R**idge/River/Road Junction; A **C**learing; a **D**own-track (or focus point); A **B**etter/worse track; A **R**idge/River crossing; A **Peak**.

Light & Colour Effects

This is one of the delights of nature! Chances are that you will be startled, even if you know what to expect, but only if you look for it. You need to wade out into a uniform reed-bed, preferably when the Sun is side-on to the prevailing wind, then look up- & down- wind. Up-wind, the tussock tips are pointing toward you. You then see between them into the deeper shaded body of the plant.

- The view up-wind is dark & colourful. The best effect is from rich brown or dark green, drooping, chest-high reeds.
- Down-wind the tips lie flat and reflect the sky shine at you — faded & bright.
  The prevailing wind may result in permanent sunbleach on one side of the grass blades.
- On a windy day you will see gusts causing bright patches in a dark background, due to the same flat blade effect.
- To neutralise the directional lighting of the Sun, look down-Sun — to your left & right will show pale vs colourful.
- The combined effect of the Sun and the wind result in four quadrants — darkest up-wind; shiniest downwind; greyest up-Sun.
- This happens even with ordinary green plants — look for it in any low, flat, wind-swept vegetation.
- The prevailing wind doesn't need to be blowing to see its permanent effect on the plants.
- At sunrise in the reed-bed, you should notice a 'funnel-web' effect on your right — like the circular scratches showing up through a sunlit window.
- At other times you may simply notice that any shiny leaves on the left of the Sun tilt left, and on the right of the Sun tilt right.

- Looking up-wind anywhere is greener. Downwind looks more bleached — due to leaf-tip scorch, leaf fading and leaflessness.
- Weather-side sandhills are white. Lee-side sandhills are greener, due to thicker growth.
- Exposed lake banks are steeper & eroded. So, sandy lagoons show white sandy vs dark muddy ends.
- In sandy heaths, downwind shows up as windblown sand patches of erosion. Up-wind shows up as continuous plant cover.
- Rocks in sandy places are sandblasted pale on the up-wind side and darkened with lichens on the downwind side.





Shiny leaves



Expect some variations

Place Recognition
You Recognise What You See, By What You Can't See

Every locality fits into a context — the invisible surroundings.
How long did I take to get here? How far from the turnoff? In what direction from home-base? Uphill or down or contour?
How many creeks have we crossed up to now?

To know where you are, you can't ignore where you are not.
e.g. 'It was an all-day slog to get there, we finished the day worn out'
is part of where you were, and fundamental to your memory of it.

Landscape recognition is relative.
That involves your senses of time, direction, distance, difficulty, slope, topography, layout, number and network.

Aspects, invisible to the eye, which surround a place, live in your mind's eye.

Description Requires Words
Can You Describe All That You Can Recognise?

E.g. a magpie. What pattern is on the head? What colour legs?
E.g. your brother — what colour eyes? what voice accent?

"Recognition" means "I need to see it before I can recognise it"
"Description" is "I can recall it to my mind and describe it"

If you don't deliberately memorise something you can only recognise it but can't describe it.
So thoughtful examination, notes and practice, can fill in a lot of blanks.
Repeated visits build up a subconscious picture, but you can speed up that familiarisation process by **deliberate scrutiny**.
Expressing the description in explicit words, forces your subconscious 'recognition' powers, into a new dimension.

Hint: Open your mouth; say: "The place where… " and see what comes out spontaneously.
try: "In between…" "Running alongside the… "
"You probably would remember it as the time when… "

Notice When You Cross a Catchment!

It is a major method of navigation
e.g. at night; or in a blizzard; or when you are lost; or in a forest; or descending from high ground; or exploring upstream.
But you need to get used to noticing ridges and to counting creek crossings and to matching the catchments to the map.
Notice also, when you cross from one side to the other side of a catchment.
Ask: Is this riverbed likely to be the lowest, largest channel in the whole catchment?
Look for creek-line vegetation, as sometimes the only clue to the drainage pattern.
Look for any darker patch in the road or track or beach, as a tell-tale sign of a dry creek bed.
Look at the track ruts. If the rocks are exposed, water flows over it. If the ruts flatten out, water drains away from the track there.
A subtle rise, dip or bend in the track can be traced to an obvious ridge or drain crossing it. Look sideways to appreciate the lie.
Assess any puddle, marsh or mud hole — Is it a creek line or a saddle top? — Is it in a dip or on a crest? — Can you trace a gutter?;
Notice any crest; Trace ridges to a nearby peak. I.e. Don't get caught whingeing about the government, instead of noticing the lie.
Ridges divide: they shed water. Creeks collect: they catch water. Valleys drain: they empty into the sea.
Rivers cut the catchment in two.
See "Understanding Contours" for some hints — later in this section. See also p.83b.

The Giveaway! A Change of View — Mnemonic: "Catch the View"

The new panorama is the tell-tale sign that you have changed catchments.
Perhaps you are contouring around a headland and catch the new view around the corner, or you are sidling around a ridge, or you are breasting the saddle, or reaching the peak, or cresting a paddock… It is the new vista that greets your eyes which tells you that something has changed. It is also the loss of the old valley view.
Well, maybe you can't see the view, but you may now be able to see the skylight or even blue sky down through the trees below you.
When climbing, you find yourself looking down instead of looking up. Your muscles, of course, tell you the same story.
The deeper the new valley, the more far-reaching, on average, the new view.

You Can't Cross a Creek Twice from the Same Side

If you make two successive creek crossings in the same flow-sense, you have crossed a creek divide into a different creek catchment.



Up-creek is on your left both times

The same rule can hold for ridges, but only those which slope uniformly down from high ground.
Otherwise an unexpected crest slope, instead of being a 'different ridge', may alert you to 'a local up-trend' on a down-sloping ridge.

Mark Your Trail


a pair of stones...
a gumnut on a rock
a cut leaf…
dead twig…

Two principles are needed — 1. Trail marking takes extra **time** — budget for it.
And this one is widely applicable… 2. It's easy when you know how, so **think** how!

Mark Your Trail Non-Permanently

E.g. when you could otherwise get lost

- Use what is available — pebbles, leaves, tussocks — throughout the area, for ease and consistency.
  e.g. "always look for a pair of stones"; "tie a grass blade on the top shoot of any shrub"
- Leave your mark in a visible place. E.g. "look for freshly broken twigs at the base of each trunk on the path";
  "check the topmost leaves of anything chest-high for a mark"
- Leave your mark in an expected place. E.g. cross-country: Zig-zag in straight lines between prominent features, so coming back you know exactly where to look for the next markers, and searchers do too.
  E.g. hillock, to tall tree, to clearing, to outcrop.
- Do something only slightly unnatural: (see diagrams) A gumnut on a rock; a twig through a leaf; a pair of torn leaves; grass stems bent in a consistent direction; or tied in a knot; or crumpled; a scissor-cut dead leaf; a scissor-cut fresh leaf; bark hanging from a barkless branch e.g. gum bark in a Banksia; a twig drilled into the ground; a leaf wedged into bark at eye level; a triangle of twigs; a half broken bent twig hanging in a shrub; an opposing pair of gum leaves; a trail of sticks; windblown debris which is reversed; upturn a rock onto leaf litter
- Deliberately plant your boot print when you can. Step on top of older footprints, deliberately.
- Use fresh material so that your trail may be 'aged' according to the fading or drying e.g. of green leaves or mud.
- Position markers so that time, animals, wind & rain will disrupt them (at a recognisable rate). E.g. a teepee of sticks.
- Try a snow cairn; chalk marks on rocks; cotton tied around a branch; a stick dragged in the dirt; a scratch on a rock; balls of mud; charcoal or charcoal marks; tiny shreds of paper.
- Choose one method and stick with it, with a backup method in reserve.
- Double-mark a trail e.g. when doubling back, by duplicating it.

Tracking Someone Else

- Look for the **absence** of: spider webs across the path; dew on overhanging branches. To discern a foot-path look for the absence of fallen branches; leaf litter; lichen & moss; old wombat dung on prominent rocks; unbroken sticks; untrampled seedlings; undisturbed soil
- Look for the **presence** of freshly disturbed stones/soil crust/puddles, plus footprints.
- Examine puddles: for wet edges — indicating a recent forward swash; examine for muddy water; look for muddy water in the deepest layers — indicating disturbance some time ago; for wet stems above the water — they have been trodden in and have sprung back
- Overlapping fronds across a path — they 'remember' which way they were last pushed through.
- Don't step on the boot-prints or tracks you are trying to decipher—you often need to look at them again.

Botanical Tell-Tales


permanent lean
e.g. Bracken fern
curve of stem
fallen fronds downwind
The dead stems snap in the wind
tilted clumps
e.g. Yakka
dead stalk
dead leaves
dead tussock-grass fall
initial trunk lean
e.g. Banksia tree
final lean
double curve (exaggerated)
e.g. Yakka flowering stem
'battle back up-wind'
'go with the flow' downwind
asymmetrical
tree-tip
(top view)
alternating bush 'streets'
and blowout channels
climber- & parasite-
load downwind
top-view...
..grass 'streets' in the wind-wake of a fallen branch
Wind exposure on
leading edge causes
leaf-kill, leaf-strip,
and leaf-scorch
some flowers open downwind

Discuss It

Let others open your eyes: "What can you see about this?" "Where does it remind you of?"
Ask Questions: "How do you know where you are?" "Could you get back here again next year?"
Make a game of it: "What else can you notice from here?"
Express the specifics: e.g. "That boot-print has zed-shaped ripples on the right and ess-shaped ripples on the left.
The heel patten is a smaller version of the front half, as per normal."
e.g. "This tributary lies northwest/southeast and points to the left of the peak."



Many aspects of navigation yield to these simple tricks…

discuss it   express it out loud   make it the topic of conversation
delegate the tasks between yourselves
keep yourself alert
make up your own names
collect the details   integrate them

Collect the Details

Identify a Specific Place by its Specific **Collection** of Details

E.g. "A low conical hill in flat terrain south of Mount Cameron"
That is not 'interesting'. The bits are not 'peculiar'. But the collection of the bits is unique.
E.g. Plant and insect species are often so similar to other family members that no one character is 'characteristic' enough.
The species will be identified by a set of characters.
E.g. Is this our old road?? Does anybody recognise it from last year?? but it has…

trend e.g. toward sunrise
slope e.g. mostly uphill
straightness e.g. can't see for more than 20m mostly!
traffic intensity e.g. many fallen trees across it, and encroaching bushes
length e.g. it goes on and on and gets nowhere!
vegetation e.g. set amongst old gums with yakkas under
ends e.g. it came from the saddle and ends up behind the peak

If you think you recognise it, by the combined characters, you will probably be right.
E.g. Make one name for the big tree on the crest; another to name that crest; another to describe its relative position…
and soon you can't mistake it…"the big tree with the south facing hollow on the port-side Dam-wall Ridge downstream of Tree-fern Crk.
The add-on bits are part of the name of each bit i.e. "the Big-tree Crest" (downstream of Tree-fern Creek) (near the dam wall).

The smallest collection is two, but that is a powerful combination, e.g. a peculiar log, plus a recognisable hollow trunk, is almost unique.
The combination is the peculiarity to remember — a third peculiarity.
The geometry of the combination is a fourth and even more powerful memory aid… "This log points to that hollow".

Include What You Can't See

For instance, have you noticed that there is no bare ground showing? That you can't see farmland? That there are no intervening ridges?

Break of Slope/Make of Slope

The 'make' of slope is the **steepening** as you go downhill ie the "slope" is a down-slope. The best views are at the most abrupt 'make's
The 'break' of slope is the first **flattening** out as you descend. The thickest soils occur below the 'break'.
The make and the break refer to points which separate different 'slopes'.
There is a difference between a making, or eroding slope and a breaking, or sedimenting slope…
A ridge-top is a make of 2 slopes, in cross-section, but any abrupt steepening can also be called a make of slope.
..Making — convex out-wards. Convexities shed water (usually in all directions) and shed silt and are poor sites to locate a dam or to dig one — there is bedrock below.
The water table will often break the surface at the more abrupt breaks.
..Breaking — concave up-wards. Concavities collect water and collect silt from above.
You can locate and dig a dam in silted up areas.
Constant slopes lie in between deposition and erosive scouring so on a constant flat slope the streamlets can 'braid' together



Paddocks are often cleared up to the break—the rocks.
A band of moisture-loving vegetation will often separate the slopes.

What you see in three dimensions can often be more complex than what you see in cross-section!
— When convexity changes to concavity there is a **momentary straightening** — a 'break of slope'.
This is also called a 'point of inflection' in the curve.
It's not just a meaningless mathematical quirk; it betrays a set of real changes, resulting from the erosion history.



Scree Slopes — Tread Carefully!

The boulder-field at the base of a cliff, gives you a false sense of security!
Each rock seems so solidly jammed in place, but the whole field could 'slump' and slide all the way down, if given too much of a shake.
That is why there are no old trees growing in landslide-prone slopes!

The essence of a scree slope is, like a pile of gravel: It is in a continual state of critical instability, as evidenced by the straight-edged slope (flat but not level), about 36°. 36° doesn't sound like much, but up a sandhill, it puts you on all fours!
The rock surfaces look 'fresh'. Soil doesn't accumulate.
Tread carefully. Distribute your weight on all fours. Tread on bigger rocks.
Choose the cliff-base — it has hand-holds — or the scree-base — it has a solid bottom.

Mark Your Trail More Permanently and Ostentatiously

E.g. when you are lost or in trouble or in doubt







- A teepee
- Mud upon a tussock — quite unnatural; A tussock upon a tussock!
- Hang a piece of clothing from a prominent tree limb
- Dig a hole and make a hump

(Direction of travel is ⟶)

Mark Your Trail Invisibly

E.g. so that other walkers who are not lost, don't disrupt your markers, out of a sense of bush etiquette.

- "One mark every 50 paces". E.g. one pointed pebble. You may like to use double-paces.
  It is almost impossible to notice accidentally, but impossible to miss if you look.
- "Every 10 paces, as an option" added to your scheme — to cope with junctions and bends.
- Place a pebble on the ground, on the onward side of an existing cairn. You can recognise it, and scatter it, when you come back through the fog among a maze of similar cairned routes.
- Put a small mark at the base of each track marker (e.g. under blazes-on-a-trunk or ribbons-on-a-branch)
  — you can easily find it, and know that you have been along that track.
- "Half way between (2 markers)" or "10m North (of a juncture)", can remove the marks from obvious view or significance.

A pebble Code — Keep It Simple

All codes have to be memorable to all users — complications never survive the years of disuse.
I.e. use 'one' to 'four' only, preferably only 'two' and 'three'.



Tread the pebbles into the ground for clarity & permanency.
Upturn the pebbles for visibility, and **point the stones** appropriately.

Use the smaller pebbles at the front.

One: "I woz 'ere, going that way"
Two: "Me go that way"
Three: "I'm lost, exploring that way"
Four: "Look for a message, there"
Five: "Someone has seen this message"

Square: "Don't go this way"
Circle: "Oh" for "I'm OK"
Bull's-eye: "I will be back here soon"
Junction: "I have turned off (and returned, then continued)"

Double marking: Close the pebbles up the second time past, until they touch.

Combined Effects of Wind, Salt and Light

When assessing wedge-shaped shrubs, leaning trunks, tilted canopies, etc., try to distinguish wind-cut from salt-cut and from light-lean. But beware, in any natural system, it would be easy to over-generalise from a few known specifics, or falsely extend an inadequate interpretation.

Here is a typical wind-ramp. The leading edge consists of dead twigs.
The vegetation gets greener and thicker and taller downwind.

But you cannot easily tell whether it is the result of salt-laden wind, or strong wind only.



Salt-cut will show you the direction of the prevailing onshore wind only.
Inshore, wind-ramping will show you the direction of the prevailing wind, which may be significantly different in direction.

Botanical Asymmetry

Plants must respond to the wind.
If they did not deliberately push up-wind, we would be walking through a landscape of leaning-over plants.
Therefore it must be possible to 'read' the effect of strong wind written into the branching history of a plant.

The branches of a bush may grow according to the strong wind, but the leaves will still respond according to the asymmetrical light.
The two effects may or may not be independent and you will need to examine them carefully to see the difference.
Look for asymmetry in the green parts of a plant to show up bush-noon and look for asymmetry in the other parts for bush-West.
If there is a macro response to the wind, which will confuse the macro light-response, look for micro signs of a light response, on individual branchlets.

You don't "need to know your plants" beforehand. Instead you examine the species which present themselves.
You assess what responses they make to light, wind, shelter, etc.
E.g. Do the stems colour up in sunlight? If so keep looking at that.
Do the branches throw out more leaves on one side? If not look for something else.

Extend Your Familiar Range Systematically

Explore in every direction, in ever longer legs, radially. Leave recognisable marks alongside recognisable things.
Then explore in concentric circles to make sure that you can recognise individual trees and rocks.
You know you can explore further within the endless sea of scrub, if you have 'familiar friends' which you have seen repeatedly.



Markers for future recognition e.g. on your own property…

Plant a tree Graft two branches together Suspend a forked branch into a forked trunk
Arrange logs e.g. a parallel heap Arrange rocks e.g. a cairn, or a rock on a stump, or a rock 10 m south of the biggest tree
Dig a trench Etch a mark Paint a rock Leave something solid behind
A stake A signpost A numbered metal tag A path A Campfire-place or Barbecue

Hints

It's the Campsites You Don't Use, that are Easiest to Forget

> I'm forever asking: "Can anyone remember" whether we can camp between here and there?
> Take notes of potential campsites. It makes your trip-planning more flexible, next time.

In general, take the opportunity to spy out and note down potential future trips — side-tracks, ridges, climbs…

Leap-Frog Walk in New Territory

I like to walk a new track twice, anyway. It is no big difficulty to take your time, once, and achieve better familiarity, by leap-frogging.
Explore 2 legs forward then one leg back, and you cover the ground 3 times on the way out, once more on the way back.
4 legs forward, 2 legs back, and it's like walking a return track 3 times, but it gives you a much more solid handle on each section.
You gain what you want, appreciation and re-preciation, and what you need, familiarity and sequence memory.

The best way is to combine this with a mnemonic for each leg. See AA to ZZ for an excellent method.
Its also a good time to mark each new leg discretely.

Break of Slope — And Route-Finding

- The first signs of an approaching ridge-top when climbing include: the change from deposition (breaking) to erosion (making); i.e. onto outcrops; into exposure to the wind.
- Take a rest at the break of slope — before climbing upwards.
- Get your bearings at the most abrupt make of slope, where the view is clearest.
- Look up- and down-hill for the lowest skylight beneath the trees, to reveal the change of slope.
- Avoid contouring around the break of slope — it is tempting, but — it is steep and unstable.
- In rocky gorges, or on any creek-bank, or around any permanent water, look for a break of slope just beneath water-level.
  It may be safer, than rock-climbing higher up, to get your feet wet, and use such ledges. The slope near the water may be less steep, at least on average on jagged slopes; you can't fall as far; your landing is softer (wet) — if you 'keep as low as possible'.
- On steep gravelly roads, stick to the 'crown', or the 'gutter', to avoid slipping.
  The crown will snake from side to side as the road turns.
- Slopes are awkward to walk on—steeper than the ridge or creek, so,
  when you drift up onto the sides of the creek you want to follow, you will be forced further up — onto the ridge.
  When you drift off the crest of the ridge you want to follow, you will be forced further down — into the creek bed.
  In this way 'minor' detours (e.g. around an outcrop, on the ridge or in the creek bed) may result in major redirection orders!



..Avoid the steep bits.

Keeping Track of the **Bends**

Don't just follow your nose — follow the bends!
There have already been some hints on keeping direction sense:"Walk across Australia!" & "Integrate the Jetstream and Earth rotation"
Plus the "Sky to Land" and "Land to Land" navigation systems (p.29e,34d,38d,42d).
Following a track can be mindless. But following the bends in the track means that you understand
— that you have changed direction, and by how much.
We have an ingrained bad habit — that we walk 'away from' the starting point, which is therefore 'behind' us.
Only when we 'turn around' is it 'ahead' of us on the track.
We usually only notice junctions, features & hunger, not distance or direction or exact time.
The commonest mistakes of guesstimation, are failing to notice a track curve,
and **underestimating** exactly how far a gentle but insistent bend will **turn** you around i.e. simple disorientation.

Hints: Notice the bends, with your eye on the sky or the skyline. Establish the habit of looking back.

Desired Equipment

- Compass — look at it often and interpret it
- Polaroid sunglasses — look for the dark blue band
- Radio — use it to keep orientation if you don't have a compass
- Map — orient the map to the landscape, and it acts as a rough compass
  — lay a rhumb-line through the bends, as an average course, as a reference 'track'…

Logging Constant Diversions



A stick or string helps you measure direction changes…
Held at arm's length, you add or subtract, as you decide to change course left and right.
Thus you can revert to an intended course after a short 'blind' section,
and average out the course changes even without a compass, or being able to see the Sun.
You could use the skyline as a reference direction, or lineup two tree trunks for each change.

A rougher method is to counterbalance your diversions.
If you go left-around the rock; next time, go right-around the tree.

Keeping track of countless bends is one of the few major problems in navigation
— like keeping a log of distance covered, having no location sense, and trying to stay alert.
So aim for an independent cross-check e.g. a landscape fix or a distance log.

Think like a Plant

E.g. Imagine you are a small ground-cover plant. In a desperate attempt to not be eaten or trampled to death you will probably branch and leaf out in all directions to simply survive... So don't expect much botanical asymmetry underfoot.

The idea is to become an amateur ecologist. For instance, you could work out the pollinators available, the dispersal mechanisms used, the biogeographical zones and overlaps, and the associations between species.
Therefore think about the geology, geoform, latitude, altitude and soils.

Temperature & Relative Humidity explain a lot of botany.
E.g. very cold morning winds are also very drying when they warm up later in the day.

Altitude, for instance, affects the species mix, so that with practice you can gauge your elevation above sea level.
You notice when sub-alpine species kick in e.g. Telopea (Waratah), then when true alpine species begin e.g. Richea (Scoparia).
Individual members of genera have altitude preferences and so are helpful to distinguish altitude
e.g. various Coffee berries (Coprosma) or Pink Berry (Cyathodes).
N.B. Since the prime effect of altitude is to drop the temperature, this is really a latitude-dependent temperature effect.
I.e. Going further polewards, the altitude preferences will change.

'**Aspect**' (i.e. South sloping or North facing) will be important in interpreting the presence of particular species.

Living stresses explain simple botanical systems.
E.g. In the desert, late afternoon is the baking-hot-sunlight side (cf noon in forest). Trees will be shiny leafed — to shed excess light (cf searching for more).
So consider the prevailing winds, salt spray, max. and min. temperatures, wet season, disturbance, trampling, fire, clearing, introduced competition or diseases, grazing, salinity, mineralisation.
Pioneer Species — These are the easiest to identify, because they are lonely.
Their preference is the saltiest, hottest, driest, highest, coldest, poorest, windiest, sand-blown, most flood-prone, …
If life becomes too easy, other species will smother them out. Hence, look for those that don't mind the hot baking Sun, etc.

There is a height-**succession** of plantforms grading from **lowest to tallest and deepest rooted**.
Ground lichen; moss; grass; herbs; creepers; shrubs; trees; ' emergents '
The depth of soil is crucial. The taller ones shade out the humbler ones, and their deeper roots seem to starve out the shallow-rooted ones from below. E.g. mosses need no soil and not much light, but will quickly be overgrown if these are provided.
Other factors keeping plants humble are trampling & grazing, fire frequency and dry season. Grasses survive all these stresses well.

Competition between species explains the more diverse vegetation.
E.g. Lichens overrun each other, and leave the rock surface, to become 'leafy' or fibrous or pendulous.
Lush growth betrays the most comfortable living conditions. E.g. rainforest; the underside of a rock in the desert; sheltered microclimates — crowded with species. This is opposite to pioneer species.
E.g. Where excess sunlight is the 'living stress', lush growth will show up on the shady side.

Draw the Skyline, the Ridge-lines, the Outlines
Label it with the 8 main directions



Talk the panorama into words. "Nor-Norwest Hillock, in front of a larger hill on the left, runs down into a gully behind NE– Plateau.
East Mountain is behind NE Plateau and drops away behind the vegetation south of us.
Distant Peak pokes up behind in the SW, and the closer skyline reappears in the West,
falling steadily to the NW Dip before the larger hill."

That took one minute. You do have time to look, notice, talk it through, and even draw it.
Marine navigators know that they have to.
Don't just imagine doing it, or do it silently, or do it half-heartedly — actually do it.
Unlike an avigator who uses a layout map to recognise roads, rivers, ranges, coastlines, etc, from the air,
a walker needs a nose-eye view…
MAPS DON'T DRAW YOU A NOSE-EYE VIEW — SO YOU HAVE TO!

Examine the Skyline BEFORE You Walk up to It

That might mean looking behind you, six hours ago, or to left or right, right now,
because the skyline ahead of you rapidly disappears behind foothills, just when you want a clear view of it!

A clear view of the skyline is uncommon, so you need to take advantage of any skyline view while you have it
— and that is often anywhere else except where you want to look — ahead.

Circuit walks and return trips mean that, if you haven't habitually looked at the surroundings abreast of you & behind you,
you won't be able to recognise what you are walking up to later.

One way to recognise the skyline later, is to use it
e.g. use it to keep track of bends; to keep track of progress; to disclose hidden valleys (by parallax or haze).

Another way is to name what you use e.g. "the hill behind the dam wall from camp 2—Dam Hill"

Mnemonic: "Down in the Mouth"

"Downstream" is "Down to the Coast". "Which coast? Which river mouth?"
Until you have answered that, you are disoriented.

You pass a creek-bed or a flowing stream: "Which way is it flowing?" is only half a question. "Where is it going?" is the other half.
You turn and head 'downhill': You think 'Down' — then say: 'Down in the Mouth — Which mouth?'

If you also ask "Upstream? To which ridge?" there are many possible answers because upstream is divergent.
Nonetheless it is good to know whether a river reaches to the very edge of the valley — whether it is a 'major' tributary.

Which way is the flow?

In dry, flat creek-beds, examine the tilt of the rocks… If any rock ever tilted up into the flow, it would be flipped over.
Examine the silt build up — on the sheltered downstream side of any obstacle.
Look for flood debris — matted against the upstream side of branches.
Consult your artificial horizon, if you have one.



(This is much like grass tussocks in the wind.)

Hint

Don't think "this side" & "the other side". It only makes sense for the one main lowest riverbed.
Think: Up-catchment/down-catchment/cross-catchment, overall, & Port half/Starboard half of the whole catchment in question.
(as seen from the coast, looking upstream)
Think plural: "the other sides"/ "another side" in the network…



Which 'side' of the river are you now? "I have crossed to another part of the drainage system"
Another possible answer: Examine the map for the contour heights of each channel for the lowest one.
"We are now in the starboard half of the catchment"

The Difference between 'Direction' and 'Track'

'North' is a general orientation reference **direction**.	But	'North from here to there' is a specific route — a 'bearing', 'line' or **'track'**.
'Stick to a direction'/a 'heading' means e.g.'toward sunset'		'This road points toward that Gap' will never change — it is a fixed 'track'.
It can start from any point,	cf.	'Stay 5 miles off the lighthouse' is a (curved) line of position — a track.
and sidesteps around obstacles, without bothering to return to track		'From this stump, past that tree, to the rock' — sticks to a fixed straight line, despite detours.

So the final practical 'interpretation' of, say 270°T.,
is not 'West', not 'sunset', nor 'Pot-set', not 'THERE!', not a drawing in your notebook, Not 'How hot it must be in Baghdad!'
but is a navigational track... "From this place to… that particular tall tree" "Then we will get a line on another point directly West"

I.e. Interpret a 'compass course' , finally, into accurate, achievable 'legs'—'on track'.

Continuous bends

Riverside tracks are especially sinuous, yet slowly so, so that they are deceptive.
Beaches near headlands, and lake edges, are especially insistent in their constant bending.
Contours, constant horizontal angles, and constant distance-off, are all continuously curved. Aqueducts follow contours.
Consequently we are necessarily **continually disoriented**, in following them.
No sooner do we get our bearings straight, than we lose them.
Logically then, you need to orient, not by a direction e.g. the Sun, but if at all possible, to **orient by a 'track'**
i.e. a particular path on the ground — it doesn't have to coincide with your own track, but it often will
e.g. from headland to headland. (The beach will then lie wholly on one side of this shortest distance 'track'.)
A visible, noticeable, landscape track is best e.g. the biggest river valley around.
You now can feel continuously oriented to something fixed, something which you can see & 'feel in your bones'.
As a second best choice, choose a fixed compass course e.g. a rhumb line, and watch where it intersects the landscape.

Follow the bends by anticipating the trends

Before you drive off, or plunge into the twists and turns of endless undulations, examine the map for your average course
— to give you some overall reference track ahead of you. It may be mental, or visual, or by compass.
You can see when you turn to the left or right of it, direction-wise. You can feel it when you drift too far to one side, track-wise.
Interpret each leg meaningfully. E.g. "toward the morning Sun"
(the time of day doesn't matter).
E.g. "Keep Mt Wellington on my port quarter".
E.g. "From the pine trees to the river mouth".
Divide the journey into recognisable sections, if it helps…
Make this a first priority, before studying any details.
Preferably, mark them lightly on the map.



“Mosses Mop up Moisture”

◦ “Mosses grow best on the shaded side of a tree” or a rock, ◦ where there is not enough light for competitors
◦ where there is little soil to hold the moisture, ◦ and it doesn’t dry out ◦ and often there is too much moisture for other plants.
Mosses actually monopolise the moisture
In hot places it is the late afternoon which is driest, so it is **the sunrise side, in a sunny climate**, which is the moister side.



Note: Dead moss is black and brittle.

Examine fallen logs — the shady side has a sheltered dark crevice...



In a hot climate, it may be more accurate to say,
“Mosses grow best on the sheltered side”

Examine ditches — One side might be scorched, the other, lush.
Examine bumps in the ground — One side is greener, with more moss and taller grass.
Examine underneath shrubs — for the moister, mossier, greener side under the bush.
Examine intertidal rocks — for moss-like seaweed growths on the shady, wetter side.

“Lichens Like Light”

Lichens don’t mind being dried out, so sometimes they are opposite to the mosses. However, not all lichens are so robust.
Lichens are fungi which live off algae entrapped and protected within (“Fungi Feed on Food”). They may live on mineralised substrates.
They are therefore very colourful. So the best way to learn lichen-likes is to open your eyes to the colours of each direction…

You may see white blotch lichens looking downSun but not upSun.
Yellow blotches may all be only looking uphill, not downhill. Leafy lichens like the shady enclaves, not the Sun-drenched flats.
Crusty greys and fibrous green might cohabit the underside of branches. “White paint” may only grow an the top of any rocks.
Orange granite might be just above high tide level, etc.
Diffuse lichens colonise the crumbly side of a sunbaked rock. Flat-topped rocks are trampled and won’t have thick lichens.
Look closely at surface colours of rocks and barks and soil-crusts— they may be due to diffuse lichens.
Look on the branches of shrubby growth — the lichens will grow best on one side or the other.

The idea is to start looking locally, before you need them. It’s a nice hobby. And hobbies keep you awake and observant.

“Fern Fronds Face the Front” i.e. the sunny side

Looking down-Sun, you’ll see an array of green topside fronds flat on.
Looking up-Sun, you’ll see more undersides & yellowness & edge-on fronds. It may not always show, but is clear when it does.
Tree ferns retain their lower branches longer on the sunlit side, and so seem to tilt toward the light.
(But in a windy place you will notice that the permanent lean, curve & frond-fall of ferns are downwind.)

Make a Mental Movie

Memorise a spectacular cliff looming closer overhead.
Watch the shape change. See the foreground shift. Notice the colours and contrasts. Look at the landscape flow.
Describe the silhouette. Peer into the deep shadows. Scan the skyline, looking at each interruption or change in trend.
Appreciate the hazy distance.
Follow a complete outline around, naming its shape.

Don’t forget to “record” the sound-track!

Initially try a full production only for beautiful memorable scenes.
With practice you may find that your memories stick for more and more locations.

Take Mental Photographs

Familiarity and Recognition are primarily visual. Your visual impression is adequately vivid, but your recall of it is faulty.
So put handles on the memory and you will be able to revisualise e.g. “where we found the weather balloon”.
To give your memory something to recall, take a detailed look.
The tricks are simply to give it a go, and to notice **the specifics**:

The colours, shapes, skyline, peculiarities, sequences — Talk about them.
Play a game: “Your turn: what else can you add to the picture”
Overlay some geometry on what you see — e.g. the log is parallel to the path and as far from it as the log itself is long.

Now close your eyes and see what you can reconstruct. Open them again and notice where you were wrong or were lacking detail.
Repeat this a few times until you could picture it in bed the next night.

Mental photographs are, after all, **your take-away memories**.
They are what names name; what “directions” talk about, what ‘recognition’ and ‘familiarity’ is based upon.

Take a Mental Photo of Each Change of Track

Where one subsection ends and another starts
— Look forward onto it, with the old terrain in the foreground and the new terrain joining on to it.
Now walk past the join, Look back, take in another view, with the old terrain now in the background.

This adds visual sequencing information to individual memories.

The Inside of a River Bend is Flatter Ground

The inside of a meander may be wider, sandier, marshier or of different vegetation.
On the outside of a meander, cliffs form, through ongoing undercutting. See also p.56a about the steeper North bank of a river (SH).
Consequently plan ahead and work out when to swap sides to find the easiest walking.

If the track becomes steeper underfoot, that would mean that you could be on the outside of a bend.
Check to see whether your heading has changed with the bending river.
If the track becomes flatter underfoot, this may indicate an inside bend (or a river junction)

Rivers Bend! Don't Forget to Look Backwards

Obstacles cause creeks to change direction. Outcrops of bedrock and creek junctions, for instance, cause bends, and this may be shown up ahead of time, by ridgelines pushing in closer, as you follow a riverbed.
Expect to meet a new creek clinging to the base of any ridge or shoulder which crosses your path, and also expect to change trend.

In addition, to that cause of bending, rivers follow contours and so usually are on a curved course anyway.
Furthermore, in the flats, rivers never follow a straight course but will 'meander'.

So if, while following a creek valley, you notice the slope underfoot changing, or the vegetation altering, watch out that the creek doesn't leave you, by bending away from you!

If you find yourself in the middle of a larger than normal river flat, suspect a river junction, and be very careful interpreting the trends.
E.g. you may meet 'the river' 'coming back toward you' when you were trying to go downstream!

So you can easily lose orientation while the winding river-track follows the lie of the land and gradually wends its way around corners!

Look ahead to catch the trend — and interpret it.
Look back, to see the extent of the curve.

Rivers Meander. Ridges Run Straighter

A ridgetop route will often prove shorter than following a winding river.

Keeping a Compass Course, by Legs

You can't see far ahead, but you can line up a rock or a bush which is in the right compass direction, then walk up to it.
It doesn't matter how you get there, as long as you get there.
Repeat the procedure, even if you can see far ahead — because, if you are merely following a compass needle or a distant landmark, you can "side-slip" off track.
Your eyes are freed from the compass needle while you walk.


Across the creek; Up the hill; Down the ridge; Through the tussocks
Required course
'Straight' forward!

Turn Smooth Bends into Sharp Jumps

Your brain wants something to "latch on to". A smooth bend is just the opposite! So make a series of straight-line "legs".
You "let go" of the last leg, and make a definite jump, to "latch on to" the next leg, and your subconscious smiles, and remembers.

E.g. 'compass North'; then 'to the tree'; 'to the peak'



Cut the corners as much as you can and extend as far as you can.

Mind Which Way You Go

The related problem for your brain is: "nothing critical is happening"
— no Junction, no decision, no dilemma, no emotion, no change —
Try imagining "Oh I hate veering left; I do hope the track tends right"
— to give you some reason to judge the overall trend, to notice the bends, to remember them.
Lay a bet as to which way a track will trend! Keep a tally, with pebbles, or by counting with the 0, 1, 2, 3, 4 system,
— and have a good argument about it.
"Will it reach 100°?" "Will it drop past 0°?"

Bush Noon— The Sun is Always out, If You Know How to Look

Trees & shrubs live in the light, day in, day out. You would expect that they should respond to the light, and lean or reach out to the strongest light, and throw out more branches and more leaves to the bright side.
The disposition of branches and leaves stays in view even when the Sun isn't out, and it lasts longer than a cloudy spell.
Although the Sun is a huge factor in explaining foliage asymmetry, be aware of other factors…

- A lake or sea can double the light intensity on one side, pulling the foliage toward it.
- A clearing will let more light in on one side.
- Down slopes allow the trees to see more skylight on the down-side, and less skylight on the up-side.
- Other trees can shield a tree from the Sun. Look especially for recently **fallen** ones on the ground, to explain standing branches
- The tree itself shields its own branches, so that most growth is simply outwards.
- Unrelated factors like gravity, wind, and wood collecting, alter the shape of a tree.

However, if you **average out** all the other influences, you should be left only with the noon-side Sun's influence — "Botanical Noon".
With adequate practice you should never again be "lost in the bush" because it is the thick bush itself which will tell you where North is.
You may have an initial hopeless feeling of "I can't see any meaningful asymmetry!" but the feeling will be temporary (eventually!).

Of course, this works best only where the Sun is always one-sided—in nontropical latitudes.
Hint: If a tree confuses you by pointing in the wrong direction, go over to it to learn why.

False Asymmetry

The slope of the ground
may be forcing the asymmetry,
rather than the differential in the lighting.
In the second diagram, there is asymmetry:
A is ungrassed; B is grassed.

False Symmetry

C and D are both grassed.

True Symmetry

B and C are both grassed.

True Asymmetry

A and D are differentiated from each other.



Dirt road wheel ruts...



False ("Chalk and Cheese") comparisons abound in Nature. True asymmetry is there too
Your task is to sort it all out.

E.g. Shaded foliage sees mostly blue skylight, which should make it long and lanky, compared to the red-end light from the Sun

E.g. the West side shadow is frostier for longer and the East side shade is cooler in the p.m.

E.g. the North side soil will be warmer deeper than the South side of a thick hedge

Look on the ground beneath a shrub, or log, for asymmetrical shade and shadow effects.

Remembering the Sequence, Needs More Than Logic

Logic is logical and helpful e.g. The bridge was after lunch because we were worried about the crossing over lunch.
The red rock was after that, because the second creek was dry — it had all those beautiful red lichens in it.
Then the funny tree was where we had chocolate, i.e. 3 o'clock stop.
But logic by itself is not 'sexy' enough to be emotive and memorable.
So deliberately add some emotion…
E.g. "lunch", "worried", "beautiful", "red", "funny", "chocolate"
You may need to add a song and dance, a gimmick, a clue to the time or sequence, distance or linkage.
The trouble with a memory gimmick, is that you focus on the gimmick, not on the memory itself.
E.g. If you use an acrostic, remember to feel the sequence of it, as well.

DO Something NUMERICAL

E.g. Lean one stick against "Walking-Stick Cliff" at one o'clock.
Sing two songs at "Sing-Song Pond" at two o'clock.
Make three cairns at three o'clock at the "T(hr)ee Junction"
Make four arrows on "Four Arrow Slope" during four o'clock.
Do it. Don't just imagine yourself doing it.
E.g. Scratch numbers in the ground, in sequence, as you pass points of interest.
e.g. "5FF" (the 5th stop, with the flat floor); "6SS" (six sizzling sausages—the fireplace).

Make a SHAPE; Match the SHAPE

Every or location in a forest track or in open country can be recognised from its **peculiar shapes**. Every bend or fork can be **matched to** the forest, or the shrubs and stones, so both the bend or clearing and the surroundings can be remembered, with joy.
Locations: What does this fallen log **point to**? What is **parallel to** it. *Place* something so it *does* **make a shape**.
How many shrubs do these three trunks enclose? What **face** or **picture** can you make out of the bushes, rock, clearing and the creek?
Do you see that **line** of tussocks; that **clump** of trees half-way up the slope; those parallel gutters; that oval of sand-dunes? Where does it drain? What **direction** between those **paired** stags?
Bends: ~Look for a tree trunk **leaning** over at the same angle as the bend of the track, preferably leaning over the track or bend and in the right direction. The tree stands out from all the others because of that. (Any lean at any angle in any direction will suffice.)
~Look for a branch **pointing** in the new direction, or curling, or **bending** in a way which mimics the track-bend.
~Look for a log **lying parallel** to the new direction, or any ditch, or line of rocks, or outcrop. (It doesn't have to match.)
~Look for a large rock nearby which **fits the shape** of the bend, or orient it until it does. (Matching shapes are always the best)
~Look especially at the tree trunk, or the shrub which blocks the straight line of sight ahead, or the shape of the fallen-over trunk in the way. E.g. "I'll fall into that black hole in the trunk if I keep going straight ahead! I'll have to swerve". "I need to go around that round stump". A tree **right at the bend** will be visible from both directions.
~Look for a forked branch which **matches the angle of a fork** in the track. **A series of parallel branches** at the fenceline. A couple of trunks **leaning towards each other** over the gateway. A tri-parallel set for a creek with two banks.
~Look for a branch which **points downstream**. Watch it for the next 50 years as it grows. A tree recognised is a friend for life.
~At a noticeable uphill pitch, find a leaning tree trunk and imagine climbing up it.
~Some leaning trunks can be interpreted in **reverse**… from top to bottom, to indicate the new direction.
The more you latch on to a peculiar shaped feature and the more you study its peculiarities, the better your recognition will stick.
Try to **double up** on the first peculiarity to clinch the recognisability. A **matching pair** of branches. A second confirmatory log.
You will have to **look backwards** at each bend if you want it to work well for the return trip.
Every bend and feature is a good chance to recognise another couple of trees. You stop at the bend and look around for your "friends".

Land-Form

Work downwards from a 'Big Picture' understanding. Start with a small-scale geology map, showing overall elevations.
Continental-scale domes (anticlines) & depressions (synclines) explain the overall drainage and watersheds.
Fault lines — shown by escarpments & cliffs — and individual ranges, interrupt the overall scheme.
The geological layers may be visible connecting across large distances.
E.g.


Pound
Range
Range
Easy walking on this side—don't walk 'against the grain' of the layers.
Plain
Plain

Layers become hardened and resistant to erosion when they are bent concavely upwards. They are compressed rather than fissured.
Convex layers are fractured and easily eroded, because they have been stretched. They will have been eroded away.
The present landform is a result of the erosion history on the previous landforms.

Hint

Most peaks have a steep side and a gentle side. Don't forget to make a mental note of that trend in relation to the rest of the land and the other visible peaks — you may notice a pattern, or simply keep your overall bearings better, or recognise the peak later, from afar.

What Makes a Cliff and an Overhang?

Resistant top layer



Reverse slope at the beach



The outsides of river bends



The cliffs migrate outwards

Waterfalls form at hard layers, at fault lines and at escarpments.
Look for outcrops striking across the land.

"End the Bend" i.e. Notice the Un-Bends

A bend is not simply a sharp corner, not just a change in direction: 'end of story!'.
It has a start, a curve, and **a finish, where it straightens out again**.
The curve needs to be **named** as a whole, **measured** as a whole, and thought of as **a whole bend**.
Look for the dividing points between successive curves

The arrows show where a curve to the right changes into one to the left, (a Z bend), & vice-versa (an S bend). These are "points of inflection"



— a straightening out, and remaining straight, is the other possibility.
Incorporate half of the straight section into each adjoining 'bend'.
At the end of each bend, reorient yourself — look behind, at the compass, at the Sun and your shadow. Point to 'home'.

Name the Bend, By the Trend, of its End

Trend:	Left, toward Mt Michael	e.g. "Viewmont Bend"
	Right away from camp	e.g. "The Long Right Leg"
	Left into Lake Jordan	e.g. "Left it down the Drain"
Handedness:	Hard left around the spur	e.g. "The West Bank Left Bank"
	Half left from the creekbed	e.g. "The Left Contour"
	"Clockwise Climb"	
	"Right around the Bend"	Bends will often alternate.
Direction:	"Ending with Sunset in our face — Sunset Slap"	
	"Turning until the Full Moon Rises on our Right — Werewolf Way"	
Compass:	"North Now, to Alaska"	
	"Left-Sou-West"	



Add some description
to seal the uniqueness e.g... Skyline: "Lone Pine Ridge" "Three Tree Hill"
Detail: "Uphill; On the Left Bank; Just past the river crossing; at 10 a.m."

Notice and Name Perverse Bends

Unexplained bends, or ones which buck the trend, deserve a name.
Most bends are predictable — around obstacles — at creeks — around shoulders & outcrops — shortcutting — contouring around sloping ground — at Y-junctions — joining with disused overgrown tracks
E.g. Seaside roads will hug the coast, go diagonally downhill but upstream (into a valley) and climb diagonally out of it, downstream — as a compromise between shortness and flatness.
E.g. For the same reason, tracks will often change direction at a creek crossing.

So name the curves that go against the flow…
E.g. "Sinister Switch" (Latin for left) "A Dextrous Diversion" (Latin for right) "Unorthodox Twist" (Greek: not "right" = left)
"A Wandering a Way" "Aimless Avenue" "It shouldn't've gone left!!" "The I'm-going-on-strike Uphill Bend"
"Mind Bender" "Morally Bent"



Higher Density of Leafiness on the Noon Side

From underneath, next to the trunk, you can look up in all directions and see which side is leafier.
Looking side-on you may see one solidly green side and the opposite side patchier in its cover.
Trying to look through the foliage to the back of a shrub, you will have most difficulty on the North.



The Lowest Leafy Branches are on the Noon-Side

Looking from the sunny side you see a lower branch or even a wall of greenery, right to the ground.
Low branches on the shady side are often short, dead or only thinly covered with foliage.
Looking toward noon, you see more trunks, dead wood & grey-brown sticks.



"It's the Shady Side that Shrubbery Shows up"

In practice you don't look for the noon side, but for the absence of leaves low on the pole side.
Looking toward noon, you see ill-developed shapes. Many plants will throw out branches and leaves in profusion in all directions, but you seek out the one direction which is different — the one less densely green — where the light is in short supply. It is **the 'light null' for solar direction finding**.
Look for where no vegetation leans: "No stems, plants, branches point in that direction".



Tall, Steep and Ragged Backside

Shade-side branches often reach for the sky, and are more vertical on that side, making it steep.
The noon side will be more of a smooth continuous wall of greenery from low-down upwards.



Wedge-Shaped

Looking away from noon, you see smooth and continuous foliage, slanted down toward you, often clinging right to the ground, like a wedge.
Looking toward noon you see flat tall backsides of the bushes.



Hollow under the Shady Side

You can stand closer to the trunk, or at least see more of the trunk more clearly from one side.
Down low on the shady side is where the light matters most. There may be space enough for a branch but not light enough. On the sunny side you will see leafiness deep into the low recesses.



Imperfect Shape on the Shady Side

Many shrubs seem to adopt a perfect dome shape, until you look more closely.

Gaps on the Shady Half.

The backside of shrubs is often tall, untidy, and lacking leafy branches, close to the ground especially.



Dead Branches

The overall shape may be perfect, but one side is alive and green, while the other side lacks leaves.
"Dead" South. There is a scale-effect to dead-south: The larger bushes have more depth of foliage.
The more foliage up-sun, the darker down-sun. Only the larger or thicker bushes work best.

Use a Type of Memory which you are Good at







Combine the methods for the most memorable effect.
E.g. pictorial — join images. Make them touch or glue onto, squash or hold hands, follow logically or overlap
— use a stack of pictures to put incidents into sequence.
"After the bridge we came to a red rock and then sat down for a snack at the funny tree"
E.g. ditties — A Capital Tee of Tall Trees at Three O'clock.
E.g. invented "associations"— a vivid or absurd image like a Tasmanian Tiger eating that hill.
Paint it in partly related colours, with shapes and other senses involved, to give extra "handles"/clues.
E.g. Imagine successive scenes in an invented journey/building/furnished room/street scene/pattern points.
Emphasise movement, and links between stages. Make it visual, simple, exaggerated and appropriate.
e.g. "I went inside the cave and talked to the sleepy bear (Ranger) about the bearing to follow, and he said "Seek the morning sun", so coming back out I turned to the east until I met the keeper of the bridge who said "over my dead body lies the path to right; and left". So climbing up over him...
E.g. numbers — One Wooden Bridge, Two Red Rocks, Three Funny Tree… to reflect the hours of the day
Make up a story with rhyme, from e.g. 1, bun for lunch, 2, through the dew, 3, see the sea… 7 rhymes with leaden/Heaven/redden, 11 with Aladdin/pelican/caravan/a raven, 12 with elves/shelve/delve/selves
E.g. shapes — Make a 10-rock pyramid at the 10 o'clock stop; an 11 stick teepee at 11; a 12 leaf hexagon
— e.g. see-saw on a log at 7 and draw a see-saw in your notes—it has 7 corners.
E.g. You can weave a story, of invented images to go with the times of day.
e.g. each digit looks like a... 0 hole/ball/eye, 1 stick/pen, 2 cobra/sphinx/swan, 3 bosoms/camel, 4 yacht/picnic chair
5 measuring scoop/wheelchair, 6 bomb with a fuse/yo-yo, 7 arrow/step, 8 shotgun/glasses, 9 balloon/comma,
10 ball bouncing off a wall/golfball off its tee, 11 jail/stump/goalpost, 12 jail-break/caged lion.
E.g. acrostic — 7 a.m. Z. for Zero Rule Zero: Don't forget to pack the lunch!....7:15 A Bend A in the Creek
7:30 B Bridge across the River at Bend B. 7:45 C We didn't Cee the third bend on the map!
Using this method, elapsed hours happen at Z,D,H,L,P,T,X i.e. every four letters.

Use the Name of the Track for the Acrostic

L ying down tree
E ee! There's a bull!
E e-normous bracket fungus
S wim
P addled Across
A lternative Detour
D
D
O
C
K
S

*Every quarter of an hour, look for things beginning with that letter to remember that kilometre by.
*four letters make up one hour *Use stepped word pairs, 'Lying East-west; Exciting Exit; Extra Searches
*Do Something Alphabetical
E.g. Lie down at L; Scream at E; Examine the fungus at E; SPlash at SP
*Make all your names begin with that letter e.g. Pot-holes, Pines, Possum trees, Possible campsite, Photo
*Write them all down, but try to memorise the best one.
*You can attempt to improve the sequencing, by taking the letters two or more at a time e.g….
LE In the Lee of the lying down tree
EE EEE!
ES E.S.P. told us to find the track next to the E-normous bracket fungus
SP Splash Splash. Had a Swim
*Try also to relate picture to picture in sequence e.g….
Look at the Long horns on the Lying down tree; Enormous bull!; Enormous bracket fungus, dripping with water… Swim!

Acrostics combine individual memories with a clear sequence — firstly by letter, and secondly, by overlapping one pair of letters with the next, and thirdly by overlapping one picture with the next.
You have already memorised many long sequences of letters, e.g. the words of a song, which could be used as a unique acrostic.

Headlands, Bays, Prevailing Winds, Longshore Drift of Sand, Creeks

Headlands are ridges. Bays are valleys.
The ridges determine the headlands, bays, creeks, and — look for this — the position of offshore rocks and islands, especially where a 'point' marks a change in the trend of the coastline.


Island
Reef
Headland (Ridge)
sand drift
….sand spit
Prevailing wind
Bay (Valley)
Lagoon
Flat; dunes
This creek changes course near its mouth due to the longshore drift of sand
The creek clings to the Pole-facing side of the headland
One main creek per bay

Beaches — Slope, Particle Size, and Wave Energy

Energetic erosion washes away any small particles.
A steep beach is a high energy beach with big particles.
When it is deep offshore the waves break with high energy.



A flat beach reduces the energy of breaking waves.
A low energy beach is flat with small particles.
Sandbars and shallow sandy offshore seabeds make the waves break over a long-distance.


high energy well offshore
flat onshore
flat offshore
wide overall

Much the same seems to happen on land slopes — the flatter slopes have fewer rocks. I.e. the accumulated silt which is not washed away by surface water, covers up the larger rocks.

Sea-levels have been much higher in the past, so that there will almost always be buried boulders just above the present seashore.

Look Through the Trees, to the Sky and Skyline

This is a habit which stops you being befuddled by bends. You focus on the most distant thing you can see…

- E.g. the farthest tree trunk
- E.g. the skyline — ridges, gullies, peaks, light/dark division
- E.g. the clouds — but do stop to examine their movements occasionally!
- E.g. the Sun, the Moon — obviously the best, but they move too, and… don't look at the Sun!
- E.g. the dark blue polarisation band — Use Polaroid sunglasses if you are walking a forest track and can see only the sky.

Don't forget what is abreast of you e.g. a particularly tall tree. If you need to, look behind for some reference point.

Habits take practice to develop. This one is easy, because once you appreciate it, you won't want to give it up.
— It turns many small bends into a few major trends —

Periscope

Climb a tree. Climb a hill. Stand on somebody's shoulders. Or try this…
Attach a mirror (bigger = better) at 45° (try to be exact) to one end of a long stiff stick (e.g. a fishing rod)
— then scan the tree top horizon for landmarks.

Navigating by Trees

Tall trees on high ridges stand out against the sky and are visible for miles around.
Get to know the biggest, tallest, most visible ones.
Individual trees, gum trees especially, are wonderfully fingerprinted, by their branching pattern, outline, position & orientation.
E.g. look for the direction between the two largest branches. This stands out like a weathercock whenever you glimpse that tree again.
E.g. locate the relative positions of a handful of the best trees, so as to cover a wide area.
E.g. try to note the relative direction of pairs of trees.
Most big trees will have large branches to noon. So look for big branches which are *not* pointed to noon.

If you keep looking through the immediate green barrier for more distant (unmoving) skyline trees —
you will notice them and recognise them surprisingly often.


"East Branch"
West



'Solar-Panel' Tilting of the Canopy Top

Some trees may be 'flat-topped', but they are not 'level'. They tilt toward noon. Best seen from side on.



Wedge Shaped

Branches seem to know when to stop growing, and so manage to display
a fairly **uniform**, slanted **flat wall of leaves** toward the outside and especially toward the light.



Lopsided Lean

Branches on the backside usually reach higher to bask in the skylight.
Branches on the front side are more horizontal, lower and longer.
Some trees don't seem to try to compensate and simply leave their trunk behind, on one side.



Half-Dome

— an extreme case of a steep back side

NOTE that all these signs work best in open woodland, not in forest understorey, but not always...



One-Sided Leafiness

E.g. Banksia trees
Such extreme asymmetry often only occurs in the understorey — where light is limited.
E.g. After a bushfire a gum tree revegetates from the trunk — most leafiness survives on the sunny side.



Individual Branchlets

— show similar shapes to whole trees
— tilted, asymmetrical twig patterns, one-sided leafiness, etc
The effect will show up best on the east and west sides of a plant, where the lighting is most asymmetrical.



Bare Backbone

Look for it on individual branchlets, on the rear-side of main branches, and sometimes on whole trees.
You could run your finger up the entire length on one side of many shady-side branches.

Group Several Related Images into One

This is a standard method of making your memory ability efficient.
You have less items to remember—they become a few memory prompts, each to a handful of items.
E.g. 4 groups of 4… 6,7,8,9 a.m. / 10,11,12,1 / 2,3,4,5 / 6,7,8,9 p.m.
Write each group out visually shaped e.g. at the points of a square for a group of four
with 2 opposite squares for a group of eight
inside an infinity sign for a pair of items
List the hardest to remember items, first and last.
Group the shapes i.e. the groups, into another visual structure.
Use symmetry wherever possible—it makes it easy to recall.

The Start-Stop-Rest mnemonic (see Section 5. p.110) is a good example of this "clumping" technique—never more than a handful of things to remember, yet it leads you into hundreds of points.
Put the S for Sky at the top, and use a hexagon for the six start up points. Use a clock-face for TIME, and the compass-rose for NSEW.
Balance it all on a triangle, for the 6 a.m. start



Rock Typing

Hardness — how easily eroded. Keep trying to scratch it until you find something just harder than it e.g. your pocket knife.
Colour — what colour silt. Scratch it against harder rock and look at the colour of the crumbs.
Sedimentary — the components are not of local origin. Layers — sedimentary origins. Melted sediments — crystalline bands
Sand content — grano-diorite — pale & silica rich. Clay content — basalt — dark & mineral rich. Mineral crystals in it.
Crystallisation — small crystals mean rapid (surface) cooling; large crystals means slow (deep earth—'plutonic') cooling.
Mineral content — what sort of soils does it produce? Flakiness. Behaviour in fire (Caution!)— it cracks, blisters or explodes! Melting pt.
Density, Magnetism, Fracture Pattern, Transparency, Permeability, Acid Solubility—evaporites and marine deposits may be limey.
Understanding these details is a key memory aid, since it gives you more meaning to look for, to memorise and recognise.
E.g. in basalt areas expect a more diverse & rich flora & fauna.
E.g. in the sandy plains, expect rivers to run underground, trees to have deep tap-roots and to line only the dry watercourses.
E.g. in dry sedimentary areas, look for a harder 'evaporite' layer underneath.
You don't have to identify the mineral, but you should characterise the rock type.

Soil Typing

1. Climate drives soil typing. What is the climate?
2. Latitude drives climate. What is the latitude?
3. High altitude mimics high latitude. What is the altitude?
4. How is the local climate modified? Look especially for temperature and rainfall factors.
   E.g. ranges upwind? A cold landmass? Warm ocean currents up-weather?
5. Evaporation produces salty limey evaporite deposits, whenever the evaporation rate exceeds the rainfall rate. High-temperature and wind, speed up evaporation. Flat inland areas receive less rain. Where rainfall exceeds evaporation, the soils are acidic, leached, and deep. Does the evaporation rate exceed the rainfall rate annually?
6. Climate drives vegetation as well as soil types. Soil types drive vegetation. The three go together. What is the vegetation type?
7. What is the parent bedrock? Granodiorite produces pale, sandy, friable, well-drained, mineral poor soils.
   Basalt produces dark, clay, dense, waterlogged, mineral rich soils.
   Warmth & rainfall aid chemical weathering and erosion rates of the parent bedrock, and so produce deep soils.
8. What are the relative constituents? Shake some soil and water together in a glass jar and leave it to stand until it is layered. Organics & charcoal float. Heavy minerals, pebbles & sand sink. Silts lie on top of them; then clays. Colloids remain suspended. Organic remnants accumulate in soil when it is warm enough to grow plants, but cold enough not to rot them away quickly. The decay of organic materials then provides acids for leaching, provided that high rainfall doesn't dilute the organic acids. Can you see from the sort of soils how cold and wet it has been?
9. What are the depths & layers of soil? It is leaching which transports poorly soluble salts to lower layers, until the water table dilutes the acidity. Subsoil clays also accumulate where leachates are deposited. Evaporites accumulate just below the surface and above the water table. Dry areas have poor soil depth due to slow bed-rock weathering and erosion rates.
10. What is the soil colour? Red indicates partly leached soil — iron and aluminium salts remain. Paler, ash-coloured soils are left behind after further acid leaching. Black soils result from poorly drained unleached soils. The importance is that leaching reduces fertility due to the lack of soluble plant foods. Leaching is aided by warmth (except in the case of limestone which dissolves better in colder climates).

Bush networks

The bush roadmap is made up of a network of interleaved ridges and rivers.
Instead of a major road or a minor road, you have a main ridge or river, shorter ones, and dead-end ones e.g. a 'shoulder'.
A 'cross roads' is where two creeks & two ridges meet — a saddle.
The seashore corresponds to a boundary fence; Peaks and islands act like townships — they are a focus of 'roads' and ring-routes.

Don't Navigate by Networks Only

Networks are fractal — big **creeks** have little creeks running into them; **walking tracks** have side tracks branching off from them; big ridge lines have little **ridge lines** running off from them;
dirt roads have smaller dirt roads which have still smaller dirt roads joining in.
That is why it is difficult to recognise the scale of any map just by looking at the networks on it. The more detailed the map, the more detail there is to show up. The smaller scale the map, the more detail has to be left off.

So there will always be small creeks, unmarked roads, minor tracks and minor ridges to tempt you into thinking
"This one is what is marked on the map".
You will likely find one "exactly" where you look for it, but it may not be the right one.
Don't navigate simply by expectations of network junctions.
E.g. the next creek-line has a 50% chance of being "just as I expected it — a creek-line coming in from the right"
or if not expected, the 50% chance is that you will say "probably just not marked on the map"!
If by chance it is actually correct, it will only encourage you to continue navigating by network,
but you won't always pick the correct one.

Antidotes For Guessing at Network Junctions

- **Distance** covered. Accurate measurements of progress can eliminate some minor junctions which are "almost" where you expect the desired junction to be.
- Trend — of the junction branches. I.e. the **directions** must match your expectations too. E.g. "Each side of North"
- Landmark **bearings**. Try to separate identical looking junctions by cross-checking their position in relation to skyline features.
- Care.
- **Count**. Look-alike branches are nonetheless unique, when numbered.
- Recognition, from last time, if you had bothered to identify its peculiarities. I.e. bother now, for next time.

Branching Patterns — Examine Them for thickness, length, angle, curvature



At each node some branches
grow better than others
usually toward the light
i.e. stretching outwards
or up-wind upwards
or downwind down low.
Check the **spacing.**



The choice of branchlet
can **curve** a whole branch

or stiffen it
against the wind…



bottom view
looking up…



Side branches
can **curl** around
toward noon.
Examine the ends
of the branches.

This enhances the 'bare backbone' appearance
of the dark side of a trunk or branch.

A well-leafed branchlet will usually hormonally
dominate one without buds, by active biochemical suppression.
In this way growth can be regulated.

E.g. horizontal decurvature
can search out extra light
underneath the canopy





Branches
can also bend,
leaving tell-tale 'wrinkles'
in the skin.

Double curvature can fight gravity or wind.



Gum trees show asymmetry especially easily, since they do not try hard
to be symmetrical in the first place!

Examine the main trunk itself.
It may curve away from the light
to act as a counter**balance**
to the heavy light-side branches.





Or the trunk may be overbalanced, by its branches
lengthening, thickening and curling toward the light.

Length:
Some trees 'reach' for the light
becoming lopsided



The branches that
find the
most light
thicken most…



Angle:
To get out from under the canopy,
noon-side branches often
reach out a long way
horizontally…
Shady side branches
usually reach upwards
(except maybe in a windy place).



Look for wrinkles
under the 'armpit'
where it has bent…

Working Names — Invent Them

E.g. Past the 'Little Castle Rock'
Up the 'Yellow-Crowned Tree' trail
Under the U-shaped rock face
Between the Big-Boulder Bluffs

"40 minutes in" is a handy name — when you recognise it, coming back out.

Stupid gawky names help you remember, but even better is to do something stupid to match.
E.g. Gallop like a galah, through the pass, and call it "Gallop Gap with Galahs Galore!"

Standard Name Plus Personal Name

Actual names last longer and are widely known. Use them.
But make up a personalised name too.

E.g. "Oh it is actually called 'Boomer Hill',	but we call it Porridge Hill, because it lies halfway between Oatlands and the Table Tier!
E.g. We call Wollongong "Kaus Australis"	'coz that's where we watched Kaus Australis go straight overhead.
E.g. Kaus Australis becomes	"The Wollongong Star"

Remembering Names

To help you later, when the name is 'on the tip of your tongue',
Count the syllables, consonants, short vowels, long vowels, now.
Rhyme it with something appropriate e.g. Condominium Creek has a pond of minimum seep.
Look at the spelt visual shape… for ascenders, descenders, double letters, symmetry.

Then later run through the alphabet for a guess at the first letter, then at the second, and so on.
Think about anything related, like why you went, what you ate, who you met, what you saw, the weather, the season, the news at the time…
Ask each person for these recollections. Recreate the full scene.

Contour Lines

Contour lines mark horizontal ground.
A simple trick to match up the map contour lines and the landscape, is to **point horizontally** parallel to the ground.
E.g. if you are in a valley, point along both creekbanks, using both hands. The steeper the valley sides, the narrower the contour angle.


Contour lines on the map
Horizontal ground on the creek beds

Contour lines are like water-marks on the bank of a reservoir, lake or swimming hole, visible after the water-level has dropped.
But bigger like a global flood drying up 10m at a time, leaving water-marks.
like a photograph of it, from above.
like horizontal slices progressively taken off from the top of the mountains, as when you slice clay with a thin wire and you look at what is left.
like building up a model landscape one layer of cardboard at a time, from below, with progressively smaller shapes cut out according to the map contours.
Then you draw the results on a map.
They show the path you have to walk to go 'around the contour' so that you neither climb nor descend.

Contour Navigation: **Practise** It, **Before** you Need It

At night, or in fog, or in a blizzard, you may have no other clues, but the contours, on the map, and underfoot. Try to match them up.
Hint: Don't expect every little bump to show up on the map, but only the average smooth slope.
Hint: Keep good track of compass direction, time & distance as your best crosscheck. Assess the wind. Use an altimeter (,GPS, radar…).
Hint: **Delegate** tasks — map reading; course holding; distance logging; slope assessment; exploration; memory…
Hint: To go quicker, go slower — so as to be sure. Explore the slopes to left and to right. (But don't get lost or disoriented!)
Hold regular conferences to check your judgments.
Hint: Assess slopes by looking sideways, across them. They always seem so steep when you look up!

Boat navigators in a fog, can sail toward land until they reach a predetermined depth, then sail along parallel to the coast, using the depth contours marked on their chart, and some method of finding the depth. Marine depth sounders rely on a good echo, but you can always toss a weighted line over the side to find the actual depth. Make sure to make corrections for the depth of the depth-sounder, the depth of your keel, and the height of the current tide!

Sticking to the Bush Network

- Walking **up-ridge** may perch you on an isolated hillock.
- Walking **down-stream** must get you to salt water; or at least to water, civilisation, flats, roads; but also to thicker vegetation and a loss of view; and sometimes to impassable waterfalls and gorges.
- Walking upridge, uphill, upstream lands you in steeper, drier, more jagged terrain with more open vegetation, a better view and maybe an along-ridge track.
- Walking down-ridge will "take you to the lake", but simply walking downhill may lead you into a heavily vegetated creek-valley which then drains into the lake.

Natural Routes Naturally Converge

That means that, in reverse, they must also **diverge** — which is dangerous, open to mis-navigation.

- Provided you don't cross catchment divides, walking downstream or up-ridge is **convergent** and so is safe for a one-way trip, but **un-safe as a means of retracing your steps back to base**. E.g. it is easy to climb a hill, hard to retrace exactly.
- Walking down-ridge is **divergent — deceptive and dangerous**.
You cannot easily see ridges peeling off below, and the map won't mark all the creeks you can see.
If you are trying to retrace your steps or navigate from the map, you will have to be very careful.
- Ridges converge to hilltops — so walking **downridge** leads you widely astray.
- **Upstream** is divergent — you don't know where you will end up, but at least you can find your way back, because creeks converge toward the river mouth.
- Tracks & trails converge to: popular features, bridges, car parks, waterholes, homesteads, campsites, clearings, etc.
So **leaving a focal point faces you with multiple choices** "How on earth do I get outta here!"

Coping with Divergence

The result of "directions" such as "You can't go wrong. You can't miss it" is that the truer that is, the easier it is to go wrong — after you have found it. Retracing your steps, or finding the desired way out, onward, can become a nightmare.

- Ask directions for the onward bit, not just how to get there.

For backtracking…

- Pay attention on the way in, despite your excitement at arriving. Note the direction of your arrival. Look back regularly. Mark the junctions you used, especially from minor out onto major paths. Retrace your own tracks.

Reverse logic

Be like yachtsmen, who should always explore harbours, shallows and tributaries at low tide "in case we do get stuck".

- Explore upstream — a divergent labyrinth — so that you can walk downstream to return.
Provided you don't cross water-divides, or overshoot your starting point, "you can hardly go wrong".
Ahah! There's the hint: Before you set off upstream, peek behind you, to see when to stop "coming back downstream"!
- Explore downridge, and climb back upridge later. Only don't climb down anything you can't climb back up.
- Explore away from a focus, so that you can converge back to it.

Isolated Vegetation Shows the Clearest Asymmetry



E.g. Look in any **clearing** for downwind debris/erosion,
and for up-Sun/down-Sun asymmetry at the edges.
E.g. an isolated tree in a paddock...
E.g. an open creek will give the bushes a clear view across the water...
E.g. a roadway will exaggerate the light asymmetry on one side
and suppress it on the other...
E.g. Look in the wheel ruts of bush tracks for asymmetries due to wind & light…



Examine **the tallest trees — The emergent ones** have a clear view of the Sun.

At the **edge** of a clearing, subtract the effect of wind…



Closed Canopy — Look for Gaps

Each tree canopy might look uniform, but be blown back on the upwind side, leaving a gap there, with dead branches, where it *has tried* to fill the gap. But look for a gap without dead branches and without other explanation — It might be 'shady south', which gives the tree little incentive to cover. The tree *could have* spread that far by now, if it had wanted to, but hasn't.



Tall and quick growing saplings **show the most asymmetry…**

They can be the best tell-tales of all, and the worst!
Because they respond to clearings, slope, water-shine, nearby trees — be careful!
Take extra care to average out their message.
Any one tree gives you too definite an impression!
Back-to-back saplings may show opposite asymmetry, by shading each other...
Treat the overall shape as one tree.
The sapling effect, arises from young forest trees shedding branches more often and more easily than mature trees.

Roadsides & Campsites Reverse Some Effects!

Examine trunks for broken or lopped boughs before interpreting!
The bigger lower branches are easiest and best firewood pickings!



Name the Subsections

Heart-Attack Hill	Bust-me-gall Bend	Starve-gut-Ridge			: Be Vivid
On-the-Double Decline	Cross-the-Creeks Roller-Coaster	Blackberry Bank			: Be Descriptive
Left-hand Loop	Clockwise Climb	Right-around Contour	The Zed Bend		: Be Cheiral
N-E Straight	Into the Sun Slog	West Bank	Downwind Dunes		: Be Directional
Long Leg	Short Stretch	The Middle Mile			: Tell the Distance
Last-legs Leg	Dinnertime Creek	Sunset Strip			: Tell the Time
On the Left of Third Hill	Nine Mile Beach	Five Ways	Fourth Island		: Count
The Bush Blocks	The Rock Band	Turning Point	The Up-Part	The Trip down	: Be Clever
Rubble Ramble	Possum Passage	Flower Flats			: Alliterate
The Birdwatching Bit	The Deer Park	The Gloriously Green Glade			: Be Observant
The Monkey Saddle (three creeks)	The Big Bulge	Round Shoulder	Tight Turn Tongue		: Be Shapely
The Breakaway	The Hither Side of the Hill	Round the Rim	Unto the Brink		: Be Literary
Brown Beach Bay	Wobbly Shacks (= Mount Wobbly behind the shacks)	Zigzag Track			: Be Visual
Perverse Reverse	Inland Cusp	Round the Back	Out to Sea and Back		: Name Whole Curves

Name the Sequence

Fit Each Subsection into a Larger Scheme.

- Name the Links : The Cuvier Track The Mount Barker Road The East West Ridge
- Name the Junctions : Point Pass Steppes Junction Tee -tree Junction
- Contextualise : Beyond Burrowing Crayfish Ridge Cross Catchment Climb
- Overlap Sections : Deer Sally to Sandy's Shore to All-Terrain Trek } these are simultaneous
  Sherwood Forest to Bumpy Flat to Uphill Haul } and overlapped 50%
  I.e. halfway through one section, think about how it is changing character
  into the next obvious section, and anticipate it.
- Time-Distance Clues : Lunchtime Lookout The Approach Thither Heather Tea Junction Ten-Mile Dam
- Lie-Linkage : Downstream from Dusty Waterfall Wind-Shadow Plateau
- Numbers : Fourth Bump Fifth Creek Tee Junction # Three
- Acrostic : Short Steep Step in the Southern Subdivision after the Shallow Segment

Contour Curves: Your Job is to Imagine the Shapes into Life And to Match the Lines to the Landscape



Deep Vee 'Ditches'
— they gather water.



The **sharp** points, point **up**-river. (sharp/up rhymes in p)



Round 'Shoulders' — they shed water.



The **round** points point **down**-ridge. (round/down rhymes)

— being higher ground, they separate gullies



Peak or Depression — you can't easily tell which. Peaks are much more common.



Hairpin 'Ridges' — they can look parallel, like 'a slope', if the edge of the map cuts them off.
Ridges usually show much rounder than this.



Parallel 'Slopes' —be careful about which way is 'up'. Check that they are not the same height—on a ridge or river



Here is a typical confusing array of parallel lines.
The first two are ambiguous, but seem to lead down into a valley…
The valley is shown as lines 3, 4 & 5…

The three corners here are all sharper than the corresponding ridges.
Downstream is to the left…
Imagine a deep-vee ditch.

The shoulders and peaks shown here are all much rounder…
..Uphill is → peak ←saddle→ ridge or peak ……….
Imagine a circular mound with a spur down to left and right.

Down here, upslope to higher ground is…↑

Trackless Navigation

When you leave the bush network to cut across the natural routes, you still navigate by them, by noticing when you cross them.
You choose a route in relation to the framework — of ridges, rivers, and the contours that cross them at right angles.
E.g. "I am now going diagonally right, uphill, on the left bank, to the Ridge, then…"
You describe the sort of route you are following, and **start a new subsection whenever that sort of route changes** in quality.
E.g. A dry shallow creekbed marks a change from downhill to uphill.
E.g. The major break of slope—on the "hillside"—marks the change between being on the "hill/crest/ridge" or in the "valley".
Don't forget to ask, as you cross each 'road', what that ridge or creek is doing, to the left & to the right e.g. joining, splitting, rising, falling, dividing major valleys.

The method of Names

The point of this method is to bring your normally subconscious memory into conscious focus.
You put a **name** i.e. an essential description, onto each subsection. This is in addition to naming the creeks and ridges you cross.
That is equivalent to supplying your own signposts & flashing lights to the landscape. But write down the other details also.
As with memorising any journey there are a handful of steps: Notice; Recognise; Describe; Name; Remember; Put it into Sequence.

Bush Networking Essentials

Answer up to six backbone questions about each leg, before deciding on an appropriate name for that subsection…

1. Hill-wise — What Peak? — Is your direction trend in relation to it Uphill or Downhill; towards or away?
2. Hillside-wise — Slope — Choose between Upslope/Downslope/Flat/Contouring.
3. Ridge-wise — Rise — Upridge/Downridge/Crossridge?
4. Drainage-wise — Lie — Upstream/Downstream/Crossstream?
5. Side-wise — using the standard names* — Left bank/Right bank (below the break of slope); Right flank/Left flank (above).
   *As a yachtsman going **up-**stream sees it — Port and Starboard. Use these terms in your names to remind you.
   As a traveler going **up**-ridge sees it.
   I.e. the standard directions are **up**-stream; **up**-ridge; **up**-north; **up**-wind; **up**-hill, **up**-slope.
   Be careful! The 'right bank' is the 'left flank'. You can climb to the right on the left flank (of a ridge which falls to your right).
   Walking diagonally 'downslope' can be 'upstream'.
6. Hand-wise — Tack — Clockwise around or Left around/On the left diagonal or Right diagonal?

Mnemonic: (With your right index finger) touch your **head** (the peak);
forehead (the slope);
bridge of your nose (the break of slope);
down the ridge of your **nose** (the ridge);
nostrils (the drainage);
right **cheek** (the side);
and now look at your **hand** in wonderment (What is my tack?)
Then **point** out some peculiarities...
Now **add the non-essential** — exact measurements e.g. direction/length/time/steepness/count —and descriptions, sequence, context.
(Remember: don't navigate only by networks.) See opposite, for descriptive names.

Flowers Respond to Sunlight



Examine the stalk-lean and flower-head tilt
e.g. of daisies.
Look up-Sun and down-Sun to see the striking difference, whenever the Sun is low.



Look for the first flush of flowering on the sunny side of a flower spike
E.g. Yakka (Xanthorrhoea). The mid-morning sunlight direction gets the earliest flowers.



Examine closed flowers to see whether they betray where the Sun last came from.
Many flowers 'follow' the Sun around.

Some leafy stems seem to tilt to the noon, perhaps to point their terminal flowers into the Sun.
E.g. Sea Spurge



(Top view)
Banksia pistils sprout earlier on the sunny side.

Banksia stamens deepen in colour on the sunny side.

Fruit Distribution and Ripening



Some bushes will fertilise more flowers in the sunlight because pollinators can see them better.

Fruit are fertilised flowers. So some species 'set' more fruit on the sunny side.
Look in all directions to see which aspect presents the most flowers or fruits to view.

'Ripe' colours are a result of sunlight e.g. apple, peach.
Sun-ripened colours aren't confined to fruits.
Mushrooms are often old enough to have seen some sunlight.
One mushroom in the open may not help you much, but they do come in flushes, so look for a *pattern*.

Remember the Sequence from AA to ZZ

— A Ready Made Acrostic of memorable unique items, with endless extension if needed. I recommend it as the pick of the mnemonics.

You may need to remember each tree in a forest walk, or every twist in a path, or every choice in a maze, or every square in a grid.
AA to ZZ supplies 676 *differently named and sequenced letter pairs*.

If you turn the letter pairs into appropriate *two word phrases*, there is no limit to the useful memory aids.
E.g. I could call this system the Alphabetic Zygote (of 'letters paired' A-Z).
As with all gimmicks, it only works best if you *study and* ***memorise*** **the object** ***receiving*** **the label**.
Examine the tree for anything which could attract the label DF (damp foliage; dendritic form; downpointing flowers),
or mentally *photograph* the MS munch-stop, or *actually* bird-watch at BW.

It's up to you to use the letter pair in a memorable way. Don't forget to use visual, emotional, sequenced and appropriate words.
Consistent rules help.
On a pure sequence walk, begin with double letters, rather than with A-Z single letters. This makes two word phrases the consistent rule.
In fact begin with *any* double letter, but especially **the initials of the walk**, e.g. BL for Blackmans Lagoon.
Two word Phrases e.g. AA = Ask Again, avoid the ambiguity about which other letter in the word or phrase might be emphasised.
E.g. is Aeroplane, AE or AR or AP or AN? Was 'Anabolic steroids' A or AS?
Add a third word to the phrase as needed, to spell out what it means, e.g. Backwater Island turnoff.

The trick is to make the mnemonic **match** the feature.
E.g. if there is a plague of mosquitoes which you attack with a stick, Aaron's Almond-tree walking stick might be appropriate for AA.
Then the need is to somehow link the previous with the next.
E.g. AB Aaron's Budded walking stick (if you know that story), might focus your attention on the buds in the next gum-tree.
Without a '**theme**' it is difficult to pluck out your memory what 'DF' might have been. But 'Doctor's Emergency' where you stubbed your toe, leads on to 'Doctor's Ferari' when you walk on quickly anyway, and on to 'Doctor's Gasoline' where you topped up with lunch.

If you do a 'grid-line walk', you use A-Z to begin with, and say you move from A0 to C4; you might go through A1, A2, B2, B3, C3, C4.
The memory aid goes A0, then Ahead on 1 leg, hopping, then Across, on 2 legs, Ban-tu, Ban-three, See the three cattle?, Count to 4...
'Minus', in cases of ambiguity, might come out as 'which was 4 metres deep', or 'where I left 4 pebbles behind', or 'and Not 4 blisters' or 'at anything but 4pm'.
When you get into AD you look for a-d **peculiarities** to remember like 'Add 4+6 wattles (to get 46)' or '33AD crucifixion tree' or 'Adder-Death, two score of them'.
As an alternative, name all grid squares with *letters*, e.g. D-G, and look for things to name, such as Dark Green; Discarded Gaiter.

In a maze, you could choose Long words for turning Right; Short words for turning Left, a mixed phrase for Straight Ahead. These match the meaning-words in length of sound.
Maybe you need some **variations**:
One, two, three or four syllables for left, right, through, reverse.
Long first vowel sound vs short vowel sound.
Begin with one *letter* and *end* with the other *sound*, e.g. Amanda, Abib, Ace, Add, Abbey…
Let sounds take priority where needed. E.g. few words start with K, but many start with a hard C. X is hard unless you allow Ex-.

Memorised sequences are most effective if revised almost on the spot, e.g. via a leap-frog walk (2 forward, one back), and on the return.
Equally, other methods are enhanced by adding this mnemonic, such as when marking a trail, writing track notes, or making a mudmap.

Contour Heights: Read the Numbers!

Determine **the Contour Interval** — and interpret which way is 'up' from the **numbers**… Note: On maps, the numbers are printed to be read as if looking **uphill.**



This first diagram is "every 50 m".
And 'up' is toward the top.

Zero means "sea level"
Read the absolute numbers!



In the second diagram, the contour interval is every '10 m'

'Up' is now downwards.



Note that **major** contours may be marked as thicker
e.g. every 50 or 100 m



..The first is a peak; the second is a hollow...

Marine charts show spot-depths, 'soundings', in metres and decimeters, below lowest water, with offshore depth-contours.
If the "depth" is underlined, it refers to a "drying height" of intertidal rocks.
At sea, keep a record of the soundings as you sail in to land, preferably in a straight line. Plot them onto tracing paper or mark them on the edge of a ruler, and try to match the pattern to charted depths.

Contour Spacing: Close = Steep Slope



Wide spacing = flat land Examples: mountain plateaus; valley floors; paddocks; dunes
Irregular contour shapes (meandering all over the map; not shown here) = very flat land

Slope

Ridge — carefully notice when numbers are identical. **The rule "Closer Equals Steeper" only holds for different height levels, not for hairpin contours around ridges or rivers.**
In fact, "close" might equal "flat" i.e. on a ridgetop

Slope

Cliff — Very close = Very steep

Slope; have you worked out downhill?

Walking "Straight" through the Bush

- 'Straight' downstream; upstream; down-ridge; up-ridge; uphill; downhill
- 'Straight' around the contour
- 'Straight' along the path of least resistance
- 'Straight' through the obstacle course, dodging to left and right
- The Line 'of Best fit' — to a chosen trend cross-country

None of these are straight, but most are easier than 'straight across a slope' — crossing innumerable ups and downs!
Most are predictable.
The navigator simply goes last in line with a compass and logs the twists and turns, whatever course that takes.

Why last in line? It is a fact of life that following your nose through the bush quickly disorients the leader of the party, while those following behind maintain their bearings easily.
Also, to clearly show up the trend of a sinuous course, the last person can drag a long smooth string loosely behind him.

Straight around

At a…

- Constant Angle—to the (changing) Sun, Moon, star, planet, landmark e.g. keep the peak "ahead on your left" — a spiral course.
- Constant Distance Off — as judged by the rule of thumb — you keep a prominent landmark appearing to be a constant size — from base to peak. The course is circular, concentric to the landmark. E.g. offshore, around a lighthouse.
- Constant Horizontal Angle — between two prominent features. This gives a cusp-like circular course.

You can retrace these courses, but the going may well be difficult — crossing many streams and ridges.

How to Walk in an Unintentional Circle

Haven't you heard of people walking in a large circle when they are lost?
They thought that they were walking in a straight line, but some hours later they recognise the same scenery!
I've done it; it's no myth. Discover your natural drift...

Blindfold yourself. Try to walk straight across a flat. I bet you can't.
Most people have one slightly shorter leg, usually their left leg.

Now try to walk across a slope, blindfolded of course, in a straight line. I bet you drift.
But once you realise it, you are just as likely to head uphill too much, in overcompensation.

Don't trust your senses in a fog. Find out by trials at home — before you find out the hard way — how far 'off' you are.
Also find out how to properly walk in a straight line in a fog!

Stem and Leaf Colouring



Samphire saltbushes
colour up
on the bright side

Many other plants
show red stems
or leaves etc
Look for a paler side.



Look from the top
and sway side to side
to find the deeper colour



The colour deepens on
the bracts higher up
on the sunny side



Succulent leaves redden up
on the bright side. Look one
way over the flats & it is
pinker than the other way,
especially just after sunset!

N.B. Older stems may show a reverse trend! The colour fades on the sunny side after having deepened more while young.

Beware: When flower-stalks twist as they grow, the colouring or fading effect is unreliable. You can detect the twisting *by* the fading.

Example: Blackberry stems and leaves redden in sunlight, staying green on the shady side.

New Growth is Colour Differentiated

Looking up- or down-Sun (on a cloudy day) will show up new growth as yellowish or brownish or bluish (depending on the species) in one direction more than the other.
The sunny side will 'green up' the new leaves more quickly and will look more normal coloured.
But test it out first — it may go the other way — sunlight might promote new growth, before it colours it up.
When new growth is distributed throughout the shrub, the sunny side will often show deeper green (i.e. more of the same pigment) and be more vari-coloured e.g. some leaves take on a red blush or red margins in response to the Sun.

Revise your Memories

..after a 10 minute distraction
..after an hour, a day, a week, a month, a year e.g. for an acrostic which you wish to remember permanently
..and whenever after, when you begin to have trouble remembering
Choose undistracted, mindless times
e.g. while trudging or being driven, waiting or relaxing, or last thing before sleep, to run over things in your head.
Overpractise your mistakes. Out loud is always better. Take any opportunity to tell someone.

To Remember Formulae such as those at p. 19b

(1) Make up memorable ditties, and refresh your memory, as above, before you lose them.
(2) 'Read' the formulae *for sense* — They are just shorthand for how things *must* behave. If you don't like maths, it's probably because you never understood the common sense behind it, and that is probably because you never had the opportunity to see it, or developed the skill to read formulae.
E.g. '**Sin, Sin, Sin! It's High Latitudes which Declines it**, for both Easterners and Westerners'
for: the three sine ratios in the formula… 'sin (**heigh**t E-W) sin (**latitude**) = sin (**declin**ation)'
i.e. as the latitude increases, the height must decrease, and vice-versa, to preserve any sin (dec) figure as constant.
The formula should return zero height for zero declination, and 90° height for dec=lat.

This next one assumes that you measure the angle away from East-West (rather than from the 'elevated pole', as on p 19b).
You can use 'sine of the variation from E-W' instead of 'cosine of the angle from the pole', because 'co-sine' says 'sine of the co-angle'.
'The sin of the increasing the sunset angle, by cause of increasing latitude, is a sign of decline'.
sin (sunset angle) (multiplied by) cos (lat) = sin (dec)
Read this as: For any specific declination, as lat increases (=the cos reduces), the angle must increase, to preserve a constant sin (dec).
You can also put in dec=0 and expect a 0° answer no matter what the lat.
At the Equator, declination directly determines the direction of set N or S of E-W.

'Why bother with the E-W Sun? Be**cause of its E-W *timing*!** It's **today or too late**' t for tan; d for dec; late for lat;
90° = 6hrs each side of noon cos (time of E-W) = tan D / tan L, *'or' for "o'er" for 'over'*
Lat = 0 throws the calculation into a spin, because any declination other than 0 can't be E or W. Dec = 0 must return 90° for any lat.
Dec = 90 must be impossible (it's N or S!), but so must any dec > lat, since cosine doesn't go above 1. Those stars stay polewards.

'One New Day at a Time? Not quite, **'cause for tomorrow's sunrise time, today's time's not too late**!'
It changes only slowly, as dec changes. cos (time of sunrise) = tan D x —tan L 15° = 1 hr. each side of noon
0,0 must return 90°. Opposite hemispheres must return a large positive cos and hence a smaller angle, and a short day.
Same hemispheres must return a negative cos, which means a long day.
Too much lat, and the tropical bodies disappear altogether, as expected. Too much dec, like a circumpolar star, and it won't even set.

Try **the Equation of Time**, p.17b.
The First FFive months, From FFebruary, Fence-sit Four Features (halF-each side). The next 7 *finish* at four more features.
–1**4**,0,**4**, 0, -**6**,0,1**6**, 0 Makes nice mirror patterns of the two sets of four features. Minus means a fast Sun, up early; a 'slow' clock.
FFFebruary Founders at FFFourteen; Marches up again; April crosses (its hot-cross buns); May turns 4; June double-crosses;
July *finishes* work at six; August rises augustly, to zero; SSSeptember and October get up to SSSixteen;
November and **Dec**ember **dec**line a lot; December crosses at Cross-mass; January Sun decends from the cross, fast, for a new year.

Contour Slopes: Work Out 1 mm and 1 cm Contour Spacing



Example: a Rise of 10 m in a Run of 100 m is a Slope of one in 10 and an angle of 5.7°
[Tangent(angle)=rise/run Angle=Arctan(rise/run)]
rise/run is technically called the "gradient" i.e. an up-slope.

1) Example of 1 mm contour spacing: A 1:100,000 map-scale says: 1mm equals 100m (See 'map scaling factors' p.92a)
with 50m contours the slope must be 50m every 100m or 1 in 2 or 26°½.
2) Example, with 1 cm contour spacing: 10 times less slope, in the same example, or one in 20, or 3°

Using these 2 reference spacings (**work them out again for every new map**) fit the actual contour spacing (eg 3mm) between them.
E.g. map scale: 1:25,000 (1mm = 25m); for 10m contours, 10m rise in the 1mm run, on the map (=25m in reality) is,
"1mm contour spacing = 1 in 2.5"; (10mm contour spacing) = 1 in 25; (20mm contour spacing) = 1 in 50;
So… 3mm means 1 in 7.5

Reference Slopes — To Imagine the Climb with!

One in one; 45°; One up / one across; On all fours!
One Degree is 'one in 57' (or approximately 1 in 60) So 10° is 'one in 5.7' — maximum for public **roads**
One in Four is 14° — a neat coincidence to memorise. So One in 40 is 1.4° — maximum for **railways**
36° slope — 8 in 11 — more or less maximum for sand, gravel, scree, or any loose material.
Small slopes may be multiplied with approximate linear accuracy, but in an **inverse** fashion…
Examples: 2° is one in 30 — from the one in 60 rule
1 in eight is 7° — from the one in four rule
5° is one in 11 — either from 57/5 or from 5.7 x 2 or 1/8 of 36° see also "sine-cos chart" p.106b

The Beaufort Wind Scale — Modified for Bushwalkers

One in 40	contour lines absent or rare; pleasant ambling; wind whistles through the lips; grey hair relatively common
One in 30	car engine quieter than road noise; perambulators plentiful; locomotives absent.
One in 20	car engine noise louder than road noise; walkers plentiful
One in 15	skin moist despite cold conditions; heavy breathing is heard above background noise
One in 10	eyes sting from sweat; bicycles experience difficulty staying upright
One in eight	flies are constant companions; car smoke exits parallel to the ground; mountain bikers walk
One in six	cigarette butts become less frequent; 2 wheel drives mostly absent
One in five	walkers experience difficulty making forward progress
One in four	cannot hear the sound of a cigarette being lit; leaf litter easily lifted off ground
One in three	sturdy walkers stagger and sway; frequent rests; slow progress; loose soil swept away
One in two	large trees tilt at a noticeable angle to the ground; rocks experience difficulty staying in place; walkers remain upright only by zigzagging
One in one	toenails begin to bleed; trail bikes begin to bleed
Two in one	fingernails begin to bleed; small trees are pulled up by their roots
Three in one	contour lines begin to merge; danger of severe falls; you are in danger of being completely… winded!

Walking an Exact Straight Line in Open Country

Assume the visibility is limited, or the terrain difficult, or the vegetation is closed in…

- Lengthen the Whole Party—In Single File. Shout to the leader, if he wanders to left or right. Stop still if you lose sight of the person behind you, i.e. do something to make sure that no one gets lost in the fog.
- Drag a flat object (or a person) on a long string. Tie your end of the string onto a stick, and hold it forward above your head. Alternatively, pivot the stick in your hand at its halfway point, and it will point in the right direction. (Watch that the wind doesn't blow it sideways; Stop the flat object rolling; Stop it sliding downhill; Don't let it drag at an angle)

Try just a slippery fishing line with no object.



- Harness the leader in a pair of reins!
  Tie one string to either arm of the leader, and steer him properly.
- Hold the rear end of the string over a compass.



- Leave a trail of visible markers lined up exactly.
  You need to look back frequently and drop a new marker.
  — stones, sticks, stumps, tree trunks
  Leapfrog with only three marker sticks — take them with you.
  Leapfrog people!—leave someone behind; send someone ahead; line them up with each other & with a compass if available.
- Scratch a line into the dirt. Look back frequently. Readjust yourself
- Use the radio for radio direction finding.
- Orient by Sunset glow, the wind on your cheeks, the blue band, town lights, distant noise, etc.

To keep to a fixed "track", manoeuvre around obstacles in a rectangular fashion, or reverse any diversion.



Leap-frog a Straight Line by Looking Ahead

A. A straight line course is easily achieved visually — like keeping a hundred fence posts in a dead straight line.
In clear open country, you simply walk toward a new mark halfway between you and your destination — no problems.
Keep the 2 lined up. When you get halfway choose another halfway point in line. If you can keep sight of the more distant destination, this method means you only use the magnetic compass once, to locate the distant destination—then keep a fixed 'track' visually.
When obstacles force you sideways off track, you can easily regain track, visually.
B. In more difficult circumstances, you cannot see far ahead and usually rely on looking back, as above.
But leaving markers behind you slows you down and keeps you looking around.
This method does not require you to look back, but requires a simple discipline — leapfrogging visible marks exactly ahead of you.
Step one: Choose two distinct marks exactly in line with your desired direction
Step two: **On reaching the first mark, choose a third, still in line. And so on.**
You can do this while following a formed track. The track will bend from the average straight line, but you'll notice that immediately.
I.e. when you don't get to the third mark, and have to start again, you are well aware of the change in trend.



The end result accumulates errors
(despite the averaging process).



Noon-Sunlight is More Vertical

Examine needle bush (e.g. Hakea) needles, one by one.

Some effects will be more noticeable in winter, and in higher latitudes.
In summer, the 'shady' side is actually bathed in horizontal sunlight twice a day!





The Shedding of Bark on the Sun-Baked Side

The patchwork of coloured fresh new bark shows that
the bark strips an extra layer deep on the sunny side.
Look also at the coloration of the freshly exposed bark, for asymmetry.
The bark 'stocking' clings higher on the shady side.
It is older, deeper, darker and allows more and older lichens.
Look for the 'curl' of bark ribbons — the pipe-like shapes peeling off —
as there may be more curling shown up on the dry side,
but it depends on the species.







Where to Look for Fading or Lack of it

****Turn leaf blades around** to compare the greenness in each direction.
Find a pair facing the same direction, and twist one of them, then
make a comparison to see which side is more faded.

****Twist an *untwisted vertical reed stem***, to detect the more faded side.

Look at stumps and old posts, tree trunks and fallen sticks.
E.g. Sunlight bleaches the sunny side of bark and dries out any secretions
E.g. The dark side of the trunk will often be darkly stained
e.g. with cider-gum secretions.

Leaves dropped into the shady zone will not fade and dry out so quickly.
The shady zone is offset toward the pole,
because the sunlight penetrates deeper on the noon side.



The broken faces of lying timber may be more coloured
and less bleached in the shade.



Bumps and slopes, diggings and burrows, may show dead dark moss on the
hot side, or grass which has dried up.

Look for a very subtle pink glow on the shady side of dead timber, which is absent or greyer and paler on the exposed side.
Once your brain sees a hint of it, it becomes easier to see—so persevere.

Bracken fronds die off from their tips, but the fronds that retain their greenness the longest are on the lowest, shady side.
Dead thistle stems fade on the Sunny side.

The topsides of grass blades fade more due to being blown over flat by strong **wind**s, and so are exposed to sunlight, wind & drying.
Upwind edges of green bushes often show a brown wind-scorch.

Fresh diggings (echidna, bandicoot, wombat) expose soil to bleaching. Look at the steepest sides for the least faded soil.
Some fading is due to **oxidization** (exposure to air), some to **dessication** (loss of humidity), some to sun-**bleaching** (exposure to ultra-violet). Again it will pay to study the various effects before you need to rely on them.
Also be aware that diffuse lichens will give a covering colour to dirt, wood, rocks, etc, which may complicate the appearances.

Button-grass flower-stalks fade but darken on their exposed side, perhaps due to fungus. One side is dark grey; the other pale yellow.

Make a Clinometer — a Slope Measurer

One person holds the loop knots apart under slight tension. He barely touches both plumb-bobs onto the ground, to settle them.
Their identical lengths ensure a parallelogram.
The second person alters the middle string until it just touches the plumb-line.
The identical lengths ensure an isosceles triangle.
The 5 cm marks represent whole degrees of slope. Use 6 m of non stretchy cord. Measure and constru .



E.g. the slope is 11°½ here…

Accurate from 0° up to 20° or so
The method is based on the isosceles triangle rule
(double the half-angle sine; nearly linear for small angles)
and on 1 in 56. You can use 1.40 to 1.50,
but the lengths must be exactly equal.

The one-man version has two foot-loops.
Spread you feet and hold up the plumb bob.
See which side the plumb leans to.



Use it occasionally, to refresh your judgment of slight slopes.
It may also be used to gauge the height of landmarks or stars. (Hang the second loop knot from a sky hook; Sight along the top string; Steady the bobs). Used horizontally, it yields horizontal angles. (Complete the string parallelogram; Sight along the two 'top' strings; and double the reading)
Of course this is only for a hobby, for interest's sake, for mathematical curiosity, not for absolute accuracy!
The more you play, the more you learn.

Just Draw It



The question is…
Can I see the peak from camp?
Draw three lines of 5, 3, 2 units…



.."Yes, I should see over the ridge to the peak"

Radio Direction Finding — As Good As a Compass

AM stations — Amplitude Modulated — the older style, for medium distance transmissions
— also called Medium Wave; Medium Frequency — MW; MF

Your portable radio has an **internal aerial** for AM stations, which is direction sensitive.
It usually lies lengthwise inside the radio, as a long **ferrite rod** wrapped in a wire coil.
To make that ferrite rod horizontal, you probably need to lay the radio down flat.
Now twist the radio to change its horizontal direction.

When the internal ferrite rod points at the medium wave transmitter,
the reception drops off — you have detected a "null".

This occurs at two opposite orientations — **pointing away from the transmitter as well**.
(Good reception is by pointing the radio 90° away from that null direction.)

FM stations — Frequency Modulated — the newer style, of shorter distance transmission
— Very high, Ultrahigh frequencies — VHF; UHF — It does not use a ferrite rod.
With a whip aerial, or an extensible aerial, or a long wire aerial,
you can detect a null by pointing the aerial at the transmitter.
This is for horizontally polarised transmissions. Some stations are polarised vertically.

Shortwave stations — Amplitude Modulated — higher frequencies, for longer distance transmission
— SW; High-Frequency, HF — It usually requires an external aerial.

Use a **long wire aerial**; keep the ferrite rod perpendicular to the long aerial.
The null occurs when the long aerial does not point to the transmitter — but it is perpendicular to that direction. (Opposite to FM)
Point the long-wire aerial perpendicular to the transmitter, for a 'null'.

Weak AM stations can also be used, provided you have a long wire aerial to pull them in. The exact length sometimes matters—you will notice the volume rise and fall in cycles as you wind the aerial back in.

THE RADIO "NULL" ACTS AS A COMPASS NEEDLE — it keeps a constant angle to the distant transmitter tower or repeater.
You swing the radio aerial each side of the null to keep checking its direction.
To avoid having to give the radio constant attention, break your course into separate lines of sight ('legs') as with a compass.
Marine navigators know that radio signal direction can be distorted by mountains, or by the signal crossing the coast at an angle, or by reflections off the rigging, but bushwalkers seldom have to worry about that, because they only want a constant reference direction, not an exact bearing.

You could consider setting up a radio beacon so that you can always say: e.g. "The car is that way" or "Home-base is yonder"
End of Section 3.

Distance Guesstimation is a Major Problem for Walkers

Because distance measurement is a major problem, we find it easier to ignore.
We resort to some other method of navigation.
If we simply, out of laziness, give up on logging our pace & distance-already-come, we waste a sensible cross-check.

The first of these three sub-sections will look at the amount of distance you have covered — progress — distance made good…

- Elapsed distance — puts you on the map precisely — unless you are not very sure of your progress! or the map scale!
- Map scale — "It looked so easy on the map!" — Judging time, distance & difficulty is a question of reading the map-scale properly. "How far could we get by lunchtime?". Guessing at a curved distance is always a bit of a bluff. If you hear yourself saying "On the map that's **about** 5 km" stop and measure from the map-scale more accurately!
- Sideways drift — is a matter of trigonometry, when you discover an error in your direction heading
- Up/down progress — is in another dimension. You don't need an altimeter, but it helps. (If you do take a portable altimeter/barometer, make sure to test it to see whether or not it reacts falsely to temperature change—put it in the fridge then in a warm place; then don't forget to keep adjusting it according to the atmospheric pressure changes)

The second sub-section is about the rate of covering distance — pace — and distance-yet-to-go.

The third sub-section is about the distance you can see, but don't cover — estimating the 'range'. How Far to That Landmark?
E.g. You can identify a peak on the map — but only if you are certain enough of the distance from you to it.

Distance = Speed x Time

E.g. 4 km per hour x 3 hours = 12 km
Hint: Measure only elapsed, 'walking' time; Delegate someone to keep track of accumulated time out for stops and diversions.
Hint: Mentally bring forward your starting time e.g. "(as if) we started at 10a.m." (You started at 9, but had two, ½ hour stops)
E.g. foam takes ½ a second to pass your 10 m yacht; speed equals 10/.5 = 20/1= 20 m per second.
E.g. I seem to have drifted 12 km in one day = ½ kph current. E.g. The cloud shadows cover 5km in 2minutes = 150kph wind.

Keep a Log!

That's how mariners keep track—they write it down in the special book. Do you carry a notebook?

Adding Two Speeds

Convert speed to a length (e.g. 4 kph = 4 cm) and direction to an arrow.
Add the two arrows, tail to tip, in either order.
Complete the triangle or quadrangle tail-to-tip.



Note that it is faster to swim a river by pointing straight across and letting yourself be swept downstream, than by trying to stem the flow by pointing upstream. Only when the two speeds are perpendicular do they not affect each other e.g. the 4 km per hour is not affected by the current in the first example. Or e.g., If your boat speed is 4kph ahead, and the tidal flow is 5kph against you, your actual movement is backwards! (with any sideways component added in independently).

Example: Three air-speeds ↗ + wind ↘ = actual progress ↗ very fast across the ground, slightly to your right.

I.e. Your speed & direction through the medium (air/water), relative to the ground + the medium's movement, over the ground (the medium carries you when it moves) = your total speed and direction, over the ground.
Lastly, *to analyse apparent wind speed, to avoid confusion, draw only the three winds involved*. I move this way...
First convert your progress over the ground (top arrow) to an opposing apparent wind (right-hand arrow opposing it).
Don't try to add wind to your motion—that's not a sensible question/answer. The medium (air) doesn't carry you when it moves. Answer: I feel the actual ground-wind, a cross-wind (→) in my face, diagonally as shown…



Range: Rule One: Guess

Then don't trust any calculation which doesn't agree with your initial guesstimation.
But remember that distance is deceptive over featureless terrain e.g. water/beach — we underestimate it.
Birds bob their heads to see how much an object shifts against foreground and background. It's worth some practice.

"Range" of Visibility — Two Halves to the Picture

"Extreme visual range" must be calculated in two bites — So Don't Forget To Add!
— e.g. when asking "Should we be able to see Ben Nevis from Brady's Peak?"
— e.g. at sea when you can first see the lighthouse lens, not just its loom.
From a kilometre high you can see 1° of latitude
before the curvature of the earth cuts your line of sight.
— e.g. you can see a 1 km high mountain from two degrees away
if you are on a 1 km high mountain — see diagram…



"Range Squared is Dee Height"

This is an easy mnemonic. "Dee" is dee Earth's Diameter i.e. Extreme Range = √(D x H) see p.92c
H is your height above the intervening horizon e.g. the wave tips, or a 250m plateau.
Since the Earth is 40,000 km around, divide by Pi to get **12,700 km diameter**.



The formula is a theorem in geometry,
about the geometric mean (the tangent) of an extended diameter and the extension length (H).
The formula states: the square (range x range) = the rectangle (not shown: H x D+H).
(i.e. the range substitutes for both parts of the product, 'geometric-' or area-wise)
but since the height H, in reality, is very small, therefore **range^2 = D x H**

To "Read" a Map — Rule One: Don't Lose Your Place!

Get the geometry fixed in your vision — of where you are on the map e.g. "in the top right grid square, next to that lake".
And then don't keep losing your place every time you look at the map again!
..Whether the map is now upside-down, side-on, or whatever.

Rule Two: Imagine Arrows, for the Sun, & Your Movement

Again, visualise them geometrically, in relation to the whole map shape, from one corner of the map, for the Sun, and from where you are on the map, for your movement. When your map is properly oriented, the movement arrow will point in front of you, ahead, matching the trend of your movement onwards.

Rule Three: Get Used To Any New Map Scale

Maps are "Fractal" They show "self-similarity across scale"
i.e. A river system will look the same on a small-scale or large-scale map — there is always finer detail to show.
A road network is the same — the smaller the scale, the more roads are left out, leaving a similar looking network.
A coastline shows such self-similarity. Magnify the details and it still looks like 'a coastline'.
New Map-Scales are Hard to Adjust to
It takes time and testing to get used to a map scale, because they all look alike no matter what the scale.
To get used to the new 'feel' of a map, check up regularly on your map-progress, until you are no longer surprised by how far you have or haven't come.

Rule Four: Don't Give Up!

Don't let the combination of difficulties bluff you!
E.g. You misjudge the scale, misjudge the Sun's direction by optical illusion, you see turns & bumps not marked on the map, doubt the accuracy of the map, fail to assess the slope accurately,… and so eventually… give up in confusion!
Problems are normal, and **solving them by the map is normal too — don't give up trying**.

—Also See "Map Checklist" p.113—

"L.M.N.Or P."

L for Landscape; M for Map; N for Compass Needle: Or for Either/Or (the big point of the mnemonic)**; P for protractor**
Either/Or means: Each component of map&compass work can be used alone and independently for some tasks, if desired.
Plotting compass bearings can seem complicated. This mnemonic is designed to smooth the way.
A navigational compass has a protractor independent of its needle. The trick is to remember that!
The protractor has 2 parts too (p.93b). Note that some compasses have the magnet one-piece—glued onto—the protractor card.
If you get used to using each component separately, you will find 'map and compass work' to be simpler.
The trick is to isolate each of "LMN Or**P" in turn, to avoid confusion.** That includes the 2 moving parts of the protractor.
It is hard to use more than two at a time! so know which two you need to use at each stage.
E.g. A 'prismatic' compass will let you see both **L**and & numbers (**P**) at the same time—to take an accurate bearing e.g. at sea.
E.g. You can align the **M**ap to the **L**andscape, without ever using a number. Or you can point the **N**eedle to the horizon likewise.
E.g. The **P**rotractor may be used to assess slopes, to measure the Sun's height, to take a map bearing, to draw an angle on the map, to take a horizontal angle between two landmarks, to sight a vertical angle like a sextant (this may need two people), to find North from Sun-time, or to set a course to the left of the Sun.
So don't forget to use the **P**rotractor to its full potential, quite independently of that funny little piece of metal rattling around inside it. (**N**).
E.g. An emergency 'compass' is just a floating sewing **N**eedle, or a suspended magnet. So the protractor has little to do with orienting the map by the magnetic field, or with heading North by the compass needle.

If your navigational compass has a magnifying glass, a set-square and a graduated ruler, you should hardly get confused by thinking they had something to do with the magnetic field! — so don't worry when you see some numbers marked around your compass needle — I think you learnt how to use a protractor in elementary school, didn't you?

Working from land to compass is called "Taking a Bearing" (L+P1,N+P2) You use the protractor to put a number on the direction
..from map to compass is called "Getting a Heading". (M+P). You then use the needle (P+N) to find then follow that heading (L).
Working from compass to map is called "Plotting a Fix". (P+M). I.e. You use the protractor, ruler and set square to draw angles.

Maps Mean: Imagine Me! — Making Mental Maps

The meaning of using a map is that **it lines up**
— with what you see; with what you saw; with your mental maps; with what you know; with what you can't see & don't know.
E.g. You glimpsed the coastline as you drove in, the lie of the valleys, the drainage of the creeks, and of course you know the highway that you drove in on! You can no longer see them, but it is normal to orient yourself by imagining the invisible.
And then, your mental map is still incomplete, so that you need to use the map to add to your imagination…

"Map To Mind" Navigation

Transfer from the map both visible and invisible features back into your mental model and mental layout.
1. Start with the Invisible Big Pictures — visible on the map but not to you.
Look at the sky and the skyline as you interpret the map for what lies out of sight.
2. Add in the local visible features — visible both on the map and to you.
These two steps work together like lock and key — each is not very useful without the other.
Yet both steps are often neglected and seldom put together as a whole.
"The cars are now behind that notch in the skyline"
"The highway runs behind that hill then turns South-East"
"That low spot marks the river we want"
"Our camp tonight is in line between Mount Socks and the pine plantation yonder"
When you become temporarily bushed in, or blinkered by the rain, or shut in by the dark — then you see whether you can maintain proper orientation — by the invisible — or whether you just feel lost — "I can't see where I am!".
If you do not make a mental map and orient yourself by imagining the invisible—you will be disoriented,
even if you "can see where you are".
♦ Part of the job is to look at the map in order to join your several local mental maps into one regional map.
Remember that a map is a great memory aid, or a great memory bypass — take your choice.
♦ Rather than "put yourself on the map", put the map in you!

Use the Map Scale — Don't Just Look at It!

Many errors of judgment result from guessing at the map distance, even when the map scale is clearly marked.
The scale is not much good down in the bottom corner of the map, fixed in place! So copy the map scale onto cardboard.
Somehow attach it to the map e.g. into a separate paper-pocket; onto a string; in the map bag.
The string is useful for measuring distance accurately. You place it over a curved path then stretch it out straight to measure it.
Point the corner of the cardboard at the starting position; position the string from there; then stretch the result along the scale.

The Jargon



"Large-Scale" is like a "Full-Scale Model" It shows all the details.
Like a 'large-scale simulation' — it leaves out nothing. **Picture a magnified 'Large' map-scale**.
"Small-Scale" is like a "Small-Scale Model". You can't see the small details.
It is like a 'small pilot study' — not full scale. **Imagine a very hard to read small map-scale in the distance**. No Details.
"Full-Scale" is "1 to 1" like the Cosmos. "Half-Scale" is "1 to 2". *"Small-Scale" is* "1 to a million" *like Cosmological diagrams.*
The bigger the second number, the smaller the fraction. The bigger the big number, the bigger the span on the map.

Map-Scaling-Factors are Meant to be Interpreted

1:100,000 means "One unit represents 100,000 units"
Split this into two parts: (a) 100 & (b) 1000 and **use centimetres i.e. 1/100 m** — 1 cm: 100,000 cm
Say (a) 1 cm represents 100 cm i.e. 1 m — **drop off two zeros and call centimetres 'metres'**
And (b) 1 m, from part a, represents 1000 m i.e. 1 km — **drop off another three zeros and call metres 'kilometres'**
So the answer is: "1 cm to 1 km"
1: 1,000,000 1 mm = 1 km I.e. **You can also drop off three (or 6) zeros and call millimetres 'metres' (or km)**
50,000 units makes you calculate '1/50th of a metre' (=2cm), so 1:50,000 must be '2cm to 1km'. Or multiply to 2:100,000.
1: 250,000 Turn this into 4:1,000,000 by multiplying both sides by four. 4mm to a km (since 1mm is 1/1000m)
or (a) ÷100: cm to m (i.e. 4cm to 10,000m no longer cm to cm) (b) ÷10: cm to lots of 10m (c) ÷1000: cm to 10km
the grid should be marked in **10 km squares, of 4 cm each**
Your compass will be marked in centimetres, but perhaps also in special scales e.g. 1 inch to a mile (1: 63,360)

Pace Your Progress — Pre-Dict It, Don't Post-Dict It!

To avoid looking at the map continually, to locate yourself continually, predict the estimated time of arrival **once**, and relax.
We are normally lazy about looking at our watch often, poor at calculating, on the hop, distance covered, and lazy about locating ourselves on the map often. Mental arithmetic is clearly noxious, so we try to avoid it. Working abstractly from time to distance to map, after the event is too hard for us. But we usually only resort to the watch after we begin to doubt our position. (See "the 11:59 syndrome" — we do doubt.)
Something needs to be done about this!

Consequently, the antidote to us refusing to log our distance, is to anticipate the timing instead
i.e. to work more concretely, from map (I can see that) to distance (I can visualise that) to time (I can calculate that).

- Examine the map beforehand — as a first step not a last step. You will have to do the calculation later anyway, on the trot! Why not do it now, calmly.
- Guesstimate the time needed to cover the distance ahead — to the next recognisable milestone. E.g. use 4kph, ¼hr/km
- Look at your watch, as the last step, when you near your goal.

In this way the **landscape 'means' time** to you; "When we reach the bridge, we turn left — and that should be in 25 minutes"
Your guesswork will get better too.
You will find yourself looking at your watch more frequently, with the question: "Should I be there yet?".

Anticipation Is Exciting. Back-Calculation is as exciting as the washing-up.

"Range Squared is: Dee Height" "Dee" is Diameter

i.e. Extreme Range of Visibility = √(D x H) on this side of the horizon. **Don't forget to add the 'beyond the horizon' range**.
Five round-number rules are highlighted. By playing around with some approximations, we can find some rules of thumb…
127 is close to 128 and 125 and 11.3^2; Pi (3.14) is close to √10 (3.16);… I hope these tricks will make the square roots easier

40,000/pi x 40/pi km = **400** km range from 12.7 km Notice the two related doubling sequences I have given.
40,000/pi x pi km high = **200** km range from 3.14km You can only see twice as far from four times the height
12,500 km x 4/5 km = **100** km range from 800 m high 125 is five cubed
113^2 x 9^2 / 10^2 = **100** km range from 810m 34 km from 90 m; 11.2 km from 10 m — 1/3 from 1/9 height
12,500 km x 1/5 km = **50** km range from 200 m high "Rule of (lesser) fives: **50 km from 1/5 km**";
12,500 km x 1/20 km = **25** km range from 50 m high Multiply or divide H by four to double or halve the range
12½km range from 12½m e.g. from the top of a beach

12,700kmx.0127km=**12.7km from 12.7m—**from a ship's deck, to the horizon, when estimating distances across open water.
12,700 km x 1.27 km = **127** km range from 1.27 km high 1/10 from 1/100. Remember the number 127 must be 400/Pi;
100,000/8 x 10/8 km = **125** km range from 1.25 km 0.125 is 1/8

12,800 km x 1/2 km = **80** km range from 500 m high or "Rule of (greater) fives: **50 miles from 500m**"
12,800 km x $1/2^3$ km = **40** km range from 125 m high You can also derive 160 km from 2 km; 800 km from 50 km
40,000/√10 x 0.4/√10 = **40** km range from 127 m high = "400km from 12.7 km" = 1/10 range from 1/100 the height.
12,800 km x $1/2^5$ km = **20** km range from 31 m high = 200 from 3.14 above.
12,800 km x $1/2^7$ = **10** km range from 7.8 m high ..if you bother to halve 1000m seven times!
12,800 km x 1/500 = **5 km range from 2m high** **From a dinghy/beach**. 1/5 range from 1/25 height cf 50m high.

21,600 nautical ml/pi = **150** nautical miles from Pi n.ml high approximately, because 150 squared is 22500.
83^2 n.ml x 1 n.ml. = 83 n.ml. **150km from 1 n.ml**. 60 x 360 / Pi is approximately 83 squared nautical miles
12,300 km x 1 km = **111 km** range from 1 km height **1° of latitude, from 1 km high**, approx. "**55** from 1/4" = 250m
111^2 km x 1/9 km **37 km** range from 111 m high 1/3 of the range from 1/9 of the height

Look Carefully at the Fine Detail on the Map



E.g. a kink in the track, just before a junction, may make it look "not like the map!" until… you re-examine the map…
"Oh yes, it is marked like that after all, **I just didn't look closely enough**"
E.g. that maze of fine blue watercourses marked — don't be a-maze-d by it — look at its detail!
There is usually a magnifying glass on the compass.
For a stronger **magnifying glass**, reverse your binoculars. For an even stronger magnifier, remove the eyepiece and use it.

Look Carefully at the Fine Print

E.g. date of compilation ..1864?
E.g. "adjust all longitudes by + 2 minutes of arc"
E.g. yearly magnetic drift
E.g. Contour interval — 10 m or 100 m?

Some Map Details are Not to Scale!

E.g. Two wheel ruts might look like a 100 m wide road on a map (if you took it seriously).
Consequently…



..may be a 100 m Zig-zag! And…



..is not a cross-road and the hut is not "at the junction"

E.g. A "cascade" symbol…



..might equally mean two huge waterfalls, 300 m apart.

E.g. 'Smooth' bends



..probably hide many small extra sinuous ones. E.g. in a river.

Moral: Keep an Open Mind. **Keep your eyes open** for alternative interpretations.

Using the Protractor by Itself

The protractor has two sets of lines — the lines on the movable 0-360 protractor-circle, and the fixed "follow me" arrow, taken together with the edges. Line up one set with horizontal, or North, or whatever; line the other up with the slope or angle to be measured. The angle in degrees clockwise is the space between the zero and the "follow me" arrow, not the other way around.



When the angle of the Sun
(it moves around at 15°/hr)
corresponds with the time of day,
you must be facing North/Polaris.
This may be used when the magnetic field
is locally anomalous or untrustworthy.
(Tilt the compass axis to Polaris)
Reverse this to get the time from North.

Point the edge of the compass body directly at the Sun
until it casts no shadow. (Don't look at the Sun)
If your compass fluid has a bubble in it,
it can be used as an artificial horizon.


Keeping a course relative to a landmark.
Peak
Measuring a horizontal angle
for a circle of position.
Draw an angle
or measure it
top
view
Measuring a
vertical angle
for 'distance off'

Mental Networks

Our mental maps seem to run on networking — junctions and joins; choices and destinations; routes and 'directions'
Consequently mental maps are prone to logical-type blunders

- Missed junctions e.g. of creeks or paths
- Misidentifications e.g. of segments, features or forks
- Poorly judged measurements of lengths or direction e.g. hairpin bends which aren't noticed
- Mistakes of number

If you reread the section "Logical Blunders" (p.39b) you will notice that most can be seen as a **wrongly imagined network**.
That's one more reason to study the real map, in order to bring your mental map up to speed.
When we function on short term memory of mental branching directions, any shock or daze can be crucially disorienting.

The Most Valued Map

..Is one which you have made yourself. A do-it-yourself job makes it "yours". Practise with a MUDMAP, p46e.

When you copy important detail from other maps onto your map e.g. peak elevations; track notes; waterholes,
then your map becomes more valuable than a replacement map.
You add extra details e.g. campsites; walking times; side-tracks & old tracks and suddenly you prefer the old dog-eared version to a brand-new map!
Sometimes it is even better to start with a blank sheet of paper.
But since it does you no good to pinpoint your position on a blank map, unless you are at sea,
you proceed to add in the important local details so that you can tell where you are…

To copy a map: **Copy the Grid First**. ..if there is one. Add in many diagonals as guidelines.
The next rule is: **Get the Landmarks in their correct relative position first** **i.e. work top-down.**

The Psychological 'Half-Way Point'

You have to judge and juggle several factors before you decide that you are 'half-way'.

E.g. The "Unknown Territory" Scare-Factor (Ambition versus Safety Margin). In planning your time-budget, you can't relax in a one-way journey through unknown territory, until you know you have a reasonable safety margin in hand

So 2/3 the distance along, might be 'half-way through the test'. Other examples...

The "Point of No Return" — You tend to speed up, once committed to the next goal.
The "Downhill Run" — It is the quicker half.
The "Back-Track Return" — tends to be quicker i.e. the turnaround point can be after lunch.
The Morning Spurt-Afternoon Hurt Syndrome — puts 'halfway' before lunch.
The Side-Track Scheduling — if you don't explore side tracks on the way in, when you are fresh, you may not want to tackle them on the return journey.
The "My Feedbag is That Way" Home-run spurt on the last day.

When You Meet Other Walkers

"When did you leave this morning?" = how far to your next camp.
"Anything about the track that we should know?" E.g. slow sections
"Any deep water crossings" or other hold-ups

Other questions, less related to walking progress and pace, are…

Anyone else ahead of us? (Will there be room for us all?)
Do you carry a track guidebook? (Can I read it?) Do you know the forecast?
Any good water available on the way? Can you recommend a camp site?
Did you pass our tents? (Are they still there!)

Pluck up your courage to ask what you want to know, and be prepared to share what you know.

Advice about Walking Times — Double & Halve!

E.g. Brochures seem to add "return" or "one way" by guesswork sometimes.
So "6 hrs" means 3 to 12 hours until proven otherwise.
E.g. Fit young rangers saying "six hours" may mean "for me; double it for you" or "for you; halve it for me"
E.g. "walking time" may mean "excluding stops, rests and meals" — you could find yourself pushed for time.
E.g. "Not far, you can't miss it, it's easy all the way" could prove disastrous. E.g. ('provided you find the right track')

20 Minutes per Kilometre — Double & Halve — Easygoing Maths

It means **3 km per hour** —an easy-going overall walking pace when you include short rests, difficult vegetation (within reason) and lack of any hurry — tourists on track, walkers off track.
Obviously you need to multiply and divide by 20 to convert kilometres to minutes, or minutes to kilometres.

If the number is small — kilometres — multiply it up to the larger number — minutes — **double** it and add a zero.
If the number is big — minutes — divide it down to the smaller number — kilometres — **halve** it and subtract a zero.
You could also express it as a "half a kilometre every 10 minutes" but the "20" makes the maths easy;
And even simpler, to cope with the zero, express yourself in 'lots of 10 minutes'.
E.g. 5½ kilometres will take about… (double it, to get many minutes)… 11 **lots of 10 minutes**
E.g. "We've been going 50 minutes — (five lots of 10 minutes) — ; that's about… (halve it, to get a few km)… 2½ kilometres"

4 km per hour — Normal Walking Pace — Double and Halve!

You can easily double or halve your pace. Start with 4kph as a sustainable rate of progress, and use the doublings 1,2,4,8…
8 km per hour is someone tall walking in a hurry. 2 km per hour is someone small dawdling. 1kph is for very difficult going.
Coincidentally 4 km per hour is 10 miles in four hours or 2½ miles per hour.
Incidentally also, at 4 kph, a landmark 15 km on your left will change direction at 15° per hour as you walk past it.

Double, the Acute Angle, off Your Nose — For the Distance Off

This double-angle method puts numbers on a very "natural" method of gauging distance…
In the first diagrams you walk from the bottom left to the top, and watch a landmark, ahead on the right, pass you by.
The distance walked = the distance off if you walk far enough to double the original angle (away from straight ahead).
The initial angle must be acute. You need to maintain a straight course throughout.

The simplest case uses the diagonal of a square.	45° changes into 90°
The next simplest example is the equilateral triangle.	60° changes to 120°
Followed by the 30° isosceles triangle.	30° changes to 60°

But the general case is made clear by the geometry of two equal radii in a circle.
It is because the angle at the centre of a circle is double the angle at the circumference.
The angle at the centre is the final angle—double the initial one. top view…



Ahead of you, the angle is always less than 90°.
In the second diagrams, below, the landmark may not be ahead of you and the initial angle may not be acute...

If you walk backwards, from top to bottom, using the top method in reverse, you get...

Halve, Any Angle, from your Stern—For Distance Off,

..i.e. In Retrospect The initial distance off, not the final distance off is what must be travelled.
The initial angle is now the double angle, and need not be acute.
I.e. turn the bow-angle diagrams upside-down…
E.g. 90° becomes 45°; or 120° becomes 60° becomes 30°…





Permanent Landscape is More Trustworthy Than Surface Detail!

When what you see "doesn't match what is on the map" have the sense to distinguish between 100 m deep contours which would take an atom bomb to shift, and walking-track junctions which a fire could reshape.
Professional map-makers and satellite photos rarely make mistakes — in landscape positioning.
But when they add the local details, it is another story.
Time changes such details also. New roads, cleared bushland, second bridges — these will mislead and confuse you.
When your mind says: "The map is wrong!" remember that what the map says — about landscape — is not wrong.

Details Added on to a Map Are Prone to Error

Notorious for errors are: Map North; Map Scale; Roads.
So beware of anything other than a good-quality official government map.

Expect The Map To Be Unhelpful

Many important details will not be shown on the map — you just have to expect that.
You can often trust what is on the map; You can often trust that what you want, won't be on the map.

Maps Do Give You 10 Times More Detail Than You Can Notice

After you get lost and finally sort it all out on the map, you notice… "Oh yes, silly me, those contours are **up**slope not downslope! And they **do** show a creek-line, by those sharp bends! Oh, of course, there is **a peak** on the right, and that fenceline opposite — I missed both of those when I first studied the map. You **can** see Mount Bruce, lined up with the lake, from there, but not at all from over there. And that squiggle in the blue line, is the hair-pin bend that tricked me, but I should have realised that all rivers must drain to the north-west eventually…"

Try to reduce your ten-fold folly to five-fold folly for next time!

Using the Needle Alone — Emergency Magnetic Compass

- Magnetise your repair-kit sewing needle; It will probably already be magnetised somewhat. Stroke it with a South Pole toward the sharp end, so that the North-seeking pole is at the pointy end.



- Float the needle in calm water, on the surface tension (no detergent!)
  (a) lay the needle on toilet paper
  (b) lay both on a bowl of clean water
  The paper will wet and sink, leaving the needle afloat. You could also try sticking it through a piece of foam.



- Hang any magnet horizontally, from hair or fine thread. It helps if you know which end is North-seeking.
  In the field, test it against a Natural North, eg, Bush Noon. At home, test it on a compass. Like poles repel…

Hint

Understand that **magnetic poles should be called 'North-Seeking' and 'South-Seeking'** and that **our "North Pole" is a South-seeking pole!**
(so that North-Pole seeking poles point to it — Unlike poles attract)



The Earth's internal magnet is as shown (It is slightly off-line with the rotation axis!)

A compass needle on the Earth's surface has a red end labeled 'N' i.e. North-Seeking

The white end is labeled 'S'

Strip Map Navigation — Follow-Your-Nose Navigation

Our mind definitely prefers a strip map — a sequence of "directions" to follow. (None-the-less, make a MUDMAP in conjunction)
Our eyes definitely prefer a strip map — "up" is "straight ahead"! (See "N.O.R.West/N.O.T.Least" "Nose Navigation" p31e)
A strip-map is simply a way of formalising your track notes—every navigator really ought to do it this way…
There are two good ways to make a strip map as you go: with a sheet of graph paper, working from bottom to top, and
in a track notebook, working from top to bottom, but…
Both assume that **progress arrows are up-page**. You could turn your notebook side-on or upside-down to write in it.
In either case you set aside several **vertical** lines for each **type** of information,
and set aside one **horizontal** line for each **subsection** of the journey,
and a second line for descriptions and for comments,
and a line for overall information e.g. trend, drainage, season; totals: time, climbing and distance.
The trick is to use symbols. One vertical line for one sort of symbol e.g. compass needle direction
(See the **Symbol appendix** p 122) Another line for another sort of symbol e.g. slope-direction, and steepness
This way you can cram a lot of information into a small space, in a consistent and regulated manner, and be able to read it!
e.g. …



track feature	compass needle	up slope	landmark direction	time check	leg time	leg distance	distance check	comments
Climb			Lake	1:20			6km	Peak by lunchtime
				1pm	20m	1km	5	cliffy
			Peak	12½	30m	1km	4	trend right after creek
				10½		½km		munch stop overlooking creek

e.g...



Distance

AIMING OFF by 10° — 10° is **175m per kilometre**

1° is one in 57.3, so one in 5.73 is about **10°**, (and 1 / 5.73 = .175) or **175 in 1000**. (For bigger angles use the 1 in 60 rule)
Alternatively, 2sin5° = 0.174 isosceles chord, yielding "0.174 per one" or 174 per 1000. (167m per 1000m / degree for >10°)
This is easier than working in sixes using "one in 60".

Hint: Express any ratio as "something in 1" or "in 10, 100, 1000"
E.g. '1 in 50' becomes '2 **in 100**' or '200 m in 10 km' (.4 in 20 etc)

Example: "The T-junction is somewhere ahead — about 017°, 5 km. But so that we can't miss it, we must aim off to the right e.g. 027°. We therefore expect to hit the road 875m to the right of the Junction" (5 lots of 175m).
This is how ocean navigators find an island in an ocean: Step 1: sail N/S to the right latitude. Step 2: sail E/W to the right long.
Don't just head straight toward something. If it doesn't show, you won't know which way to turn!
Remember that a 10° error is fairly easy to make when using a compass over rough terrain (or trackless shifting ocean)!





Aiming-off at Sea…

Aim-off to arrive up-current & up-wind of your destination—to make it easy to turn and sail to it.

- Aim-off 6° to counteract leeway when sailing into the wind; 10° in stronger winds; 15° in a storm.
 Measure the appropriate angle from the wake e.g. 6° is how much your pointing-finger-tip shifts when you change eyes
- Aim-off 6° (1 in 10) to counteract a 10% (1 in 10) cross-current. This refers to the perpendicular component, compared to your speed. The rule works +/−1° up to 36°—up to 60% cross-current. To avoid judging components...
- Aim-off 1°,2°,3°,4°,5°,6°, to counteract a 10% current at 10°,20°,30°,45°,60°,90° to course, either ahead or behind.
- Aim-off to avoid GPS-induced collisions caused by very accurate course-holding. You should plot a course off to one side of the obvious line on the chart, to avoid vessels coming the other way on the same line!

Aim Off 6° or 10%

Blink your eyes at the destination, and when you get there, pace off the 6° offset. Ten-tuple the result for the distance there.

---

1 Metre per Second is 3.6 kph

This is merely a logical reference point for your calculations. (And slightly faster than "20 minutes/kilometre" (3 km per hour))
60 minutes x 60 secs per min is **3600 seconds in one hour**, at 1 m per second, is 3600 m in one hour, or 3.6 km per hour.

One metre is Up to your belly button A child's double pace One strong fast stride

One second is the time it takes to pronounce "Alligator One" in a normal fast voice—don't let it drag. Follow it with "Parramatta two", "Oodnadatta three", (or "a thousand and four", but "alligator" keeps its speed more consistently when drowsy).
Get used to the rhythm of tapping your finger in time with the seconds — your mind subconsciously remembers the timing.
Take a Watch, Perhaps a Stopwatch
1 m per second is very nearly 2 knots.

"1 Hour Extra per 5 Hours"

You can normally walk at 5 km per hour, on a track, on a short walk.
But you will sustain an average 4 km per hour, when you include fatigue, and rest stops.

"1 Hour Extra per 500m easy climbing"

Gentle up-climbing is tiring—allow this extra time. (We are not concerned here with how long it takes to rock-climb!)
Down-slope walking may speed you up, or slow you down, depending on the slope.
Dense tussock country (e.g. snow grass; button grass) is the equivalent of a climb, in its up-down-up steps. Crossing the drainage can also be as tiring as climbing, in its regular climb-descend-climb-descend path.

Distance by Optical Rangefinder — Accurate up to a Kilometre or Three

We are woeful at guessing distance in that range, so there are focussing devices available which are designed for it.

Range by Parallax and a Piece of String — DIY Rangefinding

Animals shift their heads to see how much an object shifts. Blink you eyes to see the effect; walk sideways to practice it.
For more distant objects, the very slight sideways offset can be magnified then measured...
The landmark you are measuring appears in a slightly different direction from each of two different viewpoints.
Pack a long non-stretch string e.g. a polymer kite-string. Know its length. Mark it every 5 m before you go.
Use it as a giant pair of eyes—a long baseline—& to mark out a large square or rectangle on the ground, one side at a time.
Guess at the right-angles — they don't need to be accurate. Just make sure to use equal tension when you stretch the string.
But use a plumb-bob to mark the corners of the square on the ground accurately — with a pebble.
Use the plumb-line also for accurate sighting of the landmark. (You can pack up the string once you have placed the pebbles.)
Twice as big = four times as accurate (in measuring d) If you have enough room to move, aim for over 10 m sides.
Range = ab/d or a^2/d if a = b; from the similar triangles involved. Measure the shortfall, d, at the front, or the overfall, d, at the baseline.





An easy way to remember the formula
is to say that the area R d = the area a b
because if you shear the ab rectangle,
it becomes a long thin parallelogram
R long, and d wide, preserving its area.

As a result, the formula becomes...
Range = Area / parallax offset, d
km sq. m mm

The Range=ab/d formula also *makes sense*
The range *should* so depend on a & b and d

"Maps Grip the Universe"

When you swing the map in your hands, around with you as you turn, the whole Universe doesn't follow it! — it doesn't twist!
Instead your map gets disoriented.
Leave the map behind, as you twist! — leave it lined up.
The map is designed to lock into the landscape, to 'map onto' it, and should be used like that, not twisted out of alignment.

You need to swing the map an *equal and opposite* amount to neutralise what you do.
It's called "swinging the map" (when you leave it locked onto true North while you swing to left and to right).

It should not be called that!

It should be called "**NOT Swinging the Map** with you"

Map work includes 'not swinging the map'. See "Magnets Grip Maps". The most common method is to match the map to a compass needle p.103b

Maps mean landmarks — those landmarks there! Open your eyes — and line the map up with the visible landscape. p101a.
i.e. orient the picture of the land — the map — to map onto the actual land.
Line the Grid North up with North e.g. by compass or by Sun.

You may have to twist yourself, or put 'North' at the bottom left, but to always put 'North' up the top, is to divorce your eyes!
Yes, you may have to read names upside down! Yes, it is a bother, to keep changing its 'up' every time you turn.
But it means that you can just lift your eyes from the map to see what it points out. And can know what lies beyond that.
If your map is not consciously oriented, how can you be oriented, to other than what you can see in front of your nose?

Think "+/- 5°" For Compass Bearings;
"+/- 10°" For Following a Compass;
"+/- 15°" For Using a Compass!

Compass bearings "+/– 5°"
Test yourselves: Ask each person in turn to nominate where "magnetic North" is on the skyline
using one particular compass, handheld. **My results:+/- 5°** **"User Inaccuracy"**
Now try putting that compass on the ground. **My results: +/- 3°** **"Needle Instability, friction" etc**
Try stretching a fishing line over the needle. **My results: +/- 1°** **"We still can't agree!"**
Next try that best method for different compasses. **My results: +/- 3°** **"Calibration and Zero Errors"**
Now try **not** being very careful, with an **untested** compass, at night, when you are tired!

Following a compass blind: Walk on a fixed compass bearing for 100 m or so in a fog i.e. eyes glued to the compass.
Repeat it e.g. turn around & see where you come back to. Give the next person a try at doing better.
I think it matters which eye you use and which hand you hold the compass in.
We don't necessarily walk 'straight ahead' when we try. We don't necessarily point the 'follow me' arrow straight ahead.
We don't do very well at integrating and averaging out any diversions around obstacles.
Slopes play havoc with your sense of a 'straight' line ahead.

Try this…



The front person finds the route.
The back person guides the route-finder.
The navigator logs the route directions taken.

Using a compass: You may plot a single line on the map, or as +/- 5°, but mentally allow an extra +/- 10°, i.e. think +/- 15° (for accumulated errors, possible blunders about magnetic variation, etc.). Keep the possibility of error in the back of your mind

Caving Strip-Maps — Come in Books



A "cave-directory" booklet records **each separate section of a cave on a separate page**.
E.g. Make your own…



You may need separate booklets for different levels of the cave system.

Use the same symbols as before, for needle, slope, turns, etc.

Use Abbreviations: E1, E2, E3… for Exits; L1, L2, L3… for Light sources; Parentheses (L1) = "Can see L3 from here"

Make up names for each section e.g. "Chamber of Horrors"

Add copious notes e.g. "water level up to ½m deep"

Forethought and cooperation is required to quickly and effectively map a warren or a labyrinth.
Initially you make a muddy map, as you go, but then you add a neat copy into the book later.
(But keep your muddy copies, for next time.)

Up-down Progress



In the first diagram you can see that you are halfway up the mountain alongside of you — **use the horizon to gauge your altitude**.

Note: the horizon drops below true horizontal as you go higher.

In the second diagram your shadow is obviously halfway up the shadow of the hill you are on — **use the shadow of the mountainside.**

To find your tiny shadow:

Close one eye — to line up more accurately.
Look past the shadow of your head falling onto your hand
Look for a 'halo' — a bright spot directly down-Sun on the plain
Wave your raincoat around
Well, you know where the shadow should be by now!
So you don't even need to see your shadow!

Keep count of height in body-lengths

(3) Walk up to a stone which was horizontal from you before.
(4) Downhill can be counted by leapfrogging with two people.

Half-Way across? Provided you stay in one position...
Looking parallel from half the height gives you half the distance
(5) E.g. when someone is swimming across a lake

Artificial horizons allow you to maintain parallel gaze (6)
E.g. "The edge of the lake is 'two fingers low'



<horizon (or **any distant landmark**)

<lake edge (now, halve your height above water e.g. by squatting down)

Adjust Your Expected Pace

! Three hours up, two hours down — are typical proportions, except in very steep or loose descents — 6 hours up, 6 hrs down.
! You walk more briskly while fresh, in the morning, than after a whole morning's walk. Pace yourself with this in mind.
! Groups travel slower. Allow the slowest person to set the pace, because stragglers may battle or even panic if left behind.
! Retracing your steps is quicker, since it has fewer diversions, less interest, and no unknowns. Allocate less time to return.
! Carrying packs is not necessarily slower, on flats. If your pack is uncomfortable, you won't dawdle, or even want to sit down, and can't stop to look at insects or flowers or to chase birds.
! River crossings chew up enormous amounts of "fussing around" time — organising and reorganising afterwards.
! Beware of smoothed out "routes" marked on maps. The actual terrain may involve many obstacles and consequent slow going and detours. The words "route only" are trying to tell you that.
! Your pace quickens surprisingly when the party falls "into the groove" of walking (without talking, noticing things or relaxing often).
! Path finding can make you nervous especially in unfamiliar territory, which tends to quicken your pace without you knowing it.
The same person, following a leader, is relaxed — and slows down.
So when you take the lead and you wonder why the others seem to fall behind, realise that you are too keen.

Don't Overcompensate for Slopes And Meanders

The worst case for slopes is about 36° for rock scree. But that adds only a quarter to the distance shown on the map. It is far more relevant to say "It's the climbing and the awkwardness which will slow us down more".
The worst case for obstacles is grass-tussock negotiation — but that only adds a maximum of 50% to your distance covered.
An ordinary zigzag may only add 10%



Distance by averaging Maximum & Minimum Guesses

Yes it is worth doing, because it reduces the slop in your individual guesses.
E.g. "More than a kilometre, for sure. Less than 3 km surely! Split the difference & say 2 km

Distance by Comparison with Some Length You Know

E.g. The central business district—1 square mile or whatever
E.g. old-fashioned 'chains' i.e. cricket pitch lengths
E.g. 100 m race; playing fields
E.g. "a day's walk"
E.g. that island which you can see, which the map says is 1 km long.

Distance by Cloud Shadows — Look for Them

- Notice how quickly the cloud shadows move here (use distance/time), then look how slowly they are moving over there
- Time how long they take to get there.
- See how large they look here, and how large there.
- Look how high the cloud base is here, then compare the size of hills in relation to that ground-to-cloud gap, over there.



Hint: To see which shadow attaches to which cloud, hold a string, to pass from Sun to shadow (past its cloud) but… Don't look directly at the Sun!

Sound Travels Three Seconds to the Kilometre

This tells you how close the lightning storm is. "(Flash), Alligator One, Alligator Two, Alligator Three, Boom!, One Kilometre!"
If you see a flash to ground, you can find the distance there.
Otherwise, the distance is to the nearest part of the lightning flash overhead.

Align the Track

Line the map up with what you see! Often that is the road ahead, or a well-marked track.
This is a great trick for the car navigator when using a road map — it's so easy to see the line!
It's equally helpful when following any marked track on the map with the map aligned to the landscape — it locates you on the map — on that bit of the map which lines up with the track.

If you were landing a fighter jet onto an aircraft carrier in the fog, you would not want to miss the runway!
Well, think of the real track as the runway on the aircraft carrier, the land as the sea around it, & the tiny map-picture of the track as the jet plane.
Twist and turn your 'jet plane' until it can come in to land properly. Even when you are in the fog!

Assuming you have a properly oriented map…

You can find where you are on it…



If you know where you are on the roadmap…

..Now the map is properly oriented.

Compass Errors — Be Impressed! Be Careful!

Electrical currents swing the needle e.g. reading the compass by torchlight; untwisted pairs of DC wires e.g. marine compass lights; Mobile phones; GPS; radio. "Impressed (DC) current" anti-corrosion systems in marinas.
Magnets e.g. other compasses, motors, loudspeakers, clocks, ironstone. Note: Iron-rich dolerite doesn't look rusty.
Iron & Steel e.g. your pack, pocket knife, keys, wrist watch, cutlery, steel-capped boots, glasses, geology hammer, batteries, torch, studs, zips, pens, trig points, shed, fence, car, ironstone, buried machinery, coils of old fencing wire half-buried in the ground, tools, fuel stove, internal springs, reinforced concrete, railway lines, power pylons, pipelines. Navigating in a mineshaft.
Many of these might have permanent magnetism too. Stainless steel is often magnetic.
User error
Parallax — viewing the needle from one side; viewing the scale from side-on.
Misreading — e.g. any scale marked every 2° is easily confused. Mis-setting the movable scale.
Miscalculations — especially applying the variation the wrong way — adding it instead of subtracting. Confusing left and right.
Out of date chart of deviation. Deviation is the general name for any compass error—apart from expected, normal variation.
Quality of Construction
Needle instability; under-damping; over-damping; motion. Let it settle. Put it on the ground.
Vibration — has unpredictable effects e.g. twisting the needle clockwise. Walking provides regular slow vibration! Motors.
Sticky pivot — Tap the compass Un-centred pivot
Zero-error — the needle doesn't match the 'zero' Mis-calibration of the protractor
Needle mis-magnetisation — not quite longitudinal; amateur attempts at re-magnetisation.
Reversed polarity — Poor quality needles can pick up remagnetisation from nearby strong magnets without you knowing it!
Variation The difference between True North and Magnetic North changes with time and place. The map is out of date.
Magnetic drift of the magnetic pole — we only have 'predictions' or 'trends' of an unpredictable variation. Are you up to date?
Latitude change — alters the magnetisation of surrounding fixed iron e.g. a car body or a boat's motor or hull.
Local anomalies e.g. Tasmania is full of ironstone dolerite. Many rocks preserve ancient magnetism.
External magnetic fields e.g. which way a boat moors, or who moors next to it. Competing fields change or capture each other.
Lightning strike after-affects.
Correcting mechanism out of **adjustment**.

Map Folding and Map Holding



Maps aren't forever — they blow over waterfalls, tear & get unreadable.
  Pack a spare
  Cover the whole surface with (non-shrinking) clear plastic film
With good-quality laminating plastic & cutting, taping and sealing, maybe it will last forever!

Folds and Corners lose details, and wear through.
  Cut along the fold lines cleanly e.g. to A4 size

Use a photocopy of your own map to use in the field, to keep your original map in good condition.
Wet maps lose details when rubbed.
  Get an A4 plastic sheet protector for the map. Tape it closed. Hang it around your neck.

Mapwork requires bearing-lines to cross the whole map.
  Tape the (A4 or other) sections back together with wide clear tape, leaving wide gaps, as shown.
  — you can butt the edges closely when needed; the tape will crease out of the way
  — you can refold it at will, as often as you like, and show the two most useful sides out of the many sections.



Distance by Double Pace — Test Yours

A 'mile' (or "thousand" in Latin) is a thousand double-paces, on forced march i.e. 5.28 feet (Romans were small people)
My dawdle double-pace is 5.25 feet. What is yours? In metres?
Answer: Test it. Test it again and again. Average it. Each person is different. Relax, don't push yourself.
Test it again uphill, downhill, laden, unladen, tired, in a hurry.
Test it at one double-pace per second — walking by the clock.
It helps to make a 10 m cord. Use a tape measure to make the cord, then use the cord.
E.g. I know I use 12.5 **paces (single steps) per 10 m** i.e. alternating 12 & 13 double places per 20 m.
and I walk at 4.5 kph; 1 1/4 metres per second; eight **seconds per 10 m.** The timing varies more easily than the distance
While watching the seconds tick over on my watch, and striding out in time with them, I manage 1.5m/sec, get tired, and step further out.
You Can Be As Accurate As You Have Been Careful. If you are full-grown, working this out once can set you up for life.

Tie Your Ankles Together!



For a well-measured pace (heel to heel) use a 50 cm cord, for instance.
Count double-paces, and don't lose count — see 'finger math'

Test your pedometer

Pedometers work in different ways, so test yours on different terrain. Your knee-lift is higher on uphill sections, and your pace is shorter in rocky terrain. You can make your own pedometer from an old odometer, working off the flex of your boot, your hip, your walking stick, or whatever, or you can roll a small bicycle wheel along the ground, fitted with an odometer.

Don't Lose Count! Use Finger-Math

Finger counting is a silent and **number-free** counting method — you only pronounce the number after you have finished counting. Count automatically, by placing your fingers down, each in turn, onto a hard surface.
A thumb counts for five fingers, and the **left-hand counts 10 per finger**.
When you run out of digits you have 99, so you next say aloud "A hundred" and start over again with no fingers down.
Place each finger down onto a surface, in a **definite sequence**: Right Index ("1"); Middle (two fingers down); Ring (3); Little (4); Lift all four and put down the thumb ("5"); Leave the thumb down and put and leave down the index finger (6); middle (7); ring (8); little (9); Lift all five and put down the left index finger ("10"); Then put down the right index finger again (11), and so on, until you need to put down the left middle finger in place of the other five (two 'tens' down).
With practice, you can count, add, subtract, multiply and divide — almost thoughtlessly — as quickly as with an abacus.
We are concerned here with **counting single or double paces**, e.g. in a fog, and doing so **in lots of 10m** (or 20m or 40m for double paces). I.e. you count up to about 12 or 25 single or double paces mentally, and add "one more lot" to your finger tally.
If you are in a group, you can check each other's counting by stopping where you think every hundred metres is.



Lift all your fingers off
and nod your head down
for '100', then start again.

100 lots of 10m equals 1km
100 lots of 20 m equals 2 km
100 lots of 40m equals 4 km

or 100 double paces is 1/10 of your mile

Lighting Conditions & Eyesight

Make allowances for optical effects…
Looking up-Sun, especially in the afternoon, you see haze (backlit dust & insects) which gives a false impression of 'distance'.
Looking down-Sun on a clear morning after rain or after a cold change (i.e. minimal haze) things 'look close enough to touch'.
As your eyesight begins to fail in mid-life, everything seems 'distant' but turns out to be surprisingly close
i.e. you have been judging distance by crispness of detail all your life…

Visual Acuity is about One Minute of Arc

..which means that you can spot a 1 m object at 3.6 km on a clear day (since one minute of arc is (1/60)° or '1 in 3600').
I.e. You can see details several thousand times smaller than the distance to them.

This is how seamen can judge distances over open water, to land, even though there are no other clues to go by.
They ask: "Can I see trees? What about tree trunks? Or branches? Or leaves!"

Lighting, Contrast, Haze and Eyesight play havoc with accuracy; But experience is a great teacher.
Feed your mind and memory by deliberately looking through the haze to the finest details you can pick up.
Use binoculars as a cross-check. Have competitions with your family.
Children have better eyesight, but the idea is to judge the distance according to how it looks to you.

Align the Map to the Landmarks

Make the Map Match the Marks — if you know where you are on the map you need only one landmark…



The easiest way to keep the map aligned to the landscape is by then using the direction of the Sun now, a very visual method.
The commonest method uses a magnetic compass to find North.
This one-landmark method can be used whenever you can see something in the distance.

If you don't know where you are on the map you can still orient it to match the landscape, but you will need two or more landmarks identified to do this.

Compass Use — Master It, but Be a Good Master.

- Use it to orient yourself, then put it away!
- Use it to orient the map or to choose a route, then put it away!
- Use it as a protractor. Use it as a ruler. Use it as a map scale measurer. Use it as an artificial horizon. As a set-square.
- Use the set square for a back-course or a side-course without altering the forward-set-course.
- Don't rely on it — use other methods of direction-holding.
- Let it point your eyes outwards, to the horizon.
- Use NORWEST/NOTLEAST, if you have to stare at it — e.g. in a cave.
- Hold it 1½m above rocks; 10m away from cars, sheds, etc; several item 'lengths' away from small items — test it.
- Let it point out a foreground mark as a destination, then follow a visual line of sight
  e.g. 'leapfrog' or manoeuvre by 'legs'
- Don't consult it again until you need to check or choose another point.
- Don't trust it, but trust yourself to it, when you need to.
- CHECK ITS ERRORS. Check it against the map by taking a bearing from a known point to a distant landmark
- Take a pair of forward and reverse bearings—to and from a chosen mark, to check for local magnetic field anomalies.
- Check your errors in using it, e.g. on the move; against someone else.
- Interpret it for orientation value, not just for route-finding.
- Consult it more often than you want to, when you are 'not using it'.
- Check your guesswork as to e.g. 'Gully North' or 'Wind-West' by it.
- Take it.

Layout Map — Blind

- This project requires a pedometer to measure every hundred, metres or paces or something. A stop-watch could do.
- Use graph paper, so that each square on the graph paper represents one 'leg' of 100 (or '1 minute's walking').
  (Hint: Graph paper is a handy thing when making a casual mud-map of your progress, for this very reason.)

Try it at least once. Without triangulation and cross-checks you can build up the layout just by reading the compass.
i.e. Beware: This is a bottom-up method, prone to inaccuracy. After one accurate practice-run, you can do a better casual job.
I achieved over 90% efficiency at coming back to my starting point after a 24 km circuit on my first try!
(In fact I know that the 8% error was mainly only due to a few blunders in marking the wrong direction.
Also, I only measured 'direction' to +/–15° since I was also testing the 'clockface method' of direction — to the nearest ½hr.)

When the compass read "2:30", I needed a reverse clockface on the map, and I needed to mark…







(Hence I made a few left-right blunders which I had no record of!)
You don't need a map for position-sense, if you make your own as you go. Position sense is hard to come by, otherwise.

Line of Sight Can Be Extremely Accurate



..But is often neglected, for far inferior methods.
E.g. locate yourself on a 'position line' as a means of marking your progress…
E.g. keep a straight line by walking to a point ½ way between you and your next destination
E.g. 100 fence posts can be positioned to look like one when seen end on.
E.g. fishermen can **locate** their offshore fishing spot again
— "The jetty is underneath Mount Lofty, and the tower is behind the Town Hall"
You can sometimes consult a map to fix your position...
E.g. You may notice that **"this part of the track runs directly toward"** a peak.

Un-mappable lines abound. Choose the **nearest** objects in front for best accuracy.
E.g. "That far rock lines up with this bush. **Remember** them!"

Use mapped features and the accuracy is still extraordinary.
E.g. "The peak lines up with the intersection, but if you step only three paces left you can see the difference!"
The alignment doesn't need to be accurate, provided you can memorise the exact inaccuracy e.g. 1° to the left of the hillside.
Two such alignments are needed for a fix. Look around: "What is in front of Mount William? What is behind the lighthouse?"

Two Opposite Landmarks

It **more than doubles** the alignments available to you if you have eyes in the back of your head!
With two people, separate some distance, for accuracy, then **look past each other's heads**.
Walk slowly around in a circle looking at the horizon for possible line-ups.
With one person, **place a rock on the ground then circle it**, scanning the horizon. Place a pebble to mark each feature.
The good thing about this method is that one landmark cannot 'blot out' another — all the visible features are available to you.
You may use this method to stick to a direct 'track' between two landmarks.

A Slow Kilometre Cancels out Three Quick Ones

Let's try to keep up an average of 4 km per hour…
First we travel 2 km in half an hour, but then we hit a slow section and manage only 1 km in the next half-hour (2 kph).
To counteract this we would need to triple our slow speed to 6kph for the next half-hour!
So we then decide to stop and catch our breath for half an hour.
To counteract that we would need to double our desired average speed (to 8kph) for the next ½hr!! Or 6kph for 6km.
i.e. a wasted hour takes several hours of catch-up, to regain.
(2kph for ½ hr + 6kph for ½ hr = 4kph; 0kph for ½ hr + 8kph for ½ hr = 4kph; 0kph for ½hr+ 6kph for 1hr= 6km in 1½hr)

Slow sections chew up the time available, so don't dawdle.
Quick sections can't easily repair the damage, because they don't last long.
You may try to be time-efficient and walk more quickly on the easy sections i.e. hurry along the flats,
but you can't gain much time that way.

To Progress Faster More Easily
Pace Yourself — Slow Down, but Don't Stop

i.e. Pace yourself so that you don't need rest stops, since they ruin your time budget, and it is time which determines pace.
It is better for your overall pace to keep walking slowly than to stop completely.
Go slowly on the hard sections. Pick up your pace, maybe, on long flat easy sections.
Shorten your rest stops e.g. don't remove your packs.
The old rule to cover a lot of ground quickly is: run 50, walk 50 (paces or double paces).
Catch the paradox of it — to keep going faster, go easier.

Approximate Figures for Visual Acuity

At 1:1,000 "I can just count my grandchildren"
At 1:2,000 you can count individual items.
At 1:3,000 you **can't count** them. E.g. people/shrubs/birds
At 1:4,000 you can **see** items, but can't count them.
At 1:5,000 you **can't see** them individually.
At 1:6,000 you can **read unfamiliar letters**
At 1:7,000 you can't **read unfamiliar letters**.
At 1:8,000 you can **read familiar signs**.
At 1:9,000 you can't read familiar signs
At 1:10,000 you cannot see that there are individual letters.
At 1:15,000 you can see single objects e.g. trig points against the sky.

You need to supply figures which work for you.
Multiply the size of the smallest objects you can **count** by 2,000
Multiply the size of the largest objects you **can't** count by 3,000
Multiply the smallest items you can **see** by 4,000.
Multiply the largest details you **can't** see by 5,000.
Multiply the letter-stroke widths you can **read** by 6,000.
Multiply the letter-stroke widths you **can't** read by 7,000.

Of course it's rough! I told you so in Rule 1: Guess!
Adjust the numbers to your eyesight e.g. "I can only count to 1500".
The idea is to build up your subconscious guesswork.
E.g. "I **can count** to 3000 and can count house windows" try 1 m x 3,000 = 3 km away
"I **can't quite see** heads" try 25 cm x 4,000 = 1 km away

Test Your Own Visual Acuity



Walk up to a signpost until you can read it. Pace the remaining distance.
Measure the size of its letter strokes.
When do you lose sight of a dollar coin?! Can you count heads in a crowd at 600 m?
Set up a 1 cm test pattern of squares (for others) to count. Try yellow squares too.
Test yourself in different conditions — on an overcast day, in direct sunlight, in glare, on a hazy day, and at a large distance.

Align the Map to Identify Landmarks

Lift your eyes from the properly aligned map back onto the landscape… "There should be a peak in the distance over that way." "Look for an outstation in this direction" "Can you see the transmitter structure??"



This is "Map To Land" navigation.

If you are on a peak, you may want to keep a copy of these relative directions in a notebook (especially the ones which go off your map).

"Magnets Grip Maps"

This mnemonic is meant to remind you to twist the map to the north — the map should be one piece with the compass needle.

- Place the compass on the map
- **Grip both the map and the compass in one hand**
- Turn the whole map, or yourself, or both — so that the magnetic needle points to the map's magnetic North

The result is that the map is aligned to the landscape.
Keep it that way!
Even while you walk, and twist, and turn… This is called "Swinging the Map".
A one-off effort is called "Orienting the Map".
Swinging all three of you is called "Orienting yourself" e.g. to North.

Align Your Map in the Dark

The commonest way to align the map to the landscape is by a magnetic compass.
The magnet — the compass needle — must 'grip the map', magnetic North to magnetic North, in order to keep the map oriented.
One method is to set the compass protractor to zero — true North — and
set the compass edge to grid North/true North (see diagram) and then
set the magnet needle to magnetic North — as marked on **the compass rose on the map**
Another method is to line the edge of the compass up with the magnetic North mark on the rose.
Then you simply keep the needle point pointing to zero on the protractor.
A third method is to set the compass to the correct compass heading then line the protractor edge up with the desired course on the map, and the needle to the protractor, then follow the compass arrow.
A fourth method is to set the compass to the correct true course on the map, then line the compass needle up with magnetic North on the map, then follow the arrow. But **always line up the two magnetic Norths!**

The Magnetic North
marked on the map
is crying out
to be matched up with…
..the magnetic needle
but check
that the
angle is
drawn to
scale!



A Compass Holder

Rather than hanging the compass around your neck, where you hardly ever see it, you can make it constantly visible.
For map making, it is indispensable.



Version 1: Aluminium wire around your neck and around the compass, like a bib or harmonica holder…
The compass circle is grasped by a circle of non-magnetic wire.

Version 2: Hang a flat map board from your neck, and blue-tack the compass on to the map board…
Drill holes in the four corners of a light board.
One string loop goes around your neck and through the two close corners.
Another string loop goes around your neck and through the other two corners
and has an adjusting knot in it (rolling hitch).
The compass protractor is set to 0° i.e. Use Magnetic North
or it is set to x° i.e. Use True North
To orient the map, or yourself, turn around and face North.
For a back-bearing, turn around and use the white end of the needle to read your direction — where you have come from.
Use the "NORWEST; NOT LEAST" mnemonic to keep you in touch with normal orientation. See p.101c & 106b for how to build up a map, or keep track, blind, using such a compass holder.

"Changeover Lines" of Progress — Relative Apparent Sizes

All visual elements which surround you have an apparent size, each of which changes as you progress.
E.g. "The hut behind us seems so tiny now, poking out from the sea of snow"
E.g. "That hill now seems to loom **high** above the plain" (a vertical angle).
Two apparent sizes will, at some stage, become equal, at e.g. as you move away from one object, which shrinks, and toward another, which expands. Simply notice "the changeover" and you have 'a line of position' to log your progress.
"The hill is the **same size as** the leaning over gum tree" (a vertical angle, a diagonal angle, and a changeover line)
You don't need to remember what size you measured — just compare them for equality!
"The width of the patch of forest is much less than the island is **across**" (horizontal angles)
"But the island alongside us is about the **same width** as the **gap** between the two" (another "changeover point")
You don't get a single point fix, only a line of separation. The third and fourth diagrams each show an example.
A measurement without numbers is like saying "We are halfway there" instead of saying "4.5 km on"
or like waiting until you are "Exactly East of Mount Big" rather than measuring "079°C" at any time
or somewhat like "These two line up, if you put a hand span in the gap"
The closer the objects, the better. The more distant, the more careful you need to be!

Use the Landscape Itself to Measure & Mark Progress

Example: "Where I came out onto the beach,
Sloop Rock was one island to the right of Gannett Island"
A top view shows that this is simply a line of sight, locating a point next to the island.



Island = gap;
An apparent-size changeover line



Rule of Thumb for counting





°

Distance-Off by Vertical Angle



The simplest range finder is a piece of grass held at arm's stretch, (if your fingernails are too small).
Measure the apparent height of something which you can recognise later,
then measure how many millimetres of grass was needed!
You can relocate that distance-off later by its apparent height e.g. distance from a prominent peak;
from a lighthouse seen from offshore; from any recognisable tree; or from a cliff with a clear base to measure up from.
This is how our mind analyses the skyline heights — it is a very 'natural' method.
Yacht navigators will find out the height of a lighthouse from a chart,
measure the angle with a sextant, and calculate the range by trigonometry…



To fix your position requires two separate measurements e.g. two different vertical features
In theory, the plotting looks like two circular arcs intersecting, because any distance-off must give you a circle of possible positions.
The closer the features, the smaller the circles, and the more accurate the fixing of the location.
Confuse your friends with: "1 inch away from the windmill, and 13 mm from the pine tree"…

Safe Distance Off

You might be sailing around a headland or reef, and want to maintain safety…
Without needing to know where you are you can maintain a minimum distance off.
E.g. "no higher than 1° apparent height by vertical angle"
E.g. "keep the horizontal angle acute, between those two points"
E.g. "stay outside the apparent radar range of 5 km"
E.g. "deeper than 20 m"



Discard one of the two possible positions.

Circle-of-Position by Horizontal Angle

Here you keep track of the horizontal space between two prominent points; or any noticeable gap; or the apparent width of an island. Use a string stretched across your line of sight, or a stick gripped between two fists.



In this horizontal case though, unlike the vertical angle, the 'circle' of position is really only a cusp — part of a circumference, which must pass through the two points, and your position.
If you are closer — a wide angle — the arc is flatter; a narrower angle means you are further away — a larger part of the circle lies on your side of the landmarks.





There is a constant angle
at anywhere on the circumference
when looking at the two points.

You don't need to draw this though.
Only memorise or note the angle.
To fix your position make two separate measurements e.g. one vertical angle and one horizontal angle too; or two horizontal angles—using three landmarks (or two vertical angles; or a radar range & direction from a single landmark; or use any other line(s) of position e.g. a compass bearing or line of sight or an advanced position line).
Now you can relocate that buried treasure, that fishing spot, waterhole, rare plant, good campsite… simply through making a couple of notches in your walking stick.

The best range-finder

..is a theodolite/sextant — designed to measure angles very accurately. You can use them horizontally.

Align the Map to Fix Your Position

Match the map to the landscape visually.
(The first result is to show you geographical (true) North.)
(The second result is to show up other landmarks.)
The third result is to show up **where you must be**.
(The fourth result will be to indicate which way to continue.)

I.e. Work **backwards** — from Land to Map.
One method is as follows…
Place a small pebble on the ground.
Place other pebbles in a circle around that,
each one lining up with some landmark.
Now place the map over that centre pebble.
Twist and shift the map until it lines up.
Get down behind the map and visually sight over it.
When everything lines up you must be at the centre of the circle
— over the central pebble.

Your position should **look** obvious!



A Horizontal Angle between Features Yields a Position Circle

There is no need to draw this position circle (diagram 1), and it is somewhat awkward to construct, but there are two cases which are well worth drawing (permanently) on the map…

Diagram 2. A right-angle between two peaks — it means that those two peaks mark the **diameter** of the circle — easy to draw.
Diagram 3. The 'circumscribed' circle of three peaks — you can see whether you are inside or outside of that circle.
To find the centre of the circle, use perpendicular bisectors.

The angle seen from the circumference is constant.





Horizontal angles are **larger** on the **inside**.



'Two Horizontal Angles' Usually Fixes Your Position



Record the information on a piece of string at arms' length
Or drawn onto paper
Or onto **tracing paper**
Or by compass bearings*
Or with a pair of compasses; Fold the paper against your eye
Or by angles cut into a leaf; drawn on the ground; folded into paper; etc
*you could plot back-bearings, or simply record the three directions for reference.

This is a quick, natural, accurate method which uses no numbers or circles. It is how our mind judges the horizontal layout.
Only one position on the map will produce such a pair of horizontal angles.
If you draw the angles onto tracing paper, you can **place it directly down over the map, to fit it on properly**.
If you make a three-arm trio of compasses with a locknut at the pivot, you can also place this directly onto the map.
Coastal yacht navigators find the method useful, and to measure angles very accurately they use a sextant horizontally.
In theory it plots as two intersecting circles — only one intersection makes sense.
The nearer the landmarks, the smaller the circles, and the better the fix.
Just don't choose three landmarks which are already on one circle along with you!





You don't have to draw these circles
Also, if you want to find an angle from the map
you can just read it from the map without drawing any circle

The Sine-Cosine Tally Method of Keeping Track, Blind

This project is only "for experience" — i.e. you are unlikely to want to do it twice! — but you should do it once.
The idea is to **keep a running total of your 'Northing' and 'Easting'** from a starting point.
I scored 97% efficiency in getting back home, on an 11 km circuit, on my first try, with an unreliable home-made pedometer!
It is a 'bottom-up' method — for when you are walking blind — when you cannot work down from the Big Picture.
With pen and paper you record your pedometer readings & directions, and update the numbers, say every hundred double paces.
E.g. "Current Pedometer Reading: 1400; (time-check 1 1/4 mins; pacing check 140 m) efficiency: 90% (slightly indirect path)
Recent Direction 005°; **adjustment needed +90, +8**; new tally: 419, -45; (comments: crossed a wet ditch)"

The chart of 'adjustments' follows this box, with an example.
200% efficiency would mean "I missed the last 100 reading"
50% = "I had a diversion" 110% ="I stopped at 110 — make the next reading 90% efficient"

◇ Set it all out with headings and long columns.
◇ Your judgment and arithmetic don't need to be accurate, because the errors are likely to cancel (!)
◇ Check your pedometer for each type of terrain, by time and by pacing.
◇ Avoid blunders e.g. check that the direction and the adjustments are similar between two legs.

It is quite pleasant to stop every minute or so — at every 100 on the pedometer — It keeps you alert, rested and oriented.
Making a full map (see 'Layout Map—Blind) is more satisfying and just as quick.

Mariners can (either draw their tacks, or, using this method) calculate an overall course-made-good from their many compass legs, by first adding up (distance x sin true course) East, and then adding up (distance x cos true course) North, from each individual distance and course.
Their overall distance is $\surd(\mathrm{sum1}^2+\mathrm{sum2}^2)$ at an angle of arc-tan(sum1/sum2). Then correct for magnetic variation.

Rise and Run Adjustments — Sine and Cos — North and East

Caution: These are COUNTER-Clockwise Bearings! — as seen from a compass holder…
I.e. The needle swings to left and to right while you point straight ahead.
E.g. when the needle points to "20° East of 0°", as in the diagram,
"N(orth) O(n) R(ight)-West" reminds you that you are heading NNW-ish,
not to the East. N20°W is your **anti-**clockwise heading.
Don't let this unusual method of measuring bearings confuse you
about normal clockwise bearings.
There are really only 10 pairs of adjustments used in the whole table
I have made East positive, only to match normal bearings and
Map grids, which use East as positive (West as negative).
Here, **West is negative; East is Positive.**
South is negative; North is positive
Examples: North East is + + N315°W;
South West is – – N135°W;
North West is +– N45°W;
South East is – + N225°W
The + and – signs tell you
how to change your tally of North and East.
E.g.
100 paces to the NNW ish, as in the diagrams is...
94 paces of Northing and 34 of Westing
Or +94, –34





Actual direction…	(NE	SE	SW	NW)	Change N	E
Adjustments…	+ +	– +	– –	+ –	cos	sin
Protractor Readings…	360	180	180	**000**	**100**	**0**
N nnn° W…	355	185	175	**005**	**100**	**9**
	350	190	170	**010**	**98**	**17**
	345	195	165	**015**	**97**	**26**
	340	200	160	**020°**	**94**	**34**
	335	205	155	**025**	**91**	**42**
	330	210	150	**030**	**87**	**50**
	325	215	145	**035**	**82**	**57**
	320	220	140	**040**	**77**	**64**
	315	**225**	**135**	**045**	**71**	**71**
The next figures rerun the previous ones...						
	310	230	130	050	64	77
	305	235	125	055	57	82
	300	240	120	060	50	87
	295	245	115	065	42	91
	290	250	110	070	34	94
	285	255	105	075	26	97
	280	260	100	080	17	98
	275	265	095	085	9	100
	270	270	090	090	0	100

e.g. As a different example, a tally of –640 +770 means that you are 640 paces South
and 770 paces East of your starting point, which means that you are now N230°W from home, according to the table.

Rule of Fingernails



Your pointing fingernail should be about 1°, one in 60, when you stretch your arm.
Your thumbnail at arm's length, held upright, might be one in 50……
A pencil in your fist will be about one in 100.
Check it out with a tape measure and calculator. E.g. 1.2 cm (width) / 69 cm (distance from eye) = one in 57 = 1°
Adjust how you hold your arm (e.g. square in front, diagonally- or fully- on the side) and which fingernail, etc, until you find suitable combinations which you can remember.
But the trick to making this useful in range guesstimations is to guess the distance away first, then estimate the height of a mountain, as follows… 60 km away — use one in 60. One full nail means 1 km showing;
30km away—use 1 in 60 =½km showing; 50km away—use 1 in 50 = 1km showing; 10km away—use 1 in 100 = 100m showing
Reverse logic can give you the distance away, if you can see the base clearly e.g. from sea, and know the full height.

Rule of Tom Thumb



At various times you have to judge parallax.
And the trick is to project the needed sideways movement onto the intervening landscape.
Imagine yourself over there on that ridge — Are you as thick as that tree trunk? Are you as tall as that bush?
To make the two landmarks line up, imagine the distance over there in the distance.
"I would have to walk that far sideways over there" = "I would have to walk the same distance sideways over here"

Apparent Size

The size of people, cars, houses, as measured at arm's length, varies with distance. You know how big they are already.
To get a good gauge of very small angles, compare their width & height with a key or knife-blade or toothpick, held edge-on.

Which Way is North?


Left Edge of Grid North
Star North
Botanical North
Bush Noon (SH)
Adjusted Cusp North
Moon North
Psychological North
(Person A)
Upper Westerlies North
Wind North today
Gully North
Rock North
Map North (on a bad map)
Wave North
Dew North
Barnacle North
Low-Cloud North
Noise North
Calculated North
Reversed polarity needle
Not included are Coast North and other mental Norths.
True North; Due North; Geographical North
Grid North
Grid North Right Edge
Magnetic North on Map
Magnetic North currently
Compass North
Compass North near my boots
Snow North
Landscape (Skyline) North
(if my map is dis-oriented)
Prevailing Wind North
Yesterday's-Wind North
Previous Landscape North
These are only the horizontal Norths
Galactic North; Ecliptic North; Polaris
are not horizontal.
Neither is the North Pole.
Psychological North
(Person B)
A Northern Hemisphere Person Judging North by the Southern Hemisphere Sun

---

'East-least; West-Best' Rule — Tells You Which Bearing is 'Best'

This rule works only for horizontal directions, measured clockwise.
It is for shifting between True, Grid, Magnetic & Compass bearings 0-360°.
"Least" really means "Less than the other alternative number" **"Best" really means "More than the other choice"**
The following wording ("the North which is") is important, since you need to choose correctly between a right and wrong choice!
The "North" which is East **(clockwise) of another "North"** ***gives the Least bearing*****.**
Any *"North" to the West* (anticlockwise) of an alternative "North" yields the *Best* & Biggest numbers.
Specifically, it is most used to shift back and forth between magnetic North and true North bearings.
The wording may then be rendered: "Compass error West; compass heading best". Memorise that wording.
Because this mental arithmetic is a difficult ask, you need to draw a diagram to make the conversion clear.
Learn this reminder "Check-up-on-yourself!" diagram… And visualise it, on the real landscape in front of you.


North 'A'
North 'B'
Landmark

North 'A' is **West** of North 'B': it yields the **Best** of the two bearings.
(e.g. if A is true North, and B is magnetic North, the 'magnetic variation' is 'To the East'
and "the compass heading is Least")

Bearing A is Best (It yields a bigger number — East-around)
(e.g. if the magnetic bearing is 085°, the true bearing is bigger… 120°)

Bearing B is Least North 'B' is **East** of North 'A': it gives the **Least** clockwise angle.

It is the *North* which is "East" or "West"; The *bearings from it* are "least" or "best".
Numbers are meant to make sense — your job is to look for that sense, visually.

E.g. Compass Deviation………If my compass *North* points too far East e.g. by 10°, 050°M = 040°Compass (-*bearing* is Least)
E.g. Grid Convergence Correction…If Grid N is 2° tilted to E of true N, 070°T = 068°G (Grid is Least, since Grid N is East)
E.g. Map to Compass………… 090° on the map means: set your compass to 100°M, when magnetic variation is 10° West (Best)
E.g. Compass to Map………… 205°M as a compass bearing = draw 220°T on the map, when magnetic variation is 15° Least
E.g. *Add* the GridtoMagnetic Convergence clockwise *E* angle to magnetic N to get *Grid* N "MAG=**M**agnetic, **A**dd(the GMC)=**G**rid"

String Map

This is a fun-project. As you un-do each knot later, you relive the journey!
A suitable string is builders' twine — long, thin & strong.
An extraordinary number of code variations are possible, provided you can "read" the different knots afterwards!
Keep it simple, for a start.
Example: Start with a slip knot. Half-hitch it every hundred paces, to keep track of distance.
Tie a special knot at any change — to remember it by.
E.g. a strangler hitch around some bark for "thick forest"!; a thumb knot around a feather for "Water Bird Lake"
Chain the slip loop to keep it going. Or thumb knot the loop to lock it all up.

A simple numerical code is: slip knot; + n half-hitches; chain on; m half-hitches; chain on; ongoing tally…
n might mean something like 'direction' by clockface
m could be 'terrain type'

Here are some variations…


right and left
half-hitches
twisted hitch
multi-twisted hitch
crossed hitch
figure-of-eight loop
multi-turn hitch
slip knot; two half-hitches; chain-on
reef knot chain-on
thumb knot

Progressing A Position Line across the Map

Situation: You catch sight of one landmark; plot a back bearing; then travel — say for two hours, West — before you catch sight of a cross-bearing. You can still plot a 'fix'! Example (fictitious): You lose sight of Mount Connor in the Northeast; and later see Ayer's Rock. Your pace is 4kph. From the bearing of Mount Connor, you plot a position line (by a back bearing running back from Mount Connor). You must label this '10 a.m.' Now **shift the whole position line** 2 hours to the West i.e. 8 km, and label it '12md'. To do this choose any two points on it; shift those points 8 km West; draw **a new line parallel to the old**. You are now ready to plot another back bearing — this time from Ayer's Rock — to cross the advanced position line, for a 'pinpoint fix'. Alternatively, you could 'shift' only Mt Connor on the map, first.



Pinpoint "Fixes" are a Myth!

(Rule: Don't suppress uncertainty, nor reject any unwelcome information!)

Any 'line' of position looks exact. But it comes with unavoidable uncertainty and should be plotted (mentally at least) as a wide band of 'likely position'.
Potential inaccuracies abound. E.g. lining up the compass;
reading the compass; plotting that angle;
grid north variation across the map; map distortions;
errors in magnetic variation; protractor inaccuracy;…

You can now advance your "area of uncertainty"
across the map, expanding it with each blind move!
'Deduced Reckoning' navigation at sea (i.e. "intelligent guess")
is more a matter of keeping track of **accumulated errors**
due to tides, leeway, inaccurate course-holding/recording/plotting, inaccurate instruments. So too on land.



Getting Started in the Dark

The task is to know what direction to head off in, when you can't necessarily see the landscape…
You need a Map & Compass.

TAKE A MAP-BEARING — Find the desired angle, on the map, in relation to the North-South grid…………..
— "About 60°, as a **guess**"
— Use the edge of the protractor
— Measure the angle — only the protractor is needed for this!
Line up both sets of parallel lines — mapgrid lines,
and the lines on the needle-holder-circle.
— The protractor will display the angle between the two sets of its parallel lines
"55° E. of N." (It is marked clockwise)
(This is Called Working from **Map to Compass**)

SET THE COMPASS — Using 5° East magnetic variation, and ignoring compass deviation…
Compass bearings should be 'Least'
i.e. 050°C
— adjust the 'Follow Me' Arrow to point to 50° (to the East of North)
Twist the circle on its mounting.
— Don't alter the protractor again!

FOLLOW THE COMPASS — Now turn your attention to the needle
— Line it up with the 'zero' on the protractor, by twisting the whole instrument,
And by using the grid lines on the movable circle as a guide.
— Twist yourself this time, to line up with the 'follow me' arrow. And off you go!











Mnemonic: **Map to Compass** (= Map to Compass Course) Means **M**ap Grid to Compass Zero;
Angle the **Ar**row to the course target;
Put on the correction; **To** Get it, use the East Least West Best Rule;
Compare the Compass Zero to the Compass Needle; **Pas**t the Follow Me Arrow is the Course Target.

Thinking Backwards

"Danger bearings" allow you to stay safe, without knowing your position accurately, but you need to think accurately… As seen from the lighthouse, you must stay on the right of 315° (and to the left of 060°). That much is clear from the chart. Anything 'to the right', is clockwise from the observer, so for the keeper to keep something (e.g. you) 'on the right' means to keep its bearing bigger than ahead. 'Ahead' is parallel to the 315° track shown, since the lighthouse keeper is wishing to see you 'on its right'. He will be happy to see you on any bearing bigger than 315° and less than 060° i.e. 315 to 360, 0 to 60. From your point of view, that means, that you must *use back bearings,* of 135° and 240°, and then keep those tracks on your right and on your left respectively, as you look in. 'Ahead' is parallel again, but opposite to the track shown on the chart, if you are trying to keep the track 'on your right'. Looking in, moving yourself to the left will place the track further to the right, and make bearings to things on it bigger. That means, in numbers, the lighthouse will bear more than 135° and less than 240°, i.e. It is safe to approach at **anything between 135° and 240°**. Notice that the more/less sense is preserved with such use of backbearings.



Taking a Bearing from the Landscape

- **Start with a guess** e.g. "That hill is about 060°T from me"
- Point the 'follow me' arrow to the landmark
- Grip and twist the movable protractor circle until the grid marks on it — i.e. the zero — line up with the compass needle
- Read the resulting angle off — between the zero (which is "North" —Compass North in this case), and the landmark.

The result should agree with your guess e.g. "The landmark lies at 065°C" i.e. East of Compass North i.e. clockwise from.
Take a B.E.A.Ring Mnemonic: **B**earings are Tracks; **E**xpect to have to plot a back-bearing;
Arrow to Landmark; **Ring** to Needle and **R**ead It off. (Think: "Arrowing" to remember A)



If it helps you sight the landmark, hold your compass string vertically upwards from underneath the tip of the follow me arrow.
The 'Zero' is meant to be used for 'North'! But if you point the follow-me arrow to North and the 'zero' to the landmark, then (a) it is more awkward and (b) it is an anti-clockwise "bearing".

If you are about to use a map, you must now convert the compass bearing to a 'True bearing'.
Firstly mentally change the compass bearing to a magnetic bearing if you are aware of any compass deviation i.e. compass errors. (You usually do not worry about compass deviations when bushwalking.)
Next mentally convert the magnetic bearing to a true bearing using the East-least, West-best rule.
Example: "6° variation West" (The Magnetic *North* is West of True) "Compass Best" so… 065°C = "059° True"
Lastly, physically change the protractor to read 059° when you want to draw on the map, at an angle to the map's True North.

See opposite & above

Plotting a ('Compass-to-Map') Back-Bearing

Draw a line on the map from the landmark in an opposite direction. Use the protractor to get the angle right.
If you see a landmark North of you, you must be South of it.
Or, what looks 'South-West of me' must mean that you are 'North-East of it'.
Think backwards! See "Back bearings: +/-200° then -/+20°" p.18e E.g. 059°T from me to it…
Note that I have already converted Compass to True. 239°T from it to me.
One bearing yields **one** line of position (from a back-bearing plot — diagram 1)…
Two bearings from two different directions cross for a 'fix' — diagram 2…
Three bearings don't cross. They form a 'cocked hat' and keep you humble — diagram 3…
In this case, you could be anywhere nearby (which is also true for any "Fix").
Expand your possible positions, don't try to pinpoint a "better" one.
Take more care next time, especially on the closer i.e. the more reliable landmarks.
Check your compass for fixed errors e.g. "always 3° too much".
Choose directions which are quite different from each other, to get the clearest crossing.
Compass to Map Mnemonic: (Compass B.E.A.Ring, then) **Compass to** Grid (or True) Correction;
Make it a Back Bearing; **A**ngle to Grid; **P**encil to Paper—Draw It in. (Think: "Mangle" to remember A)



No-Number Back-Bearings

Method 1. Use the white-tipped (South) end of the compass needle, when you take the bearing.
Method 2. Point the "follow me" arrow back toward you, when you take the bearing or follow the compass.
Method 3. Line the protractor zero up with Map South, when you plot the bearing.
Method 4. Point the compass edge to the landmark on the map and draw your back-bearing line backwards from the landmark.
You don't need to alter the compass setting at all (except for the magnetic variation or grid/magnetic convergence angle).
Warning 1. Don't mix back-bearing shortcut-methods, or you may get a 'double negative'!
Warning 2. Check all you do, against reality, for sense.
Warning 3. Don't try to shortcut Compass-to-True conversions at the same time as shortcutting the back-bearing, or you will get confused.

Parallax While You Walk — JUST DRAW IT!

Most **hand-made maps** start with **a known baseline** scale — a straight segment of a known distance.
I.e. "I walked from here to there in a straight line for 1 km" — for this you may need a pedometer.
Or if you are Captain Cook or Matthew Flinders "We sailed on (this) bearing at (this) speed for (this amount of) time"

You can then **add cross-bearings at any time** to fix the position of distant landmarks
— obviously at the beginning and end of the baseline are the preferred places,
perhaps combined with one from the middle…
The longer the baseline the more accurate the fix on distant marks.

You really only need a protractor for this **running base-line triangulation**.
(And on a Mudmap, you just eyeball the direction and draw an arrow in freehand.)



Here is an example of the easiest sort, and the reverse of a double-angle…
After a week at sea, with no sight of the sky to navigate by, I was understandably over-anxious about my position, and "needed" a "fix"! I decided to sail toward an isolated lighthouse-island, in the hope of passing close enough to see it, perhaps, if we weren't too far off course. The winds were hurricane force, of course, and the sky was filled with salt-spray lifted off from the water's surface. It was dusk. Suddenly, above the mist, dead ahead, the lighthouse turned on! Alarmingly high, and close. Too close!
Were we "found" or about to be "lost"!? (See "Aiming Off"!) After the cheers: "What do we do? How far off are we?!"
"Turn at right angles to it; Maintain that course; Take regular bearings until it is diagonal; Keep track of the distance run. Then resume your course. That way we can tell how far away it is."
"How can you do that!" said the bewildered, inexperienced navigator.
I replied: "I'll **just draw it**"



"We will pass as far away
as the sideways distance we have run"

A "Start-Stop-Rest" Navigation Mnemonic   Overview

START
"Start" has six points, as illustrated in the diagram below…
These mnemonics, e.g. S.T.A.R.T. or S.T.O.P., will be expanded in the rest of this section—they summarise the book.

- Start with a **Prayer** — "What more do I need to do to avoid getting dead?"
- **P.R.E.P.A.R.E.D.** — What have I forgotten to do or to take, to practise or remember? Start off oriented before you go!
- **S.T.A.R.T.** — with your start-off-trend-direction, which is the single most important navigational item. Start off aligned!
- Start on **T.I.M.E.** — Read your watch, and benchmark your trip. Say: "Time & Tide" as well, because sometimes tide levels are crucial.
  — Check pace & progress. Estimate the Range, because time is all about distance.
- Start time is **6 a.m.** — It's always time to **look** in **6** directions, plus 2—Time to Look **A**ll **A**round, **A**ppreciatively, plus time to look at the **M**ap
- Start with **N.S.E.&W.** —4 sets of 4 directions. The final W is for **W.E.A.T.H.E.R.**

The final R signals that you are **Ready** to go. Don't start until you **R**!

S.T.O.P. A **S**top is a **S**ignal—Interpret the Why? of your stop: Does it **S**ignal a change in watershed, catchment or view;
in **T**rend or **T**errain or '**T**ime & **T**ired';
in **O**rientation (embarrassment—if lost, rule one: Stop);
in **P**rogress/**P**osition/**P**lacement—campsite, junctions, features?

REST is best remembered as a mnemonic of 5 RE's…
R.E.-O.R.I.E.N.T. — using these letters as a mnemonic. E.g. **RI** re-Visualise the Invisible Big Picture, and **ENT** Relate yourself to Nature.
RE-RE.L.A.T.E. — re-interpret all directions to relate to each other and to the skyline, as explained below. Now don't forget...
RE-MEMBER — the WAY and the SEQUENCE and especially to NOTE down (in the NOTEBOOK) the NAMES, and DRAW what you need to.
RE-LAX — Play the Navigational Game—teach it—and 5 other games.
There is a final '-art' to 'stop and rest-'
RE-ST-ART 1.1 **re-**pray; 1.2 **re-**prepare; 1.3 **re-**s.t.a.r.t; 1.4 **re-**t.i.m.e.; 1.5 **re-**look (6 a.m.); 1.6 **re-**direct (NSEW), (which includes **re-**weather)
... e.g. 1.3 Re-S.T.A.R.T. after a rest, on the next leg—to relate it to the last & to the *start*-finish trend.

Summary: **"Start"** 6 times**; "Stop, and Re-st-"** (with 4 new **"Re-"**s)

(The Start mnemonic is a good example of the "clumping" technique
—never more than a handful of things to remember, yet it leads you into hundreds of points.)
Put the S for Sky at the top, where it should be.
Use a hexagon for the 6 START up points.
Use a clock-face for TIME,
and the compass-rose for NSEW.
Show the 6 directions in 3 dimensions.
Balance it all on a triangle
—for the "6 a.m. start" , since it has 3 parts.

See the boxes to follow



Now read the boxes to follow, downwards...

P.R.E.P.A.R.E.D.—A Before-You-Go Checklist ..so that most of your navigating is already done, from home!

P.ractise Global orientation. Get a blow-up globe. Teach others. Learn (what to learn, look for, do etc.). E.g. predict the Sun.
Learn the Mnemonics, Codes & standards e.g. S&R signals, compass directions
Pace your paces — metres per minute; steps per 10 metres. Left-right bias (blindfold).
R.esearch History. Ruins. Artifacts. Mines. Geology. Get a geological map from the library. Landform. Soils. Climate. Windy season. Prevailing winds. Wet season. Vegetation analysis. Rare species. Biogeography. Geography — global neighbours; time zones; local coasts & river mouths. Catchments. Cardinal features — places N,S,E,W from you. Land lines on map. Place names — their meanings and history.
E.quipment See the next box.
P.lace names See the box after that.
A.stronomical orientation Sleep on a map, and with a compass nearby. Point the map North. Times and directions and heights of Sunrise & set, Moonrise & set. Southern Cross. Pot. Sun at noon, at magnetic North/South, when East, when West, at magnetic East and West. What landscape markers (from the map) for these directions? The star opposite the Sun. Time zone. Local noon — its exact time. The Sun's coordinate predictions. Your longitude. The "Equation of Time". Moon-phase, -number and –day of week. Tide times.
R.eminder Note your intentions—and tell someone where you are going and when you expect to be back.
E.xpectations of the Weather Barometer reading. Get the Weather forecast. Follow the Changes. Buys-Ballot's law. Steering winds.
D.irections & Familiarity Ask someone who has been there. Read track guides. Look at an aerial photograph. Go beforehand! Find your old track notes. Look closely on the way in. Choose a route. Plan your strategies. Coordinate the cars, the car keys, any food drops, shuttles or codes

Equipment — A What-You-Might-Like-to-Take Checklist

(E. in PR**E**PARED, for "Equipment"…)

- **A Map** **A compass** **A clock**
- A notebook and pen — for track notes. A track guide. An aerial photograph. A navigator's handbook.
- For map making — graph paper, paper, pencil, a compass-holder. A map-holder (string around neck to a…), clipboard, stopwatch.
- Polaroid glasses — to orient by the dark blue sky band. Radio — for RDF, weather. Mobile phone. GPS. Camera.
- Binoculars. Pedometer. Rangefinder. Calculator. Altimeter. A sine-cosine table.
- A map cover. A spare map. A navigational protractor. A magnetised needle. A sundial compass. A two-flap cardboard compass.
- Marker tape; Chalk; Scissors (for cutting leaves!). A clear plastic tube. A clear plastic drinking bottle (for an artificial horizon).
- A long piece of string (e.g. for a range-finder). Short pieces of string (e.g. for a plumb-bob). A walking stick. Someone who knows the way.

(P in PRE**P**ARED) **P**lace-Names —Learn Them—You Navigate by the Local Features!

"Look. That's Big Split Rock and that's Little Split Rock. Wild Dog Tier is that range over there, and this plain drains out over there, into the Ouse River You can find your way anywhere around here from those."

Suddenly I was unforgettably oriented, just like he said he was, when his dad told him.
For me, the funny names on the map now meant something worth knowing.

Place-names are not just names you don't know; they name places, which you ought to know.

More accurately, place names 'place' you in the landscape, as well as 'orient' you to it.
A sense of location is almost independent from your sense of direction, and is rarer to come by.
Direction-sense places you in relation to very distant background references i.e. it doesn't 'place' you at all!
Location-sense places you in relation to the immediate foreground — visible landmarks, catchment basins, fixed 'tracks', etc.
Place Names Place You

S.T.A.R.T. off Oriented

— **S**tart-off Direction? (e.g. "upstream") — the **S**ingle most important navigational knowledge — it tells you the return path, and the search path.
Sky/**S**kyline i.e. especially according to the **S**ky (e.g. "toward the Moon; into the sunset") and related to the **S**kyline.
Start-off directions for the parallax method, pp. 51a,53a, e.g. to magnetic NSEW skyline or recognisable middle-ground points, or rhumb-line point and another set of such bearings, taken from the map, as seen from the finish, if you are on a one-way trip.
— **T**oward what **T**arget? Specify a
Track (e.g. "downhill to the lake") or a **T**rend. A rhumb-line bearing is best—from start to finish.
Through what **T**errain? (e.g. especially see what the land-shapes would look like without vegetation)
— Away from What Point? (e.g. "from the lookout carpark), and in what
Anti-direction (e.g. toward that other peak"—a skyline direction)
— **R**ain Catchment — In what major
Region? — as can be gauged by the surrounding
Ranges. (e.g. "on the main spur dividing North from South arm, downstream of…")
— Trend: **R**ead the **T**rend off the map, for starters; then continue to **R**ead the **T**rends & bends and the progress as you go on.
Read (your compass; map; watch) in **R**elation to the **T**rend, i.e. in order to follow the trend, which is the focus of this mnemonic.
Plus: **R**ead any other **T**rends, from any other places, from memory, in relation to the sky. Be able to revisualise them at will.
— Re-s.t.a.r.t. on the next leg, to relate it to the start-finish trend, and to relate it to the previous leg.

T.I.M.E. & Distance — that's the point

TIME to Look at your Watch — PACE YOUR PROGRESS — the point of this T.I.M.E. mnemonic is distance.
— "Watch" your steps—i.e. calculate your pace from the elapsed time;
— "Watch" the Sun without looking at it, because your watch tells you where it should be.
— TIDE times may be necessary.

Instrument Check — watch, stopwatch, pedometer, odometer, rangefinder — for progress
— compass: Double the bow angle, or halve the stern angle p.94c; parallax readings on landmarks.
— (and other instruments — barometer, altimeter, GPS, radio null, radar, depth-sounder)

Map-Scale Check — are you judging the scale well? — What is the next goal? (This M is not for Map in general, but only for distances.)

Estimate the Time of **E**xpected Arrival — guess each milestone ahead of time to set you free from a nervous TIME. Nominate an E.T.A.

Distance

PROGRESS: can also be gauged by lines of sight and changeover lines. Use a stopwatch, or pedometer. Read the scale.

PACE: distance divided by time; 20min/km, double and halve = 3kph; 1mps = 3.6kph; 4kph normal walking pace;
finger-math helps; pace yourself evenly.

RANGE: Use the letters of RANGE & FACULTIES as a mnemonic to remember the different ways of gauging distance in the distance...
Range squared = dee height; Area divided by offset; New direction parallax; Grass-leaf vertical angle, horizontal angles too; Educated guess
Familiar lengths, and Fingernail Rule; Acuity of vision and Apparent sizes; Cloud behaviour; Upper and lower guesses, averaged; Landscape lengths;
Tom Thumb Parallax; Intervening detail & haze alters your perception of distance; Extreme range comes in two bites; Sound travels at 1 km/3secs and
Sidewise offsets with blinking.

150km from 1 nautical mile high; 1° latitude from 1km; 50 miles from 500m; 50km from 1/5 km; 5km from 1/500 km (2 m); 12.7km from 12.7m.

Look in These 6 Directions — in 6 ways — Up and Down (Part of "Start at **6** a.m.")



UP — **Astronomy** — Sun Moon Calendar-Stars
— **Sky** — Clouds, Contrails — Blue Band
— What's up with the Weather?
then DOWN —Geology — **Soil** Type; Rock Type
—Clues — Animal **Trails**; Bootprints; Fallen markers

— Up-**Sun** — haze & glare
— Over what tropical country? Then — **Down**-Sun — haze, shadows, colour changes

— **Wind**-wise — Up-Wind — Where on the skyline? — Down-Wind — Around what obstacle?
— Around what pressure system? (Wind in your face)
— From what coast/ocean? Listen; Smell
— Up-Breeze — To what cold surface? — Down-Breeze — To what warm surface?
— What's up-Weather? Where are the steering winds coming from?

— **Land**-wise
— Up-Hill — To what dominant peak?
— Point to the dominant peak, even when it is invisible,
— Down-Hill — antidirection?
turn around to see what lies away from the peak — the "anti-peak", especially in relation to your shadow — this anti-direction has a lot to do with a compass back-bearing—a visible line of position, you see
— Up-Ridge — To what hill/hillock? — Down-Ridge — Down which ridge? — To what headland?
— what offshore/underwater topography e.g. shallow reefs; islands?
Since this mnemonic is about direction, try to point to them.
— Up-Slope — To what ridge? — Down-Slope — Into what valley? Name them.
At what angle across the gradient?
— Where is the lowest upslope skyline, under the canopy? — Where is the highest downslope skyline, under the canopy?
— Up-**Stream** — To what distant divide? — **Down**-Stream — What stream? To what distant mouth?
— to what sedimented shelf; or deep-water channel?

Summary: **Above & Below** (twice each) + **Sun & Wind** (above eye-level) + **Land & Water** (below eye-level) = 6 ways for "Up & Down"

---

4 More Slopes

1 in 4, is 14°;

10° (aim off, 1 in 6) is 175 m per km;

1 in 60, is 1° (1 in 57.3 is the exact figure, but it doesn't multiply up linearly after a few degrees, whereas 1 in 60 does well after a few degrees)
& n° is n in 60
(1 in 6 is 10°; 1 in 10 is 6°);
The equivalent is 5/3 in 100, 5 in 300, 167 in 1000, for use with multiplying up with the isosceles triangle angle method.

36°, 8 in 11, is critically unstable.

Multiply them up, inversely.

Look in These 6 Directions — in 6 ways — Ahead and Behind

Look Back Regularly: Is bad weather sneaking up behind you? (p.46c) "Abracadabara Peek behind you" (p.63b)
How much has the track bent around behind you? Any acute track junctions? Can you remember this way back?
Compare Forwards with Backwards: Do you need a back bearing? Are you half-way? Is your starting point visible, to get an anti-track forwards?
Are there any changes in the terrain, to photograph, in your mind? Have you memorised the transition, from the far side?
Look forward — in **time** — the forecast! What is the Estimated Time of Arrival? Look Back — in time — How far have I come?
Look ahead and behind in **U**pper case **Time** — Could you recognise this place much later, in hindsight? — What is the history of this place?

Look AHEAD — Has the **view** changed — into a new catchment? Look BEHIND — Have you left the old view behind — crossed a divide?
— at the terrain, the track showing up ahead, and the difficulties — Do you remember the **way**? Could you recognise it again?
— Look for track **markers**, and for trails ahead — Look behind for hidden, reverse track markers.
— Line up two (new) marks exactly ahead to keep your direction sense. — Look for the old lined up mark left behind.
Is it time to choose another leg, and a **pair of marks** lined up to it? Do I need to find new ones behind me?
Mnemonic: R,S,T-U,V,W,X-Y-Z **R**egularly **R**everse your nose. **S**tart/anti**S**tart bearing & **S**napshot-**S**equence your transitions
time (+**U**pper case Time); The **V**iew; **W**ay (remember it?); **XYZ: X** marks the Track (Markers); the (**Y**&**Z**) Leapfrog Marks =6 ways for Ahead & Behind.

Look in These 6 Directions — in 6 ways — Right and Left

Look RIGHT Through! 1. — the bushes, to the land-form underneath; to the contours & bedrock
2. — the canopy, to the skylight beneath it
3. — the trees, to the most distant marks, including other trees
4. — the treetops, to the sky — the Moon, clouds and the blue band
5. — the foreground, to the most distant skyline horizon, whenever you can glimpse it
6. — the haze, to the skyline details beyond the land horizon—use binoculars too.
E.g. to barely visible mountain peaks, or a second skyline & its parallax, or to islands in the haze, or the rising Moon.
Look LEFT 1. — to the most distant thing you have LEFT BEHIND on each side! i.e. Have you left it behind yet? Is it time to choose another one?
2. — Have you left behind your: handbook; air photos; track guide; track notebook? — No, well, don't just carry them — Look at them!
3. — Have you left anything behind at the rest stop? It's an important habit, to ask this each time you move.
4. — Look to the right and left, for the contours, the natural 'tracks', and the behaviour of the network you are crossing and leaving behind.
5. — Things on the right have big bearings; things on the left are lesser; than straight ahead, even less as you leave them behind.
6. — NORWest & NOTLEast — North needle 'on the left', means you are heading roughly East. (N. On your Right = West-ish)
Summary: **Right Through & Left Behind**.
In summary for all the 6 directions make sure you **Check Each One Out—Thoroughly!** (6 ways each)

..Plus in 2 More Directions — (1.) All, Around, Appreciatively, And At 6 L's

1. **A**ll your senses: Listen, Smell. Look around with your other senses.
2. Look 360° **A**round for the best & worst showings of colour, shine, flowers, greenery, new growth, fern fronds, lichens, trunks, branches, dirt. Compare Ahead with Behind, & Left with Right, & upSun with down-Sun, & up-wind, uphill, etc. for direction-dependent light and colour effects.
3. **A**PPRECIATE — the scenery; the colours; the contrasts; the shapes, outlines and silhouettes; the foreground movements.
4. **A**n Environmental Notice Time (see later box E.N.T. in REORIENT)
5. **A**ny LOCAL PECULIARITIES to remember.
6. **A**nd **A**t — **the six L's...** — **Land**marks — distances, sizes (apparent Largeness), altitudes Use binoculars.
   - — Are any familiar, from other walks you have done elsewhere?
   - — Do the place names make any sense? — interpret them!
   - — **Lay**out — relative angles, compass bearings. Am I inside or outside of major landmark circles/triangles?
   - — **Lie** — slope and terrain, catchment and drainage, contours and altitude
   - — **Lines** Catchment Dividing Ridges and Rivers; Contours at right angles to the slope; Flight Tracks
   - — **Ligns** — 'Same direction' Lines of Sight, or nearly so; and 'Opposite directions' alignments: Am I in between?
     - — the fixed A-lignments . Am I left or right of major 'ligns'?
   - — **Sky-Line** — talk it through; draw it. Cross-relate all directions to each other, and to the skyline

Summary: 'A' for 'a.m.': 6 A's, with 6 L's

..(2.) Look at **the Map**: a Systematic Checklist. (What 'System'??)

The system is to examine **top-down**. From general to specific detail. From large-scale to small-scale. Look for the downward progression in these…
3-D location: Latitude, Longitude, Elevation. Centre of the time-zone. The inset map showing where you are on the continent. Scale & size. The overall width- and breadth- distance of the map coverage. Grid size e.g. 10 km squares. Where you are on the map, geometrically too. The Starting Point. The Relative Location—over the horizon landmarks; coastal towns N.S.E.W. of you; something NE,NW,SE,SW of you. Radio stations. Highways. Light sources. Powerlines. Pipelines. Place names. Visible Landmarks. False peaks. Lines of the land — between landmarks. Recognisable hill-hill reference distances. Recognisable elevations e.g. towers. Grid North; True North; Magnetic North; Magnetic Variation; Yearly Drift in Variation.
Catchments & Divides; Catchment Size; Adjacent Catchments; River Drainage. Land shapes i.e. interpret the slopes, contours, the contour interval.
Trends and Bends — of the coast; rivers; roads; ridges; ranges; the track. Notice any creeks which flow backwards i.e. against the trend, and why.
What rising ground will be visible in each direction? Perimeter features surrounding your walk e.g. a river, a range, a road, the coast, a forest. Escape routes — unplanned exits. What are the ridge-line limits of the sub-catchment which most encloses your possible location? What high points are on it?
Possible routes. Clockwise or anticlockwise? Distances. Overall distance of your route. Milestone features. " Wake-Up " landmarks.
Initial bearings to landmarks. Initial angles to landmarks. Initial horizontal angles to landmarks. Final bearings. Rhumb–line trend from start to finish
Around what Obstacles? Fine details of the route. Don't forget the fine print — the date and reliability of all the map details; the grid datum for GPS use; the legend of symbols; colour codes; contour line thicknesses.

Mark the Lines-of-the-Land On Your **Map**

6 M's for Map:
Map Checklist (above); Map-Lines (this box); (all below...) Map Alignment; East-Least West-Best Mnemonic; Map & Compass; Map-Making Methods.

Pre-prepare your map — **Mark in the navigational lines** which the mapmaker has left out. Most of these are permanent.

A. Cardinal Tracks — NSEW lines. Across the whole map, from the very prominent peaks; or simply covering a local area, from the local peaks
B. Alignments — e.g. from Peak to Peak; Tower to Town; Point to Point — You may see two in line, or walk in between two landmarks.
C. Directions to major distant features — (for orientation purposes) — e.g. capital cities; coastal towns
D. The Overall 'Track' — the RhumbLine — from start to finish. Mark this lightly; &/or two or three obvious overall 'legs'
E. Circles of Distance Off — e.g. 5, 10, 15 km from Mt. X.
F. Circles of 90° horizontal angle — i.e. make two landmarks the diameter of a circle
G. Circumscribed circles around (i.e. which just include) the triangles in the triangular grid of landmarks
H. Transmitter to Transmitter networks — i.e. a triangular network of major peaks; include the distances and bearings on each line.
I. Flight Paths — if you can get hold of an aeronautical chart — it forms a second triangular network.
J. Catchment divisions.

Mnemonic: Four Straight Lines; Three Circles; Two Sets of Triangles; And One Very Sinuous Set.

Mnemonics for **Map** and Compass Work

◦ Map Alignment

A.L.I.G.N. the **M.A.P:**
A… Align the map to Sun with an imagined **A**rrow, and to your course with **A**nother **A**rrow;
L… to the **L**andscape;
I… To **I**dentify Landmarks and to get a Fix;
G… **G**rip the Magnet to the Map, and the Map to the Universe;
N… **N**ot "Swinging the Map" As You Turn;
Magnetic Needle to **M**agnetic North (in four variations, "0°" to North or arrow to course, Magnetic or True);
Angles Horizontal, fit over the map;
P… Align the **P**ath like landing a **P**lane, or align the map by aligning the **P**ath.

◦ Mnemonic East least, West best

East is Least and West is Best, tells you the North which gives the bearing that is best. i.e. the biggest in number; or lesser in number.

◦ Map & Compass

LMNOrP: Landscape; **M**ap; **N**eedle; **P**rotractor; either one **O**r two at a time, but not all three.

M.A.P. To Com.Pass, = Map to Compass Course, Means…
Map Grid to Compass Zero; **A**ngle the **A**rrow to the course target; **P**ut on the correction;
To Get it, use the East Least West Best Rule;
Compare the Compass Zero to the Compass Needle; **Pas**t the Follow Me Arrow is the Course Target.

Take a B.E.A.Ring: Bearings are Tracks; (**E**xpect to have to plot a back-bearing); **A**rrow to Landmark; **R**ing to Needle and **R**ead it off.

Compass to M.A.P.; Compass bearing, then **Compass**-**to**-True Correction; **M**ake it a Back Bearing; **A**ngle to Grid; **P**encil to Paper—Draw it in

◦ MUDMAP:

Mudmap on paper; **M**ark the start point on one edge; **U**p-arrow for orientation (**U**pdate it); by a Reference **D**irection (Up**D**ate it);
Maintain a trend, a long straight leg; **A**lign the **A**rrow when you stop; **P**encil in the **P**rogress, and a new leg direction.

◦ Other **M**apmaking **M**ethods — Use the letters of COMPASSES:

Copy a Map Top-Down; Own Map is Valued; Mental Map—Map to Mind Navigation; Parallax onto a Running Baseline; Accumulate the Layout Blind; Sine-Cosine Tally of Accumulated Eastings and Northings; String Map; Exploring a Cave System Needs a Book, of Strip Maps.

"N.S.E.& W." — the four cardinal directions, is a mnemonic of fours



N for "**N**orth Coast" — all about visualising the invisible directions…

Name which coastal towns are N. S. E. W.
"**S**weetheart" features Name your favourite spots NSEW of you
Encircling horizon features — **Horizon** North; **Skyline** South; **Environmental** East; **Landscape** West.
Which-way-am-I-going trend (rhumb-line), from the map, then marked onto the terrain—e.g. to behind that hillock

S for "**S**hortest **Shadow S**outh" — all about the path of the **Sun** (and Moon)—the 1234 system
— and the **S**unny **S**kies quadrant system
— How the Sun, Blue Band trend & ends, and your Shadow, currently lie in relation to…

N Highest **Noon** (How High?)
S Shortest-**Shadow** Souths (SH) & the two-flaps South. Coldest South is the best reference in the SH. String South using the Sun's Shadow.
E **Sunrise** (Where?) Anti-sunrise from a string-line to the horizon.
W Sunset (When?); Bisect them. Anti-sunset from a string-line in the afternoon.

E for **E**quinoctial **E**ast—i.e. other things astronomical, **E**tc.

Needle-North-Seeking-Northern-Canada—over Red Hot tropics!
South Pole Star (How High?) & Southern Cross (Where?) & Star-Chart octants & Star Compasses & Star Fixes
Ecliptic & Equator & Equinoctial Precession
W for the motion of the Pot, s**e**tting in the W**e**st (rhyme), at the latitude angle

W for **W**ind **W**est, i.e. Natural Directions.

N for Nature's Norths: Rock Noon; Botanical Noon; Solar Panel Noon; Satellite Dish North
S for Snow South; Frost South-East; Steep Gully South; Mud-in-the-Shadow South; Dead South; Siesta South.
E for Moss East-South-East
Wind: Upwind: scorch, erosion & flats, Downwind: shelters, debris & steeps; Noise & colour from up-wind; Rumble & skyshine from downwind.
& **W**eather Directions (& see below)—Where is Wind West? What is Upwind? Upper Winds Steer the Weather (from the West?) What is Upweather?

Summary: 4 directions with 4 variations; Then finish with **W**.E.A.T.H.E.R. After a rest, re-direct yourself.

W.E.A.T.H.E.R. — Check for Change

W. for Wind. Has it changed — in strength, direction, gustiness?
for Wind — in Your Face — Low on Your Left. Low winds bring the rain, clockwise.
for "Weather systems come from the West" — in temperate latitudes — can you make a prediction?
for the upper level steering Westerly-Wave Winds — are they deviating much from average? Are they steering a storm toward you?
for "Wind-West" showing up in the vegetation, for when the prevailing wind is not blowing.
for the prevailing Westerlies (or whatever).
E. for Ephemerals — i.e. the clouds and contrails (don't forget this E.!)
Have they changed? — in height, type, wateriness, thickness, darkness — in directions — steering wind directions? In relation to the Sun?
— Examine them carefully for dissipation (i.e. thinning, soft edges, layering) or for building up (hard edges and heaping).
A. for Atmospheric Pressure Change — imagine the isobars across the land from the forecast.
Sometimes you can see a lowering atmospheric pressure when marsh gas starts to bubble in cold weather i.e. not due to warming.
T. for Temperature — of the air-mass
H. for Humidity — the absolute one (measure the dew point — will it frost?). For the relative humidity try huffing to produce a fog, or onto metal.
Does the air mass humidity & temperature, speed & turbulence let you know which direction the wind must be from?
E. for Expectations — i.e. the weather forecast — test it — is it coming true?
R. for Rain — Will it? R.ight? Are you **R.eady** to move? Grab your R.aincoat and let's go… Keep looking until it is time to S.T.O.P. for a rest…

Oriented? No?
Rule one: Stop! getting more lost.
Rule two: Start! getting unlost. Start navigating!
Rule three: Stay, or Steer a Straight course.
Rule four: Don't do it again!

Position/**P**lacement/**P**rogress—has it changed?
Have you arrived somewhere?
Is it a named feature? A campsite? A junction?

Have you changed view?
Have you changed catchment?
Interpret the Why of your stop...



Trend And **T**errain—Has it changed?
Time & Tired—Does that explain your stop?

Stop -Signal: Why have you stopped?

REST and R.E.O.R.I.E.N.T yourself

Take 5; a 5 minute rest; REST is a mnemonic of 5's.
RE-RELATE; **RE-ORIENT; RE-member**; **RE-lax;** (= the 4 new RE-'s before you) **RE-start**. = 5 RE's

RE-RELATE to the skyline.
RE-RE for Re-Read the map,
L for Re-Late the Map to the Landscape
A for Astronomy—relate the Sky to the Skyline
T for Trends—imagine the Trend of invisible landscapes, in relation to the Sun, and relate your current trend to a point on the skyline
E for Each direction clue Re-lated to Each other direction clue, especially to the landscape/skyline shapes.
RE.O.RI.ENT — **RE** for Re-Orient the Map to the landscape,
— **O.** for **O**ops! Don't make logical blunders; Have questions on your mind; notice; speak up; integrate; connect; interpret.
Observe the **Overall** trends and bends.
— **R.I.** for **R**e-Visualise the **I**nvisible (Next checklist; and see Section 1 Astronomical Overview; Include the clock-sense mnemonic here)
Re-late yourself to the Big Picture
— **E.N.T.** for an **E**nvironmental **N**otice **T**ime — Re-late yourself to Nature — coming up.

R.I. For Revisualise the Invisible (and then Relate It to the skyline!)

Work down from the Biggest Picture. Work most on the ones you can't yet visualise.

Astronomy — Visualise the paths of Sun/Pot/Moon/Stars; Point to the South Pole Star; North Pole Star; the **Clock-sense** of stars around each Pole
— The star opposite the Sun during the Day & during the night; the Southern Cross during the day; the Ecliptic; the Milky Way
— Earth rotation; Horizon rotation; horizon trails; clock-sense of Horizon rotation; **clock-sense** of low stars' movement around horizon
— the Moon-Sun, and Ecliptic line; The Moon phase explaining the present tidal force. See the overview at the end of section 1.

Global — Latitude; Polar distances; Equators; Earth Poles; Seasonal Sun height; Shadow South — visualise the aurorae; Antarctica;
— North Magnetic Pole in Canada, as a 'South-seeking' Pole; Aurorae; Unequal Tidal bulges. "Go Overseas" p.25e.
— Tropical countries — corresponding to sunrise, noon, noon height, sunset, the country under the Sun now, the time zones
— Light & Dark halves — Sunrise-/sunset-circle countries; Half the arc-distance; How the horizon is shifting due to your movement.

Continental — Weather map isobars—visualise them across the continent — the one in front of your eyes, and on a continental aerial photo.
— Latitudinal wind system and pressure system helices.
— North Coast; N-S-E-W townships; NW-NE-SW-SE features. "Walk across the Continent" p.29e. "Compass-needle Continent" p.9e.

Local — Catchments; Divides; Mouths; Mounts; Radio Transmitters; Night Lights
— Nearby landmarks & places & highways; Home; Car
— Perimeter features; Escape targets & Routes — Bird's-eye layout of your route.



0 The standard viewpoint is "seen from above"; ◦ Clockwise is to your right; Compass Bearings Circle Clockwise;
1 Wrong Way Go Back! **Anti clockwise is ENWiSE** ◦ ◦ **SWiNES** That's how the Sun moves in the northern hemisphere
2 Unscrewing is an anticlockwise motion (on a right-hand helix) ◦ ◦ Screwing in is a 'right-hand' motion (for a right-hand screw)
3 24 hour clockfaces have only 15**°** per hour, like the Sun ◦ ◦ one hour = **30° clockwise**, on the 12 hr clock face method
4 High pressure systems circle **anti**clockwise in the SH ◦ ◦ **'Low' winds** come clockwise, in the SH.
5 Things on the **Left** have a **Lesser Bearing** ◦ ◦Things on the **Right** have a **Bigger Bearing**
6 All the solids rotate **anti-clockwise,** seen from the **N.** ◦ ◦ **Low stars** all around the horizon follow the Sun-sense
The ground under your feet shifts anti-clockwise in NH ◦ ◦ The ground under your feet turns clockwise (SH)
7a&b So the ho**RI**zon **N**ever **H**eads **RI**ght in the **NH** ◦ ◦ The ho**RI**zon **SH**ifts **RI**ght in the **SH**
8 Wind-shift due to ground friction opposes the Sun-sense ◦ ◦ Coriolis forces follow the Sun sense
9 **North lies between the SH Sun and the hour hand** ◦ ◦ The NH Sun is between the hour-hand & South
(actual noon points to Sun; clockface tilted parallel to Equator) (noon-time to Sun; axis to Polaris)
10 The SH Sun seems to move anticlockwise ◦ ◦ The Moon goes backwards, night by night (clockwise, in SH)
11 Nose Nav'n turns everything away **NOTLEast** Nth on the left=E ◦ ◦ **NORWest** — Needle-North on the right = heading West
12 **Shadows** Follow the Sun-Sense. + You can't cross a stream twice in the same flow-sense

---

E.N.T. for Environmental Notice Time —Orient yourself to Nature

Take **a top-down approach**...

Geology; geo-trends; geo-morphs i.e. landforms; geo-Norths
Dividing ridges; dominant peak; upstream catchment size; wind shadow; rain shadow
Season; climate type; prevailing wind; average rainfall
Rocks; bedrock; outcrops; parent rocks e.g. upstream
Soil types; nutrient availability
Soil Drainage — good or poor; Water Sources; groundwater? salinity
Aspect i.e. which direction does the slope face, in relation to high noon?
Living stresses? — salt, minerals, wind, exposure, frost, heat, low humidity, fire, flood, wet roots, pests, diseases, competition, grazing, trampling, disturbance, rock instability.
Vegetation type; the overall density of green, and of cellulose, and the height; dominant species; associations of plant types; diversity; individual species; individual plants. Pollinators available; seed dispersal mechanisms operating.
Mammals; Birds; Reptiles; Insects. Drinking water availability, cover for animals, hunting pressure
The 'Natural Norths' — Gully North; rock North; Bush North; insect North; Dew North; snow North; ripple North; prevailing wind North

---

RE-MEMBER to Note down the Names in the Notebook

Remember the **Way**, and the **Sequence**.
Remember to take a Notebook. Make a neat permanent copy of your notes i.e. in ink, maybe sometime later on, in your master track notebook.
Be Bit-wise!
Name the subsections, junctions & links. Name the peculiarities. In the name, try to include…

The Why, When & Where of your stop.	Link & Sequence information — time, distance, context
Lie of the Land	Words to indicate the direction trend, & curves — left or right
Visual words — colour, shape, alignments, curves	Descriptive words. Collect the details. Enlist the others to describe and name it.

Give yourself something to remember — create an acrostic; craft a creative name; sit down and write up your track notes
Update any acrostic alliteration. And the count e.g. of the creek crossings. Do something numerical. Do something alphabetical.
Be vivid, clever, memorable. Do something Shapely or Geometrical there Do something Memorable there. Do something there.
Draw the shapes, outlines & skylines. Draw the directions of other landmarks from any high viewpoint. Take reference photographs.

Remember most of all to do it all — don't just recite the reminders to do it all!
Mnemonics of Fives: Remember the Way; the Sequence; Make Notes; Invent Names; Draw What You Need to.

Re-lax, and Play — Navigation Games and Activities (5 pairs to recall)

Walk & Talk — a night walk — a fog walk — a walk off the track — climb a hill with a small scale map & binoculars & compass.
"Track My Trail" ("If you want lunch, you'll have to find me — give me a quarter of an hour, then track me down").
Keep a compass course, blind — keep a straight course, blind — on a slope? "Let's all make an acrostic to remember this track by".
Try Orienteering — Try making a map of a maze of trails — then a string map — a strip map — or a sine/cosine tally map.
Look & Learn — "Go to the front of the line if you spot a track marker which the others have missed" In a windy place look for wind clues, etc.
Take it in turns to name a navigational or orientation clue which is visible, until you have to drop out.
"I notice… (fill in the blank). Your turn. What extra can you add (to the description, or to the clues)?"
Guess & Test — Each of you estimate the time of arrival; the direction to the car; the distance to a landmark — then check the map.
Guess the time from the Sun, Moon, Southern Cross, or other stars, then check your watch. Use your compass to check your guesstimation of North from the bush, gullies, rocks, a star-trail, a star-set etc. Predict the tide, or the time & direction of moonrise — then sit down and wait for it. Predict a star-set position. Find your 'shortest shadow' angle today & use it tomorrow.
Make & Use — an odometer from a wheel, a pedometer, a sundial/declination compass, a portable sundial, a string rangefinder, a slope-meter.
Measure — Try some star navigation observations — Rise & set bisection; Use a plumb-line; a bush quadrant; a bush sextant.
Test how accurately you can each use a compass. Test each compass against the others.
& Memorise — yesterday's acrostic. Remember all the mnemonics! Can you add to any of my checklists? Have a star identification evening.

Moon-Phase & Tide-Time Dial

This is a handy tide-predictor, based on the assumption that tides will follow the moon. It shows you where the moon will be, at high tide. It also tells you what the moon is doing if you know the date but haven't seen the moon for a while. The deluxe version can predict tides and phases years ahead of time. It consists of a series of dials rotating on a single pin.

◇ The idea is that many of these concentric cardboard/plastic dials rotate together once properly adjusted, and as quickly as the Moon orbits the Earth. They show the Moon Phase, the Sun, the Earth and the resulting astronomical tide-producing forces.

Each disk is loosely fixed to a neighbour with friction (e.g. a smear of dried silicone glue) or a clip or tape or a pin, to allow adjustment.

Set it up by observation, or by tide-table predictions. Add notes, as you accumulate information about locations, tidal range, etc.
It can be especially useful for travellers, e.g. when fishing an unknown coast.
If the dials are correct for any one tide (spring-tide is best), they should be correct for all the tides thereafter *
* give or take a couple of hours for the smaller effect of the position of the Sun.
The effect is 43% of that of the Moon, and can be estimated with practice—change the hour reading to toward the Sun, or the anti-Sun, a little, if the Moon is near the Sun-anti-Sun line (no more than 45° from). Local shallow water resonance effects will also alter the actual effect of the Sun. When in doubt, around neaps, try averaging the tide-time for one or two days ahead and 1 or 2 days after.
The theory is that slosh resonance, or the Moon alone, or the Sun alone, might predict the difficult tides better.

◦ The hanger (outline not fully shown) is hung from the wall and also folds down behind to receive the pin on which the dials rotate.
It doubles as an indicator window, and should mark five consecutive high tides (ignoring a.m./p.m.).
◦ The clockface is 24-hours i.e. 15° per hour clockwise, (markings not fully shown). Think "a.m./p.m." for the two high tides per day, no matter what the reading says.
Each new location visited may need the clockface to be twisted slightly to allow for local tide delays. Keep a note of such settings.
Daylight saving requires a +/– 1hr change — to relocate the Sun forward in summer, back to normal in winter.



◦ Friction-fix the Moon-window dial (white with grey window) to the hanger, so that it maintains its position. It covers over all the other Moon phases.
◦ The Moon-phase diagrams (29 of them) underneath that, on a separate dial of the same diameter, should look right for the Southern Hemisphere—i.e. the Sun rising in the East, illuminating the Moon; all the phases parallel. Make the Moon-shape highly visible from a distance. Attach the Sun to the No-Moon phase, Day 0, via a transparent link; then set the Sun to the Clockface, to indicate true noon—when the Sun is exactly North.
◦ The optional tide-type ring (showing "neaps"), set to the Moon-phases, allows you to adjust the delay after new/full Moon, before spring tides.
If you also indicate which high tide is dominant—the one nearest the Moon or the one farthest—then that will need adjustment when the Sun crosses the Equator. I suggest that you set the top tide for the tide when the Moon is visible, to give you a visual feel for the tide producing forces.

◦ The date-dial is 29.5(30526805) days around—the complete lunar month—and marked clockwise from 1 to 32 (only one date is shown in the diagram). **Dial up the date, by rotating the Sun**. (For a 12-hour clockface, you would need to double the 12.19077473° per day). Since the next high tide will (if you are looking in the daytime) be on average that afternoon, I suggest you think of the date number as "the middle of the 23rd"—to avoid adjusting the date hand minutely for how far through the day the next tide will be.

◦ The month window is attached to the date dial, at Day 1 of the month, if you include a month setter.
◦ The optional but useful month-setter dial (markings not all shown) starts at March 1, to avoid leap-year adjustments; It makes March 32 = April 1, April 31 = May 1, and so on—spanning approximately 11 days for the year. Restart every March 1, and reset it every month.
Calculate the monthly positions by the day number since March 1, avoiding an off-by-one error (17.9°;23.6;41.6;47.3;65.2;83.1;88.8;106.7;112.5;130.4;148.3). Set the month name to the first day of the date dial.
You can also calculate and indicate a one-year increment, 129°.6327779, a leap year, 141°.82355, and a four-year increment, 170°.7218865. To make an adjustment, make the old date indicated by one mark on the month dial, now line up with the increment mark selected, so as to indicate a date in a new month/year/leap year cycle.

◦ An optional Earth ring in the very centre, can show the entire Southern Hemisphere map (not illustrated, or NH on the reverse side), and be set to the right longitude. It is fixed to the hanger, and to the tide-bulge ring...
◦ A second ring just behind the earth can indicate two tidal bulges, one pointing upwards (or otherwise if you want to indicate the local tidal delay compared to the actual ocean bulge).

Mock it up in paper, until you understand the functioning.
Glue those paper discs onto cardboard to trial the thing for a while.
After deciding on improvements, make it neatly, to last for decades.
E.g. Try getting the computer to print the dial markings onto acetate, and glue that to sheets of stiff plastic.

You can experiment with different dial orders, e.g. the date-dial on the outside of the phase-dial.

You can make room for comments,
e.g. by expanding the dial area showing, to say when the moon rises and sets; e.g. "light from midnight onwards"—beneath each Moon-phase diagram
e.g. when and where the Sun rises and sets; Mark three horizontal lines in the background for Summer, Equinoxes and Winter.
I.e. mark them on the backfold of the hanger piece, or on the wall. Try to match midwinter sunrise time to where the "winter horizon" cuts the clockface, which will also suggest the approximate direction of sunrise.
e.g. when and where the first, second and third quarters set in each season; Full Moon opposite the Sun, i.e. 6 months different; Half Moon Waxing is one season ahead of the Sun; Half Moon Waning is one season behind the Sun (as far as which horizon line to use).

You will discover that an invisible connection needs to be made between the outer top window and the inner window and dials, so that they do not rotate with the other dials. One way to do this is to push the pin through a piece of rubber eraser, and glue that rubber to the dial. Another method is to have a square pin, and key the inner dials to it, while using round holes for the rotating dials. A third and simpler method is to have a transparent link from the centre, over the top of the other dials. You do not want the hanger to obscure any diagrams or dials which need to be visible.

The Time and Date dials are the indispensable ones. Instead of dialing up the date, you can use a normal clockface (12md always on top) and an hourhand to point out the next tide; you point the pointer at the date. On a 24hour clock-face it can be made like a + sign, to point out all 4 tides that day.

Here is the simpler alternative version, showing an 11:30 high tide on the 19th…



Divide the Star Globe into 8 Octants—and Learn the Stars in Each

The three dividing great circles are the Equator, the Ecliptic, and the Milky Way Galactic Plane.
A star may be North or South of each line, or on one or more of them. The lines on the backside of the globe are shown dashed.
The labels refer to the three lines in the order given. Six of the octants show in the front view with the two in parentheses on the back.
Verify each label before you start. E.g. NSN = North of the Equator, South of the Ecliptic, North of the Milky Way.
Compare with a good star chart e.g. out of a large atlas, as this is only a memory aid.

The Milky Way Crosses the Equator
at the centre of
Procyon-Sirius-Betelgeuse

NNS—The Great Square, etc.

Summer (Northern) **S**olstice
Elnath to Gamma Geminorum

NSS
Aldebaran
Betelgeuse
Bellatrix
Menkar

SSS
Pot
Big Dog
Canopus
Diamond Cross
False Cross
Acamar
Achernar (central)
Magellanic Clouds
South Galactic Pole
South Pole Star
Diphda
Ankaa
Fomalhaut
The Crane
Peacock
The Archer
Scorpion's Tail
Atria



NSN
Procyon
Gamma Geminorum

SSN
The Centaur
Antares
Spica
Corvus
Suhail
Alphard

between SSS & SSN
Southern Cross
Southern Pointers

The Southern Figure of Eight—Two Star-Circles—joined by the backbone of Canopus—Achernar—Fomalhaut, a straight line
(not to scale; consult a star chart to verify each star, then find them in the sky)

Fomalhaut
Achernar
Canopus
Sirius |
Orion's belt | these 3 are also straight
Aldebaran |
Pleiades
Aries
Great Square

Milky Way
Cn=Pointers (alpha and beta Centauris)
Southern Cross
Diamond Cross
False Cross



Canopus
Achernar (find Acamar on the way)
Fomalhaut (find Ankaa on the way)
Great Square (find Diphda)
Aries, the Ram
Pleiades, The Seven Sisters
Aldebaran, in the Bull
The Pot, Orion's belt
Sirius, in the Big Dog

Around the South Pole Star
Canopus (find Acamar next)
Achernar (find Ankaa next) *Ach.-Fom.-Pck*
Fomalhaut *form a triangle*
Grus, the Crane, with Alna'ir *to find AlNair*
Peacock then Atria (find Scorpio) *& Ankaa*
Centaur, the two Pointers (find Arcturus)
(find Spica)
Southern Cross (find Corvus, the Crow)
(find Leo)
Diamond Cross, False Cross, Canopus

Visible in its entirety in October plus or minus a few months.

Divide the Star Globe into 8 Octants—and Learn the Stars in Each

The smaller groups, and the crossover points, are worth learning, because they show you the three lines best.

NNN
Alkaid (central)
Capella
Twins
North Galactic Pole
Big Dipper
Little Dipper
Polaris
Arcturus
Alphecca
Rasalhague
Draco
Vega
Deneb
Most of Leo
(Regulus adjoins NSN)

Summer **S**olstice
Between Aldebaran & Pollux

Autumnal **E**quinox
Between Spica
and Regulus

NNS
Altair
Enif
Great Square
Mirach
Almach
Algol, Mirfak
Aries
Pleiades
Elnath
(Caph, Schedar, Ruchbah)

Winter **S**olstice
Nunki to Sabik

SNN
Zubenelshemali
Sabik
(Zubenelgenubi adjoins SSN)



The Milky Way Crosses the Equator
at the extension of
Beta-Delta Aquila (see p.15c)

Spring **E**quinox
between
Diphda & Markab

SNS
Beta Aquarius

The Zodiac i.e. the constellations along the ecliptic. In order of appearance. Not all of them are bright or obvious in shape to look at.

Mnemonic:	Are	Tall	Twins	Cancerous	Leo?	Virginal	Liberated	Scorpions	Shoot	Capricious	Aquarium	Fishes.
i.e.:	Aries,	Taurus,	Gemini,	Cancer,	Lion,	Virgo,	Libra,	Scorpio,	Sagittarius,	Capricornus,	Aquarius,	Pisces
	Ram	Bull		Crab			Scales		Archer	Goat	Water-Carrier	

Morse Code & Rhythm Mnemonics

Dit/Dah/Pause is an extremely flexible system. Adapt it to torchlight, sounds, sewing stitches, body movements… A lot of fun for all the family.
if dit = one time unit; then Dah = three dits long; the di-Dah separator = one time unit; letter separator = three units long; word-separator = 6

	Say…		**Write…**	**Signal…**	Special Meanings (only for reference)
A	an A		. _	di Dah	
B	B bi-bi-bips		_ . . .	Dah di di dit	Fog Horn: I am under tow
C	C is Sea-sick		_ . _ .	Dah di Dah dit	Between ships manoeuvring: I a**c**knowledge your signal
	(Capital letters for a Dah syllable; lower case for a dit)				i.e. You may overtake on the side you indicated
D	Dee did it		_ . .	Dah di dit	Fog Horn: restricted manoeuvrability; deep draught; sailing; etc.
E	egg		.	Dit	I am altering my course to... **Starboard**
F	f’ f’ Forfeit	f’ f’ Fore foot	. . _ .	di di Dah dit	
G	Gee Gee git	Go Go get	_ _ .	Dah Dah dit	I intend to overtake you, to Starboard
H	h’-h’-h’-hit		. . . .	di di di dit	I intend to turn completely around to… Fog Horn: Pilot vessel on duty
I	is it		. .	di dit	I am altering my course to... **Port**
J	a J Goes Jay		. _ _ _	di Dah Dah Dah	
K	K for Kay		_ . _	Dah di Dah	
L	an ELL leph’nt /in ELLement /inELLegant		. _ . .	di Dah di dit	(draw out the Ell sounds)
M	My My		_ _	Dah Dah	Fog Horn: “under power, not making way”
N	No en		_ .	Dah dit	
O	Oh Oh Oh		_ _ _	Dah Dah Dah	
P	a P Goes pip		. _ _ .	di Dah Dah dit	
Q	Q Forms a Queue		_ _ . _	Dah Dah di Dah	(to the tune of “Here Comes the Bride”—Queue up to get married!)
R	an R dits		. _ .	di Dah dit	
S	s-s-s	ess ess ess	. . .	di di dit	I am under Astern propulsion
T	Tea		_	Dah	Fog Horn: “under power, making way”
U	it is U		. . _	di di Dah	
V	v’ v’ v’ Vee		. . . _	di di di Dah	(to the tune of Beethoven’s V)
W	a White Wine	a World War	. _ _	di Dah Dah	
X	EX mimics P	All ex’s Hurt	_ . . _	Dah di di Dah	(drawl the EX, to lengthen it in the first, not in the second)
Y	Why is Y Y?		_ . _ _	Dah di Dah Dah	(say the ‘is’ quickly)
Z	Zee Goes zi-zit	Zees Go zi-zit	_ _ . .	Dah Dah di dit	I intend to overtake you, to Port
Ü	it is U too	(this pairs to Zed)	. . _ _	di di Dah Dah	(U umlaut or U diaresis. Invent a meaning for it.)

Hint: For Learning, repeat each letter thrice.

By the time the other person recognises the first, the second has finished and he is waiting to check it out against the third.

0	No No No No No		_ _ _ _ _	
1	it Carts Four More Dahs		. _ _ _ _	
2	it is Two Two Two		. . _ _ _	
3	di di di Makes Three		. . . _ _	
4	di di di di Four	pitter patter 4 (your puppy’s feet)	. . . . _	
5	fit ‘em in a mit	(your five fingers, that is)	. . . . .	
6	Five si– si– si– six		_	
7	Five Seeks seven dits	(=567dits drawled on the 6)	_ _ . . .	
8	8 8 8 bi bits	(8 binary bits in a byte)	_ _ _ . .	
9	9 9 9 9 nips		_ _ _ _ .	
	Long dash	Daaaaaaaash	_______	e.g. (Fog Horn or car horn) before you enter a blind bend!
	Error	it isn’t a bit of it	. . . .	Between yachts: “I do not understand/agree with your intention/action”
:	Colon	Now Here Comes in a list	_ _ _ . . .	

Learn the next ones in pairs i.e. swap dit for dah

. a STOP a STOP a STOP (i.e. don’t pronounce ‘stop’ as short) . _ . _ . _
; SEMi SEMi SEMi (i.e. drawl the first syllable) _ . _ . _ .

These 2 shapes are convex to the right

, Go Go comma Go Go Dah Dah di di Dah Dah _ _ . . _ _
? did he Dah Dah did he? did ’e Blah Blah did ’e . . _ _ . .

These 2 come in pairs normally

“” a Quote is a Speech bit di Dah di di Dah dit . _ . . _ .
() Here’s the Blah Blah bit Here There’s the Blah Blah bit There _ . _ _ . _

These 2 are in the middle of a word ..hyphen and apostrophe

- ’Aitch in the middle Daash (‘Hyphen’ starts with an ’aitch) _ . . . . _
’ it Saves All Those Hard bits di Dah Dah Dah Dah dit . _ _ _ _ .

/ Slaash t’ diVide it (Drawl the first vowel) Slaash is a Slaash bit There was the Whole bit _ . . _ .
Á an A Sharp an A You could use it for “Repeat”: re Peat Whole re Peat . _ _ . _
É it is E a-cut(e) . . _ . . cute is cut short (You could use it for “Bad Reception”: cannot Hear the bits)
Ñ Nya Nya ny’ Nya Nya _ _ . _ _ (with thumb to nose, fingers waving) “ny” sound (I use enya for “Do You reCeive Me”)

SOS a bit of ‘Save Our Souls’ isn’t it? (no letter breaks; repeat regularly) . . . _ _ _ . . . . . . _ _ _ . . . (Life & death only)
XXX Come quickly Come, Come quickly Come, Come quickly Come All ex’s Hurt All ex’s Hurt All ex’s Hurt (When you Need urgent help)

Signals procedures, developed by hard experience, short circuit a world of miscommunications — stick to them. I.e. learn them too.

I’m Looking For Talk; CQ CQ CQ; Calling Calling All Radios; Hear ye Hear ye All AuditOrs; Tune in Tune in Lend Me y’r Ears
From; D, E; De = French for ‘from’ Heard of it ; fr’m Dah-di-dit dit
Go Ahead; invitation for anyone to transmit; K Call in Now
Break In B, K Break in to it; Make a Break (“BK DE (identify yourself)” = “let me use this channel”)
Starts; Attention; Message Coming Start it Start it Now Start of My bit Now _ . _ . _
End of Paragraph; Pause; new thought; double dash Pause if it is New _ . . . _
Wait a Wait f’r a bit . _ . . . You could invent “Speed up All Your Work” to pair with it.
Over; invitation for your contact to transmit O ver Your Turn stop _ . _ _ . (to start a person-to-person contact: ###DE### Over)
End of Message in traffic; not end of contact; not clear of station the End of My bit; con Clude con Clude it . _ . _.
R; Roger; Received and Understood all of Message
End of Work; but still on air; clear of contact it is the End of Work (to the tune of… here we go Out to Play) . . . _ . _
Clear of all contacts; shutting down; Clear of Station; C, L Clear it Clear it, b’ Clear of it

Add your own signals for procedural or other matters. E.g. “Please repeat my message back to me for a check” “Adjust the beam left”

Ä an A an A . _ . _ an A ‘m Laut It pairs to C Invent a use for it like “i Don’t a-Gree” to be opposite to C, I Agree
Å an A an A too . _ . _ _ an A an Aang Strom
Xhi Khi Khi Khi Khi _ _ _ _ K-H-Like-H soft Kh sound (I use it for “to” i.e. T+O, after DE “from”) cf Ree Call All Souls
Ö Oh Oh Oh dit _ _ _ . Goe– Goe– Goethe It pairs to V You could use it to say Sorry

North American Morse is somewhat similar. There is also a Japanese version. Morse is no longer supported as International.

Semaphore Signalling Code & Mnemonics for it

Semaphore is a clockwise system, as viewed by the decoder, and it starts from below.
When the two hands can’t be seen, that is the neutral position, used for a… **Pause**
The black square represents the signaller’s body; the line(s) are his arm(s).
The numbers 1-9 and 0 are the same as A-I and J. The first 7 single-arm positions are shown…
You can tell the difference, because the signal “numbers coming” precedes a number, and a “pause” follows the end of the numbers.





One arm, pointing up, therefore is either D or 4,
Think of God as the 4th Dimension to your life, and remember ‘up’ as “**4D**”
Or if it sticks in your memory, think perversely, that “**Up is fo(u)r D.own**!?”
Learn the letters in symmetrical pairs.



Here is a “**B F**lat” mnemonic. One arm flat is either a B (-flat) or an F (-flat)
“2 be or not 2 B?” and a “**F Sixth** chord” might help you remember the numbers.



Wave the C to say “Replying”. Wave the E to signal “Error”
(cf Morse “C” for “Acknowledge”)
The *odd number* positions are diagonals.
1,3,5; 7… **One is an ACE** isn’t it? And Dia**g**onal has a **G** in it doesn’t it?
a G7 chord to follow the F **F**lat minor **6**
ABC = 123 is easy enough to see, and **5E follows 4D** makes the E position easy



2 Hands…



“Roger” is simply an indispensable signal to learn… it means “Yes, I understand, OK, Received”
For Learning: Acknowledge every letter understood, with a Roger

2 Hands Straight:
Think **“Long**, then **Left down = Slash down** or **L**eft **up = L**ift **up”** (referring to **their** Left arm)…



2 hands in a catching formation, above the head…
Shout **“Catch iT…”** and think **“..Tee—numbers coming”**



2 Hands in a slip-catching formation, to one side…
Shout: **“HOWZ”**at!



You are meant to wave black and white flags around,
but usually you make do with opening your palms.
Only be careful to position yourself against a good uniform background.

’aitch rhymes with eight



2 hands at a right-angle…
“Ya gotta have the **Right** **P**y**J**amas” (“PJ”s)
J, the tenth letter, is used for Zero   ABCDE FGHIJ

PJ is not in alphabetical order, because in the Semaphore Alphabet J comes after #



2 hands at a right angle, Vee-shaped, up or down…
Can you see the **shapes** of the **lower case letters n and u** in them?

To attract attention wave U, to say “Message Coming”



2 hands, like a Roman Numeral Five on its side…
I and **X** are **Roman Numerals too.** The I is used for numeral **9 (IX)** in semaphore
The X looks like **the right-half of the X**

So it sort of goes, left to right “nine, ten”

2 hands flapping and banking. I.e. a shallow Vee formation…
“MY Queue**S”** is the clockwise mnemonic
But YQ is not in alphabetic order (like PJ, the only two cases).

You can use Q for “Query” - What did you say/mean?

From the sky, down to earth come… **“K**ilo**V**olts” (or **“K**iller**V**olts”)

You can follow the clockwise logic of Semaphore if you leave out the JVWXZ till last
Pause, ABCDEFG, HIKLMN, OPQRS, TUY/, #JV, WX, Z

Make each in turn to see the progression.



Appendix: More symbols for map-making Useful for mud-maps, or for track notes.

The first symbol in a strip map column should show the *reason* for the stop. This saves a lot of words and is instant to read.



In turn these are:

A Context Entry; Surroundings; Overall Perspective. E.g. catchment and drainage. It's a chance for a general note.
A Stop. Expect a reason like 'Lunch'.
A Location. Expect a description.
Crossing. This might be a crossing of a ridge, river, road, canal, boundary. Expect notes on what is to left and right.
Leg. The first of the 2 main reasons for an entry: either a new subsection (leg) or the location *between* two sections in its own right (next symbols).
Overlap-section between legs. This is a memory aid, to sequence subsections, to remind you how individual sections join to each other.
Change of legs; new subsection; = notes on *the changeover*, rather than on the next section.
Junction (Y for Y junction, but used also for other junctions). This might be a 'natural' junction between ridges or creeks; or an intersection of paths.
Viewpoint; Change of view; First glimpse; Last glimpse (I for 'Eye')
Corner
Bend
Curved section beginning; Arrow shows clock-sense. This one is a Right-hand bend.
Curved section ending; Arrow should show same clock-sense as previous one. This one ends a left-hand bend.
Change from left-curve to right-curve
Break of slope
Feature
Special feature
Ridge; Crest
Saddle;
Valley; creek-bed; Gutter
Tent; Campsite
Peak
Fix
Cliff
Creek
New grid square







Boundary walks: fenceline; railwayline; road; path; circumnavigation; shoreline
Use symbols which work for you, e.g. Rise or Set direction. Add your own, e.g. Hut

The second symbol ought to show the main direction clue, followed by subsidiary ones as a third symbol



Trending half left from that landmark (write the name of the landmark next to the arrowhead). Useful when following a windy path.
Maintaining half right of downwind;
Walking the crest down ridge — Progress is assumed to be 'Up'wards on the page.
Leg.
Trend direction (for when the terrain is up and down, left and right) ('T' for Trend).
Named landmark; General purpose arrowhead; add the name and the bearing
Peak
Anti-peak direction (e.g. as mentally marked on the skyline opposite the peak)
Up-Slope.
One arrow for 'below average'; Two arrows for 'average'; three arrows for 'above average' — low; medium; high. Use this for other things too.
Compass needle North, modelled after the symbol for North
Up-Sun
Shadow; Down-Sun
Wind source; Upwind. Use the 1-2-3 code for strength. This one is 'above average'.
Down-stream river flow
Up-stream (to a peak) (useful when 'downstream' is behind you)
Moon direction
Up-Ridge; The direction of the highest skyline through the vegetation, if that is all you can see.
Down-valley. The direction of the lowest skyline when that is all you can see.
General Drainage trend (down the valley to the river mouth)
Up-Weather; Low cloud source direction; Cloud Source (when only one set of clouds is visible)
Down-clouds
Alto Clouds source direction (make the circles fluffier than I can show)
Cirro-clouds source direction
Glow at night
Radio-null (from the symbol for an antenna)
Trend of some feature like the coast — write in the details.

1,2,3 for size and importance of junctions…



The notebook might be set out as follows: The first line across a narrow notebook is in informal columns; the second is for written notes.

Time ;	**Reason** ;	**Trend** ;	**Directions** ;	**Times** ;	**Distances** ;	**Grid**
Fill in a **number**	Use the top **symbols**	Use the main clue	make a rose of others	elapsed time	total elapsed	e.g. A5
if you don't				leg time	last leg length	
have a watch	Start with an 'Overall'			lost time	lost distance	
				total time out	total diversions	
Sequence is a				net walking time	net progress	
primary need						

(Use abbreviations, e.g. NWT, or dedicated columns)
(Do your calculations here at leisure)

Now write *across* the next line(s) the **name; mnemonic; description; comments**
The description of a cross-country leg could include the side or flank, hand, clock-sense, break, steepness, difficulty, curviness, hilliness, perversity, terrain, contours, topography, view, what you can't see, skyline, traffic intensity, track-markers, their age, rock type, soil type, vegetation, biology, colours, peculiarities, reference to another page of the notebook to a diagram.
The more you include in the symbols, the less you need to say, and the easier it is to read later.

Appendix: A List of Star Coordinates.

100 brightest stars
Declination is equivalent to Latitude. –nn = South; +nn = North
Siderial Hour-Angle is equivalent to Longitude West of Zero.

Common Name (s)		Dec.	S.H.A.	Constellation
Miaplacidus		-69.72	221.70	b Carinae
Atria		-69.03	107.83	a Trianguli Australis
Acrux		-63.10	173.35	a Crucis
Rigil Kentaurus	/Toliman	-60.84	140.10	a Centauri
Hadar	/Agena	-60.37	149.04	b Centauri
Mimosa		-59.69	168.07	b Crucis
Avior		-59.51	234.37	e Carinae
Aspidiske	/Tureis	-59.28	220.72	i Carinae
Achernar		-57.24	335.56	a Eridani
Gacrux		-57.11	172.21	g Crucis
Peacock		-56.74	053.60	a Pavonis
k Velorum		-55.01	219.46	k Velorum
d Velorum		-54.70	228.82	d Velorum
e Centauri		-53.47	155.02	e Centauri
Canopus	2nd brightest	-52.70	264.01	a Carinae
Muhlifain		-48.97	169.62	g Centauri
Regor		-47.34	237.61	g Velorum
Alna'ir		-46.96	027.95	a Gruis
b Gruis		-46.88	019.34	b Gruis
Suhail	/Al Suhail	-43.43	223.01	l Velorum
Akrab/ Sargas	/Rastaban Sc.	-43.00	095.67	theta Scorpii
Ankaa		-42.31	353.43	a Phoenicis
eta Centauri		-42.16	141.12	eta Centauri
Naos		-40.00	239.10	z Puppis
k Scorpii	(not Akrab)	-39.03	094.38	k Puppis
Shaula		-37.10	096.60	l Scorpii
pi Puppis		-37.10	250.71	pi Puppis
Menkent	(not Menkar)	-36.37	148.33	th Centauri
Kaus Australis		-34.38	083.96	e Sagittarii
e Scorpii		-34.29	107.46	e Scorpii
Ascella /Nushaba		-29.88	074.36	z Sagittarii
Fomalhaut		-29.62	015.59	a Piscis Austrinis
Aludra		-29.30	248.97	eta Canis Majoris
Adhara		-28.97	255.34	e canis Majoris
Antares		-26.43	112.65	a Scorpii
Wezen		-26.39	252.90	d Canis Majoris
Nunki		-26.30	076.18	s Sagitarii
Dschubba		-22.62	119.91	d Scorpii
Diphda	/Deneb Kaitos	-17.99	349.11	b Ceti
Mirzam	/Marzim	-17.96	264.33	b Canis Majoris
Arneb	/Arnebo	-17.82	276.82	a Leporis
Sirius	/Dog (brightest)	-16.72	258.72	a Canis Majoris
Sabik		-15.72	102.41	eta Ophiuci
Spica		-11.16	158.70	a Virginis
zeta Ophiuci		-10.57	110.72	zeta Ophiuci
Saiph		-09.67	273.06	k Orionis
Zubenelschemali		-09.38	130.75	b Librae
Alphard		-08.66	218.10	a Hydrae
Rigel	not Rigil K.	-08.20	281.37	b Orionis
Alnitak	S. belt	-01.95	274.80	z1 Orionis
Alnilam	Mid belt	-01.20	275.94	e Orionis
Mintaka	N. belt	-00.30	277.00	d Orionis

Common Name (s)		Dec.	S.H.A.	Constellation
Polaris	N. Pole Star	+89.26	(322.06)	a Ursa Minoris
Kochab		+74.16	137.32	b Ursa Minoris
Alderamin		+62.59	040.35	a Cephei
Duhbe		+61.75	194.07	a Ursa Majoris
Navi	/Cih	+60.72	345.82	g Cassiopeiae
Ruchbah	/Ksora	+60.24	338.55	d Cassiopeiae
Caph		+59.15	357.70	b Cassiopeiae
Schedar	/Schedir	+56.54	349.87	a Cassiopeiae
Merak		+56.38	194.53	b Ursa Majoris
Alioth		+55.96	166.50	e Ursa Majoris
Mizar	(+Alcor nearby)	+54.93	159.01	z Ursa Majoris
Phecda		+53.69	181.54	g Ursa Majoris
Eltanin	/Etamin	+51.49	090.86	g Draconis
Mirfak		+49.86	308.92	a Persei
Alkaid	/Benetnash	+49.31	153.12	eta Ursa Majoris
Capella		+46.00	280.83	a Aurigae
Deneb	(not Denebola)	+45.28	049.64	a Cygni
Menkalinan		+44.95	270.12	b Aurigae
Almak	/Alamac	+42.33	329.02	g Andromedae
Algol		+40.96	312.96	b Persei
Sadar	/Sadir /Sadr	+40.26	054.45	g Cygni
Vega		+38.78	080.76	a Lyrae
theta Auriga		+37.22	270.07	th Aurigae
Mirach		+35.62	342.57	b Andromedae
Aljanah		+33.97	048.45	e Cygni
Castor	N. twin	+31.89	246.34	a Geminorum
Alpheratz	/Sirrah	+29.09	357.90	a Andromedae
Elnath	/Nath	+28.61	278.43	b Tauri
Scheat	/Schert	+28.08	014.06	b Pegasi
Pollux	S. twin	+28.03	243.67	b Geminorum
Izar		+27.07	138.75	e Bootis
Alphecca	/Gemma	+26.71	126.33	a Coronae Borealis
Hamal		+23.46	328.20	a Arietis
Sheratan	/Sheratain	+20.81	331.33	b Arietis
Zozma	/Zosma	+20.52	191.47	d Leonis
Algeiba		+19.85	205.00	g1 Leonis
Arcturus		+19.18	146.08	a Bootis
Aldebaran	(not Alderamin)	+16.51	291.01	a Tauri
Alhena		+16.40	260.56	g Geminorum
Markab		+15.21	013.82	a Pegasi
Denebola		+14.57	182.73	b Leonis
Rasalhague		+12.56	096.27	a Ophiuci
Regulus		+11.97	207.90	a Leonis
Enif		+09.88	033.96	e Pegasi
Altair		+08.87	062.31	a Aquilae
Betelgeuse		+07.41	271.20	a Orionis
Bellatrix		+06.35	278.71	g Orionis
Procyon		+05.22	245.17	a Canis Minoris
Vernal Equinox, defined as fixed		00.00	000.00	'the first point of Aries'

Figures are from Epoch 2000.0.

Precession of the equinoxes:

Stars drift about 1° of position relative to the (0,0) reference star, in **72 years**, because it moves to the **WNW along the Ecliptic**. See p 33b
The third figure will therefore become off by one after 10-20 years. E.g. Mimosa used to be –59.59; Atria used to be 108.3W
One degree of latitude or declination = 60n.ml. =111km; so a maximum change in **0.1° over 18** years represents 11km, or about 0.6km per year, max.
(The actual change in Declination depends on its relationship to the Northern Spring Equinox point — see below.)
One degree of SHA = 60n.ml. at the Equator; half that at 60° Lat. ; **1° reduction in 80 years** is about 3 seconds later in timing per year, or 1.4 km max, at the Equator.



Ecliptic The first point of Aries moves along it at about 50 seconds of arc per year (5/6° in 60 Years)
Declination change of 1/3 minute of arc per year (20 secs of arc)
SHA change of 46 seconds of arc per year $20^2 + 46^2 = 50^2$

If you set your star watch by the actual visible stars each year, you eliminate E-W 'precession' component, and are left with only the drift *in declination*.
So it is of some worth to be able to predict how that rate of change in declination depends on SHA.
Obviously Stars to the North of Aries lose Northern dec, at the full rate. Stars to the South must *gain* Southern Dec.
Stars *opposite* Aries (SHA=180°) do the opposite. Stars exactly in between are *unaffected* (SHA=90° or 270°).
The rate for all cases follows **the cosine of the SHA**. E.g. stars at 60**°** SHA will have 50% of the full dec adjustment (of 1/3 n. ml. per year).
Take care with Polaris, since it is too close to the Pole.

Appendix: Drawing Great Circles



First, bisect a globe.
Two equal halves.

Put the halves back together.
Notice the ellipse.
The backside is dashed.

Draw it symmetrically around the centre.
Use *flat* ends to the ellipse.

Choose the clearest perspective
E.g. 1. Rising/ setting is 90° away, so put yourself in the centre, surrounded by a 90° circle. Z is used for your Zenith — overhead.
E.g. 2. Look at the Equator side-on to make it and the latitude circles straight.
E.g. 3. Centre on the pole, to show up the polar distance. P is used for the Pole.
E.g. 4. Curve away from the centre. If in doubt, draw the whole ellipse and discard the unwanted parts.
5. A Great-circle can be drawn as a straight line. X is used to mark the position of the Star/ Sun/ Moon/ Planet
6. Draw the 'Vertex' of the course as a tangent to the maximum latitude small-circle.
7. The vertex can be drawn side-on.



The PZX spherical triangle

8. Deliberately avoid straight lines to show up the curve of the triangles.
8a. ZX is the angular distance from you to the star, or the co-height.
8b. PX is the polar distance or co-declination to a point directly underneath the star.
8c. PZ is the polar distance or co-latitude of your position, 90° — lat.
8A. The angle ZPX, or 't', is a longitude difference — between the SHA of the star and your West longitude. A longitude difference is a time delay.
8B. The angle PZX is a horizontal direction relative to P, towards X. Technically called an 'azimuth'.
8C. The angle PXZ is similar but only meaningful if there were someone under the star, looking toward you.
9. A, B, C and a, b, c are used to label angles and sides of any spherical triangle; It's up to you to know which ones label what.
10. Draw a full 180° to show up the supplementary angles.
11. Draw the Equator cutting East and West of you, 90° away. Mark any right angles, and the complementary angles.



The PZX navigational triangle conforms to a handful of standard **fundamental spherical trigonometrical formulae**…

The Angle **Sum**: a+b and A+B are both greater than, or both smaller than, or both equal to, 180°
The **Sine** Rule: sina/sin A = sin b/sin B = sin c/sin C = constant. Ambiguity (about obtuse angles) can be resolved by the angle sum rule.
The **Polar** Triangle Rule: abcABC can all be swapped for the supplement of the opposite members.
E.g. 'a' becomes '180°—A'; 'B' becomes '180°—b', and the resulting formula is still valid. E.g. the sine rule simply inverts.
The **Cosine** Rule: cos a = cos b cos c + sin b sin c cos A
The Polar Cosine Rule: cos A = — cos B cos C + sin B sin C cos c
The **Four Parts** (in a row) Rule: e.g. AbCa or aBcA in the triangle aBcAbC or aCbAcB. You can find the 4th (outer) part from the first 3.
cos (**inner** side) **cos** (**inner** angle) = s**in** (**in**ner side) c**ot** (**ot**her **side**) — **sin** (**in**ner angle) c**ot** (**ou**t**e**r **angle**)
If you want an inner part, use the sine rule and angle sum rule to find the 5th part, then go to the half-angle rules.
The **Five Parts** Rule: sin 1 cos 2 = sin 3 cos 5 + sin 5 cos 3 **cos** 4, where 4 is a side. It gives you any but part number 3, from the other 4.
The Polar Five Parts Rule: sin 1 cos 2 = **—** sin 3 cos 5 + sin 5 cos 3 cos 4, where 4 is an angle
The **Half-Side** Rule, to find the *middle* of 5 parts, when the middle part is a side: halve each side and angle first:
tan (half side) = tan (half sum) cos (half sum) / cos (half difference) ; tan refers to sides, sin and cos to angles
= tan (half difference) sin (half sum) / sin (half difference) but this introduces order-ambiguity because of the sines.
The **Half-angle** Rule to find the middle of 5 parts when it is an angle
cot (half angle) = tan (half sum) cos (half sum) / cos (half difference)
= tan (half difference) sin (half sum) / sin (half difference)

Make North and West positive, and East and South negative, and the formulae automatically work on PZX for angles up to 360°.

The formulae simplify where a side or an angle is 90°, since sin 90°=1 and cos 90°=0.
Napier's Rules…
The rules for **right-angled** triangles and **right-sided** triangles are simplified when the 5 other parts of the triangle laid out **in a pentagon**, and the 3 parts not adjacent to the right angle are changed to their **complement**.
In addition the part opposite a 90° *side* must have an extra **negative** sign.
E.g. if A is the right-*angle*, use (90°—a) as part 3, (90°—B) and (90°—C) for parts 2 and 4; if a is a 90° *side*, use A-90° for part 3.
Then… Sin of any one part = t**a**n t**a**n of **a**djacent parts or = c**o**s c**o**s of **o**pposite parts (in the pentagon of changed parts).
Ambiguity must still be resolved by special rules: Problems occur when there are 2 or more right-angles in the triangle.
'A' and 'a' (opposite parts in the triangle, with matching letter names) are both less than or both more than 90°. Likewise for Bb and Cc.
If one part and any part not opposite it (i.e. not A and a, as above) are on the *same* side of 90°, so are all the other mismatched pairs.
If one part and any part not opposite it (i.e. not A and a) are *not* on the same side of 90°, neither are any of the other mismatched pairs.
These refer to the triangle parts, not the altered pentagon parts.

Appendix: Calendars in the Sky — the first glimpse and last glimpse of stars

~ Firstly, What's wrong with **sunrise/sunset time**?

- To know what time of year it is, you could note the ordinary standard Sun time of sunrise/set at *that* place (e.g. from home).

—But this is insensitive (maximum shift is about 1 minute a day), useless around solstice, latitude & longitude dependent & requires a watch

~ You need to use apparent *star* time; no watches, to **locate the Sun's position on the Zodiac relative to the stars**.
— i.e. 'what stars are up' at midnight, or at twilight, or what stars are invisibly up at mid-day or sunrise or sunset.

- The Sun creeps Eastward about 1° per day along the Ecliptic (through the middle of the Zodiac belt).
- That quadruples the sensitivity to 4 minutes change a day, steady year-round.
  It is only affected by the Equation of Time, which is a minor variability, 1/4 min a day, max.
- The Sun will 'blot out' each Ecliptic star for about a month at a time.
  That's a rough way of finding the month: 'I can't find The Twins' (July).
- 'Nautical twilight' is when the Sun is 10° below the horizon (about 1 hour, in Tasmania), dark enough for the bright navigational stars to be visible while the horizon still shows clearly enough to be used with a sextant;
  So bright stars 10-15° away from the Sun begin to be visible. That means that a bright Ecliptic star might only be invisible for 3 weeks.
  [Civil twilight is 5° below, requiring lighting; and astronomical twilight is 15° below, dark enough to be called 'night', and to use a telescope]

E.g. 'What stars are up at midnight', uses the 'apparent star time' of the anti-Sun, as it were. You need to bisect sunrise and sunset, and be up then

- Find which star is N-S of you (the 'local apparent star time') at 'local apparent midnight' (= opposite noon — i.e. the anti-Sun stars).

But that is difficult — you need to know the apparent noon (which is longitude dependent), not the clock noon — and it still requires a watch.
So how can you do better?

- You could note **the clock-time of any particular star event**. E.g. follow 'Rigel over Capella' during Summer. E.g. Antares at 10° high.
  This is *simple, and accurate,* but it would only work for that location, no other, since longitude alters the clock-time of appearances.
- You could note **the clock-time *delay*** between any particular star-event and either sunrise or sunset. **This is a good method**, since it pinpoints sunrise or sunset more accurately than saying 'At twilight, when the stars come out, or when they fade out'.
  For best results, choose which star-event directions to use, as explained below, so that people at all latitudes see the same appearances.
    - This pinpoints the star-time—it tells you where the stars are—in relation to the apparent Sun-time (by tying it to sunrise or set).
    - For Rise/Set observations, you need a good horizontal horizon (or other fixed height-of-star) for star-rise/set to be latitude-independent, and location independent; but at home you simply need a repeatable point of view of a given horizon.

~ But to get back onto the main topic: The use of a watch can be eliminated by using twilight 'glimpses'...

- For Twilight observations, you need dependable eyesight; & a clear sky, with no Moon or light pollution, or haze, to be repeatable.

The idea of a 'glimpse' is that it is positively there or not. And it doesn't need a watch. There are 10 or so varieties...

- If you see a star *before dawn*, it's positively there, or if you can't see it *after dark*, it's not there.
    - Look to the East before dawn and you will see **a new star appearing** for the first time in the season — a first glimpse.
      You will then lose sight of it due to daylight. This is the standard star-calendar event.
    - Look to the West after sunset and a star will have **disappeared** for the rest of the season — a last sighting.
      You glimpse it briefly, before it moves into the sunset glow, and is lost to sight for weeks.
    - Examples: The last glimpse of Spica is just after the September Equinox; Regulus is first seen just ahead of the September Equinox;
      The Equinox is between the two, and both are on the Ecliptic, about 25° each side. That's 25 days for the Sun's movement.
      The first glimpse of Antares is around Christmas time, since it is about 20° ahead of the solstice;
      Aldebaran reappears around the winter solstice; The Twins disappear soon after it.
      The solstice is between these two, 25° away from each.

    You need to check the exact dates of appearance and disappearance because they vary with the exact latitude—this is a semi-local calendar.
- If *a star-pair* has tilted *out* of alignment by the time the stars come out, you simply *don't* see it occur;
  or if it doesn't align before dawn, you can't see it 'happen'.
    - Look pre-dawn for the first date on which you can glimpse **a star pair reach its proper alignment**, before dawn takes over.
    - Look post-sunset for the *last* date on which you can see a star pair attain its right alignment, after which it is lost for a month or so.
- Each day a Western star gets closer to the Western horizon from above. Each day a rising star gets earlier to the Eastern horizon, from below.
    - Look for the first glimpse of a star clearly **rising or setting** *pre-dawn*
    - Look for the last glimpse of a star clearly **rising or setting** *post-sunset*.

    If you see it setting, you know it; if you see it rise, you have seen it happen.
- Wait to see whether a star reaches a known fixed **height** (e.g. not too far above the horizon), to make observation easier.
    - Looking at a reflection of a star in smooth water or oil, will *double* its height 'above horizontal', if you want a method to work anywhere.
- Wait until a star coincides with a known fixed **direction** (e.g. 'over the tower'). This makes it location-specific, but may be useful.

These all have the effect of describing the height or tilt or direction of the horizon 'at twilight'.

- A star **overhead** at twilight will show up as a first/last glimpse. You look for it, but it may not 'happen'. This is latitude-specific.

~ You could now combine the 'glimpse' methods and 'crisp timing' to avoid the indistinctness of twilight (but this is more latitude dependent).
Look 'exactly 1 hour from sunset/rise' to crisp up the timing of the 'events'. Any exact time-span at least that long, would suffice.

~ To clinch the star-time, in a latitude-independent way, **use Great-Circle type directions** ('at right-angles to sunset/sunrise' 'a star near the Sun at twilight' 'opposite it') to ensure that people over a wide range of latitudes more or less agree in their observations.
The standard direction is not sunrise/sunset itself but 'where the Sun is *at twilight*' which is 1 hour to the left (SH); *the brightest part* of the horizon.

- identify star-pairs ***at right-angles to the Sun's* direction at twilight**.
- or examine the rise/set of **stars *near the Sun***, especially those ahead or behind it, in its rising and setting path.
- or look for stars rising, setting or simply being visible, ***opposite* the Sun** at twilight.
- You can use any other 'star direction', but it will only apply to that latitude. The best great-circle directions are between NW/SE & NE/SW.

~ But the sensitivity can be further improved, by **choosing *which* twilight** gives the most daily change…

- The nightly change (averaging 4 mins) is not the same amount through the year.
  It can be reduced to 3 or increased to 5 in a place like Tasmania, as the seasonal day-length varies by several hours.
  The change in sunrise or sunset time by up to a minute a day is overlaid onto the steady star progression.

Look at the time of day when the most rapid change is taking place, since you want the most accurate discrimination:

After mid-summer, look for 'first glimpses' in the pre-dawn ;

- Nights lengthen after the summer solstice — more stars rise in the East than set in the West as the night-time gradually dominates
  At dawn, the Sun lingers a little longer under the horizon allowing more stars to rise, in their creeping ahead of the Sun.
  But at sunset, the Sun goes down earlier, like the stars do, and you don't notice much change as to which stars are up.
- So when the nights lengthen, look **before dawn** and try to see any first glimpse this season.
  Luckily the pre-dawn in Summer/Autumn is mild, but it can be quite early. Use the clock-time delay method 'from sunset', not 'to sunrise'.

After mid-winter, look for 'last glimpses' post-sunset ;

- Conversely, after the winter solstice, the increasing day length dominates over the night sky — more stars set and fewer stars rise.
  You will lose sight of stars setting in the West, quite easily, as the Sun will linger before setting, because of the season,
  but find it hard to see a new star rising in the East for the first time that year, because the Sun pops up early.
- So when the days lengthen, to pinpoint the time of year, look **after sunset** for any last glimpse.
  That's not too late at night in Winter/Spring, and it should not be too cold. Or use the clock-time 'until sunrise', to maximise the daily gap.

The overall idea works in both hemispheres, but the optimal choices of when to look are tied to the seasons, not the date.
Use either method, when near to the solstice, or near the Tropics, or at any time you want to.

- Around mid-winter and mid-summer, you can happily use any of the 10 glimpses, or any of the clock-time methods.
- Near the Tropics, also, there is little differential advantage, compared with temperate latitudes, since day-length is fairly constant

~ Keep a special perpetual calendar (a 365 day chart with no days of the week specified) to note down your observations; with room for related seasonal changes, like bird migrations, frosts, plantings.
All this has little to do with navigation, directly, but gives you practice in *following the seasonal movements* of Sun and stars.

About the Author.

I have a big bushy beard from too much bushwalking and ocean sailing, but now that it has grown too grey, it is time to hang up my boots and write it all down.

My dad was a ’plane navigator during World War 2 and as a child I studied his manuals. Then at University I spent more time in studying naval navigational manuals and in bushwalking off track, finding my way over the snow or canoeing across lakes, than in studying for my exams. I used the library to learn spherical trigonometry, then, as soon as I finished Uni, set out across the trackless ocean. I soon found myself inventing techniques to plug the holes in my normal abilities. I returned home years later, not knowing what I was meant to do in life, but as I lay there on my old bed, I knew that if I was to be a navigator I would like to be one like Captain Cook. He experimented with new techniques, and with old — he described native sea-navigation expertise. How *did* they do it? Even now, no-one seemed to know. I immediately had a vision of one star above another, which kept me busy for years on great-circle navigation methods.

I had honed my skills trying to teach boaties and would-be ocean sailors, but my biggest challenge was to teach my wife and children. We became a feral family for a while and walked every track we came across, here and overseas. Only then did I appreciate how much more there is to orienting yourself *to your surroundings*, than simply having a compass.

My next inspiration came while walking the forest on a foggy day. I simply asked how the trees themselves would hold the secret to which way is which. Years of observation and testing later again, and this is the result. I don’t want it to die with me.

I hope you too can now enjoy the magic of the science and love the art of exploring, even teaching yourself, before you too have to stop still, inside the bounds.

Learn a little before it is too late.

Outline

“Navigation Down-Under” is your complete manual of bush navigation and outdoor orientation for when you go off the well-worn track. A free pocket guide to take with you bush-walking is part of the pack.

Do you know how to predict and find direction from the Moon by memorising just two simple numbers? Can you interpret the Australian bush plants for direction? You will find some never-before published new techniques, as well as all you need to know about traditional methods like Lie-of-the-Land.

If you come from the Northern hemisphere, you’ll need the top-down global approach, and can try some special Southern Hemisphere methods of direction keeping.

Sailors will find here a valuable beginning into celestial navigation.

A lot of it is about how to navigate without a compass, how to stay oriented and how not to get lost. It is an essential course in basic bush awareness and orientation, for surety and safety, plus it also throws out the challenge that you can improve your already existing competence very quickly and easily.

For Scouts or emergency search-and-rescue workers, it is a thorough course, advancing beyond the map and compass. Or perhaps you are a tour-guide and need more than course and distance — You’ll get something more, something more like biogeography or ecology.

Each page is a carefully arranged lucky dip of interesting tidbits.

Keywords

Navigation; Orientation; Celestial Navigation; Bushwalking; Map and Compass; Without a Compass

Section 1. BIG-PICTURE TOP-DOWN pp 3-33

General Introductory Points Big-Picture Rule One:

3 Locate a Distant Reference Direction First
3 Visualisation is your Key Skill
3 Big-Picture Orientation, a Mental Layout Acquired Beforehand
3 Compass Navigation Robs You of a Global Perspective
3 The Big Picture is Invisible — Your Job is to Visualise It!

Global Perspective; Earth

3 Compass Navigation Robs You of a Global Perspective
4 Global Re-orientation — Light-Half/Dark-Half
5 A mnemonic for global orientation: "True Polarity"
6 Mnemonic: "Time Tells Turning"
7 The sky turns 15° per hour —Use your thumb and forefinger
8 Global Orientation: Latitude and Polar Distance
9 The Angle of Rising and Setting—is Determined by Your Lat.
10 Global Orientation: Point to the South Pole…
..half its polar distance below horizontal
11 The North Pole is *Perpendicular to the South Pole*
12 Global Orientation: the South Pole Star, and Polaris
13 Pole Stars—"(Latitude)° above and below, South & North"
Point to 2 Points on the Equator — Halfway between the Poles
15 Perspective Distortion — The Sun Moves in a Straight Line!
16 Global Orientation: Half the Arc-Distance below Horizontal
17 Half the Arc-Distance below Horizontal—2 Explanations
18 Example: Point to Tahiti
19 Use Latitude for a Distance Scale (Not 'Long'-itude)
20 The Horizon Rotates to Your Right in the S. Hemisphere
21 Global Perspective — Rotation of the Horizon
22 How to Shift Your Horizon —Its Timing and Height
23 Latitude without Numbers
24 Mnemonic "The Sun Travels the Tropics"
25 Tropical Countries and Places Under the Sun
— Arranged in Time Zones Relative to Eastern Australian Time
— 10 hrs ahead of Greenwich
26 North/South and Noontime by Bisection (of Rise and Set)
27 Finding Magnetic Variation by Bisecting Rise and Set
Find E/W by Delayed Bisection of Sun & Full Moon At Rise/Set
28 Find North from the Combination of the Sun and the Moon
29 Eastern Australian Standard Time Zone
10 hours ahead of Greenwich
Showing Tropical countries and places underneath the Sun
32,33 Overview
128, 129 Tropical countries and places underneath the Sun

Sun Your Best Reference Direction:

4 Imagine the Sun at High Noon — Always
5 Mnemonic: **N**oon Sun Passes **N**orth of My **N**ose Down Under
6 Notice these, Yesterday — to Guess the Time Today
7 Mnemonic: The Southern Summer Sun Sets Somewhat South
8 Mnemonic: "Sun at High Noon — How High?"
8 On Overcast Days, Average the Brightest Sky over 1/4 hour
9 High Noon — How High?
10 Optical Illusion — Beware!
— Use Your Shadow Not the Sun, For Direction
11 The Dark-Blue Polarisation Band Perpendicular to the Sun
11 The Centre of the Rainbow is Down-Sun
12 Your Shadow Rotates with the same clock-sense as the Sun
Shadow-Rise and Shadow-Set is opposite direction to the Sun
12 Mnemonic: Shadow Rise is on the Right; Set is on the Left
12 Mnemonic: Your Shadow Passes South of Southerners
at Southern Noon
13 The Sun Passes Quickly Past North-South Nearer the Tropics
14 Shortest Shadow South—Opposite Highest Noon.
Always Imagine "Shadow-Noon" on your "Shadow South" Side
15 Locate Polaris (& Find N) by Imagining the Centre of Circling
16 " Noon " is Not at 12 O'clock
17 The "Equation of Time" Diagram
18 The Sun Oscillates Seasonally between +/- 23½° Latitude
19 Using the Declination of the Sun
20 Tell the Time by the Compass Protractor—Tilt to the Equator
21 Or Judge the Time By Sight—by Mirroring the Sun Around N
(To Make an Hour Hand on a 12 Hr Clockface)
22, 23 Walking in Phase with the Sun, Wind and Moon
24 Tell the Time of Night by the Star Opposite the Sun
25a Eastern Australian Standard Time Zone 10 hours ahead
25 Tell North from The Time By Using a Protractor
26 Longitude and Latitude from the Sun
27 A Bush Theodolite for Overnight Equal Height Observations
28 Find North by your (non-digital) Watch-Hands
29 Find Any Other Direction Too — Using the Hour Hand
29c String North
30 Locating Anti-sunrise Shortest Shadow Souths
30 Sun Path Norths — Summary
31 The 2 Flaps Method for N.—Lat. & Dec. Angles Separately
31 Seasonal Adjustments For Equinoctial East
32, 33 Overview
132, 133 Eastern Australian Standard Time Zone
10 hours ahead of Greenwich
Showing Tropical countries and places underneath the Sun

Stars

4 The 4 Bright Stars of Orion Point out Where the Pot is Going
4d The Ecliptic
5 The Two Brightest Stars Point out the South Pole Star
6 The Spinning Earth Makes Circular Paths for the Sun, Moon
7 Stars Leave Star-Trails
8 RISE and SET Directions for a (Local) STAR COMPASS
9 Global Star-Compasses e.g. 'Perpendicular to' rise and set
10 Right Around the Horizon, Stars Move to Your Left, Down S.
11 Identify the Stars That Pass Directly Overhead
12 Ways to Locate the South Pole Star Or the N./S. Meridian
12a&13a Global Orientation: the South Pole Star, and Polaris
13 Pole Stars—"(Latitude)° above and below, South and North"
13 South Pole Star Chart
14 Find the Polar Axis by Star-Trail Bisection
15 The Eagle Clips the Equator, South of Altair
16 Equatorial Stars Rise and Set Due East and West
17 Rigel-to-Capella is a good S./N. Pair
18 Use the Southern Cross as an Hour Hand
18 Picture the Southern Cross during the Day
19 Perspective Distortion — Use the Correct Vertical
20 The Southwest Corner of the Great Square is N. S. E. W.
21 The Southern Summer Rectangle And a Triangle Pointing S.
22 Navigating by the Shape of the Night Sky
23a Latitude without Numbers
23 Matching Sky to Sky — Move Only Your Horizon
24b Stars Opposite the Sun
24 2 Different Back-and-Forth-Star-Directions for a Position Fix
25 For Land-Navigation, the Plumb-Line Star-Pair Method
26 Equal-Height Stars When the Sea Horizon is Visible
27 Great-Circle Reference Star Directions
28 Leo the Lion Looks like a Lion or Sphinx Squatting
It Has Four Lines which Show N./S. E./W.
29 String North Latitude without Numbers
30 "Star-Time" Gains Four Minutes a Day
31 Working the Star-Longitude Numbers
32, 33 Overview
118,119 Appendices: Divide the Star Globe into 8 Octants
—and Learn the Stars in Each
The Southern Figure of Eight
The Zodiac
122 A List of Star Coordinates
124 Drawing Great Circles
125 Calendars in the Sky

Moon

4 Look for the Line Joining Sun, Moon, Planets & Zodiac Stars
— the Ecliptic
6 The Moon; Rule 4: Look for It
8 From the Moon, Locate the Sun-Moon Direct Line, Carefully.
10 *Mentally Rotate the Sun-Moon Line Around Polaris*
12 "Cusp North" — Approximate Direction from the Moon
14 The Rabbit Looks up Ahead at Full Moon Using the Ecliptic
16 The Moon Cusps Push and Pull the Hour Hand Backwards,
Down South
17 Watch the Clouds Cross the Moon
18 The Moon is Lit By the Sun
20 The Moon Rises and Sets 50 Minutes Later Each Night
22 The Moon is "in Phase" with the Sun — Watch for It
24a The Moon Moves Over the Tropics
24 Predict the Full Moon Path According to the Time of the Year
24d Finding North from the Moon, by its height & phase
25 Predict the Moon Phases by " N minus M "
28a Find E/W By Bisection of Sun & Full Moon At Rise or Set
28 To Predict the Moon's Path, Visualise the Ecliptic
29a Find North from the Combination of the Sun & the Moon
29 A 4 Week *Position Cycle* of Moonrise/set, to Find E/West
29e Keeping Track of the Moon's Motion along the Ecliptic
30 Adjusted Moon-Cusp North:
To the Left or Right, By Moving the Sun
32 Overview: The Moon
116,117 Appendix: Moon-Phase & Tide-Time Dial

Wind See also pp. 60a-68a

5 Mnemonic: "Wind? Weather Map!"
7 Mnemonic: "Wind in Your Face"
9 'Low' Clouds Come Clockwise Down under
11 Weather Fronts Distort The (Circular) Wind Circulation
13 Wind-Direction-Change Rule for Buys Ballot's Law
13 Steering Winds
15 Atmospheric Pressure Changes.
17 Watch the Clouds Cross the Moon
19 To Determine Upper Wind Direction from the Clouds
21 Clouds and Con-trails and Their Winds
23 Prevailing Winds on Creek Banks Tips for calm weather
27 Make a Bush Psychrometer
31 Topographic-Level Winds
33 Overview: Global Weather Patterns

52e The Aurorae
53e City Glow

Clockwise See also Map & Compass Work

4 Mnemonic: "Clock"wise Northern Hemisphere SWiNES
6 "VEERING" with the Sun is "Clockwise"
only in the Northern Hemisphere
"BACKING", against the Sun's movement, is "Anticlockwise"
— but only in the Northern Hemisphere.
8 Mnemonic: (when you say) "COMPASS" (say) "CANADA"
10 "Bears Circle Clockwise" Compass Bearings are Clockwise,
A Full Circle, and Eurocentric, Cee?
12 Mariner's "Compass Points" work on Successive Halvings
14 "E. W. N. South" Of What!? Rule: Say What
16 Back-Bearings Killed Sleepy Pilots
18 Back-Bearing: Plus or Minus 200° Then Minus or Plus 20°
20 Turn 90°? "+/-100° -/+10°" !
22 The Clock-Face Method for Direction
24 One Degree is about One in Sixty
26 Anticlockwise is Your Best Spin-Reference Direction
28 Bearings & Tracks: "If it is right, it is big in my sight"
30 "By the Nose" Navigation
32 Overview

Anticlockwise

5 Mnemonic: Down Under, The Sun Moves ANTI-BigBENWiSE
i.e. anticlockwise
7 Southerners Need Anticlockwise Systems
9 A Compass-Needle Continent—Swinging the Continent
11 Interpret a Compass Needle as "RED HOT—WHITE FROST"
13 Four Reference Directions—Name Them "Rise, Noon, Set, Midnight"
15 "Rise-Noon-Set-Midnight" carries its meaning across the Equator!
N.S.E.W. doesn't.
17 The 0, 1, 2, 3, 4 Reference Directions
19 The Sunny Skies Quadrant System
21 The "SWEETHEART" Method of Orientation
23 Mnemonic: "North; Coast"
23 Go Overseas!
27 Walk across Australia! English!
29 South is a Triply Better Reference Direction than North, in the Sth
31 Nose-Navigation Needs an 'Anti' Mnemonic: "Nor-West, Not-Least"
32 Overview
Revision, Overview and Explanations pp. 32,33
Top Down Orientation
Time is counted in cycles
Closer to Home
The Precession of the Equinoxes
The Moon
Global Weather Patterns
The Moving Horizon
The Spherical Earth
The Spinning Earth
Moving the Horizon

Section 2. THE INSIDE STORY—Mental Manoeuvres pp.34-55

Learn

34 Navigation is More Than Navigating Common Sense
36 The "Good" Navigator. You.
38 Don't Just 'Get By' and 'Make Do'
40 Walk Where the Navigators Talk — if you want to learn navigation
40 Explore It's No Fantasy
42 Self-Motivation is Fundamental
44 Routine Mind-Shut-Down Procedures
46 Navigation is Mental Work — Stay Alert
48 To Work Harder, Rest Harder
50 A Three-Track Mind
52 Concentrate Outwards
54 Come to your Senses

Think; Interpret

34 Your Subconscious is Superior to Science!
36 Think out Loud
38 Memories are Made of Landscapes, Not Compass Needles!
40 Feed Your Subconscious through Your Conscious Focus
42 How to Feed Your Brain
44 Feed Your Subconscious Subconsciously
46 Instruments Instruct the Intelligent
48 Minds Work Best with Intelligent Questions on Them
50 Interpret!
52 SPELL Out Numbers — Into Words
52 PAINT your Words — Into Pictures
54 TRANSFER Your Pictures into Reality
54 Put That Experience in Your Memory Bank
55 Extend Visible Reality into the Invisible Picture

Angle:

34 Measuring angles at 1 cm per degree
35 Point and Blink = 10% Shift
36 Guesstimating Angles at 1 degree per cm
37 Distance using Apparent Size;
37 Visual Angle, Size and Distance & 6°; Side-wise Offset
(38, 39 Grid-line Walk & Mental Grid Maps)
40 Cyclical Motion Divided into 12ths
41 Approximate Sine-Wave Values

Look

34 Visual Assessment is Your Main Clue — Rely on It More
36 You Need Excuses to Stop and Have a Good Look
38 You Need a Road-Map To Climb a Hill!
40 Look into the Far Distance Look through the Haze Wait
40 Wait for a Change in Perspective...
42"Retracing is Re-preciating"
44 Look Back Regularly. Look Around
46 Look Through the Vegetation, to the Contours
48 Play the Field-Scientist
50 Look at the Ground
52 Look for Foreshortening & Overlap & Parallax
54 Look, with Vengeance Aforethought

Integrate

3 Visualisation is your Key Skill
34 Integrate: Jetstream, Earth Rotation & Heaven Rotation
36 Visualise Familiar Landscape Trends, Under the Sun
38 'Land to Sky — Sky to Land' Navigation
40 Join the Invisible Big Picture To the Visible Landscape
42 Landmark to Landmark Network Navigation
44 Aim to Integrate…
46 Imagine an Aerial Photograph of the Continent
48 Connections to the Outside World
—You don't need to feel isolated
50 Orientation is More Fundamental Than Position Sense
52 Make Common Sense of the Various Direction Clues
52 Don't Degrade the Point of a Clue or System
54 Preparation is the Key to Difficult Navigation
42e Moveable Position vs Fixed Orientation
43e Name Each Clue — with solid ground
44e Notice and Match Up
45e In-Line Integration
50e Think in Pairs, in lines, trends and tracks

Orientation 35 Orientation = Direction Sense

37 The Get-Back Path is the Single Fundamental
38e Grid-Line Walk
39 Disorientation is More Dangerous Than Being Lost
39e Mental grid Map
41 Which Way Did I Come In? Which Way Do I Go on?
43 Disorientation — A Killer Syndrome
42e Movable Position vs Fixed Orientation
45 Un-Dis-Oriented;
47 Avoid Disorientation: OverNavigate
46e Making a M.U.D. M.A.P.-m.a.p.-m.a.p.
49 OverNavigate: Equals Over-Familiarise
51 Needle N, S, E & W. Identify them on the Landscape
51 Orientation to Start-Finish Rhumb Line—by sight or compass
51 Orientation to Your Finish Point, By the Parallax Method
53 Orientation to Your Start Point, By the Parallax Method
55 Look Backwards, Think Forwards

Disorientation

35 The Navigator's Top 10 Problems; and Band-aid Solutions
37 How I Manage to Get Lost or Disoriented
39 Logical Blunders — Examples
41 Logical Presumption Leads to Utter Delusion
43 Casual Outings Catch You Out
45 Trapped! By Not Looking Back
47 How to Get Lost—Follow the Track—A Track is a Trap-Door
47e Disorientation in new territory
49 How to Get Lost—Follow the Leader
51 Exponential Anxiety — the 11:59 syndrome
53 Nervous Nellie Navigation — Not

Reorientation

35 Reorientation
37 Voice Your Thoughts — Don't Suppress Important Clues
39 Trust the Untrustworthy
41 Trust Less and Prove More
43 Trust Yourself Less
45 Disoriented? Stop. Say So. Reorient!
47 Reorientation; And a Fresh Start
49 "As Solid As the Rocks in My Head"
51 Explore Junctions, While You Can
53 Look for the Essentials — the 'Directions'
55 To Get There Quicker, Go Slower

Lost?

35 Lost? Rule One: Stop! ..getting More Lost
37 Back-track in Your Mind before You Back-track on Your Steps
39 Rule 2: Start! Getting Unlost. Find yourself. Regain confidence
38e Grid-line Walk — Explore in a Square Grid Pattern
39e Mental Grid Map
41 The Simplest Way to Get Unlost is to Retrace Your Steps
43 More is Better — Thought, Time Care
45 Lost? Rule 3: Do a Good Job—of walking out or staying put
47 How to Leave a Message
49 Lost? Rule 4: DON'T Do It Again!
51 Separated? An Agreed Plan Helps
53 A Whistle-Code for Contact Calls
55 Search and Rescue Signals — Noises Repeated Regularly
120 Appendix: Morse Code and Rhythm Mnemonics for it
121 Appendix: Semaphore Code and Mnemonics for it

Section 3. REALLY INTERESTING STUFF
—Bush Navigation pp56-89 See Also 'Wind'

Nature's Norths

56 Nature's Norths
58 Rock Noon
60 Wind West See also Wind, Section 1
62 Think Wind
64 Be Wind-Wise: Listen
64 Obvious Tell-Tales: Windblown Objects
64 Obvious Tell-Tales: Landscape
66 Light & Colour Effects
68 Botanical Tell-Tales
70 Combined Effects of Wind, Salt and Light
70 Botanical Asymmetry
72 Think like a Plant
72 "Mosses Mop up Moisture" "Lichens Like Light"
72 "Fern Fronds Face the Front" i.e. the sunny side
74 Bush Noon— The Sun is Always out, If You Know How to Look
74 False Asymmetry & Symmetry True Symmetry & Asymmetry
76 Higher Density of Leafiness on the Noon Side
76 The Lowest Leafy Branches are on the Noon-Side
76 "It's the Shady Side That Shrubbery Shows up"
76 Tall, Steep and Ragged Backside Wedge-Shaped
76 Hollow under the Shady Side & Imperfect Shape
76 Gaps on the Shady Half Dead Branches
78 'Solar-Panel' Tilting of the Canopy Top
78 Wedge Shaped Lopsided Lean Half-Dome One-Sided Leafiness
78 Individual Branchlets Bare Backbone
80 Branching Patterns
—Examine Them for thickness, length, angle, curvature
82 Isolated Vegetation Shows the Clearest Asymmetry
82 Closed Canopy — Look for Gaps; Saplings
82 Roadsides & Campsites Reverse Some Effects!
84 Flowers Respond to Sunlight Fruit Distribution and Ripening
86 Stem and Leaf Colouring New Growth is Colour Differentiated
88 Noon-Sunlight is More Vertical
88 The Shedding of Bark on the Sun-Baked Side
88 Where to Look for Fading or Lack of it

Memory & Naming Skills See Sect.5, Navigation Mnemonic

56 Don't Forget to Remember, Your Way!
56 Unlock Memorable Chapters in Your Life
56 Go for the Jugular. Zero in on What Matters
58 Don't Try to Memorise Details without an Overall Framework
58 Don't Try to Remember Anything You Haven't Memorised
58 Write down What You Memorise!
60 Anything is Memorable
60 Make Individual Memories Memorable!
60 Remembering Trees
62 The Difference between Looking at, and Seeing
62 Search-Image
62 We Recognise 'Sameness' But Need to Describe the Differences
64 Place Recognition
64 You Recognise What You See, By What You Can't See
64 Description Requires Words
64 Can You Describe All That You Can Recognise?
66 Discuss It
66 Collect the Details
66 Identify a Specific Place by its Specific Collection of Details
66 Include What You Can't See
68 Extend Your Familiar Range Systematically Hints
68 Leap-Frog Walk in New Territory
70 Draw the Skyline, the Ridge-lines, the Outlines
70 Label it with the 8 main directions
72 Examine the Skyline BEFORE You Walk up to It
72 Make a Mental Movie
72 Take Mental Photographs
72 Take a Mental Photo of Each Change of Track
74 Remembering the Sequence, Needs More Than Logic
74 Do Something NUMERICAL
74 Match the SHAPE
76 Use a Type of Memory which you are Good at
76 Use the Name of the Track for the Acrostic
78 Group Several Related Images into One See also p. 110
80 Working Names — Invent Them
80 Standard Name Plus Personal Name
80 Remembering Names
82 Name the Subsections
82 Name the Sequence
84 Revise your Memories To Remember Formulae
86 Remember the Sequence — from AA to ZZ

Lie of the Land

57 The "Lie" of The Land
57 Listen to the Pioneers Lie Has To Do with Water Drainage
59 Major Rivers & Ridges vs Minor Ones Sort it out on the Map
59 Catchment Divisions Snake from Coast to Coast
59 A Catchment-Division Separates Whole Valleys
61 Ridges Ridge Names Mnemonic: "Ridges Rise"
61 Uphill — Which Hill? Upstream — to which Divide?
63 Shoulders Stop. Shoulders are Not Easy (like Ridges) to Walk on
63 Saddle — A Flat between Hills, Sitting Astride a Ridge
65 Notice When You Cross a Catchment!
65 The Giveaway! A Change of View—Mnemonic: "Catch the View"
65 You Can't Cross a Creek Twice from the Same Side
67 Break of Slope/Make of Slope Scree Slopes — Tread Carefully!
69 Break of Slope — And Route-Finding
71 Mnemonic: "Down in the Mouth" Which way is the flow?
71Hint: Don't think "this side" & "the other side".
73 The Inside of a River Bend is Flatter Ground
73 Rivers Bend! Don't Forget to Look Backwards
73 Rivers Meander. Ridges Run Straighter
75 Land-Form. Hint. What Makes a Cliff and an Overhang?
77 Headlands, Bays, Prevailing Winds, Longshore SandDrift, Creeks
77 Beaches — Slope, Particle Size, and Wave Energy
79 Rock Typing Soil Typing

Contours and Slopes

81 Contour Lines
81 Contour Navigation: Practise It, Before you Need It
83 Contour Curves: Your Job is to Imagine the Shapes into Life
And to Match the Lines to the Landscape
85 Contour Heights: Read the Numbers!
85 Contour Spacing: Close = Steep Slope
85 Contour Slopes: Work Out 1 Mm and 1 Cm Contour Spacing
85 Reference Slopes — To Imagine the Climb with!
85 The Beaufort Wind Scale — Modified for Bushwalkers
87 Make a Clinometer — a Slope Measurer
89 Just Draw It

Tracks and Bends

57 Stick to the Track Reasons for Leaving the Beaten Track
57 Cross-Country Routes
59 Tracks are like Naughty Children
59 The same is true for creeks & ridges
59 Explore Branches While You Can
59 Convergent Tracks Lead to Civilisation
59 Down-Track vs Up-Track
61 Sympathy and Understanding with Track Markers
61 Old Track Markers
63 Track Markers When You Lose the Track-Markers
63 Notice (with Alarm!) When...
65 Mark Your Trail Mark Your Trail Non-Permanently
65 Tracking Someone Else
67 Mark Your Trail More Permanently and Ostentatiously
67 Mark Your Trail Invisibly
67 A pebble Code — Keep It Simple

Bends

69 Keeping Track of the Bends Desired Equipment
69 Logging Constant Diversions
71 The Difference between 'Direction' and 'Track'
71 Continuous bends
71 Follow the bends by anticipating the trends
73 Keeping a Compass Course, by Legs
73 Turn Smooth Bends into Sharp Jumps
73 Mind Which Way You Go
75 "End the Bend" i.e. Notice the Un-Bends
75 Name the Bend, By the Trend, of its End
75 Notice and Name Perverse Bend
77 Look Through the Trees, to the Sky and Skylines
77 Periscope Navigating by Trees
79 Bush networks Don't Navigate by Networks Only
79 Antidotes For Guessing at Network Junctions
81 Sticking to the Bush Network Natural Routes Naturally Converge
81 Coping with Divergence Reverse logic
83 Trackless Navigation The method of Names
83 Bush Networking Essentials
85 Walking "Straight" through the Bush Straight around
85 How to Walk In an Unintentional Circle
87 Walking an Exact Straight Line in Open Country
87 Leap-frog a Straight Line by Looking Ahead
89 Radio Direction Finding—As Good as a Compass

Section 4a. DISTANCE pp. 90-108 left-hand pages
See also 'Angle'

Progress

90 Distance Guesstimation is a Major Problem for Walkers
92 Use the Map Scale—Don't Just Look at It The Jargon
92 Map-Scaling-Factors are Meant to be Interpreted
94 Psychological 'Half-Way Point' When You Meet Other Walkers
96 AIMING OFF by 10° — 10° is **175m per kilometre**
96 Aiming-off at Sea; Aim Off 10% or 6°
98 Up-down Progress
100 Distance by Double Pace—Test Yours Tie Your Ankles Together
100 Don't Lose Count! Use Finger-Math
100 Test your pedometer
102 Line of Sight Can Be Extremely Accurate
102 Two Opposite Landmarks
104 "Changeover Lines" of Progress — Relative Apparent Sizes
104 Use the Landscape Itself to Measure & Mark Progress
106 The Sine-Cosine Tally Method of Keeping Track, Blind
106 Rise and Run Adjustments — Sine and Cos — North and East
108 Progressing A Position Line across the Map
108 Pinpoint "Fixes" are a Myth!

Pace

90 Distance = Speed x Time Keep a Log! Adding two Speeds
92 Pace Your Progress — Pre-Dict It, Don't Post-Dict It!
92 Advice about Walking Times — Double & Halve!
92 20 Minutes per Kilometre — Double & Halve — Easygoing Maths
92 4 km per hour — Normal Walking Pace — Double and Halve!
94 1 Metre per Second is 3.6 kph "1 Hour Extra per 5 Hours"
94 "1 Hour Extra per 500 m easy climbing"
96 Adjust Your Expected Pace
96 Don't Overcompensate for Slopes And Meanders
98 Don't Lose Count! Use Finger-Math
100 A Slow Kilometre Cancels out Three Quick Ones
100 To Progress Faster More Easily Pace Yourself
— Slow Down, but Don't Stop
102 Distance-Off by Vertical Angle Safe Distance Off
104 Circle-of-Position by Horizontal Angle
105b A Horizontal Angle between Features Yields a Position Circle
105c 'Two Horizontal Angles' Usually Fixes Your Position
106 Rise and Run Adjustments — Sine and Cos — North and East

Range

24e One Degree is about One in Sixty
34-36e Estimating angles
37e Distance using Apparent Size & 6°
37e Visual Angle, Size and Distance Side-wise Offset
51a & 53a Parallax methods
90 Range: Rule One: Guess
92 "Range" of Visibility — Two Halves to the Picture
92 "Range Squared is Dee Height"
92 "Range Squared is Dee Height"
94 Double, the Acute Angle, off Your Nose — For the Distance Off
94 Halve, Any Angle, from your Stern—For Distance Off
96 Distance by Optical Rangefinder
96 Range by Parallax and a Piece of String DIY Rangefinding
98 Distance by averaging maximum & minimum Guesses
98 Distance by Comparison with Some Length You Know
98 Distance by Cloud Shadows — Look for Them
98 Sound Travels Three Seconds to the Kilometre
100 Lighting Conditions & Eyesight
100 Visual Acuity is about One Minute of Arc
102 Approximate Figures for Visual Acuity
102 Test Your Own Visual Acuity
104 Circle-of-Position by Horizontal Angle
105b A Horizontal Angle between Features Yields a Position Circle
105c 'Two Horizontal Angles' Usually Fixes Your Position
104 The best range-finder
106 Rule of Fingernails Rule of Tom Thumb Apparent Size

Section 4b. MAP and/or COMPASS pp. 91-109 right-pages

Map Use

54e Helpful Chart Symbols 122 Appendix: Symbols
38,39e Grid-line Walk & Mental Grid Maps
46e Making a M.U.D. M.A.P.-m.a.p.-m.a.p.
91 To "Read" a Map — Rule One: Don't Lose Your Place!
91 Rule Two: Imagine Arrows for the Sun, & Your Movement
91 Rule Three: Get Used To Any New Map Scale
91 Rule Four: Don't Give Up!
93 Look Carefully at the Fine Detail on the Map
93 Look Carefully at the Fine Print
93 Some Map Details are Not to Scale!
95 Permanent Landscape is More Trustworthy Than Surface Detail!
95 Details Added on to a Map Are Prone to Error
95 Expect The Map To Be Unhelpful
95 Maps Do Give You 10 Times More Detail Than You Can Notice
97 "Maps Grip the Universe"
99 Align the Track
101 Align the Map the Landmarks
103 Align the Map to Identify Landmarks
105 Align the Map to Fix Your Position
107 Which Way is North?

Magnetic Compass Use See also "Clockwise", Section 1

37e Chart symbols
91 "L.M.N.Or P."
93 Using the Protractor by Itself
95 Using the Needle Alone — Emergency Magnetic Compass
95 Hint Understand that magnetic poles should be called
'North-Seeking' and 'South-Seeking'
97 Think "+/- 5°" For Compass Bearings "+/- 10°"
For Following a Compass; "+/- 15°" For Using a Compass!
99 Compass Errors — Be Impressed! Be Careful!
101 Compass Use — Master It, but Be a Good Master.
103 "Magnets Grip Maps"
103 Align Your Map in the Dark
107 'East-least; West-Best' Rule—Tells You Which Bearing is 'Best'
108b Getting Started in the Dark
108c Thinking Backwards
109a Taking a Bearing from the Landscape
109 Plotting a ('Compass-to-Map') Back-Bearing
109 No-Number Back-Bearings
124 Appendix: Map Symbols

Mapmaking

38e Grid-line walk
39e Mental Grid Map
46e Making a M.U.D.M.A.P.-m.a.p.-m.a.p.
91 Maps Mean: Imagine Me! — Making Mental Maps
91 "Map To Mind" Navigation
93 Mental Networks
93 The Most Valued Map
95 Strip Map Navigation — Follow-Your-Nose Navigation
97 Caving Strip-Maps — Come in Books
99 Map Folding and Map Holding
101 Layout Map — Blind
103 A Compass Holder
106a The Sine-Cosine Tally Method of Keeping Track, Blind
106b Rise and Run Adjustments—Sine and Cos—North and East
107 String Map
109 Parallax While You Walk — JUST DRAW IT!

Section 5. Navigational Mnemonic pp. 110-115
78b Group Several Related Images into One
110 A "Start-Stop-Rest" Navigation Mnemonic
110 P.R.E.P.A.R.E.D.— A Before-You-Go Checklist
111 Equipment—A What-You-Might-Like-to-Take Checklist
111 Place-Names; Learn Them; You Navigate by Local Features
111 S.T.A.R.T. off Oriented
111T.I.M.E. & Distance — that's the point
111 Distance
111 Progress; Pace; Range
112 Look in These 6 Directions — in 6 ways — Up and Down
112 4 More Slopes
112 Look in These 6 Directions — in 6 ways — Ahead and Behind
112 Look in These 6 Directions — in 6 ways — Right and Left
113 ..Plus in Two More Directions
113 (1) All, Around, Appreciatively, And At 6 L's
113 (2) Look at the Map: a Systematic Checklist. What 'System'?
113 Mark the Lines-of-the-Land On Your Map
113 Mnemonics for Map and Compass Work
114 N.S.E.& W.—the 4 cardinal directions, is a mnemonic of fours
114 W.E.A.T.H.E.R. — Check for Change
114 Stop-Signal: Why have you stopped?
114 REST and R.E.O.R.I.E.N.T yourself
115 RI For Revisualise the Invisible & then Relate It to the skyline
115 Clock-Sense Mnemonic
115 ENT for Environmental Notice Time—Orient yourself to Nature
115 REMEMBER to Note down the Names in the Notebook
115 Re-lax, and Play — Navigation Games and Activities

Miscellaneous pp. 34e - 55e
52e The Aurorae
53e City Glow
54e Helpful Symbols for Standardising your Chart–Work

Appendices pp. 116-121
116 Moon-Phase & Tide-Time Dial
118 Divide the Star Globe into 8 Octants
—and Learn the Stars in Each
118 The Southern Figure of Eight
119 Divide the Star Globe into 8 Octants
—and Learn the Stars in Each
119 The Zodiac
120 Morse Code & Rhythm Mnemonics
121 Semaphore Signalling Code & Mnemonics for it
122 Symbols for Track-Notes and Mud-maps
122 A List of Star Coordinates
128, 129 Tropical countries and places underneath the Sun
124 Drawing Great-Circles. The PZX navigational triangle
125 Calendars in the Sky
126,127 About the Author; Outline
Index pp. 128-129
Contents p. 2

Appendix

Eastern Australian Standard Time Zone

10 hours ahead of Greenwich
Showing Tropical countries and places underneath the Sun

p24a,25a


(CANBERRA 36° S.)
ROCKHAMPTON 23°½ S.
NEW BRITAIN 5°S
12
21° S. NOUMEA 11
13 ALICE SPRINGS 23°½ S
15° S. FIJI 10
14 MANILA 15° N. PORT HEDLAND 20° S..
SULAWESI 0°
WEST SAMOA 14° S.
23°½ N. HAWAII 9
15 JAKARTA 7° S; SINGAPORE 1° N.;
CHRISTMAS IS. 10° S.
COOK ISLANDS 11° S.
COCOS ISLANDS 12° S.
17°½ S. TAHITI 8
13
SUMMER TIME
Rotate this for other time zones
16 CALCUTTA 23°½ N.
23°½S. MANGAREVA 7
/MARQUESAS
17 MALDIVES 0°
PITCAIRN/Easter Is 6
25° S.-27° S.
(34° N. Los Angeles)
7
19
18 Gulf of OMAN
23° ½ N.
Tip of Californian Peninsula 23° ½ N
Is. De Revilla Gigedo 20° N.
Seychelles 5° S.
Gomez 26° S. 5
Mexico Guadalahara
23°½N.
19 Port of Aden 12° N.
Mogadishu 3° N.
Madagascar 23°½ S.
Galapagos Islands 0° 4
Guatemala 15° N.
20 Lake Victoria 0°
N limit of S Africa 23°½S.
Panama 8° N.
1
Sudan/Egypt; 23°½ N.
Aswan Dam
Cuba/Haiti 20° N. 3
Bogota 5° N.
21 Lake Chad 14° N.
Namibian Desert Coast 23°½ S.
Trinidad and Tobago 10° N. 2
22 Accra 5° N.
Timbuktu 17° N.
Brasilia 16° S. 1
23
Sao Paulo / Río de Janeiro 23°½ S.
0
West African Coastal Bulge 15° N.
Mid North Atlantic 23°½ N.

Places in capitals are less than 6 hours away from Australia. The others are on the other side of the world.
View this as if from above the North Pole—the Sun 'moves' clockwise, but the Earth spins anticlockwise.

Eastern Australian Standard Time Zone

10 hours ahead of Greenwich

Showing Tropical countries and places underneath the Sun

Cut this one out and post it on your wall until you have learned most of it.


(CANBERRA 36° S.)
ROCKHAMPTON 23°½ S.
NEW BRITAIN 5°S
12
21° S. NOUMEA 11
13 ALICE SPRINGS 23°½ S
15° S. FIJI 10
14 MANILA 15° N. PORT HEDLAND 20° S.
SULAWESI 0°
WEST SAMOA 14° S.
23°½ N. HAWAII 9
15 JAKARTA 7°S;
SINGAPORE 1°N;
COOK ISLANDS 11° S.
COCOS ISLANDS 12° S.
CHRISTMAS IS. 10° S.
17°½ S. TAHITI 8
13
SUMMER TIME
Rotate this for other time zones
16 CALCUTTA 23° ½ N.
23°½ S. MANGAREVA
/MARQUESAS 7
17 MALDIVES 0°
PITCAIRN/Easter Is 6
25° S.-27° S.
(34° N. Los Angeles)
7
19
18 Gulf of OMAN
23° ½ N.
Tip of Californian Peninsula 23° ½ N
Is. De Revilla Gigedo 20° N.
Seychelles 5° S.
Gomez 26° S. 5
Mexico Guadalahara 23°½N.
19 Port Aden 12°N.
Mogadishu3° N.
Madagascar23°½S.
Galapagos Islands 0° 4
Guatemala 15° N.
20 Lake Victoria 0°
N limit of S Afr. 23°½S.
Panama 8° N.
1
Sudan/Egypt; 23°½N.
Aswan Dam
Cuba/Haiti 20° N. 3
Bogota 5° N.
21 Lake Chad 14° N.
Namibian Desert Coast 23°½S.
Trinidad and Tobago 10° N. 2
22 Accra 5° N.
Timbuktu 17° N.
Brasilia 16° S. 1
23
Sao Paulo / Río de Janeiro 23°½ S.
0
West African Coastal Bulge 15° N.
Mid North Atlantic 23° ½ N.

Places in capitals are less than 6 hours away from Australia. The others are on the other side of the world.
View this as if from above the North Pole—the Sun 'moves' clockwise, but the Earth spins anticlockwise.

MOUNTAINEERS OUTDOOR EXPERT
series

CLIMBING SELF RESCUE:
Improvising Solutions for Serious Situations

Andy Tyson & Molly Loomis

THE MOUNTAINEERS BOOKS

Table of Contents

Title Page
Copyright Page
Acknowledgements
Introduction
CHAPTER 1

The Basics

CHAPTER 2

Rescue Knots

CHAPTER 3

Escaping a Belay

CHAPTER 4

Descending

CHAPTER 5

Ascending

CHAPTER 6

Raising

CHAPTER 7

Passing Knots

CHAPTER 8

Scenarios and Solutions

CHAPTER 9

Getting Outside Help
Appendix A: Accident Statistics
Appendix B: Gear Specifications
Appendix C: Knot Efficiencies
Appendix D: Continuing Education
Appendix E: Recommended Reading
Glossary

Index



MOUNTAINEERS
OUTDOOR EXPERT
series

CLIMBING SELF-RESCUE:
Improvising Solutions for Serious Situations

Andy Tyson and Molly Loomis

M
THE MOUNTAINEERS BOOKS

THE MOUNTAINEERS BOOKS
is the nonprofit publishing arm of The Mountaineers Club,
an organization founded in 1906 and dedicated to the
exploration,
preservation, and enjoyment of outdoor and wilderness areas.

1001 SW Klickitat Way, Suite 201, Seattle, WA 98134

© 2006 by Andy Tyson and Molly Loomis All rights reserved

First edition, 2006

No part of this book may be reproduced in any form, or by any electronic, mechanical, or other means, without permission in writing from the publisher.

Manufactured in Canada

Acquiring Editor: Christine Hosler
Project Editor: Mary Metz
Copy Editor: Julie Van Pelt
Cover and Book Design: The Mountaineers Books
Layout: Kate Basart/Union Pageworks
Illustrator: Mike Clelland
Photographs by Molly Loomis and Andy Tyson unless otherwise noted.

Cover photographer: Mark Fisher
Frontispiece: *The need for self-rescue skills can arise when least expected.*

Library of Congress Cataloging-in-Publication Data
Loomis, Molly, 1977-Climbing self-rescue : improvising solutions for serious situations / by Molly Loomis and Andy Tyson.—1st ed.
p. cm.
Includes index.
ISBN 0-89886-772-X
1. Mountaineering—Search and rescue operations. 2. Mountaineering accidents. I. Tyson, Andy, 1968- II. Title.
GV200.183.L665 2005

796.5'220289—dc22
2005035066
CIP

♻ Printed on recycled paper

Acknowledgments

An enormous thank-you for the information, experiences, and time generously shared by Mike Clelland!, Kelly Cordes, Kevin Emery, Mark Fisher, Will Gadd, Ben Gilmore, Tony Jewell, A.J. Linnell, Nick Lewis, Allen O'Bannon, Jen Pine, Andy Rich, Louis Saas, Toby Schmidt, Phil Schneider, Clyde Soles, Garth Willis, and folks at the following organizations: Werner Braun (Yosemite Search and Rescue); Colby Coombs (Alaska Mountaineering School); Lisa Gnade (DMM); Mike Gibbs (Rigging For Rescue); Gordy Kito and Maureen McLaughlin (Denali National Park); Tom Moyer (Salt Lake Country Search and Rescue); Ken Phillips (Grand Canyon National Park); Kolin Powick (Black Diamond Equipment Ltd.); Paul Roderick (Talkeetna Air Taxi); Jim Ewing and Paul Niland (Sterling Rope); Jed Williamson (AAC's *Accidents in North American Mountaineering*); Julie Van Pelt (JVP Editing); Christine Hosler and Mary Metz (The Mountaineers Books). (Organizations are listed for identification only.) And our parents!

Good rescue skills can minimize or eliminate the need for outside help.

Introduction: Why Self-Rescue?

Climb long enough and at one point or another getting stuck in a jam high up off the ground is inevitable: stuck ropes, a crucial piece of gear missing in action, wandering off-route into dicey terrain, or an injury that leaves a climber in need of help. Typically, we piece or puzzle our way to a solution and move forward. Climbers are generally smart and resourceful, able to handle challenging situations, so why a whole book on self-rescue techniques?

Flip through the annual *Accidents in North American Mountaineering (ANAM)* and some obvious trends become evident. Most, if not all, climbers strive to climb in a safe, intelligent, and independent manner, but we often up the ante when we climb with less-experienced partners, fail to practice our rescue techniques (until the crucial moment), forget that we are smart and act dumb, or we end up just needing to learn the hard (sometimes very hard) way. There are plenty of accidents every year that *ANAM* does not cover; in fact most accidents included are documented because there was outside help provided for the party. Many accidents are never reported because the climbers were able to take care of themselves, using their problem-solving, first-aid, and rescue skills to handle the situation independently.

With a little more know-how and practice, many of the reported accidents could be handled better by the party in the mountains or on the rock. The more effectively you as a climber are able to control the situation (e.g., by getting your partner safely down the route to the base of the climb rather than waiting midroute for rescue by an outside party), the less effort (and risk) is required of outside rescuers. Depending on the situation, by employing self-rescue skills you may be able to eliminate the need for outside assistance entirely, if outside assistance is even an option. Depending on weather, local resources, and your location, it may not be. Organized rescue efforts are time-consuming, people- and gear-intensive, and are often costly, not to mention risky for rescuers (frequently volunteers). A solid grasp of self-rescue skills helps everyone in a bad situation. Remember that novice partners may find themselves needing to rescue you if things go awry. This book is not just for you; it is for your partner as well.

NUTS AND BOLTS

Climbing: Self Rescue seeks to inform readers how to confidently handle rescue scenarios ranging from simple to complex in all mediums of the vertical world—rock, snow, and ice—and also aims to serve as a resource by sharing technical tips and tricks, resources for continuing education, and data regarding both climbing-related injuries and climbing gear. It is our hope that this type of information, which helps further your skill base, can help prevent you from getting into trouble in the first place.

This is not a text on prevention of accidents; on the contrary, it assumes that you may find yourself in a situation that requires good critical thinking and creative rope work to alleviate. Prevention is, however, an overall goal, and one way to learn about prevention is to realize the penalty of failure. Understanding the reality of the real-life situations presented in this book will make any smart climber focus on prevention.

As in life, in climbing there are often multiple ways to solve a single problem. Certainly some solutions are more efficient than others and each has benefits and downsides; but the bottom line is that the "best" solution is the one that you as a rescuer can execute successfully and safely. In writing this book we have tried to avoid a black-and-white approach to explaining rescue skills (i.e., using words like "always" and "never"). A dogmatic teaching style only hinders development of the critical thinking we believe is so important to being a competent, confident, and safe climber.

Realize that in some instances you may not agree with our approach to a certain scenario or skill; rather than discard the solution presented, take it as a learning opportunity to investigate the pros and cons of the different methods. Not every solution known to the climbing discipline is included—space, time, and sanity intervened—but we have tried to present a variety of solutions, addressing the pros and cons of each. Initially the number of options may overwhelm a climber new to self-rescue. Stick with it and all should become clear with time!

Perhaps most importantly, *Climbing: Self-Rescue* seeks to develop your critical-thinking skills as a climber. The unfortunate truth is that real-life rescues rarely unfold as in practice; the list of variables is endless. *Climbing: Self-Rescue* addresses these variables by using scenarios that call on readers' understanding of improvisational rescue. Although experience is undoubtedly one of the best teachers for developing judgment, the climbing conundrums shared in this book will help you be all the more prepared for the unexpected when it crops up.

WHAT THIS BOOK IS NOT

Climbing: Self-Rescue is not an introductory climbing manual. We assume that readers already have knowledge of and adequate practice with the following skills: belaying, rappelling, placing artificial protection, constructing multidirectional anchors, lead-climbing theory, and basic climbing knots (figure eight series and overhand series). This is also not a first-aid manual. Although some scenarios may reference specific injuries, covering the treatment, packaging, and management of such injuries is outside the scope of this book. *Medicine for Mountaineering* by James Wilkerson or the compact *Backcountry First Aid and Extended Care* by Buck Tilton are recommended as accompanying references for first-aid skills.

HOW TO EFFECTIVELY USE THIS BOOK

Chapters 1 through 7 are an instruction manual focusing on improvised self-rescue. Text, illustrations, and photographs explain knots and *raising systems*, descent and ascension methods and considerations, passing knots, how to safely assist and rig an injured climber, and a variety of other information. The simplest way to complete any given task is presented first, then other options follow.

Do you have to be a master climber to understand this stuff? No. The situations presented are easy to envision and the systems build on each other. We do not recommend jumping into something like *counterbalance rappelling* (chapter 4) right off the bat, though. The instructions in this book build on one another, so a start-to-finish read is recommended. If you know your knots (chapter 2), you may choose to start with escaping a belay (chapter 3) and work from there. The building blocks of self-rescue are all in escaping a belay and are used in conjunction with all other systems.

After the instruction portion of the book, we give you a chance to test your skills in chapter 8. This chapter is devoted to climbing scenarios ranging from moderate to severe. We asked friends and other experienced climbers for tales of their own mini and full-blown epics. Some scenarios have been tweaked a bit to illustrate a certain point, but all are from real situations. The simplest and most time-efficient solution is presented, with other options following. We also discuss potential pitfalls and prevention tips, as well as list what skills to review. More experienced readers may choose to begin with the scenarios, using the referenced sections as a way to brush up on their skills.

Information provided in chapter 9 and in the appendixes is an excellent way to arm yourself with even more knowledge. Reviewing the statistics of documented accidents over the past fifty-plus years (Appendix A) will tune you in to common accident factors, how to avoid them, and what sort of self-rescue techniques you could employ should you encounter them. Appendix B, Gear Specifications, looks at a wide selection of gear on the market and describes things like the strength of a piece of protection, a carabiner, or of webbing. Appendix C, Knot Efficiencies, can help you make conscious choices about the knots you use instead of relying on habit and memorization (as many of us do). The Continuing Education and Recommended Reading appendixes are a collection of organizations, publications, and courses that can help you continue developing your skills.

But most importantly, practice the rescue systems we describe! The only way to learn them is by practicing. Learn to use friction hitches, releasable hitches, and backups. Learn the ins and outs of raising systems. Remember: If you are in a rescue situation, things have already gone wrong. There is no good reason to shortcut safety during a rescue; you will only endanger your own life as well as your partner's. This book's goal is to help prepare you for the unexpected and practice is essential for doing just that. Just as backcountry skiers practice transceiver searches and whitewater kayakers work on rolls, climbers should practice vertical rescue skills.

Rescue is as much an art as it is a science and it is constantly evolving. We have done our best to provide accurate facts, figures and techniques but changes are inevitable. Please send your comments to us, care of the publisher, so we can keep the information current. Thanks!

A NOTE ABOUT SAFETY

Safety is an important concern in all outdoor activities. No book can alert you to every hazard or anticipate the limitations of every reader. The descriptions of techniques and procedures in this book are intended to provide general information. This is not a complete text on self-rescue technique. Nothing substitutes for formal instruction, routine practice, and plenty of experience. When you follow any of the procedures described here, you assume responsibility for your own safety. Use this book as a general guide to further information.

—*The Mountaineers Books*

Knowledge of self - rescue techniques can help you move beyond the basics and travel with increased confidence in the high mountains.



CHAPTER 1

The Basics

FALL ON ROCK, PULLED OUT

Bitterroot Range, Montana

John put his light gloves down on the small ledge and they promptly blew away—just another glitch in the day's long chain of events. He and his partner, Glen, had started climbing the Perfect Buttress route in Blodgett Canyon at 9:45 AM that late-September morning. The pair took their time climbing; it was a beautiful day and they were enjoying the adventurous, high quality, and seemingly remote route. They swung leads; Glen started, so he would lead the last, ninth pitch, rated 5.11. The beginning pitches had some 5.9 and 5.10 moves, so both climbers were working hard throughout the day. They arrived at the last pitch around 5:00 PM. It would not get dark until after 7:00 PM, so they did not even discuss the time. Glen was excited for the challenge; he had wanted to climb this route all season. He racked and started up.

The pitch was steep and beautiful—a combination of face and crack climbing, the high crux a thin finger crack. Glen placed some small stoppers at the beginning of the pitch, saving *his cams for the crux. The lead took awhile. He rested whenever he could, trying to maintain his strength for the challenge above. John was belaying Glen with an ATC off his harness while watching some evening clouds roll in.*

Glen reached the crux at about 110 feet above John. About 10 feet below the crux Glen had placed a poor nut (expecting to put a lot of good protection above). About 8 feet below that was a large cam behind a block, and 5 feet below that was a quality large nut. Glen was disappointed with the protection possibilities when he arrived at the thin crack. It was steep and the crack was narrow and bottoming. He wished he had his small stoppers! Instead he placed a small rigid-stem Friend. Since the crack was so shallow, the head of the cam was against the back of the crack and the stem pointed straight out of the rock. It did not look like there would be much more protection for another 10 feet above the piece, but the climbing did not look as hard as he had anticipated. Glen continued up. With his feet just above his last piece, he tried to find a stance for his next placement. This is where he popped off the route.

The fall was clean at first, but the rigid stem on the Friend snapped so fast that he did not even slow down. The stopper launched and then the cam disintegrated the block. Glen ended up hanging from the quality nut. He hit his head and broke his ankle and upper arm in the 65-foot fall. John launched up off the ledge and came tight to the anchor. John was now in *charge of a rescue. He looked at his watch:* 6:00 PM.

The steep walk-off at the top of the climb did not seem a likely option. On the route there were fixed rappel anchors at the belays since many climbers rappelled before the last crux pitch. John lowered Glen as far as he could. Because of the protection failures Glen almost reached the belay ledge. John tied Glen off to his belay device and tossed him their second rope, with a figure eight on a bight tied on the end with a locking carabiner clipped to it. Glen clipped this to his harness belay loop and then clipped the rope into the nearest piece of lead protection he could reach. Glen was able to one-handedly wiggle in a second piece for backup. John put the second rope on a Munter hitch belay and slowly released the lead belay line, making sure as Glen came tight on the second rope that the pieces held. John released the lead rope, and continued to lower Glen to the belay ledge. On the ledge he tied Glen in and started treating his injuries.

Glen was dazed but helpful. After a slow tandem rappel John decided to lower Glen to the next anchor and have him clip in while John set up a rappel for himself. The process was efficient but still somewhat slow and it was getting dark. They had to switch back to tandem rappels for the bottom pitches since they were lower angle and John needed to support Glen and his injuries. At the last rappel station John set his gloves down in haste and they blew away. The clouds he had noticed *earlier were turning into a storm. He was glad they were almost back to their packs where they had some extra supplies.*

At the bottom of the route John bundled up Glen in all the extra clothes and rain gear they had and helped him to a sheltered spot. John left him with water and food before turning on his headlamp and hiking the 2 miles to the road to call for help. Local search and rescue was mobilized and they used a wheel litter to transport Glen to the ambulance at the road head late that night.

ANALYSIS

Glen chose to lead a hard pitch late in the afternoon after a long day in a remote setting. Perhaps he could have worked to get better gear placements and certainly should not have trusted his highest placement. After the accident John handled the situation very competently. He improvised a system (that was creative and backed up) to get Glen back to the belay ledge. He modified his descent systems to balance speed and comfort. John organized the rescue to minimize external involvement, getting to the bottom of the cliff and making sure Glen was comfortable and stable before heading for help.

Luckily, more often than not as climbers, we deal with snafus and not incidents as serious as the one described above—like realizing midrappel that the rope ends are hopelessly uneven or needing to assist a partner through a challenging section because that person lacks experience or has a minor injury. These situations can be solved with ease and efficiency by employing a variety of simple techniques and tricks of the trade. Thankfully the "femur fracture, concussion, broken ribs, hanging from a wall 2,000 feet up, dark with a lightning storm approaching" rescue experience is not the norm for the majority of us. That said, a simple snafu can quickly turn into a full-blown emergency if it is not handled quickly and correctly. Cold, wind, weather, impending dark, altitude, and human error, compounded by a simple glitch (or a serious accident) can quickly result in a downward spiral of hypothermia, frostbite, dehydration, or mistakes made out of exhaustion.

Run back through the incident described above and imagine how the evening might have unfolded differently if John or Glen had at any point panicked, thereby losing the ability to effectively problem-solve on the spot; or if they forgot any of the basic rescue skills they successfully used to safely extract themselves from the situation. This well-managed accident could have quickly turned into a cascade of follies with perhaps a grimmer outcome.

EMERGENCY PROCEDURES

"Emergency procedures" form the organizational framework we use to deal with any critical situation. *Climbing: Self-Rescue* focuses on the technical skills and improvised thinking needed to effect a rescue with an emphasis on backcountry settings, but it is certainly worth taking a look at the larger foundation underlying technical rescue. You may know every rope trick in the book, but unless you can incorporate your technical skills into the bigger picture, your tricks will not do much good (and may run the risk of making the situation even worse). The following steps will help you organize the rescue, thereby helping to produce a calm and efficient operation. Not all these steps are pertinent to every situation, though they are all worth considering.

- Plan ahead and prepare (the "Five Ps": prior planning prevents poor performance)
- Assess the scene (safety for you, other rescuers, and the patient)
- Initiate first aid if necessary
- Make a plan

- Rescue
- Follow through

PLAN AHEAD AND PREPARE

Self-rescue is much easier (both logistically and mentally) if you are prepared for it. Planning ahead and preparing (also one of the seven Leave No Trace principles) are of utmost importance. Whether a one-day outing or a month-long expedition, some initial research and basic knowledge will pay off if things go awry. Who should you call if you have a medical emergency at a trailhead? Who should you call if you need technical rescue assistance?

- Know the location of nearby public phones.
- If carrying a cell phone, know whether and where it will get coverage.
- Know the location of nearby medical facilities.
- Find and carry with you important local numbers (emergency services [911], police, local search and rescue (SAR) group, medical facilities, friends who could lend a hand).
- Leave a copy of your itinerary (route description and

estimated return information) with family or friends; consider whether your route description references geographical features that will be recognized and understood by non-climbers.

Also under “plan ahead and prepare” is packing any needed supplies in the event of an emergency. A first-aid kit should be carried, even if it is just a roll of tape and some gauze pads. Hopefully you have a more comprehensive one in your pack at the base of the climb or in your car not too far away. Rescue gear is important as well (though in this book we try to demonstrate how to effect a rescue with little extra gear); it is certainly nice to have at least the basics presented in the “Equipment” section later in this chapter.

ASSESS THE SCENE (SAFETY)

Before you dive into any rescue, make sure the scene is safe for you and the patient. If there are threats to your life (e.g., loose rock, lightning, avalanche), you should make a decision that does not create more patients. This may mean waiting for the situation to change and not helping your partner immediately, a difficult yet important choice. If the scene is unstable (e.g., there may be a second round of rockfall ready to dispatch), perhaps you can quickly move the patient to another area for treatment. This move may not be the best for the patient, but it will allow you to provide care instead of you both being seriously threatened had you not made a quick move.

INITIATE FIRST AID

Not all rescues require first aid. If this one does, take it on or, if available, enlist the help of someone else. Consider whether monitoring vital signs is necessary; if so, start recording. We recommend that all backcountry travelers have a basic understanding of wilderness first aid. There are several good training institutions listed in appendix D, Continuing Education.

You do not necessarily need to be with the patient to initiate first aid. If he is conscious you can call to him to obtain information about his condition and suggest things he can do while you make a plan. However, if your partner's condition is unstable, or he is unconscious, you will need to provide hands-on care.

MAKE A PLAN

During a rescue it is tempting to just move forward with the next step without stopping the action to create a plan. This constant motion can be effective, though it can also quickly go bad. When faced with a rescue situation, stop and make a plan. The "stop" does not have to be long, but the plan should be thorough, otherwise you run the risk of wasting time and energy with unnecessary additional steps.

Once you formulate a plan, it helps to make it verbally clear. That is, you would be able to tell someone else what you have done, what you are doing, and what you will do after that, followed by why it is a good plan over other possibilities. We recommend talking the plan out even if there is no one there to hear it. This should not make you feel like you are adding sudden insanity to the list of things that are going wrong; by verbalizing your plan you are clarifying what is rapidly speeding through your head. Taking the time to justify it over other options also helps you explore other possibilities. If you realize another good option while talking it through, don't be afraid to flex your plan, though make sure it all fits together before executing it. Talking out the plan can be done with the patient as well.

RESCUE

Hopefully your rescue is simply hauling your friend up a few feet through a difficult *crux* or exiting down a route to escape an impending thunderstorm. The simple and straightforward solutions are what we are striving to help with in this book. Though we spend time in this "Emergency Procedures" section talking about the big-picture framework, this same framework can and should be pared down and applied to specific components of any situation you find yourself in. For example, say while climbing a multipitch route your partner has taken a bad lead fall and is knocked unconscious. The emergency procedures process can be implemented for each stage of the overall rescue: reaching your partner, safely descending the route, evacuating yourselves to further care from the cliff base. Each stage will have its own microplan with unique and specific details.

Outside help. In making your plan, first assess whether you can handle the situation on your own or if you should consider asking for outside help from a rescue team or from others in the immediate vicinity. If you are able to execute the rescue on your own, formulate a plan and get cracking!

If you need outside help, decide on the most effective means of contact: Using a cell phone? Sending a messenger? Leaving your patient and heading out on your own? Before involving others you should assess the situation, evaluating what is wrong and what you think should be done, and then you should make a careful decision about who you think can help. Chapter 9 goes into detail about getting outside help.

Hopefully you will be able to take care of things on your own, but know where and who to turn to in case you do need help. There are some excellent resources for rescue out there, and knowing how to access the one you need will help complete this step of enlisting outside help quickly.

In the United States, calling 911 will connect you to a local dispatcher. The dispatcher will take information from you and contact the appropriate public assistance (e.g., ambulance, sheriff, fire department, SAR, backcountry rangers).

With this call you are requesting help and when the dispatched unit arrives they will take charge of the situation. This assistance is generally welcome and helpful, though depending on your situation and the local assistance available, you may realize you could have completed the rescue a different way. For example: You are a beginner climber and your partner accidentally drops the rope while threading the rope for rappel at the anchors atop a very hard sport climb. He ends up stuck, hanging from an anchor 75 feet up a 300-foot cliff. You know your expert climbing buddy is supposed to show up in an hour and he could help you out, but you call 911 instead. The local SAR crew shows up with ten people and more on the way. They place five bolts at the top of the cliff to rap down and pick your friend off the anchor. The newspaper writes another article about crazy climbers and interviews the local landowner who again questions whether he should allow climbing on his property.

Certainly this is an overdramatization, but this book is about personal resourcefulness. We are not advocating that you take matters into your own hands if you can't handle a situation, but we are saying you should take matters into your own hands that you *can* handle.

It is worth mentioning that with *definite exception*, many SAR teams are not comprised of technical climbers. Ideally they may have a few specialized high-angle rescue technicians, but this is not always the case. Realize too that safety systems built by organized rescue teams are a bit different than the improvised rescue systems acceptable for you and your buddies; SAR teams typically work with a higher margin of safety, which can mean more gear and additional lines. This does not mean one form of rescue is better or worse than another, rather that it is important as a climber relying on outside services to be aware of what that realistically may entail. With very rare exception is a rescue just like in the movies; do not expect helicopters diving in and whisking the injured party off a cliff face.

An important resource not to overlook (particularly in the example earlier of the dropped rope at a sport crag) might be other climbers at the cliff. There are plenty of documented cases of overzealous "experts" making the situation worse, but there are plenty more cases of Good Samaritans helping others out of a bind. This is a judgment call. Maybe that day at the cliff you see some people that you know are experienced big-wall climbers, able to handle this situation. Some random folks that you have seen in the local climbing gym a few times may not be the place to turn.

FOLLOW THROUGH

The rescue is not over until you clean it up and talk about it, no matter how simple or serious the situation. This is important.

Relax and regroup before continuing. You created a little system to pull your partner up through a crux section of the climb. Although certainly not a "serious rescue," don't just launch up the next pitch; there is still valuable information to be gained that will make your climbing more efficient. Check in and make sure he wants to continue (or understands why you both need to continue) and discuss how you might make the system better if you need it two pitches up on the hardest part of the route. Another example: You just spent the last fifteen minutes yelling and doing rope tugs to let your partner know he was on belay and could start climbing. Talk about the communication gap when you get back together (even if you are at the top of the climb). It will help greatly the next time the situation arises.

Transfer the patient to someone with higher medical

training. Maintain the patient as best you can while you are in charge of him. Keep track (write down if you can) how you found him, how his vitals have changed over time, and all pertinent information you can gather. This information will be invaluable for the next caregiver. Consciously transfer the patient to someone with higher medical training when that person arrives, and provide the information you gathered.

Remove rescue equipment and clean the area. Say you request a helicopter rescue for some severely injured climbers. Twenty SAR team members respond and execute the rescue. Ask them to help you clean up the area when done (if they have not already) or organize a local climber cleanup.

Evaluate. Find out what caused the accident and let your climbing friends know so they do not make the same mistake. If you have been part of a more serious incident, posttraumatic stress syndrome can be a very real, legitimate aftereffect. See the Continuing Education and Recommended Reading appendixes for references on this topic. If an organized SAR team or ambulance service is involved, they typically will have their own "critical incident stress debrief." Ask them for ideas of local resources.

WHAT ABOUT THE TEN ESSENTIALS?

If you have spent time outside you have probably heard of the Ten Essentials: ten items you should not head off into the wilds without. These include map and compass, sunglasses and sunscreen, extra clothing, headlamp or flashlight, first-aid supplies, fire starter and matches, repair kit and tools, extra food, extra water, and emergency shelter. However, considering the necessity of traveling light and fast on a route, emergency supplies realistically will vary greatly depending on the distance from car to route and from car to medical facilities, the type of route you are climbing (single pitch, long multipitch, or remote alpine route), and the type of environment you are climbing in (desert, isolated waterfall ice) and your familiarity with the area. Here are some lightweight emergency items worth considering depending upon your objective:

- **First-aid kit.** A half roll of tape in your pack or a few long strips stuck on the inside of your helmet can do wonders.
- **Knife**. Useful for cutting improvised bandages out of clothing strips. Has other very important applications, like cutting cord or webbing to leave at anchors, clearing crispy old rappel webbing, or cutting stuck ropes.
- **Space blanket.** There are several lightweight versions that fold up into extremely small packages.
- **Signal mirror.** Stranded high on a cliff this may be your

best bet for signaling for help.

■**Cell or satellite phone**. Although the purpose of this book is to help make you self-sufficient in the vertical world, it would be unrealistic to discard some climber's desire and some situation's need for outside help. Realize that getting help in vertical terrain is not an immediate process. It is time-consuming, resource-intensive, and may endanger the lives of others coming to your aid. That said, cell phone coverage is constantly expanding. A cell or satellite phone is a resource worth considering for adding to your toolbox as long as it is used responsibly.

■**Small stove.** Depending on the season, length of route, and your experience level, you may consider bringing a small, lightweight stove for melting water or emergency heat.

TECHNICAL RESCUE SKILLS OVERVIEW

Technical rescue skills fit into the "Make a Plan" and "Rescue" sections of the emergency procedures framework discussed above. Although in practical application, rescue skills will typically be combined, or transitioned from one into another, for simplicity's sake this book discusses one element per chapter and then looks at how they fit together in chapter 8, Scenarios and Solutions. The following skills are covered:

- Rescue knots (chapter 2)
- Escaping a belay (chapter 3)
- Descending (chapter 4)
- Ascending (chapter 5)
- Raising (chapter 6)
- Passing knots (chapter 7)

As mentioned in the Introduction, rescue, like climbing, is open to many interpretations, systems, and opinions. Though as individuals we may think our way is the best and only way, it is neither. As the saying goes, there are many ways to skin a cat. The most important thing is that you execute these skills safely and successfully without injuring you or your partner. In each chapter we describe a safe and acceptable method of applying a skill. Then we present additional options and encourage improvisation in the scenarios later in the book.

While discussing each skill we cover common terms and language used subsequently in the introduction of other skills. For that reason each skills chapter should be read and learned in order, if only so you do not miss terms that may be undefined in later skill instruction. Skills are ordered in a logical progression for learning, covering the necessary and easiest options first then moving to the more complex and less desirable options. Without a common language and understanding of rescue (just like climbing), it will be more difficult for you and your partner to work together in a tough situation.

Fig. 1-1. An example of the basic gear that can be used to carry out an improvised rescue.



EQUIPMENT

The beauty (and danger) of improvised self-rescue is that you are relying on yourself and no one else to carry out a safe and successful rescue. The improvisational element refers to the fact that no one, especially you, expects a need for rescue in the first place. Therefore fancy (and expensive) search and rescue gear like PMPs (*Prusik-minding pulleys*), brake bars, or litter baskets are left out of the equation. All skills taught in this book use the same items typically found on a climbing rack: a rope, carabiners, slings, and cord. Sure, items like pulleys and ascenders are certainly helpful and can make a big difference; but most of us do not typically carry that equipment on a single-day free climb. We will touch on the use of some more specialized gear (like pulleys and *mechanical ascenders*), but in general, instruction will focus on simpler tools (fig. 1-1 shows basic gear).

It is important to understand the added forces introduced in rescue situations and the limitations of climbing gear. This type of information is highlighted in sidebars throughout the book and in appendix B, Gear Specifications. Don't just assume that because a piece of gear works for climbing, it will automatically be adequate for all rescue applications.

Below is a list of gear we assume each climber will have (or each climbing party if specified). This list is an ideal; the reality is that not all climbers (especially the follower) will choose to have all of these items on his or her harness at all times. The more you learn the more you will be able to improvise and make do with what you have.

- one single *dynamic rope* per party, 50-60 meters (160-200 ft)
- six nonlocking carabiners
- six locking carabiners
- forty feet of 7-millimeter accessory cord cut into five lengths
- Some webbing for creating runners
- Tubular belay device (like an ATC)
- UIAA-rated harness
- UIAA-rated helmet

HALF AND TWIN ROPES

Some climbers prefer using either a half-rope or a twin-rope system for alpine and ice endeavors. These skinny two-rope systems are lighter, can reduce rope drag, and provide a great deal of versatility. Leading on twin ropes involves clipping both ropes through all pieces of placed gear. Half-rope technique involves alternating which rope is clipped through the gear. With either system, leaders are belayed on both ropes simultaneously. Per manufacturers' recommendations, half and twin ropes are meant to be used in tandem, never by themselves.

There are no cut and dried rules for incorporating half and twin ropes into improvised rescue. Although the skinnier your rope is the less ideal it is for rescue, there are plenty of other good reasons for using skinny ropes. The biggest risk is the amount of wear and tear a half or twin rope can handle compared with a single rope. If lowering, raising, or counterbalance rappelling, take particular note if your ropes are running over any sharp edges. Use your best judgment to problem-solve and play it safe.

ONE DYNAMIC CLIMBING ROPE

Length and diameter is left to personal preference, though considering this book focuses on single-rope technique the rope chosen should be rated as a single rope. Many climbers prefer 60-meter ropes for the versatility it allows in route selection and rappelling.

We will often refer to a second rope, although it is not necessary to purchase one simply for practicing purposes. Two ropes are needed for rappelling many routes. You can save weight and money by buying a second rappelling rope that is either of smaller diameter or that is *static* instead of dynamic. (Be aware there are specific precautions that must be taken when tying two ropes of different diameters together.)

SIX NONLOCKING CARABINERS

All UIAA-approved varieties of nonlocking carabiners are acceptable. It is not necessary to always reserve six unoccupied carabiners solely for the purpose of a rescue. If in a pinch, gear can always be reracked to free up additional carabiners.

SIX LOCKING CARABINERS

Large pearabiners are ideal for rescue applications. However many climbers scoff (with good reason) at the idea of carrying six locking pears; although ideal for smooth rope management and belay anchor construction, they are heavy! If you want to keep it light, try a combination of lighter weight, smaller locking carabiners and pears. Opposite and opposed nonlocking carabiners can always be used if you are stuck without enough lockers (fig. 1-2).

Fig. 1-2. Carabiner gates are opposite and opposed, minimizing the chance of the rope slipping free should one of the gates accidentally open.



CORD AND WEBBING

Recommended cord and webbing lengths follow. We do not recommend that you carry all of these lengths at all times. These lengths are great to practice with and, after realizing what is most essential to various situations, you can carry various combinations of them depending on your route and conditions. With a knife the longer cords can become whatever length you need in an emergency. And with practice the shorter ones will be useful for every situation.

CORD

Cordelettes are lengths of nylon accessory cord (also called Perlon) at least 6 millimeters in diameter (there are also a few specialty cord materials on the market for cordelettes). Length can vary but they are generally at least 15 feet long. If used for linking pieces in a multidirectional anchor, a cordelette is often at least 20 feet long.

What we call a *rescue loop* is a short loop of 7-millimeter cord tied with a Flemish bend or double fisherman's. A 4-foot length of 7-millimeter cord tied off with a bend will yield a 1.5 foot long loop that makes a nice length for tying most *friction hitches;* the resulting excess loop is fairly short after it is tied on the line.

See appendix B, Gear Specifications, for more information.

Cord lengths:

- Two pieces, 4 feet (122 cm) each, tied with a double overhand (aka double fisherman's) knot (we call these rescue loops (RL); usage detailed throughout the book)
- One piece of cord as long as you are tall plus 6-12 inches (for a *waist Prusik,* detailed in chapter 5, Ascending)
- One piece of cord twice your height (for a *foot Prusik,* detailed in chapter 5, Ascending; can also double as a shorter cordelette)
- One piece about 15 to 20-plus feet (460 cm) (for a cordelette)

WEBBING

Below are some common lengths for tying runners (aka slings).

See appendix B, Gear Specifications, for descriptions of the different webbing materials available. Many climbers prefer lighter weight 11/16-inch webbing for slings compared to 1-inch tubular webbing. The type of route you are climbing will typically dictate what assortment of slings you decide to take. Bringing a few hand-tied slings (as opposed to sewn runners) is a good idea; they are easy to adjust, easy to thread around natural features, and can be cut up and used for creating anchors at rappel stations.

Webbing Lengths (Before Knots):

- 5.5 feet (168 cm): Single sling (draped diagonally across torso)
- 9.5 feet (290 cm): Double sling (doubled and worn diagonally across torso)
- 13.5 feet (410 cm): Triple sling (tripled and worn diagonally across torso)

BELAY AND ANCHOR TERMINOLOGY

Here are some common terms and abbreviations used throughout the book specifically relating to anchors. Protection placement and anchor-building techniques are not covered. See the Recommended Reading and Continuing Education appendixes for ideas.

BELAY POSITION

Belays can be configured off of a climber's harness as well as directly off of an anchor. Both situations are covered throughout the book and we will also touch upon the specifics of belaying with a redirectional.

Generally, lead climbers belay their second off of the anchor in good-quality multipitch rock. Belaying is done off of the harness in most other climbing situations. It is almost always easier to effect a rescue if the belay is on the anchor already, but that is not justification for belaying off of a marginal or poorly positioned anchor. Cases can be made that it is safer to belay one way over another in different situations (see appendix E, Recommended Reading for more information). Generally, we assume that a Munter hitch or a *self-blocking belay device* is used to belay off of an anchor, and any preferred belay device is used off of a harness. Knowledge of how to execute rescues from all belay configurations, including belays with a redirectional, will only increase your improvisational arsenal. We do not recommend belaying off of an anchor with a traditional stitch plate or *tubular belay device* (like an ATC) because of the upward lock-off motion these belay devices require to create an effective brake.

HANDS-FREE

How to get *hands-free* is covered in the first step of escaping a belay, in chapter 3. This basically means tying off the climber so that as the belayer/rescuer you can use both hands to complete a task rather than maintaining a brake hand. There will be times throughout the rescue scenarios where it is possible to do something without getting both hands free first. This is certainly up to rescuer judgment. We recommend the conservative (and slower) approach at first, but as you get comfortable with the systems it might be preferable to maintain your belay with one hand and complete a few steps with the other.

Fig. 1-3. When creating a shelf, make sure to clip the carabiner in a way that includes a strand from each piece of protection used in the anchor, and have a carabiner (regardless of whether it is weighted) clipped through the master point.



ANCHORS

Multidirectional anchor. At least three solid pieces of protection, with at least one piece maintaining the integrity of the whole anchor against multidirectional pulls, including upward and sideways.

Directional anchor. At least three solid pieces of protection that are joined to create a solid equalized anchor, generally resisting a downward pull, though it might be oriented to resist an upward or sideways pull in certain situations.

Master point (MP). This is the term we use for the redundant, equalized, clip-in point of any anchor. We use the abbreviation "MP" when referred to repeatedly.

Shelf. When building an anchor it is possible to consciously create a *shelf*—a separate space to clip through just above the MP that can be as redundant and effective as the MP itself. This separate clip-in can help keep things organized and also helps keep ropes from binding up while raising or lowering. If one or two ropes are weighted and moving through carabiners next to each other, they create friction against each other and it becomes harder to move them. Physically separating the carabiners on the same anchor allows the rope to move more freely, thus reducing the loads on the anchor. *Important note:* A shelf must be equalized, and redundant; take care to clip through a section of cord coming off each piece of protection (fig. 1-3). Always keep a carabiner clipped through the MP even if that carabiner is not holding any weight; this carabiner safeguards against inverting the MP knot. A shelf should also not jeopardize the anchor in any way.

RESCUE OVERVIEW

A rescue is highly situation-dependent. The accompanying charts (figs. 1-4 and 1-5) are not foolproof, but they will help familiarize you with the different components of self-rescue and will help you visualize the rescue process. The charts are based on a rescue situation involving two people, one being injured. Because every situation is unique, continued improvisation and thought are necessary. Use these charts as a map to clarify and provide a basis for your thought process when entering a rescue situation and as useful reminders as you work your way through the scenarios in chapter 8 of this book.

RESCUING THE FALLEN LEADER


Is the ground easier to reach by descending?
YES
NO
Is less than half the rope out?
NO
YES
Tie off the climber. Ascend to begin patient care. Descend and free rope. Ascend to patient. Rope solo to good ledge. Set raising system. Descend to prep. Ascend and raise patient.
Is there more than one rope?
Lower climber to your ledge and begin patient care.
Top?
YES
NO
YES
NO
Rope solo to good ledge. Set raising system. Descend to prep patient. Ascend and raise patient.
Would it be easy to set up a knot-passing system (low pro can easily be removed)?
Tie off climber, ascend to begin patient care, set anchor, prepare tandem rappels, and return to initial ledge.
Is it possible to walk off?
YES
YES
NO
Tie off climber, set system to pass knot, and lower.
Are you on the ground?
NO
Continue by tandem rappelling.
Treat as low-angle rescue.
Begin rappel or lower sequence.

RESCUING THE FALLEN SECOND


Is it easier to lower or rappel to the ground than ascend?
YES
NO
Can you lower the climber to the ground or a safe ledge with the belay rope?
Tie off the climber. Set raising system. Descend to climber and begin patient care. Ascend and clean route. Raise patient to ledge.
YES
NO
Lower climber to the ground or safe ledge. Tie off climber and descend. Begin patient care.
Set counterbalance rappel. Take all gear. Descend and clean route to climber. Begin patient care.
Is it possible to walk off?
NO
On the ground?
Rope solo to good ledge and set raising system. Descend to prep patient and return to raise patient.
YES
NO
Establish anchor and either lower patient to ground passing a knot if necessary, or tandem rappel.
Treat as low-angle rescue

The Munter-mule-overhand a fundamental rescue knot



CHAPTER 2

Rescue Knots

In this chapter we focus on tips and tricks for tying a few knots commonly used for rescue (chosen in part for their simplicity and their familiarity to many people). There are of course plenty of other acceptable knots. Check out appendix E for additional knot references.

It is important to become proficient and confident with these ties so that when trouble hits you can concentrate on the epic at hand, not whether you tied your knot correctly. Practice tying these knots in both hands as well as in the dark. This may sound silly now, but it won't the first time you're rigging a system high on a cliff as night falls around you.

KNOT TERMINOLOGY

BIGHTS AND LOOPS

A *bight* is like a half circle; there is an obvious curve in the rope, but the rope strands do not cross one another. (See fig 2-1).

Fig. 2-1. A loop (left) crosses itself while a bight (right) remains open.



A *loop* is like a full circle; the rope strands *do* cross and the circle is closed. It can be tied anywhere along the rope. When a loop is in your palm, at the spot where the strands cross, one strand is considered the bottom strand (against your hand), and the other is the top strand (closer to your eyes).

WORKING END, STANDING END

When tying a knot, the *working end* is the side of the rope that leads to the active climber or is the section of rope used to tie the knot. The *standing end* is the side of the rope leading to the anchor, the inactive climber, or is simply the end that runs into your rope bag.

LOAD STRAND, BRAKE STRAND

After a knot is tied, the *load strand* refers to whichever strand of rope is actively holding the load (e.g., the climber). In the case of a belay setup, the *brake strand* refers to the side of rope breaking a climber's fall and/or the strand that will be fed through a belay device to lower a climber. These terms are often used instead of working end and standing end, though for ease of explanation we use both sets of terms.

KNOT COMBINATIONS

Munter-mule-overhand (MMO). The Munter-mule-overhand is a *releasable hitch* whose application is introduced in chapter 3, Escaping a Belay. The mule hitch must always be backed up, either with an overhand knot or with a carabiner; see instructions later in this chapter for tying both the Munter and the mule. When we refer to the setup repeatedly, we simply use the abbreviation MMO.

Prusik-Munter-mule-overhand (PMMO). This is a series of hitches tied with a cordelette: a Prusik hitch tied with one end (and attached to the rope) and an MMO tied with the other. Its application is explained in chapter 3, Escaping a Belay. Like the MMO, it is referred to throughout the book; we abbreviate it as PMMO. (See instructions later in this chapter for tying each hitch in this series.)

KNOT FAMILIES: LOOPS, ENDS, AND HITCHES

LOOPS

Loops form a continuous circle and can be tied anywhere along a rope. Changing the size of a loop is simple—just loosen the knot (no need to undo it!) then thread through the appropriate amount of rope to achieve the desired size. Knots that form loops discussed in this book include the figure eight on a bight, overhand on a bight, and the butterfly.

BENDS

As the saying goes, “bends join ends.” Examples of *bends* discussed in this book include the water knot, Flemish bend (aka figure eight bend), and the double fisherman’s. The tails of the knot exit in opposite directions. These bends are generally favored for ease of tying and security once tied.

HITCHES

Hitches have to be tied around something in order to maintain their form. Hitches have a huge role in rescue and include friction hitches used for ascending and descending lines. Any material (i.e., webbing, cord) routinely used as a friction hitch should be inspected frequently for wear due to the greater amount of abrasion it receives. Hitches covered include the clove, Munter, mule, klemheist, autoblock, Penberthy, Bachmann, mariner’s, Garda, and the Prusik.

KNOT TYING AND TIPS

DRESSING THE KNOT

A well-dressed knot is a correctly tied knot; it does not have any kinks or loose or unnecessarily twisted portions. It has also been "set" or snugged down with a good tug prior to loading. (See fig. 2-2.) Dressing a knot serves a variety of purposes: it makes the knot much easier to visually inspect and it eliminates the potential for loose bits to get snagged, which might loosen or undo the knot. Some argue that undressed kinked portions add unnecessary turns, thereby reducing the knot's efficiency (i.e., strength); others say this loss of strength is minimal, and indeed an undressed figure eight is still incredibly strong. Friction hitches in particular do not grip the rope correctly unless properly dressed. *Dressed knots* are also generally easier to untie.

Fig. 2-2. Dressed knot. Left: Dressed and set figure eight on a bight. Right: Knot is not dressed.

TAILS AND BACKUP KNOTS

Long tails and backup knots are used by many climbers to protect a knot's tail from slipping through and untying the knot as the knot is loaded and unloaded (a process known as *cyclical* *loading*). There is some value in using long tails and backups, but there are also some common misconceptions about them.

A rough guideline is that knot tails should be twice the length of the original knot. Having a few extra inches of tail also acts as a safeguard should your knot get snagged, and thereby inadvertently loosened.

A few climbing knots, such as many bowline variations, can loosen due to the effects of cyclical loading. These should be tied with backup knots. Slippery hitches like the mule also warrant a backup knot. The name of these knots says it all; they like to slip.

Water knots are subject to cyclical loading, but it takes such a high number of pulls for the tails to slip though the knot that it is not necessary to tie water knots with backup knots; long tails are adequate. It is a very good idea to periodically retie or, at the very least, inspect anything tied with a water knot.

Important note: To avoid redundancy, all knot-tying descriptions assume that readers will dress each knot and check that each knot is tied with adequate tail length.

WHICH KNOT TO USE?

Hopefully a variety of factors (and not just rote memorization) play into your decision of what knot to use when and where. Here are some considerations to help you choose the best knot depending upon the circumstances.

Strength. Is the knot strong enough for the job? Will it retain its strength despite the anticipated direction of pull? For example, a butterfly knot would be a better choice for three-way loading than an overhand on a bight.

Familiarity with the knot/ease of tying. This is a rescue—no time for mistakes or fiddling with difficult knots. For example, although slightly weaker than a figure eight, a bowline is typically much quicker to tie off around a tree (and is more easily adjustable) than retracing a figure eight follow-through.

Versatility. Is the knot easily convertible into a different knot or can it be used for a variety of purposes? Do you need versatility?

Compactness. Most likely you will not have an unlimited amount of rope at your disposal; the amount of rope that knots consume varies. For example, a figure eight on a bight consumes twice as much rope as a single bowline backed up with a Yosemite finish.

Ease of untying. You may not want to waste precious time untying stubborn knots. Is the knot easy to untie and adjust once it has been weighted?

KNOTS

WATER KNOT (AKA OVERHAND BEND, RING BEND)

Fig. 2-3. Water knot. The dark webbing retraces the overhand knot tied on the light webbing. The tails exit from opposite sides.



The water knot (fig. 2-3) is typically used to connect two pieces of webbing together to create an extension or to tie a runner. As with any bend, the two ends feed out from opposite sides of the knot. If the two ends exit the knot on the same side, you have retraced your way to an overhand on a bight. Make sure to set the knot tightly before loading; the tails have been known to slip under load when not properly set.

1. Tie an overhand knot 2 to 3 inches away from the end of a piece of webbing.
2. Bring the other end of webbing up to the knot's tail and retrace the overhand knot beginning from the tail side. The knot should be completed with the two ends exiting on opposite sides.

Fig. 2-4. Figure eight on a bight. A figure eight on a bight looks exactly like a figure eight follow-through. The difference is that with a figure eight on a bight you cannot tie the loop through something (like a belay loop) without a carabiner, while because of the retrace step in a figure eight follow-through you can.



FIGURE EIGHT AND FIGURE EIGHT ON A BIGHT

Considering that these are beginning climbing knots, their tying instructions have not been included. The figure eight and figure eight on a bight (fig. 2-4) certainly consume more rope than other knots, but they are also easier to undo than an overhand on a bight, for example; a consideration for heavy rescue loads. All members of the figure eight family can also be tied in webbing (it makes for a much stronger knot than an overhand; however, figure eights tied in webbing can be very difficult to untie).

A variation of the figure eight on a bight is a *figure nine*. A figure nine simply employs another wrap around the middle of the eight before inserting through the final loop. A figure nine, although messy looking, creates a bulkier knot, which can make skinnier cord that has been holding heavy loads (as in a rescue) easier to untie. Tests show the figure nine to be stronger than the figure eight.

FLEMISH BEND (AKA FIGURE EIGHT BEND)

A Flemish bend (fig. 2-5) is used almost exclusively with cord and rope, although it can certainly be tied with webbing (a bit messy and difficult to dress). As with a water knot, the tails exit the knot in opposite directions. This is what distinguishes a

Flemish bend from a figure eight on a bight or a figure eight follow-through. The Flemish bend is much easier to tie, adjust, and untie after being loaded than a double fisherman's, and it is a good knot for creating a quick, improvisational cordelette loop. Although a bit bulkier than an overhand knot (aka "eurodeath knot"), the Flemish bend is also good for linking two rappel ropes together since it is easy to tie and untie, strong, and has a relatively narrow profile.

1. Tie a figure eight 2 to 3 inches away from the end of a piece of cord or rope.
2. Retrace the figure eight with another strand of rope, taking care to initiate the retracing from the knot's tail, ensuring that the tails will exit in opposite directions.

Fig. 2-5. Flemish bend. The dark rope retraces the simple figure eight tied on the light rope. The tails exit in opposite directions.



Fig. 2-6. Double fisherman's. The light cord circles twice around the dark cord forming an X. The tail then slides under and out through the X (indicated by the arrow.) The two knots are pulled tight so that the two Xs are snug against each other.



DOUBLE FISHERMAN'S

The double fisherman's is popular for creating rescue loops (see chapter 1, "Equipment"). It also can be tied on the end of a rope as a stopper knot to avoid rappelling off the end of the rope or allowing the end of a rope to slip through a device when belaying or lowering. Some climbers also use this knot for linking two rappel ropes together. When used as a bend, a double fisherman's is tied on either side of the line and pulled together as shown in fig. 2-6.

1. Take one end of the rope and wrap it around the other rope (or the end of the same rope) in two complete circles. The first circle should be made moving away from you while the second circle comes back towards you, creating an X where the two circles cross.
2. Find the X, created by rope crossing over itself, and thread the tail under and through that X, exiting in line with the strand of rope you have tied your knot around. The tail should exit under and through the X away from you.

When joining two ropes together (or creating a loop out of cord), tie the same knot with the other tail. Bring the two knots snug up against each other and rotate until the two Xs are lined up. Cinch down to set.

Fig. 2-7. Munter hitch. Top: Step 1. Bottom: Step 2. Step 3 is to clip the carabiner around the two strands of rope directly above the carabiner as indicated by the arrow



Fig. 2-8. Building a Munter on a carabiner. Steps 2 and 3: Bring a bight of rope from behind the loaded strand and clip the bight into the carabiner as shown in photostrands of rope directly above the carabiner as indicated by the arrow.



Fig. 2-9. Loaded Munter. Note how the hitch rotates around the carabiner depending upon how the hitch is being used. Left: Munter is rotated for lowering. Right: Munter is rotated for taking in slack.

HITCHES

MUNTER HITCH

The Munter hitch is a versatile and quick hitch that can be used for lowering or belaying, as well as for rappelling in place of a belay device. The Munter is unique in that it has two positions (lowering and taking in slack) and depending on how the climber is weighting the rope (being lowered or climbing), the hitch will need to rotate between those two positions. Although the hitch's orientation can change, the load strand should be located on the spine side. Using a Munter does generate a large amount of friction but the friction of rope on rope is not of concern because the sections of rope rubbing against each other are constantly changing.

1. Place a loop of rope flat in your hand, the circle oriented away from you as shown in fig. 2-7.
2. Fold the loop over itself, toward you. The (formerly) top strand should now be sandwiched between two sections of the bottom strand.
3. Clip a carabiner around the two stacked strands.

Another handy way to tie a Munter is to build it directly on the carabiner; this is also an easy way to ensure that the load strand is tied on the spine side:

1. Clip a bight of rope in to a locking carabiner with the gate screwing downward.
2. Grab the unweighted strand of rope from behind the loaded strand and bring it around in front of the load strand.

3. Clip a bight of the unweighted strand in to the carabiner (fig. 2-8). You do not need to change your hand position or change the unloaded strand's orientation (e.g., don't twist it, etc.) to do this.
4. Make sure to set the knot in the correct position (so that the load strand is in fact loaded) before the climber weights the rope (see fig. 2-9).

MULE HITCH

The mule hitch allows a belay to be tied off, giving the belayer the ability to remove her brake hand from the rope and attain the hands-free position. Many knots work okay for this purpose, but the mule hitch is a reliable slippery hitch that is relatively easy to remove after loading. It combines well with a Munter, making it the hitch of choice, and is an important component of rope rescue.

Because it is a slippery hitch, the mule is always backed up. An easy and reliable backup is an overhand on a bight tied around the load strand with the working end. Another option, which uses much less rope, is to clip the loop (coming off the mule hitch) with a carabiner to the load strand (fig. 7-4 in chapter 7 shows this backup method).

TYING OFF A MUNTER BELAY WITH A MULE HITCH

1. While maintaining a safe belay, create a loop with the brake strand. The portion of the brake strand closest to the Munter must be stacked between the load strand and the standing end of the brake strand (the circle in fig. 2-10).
2. Make a bight of rope in the standing end of the brake strand ("2A" in fig. 2- 10), and push it through the loop you just created, making sure to travel in a direction that wraps the brake strand in a half circle around the load strand ("2B" in fig. 2-11).
3. Cinch the mule hitch down (fig. 2-12).
4. Tie a backup knot as close to the mule hitch as possible (fig. 2-13). A good backup knot is an overhand on a bight tied around the load strand with the mule tail. *Note:* To keep the mule and the backup knot as close to the Munter as possible, work on a plane perpendicular to the rope rather than pulling and tightening up and away from the Munter (see fig. 2-18, which shows the same tie-off with a belay device). Figure 2-14 shows a completed Munter-mule-overhand (MMO).

TYING OFF A MUNTER BELAY WITH A MULE HITCH

Fig. 2-10. Step 1 and beginning of step 2.



Fig. 2-11. Step 2: the brake strand makes a half circle around the load strand.



Fig. 2-12. Step 3.



Fig. 2-13. Step 4; arrow indicates the path for tying an overhand.



Fig. 2-14. Completed mule hitch with an overhand back-up tying off a Munter belay.



TYING A MULE HITCH ON A BELAY DEVICE

Fig. 2-15. Step 1: Note the sharp kink in the belay strand (1A).



Fig. 2-16. Step 2.



Fig. 2-17. Step 3.



Fig. 2-18. Completed mule hitch with an overhand backup tying off an ATC belay.



TYING A MULE HITCH ON A BELAY DEVICE

1. Using your fingers to maintain the rope’s braking position

(that sharp kink in the belay strand as it exits the belay device; “1A” in fig. 2-15), pass a bight of rope through the open space of the carabiner (fig. 2-15).
2. Twist that bight into a loop, taking care to stack the section of brake strand closest to the ATC between the standing end and the loaded climbing rope (dashed circle in fig. 2-16); pull more slack through if you need it.
3 and 4. Pick up at step 3 of tying off a Munter with a mule (fig. 2-17 and 2-18). Pull any slack out on a plane perpendicular to the rope and belay device (see arrow in fig. 2-17). This helps keep the backup knot close to the mule.

To release the mule, just work your way backward, but be careful! If using a belay device, make sure to maintain that sharp kink in the brake strand next to the device (see “1A” in fig. 2-15 and step 1 of tying a mule on a belay device) as you return the brake strand to its standard belaying position. (If the kink is not maintained you could lose belaying control as you undo the mule.) Warn your climber that he might feel a little pop as the mule is released.

CLOVE HITCH

The clove hitch is an effective knot for securing a line, weighted or unweighted, into a carabiner. Instead of using *daisy chains*, many climbers (especially alpinists, in their effort to climb fast and light) tie in to belay anchors with clove hitches, which are easy to adjust and untie. Unlike some other hitches, the clove hitch has the advantage of holding tight when just one strand is weighted. If weighted and unweighted repeatedly, the clove hitch can loosen and if not properly tightened it may creep up and potentially open the gate of a nonlocking carabiner. For this reason it is recommended to not leave clove hitches unattended and to use a locking carabiner.

As with the Munter, you should ideally tie this hitch so that the load strand is on the carabiner's spine side. Weighting a carabiner's gate axis can decrease the carabiner's strength considerably.

1. Take a bight of rope in either hand, leaving only a few inches of space between the two bights.
2. Rotate both bights half a circle in the same direction to create two loops.
3. Bring the two loops together, making sure to sandwich the two longer strands (that dangle down) together (fig. 2-19).
4. Clip a carabiner through the two loops.

Fig. 2-19. Clove hitch. Left: Step 3; bring the loop on the left in

front of the loop on the right. Right: Step 4; completed clove hitch clipped through the anchor's master point.



Fig. 2-20. Building a clove hitch on a carabiner. Bring a bight of rope from behind the load strand; create a loop by turning the bight in a half circle back toward the carabiner's spine, and then drop that loop into the carabiner. Note how the loop on the left is closed off on the opposite side of the rope than the loop on the right.



Fig. 2-21. Building a clove hitch on a carabiner. Clip the loop through the carabiner to complete the clove hitch.



The ability to build a clove hitch on a carabiner is a useful skill for a variety of situations. If you are belaying your follower on a Munter, the Munter can quickly be switched to a clove hitch (assuming your climber is in a safe, stable position). Additionally, tying a clove hitch directly on the anchor ensures that the load strand will be on the spine side of the carabiner. See figs. 2-20 and 2-21.

FRICTION HITCHES

Friction hitches are vital rescue knots used for ascending, descending, and holding loads at specific spots on a rope. The hitch can slide along the line but once weighted will grip the rope at that spot and hold its position on the line.

It is very important to always (yes, *always*) test your friction hitch prior to loading it for real to ensure that it grips and slides when necessary. Every rope is a little different. Newer ropes can be more slippery than older ones and so might need another wrap thrown on to make sure the hitch grabs. The number of wraps needed for any friction hitch also depends on the comparative diameter of the rope and the cord being used; the larger the difference the fewer the wraps. You may also find yourself adjusting the number of wraps if ropes are wet or snowy or if you are dealing with a large load. Hanging midair, slowly slipping, is not the place to realize you could have used another wrap in your friction hitch. *HMPE* materials (like Dyneema and Spectra sewn runners) are not recommended for friction hitches because of their low melting point and slippery texture.

PRUSIK HITCH

The Prusik hitch provides the tightest grip on the rope of all friction hitches. But that also creates its biggest downfall; it can be difficult to untie or slide after holding a large load. With the exception of laid ropes, which are rarely used by modern climbers, another advantage is that a Prusik does a great job holding a load in any direction. The two-wrap Prusik is adequate for many things but a Prusik hitch with three wraps (called an "improved Prusik hitch" by some) is recommended for rescue applications; the extra wrap creates more surface area for grabbing the rope. Throughout this book we simply use "Prusik hitch" to mean a three-wrap Prusik. Cord is the preferred material for tying Prusiks; however, nylon webbing can be used. With webbing you should use more wraps, and Prusiks tied in webbing are much more difficult to release once weighted.

1. Make a rescue loop with a 4-foot piece of 7-millimeter cord, connecting the two ends with a double fisherman's or a Flemish bend.
2. Hold one side of the loop in either hand, placing the knot in the other hand, and stretch the loop out to full length (fig. 2-22, left).
3. Bring your hands together around the rope, passing the knot through the inside of the loop as if you were putting on a luggage tag (fig. 2-22, right).
4. Repeat this process (for a total of three times), making sure to wrap in the same direction and always wrapping

through the middle of the loop (fig. 2-22, right).
5. Move your hand just a few inches off the knot to either side.
6. Pull the loop directly away from the rope, allowing the wraps to cinch down (fig. 2-23, left).
7. In order to properly dress the Prusik, you must sort the wraps over one another until there are no crisscrosses and they are all lying flat, tight in line on the rope (fig. 2-23, right). Picture a well-dressed Prusik as four straight teeth in the center with a large lower lip running in an uninterrupted crescent shape from left to right on the outside. Once the Prusik is loaded and bites down, these loops will shift somewhat. Should you need to change the Prusik's position on the line, unweight it, then loosen up the lower lip (or "brake bar") with your thumb. Now slide the Prusik to the desired new spot on the rope and weight as needed.

Fig. 2-22. Three-wrap Prusik. Left: Step 2. Right: Steps 3 and 4.



Fig. 2-23. Three-wrap Prusik. Left: Steps 5 and 6. Right: Step 7; completed and dressed Prusik.



To quickly remove the Prusik, grab the lower lip and pull straight out, away from the rope to which it is hitched.

It is important to emphasize with climbers new to friction hitches that you should not grab them; you should push them. With a Prusik, push it with your thumb from either above or below depending on your direction of travel. Grabbing the Prusik or wrapping your hand over it does not allow it to grip the rope. The best way to let the Prusik grip is to let go of it. In a panic a climber may forget to let go of the Prusik, his hand inadvertently keeping the Prusik open and causing him to slide down the line.

AUTOBLOCK HITCH

The autoblock is a releasable hitch that is quite similar to the Prusik both in form and function. It is a bit quicker to tie than a Prusik and is easier to remove, especially when weighted, but it does not grip as quickly or as firmly as a Prusik. Autoblocks should be used with caution in snowy conditions such as crevasse rescue. Compared to a Prusik it is easier for snow to get in between the looser wraps on an autoblock, loosening their grip on the rope and thereby decreasing the hitch's holding power.

Fig. 2-24. Autoblock. Left: Step 2. Right: Step 3; completed autoblock.



Fig. 2-25. Tying an autoblock with a Penberthy.



1. Make a rescue loop with a 4-foot piece of 7-millimeter cord (or 9/16-inch webbing), connecting the two ends with a double fisherman's, a Flemish bend, or a water knot.
2. Wrap the loop four to six times (depending on diameter of lines, conditions, and length of the loop) around the rope (fig. 2-24, left).
3. Bring the two ends together and clip a carabiner through

both ends (fig. 2-24, right).

To undo the autoblock, simply unclip one side of the loop from the carabiner and unwind.

An autoblock can also be tied using a strand of cord tied off with two overhand knots on either end. This single-strand version is called a *Penberthy*. Follow the same steps as described for tying an autoblock. Clip the carabiner through the two loops created by the overhand knots. See fig. 2-25. This is a great hitch for a third-hand *rappel backup,* discussed in chapter 4.

KLEMHEIST

The klemheist is almost identical to the autoblock but is generally constructed with fewer wraps and a different final step. Like the autoblock, the klemheist is much easier to release under load compared to a Prusik. According to tests, klemheists also have better gripping power than autoblocks. Unlike the other friction hitches already introduced, the klemheist will grab best in one direction, dictated by how it is tied.

1. Make a rescue loop with a 4-foot piece of 7-millimeter cord (or 9/16-inch webbing), connecting the two ends with a

double fisherman's, a Flemish bend, or a water knot.

2. Just like an autoblock, wrap the runner four to six times (depending on diameter of lines, conditions, and length of the loop) around the load strand. But make sure to leave more tail on the bottom portion of the runner.
3. Instead of simply bringing the two end bights together, feed the bottom end bight up through the top end bight (fig. 2-26, left).
4. Pull all the slack through and clip a carabiner into the bottom end bight (fig. 2-26, right). The klemheist will grip best when the bottom end bight is pulled downward.

Fig. 2-26. Klemheist. Left: Step 2, with Step 3 shown by an arrow. Right: Step 4; completed klemheist.



Fig. 2-27. Bachmann. Steps 1 and 2. Note the runner clipped through the carabiner and the arrow indicating the direction in which the runner should be wrapped.



Fig. 2-28. Bachmann. Step 3: Completed knot. Note how the runner exits directly off the carabiner, not off the rope.



BACHMANN

The Bachmann is another knot that can be used for ascension, with the advantage of the carabiner acting as a handle that can slide up and down the line. The Bachmann can be tied with either cord or webbing. Like the klemheist, the Bachmann catches best in one direction.

1. Clip a carabiner through the end of a runner.
2. Lay the carabiner up against the rope. Wrap the runner around the rope and the spine of the carabiner three to four times, moving down the carabiner's spine as you wrap but keeping the webbing or cord neat (fig. 2-27). The actual number of wraps will depend upon the diameters of your cord or runner and of the rope.
3. Finish the hitch off by wrapping the runner through the carabiner one last time, but not around the rope. The runner exits directly off the carabiner (fig. 2-28).
4. Clip in to the runner. The carabiner acts as a handle to slide the hitch along the line but is not load bearing.

GARDA HITCH

The Garda hitch is a type of friction hitch tied with just the climbing rope and two carabiners. The rope can move one way through the carabiners; it is blocked from moving the other way. The Garda, when combined with an additional friction hitch, provides another way of ascending a line (see chapter 5, Ascending). The Garda can also be incorporated into a simple raising system, although it has the disadvantage of not being reversible or easily releasable under a load. The Garda works best with carabiners of the same size. If tied with nonlocking carabiners the Garda should be attended to avoid the rope creeping up and slipping through a gate after repeated loading and unloading.

Fig. 2-29. Garda. The left rope strand will hold the load while the right strand can be pulled through the carabiners.



1. Clip a bight of rope through two carabiners.
2. Make a loop on one side of the rope.
3. Clip the loop into the carabiner farthest from the loop. The rope will be pulled freely through this side. The side that holds the load *does not* receive the additional loop of rope and

is the side of rope that you do not want slipping (e.g., your load if you are hauling, or the remaining portion of line you have yet to ascend). See fig. 2-29.

MARINER'S HITCH

The *mariner's hitch* is a releasable hitch used to make a system reversible, just like the Munter-mule combination. The mariner's is attached to the anchor on one end, and on the other end is some sort of friction device or knot in the climbing rope. The mariner's can transfer a load (lowering it a short distance), but should not be released and then relied upon as a belay, whereas the Munter-mule setup can be. Care should be taken to carefully tie (or clip) off the mariner's so it does not slip over time. Both cord and webbing are acceptable materials for tying the mariner's (although HMPE sewn runners are not recommended).

1. Attach a cordalette (or runner) to the climbing rope with a friction hitch or to a knot on the rope.
2. Bring the cordalette back up to a locking carabiner located on either the anchor's master point (MP) or shelf. Wrap the cordalette around the carabiner. (An alternative is to thread a

Munter hitch around the carabiner, creating a Munter-mariner’s combination; see fig. 2-31, left.)

3. Wrap the cordalette back around itself (between the climbing rope and the carabiner) at least five times (fig. 2-30).
4. Slip the end of the cordalette through the two strands of the cordalette you have just been wrapping. To keep the mariner’s from coming undone, tie the mariner’s tail unto a loop and bight of the mariner’s and clip the loop around the climbing rope with a carabiner (fig. 2-31, left).

Fig. 2-30. Mariner’s hitch. Steps 1 and 2: The cord is attached to the rope with a klemheist and goes back up to a carabiner, around which the cord is wrapped. Step 3: Loop the cord around its two strands at least five times, as indicated by the arrow



Fig. 2-31. Mariner's hitch. Left: Completed knot. Note how the tail is threaded through the two strands of the cord ("A"), with the tail clipped off to the climbing rope with a carabiner (Step 4). Right: Munter-mariner's. The setup is shown tied with a rescue loop and a separate piece of cord versus the single continuous strand in the left example.



To release the mariner’s, slowly undo the wraps and allow slack to slowly feed through the system until the load is transferred back to the climbing rope.

If you have a long enough section of cord you can tie a mariner's with one piece of material. Double the material up (creating a large bight) so you have two strands. Tie a friction hitch at the top of the bight and use the tails to tie a mariner's hitch back at the anchor. Figs. 2-30 and 2-31 (left) show this method.

"A climber's normal gear rack generally contains all the gear necessary for a rescue."



ROPE MANAGEMENT

Good rope management becomes especially crucial in rescue. As you bring multiple strands back to the anchor make sure they are attached in an order and place on the anchor that leaves them easily accessible—not caught up by the weight of other ropes or gear, and free of getting tangled.

TABLE 2.1 SUMMARY OF RESCUE HITCHES

Hitch	Use	Pros	Cons
autoblock	■ Ascending and descending a line ■ Grabbing the rope at a fixed point on the line ■ Somewhat releasable hitch	■ Very quick to tie ■ Moves up and down the line with greater ease than a Prusik ■ Can be loaded in either direction ■ Relatively easy to release under load	■ Weakest gripping strength of presented friction hitches ■ Sometimes slow to grab; needs to be set carefully ■ Use with caution in snowy conditions ■ Abrupt load release
Bachmann	■ Ascending and descending a line ■ Grabbing the rope at a fixed point on the line	■ Good grip strength especially in one direction ■ Carabiner can be used as a handle to slide the hitch	■ Weighting the carabiner handle can also cause the hitch to slip ■ Less grip than a Prusik ■ Need webbing or cord and a carabiner to construct
Garda	■ Works like a ratcheting Prusik in a raising system ■ Can be used for ascending	■ Easy hitch to tie with practice ■ Requires minimal gear (two carabiners) ■ Has a very strong grip; creates a lot of friction	■ Not releasable under load ■ Can be difficult to pull rope through due to high amount of friction
klemheist	■ Ascending and descending a line ■ Grabbing the rope at a fixed point on the line	■ Moves up and down the line with greater ease than a Prusik ■ Gripping strength is high but not as strong as a Prusik ■ Sometimes able to release under load	■ Grips best only in one direction ■ Use caution in snowy conditions
mariner's	■ Load releasing hitch for short load release transitions like escaping a belay or passing a knot	■ Fast and easy to tie ■ Can be effectively tied with both webbing and cord ■ Lots of friction for controlling heavy loads	■ Must be carefully clipped off to stay secure ■ Uses a lot of material to tie ■ Can only let out loads; can't belay loads in
Munter	■ Belaying climber in and out ■ Rappelling	■ Can belay rope in and out ■ Lots of friction for controlling heavy loads ■ Easy way to improvise a rappel	■ Can put twists in rope, especially if used repeatedly
mule	■ Releasable tie-off for a belay	■ Releasable under load	■ Easily releasable; must be backed up
Prusik	■ Ascending and descending a line ■ Grabbing the rope at a fixed point on the line	■ Can handle the weight of very large loads without slipping ■ Can be loaded in either direction	■ Once weighted, does not slide up and down the line as easily as other friction hitches ■ Very difficult to release under load

How many of your climbing partners are confident and competent at escaping a belay ?



CHAPTER 3

Escaping a Belay

The *belay escape* is a fundamental skill necessary for the majority of rescues ranging from the simple to the serious; in order to effect a rescue, a rescuer must be freed from the responsibilities of belaying. It is also a good starting point for talking about rescue systems. We use the process of escaping a belay to introduce a number of skills.

Sometimes it is possible to move into a lowering or raising sequence before completing all steps of a belay escape. It is important to know the complete system, however, before combining systems or skipping steps.

Throughout the belay escape the climber's position on the rope is maintained. The end result is a system that is releasable under load and still useable in further steps as a belay. Returning to belay mode is often a necessity once you have formulated a plan; maybe your partner needs to be lowered or, after assistance, is able to continue climbing. Either of these steps (as well as raising and counterbalance rappelling) require that the system be releasable.

WHEN BELAYING OFF YOUR BODY

Below we describe two ways of escaping a belay if you are belaying a leader off your body with an ATC (or any tubular belay device). In subsequent sections we then cover escaping a belay when belaying directly off the anchor and when using a *redirectional piece* off the anchor.

ESCAPING A BELAY: STANDARD SEQUENCE

1. Get hands-free: Tie a mule hitch and an overhand backup on the load strand between your ATC and the climber (fig. 3-1); or, wrap the load strand around your leg multiple times to maintain the brake on the belay (these are called *"leg wraps";* take great care when doing your leg wraps—you do not want to introduce excess slack into the system). When tying the mule-overhand, pay special attention to maintaining a good pinch on the brake strand as you negotiate the bight of rope through the ATC; transfer your brake hand to the other side of the belay carabiner and keep the brake locked off while tying the mule-overhand. Although you are not yet out of the belay setup, once the mule-overhand is tied your hands are relieved of belay duty (you are "hands-free"), enabling you to use your hands for other tasks while your partner is securely held by the mule hitch (or the leg wraps).
2. Using a Flemish bend, tie a long cordelette into a loop.
3. Using this loop, tie a Prusik hitch onto the load strand of the climbing rope (fig. 3-2); keep the loop's knot close to the Prusik hitch. (This is the Prusik part of tying a PMMO.)

4. Next, reach back to the anchor and clip a locking pearabiner through the master point or shelf with the pearabiner's gate oriented down and out (fig. 3-2).
5. Using the long strands dangling from the cordelette, tie a Munter onto the pearabiner you just added to the anchor (this is the Munter-mule-overhand part of tying a PMMO). Pull in all the slack and then reset the Munter into the lowering position by pulling on the load strands of the cordelette so that the Munter rotates, and tie a mule hitch with an overhand backup (fig. 3-2).
6. Push the Prusik hitch along the rope toward the climber until the slack between the Prusik and the MMO is taken up (fig. 3-3). Be careful to not push the Prusik too far out of reach. If there is still excess slack in the cordelette between the two knots, go back up to the Munter-mule, undo the mule, and take in the excess slack using the Munter.
7. Carefully undo the mule-overhand on your ATC and let slack through the ATC, transferring the climber's weight onto the cordelette—you should not have to lower the climber much (fig. 3-3).
8. Reach back to the anchor and clip another locking carabiner through either the MP or the shelf, oriented down and out (fig. 3-4).
9. Bring the brake strand of the climbing rope back to the newly attached carabiner and tie a Munter onto the carabiner

(fig. 3-4).

10. Once the Munter is tied with the brake strand of the climbing rope, bring in most of the excess rope between the Munter and your ATC, leaving just enough slack for unclipping from the device.

11. Maintaining a hand on the brake strand coming off the Munter you just tied, take your ATC off the rope.

12. Pull in all the excess slack in the climbing rope via the Munter. Finish this step by tying a mule hitch, snug against the Munter, and an overhand backup (fig. 3-5).

13. Release the mule-overhand tied with the cordelette and use the munter to transfer the weight from the cordelette onto the climbing rope (fig. 3-6). Once the weight is fully on the climbing rope, detach the cordelette from the rope.

ESCAPING A BELAY

Fig. 3-1. Step 1. Note: climber is tied into the anchor with a clove hitch.



Fig. 3-2. Steps 3, 4, and 5 (Step 2 not shown.)



Fig. 3-3. Steps 6 and 7.



Fig. 3-4. Steps 8 and 9.



Fig. 3-5. Step 12 (steps 10 and 11 not pictured).



Fig. 3-6. Step 13.



Fig. 3-7. Completed.



All you should be left with is an MMO tied with the climbing rope onto the anchor (fig. 3-7). Now you are ready to execute the plan for helping your partner.

ESCAPING A BELAY USING A RESCUE LOOP

This second way of escaping a belay is a great method if you are far from the anchor and/or do not have a long cordelette. This method has the advantage of only using one short rescue loop (with a Prusik hitch) and a couple of locking carabiners. It is quick and easy to adapt to many situations. Be careful to tie off the main climbing rope to the main anchor to finish this belay escape, especially if you are using a clove hitch as your personal anchor tie-in.

ESCAPING A BELAY USING A RESCUE LOOP

Fig. 3-8. Step 1. (The "3" indicates the strand of rope that will be used to complete Step 3.


1
3

Fig. 3-9. Steps 2, 3, and 4. The mule-overhand has yet to be tied.



Fig. 3-10. Steps 5 and 6



Fig. 3-11. Step 7 completed.



Fig. 3-12. Step 8



Fig-3-13. Escaping a belay using a rescue loop, completed.



1. Get hands-free by tying a mule hitch and overhand backup (fig. 3-8), or do some leg wraps with the load strand; see step 1 of "Escaping a Belay: Standard Sequence," above.
2. Place a rescue loop (with a Prusik hitch) onto the load strand just above the MMO, and clip a carabiner (locking, if you have it) onto the rescue loop (fig. 3-9).
3. Reach back to your tie-in at the anchor. (This is assuming the belayer is tied in to the end of the rope and then tied in to the anchor with a figure eight on a bight or a clove hitch.) Take the free strand of your tie-in (not the strand attaching you to the anchor) and bring it forward to the carabiner clipped through the rescue loop (fig. 3-9). If you can't reach your anchor, grab your rope stack and run through that until you get to the other side of your anchor tie-in.
4. With the free strand, tie a MMO onto the rescue loop carabiner (fig. 3-9).
5. Slide the rescue loop Prusik hitch along the rope toward the climber to take out the slack (fig. 3-10).
6. Transfer the load onto the rescue loop Prusik by letting slack through your ATC (fig. 3-10).
7. Take the ATC's brake strand back to the anchor and tie a Munter onto another locking carabiner clipped directly into

the anchor (fig. 3-11). Do not take your ATC off until the Munter is in place. Once the ATC is removed, bring in the excess slack and tie off the Munter with a mule-overhand.

8. Undo the mule-overhand tied on the rescue loop's carabiner. Using the Munter, slowly transfer the weight from the rescue loop onto the Munter-mule tied on the carabiner coming off the anchor (fig. 3-12). Once the weight is fully transferred, you can undo the Munter connected to the rescue loop, and remove the rescue loop from the load strand (fig. 3-13).

IMPROVISE: ESCAPING A BELAY USING A RESCUE LOOP

Here is a third belay escape method to practice. It is just another variation on the theme but is a very quick escape needing only one rescue loop, one MMO tie-off, and a few carabiners.

Follow the steps in "Escaping a Belay Using a Rescue Loop," but instead of using a Prusik hitch, use an autoblock (step 2). When tying the rope to the rescue loop carabiner in step 4, use a clove hitch or a figure eight on a bight instead of a Munter-mule. To release the load back to the main tied-off climbing rope in step 8, just pull on the top of the autoblock coils to get the autoblock to release. Be careful! The autoblock often does not release gradually. If there is a lot of slack to transfer, it might shock the system. Experienced climbers could do this while maintaining a brake hand as well.

REVIEW OF ESCAPING A BELAY

1. Get hands-free.
2. Transfer the climber's weight to the anchor.
3. Move the main belay to the anchor and tie it off.
4. Remove the cordelette or rescue loop.

WHEN BELAYING OFF THE ANCHOR

Let's first work through belaying with a Munter hitch off the anchor, and then we'll take a look at some of the other belay devices on the market.

DO YOU NEED TO BEEF UP THE ANCHOR?

Depending on the quality of your anchor, your anticipated direction of pull, and what your next steps are, you *may* need to take the time to beef up the anchor before embarking on a rescue. Hauling, for example, exerts a much larger amount of force on an anchor compared to the forces of rappelling.

If you are simply adding to an already existing multidirectional anchor, hopefully you will be able to work the new points in with some creative sling craft. Double, triple, quadruple up slings; tie knots in runners; adjust water knots in webbing—whatever!

If you are looking at tying a lead climber off on a minimal anchor (like a single upward directional pull piece incorporated into a larger anchor), you will need to take the time to strengthen the anchor or create a new one (if you have extra gear). Most likely the leader will have all the protection pieces, though you may have slings and cordelettes. If lowering your leader is not an option (e.g., she has led past the rope's halfway point, or she has traversed or climbed over a large overhang), you may need to ascend or rope solo up to retrieve some of the pieces your leader placed lower down, to use in reinforcing the anchor. See chapter 5, Ascending.

First, take the same initial step of getting your hands free. If the anchor needs to be reinforced for an upward pull, try to change the webbing or cord in the anchor for better direction of pull. It may also be possible to reposition a piece or two for better upward pull. Caution: Do not jeopardize your security! Make sure the anchor still protects you from a fall. After you reinforce the anchor, pick up where you left off in the process of escaping the belay; your hands are already free, now it is time to escape the belay.

ESCAPING A BELAY USING A MUNTER HITCH

Belaying directly off the anchor with a Munter hitch is a lightweight and simple way to belay your partner. This method makes escaping the belay unnecessary, as the belay is already on the anchor and not your harness. The disadvantages are (1) that it is not acceptable for belaying a lead climber; (2) you are belaying directly off the anchor (only a problem if your anchor is questionable or poorly positioned); and (3) many people complain about the kinks that belaying with a Munter creates.

Follow these steps for escaping a belay using a Munter hitch:

1. Make sure the Munter is in the lowering position, with the

climber weighting the rope.

2. Tie a mule hitch and backup knot against the Munter. With that simple step you have both freed your hands and escaped the belay.

ESCAPING A BELAY USING A SELF-BLOCKING BELAY DEVICE

A self-blocking belay device allows a lead climber to give her second a belay while maintaining just a light hand on the brake strand. This is extremely useful when climbing long multipitch routes. The slack generated by the follower can be pulled in through the belay device but not pulled out; when weighted, the device and carabiner lock down on the rope. This allows the belayer to use her hands for other tasks (putting on another layer, getting food and water, or reorganizing gear for the next pitch) while still giving a secure belay. *Note:* manufacturers recommend that a light brake hand should be maintained even with a self-blocking device. Examples of such devices are the Trango B-52, Kong GiGi, New Alp Plaquette, and the Petzl Reverso.

As with belaying off the anchor with a Munter, the majority of your work escaping the belay is already done. By virtue of belaying with a self-blocking belay device your hands are already free and you have escaped the belay. The only step left to do is back up the system. Tie a mule-overhand or a backup knot onto the main line as a backup (fig. 3-14 shows a figure eight on a bight as the backup knot).

Fig. 3-14. A self-blocking belay device backed up by a figure eight on a bight ("A"), clipped off to the anchor.



ESCAPING A BELAY USING LOCKING-ASSIST

BELAY DEVICES

The Trango Cinch and Petzl GriGri are popular belay devices with locking-assist mechanisms and are commonly used at crags and on big walls. With these, it is possible to give a lead or following climber a solid belay. (A light grip should be maintained on the brake strand at all times.) Be aware that these devices can slowly “ooze” out small amounts of slack when holding a load over a longer period of time. Therefore it is necessary to put in some sort of backup while you escape the belay. Tie a mule-overhand as you would if you were belaying with a regular device, or tie a backup knot, like a figure eight on a bight, and clip it to the anchor.

Fig. 3-15. In some situations, some climbers prefer to belay through a redirectional piece off the anchor.



Fig. 3-16. Escaping a belay using a redirectional. Steps 1 and 2 completed.



Fig. 3-17. Escaping a belay using a redirectional. Step 3 completed; belayer is in the process of completing step 4.



WHEN BELAYING USING A REDIRECTIONAL PIECE

For more comfortable positioning, a redirectional piece might be preferred to directly belaying off the anchor especially if you do not have a self-blocking belay device and do not like using a Munter (fig. 3-15). Using a redirectional piece multiplies forces on the anchor (a 2:1 ratio of *force* is created) versus belaying directly off the anchor, so make sure the anchor and rock quality are bomber.

1. Get hands-free (fig. 3-16); see step 1 of "Escaping a Belay: Standard Sequence."
2. The PMMO step: Using a cordelette, set a Prusik on the load strand (leading to the climber). Tie a MMO with the cordelette onto a new locking carabiner clipped into the anchor's master point or shelf (2 on fig. 3-16).
3. Lower the climber's weight onto the Prusik and tie a MMO with the climbing rope to a locking carabiner on the MP (fig. 3-17). Simply let slack through your belay device to give enough slack to create the MMO.

4. Transfer the weight back onto the climbing rope with the Munter tied with the cordelette and then remove the PMMO (fig. 3-17).

PRACTICE: BELAY ESCAPES

Practicing belay escapes is done much more effectively with a partner, but you can also use a heavy backpack if you can't find a willing guinea pig. Regardless of how confident you are, provide your guinea pig with a backup your first few times around. This can be done several ways:

1. If you have enough slack, you can tie the other end of the rope directly to the anchor and dangle it back down to your partner.
2. Have your partner tie in to the rope you will be practicing on and also *tether in* to the dangling line using a friction hitch. Leave enough slack so that you feel your partner's weight, but not so much that she would drop too far should you make a mistake.

If you do not have enough slack to drop down, you will need a second rope and preferably another anchor to help keep things clear and organized. Your partner can attach herself to the second line with a friction hitch, as described above.

Take the time to practice on a bottom anchor as if belaying a leader *and* up on the wall as if belaying a follower. Work your way up to practicing this on a hanging belay. Trying to escape a belay hanging in a harness is much more difficult than escaping a belay while standing on solid ground.

Many successful ascents have been soured by descents gone awry . Pay just as much attention to how you' ll get down as how you' ll get up.



CHAPTER 4

Descending

There are many different ways to descend, all of which are situation-dependent. In this chapter we discuss the important logistics, steps and considerations unique to lowering, rappelling, *tandem rappelling*, counterbalance rappelling, and pick-offs.

LOWERING

If the ground is close, lowering is usually the fastest way to get your partner (or partners) down in a hurry—no rappel ropes to deal with threading or throwing. Lowering can also create a viable exit for a follower unable to negotiate a tricky section of a route or for someone who has fallen into a crevasse and is able to walk out the bottom. Described below are a few different configurations to consider, dependent upon the climber's position as either leader or follower.

LOWERING MORE THAN ONE ROPE LENGTH

To lower from the top of a climb, set an anchor if you do not already have one, put the climber on belay on the anchor, and lower him down. This is a great technique if it is very windy and you are worried about your ropes getting stuck or your climber's ability to rappel.

Here is a step-by-step way to lower your partner two full rope lengths:

1. Tie two climbing ropes together (Rope A and Rope B).
2. Have your partner tie in to the end of Rope A. Tie the end of Rope B in to the anchor.
3. Tie a Munter to the anchor with Rope A.
4. On Rope B (just after the knot with Rope A) pre-rig a Munter-mule-overhand (MMO) clipped in to the anchor or shelf.
5. Lower your partner on Rope A until you run into the knot with Rope B. Have your partner unweight the rope by grabbing onto the rock, standing in the snow, etc. If your partner can't unweight the rope in this step, you will have to pass the knot (see chapter 7, Passing Knots).
6. Untie the Munter on Rope A, allowing the pre-rigged, tied-off MMO on Rope B to take the load.
7. Have your partner reweight the rope.
8. Remove the mule-overhand on Rope B and continue lowering your partner on Rope B's Munter.
9. To remove your partner from the system, she will have to

either be on the ground or will have to make an anchor and clip in to it.

10. Your partner unties from Rope A so you can pull it up and do two double-rope rappels or a single rope rappel with a knot pass to reach her.

LOWERING WITH A SELF-BLOCKING BELAY DEVICE

Lowering a follower or providing slack on a self-blocking belay device like a Reverso or GiGi is not as easy as with a tubular belay device or a Munter hitch. (With a self-blocking belay device you will be belaying directly off the anchor.)

Fig. 4-1. Lowering with one follower using a self-blocking belay device: Step 1.



Fig. 4-2. Lowering with one follower using a self-blocking belay device: Step 2.



Fig. 4-3. Using body weight to release a self-blocking belay device.

If your partner is not able to unweight the rope, follow the manufacturer's recommendations for lowering. Most devices require a cord to be attached to either the device or the blocking carabiner and then carefully levered to release the block. Each device is slightly different, so know your gear and follow the recommendations of the manufacturer.

LOWERING WITH ONE FOLLOWER

Let's first look at providing slack when belaying just one follower, using the Petzl Reverso in this example.

1. Girth-hitch a sling through the large metal loop on the Reverso. Clip a carabiner into the master point's (MP) shelf. Drape the sling through the carabiner (fig. 4-1).
2. Create a block and tackle by weaving the sling back and forth between the large loop on the Reverso and the carabiner (fig. 4-2). After a few wraps you should have enough leverage to pull down on the sling to release the belay device.

Important note: Remember to back the system up with a Munter tied with a carabiner on your belay loop; you are, after all, releasing your partner's belay. With the Munter you can feed out slack and lower your partner.

A variation on the above is, instead of doing a block and tackle, to use a long sling (or girth-hitch slings until you achieve the desired length) and step into the sling using your body weight to release the device (fig. 4-3). Again, remember to back the system up with a Munter and carabiner off your harness.

LOWERING WITH TWO FOLLOWERS

Say you are belaying two climbers on a self-blocking belay device; one needs slack while the other one wants to continue climbing. How will you provide slack to one without lowering the other? (The decision to belay two followers climbing at the same time is an advanced climbing technique with a variety of factors that need to be considered before implementing, which are outside the scope of this book. To learn more consult appendix D, Continuing Education).

1. Tie a mule overhand or a backup knot (clipped to the anchor) in the strand of rope going to the climber who does *not* wish to be lowered (fig. 4-4).
2. Lower the climber following your device manufacturer's recommendations. Make sure to provide slack to the correct side of the system—the climber who wanted slack in the first place. Remember to back the lower up with a figure eight on a bight clipped to the MP or the Munter clipped to your belay loop depending on the length of the lower.
3. Once you have lowered your climber to the desired spot, tie a backup knot (clipped off to the anchor) or a mule overhand.
4. Carefully undo the backup knots while maintaining a hand

on the brake strands. Make sure the belay device has re-engaged and then let her know that she can climb again.

Fig. 4-4. Lowering with two followers. The light rope (right) holds the climber who does not *want to be lowered. This light rope is tied off with a mule overhand. A block and tackle is set up on the dark rope to lower the second climber.*



LOWERING A LEADER

Lowering a leader is typically the fastest and simplest way to get your partner out of a tricky situation or help him with injuries.

LESS THAN HALF A ROPE LENGTH OUT

The easiest lowering situation involves a leader who is less than half a rope length up the next pitch, who needs help. If possible have your partner reinforce the piece of gear he is hanging on. Then just lower the lead climber back to the ledge or ground where you are. Careful! The lead climber can't be more than half a rope length up the route.

If the leader traveled over a roof or traversed to one side, it might be hard to get him back to the belay ledge. Try throwing excess rope or a long cordalette to him, then pull him in or have him help pull as you lower.

IMPROVISE: MUNTER POP

This useful rescue trick is a way to remove a loaded Munter from a carabiner. The pop can be used in a variety of situations. In this example it is being used to lower someone two rope lengths.

Tie the patient into the end of line A. Tie one end of line B to the anchor. Tie line B and line A together. On the MP put line B on belay (with a belay device or Munter hitch) just after the knot with line A and tie it off with a mule-overhand. Attach a two-foot sling to the MP and clip a locking carabiner to the end of the sling. Tie a Munter hitch in the end of line A attached to the patient and clip it to the locker on the sling. You are now ready to lower the patient off the Munter. Continue lowering the patient until all of line A is paid out. The tied-off belay device on line B is holding the load. The knot between the ropes is between the belay device and the carabiner with the Munter. Now it is time for the Munter pop. Open the locking carabiner that has the Munter and pull the loaded line out of the gate. Let the gate close. If the carabiner does not flip around on its own, just bang it and it should pop and flip around. You can now unclip it from around rope A. Take out the mule-overhand backup and start lowering line B through the second Munter hitch.

To use the Munter pop you must have the first Munter loaded from both directions—in other words you must have a load hanging from the Munter and the brake strand (the side of the rope going up to the knot linking the two ropes) must be fully loaded and tied off as well.

The Munter Pop set for the pop. The second rope is tied off and holding the load. Unclip the Munter strand and you are ready to lower on the second rope.



If he is unable to help pull himself in, and he will not end up back on the ledge where you are, you will have to escape the belay. Ascend the line and attach a carabiner and sling to his side of the rope as soon as you can reach it (you do not necessarily have to ascend all the way up to him, but you do have to reach the side of rope that he has fallen onto). Descend back to the belay ledge and pull him in to the anchor as you lower. Be aware of any ledges the leader might hit as he is lowered. (See chapter 5, Ascending to a Hurt Leader, for details.)

MORE THAN HALF A ROPE LENGTH OUT

The hardest lowering situation is if the leader is more than half a rope length out. If possible have the leader reinforce the piece of gear he is hanging from, ideally creating an anchor into which he can clip himself and the climbing rope. Now escape the belay and ascend up the line. (See chapter 5, Ascending.)

If you have a second rope, you may be able to escape the belay and rope-solo or ascend the line a bit to remove enough of the low protection so that you will be able to lower him back to the belay ledge (or ground) using the two ropes tied together. Removing the low protection allows the knot linking the two

ropes together to travel up toward the leader without getting stuck in the protection carabiners. Careful! Do not remove protection that might jeopardize the leader. He is hanging on one piece at the top of the system and a few pieces should be left to back that one up. You will
have to pass the knot linking the two ropes as you lower the leader.

If you are uncomfortable removing your leader's pieces in order to allow the knot pass during a lower (perhaps he ran the pitch way out and there are just a few pieces to begin with), you will need to ascend or rope solo up to him.

RAPPELLING

Rappelling has multiple applications in a self-rescue scenario: it is used in tandem rappelling, counterbalance rappelling, and in the related topic of pick-offs. Let's first take a look at some common rappelling conundrums and solutions. Much of this first section lists some simple ways to avoid needing a rescue in the first place. Many climbers, especially alpine and traditional climbers, will testify that the majority of their rope mishaps have occurred while rappelling.

MANAGING RAPPEL ROPES

Stuck rappel lines are many climbers' public enemy number one. They have a sinister way of turning a nice outing into an epic! Here is a list of alternatives to simply throwing rappel lines—ideas worth considering, especially if you are rappelling a section where the rope could get easily snagged in deep cracks, on horns, bushes, or chicken heads, or be blown off course by strong winds. If you are rappelling a clean steep face or an overhang, you are less likely to run into problems.

RAPPELLING ON A MUNTER

In addition to being a way to belay, the Munter also provides an easy way to rig yourself either on a single- or double-strand rappel. When using two strands, just tie one big Munter with both strands at the same time (fig. 4-5). To minimize twists in the rope, keep your brake hand oriented directly in line under the carabiner and the Munters rather than off to the side.

Fig. 4-5. A two-strand Munter ready for rappelling. Caution! Note how the brake strand runs right next to the carabiner's gate. In positioning your brake hand take care that the brake strands do not run across the gate. Depending upon your carabiner's orientation the ropes could inadvertently unscrew the locker.



These tricks also have important rescue application: you do not want to further injure a patient by dislodging rocks, hitting him with airborne ropes, or risk a panicky climber grabbing the end of your rappel line, thereby inadvertently providing an unneeded *fireman's belay* (explained later in this chapter).

THE DIRECTED THROW

This method works well if it is not too windy and there are not too many things for the lines to get hung up on.

1. Set up the rappel as usual. Tie a knot near the rope's midpoint (or if a double-rope rappel, on one side of the knot linking the two ropes together) and clip that knot in to the anchor. This knot keeps the rope's midpoint in position while you throw the rope down. Otherwise the weight of thrown ropes can adjust the midpoint; you don't want to realize midrappel that your rope ends are uneven!
2. Make a set of very tight coils with each side of the rope—it works best to split each side into a set of anchor coils (the bit of rope from the anchor to about halfway to the end of the rope) and a set of end coils (end of the rope to about halfway to the anchor).
3. Overhand-throw the anchor coils directly where you want the line to go (or modify the direction to compensate for

wind).
4. Throw the end coils based on what you learned with the first throw.
5. Repeat with the other side of the rappel ropes.
6. Untie the knot that keeps the midpoint in place and rappel.

THE HOLSTER METHOD

1. Carefully flake out each side of the rappel line separately, as if making a butterfly coil. Make sure that the end of the rope is on the bottom of the pile.
2. Girth-hitch a sling to a gear loop on either side of your harness.
3. Face the anchor and, while holding up the far side of the sling, lay the stack of rope into the sling at approximately the sling's midpoint.
4. Close the sling off by clipping the far side of the sling into a carabiner attached to the same gear loop you girth-hitched initially.
5. Repeat with the other side.
6. As you rappel, the rope will feed out of these holsters (fig. 4-6). Sometimes the rope gets tangled. Take a second to undo

the snag and then keep rappelling. This method works well, though remember that some rope management must be done as you descend. With practice it is possible to set the holsters up with rope coils that will not tangle as easily. Be careful allowing a novice to do this. Use a rappel backup!

Fig. 4-6. The holster method. Each side of the rappel rope is neatly coiled and stored in holsters.

THE BACKPACK METHOD

1. Starting with both ends of the rappel line, create a stack inside the backpack. Do not pack the backpack so tightly that rope will not feed out freely as you rappel.
2. As you rappel stay ahead of the game by keeping a few feet of slack in the line between your belay device and your backpack (otherwise you will be caught fighting gravity with a taut line). Maintain your rappel with one hand and pull slack from the backpack with the other.

KEEPING ROPES FREE

Here are some other tips and tricks for good rope management and what to do when faced with stuck ropes.

Important Note: Do not rappel below any stuck section of your rope! Pause as you approach from above on rappel to free any stuck portions of rope.

- If the ropes run over an edge, think about extending the rappel even if this means leaving a sling behind; it could be well worth it, particularly if you’ve tied two ropes together and are concerned about the knot getting caught as it pulls over the lip. The friction generated by pulling the rope over the edge may make it difficult to retrieve.
- Choose a low-profile knot if tying two ropes together (e.g. Flemish bend or overhand, aka eurodeath knot).
- Before the last person rappels have someone below check the pull of the ropes. If it looks like there are going to be any problems, then the person up top can make adjustments before going down.
- Make sure you are pulling the correct strand down if you have knotted two ropes together and check that there are no twists in the ropes.
- Depending on the length of the rappel, it is possible to move the rappel knot past an offending edge by adjusting the ropes. It is even possible for the last rappeller to stop a little way down and readjust the ropes, moving the knot over any problem spots. Careful! Doing this makes the rope ends uneven. Only do this if you have knots in the end of your rope or know you have plenty of slack to reach the next rappel station.
- If the rappel station is set up so that one of the rope strands

will run against the rock and the other will be stacked on top of it, set the ropes up so that you will pull the strand that hangs against the rock. If you pull the outer strand it can sometimes pinch the inner one at the anchor and make it difficult to pull.

- When rappelling with two ropes in windy situations, position the knot on the upwind side of the rappel anchor. When you pull the ropes, the free line blows downwind and is easy to pull through the anchor. If it is set up the other way, when the free line blows downwind, it can put almost a full wrap onto the anchor and adds quite a bit of friction, especially if there are any twists in the lines.
- If possible, change your position if you encounter resistance: move farther away from the wall and/or try moving to either the right or the left.

Getting Ropes Unstuck and Last Resorts

When ropes do get stuck, try the following:

- If you still have both ends of the rappel line, sometimes it helps to pull the rope back up a bit—pulling on the other strand can actually help free the stuck side.

- Flick the rope from left to right, up and down. Give yourself enough slack to create a wavelike motion with the rope.
- As a last resort, tug in all directions with all of your and your partner's might. Watch for whipping rope ends and even more dangerous, dislodged rocks!

If you can't get your ropes unstuck, here are a few options:

- If both strands are still with you, tie a friction hitch (like a Prusik) around both strands of rope and free-climb or ascend (see chapter 5) back up the rappel route, pushing the Prusiks up the line with you as you climb. If you are reclimbing a route that is only typically used for descents, take care; the rocks may be much looser than you would find on an ascent line.
- If only one strand is available, then you may have enough rope to relead the pitch. If you can't free-climb the pitch, remember that French-freeing or aiding back up is always an option! (See chapter 5 for a description of *French-freeing*.) Attach a Prusik to the stuck rope and slide it up as you go as a backup.
- If only one strand of the rappel line is available and you do not have enough slack to lead the pitch, or if the terrain is too difficult to free or aid climb (while pushing a Prusik up the

line as described in the first example), then you are looking at ascending the rope using an *ascension rig* (see chapter 5, Ascending). This is a scary proposition, since you have no idea what your rope is stuck on and therefore no idea what will be holding your weight. Build an anchor and have your partner clip in to the anchor and tie in to the bottom of the stuck line on which you will be *prusiking*. Have him put the stuck line (you) on belay. You will ascend the line with your ascension rig (rather than being tied in to the rope, you are attached via your ascension rig). Place gear at any available opportunity and clip the rope you are ascending to it; this way if the rope does dislodge, you will take a leader fall, or at worst a fall on the anchor, which is not great but is better than plummeting down multiple pitches with the freed climbing rope.

- A minor saving grace with this option is that if you and your partner tugged as hard as you could and the rope still would not budge, hopefully that means the rope is good and stuck. That being said this is *not* an option to be taken lightly. Do not rule out the idea of cutting the rope and continuing to descend with whatever portion of rope you have left.
- If it so happens that you are stuck with only one strand but are not too far off the ground, consider rappelling on the available side of rope. Build an anchor and fix the available strand of rope to the anchor's MP. Rappel down on the single

strand. This solution does mean leaving gear and your rope; certainly costly, but still potentially lower than the price of higher-risk options.

RAPPEL BACKUP

Many climbers view rappelling as one of the most vulnerable moments of a climb. A climber is no longer relying on good movement as her primary means of safety; instead she is completely relying on an artificial system. Imagine if a rock fell from above and crashed into your arm (or knocked you unconscious), or a wasp took you by surprise with a sharp bite. Would you maintain your brake hand? Hard to say. Imagine if your hand came off even for a second. What would happen? Or what if you had not tied knots in the ends of your rappel line and you did not notice you were at the end until you only had a few inches left to go? Many people have died this way. If you are on belay during the climb you are backed up for these eventualities. It makes sense to back yourself up for the rappel as well.

Fig. 4-7. Fireman's belay. The climber on the ground provides a belay by pulling downward on the two rappel strands.

Personal comfort level and perceived risk dictates whether or not you choose to employ a backup, but in a rescue setting it is a certainly a good idea. With adrenaline pumping and seldom-used systems put into operation under tense circumstances, it can be easy to make a mistake. You are also taking responsibility for someone else's well-being, not just your own. Finally, think of all the tasks you may need to accomplish with your hands; having a backup already in place will speed up the process of freeing your hands.

FIREMAN'S BELAY

This is an extremely fast and simple backup. Just have someone located on the ground (or at the anchor you are rappelling down to) hold both rope strands, leaving a little bit of slack in the line (fig. 4-7). Should you need to stop and free your hands (or suddenly get hit in the head by a large chunk of falling ice), your belayer simply yanks downward, their pull acting as a remote brake hand. When you want to continue rappelling, your belayer simply lets up a bit on the rope. (You maintain your own brake hand, feeding slack through your rappel device as you descend.) As a backup belayer take care that you are out of harm's way as best you can from rock fall or other debris.

THIRD HAND

A *third hand* is a friction hitch tied with a rescue loop or runner around both brake strands below the rappel device. With a regular rappel setup, it can be attached to a harness' leg loop. Or, the belay device can be set on a *cow's tail* (described later in this chapter) and the third hand attached to the harness' belay loop.

1. With a rescue loop or a runner, wrap an autoblock around both brake strands and clip the rescue loop in to your harness' leg loop with a locking carabiner (fig. 4-8).
2. Keep your brake hand just above the autoblock (closest to the rappel device). If you rappel at an even pace, taking care to feed the rope through the third hand with a smooth motion, your autoblock will be less likely to catch unwantedly, resulting in a smoother, more comfortable rappel.

Fig. 4-8. Third hand. An autoblock clipped to the leg loop with a locking carabiner.



Fig. 4-9. Third-hand variation. Using a short cord, tie a Prusik

around the brake strands, then tie the cord off to the harness' leg loop with an overhand.



If you need to stop and get your hands free, all you have to do is gradually let go and make sure the autoblock engages.

Another viable option for a third hand is tying a Prusik around the two brake strands (again, below your belay device) with a piece of cord (the cord does not need to be tied into a loop). Thread one side of the cord through your harness' leg loop and simply connect it to the other strand of cord with an overhand or figure eight on a bight. This eliminates the need for a carabiner. (See fig. 4-9.)

As whenever using friction hitches, test your hitch with a quick tug in the direction of pull and make sure it catches. This is especially necessary if using ropes that are new and slippery or of two different diameters.

RAPPELLING WITH A COW'S TAIL

A cow's tail is a tether or single sling girth-hitched on a harness' belay loop with a locking carabiner and attached to the other end of the sling. In this case the locking carabiner that would typically clip through your belay loop (then into the rappel device and rope) connects the cow's tail to a rappel device.

1. Girth-hitch a runner around your belay loop, creating a cow's tail.
2. Load your rappel device with the rope as you normally do for belaying.

3. Clip a locking carabiner through the rappel device and rope, then through the cow's tail instead of the belay loop.

It is easy to employ the use of a third hand in this setup. You can clip the third hand right to your belay loop. See fig. 4-10 showing a rappel using a cow's tail. Note the climber pushing down her third hand (right hand) as she rappels.

A cow's tail serves multiple purposes: The rappel device is further removed from the waist/chest area and therefore objects like clothing, long hair, and skin are less likely to get caught. It is less cumbersome to deal with when paying out rope as you rappel (especially if you are rappelling with your ropes stacked in holsters) or when managing a third hand, and the uncluttered space created by using a cow's tail can make rappelling with a patient much more manageable.

Fig. 4-10. Cow's tail. "A" indicates the rappel device and locking carabiner; "B" indicates the cow's tail; "C" indicates the rappeller's third-hand rappel backup.



Using a cow's tail also provides an easy way to leave a rappeller unsupervised and ready to rappel, without relying on him to safely rig himself in to the system. Once the climber is rigged on rappel with a cow's tail, you can rappel first. The downward pull on the ropes created by the weight of the first rappeller functions as a lock-off on the second rappeller’s brake strands—just like a fireman’s belay. (The cow’s tail creates an extension that prevents the second climber from getting sucked into the rock.) Once the first rappeller is done rappelling and her weight is taken off the rope, the second rappeller has enough slack necessary for rappelling. *Important Note:* Careful about unweighting the rope midrappel. As soon as the first rappeller unweights the rappel rope the second person’s rappel can be initiated.

TANDEM RAPPELLING

Tandem rappelling involves rappelling with two people using the same device. This is a great technique for descending with an injured, unskilled, or incapacitated person, or when completing a “pick-off” (described later in this chapter). The easiest way to rig a tandem rappel uses two separate tethers. This is where a Purcell Prusik (see the Purcell Prusik sidebar) comes in handy providing an adjustable tether for the rescuer. Adjustable tethers allow you to change your position in relation to your patient and the terrain, thereby allowing a more comfortable descent for you and your patient. Although using a tether is simple and fast, it does not provide you with an easy way to transfer your and your patient's weight on and off the anchor (see fig. 4-11).

1. Girth-hitch a runner through your partner's belay loop, creating a cow's tail.
2. Girth-hitch your Purcell Prusik (or cow's tail) through your belay loop and extend it so you will hang slightly below your patient once on rappel.
3. Load the rappel device with the rope.
4. Clip both you and your patient's carabiners through the rope and the rappel device. The two carabiners add friction to the system and make it easier to control the double load. They also allow you and your patient to be on independent systems. If two isn't enough, you can always consider a third carabiner.
5. Once you both unclip from the anchor you are ready to rappel.

Fig. 4-11. Starting a tandem rappel. This photo provides a good view of tandem rappelling and the use of two separate cow's tails, one for each rappeller. The attendant (left) stands behind the patient (right) with legs staggered to provide support as they move over the edge.

STARTING THE RAPPEL

Leaning back over the edge can be one of the most difficult parts of tandem rappelling.

1. Get behind your patient.
2. With each of you standing in a shoulder-width stance, alternate your legs. Each of you should have one leg on the outside of the stance.
3. Lean back and lower or rappel as normal.

THE PURCELL PRUSIK

The Purcell Prusik, developed by British Columbia's Columbia Mountain Rescue Group, is an excellent multiuse tool for improvised rescue and personal climbing application. The Purcell functions both as an adjustable tether that can be used for clipping in to an anchor (or a rappel device) and also for ascending a fixed line. It does take more cord to tie than other ascension rigs (see chapter 5, Ascending), but its multipurpose nature makes it very versatile. It can always be untied and used as a cordalette as well.

The Purcell setup consists of three different lengths of cord tied to create two separate foot Prusiks of different lengths and one waist Prusik. Here we explain how to tie a foot

Purcell Prusik (in improvised rescue, just one foot Purcell can be adequate); this length can be used as a tether (aka cow's tail) or as a foot Prusik for ascension. Measurements for the waist Prusik (same as the one employed in other improvised ascension rigs) are discussed in chapter 5, Ascending.

Depending on your height you will need 12-15 feet of cord.

1. Tie a figure eight on a bight, incorporating both ends of the cordelette (similar to a Frost knot). The resulting smaller bight should be approximately 8 inches in diameter (figs. 4-12 and 4-13). This loop ("A" in the figures) will be attached to the rope with a Prusik for ascending or can be girth-hitched through a harness' belay loop for use as a tether.
2. With the bigger loop ("B" in the figures) create the skeleton of a three-wrap Prusik on your index finger and thumb (fig. 4-14). Wrap the cord around your fingers starting the wrap on the outside of your fingers and finishing on the inside. Move up the length of your fingers toward your fingertips.
3. Bring your fingertips together. Then slide two fingers in through the loops to facilitate step 4.
4. Thread loop "A" through the Prusik skeleton you have just created (fig. 4-15). Pull through the Prusik all but a few inches at the end.

5. Grab the two strands exiting the Prusik ("C" in fig. 4-16) and pull them directly downward. Tailor the length of your Purcell to your body by feeding slack through the Prusik; adjust tail length of the figure eight if necessary. Fig. 4-17 shows a completed, long Purcell Prusik.

The loop created with the Prusik hitch can be cinched down around your foot for ascension purposes or can be clipped with a carabiner when used as a tether. When used as a tether, a simple slide of the Prusik adjusts the tether's length.

Fig. 4-12. Step 1.



Fig. 4-13: Step 1, completed. "A" indicates the smaller loop; "B" indicates the larger loop.



Fig. 4-14. Step 2 (Step 3 not shown).



Fig. 4-15. Step 4.



Fig. 4-16. Step 5 "C" indicates the two strands exiting the Prusik.



Fig. 4-17. A completed long Purcell Prusik.



RESCUE SPIDER

The *rescue spider* is another simple way to quickly rig for a tandem rappel. It has a number of advantages: it connects the rescuer and the patient while requiring only one sling; it allows attachment for a rappel device; it has a long tail for transferring both climbers onto an anchor with a releasable hitch. These attributes make transitions to and from multiple rappel anchors quick and simple. Its only drawback is that its tether lengths are fixed. It is not as easy as a Purcell to adjust your position relative to your patient once connected.

Building a Rescue Spider

1. Use a long rescue cordelette (about 20 feet) tied in a loop with a Flemish bend.
2. Double the loop over and tie a figure eight on a bight so that you are left with three loops, one long and two short (one of which will have two loops of its own—a result of tying the bight). One short loop should be about 1 foot long, the other short loop should be about 1.5 feet long, and the long loop should be about 3-5 feet long. (The figure eight bend should not be on the long loop; it should be in one of the two shorter loops).
3. Clip locking carabiners in to the two shorter loops (fig 4.18). These carabiners clip in to your harness and your patient's. Clip the 1.5-foot loop in to your harness. (It is possible to tie knots in this loop to shorten it up in case you want to be in front of your patient during parts of the descent. That technique is not shown.)

Fig.4-18. A tied rescue spider. Patient and rescuer each have a carabiner to clip into.



Using the Rescue Spider

In this scenario we assume you are setting up for a tandem rappel with your patient.

USING THE RESCUE SPIDER

Fig. 4-19. Steps 2 and 3: (not yet tied off with a mule-overhand).



Fig. 4-20. Step 3 complete. You and your patient can now weight the anchor (step 4 not shown).



Fig. 4-21. Steps 5, 6, 7, and 8.



Fig. 4-22. Step 9



Fig. 4-23. Step 10



1. Set up your rescue spider (fig. 4-18) and clip the 1.5-foot loop to your harness. Clip the shorter loop in to your patient's harness.
2. Build an anchor and place a locking carabiner on the MP (fig. 4-19).
3. Attach the spider to the anchor using the spider's long loop

to tie a MMO (fig. 4-20).
4. You can now weight the anchor and hang from the spider.
5. Set your rope up for rappel on the anchor (fig. 4-21).
6. Attach a locking carabiner to the rescue spider through the two tether loops connecting you and your partner, below the large figure eight knot (fig. 4-21).
7. Set up the rappel device on the rope (fig. 4-21). Use two locking carabiners here instead of one for extra friction, especially if dealing with a heavy patient.
8. Attach a third hand to the rappel ropes and clip it to your harness belay loop (fig. 4-21).
9. Release the mule-overhand and lower your weight onto the rappel device (fig. 4-22). Make sure the third hand engages, holding the load.
10. Remove the Munter and take the extra locker from the anchor (fig. 4-23). Rappel to the next station.

Repeat these steps at each station until you reach the ground.

RAPPEL POSITIONING IN RELATION TO A PATIENT

There are a variety of ways to position yourself in relation to your patient—all depending upon you and your patient's height and weight, the terrain you are rappelling through, and the severity of your patient's injuries. Here are some considerations.

In the Lap

If your patient is the same size or smaller than you, suffers from injuries that you need to keep your hands on, or you need to provide head support while rappelling, place him perpendicular to your body in your lap. If your partner is significantly larger or heavier than you it can be difficult to negotiate lower-angle terrain in this position. If you have short legs it can be tough to rappel over roofs or to rely on your legs for control in this position.

Side by Side

If your partner is physically able, this is a good option for rappelling down lower-angle terrain. You are able to coach and physically support your partner if need be. Depending upon the severity of the situation, some patients may appreciate the relative sense of control that using their feet provides. It also may be less taxing for you as a rescuer—something important to keep in mind especially if you have a long descent. From the side-by-side position it is easy to move into a staggered rappel position (see fig. 4-11, earlier this chapter) to help your patient negotiate terrain features and complete edge transitions.

Piggyback

Once in motion on the rope, gently swing your patient around onto your back. (This sounds more difficult than it actually is.) This technique works especially well when the rescuer is smaller than the patient. The cow's tail holds the patient's weight while you simply keep the patient in place with a piggyback. Because there is nothing between you and the wall, you can easily negotiate terrain. Once you and your patient reach the next belay station (or the ground), swing your patient back around in front, positioning him either hip-to-hip with you or with your legs staggered as explained in "Starting the Rappel," earlier this chapter.

EDGE TRANSITIONS

Edge transitions can be tricky, particularly if more than one person is on the line. These transitions are awkward and pose definite risks to the rescuer and/or patient: a slip, or even too quick a transition while moving over the edge, puts more force on the anchor as the climber's weight drops and there is the potential for injury or rope damage. Here are some tricks for making your edge transitions smoother:

Try to rig high: This can lessen the sharpness of the angle created by the rope going over an edge. Setting the anchor higher also reduces the amount of friction added to the system by the rope running over the edge (making hauling easier) and can protect the rope from abrasion or an abrupt transition.

Consider edge protection: It is worth emphasizing that your ropes are your lifelines. Do what you can to protect them! If the rope moves over a sharp lip, pad the area with backpacks, extra clothing, a rope bag—whatever you have available (don't forget to attach these items to the anchor). Due to the way the rope's core is constructed, lateral movement over sharp protrusions running perpendicular to a rope are much more damaging than a protrusion running parallel. This is particularly important as you add more weight into the system (i.e., two people hanging off the system instead of just one).

COUNTERBALANCE RAPPELLING

The counterbalance rappel is a good method to use when you know you need to descend to a patient and will continue down to him. This is a technically involved skill, and care should be used when executing it. It is fast and efficient when employed correctly, and it is mostly used in emergency (injury) situations so it should be practiced thoroughly.

Counterbalance rappels are rigged so that the rope can be pulled and retrieved once the rappel is complete. (If you anticipate needing to raise your patient, a single strand rappel, tied off to the anchor, may make more sense.) This method works even if there is only one rope and the second is more that half a rope length down.

1. If belaying off the anchor (as shown in figs. 4-24-4-31), get hands-free ("1A" in fig. 4-24) and back up the belay ("1B" in fig. 4-25). If belaying off your harness, get hands-free and then follow slightly different steps, described second in the steps that follow, until step 6. In either case, reinforce the anchor if necessary. Two people's weight will be hanging on the anchor with the forces of a lower and a rappel.
2. Attach a cordelette using a PMMO between the load strand and the anchor for load transfer ("2A" and "2B" in fig. 4-25).
3. Lower your climber onto the PMMO setup (fig. 4-26). (If using a self-blocking belay device like a Reverso you may need to employ the steps for lowering described earlier in this chapter if you are unable to manually release the belay device.)
4. Clip a locking carabiner through the anchor's MP (fig. 4-27) and clip in the section of rope running between the

loaded Prusik and the belay backup knot. If you were belaying off your harness, you can clip the rope between the loaded Prusik and the tied-off belay into the locking carabiner. This is your new MP.

5. Thread the rope through your rappel device ("5A" in fig. 4-27). Attach a third hand to your brake strand ("5B" in fig. 4-28). Gather all gear and equipment, as you will not return to this spot. If you were belaying off your harness, you are already set to rappel.

6. Remove the belay backup knot and take up the slack through your Munter (fig. 4-28). If you were belaying off your harness, you should be slack-free already.

7. Weight your side of the rappel setup and undo your anchor tie-off or tether so you are ready to rappel down the rope (fig. 4-28).

8. Undo the MMO tied onto the load strand with the cordelette and slowly lower your patient's weight onto the climbing rope (fig. 4-29). You are the counterbalance, so make sure you weight the other side or you will be pulled up to the anchor carabiners.

9. Leave the Prusik (of the PMMO setup) on the patient's rope ("9A" in fig. 4-30). Clip the other end of the cordelette in to a locker on your belay loop ("9B" in fig. 4-30). This connection allows you to stay in control of both ropes. It is very important you remember to slide the Prusik connected to your partner's

side of the rope down the line with you as you rappel.
10. Rappel as far as you can until you reach your patient or you run into your tie-in at the other end of the rope.

If you have not reached your patient you must build another anchor and repeat the above steps. Steps for building another anchor follow. Skip to step 22 if you reach your patient.

11. Make sure your third hand grabs and get hands-free.
12. Build an anchor.
13. Clip yourself in to the anchor with your tether, but do not weight it.
14. Use a spare cordelette to attach your patient's side of the rope to the anchor by tying a PMMO combination onto a locking carabiner clipped through the MP.
15. Slowly feed out rope through your rappel device so your patient's weight is transferred to the cordelette (and thereby the anchor) along with your weight transferring onto your tether.
16. On your patient's side of the rope, above the loaded Prusik, tie a figure eight on a bight and clip it to the MP; this serves as a backup to the cordelette.
17. Untie the rope from your harness.
18. Pull the rope through the first anchor and rethread it through the anchor you are hanging on.

19. Tie in to the end of the rope (or tie a stopper knot at the end of the rope) and set yourself up to rappel. Set your third hand so you can be hands-free.
20. Make sure all slack is out of the rappel system and you have everything you need. Release the PMMO tied on your patient's side of the rope, lowering your patient's weight onto the other side of the MP.
21. Unclip your tether and clip it to your patient's side of the line as you rappel, taking care to slide it down with you as you descend.

You now have much more rope and will hopefully reach your patient without having to do this all again—though you might! In which case, repeat steps 11 through 21.

22. Once you have reached your patient you must build another anchor and transfer both of you to it (fig. 4-31). Then pull the rope down through the last anchor and continue by means of tandem rappelling. For efficiency, use a rescue spider to connect you and your patient together as well as to transfer your weight on and off the anchor for rappelling.

Fig. 4-32. Counterbalance rappelling. Steps 1-18 completed. The rescuer was not able to reach her patient with just one

counterbalance rappel so she is taking the steps necessary to set up a second counterbalance rappel. She has built a new anchor to which she and her patient are attached (her patient with a releasable hitch.) She is now pulling the rope through the anchor above in order to rappel off the new anchor.


PREVIOUS ANCHOR
PULL
CLIP into the SHELF
COW'S tail
UP!
PPMO

COUNTERBALANCE RAPPELLING

Fig. 4-24. Step 1A. Get hands-free.



Fig. 4-25. Steps 1B, 2A, 2B. Back up the belay; attach a PMMO (Prusik, 2A; Munter-mule-overhand, 2B).



Fig. 4-26. Step 3. Transfer the load to the PMMO, in this

case by levering the self-blocking belay device using the striped sling.



Fig. 4-27. Steps 4 and 5A. Set up to rappel. Thread the rope through your rappel device.



Fig. 4-28. Steps 5B, 6 and 7. Attach a third hand to your brake strand. Take out all slack and leave a good anchor.



Fig. 4-29. Step 8.



Fig. 4-30. Steps 9A and 9B. The Prusik is on the patient's rope (9A) and the other end of the cordelette is clipped in to a

locker on your belay loop (9B).



Fig. 4-31. Step 10: Counterbalance to tandem rappelling. Attach to the patient and get onto an anchor. Note: If you were unable to reach your patient in one counterbalance rappel you will have to continue counterbalance rappelling (see Fig. 4-32). Step 10 assumes you are at your partner.



ANCHOR-BUILDING TECHNIQUES

Stand on your bathroom scale and quickly drop down to your knees. Notice how you can cause the dial to spike way beyond your actual weight? The same effect happens when you bounce on a climbing rope or an anchor. (The effect is dampened by a variety of factors, for example the amount of rope active in the system.) Now imagine that effect with two climbers relying on the system. The amount of weight your anchor experiences increases dramatically. Therefore, before continuing with a rescue it may be necessary to reinforce your anchor or at the least evaluate your anchor's vector angles, sling craft, and position, particularly if you will be raising or counterbalance rappelling.

SLING CRAFT

A well-thought-out rescue anchor can become a bit more complicated than simply slinging a bunch of pieces together. The amount of cordage used in linking pieces in anchor construction affects how much force is transferred to each individual piece. (See fig. 4-33.)

As Mike Gibbs of Rigging for Rescue puts it, think about stretching out one side of a rubber band. Now stretch both sides of the rubber band using the same amount of force. It does not stretch as far. This same principle applies to the cordelette used in anchor construction.

The more material an anchor point has (as compared to other anchor points in the system), the less that anchor point's material will stretch when the anchor is loaded. The less an anchor point can stretch, the higher the force that will be transferred to that anchor point's piece of protection. (The principle is similar to the difference between taking a big lead fall on a static rope versus a dynamic one. A static rope delivers a much higher jolt to your body while the dynamic rope stretches, dampening the effects of the fall.) Therefore, an easy way to maximize the use of stronger pieces in your anchor system (like a big bottleneck hex in perfect rock) is to bring more material (webbing or cord) to that particular anchor point.

Take a look at the center anchor in Figure 4-33. The middle anchor point has two strands of webbing compared with just the one strand comprising both outside anchor points. This means that more force will be transferred to the anchor's middle point, and less to the outside points (they have less material) due to the differences in elongation (excluding differences in vector angles).

A separate consideration, not to be confused with the elongation principles information explained above, is that the material linking the middle anchor point to the master point has a stronger strength rating than that of the outside anchor points. A single strand of 7-mm knotless cordelette is rated for 10 kiloNewtons (kN) while a doubled-over section of cord (as shown in the center anchor point) can handle double the load (less the strength reduction for the knot).

A similar principle applies to the length (amount) of material between a specific piece of protection and the MP. The longer the distance between the MP and the piece of gear, the more material there is available for absorbing forces. The shorter the distance the less material there is available for absorbing forces and therefore the more force that that piece of gear will receive. If you find you're dealing with marginal gear placements, it might be time to rethink your sling craft. (See right anchor in fig. 4-33).

CARABINER LOADING

Considering that you are more likely to repeatedly weight and unweight the anchor in a rescue scenario (think of all the repositioning down below that might go on with a patient), it is important to keep the possibility of cross-loading or triaxial loading carabiners in mind. *Cross-loading* refers to loading a carabiner across its short axis (over its gate.) *Tri-axial loading* refers to loading a carabiner in three directions at the same time rather than the two directions it is designed for. When the tension on a system is relaxed and then reapplied, a carabiner can slip into a dangerous orientation. This is one of the reasons why being tight on your anchor is always emphasized. Take care to rig conservatively and with this consideration in mind.

Fig. 4-33. **Left Anchor:** *All three anchor points are equal in*

amount of available material. Force will be distributed equally throughout this anchor. Compare this to the right anchor where all three anchor points are different lengths.

Center Anchor: *Although the anchor component lengths are the similar, the outside components have one strand of cordelette while the inside has two. Because the inside anchor point has more available material it will stretch less.*

Right anchor: *The anchor components are unequal so they will see unequal loading. The shortest will see the most load and the longest will see the least load.*







Fig. 4-34. Here’s a good look at why building a solid anchor is so important. For testing purposes the UIAA uses 80 kilograms (176 lb) as a climber’s weight. We have increased that to 160 kilograms (352 lb), because many rescues involve the weight of two climbers on the system. Look at the different amounts of force each anchor component will receive as the vector angle increases. Although quality gear in quality rock can certainly withstand these forces, this demonstrates why building with small vector angles (particularly in snow, poor rock, or ice) is important.


186 lb
A
186 lb
A
30°
211 lb
B
211 lb
B
60°
246 lb
C
246 lb
C
90°
352 lb
D
352 lb
D
120°
1,013 lb
E
1,013 lb
E
160°
TWO CLIMBERS
TANDEM
RAPPELLING
80 kgs (176 lb) each
=
160 kg (352 lb) TOTAL

(20° or less = 50%)

A.	30° =	53%	.8 kN
B.	60° =	60%	.9 kN
C.	90° =	70%	1 kN
D.	120° =	100%	1.6 kN
E.	160° =	290%	4.5 kN

VECTOR FORCE PERCENTAGES and kN for ***EACH SIDE*** ***OF THE ANCHOR***

PICK-OFFS

A *pick-off* is the process of a rescuer either rappelling or being lowered down to a stranded or injured person (could be a climber or even a hiker that got in over his head) and "picking him off" the wall.

Our discussion of pick-offs assumes the rescuer is using a single rope. Search and rescue (SAR) teams typically use two-rope techniques: a main line and a belay. Those systems are beyond the scope of this book. There are many good classes referenced in appendix D, Continuing Education.

You might use a pick-off to deal with a situation involving your party—rock fall severing a rope, for example. More likely you will use it to help another party. It is a great skill to know and one of the basics of organized search and rescue.

PICK-OFF PREP

It is important to think and plan a little before jumping over the edge to help someone. Before you descend, consider the following:

- Should you bring any supplies down with you? For example: first-aid supplies, specific medication, extra layers, food and water, a harness or material to make a harness with, material for a chest harness, extra gear for creating an anchor or reinforcing the injured climber's gear.

■If someone has accompanied you to the site, how will you communicate with him or her?

■Although obviously subject to change, what is your plan of action?

■Before you set an anchor consider where it lies in relation to the patient. If possible set it off slightly to either side; you do not want ropes or loose debris to hit your patient. Off-setting the rope to one side also lessens the risk of a panicky patient grabbing your lines. (Another way to avoid both of these hazards is to keep the rope strands with you as you rappel, in either a holster or a backpack as discussed in the Rappelling section.) However, do not set your anchor so far off to the side that reaching your patient turns into a struggle.

■It might be necessary to spend a little time clearing out potential hazards (loose rocks, deadfall, etc.) that could fall on you and your patient.

■Is the anchor strong and secure enough to withstand the forces of raising should you and the patient need to be hauled?

■If rappelling, rig your rappel device on an adjustable tether and pre-rig a fixed-length tether for your patient. Or use a rescue spider. (Run the rappel rope through two carabiners.

The additional friction will help control the weight of two climbers.)

THE PICK-OFF

When executing a pick-off, you want to be able to clip the patient in to a rope as quickly as possible. Be aware that as you approach your patient he may, out of panic or relief, grab at you, creating an obstacle that makes it difficult for you to rappel or to clip in to him. In this type of situation you should be very direct: tell the patient exactly what you want him to do. Again, your first objective will typically be to get the patient clipped in to your system as soon as possible.

Once you have reached your patient, clip the free locking carabiner coming off the tether (or rescue spider) in to your patient's belay loop, or secure him into an improvisational harness (as described below in "Safely Assisting and Rigging an Injured Climber").

In all likelihood it will make most sense to untie your patient from his climbing rope, as he is now clipped in to your system. But do not simply untie him as a matter of course—consider if this is in fact what makes the most sense. And of course, double-check that he is correctly clipped in to your system before untying anything. Your patient will need to unweight his rope in order to facilitate untying from it.

From this point you have a variety of options: perhaps you build an anchor and pull the rope (or it is dropped down to you if you are being lowered) and continue via tandem rappel (see “Rappel Positioning in Relation to a Patient” and “Tandem Rappelling” earlier this chapter); maybe you prepare for a raise; or it may be that the best solution is to continue down the rest of the rope’s length via either lowering or rappelling.

This pick-off process will be essentially the same whether you are being lowered down by a third party from above or rappelling.

SAFELY ASSISTING AND RIGGING AN INJURED CLIMBER

If you are descending to a patient who is not wearing a harness (e.g., an adventurous kid stranded on a ledge), bring something you can loop around her quickly, such as a sewn or tied double-length runner. Loop it around her waist and clip the rope in to her immediately. If she were to take a small stumble or fall, the loop would slide up her body, stopped by her armpits. This is of course only a temporary solution. Then you can take the time to tie an improvised harness (like the diaper harness described below) or to fit the patient in a manufactured one.

The injured party may also require additional support. Described below are a variety of sling, chest, and seat harnesses—all built with a limited amount of tools, most involving nothing more than a cordelette or webbing. Although there are few situations when you actually need to use these tools, they are useful to know. If moving in tandem with your patient, you obviously will be able to provide her with plenty of support using your own body. But what happens when you reach an anchor and your hands need to switch from stabilizing your patient to rigging tasks? This is exactly the type of instance where these particular techniques come in handy. You can pay full attention to your anchor transition, knowing that your patient is still in a stable and supported position.

As with any improvised rescue, there is no perfect answer. For assisting and rigging an injured climber, the solution depends on what gear and outside resources (bystanders or rescue teams) you have available, the climber's injuries, and the terrain over which you will be moving your patient.

These descriptions exclude first-aid information, in particular the important step of evaluating and treating for spinal injury. Refer to the Continuing Education and Recommended Reading appendixes for more information on wilderness first aid.

HARNESS HANG SYNDROME

Although rare, harness hang syndrome is worth being aware of. It occurs when someone is left hanging from a rope immobile in a harness and can result in death. More commonly recognized among cavers, the syndrome has indeed occurred in climbing situations. The syndrome is believed to be caused by the harness trapping blood in the legs and as a result not enough blood gets to the brain; a change in blood chemistry is also indicated, and it is believed that the situation overall can be exacerbated by exhaustion or cold. But no one is certain what causes the syndrome and theories vary. Tests conducted at the Aerospace Medical Research Lab at the Wright-Patterson Air Force Base found that symptoms onset in an average of six minutes. Symptoms begin as a general feeling of flulike illness and progress to excessive sweating, nausea, dizziness, and hot flashes followed by unconsciousness. Even the slightest movement can help avoid this. If a patient is caught hanging in a harness the bottom line is to get to your patient as quickly as possible.

Diaper Harness

A diaper seat is an acceptable quick harness. This harness is quick and more secure than just a sling around a patient's waist, but it is not a foolproof harness. Tying a Swiss seat or having a second harness for the patient will be preferable if you need to perform a long lower or raise; if you are assisting someone without a harness, try to borrow someone else's to take with you to the patient.

For the diaper harness, you will need a double- or triple-length sling tied or sewn in a loop (about 4 feet long when tied).

1. Put the loop around the patient's waist like you are putting on a belt (do not put it over her head).
2. Grab one of the loop's strands and pull it up through the patient's legs.
3. Bring the bight you just pulled between the patient's legs and the two bights created by the end of the loop, resting on either side of her waist, together at her belly button.
4. Adjust the strand going around the patient's back so it is snug; the excess slack should come out in the bight between her legs.
5. Depending on the patient's size you can just clip the three bights together with a locking carabiner, or you can tie knots to shorten the webbing for a snug fit and then clip. If the patient is too big for the diaper, just wrap her waist and use another piece of webbing to create leg loops.

Chest Harness

This simple and easy-to-tie chest harness is suitable for rigging a patient or yourself should you find that managing your patient is easier when being kept upright by a chest harness. This chest harness is suitable in an improvised setting in which the patient will only rely on it for a short time.

Fig. 4-35. Making a chest harness in the vertical world.

Fig. 4-36. Climber's cow's tail is clipped through her chest harness.



Using a double-length sling:

1. Twist the sling (runner) so that a single X is formed in the center of the loop.
2. As if you were helping her into a jacket, insert your patient's arms (or your own) through each side of the loop; the X should lie in the center of her back.
3. Bring the two sides of the loop together with a carabiner. The carabiner should be located in the center of your patient's chest. Shorten the loop by adjusting the sling's knot so that the harness is relatively tight on the chest and will hold your patient upright.
4. Clip the climbing rope through the carabiner on the chest harness (no knot is necessary—the climbing rope should run freely through the carabiner). See fig. 4-35.

If you or your patient is connected to the rope via a cow's tail, simply clip the cow's tail through the chest harness' carabiner instead of the climbing rope. See fig. 4.36.

To add stability and support to this basic setup:

5. Use a short rescue loop to tie a Prusik hitch onto your patient's rope and clip the chest harness carabiner into the rescue loop. Slide the Prusik up the rope until your patient feels more comfortable.

Head Sling

A head sling should not be rigged without some sort of chest harness included. You do not want the entire weight of the upper torso to be relying on the neck muscles to keep your body upwardly oriented.

1. Slip a runner behind your patient's head (pad the back of your patient's head if possible). Get creative! Adjust and tie cord and webbing to whatever you need to keep your patient's head upright. You can also use the waist of a shirt or pair of pants, or the opening of a bag. Slip it over the back of your patient's head and bring it together in front, securing it either with a carabiner poked through the material or with a knot.
2. How you attach your patient's head sling to the rope will depend on how your patient is rigged. If your patient is rigged on a cow's tail, you may be able to clip the head sling into the carabiner extended off the cow's tail. If the climbing rope is attached to your patient's waist, connect a runner or cordelette with a friction hitch to the rope and adjust accordingly once the head sling is clipped to that runner.

Lower Body and Foot Sling

The process for creating a lower body and foot sling for a patient is the same as described above for creating a head sling. The only difference from the head sling is the length of material you need for attaching the lower body/foot sling to the rope. Wrap whatever material is available around your patient's lower body or feet and bring the two sides together, connecting them with a carabiner or knot. You also have the option of girth-hitching something around the patient's quadriceps and/or feet to keep him in position. (In either case, but especially when girth-hitching, include padding.) Make sure that the sling is long enough so that you are not inadvertently causing your patient to tip backward.

SHORT ROPING

Short roping is a guiding technique that should only be employed by experienced professionals. Basically a short piece of rope is attached to a wobbly climber (e.g., who is hurt, disoriented, uncoordinated, etc.). The guide holds the rope so that if the climber slips the guide can pull quickly and definitively on the climber to stop any sort of slip or fall. The guide is generally about 3-5 feet from the wobbly climber and needs to be ultra attentive. Guides use the technique in exposed terrain where an unexpected fall would be bad. By tying to the climber, the guide is putting her life on the line if she is not able to support the climber in all the terrain they encounter. This technique might be useful to a rescuer when shepherding someone down a trail with a nasty drop on one side, but should not be used without practice and knowledge of the consequences of failure.

Real-life improvised rescue on Ama Dablam in the Himalaya



CHAPTER 5

Ascending

In this chapter we talk about ascending a fixed line, rope soloing and other handy ascension methods. A line is "fixed" when it is directly anchored above you (and possibly below you as well).

Fixed lines are also used in big-mountain climbing to protect exposed terrain that is not necessarily vertical. These lines are used much the same way as in vertical terrain, typically with both ends clipped to an anchor at the top and bottom, though commonly the climber can just clip to the line to back up his movement, not relying wholly on the line for upward progress.

In this chapter we focus on vertical or near vertical terrain. Let's begin with a look at some of the simplest means of ascending a rope and their applications for improvised self-rescue.

STUCKING HANGING

Eventually, no matter how lucky you are, something will get caught in your rappel device, long hair or clothing being the most common. If you continue rappelling, whatever is caught will continue to get sucked up by your belay device, clogging it up, not to mention creating a great deal of pain if it happens to be your hair or skin getting reeled in.

No matter what the stuck object is, in order to continue rappelling, the rappel device must be unweighted—not too tricky if you are rappelling a low-angle route where you may be able to simply stand up on the rock to unweight the device. But what about on a free-hanging rappel?

Here is an easy fix to something stuck in your belay device:

1. Free your brake hand using a Munter-mule-overhand (MMO), leg wraps, or by engaging your third-hand backup.
2. Attach either a spare runner or a rescue loop onto the rope above your belay device using a friction hitch. (Take care not to push it too high above or you will be stuck with the problem of retrieving it.)
3. Now girth-hitch whatever kind of webbing or cordage you have available to the runner or rescue loop already attached to the rope. Keep girth-hitching runners together until you have the desired length for a foot loop.
4. Stand up in the foot loop, grabbing the rope *not* the friction hitch (fig. 5-1); if you grab the hitch it will slide down. You have successfully unweighted the rappel device and are in a position to effectively deal. If your hair or clothing is really stuck, you may have to rip it out; sometimes that's the only option.

5. Once you have remedied the situation, sink back down onto your rappel device. Undo the string of girth-hitched runners and reach up to remove the foot sling's friction hitch.

Fig. 5-1. Using a chain of runners girth-hitched together and attached to the rope with a friction hitch, the climber is able to stand up and remove stuck items from her rappel device.


GIRTH HITCHED SLINGS

Climbers can get stuck in a similar predicament when using a Prusik hitch or klemheist placed above the rappel device as a back-up. If a climber does not adequately compensate for the amount of rope sliding through her belay device, while simultaneously moving the Prusik down the line above her, she may find herself suddenly stuck hanging from a fully weighted Prusik.

Here is an easy fix to the Prusik conundrum using a *foot wrap:*

1. With one hand tight on your two brake strands, use your other hand to run the rope under one foot and back up to a few feet above your belay device.
2. Holding tight to the four strands, step your foot into the loop and stand up. This should allow you to loosen the Prusik wraps and slide the Prusik down to the rappel device. If necessary you can wrap the rope around your foot several times to create a more sturdy foot loop.
3. Slowly transition back into your rappelling position, taking care to retain your grip on the brake strands while sinking back down and then slowly undoing the foot wraps.

IMPROVISING AN ASCENSION RIG

This improvised fixed-line ascension rig is an easy, quick, and versatile way to get up a line without the use of mechanical ascenders. Times you may need to ascend a fixed line include:

- Retrieving a stuck rappel line or if you have rappelled past an anchor.
- Attending to a hurt leader.
- Exiting a crevasse.
- Getting back on route after falling on a traverse or off a large roof.

The rig is made from materials that a climber is typically already carrying on her rack: a rescue loop and a cordelette. These are used to make a waist loop and a foot loop (a waist Prusik and a foot Prusik). These lengths of material do not have to be reserved just for creating an ascension rig; these two pieces of cord can serve multiple purposes and do not need to remain hanging from your harness pre-tied.

There are many different ways of creating an ascension rig and the process for correctly sizing your rig varies depending on if you are using one foot loop, two foot loops, or a locking girth hitch on your heel. There is no right or wrong way; the bottom line is figuring out what lengths work best for you to allow you to move efficiently on the rope.

Below are the steps for tying a one-foot-loop ascension rig.

This rig can be tied using a spare cordelette and provides a clip-in point so you will have two points of attachment to the rope when ascending.

THE KNIFE AS LAST RESORT

It is a good idea to get in the habit of carrying a small knife on your harness, particularly on longer climbs. Perhaps something is hopelessly stuck in your belay device, or the rope got hung up on a rappel and is irretrievable. You may want to cut up webbing to make an anchor or remove crispy, old webbing at a rappel station. Save the knife as a last resort if you are actually on the rope (e.g., your long hair is caught in the belay device). Look for other alternatives to getting unstuck such as the ones described in this chapter. Sharp knives can cut weighted, taut ropes in an instant. If you do use your knife, before opening it, attach webbing or cordage with a friction hitch onto the rope above you and clip in to it. That way should the knife mistakenly slip and slice the rope, you have a backup attachment to the climbing rope.

Fig. 5-2. Foot Prusik. Climber with a properly measured foot Prusik. The loop ("A") will be used for tying a Prusik hitch on

the climbing rope.



1. To tie a waist loop (waist Prusik), cut a piece of 7-millimeter cord as long as you are tall, plus 6 inches to a foot. Tie a double fisherman's or Flemish bend with the ends to form a loop.
2. For a foot loop (foot Prusik), cut a piece of 7-millimeter cord that is twice your height. On one end, tie an overhand on a bight that leaves a small loop big enough to clip a carabiner to. On the other end, tie a figure eight on a bight that leaves a 6- to 8-inch loop. Girth-hitch that loop to your foot. Clip the other end in to a locking carabiner on your belay loop.
3. Tie a figure eight on a bight that leaves a 10-inch loop. This knot should be about crotch level if your foot is on the ground and girth-hitched into the foot loop. The other strand, going to your harness carabiner, should be loose and 1 or 2 feet long. Proper length ensures you will achieve full extension as you push your foot Prusik up the rope. See fig. 5-2.

ASCENDING WITH AN ASCENSION RIG

The movement of ascension, when executed by an experienced climber, is impressive to watch. Some expert big-wall climbers are reputed to ascend with mechanical devices as quickly as they walk.

Here is a look at how to ascend with your newly tied ascension rig:

1. Attach your waist Prusik and your foot Prusik to the rope with Prusik hitches. The waist Prusik is tied farthest away from you, above the foot Prusik—think "waist away." (If using a Purcell Prusik, just substitute it for "foot Prusik" in these instructions.) Make sure you have secured the friction hitch around *both* strands of rope. And before being put to use, friction hitches need to be dressed and tested.
2. Clip the small loop on your foot Prusik and a section of your waist Prusik in to a locking carabiner clipped in to the belay loop on your harness (fig. 5-3). Note: If you will be passing a knot while ascending, each Prusik should be clipped into a separate carabiner (see chapter 7, Passing Knots).
3. Slide the waist Prusik up as high as you comfortably can reach.
4. Let your waist Prusik hold your weight as you tilt backward and slide your foot Prusik up as high as you can, ideally just below the base of your waist Prusik. Until you have significant rope weight beneath you, you will make your job of ascending easier by grabbing the rope with one hand below your Prusik and holding the rope steady with a downward pull as you

move the Prusik up the line.

5. Bring your feet in under your butt and grab the climbing rope as high up as you can.
6. Stand up in your foot loop while pulling your torso up, using the rope for assistance.
7. Once steady—you are weighting the foot Prusik—push the waist Prusik up as high as you can. (You can keep using the rope for assistance.)
8. Now sink back down onto the waist Prusik and repeat the process. Again, again, again, and again. We call this "ascending" or "Prusiking."

Fig. 5-3. Ascension rig. "A" indicates the climber's waist Prusik; "B" indicates the climber's foot Prusik. Both are attached to the climber with locking carabiners clipped onto the climber's belay loop. Note the raised foot girth-hitched into the foot loop.


A
B

IMPROVISE: ASCENDING WITH A GARDA HITCH

What can you do if you are stuck needing to ascend a line but do not have much extra gear? You need to ascend to a fallen leader, for example. Combined with a long sling (or a few shorter slings girth-hitched together), the Garda hitch provides a way to ascend a line in a pinch (see fig. 5-4).

Use the climbing rope to tie a Garda hitch through two carabiners clipped into your belay loop. (Make sure to correctly tie the Garda so that slack can be pulled through correctly in relation to the direction of ascent.) Now set a friction hitch above the Garda on the climbing rope. Add as many slings as you need to create a foot loop to stand in. Stand up in your foot loop and pull as much slack as possible in through the Garda. Note: when ascending with a Garda hitch the foot Prusik is above the waist Prusik (the Garda). Now weight the Garda and push up your foot loop. Continue ascending in this manner.

Fig. 5-4. Garda ascension rig. This rig is set up opposite of the Prusik ascension rig. "A" indicates the foot loop built out of girth-hitched slings and attached to the rope with a friction hitch. "B" indicates the Garda hitch tied off on the climber's belay loop with two carabiners. The climber is pulling on rope in his right hand to bring in slack through the Garda.


A
B

If you encounter pieces of gear while ascending simply clip your Prusiks through the runner's carabiner; similar to clipping through on a piece of protection while *simul-climbing*. There is no need to take your ascension rig off the rope.

Remember, as discussed in chapter 2, Rescue Knots, you may need to push the lower lip (or mouth) of the Prusik hitch open with your thumb in order to loosen it enough so that it will slide up the rope. You can also use other friction hitches to ascend; see the sidebar, "Improvise: Ascending with a Garda Hitch."

DESCENDING WITH AN ASCENSION RIG

Just as competent downclimbing is a skill stressed in rock climbing, the ability to descend a line is an important aspect of *fixed-line ascension*.

To descend using an ascension rig simply reverse the ascension process:

1. Stand up in your foot loop and slide your unweighted waist Prusik down the rope to the top of your foot Prusik. Leave an inch or two of space between the foot and waist Prusiks, or your waist Prusik will not grab as well when you sink onto it.

2. Now weight the waist Prusik and slide the unweighted foot Prusik down the line. Take care to not slide the foot Prusik down too far. You need to stand in the foot Prusik to unweight the waist Prusik; if you slid the foot Prusik down too far, you will not be able to reach it.
3. Repeat until you are back down.

MECHANICAL ASCENDERS

Ascenders made by Gibbs, Petzl, Blue-Water Ropes (Jumars), and so on are all types of mechanical ascenders that can be used for moving up and down fixed lines. Compared to friction hitches, mechanical ascenders have several advantages: they are extremely easy to clip on and off the rope, they slide with great ease, and they offer a comfortable grip.

There are, however, disadvantages to using mechanical ascenders: they are heavy, expensive, and their application is more limited than a set of Prusiks. Mechanical ascenders, if used at all, should be used with *great* caution when belaying or hauling. Testing shows that a shock load on mechanical ascenders can dangerously damage the rope—even shred the core. Because of mechanical ascenders' small camming area, in the event of a fall the rope can be severely damaged at as little as a third of the rope's rated strength. We do not recommend using a mechanical ascender in a raising system.

There are a few ascenders that are light and small. The Wild Country Ropeman and the Petzl Tibloc are two examples. These devices solve the weight issue while being quick and easy to use. They still have the disadvantage of being able to severely damage (even cut) the rope in a dynamic loading event, and they are not releasable under a load. Prusik hitches are the rescue tool of choice despite the apparent advantage of a piece of manufactured gear and easy application.

CLIPPING IN SHORT

Whenever ascending or descending a line, if the line is not weighted or fixed, it is a good habit to tie a figure eight on a bight every 10 feet or so and clip that bight into a spare locking carabiner on your belay loop. In the event that something should fail, you have created a trustworthy, relatively close backup for yourself. A fall of just a few feet is obviously preferable to falling the length of the rope back to your original tie-in point. This is sometimes called "tying in short" (see fig. 5-5).

ASCENDING WITH MECHANICAL ASCENDERS

Refer to the instructions that come with your mechanical ascenders for proper use. Some amount of practice is needed to develop smooth technique. Take the time to learn how to do it right.

To link yourself to the ascender, girth-hitch a runner or a daisy chain through your harness, then clip this with a locking carabiner into the eyehole on the lower section of the ascender.

If using a mechanical ascender on a traverse, clip a nonlocking carabiner through the eyehole of the ascender and then to the rope. Should your ascender come off the rope (traversing is the most likely scenario during which that can happen), you will still be attached to the rope with a carabiner.

DESCENDING WITH MECHANICAL ASCENDERS

Descending with mechanical ascenders is a little trickier than with an ascension rig; they are called ascenders for a reason! They like to go up, not down. Use your thumb to release the camming unit while simultaneously sliding the ascender down the line. Do your best to avoid the start-and-stop jerk of the teeth biting down by keeping the ascender in line with the rope and pulling out slightly.

Fig. 5-5. Clipping in short. Climber has clipped a figure eight on a bight back in to her harness as a backup while she ascends. Note the waist Prusik (top cord) and the foot Prusik (bottom cord) tied on the line.



Fig. 5-6. A climber having detached her skis and backpack, is

ready to ascend out of the crevasse.



If descending on lower-angle terrain, orient the ascender on the rope as if you were going to ascend. But instead of going up, retract the camming unit and slide the ascender down the line as you descend. Clipping a nonlocking carabiner through the ascender's top eyehole and the rope can help keep the ascender attached to the rope while you disengage the camming unit.

Make sure to practice in a controlled setting (on the ground or with a belay) before lifting off.

GLACIERS

In essence, the process of ascending out of a crevasse is exactly the same as ascending a fixed line in the desert. There are, of course, a few added steps pertinent to the unique environment of a crevasse's innards; these are addressed in detail in specific glacier-travel books (like Andy Tyson's *Glacier Mountaineering*).

If you have fallen into a crevasse, take a look around behind you, below you, and in front of you. It is easy to develop tunnel vision in stressful situations and there may be a simple solution right in front of your eyes. Maybe with the use of your ice ax you can easily climb out. Are the walls of the crevasse close enough together that you could stem your way out? You can always try and call up to a teammate to ask her to send down some equipment like another ice ax. If the crevasse's bottom is within sight, another option is to have your partners lower you; you may be able to simply walk out the bottom of the crevasse or move down to a better spot for climbing out. However, watch out that you are gently lowered onto the crevasse floor—it may be just another unstable snow bridge like the one you fell through in the first place. Move with care and stay on belay.

Depending on your mode of travel (boots, snowshoes, or skis), it may be necessary to drop your skis or snowshoes either to climb or ascend. Unhook them and let them dangle from their leashes (see fig. 5- 6), or stow them on your pack.

USING AN ASCENSION RIG

If you can't find any other way out and you are uninjured, then it is time to ascend. Some specifics, like your pack tether, chest harness, and your particular ascension rig may differ depending on the setup you're using.

1. Unhook your pack's waist belt and sternum strap and *gently* load your pack onto the rope. Hastily dropping your

pack only shocks the system (which may still be your partner holding your fall). The pack hanging below you will act as a weight holding the rope in place, making ascension easier (the same reason why aid climbers often ascend the line from which the haul bag hangs).

2. Unclip the rope from your chest harness.
3. Insert your feet into the foot loops. There is no need to tie your ascension rig onto the rope—in glacier travel it should already be in place.
4. Yell “Ascending” up to your teammates and start making your way up the line.

Fig. 5-7. A climber negotiates past a crevasse lip while ascending.



Use your body and feet to keep yourself off the wall if the wall is less than vertical. You want to keep the Prusik hitch as free of snow as possible. Snow caught in your Prusik will only make your job more difficult, as snowy, wet Prusiks are more difficult to slide up the line and do not catch as well.

The lip of the crevasse is usually the worst part of this process (see fig. 5-7). Often, as a climber falls, the climbing rope slices downward into the lip of the crevasse. The rope can be so deeply entrenched that the remaining team members above must send down a separate line and the climber must switch over, retying into the new line.

In the best of circumstances, your partners will pad the lip of the crevasse with an ice ax shaft or backpack. This way, as you approach the lip your weight on the line does not cause the rope to continue cutting into the snow deeper and deeper. As you approach the lip, batten down the hatches: pull up and tighten your hood, zip up everything, make sure snow can't slide down your sleeves, neck, or waistband.

Here are a few tips and tricks for passing the crevasse lip:

- Do not hesitate to use your ice ax to gain purchase in your upward push. If the snow is particularly soft, use the ice ax's shaft instead of the pick.
- Get aggressive with your feet, kicking footholds for purchase in your upward fight.
- Be wary that Prusiks can be a bit slower to catch once wet and choked with snow. You can minimize this clogging by trying to place your hand under the Prusik, protecting it as

you move it up the rope through the snow.

- If possible have one of your teammates toss you a line (either excess rope, a long strand of webbing, or a cordelette). This should be either attached to the anchor, or your partner can simply hold it as long as she is securely attached to either the anchor or the haul line and is in a secure position (butt and boots dug into the snow). Pull on the cord to help you with the final few feet. (Because your Prusik would take the weight of any slip you might take while ascending these last feet, this improvisational, hand-over-hand aid from your partner is acceptable.)

USING MECHANICAL ASCENDERS ON GLACIERS

Some people opt to use mechanical ascenders for their waist Prusik while crossing glaciers. Mechanical ascenders can easily be placed on and taken off the rope, an advantage if you are using fixed lines while on glaciated terrain.

But because of their camming action, mechanical ascenders should not be placed on a rope while traveling. As discussed above, the cam can severely damage the rope in a dynamic fall. Instead, mechanical ascenders should be kept clipped off to the side on a harness. Only after the fall should the ascender be placed on a rope.

Like the Prusik hitch, a mechanical ascender can get jammed with snow while ascending out of a crevasse. Be wary of the ascender's tendency to slip back down when placed on icy, snowy ropes. You must pull directly down on the ascender to achieve optimal bite on the rope, a sometimes difficult step when ascending through the less than vertical angle of a crevasse's lip.

PRACTICE: FIXED-LINE ASCENSION

Fixed-line ascension is easy to practice either by yourself or with a partner. Remember how slowly it goes on your first shot, then imagine having tried it for your first time hanging below the surface of an icy crevasse. You will be glad you practiced.

1. Fix a line to a solid anchor built off a tree or balcony, etc. To make it worth your efforts, aim to hang the line about 20 feet off the ground.
2. Now attach your ascension rig to the rope and start ascending. When you reach the top, descend back down.

If you have a partner, rather than fixing a line, create a top-rope anchor:

1. Have your partner put you on belay as if you were going to top-rope a climb, and attach your ascension rig to your side of the rope.
2. As you ascend, your partner belays slack through the system, providing you with at least half a rope length of fun ascending or torture (depending on how you look at it).

ASCENDING TO A HURT LEADER

If you are unable to lower your leader back down to the anchor (as discussed in chapter 4, Descending) and she is unable to assist herself, you will need to ascend to her.

With One Rope

1. If possible, have her reinforce the piece she is hanging on.

(Do not rule out the possibility of her creating an anchor, attaching herself to it, and fixing her end of the lead rope to the anchor.)

2. Examine your anchor carefully. Depending on the anchor's primary direction of pull you may need to add more (or reorient) pieces for the predominately upward pull of your fallen leader. Do your best! (See the chapter 3 sidebar, "Do You Need to Beef Up the Anchor?" for more thoughts on this.)
3. Escape the belay. By fixing the rope to the anchor you create a backup for yourself should (in a worst-case scenario) your partner's pieces fail while you are ascending.
4. If you plan on climbing while using the lead line only as a backup, use two waist-sized loops attached to the lead line with friction hitches. Use good movement on the rock as your primary means of protection while pushing your Prusiks ahead as you ascend. In some instances (e.g., if the rock is extremely overhanging), you may have to ascend the line with an ascension rig (described earlier in this chapter).
5. As you ascend you may want to remove some of the gear your partner placed, freeing it for use above. On the other hand, because you and your partner are relying on only the top piece of gear, additional pieces are your backup should the top piece fail—so leave a few of the lead pieces in as you ascend. Every situation will demand a different solution.
6. Once you reach your partner, build a new anchor. Transfer

both her and the rope to the anchor.
7. Depending on what your next steps are you will need to descend to free the bottom end of the climbing rope if it is fixed. How you choose to do so (e.g. single- or double-strand rappel or descending with your Prusik) will depend on the specific circumstances.

With More Than One Rope

The advantage of utilizing two ropes while ascending to an injured leader is that you are relying on two independent systems; one backs up the other.

1-4. Follow steps 1 through 4 for ascending with one rope.
5. Set up a new multidirectional anchor for upward pull (if you can).
6. Attach the top of the second rope to the new anchor and tie in to the bottom end.
7. Rope-solo (free or aid) up the route using the second line as the belay (see later in this chapter for a description of rope soloing). Clip your lead-line through the pieces of gear placed by the leader.

ROPE SOLOING

Climbing by yourself with a backup rope system is called *rope soloing*. Some climbers complete many climbs this way—everything from big-wall to small-crag climbs. It is possible to solo free climb and solo aid climb with a self-belay.

Times when you might choose to rope solo or rope solo aid in an improvised rescue scenario include climbing up to:

- Assist an injured leader.
- Retrieve a stuck rappel rope.
- Assist a partner who has become so incapacitated that he cannot belay you and the only way out is up. Rope soloing the pitch may be your best option.

The best way to rope solo is with a special device that allows the rope to feed through while you climb, but that locks if you fall (manufacturers of the Petzl GriGri and Trango Cinch do not recommend these devices for solo aiding though some people use them).

There are specific devices that work much better for rope soloing than what is described here. But, in keeping with the improvised character of self-rescue, we will assume you do not have such devices with you. The main challenge is to move up terrain that you feel comfortable on, staying protected by the rope despite there not being a second person belaying you.

These are acceptable systems. There *is* the possibility of longer falls if you have just put some slack into your rope backup system. A rescue is not the time to learn these systems, however—it is best to practice before you are in the heat of the moment.

Fig. 5-8. An overview of rope-soloing up to an injured leader. The rescuer has created a separate anchor and is using a second rope to ascend to the patient. The top of the rope stack is fixed to the anchor and the rescuer is tied in just a few yards away. As he ascends the rescuer adjusts his tie-in point to maintain an upward pull on the bottom anchor. The rescuer is also tied in to the bottom end of the rope (indicated by the outside line of rope between the rope stack and the rescuer).


OY VEY!
INJURED LEADER
ROPE-SOLO technique
ANCHORS RIGGED FOR UPWARD PULL
RESCUER USING SECOND ROPE

Rope Soloing, Basic Method

These systems can be used for rope-solo free climbing and rope-solo aid climbing. (Aiding refers to relying on gear placements rather than climbing movement to move up a rock face. See "French-Freeing" at the end of this chapter for more information on aid climbing.)

1. Attach the top end of the rope to a multidirectional anchor. This anchor should mainly protect for an upward pull.
2. Tie in to the other end of the rope (the bottom end of the rope stack).
3. From the anchor (the top of the rope stack), pull out enough rope to climb about 10 feet. Tie a bow line on a bight through your belay loop and clip the bight's tail off with a locking carabiner. (Alternately, you can tie a figure eight on a bight and clip it to two locking carabiners on your belay loop; we refer to this as your "short tie-in".)
4. Climb up about 5 feet and place a piece at your chest (or clip into your fallen leader's piece of gear). Clip in the rope between you and the anchor. You will have to experiment with distances, though you should not need to adjust your tie-in to let you continue climbing higher. Retie in so that you have 10 to 20 more feet of rope to climb with, and protect as

necessary. See fig. 5-8.

Fig. 5-9. An up-close look at rope soloing using a clove hitch as an adjustable clip-in point. The figure eight on a bight clipped to the belay loop with a locking carabiner serves as a back up to the clove hitch. (Approximately ten feet is a manageable amount of slack to maintain between the two knots.) As the climber ascends, these lengths will need to be adjusted periodically. Note how the climber is tied into the bottom end of the rope with a figure eight follow-through, while the top end of the rope is fixed to the anchor.


CLOVE HITCH
TIE INTO THE END OF THE ROPE
BACK UP KNOT
CAREFULLY STACKED ROPE
MULTI-DIRECTIONAL ANCHOR

Keep in mind:

- Throughout this process you need to remain tied in the whole time.
- When you retie in, tie your new knot first and then untie your old one.
- Remember that the slack from untying the old tie-in will add to the distance you can travel (or fall!).
- It is best not to have to retie in between protection placements.
- With this method, you are climbing with slack in the system and any fall will be as big as the slack you put in the system.
- Watch out for making ground or ledge falls possible by adding too much slack.
- Clip in short as a backup whenever possible.
- Move your leader's pieces of gear or *leap-frog* as necessary as you climb.

Rope Soloing, Alternate Method

High on a wall, where ground or ledge falls are not possible, there is a variation to the basic rope-soloing method. Since you may not hit anything if your short tie-in knot slips, you can use a clove hitch, which is easier to adjust but is less secure than a bowline or a figure eight.

1. After securing the top end of the rope to a multidirectional anchor, tie in to the other end (or measure off the distance you ultimately want to climb and tie in to the rope there).
2. Put a locking carabiner on your belay loop.
3. From the anchor, take enough rope to climb a bit, and then attach a clove hitch to your locker at that point.
4. Climb and protect as necessary, while adjusting rope through your clove hitch to allow further progress. The clove hitch is backed up by the tie-in you have at the end of the rope. Careful! Clove hitches need to be cinched down in order to work. Your movement during climbing can easily loosen a hitch. Make sure to set the clove hitch well and that you have a good backup knot.

These two methods can be combined: tie in using a bowline with 30 feet of slack in the system and then use a clove hitch to reduce the slack as you climb. The important thing is that the climbing should be relatively easy for you to consider using this technique, and you should try to estimate distances so that you do not have to fiddle with your knots during a tricky move.

FRENCH-FREEING

French-free is a term used by some U.S. climbers. Generally, when freeing a route you do not use your protection pieces for hand- or footholds. If you do, it is called “using a point of aid” or “French-freeing” (fig. 5-10). Without getting into the etymology or politics of the phrase, it is a good technique to employ if faced with a tough move, or if you are in a situation that you need to move quickly though and do not have time to work out the crux sequence. If a thunderstorm is impending and you are leading a tough pitch, you might want to speed it up with some selective gear grabbing.

- Clip a quickdraw to the bolt and grab the draw while clipping the rope; keep climbing.
- Place a piece and pull on it to get up to the next good handhold.
- Add a foot sling to a piece for a high reach. Free climbers generally regard this as poor style. But getting yourself out of trouble is very good style, so yard away—just don’t say you freed the route.

Fig. 5-10. French-freeing. To help himself through a difficult section, the climber grabs on a piece of gear that he may or

may not clip the lead rope through. He could also extend the piece of gear with a long sling for stepping up, in order to gain as much height as possible for his next placement.



SIMUL-CLIMBING

Simul-climbing (sometimes referred to as a “running belay system”) is a great technique that allows competent climbers to cover easy but exposed terrain quickly while maintaining some backup protection from a rope system. A common use of simul-climbing is on steep snow slopes. The team is roped together and all moving up the slope. The leader places protection and clips the rope through to it. The followers clip through, or if a climber is last on the rope he may clean the protection. This is a basic simul-climbing system.

On rock there are usually not more than two people on the rope, one tied to each end. The leader places protection and the follower takes it out when she gets to it. They should always have a few pieces of protection on the line between them. If either climber falls, he will probably pull the other off. Although the consequences would be greater had they not had a rope in the first place, falling while simul-climbing can still result in serious injury. The consequences of a fall necessitate the rope system, though the simul-climbing system is meant for speed over safety. Climbers should use it with caution: the terrain should be well within their abilities, the system protecting against the unlikely event of a fall. Climbers should not travel in exposed terrain roped together with no protection between them. Many climbers have died in serious accidents when traveling roped on steep slopes but without the use of protection.

If trouble arises while simul-climbing, the rescue procedures will be the same as in other situations. The climber at either end of the rope faces the potential of needing to build an anchor if there is trouble at the other end. For this reason it is always good for both climbers to have some gear and slings, just in case.

HELPING YOUR PARTNER AID THROUGH THE CRUX

If you anticipate your partner is going to have a difficult time with a route's crux, do not be shy about placing a piece of aid for him above the difficult move. Extend the piece's runner so that when your partner is right below the crux he will be able to reach the runner and pull on it; you can even build him a little etrier if need be. (This runner is not necessarily what you want to clip your lead rope in to. Use a runner of appropriate length for that.) Once past the difficult section, your partner can clean the protection. This trick can save precious time and energy on both ends of the rope.

The only way out is up!

CHAPTER 6

Raising

Raising a climber is never physically easy, but with practice a raising system is not necessarily tough to build. Some raising systems are quite complex, but we will start with simple systems and work our way up. All of the systems are described with the rescuer above the climber, and all systems are described using carabiners as the pulley mechanism.

Times you might want to raise a climber include:

- Giving a quick assist to your second through a short, tough section of the climb.
- Raising one pitch or less in order for a hurt, tired, wet climber to top out the climb.
- When using a crevasse rescue system (to get your partner back to the surface).
- During a multipitch rescue for an injured climber, where it is not possible to descend.

SIMPLE 1:1

A quick and helpful solution to a difficult crux section is to keep a tight belay, which may need to become more of a downright fish fight. The 1:1 pull is definitely effective, and all climbers (and certainly guides) have used it successfully. With good positioning, the lift can happen with the legs. Lock your belay device off while lifting, and then pull in captured rope while the climber fights to maintain his position. This method will not work if the climber can't assist while the belayer captures rope through the belay device.

With the climber above on a top-rope or through a redirect, it is possible to do a counterweight pull by locking your belay device and dropping to a crouch. Then, because of the friction at the top-rope carabiners, it is generally possible to quickly stand up and take in rope at the same time, locking off when standing again. Repeat this sequence. If you need to see this in action, head to the nearest super rad sport-climbing area. There should be plenty of folks using this technique to "work" routes.

DROP-LINE ASSIST 1:1

This next simple system is great for a short hard crux that leads to easier ground. It is not possible to do a drop-line assist if the climber is more than one-third the rope length from the rescuer/belayer. With a second rope you can do this assist with the climber a full pitch away.

Make sure the standing end of the rope is anchored to the master point (MP) (often it already is, if you are clipped in with a figure eight on a bight or clove hitch). Lower the rope stack to the climber. She can now use the rope to pull on as you belay her in. She gets to do the hard work! If she is adept at friction hitches, she can get busy and throw one on the spare line as well, pushing it up the rope as she ascends. You might also want to pre-tie loops before you throw the rope, so she has something to pull on. Simple is good!

DROP A LOOP 2:1

It is possible to convert a drop-line assist to a simple 2:1 pulley assist. However, the farthest the climber can be from you is about 75 feet (if you have two 160-foot ropes), or about 50 feet (if you have only one 160-foot rope).

Fig. 6-1. Raising Systems. A simple 2:1


ANCHOR
PULL

Fig. 6-2. Raising Systems. A drop loop assist is an easy way to create a 2:1.


ANCHOR
COW'S TAIL into the SHELF
REVERSO
GOOD STANCE
ROOF CRUX

1. Get hands-free: you will need your hands free of the belay for pulling.
2. Doublecheck that the standing end of the rope is attached to the anchor.
3. Clip a carabiner onto the rope stack. The carabiner should slide freely on the rope; do not tie it onto the rope in any way. Drop this rope and carabiner to the climber. Keep hold of the other end of the rope.
4. Have the climber take the carabiner and clip it in to his belay loop.
5. Now you can pull on the unanchored end of the rope you just dropped him. The climber can help by trying to pull on the anchored end of the rope. He should slowly go up.

Caution! The climber is tied off to the belay at his starting height. So if you let go he will drop back down to the tie-off point. For a quick short-aid section, it might be fine to hand-haul. For a longer pull use a Prusik to take in slack or put a locking carabiner with a Munter on the MP or shelf. As you pull up, take in the slack through the Munter. In cases of a long haul (e.g., the rest of the pitch), it would be best to completely escape the belay (since you will not be resuming it).

This 2:1 can also be used in crevasse rescue. It is a good way to get the climber out of a crevasse that has a nasty lip above the climber's original line.

3:1 SYSTEMS

A 3:1 raising system is a good way to get a climber up a short section without dropping a rope to him. There are a number of variations to building a 3:1: it can be built on the anchor, with a self-blocking belay device, with a Garda hitch, off your harness, and as a complex 3:1 (aka the *Spanish Burton*), which allows for pulling in a downward direction.

It is best to do long raises off the anchor (as opposed to off your harness). If you are building a system specifically to raise someone, there are several things you can do to help yourself out:

- Build the anchor high, mainly so the rope runs cleanly over the edge of the ledge you might be on, but also so you have some room to work.
- If you have pulleys, use them instead of carabiners—one attached to the pulley-point Prusik and one at the anchor pulley.

■Create a *self-tending ratchet Prusik* by putting a belay device (like an ATC) on the loaded line running through the anchor. The ATC will not provide friction, though it will block the ratchet Prusik from flipping through the carabiner through which the climbing rope runs (or from getting sucked up by the anchor pulley if you are not using a specialized Prusik-minding pulley). Creating a self-tending ratchet Prusik saves you the effort of resetting the ratchet and maintaining it. If you do not have a belay device to insert here, you will need to watch the ratchet very carefully.

Fig. 6-3. Raising Systems. A simple 3:1. “A” indicates the anchor pulley point, “B” the ratchet Prusik; “C” the pulley point carabiner, and “D” the pulley point Prusik.


ANCHOR
A
ANCHOR PULLEY POINT
PULL
B
RATCHET PRUSIK
C
PULLEY POINT CARABINER
D
PULLEY POINT PRUSIK

3:1 OFF THE ANCHOR

1. If belaying off the anchor, get hands-free. If belaying off your body, escape the belay.
2. Take a rescue loop and tie a Prusik onto the weighted belay strand. Clip the loop into a locking carabiner on the master point or shelf. (This is the ratchet Prusik.)
3. Take another rescue loop and reach forward, down the loaded strand leading to your climber, as far as you can and attach the rescue loop with a Prusik hitch at that point on the line—a "pulley point." (A rescue loop tied in this manner is the pulley-point Prusik.)
4. Clip a locking carabiner to this pulley-point Prusik and then clip the loose brake strand through the carabiner. (If carrying a pulley, use it here instead of a locking carabiner.) Maintain a hand on the brake strand while you complete the remaining steps.
5. If an ATC is available, use it to create a self-tending ratchet. Attach it to the brake strand as close as possible to where the rope exits the Munter-mule-overhand (MMO). Clip

a locking carabiner around the rope and through the belay device and attach it to the MP. (This locking carabiner is the anchor pulley.)

6. Transfer the load onto the ratchet Prusik by slowly undoing the mule-overhand and the Munter. Remove the carabiner on which the MMO was tied. Pull in all slack.
7. Once you have removed all slack created by undoing the MMO, you are now ready to haul. As you pull in line you may need to "set" the ratchet by pushing it forward before easing off your pulling. Eventually the pulley-point Prusik will reach your belay device. At this point you will need to reset it.
8. To reset the pulley-point Prusik, ease off the line, letting the ratchet hold the climber's weight, and then push the pulley-point Prusik as far forward as you can. Repeat as necessary.

Fig. 6-4. A 3:1 raising system with self-blocking belay device. "A" indicates the self-blocking belay device (which replaces the need for a ratchet Prusik); "B" the load strand; "C" the pulley point Prusik; "D" the haul strand.


A
D
C
B

3:1 WITH SELF-BLOCKING OR LOCKING-ASSIST BELAY DEVICE

If belaying off the anchor with a self-blocking or *locking-assist belay device*, there is no need to set a ratchet Prusik. Simply follow steps 3 and 4 above in "3:1 Off the Anchor." Eventually you will have to reset the pulley-point Prusik, following step 7. Fig. 6-4 shows a 3:1 system with a self-blocking device.

3:1 WITH A GARDA HITCH

Some climbers choose to build a 3:1 with a Garda hitch. This eliminates the need for a ratchet (and ratchet tending). It is fast and easy to set. One major downfall, however, is that this system is not easily reversible.

Fig. 6-5. A 3:1 employing the use of a Garda hitch. Note how the Garda is tied; the loop (see "Tying a Garda, step 3" in chapter 2) is clipped into the carabiner that corresponds to the side of the rope that you want holding the load.


ANCHOR
PULL

1. If belaying off your body, escape the belay, but instead of tying a MMO on the MP with the climbing rope, tie a Garda. If belaying off the anchor with a Munter, attach two nonlocking carabiners to the MP or shelf on the same side of the brake strand. While carefully maintaining your brake hand, tie a Garda hitch.
2. Pick up at steps 3 and 4 described above in “3:1 Off the Anchor.” Take great care to maintain a hand on the brake strand while you do this.
3. Pull in the excess slack and undo the Munter hitch, removing the carabiner that the Munter was tied to.

Eventually you will need to reset, picking up as described in step 7 of “3:1 Off the Anchor.”

3:1 OFF YOUR HARNESS

This system can also be set up off your harness when belaying off your body with a belay device. Instead of escaping the belay, get hands-free and pick up at step 2 described above in “3:1 Off the Anchor.” (You can skip step 5, assuming your belay device is already part of the system).

Because the climber's weight is entirely on you (and then some, because of the pulley effect that multiplies forces), a 3:1 off your harness may be uncomfortable and will certainly hinder your range of motion, restricting your ability to put your weight into the pull. But if you are concerned about trusting your anchor with the forces of hauling, if you need to haul your partner just a short distance, or if you want a speedy solution (no belay escapes with this one!), it is a viable option. Make sure you are in a secure position and the system is backed up on the anchor.

Fig. 6-6. The Spanish Burton is a complex 3:1 configured so that the rescuer may pull downward instead of up.


ANCHOR
PULL

A 3:1 in action.

COMPLEX 3:1 SPANISH BURTON

A Spanish Burton puts gravity on your side with a downward pull. This is a big advantage if you are trying to raise someone significantly heavier than you up a vertical face.

1-3. Follow steps 1-3 described above in “3:1 Off the Anchor.”
4. Attach a cordelette (or runner) to the rescue loop you just placed on the load strand in step 3.
5. Attach a rescue loop to the brake strand with a Prusik hitch. The rescue loop and carabiner (or pulley) coming off this Prusik will be your pulley-point Prusik.
6. Clip the cordelette (or runner) introduced in step 4 through the pulley-point Prusik. This cordelette is what you will pull on.
7. Pick up at step 5 described above in “3:1 Off the Anchor,” and continue with the remaining steps.

PULLEY VERSUS CARABINER EFFICIENCY

Fig. 6-7. (A) A wire-gate carabiner, (B) A DMM Revolver carabiner, which incorporates a small pulley into the carabiner’s base, (C) A basic climbing pulley, and (D) A

Prusik-minding pulley.

When a rope runs over or around something, there is friction. The more pronounced the angle of contact, the rougher the surface, and the more weight against the surface, the more the friction. If a rope holding 100 pounds were to run over a surface with an efficiency loss due to friction of 50 percent, you would need to double your effort and pull with 200 pounds of force in order to raise the load. Friction is our enemy in mechanical advantage systems. It makes us work harder and it puts higher forces on our gear than if we were working in a frictionless world. Different combinations of ropes and carabiners, along with the actual forces in play, will result in different friction coefficients.

Below we list efficiencies for carabiners and pulleys. This is intended for general information purposes and does not apply to all situations or all combinations of gear.



Oval carabiner: 70 percent
DMM's Revolver: 75–80 percent
Basic climbing pulley: 80–85 percent
High-quality rescue pulley: 90+ percent

What efficiency percentages mean: If a carabiner has 70 percent efficiency and we are raising 100 pounds with it on a 2:1 system, we will have to lift with 59 pounds (not getting into static friction coefficients and rope-stretch details). If we are using a 3:1 system and there are two carabiners in the system, we will have to pull with 46 pounds—far from the 33.3 pounds of the frictionless world!

Note the diminishing returns as well. The more carabiners we add to the system, the smaller the gain. The forces on our gear keep going up, but we get less out of the system because the inefficiencies add up. Interestingly, when we stack a 3:1 on a 3:1 using carabiners to build the system, we need to input 21 pounds to lift 100. If instead we stack a 2:1 on a 3:1, we need to input 27 pounds to lift 100. Not much difference. These systems are supposed to be 9:1 and 6:1 respectively but lot of force is lost through friction!

This highlights the difference between *ideal mechanical advantage* (e.g. 9:1) and *theoretical mechanical advantage:* the resulting mechanical advantage once friction generated by pulleys, carabiners, cliff edges, etc. is accounted for. Because of the amount of efficiency lost to friction it is not always worth building more involved systems unless you have high quality pulleys.

IF YOU NEED MORE!

How large a system do you want? We already said simple is better and we know friction is eating away at our efficiency (especially if we are using carabiners instead of pulleys), but what system will be enough to get the job done? Here are a few more points to consider with raising systems.

Mechanical advantage or change of direction? Mechanical advantage explains how work is spread out over time and distance. For the purposes of improvised self-rescue, “mechanical advantage” can be thought of in these simplified terms: with a mechanical advantage ratio of 3:1, for every three feet of rope pulled through the system, your patient will be raised one foot. With a 9:1, for every nine feet of rope pulled through the system your patient will be raised one foot. When building a mechanical advantage system, if the last pulley is attached to the anchor and is *not* moving, it is not helping with the mechanical advantage. Instead, it is termed a “change of direction.” This is good if you want to pull down instead of up, but not if you are concerned about friction. It is only adding more friction to the system, not any mechanical advantage. That being said, do not be afraid to add a change of direction to any of your systems, if it will help. Note the Spanish Burton: the last pulley is moving so it *is* helping with mechanical advantage.

How big do you go? In the sidebar “Pulley versus Carabiner Efficiency” we give some real-world numbers relating to input effort for different systems to raise a 100-pound load. These numbers merely look at friction at the pulley points and do not look at friction or losses throughout the rest of the system. Building a wonderful 3:1 to pull up our 200-pound buddy is not such a rosy picture when we look at all the losses in the system. If the rope runs sharply over an edge, say a 90-degree bend (ouch!), you can lose as much as 50 percent of your effort. That means if you have a 3:1 built with climbing pulleys (83 percent efficiency), and your rope runs over a bare rock edge down to the 200-pound patient, you need to pull with 120 pounds! You would only have to pull with 80 pounds if that edge was not there. (Reducing edge angles is another reason to rig high.)

Fig. 6-8. Because the quickdraw coming off the anchor is stationary it does not add mechanical advantage to this 3:1 pulley. All the quickdraw does is provide a change of direction so that the belayer can pull downwards. Because of the added friction the change of direction carbiner creates, it would make more sense to raise with a Spanish Burton (a 3:1 that already incorporates a downward pull).


ANCHOR
PULL

One easy way to increase your system's efficiency is to replace carabiners used as pulley points with actual pulleys. Some climbers would say you are foolish to head up a long multipitch climb without a pulley. This simple substitution reduces a large amount of friction in the system. (DMM's Revolver—a carabiner with a small, built-in pulley—is a lightweight solution). If you are dealing with obstacles like sharp edges, don't forget to consider protecting your rope with some impromptu edge protection: extra clothes, a pack, an ice ax shaft, and so on. Remember to secure the item to the anchor.

Keeping the system clean, simple, and straight will get you more bang for your effort than adding advantage with pulleys to an inefficient system. But if inefficiencies are unavoidable, then yes, you may need to look at adding more mechanical advantage. Note also that the forces you are putting on your anchor when raising are much higher than in normal climbing scenarios. Do you need to beef up your anchor? If you pull on a system and there is something stuck, like a knot in a crack, and you continue pulling, the forces exerted on the anchor could sky-rocket. A good rule of thumb when building these systems is that you should definitely be able to feel the load when you pull on the system; this also helps safeguard against pulling your patient up through an obstacle (a ledge, vegetation, a crevasse lip, a stuck section of rope, etc.), which could result in serious injury and putting undue forces on the anchor.

TURNING A SIMPLE 3:1 INTO A COMPLEX 5:1

This is a nice little system that allows you some more mechanical advantage: a 5:1, with just a little adjusting.

1. Clip a long single strand length of webbing or cord through your anchor's shelf. (The longer the piece of webbing the better)
2. Clip the webbing through the carabiner attached to the pulley-point Prusik.
3. Clip the haul line through a carabiner attached to the other end of the webbing strand. (See illustration 6-9.)

MULTIPLYING ADVANTAGE

The basic 2:1 and 3:1 are excellent for the majority of needs; sometimes you might want a system with bigger mechanical advantage, like the 5:1 systems described above. It is also possible to gain much more advantage, without making the system too involved, by stacking systems. If you build a 2:1 to pull (act on) a 3:1, you get a 6:1—the advantage is multiplied. So if you pull on a 3:1 acting on a 3:1, you get a 9:1. That's a lot of force! Again, your anchors need to be able to handle the forces you create; and the forces are higher than ideal due to friction in the system. Friction in the system also makes the higher mechanical advantage systems much less efficient unless you include some pulleys in place of carabiners.

Generally, on a small rock ledge space is an issue, so stacking systems is tough to do. On a glacier there is more space to work, so it is easier to build bigger, more complex systems. Keep it simple. It is often more efficient to pull harder than it is to add more carabiners (friction) and bends in the rope (friction).

Raising systems can get quite involved, and we do not discuss the more complex systems that may be used in larger rescues.

Fig. 6-9. A complex 5:1. A 3:1 can be quickly turned into a 5:1 with the addition of just two carabiners and a piece of webbing.


ANCHOR
PULL

Fig. 6-10. Raising System. A compound 9:1. A 3:1 acting on a 3:1.


ANCHOR
PULL

In reality, the 2:1 and 3:1 presented above should take care of a majority of small-party rescue situations. If you need more complex systems, you also may need more people and more gear than you have with you. Just because you can build it does not mean your equipment can handle it. Remember to tie off the original system when you are in the process of adding advantage.

BUILDING A 2:1 ACTING ON A 3:1

1. Take a long sling, cord, or the standing end of the rope. Clip it directly to the anchor.
2. Tie a Prusik with a rescue loop on the haul line of the 3:1 and clip a locking carabiner to it (this is a second, new pulley-point carabiner).
3. Clip your new piece of sling/cord/ rope (introduced in step 1) through the new pulley-point carabiner.
4. Push both pulley-point carabiners down the lines as far as possible while the ratchet Prusik holds the load.
5. Haul on the new piece of sling/cord/ rope.
6. You are now using a compound 6:1.

Reset the pulley-point Prusiks as necessary.

BUILDING A 3:1 ACTING ON A 3:1

1. Clip a locking carabiner in to the MP or shelf of your anchor.
2. Slide the pulley-point Prusik down the rope as far as possible.
3. Tie a Prusik with a rescue loop on the haul line of the 3:1 and clip a locker to it (just as in step 2 of "Building a 2:1 Acting on a 3:1").
4. Clip the haul line through the new locker on the anchor and then run it back down and clip it through the locker on the rescue loop.
5. You now have a compound 9:1. Pull and reset the pulley-point Prusiks as necessary.

Though it looks like a mess, passing knots is a simple process.



CHAPTER 7

Passing Knots

Passing a knot can be a necessary maneuver in all sorts of situations: ascending or descending a fixed line, hauling, rappelling, or belaying—in short, any time two ropes have been tied together to create one, long continuous line or there is a knot isolating a damaged section of rope.

The common element, no matter what direction you are moving on the rope (or are moving someone else via belaying or hauling), is to maintain a secure connection to the rope at all times while moving around the knot—*around* being the key word.

ASCENDING AND DESCENDING

Regardless of whether you are using mechanical ascenders or an ascension rig, these same steps apply for passing a knot while ascending or descending. We describe both processes with the climber using a tied ascension rig.

ASCENDING

1. Ascend until your waist Prusik is within an inch or two of the knot.
2. Attach a cordelette (preferably a rescue loop) with a friction hitch above the knot. This will become your new waist Prusik.
3. Stand in your foot Prusik and, with a carabiner clipped through your belay loop, clip in to the new waist Prusik.
4. Hang on the new waist Prusik and remove the old waist Prusik (reset the old waist Prusik above the knot if you need to keep using it, that is, if the length of the new waist Prusik makes ascending inefficient).
5. Continue ascending until your foot Prusik hits the knot. Remove your foot Prusik and reset it above the knot.

You have passed the knot and can continue ascending the line.

IMPROVISE: PASSING A KNOT ON A SINGLE-STRAND LINE

If you know you will be descending or ascending a single-strand line with a knot prior to loading the line, here is a useful variation. We use rappelling as an example. This technique will not work as described with double ropes; it can only be implemented on a fixed, single-strand line.

1. When tying two ropes together, leave an extra foot of tail on the side exiting closest to the ground. Tie a figure eight on a bight (overhand on a bight if you do not have enough line) in that tail.
2. When you arrive at the knot you need to pass, simply clip in to the knot tied on the tail with some sort of tether. This becomes your primary attachment to the rope.
3. Follow steps previously described in “Ascending.” Transition your weight back onto your descent device. Do not forget to take your foot Prusik with you!

The last person to use the knot tied on the tail should undo it to avoid possible snagging when the rope is either pulled up or dropped.

Fig. 7-1. Passing a knot on a single strand line. Clipping into the figure eight on a bight tied on the Flemish bend’s tail provides a quick and easy way to back yourself up as you pass the knot.



DESCENDING

To descend, follow the same process as ascending, but in reverse:

1. Descend until your foot Prusik is at the knot and your waist Prusik is 4 to 5 inches above the knot. While weighting your waist Prusik, remove your foot Prusik and reset it on the line right below the knot.
2. Place a temporary waist Prusik below the knot with a friction hitch and transfer your body weight down to it.
3. Reset your main waist Prusik below the knot. Simple!

Note: Either ascending or descending, it is possible to pass the knot without a spare waist Prusik, but you will need to stand in your foot loop, remove your waist Prusik, and replace it all with one hand. For the short time during which you remove your waist Prusik, you are only attached to the rope by one means: your foot Prusik. This is a good reason for tying in short every 10 feet or so with a figure eight on a bight. If you are unable to, due to weight at the end of the line or it being fixed, be cautious and make sure you are backed up, attached to the line at two points.

RAPPELLING

In order to pass a knot while rappelling, you need your hands free to manipulate the rope; anticipate this and have some sort of backup belay in place before you start heading down. The process of passing a knot on rappel is the same regardless of if you are rappelling one strand of rope or two. (See fig. 7-2.)

1. About 6 inches to a foot before your rappel device hits the knot, stop, let your third hand engage, achieving "hands-free," and pull out your cordelette.
2. Pull up about 10 feet of the rappel line, and then tie a figure eight on a bight and clip it to your belay loop with a locking carabiner as a backup. Use both rope strands if it is a double-strand rappel.
3. Tie your long cordelette in a loop using a bend, and attach it to the rappel ropes with a Prusik hitch a few inches above your belay device.
4. Clip a locking carabiner in to your belay loop, and with the excess cordelette tail, tie a Munter-mule-overhand (MMO) onto the carabiner. (This is the PMMO sequence, just tied and attached in a different place.)

5. Push the Prusik up the line, removing as much slack as possible. (Take care to create the MMO in a tight package so that it does not get pushed up out of reach).
6. Lower yourself onto the cordelette using your rappel device.
7. With the cordelette holding your weight, remove your rappel device and reset it on the line just below the knot.
8. Reset your third hand onto the rope below your rappel device. Or tie off the rappel with leg wraps or a mule-overhand.
9. Undo the mule overhand tied with the cordelette on your carabiner and slowly lower yourself back onto the climbing rope using the cordelette's Munter hitch.
10. Once you have transferred your weight back onto your rappel device, you can unthread the Munter, and reach up and remove the Prusik hitch from the top line.
11. Undo your backup tie-in and start rappelling again.

Fig. 7-2. Passing a knot while top rope lowering. If a second belayer is not available to help you with passing a knot while top rope belaying you will need to tie a PMMO with a cordalette. The process is almost identical to passing a knot on rappel; the cordalette holds the climber's weight while you move the belay device around the knot, then use the cordalette

to transfer the weight back onto the belay device.


THREE WRAP PRUSIK
LOCK OFF the TAIL
MULE KNOT
MUNTER HITCH
BELAY DEVICE
BRAKE HAND
LONG TAIL!
HARNESS
KNOT CONNECTING TWO ROPES
BACK UP KNOT
about SIX FEET

Fig. 7-3. Passing a knot while rappelling. The PMMO tied with the cordalette will hold the climber's weight as he moves his belay device around the damaged section of rope. He can then employ the Munter to transfer his weight back onto his belay device. Once the weight transfer is complete he will remove the cordalette from the climbing rope. The figure eight on a bight serves as a backup while he passes the knot.


PPMO
THREE WRAP PRUSIK
LOCK OFF the TAIL
MULE KNOT & MUNTER HITCH
BELAY DEVICE
LONG TAIL!
HARNESS
BRAKE HAND
DAMAGED ROPE TIED OFF with a BUTTERFLY KNOT
BACK UP KNOT
about SIX FEET

SETTING THE PRUSIK CORRECTLY

The length of the loop you create on your cordelette and where you tie the Prusik that attaches your cordelette to the rope are both important. If you do not get these measures right, you will end up wasting a lot of time, hanging in an uncomfortable position. For example, take a look at passing a knot on rappel. If you tie your Prusik on too high up, you will never be able to reach it once you move around the knot. But if you do not make your cordelette loop long enough, you will have a tough time getting back onto your belay device. In that same vein, if you rappel down too close to the knot, you will have trouble getting out of your rappel device. All these reasons make passing a knot on rappel a good skill to practice.

ON A TOP ROPE

TOP-ROPE BELAYING

The simplest way to pass a knot while top-rope belaying is to employ the help of another person:

1. Belay the climber as normal until you are just 1 to 2 inches from the knot. At this point, ask the climber to wait for a moment on the climb.
2. Take a couple steps forward and have the third person clip her belay device in to the climber strand on the other side of the knot.
3. The belay is immediately transferred to your recruited helper.
4. The new belayer can start taking in slack as the climber climbs. You can unclip your belay device from your harness if you want, or leave it on for the lowering transition (described below).

If you do not have another person at your disposal, start at a new step 2:

2. With a little slack in the climbing line, load a second belay

device onto the rope above the knot. (Assuming the climber can temporarily unweight the rope, you may want to do some leg wraps with the belay line to free your hands for this.)
3. Attach this second belay device to your harness and start belaying. You can leave the first one on for the lowering transition.

TOP-ROPE LOWERING

The simplest way to pass a knot while top-rope lowering is, again, to employ the help of another person:

1. As described above, you transferred the climber to your recruited helper's belay device; now the helper starts the lower once the climb is finished. Have your helper lower the climber all the way to the knot.
2. At this point, let your climber know you need to pass the knot. If possible have him unweight the rope by using a good foothold, handhold, or ledge. If he is unable to do this, things will be a bit harder for you.
3. While your helper locks off the climber's belay (the knot is a great backup here), put your belay device on below the knot. If you passed this knot while the climber was going up, you

may have left your device attached to the rope, and all you need to do is reattach the device to your harness.

4. Let your partner know you are ready to continue belaying.

5. Have your helper step forward and unclip her belay device from her harness. It can remain on the line while you finish lowering the climber.

For both passing a knot while top-rope belaying or lowering, the steps are the same if you are by yourself. It is best to get hands-free to do the transitions from one belay device to another.

See fig. 7-3 for instructions as to how to pass a knot while top roping. The steps are very similar to passing a knot on rappel as previously described.

LOWERING ON THE ANCHOR

1. About 10 inches before the knot (“1A” in fig. 7-4) reaches the Munter hitch, free your hands with a mule. Rather than tying an overhand back-up clip the mule’s loop off with a carabiner; it saves rope and keeps the system short. (See the completed mule and backup “1B” in fig. 7-5).

2. Tie a friction hitch (a Prusik) on the load strand using the cordelette (2 in fig. 7-6).

3. Tie the other end of the cordelette to a free locking carabiner (on the MP) with a MMO; this completes the PMMO (3 in fig. 7-6).

4. Take the rope beyond the offending knot and set up an MMO with this section of rope onto another locker clipped in to the anchor (4 in fig. 7-6). (Alternately, you could use a self-blocking or locking assist belay device if you had one. Insert the belay device onto the rope with a locking carabiner and tie it off with a mule overhand.) You should now have three tied-off belays in a row.

5. Undo the mule backup clip and let the Prusik hold the load (fig. 7-7).

6. Undo the MMO on the cordelette and lower the climber until the tied-off rope is loaded after the knot (fig. 7-8).

7. Undo the Prusik hitch and Munter hitch tied with the cordelette and remove the cordelette from the system (fig. 7-8).

8. Undo the mule-overhand in the rope and continue lowering the climber using the Munter now that the knot has been passed.

PASSING A KNOT WHILE LOWERING

Fig. 7-4. About 10 inches before the knot (1A) reaches your belay device, prepare to free your hands with a mule hitch and backup.


1A
to climber

Fig. 7-5. Step 1, completed. "1A" indicates the knot to be passed; "1B" is the Munter mule and backup.


1B
1A
to climber

Fig. 7-6. Steps 2, 3 and 4.



Fig. 7-7. Step 5.



Fig. 7-8. Step 6. Once the knot is passed, remove the cordalette from the system (step 7) and undo the mule-overhand (step 8).



Fig. 7-9. Completed knot pass. Continue lowering on the Munter hitch.



PRACTICE: PASSING KNOTS

One advantage to the process of passing a knot—either while ascending, descending, or while on rappel—is that you are always attached to the rope in at least two places: by one of your Prusik knots and by the backup knots tied every 10 feet and attached to your harness. Although these backups are relatively foolproof, we still recommend practicing on the ground before going vertical and using a fixed line for backup the first time off the ground. Note: It helps when practicing to have weight on the line.

RAISING

If you are unfamiliar with the construction and anatomy of raising systems, you will find it useful to read chapter 6, Raising, in order to gain an understanding of what this technique is all about.

These steps are for use on a 3:1 raising system. Other systems will be similarly easy. The knot will first appear below the moving pulley-point Prusik on the load strand.

1. When resetting the pulley-point Prusik, simply loosen and move the Prusik hitch to the climber side of the knot.
2. Continue hauling until the knot is just a few inches away from the ratchet Prusik.

3. While the ratchet does its job—holding the weight of the climber without letting him slip back down—make a new ratchet on the other side of the knot. You can construct this extra ratchet many ways: use a short rescue loop to tie a Prusik and then clip the rescue loop to the anchor with a sling (you can also just use a long cordelette). It is easier to pass the knot if the new ratchet is longer than the original one.
4. Haul a bit more to transfer the load to the new ratchet—you will have to set the new ratchet (to allow it to hold your patient's weight) and then remove the old ratchet.
5. Clip a new locking carabiner to the MP. Tie a backup knot on the free end of the haul line and clip it into the locking carabiner. (This is the system backup.)
6. Haul your partner a few more inches until the knot is against the anchor pulley point or your belay device. Make sure the ratchet is engaged, and then move the MP around the knot onto the new line. You may need to extend the MP with a runner to get the knot to the other side. Once the knot is passed, undo the backup knot and continue hauling.

ISOLATING ROPE DAMAGE

A butterfly is the knot of choice for isolating rope damage.

1. Take a bight of rope and turn it in a full circle. The rope will cross itself over in two sections creating a top loop, a middle loop, and a "bight"(for lack of a better term) on the bottom.
2. Take the top loop and bring it down and under the "bight" through to the other side. (Make it easier on yourself by bringing the loop in whichever direction maintains the structure of the top loop.)
3. Continue, bringing the top loop through the middle loop. (You will actually be traveling through two loops, the second one resulting from the top loop having folded downward.)
4. Pull the loop through until snug and dress.

Fig. 7-10. Butterfly knot. Left: Step 1, with arrow indicating steps 2 and 3. Right: Completed knot



Big mountains, high altitude, and technical terrain are a recipe for the unexpected.



CHAPTER 8

Scenarios and Solutions

Here is an opportunity to test your knowledge and understanding of the techniques covered in this book and to hone your problem-solving capabilities by looking at incidents that really have happened in the vertical world.

Each scenario presented is followed by a solution, a discussion of potential pitfalls (if any), tips for prevention, and a list of skills to review (not all skills to review are discussed in this book; we highlight those necessary to solve the situation). In addition to the primary solution, viable alternatives may be presented; generally, the solution presented first is a simple or fast option. Some scenarios have multiple solutions, but in the interest of space we have not covered all possibilities.

You will get the most benefit by working through the scenarios before reading the solutions. Formulate your own solution first. Then test yourself further by asking:

What are alternative solutions? Potential pitfalls? Ways of preventing the problem in the first place?

To test yourself even further, review the six emergency procedures discussed in chapter 1: plan ahead and prepare, assess the scene, initiate first aid, make a plan, rescue, and follow through. Imagine what these steps would look like in some of the areas where you enjoy climbing.

Note: Scenarios range from the simple to the complex.

Invariably you may disagree with us on our approach to a particular scenario or solution. But regardless of if you breeze through a scenario or find yourself scratching your head, the exercise will be helping you to meet the goal of developing critical-thinking climbing skills.

We assume that you have the following equipment with you:

- One single dynamic rope per party, 50-60 meters (160-200 ft)
- Second rope indicated if a part of the scenario
- Six nonlocking carabiners
- Either a traditional or sport climbing rack for the leader
- Six locking carabiners
- Forty feet of 7-millimeter accessory cord cut into five lengths (discussed in text)
- Some webbing for creating runners
- Tubular belay device (like an ATC)
- UIAA-rated harness
- UIAA-rated helmet
- A small knife

SCENARIO 1

You have been struggling on the third and final pitch of this traditional route for quite a while; in fact, you are so tired from the previous attempts, you have given up. You yell up to your belayer that you need a boost, but no luck. She does not seem to hear you. Your belayer mainly sport climbs and you are pretty sure she is not familiar with raising systems or assists. What can you do to get yourself past the crux besides praying for a sudden miracle?

SOLUTION

It's a trad route so you should have cleaned a bit of gear from the route that could be placed and used as a point of aid. Considering the gear's application (you are on belay from above) it doesn't need to be a bomber piece of gear; just make sure it's attached to something in case it blows. You hopefully also have some slings and cordelettes with which to quickly make an ascension rig if you can't French-free your way up.

POTENTIAL PITFALLS

If you end up ascending, be careful when you start climbing on the rock again, after you have Prusiked past the crux. Slowly slide your Prusiks off the rope so that your partner can take up the slack with the belay. Do not just climb with your Prusiks on the line and a loop of slack below you.

PREVENTION

Pick appropriate routes. Do not wear yourself out on one particular move. Always be prepared—in particular, know what your partner is capable of and what you might have to do for yourself.

SKILLS TO REVIEW

French-freeing, tying an ascension rig and ascending a fixed line (chapter 5).

SCENARIO 2

After flying into Denver International Airport from Florida, you and your partner rent a car and head straight for Rocky Mountain National Park. Less than 24 hours later, you are standing on the summit of a pinnacle (elevation: close to 13,000 feet). Throughout the several-hour, seven-pitch climb, your partner has not been feeling quite himself (he chalks it up to being dehydrated). He continues to deteriorate and at the summit he tells you he feels like he is on the verge of passing out; he is nervous about his ability to rappel. How will the two of you safely descend? There is no walk-off.

SOLUTIONS

There are multiple solutions to this scenario, the simplest being to tandem rappel as long as you trust your anchors with your and your partner's combined weight. This way you would be with your partner if he faints.

You could also employ a cow's tail for your partner's rappel rig. Back him up with a fireman's belay as he makes his way down. Remember, as the first rappeller, to use a third hand as a backup.

PREVENTION

Rapid changes in altitude, as experienced in this scenario, can take their toll on the body in many ways, especially if compounded by dehydration, exhaustion, or a calorie deficit. Give yourself time to acclimatize. Perhaps your partner should have spoken up about his condition earlier.

SKILLS TO REVIEW

Tandem rappelling, third-hand backup, fireman's belay (chapter 4)

SCENARIO 3

While traveling on a popular glacier route, your partner falls into a crevasse. You are traveling in a team of two. You quickly set up a compound 9:1 raising system. Your partner has fallen 30 feet and the process is slowgoing. Soon another two-person team arrives on the scene. How can you best use these additional people to help you?

SOLUTION

Drop that raising system down. The higher a raising system's mechanical advantage, the less the distance you are actually raising your patient per pull. Turn it back to a 3:1 and haul on it. It will be faster and easier for everyone.

POTENTIAL PITFALLS

Pulling on a big-advantage system with a lot of people can be hard on your anchors, gear, and patient. Remember while pulling that you should still feel your patient's weight to guard against injuring him.

PREVENTION

Crevasse falls are part of the risk of traveling through glaciated terrain. There are of course several measures that can be taken to improve your chances of safe travel: using a probe, receiving a more formal belay, and/or crawling on all fours over suspicious snow bridges. If you find yourself punching through consistently, it is important to consider if it is really appropriate to be traveling in crevasse country in such conditions. Should you be traveling instead at night, when it is cooler, or wait a day to see if conditions firm up?

SKILLS TO REVIEW

3:1 and 9:1 raising systems (see chapter 6)

SCENARIO 4

Your climbing partner is following your trad lead, struggling desperately with a route's crux move. After 15 minutes, he gives up. Spent, he asks you for assistance. He is about 15 meters from the belay station. What is the simplest way for you to assist him and/or for him to help himself?

SOLUTIONS

There are a variety of solutions to this scenario, ranging from simple to overkill and complicated. First: Your partner can always pull on the runners of the gear placed above him for assistance (in lead climbing this is called "using a point of aid" or French-freeing). If he has any extra runners, gathered from cleaning the rest of the route, he can girth-hitch several together to create a makeshift etrier to help him through the crux. He can also place any gear he has with him, accumulated from cleaning the route, into the crack and employ the techniques listed above.

If none of the above solutions work, the next easiest thing is to get your hands free with a mule-overhand. Then secure a section of the brake strand to the anchor with a figure eight on a bight or a clove hitch, and lower the remaining slack down to him. Because it is a fixed line, he can pull on it all he wants for assistance while you continue belaying him up. If for some reason he cannot pull, the next option would be a drop-line assist.

POTENTIAL PITFALLS

If your partner had not yet climbed close enough to the belay, then you would not have enough rope to send down to him. You would have to rely on a more involved raising system such as a 3:1.

PREVENTION

It is worth asking yourself as the leader if this route is appropriate for your partner. Had you anticipated that your partner might have problems, you could have set a piece with a long sling (or created an etrier by girth-hitching several slings/runners together to the desired length) above the crux—long enough so that he could reach it and pull himself up through the crux. Consider if you should do something similar for the following pitches.

SKILLS TO REVIEW

Mule-overhand (chapter 2), getting hands-free (chapter 3), French-freeing (chapter 5), drop line assist (chapter 6)

SCENARIO 5

You are belaying your friend at a popular top-rope site with a lot of other climbers around. He pulls off a large rock that falls and significantly damages the rope 3 feet below your brake hand on the belay strand. Your partner is shaken and wants to be lowered. How will you get him down? *Note:* You can borrow a second climbing rope from a nearby climber if desired.I

SOLUTION

Tie your partner off with a mule-overhand to free your hands. Then isolate the damaged section of rope with a butterfly knot. Ask a nearby climber, Rita, to come over and put your partner on belay after the knot. Untie the mule-overhand and lower your partner until you hit the knot. Make sure that Rita has the belay and then unclip your device from your harness. Rita continues lowering your partner to the ground (your carabiner and belay device can stay on the rope).

If the rope is completely severed, then borrow a second rope from a nearby climber and tie the two ropes together using a double fisherman's or Flemish bend. You will still need to pass the knot.

POTENTIAL PITFALLS

What if you are alone at the base? Free your hands, tie a butterfly or retie the two severed strands together, put a second locker into your harness, and tie a Munter-mule-overhand (MMO) onto that carabiner after the knot. You then can lower your partner and when you reach the knot, ask him to unweight the rope by holding onto a feature on the climb. Take the necessary steps for passing a knot on a top-rope lower.

PREVENTION

Watch where you belay for a top rope. Generally you have options for this type of setup. If you know the route has loose rock, site the belay out of firing range.

SKILLS TO REVIEW

MMO (chapter 2), passing a knot while lowering, and butterfly (chapter 7)

SCENARIO 6

You hear cries for help coming from a ledge far below that you are about to rappel over after a day of cragging. You are able to talk with the person shouting. The climber says that he has been trying to practice an aid-climbing technique that he read about. His last piece pulled out and he smashed his hand and can't get out of the system. You are able to see that he is dangling from the end of a rope that is girth-hitched to a locking carabiner on his harness. He is 50 feet off the ground and 5 feet below his last piece. How will you help him?

SOLUTION

Continue setting up your rappel, but rig your rappel device for a tandem rappel with either two cow's tails or a rescue spider. Rappel to just above the climber. Free your hands by using a third-hand backup and assist him by helping him clip the cow's tail (or rescue spider) to his harness. The injured climber needs to unweight his locking carabiner at this point. Have him pull up on your rope while you undo his attachment, or set up a short sling for him (to pull on or step into) attached to your rope with a Prusik hitch. Once he is separated from his system continue as a tandem rappel to the ground. Deal with his gear separately.

POTENTIAL PITFALLS

Avoid rappelling below the injured climber. That will make the transfer more difficult. Don't worry about his stuff. Just get him safely to the ground. He messed up one system already; don't let him mess up yours too. You are the rescuer, so take charge and make sure he does what you want him to do.

PREVENTION

His aid system was flawed; he used a girth hitch rather than a clove. He should have had Prusik slings along to get himself out of his jam.

SKILLS TO REVIEW

Rappelling on a cow's tail, tandem rappelling, weight transfer, pick-off (chapter 4)

SCENARIO 7

You and your partner have just completed a linkup of two long ice routes. It is now well after dark and you are in the middle of rappelling off the top of the second 500-foot ice route. You are using two ropes to rappel. Your partner raps and shortly you are both down at the next V-thread, optimistic that you will be back at the car in an hour. You carefully pull the rope, watching as one end pulls out of view, making sure that there are no knots, and the rope starts whipping down as expected. But it stops. “No big deal,” you think. “It must have gotten hung up somewhere.” On ice routes this often can be easily fixed by just pulling harder. But the rope does not budge. The temperature is -30°C; you are tired, cold, and really just want to get back to the warmth of the truck. What to do? Rappelling down the next 300 feet of ice would be a real pain with only one rope, plus if you leave a rope you are looking at a round trip of 10+ hours the following day to retrieve it; by then it may well be covered in new ice and impossible to get.

What are your options for getting off the route? After short debate over the efficiency (and expense) of continuing on just one rope versus releading the pitch to retrieve the stuck one, you opt for the latter. Although it is cold and dark, as a team you feel comfortable with the situation. (If it were an emergency you would not hesitate to leave gear.) How will you go about retrieving the stuck rope? How could it have gotten stuck in the first place?

SOLUTION

First, beef up the V-thread so that it is now adequate as a lead-climbing anchor, not just a rappel anchor. Put a waist Prusik on the stuck rope and clip it to your harness as a backup; your partner puts you back on belay with the second rope. You lead back up the route, placing screws regularly. At the top you realize why the rope stuck; there is a perfect overhand knot 2 feet from the end of the rope. You are positive that knot was not there when you started rappelling—you pulled the rope and double-checked. Somehow while being pulled the rope whipped around in the air creating a knot. Although a rare occurrence, this definitely can and does happen. Continue on to the anchor, reset the rope for a rappel, and hurry back down.

POTENTIAL PITFALLS

Considering that it is the end of a long day, make sure you as a leader are up for the lead and that your partner will be warm enough for belaying.

PREVENTION

Knots happen; rappel ropes get stuck; be ready for it.

SKILLS TO REVIEW

Dealing with stuck ropes (chapter 4). Ascending a fixed line (chapter 5)

SCENARIO 8

While cleaning the pitch you just led, your partner falls. Due to the loud roar of the stream below, you are unable to speak with him to determine his condition. Several minutes have passed and there is still no movement on his end of the rope. You decide to escape the belay so you can more accurately assess the scene and determine what sort of assistance he needs. It is a hanging belay and you are belaying off your body. However, because you clipped in to the longest link on your daisy chain so you could reach a comfortable belay stance, you can't reach the anchor—it is just out of arm's reach. How will you escape the belay?

SOLUTION

If you are on a daisy, the anchor can't be that far out of reach. Get hands-free from the belay. Lean into the rock and stretch as far as possible to get a carabiner onto the anchor. If you *really* can't reach it, escape the belay and move it onto your daisy (although this is by *no* means ideal) as close to the anchor as you can put the system. Once you can move up a bit, transfer the weight again off your daisy and on to the MP as soon as possible.

POTENTIAL PITFALLS

Daisy chains are not meant for this type of application. They are for clipping in to a system, but many are only rated for body weight. They are not intended to hold you and your belay. It is surprisingly easy to blow the sewn pockets on several brands of daisy chains with dynamic loading. When you move the belay to the daisy, watch out that your climber is not getting ready to try the route again, potentially generating a fall load right onto the daisy. Check the manufacturer's instructions for the proper application of your daisy.

PREVENTION

Using the climbing rope as an anchor tether has many advantages as illustrated by this scenario. This way you will always have a fixed section of rope available for rescue purposes (assisting or raising your partner), and can easily extend the anchor. If you've chosen to use a tether instead and the climbing rope is not connected to the anchor in any way, make sure to stay within an arm's reach of the anchor or take the steps to extend your anchor ahead of time. We do not recommend using daisy chains for extending anchors.

SKILLS TO REVIEW

Escaping a belay (chapter 3)
Note: Scenarios 9-12 include multiple characters.

SCENARIO 9

Kelly is part of a group of three on a five-pitch climb in

Wyoming. The group is trying to move faster with an advanced technique: The leader leads the pitch on one rope while dragging a second one. At the belay he puts both his partners on belay and they climb together while he belays them at the same time, with a self-blocking belay device like a GiGi (Reverso, B-52, etc.).

Pat leads the third pitch, trailing two ropes, and then puts Kelly and Chris on belay. Kelly climbs first, and then Chris starts out after Kelly about 10 feet above him. The pitch is challenging for both of them. About halfway up Chris is tired and having trouble with the climb. He falls and swings 10 feet off the line of the climb. It is even harder where he is and he can't climb any farther.

Pat forgot to take the GiGi from the last leader when he started leading and so he used his ATC as a belay device instead. He put one climber's rope through one hole and one through the second hole and has been belaying both climbers by pulling in the lines, using his fingers to separate them and pull up slack whenever he feels one of them move. He is on a nice ledge, with the anchor situated down low at the back, so he is sitting, tied in to the anchor with a clove hitch and belaying directly off his harness.

It is windy so communication is hard. The team discussed communicating in the wind (with rope tugs for on and off belay), talked about who and which color rope would climb first, but did not solidify a plan. None of them has used this technique of double seconding before. Kelly and Chris are not able to communicate what the situation is to Pat. Kelly, still able to climb but getting tired, has tried to continue climbing, but Pat is not taking up the rope slack. Pat has locked his ATC to hold Chris, so he is unable to take in Kelly's rope. What can Kelly do? What can Chris and Pat do?

SOLUTIONS

For Kelly: Kelly does not have many options. He is in Pat's hands. He can coach Chris on the moves and encourage him higher, but his independent progress is limited by the locked ATC (of which he is unaware). He can try and communicate with Pat by directing his voice toward the belay and yelling clear simple statements, but only the conditions will tell if that is effective.

If he is on terrain that is easy, he can try climbing up, creating a bit of slack in his rope and then tying in short with a knot clipped to a locking carabiner on his belay loop. If the terrain is too difficult, he can use a friction hitch to ascend the line or use friction hitches as a backup while he climbs. This would get him to the belay to help Pat. The problem with this independent progress is that Pat may not be expecting it and if Kelly falls there will be a big shock load on Pat and his belay.

This is a situation for Pat to deal with. If communication becomes possible Kelly might consider climbing to the nearest piece of protection (if it is not too far) and then evaluate the piece and clip in to it if it is good. At this point, Pat could easily only lower Chris through the device.

For Pat: Though bleak at first look, there are a variety of possible solutions to this one. With time, Kelly will become tired and unable to hang on. He will eventually hang on the rope as well, at which point Pat, desperately needing a solution, will probably decide to just lower his partners. Hopefully Chris will be able to swing over to the last belay anchor. Kelly may need to provide a helpful pull.

Another option for Pat is to quickly tie off Chris (maybe with some leg wraps) and extend the anchor (with the tail of his tie-in as described in Scenerio 8). Then, if there is enough slack in Kelly's line, he can tie a MMO with Kelly's rope onto the extended anchor. The MMO can function as a lock-off on Kelly's position while Pat lowers Chris, or Pat can fully escape both belays, transferring both to the anchor. Pat can make a longer tether for himself to get farther from the anchor (he will probably need a sling to do that and then untie from his tie-in knot). Now Pat may be able to see what is going on down there and maybe communicate better. At this point—with the belay now on the anchor—the two climbers' belays are separated. Each climber is free to move up and Chris can be lowered if need be. They have to be independently belayed at this point.

POTENTIAL PITFALLS

If Pat tries to mess with the ATC to get it to release, he may be able to lower Chris but he will lose his belay on Kelly. Perhaps the biggest risk is if the climbers begin trying to rescue themselves all at the same time, working independently of one another. Communication is imperative!

PREVENTION

This is a good scenario for prevention. Painfully obvious is the fact that this whole situation could have been prevented by taking the GiGi in the first place. Another obvious prevention tip is to be familiar with techniques before using them—Pat should not have just used his ATC. He should have resorted to individually belaying his partners. Even with difficult communication, he would not have had to relay that. He could have just started belaying the climber he was supposed to start with, not taking in slack on the second climber until the first was at the belay with him.

SKILLS TO REVIEW

Escaping the belay (chapter 3), fixed line ascensions (chapter 5)

SCENARIO 10

You and Pat are swapping leads on a multipitch climb in front of another party. You are leading a pitch that is challenging for you. You place good protection, but add runners that are too short. Your rope zigzags back and forth, creating a lot of rope drag. High on the pitch and out of sight of your belayer (Pat), you can’t pull the rope up any more due to the drag. You are runout about 20 feet above your last piece and are not able to downclimb. You yell down to Pat, “I’m stuck, I can’t go up and I can’t go down!” The other party reaches the anchor just as you begin shouting to Pat. How could they help you? How would your options change if Pat had a second rope?

SOLUTIONS

In this case, there is another party climbing up the route. They might be able to climb up the pitch a bit and unclip some of the offending drag pieces. This might allow you to finish the route safely. It would not be good to have the other party do this if it puts Pat or you in danger, if the other party is inexperienced, or if they might fall into your system.

Although undesirable, it might be best to attempt downclimbing. Pat can give a very attentive belay while you carefully reverse your route. If you fall, Pat is ready to catch.

A much more involved option is for Pat to escape the belay. If Pat feels comfortable with the climb's grade (or even with just the initial part of the pitch) and has a second rope, he could rope-solo up the route, either extending the runners on the already placed pieces of gear or replacing the protection in a straighter line. It may be that changes made to just the first section of the pitch will be enough to allow you to continue up or to downclimb to extend some of your pieces. Before you proceed though, Pat needs to descend back to the bottom anchor and put you back on belay.

POTENTIAL PITFALLS

A big leader fall is possible with large forces on top pieces—watch out. The leader should remain in control of the situation and direct the action before the belayer starts running around trying to fix the situation.

PREVENTION

Placing gear and adding runners so that the rope runs smoothly in a line up the route reduces the forces on individual pieces in the event of a fall, as well as avoiding the dreaded rope drag. Rope drag naturally occurs just as a result of the rope running over and around corners of rock, so adding climber-induced rope drag with poor runner lengths in addition is a recipe for challenge. Also, watch those runouts!

SKILLS TO REVIEW

Escaping a belay (chapter 3), rope soloing (chapter 5)

SCENARIO 11

This scenario uses the characters Pat and Chris described in scenario 9.

Pat starts up from the hanging belay at the top of the second pitch on a five-pitch route in Arizona. It is not possible to get in any gear for the first 30 feet of the pitch, but after the first move the climbing is easy. The route goes up about 10 feet then traverses over about 20 feet to the right, where there are large chicken heads (big plates of solid granite) heading up and angling slightly left for the rest of the climb. Since he has no protection so far and is looking at a swinging 40-plus-foot factor 2 fall onto the anchor, Pat places a sling on the nearest chicken head before the climb angles back left. He climbs the rest of the pitch, finding excellent, regular protection, and sets another hanging chicken head belay after climbing a full rope-length. Pat sets up a Munter belay off the anchor and calls "on belay" to his partner, Chris.

Chris takes out the anchor and starts to climb. He underestimates the first move and falls. Unfortunately, because of where the first piece is, he swings violently down and pendulums to the right about 20 feet and is left hanging 30 feet below the first piece of protection. The wall where he is now is blank and overhanging. There is not an anchor in sight below him for more than a rope length. What to do? What if it is windy and they can't see each other so they can't communicate?

SOLUTION

Pat: Pat does not have much rope, since Chris fell right off the anchor, so Pat can't really lower him anywhere. Pat does not have much rope to raise him either; it also would not make sense to just start raising your second if he fell, particularly if you cannot communicate with him. Try to assess the injury first. Because communication is poor, Pat is worried that Chris could be hurt. Pat needs to move to a place where he can communicate with Chris. He ties off the belay and descends the line using an ascension rig in order to communicate. He will then need to Prusik back up and set up a raising system if Chris is unable to ascend on his own.

Chris: If there is no communication, since Chris is hanging in space, the only thing he could really do is take out his waist and foot Prusiks and start climbing the line (a fixed-rope ascent). If Pat did not evaluate the traversing fall, he may not realize that Chris is hanging in space. Hopefully they can communicate.

POTENTIAL PITFALLS

Difficulty in communication is the key here; it's important that Pat realizes that Chris is in trouble. If Pat chooses to get out of the system and descend to communicate he will need to be diligent about maintaining a backup: he will need at least two Prusiks on the line attached to his harneses. A fully extended and weighted line is a tough situation.

PREVENTION

Pat should have assessed the traversing fall hazard for his second. One easy solution would be to move the first piece of gear higher on the route. Pat could have placed his first piece to protect himself, then have moved up and placed another piece or two. He could then have downclimbed to remove his first piece. Moving the first piece higher on the route would reduce the severity of his second's swing. Also, the route above angles back to the left, so if Pat moved his first piece high enough there would be less than 20 feet to swing and his second would not drop lower than the route. This lead technique employs the same sling craft principles as described in scenario 10 (extending runners on a wandering pitch). Backcleaning should be done only with a few good pieces of protection above; leapfrogging only two pieces is not recommended, given the severity of the fall if one piece fails while leap-frogging the other.

It is instructive to think through your own scenarios: what would I do if she fell?



SKILLS TO REVIEW

MMO (chapter 2), ascending a fixed line (chapter 5), raising systems (chapter 6)

SCENARIO 12

This scenario uses the characters Pat and Chris, introduced in scenario 9.

Pat tops out and sits down in an excellent position belay (a hip belay) after an easy final pitch high on an alpine route. Chris starts climbing up. About one-third of the way up, Chris wanders off-route a bit into less climbed, steeper, and looser terrain. The rope above him catches under a rock and it dislodges, taking a nice chunk out of Chris's leg as it flies by. The impact from the rock caused Chris to fully weight the rope and he is bleeding and disoriented.

Pat is giving a hip belay with no anchor; because the route he climbed was easy and on solid rock, and thinking Chris would have no problem, Pat opted for a fast-position hip belay. After Pat yells to communicate with Chris, he realizes that Chris is dazed and might need help stopping the bleeding. Pat does a few leg wraps to free his hands, builds an anchor, and escapes the belay.

They have two ropes, but Chris is dragging the second one. Pat puts two waist Prusiks on the rope to Chris, unties from the anchor, and starts downclimbing, sliding his Prusiks down the line as a backup and removing protection as he goes. About 20 feet above Chris, the rope runs over an edge in the rock. With Chris's weight on the rope, Pat is not able to slide his Prusiks down any more, and the route is overhanging below him. He can talk to Chris, who is starting to panic due to his profusely bleeding leg. What next?

SOLUTION

Chris must find a way to get some weight off the rope. Some coaching by Pat should accomplish this. Just a foot on a good foothold and a hand on a decent handhold should allow enough slack for Pat to move his Prusiks down the line. If Chris still cannot unweight the rope, Pat will need to treat the edge like a knot and pass it. He will have to go into vertical terrain, so hopefully he brought some gear and slings to make a foot loop to comfortably descend. Once he is next to Chris, he can help with the wound and hopefully calm him down. Pat will then need to reascend the line and continue accordingly: either raise Chris or counterbalance and then tandem rappel.

POTENTIAL PITFALLS

Not having a site or gear to build an anchor. The choice to do a position belay should be based on there being a good spot to build an anchor within easy reach, should you need one. If there is not an anchor site in reach, it is not a good place to belay. Pat must also be careful to maintain his position so that he does not jeopardize his hip belay while building an anchor.

Alpine climbing requires good route finding skills

PREVENTION

This is a tough one to prevent. The decisions along the way are appropriate. It is unfortunate that Chris wandered off-route. Pat was able to solve the no-anchor problem quickly and easily because he chose to belay in a spot with a good place to build an anchor.

SKILLS TO REVIEW

Tandem rappel and counterbalance (chapter 4), descending a fixed line (chapter 5), raising systems (chapter 6), passing a knot (chapter 7)

SCENARIO 13

While climbing a 5.7 alpine ridge traverse, bad weather moves in. You and your partner are pushing your leading ability levels and the rapidly falling fresh snow does not help either's climbing confidence. Because several of the slabs you traversed are now wet with snow and the route is notoriously runout, you do not feel comfortable backtracking or continuing. Your partner thinks you should wait the storm out in a small sheltered nook, while you—afraid that with the strong winds and cold temperatures hypothermia might set in—want to try to descend via a system of dihedrals below. After much discussion of the pros and cons of both ideas, you begin descending the dihedral system on anchors you set and then leave as you descend further.

While pulling the ropes after the second rappel, the end of the second rope gets stuck. Reluctant to lead the pitch (it is a very runout slab and the granite is now soaking wet), your partner decides to cut the rope with the small knife he carries on his harness. You and your partner continue rappelling, having to stop and set anchors much more frequently because now you have just one 60-meter rope, your other rope being just 40 meters because you cut it. You must also pass the knot on each rappel. The process is harrowing—swinging across the wall looking for spots that will support enough gear for an anchor. At the fifth rappel station, you see nothing but blank granite below; there is no obvious crack system for building another rappel station. The ground looks approximately 90 to 110 meters away. What next?

Fast and light should not mean unprepared

SOLUTION

Since your ropes will not reach the ground if tied in a double-strand rappel, create a long single-strand rappel by fixing just one end of the line into the anchor, then rappel the long single strand. Approximately forty meters down, you will need to pause to pass the knot connecting the two lines together. The rope just reaches the ground.

Your partner rappels the same line, but considering that the rope is tied into the anchor (and must remain that way so that the rope reaches the ground), the ropes will have to be left behind.

POTENTIAL PITFALLS

If the rope does not reach the ground, you and your partner would plain and simple be up a creek. Using an ascension rig, you would have to ascend the rappel line (passing the knot once again) to return to the anchor.

PREVENTION

Rappelling down an unknown face, unless you carry aid gear (and potentially a hand drill and bolts), is a dicey proposition. Once the lines are pulled, you are stuck on that section of rock; there may be no easy way to ascend back up.

Do your homework and investigate your descent. Look into all options in case you have to bail early. There is no guarantee that a crack system will run the entire length of a wall, and if it does it may very well be a route noted in a guidebook.

Finally, consider getting the rope unstuck before cutting it. Often accidents happen as a result of a number of poor choices rather than one big obvious one.

SKILLS TO REVIEW

Rappelling with a backup (chapter 4), ascending (chapter 5), passing a knot (chapter 7)

SCENARIO 14

In the middle of a runout slab section, you feel your rope go taut. “SLACK!!” you yell to your friends, novice climbers, belaying below. “The rope is stuck!” they call back. Not only is the rope stuck, but you do not want to downclimb the thin, slabby terrain.

Seated in a crack system, your buddies allowed some of the rope coils to drop below into a deep crack right underneath them. A few of the rope sections doubled back on themselves and are now tightly pinched off deep in the slot. They are unable to slide their hands into the tapered crack. The rope will not budge and there is no more slack to feed out despite your uncomfortable stance. What will you do, what can you advise your friends to do, and how could you have avoided this situation?

SOLUTION

Cleaning tools do not have to be used only for artificial protection! Because you can access the rope from a variety of angles, a cleaning tool could be indispensable in this situation. Your friends can work on dislodging the rope with the cleaning tool, trying to pry the rope free.

Either take a deep breath, hold on, and hope your belayer can free the line, or begin downclimbing, preparing for a possible lead fall on the runout slab. Hopefully with the additional slack generated as you downclimb, your friends will be able to free the rope. If they are not able to free the rope, you can either continue downclimbing or stop at a solid piece of protection and clip in while they continue battling the rope.

If this scenario included only you and your belayer, it is important that the belayer knows how to safely get hands-free with a mule-overhand so that he is able to work on freeing the rope. In the worst-case scenario you will need to downclimb until there is enough slack available to lower you down to the anchor and lend a hand.

The munter mule with a carabiner bight clip for backup.



POTENTIAL PITFALLS

Make sure your belayer isn't too distracted by the rope-freeing process and is still providing you with a good belay.

PREVENTION

The best solution to this predicament runs along the lines of, "An ounce of prevention is worth a pound of pain." Rope management is often a difficult, overwhelming task for new climbers, and they do not realize how easily tangles and knots can happen. Do yourself the favor of setting yourself and your partners up for success by keeping belay ropes organized. At a crowded belay station or spots with deep cracks, take the time to make hanging holsters that ropes can feed in and out of, or designate good spots to stack the rope. Educate your climbing partners about the importance of good rope management and active belaying. It helps everyone in the long run.

SKILLS TO REVIEW

Mule overhand (chapter 2), getting hands-free (chapter 3)

SCENARIO 15

You and your partner are one double rope rappel away from getting off your climb. Your partner threads one end of the line through the rap chains. Once she has coiled one of the ropes in her hand, she tosses it down while simultaneously you continue pulling the second rope down from above. Unfortunately, she throws the rope directly into a tree below and the rope snags in its branches. She tugs and tugs, but the rope is caught beyond recovery. Meanwhile, you have run into a snag of your own; the rope you have been pulling on appears to be stuck above, caught on one of the route's many chicken heads. You have tried every trick you can think of for freeing the rope from below (swinging the rope out, flicking it, pulling from a different angle, etc.) to no avail. With both of your ropes stuck, how will you and your partner get down?

SOLUTION

Unfortunately, your partner's efforts at efficiency will end up costing time in the long run. Fix the ropes to the anchor. Have your partner slowly rappel the single strand using a third hand as a backup, taking care *not* to rappel below the tree. As soon as she is right above the tree (or can't rappel any lower without risking dropping below the tree), she can begin untangling the rope and pulling it up. A third-hand backup becomes very important so that she can keep her hands free for working on the rope.

Once the rope is untangled, she rappels all the way to the ground where she then reties in to the rope and reclimbs the pitch while you belay from above (or she ascends the line with an ascension rig).

Back at the anchor, she clips in, unties, and gives her end of the rope to you. You tie in and now, with her belaying, lead the pitch above. When you get to the stuck section of rope, either free it and toss it down to your partner and downlead, or continue up to the anchors, dragging the second rope with you, and rappel, hoping the rope will not snag again when you pull it.

POTENTIAL PITFALLS

If for some reason your partner could not climb the pitch back up to you (rappel routes do not always follow climbable lines), she would have to get out her waist and foot Prusiks and ascend the line she just rappelled.

If for some reason the section where the rope is stuck above is unclimbable, unaidable, and so on, you can still descend. Since you are just one rope length from the ground, you can fix one end of the rope to the anchor and rappel to the ground on that single strand.

PREVENTION

Good rope management (i.e., thinking about the obstacles below before throwing) may have avoided this predicament.

SKILLS TO REVIEW

Third-hand backup (chapter 4), French-freeing, tying an ascension rig and ascending a fixed line (chapter 5)

"Old school" techniques can add a quick safety margin in unexpected terrain

SCENARIO 16

While leading out a long horizontal traverse on a desert tower, your partner falls, penduluming approximately 60 feet across the blank wall. The two of you are three pitches up; he had placed a #4 Camelot at the beginning of the traverse, then 15 feet later clipped an old piton that pulled out from the force of his fall. In his fall he hits a small ledge, shattering both ankles. He is now hanging approximately 10 feet to the right of you (the #4 Camelot holding his weight) and 60 feet below on the relatively blank wall. How can you assist him while taking care to attend to the possibility of a spinal injury incurred from the impact?

You have a spare line with you for the descent, which is several double-rope rappels.

SOLUTIONS

Since the only way out is to return to the base of the tower, set up a counterbalance rappel off of your partner's #4 Camelot. Clip the main rope to the belay anchor as a backup to the high piece. (Try to extend the anchor: you will want the extra slack for swinging toward your partner.) Make sure to put a third-hand backup on your rappel. Begin rappelling with all available gear (other than the pieces in the anchor and the #4). After rappelling about 20 feet, pendulum over to your partner's line and clip a bight of the second rope to his line. Return to your descent path, holding the rest of the spare rope. Then continue descending about 60 feet, until you are just across from your partner, about 15 feet away.

Build an anchor and pull your partner over with the spare line that is clipped to his line. Make a rescue spider and transfer onto the new anchor with a releasable hitch (MMO). You want him to be on a releasable hitch since you will have to get him back off the anchor to continue rappelling. Due to his broken ankles he is unable to stand (or climb) and unweight the anchor.

Now attend to his injuries, improvising a chest harness and using a shirt and some gear to provide splint support for his ankles. Pull the ropes and set up a double-rope tandem rappel. Set another anchor and repeat the process until you reach the ground. Each time you must transfer your partner onto the anchor with a releasable hitch. Once on the ground you need to take time to provide first aid for your partner, making sure he is stable before going for help with evacuation or attempting it yourself. If you suspect a spinal injury, you should find a backboard.

If your partner is in a life-threatening situation, and a counterbalance rappel is not fresh in your mind, consider escaping the belay and using the second rope to rap to your partner to provide life support and stabilization. Pendulum to find a good anchor and try to transfer your partner to it (this transfer might be hard if the anchor is significantly below or above him). Then ascend back to the anchor and clean up the system, pull his rope, and rappel back down on the original anchor. Continue down by tandem rappelling.

Speedy but thoughtful rope work will get you out of a jam

POTENTIAL PITFALLS

Lots of course! Watch that #4. You are relying on only one piece of gear that has been fallen on and not reinspected. If you have any doubts, you must escape the belay, ascend to the piece, and back it up with any available gear. Unfortunately, your leader has the rack. It might be possible to remove the original anchor on the counterbalance descent.

PREVENTION

More solid pieces in the traverse. You should always protect against a bad pendulum.

SKILLS TO REVIEW

Munter-mule-overhand (chapter 2); counterbalance rappelling, tandem rappelling, and rescue spider (chapter 4); rigging an injured climber (chapter 4); ascending a fixed line (chapter 5)

SCENARIO 17

You are leading the last pitch of a five-pitch sport route. This pitch is tougher than you anticipated and you are spent! You've got three more bolts to go till the anchor but you've already spent a good fifteen minutes trying to advance to the next bolt. This pitch is beyond your partner's leading ability so lowering and offering him a shot at the section is not an option. Rappelling down the entire route is an option but you decide against it since the top of the climb is so close. Unfortunately, because this is a sport route you did not bring any sort of cordelette or rescue loops. How can you ascend up past the final three bolts to the anchor?

SOLUTION

Here's a handy trick for improvised aiding on a sport climb when you are without any tools (e.g. rescue loops, additional cordelette, etc.). Clip your remaining quickdraws together to create a long chain. Clip the last carabiner on one end of the chain around the draw (just the "dogbone" section of material) linked above. Insert your foot and stand up in the loop you've created and reach for the next bolt. Hopefully this will give you enough reach!

POTENTIAL PITFALLS

If you still can't reach, play with the length of the chain of quickdraws. The shorter the chain is the higher you can stand but the more difficult it may be to maintain your balance while transitioning to this position. Use the rock as much as you can to assist. Watch that the carabiner gates aren't pushed open depending on how you orient the chain.

PREVENTION

Considering this is a multipitch, you should have brought some extra cord and rescue loops along, regardless of the fact that it is a sport route.

SKILLS TO REVIEW

This is a variation on French-freeing (chapter 5).

SCENARIO 18

You and your teammates are crossing a glacier in two rope teams of two, with each person carrying a coiled portion of rope, when your partner, who is breaking trail for the group, punches through a snow bridge. You are able to arrest the fall and build an anchor. Upon arrival at the crevasse lip, you realize it is extremely undercut and the climbing rope has sliced several feet deep through the lip, leaving your partner choked up against the lip's underbelly. How will you get your partner out? What can he do to help the situation?

SOLUTION:

Prepare another lip off to the side where the rope cuts into the original lip. Remove as much snow as you can but try not to dislodge the snow above the climber if possible. Bring the second team up to your anchor (make sure it's probed and free of crevasses), and have them untie and attach one end of their rope to the anchor. Drop a bight with a carabiner down to your partner, have him clip in to a 2:1 system and haul him out. Once he is clipped in and moving on the 2:1, he can unclip from the main climbing rope if it is hopelessly stuck in the original lip.

POTENTIAL PITFALLS

A huge snow plug (created by the rope slicing vertically from the fall and then horizontally as the climber moves to the new rope) dropping on the climber would be bad. Speed and good systems will help get him out of there fast. Do not just pull him up into the original lip; you will need to prep another site in this situation.

PREVENTION

Crevasse falls are part of the risk of traveling through glaciated terrain. There are of course several measures that can be taken to improve your chances of safe travel: using a probe, receiving a more formal belay, and/or crawling on all fours over suspicious snow bridges. If you find yourself punching through consistently, it is important to consider if it is really appropriate to be traveling in crevasse country in such conditions. Should you be traveling instead at night, when it is cooler, or wait a day to see if conditions firm up?

SKILLS TO REVIEW

Raising systems (chapter 6)

SCENARIO 19

While leading the third pitch of a five-pitch ice climb, your partner takes a leader fall. She has dislocated her shoulder and is in extreme pain. She is unable to continue climbing. She has climbed 30 feet past the rope's halfway point. You have a second rope stacked beside you at the belay, a hanging belay of one V-thread and one ice screw. How will you safely assist your partner? What safety precautions should you keep in mind?

SOLUTIONS

Lower your partner to the lowest ice screw you can get her to where she can clip in (make sure the ice screw is a good one!). Escape the belay, moving the belay to the anchor. Because she has climbed approximately 30 feet beyond the halfway point, you should only need about 30 more feet of rope to get her to the anchor. If there is no low protection, you can tie on the other rope and pass the knot to lower her all the way to you at the anchor. Continue descending via rappels (tandem if necessary).

If there is a bit of low protection, you may need to rope-solo on the other rope to clean the bottom pieces and *then* pass the knot so that you will have enough space to lower her to your station before the knot hits the pro. Build a new anchor for this step if you have the materials.

The third option is to escape the belay and use the second rope to rope-solo up to her and start building your descent anchors there. Ice is nice in that you can generally build your anchors where you need them (obviously, depending on ice quality). You can then transfer onto a new anchor and clean the first one as you rappel by on the way down.

POTENTIAL PITFALLS

If your partner does not have a good quality screw to clip in to, then just escape the belay and keep her on your anchor and the screw she is hanging on already.

Do not start rope-soloing or ascending on her line; you have another rope available, so use it! With weight, ice anchors pressure-melt—not something to worry about in this scenario, but be careful leaving a patient hanging or attached to an ice anchor. Ice anchors will melt out over time, especially with a bit of weight.

Due to pressure-melt, rope soloing is preferable to ascending the fallen leader's line. Ascending her line would put more weight on the piece she is hanging from, thereby increasing the rate at which pressure-melting occurs.

PREVENTION

Careful on those ice leads! This scenario illustrates an advantage of climbing with two ropes (including double or twins).

SKILLS TO REVIEW

Escaping a belay (chapter 3), rope-soloing (chapter 5), passing a knot (chapter 7)

SCENARIO 20

You are cleaning a route led by your partner and arrive at a spot where the rope has doubled over on itself and is hopelessly stuck in the crack. You were climbing the route quickly, thereby generating pools of slack, and your belayer was having a hard time keeping up with you. You decide that the rope must have gotten stuck in one such instance. You work on the rope for a while without success. Given that your belayer can't pull in any more slack and is therefore unable to belay you, how can you safely continue up the line? First assume that you can communicate with your partner. What would you do differently if you could not communicate with your partner?

SOLUTION

Call up for your partner to escape the belay and fix the line. Meanwhile, you can pull out your rescue loops and a cordelette and fashion an ascension rig. Tie your ascension rig to the line with Prusik hitches. You will have to untie from the climbing rope once you are clipped in to your Prusiks. Because the rope is stuck, you will not have the option of clipping in short with an overhand or figure eight on a bight as a backup. Once you have confirmed that the line is fixed, begin ascending all the way to the anchor.

If you can't communicate with your partner, do the same thing.

It is up to you and your partner to decide what to do next. Perhaps she descends back down the line to give freeing the rope a shot. It is certainly worth giving it another try before cutting the line, which may be your next option. If you are short on materials for creating an ascension rig, don't forget about the Garda hitch!

POTENTIAL PITFALLS

If you have no means of creating an ascension rig, you might consider tying in above the stuck rope and then cutting the rope below your tie in as a last resort. This is not recommended if you will need the rope for your descent. If you have not been able to communicate with your belayer, be aware that the added force of your ascending may take her by surprise.

PREVENTION

It is important for a variety of reasons not to generate much slack as a follower: the potential of shock loading the anchor should you take a big fall, the chance of ropes getting stuck as in this scenario, and so on. As a follower it is your responsibility to keep appropriate rope tension and communicate with your belayer.

SKILLS TO REVIEW

Tying a Purcell Prusik (chapter 4), ascension rig, ascending a fixed line and backing up a fixed line, and ascending with a Garda hitch (chapter 5)

SCENARIO 21

While leading a pitch, your partner falls and does not want to continue. She calls down to be lowered. She has only used about a third of the rope, so rope length will not be a problem. However, the anchor from which you are belaying is located off to the side of the climb and under a large roof. How will you get your partner back to the belay anchor once she is lowered past the roof? What different steps would you take if she were knocked unconscious and unable to help?

SOLUTIONS

For the conscious patient, your partner could clip a quickdraw to the rope (or simply pull hand-over-hand) which would keep her close to the wall as she lowers. She would have to clip around or through each piece of gear she passed. Another option: lower her down to where you can talk and see each other. Get hands-free from the belay. Get a bight of rope or long cord (made into a sling) and throw it to her. Alternately, she can throw you something (like a chain of runners girth-hitched together) to clip to the anchor. Attach the rope bight or sling to both the anchor and your partner. Continue lowering her and have her pull herself to the anchor. If she is unable to pull in, just lower her until she swings in due to the tether attaching her to the anchor, and then bring her up to the anchor.

If your partner is unconscious or none of the above options works, you will need to get a sling on her somehow. There are a couple of options, but first get hands-free. Option one: Take a carabiner and tape open the gate. Add some webbing and see if you can lasso the lass. Option two: Escape the belay. Rope-solo or ascend out to where you can attach a tether to her or her rope. You may have to go up a ways if she is really hanging in space. This is assuming you want to get her back to your anchor. If she is unconscious you may need to ascend to her and administer care. Your subsequent steps will be very situation-dependent. Choose the option that will get you to your unconscious partner most quickly.

POTENTIAL PITFALLS

Take care not to hurt your partner with the carabiner toss method. If your partner is conscious, try to use a rope section or cord to tether her to the anchor; webbing has less give. If she becomes unable to pull in on the webbing, she will have quite a bit of force as she swings back out against it. You could generate a very large outward shock load on your anchor this way.

PREVENTION

Be careful where you put the belay anchor. If it is possible to put it lower and not wedge yourself up under a roof, that is generally better.

SKILLS TO REVIEW

Escaping a belay (chapter 3), rope soloing (chapter 5)

SCENARIO 22

You are belaying at the top of a two-pitch trad-route tower. Your inexperienced partner is out of sight about two-thirds of the way up the pitch. He allows his rope to get caught on a rock nubbin as he climbs up and sideways, generating about 6 feet of slack.

At this point he falls and swings into a small dihedral and smacks his head. You feel the sudden large fall and can get no response from him. You have only one rope because the tower has two single-rope raps to get off the other side. What will you do?

SOLUTION

Begin a counterbalance rappel. Take all the gear except the anchor with you. Descend to your partner and set a new anchor. Transfer him to the anchor with a releasable hitch and attend to life support. Set a single-rope rappel and continue tandem rappelling until reaching the ground.

POTENTIAL PITFALLS

Depending on how you as the belayer are situated at the top anchor, it could be tough to quickly switch into a counterbalance rappel; this will be situation-dependent.

PREVENTION

When following, be careful when you choose to climb above your belay line.

SKILLS TO REVIEW

Counterbalance rappelling and tandem rappelling (chapter 4)

SCENARIO 23

You are traveling in the middle on a rope team of three through heavily crevassed terrain. Snow conditions are not good; you and your teammates have been popping through snow bridges all day. Suddenly, Adam, located at the front of the line, takes a long fall, deep into a crevasse. You need to establish communication with Adam but there is another obvious snow bridge between you and the point where he fell in—the same snow bridge that Adam's foot popped through only minutes ago.

A few questions to think about: Considering the precarious nature of the terrain between you and Adam, is it still necessary to approach the lip of the crevasse? If so, how will you safely do so? How will you proceed from there?

SOLUTION

Unless you are able to establish verbal communication with Adam by shouting, it is necessary to approach the crevasse to assess the extent of his fall and the nature of his injuries (if any). Considering the lousy snowpack, it is likely that Adam's rope has cut (potentially quite deeply) through the crevasse's lip and you will need to prep the lip for him.

The first thing for you to do is to establish an anchor near the middle person, as that person continues holding Adam. Then belay yourself off the anchor toward Adam. Make yourself as light as possible as you approach Adam, ditching your backpack, etc. Crawl on all fours to distribute your weight as much as possible. Have your ascension rig already set on the line, sliding it alongside you as you move out, as a belay. Probe the snow bridge before getting onto it; consider trying an alternative route if the line Adam took does not look so good.

Once you reach the lip of the crevasse, assess Adam's condition and make a plan. Can he ascend on his own, or does he need assistance? If he needs assistance, then your third will need to come forward so you can use her portion of the rope for creating a raising system. Decide if you need to pad the lip, to what extent, or if Adam needs an entirely new line sent down and if that is possible or not.

POTENTIAL PITFALLS

The biggest risk is more snow bridges giving out as you approach Adam.

PREVENTION

Crevasse falls are part of the risk of traveling through glaciated terrain. There are of course several measures that can be taken to improve your chances of safe travel: using a probe, receiving a more formal belay and/or crawling on all fours over suspicious snow bridges. and so on. If you find yourself punching through consistently, it is important to consider if it is really appropriate to be traveling in crevasse country in such conditions. Should you be traveling instead at night, when it is cooler, or wait a day to see if conditions firm up?

Nothing like a little crevasse rescue and fixed line ascension practice to keep your skills fresh.

SKILLS TO REVIEW

Ascending a fixed line (chapter 5), raising systems (chapter 6)

SCENARIO 24

You are belaying your partner on the first pitch of a multipitch sport route when she takes a lead fall just 10 feet from the top anchor. Both of her ankles have been injured in the fall, and she is unable to continue climbing. All you have left on the ground is about 20 feet of rope—not enough to lower your partner back to the ground. Because this is a route with a walk-off descent, there was no need for a second rope for rappelling. You did not build a ground anchor beforehand and there is nothing in the immediate vicinity. All you have is one cordelette and a locking carabiner. How will you help your partner? (She does not have any rescue knowledge.)

SOLUTIONS

If the upper piece is a good bolt, consider lowering your partner with whatever amount of rope you have left. You can then start climbing (or ascending) up. She will start to lower. As you go up, remove the quickdraws. When you pass her—if you are close enough—attach a rescue loop to her line and clip it to your harness. This will be a safety backup for you when she gets to the ground. Ideally, when she reaches the ground there will still be two or three draws between you.

Once she is on the ground, you have a few options. You can clip in to the nearest bolt, attach the rope, and rappel the line back to your partner, leaving the line fixed. Or you can have your partner untie. (Careful! Make sure you are clipped to a bolt or have a Prusik connecting you to her line as previously described; otherwise, you'll be dropped. Even the ropes out through the last draw and rappel the line. Near the end of the rappel, clip a draw in to each of two bolts (you'll have to reach up high to a bolt above to do this), and clip one side of the rope through both draws. Clip yourself to one of the bolts and pull the rope so that it stays through two draws (this can be done off one bolt, but it is good to realize that you can do it off a couple bolts as described here); do another single-rope rappel, hopefully to the ground. Repeat if you need to. You now have your hurt leader on the ground and your rope for carrying her if necessary.

You have another option at the moment when you pass your partner as you are climbing up. Switch to a tandem rappel, but make sure that both of your body weights are not just hanging and rapping off of one bolt.

Alternatively, you could lower her to the nearest bolt, have her clip in and fix the line to the bolt. You would then ascend up to her. However, this process will take longer than the one described above so it's not the best option if getting her down to the ground as quickly as possible is critical.

POTENTIAL PITFALLS

Back up single bolts whenever and however possible. In many cases single bolts should not be trusted. Be careful as you go up the route to maintain your status as rescuer. You do not want to turn into a victim or get stuck at the top of the climb where you are no longer able to help your partner.

PREVENTION

Consider the consequences if you forego building a ground anchor even at a sport crag.

SKILLS TO REVIEW

Rappelling, counterbalance rappelling, and tandem rappelling (chapter 4)

SCENARIO 25

While cleaning the last pitch of an eight-pitch route, your partner is struck by a rock and is seriously injured, floating in and out of consciousness. For a variety of reasons it makes more sense for you to evacuate him via the top of the route instead of rappelling all the way back down; there is an access road leading to the top of the cliff, with a large cleared parking area (if a helicopter landing is needed). You are also looking at rappelling eight full rope lengths versus hauling him 30 feet up. Your partner is trailing the second rope. How will you get your partner to safety?

SOLUTION

Your partner's injuries must first be assessed. If he is only 30 feet away, you may be able to do an effective job of assessment from where you are. But if you can't see him, you will have to get down to him to administer first aid. The easiest way to do this is to fix the brake strand to the anchor and rappel down to him on the single fixed line; then ascend back up once you have assessed and treated him.

Assuming he does not need any support slings (provide them if necessary), it is time to start raising. Build your raising system. If your partner is conscious enough, a 2:1 drop loop assist may be a viable option. If he is not conscious enough to clip in to the carabiner, you will need to build at least a 3:1.

POTENTIAL PITFALLS

Considering that your partner is trailing the second rope, take great care if you notice any increase in resistance in your system. An increase in resistance could indicate that something is snagged. If that occurs you will have to descend to your partner and attempt to free the rope. Ideally, you will take the second rope from him when you descend to administer care.

PREVENTION

Rockfall is one of the risks inherent to rock climbing.

SKILLS TO REVIEW

Escaping a belay (chapter 3), rappelling, rigging an injured climber (chapter 4), 2:1 and 3:1 raising systems (chapter 6)

SCENARIO 26

While exiting out a large roof on lead, your partner falls and takes a long whipper into space. She is uninjured and raring to go. But she is hanging in midair. How can you work together to get her back up into the crack? Because she was a bit run out when she fell, she is unable to reach up to the rock or to any of her pieces. She has traveled past the rope's halfway point, so lowering her down is not an option.

SOLUTION

There are multiple options, ranging from the easy to the more complex. Easiest is the “bounce technique.” She grabs the rope above her and pulls up hand-over-hand. At the same time you lock off your belay device and put all your weight on the rope. She lets go and you drop a couple feet while she remains slightly higher than she was. Repeat. She could also ascend up the line back to the roof using either an improvised ascension rig or a foot loop and Garda hitch. Finally, as the belayer you could build a 3:1 raising system off your harness and haul her back up the remaining feet to the roof.

POTENTIAL PITFALLS

Make sure your gear is strong and secure. The first technique can put a lot of force on pieces. The solutions range from the most work-intensive for the climber and least time-consuming to the most work-intensive for the belayer and most time-consuming.

PREVENTION

That's the way roofs go. Hopefully she will work on getting bomber gear placements with better spacing (less runout) and not rule out the possibility of using some points of aid through the roof if need be.

SKILLS TO REVIEW

Ascending a fixed line (chapter 5) and raising systems (chapter 6)

SCENARIO 27

You and your partner are climbing at an infrequently visited choss pile. The rock is loose, the cracks are flared and dirty, but you love a good adventure. You are at the top of the route's final pitch when your partner (who is cleaning the route) pulls off a rock that smashes right down on her hand and knee. She can't continue climbing and asks for a raise. She is just 40 feet from the top; you have plenty of rope at your disposal. But you are nervous about your anchor; the rock quality is not good and you have both been choosing to belay off your body for the entire climb to lessen forces on the anchor pieces. You are concerned about the ability of your current anchor to hold the additional forces that a raising system will generate. What are your options for raising your partner and what can you do to make the situation as safe as possible?

SOLUTION

Do your best to reinforce your anchor. Add as many additional pieces to the anchor as you think necessary. You could also try introducing more material into the system to favor your strongest and most secure pieces.

If you are still hesitant to set up a full raising system on your anchor, even with reinforcement, you do have a few options, but you must have a good belay position to execute them. See if you can talk your partner into ascending up the line with an improvised ascension rig using her uninjured limbs. If she agrees to ascend, tie off the belay with a mule-overhand and brace yourself. If she does not want to ascend, then you can build a quick 3:1 right off your harness. Again, make sure you have a good stance and are secured on your anchor if you attempt this option.

POTENTIAL PITFALLS

If there is a large weight differential between you and your partner, then holding her weight while she ascends or hauling her off your harness will be *very* difficult and somewhat painful.

PREVENTION

If the rock is that dangerous, do you really want to be climbing there in the first place? If the answer is still yes, try to stick to routes with good anchors.

SKILLS TO REVIEW

Mule-overhand (chapter 2), anchor-building techniques (chapter 4), ascending a fixed line (chapter 5), raising systems (chapter 6)

SCENARIO 28

While leading an upward traversing pitch your partner takes a hard fall and dislocates her shoulder. The rock quality has been very poor all along and the climbing more difficult than expected. There is not enough rope available to lower her and there is no way to reach over to her either; she is approximately 160 feet out, 50 feet over and hanging 5 feet below her last piece; a blue TCU. She is in great pain and is asking for assistance. The descent is three single-rope rappels. What is your plan of action?

SOLUTION

As described in "Ascending to a Hurt Leader" you will need to reinforce the bottom anchor as best you can, escape the belay, and begin ascending the rope. Keep your fingers crossed that the blue TCU holds. Selectively clean some gear as you go to use in reinforcing the top anchor. Do your best to build an anchor where your partner is hanging. Transfer your partner to the new anchor and clean the upper TCU if you can. Fix the climbing rope to the new anchor. Next descend back down to your original belay anchor, free the rope, and dismantle the anchor. Time then to re-ascend to your partner, cleaning the route as you go. Once you arrive back at your partner rig the anchor for a tandem rappel and start heading down.

POTENTIAL PITFALLS

If the small TCU blows you both will go for a little ride. There is always the chance that you will not be able to set an anchor at the site where your partner has fallen. See the next scenario for ways to deal with that predicament.

PREVENTION

Injury is a risk inherent to rock climbing. Contributing factors may have been poor rock quality and/or exceeding abilities.

SKILLS TO REVIEW

Belay escapes (chapter 2), ascending to a hurt leader (chapter 5)

SCENARIO 29

Now, using the circumstances described in Scenario 28, what would you do if your partner has fallen twenty feet below her last piece and is hanging in space next to a section of blank rock where there is no spot to build an anchor? She is still asking for you to help reduce her shoulder pain.

SOLUTION

Create a good anchor at your partner's last (highest) piece of gear. Then descend and attend to your partner's needs. Once she is stable (or as close to it as you can get her), take all the gear from her, hit reverse, and move back up the line to the top anchor. Clip yourself in to the anchor and build a raising system (improvise with slings as the haul strands). Raise your partner to the anchor and attach her with a releasable hitch. Make sure the climbing rope is attached to the top anchor. Either rappel on the single strand or descend back down to your original anchor, clean it, and then ascend back up to your new anchor, cleaning gear as you go. Begin tandem rappels.

Groups are able to handle larger challenges.

There are other possible solutions depending on the actual configuration of the climb and anchoring options.

POTENTIAL PITFALLS

You will need to be fast and creative with your anchoring and ascending systems. Make sure you maintain good pieces securing the rope system. Be careful not to clean too many pieces for use in building the top anchor.

PREVENTION

Same as Scenario 28.

SKILLS TO REVIEW

Belay escapes (chapter 2), ascending to a hurt leader (chapter 5), raising systems (Chapter 6)

Early morning helicopter in the wilderness

CHAPTER 9

Getting Outside Help

Sometimes self-rescue is not an option or is only part of what a situation calls for. This chapter addresses what is involved in calling for outside help. As the party requesting rescue it is important to be realistic in your expectations of what rescuers can do to help you. They will be working under the same limiting factors you are: terrain, weather, and darkness to name a few. All of the rescue situations discussed in this chapter provide basic guidelines and suggestions. Every climbing area (be it a crag or mountain range) has its own unique protocol and resources.

DECISION-MAKING TECHNIQUES AND TIPS

Rescue decisions are important, stressful, and tricky. The best solution is not always obvious and the difficulties surrounding decision-making typically are compounded by the distraction of an emotional situation. To look at decision-making, we will focus on three situations: one rescuer and one responsive patient, one rescuer and one unresponsive patient, and lastly, more than one rescuer and a responsive patient.

The first step in any emergency decision-making process is to breathe; or, in the words of Teton pioneer Paul Petzoldt, "Smoke a butt." Take a moment to clear your head and take full stock of the situation. In only a few circumstances will those extra minutes be detrimental. Taking that time to think can be difficult; all your instincts may be urging you to "Act now!" But poorly concocted plans can often result in time wasted in the long run or in more injuries.

After working through the initial emergency procedures (chapter 2), the first plan of action should be to get your patient up or down the climb to a safe and protected spot accessible to rescuers, as long as that process will not make the patient's condition worse. This should be attempted only if it is reasonable for you as a solo rescuer to move the patient.

With a responsive patient. A solo rescuer can often get good advice and can actually help calm the patient by involving him in some of the planning and decisions. This is not always the case, but it should definitely be considered. By involving the patient in simple, relevant decisions, it is possible to see if he will be able to have a role with bigger-picture issues. For example: if the patient is giving good information while you are repositioning his broken limb and is indicating in what position he is most comfortable, you may want to discuss how you are going to get him out of there. Listening to the patient's input, even if he is quite injured, can be good for both of you. The patient will generally be supportive of your efforts and will better understand the plan if he helps make it. You get a second opinion and sometimes new ideas, given your patient's closeness to the challenge ahead. However, involving your patient in rescue decisions is not always the best idea—for instance, if you know the patient's stress level will rise due to uncertainties or if the patient does not perceive the severity of his injuries or situation.

You may or may not need to leave a responsive patient; following are some considerations should this be necessary.

With an unresponsive patient. The solo rescuer must rely on his or her own judgment and decisions. An unresponsive patient in the backcountry is likely to be severely injured. Good first-aid skills must be used with this patient.

Most likely, you will need to make a decision at some point about leaving an unresponsive patient to get more help. Remember that environmental conditions may change while you are gone: shade becomes sun, sun becomes rain or snow, and so on. Prepare and situate the patient for these possibilities if you can by insulating him with padding below and layers on top. Regardless of the air temperature, the patient's body temperature will cool down. It is also possible that the patient could resume consciousness while you are away. Leave him a message and supplies that will help him: water, basic food, and easily accessible clothing. Do not leave him with gear he does not know how to use, with complex foods, or with prescription drugs he could overdose on or have an allergy to. If the patient is unconscious, it is vital that he be left in the recovery position.

There is no point leaving your patient if you do not have a plan, so know the following before you depart:

WATCH WHAT YOU SAY

Medical professionals say that a person's hearing is the last thing to go. Be aware of this as a rescuer; even if your patient is unresponsive, reassuring and encouraging him can make a difference. Tell him what you are doing and always encourage him. Also, be sensitive in your language and the manner in which you describe your patient's condition.

- The patient's exact location so you can find him again, as well as so you can describe the location to others (mark coordinates on a map or write down a description; in times of high stress it becomes easy to confuse details)
- Where you are going and how long you think you will be gone
- What condition the patient is in when you leave relative to when you started care
- What help you need from the other rescuers (horse,

helicopter, oxygen, etc.)

When there is more than one rescuer. Communication becomes paramount. Many hands can make light work, but only if there is a brain controlling them well. It is best to have one lead rescuer in this situation. If possible, the lead rescuer should not be the primary caregiver. It is hard to both keep tabs on the big picture and provide direct patient care. If you have the resources, it is best to put a knowledgeable first-aider in charge of the patient and have another leader direct the rescue. You may be in a situation that the best person for both tasks is the same individual. In this case, focus on stabilizing the patient, and then train someone else to step in and take on patient care while the person most qualified for both roles steps out to be the lead rescuer.

The lead rescuer should keep the other rescuers occupied and productive. Some jobs may seem unnecessary, but in a rescue situation people like to feel like they are helping out; keeping people busy also can help keep their minds off the severity of the situation and focused on the task at hand. If there are excess hands, put them to work. Have people gather firewood, set up tents, make hot water, build anchors, coil ropes, scout the route down, and so on. Keep people busy but, as lead rescuer, try not to add too much unnecessary supervision to your list of tasks; keep your priorities in focus.

The “after” of a rescue is an aspect often overlooked. Everyone’s combination of climbing and life experience varies greatly. Rescues affect everyone differently, whether the circumstances were traumatic or trite. It is important to discuss the rescue as a group after it is complete and seek professional help if necessary.

POST-TRAUMATIC STRESS DISORDER

> According to the National Mental Health Organization and the National Institute for Mental Health, the following symptoms experienced more than a month after a particular event are indicative of post-traumatic stress disorder (PTSD): reexperiencing the incident in the form of flashbacks, nightmares, or frightening thoughts, especially when exposed to similar circumstances or surroundings. Anniversaries of the event can also trigger these responses. People experiencing post-traumatic stress disorder may also have emotional trouble, sleep disturbances, depression, irritability, anger, anxiety, or guilt. See appendix D, Continuing Education, and appendix E, Recommended Reading, for resources for identifying and coping with PTSD.

CARRYING DEVICES AND LITTERS

So you have gotten yourself safely off the wall, out of the crevasse, or down the frozen waterfall, now what? Below are several improvised carrying devices to help get you the rest of the way out. Ideally, the injured party can walk out on his own. If that is not possible, the severity of his injuries will determine how much assistance he needs. We have described the carrying methods we find to be the most practical; other methods do, of course, exist.

Keep in mind that the following information excludes any assessment for spinal injuries. If spinal injury is suspected, it may make more sense to go for help rather than trying to evacuate the patient yourself, risking further injury: spinal injury is not something to mess around with, especially if you lack specific wilderness medical training. See the Continuing Education and Recommended Reading appendixes for more information on wilderness first aid.

Realize that carrying a patient will be a difficult and physically demanding process no matter how you slice it, especially if the patient is significantly larger than you. Although

we advocate self-sufficiency and resourcefulness, trying to carry another person can be an easy way to end up with two injured people instead of just one. In
this situation it may make more sense to get additional help, either from bystanders or trained personnel.

ONE- AND TWO-PERSON CARRIES

Here are a few options for carrying a person out by yourself or with a partner. Do what you can to pad yourself and your patient from materials cutting into skin, particularly if this is going to be a long evacuation. The different ways of carrying presented use different materials, thereby allowing you to improvise appropriately based on the resources you have.

One-Person Split-Rope Carry

1. Coil the entire climbing rope into a mountaineer's coil sized normally for wearing slung across your torso. Tie it off as normal.
2. Halve the coils into two equal sections.
3. Have your patient step into the loops, one foot into each section. Have her pull the coils up (like putting on a pair of pants) until the coils rest right below her crotch. The wraps of

the mountaineer's coil should be resting on her lower back.
4. Now insert your arms into the upper section of the coil's loops (one arm through each side), like you are putting on a backpack, your back to your patient's belly (fig. 9-1). If possible, have your patient situate herself on an elevated surface like a boulder or a fallen tree. This will make the lifting process significantly easier for you.

Useful Variations

You may find it more comfortable to attach some sort of chest strap across the mountaineer's coil. Here is one way to do it:

1. Girth-hitch a runner around one side of the coil.
2. Bring it across your chest, around the other coil, and back to the side you started from.
3. Tie the runner off using a simple and easily releasable knot, like a double half hitch.

If your partner's mental status is unreliable, you may want to secure her upper body to you. The coil carry described above relies on the patient's ability to hold on to keep from tilting backward.

1. Loop a long runner over your patient's back, snugging it up under her armpits.

2. Tie the runner off in front, over your chest.

One-Person Backpack Carry

Some full-size backpacks have zippers running the pack's entire length on each side. These zippers can be used for more than just packing; they serve a useful rescue purpose too.

1. Stuff the bottom one-quarter of the backpack with soft padding like extra jackets and down. (Nothing too heavy—remember you are carrying all of this.)
2. Unzip both side zippers all the way down.
3. Have the patient step into the backpack, inserting his legs through the openings created by the unzipped zippers. (Most people prefer riding piggyback style versus back to back.)
4. The patient pulls the backpack up to crotch level.
5. Taking great care to not injure your back, put the backpack on your back and stand up. (Again, try to situate the patient on something at your torso height to make picking up the load easier.)

Fig. 9-1. One-person split-rope carry. The patient puts her legs through the loops of the split mountaineer's coil. The rescuer then inserts his arms through the coil's loops as if he were

putting on a backpack.



Two-Person Split-Rope Carry

1. Split your rope in a mountaineer's coil but make the coils approximately 3 feet in diameter.
2. Each rescuer slings one side of the divided coil across her torso, just like a gear sling.
3. The patient sits on the wrapped portion, supporting himself with his arms around his rescuers' shoulders. His rescuers cross their inside arms to provide additional support for his back.

Two-Person Pole Carry

Each rescuer will need two double-length runners.

1. Each rescuer puts a runner on in gear-sling fashion, running from one shoulder to the far hip.
2. Each rescuer repeats step 1 on the opposite shoulder. The two runners should form an X across each rescuer's body.
3. Find a long branch approximately 6 to 8 feet in length. (Extended telescopic ski poles doubled up, or stick clips duct-taped or lashed together with multiple clove hitches may work too.)
4. Insert the branch through the bottom of all four runners,

creating a railing for the patient between you and the other rescuer.

5. The patient sits on the rail (she'll certainly appreciate padding), her arms around the shoulders of each rescuer while the two rescuers link arms behind her to provide additional stability.

IMPROVISED STRETCHERS

If your patient is severely injured you may need to evacuate him on a stretcher. Obviously, a manufactured backboard is ideal, however here are some improvisational options. First described are stretchers that could be carried by just two people (depending, of course, on weight and size of the patient and rescuers). Described last are stretchers that depend upon the power of more than just two rescuers.

Jacket Stretcher

You will need two long poles (branches, skis, etc.), approximately 3 feet longer than the height of your patient, and at least three to four upper-body layers. The tougher the fabric (i.e., less stretchy) the better.

1. Slide the poles down inside the torso of the layers.
2. Evenly space the layers down the length of the poles. The more layers you can spare, the better; the fewer the layers, the more your patient's weight will droop and sag in the stretcher.
3. Aim for about 1.5 feet of excess pole on either end of the stretcher to give yourself enough room to carry.
4. Consider adding stabilizers (improvise with tree branches, telescopic poles, backpack stays, etc.) at either end of the stretcher to help maintain the stretcher's integrity as you carry your patient. (See fig. 9-2)
5. One rescuer carries the litter at each end. Be careful of the terrain you try to cross; if you drop your patient there is nothing protecting his back.

Rope-Bed Stretcher

Again, you will need two poles (as described for the jacket stretcher, above), but this time you will form the stretcher's surface out of climbing rope.

1. Lay the two poles on the ground parallel to each other, no wider than the width of your patient's body. (If the stretcher is too wide your patient will sag and swing, making the stretcher

more difficult for you to carry and much more uncomfortable for her.)

2. Tie one end of the rope off to one end of one of the poles.
3. Bring the rope over to the parallel pole and tie it off with a clove hitch, making sure to keep appropriate stretcher width in mind.
4. Cross back over to the other side and tie the rope off with a clove hitch.
5. Repeat steps 3 and 4 several times. Eventually you will have to slide your series of clove hitches along the pole to make room for more hitches.
6. Continue until you have created a diagonal matt of rope running the length of the stretcher, leaving 1.5 feet of room at each end for carrying. (See fig. 9-2.)

The more rungs of rope you provide your patient, the more comfortable and stable her ride will be. As a minimum guideline, rope rungs should be no more than 6 inches apart.

If possible, pad the stretcher bed with clothing or empty backpacks. This will make it a much more comfortable ride. (There is, however, a critical balance between your patient's comfort and the amount of weight you as a rescuer are carrying.) As with the jacket stretcher, consider adding stabilizers to either end of the stretcher to help it maintain its shape.

With either the jacket stretcher or the rope-bed stretcher, if your materials are sturdy enough, you *may* be able to drag the setup behind you. Make sure to create some sort of foot bar with webbing for your patient so that she does not slide right out of the stretcher as you pull it along. Depending on the terrain, consider securing her into the rig (not too tight)—again, to keep her from falling out.

Opposite: Fig. 9-2.
Top: Jacket stretcher;
Middle: Rope-bed stretcher;
Bottom: Sheet stretcher.


CUT THE SHOULDERS if necessary
CROSS-BARS RECOMMENDED
CLOVE HITCH
CROSS-BARS RECOMMENDED
CLIMBING ROPE
FOLDED BLANKET

Sheet Stretcher

Once again you will need two poles (as described for the jacket stretcher, above). You will also need some sort of large sheet, like an unfurled large rope bag, a large tarp, a tent body, or tent fly.

1. Measure off three equal sections of the sheet right next to one another. The sections should be equal to the patient's body width and height. Any excess can be doubled up.
2. Lay the two poles on either side of the sheet's middle section, lengthwise.
3. One at a time, fold the two outside sections up over the top of the poles, one on top of the other. (See fig. 9-2.)

The patient's body weight will keep the sections from slipping out. But be careful, as the sections will begin to slip with time and jostling.

Climbing-Rope Stretcher

Unless the rescuers are significantly larger than the patient, this type of stretcher demands multiple carriers. You will need one climbing rope.

1. Find the rope's midpoint.

2. Starting at the midpoint, lay sixteen bights of rope out side by side in a continuous S pattern. The bights should be equal in length to your patient's body. Sixteen bights are a guideline; as with the rope-bed stretcher, the more rope rungs the better it supports your patient.

3. From the resulting stack of excess rope at either end of the row of bights, lay a length of rope on both sides parallel to the row of bights.

4. Insert the apex of the bight through the skeleton of a clove hitch (tied in the length of rope described as running parallel to the bights in step 3) and tighten (fig. 9-3). Aim for the resulting bight to be approximately 3 inches, uniform in size as you proceed down the line.

5. Work your way down the entire side, tying clove hitches and inserting the apex of every bight. (Hint: As you tighten each clove hitch down, try to minimize the amount of slack you create on the side of bights you have already tied; Try to bring slack down to the side you still have yet to tie clove hitches in. This will keep the stretcher tighter.)

6. Repeat on the other side.

7. Now thread the excess rope (that ran the length of the rows of bights) through the bights coming out of each clove hitch. Fig. 9-4 shows a rope stretcher completed to this point.

8. Continue threading around and around with each side of the rope.

9. When you come to the foot and head of the stretcher, wrap the rope around itself to keep the strands together. This will also make the stretcher easier to carry.
10. Repeat the threading process at least five or six times, or until you have used the entire rope.
11. Tie both sides off using any applicable knot.

Fig. 9-3. Climbing rope stretcher: Step 4. The apex of the bight is inserted into clove hitch.



As with the rope-bed stretcher, consider lining the stretcher bed. You must work backwards in deconstructing this stretcher; otherwise you'll end up with an absolute mess of rope.

Carabiner Alternative

Threading the rope through each bight multiple times is time-consuming, both in building and breaking down. You must deconstruct the stretcher just as you constructed it—otherwise you will end up with a massive tangle on your hands. This alternative requires multiple carabiners; although heavier because of the added metal, it is faster to make and much easier to undo.

1. Lay out the rope just as described above and lay a carabiner at the apex of each bight.
2. Like before, tie a clove hitch in the strand of rope running the length of the row of bights. Clip the carabiner into the clove hitch.
3. Insert the apex of the bight into the carabiner.
4. Repeat on every bight.
5. Now, instead of threading the rope multiple times through each bight (as described above), to reinforce the stretcher sides, just clip the rope into each carabiner as you thread

your way around the stretcher multiple times.

6. Again, at the stretcher's head and foot, wrap the rope around itself to keep the strands together.
7. Repeat the threading process until you have used the entire rope.
8. Tie both sides off using any applicable knot.

Fig. 9-4. Completed climbing rope stretcher. The rope has been threaded through each bight and wrapped around itself at the stretcher's head and foot.



This method does, of course, have a few drawbacks: it is gear intensive and therefore heavier. But if you have the people power and resources, it is definitely worth considering.

Sleds

You are in luck if you are traveling with a sled: you already have an improvised litter at your disposal. Although most sleds (whether specifically for mountaineering purposes or a kid's sled) are not the entire body length of a supine adult, they are still effective.

Insulate your patient as best you can, situate her on the sled, and if necessary (depending on the severity of the injuries), secure her onto the sled. You do not want your patient to fall off of the sled while you are transporting her; at the same time, should you lose control you do not want her to get stuck on the sled either.

EVACUATING SOMEONE DOWN A SNOW SLOPE

If you are descending with an improvised litter down snowy terrain, it is extremely important to insulate your patient as best you can. Lying inactive on the snow is a recipe for a quick case of hypothermia.

Place as much insulation as possible under and around the patient.

With enough people power, you can ideally have one to two people controlling the litter from above and another person controlling the litter from below. Regardless of how many rescuers are involved, in sloping terrain the priority lies in controlling the litter from above.

HELICOPTERS AND AIRPLANES

It may be that signaling an aircraft (either from the ground or via a radio, satellite, or cell phone) is your best bet for help or that whoever you contact will in turn summon an aircraft. Presented below are some thoughts on effective signaling and useful aircraft etiquette, which will help the pilot get the job done.

Bringing a helicopter or airplane onto the scene is not a decision to be taken lightly. Flying in a mountain environment can be dangerous for pilots and passengers alike, not to mention the large amount of resources used in conducting this type of rescue.

It is perhaps a misconception, perpetuated by Hollywood stuntmen and -women, that a helicopter can just swoop in and pluck a climber off a wall. Although it is possible, it is a maneuver only made under very specific circumstances and by highly trained teams. The vast majority of aircraft-assisted rescues require the injured party to be brought to the top of the cliff (providing that an adequate landing site exists) or to be on level ground out from the base of the climb.

HELP SIGNAL

Ideally, any signal visible from the air will attract the attention of a pilot flying above: “Help!” in big letters, a flashing signal mirror, a signal fire, and so on. But if you want to play it by the book, thereby avoiding the possibility of misinterpretation, here are a few official signals.

“Help,” “SOS,” a V (indicates help needed), or an X (indicates medical help needed) can be scratched out in deep troughs in the dirt with sticks and rocks, stamped or dug out in the snow, spelled out with climbing rope, and so on. Colored drink crystals (including hot chocolate), pudding, and gelatin can all be mixed with water and sprinkled over the snow to help define the letters. Remember the difference in scale from the air; a general guideline is that letters be at least 1 foot in width and 8 to 12 feet tall.

You can also lie down on the ground if the suggestions above fail to attract attention. Frantic waving at aircraft sends an unclear message.

OTHER SIGNALING TOOLS

A whistle, signal fire, or mirror can also be used to draw attention to your party.

If using a signal fire, search for a wide-open clearing to build it in. During the day, use a fire's smoke to draw attention to yourself. Carefully adding wet foliage helps produce billowing white smoke, while rubber items (if this is truly an emergency it might be worth parting with that sticky rubber) generate thick black smoke. At night, three fires situated in a triangle signify a call for help.

Although shouting is effective for drawing attention to one's self, the human voice eventually tires. A whistle is much more effective not only for longevity, but for the high-pitched tone it produces—audible over a much larger distance than the human voice. Three sharp blasts indicate a need for help.

A mirror (or anything reflective for that matter) can be effective at communicating over long distances. It is not a foolproof tactic by any means—particularly if the weather is cloudy—but is nonetheless worth having in your bag of tricks. Again, hopefully any sharp glint will be enough to attract the attention of someone flying above (or off at a distance), but to help avoid being missed, here is the SOS pattern: three short flashes, three long flashes, three short flashes.

Once a pilot locates you she may signal you back with a rocking left to right motion, which means, “Signal understood. I will comply.”

HELPING THOSE WHO WILL HELP YOU

Time is extremely important in mountain rescue; conditions constantly are changing and pilots are often dealing with flying in tight, narrow spaces with not much of a margin for error. As a party anticipating a rescue, there are several ways in which you can help your pilot prior to her landing:

- If applicable have all medical notes about your patient organized and ready to be handed off (these are called “SOAP notes” in wilderness medicine speak).
- Have a small, lightweight travel bag ready for whoever is being evacuated containing a warm layer, a small quantity of food and water, and any medications. The pilot may be limited on the amount of weight she can fly out; it is preferable to be organized and prepared with less rather than more.
- Keep ice axes, ski poles, and other sharp objects separate from your patient’s small travel bag. Often pilots will want to

stow these separately. If you have extra material available, wrap all sharp points of these objects and secure them with tape. Balled-up socks stuffed onto the points work well.

The bottom line is to follow your pilot (or rescuer's) instructions as best you can. That will be the biggest help overall.

SITE PREPARATION

Find a clear landing site as flat as possible (for a helicopter the landing zone can't have more than a 10 percent grade).

Areas must be clear of wires. Often these are not visible from the air.

Ideally the site will allow the aircraft to drop slightly downward on its take-off (this is more relevant to airplanes than helicopters). This translates into a runway or landing pad that slopes slightly downhill.

For a helicopter, create at least a 100-foot-diameter landing pad.

For an airplane, the runway will depend on the plane's size. In Alaska, most bush planes need a 1000-foot by 50-foot landing strip. (If you are on the snow this means packing out a runway either with snowshoes, skis, or walking up and down ad nauseam. It is a tedious task but it could mean the difference between being rescued or not).

If you are creating a landing strip on a relatively unfamiliar glacier, take the time to probe for crevasses.

If being rescued on snow, firmly plant large objects (the brighter the color, the better) in the snow along the runway's right side (looking downglacier). Sticks or wands are not large enough; do not use metal objects. Light changes rapidly on snowy surfaces and any sort of additional depth of field you can provide your pilot in flat light can be of great help to her. It can also be helpful to the pilot to hang some sort of wind-direction indicators (any lightweight material tied up off the ground to a ski, stick, small tree, or pole; make sure it is securely tied).

LANDING AND TAKE-OFF

If you have ground-to-air connection with your pilot, provide her with your best estimates on the following details:

- Air temperature
- Wind speed and direction
- Any obstacles in the landing zone
- Snow conditions if applicable
- Angle of the landing zone

- Type of terrain in the landing zone

As the aircraft approaches (and then takes off), make sure that all loose items are secured. Be aware that even small debris kicked up by the aircraft as it lands can be a hazard to uncovered eyes and faces. Also, any sort of long poles (e.g., wands sticking out of your pack, probes, a radio antenna) can be ripped out of your hands by a helicopter's wind.

RESCUE INSURANCE

Rescue insurance is something definitely worth considering; your wallet will thank you. According to Denali National Park, a short evacuation in a helicopter can cost upward of several thousand dollars, not to mention the additional cost of rescue workers. For example, helping an injured climber with a knee tweaked just above the 17,000-foot camp on Denali ended up costing the park $21,750; ground base rescue crews were deployed from the 14,000-foot camp and the patient was then evacuated by helicopter to base camp. Coinciding bad weather compounded the costs. These figures do not even reflect costs to the military for use of their specialized high-altitude helicopters. The American Alpine Club offers climber's insurance with additional high altitude coverage as part of their yearly membership (see www.americanalpineclub.org).

The powerful downwash created by a helicopter's rotors in landing and taking off can create a severe drop in temperature, a scenario that has resulted in episodes of frostbite in cold conditions. Dress appropriately if you are in such conditions.

If the helicopter is raising or lowering anything by a line, allow the line to touch down to the ground before you touch it; otherwise you may get shocked with static electricity.

If your pilot is making a night landing, do not shine lights directly at the aircraft.

A few important signals to keep in mind as the aircraft approaches:

- Holding your arms straight out horizontally and flapping them up over your head several times signals "Do not land" to the aircraft (not, "Hey, here we are! We need help!").
- Standing with your back into the wind and arms pointing straight into the landing site signals "Backs are to the wind, land where we are pointing."

Some other things to keep in mind: Once the helicopter or airplane lands, do not approach until instructed to do so by the pilot. Imagine a clock drawn around the radius of the helicopter or airplane with twelve o'clock at the nose and six o'clock at the tail. It is proper etiquette to approach from between ten and twelve o'clock. The helicopter's back rotor is almost invisible once it is in motion; therefore, it is good practice to not approach helicopters from the back.

If the aircraft lands on a slope, approach and exit from the downhill side.

If you are not needed at the aircraft, stay at least 100 feet away.

Again, time can be of the essence for pilots. Do your best to be as efficient as possible so the pilot can be quickly on her way. There is more than one story out there of Alaska bush pilots sneaking in a glacier landing during a short weather window only to be stuck out on the glacier for the night (or more!) due to quickly changing conditions.

Appendix A: Accident Statistics

Reviewing trends that have either directly caused or contributed to climbing accidents is a valuable learning tool for increasing risk-management and decision-making skills. These figures are courtesy of the 2005 edition of the American Alpine Club's *Accidents in North American Mountaineering*, edited by Jed Williamson.

	1951-03 USA	1959-03 CANADA	2004 USA	2004 CANADA
Terrain				
Rock	4141	503	96	18
Snow	2289	341	46	5
Ice	231	146	18	12
River	14	3	0	0
Unknown	22	9	0	0
Ascent or Descent				
Ascent	2735	555	118	23
Descent	2152	352	40	10
Unknown	247	10	1	2
Other [N.B.]	6	0	1	0
Immediate Cause				
Fall or slip on rock	2887	273	71	10
Slip on snow or ice	915	198	35	7
Falling rock, ice, or object	585	131	16	4
Exceeding abilities	500	29	25	1
Illness [1]	357	25	5	1
Stranded	310	49	13	3
Avalanche	276	120	2	5
Exposure	257	13	7	0
Rappel Failure/Error[2]	252	44	11	1
Loss of control/glissade	185	16	7	0

	1951-03 USA	1959-03 CANADA	2004 USA	2004 CANADA
Immediate Cause (continued)				
Nut/chock pulled out	183	8	8	1
Failure to follow route	164	29	7	0
Fall into crevasse/moat	152	48	1	2
Piton/ice screw pulled out	87	12	7	0
Faulty use of crampons	87	5	5	0
Lightning	45	7	1	0
Skiing[3]	50	10	1	1
Ascending too fast	61	0	3	0
Equipment failure	13	3	1	0
Other[4]	358	34	27	1
Unknown	60	9	1	0
Contributory Causes				
Climbing unroped	960	161	19	2
Exceeding abilities	877	199	4	1
Placed no/inadequate protection	646	94	27	12
Inadequate equipment/clothing	630	68	21	0
Weather	442	63	10	1
Climbing alone	370	67	13	2
No hard hat	304	28	12	1
Nut/chock pulled out	196	31	0	1
Inadequate belay	181	27	9	1
Darkness	134	20	2	0
Poor position	151	20	6	0
Party separated	110	10	3	2
Piton/ice screw pulled out	86	13	0	0
Failure to test holds	89	28	4	3
Exposure	57	13	0	0
Failed to follow directions	71	11	0	0
Illness[1]	39	9	0	0
Equipment failure	11	7	0	0
Other[4]	251	99	5	1
Age of Individuals				
Under 15	123	12	2	0
15-20	1226	202	9	1
21-25	1304	246	33	5
26-30	1208	205	27	3

	1951-03 USA	1959-03 CANADA	2004 USA	2004 CANADA
Age of Individuals (continued)				
31-35	1011	110	18	2
36-50	1090	136	58	5
Over 50	191	27	15	2
Unknown	1900	504	33	13
Experience Level				
None/Little	1676	294	48	5
Moderate (1 to 3 years)	1494	354	50	0
Experienced	1718	427	79	6
Unknown	1915	511	43	24
Month of Year				
January	202	23	7	2
February	196	51	2	4
March	279	66	13	2
April	381	33	8	5
May	847	55	18	2
June	979	65	30	4
July	1061	244	24	6
August	987	177	15	4
September	1136	70	11	4
October	415	38	20	0
November	175	14	5	2
December	86	24	7	0
Unkknown	17	1	0	0
Type of Injury/Illness (Data since 1984)				
Fracture	1049	206	67	10
Laceration	622	71	35	0
Abrasion	299	75	10	1
Bruise	406	77	27	4
Sprain/strain	281	29	24	2
Concussion	201	28	13	0
Hypothermia	144	15	3	1
Frostbite	112	9	4	0
Dislocation	99	15	10	1
Puncture	42	13	1	0
Acute Mountain Sickness	39	0	1	0
HAPE	65	0	0	0
HACE	23	0	0	0
Other[3]	274	43	20	4
None	184	182	23	6

[N.B.] Some accidents happen when climbers are at the top or bottom of a route, not climbing. They may be setting up a belay or rappel or are just not anchored when they fall. (This category was created in 2001. We still have "Unknown" because of solo climbers.)

[1] These illnesses/injuries, which led directly or indirectly to the accident, included: AMS, deep vein thrombosis, tooth problems, HAPE, frostbite, and an acute abdomen.

[2] These include no back-up knot—so rappelled off end of ropes, inadequate anchors, rope too short, improper use of descending device, inattention by belayer when lowering.

[3] This category was set up originally for ski mountaineering. Backcountry touring or snowshoeing incidents—even if one gets avalanched—are not in the data.

[4] These include: hand or foothold broke off (10); frostbite (3); unable to self-arrest (7); rope ascender came off; failure to disclose medical condition to guides (2); dislocated shoulder while mantling; rope jammed in crack; carrying ice ax upside down; bee attack; simul-climbing—so too much slack in rope; ice pillar broke off; threw whole rope down—so came undone when weighted; late starts resulting in benighting (2); failure to follow instincts; wet rock (3); leader unable to communicate with belayer (2).

[5] These included: dehydration and exhaustion (5), DVT, rope burns on hands; kidney failure; collapsed lunch; pneumo/hemothorax; heat exhaustion; multiple bee stings; internal injuries; acute abdomen (unknown problem); tooth problems; lightning burns.

Editor's Note: Under the category "other," many of the particular items will have been recorded under a general category. For example, the climber who dislodges a rock that falls on another climber would be coded as Falling Rock/Object, or the climber who has a hand hold come loose and falls would also be coded as Fall On Rock.

A climber disappeared on Mt. Sir Sanford, but no details are known as to whether it was on ascent or descent or what the cause may have been so it is reported as "unknown."

Appendix B: Gear Specifications

Climbing equipment is designed to be both lightweight and strong. However, these goals are often in opposition, so the end result is equipment made strong enough for standard climbing applications, and as light as possible while still allowing for a decent margin of safety. This fact becomes increasingly important when we move out of “normal” recreational use and into the more complex systems and forces seen in rescue situations. To account for this, many SAR teams use heavy-duty gear: steel carabiners and super-fat webbing straps, specialty pulleys and thicker diameter ropes. Carrying gear of this magnitude when recreational climbing is unrealistic, so realize that when you are faced with a more complex rescue an awareness of your gear’s strength ratings will help you make educated decisions and construct systems appropriate to the situation.

The manufacturers’ specifications that accompany climbing gear often seem confusing and can be difficult to interpret on their own. Check out the rated strength of a climbing rope, webbing, and carabiners—the common links in our systems—then note the strength on a single wired nut, and add a few knots in all the webbing and rope associated with a normal system. It is quickly clear that equipment strength is important, especially considering the forces that can be generated in a rescue.

It is worth noting that there are no North American gear strength standards. Therefore, in the US you could theoretically start making carabiners in your garage and sell them at your local shop. In Europe minimum gear standards do exist: CE standards. A product must meet these CE specifications in order to be sold legally in Europe. Most major climbing gear manufacturers, North American included, make gear that meets CE standards. However, manufacturers may choose not to pursue a CE certification; CE certification involves time and money that many smaller companies can't afford. In fact, most companies perform tests above and beyond that which would be required of them by CE. Beware though: some manufacturer's gear still does not meet the CE requirements. The UIAA also certifies gear to their own standards, though its seal of approval is not mandatory for sale into Europe. Often UIAA tests are more stringent than CE tests.

In this appendix we have compiled minimum CE strength requirements for commonly used climbing gear as well as some basic information to help interpret the terms. To see how strong your gear is check the manufacturer specifications. Often the kN strength rating is stamped or printed on the piece.

DEFINITIONS

KILONEWTON (kN):

- A newton is the amount of force required to accelerate a mass of one kilogram at a rate of one meter per second squared (1 N = 1 kg x 1 m/s2). Force = mass x acceleration. A kilonewton is 1000 newtons
- A kN is an accurate indication of tested strength because it factors in force due to gravity.
- To obtain a more familiar, if not completely accurate, measurement you can use these formulas to convert the metric system to the English system:

1 kN = 100 kg = 224.8 lb
X kN x 100 kg = X kg
X kN x 224.8 lb = X lbf

POUND FORCE (LBF):

■English system equivalent of the kN. Basically pounds, but also indicates force due to gravity.

IMPACT FORCE:

■Amount of stress put on an object as a result of a fall. For a rope or helmet, low impact force is desirable. It indicates that the rope or helmet absorbs some of the stress so the other objects involved—like the climber, protection, or the sharp edge—do not receive the full potential force.

BASIC CONVERSIONS

These numbers are listed in case you want to break out the calculator and start figuring out forces, loads, and so on.



lb		oz		g		kg
2.2	=	35.3	=	1000	=	**1 kg**
.00022	=	.035	=	**1 g**	=	.001
.063	=	**1 oz**	=	28.35	=	.02835
1 lb	=	16	=	453.6	=	.454



in		yd		m		mm
.039	=	.000108	=	.001	=	**1 mm**
1 in	=	.028	=	.0254	=	25.4
36	=	**1 yd**	=	.9144	=	914.4
39.37	=	1.093	=	**1 m**	=	1000

ROCK PROTECTION

Note that the numbers given are from laboratory test conditions. It doesn't matter how strong the piece is if the rock is poor quality. The wire on protection pieces is often the weakest link so, generally, the bigger the wire, the stronger the piece. This includes camming devices.

Wired/slung Nuts and Chocks
CE standard: 2kN (449.6 lbf)
Spring Loaded Camming Device (SCLD) CE standard: 5kN (1124lbf)

Note: SLCDs vary widely in strength ratings. Some of the very small ones (usually marketed as aid pieces only) do not meet the CE minimum and therefore are not certified. Conversely, many of the larger cams are much stronger than the CE minimum.



BOLTS		
Solid Head Sleeve Bolt	Strength/ Medium Rock (lb)*	Strength/Hard Rock (lb)
3/8 in by 3 in	23/32 kN (5200/7200)	25/36 kN (5600/8100)
1/2 in by 33/4 in	33/45 kN (7300/10,000)	44/48 kN (9800/10,700

* First number is tensile strength and the second is shear strength. Tensile strength is how strong the metal is when a load pulls directly out on it (similar to the slow pull testing used for ropes, cord, and webbing). Shear strength is how strong the shaft of the bolt is when weighted parallel with the rock surface. This test is more relevant as it reflects normal use for bolt anchors and sport climbing bolts.

BOLT HANGERS

UIAA standard: 25 kN



CARABINERS			
CE standards	Gate closed (Major Axis)	Gate open	Gate side (Minor Axis)
Oval	18kN	5kN	7kN
D-shaped	20kN	7kN	7kN
HMS (for belaying)	20kN	6kN	7kN

Note: Locking carabiners need to pass the same strength test numbers.

OTHER GEAR

ASCENDERS

CE standards require statically weighting an ascender on a rope to 4 kN five times. The ascenders should not deform or sustain damage and the rope should not sustain damage. Note that all ascender tests are static. Ascenders are not meant to hold dynamic falls.

Synthetic ropes generally fail at less than one-third the rope's strength when force is applied through an ascender. Do not rely on an ascender to hold a dynamic fall. It is not likely that the ascender will break but the rope almost definitely will fail.

HELMETS

To be CE-approved, helmets must pass the following tests:

- a rounded 5 kg weight dropped from 2 m - the measured impact force must be under 10 kN;
- a flat 5 kg weight dropped onto the front of the tilted helmet - the measured impact force must be under 10 kN
- a flat 5 kg weight dropped onto the back of the tilted helmet - the measured impact force must be under 10 kN
- a flat 5 kg weight dropped onto the side of the tilted helmet - the measured impact force must be under 10 kN
- a sharp 3 kg weight dropped from one meter - the result should be less than full penetration
- the chin strap loaded with 500 N - must result in less than 25 millimeter stretch
- a roll-off test that is difficult to explain

Climbing helmets are certified when they protect against objects hitting your head. They are not approved to protect your head when it hits something else. So wearing a CE-approved helmet is no assurance (for your head) against a long pendulum fall into a corner or a 20-foot ground fall. Bike helmets on the other hand are "approved" when they protect your head when it hits something but not from things hitting your head. Some climbing helmets do have good protection in both areas, though the CE label does not recognize this. No bike, ski, or kayak helmet is CE approved for climbing.

ICE SCREWS

CE approval strength: 10 kN (2248lbf)

An ice screw is only as good as the ice it is placed in.

ICE AXES

Ice axes can have one of two CE strength ratings.

B-rated (Basic) axes have shafts strong enough for general use.

T-rated (Technical) axes are 30 to 40 percent stronger and are designed for heavy abuse, like torquing of the shaft while climbing mixed routes.

Ice axes with interchangeable picks could have a B shaft with a T pick or vice versa.

ROPES & WEBBING :

ROPES AND CORD

In order to be CE certified, rope and cords must pass the following tests described below. (UIAA standards are typically very similar.) All tests are conducted on brand new sections of rope and cord. It's important to recognize that results would differ greatly with used materials. Materials are tested without knots, sharp edges, or other common occurrences that also decrease overall strength.

SINGLE DYNAMIC CLIMBING ROPES

Note: Rope standards do not differ based on a rope's diameter; rather, all single dynamic climbing ropes must pass these minimums in order to receive CE certification.

A sample of rope is placed in the test rig by means of a figure eight knot attached to an 80kg mass on one end and firmly clamped to a fixed anchor on the other. A factor 1.77 drop is then performed every five minutes until the rope fails. A detailed drawing of of the test configuration can be found at *http://www.uiaa.ch/web.test/visual/Safety/SafComPictorials/PictUIAA101-EN892DynamicRopes. pdf*

- Static elongation must be less than 10%.
- Impact force can be no greater than 12 kN (Note this is tested on one initial drop.)
- No fewer than 5 falls held.
- Dynamic elongation cannot exceed 40% on first drop.
- Sheath slippage (either positive or negative) can be no greater than 20mm. The rope is run multiple times through a device that pulls down on the rope's sheath like a circular squeegee.

There is no tensile strength requirement for single dynamic climbing ropes.

ACCESSORY CORD (NYLON)

Multiple tests are run to ensure accurate measurement of a cord's diameter and weight but tensile strength tests are the only type of tests required to measure how cord will perform under load. Cords between 4 and 8 millimeters are tested.

Cord is pulled on a double drum machine that slowly draws the material out in either direction. The breaking point determines the strength rating. 7mm cord must have a strength rating of 9.8 kN and 8 mm cord a rating of 12.8 kN.

WEBBING AND CORD MATERIALS

NYLON WEBBING

One-inch tubular nylon webbing, first put into use during World War II, is cheap, strong, and abrasion-resistant, but is heavier than many of the other material currently on the market (such as Super Tape and HMPE materials, i.e., Dyneema and Spectra). Most climbers reserve nylon webbing for setting up top-rope anchors and they carry short sections of it on multipitch climbs to leave on rappel anchors. Although nylon webbing does not stretch the way a high-stretch (aka dynamic) rope does, it certainly stretches to some degree. It is a common misconception that webbing has no give at all. When weight is applied the webbing (and any type of material used as a runner) elongates, thereby reducing the amount of force the anchor receives.

11/16-INCH WEBBING

Super Tape (one manufacturer’s brand name) is a slimmed-down version of 1-inch tubular nylon webbing. It is not as strong as 1-inch tubular, but is lighter and it has a narrower profile and is therefore favored by many climbers. It is resilient and durable, and it also has good friction holding power on a rope for tying friction hitches.

HMPE (DYNEEMA/SPECTRA)

Plastic grocery bags, six-pack carriers, and milk jugs are the not-so-distant cousins of HMPE products like Spectra and Dyneema—exceptionally strong, lightweight, and fairly water-resistant materials popular in the construction of sewn runners. Although remarkably strong, HMPE products do not absorb energy as well as nylon, due to lower elongation (they are not as stretchy). Another downfall is that its slippery nature makes it difficult for it to hold a knot, and knots significantly reduce a HMPE runner’s strength, some sources say up to 50 percent. (This is one reason why the runners are sewn. They can indeed be tied; a triple fisherman’s knot is recommended to account for the material’s slippery properties but is still not ideal.) HMPE also has a very low melting point. The material begins to yield (i.e., deform) at just 67°C. It is therefore not recommended for friction hitches.

ARAMID (KEVLAR/GEMINI CORD)

Many aramid materials, like Gemini cord, contain Kevlar, which make them incredibly strong. At the same time this can be a disadvantage because the cord is not very flexible and is difficult to tie knots in. This type of material is typically reserved for creating slings for climbing protection (like those used with Hexcentrics). While it can withstand extremely high temperatures (decomposition begins at 500°C). it is neither very abrasion resistant nor does it absorb forces all that well. Its fibers are also more brittle and degrade with flexing and knots.

NYLON CORD

Many climbers carry a 15- to 20-foot piece of small-diameter nylon cord (also called Perlon) or cordelette on their harnesses for rigging multidirectional anchors. It can also double as a useful rescue tool. Although nylon cord is not as strong as some of the other cord or webbing products on the market, it is easy to tie knots in, is light, and is fairly abrasion resistant. Cord smaller than 7 millimeters will certainly hold your weight, though it is not advised for improvisational rescue purposes. Be aware that cord between 4 and 8 millimeters may be UIAA certified (EN 564), but it is not tested for shock absorption or elasticity. Only mass and tensile strength are tested. Many climbing institutions require cordelettes to be at least 7-millimeters thick.

Be wary of the latest and greatest products on the market. Tried and true products work very well; often, newer products will make improvements in one area but may be lacking in another.

Appendix C: Knot Efficiencies

The following information on knot efficiencies and strength-loss percentages is provided for those of you who fancy yourself "tech geeks": people who enjoy getting into the minutia and science of systems.

It is by no means necessary to memorize the breaking strength of every single knot known to climbers, but it can be interesting to note comparative strengths. Just understanding the basic concept behind a knot's breaking strength is enough to help you make educated decisions and think critically about the knots you are choosing to tie and why.

A rope's (webbing's or piece of cord's) tensile strength is measured by the rope being pulled in a straight line. This is the scenario in which a rope is the strongest; the fibers inside the rope are all being pulled in a straight line. The minute any change of direction is introduced, the fibers become less efficient; in other words, strength is lost. As the rope curves, the fibers on the outside of the rope elongate while the fibers on the inside of the curve are compressed. When weighted, the elongated fibers hold a greater percentage of the load than the compressed fibers. The tighter this curve, the more unequal the weight distribution is between the elongated side and the compressed side and the less efficient the rope becomes. That is why typically rope, cord or webbing break on the outside of a knot's radius instead of within it.

For example, tie an overhand on a bight in a dynamic climbing rope and the rope's strength decreases by 32 to 42 percent. Tie a figure eight on a bight instead and the rope's efficiency decreases 23 to 34 percent. The reason for this difference is that the radiuses of an overhand on a bight's curves are tighter than those of a figure eight on a bight. However, as explained in chapter 2, Rescue Knots, there are multiple factors to consider when choosing a knot. Strength is merely a part of the puzzle worth understanding.

When tying a hitch it is worth understanding that the resulting curve will depend on not only the type of hitch but also on the ratio between the diameter of the material being tied and what it is being tied around. A piece of webbing girth-hitched to a piece of cord will have much sharper curves and bunching in it (and thereby a greater loss in strength) compared to a piece of webbing girth-hitched around a large tree. The greater the ratio, the less strength lost; the smaller the ratio, the more strength lost.

Test results vary considerably, perhaps because there are simply *so* many variables. This explains why the figures presented below are ranges instead of exact percentages. A good rule of thumb is that any combination of standard climbing knots will reduce a material's strength by a minimum of about 30 percent.

This information was compiled from the following sources: Geoffrey Budworth's *Illustrated Encyclopedia of Knots*, Craig Luebben's *Knots for Climbers*, Clyde Soles's *Outdoor Knots Book*, and WSCMRT Training's "Basic Ropes and Knots."

TYPE OF TIE	PERCENTAGE OF STRENGTH LOST
No knot (tensile strength of webbing cord, rope)	0 %
LOOPS	
Figure eight on a bight	20–30 %
Figure eight follow-through	19–34 %
In-line figure eight	25%
Butterfly	28–39%
Bowline	26–45%
Double bowline	25–30%
Overhand on a bight	32–42%
Overhand on a bight (tied in webbing)	32–42%
Figure eight on a bight (tied in webbing)	30%
HITCHES	
Clove hitch	35–45%
Girth hitch	30-60%
Two half hitches	35–40%
BENDS	
Water knot (tied in webbing)	30–40%
Double fisherman’s	20–35%
Flemish bend	19–30%

Appendix D: Continuing Education

These organizations provide training and valuable publications should you want to continue learning skills pertinent to the field of rescue (like first-aid training), find groups with which to practice your techniques, or take your skills to the next level.

The American Alpine Club
710 10th Street, Suite 100
Golden, CO 80401
(303) 384-0110 www.americanalpineclub.org

The American Alpine Club (AAC), in operation since 1902, is the United States' national mountaineering and climbing organization. Each year the AAC publishes *Accidents in North American Mountaineering* , the *American Alpine Journal*, and the quarterly *American Alpine News*.

The Alpine Club of Canada
PO Box 8040, Indian Flats Road
Canmore, AB

Canada T1W 2T8
(403) 678-3200 www.alpineclubofcanada.ca

The Alpine Club of Canada (ACC) is Canada's national mountaineering organization and has been a focal point for Canadian mountaineering since 1906. The ACC's website contains a variety of interesting and informative technical articles.

American Mountain Guides Association
Physical address:
1209 Pearl Street, Suites 12 and 14
Boulder, CO 80302

Mailing address:
PO Box 1739
Boulder, CO 80306
(303) 271-0984 www.amga.com

The American Mountain Guides Association (AMGA), founded in 1979, provides support and education to American mountain guides and establishes standards for guiding. The AMGA maintains a database of AMGA-certified guides around the country and affiliated guiding companies.

Association of Canadian Mountain Guides
Box 8341

Canmore, AB
Canada T1W 2V1
(403) 678-2885
www.acmg.ca
Training and Certification Programs
University College of the Caribou
Box 3010
Kamloops, BC
Canada V2C 5N3
(250) 372-0118

Like the AMGA, the Association of Canadian Mountain Guides is a trade and education association for professional mountain guides.

Cordage Institute
994 Old Eagle School Road, Suite 1019
Wayne, PA 19087
(610) 971-4854 www.ropecord.com

The Cordage Institute is an international association of manufacturers, producers, and resellers of cordage, rope, and twine. The institute is involved in the development of standards and guidelines and also publishes a technical manual, *The Ropecord News*, and documents about the safe use of cordage and rope.

International Critical Incident Stress Foundation Inc.
www.icisf.org

This website provides links, articles, and even a hotline number for people struggling with the aftermath of a traumatic event.

International Technical Rescue Symposium
C/O National Association for Search and Rescue
PO Box 232020
Centreville, VA 20120
877-893-0702 www.nasar.org/nasar/conferences.php?id=146

The International Technical Rescue Symposium (ITRS) is an annual gathering of people involved in all disciplines of rescue, including mountain rescue.

Mountain Rescue Association
PO Box 880868
San Diego, CA 92168 www.mra.org

The Mountain Rescue Association (MRA), formed in 1958, shares information to improve patient care in the mountains and to improve SAR techniques. It is an excellent resource and informational tool for those interested in learning more about organized rescue.

National Association for Search and Rescue

PO Box 232020
Centreville, VA 20120
877-893-0702
www.nasar.org

The National Association for Search and Rescue (NASAR) is dedicated to advancing professional, literary, and scientific knowledge in fields related to search and rescue.

Petzl America
PO Box 160447
Clearfield, UT 84016
(801) 926-1500 en.petzl.com/petzl/Accueil

Petzl, a climbing, caving, canyoneering, and technical-rescue gear manufacturer, provides valuable information on their website and in catalogs about roped climbing and rescue. Their website also includes a "fall factor simulator."

Rigging for Rescue
PO Box 745324
5th Street
Ouray, CO 81427
(970) 325-4474 www.riggingforrescue.com

Rigging for Rescue provides technical rescue workshops emphasizing critical thinking about the statistics and dynamics of rigging, all backed by physics and testing.

Sterling Rope Company
31 Washington Avenue
Scarborough, ME 04074
(207) 885-0330 www.sterlingrope.com

Sterling Rope Company's website offers useful information on rope care, strength, and safe application.

Wilderness Medical Associates
189 Dudley Road
Bryant Pond, ME 04219
888-WILDMED
www.wildmed.com

Wilderness Medical Associates has been teaching courses since 1978 in wilderness emergency situations, rescue, SAR, disaster, and mass casualty, all focused on providing care in a wilderness context.

Wilderness Medical Society
5390 N Academy Boulevard, Suite 310
Colorado Springs, CO 80918
(719) 572-9255 www.wms.org

The Wilderness Medical Society (WMS) is a trade organization for physicians and health professionals. The society publishes a peer-reviewed medical journal, a quarterly newsletter, and an educational presentation series on wilderness medicine topics.

Wilderness Medicine Institute
C/O National Outdoor Leadership School
284 Lincoln Street
Lander, WY 82520
(866) 831-9001 www.nols.edu

The Wilderness Medicine Institute (WMI) offers classes focusing on elements of first aid and emergency medicine unique to wilderness travelers.

Wilderness Risk Managers Conference
NOLS Professional Training
284 Lincoln Street
Lander, WY 82520
(307) 332-8100 www.nols.edu/wrmc/

The Wilderness Risk Managers Conference is held every fall with the goal of helping wilderness enthusiasts and professionals share information on important developments in the field of risk management and wilderness adventure.

Appendix E: Recommended Reading

The following books and magazines can help you further your technical-rescue knowledge as well as develop climbing, critical-thinking, and wilderness medicine skills. Having these skills is an important component in lessening the chance of needing a rescue in the first place. Many of these books were also used as references in writing this book.

ACCIDENTS

American Alpine Club. *Accidents in North American Mountaineering*. Golden, CO: American Alpine Club Press. Published annually.

CLIMBING AND MOUNTAINEERING TECHNIQUES

Chouinard, Yvon. *Climbing Ice*. San Francisco: Sierra Club Books, 1978.
Cox, Steven M., and Kris Fulsaas, eds. *Mountaineering: The*

Freedom of the Hills. 7th ed. Seattle: The Mountaineers Books, 2003.

Gadd, Will. *Ice and Mixed Climbing: Modern Technique*. Seattle: The Mountaineers Books, 2003.

Houston, Charles. *Going Higher*. 4th ed. Seattle: The Mountaineers Books, 1998.

Houston, Mark, and Kathy Cosley. *Alpine Climbing: Techniques to Take You Higher*. Seattle: The Mountaineers Books, 2004.

Long, John. *How to Rock Climb: More Climbing Anchors*. Evergreen, CO: Chockstone Press, 1996.

Long, John, and Craig Luebben. *How to Rock Climb: Advanced Rock Climbing*. Helena, MT: Falcon, 1997.

Long, John, and John Middendorf. *How to Rock Climb: Climbing Big Walls*. Evergreen, CO: Chockstone Press, 1994.

Lowe, Jeff. *Ice World, Techniques and Experiences of Modern Ice Climbing*. Seattle: The Mountaineers Books, 1996.

Luebben, Craig. *How to Rappel*. Guilford, CT: Globe Pequot/Falcon, 2000.

_____. *Rock Climbing: Mastering the Basic Skills*. Seattle: The Mountaineers Books, 2004.

March, Bill. *Modern Rope Techniques in Mountaineering*. Cumbria, England: Cicerone Press, 1990.

Pesterfield, Heidi. *Traditional Lead Climbing: Surviving the Learning Years*. Berkeley: Wilderness Press, 2002.

Powers, Phil. *NOLS Wilderness Mountaineering*.

Mechanicsburg, PA: Stackpole Books, 1993.

Twight, Mark, and James Martin. *Extreme Alpinism, Climbing Light, High and Fast*. Seattle: The Mountaineers Books, 1999.

EQUIPMENT AND KNOTS

Ashley, Clifford. *The Ashley Book of Knots*. New York: Doubleday, 1944.

Budworth, Geoffrey. *The Illustrated Encyclopedia of Knots*. New York: The Lyons Press, 2002.

Luebben, Craig. *Knots for Climbers*. 2nd ed. Guilford, CT: Globe Pequot, 2002.

Soles, Clyde. *The Outdoor Knots Book*. Seattle: The Mountaineers Books, 2004. _____. *Rock and Ice Gear: Equipment for the Vertical World*. Seattle: The Mountaineers Books, 2000.

WSCMRT Training. "Basic Ropes and Knots." *www.western.edu/wscmrt/docs/pdf/trng_rope.pdf* .

FIRST AID AND WILDERNESS MEDICINE

Hackett, Peter, MD. *Mountain Sickness, Prevention, Recognition, and Treatment*. Golden, CO: American Alpine Club

Press, 1980.

Schimelpfenig, Tod, and Linda Lindsey. *NOLS Wilderness First Aid*. Mechanicsburg, PA: Stackpole Books, 1991.

Tilton, Buck. *Backcountry First Aid and Extended Care*. 4th ed. Guilford, CT: Globe Pequot, 2002.

Wilkerson, James. *Medicine for Mountaineering and Other Wilderness Activities*. 5th ed. Seattle: The Mountaineers Books, 2001.

RESCUE DEBRIEFING AND TRAUMA RESPONSE

Conover, K. C. "Wilderness EMT Curriculum: Stress Management and Critical Incident Stress Debriefing." Syllabus, Appalachian Search and Rescue Conference, Pittsburgh, PA, 1990.

Mitchell, J. "Development and Functions of a Critical Stress Debriefing Team." *Journal of Emergency Medical Services* 12, no. 12 (1988): 42-46.

Rothschild, Babette. *The Body Remembers*. New York: W. W. Norton, 2000.

RESCUE TECHNIQUES

Fasulo, David. *How to Rock Climb: Self-Rescue*. Helena, MT: Falcon, 1997.

Frank, James A., and Jerrold B. Smith. *CMC Rope Rescue Manual*. Santa Barbara, CA: CMC Rescue Inc., 1992.

Lipke, Rick. *Technical Rescue Riggers Guide*. Bellingham, WA: Conterra Inc., 1998.

Smith, Bruce, and Allen Padgett. *On Rope: North American Vertical Rope Techniques*. Rev. ed. Huntsville, AL: National Speleological Society, 1996.

Tyson, Andy. *Glacier Mountaineering: An Illustrated Guide to Glacier Travel and Crevasse Rescue*. 2nd ed. Carbondale, CO: *Climbing Magazine,* 2004.

Vines, Tom, and Steve Hudson. *High Angle Rescue Techniques*. 2nd ed. St. Louis: Mosby, 1999.

Glossary

ascension rig - a combination of cords or mechanical ascenders that allow a climber to move up a rope. Common names include: Prusik rig (generally two cords - one called a waist Prusik and the other called a foot Prusik); ascender rig uses mechanical ascenders instead of Prusik hitches.

belay escape - a series of steps that allow the belayer to move and tie off the belay to an anchor so that he is free to enact a rescue. The belayed climber's position is maintained on the rope.

belay loop - a sewn loop on most harnesses that is the main connection point between the harness and the leg loops.

bend - a tie that joins the ends of a piece of material together either to form a continuous loop or links two pieces of material together. The tail ends exit the knot in opposite directions.

bight - like a half circle; there is an obvious curve in the rope, but the rope strands do not cross one another.

brake strand - the side of rope breaking a climber's fall--the strand that will be fed through a belay device to lower a climber.

clipping-in short - tying or clipping into the rope at waypoints to reduce the amount of slack in the system; commonly used while ascending a line.

cordelette - a piece of perlon or cord that is generally approximately 7 millimeters in diameter. Its length varies - generally around 10 - 25 feet though it can be shorter.

counterbalance rappelling - using the injured climber's weight on one side of the rope to counterbalance the rescuer's weight for a quick rappel.

cow's tail - a short sling girth hitched to the belay loop; used for attaching to an anchor, setting up a tandem rappel, and rappelling.

cross-loading - loading a carabiner across its short axis: across the gate and spine. This is a much weaker orientation for a carabiner.

crux - the hardest part of a climb; may be only a few moves or it can be longer. A climb is generally rated for the difficulty of its crux.

cyclical loading - the repeated weighting and unweighting of a piece of cordage or webbing.

daisy chain - sewn-webbing leash that a climber uses to attach himself to an anchor or aid pieces. Depending on the style of construction a daisy is generally not made to hold more than body weight.

directional anchor - an anchor that is good for holding a load in one direction.

dressed knot - a tie that does not have any kinks or loose or unnecessarily twisted portions. It has also been "set" or snugged-down with a good tug prior to loading.

dynamic rope - a nylon rope that absorbs force by stretching when loaded.

Dyneema - *See* HMPE.

emergency procedures - organizational framework used to deal with emergency situations.

figure nine - a figure eight on a bight with an additional wrap around the eight's center.

fireman's belay - a back-up belay for rappelling.

fixed-line ascension - climbing a rope that has been anchored at the top and sometimes the bottom. Friction hitches or mechanical ascenders are used to grab the rope and move up or down it.

foot Prusik - a piece of cord that is attached to the rope with a friction hitch. It is long enough to put a foot in and stand up. Used as part of an ascension rig.

foot wraps - wrapping the rope around your foot for friction.

force - the capacity to do work or cause physical change; a vector quantity.

French-freeing - pulling on a piece of climbing gear to help upward progress. Considered poor free climbing style, but useful for quickly getting up challenging sections when time is important.

friction hitches - a type of tie that, when tied around a rope, grabs and holds fast to that specific spot on the line even when weighted.

hands-free - tying off the belay so that the rescuer is able to let go of the belay strand, allowing him to use both hands for another task.

hitch - a tie that has to be tied around something to maintain its form.

HMPE - an exceptionally strong, lightweight and fairly water-resistant material used in making sewn runners. The downsides of HMPE are that its slippery nature makes it a poor choice for knots and it has a very low melting point, so it is generally not recommended friction hitches.

kiloNewton - the amount of force required to accelerate a mass of 1000 kilograms at a rate of one meter per second squared (1 kN = 1000 kg x 1 m/s2).

leap-frog - to use one piece of gear as protection while moving the previous protection piece forward to protect the next move.

kN - *See* kiloNewton.

leg wraps - wrapping the belay strand around the leg to substitute for the break hand. This allows the climber to be hands-free.

lfb - *See* pound force.

load strand - whichever strand of rope is actively holding the load (e.g., the climber). **locking-assist belay device -** a belay device, such as the Petzl GriGri or Trango Cinch, that automatically locks onto the rope in the event of a fall.

loop - a tie that forms a continuous circle and can be tied anywhere along a rope. a loop can also be created without a knot in which case it is like a bight except that the rope strands do cross and the circle is closed.

master point - the main connection point for attaching anything to an anchor.

mechanical advantage - a system that spreads work out over time and distance to reduce the amount of force necessary to complete a task.

mechanical ascenders - a climbing device that

MMO - abbreviation for Munter-mule-overhand.

MP - abbreviation for Master Point.

multidirectional anchor - an anchor constructed to hold a load in multiple directions. Most often constructed in multipitch climbing in which an anchor must be able to resist a downward pull as well as upward or sideways pulls.

multiplying advantage - stacking mechanical advantage systems; for example a 2:1 acts on a 3:1 thus creating a 6:1.

Munter-mule - two hitches commonly tied together; the Munter is used to belay a line and the mule is used to tie off the Munter.

PMMO - abbreviation for Prusik-Munter-mule-overhand.

PMP - Prusik-minding pulleys. **pound force** - the English units equivalent of the kiloNewton.

prusiking - using friction hitches to ascend a rope. Generally the climber uses a waist Prusik and a foot Prusik for his ascension system

pulley point -the moving pulley in a 3:1 system.

pulley system - *See* raising system.

raising system - a mechanical advantage system created to lift an object.

rappel backup - a safety backup to a climber's rappel break hand. If the climber is incapacitated on his rappel or he removes his break hand from the rope for any reason he will stop on the rope rather than sliding to the bottom (or off the ends).

ratchet - a device used to restrict motion in one direction.

redirectional piece - a piece of gear used to redirect the rope.

releasable hitch - a hitch that can be released while under load, generally without causing the system to fail.

rescue loop - a short loop of 7-millimeter cord tied with a Flemish bend or double fisherman's.

rescue pulley - a wheeled pulley used for rescue purposes.

rescue spider - a way to tie a cordelette that allows easy anchor-to-rappel transitions and security for tandem rappelling.

rope solo - a rope system to protect solo climbing.

self-blocking belay device - a belay device that can be set up to block or trap the rope in the event of a fall. The belayer can let go of his brake hand without compromising the belay.

self-tending ratchet - a friction hitch attached to the main hauling line that captures the gain of the raised load.

shear strength - resistance of a material to side force that would cause it to split and slide past itself. **shelf** - secondary anchor clip-in point.

It is above the master point, but still redundant if constructed properly.

short roping - a guiding technique used to assist a challenged climber through exposed terrain.

simul-climbing - a rope system allowing two or more climbers to climb at the same time, including the leader.

Spectra- *See* HMPE.

static rope - a rope that is constructed to be low-stretch. Generally the rope absorbs less force and therefore transfers more of that force to the anchors or climber.

tandem rappelling - two people attached together and rappelling on the same lines.

tensile strength - the resistance of a material to a force that is pulling or tearing it apart.

tension release hitch - *See* releasable hitch.

tether - a short sling or section of rope used to attach something (for example, a climber) to an anchor.

third hand - a piece of cord that is tied onto the rope with a friction hitch and clipped to the harness, used as a backup to a climber’s brake hand on rappel.

triaxial loading - loading a carabiner in three directions. Carabiners are designed to be loaded in two directions along their longest axis; triaxial loading greatly reduces a carabiner's strength.

tubular belay device - a common style of belay device (e.g., ATC, Tuber, Stichplate, Pyramid, etc.).

waist Prusik - *See* ascension rig.

working end - the side of the rope leading to the anchor, the inactive climber, or simply the end that runs into the rope bag.

Index

Photographs or illustrations are indicated in bold.

A

Accident statistics
Acknowledgements
Aiding
Airplanes
Anchor construction
pulley point
terminology
Aramid
Ascending
fixed line
French freeing
garda hitch
glaciers
injured leader

mechanical ascenders
  passing a knot
stuck rappel ropes
rig
  rope soloing
Autoblock hitch

B

Bachmann hitch
Backpack carry
rope organization
Backup knots
Belay escapes
  off anchor
off body
  off redirectional
Belaying
off anchor
position
terminology
Bend

Bight
Block and tackle
Bottom strand
Butterfly knot
Brake strand

C

Carabiners
efficiencies
Carrying devices
  See improvisational litters
Cell phone
Chest harness
Climbing rope bed stretcher
Clipping in short
Clove hitch
Conversion table
Cord
Cordelette
Counterbalance rappelling
Cow's tail

Cross-loading
Cutting a rope
Cyclical loading

D

Decision making
Descending a fixed line
Diaper harness
Directed throw
Directional anchor
Double fisherman’s
Dressing, knots
Drop-line assist
Drop-loop assist
Dynamic rope
Dyneema

E

Edge protection
Edge transitions
11/16" webbing
Emergency gear procedures
Escaping a belay
  See belay escapes
Etrier
Equipment
  See gear and gear specifications

F

Figure eight on a bight follow-through
Figure nine
Fireman’s belay
First aid kit
Fisherman’s, double see *double fisherman’s*

5:1 raise
Fixed line ascension see *ascension*
  ascension
Flemish bend
Foot Prusik
sling
wrap
French freeing
Friction hitches

G

Garda
Gear
specifications and strengths
Gemini cord
Glaciers
Glossary

H

Half ropes
Hands free
Harness hang syndrome
improvisational
See improvisational harnesses
Hauling
See raising
Head sling
Helicopters
See airplanes
Hitches
HMPE
Holsters

I

Impact force
Improvised liters and carrying devices
Improvised harnesses
Injured leader

J

Jacket stretcher

K

Kevlar
KiloNewton
Klemheist
Knife
Knot strength
terminology
  tying & tips

L

Lbf

See pound force
Leg wraps
Litters
  See improvisational litters
Load strand
Locking assist belay device
Locking carabiners
Loop
Lower body sling
Lowering
  A leader

M

Managing rappel ropes
Mariner's hitch
Master point
Measurements
  See table conversion
Mechanical advantage
Mechanical ascenders
MP

See master point
Mule hitch
Multi-directional anchor
Multiplying advantage
Munter hitch
Munter-mule-overhand
MMO
See Munter-mule-overhand
Munter pop

N

9:1 raise
Nonlocking carabiners
Nylon

O

1:1 assist
One-person split rope carry

P

Passing knots
  ascending
  descending
lowering on the anchor raising
rappelling
top rope belaying
top rope lowering
Patient/rescuer positioning
Penberthy
Perlon
Pick-off
PMMO
  See prusik munter mule overhand
PMP
  See prusik-minding pulley
Pole carry, two-person
Post Traumatic Stress Disorder
Pound force
Prusik hitch

Prusking
Prusik-minding pulley
Prusik munter mule overhand
Pulley efficiency
point carabineer
point prusik
prusik

R

Raising systems
  drop line assist
  drop loop assist 2:1
if you need more
multiplying advantage
simple 1:1
  3:1 raises
Rappelling
backups
counterbalance
munter
position

stuck ropes
  tandem
Ratchet prussic
Reccomended reading
Redirectional piece
Reinforcing anchors
Releaseable hitch
Rescue insurance
loop
overview
spider
Revolver
Rigging an injured climber
Ring bend
  See water knot
Rope bed
damage
management
soloing

S

Self-blocking belay device
Self-tending ratchet
Shelf
Sheet stretcher
Short roping
Signals
Simul-climbing
6:1 pulley
Sleds
Slings, climbing gear
Slings, rigging an injured patient
Snow, patient transport on
Soloing
Spanish Burton
Spectra
Split-rope carry
Standing end
Stuck rappel ropes
Stretchers
  See improvised stretchers
Super tape

T

Tails, knot
Tandem rappelling
Ten essentials
Third hand
3:1 raise
Top strand
Tri-axial loading
Twin Ropes
2:1 raise
Two-person split rope carry
pole carry

V

Vector angles

W

Waist prusik
Water knot
Whistle
Webbing
Working end

Big mountains require honed skills. Competent climbers are ready for the unexpected.

About the Authors

Molly Loomis and Andy Tyson’s are international mountain guides. Their work, personal expeditions and travels have led them to crags and ranges around North America, and farther-flung places like Patagonia, Kyrgyzstan, Russia, Nepal, Bhutan, China, South Korea, India, and Antarctica. Together they bring more than twenty-five years of guiding and instructing experience to this book. Both also volunteer on their local search and rescue team. Andy is the author of *Glacier Mountaineering*, published by *Climbing* magazine, while Molly has published articles in publications such as *Rock and Ice*, *Climbing*, *Alpinist*, and the *American Alpine Journal*. Upcoming climbing adventures include returning to Antartica and the eastern Himalaya; they also enjoy spending time at their home in the Tetons.

The UIAA encourages the inclusion of information in guidebooks that helps visitors from overseas to understand the most important information about local access, grades and emergency procedures. The UIAA also encourages climbers and mountaineers to share knowledge and views on issues such as safety, ethics, and good practice in mountain sports. The UIAA is not responsible for, and accepts no liability for, the technical content or accuracy of the information in this guidebook. Climbing, hill walking and mountaineering are activities with a danger of personal injury and death. Participants should be aware of, understand and accept these risks and be responsible for their own actions and involvement.

THE MOUNTAINEERS, founded in 1906, is a nonprofit outdoor activity and conservation club, whose mission is "to explore, study, preserve, and enjoy the natural beauty of the outdoors. . . ." Based in Seattle, Washington, the club is now the third-largest such organization in the United States, with seven branches throughout Washington State.

The Mountaineers sponsors both classes and year-round outdoor activities in the Pacific Northwest, which include hiking, mountain climbing, ski-touring, snowshoeing, bicycling, camping, kayaking, nature study, sailing, and adventure travel. The club's conservation division supports environmental causes through educational activities, sponsoring legislation, and presenting informational programs.

All club activities are led by skilled, experienced instructors, who are dedicated to promoting safe and responsible enjoyment and preservation of the outdoors.

If you would like to participate in these organized outdoor activities or the club's programs, consider a membership in The Mountaineers. For information and an application, write or call The Mountaineers, Club Headquarters, 300 Third Avenue West, Seattle, WA 98119; 206-284-6310. You can also visit the club's website at *www.mountaineers.org* or contact The Mountaineers via email at *clubmail@mountaineers.org*.

The Mountaineers Books, an active, nonprofit publishing program of the club, produces guidebooks, instructional texts, historical works, natural history guides, and works on environmental conservation. All books produced by The Mountaineers Books fulfill the club's mission.

Send or call for our catalog of more than 500 outdoor titles:

The Mountaineers Books
1001 SW Klickitat Way, Suite 201
Seattle, WA 98134
800-553-4453
mbooks@mountaineersbooks.org
www.mountaineersbooks.org

The Mountaineers Books is proud to be a corporate sponsor of The Leave No Trace Center for Outdoor Ethics, whose mission is to promote and inspire responsible outdoor recreation through education, research, and partnerships. The Leave No Trace program is focused specifically on human-powered (nonmotorized) recreation.

Leave No Trace strives to educate visitors about the nature of their recreational impacts, as well as offer techniques to prevent and minimize such impacts. Leave No Trace is best understood as an educational and ethical program, not as a set of rules and regulations.

For more information, visit *www.LNT.org*, or call 800-332-4100.

MORE CLIMBING TITLES FROM THE TOP ATHLETES AND ORGANIZATIONS IN THE SPORT:


MOUNTAINEERING
The Freedom of the Hills
7

Mountaineering: The Freedom of the Hills, 7th Ed.
The Mountaineers
The all-time best selling standard reference for the sport of climbing.

Alpine Climbing: Techniques to Take You Higher
Kathy Cosley and Mark Houston


ALPINE CLIMBING:
Techniques To Take You Higher

BIG WALL CLIMBING:
Elite Technique

Big Wall Climbing: Elite Technique
Jared Ogden
Skills and strategies unique to big walls.

Ice and Mixed Climbing: Modern Technique
Will Gadd
Expand your climbing chops with instructions from the best.


ICE & MIXED CLIMBING:
Modern Technique


ROCK CLIMBING:
Mastering Basic Skills

Rock Climbing: Mastering Basic Skills
Craig Luebben
For beginner to intermediate climbers.

Gym Climbing: Maximizing Your Indoor Experience
Matt Burbach
Urban climbing for new climbers, climbers staying in shape and climbers who find all the challenge they desire indoors.


GYM CLIMBING:
Maximizing Your Indoor Experience


CLIMBING:
Training for Peak Performance

Climbing: Training for Peak Performance
Clyde Soles
Build the muscles you need for this ultimate of muscle-powered sports.

Climbing: Expedition Planning
Clyde Soles and Phil Powers
How to organize climbing trips from small to large groups.


CLIMBING:
Expedition Planning

THE MOUNTAINEERS BOOKS

GUNSMITHING

Made Easy

SUPER PRIMER

Bryce M. Towsley

Stoeger Publishing
Great Outdoor Books Since 1924

STOEGER PUBLISHING COMPANY
is a division of Benelli U.S.A.

Benelli U.S.A.
Vice President and General Manager:
Stephen Otway
Vice President of Marketing and Communications:
Stephen McKelvain

Stoeger Publishing Company
President: Jeffrey Reh
Managing Editor: Harris J. Andrews
Creative Director: Cynthia T. Richardson
Marketing and Communications
Manager: Alex Bowers
Imaging and Pre-Press Manager: William Graves
National Sales Manager: Jennifer Thomas
Special Accounts Manager: Julie Brownlee
Publishing Assistants: Amy Jones, Amy Sargent

Proofreader: Celia Beattie
Photography: Bryce Towsley

© 2006 by Stoeger Publishing Company.
All rights reserved.

No part of this book may be reproduced or transmitted in any form or by any means, electronic or mechanical, including photocopying, recording, or by any information storage and retrieval system, without permission in writing from the publisher.

Published by:
Stoeger Publishing Company
17603 Indian Head Highway, Suite 200
Accokeek, Maryland 20607

BK0511
ISBN-13: 978-0-88317-294-0
ISBN-10: 0-88317-294-1
Library of Congress
Control Number: 2004109586

Manufactured in the United States of America.

Distributed to the book trade and
to the sporting goods trade by:
Stoeger Industries
17603 Indian Head Highway, Suite 200
Accokeek, Maryland 20607
www.stoegerpublishing.com

OTHER PUBLICATIONS:

Shooter's Bible
The World's Standard Firearms Reference Book
Gun Trader's Guide
Complete Fully Illustrated Guide to Modern Firearms with Current Market Values

Hunting & Shooting:
Archer's Bible Presents:
The Bowhunter's Guide
Elk Hunter's Bible
High Performance
Muzzleloading
Big Game Rifles
High Power Rifle Accuracy
Hunt Club
Management Guide
Hunting Whitetails
East & West
Hunting the Whitetail Rut
Shotgunning for Deer
Taxidermy Guide
Tennessee Whitetails
Trailing the Hunter's Moon
The Turkey Hunter's
Tool Kit: Shooting Savvy
The Ultimate in Rifle Accuracy
Whitetail Strategies

Firearms:
Antique Guns
How to Buy & Sell Used Guns
Model 1911: Automatic Pistol
Modern Beretta Firearms

Reloading:
The Handloader's Manual of
Cartridge Conversions 3rd Ed.

Fishing:
Archer's Bible Presents:
Practical Bowfishing
Big Bass Zone
Catfishing:
Beyond the Basics
Fishing Made Easy
Fishing Online:
1,000 Best Web Sites
Flyfishing for Trout A-Z

Cooking Game:
The Complete Book of
Dutch Oven Cooking
Healthy Game & Fish Meals
Wild About Freshwater Fish
Wild About Game Birds
Wild About Seafood
Wild About Venison
Wild About Waterfowl
World's Best Catfish Cookbook

Nature:
The Pocket Disaster
Survival Guide
The Pocket Survival Guide
U.S. Guide to Venomous
Snakes and Their Mimics

Fiction:
The Hunt
Wounded Moon

Nonfiction:
Escape In Iraq:
The Thomas Hamill Story

Foreword

"Gunsmith." Just the word itself brings to mind images of the Hawken Brothers, in St. Louis, hand-building the rifles that would dominate the Great Plains, or the old-school gunsmiths, such as my friend the late *American Rifleman* field editor Russ Carpenter. Russ was one of those guys who could do or fix anything that involved a gun. From the time he made a new extractor from scratch for my well-worn L.C. Smith or the odd hammer spring he made for *Rifleman* editor Pete Dickey's Robin Hood revolver, he personified the old-school gunsmith. (Russ' time on that spring probably exceeded the gun's value by a factor of ten, by the way.) He could be cranky, he could be brusque, but he could also be jovial and share his incredible knowledge and skill gladly—and he always did the job right or he wouldn't do it. I can think of no higher praise for someone who makes their living with guns than another saying, "He's a really good gunsmith."

What about the "new school" of gunsmiths? There are dozens of excellent gunsmithing courses that turn out thousands of qualified gunsmiths every year, yet it seems harder to find a "really good" one. They're out there, and most do great work, but they never seem to be anywhere near me when something happens that I can't fix.

There has also been another evolution in gunsmithing that's on the rise. And that's the home gunsmith. It turns out that working on your own guns is, well, pretty fun. And more and more shooters are giving it a try. Just look at the pages of the Brownells or Midway catalogs and you will instantly realize that even if every professional gunsmith in the country was spending money like a drunken sailor, there's no way they could support such a wide range of items as presented in those catalogs. So, who's buying this stuff? Guys like you and me.

American Rifleman readers reflect the heart and soul of the American shooting and hunting community. It used to be that the average guy getting the *Rifleman* either had a lathe in his basement or a distinguished marksman's badge on the wall. Almost every issue in the 1950s had a story about sporterizing a military rifle or rechambering one to a different caliber. As time has gone by, NRA's role and membership have changed. Now NRA is nearly four million members strong, and while there are still a lot of guys with lathes in their basements, many others don't have them. That doesn't mean they are not interested in working on their own guns, just that the tools or skills of the traditional gunsmith are beyond their reach.

When it came to bringing that home-gunsmithing type of story back to *American Rifleman*, the guy I went to, without hesitation, was field editor Bryce M. Towsley. I've worked with Bryce for more than 10 years and I am pleased to count Bryce as a dear friend, good for a good two-hour conversation on just about any aspect of guns, shooting or hunting. The thing I enjoy most about Bryce, be it in his writing or tales of hunting camps from Alaska to Africa, is his enthusiasm for all aspects of firearms. From bullet performance to bedding a rifle stock, his energy and passion for the subject rings throughout his text. You'd have a hard time finding a guy who enjoys guns—and home gunsmithing—more than Bryce.

In addition, Bryce offers the reader his excellent photography. I can't count the times I've tried to figure out exactly how to do something in my well-worn copy of Walther J. Howe's *Modern Gunsmithing*, thinking that a photo or two might have helped me avoid ruining a piece of metal or wood. Bryce has done a superb job of describing the process—be it fixing an inexpensive injection-molded stock or chambering a bolt-action rifle—in a clear, step-by-step manner backed up with excellent photos that show you how to do it.

That's why I think this book is so important. In one place, you can find a host of projects that you can do yourself. Even if you are not interested in anything more than putting on a new scope, Bryce's insights and helpful tips make me wish he had done this book 15 years ago when I was trying to figure out a lot of this stuff for myself.

Bryce has learned gunsmithing by actually doing it and is not afraid to ask for help. He might try something for himself and realize it's not going well. Then he will go to the right guy for help. He asked Mark Bansner for help on chambering a rifle and, thanks to Mark's instructions, Bryce was able to chamber his rifle without having to recut the threads or start over.

Another thing you can count on with Bryce is that if says he did it, he really did. Whether it's shooting too many groups from the bench with a .458 Winchester Magnum rifle or botching a bedding job, he will tell you not only the truth, but what he learned from it. He might be opinionated about things—and you may not agree with him—but you never have to doubt his sincerity or veracity. Bryce Towsley is a "gun guy" through and through, and that's who this book is written to entertain and inform, other "gun guys."

Mark A. Keefe IV
Editor-in-Chief *American Rifleman*

Contents

Chapter 1
The Gunsmith's Shop *page 10*

Chapter 2
How We Learn *page 34*

Chapter 3
Cleaning & Maintenance *page 80*

Chapter 4
Enhancing Accuracy *page 96*

Chapter 5
"Pimp My Rifle" *page 124*

Chapter 6
An Excuse for a New Rifle *page 136*

Index *page 156*

Introduction

I knew it would be trouble when the music man called a meeting. The guy was from another town, one that was about twenty miles from us, but back then it might as well have been on Mars for all I knew. His meeting was to be held in the tiny cafeteria of our small-town elementary school on a Friday night. The teacher said that attendance was mandatory and I was mad. That was supposed to be my time, not theirs.

It turned out that the school was starting a band. (It was a convenient thing for the "music guy" who would act as music teacher and bandleader because he owned the store where we would all buy our instruments.) At that news, my buddies and I tried to make it to the back door unnoticed, but parents have a sixth sense about that sort of thing and we got ambushed.

When it came my turn to pick an instrument, the music guy was pushing too hard for the clarinet (my guess was he had an overstock), so partly out of stubbornness and partly because I thought playing the clarinet was too sissy, I insisted on the trumpet.

I tried, but I could never understand any of it. I love music, I listen to it constantly and I marvel at the magic it inspires, but how it is created is a vast mystery to me. My wife and daughter, who both have musical talent, talk about "sharp" or "flat" notes or which "key" something is in, but to my ear, it all sounds the same. I enjoy and recognize good music, but when it comes to the specifics, I honestly can't tell the difference. Apparently, in learning to play the trumpet it's important that you can.

It wasn't long before I wanted to quit and nothing could change my mind. I begged, I pleaded, I fought, I screamed, pouted and I even ran away. Then my dad offered me a deal. "Stick with this for a year and I'll give you a .22 rifle."

That's all it took. When it was daylight out and I wasn't corralled into playing that devil's instrument, I was shooting. My uncle Frank was overseas with the military and he had loaned me his .22 rifle. I was doing all I could to wear it out before he got home, but the most important mission in my young life was to get a rifle of my own. Clearly, my dad understood that.

I kept my end of the deal, more or less. I stayed with the band; I played in the concerts, marched in the parades and attended all my lessons. I even endured most of the assigned practice hours and made an honest effort to make it work. At the end of the year, I called the note due. Dad kept his end of the deal, too, and gave me his rifle. I realize now that with a factory worker's income and five kids to raise, it was probably because there was not enough money for a new gun, but that point was lost on me at the time. His rifle was better than any new gun. It was the one I had coveted for years, the one I begged to be allowed to shoot and the one I stared at through the glass doors of his tiny gun cabinet for hours.

I was delirious. Life was good. No, it was great. It was perfect. I had a rifle to call my own and I could finally quit the Sisyphus-like quest of trying to master the impossible. I put down the trumpet, picked up the rifle and never looked back.

The rifle was a Marlin Model 80E, bolt action. It fed from a clip, had a receiver mounted peep sight and it was the best .22 rifle ever made. Even today I'll fight any man who would dispute that claim. My life from that point on was consumed with finding ways to make enough money for ammo and then shooting the ammo I bought. The general store in town sold ammo back then, even to kids. It simply never occurred to anybody that there was any reason not to. I can't remember exactly how much it cost for a box of shells, but I do recall that longs were about a dime less than long rifles so that's what I used when I was paying the tab. My mother would always put a few boxes in my stocking at Christmas and one in my candy basket on Easter and she always sprung for the top-shelf Long Rifle ammo, which I horded to use only for "serious hunting."

My buddies and I were in the woods every afternoon as soon as the misery of school finally ended. On the weekends and during summer vacation we made "expeditions" where we hiked for miles on the back roads and woods trails. We explored old farms and abandoned buildings, sometimes spending the night in them or in the shelters along the Long Trail (part of the Appalachian Trail system). We always carried lots of canned beans and our .22 rifles.

I lived in town and so getting to any woods meant a walk. I simply took my rifle and carried it to where I had to go. Nobody thought much about it, a kid walking down the sidewalk with a rifle was just part of small-town life back then. On the days when I planned to ride the school bus home with one of my buddies who lived in the country, I just brought the gun to school and had a teacher keep it until the bell rang. Then it went on the bus with me. Things have changed a bit since then.

We hunted woodchucks in the summer and squirrels and rabbits in the fall and winter. In the spring we would walk the banks of Otter Creek for miles hunting for muskrats. On the weekends we could sometimes talk my mother into getting up at dawn and driving the truck with Dad's old johnboat in the back to a spot miles upstream. Then we would spend the day floating home and hunting muskrats. We would skin them, stretch their hides, sell them for about a buck apiece and spend the money on more ammo.

When hunting season was closed, we just rambled the woods with our rifles, shooting at just about anything we could find. Pine cones, apples, rocks, old cans, sparrows and to be perfectly honest, far too many chipmunks. While I do regret the chipmunks, it truly was a great way to grow up.

That rifle taught me a lot about shooting, about the awesome power over life inherent to any gun, and about responsibility. It also inspired my hidden gunsmithing talents and probably set me on the path to writing this book. One of the first things I did was to refinish the stock with a complicated and time-consuming process that my grandfather explained to me and which even today I can recite by rote. It was a process better suited to an expensive rifle with fine walnut, not a kid's .22, but to me they were one and the same. It took the rifle out of commission for a couple of months, so I planned the project for when the snow was deep and the only hunting was for rabbits in front of the dogs. I was using Uncle Frank's bolt-action 16-gauge shotgun for that, so I could spare the rifle's downtime. The Marlin has a surprisingly good piece of walnut and I just assumed that it looked so good when I finished because of the process and, of course, my gunsmithing talents. I didn't know about wood quality back then and when my buddies tried the same thing on their cheap single-shot rifles, I ridiculed them for doing it wrong. It never occurred to any of us that the lesser wood on their rifles was the main culprit.

I can also remember a couple of crisis moments. The magazine is made from stamped sheet metal and as I was loading it one day, it flew apart in my hands. There was no fixing it and I was devastated. That Saturday morning my mother drove me the ten miles of narrow country roads to the only "big" sporting goods store for miles. It puzzles me today, but seemed quite sensible at the time that they actually had a magazine in stock to fit this rifle. Mom loaned me the money to buy it and I was back in business.

Some months later I was out squirrel hunting with my buddies when I discovered that the peep sight had broken. Most of it was missing and no amount of searching could turn it up. That night Dad took the rifle and me to my grandfather's and explained the problem. *Gunsmoke* was on the television and Gramp rarely missed an episode in that show's long run and would not tolerate an interruption. So we left the rifle and went home. Late the next day Gramp called and, as was his way on the telephone, said to me, "come get your rifle" and then hung up.

I walked to his house and found the gun standing in the living room corner with a brand-new Lyman receiver sight. I didn't have any money to pay for the sight and I guess he knew that. "I happened to have one in a drawer that was a perfect fit. Just help me with some firewood this winter and we'll call it even," was all he said when I asked how much it cost. But I knew he had probably driven to the sporting goods store that morning and bought the sight.

Today, I make my living writing about guns and hunting and while I live just up the road from the town where I grew up, I have traveled a long way. I have been lucky to live the life I dreamed about back then and looking back it's clear that this rifle was important in what I have become.

That .22 rifle set me out on the path that led to writing this book. It was the start of a life filled with guns, hunting, shooting and adventure. While it was a rocky road to get here, I am now earning my living doing what I love most in life. Not many men can claim that, and I can trace it all back to that Marlin .22 rifle. A lot of guns have come and gone over the years and my collection has expanded quite a bit from that first rifle. I haven't shot the Marlin much in recent times, but I keep it in the vault with the others as a reminder of the past and as a connection to my roots. I don't know what the future will bring, but often late at night when I am in a dark and brooding mood I think that it won't be good for people like me. But there is one solid truth I know. Nobody can ever take that .22 rifle away from me.

This one is for Dad ~ for giving me my first "real" gun.

BROWNELLS MAGNA-TIP
MM STW

ZEISS

The Gunsmith's Shop

Chapter 1

Exterior of the new workshop.

One of my whitetail hunting buddies has something he calls the "Jennifer Lopez Syndrome" that he brings up every time somebody talks about how they want to shoot a Boone and Crockett buck.

"I want to date J-Lo too," he says. "I am a man and she is a woman and we both live on planet Earth. All the elements are in place, so theoretically it could happen. But, it's got about the same chance of success as you do shooting a Boone and Crockett whitetail."

I feel the same way about my gunsmith shop. I would love a 5,000 square-foot shop that's fully equipped with a CNC mill, a big lathe, a surface grinder and all the other latest cutting-edge machinery. It could happen, but like Boone and Crockett whitetails and other fantasies, it's not likely. I am a hobby gunsmith, I spend money at this, not earn income. Justifying a shop like that, I would have to win the lottery or marry a rich movie star. Since I don't buy lottery tickets and I am quite satisfied with the wife I have, I guess I'll make do.

Actually, my new shop is a huge improvement. For many years I had a little corner of my basement to work in. I had one small bench with a path through the clutter to get to it. It was so crowded that some of my power tools were set up in an unheated storage shed out in back of the house. In the winter I had to wade through waist-deep snow to use them with frozen fingers. Other power tools had to take turns on my bench. When I was finished with one, I would remove it to make room for something else. It got pretty frustrating but, looking back, I did a lot of gun work under those conditions, so I guess I can't buy the argument that "I don't have enough room to work on guns." Anybody has who is not homeless has enough room, that's why they call it "kitchen table gunsmithing."

Back in my single days I lived for a few years in a mobile home. (Yes, it's true; I did a stint as "trailer park trash!") The spare bedroom was smaller than most walk-in closets, but I had a reloading and hobby gunsmithing shop set up in there. It wasn't ideal, but I managed to complete a lot of projects. I paid a lot of entry fees to shooting matches with trigger and tuning jobs on handguns, all done in that cramped and campy space with the puke green shag carpet. Compared to that room, my corner in the basement was a step up in the world. And from that perspective, my new shop is a glimpse of heaven.

My point is you can work on guns just about anyplace, just that "some's better than others." Don't let a lack of space keep you from tinkering on your guns, simply get creative. But, keep the florist's phone number on speed dial. You are going to need it if you get bedding compound on your wife's kitchen floor!

Don't bother asking why I know that.

Setting Up Shop

Interior of workshop, note the bank of fluorescent lights.

We all need a place to work and I certainly can't define where yours will be. But, I can speak to setting up a shop like the one I just built, which is just about right for a serious hobby gunsmith. Most people will be working in the basement or garage, which will be similar. But anybody, even the guy working on the kitchen table, can find something in here that will apply to the space they have. You can do as I once did and keep your tools and materials in toolboxes that can be stored off-site and brought out when you have a project going on. That works well for a kitchen table approach and it sure keeps things easy to find. The key is to adapt, improvise and make do.

Obviously, you can't buy everything at once so don't expect a complete shop right out of the gate. You will find that over time you will buy the tools you need for the specific job each time you start a new project and before you know it, you have a pretty well stocked shop.

This section covers the general use tools, the ones that should be in your shop because they are used often and will be needed for a wide range of projects. I think of these as "shop tools" because they belong in every well-equipped shop. Each project may have further specialty tools and they will be identified in those chapters dealing with the jobs they are used for.

My new place is actually a two-car garage that I had built in the back yard. It measures 24 feet by 28 feet and has two stories. The upstairs is shelving and storage for tools, ammunition and reloading components. The downstairs has a cement floor. It is insulated, finished with drywall and heated. It's fast becoming my favorite place and I love the time I spend out there working on guns. But, I have only been working in it for less than year as I write this. For decades I made do with something much smaller and more crowded. This is heaven, that was reality, and I understand them both.

LIGHTING • Ideally, any work area should be well lighted. I buy inexpensive four-foot florescent shop lights and hang them everywhere as supplemental lighting to the banks of incandescent lights on the ceiling. All my benches have these hanging over them, as do all the power tools.

I also keep a flashlight handy for peering into actions and looking for dropped parts.

BENCH • A bench can mean many things. Your wife might call yours "the dinner table," but if so, clearly she is not into gunsmithing. However, it's a good idea to have a bench to work on that doesn't include a centerpiece or place settings. It's a pain in the neck to pick up and move in the middle of glass bedding a stock, just because the in-laws are coming over for dinner, or some other equally frivolous reason.

The workbench should be the right height for working while standing up. For me that is 36 or 37 inches. If you wish to sit, you can use an adjustable stool. If the bench is any higher, a stool doesn't work well. About 25 to 30 inches wide is good. Length is as long as you can comfortably fit, but at least four feet, with eight feet better. I have three benches in the shop and the one I gravitate to most often is 36 inches high, 27 inches wide and eight feet long. It has a shelf underneath and a smooth, painted top.

Any bench should be rugged and heavy. This is particularly true if you are going to have a vise or a barrel vise attached to it. You cannot build a bench too heavy. The heavier it is, the more stable it will be. It should also have a smooth top rather than planking, as small parts have a way of falling through the cracks. If you have a plank top, laminate a piece of one-inch plywood to it. That gives a better top and adds some weight. The best way is to glue it with construction glue and to screw it down every six inches. Send the screws up from the bottom if possible, so they don't show from the top. If that's not possible, put the screws in from the top and countersink the holes. Then fill them with Acraglas Gel. Sand it all smooth after the Acraglas Gel sets.

The last bench I made was for handloading, but the requirements are about the same. I used one-inch plywood and doubled it to create a two-inch-thick top. I coated the pieces with construction glue and used a screw every six inches. When the glue hardened, I squared the edges with a skill saw. I built a simple box frame from 2x6 lumber and used 4x4 timbers for the legs. I added a shelf on the bottom with one-inch plywood. The bench is so heavy that we moved it in two pieces, the frame and the top and then put them together on-site. But, it's a good design for a workbench or a reloading bench. Materials are relatively inexpensive and the construction is easy for anybody with basic tools and skills.

The other alternative is to buy a commercial workbench. I have a couple and they are fine for light work. Neither of mine is rugged enough to mount any kind of a vise on, though.

Finish the bench top with paint or polyurethane so that spilled oil or solvent will wipe up without soaking in and staining the wood.

STORAGE • You need plenty of storage in the form of shelves, drawers and cabinets. Those chests with multiple plastic drawers that are sold at the home supply store are very handy for small parts and tools. You can never have too many of them.

THIS IS A GOOD HEIGHT FOR A WORKBENCH.



1. Materials to build a bench. 2-4. Assembling the bench. 5. Using a skill saw to square the edges after gluing two pieces of plywood together to form the top of the bench.




Shop cabinet

Shop shelving

Parts cabinet

Pegboard is wonderful stuff. Hang it anyplace you have room and it will provide shelving and hangers for all kinds of tools and materials. There are hangers available for just about anything you can imagine.

I recommend at least one tightly sealed storage cabinet to keep things out of the dust and dirt that permeates all through any well-used shop. Also, include a few very strong shelf units for the heavy stuff. What you add depends a great deal on how much room you have and your budget, but I doubt you can ever have too much storage space.

You will also need a good toolbox. It not only will keep your tools protected, but it ensures that they have a place where they belong, which makes it much easier to keep track of them. Some delicate tools like micrometers or reamers should be kept in a closed toolbox and protected from contact with other tools that might damage them.

VISE • Every workbench should have a vise. You can get by with a small clamp-on vise that can be set up and removed on a temporary basis, but the best situation is a medium size, permanently mounted vise. About a four- to six-inch jaw size is good. The vise should be on a heavy and rugged bench so it has a strong foundation. Locate it on a corner so it's not in the way, but is easy to access when you do need it. Reinforce the bench top from underneath when you mount the vise.

Most vises will also have a flat section on the rear that will serve as a light duty anvil. Buy a set of magnetic soft jaws for the vise. These simply snap into place and will prevent marring any parts you are working on. They are inexpensive and incredibly useful. I picked mine up at Home Depot for about $15.00. The old standby is leather jaws. They work well, too, and Brownells still sells them.

Forester Products has a small vise they call the "Swiv-O-Ling Vise." It has a head that will rotate a full 360° and tilt up to 28° from the vertical. This small vise is very handy for working on small parts. Because it swivels in just about every direction, you can put the work exactly where you want it. I find it useful for stoning trigger parts and similar detail work.





Far left: Bench vise with magnetic soft jaws.

Left: Using a Forester Products Swiv-O-Ling Vise to hold a trigger sear for stoning.

BROWNELLS MAGNA-TIP SUPER-SET
BROWNELLS

Brownells Fixed-Blade Gunsmith's Master Set screwdrivers (left to right), Magna-Tip 58 bit Master Super-Set Plus screwdrivers and the 12-In-1 Precision Miniature Screwdriver Set (front).

SCREWDRIVERS • Almost all gun work will require screwdrivers and it is extremely important that the proper screwdriver be used, both in design and fit. Never use a standard screwdriver on a gun. Most screwdrivers sold in hardware, home or auto supply stores have tapered sides. This allows them to fit a wide variety of screw slot sizes and it also adds strength. But they are a horrible choice for working on guns and they should never be used. The reason is that a tapered screwdriver will cam against the taper as you apply pressure and cause the screwdriver to ride up out of the slot, which will cause it to go skidding off and gouging anything in its path. It may be your hand, which will likely heal. Or it could leave an ugly gouge in the gun, which is forever. Either way it is guaranteed to ruin the screw, probably making it difficult to remove without drilling, and certainly unsightly. The pressure exerted by a screwdriver is amazing when it's applied to a very small surface. A tapered blade in a straight-sided slot contacts the screw only at the top of the slot. The forces applied to such a small contact area are enough to move the steel and cause the edges of the slot to round and strip.

A screwdriver must fit exactly in the slot of the screw it is being used on, both in thickness and in the width of the screw. I cannot stress the importance of this enough. The sides of the blade should be either hollow ground or with both sides parallel. A hollow-ground screwdriver will apply pressure to the bottom of the screw slot, rather than at the top as a tapered screwdriver does. This actually helps to "lock" the screwdriver into the screw as opposed to tying to cam it out of the slot like a tapered screwdriver will. A parallel side screwdriver will apply force for the entire depth of the screw slot, which distributes the force over a much larger surface area than a tapered screwdriver. A screwdriver that fits properly will fill the slot and have little slop and the maximum amount of contact surface inside the slot to distribute the forces being applied.

A properly fitting screwdriver will fill the width of the screw slot, which applies more leverage by moving the forces out to the very edges of the screwhead. This is a simple principle of leverage. With all else equal, it's much easier to turn a large wheel than it is a small wheel. There is little point in having a large wheel to allow more leverage

Working on guns will require specialized screwdrivers. There are kits available from a lot of different suppliers. These are from Chapman, Brownells, Midway and Lyman.



Tapered standard screwdriver on right and parallel straight side gunsmith's screwdriver on left.

and then only turning it from the halfway point which is closer to the axis and has less leverage. It turns easier when the force is applied to the outside radius, which is the farthest point from the axis. Think of the screwhead as the wheel that turns the screw. If your screwdriver only fills half the "wheel," you lose leverage. But if it fills the entire slot, it is turning from the full diameter of the "wheel" and is utilizing all the leverage possible.

In days past, gunsmiths spent hours filing the blades on screwdrivers until they fit perfectly. Today we have better options. Simply buy one or more of the many different screwdriver sets available that are designed for gun work. Some are fixed blade, but the most economical are the sets that use detachable bits with a single handle. This also allows you to have bits for Torx head, Phillips head and Allen head screws.

Lyman has one called the Magdriver. It features six hollow-ground bits and one 3⁄32 hex bit that all store in the handle. Extra tips including Phillips and Torx designs are available. A magnetic hex tip allows easy changing of the tips. It's very handy for a range bag as well as on the workbench. They also have several models with more tips that are designed for shop uses.

Pachmayr, which is owned by Lyman, has a set of 10 fixed-blade screwdrivers designed specifically for gunsmiths. Each screwdriver has a rubber coated handle and a magnetized tip that is parallel ground. They are sided to fit Colt, Smith & Wesson, Ruger pistols and revolver screws as well as Torx for all scope rings and bases. A plastic stand is included that will mount on the bench or wall.

Chapman has a kit that includes a screwdriver handle, an extension and a ratchet handle. The #9600 also includes 14 hollow-ground bits, one .050 hex and two Phillips head tips. The #8900 has the same handles, 12 hollow-ground bits, 2 Phillips and 10 hex heads. There are also several extra heads that can be added.

Brownells has a huge variety of choices for screwdrivers, including the Chapman kits. In fixed-blade screwdrivers, the best is likely the Fixed-Blade Gunsmith's Screwdrivers, which can be bought individually or in one of several sets. Their Fixed-Blade Gunsmith's Screwdriver Super Master Set might be the crown jewel of gunsmithing screwdrivers. It's a bit pricey, but worth the money if you are serious about this.

Brownells also offers several interchangeable magnetic tip screwdriver kits over a wide price range. Mine is the top of the line 58 bit Master Super Set. It includes two handles, one long and one short, 44 assorted hollow-ground tips, 10 Allen head tips, three Phillips head tips and a 1⁄8-inch square tip for some Remington butt plates. I added the four-piece Torx head bits as an extra. This is certainly one of the most complete kits available anywhere and at a cost far less than it would be for this many individual screwdrivers. It has been on my workbench for many years now and I don't recall a single problem or the need to replace any of the tips. That's a strong statement because these screwdrivers walk a fine line. If they are heat treated too much, they become brittle and will break, but too little heat treat and they will twist under pressure. At least on my set, Brownells got it exactly right. My only complaint is there are no Torx head tips included. But they can be added for just a few dollars more.

Midway USA sells the Wheeler Engineering Deluxe Screwdriver Set. This is a newer product and I have been using one for a few months now. It seems to be a very complete screwdriver kit. Wheeler's engineers measured the screws on over 100 modern and antique firearms to make sure that they offered bits for every situation. There are 54 hollow-ground flat bits that range in size from .120" x .020" to .360" x .070". That includes doubles in the thinnest sizes, because even the best will break now and then when they are this small.

The set also includes a complete selection of Phillips, Allen and Torx bits. There are 17 "specialty bits" that are included in the "professional" set. The set comes with two handles. The first is a regular size handle that's good for most jobs, and the second is a slimmer, shorter "Close Quarters" handle that is good for finesse work with smaller bits. It's all in a plastic case.

B-Square has a kit with 26 hardened steel bits in Phillips, Slotted, Hex, Torx, and Posi-Drive. There are no doubt many more screwdriver kits on the market, but these are what I have used and like.

You will also need a set of small "jeweler's" screwdrivers for some of the more delicate work you will encounter.

Brownells Fixed-Blade Gunsmith's Master Set screwdrivers.

Again, I turned to Brownells for their 12-IN-1 Precision Miniature Screwdriver set. Finally, you will need a selection of "hardware" type screwdrivers. A long, thin, shank #2 Phillips head screwdriver is handy for removing recoil pads. Pick one that has a round shank and is polished and chrome plated. You want to be as smooth as possible to reduce the possibility of tearing the rubber in the pad. Also you will need a long (about 12 inches) and fairly large flat blade screwdriver to reach into the butt of shotguns and some rifles to remove the screw that holds the buttstock on. There are specialty screwdrivers on the market for this, but a high quality hardware store type will work fine for most guns.

Another screwdriver that I have found useful is a big wide tip that I filed a notch in for removing over-tightened nuts on Weaver Tip Off scope mount rings. The screw often extends out past the bottom of the slot and prevents the screwdriver from seating fully. The slot allows the screw to extend into the screwdriver so it can seat in the bottom of the slot. The big handle provides plenty of power to remove the nut, no matter how tight it was put it on.

FILES • Every gunsmith is going to need a selection of files and the ability to use them. The first you can buy, the second you must earn. The European gunmakers are said to test their students by asking them to make a perfect one-inch cube of steel with nothing more than a file. "Simple enough," I figured when I first read about it years ago. Then I tried it. After several attempts I concluded that success is elusive (at least for me) and secondary to teaching an aspiring gunsmith about using a file. It sounds easy in concept, but keeping all the sides even, parallel and square on this cube makes mastering Rubik's Cube look like kindergarten work. However, during any attempts you will learn a lot about how to use a file. Which may well be the point of it all.

Files have teeth that extend as continuous rows across the face at an angle. Files with rows of teeth going in one direction are called mill files. Files with rows going in both directions are called double-cut or flat files. Mill files generally provide smoother finishes than double-cut files and are more useful for gun work. The closer the rows are to each other, the finer the cut of the file in use. Coarse files are called bastard files. Medium files are called second-cut files. Fine files are called smooth files. Good files are expensive, so you will build your collection over time. For starting out, you will probably want at least one eight-inch mill file in smooth cut and another perhaps slightly larger, 10-inch in second-cut. A few more basic files you probably need include a round

BROWNELLS STARTER FILE SET

Not sure how to get started? Once again, Brownells to the rescue. They offer what they call a "Starter File Set," which includes the following:

1. **Needle File Set (fine)**
2. **3 Square Bent 60° File**
3. **60° Sight Base File**
4. **4" Barrette File (#1 cut)**
5. **8" Half-Round File (smooth cut)**
6. **8" Mill File (smooth cut)**
7. **8" Hand File (smooth cut)**
8. **6" Pillar File (#2 cut)**
9. **8" Extra Narrow Pillar File (#2 cut)**
10. **4" Very Extra Narrow Pillar File (#2 cut)**
11. **Six-pack File Chalk**
12. **Double Face File Card**
13. **3 Needle File Handles**
14. **2 Adjustable File Handles**



Draw file shown with a single cut mill file.



Mill or single cut (left) and double cut or flat file.

Surform tools



Chalking a file.



Using a file card.

and a half-round in eight-inch smooth. Also a triangle file, six- or eight-inch. For working on dovetails, the best file is a 60° Standard Slot file designed for this work. This file has parallel sides rather than tapered, but with only one side with cutting teeth. The other two sides are "safe," which means they do not have teeth. The file can be used to widen dovetail slots in gun barrels without danger of inadvertently deepening the slot or damaging the edge not being worked on, because only one side cuts. As a parallel file, you have absolute control over the angle of the dovetail, which is all but impossible with tapered triangle files. This file should be in every gunsmith's shop.

If you are doing much stock work, you will add a few wood rasps, which are closely related to files. The teeth are different and they are definitely not interchangeable with files. Get one in each shape: flat, round and half-round. Also consider a couple of Stanley Surform tools, which are sort of files. These are fast cutting wood rasps with replaceable blades. They are inexpensive and are handy for stock work where you need to remove material in a hurry.

You will also need a set of small "needle" files which are used in tight or small locations and for delicate work. Guns are full of tight and small locations, so they will see a lot of use. As you progress with your gun work, you will discover that you need many more size, shape and cuts of files, but these will get you started.

Always use an appropriate file handle whenever you use any size or shape file. File handles lessen hand and arm fatigue and give you more control of the file for more consistent, even cutting strokes which will improve the look, accuracy and final result of your work. File handles help you hold the file more securely and protect your hand from accidental injury caused by sharp, exposed file tangs. The tapered end of a file is made to fit in a handle, but it serves very well as a spear. All it takes is one slip and you have the file impaled in your hand. While a file handle makes the file easier to control and reduces hand fatigue, its most important function might be that it also keeps you from bleeding all over the guns.

To use a file, hold the handle in one hand and grasp the front of the file with the other hand. This allows more control over the pressure, direction and the angle of the cut. Check after every couple of strokes to make sure you are cutting what you want to cut and where you want to cut it.

When you get a new file, clean it with a solvent degreaser to remove any traces of preservative oil applied by the manufacturer. If oil or grease is left on the file, it will cause metal chips removed during filing to stick or lodge between the file teeth (this is known as "pinning"). Pinning inhibits the cutting effectiveness of the file and the pieces can score or scratch the surface of whatever you are working on.

After degreasing the file, rub file chalk into the teeth. The chalk collects between the teeth and helps prevent metal chips from sticking and building up on the file. To apply file chalk, simply rake the chalk back and forth along the face of the file. One or two strokes will apply sufficient chalk.

Never pull a file backward across the work piece, unless you want a useless and dull file. Push forward to cut, then lift the file clear of the work piece on the return stroke. Files cut on the forward stroke only. Maintaining pressure and pulling the files backward will roll the sharp edges of the file teeth and dull the file. Also be careful about what you use a file on; filing hardened or plated metal will also quickly dull your files.

A file card is a double-sided brush with fine nylon bristles on one side and bent steel bristles on the other. (Some also have short, stiff steel bristles on one side only.) This is a tool that is specially made to clean filing residue from between the file teeth. Use the file card frequently while working to keep the file teeth clean and clear of chips. Keeping the file teeth clean will enhance the cutting efficiency and smoothness of the cut. Thoroughly clean your files with the file card after every use and re-chalk after every cleaning and before putting them away.

Files should be stored so they never contact or touch one another. Files are very hard and very brittle. Contact between files can lead to chipped, broken or damaged teeth. Do not dump files together in a toolbox or drawer as that can dull or damage them. (I will plead guilty to this and speak from experience.) Wrap them in a shop rag to protect them and always protect a file from rusting. It's a good idea to make individual "sheaths" of cardboard for your files if they are to be stored in a toolbox. Given proper care, files will last for many years and provide excellent service. I have some that I have owned since the 1970s and they are still working fine. I have a few others that my wife's grandfather gave me that I suspect are older than I am. He was a tool and die maker so they saw a lot of use before I got them. They are worn and showing their age, but still working. Kind of like me.

A good rule of thumb to follow anytime you are cutting or filing anything on a gun is to remember that you can always remove material from any part. But, replacing material after you screw up and remove something you did not intend to remove is extremely difficult and often impossible. Always pay attention, work slowly and look more than you file. Check your work from several angles. Often you think you are doing a great job when viewing the work from one angle as you file away, but when you see it from another viewpoint it becomes obvious that the file is cutting more in one location than another. That's one of the biggest challenges in making a cube with a file. The tendency is to file in something other than a square, flat plane. Pressure and stroke change as you move the file and a file has no conscience; it simply cuts what it is directed to cut.

STONES • Any gunsmith has got to have "stones." Not in the wise guy sense, although that helps the first time you start any new project, but abrasive stones. Much of gunsmithing is detail work and the stones are used for polishing and shaping metal parts. For that, you need a selection of different sizes, shapes and grits. There are several different types of stones that you can use. The first are natural stones. Most are silicon quartz which are mined in Arkansas and are usually called an Arkansas stone. One good feature of these is they tend to polish as they sharpen and for edged tools they remove less metal than man-made stones when sharpening.

These stones are mined from the earth and processed. There are several grades, but no true industrywide set standard. Norton may well be the largest supplier of abrasive stones and they use their own grading system for natural stones. They are as follows. Norton Soft Arkansas; this is an extra fine stone, but is still the coarsest grained of the Arkansas stones. Next is the Norton Hard



Above: Spyderco ceramic bench stone and ceramic file set.

NORTON SHARPENING STONES
HARD ARKANSAS MADE IN USA

Right: Stones from Norton and Brownells. The white stones are natural Arkansas stone or man-made ceramic; the darker stones are man-made India stones.

Air compressor

Arkansas. They rate this as "superfine" but state that it's less dense than a hard Arkansas stone. Finally, they have a Norton Hard Translucent Arkansas. This stone is rated Ultrafine and is used for the finest finish and would be a good choice for trigger work and the like where polishing critical areas is the task.

Next are man-made stones. Norton calls their aluminum oxide stones "India stone." They have very hard and smooth cutting edges for close tolerance and are the best choice for most gun work other than polishing. They are usually orange in color and are offered in coarse, medium or fine and a wide variety of shapes and sizes.

Silicon carbide stones are also man made and they are a fast cutting stone, but do not give as nice a finish as the aluminum oxide stones. Silicon carbide stones are fine for removing material or sharpening tools, but not for polishing parts. Usually they are used in a bench stone. Again, they are offered in coarse, medium and fine.

Finally, there are ceramic stones. These are also man made and are less expensive than natural stones. They can produce a very fine finish and are very precise. They resist wear and retain their precise angles and shape well. Ceramic stones do not require oil during use as the other man-made and natural stones do and can be used dry or with water. This makes cleanup easier. When they glaze over, they can be cleaned with scrubbing powder and water.

Water stones are man-made stones used primarily for sharpening woodworking tools. They are named this because they use water rather than oil and so reduce the risk of staining a fine wood stock with oil transferred from a stone by the tools. They are soft and wear out fast. They often require "dressing" to keep them flat. If you are working with fine walnut stocks, a water stone that is dedicated to sharpening your carving tools is a very good idea.

Stones are like a lot of other tools in that you will find that they accumulate over the years. But to start with, you will need a good bench stone, preferably a double-sided one that has fine grit on one side and medium on the other. These are available from any hardware store. You will also need a selection of small Arkansas, ceramic and India stones in several grits and shapes. These are sometimes called stone files and are used in a lot of work in guns. Brownells has several kits to choose from and Norton has an excellent stone file kit that includes both natural and man-made stones.

Spyderco has a wide selection of ceramic stones including bench stones in three grits. They also have ceramic stone files, including a kit that has four stones, round, square, triangular and slip. They are housed in a leather pouch and are excellent for gun work.

AIR COMPRESSOR • It won't be long before you realize that you need an air compressor. It's used to blow dirt or solvent out of parts and mechanisms, to run power tools, for sandblasting, cleanup of dust and dirt and for spraying coatings. You will use it for a thousand other things as well, everything from blowing up your kid's bicycle tires to cleaning the dust out of your air conditioner when you get it out of winter storage.

I remember the air compressor my grandfather had in his garage when I was growing up. It was huge, noisy, nasty, dirty and a little scary. It was a complicated-looking contraption with lots of giant gears, spinning wheels and flopping belts. The beast filled a small room and probably cost as much as a car when it was new, which was well before my father was born. Today you can buy one that does everything that one did, but with less noise and commotion for about $300. (Although, they are still noisy!) One man can easily wheel it around and even load it in a pickup truck. I bought mine as a closeout on a floor model and got it for less than $200.

Make sure that the tank has enough volume for spraying and sandblasting applications, 25 to 30 gallons is good, 15 gallons might be adequate. Make sure it has at least 150 psi. Add a line filter to make sure the air is clean and free of water.

BELT AND DISK SANDER • It might be a toss-up between this and the drill press being the most valuable power tool in your shop. My sander has an eight-inch disk and a two-inch vertical belt. It will sand, shape, grind and sharpen. It will work metal as well as wood. I use it for everything from reshaping triggers to installing recoil pads. I recommend that you make this one of your first power tool purchases.

DRILL PRESS • I worked for years with just a hand-held drill. Then one year, my wife bought me a drill press for Father's Day and I couldn't understand how I ever survived without one. I use it for drilling, polishing, shaping and light milling (with a special vise). I have even used it as a makeshift arbor press to reassemble a double barrel shotgun.

In that circumstance, I needed a way to compress the hammer and its extremely stiff spring so that I could insert the hammer pivot pin. I needed to do this because I was dumb enough to dry-fire my old and much loved Lefever double barrel shotgun after cleaning it. When the right barrel snapped I heard the firing pin break, sending a fragment rattling out the bore. Just finding a new firing pin for that old shotgun was quite a challenge, but that was only the warmup for what was ahead.

Drill press

Bench-mounted belt and disk sander

This was one of those projects where I thought I knew what I was doing when I decided to take everything apart. But when I pushed the hammer pivot pin out and parts and pieces went flying across the bench and scattered around the room, I knew I was in trouble. I tried to put it all back together, but Superman could not have compressed that spring by hand.

To do this required that the hammer be in place while you pressed on the hammer to compress the spring. The part of the hammer that was available for pushing was a radius and it was hard to find a place to press that was in alignment with the spring. The spring had to be compressed a long distance, and as the spring compressed and the hammer moved, it shifted the angle. Because of the radius, that would cause the relationship of the contact with whatever was pushing and the centerline of the spring to change. The force would suddenly be off center and something would slip and let loose. Parts would suddenly fly off to hide in my cluttered shop.

After about fifty tries, I knew I was in trouble. After about a hundred, I had skinned knuckles, a bad attitude and a wild look in my eyes. I also punched in the guts and panicked, "what the hell have I done now" feeling that every hobby gunsmith is going to experience every now and then. (A hint: When it happens, stop and go do something else for a while to calm down. You can probably fix it, but panic is not the route to an acceptable outcome. It will wait, so give it a day. Go fishing, wash the dishes for your wife or do anything except try to fix your blunder. Drinking works for me.)

Nathan Towsley uses a cordless electric drill to install shelf brackets over the workbench.

When I decided to tackle it again a few days later, I called everybody I knew to ask what to do. After I explained the problem, most laughed hysterically and responded by saying, "What the hell did you do that for?" Nobody knew how to put the damn thing back together.

But one of the Brownells' "Gunsmithing Kinks" books (there are five volumes of the "Kinks" books and each is filled with lots of tips for the gunsmith) had a little blurb about using your drill press as an arbor press by raising the table against the part. That got me to thinking. I clamped the shotgun's action in a vise and clamped the vise to the drill press table. Then I ground the short leg of a large Allen wrench to fit the contour of the hammer. I clamped the long end of the wrench in the drill chuck. I lined it all up so that the Allen wrench was pushing on the hammer and then I raised the drill press table with the crank to compress the spring. It took a couple of tries to get the angle just right, but after that it worked perfectly. Ten minutes later I had my shotgun back together.

Of course, I got stupid and got to thinking whether there was a left and right to the hammers and if I had them in correctly. So, I took the shotgun apart again. Turns out that I had it right the first time. It also turns out that my idea about the drill press actually working was not a fluke and the gun went back together again with no major problems. Take my drill press away from me? Only when you pry it from my cold, dead hands!

HAND-HELD CORDLESS DRILL • These are not a replacement for a drill press, but rather a supplement to one. Actually, they are an entirely different tool and while there is some overlap, they serve a different function. I would like to see you building shelves in your shop using sheet rock screws and installing them with a drill press!

The new hand-held, rechargeable, cordless drills have all but replaced the old electric drills of the past. These variable speed, adjustable torque drills are not just for making holes. They also will turn screws, grind or polish parts and even mix you a drink if you are so inclined. Every shop should have one. Get the 18-volt model rather than the cheaper 12-volt. It will be more powerful and the battery will last longer. A spare battery is a very good idea. That way, one can be charging while you are using the other one.

DRILL BITS • A drill index with a complete set of drills should reside by your drill press. You will also need specialty drills as you move into some more advanced

STORAGE
STORAGE

Drill set for metal and wood

Wood drilling spade bits



Author Bryce Towsley, in his shop (shown at right) cutting a stock off using a table saw.

projects, but an index that includes 1⁄16 inch through at least ⅜ inch is almost mandatory. Better yet is to go up to ½ inch. Try to get good quality as opposed to the cheap, discount drills. You might also add a selection of wood drilling spade bits.

TABLE SAW • I once picked up a gun in a trade that had a really odd-looking recoil pad installation. The guy had used a Skill saw to cut the buttstock off and a pocketknife to whittle the recoil pad to fit. Not only did it look like a beaver had chewed the pad down more or less flush with the stock, but every angle was wrong on the recoil pad. It listed to the right and the top was cocked back at the gun with the toe pointing at the shooter. I didn't even bother trying to shoot it; I just traded off to another guy who said he didn't care.

The best way to cut off a buttstock for a new recoil pad installation or to shorten the length of pull is with a table saw. You will need a 40 tooth combination crosscut and ripping, general purpose blade for most of the work. But for cutting off stocks and other fine work, get a high quality 80 tooth carbide, trim and finish saw blade. They are expensive, but worth the money. They will make a clean cut with no chipping on the off edge. Don't use the blade for anything else except stock work and protect it like it was your first-born child. Never drop a carbide tooth (or any other) saw blade on a shop floor. It will break the teeth and ruin the blade. Don't use this blade for cutting anything except wood. If it hits a nail or anything else, it can ruin it.

With the appropriate blade, a table saw is also useful for other gunsmithing-related jobs dealing with wood or plastic. For example, I recently used mine to make wooden jaws for my vise to hold a rifle action.

You will also use a table saw for making shelf units in your shop, making gun racks for the shop and maybe to remodel the bathroom. Perhaps you can live without a table saw, but it will be like living without good food. You can get by, but life is not as enjoyable. Every shop should have a table saw. You will be amazed at how often you will use it.

EYE AND EAR PROTECTION • You can't hunt, shoot, work on guns or look at your wife and kids if you are blind. Every time you shoot a gun, run a power tool or use a solvent or chemical, you should be wearing safety glasses. Just a few days ago I was putting a 1911 pistol back together and something slipped. The recoil spring came free and bounced off my safety glasses, knocking them off my face and scratching the lenses. In the past forty years, that makes about a hundred times that glasses have saved my eyes. Broken end mills, shattered grinding wheels, carbide tips flying off saw blades, flying gun parts, they have all happened to me. I have also had a strip of primers blow up in my face and had a high-voltage power line short out and break my safety glasses with flying debris. (That one happened while I was standing on "hooks" 30 feet up a telephone pole.) It was actually one of those climbing hooks that caused the short, and the result was that the spike was burned off my climber. That was back in another life when I was a lineman for the telephone company. It was actually the first "real world" pole I climbed after completing climbing school. Not having the spike presented a big problem as there was no way to climb back down.

Safety gogles, face shield and ear protection.

I wasn't sure I wanted to anyway as the short caused an entire shopping center to lose power and there were a lot of angry people on the ground. One of my co-workers finally came up with a bucket truck and extracted me from my "position" on the pole. In the next decade I climbed a few thousand more telephone poles, but I never forgot to look where I was stabbing my hooks again. I lost the broken safety glasses, but I still have the climbing hook as a souvenir.

I have seen a lot of guys who think they can get away with "just a few minutes" without eye protection because they don't want to take the time to find it and put it on. They stand off to the side of a grinding wheel as they work and assume nothing will fly in their direction. They run the drill press without eye protection because it will only take a minute and they can't find the goggles. They squint as they run the power saw, to keep the sawdust out of their eyes. Most of the time they get away with it. But, I know at least three men who have lost their eyes in accidents where safety eye protection would have saved their vision. Not one of them feels the minutes they saved by not locating some eye protection was worth the price they paid. All three told me that it hurt like hell, too.

Every power tool should have goggles hanging by it, where they are convenient and easy to use. Every bench should have goggles or safety glasses on or near it. The power tools with a greater potential for problems, like grinders, saws, lathes or milling machines, should be run only while wearing a safety shield or goggles. If you sandblast, wear eye protection. If you are spraying coatings, wear eye protection. If you are working on spring-loaded mechanisms, wear eye protection. If you are running any power tool, wear eye protection. If you are working with dangerous chemicals, wear eye protection. When in doubt, wear eye protection.

Goggles can fit over eyeglasses. They are inexpensive and I keep several in my shop. A face shield will fit over glasses and help to protect your entire face; I have one adjusted to fit my head hanging near most of my power tools. I need reading glasses, so I bought a pair of bifocal safety glasses with side shields. The top part is clear, but the bottom is a 2.5X magnification. They allow me to be protected at all times and still see, no matter if I am working close or farther away. I wear these most of the time in the shop.

You should also have a pair of muff type hearing protectors in the shop. The rule here is simple: anything you are doing that is loud, put them on. That includes running most power tools. Hearing loss is cumulative and while you may not think you are damaging your hearing, you likely are losing a little bit every time you expose your ears to loud noises. The damage accumulates over the years until one day you can't understand conversations or what the actors are saying at the movies. Usually, I can ask my wife what the actor said about five or six times before she throws her popcorn at me and says, "He said to shut the hell up and watch the movie!" I don't mind her outburst and don't blame her, but popcorn is too expensive to waste.



A variety of punches

It goes without saying that every time you test fire a gun you should have on both eye and ear protection.

PUNCHES • A gunsmith needs to know how to take a punch. Take it and fix a gun, of course! You will need an assortment of punches, both steel and brass. Brownells, Midway and others have kits that include most of the popular sizes. Start off with a kit for each steel and brass. You may need to add more specialty punches as you go along.

You will need a center punch for marking locations for drilling. I have both a conventional one that is struck with a hammer and a spring-loaded Starret model that is activated by pushing down on it. This spring-loaded punch is extremely handy because it will mark exactly where you want it to. Sometimes a conventional center punch will wander before you hit it with the hammer. It's not the fault of the punch, but more a case of ADD with the operator, but nevertheless it happens too often.

Punches are used to knock out pins and parts. They can also serve as a drift to help align parts when replacing the pins in guns. Drift punches have a long tip section with parallel sides. They are used for removing pins and should closely fit the diameter of the pin, but must not be larger, as they will not fit through the hole if they are. Drift punches should not be used for heavy work such as freeing a stuck pin, as they can bend easily. Once bent, you can never get them straight again. Tapered punches are just that, tapered. They are stronger and should be used to start stubborn pins. Select one that has a tip size close to the pin diameter. You won't be able to move the pin very far because the tapered punch will grow too large for the hole before it enters very far. But once the pin is broken free and started, it should move much easier. After the pin is started, switch to a drift punch to complete the removal. Keep your damaged punches, as you will need specialty punches from time to time and you can often make them from broken or bent punches. Chuck them in a drill press and use a file to reshape them to fit the job at hand.

A punch with a long, tapered, sharp point is handy for sometimes removing broken screws. If the screw is large enough, you can use the punch along the outside edge to bite in and turn the screw. Place the punch near the outside edge, angled so when it's tapped with a hammer it will bite into the metal and turn the screw counter-clockwise. This is an old mechanic's trick that sometimes will work on gun screws. It's always worth a try.

HAMMERS • There are very few problems that can't be solved with a bigger hammer. Just remember that the outcome will not always be what you wanted.

Your shop will need several hammers. A small hammer with replaceable tips is probably the most useful. With a plastic tip on one side and brass tip on the other, this will be the hammer that sees the most use on your bench.

You will need a small and a medium ball-peen hammer and a big bludgeon type hammer. But, use that one only as a very last resort. Let it serve more as a reminder that brains over brawn is the best way to have a good outcome to a sticky problem. But when brains fail, get the bigger hammer. A good quality large rubber hammer will also be useful at times, as will a larger plastic-faced hammer.

Grinder with wire wheel

GRINDER • A bench-mounted grinder is another "must-have" power tool. Buy the biggest and best you can afford, but nothing less than six inches. You will probably use this tool just about every time you work on a gun. A grinder will reshape parts, sharpen and modify tools, shorten springs and screws and even trim your fingernails. Although the last is usually accidental and is definitely not recommended.

An assortment of hammers

Make sure you have a dressing tool to keep the wheel surface square. Most bench grinders will have two wheels, one on each side. In addition to the grinding wheel, you should also have a wire wheel which is used for cleaning rust or dirt off parts. Also have a cloth polishing wheel with a selection of polishing compounds. This will be used to polish parts for better operation or for finishing.

HAND GRINDER (DREMEL TOOL) • You will need a small hand-held grinder tool. Dremel is the most common brand and the name is often used generically to describe this tool. The grinder will accept a huge selection of grinding, cutting and polishing attachments. This little dynamo is one of the most-used hand tools you will have on the bench. It can shape stocks, modify parts, cut slots in screws, make parts, polish internal parts, cut off small metal pieces such as screws, and the list goes on and on. I have three of them. One industrial size and one Dremel brand date back to the 1970s, so they obviously hold up well. I also have a newer variable speed Dremel that's about five years old and still going strong. I will say that the variable speed is the way to go. I have not tried the cordless models, but I think one might be on the list of "new tools I need."

Plan on getting a good selection of bits and accessories. Brownells has a kit with all the most popular grinding stones. They also have another kit with felt polishing tools that work with polishing compound. Other polishing tools are made from rubber impregnated with abrasive; they are extremely useful for polishing. Dremel makes a few of these and Brownells has a kit by Cratex that has several shapes and abrasive grits. You will also need some cutting wheels for cutting off screws, making slots in screws and that sort of thing. Metal cutting heads, either tool steel or tungsten, are used to shape inletting in stocks and remove material when needed. There are wire wheels for cleaning and tools for sanding, routing, engraving, carving and just about everything you want to do. There are even tiny little saw blades for cutting off small pieces.

USING A CUTTING WHEEL ON A HAND GRINDER



1. Dremel hand grinder with assorted Cratex polishing tools from Brownells. 2. Polishing and grinding tip kits from Brownells for use with Dremel type hand grinders.

2
BROWNELLS
FELT BOB POLISHING KIT
BROWNELLS
"PREMIUM PLUS" GRINDING POINT KIT
BROWNELLS, Inc.

GUN VISE • Every gunsmith needs a gun vise to hold long guns as they are being worked on or cleaned. The old style wooden Decker model was always a great choice, but, wood requires that it be finished or it will stain from solvent, oil or grease spills. Sinclair International now owns Decker and they have updated the Decker Gun Vise. It now features a heavy, machined polyethylene base with parts trays. This base is resistant to solvents and cleans easily. It adds a great deal of weight to the vise to make an extremely solid base. Rubber feet are screwed into the base to give a firm grip to the work surface. The forend rest is solid oak with padded leather upholstery.

The vise frame is powder-coated steel with leather padded vise jaws to ensure that the gunstock finish is protected and has solid oak trim surrounding the steel vise frame. This is a very classy gun vise. At 12.3 pounds, it stays put on the bench. There is also a version that is scaled down for use on handguns.

There are several plastic gun vises on the market of similar design, but less expensive than the fine wood vises. They work very well and are easier to keep clean.

The new Tipton's Best Gun Vise offers an interesting new approach. The vise was designed to accommodate a wide range of firearms for cleaning, maintenance or gunsmithing. It can be configured to handle bolt-action rifles, break-open shotguns, AR-15s, and handguns. A central aluminum channel lets the user move individual components to the ideal position for their firearm. Each component then adjusts to position for secure support. The rear base features two adjustable offset clamps for a tight grip on a wide range of buttstock configurations.

PARTS CLEANING TANK • A parts cleaning tank filled with solvent and with a filtering system is very useful for cleaning old gunk-filled actions and for removing the packing grease on new actions. In fact, it is useful for any kind of degreasing or cleaning job. Mine is 30 inches wide and holds up to 20 gallons of solvent. There is a filter and a pump that will spray the solvent from a nozzle to keep it circulating. I bought it at an auto parts store.



Note the oak and leather features of the gun vise.

Decker Gun Vise

Decker handgun vise

BENCH PADS • These are basically place mats for your bench. They protect the bench and the guns. They are padded, non-marring and help keep little parts from rolling off the bench. Every bench needs one.

WRENCHES & SOCKET • A ⅜-inch or a ¼-inch drive socket set like those sold for mechanics will come in handy now and then and is a good thing to have anyway. The same with a set of open-end and box-end wrenches. Every complete shop should have a basic set of each. It's not just for gun parts that they fit, but you will use these to adjust a lot of tools.

DENTAL PICKS • Dental picks aren't just for cleaning teeth anymore. They are very handy for the endless reasons you need to get into the nooks and crannies of guns. They can dig out the crud, push a cleaning patch into mysterious places and dig out stuck things. These inexpensive tools are very handy and you should have a couple on every bench. I bought mine at the local hardware store.

WOOD CARVING CHISELS • Even if the extent of your stock work is glass bedding and fitting parts that can't be seen from the outside, you will need a set of hand chisels. They are so much handier and do a much better job than a pocketknife. Obviously, if you get into stock work on an advanced level, you will need to add to that list. Hand chisels or carving tools are extremely handy and are another "must have." Brownells offers a set of six basic designs that will handle 90 percent of the jobs that you might encounter.

Socket sets and wrenches

Nathan Towsley at a parts cleaning tank. Note use of Brownells' long apron to keep clothes clean.

Dental picks are very handy for cleaning guns.

4000 GRIT
8000 GRIT
BUCK BROS

Inset: Using a Norton India slip stone to sharpen a hand chisel.

A set of wood carving hand chisels. Shown with a Norton India slip stone, and a larger Norton water stone.

HACKSAW • From cutting off screws to cutting off barrels, the cheapest, easiest and safest way to cut metal is a hacksaw. Make sure you have a good one on hand with a good supply of blades of various tooth counts. Avoid the cheap hacksaws, as the frames are not ridged enough and they can flex allowing the blade to bend, break or come off the frame. This can cause a serious injury to your hands and can damage the gun. Spend a few bucks more and get a good hacksaw.

MEASURING TOOLS • Every gunsmith will need a dial caliper and a one-inch micrometer. You will also need a tape measure and a six-inch metal ruler.

The dial caliper will see a lot of use for most of your measuring. Don't skimp and buy a plastic model, get a high quality metal one. Digital models are more expensive and the batteries always seem to be dead when I need it most. The dial version works just as well and is not that much harder to read. Compared to the old vernier calipers, which required an advanced degree and a double helix nerd gene to understand, both the dial and the digital models are worlds ahead.

Micrometers are more precise than a caliper and are used when exact size matters a great deal. Traditional micrometers can be a bit tricky to use and read, but the newer digital micrometers, along with the ratcheting handles, have made them just about "dummy proof."

SCREW PITCH GAUGE • These are used to tell you the thread pitch of a screw. If you know the diameter (use your micrometer or dial caliper) and the pitch, you know what the screw is. Get one for U.S. (English) style threads and one for metric threads.

The English system is inch based and the threads are



Measuring tools, micrometers, calipers and steel rulers.

specified by how many peaks there are in one inch of the length. They are specified as "threads per inch" written "TPI." The higher the number, the finer the thread. The diameter of the screw is measured and specified in thousandths of an inch. The diameter of a screw is the outer diameter of the thread, which is approximately equal to the diameter of the shaft before a thread was cut in it.

The size for U.S. screws is specified as a number for the smaller screws used often in gun work, or in a fraction of an inch for larger screws. Screws are described as 4-40, 6-48, 8-32, 10-32, 10-24, etc. (for numeric sizes, odd numbers are rare), or ¼"-20, ¼"-28, etc. The first number is the shaft diameter (numeric or inches) and the second number is the threads per inch.

A metric screw thread is specified by how far, in millimeters, the thread advances the part in one turn of the screw. For example, if one turn of a screw moves it one millimeter, the thread is called M1.0. This measurement is also the distance from one peak of the thread to the next one. The diameter of a metric screw is usually specified in millimeters (mm) prefixed by the capital letter M, as in "M5" for a 5 mm diameter screw.

TAP & DIE • You will need at least one tap and die set, and probably two. One in U.S. or "English" threads and one for metric threads. Of the two, the U.S. is much more important and you will find that you can get by with only that one for most gun work. But some imported guns use metric screws and once in a while you will run into one. The trouble is while screw pitch gauges are inexpensive and are needed in both standards to identify unknown screws, tap and die sets cost a lot of money. It might be best to buy a U.S. set, which will do 99 percent of the work. Then get the individual metric taps or dies as the work comes up.



Screw thread pitch gauge

Tap and dies

Plan on using 6-48 taps a lot, as that's the most popular screw size you will encounter in gun work. Taps are brittle and they break, so get a few extra in that size. Also, you will need tapered taps, plug taps and bottoming taps in the popular sizes. (Don't panic, they are not all that expensive.) The tapered tap will start easily. The plug tap will do most of the jobs, but cannot thread a blind hole to the bottom. A bottom tap has threads to the end and will cut to the bottom of the hole.

You will need a good T-handle tap handle as well as a tap wrench for the bigger jobs. You will also need a handle for the dies. You'll find that most kits include all of these handles.

Taps and dies are used to cut threads. As your gunsmithing skills expand, you will find that you are using them more and more for that purpose. For example, installing sights and scope bases, making screws, etc. But, you will also find that you will use them a lot to fix damaged threads. This is called "chasing" a thread; you will do a lot of that in gun work.

BENCH BLOCKS • Bench blocks are plastic or nylon blocks featuring various grooves and holes. They are used to support various parts during certain operations. For example, if you are driving a pin out, you can position the part on the bench block with a hole under the pin. Then you will be able to drive the pin out of the part and into the hole while the part is fully supported. Bench blocks are inexpensive and will come in very handy.

SHOP MATERIALS • There are some basic materials that you will need in your shop. Here are but a few suggestions.

SCREW KITS • Several companies offer kits that have a collection of the most commonly used gun screws. It's a good idea to have at least one and preferably several of these. It's not uncommon to be mounting a scope and have a screw break. If you have a kit, it's a small inconvenience. But without it, you will likely need to order another screw, delaying the job's completion for a week or more. The kits don't always contain exactly the screw you need, but they usually have one you can make into the screw you need. Without them you are stalemated, and don't count on finding any gun screws at your local hardware or industrial supply shops. I needed a screw a little while ago to repair my son Nathan's reproduction Winchester 1873 rifle. This is his Cowboy Action competition rifle and we had a shoot the next day. I live close to a medium-size city and we spent several hours looking, but never could find the right screw. However, back at the shop, one screw kit I had contained a screw that was close and I was able to modify it to fit. He took first place in the junior division the next day. After that, I ordered a few more screw kits. The low price is well worth the time they can save.

LOCTITE • Get a bottle of blue 242 Loctite and use it on just about every screw you put in a gun. You don't need much, just a drop or two, and a bottle will last a long time. The fact that most screws will stay put until you want to remove them is reason enough to use it. The 242 will allow you to remove the part later, something else that's important.

Screw kits

Also consider the lower strength 222 for smaller parts as it's easier to take apart later. The 262 is a permanent application and should only be used on screws you have no plans to ever remove. The 290 is a wicking grade that can be applied outside the screw and it will penetrate the threads. Sometimes you will encounter a screw in a situation where removing it will cause all kinds of parts to spring out. But, you still want to lock the threads so it doesn't come out on its own. A wicking grade solves that problem, but note that it's all but permanent. The screw will require heat to remove it later.

I like the liquid, but they also offer medium and high strength in semisolid sticks called Quickstix. I have been using one on my bench for about a year, but decided I like the liquid much better.

SANDPAPER • Keep a selection of sandpaper and emery cloth on hand in several grits. You will need them often for sanding wood, synthetics or metal. Also keep a selection of different grades of steel wool. An assortment of Scotch-Brite pads is also useful for final polish.

Note that Scotch-Brite pads will remove bluing. Nathan found one in our sink and used it to remove some stubborn release agent from a rifle he just bedded. He thought it was just a scrub pad, but it took the bluing off. Fortunately, it was just on the floor plate and we were able to polish and re-blue the part.

RAGS AND PAPER TOWELS • Pick up a good supply of shop rags and heavy-duty paper towels. I buy mine at one or the other of the "Marts" and usually grab an armload at a time. The ubiquitous red shop rag is used for all kinds of things, and it looks cool hanging out of your back pocket as you work. Everybody knows that's the one true sign of a professional. Also look for some softer shop rags to use for rubbing down more delicate parts and finely blued guns. I usually buy some of the absorbent terry cloth shop rags as well

I keep a roll of industrial grade paper towels over every bench and use them for everything from wiping down a gun I just sprayed with rust protector to cleaning up the many messes I seem to make.

APRONS • A shop apron will keep your clothes clean. For example, I recently spilled a cup of DuraCoat metal coating on a brand-new shirt. I ruined the shirt and stained my belly. The shirt is now a rag and my belly is interesting to explain at the beach. Anytime you are working on guns, you will be working with solvents, oils, sprays, paints and a lot of other things that can ruin clothing. An apron will protect them and keep you looking good.

Bench blocks



Loctite

Assorted sandpapers

Assorted shop rags

Chemical-resistant vinyl gloves

I have two from Brownells, one short and one full length. The short one covers to just above the knees and the long one to below the knees.

LATEX AND VINYL GLOVES • Keep a good supply of throwaway latex and/or vinyl gloves on hand. You will need them for cleaning guns, handling stock finishing products, working with coatings, glass bedding and just about anything else that involves nasty or sticky substances.

You should also have a few pairs of long cuff, heavy-duty chemical gloves to use with parts cleaning solvents and degreasing tanks.

TRASH CANS • There is nothing more aggravating than needing to constantly cross the shop to throw away things. Keep a large trash can near every work station. At the very least, have one at each end of the shop. Use the heavy-duty contractor-style liner bags, as the thin bags will break and leak when you try to pull them out of the can.

Gun Safety

Bryce M. Towsley shooting prairie dogs in Montana with VarminATor bullets.

The destructive power of a modern firearm is incredible and once it's unleashed, it can never be taken back. It only takes a second of inaction for a gun to go off, but a lifetime of regret will never change the outcome.

First off, accept that if you handle firearms enough, sooner or later one is going to go off when you are not expecting it. I know that this statement goes against the "teachings" of gun safety protocol today, but it's the stark, naked truth.

But if you *always* have the muzzle pointed in a safe direction at *all times,* of *every gun* you handle, when this happens it will be embarrassing and it will scare the hell out of you, but nobody will get hurt. The number one rule of safe gun handling is to always consider every gun loaded, even if you know it is not, and to always have the muzzle pointed in a safe direction. Always, always, always, no matter what.

The only exception may be when doing some work on guns that requires the muzzle being pointed in a less than desirable direction. For example, it's difficult to re-crown a rifle muzzle without having body parts in the line of fire. In that circumstance the gun should be made inoperable by removing the bolt or other parts needed to function. At the very least, the action should be kept open.

The first stop for every gun that comes through the shop door is in your hands. Make it a habit to first check every gun to make sure it is unloaded. Open the gun and make a visual check to see that the chamber is empty and that you can see the magazine follower, which indicates that no cartridge is in the magazine. Then stick your pinky finger in the chamber to feel that it's empty. If the gun is a repeating design, point the muzzle in a safe direction and work the action several times, and then check again, both visually and by feel to be certain it's still not loaded.

Every time you pick up a gun, check it again. Even if you think you just did. Somebody could have loaded it when your back was turned. It may seem silly and redundant, but it is not. This does two things. First, it ensures that the gun is safe. Second, it forms a habit with you that after a while becomes second nature. If you automatically check a gun every time you pick it up, you will be less inclined to make a mistake or get an unpleasant surprise.

Never function test a gun with live ammo inside the shop. Use dummy rounds. These are simple to make by resizing brass and seating the bullet without powder or a new primer. Function testing with live ammo to ensure the gun fires, or that a semi-auto will cycle, should only be done at the range or in the shop with an infallible bullet stop such as the Savage Snail Trap Range System. The Snail Trap allows shooting inside and will safely catch

GUN SAFETY PROTOCOL



An automatic pistol with the slide pulled back and the chamber open. Every time you pick up a firearm, make a visual inspection to be certain that the weapon is unloaded.



To be doubly sure that the firearm is unloaded, insert your little finger into the chamber and feel to make certain that it is empty.

the bullets. I have two and the larger one will handle cartridges up to .50 BMG. The smaller "Gunsmith" model will handle cartridges up to the .338 Winchester. This system captures the bullet in a wet, lubricated steel spiral that sends it around and around until the energy is spent. Then the bullet drops through a hole in the bottom into a collection tray. Unless you have a range on-site, this is a very handy tool to have in your shop. It allows firing a gun safely inside a building or in an urban area.

To be blunt, if you fire even a single round at the shooting range or in your shop with the Snail Trap without high-quality eye and ear protection, you are a total moron. One simple question, how much hunting, shooting or tinkering on guns are you going to be doing when you are blind? I suppose you can still do most of that if you are deaf, but it won't be fun and your success will be less than sterling.

It takes about a millionth of a second to lose your sight and you can't know when it's coming. Your gun or the guy's next to you can blow up, it can potentially happen to any gun at any time. But the possibility of splash back from the bullet is just as real. My cousin Philip can attest to that. He was hit in the leg by splash back and it penetrated through his new jeans and stopped when it hit his femur and cracked it. Philip is a big, rugged guy with muscular legs and if it penetrated to the bone on his thigh, it would certainly have taken out his eye with no problem.

Save your money, buy the best shooting glasses you can afford and wear them every single time you fire a gun. No exceptions.

Hearing loss is not so immediate, but is instead a cumulative effect. Every time you fire a gun without ear protection you lose a little more hearing. If you don't think that can add up, ask an old shooter from your grandfather's generation when they rarely wore ear protection. But write the question down, because I doubt he will hear you.

I have been lucky to meet several of the old gun writers whose work I had been reading for years. They all seemed to have the same limited vocabulary.

"Huh?"

"What?"

It makes for lousy conversation.

45

How We Learn

Chapter 2

Installing a Recoil Pad...36
Modifying a Shotgun Stock...40
Stripped Allen Head Screws...44
Trigger Talk...47
Chamber and Bore Polishing...52
Installing Sling Swivel Studs...54
Installing a Marble's Tang Sight...58
Repairing a Ruger Trigger...60
Scope Mounting Made Easy...66
Cutting Off a Barrel...76

Most hobby gunsmithing consists of small projects like installing a set of sling swivels, mounting a scope, installing a recoil pad or perhaps adding a new trigger. These are the core of this hobby and are also how we learn the craft. You can't expect to jump in with both feet and build a rifle if you don't even know how to run a drill press or read a micrometer. These small to moderate size projects are how we develop our skills. They make up the day-to-day work that builds familiarity with the tools and processes and breed confidence for bigger jobs.

I am not sure when I first began hobby gunsmithing, but the first project I recall was when I was about ten years old and someone at school sold me a BB gun scope. It was a side-mounted affair and not made to fit my gun. But I had a plan. I glued the mount to the side of my lever action Daisy. But I forgot one important thing, the scope was not lined up with the bore and there was no way to adjust the sight enough to compensate. But now I had the thing permanently epoxied to my gun. With my father's help I managed to get the scope off, shim it until it lined up and put it back on with a couple of screws. I was envied by all of my buddies, who I neglected to tell about my attempt to mount the scope by myself. My next project was refinishing the stock on my first .22 rifle. The outcome was very good and inspired me to keep trying.

There were more small projects, like repairing a broken rifle stock for one of my teachers, or fixing the safety on a Marlin .22 pump-action rifle. I mounted sights and scopes and did several stock refinishing jobs and I was starting to get a little cocky. Then I got into another problem trying to drill and tap a .22 rifle for one of my buddies. I didn't have a clue what I was doing and was too stubborn to ask for help. The result was a mess, and it haunts me to this day. But this is how we learn, by doing. My biggest mistake was doing it on someone else's gun. My other mistake was in not wanting to ask for help, or at least learning all I could before starting. In the end, the best I can say is it was a learning experience.

Don't be afraid to fail, but don't be too proud to look for help. Think more than you act, not all projects will be raging successes, but each will teach you something. Even the masters had to start someplace and you can be sure that they made mistakes along the way, too.

My friend and master gunsmith Mark Bansner just built a rifle for a fund raiser for the Grand Slam Club/Ovis. The rifle was named the Transcaspian Urial Ultimate Classic Rifle, the first in a series of four unique rifles. It recently sold for $38,000, a testament to Mark's gun building skills. But he wasn't born with them. He learned by doing many different things with many different guns. No doubt he made some mistakes along the way, but he learned from them and went on to build some of the finest rifles made today. None of us on the "hobby" side will likely attain Mark's skill level, but we should always strive to be the best we can be at what we do.

I plan to send an inscribed copy of this book to my old junior high buddy along with an apology for messing up his .22 rifle and a thank-you for a lesson that stuck.

Installing a Recoil Pad

Gunsmithing Project No. 1

A finished recoil pad installation on a Stoeger Coach Gun.

MATERIALS LIST

- pencil
- jig
- sander
- abrasive
- masking tape
- felt marker
- sanding block
- soap
- screws

Can hobby gunsmithing books or magazine articles have a cliché? If so, installing a recoil pad is a candidate for the top of the list. It's been "done to death" as they say, but it's still a viable project.

While there are some recoil pads on the market today that are "pre-fit," they are mostly for the very popular model firearms and we will proceed on the assumption that your gun is not a candidate.

Measure the butt of your gun and order a recoil pad that is slightly wider and slightly longer. Make sure it's the style and design you want. In years past, you could have red-ventilated or black-ventilated, today there are lots of options. Some of the new high-tech recoil pads like the Pachmayr Decelerator do a wonderful job of reducing felt recoil and I highly recommend them, even though they cost a bit more. The recoil pad must be larger than the gunstock at all points around the parameter and have enough extra to carry the lines of the toe and heel out to the edge of the recoil pad. However, do not get a recoil pad that is too big, as some contain an internal metal frame and if you sand enough of the recoil pad away, the frame will show. (I learned this the hard way!) Here is a tip that might save the job. If a small amount of the metal frame is exposed on a black recoil pad, you can coat it with liquid electrician's tape. Apply several overlapping coats to the rubber on the recoil pad, and when it's dry, sand it flush to the recoil pad. It will likely show as the color will be slightly off, but it's far better than the metal showing.

Remove the stock from the gun. If you are built like my buddy Pete Lajoie and are six feet six inches tall with arms longer than my legs (his son Colin is seven feet two inches!), you probably need the extra length of pull that a new recoil pad can add to a rifle or shotgun. However, for those of us constructed more like normal humans, the next step will be to cut the stock off.

If you want to adjust the length of pull longer or shorter, now is the time. Just remember to add for the recoil pad length to your final measurement. If you want to retain the same length of pull, you will need to cut the same amount off the stock as the thickness of the recoil pad. If the pad is one inch thick, you need to cut one inch off the stock to maintain the same length of pull.

This pad shows careful installation on a high-tech synthetic stock.



Measuring the length of pull on a shotgun stock with a Brownells Pull & Drop Gauge prior to installing a recoil pad.

The best way to cut the stock off is with a table saw. Use a high quality 80 tooth carbide trim and finish blade. Keep this blade just for this type of work and protect it from any damage or misuse. This blade will help to keep chipping on the off side of the cut to a minimum. I have read that wrapping the stock with masking tape will also help reduce chipping, but in the couple of times I tried this I have not noticed that it helped and the tape can gum up the saw blade.

Set the ripping fence on the table saw to maintain the correct distance for the amount you wish to cut off. Remember to measure from the opposite side of the saw blade to allow for the width of the cut. The ripping fence provides a positive stop for the stock to maintain the correct length to be cut off, and it also provides a square surface to index the butt against. The butt should fit flat and square against the ripping fence to ensure that the cut exactly follows the lines of the stock. Use the crosscut guide to push the stock, and angle it so that it is pushing the stock with the butt perfectly square to the saw blade. It's likely that the front of the stock will require a shim or two underneath to raise it up to keep the butt square with the ripping fence. That's because the stock is thinner to the front than in the rear. If left to just lie on the table, the cut would not be square to the centerline of the stock. So, take a little time and make sure the stock is leveled so that the butt remains square to the ripping fence. It's a good idea to tape the shim to the stock to keep it in place. Lower or remove the saw blade and try pushing the stock along the path you will use to make the cut to ensure that everything is going to work the way it should. Shims have a way of slipping; things catch, shift and move. Find this all out and correct any problems before you start the cut. Check and recheck everything until you are absolutely certain it's perfect. You can't replace what you cut off and if you do it wrong, you are screwed! So check twice, cut once.

Of course, if you are planning to change the angle or pitch of the butt pad, you will not square with the ripping fence, although the cut must still be 90° with the centerline of the stock. Making this change is something to consider. Most rifles have the recoil pad at an angle, but a butt pad that is ninety degrees to the bore will reduce the felt recoil of a rifle. If you elect to make the change, always make your measurement from the longest

MARATHON
Long Distance Runner
IRWIN
80T
Trim/
Finish
Corte / acabado
Garniture/ finition
10-in
40 Tooth
Rip / Cross Cut
5,500
MAX RPM
WARNING

Top: For the best cut on a gunstock, use a carbide 80 tooth saw blade.



Using a table saw to cut a shotgun buttstock.



Cutting the stretched rubber of a recoil pad to allow inserting the screws. Always use a new razor blade or a fresh utility knife.

point to ensure that the length of pull is correct.

It goes without saying, or should, that you need eye protection when running the saw. Start the saw and carefully make the cut. It should be perfect but if it's slightly off, you can square it up and clean it up later on a disk sander. Make sure to check the table on the sander for square before working.

It's a good idea at this point to seal the wood before proceeding. Use polyurethane that has been thinned according to the instructions on the can. The wood should soak up the first couple of coats. When it stops absorbing the thinned polyurethane, finish with a couple of coats of uncut polyurethane. This will slow the job down due to the drying time, but will give a much better end result by protecting the stock from water damage. Among other things, water can cause the stock to swell which will ruin the fit of the recoil pad. Also note that some older Remington pump-action rifles and perhaps other guns used compressed wood on their stocks. The stock was somehow compressed into shape and then coated with a "bowling alley" finish to seal it. Once you cut the stock, and particularly if you do not seal it again, the stock will swell. The recoil pad you fitted so carefully is mysteriously too small a few months later. I am not sure of the answer here, except to seal the stock and hope for the best. Or perhaps to leave the recoil pad slightly oversize and then trim it to fit a few months later after the stock has had a chance to stabilize.

Some recoil pads will be warped slightly. If so, you can square up the base on a belt or disk sander. Most recoil pads will require that you cut the rubber to allow the screws to enter. Push a punch that fits in the hole through from the back so it stretches the rubber on the recoil pad side. Use a small, thin, new and sharp utility knife or razor blade to make a small vertical slit centered in the stretched portion of the recoil pad. After making the cut and releasing the pressure from the punch, the slit should not be visible. Do the same for both holes. Lubricate the holes generously with liquid dish soap and carefully insert the screws. You will need a screwdriver that has a round shank and the best would be chrome plated and very smooth. A square or rough shank will tear the rubber where you made the slits and damage the recoil pad. A round, smooth screwdriver that is well lubricated with soap should not.

Odds are the screw holes for the recoil pad will not line up with the existing holes in the stock. Generally, one or the other will line up enough to use. If that's the case, install that screw. You may need to lengthen the screw hole in the stock first to allow for the length that has been cut off. Snug that screw up and carefully align the recoil pad. When the recoil pad is centered, put the punch or large nail through the other hole and tap with a hammer to mark the location to drill for the other screw hole. If neither of the existing holes line up, carefully center the recoil pad and mark the location for both new holes. If they are too close to the existing holes, you may need to fill the old holes. Drill to ¼ inch and insert a piece of ¼-wooden dowel that you have coated with epoxy. Cut the dowel off and sand or file it flush to the stock. After the glue has set, you can drill the new holes.

Drill the holes with the correct size drill bit for the screws. Make sure the holes are deep enough, as a screw that bottoms out will not hold the recoil pad tight. If you try to force it past the end of the hole, it can damage the stock.

Install the recoil pad on the stock. It will be oversized and should overlap the stock all the way around its perimeter. There are a couple of ways to go from here. One is to scribe a line all around the recoil pad at the edge of the stock. Then use a jig to do the grinding. This keeps all the grinding operations off the stock and eliminates the possibility of damaging the wood or the finish. Unless you are planning to refinish the stock, this is the safest way to go. It's easy to hit the stock with the sander; one small contact and the damage will be done. That can't happen if you do the sanding with the recoil pad off the stock.

To use the jigs made by B-Square or Miles & Gilbert, mount the recoil pad on the jig, back side up and set the toe angle as explained in the instructions. Hold the base of the jig on the platform of the sander. It is a good idea to check the platform for square before starting. Sand the recoil pad on a disk or belt sander until just taking scribe line. Remember the line was made outside of the stock, so you must sand to the inside of the scribe line for the best fit. This is tricky, so work slowly and be careful. Once the toe is shaped, reset the jig angle for the heel. Then sand the heel re-set the jig and the sides to the scribe line, again just taking the line. You may want to finish with a hand sanding block. Finally install the recoil pad.

The other method is to sand the recoil pad on the stock. This gives the best fit, but subjects the stock to danger of damage. Simply sand the recoil pad, following the same lines as the stock, but be very careful not to hit the stock with the abrasive. Make sure that you carry the lines of the stock out to the end of the recoil pad. There is a tendency with novices to want to sand the recoil pad edges at a ninety-degree angle to the back of the recoil pad, which, of course, will ruin the pad. Follow the lines of the toe and heel all the way to the end of the recoil pad. This will result in the edge of the pad being at an angle something other than 90 degrees to the back.

INSTALL A RECOIL PAD







3. Pad in Miles & Gilbert recoil pad sanding jig.

1. Masking tape wrapped on the stock to protect the finish while sanding the recoil pad. 2. Scribing a line on the recoil pad along the edge of the stock to allow sanding the pad on a jig.





4. Sanding a recoil pad in Miles & Gilbert recoil pad sanding jig. 5. Shaping a recoil pad attached to the stock. 6. If the stock is going to be refinished, the best fit is by sanding the recoil pad and the stock at the same time.

7. Shaping a recoil pad on a disk and belt sander. Note safety glasses and mask.

Wrap the stock near the recoil pad with masking tape. Use two layers and cover the top layer with marks from a permanent felt marker or pencil. When you start to see these marks disappear, you know you are getting close as the sander is hitting the tape. At that point it's best to stop using the power sander and work with a hand sanding block. Finish with a single layer of tape that is marked and sand until those marks are starting to disappear from sanding. Be very careful not to sand through the masking tape. If you are going to refinish the stock, you can forget the tape and sand the wood and recoil pad at the same time for a perfect match.

Make sure you add more soap when installing the recoil pad and make sure the screws snug it down tight. Clean up the left over soap.

That's it, you are done.

Modifying a Shotgun Stock

Gunsmithing Project No. 2

Shooting the shotgun to check for proper fit as the stock is modified.

MATERIALS LIST

- tape measure
- pull & drop gauge
- pocket plane
- paintbrush
- steel wool
- gunstock sealer & filler
- Tru-oil stock finish

When shooting a shotgun, the shooter's eye is in effect the rear sight. If it is not lined up properly, you will not hit what you are shooting at. The comb is the top line of the shotgun's stock and it's the part that supports the shooter's face and controls the position of the eye. If the comb is too high or too low, the gun will shoot high or low. If it's too much to the left or right, the gun will shoot left or right.

My son Nathan's Stoeger Coach Gun shotgun had this problem. The Coach Gun is an inexpensive and incredibly tough double barrel shotgun that we bought for him to use in Cowboy Action Shooting. This short barreled gun has thousands of shotshells through it in three years of intense competition and it has never failed. Nathan likes it so well that in spite of a vault full of options he also uses it for hunting, skeet and our informal sporting clays sessions. But the comb was too high and that created a tendency to shoot high. This was particularly true in the fast moving game of Cowboy Action Shooting. If Nathan missed, it was always because he was shooting over the targets.

There are some options on adjusting the stock. Remember that the key to sighting in a gun is that you move the back sight in the direction you want the bullet (or in this case the pattern) impact to move on the target. So if the gun is shooting high you will want to move the point of impact down, which means the "back sight," the shooter's eye in this case, must move down. If you are shooting to the left, the back sight must move to the right, hitting right, move the sight left.

If the comb must be higher, the only way to correct it is to add material. There are aftermarket pads that stick on the stock to raise the comb or you can replace the stock with one with the correct dimensions, or even laminate a piece of wood to the top and reshape it. In this case the gun was shooting high, so the stock's comb had to be lowered, which is the easiest of the possibilities. Also, the comb was a little too thick, so the shooter's face was a bit too far to the left (for a right-handed shooter) and it needed to be thinned a little.



Note how the shooter's eye is positioned incorrectly. This indicates the comb height is correct. (Note: This gun is disabled and cannot shoot.)



Measuring the drop on a shotgun stock with a Brownells Pull & Drop Gauge prior to installing a recoil pad.

Before starting, we used a Brownells Pull & Drop Gauge to get some baseline measurements. This is an "L" shaped measuring tool with the short arm movable. The tool is made from cherry wood and not only is functional but looks good hanging on the shop wall as well. It is used to measure the length of pull and the drop of a shotgun stock. With it, we knew what the stock measured for drop when we started, so we could keep track of how much we were removing by measuring with the tool again as we progressed.

The first step is to shoot several patterns over the course of several days before making any changes to ensure that it is indeed a gun problem and not a shooter problem. Ideally the shooter's eye should be looking down the barrel's rib when it's properly aligned, but don't depend on that. I have a couple of double barrel shotguns with combs that are too high and my eye is positioned high so that I am looking down at the rib. Yet, I shoot them well and the patterns hit where they are supposed to hit. So, use your head position as a guideline, but do not make any changes until you shoot the gun several times over the course of several different days. Don't force the aiming. In fact, don't aim at all; shotguns are pointed, not aimed like rifles. Just shoot the shotgun as you would naturally. In this case I had Nathan shoot at steel plates in a simulation of a Cowboy Action Shooting match. I painted the plates between shots so that each pattern impact could be seen. Just as it always had, the gun continued to shoot high and a little to the left. So we decided to go ahead with shaving the comb down and making it thinner.

To shape the stock, we simply took a Stanley Surform pocket plane and a Surform shaver and slowly worked the comb to remove material and make it lower, while being careful to preserve the lines by taking an equal amount of wood off the entire comb. At the same time we thinned the comb a bit, keeping both sides equal to preserve the aesthetic balance.

The Surform is a replaceable blade tool that works like a wood rasp to remove wood. The blade has several formed teeth which cut the wood as the tool is moved along the surface. It will remove wood quickly, so care



Reshaping the comb.

Checking the stock for fit.



Checking the fit will require test firing the shotgun as the stock is modified. Note the pattern on target, not perfectly centered but better than when we started.

is needed to not go too far.

We lowered the comb and thinned it slightly. Then we would try the gun to see how it positioned Nathan's eye along the center rib. When we thought we were getting close, we took the gun out to the range and shot several targets. Then shaved a little more, shot more targets, shaved, shot, etc., etc., until we got it perfect. Just to be sure, we waited a few days and shot some more until we were satisfied that the stock was correctly sized and shaped to align Nathan's eye perfectly. Because we were also fitting a new Pachmayr Decelerator recoil pad, all the work was completed at the same time.

Of course, this cutting down will require that the stock be refinished as it's all but impossible to blend

REFINISHING A SHOTGUN STOCK

1
Klean-Strip
STRIPPER

Stripping the old finish off a stock.

Sanding the stock.

4
BIRCHWOOD CASEY
Tru-Oil
Gun Stock Finish

Tru-Oil
Filler

Finishing the stock.

the color of any new finish to the old finish. So we stripped the old finish off with paint and finish remover and then sanded the stock. After sanding, we stained the stock with a walnut stain. When that was dry, we applied several coats of Birchwood Casey Gun Stock Sealer & Filler, using steel wool between coats. Then we followed with several coats of Birchwood Casey Tru-Oil stock finish; again, lightly polishing with fine steel wool between coats. The stock looks better now than it did when the gun was new.

Nathan could count on several missed shotgun targets in any CAS match before we did this work. With three matches under our belts since modifying the stock, he has yet to record a miss. I would say we got this one right.

3

Staining the stock.

Finished stock on Stoeger Coach Gun.

5

Stripped Allen Head Screws

Gunsmithing Project No. 3

Small vise grips holding broken screw.



MATERIALS LIST

- gun vise
- screwdriver Torx or Allen bits
- plastic hammer
- frozen screw jack
- vise grips
- Dremel tool

The tiny hex head or Allen head screws used on scope mounts have an annoying habit of stripping at just the wrong time. (Kind of a dumb expression isn't it? When is exactly the "right time" for a screw to strip?) This is particularly true when removing a scope mount that's been installed for a while. The screws might be a little rusty from years of hunting and there usually is a bit of corrosion between the screw and the ring threads. Also, the screws were often overtightened when they were installed. It's very common that the screw was damaged during installation by the wrench slipping and buggering up the head. All this adds up to screws that are very tough to remove.

When trying to remove existing scope mounts, it's asking for trouble to use the cheap "giveaway" Allen wrenches that come with scope mounts. They are soft and will strip and round the edges. Usually this will damage the screw at the same time. They are barely acceptable for new installations where everything is new and exactly as it should be with clean threads and where you are in charge of how much torque will be applied to complete the job. But when you are removing old screws that may be rusted in place, very well could have been overtightened when they were installed and may already be damaged from the installation, these cheap wrenches are a poor choice. Use only a good, high quality hardened steel bit in a large diameter screwdriver handle. This also allows you to keep the torque centered on the axis of the screw. With the L-shaped Allen wrenches, the tendency is for the torque to

B-SQUARE SCREWDRIVERS

The giveaway Allen wrench that is often packaged with new rings or bases is more likely to damage the screws than a new high quality screwdriver bit.



B-Square screwdriver set.

✳ B-SQUARE has a tool called a frozen screw jack. This uses replaceable screwdriver tips which it clamps into the screw by force. Then it is turned with a wrench to apply a lot of force. This ensures that the screwdriver won't slip out of the screw, but it's not a guarantee that something will not break. However, if the screw has a prayer of being removed with a screwdriver, this tool is your best option.

be twisted off center and cause the wrench to tip in the screw, which leads to slipping and stripped screw heads and rounded wrenches.

You are only going to get one shot at this, so take some time and get it right. Hold the gun in a gun vise so it's solid and you don't need to worry about holding on to it while you work. Select a hex bit that is in good shape without rounded or worn edges. Make sure the hex in the screw is clean and free from debris so that the bit can enter all the way to the bottom of the screw. Insert it into the screw and tap it into place with a plastic tipped hammer. A few solid whacks with the hammer on the screwdriver handle not only seats the hex bit in the screw, but may also help to loosen the screw. If the fit is sloppy at all, put a little Drive Grip on the wrench. Using two hands push down straight on the screwdriver with one hand and turn with the other. Keep the screwdriver perfectly in line with the center of the screw; do not allow it to tip. Be careful about how much torque you apply as these are small, rather delicate screws. You are not building a bridge here or bolting a new cylinder head on a truck engine, keep that in mind. If the screw doesn't loosen, back off. Try again while tapping on the screwdriver handle with a plastic hammer and applying constant torque to the handle. This is easier to do if you have some help. One person taps on the handle with the hammer while the other keeps the screwdriver straight and applies the torque.

If one screw is a problem, remove the rest of them first. Sometimes there is a misalignment of parts so that when all the screws are tight, the part is applying pressure on one particular screw. If you remove the rest of them, that pressure is relieved and often the screw can then be removed.

If the screw is in a scope base that is sitting on a flat receiver, you can sometimes use a plastic hammer to tap on the base and turn it on the gun enough to loosen the screw. Remove all the other screws, and then tap the corner of the base so that it will drive the base counter-clockwise. It's not necessary to turn it very far, just a partial turn will often break the screw free. Sometimes working the base back and forth with the hammer a few times will also break the screw free. Be careful about doing this on rounded receivers like the Remington 700, as tapping the mount will cause it to cam against the receiver and jam the screw tighter or break it off.

Sometimes you can do everything right and the screw still strips. The base I just removed from a Remington 700 .35 Whelen is a perfect example. The scope was installed sometime back in the late 1980s. The first three screws came free just fine, a testament to the fact that I use only high quality bits for this kind of work, but the last one stripped. I thought it could handle the amount of pressure I was applying, but it had been damaged during installation and the hex stripped easier than it should have, catching me off guard.

I switched to a bit designed for a Torx head screw that was slightly larger than the stripped hole in the screw. Keeping it straight, I tapped the screwdriver with a hammer to drive the Torx head wrench into the screw, effectively cutting the metal with the bit. That allowed me to remove the screw. Of course, the screw is no good anymore and it sometimes damages the Torx bit, but a new bit is only a couple of dollars, far less than the cost or time needed to drill out the broken screw and re-tap the hole. I always keep a supply of screws on hand anyway because it's very common to need a replacement. Brownells and B-Square offer

Tapping the screwdriver with a hammer seats it in the screw and can help loosen the screw.

Sometimes to loosen a stuck screw, remove all the other screws, then tap on the corner opposite the stuck screw to turn the base. This works best with flat receivers.



Brownells Rosin



Shows Torx and Allen type tips screwdriver set.

kits of assorted scope mount base and ring screws.

Sometimes nothing will work and you must drill out the screw. Clamp the gun in a vise and use a drill press, which will give you a lot more control than a hand-held drill. Select a bit that is slightly smaller than the head of the screw. Drill just far enough to remove the head from the screw. Once the drill bit hits the bottom of the wrench socket, it should be centered and it will drill to the shank of the screw. This removes the head from the shank. This will free up the base and if you are lucky leave a small amount of the screw shank sticking out from the gun. If it still will not come out easily and if you have time, it wouldn't hurt to keep this screw saturated for a few days with penetrating oil before attempting to remove it.

Use a new pair of small and high quality Vise Grips to clamp onto the screw and try to remove it. New, so that the teeth are clean, sharp and the jaws are perfectly aligned. Sometimes you get lucky. If there is not enough screw protruding to grip with Vise Grips you may be able to very carefully cut a slot in the screw with a cutting wheel on a small hand-held grinder. Tape off the gun with several layers of masking tape, as the cutting wheel can catch and fly off the screw and mark the gun. Be very careful and hold the hand grinder very firmly when doing this, as it will tend to have a mind of its own. Use very little pressure and a delicate touch. Let the wheel do the work and do not try to force it, as that will cause it to grab and run off to have great adventures with your gun's finish. After cutting the slot, use a flat bladed screwdriver that fits the slot to try and remove the screw. If the screw was rusted or stuck, this slot probably won't be strong enough to remove it. But if the screw was overtightened and jammed, sometimes removing that pressure by drilling the head off will allow you to remove it this way. It may help to gently heat the receiver with a heat gun.

The final solution is to drill out the screw and re-tap the hole. This is a bit tricky and I don't recommend trying it on a rifle receiver until after you have some experience with less critical applications. If you do not have any experience with drilling out broken screws and rethreading the screw holes, a rifle receiver is not the place to practice. Take the rifle to somebody who knows how and has the proper equipment. I have seen several ruined receivers and more than one hole drilled through the barrel by people who didn't believe that advice.



Using Dremel cutting wheel to cut a slot for a screw.

Trigger Talk

Gunsmithing Project No. 4

The trigger has been ground off shorter, reshaped and blued to fit a narrow guard.



MATERIALS LIST

- file
- Allen wrenches
- pliers
- Dremel tool
- trigger pull gauge
- calipers
- punch
- cold blue
- aluminum black
- cleaner/ degreaser
- grinding wheel

One of the undeniable truths about buying used guns is that sometimes you get surprised. The surprises are not always good, and like everybody else I have been burned a time or two. But sometimes the surprise is in your favor.

WHAT A DIFFERENCE A TRIGGER MAKES •

Not too long ago I bought three guns from a family friend as a package deal. The one I really wanted was a 16-gauge Fox Stirlingworth side-by-side double barrel shotgun. No surprises there, it's a lively, light and well-made shotgun. One of my great pleasures in life is in rambling the fall New England woods in pursuit of ruffed grouse. The sharp cold and clean air is filled with the smell of autumn, the trees are at their peak color and the anticipation of flushing birds is like no other feeling in the world. For that, a man really ought to use a double barrel shotgun and to be truly proper, they should be stacked side by side. That's what this gun was born to do, that's what I bought it for.

The second gun is a Savage Model 1907 semi-auto handgun in .32 ACP. It's a compact little handgun that so far seems to shoot surprisingly well. No surprise here, either.

But the third gun was the surprise. I bought it simply because the price was right and because it was part of the "deal," but I held little hope that it would prove to be much of anything interesting or useful. It's a "Pasadena Firearms Company, Inc." rifle built back when guns were trendy and socially acceptable with the "in" crowd and when the state of California still liked them. This sixties-era rifle is based on a Mauser action and is chambered for 6mm Remington. It's a simple bolt-action rifle in a plain walnut wood stock with checkering and whiteline spacers on the grip cap and the buttplate. It has open sights and is topped with a Realist 1.4-4.5 scope, another relic of the sixties, in Weaver mounts. The scope was weeping grease inside the adjustment caps, which made me think of problems. But I cleaned it up and took the gun to the range.

In spite of a horrible double-digit pull-weight trigger with about a foot of creep, the gun turned in some excellent groups. The scope responded well to corrections and seemed to be working fine. I thought it showed some potential so I went home and ordered some ammo. Then I ordered a new trigger. Changing the trigger was a simple job. If not for the fact that I had to modify the trigger portion to fit inside the trigger guard, I would have



Bold trigger from Boyds Gunstock Industries on a Mauser action.

Sean Dwyer, Remington VP of ammo, checking zero in Argentina. Remington Model 700 triggers are adjustable.

completed it in about fifteen minutes with only a few simple tools. The gun has a very shallow trigger guard, so the bottom of the trigger hit the trigger guard. That required that I grind off about a quarter-inch from the bottom of the trigger and reshape the end. I polished the metal and cold blued it. This fully adjustable trigger was easily set to a crisp, clean, three pounds.

The bedding on the stock was appalling but with no time to mess with it, I put it all back together and headed for the range. The gun shows a definite preference for 100-grain bullets and with either Remington Core Lokts or Federal Premium with Nosler Partitions it will group right at one inch at one hundred yards. Later, I glass-bedded the action and the groups shrunk a little more. Handloads brought them down a bit more and in the end this "clunker" gun was shooting like a finely tuned varmint rifle. The rifle may not be all that pretty, but from a shooting standpoint it is a jewel and a pleasant surprise. The single biggest change came from simply replacing the trigger.

The single most important key to good shooting is in the trigger. In a test I did with two rifles of every action type a few years ago, I used six shooters of different abilities and tested for speed and accuracy under hunting conditions. One clear point, perhaps the only clear point, that emerged was that for accurate shooting, the trigger is the key element. Yet most factory guns today have triggers designed to keep the lawyers happy, not the shooters. I think this has been going on for so long now that a complete generation of shooters has never known a good trigger on a factory rifle.

Triggers can be adjusted and some will give a satisfactory result. For example, the Remington Model 700 rifle still has an adjustable trigger and it can almost always be tuned to a very acceptable result. But, most of the gun companies have caved to the trial lawyers and installed nonadjustable triggers or "adjustable" triggers that are a joke on their rifles. They may advertise them as adjustable and I suppose it's accurate, but they are often adjustable from eight pounds down to five pounds, hardly acceptable to a discerning rifle shooter.

FACTORY TRIGGERS • It's a rare factory rifle that is shipped today with a really great trigger, and while some claim to be adjustable, few offer enough adjustment options to achieve an exceptional result. Yet, a good trigger pull is one of the most important things you can add to any firearm.

Achieving greatness in a rifle trigger is almost always going to require some gunsmithing work. Trigger work is one of the most specialized and tricky gunsmithing areas you can get into. It's also one that can create a dangerous condition if you get it wrong. My advice is if you don't know what you are doing when it comes to modifying or adjusting a trigger, don't even try. The best approach for now is to take the gun to a competent professional gunsmith and ask if he will let you watch and learn.

If you understand what makes a good trigger, you will be able to communicate better with the gunsmith about what you want on your rifle. There are four important points to trigger pull. First is the let off weight. This is simply how hard you need to pull on the trigger to make the gun go bang. Big game hunting rifles should have about a three-pound trigger pull. Competition or varmint hunting rifles might require a much lighter trigger pull.

Next is how smooth the trigger pull is. A rough trigger

Tipton
INSTA-CLEAN
Lyman

Installing a Timney trigger on this Weatherby Vanguard rifle has greatly improved the trigger pull.

Nathan Towsley shooting a .223 Remington Model 700 LV SF with a Leupold Vari-X I 4-12X40mm scope. A good trigger pull is important for accurate field shooting.

will actually feel like it pulls harder than it does and a smooth trigger will feel lighter than it actually is. A trigger that hitches and catches as you pull it will never allow precise trigger control for the shooter. A good trigger should pull smoothly with little discernable movement and then break cleanly. The term "breaking like glass" describes the crisp, clean release of a good trigger.

Creep is the amount the trigger travels before it releases. The best rifle triggers have little or no discernable creep.

Finally is overtravel. This is the amount of distance the trigger can move after the sear releases. It's important because that movement occurs during a critical time when the gun is firing and can disturb the aim.

Most adjustable triggers will have three or less adjustments. One will be the tension on the trigger return spring. This is the spring that pushes the trigger back into position after you pull and release it. Every time you pull the trigger, you are pulling against this spring. The idea is to have the minimum amount of spring tension needed to return the trigger into position. That way you are not pulling against more pressure than is necessary. If you get the spring too light, the trigger will not reliably return to position for re-cocking. It might be fine in the shop, but out in the cold, wet, dirty, cruel world it could stop working just when you need it most. So, it's always best to leave at least a little cushion of insurance in the trigger return spring tension. Adjust for the minimum of spring tension needed to return the trigger to position, and then add another turn of the screw to be sure.

Some triggers have a sear engagement adjustment. This one is very dangerous to mess with and if you get it wrong it can result in an unsafe rifle. It's best to leave it alone.

Many triggers have an overtravel stop adjustment. Leave this adjustment for last. After all the other



Adjusting a Timney trigger.

Adjusting the trigger on .458 Winchester Mauser. Wrenches are from Brownells.

Using a Dremel grinder to remove stock material to allow a Timney Trigger to fit on a Weatherby Vanguard rifle.

BIRCHWOOD CASEY
Perma Blue
Liquid Gun Blue
BIRCHWOOD CASEY
Cleaner-Degreaser
BIRCHWOOD CASEY
luminum Black
Metal Touch-up

Birchwood Casey Perma Blue Cold Blue, Cleaner-Degreaser and Aluminum Black.

adjustments have been made, turn the overtravel adjustment screw in until the gun will not dry fire. (It should go without saying that you have made absolutely sure that the gun is empty. That is the first step anytime you pick up a gun for any reason.) Then back it off while holding pressure on the trigger until the gun dry fires. Now turn the screw one-half turn more and lock it down. Check several times to make sure that the gun will fire. If not, add another half-turn on the adjustment screw.

If these adjustments are not enough to provide an acceptable trigger pull, the next step is to take the trigger apart and polish the engagement surfaces with a very fine stone. This is tricky work that can result in an unsafe firearm if done incorrectly. My advice is do not attempt to modify or otherwise change the internal parts of a trigger. Some things are best left to the professionals.

While modifying and tuning a trigger is a complicated project, and not recommended for most hobby gunsmiths, usually replacing the trigger is simple and is an easy project. Companies like Timney, Boyds and others offer aftermarket triggers that are well made, fully adjustable and usually very easy to install on most factory rifles.

Usually it's a matter of taking the action out of the stock and removing a screw or backing off on a set screw and removing a pin that holds the trigger group on the gun. Then reverse the process with the new trigger. Usually it's about ten minutes' work.

Sometimes you need to modify the stock a little bit to allow room for the new parts, as the trigger may not have the exact same external dimensions as the old trigger. That was the situation when I put a Timney trigger on my new Weatherby Vanguard in .257 Weatherby. I had to use a Dremel tool to remove a little bit of stock material in front of the trigger to allow for slightly wider trigger housing. That caused the job to take about twenty minutes.

When installing a Timney trigger on a Charles Daly Mini-Mauser, it was necessary to make a choice between modifying the slot in the trigger guard or modifying the trigger, as the trigger was too thick to fit through the slot in the bottom metal. I have done it both ways, but the easiest is to simply thin the actual trigger (the part you pull on) on a belt grinder or with a file until it fits. Then polish the metal and cold blue. With this trigger, putting on the safety causes a pin to pop out of the other side of the trigger assembly and it was necessary to remove a bit of wood for clearance. It was also necessary to bend the

ALLOWING SPACE FOR A WIDER TRIGGER



Measuring the trigger guard on a Mini-Mauser to allow for a wider trigger.



Using a file to open the space in the trigger guard on a Mini-Mauser to allow for a wider trigger.

BIRCHWOOD CASEY
Perma Blue
Liquid Gun Blue

Rebluing the trigger guard with cold blue after the space is enlarged.

safety arm with a pair of pliers so that it would clear the bolt shroud. Some material had to be removed from the stock to allow the safety to operate without interference. In the end, the job took about an hour the first time. But I had an excellent end result.

My point here is to illustrate some of the problems of installing a trigger and how to deal with them. They are mostly problems dealing with fitting the new trigger into the stock and trigger guard, which are not very technical, but do require patience and skill. Each rifle will be slightly different in the problems it presents, but by talking about those I have worked on recently, I can illustrate some of the approaches to solving those problems.

Changing a trigger is almost always easy and fast and will result in a far better trigger pull. Contrast that with the last full-blown trigger job I did on an existing trigger, a Ruger M-77, when I had about three hours invested to create a very good trigger pull. A few months later I had to send the gun back to Ruger for a replacement barrel and they took my trigger off and replaced it with another "Ruger" trigger that pulled seven pounds of creepy crud. Sometimes you just can't win.

NEW TRIGGER FOR WEATHERBY

Installing a Timney trigger on a Weatherby rifle.



Installing a new trigger is often as easy as loosening a screw and pushing out a pin, then reversing the process. The pin is indicated by a pointer, and the screw by a screwdriver.

NEW TRIGGER FOR MINI-MAUSER

Measuring a Mini-Mauser trigger.

Timney trigger on a Mini-Mauser rifle in a Boyds stock.

Using pliers to bend the safety on a Timney trigger so it will clear the bolt on a Mini-Mauser rifle.

Chamber and Bore Polishing

Gunsmithing Project No. 5

Using a Brownells chamber flex hone to polish a shotgun chamber.

MATERIALS LIST

- chamber hone
- hone oil
- wire brush
- cotton patches
- jeweler's rouge
- variable speed electric drill

If you are competing in Cowboy Action Shooting with a double barrel shotgun, you need to be able to reload quickly. The SASS rules state that the gun must not have ejectors, and one of the most frustrating things I dealt with early on was trying to get the empty shells out of my double gun in a hurry. I learned by watching the top competitors and I noticed that they all just dumped them out, or some simply opened the gun and thrust it forward suddenly, ejecting the empties. I tried both with my shotgun, but it didn't work. So I started asking questions. It turns out that they can do it because they have chambers that are polished and this allows the empty hulls to slide out easily.

Brownells makes an inexpensive tool to polish the chambers called a chamber flex hone. This tool has hundreds of abrasive "balls" mounted on a flexible shaft that will polish the chamber. Always use their Flex Hone Oil, as any other oil can damage the hone. Keep lots of oil on the hone and make sure you are prepared for a mess. The oil will run out the bottom of the barrel as you work and make a mess on your shoes and the floor if you are not careful. The hone will fling oil from centrifugal force each time it exits the barrel. I like to do this outdoors and to let the oil drain onto a wad of paper towels. Wear old clothes and/or a shop apron. Always have on eye protection.

Clean the chamber and bore first, making sure you have all the fouling out. The plastic fouling from wads can be tough to remove, but you must get it all out as it can damage the hone. Use a wad fouling solvent and a wire brush, and keep scrubbing. A while back, my son Nathan called my cell phone while I was off on a hunting trip. He had just cleaned his Stoeger Coach Gun shotgun with a wire brush and when he looked through the barrel,

FLEX-HONE OIL
18.0 VOLT

The Brownells chamber flex hone, shown attached to a drill, is used for polishing a shotgun chamber.

it was all peeling away. He was sure he had ruined his shotgun and was very upset. Of course, it was just all the plastic fouling that had collected after a long season of Cowboy Action Shooting and a lax cleaning program. I had him switch to the proper solvent and he had the barrel looking great in no time at all. We try to stay on top of the fouling better now and clean after every match with the right solvents.

Remove the barrel from the shotgun. Chuck the flex hone in a variable speed electric drill and wet the hone with Brownells Flex Hone Oil. Start the drill on low speed and insert the hone into the chamber. Run it up to about three-quarter speed, or about 700 rpm to hone the chamber, as it cuts a slurry of abrasive and oil develops to help speed the cutting action. Avoid excess pressure and slowly keep the hone moving front to back.

I usually take this a step further and after using the Brownells hone, I finish the chambers by using a brush wrapped with cleaning patch material and impregnated with jeweler's rouge. Or, if I can find them, an oversize chamber mop, for example a 10-gauge mop for a 12-gauge gun. I simply impregnate these with jeweler's rouge and polish the chamber by moving the tool in and out. I then reverse the direction of the drill, and replenish the jeweler's rouge often. This gives me a very smooth, polished finish in just a few minutes.

Brownells also offers a Flex Hone which is a diameter to fit the bore and, of course, has a longer shaft so it can reach the entire barrel. Polishing the bore will clean up the barrel's bore and reduce fouling as well as potentially help patterns. It also makes cleaning the barrel much easier. Another hone is designed for the forcing cone if you want to cover all the bases.

After completing the work, clean the barrel with a degreasing spray to flush out all the slurry. Then clean with patches wet with solvent followed by dry patches. Finish with a rust protector.

This is not only a good treatment for a CAS competition shotgun, but polishing the chamber and the bore is also a great way to improve any hunting or clay target gun that does not have chrome lined barrels. The gun will shoot better and will clean easier. If it's a semi-auto, extraction will be improved and as a result, the gun will function more reliably.

Plus, there is a certain satisfaction in looking down a shotgun's bore and seeing all that shiny, perfect finish and thinking, "I did that."

Note how this CAS shooter is dumping the empty hulls from his shotgun.

Installing Sling Swivel Studs

Gunsmithing Project No. 6

A sling swivel stud installed on the forend of a bolt-action rifle.

MATERIALS LIST

- tape measure
- screwdriver
- electric drill
- drill press
- bits
- glue
- electrician's tape
- bit alignment tool
- brass punch
- plastic hammer

The old saying that "you carry your rifle a lot more than you shoot it" has a ring of truth to it. A sling on a rifle makes it a lot easier to carry the rifle and can be used as a shooting aid. Not all guns are shipped with sling swivel studs, but installing them is an easy project for the hobby gunsmith.

The following instructions work well for both wood and synthetic stocks. You will need a set of sling swivels designed to fit your rifle. Perhaps the best known supplier of these is Michael's of Oregon. You will also need the correct size drills. You can buy drills designed specifically for this job, or use standard drill bits you probably have in your shop.

It's important to remove the stock from the rifle. This not only makes it easier to handle, but helps prevent damage to the metal. The first step is to mark the location for the rear stud about 2¼ inches to 3 inches from the toe of the butt pad. If you use a drilling fixture like the Miles & Gilbert shown in the photos on page 56-57, draw a pencil line along the centerline of the stock to help align the fixture. Otherwise, use a prick punch to mark a hole in the exact center of the stock at the location where you want to mount the swivel stud.

Uncle Mike's recommends a .157-inch drill (5⁄32 inch) for the rear swivel stud screw. It is critical that the drill be exactly centered on the stock and that it is at a 90-degree angle to the bottom edge of the stock. The drill fixture will keep the 90-degree angle, but will not guarantee that the drill is centered. It is best to clamp the stock in a padded vise and use a drill press but if you are extremely careful, a hand-held drill will work. Make the hole deep enough to accommodate the full length of the rear swivel stud screw and ⅛ inch more. If you are using a hand-held drill, wrap a piece of electrician's tape around the drill to act as a marker or stop for when you are deep enough. With a drill press, set the stop on the press for the correct depth.

The top shank of the screw is not threaded and so a slightly larger hole must be drilled to allow it to pass without splitting the stock. Uncle Mike's suggests a .220-inch drill (7⁄32 inch). Be very careful to only drill deep enough to accommodate the shoulder of the screw and no deeper. If you are using a hand-held drill, it's a good idea to wrap the drill with vinyl electrician's tape to act as a stop, as the drill bit can catch in the wood and pull the drill in too deep without some sort of mechanical stop. If you are using a drill press, set the stop to prevent the bit from drilling too deep.

Finally, the stock should be squared to accept the swivel stud base and, if you elect to use one, the white spacer. It's best to use a cutter designed for that job. Uncle Mike's offers a counterbore that is .373 inch. But if you do not have that, you can do it with a ⅜-inch drill bit, although this is a distant second choice. Be very careful as you only want to "kiss" the wood and not actually drill to any depth. This simply squares up the face of the stock and gives the swivel base a solid foundation to tighten against. Sometimes, running the drill in reverse first will help to compress the wood and "pre-stress" it in preparation for the actual drilling.

Seal any exposed wood with stock finish or polyurethane and let it dry. Coat the threads of the swivel stud with glue and carefully screw it into the hole. Make sure that you have it square and aligned correctly with the hole. Use a pin punch, a nail or an Allen wrench to screw the stud in. No matter which you select, be very careful that it doesn't contact the stock as you turn it, as this can scratch the wood. An Allen wrench is usually available and will work, but the wrench can turn and the short leg can scratch the stock, so be very careful. Or better yet, use a pin punch. When the swivel base is tight, it should sit square and tight against the stock and should be aligned in the center. Make sure, too, that the hole through the swivel stud is ninety degrees to the centerline of the gun.

Bolt-action rifles have the forward stud mounted in the stock about 2 inches to 2½ inches from the forend tip. You must remove the stock from the rifle for this one. Carefully mark the stock in the exact center with a prick punch. In this case, we are drilling a hole that the machine screw for the front swivel will pass through, so the hole has to be slightly larger than the screw. For Uncle Mike's sling swivels, use a .190-inch (3⁄16-inch) drill bit and drill all the way through the stock.

Turn the stock over so that the barrel channel side is facing up. The hole must be counterbored with a larger drill to allow the swivel nut to be inserted far enough to be below the surface of the barrel channel. Uncle Mike's suggests a .388-inch counterbore or a ⅜-inch drill bit will work. Be careful not to drill it too large, as the edge of the nut is serrated and it must be a tight fit in the hole for those serrations to grip and hold the nut against turning.

Coat all exposed wood with stock finish or polyurethane and let it dry. Using a small brass or plastic hammer, and/or a brass or nylon punch, tap the swivel nut into the hole with the rounded side down. Work carefully, making sure the nut doesn't twist or get out of alignment with the hole. Make sure that the top of the nut is below the surface of the barrel channel in the stock. Now screw the swivel stud in from the other side and tighten. Make sure that the screw does not protrude above the barrel channel in the stock. If it does, remove it and grind off enough to bring it below the stock. Reassemble the rifle and install the sling.

Pump action, semi-auto and lever action rifles often use a band type front swivel stud. In the Uncle Mike's style, these are wrapped around the barrel or magazine tube and a hollow screw is threaded through to pull the two sides together. The sling swivel's pin will then pass through the hollow screw. These bands can be a bit aggravating to install and persistence is your best tool. Position the band as close to the top of the forend as possible. However, the diameter of the tube or barrel often will limit how far down the band will slide. Be careful not to force anything, as you can easily scratch the bluing.

A few tips. Smooth the inside of the ring and polish a small radius on the edges. This will help it slide up and down easier for positioning and reduce the risk of marring the bluing. Make sure that the holes on the two sides are in perfect alignment before attempting to install the screw. A padded vise can help correct any misalignment. It is easier to remove any sights and barrel bands to allow the band to slide down the tube or barrel than it is to bend the ring around them and then try to bring it back into alignment.

If the swivel will not close all the way after installation, use a file to carefully cut the sides of the stud to reduce the thickness until the swivel will close and lock.

FIXING MISTAKES • If you screw up and drill the rear swivel hole slightly off center, Larry Weeks at Brownells explained that there may be a way to correct the mistake.

Redrill the hole using a larger drill, but make sure that

Miles Gilbert
Gun Engineering Supplies
UNCLE MIKE'S
#1441-2
760 BB
for up to 1" Slings
NEW Quiet Swivels with Tri-Lock

Tools and materials for installing sling swivels on a pump action rifle. Drills, alignment tool and swivels.

it is smaller than the base diameter of the swivel. Try to correct the alignment problem as much as possible while drilling this hole. You may also try using a small cutter in a Dremel tool to open the hole on the side that is off center.

Coat the swivel stud and screw with a release agent and allow it to dry. Paste wax will work, but the best is the release agent that Brownells supplies with their glass bedding kits. They also sell it in three-ounce or one-quart bottles.

Clamp the stock in a vise to keep it level and cover the stock around the hole with masking tape. Fill the hole with Brownells Acraglas Gel bedding compound and insert the swivel stud into the hole. Wipe up any excess gel and keep the swivel stud aligned; use a piece of tape to hold it if necessary. It's a good idea to dye the Acraglas Gel as close to the color of the stock as possible. After the Acraglas

INSTALLING STUDS ON WOOD AND SYNTHETIC STOCKS



1. The drill selected to countersink the hole in the forend of a bolt-action rifle's stock must be slightly smaller than the knurled nut used so that it will be a tight fit to grip the nut. 2. Marking the location for the rear sling swivel stud.



3. Using a drill alignment tool as a guide while drilling a rifle stock to install a rear sling swivel stud. When using a hand-held drill, care must be taken to keep the alignment correct. 4. This cutter squares the stock for better alignment of the sling swivel stud.

5
GORILLA GLUE

5. A dab of glue on the sling swivel stud screw will help keep it in place.



6. Using an Allen wrench to install the rear sling swivel stud. Be very careful to not contact the wood with the Allen wrench, which can gouge the stock. 7. Shows a correctly installed rear sling swivel stud. In this installation the optional white spacer was included.

Gel sets, you can remove the stud by unscrewing it. Clean up any excess gel and carefully sand flush to the stock contours. Reinstall the swivel stud and wait a week before using it, to allow the compound to set completely.

You can also repair a rear swivel stud that has pulled out and stripped the wood using this method. Drill the hole just enough larger to clean it up and give you a clean wood surface for the Acraglas Gel to adhere to.

8. This shows a rifle stock clamped in a vise in a drill press in preparation for drilling. 9. Proper drill size is important to a quality installation of a sling swivel.



11
BIRCHWOOD CASEY
Tru-Oil
Gun Stock Finish

10. Using a brass punch to tap the knurled nut into place for installing a sling swivel stud on the forend of a bolt-action rifle. 11. All exposed wood should be coated with stock finish.



12. Installing the tension screw for a Michael's of Oregon band type sling swivel on a Remington 7600 pump-action rifle.



13. A completed installation of Michael's of Oregon band type sling swivel on a Remington 7600 pump-action rifle.

Installing a Marble's Tang Sight

Gunsmithing Project No. 7



Marlin 1894 rifle with tang sight.



Shooting a Marlin with a tang sight.

MATERIALS LIST

- gun vise
- gunsmith's screwdrivers
- brass hammer
- drill press
- tap & die set
- center punch
- brass or nylon punch

There is something inherently "American" about hunting with a lever action rifle. After all, the lever action is the "gun that won the West." It's the gun our grandfathers hunted with and for many of us it's the gun we first lugged into the deer woods. Returning to those roots has a certain appeal, but for a lot of us the open sights are not as sharp as they were when our eyes were young. A peep sight is much kinder to eyes of any age and a tang-mounted peep sight is a nostalgic return to the roots of lever action rifles and is extremely popular with Cowboy Action shooters.

Installing a tang-mounted peep sight on a lever action rifle is a simple "do-it-yourself" project for any hunter with a few basic tools. Both Lyman and Marble's offer tang sights to fit Winchester and Marlin lever action rifles. In this case we will be mounting a Marble's tang sight on a Marlin Model 1894 rifle.

Clamp the rifle in a cradle like the Decker Gun Vise. Remove the tang screw and place the sight on the tang. Make sure that you use a gunsmith's screwdriver that exactly fits the screw slot and has parallel sides. Do not use a standard screwdriver, as the tapered sides can cause the screwdriver to ride out of the slot and gouge the rifle. One of the best investments you can make is a set of gunsmith's screwdrivers available from Brownells, Lyman or Chapman.

Install the longer tang screw supplied in the rear sight in the hole and tighten enough to hold the sight, but also to allow it to move when tapped gently with a plastic hammer. Center the front of the sight on the tang by tapping it gently with a plastic hammer or with a hammer and a nylon or brass punch.

Using a center punch, mark the tang in the exact center of the hole. A spring-loaded center punch like the one made by Starret makes the job a little easier, as it eliminates the use of a hammer and is easier to control. If you plan to on installing more sights in the future it will be worth the extra cost. A shotgun bead drill fixture sold by Brownells is designed to center a drill on a shotgun rib. It can be used to ensure that you are exactly in the center of the tang.

Remove the tang screw and remove the sight and the buttstock. Clamp the rifle in a vise with padded jaws and place it in a drill press. Chuck the proper size drill in the drill press. In this case we will use a #21 drill for a 10-32 screw. (The screw size information will be included with the sight.) Make sure that the tang is square to the drill and that the drill is lined up exactly with the punch mark in the tang. Double-check everything and when you are certain it is correct, carefully drill through the tang.

Select the correct tap for the screw supplied with the sight, in this case a 10-32. Put the tap in a tap handle. Make sure that the tap is square with and centered in the drilled

INSTALLING A TANG-MOUNTED PEEP SIGHT


1. Center punch marks location to drill.


2. Starrett spring-loaded center punch.


3. Brownells' shotgun bead drill fixture to center drill.


4. Drilling the new hole.


5. Tapping the new hole.


6. Tightening the screw.


7. Using a brass punch to install a plug in the dovetail where the rear sight was.


8. New tang sight installed on Marlin Model 1894 rifle.

hole and that you have applied plenty of cutting oil. Carefully turn the tap clockwise to cut the new threads. Make sure to reverse the tap often to clear the chips every turn or so. The tap should turn easily and cut cleanly. If it binds or chatters, stop, something is wrong. Do not force it as taps are very brittle and can break easily if misused.

After you have the thread the full depth of the hole, wipe the tang clean of cutting oil and chips. Install the buttstock and the sight. Replace the tang screw, but do not tighten. Install the front screw and snug it down. Tighten the rear tang screw, then tighten the front sight screw. A drop of blue Loctite on the threads of each screw before installing will help ensure that the screws stay tight.

Use a brass or nylon punch and a hammer to remove the open sight from its dovetail. Install a dovetail slot blank by tapping it into place until centered with a brass or nylon punch. If you use brass, it may mark the metal. Wipe this with a patch wet with copper removing bore solvent and it should remove the brass smear. The front sight bead should be fine, but you may consider one that is higher or lower.

The sight is now installed. All that is needed is to zero the gun at the shooting range and enjoy it.

Repairing a Ruger Trigger

Gunsmithing Project No. 8

Ruger Vaquero single action handgun



MATERIALS LIST

- gunsmith's screwdrivers
- trigger pull scale
- plastic hammer
- vise
- punch
- Arkansas stones (hard)
- Dremel tool
- buffing wheel

By the end of World War II, Colonel Colt's famous six-gun was yesterday's news; everybody knew that, even Colt. In 1947 Big C had announced that they would no longer make single action handguns. With that, the design became obsolete. The future, they said, was in double action revolvers and semi-auto handguns. One Colt executive snidely told Bill Ruger, "You'll find that out."

But, as Ruger said about the people running Colt at the time, "They really saw no fun in the gun. To them it was a chore and a bore. . . " Ruger was a gun guy and he decided that a single action still would appeal to the public and set out to prove that with a new single action .22 rimfire revolver. Pete Kuhlhoff ran a small announcement about this new single action .22 LR in *Argosy* magazine, and the Southport, Connecticut, post office was flooded with mail. That left little doubt that the public didn't share Colt's views on the role of single action revolvers in the mid 20th century and it launched Ruger into the single action revolver business.

Sturm Ruger introduced the Single Six, single action .22-caliber revolver in 1953 and from that grew to be the single largest producer of single action handguns in America today. The Ruger single action handguns are legendary for strength, reliability, accuracy and durability. In recent years they are also legendary for the poundage of their trigger pulls. As my cousin and local shooting philosopher Philip Baker said, "It takes three men and a hairy dog just to pull the trigger on those guns!"

With lawyers setting the rules for so much of American life these days, a good trigger pull on a factory shipped gun is as rare as an honest politician. They exist, but most folks have never seen one in its natural habitat. Yet, like honesty, a quality trigger pull is perhaps the number one prerequisite for straight shooting.

I am not sure what we can do about honesty in politics, but putting a good trigger and a smooth action in a single action Ruger handgun is pretty simple. It can be done by any hobby gunsmith with a few tools and a mechanical aptitude that is at least a little higher than Michael Jackson's.

Your workbench should be clean, free from clutter and have good lighting. You will need a pad to work on to prevent scratching the gun. There are lots of excellent commercial pads, but an old bath towel works well, too.



The Ruger Vaquero handgun with some of the tools and parts needed to improve the trigger pull and smooth up the action.

Trigger Pull Gauge
Lyman
4.93
TERS

The Ruger Vaquero handgun showing the "before" trigger pull on a Lyman trigger pull scale.

One excellent investment anytime you work on guns is a book that shows an exploded parts drawing of the gun you are going to be working on. I can't tell you how many times I have been saved by this. It's easy to take a gun apart, but sometimes not so easy to put it back together, and a drawing showing how it all goes back in place is a pretty good embarrassment antidote.

Most of the Ruger single action revolvers are pretty similar, but there can be some differences. The gun we are working on here is a Vaquero chambered for .357 Magnum. This is basically the same gun as the Blackhawk, but without adjustable sights. As the slimy VCR salesman on the old SNL skit said, "same guts." It's is also essentially the same as the Super Blackhawk and the New Model Single Six. The parts are not interchangeable, but the design is pretty much the same.

One trick that will save you a lot of trouble is to clear a space on your bench away from where you are working. As you remove the parts from the gun, place them in the relative location where they go. Orient the gun as you would hold it to shoot as a reference. Place the top screws on top, left screws on the left, etc. Do the same with internal parts, keep them in the relative position they are removed from.

If course, it goes without saying that you should make sure the gun is unloaded before doing anything. Open the loading gate to free the cylinder. Depress the lock for the base pin located in the front of the frame and remove the base pin by sliding it forward. On some guns it will hit the ejector rod before it's completely clear of the frame, so you can't completely remove it without removing the ejector rod housing. However, this is not necessary as the pin should be far enough forward to remove the cylinder, which is the goal here. After removing the cylinder, close the loading gate. Remove the grip screw and remove the grips. If they are sticking, replace the screw but leave it slightly high. Then gently tap the screwhead with a small plastic hammer. This will break the off-side grip free. Remove the screw and the grip panel. Reach through the grip frame with a large punch and gently tap the other grip to free it.

Cock the handgun. Sometimes the cylinder advance pawl will catch on the frame if the cylinder is not in place, preventing the gun from being cocked. If that happens, simply reach into the frame with a small screwdriver, push back on the pawl and the gun should cock.

Inside the grip frame, the hammer strut should be protruding outside of the hammer spring by a considerable margin. Notice the small hole in the hammer strut. Insert a nail or pin punch into that hole and pull the trigger while holding the hammer, then slowly lower the hammer. The mainspring seat will hit the nail or punch you inserted and will hold the tension off the hammer. Remove the five grip frame screws. The top screws first, the front bottom screw next and then the rear bottom screws. Make sure you place them on the bench in order so you know exactly where each screw fits. Note that the screw on the bottom right has an extension that mates with a groove in the hammer pivot pin, so it must be replaced in exactly the same hole. Pull the grip frame slightly to the rear and remove. Remove the hammer strut and spring assembly from the grip frame. Make note of the orientation of the strut, as there is a top and bottom and it must be correct when reinstalling it.

If you are planning to change the hammer spring, you would skip the step with the nail and simply remove the grip frame with the spring under tension. For any hunting handgun, there is little reason to replace the hammer spring; however, a lot of Cowboy Action

wolff
BROWNELLS
PRO-SPRING KIT
RSA-106

Replacement spring kits



The replacement spring (bottom) is shaped different than the factory original spring.

DISASSEMBLE THE GRIP & FRAME

1



1. Tapping the grip screw on a Ruger Vaquero Single Action Handgun to knock the grip loose.

2



2. Punch shows the location of the hole in the hammer spring strut. The pin (or a nail) can be inserted in this hole when the gun is cocked. This keeps the spring in place during disassembly.

3



3. The bottom, right screw on the Ruger Vaquero has an extension that mates with this groove in the hammer pivot pin to lock it in place. Use a stone to smooth the surface of this groove to help ensure a good trigger pull.

Shooting competitors replace the hammer spring with a lighter spring so that the gun will cock easier. There may be a slight tactical advantage in doing that as it will be slightly faster. Also, the gun will be slightly less difficult to cock and so it may prevent a few "missed" cocking cycles. But, a lighter spring risks misfires and for most shooters the factory Ruger hammer spring is probably fine. I have seen springs so light that the competitors have to use not only a specific brand of primer, but even a specific lot of that primer. That seems a bit ridiculous to me. If the gun misfires even once, you will lose more points than a lighter spring will ever gain for you. For what it's worth, I left the factory springs in my Cowboy Action competition guns. I don't think it takes a bit longer to work the action and with the adrenalin flowing as it is in competition, I never notice the difference and my guns go off every time.

If you wish to replace the hammer spring, have all your proper swear words lined up and ready to go, because you will need them. Clamp the mainspring seat in a soft jaw vise and turned so that the side of the hammer strut will show the nail hole when it's inserted. That is so that the flat of the hammer strut will be horizontal. That way the hole will be in a position so that you can insert a punch or nail when the hammer strut exits the mainspring seat. Put the new spring on the hammer strut, pad your hand with a shop rag and push the strut into the mainspring seat as it's held firmly in the vise, compressing the spring as you go. You will need to hold the spring with your off hand to keep it aligned and not twisting and turning. Push the strut in far enough that it exits the mainspring seat enough to allow you to insert the nail in the hole. This keeps the spring compressed. It's pretty simple reading it here, but can be frustratingly difficult to pull off with less than three hands.

When removing the grip frame, be careful not to lose the cylinder stop plunger and spring from the grip frame; or the cylinder hand spring and plunger from the hole in the upper left of the main frame. Use needle nose pliers to unhook the two legs of the trigger return spring from the cross pin in the grip frame. Use the correct size punch to tap out the trigger spring retaining pin and remove the spring. Replace it with the spring from your new kit and replace the retaining pin. Hook the legs of the spring over the cross pin and reassemble the handgun in the reverse order. You will need to push up on the spring arm as you slide the grip frame into place to allow the trigger spring to enter the slot in the back of the trigger. A small screwdriver and the same three hands make this easier. If you have trouble, unhook the legs of the spring from the cross pin until the grip frame is in place, then hook them back on the cross pin to tension the spring.

INSTALLING A NEW HAMMER SPRING





1. Installing a new hammer spring. Hold the mainspring hammer seat in a vise, install the new spring on the hammer strut and push it into the seat until you are able to place a nail or pin through the hole to hold the tension. Note the padding on the hand and the small Allen wrench on the vise ready to be placed in the hole. 2. Punch shows the location of trigger spring pin. This pin is removed to change the trigger return spring.







3. Shows pliers being used to unhook the trigger return spring arms from the cross pin. 4. Using a small punch to knock out the pin that holds the trigger return spring in place on a Ruger Vaquero. 5. The pen points to the groove in the Ruger trigger where the trigger return spring rides. If the surface inside is not smooth, the spring will bind, causing the trigger to pull hard. Use a stone to smooth the surface of this groove to help ensure a good trigger pull.

Usually, this is enough to show considerable improvement in the trigger pull. But if you are still not a pound or two lighter than before, look at where the tab of the spring slides into the trigger. Sometimes this is rough and if it is, you will never attain a proper trigger pull until you fix it. That's because the spring will bind when the trigger is activated. It is rare, but I have encountered this on a couple of Ruger handguns. To correct it, use a thin stone to reach inside this groove and polish the surface that engages the spring. It's far easier if you remove the hammer, which requires taking the rest of the action apart. But if you are planning on working on the action, you will need to take the gun apart anyway.

The trickiest part of disassembling the handgun is removing the trigger/cylinder latch pivot pin. It's locked into the frame by the loading gate spring.You must compress this spring and push the trigger pin out at the same time. Again, it's easier with three hands. Remove the loading gate spring and the cylinder stop. Then remove the trigger by detaching it from the transfer bar. Push out the hammer pivot pin and remove the hammer from the bottom. The cylinder hand should come with it, make note of how they fit together, because it's much easier to remember now than it is to figure it out later. Finally, the transfer bar can be removed.

This is a good time to polish all the contact surfaces on the moving parts. Work very carefully with hard Arkansas stones and a buffing wheel on a hand-held Dremel type grinding tool until they are smooth.Don't remove any metal, just polish and never change the shape, dimension or contour of any part. Be very careful with any edge or corner as it's easy to round them off

REMOVING THE TRIGGER/CYLINDER LATCH PIVOT PIN





1. The trigger/cylinder latch pivot pin is held in place by the loading gate spring. This spring must be compressed for the trigger/cylinder latch pivot to be removed. 2. The groove in the pin is for the spring to lock it in place. Also note the brass punch (from Dillon) used to push out the pin without marring the metal.

3. For the best results, polish all the contact surfaces on the internal parts. This will smooth up the action.

without realizing that you are doing it. All you are doing is polishing off the rough spots on any contact areas, not reshaping any parts. Be sure to polish any moving part that contacts any other part. The smoother they are, the easier they slide. Polish the hammer pivot pin and the trigger/cylinder latch pivot pin. This can be done by clamping them in a drill press and using the polishing wheel on the pin as it rotates. Have the polishing wheel turning in the opposite direction as the pin in the drill press. Then turn it around and do the other end. Again, and this is important, do not remove metal from any part, simply polish what is there. That means only the finest compounds on the polishing wheels and only the finest stones. I even polish the hammer strut and round the edges very slightly so that it slides through the mainspring keeper better. This is the only place I remove any metal or change contours. Then polish the end that fits into the hammer. Look at every single part and see if it moves, or has another part moving against it. If it does, polish the contact surfaces. Also polish anyplace in the frame where a moving part contacts it. A selection of different sizes and shapes of hard Arkansas stones works best for this as they are easier to control than a power tool. But some places are just hard to get at with a stone. Use a hand grinder with a rubber tip that is impregnated with abrasive compound for those places. Finish with a buffing wheel and buffing compound until the area is smooth and bright. Work slowly and very carefully, being certain to not change any angles or remove any metal. The buffing wheels with red buffing compound are pretty safe as they are not all that abrasive, but the impregnated rubber tips from Dremel or Cratex can remove metal, so caution is urged.

Use an oversize chamber mop impregnated with jeweler's rouge to polish the inside of the chambers so that the empty cases will drop out easily.

Put the gun back together in the reverse order. Starting the trigger pin past the loading gate spring is tricky. You must compress the spring as you insert the pin and push the pin past the spring and line it up with the cylinder latch and the frame. With plenty of patience (and a handy third hand) it can be accomplished.

After the gun is fully assembled, check it for function and put a few drops of good lubricating oil on the key parts and you should be done.

Nothing you can do will improve your handgun shooting more than a good trigger job and you will be absolutely amazed at how much better you will shoot. One word of advice, though. Keep it a secret. If your shooting buddies find out you know how to do this, they will all want you to "fix" their guns, too. Then you will be spending all your time in the shop, instead of on the range.

SMOOTHER ENGAGEMENT SURFACE •

Stoning the engagement surfaces of the hammer sear and trigger will help smooth up the trigger pull considerably. This not only lightens the pull weight, but polishing the engagement surfaces also helps to smooth up the trigger pull by eliminating hitches and glitches.

But this is pretty tricky work and if you don't know how, it's best to just leave it alone. Simply changing the springs will usually make a big difference in the trigger pull. It will be better with the engagement surfaces polished, but not enough better to risk a dangerous gun if you do them wrong.

*** ***I would caution you that this is tricky work and is best left to the professionals, and that I cannot take any responsibility for mistakes you make.*** ***

However, if you choose to disregard my advice to hire a professional and are planning to work on the sear, you will need some stones and possibly a jig to keep the alignment. Also, some sort of magnification tool for viewing your work is very handy

The key is to never change the angle, shape or contour of the surface. What you are doing is simply polishing the contact surfaces without removing any more metal than needed to smooth the surface. This is the same concept as the polishing you did on the internal parts, but at a more critical level.

Do not use the felt polishing wheel. They will wear at the edges of the part and cause a slight radius rather than a perfect corner. Because the cloth polishing wheels are flexible, they are difficult to control and a wheel is not the best shape for this job. Select a hard Arkansas stone or one of the new extra fine ceramic stones that will allow you to make contact with the entire surface and to keep the surfaces flat and the edges square. Use only a new stone that is in good shape and not worn. Make sure that it is very flat with square edges. The trigger will require a flat stone, but the hammer may require a knife edge stone so that it has enough clearance on the hammer notch. Use the stone with plenty of oil to smooth and polish the engagement surfaces on the trigger and hammer. Move the stone in a linear motion across the surface. Work slowly and carefully, making sure to check the progress often and to ensure that the stone is making complete contact with the surface. Wipe the oil off the surface each time before doing the visual check so that you are looking at the metal and not an oil coating. It helps to use a magnifying eyepiece to visually check the progress. I often use a 5X to 11X photo loupe to look at the surface. Polish only enough to smooth the surfaces and no further. Hold the part in a vise while you work. Better yet, hold the trigger in a jig such as the Power Custom Inc. Series I Universal Sear Stoning Fixture sold by Brownells. This will keep the trigger and the stone aligned to maintain the correct angle at all times.

When the engagement surface is polished to a glass smooth finish, you are done. Reassemble the gun with the new lighter trigger spring and feel the magic.



By mounting the trigger and hammer on the pins inserted in the side of the revolver frame, you can see how the trigger works. This is an aid in knowing which parts need to be polished to improve the trigger pull.

When working on small parts like this hammer, it's easier to hold it in a vise. This vise is made by Forester and the ball head will pivot to any angle.

This Universal Sear Stoning Fixture is sold by Brownells. It maintains the correct angle when stoning the trigger sear to polish it.



The Ruger Vaquero handgun showing the "after" trigger pull on a Lyman trigger pull scale.

Scope Mounting Made Easy

Gunsmithing Project No. 9

Using a bore sighter inserted in the barrel, this shooter adjusts his scope enough to "get it on paper" before making final adjustments by shooting at a target.

MATERIALS LIST

- Torx head screwdriver
- Loctite
- gun vise
- torque wrench
- file
- aluminum rod
- alignment rods
- ring lapping kit
- soap
- screws

It is so rare to see a rifle in the field without a scope these days that everybody feels compelled to mention it. While working on a book a few yeas ago, I hunted in northern Maine with a Remington 7600 pump action rifle mounted with a Williams peep sight. My choice was entirely intentional and made with good and sound reasoning. I was there to study the art of deer tracking with the legendary Benoit family and because they believe that this setup is the best available for that style of hunting, I wanted to see firsthand if they were indeed correct. The question if they were right paled in comparison to the many times I had to explain why I didn't have a scope on my rifle. Everybody outside of the Benoits' circles that I ran into had to know. It would almost have been easier to have a card printed, so I could hand it to them without needing to explain again verbally.

This only serves to illustrate that scopes are a fixture on today's hunting rifles. One primary factor in how well they will perform is in how they are installed. Improper installation can affect accuracy, reliability and even the life of the scope. Mounting a scope is not all that hard to do it right and with a minimum of tools, anyone who is reasonably handy can can do it on a rifle so that everything works properly. This is one of those projects that works as well on a kitchen table as it does in a fully equipped shop.

As with any job, it is important that you have the correct tools. In years past, a lot of the mounts used Allen head hex screws and many still do. These are an improvement over slotted screws, but they still will strip if too much pressure is applied. The line between a tight screw and a stripped head is pretty fine and care must be taken when tightening this (or any) style of mounting screw. They will require a new wrench with clean, sharp edges that haven't been rounded by previous slippage during use. The cheap throw away wrenches that come with the ring sets are not the best choice, as they tend to be soft and will slip and strip too easily. It's far better to use an Allen head tip with a high quality gunsmithing screwdriver set. These are hardened steel and will not strip when tightening the screws.

The current trend is to use Torx head screws which are much better. These require a special six-point "star" shaped wrench which provides more gripping surface that allows



Remington 7600 Carbine pump in .30-06 with a Williams peep sight. Some hunters, particularly in the Northeast, still cling to iron sights. Certainly it's a personal choice, but any argument that they are faster than scopes for shooting at game lacks credibility.

more power to be applied to the screw without stripping.

Almost all gun work will require screwdrivers for slotted screws and that still includes a lot of scope mounts. Although it's a lot rarer than in the past, many mounts still use slotted screws and to the eyes of some shooters, they are still the most aesthetically pleasing. However, it is imperative that the proper screwdriver be used. The sides of the blade should be either hollow ground or with both sides parallel. Most screwdrivers sold in hardware stores have tapered sides and should never be used for working on guns. A screwdriver must fit exactly in the slot of the screw it is being used on, both in thickness of the slot and in the width of the screw. I cannot stress the importance of this enough. The reason is that a tapered or poor fitting screwdriver will ride out of the slot as pressure is applied and is guaranteed to ruin the screw, probably making it difficult to remove without drilling. Also, the screwdriver can fly off uncontrollably. This is, of course, dangerous as it can easily stab into important body parts. I heard of one poor fella who stabbed his left wrist and hit the artery. He almost bled to death because of using a cheap screwdriver on his scope mount. The screwdriver flying off will also often add custom, although less than artistic, engraving to your rifle as it gouges the wood and metal without discrimination. The first time you do that to one of your favorite rifles, or a gun you just spent a month making pretty, you will feel like slashing your wrists anyway.

A hollow-ground screwdriver will apply pressure to the bottom of the screw slot, rather than at the top as a tapered screwdriver will. This actually helps to "lock" the screwdriver into the screw as opposed to trying to cam it out of the slot like a tapered screwdriver will. A screwdriver that fits properly will fill the slot and have the maximum amount of contact surface inside the slot to distribute the forces being applied. It's amazing how much per-square-inch force is applied by the screwdriver blade. A poorly shaped screwdriver will tend to concentrate the force on the small contact area, which increases the chances of damaging the screw or having the screwdriver slip. Also, a properly fitting screwdriver will distribute the force over a larger area and allow more leverage on the screw. A screwdriver that is turning from the edge of the screw slot will have more leverage, because the force radiates further from the axis, than one that is narrower and is applying pressure closer to the center of the screw. It's simply the physics of a lever in action.

A product that I have found helpful when using screwdrivers or Allen wrenches on a worn screwhead or a stuck screw is called Drive Grip. It has fine abrasive in a gel carrier that when applied to the contact surfaces between the screw and screwdriver or wrench helps in gripping. Another alternative is to use a little powdered rosin to help the tool grip better. Brownells sells powdered rosin for use with barrel vises, but it also has plenty of other applications around the shop.

Another handy tool is a gun vise to hold your rifle while you work. The first time you slip while trying to loosen a stubborn screw and stab your hand or, worse



Tips for three commonly used screwdriver bit types. It is very important to use a screwdriver that fits and has parallel blade sides when working on guns.

Putting Drive Grip on screwdriver.

BROWN
SPORTS OF

Working on guns will require specialized screwdrivers. Kits are available from a lot of different suppliers. These are from Chapman, Brownells, Midway and Lyman.

Adding Loctite to any gun screws is an important step. Make sure you use the kind that allows later removal of the screw.



Tightening a scope ring screw with an Allen wrench.

yet, gouge a chunk out of your rifle, you will agree. There are lots of gun vises on the market for a very reasonable price and every bench where long guns are worked on should have one. I have several in my shop, including one that is in two pieces.

It's a bit of a long story, but it illustrates what not to do with a gun vise. Back in my hungry days I would take any magazine assignment that paid in black ink and whittled a little at the mortgage. They weren't all smart, but the dumbest one I ever said yes to was to test every 12-gauge 3-inch and 3½-inch turkey load on the market in three different guns. It worked out to firing an average of eight shots from each gun with each load and the number of loads seemed limitless.

For those of you not bitten with the turkey hunting addiction, I will note that these things kick. The 3½-inch loads have a recoil level that is equal to an elephant gun when used in firearms of equal weight. The problem is that a turkey gun weighs about two pounds less than most elephant guns, so they actually kick the shooter harder. The other problem is that, following my standard operating procedure, I waited until just before the deadline to start the project, and so had to rush to get it all done. After two long days of shooting at the bench, I was suddenly hit with a wicked headache and found myself vomiting beside the shooting bench. Turns out I had a mild concussion caused by my brain bouncing around inside my skull from the recoil. I had to finish the project, so it was time to get creative. I tried duct taping a 25-pound bag of shot to the barrel, but the tape ripped off in a few shots. I hung the shot bag over the front of the bench from a rope tied to the trigger guard. But that broke the trigger guard after a few shots. (Dumb, I know, but I had the "brain damage" thing going on.) Then I got the bright idea to clamp a Decker wooden gun vise to my bench and lock the shotgun in it. The first couple of shots drove the C-clamp in the back of the gun vise into the recoil pad; in turn, driving the recoil pad into the hollow synthetic stock on the pump shotgun and damaging the buttstock. I fixed the pad and the stock,

ALIGNING A SCOPE BASE

Many scope mounts do not have any way to adjust for windage problems. I recently encountered this when mounting a scope on a new muzzleloader. I didn't have enough scope windage to adjust it using a Leupold Magnetic Bore Sighter. Usually, when this happens I'll double-check with another bore sighter to make certain the problem is with the mounts and not the bore sighter. Sometimes I find that the end of the barrel is not square with the bore and this can affect the reading on magnetic bore sighters that attach to the face of the barrel.

I ran into this problem a while ago with a bolt-action .243 Winchester. The gun was out of production, so I had to modify a newer scope mount. The front base was fine, but the rear base was too thick, so I had to thin the rear base to bring the elevation in line. I thinned the base by working carefully on a belt grinder. I checked the thickness often at several points with a dial caliper (*at left*) to ensure that I was removing metal evenly so that



and then I made a plate to cover the clamp and distribute the recoil forces over the entire recoil pad.

I wasn't concerned with pinpoint accuracy, but only with keeping the pattern on the paper. My finger was taking a beating while pulling the trigger, so I rigged up a string to accomplish that chore. This "poor man's universal receiver-bench test gun" worked pretty well for a while and the testing progressed nicely.

Then it rebelled. I had my portable shooting bench set up in front of the kid's four-foot-deep swimming pool in my yard and after about a dozen more shots, the front part of the cradle stayed clamped to the bench, but the back half, complete with my Browning Gold shotgun, flipped through the air and splashed down dead center in the swimming pool.

The recoil forces had broken the gun vise in the center. When I ordered a new one from Decker, they suggested that I might want to restrict its use to mounting scopes and other gun work. That broken vise stays around as a reminder of the fact they were obviously correct.

Before mounting the scope, you should clean all the screw holes, contact surfaces, screws, rings and bases with a good spray degreaser. Degreasers are nasty, so use them in a well-ventilated area, protect your eyes and wash off any contact with your skin right away. I usually take everything outdoors, if possible, for degreasing. You can also use isopropyl alcohol. I don't think this works quite as well, but it is a lot less offensive. The key is to use a degreaser that dries without any residue, leaving the metal clean.



Torque wrenches made by CDI Torque Products and available from Sinclair International.

Mount the base or bases on the receiver of the rifle, making sure to use the correct screws in the proper holes, as some bases will use different length screws for each of the holes. Leave all the screws loose and then tighten them one at a time, checking to see that the screw will tighten the base until you cannot move it. Then back out that screw and try the next one. This is to ensure that none of the screws are bottoming out instead of clamping the base. At the same time make sure that none of the screws are projecting past the end of the hole. If they are, take them out and recheck that you have the correct length screws in each hole. If you find the screws are placed correctly, grind or file a little off the end. Make sure to carefully round the end of the threads so that they will start into the holes properly. The best way to do this is to chuck the screw in a drill press, and use a hand-held file to shorten and shape the screw. Make sure that the file has a handle installed as it can catch and be thrown by the power of the drill press, and the sharp tapered end designed to fit in the handle can cause serious injuries. This is not as likely to happen with small parts like mount screws but if you get in the habit, sooner or later you will use a file without a

the base was the correct thickness at all points and the bottom was parallel with the top. I finished with emery cloth on a flat surface, polishing the mount over that to ensure that the bottom was perfectly flat. I blued the base with Birchwood Casey Super Blue Liquid Gun Blue and oiled the steel to stop the bluing process and protect it from rust. I shortened some screws to the correct length and installed the base.

It worked perfectly, as far as it went. But after getting the elevation correct, I couldn't get the windage to zero on the bore sighter. I switched to a bore sighter with an internal spud and found that the face of the barrel was not cut square. After adjusting with an internal arbor bore sighter, the gun was less than two inches off at 100 yards when I test fired it. I figured I had the same problem with the muzzleloader. But, I didn't have a bore sighter with a large enough spud and decided to shoot the gun to see what was going on. I discovered that it shot a foot to the left with all the right windage the scope would allow.

The base was a simple two-piece "Weaver" style with the recoil slot in the center. So, I removed the bases and turned them around 180 degrees. Using a bore sighter, I was able to get it back on the paper. I was now able to sight in the rifle and the scope was much closer to the center of adjustment. Either the receiver, or one, or both of the mount bases had been drilled off center.

Try every combination you can think of before giving up. Something as simple as reversing a scope base solved what at first appeared to be a big problem.

Using a one-inch aluminum rod to turn in a dovetail front ring. Inset: It is a good idea to add lubricant to any dovetail rings before installation.

ALUMINUM ROD ALIGNMENT







1. Using a one-inch aluminum rod to check the alignment of the two scope rings. 2. Sleeved scope alignment rods for use on 30mm as well as one-inch rings from Brownells. Note that by lining up the points, the rings are in alignment with each other. 3. Using a Sinclair International lapping tool to lap the rings. Note the lapping compound in the small white container.

handle on a bigger part and be wondering why it's sticking through your arm. Be safe, use a file handle.

Put a drop of Loctite on each screw before installation. I prefer the blue #242 because it allows the screws to be removed later. Once you are sure all the screws will tighten the base properly, go ahead and snug them up. Move from front to back or back to front so that the screws will draw the base down smoothly and firmly. Apply torque until all the screws are tight. This requires a balance and a certain feel. The screws must be tight, but you need to be careful not to strip or break them. Some sources recommend tapping the screwdriver with a hammer as you tighten the screw, but many now discourage this practice and I have found it unnecessary.

Leupold recommends that 6-48 screws in a ring or base be tightened to 18 inch-pounds and 8-40 screws be tightened to 28 inch-pounds.

Chapman says that with their screwdriver's relatively small handle and full hand pressure, most men will achieve 17 to 50 inch-pounds. With the thumb and first two fingers, most will apply 10 to 17 inch-pounds. But that is subjective at best. I can apply a lot more torque with this method than my son can and we are both pretty much grown men. I just outweigh him by about 60 pounds. The only true measure of how much you are tightening a screw is a torque wrench.

A torque wrench has the capability of reading how much torque you are applying to any bolt or screw. I used a big half-inch drive torque wrench for years when working on engines. For example, the torque applied to cylinder head bolts was important to ensure that the engine worked correctly, particularly on some of the high performance racing engines we were building. The same principle would apply to working on guns, particularly in mounting scopes, but on a smaller scale.

Recently, I have been using two torque wrenches made by CDI Torque Products and available from Sinclair International. One is The Adjustable Plastic Handle Micrometer Torque Wrench. It looks like a long handle ratchet wrench for use with socket wrenches. This ¼-inch drive torque wrench is designed for action screws and the like. It has a range of 30.0 inch-pounds to 150.0 inch-pounds. This puts it above the range needed for most scope mounting operations. It is, however, useful for a lot of other gunsmithing applications.

The smaller model is the Micrometer Adjustable Torque Screwdriver. This is designed for scope mounts and rings. It uses a screwdriver type handle and will accept any of the common screwdriver, Torx or Allen style bits. This tool has a range of 8.0 inch-pounds to 50.0 inch-pounds, which is perfect for scope mounting.

Brownells Rosin

Dykem Layout Fluid

It shocked me when first using this precision tool by just how much I have been overtightening my base and ring screws all these years. These torque wrenches will really open your eyes to the mistakes you have been making and they will ensure that you don't continue to make them in the future. They are expensive and I recognize that most hobby gunsmiths will never buy one. That's probably OK; I mounted hundreds of scopes before I got mine. However, they do make for a better end result and will help to educate you a great deal on how much is too much when it comes to these small screws, so if you can afford one I would consider it money well spent.

Over-torqued screws can cause all kinds of problems, like broken screws or stripped threads. Also, stripped sockets for the wrench in Allen or Torx head screws. Also, twisting the ring screws too tight can damage the scope. It can result in bent or dented scope tubes and misaligned internal parts. The adjustments may not work correctly in a scope that has the tube distorted, making it impossible to sight in or in some cases to retain zero. It's a fine line between getting it tight enough so that things stay in place and so tight that things break. The best way to do this is with a torque wrench. That's not to say you absolutely need one to mount scopes on guns. Like I said before, thousands are mounted every year by people who have never heard of a torque wrench. But, for the very best job and for an eye-opening look at how much torque is correct, a torque wrench is the only answer.

In years past when mounting scopes on heavy recoiling firearms, I often would use a film of Loctite 242 between the base and the receiver as well as on the screws. This helps to fill in the gaps and provide a full contact area to aid in preventing slipping. But it would still allow the rings or bases to be removed. However, the Loctite is very difficult to remove from the rings, bases, rifle or scope. Because of this difficulty of removing the Loctite, if I want to reuse the rings, bases, rifle or scopes again, I find that I am more cautious about applying this practice. (I can deal with occasionally trashing a scope base or a set of rings, but the rifles were getting expensive.)

One alternative is to use powdered rosin on the rings to aid in gripping. I have only tried it a few times, but so far the results with some very hard recoiling rifles are promising and this might be a better alternative. I questioned Larry Weeks at Brownells about that practice and he said that a lot of gunsmiths use powdered rosin on the rings with good results. However, for the vast majority of scope installations I do these days I use nothing for a grip enhancer. I simply lap the rings for good contact and tighten them correctly. I can't remember the last time a scope slipped after doing this. That includes heavy recoiling guns as well as the pipsqueaks.

After tightening all the base screws, clean all excess Loctite off the rings and bases. Don't forget to clean inside the action where the screw holes come through as the Loctite can drip through and cause problems if it's not cleaned up.

Now mount the rings on the bases. On dovetail turn-

Bryce Towsley takes aim with a Knight Revolution ML while hunting whitetails in South Dakota in 2004.

C6289150
Rem

An extension ring

in type rings, add a bit more lubricating grease to the dovetail before installing the ring. Never use the scope to turn the ring into place. Instead use a one-inch aluminum or steel rod or a Leupold Ring Wrench. If you use a rod, always have the top of the ring screwed on before you apply torque to avoid springing the bottom section of ring, causing it to misalign with the top. If this happens, you will have trouble starting the screws and the ring won't fit the scope correctly.

Use the one-inch aluminum rod to make sure that both rings are aligned properly before installing the scope. If you can lay the rod in the rings and turn and slide it back and forth without any of the edges or corners shaving or dragging and the rod lies on the bottom of both rings, you have them properly aligned.

Better still, buy a set of scope alignment rods from Brownells or Wheeler Engineering sold by Midway. These are pointed on one end and after mounting one in each ring, you adjust the rings until the points are in perfect alignment with each other.



After you have the rings in alignment, it is a good idea to lap them. Due to variances in manufacturing the rings, bases and gun receivers, there can be some subtle differences between the front and rear rings. Lapping eliminates those differences and brings all the surfaces to the same plane. This improves the mounting job and adds to the gripping surface, which can be important for hard recoiling guns. Lapping works best with steel rings. Aluminum is soft enough that it can wear away too fast and it can imbed the abrasive grit from the lapping compound and scratch your scope.

Brownells, Midway and Sinclair International all offer ring lapping kits. They are simple to use. Coat the one-inch steel lapping rod with compound and place it in both rings on the base only with the top removed. If you are lapping 30mm rings you will need a lapping rod of the correct diameter for that size ring. The rod must be exactly the same diameter as the scope body.

Lapping works best with horizontally split rings that have a top and bottom. The rings that split vertically can be lapped, but not easily and some designs do not work well with any approach to lapping. An inquiry to Warne reported that they do not recommend lapping their rings at all.

Move the lapping tool back and forth while rotating slightly and applying downward pressure. Check often to see how much of the ring is being lapped and stop when you have at least 75 percent contact on both ring bases. More contact is better, but 100 percent is all but impossible and you do not want to remove so much metal that the ring is too big. If that happens, you can sometimes file a little off the contact shoulders of the rings to allow them to close a little tighter. However, this will only work for a slight adjustment. Usually, rings that are opened up too far will require replacement, because they are too big and are no longer round. So, work carefully and check your progress often.

It's easy to tell if you are getting enough contact on blued rings as the shiny metal will indicate where lapping has taken place. On stainless steel rings it is not as apparent. Before starting lapping on these rings, coat the surface with Dykem layout fluid. This will abrade away on the high spots, showing the contact surface as shiny. Or you can do the same with a felt-tip marker by coloring the ring surface.

The Reticle Leveler in use. This clever device makes aligning the crosshairs during a scope installation much easier.



The view using a bore sighter to adjust the scope enough to "get it on the paper."

Most sources say that it is not necessary to lap the tops of the rings, as they are springy enough to compensate for slight misalignment. However, I do usually like to break the edges with a round fine India stone. This will remove any "cutting edge" and help to lessen the chance of marring the scope while moving it inside the rings for final positioning. I simply put a slight radius on the edges of the rings, paying particular attention to the corner where the rings split.

After completing lapping, clean the rings to remove any lapping compound. If any is left in place, the abrasive will make adjusting the position of the scope in the rings difficult and it can scratch the surface of the scope tube.

Place the scope in the rings and tighten the screws until there is a little drag on the scope but it can still be moved. Keep the rings evenly tightened so that the gap between the top and bottom ring is equal on each side.

Adjust the scope forward and back until the eye relief is correct for you. With a variable scope, make certain that you check it at both ends of the power spectrum. To check, hold the rifle in a natural shooting position while looking through the scope. Move your head forward until you start to see a black ring around the outside edge of the scope's field of view. Make a mental note of where your head is located on the gun's stock. Now move your head back slowly until the ring disappears and continue moving back until the ring reappears. Make a mental note of that position. The ideal "eye relief" is halfway in between. It often takes a couple of trips up and down the stock to find exactly the right spot.

The ideal scope position is when your head is in the natural position for shooting and it is exactly halfway between the two spots the scope starts to black out. Obviously, you move the scope forward or back to adjust for that. If the center of the eye relief is too far forward, move the scope back. If it's too far to the rear, move the scope forward. Remember to check eye relief when dressed in hunting clothes. Setting the eye relief in a T-shirt and then trying to shoot a buck next hunting season while bundled up in several layers of thick clothing may bring some surprises and allow the buck to die of old age.

Sometimes there simply isn't enough room to move the scope without hitting the rings with the objective, power ring or adjustment turret. The answer is an extension ring. This is a ring that is offset with an extension so that the ring can be farther in front of or behind the base. This allows more latitude for adjusting for eye relief. Extension rings are also handy when the gun has a short receiver that puts the scope bases too close together or a long receiver where they are too far apart for the scope you want to mount.

Perhaps the most difficult part of mounting a rifle scope is aligning the crosshairs. The vertical crosshair should be in line with the axis of the bore, but on a huge number of rifles that I look at, it's tilted. This can make it difficult to properly sight in your rifle and can even affect your shooting in the field. The Reticle Leveler from Segway Industries solves that problem. It's one of those "why didn't I think of that?" gadgets. It indexes to a flat surface, usually on the scope mount base, and allows alignment of the crosshairs with the bore. It is remarkably easy to use and surprisingly accurate. However, this tool will not work with all guns or mounts. It must have a flat surface that is square with the bore to index off. Sometimes the mounts are too compact and there is no surface to index off. I have also run into guns on which the holes for the mounts or the receiver itself is off center, causing the scope bases to tilt slightly. But, in the vast majority of installations the Reticle Leveler works great.

To use it, put the two halves together in place and place them on a flat surface close to the rear of the scope. A rubber band hooks on either side and runs underneath the gun to keep tension on the tool. Look through the scope and use your peripheral vision to see the relationship between the scopes' horizontal crosshair and the lines on the Reticle Leveler. Any misalignment will be instantly apparent and can be corrected by turning the scope in the rings.

Another tool that works very well with most rifles is



The rear base is for windage. Note the damage caused to the screw by using an improper screwdriver.



Wheeler Engineering Level-Level-Level being used to square scope crosshairs.

Using the Level-Level-Level to align an aimpoint red dot sight.

the Wheeler Engineering Level-Level-Level (Hey, I don't name them, I just report on how they work). This tool uses a magnetically attached level that indexes off the bolt rails in the action. Another level is placed on the top adjustment cap on the scope. When both are reading perfectly level, the scope is in alignment with the bore. It works very well, but will not fit on some rifles because of the action design.

There are several other theories about how to make sure the scope is square to the bore by visually checking the horizontal crosshair. I do it by looking through the scope at a white wall as I hold the rifle, being careful to not cant the gun. I also check to see that the vertical crosshair is centered on the barrel or receiver. I recheck this several times to make sure I am not inadvertently twisting the gun. Another method is to place the gun in a gun vise and step back, away and behind the rifle. You can't see through the scope, but if you get the angle just right, you can see the crosshairs. Visually check to see if the vertical crosshair is aligned with the centerline of the butt plate.

When the crosshairs are aligned correctly, tighten the ring screws in an alternate pattern, left to right and front to back.

When you cleaned and degreased the mounts, you left the metal without protection; so now is a good time to spray the rings and bases with a metal preservative or oil to prevent rusting. Be careful not to get any on the lenses, as you don't want any oil on the optics.

I have used this method of installing scopes on rifles up to .458 Winchester without a single problem. However, in really hard kicking rifles (yes, there are some with more recoil than the .458 Winchester!) you might consider epoxy on the bases and epoxy, rosin or another grip enhancer on the rings. Just remember that epoxy is pretty permanent; you can remove it with heat but that's difficult and tricky when you have optics involved. Too much heat and your scope can be damaged.

Boresighting can be accomplished by clamping the rifle, minus the bolt, in your gun vise and sighting through the bore at a distant object and then without moving the rifle make the adjustments by turning the scope adjustments until the crosshairs are aimed at the same object. A much easier way, in fact the only way for rifles such as lever actions that don't allow you to look through the breech, is to use a commercial bore sighter. Many use an arbor that fits in the bore, but a few years back Leupold brought out a bore sighter that has a magnet to attach it to the front of the barrel. One downside is that it had to be pointed at something bright

SCOPE SHIMS

In years past, you often needed to shim scope bases to make them fit correctly. That was because manufacturing tolerances were a lot more "loosely interpreted" and one receiver might not be the same as the next. Because of computer controlled machines, today's guns and scope bases are so well made that this is almost a thing of the past. But, once in a while you will encounter a mount that needs a shim. The shim must be metal and steel is best. Never use cardboard or wood. The traditional way is to make a shim which takes a lot of time and never works out the way you had hoped.

BROWNELLS
SCOPE SHIM KIT
STEEL SHIM ASSORTMENT

Another approach is to use a pre-made shim. Brownells has a kit called the Brownells Scope Shim Kit. The kit contains 10 blued steel shims for each of the various hole spacings and thicknesses—a total of 80 shims. They are .600-inch and .860-inch center-to-center hole spacing. The thickness is .006 inch, .008 inch, .010 inch, .012 inch. The shims are sold individually in packs of 10 each.

The holes are large enough to allow some shifting for alignment and even if there is not an exact shim to fit your specific need, these are easy to modify.

If you install a shim, you may need to replace the screw with a longer one to make up the distance. This is particularly important on the blind holes on the front of most receivers. They are not all that deep to start

to work best. But that model was recently replaced by an updated version with an internal light. These are fast and accurate if the muzzle is square with the bore. I have run into some guns where the muzzle is not cut square and that skewed the readings. In that situation I simply got out my old bore sighter with the arbors that fit in the bore and that took care of business.

If you do not have enough adjustment in the scope to boresight, then the mounts must be moved. Vertical adjustments can be made by placing a shim under the front or rear base as needed. Horizontal adjustment is easiest with the "Redfield JR" type of mount that captures the rear ring with two screws. This style of mount is sold by many other mount manufacturers, including Leupold. Simply loosen one screw and tighten the other to move the rear ring left or right. The front ring is in a dovetail that can pivot slightly to keep the scope from becoming twisted. If you are not using this type of base and do not have enough horizontal adjustment, you now have a problem. Try switching the rings and if possible the bases. Also try turning them around. Often, there can be a slight misalignment that self-corrects with a different position. If the misalignment is so bad that nothing works, switch to a scope mounting system that allows horizontal adjustments.

The goal is to have the scope's adjustments close to the center of their range when the gun is boresighted. To find the center of the adjustment range, turn the adjustment screw in one direction until it stops. Now turn it back in the opposite direction until it stops again, making sure to count the turns. Go back in the opposite direction again to exactly half the number of turns it took to go from stop to stop and that's the halfway point. Try to get as close to that as possible, both vertically and horizontally when the gun is boresighted.

Just remember though, boresighting is only to "get you on the paper." You must shoot the rifle to completely sight in the rifle.

If you follow these simple instructions, you should have years of trouble free service from your scope and rifle.

And a lot fewer questions to answer.

Bryce Towsley with a caribou taken in Manitoba with a Knight .52 caliber muzzleloader.

with and because the front base absorbs most of the recoil forces, it's important that the screw fit all the way to the bottom so that every available thread is utilized. A few thousands of an inch probably won't matter, but if the base required multiple shims for a thick shim pack, you will need a new screw.

Fitting the screw will probably require cutting off a long screw and grinding it for a perfect fit. The easiest way to cut it off is with a pair of electrician's wire strippers with a screw shortening capability. The final fit should be done by carefully grinding off a little at a time and trying the screw until it firmly locks the base in place, without bottoming out in the screw hole.

Chuck the screw in a drill press and work it carefully with a file. File a small amount off the bottom of the screw, round the bottom edge slightly to permit it to start in the threads and try the screw. If it's too long, the base will be loose after the screw is tightened. The screw is hitting the bottom of the hole and not the base. With through holes, you can see the screw protruding below the surface of the action. If it's too long, remove the screw and take a little more off the end. When the screw firmly locks the base to the receiver or is flush with the receiver in a through hole, you are done.

With front screws, I try to have a slight relief between the screw and the bottom of the hole after the screw is tight. To check, coat the bottom of the screw with Dykem and tighten it with the base in place. If the Dykem indicates that the screw is contacting the bottom of the hole, take a few more thousandths of an inch off the end and try it again. When the Dykem is not marked, there is no contact between the screw and the bottom of the hole.

Cutting Off a Barrel

Gunsmithing Project No. 10

Measuring and marking a barrel in preparation for cutting it off. Note that a quarter inch is left to make up for a cut that is not square.



MATERIALS LIST

- felt marker
- hacksaw
- muzzle facing/ chamfering tool
- drill
- chuck adapter
- stop collar system
- muzzle radius cutter

I remember several things in my life that were hard to get started. Like jumping off a high bridge into the river, back when I was ten years old. I stood with shaking knees through several false starts. But after my buddies jumped, I couldn't chicken out, and I finally dove into the thin air and made the long drop to the cool water. Throwing a punch at the school bully took some determination. He was bigger than me, liked to fight, and was dead set on fighting with me. I had most of the fourth grade watching, so I couldn't chicken out. That would have hurt more than a bloody nose. The first time I flew a hang glider required more courage than I thought I had, but we had a couple of good-looking girls watching, so not doing it was never an option. However, when I recently took a hacksaw to cut off my new Douglas rifle barrel, it might have been harder than all those things combined.

A hacksaw? On a brand-new, top quality rifle barrel?



Shortening a rifle barrel with a hacksaw.

Isn't that against the laws of man? Or at the very least a venial sin? It was pretty scary to think of the consequences if things went wrong. With that other stuff, my bruises would heal over time, but a ruined barrel is forever. On top of that, I didn't have any audience for this and I seriously considered chickening out. But who on earth would build a .358 Winchester rifle with a 26-inch barrel? It had to be done and this was the only way, so I took a deep breath, closed my eyes and pushed on the hacksaw to start the cut.

End of a rifle barrel after cutting it off with a hacksaw. Note below how it is uneven.



Yes, I know professional gunsmiths take the barrel off the action and chuck it in a lathe to shorten it. But if you don't have a lathe, there is another way. One with results that are just as good, and in fact it's a way that I think is a lot easier. Removing a barrel from the action is hard work and it runs the risk of a marred finish from the barrel slipping in the barrel vise or the action in the action wrench. Avoiding it altogether is a rather inviting alternative.

There are lots of reasons to cut off a rifle barrel. In this case, I wanted a new deer rifle in one of my favorite cartridges. I have been a fan of 35-caliber rifles for most of my hunting career and I have used most of them at one time or another in the hunting fields. I learned decades ago that the .358 Winchester is one of the best woods cartridges for deer and black bear ever conceived. I have had a couple of them over the years, but currently found that my gun vault had a serious deficit of rifles in that chambering. I suffered the pains of withdrawal for as long as I could bear, and then caved in to the urges. I decided the only cure would be a new bolt-action rifle in .358 Winchester well before deer season opened. Because the .358 Winchester is no longer offered in any bolt-action rifles, I decided to build one of my own. I ordered one of the new Remington Model 700 SPS rifles in .308 Winchester and removed the barrel before firing a shot. After stripping the action and sandblasting it in preparation for a new DuraCoat finish, I fitted a short chambered Douglas .358 Winchester barrel that I ordered through Brownells. These barrels come "full length," which is 26 inches, with the expectations that they will be cut to the desired length. In this case, I wanted a short and handy rifle for hunting in the thick brush, and I wanted it to be just a little bit different. So, I cut the barrel off to 21 inches.

Of course, building a rifle is just one of many reasons you may wish to cut off a rifle barrel. Perhaps there is crown damage and you need to remove the end section. Or perhaps you simply want a shorter barrel on your rifle. It's also a way to enhance accuracy. For years Browning engineers knew that if a rifle was returned with accuracy complaints and nothing else worked, if they cut a little off the barrel the accuracy was often improved. That knowledge led to the BOSS system that allows the "length" of the barrel to be adjusted by moving a threaded weight in or out on the end of the barrel. So, if you have a gun that's not shooting as well as it should, before you install a new barrel or trade it to somebody you don't like, it's worth a try to cut half an inch off at a time to see if the accuracy improves.

No matter what the motivation, this is an easy project with the right tools. There is no need to remove the barrel from the action. Remove the bolt and mark where you will be cutting the barrel. Then run a tight plug of cleaning patch material into the bore, leaving it a few inches from where you will be cutting. This will prevent chips from traveling down the barrel and into the action.

Once you know how long you want the barrel, clamp it in a vise with soft jaws and start "hacking" with a hacksaw. Try to keep the cut as straight and square as possible, but don't worry if it's not perfect and trust me, it won't be.

Once again, it's Brownells to the rescue. You will need a 90-degree muzzle facing cutter, larger than the diameter of the barrel's muzzle and a pilot to fit the bore of the rifle you are working on. The pilots are offered in steel or brass. I chose brass simply because I think there is less chance

Brownells' 90-degree muzzle facing cutter and Brownells Muzzle Facing/Chamfering Tool Stop Collar System block.



of damage to the rifle's bore. The cutter comes with a T-handle to turn it and you can certainly use that to do the job. But, it's much easier and faster to buy the Muzzle Facing/Crowning Cutter Drill Chuck Adapter. Long name, amazing results. This little inexpensive adapter allows you to chuck the cutting tool in a hand-held drill. This makes things go much faster and easier. Simply turn the drill to its lowest RPM setting, and remember to use plenty of cutting oil. The cutter will soon have the face of the barrel a perfect 90 degrees to the bore. But, be careful as this cutter works fast and you can shorten your barrel more than you planned if you are not paying attention.



Rifle barrel muzzle after facing it off with a Brownells' 90-degree muzzle facing cutter.

One problem with doing this job without a lathe is that the cutter has a tendency to chatter. The cutter blades then tend to follow the contours of the chatter, which deepens the valleys and makes it worse. Once that starts, it becomes all but impossible to correct while using the cutter either by hand or in the drill.

Chatter creates marks in a regular pattern that appear on the cutting surface of the barrel as the muzzle is chamfered or faced. Chatter is a low frequency vibration that may be initiated by hard or soft spots in the steel, causing a cutter flute to dig in or bounce. It can also be caused by uneven pressure on the cutter against the barrel. With a lathe, it's easy to control the pressure on the cutter and the depth it can cut, but when you are hand holding the cutter, that level of control becomes almost impossible.

The answer is the Brownells Muzzle Facing/Chamfering Tool Stop Collar System, which is a long way to say this is a stop that will control the depth the cutter can travel. When this system is used, the cutter is physically blocked from continuing to cut in the low areas caused by chatter, so any high spots will be cut down until the entire surface is even.

The Stop Collar System is made of steel and consists of an adjustable ring to surround the cutter and a stop clamp for the barrel. Two different tools allow using either a cutter that is larger than the barrel or one that is smaller than the diameter of the barrel. Simply loosen the adjustment and move the stop until the gap is set for the desired depth of cut.

Cut until the Stop Collar touches either the muzzle or

Brownells Muzzle Radius Cutter in drill. Finished rifle muzzle.

the Stop Blocks, depending on your setup. Make sure you frequently clean all metal chips from the cutter and the bore because they can accumulate quickly and can cause scoring of the barrel. Each time the cutter and pilot are removed from the barrel, clean the muzzle, bore, cutter and pilot and check for chatter marks. If they start to develop, don't worry! When the face of the Stop Collar reaches the face of the barrel or the rim of the Stop Collar reaches the Stop Blocks, simply continue cutting until the chatter marks are removed. Always turn the cutter in a clockwise direction. Reversing the cut will roll the edges of the blades and ruin them.

Now switch the 90-degree cutter to one designed for cutting the crown. My choice on the .358 Winchester was a 79-degree cutter that was slightly smaller than the diameter of the barrel, which gave me a recessed crown. The 79-degree cutter is designed for what is commonly called an 11-degree crown, which is considered very good for accuracy. (The name is a result of 90 degrees, or the angle between the bore and the muzzle, minus 11 degrees equals 79 degrees.) Again, I adjusted the stop for the depth I wanted and ran the cutter until all the chatter marks were gone.

Finally, a radius on the outside edge of the muzzle gives the barrel a "finished" look and removes the sharp edge. For that I used a Brownells Muzzle Radius Cutter, designed to put the finishing touch on the barrel crowning job. This tool removes the sharp outside edge that remains after shortening a barrel or cutting a new crown with a cutter wider than the barrel. The cutter comes in three sizes and each cutter covers a range of diameters. Simply order the one with the diameter range that your barrel falls into. Chuck this cutter in the hand drill and make a few turns on the end of the barrel until the desired effect is achieved and you are done.

Obviously, the barrel is now raw steel. You can leave it like that, which is a good approach with stainless steel. Or if it's carbon steel, you can refinish it with cold blue. In my case I was applying DuraCoat to the entire barreled action anyway, so the finish, or lack of it, was not a problem.

One key to exceptional accuracy is a good crown that is perfectly square to the bore. My .358 Winchester was shooting minute of angle groups the first trip to the shooting range. I guess I can live with that, and I doubt a barrel cut off and crowned on a lathe would do any better.

Left: Brownells 79° crown cutter being used in drill to add a radius to the outside of the barrel's muzzle. The finished muzzle is shown above.

Remington
BARNES
CR-10
Midway
SHOOTER'S VISE

Cleaning & Maintenance

Chapter 3

This Mauser .30-06 for years was thought to be a mediocre shooter at best. But a proper cleaning of the bore brought out its accuracy.

In my family, my grandfather was really the only avid shooter. Others hunted and owned guns, but he was the one who built his life around them.

In our blue-collar, lower middle-class, small-town world his was an awe-inspiring collection. While he favored old lever-action Winchester rifles and well-balanced side-by-side shotguns, his collection pretty much ran the category from odd and unusual to modern and common.

One of the nicer rifles was a .30-06 Mauser sporter with a half-octagon barrel, a full rib and a front sight ramp all milled from a single piece of steel. It was always a source of Gramp's pride but every time he showed the rifle, he felt compelled to mention that it never shot as well as he liked.

Like most of his guns, it was sold to a famous baseball player after he died more than two decades ago. I thought I had seen that rifle for the last time when they took it out the door of Gramp's suddenly hollow and empty house. The collection was cherry-picked and some of it was sold off. The better pieces like this Mauser went to private collectors and were not offered for sale to the public, while others were sold to dealers. It was heartbreaking to see some of Gramp's guns show up on the tables at gun shows over the next several years. Even more so, given that my financial status at the time prevented me from doing anything more than looking at them. A few years ago my uncle Butch was able to buy the Mauser from the man who had owned it for the last 18 years. He brought it to me soon after when he was having some trouble with cases sticking in the chamber. We cleaned up the gunk that was the problem and at the same time I kept the rifle for a few days and properly cleaned the bore, which proved to be badly clogged with two generations of metal fouling. It took me two days of scrubbing to get all the gunk out of the rifle, but with that small change it's now an amazingly accurate rifle. It wasn't that the rifle was inherently inaccurate, it was just dirty!

Gramp started shooting in the early days of smokeless powder and was "old school" in much of what he believed. Because they favored low velocity cartridges that didn't foul much, once noncorrosive priming was introduced he and many others of his generation thought that a gun barrel did not need to be cleaned often. "More guns are ruined by cleaning than are by shooting" was the conventional wisdom heard often around the deer camps of his time, and they were probably right. Bad technique, poor cleaning rods and soft steel in the old barrels led to spoiled rifles and a propensity not to clean.

Today we know better.

Got Accuracy Problems? Clean the Bore

Cleaning the bore correctly and often is the key to a correct rifle break-in.

It might seem odd to have a chapter on gun cleaning in a book on gunsmithing. But more than just about anything else you can do to a rifle, knowing how to clean it correctly will restore and maintain accuracy. If you do not know how to do this, nothing else you will do to your rifle will make it accurate.

If you want your rifle to perform to its ability, you must clean it properly and often. Many of today's shooters get the "often" part right, but fail badly on the "properly" side of the equation. With today's "bigger-better-faster" trend in cartridge design coupled with parallel trend for better terminal performance bullets, this has never been more important. Just because you made a couple of swipes with a patch down the barrel doesn't mean you have the rifle clean. You must remove all metal and powder fouling to call a bore "clean."

I suspect that a lot of barrels that were replaced as "shot out" in years past simply needed a good cleaning. In my grandfather's time they didn't have the super solvents that we have today and removing metal fouling was difficult. I have long suspected that the .220 Swift's reputation as a barrel burner was more likely because it was a barrel fouler. Sure it would burn out a barrel quicker than other cartridges of that era; this was a cartridge that was topping 4,000 fps in an era when 3,000 fps was still awe inspiring. When it was introduced in 1935 it was the hottest thing around and that performance always comes with a price. But, they didn't have the bullet materials or the powders that we have today and I suspect that the metal fouling was horrendous. Without the means or the knowledge to properly clean that



Starting a patch using the Bore Tech Patch Guide in the bore of a .358 UMT rifle. These bore guides are inserted through a rifle's receiver after removing the bolt. They keep the cleaning rod aligned with the bore while protecting the action from dripping solvent. They also make it easier to start a patch.

BARNES
TRIPLE-SHOCK X-BULLET
50 BULLETS
35824
35cal. 358dia.
225 GR
FLAT BASE

Barnes Triple Shock bullets are one example of the new generation of high-tech bullets.

BARNES
50 BULLETS
35825
35cal. 358dia.
225GR "XFB"
COATED

This three-shot, 100-yard group was fired with a .358 UMT and Barnes VLC X-Bullets. For the best accuracy from any rifle, you need the bore clean.

fouling from the bore, I am guessing a lot of poor shooting barrels were labeled as "shot out" and replaced. The label "barrel burner" stuck and the Swift never recovered from the bad publicity. It ruined the Swift's reputation and all but killed the cartridge in the marketplace. It's funny that when the .22-250 was introduced by Remington as a factory cartridge 30 years later, it had similar ballistics, but wasn't labeled a "barrel burner." That was probably due in part to advancements in barrel metallurgy and propellant technology. But, also in great part to better bullets and far better cleaning solvents. Today the Swift has seen a small comeback and I don't hear anybody complaining that it shoots out barrels faster than any other high performance varmint cartridge. I have owned three and have not seen any premature barrel failure from any of them.

The high velocity of today's rifles comes at a price and the currency is pressure and heat. When a bullet is accelerated to three or four thousand feet per second in two feet or less of barrel, you know there is some serious "stuff" going on inside. Modern cartridges generate as much as 65,000 pounds per square inch of pressure. That pressure is developed by burning powder which creates rapidly expanding gasses. This process also generates a tremendous amount of heat. The heat, combined with the expanding gasses, is like a blow-torch in the barrel, pushing on the bullet and everything else. Also consider the friction that is generated as the bullet is reshaped to fit the rifling and then is pushed at an extremely high rate of acceleration down the barrel. It's a wonder we don't simply melt down the bullets in the barrel!

Today's high velocity big game cartridges not only drive a bullet very fast down the barrel, but they also demand a lot when that bullet contacts the target. The bullet makers have responded with "super" bullets that expand over a wide range of impact velocity and still retain weight for penetration. Many of them are made from material that is more prone to metal-foul the bore than more "common" bullets. The problem is compounded when we practice shooting with gilding metal jacketed bullets and then switch to copper jacketed bullets for hunting. Gilding metal is harder than the copper and the fouling in the rifle barrel actually will "weld" with the softer copper as it passes by, greatly escalating the speed of fouling. The only answer is to completely clean the bore after every shooting session and always before switching bullet types.

When I have a rifle come into my shop that is having accuracy problems, the very first thing I do to it is clean the bore completely. More often than not that will correct the problem, just as it did with my grandfather's old Mauser. However, even if it does not fix the problem, it will eliminate one more possibility in the checklist of what is causing the accuracy trouble.

Many shooters run a few patches through the bore and maybe make a pass or two with a brush and assume that they have cleaned the rifle. But, the truth is that a fouled bore is tough and time consuming to clean properly and because fouling is cumulative, each time that you fail to clean properly, the fouling left behind is added to the collection and the problem is compounded and grows over the weeks, months or years. If you shoot 20 rounds, but only clean enough to remove the fouling from eight rounds, and then do this repeatedly, after a dozen shooting sessions you have the accumulated fouling from 144 rounds. It's no wonder the gun is not shooting accurately. The only solution is to completely clean the bore to the bare metal, each time.

Running a few patches with some solvent through the barrel is not enough. You must clean the barrel down to bare steel and remove all powder and metal fouling each time you clean. If you can accomplish that with a few patches, fine, but it doesn't happen often. I have a custom rifle with a Krieger Barrel that is that easy to clean. In spite of the fact it is chambered for an extreme wildcat, the .358 UMT, which pushes a 35-caliber 250-grain bullet to more than 3,100 fps, the bore on this gun is so good that it rarely fouls and when it does it's very easy to clean. But, that's at one very lonely end of the spectrum. Most rifle barrels, particularly factory guns, are somewhere closer to the other end of the bell curve, and they will take more effort to clean. I can't say how many patches or how many swipes of the brush will be required to clean any specific rifle, nobody can. What I can give you is some guidelines on how to do it correctly and how to tell when you are done.

A PLACE TO WORK • You must have a solid surface like a workbench or a table and it's always best to hold the rifle in a cradle or gun vise of some sort. There are lots of commercial rifle cleaning cradles and gun vises on the market. Having one on your workbench will be money well spent.

The chemicals used for cleaning guns are powerful and nasty. How could they not be, they are designed to dissolve metal fouling. Do you really think that warm milk would do the job? When you clean your guns, take measures to not ingest or absorb these solvents. Make sure that you have good ventilation. Keep a supply of latex or, better still, vinyl gloves to wear. Some gun cleaning chemicals will damage latex, but vinyl seems immune to more of them. Safety glasses or goggles are a good idea. I can tell you from painful experience that the aggressive copper eating solvents we use on a rifle bore are not pleasant to have in your eyes. Another smart product would be a shop apron to keep the mess off your clothes. You will need lots of shop rags and I always keep a roll of shop grade paper towels on a hanger above the bench. Wipe up spills and when you finish put all the rags and used patches in a sealed container like a Ziploc™ bag before putting them in the trash. Keep a large trash can close to the bench with a contractor's grade liner bag. That allows you to keep the mess to a minimum and to tie up the bag at the end of your session to help trap the fumes from the solvents.

A very handy product is the Patch Hog made by Bore Tech and sold by Brownells. One end screws onto a half-gallon plastic soda bottle and the other end slips over the muzzle of the gun. One size fits all, even over the front sights. The bottle catches the patches and when it's full, you simply unscrew it, put a cap on the bottle and dispose of it. It eliminates solvent dripping on the bench and the need to pick up those crud-covered patches. It also helps to contain the fumes. When using a brush, the bristles will "spring" forward as they exit the bore and this sprays solvent all over everything, but with the Patch Hog, it's all contained in the bottle. No mess. It's a great product.

THE ROD • Cleaning rod wear, caused by the rod excessively contacting the rifling, particularly at the crown, is one source of barrel damage. It's what led to the common idea in Gramp's time that cleaning was a bad idea. This is particularly true when a cheap aluminum rod is used to clean from the muzzle. Soft aluminum rods pick up and imbed grit to become, in essence, a file that grinds away at the muzzle crown.

The best cleaning rods are one piece. Jointed rods

Tipton
Bore Solvent
Tipton
INSTA-CLEAN
WD-40

A good, well-equipped place to work can make gun cleaning chores a lot easier. Note the wide variety of chemicals used for cleaning and maintaining guns.

Some of the options on cleaning rods include hard steel or plastic-coated rods.

Left: You can never have too many cleaning rods. A high quality rod that fits the bore of the gun you are working on will make the job easier and help protect the gun.

have more flex and the joints provide potential areas for embedded particles or sharp edges which can harm barrels. There are two schools of thought concerning the design of one-piece rods: some like hardened steel rods, while other shooters prefer plastic coated rods. The theory is that a hard steel rod will not embed grit and become a "file." Other shooters prefer a coated rod because it's soft enough not to damage the bore and will not imbed particles as easily as aluminum. There is also a theory that as a rod flexes inside the bore, it continuously hits the edge of the lands on the rifling. The theory is that a steel rod will continuously hit the barrel at the flex point and "peen" the rifling as it pushes the patch through, while a coated rod provides some protection against that. If a steel rod is damaged, it can develop a burr that can damage a rifle bore. For what it's worth, most serious shooters I know use coated rods. More recently, graphite rods have become popular. They are soft like coated rods, have less propensity to embedding grit than aluminum and they are relatively inexpensive.

The rod should also fit relatively snugly in the rifle bore. Forget "all-purpose" cleaning kits and buy a rod specific to each bore diameter. The cost is small compared to the benefits it will bring.

Wipe the rod clean of solvent and debris often during the cleaning process. Keeping the rod clean preserves its useful life and also helps reduce the chance of bore damage.

GUIDES • If possible, always clean from the breech and use a rod guide. This is a tool that inserts into the action after you remove the bolt. It will fit into the chamber and extend out past the back of the action. This provides a pipeline from the front of the gun to the bore. The best guides not only keep the rod aligned with the bore, but also protect the action from dripping solvent and crud. Trying to keep a patch lined up on the jag as you push it through the action can be frustrating enough to make a grown man cry, and one other big asset of a bore guide is it will also make it much easier to start a patch.

Some rifles such as semi-auto, lever-action or pump-actions must be cleaned from the muzzle. A big danger here is cleaning rod wear. Years ago I traded a shotgun I didn't like for a Winchester Model 94 carbine in .44 Magnum. The guy who owned the Winchester had taken the gun apart and could not figure out how to get it back together, which put me in a good bargaining position. I put all the parts back in place, but the darn thing never shot all that well. A careful examination and a few questions to the former owner revealed that he had been very exuberant about cleaning the gun. The rifling was damaged and worn on one side of the muzzle from an aluminum cleaning rod constantly rubbing on it.

It is important in any "clean from the muzzle" situation to use a muzzle guide to align the rod with the bore and to protect the delicate crown from cleaning rod wear. A muzzle guide is a cone-shaped piece of plastic or brass with a hole through the center. The cone is inserted into the

ROD GUIDES



A selection of bore guides. These bore guides are inserted through a rifle's receiver after removing the bolt. They keep the cleaning rod aligned with the bore while protecting the action from dripping solvent. They also make it easier to start a patch.



Shows starting a patch, using Bore Tech Patch Guide.

These muzzle guards fit into the rifle's bore and align the cleaning rod with the bore, preventing it from contacting the crown and causing damage.

With rifles that must be cleaned from the muzzle like this Marlin 1895, it's a good idea to place the gun upside down and put a rag in the action to catch the solvent. A gun vise will make cleaning any rifle much easier.

muzzle and the rod is run through the hole in the center. The guide keeps the rod centered in the bore so it will not contact the muzzle and cause wear or damage. The downside of a muzzle guide is that the hole is usually rod size and so you can't push a patch through it. The guide stays on the rod and the patch must be started into the bore without the use of the rod guide. This is a window of vulnerability when crown damage can occur, so extreme care is needed when starting the patch. Once the patch is a few inches down the bore, the muzzle rod guide can be slid down the rod and put in place on the muzzle.

Turn these rifles upside down in the cradle so that the solvent will not run down into the action parts. Put a rag in the action to catch the crud you push out of the barrel.

PATCHES, JAGS AND BRUSHES • Select the largest patch that fits in the bore with your jag. The patch should fit snug, but not so tight as to be difficult to push down the barrel, as a tight patch will wring the solvent off the patch. When I find a patch that fits well for a rifle that I shoot a lot, I buy a bunch of them. I prefer cotton, but buy whatever is on sale. To clean a rifle right, you will use a lot of patches and trying to extend their life by using them more than once is false economy, although I will admit to using both sides of the patch, particularly early in the cleaning process. I will run the patch down the bore, then flip it over so the other side contacts the bore and run it through again. But as I get closer to the goal of a clean rifle bore, the final patches are used only once and only on one side.

Brushes should be bronze for most cleaning chores. Most nylon brushes do not have the scrubbing ability and stainless steel can gall and ruin the barrel very quickly.

Although nylon brushes are handy when scrubbing with very aggressive copper-eating solvents, because these solvents will destroy a bronze brush quickly, but do not affect nylon. With any brush, I usually buy one size larger than my bore size. I make it a practice to never reverse a brush while it's in the bore. Some say it won't damage the bore; I am not willing to take that chance. I run the brush the full length of the barrel until it exits before reversing direction. Brass cores in the brushes are better than steel, as steel can damage the bore.

There are a lot of theories about jag design, some of them are practical and some border on esoteric. Mine is simple and pragmatic. The jag should fit the bore snugly with the patch you are using and it should hold the patch securely. I prefer brass and I don't trust stainless steel, although I'll admit that I use them quite often. I want a jag that is made of a material softer than my rifle bore so that it will not scratch or damage it. I am not sure that stainless steel is soft enough. When used correctly, it shouldn't contact the bore anyway, but why chance it? Plastic jags work, but are not very durable. Slotted patch holders are just about useless for cleaning the bore. However, an oversize one is useful for holding a big patch to wipe out the action, chamber and the bolt lug recesses.

You will also need a good action cleaning tool to wipe the crud out of the bolt recesses. Dewey has a good one, as does Midway USA. These are short rods with a device on the end to hold a cotton swab. The tool is used to turn the swab in the action to remove any solvent or crud from the bolt locking recesses.

SOLVENTS • Solvents are the key to cleaning a rifle and it's there that we have made so much progress in the past couple of generations. Today's advanced chemistry is far better than my grandfather's generation had. I remember he told me that they used to put mercury into a barrel to remove metal fouling. Today we have chemicals that are much safer and more effective.

I would divide them into three categories. General use, aggressive copper removers and those that split the difference. The last category are the solvents that

RIFLE & HANDGUN BORE CLEANING SOLVENT
BARNES
CR-10
FOR REMOVING ALL COPPER, BRASS & LEAD FOULING
CAUTION: KEEP OUT OF REACH OF CHILDREN EYE IRRITANT
8 FL. OZ.

Barnes CR-10 Bore Cleaning Solvent. This is a very aggressive copper removing cleaner.

PATCHES, JAGS AND BRUSHES

MONTANA X-TREME

A selection of cleaning patches.

A selection of cleaning tips. A jag should fit the rod and rifle bore properly. Bronze brushes are best and should be a snug fit in the bore. Slotted patch holders are helpful for wiping out a wet bore or cleaning the chamber but are not good for bore cleaning.

Tipton
12-Piece Brass Cleaning Jag Set

Tipton Jag Kit with Tipton Carbon Fiber cleaning rod.

Cleaning solvents

Hoppe's Elite System

Tipton cleaning products

combine general powder solvent cleaning abilities with more aggressive copper removal.

TECHNIQUE #1

TYPE "A" AGGRESSIVE CLEANING • Start cleaning the bore with a general bore solvent, making several passes through with a new wet patch each time. It's best to use each patch for only one pass before replacing it with a new solvent soaked patch, but I do sometimes use both sides of the patch at this stage of cleaning. Don't scrub, but instead push the patch straight through the bore. You may want to let the gun soak a few minutes between patches to allow the solvent to work.

Leaving the barrel wet with solvent, use a properly fitted brush dipped in and soaked with solvent to make several passes. Keep the brush wet with solvent, reapplying after every couple of passes. Don't dip the brush in the solvent bottle, as this will contaminate the remaining solvent. Instead, put some solvent in a long, thin container like a test tube and dip in that. Use the leftover solvent on the patches; do not put it back in the bottle. I keep a Dixie cup with solvent near me as I clean and I put several patches at a time in to soak.

Don't reverse the brush in the bore; instead, push it all the way out of the muzzle then pull it back through. Always use a bore guide or muzzle guide to keep the brush centered at all times, as the steel core of the brush can gall the barrel.

After use, always clean the solvent from your brush with a degreasing spray. This is to prevent abrasive debris from accumulating and also because some solvents will eat the bronze bristles.

Let the gun sit for a few minutes to allow the solvent to work, and then follow with one wet and several dry patches to remove all traces of solvent. Now pass a patch soaked with copper removing solvent through the bore. Be sure to read the instructions on the label. Most recommend that they not be left in the bore for more than 15 minutes. Let the bore soak for a few minutes and follow with another patch wet with copper solvent followed by a dry patch. Then repeat. The goal is to have no blue or green stains on your patches, indicating that there is no remaining metal fouling. Remember, though, that a brass jag can leave a "false" stain on the patch, although it's usually on the inside rather than the outside of the patch, so it's easy to distinguish from stains from bore fouling. When in doubt, use a plastic or stainless steel jag. When you have patches coming out with no trace of green or blue (it may take a while if the fouling is extensive), dry the bore with several clean patches.

Scrub the bore again with the general solvent, using



The progression of color on cleaning patches. Keep cleaning until the patches come out of the rifle with no blue or green stains.

patches and brushes. Then dry and repeat the copper solvent treatment. Sometimes, metal fouling can be trapped under layers of baked-on powder fouling that you must remove to allow the copper solvent to get at the metal fouling. Keep repeating this process until you have no sign of blue or green on any patches. If you let the solvent work for five minutes before you push a patch down the bore and the patch is the same color coming out as it was going in, your rifle is clean. If there are any stains on the patch, you still have work to do.

Outers
Foul Out III
Outers
Cop Out PLUS+
COPPER REMOVAL SOLUTION
Outers Foul Out III

TECHNIQUE #2

THE "LAID-BACK APPROACH" • Because my workshop is close to my office, I use this technique quite often. I choose a solvent that is more aggressive than the general solvents on copper removal, but has a manufacturer's recommendation that it can be left for an extended time in the bore.

As before, I pass several patches that are wet with solvent through the bore. Then I scrub it with a wet brush, reapplying the solvent to the brush often so that the bore is well saturated.

Then I remove my rubber gloves, wash my hands and return to work. An hour or so later I run a few patches wet with solvent through the bore followed by a couple of dry patches. Then I repeat the process, using the brushes and patches. The crud that the solvent will loosen during this extended soaking is sometimes amazing. If the gun is not clean at the end of the day, I will let the solvent work overnight. A badly fouled bore may take a few days to clean, but in the end it's less work because I am giving the solvent more time to dissolve the crud.

TECHNIQUE #3

ELECTRONICS • If you clean a lot of guns, particularly guns with badly fouled bores, electronics can do the work for you. The Outers Foul Out Electronic cleaner is a device that uses an electric current to activate a reverse plating process. This removes the fouling from the bore and deposits it on a metal rod, speeding up the cleaning process a great deal. The system is not terribly expensive and anybody with several guns and an interest in shooting should have one.

First clean the bore with a general solvent and dry it with several patches. Then degrease the bore down to bare metal, using patches impregnated with a good degreasing solution that dries without leaving a residue.

Plug the barrel at the breech with the rubber plug supplied with the Foul Out system and fill the bore with the proper solvent. There is one for lead removal and one for copper removal. Insert the metal rod with the rubber O-rings in place to isolate it from the barrel, and then hook up the Foul Out cleaner according to the instructions. After it has cycled through and is indicating "clean," dry the bore. Now clean with a general solvent again to scrub out baked-on powder fouling that might be hiding metal fouling underneath. Degrease and repeat with the Foul Out. Usually, one or two times is enough, but I once had a .338 Winchester that I cycled through thirteen times before the bore was clean. This renegade rifle was shooting three-inch plus groups and I was about to trade it, but after cleaning it started behaving again and I decided to let it stay in my gun room.

J-B NON-EMBEDDING BORE CLEANING COMPOUND

• Another method that is preferred by a lot of precision shooters is to use J-B Non-Embedding Bore Cleaning Compound, available from Brownells. This is a slightly abrasive cleaner that will help to remove tough deposits of fouling. Clean the gun with solvent and brushes following the steps listed above. Then dry the bore and run several patches that are wet with Kroil through the bore. Wet another tight fitting patch and smear it well with the J-B Compound. Do this on a jag or use a slightly undersize brush with the patch over top of it. Run this through the bore, scrubbing, using short strokes of three to four inches. Stroke back and forth about ten times before moving down a few inches and repeating until exiting the muzzle. Clean the bore with solvent and patches and repeat.

If the rifle has been used with moly coated bullets, this is the best way to clean the bore. Moly may coat the bore and is all but impossible to remove with conventional cleaning approaches. However, J-B Compound will remove the moly, although it may take a while.

J-B Bore Bright acts as a cleaner and a final polish. Finishing up with that product used the same way will help

J-B Non-Embedding Bore Cleaning Compound, J-B Bore Bright and Kroil shown with a patch wrapped around a brush coated with Bore Bright.

Despite what a lot of "gun guys" say, I have had good luck with WD-40 for short-term protection of firearms. This is particularly true on this Ruger's case-hardened frame where other "metal protection" products have failed.

to polish and condition the bore. Be careful when cleaning gas-operated semi-auto firearms, as the compound can creep into the gas ports and cause problems if it's not cleaned out before firing the gun.

FINISHING UP • Finally, after cleaning with any of the above techniques, dry the bore with several clean patches and apply a rust protector by running several saturated patches down the barrel. Wait a minute or two, then run one loose fitting dry patch through to remove the excess. This will leave just enough rust preventive to protect the bore. Be sure to run a tight fitting dry patch through the bore before shooting the rifle to wipe out any residual lubricant/protector. Do not let any lubricant accumulate in the chamber, as the brass needs to be able to grip the chamber walls when the gun is fired. Lightly wipe the chamber down with rust preventive, and then dry it with an oversize patch.

Before shooting, wipe the chamber with an oversize patch with a degreaser. If you are hunting with the rifle in foul weather, skip the degreasing in the chamber and wipe it out with dry patch, but leave a thin film of rust preventive. Then run a single dry patch through the barrel to remove any residual rust preventive. This will leave a very slight film of lubricant on the bore to ease the first bullet through.

Often, the first shot may be off from the group (usually high), so a fouling shot is not a bad idea before hunting or competing. With most guns, the bullet will still hit very close to the zero and it's probably not a big deal, particularly when hunting. However, some guns are different. I had one Remington Model 788 in .243 Winchester that would not even hit the target if there was any oil in the bore. It was one of the most accurate rifles I ever owned, except for that one little idiosyncrasy. When I was young and opportunities for deer were painfully scarce, not knowing about it cost me a whitetail buck. I never hunted with that rifle again without firing a fouling shot. In fact, the lesson is so painful and ingrained that even today I rarely hunt with any firearm without firing a fouling shot.

Use an action cleaning tool to wipe out the bolt recesses. The action and/or bolt should be taken apart and cleaned every now and then. But, a quick-clean approach can be used by spraying with a good aerosol spray degreaser designed for use on gun parts. Work outdoors and with safety glasses or better yet, a face shield, rubber gloves and a respirator or painting mask. Hold the parts over a bucket to collect the run-off for proper disposal. Spray all the parts, letting the liquid run off so that it flushes the grease away. Work at stubborn deposits with an old toothbrush that is saturated with the degreaser. Direct the spray into all the little nooks and crannies until you have all the parts clean and free of any buildup. After the degreaser dries, the metal is chemically clean and is subject to rusting very quickly. Coat every surface with a combination protector/lubricant, making absolutely sure that the manufacturer guarantees it for use in extreme cold. If it doesn't say it works to at least −30 degrees, don't use it. The old standby is dry lubricant like graphite, which still works fine, except it provides little, if any, rust protection.

Also use the degreasing spray to clean the action of the rifle, including the bolt lug raceways. Do not attempt to take your trigger apart, but instead spray the trigger assembly from every possible angle and direct the spray into every hole and opening. Let the liquid flush away all the dirt and grease. After it dries, lightly spray a protector/lubricator, then shake out and wipe up any excess.

At least one premium trigger manufacturer recommends that the trigger be flushed with lighter fluid, the same stuff used to fill a Zippo lighter. Let it drain and



Dewey Action Cleaning Tool

dry. The lighter fluid will not only clean and degrease, but after drying it will leave just the right amount of lubricant in the trigger.

The outside metal of the gun should be sprayed with a good protector and then wiped clean, leaving a thin film. Clean the scope optics with lens cleaning paper and fluid available from any camera store. I prefer the Kodak soft brand of paper and avoid the stiff, hard kind that is often sold in camera stores. Use an optics brush to wipe away any dust or dirt. Then crumple up a lens cleaning paper into a loose ball. Put a couple of drops of fluid on the paper; never put the fluid directly on the lens. Then, gently wipe the glass in a circular motion. Crumple another paper and use it dry, to very gently wipe the lens dry. The coatings on the optics are delicate, so only use optical quality paper and fluid and be gentle.

If the stock is wood, I like to wet a shop cloth with a little linseed oil and wipe the stock down. This helps to hide any small scratches and the smell of linseed oil just goes great with rifles. A synthetic stock should be wiped free from any solvent. If it's dirty, clean it with a household spray cleaner. Use a shop towel and not paper towels, as they will leave lint behind.

The first step to gun repair is maintenance. This ensures that anything else you do will have the gun operating at peak performance.

I think that if Gramp had lived to see the super solvents and electronics of today, he might have had to change the dialogue when he showed that Mauser to a visitor.

A SIX-PACK OF CLEANING TIPS



1. **Always clean a rifle as soon as possible after using it. The longer you leave the barrel dirty, the higher the potential for corrosion damaging the bore.**
2. **Use modern solvents that remove copper and powder fouling and keep cleaning until you have patches coming out without blue or green stains, indicating all fouling has been removed.**
3. **Always clean from the breech if possible, using a bore guide. If you must clean from the muzzle, use a rod guide to protect the crown from damage, and catch the crud coming out at the breech so it doesn't get into the action.**
4. **Before storing a rifle for any length of time, or after cleaning, always use a protectant on the bore and other exposed metal surfaces to prevent rust. If it's going to be stored for a long time, coat the metal with RIG grease.**
5. **Before firing, always wipe the bore clean with a patch to remove any excessive residual oil. But don't make it chemically clean by wetting the patch with a degreaser. Instead, use a dry patch so that a microscopic film of lubricant is left in the bore to protect it from the first bullet's passage.**
6. **Fire a fouling shot before hunting. Some rifles will shoot to a different point of aim with a clean bore than they do from a fouled bore. This is particularly true when there are traces of oil or other protectants in the bore.**

Preparing Your Rifle for Extreme Weather Hunting

Rifles must be prepped to work under harsh conditions like this winter muskox hunt north of the Arctic Circle. Wind chills were nearly seventy below zero.

Although the wind was blowing very hard through this remote Alaska Peninsula river valley, the mountain I was looking at provided a clue to just how sheltered it really was here on the river. Near the top of the mountain a rain swollen stream ran over a cliff to form what should have been a waterfall. Instead, the wind was blowing the water back up the mountain and off the top like a geyser.

Later, when we exited the river and started across the unsheltered saltwater bay, we were hit with the full force of that wind and realized we were in trouble. The flat-bottomed jet boat was designed to run in shallow rivers, not wind-pounded seas. On the other hand, *The Queen Mary* might have had trouble in this water. The bay was a mass of foam and wind-whipped spray for as far as the eye could see, making the "Perfect Storm" seem like a few ripples.

For what felt like hours, we pounded on through this maelstrom with the water cascading over us in sheets with every wave we hit. It stopped being fun a long time before it occurred to me that we could die here. Finally, we admitted defeat and turned to the near shore. We made our way behind a finger of land that protected part of the bay enough to reach shore without smashing on the rocks. From there, we walked to a derelict cabin where we would spend a long, wet and cold night. Everything, including my custom Bansner rifle, was soaked with salt water, but there was nothing to be done to clean or dry any of it until we could get back to our camp. Clearly that would not happen on this night.

This was my third hunting trip to Alaska in as many years, and every one of them has been an endurance test for me and my rifles. It rains just about all the time and much of the hunting has been from tent camps where drying gear is but a wistful dream. It's a harsh environment to take a rifle into. But then, so are most places game is hunted.

In almost forty years of big game hunting, I have also used rifles in bitter cold, raging snowstorms, relentless sleet and blistering heat. I have hunted in the winter above the Arctic Circle where the wind chills were gusting to nearly seventy below zero Fahrenheit. We were living in a small tent with no floor other than a few caribou hides. It was so crowded that my rifle had to stay outside in the sled. At the other extreme, I hunted in the Zambezi River Valley of Zimbabwe in October when the temperatures were hitting more than 110 degrees Fahrenheit. Or another time hunting on the Yucatán peninsula in southern Mexico in May, when it was just as hot and a lot more humid.



Bryce Towsley took this Alaskan moose with a Marlin Model 1895M Guide Gun firing .450 Marlin.

I do seem to recall one hunting trip in all those years when it wasn't cold, raining, snowing, sleeting, hot, windy or humid. We didn't see or shoot a damn thing. The truth is, hunting almost always exposes you and your gun to some of the harshest conditions possible.

While I have witnessed several, I have personally never had a weather related functional failure when the time came to shoot. I'll be the first to admit that some of that is luck, but a lot is because I think ahead. The key to keeping your rifle operating and/or keeping it from turning into a rusted, decrepit junker is in preparation. Preparing a gun for foul weather is a simple, but important, project for a hobby gunsmith.

The strategy in keeping a hunting rifle functioning and pretty is in recognizing the enemy. Weather-directed attacks generally come in two forms: temperature and moisture. Address these issues and you have most potential problems under control.

In repelling the ravages of moisture, the first step is in selecting the materials used for your rifle. Hunting rifles might be better approached with a pragmatic design rather than picking a gun for its aesthetics. Extreme hunting is really not the place for fine walnut and highly polished metal. These make for a wonderful looking rifle, but they rarely stay pretty for long. A smart hunter considers function over form in choosing a rifle.

Henry Ford was quoted as saying that the American buyer could have his car in any color they wanted, as long as it was black. That same variety of options applied for years to rifle stocks; a hunter could have any material he wanted as long as it was wood. The problem with wood in extreme weather is that it can absorb water and change dimensionally. We have all seen that when our screen door sticks during a humid spell in the summer. It sticks because the wood fibers have swollen from the water they absorbed. It's an annoyance when it happens to a door, but can be a disaster when it's a rifle stock. The metal to wood fit in a rifle is critical to how well a rifle functions. Bedding, which is the way the action and barrel mate to the wood, is important to accuracy and, in extreme examples, to function. The bedding may be perfect during a hot, dry summer day but a week of hunting in the rain will change the moisture content of the wood. This can lead to point of impact changes, accuracy problems and sometimes rifles that no longer work.

I love to read the work of the early gun writers and much of it is filled with tales of rifle stocks that caused problems after being exposed to harsh weather. In one story the rifle was unusable until they chopped the stock away with a hatchet! But today we rarely hear about this happening, for a couple of reasons. First is that most serious hunters who know they are going to be out and about in harsh weather use rifles with synthetic or laminated wood stocks. Both of these are resistant to absorbing water. Synthetic simply doesn't do it and the laminated wood is impregnated with a resin that seals the fibers.

Still, a lot of hunters use rifles with "plain ol' wood" stocks today and report few problems. The reason is simple enough: the coatings used for finishing the wood today are much better at repelling water than those used in the "olden days." Back then they used a lot of oil finishes

Ruger M-77 MK II SS

WEATHER AND MOISTURE



Applying thinned polyurethane.

Sealing all exposed wood.

Applying paste wax.

that looked and smelled great, but didn't provide a barrier protection against moisture entering the wood. Today, we have high-tech finishes that seal the wood against moisture entering. However, the gunmakers cut corners in the places you can't see. Any wood stock should be removed from the rifle and sealed in all the hidden uncoated areas that many gunmakers skip.

Use a good grade of polyurethane and thin it according to the instructions on the can. Coat all the unfinished surfaces evenly with a thin coat. That includes the barrel channel, action and along the sides of the magazine well. Also remove the butt pad and grip cap and coat the end grain of the stock. The wood should absorb the thinned polyurethane. Allow it to dry and apply another coat. Continue until it is no longer absorbed. Finish with a single coat of uncut polyurethane in the areas that have a critical tolerance, such as where the action is bedded. The barrel channel and butt end where tolerances are less critical can get another coat or two. Make sure you have sealed every exposed wood surface. If water can't reach the wood, it can't be absorbed.

Or better yet, put the pretty wood stock in the closet until after hunting season and replace it with an aftermarket synthetic stock. Fit and glass bed it as detailed elsewhere in this book and you have a weatherproof, perfectly fitted rifle stock. After the hunting season is over, put the pretty wood back on the rifle.

The other problem that water can create is plain old-fashioned rust on any or all ferrous metal parts, including stainless steel. When the conditions are extreme and you do not always have the ability to properly care for your rifle, stainless steel has a bigger insurance policy in its greater resistance to rust and corrosion than does carbon steel, but stainless steel can rust. Both will stay rustproof if you can keep them protected with a barrier agent that keeps the water away from the metal, but that's not always possible. For hunters spending a lot of time in wet weather, one option is to have the metal permanently coated with a protecting agent. One very good option is DuraCoat, which is explained in another chapter. If you like the looks of your rifle, you can apply the clear DuraCoat which will maintain the appearance of the rifle, but provide a permanent protective barrier to the metal. Just remember that the bore and some internal and/or action parts are not coated, so they need other protective steps.

The concept with DuraCoat is basically the same as how oil protects your rifle, by creating a barrier between the water and the steel. The difference is that unlike oil or other chemicals, the coatings are permanent. You can change the color of the rifle, or put on a clear coat that only protects the gun, but either way adds material.



Spraying degreaser into a rifle trigger to clean and remove oil.

If the label doesn't say a lubricant is rated for cold weather use, do not use it on your rifle.



Wide Temperature Range
−95°F to +450°F
Non Flammable · Prevents Corrosion
Will not attract dirt, dust or lint
Displaces water

Directions for use:
Hold can upright. Use in well ventilated area. Spray away from body by depressing red button on top. Point arrow on button towards object to be sprayed and away from face. Do not spray into wind.

Keep can 10 to 12 inches from object to be sprayed. By rotating button so that arrow

The other option is a chemical coating of some sort. The problem is oil or other coatings wear off rather quickly. Some of the new hightech waterproofing agents actually penetrate into the pores of the metal, which makes their protection last longer, but they, too, will wear off over time and with use.

The outside of a rifle can be covered with paste wax, which is said to last longer than oil or spray-on water barriers. This is particularly useful for areas of metal that are hidden by the stock, such as the underside of the receiver and barrel. These are always problem areas when using the rifle for extended periods in extreme weather. Applied protections often do not last for long, but a layer of paste wax will last through most hunting trips. However, it should not be used on any internal parts; instead, use a spray-on protector from a company that specializes in gun care products. Don't forget the chamber and bore of the rifle. Caution must be used here not to have a buildup or too thick a layer, as that can affect performance and perhaps even create a dangerous situation. Coat the surface with a rust protector, wait a few minutes and then wipe it off. In extreme weather, you should reapply daily. Even on backcountry hunts I take a small multi-section rod, a few patches and a small bottle of metal protector and lubricant. I try to tend to my rifle every evening. (Except, of course, those where I am stranded in the bush with no heat, no food and little shelter, as was the case in Alaska!)

Extreme cold presents another set of problems that must be dealt with in the shop before the hunting season. Cold can cause oil or grease in a firearm to gel up and prevent the gun from firing. I have seen congealed oil and grease inside a bolt stop the firing pin from moving or slow it down enough to cause misfires several times when the temperatures approached zero Fahrenheit. I have also seen a buildup of oil, grease and dirt make a trigger inoperable in cold weather.

Any rifle you will be using in cold weather should be completely degreased and relubricated with a product designed for use in extreme cold. Disassemble the bolt and/or action. If you have a parts cleaning tank, soak the parts well and use a brush to remove all dirt, oil or grease. Then dry with shop air and repeat.

When the gun is free from grease, gunk and dirt buildup, spray with a no-residue aerosol degreaser and let it run off to remove all traces of solvent. If you do not have a parts cleaning tank, use a good aerosol spray degreaser designed for use on gun parts. Work outdoors and with safety glasses, rubber gloves and a painting mask. Hold the parts over a bucket to collect the runoff for proper disposal. Spray all the parts, letting the liquid run off so that it flushes the grease away. Work at stubborn deposits with an old toothbrush that is saturated with the degreaser. Direct the spray into all the little nooks and crannies until you have all the parts clean and free of any buildup. After they dry, the metal is chemically clean and it is subject to rusting very quickly, so immediately coat every surface with a combination protector/lubricant, making absolutely sure that the manufacturer guarantees it for use in extreme cold. If it doesn't say it works to at least −30 degrees, don't use it. The old standby is dry lubricant like graphite, which still works fine for lubrication, but provides little, if any, rust protection.

Also use the degreasing spray to clean the action of the rifle, including the bolt lug raceways. Do not attempt to take your trigger apart, but instead spray the trigger assembly from every possible angle and direct the spray into every hole and opening. Let the liquid flush away all the dirt and grease. After it dries, lightly spray a protector/lubricator, then shake out and wipe up any excess.

Finally, realizing that while these steps will help ensure that your rifle functions in extreme weather, resign yourself to the fact that a hunting rifle is going to show some use and is not going to look showroom pretty forever. You can keep it working, but the finish is going to carry the evidence of hard use. It's a badge of experience, show it with pride.

If you are going to hunt where the weather is harsh and unpredictable, prepare your rifle, but also bring a space blanket and a pocketful of granola bars. As I know all too well from experience, they may be what "gets you through the night."

LEUPOLD
BROWNELLS, Inc
MONTEZUMA, IOWA

Enhancing Accuracy

Chapter 4

Coni Brooks testing BarnesVarminATor bullets from a bench. Coni and her husband Randy own Barnes Bullets.

A common problem that a hobby gunsmith must deal with is poor rifle accuracy. Many of our projects are intended to increase the inherent accuracy of a rifle, but we are often called on to fix a gun that is suddenly not shooting as it should. These rifles gone rogue are both perplexing and aggravating, but a simple step-by-step approach can help eliminate the problem. Think of any rogue rifle as a puzzle to be solved by following a logical plan in a linear, step-by-step manner. First, keep it sensible. If it's not your rifle, take it out and shoot it. More often than not, accuracy problems are really shooter problems. Also, make sure you keep it all in perspective. Rifle design and cartridge selection will dictate the inherent accuracy of any rifle. It is unreasonable to expect that a lever action deer rifle will shoot as well as a bolt-action varmint rig. Nor should we expect a .30-30 Winchester to shoot as accurately as a 6mm PPC. Certain cartridges have a lot more inherent accuracy than others.

If you are dealing with a new rifle or one that you are working on for somebody else, experiment to determine what load the rifle likes best. If that doesn't correct the problem, try the following. Clean the bore down to bare metal and remove all fouling. Next, check all of the screws to be sure they are tight. Remove them one at a time and if any are loose, apply Loctite before replacing. Remove the stock to look inside and near the screw holes for cracks. If its' still not shooting accurately replace the scope.

If nothing changes, examine the bedding, particularly on a wood-stocked rifle where humidity can cause changes. Synthetic stocks can fail as well, especially the cheaper injection-molded types. You can sometimes detect bedding problems by holding the action at the junction of the metal and wood and alternately loosening and tightening the action screws. You should be able to feel unwanted movement that you can't see.

Another common bedding problem occurs when the stock contacts the barrel improperly. To check for adequate clearance with floating barrels, wrap a dollar bill around the barrel with the ends pointing up and slide it along between the barrel and the stock. It should pass easily for the length of the barrel, unless the rifle has a hard contact near the forend. Any drag or sticking indicates that the stock may be contacting the barrel and affecting accuracy. Removing material from the offending area will usually correct this problem. Bedding-induced accuracy problems can usually be easily corrected by glass- or pillar-bedding the action and floating the barrel.

Finally, if you still can't make it shoot and there are no obvious defects, consider a new barrel, the old one might be shot out or is just no good. Or maybe it's simply a rifle that needs to be traded.

But usually when you have done these things, the rifle will shoot much better and poor accuracy is no longer an excuse for missing, so you will need to find a new one.

The wind works for me.

Re-Crown a Rifle Muzzle

Eddie Stevenson checking zero in Argentina.

"Only accurate rifles are interesting."

—Col. Townsend Whelen

I can't say I agree with the good Colonel on this because I have had some poor shooting rifles that were damn interesting. But I will concede that accurate rifles are a lot less aggravating.

If you have accuracy problems with a gun and load that has always shot well and has suddenly gone sour, my advice is to take these steps. First, clean the bore until all copper fouling is removed. This can take an unbelievable amount of time and work to get it right. But in about half the cases, it will fix the accuracy problem. When somebody brings a rifle to my shop that's not shooting well, the first thing I do is clean the bore. Most of them will argue with me and say, "I already cleaned the gun and you are wasting your time." I wonder why they brought the gun to me in the first place if they already know more than I do about the problem. But, I don't argue. I just clean the gun and if it's shooting accurately again, I don't even tell them what I did. I just let them think I am a miracle worker.

Next, check that all screws are tight and that the stock has not cracked or warped. Still not shooting? Replace the scope. If it's still not back to its former accuracy potential, re-crown the barrel.

The crown is the point in the muzzle that is at the end of the barrel. It's the last place that the rifle has any physical influence on the bullet and it is critical that it be perfect. The crown must be perfectly square with the bore, perfectly round and free from any defects. Even the slightest imperfection can impact the bullet as it exits the barrel and have an adverse affect on accuracy. One of the major rifle makers in the country told me that when a rifle comes in for repair with a poor accuracy complaint and no obvious defect is found, the first thing they do is re-crown the muzzle. In a surprising number of cases that corrects the problem.

I have seen a lot of poor crowns right from the factory.



These tools are used to reface the end of the barrel and to recut the crown. Left to right: 45-degree muzzle crown cutter, brass muzzle crowning lap, 90-degree muzzle facing cutter and brass pilot. Lapping compound and cutting oil.

I have one .45-70 rifle that had a big ding in the crown when I received the rifle. It would only shoot into about three inches at 100 yards. I re-crowned the barrel and now it groups at half that. A lot more rifle crowns have become damaged in the field. It only takes a moment of inattention to set the muzzle down on a jagged rock and the damage is done. But, the best way I know to ruin a rifle crown is by riding in the truck with the muzzle of the rifle down on the floorboard. The collected dirt and sand on the floor is abrasive and it grinds away at the delicate edges of the crown. If you must have the gun pointing down in a vehicle, at least protect the muzzle with something to keep it out of the dirt.



Brownells Brass Muzzle Crowning Lap on rifle barrel.



Brownells Chamfering & Facing Combo Set with pilots and cutters for crowning and facing barrels.

The simplest way to correct minor crown damage is with an inexpensive Brownells Brass Muzzle Crowning Lap. This is a tapered "cone" of brass with a stem to allow it to be inserted into a drill. Another style they offer is a large brass rod with the end rounded. Some old-timers used a large round head brass machine screw, and the Brownells tool is basically a commercial version of that. The idea is to "lap" the final edge of the bore until it is completely concentric and at a perfect 90-degree angle to the bore, smooth and free from any imperfections. The tapered brass lapping tool will ride in the bore and is self-centering. By slightly wobbling the tool as you work and by reversing the direction of rotation any minor imbalances or imperfections are compensated for and the crown will be true to the axis of the bore.

Before starting, plug the bore of the rifle with a tight fitting cloth patch and leave it about three or four inches down from the muzzle. Put the lapping tool in a variable speed ⅜-inch drill, coat it well with 600 grit lapping compound and insert it into the bore until it contacts the muzzle. Start the drill and rotate the lapping tool at slow-to-moderate speed while slightly wobbling the drill. After ten seconds or so, reverse the direction of rotation and continue to wobble the drill. It's better to work slow and check the results often. So, stop and wipe the compound off the muzzle and check your progress after ten seconds of rotation in each direction. There will be a bright ring on the muzzle from the lapping compound wearing away the metal. When it's complete, it should be completely around the bore and extend to the bottom of each of the rifling grooves and to the top of the lands. The best way to inspect it is with a magnifying glass or with a magnifying headset like those used by jewelers. If the ring is still not complete, put some more lapping compound on the tool and continue.

Keep working and checking until you have a clearly defined ring all around the muzzle, all the way to the inside edge and all the way to the bottom of the rifling lands. When that is complete, you are done. It's that simple.

If you want a more professional and contemporary looking job, consider using Brownells Muzzle Crowning Cutter with the appropriate pilot to cut a new crown. *See sidebar on page 100.* Brownells' also offers a cutter to square up the muzzle called the Muzzle Facing Tool, which squares the muzzle to the bore. If you have cut off the barrel this will also face off the barrel square with the bore, which is necessary before crowning. On an existing rifle, it's usually not necessary to reface the muzzle, but it makes for a more finished look. Use the muzzle facing cutter first and remember to use plenty of cutting oil with any cutter. Insert the pilot in the bore and turn the cutter until you have achieved the desired result. The cutter can be turned by hand or with a hand held drill. Use a very light touch with the cutter. If you use too much pressure, the blades can chatter, and once that happens it's very hard to correct when turning the cutter by hand. That's because the cutter will follow the contours of the surface

CORRECTING CROWN DAMAGE



1. Caliper measuring a pilot. It's critical that the pilot fit the bore of the barrel when cutting a new crown or facing the barrel.



2. Brownells Muzzle Crowning Cutter with paper pilot attached.



3. Shows the Brownells Muzzle Facing Tool in use. This tool cuts the face of the barrel square with the bore.



4. This rifle muzzle has been faced off with the Brownells Muzzle Facing Tool and then re-crowned with a 45-degree cutter.

created by the chatter and will simply keep repeating the same cuts and deepening the waves created by the chatter. To correct this problem, use the stop that Brownells sells which fits on the cutter. This stop will not allow the cutter blades to drop down into the valleys created by the chatter. This ensures a constant contact with the cutter that will hit only the high points and so will correct the "waves" created by the cutter chatter.

Next, put the pilot on the crown cutter and cut an 11-degree crown. (Actually it's 79 degrees, but it's commonly called 11-degree. That's because 90 degrees, minus 11 degrees is 79 degrees.) This is a very popular type of muzzle crown and is said by some to enhance accuracy. If you prefer, Brownells also has a 45-degree cutter that can be used for a deeper angled crown and one that can be made deeper in the barrel so that it is better protected from field damage. Finally, finish with a brass lapping tool to just break the edge.

Just remember that the metal will be bare after cutting. You can leave it like that or re-blue or finish it with a coating. Either way, it must be protected from rust.

Push the plug out of the barrel from rear to front. Then wipe the bore with a few solvent-soaked patches to clean the residual lapping compound. Always work from the rear or action end of the gun and push the patches out of the muzzle so that the gunk is not pushed into the action. Finish with a dry patch.

The Experience of Glass Bedding a Rifle Stock

This stock has the action and first few inches of the barrel bedded.

"Experientia docet" (Experience teaches)
—Cornelius Tacitus

Wise words from one of the world's greatest historians. But, no less a social commentator, Oscar Wilde said, "Experience is the name everyone gives to their mistakes."

It is no secret that glass bedding a rifle stock can often do wonders for the accuracy. If you believe all you read on the subject, it's also an example of a home gunsmith project that anybody with a few basic tools and at least a rudimentary ability to manipulate them can complete with wonderful results.

Don't believe everything you read.

In the early days of synthetic hunting rifle stocks, I decided I needed one. When my order arrived, what was in the box might have passed for a rifle stock, but barely. It was a crude lay-up that lacked everything from a butt pad to holes for the action screws. I spent days sanding, drilling, shaping and filing. Then I mixed up about two pounds of bedding compound and filled the stock to the brim before bolting everything into place.

I am first to admit that I am not good with "sticky substances." So when all that excess bedding compound squirted out, I should have asked for help or at least not panicked. But I did neither. I was so focused on cleaning up the gun that by the time I noticed the big glob on the floor, I had already walked in it several times. In my many trips to the kitchen for more paper towels, I had a nice, even layer of bedding compound making a defined path on the carpeted cellar stairs and throughout the house. The stuff seemed to breed and reproduce and like the 1958 Steve McQueen movie *The Blob,* I thought it would soon fill the world. What wasn't on the carpet or the kitchen's



Note the support area left on the stock before bedding. This makes contact with the action, while the bedding fills in the areas that are cut away to the same level.

Materials and tools used for glass bedding.

Laminated stock ready for bedding work.

vinyl floor was on my shirt or in my hair.

None of it was "water soluble."

The directions recommended using vinegar to clean up, great if you have some on hand. I did not. In rushing to the store to buy vinegar, I didn't notice that I had bedding compound all over my pants, which transferred nicely to my truck seat. All the vinegar really did anyway was smear the compound around more and give everything a funky smell.

One way or the other, all messes clean up eventually and most marriages survive them. The next day I was ready to remove the barreled action from the stock. I had "bedded" the entire gun in one operation, pushing the action deep into the stock, and compound had squirted into all the holes and filled every void. After several hours of trying to separate the parts, I finally read the directions that came with the bedding kit, which mention all these things. Mostly stuff about not doing them.

Hours later, I found a gunsmithing book that suggested chopping the stock off the action with an ax, but before I went to the shed to get my hatchet I decided to give it one last shot. Back then I was young and working every day in a telephone company line crew. I was as strong as I'll ever be in my life and I put all I had into the effort. With the gun on the bench and one knee on the stock, I yanked first on the barrel, and then on the wooden dowel in the action, alternating back and forth until suddenly everything popped free! I fell backward off the stool I was standing on (with one foot) and the barreled action crashed beside me on the cement floor, breaking the trigger assembly off.

I have glass bedded dozens of rifles in the years since. And while there were damn few mistakes I didn't make on that first one, these years of experience have allowed me to correct that, and I think I have a complete collection now. So if you will allow me to teach you with my "experiences," I will make some suggestions on how to glass bed your rifle with a minimum of pain and aggravation.

First, read the directions. Like most guys, I wait until I am in trouble before taking this step. That's why I get in trouble. Next, make sure you have everything you need to complete the job on hand before you start. That includes materials to clean up any messes. Finally, go slow, pay attention to details and take it one step at a time. Every time I try to hurry or cut corners I get into trouble.

These instructions are for wood or wood laminate stocks, but they apply to most of the better synthetic stocks as well. The exception being inexpensive injection molded synthetic stocks. Bedding compound will stick to wood, metal, paper, concrete, carpet, hair, skin, glass and every known substance in the modern universe, except an injection molded rifle stock. I don't know who the genius was that came up with the material for those stocks, but if my kitchen floor had been covered with it instead of that expensive Armstrong vinyl, I would have had a much happier wife all those years ago. If you are

Hand chisels and scraper.

BEDDING FOR WOOD AND WOOD LAMINATE

1



1. Using a hand grinder to cut away a thin layer of stock material in front of the magazine and in the recoil lug mortise.

2



2. Using a small chisel to cut away stock material and rough the surface to prepare for glass bedding.

3



3. When removing wood from the action area in preparation for glass bedding, be sure to leave a section for support.

4



4. Shows completed stock bedding. Note the numbers imprinted in compound which illustrates the "skin-tight" fit. Note that the bedding at top does not contact the barrel. On left is a laminated stock before bedding.

bedding an injection molded stock, there are other steps that will be covered later which must be used to ensure the bedding stays in place.

To get started, first remove the bolt, then the scope, if for nothing else to protect it from damage. Then remove the action screws and take the rifle apart. Slide the magazine follower spring out of the floor plate and place it and the magazine box in a safe place. Place the stock in a cradle or gun vise that will hold it while you work.

Using a hand chisel, scraper or a small electric hand grinder, remove a thin layer of wood everywhere under the action in front of the magazine and in the recoil lug mortise, except for two support sections. To create these, leave a small strip about ½ inch wide between the action screw and the recoil lug mortise. This is to support the action at the proper height until the bedding compound has hardened. Do the same where the recoil lug face contacts the stock in the recoil lug mortise on the load-bearing side. This prevents the action from moving back in the stock. What you are doing is supporting the action and the recoil lug, which keeps the action in exactly the position it was already in. But, by removing the material from everywhere except those two support locations, you have created a gap for the bedding compound to fill.



After preparation, the rifle is assembled and a cardboard index card is used to check for clearance between the barrel and the stock.



Bedding compound in the barrel channel for full-length bedding of the barrel.



Masking tape on the stock to protect it from excess bedding compound.

A master stock maker will spend hours smoking the action, trying the gun, and then scraping away the high points in the bedding as indicated by the black smudges. Then trying it again and scraping again, and again, and again, and again until there is a perfect match. But with glass bedding, the miracle of modern technology allows you to create the same or an even better fit in a fraction of the time. The idea is that the compound will mirror exactly the surface of the action. The match is so good that often in the completed job you can see the machining marks on the metal reflected in the bedding compound. That gives a complete contact with the load-bearing surfaces, which creates a solid and even match between the stock and the action. There will be no twisting, torque or uneven stresses placed on the action with a correctly bedded rifle. Instead, the stock and action mate in perfect harmony. The stock's job is to support the barrel and action and to allow the shooter to hold and aim the rifle. It should never induce any flexing or stress on the action and in a nutshell that is what you are trying to achieve here, equilibrium between the two parts of the gun.

Don't worry about keeping the areas you cut away in the stock neat or smooth. Actually, the rougher the surface, the more contact area for the bedding compound to mate with. The idea is to create a gap between the metal and the wood. However, the small strips you leave in place ensures that the action sits in the same place as it did before you removed the wood. Because the bedding compound will match with them exactly, the supports left in place will transition to the compound seamlessly once the job is complete. Running your finger over the stock support to the compound will show no change in dimension if things are done correctly.

Once this is complete, put the gun back together (without the magazine "guts") and snug the screws, but not tight enough to crush the small supports you left. Wrap an index card, business card or similar piece of thin cardboard around the barrel and slide it between the barrel and stock to make sure there is clearance. For a tight fit, a dollar bill works very well. If the stock is contacting the barrel, mark the spot with a pencil on the top of the stock that corresponds to the tight area and after taking the rifle apart, remove the wood from the offending area. A barrel-bedding scraper makes this easier, but sandpaper and patience will work. Wrap the sandpaper around a large wooden dowel to help maintain the contours. But, the best way is to use a Barrel Bedding Tool available from Brownells. This is a series of round cutters mounted on a contoured rod with a handle at each end. The cutters maintain the round contours of the barrel channel while cutting with each stroke. They will not dig in or gouge, but take a nice even cut each time. These are available in several different diameters to match the barrel you are bedding. In terms of time saved and aggravation avoided, this is a "must have" for stock work and I have several in my shop.

What happens under the barrel will not show, but



A rifle fitted with stock maker's hand screws during the bedding process. These T-screws are handy when doing work that requires assembling the stock and action often. Note that the stock is covered with masking tape to prevent any compound from sticking to it.

remember that the inside edge of the barrel channel along the top of the stock will. So, go very carefully when working on this top edge of the barrel channel. Put the gun back together and check the clearance again. Repeat until the only places in front of the magazine making contact are the thin strips of wood you left to support the action and recoil lug. The action and barrel should sit high enough in the stock so that the centerline is above the top edge of the stock; this is particularly important with a round action like the Remington Model 700. The barrel should fit evenly in the barrel channel without big gaps, including underneath at the forend tip. You may want to make adjustments by removing more wood from the action support area to allow it to sit deeper or by placing a shim under the action to raise it higher. A strip of plastic or wood super-glued to the stock works fine for a shim. You can simply leave it in when bedding and surround it with compound so it won't show, except where it contacts the rifle.

BROWNELLS BEDDING/ MASKING TAPE
10MIL PIPE WRAP
PASCO

Brownells' bedding tape and .010-inch pipe wrap

Cover all the outside surfaces of the stock with masking tape. Overlap it into the barrel channel and use a sharp razor blade to trim it to the edge. I find it best to cover the entire stock with masking tape. Sooner or later you will have bedding compound on your fingers while handling the stock and the resulting "fingerprints" can be tough to remove without damaging the finish. Fill the magazine cutout and any other places you do not want bedding compound to flow into with clay.

Degrease the metal parts of the barreled action with a spray degreaser. Fill the magazine gap in the action with clay, as well as any screw holes or other places that should not have compound in them. On some actions, you can cover the magazine opening in the action with tape. Cover the recoil lug with two layers of masking tape, except on the load bearing rear face. This will create a gap around the recoil lug so that it does not contact the stock, except where it transfers the recoil.

I usually bed the first few inches of the barrel and float the rest. To do this, place two layers of 2-inch electrician's tape along the barrel. Or better yet, use Brownells .010-inch-thick pipe wrap tape. This 2-inch tape is the right thickness for a perfect floated barrel. It will also work in a single layer on the recoil lug. Masking tape will not work for floating the barrel, it is too absorbent and will stick to the compound. This makes it hard to remove and does not leave as nice a finished product. End the tape where you want the bedding to end and cut the end square. The tape will create a gap between the bedding and the barrel. Try putting the gun together to make sure the tape isn't hitting the barrel channel and preventing assembly. This is one of those things best discovered before you have the bedding compound in place. If the fit is too tight, switch to a single layer of tape, or open the barrel channel up a little more.

Now paint the entire barreled action with the release agent supplied with the bedding compound. Coat all the metal, tape and clay. Let it dry and repeat. Hold the gun under a light to make sure you have complete coverage. Let the release agent dry completely. Even though you



Rifle action and stock with clay filling the action and magazine opening to keep bedding compound out. Stock has masking tape to protect against overflow of bedding compound.

BEDDING WITH ACRAGLAS GEL



Painting release agent on barreled action before glass bedding. Note tape on barrel to create gap for floating barrel.

Acraglas Gel with dyes, thinner atomized metal and release.

ACRAGLAS GEL
RESIN
WARNING
ACRAGLAS GEL
HARD

Acraglas gel is a two-part bedding compound that must be mixed in equal parts.



The recoil lug and the action area of the stock is filled with bedding compound.

will not be bedding the end section of the barrel, coat it anyway. You will handle it with compound on your fingers and if you don't, it will be very hard to remove the mess without damaging the bluing. (One tip—if you have "fingerprints" of compound on the metal that you are having trouble removing, try some Hoppe's #9 solvent. It will often remove stubborn spots of unwanted compound.) Don't forget to coat the action screws and inside the holes, as well as the trigger guard and bottom metal. Coat the tape along the top and down the sides of the stock. Be careful not to get release agent on the inside where you want the bedding compound to stick. Coat anything you do not want bedding compound to stick to. In my case I should probably coat my entire body, all my tools, my workbench, the shop walls and from past experience my wife's kitchen floor. But, I usually just coat the gun parts I don't want to stick and take my chances with the rest.

The best bedding compound I have used is Brownells Acraglas Gel. This two-part epoxy is mixed in equal parts. The package comes with brown and black dye which can be added to match the color of the stock. After mixing according to the instructions, use a flat "Popsicle" stick (I buy mine in big boxes at the local arts and craft store) to butter the compound on the stock around the recoil lug, action and the first few inches of the barrel channel. It's always best to bed one section of the gun at a time. For example, bed the forward action and recoil lug area in one step. If you are to bed the barrel or the rear of the action, do those in their own separate steps. Use a Q-Tip to make sure the hole for the action screw is clean of bedding compound. Put another Q-Tip into the screw hole in the action and guide the other end through the hole in the stock as you carefully place the barreled action into the stock. After the action is seated, pull the Q-Tip out through the bottom of the stock. This clears much of the passage for the stock screw. Use a few more Q-Tips to make sure the action screw hole is clean and free of compound. Then attach the bottom metal and replace the action screws. Snug them tight, but not too tight. You want the action fully seated, but not crushing the fibers in the stock where you left those small support sections.

Clean up the compound that oozes out. A Popsicle stick that has been cut to match the contours of the barrel works well. Then leave the gun alone overnight. Resist the temptation to "check" on it until the bedding compound has fully hardened. The next day, remove the action screws, turn the gun over and clamp it in the cradle. Place a wooden dowel in the action and holding the stock down, alternate upward pressure on the dowel and the barrel. Keep rocking back and forth until the action comes free. If you have trouble, put the gun in the freezer for a few hours to contract the metal. Because the metal will contract at a faster rate than the compound, this will often break the adhesion. Or if, like me, you live in the north, putting the gun outside the shop if it's cold enough works too. Last winter I was bedding a stock and having trouble. It was 20 degrees below zero outside, which is a lot colder than my freezer. I just put the gun on the picnic table outside the shop. But I did it quickly.

If you still have trouble, Brownells sells a slide hammer tool that will "snap" the action free from the bedding compound. (Sure wish I had that on my first rifle!) It uses a rod in the action and the slide hammer is a weight that slides up a rod that is threaded at 90 degrees into the rod in the action. A stop at the end of this rod arrests the motion of the sliding hammer and transfers the energy to the shaft, and consequently to the action.

Once the action is free from the stock, use a small knife, dental pick or screwdriver to pick the tape out of the recoil lug mortise. The compound is still soft and will cut or file easily to clean up the areas where it does not belong. Usually, you will smooth the top of the stock with a small file to even the compound with the wood. Work carefully so that you do not damage the finish on the stock.

If there are gaps or missed spots, they really don't hurt anything unless they are excessive. But it looks better to fill them in and they can be filled by repeating the process. Just remember to clean the release agent off so the compound will stick. Use a cotton swab and lacquer thinner. If the release agent is water soluble, I usually put the stock in my laundry sink and scrub it under running water with a soft bristle brush. Then I let the stock dry for a couple of days. It's also a good idea to "rough up" the surface in the voids with a hand grinder to ensure a good surface for the new compound to adhere to.

To bed the barrel channel, simply keep the two layers of tape on the barrel, but recoat everything with release agent. Butter the barrel channel with bedding compound and put the rifle together. After the compound hardens, you can remove the barreled action and remove the tape. The gap left from the tape will give you a smooth and consistent gap between the barrel and the stock for a perfect free-floating barrel. This layer of compound will also provide a waterproof coating on the wood stock to prevent moisture from entering, and will add strength to the stock to resist warping.

If you are going to bed the rear of the action, repeat the process until you have completed everything. Often though, I find that bedding the action ahead of the magazine and floating the barrel is enough to make the gun shoot well and that bedding the rear of the action is not necessary. So my suggestion is to shoot the gun before deciding to bed any more of the action, unless you have an obvious fitting problem.

When all bedding is complete and the compound cured, remove all the clay, masking tape and release agent. Coat any exposed wood with a sealer. Wipe the metal down with a rust protector and put the gun back together, including the magazine parts and the scope. The action should fit tightly into the stock with no rocking or movement as you alternately tighten and loosen the screws. Finish with the screws snug but not tight. Check the barrel channel for clearance. If it's good, put the gun away for a week to let the compound harden further. Then tighten the action screws and you are ready to head for the range.

BROWNELLS
GLASBED
ACRAGLAS GEL
ACCURIZE WITH ACRAGLAS
BROWNELLS
STEEL-BED
DECKER

This stock has been glass bedded around the action. Accuracy was improved by this work. Glass bedding a stock is easy enough that anybody can do it, and it can make a dramatic difference in accuracy.

HOW TO GLASS BED A RIFLE STOCK



1. Masking tape on the stock to protect it from excess bedding compound.



2. Bedding compound in place for the action, recoil lug and the first few inches of the barrel.



3. Place a Q-Tip in the action screw hole before placing the barreled action in the stock. This prevents the bedding compound from entering the hole, and when you pull it out it clears the path for the screw.



4. Shows the gun together during the bedding. Note the bedding compound along the edges. Note that the stock is covered with masking tape to prevent any compound from sticking to it.

5. The assembled rifle with bedding compound. Shows the bedding compound oozing out around edges.



6. Illustrates how the slide hammer fits into the action. This tool from Brownells is used to separate a barreled action and stock after bedding.



7. This rifle stock shows how the glass bedding job is a good fit on the action and recoil lug, but has gaps that need filling in the area under the barrel.

8. Using a file to clean up the overflow of bedding compound.



Shows completed stock bedding. Note the numbers imprinted in compound. This illustrates the "skin-tight" fit. Note area of bedding at top that is not contacting barrel.



Bedding the tang area on the stock.



Illustrates the bedding compound after bedding. Note the sharp edge that ends the barrel bedding. This is created by using tape on the barrel.



This stock has the action and first few inches of the barrel bedded. The barrel channel in the stock was also bedded using tape on the barrel as a spacer. This strengthens the stock and waterproofs the area that is bedded.

CORRECTING WARPING PROBLEMS IN A WOOD STOCK

A lot of accuracy-affecting bedding problems occur when the forend of the stock warps, causing it to contact the barrel. This actually is the reason I ended up with one of the most accurate rifles I ever owned. I was on a deer hunt and the guide wanted my rifle very badly. We stopped for coffee at his house one night after the hunt and he started trying to trade me out of it. One of the items on the table was a Ruger M-77 heavy barreled varmint rifle in .220 Swift. I noticed that the barrel had a big gap on the left side of the stock while the right side had made hard contact with the barrel. I surmised that he was having trouble making it shoot and that he probably wanted to get rid of it. So, I worked that to my advantage and before the deal was done, he offered far more than my rifle was worth even without the Ruger in the mix. I am too honest to be a good trader and I pointed out to him that he was not getting a fair deal, but he wanted my rifle, so we traded.

When I got the Ruger home, my suspicions were confirmed. I took the gun apart and found several brass shims under the action. Shimming the action is a low-rent way to fix bedding problems and it told me that even though he denied it, he was aware of the gun's problems. I suddenly didn't feel so guilty about the trade. I opened up the barrel channel to float the barrel and glass bedded the action. The gun turned out to shoot quarter-inch, 100-yard groups. The downside is that I got stupid and traded it off a few years later for a gun that I don't really like.

My point is that the stock warping is a common problem and often even after you remove enough wood to fix the problem, it can continue to warp. One way to help correct that is to first remove enough wood so that the barrel is floated and there is enough clearance for bedding compound as well as the double layer of 2-inch electrician's tape or Brownells' .010-inch pipe wrap tape. This may result in a big gap between the barrel and the stock on both sides of the barrel, but that's unavoidable. It will later be filled in with bedding compound. But be advised, the line between the stock and the compound will show, so try to keep the lines straight.

Now use a hand grinder or a chisel to cut a channel in the bottom of the stock, deep enough to accept a ¼-inch steel rod with plenty of clearance above it. Cut a piece of ¼-inch threaded rod to the proper length, degrease it, put it in the bottom of the channel and make sure that you have at least ⅛-inch clearance between it and the bottom of the barrel channel. Tape off the stock, but leave the top of the sides along the barrel channel uncovered and free from release agent. Bed the barrel, using plenty of compound and making sure that you completely fill the channel and bury the rod in compound. Dye the compound to match the color of the stock as closely as possible, as it will be showing along the top of the barrel channel. Let the compound ooze out the top and then clean it off with a Popsicle stick, but leave it higher than the top edge of the stock. After it hardens and you remove the barreled action, you can file and sand the compound down even with the top of the stock. This will fill in the gap between the barrel and the stock. It will show, of course, but if you matched the color it won't be too noticeable and it will certainly look a lot better than a big air gap. It will probably be necessary to refinish the stock, as the top section will probably show some marks from filing and sanding the compound even with the stock. When doing this, use a stain to more closely match the compound color to make it less noticeable.

The rod imbedded in the compound provides structural strength and will help to keep the forend from warping again. Using threaded rod allows it to grip better in the compound than a smooth side rod, again adding strength. The compound covering the wood will help prevent water from entering the wood, which is what causes warping. As always, make sure to seal any exposed wood against moisture during the finishing process. It won't be the prettiest stock in your gun room, but it might be on your best shooting rifle.

WHAT IF IT STILL DOESN'T SHOOT?

Most rifles shoot well with the front of the action and first few inches of barrel glass bedded and the barrel floating. But some rifles simply prefer pressure on the barrel near the stock's forend tip.

If the rifle is still not shooting well after bedding, try a thin one-inch-wide shim between the barrel and the stock an inch or so back from the end of the forearm tip. Because the shim will become permanent, plastic is better than cardboard. Experiment with different thickness and placement until you find one that makes the gun shoot the way you want.

Mark the shim's location with a pencil. Take the gun apart and coat the barrel with release agent. On either side of the shim's location sand the barrel channel to bare wood, but leave a ½-inch strip that corresponds with the shim that is untouched. Trim the shim to a quarter inch wide and place it in the barrel channel perpendicular to the barrel. A drop of Super Glue will help keep it in place. Make sure that the barrel will center on the shim when the gun is assembled. Cover the shim well with Acraglas Gel and at least ½ inch out in each direction. Use enough bedding compound to ensure the shim is trapped and encapsulated. Reassemble the rifle. The shim will maintain the exact pressure on the barrel until the bedding compound has hardened. The next day, take the stock off the rifle and trim the compound to the 1-inch width of the original shim. (The ½-inch shim should be left in place.) Clean up the release agent, seal the bare wood and put the rifle back together.

If the pressure pad is too wide, it's easy to trim it to size with a hand chisel while the bedding compound is still soft. If you wait until the compound is completely set up, you can grind it to shape with a Dremel hand grinder.



This pad was installed in the forend to provide pressure on the barrel. This .280 AI shot much better after doing this.

STOCKMAKER'S HAND SCREWS

Any stock work will involve taking the gun apart and putting it back together several times. No matter how careful you are, it's easy to mark up the bottom metal or the screws with the screwdriver. It's far simpler to use a set of stockmaker's hand screws. These have an extended "T" handle and are much faster than a screwdriver. Of course, Brownells sells them. So does Midway USA.

Pillar Bedding Your Rifle

Remington M-700 BDL SS DM in 7mm STW. Zeiss Diavari 5-15 T scope. Shows the stock after pillar bedding and filling the barrel channel with Bondo.*

Any mass-produced product, no matter how technically advanced, will have manufacturing tolerances that will dictate a variation in the dimensions of the parts. Rifles are not exempt from this, but it is inarguable that with the increasing use of computer controlled manufacturing machines, today's factory rifles have reduced those tolerances dramatically. Enough, it would seem, that the accuracy goals of a "tuned" rifle from a couple of generations ago are generally close to the minimum out-of-the-box standard today. However, while we may be getting closer, perfection is still elusive.

Dimension variations in bedding, which is the relationship between the metal and the stock of a rifle, particularly around the action, can be critical to the performance of a bolt-action rifle. Even a small variation in dimension can affect the accuracy if it is in a critical location. With the "drop-in" design of most factory-installed stocks, exact bedding is compromised for the sake of affordability and rapid manufacturing. In spite of that, today's rifles still shoot amazingly well. That said, as good as they are, almost any factory rifle will shoot better with improvements in the stock bedding.

Rebedding a rifle is usually the single most important change a shooter can make to improve accuracy. It's easily done in a home shop with a minimum of tools and by anybody handy enough to work a screwdriver without drawing blood.

So-called "glass bedding," when done properly, provides a bedding platform that is so tight to the action that often you can see machine marks from the metal mirrored in the bedding material. Properly done, glass bedding (actually, it's usually epoxy these days rather than fiberglass and resin) will provide a bedding foundation that not even the most skilled old-world craftsman could duplicate with wood to metal bedding. But there are a few problems with using just glass bedding on some stock, regardless if it is wood or synthetic.

One problem that is inherent with wood stocks is that wood will compress. When you glass bed the stock without pillar bedding, the action screws are putting constant pressure on the wood material of the stock. As the cells in the wood compress under that pressure, the tension of the action screws can change, affecting accuracy.

This is also true with some synthetic stocks, particularly the less expensive injection molded styles usually found on factory rifles. The plastic may not compress, but it can be malleable enough to move under pressure, causing the same end result.

I remember testing a rifle from a well-known gunmaker back in the 1980s when they were first offering synthetic stocks. The front action screw had a relatively small head and because it was a blind magazine style, the screw simply tensioned against the plastic stock. Every time I

John R. Kascenska disassembles a rifle in preparation to pillar bed the stock. Here, he is inspecting the trigger.

checked the screw, I found it slightly loose. This puzzled me as I was using Loctite on the threads. Of course, each time the screw was loose, the groups would start to open up. However, it wasn't long before the head of the screw had imbedded itself more than a quarter inch into the stock, which was hard to ignore. It was actually tunneling into the stock, displacing material and, of course, never maintaining constant tension. Obviously, this rifle never shot as accurately as I thought it should. Within a very short time, that gun company started pillar bedding all its rifles, and those guns have a reputation for providing outstanding accuracy.

As they found out, pillar bedding is one answer to this problem. It is simply adding a "pillar" of metal or some other strong material to support the tension of the bedding screws. Most pillars are simply tubes of metal with a hole through the center for the screw to go through. The action sits on the top of the pillar, while the action screw tightens against the bottom of the pillar.

Sometimes nothing else supports the rifle's action except these two pillars. When bedded this way, the rest of the action simply floats slightly above the stock, making contact with the stock itself only at the recoil lug. Because the pillars are strong, noncompressible metal, the tension on the screws remains constant. Not only do the pillars provide excellent bedding support, but they are not affected by changes in dimensions caused by humidity.

Pillar bedding works best when done in conjunction with glass bedding of the action. For best results, you should not allow the pillars to be the sole support of the action. Instead, also glass bed the section of the action between the front of the magazine box and the recoil lug and the rear tang area. Also, the recoil lug should be properly glass bedded so that there is clearance around all but the rear load-bearing surface. It's also a good idea with most rifles to bed the first two inches of the barrel, while free floating the rest. The section of the action between the rear tang and the front of the magazine box can be bedded, but it's usually better to free float it so that the action is supported front and rear, but floating in the center.

All this ensures that the action fits properly on the pillars and is especially important with round actions like the Remington Model 700 to ensure that it sits squarely in the stock. If the action only sits on the pillars, it can potentially roll slightly off center, but by bedding the action and recoil lug in conjunction with pillar bedding, the fit is so tight that the action can only fit in the stock one way.

My first stop was Brownells, where I ordered a pillar bedding kit which comes with a set of adjustable pillars, two tubes of pre-colored Acrabed bedding compound, release agent and assorted tools and gadgets needed for a pillar bedding project. It also includes detailed instructions.

You can order the kit with or without a $^{9}/_{16}$-inch wood drill to enlarge the action screw holes. It works fine if you are only going to do one or two stocks, but the Piloted Forstner Bit that they offer separately works much better as the pilot will follow the existing hole to keep the alignment of the drill in relation with the old action screw holes correct. If you are going to drill the stock with a hand-held drill, the piloted drill is a must.

The adjustable pillars are great. The length of the pillars is critical, as they need to support the action in the correct relationship to the stock. Rather than fooling with cutting them to length, you can simply screw the pieces in or out until you have the length that you need.

The toughest part may well be drilling the action screw holes larger to accept the pillars. The best way to do this is to use the piloted drill that has a pilot the size of the existing hole. The pilot follows the hole and keeps the drill exactly centered. This allows you to drill the holes even with a hand drill and keep things lined up properly. When drilling through an injection molded stock, a standard non-piloted drill has a tendency to grab the material and then set a course of its own. You never know where it might end up, but often it's not where you want it.

If this happens to you, don't panic. You can still salvage the job by simply drilling the holes even bigger and "floating" the pillars in bedding material. If you prepare everything and fill around the pillars with material at the same time you bed the action and put it all together, they will find their own "center" and when the material hardens, they should be placed properly. The only adjustment you may have to make is to relieve the pillar a little if the screw is hitting the inside. The best policy though is to drill the holes in alignment with the existing action screw holes, so always try for that goal.

When the job is complete, the action screw should never contact the pillar with the shank portion. The force of recoil must transmit to the stock only through the recoil lug and never through any of the action screws. To assure this, the screw only contacts the pillar on the head, never the shank.

If you are working with an injection molded stock, remember that the plastic used in these stocks is difficult to adhere to. Actually, that's an understatement, nothing except Alabama field mud will stick to the stuff and it's not stabile enough for bedding material. The answer is to drill anchor holes at various angles and make some undercuts to mechanically lock the bedding material to the stock. Make sure to do this inside the holes that will accept the pillars. After making all your cuts and roughing up the surfaces and just before you apply the bedding compound, make sure that the area to be bedded is chemically clean and free of oil by spraying with a degreaser that leaves no residue. In addition, after degreasing, but before bedding, I finish with a spray-on product I bought at the local auto supply store that is designed to aid adhesion of paint to plastic called Bulldog Adhesion Promoter, which seems to help.

Once you have the pillars correctly adjusted and fitted, coat them well with bedding compound or epoxy glue and put them in place. Screw the rifle together, make sure that everything is in correct alignment and wait for the glue to cure. Glass bedding the action and recoil lug should be done in a separate step after the pillars are correctly installed.

Once the pillars are in place, cut and gouge out the area of the stock that will be bedded to allow room for the bedding compound, leaving only a small support section behind the recoil lug to keep the action in the correct location front to back. The pillars will support the receiver. Do not go very deep or remove much material, just enough to ensure that the action contacts only the pillars and the small section of the stock material you left for the recoil lug to butt against.

BROWNELLS GLASBED
ACRAGLAS GEL
ACCURIZE WITH ACRAGLAS
BROWNELLS STEEL-BED
BROWNELLS STEEL-BED

While this wood stock has been glass bedded without pillars, a variety of pillar kits are available on the market.

MARK BANSNER

Adamstown, Pennsylvania

I know of one custom gunsmith, Mark Bansner, who creates his pillars by first glass bedding the stock. Then he drills out the screw holes and fills them with glass bedding compound mixed with powdered metal (called Atomized metal by Brownells). He coats the screws, action and bottom metal with release agent and puts the gun back together. When the material has hardened, he takes the gun apart, cleans up the overflow and then drills the holes one size larger to ensure there is no contact with the screws and the pillars except at the screwhead.

This in effect creates a custom-sized pillar that is perfectly fitted. It's independent of the bedding and a lot tougher. Mark's guns enjoy a reputation for outstanding accuracy and durability. I know, I have three of them and they are all extremely accurate, tough and stable. I have hunted with them from Alaska to Zimbabwe and never had a problem. None of them are chambered in "sissy" cartridges. Two are wildcats I designed on the Remington Ultra Mag case, a .358 and a .416, and they are very hard recoiling cartridges that demand a lot out of the bedding.

All other areas should have clearance. The idea is to hold things in place until the bedding material has a chance to set up. If you are going to float the barrel, make sure that when the action is seated and the screws are snug, you can pass a business card between the barrel and stock along the length of the barrel without dragging.

The front, sides and bottom of the recoil lug should be covered with a layer of masking tape before the release agent is applied. But, do not cover the load-bearing surface of the recoil lug. That is the flat that is facing to the rear of the rifle. When removed, this tape creates a slight gap around the recoil lug, ensuring that the only contact is on the rear load-bearing surface. The entire action and the first two inches of the barrel are usually bedded at this time. Apply a couple of layers of masking tape to the barrel ahead of where you wish to bed and one layer on the center section of the action, the part you wish to float. This will provide a few thousandths of clearance after it is removed. Put masking tape on the outside of the stock and along the top to protect those areas from the overflow of bedding compound. The best way is to put the tape on the top then trim the edges with a sharp razor blade. Tape up or remove the trigger assembly. Coat all the metal and any tape on the metal with a release agent. Mix the bedding agent according to the instructions and fill the areas to be bedded. Be generous and let the excess spill out. That ensures that all the gaps are filled. Put the rifle together and just snug the screws, but not too tight.

When the bedding agent has cured, remove the barreled action from the stock. (A little hint: After the bedding agent has cured, if you put the gun in the freezer for a couple of hours before you separate them, the metal will contract and make the job easier.)

If you are now going to glass bed the barrel channel, make sure there is plenty of clearance. Then cover the barrel with a layer of .010-inch pipe wrap tape available from Brownells. Then bed the length of the barrel. The tape serves as a spacer that, when removed, creates a perfect gap and leaves the barrel free floating.

This pillar bedding, along with glass bedding, is as solid a foundation as you can create for your rifle's action. It should be accurate, tough and permanent.

BROWNELLS' INSTRUCTIONS FOR PILLAR BEDDING • Pillar bedding creates a uniform bedding surface and helps eliminate changes in guard screw tension, thus enhancing accuracy in many bolt-action rifles. Brownells Adjustable Pillar Bedding Sleeves are aluminum with steel sleeves threaded together to allow precise adjustment to fit individual rifles. Adjustable Pillar Bedding Sleeves eliminate the need to machine pillars to fit individual rifles. Rifles of the same make and model may have variations of over 1⁄16 inch in distance from the underside of the action to the top of the trigger guard-floor plate unit. The main aluminum adjustment piece is reversible to easily adapt to either flat- or round-bottomed receivers.

NOTE: Brownells Adjustable Pillar Bedding Sleeves are not suitable for use on Mauser, Springfield, Ruger, or other rifles with the front guard screw directly threaded into the recoil lug or with very narrow rear tangs.

How to Use

We recommend that pillar bedding be done as a multiple step process, first installing and bedding the pillars and the area surrounding them, then the recoil lug area, and last, the trigger guard. Areas to be bedded normally are the rear ⅓ to ¼ of the action including the rear tang; the front area of the action from the front of the magazine box opening up to the barrel; and the breech end of the barrel to about the front of the chamber area, roughly 1½ inches to 2½ inches in front of the action.

Bedding Compounds

Brownells Adjustable Pillar Bedding Kits come with Acrabed, a brown, pre-colored bedding compound packed in squeeze tubes for easy measuring of its one-to-one proportions. When very heavy recoiling rifles are pillar bedded, we recommend the use of Brownells Steel Bed in the recoil lug areas, with Acrabed or Acraglas Gel used on the remainder of the job.

Drilling the Stock

The trigger guard screw holes in the stock must be opened up to allow use of the Pillar Bedding Sleeves. We recommend using a 9⁄16-inch Forstner-type drill bit to cut the recesses in the stock for the Adjustable Pillar Bedding Sleeves. This type of drill bit is guided by its outer edge, and has little or no tendency to drift or to chip out wood from the hole being drilled. If a conventional wood drill is used, always drill from the trigger guard (bottom) side of the stock toward the action side. Any chipping where the drill comes through will be covered by bedding compound. Use of the drill press or vertical milling machine for drilling the pillar sleeve holes will minimize problems with drilling and is highly recommended. If the original guard screw holes are not located correctly or are not at right angles to the bore line, now is the time to "adjust" the fit by setting up the stock so the sleeve holes will be "square" to the action. Re-inlet the action and trigger guard-floor plate unit if needed. Remember, the widest points of the barrel and action (the horizontal centerline) should be at or very slightly above the top level of the stock.

Fitting and Adjusting the Sleeves and Forend

Clamp the stock in a padded vise and place the barreled action and trigger guard-floor plate unit in it. Push the action back so the back face of the recoil lug is tight against its recess in the stock. Insert and tighten the guard screws to their normal tension. Inspect the forend area to be sure the barrel is free floated; there should be about .010-inch to .030-inch clearance (about one to two times the thickness of an average business card) for the full length of the barrel channel. Remove the barreled action and adjust the barrel channel with scrapers and sandpaper as needed. (Note: A stock with forend tip pressure against the barrel can be a source of point-of-impact changes from either humidity on

ACRABED
RESIN
ACRABED
HARDENER
BROWNELLS

Remington synthetic stock, Brownells Acrabed, pillars and pilot drill. Note the removable pilot on the drill.



Disassembled Remington M-700 BDL SS DM with materials and tools for pillar bedding.

a wooden stock or sling pressure movement of the forend on a wood or synthetic stock.) Remember, when checking and adjusting your inletting, the widest points on the barrel and receiver should be at or above the top line of the stock. This will help prevent "mechanical locking" of the barreled action into the stock when using bedding compound. After the forend and inletting have been checked and adjusted, clamp the barrel in your padded bench vise ahead of the forend top area, with the underside of the action facing upward. If your action uses a separate magazine box, set it into the action. Set the stock onto the barreled action. Place the Adjustable Sleeves into their holes in the stock. If your action is round-bottomed, set the radiused end of the thick outer sleeves against the action. If it is flat-bottomed, like the Winchester M-70, set the flat sides against the action. Turn the slotted steel inner sleeves in or out until they are just below flush with the bottom of the inletting for the trigger guard. Adjust the narrow aluminum outer sleeves in or out until they are flush with the bottom of the inletting. Set the trigger guard-floor plate unit into its inletting and inspect to see if its outer surface is flush with the underside of the stock. Remove the guard and turn the narrow aluminum outer sections of the sleeves in or out until the fit is proper. The magazine box should have about 1⁄64-inch to 1⁄32-inch vertical clearance between the trigger guard-floor plate unit and the inside of the action. After adjusting the sleeves, carefully remove them from the stock and set them aside. A drop of epoxy, Loctite, fingernail polish, or Super Glue on the inside section, where the aluminum outer sleeve portions join the steel inside sleeve, will hold the sleeve assembly at its proper length while handling.

Metal Preparation for Bedding

Make certain the barreled action and trigger guard are clean and free from dirt, oil and any debris from stock work. Either remove the trigger assembly from the receiver or use Brownells Bedding Tape to completely cover it so no bedding compound can get into the mechanism. (Make sure it will still fit into its inletting in the stock if it is masked off rather than removed.) Use modeling clay and tape to fill or cover any grooves, slots, or rough areas that bedding compound could flow into and "lock" the action to the stock. Check the recoil lug to ensure that it is narrower at the bottom than where it meets the action and that there are no machining marks on its rear face that could cause a mechanical lock of the barrel to the stock. To provide proper clearance for future disassembly and reassembly, we recommend putting two layers of Brownells Vinyl Bedding Tape on the sides, front and bottom of the recoil lug. DO NOT put any tape on the rear vertical face of the recoil lug! Thoroughly coat all parts with a high quality release agent, such as Brownells Acra-Release or Brownells Release Ageny, carefully, following the instructions supplied with the release agent for application. Note: The exterior portions of the sleeves should not be coated with release agent, as they will be permanently bedded into the stock. Be absolutely certain that any portion of the barreled action, magazine box, guard screws or trigger guard assembly that may come in contact with the bedding compound is well covered with release agent. This will help avoid the possibility of damage during the initial disassembly following bedding. Be sure to use release agent on the guard screws (or Stockmaker's Hand Screws, if they are to be used for the bedding process). Coat all surfaces with the release agent. Use a cotton swab to coat the inside of the sleeves with release agent.



John R. Kascenska prepares to drill action screw holes larger to accept pillar bedding.

Below: Preparing to drill synthetic stock for pillar bedding.

Final Wood Preparation and Bedding of the Pillars

If pillar bedding is being done on a finished stock, make sure the stock finish is thoroughly cured before bedding. We strongly urge you to "mask off" the exterior of the stock with fresh, high quality masking tape to protect the exterior from any accidental contact with the bedding compound. Note: Incompletely cured stock finish may "pull off" from the stock when masking tape is removed. Old or poor quality masking tape can leave residues on the surface, which may harm the finish. The wood surrounding the front Pillar Bedding Sleeve should be removed on the action side of the inletting to a depth of about ⅛-inch. For round-bottomed receivers, such as the Remington 700, this should extend up about ½ inch to ⅝ inch on either side of the stock centerline. For flat-bottomed actions, such as the Winchester Model 70, cut wood away to within 1⁄16 inch of each side of the action's side walls. This "cutaway" area should extend from the front of the magazine box opening in the stock to the rear of the recoil lug inletting in the stock. DO NOT remove any wood from the vertical face behind the recoil lug beyond this ⅛-inch-deep area at this time; it will be done later. Wood must also be removed surrounding the rear pillar location. With actions that sit above the wood line at the rear, such as the Remington 700, set the action into the stock and lightly mark around the rear tang, using a pencil. Remove the action, and scribe a line about 1⁄16 inch inside the penciled line. This is your outer limit around the rear pillar when deepening the inletting by the recommended ⅛ inch. On actions where the rear tang is inletted into the stock, mark the stock about 1⁄32 inch inside of the inletting, and remove wood around the pillar's hole to about ⅛-inch depth to the marked line. You may have to make "dams" of modeling clay in the stock to prevent bedding compound from running out of the pillar cuts. Be sure to "dam" or mask off areas where bolt release or safety components are located, to allow free movement. Mix up enough Acraglas Gel or Steel Bed bedding compound to completely fill the areas in the stock surrounding the pillars where you have removed wood, plus about 25 percent extra as a "fudge factor." Follow our directions for proper mixing. Double-check that all of the metal parts are properly coated with release agent. Clamp the stock in a padded bench vise with the vise jaws clamped lightly but firmly on the forend, and the toe of the stock supported by your workbench. Coat the outside of the Pillar Bedding Sleeves with bedding compound and place them in their proper holes in the stock. Place the trigger guard into its inletting and hold it in place with masking tape. Put the bedding compound into the stock, working out any bubbles that may form. Try to avoid getting any bedding compound into the guard screw holes in the sleeves. If your action is round bottomed, double-check that the radiused ends of the thick aluminum portions of the sleeves are properly aligned. Place the action into the stock with the recoil lug held firmly against its recess. Install and tighten the guard screws or stockmaker's hand screws. Note: There is no need to overtighten these screws. Tighten them just enough to hold the parts in position with the centerline of the barrel at, or slightly above, the top of the forend. If a very heavy barrel is on the rifle being bedded, a small amount of modeling clay in the barrel channel or even one or two business cards under the barrel near the forend tip will help to support the barrel during this process. Following our instructions, allow the bedding compound to cure to "handling strength." When the bedding compound has cured to this "handling strength" point, remove the barreled action from the stock. Clean off all release agent for the barreled action AND from the bedding in the stock. If bedding compound has migrated into any areas where it is not needed, remove it along with the modeling clay used as dams when bedding the pillars.

Bedding the Recoil Lug and Barrel Breech

Proper bedding of the recoil lug is absolutely essential in a large caliber rifle to prevent recoil from splitting the stock. In any rifle, improper bedding of the recoil lug can cause inaccuracy. Before bedding the recoil lug, remove about ⅛ inch of wood from the area behind the lug, and about 1⁄16 inch on either side of it. Bedding the breech end of the barrel to the front of the chamber area (roughly 1½ inches to 2½ inches in front of the receiver) will help to support the barrel, and will usually aid in increasing accuracy. If the barrel is a heavy contour, a small amount of modeling clay in the barrel channel near the forend tip while the bedding compound is curing will help to support the weight. If any voids are visible in the portion of the bedding completed so far, now is the time to fill them. First, clean out and slightly roughen the voids with a small scraper or wood chisel. Using a cotton swab, clean out the voids with TCE or lacquer thinner. Allow to air dry until no trace of solvent or thinner odor is present in the void area. CAUTION: Both TCE and lacquer thinner can damage fresh bedding as well as stock finish if allowed to "pool" on it. Check the solvent or thinner maker's instructions for specific warnings relating to their use. Check the tape on the sides, front and bottom of the recoil lug to be sure that it is still intact, and replace if necessary. Following our instructions, recoat the barreled action, including the taped areas on the recoil lug, with release agent. Recoat the front guard screw with release agent. Mix enough bedding compound to replace the wood removed from the recoil lug areas, the barrel breech, and any voids to be filled, plus about 25% extra. Secure the stock horizontally in a padded bench vise with the action area facing upward. Put the bedding compound in the stock. It may be helpful to use a 10cc polypropylene syringe with bedding compound in it to fill any voids. Do not overfill the voids, as any excess bedding compound will cause high spots in the bedding job. NOTE: If you fill the corner between the front of the recoil lug and the barrel with bedding compound (placed directly onto the steel), you will eliminate most instances of bubbles or voids in the bedding at that area. Place the barreled action into the stock. Tighten the guard screws or stockmaker's hand screws just firmly enough to hold the barreled action in place. Be sure the action is fully down in its inletting and the horizontal centerline of the barrel is at, or very slightly above, the top of the forend.

Allow the bedding compound to cure to "handling



Shows the Remington M-700 BDL SS DM stock. Note that the area around the action has been roughed up and anchor holes have been drilled for bedding material. Hole for pillar is drilled and masking tape is applied.

strength" and remove the barreled action from the stock. Clean up any excess bedding compound. Use a good quality stock finish to seal the barrel channel and any areas in inletting where raw wood is exposed. This will help to minimize moisture transfer and possible stock warping through the forend.

Bedding the Trigger Guard-Floor Plate Unit

Many factory inletted rifles and some prefinished synthetic stocks allow the trigger guard's exterior surface to be below flush with the exterior of the stock. When the Adjustable Pillar Bedding Sleeves were adjusted to the stock and barreled action, this situation was corrected by setting the pillar's overall lengths. To "finish" this part of the job, and give proper support to the underside of the trigger guard-floor plate unit, it must be bedded. Carefully scrape away any stock finish in the inletting where you will be adding bedding compound. Coat the trigger guard-floor plate unit, the guard screws and their holes in the receiver, and the inside of the pillar bedding sleeves with release agent. Mix an appropriate amount of bedding compound and put enough into the inletting to allow the trigger guard-floor plate unit to be properly supported when it is cured. Hold the barreled action in a padded bench vise by the barrel, ahead of the forend tip. Place the stock on the barreled action, and put the trigger guard-floor plate unit into the stock. Install and lightly tighten the guard screws, and allow the bedding compound to cure. When cured, remove the guard screws and the trigger guard-floor plate unit and clean up any excess bedding compound. Reassemble the rifle and make certain the floor plate (if it is hinged) is able to function easily through its normal range of movement, and that its latch is also free.



Above: Applying release agent to rifle metal.

Pillar Bedding Blind Magazine Rifles

Rifles with blind magazines (no floor plate assembly), such as the Remington 700 ADL, can be successfully pillar bedded using Brownells Adjustable Pillar Bedding Sleeves. If the diameter of the escutcheon surrounding the head of the front guard screw is smaller than 9/16 inch, you will not be able to use both aluminum adjusting rings. Carefully remove the escutcheon from the stock, and drill a ½-inch hole through the stock for the steel inner sleeve, drilling from the bottom of the stock toward the action side. Drilling from the inside of the stock, next drill a 9/16-inch-diameter hole about ½ inch deep for the thick adjustment ring. (This method can be used on a stock



Right: Remington M-700 BDL SS DM. Note the masking tape on stock and trigger. Also on all but the load-bearing rear surface of the recoil lug. Release agent has been applied to the metal and the tape on the gun.



Remington M-700 BDL SS DM in 7mm STW. Zeiss Diavari 5-15 T* scope. With Nitrex 145-grain ammo. Shows the accuracy of the rifle after pillar bedding the stock and filling the barrel channel with Bondo.

with a trigger guard-floor plate unit that is narrower than 9⁄16 inch at each end for the guard screws.)

Pillar Bedding Synthetic Stocks

Pillar bedding can benefit synthetic stocks by preventing distortion of the action area from overtightening of the guard screws. Bedding compounds will bond to most laid-up synthetic stocks, once any paint or release agents are removed from those areas to be bedded. Many injection-molded stocks are made of materials that will not chemically bond to bedding compounds. These stocks can still be bedded if a series of small (1⁄8-inch diameter), shallow "anchor" holes are drilled or ground into the surfaces to receive the bedding compound, with the holes going at different angles to each other. A Dremel or Foredom hand grinder using a 1⁄8-inch diameter ball end carbide cutter is ideal for this job. CAUTION: Do not drill these anchor holes through to the exterior of the stock! If your synthetic stock is hollow under the breech end of the barrel, a small wood block (one to two inches long) can be fitted to the recess at that point, as long as it is coated with bedding compound on all surfaces. This will help to support the weight of a heavy barrel and will usually aid in increasing accuracy.

Finish Notes

With any bedding compound, let the finished bedding job "cure" for three to ten days before shooting the rifle. Remember, the cooler your shop area is, the longer the bedding compound will need to cure. Make certain all excess bedding compound is removed from the inside of the stock inletting. Be ABSOLUTELY SURE that no bedding compound has "migrated" into the inside of the receiver through the guard screw holes or the cartridge feed ramp. Clean up all traces of release agent from both metal parts and the bedding compound, following the instructions for the release agent. Be sure to put a light coat of a good grade of gun oil on the steel parts to prevent rust.

Reassemble the firearm according to the manufacturer's instructions. Check for proper functioning using Action Proving Dummies. Make sure ALL SAFETY MECHANISMS are fully functional as designed and approved by the manufacturer. If these tests prove satisfactory, test-fire the firearm with live ammunition in a SAFE and APPROPRIATE manner. IMPORTANT! Start the live ammunition tests by first loading an Action Proving Dummy, then a live round, into the magazine. Only after several tests have been conducted in this manner should additional rounds be placed in.

Fixing Injection Molded Stock Problems

*To fix the noisy, hollow butts of
injection molded stocks, inject foam,
or simply fill with packing material and crush it tight.*

GREAT STUFF
BIG GAP FILLER

I have noticed that many of the rifles with injection molded synthetic stocks I have tested in recent years didn't seem to shoot as well as I thought they should. For the most part, they were acceptable, but never quite as accurate as I knew they should be. The problem seems to be even more pronounced in guns chambered for the bigger, more aggressive cartridges. I have always suspected that most of the trouble was with the much too flexible designs of these stocks. I wondered what it would take to correct the problem.

To be honest, I think the main reason that injection molded stocks are so unruly, particularly with bigger guns, is because of forend flexing. On my Remington Model 700 7mm STW I could move the forend back and forth easily and independently of the barrel and this was a gun that uses forend tip pressure on the barrel. If I could move the forend that easily with my hands, the forces of shooting would have an even more dramatic effect. No rifle will shoot well if the bedding is inconsistent, and with this rather fluid bedding situation on the forend tip I wasn't surprised this gun was not accurate. The best that gun would shoot was about three-inch groups with the factory stock, which is edging into "terrible" territory with a new bolt-action rifle. Particularly for a Remington Model 700, which enjoys a much deserved reputation for excellent out-of-the-box accuracy.

Rather than spring for an expensive new stock, I thought it was a good candidate for pillar bedding and I decided to see what I could do with that misbehaving STW. But, my first attempts were disappointing. Even after pillar and glass bedding the stock, the rifle wasn't as accurate as I felt it should have been. I was pretty sure the problem was with that forend flexibility and I decided to float the barrel and remove any hard contact near the forend tip. But it still wasn't all that accurate. The stock was so flexible that my guess was that it was flexing and hitting the barrel as I fired the gun. The stock must be a lot more rigid than it was if good accuracy was going to be achieved.

The first step was prepping the barrel channel the same way as the action area for pillar bedding. I roughed up the surfaces with a hand grinder and drilled several anchor holes at different angles. I drilled the anchor holes any place there was enough material. Then I used a hand grinder tool with a cutter blade to undercut a lip the entire length of the barrel channel just under the top of the stock, and on both sides. This acts like a mechanical anchor to lock the bedding to the stock in the event the compound will not adhere to the stock material. I covered the barrel with

BULLDOG
ADHESION PROMOTER
MAKES PAINT STICK

This product helps bedding compound stick to injection molded stocks.

two layers of two-inch electrician's tape (this was before I discovered the .010-inch tape from Brownells) and coated the tape with car wax to act as a release agent. I sprayed the stock with Outers Crud Cutter degreaser and let it dry. Then I sprayed Bulldog Adhesion Promoter agent to help the bedding material bond with the stock. I bought this at an auto parts store and it's designed to aid paint in sticking to plastic body parts. I reasoned that it would probably help things stick to the injection molded stock as well. I can't say for sure that it made a difference, but every time I have used it, the bedding compound has stayed put. Several times when I did not use the adhesion agent, the compound became loose in the gun, so the evidence would support that it works as claimed.

Next, I filled the stock with fiber-enhanced auto body filler, available at any auto parts store. This two-part filler is lighter than glass bedding and it's relatively strong. While I don't believe it's strong enough to bed load-bearing surfaces such as the action and recoil lug, it will work fine for this non-load-bearing bedding job.

After filling the barrel channel with the auto body filler, I assembled the gun quickly as the filler sets up very fast. When the filler hardened, I removed the barrel and action from the stock and removed the tape. The gap from the tape creates an almost perfect floated barrel. With a little spot sanding on the high spots, a business card would pass between the stock and the barrel with no drag. A quick coat of flat black spray paint finished the job. Remember to tape off the rest of the stock, including the bedded area around the action before painting. The stock is much stiffer now, particularly along the barrel channel. This also added some weight, which was welcome in this hard recoiling rifle. Before doing this work I could move the forend back and forth independently of the barrel with my hands, but after this treatment the stock was solid.

The proof, however, is shown at the target. I headed for the shooting range with the completed rifle where I tested four different factory loads; firing four, three-shot groups with each at 100 yards. The average of all sixteen groups was 1.12 inches. The best average was with now-defunct Speer Nitrex 145-grain ammo and measured only .85 inch. The best group I fired was also with Nitrex and measured a dainty .65 inch.

It looks to me like the problem is cured.

MICRO LITE
LIGHT WEIGHT SPACE AGE
body filler
6370

Auto body filler can be used to fill forend on an injection molded stock.

FIXING NOISEY SYNTHETIC STOCKS

Some injection molded synthetic rifle stocks, particularly the early ones, have hollow butts that are noisy when they hit any brush or scratch against anything. The hollow, empty space acts as a sound chamber and amplifies the sound and may have turned off a lot of hunters to "plastic" on their rifles. The best solution I have found is to fill the space with the spray foam sold at home improvement stores. This stuff expands and grows and gets all over everything, so tape off the stock with masking tape. Because the butt is so deep, do not try to complete the job all at once. Instead, fill the stock in several sessions. Spray in a couple of inches of foam and allow it to expand and cure for a few hours, then repeat until the stock is full. You can use a sharp knife to trim the excess and then shape it to the opening in the back with a wide file or a Surform tool. Reinstall the butt plate or recoil pad, remove the tape and it's done.

Another approach that is cheaper, faster and easier, but not quite as good, is to fill the stock with those ubiquitous Styrofoam peanuts that are used in shipping. Remove the recoil pad and cram the stock full. Really work them in, crushing and crunching until you fill the space with as much foam as you can, then replace the recoil pad.

Either method only adds a few ounces, but it quiets that hollow sound so common to these stocks.


BARNES

"Pimp My Rifle"

Chapter 5

My .30-06 Model 760 pump action rifle with scratches, dents and worn bluing was a great candidate for a total makeover.

Some of the most popular television shows these days deal with makeovers. Whether it's a house, car, or person, we are fascinated by creating something new and better from the worn and familiar. So, why not do a "total makeover" on a rifle?

It's a great concept and it's an excellent hobby gunsmith project to fix up an old gun. We all have a beater gun or two around that needs "pimping," or if not what better excuse to buy another gun? It probably won't cost much and as long as the the action and the barrel are good, who cares what it looks like? If the bore is good and the mechanics function correctly, it's a candidate for "pimping."

I had planned to do this with my old Remington Model 760 pump action .30-06 Springfield. I bought it new in 1973 and it was my "deer rifle" for many years. The bluing is worn in several places and the stock is dented and scratched. It was a perfect candidate for this "makeover" treatment. So I ordered a synthetic stock, DuraCoat, for a new metal finish and a new scope and mount. But, sentimentality got the best of me.

Every ding and every dent on that gun had a memory associated with it. For example, the bluing is worn off the left side of the barrel in an oval patch. I recall how it happened because it was the day I got lost deep in the Green Mountains of Vermont in a raging blizzard and missed a chance at a buck I had pursued for years.

I found his tracks early that morning and followed them all day. By late afternoon, the wind was blowing snow and sleet into my face and I had to squint through my eyelashes to see where I was going. I pounded up an icy hill with my gun in my right hand which was protected by a brand-new glove. As I topped the ridge I spotted the buck and a young apprentice running for cover.

The protégé had an impressive rack, but it seemed tiny compared to the one on the other buck. This buck was finally mine. I had spent hours shooting at moving targets with that rifle and there was no way I could miss. I raised my gun and sighted through the scope. The driving snow turned my view into an opaque white wall. I lowered the gun and they were still out there, visible to the naked eye. I raised the gun and once more was blind, I dropped it and they were gone.

Hours later I staggered into camp. I was hungry, cold, angry and discouraged. As I put my rifle in the gun rack I noticed that a spot of bluing on the barrel that had been worn away by the new abrasive leather of my glove-clad thumb. I was pretty upset then, but now it reminds me of that day, which was one of the best in a long line of hunting days. I never did get that buck, but I think about him every time I see that worn spot on my 760.

Total Rifle Makeover

The finished version of our Winchester Ranger Model 94 rifle makeover.

With my aborted "project" gun safely ensconced back in the vault, I set out to buy another Remington pump rifle. The problem is I couldn't find one at a reasonable price. I guess I am partly to blame for that. I have written two books about tracking deer with the legendary Benoit family, *Big Bucks the Benoit Way* and *Benoit Bucks,* and both have been successful. The Benoits shoot an amazing number of big whitetail bucks and they do it with Remington pump action rifles. That has made these guns very popular here in the Northeast and a used one, even a beater, commands a premium price.

I was running up against a deadline for this book and decided that an alternative might be the way to go. While traveling on business, I stopped at a gun shop about two hours from my home to see what they had kicking around. I found a Winchester Model 94 Ranger in .30-30 Winchester on the shelf and wearing a price tag of only $150. I have an interest in lever actions lately, partly because they are what I started hunting with forty years ago and partly because of all the Cowboy Action Shooting I am doing. So, I bought the old beater and decided to use it for this "Pimp My Rifle" project.

There was also an older Savage Model 99 lever action in .300 Savage right beside it. That gun begged and whimpered until I agreed to take it home as well. I usually stop at this gun shop when I am passing by and I think they have some kind of magnetic field on the door that alters your brain activity with subliminal messages, because every time I stop in there I buy two guns. The last time was only a couple of months earlier and I left with a Remington Model 14 pump action rifle in .30 Remington and an old-style Ruger M-77 bolt action in 7X57 Mauser. Whatever that gun shop is doing, it borders on marketing genius.

I cleaned the bore on the .30-30 and it looked like it was in good shape. Next, I loaded a few cartridges and made sure it would shoot. It was hard to check the accuracy because the front sight was damaged and looked like a confused beaver had chewed the top off of it. It didn't matter because I had planned to replace it with a fiber-optic sight but until I did, the best I could do was make sure the gun would shoot and that it had minute of backstop accuracy.

The hardwood stock was stained to look like walnut, but like a country cousin no amount of makeup could hide its plainness. The finish was worn and chipped and there were a few dents here and there. The bluing on the metal was worn and the receiver was pitted with rust. But the part that shoots, all seemed to be in good shape. It appeared to be a good candidate for the project, so it was anointed worthy.

Left: "Pre-Makeover" Winchester Ranger Model 94 rifle.



Note the front sight damage.



Note the rust on receiver around the loading gate.

Note the dent of the plain wood forearm.

My son Nathan was helping me on this and he took the stock and forend off the gun while I gathered up some tools. The next step was to take the rest of the gun completely apart. That included using a punch to drive the rear sight out of the dovetail. The front sight on a Ranger Model 94 is also dovetailed into the barrel, as opposed to most Model 94 rifles that have a ramp on the barrel with the sight on the ramp. So, I also drove the front sight out of the dovetail. Because the front sight was damaged and useless and I had plans to trash the rear sight, I used a steel punch. If I had wanted to save them, I would have used a brass or nylon punch. I ordered a new fiber-optic front sight and an FP-94 SE rear peep sight from Williams.

The action was caked with grease and gunk, so all the metal parts went into the solvent tank to soak for a while. While they were soaking, I sanded the wood to rough up the finish and I filled the dents with automotive body filler. My idea was to paint the plain wood stock black so it would look like synthetic, so it didn't matter that the body filler was a pink color.

In a project like this, the stock has the most options available. (They are the only "stock options" I understand. I tried the others and they seem to just be a great way to get rid of money.) In this circumstance I am painting the stock, which is the simplest and fastest way to the end result. Another option would be to replace the stock as I had planned to do with the Remington 760. In that case I had a synthetic stock, but there are also laminated wood stocks and, of course, you can always upgrade to a finer grade of walnut. There are many aftermarket synthetic stocks available for most rifles, far too many to list. I will note that I have had very good luck with High Tech Specialties, Bell & Carlson and McMillan Fiberglass Stocks: Boyds Gunstock Industries has a good selection of laminate wood and wood stocks. I have used a lot of their rifle stocks over the years and can highly recommend them for quality, fit and finish. If you are feeling really frisky, consider a high grade walnut stock blank and make your own stock. You will notice that project is conspicuously absent from this book, as is anything on checkering. I have tried them both and like Clint Eastwood said in one of his best movies, "A man ought to recognize his limitations."

Perhaps the best alternative is to simply refinish the wood on the gun. This is an easy project these days with the many kits available. Simply strip the old finish and sand the stock until it's smooth. If you want to stain the stock, do so at this time. It's best to try a little of the stain first in a place that will not show, such as the barrel channel or under the butt pad. After staining, use a stock filler to fill the grain and pores and follow with a few coats

Degreasing parts of the Model 94.

of final finish. Remember to follow the instructions with the final finish. Most will recommend light sanding or using steel wool between coats. I have had good luck with Birchwood Casey products for refinishing and am now trying some wood finishing products from LCW, the makers of DuraCoat. I don't have a lot of experience with them at this time, but I like what I see so far.

But my goal was to do the project fast and easy and get a unique look for this Model 94. Flat black paint was my secret weapon. I gave the stock two coats of flat black primer and followed with four coats of high quality flat black spray paint. That should have been the end of it.

I hate going through life clumsy and this was another reminder that I am stuck with that affliction forever. I had the stock and forend hanging on wires from a handcart (like you would use to move a refrigerator) parked in front of the shop so they could air dry. At the end of the day I was wheeling the cart back inside when the stock fell off the wire and landed on the crushed stone in front of my shop. I couldn't stop myself in time and I stepped on the stock. The paint was still soft and it was ruined. I tried to sand out the bad spots, but it just wasn't working. Part of that was because I got in a hurry and tried to do it that night when the paint wasn't completely set. The paint balled up under the sandpaper and made a mess out of everything. So I put it on the bench, locked the shop and headed to the house for a drink to drown my sorrows.

The next morning I used paint stripper to clean the stock down to bare wood. Then I sanded it with several decreasing grits of sandpaper until it looked ready for some paint. I hung it back on the same wire, but this time I twisted the wire back on itself. Two coats of primer and four coats of paint later, it looked pretty good.

To add a "touch of class" to the "Pimp Rifle," we decided to jewel the hammer, the trigger, the locking bolt and the link. The link is the big block at the bottom of a Model 94 rifle that the lever passes through. It moves as the gun is opened and drops down. This piece fills the bottom of the action and is an excellent candidate for jeweling.

The hammer looks great, as does the locking bolt. The hammer you can see, but the bolt you will need to take my word on. The Williams receiver sight that we installed covers it up. If I had realized that in the beginning, I would not have wasted the time involved in jeweling the locking bolt. (Actually, I just polished the part while Nathan did the actual jeweling on the bolt.) The trigger is another thing altogether. It's a casting and the metal didn't polish up or take the jeweling as well as I had hoped it would. I suppose I could have worked at it for a while to reshape it with a file and add a higher polish. But, I simply cold blued the part instead. I wasn't satisfied with that result and finally decided to give it a coating of DuraCoat. The link though, looks great.

Klean-Strip
STRIP-X
STRIPPER
FAST
TOUGH
EASY

Stripping the old finish off a stock.

Painting the stock.

Any carbon steel part can be jeweled. Jeweling is also called Engine Turning and Damascening. It is the process of polishing small swirls into the surface of the metal. This is usually done in an overlapping "fish-scale" pattern. It adds a nice touch to any rifle and is very easy to do. It also holds oil better than non-jeweled metal to prevent rust. Jeweling is sometimes done inside a gun to reduce friction, but in this circumstance we are using it for cosmetics only.

The key to a good jeweling job is in the preparation. The part must be polished before starting. I polished the hammer sides and the top of the locking bolt on flat bench stones, starting with fine India and finishing with a hard Arkansas. The key is to just remove any machine marks and polish the surface without removing any more metal than is absolutely necessary. Check the progress often and as soon as the entire surface shows the same sheen, move to the next finer abrasive. I finished with a buffing wheel with red jeweler's rouge buffing compound. One tip while buffing with a wheel is to watch the angle and where on the part you are buffing; if the buffing wheel catches the front edge of the part, it will snap it from your hands and fling it against whatever is behind the buffing wheel. This can put holes in the wall, damage the part and cause harm to you or any bystander. Do not let the wheel get close to the top edge of any part. Polish to just past the halfway point, then reverse the part and polish from the bottom up until they meet.

The link was not perfectly flat, so I couldn't polish it on a stone. It was also very rough and needed more than a simple polishing. I had a lot of machining marks that had to be removed, as did the old bluing. So I clamped it in a soft-jawed vise and used a fine, single cut file to draw file the surface.

Draw filing is a technique to use a file in a way that gives a better finish. It's often used to create the final surface on a part and to remove any machining marks. One good example is an octagon barrel. While the mass-produced barrels are done with CNC machines, the old craftsmen and those still practicing their trade used draw filing to make the flats. A craftsman would pride himself on a perfect flat on the barrel, one that is straight and free from ripples. The best file for this is a Brownells draw file, but any new, single cut file will work for draw filing.

The file is often called a "poor man's milling machine" and if that's so, then draw filing is the finishing cutter. With regular filing, the file is pushed longitudinally across a piece of metal. With draw filing, you use a single cut file and operate it like a draw knife in woodworking. That is, you hold both ends and pull it toward you across the work. In other words, draw filing is basically to hold the file at a 90-degree angle to the part and to pull both ends to drag it along the part. Because the file's teeth are at 45 degrees, you have to be careful not to let the file drift to the side while making a cut. The angled teeth will try to force the file to the side and you need to hold it against that so the teeth cut, rather than ride to the side. I find it's helpful to grasp the file on both sides and push the knuckles of my index fingers against the sides of the part. This keeps the file from shifting to the side and keeps the teeth cutting. Again, use only a single cut file, and

Jeweled hammer on Winchester Model 94 Ranger.



Jeweled link on Winchester Model 94 Ranger.



Buffing and polishing wheel.



Draw filing

remember, files only work in one direction, so don't back up. Keep the file clean, as any chips embedded in the teeth of the file will cause damage to the surface. Keep a nice steady pull without excessive down force, and you can make a surprisingly flat and polished surface with very little effort and a minimum of cleanup work.

After draw filing the link, I polished it with a wheel and an abrasive polish, then I cleaned the wheel and added jeweler's rouge and gave it a final polish.

Before jeweling, all the polished parts must be free from oil, grease or buffing wax. I used degreasing spray and a large, clean, cotton cleaning patch to scrub them. Then I sprayed again with degreaser, letting it run off and air dry.

I have heard for years that a pencil with a rubber eraser makes a good jeweling tool. Simply clamp it in the drill press, smear some abrasive lapping compound on the metal and go to town. The first time I tried this it ended with an empty pencil box and one very frustrated hobby gunsmith. In that case I ended up abandoning the project and using a different finish on the part. This time I got a little smarter and ordered the tools the pros used from Brownells.

They basically offer two different tools. One is a small brush with metal bristles. This is held in the drill press, or better yet in the spring-loaded brush holder that Brownells offers. This holder helps to regulate the pressure used and gives a better result. The bristles tend to spread, so there are some small O-rings included in their kit that slip over the brush and help hold the bristles in place. The O-ring tended to migrate up the brush, but I found that I could hold it in place with my index fingernail, letting it slide along the oiled surface and that would keep it from slipping up the brush.

Mix a small amount of 120-grit Silicon Carbide Abrasive with a few drops of Do-Drill oil to form slurry. (They are also included in the kit from Brownells.) Spread the abrasive slurry on the part and lightly touch it with the spinning brush to form a swirl on the polished surface of the metal. The brushes work well on any flat surface and are the best option if you are doing curved surfaces like a rifle bolt, as they will follow the contours.

The other method, and frankly the one that worked a lot better for me, was to use Cratex rubber rods impregnated with abrasive. While you can simply chuck a rod in your drill press, they are fragile and break easily. The best way is to hold the rod in a "Damascening Tool" sold by Brownells. This has a brass rod that will hold the rather delicate abrasive rods, but is small enough to allow working around bolt handles and other obstructions.

It is not necessary to use any abrasive compound with the Cratex rod, simply apply the spinning abrasive rod to the polished surface of the part. Keep the end of the rod trimmed with a file so it stays sharp and square. This by far gave me the best results. I suspect that the brush has a longer learning curve as I know they can provide excellent results, but the Cratex rods turned in a good job the first time out of the chute. This is, of course, on

TOOLS FOR JEWELING



Cratex rods and holder.



Shown with Winchester 94 hammer.



Shown with Winchester 94 link.

Jeweling the link on a Model 94.



flat surfaces as they cannot follow contours as well as the brushes.

The most important thing is to have a way to keep your lines straight and the swirls indexed at the correct spacing. The pros use a milling machine, but you can get just as good results with a drill press. You will need an indexing table or vise on your drill press. Clamp the piece in soft or rubber jaws to prevent marring. Plan out the pattern on the piece. Some pieces may have a long narrow section, such as the hammer spur. This requires that the pattern follow the shape of the piece. For the best results, you will want to use that same line for the rest of the piece. There may be gaps, but simply skip past the gaps to keep the same lines throughout the entire piece.

The indexing vise should be clamped to the drill press table. Set the piece up so the tool is centered at the end nearest to you. Run the piece all the way to the other end to make sure that you have everything lined up properly and that the piece is still centered with the jeweling tool at the opposite end. Make any necessary corrections to ensure that everything is square, and then lock down the drill press table. Run the indexing vise back to the edge closest to you and start with the tool about halfway on the edge and centered on the piece. (Or you can start at one side edge rather than the center, depending on the results you are looking for.) Turn on the drill press at a relatively high speed and lightly touch the tool to the metal and let it run for a few seconds. Now index so that the next swirl will overlap the first by ⅓ to ½. On my indexing vise, that is one complete revolution of the handle for the 3⁄16-inch Cratex rods. Form the next swirl. Watch to see how much pressure and time it will take to give you the result you desire. Stop the drill press and wipe the piece with degreaser and a cotton patch, but do not remove it from the vise or move the vise. Check the swirls with a strong light. If you have the result you want, move on. If you do not, reapply the rod to the same spot again. The swirl will be subtle so don't get upset if it's not as defined as you expected. Remember, you are going for a total finished effect and the whole is much more dramatic than any single mark. One or two swirls will not be impressive, but when you are finished and are able to hold the piece and turn it back and forth so that it catches the light on the entire jeweled surface, things change and the effect can be startling.

Once you know how much pressure and time is needed, index the vise and make the next swirl. Continue until you run off the end of the piece being jeweled. Do not make the next line in the opposite direction as all lines should be made in one direction. Run the indexing vise all the way back to the end of the piece closest to you again. Now index left or right to give the same amount of overlap. Make the next line of swirls, overlapping the first line and each other. Continue with this pattern until you are to the edge of the piece. Now return to the center and do it on the other side of the piece until that is covered with jeweling. Or if you started on one edge, continue until you have jeweled everything to the opposite edge. Once you are done and satisfied, remove the piece from the vise, degrease it again and then coat it with a rust preventive.

This is fine for flat parts like those we did on this Model 94 "Pimp Gun." But for a round part like a bolt, you will need to add another tool. A jig to hold the bolt and to index it around the center. In this case, you will clamp the jig in your indexing vise and keep the tool centered. Run the line down the length of the bolt, and then return to the start. Turn the bolt in the indexing jig for each new line. B-Square makes a bolt jig that is marketed by Brownells.

The rest of the metal parts were retrieved



Jeweling a rifle bolt, using the B-Square fixture and an indexing vise.

APPLYING DURACOAT FINISH

1

1. Final degreasing in preparation for DuraCoat. This tank contains TruStrip degreaser from DuraCoat.

2

2. Measuring and mixing DuraCoat.

3

AIRBRUSH PROPELLANT
NO.17

3. Spraying DuraCoat on various surfaces.

from the solvent tank. The internal parts were sprayed with a degreaser to remove the solvent and then coated with Break Free CLP to keep them from rusting. All the parts that will be visible externally, including all the screws, the hammer, trigger and bolt were again degreased with Trustrip degreaser and cleaning fluid from DuraCoat. This is available in bulk for use in a tank or in an inexpensive spray can. I used emery cloth to buff the blued surfaces to rough them up and to remove any rust. The gun had a scope on it at one time that had been removed and the mount screw holes were empty. The two rear holes would be used for the peep sight, but the front two holes needed plugs. Brownells offers a set of plug screws that includes every conceivable size and shape, so I selected two 6-48 plug screws that were short enough to go in the holes until they were flush with the top, but not bottom out. I installed them with a little Loctite to keep them in place. I lined the slots up with the bore for a more "finished" look. Then I degreased everything again with TruStrip.

SUPER PRIMER

Using a hard Arkansas stone to polish the trigger sear.

While I had everything apart, I polished the trigger sear with a hard Arkansas stone to smooth up the trigger pull a bit. I also very lightly polished the trigger notch.

DuraCoat is a modern gun coating that is unique because it can air dry. Most of the gun coatings on the market require an oven to cure, which is tough for a hobby gunsmith to handle. Most kitchen ovens are too small and a commercial oven is very expensive. DuraCoat eliminates this problem. An oven speeds the process up, but the coating can air dry with equally good results.

While I have a spray gun and compressor to apply DuraCoat, I wanted to try their $49.99 DuraCoat EZ Finishing kit as this is what most hobby gunsmiths will use to start out with. The kit comes with an airbrush sprayer with all the hoses and couplings, a nine-ounce can of airbrush propellant with a valve, a color bottle with cap, four ounces of DuraCoat in any stock color, one ounce of DuraCoat Hardener, two ounces of DuraCoat Reducer, a 16-ounce aerosol can of TruStrip and an instructional DVD. This kit is designed for the hobby gunsmith who isn't looking for a big investment in spray guns and air compressors and it has enough material to coat two to four firearms. The airbrush is powered by a can of propellant rather than an air compressor. If you want to do more, simply buy more compressed air and more DuraCoat, the airbrush will work for many guns if you take care of it.

One thing that is not included, but might be needed in a project like this is Durafil. This is a filler product that is sprayed on first to fill in any gouges or rust pits that might be too deep for DuraCoat to cover. The pitting on the receiver on my Model 94 was mild, so I took a chance that the DuraCoat would cover it and did not use the Durafil. However, if I had deeper pitting or gouges to fill, I would order a can of Durafil and start with that as a base coat to fill these spots.

DuraCoat is offered in a wide selection of colors and given the theme of "Pimp My Rifle" I had considered something like Electric Lavender. I am secure enough in my manhood to use a rifle like that, but I just couldn't do it. In the end, this is a hunting rifle and I wanted something more to that theme than a parade gun for Gay Pride Day. I settled on a color called SOCOM which is designed for "tactical" use on rifles for police or military. But, this low-key, nonreflective gray with a slight hint of green was a perfect color for a hunting gun as well. There are 55 stock DuraCoat colors, seven electric colors and clear. So undoubtedly there is a color to suit any taste.

It was a simple matter to follow the directions to set up the airbrush and to mix the DuraCoat. I spent a minute adjusting the air pressure and the volume of DuraCoat by spraying at a piece of newspaper until I had the spray pattern just right. It's best to apply DuraCoat in very thin layers, so I adjusted for a fine spray. Then I coated the barreled action, the magazine tube, the bolt, the heads of all the screws, the trigger and all other exposed parts with DuraCoat. The jeweling on the hammer and the link was masked off with blue, painter's masking tape and the other surfaces on these pieces were coated. One thing to remember is that any screw that shows on both sides of the rifle must be coated on both ends. Do you wonder why I know that? I coated only the heads on those screws. Of course, I discovered that mistake after cleaning up the spray gun and putting it away. I had to mix up more DuraCoat, spray the end of the screws, then dump out the excess and clean the airbrush again. It's a lesson I will remember.



Bryce Towsley proves he is secure enough in his manhood to use a lavender rifle

BROWNELLS
POWDERED
ROSIN
#083-016-100
SPECIALLY PREPARED TO PREVENT CAKING

A rear sling swivel installed on the Winchester Ranger Model 94.

Inset: This front swivel would not stay in place until it was coated with rosin.

I also coated the barrel band and the forend band. Because I had planned to replace the rear sight with the Williams peep sight, I had a plug to fit in the dovetail for the rear sight. I made sure to degrease it and coat it with DuraCoat as well.

All the parts were left undisturbed to air dry overnight and I gave it a full 24 hours before putting the gun together. It took a little filing and fitting to make the Williams front sight fit in the dovetail. But with a 60°-Standard Slot file from Brownells this was easy. This file is a true parallel, 3-square file with only one side cutting and the other two sides safe. The file can be used to widen dovetail slots in gun barrels without danger of deepening the slot or damaging the edge not being worked on, because only one side cuts. As a true parallel file, you have absolute control over the angle of the dovetail, which is impossible with tapered triangle files. It should be in every gunsmith's shop. I used it to adjust both the too-tight dovetail slot in the gun barrel and the corresponding dovetail on the sight. Once the sight was in place, I degreased it and put some cold blue on the shiny spots that were showing. After the color was right, I hit it with a little oil to stop the bluing action.

Another good piece of advice is to pay attention to how the parts fit together when you take the gun apart. In the excitement of starting a new project, it's easy to just start taking things apart, thinking you've got it covered. But then later you will find yourself staring at a piece and wondering what the hell it is and where it goes. It has been a while since I had a Model 94 fully apart and that happened to me here. The exploded view book told me where the "cartridge guide left hand" and the "cartridge guide right hand" went, but it was a damn liar. Nothing would fit no matter what I tried. I even sent my son Nathan to the gun vault to gather up some more Winchester Model 94 rifles so that I could peer into their bowels and cipher their mysteries. I knew I had everything right, but it wasn't working. Then out of desperation, I tried reversing them and putting everything in backwards, and they fit. Ok, so maybe it wasn't backwards after all, maybe it was right.

That accomplished, I was off to the next challenge, which was getting all the parts and springs back in the trigger and hammer assembly. The key is to be patient, keep trying and never, never force anything. Parts are made to fit and if they do not, it's you—not the parts—causing the problem. I have a buddy who has a bad habit of trying to make things fit the way he wants them to rather than how they are designed to fit. If he is having trouble, the first thing he does is start modifying the parts. He will grind, file, drill and sand, but, of course, in the end, nothing ever fits quite right. He will curse the manufacturer and claim it's shoddy workmanship and a decline in the American work ethic, but in the end he has things all screwed up. The better approach is to work slow and think more than you act. It all fit together nicely when you took it apart, so it should all fit back together again when you put the pieces back. If it does not, the problem is very likely with you and what you are



Two examples of oval patches where the bluing has worn off of this Remington 760, due to abrasive leather gloves.

DuraCoat®
DuraCoat Products
DuraCoat
Sniper Green

Some DuraCoat color options for this Colt 1911 handgun.

doing and not with any inherent defect in the parts.

Nathan added a set of Michael's of Oregon sling swivels, using the methods detailed elsewhere in this book. The front was a clamp that went on the magazine tube and it would not grip tight enough. It would turn and slip with only a little pressure. So I had him take it off and put a little powdered rosin on the piece. That solved the problem and it now grips like they are welded.

Once the gun was put back together and tested for function, I let it set for a week so that all the DuraCoat and the paint had a chance to harden.

This rifle now looks dramatically different. It went from a scratched, dented and rusted, decrepit-looking rifle to what one recent teenage visitor to my shop proclaimed as "way cool!"

The total work time was about 12 hours. But, that included fixing the mistakes (like stepping on the stock) and figuring out how to do a lot of the work and shooting some photos. With some more experience, I think a project like this one can be completed in a day.

I still have my eyes open for a Remington pump action rifle for the next "makeover" project. I am planning to cut the barrel down to 20 inches, swap out the stock and coat it with a dark green DuraCoat called Sniper Green. I'll fix up the trigger and add a 1.5-5 Leupold Vari X III scope, which I'll also DuraCoat. It will be the ultimate whitetail hunting "woods" rifle, and will be unique in this world. I already have an imported 1911 pistol in .45 ACP which I bought new with a project in mind. I will strip the gun, add new sights, an ambidextrous safety and a flared magazine well. I'll tune up the trigger, tighten the slide bushing and then coat the slide and frame in contrasting DuraCoat colors. I am thinking of OD Green for the slide and flat black for the frame, but I have not entirely ruled out the Electric Lavender option. No matter what color it ends up, it will be an inexpensive IPSC competition gun as well as a cool carry gun. Then after that, I am planning on a . . . .

Well, I guess you can say this project was addicting. It was an inexpensive and fun way to add some "custom" guns to my collection. I made some mistakes, but that's how you learn. I can see that perhaps this could turn into a television series; I think I'll call it "Pimp My Piece."

Anybody know a good agent?

An Excuse for a New Rifle

Chapter 6

Custom .458 Winchester on a Charles Daly Mauser action. Built by Bryce and Nathan Towsley. Kahles 1.1-4 scope, Warne mounts.



Turning fifty is destined to be a love/hate thing for me and I have no doubt it will be a traumatic event in my life. The "love" part stems from the fact that I wasn't sure I would make it that far. Much of my family doesn't and I inherited the problems that cause a lot of them to check out early. It looks, though, like I will beat the odds and for that I am grateful.

On the other hand, my fiftieth birthday represents a passing through the gate into an age class that none of us really wants to venture into. It's one of those milestones in life that causes us to run head-on into our mortality. It's a rude message pointing out that a lot more of my life is behind me than ahead. Turning fifty is a reminder that my days in the field and nights around the campfire are diminishing, that what makes life worth living is no longer a well-stocked supply room, but is instead a dwindling and horded cache.

This birthday is traumatic, depressing and unavoidable, so I did what any panicked midlife crises kind of guy would do, I booked a safari in Africa. I leave on my birthday.

Of course, I needed a new dangerous game rifle (any excuse, right?) But, rather than another "store-bought" gun, I decided to build it myself. Ownership of a custom rifle is pretty appealing to most shooters and hunters, but the idea of paying for one is not. Well-executed custom rifles built specifically for hunting are for the most part works of pragmatic art, but some of them cost as much as a good used car.

I am a blue-collar guy with a rich man's appetite and that means I have to pick and choose. The safari got the bucks, but the rifle got my attention. I figured if I couldn't afford a new custom rifle, I could build it myself. The truth is after paying for the safari, there wasn't much money left for new guns and this looked like a solution to the age-old problem of feeding the need for another hunting rifle.

Build Your Own Custom Rifle

Applying a DuraCoat finish to a rifle barrel and action.

Building a rifle would seem on the surface to be an impossible task for the uninitiated. When first starting out on the journey, the feeling will likely be that it might be easier to design and build a new space shuttle. But by the time you are shooting the rifle at the range, you will have reached an understanding that this really is not all that complicated or difficult. You will also experience a feeling of immense satisfaction. It is very cool to pick up a rifle and say, "I built this." It's also OK to gloat a little when you show it to your hunting buddies. At least it better be, because I have done a bunch of it.

I wanted to approach this like an advanced "hobby" gunsmith. Something that a reasonably well-equipped shop can do, but without the need for a lathe or milling machine. As this project progressed, it became clear that building a rifle like this is easy and fun. It required a few new tools, but tools are like guns, you can never have too many. This first rifle inspired me to build several more and most of the tools find continued use in those projects, so the cost is continually spread out. It has also opened the door to several aspects of gun work that I might not have otherwise have explored; for example, metal coating finishes and fitting a new barrel on an existing action. This approach to building a rifle gives you a "custom rifle" finished product at off the shelf pricing and it's one of the best projects a hobby gunsmith can tackle.

What follows is the step-by-step journey of building the rifle. Most of this will apply to any bolt action rifle. For example, my next gun is already in the works and it's going to be a .358 Winchester on a Remington short action Model 700 rifle. The Remington will require some different tools than the Mauser. For example, the action wrench will be different as will the bolt lapping tools. But, other than a few specialty tools, the process is the same. The only real difference in building that .358 Winchester and this .458 Winchester is the feeding system. The Remington is a push feed action and the Mauser is a controlled round feed action. Other than the steps directly related to the extractor and feeding, there is very little difference in building the two rifles.

Any building starts with the foundation, and the foundation of a rifle is the action. If there is a more famous, or more revered, rifle action among hunters than the Mauser 98, it has escaped my notice. The controlled round feeding is respected in hunting fields around the world and is considered a must for dangerous game rifles.

Controlled round feeding is a bolt action design where the cartridge rises up from the magazine and is captured

This Cape buffalo was taken in Zimbabwe by the author using the .458 Winchester rifle he built on the Charles Daly Mauser action rifle, as described in this chapter.

by the extractor on the rifle bolt as it is guided into the chamber. Because the bolt has the cartridge firmly in its grasp, the possibility of a jam is reduced. If the shooter short strokes the action, depending on how far the bolt is cycled back, the cartridge stays with the bolt and is either ejected and thrown clear, or is held in position to feed into the chamber. It's as close to a foolproof system as we have for bolt action rifles. While other systems, such as push feed rifles, have their merits, the controlled round feed system is considered the best available for a dangerous game rifle where a jam can get you stomped, bitten, gored, clawed and leaking body fluids.

The Mauser 98 is considered one of the best controlled round feeding designs ever made and it's the inspiration for many of our modern-day rifle actions. It's also the basis for a lot of dangerous game bolt action rifles, including mine.

Another problem with rifle actions these days is it's very hard to find one to build a rifle with. Most rifle makers do not sell actions because of some perceived "liability" issue. That means that you must buy a complete rifle and then remove and throw most of the parts in the trash. This, of course, is wasteful and foolish.

However, Charles Daly is now importing Mauser actions in several lengths and sizes. I selected a magazine length of 3.375 inch. My rifle is in .458 Winchester Magnum and the SAAMI cartridge overall length is 3.340 inch, so there is plenty of room. I also selected the bolt face diameter of .532 inch, which matches with most belted magnums. These actions are offered "in the white" which means that they are not finished or blued. They are available in chrome-nickel steel or stainless steel.



A Brownells Bolt Lapping Tool and lapping compound were used to lap this Mauser bolt.

The first step is to completely disassemble the action. Then degrease everything. Be careful with the small parts and put them in a safe place so they won't get lost. It might be a while before you are ready to use them again, so don't just leave them on the bench. Instead, put them in a container that you can find. Remember that chemically clean steel will rust very fast, so spray some rust inhibitor or oil on all the parts. Make sure that you have an exploded parts diagram so that you can put everything back together. It's easy to forget where the parts fit by the time you are ready to put it all back together.

LAPPING THE BOLT • For the best accuracy in any rifle, the bolt locking lugs must seat evenly and completely in the receiver. Also, by having all lugs bear evenly, the back-thrust stresses placed on the bolt during firing are distributed uniformly; no one lug is subjected to undue pressure. This can aid not only in accuracy and dependability, but will also help prevent premature wear on the action. Finally, if the lugs are lapped with a fine abrasive, the bolt will close with that slick, smooth feeling of quality that is common to custom rifles.

The Brownells Bolt Lapping Fixture helps to maintain constant, even pressure on the bolt while the locking lugs are being lapped to match the receiver recesses. This is simply a tool that threads into the front of the action where the barrel fits, and has a spring-loaded plunger that will apply pressure to the bolt face.

Disassemble the bolt, removing the extractor, firing pin and spring. The extractor collar can be left on, although you should probably remove it to allow coating or polishing later. Degrease all the parts.

Next, a light coating of Dykem or layout blue should be applied to the rear surface of the locking lugs on the bolt as well as the corresponding surfaces of the receiver locking lug recesses or seats. A felt-tip marker also works well here, simply coat all of the contact surfaces on the bolt lugs and receiver.

Install the Bolt Lapping Fixture by screwing it into the receiver threads where the barrel would fit. Apply only moderate pressure to the "T" handle of the Bolt Lapping Fixture to fully seat it against the inner collar of the receiver.

Now, install the bolt and move it into the locked position. It should close hard against the spring pressure from the Bolt Lapping Fixture. Lift the bolt handle approximately 45 degrees and then return it to the locked, or "down," position several times. Remove both the bolt and the Bolt Lapping Fixture. The rear of the locking lugs on the bolt and the locking lug recesses or seats in the receiver can then be examined carefully to determine the extent of contact that is being achieved. This is indicated by the area where the Dykem or felt-pen markings are worn off, showing contact. Anything less than 90 percent contact is unsatisfactory.

Remove the Bolt Lapping Fixture and place a small amount of silicon carbide lapping abrasive (600 or 800 grit) on the bearing surface of the bolt lug recesses in the receiver. Do not allow any abrasive between the plunger and the face of the bolt. The lapping compound should be applied before the Bolt Lapping Fixture is installed through the front of the forward receiver ring. Apply just enough abrasive compound to cover the lug seating area; a small amount will go a long way.

Reinstall the Bolt Lapping Fixture. Put the bolt into the action, pushing it as far forward as possible when closing, to keep the compound from being squeegeed off when you close the bolt. Lift the bolt about 45 degrees and push it down again, repeat about fifty times. Do not raise the bolt far enough to allow the lugs to move out of the lug recesses. If this occurs, you can lap metal off the sloped lead-in surfaces of the lug seat and other areas that should not be tampered with. Remove the bolt and check for the amount of contact on the lug face. This will

BROWNELLS BOLT LAPPING TOOL & LAPPING COMPOUND





1. After applying lapping abrasive on the bearing surface of the bolt lug recesses, screw the bolt lapping fixture into the receiver threads. 2. Install the bolt and push it into the locked position.





3. Lift the bolt to about 45° (not far enough to allow the lugs to move out of the lug recesses) and close it to the locking position repeatedly for about 50 times.

4. Check the degree of lug contact by examining the amount of polish on the bolt lug faces.

be evident by the polished surface on the lugs after you wipe the lapping compound away. It's unlikely that you can achieve 100 percent contact without removing too much metal, so don't set your goals that high, but try for at least 90 to 95 percent. If you are not there yet, put a little more lapping compound on the lugs and go back to work until you hit your goal.

Make sure to clean out every bit of lapping compound from the bolt and action after you finish. It has a way of working into nooks and crevices, so be diligent. This is not something you want left in the gun, as it can cause damage. A parts cleaning tank is probably best, but you can use spray degreaser as well. Finish with shop air and a close inspection.

After completion, apply layout blue or a felt-tip marker to the lugs and lug recesses; reinstall the bolt and the Bolt Lapping Fixture and seat the bolt a few times. Remove the Bolt Lapping Fixture and bolt, and again carefully check to see if you have less than 95 percent on either lug. If so, reapply the lapping compound, reinstall the Bolt Lapping Fixture and repeat the lapping procedure. Once you are finished and the lapping compound is cleaned out of the action, celebrate a little, because you have just completed your first "gunsmithing" operation on this rifle!

It's important that bolt lapping be done before installing the barrel and setting the headspace. Lapping the lugs removes metal and this can have an effect on headspace. So if you decide to do it to any other rifle, make sure that you check the headspacing before shooting the rifle again. If lapping has taken the headspace out of tolerance, it will need to be corrected, which will require some lathe work. But, by lapping the lugs on the rifle before installing the barrel and setting the correct headspacing, we eliminate that potential problem.

POLISHING THE ACTION RACEWAYS • The "glass smooth" actions seen on most custom rifles are a result of a lot of polishing to smooth up the contact surfaces of the moving parts. It's a simple fact that the action of metal moving against metal flows most smoothly when both surfaces are polished. This basic tenant is key to custom gun work. Anytime there are two metal surfaces sliding against each other, if you polish the contact surfaces they will slide easier and make the gun feel smoother.

So, the next step is to polish the bolt raceways for a smoother working of the action. The action raceways are the "bed" on the action where the bolt's lugs ride as the action is being worked. If the surfaces are rough from machining, it will make the action work hard and feel sticky and rough. If they are polished, the bolt will work

BROWNELLS RECEIVER WAY POLISHER







1. Wrap abrasive paper around the head of the tool. Apply a small amount of kerosene or stoning oil to the raceway surfaces. 2. Insert the receiver way polisher into the rear of the action so that the tip rides on the bolt raceways. 3. Keep downward pressure on the tool move and it back and forth to polish the surfaces.

Using a hard Arkansas stone to polish the feed ramp.

Polishing the feed ramp on the Mauser action.

with that slick feeling that makes a custom gun so desirable. In this case I am building a dangerous game rifle and I want the action to work as slick and smoothly as possible. This gun may be called upon to stop a charge from a big and angry critter bent on my destruction and I want each cartridge to chamber as fast and as smoothly as possible.

The first step is to disassemble and degrease the action, but in this case we have already done that. Any trace of grease or oil should be removed, so if you have put an anti-rust preventive on the metal, clean it off with a spray degreaser. Now coat the surfaces to be polished with machinist's layout fluid (Dykem) or color them with a felt-tip marker.

Once again, my tool for this job is from Brownells. It is called the Receiver Way Polisher. It's a heavy bar with a flat at the end with a split in the center. To use it, simply cut a piece of 220 or 330-grit abrasive paper to 1.5 x 2.5 inches. One end is tucked in the slot, the paper wrapped around the tool and the other end tucked in the same slot, then the set screw is tightened to hold it in place. The tool is inserted in the rear of the action and rides on the bolt raceways. Apply a small amount of kerosene or stoning oil and then add elbow grease to polish the surfaces. Keep polishing until you have a uniform, smooth surface. Keep some downward pressure on the tool by using your "off" hand to push on the top of the toolhead as you move it back and forth with your other hand gripping the knurled handle. Take care that it is contacting both raceways evenly.

Stop often and check your progress. You will see the machinist's layout fluid is polished off from the high points and it should give you an idea of where you are in the process. The goal is to remove as little metal as possible while still creating a smooth surface. It may be possible to have the entire surface polished mirror smooth, but with a really rough action that might require too much material removal. However, if you have removed all the peaks, and now have them at a uniform height and well polished, a few valleys will not be a problem. The bolt will ride on the polished and uniform high spots and pass over any low spots. That's not to say that just polishing a few high points is enough. You need to have the majority of the raceway at a uniform polished height. So, shoot for at least 80 percent of the area polished.

There is no point in polishing the raceways and then running a rough bolt over them. However, the bolt is usually much smoother to start, so it's less work. The bolt body can be polished with a cloth wheel and buffing compound. Polish the bottom of the lugs, the surfaces that ride on the action raceways with a hand-held Dremel grinder with a small polishing wheel and buffing compound. Be very careful not to remove any metal from the back of the lugs where they contact the action or from any other surface or edge, other than the bottom of the lugs where they ride on the raceway and polish them only sparingly.

POLISHING THE FEED RAMP • The feed ramp is the angled "ramp" just under the barrel that helps to guide the cartridge from the magazine into the chamber. This ramp will pick up the nose of the bullet and slide it up to the back of the chamber. It should be smooth and polished for the best feeding. I used round and half-round stones with plenty of oil. Then I finished with a cloth wheel in a hand grinder and buffing compound for a final polish.

INSTALLING A BARREL • If the action is the foundation of a good rifle, then the barrel is the heart. The quality of both the barrel and the installation is critical to how well your gun will shoot. A custom gunsmith will buy a barrel blank and then turn the contour on the outside, cut the threads and shoulder, crown the muzzle and ream the chamber. This takes a lot of time, a lot of skill and a good lathe. This is specialty machining that takes years of training to learn. It also requires thousands of dollars of tools and equipment. While it makes sense for a custom gun builder who is making several guns a year, it's beyond the reach of most hobby gunsmiths.

But that doesn't mean you can't put a barrel on your rifle. Actually, it's easy to install a new barrel, even without a lathe. Simply purchase a "short-chambered" barrel. These are essentially finished barrels. They have the final contour on the outside, the threads and shoulder are all cut and the chamber is reamed, all but the finishing. The barrel on my .458 Winchester came from Midway USA. It is the Adams & Bennett Series 3, in .458 Winchester Magnum. It has an F44 Contour, a 1 in 14-inch twist and is 24 inches long. The barrel is chrome moly steel and in the "white."

Short chambered means that the chamber is not reamed to its full length and is left about .050 inch short. That allows you to set the chamber for the exact headspacing needed for your action. Doing that will require finish reaming to the correct depth. That sounds a bit intimidating, but if you pay attention to what you are doing, work slowly and think before you act, it's not all that difficult.

In addition to a chamber reamer and a wrench to turn it, you will need a set of "go" and "no-go" gauges to check headspace. These are gauges that look a little bit like a cartridge and are designed so that one is slightly longer than the other. To use these gauges on a controlled feed action like the Mauser, slide the rim in behind the extractor like a cartridge and close the bolt. If the extractor is not on the bolt, simply place the gauge in the chamber and close the bolt. If the bolt can close on the "go" gauge, it indicates that the chamber is long enough to accept a cartridge. The "no-go" gauge is slightly longer and the bolt should not close when that gauge is in the chamber. If the bolt does close, that indicates that the chamber is too long and has what is commonly called "excessive headspace." In this circumstance it means you have cut the chamber too deep. If you make a mistake reaming the chamber and go too deep, the barrel must be turned on a lathe and a small amount removed from the end to shorten the chamber enough to start over. Those of us hobby guys without a lathe should take all precautions possible to avoid that. However, if you do go too far with the reamer, it's not a total disaster. It just means you need to take the barrel to a machine shop and have them turn a little metal off the shoulder and an equal amount off the back of the barrel. If the barrel is stamped with lettering so that it must index to exactly the same place when tightened, you need to remove the length of one thread from the rear threaded portion and the same amount from the shoulder. That is so that the lettering will line up properly when the barrel is reinstalled. However, with a blank barrel with no lettering you can remove a small amount of metal, just enough to put the chamber back into a "short" condition.

There are a couple of ways to go at cutting the chamber. The first is to install the barrel in the action and then ream a little. Clean the chamber and try the "go" gauge. If the bolt doesn't close, remove the gauge, put the reamer back in and ream a little more. Then clean and try the gauge again. This approach is acceptable if you are more patient than Job himself, because it's going to take a while. It also opens the door to a lot of opportunities for mistakes or damage to the reamer, simply because you are putting the reamer in and taking it out so many times.



Threads of Mauser action & barrel

BELT MAG GO
NO-GO
PTG 9/04

"Go" and "no-go" gauges

However, this approach was my plan until I called my buddy and master gunsmith Mark Bansner. He explained how the pros do this job.

Doing it the way Mark explained will require a depth micrometer. It must be a micrometer, as a dial caliper is not accurate enough for this kind of work. Make sure that the bolt does not have the firing pin or spring installed. Place the bolt in the action and close it fully. Measure the distance from the end of the action to front of the bolt face. Write the number down. If it's your first time using a depth micrometer, it will be confusing as you are reading it backwards from a conventional micrometer. Now measure the distance from the shoulder on the barrel to the end of the barrel threads. Subtract that barrel thread shank length from the receiver to bolt face measurement and write down the number. Make absolutely sure that the chamber in the barrel is clean and then place a chamber "go" gauge in the chamber. Measure the distance from the back of the gauge to the back of the barrel. Subtract that number from the first number and the difference is how much you need to lengthen the chamber. The two numbers should match before installing the barrel. Actually, Mark likes to add in .003 inch of "crush factor" when installing a new barrel. So the number should be .003 inch less than equal before installing the barrel. That makes the chamber .003 inch too deep, but when the barrel is tightened to the receiver, the threads "crush" and make up the difference.

The chamber reamer has a ⅜-inch square to drive it and can be turned with a large tap wrench. Always turn only in the direction that the reamer cuts. Never back up any reamer or cutter, as that can chip the cutting surface and ruin the reamer.

I didn't trust myself enough to go all the way, so I stopped a few thousandths of an inch short and installed the barrel. Then I inserted the reamer and turned it a little, cleaned the chamber and tried the "go" gauge. Then repeated the process. Reaching through the action to turn the reamer proved to be a challenge. I finally used a long ⅜-inch drive socket wrench extension. I reversed it so that the female end would fit over the reamer and clamped a pair of vise grips on the male end to turn it. After I completed this rifle, I did a little research and found out that it would have been far better to use the Clymer 12-inch rifle extension or the Clymer Rifle T-Handle. I already ordered both from Brownells' for the next job.

Headspacing is correct when the bolt will close on the "go" gauge, but will not close on the "no-go" gauge. A lot of shooters like a "minimum headspace" chamber. That is one that is on the tight side of the tolerance, which is to say a chamber where the bolt will barely close on a "go" gauge. This will usually result in better accuracy from factory loads and will be easier to handload, although it can cause some ammo to chamber hard. However, I took a slightly different approach on this rifle. Because this is a dangerous game rifle, reliability is more important than accuracy. I need to know that when I close the bolt, the gun will chamber the ammo and will fire, every single time. My life can depend on this rifle working and I think that's more important than shaving another quarter-minute off the group size. (On the other hand, I will set the headspacing on the .358 Winchester I am building next to a tighter tolerance. I will be shooting primarily handloads and whitetails are not hard to stop when they charge. Just take their Visa Card away.) I wanted the chamber in my .458 Winchester Magnum to be large enough to accept any ammo and under any conditions, but still tight enough to ensure accuracy and reliability. Mark suggested that I adjust it so that the bolt will close about halfway on the "no-go" gauge which puts it closer to the upper end of the tolerance, so that's what I did.

I should have listened to him on cutting the chamber as well. After I had it exactly correct, I made a witness mark on the barrel and action so I could tighten them back to exactly the same location and removed the barrel. I checked the measurements again with the depth micrometer. The chamber that I had fitted perfectly with the "turn and try" method measured exactly what Mark had told me it would. If I had trusted myself enough to cut the chamber fully before installing the barrel, I could have saved a lot of work. On the other hand, there is no room for error and my way was a little safer for a first-timer.

The way I did it can save you money. Depth micrometers are a bit pricy and the "hybrid" method I used could work with a dial caliper. Simply cut the chamber to within .010 inch, then install the barrel and use the "turn and try" method until you have the headspace correct. Using a dial caliper to get close allows you to do a lot of the cutting with the barrel out of the action where it's easier and faster. It also saves you the price of a depth micrometer.

Be very certain that you have all the chips out of the chamber and that it is perfectly clean before you insert the "go" or "no-go" gauge. Anything at all in the chamber can affect the readings.

You will need a barrel vise and an action wrench to install the barrel to the action. My vise is the Wheeler Barrel Vise from Midway USA. The vise is shipped with three sets of oak blocks. Two of them will clamp on just about any size barrel, one has a one-inch hole and the other has a ¾-inch hole. The third set is uncut so you can custom fit them to your barrel if necessary. They should be clamped on the barrel close to the receiver where the barrel

REAMING THE CHAMBER



1. Using a depth micrometer to measure from the front of the action to the bolt face.



2. Measuring the length of the barrel shank.



3. Inserting the "go" gauge into the chamber to check for the headspacing.



4. Measuring from the back of the "go" gauge to the face of the barrel.



5. Reaming the chamber on a .458 Winchester barrel. Note the barrel in the action and the socket wrench extension with vise grips to turn it.



6. Reaming the chamber with a Clymer T-handle.



7. Inserting the "go" gauge into the chamber to check for the headspacing. Inset shows detail.

8. Cleaning the chips from the chamber with shop air before inserting the "go" gauge into the chamber to check for the headspacing.



9. A completed chamber for the .458 Winchester, which is a belted case.



Tightening a Mauser barrel in a Wheeler Barrel Vise. The wooden vise blocks are fitted with lead shims to prevent slippage.

Inset: Note cardboard on the action wrench to keep from marring the top of the action.

is large enough to accommodate the chamber. I soon found that no matter how tight I clamped the vise, the barrel would turn in the wooden blocks. I tightened the vise so much that I destroyed two sets of blocks, but still the barrel would slip and turn before I could get enough torque to seat the barrel correctly to the action.

So, I did some more research. Midway USA sells lead shims that help the grip which should work fine. But, on Bansner's advice I ordered some ground rosin from Brownells. This comes in a one-pound can that will probably be enough to last a lifetime. I sprinkled a little on the wooden blocks and the problem was solved. I suspect that this stuff might help with scopes slipping in the rings on hard recoiling rifles and handguns as well, and I plan to find out.

You will also need an action wrench to tighten the action against the barrel. Again, I turned to Midway USA for their Wheeler Engineering Action Wrench. These are specific to the rifle's action, so I ordered the Mauser style which fits most actions that are flat on the bottom. The other style is for round receivers like the Remington 700. One tip that Bansner passed on is to place some cardboard on the top of the action where the wrench contacts it to prevent marring.

How much to tighten the barrel is a little bit of a mystery. The Brownells tech department told me that there isn't any real number as far as the torque needed to install a barrel. They said that generally the barrel is tightened enough to account for about a .002-inch crush factor. A rule of thumb is to hand tighten the barrel and then turn it about 10 degrees more. Reid Coffield from Midway USA said that generally a large ring Mauser is tightened to 65 to 75 foot-pounds of torque. Which would be great information if I had a torque wrench that would fit on the action. But, of course, I do not and am not aware of any on the market. However, they both gave me useful information that helped to make an informed judgment. I have tightened enough threaded things over my lifetime to have an instinctive knowledge of how tight the barrel should be based on their information. I tightened the barrel and action until it was snug. Then I pulled up on the wrench until I was lifting my bench off the floor. I think that the wrench moved about 10 degrees and that I was probably applying about 75 foot-pounds of torque. I know that the barrel is tight in the action and is torqued to an amount that is compatible with this size and type of thread.

Is that too ambiguous? I suppose it is, but sometimes things are best done by the seat of your pants and this may well be one of those times. Simply put, tighten the barrel in the action until it's tight enough, but not too tight.

After installing the barrel, if you have not finished chambering the gun, do so. If you have the chambering complete, check with the "go" and "no-go" gauges to make sure headspacing is correct. Once the headspacing is correct, make a witness mark on the barrel and the action so they can be returned to the same location. You can do this with a center punch or a small chisel to make a mark on both the barrel and the action exactly opposite of each other. Don't use a felt marker as that will be sandblasted away or covered up when doing the finish on the gun. If you remove the barrel and reinstalling it, tighten until the two marks are lined up and the headspacing will be correct again.

Now is a good time to mark the cartridge designation

Wheeler Barrel Vise and action wrench from Midway USA being used to tighten a barrel in a Mauser action.



Stamping the numbers on the barrel, using Wheeler Engineering stamps and a B-Square guide sold by Brownells.



Illustrating mistakes made while stamping the gun.

Below: Shows markings on barrel after touching up the scratches with DuraCoat. Note that the scratches still show.

on the barrel. This is done with a set of stamp punches and a guide. I made the mistake of doing it after finishing and the guide clamp scratched the gun, so I had to touch up the DuraCoat. It's better to do it before sandblasting or coating the gun. That way any slight marks left by the guide will be blasted away and covered. My stamps are from Wheeler Engineering and sold by Midway USA. They are 1/16 inch and come in a complete kit. My guide is made by B-Square and sold by Brownells and is specific to the 1/16-inch-size stamps. Be sure to work out the spacing and layout before stamping the barrel. I used a piece of scrap cold rolled rod to check everything out and it took several tries before I got it exactly right. (Actually the truth be known, I tried to stamp the barrel without the guide. I used a piece of tape as a guide and hand held the stamps. The result was embarrassing. The good thing is I screwed it up in another way, too, and marked it too low on the barrel so the stock covered it up.) That's when I ordered the guide.

Once the spacing is worked out, clamp the guide on the barrel and stamp the barrel. It takes a little practice to know how hard to strike the stamps. For example, the "I" stamp makes a much deeper imprint with the same striking power than say the "8" or "W." Obviously, that's because there is less area to imprint. At least it's obvious now. I wish I had thought of that before marking the barrel. I hit them all with equal force with the hammer, but the "I" is deeper and more pronounced than the larger numbers. This is one more reason to practice before stamping your rifle, because like diamonds, the stamp marks are pretty much forever.

Now take the barrel back off the action for sandblasting. If you try to sandblast while the two are still assembled, some blasting media will work into the joint and thread, which will cause problems. So the barrel and action are disassembled for degreasing and sandblasting and then reassembled for coating.

METAL FINISH • Metal finishing is not as complicated as you might think. In days past, you would have had to have bluing tanks and all the toxic chemicals that entails. While bluing is still an excellent way to finish a rifle, the hobby gunsmith has some new options. Also, bluing will not work on stainless steel and so these new options are a better, perhaps only, choice with that metal if you want a finish other than the natural steel.

These days you can easily apply a finish that not only looks good, but will protect the metal from rust in a way that bluing cannot. Bluing is a form of rust and offers no protection. The protection must be applied in the form of a barrier to water, such as oil. However, the coating finishes are in effect a barrier themselves that insulate the metal from moisture and the air. This prevents rust and oxidization. Many coatings are easy to apply and the prep work is much easier than the polishing required for a good bluing job.

There is several coating-type metal finishes on the market, but most require oven drying. A rifle's barrel and action is too long to fit in the kitchen oven, so that means buying a very expensive shop oven or making one, which is also expensive and time consuming. At least one coating though, DuraCoat, can air dry. DuraCoat is available in a wide variety of colors, including seven "electric" neon colors and 55 stock colors. They also offer it in clear to cover a stainless steel gun when you want to retain the



To prepare it for sandblasting, this action has clay packed into the holes and ports. Tape is placed over other components to block the sandblasting in these places.

natural look or to cover bluing to prevent rust. In keeping with the all-black "pragmatic hunting gun" theme of my rifle, I chose flat black.

This stuff is tough enough that some military special forces use it on their guns. I talked with my buddy Randy Luth who owns DPMS, one of the premier makers of AR type rifles, and he says he has had outstanding luck with DuraCoat on his guns. It is so easy to apply that I got it pretty much right on the first try and I am not good with sticky substances or anything resembling painting. Believe me, if I can do this anybody can.

Because I could see that this was headed for a lot more "project" guns, I got the relatively inexpensive gravity feed spray gun that is powered by my shop air compressor. This is offered by Lauer Custom Weaponry, the company that makes DuraCoat. They have a complete line of products for coating firearms with several different options besides DuraCoat. They also have a complete line of tools and accessories. But if you are just building one or two rifles, for $49.99 you can buy the DuraCoat EZ Finishing kit that comes with an airbrush sprayer, propellant, hoses and all the materials.

All the metal must be degreased with a solvent that dries without residue. This can be done with aerosol spray cans of degreasing agent. But if you take this approach, be sure to degrease the gun before you assemble the barrel and action and then again just before coating. If you do not, oil in the threads can "weep" out of the joint between the action and the barrel and cause the DuraCoat not to stick. It's better in every circumstance and necessary if the barrel and action are together, to have a tank of solvent. I used TruStrip Solvent available from Lauer Custom Weaponry, and one of their solution tanks. This tank is long enough to put the entire barreled action in with room left over. I scrubbed the gun with a small brush and then let it soak for half an hour before removing it and letting it air dry. After that, I handled the gun only while wearing gloves. I use latex gloves and wash them to remove the powder. However, Midway has cotton inspection gloves that would be a better choice.

Tape is wrapped over the barrel threads to protect them during the sandblasting process.

A clay plug in the muzzle prevents sand from damaging the bore and rifling.

Sandblasting the Mauser action to prepare the surface to accept the DuraCoat finish.

The Mauser bolt after applying DuraCoat finish.

While DuraCoat can be applied over just about any clean surface, it's best to sandblast the metal parts to be coated so that the DuraCoat has plenty of area to adhere to. The rough surface from sandblasting actually increases surface area for the DuraCoat to grip and gives it "tooth." Tape off anything you don't want sandblasted with several layers of masking tape. Plug any holes with modeling clay. I fitted a tapered wooden dowel into the muzzle of the barrel to plug that and also to act as a support to suspend the barrel for spraying.

I used the gravity feed LCW Speedblaster sandblaster sold by LCW. Most shops use a blasting cabinet so that the blasting sand can be recovered. But for a one-time job, I considered $5.00 worth of sand a consumable item and did the blasting outside, catching what sand I could in a cutoff plastic 55-gallon barrel. Blast with 120 Grit Aluminum Oxide Media. The operating range of this sandblaster is 60 psi to 125 psi of air pressure. I ran it with about 100 psi and had good results. Keep the sandblaster moving all the time and watch the metal so that you have an even sheen to the finish. Be sure to wear thick leather gloves, long sleeves, a respirator, face shield and goggles. I know from painful experience that this stuff will sandblast the skin off your hands in a split second. The manufacturer recommends that you wear a rubber rain coat for protection from the flying sand. It would be easier to clean up as well, as the sand imbeds in your clothing.

After completing sandblasting so that all the metal has an even texture, remove all the tape and clay and reassemble the barrel and action. Don't forget to sandblast all the small parts that you are planning to coat. That includes the bottom metal, scope mounts, action screws and even the bolt. If you decide to coat the bolt, make sure to tape off the lugs as you do not want to sandblast or coat them. Small parts like the extractor retaining ring can be blasted and coated.

I coated the bolt on my gun, but I am not sure I would take this approach again. It's already showing wear marks in places, which is to be expected. I think that just the bare metal or perhaps a jeweled bolt would work better, at least on a Mauser type action where the extractor moves on the bolt and can mark up the coating. Also, I coated the polished raceways on the action, but the bolt tended to stick when running on straight DuraCoat. So, I used the raceway polishing tool to polish the raceways out again. The DuraCoat filled some of the valleys and now I think the action is even slicker than before. But, in the future I will tape the raceways off to prevent coating them.

THE STOCK • It's probably a good idea at this point to fit the stock rather than risk marring the metal finish later. I used a Bell & Carlson Carbelite Classic stock in basic black, which I ordered from Midway USA. Because there are so many variations on the Mauser and because mine was a relatively heavy barrel contour, fitting the stock took the most time of anything in this project. I had to open the barrel channel up considerably. With a lot of synthetic stocks that would not have been possible as it would have resulted in structural weakness. However, I called Junior Dunn at Bell & Carlson and he told me that as long as I kept the aluminum skeleton intact and well supported in the stock, I would be fine. To open the barrel channel I used a Barrel Bedding Tool from Brownells. This is a series of round cutters mounted on a contoured rod with a handle at each end. The cutters maintain the round contours of the barrel channel while cutting with each stroke. They will not dig in or gouge, but take a nice even cut each time. These are available in several different diameters to match the barrel you are bedding. It's a "must have" for stock work and I have



Brownells' Barrel Bedding Tool is used to scrape away material and open the barrel channel in a rifle stock.

RELEASE AGENT
RELEASE AGENT

Painting Brownells' release agent on a rifle action in preparation for glass bedding the action into a rifle stock.

several in my shop.

It took a lot of cutting and trying to finally make the barrel and action fit in the stock. I could have ordered the Varmint/Tactical-style stock from Bell & Carlson, which has a larger barrel channel, but I like the classic styling of the Carbelite Classic on a big game hunting rifle.

The Charles Daly has the safety on the trigger rather than on the bolt like a lot of Mausers. The safety lever sticks off to the side and it took a lot more cutting and fitting of the stock to clear the safety. I had to remove some metal from the internal aluminum block for the safety to clear. I used a Dremel hand grinder with a cutting tool to do that, working slowly and carefully to make sure I got an exact fit with just a minimum amount of clearance. I didn't want to remove any more metal than necessary on a hard recoiling rifle like this one. I also had to modify and cut down the top of the stock to allow clearance for the safety.

Once I had everything fitted together, I bedded the action and barrel channel using Brownells Acraglas. I bedded the action and first three inches of the barrel fully, except around the recoil lug where only the rear, load-bearing surface has contact. The barrel is free floated other than the first three inches in front of the action. The exact procedure for bedding a rifle stock is covered in another chapter of this book. The only thing I would do different next time is to add some Brownells Atomized metal to the bedding compound for more strength in such a hard recoiling rifle. The tungsten will add weight and strength or the stainless steel for a little less weight.

APPLYING DURACOAT FINISH


1

1. Wooden dowel used to plug the muzzle on the barrel while applying DuraCoat finish. This dowel also supported the barrel.

2

2. DuraCoat is applied to the small parts individually.

3

3. DuraCoat is applied to the action screws.

4

4. DuraCoat is applied to the bottom metal and magazine box.



Adjusting the trigger on a .458 Winchester Mauser. Wrenches are from Brownells.

APPLYING THE METAL FINISH

• LCW says that for the best possible finish, the gun can be Parkerized before applying the DuraCoat. Parkerizing has been used for years on military guns and it provides a durable, no-shine finish to protect the metal which by itself is a very good option for serious hunting gun. The Parkerizing will absorb oil and protect the metal. I have a Remington 7600 pump action rifle in .35 Whelen that I had Parkerized back in the 1980s. It has been on a lot of whitetail hunts and still looks as good as it ever did.

Parkerizing is easy to apply and does not require a lot of polishing time like bluing. In fact, it works best over a blasted surface. What I have is Zinc Phosphate Parkerizing Solution from DuraCoat Products. To use it, simply mix according to instructions, which is four parts water to one part solution. This is put in a tank which is then heated to 170-185 degrees Fahrenheit. A heated bluing tank works perfectly and runs off propane. The heated solution is conditioned by immersing a pad of coarse steel wool in the solution for 30 minutes. Then simply put the prepared gun in the tank for five to fifteen minutes. This will produce a traditional gray Parkerized surface on the metal. Follow by immersion in LCW post Treatment Solution, which is water displacing oil, or by applying DuraCoat. A gallon of solution will last for many Parkerizing sessions and is an economical gun finish option as well as a base for DuraCoat.

LCW suggests that DuraCoat can be applied over the Parkerized surface for the very best adhesion. However, I elected to use another option they offer and skip Parkerizing and apply the DuraCoat directly over the sandblasted metal.

After again degreasing the barrel and action, I used the wooden dowel in the muzzle and another inserted in the action to suspend the gun above my newspaper-covered bench. After adjusting the spray gun for the proper flow (which took a bit of fooling with air pressure) I "spray painted" the barrel and outside of the action with microscopic coating of DuraCoat.

Then I did each of the other parts I wanted covered one at a time. When everything was coated and dried, I put the gun together.

Applying DuraCoat is covered more completely in another chapter in this book.

TRIGGER & FEEDING

• The trigger on the Charles Daly Mauser is adjustable, so I set it at 3.5 pounds, which is fine for a dangerous game rifle. I had some feeding problems, which are not fine on a dangerous game rifle. The first two cartridges out of the magazine would feed without problems, but the third cartridge would often twist with the bullet pointing off to the left. This would jam the nose of the bullet against the left edge of the barrel at the chamber. This is, of course, completely unacceptable in any rifle, but particularly so in a dangerous game gun. There were actually two problems at work here. The fact that it was always the last cartridge in the magazine indicated that there was probably a problem with the magazine follower. The other two cartridges are feeding off the top of another cartridge, but the third and last cartridge is feeding off the top of the follower. I tried several different followers before discovering that a plastic follower out of a new Model 70 Winchester





Shows the replacement follower from a Winchester Model 70 rifle installed in custom Mauser.

Mauser action controlled round feed.

Classic Stainless rifle would feed better. That helped the problem by about 50 percent, which told me I was on the right track. I then ordered a steel follower designed for a Model 70 belted magnum. The Winchester follower has a lip in the bottom rear that makes it much thicker. This prevented loading three cartridges in the magazine. I ground that off and thinned the front of the follower as well, which allowed the follower to go low enough to load three cartridges in the magazine and barely have enough room to compress them so the bolt can be closed without feeding the top cartridge.

The new follower helped even more, but the gun still would on occasion jam the last shot. This was particularly true with blunt nose ammo. The big, blunt Winchester 510-grain factory load has a lot of exposed lead in the tip and was the worst offender. But the Federal 500-grain Trophy Bonded Sledgehammer Solid with its flat nose didn't feed very well either. Pointed bullets like the Federal Trophy Bonded Bearclaw ammo worked fine.

I made up some dummy cartridges with no powder and inert primers. By watching the cartridge as it fed out of the magazine, I realized that it was not coming all the way up behind the extractor. The worst offender was the last cartridge in the magazine, as that's when the magazine spring has the least amount of power.

I took the extractor off the bolt. To do this, clamp the extractor retaining ring in a soft-jawed vise. This holds the bolt and compresses the ring. Then use a screwdriver to pry the front of the extractor up while tapping the back of the extractor with a plastic hammer. This will force the extractor forward where it will come free from the retaining ring.

My extractor had a burr along the bottom which I carefully stoned off. Then I polished the entire extractor using a Dremel tool with a felt polishing wheel and polishing compound. Before reinstalling the extractor, I flexed it backwards by holding both ends and pushing in the middle. This slightly bent the extractor and caused it to have a little less spring tension against the cartridge that was trying to feed up behind it.

I polished the front bevel or leading edge on the extractor so that it will slip over a chambered cartridge. This allows single loading or topping off a full magazine with a fourth cartridge in the barrel. Many Mausers will not allow loading this way, as the extractor will not slip past the cartridge rim and they must be fed from the magazine. However, this limits the capacity to what the magazine will hold. By polishing the front of the extractor and lightening the spring tension, my gun would easily single feed by placing a cartridge in the chamber and closing the bolt.

The extractor is reinstalled on the bolt by carefully lining it up with the retaining ring and tapping the front with a plastic hammer. It may be necessary to slightly lift up on the front of the extractor to allow it to slide over the front of the bolt.

The gun fed better, but the cartridges were still not feeding all the way into the bolt behind the extractor. In watching this action, I could see that the shape of the extractor was part of the problem, as the bottom protruded too far out and the cartridge had a hard time moving up past that point. So, I removed the extractor again and very carefully removed a little metal with a hand grinder. I only took off a few thousandths of an inch, then shaped and polished the leading edge again. I polished the entire lip of the extractor and I used the



Shows new and modified Winchester follower with Brownells' 10 percent stronger spring beside original follower and spring.

Dremel tool to polish the bolt face. After that, the gun fed almost perfectly. Just to be sure I ordered an extra power magazine spring from Brownells. This spring has 10 percent more power than the standard Mauser spring and provides more push to the cartridge as it slides up behind the extractor. I added the spring and it seems to do a better job. Now, the rifle is feeding perfectly.

SIGHTING OPTIONS • The Charles Daly Mauser action is already drilled and tapped for scope mounting. I mounted a Kahles 1.1–4X24, 30mm scope in Warne mounts using the procedures detailed elsewhere in the book. I selected this scope for the low end magnification, which is almost zero. For an experienced shooter, a scope is faster and more accurate than any iron sights, but on a dangerous game rifle too much magnification can be a problem. When you have a buffalo charging and he is close, a scope with too much magnification might result in not being able to identify what part of the buffalo you are shooting at. On the Kahles, 1.1X is virtually zero magnification. The upper end of 4X allows me to crank up the scope for range work or for the occasional longer shot. This scope is a 30mm tube, so it's bright in poor light and has lots of adjustment latitude.

Warne rings and bases are made like tanks; they are virtually indestructible and I think they might survive a direct missile strike. They are a little heavy, but weight is your friend with a big gun like this. Warne rings are quick release so I also have another Kahles 1.1-4 X24 scope, this one with a lighted reticle, mounted in rings and zeroed for the gun. This will serve as a backup in case of problems. Kahles scopes are tough, but "stuff happens" so a backup is a good idea. I have seen scopes smashed when the hunter fell down a mountain, or dropped the gun on some big rocks, and I have seen several that were run over by trucks. For a big expensive trip like an African safari, I try to leave as little as possible to chance. The lighted reticle may also be useful for low light hunting situations such as leopard hunting or perhaps the gloomy weather of Alaskan bear hunting.

A SIMPLER APPROACH

PREY MASTER

Custom .22-250 Remington built on a Charles Daly Mini-Mauser action. Built by Bryce and Nathan Towsley. Owned by Nathan Towsley. Leupold Compact 2-7 scope.

The most daunting part of building a rifle is fitting the barrel and cutting the chamber. If you are not comfortable with this big of a project to start, consider a simpler approach to a "custom" gun. Charles Daly also sells barreled actions. These are offered in stainless steel, polished blue or matte blue. They have the barrel already installed on them and the headspacing is set. All they really need is a stock and a scope. Or, if you like, you can refinish the metal with DuraCoat for better rust protection and a different color option.

Bell & Carlson offers synthetic stocks and Boyds has laminated wood stocks to fit all the models, including the Mini-Mauser.

Nathan and I both ordered barreled "Mini-Mauser" actions. His is in .22-250 and mine is in 7.62X39. We fitted a Bell & Carlson Carbelite synthetic stock to Nathan's gun and installed a Leupold Vari-X II 3-9 Ultralight scope. Mine is in a Boyds Ross Thumbhole laminated wood stock and is fitted with a Leupold 2.5-8 Vari-X III scope. They look and feel like two very different rifles, but the only practical difference is the stock.

These were simpler projects, as all we had to do was fit the stocks and glass bed them and then mount the scopes.

The rifles are small, lightweight, compact and accurate. We built them with coyote calling in mind, but my 7.62X39 is also a good rifle to loan to a recoil-shy kid during our annual youth deer hunt.

If your choice runs more to a full size rifle, Charles Daly offers all their actions barreled and ready to stock in most popular calibers from .22 Hornet to .458 Winchester.

The gun is a hefty 9 ¾ recoil-reducing pounds with the scope mounted. Add four cartridges and a sling and it's over ten pounds. Heavy enough to soak up some recoil, but still light enough to carry all day.

After a few shots to zero the scope, I began to shoot some groups to test ammo. My first three-shot group was my best and it measured .8 inch with Winchester 510-grain soft nose ammo. That was a lucky group and the rest of the groups with that ammo measured an average of 1.25 inches. Federal 500-grain Trophy Bonded and 400-grain Trophy Bonded shot just over one inch. The Federal Trophy Bonded Sledgehammer 500-grain solids went into 1.5 inches. Obviously, I was delighted with this accuracy. Mark Bansner had told me that most .458 Winchester rifles are excellent shooters and he was as usual—right.

But, this is not a gun made for shooting off the bench. So after testing the ammo and zeroing the scope, I switched to shooting from hunting positions. I am shooting it quite a bit to prepare for this safari. I practice primarily shooting off hand and fast, because that safari is for two of the most dangerous game animals on the planet: elephant and buffalo. I know it's going to be exciting and I expect that taking them with a gun I built myself will raise the needle on the satisfaction and thrill meter to new levels.

My son and I have been practicing a drill we call "charging firewood." We have some chunks of firewood that were cut from a tree that fell on our range during a storm. We stand them up randomly at about 40 yards. We start with the gun loaded with three cartridges in the magazine, the bolt closed on an empty chamber. Using a timer, at the buzzer we see how fast we can hit all three. I can get the first one in about two seconds and all three in five seconds. This is where all that polishing earns its keep, as the action is slick and smooth. It's great practice to learn fast and accurate shooting with this big gun. Recoil recovery is important and this teaches us how to roll with the recoil as we work the action and bring the gun back on target. On top of that, it's great fun! The big slugs really make the chips fly when they hit the firewood!

I built this rifle in a big cartridge because of the upcoming safari; but if you build one, it doesn't have to be such a cannon. The same techniques I used here will work with any rifle chambering. While you may not have an interest in hunting dangerous game on The Dark Continent, just imagine how it will feel to drop the hammer on a big whitetail with a custom rifle that you built in your home shop. The money you saved on the rifle will more than cover the taxidermy bill!

Custom .458 Winchester on a Charles Daly Mauser action. Built by Bryce and Nathan Towsley. Kahles 1.1-4 scope, Warne mounts.

TOOLS FOR THE PROJECT

This is a list of the tools that I acquired specifically for this project. I already had things like gunsmithing screwdrivers, an air compressor, workbench, vise, etc.

Most of these tools can be used for years; so, the actual costs are spread out over numerous projects.

Bolt Lapping Tool*	Brownells	$49.97
Receiver Way Polisher*	Brownells	$39.97
PTG Solid Pilot Chamber Finish Reamer	Midway USA	$106.99
Forster Headspace "Go" Gauge Belted Magnums (.535" Base)	Midway USA	$18.19
Forster Headspace "No-Go" Gauge Belted Magnums (.535" Base)	Midway USA	$18.19
Starrett Depth Micrometer*	Brownells	$207.87
Wheeler Engineering Action Wrench #1 Mauser Flat-Bottomed Receiver	Midway USA	$39.99
Wheeler Engineering Barrel Vise with three Wood Bushings	Midway USA	$46.49
B-Square Steel Stamp Guide*	Brownells	$35.95
Wheeler Engineering Steel Letter and Number Barrel Stamp Set 1/16"*	Midway USA	$42.99
LCW Speed Blaster, gravity feed media/sandblaster	LCW	$87.00

* Indicates optional tool.



NECESSARY PARTS

This is a list of the parts that I acquired specifically for this project.

Mauser Action	Charles Daly	$359.00
Adams & Bennett Barrel	Midway USA	$104.99
DuraCoat EZ Finishing Kit	LCW	$49.99
Bell & Carlson Carbelite Classic Stock	Midway USA	$152.99
RIFLE TOTAL		$666.97
Warne Rings & Bases	Brownells	$73.99
Kahles 1.1-4 scope	Midway USA	$849.00

Index

A
Accuracy enhancement
  bore cleaning, 81-91
  causes of accuracy problems, 97
  fixing injection molded stock problems, 122-123
  glass bedding a rifle stock, 101-111
  pillar bedding a rifle stock, 112-121
  re-crowning a rifle muzzle, 98-100
Acrabed, 116
Acraglas Gel, 13, 56-57, 106, 150
Action raceways, 141-142
Adjustable Pillar Bedding Sleeves, 115-116, 120
Air compressors, 20
Allen head screws, stripped, 44-46
Allen wrenches, 44
Aluminum oxide stones, 20
Aluminum rod alignment, 70
Aprons, 30-31
Arkansas stone, 19-20, 132, 142
Auto body filler, 123

B
B-Square, 16, 131
B-Square screwdriver set, 44
Bansner, Mark, 35, 115, 144, 146
Barnes, 83, 87, 97
Barrel Bedding Tool, 104, 149
Barrel breech bedding, 119-120
Barrel installation, 143-147
Barreled actions, 153
Barrell cutting, 76-79
Bedding
  glass, 101-111
  pillar, 112-121
Bedding tape, 105, 117
Bell & Carlson, 149, 153
Belt and disk sander, 21
Bench, 12-13
Bench blocks, 29
Bench pads, 27
Bench vises, 14
Birchwood Casey, 50
Blasting cabinets, 149
Blind magazine rifles
  pillar bedding, 120-121
Bluing, 147
Bolt lapping, 139-141
Bolt Lapping Tool, 139
Bolt raceways, 141-142
Bore cleaning, 81-91
Bore guides, 86
Bore polishing, 52-53
Bore Tech Patch Guide, 82, 86
Boyd's, 153
Brass Muzzle Crowning Lap, 98-99
Bronze brushes, 86-87
Brooks, Coni, 97
Brownells
  Adjustable Pillar Bedding Sleeves, 115-116
  Barrel Bedding Tool, 104, 149
  Bolt Lapping Tool, 139-140
  Brass Muzzle Crowning Lap, 98-99
  chamber flex hone, 52-53
  Damascening Tools, 130
  files, 17
  Muzzle Facing/Chamfering Tool, 78-79, 99
  Muzzle Radius Cutter, 78-79
  pillar bedding instructions, 115-121
  polishing tools, 26
  Pull & Drop Gauge, 37
  Receiver Way Polisher, 141-142
  rosin, 45, 71
  Scope Shim Kit, 74
  screwdrivers, 15-17
  stockmaker handscrews, 111
  stone files, 19
Buffing and polishing wheel, 129
Building a rifle, 138-155

C
Cabinets, 14
Carpenter, Russ, 3
Cartridge feeding, 151-153
CDI Torque Products, 69, 70
Ceramic stones, 19, 20
Chamber flex hone, 52-53
Chamber polishing, 52-53
Chamber reamers, 144-145
Chapman, 15, 16
Charles Daly Mauser action rifle, 137-155
Chisels, 27, 28
Cleaning patches, 86-87
Cleaning rifles, 81-91
Cleaning rods, 84-85
Clymer Rifle T-Handle, 144-145
Coating finishes, 147
Coffield, Reid, 146
Cold weather, rifle preparation, 92-95
Comb height, 40-42
Cordless drill, 22
CR-10 Bore Cleaning Solvent, 87
Cratex, 26, 130
Crown damage, 100
Crush factor, 144, 146
Custom rifles, 137-155
Cutting chambers, 143-144

D
Damascening tools, 130
Decker, 26-27
Degreaser, 95, 132
Degreasing parts, 128, 148
Dental picks, 27
Depth micrometers, 144-145
Dewey action cleaning tool, 91
DPMS, 148
Draw filing, 130
Dremel tools, 25-26
Drill bits, 22-23
Drill presses, 21-22
Drills, 22
Drive grip, 67
Dunn, Junior, 149
DuraCoat, 94, 132-135, 147-151
Dwyer, Sean, 48
Dykem Layout fluid, 71, 75

E
Electronic cleaners, 89

Engagement surfaces, smoothing, 64-65
Engine turning and damascening, 129
Excessive headspace, 143
Extractor polishing, 152
Extreme weather hunting, rifle preparation, 92-95
Eye and ear protection, 23-24

F
Face shields, 23-24
Factory triggers, 48-51
Federal Trophy Bonded cartridges, 152, 154
Feed ramp polishing, 142
Feeding, 151-153
File cards, 19
Files, 17-19
Follower modification, 152
Forester Products, 14
Foul Out III, 89
.458 Winchester Magnum, 137-155

G
Glass bedding, 101-111
Gloves, 31
"Go" and "no go" gauges, 143-145
Grinders, 25-26
Gun safety, 32-33
Gun vises, 26
Gunsmith shop. *See Work shop*

H
Hacksaws, 28
Hammers, 25
Hand grinders, 25-26
Handheld cordless drill, 22
Headspace, 143-145
Hoppe's Elite System, 88

I
Indexing vise, 131
India stone, 19, 20, 28
Injection molded stock problems, 122-123

J
J-B Non-Embedding Bore Cleaning Compound, 89-90
Jags, 86-87
Jewelling, 128-131

K
Kahles scope, 153-154
Kascenska, John R., 113, 118
Kroil, 90

L
Laminated wood rifle stocks
  bedding for, 103, 110
Lapping the bolt, 139-141
Latex gloves, 31
Lauer Custom Weaponry, 148
LCW, 149, 151
Level-Level-Level, 74
Lighting, 12
Loctite, 30, 68, 71
Luth, Randy, 148
Lyman, 15, 16, 58

M
Maintenance
  bore cleaning, 81-91
  preparing rifles for extreme weather hunting, 92-95
Marble, 58-59
Marlin tang sight, 58-59
Mauser action rifle, 137-155
Measuring tools, 28
Metal finishing, 147-149, 151
Michael's of Oregon, 54, 57
Micrometer adjustable torque screwdriver, 70
Micrometers, 144-145
Midway USA, 15-16, 144, 146-147
Miles & Gilbert, 38-39
Mini-Mauser actions, 153
Moisture sealing, 94
Muzzle facing/chamfering tool, 78-79, 99
Muzzle radius cutter, 78-79
Muzzles
  re-crowning, 98-100

N
Norton, 19-20, 28

O
Outers Foul Out III, 89

P
Pachmayr, 16
Parkerizing, 151
Parts cabinets, 13-14
Parts cleaning tank, 26
Paste wax, 95
Patch Hog, 84
Pegboard storage, 14
Pillar bedding, 112-121
Pipe wrap, 105
Polishing action raceways, 141-142
Polishing tools, 26
Polyurethane, 94
Pull & drop gauge, 37
Punches, 24-25

R
Re-crowning a rifle muzzle, 98-100
Reaming chambers, 144-145
Receiver way polisher, 141-142
Recoil lug bedding, 119-120
Recoil pad installation, 36-39
Refinishing shotgun stocks, 42-43
Remington 7600 Carbine pump, 66
Remington M-700 BDL SS DM, 112, 117, 119-121
Remington Model 760 .30-06 Springfield, 125
Reticle leveler, 72-73
Rifle makeover project, 126-135
Rifle muzzles, re-crowning, 98-100
Rifle stocks
  fixing injection molded stock problems, 122-123
  glass bedding, 101-111
  pillar bedding, 112-121
Ring lapping kits, 72
Rod guides, 85-86
Rosin, 45, 71
Ruger triggers
  repairing, 60-65

S
Safety. *See Gun safety*
Safety goggles, 23-24
Sandblasting, 147-149
Sanders, 21
Sanding jigs, 38-39
Sandpaper, 30
Savage Snail Trap Range System, 32-33
Scope base alignment, 68-69
Scope mounting, 66-75, 153
Scope shims, 74-75
Screw kits, 30

Screw pitch gauge, 28-29
Screwdrivers, 15-17
Shelving, 14
Shop materials, 30-31
Shop rags, 30
Shop tools. *See specific tool by name*
Shotgun stocks. *See Stocks*
Sighting, 153-154
Silicon carbide stones, 20
Sinclair International, 69, 70
Slide hammer, 107
Sling swivel stud installation, 54-57, 134-135
Slip stone, 28
Socket sets, 27
Solvents, 87-88, 148
Speedblaster sandblaster, 148-149
Spyderco, 19, 20
Stamp punches, 147
Stevenson, Eddie, 98
Stock modification, 40-43
Stockmaker handscrews, 111
Stocks
  cutting, 37
  fitting, 149-150
  fixing injection molded stock problems, 122-123
  glass bedding, 101-111
  modifying, 40-43
  painting, 128
  pillar bedding, 112-121
  stripping finish, 128
Stones, 19-20
Stop Collar System, 78-79
Storage areas, 13-14
Stripped allen head screws, 44-46
Stripping finish, 128
Stud installation, 54-57
Surform tools, 18
Swiv-O-Ling vise, 14
Synthetic stocks
  bedding for, 110
  pillar bedding, 121

T
Table saws, 23
Tang-mounted peep sight, 58-59
Tap & die sets, 29
Timney Triggers, 48-51
Tipton, 26, 88
Tipton Jag Kit, 87
Toolboxes, 14
Tools. *See specific tool by name*
Torque wrenches, 69, 70-71
Towsley, Bryce, 23, 32, 37, 71, 75, 93, 133, 138-139
Towsley, Nathan, 22, 27, 40-41, 49
Trash cans, 31
Trigger guard-floor plate bedding, 120
Triggers
  adjusting, 151-153
  design, 47-48
  factory, 48-51
  installing, 48-51
  repairing a Ruger trigger, 60-65
Triple Shock bullets, 83
Trophy Bonded cartridges, 152, 154
TruStrip Solvent, 148

V
Vinyl gloves, 31
Vises, 14, 144, 146
VLC X-Bullets, 83

W
Warne mounts, 153-154
Water stones, 20, 28
WD 40, 90
Weather issues
  preparing rifles for extreme weather hunting, 92-95
Wheeler Barrel Vise, 144, 146
Wheeler Engineering, 74, 146-147
Winchester Ranger Model 94 rifle, 126-135
Wood carving chisels, 27, 28
Wood rifle stocks
  bedding for, 103, 110
Work shop
  air compressor, 20
  aprons, 30-31
  belt and disk sander, 21
  bench, 12-13
  bench blocks, 29
  bench pads, 27
  dental picks, 27
  Dremel tool, 25-26
  drill bits, 22-23
  drill press, 21-22
  eye and ear protection, 23-24
  files, 17-19
  gloves, 31
  grinders, 25-26
  gun vise, 26
  hacksaw, 28
  hammers, 25
  hand grinder, 25-26
  handheld cordless drill, 22
  latex gloves, 31
  lighting, 12
  loctite, 30
  measuring tools, 28
  paper towels, 30
  parts cleaning tank, 26
  punches, 24-25
  rags, 30
  sandpaper, 30
  screw kits, 30
  screw pitch gauge, 28-29
  screwdrivers, 15-17
  shop materials, 30-31
  socket sets, 27
  space requirements, 11
  stones, 19-20
  storage, 13-14
  table saw, 23
  tap & die sets, 29
  trash cans, 31
  vinyl gloves, 31
  vise, 14
  wood carving chisels, 27, 28
  wrenches, 27
Wrenches, 27

Z
Zinc Phosphate Parkerizing Solution, 151

Stoeger Publishing

Great Outdoor Books Since 1924



For more than 80 years Stoeger Publishing has been dedicated to the production of the best outdoor titles available. In addition to our classic annuals, *Shooter's Bible* and *Gun Trader's Guide,* our catalog of books includes more than 50 titles on hunting, firearms, shooting, reloading, collecting, fishing, game and fish cookery and survival. Books from Stoeger will make a fine addition to any sportsman's library.


98th EDITION
Shooter's Bible
The World's Standard Firearms Reference Book Since 1924
OVER 7 MILLION COPIES SOLD

SHOOTER'S BIBLE

98th Edition

As the most widely-recognized publication on firearms and accessories, *Shooter's Bible* provides an invaluable reference for both hunters and collectors. The 98th Edition includes expanded selections and articles and the latest information on what's new from the world's foremost makers of guns and shooting accessories.


GUN TRADER'S GUIDE
29TH EDITION

GUN TRADER'S GUIDE

29th Edition

For more than 50 years, millions of gun buffs, collectors, dealers and curators have chosen *Gun Trader's Guide* as a primary reference tool for firearms identification and pricing. The book features updated specifications, dates of manufacture and current average market values for more than 6,000 handguns, rifles and shotguns, both domestic and foreign.


THE HANDLOADER'S MANUAL OF CARTRIDGE CONVERSIONS
JOHN J. DONNELLY & BRYCE TOWSLEY

THE HANDLOADER'S MANUAL OF CARTRIDGE CONVERSIONS

John J. Donnelley and Bryce M. Towsley

Stoeger's classic guide has been revised and updated with a new format and additional cartridge data. *The Handloader's Manual* provides the data and drawings needed to convert modern materials into more than 900 rifle and pistol cartridge cases.


High Power Rifle Accuracy
Before You Shoot
DOUGLAS E. ARNOLD

HIGH POWER RIFLE ACCURACY: BEFORE YOU SHOOT

By Douglas E. Arnold

Gives the reader an in-depth look at what you need to know to get the maximum performance out of your high-power rifle and loads. The author provides tips ranging from barrels and stocks to handloading, cleaning and sighting. It also contains ballistics and loading charts on more than a hundred cartridges.


HOME GUNSMITHING
SIGHT SYSTEMS
JAY LANGSTON AND MARK BANSNER

HOME GUNSMITHING: SIGHT SYSTEMS

Jay Langston and Mark Bansner

Includes expert tips on picking the best sight systems, getting the systems to perform when it counts and trouble shooting problems during a hunt. Viewers will be able to hit the trail or step up to the firing line with the confidence that their sights will perform no matter what conditions arise.

For a complete list of Stoeger books call: 1-877-GUN-BOOK or visit us on the web at www.stoegerpublishing.com

Brownells Has What You Need...



When You Need It...

Even When You "Needed It Yesterday!"

You've planned for every detail of your hunt, and you're leaving tomorrow. From the powder and bullets in your carefully prepared handloads to the time spent scouting and knocking on doors to secure permission to hunt that favorite "honey hole." Everything's finally in order and ready to go…or so you thought!

Same Day Shipping

With Brownells only a phone call away, discovering a missing or broken gun part or shooting accessory at the very last minute doesn't have to spell disaster. Our Same Day Shipping policy ensures your order goes out as stated– the same day you order it. And, if it ships by air, you can have it on your doorstep the very next day – in time for your hunt. No hassle, no long wait, just the superior service you can always expect from Brownells, the leading name in Firearms Accessories and Gunsmithing Tools.

Your Satisfaction Guaranteed. Period.

Our Satisfaction Guarantee is unheard of in any industry. It's simple. If you aren't 100% completely satisfied with any purchase of any product at any time, return it to us for a full refund or exchange. No questions asked. No special authorization required. We've been doing business this way for over 67 years, and aren't about to change now!

Gunsmiths On Call To Answer Your Questions

With over 32,000 products in our inventory, we understand it can be difficult to know exactly what you need or how to repair every firearm, but you can get an expert's opinion from our staff of experienced gunsmith technicians. They're on call 8 hours a day to make sure you get exactly what you need, when you need it, even when you needed it yesterday! Just call us at 1-800-741-0015 department 986, or visit on online at www.brownells.com.

Horizontal Format
Uniquely Brownells

BROWNELLS
SELECTION. SERVICE. SATISFACTION.
The Worlds Largest Supplier of Firearms Accessories and Gunsmithg Tools.™

1-800-741-0015 • www.brownells.com

The Texas Manual on Rainwater Harvesting

Texas Water Development Board

Third Edition

The Texas Manual on Rainwater Harvesting

Texas Water Development Board

in cooperation with
Chris Brown Consulting
Jan Gerston Consulting
Stephen Colley/Architecture

Dr. Hari J. Krishna, P.E., Contract Manager

Third Edition
2005
Austin, Texas

Acknowledgments

The authors would like to thank the following persons for their assistance with the production of this guide: Dr. Hari Krishna, Contract Manager, Texas Water Development Board, and President, American Rainwater Catchment Systems Association (ARCSA); Jen and Paul Radlet, Save the Rain; Richard Heinichen, Tank Town; John Kight, Kendall County Commissioner and Save the Rain board member; Katherine Crawford, Golden Eagle Landscapes; Carolyn Hall, Timbertanks; Dr. Howard Blatt, Feather & Fur Animal Hospital; Dan Wilcox, Advanced Micro Devices; Ron Kreykes, ARCSA board member; Dan Pomerening and Mary Dunford, Bexar County; Billy Kniffen, Menard County Cooperative Extension; Javier Hernandez, Edwards Aquifer Authority; Lara Stuart, CBC; Wendi Kimura, CBC. We also acknowledge the authors of the previous edition of this publication, *The Texas Guide to Rainwater Harvesting*, Gail Vittori and Wendy Price Todd, AIA.

Disclaimer

The use of brand names in this publication does not indicate an endorsement by the Texas Water Development Board, or the State of Texas, or any other entity.

Views expressed in this report are of the authors and do not necessarily reflect the views of the Texas Water Development Board, or any other entity.

Table of Contents

Chapter 1 Introduction.. 1

Chapter 2 Rainwater Harvesting System Components.. 5
  Basic Components 5
  The Catchment Surface.. 5
  Gutters and Downspouts 6
  Leaf Screens.. 7
  First-Flush Diverters 8
  Roof Washers.. 10
  Storage Tanks.. 10
  Pressure Tanks and Pumps... 16
  Treatment and Disinfection Equipment 17

Chapter 3 Water Quality and Treatment 21
  Considerations for the Rainwater Harvesting System Owner 21
  Water Quality Standards 22
  Factors Affecting Water Quality... 22
  Water Treatment 23

Chapter 4 Water Balance and System Sizing... 29
  How Much Water Can Be Captured? 29
  Rainfall Distribution 30
  Calculating Storage Capacity... 32
  The Water Balance Method Using Monthly Demand and Supply 32
  Estimating Demand... 33
    Estimating indoor water demand 33
    Indoor water conservation.. 35
    Estimating outdoor water demand 36

Chapter 5 Rainwater Harvesting Guidelines 41
  RWH Best Management Practices.. 41
    Water Conservation Implementation Task Force Guidelines............................. 41
    American Rainwater Catchment Systems Association....................................... 41
  Building Codes.. 41
  Cistern Design, Construction, and Capacity 42
  Backflow Prevention and Dual-Use Systems 42
  Required Rainwater Harvesting Systems... 43

Chapter 6 Cost Estimation 45
  Comparing to Other Sources of Water.. 51

Chapter 7 Financial and Other Incentives 53
Tax Exemptions 53
Municipal Incentives 54
Rainwater Harvesting at State Facilities 55
Performance Contracting 56

Appendix A References A1

Appendix B Rainfall Data A7

Appendix C Case Studies A11

Appendix D Tax Exemption Application Form A25

Chapter 1
Introduction

Rainwater harvesting is an ancient technique enjoying a revival in popularity due to the inherent quality of rainwater and interest in reducing consumption of treated water.

Rainwater is valued for its purity and softness. It has a nearly neutral pH, and is free from disinfection by-products, salts, minerals, and other natural and man-made contaminants. Plants thrive under irrigation with stored rainwater. Appliances last longer when free from the corrosive or scale effects of hard water. Users with potable systems prefer the superior taste and cleansing properties of rainwater.

Archeological evidence attests to the capture of rainwater as far back as 4,000 years ago, and the concept of rainwater harvesting in China may date back 6,000 years. Ruins of cisterns built as early as 2000 B.C. for storing runoff from hillsides for agricultural and domestic purposes are still standing in Israel (Gould and Nissen-Petersen, 1999).

Advantages and benefits of rainwater harvesting are numerous (Krishna, 2003).

- The water is free; the only cost is for collection and use.
- The end use of harvested water is located close to the source, eliminating the need for complex and costly distribution systems.
- Rainwater provides a water source when groundwater is unacceptable or unavailable, or it can augment limited groundwater supplies.
- The zero hardness of rainwater helps prevent scale on appliances, extending their use; rainwater eliminates the need for a water softener and the salts added during the softening process.
- Rainwater is sodium-free, important for persons on low-sodium diets.
- Rainwater is superior for landscape irrigation.
- Rainwater harvesting reduces flow to stormwater drains and also reduces non-point source pollution.
- Rainwater harvesting helps utilities reduce the summer demand peak and delay expansion of existing water treatment plants.
- Rainwater harvesting reduces consumers' utility bills.

Perhaps one of the most interesting aspects of rainwater harvesting is learning about the methods of capture, storage, and use of this natural resource at the place it occurs. This natural synergy excludes at least a portion of water use from the water distribution infrastructure: the centralized treatment facility, storage structures, pumps, mains, and laterals.

Rainwater harvesting also includes land-based systems with man-made landscape features to channel and concentrate rainwater in either storage basins or planted areas.

When assessing the health risks of drinking rainwater, consider the path taken by the raindrop through a watershed into a reservoir, through public drinking water treatment and distribution systems to the end user. Being the universal solvent, water absorbs contaminants and minerals on its travels to the reservoir. While in residence in the reservoir, the water can come in contact with all kinds of foreign materials: oil, animal wastes, chemical and pharmaceutical wastes, organic compounds, industrial outflows, and trash. It is the job of the water treatment plant to remove harmful contaminants and to kill pathogens. Unfortunately, when chlorine is used for disinfection, it also degrades into disinfection by-products, notably trihalomethanes, which may pose health risks. In contrast, the raindrop harvested on site will travel down a roof via a gutter to a storage tank. Before it can be used for drinking, it will be treated by a relatively simple process with equipment that occupies about 9 cubic feet of space.

Rainwater harvesting can reduce the volume of storm water, thereby lessening the impact on erosion and decreasing the load on storm sewers. Decreasing storm water volume also helps keep potential storm water pollutants, such as pesticides, fertilizers, and petroleum products, out of rivers and groundwater.

But along with the independence of rainwater harvesting systems comes the inherent responsibility of operation and maintenance. For all systems, this responsibility includes purging the first-flush system, regularly cleaning roof washers and tanks, maintaining pumps, and filtering water. For potable systems, responsibilities include all of the above, and the owner must replace cartridge filters and maintain disinfection equipment on schedule, arrange to have water tested, and monitor tank levels. Rainwater used for drinking should be tested, at a minimum, for pathogens.

Rainwater harvesting, in its essence, is the collection, conveyance, and storage of rainwater. The scope, method, technologies, system complexity, purpose, and end uses vary from rain barrels for garden irrigation in urban areas, to large-scale collection of rainwater for all domestic uses. Some examples are summarized below:

- For supplemental irrigation water, the Wells Branch Municipal Utility District in North Austin captures rainwater, along with air conditioning condensate, from a new 10,000-square-foot recreation center into a 37,000-gallon tank to serve as irrigation water for a 12-acre municipal park with soccer fields and offices.
- The Lady Bird Johnson Wildflower Research Center in Austin, Texas, harvests 300,000 gallons of rainwater annually from almost 19,000 square feet of roof collection area for irrigation of its native plant landscapes. A 6,000-gallon stone cistern and its arching stone aqueduct form the distinctive entry to the research center.
- The Advanced Micro Devices semiconductor fabrication plant in Austin, Texas, does not use utility-supplied water for irrigation, saving $1.5 million per year by relying on captured rainwater and collected groundwater.
- Reynolds Metals in Ingleside, Texas, uses stormwater captured in containment basins as process water in its metal-processing plant, greatly offsetting the volume of purchased water.
- The city of Columbia, Nuevo León, Mexico, is in the planning stages of developing rainwater as the basis for the city's water supply for new

growth areas, with large industrial developments being plumbed for storage and catchment.

- On small volcanic or coral islands, rainwater harvesting is often the only option for public water supply, as watersheds are too small to create a major river, and groundwater is either nonexistent or contaminated with salt water. Bermuda, the U.S. Virgin Islands, and other Caribbean islands require cisterns to be included with all new construction.

In Central Texas, more than 400 full-scale rainwater harvesting systems have been installed by professional companies, and more than 6,000 rain barrels have been installed through the City of Austin's incentive program in the past decade. Countless "do-it-yourselfers" have installed systems over the same time period.

An estimated 100,000 residential rainwater harvesting systems are in use in the United States and its territories (Lye, 2002). More are being installed by the urban home gardener seeking healthier plants, the weekend cabin owner, and the homeowner intent upon the "green" building practices – all seeking a sustainable, high-quality water source. Rainwater harvesting is also recognized as an important water-conserving measure, and is best implemented in conjunction with other efficiency measures in and outside of the home.

Harvested rainwater may also help some Texas communities close the gap between supply and demand projected by the Texas Water Development Board (TWDB), as the state's population nearly doubles between 2000 and 2050 (Texas Water Development Board, 2002).

In fact, rainwater harvesting is encouraged by Austin and San Antonio water utilities as a means of conserving water. The State of Texas also offers financial incentives for rainwater harvesting systems. Senate Bill 2 of the 77th Legislature exempts rainwater harvesting equipment from sales tax, and allows local governments to exempt rainwater harvesting systems from ad valorem (property) taxes.

Rainwater harvesting systems can be as simple as a rain barrel for garden irrigation at the end of a downspout, or as complex as a domestic potable system or a multiple end-use system at a large corporate campus.

Rainwater harvesting is practical only when the volume and frequency of rainfall and size of the catchment surface can generate sufficient water for the intended purpose.

From a financial perspective, the installation and maintenance costs of a rainwater harvesting system for potable water cannot compete with water supplied by a central utility, but is often cost-competitive with installation of a well in rural settings.

With a very large catchment surface, such as that of big commercial building, the volume of rainwater, when captured and stored, can cost-effectively serve several end uses, such as landscape irrigation and toilet flushing.

Some commercial and industrial buildings augment rainwater with condensate from air conditioning systems. During hot, humid months, warm, moisture-laden air passing over the cooling coils of a residential air conditioner can produce 10 or more gallons per day of water. Industrial facilities produce thousands of gallons per day of condensate. An advantage of condensate capture is that its maximum production occurs during the hottest month of the year, when irrigation need is greatest. Most systems pipe condensate into the rainwater cistern for storage.

The depletion of groundwater sources, the poor quality of some groundwater, high tap fees for isolated properties, the flexibility of rainwater harvesting systems, and modern methods of treatment provide excellent reasons to harvest rainwater for domestic use.

The scope of this manual is to serve as a primer in the basics of residential and small-scale commercial rainwater harvesting systems design. It is intended to serve as a first step in thinking about options for implementing rainwater harvesting systems, as well as advantages and constraints.

References

Gould J, Nissen-Petersen E. 1999. Rainwater catchment systems for domestic rain: design construction and implementation. London: Intermediate Technology Publications. 335 p.

Krishna H. 2003. An overview of rainwater harvesting systems and guidelines in the United States. Proceedings of the First American Rainwater Harvesting Conference; 2003 Aug 21-23; Austin (TX).

Lye D. 2002. Health risks associated with consumption of untreated water from household roof catchment systems. Journal of the American Water Resources Association 38(5):1301-1306.

Texas Water Development Board. 2002. Water for Texas – 2002. Austin (TX): Texas Water Development Board. 155 p.

Chapter 2
Rainwater Harvesting System Components

Rainwater harvesting is the capture, diversion, and storage of rainwater for a number of different purposes including landscape irrigation, drinking and domestic use, aquifer recharge, and stormwater abatement.

In a residential or small-scale application, rainwater harvesting can be as simple as channeling rain running off an unguttered roof to a planted landscape area via contoured landscape. To prevent erosion on sloped surfaces, a bermed concave holding area down slope can store water for direct use by turfgrass or plants (Waterfall, 1998). More complex systems include gutters, pipes, storage tanks or cisterns, filtering, pump(s), and water treatment for potable use.

This chapter focuses on residential or small-scale commercial systems, for both irrigation and potable use.

The local health department and city building code officer should be consulted concerning safe, sanitary operations and construction of these systems.



Figure 2-1. Typical rainwater harvesting installation

Basic Components

Regardless of the complexity of the system, the domestic rainwater harvesting system (Figure 2-1) comprises six basic components:

- Catchment surface: the collection surface from which rainfall runs off
- Gutters and downspouts: channel water from the roof to the tank
- Leaf screens, first-flush diverters, and roof washers: components which remove debris and dust from the captured rainwater before it goes to the tank
- One or more storage tanks, also called cisterns
- Delivery system: gravity-fed or pumped to the end use
- Treatment/purification: for potable systems, filters and other methods to make the water safe to drink

The Catchment Surface

The roof of a building or house is the obvious first choice for catchment. For additional capacity, an open-sided barn – called a rain barn or pole barn – can be built. Water tanks and other rainwater system equipment, such as pumps and filters, as well as vehicles, bicycles, and gardening tools, can be stored under the barn.

Water quality from different roof catchments is a function of the type of roof material, climatic conditions, and the surrounding environment (Vasudevan, 2002).

Metal

The quantity of rainwater that can be collected from a roof is in part a function of the roof texture: the smoother the better. A commonly used roofing material for rainwater harvesting is sold under the trade name Galvalume®, a 55 percent aluminum/45 percent zinc alloy-coated sheet steel. Galvalume® is also available with a baked enamel coating, or it can be painted with epoxy paint.

Some caution should be exercised regarding roof components. Roofs with copper flashings can cause discoloration of porcelain fixtures.

Clay/concrete tile

Clay and concrete tiles are both porous. Easily available materials are suitable for potable or nonpotable systems, but may contribute to as much as a 10-percent loss due to texture, inefficient flow, or evaporation. To reduce water loss, tiles can be painted or coated with a sealant. There is some chance of toxins leaching from the tile sealant or paint, but this roof surface is safer when painted with a special sealant or paint to prevent bacterial growth on porous materials.

Composite or asphalt shingle

Due to leaching of toxins, composite shingles are not appropriate for potable systems, but can be used to collect water for irrigation. Composite roofs have an approximated 10-percent loss due to inefficient flow or evaporation (Radlet and Radlet, 2004).

Others

Wood shingle, tar, and gravel. These roofing materials are rare, and the water harvested is usually suitable only for irrigation due to leaching of compounds.

Slate. Slate's smoothness makes it ideal for a catchment surface for potable use, assuming no toxic sealant is used; however, cost considerations may preclude its use.

Gutters and Downspouts

Gutters are installed to capture rainwater running off the eaves of a building. Some gutter installers can provide continuous or seamless gutters.

For potable water systems, lead cannot be used as gutter solder, as is sometimes the case in older metal gutters. The slightly acidic quality of rain could dissolve lead and thus contaminate the water supply.

The most common materials for gutters and downspouts are half-round PVC, vinyl, pipe, seamless aluminum, and galvanized steel.

Seamless aluminum gutters are usually installed by professionals, and, therefore, are more expensive than other options.

Regardless of material, other necessary components in addition to the horizontal gutters are the drop outlet, which routes water from the gutters downward and at least two 45-degree elbows which allow the downspout pipe to snug to the side of the house. Additional components include the hardware, brackets, and straps to fasten the gutters and downspout to the fascia and the wall.

Gutter Sizing and Installation

When using the roof of a house as a catchment surface, it is important to consider that many roofs consist of one or more roof "valleys." A roof valley occurs where two roof planes meet. This is most common and easy to visualize when considering a house plan with an "L" or "T" configuration. A roof valley concentrates rainfall runoff from two roof planes before the collected rain reaches a gutter. Depending on the size of roof areas terminating in a roof valley, the slope of the roofs, and the intensity of rainfall, the portion of gutter located where the valley water leaves the eave of the roof may not be able to capture all the water at that point, resulting in spillage or overrunning.

Besides the presence of one or more roof valleys, other factors that may result in overrunning of gutters include an inadequate number of downspouts, excessively long roof distances from ridge to eave, steep roof slopes, and inadequate gutter maintenance. Variables such as these make any gutter sizing rules of thumb difficult to apply. Consult you gutter supplier about your situation with special attention to determine where gutter overrunning areas may occur. At these points along an eave, apply strategies to minimize possible overrunning to improve catchment efficiency. Preventative strategies may include modifications to the size and configuration of gutters and addition of gutter boxes with downspouts and roof diverters near the eave edge.

Gutters should be installed with slope towards the downspout; also the outside face of the gutter should be lower than the inside face to encourage drainage away from the building wall.

Leaf Screens

To remove debris that gathers on the catchment surface, and ensure high quality water for either potable use or to work well without clogging irrigation emitters, a series of filters are necessary. Essentially, mesh screens remove debris both before and after the storage tank. The defense in keeping debris out of a rainwater harvesting system is some type of leaf screen along the gutter or in the downspout.

Depending upon the amount and type of tree litter and dust accumulation, the homeowner may have to experiment to find the method that works best. Leaf screens must be regularly cleaned to be effective. If not maintained, leaf screens can become clogged and prevent rainwater from flowing into a tank. Built-up debris can also harbor bacteria and the products of leaf decay.

Leaf guards are usually ¼-inch mesh screens in wire frames that fit along the length of the gutter. Leaf guards/screens are usually necessary only in locations with tree overhang. Guards with profiles conducive to allowing leaf litter to slide off are also available.

The **funnel-type downspout filter** is made of PVC or galvanized steel fitted with a stainless steel or brass screen. This type of filter offers the advantage of easy accessibility for cleaning. The funnel is cut into the downspout pipe at the same height or slightly higher than the highest water level in the storage tank.

Strainer baskets are spherical cage-like strainers that slip into the drop outlet of the downspout.

A cylinder of rolled screen inserted into the drop outlet serves as another method of filtering debris. The homeowner may need to experiment with various grid sizes, from insect screen to hardware cloth.

Filter socks of nylon mesh can be installed on the PVC pipe at the tank inflow.

First-Flush Diverters

A roof can be a natural collection surface for dust, leaves, blooms, twigs, insect bodies, animal feces, pesticides, and other airborne residues. The first-flush diverter routes the first flow of water from the catchment surface away from the storage tank. The flushed water can be routed to a planted area. While leaf screens remove the larger debris, such as leaves, twigs, and blooms that fall on the roof, the first-flush diverter gives the system a chance to rid itself of the smaller contaminants, such as dust, pollen, and bird and rodent feces.

The simplest first-flush diverter is a PVC standpipe (Figure 2-2). The standpipe fills with water first during a rainfall event; the balance of water is routed to the tank. The standpipe is drained continuously via a pinhole or by leaving the screw closure slightly loose. In any case, cleaning of the standpipe is accomplished by removing the PVC cover with a wrench and removing collected debris after each rainfall event.

There are several other types of first-flush diverters. The ball valve type consists of a floating ball that seals off the top of the diverter pipe (Figure 2-3) when the pipe files with water.

Opinions vary on the volume of rainwater to divert. The number of dry days, amount of debris, and roof surface are all variables to consider.

One rule of thumb for first-flush diversion is to divert a minimum of 10 gallons for every 1,000 square feet of collection surface. However, first-flush volumes vary with the amount of dust on the roof surface, which is a function of the number of dry days, the amount and type of debris, tree overhang, and season.

A preliminary study by Rain Water Harvesting and Waste Water Systems Pty Ltd., a rainwater harvesting component vendor in Australia, recommends that between 13 and 49 gallons be diverted per 1,000 square feet.

The primary reason for the wide variation in estimates is that there is no exact calculation to determine how much initial water needs to be diverted because there are many variables that would determine the effectiveness of washing the contaminants off the collection surface, just as there are many variables determining the make up of the contaminants themselves. For example, the slope and smoothness of the collection surface, the intensity of the rain event, the length of time between events (which adds to the amount of accumulated contaminants), and the nature of the contaminants themselves add to the difficulty of determining just how much rain should be diverted during first flush. In order to effectively wash a collection surface, a rain intensity of one-tenth of an inch of rain per hour is needed to wash a sloped roof. A flat or near-flat collection surface requires 0.18 inches of rain per hour for an effective washing of the surface.

The recommended diversion of first flush ranges from one to two gallons of first-flush diversion for each 100 square feet of collection area. If using a roof for a collection area that drains into gutters, calculate the amount of rainfall area that will be drained into every gutter feeding your system. Remember to calculate the horizontal equivalent of the “roof footprint” when calculating your catchment area. (Please refer to the Figure 4-1 in Chapter 4, Water Balance and System Sizing.) If a gutter receives the quantity of runoff that require multiple downspouts, first-flush

First-Flush Diverters


Inlet
First flush chamber
Outlet
Hose bibb drip
Clean-out plug

Figure 2-2. Standpipe first-flush diverter

Standpipe

The simplest first-flush diverter is a 6- or 8-inch PVC standpipe (Figure 2-2). The diverter fills with water first, backs up, and then allows water to flow into the main collection piping. These standpipes usually have a cleanout fitting at the bottom, and must be emptied and cleaned out after each rainfall event. The water from the standpipe may be routed to a planted area. A pinhole drilled at the bottom of the pipe or a hose bibb fixture left slightly open (shown) allows water to gradually leak out.

If you are using 3” diameter PVC or similar pipe, allow 33” length of pipe per gallon; 4” diameter pipe needs only 18” of length per gallon; and a little over 8” of 6” diameter pipe is needed to catch a gallon of water.

Standpipe with ball valve

The standpipe with ball valve is a variation of the standpipe filter. The cutaway drawing (Figure 2-3) shows the ball valve. As the chamber fills, the ball floats up and seals on the seat, trapping first-flush water and routing the balance of the water to the tank.


Inlet
Floating ball
Outlet
First flush chamber
Hose bibb drip
Clean-out plug

Figure 2-3. Standpipe with ball valve

diversion devices will be required for each downspout.

Roof Washers

The roof washer, placed just ahead of the storage tank, filters small debris for potable systems and also for systems using drip irrigation. Roof washers consist of a tank, usually between 30- and 50-gallon capacity, with leaf strainers and a filter (Figure 2-4). One commercially available roof washer has a 30-micron filter. (A micron, also called a micrometer, is one-millionth of a meter. A 30-micron filter has pores about one-third the diameter of a human hair.)

All roof washers must be cleaned. Without proper maintenance they not only become clogged and restrict the flow of rainwater, but may themselves become breeding grounds for pathogens.

The box roof washer (Figure 2-4) is a commercially available component consisting of a fiberglass box with one or two 30-micron canister filters (handling rainwater from 1,500- and 3,500-square-foot catchments, respectively). The box is placed atop a ladder-like stand beside the tank, from which the system owner accesses the box for cleaning via the ladder. In locations with limited drop, a filter with the canisters oriented horizontally is indicated, with the inlet and outlet of the filter being nearly parallel.



Figure 2-4. Box roof washer

Storage Tanks

The storage tank is the most expensive component of the rainwater harvesting system.

The size of storage tank or cistern is dictated by several variables: the rainwater supply (local precipitation), the demand, the projected length of dry spells without rain, the catchment surface area, aesthetics, personal preference, and budget.

A myriad of variations on storage tanks and cisterns have been used over the centuries and in different geographical regions: earthenware cisterns in pre-biblical times, large pottery containers in Africa, above-ground vinyl-lined swimming pools in Hawaii, concrete or brick cisterns in the central United States, and, common to old homesteads in Texas, galvanized steel tanks and attractive site-built stone-and-mortar cisterns.

For purposes of practicality, this manual will focus on the most common, easily installed, and readily available storage options in Texas, some still functional after a century of use.

Storage tank basics

- Storage tanks must be opaque, either upon purchase or painted later, to inhibit algae growth.

- For potable systems, storage tanks must never have been used to store toxic materials.
- Tanks must be covered and vents screened to discourage mosquito breeding.
- Tanks used for potable systems must be accessible for cleaning.

Storage tank siting

Tanks should be located as close to supply and demand points as possible to reduce the distance water is conveyed. Storage tanks should be protected from direct sunlight, if possible. To ease the load on the pump, tanks should be placed as high as practicable. Of course, the tank inlet must be lower than the lowest downspout from the catchment area. To compensate for friction losses in the trunk line, a difference of a couple of feet is preferable. When converting from well water, or if using a well backup, siting the tanks near the well house facilitates the use of existing plumbing.

Water runoff should not enter septic system drainfields, and any tank overflow and drainage should be routed so that it does not affect the foundation of the tanks or any other structures (Macomber, 2001).

Texas does not have specific rules concerning protection of rainwater systems from possible contamination sources; however, to ensure a safe water supply, underground tanks should be located at least 50 feet away from animal stables or above-ground application of treated wastewater. Also, runoff from tank overflow should not enter septic system drainfields. If supplemental hauled water might be needed, tank placement should also take into consideration accessibility by a water truck, preferably near a driveway or roadway.

Water weighs just over 8 pounds per gallon, so even a relatively small 1,500-gallon tank will weigh 12,400 pounds. A leaning tank may collapse; therefore, tanks should be placed on a stable, level pad. If the bed consists of a stable substrate, such as caliche, a load of sand or pea gravel covering the bed may be sufficient preparation. In some areas, sand or pea gravel over well-compacted soil may be sufficient for a small tank. Otherwise, a concrete pad should be constructed. When the condition of the soil is unknown, enlisting the services of a structural engineer may be in order to ensure the stability of the soil supporting the full cistern weight.

Another consideration is protecting the pad from being undermined by either normal erosion or from the tank overflow. The tank should be positioned such that runoff from other parts of the property or from the tank overflow will not undermine the pad. The pad or bed should be checked after intense rainfall events.

Fiberglass

Fiberglass tanks (Figure 2-5) are built in standard capacities from 50 gallons to 15,000 gallons and in both vertical



Figure 2-5. Two 10,000-gallon fiberglass tanks

cylinder and low-horizontal cylinder configurations.

Fiberglass tanks under 1,000 gallons are expensive for their capacity, so polypropylene might be preferred. Tanks for potable use should have a USDA-approved food-grade resin lining and the tank should be opaque to inhibit algae growth.

The durability of fiberglass tanks has been tested and proven, weathering the elements for years in Texas oil fields. They are easily repaired.

The fittings on fiberglass tanks are an integral part of the tank, eliminating the potential problem of leaking from an aftermarket fitting.

Polypropylene

Polypropylene tanks (Figure 2-6) are commonly sold at farm and ranch supply retailers for all manner of storage uses. Standard tanks must be installed above ground. For buried installation, specially reinforced tanks are necessary to withstand soil expansion and contraction. They are relatively inexpensive and durable, lightweight, and long lasting. Polypropylene tanks are available in capacities from 50 gallons to 10,000 gallons.



Figure 2-6. Low-profile 5,000-gallon polypropylene tanks

Polypropylene tanks do not retain paint well, so it is necessary to find off-the-shelf tanks manufactured with opaque plastic. The fittings of these tanks are aftermarket modifications. Although easy to plump, the bulkhead fittings might be subject to leakage.

Wood

For aesthetic appeal, a wood tank (Figure 2-7) is often a highly desirable choice for urban and suburban rainwater harvesters.

Wood tanks, similar to wood water towers at railroad depots, were historically made of redwood. Modern wood tanks are usually of pine, cedar, or cypress wrapped with steel tension cables, and lined with plastic. For potable use, a food-grade liner must be used.



Figure 2-7. Installation of a 25,000-gallon Timbertank in Central Texas showing the aesthetic appeal of these wooden tanks

These tanks are available in capacities from 700 to 37,000 gallons, and are site-built by skilled technicians. They can be dismantled and reassembled at a different location.

Metal

Galvanized sheet metal tanks (Figure 2-8) are also an attractive option for the urban or suburban garden. They are available in sizes from 150 to 2,500 gallons, and are lightweight and easy to relocate. Tanks can be lined for potable use. Most tanks are corrugated galvanized steel dipped in hot zinc for corrosion resistance. They are lined with a food-grade liner, usually polyethylene or PVC, or coated on the inside with epoxy paint. The paint, which also extends the life of the metal, must be FDA- and NSF-approved for potability.



Figure 2-8. Galvanized sheet metal tanks are usually fitted with a food-grade plastic liner.

Concrete

Concrete tanks are either poured in place or prefabricated (Figure 2-9). They can be constructed above ground or below ground. Poured-in-place tanks can be integrated into new construction under a patio, or a basement, and their placement is considered permanent.

A type of concrete tank familiar to residents of the Texas Hill Country is constructed of stacked rings with sealant around the joints. Other types of prefabricated concrete tanks include new septic tanks, conduit stood on end, and concrete blocks. These tanks are fabricated off-site and dropped into place.

Concrete may be prone to cracking and leaking, especially in underground tanks in clay soil. Leaks can be easily repaired although the tank may need to be drained to make the repair. Involving the expertise of a structural engineer to determine the size and spacing of reinforcing steel to match the structural loads of a poured-in-place concrete cistern is highly recommended. A product that repairs leaks in concrete tanks, Xypex™, is now also available and approved for potable use.



Figure 2-9. Concrete tank fabricated from stacking rings of concrete

One possible advantage of concrete tanks is a desirable taste imparted to the water by calcium in the concrete being dissolved by the slightly acidic rainwater. For potable systems, it is essential that the interior of the tank be plastered with a high-quality material approved for potable use.

Ferrocement

Ferrocement is a low-cost steel and mortar composite material. For purposes of this manual, Gunite™ and Shotcrete™ type will be classified as ferrocements. Both involve application of the concrete and mortar under pressure from a gun. Gunite, the dry-gun spray method in which the dry mortar is mixed with water at the nozzle, is familiar for its use in swimming pool construction. Shotcrete uses a similar application, but the mixture is a prepared slurry. Both methods are cost-effective for larger storage tanks. Tanks made of Gunite and Shotcrete consist of an armature made from a grid of steel reinforcing rods tied together with wire around which is placed a wire form with closely spaced layers of mesh, such as expanded metal lath. A concrete-sand-water mixture is applied over the form and allowed to cure. It is important to ensure that the ferrocement mix does not contain any toxic constituents. Some sources recommend painting above-ground tanks white to reflect the sun's rays, reduce evaporation, and keep the water cool.



Figure 2-10. Ferrocement tanks, such as this one, are built in place using a metal armature and a sprayed-on cement.

Ferrocement structures (Figure 2-10) have commonly been used for water storage construction in developing countries due to low cost and availability of materials. Small cracks and leaks can easily be repaired with a mixture of cement and water, which is applied where wet spots appear on the tank's exterior. Because walls can be as thin as 1 inch, a ferrocement tank uses less material than concrete tanks, and thus can be less expensive. As with poured-in-place concrete construction, assistance from a structural engineer is encouraged.

In-ground polypropylene

In-ground tanks are more costly to install for two reasons: the cost of excavation and the cost of a more heavily reinforced tank needed if the tank is to be buried more than 2-feet deep in well-drained soils. Burying a tank in clay is not recommended because of the expansion/contraction cycles of clay soil. For deeper installation, the walls of poly tanks must be manufactured thicker and sometimes an interior bracing structure must be added. Tanks are buried for aesthetic or space-saving reasons.

Table 2-1 provides some values to assist in planning an appropriate-sized pad and cistern to meet your water needs and your available space. Many owners of rainwater harvesting systems use multiple smaller tanks in sequence to meet their storage capacity needs. This has the advantage of allowing the owner to empty a tank in order to perform maintenance on one tank at a time without losing all water in storage.

A summary of cistern materials, their features, and some words of caution are provided in Table 2-2 to assist the prospective harvester in choosing the appropriate cistern type. Prior to making your final selection, consulting with an architect, engineer, or professional rainwater installer is recommended to ensure the right choice for your situation.

Table 2-1. Round Cistern Capacity (Gallons)

Height (feet)	6-foot Diameter	12-foot Diameter	18-foot Diameter
6	1,269	5,076	11,421
8	1,692	6,768	15,227
10	2,115	8,460	19,034
12	2,538	10,152	22,841
14	2,961	11,844	26,648
16	3,384	13,535	30,455
18	3,807	15,227	34,262
20	4,230	16,919	38,069

Rain barrel

One of the simplest rainwater installations, and a practical choice for urban dwellers, is the 50- to 75-gallon drum used as a rain barrel for irrigation of plant beds. Some commercially available rain barrels are manufactured with overflow ports linking the primary barrel to a second barrel. A screen trap at the water entry point discourages mosquito breeding. A food-grade plastic barrel used for bulk liquid storage in restaurants and grocery stores can be fitted with a bulkhead fitting and spigot for garden watering. Other options include a submersible pump or jet pump.

Table 2-2. Cistern Types

MATERIAL	FEATURES	CAUTION
Plastics		
Trash cans (20-50 gallon)	commercially available; inexpensive	use only new cans
Fiberglass	commercially available; alterable and moveable	must be sited on smooth, solid, level footing
Polyethylene/polypropylene	commercially available; alterable and moveable	UV-degradable, must be painted or tinted
Metals		
Steel drums (55-gallon)	commercially available; alterable and moveable	verify prior to use for toxics; prone to corrosion an rust;
Galvanized steel tanks	commercially available; alterable and moveable	possibly corrosion and rust; must be lined for potable use
Concrete and Masonry		
Ferrocement	durable and immoveable	potential to crack and fail
Stone, concrete block	durable and immoveable	difficult to maintain
Monolithic/Poured-in-place	durable and immoveable	potential to crack
Wood		
Redwood, fir, cypress	attractive, durable, can be disassembled and moved	expensive

Adapted from *Texas Guide to Rainwater Harvesting, Second Edition*, Texas Water Development Board, 1997.

Pressure Tanks and Pumps

The laws of physics and the topography of most homesteads usually demand a pump and pressure tank between water storage and treatment, and the house or end use. Standard municipal water pressure is 40 pounds per square inch (psi) to 60 psi. Many home appliances – clothes washers, dishwashers, hot-water-on-demand water heaters – require 20–30 psi for proper operation. Even some drip irrigation system need 20 psi for proper irrigation. Water gains 1 psi of pressure for every 2.31 feet of vertical rise. So for gravity flow through a 1-inch pipe at 40 psi, the storage tanks would have to be more than 90 feet above the house.

Since this elevation separation is rarely practical or even desirable, two ways to achieve proper household water pressure are (1) a pump, pressure tank, pressure switch, and check valve (familiar to well owners), or (2) an on-demand pump.

Pumps are designed to push water rather than to pull it. Therefore, the system should be designed with the pumps at the same level and as close to the storage tanks as possible.

Pump systems draw water from the storage tanks, pressurize it, and store it in a pressure tank until needed. The typical pump-and-pressure tank arrangement consists of a ¾- or 1-horsepower pump, usually a shallow well jet pump or a multistage centrifugal pump, the check valve, and pressure switch. A one-way check valve between the storage tank and the pump prevents pressurized water from being returned to the tank. The pressure switch regulates operation of the pressure tank. The pressure tank, with a typical capacity of 40 gallons, maintains pressure throughout the system. When the pressure tank reaches a preset threshold, the pressure switch cuts off power to the pump. When there is demand from the household, the pressure switch detects the drop in pressure in the tank and activates the pump, drawing more water into the pressure tank.



Figure 2-11. Cistern float filter

The cistern float filter (Figure 2-11) allows the pump to draw water from the storage tank from between 10 and 16 inches below the surface. Water at this level is cleaner and fresher than water closer to the bottom of the tank. The device has a 60-micron filter. An external suction pump, connected via a flexible hose, draws water through the filter.

On-demand pump

The new on-demand pumps eliminate the need for a pressure tank. These pumps combine a pump, motor, controller, check valve, and pressure tank function all in one unit. They are self-priming and are built with a check valve incorporated into the suction port. Figure 2-12 shows a typical installation of an on-demand pump and a 5-micron fiber filter, 3-micron activated charcoal filter, and an ultraviolet lamp. Unlike conventional pumps, on-demand pumps are designed to activate in response to a demand, eliminating the need, cost, and space of a pressure tank. In addition, some on-demand pumps are specifically designed to be used with rainwater.

Treatment and Disinfection Equipment

For a nonpotable system used for hose irrigation, if tree overhang is present, leaf screens on gutters and a roof washer diverting 10 gallons for every 1,000 square feet of roof is sufficient. If drip irrigation is planned, however, sediment filtration may be necessary to prevent clogging of emitters. As standards differ, the drip irrigation manufacturer or vendor should be contacted regarding filtering of water.

For potable water systems, treatment beyond the leaf screen and roof washer is necessary to remove sediment and disease-causing pathogens from stored water. Treatment generally consists of filtration and disinfection processes in series before distribution to ensure health and safety.

Cartridge Filters and Ultraviolet (UV) Light

The most popular disinfection array in Texas is two in-line sediment filters – the 5-micron fiber cartridge filter followed by the 3-micron activated charcoal cartridge filter – followed by ultraviolet light. This disinfection set-up is placed after the pressure tank or after the on-demand pump.

It is important to note that cartridge filters must be replaced regularly. Otherwise, the filters can actually harbor bacteria and their food supply. The 5-micron filter mechanically removes suspended particles and dust. The 3-micron filter mechanically traps microscopic particles while smaller organic molecules are absorbed by the activated surface. In theory, activated charcoal can absorb objectionable odors and tastes, and even some protozoa and cysts (Macomber, 2001).



Figure 2-12. Typical treatment installation of an on-demand pump, 5-micron fiber filter, 3-micron activated charcoal filter, and an ultraviolet lamp (top).

Filters can be arrayed in parallel for greater water flow. In other words, two 5-micron fiber filters can be stacked in one large cartridge followed by two 3-micron activated charcoal filters in another cartridge. The ultraviolet (UV) light must be rated to accommodate the increased flow.

NSF International (National Sanitation Foundation) is an independent testing and certification organization. Filter performance can be researched using a simple search feature by model or manufacturer on the NSF website. (See References.) It is best to purchase NSF-certified equipment.

Maintenance of the UV light involves cleaning of the quartz sleeve. Many UV lights are designed with an integral wiper unit. Manual cleaning of the sleeve is not recommended due to the possibility of breakage.

UV lamps are rated in gallons per minute. For single 5-micron and 3-micron in-line filters, a UV light rated at 12 gallons per minute is sufficient. For filters in parallel installation, a UV light rated for a higher flow is needed. In-line flow restrictors can match flow to the UV light rating.

UV lights must be replaced after a maximum of 10,000 hours of operation. Some lights come with alarms warning of diminished intensity.

Ozone

Chemically, ozone is O_3: essentially a more reactive form of molecular oxygen made up of three atoms of oxygen. Ozone acts as a powerful oxidizing agent to reduce color, to eliminate foul odors, and to reduce total organic carbon in water. For disinfection purposes, an ozone generator forces ozone into storage tanks through rings or a diffuser stone. Ozone is unstable and reacts quickly to revert to O_2 and dissipates through the atmosphere within 15 minutes.

A rainwater harvesting system owner in Fort Worth uses an ozone generator to keep the water in his 25,000 gallons of storage "fresh" by circulating ozone through the five tanks at night. A standard sprinkler controller switches the ozone feed from tank to tank.

Membrane Filtration (Reverse Osmosis and Nanofiltration)

Membrane filtration, such as reverse osmosis and nanofiltration work by forcing water under high pressure through a semipermeable membrane to filter dissolved solids and salts, both of which are in very low concentrations in rainwater. Membrane processes, however, have been known empirically to produce "sweeter" water, perhaps by filtering out dissolved metals from plumbing.

A certain amount of feed water is lost in any membrane filtration process. Reject water, referred to as "brine," containing a concentrate of the contaminants filtered from the feed water, is discharged. The amount of reject water, however, is directly proportional to the purity of the feed water. Rainwater, as a purer water source to begin with, would generate less brine. Reverse osmosis membranes must be changed before they are fouled by contaminants.

Reverse osmosis (RO) equipment for household use is commercially available from home improvement stores such as Lowe's and Home Depot.

Chlorination

For those choosing to disinfect with chlorine, automatic self-dosing systems are available. A chlorine pump injects chlorine into the water as it enters the house. In this system, appropriate contact time is critical to kill bacteria. A practical chlorine contact time is usually from 2 minutes to 5 minutes with a free chlorine residual of 2 parts per million (ppm). The time length is based on water pH, temperature, and amount of bacteria. Contact time increases with pH and decreases with temperature. K values (contact times) are shown in Table 3-3.

References

Macomber P. 2001. Guidelines on rainwater catchment systems for Hawaii. Manoa (HI): College of Tropical Agriculture and Human Resources, University of Hawaii at Manoa. 51 p.

NSF International, filter performance, www.nsf.org/certified/DWTU/

Radlet J, Radlet P. 2004. Rainwater harvesting design and installation workshop. Boerne (TX): Save the Rain.

Rain Water Harvesting and Waste Water Systems Pty Ltd., www.rainharvesting.com.au

Texas Water Development Board. 1997. Texas guide to rainwater harvesting. Austin (TX): Texas Water Development Board. 58 p.

Vasudevan L. 2002. A study of biological contaminants in rainwater collected from rooftops in Bryan and College Station, Texas [master thesis]. College Station (TX): Texas A&M University. 180 p.

Waterfall P. 1998. Harvesting rainwater for landscape use. Tucson (AZ): The University of Arizona College of Agriculture and Life Sciences. 39 p.

Chapter 3
Water Quality and Treatment

The raindrop as it falls from the cloud is soft, and is among the cleanest of water sources. Use of captured rainwater offers several advantages.

Rainwater is sodium-free, a benefit for persons on restricted sodium diets.

Irrigation with captured rainwater promotes healthy plant growth. Also, being soft water, rainwater extends the life of appliances as it does not form scale or mineral deposits.

The environment, the catchment surface, and the storage tanks affect the quality of harvested rainwater. With minimal treatment and adequate care of the system, however, rainfall can be used as potable water, as well as for irrigation.

The falling raindrop acquires slight acidity as it dissolves carbon dioxide and nitrogen. Contaminants captured by the rain from the catchment surface and storage tanks are of concern for those intending to use rainwater as their potable water source. The catchment area may have dust, dirt, fecal matter from birds and small animals, and plant debris such as leaves and twigs. Rainwater intended for domestic potable use must be treated using appropriate filtration and disinfection equipment, discussed in Chapter 2, Rainwater Harvesting System Components.

Total dissolved solids (TDS) in rainwater, originating from particulate matter suspended in the atmosphere, range from 2 milligrams per liter (mg/l or ppm)[1] to 20 mg/l across Texas, compared with municipal water TDS ranges of 100 ppm to more than 800 ppm.

The sodium content of some municipal water ranges from 10 parts per million (ppm) to as high as 250 ppm. Rainwater intended solely for outdoor irrigation may need no treatment at all except for a screen between the catchment surface and downspout to keep debris out of the tank, and, if the tank is to supply a drip irrigation system, a small-pore filter at the tank outlet to keep emitters from clogging.

Considerations for the Rainwater Harvesting System Owner

It is worth noting that owners of rainwater harvesting systems who supply all domestic needs essentially become owners of their "water supply systems," responsible for routine maintenance, including filter and lamp replacement, leak repair, monitoring of water quality, and system upgrades.

The rainwater harvesting system owner is responsible for both water supply and water quality. Maintenance of a rainwater harvesting system is an ongoing periodic duty, to include:

- monitoring tank levels,
- cleaning gutters and first-flush devices,
- repairing leaks,
- repairing and maintaining the system, and
- adopting efficient water use practices.

In addition, owners of potable systems must adopt a regimen of:

- changing out filters regularly,

---

[1] For dilute aqueous solutions mg/l is approximately equal to ppm because a liter of water weighs one kilogram.

- maintaining disinfection equipment, such as cleaning and replacing ultraviolet lamps, and
- regularly testing water quality.

Water Quality Standards

No federal or state standards exist currently for harvested rainwater quality, although state standards may be developed in 2006.

The latest list of drinking water requirements can be found on the United States Environmental Protection Agency's website. (See References.) The next section discusses the potential vectors by which contaminants get into rainwater. For those intending to harvest rainwater for potable use, the microbiological contaminants *E. coli*, *Cryptosporidium*, *Giardia lamblia*, total coliforms, legionella, fecal coliforms, and viruses, are probably of greatest concern, and rainwater should be tested to ensure that none of them are found (Lye, 2002). County health department and city building code staff should also be consulted concerning safe, sanitary operations and construction of rainwater harvesting systems.

Factors Affecting Water Quality

pH (acidity/alkalinity)

As a raindrop falls and comes in contact with the atmosphere, it dissolves naturally occurring carbon dioxide to form a weak acid. The resultant pH is about 5.7, whereas a pH of 7.0 is neutral. (A slight buffering using 1 tablespoon of baking soda to 100 gallons of water in the tank will neutralize the acid, if desired. Also, a concrete storage tank will impart a slight alkalinity to the water.) While Northeast Texas tends to experience an even lower pH (more acidic) rainwater than in other parts of the state, acid rain is not considered a serious concern in Texas.

Particulate matter

Particulate matter refers to smoke, dust, and soot suspended in the air. Fine particulates can be emitted by industrial and residential combustion, vehicle exhaust, agricultural controlled burns, and sandstorms. As rainwater falls through the atmosphere, it can incorporate these contaminants.

Particulate matter is generally not a concern for rainwater harvesting in Texas. However, if you wish, geographic data on particulate matter can be accessed at the Air Quality Monitoring web page of the Texas Commission on Environmental Quality (TCEQ). (See References.)

Chemical compounds

Information on chemical constituents can also be found on the TCEQ Air Quality website. (See References.)

In agricultural areas, rainwater could have a higher concentration of nitrates due to fertilizer residue in the atmosphere (Thomas and Grenne, 1993). Pesticide residues from crop dusting in agricultural areas may also be present.

Also, dust derived from calcium-rich soils in Central and West Texas can add 1 mg/l to 2 mg/l of hardness to the water. Hard water has a high mineral content, usually consisting of calcium and magnesium in the form of carbonates.

In industrial areas, rainwater samples can have slightly higher values of suspended solids concentration and turbidity due to the greater amount of particulate matter in the air (Thomas and Grenne, 1993).

Catchment surface

When rainwater comes in contact with a catchment surface, it can wash bacteria, molds, algae, fecal matter, other organic matter, and/or dust into storage tanks. The longer the span of continuous number of dry days (days without rainfall), the more catchment debris is washed off the roof by a rainfall event (Thomas and Grenne, 1993; Vasudevan, 2002).

Tanks

The more filtering of rainwater prior to the storage tanks, the less sedimentation and introduction of organic matter will occur within the tanks. Gutter screens, first-flush diverters, roof washers, and other types of pre-tank filters are discussed in Chapter 2. Sedimentation reduces the capacity of tanks, and the breakdown of plant and animal matter may affect the color and taste of water, in addition to providing nutrients for microorganisms.

Most storage tanks are equipped with manholes to allow access for cleaning. Sediment and sludge can be pumped out or siphoned out using hose with an inverted funnel at one end without draining the tank annually.

Multiple linked tanks allow one tank to be taken off line for cleaning by closing the valve on the linking pipe between tanks.

Water Treatment

The cleanliness of the roof in a rainwater harvesting system most directly affects the quality of the captured water. The cleaner the roof, the less strain is placed on the treatment equipment. It is advisable that overhanging branches be cut away both to avoid tree litter and to deny access to the roof by rodents and lizards.

For potable systems, a plain galvanized roof or a metal roof with epoxy or latex paint is recommended. Composite or asphalt shingles are not advisable, as toxic components can be leached out by rainwater. See Chapter 2 for more information on roofing material.

To improve water quality, several treatment methods are discussed. It is the responsibility of the individual installer or homeowner to weigh the advantages and disadvantages of each method for appropriateness for the individual situation. A synopsis of treatment techniques is shown in Table 3-1. A discussion of the equipment is included in Chapter 2.

Table 3-1. Treatment Techniques

METHOD	LOCATION	RESULT
Treatment		
Screening		
Leaf screens and strainers	gutters and downspouts	prevent leaves and other debris from entering tank
Settling		
Sedimentation	within tank	settles out particulate matter
Activated charcoal	before tap	removes chlorine*
Filtering		
Roof washer	before tank	eliminates suspended material
In-line/multi-cartridge	after pump	sieves sediment
Activated charcoal	after sediment filter	removes chlorine, improves taste
Slow sand	separate tank	traps particulate matter
Microbiological treatment /Disinfection		
Boiling/distilling	before use	kills microorganisms
Chemical treatments (Chlorine or Iodine)	within tank or at pump (liquid, tablet, or granular) before activated charcoal filter	kills microorganisms
Ultraviolet light	after activated charcoal filter, before tap	kills microorganisms
Ozonation	after activated charcoal filter, before tap	kills microorganisms
Nanofiltration	before use; polymer membrane (pores 10^{-3} to 10^{-6} inch)	removes molecules
Reverse osmosis	before use: polymer membrane (pores 10^{-9} inch)	removes ions (contaminants and microorganisms)
*Should be used if chlorine has been used as a disinfectant.		

Adapted from *Texas Guide to Rainwater Harvesting, Second Edition*, Texas Water Development Board, 1997.

Chlorination

Chlorination is mentioned here more for its historical value than for practical application. Chlorine has been used to disinfect public drinking water since 1908, and it is still used extensively by rainwater harvesters in Hawaii, the U.S. Virgin Islands, and in older rainwater harvesting systems in Kentucky and Ohio. Chlorine must be present in a concentration of 1 ppm to achieve disinfection. Liquid chlorine, in the form of laundry bleach, usually has 6 percent available sodium hypochlorite. For disinfection purposes, 2 fluid ounces (¼ cup) must be added per 1,000 gallons of rainwater. Household bleach products, however, are not labeled for use in water treatment by the Food and Drug Administration. A purer form of chlorine, which comes in solid form for swimming pool disinfection, is calcium hypochlorite, usually with 75 percent available chlorine. At that strength, 0.85 ounces by weight in 1,000 gallons of water would result in a level of 1 ppm. In either case, it is a good idea to carefully dilute the chlorine source in a bucket of water, and then stir with a clean paddle to hasten mixing (Macomber, 2001). Chlorine contact times are show in Table 3-2.

The use of chlorine for disinfection presents a few drawbacks. Chlorine combines with decaying organic matter in water to form trihalomethanes. This disinfection by-product has been found to cause cancer in laboratory rats. Also, some users may find the taste and smell of chlorine objectionable. To address this concern, an activated carbon filter may be used to help remove chlorine.

Chlorine does not kill *Giardia* or *Cryptosporidium*, which are cysts protected by their outer shells. Persons with weakened or compromised immune systems are particularly susceptible to these maladies. To filter out *Giardia* and *Cryptosporidium* cysts, an absolute 1-micron filter, certified by the NSF, is needed (Macomber, 2001).

Table 3-2. Contact Time with Chlorine

Water pH	Water temperature		
	50 F or warmer	45 F	40 F or colder
	Contact time in minutes		
6.0	3	4	5
6.5	4	5	6
7.0	8	10	12
7.5	12	15	18
8.0	16	20	24

UV Light

UV light has been used in Europe for disinfection of water since the early 1900s, and its use has now become common practice in U.S. utilities. Bacteria, virus, and cysts are killed by exposure to UV light. The water must go through sediment filtration before the ultraviolet light treatment because pathogens can be shadowed from the UV light by suspended particles in the water. In water with very high bacterial counts, some bacteria will be shielded by the bodies of other bacteria cells.

UV lights are benign: they disinfect without leaving behind any disinfection by-products. They use minimal power for operation. One should follow manufacturer's recommendations for replacement of bulbs.

Testing

Harvested rainwater should be tested before drinking and periodically thereafter. Harvested rainwater should be tested both before and after treatment to ensure treatment is working. It is advisable to test water quarterly at a minimum, if used for drinking.

Harvested rainwater can be tested by a commercial analytical laboratory, the county health departments of many Texas counties, or the Texas Department of Health.

Before capturing rainwater samples for testing, contact the testing entity first to become informed of requirements for container type and cleanliness, sample volume, number of samples needed, and time constraints for return of the sample.

For instance, for total coliform testing, water must usually be captured in a sterile container issued by the testing entity and returned within a maximum of 30 to 36 hours. Testing for pH, performed by commercial analytical laboratories must be done on site; other tests are less time-critical.

A list of county health departments that will test for total and fecal coliform can be found on the Texas Department of State Health Services (TDSHS) website. (See References.) The testing fee is usually between $15 and $25. Homeowners should contact the health department prior to sample collection to procure a collection kit and to learn the proper methods for a grab sample or a faucet sample.

Texas Department of State Health Services will test for fecal coliforms for a fee of $20 per sample. (See References.) A collection kit can be ordered from TDSHS at (512) 458-7598.

Commercial laboratories are listed in telephone Yellow Pages under Laboratories–Analytical & Testing. For a fee, the lab will test water for pathogens. For an additional fee, labs will test for other contaminants, such as metals and pesticides.

References

Lye D. 2002. Health risks associated with consumption of untreated water from household roof catchment systems. Journal of the American Water Resources Association 38(5):1301-1306.

Macomber P. 2001. Guidelines on rainwater catchment systems for Hawaii. Manoa (HI): College of Tropical Agriculture and Human Resources, University of Hawaii at Manoa. 51 p.

Texas Commission on Environmental Quality, Air Quality Monitoring, www.tceq.state.tx.us/nav/data/pm25.html

Texas Commission on Environmental Quality, chemical constituents, www.tnrcc.state.tx.us/airquality.html

Texas Department of State Health Services, county health departments, www.dshs.state.tx.us/regions/default.shtm

Texas Department of State Health Services, testing for fecal coliforms, www.dshs.state.tx.us/lab/default.shtm

Thomas PR, Grenne GR. 1993. Rainwater quality from different roof catchments. Water Science Technology (28):290-99.

United States Environmental Protection Agency, drinking water requirements, www.epa.gov/safewater/mcl.html

Vasudevan L. 2002. A study of biological contaminants in rainwater collected from rooftops in Bryan and College Station, Texas [masters thesis]. College Station (TX): Texas A&M University. 90 p.

This page intentionally left blank.

Chapter 4
Water Balance and System Sizing

The basic rule for sizing any rainwater harvesting system is that the volume of water that can be captured and stored (the supply) must equal or exceed the volume of water used (the demand).

The variables of rainfall and water demand determine the relationship between required catchment area and storage capacity. In some cases, it may be necessary to increase catchment surface area by addition of a rain barn or outbuilding to capture enough rainwater to meet demand. Cistern capacity must be sufficient to store enough water to see the system and its users through the longest expected interval without rain.

The following sections describe ways to determine the amount of rainfall, the estimated demand, and how much storage capacity is needed to provide an adequate water supply.

Intended End Use

The first decision in rainwater harvesting system design is the intended use of the water. If rainwater is to be used only for irrigation, a rough estimate of demand, supply, and storage capacity may be sufficient. On the other hand, if rainwater is intended to be the sole source of water for all indoor and outdoor domestic end uses, a more precise reckoning is necessary to ensure adequate supply.

How Much Water Can Be Captured?

In theory, approximately 0.62 gallons per square foot of collection surface per inch of rainfall can be collected. In practice, however, some rainwater is lost to first flush, evaporation, splash-out or overshoot from the gutters in hard rains, and possibly leaks. Rough collection surfaces are less efficient at conveying water, as water captured in pore spaces tends to be lost to evaporation.

Also impacting achievable efficiency is the inability of the system to capture all water during intense rainfall events. For instance, if the flow-through capacity of a filter-type roof washer is exceeded, spillage may occur. Additionally, after storage tanks are full, rainwater can be lost as overflow.



Figure 4-1. Catchment areas of three different roofs



Figure 4-2. Average annual precipitation in Texas, in inches

For planning purposes, therefore, these inherent inefficiencies of the system need to be factored into the water supply calculation. Most installers assume an efficiency of 75 percent to 90 percent.

In most Texas locations, rainfall occurs seasonally, requiring a storage capacity sufficient to store water collected during rainy times to last through the dry spells. In West Texas, total annual rainfall might not be sufficient to allow a residence with a moderate-sized collection surface to capture sufficient water for all domestic use. Some residences might be constrained by the area of the collection surfaces or the volume of storage capacity that can be installed.

Collection Surface

The collection surface is the “footprint” of the roof (Figure 4-1). In other words, regardless of the pitch of the roof, the effective collection surface is the area covered by collection surface (length times width of the roof from eave to eave and front to rear). Obviously if only one side of the structure is guttered, only the area drained by the gutters is used in the calculation.

Rainfall Distribution

In Texas, average annual rainfall decreases roughly 1 inch every 15 miles,



Figure 4-3. Maximum number of dry days (Krishna, 2003)

as you go from east to west (Figure 4-2), from 56 inches per year in Beaumont to less than 8 inches per year in El Paso. As one moves westward across the state, the prevalence and severity of droughts must also be considered.

To ensure a year-round water supply, the catchment area and storage capacity must be sized to meet water demand through the longest expected interval without rain. For instance, in West Texas, the historic longest span of continuous dry days has exceeded three months. For reference purposes, a contour map of historical maximum number of dry days in Texas is shown in Figure 4-3 (Krishna, 2003). If the rainwater harvesting system is intended to be the sole water source for a household, the designer must size the system to accommodate the longest anticipated time without rain, or otherwise plan for another water source, such as a well backup or hauled water.

Also, rainfall from high-intensity, short-duration rainfall events may be lost to overflow from storage tanks or splash-out from the gutters. Although these intense rainfall events are considered part of the cumulative annual rainfall, the total available volume of such an event is rarely captured.

Another consideration is that most rainfall occurs seasonally; annual rainfall is not evenly distributed throughout the 12 months of the year. The monthly distribution of rainfall is an important factor to consider for sizing a system. Monthly rainfall data for selected Texas cities is given in Appendix B.

Monthly Rainfall

Two different estimators of monthly rainfall are commonly used: average rainfall and median rainfall. Average annual rainfall is calculated by taking the sum of historical rainfall and dividing by the number of years of recorded data. This information is available from numerous public sources, including the National Climate Data Center website. (See References.) Median rainfall is the amount of rainfall that occurs in the midpoint of all historic rainfall totals for any given month. In other words, historically for the month in question, half of the time the rainfall was less than the median and half of the time rainfall was more than the median. Median values and average rainfall values for representative Texas cities are provided in Appendix B.

Median rainfall provides for a more conservative calculation of system sizing than average rainfall. The median value for rainfall is usually lower than the average value since large rainfall events tend to drive the average value higher. In other words, the sum of monthly medians is lower than the annual average due to the fact that the arithmetic average is skewed by high-intensity rainfall events. For planning purposes, median monthly rainfall can be used to estimate water availability to a reasonable degree of certainty (Krishna, 2001).

For example, in the sample calculations at the end of this chapter, the average annual rainfall for Dallas is about 35.0 inches, but the sum of the monthly medians is only 29.3 inches.

Calculating Storage Capacity

Once the median or average potential for rainfall capture is known from rainfall data and catchment area, it will be necessary to calculate storage capacity. The decision of whether rainwater will be used for irrigation, potable and domestic use, or both, will dictate water demand, and therefore, capacity.

A simple method of roughly estimating storage capacity popular among professional installers is to size the storage capacity to meet quarterly demand. The system is sized to meet estimated demand for a three-month period without rain. Annual estimated demand is divided by four to yield necessary storage capacity using this approach. This approach, however, may result in a more expensive system due to higher storage costs.

If a rainwater harvesting system is to be the sole water supply, overbuilding ensures a safety margin. As with many things in life, it helps to hope for the best but plan for the worst. Even when budget constraints may not allow the user to install as much storage capacity as a sizing method may indicate, it is important to provide for an area where additional tanks or cisterns can be installed at a later date when finances permit.

The Water Balance Method Using Monthly Demand and Supply

One method of determining the feasibility of a proposed system is the monthly water balance method. This method of calculation is similar to maintaining a monthly checkbook balance. Starting with an assumed volume of water already in the tanks, the volume captured each month is added to the previous balance and the demand is subtracted. The initial volume of water in the tanks would be provided by hauling or capturing water prior to withdrawing water from the system. An example is presented at the end of this chapter.

Data and calculations can be entered on an electronic spreadsheet to enable the user to compare different variables of catchment area and storage. It is suggested that homeowners experiment with different variables of storage capacity and, if applicable, catchment surface to find individual levels of comfort and affordability for catchment size and storage capacity.

As mentioned above:

- catchment area and rainfall determine supply, and
- demand dictates required storage capacity.

A commitment to conserving water with water-saving fixtures, appliances, practices indoors, and low-water-use landscaping outdoors is an essential component of any rainwater harvesting system design. Not only is conservation good stewardship of natural resources, it also reduces the costs for storage capacity and related system components.

If the amount of rainwater that can be captured – calculated from roof area and rainfall – is adequate or more than adequate to meet estimated demand, and meets the physical constraints of the building design, then storage capacity can be sized to meet estimated demand. If the monthly amount of water that can be captured, accounting for dry spells, is less than monthly estimated demand, then additional catchment area or supplemental supplies of water (such as groundwater from a well) will need to be considered.

In drier areas, no matter how large the storage capacity, catchment area may need to be increased with a rain barn or additional roof area to meet demand.

At the end of this chapter, an example of a water balance calculation is shown for the City of Dallas.

Estimating Demand

A water-conserving household will use between 25 and 50 gallons per person per day. (Note that total gallons per capita per day figures published for municipalities divide all the water distributed by the population, yielding a much larger amount per capita than actual domestic consumption.)

Households served previously by a water utility can read monthly demand from their meter or water bill to find monthly demand for purposes of building a new rainwater harvesting system. Divide the monthly total by the number of people in the house, and the days in the month to get a daily per capita demand number.

Water conservation is covered later in this chapter. Households solely dependent upon rainwater should adopt efficient water use practices both indoors and outdoors.

Estimating indoor water demand

Indoor water demand is largely unaffected by changes in weather, although changes in household occupancy rates depending upon seasons and ages of household members, more water use during the hot summer months, and very minor changes in consumption of water due to increases in temperature may be worth factoring in some instances. The results of a study of 1,200 single-family homes by the American Water Works Association (AWWA) in 1999 found that the average water conserving households used approximately 49.6 gallons per person per day (American Water Works Association, 1999).

Table 4-1 can be used to calculate indoor water demand. Many households use less than the average of 49.6 gallons per person found in the 1999 report by the AWWA, *Residential End Uses of Water*. The water volumes shown in the table assume a water-conserving household, with water-conserving fixtures and good practices, such as shutting off the water while brushing teeth or shaving. Overall demand in showers, baths, and faucet uses is a function of both time of use and rate of flow. Many people do not open the flow rate as high as it could be finding low or moderate flow rates more comfortable. In estimating demand, measuring flow rates and consumption in the household may be worth the effort to get more accurate estimates.

Table 4-1. Estimating Indoor Daily Domestic Demand

	A. **Water consumption using conserving fixtures**	**B.** **Assumptions from AWWA Residential End-Use Study**	**C.** **Adjustments to assumptions (adjust up or down according to actual use)**	**D.** **Number of persons in household**	**E.** **Household monthly demand** **A x (B or C)x D x 30**
Toilets (use only appropriate type)					
ULFT	1.6 gal/flush	6 flushes/ person/day			
Dual Flush	1 gal/flush liquids 1.6 gal/flush solids	6 flushes/ person/day			
Baths & showers					
Showerhead	2.2 gal/min	5 minutes/ person/day			
Bath	50 gal/bath	NA			
Faucets (personal hygiene, cooking, and cleaning of surfaces)	2.2 gal/faucet/min	5 minutes/ person/day			
Appliances or uses which are measured on a per-use basis (not a per-person basis):					
Clothes washer Front-loading (horizontal-axis)	18–25 gal/load	2.6 loads/week			
Dishwasher	8 gal/cycle	0.7 cycles/day			
Miscellaneous other					
Total					

One can use Table 4-1 if the designer prefers to incorporate known or expected behavioral habits into the water demand estimates. The values in the first column are to be multiplied by variables reflecting your own household water use patterns. The average values in the second column are offered for information, but as with all averages, are subject to wide variation based upon actual circumstances. An example is dual flush toilets – multiply three flushes per day liquid only (1 gpf), and add three flushes per day for solids (1.6 gpf), (3x1) + (3x1.6) = 7.8 gallons multiplied by 3 persons = 23.4 gpd household demand x 30 days = 702 gallons per month. The authors recommend verifying any assumptions against the records of historical use from a municipal water bill if available.

Indoor water conservation

Indoor domestic water conservation can be achieved by a combination of fixtures, appliances, and water-conserving practices. The advantage of water-conserving appliances is that they require no change in household routine. Some water-conserving practices need user action, such as turning off the water while brushing teeth or shaving; washing vegetables in a pan rather than under a stream; washing only full loads of laundry and dishes; and keeping a pitcher of water in the refrigerator, rather than waiting for cold water to arrive from a faucet.

Water conservation appliances include:

- **Ultralow flush toilets (ULFTs)**. Since 1993, only ULFTs with 1.6 gallons per flush may be sold in the United States. Older toilets should be replaced with the more efficient models. Some of the ULFTs require special early closing flappers to maintain their low-flow rates, so care should be taken in purchasing the correct replacement flapper for leaking toilets. If purchasing a new toilet, those that do not use early closure flappers are recommended. Dual-flush toilets (using less volume for liquid wastes) are also a good choice for a water-wise household.
- **Faucet aerators and efficient showerheads**. These fixtures are designed to use 2.2 gallons per minute at 60 psi, or 2.5 gpm at 80 psi (Table 4-1). Studies have shown that most people feel comfortable at less than full flow rates, so using the new fixtures (which are the only ones sold in the United States since 1992) should provide you with an efficient and comfortable experience.
- **Hot water on demand**. These wall-mounted units heat water just prior to use, eliminating the waste of waiting for hot water from the water heater while cold water is allowed to flow down the drain. Hot water loop systems keep hot water continuously circulating to achieve the same goal, but can use more energy. Another on-demand unit heats water quickly only when activated by a pushbutton, rather than circulating water through a loop, saving both water and energy. A rebate from San Antonio Water System (SAWS) is available for installation of this type of on-demand circulation system.
- **Horizontal-axis (front-loading) clothes washers.** Because clothes are tumbled through a small volume of water in the bottom of the drum (rather than washed in a full tub of water), this appliance can save up to half the water of a traditional clothes washer. It is also as much as 42 percent more energy efficient. A list of front-loading, horizontal-axis clothes washers is maintained by the Consortium for Energy Efficiency online. (See References.) Several municipal utilities in Texas, including City of Austin, SAWS, and Bexar Met, offer rebates for the purchase of these energy- and water-efficient appliances.

Estimating outdoor water demand

Outdoor water demand peaks in hot, dry summer. In fact, as much as 60 percent of municipal water demand in the summer is attributable to irrigation.

The water demands of a large turfgrass area almost always preclude the sole use of harvested rainwater for irrigation.

Many urban dwellers capture rainwater for irrigation of vegetable and ornamental gardens. Because it is free of salts and minerals, rainwater promotes healthy plant growth. In urban areas, rainwater harvesters may reduce their water bill by substituting harvested rainwater for municipal water for garden irrigation.

For both the health of landscape plants and water use-efficiency, the best way to water plants is according to their needs. For most plants adapted to Texas' climate, water stress is visually evident well before plant death. Signs of water stress include a gray blue tint to leaves, leaf rolling, and in the case of turfgrass, a footprint that does not spring back. Watering infrequently and deeply has been shown to promote plant health, waiting until plants need the water helps the water user to be sure that they are growing a healthy landscape.

For planning purposes, historical evapotranspiration can be used to project potential water demands. Evapotranspiration is the term for water use by plants, the combination of evaporation from the soil and transpiration from the plant leaves. An estimated value called potential evapotranspiration is available on the Texas Evapotranspiration website, or can be calculated from weather-related data. (See References.)

A recommended general reference for water-wise landscaping is *Xeriscape: Landscape Water Conservation*, publication B-1584, available online. (See References.) Other plant lists and resources are available at the Texas Master Gardeners' website. (See References.) Many municipal water utilities, including those in the cites of El Paso, Houston, Austin, San Antonio, and the Metroplex area have published water-wise landscaping information tailored to local climate and soil conditions

It is recommended that rainwater harvesting families install landscapes of native and adapted plants, and also ascribe to the seven principles of Xeriscaping. A water-wise landscape can be quite attractive, while conserving water and demanding less care than a garden of non-native or non-adapted plants.

Principles of Water-Wise Landscaping

1. Plan and design for water conservation.
2. Create practical turf areas.
3. Group plants of similar water needs together.
4. Use soil amendments like compost to allow the soil to retain more water.
5. Use mulches, especially in high and moderate watering zones, to lessen soil evaporation.
6. Irrigate efficiently by applying the right amount of water at the right time.
7. Maintain the landscape appropriately by fertilizing, mowing, and pruning.

References

American Water Works Association. 1999. Residential end uses of water. Denver (CO): American Water Works Association Research Foundation. 310 p.

Consortium for Energy Efficiency, list of clothes washers, www.cee1.org/resid/seha/rwsh/rwsh-main.php3

Krishna H. 2001. Rainwater catchment systems in Texas. Proceedings of the 10th International Conference on Rainwater Catchment Systems of the International Rainwater Catchments Systems Association; 2001 Sep 10-14; Mannheim, Germany.

Krishna H. 2003. An overview of rainwater harvesting systems and guidelines in the United States. Proceedings of the First American Rainwater Harvesting Conference; 2003 Aug 21-23; Austin (TX).

National Climate Data Center, www.ncdc.noaa.gov

Texas Evapotranspiration Network, texaset.tamu.edu

Texas Master Gardeners, aggiehorticulture.tamu.edu/mastergd/mg.html

Xeriscape: Landscape Water Conservation, publication B-1584, tcebookstore.org

Rainwater Harvesting System Sizing
Sample Water Balance Calculations for Dallas, Texas

Two methods of determining system sizing are shown below. In the first example, monthly average rainfall data are used, and in the second example, monthly median rainfall data are used for calculations. Monthly rainfall data for several locations in Texas are provided in Appendix B.

Keep in mind that the basic monthly water balance calculation is
Water available (gallons) = Initial volume in storage (gallons) + gallons captured – gallons used.
In an especially wet month, gallons in storage + gallons captured may exceed storage capacity; storage capacity could become a limiting factor, or a slightly larger cistern may be considered.

Assumptions

- Demand of 3,000 gallons/month
- Collection efficiency of 85 percent
- 0.62 gallons per square foot of roof area per inch of rain
- 10,000-gallon storage capacity
- 1,000 gallons in storage on January 1 to start out. (The water may have been collected between the time of system completion and new home occupancy, or it may be hauled water; systems designed for irrigation use only should be completed in the fall to collect rainwater during the slow-/non-growth season.)
- Irrigation volume is estimated based upon a small ornamental landscape, and limited supplemental irrigation, since this example is used for potable supply.

Calculations using Monthly Average Rainfall Data

First calculate the number of gallons collected in January. Using the average value of 1.91 inches of rain for January in Dallas (from Appendix B), the number of gallons of rainwater that can be expected to be stored in January from a 2,500-square-foot roof assuming 85% collection efficiency is determined from the equation:

Rainfall (inches) x roof area x 0.62 gal/sq ft /in. rain x collection efficiency

In this example:

$1.97_{\text{in. rainfall}} \times 2{,}500_{\text{sq. ft. catchment}} \times 0.62_{\text{gallons/in. rain/sq. ft.}} \times 0.85_{\text{collection efficiency}} = 2{,}595$ gallons

To calculate gallons in storage at the end of each month, add the volume of water already in storage (1,000 gallons in this example) to the gallons collected and subtract the monthly demand.

1,000 + 2,595 – 3,000 = 595 gallons available in storage at the end of January

This calculation is repeated for each month. To help you follow Table 4-2, please read below:

The value in Column E is added to Column F from preceding row and then A is subtracted. If calculated storage amount is zero or less, use zero for the next month. Rainfall exceeding storage capacity is ignored (water lost). The table shows that a collection surface of 2,500 square feet is adequate to meet expected demand (Column F should be more than zero at all times, if not the collection area needs to be increased or the monthly demand should be reduced).

Calculations using Monthly Median Rainfall Data

Table 4-3 shows the results of using monthly median rainfall (Column D), and performing the same calculations as before. Using monthly median rainfall data is a more conservative method, and is likely to provide a higher reliability than using average rainfall data for system sizing.

Homeowners can easily try different values for collection surface and storage capacity using an electronic spreadsheet, downloadable in Excel format from the Texas Water Development Board www.twdb.state.tx.us/assistance/conservation/alternative_technologies/rainwater_harvesting/rain.asp

Table 4-2. Sample Water Balance Calculations for Dallas, Texas (Using Average Rainfall and a 2,500-square-foot collection surface)

Month	A. Water demand	B. Irrigation demand (watering by hose or bucket)	C. Total demand (gallons)	D. Average rainfall (inches)	E. Rainfall collected (gallons)	F. End-of-month storage (1,000 gal. to start)
January	3,000	0	3,000	1.97	2,596	595
February	3,000	0	3,000	2.40	3,162	757
March	3,000	150	3,150	2.91	3,834	1,441
April	3,000	150	3,150	3.81	5,020	3,311
May	3,000	150	3,150	5.01	6,601	6,762
June	3,000	150	3,150	3.12	4,111	7,723
July	3,000	150	3,150	2.04	2,688	7,261
August	3,000	150	3,150	2.07	2,727	6,838
September	3,000	150	3,150	2.67	3,518	7,206
October	3,000	150	3,150	3.76	4,954	9,010
November	3,000	0	3,000	2.70	3,557	9,567
December	3,000	0	3,000	2.64	3,478	10,000*

* Note that there were 44 gallons of overflow in December in this example. A 10,000-gallon cistern appears to be appropriate under the given assumptions.

Table 4-3. Sample Water Balance Calculations for Dallas, Texas (Using Median Rainfall and a 2,500-square-foot collection surface)

Month	A. Water demand	B. Irrigation demand (watering by hose or bucket)	C. Total demand (gallons)	D. Median rainfall	E. Rainfall collected	F. End-of-month storage (1,000 gal. to start)
January	3,000	0	3,000	1.80	2,372	372
February	3,000	0	3,000	2.11	2,780	151
March	3,000	150	3,150	2.36	3,109	111
April	3,000	150	3,150	2.98	3,926	887
May	3,000	150	3,150	4.27	5,626	3,363
June	3,000	150	3,150	2.85	3,755	3,968
July	3,000	150	3,150	1.60	2,108	2,926
August	3,000	150	3,150	1.74	2,292	2,068
September	3,000	150	3,150	2.50	3,294	2,212
October	3,000	150	3,150	2.94	3,873	2,935
November	3,000	0	3,000	2.00	2,635	2,570
December	3,000	0	3,000	2.10	2,767	2,337

This table shows that it is critical to start with an initial storage (1,000 gallons), otherwise the cistern may run out of water in February/March, under the given assumptions.

The graph below (Figure 4-4) illustrates the information from Tables 4-2 and 4-3, previous page. The area under the curves represents the amount of water in storage at the end of each month. The assumptions from the example on the previous page are: a Dallas family of three using 33 gallons per person per day for indoor use, plus irrigation demand as shown in the examples, a collection efficiency of 85 percent, and a roof area of 2,500 square feet. The upper curve denotes water availability using average monthly rainfall data, and the lower curve is based on the monthly median rainfall. A 10,000-gallon cistern is planned in this example for storage of rainwater.



Figure 4-4. Volume of water in storage, using average rainfall data and median rainfall data for Dallas, Texas

Chapter 5
Rainwater Harvesting Guidelines

No national standards exist for rainwater harvesting systems. As a result, efforts abound to give assistance to those considering using rainwater as a water supply at state and local levels. In Texas the voluntary approach has been the hallmark of water conservation efforts, and a Water Conservation Best Management Practices (BMP) Guide produced by the Texas Water Development Board (TWDB) in 2004 included a section on Rainwater Harvesting and Condensate Reuse for use by water providers. (See References.) Guidance in other parts of the country ranges from voluntary guidelines such as BMPs to codes and ordinances stipulating minimum standards for various aspects of rainwater harvesting. The wide variety in approaches is summarized in this chapter by sharing a few key examples of the initiatives that are available to assist the planner of a rainwater harvesting system.

RWH Best Management Practices

Water Conservation Implementation Task Force Guidelines. In 2003 a statewide Water Conservation Implementation Task Force was appointed by the TWDB under a legislative mandate to develop recommendations for water conservation for the state of Texas. Best management practices reached by a consensus of the Task Force address rainwater harvesting and air conditioner condensate in the Task Force Water Conservation Best Management Practices Guide (TWDB, 2004).

American Rainwater Catchment Systems Association. The American Rainwater Catchment Systems Association (ARCSA) is in the process of publishing guidelines for potable and nonpotable rainwater harvesting systems. The guidelines will be available on the ARCSA website at www.arcsa-usa.org.

Other Voluntary Guidelines

A number of University-level programs have published guidelines that are helpful to rainwater designers and planners. Included among them are Texas Cooperative Extension's guidelines and the University of Arizona's "Harvesting Rainwater for Landscape Use," both of which focus on capturing rainwater for outdoor irrigation. The University of Hawaii College of Tropical Agriculture and Human Resources in Hawaii produced "Guidelines on Rainwater Catchment Systems in Hawaii," which has information for people using rainwater for potable consumption. (See References.)

These guidelines for potable systems recommend that storage tanks be constructed of non-toxic material such as steel, fiberglass, redwood, or concrete. Liners used in storage tanks should be smooth and of food-grade material approved by the U.S. Food and Drug Administration (Macomber, 2001).

Building Codes

In addition to voluntary effort, some states and municipalities are choosing to establish rules. Ohio, Kentucky, Hawaii, Arizona, New Mexico, Washington, West Virginia, Texas, and the U.S. Virgin Islands are considering or have developed rules related to rainwater harvesting.

Rules, ordinances, building codes, and homeowner association covenants nationwide run the gamut from requiring rainwater harvesting systems on new construction to prohibiting tanks as an eyesore.

In Texas, HB 645, passed by the 78th Legislature in 2003, prevents homeowners associations from implementing new covenants banning outdoor water-conserving measures such as composting, water-efficient landscapes, drip irrigation, and rainwater harvesting installations. The legislation allows homeowners associations to require screening or shielding to obscure view of the tanks.

The State of Ohio has the most extensive rules on rainwater harvesting in the United States, with code on cistern size and material, manhole openings, outlet drains, overflow pipes, fittings, couplings, and even roof washers. Ohio's rules also address disinfection of private water systems. (See References.)

Cistern Design, Construction, and Capacity

Cistern design is covered by rules in some states, often embedded in the rules for hauled water storage tanks. In Ohio, cisterns and stored water storage tanks must have a smooth interior surface, and concrete tanks must be constructed in accordance with ASTM C913, *Standard Specification for Precast Concrete Water and Wastewater Structures*. Plastic and fiberglass tank materials and all joints, connections, and sealant must meet NSF/ANSI Standard 61, *Drinking Water System Components*.

In the U.S. Virgin Islands, Bermuda, and other Caribbean islands (islands without large reservoirs or adequate groundwater reserves), all new construction and even building expansion must have a provision for a self-sustaining water supply system, either a well or a rainwater collection area and cistern.

The rules for private water systems in the U.S. Virgin Islands state that new cisterns must have a minimum capacity of 2,500 gallons per dwelling (Virgin Islands Code, Title 29, Public Planning and Development).

The U.S. Virgin Islands specifies that cisterns for hotels or multi-family dwellings have a minimum capacity of 10 gallons per square foot of roof area for buildings of one story, and 15 gallons per square foot of roof area for multi-story buildings, although the requirement is waived for buildings with access to centralized potable water systems.

The City of Portland, Oregon, requires a minimum cistern capacity of 1,500 gallons capable of being filled with harvested rainwater or municipal water, with a reduced pressure backflow prevention device and an air gap protecting the municipal supply from cross-connection (City of Portland, 2000).

Backflow Prevention and Dual-Use Systems

The option of "dual-supply" systems within a residence – potable harvested rainwater supplemented with water from a public water system with appropriate backflow prevention – is an option that might be explored for residences which cannot collect enough rainwater.

In most Texas locations, rainfall occurs seasonally, requiring a large storage capacity to hold enough water collected during rain events to last through the dry spells.

Allowing for a connection to the public water supply system could serve to promote harvested rainwater as a supplemental water source to customers already connected to the public water supply infrastructure.

This “conjunctive” use would require an appropriate backflow prevention device to keep rainwater from entering the public water supply due to a drop in pressure in the utility’s distribution system.

The City of Portland has approved supplemental use of public utility water at a residence since 1996. The code includes specific guidance for design and installation of the system. It also limits rainwater to nonpotable uses. The Portland Office of Planning and Development publishes a RWH Code Guide which includes FAQ and the relevant code sections (City of Portland, 2000).

The State of Washington Building Codes Council in 2002 developed guidelines for installation of rainwater harvesting systems at commercial facilities. They are similar to the City of Portland guidelines mentioned above, but require a larger cistern size, determined by the size of the catchment area, which is limited to roof areas. In 2003, the Washington State Legislature approved a 10 percent reduction in stormwater fees for any commercial facility that installed a rainwater harvesting system in compliance with the guidelines (Washington State Legislature, 2003).

Required Rainwater Harvesting Systems

Perhaps the most supportive ordinances are those requiring rainwater harvesting in new construction.

For instance, Santa Fe County, New Mexico, passed the precedent-setting regulation requiring rainwater harvesting systems on new residential or commercial structures of 2,500 square feet and larger. A bill requiring rainwater harvesting systems on all new construction narrowly missed passage in the New Mexico legislature (Darilek, 2004; Vitale, 2004)

The City of Tucson, Arizona, has instituted requirements for water harvesting in its land use code as a means of providing supplemental water for on-site irrigation. In fact, “storm water and runoff harvesting to supplement drip irrigation are required elements of the irrigation system for both new plantings and preserved vegetation” (City of Tucson Code, Chapter 23).

Water harvesting in Tucson is also intended to help in meeting code requirements for floodplain and erosion hazard management (City of Tucson Code, Chapter 26).

2005 Rainwater Harvesting Legislation

The Texas Legislature passed House Bill (HB) 2430 in May 2005, establishing a rainwater harvesting evaluation committee to recommend minimum water quality guidelines and standards for potable and nonpotable indoor uses of rainwater. The committee will also recommend treatment methods for indoor uses of rainwater, methods by which rainwater harvesting systems could be used in conjunction with existing municipal water systems, and ways in which that the state can further promote rainwater harvesting. The committee consists of representatives from the Texas Water Development Board, Texas Commission on

Environmental Quality, Department of State Health Services, and the Texas Section of the American Water Works Association. The committee will provide its recommendations to the Legislature by December 2006.

References

ASTM. 2004. ASTM C913-98 standard specification for precast concrete water and wastewater structures. In: ASTM Book of standards.

City of Portland. 2000. Code guide. Portland (OR): Office of Planning and Development. 18 p.

City of Tucson Code, Chapter 23, Land Use Code, Section 3.7.4.5B. 2004.

City of Tucson Code, Chapter 26, Floodplain and Erosion Hazard Management, Section 26-10, Detention/retention systems. 2004.

City of Tucson, Water Harvesting Guidance Manual, dot.ci.tucson.az.us/stormwater/education/waterharvest.htm

Darilek A. 2004 Mar 11. [Personal communication]. Office of the New Mexico State Engineer.

Macomber P. 2001. Guidelines on rainwater catchment systems for Hawaii. Manoa (HI): College of Tropical Agriculture and Human Resources, University of Hawaii at Manoa. 51 p.

NSF International, NSF/ANSI Standard 61, Drinking Water System Components, www.nsf.org/business/water_distribution/standards.asp?program=WaterDistributionSys

Ohio Department of Health Final Rules, 3701-28-09 Continuous Disinfection, www.odh.ohio.gov/Rules/Final/Chap28/Fr28_lst.htm

Texas Cooperative Extension. 2004. Rainwater Harvesting. Bryan (TX): Texas Cooperative Extension.

Texas Water Development Board, Water Conservation Best Management Practices Guide, p 96-101, www.twdb.state.tx.us/assistance/conservation/TaskForceDocs/WCITFBMPGuide.pdf

Vitale L. 2004 Mar 11. [Personal communication]. Sante Fe County.

Virgin Islands Code, Title 29, Public Planning and Development; Chapter 5, Building Code; Section 308, Water supply, cisterns, gutters, downspouts, wells. 2004.

Washington State Legislature. 2003 Mar 13. House Bill 2088.

Waterfall P. 1998. Harvesting rainwater for landscape use. Tucson (AZ): The University of Arizona College of Agriculture and Life Sciences. 39 p.

Welsh DF, Welch WC, Duble RL. 2001. Xeriscape…Landscape Water Conservation. Bryan (TX): Texas Cooperative Extension. 16 p.

Chapter 6

Cost Estimation

Developing a budget for a rainwater harvesting system may be as simple as adding up the prices for each of the components and deciding what one can afford. For households without access to reliable groundwater or surface water, and too remotely located to hook up to the existing potable supply infrastructure, the information in this chapter will assist in determining how large a system can be installed for a set budget, and the range of costs for an ideal system. For some, the opportunity to provide for all or a portion of their water needs with rainwater is an exercise in comparing the costs with other options to determine which is most cost-effective. This chapter provides some information on cost ranges for standard components of rainwater systems for both potable use and for irrigation. It also has a brief section on comparing costs with other types of water supply.

The single largest expense is the storage tank, and the cost of the tank is based upon the size and the material. Table 6-1 shows a range of potential tank materials and costs per gallon of storage. The size of storage needed (see Chapter 4, Water Balance and System Sizing) and the intended end use of the water will dictate which of the materials are most appropriate. Costs range from a low of about $0.50 per gallon for large fiberglass tanks to up to $4.00 per gallon for welded steel tanks.

As tank sizes increase, unit costs per gallon of storage decreases.

Table 6-1. Storage Tank

	Cost	Size	Comments
Fiberglass	$0.50–2.00/gallon	500–20,000 gallons	Can last for decades w/out deterioration; easily repaired; can be painted
Concrete	$0.30–1.25/gallon	Usually 10,000 gallons or more	Risks of cracks and leaks but these are easily repaired; immobile; smell and taste of water sometimes affected but the tank can be retrofitted with a plastic liner
Metal	$0.50–1.50/gallon	150–2,500 gallons	Lightweight and easily transported; rusting and leaching of zinc can pose a problem but this can be mitigated with a potable-approved liner
Polypropylene	$0.35–1.00/gallon	300–10,000 gallons	Durable and lightweight; black tanks result in warmer water if tank is exposed to sunlight; clear/translucent tanks foster algae growth
Wood	$2.00/gallon	700–50,000 gallons	Esthetically pleasing, sometimes preferable in public areas and residential neighborhoods
Polyethylene	$0.74–1.67/gallon	300–5,000 gallons	
Welded Steel	$0.80–$4.00/gallon	30,000–1 million gallons	
Rain Barrel	$100	55–100 gallons	Avoid barrels that contain toxic materials; add screens for mosquitoes

Gutters and downspouts (Table 6-2) are needed to collect the water and route it to the tank. Two types of gutters are available for the “do-it-yourselfers”: vinyl and plastic, which are available for approximately the same cost. For those desiring professionally installed materials, costs range from $3.50 to $12 per foot of gutter, including materials and installation, in 2004.

Table 6-2. Gutters

	Cost	Comments
Vinyl	$.30/foot	Easy to install and attach to PVC trunk lines
Plastic	$.30/foot	Leaking, warping and breaking are common problems
Aluminum	$3.50-6.25/foot	Must be professionally installed
Galvalume	$9-12/foot	Mixture of aluminum and galvanized steel; must be professionally installed

Some method of discarding the first flush of rain from the roof is necessary to remove debris. The simplest method is a vertical PVC standpipe, which fills with the first flush of water from the roof, then routes the balance of water to the tank.

The roof washer, placed just ahead of the storage tank, usually consists of a tank with leaf strainers and a filter. A commercially available model has a series of baffles and a 30-micron filter.

Table 6-3. Roof Washers

	Cost	Maintenance	Comments
Box Washer	$400-800	Clean the filter after every substantial rain	Neglecting to clean the filter will result in restricted or blocked water flow and may become a source or contamination
Post Filtering w/ Sand Filter	$150-500	Occasionally backwash the filter	Susceptible to freezing; a larger filter is best
Smart-Valve Rainwater Diverter Kit	$50 for kit	Occasional cleaning	Device installed in a diversion pipe to make it self-flushing and prevent debris contamination; resets automatically

Roof washers consist of a tank, usually between 30- and 50-gallon capacity, with leaf strainers and a filter. A roof washer is a critical component of potable systems and is also needed to filter small particles to avoid clogging drip irrigation emitters. A wide range of equipment is available with different flow capacity and maintenance requirements. In Table 6-3 a list of different equipment used to intercept and pre-filter the water shows a range of costs from $50 to more than $800. It is important that the rainwater harvester pick a roof washer that is adequate for the size of collection area.

Table 6-4 shows the ranges for pump costs including pressure tanks. Demand-activated pumps such as Grundfos may not require a pressure tank, and can often provide enough water to meet a home's demand for instantaneous flow. Careful thought should be given to the possibility of multiple simultaneous demands upon the system in determining the appropriate size pump. The range for pump costs runs from $385 for the low-end tankless pump, to more than $1,000 for the combined price of a high-end pump and pressure tank.

Table 6-4. Pumps and Pressure Tanks

	Cost	Comments
Grundfos MQ Water Supply System	$385-600	Does not require a separate pressure tank
Shallow Well Jet Pump or Multi-Stage Centrifugal Pump	$300-600	These require a separate pressure tank
Pressure Tank	$200-500	Galvanized tanks are cheaper than bladder tanks but often become waterlogged, and this will wear out the pump more rapidly

For those planning a potable system, or if a drip irrigation system is used, some sort of filtration is necessary. Rainwater harvesting suppliers can assist the end user in purchasing the right equipment for his/her needs and the expected demand.

It is important for the end user intending to use rainwater for potable supply to include disinfection among the water treatment components. The costs vary widely depending upon intended end-use, the desired water quality, and preferences of the user. As shown in Table 6-5, combined filtration/ disinfection costs can cost up to $1,000 or more. Chapter 2, Rainwater Harvesting System Components, will assist you in choosing the right filtration and/or disinfection equipment for your system.

Table 6-5. Filtering/Disinfection

	Cost	Maintenance	Effectiveness	Comments
Cartridge Filter	$20-60	Filter must be changed regularly	Removes particles >3 microns	A disinfection treatment is also recommended
Reverse Osmosis Filter	$400-1500	Change filter when clogged (depends on the turbidity)	Removes particles >0.001 microns	A disinfection treatment is also recommended
UV Light Disinfection	$350-1000; $80 to replace UV bulb	Change UV bulb every 10,000 hours or 14 months; the protective cover must be cleaned regularly	Disinfects filtered water provided there are <1,000 coliforms per 100 milliliter	Water must be filtered prior to exposure for maximum effectiveness
Ozone Disinfection	$700-2600	Effectiveness must be monitored with frequent testing or an in-line monitor ($1,200 or more)	Less effective in high turbidity, can be improved with pre-filtering	Requires a pump to circulate the ozone molecules
Chlorine Disinfection	$1/month manual dose or a $600-$3000 automatic self-dosing system	Monthly dose applied manually	High turbidity requires a higher concentration or prolonged exposure but this can be mitigated by pre-filtering	Excessive chlorination may be linked to negative health impacts.

Operating Costs

There are also operating costs that should be considered as you prepare your budget. As with any water treatment system, the cleaner the water needs to be, the greater the effort required to maintain the system.

Fortunately, with filter cartridges, this just means regular replacement of the cartridges, and with the disinfection system, following the manufacturers' recommendations for regular maintenance. But proper operation and maintenance of the system does add to total costs.

Filter cartridges should be replaced per manufacturer's specifications, based upon the rate of water use.

Some of the operating costs and time expenditures necessary for system maintenance are regularly cleaning gutters and roof washers, checking the system for leaks by monitoring water levels, and paying close attention to water use rates to determine if an invisible leak has sprung. Although the “do-it-yourselfers” can handle all of these tasks with little added financial burden, the time for regular maintenance and operation must be set aside to operate a successful system.

Comparing to Other Sources of Water

In some areas of Texas the cost of drilling a well can be as high as $20,000 with no guarantee of hitting a reliable source of water. The deeper the well, the more expensive the effort will be. Also, well water can have very high TDS levels in some aquifers, resulting in “hard” water. Rainwater is naturally soft and has become a preferred option in some parts of rural central Texas with costs lower than or equal to those of drilling a well, and reliability high enough to justify reliance on weather patterns, rather than on an aquifer’s water quality and quantity.

This page intentionally left blank.

Chapter 7
Financial and Other Incentives

Financial incentives and tax exemptions encourage the installation of rainwater harvesting systems. The Texas Legislature has passed bills, and some local taxing entities have adopted rules that provide tax exemptions for rainwater harvesting systems. A few public utilities have implemented rebate programs and rain barrel distribution events that encourage rainwater harvesting by residential, commercial, and industrial customers. In addition to financial incentives, performance contracting provisions in state code can be used to encourage installation of rainwater harvesting systems. This chapter includes a brief description of methods for determining the appropriate size of an incentive by local governments.

In addition to financial incentives, administrative contracting rules for state and local governments encourage the use of rainwater harvesting as an alternative water source in Texas.

Tax Exemptions

Property tax exemption for commercial installations (State-wide exemption)

A constitutional amendment passed as Proposition 2 by Texas voters in November 1993 exempted pollution control equipment, including water-conserving equipment at nonresidential buildings, from property taxes. Rainwater harvesting equipment at commercial installations is considered water-conserving equipment. The intent of this amendment to Article VIII of the Texas Constitution was to ensure that capital expenditures undertaken to comply with environmental rules and regulations did not raise a facility's property taxes, by adding Section 11.31 to Chapter 11, and Section 26.045 to Chapter 26 of the Texas Tax Code.

The Texas Commission on Environmental Quality (TCEQ) established procedures and mechanisms for use determination under Texas Administrative Code (TAC) Title 30, Chapter 17.

To qualify for the property tax exemption, (1) a facility must first receive a determination from the TCEQ that the property is used for pollution control purposes, and (2) the applicant then submits this use determination to the local tax appraisal district to obtain the property tax exemption.

The Application and Instructions for Use Determination for Pollution Control Property and Predetermined Equipment List, as well as instructions for applying for Property Tax Exemptions for Pollution Control Property, are downloadable from the TCEQ website. (See References.)

Property tax exemptions extended (State-wide)

Passed in 2001 by the 77th Texas Legislature, Senate Bill 2 amended Section 11.32 of the Texas Tax Code to allow taxing units of government the option to exempt from taxation all or part of the assessed value of the property on which water conservation modifications have been made. The taxing entity designates by ordinance or law the list of eligible water conservation initiatives, which may include rainwater harvesting systems.

County property tax exemptions

Homeowners planning to install rainwater harvesting systems should check with their respective county appraisal districts for guidance on exemption from county property taxes. Links to some county appraisal districts, as well as the Office of the State Comptroller's Application for Water Conservation Initiatives Property Tax Exemption, can be found online. (See References.)

Hays County is one of the fastest-growing counties in Texas, and is also the county with the most rapidly increasing number of new rainwater harvesting installations in the state. Hays County encourages rainwater harvesting with a $100 rebate on the development application fee.

For rainwater harvesting systems serving as the sole source of water for a residence, Hays County grants a property tax exemption from county taxes for the value of the rainwater harvesting system. Guidelines for rainwater harvesting benefits and qualification can be found at the Hays County website. (See References.)

Homeowners in other parts of the state should consider approaching their local government to see if such a property tax exemption could be passed in their locale.

Sales Tax Exemption (State-wide)

Senate Bill 2 exempts rainwater harvesting equipment and supplies from sales tax. Senate Bill 2 amended Subchapter H of the Tax Code by adding Section 151.355, which states:

> "Water-related exemptions. The following are exempted from taxes imposed by this chapter: (1) rainwater harvesting equipment or supplies, water recycling and reuse equipment or supplies, or other equipment."

An application for sales tax exemption is included as Appendix D, or can be downloaded from the Office of the State Comptroller. (See References.)

Municipal Incentives

In addition to tax exemptions, two Texas cities offer financial incentives in the form of rebates and discounts to their customers who install rainwater harvesting and condensate recovery systems.

City of Austin Rainwater Harvesting Programs

The City of Austin Water Conservation Department promotes both residential and commercial/industrial rainwater harvesting. (See References.) The City of Austin sells 75-gallon polyethylene rain barrels to its customers below cost, at $60 each, up to four rain barrels per customer. City of Austin customers who purchase their own rain barrels are eligible for a $30 rebate.

Customers may also receive a rebate of up to $500 on the cost of installing a pre-approved rainwater harvesting system. The rebate application includes a formula to calculate optimum tank size and a list of area suppliers and installation contractors. (See References.)

Commercial entities may be eligible for as much as a $40,000 rebate against the cost of installing new equipment and processes to save water under the Commercial Incentive Program. (See References.)

New commercial or industrial sites that develop capacity to store sufficient water on-site for landscape irrigation may be able to receive an exemption from installing an irrigation meter.

San Antonio Water System Large-Scale Retrofit

Rainwater harvesting projects are eligible for up to a 50-percent rebate under San Antonio Water System's (SAWS) Large-Scale Retrofit Rebate Program. (See References.) SAWS will rebate up to 50 percent of the installed cost of new water-saving equipment, including rainwater harvesting systems, to its commercial, industrial, and institutional customers. Rebates are calculated by multiplying acre-feet of water conserved by a set value of $200/acre-foot. Equipment and projects must remain in service for 10 years. The water savings project is sub-metered, and water use data before and after the retrofit are submitted to SAWS to determine if conservation goals are met. To qualify for the rebate, an engineering proposal and the results of a professional water audit showing expected savings are submitted.

The rebate shortens the return on investment period, giving an incentive to industry to undertake water-conserving projects.

Determining How Much of a Financial Incentive a Utility May Wish to Offer

To determine whether a municipal utility should consider offering a rebate or financial incentive to stimulate the use of rainwater harvesting, benefits and costs must be presented on an economic basis. This is most easily accomplished by condensing the factors into terms of dollars per acre-foot ($/AF) and comparing that to the cost of building a new water supply project. The spreadsheet included in the TWDB's Report No. 362, Water Conservation Best Management Practices Guide (p. 118 to 130), gives an example and the steps in calculating the net present value of conserved water.

This approach requires the utility to estimate the potential for water savings due to rainwater harvesting systems installed and the likely number of participants in a program.

Rainwater Harvesting at State Facilities

In 2003, the 78th Texas Legislature, second session, passed HB9, which encourages rainwater harvesting and water recycling at state facilities. The bill requires that the Texas Building and Procurement Commission appoint a task force charged with developing design recommendations to encourage rainwater harvesting and water recycling at state facilities built with appropriated money.

The intent of HB9 is to promote the conservation of energy and water at state buildings. The bill requires that before a state agency may use appropriated money to make a capital expenditure for a state building, the state agency must determine whether the expenditure could be financed with money generated by a utility cost-savings contract.

If it is determined to be not practicable to finance construction with utility cost savings, rainwater harvesting and water recycling are encouraged by HB9.

In addition the Texas Education Code (Section 61.0591) provides an incentive to institutes of higher education for achieving goals set by the Texas Higher Education Coordinating Board (THECB) including:

> “energy conservation and water conservation, rainwater harvesting, and water reuse.”

The code states that not less than 10 percent of THECB total base funding will be devoted to incentive funding.

Performance Contracting

Another means of encouraging the installation of water- or energy-efficient equipment is to pay for the equipment through the savings in utility bills. This method of financing water conservation has been used by commercial and industrial consumers, and is written into state code for government buildings in several locations.

The Texas Education Code (Chapter 44.901 and Chapter 51.927), the Texas Local Government Code (Chapter 302.004), and the State Government Code (Chapter 2166.406) allow public schools, institutes of higher education, state building facilities, and local governments to enter into performance contracts. Performance contracting allows a facility to finance water- and energy-saving retrofits with money saved by the reduced utility expenditures made possible by the retrofit. In other words, the water- and energy-conserving measures pay for themselves within the contracted period. More information on performance contracting can be found on the State Energy Conservation Office website. (See References.)

Following are descriptions of alternative water sources that are eligible for performance contracts:

> “landscaping measures that reduce watering demands and capture and hold applied water and rainfall, including: (a) landscape contouring, including the use of berms, swales, and terraces; and (b) the use of soil amendments that increase the water-holding capacity of the soil, including compost.”

> “rainwater harvesting equipment and equipment to make use of water collected as part of a stormwater system installed for water quality control.”

> “equipment needed to capture water from nonconventional, alternate sources, including air-conditioning condensate or graywater, for nonpotable uses, and metering equipment needed to segregate water use in order to identify water conservation opportunities or verify water savings.”

Performance contracts serve as a win-win opportunity for school districts and institutes of higher education to effect improvements on facilities for water- and energy-conservation without incurring net construction costs.

The State Energy Conservation Office, in Suggested Water Efficiency Guidelines for Buildings and Equipment at Texas State Facilities, recommends that use of alterative water sources be explored for landscape irrigation use. (See References.) Suggested water sources include captured stormwater or rainwater, air-conditioner condensate, water from basement sump pump discharge, and other sources, in accordance with local plumbing codes.

References

City of Austin Water Conservation Department, www.ci.austin.tx.us/watercon/

City of Austin Water Conservation Department, commercial process evaluations and rebates,

www.ci.austin.tx.us/watercon/commercial.htm

City of Austin Water Conservation Department, rainbarrel rebate, www.ci.austin.tx.us/watercon/rainwater.htm

Hays County, rainwater harvesting benefits and qualification, www.co.hays.tx.us/departments/envirohealth/forms.php

Office of the State Comptroller, application for sales tax exemption, www.window.state.tx.us/taxinfo/taxforms/01-3392.pdf

Office of the State Comptroller, application for water conservation initiatives property tax exemption, www.window.state.tx.us/taxinfo/taxforms/50-270.pdf

San Antonio Water System, large-scale retrofit rebate program, www.saws.org/conservation/commercial/retrofit.shtml

State Energy Conservation Office, www.seco.cpa.state.tx.us/sa_performcontract.htm

State Energy Conservation Office, Suggested Water Efficiency Guidelines for Buildings and Equipment at Texas State Facilities, www.seco.cpa.state.tx.us/waterconservation.pdf

Texas Commission on Environmental Quality, application and instructions for use determination for pollution control property and predetermined equipment list, www.tnrcc.state.tx.us/exec/chiefeng/prop2/guidance.pdf

Texas Commission on Environmental Quality, property tax exemptions for pollution control property, www.tnrcc.state.tx.us/exec/chiefeng/prop2/0611.doc

Texas county appraisal districts, www.texascad.com

Texas Statutes Tax Code, www.capitol.state.tx.us/statutes/tx.toc.htm

Texas Water Development Board, Water Conservation Best Management Practices Guide, p 96-101, www.twdb.state.tx.us/assistance/conservation/TaskForceDocs/WCITFBMPGuide.pdf

This page intentionally left blank.

Appendix A
References

ASTM. 2004. ASTM C913-98 standard specification for precast concrete water and wastewater structures. In: ASTM Book of standards.

American Rainwater Catchment Systems Association. 2003. First American rainwater harvesting conference proceedings. Austin (TX). 2003 Aug 21-22.

American Water Works Association. 1999. Residential end uses of water. Denver (CO): American Water Works Association Research Foundation. 310 p.

Banks S, Heinichen R. 2004. Rainwater collection for the mechanically challenged. Dripping Springs (TX): Tank Town Publishing. 108 p.

Campbell S. 1983. Home water supply: how to find, filter, store, and conserve it. Charlotte (VT): Garden Way Publishing. 240 p.

City of Albuquerque. 1999. Rainwater harvesting: supply from the sky. Albuquerque (NM): Water Use and Conservation Bureau. 32 p.

City of Albuquerque. 2000. A waterwise guide to rainwater harvesting. Albuquerque (NM): Water Use and Conservation Bureau. 4 p.

City of Austin. 1995. Sustainable building sourcebook. Austin (TX): City of Austin Environmental and Conservation Services Department. 400 p.

City of Portland. 2000. Code guide. Portland (OR): Office of Planning and Development. 18 p.

City of Tucson Code. 2004. Chapter 26, Floodplain and Erosion Hazard Area Regulations, Section 26-10, Detention/retention systems.

College of Tropical Agriculture and Human Resources. 2000. Rainwater catchment systems. Manoa (HI): University of Hawaii at Manoa. 4 p.

County of Hawaii. Undated. Guidelines for owners of rain catchment water systems. Hilo (HI): County of Hawaii. 5 p.

Darilek A. 2004 Mar 11. [Personal communication]. Office of the New Mexico State Engineer.

Darrow K, Saxenian M. 1986. Appropriate technology sourcebook: a guide to practical books for village and small community technology. Stanford (CA): Volunteers in Asia. 800 p.

Frasier G. 1974. Water harvesting symposium proceedings. Phoenix (AZ). 1974 Mar 26-28.

Gould J, Nissen-Petersen E. 1999. Rainwater catchment systems for domestic rain: design construction and implementation. London: Intermediate Technology Publications. 335 p.

Kinkade-Levario H. 2004. Forgotten rain.

Krishna H. 2001. Rainwater catchment systems in Texas. Proceedings of the 10th International Conference on Rainwater Catchment Systems of the International Rainwater Catchments Systems Association; 2001 Sep 10-14; Mannheim, Germany.

Krishna H. 2003. An overview of rainwater harvesting systems and guidelines in the United States. Proceedings of the First American Rainwater Harvesting Conference; 2003 Aug 21-23; Austin (TX).

Lye D. 1992. Microbiology of rainwater cistern systems: a review. Journal of Environmental Science and Health A27(8):2123-2166.

Lye D. 2002. Health risks associated with consumption of untreated water from household roof catchment systems. Journal of the American Water Resources Association 38(5):1301-1306.

Macomber P. 2001. Guidelines on rainwater catchment systems for Hawaii. Manoa (HI): College of Tropical Agriculture and Human Resources, University of Hawaii at Manoa. 51 p.

Morgan D, Travathan S. 2002. Storm water as a resource: how to harvest and protect a dryland treasure. Santa Fe (NM): City of Santa Fe. 24 p.

National Academy of Sciences. 1974. More water for arid lands. Washington (DC): National Academy of Sciences. 149 p.

National Park Service. 1993. Guiding principles of sustainable development. Denver (CO): Government Printing Office.

Pacey A, Cullis A. 1986. Rainwater harvesting: the collection of rainwater and runoff in rural areas. London (UK): Intermediate Technology Productions. 216 p.

Phillips A. 2003. City of Tucson water harvesting guidance manual. Tucson (AZ): City of Tucson. 36 p.

Radlet J, Radlet P. 2004. Rainwater harvesting design and installation workshop. Boerne (TX): Save the Rain.

Speidel DH, Ruesdisili LC, Agnew AF. 1987. Perspectives on water uses and abuses. New York (NY): Oxford University Press. 400 p.

Spence CC. 1980. The rainmakers: American pluviculture to World War II. Lincoln (NE): University of Nebraska Press. 181 p.

Steadman P. 1975. Energy, environment and building. New York (NY): Cambridge University Press. 287 p.

Steward JC. 1990. Drinking water hazards: how to know if there are toxic chemicals in your water and what to do if there are. Hiram (OH): EnviroGraphics.

Still GT, Thomas TH. 2003. Sizing and optimally locating guttering for rainwater harvesting. Proceedings of the 11th International Conference on Rainwater Catchment Systems; 2003 Aug 25-29; Mexico City (MX).

Thomas PR, Grenne GR. 1993. Rainwater quality from different roof catchments. Water Science Technology (28):290-99.

Texas Cooperative Extension. 2004. Rainwater Harvesting. Bryan (TX): Texas Cooperative Extension.

Texas Water Development Board. 1997. Texas guide to rainwater harvesting. Austin (TX): Texas Water Development Board. 58 p.

Texas Water Development Board. 2002. Water for Texas – 2002. Austin (TX): Texas Water Development Board. 155 p.

Vasudevan L. 2002. A study of biological contaminants in rainwater collected from rooftops in Bryan and College Station, Texas [masters thesis]. College Station (TX): Texas A&M University. 180 p.

Virgin Islands Code. 2004. Title 29, Public Planning and Development; Chapter 5, Building Code; Section 308, Water supply, cisterns, gutters, downspouts, wells.

Vitale L. 2004 Mar 11. [Personal communication]. Sante Fe County.

Waterfall P. 1998. Harvesting rainwater for landscape use. Tucson (AZ): The University of Arizona College of Agriculture and Life Sciences. 39 p.

Washington State Legislature. 2003 Mar 13. House Bill 2088.

Welsh DF, Welch WC, Duble RL. 2001. Xeriscape…Landscape Water Conservation. Bryan (TX): Texas Cooperative Extension. 16 p.

Websites

American Rainwater Catchment Systems Association, www.arcsa-usa.org

Application for Water Conservation Initiatives Property Tax Exemption, www.window.state.tx.us/taxinfo/taxforms/50-170.pdf

City of Austin Water Conservation Department, www.ci.austin.tx.us/watercon/

City of Austin Water Conservation Department, commercial process evaluations and rebates, www.ci.austin.tx.us/watercon/commercial.htm

City of Austin Water Conservation Department, rainbarrel rebate, www.ci.austin.tx.us/watercon/rainwater.htm

City of Austin Green Builder Program, www.ci.austin.tx.us/greenbuilder/

City of Tucson. 2003. Water Harvesting Guidance Manual, dot.ci.tucson.az.us/stormwater/education/waterharvest.htm

City of Tucson Code. 2004. Chapter 23, Land Use Code, Section 3.7.4.5B, Use of Water, www.tucsonaz.gov/planning/luc/luc.htm

Consortium for Energy Efficiency, list of clothes washers, www.cee1.org/resid/seha/rwsh/rwsh-main.php3

Green Builders, www.greenbuilder.com

Hays County, guidelines for rainwater harvesting benefits and qualifications, www.co.hays.tx.us/departments/envirohealth/forms.php

International Rainwater Catchment Systems Association, www.ircsa.org

National Climate Data Center, www.ncdc.noaa.gov

National Oceanographic and Atmospheric Administration, www.noaa.gov

NSF International, filter performance, www.nsf.org/certified/DWTU/

NSF International, NSF/ANSI Standard 61, Drinking Water System Components, www.nsf.org/business/water_distribution/standards.asp?program=WaterDistributionSys

Office of Arid Land Studies Desert Research Unit, Casa del Agua, www.ag.arizona.edu/OALS/oals/dru/casadelagua.html

Office of the State Comptroller, application for sales tax exemption, www.window.state.tx.us/taxinfo/taxforms/01-3392.pdf

Office of the State Comptroller, application for water conservation initiatives property tax exemption, www.window.state.tx.us/taxinfo/taxforms/50-270.pdf

Ohio Department of Health Final Rules, 3701-28-09 Continuous Disinfection, www.odh.ohio.gov/Rules/Final/Chap28/Fr28_lst.htm

Organization of American States, Rainwater Harvesting from Rooftop Catchments, www.oas.org/usde/publications/Unit/oea59e/ch10.htm

Rain Water Harvesting and Waste Water Systems Pty Ltd., www.rainharvesting.com.au

San Antonio Water System, large-scale retrofit rebate program, www.saws.org/conservation/commercial/retrofit.shtml

State Energy Conservation Office, www.seco.cpa.state.tx.us/sa_performcontract.htm

State Energy Conservation Office, Suggested Water Efficiency Guidelines for Buildings and Equipment at Texas State Facilities, www.seco.cpa.state.tx.us/waterconservation.pdf

Texas Administrative Code, www.sos.state.tx.us/tac/

Texas Commission on Environmental Quality, Air Quality Monitoring, www.tceq.state.tx.us/nav/data/pm25.html

Texas Commission on Environmental Quality, application and instructions for use determination for pollution control property and predetermined equipment list, www.tnrcc.state.tx.us/exec/chiefeng/prop2/guidance.pdf

Texas Commission on Environmental Quality, chemical constituents, www.tnrcc.state.tx.us/airquality.html

Texas Commission on Environmental Quality, property tax exemptions for pollution control property, www.tnrcc.state.tx.us/exec/chiefeng/prop2/0611.doc

Texas county appraisal districts, www.texascad.com

Texas Department of State Health Services, county health departments, www.dshs.state.tx.us/regions/default.shtm

Texas Department of State Health Services, testing for fecal coliforms, www.dshs.state.tx.us/lab/default.shtm

Texas Evapotranspiration, texaset.tamu.edu

Texas Legal Directory, county appraisal districts, www.texascad.com

Texas Legislature Online, www.capitol.state.tx.us/

Texas Master Gardeners, aggiehorticulture.tamu.edu/mastergd/mg.html

Texas Statutes Education Code, www.capitol.state.tx.us/statutes/ed.toc.htm

Texas Statutes Local Government Code, www.capitol.state.tx.us/statutes/lg.toc.htm

Texas Statutes Tax Code, www.capitol.state.tx.us/statutes/tx.toc.htm

Texas Water Development Board, Water Conservation Best Management Practices Guide, p 96-101, www.twdb.state.tx.us/assistance/conservation/TaskForceDocs/WCITFBMPGuide.pdf

Texas Water Development Board Conservation, www.twdb.state.tx.us/assistance/conservation/consindex.asp

United States Environmental Protection Agency, drinking water requirements, www.epa.gov/safewater/mcl.html

United States Environmental Protection Agency Safe Drinking Water Act, www.epa.gov/safewater/sdwa/sdwa.htm

This page intentionally left blank.

Appendix B
Rainfall Data

The following data are provided for representative Texas cities in various geographical areas to assist in assessing the optimal storage size for a particular rainwater harvesting system. Each rainwater harvesting system designer should assess the variables of water demand, rainfall, catchment surface area, storage capacity, and risk tolerance when designing a rainwater harvesting system, especially one intended to be the sole water source.

Abilene

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Minimum	0.00	0.00	0.03	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Maximum	4.35	3.60	5.16	6.80	13.17	9.60	7.52	8.18	11.03	10.68	4.60	6.28
Median	0.81	0.73	0.90	1.88	2.47	2.30	1.69	1.62	2.25	2.09	0.94	0.77
Average	1.00	1.05	1.17	2.05	3.22	2.90	2.03	2.40	2.71	2.56	1.24	1.03

Average annual rainfall **23.36**

Amarillo

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Minimum	0.00	0.00	0.00	0.00	0.04	0.01	0.10	0.28	0.03	0.00	0.00	0.00
Maximum	2.33	1.83	4.01	5.84	9.81	10.73	7.59	7.55	5.02	6.34	2.26	4.52
Median	0.33	0.42	0.58	0.86	2.45	3.08	2.59	2.79	1.61	0.97	0.43	0.35
Average	0.52	0.55	0.93	1.18	2.67	3.40	2.80	2.93	1.84	1.44	0.59	0.53

Average annual rainfall **19.39**

Austin

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Minimum	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.09	0.00	0.00	0.00
Maximum	9.21	6.56	6.03	9.93	9.98	14.96	10.54	8.90	7.44	12.31	7.95	14.16
Median	1.27	2.30	1.73	2.20	3.68	2.89	1.15	1.27	2.98	2.82	1.88	1.42
Average	1.77	2.37	1.90	2.83	4.33	3.54	1.73	2.18	3.17	3.63	2.25	2.26

Average annual rainfall **31.96**

Brady

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Minimum	0.00	0.10	0.00	0.00	0.06	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Maximum	6.40	5.30	4.30	6.02	8.00	7.70	13.55	11.30	9.45	7.04	10.40	7.90
Median	0.60	1.26	0.90	1.78	3.10	1.87	0.85	1.34	2.40	1.70	1.10	0.70
Average	1.03	1.50	1.26	2.07	3.40	2.40	1.80	2.01	2.86	2.34	1.43	1.28

Average annual rainfall **23.38**

Brownsville

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
Minimum	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.02	0.07	0.34	0.01	0.00	
Maximum	4.79	10.25	5.72	10.35	9.12	8.52	9.43	9.56	20.18	17.12	7.69	3.98	
Median	0.77	0.84	0.41	0.84	1.86	2.22	0.96	2.45	4.69	2.92	0.90	0.78	
Average	1.31	1.38	0.80	1.62	2.39	2.55	1.50	2.69	5.19	3.62	1.55	1.10	
Average annual rainfall													**25.70**

College Station

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
Minimum	0.22	0.1	0.29	0.08	0.23	0.09	0	0	0.32	0	0.19	0.23	
Maximum	15.6	9.82	6.07	12.5	11.38	12.63	7.06	10.63	12.13	12.91	8.33	10.72	
Median	2.205	2.72	2.12	3.75	4.515	2.895	1.97	1.84	4.12	3.18	2.92	2.635	
Average	2.87	2.88	2.5	3.77	4.73	3.79	2.24	2.43	4.3	3.64	3.07	3.15	
Average annual rainfall													**38.75**

Corpus Christi

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
Minimum	0.01	0.00	0.00	0.00	0.00	0.03	0.00	0.10	0.49	0.00	0.00	0.01	
Maximum	10.78	8.11	4.89	8.04	9.38	13.35	11.92	14.79	20.33	11.88	5.24	9.80	
Median	0.99	1.36	0.78	1.39	2.70	2.43	1.04	2.64	4.00	2.60	1.34	0.90	
Average	1.54	1.85	1.36	2.03	3.12	3.16	1.80	3.28	5.21	3.50	1.57	1.59	
Average annual rainfall													**30.00**

Dallas

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
Minimum	0.00	0.25	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.18	0.13	
Maximum	8.46	7.60	8.70	15.40	13.74	10.30	7.34	5.12	10.67	14.00	7.54	8.90	
Median	1.80	2.11	2.36	2.98	4.27	2.85	1.60	1.74	2.50	2.94	2.00	2.10	
Average	1.97	2.40	2.91	3.81	5.01	3.12	2.04	2.07	2.67	3.76	2.70	2.64	
Average annual rainfall													**35.10**

El Paso

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
Minimum	0.00	0.00	0.00	0.00	0.00	0.00	0.04	0.00	0.00	0.00	0.00	0.00	
Maximum	2.23	1.69	2.26	1.42	4.22	3.18	5.53	5.57	6.68	3.12	1.63	3.29	
Median	0.29	0.34	0.18	0.09	0.10	0.36	1.18	1.06	0.96	0.55	0.24	0.42	
Average	0.42	0.40	0.30	0.21	0.32	0.70	1.57	1.45	1.38	0.71	0.36	0.61	
Average annual rainfall													**8.43**

Houston

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
Minimum	0.36	0.38	0.11	0.43	0.04	0.26	0.45	0.31	0.80	0.05	0.41	0.64	
Maximum	9.78	5.99	8.52	10.92	14.39	16.28	8.10	9.42	11.35	16.05	10.07	9.34	
Median	2.82	2.63	3.19	2.59	5.02	3.55	2.69	3.52	3.92	3.79	3.27	3.41	
Average	3.68	2.95	3.40	3.54	5.36	5.07	3.05	3.69	4.31	4.63	4.09	3.54	
Average annual rainfall													**48.45**

Lubbock

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
Minimum	0.00	0.00	0.00	0.04	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
Maximum	4.05	2.51	3.34	5.63	13.38	8.43	7.20	8.85	8.55	10.80	2.67	2.24	
Median	0.33	0.39	0.63	1.08	2.23	2.37	2.07	1.78	1.87	0.98	0.45	0.42	
Average	0.52	0.62	0.90	1.24	2.64	2.95	2.16	2.15	2.49	1.81	0.67	0.56	
Average annual rainfall													**18.49**

San Angelo

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
Minimum	0.00	0.01	0.00	0.00	0.26	0.05	0.00	0.00	0.00	0.00	0.00	0.00	
Maximum	3.65	4.47	5.00	5.10	11.24	6.01	7.21	8.13	11.00	8.68	3.55	3.98	
Median	0.58	0.62	0.65	1.29	2.32	2.09	0.70	1.38	2.38	1.90	0.68	0.33	
Average	0.79	1.04	0.92	1.66	2.78	2.20	1.10	1.75	2.83	2.24	0.98	0.76	
Average annual rainfall													**19.12**

San Antonio

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
Minimum	0.00	0.01	0.03	0.02	0.00	0.01	0.00	0.00	0.05	0.00	0.00	0.03	
Maximum	8.52	6.43	6.12	9.32	12.85	11.95	8.29	11.14	13.09	17.96	8.51	13.96	
Median	1.10	1.85	1.27	1.94	3.04	2.70	1.21	2.00	2.24	2.75	1.93	1.09	
Average	1.59	1.92	1.66	2.52	3.97	3.61	1.82	2.45	3.08	3.42	2.24	1.69	
Average annual rainfall													**29.96**

Waco

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
Minimum	0.03	0.00	0.04	0.12	0.52	0.27	0.00	0.00	0.00	0.00	0.13	0.04	
Maximum	5.92	7.69	5.56	13.37	15.00	12.06	8.58	8.91	7.29	10.51	7.03	9.72	
Median	1.55	2.00	2.22	2.76	3.87	2.34	0.82	0.96	2.57	2.37	2.29	1.94	
Average	1.83	2.28	2.25	3.30	4.49	2.98	1.82	1.76	3.02	3.12	2.40	2.31	
Average annual rainfall													**31.68**

This page intentionally left blank.

Appendix C
Case Studies

Lady Bird Johnson Wildflower Center
Austin

4801 La Crosse Avenue
Austin, Texas 78739
(512) 292-4100
http://www.wildflower.org

Capacity:	70,000 gallons
Catchment area:	17,000 square feet
Demand:	Gardens and landscaping

The entry cistern at the Lady Bird Johnson Wildflower Research Center is reminiscent of the stone-and-mortar cisterns used by Hill Country settlers. Water from a 1,200-square-foot roof area is conveyed to the entry cistern via an aqueduct.

Harvested rainwater from three separate catchment areas provides 10 to 15 percent of the garden and landscaping irrigation of the Lady Bird Johnson National Wildflower Research Center in Austin. An integral part of its architecture, the Center's rainwater harvesting system serves to not only conserve water, but also as a public education tool. The Center collects water from 17,000 square feet of roof space and can store more than 70,000 gallons in on-site cisterns.

One of the most prominent features of the center is the 43-foot native-stone-façade tower cistern, which is built around a 5,000-gallon storage tank. Metal rooftops totaling an area of 17,000 square feet drain into the tower cistern and two 25,000-gallon tanks collect a total of about 300,000 gallons in an average rainfall year. A pressurized distribution system delivers water from the large tanks to an irrigation system. The municipal water supply is linked to the systems with backflow prevention devices to prevent water contamination.

The 3,000-gallon entry cistern, fed by an elevated stone-faced aqueduct draining just less than 1,200 square feet of roof area, is reminiscent of rainwater cisterns used by original Hill Country settlers. The Little House cistern captures rainwater from a roof area of about 700 square feet in the Children’s Area.

In addition, the Wetland Pond, the Commons Well, and the Balcony Spring together collect 2,500 gallons per inch of rain from the roofs, although water from these features is not used for irrigation.

H-E-B
Austin

6900 Brodie Lane
(corner William Cannon Blvd. and Brodie Lane)
Austin, Texas 78745

Capacity:	28,000 gallons
Catchment area:	50,000 square feet
Demand:	Native and adapted plant landscape

The H-E-B at the corner of Brodie Lane and William Cannon Blvd. in south central Austin irrigates an adjacent landscape of water-thrifty plants with rainwater stored in four painted steel tanks totaling 28,000 gallons. A 24-inch-diameter pipe conveys water from the roof to the tanks.

Two 8,000-gallon and two 6,000-gallon painted steel tanks are fed from a 24-inch-diameter collection pipe draining the 50,000-square-foot roof. Using efficient drip irrigation, captured rainwater irrigates an adjacent water-thrifty landscape of native and adapted trees and ornamentals. Walkways and plant labels enhance the attractiveness of the site.

The four tanks are connected with 6-inch PVC pipes and valves, allowing a tank to be taken off-line to be drained and cleaned.

H-E-B, based in San Antonio, prides itself on environmental stewardship in the communities where its supermarkets conduct business. H-E-B saves 6.2 million gallons of water annually by recycling condensation from manufacturing steam equipment.

Tanks are linked with 6-inch PVC pipe. Valves allow taking one or more tank off-line for draining or cleaning.

Sunset Canyon Pottery
Dripping Springs

4002 E. Highway 290
Dripping Springs, Texas 78620
(512) 894-0938

Sunset Canyon Pottery supplies all its potable and pottery works water demand with water stored in a 46,000-gallon ferrocement tank. When visiting this site on private property, please first request permission from Sunset Canyon Pottery staff.

The ferrocement tank at Sunset Canyon Pottery supplies process water for pottery works, as well as potable water for the straw-bale studio and gift shop. The tank was constructed first by forming an armature of steel reinforcement bars, then spraying on a cement-like material similar to that used for in-ground swimming pools.

New Braunfels Municipal Utility District
New Braunfels

New Braunfels Utilities Service Center
355 FM 306
New Braunfels, Texas 78130

The New Braunfels Utilities Service Center, completed in 2004, captures rainwater in four 1,000-gallon plastic-lined galvanized steel tanks, one located at each building wing. Water is used to irrigate the landscape of native and adapted plants. The metal tanks form both a practical and aesthetic feature of the architecture of this public building.

Four lined, galvanized steel tanks will capture water for irrigation of native and adapted plants.

Hays County Cooperative Extension Office
San Marcos

1253 Civic Center Loop
San Marcos, Texas 78666
(512) 393-2120

Capacity:	750-gallon galvanized metal tank 1,600 polyethylene tank
Catchment area:	2,500 square feet
Demand:	Demonstration garden
Cost:	$1,125



As a demonstration project, a 750-gallon galvanized steel tank captures rainwater from the 5,000-square-foot roof of the Hays County Extension Office.

The Hays County Extension Office captures rainwater from half the roof area of its 5,000-square-foot building in two tanks: a 750-gallon galvanized steel tank and a 1,600-gallon black polypropylene tank using existing guttering and downspouts. Plans are in the works for water to be gravity-fed to an adjacent Master Gardener demonstration garden.

Edwards Aquifer Authority
San Antonio

1615 N. St. Mary's Street
San Antonio, TX 78215
(210) 222-2204

Capacity:	2,500 gallons
Catchment area:	1,135 square feet
Demand:	Landscaping

The Edwards Aquifer Authority collects rainwater from a catchment area of 1,135 square feet in two cisterns. Water is delivered through gravity flow into a 500-gallon polypropylene tank in the courtyard area. The second cistern, a 2,000-gallon ranch-style metal cistern, is located on the front lawn, visible from the street. Harvested rainwater is used to irrigate the 266-square-foot courtyard, and 2,700-square-foot lawn.

A 2,000-gallon, ranch-style metal cistern is one of two tanks that capture rainwater for landscaping at the Edwards Aquifer Authority building. (Photo courtesy: Lara Stuart)

J.M. Auld Lifetime Learning Center
Kerrville

1121 Second Street
Kerrville, Texas 72028
(830) 257-2218

Capacity:	6,600 gallons (Two 3,300-gallon stacked concrete ring tanks)
Catchment area:	5,000 square feet
Demand:	Adjacent gardens Pondless waterfall
Total Cost:	$10,500
Breakdown:	Two 3,300 concrete tanks, $4,766 Plumbing supplies, $520 Pump, pressure tank, switch, $1,535 Gutter work, $541 Electrical supplies, $160 Trencher rental, $175 In-kind labor, Kerrville ISD, $2,800

Stacked concrete ring 3,000-gallon tank at the Auld Center, Kerrville, showing first flush diverter and cistern.

The Auld Lifelong Learning Center of Kerrville Independent School District is a community education facility operated by Kerrville Independent School District. Installed in 2003, two 3,300-gallon stacked concrete-ring tanks collect rainwater from a 5,000-square-foot roof. Tanks are located at the back corners of the building, with a transverse 3-inch PVC pipe conveying the rainwater drained from the front half of the roof. Five-gallon first flush diverters at each corner capture the dust and debris of the initial runoff of each rainfall event.

Tanks are fitted with unique water-level sight gages. Vertical rods the same length as the tank height are suspended on floating platforms within the tank. The length of rod protruding from the tops of tanks indicates water level.

Captured rainwater will irrigate several adjacent themed gardens. In addition, a unique water feature, a recirculating waterfall, adds aesthetic interest.

Menard ISD Elementary School
Menard

200 Gay St.
Menard, Texas 76859

Container garden and landscape-plant irrigation

Capacity:	1,000-gallon green polyethylene tank
Catchment area:	600 square feet
Demand:	50 emitters: 20 landscape plants, 30 container garden emitters
Total cost:	$475
Breakdown:	Tank, $400 Connections and valves/roofwasher, $35 Black poly pipe and emitters, $40

The rainwater harvesting system serves multiple purposes of education, beauty, and habitat improvement at Menard Independent School District Elementary School. The wildscape provides the requirements of food, water, and shelter for native animals. The demonstration site aids in teaching students about healthful wildlife habitats and container and landscape gardening. The water features, gazebo, and rock walkway enhance the outdoor esthetics of the school. A backyard wildscape at Menard Elementary School demonstrates the requirements of food, water, and shelter for rangeland maintenance conducive to supporting wildlife. Using existing gutters and downspouts from the roof of Menard Elementary School, rainwater is diverted into two 1,000-gallon green polypropylene tanks. One tank supplies a birdbath made of rocks with natural cavities and a prefabricated pond. Both water features are supplied with water conveyed by gravity pressure through 3/4-inch PVC pipe and drip emitters. Native plants provide a food source and cover for wildlife.

Using existing gutters and downspouts, rainwater harvesting techniques were used to create a backyard wildscape. The principles of wildscape construction can be transferred to large wildlife management programs.

Menard Elementary School rainwater harvesting installation showing downspout, 1,000-gallon poly tank, and gazebo (left) surrounded by native and adapted landscape plants. In this very attractive installation, harvested rainwater (using existing gutter and downspouts) furnishes water not only to the landscape, but also to a watering pond, birdbath, and wildlife guzzler. (Photo courtesy: Billy Kniffen)

Walker County Cooperative Extension Office
Huntsville

102 Tam Road
Huntsville, Texas 77320
(936) 435-2426

Capacity:	550-gallon polyethylene tank
Catchment area:	1,500 square feet
Demand:	Master Gardener demonstration plot
Total cost:	Total: $230
Breakdown:	Used 550-gallon tank, $150 Plumbing supplies and fittings, $70 Glue, thinner, and paint, $10

Rainwater captured from the 1,500-square-foot roof of the Walker County Extension office is stored in a 550-gallon polypropylene tank, a type readily available at ranch supply retailers. The 10-gallon flush diverter is the vertical standpipe visible to the left of the tank. Captured rainwater irrigates an adjacent Master Gardener demonstration garden, foreground.

The Walker County Master Gardeners and staff of Texas Cooperative Extension, supervised by agricultural county agent Reginald Lepley, installed a rainwater harvesting system at the Walker County Extension office for a cost of less than $250. A used white 550-gallon polypropylene tank was thoroughly cleaned and pressure-washed, and painted with brown latex paint to discourage algae growth. Raising the tank on concrete blocks allows gravity flow to a 10-foot by 25-foot Master Gardener demonstration garden. A detailed parts list, instructions and tips for rainwater harvesting in general, and more information on this installation can be found at

urbantaex.tamu.edu/D9/Walker/AG/HomeHort/WCMG/hortdemo/Waterdemo/index

AMD/Spansion FAB25
Austin

5204 E. Ben White Blvd.
Austin, Texas 78741

Rainwater drained from the facility's roofs and groundwater from the building perimeter drains furnish all the water needed for landscape irrigation on AMD's Spansion site in east Austin. Water is collected and stored in a 10,000-gallon fiberglass tank, and then pressurized through the site irrigation loop using surplus pumps. The water savings has been verified at about 4.75 million gallons per year using online flow meters. In-house engineers designed the system and facilities tradespersons installed the tank, pump, piping, and electricity. The irrigation reclaim system has a three-year return on investment.

The plant also has segregated drains that allow the reuse and recycling of rinse water from the wafer manufacturing process for cooling tower and Ultra-pure treatment plant makeup drastically reducing city-supplied water. The water savings from the rinse water reuse system is approximately 210 million gallons per year and had a return on investment of less than one year.

J.J. Pickle Elementary School/St. John Community Center Austin

Corner of Blessing and Wheatley Avenues
Austin, Texas

A model of sustainable design and building, the J.J. Pickle Elementary and St. John Community Center in northeast Austin is a joint project of Austin Independent School District and the City of Austin. Water from a portion of the 116,200-square-foot facility drains into three tanks, which provide cooling water to the air-conditioning system.

For energy savings, the classrooms, gym, dining area, and City library use sunlight rather than electric lights during the day. The complex opened in January 2002, with operational and maintenance cost savings of $100,000 expected each year.

The complex includes a public elementary school, shared gymnasium, a health center, public and school libraries, and a community policing office. The cost of construction is $13.6 million, with the AISD funding about $8.3 million and the City of Austin funding about $5.3 million. The money came from a 1996 School District bond election and a City 1998 bond package.

Water collected from the roof of the J.J. Pickle Elementary School and St. John Community Center is stored in three large tanks behind the building and used as cooling water for the complex's air-conditioning system.

Feather & Fur Animal Hospital
Austin

9125 Manchaca Road
Austin, Texas 78748

The Feather & Fur Animal Hospital in South Austin features a standing-seam metal roof for rainwater harvesting.

Captured water from the roof, parking lot, and condensate from the air conditioners is the sole source irrigation water for a 1-acre turf landscape at the Feather & Fur Animal Hospital in South Austin. Dr. Howard Blatt first explored ways to make use of an existing hand-dug 18,000-gallon underground cistern. The project has since been expanded to take advantage of other rainwater sources.

Rainwater collected from a standing-seam metal roof gravity flows into the cistern. Then water from the parking lot flows through a water quality pond with gabion for sedimentation and filtration treatment. From the pond, water flows via a 6-inch pipe to catch basin. A small sump pump empties to a 12,500-gallon fiberglass tank. Additionally, the primary condensation line from the air handlers also drains into the gutter and downspout system, which services the roof.

Pomerening/Dunford Residence
Bexar County

The Pomerening/Dunford family lives on the western edge of Bexar County and uses rainwater harvesting for all of their potable needs. The four-year-old installation features two 10,000-gallon cisterns that store captured water from a 2,400-square-foot collection area.

Two 10,000-gallon cisterns collect rainwater at the Pomerening/Dunford residence in Bexar County.

This page intentionally left blank.

Appendix D
Tax Exemption Application Form



01-339(Back)
(Rev.6-04/5)

TEXAS SALES AND USE TAX EXEMPTION CERTIFICATION

Name of purchaser, firm or agency	
Address *(Street & number, P.O. Box or Route number)*	Phone *(Area code and number)*
City, State, ZIP code	

I, the purchaser named above, claim an exemption from payment of sales and use taxes (for the purchase of taxable items described below or on the attached order or invoice) from:

Seller: ____

Street address: ________________________ City, State, ZIP code: ________________

Description of items to be purchased or on the attached order or invoice:

Purchaser claims this exemption for the following reason:

I understand that I will be liable for payment of sales or use taxes which may become due for failure to comply with the provisions of the Tax Code: Limited Sales, Excise, and Use Tax Act; Municipal Sales and Use Tax Act; Sales and Use Taxes for Special Purpose Taxing Authorities; County Sales and Use Tax Act; County Health Services Sales and Use Tax; The Texas Health and Safety Code; Special Provisions Relating to Hospital Districts, Emergency Services Districts, and Emergency Services Districts in counties with a population of 125,000 or less.

I understand that it is a criminal offense to give an exemption certificate to the seller for taxable items that I know, at the time of purchase, will be used in a manner other than that expressed in this certificate and, depending on the amount of tax evaded, the offense may range from a Class C misdemeanor to a felony of the second degree.

sign here ▶ Purchaser	Title	Date

NOTE: This certificate cannot be issued for the purchase, lease, or rental of a motor vehicle.
THIS CERTIFICATE DOES NOT REQUIRE A NUMBER TO BE VALID.
Sales and Use Tax "Exemption Numbers" or "Tax Exempt" Numbers do not exist.

This certificate should be furnished to the supplier. Do **not** send the completed certificate to the Comptroller of Public Accounts.

ORNL/CON-295

OAK RIDGE
NATIONAL
LABORATORY

MARTIN MARIETTA

Builder's Foundation Handbook

John Carmody
Jeffrey Christian
Kenneth Labs



Part of the National Program for
Building Thermal Envelope Systems and Materials

Prepared for the
U.S. Departmet of Energy
Conservation and Renewable Energy
Office of Buildings and Community Systems
Building Systems Division

MANAGED BY
MARTIN MARIETTA ENERGY SYSTEMS, INC.
FOR THE UNITED STATES
DEPARTMENT OF ENERGY

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615) 576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Builder's Foundation Handbook

John Carmody
Underground Space Center
University of Minnesota

Jeffrey Christian
Oak Ridge National Laboratory
Oak Ridge, Tennessee

Kenneth Labs
Undercurrent Design Research
New Haven, Connecticutt

Book Design and Illustrations: John Carmody

Date of Publication: May, 1991

Prepared for:

Oak Ridge National Laboratory
Oak Ridge, Tennessee 37831

Operated by:

Martin Marietta Energy Systems, Inc.
for the U. S. Department of Energy
under Contract DE-AC05-84OR21400

List of Figures and Tables

Chapter 1 Figures

Figure 1-1: The impact of basement insulation is monitored on several modules at the foundation test facility at the University of Minnesota.
Figure 1-2: Benefits of Foundation Insulation and Other Design Improvements
Figure 1-3: The impact of slab-on-grade foundation insulation is monitored in a test facility at Oak Ridge National Laboratory.
Figure 1-4: Decision-Making Process for Foundation Design
Figure 1-5: Basic Foundation Types
Figure 1-6: Points of Radon Entry into Buildings

Chapter 2 Figures

Figure 2-1: Concrete Masonry Basement Wall with Exterior Insulation
Figure 2-2: Components of Basement Structural System
Figure 2-3: Components of Basement Drainage and Waterproofing Systems
Figure 2-4: Termite Control Techniques for Basements
Figure 2-5: Radon Control Techniques for Basements
Figure 2-6: Soil Gas Collection and Discharge Techniques
Figure 2-7: System of Key Numbers in Construction Drawings that Refer to Notes on Following Pages
Figure 2-8: Concrete Basement Wall with Exterior Insulation
Figure 2-9: Concrete Basement Wall with Exterior Insulation
Figure 2-10: Masonry Basement Wall with Exterior Insulation
Figure 2-11: Concrete Basement Wall with Interior Insulation
Figure 2-12: Concrete Basement Wall with Ceiling Insulation
Figure 2-13: Pressure-Preservative-Treated Wood Basement Wall

Chapter 3 Figures

Figure 3-1: Concrete Crawl Space Wall with Exterior Insulation
Figure 3-2: Components of Crawl Space Structural System
Figure 3-3: Crawl Space Drainage Techniques
Figure 3-4: Crawl Space Drainage Techniques
Figure 3-5: Termite Control Techniques for Crawl Spaces
Figure 3-6: Radon Control Techniques for Crawl Spaces
Figure 3-7: System of Key Numbers in Construction Drawings that Refer to Notes on Following Pages
Figure 3-8: Vented Crawl Space Wall with Ceiling Insulation
Figure 3-9: Unvented Crawl Space Wall with Exterior Insulation
Figure 3-10: Unvented Crawl Space Wall with Interior Insulation
Figure 3-11: Unvented Crawl Space Wall with Interior Insulation

Chapter 4 Figures

Figure 4-1: Slab-on-Grade Foundation with Exterior Insulation
Figure 4-2: Structural Components of Slab-on-Grade Foundation with Grade Beam
Figure 4-3: Structural Components of Slab-on-Grade Foundation with Stem Wall and Footing
Figure 4-4: Drainage Techniques for Slab-on-Grade Foundations
Figure 4-5: Termite Control Techniques for Slab-on-Grade Foundations
Figure 4-6: Radon Control Techniques for Slab-on-Grade Foundations
Figure 4-7: Soil Gas Collection and Discharge Techniques
Figure 4-8: System of Key Numbers in Construction Drawings that Refer to Notes on Following Pages
Figure 4-9: Slab-on-Grade with Integral Grade Beam (Exterior Insulation)
Figure 4-10: Slab-on-Grade with Brick Veneer (Exterior Insulation)
Figure 4-10: Slab-on-Grade with Brick Veneer (Exterior Insulation
Figure 4-12: Slab-on-Grade with Masonry Wall (Exterior Insulation))
Figure 4-13: Slab-on-Grade with Concrete Wall (Insulation Under Slab)
Figure 4-14: Slab-on-Grade with Masonry Wall (Insulation Under Slab)
Figure 4-15: Slab-on-Grade with Masonry Wall (Interior Insulation)
Figure 4-16: Slab-on-Grade with Brick Veneer (Insulation Under Slab)

Chapter 5 Figures

Figure 5-1: Steps in Worksheet to Determine Optimal Foundation Insulation
Figure 5-2: Formulas Used as a Basis for Worksheet 1
Figure 5-3: Formulas Used as a Basis for Worksheet 3

Chapter 2 Tables

Table 2-1: Insulation Recommendations for Fully Conditioned Deep Basements
Table 2-2: Insulation Recommendations for Unconditioned Deep Basements
Table 2-3: Fuel Price Levels Used to Develop Recommended Insulation Levels in Tables 2-1 and 2-2

Chapter 3 Tables

Table 3-1: Insulation Recommendations for Crawl Spaces
Table 3-2: Fuel Price Levels Used to Develop Recommended Insulation Levels in Table 3-1

Chapter 4 Tables

Table 4-1: Insulation Recommendations for Slab-on-Grade Foundations
Table 4-2: Fuel Price Levels Used to Develop Recommended Insulation Levels in Table 4-1

Chapter 5 Tables

Table 5-1: Weather Data for Selected Cities (page 1 of 2)
Table 5-2: Insulation R-Values and Costs for Conditioned Basements (page 1 of 4)
Table 5-2: Insulation R-Values and Costs for Slab-on-Grade Foundations (page 4 of 4)
Table 5-3: Heating Load Factor Coefficients (HLF_I and HLF_S)
Table 5-4: Cooling Load Factor Coefficients (CLF_I and CLF_S)
Table 5-5: Initial Effective R-values for Uninsulated Foundation System and Adjacent Soil
Table 5-6: Heating and Cooling Equipment Seasonal Efficiencies[1]
Table 5-7: Scalar Ratios for Various Economic Criteria
Table 5-8: Energy Cost Savings and Simple Paybacks for Conditioned Basements
Table 5-8: Energy Cost Savings and Simple Paybacks for Conditioned Basements
Table 5-10: Energy Cost Savings and Simple Paybacks for Crawl Space Foundations
Table 5-11: Energy Cost Savings and Simple Paybacks for Slab-on-Grade Foundations

Preface

This handbook is a product of the U.S. Department of Energy Building Envelope Systems and Materials (BTESM) Research Program centered at the Oak Ridge National Laboratory. The major objective of this research is to work with builders, contractors, and building owners to facilitate the reality of cost-effective energy efficient walls, roofs, and foundations on every building. This handbook is one of a dozen tools produced from the BTESM Program aimed at relevant design information in a usable form during the decision-making process.

The *Builder's Foundation Handbook* contains a worksheet (Chapter 5) to help select insulation levels based on specific building construction, climate, HVAC equipment, insulation cost, and other economic considerations. This worksheet permits you to select the optimal insulation level for new and retrofit applications.

This handbook contains construction details representative of good practices for the design and installation of energy efficient basement, crawl space, and slab-on-grade foundations. In the preface to the *Building Foundation Design Handbook* published in 1988, I asked for comments on how to improve future editions. Most of the suggestions received have been incorporated into this version. For example, one suggestion was to add a detail showing how to insulate a slab-on-grade foundation supporting an above-grade wall with brick veneer. This detail appears as Figure 4-10.

The construction details are accompanied by critical design information useful for specifying structural integrity; thermal and vapor controls; subsurface drainage; waterproofing; and mold, mildew, odor, decay, termite, and radon control strategies. Another useful feature is a checklist which summarizes the major design considerations for each foundation type—basement (Chapter 2), crawl space (Chapter 3), and slab (Chapter 4). These checklists have been found to be very useful during the design stage and could be very useful during construction inspection.

The first foundation handbook from the BTESM program—the *Building Foundation Design Handbook*—was released to the public in May 1988. Since that time several significant national codes have adopted foundation insulation levels based on research results from this program. In October 1988, the Council of American Building Officials Model Energy Code Committee accepted an upgrade to more energy efficient foundations. Several states have adopted the Model Energy Code into their building inspection programs including Iowa and Utah. The Department of Housing and Urban Development (HUD) Minimum Property Standard also looks as if it is going to adopt these foundation insulation recommendations.

Foundation insulation is gaining acceptance in the U.S. residential building industry. Moisture and indoor air quality problems caused by faulty foundation design and construction continue to grow in importance. The material contained in this handbook represents suggestions from a diverse group of knowledgeable foundation experts and will help guide the builder to foundation systems that are easily constructed and that have worked for others in the past, and will work for you in the future.

I welcome your response to this handbook. Please send me your comments and suggestions for improving future editions.

Jeffrey E. Christian
Oak Ridge National Laboratory
P.O. Box 2008
Building 3147 MS 6070
Oak Ridge, TN 37831-6070

Acknowledgments

This handbook, directed at builders, grew from a “brain storming” session including representatives from the research and building communities back in 1987. It was recognized that after development of a more comprehensive design manual, the *Building Foundation Design Handbook* (Labs, et al. 1988), it would be desirable to condense the pertinent information into a handbook for builders.

The authors are grateful to all those who participated in the development of the earlier *Building Foundation Design Handbook*, from which most of the material in this handbook is drawn. In particular we acknowledge the contributions of the following authors of the original book: Raymond Sterling, Lester Shen, Yu Joe Huang, and Danny Parker.

Funding support for this report came from Sam Taylor and John Goldsmith at the U.S. Department of Energy. Sam Taylor also insisted on a high quality book with an inviting format to better convey the important messages contained in all this fine print.

The handbook was graciously reviewed and enhanced by a number of foundation experts. Several of the reviewers provided lengthy lists of constructive suggestions: Don Leubs, National Association of Home Builders / National Research Center; Mark Kelly, Building Science Engineering; Phil Hendrickson, Dow Chemical; Peter Billings, National Forest Products Association; J.D. Ned Nisson, Energy Design Update; Mark Feirer, Fine Homebuilding; Steven Bliss, Journal of Light Construction; Bob Wendt, Oak Ridge National Laboratory; Ron Graves, Oak Ridge National Laboratory; Martha Van Geem, Construction Technology Laboratories; Dave Murane, Environmental Protection Agency; Roy Davis and Pat Rynd, UC Industries, Inc.; Jon Mullarky and Jim Roseberg, National Ready Mix Contractor Association; Donald Fairman and William Freeborne, U.S. Department of Housing; Douglas Bowers, Geotech; Joe Lstiburek; John Daugherty, Owens-Corning Fiberglas; and Tom Greeley, BASF Corporation.

All of the drawings and the graphic design of the handbook were done by John Carmody of the Underground Space Center at the University of Minnesota. The authors appreciate the contribution of Pam Snopl who edited the final manuscript.

Abstract

This handbook contains a worksheet for selecting insulation levels based on specific building construction, climate, HVAC equipment, insulation cost, and other economic considerations. The worksheet permits optimization of foundation insulation levels for new or retrofit applications. Construction details representing good practices for the design and installation of energy efficient basement, crawl space, and slab-on-grade foundations are the focal point of the handbook. The construction details are keyed to lists of critical design information useful for specifying structural integrity; thermal and vapor control; subsurface drainage; waterproofing; and mold, mildew, odor, decay, termite, and radon control strategies. Another useful feature are checklist chapter summaries covering major design considerations for each foundation type--basement, crawl space, and slab-on-grade. These checklist summaries are useful during design and construction inspection. The information in this handbook is drawn heavily from the first foundation handbook from the DOE/ORNL Building Envelope Systems and

Materials Program, the *Building Foundation Design Handbook* (Labs et al., 1988), which is an extensive technical reference manual. This book presents "what to do in foundation design" in an inviting, concise format. This handbook is intended to serve the needs of active home builders; however, the information is pertinent to anyone involved in foundation design and construction decisions including homeowners, architects, and engineers.

CHAPTER 1

Introduction to Foundation Design

The foundation of a house is a somewhat invisible and sometimes ignored component of the building. It is increasingly evident, however, that attention to good foundation design and construction has significant benefits to the homeowner and the builder, and can avoid some serious future problems. Good foundation design and construction practice means not only insulating to save energy, but also providing effective structural design as well as moisture, termite, and radon control techniques where appropriate.

The purpose of this handbook is to provide information that will enable designers, builders, and homeowners to understand foundation design problems and solutions. This chapter provides the general background and introduction to foundation design issues. Section 1.1 explains the practical and economic advantages of good foundation design. The organization and

Figure 1-1: The impact of basement insulation is monitored on several modules at the foundation test facility at the University of Minnesota.

scope of this handbook is described in section 1.2. Before proceeding with solving design and problems, there must be a basic decision about the type of foundation to be used—basement, crawl space, or slab-on-grade. Section 1.3 discusses the considerations that affect choosing a foundation type. While many aspects of foundation design and construction are known to some extent, there is one major concern that is relatively new—controlling radon. Because radon represents a potentially major health hazard, and knowledge about techniques to control it are just emerging, a special introduction to radon appears in section 1.4. This chapter is intended to set the stage for the more detailed information found in chapters 2 through 5.


CREATION OF MORE COMFORTABLE ABOVE-GRADE SPACES
REDUCTION IN HOMEOWNER'S UTILITY BILLS
CREATION OF MORE USABLE, COMFORTABLE BELOW-GRADE SPACES
AVOIDANCE OF COSTLY MOISTURE, TERMITE, AND STRUCTURAL PROBLEMS
AVOIDANCE OF HEALTH-RELATED EFFECTS OF SOIL GAS

Figure 1-2: Benefits of Foundation Insulation and Other Design Improvements

1.1 Benefits of Effective Foundation Design

The practical and economic advantages of following the recommended practices in this handbook are:

- Homeowners' utility bills are reduced.
- Potentially costly future moisture, termite, and even structural problems can be avoided.
- Potentially serious health-related effects of soil gas can be avoided.
- More comfortable above-grade space is created.
- For houses with basements, truly comfortable conditions in below-grade space are created.

All these potential advantages are selling points and can help builders avoid costly callbacks.

The Benefits of Foundation Insulation

The primary reason behind the current interest in foundation design and construction is related to energy conservation, although in some areas radon control is also a primary concern. Today's prospective home buyers are increasingly demanding healthy, energy-efficient homes that will provide the most comfort for their families at a reasonable price. In the past, the initial cost and the monthly mortgage payment were the critical criteria considered. Now, with rising energy costs, operating expenses are also a prime consideration and exert a major influence upon the more educated home buyer’s decision. Home buyers want a home they can not only afford to buy—they want one they can also afford to live in.

Home builders and code officials have



Figure 1-3: The impact of slab-on-grade foundation insulation is monitored in a test facility at Oak Ridge National Laboratory.

initially responded to these desires by providing more thermal insulation in the above-grade portions of the home. Attention to the foundation has lagged for the most part, with most effort focused primarily on a foundation's structural adequacy. Lately however, the general awareness of health-oriented, energy-efficient foundation construction practices has increased in the United States. In 1989-90 several national building energy codes and standards were revised to recommend foundation insulation in moderate to cold U.S. climates (those with over 2500 heating degree days). Uninsulated foundations no longer represent 10 to 15 percent of a poorly insulated building's total heat loss; instead, an uninsulated, conditioned basement may represent up to 50 percent of the heat loss in a tightly sealed house that is well insulated above grade.

In order to develop a better understanding of the impact of foundation insulation and provide information to the building industry and the public, several research activities are proceeding. Two notable projects are the foundation test facilities located at the University of Minnesota (Figure 1-1), and at Oak Ridge National Laboratory (Figure 1-3).

Other Foundation Design Issues

While saving energy may be the primary reason for understanding good foundation design practices, there are other related benefits. For example, insulating any type of foundation is likely to result in warmer floors during winter in above-grade spaces, thus improving comfort as well as reducing energy use. Insulating basement foundations creates more comfortable conditions in below-grade space as well, making it more usable for a variety of purposes at a relatively low cost. Raising basement temperatures by using insulation can also reduce condensation, thus minimizing problems with mold and mildew.

In addition to energy conservation and thermal comfort, good foundation design must be structurally sound, prevent water and moisture problems, and control termites and radon where appropriate. The


DETERMINE FOUNDATION TYPE:
- BASEMENT
- CRAWL SPACE
- SLAB-ON-GRADE
DETERMINE USE OF BASEMENT:
- HEATED / COOLED
- UNCONDITIONED
DETERMINE CONSTRUCTION SYSTEM:
- CONCRETE
- MASONRY
- WOOD
DETERMINE INSULATION PLACEMENT:
- INTERIOR / EXTERIOR
- VERTICAL / HORIZONTAL
- WITHIN STRUCTURE (WOOD JOISTS OR STUDS)
DETERMINE AMOUNT OF INSULATION
DEVELOP CONSTRUCTION DETAILS:
- INSULATION / THERMAL
- STRUCTURAL
- DRAINAGE AND WATERPROOFING
- TERMITE CONTROL
- RADON CONTROL
FINALIZE CONSTRUCTION DOCUMENTS AND ESTABLISH QUALITY CONTROL INSPECTION PROCEDURES

Figure 1-4: Decision-Making Process for Foundation Design

importance of these issues increases with an energy-efficient design because there are some potential problems caused by incorrect insulating practices. Under certain circumstances the structural integrity of a foundation can be negatively affected by insulation when water control is not adequate. Without properly installing vapor barriers and adequate air sealing, moisture can degrade foundation insulation and other moisture problems can actually be created. Improperly installed foundation insulation may also provide entry paths for termites. Insulating and sealing a foundation to save energy results in a tighter building with less infiltration. If radon is present, it can accumulate and reach higher levels in the building than if greater outside air exchange was occurring. All of these potential side effects can be avoided if recommended practices are followed.

1.2 Organization and Scope of the Handbook

Residential foundations can be constructed which reduce energy consumption without creating health, moisture, radon, structural, or other foundation-related problems. The two basic purposes of this handbook are (1) to provide simplified methods for estimating the site-specific energy savings and cost-effectiveness of foundation insulation measures, and (2) to provide information and construction details concerning thermal protection, subdrainage, waterproofing, structural requirements, radon control, and termite damage prevention.

Handbook Organization

The book is organized in a manner that reflects the decision-making process used by a designer, builder, or homeowner dealing with foundation design questions (see Figure 1-4). First, one must determine the foundation type and construction to be used. Then, if it is a basement foundation, it must be decided whether the below grade space be heated and / or cooled. These decisions are determined by regional, local, and site-specific factors as well as individual or market preference. Considerations related to choosing a foundation type are discussed later in chapter 1. The first chapter also includes introductory information on some general concerns that pertain to all foundation types.

After selecting a foundation type, proceed to the corresponding chapter: chapter 2 for basements, chapter 3 for crawl spaces, and chapter 4 for slab-on-grade foundations. Each of these chapters is organized into four parts. The first section of each chapter helps you select a cost-effective insulation placement and amount for a particular climate. The second section summarizes general principles of structural design, drainage and waterproofing, as well as radon and termite control techniques. This is followed by a series of alternative construction details illustrating the integration of the major concerns involved in foundation design. These construction details can be adapted to fit a unique site or building condition. Within each construction drawing are labels that contain numbers within boxes that refer to notes listed at the end of this section. Finally, the last section in chapters 2, 3, and 4 is a checklist to be used during design and construction.

Chapter 5 provides an alternative method for determining the cost-effectiveness of foundation insulation. In the first section of chapters 2, 3, and 4, insulation levels are recommended for each foundation type using a 30-year minimum life cycle cost analysis for several climatic regions in the United States. These are based on average construction costs and representative energy prices for natural gas and electricity. While these tables of recommendations are easy to use and provide good general guidelines, they cannot easily be adapted to reflect other costs and conditions. Therefore, if the assumptions underlying the recommended insulation levels in chapters 2, 3, and 4 do not correspond to local conditions, it is strongly recommended that the user fill out the worksheet provided in chapter 5. This worksheet helps select the optimal level of foundation insulation for site-specific new or retrofit construction. Local energy prices and construction costs can be used in the calculation, and economic decision criteria can be chosen such as 20-year minimum life cycle cost (suggested for retrofit) or 30-year minimum life cycle cost (suggested for new construction).

Scope of the Handbook

The information presented in this handbook pertains mostly to new residential construction and small commercial buildings. The handbook covers all three basic foundation types — basement, crawl space, and slab-on-grade. Conventional foundation systems of cast-in-place concrete or concrete block masonry are emphasized, although pressure-preservative-treated wood foundations are also addressed.

The intention of this book is to provide the tools to help people make decisions about foundation design. Often information exists related to a particular building material or product, but this book is one of the few resources that attempts to address the overall integration of a number of systems. While this book does not provide exact construction documents, specifications, and procedures, it provides the basic framework and fundamental information needed to create these documents.

Relation to the Previous Handbook

The information in this handbook is drawn mainly from the *Building Foundation Design Handbook* (Labs et al., 1988), a more extensive technical reference manual on foundation design. The original handbook was intended for architects and engineers, while this handbook is intended to serve builders. The first book explained not only what to do in foundation design but also much of the technical rationale behind the recommendations. This book presents what to do in foundation design in a more concise format, and includes a few additions and improvements to the original handbook. While the intended audience for this book is clearly home builders, the information is pertinent to anyone involved in foundation design and construction decisions including homeowners as well as architects and engineers looking for information in a more concise and updated form.

While this handbook does not include the technical reference information of the original book, notable additions to this version are: (1) the worksheet in chapter 5 which permits energy use calculations based on individual parameters, (2) simplified tables of recommended insulation levels in chapters 2, 3, and 4, (3) distinct insulation recommendations for several subcategories of insulation placement (i.e., interior, exterior, ceiling, and within wall insulation for basements), (4) construction practice notes linked to the drawings, and (5) drawings that have been revised or replaced. In spite of these improvements, the original *Building Foundation Design Handbook* represents a valuable resource for detailed technical information not found in this book.

1.3 Foundation Type and Construction System

The three basic types of foundations—full basement, crawl space, and slab-on-grade—are shown in Figure 1-5. Of course, actual houses may include combinations of these types. Information on a fourth type of foundation—the shallow or half-bermed basement—can be found in the *Building Foundation Design Handbook* (Labs et al. 1988).

There are several construction systems from which to choose for each foundation type. The most common systems, cast-in-place concrete and concrete block foundation walls, can be used for all four basic foundation types. Other systems include pressure-preservative-treated wood foundations, precast concrete foundation walls, masonry or concrete piers, cast-in-place concrete sandwich panels, and various masonry systems. A slab-on-grade construction with an integral concrete grade beam at the slab edge is common in climates with a shallow frost depth. In colder climates, deeper cast-in-place concrete walls and concrete block walls are more common, although a shallower footing can sometimes be used depending on soil type, groundwater conditions, and insulation placement.

Most of the foundation types and construction systems described above can be designed to meet necessary structural, thermal, radon, termite and moisture or water control requirements. Factors affecting the choice of foundation type and construction system include site conditions, overall building design, the climate, and local market preferences as well as construction costs. These factors are discussed below.

Site Conditions

The topography, water table location, presence of radon, soil type, and depth of bedrock can all affect the choice of a foundation type. Any foundation type can be used on a flat site; however, a sloping site often necessitates the use of a walkout basement or crawl space. On steeper slopes, a walkout basement combines a basement foundation wall on the uphill side, a slab-on-grade foundation on the downhill side, and partially bermed foundation walls on the remaining two sides.

A water table depth within 8 feet of the surface will likely make a basement foundation undesirable. Lowering the water table with drainage and pumping usually cannot be justified, and waterproofing may not be feasible or may be too costly. A water table near the surface generally restricts the design to a slab-on-grade or crawl space foundation.

The presence of expansive clay soils on a site requires special techniques to avoid foundation movement and significant structural damage. Often, buildings placed on sites with expansive clay require pile foundations extending down to stable soil strata or bedrock. Similarly, sites with bedrock near the surface require special foundation techniques. Expensive bedrock excavation is not required to reach frost depth nor is it economically justifiable to create basement space. In these unusual conditions of expansive clay soils or bedrock near the surface, special variations of the typical foundation types may be appropriate.

Overall Building Design

The foundation type and construction system are chosen in part because of appearance factors. Although it is not usually a major aesthetic element, the foundation at the base of a building can be raised above the ground plane, so the foundation wall materials can affect the overall appearance. A building with a slab-on-grade foundation has little visible foundation; however, the foundation wall of a crawl space or basement can vary considerably from almost no exposure to full exposure above grade.

Climate

The preference of foundation type varies with climatic region, although examples of most types can generally be found in any given region. One of the principal factors behind foundation preference is the impact of frost depth on foundation design. The impact of frost depth basically arises from the need to place foundations at greater depths in colder climates. For example, a footing in Minnesota must be at least 42 inches below the surface, while in states along the Gulf Coast, footings need not extend below the surface at all in order to avoid structural damage from frost heave. Because a foundation wall extending to a substantial depth is required in northern climates, the incremental cost of creating basement space is much less, since it is necessary to build approximately half the basement wall anyway. In a southern climate the incremental first cost of creating a basement is greater when compared with a slab-on-grade with no significant required footing depth.

This historic perception that foundations must extend below the natural frost depth is not entirely accurate. Buildings with very shallow foundations can be used in cold climates if they are insulated properly.

Local Market Preferences and Construction Costs

The foundation type and construction system are also chosen based on cost and market factors that vary regionally or even locally. Virtually any foundation type and construction system can be built in any location in the United States. The relative costs, however, are likely to differ. These costs reflect local material and labor costs as well as the availability of certain materials and the preferences of local contractors. For example, in certain regions there are many contractors specializing in cast-in-place concrete foundation walls. Because they have the concrete forms and the required experience with this system and because bidding is very competitive, this system may be more cost-effective compared with other alternatives. In other regions, the availability of concrete blocks is greater and there are many contractors specializing in masonry foundation walls. In these areas, a cast-in-place concrete system may be less competitive economically because fewer contractors are available.

More subjective factors that influence a designer's choice of foundation type and construction system are the expectations and preferences of individual clients and the home-buying public. These market influences are based not only on cost but also on the area's tradition. If people in a certain region expect basements, then builders generally provide them. Of course, analyzing the cost-effectiveness of providing a basement requires a somewhat subjective judgment concerning the value of basement space. These more subjective market factors and regional preferences tend to increase the availability of materials and contractors for the preferred systems, which in turn makes these systems more cost-effective choices.



A: DEEP BASEMENT



B: CRAWL SPACE



C: SLAB-ON-GRADE

Figure 1-5: Basic Foundation Types

1.4 Radon Mitigation Techniques

In this introductory chapter radon is addressed because it is a relatively new concern and one in which techniques to deal with it are just emerging.

Radon is a colorless, odorless, tasteless gas found in soils and underground water. An element with an atomic weight of 222, radon is produced in the natural decay of radium, and exists at varying levels throughout the United States. Radon is emitted from the ground to the outdoor air, where it is diluted to an insignificant level by the atmosphere. Because radon is a gas, it can travel through the soil and into a building through cracks, joints, and other openings in the foundation floor and wall. Earth-based building materials such as cast concrete, concrete masonry, brick, and adobe ordinarily are not significant sources of indoor radon. Radon from well water sometimes contributes in a minor way to radon levels in indoor air. In a few cases, radon from well water has contributed significantly to elevated radon levels.

Health Risk of Radon Exposure

Radon is potentially harmful only if it is in the lungs when it decays into other isotopes (called *radon progeny* or *radon daughters*), and when these further decay. The decay process releases small amounts of ionizing radiation; this radiation is held responsible for the above-normal incidence of lung cancer found among miners. Most of what is known about the risk of radon exposure is based on statistical analysis of lung cancers in humans (specifically, underground miners) associated with exposure to radon. This information is well documented internationally, although much less is known about the risk of long-term


CRACKS IN WALLS
GAPS IN SUSPENDED FLOORS
GAPS AROUND SERVICE PIPES
CAVITIES IN MASONRY WALLS
CONSTRUCTION JOINT AT SLAB EDGE
CRACKS IN BELOW-GRADE WALLS
CRACKS IN FLOOR SLABS

Figure 1-6: Points of Radon Entry into Buildings

exposure to low concentrations of radon in buildings.

The lung cancer hazard due to radon is a function of the number of radioactive decay events that occur in the lungs. This is related to both intensity and duration of exposure to radon gas and decay products plus the equilibrium ratio. Exposure to a low level of radon over a period of many years in one building can present the same health hazard as exposure to a higher level of radon for a shorter period of time in another building. The sum of all exposures over the course of one's life determines the overall risk to that individual.

Strategies to Control Radon

As a national policy, the public has been urged by the Environmental Protection Agency to consider 4 pCi/L (from long-term radon tests) as an “action level” for both new and existing buildings (EPA 1987). The ASHRAE Standard 62-1989, *Ventilation for Acceptable Indoor Air Quality*, has also recognized this value as a guideline (ASHRAE 1989).

In order to address the radon problem, it is necessary to find out to what degree it is present on the site. Then, depending on the level of concern, various techniques to control radon levels can be applied. Generally there are three approaches: (1) the barrier approach, (2) soil gas interception, and (3) indoor air management. The barrier approach refers to a set of techniques for constructing a tight building foundation in order to prevent soil gas from entering. Since the barrier approach differs for each foundation type, these techniques are described in chapters 2, 3, and 4 as they apply to basements, crawl spaces, and slab-on-grade foundations. Intercepting soil gas refers to using vent pipes and fans to draw soil gas from a gravel layer beneath the foundation floor slab. Since this approach can be utilized for basements and slab-on-grade foundations, it is described in detail in chapters 2 and 4. The third general approach—managing indoor air—applies to all foundation types and is described below.

Managing Indoor Air

Air management techniques may be used to minimize the suction applied to the surrounding soil gas by the building. To control the pressure differential across the envelope, it is desirable to make the entire building envelope airtight and control the amount of incoming fresh air, exhausted inside air, and supply air for combustion devices. A passive house with no mechanical fans operating at any given condition has a neutral pressure plane where no pressure differential exists across the building envelope. Envelope cracks above this plane exfiltrate and openings below infiltrate.

The principles applied to minimize pressure differences across the building foundation envelope are essentially the same as those recommended for moisture vapor control and energy-efficient design. These include the following:

1. Reduce air infiltration from the unconditioned spaces (crawl spaces, attics, and unconditioned basements) into the occupied space by sealing openings and cracks between the two, including flues, vent stacks, attic hatchways, plumbing, wiring, and duct openings.

2. Consider locating the attic access outside conditioned space (for example, an attached garage).

3. Seal all openings in top and bottom plates of frame construction, including interior partitions.

4. Provide separate outdoor air intakes for combustion equipment.

5. Install an air barrier in all above-grade exterior walls.

6. Adjust ventilation systems to help neutralize imbalances between indoor and outdoor air pressures. Keeping a house under continuous slight positive pressure is a difficult technique to accomplish. At this time whole house, basement, or crawl space pressurization does not appear to be a viable solution to radon control.

7. Do not locate return air ducts in a crawl space or beneath a slab. Placing the HVAC ducting inside the conditioned space will save energy as well.

8. Do not locate supply ducts below concrete slabs on or below grade.

9. Seal all return ductwork located in crawl spaces.

10. Balance the HVAC ducts. System imbalance can lead to pressurization in some zones and depressurization in others.

CHAPTER 2

Basement Construction



Figure 2-1: Concrete Masonry Basement Wall with Exterior Insulation

This chapter summarizes suggested practices related to basements. Section 2.1 presents recommended optimal levels of insulation. Recommendations are given for two distinct basement conditions: (1) a fully conditioned (heated and cooled) deep basement, and (2) an unconditioned deep basement.

Section 2.2 contains a brief summary of basement design practices and covers structural design, location of insulation, drainage and waterproofing, termite and wood decay control, and radon control. Section 2.3 includes a series of alternative construction details with accompanying notes indicating specific practices. Section 2.4 is a checklist to be used during the design, construction, and site inspection of a basement.

2.1 Basement Insulation Placement and Thickness

The term deep basement refers to a 7- to 10-foot basement wall with no more than the upper 25 percent exposed above grade. Fully conditioned means that the basement is heated and cooled to set thermostat levels similar to typical above-grade spaces: at least 70°F during the heating season, and no higher than 78°F during the cooling season.

The unconditioned deep basement is identical to the conditioned deep basement described previously except that the space is not directly heated or cooled to maintain a temperature in the 70°F to 78°F range. Instead, it is assumed that the basement temperature fluctuates during the year based on heat transfer between the basement and various other heat sources and sinks including (1) the above-grade space, (2) the surrounding soil, and (3) the furnace and ducts within the basement. Generally, the temperature of the unconditioned space ranges between 55°F and 70°F most of the year in most climates.

Insulation Configurations

Tables 2-1 and 2-2 include illustrations and descriptions of a variety of basement insulation configurations. Two basic construction systems are shown—a concrete (or masonry) basement wall and a pressure-preservative-treated wood basement wall.

For conditioned basements, shown in Table 2-1, there are three general approaches to insulating the concrete / masonry wall: (1) on the exterior covering the upper half of the wall, (2) on the exterior covering the entire wall, and (3) on the interior covering the entire wall. With pressure-preservative-treated wood construction, mineral wool batt insulation is placed in the cavities between the wood studs.

Table 2-2, which addresses unconditioned basements, includes the same set of configurations used in Table 2-1 as well as three additional cases where insulation is placed between the floor joists in the ceiling above the unconditioned basement. This approach thermally separates the basement from the above-grade space, resulting in lower basement temperatures in winter and usually necessitating insulation of exposed ducts and pipes in the basement. Basement ceiling insulation can be applied with either construction system — concrete / masonry or wood basement walls — but is most commonly used with concrete / masonry foundations.

Recommended Insulation Levels

While increasing the amount of basement insulation produces greater energy savings, the cost of installation must be compared to these savings. Such a comparison can be done in several ways; however, a life cycle cost analysis presented in worksheet form in chapter 5 is recommended. It takes into account a number of economic variables including installation costs, mortgage rates, HVAC efficiencies, and fuel escalation rates. In order to identify the most economical amount of insulation for the basement configurations shown in Tables 2-1 and 2-2, the case with the lowest 30-year life cycle cost was determined for five U.S. cities at three different fuel cost levels. See the *Building Foundation Design Handbook* (Labs et al. 1988) to find recommendations for a greater number of cities and for a detailed explanation of the methodology. The economic methodology used to determine the insulation levels in Tables 2-1 and 2-2 is consistent with ASHRAE standard 90.2P. The simple payback averages 13 years for all U.S. climate zones, and never exceeds 18 years for any of the recommended levels.

Economically optimal configurations are shown by the darkened circles in Tables 2-1 and 2-2 in the following categories: (1) concrete / masonry wall with exterior insulation, (2) concrete / masonry wall with interior insulation without including the cost for interior finish material, (3) concrete / masonry wall with interior insulation which includes the cost for sheetrock, (4) pressure-preservative-treated wood wall insulation, and (5) ceiling insulation (shown only in Table 2-2). Configurations are recommended for a range of climates and fuel prices in each of these categories, but the different categories of cases are not directly compared with each other. In other words, there is an optimal amount of exterior insulation recommended for a given climate and fuel price, and there is a different optimal amount of insulation for interior insulation with sheetrock. Where there is no darkened circle in a particular category, insulation is not economically justified under the assumptions used.

Fully Conditioned Basements

For fully conditioned basements with concrete / masonry walls, exterior insulation is justified at three fuel price levels (shown in Table 2-3) in all climate zones except the warmest one, which includes cities such as Los Angeles and Miami. In most locations R-10 insulation or greater covering the entire wall on the exterior is justified with a fully conditioned basement. For interior insulation even higher levels of insulation are generally recommended ranging from R-11 to R-19 in most cases. Whether or not sheetrock is included in the cost of installation appears to have relatively little impact on the recommendations. For pressure-preservative-treated wood walls, R-19 insulation is justified in almost all

Table 2-1: Insulation Recommendations for Fully Conditioned Deep Basements

A: Concrete or Masonry Foundation Walls with Exterior Insulation

CONFIGURATION	DESCRIPTION	RECOMMENDED CONFIGURATIONS AT THREE FUEL PRICE LEVELS														
		0-2000 HDD (LOS ANG)			2-4000 HDD (FT WORTH)			4-6000 HDD (KAN CITY)			6-8000 HDD (CHICAGO)			8-10000 HDD (MPLS)		
		L	M	H	L	M	H	L	M	H	L	M	H	L	M	H
EXTERIOR: HALF WALL 	NO INSULATION	●	●	○	○	○	○	○	○	○	○	○	○	○	○	○
	4 FT: R-5 RIGID	○	○	●	●	○	○	○	○	○	○	○	○	○	○	○
	4 FT: R-10 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
EXTERIOR: FULL WALL 	8 FT: R-5 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	8 FT: R-10 RIGID	○	○	○	○	●	●	●	●	○	●	●	○	●	○	○
	8 FT: R-15 RIGID	○	○	○	○	○	○	○	○	●	○	○	●	○	●	●
	8 FT: R-20 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○

B: Concrete or Masonry Foundation Walls with Interior Insulation (Costs do not include interior finish material)

INTERIOR: FULL WALL 	NO INSULATION	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	8 FT: R-6 RIGID	●	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	8 FT: R-8 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	8 FT: R-11 BATT	○	●	●	●	●	●	●	○	○	●	○	○	○	○	○
	8 FT: R-19 BATT	○	○	○	○	○	○	○	●	●	○	●	●	●	●	●

C: Concrete or Masonry Foundation Walls with Interior Insulation (Costs include sheetrock on interior wall)

INTERIOR: FULL WALL 	NO INSULATION	●	●	○	○	○	○	○	○	○	○	○	○	○	○	○
	8 FT: R-6 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	8 FT: R-8 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	8 FT: R-11 BATT	○	○	●	●	●	●	●	●	○	●	○	○	●	○	○
	8 FT: R-19 BATT	○	○	○	○	○	○	○	○	●	○	●	●	○	●	●

D: Pressure-Treated Wood Foundation Walls

WOOD: FULL WALL 	NO INSULATION	●	●	○	○	○	○	○	○	○	○	○	○	○	○	○
	8 FT: R-11 BATT	○	○	●	●	○	○	○	○	○	○	○	○	○	○	○
	8 FT: R-19 BATT	○	○	○	○	●	●	●	●	●	●	●	●	●	●	●
	8 FT: R-30 BATT	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○

1. L, H, and M refer to the low, medium, and high fuel cost levels indicated in Table 2-3.
2. The darkened circle represents the recommended level of insulation in each column for each of the four basic insulation configurations.
3. These recommendations are based on assumptions that are summarized at the end of section 2.1 and further explained in chapter 5.

Table 2-2: Insulation Recommendations for Unconditioned Deep Basements

A: Concrete or Masonry Foundation Walls with Exterior Insulation

CONFIGURATION	DESCRIPTION	RECOMMENDED CONFIGURATIONS AT THREE FUEL PRICE LEVELS														
		0-2000 HDD (LOS ANG)			2-4000 HDD (FT WORTH)			4-6000 HDD (KAN CITY)			6-8000 HDD (CHICAGO)			8-10000 HDD (MPLS)		
		L	M	H	L	M	H	L	M	H	L	M	H	L	M	H
EXTERIOR: HALF WALL 	NO INSULATION	●	●	●	●	●	●	●	●	○	●	○	○	○	○	○
	4 FT: R-5 RIGID	○	○	○	○	○	○	○	○	●	○	●	●	●	●	○
	4 FT: R-10 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
EXTERIOR: FULL WALL 	8 FT: R-5 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	8 FT: R-10 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	●
	8 FT: R-15 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	8 FT: R-20 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○

B: Concrete or Masonry Foundation Walls with Interior Insulation (Costs do not include interior finish material)

INTERIOR: FULL WALL 	NO INSULATION	●	●	●	●	●	●	●	○	○	○	○	○	○	○	○
	8 FT: R-6 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	8 FT: R-8 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	8 FT: R-11 BATT	○	○	○	○	○	○	○	●	●	●	●	●	●	●	●
	8 FT: R-19 BATT	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○

C: Concrete or Masonry Foundation Walls with Interior Insulation (Costs include sheetrock on interior wall)

INTERIOR: FULL WALL 	NO INSULATION	●	●	●	●	●	●	●	●	●	●	●	○	●	○	○
	8 FT: R-6 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	8 FT: R-8 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	8 FT: R-11 BATT	○	○	○	○	○	○	○	○	○	○	○	●	○	●	●
	8 FT: R-19 BATT	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○

D: Pressure-Treated Wood Foundation Walls

WOOD: FULL WALL 	NO INSULATION	●	●	●	●	●	●	●	○	○	○	○	○	○	○	○
	8 FT: R-11 BATT	○	○	○	○	○	○	○	●	●	●	●	●	●	○	○
	8 FT: R-19 BATT	○	○	○	○	○	○	○	○	○	○	○	○	○	●	●
	8 FT: R-30 BATT	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○

E: Concrete or Masonry Foundation Walls with Ceiling Insulation

CEILING 	NO INSULATION	●	●	●	●	●	●	○	○	○	○	○	○	○	○	○
	R-11 BATT	○	○	○	○	○	○	●	●	○	○	○	○	○	○	○
	R-19 BATT	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	R-30 BATT	○	○	○	○	○	○	○	○	●	●	●	●	●	●	●

1. L, H, and M refer to the low, medium, and high fuel cost levels indicated in Table 2-3.
2. The darkened circle represents the recommended level of insulation in each column for each of the four basic insulation configurations.
3. These recommendations are based on assumptions that are summarized at the end of section 2.1 and further explained in chapter 5.

Table 2-3: Fuel Price Levels Used to Develop Recommended Insulation Levels in Tables 2-1 and 2-2

SEASON	FUEL TYPE	LOW PRICE LEVEL ($)	MEDIUM PRICE LEVEL ($)	HIGH PRICE LEVEL ($)
HEATING	NATURAL GAS	.374 / THERM	.561 / THERM	.842 / THERM
	FUEL OIL	.527 / GALLON	.791 / GALLON	1.187 / GALLON
	PROPANE	.344 / GALLON	.516 / GALLON	.775 / GALLON
COOLING	ELECTRICITY	.051 / KWH	.076 / KWH	.114 / KWH

locations at all fuel price levels. This is due to the low initial cost of installing insulation within the available stud cavity of the wood foundation.

Unconditioned Basements

Compared with recommended insulation levels for fully conditioned basements, lower levels are economically justified in unconditioned basements in most locations due to generally lower basement temperatures. For concrete / masonry walls with exterior insulation, R-5 insulation on the upper wall is justified only in the colder climates at low (L) and medium (M) fuel prices. At the high fuel price level (H), R-5 insulation on the upper wall is justified in moderate climates, while R-10 insulation on the entire wall is recommended in the coldest cities. For interior insulation without sheetrock, R-11 is recommended in moderate to cold climates at all fuel price levels. Including the cost of sheetrock, however, reduces the number of cases where interior insulation is economically justified. For basements with pressure-preservative-treated wood walls, R-11 to R-19 insulation is justified in moderate to cold climates. When ceiling insulation is placed over an unconditioned basement, R-30 insulation is justified in colder cities and some insulation is justified in most cities.

Comparison of Insulation Systems

Generally, insulating pressure-preservative-treated wood walls is more cost-effective than insulating concrete / masonry walls to an equivalent level. This is because the cavity exists between studs in a wood wall system and the incremental cost of installing batt insulation in these cavities is relatively low. Thus, a higher R-value is economically justified for wood wall systems.

On concrete / masonry basement walls, interior insulation is generally more cost-effective than an equivalent amount of exterior insulation. This is because the labor and material costs for rigid insulation with protective covering required for an exterior installation typically exceed the cost of interior insulation. Even though the cost of studs and sheetrock may be included in an interior installation, the incremental cost of batt installation is relatively little. If rigid insulation is used in an interior application, the installation cost is less than placing it on the exterior. Because it does not have to withstand exposure to water and soil pressure below grade as it does on the exterior, a less expensive material can be used. Costs are further reduced since interior insulation does not require a protective flashing or coating to prevent degradation from ultraviolet light as well as mechanical deterioration.

Insulating the ceiling of an unconditioned basement is generally more cost-effective than insulating the walls of an unconditioned basement to an equivalent level. This is because placing batt insulation into the existing spaces between floor joists represents a much smaller incremental cost than placing insulation on the walls. Thus higher levels of ceiling insulation can be economically justified when compared to wall insulation.

In spite of the apparent energy efficiency of wood versus concrete / masonry basement walls, this is only one of many cost and performance issues to be considered. Likewise, on a concrete / masonry foundation wall, the economic benefit of interior versus exterior insulation may be offset by other practical, performance, and aesthetic considerations discussed elsewhere in this book. Although ceiling insulation in an unconditioned basement appears more cost-effective than wall insulation, this approach may be undesirable in colder climates since pipes and ducts may be exposed to freezing temperatures and the space will be unusable for many purposes. In all cases the choice of foundation type and insulation system must be based on many factors in addition to energy cost-effectiveness.

Assumptions

These general recommendations are based on a set of underlying assumptions. Fuel price assumptions used in this analysis are shown in Table 2-3. The total heating system efficiency is 68 percent and the cooling system SEER is 9.2 with 10 percent duct losses. Energy price inflation and mortgage conditions are selected to allow maximum simple payback of 18 years with average paybacks of about 13 years.

The total installed costs for all insulation systems considered in this analysis are shown in Table 5-2 in chapter 5. Installation costs used in this analysis are based on average U.S. costs in 1987. For the exterior cases, costs include labor and materials for extruded polystyrene insulation and the required protective covering and flashing above grade. For the interior cases, costs include labor and materials for expanded polystyrene (R-6 and R-8) and wood framing with fiberglass batts (R-11 and R-19). The installed costs and R-values for all interior cases are shown with and without interior finish material. All costs include a 30 percent builder markup and a 30 percent subcontractor markup for overhead and profit.

With pressure-preservative-treated wood construction, batt insulation is placed in the cavities between the wood studs. Costs used in the analysis reflect only the additional cost of installing the insulation, not the interior finish which might be used with or without insulation. A higher cost increment is used when R-30 insulation is placed in a wood wall reflecting the additional depth required in the studs.

If the general assumptions used in this analysis are satisfactory for the specific project, the reader can determine the approximate recommended insulation level for a location by finding the heating degree days from Table 5-1 in chapter 5 and selecting the appropriate climate zone and fuel price level shown in Tables 2-1 and 2-2. If not, project-specific optimal insulation levels can be determined using actual estimated construction costs with the worksheet provided in chapter 5. The worksheet enables the user to select economic criteria other than allowing maximum simple paybacks of 18 years. In addition the user can incorporate local energy prices, actual insulation costs, HVAC efficiencies, mortgage conditions, and fuel escalation rates. Cost-effectiveness can vary considerably, depending on the construction details and cost assumptions.

2.2 Recommended Design and Construction Details

STRUCTURAL DESIGN

The major structural components of a basement are the wall, the footing, and the floor (see Figure 2-2). Basement walls are typically constructed of cast-in-place concrete, concrete masonry units, or pressure-preservative-treated wood. Basement walls must be designed to resist lateral loads from the soil and vertical loads from the structure above. The lateral loads on the wall depend on the height of the fill, the soil type, soil moisture content, and whether the building is located in an area of low or high seismic activity. Some simple guidelines for wall thickness, concrete strength, and reinforcing are given in the construction details that follow. Where simple limits are exceeded, a structural engineer should be consulted.

Concrete spread footings provide support beneath basement concrete and masonry walls and columns. Footings must be designed with adequate size to distribute the load to the soil. Unless founded on bedrock or proven non-frost-susceptible soils, footings must be placed beneath the maximum frost penetration depth or be insulated to prevent frost penetration. A compacted gravel bed serves as the footing under a wood foundation wall when designed in accordance with the National Forest Products Association’s wood foundations design specifications (NFPA 1987).

Concrete slab-on-grade floors are generally designed to have sufficient strength to support floor loads without reinforcing when poured on undisturbed or compacted soil. The use of welded wire fabric and concrete with a low water/cement ratio can reduce shrinkage cracking, which is an important concern for appearance and for reducing potential radon infiltration.

Where expansive soils are present or in areas of high seismic activity, special foundation construction techniques may be necessary. In these cases, consultation with local building officials and a structural engineer is recommended.


ANCHOR BOLT CONNECTS FOUNDATION WALL TO SUPERSTRUCTURE AND RESISTS WIND UPLIFT
WALL RESISTS VERTICAL LOAD FROM ABOVE-GRADE STRUCTURE
SPREAD FOOTING DISTRIBUTES VERTICAL LOAD TO GROUND
WALL RESISTS LATERAL LOAD FROM SOIL
SLAB SUPPORTS FLOOR LOAD FROM BASEMENT

Figure 2-2: Components of Basement Structural System

DRAINAGE AND WATERPROOFING

Keeping water out of basements is a major concern in many regions. The source of water is primarily from rainfall, snow melt, and sometimes irrigation on the surface. In some cases, the groundwater table is near or above the basement floor level at times during the year. There are three basic lines of defense against water problems in basements: (1) surface drainage, (2) subsurface drainage, and (3) dampproofing or waterproofing on the wall surface (see Figure 2-3).

The goal of surface drainage is to keep water from surface sources away from the foundation by sloping the ground surface and using gutters and downspouts for roof drainage. The goal of subsurface drainage is to intercept, collect, and carry away any water in the ground surrounding the basement. Components of a subsurface system can include porous backfill, drainage mat materials or insulated drainage boards, and perforated drainpipes in a gravel bed along the footing or beneath the slab that drain to a sump or to daylight. Local conditions will determine which of these subsurface drainage system components, if any, are recommended for a particular site.

The final line of defense—waterproofing—is intended to keep out water that finds its way to the wall of the structure. First, it is important to distinguish between the need for dampproofing versus waterproofing. In most cases a dampproof coating covered by a 4-mil layer of polyethylene is recommended to reduce vapor and capillary draw transmission from the soil through the basement wall. A dampproof coating, however, is not effective in preventing water from entering through the wall. Waterproofing is recommended (1) on sites with anticipated water problems or poor drainage, (2) when finished basement space is planned, or (3) on any foundation built where intermittent hydrostatic pressure occurs against the basement wall due to rainfall, irrigation, or snow melt. On sites where the basement floor could be below the water table, a crawl space or slab-on-grade foundation is recommended.


1. SURFACE DRAINAGE
SYSTEM COMPONENTS
- SLOPE GROUND AWAY
- IMPERMEABLE TOPSOIL
- GUTTERS AND DOWNSPOUTS
2. SUBSURFACE DRAINAGE
SYSTEM COMPONENTS
- POROUS BACKFILL OR DRAINAGE MAT
- DRAIN PIPES IN GRAVEL BED ALONG FOOTING
- GRAVEL LAYER UNDER FLOOR SLAB
- PIPES DRAIN TO A SUMP OR DAYLIGHT
3. DAMPPROOFING OR WATERPROOFING SYSTEM COMPONENTS
- MATERIAL APPLIED DIRECTLY TO WALL EXTERIOR
- PROTECTION BOARD OFTEN REQUIRED

Figure 2-3: Components of Basement Drainage and Waterproofing Systems

LOCATION OF INSULATION

A key question in foundation design is whether to place insulation inside or outside the basement wall. In terms of energy use, there is not a significant difference between the same amount of full wall insulation applied to the exterior versus the interior of a concrete or masonry wall. However, the installation costs, ease of application, appearance, and various technical concerns can be quite different. Individual design considerations as well as local costs and practices determine the best approach for each project.

Rigid insulation placed on the exterior surface of a concrete or masonry basement wall has some advantages over interior placement in that it (1) can provide continuous insulation with no thermal bridges, (2) protects and maintains the waterproofing and structural wall at moderate temperatures, (3) minimizes moisture condensation problems, and (4) does not reduce interior basement floor area. Exterior insulation at the rim joist leaves joists and sill plates open to inspection from the interior for termites and decay. On the other hand, exterior insulation on the wall can provide a path for termites if not treated adequately and can prevent inspection of the wall from the exterior.

Interior insulation is an effective alternative to exterior insulation. Interior insulation placement is generally less expensive than exterior placement if the cost of the interior finish materials is not included. However, this does not leave the wall with a finished, durable surface. Energy savings may be reduced with some systems and details due to thermal bridges. For example, partial interior wall insulation is not recommended because of the possible circumventing of the insulation through the wall construction. Insulation can be placed on the inside of the rim joist but with greater risk of condensation problems and less access to wood joists and sills for termite inspection from the interior.

Insulation placement in the basement ceiling of an unconditioned basement is another acceptable alternative. This approach is relatively low in cost and provides significant energy savings. However, ceiling insulation should be used with caution in colder climates where pipes may freeze and structural damage may result from lowering the frost depth.

With a wood foundation system, insulation is placed in the stud cavities similarly to insulation in an above-grade wood frame wall. A 2-inch air space should be provided between the end of the insulation and the bottom plate of the foundation wall. This approach has a relatively low cost and provides sufficient space for considerable insulation thickness.

In addition to more conventional interior or exterior placement covered in this handbook, there are several systems that incorporate insulation into the construction of the concrete or masonry walls. These include (1) rigid foam plastic insulation cast within a concrete wall, (2) polystyrene beads or granular insulation materials poured into the cavities of conventional masonry walls, (3) systems of concrete blocks with insulating foam inserts, (4) formed, interlocking rigid foam units that serve as a permanent, insulating form for cast-in-place concrete, and (5) masonry blocks made with polystyrene beads instead of aggregate in the concrete mixture, resulting in significantly higher R-values. However, the effectiveness of systems that insulate only a portion of the wall area should be evaluated closely because thermal bridges through the insulation can impact the total performance significantly.

TERMITE AND WOOD DECAY CONTROL TECHNIQUES

Techniques for controlling the entry of termites through residential foundations are advisable in much of the United States (see Figure 2-4). The following recommendations apply where termites are a potential problem. Consult with local building officials and codes for further details.

1. Minimize soil moisture around the basement by using gutters, downspouts, and runouts to remove roof water, and by installing a complete subdrainage system around the foundation.

2. Remove all roots, stumps, and scrap wood from the site before, during, and after construction, including wood stakes and formwork from the foundation area.

3. Treat soil with termiticide on all sites vulnerable to termites.

4. Place a bond beam or course of cap blocks on top of all concrete masonry foundation walls to ensure that no open cores are left exposed. Alternatively, fill all cores on the top course with mortar, and reinforce the mortar joint beneath the top course.

5. Place the sill plate at least 8 inches above grade; it should be pressure-preservative treated to resist decay. The sill plate should be visible for inspection from the interior. Since termite shields are often damaged or not installed carefully enough, they are considered optional and should not be regarded as sufficient defense by themselves.

6. Be sure that exterior wood siding and trim is at least 6 inches above grade.

7. Construct porches and exterior slabs so that they slope away from the foundation wall, and are at least 2 inches below exterior siding. In addition, porches and exterior slabs should be separated from all wood members by a 2-inch gap visible for inspection or by a continuous metal flashing soldered at all seams.

8. Fill the joint between the slab floor and foundation wall with urethane caulk or coal tar pitch to form a termite barrier.

9. Use pressure-preservative-treated wood posts on the basement floor slab, or place posts on flashing or a concrete pedestal raised 1 inch above the floor.

10. Flash hollow steel columns at the top to stop termites. Solid steel bearing plates can also serve as a termite shield at the top of a wood post or hollow steel column.

Plastic foam and mineral wool insulation materials have no food value to termites, but they can provide protective cover and easy tunnelling. Insulation installations can be detailed for ease of inspection, although often by sacrificing thermal efficiency. In principle, termite shields offer protection, but should not be relied upon as a barrier.

These concerns over insulation and the unreliability of termite shields have led to the conclusion that soil treatment is the most effective technique to control termites with an insulated foundation. However, the restrictions on widely used termiticides may make this option either unavailable or cause the substitution of products that are more expensive and possibly less effective. This situation should encourage insulation techniques that enhance visual inspection and provide effective barriers to termites.


PRESSURE-PRESERVATIVE TREATED SILL PLATE 8-IN. MIN. ABOVE GRADE
WOOD SIDING 6-IN. MIN. ABOVE GRADE
BOND BEAM, CAP BLOCK, OR FILLED UPPER COURSE OF MASONRY WALL
TREAT SOIL FOR TERMITES
WOOD POSTS SHOULD BE TREATED OR PLACED ON A 1-IN. PEDESTAL
PLACE FLASHING OVER HOLLOW METAL POSTS
REMOVE ROOTS, TRUNKS, AND SCRAP WOOD FROM FOUNDATION AREA
MINIMIZE SOIL MOISTURE
- USE GUTTERS AND DOWNSPOUTS
- INSTALL SUBSURFACE DRAINAGE SYSTEM
FILL JOINT WITH CAULKING

Figure 2-4: Termite Control Techniques for Basements


BOND BEAM, CAP BLOCK, OR FILLED UPPER COURSE OF MASONRY WALL
SEAL AROUND ALL DOORS, DUCTS OR PIPES IN WALLS, FLOORS, OR LEADING TO ADJACENT CRAWL SPACES
USE SOLID DRAINPIPES IN FLOOR WITH MECHANICAL TRAPS
PARGE MASONRY WALL
INSTALL DRAINAGE BOARD TO PROVIDE ESCAPE FOR SOIL GAS
DAMPPROOFING OR WATERPROOFING
SOLID BLOCK OR FILL LOWER COURSE SOLID
POLYURETHANE CAULKING IN JOINT
REINFORCE SLAB AND USE CONCRETE WITH LOW WATER/CEMENT RATIO TO REDUCE CRACKING
REINFORCE WALLS AND FOOTING TO MINIMIZE CRACKING
6-MIL POLY LAYER UNDER SLAB SEALED TO WALL

Figure 2-5: Radon Control Techniques for Basements

RADON CONTROL TECHNIQUES

Construction techniques for minimizing radon infiltration into the basement are appropriate where there is a reasonable probability that radon may be present (see Figure 2-5). To determine this, contact the state health department or environmental protection office. General approaches to minimizing radon include (1) sealing joints, cracks, and penetrations in the foundation, and (2) evacuating soil gas surrounding the basement.

Sealing the Basement Floor

1. Use solid pipes for floor discharge drains to daylight, or mechanical traps that discharge to subsurface drains.

2. Use a 6-mil (minimum) polyethylene film beneath the slab on top of the gravel drainage bed. This film serves as a radon and moisture retarder and also prevents concrete from infiltrating the aggregate base under the slab as it is cast. Slit an “x” in the polyethylene membrane to receive penetrations. Turn up the tabs and tape them. Care should be taken to avoid unintentionally puncturing the barrier; consider using rounded riverbed gravel if possible. The riverbed gravel allows for freer movement of the soil gas and also offers no sharp edges to penetrate the polyethylene. The edges of the film should be lapped at least 12 inches. The polyethylene should extend over the top of the footing, or be sealed to the foundation wall. A 2-inch-thick sand layer on top of the polyethylene improves concrete curing and offers some protection from puncture of the polyethylene during the concrete pouring operation.

3. Tool the joint between the wall and slab floor and seal with polyurethane caulk, which adheres well to concrete and is long-lasting.

4. Avoid perimeter gutters around the slab that provide a direct opening to the soil beneath the slab.

5. Minimize shrinkage cracking by keeping the water content of the concrete as low as possible. If necessary, use plasticizers, not water, to increase workability.

6. Reinforce the slab with wire mesh or fibers to reduce shrinkage cracking, especially near the inside corner of “L” shaped slabs.

7. Where used, finish control joints with a 1/2-inch depression and fully fill this recess with polyurethane or similar caulk.

8. Minimize the number of pours to avoid cold joints. Begin curing the concrete immediately after the pour, according to recommendations of the American Concrete Institute (1980; 1983). At least three days are required at 70^{O}F, and longer at lower temperatures. Use an impervious cover sheet or wetted burlap to facilitate curing. The National Ready Mix Concrete Association suggests a pigmented curing compound should also be used.

9. Form a gap of at least 1/2-inch width around all plumbing and utility lead-ins through the slab to a depth of at least 1/2 inch. Fill with polyurethane or similar caulking.

10. Do not install sumps within basements in radon-prone areas unless absolutely necessary. Where used, cover the sump pit with a sealed lid and vent to the outdoors. Use submersible pumps.

11. Install mechanical traps at all necessary floor drains discharging through the gravel beneath the slab.

12. Place HVAC condensate drains so that they drain to daylight outside of the building envelope. Condensate drains that connect to dry wells or other soil may become direct paths for soil gas, and can be a major entry point for radon.

13. Seal openings around water closets, tub traps, and other plumbing fixtures (consider nonshrinkable grout).

Sealing the Basement Walls

1. Reinforce walls and footings to minimize shrinkage cracking and cracking due to uneven settlement.

2. To retard movement of radon through hollow core masonry walls, the top and bottom courses of hollow masonry walls should be solid block, or filled solid. If the top side of the bottom course is below the level of the slab, the course of block at the intersection of the bottom of the slab should be filled. Where a brick veneer or other masonry ledge is installed, the course immediately below that ledge should also be solid block.

3. Parge and seal the exterior face of below-grade concrete masonry walls in contact with the soil. Install drainage boards to provide an airway for soil gas to reach the surface outside the wall rather than being drawn through the wall.

4. Install a continuous dampproofing or waterproofing membrane on the exterior of the wall. Six-mil polyethylene placed on the exterior of the basement wall surface will retard radon entry through wall cracks.

5. Seal around plumbing and other utility and service penetrations through the wall with polyurethane or similar caulking. Both the exterior and the interior of concrete masonry walls should be sealed at penetrations.

6. Install airtight seals on doors and other openings between a basement and adjoining crawl space.

7. Seal around ducts, plumbing, and other service connections between a basement and a crawl space.

Intercepting Soil Gas

At this time the best strategy for mitigating radon hazard seems to be to reduce stack effects by building a tight foundation in combination with a generally tight above-grade structure, and to make sure a radon collection system and, at the very least, provisions for a discharge system are an integral part of the initial construction. This acts as an insurance policy at modest cost. Once the house is built, if radon levels are excessive, a passive discharge system can be connected and if further mitigation effort is needed, the system can be activated by installing an in-line duct fan (see Figure 2-6).

Subslab depressurization has proven to be an effective technique for reducing radon concentrations to acceptable levels, even in homes with extremely high concentrations (Dudney 1988). This technique lowers the pressure around the foundation envelope, causing the soil gas to be routed into a collection system, avoiding the inside spaces and discharging to the outdoors. This system could be installed in two phases. The first phase is the collection system located on the soil side of the foundation, which should be installed during construction. The collection system, which may consist of nothing more than 4 inches of gravel beneath the slab floor, can be installed at little or no additional cost


ROOF VENT FOR SOIL GAS DISCHARGE
DISCHARGE FAN LOCATED IN ATTIC
RISER PIPES FROM SUMP AND AREA UNDER SLAB
STANDPIPES CAN BE CAPPED FOR FUTURE USE
CONCRETE SLAB OVER POLY VAPOR BARRIER
SEALED SUMP PIT COVER
SUCTION TAP CAST IN SLAB
REINFORCED FOOTING OVER PIPE TRENCH NEAR SUMP
MONOLITHIC CONCRETE OR SOLID PLASTIC SUMP WITH PUMP
PERIMETER DRAINPIPE AT FOOTING DRAINS TO SUMP

Figure 2-6: Soil Gas Collection and Discharge Techniques

in new construction. The second phase is the discharge system, which could be installed later if necessary.

A foundation with good subsurface drainage already has a collection system. The underslab gravel drainage layer can be used to collect soil gas. It should be at least 4 inches thick, and of clean aggregate no less than 1/2 inch in diameter. Weep holes provided through the footing or gravel bed extending beyond the foundation wall will help assure good air communication between the foundation perimeter soil and the underside of the slab. The gravel should be covered with a 6-mil polyethylene radon and moisture retarder, which in turn could be covered with a 2-inch sand bed.

A 3- or 4-inch diameter PVC 12-inch section of pipe should be inserted vertically into the subslab aggregate and capped at the top. Stack pipes could also be installed horizontally through below-grade walls to the area beneath adjoining slabs. A single standpipe is adequate for typical house-size floors with a clean, coarse gravel layer. If necessary, the standpipe can be uncapped and connected to a vent pipe. The standpipe can also be added by drilling a 4-inch hole through the finished slab. The standpipe should be positioned for easy routing to the roof through plumbing chases, interior walls, or closets. Note, however, that it is normally less costly to complete the vent stack routing through the roof during construction than to install or complete the vent stack after the building is finished. Connecting the vent pipe initially without the fan provides a passive depressurization system which may be adequate in some cases and could be designed for easy modification to an active system if necessary.

A subslab depressurization system requires the floor slab to be nearly airtight so that collection efforts are not short-circuited by drawing excessive room air down through the slab and into the system. Cracks, slab penetrations, and control joints must be sealed. Sump hole covers should be designed and installed to be airtight. Floor drains that discharge to the gravel beneath the slab should be avoided, but when used, should be fitted with a mechanical trap capable of providing an airtight seal.

Another potential short circuit can occur if the subdrainage system has a gravity discharge to an underground outfall. This discharge line may need to be provided with a mechanical seal. The subsurface drainage discharge line, if not run into a sealed sump, should be constructed with a solid-glued drainpipe that runs to daylight. The standpipe should be located on the opposite side from this drainage discharge.

It is desirable to avoid dependence on a continuously operating fan. Ideally, a passive depressurization system should be installed, radon levels tested and, if necessary, the system activated by adding a fan. Active systems use quiet, in-line duct fans to draw gas from the soil. The fan should be located in an accessible section of the stack so that any leaks from the positive pressure side of the fan are not in the living space. The fan should be oriented to prevent accumulation of condensed water in the fan housing. The stack should be routed up through the building and extend 2 to 4 feet above the roof. It can also be carried out through the band joist and up along the outside of wall, to a point at or above the eave line. The exhaust should be located away from doors and windows to avoid re-entry of the soil gas into the above-grade space.

A fan capable of maintaining 0.2 inch of water suction under installation conditions is adequate for serving subslab collection systems for most houses (Labs 1988). This is often achieved with a 0.03 hp (25W), 160 cfm centrifugal fan (maximum capacity) capable of drawing up to 1 inch of water before stalling. Under field conditions of 0.2 inch of water, such a fan operates at about 80 cfm.

It is possible to test the suction of the subslab system by drilling a small (1/4-inch) hole in an area of the slab remote from the collector pipe or suction point, and measuring the suction through the hole. A suction of 5 Pascals is considered satisfactory. The hole must be sealed after the test.

Active subslab depressurization does raise some long-term concerns which at this time are not fully understood. If the radon barrier techniques are not fully utilized along with the subslab depressurization, considerable indoor air could be discharged, resulting in a larger than expected energy penalty. System durability is of concern, particularly motor-driven components. This system is susceptible to owner interference.

2.3 Basement Construction Details

In this section several typical basement wall sections are illustrated and described. Figures 2-8 through 2-10 show configurations with insulation on the exterior surface of basement walls. A typical interior placement configuration is shown in Figure 2-11. Figure 2-12 illustrates ceiling insulation over an unconditioned basement. A typical wood foundation wall section is shown in Figure 2-13. Included in this group of details are variations in construction systems, use of insulation under the slab, and approaches to insulating rim joists. Numbers that occur within boxes in each drawing refer to the notes on pages 31 and 32 that follow the drawings (see Figure 2-7).

The challenge is to develop integrated solutions that address all key considerations without unnecessarily complicating construction or increasing the cost. There is no one set of perfect solutions; recommended practices or details often represent compromises and trade-offs. For example, in some regions termite control may be considered more critical than thermal considerations, while the reverse is true elsewhere. No particular approach, such as interior versus exterior insulation, is considered superior in all cases. The purpose of this section is to show and describe a variety of reasonable alternatives. Individual circumstances will dictate final design choices.


RIM JOIST
PROTECTION BOARD OR COATING EXTENDS 6 IN. BELOW GRADE 1
8-IN. MIN.
GROUND SLOPES AWAY FROM WALL AT 5% (6" IN 10 FT) 2
7-IN. MIN.

Figure 2-7: System of Key Numbers in Construction Drawings that Refer to Notes on Following Pages

EXAMPLE OF NOTES CORRESPONDING TO CONSTRUCTION DRAWING:

1. Insulation protection: Exterior insulation materials should not be exposed above grade. They should be covered by a protective material — such as exterior grade plastic, fiberglass, galvanized metal or aluminum flashing, a cementitious coating, or a rigid protection board — extending at least 6 inches below grade.

2. Surface drainage: The ground surface should slope downward at least 5 percent (6 inches) over the first 10 feet surrounding the basement wall to direct surface runoff away from the building. Downspouts and gutters should be used to collect roof drainage and direct it away from the foundation walls.


EXTERIOR SIDING
RIGID INSULATION SHEATHING
BATT INSULATION
VAPOR RETARDER
GYPSUM BOARD
SUBFLOOR
SEALANT, CAULKING OR GASKET (OPTIONAL) 10
RIM JOIST
PRESSURE-TREATED SILL PLATE 11
PROTECTION BOARD OR COATING EXTENDS 6 IN. BELOW GRADE 1
8-IN. MIN.
7-IN. MIN.
GROUND SLOPES AWAY FROM WALL AT 5% (6" IN 10 FT) 2
REINFORCING (OPTIONAL) 12
1/2-IN. ANCHOR BOLTS AT 6 FT. O. C. MAX. 13
LOW PERMEABILITY SOIL (OPTIONAL) 3
CONCRETE FOUNDATION WALL 14
DRAINAGE MAT, INSULATING DRAINAGE BOARD, OR GRANULAR BACKFILL (OPTIONAL) 4
ISOLATION JOINT 15
RIGID INSULATION 5
4-IN. CONCRETE SLAB WITH OPTIONAL W. W. MESH 16
DAMPPROOFING OR WATERPROOFING 6
VAPOR RETARDER 17
FILTER FABRIC ABOVE GRAVEL (OPTIONAL ON SIDES AND BELOW) 7
COARSE GRAVEL
4-IN. PERFORATED DRAIN PIPE WITH HOLES FACING DOWN (OPTIONAL) 8
4-IN. GRAVEL DRAINAGE LAYER (OPTIONAL) 18
THROUGH WALL MOISTURE BARRIER / KEYWAY (OPTIONAL) 19
CONCRETE FOOTING 9
2-IN. DIAMETER WEEP HOLES AT 8 FT. O. C. MAX. (OPTIONAL) 20
REINFORCING (OPTIONAL) 21

Figure 2-8: Concrete Basement Wall with Exterior Insulation

Figure 2-8 illustrates a concrete foundation wall with exterior insulation. The rigid insulation also serves as sheathing over the 2 x 4 wood frame wall above grade. This approach can be used for rigid insulation that is 1.5 inches thick or less.

Figure 2-9 illustrates a concrete foundation wall with exterior insulation. This differs from Figure 2-8 in that the above grade wood frame wall is constructed of 2 x 6's which overhang the foundation wall. The overhang can be up to 2 inches but additional rigid insulation can be added that extends over the entire wall assembly. Another minor difference is that this figure shows a sand layer beneath the floor slab.


EXTERIOR SIDING
SHEATHING
2 x 6 FRAME WALL OVERHANGS RIM JOIST UP TO 2 IN.
BATT INSULATION
VAPOR RETARDER
GYPSUM BOARD
SUBFLOOR
SEALANT, CAULKING OR GASKET (OPTIONAL) 10
RIGID INSULATION 5
RIM JOIST
PRESSURE-TREATED SILL PLATE 11
PROTECTION BOARD OR COATING EXTENDS 6 IN. BELOW GRADE 1
8-IN. MIN.
7-IN. MIN.
GROUND SLOPES AWAY FROM WALL AT 5% (6" IN 10 FT) 2
REINFORCING (OPTIONAL) 12
1/2-IN. ANCHOR BOLTS AT 6 FT. O. C. MAX. 13
LOW PERMEABILITY SOIL (OPTIONAL) 3
CONCRETE FOUNDATION WALL 14
DRAINAGE MAT, INSULATING DRAINAGE BOARD, OR GRANULAR BACKFILL (OPTIONAL) 4
ISOLATION JOINT 15
4-IN. CONCRETE SLAB WITH OPTIONAL W. W. MESH 16
RIGID INSULATION 5
2-IN. SAND LAYER (OPTIONAL) 16
DAMPPROOFING OR WATERPROOFING 6
VAPOR RETARDER 17
FILTER FABRIC ABOVE GRAVEL (OPTIONAL ON SIDES AND BELOW) 7
COARSE GRAVEL
4-IN. GRAVEL DRAINAGE LAYER (OPTIONAL) 18
4-IN. PERFORATED DRAIN PIPE WITH HOLES FACING DOWN (OPTIONAL) 8
THROUGH WALL MOISTURE BARRIER / KEYWAY (OPTIONAL) 19
CONCRETE FOOTING 9
2-IN. DIAMETER WEEP HOLES AT 8 FT. O. C. MAX. (OPTIONAL) 20
REINFORCING (OPTIONAL) 21

Figure 2-9: Concrete Basement Wall with Exterior Insulation


EXTERIOR SIDING
SHEATHING
2 x 4 FRAME WALL
BATT INSULATION
VAPOR RETARDER
GYPSUM BOARD
SUBFLOOR
FLASHING COVERS TOP OF INSULATION
SEALANT, CAULKING OR GASKET (OPTIONAL) 10
RIGID INSULATION 5
PRESSURE-TREATED SILL PLATE 11
RIM JOIST
PROTECTION BOARD OR COATING EXTENDS 6 IN. BELOW GRADE 1
8-IN. MIN.
GROUND SLOPES AWAY FROM WALL AT 5% (6" IN 10 FT) 2
1/2-IN. ANCHOR BOLTS AT 6 FT. O. C. MAX. EMBEDDED 7 TO 15 IN. AS REQUIRED BY CODE 31
FILLED BLOCK CORES OR BOND BEAM 33
CONCRETE MASONRY FOUNDATION WALL 22
LOW PERMEABILITY SOIL (OPTIONAL) 3
DRAINAGE MAT, INSULATING DRAINAGE BOARD, OR GRANULAR BACKFILL (OPTIONAL) 4
ISOLATION JOINT 15
4-IN. CONCRETE SLAB WITH OPTIONAL W. W. MESH 16
RIGID INSULATION 5
DAMPPROOFING OR WATERPROOFING 6
2-IN. SAND LAYER (OPTIONAL) 16
VAPOR RETARDER 17
FILTER FABRIC ABOVE GRAVEL (OPTIONAL ON SIDES AND BELOW) 7
COARSE GRAVEL
RIGID INSULATION (OPTIONAL) 32
4-IN. PERFORATED DRAIN PIPE WITH HOLES FACING DOWN (OPTIONAL) 8
4-IN. GRAVEL DRAINAGE LAYER (OPTIONAL) 18
CONCRETE FOOTING 9
2-IN. DIAMETER WEEP HOLES AT 8 FT. O. C. MAX. (OPTIONAL) 20
REINFORCING (OPTIONAL) 21

Figure 2-10 illustrates a concrete masonry foundation wall with exterior insulation. This differs from Figure 2-8 and 2-9 in that the rigid foundation insulation is covered by a flashing material at the top. There is no limit to the thickness of the foundation insulation. The wood frame wall can be either 2 x 4 or 2 x 6 construction and does not overhang the foundation wall. This figure also shows insulation and a sand layer beneath the floor slab.

Figure 2-10: Masonry Basement Wall with Exterior Insulation

Figure 2-11 illustrates a concrete foundation wall with interior insulation. A wood frame wall is constructed inside the foundation wall and batt insulation is placed between the studs. Rigid insulation can also be placed between furring strips on the interior wall. This figure also shows rigid insulation beneath the floor slab.


EXTERIOR SIDING
SHEATHING
2 x 6 FRAME WALL OVERHANGS RIM JOIST UP TO 2 IN.
BATT INSULATION
VAPOR RETARDER
GYPSUM BOARD
SUBFLOOR
RIM JOIST (OPTIONAL CAULKING ABOVE AND BELOW RIM JOIST) 10
BATT INSULATION
PRESSURE-TREATED SILL PLATE 11
RIGID INSULATION CAULKED AT ALL EDGES FORMS A VAPOR RETARDER (OPTIONAL) 23
GASKET UNDER SILL PLATE 34
GROUND SLOPES AWAY FROM WALL AT 5% (6" IN 10 FT) 2
8-IN. MIN.
REINFORCING (OPTIONAL) 12
7-IN. MIN.
LOW PERMEABILITY SOIL (OPTIONAL) 3
1/2-IN. ANCHOR BOLTS AT 6 FT. O. C. MAX. 13
INSULATION IN FRAME WALL 24
VAPOR RETARDER
FINISH MATERIAL
DRAINAGE MAT, INSULATING DRAINAGE BOARD, OR GRANULAR BACKFILL (OPTIONAL) 4
RIGID INSULATION IN JOINT (OPTIONAL) 15
DAMPPROOFING OR WATERPROOFING WITH PROTECTION BOARD AS REQUIRED 6
PRES.-TREATED PLATE
4-IN. CONCRETE SLAB WITH W. W. MESH 16
CONCRETE FOUNDATION WALL 14
VAPOR RETARDER 17
RIGID INSULATION (OPTIONAL) 32
FILTER FABRIC ABOVE GRAVEL (OPTIONAL ON SIDES AND BELOW) 7
COARSE GRAVEL
4-IN. GRAVEL DRAINAGE LAYER (OPTIONAL) 18
4-IN. PERFORATED DRAIN PIPE WITH HOLES FACING DOWN (OPTIONAL) 8
THROUGH WALL MOISTURE BARRIER / KEYWAY (OPTIONAL) 19
CONCRETE FOOTING 9
2-IN. DIAMETER WEEP HOLES AT 8 FT. O. C. MAX. (OPTIONAL) 20
REINFORCING (OPTIONAL) 21

Figure 2-11: Concrete Basement Wall with Interior Insulation


EXTERIOR SIDING
SHEATHING
BATT INSULATION
VAPOR RETARDER
GYPSUM BOARD
SUBFLOOR
RIM JOIST (OPTIONAL CAULKING ABOVE AND BELOW RIM JOIST) 10
PRESSURE-TREATED SILL PLATE WITH GASKET 11
8-IN. MIN.
7-IN. MIN.
GROUND SLOPES AWAY FROM WALL AT 5% (6" IN 10 FT) 2
INSULATION BETWEEN FLOOR JOISTS WITH VAPOR RETARDER ON TOP OF INSULATION 25
REINFORCING (OPTIONAL) 12
1/2-IN. ANCHOR BOLTS AT 6 FT. O. C. MAX. 13
LOW PERMEABILITY SOIL (OPTIONAL) 3
CONCRETE FOUNDATION WALL 14
DRAINAGE MAT, INSULATING DRAINAGE BOARD, OR GRANULAR BACKFILL (OPTIONAL) 4
ISOLATION JOINT 15
4-IN. CONCRETE SLAB WITH OPTIONAL W. W. MESH 16
DAMPPROOFING OR WATERPROOFING WITH PROTECTION BOARD AS REQUIRED 6
VAPOR RETARDER 17
FILTER FABRIC ABOVE GRAVEL (OPTIONAL ON SIDES AND BELOW) 7
COARSE GRAVEL
4-IN. GRAVEL DRAINAGE LAYER (OPTIONAL) 18
4-IN. PERFORATED DRAIN PIPE WITH HOLES FACING DOWN (OPTIONAL) 8
THROUGH WALL MOISTURE BARRIER / KEYWAY (OPTIONAL) 19
CONCRETE FOOTING 9
2-IN. DIAMETER WEEP HOLES AT 8 FT. O. C. MAX. (OPTIONAL) 20
REINFORCING (OPTIONAL) 21

Figure 2-12: Concrete Basement Wall with Ceiling Insulation

Figure 2-12 illustrates a basement with insulation placed in the ceiling between the floor joists. This approach is appropriate for an unconditioned basement. It should be used with caution in colder climates and any ducts and pipes in the basement should be insulated.

Figure 2-13 illustrates a pressure-preservative-treated wood foundation wall. Insulation is placed between the studs similar to a conventional wood frame wall.


EXTERIOR SIDING
SHEATHING
BATT INSULATION IN WOOD FRAME WALL
INTERIOR FINISH MATERIAL
VAPOR RETARDER
SUBFLOOR
RIM JOIST (OPTIONAL CAULKING ABOVE OR BELOW RIM JOIST) 10
FIELD-APPLIED TOP PLATE
WALL SYSTEM TOP PLATE 11
BATT INSULATION
RIGID INSULATION CAULKED AT ALL EDGES FORMS VAPOR RETARDER (OPTIONAL) 23
CEILING FINISH MATERIAL
GROUND SLOPES AWAY FROM WALL AT 5% (6" IN 10 FT) 2
PRESSURE-TREATED WOOD FRAME WALL 28
INSULATION 29
VAPOR RETARDER
INTERIOR FINISH MATERIAL
LOW PERMEABILITY SOIL (OPTIONAL) 3
COARSE GRAVEL BACKFILL ON LOWER HALF OF WALL 26
2-IN. AIR SPACE 35
4-IN. CONCRETE SLAB WITH OPTIONAL W. W. MESH 16 36
2-IN. SAND LAYER (OPTIONAL) 16
PRESSURE-TREATED PLYWOOD
6-MIL POLY WATER SHEDDING MEMBRANE 6
3/4-W MIN.
1/2-W MIN.
W
1/2-W MIN.
PRESSURE-TREATED FOOTING PLATE
GRAVEL FOOTING PAD BENEATH FOOTING PLATE 27
VAPOR RETARDER 17
4-IN. GRAVEL DRAINAGE LAYER DRAINS TO SUMP 30

Figure 2-13: Pressure-Preservative-Treated Wood Basement Wall

NOTES FOR ALL DETAILED BASEMENT DRAWINGS (FIGURES 2-8 THROUGH 2-13)

1. Insulation protection: Exterior insulation materials should not be exposed above grade. They should be covered by a protective material — such as exterior grade plastic, fiberglass, galvanized metal or aluminum flashing, a cementitious coating, or a rigid protection board — extending at least 6 inches below grade.

2. Surface drainage: The ground surface should slope downward at least 5 percent (6 inches) over the first 10 feet surrounding the basement wall to direct surface runoff away from the building. Downspouts and gutters should be used to collect roof drainage and direct it away from the foundation walls.

3. Backfill cover: Backfill around the foundation should be covered with a low permeability soil, or a membrane beneath the top layer of soil, to divert surface runoff away from the foundation. (Optional)

4. Backfill or drainage materials: Porous backfill sand or gravel should be used against the walls to promote drainage. Backfill should be compacted so that settlement is minimized. In place of porous backfill, a drainage mat material or insulating drainage board can be placed against the foundation wall. The drainage mat should extend down to a drainpipe at the footing level. (Optional)

5. Exterior insulation materials: Acceptable materials for exterior insulation are: (1) extruded polystyrene boards (XEPS) under any condition, (2) molded expanded polystyrene boards (MEPS) for vertical applications when porous backfill and adequate drainage are provided, and (3) fiberglass or MEPS drainage boards when an adequate drainage system is provided at the footing.

6. Dampproofing/waterproofing: A dampproof coating covered by a 4-mil layer of polyethylene is recommended to reduce vapor transmission from the soil through the basement wall. Parging is recommended on the exterior surface of masonry walls before dampproofing. Waterproofing is recommended on sites with anticipated water problems or poor drainage. Waterproofing should be placed on the exterior directly over the concrete, masonry, or wood substrate. Exterior insulation should be placed over the waterproofing. Waterproofing should extend down to the level of the drainage system at the footing.

7. Filter fabric: A filter fabric over the gravel bed and drainpipe is recommended to prevent clogging of the drainage area with fine soil particles. Wrapping the filter fabric around the entire gravel bed is an optional technique for better protection against clogging.

8. Drainage system: Where drainage problems are not anticipated, a gravel bed placed along the footing will provide adequate drainage. Where conditions warrant, a 4-inch-diameter perforated drainpipe should be installed in the gravel. Perforated drainpipes should be placed with holes facing downward alongside the footing on either the outside or inside. Outside placement is preferred for drainage but inside placement is less susceptible to failure. Drainpipes should slope 1 inch in 20 feet and lead to an outfall or sump. A vertical clean-out pipe with an above-grade capped end is recommended to flush out the system. The top of the pipe should be below the level of the underside of the basement floor slab. The pipe should be surrounded by at least 6 inches of gravel on the sides and 4 inches of gravel above and below the pipe. Surface or roof drainage systems should never be connected to the subsurface drainage system. (Optional)

9. Concrete footing: All concrete footings must be designed with adequate size to distribute the load to the soil and be placed beneath the maximum frost penetration depth or insulated to prevent frost penetration. Concrete used in spread footings should have a minimum compressive strength of 2500 psi.

10. Caulking: Caulking at the following interfaces minimizes air leakage: foundation wall/sill plate, sill plate/rim joist, rim joist/subfloor, subfloor/above-grade wall plate. An alternative is to cover these points on the exterior with an air barrier material. (Optional)

11. Sill plate: The sill plate should be at least 8 inches above grade and should be pressure-preservative treated to resist decay.

12. Crack control reinforcing in walls: Even when no structural reinforcing is required, reinforcing is desirable to minimize shrinkage cracking. Two No. 4 bars running continuously 2 inches below the top of the wall and above/below window openings are recommended. (Optional)

13. Anchor bolts in concrete walls: Anchor bolts should be embedded in the top of concrete foundation walls to resist uplift. Most codes require bolts of 1/2-inch minimum diameter to be embedded at least 7 inches into the wall. Generally, anchor bolts can be placed at a maximum spacing of 6 feet and no further than 1 foot from any corner.

14. Cast-in-place concrete wall: Concrete used in the wall should have a minimum compressive strength of 2500 psi with a 4- to 6-inch slump. No additional water should be added at the job site. Generally, where there are stable soils in areas of low seismic activity, no reinforcing is required in an 8-inch-thick basement wall with up to 7 feet of fill.

15. Isolation joint: An isolation joint should be provided at the slab edge to permit vertical movement without cracking. Where radon is a concern, a liquid sealant should be poured into the joint over a foam backing rod. Rigid insulation placed in the joint prevents a thermal bridge when there is insulation beneath the slab.

16. Concrete slab: A minimum slab thickness of 4 inches is recommended using concrete with a minimum compressive strength of 2500 psi. Welded wire fabric placed 2 inches below the slab surface is recommended to control shrinkage cracks in areas of high radon and termite hazard. Generally, concrete slabs should not rest on footings or ledges of foundation walls if possible to avoid cracking due to settlement. If a slab is poured directly over an impermeable vapor retarder or insulation board, a concrete mixture with a low water/cement ratio is recommended. An alternative technique is to pour the slab on a layer of sand or drainage board material above the vapor retarder to minimize cracking.

17. Vapor retarder: A 6-mil polyethylene vapor retarder should be placed beneath the slab to reduce moisture transmission and radon infiltration into the basement.

18. Gravel layer under slab: A 4-inch gravel layer should be placed under the concrete floor slab for drainage where local conditions suggest basement leakage may be a problem. (Optional)

19. Moisture barrier and wall/footing connection: The concrete wall should be anchored to the footing in one of three ways: (1) sufficient roughening of the top of the footing to prevent sliding, (2) by use of a keyway, or (3) by use of reinforcing dowels. A through-wall moisture barrier is recommended between a concrete wall and footing to prevent capillary draw. (Optional)

20. Weep holes: Two-inch-diameter weep holes through the footing 4 to 8 feet apart may be used to connect the underfloor drainage layer to the drainage system outside the footing. (Optional)

21. Crack control reinforcing in footing: Reinforcing bars placed 2 inches below the top of the footing running parallel to the wall are recommended where differential settlement is a potential problem. (Optional unless required)

22. Masonry wall: Generally where there are stable soils in areas of low seismic activity, no reinforcing is required in a 12-inch-thick masonry wall with up to 6 feet of fill. When reinforcing is required, it must be grouted into block cores. Vertical bars should be spaced no more than 48 inches apart or 6 times the wall thickness, whichever is less.

23. Insulation inside rim joist: Insulation can be placed on the inside of the rim joist but with greater risk of condensation problems and less access to wood joists and sills for inspection from the interior. Low permeability rigid insulation (such as extruded polystyrene) should be used, or a vapor retarder should be placed on the inside of the insulation and sealed to all surrounding surfaces.

24. Interior insulation materials: For interior placement, virtually any batt, blown, or foam insulation is acceptable. Most products require a thermal barrier for fire protection. The use of foam insulation does not require a frame wall—only furring strips are required.

25. Ceiling insulation: Insulation placement in the basement ceiling is an effective alternative where an unconditioned basement is acceptable and ducts are adequately insulated. With fiberglass insulation placed between the wood joists, the vapor retarder should be on the warm side of the insulation facing upwards.

26. Gravel backfill for wood foundation: Coarse gravel backfill should be placed against the lower half of the walls to promote drainage. Backfill should be lightly compacted so that settlement is minimized.

27. Gravel bed beneath wood foundation wall: A compacted gravel bed may serve as the footing under a wood foundation wall. Beneath the wall the gravel layer should be at least 6 inches thick (or three-quarters of the bottom wall plate width, whichever is greater), and the bed should extend out from the footing at least 6 inches on each side (or one-half of the bottom wall plate width).

28. Wood foundation walls: Wood foundation walls must be designed to resist lateral and vertical loads and must be constructed of lumber and plywood that is properly treated to resist decay. Wall construction and material specifications are found in the National Forest Products Association design manual (NFPA 1987). Local codes should be consulted for specific requirements.

29. Insulation in wood foundation walls: Batt, blown, or foam insulations are placed within the stud cavities of a wood foundation system and a vapor retarder is placed on the warm side of the wall.

30. Gravel beneath floor of wood foundation system: A 4-inch layer of gravel should be beneath the floor of a wood foundation system with a sump area located in the middle of the basement. The sump area should be at least 24 inches deep and either 16 inches in diameter or 16 inches square, and can be formed with clay tile flue liner or concrete pipe. The sump must drain to daylight or be provided with a pump (National Forest Products Association, 1987).

31. Anchor bolts in masonry walls: Anchor bolts should be embedded in the top of masonry foundation walls. Most codes require bolts of 1/2-inch minimum diameter embedded at least 7 inches into the wall. In some locations, codes require bolts to be embedded 15 inches in masonry walls to resist uplift. To provide adequate anchorage in a masonry wall, bolts either must be embedded in a bond beam or the appropriate cores of the upper course of block must be filled with mortar. Generally, anchor bolts can be placed at a maximum spacing of 6 feet and no further than 1 foot from any corner.

32. Insulation under the slab: Acceptable materials for underslab insulation are: (1) extruded polystyrene boards (XEPS) under any condition, (2) molded expanded polystyrene boards (MEPS) when the compressive strength is sufficient and adequate drainage is provided, and (3) insulating drainage boards with sufficient compressive strength.

33. Bond beam on masonry wall: When required by code or structural consideration, a bond beam provides additional lateral strength in a masonry wall. Using a bond beam or filling the cores of the upper courses of block also are recommended as radon and termite prevention techniques. (Optional)

34. Gasket: To minimize air leakage, use a compressible foam plastic sill sealer or equivalent.

35. Air space: A 2-inch air space should be provided between the end of the insulation and the bottom plate.

36. Pressure-preservative-treated wood floor: Instead of a concrete floor slab, pressure-preservative-treated wood floors are sometimes used in conjunction with wood foundations. These floors are required to resist the lateral loads being imposed at the bottom of the foundation wall as well as to resist excessive deflection from the vertical floor load.

2.4 Checklist for Design and Construction of Basements

This checklist serves as a chapter summary, helps review the completeness of construction drawings and specifications, and provides general guidance on project management. The checklist could be used many ways. For example, use one set of blanks during design and the second set during construction inspection. Note that not all measures are necessary under all conditions. Use different symbols to distinguish items that have been satisfied (+) from those that have been checked but do not apply (x). Leave unfinished items unchecked.

SITEWORK

____ ____ Locate building at the highest point if the site is wet
____ ____ Define “finish subgrade” (grading contractor), “base grade” (construction contractor), “rough grade” level before topsoil is respread, “finish grade” (landscape contractor)
____ ____ Establish elevations of finish grades, drainage swales, catch basins, foundation drain outfalls, bulkheads, curbs, driveways, property corners, changes in boundaries
____ ____ Establish grading tolerances
____ ____ Provide intercepting drains upgrade of foundation if needed
____ ____ Locate dry wells and recharge pits below foundation level
____ ____ Establish precautions for stabilizing excavation
____ ____ Establish limits of excavation and determine trees, roots, buried cables, pipes, sewers, etc., to be protected from damage
____ ____ Confirm elevation of water table
____ ____ Determine type and dimensions of drainage systems
____ ____ Discharge roof drainage away from foundation
____ ____ Remove stumps and grubbing debris from site
____ ____ Provide frost heave protection for winter construction
____ ____ Call for test hole (full depth hole in proposed foundation location)
____ ____ Locate stakes and benchmarks
____ ____ Strip and stock pile topsoil
____ ____ Define spoil site

FOOTINGS

____ ____ Position bottom of footing at least 6 inches below frost depth around perimeter (frost wall at garage, slabs supporting roofs, other elements attached to structure). Make sure footing is deeper under basement walkouts
____ ____ Confirm adequacy of footing sizes
____ ____ Do not fill the overexcavated footing trench
____ ____ Install longitudinal reinforcing (two No. 4 or No. 5 bars 2 inches from top)
____ ____ Reinforce footing at spans over utility trenches
____ ____ Do not bear footings partially on rock (sand fill)
____ ____ Do not pour footings on frozen ground
____ ____ Indicate minimum concrete compressive strength after 28 days
____ ____ Call out elevations of top of footings and dimension elevation changes in plan
____ ____ Use keyway or steel dowels to anchor walls
____ ____ Dimension stepped footings according to local codes and good practice (conform to masonry dimensions if applicable)
____ ____ Provide weep holes (minimum 2-inch diameter at 4 feet to 8 feet on center)
____ ____ Provide through-joint flashing as a capillary break

BASEMENT CHECKLIST (PAGE 2 OF 5)

CAST-IN-PLACE CONCRETE WALLS

____ ____ Determine minimum compressive strength after 28 days
____ ____ Determine maximum water/cement ratio. (Note: add no water at site)
____ ____ Determine allowable slump
____ ____ Determine acceptable and unacceptable admixtures
____ ____ Determine form-release agents acceptable to WPM manufacturer
____ ____ Establish curing requirements (special hot, cold, dry conditions)
____ ____ Establish surface finish requirements and preparation for WPM (plug all form tie holes)
____ ____ For shrinkage control: use horizontal reinforcing at top of wall and/or control joints
____ ____ Design width of wall to resist height of fill, seismic loads, and loads transmitted through soil from adjacent foundations
____ ____ Use two-way reinforcing (horizontal and vertical) for strength, watertightness, termite and radon resistance
____ ____ Establish anchor bolt depth and spacing requirements, and install accordingly
____ ____ Provide cast-in-place anchors for joist ends
____ ____ Establish beam pocket elevations, dimensions, details
____ ____ Determine top of wall elevations and changes in wall height
____ ____ Determine brick shelf widths and elevations

CONCRETE MASONRY WALLS

____ ____ Specify mortar mixes and strengths
____ ____ Size walls to resist height of fill, seismic loads, loads transmitted through soil from adjacent foundations
____ ____ Grout top courses of block to receive anchor bolts
____ ____ Indicate special details for proprietary masonry systems
____ ____ Ensure that the surface quality is suitable to WPM
____ ____ Prepare exterior surface for application of dampproofing or WPM (special preparation consisting of cement parging, priming)
____ ____ For crack control, use bond beam or horizontal joint reinforcing

FLOOR SLAB

____ ____ Determine minimum compressive strength after 28 days
____ ____ Determine maximum water/cement ratio. (Note: add no water at site)
____ ____ Determine allowable slump
____ ____ Determine acceptable and unacceptable admixtures
____ ____ Establish curing requirements (special hot, cold, dry conditions)
____ ____ Determine surface finish
____ ____ Provide shrinkage control: WWF reinforcement or control joints
____ ____ Provide isolation joints at wall perimeter and column pads
____ ____ Provide vapor retarder under slab
____ ____ Provide sand layer over vapor retarder or insulation board
____ ____ Compact fill under slab

BASEMENT CHECKLIST (PAGE 3 OF 5)

BACKFILLING AND COMPACTION

____ ____ Establish minimum concrete strength or curing prior to backfilling
____ ____ Use high early strength concrete if necessary
____ ____ Install temporary wall support during backfilling
____ ____ Establish condition of fill material (if site material stays in clump after soaking and squeezing in hand, do not use as backfill)
____ ____ Determine proper compaction
____ ____ Cap backfill with an impermeable cover

SUBDRAINAGE

General considerations. Footing drains (1) draw down the ground water level; (2) prevent ponds of rainwater and snow melt in the backfill. The underslab drainage layer (1) conveys rising groundwater laterally to collecting drain lines; (2) acts as a distribution and temporary storage pad for water that drains through the backfill and would otherwise form ponds at the bottom.

____ ____ Use gravel pad and footing weep holes
____ ____ Position high end of footing drains below underside of floor slab (Note: outside footing placement is preferred for drainage; inside placement is less susceptible to failure)
____ ____ Ensure footing drain is pitched
____ ____ Lay footing drain on compacted bedding (minimum 4 inches thick)
____ ____ Set unperforated leaders to drain to outfall (hand backfill first 8 inches to avoid damaging pipe)
____ ____ Ensure that transitions are smooth between pipes of different slopes
____ ____ Separate surface, roof, and foundation drain systems
____ ____ Call out gravel or crushed stone envelope around drainpipe and wrap with a synthetic filter fabric
____ ____ Locate clean-outs for flushing the system
____ ____ Install porous backfill or wall-mounted drainage product
____ ____ Provide minimum 4-inch-thick gravel or stone layer under slab
____ ____ If large flow of water is anticipated, use curtain drain to intercept

MOISTUREPROOFING

General considerations. Waterproofing is usually recommended for all below-grade living and work spaces. Dampproofing provides a capillary break and serves as a vapor retarder. Waterproof membranes (WPM) dampproof, but dampproofing does not waterproof.

____ ____ Either dampproof or waterproof walls
____ ____ Place a polyethylene vapor retarder under floor slabs (optional sand layer between polyethylene and slab)
____ ____ Place a continuous WPM under slab for basements below groundwater (special detailing and reinforcement required for support)
____ ____ Install control and expansion joints according to recommendations of WPM manufacturer
____ ____ Provide protection board for WPM

BASEMENT CHECKLIST (PAGE 4 OF 5)

THERMAL AND VAPOR CONTROLS

General considerations. Exterior insulation maintains the wall close to indoor temperature. This can eliminate the need for vapor retarders on the interior and keeps rubber and asphalt-based moistureproofing warm and pliable. Interior and integral insulations require a vapor retarder at the inside surface. Difficulty of vapor sealing at the rim joist generally favors exterior insulation.

____ ____ Verify that wall insulation R-value and depth meet local codes and/or recommendations from this handbook
____ ____ Insulate ceiling in unconditioned basements
____ ____ If used, specify exterior insulation product suitable for in-ground use
____ ____ Install protective coating for exterior insulation
____ ____ Install polyethylene slip sheet between soil and wall (nondrainage) insulation
____ ____ Install vapor retarder at inside face of internally and integrally insulated walls
____ ____ Place a fire-protective cover over combustible insulations
____ ____ Install infiltration sealing gasket under sill plate
____ ____ Seal air leakage penetrations through rim joists
____ ____ Install an air barrier outside rim joist

DECAY AND TERMITE CONTROL

General considerations. Strategy: (1) Isolate wood members from soil by an air space or impermeable barrier; (2) expose critical areas for inspection. Pressure-treated lumber is less susceptible to attack, but is no substitute for proper detailing. Termite shields are not reliable barriers unless installed correctly.

____ ____ Pressure-treat wood posts, sill plates, rim joists, wood members in contact with foundation piers, walls, floors, etc.
____ ____ Pressure-treat all outdoor weather-exposed wood members
____ ____ Install dampproof membrane under sill plate and beams in pockets (flashing or sill seal gasket)
____ ____ Leave minimum 1/2-inch air space around beams in beam pockets
____ ____ Expose sill plates and rim joists for inspection
____ ____ Elevate sill plate minimum 8 inches above exterior grade
____ ____ Elevate wood posts and framing supporting porches, stairs, decks, etc., above grade (6-inch minimum) on concrete piers
____ ____ Elevate wood siding, door sills, other finish wood members at least 6 inches above grade (rain splash protection)
____ ____ Separate raised porches and decks from the building by 2-inch horizontal clearance for drainage and termite inspection (or provide proper flashing)
____ ____ Pitch porches, decks, patios for drainage (minimum 1/4 in/ft)
____ ____ Treat soil with termiticide, especially with insulated foundations
____ ____ Reinforce slab-on-grade
____ ____ Remove all grade stakes, spreader sticks, and wood embedded in concrete during pour
____ ____ Do not disturb treated soil prior to pouring concrete slab
____ ____ Reinforce cast-in-place concrete walls (with No. 5 bars) along the top and bottom to resist settlement cracking

BASEMENT CHECKLIST (PAGE 5 OF 5)

RADON CONTROL

General considerations. The potential for radon hazard is present in all buildings. Check state and local health agencies for need of protection. Strategies include: (1) barriers; (2) air management; and (3) provisions to simplify retrofit. Since radon is a gas, its rate of entry through the foundation depends on suction due to stack effect and superstructure air leakage.

____ ____ Separate outdoor intakes for combustion devices
____ ____ Install air barrier wrap around superstructure
____ ____ Seal around flues, chases, vent stacks, attic stairs
____ ____ Install polyethylene vapor retarder as floor underlayment between first floor and unconditioned basement
____ ____ Reinforce cast-in-place concrete walls (with No. 5 bars) along the top and bottom to resist settlement cracking
____ ____ For crack control in masonry walls, use bond beam or horizontal joint reinforcing
____ ____ Seal top of hollow masonry walls with solid block, bond beam, or cap block
____ ____ Parge exterior face of masonry walls
____ ____ Install continuous moistureproofing on the outside of masonry walls
____ ____ Reinforce slab-on-grade
____ ____ Remove all grade stakes, spreader sticks, and wood embedded in concrete during pour
____ ____ Form perimeter wall/floor joint trough for pour-in sealant
____ ____ Place vapor retarder under slab (with optional sand layer)
____ ____ Caulk joints around pipes and conduits
____ ____ Install sump pit with airtight cover
____ ____ Vent sump pit to outside
____ ____ Do not use floor drains, unless mechanical trap valves are used
____ ____ Lay minimum 4-inch-thick layer of coarse, clean gravel under slab
____ ____ Cast 4-inch-diameter PVC tubing standpipes (capped) into slab

PLANS, CONTRACTS, AND BUILDING PERMITS

____ ____ Complete plans and specifications
____ ____ Complete bid package
____ ____ Establish contractual arrangements (describe principals, describe the work by referencing the blueprints and specs, state the start/completion dates, price, payment schedule, handling of change orders, handling of disputes, excavation allowance, and procedure for firing)
____ ____ Acquire building permits

SITE INSPECTIONS DURING CONSTRUCTION

____ ____ After excavation and before concrete is poured for the footings
____ ____ After the footings have been poured before foundation wall construction
____ ____ After foundation construction and dampproofing before rough framing
____ ____ After rough framing
____ ____ After rough plumbing and electrical
____ ____ After insulation installation before drywall and backfilling in case of exterior insulation
____ ____ Final

CHAPTER 3

Crawl Space Construction

This chapter summarizes suggested practices related to crawl spaces. Section 3.1 presents various insulation configurations along with recommended optimal levels of insulation for vented and unvented crawl spaces.

Section 3.2 summarizes crawl space design and construction practices in the following areas: structural design, location of insulation, drainage and waterproofing, termite and decay control, and radon control. Section 3.3 includes a series of alternative construction details with accompanying notes indicating specific practices. Section 3.4 is a checklist to be used during the design, construction, and site inspection of a crawl space.



Figure 3-1: Concrete Crawl Space Wall with Exterior Insulation

3.1 Crawl Space Insulation Placement and Thickness

To provide energy use information for buildings with crawl space foundations, heating and cooling loads were simulated for a variety of insulation placements and thicknesses in representative U.S. climates (Labs et al. 1988). Two types of crawl spaces were analyzed for energy purposes — vented and unvented. Generally most major building codes require vents near each corner. These vents may have operable louvers. The vented crawl space is assumed to have venting area openings of 1 square foot per 1500 square feet of floor area. The temperature of the vented crawl space varies between the interior house temperature and the exterior temperature. The unvented crawl space is assumed to have vents fully closed, leaving only gaps in construction that could allow infiltration. Unvented crawl spaces insulated at the perimeter are similar to unheated basements, with temperatures that fluctuate between 50°F and 70°F most of the year, depending on climate and insulation placement.

Crawl spaces can vary in height and relationship to exterior grade. It is assumed in the analysis that follows that crawl space walls are 2 feet high with only the upper 8 inches of the foundation wall exposed above grade on the exterior side.

Insulation Configurations and Costs

Table 3-1 includes illustrations and descriptions of a variety of crawl space insulation configurations. Two basic construction systems are shown for unvented crawl spaces — a concrete (or masonry) foundation wall and a pressure-preservative-treated wood foundation wall. For vented crawl spaces, concrete (or masonry) walls are shown.

In a vented crawl space, insulation is placed between the floor joists in the crawl space ceiling. In an unvented crawl space, the two most common approaches to insulating concrete / masonry walls are (1) covering the entire wall on the exterior, and (2) covering the entire wall on the interior. In addition to these conventional approaches, insulation can be placed on the interior wall and horizontally on the perimeter of the crawl space floor (extending either 2 or 4 feet into the space). With pressure-preservative-treated wood construction, batt insulation is placed in the cavities between the wood studs.

Recommended Insulation Levels

While increasing the amount of crawl space insulation produces greater energy savings, the cost of installation must be compared to these savings. Such a comparison can be done in several ways; however, a life cycle cost analysis (presented in worksheet form in Chapter 5) is recommended since it takes into account a number of economic variables including installation costs, mortgage rates, HVAC efficiencies, and fuel escalation rates. In order to identify the most economical amount of insulation for the crawl space configurations shown in Table 3-1, the case with the lowest 30-year life cycle cost was determined for five U.S. cities at three different fuel cost levels. See the *Building Foundation Design Handbook* (Labs et al. 1988) to find recommendations for a greater number of cities and for a detailed explanation of the methodology. The economic methodology used to determine the insulation levels in Table 3-1 is consistent with ASHRAE standard 90.2P. The simple payback averages 13 years for all U.S. climate zones, and never exceeds 18 years for any of the recommended levels.

Economically optimal configurations are shown by the darkened circles in Table 3-1 in the following categories: (1) unvented crawl spaces with concrete / masonry walls and exterior insulation, (2) unvented crawl spaces with concrete / masonry walls and interior insulation, (3) unvented crawl spaces with wood walls, and (4) vented crawl spaces with concrete walls. Configurations are recommended for a range of climates and fuel prices in each of these categories, but the different categories of cases are not directly compared with each other. In other words, there is an optimal amount of exterior insulation recommended for a given climate and fuel price, and there is a different optimal amount of insulation for interior insulation. Where there is no darkened circle in a particular category, insulation is not economically justified under the assumptions used.

For unvented crawl spaces with concrete / masonry walls, exterior insulation ranging from R-5 to R-10 is justified at all fuel price levels (shown in Table 3-2) in all climate zones except the warmest one. Similar levels of interior insulation are recommended. However in colder climates, placing insulation horizontally on the crawl space floor in addition to the wall is frequently the optimal configuration. If the crawl space wall is higher than 2 feet, as it often must be to reach frost depth in a colder climate, it is advisable to extend the vertical insulation to the footing. Although simulation results for crawl spaces with higher walls and deeper footings are not shown here, the need for insulation placed deeper than 2 feet in cold climates is obvious and is reflected by the economic benefits of placing insulation on the floor of a shallower crawl space.

For unvented crawl spaces with pressure-preservative-treated wood walls, insulation ranging from R-11 to R-19 is justified in moderate and colder climates. In vented crawl spaces, ceiling insulation

Table 3-1: Insulation Recommendations for Crawl Spaces

A: Unvented Crawl Space - Concrete or Masonry Foundation Walls with Exterior Insulation

CONFIGURATION	DESCRIPTION	RECOMMENDED CONFIGURATIONS AT THREE FUEL PRICE LEVELS														
		0-2000 HDD (LOS ANG)			2-4000 HDD (FT WORTH)			4-6000 HDD (KAN CITY)			6-8000 HDD (CHICAGO)			8-10000 HDD (MPLS)		
		L	M	H	L	M	H	L	M	H	L	M	H	L	M	H
EXTERIOR VERTICAL 	NO INSULATION	●	●	●	●	○	○	○	○	○	○	○	○	○	○	○
	2 FT: R-5 RIGID	○	○	○	○	●	●	●	○	○	●	○	○	○	○	○
	2 FT: R-10 RIGID	○	○	○	○	○	○	○	●	●	○	●	●	●	●	●

B: Unvented Crawl Space - Concrete or Masonry Foundation Walls with Interior Insulation

INTERIOR VERTICAL 	NO INSULATION	●	●	●	○	○	○	○	○	○	○	○	○	○	○	○
	2 FT: R-5 RIGID	○	○	○	●	●	●	●	●	●	●	○	○	○	○	○
	2 FT: R-10 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
INTERIOR VERTICAL AND HORIZONTAL 	2 FT/2 FT: R-5 RIGID	○	○	○	○	○	○	○	○	○	○	●	●	●	●	○
	2 FT/4 FT: R-5 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	2 FT/2 FT: R-10 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	●
	2 FT/4 FT: R-10 RIGID	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○

C: Unvented Crawl Space - Pressure-Treated Wood Foundation Walls

WITHIN WOOD WALL 	NO INSULATION	●	●	●	●	●	○	○	○	○	○	○	○	○	○	○
	2 FT: R-11 BATT	○	○	○	○	○	●	●	●	○	○	○	○	○	○	○
	2 FT: R-19 BATT	○	○	○	○	○	○	○	○	●	●	●	●	●	●	●

D: Vented Crawl Space - Concrete or Masonry Foundation Walls with Ceiling Insulation

CEILING 	NO INSULATION	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	R-11 BATT	●	●	●	●	●	○	○	○	○	○	○	○	○	○	○
	R-19 BATT	○	○	○	○	○	●	●	●	●	●	●	○	●	○	○
	R-30 BATT	○	○	○	○	○	○	○	○	○	○	○	●	○	●	●

1. L, H, and M refer to the low, medium, and high fuel cost levels indicated in Table 3-2.
2. The darkened circle represents the recommended level of insulation in each column for each of the four basic insulation configurations.
3. These recommendations are based on assumptions that are summarized at the end of section 3.1 and further explained in chapter 5.

Table 3-2: Fuel Price Levels Used to Develop Recommended Insulation Levels in Table 3-1

SEASON	FUEL TYPE	LOW PRICE LEVEL ($)	MEDIUM PRICE LEVEL ($)	HIGH PRICE LEVEL ($)
HEATING	NATURAL GAS	.374 / THERM	.561 / THERM	.842 / THERM
	FUEL OIL	.527 / GALLON	.791 / GALLON	1.187 / GALLON
	PROPANE	.344 / GALLON	.516 / GALLON	.775 / GALLON
COOLING	ELECTRICITY	.051 / KWH	.076 / KWH	.114 / KWH

ranging from R-11 to R-30 is recommended in all climates at all fuel price levels.

Comparison of Insulation Systems

Insulating the ceiling of a vented crawl space is generally more cost-effective than insulating the walls of an unvented crawl space to an equivalent level. This is because placing mineral wool batt insulation into the existing spaces between floor joists represents a much smaller incremental cost than placing rigid insulation on the walls. Thus higher levels of insulation are recommended in the floor above a vented crawl space than for the walls of an unvented space.

When exterior and interior insulation are compared for an unvented crawl space with concrete / masonry walls, thermal results are very similar for equivalent amounts of insulation. Since it is assumed that exterior insulation costs more to install, however, interior placement is always economically optimal in comparison. This increased cost for an exterior insulation is attributed to the need for protective covering and a higher quality rigid insulation that can withstand exposure to water and soil pressure.

Generally, insulating pressure-preservative-treated wood walls is more cost-effective than insulating concrete / masonry walls to an equivalent level. This is because the cavity exists between studs in a wood wall system and the incremental cost of installing batt insulation in these cavities is relatively low. Thus, a higher R-value is economically justified for wood wall systems.

In spite of the apparent energy efficiency of wood versus concrete / masonry basement walls, this is only one of many cost and performance issues to be considered. Likewise, on a concrete / masonry foundation wall, the economic benefit of interior versus exterior insulation may be offset by other practical, performance, and aesthetic considerations discussed elsewhere in this book. Although ceiling insulation in a vented crawl space appears more cost-effective than wall insulation in an unvented space, a vented crawl space may be undesirable in colder climates since pipes and ducts may be exposed to freezing temperatures. In all cases the choice of foundation type and insulation system must be based on many factors in addition to energy cost-effectiveness.

Assumptions

These general recommendations are based on a set of underlying assumptions. Fuel price assumptions used in this analysis are shown in Table 3-2. The total heating system efficiency is 68 percent and the cooling system SEER is 9.2 with 10 percent duct losses. Energy price inflation and mortgage conditions are selected to allow maximum simple payback of 18 years with average paybacks of about 13 years.

The total installed costs for all insulation systems considered in this analysis are shown in Table 5-2 in chapter 5. Installation costs used in this analysis are based on average U.S. costs in 1987. For the exterior cases, costs include labor and materials for extruded polystyrene insulation and the required protective covering and flashing above grade. For the interior cases, costs include labor and materials for expanded polystyrene. All costs include a 30 percent builder markup and a 30 percent subcontractor markup for overhead and profit.

With pressure-preservative-treated wood construction, batt insulation is placed in the cavities between the wood studs. Costs for wood foundations reflect the additional cost of installing insulation with an ASTM E-84 flame spread index of 25 or less in a wood foundation wall.

If the general assumptions used in this analysis are satisfactory for the specific project, the reader can determine the approximate recommended insulation level for a location by finding the heating degree days from Table 5-1 in chapter 5 and selecting the appropriate climate zone and fuel price level shown in Table 3-1. If not, project-specific optimal insulation levels can be determined using actual estimated construction costs with the worksheet provided in chapter 5. The worksheet enables the user to select economic criteria other than allowing maximum simple paybacks of 18 years. In addition, the user can incorporate local energy prices, actual insulation costs, HVAC efficiencies, mortgage conditions, and fuel escalation rates. Cost-effectiveness can vary considerably, depending on the construction details and cost assumptions.

3.2 Recommended Design and Construction Details

VENTED VERSUS UNVENTED CRAWL SPACES

The principal perceived advantage of a vented crawl space over an unvented one is that venting can minimize radon and moisture-related decay hazards by diluting the crawl space air. Venting can complement other moisture and radon control measures such as ground cover and proper drainage. However, although increased air flow in the crawl space may offer some dilution potential for ground source moisture and radon, it will not necessarily solve a serious problem. The principal disadvantages of a vented crawl space over an unvented one are that (1) pipes and ducts must be insulated against heat loss and freezing, (2) a larger area usually must be insulated, which may increase the cost, and (3) in some climates warm humid air circulated into the cool crawl space can actually cause excessive moisture levels in wood. Vented crawl spaces are often provided with operable vents that can be closed to reduce winter heat losses, but also potentially increase radon infiltration. Although not their original purpose, the vents can also be closed in summer to keep out moist exterior air that can have a dew point above the crawl space temperature.

It is not necessary to vent a crawl space for moisture control if it is open to an adjacent basement, and venting is clearly incompatible with crawl spaces used as heat distribution plenums. In fact, there are several advantages to designing crawl spaces as semi-heated zones. Duct and pipe insulation can be reduced, and the foundation is insulated at the crawl space perimeter instead of its ceiling. This usually requires less insulation, simplifies installation difficulties in some cases, and can be detailed to minimize condensation hazards. Nevertheless, venting of crawl spaces may be desirable in areas of high radon hazard. However, venting should not be considered a reliable radon mitigation strategy. Pressurizing the crawl space is one potentially effective method of minimizing soil gas uptake, but the crawl space walls and ceiling must be tightly constructed for this approach to be effective.

Although unvented crawl spaces have been recommended, “except under severe moisture conditions,” by the University of Illinois’s Small Homes Council (Jones 1980), moisture problems in crawl spaces are common enough that many agencies are unwilling to endorse closing the vents year-round. Soil type and the groundwater level are key factors influencing moisture conditions. It should be recognized that a crawl space can be designed as a short basement (with slurry slab floor), and, having a higher floor level, is subject to less moisture hazard in most cases. Viewed in this way, the main distinction between unvented crawl spaces and basements is in the owner’s accessibility and likelihood of noticing moisture problems.

STRUCTURAL DESIGN

The major structural components of a crawl space are the wall and the footing (see Figure 3-2). Crawl space walls are typically constructed of cast-in-place concrete, concrete masonry units, or pressure-treated wood. Crawl space walls must resist any lateral loads from the soil and vertical loads from the structure above. The lateral loads on the wall depend on the height of the fill, the soil type and moisture content, and whether the building is located in an area of low or high seismic activity. Some simple guidelines for wall thickness, concrete strength, and reinforcing are given in the construction details that follow. Where simple limits are exceeded, a structural engineer should be consulted.

In place of a structural foundation wall and continuous spread footing, the structure can be supported on piers or piles with beams in between. These beams between piers support the structure above and transfer the load back to the piers.

Concrete spread footings provide support beneath concrete and masonry crawl space walls and / or columns. Footings must be designed with adequate size to distribute the load to the soil and be placed beneath the maximum frost penetration depth unless founded on bedrock or proven non-frost-susceptible soil or insulated to prevent frost penetration. A compacted gravel bed serves as the footing under a wood foundation wall when designed in accordance with the National Forest Products Association's wood foundation specification (NFPA 1987). Since the interior temperature of a vented crawl space may be below freezing in very cold climates, footings must be below the frost depth with respect to both interior and exterior grade unless otherwise protected.

Where expansive soils are present or in areas of high seismic activity, special foundation construction techniques may be necessary. In these cases, consultation with local building officials and a structural engineer is recommended.

DRAINAGE AND WATERPROOFING

Although a crawl space foundation is not as deep as a full basement, it is highly desirable to keep it dry. Good surface drainage is always recommended and, in many cases, subsurface drainage systems may be desirable. The goal of surface drainage is to keep water away from the foundation by sloping the ground surface and using gutters and downspouts for roof drainage. Where the crawl space floor is at the same level or above the surrounding exterior grade, no subsurface drainage system is required (see Figure 3-3). On sites with a high water table or poorly draining soil, one recommended solution is to keep the


ANCHOR BOLT CONNECTS FOUNDATION WALL TO SUPERSTRUCTURE AND RESISTS WIND UPLIFT
WALL RESISTS VERTICAL LOAD FROM ABOVE-GRADE STRUCTURE
WALL RESISTS LATERAL LOAD FROM SOIL
SPREAD FOOTING DISTRIBUTES VERTICAL LOAD TO GROUND

Figure 3-2: Components of Crawl Space Structural System


SURFACE DRAINAGE TECHNIQUES:
- SLOPE GROUND AWAY
- USE GUTTERS AND DOWNSPOUTS
WHEN THE CRAWL SPACE FLOOR IS AT OR ABOVE EXTERIOR GRADE, A SUBSURFACE DRAINAGE SYSTEM IS NOT NECESSARY

Figure 3-3: Crawl Space Drainage Techniques


SURFACE DRAINAGE TECHNIQUES:
- SLOPE GROUND AWAY
- USE GUTTERS AND DOWNSPOUTS
WHEN THE CRAWL SPACE FLOOR IS BELOW EXTERIOR GRADE, A SUBSURFACE DRAINAGE SYSTEM IS RECOMMENDED IF SOIL IS NONPOROUS

Figure 3-4: Crawl Space Drainage Techniques

crawl space floor above or at the same level as exterior grade.

On sites with porous soil and no water table near the surface, placing the crawl space floor below the surface is acceptable with no requirement for a subdrainage system. Where it is necessary or desirable to place the crawl space floor beneath the existing grade and the soil is nonporous, a subsurface perimeter drainage system similar to that used for a basement is recommended (see Figure 3-4). In some cases a sump may be necessary. On a sloping site, subdrainage may be required on the uphill side if the soil is nonporous. Generally no waterproofing or dampproofing on the exterior foundation walls of crawl spaces is considered necessary, assuming drainage is adequate.

LOCATION OF INSULATION

If a vented crawl space is insulated, the insulation is always located in the ceiling. Most commonly, batt insulation is placed between the floor joists. The depth of these joist spaces accommodates high insulation levels at a relatively low incremental cost. This placement usually leaves sill plates open to inspection for termites or decay.

A key question in the design of an unvented crawl space is whether to place insulation inside or outside the wall. In terms of energy use, there is not a significant difference between the same amount of insulation applied to the exterior versus the interior of a concrete or masonry wall. However, the installation costs, ease of application, appearance, and various technical concerns can be quite different.

Rigid insulation placed on the exterior surface of a concrete or masonry wall has some advantages over interior placement in that it can provide continuous insulation with no thermal bridges, protect structural walls at moderate temperatures, and minimize moisture condensation problems. Exterior insulation at the rim joist leaves joists and sill plates open to inspection from the interior for termites and decay. On the other hand, exterior insulation on the wall can be a path for termites and can prevent inspection of the wall from the exterior. If needed a termite screen should be installed through the insulation where the sill plate rests on the foundation wall. Vertical exterior insulation on a crawl space wall can extend as deep as the top of the footing and, if desired, be supplemented by extending the insulation horizontally from the face of the foundation wall.

Interior crawl space wall insulation is more common than exterior, primarily because it is less expensive since no protective covering is required. On the other hand, interior wall insulation may be considered less desirable than exterior insulation because it (1) increases the exposure of the wall to thermal stress and freezing, (2) may increase the likelihood of condensation on sill plates, band joists, and joist ends, (3) often results in some thermal bridges through framing members, and (4) may require installation of a flame spread resistant cover. Rigid board insulation is easier to apply to the interior wall than batt insulation since it requires no framing for support, is continuous, can be installed prior to backfilling against the foundation wall or installing the floor, and may require no additional vapor retarder. Insulation placed around the crawl space floor perimeter can provide additional thermal protection; however, it may also create additional paths for termite entry. Batt insulation is commonly placed inside the rim joist. This rim joist insulation should be covered on the inside face with a polyethylene vapor retarder or a rigid foam insulation, sealed around the edges, to act as a vapor retarder. In place of batts, simply using tight-fitting rigid foam pieces in the spaces between the floor joists is an effective solution.

Less expensive batts are an alternative to rigid foam insulation on the interior crawl space wall. It is possible to install them in a crawl space similar to a basement installation. One way is to provide a furred-out stud wall and a vapor retarder on the studs. This is a more expensive and less likely approach than simply using rigid foam with no furring. A common, low-cost approach to insulating crawl space walls is simply draping batts with a vapor retarder facing over the inside of the wall. In most states, codes require the batt vapor retarder cover be approved with respect to flame spread. These can be laid loosely on the ground at the perimeter to reduce heat loss through the footing. With this approach it is difficult to maintain the continuity of the vapor retarder around the joist ends and to seal the termination of the vapor retarder. Good installations are difficult because of cramped working conditions, and a vapor-proof installation will prevent easy inspection for termites.

With a pressure-preservative-treated wood foundation system, insulation is placed in the stud cavities similar to above-grade insulation in a wood frame wall. This approach has a relatively low cost and provides sufficient space for considerable insulation thickness.

In addition to more conventional interior or exterior placement covered in this handbook, there are several systems that incorporate insulation into the construction of the concrete or masonry walls. These include (1) rigid foam plastic insulation cast within concrete walls, (2) polystyrene beads or granular insulation materials poured into the cavities of conventional masonry walls, (3) systems of concrete blocks with insulating foam inserts, (4) formed, interlocking rigid foam units that serve as a permanent insulating form for cast-in-place concrete, and (5) masonry blocks made with polystyrene beads instead of aggregate in the concrete mixture, resulting in significantly higher R-values. However, the effectiveness of systems that insulate only a portion of the wall area should be evaluated closely because thermal bridges through the insulation can impact the total performance significantly.

TERMITE AND WOOD DECAY CONTROL TECHNIQUES

Techniques for controlling the entry of termites through residential foundations are advisable in much of the United States (see Figure 3-5). The following recommendations apply where termites are a potential problem. Consult with local building officials and codes for further details.

1. Minimize soil moisture around the foundation by using gutters and downspouts to remove roof water, and by installing a complete subdrainage system around the foundation.

2. Remove all roots, stumps, and scrap wood from the site before, during, and after construction, including wood stakes and formwork from the foundation area.

3. Treat soil with termiticide on all sites vulnerable to termites.

4. Place a bond beam or course of solid cap blocks on top of all concrete masonry foundation walls to ensure that no open cores


PRESSURE-PRESERVATIVE TREATED SILL PLATE 8-IN. MIN. ABOVE GRADE
WOOD SIDING 6-IN. MIN. ABOVE GRADE
REMOVE ROOTS, TRUNKS, AND SCRAP WOOD FROM FOUNDATION AREA
BOND BEAM, CAP BLOCK, OR FILLED UPPER COURSE OF MASONRY WALL
WOOD POSTS SHOULD BE TREATED, PLACED ON FLASHING, OR PLACED ON A CONCRETE PEDESTAL 8 IN. ABOVE FLOOR
TREAT SOIL FOR TERMITES
MINIMIZE SOIL MOISTURE
- USE GUTTERS AND DOWNSPOUTS
- INSTALL SUBSURFACE DRAINAGE SYSTEM

Figure 3-5: Termite Control Techniques for Crawl Spaces

are left exposed. Alternatively, fill all cores on the top course with mortar, and reinforce the mortar joint beneath the top course.

5. Place the sill plate at least 8 inches above grade; it should be pressure-preservative treated to resist decay. The sill plate should be visible for inspection from the interior. Since termite shields are often damaged or not installed carefully enough, they are considered optional and should not be regarded as sufficient defense by themselves.

6. Be sure that exterior wood siding and trim is at least 6 inches above the final grade.

7. Construct porches and exterior slabs so that they slope away from the foundation wall and are at least 2 inches below exterior siding. In addition, porches and exterior slabs should be separated from all wood members by a 2-inch gap visible for inspection or by a continuous metal flashing soldered at all seams.

8. Use pressure-preservative-treated wood posts within a crawl space, or place posts on flashing or on a concrete pedestal raised 8 inches above the interior grade.

Plastic foam and batt insulation materials have no food value to termites, but they can provide protective cover and easy tunnelling. Insulation installations can be detailed for ease of inspection, although often by sacrificing thermal efficiency. In principle, termite shields offer protection through detailing, but should not be relied upon as a barrier.

These concerns over insulation and the unreliability of termite shields have led to the conclusion that soil treatment is the most effective technique to control termites with an insulated foundation. However, the restrictions on some traditionally used termiticides may make this option either unavailable or cause the substitution of products that are more expensive and possibly less effective. This situation should encourage insulation techniques that enhance visual inspection and provide effective barriers to termites.

RADON CONTROL TECHNIQUES

Construction techniques for minimizing radon infiltration into a crawl space are appropriate if there is a reasonable probability that radon is present (see Figure 3-6). To determine this, contact the state health department or environmental protection office.

1. For crawl spaces susceptible to low radon exposure, provide substantial outside air ventilation. Place vents on all four sides of the crawl space. A second more reliable radon control solution is to control and isolate the source as suggested for basement construction in Chapter 2.

2. Place a 6-mil polyethylene vapor retarder over all exposed soil floor areas. Overlap edges 12 inches and seal. Seal edges to the interior face of the foundation wall.

3. If the crawl space is unvented or if indoor radon levels could be moderate to high, follow the radon control techniques recommended for basements (see Chapter 2). This may also include pressurization of the crawl space or soil gas removal from beneath the crawl space soil covering.

4. Construct floors above unconditioned spaces with a continuous air infiltration barrier. Tongue and groove plywood floor decking should be applied with butt joints continuously glued to floor joists with a waterproof construction adhesive. Seal all penetrations through the subfloor with caulk. Enclose large openings such as at bath tub drains with sheet metal or other rigid material and sealants.

5. Avoid duct work in the crawl space if possible, but it may be installed providing all joints are securely taped or otherwise tightly sealed.

6. Render crawl space walls separating an attached vented crawl space from a basement or living space as airtight as possible.


CONSTRUCT FLOOR WITH CONTINUOUS AIR BARRIER
SEAL ALL PENETRATIONS THROUGH FLOOR WITH CAULKING
PROVIDE SUBSTANTIAL OUTSIDE AIR FOR VENTILATION
SECURELY TAPE ALL JOINTS IN DUCTWORK - IF POSSIBLE AVOID PLACING DUCTWORK IN CRAWL SPACE
IF CRAWL SPACE IS UNVENTED, APPLY RADON CONTROL TECHNIQUES FOR BASEMENTS (SEE FIG. 2-4)
PLACE 6-MIL POLY OVER FLOOR AND SEAL TO WALLS

Figure 3-6: Radon Control Techniques for Crawl Spaces

3.3 Crawl Space Construction Details

In this section several typical crawl space wall sections are illustrated and described. Figure 3-8 shows a typical vented crawl space with insulation placed in the floor joists above the space. In Figure 3-9 insulation placed outside the foundation wall of an unvented crawl space is shown, while Figures 3-10 and 3-11 show insulation placed inside the wall of an unvented crawl space. Included in this group of illustrations are variations in construction systems and approaches to insulating the rim joist area. Numbers that occur within boxes in each drawing refer to the notes on pages 53 and 54 that follow the drawings (see Figure 3-7).

The challenge is to develop integrated solutions that address all key considerations without unnecessarily complicating the construction or increasing the cost. There is no one set of perfect solutions; recommended practices or details often represent trade-offs and compromises. The purpose of this section is to show and describe a variety of reasonable alternatives. Individual circumstances will dictate final design choices.


RIM JOIST
PROTECTION BOARD OR COATING EXTENDS 6 IN. BELOW GRADE 1
8-IN. MIN.
GROUND SLOPES AWAY FROM WALL AT 5% (6" IN 10 FT) 2
7-IN. MIN.

Figure 3-7: System of Key Numbers in Construction Drawings that Refer to Notes on Following Pages

EXAMPLE OF NOTES CORRESPONDING TO CONSTRUCTION DRAWING:

1. Insulation protection: Exterior insulation materials should not be exposed above grade. They should be covered by a protective material — such as exterior grade plastic, fiberglass, galvanized metal or aluminum flashing, a cementitious coating, or a rigid protection board — extending at least 6 inches below grade.

2. Surface drainage: The ground surface should slope downward at least 5 percent (6 inches) over the first 10 feet surrounding the basement wall to direct surface runoff away from the building. Downspouts and gutters should be used to collect roof drainage and direct it away from the foundation walls.

Figure 3-8 illustrates a vented crawl space with a concrete foundation wall. The insulation is placed between the floor joists over the crawl space. The crawl space floor is at the same level as the surrounding grade resulting in no major drainage concerns.


INTERIOR FINISH MATERIAL
EXTERIOR SIDING
VAPOR RETARDER
SHEATHING
INSULATION IN 2 x 4 WALL
SUBFLOOR
RIM JOIST
PRESSURE-TREATED SILL PLATE 11
BATT INSULATION BETWEEN FLOOR JOISTS WITH VAPOR RETARDER ON TOP 20
CRAWL SPACE VENT AT TOP OF FOUNDATION WALL 21
7-IN. MIN.
1/2-IN. ANCHOR BOLTS AT 6 FT. O. C. MAX. 12
24-IN. 17
CONCRETE FOUNDATION WALL 13
CONTINUOUS VAPOR DIFFUSION RETARDER (GROUND COVER) 18
GROUND SLOPES AWAY FROM WALL AT 5% (6" IN 10 FT) 2
CONCRETE FOOTING 8
REINFORCING (OPTIONAL) 19

Figure 3-8: Vented Crawl Space Wall with Ceiling Insulation

Figure 3-9 illustrates an unvented crawl space with a concrete masonry foundation wall. The exterior insulation is covered by a flashing at the top. There is no limit to the thickness of insulation that can be used with this approach. The crawl space floor is below the level of the surrounding grade. A perimeter drainage system is shown.


INTERIOR FINISH MATERIAL
VAPOR RETARDER
EXTERIOR SIDING
INSULATION IN 2 x 4 WALL
SHEATHING
SUBFLOOR
FLASHING COVERS TOP OF INSULATION
CAULKING (OPTIONAL) 9
PROTECTION BOARD, COATING 1
PRESSURE-TREATED SILL PLATE 11
RIGID INSULATION 5
RIM JOIST
GASKET UNDER SILL PLATE
GROUND SLOPES AWAY FROM WALL AT 5% (6" IN 10 FT) 2
8-IN. MIN.
1/2-IN. ANCHOR BOLTS AT 6 FT. O. C. MAX. EMBEDDED 7 TO 15 IN. AS REQUIRED BY CODE 23
LOW PERMEABILITY SOIL (OPTIONAL) 3
FILLED BLOCK CORES OR BOND BEAM 22
24-IN. 17
CONCRETE MASONRY FOUNDATION WALL 14
VAPOR RETARDER 18
DRAINAGE MAT, INSULATING DRAINAGE BOARD, OR GRANULAR BACKFILL (OPTIONAL) 4
FILTER FABRIC ABOVE GRAVEL (OPTIONAL ON SIDES AND BELOW) 6
CONCRETE FOOTING 8
REINFORCING (OPTIONAL) 19
COARSE GRAVEL (OPTIONAL)
4-IN. PERFORATED DRAIN PIPE WITH HOLES FACING DOWN (OPTIONAL) 7

Figure 3-9: Unvented Crawl Space Wall with Exterior Insulation


INTERIOR FINISH MATERIAL
VAPOR RETARDER
EXTERIOR SIDING
INSULATION IN 2 x 4 WALL
SHEATHING
SUBFLOOR
BATT INSULATION
RIM JOIST (OPTIONAL CAULKING ABOVE AND BELOW RIM JOIST) 9
RIGID INSULATION CAULKED AT ALL EDGES FORMS VAPOR RETARDER (OPTIONAL) 10
PRESSURE-TREATED SILL PLATE 11
GROUND SLOPES AWAY FROM WALL AT 5% (6" IN 10 FT) 2
8-IN. MIN.
1/2-IN. ANCHOR BOLTS AT 6 FT. O. C. MAX. 12
LOW PERMEABILITY SOIL (OPTIONAL) 3
RIGID INSULATION 15
24-IN. 17
CONCRETE FOUNDATION WALL 13
VAPOR RETARDER 18
RIGID INSULATION MAY EXTEND HORIZONTALLY ON FLOOR (OPTIONAL)
DRAINAGE MAT, INSULATING DRAINAGE BOARD, OR GRANULAR BACKFILL (OPTIONAL) 4
FILTER FABRIC ABOVE GRAVEL (OPTIONAL ON SIDES AND BELOW) 6
CONCRETE FOOTING 8
REINFORCING (OPTIONAL) 19
COARSE GRAVEL
4-IN. PERFORATED DRAIN PIPE WITH HOLES FACING DOWN (OPTIONAL) 7

Figure 3-10 illustrates an unvented crawl space with a concrete foundation wall. Rigid insulation is placed vertically on the interior. There is no limit to the thickness of insulation that can be used with this approach. The crawl space floor is below the level of the surrounding grade. A perimeter drainage system is shown.

Figure 3-10: Unvented Crawl Space Wall with Interior Insulation

Figure 3-11 illustrates an unvented crawl space with a concrete foundation wall. Batt insulation is placed vertically on the interior wall and extends horizontally onto the perimeter of the floor. The crawl space floor is below the level of the surrounding grade. A perimeter drainage system is shown.


INTERIOR FINISH MATERIAL
VAPOR RETARDER
EXTERIOR SIDING
SHEATHING
INSULATION IN 2 x 4 WALL
SUBFLOOR
BATT INSULATION
RIM JOIST (OPTIONAL CAULKING ABOVE AND BELOW RIM JOIST) 9
VAPOR RETARDER SEALED TO SUBFLOOR AND FLOOR JOISTS 16
PRESSURE-TREATED SILL PLATE 11
GROUND SLOPES AWAY FROM WALL AT 5% (6" IN 10 FT) 2
1/2-IN. ANCHOR BOLTS AT 6 FT. O. C. MAX. 12
8-IN. MIN.
VAPOR RETARDER EXTENDS ABOVE GRADE ON WALL (OPTIONAL) 18
LOW PERMEABILITY SOIL (OPTIONAL) 3
CONCRETE FOUNDATION WALL 13
24-IN. 17
FIBERGLASS INSULATION WITH VAPOR RETARDER ON INSIDE 16
DRAINAGE MAT, INSULATING DRAINAGE BOARD, OR GRANULAR BACKFILL (OPTIONAL) 4
VAPOR RETARDER 18
FILTER FABRIC ABOVE GRAVEL (OPTIONAL ON SIDES AND BELOW) 6
CONCRETE FOOTING 8
REINFORCING (OPTIONAL) 19
COARSE GRAVEL
4-IN. PERFORATED DRAIN PIPE WITH HOLES FACING DOWN (OPTIONAL) 7

Figure 3-11: Unvented Crawl Space Wall with Interior Insulation

NOTES FOR ALL DETAILED CRAWL SPACE DRAWINGS (FIGURES 3-8 THROUGH 3-11)

1. Insulation protection: Exterior insulation materials should not be exposed above grade. The above-grade portion should be covered by a protective material — such as exterior grade plastic, fiberglass, galvanized metal or aluminum flashing, a cementitious coating, or a rigid protection board — extending at least 6 inches below grade.

2. Surface drainage: The ground surface should slope downward at least 5 percent (6 inches) over the first 10 feet surrounding the crawl space wall to direct surface runoff away from the building. Downspouts and gutters should be used to collect roof drainage and direct it away from the foundation walls.

3. Backfill cover: Backfill around the foundation should be covered with a low permeability soil, or a membrane beneath the top layer of soil, to divert surface runoff away from the foundation. (Optional)

4. Backfill or drainage materials: When the crawl space floor is below exterior grade, porous backfill sand or gravel should be used against the walls to promote drainage. Backfill should be compacted so that settlement is minimized. In place of porous backfill, a drainage mat material or insulating drainage board can be placed against the foundation wall. The drainage mat should extend down to a drainpipe at the footing level. (Optional)

5. Exterior insulation materials: Acceptable materials for exterior insulation are: (1) extruded polystyrene boards (XEPS) under any condition, (2) molded expanded polystyrene boards (MEPS) for vertical applications when porous backfill and adequate drainage are provided, and (3) fiberglass or expanded polystyrene drainage boards. The portion above grade could be polyurethane or MEPS.

6. Filter fabric: Where a drainage system is used, a filter fabric over the gravel bed and drainpipe is recommended to prevent clogging of the drainage area with fine soil particles. Wrapping the filter fabric around the entire gravel bed is an optional technique for better protection against clogging.

7. Drainage system: Where porous soils are present and drainage problems are not anticipated, no subdrainage system is necessary. Where conditions warrant and the crawl space floor is below that of the exterior grade, a gravel drainage system should be installed. An optional 4-inch-diameter perforated drainpipe may be installed in the gravel. Perforated drainpipes should be placed with holes facing downward alongside the footing on either the outside or inside. Outside placement is preferred for drainage but inside placement is less susceptible to failure. Drainpipes should slope 1 inch in 20 feet and lead to an outfall or sump. A vertical clean-out pipe with an above-grade capped end is recommended to flush out the system. The pipe should be surrounded by at least 6 inches of gravel on the sides and 4 inches of gravel above and below the pipe. Surface or roof drainage systems should never be connected to the subsurface drainage system. (Optional)

8. Concrete footing: All concrete footings must be designed with adequate size to distribute the load to the soil and be placed beneath the maximum frost penetration depth unless founded upon bedrock or proven non-frost-susceptible soil, or insulated to prevent frost penetration. Concrete used in spread footings should have a minimum compressive strength of 2500 psi.

9. Caulking: Caulking at the following interfaces will minimize air leakage: foundation wall/sill plate, sill plate/rim joist, rim joist/subfloor, subfloor/above-grade wall plate. An alternative is to cover these points on the exterior with an air barrier material. (Optional)

10. Insulation inside rim joist: Insulation can be placed on the inside of the rim joist but with greater risk of condensation problems and less access to wood joists and sills for inspection from the interior. Low permeability rigid insulation (such as extruded polystyrene) should be used, or a vapor retarder should be placed on the inside of the insulation and sealed to all surrounding surfaces.

11. Sill plate: The sill plate should be at least 8 inches above grade and should be pressure-preservative treated to resist decay.

12. Anchor bolts for concrete walls: Anchor bolts should be embedded in the top of concrete foundation walls. Most codes require bolts of 1/2-inch minimum diameter to be embedded at least 7 inches into the wall. Generally, anchor bolts can be placed at a maximum spacing of 6 feet and no further than 1 foot from any corner.

13. Cast-in-place concrete wall: Concrete used in the wall should have a minimum compressive strength of 2500 psi with a 4- to 6-inch slump. No additional water should be added at the job site. Generally, where there are stable soils in areas of low seismic activity, no reinforcing is required in a 6-inch-thick basement wall with up to 4 feet of fill.

14. Masonry wall: Generally, where there are stable soils in areas of low seismic activity, no reinforcing is required in an 8-inch-thick masonry wall with up to 4 feet of fill. When reinforcing is required, it must be grouted into block cores. Vertical bars should be spaced no more than 48 inches apart or 6 times the wall thickness, whichever is less.

15. Interior rigid insulation materials: Acceptable materials for placement inside a crawl space wall include (1) extruded polystyrene boards (XEPS) and (2) expanded polystyrene boards (MEPS). An ignition barrier may be required for some of these materials for fire protection.

16. Interior fiberglass batt insulation: Fiberglass batts can be draped over the wall and laid loosely on the ground at the crawl space perimeter. Special care is necessary to maintain continuity of the vapor retarder on the insulation face. If left exposed the batts should have “low flame spread” facing.

17. Crawl space height: There should be adequate space under all beams, pipes, and ducts to allow a person to access all areas of the crawl space, and especially the perimeter. Leaving adequate space also prevents ventilation from being impeded. Codes and standard practice guides usually call for a minimum of 18 inches between the crawl space floor and the underside of the joists, but this is often inadequate after ducts and plumbing are installed. Instead, a minimum of 24 inches under the joists is advisable. An access way into the crawl space must also be provided.

18. Vapor retarder (ground cover): In regions with 20 inches or more annual precipitation or if radon mitigation is necessary, a 6-mil polyethylene vapor retarder should be placed over the entire crawl space floor. All debris must be removed and the soil leveled before laying the membrane. Edges of the membrane should be lapped 12 inches. No sealing is required for moisture but is suggested for radon mitigation. It is not necessary to carry the ground cover membrane up the face of the wall unless the interior grade is below that outside, or radon is of particular concern. A membrane on the wall helps confine water that may leak through the wall to the underside of the membrane on the floor.

19. Reinforcing in footing: Reinforcing bars placed 2 inches below the top of the footing running parallel to the wall are recommended where differential settlement is a potential problem. (Optional)

20. Ceiling insulation: Insulation is placed in the crawl space ceiling when the space is vented. With fiberglass insulation placed between the wood joists, the vapor retarder should be above the insulation.

21. Vent requirements: A rectangular crawl space requires a minimum of four vents, one on each wall, located no farther than 3 feet from each corner. The vents should be as high on the wall as possible but below the floor insulation to best capture breezes, and landscaping should be planned to prevent obstruction of the vents. The total free (open) area of all vents should be no less than 1/1500 of the floor area. The gross area of vents required depends on the type of vent. In the absence of a ground cover, the vent area should be increased to 1/150 of the floor area. Ventilation alone should not be relied upon where soils are known to be moist.

22. Bond beam on masonry wall: When required by code or a structural engineer, a bond beam provides additional lateral strength in a masonry wall. Using a bond beam or filling the cores of the upper course of block also are recommended as radon and termite prevention techniques. (Optional)

23. Anchor bolts for masonry walls: Anchor bolts should be embedded in the top of masonry foundation walls. Most codes require bolts of 1/2-inch minimum diameter embedded at least 7 inches into the wall. In some locations, codes require bolts to be embedded 15 inches in masonry walls to resist uplift. To provide adequate anchorage in a masonry wall, bolts either must be embedded in a bond beam or the appropriate cores of the upper course of block must be filled with mortar. Generally, anchor bolts can be placed at a maximum spacing of 6 feet and no further than 1 foot from any corner.

3.4 Checklist for Design and Construction of Crawl Space Foundations

This checklist serves as a chapter summary, helps review the completeness of construction drawings and specifications, and provides general guidance on project management. The checklist could be used many ways. For example, use one set of blanks during design and the second set during construction inspection. Note that not all measures are necessary under all conditions. Use different symbols to distinguish items that have been satisfied (+) from those that have been checked but do not apply (x). Leave unfinished items unchecked.

OVERALL

General considerations. Under adverse conditions, crawl spaces should be designed with the same drainage measures as basements. All areas of the crawl space must be accessible for inspection of pipes, ducts, insulation, sill plates, rim joists, posts, etc. A crawl space floor above exterior grade is preferred for positive drainage.

____ ____ Provide access into crawl space
____ ____ Provide clearance under floor structure and ducts to provide access to entire perimeter
____ ____ Call for trenches under girders and ducts to allow passage
____ ____ Use 2-inch slurry slab (vermin control and ground cover protection)
____ ____ Locate footing frost depth with respect to interior for well-vented recessed crawl spaces
____ ____ Consider optional floor drain

SITEWORK

____ ____ Locate building at the highest point if the site is wet
____ ____ Define "finish subgrade" (grading contractor), "base grade" (construction contractor), "rough grade" level before topsoil is respread, "finish grade" (landscape contractor)
____ ____ Establish elevations of finish grades, drainage swales, catch basins, foundation drain outfalls, bulkheads, curbs, driveways, property corners, changes in boundaries
____ ____ Establish grading tolerances
____ ____ Provide intercepting drains upgrade of foundation if needed
____ ____ Locate dry wells and recharge pits below foundation level
____ ____ Establish precautions for stabilizing excavation
____ ____ Establish limits of excavation and determine trees, roots, buried cables, pipes, sewers, etc., to be protected from damage
____ ____ Confirm elevation of water table
____ ____ Determine type and dimensions of drainage systems
____ ____ Discharge roof drainage away from foundation
____ ____ Remove stumps and grubbing debris from site
____ ____ Provide frost heave protection for winter construction
____ ____ Call for test hole (full depth hole in proposed foundation location)
____ ____ Locate stakes and benchmarks
____ ____ Strip and stock pile topsoil
____ ____ Define spoil site

CRAWL SPACE CHECKLIST (PAGE 2 OF 4)

FOOTINGS

____ ____ Position bottom of footing at least 6 inches below frost depth around perimeter (frost wall at garage, slabs supporting roofs, other elements attached to structure). Make sure footing is deeper under basement walkouts
____ ____ Confirm adequacy of footing sizes
____ ____ Do not fill the overexcavated footing trench
____ ____ Install longitudinal reinforcing (two No. 4 or No. 5 bars 2 inches from top)
____ ____ Reinforce footing at spans over utility trenches
____ ____ Do not bear footings partially on rock (sand fill)
____ ____ Do not pour footings on frozen ground
____ ____ Indicate minimum concrete compressive strength after 28 days
____ ____ Call out elevations of top of footings and dimension elevation changes in plan
____ ____ Use keyway or steel dowels to anchor walls
____ ____ Dimension stepped footings according to local codes and good practice (conform to masonry dimensions if applicable)
____ ____ Provide weep holes (minimum 2-inch diameter at 4 feet to 8 feet on center)
____ ____ Provide through-joint flashing as a capillary break

STRUCTURAL DESIGN

General considerations. Walls with high unbalanced fill should be designed as a basement.

Confirm wall engineering and accessories:

____ ____ Wall sized to resist height of fill and seismic loads
____ ____ Anchor bolt requirements for sill plate (minimum code)
____ ____ Anchors for joist ends (typically 6-foot spacing)
____ ____ Beam pocket elevations, dimensions, details
____ ____ Top of wall elevations and changes in wall height
____ ____ Brick shelf widths and elevations

Determine concrete specifications:

____ ____ Minimum compressive strength after 28 days
____ ____ Maximum water/cement ratio. Note: add no water at site
____ ____ Allowable slump
____ ____ Acceptable and unacceptable admixtures
____ ____ Curing requirements (special hot, cold, dry conditions)
____ ____ Two-way reinforcing
____ ____ No. 5 bars at top and bottom of wall to resist settlement cracking (for termite resistance)

Determine concrete masonry wall specifications:

____ ____ Specify mortar mixes and strengths
____ ____ Special details for proprietary masonry systems
____ ____ Use either bond beam or joint reinforcing for crack control (for termite resistance)
____ ____ Use special measures for high termite hazard areas

CRAWL SPACE CHECKLIST (PAGE 3 OF 4)

THERMAL AND VAPOR CONTROLS

General considerations. Vented crawl spaces are insulated in the ceiling, and enclosed crawl spaces are insulated either inside or outside the wall. Ceiling insulation requires insulating ducts and plumbing. Wall insulations require special moisture control measures and may conceal termite infestations. Exterior insulation may reduce condensation hazard at rim joists.

____ ____ Confirm that wall or ceiling insulation R-value meets local codes and/or recommendations provided by this handbook
____ ____ If used, specify exterior insulation product suitable for in-ground use
____ ____ Cover exterior insulation above grade with a protective coating

DECAY AND TERMITE CONTROL

General considerations. Strategy: (1) Isolate wood members from soil by an air space or impermeable barrier; (2) expose critical areas for inspection. Pressure-treated lumber is less susceptible to attack, but is no substitute for proper detailing. Termite shields are not reliable barriers unless installed correctly.

____ ____ Locate and specify foundation vents
____ ____ Install ground cover vapor retarder
____ ____ Elevate interior wood posts on concrete pedestals
____ ____ Locate floor (area) and footing drains if crawl space floor is below exterior grade (see Subdrainage under basement checklist in chapter 2)
____ ____ Pressure-treat wood posts, sill plates, rim joists, wood members in contact with foundation piers, walls, floors, etc.
____ ____ Pressure-treat all outdoor weather-exposed wood members
____ ____ Install dampproof membrane under sill plate and beams in pockets (flashing or sill seal gasket)
____ ____ Leave minimum 1/2-inch air space around beams in beam pockets
____ ____ Expose sill plates and rim joists for inspection
____ ____ Elevate sill plate minimum 8 inches above exterior grade
____ ____ Elevate wood posts and framing supporting porches, stairs, decks, etc., above grade (6-inch minimum) on concrete piers
____ ____ Elevate wood siding, door sills, other finish wood members at least 6 inches above grade (rain splash protection)
____ ____ Separate raised porches and decks from the building by 2-inch horizontal clearance for drainage and termite inspection (or provide proper flashing)
____ ____ Pitch porches, decks, patios for drainage (minimum 1/4 in/ft)
____ ____ Treat soil with termiticide, especially with insulated foundations

CRAWL SPACE CHECKLIST (PAGE 4 OF 4)

RADON CONTROL MEASURES

General considerations. The potential for radon hazard is present in all buildings. Check state and local health agencies for need of protection. Strategies: (1) barriers; (2) air management; (3) provisions to simplify retrofit. Since radon is a gas, its rate of entry through the foundation depends on suction due to stack effect and superstructure air leakage.

____ ____ Separate outdoor intakes for combustion devices
____ ____ Install air barrier wrap around superstructure
____ ____ Seal around flues, chases, vent stacks, attic stairs
____ ____ Install polyethylene vapor retarder as floor underlayment between first floor and crawl space

PLANS, CONTRACTS, AND BUILDING PERMITS

____ ____ Complete plans and specs
____ ____ Bid package
____ ____ Contractual arrangements (describe principals, describe the work by referencing the blueprints and specs, state the start/completion dates, price, payment schedule, handling of change orders, handling of disputes, excavation allowance, and procedure for firing)
____ ____ Building permits

SITE INSPECTIONS DURING CONSTRUCTION

____ ____ After excavation and before concrete is poured for the footings
____ ____ After the footings have been poured before foundation wall construction
____ ____ After foundation construction and dampproofing before rough framing
____ ____ After rough framing
____ ____ After rough plumbing
____ ____ After rough electrical
____ ____ After insulation installation before drywall and backfilling in case of exterior insulation
____ ____ Final

CHAPTER 4

Slab-on-Grade Construction

This chapter summarizes the major recommendations and practices related to slab-on-grade foundation design. Section 4.1 shows typical recommended levels of insulation for each of five representative U.S. climates.

Section 4.2 summarizes design and construction practices covering the following areas: structural aspects, location of insulation, drainage, termite and wood decay control, and radon control. Section 4.3 includes a series of alternative construction details with accompanying notes indicating specific practices. Section 4.4 is a checklist to be used during the design and construction of a slab-on-grade foundation.

4.1 Slab-on-Grade Insulation Placement and Thickness

To provide energy use information for buildings with slab-on-grade foundations, heating and cooling loads were simulated for different insulation placements and thicknesses in a variety of U.S. climates (Labs et al. 1988). Key assumptions are that the interior space above the slab is heated to a temperature of 70^{O}F and cooled to a temperature of 78^{O}F when required.

Insulation Configurations and Costs

Table 4-1 includes illustrations and descriptions of a variety of slab-on-grade insulation configurations. The construction system in all cases is a concrete (or masonry)



Figure 4-1: Slab-on-Grade Foundation with Exterior Insulation

Table 4-1: Insulation Recommendations for Slab-on-Grade Foundations

A: Concrete or Masonry Foundation Wall with Exterior Insulation Placed Vertically

CONFIGURATION	DESCRIPTION	RECOMMENDED CONFIGURATIONS AT THREE FUEL PRICE LEVELS														
		0-2000 HDD (LOS ANG)			2-4000 HDD (FT WORTH)			4-6000 HDD (KAN CITY)			6-8000 HDD (CHICAGO)			8-10000 HDD (MPLS)		
		L	M	H	L	M	H	L	M	H	L	M	H	L	M	H
EXTERIOR VERTICAL 	NO INSULATION	●	●	●	●	○	○	○	○	○	○	○	○	○	○	○
	2 FT DEEP: R-5	○	○	○	○	●	●	●	●	○	●	○	○	●	○	○
	2 FT DEEP: R-10	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	4 FT DEEP: R-5	○	○	○	○	○	○	○	○	○	○	●	○	○	●	○
	4 FT DEEP: R-10	○	○	○	○	○	○	○	○	●	○	○	●	○	○	●
	4 FT DEEP: R-15	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	4 FT DEEP: R-20	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○

B: Concrete or Masonry Foundation Walls with Interior Insulation Placed Vertically

INTERIOR VERTICAL 	NO INSULATION	●	●	●	○	○	○	○	○	○	○	○	○	○	○	○
	2 FT DEEP: R-5	○	○	○	●	●	●	●	●	○	●	○	○	●	○	○
	2 FT DEEP: R-10	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	4 FT DEEP: R-5	○	○	○	○	○	○	○	○	●	○	●	○	○	●	○
	4 FT DEEP: R-10	○	○	○	○	○	○	○	○	○	○	○	●	○	○	●
	4 FT DEEP: R-15	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	4 FT DEEP: R-20	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○

C: Concrete or Masonry Foundation Walls with Interior Insulation Placed Horizontally Under Slab Perimeter

INTERIOR HORIZONTAL 	NO INSULATION	●	●	●	●	○	○	○	○	○	○	○	○	○	○	○
	2 FT WIDE: R-5	○	○	○	○	●	●	●	●	○	●	○	○	○	○	○
	2 FT WIDE: R-10	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	4 FT WIDE: R-5	○	○	○	○	○	○	○	○	●	○	●	○	●	●	○
	4 FT WIDE: R-10	○	○	○	○	○	○	○	○	○	○	○	●	○	○	●

D: Concrete or Masonry Foundation Walls with Exterior Insulation Extending Outward Horizontally

EXTERIOR HORIZONTAL 	NO INSULATION	●	●	●	○	○	○	○	○	○	○	○	○	○	○	○
	2 FT WIDE: R-5	○	○	○	●	●	●	●	●	●	●	●	●	●	●	●
	2 FT WIDE: R-10	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	4 FT WIDE: R-5	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
	4 FT WIDE: R-10	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○

1. L, H, and M refer to the low, medium, and high fuel cost levels indicated in Table 4-2.
2. The darkened circle represents the recommended level of insulation in each column for each of the four basic insulation configurations.
3. These recommendations are based on assumptions that are summarized at the end of section 4.1 and further explained in chapter 5.

Table 4-2: Fuel Price Levels Used to Develop Recommended Insulation Levels in Table 4-1

SEASON	FUEL TYPE	LOW PRICE LEVEL ($)	MEDIUM PRICE LEVEL ($)	HIGH PRICE LEVEL ($)
HEATING	NATURAL GAS	.374 / THERM	.561 / THERM	.842 / THERM
	FUEL OIL	.527 / GALLON	.791 / GALLON	1.187 / GALLON
	PROPANE	.344 / GALLON	.516 / GALLON	.775 / GALLON
COOLING	ELECTRICITY	.051 / KWH	.076 / KWH	.114 / KWH

foundation wall extending either 2 or 4 feet deep with the upper 8 inches of the foundation wall exposed on the exterior.

The three most common approaches to insulating slab-on-grade foundations with concrete / masonry walls are (1) placing insulation vertically on the entire exterior surface of the foundation wall (2 or 4 feet deep), (2) placing insulation vertically on the entire interior surface of the foundation wall (2 or 4 feet deep), and (3) placing insulation horizontally under the slab perimeter (extending 2 or 4 feet). When insulation is placed either vertically or horizontally on the interior, it is important to place insulation in the joint between the slab edge and foundation wall. It is not necessary to place more than R-5 insulation in this joint. For example, even when R-15 insulation is recommended for the foundation wall, only R-5 insulation in the joint proves to be cost-effective.

In addition to these conventional approaches, some cases were simulated where insulation is placed horizontally on the building exterior (extending either 2 or 4 feet into the surrounding soil). In some regions it is common practice to have a shallower footing than 2 feet or have no foundation wall at all—just a thickened slab edge. In these cases, a full 2 feet of vertical insulation is not an option; however, additional horizontal insulation placement on the exterior is possible.

Recommended Insulation Levels

While increasing the amount of foundation insulation produces greater energy savings, the cost of installation must be compared to these savings. Such a comparison can be done in several ways; however, a life cycle cost analysis (presented in worksheet form in chapter 5) is recommended since it takes into account a number of economic variables including installation costs, mortgage rates, HVAC efficiencies, and fuel escalation rates. In order to identify the most economical amount of insulation for the crawl space configurations shown in Table 4-1, the case with the lowest 30-year life cycle cost was determined for five U.S. cities at three different fuel cost levels. See the *Building Foundation Design Handbook* (Labs et al. 1988) to find recommendations for a greater number of cities and for a detailed explanation of the methodology. The economic methodology used to determine the insulation levels in Table 3-1 is consistent with ASHRAE standard 90.2P. The simple payback averages 13 years for all U.S. climate zones, and never exceeds 18 years for any of the recommended levels.

Economically optimal configurations are shown by the darkened circles in Table 4-1 in the following categories: (1) exterior insulation placed vertically on the foundation wall, (2) interior insulation placed vertically on the foundation wall, (3) interior insulation placed horizontally beneath the slab perimeter, and (4) exterior insulation extending outward horizontally from the foundation wall. Configurations are recommended for a range of climates and fuel prices in each of these categories, but the different categories of cases are not directly compared with each other. In other words, there is an optimal amount of exterior vertical insulation recommended for a given climate and fuel price, and there is a different optimal amount of interior insulation placed vertically. Where there is no darkened circle in a particular category, insulation is not economically justified under the assumptions used.

Exterior vertical insulation ranging from R-5 to R-10 is justified in all climate zones except the warmest one. As the climate becomes colder and fuel prices increase, the recommended R-value and depth of insulation increase as well. Similar levels of interior insulation are recommended for both vertical and horizontal placement. For exterior insulation extending outward horizontally, a 2-foot-wide section of R-5 insulation is recommended at all fuel price levels and in all climate zones except the warmest one.

It should be noted that for all cases with interior vertical or horizontal insulation, it is assumed that R-5 insulation is placed in the gap between the slab edge and the foundation wall. A simulation with no insulation in the gap indicates that energy savings are reduced by approximately 40 percent, compared with a similar configuration with the R-5 slab edge insulation in place.

Comparison of Insulation Approaches

When exterior and interior vertical insulation are compared, thermal results are very similar for equivalent amounts of insulation. Since it is assumed that exterior insulation costs more to install, however, interior placement is always economically optimal in comparison. This increased cost for an exterior insulation is attributed to the need for protective covering.

Interior insulation placed horizontally beneath the slab perimeter performs almost identically to interior vertical insulation in terms of energy savings. However, interior vertical insulation is slightly more cost-effective than placement beneath the slab perimeter because the installation cost of the horizontal approach is slightly higher (although not as high as exterior vertical insulation).

Exterior horizontal insulation actually saves more energy for an equivalent amount of insulation compared with the other alternatives; however, it is the least cost-effective approach. In fact, exterior horizontal insulation is not directly comparable to the other cases since it actually requires an extra foot of vertical insulation before it extends horizontally. Thus, costs are higher due to the protective cover as well as the additional amount of material.

In spite of the apparent cost-effectiveness of interior vertical insulation compared with the other approaches, this is only one of many cost and performance issues to be considered. The economic benefit of interior vertical insulation may be offset by other practical, performance, and aesthetic considerations discussed elsewhere in this book.

Assumptions

These general recommendations are based on a set of underlying assumptions. Fuel price assumptions used in this analysis are shown in Table 4-2. The total heating system efficiency is 68 percent and the cooling system SEER is 9.2 with 10 percent duct losses. Energy price inflation and mortgage conditions are selected to allow maximum simple payback of 18 years with average paybacks of about 13 years.

The total installed costs for all insulation systems considered in this analysis are shown in Table 5-2 in chapter 5. Installation costs used in this analysis are based on average U.S. costs in 1987. Costs include labor and materials for extruded polystyrene insulation and the required protective covering and flashing above grade (for the exterior cases). All costs include a 30 percent builder markup and a 30 percent subcontractor markup for overhead and profit.

If the general assumptions used in this analysis are satisfactory for the specific project, the reader can determine the approximate recommended insulation level for a location by finding the heating degree days from Table 5-1 in chapter 5 and selecting the appropriate climate zone and fuel price level shown in Table 4-1. If not, project-specific optimal insulation levels can be determined using actual estimated construction costs with the worksheet provided in chapter 5. The worksheet enables the user to select economic criteria other than allowing maximum simple paybacks of 18 years. In addition, the user can incorporate local energy prices, actual insulation costs, HVAC efficiencies, mortgage conditions, and fuel escalation rates. Cost-effectiveness can vary considerably, depending on the construction details and cost assumptions.

4.2 Recommended Design and Construction Details

STRUCTURAL DESIGN

The major structural components of a slab-on-grade foundation are the floor slab itself and either grade beams or foundation walls with footings at the perimeter of the slab (see Figures 4-2 and 4-3). In some cases additional footings (often a thickened slab) are necessary under bearing walls or columns in the center of the slab. Concrete slab-on-grade floors are generally designed to have sufficient strength to support floor loads without reinforcing when poured on undisturbed or compacted soil. The proper use of welded wire fabric and concrete with a low water/cement ratio can reduce shrinkage cracking, which is an important concern for appearance and for reducing potential radon infiltration.

Foundation walls are typically constructed of cast-in-place concrete or concrete masonry units. Foundation walls must be designed to resist vertical loads from the structure above and transfer these loads to the footing. Concrete spread footings must provide support beneath foundation walls and columns. Similarly, grade beams at the edge of the foundation support the superstructure above. Footings must be designed with adequate bearing area to distribute the load to the soil and be placed beneath the maximum frost penetration depth or be insulated to prevent frost penetration.

Where expansive soils are present or in areas of high seismic activity, special foundation construction techniques may be necessary. In these cases, consultation with local building officials and a structural engineer is recommended.

DRAINAGE AND WATERPROOFING

Good surface drainage techniques are always recommended for slab-on-grade foundations (see Figure 4-4). The goal of surface drainage is to keep water away from the foundation by sloping the ground surface and using gutters and downspouts for roof drainage. Because a slab-on-grade floor is above the surrounding exterior grade, no


SLAB SUPPORTS FLOOR LOAD
ANCHOR BOLT CONNECTS FOUNDATION WALL TO SUPERSTRUCTURE AND RESISTS WIND UPLIFT
GRADE BEAM DISTRIBUTES VERTICAL LOAD FROM ABOVE-GRADE STRUCTURE TO GROUND

Figure 4-2: Structural Components of Slab-on-Grade Foundation with Grade Beam


SLAB SUPPORTS FLOOR LOAD
ANCHOR BOLT CONNECTS FOUNDATION WALL TO SUPERSTRUCTURE AND RESISTS WIND UPLIFT
WALL RESISTS VERTICAL LOAD FROM ABOVE-GRADE STRUCTURE
SPREAD FOOTING DISTRIBUTES VERTICAL LOAD TO GROUND
FOOTING MUST BE BELOW MAXIMUM FROST PENETRATION DEPTH

Figure 4-3: Structural Components of Slab-on-Grade Foundation with Stem Wall and Footing

subsurface drainage system or waterproofing is required. On sites with a high water table, the floor should be raised above existing grade as much as possible and a layer of gravel can be placed beneath the slab to ensure that drainage occurs and moisture problems are avoided.

LOCATION OF INSULATION

Good construction practice demands elevating the slab above grade by no less than 8 inches to isolate the wood framing from rain splash, soil dampness, and termites, and to keep the subslab drainage layer above the surrounding ground. The most intense heat losses are through this small area of foundation wall above grade, so it requires special care in detailing and installation. Heat is also lost from the slab to the soil, through which it migrates to the exterior ground surface and the air. Heat losses to the soil are greatest at the edge, and diminish rapidly with distance from it. Both components of the slab heat loss — at the edge and through the soil — must be considered in designing the insulation system.

Insulation can be placed vertically outside the foundation wall or grade beam. This approach effectively insulates the exposed slab edge above grade and extends down to reduce heat flow from the floor slab to the ground surface outside the building. Vertical exterior insulation is the only method of reducing heat loss at the edge of an integral grade beam and slab foundation. A major advantage of exterior insulation is that the interior joint between the slab and foundation wall need not be insulated, which simplifies construction. Several drawbacks, however, are that rigid insulation should be covered above grade with a protective board, coating, or flashing material, and with brick facings, a thermal short can be created that bypasses both the foundation and above-grade insulation. A limitation is that the depth of the exterior insulation is controlled by the footing depth. Additional exterior insulation can be provided by extending insulation horizontally from the foundation wall. Since this approach can control frost penetration near the footing, it can be used to reduce footing depth requirements under certain circumstances. This can substantially reduce the initial foundation construction cost.

Insulation also can be placed vertically on the interior of the foundation wall or horizontally under the slab. In both cases, heat loss from the floor is reduced and the difficulty of placing and protecting exterior insulation is avoided. Interior vertical insulation is limited to the depth of the footing but underslab insulation is not limited in this respect. Usually the outer 2 to 4 feet of the slab perimeter is insulated but the entire floor may be insulated if desired.

It is essential to insulate the joint between the slab and the foundation wall whenever insulation is placed inside the foundation wall or under the slab. Otherwise, a significant amount of heat transfer occurs through the thermal bridge at the slab edge.


SURFACE DRAINAGE TECHNIQUES:
- SLOPE GROUND AWAY
- USE GUTTERS AND DOWNSPOUTS
GRAVEL DRAINAGE LAYER RECOMMENDED BENEATH SLAB IF A HIGH WATER TABLE IS PRESENT
NO SUBSURFACE DRAINAGE REQUIRED

Figure 4-4: Drainage Techniques for Slab-on-Grade Foundations

The insulation is generally limited to no more than 1 inch in thickness at this point. Both the American Concrete Institute (1985) and the Building Research Advisory Board (1968) recommend against pouring the slab on a shelf formed in the foundation wall, regardless of whether or not the joint is insulated or an expansion joint is provided.

A solution to designing this floor / wall joint is shown in Figure 4-10 for a cast-in-place concrete foundation wall. The notched wall section permits 1 inch of rigid insulation to be placed in the joint and also permits the slab to move vertically. This detail can be used for vertical interior or subslab insulation. Concrete masonry foundation walls are more difficult to resolve successfully. Figures 4-14 and 4-15 illustrate two solutions. The detail in Figure 4-14 uses a 6-inch-thick block on the top course that permits insulation in the joint and vertical movement of the slab. This detail is designed for a 2-by-6 above-grade wall. In Figure 4-15 a similar detail with a 2-by-4 above-grade wall on a 4-inch-thick block on the top course is shown. This last alternative effectively provides insulation in the joint but diverges from ideal structural practice. The slab rests on a ledge and becomes thinner near the insulated edge.

Another option for insulating a slab-on-grade foundation is to place insulation above the floor slab. A wood floor deck can be placed on sleepers, leaving cavities that can be filled with rigid board or batt insulation, or a wood floor deck can be placed directly on rigid insulation above the slab. This approach avoids some of the construction detail problems inherent in the more conventional approaches discussed above, but may lead to greater frost depth in the vicinity of the slab edge.


PRESSURE-PRESERVATIVE
TREATED SILL PLATE
8-IN. MIN. ABOVE GRADE
WOOD SIDING 6-IN. MIN.
ABOVE GRADE
FILL JOINT WITH CAULKING
REMOVE ROOTS, TRUNKS,
AND SCRAP WOOD FROM
FOUNDATION AREA
BOND BEAM, CAP
BLOCK, OR FILLED
UPPER COURSE
OF MASONRY WALL
TREAT SOIL
FOR TERMITES
MINIMIZE SOIL MOISTURE
USING SURFACE
DRAINAGE TECHNIQUES
- USE GUTTERS AND
DOWNSPOUTS
- SLOPE GROUND AWAY

Figure 4-5: Termite Control Techniques for Slab-on-Grade Foundations

TERMITE AND WOOD DECAY CONTROL TECHNIQUES

Techniques for controlling the entry of termites through residential foundations are necessary in much of the United States (see Figure 4-5). Consult with local building officials and codes for further details.

1. Minimize soil moisture around the foundation by surface drainage and by using gutters, downspouts, and runouts to remove roof water.

2. Remove all roots, stumps, and wood from the site. Wood stakes and form work should also be removed from the foundation area.

3. Treat soil with termiticide on all sites vulnerable to termites (Labs et al. 1988).

4. Place a bond beam or course of solid cap blocks on top of all concrete masonry foundation walls to ensure that no open cores are left exposed. Alternatively, fill all cores on the top course with mortar. The mortar joint beneath the top course or bond beam should be reinforced for additional insurance.

5. Place the sill plate at least 8 inches above grade; it should be pressure-preservative treated to resist decay. Since termite shields are often damaged or not installed carefully enough, they are considered optional and should not be regarded as sufficient defense by themselves.

6. Be sure that exterior wood siding and trim are at least 6 inches above grade.

7. Construct porches and exterior slabs so that they slope away from the foundation wall, are reinforced with steel or wire mesh, usually are at least 2 inches below exterior siding, and are separated from all wood members by a 2-inch gap visible for inspection or a continuous metal flashing soldered at all seams.


SEAL AROUND ALL DUCTS AND PIPES IN SLAB
USE SOLID DRAINPIPES IN FLOOR WITH MECHANICAL TRAPS
BOND BEAM, CAP BLOCK, OR FILLED UPPER COURSE OF MASONRY WALL
FILL JOINT WITH CAULKING
REINFORCE SLAB AND USE CONCRETE WITH LOW WATER/ CEMENT RATIO TO REDUCE CRACKING
6-MIL POLY LAYER UNDER SLAB EXTENDED OVER TOP OF FOUNDATION WALL

Figure 4-6: Radon Control Techniques for Slab-on-Grade Foundations

8. Fill the joint between a slab-on-grade floor and foundation wall with liquid-poured urethane caulk or coal tar pitch to form a termite and radon barrier.

RADON CONTROL TECHNIQUES

The following techniques for minimizing radon infiltration through a slab-on-grade foundation are appropriate where there is a reasonable probability that radon may be present (see Figure 4-6). To determine this, contact the state health department or environmental protection office.

1. Use solid pipes for floor discharge drains to daylight or provide mechanical traps if they discharge to subsurface drains.

2. Lay a 6-mil polyethylene film on top of the gravel drainage layer beneath the slab. This film serves both as a radon and moisture retarder. Slit an “x” in the polyethylene membrane at penetrations. Turn up the tabs and tape them. Care should be taken to avoid unintentionally puncturing the barrier; consider using riverbed gravel if available at a reasonable price. The round riverbed gravel allows for freer movement of the soil gas and has no sharp edges to penetrate the polyethylene. The edges should be lapped at least 12 inches. The polyethylene should extend over the top of the foundation wall, or extend to the outer bottom edge of a monolithic slab-grade beam or patio. Use concrete with a low water/cement ratio to minimize cracking. A 2-inch-thick sand layer on top of the polyethylene improves concrete curing and prevents the concrete from infiltrating the aggregate base under the slab. The sand should be dampened, but not saturated, before the concrete is poured. The sand will also offer some puncture protection for the polyethylene during the concrete pouring operation.

3. Provide an isolation joint between the foundation wall and slab floor where vertical movement is expected. After the slab has cured for several days, seal the joint by pouring polyurethane or similar caulk into the 1/2-inch channel formed with a removable strip. Polyurethane caulks adhere well to masonry and are long-lived. They do not stick to polyethylene. Do not use latex caulks.

4. Install welded wire in the slab to reduce the impact of shrinkage cracking. Consider control joints or additional reinforcing near the inside corner of "L" shaped slabs. Two pieces of No. 4 reinforcing bar, 3 feet long and on 12-inch centers, across areas where additional stress is anticipated, should reduce cracking. Use of fibers within concrete will also reduce the amount of plastic shrinkage cracking.

5. Control joints should be finished with a 1/2-inch depression. Fill this recess fully with polyurethane or similar caulk.

6. Minimize the number of pours to avoid cold joints. Begin curing the concrete immediately after the pour, according to recommendations of the American Concrete Institute (1980; 1983). At least three days are required at 70^{O}F, and longer at lower temperatures. Use an impervious cover sheet or wetted burlap.

7. Form a gap of at least 1/2-inch width around all plumbing and utility lead-ins through the slab to a depth of at least 1/2 inch. Fill with polyurethane or similar caulking.

8. Place HVAC condensate drains so that they run to daylight outside the building envelope. Condensate drains that connect to dry wells or other soil may become direct conduits for soil gas, and can be a major entry point for radon.

9. Place a solid brick course, bond beam, or cap block on top of all masonry foundation walls to seal cores, or fill open block cores in the top course with concrete. An alternative approach is to leave the masonry cores open and fill solid at the time the floor slab is cast by flowing concrete into the top course of block.

Intercepting Soil Gas

At this time the best strategy for mitigating radon hazard seems to be to reduce stack effects by building a tight foundation in combination with a generally tight above-grade structure, and to make sure a radon collection system and, at the very least, provisions for a discharge system are an integral part of the initial construction. This acts as an insurance policy at modest cost. Once the house is built, if radon levels are excessive, a passive discharge system can be connected and if further mitigation effort is needed, the system can be activated by installing an in-line duct fan (see Figure 4-7).

Subslab depressurization has proven to be an effective technique for reducing radon concentrations to acceptable levels, even in homes with extremely high concentrations (Dudney 1988). This technique lowers the pressure around the foundation envelope, causing the soil gas to be routed into a collection system, avoiding the inside spaces and discharging to the outdoors. This system could be installed in two phases. The first phase is the collection system located on the soil side of the foundation, which should be installed during construction. The collection system, which may consist of nothing more than 4 inches of gravel beneath the slab floor, can be installed at little or no additional cost in new construction. The second phase is the discharge system, which could be installed later if necessary.

A foundation with good subsurface drainage already has a collection system. The underslab gravel drainage layer can be used to collect soil gas. It should be at least 4 inches thick, and of clean aggregate no less than 1/2 inch in diameter. Weep holes provided through the footing or gravel bed extending beyond the foundation wall will help assure good air communication between the foundation perimeter soil and the underside of the slab. The gravel should be covered with a 6-mil polyethylene radon and moisture retarder, which in turn could be covered with a 2-inch sand bed.

A 3- or 4-inch diameter PVC 12-inch section of pipe should be inserted vertically into the subslab aggregate and capped at the top. Stack pipes could also be installed horizontally through below-grade walls to the area beneath adjoining slabs. A single standpipe is adequate for typical house-size floors with a clean, coarse gravel layer. If necessary, the standpipe can be uncapped and connected to a vent pipe. The standpipe can also be added by drilling a 4-inch hole through the finished slab. The standpipe should be positioned for easy routing to the roof through plumbing chases, interior walls, or closets. Note, however, that it is normally less costly to complete the vent stack routing through the roof during construction than to install or complete the vent stack after the building is finished. Connecting the vent pipe initially without the fan provides a passive depressurization system which may be adequate in some cases and could be designed for easy modification to an active


ROOF VENT FOR
SOIL GAS DISCHARGE
DISCHARGE FAN
LOCATED IN ATTIC
RISER PIPE FROM
AREA UNDER SLAB
STANDPIPES CAN
BE CAPPED FOR
FUTURE USE
SUCTION TAP
CAST IN SLAB
CONCRETE SLAB
OVER POLY
VAPOR BARRIER
GRAVEL
DRAINAGE LAYER

Figure 4-7: Soil Gas Collection and Discharge Techniques

system if necessary.

A subslab depressurization system requires the floor slab to be nearly airtight so that collection efforts are not short-circuited by drawing excessive room air down through the slab and into the system. Cracks, slab penetrations, and control joints must be sealed. Floor drains that discharge to the gravel beneath the slab should be avoided, but when used, should be fitted with a mechanical trap capable of providing an airtight seal.

It is desirable to avoid dependence on a continuously operating fan. Ideally, a passive depressurization system should be installed, radon levels tested and, if necessary, the system activated by adding a fan. Active systems use quiet, in-line duct fans to draw gas from the soil. The fan should be located in an accessible section of the stack so that any leaks from the positive pressure side of the fan are not in the living space. The fan should be oriented to prevent accumulation of condensed water in the fan housing. The stack should be routed up through the building and extend 2 to 4 feet above the roof. It can also be carried out through the band joist and up along the outside of wall, to a point at or above the eave line. The exhaust should be located away from doors and windows to avoid re-entry of the soil gas into the above-grade space.

A fan capable of maintaining 0.2 inch of water suction under installation conditions is adequate for serving subslab collection systems for most houses (Labs 1988). This is often achieved with a 0.03 hp (25W), 160 cfm centrifugal fan (maximum capacity) capable of drawing up to 1 inch of water before stalling. Under field conditions of 0.2 inch of water, such a fan operates at about 80 cfm.

It is possible to test the suction of the subslab system by drilling a small (1/4-inch) hole in an area of the slab remote from the collector pipe or suction point, and measuring the suction through the hole. A suction of 5 Pascals is considered satisfactory. The hole must be sealed after the test.

Active subslab depressurization does raise some long-term concerns which at this time are not fully understood. If the radon barrier techniques are not fully utilized along with the subslab depressurization, considerable indoor air could be discharged, resulting in a larger than expected energy penalty. System durability is of concern, particularly motor-driven components. This system is susceptible to owner interference.

4.3 Slab-on-Grade Construction Details

In this section, typical slab-on-grade foundation details are illustrated and described. Figure 4-9 shows exterior insulation applied to a grade beam foundation. A grade beam supporting a brick veneer facade is shown in Figure 4-10 with exterior insulation. Insulation applied to the exterior of concrete and concrete masonry foundation walls is shown in Figures 4-11 and 4-12. Figure 4-13 illustrates insulation placed beneath the slab perimeter. The inside insulation case is illustrated for masonry foundation walls in Figures 4-14 and 4-15. A foundation wall supporting a brick veneer facade is shown in Figure 4-16 with interior insulation. Numbers that occur within boxes in each drawing refer to the notes on page 75 that follow the drawings (see Figure 4-8).

The challenge at this stage of design is to develop integrated solutions that address all key considerations without significantly complicating the construction or increasing the cost. There is no one set of perfect solutions; recommended practices or details often represent compromises and trade-offs. No particular approach is considered superior in all cases. This section shows and describes a variety of reasonable alternatives. Individual circumstances will dictate final design choices.



Figure 4-8: System of Key Numbers in Construction Drawings that Refer to Notes on Following Pages

EXAMPLE OF NOTES CORRESPONDING TO CONSTRUCTION DRAWING:

11. Isolation joint: An isolation joint should be provided at the slab edge to permit independent movement without cracking. Where radon is a concern, a liquid sealant should be poured into the joint over a foam backing rod.

12. Concrete slab: A minimum slab thickness of 4 inches is recommended using concrete with a minimum compressive strength of 2500 psi. Welded wire fabric placed 2 inches below the slab surface is recommended to control shrinkage cracks. Generally, concrete slabs should not rest on footings or ledges of foundation walls if possible to avoid cracking due to settlement. If a slab is poured over an impermeable vapor retarder or insulation board, a concrete mixture with a low water/cement ratio is recommended. An alternative technique is to pour the slab on a layer of sand or drainage board above the vapor retarder to minimize cracking.


EXTERIOR SIDING
RIGID INSULATION USED AS SHEATHING EXTENDS DOWN TO COVER GRADE BEAM 6
PRESSURE-TREATED SILL PLATE (GASKET UNDER SILL PLATE) 1
TERMITE SHIELD
PROTECTION BOARD OR COATING 2
GROUND SLOPES AWAY FROM WALL AT 5% 3
8-IN. MIN.
RIGID INSULATION MAY EXTEND HORIZONTALLY INTO THE SOIL, SLOPING AWAY FROM SLAB EDGE
REINFORCING (OPTIONAL) 9
INTERIOR FINISH MATERIAL
VAPOR RETARDER
INSULATON IN 2 x 4 WALL
4-IN. CONCRETE SLAB WITH OPTIONAL W.W. MESH 12
VAPOR RETARDER 13
4-IN. GRAVEL LAYER (OPTIONAL) 14
CONCRETE GRADE BEAM 10
SILL ANCHORS AT 6 FT. O. C. MAX. 4

Figure 4-9: Slab-on-Grade with Integral Grade Beam (Exterior Insulation)

Figure 4-9 illustrates a slab-on-grade foundation with an integral grade beam. The rigid insulation is placed vertically on the exterior face of the grade beam. Additional insulation may be extended horizontally around the foundation perimeter.


BRICK VENEER
1-IN. AIRSPACE
RIGID INSULATION
PRESSURE-TREATED SILL PLATE (GASKET UNDER SILL PLATE) 1
OPENING IN EVERY OTHER VERTICAL JOINT
FLASHING
GROUND SLOPES AWAY FROM WALL AT 5% 3
1/2-IN. ANCHOR BOLTS AT 6 FT. O.C. MAX. 4
RIGID INSULATION 6
INSULATED BLOCK SUPPORT FOR BRICK VENEER
INTERIOR FINISH MATERIAL
INSULATION IN 2 x 4 WALL
4-IN. CONCRETE SLAB WITH OPTIONAL W.W. MESH 12
VAPOR RETARDER 13
4-IN. GRAVEL LAYER (OPTIONAL) 14
REINFORCING (OPTIONAL) 9
CONCRETE GRADE BEAM 10

Figure 4-10: Slab-on-Grade with Brick Veneer (Exterior Insulation)

Figure 4-10 illustrates a slab-on-grade foundation with an integral grade beam. This differs from Figure 4-9 in that the above grade wall is wood frame with brick veneer. The rigid insulation is placed vertically on the exterior face of the grade beam and extends upward into the cavity between the wood frame wall and the brick veneer.

Figure 4-11 illustrates a slab-on-grade with a concrete foundation wall. Rigid insulation is placed vertically on the exterior face of the foundation wall. The 2 x 6 above-grade wood frame wall overhangs the insulation. The foundation wall is designed to permit vertical movement of the floor slab.


EXTERIOR SIDING
SHEATHING
PRESSURE-TREATED SILL PLATE (GASKET UNDER SILL PLATE) 1
PROTECTION BOARD OR COATING 2
GROUND SLOPES AWAY FROM WALL AT 5% 3
8-IN. MIN.
1/2-IN. ANCHOR BOLTS AT 6 FT. O.C. MAX. 4
RIGID INSULATION 6
CONCRETE FOUNDATION WALL 7
CONCRETE FOOTING 10
INTERIOR FINISH MATERIAL
VAPOR RETARDER
INSULATION IN 2 x 6 WALL
ISOLATION JOINT 11
4-IN. CONCRETE SLAB WITH OPTIONAL W.W. MESH 12
2-IN. SAND LAYER (OPTIONAL) 12
VAPOR RETARDER 13
4-IN. GRAVEL LAYER (OPTIONAL) 14
REINFORCING (OPTIONAL) 9

Figure 4-11: Slab-on-Grade with Concrete Wall (Exterior Insulation)

Figure 4-12 illustrates a slab-on-grade foundation with a concrete masonry foundation wall. Rigid insulation is placed vertically on the exterior face of the foundation wall. The top of the insulation is covered by flashing. Because the floor slab rests on the ledge of the foundation wall, it is important to compact the soil beneath the slab to minimize settlement and cracking of the slab.


EXTERIOR SIDING
SHEATHING
PRESSURE-TREATED SILL PLATE (GASKET UNDER SILL PLATE) 1
FLASHING COVERS TOP OF INSULATION
PROTECTION BOARD OR COATING 2
GROUND SLOPES AWAY FROM WALL AT 5% 3
8-IN. MIN.
1/2-IN. ANCHOR BOLTS AT 6 FT. O.C. MAX. EMBEDDED 15 IN. INTO FILLED CORES 5
RIGID INSULATION OVER CONCRETE MASONRY WALL 6 8
INTERIOR FINISH MATERIAL
VAPOR RETARDER
INSULATION IN 2 x 4 WALL
ISOLATION JOINT 11
4-IN. CONCRETE SLAB WITH OPTIONAL W.W. MESH 12
VAPOR RETARDER 13
4-IN. GRAVEL LAYER (OPTIONAL) 14
REINFORCING (OPTIONAL) 9
CONCRETE FOOTING 10

Figure 4-12: Slab-on-Grade with Masonry Wall (Exterior Insulation)


EXTERIOR SIDING
SHEATHING
INSULATION IN 2 x 6 WALL
PRESSURE-TREATED SILL PLATE (GASKET UNDER SILL PLATE) 1
GROUND SLOPES AWAY FROM WALL AT 5% 3
8-IN. MIN.
1/2-IN. ANCHOR BOLTS AT 6 FT. O.C. MAX.
CONCRETE FOUNDATION WALL 7
CONCRETE FOOTING 10
INTERIOR FINISH MATERIAL
VAPOR RETARDER
RIGID INSULATION IN JOINT 11
4-IN. CONCRETE SLAB WITH OPTIONAL W.W. MESH 12
2-IN. SAND LAYER (OPTIONAL) 12
VAPOR RETARDER 13
RIGID INSULATION 15
4-IN. GRAVEL LAYER (OPTIONAL) 14
REINFORCING (OPTIONAL) 9

Figure 4-13: Slab-on-Grade with Concrete Wall (Insulation Under Slab)

Figure 4-13 illustrates a slab-on-grade with a concrete foundation wall. Rigid insulation is placed horizontally under the slab perimeter and vertically in the joint at the slab edge. An optional sand layer beneath the slab is shown. The foundation wall is designed to permit vertical movement of the floor slab.


EXTERIOR SIDING
SHEATHING
INSULATION IN 2 x 6 WALL
PRESSURE-TREATED SILL PLATE (GASKET UNDER SILL PLATE) 1
6-IN. CONCRETE BLOCK ON 8-IN. CONCRETE MASONRY WALL 8
GROUND SLOPES AWAY FROM WALL AT 5% 3
8-IN. MIN.
1/2-IN. ANCHOR BOLTS AT 6 FT. O.C. MAX. EMBEDDED 15 IN. INTO FILLED CORES 5
INTERIOR FINISH MATERIAL
VAPOR RETARDER
RIGID INSULATION JOINT 11
4-IN. CONCRETE SLAB WITH OPTIONAL W.W. MESH 12
VAPOR RETARDER 13
RIGID INSULATION 15
4-IN. GRAVEL LAYER (OPTIONAL) 14
REINFORCING (OPTIONAL) 9
CONCRETE FOOTING 10

Figure 4-14: Slab-on-Grade with Masonry Wall (Insulation Under Slab)

Figure 4-14 illustrates a slab-on-grade with a concrete masonry foundation wall. Rigid insulation is placed horizontally under the slab perimeter and vertically in the joint at the slab edge. In order to permit vertical movement of the floor slab, 6-inch wide concrete blocks are used in the top course. This approach utilizes a 2 x 6 above-grade wood frame wall.

Figure 4-15 illustrates a slab-on-grade foundation with a concrete masonry foundation wall. Rigid insulation is placed vertically on the interior face of the foundation wall and extends into the joint at the slab edge. Because the floor slab rests on the ledge of the foundation wall, it is important to compact the soil beneath the slab to minimize settlement and cracking of the slab. This approach utilizes a 2 x 4 above-grade wood frame wall.


EXTERIOR SIDING
SHEATHING
INSULATION IN 2 x 4 WALL
PRESSURE-TREATED SILL PLATE (GASKET UNDER SILL PLATE) 1
GROUND SLOPES AWAY FROM WALL AT 5% 3
8-IN. MIN.
1/2-IN. ANCHOR BOLTS AT 6 FT. O.C. MAX. EMBEDDED 15 IN. INTO FILLED CORES 5
CONCRETE MASONRY WALL 8
INTERIOR FINISH MATERIAL
VAPOR RETARDER
RIGID INSULATION JOINT 11
4-IN. CONCRETE SLAB WITH OPTIONAL W.W. MESH 12
VAPOR RETARDER 13
4-IN. GRAVEL LAYER (OPTIONAL) 14
RIGID INSULATION 16
REINFORCING (OPTIONAL) 9
CONCRETE FOOTING 10

Figure 4-15: Slab-on-Grade with Masonry Wall (Interior Insulation)

Figure 4-16 illustrates a slab-on-grade with a concrete foundation wall. The approach above-grade wall system consists of a 2 x 4 wood frame wall with brick veneer. Rigid insulation is placed horizontally under the slab perimeter and vertically in the joint at the slab edge. Because the floor slab rests on the ledge of the foundation wall, it is important the compact the soil beneath the slab to minimize settlement and cracking of the slab.


BRICK VENEER
1-IN. AIRSPACE
SHEATHING
PRESSURE-TREATED SILL PLATE (GASKET UNDER SILL PLATE) 1
OPENING IN EVERY OTHER VERTICAL JOINT
FLASHING
GROUND SLOPES AWAY FROM WALL AT 5% 3
1/2-IN. ANCHOR BOLTS AT 6 FT. O.C. MAX. 4
6-IN. BLOCK SUPPORT FOR BRICK VENEER
CONCRETE FOUNDATION WALL 7
INTERIOR FINISH MATERIAL
INSULATION IN 2 x 4 WALL
RIGID INSULATION IN JOINT 11
4-IN. CONCRETE SLAB WITH OPTIONAL W.W. MESH 12
VAPOR RETARDER 13
RIGID INSULATION 15
4-IN. GRAVEL LAYER (OPTIONAL) 14
REINFORCING (OPTIONAL) 9
CONCRETE FOOTING 10

Figure 4-16: Slab-on-Grade with Brick Veneer (Insulation Under Slab)

NOTES FOR ALL DETAILED SLAB-ON-GRADE DRAWINGS (FIGURES 4-9 THROUGH 4-16)

1. Sill plate: The sill plate should be at least 8 inches above grade and pressure-preservative treated to resist decay.

2. Insulation protection: Exterior insulation materials should not be exposed above grade. The above-grade material should be covered by a protective material — such as exterior grade plastic, fiberglass, galvanized metal or aluminum flashing, or a cementitious coating — extending at least 6 inches below grade.

3. Surface drainage: The ground surface should slope downward at least 5 percent (6 inches) over the first 10 feet surrounding the foundation edge to direct surface runoff away from the building. Downspouts and gutters should be used to collect roof drainage and direct it away from the foundation walls.

4. Anchor bolts for concrete walls: Anchor bolts should be embedded in the top of concrete foundation walls. Most codes require bolts of 1/2-inch minimum diameter to be embedded at least 7 inches into the wall. Generally, anchor bolts can be placed at a maximum spacing of 6 feet and no further than 1 foot from any corner.

5. Anchor bolts for masonry walls: Anchor bolts should be embedded in the top of masonry foundation walls. Most codes require bolts of 1/2-inch minimum diameter embedded at least 7 inches into the wall. In some locations, codes require bolts to be embedded 15 inches in masonry walls to resist uplift. To provide adequate anchorage in a masonry wall, bolts either must be embedded in a bond beam or the appropriate cores of the upper course of block must be filled with mortar. Anchor bolts can be placed at a maximum spacing of 6 feet and no further than 1 foot from any corner.

6. Exterior insulation materials: Acceptable materials for exterior foundation insulation are: (1) extruded polystyrene boards (XEPS) under any condition, (2) molded expanded polystyrene boards (MEPS) for vertical applications when porous backfill and adequate drainage are provided, and (3) fiberglass or polystyrene drainage boards when installed with an appropriate drainage system.

7. Cast-in-place concrete wall: Concrete used in the wall should have a minimum compressive strength of 2500 psi with a 4- to 6-inch slump. No additional water should be added at the job site. Generally, where there are stable soils and low seismic activity, no reinforcing is required.

8. Concrete/masonry wall: Generally, where there are stable soils and in areas of low seismic activity, no reinforcing is required.

9. Crack control reinforcing in footing: Reinforcing bars placed 2 inches below the top of the footing or 2 inches above the bottom of the grade beam, running parallel to the wall, are recommended where differential settlement is a potential problem. (Optional)

10. Concrete footings or grade beams: Concrete footings or grade beams should be designed to distribute the load to the soil and be placed beneath the maximum frost penetration depth unless founded on bedrock or proven non-frost-susceptible soil, or insulated to prevent frost penetration. Concrete should have a minimum compressive strength of 2500 psi.

11. Isolation joint: An isolation joint should be provided at the slab edge to permit independent movement without cracking. Where radon is a concern, a liquid sealant should be poured into the joint over a foam backing rod.

12. Concrete slab: A minimum slab thickness of 4 inches is recommended using concrete with a minimum compressive strength of 2500 psi. Welded wire fabric placed 2 inches below the slab surface is recommended to control shrinkage cracks. Generally, concrete slabs should not rest on footings or ledges of foundation walls if possible to avoid cracking due to settlement. If a slab is poured directly over an impermeable vapor retarder or insulation board, a concrete mixture with a low water/cement ratio is recommended. An alternative technique is to pour the slab on a layer of sand or drainage board material above the vapor retarder to minimize cracking.

13. Vapor retarder: A 6-mil polyethylene vapor retarder should be placed beneath the slab to reduce moisture transmission and radon infiltration into the building.

14. Gravel layer under slab: A 4-inch compacted gravel layer should be placed under the concrete floor slab for drainage unless local conditions have proven this to be unnecessary. (Optional)

15. Insulation under the slab: Acceptable materials for underslab insulation are: (1) extruded polystyrene boards (XEPS) under any condition, (2) molded expanded polystyrene boards (MEPS) when the compressive strength is sufficient and adequate drainage is provided, and (3) insulating drainage boards with sufficient compressive strength.

16. Interior rigid insulation materials: Acceptable materials for placement inside a foundation wall include (1) extruded polystyrene boards (XEPS) and (2) expanded polystyrene boards (MEPS).

4.4 Checklist for Design and Construction of Slab-on-Grade Foundations

This checklist serves as a chapter summary, helps review the completeness of construction drawings and specifications, and provides general guidance on project management. The checklist could be used many ways. For example, use one set of blanks during design and the second set during construction inspection. Note that not all measures are necessary under all conditions. Use different symbols to distinguish items that have been satisfied (+) from those that have been checked but do not apply (x). Leave unfinished items unchecked.

OVERALL SLAB CONSTRUCTION

General considerations. Slab floors require advance planning for plumbing and electrical service. They generally minimize moisture and radon hazard but make detection of termite intrusions especially difficult. Expansive soils require special measures.

____ ____ Elevate slab above existing grade
____ ____ Provide minimum 4-inch-thick aggregate drainage layer under slab
____ ____ Locate plumbing to be cast in slab
____ ____ Locate electrical service to be cast in slab
____ ____ Locate gas service to be cast in slab

SITEWORK

____ ____ Locate building at the highest point if the site is wet
____ ____ Define “finish subgrade” (grading contractor), “base grade” (construction contractor), “rough grade” level before topsoil is respread, “finish grade” (landscape contractor)
____ ____ Establish elevations of finish grades, drainage swales, catch basins, foundation drain outfalls, bulkheads, curbs, driveways, property corners, changes in boundaries
____ ____ Establish grading tolerances
____ ____ Provide intercepting drains upgrade of foundation if needed
____ ____ Locate dry wells and recharge pits below foundation level
____ ____ Establish precautions for stabilizing excavation
____ ____ Establish limits of excavation and determine trees, roots, buried cables, pipes, sewers, etc., to be protected from damage
____ ____ Confirm elevation of water table
____ ____ Determine type and dimensions of drainage systems
____ ____ Discharge roof drainage away from foundation
____ ____ Remove stumps and grubbing debris from site
____ ____ Provide frost heave protection for winter construction
____ ____ Call for test hole (full depth hole in proposed foundation location)
____ ____ Locate stakes and benchmarks
____ ____ Strip and stock pile topsoil
____ ____ Define spoil site

SLAB-ON-GRADE FOUNDATION CHECKLIST (PAGE 2 OF 4)

FOOTINGS

____ ____ Position bottom of footing at least 6 inches below frost depth around perimeter (frost wall at garage, slabs supporting roofs, other elements attached to structure).
____ ____ Confirm adequacy of footing sizes
____ ____ Do not fill the overexcavated footing trench
____ ____ Install longitudinal reinforcing (two No. 4 or No. 5 bars 2 inches from top)
____ ____ Reinforce footing at spans over utility trenches
____ ____ Do not bear footings partially on rock (sand fill)
____ ____ Do not pour footings on frozen ground
____ ____ Indicate minimum concrete compressive strength after 28 days
____ ____ Call out elevations of top of footings and dimension elevation changes in plan
____ ____ Use keyway or steel dowels to anchor foundation walls
____ ____ Dimension stepped footings according to local codes and good practice (conform to masonry dimensions if applicable)
____ ____ Provide through-joint flashing as a capillary break

STRUCTURAL

____ ____ Avoid ledge-supported slabs unless structurally reinforced
____ ____ Place isolation joints at frost wall, columns, footings, fireplace foundations, mechanical equipment pads, steps, sidewalks, garage and carport slabs, drains
____ ____ Check that partition load does not exceed 500 pounds per linear foot on unreinforced slab
____ ____ Call out depressed bottom of slab where top is depressed
____ ____ Reinforce slab at depressions greater than 1-1/2 inch
____ ____ Use wire chairs or precast pedestals to support WWF
____ ____ Place sand layer over vapor retarder or insulation board
____ ____ Compact fill under slab

Determine general concrete specifications:

____ ____ Minimum compressive strength after 28 days
____ ____ Maximum water/cement ratio. Note: add no water at site
____ ____ Allowable slump
____ ____ Acceptable and unacceptable admixtures
____ ____ Curing requirements (special hot, cold, dry conditions)
____ ____ Dampening of subgrade prior to pour
____ ____ Surface finish
____ ____ Shrinkage control: WWF reinforcement or control joints
____ ____ Key or dowelling for construction joints

SLAB-ON-GRADE FOUNDATION CHECKLIST (PAGE 3 OF 4)

THERMAL AND MOISTURE CONTROLS

General considerations. Heat loss rate is greatest at the exposed slab edge or frost wall above grade, and at the floor perimeter. Continuity of insulation is difficult except for exterior placement. Horizontal exterior insulation reduces frost penetration depth.

____ ____ Confirm that insulation R-value meets local codes and/or recommendations from this handbook
____ ____ Install insulation product suitable for in-ground use
____ ____ Install infiltration sealing gasket under sole plate
____ ____ Place vapor retarder under slab

DECAY AND TERMITE CONTROL MEASURES

General considerations. Strategy: (1) Isolate wood members from soil by an air space or impermeable barrier; (2) expose critical areas for inspection. Pressure-treated lumber is less susceptible to attack, but is no substitute for proper detailing. Termite shields are not reliable barriers unless installed correctly.

____ ____ Reinforce slab
____ ____ Remove all grade stakes, spreader sticks, wood embedded in concrete during pour
____ ____ Do not disturb treated soil prior to concreting
____ ____ Avoid ducts beneath floor slab top surface
____ ____ Specify pressure-treated wall sole plates and sleepers
____ ____ Pressure-treat sill plates, rim joists, wood members in contact with foundation walls and floors
____ ____ Pressure-treat all outdoor weather-exposed wood members
____ ____ Install dampproof membrane under sill plate (flashing or sill seal gasket)
____ ____ Elevate sill plate minimum 8 inches above exterior grade
____ ____ Elevate wood posts and framing supporting porches, stairs, decks, etc., above grade (6-inch minimum) on concrete piers
____ ____ Elevate wood siding, door sills, other finish wood members at least 6 inches above grade (rain splash protection)
____ ____ Separate raised porches and decks from the building by 2-inch horizontal clearance or provide proper flashing (for drainage and termite inspection)
____ ____ Pitch solid surface porches, decks, patios for drainage (minimum 1/4 in/ft)
____ ____ Detail slab porch and patios to prevent termite access to superstructure (structural slab over inspectable crawl space)
____ ____ Treat soil with termiticide, especially with insulated slab

SLAB-ON-GRADE FOUNDATION CHECKLIST (PAGE 4 OF 4)

RADON CONTROL MEASURES

General considerations. The potential for radon hazard is present in all buildings. Check state and local health agencies for need of protection. Strategies: (1) barriers; (2) air management; (3) provisions to simplify retrofit. Since radon is a gas, its rate of entry through the foundation depends on suction due to stack effect and superstructure air leakage.

____ ____ Reinforce slab
____ ____ Remove all grade stakes, spreader sticks, wood embedded in concrete during pour
____ ____ Form perimeter wall joint with trough, fill with pour-in sealant
____ ____ Place vapor retarder under slab (optional sand layer)
____ ____ Caulk joints around pipes and conduits
____ ____ Place minimum 4-inch-thick layer of coarse, clean gravel under the slab
____ ____ Separate outdoor intakes for combustion devices
____ ____ Install air barrier wrap around superstructure
____ ____ Seal around flues, chases, vent stacks, attic stairs

PLANS, CONTRACTS, AND BUILDING PERMITS

____ ____ Plans and specs
____ ____ Bid package
____ ____ Contractual arrangements (describe principals, describe the work by referencing the blueprints and specs, state the start/completion dates, price, payment schedule, handling of change orders, handling of disputes, excavation allowance, and procedure for firing)
____ ____ Building permits

SITE INSPECTIONS DURING CONSTRUCTION

____ ____ After excavation and before concrete is poured for the footings
____ ____ After the footings have been poured before foundation wall construction
____ ____ After foundation construction and dampproofing before rough framing
____ ____ After rough framing
____ ____ After rough plumbing
____ ____ After rough electrical
____ ____ After insulation installation before drywall and backfilling in case of exterior insulation
____ ____ Final

CHAPTER 5

Worksheet for Selection of Optimal Foundation Insulation

This worksheet will help you choose the optimal foundation insulation location and amount for a new or existing residential building based on your specific building construction, climate, heating and cooling equipment, insulation cost, and other economic considerations. The energy savings of various foundation insulation configurations can be determined from the same heating and cooling load data used to develop the general recommendations in chapters 2, 3, and 4. However, here you may input your current local energy prices and actual insulation costs, and you may choose from three different economic decision criteria: (1) a 20-year minimum life cycle cost (suggested for retrofit); (2) a 30-year minimum life cycle cost, as used in ASHRAE 90.2P (ASHRAE 1989), the CABO Model Energy Code (CABO 1989), and to develop the general recommendations in chapter 2, 3, and 4 of this handbook; or (3) a second-year positive cash flow.

The major steps of the worksheet are shown schematically in Figure 5-1. The formulas used as a basis for Worksheet 1 are shown in Figure 5-2. Step-by-step instructions guide you through the fill-in-the-blank worksheet. Most of the blanks may be filled with inputs you select from the accompanying tables. Included in the tables are representative insulation R-values and installation costs. However, optional worksheets are provided to help you estimate your actual insulation installation cost (Worksheet 2), and to determine additional R-values not included in the list of typical values shown in Table 5-2 (Worksheet 3). The worksheets and tables as well as accompanying descriptions and instructions appear in section 5.1. This is followed by some examples of how to use the worksheets in section 5.2.


STEP A:
IDENTIFY FOUNDATION CHARACTERISTICS
STEP B:
DETERMINE HEATING CLIMATE
STEP C:
DETERMINE HEATING LOAD SAVINGS
STEP D:
DETERMINE HEATING ENERGY DOLLAR SAVINGS
STEP E:
DETERMINE COOLING CLIMATE
STEP F:
DETERMINE COOLING LOAD SAVINGS
STEP G:
DETERMINE COOLING ENERGY DOLLAR SAVINGS
STEP H:
DETERMINE NET DOLLAR SAVINGS

Figure 5-1: Steps in Worksheet to Determine Optimal Foundation Insulation

5.1 Descriptions and Instructions for Worksheets

THERMAL PERFORMANCE

Worksheet 1 helps you estimate the heating and cooling load changes resulting from the foundation insulation options you are considering. The first page of the worksheet addresses the heating season savings while the second page addresses cooling season savings. On each page you identify your climate by entering the local heating degree days (HDD base 65°F) and cooling degree hours (CDH base 74°F), from Table 5-1. Table 5-2 provides the list of foundation types and insulation configurations covered by the worksheet. You can specify any reasonable effective R-value and installed insulation cost. Examples of typical average installed costs for new construction in 1987 are provided in Table 5-2, which includes a markup for the subcontractor and the builder. However, you may choose to estimate your own foundation insulation costs by using Worksheet 2. If a desired level of insulation is not provided in Table 5-2, you may use Worksheet 3 for determining the U-values needed to consider this option in the optimization.

$$\text{Heating Load Factor} = HLF_I + (HLF_S \times HDD)$$

$$\text{Heating Load Savings} = \frac{\text{Heating Load Factor} \times U_{DELTA} \times HDD}{1{,}000{,}000}$$

$$\text{Heating Energy Dollar Savings} = \frac{\text{Heating Load Savings}}{\text{HEEF} \times \text{Duct Efficiency}} \times \text{Economic Scalar Ratio}$$

$$\times\ (\text{Heating Energy Price Rate} \times \text{Conversion Factor})$$

$$\text{Cooling Load Factor} = CLF_I + (CLF_S \times CDH)$$

$$\text{Cooling Load Savings} = \frac{\text{Cooling Load Factor} \times U_{DELTA} \times CDH}{1{,}000}$$

$$\text{Cooling Energy Dollar Savings} = \frac{\text{Cooling Load Savings}}{\text{CEEF} \times \text{Duct Efficiency}} \times \text{Economic Scalar Ratio}$$

$$\times\ (\text{Cooling Energy Price Rate} \times \text{Conversion Factor})$$

$$\text{Net Dollar Savings} = \text{Heating Energy Dollar Savings} + \text{Cooling Energy Dollar Savings}$$

$$-\ \text{Installation Costs}$$

Notes:

1. HLF_I and HLF_S are factors found in Table 5-3.
2. CLF_I and CLF_S are factors found in Table 5-4.
3. HDD are heating degree days found in Table 5-1.
4. CDH are cooling degree hours found in Table 5-1.
5. U_{DELTA} is the difference in U-value between the uninsulated case and an insulated case. U_{DELTA} can be found in Table 5-2 or calculated using Worksheet 3.
6. HEEF is the heating system efficiency and CEEF is the cooling system efficiency (see Table 5-6).
7. Economic scalar ratio is found in Table 5-7.

Figure 5-2: Formulas Used as a Basis for Worksheet 1

ENERGY SAVINGS

Once the load changes are derived for each case, the energy savings can be estimated. The selection of the present worth scalar ratios is where you define your desired economic decision criteria. Table 5-7 provides a variety of scalar ratios derived using three different economic decision criteria: second-year positive cash flow, 20-year life cycle cost, and 30-year life cycle cost. Also shown are seven different fuel escalation rates (0 to 6 percent) which include inflation, and three mortgage rates: 10, 11, and 12 percent.

The scalar ratio is the ratio of the present worth factor for energy savings divided by the present worth factor of mortgage payments for the added foundation insulation cost. The present worth factor for the mortgage payments adjusts for income tax savings and accounts for points paid at the beginning of occupancy as a loan placement fee. It is based on no additional down payment, 1 percent loan placement fee "points", 10 percent after tax equivalent discount rate, and 30 percent marginal income tax (state and federal combined). The higher the scalar ratio, the greater the present worth value of the energy savings, which leads to higher recommended insulation levels. A simple way of thinking about the scalar ratio is that it is the maximum allowable simple payback to the homeowner of any foundation insulation cost.

NET DOLLAR SAVINGS

The last step in the worksheet derives the net dollar savings of each foundation insulation option. Installed costs are presented in Table 5-2 or may be determined using Worksheet 2. The option with the highest positive net savings value in step H of Worksheet 1 is the most cost-effective option.

VALIDATION OF WORKSHEET 1

The objective of this worksheet is to lead you to the most cost-effective foundation insulation level based on your specific economic and HVAC performance characteristics. This procedure has been shown to reproduce the recommended insulation configuration tables in chapters 2, 3, and 4 of this handbook. Over 200 cases were run through this worksheet and the results compared to more detailed computer simulations. The worksheet led to the exact same recommended configuration over 80 percent of the time. Most of the cases that were different resulted from the relatively similar net savings values from a number of different configurations.

INSTRUCTIONS FOR WORKSHEET 1

Suggestion: Make photocopies of the worksheets, keep the originals for future jobs.

Step A. Select the foundation type and insulation configuration from Table 5-2. You may choose more than one insulation configuration from Table 5-2 in order to compare the results. For example, for the slab foundation type you can include the following insulation configurations: *2 ft vertical exterior, 4 ft vertical exterior, and 2 ft vertical interior*. Enter the installation cost for each configuration on line 4. Some typical values for new construction costs are shown in Table 5-2. These costs were national average values in 1987, but you must use Worksheet 2 to obtain current costs.

Step B. Determine heating degree days base 65^{O}F (HDD) for your climate from Table 5-1 and enter on line 5.

Step C. For determining the heating load savings, enter coefficients (HLF_I, HLF_S) from Table 5-3 for the appropriate climate and foundation system on lines 6 and 7. Multiply line 7 (HLF_S) by line 5 (HDD) and enter the result on line 8. Add lines 6 and 8 and enter the results on line 9 (this is the heating load factor). Enter U_{DELTA} from Table 5-2 (or Worksheet 3) on line 10. The heating load savings of each foundation option are determined by multiplying U_{DELTA} from line 10 by the heating load factor on line 9, then multiplying that result by HDD from line 5 and finally dividing by 1,000,000 for each option.

Step D. Suggested values for the heating equipment efficiency (HEEF) are listed in Table 5-6. The data base on which this worksheet is based uses 0.9 for the HVAC duct efficiency (line 15) for unconditioned spaces like attics and crawl spaces. Duct efficiencies can be much lower. ASHRAE 90.2P used a heating duct efficiency of 0.75 when ducts are in unconditioned spaces. When ducts are located within the

Worksheet 1: Selection of Optimal Foundation Insulation (Page 1 of 2)

	CASE 1	CASE 2	CASE 3
STEP A: IDENTIFY FOUNDATION CHARACTERISTICS			
1. Enter foundation type (basement, crawl space, or slab)			
2. Enter insulation configuration from Table 5-2			
3. Enter nominal R-value from Table 5-2			
4. Enter installation cost from Table 5-2 or use Worksheet 2 [units: \$/lin ft or \$/sq ft]*			
STEP B: DETERMINE HEATING CLIMATE			
5. Enter heating degree days (HDD) from Table 5-1			
STEP C: DETERMINE HEATING LOAD SAVINGS			
6. Enter HLF_I from Table 5-3			
7. Enter HLF_S from Table 5-3			
8. Multiply line 7 (HLF_S) by line 5 (HDD)			
9. Add lines 6 and 8 [units: Btu/(HDD x U_{DELTA})]			
10. Enter U_{DELTA} from Table 5-2 (or Worksheet 3)			
11. Multiply line 9 by line 10			
12. Multiply line 11 by line 5 (HDD)			
13. Divide line 12 by 1,000,000 [units: MBtu/lin ft or sq ft]*			
STEP D: DETERMINE HEATING ENERGY DOLLAR SAVINGS			
14. Enter heating system efficiency from Table 5-6 (HEEF)			
15. Multiply line 14 by 0.9 (duct efficiency) (see instructions for alternative duct efficiency numbers)			
16. Divide line 13 (heating load savings) by line 15			
17. Enter heating energy price rate and multiply by conversion factor:			
A. Electricity: __________\$ per kWh X 293 =			
B. Natural gas: __________\$ per therm X 10 =			
C. Fuel oil: __________\$ per gallon X 7.2 =			
D. Propane: __________\$ per gallon X 10.9 =			
18. Multiply line 16 by line 17			
19. Enter the economic scalar ratio from Table 5-7			
20. Multiply line 18 by line 19 [units: \$/lin ft or sq ft]*			

(NOTE: If cooling energy savings are not to be included in the calculation, go directly to STEP H.)

---

* If the configuration utilizes perimeter insulation then all units are expressed *per lineal foot*. If the configuration utilizes ceiling insulation then all units are expressed *per square foot*.

Worksheet 1: Selection of Optimal Foundation Insulation (Page 2 of 2)

	CASE 1	CASE 2	CASE 3
STEP E: DETERMINE COOLING CLIMATE			
21. Enter cooling degree hours (CDH) from Table 5-1			
STEP F: DETERMINE COOLING LOAD SAVINGS			
22. Enter CLF_I from Table 5-4			
23. Enter CLF_S from Table 5-4			
24. Multiply line 23 (CLF_S) by line 21 (CDH)			
25. Add lines 22 and 24 [units: Btu / (CDH x U_{DELTA})]			..
26. Enter U_{DELTA} from line 10 (Table 5-2 or Worksheet 3)			..
27. Multiply line 26 (U_{DELTA}) by line 25 (CLF)			
28. Multiply line 27 by line 21 (CDH)			
29. Divide line 28 by 1,000 [units: KBtu / lin ft or sq ft]*			
STEP G: DETERMINE COOLING ENERGY DOLLAR SAVINGS			
30. Enter cooling system efficiency from Table 5-6 (CEEF)			
31. Multiply line 30 by 0.9 (duct efficiency)			
32. Divide line 29 (cooling load savings) by line 31			
33. Enter cooling energy electric rate (i.e., $ 0.078 per kWh)			
34. Multiply line 32 by line 33			
35. Enter the economic scalar ratio from Table 5-7			
36. Multiply line 34 by line 35 [units: $ / lin ft or sq ft]*			
STEP H: DETERMINE NET DOLLAR SAVINGS			
37. Add line 20 (heating) and line 36 (cooling)			
38. Subtract line 4 (costs) from line 37 (savings) [units: $ / lin ft or sq ft]*			

* If the configuration utilizes perimeter insulation then all units are expressed *per lineal foot*. If the configuration utilizes ceiling insulation then all units are expressed *per square foot*.

INSTRUCTIONS FOR WORKSHEET 1 (CONTINUED)

conditioned space, use a value between 0.9 and 1.0. Line 17 is the current year's heating energy price. Multiplying the energy price rate by the conversion factors shown on line 17 expresses the result in $/MBtu.

The economic scalar ratio is used to determine the present worth of the foundation insulation heating energy savings. Table 5-7 provides a variety of scalar ratios calculated with different mortgage rates, fuel escalation rates, and three different economic decision criteria: (1) second-year positive cash flow, (2) 20-year minimum life cycle cost analysis, and (3) 30-year minimum life cycle cost analysis. The second-year positive cash flow criteria requires that after the second year the additional mortgage payment for the foundation insulation be less than the resulting annual energy savings. The *Building Foundation Design Handbook* (Labs et al. 1988), ASHRAE Standard 90.2P (ASHRAE 1989), and the Model Energy Code (CABO 1989) are all based on a scalar ratio of about 18. To be consistent with these codes and standards, use 18 in line 19. The result on line 20 is the heating energy dollar savings.

Step E. Determine cooling degree hours base 74^{O}F (CDH) for your climate from Table 5-1 and enter on line 21.

Step F. For determining the cooling load savings, enter coefficients (CLF_I, CLF_S) from Table 5-4 for the appropriate climate and foundation system on lines 22 and 23. Multiply line 23 (CLF_S) by line 21 (CDH) and enter the result on line 24. Add lines 22 and 24 and enter the results on line 25 (this is the cooling load factor). Enter U_{DELTA} from Table 5-2 (or Worksheet 3) on line 26. The cooling load savings of each foundation option are determined by multiplying U_{DELTA} from line 26 by the cooling load factor on line 25, then multiplying that result by CDH from line 21 and finally dividing by 1,000 for each option.

Step G. Suggested values for the cooling equipment efficiency (CEEF) are shown in Table 5-6. Line 31 is the HVAC duct efficiency while providing cooling. The *Building Foundation Design Handbook* assumes 0.9 for cooling duct efficiency. ASHRAE 90.2p uses 0.8 for cooling duct efficiency, when ducts are in unconditioned spaces. Line 33 is the current year's cooling energy price (consult your local electric utility for prices). The value to be entered in line 33 must be in dollars per kWh. Line 35 is the scalar ratio used to estimate the present worth of the cooling energy savings resulting from foundation insulation. Table 5-7 provides a variety of scalar ratios based on different economic criteria, mortgage rates, and real fuel escalation rates. To be consistent with various codes and standards listed in Step D, use a scalar ratio of 18 in line 35. The result on line 36 is the cooling energy dollar savings.

Step H. The option with the largest positive value in line 38 is the most cost-effective option. This step subtracts the first cost of each option (line 4) from the corresponding present worth value of the energy savings. If all the net savings values in line 38 are negative, this indicates that none of the cases meet your cost-effectiveness criteria. Select a set of options that have lower installed costs and repeat the worksheet. If still none exist, foundation insulation may not be a good investment for this project.

Worksheet 2: Optional Method for Estimating Foundation Insulation Installation Cost

	CASE 1	CASE 2	CASE 3
STEP A: DETERMINE MATERIAL COST			
1. Enter the total material cost of insulation			
2. Enter the total material cost of fasteners			
3. Enter the cost of protective covering or required flame spread protection			
4. Add lines 1, 2, and 3 to determine the total material cost			
STEP B: DETERMINE LABOR COST			
5. Enter site preparation cost			
6. Enter installation cost for insulation			
7. Enter installation cost for any framing or furring			
8. Enter installation cost for any protective covering			
9. Add lines 5, 6, 7, and 8 to determine total labor cost			
STEP C: DETERMINE TOTAL INSTALLED COST			
10. Add lines 4 and 9			
11. Multiply line 10 by the subcontractor markup (example: 1.3)			
12. Multiply line 11 by the general contractor markup (example: 1.3)			
13. Divide line 12 by the foundation perimeter length in feet			

INSTRUCTIONS FOR WORKSHEET 2

Step A. Material costs should be for the entire job. Line 1 represents the material costs for the entire area to be covered. Line 2 includes the insulation attachment materials; examples are fasteners for exterior systems and framing for interior systems. Line 3 includes the above-grade protection needed for exterior insulation or flame spread protection for interior applications. If the covering provides other amenities such as aesthetics (basement finishing needed anyway) then this cost should be zero.

Step B. Line 5 includes surface preparation that may be needed such as cleaning prior to liquid adhesive application. In retrofit installations the cost of excavation for exterior systems and interior wall fixture relocation for interior systems should be entered. Lines 6 and 7 cover total labor cost of attaching the insulation. Line 8 includes the labor for applying either the exterior above-grade covering or flame spread protection covering on the interior if done only to meet safety standards.

Step C. The total installed cost may include subcontractor markup (line 11) and builder markup (line 12). These markups account for indirect charges, overhead, and profit. The costs for new construction foundation insulation in Table 5-2 include 30 percent for both markups. For insulation retrofits, the builder markup should be 1.0. For homeowner retrofit the subcontractor markup could also be 1.0. Line 13 converts the total cost into dollars per foundation perimeter foot, for use in Steps A and H of Worksheet 1 for selection of optimal foundation insulation.

INSTRUCTIONS FOR WORKSHEET 3

Step A. The U-value of only the insulation layer for foundation walls can be calculated by assuming parallel heat flow paths through areas with different thermal resistances. Lines 1a through 1e are fractions of the total area transverse to heat flow representing the component materials of the wall system. For stud walls 16 inches on center, the fraction of framing is usually assumed to be approximately 0.15; for studs 24 inches on center, it is approximately 0.12. Lines 2a through 2e are the R-values of materials contained in the insulation layer. For example, an insulated stud wall will have wood and mineral batts.

Step B. R_{BASE} must be selected from Table 5-5. It represents the system that was modeled and cannot be varied in this worksheet. If the fasteners are to be ignored for board insulations as was done in Table 5-2, the nominal R-value can be added to R_{BASE} to obtain R_{EFF}. Insert R_{EFF} in line 6.

Step C. Use Table 5-5 to obtain the effective R-value of the uninsulated foundation construction (R_{BASE}) and the effective R-value of the adjacent soil (R_{SOIL}). These are not actual R-values, rather they are values that produce the best representation of the annual heating and cooling load savings data base on which this worksheet is based. These values should not be varied from those shown for each system in Table 5-5. Choose the set of values listed for the foundation system options you would like to consider, then follow the calculation procedure on lines 9 and 10 to find U_{BASE}. This is the U-value of the uninsulated case.

Step D. Add R_{EFF} from line 6 to R_{SOIL} from line 8 and enter the result on line 11. Follow the calculation procedure on line 12 to find U_{TOTAL}. This is the U-value of the insulated case.

Step E. The difference in U-value for each insulation level is determined by subtracting U_{TOTAL} (line 12) from U_{BASE} (line 10) for each option.

$$\text{Effective R-value } (R_{EFF}) = R_{BASE} + \frac{1}{(\text{Area}_1 \ / \ R_1 + \text{Area}_2 \ / \ R_2 + \ldots)}$$

$$U_{BASE} = \frac{1}{R_{BASE} + R_{SOIL}}$$

$$U_{TOTAL} = \frac{1}{R_{EFF} + R_{SOIL}}$$

$$U_{DELTA} = U_{BASE} - U_{TOTAL}$$

Notes:

1. R_{BASE} and R_{SOIL} are found in Table 5-5.
2. Area_1 is the fraction of the total area covered by material 1 (i.e. material 1 may be insulation covering 90% of the wall while material 2 may be wood framing covering 10% of the wall)
3. R_1 and R_2 represent the R-values of material 1 and material 2
4. R_{EFF}, U_{BASE}, U_{TOTAL}, and U_{DELTA} are all defined in the instructions for worksheet 3 above

Figure 5-3: Formulas Used as a Basis for Worksheet 3

Worksheet 3: Optional Method for Determining U_{DELTA}

	CASE 1	CASE 2	CASE 3
STEP A: CALCULATE THE U-VALUE OF INSULATION ASSEMBLY			
1. Enter the fraction of the total area covered by each component			
a. Component 1 (example: insulation)	______	______	______
b. Component 2 (example: framing)	______	______	______
c. Component 3	______	______	______
d. Component 4	______	______	______
e. Component 5	______	______	______
2. Divide the fractional values in line 1 by the corresponding R-values			
a. Line 1a divided by R-value for component 1	______	______	______
b. Line 1b divided by R-value for component 2	______	______	______
c. Line 1c divided by R-value for component 3	______	______	______
d. Line 1d divided by R-value for component 4	______	______	______
e. Line 1e divided by R-value for component 5	______	______	______
3. Add the results of line 2 to determine the overall U-value (2a + 2b + 2c + ...)	______	______	______
STEP B: CALCULATE THE EFFECTIVE R-VALUE (R_{EFF})			
4. Enter the appropriate R_{BASE} from Table 5-5	______	______	______
5. Divide 1 by line 3	______	______	______
6. Add lines 4 and 5 to determine R_{EFF}	______	______	______
STEP C: DETERMINE THE U-VALUE OF UNINSULATED CASE (U_{BASE})			
7. Enter R_{BASE} from Table 5-5	______	______	______
8. Enter R_{SOIL} from Table 5-5	______	______	______
9. Add lines 7 and 8	______	______	______
10. Divide 1 by line 9 [units: Btu / ^{O}F x ft^{2} x h]	______	______	______
STEP D: DETERMINE THE U-VALUE OF INSULATED CASE (U_{TOTAL})			
11. Add line 6 (R_{EFF}) and line 8 (R_{SOIL})	______	______	______
12. Divide 1 by line 11 [units: Btu / ^{O}F x ft^{2} x h]	______	______	______
STEP E: DETERMINE U-VALUE DIFFERENCE (U_{DELTA})			
13. Subtract line 12 from line 10 [units: Btu / ^{O}F x ft^{2} x h]	______	______	______

Table 5-1: Weather Data for Selected Cities (page 1 of 2)

Location	CDH[1]	HDD[2]
Alabama		
Birmingham	19497	2943
Mobile	20047	169
Montgomery	23355	2277
Arizona		
Phoenix	52408	1442
Tucson	38743	1734
Arkansas		
Fort Smith	22474	3477
Little Rock	22467	3152
California		
Bakersfield	27919	2128
Fresno	21311	2647
Los Angeles	2416	1595
Sacramento	14026	2772
San Diego	2514	1284
San Francisco	843	3161
Colorado		
Colorado Springs	6089	6346
Denver	8586	6014
Connecticut		
Hartford	5151	6174
District of Columbia		
Washington, D.C.	12121	5004
Florida		
Jacksonville	25200	1402
Miami	32951	199
Orlando	25072	656
Tallahassee	18051	1652
Tampa	26167	739
Palm Beach	32531	262
Georgia		
Atlanta	15710	3021
Augusta	20921	2563
Macon	22388	2279
Savannah	19953	1921
Idaho		
Boise	9804	5802
Illinois		
Chicago	6665	6455
Springfield	12117	5654
Indiana		
Evansville	14947	4260
Ft. Wayne	7990	6320
Indianapolis	9091	5650
South Bend	6311	6377
Iowa		
Des Moines	9512	6554
Sioux City	10581	6947
Kansas		
Topeka	16433	5319
Wichita	19757	4787
Kentucky		
Lexington	9472	4814
Louisville	14868	4525
Louisiana		
Baton Rouge	24267	1673
Lake Charles	24628	1579
New Orleans	23546	1490
Shreveport	26043	2269
Maine		
Bangor	2234	7947
Portland	2796	7501
Maryland		
Baltimore	10688	4706
Massachusetts		
Boston	5413	5593
Michigan		
Detroit	6519	6563
Flint	4216	7068
Grand Rapids	5813	6927
Lansing	4938	6987
Minnesota		
Duluth	1672	9901
Minneapolis	6344	8007
Mississippi		
Jackson	23321	2389
Missouri		
Kansas City	18818	5283
Springfield	13853	4660
St. Louis	16302	4938
Montana		
Billings	6991	7212
Great Falls	4498	7766

1. Cooling degree hours - base 74 degrees Fahrenheit
2. Heating degree days - base 65 degrees Fahrenheit

Table 5-1: Weather Data for Selected Cities (page 2 of 2)

Location	CDH[1]	HDD[2]
Nebraska		
Omaha	12448	6194
Nevada		
Las Vegas	44433	2532
Reno	9403	6030
New Mexico		
Albuquerque	15538	4414
New York		
Albany	5461	6927
Binghamton	2304	7344
Buffalo	4284	6798
New York City	8337	4922
Rochester	5224	6713
Syracuse	5274	6787
North Carolina		
Charlotte	15940	3342
Greensboro	12261	3874
Raleigh	13851	3342
Winston-Salem	11673	3679
North Dakota		
Bismarck	6861	9075
Grand Forks	4329	9881
Ohio		
Canton	5041	6241
Cincinnati	10178	4950
Cleveland	6834	6178
Columbus	9341	5447
Dayton	8401	5255
Toledo	6209	6570
Youngstown	4734	6560
Oklahoma		
Tulsa	23642	3731
Oregon		
Eugene	4436	4799
Medford	9500	4798
Portland	2711	4691
Salem	4443	4974
Pennsylvania		
Harrisburg	8091	5335
Philadelphia	9303	4947
Pittsburgh	5024	5950
Scranton	4219	6114
Rhode Island		
Providence	4359	5908

1. Cooling degree hours - base 74 degrees Fahrenheit
2. Heating degree days - base 65 degrees Fahrenheit

Location	CDH[1]	HDD[2]
South Carolina		
Charleston	16473	2147
Columbia	21060	2629
South Dakota		
Sioux Falls	7872	7885
Tennessee		
Chattanooga	16361	3583
Knoxville	14641	3658
Memphis	21614	3207
Texas		
Amarillo	16968	4231
Austin	32314	1760
Brownsville	34029	609
Corpus Chris	32684	945
Dallas-Ft. Worth	34425	2301
El Paso	28602	2664
Houston	47650	1549
Laredo	48983	926
Lubbock	19974	3516
Midland	26098	2658
Nashville	17728	3756
San Antonio	31614	1606
Waco	31843	2126
Wichita Falls	29921	3011
Utah		
Salt Lake City	12874	5802
Vermont		
Burlington	3163	7953
Virginia		
Norfolk	12766	3446
Richmond	13546	3960
Roanoke	10576	4315
Washington		
Seattle	1222	4681
Spokane	5567	6882
Wisconsin		
Green Bay	3129	8143
La Crosse	5738	7540
Madison	6164	7642
Milwaukee	4565	7326
West Virginia		
Charleston	9486	4697
Huntington	10419	4676
Wyoming		
Casper	6723	7642

Table 5-2: Insulation R-Values and Costs for Conditioned Basements (page 1 of 4)

A: Concrete or Masonry Foundation Walls with Exterior Insulation

CONFIGURATION	DESCRIPTION	NOMINAL R-VALUE	EFFECTIVE R-VALUE	U-DELTA	INSTALLATION COST ($ PER LF)
EXTERIOR: HALF WALL 	4 FT EXTERIOR	4	5	0.312	4.04
		5	6	0.335	4.44
		8	9	0.377	5.32
		10	11	0.394	6.54
		12	13	0.405	7.52
		15	16	0.418	8.47
EXTERIOR: FULL WALL 	8 FT EXTERIOR	4	5	0.210	6.2
		5	6	0.229	7.01
		8	9	0.265	8.77
		10	11	0.279	10.87
		12	13	0.290	12.71
		15	16	0.301	14.55
		20	21	0.313	18.35

B: Concrete Walls with Interior Insulation (Costs do not include interior finish material)

INTERIOR: FULL WALL 	8 FT INTERIOR WITHOUT DRYWALL	6	5.23	0.215	4.72
		8	6.83	0.241	5.76
		11	10.7	0.277	6.48
		19	18	0.307	10.24

C: Concrete Walls with Interior Insulation (Costs include sheetrock on interior wall)

INTERIOR: FULL WALL 	8 FT INTERIOR WITH DRYWALL	6	5.7	0.224	12.32
		8	7.4	0.248	13.36
		11	11.26	0.281	12.56
		19	18.56	0.308	16.32

D: Pressure-Treated Wood Foundation Walls

WOOD: FULL WALL 	8 FT WOOD	11	11.8	0.085	8.52*
		13	13.5	0.091	9.19*
		19	18.5	0.103	9.87*
		30	27.9	0.116	15.78*

* Costs include $6.08/ft for drywall covering that is not necessarily required.

Table 5-2: Insulation R-Values and Costs for Unconditioned Basements (page 2 of 4)

A: Concrete or Masonry Foundation Walls with Exterior Insulation

CONFIGURATION	DESCRIPTION	NOMINAL R-VALUE	EFFECTIVE R-VALUE	U-DELTA	INSTALLATION COST ($ PER LF)
EXTERIOR: HALF WALL 	4 FT EXTERIOR	4	5	0.221	4.04
		5	6	0.241	4.44
		8	9	0.277	5.32
		10	11	0.292	6.54
		12	13	0.302	7.52
		15	16	0.314	8.47
EXTERIOR: FULL WALL 	8 FT EXTERIOR	4	5	0.116	6.2
		5	6	0.129	7.01
		8	9	0.156	8.77
		10	11	0.168	10.87
		12	13	0.176	12.71
		15	16	0.186	14.55
		20	21	0.197	18.35

B: Concrete Walls with Interior Insulation (Costs do not include interior finish material)

INTERIOR: FULL WALL 	8 FT INTERIOR WITHOUT DRYWALL	6	5.23	0.119	4.72
		8	6.83	0.138	5.76
		11	10.7	0.166	6.48
		19	18	0.191	10.24

C: Concrete Walls with Interior Insulation (Costs include sheetrock on interior wall)

INTERIOR: FULL WALL 	8 FT INTERIOR WITH DRYWALL	6	5.7	0.126	12.32
		8	7.4	0.144	13.36
		11	11.26	0.169	12.56
		19	18.56	0.192	16.32

D: Pressure-Treated Wood Foundation Walls

WOOD: FULL WALL 	8 FT WOOD	11	11.8	0.315	8.52*
		13	13.5	0.326	9.19*
		19	18.5	0.346	9.87*
		30	27.9	0.364	15.78*

E: Concrete or Masonry Foundation Walls with Ceiling Insulation

CEILING 					**INST. COST ($ PER SF)**
	WOOD CEILING	11	13	0.092	0.34
		13	14	0.096	0.41
		19	19	0.112	0.52
		30	27.3	0.126	0.86

* Costs include $6.08/ft for drywall covering that is not necessarily required.

Table 5-2: Insulation R-Values and Costs for Crawl Spaces (page 3 of 4)

A: Unvented Crawl Space - Concrete or Masonry Foundation Walls with Exterior Insulation

CONFIGURATION	DESCRIPTION	NOMINAL R-VALUE	EFFECTIVE R-VALUE	U-DELTA	INSTALLATION COST ($ PER LF)
EXTERIOR VERTICAL 	2 FT EXTERIOR	5	6	0.307	2.00
		10	11	0.363	2.97

B: Unvented Crawl Space - Concrete or Masonry Foundation Walls with Interior Insulation

INTERIOR VERTICAL 	2 FT INTERIOR	5	6	0.307	1.15
		10	11	0.363	2.12
		11	12	0.369	1.92
		13	14	0.379	2.13
		19	20	0.397	2.57

C: Unvented Crawl Space - Pressure-Treated Wood Foundation Walls

WITHIN WOOD WALL 	2 FT WOOD	11	11.8	0.145	1.32**
		13	13.5	0.153	1.48**
		19	18.5	0.169	1.76**
		30	27.9	0.184	2.32**

D: Vented Crawl Space - Concrete or Masonry Foundation Walls with Ceiling Insulation

CEILING 					**INST. COST ($ PER SF)**
	WOOD CEILING	11	13	0.131	0.34
		13	14	0.137	0.41
		19	19	0.156	0.52
		30	27.3	0.172	0.86

** Costs include fire protective covering on the interior face.

Table 5-2: Insulation R-Values and Costs for Slab-on-Grade Foundations (page 4 of 4)

A: Concrete or Masonry Foundation Wall with Exterior Insulation Placed Vertically

CONFIGURATION	DESCRIPTION	NOMINAL R-VALUE	EFFECTIVE R-VALUE	U-DELTA	INSTALLATION COST ($ PER LF)
EXTERIOR VERTICAL: 2ft 	2 FT EXTERIOR VERTICAL	4	5	0.284	2.04
		5	6	0.307	2.25
		8	9	0.347	2.64
		10	11	0.363	3.50
		11	12	0.369	4.02
		14	15	0.383	4.58
EXTERIOR VERTICAL: 4ft 	4 FT EXTERIOR VERTICAL	4	5	0.284	3.13
		5	6	0.307	3.53
		8	9	0.347	4.41
		10	11	0.363	5.70
		12	13	0.374	6.66
		15	16	0.386	7.69
		20	21	0.400	9.68

B: Concrete or Masonry Foundation Walls with Interior Insulation Placed Vertically

INTERIOR VERTICAL 	2 FT INTERIOR VERTICAL/R-5 GAP	5	6	0.307	1.30
		10	11	0.363	2.19
	2 FT INTERIOR VERTICAL/R-5 GAP	5	6	0.307	2.59
		10	11	0.363	4.40
		15	16	0.386	6.23
		20	21	0.400	8.06

C: Concrete Walls with Interior Insulation Placed Horizontally Under Slab Perimeter

INTERIOR HORIZONTAL 	2 FT HORIZONTAL INTERIOR/R-5 GAP	5	6	0.307	1.65
		10	11	0.363	2.80
	4 FT HORIZONTAL INTERIOR/R-5 GAP	5	6	0.307	2.69
		10	11	0.363	4.52

D: Concrete Foundation Walls with Exterior Insulation Extending Outward Horizontally

EXTERIOR HORIZONTAL 	2 FT HORIZONTAL EXTERIOR	5	6	0.307	3.53
		10	11	0.363	5.70
	4 FT HORIZONTAL EXTERIOR	5	6	0.307	4.53
		10	11	0.363	7.90

Table 5-3: Heating Load Factor Coefficients (HLF_I and HLF_S)

FOUNDATION SYSTEM	CLIMATE			
	MORE THAN 2500 HDD		LESS THAN 2500 HDD	
	HLF_I	HLF_S	HLF_I	HLF_S
Slab				
2 ft vertical exterior	19.38	0	-4.40399	0.01170
2 ft vertical interior/R-5 gap	18.77	0	-4.14849	0.00996
2 ft horizontal interior/R-5 gap	19.42	0	-3.95460	0.00990
2 ft horizontal exterior	23.98	0	-5.21022	0.01154
4 ft horizontal exterior	25.34	0	-6.08104	0.01272
4 ft fdn exterior	24.30	0	-6.13994	0.01571
4 ft fdn interior/R-5 gap	24.20	0	-6.13994	0.01571
4 ft horizontal interior/R-5 gap	25.26	0	-6.33494	0.01381
Unvented Crawl Space				
2 ft exterior	19.06	0	2.56965	0.00901
2 ft interior	19.34	0	4.07627	0.00861
2 ft wood	17.40	0	-1.54462	0.00946
Vented Crawl Space				
ceiling	21.435	0	21.435	0
Deep Basement (Conditioned)				
4 ft exterior	80.40	0	-5.63157	0.05430
8 ft exterior or 8 ft interior	155.06	0	-16.53665	0.09895
8 ft wood	186.07	0	-24.93757	0.11622
Deep Basement (Unconditioned)				
4 ft exterior	25.07	0	0.39093	0.01225
8 ft exterior or 8 ft interior	59.10	0	-6.14049	0.02758
8 ft wood	33.34	0	-0.82326	0.01519
ceiling	14.81	0	-17.44417	0.01866

Table 5-4: Cooling Load Factor Coefficients (CLF_I and CLF_S)

FOUNDATION SYSTEM	**CLIMATE**					
	LESS THAN 15000 CDH		**MORE THAN 15000 CDH AND LESS THAN 30000 CDH**		**MORE THAN 30000 CDH**	
	CLF_I	**CLF_S**	**CLF_I**	**CLF_S**	**CLF_I**	**CLF_S**
Slab						
2 ft vertical exterior	-1.89761	0.00015	1.02787	-0.00005	-1.93544	0.00005
2 ft vertical interior / R-5 gap	-2.45376	0.00017	0.31361	-0.00003	-1.78118	0.00004
2 ft horiz. interior / R-5 gap	-3.02223	0.00019	-0.33245	-0.00001	-1.89340	0.00005
4 ft vertical exterior	-3.18708	0.00024	1.25057	-0.00007	-2.81314	0.00007
4 ft vertical interior / R-5 gap	-2.43021	0.00016	0.31361	-0.00003	-1.78118	0.00004
4 ft horiz. interior / R-5 gap	-5.58028	0.00033	-1.97537	0.00002	-3.32060	0.00007
Unvented Crawl Space						
2 ft exterior	-1.43093	0.00012	1.07080	-0.00005	-1.92333	0.00005
2 ft interior	-2.37578	0.00017	-1.23231	0.00003	-1.23231	0.00003
2 ft wood	-2.16409	0.00016	1.42995	-0.00007	-2.50404	0.00006
Vented Crawl Space						
ceiling	-1.78237	0.00010	-1.07055	0.000003	-1.16166	0.00003
Deep Basement (Conditioned)						
4 ft exterior	0.20910	0.00006	2.51623	-0.00008	-3.04576	0.00010
8 ft exterior or interior	-0.09706	0.00010	4.73889	-0.00018	-6.98257	0.00020
8 ft wood	-0.25473	0.00009	4.93520	-0.00021	-8.92914	0.00025
Deep Basement (Unconditioned)						
4 ft exterior	-3.45221	0.00022	0.70912	-0.00005	-3.10899	0.00008
8 ft exterior or interior	-10.68317	0.00058	-1.34275	-0.00006	-8.91748	0.00021
8 ft wood	-6.64161	0.00033	-0.73835	-0.00005	-6.25373	0.00015
ceiling	-3.84203	0.00020	-1.53760	0.00002	-2.11852	0.00005

Table 5-5: Initial Effective R-values for Uninsulated Foundation System and Adjacent Soil

FOUNDATION SYSTEM	R_{BASE}	R_{SOIL}
Slab		
2 ft vertical exterior	1.0	1.25
2 ft vertical interior / R-5 gap	1.0	1.25
2 ft horizontal interior / R-5 gap	1.0	1.25
2 ft horizontal exterior	1.0	1.25
4 ft horizontal exterior	1.0	1.25
4 ft vertical exterior	1.0	1.25
4 ft vertical interior / R-5 gap	1.0	1.25
4 ft horizontal interior / R-5 gap	1.0	1.25
Unvented Crawl Space		
2 ft exterior	1.0	1.25
2 ft interior	1.0	1.25
2 ft wood	2.5	2.1
Vented Crawl Space		
ceiling	4.8	0
Deep Basement (Conditioned)		
4 ft exterior	1.0	1.1
8 ft exterior or 8 ft interior	1.0	1.8
8 ft wood	2.5	4.3
Deep Basement (Unconditioned)		
4 ft exterior	1.0	1.7
8 ft exterior or 8 ft interior	1.0	3.2
8 ft wood	2.5	0
ceiling	4.8	1.4

Table 5-6: Heating and Cooling Equipment Seasonal Efficiencies[1]

	LOW	MEDIUM	HIGH	VERY HIGH
HEEF				
gas furnace	0.50	0.65	0.80	0.90
oil furnace	0.50	0.65	0.80	0.90
heat pump (HSCOP)	1.6	1.9	2.2	2.5
electric furnace	1.0	1.0	1.0	1.0
electric baseboard	1.0	1.0	1.0	1.0
CEEF				
heat pump (SEER)	7.25	8.75	10.25	11.75
air conditioner (SEER)	6.0	8.0	10.0	12.0

1. Does not include duct losses

Table 5-7: Scalar Ratios for Various Economic Criteria

MORTGAGE (PERCENT)	FUEL ESCALATION[3] (PERCENT)	SCALAR RATIO[2] 2 YR CROSS OVER	 20 YR LIFE CYCLE[1]	 30 YR LIFE CYCLE[1]
10	0	13.25	10.07	11.69
10	1	13.51	10.88	12.84
10	2	13.78	11.75	14.16
10	3	14.05	12.73	15.70
10	4	14.31	13.83	17.48
10	5	14.58	15.05	19.58
10	6	14.84	16.41	22.03
11	0	12.28	9.52	10.84
11	1	12.53	10.28	11.91
11	2	12.78	11.11	13.14
11	3	13.02	12.06	14.56
11	4	13.27	13.08	16.22
11	5	13.51	14.23	18.16
11	6	13.76	15.51	20.44
12	0	11.50	9.00	10.14
12	1	11.72	9.72	11.14
12	2	11.95	10.51	12.29
12	3	12.18	11.39	13.62
12	4	12.41	12.37	15.17
12	5	12.64	13.46	16.99
12	6	12.87	14.68	19.12

1. Based on 10% real after tax discount rate
2. Scalar ratio represents the maximum number of years allowed to have the energy savings resulting from the insulation pay for financing the first cost of installing the insulation.
3. This includes inflation.

5.2 Examples of How to Use the Worksheet

This section contains a set of examples indicating how to use the worksheets described in section 5.1. First, Worksheets 1 through 3 are filled out in order to compare the cost-effectiveness of three insulation configuration alternatives. This is followed by a series of tables that illustrate how the results from the worksheet calculations can be organized to create customized information for making foundation insulation decisions.

THE WORKSHEET EXAMPLES

You are building a conditioned basement in Knoxville, Tennessee. You would like to determine the optimum amount of foundation insulation to install on the exterior of the concrete masonry wall in contact with the surrounding soil. Extruded polystyrene is available in your local building materials yard with R-values of 5, 10, and 15. Other key assumptions are that you plan on installing a high-efficiency heat pump with a COP of 2.2 and a SEER of 10.25. The ducts are assumed to be in a conditioned space, but a duct efficiency value of 0.9 is assumed. Your economic criteria are a mortgage rate of 11 percent with fuel escalation (including inflation) of 5 percent per year and assuming 30-year life cycle cost analysis.

Working through Worksheet 1 leaves line 38 with the cost savings due to insulating for each case (expressed in dollars per linear foot): case 1 = $14.46, case 2 = $15.28, case 3 = $13.68. The largest value ($15.28) is the optimum case, R-10 insulation. If you add lines 18 and 34 for case 2 ($1.44) and then divide this sum into line 4 ($10.87), you see the simple payback for this case is 7.5 years. The optional worksheets 2 and 3 are also filled out for this example.

SAMPLE TABLES GENERATED FROM THE WORKSHEETS

Tables 5-8 through 5-11 show annual energy cost savings for a complete set of foundation configurations. For each option, annual savings due to insulating are given for cities in five representative U.S. climate zones. The energy savings account for changes in both heating and cooling loads. These tables allow users to compare the differences in performance among these various insulation placements. Also, the cost of insulating has been divided by annual savings to show the simple payback for the investment. These savings are based on medium fuel costs as shown in Table 2-3. Similar customized tables can be generated using the worksheets to fit local conditions.

Worksheet 1: Selection of Optimal Foundation Insulation (Page 1 of 2)—Example

	CASE 1	**CASE 2**	**CASE 3**
STEP A: IDENTIFY FOUNDATION CHARACTERISTICS			
1. Enter foundation type (basement, crawl space, or slab)			
2. Enter insulation configuration from Table 5-2			
3. Enter nominal R-value from Table 5-2			
4. Enter installation cost from Table 5-2 or use Worksheet 2 [units: $/lin ft or $/sq ft]*			
STEP B: DETERMINE HEATING CLIMATE			
5. Enter heating degree days (HDD) from Table 5-1			
STEP C: DETERMINE HEATING LOAD SAVINGS			
6. Enter HLF_I from Table 5-3			
7. Enter HLF_S from Table 5-3			
8. Multiply line 7 (HLF_S) by line 5 (HDD)			
9. Add lines 6 and 8 [units: Btu/(HDD x U_{DELTA})]			
10. Enter U_{DELTA} from Table 5-2 (or Worksheet 3)			
11. Multiply line 9 by line 10			
12. Multiply line 11 by line 5 (HDD)			
13. Divide line 12 by 1,000,000 [units: MBtu/lin ft or sq ft]*			
STEP D: DETERMINE HEATING ENERGY DOLLAR SAVINGS			
14. Enter heating system efficiency from Table 5-6 (HEEF)			
15. Multiply line 14 by 0.9 (duct efficiency) (see instructions for alternative duct efficiency numbers)			
16. Divide line 13 (heating load savings) by line 15			
17. Enter heating energy price rate and multiply by conversion factor:			
A. Electricity: ______$ per kWh X 293 =			
B. Natural gas: ______$ per therm X 10 =			
C. Fuel oil: ______$ per gallon X 7.2 =			
D. Propane: ______$ per gallon X 10.9 =			
18. Multiply line 16 by line 17			
19. Enter the economic scalar ratio from Table 5-7			
20. Multiply line 18 by line 19 [units: $/lin ft or sq ft]*			

(NOTE: If cooling energy savings are not to be included in the calculation, go directly to STEP H.)

---

* If the configuration utilizes perimeter insulation then all units are expressed *per lineal foot*. If the configuration utilizes ceiling insulation then all units are expressed *per square foot*.

Worksheet 1: Selection of Optimal Foundation Insulation (Page 2 of 2)—Example

	CASE 1	CASE 2	CASE 3
STEP E: DETERMINE COOLING CLIMATE			
21. Enter cooling degree hours (CDH) from Table 5-1			
STEP F: DETERMINE COOLING LOAD SAVINGS			
22. Enter CLF_I from Table 5-4			
23. Enter CLF_S from Table 5-4			
24. Multiply line 23 (CLF_S) by line 21 (CDH)			
25. Add lines 22 and 24 [units: Btu / (CDH x U_{DELTA})]			
26. Enter U_{DELTA} from line 10 (Table 5-2 or Worksheet 3)			
27. Multiply line 26 (U_{DELTA}) by line 25 (CLF)			
28. Multiply line 27 by line 21 (CDH)			
29. Divide line 28 by 1,000 [units: KBtu / lin ft or sq ft]*			
STEP G: DETERMINE COOLING ENERGY DOLLAR SAVINGS			
30. Enter cooling system efficiency from Table 5-6 (CEEF)			
31. Multiply line 30 by 0.9 (duct efficiency)			
32. Divide line 29 (cooling load savings) by line 31			
33. Enter cooling energy electric rate (i.e., $ 0.078 per kWh)			
34. Multiply line 32 by line 33			
35. Enter the economic scalar ratio from Table 5-7			
36. Multiply line 34 by line 35 [units: $ / lin ft or sq ft]*			
STEP H: DETERMINE NET DOLLAR SAVINGS			
37. Add line 20 (heating) and line 36 (cooling)			
38. Subtract line 4 (costs) from line 37 (savings) [units: $ / lin ft or sq ft]*			

* If the configuration utilizes perimeter insulation then all units are expressed *per lineal foot*. If the configuration utilizes ceiling insulation then all units are expressed *per square foot*.

Worksheet 2: Optional Method for Estimating Insulation Installation Cost—Example

	CASE 1	CASE 2	CASE 3
STEP A: DETERMINE MATERIAL COST			
1. Enter the total material cost of insulation			
2. Enter the total material cost of fasteners			
3. Enter the cost of protective covering or required flame spread protection			
4. Add lines 1, 2, and 3 to determine the total material cost			
STEP B: DETERMINE LABOR COST			
5. Enter site preparation cost			
6. Enter installation cost for insulation			
7. Enter installation cost for any framing or furring			
8. Enter installation cost for any protective covering			
9. Add lines 5, 6, 7, and 8 to determine total labor cost			
STEP C: DETERMINE TOTAL INSTALLED COST			
10. Add lines 4 and 9			
11. Multiply line 10 by the subcontractor markup (example: 1.3)			
12. Multiply line 11 by the general contractor markup (example: 1.3)			
13. Divide line 12 by the foundation perimeter length in feet			

Worksheet 3: Optional Method for Determining U_{DELTA}—Example

STEP A: CALCULATE THE U-VALUE OF INSULATION ASSEMBLY

	CASE 1	CASE 2	CASE 3
1. Enter the fraction of the total area covered by each component			
a. Component 1 (example: insulation)			
b. Component 2 (example: framing)			
c. Component 3			
d. Component 4			
e. Component 5			
2. Divide the fractional values in line 1 by the corresponding R-values			
a. Line 1a divided by R-value for component 1			
b. Line 1b divided by R-value for component 2			
c. Line 1c divided by R-value for component 3			
d. Line 1d divided by R-value for component 4			
e. Line 1e divided by R-value for component 5			
3. Add the results of line 2 to determine the overall U-value (2a + 2b + 2c + ...)			

STEP B: CALCULATE THE EFFECTIVE R-VALUE (R_{EFF})

	CASE 1	CASE 2	CASE 3
4. Enter the appropriate R_{BASE} from Table 5-5			
5. Divide 1 by line 3			
6. Add lines 4 and 5 to determine R_{EFF}			

STEP C: DETERMINE THE U-VALUE OF UNINSULATED CASE (U_{BASE})

	CASE 1	CASE 2	CASE 3
7. Enter R_{BASE} from Table 5-5			
8. Enter R_{SOIL} from Table 5-5			
9. Add lines 7 and 8			
10. Divide 1 by line 9 [units: Btu / ^{O}F x ft^{2} x h]			

STEP D: DETERMINE THE U-VALUE OF INSULATED CASE (U_{TOTAL})

	CASE 1	CASE 2	CASE 3
11. Add line 6 (R_{EFF}) and line 8 (R_{SOIL})			
12. Divide 1 by line 11 [units: Btu / ^{O}F x ft^{2} x h]			

STEP E: DETERMINE U-VALUE DIFFERENCE (U_{DELTA})

	CASE 1	CASE 2	CASE 3
13. Subtract line 12 from line 10 [units: Btu / ^{O}F x ft^{2} x h]			

Table 5-8: Energy Cost Savings and Simple Paybacks for Conditioned Basements

A: Concrete or Masonry Foundation Walls with Exterior Insulation

CONFIGURATION	DESCRIPTION	INSTALL. COST ($ PER LF)	ANNUAL ENERGY COST SAVINGS IN $ PER LINEAL FOOT (SIMPLE PAYBACK SHOWN IN PARENTHESES)				
			0-2000 HDD (LOS ANG)	2-4000 HDD (FT WORTH)	4-6000 HDD (KAN CITY)	6-8000 HDD (CHICAGO)	8-10000 HDD (MPLS)
EXTERIOR: HALF WALL 	4 FT: R-5 RIGID	4.44	0.22 (20.2)	0.91 (4.9)	1.11 (4.0)	1.32 (3.4)	1.64 (2.7)
	4 FT: R-10 RIGID	6.54	0.25 (26.2)	1.07 (6.1)	1.32 (5.0)	1.55 (4.2)	1.93 (3.4)
EXTERIOR: FULL WALL 	8 FT: R-5 RIGID	7.01	0.27 (26.0)	1.10 (6.4)	1.40 (5.0)	1.65 (4.2)	2.06 (3.4)
	8 FT: R-10 RIGID	10.87	0.33 (33.0)	1.32 (8.2)	1.70 (6.4)	2.00 (5.4)	2.51 (4.3)
	8 FT: R-15 RIGID	14.55	0.35 (41.6)	1.42 (10.2)	1.84 (7.9)	2.16 (6.7)	2.72 (5.3)
	8 FT: R-20 RIGID	18.35	0.37 (49.6)	1.48 (12.4)	1.92 (9.6)	2.25 (8.2)	2.84 (6.5)

B: Concrete or Masonry Foundation Walls with Interior Insulation (Costs do not include interior finish material)

INTERIOR: FULL WALL 	8 FT: R-6 RIGID	4.72	0.27 (17.5)	1.12 (4.2)	1.42 (3.3)	1.67 (2.8)	2.09 (2.3)
	8 FT: R-8 RIGID	5.76	0.29 (19.9)	1.19 (4.8)	1.52 (3.8)	1.79 (3.2)	2.24 (2.6)
	8 FT: R-11 BATT	6.48	0.33 (19.6)	1.33 (4.9)	1.72 (3.8)	2.02 (3.2)	2.53 (2.6)
	8 FT: R-19 BATT	10.24	0.37 (27.7)	1.47 (7.0)	1.90 (5.4)	2.23 (4.6)	2.82 (3.6)

C: Concrete or Masonry Foundation Walls with Interior Insulation (Costs include sheetrock on interior wall)

INTERIOR: FULL WALL 	8 FT: R-6 RIGID	12.32	0.28 (44.0)	1.14 (10.8)	1.46 (8.4)	1.72 (7.2)	2.15 (5.7)
	8 FT: R-8 RIGID	13.36	0.30 (44.5)	1.21 (11.0)	1.55 (8.6)	1.83 (7.3)	2.29 (5.8)
	8 FT: R-11 BATT	12.56	0.33 (38.1)	1.35 (9.3)	1.74 (7.2)	2.04 (6.2)	2.57 (4.9)
	8 FT: R-19 BATT	16.32	0.37 (44.1)	1.47 (11.1)	1.91 (8.5)	2.24 (7.3)	2.82 (5.8)

D: Pressure-Treated Wood Foundation Walls

WOOD: FULL WALL 	8 FT: R-11 BATT	2.44	0.12 (20.3)	0.49 (5.0)	0.67 (3.6)	0.78 (3.1)	0.98 (2.5)
	8 FT: R-19 BATT	3.79	0.15 (25.3)	0.58 (6.5)	0.81 (4.7)	0.94 (4.0)	1.20 (3.2)
	8 FT: R-30 BATT	9.70	0.17 (57.1)	0.65 (14.9)	0.91 (10.7)	1.06 (9.2)	1.35 (7.2)

Energy cost savings in this table are based on medium fuel prices shown in Table 2-3.

Table 5-9: Energy Cost Savings and Simple Paybacks for Unconditioned Basements

A: Concrete or Masonry Foundation Walls with Exterior Insulation

CONFIGURATION	DESCRIPTION	INSTALL. COST ($ PER LF)	ANNUAL ENERGY COST SAVINGS IN $ PER LINEAL FOOT (SIMPLE PAYBACK SHOWN IN PARENTHESES)				
			0-2000 HDD (LOS ANG)	2-4000 HDD (FT WORTH)	4-6000 HDD (KAN CITY)	6-8000 HDD (CHICAGO)	8-10000 HDD (MPLS)
EXTERIOR: HALF WALL 	4 FT: R-5 RIGID	4.44	0.03 (148)	0.13 (34.2)	0.23 (19.3)	0.30 (14.8)	0.41 (10.8)
	4 FT: R-10 RIGID	6.54	0.04 (163)	0.16 (40.9)	0.28 (23.4)	0.36 (18.2)	0.50 (13.1)
EXTERIOR: FULL WALL 	8 FT: R-5 RIGID	7.01	0.04 (175)	0.13 (53.9)	0.25 (28.0)	0.36 (11.7)	0.51 (13.7)
	8 FT: R-10 RIGID	10.87	0.05 (217)	0.14 (77.6)	0.32 (34.0)	0.45 (24.2)	0.65 (16.7)
	8 FT: R-15 RIGID	14.55	0.05 (291)	0.14 (104)	0.35 (41.6)	0.51 (28.5)	0.72 (20.2)
	8 FT: R-20 RIGID	18.35	0.05 (367)	0.15 (122)	0.37 (49.6)	0.54 (34.0)	0.77 (23.8)

B: Concrete or Masonry Foundation Walls with Interior Insulation (Costs do not include interior finish material)

INTERIOR: FULL WALL 	8 FT: R-6 RIGID	4.72	0.04 (118)	0.13 (36.3)	0.25 (18.9)	0.36 (13.1)	0.52 (9.1)
	8 FT: R-8 RIGID	5.76	0.04 (144)	0.13 (44.3)	0.28 (20.6)	0.40 (14.4)	0.57 (10.1)
	8 FT: R-11 BATT	6.48	0.05 (130)	0.14 (46.3)	0.32 (20.3)	0.46 (14.1)	0.66 (9.8)
	8 FT: R-19 BATT	10.24	0.05 (205)	0.15 (68.3)	0.37 (27.7)	0.53 (19.3)	0.76 (13.5)

C: Concrete or Masonry Foundation Walls with Interior Insulation (Costs include sheetrock on interior wall)

INTERIOR: FULL WALL 	8 FT: R-6 RIGID	12.32	0.04 (308)	0.13 (98.4)	0.26 (47.4)	0.38 (32.4)	0.54 (22.8)
	8 FT: R-8 RIGID	13.36	0.04 (344)	0.13 (103)	0.29 (46.1)	0.41 (32.6)	0.58 (23.0)
	8 FT: R-11 BATT	12.56	0.05 (251)	0.14 (89.7)	0.33 (38.1)	0.47 (26.7)	0.67 (18.7)
	8 FT: R-19 BATT	16.32	0.05 (326)	0.15 (109)	0.37 (44.1)	0.53 (30.8)	0.76 (21.5)

D: Pressure-Treated Wood Foundation Walls

WOOD: FULL WALL 	8 FT: R-11 BATT	2.44	0.03 (81.3)	0.?? ()	0.16 (15.3)	0.23 (10.6)	0.31 (7.9)
	8 FT: R-19 BATT	3.79	0.04 (94.8)	0.05 (75.8)	0.18 (21.1)	0.27 (14.0)	0.39 (9.7)
	8 FT: R-30 BATT	9.70	0.04 (243)	0.05 (194)	0.21 (46.2)	0.32 (30.3)	0.45 (21.6)

E: Concrete or Masonry Foundation Walls with Ceiling Insulation

CEILING		INST. COST ($ PER SF)	ANNUAL ENERGY COST SAVINGS IN $ PER SQUARE FOOT (SIMPLE PAYBACK SHOWN IN PARENTHESES)				
	R-11 BATT	0.34	0.01 (34.0)	0.01 (34.0)	0.04 (8.6)	0.06 (5.7)	0.09 (3.8)
	R-19 BATT	0.52	0.01 (52.0)	0.01 (52.0)	0.05 (10.4)	0.07 (7.4)	0.10 (5.2)
	R-30 BATT	0.86	0.01 (86.0)	0.00	0.06 (14.3)	0.10 (8.6)	0.15 (5.7)

Energy cost savings in this table are based on medium fuel prices shown in Table 2-3.

Table 5-10: Energy Cost Savings and Simple Paybacks for Crawl Space Foundations

A: Unvented Crawl Space - Concrete or Masonry Foundation Walls with Exterior Insulation

CONFIGURATION	DESCRIPTION	INSTALL. COST ($ PER LF)	ANNUAL ENERGY COST SAVINGS IN $ PER LINEAL FOOT (SIMPLE PAYBACK SHOWN IN PARENTHESES)				
			0-2000 HDD (LOS ANG)	2-4000 HDD (FT WORTH)	4-6000 HDD (KAN CITY)	6-8000 HDD (CHICAGO)	8-10000 HDD (MPLS)
EXTERIOR VERTICAL 	2 FT: R-5 RIGID	2.00	0.04 (50.0)	0.15 (13.3)	0.25 (8.0)	0.30 (6.7)	0.39 (5.1)
	2 FT: R-10 RIGID	2.97	0.04 (74.3)	0.18 (16.5)	0.30 (9.9)	0.35 (8.5)	0.47 (6.3)

B: Unvented Crawl Space - Concrete or Masonry Foundation Walls with Interior Insulation

INTERIOR VERTICAL 	2 FT: R-5 RIGID	1.15	0.04 (28.8)	0.13 (8.8)	0.32 (3.6)	0.30 (3.8)	0.38 (3.0)
	2 FT: R-10 RIGID	2.12	0.04 (53.0)	0.15 (14.1)	0.28 (7.6)	0.35 (6.1)	0.46 (4.6)
INTERIOR VERTICAL AND HORIZONTAL 	2 FT/2 FT: R-5 RIGID	2.28	0.05 (45.6)	0.13 (17.5)	0.27 (8.4)	0.37 (6.2)	0.50 (4.6)
	2 FT/4 FT: R-5 RIGID	3.42	0.06 (57.0)	0.11 (31.1)	0.35 (9.8)	0.37 (9.2)	0.53 (6.5)
	2 FT/2 FT: R-10 RIGID	4.24	0.05 (84.8)	0.14 (30.3)	0.30 (14.1)	0.41 (10.3)	0.57 (7.4)
	2 FT/4 FT: R-10 RIGID	6.36	0.05 (127)	0.12 (53.0)	0.34 (18.7)	0.43 (14.8)	0.62 (10.3)

C: Unvented Crawl Space - Pressure-Treated Wood Foundation Walls

WITHIN WOOD WALL 	2 FT: R-11 BATT	1.32	0.02 (66.0)	0.06 (22.0)	0.10 (13.2)	0.12 (11.0)	0.17 (7.8)
	2 FT: R-19 BATT	1.76	0.02 (88.0)	0.06 (29.3)	0.12 (14.7)	0.15 (11.7)	0.21 (8.4)

D: Vented Crawl Space - Concrete or Masonry Foundation Walls with Ceiling Insulation

		INST. COST ($ PER SF)	ANNUAL ENERGY COST SAVINGS IN $ PER SQUARE FOOT (SIMPLE PAYBACK SHOWN IN PARENTHESES)				
CEILING 	R-11 BATT	0.34	0.04 (8.5)	0.06 (5.7)	0.10 (3.4)	0.15 (2.3)	0.19 (1.8)
	R-19 BATT	0.52	0.05 (10.4)	0.06 (8.7)	0.12 (4.3)	0.18 (2.9)	0.23 (2.3)
	R-30 BATT	0.86	0.05 (17.2)	0.07 (12.3)	0.13 (6.6)	0.19 (4.5)	0.25 (3.4)

Energy cost savings in this table are based on medium fuel prices shown in Table 2-3.

Table 5-11: Energy Cost Savings and Simple Paybacks for Slab-on-Grade Foundations

A: Concrete or Masonry Foundation Wall with Exterior Insulation Placed Vertically

CONFIGURATION	DESCRIPTION	INSTALL. COST ($ PER LF)	ANNUAL ENERGY COST SAVINGS IN $ PER LINEAL FOOT (SIMPLE PAYBACK SHOWN IN PARENTHESES)				
			0-2000 HDD (LOS ANG)	2-4000 HDD (FT WORTH)	4-6000 HDD (KAN CITY)	6-8000 HDD (CHICAGO)	8-10000 HDD (MPLS)
EXTERIOR VERTICAL 	2 FT DEEP: R-5	2.25	0.03 (75.0)	0.13 (17.3)	0.29 (7.8)	0.35 (6.4)	0.40 (5.6)
	2 FT DEEP: R-10	3.50	0.03 (117)	0.16 (21.9)	0.34 (10.3)	0.41 (8.5)	0.47 (7.4)
	4 FT DEEP: R-5	3.53	0.03 (118)	0.16 (22.1)	0.35 (10.1)	0.43 (8.2)	0.49 (7.2)
	4 FT DEEP: R-10	5.70	0.04 (142)	0.19 (30.0)	0.43 (13.3)	0.52 (11.0)	0.60 (9.5)
	4 FT DEEP: R-15	7.69	0.04 (192)	0.20 (38.5)	0.46 (16.7)	0.56 (13.7)	0.65 (11.8)
	4 FT DEEP: R-20	9.68	0.04 (242)	0.21 (46.1)	0.48 (20.2)	0.59 (16.4)	0.68 (14.2)

B: Concrete or Masonry Foundation Walls with Interior Insulation Placed Vertically

INTERIOR VERTICAL 	2 FT DEEP: R-5	1.30	0.03 (43.3)	0.12 (10.8)	0.27 (4.8)	0.32 (4.1)	0.38 (3.4)
	2 FT DEEP: R-10	2.19	0.03 (73.0)	0.13 (16.8)	0.30 (7.3)	0.36 (6.1)	0.43 (5.1)
	4 FT DEEP: R-5	2.59	0.03 (86.3)	0.14 (18.5)	0.33 (7.8)	0.40 (6.5)	0.48 (5.4)
	4 FT DEEP: R-10	4.40	0.04 (110)	0.16 (27.5)	0.39 (11.3)	0.47 (9.4)	0.57 (7.7)
	4 FT DEEP: R-15	6.23	0.04 (156)	0.17 (36.6)	0.41 (15.2)	0.50 (12.5)	0.60 (10.4)
	4 FT DEEP: R-20	8.06	0.04 (201)	0.17 (47.4)	0.42 (19.2)	0.52 (15.5)	0.62 (13.0)

C: Concrete or Masonry Foundation Walls with Interior Insulation Placed Horizontally Under Slab Perimeter

INTERIOR HORIZONTAL 	2 FT WIDE: R-5	1.65	0.03 (55.0)	0.11 (15.0)	0.26 (6.3)	0.32 (5.2)	0.39 (4.2)
	2 FT WIDE: R-10	2.80	0.03 (93.3)	0.12 (23.3)	0.29 (9.7)	0.36 (7.8)	0.44 (6.4)
	4 FT WIDE: R-5	2.69	0.03 (89.7)	0.12 (22.4)	0.31 (8.7)	0.40 (6.7)	0.49 (5.5)
	4 FT WIDE: R-10	4.52	0.03 (151)	0.12 (37.7)	0.34 (13.3)	0.47 (9.6)	0.56 (8.1)

D: Concrete or Masonry Foundation Walls with Exterior Insulation Extending Outward Horizontally

EXTERIOR HORIZONTAL 	2 FT WIDE: R-5	3.53	0.03 (118)	0.28 (12.6)	0.47 (7.5)	0.51 (6.9)	0.56 (6.3)
	2 FT WIDE: R-10	5.70	0.03 (190)	0.26 (21.9)	0.48 (11.9)	0.53 (10.8)	0.60 (9.5)
	4 FT WIDE: R-5	4.43	0.03 (148)	0.27 (16.4)	0.47 (9.4)	0.52 (8.5)	0.58 (7.6)
	4 FT WIDE: R-10	7.90	0.03 (263)	0.25 (31.6)	0.48 (16.5)	0.56 (14.1)	0.63 (12.5)

Energy cost savings in this table are based on medium fuel prices shown in Table 2-3.

References

American Concrete Institute (ACI) 1980. *Guide to Concrete Floor and Slab Construction*, 302.1R-80, 46 pp., Detroit, Michigan.

American Concrete Institute (ACI) 1983. *Construction of Slabs on Grade*, SCM4-83, 96 pp., Detroit, Michigan.

ASHRAE 1989a. ASHRAE Standard 62-1989, *Ventilation for Acceptable Indoor Air Quality*, American Society of Heating , Refrigerating, and Air-Conditioning Engineers, Inc., Atlanta, Georgia.

ASHRAE 1989b. ASHRAE Standard 90.2P Draft 89-1, American Society of Heating, Refrigeration, and Air-Conditioning Engineers, Atlanta, Georgia, March, 1989.

Christian, J.E., Strzepek, W. R. 1987. Procedure for Determining the Optimum Foundation Insulation Levels for New, Low-Rise Residential Buildings, *ASHRAE Transactions*, V. 93, Pt. 1, January, 1987.

Christian, J.E. 1989. Worksheet for Selection of Optimal Foundation Insulation, *Conference on Thermal Performance of the Exterior Envelopes of Buildings IV*, Orlando, Florida, December 4-7, 1989.

Council of American Building Officials 1989. *Model Energy Code*, 1989 Edition, The Council of American Building Officials, Falls Church, Virginia, March, 1989.

Dudney, C.S., Hubbard, L.M., Matthews, T.G., Scolow, R.H., Hawthorne, A.R., Gadsby, K.J., Harrje, D.T., Bohac, D.L., Wilson, D.L. 1988. *Investigation of Radon Entry and Effectiveness of Mitigation Measures in Seven Houses in New Jersey*, ORNL-6487, Draft, September, 1988.

EPA 1987. *Radon Reduction in New Construction: An Interim Guide*, United States Environmental Protection Agency, Offices of Air and Radiation and Research an Development, Washington, D.C., 20460, EPA-87-009, August, 1987.

EPA 1986. *Radon Reduction Techniques for Detached Houses: Technical Guidance*, 50 pp., EPA/625/5-86/019.

Labs, K., Carmody, J., Sterling, R., Shen, L., Huang, Y.J., Parker, D. 1988. *Building Foundation Design Handbook*, ORNL/Sub/86-72143/1, May, 1988.

Jones, R.A. 1980. *Crawl Space Houses*, Circular Series F4.4, Small Homes Council/Building Research Council, Univ. of Illinois, Urbana-Champaign, Illinois, 8 pp.

National Council on Radiation Protection and Measurements (NCRP) 1984. *Evaluation of Occupational and Environmental Exposures to Radon and Radon Daughters in the United States*. NCRP Report 78. Washington, D.C.: National Council on Radiation Protection and Measurements.

National Forest Products Association (NFPA) 1987. *Permanent Wood Foundation System; Design, Fabrication and Installation Manual*, NFPA, Washington, D.C., September, 1987.

Nero, A. V. 1986. "The Indoor Radon Story," *Technology Review*, January, 1986.

Sextro, R.G., Moed, B.A., Nazaroff, W.W., Revzan, K.L., and Nero, A.V. 1987. *Investigations of Soil as a Source of Indoor Radon*, ACS Symposium Series Radon and Its Decay Products Occurrence, Properties, and Health Effects, American Chemical Society.

U. S. Census 1987. *Statistical Abstracts of the United States*, 107th edition.

Index

A

Air management, 9, 20-23, 46-47, 66-69
Air space, 18, 30, 32
Anchor bolts, 16, 31-32, 43, 53-54, 63, 75
Assumptions used in insulation analysis, 15, 41-42, 62

B

Backfill, 17, 31-32, 35, 53
Basement
  checklist, 33-37
  details, 24-32
  drainage / waterproofing measures, 17, 31, 35
  insulation, 10-15, 18, 31-32, 91-92, 104-105
  radon control techniques, 20-23, 31, 37
  structural design, 16, 31-32
  termite / wood decay control techniques, 18-19, 36
Bond beams, 18, 32, 45, 54, 65, 67
Brick veneer, 71, 74-75
Builder / subcontractor markup, 15, 41, 62, 86
Building permits / plans, 37, 58, 79

C

Caulking, 31, 53, 66
Ceiling insulation
  crawl space, 39-41, 44-45, 54, 93, 106
  unconditioned basement, 11-15, 18, 32, 92, 105
Checklists, 33-37, 55-58, 76-79
Climate data, 89-90
Collection system, soil gas, 21-23, 67-69
Concrete foundation wall
  details, 25-26, 28-29, 49, 51-54, 72-73
  insulation placement, 11-15, 39-43, 60-62, 64-65
  structural design, 16, 31-32, 34, 53-54, 63-65, 75
Concrete shrinkage cracking, minimizing, 16, 20-21, 31, 63, 67, 75
Construction costs, 7
Construction details
  basement, 24-32
  crawl space, 48-54
  slab-on-grade foundation, 70-75
Control joints, 21, 67
Cooling degree hours, 81, 84-85, 89-90
Cooling load factor coefficients, 96
Cooling system SEER, 15, 41, 62, 97
Cost savings, energy, 82, 104-107
Costs, insulation installation, 14-15, 40-41, 61-62, 86
Costs, labor / material, 7, 86
Crawl space
  checklist, 55-58
  details, 48-54
  drainage / waterproofing techniques, 43-44, 53
  insulation, 38-42, 44-45, 53-54, 93, 106
  radon control techniques, 42, 46-47, 58
  structural design, 42-43, 53-54, 56
  termite / wood decay control techniques, 45-46, 57
  vented vs. unvented, 38, 40, 43
  vents, 38, 43, 47, 54

D

Dampproofing, 17, 21, 31, 35, 43-44
Decay control, wood, 18-19, 36, 45-46, 57, 65-66, 78
Depressurization, 21-23, 67-69
Design decisions, 4-7
Details, construction
  basement, 24-32
  crawl space, 48-54
  slab-on-grade foundation, 70-75
Discharge system, 21-23, 67-69
Dollar savings, 82-85
Downspouts, 18, 20, 43, 45, 63, 65
Drainage systems, 17, 31-32, 35, 43-44, 53, 63-64

Drainpipes, 23, 31-32, 53, 67
Duct/pipe insulation, 11, 15, 18, 41, 43

E

Effective R-values, 97
Energy cost savings, 82, 104-107
EPS insulation, 18, 31-32, 45, 53-54, 75
Equipment efficiencies, heating and cooling, 15, 41, 62, 97
Expansive soil, 6, 16, 43, 63

F

Fans, discharge, 21-23, 69
Fiberglass insulation, 31, 53
Filter fabric, 31, 53
Flame spread/fire retardant, 32, 45, 53, 86
Floor/slab, 20-21, 32, 34, 63-65
Footing
  basement, 16, 31-33
  crawl space, 42-43, 53-54, 56
  slab-on-grade, 63-65, 75, 77
Formulas, worksheet, 81, 88
Foundations, introduction to, 1-7
Frost penetration depth, 16, 31, 43, 53, 63-64, 75
Fuel price assumptions, 14, 41, 61

G

Gaskets, 28, 32
Grade beams, 63-64, 71, 75
Gravel bed/layer, 31-32, 43, 67-69, 75
Gutters, 18, 20, 43, 45, 63, 65

H

Heating degree days, 82, 89-90
Heating equipment efficiencies, 15, 41, 62, 97
Heating load factor coefficients, 95
Horizontal insulation, 40-41, 45, 60-62, 64, 94, 107

I

Insulation
  basement, 10-15, 18, 31-32, 91-92, 104-105
  configurations, 10-15, 38-42, 59-62
  crawl space, 38-42, 44-45, 53-54, 93, 106
  energy savings, 82, 104-107
  exterior vs. interior placement, 18, 44-45, 62, 64
  horizontal placement, 40-41, 45, 60-62, 64, 94, 107
  installation costs, 14-15, 40-41, 61-62, 86
  R-values and costs, 94
  slab-on-grade foundation, 59-62, 64-65, 75, 94, 107
  See also Ceiling insulation; Subslab insulation
Isolation joints, 31, 66, 75

L

Labor/material costs, 7, 86
Life cycle cost analysis, 11, 40, 61, 80-88
Loads, lateral/vertical, 16, 42, 63

M

Market preferences, 7
Markup, builder/subcontractor, 15, 41, 62, 86
Masonry foundation wall
  details, 27, 50, 72-74
  insulation, 11-15, 39-43, 60-62, 64-65
  structural design, 16, 32, 53-54, 63, 65, 75
MEPS insulation, 31-32, 53-54, 75
Moistureproofing. *See Dampproofing or Waterproofing*
Mortgage rates, 82, 85, 98

P

Paybacks, 11, 40, 62, 104-107
Piles/piers, 43
Plans/permits, 37, 58, 79
Plumbing, 20-21, 67
Polystyrene, 18, 31-32, 45, 53-54, 75
Porches, 19, 46, 66

R

Radon
  basement design techniques, 20-23, 31, 37
  collection/discharge systems, 21-23, 67-69
  crawl space design techniques, 42, 46-47, 58
  general mitigation techniques, 8-9
  slab considerations, 66-69, 79
Reinforcing, 16, 31-32, 54, 67, 75
Rim joists, 18, 32, 44
R-TOTAL, R-BASE, R-EFF, 88
R-VALUES, effective, 97

S

Scalar ratios, 82, 85, 98
Seismic design considerations, 16, 43, 63
Shrinkage cracking, minimizing, 16, 20-21, 31, 63, 67, 75
Sill plate
  basement, 18-19, 31
  crawl space, 44-46, 53
  slab-on-grade, 65, 75
Site considerations, 6
Site inspection, 37, 58, 79
Sitework, 33, 55, 76
Slab-on-grade foundation
  checklists, 76-79
  details, 70-75
  drainage / waterproofing, 63-64, 75
  insulation, 59-62, 64-65, 75, 94, 107
  radon control techniques, 66-69, 79
  structural design, 63-65, 75, 77
  termite / wood decay control techniques, 65-66, 78
Slabs, concrete, 16, 31-32, 34, 63-67, 75-76
Slab / wall joints, 19-20, 60-66
Soil. *See Backfill; Expansive soil; Frost penetration depth*
Soil gas. *See Radon*
Stack pipes / effects, 22-23, 67-69
Standpipes, 22-23, 67-69
Subdrainage, 17, 31-32, 35, 43-44, 53
Subslab insulation, 32, 61-62, 73-75, 94, 107
Sumps, 21-23, 44
Surface drainage, 17, 31-32, 35, 43-44, 53, 63-64, 75

T

Termite / wood decay control, 18-19, 36, 45-46, 57, 65-66, 78

U

U-DELTA, 82-88
Underfloor / underslab insulation, 32, 61-62, 73-75, 94, 107

V

Vapor retarder / control
  basement, 18, 31-32, 36
  crawl space, 45, 47, 53-54, 57
  slab-on-grade foundation, 75, 78
Ventilation. *See Air management; Crawl space; Radon*
Vents, 38, 42, 47, 54

W

Walls, foundation. *See Concrete foundation wall; Masonry foundation wall; Wood foundation wall*
Waterproofing, 17, 31, 35, 43-44, 53, 63-64
Weather data, 89-90
Weep holes, 23, 32, 67
Welded wire fabric, 16, 20, 31, 63, 67, 75
Wood decay control, 18-19, 36, 45-46, 57, 65-66, 78
Wood foundation wall
  detail, 30
  insulation, 11-15, 39-43, 91-93, 104-106
  structural design, 16, 18, 32, 45
Worksheets, 80-88, 100-103

X

XEPS insulation, 31-32, 53-54, 75

Rainwater Harvesting 101

Rainwater Harvesting Systems

RAINWATER HARVESTING 101

GROWNYC

Robert J. Kafin, Esq., Chairman

Marcel Van Ooyen, Executive Director

Prepared by:
Julia Leung, DEC Summer Intern
for
GrowNYC
51 Chambers Street, Room 228
New York, NY 10007
(212) 788-7900

August 2008

PREFACE

GrowNYC is a hands-on non-profit that has been improving New York City's environment for over thirty years. GrowNYC's dedicated staff green our neighborhoods, create the environmental leaders of the future, promote waste prevention and recycling, and run the largest farmers market program in the country. GrowNYC achieves its mission through the following projects and programs: The Open Space Greening Program, Greenmarket, The New Farmer Development Project, Environmental Education Training Student Organizers, Learn It, Grow It, Eat It and Office of Recycling Outreach and Education.

The Open Space Greening Program (OSG) empowers people in neighborhoods throughout the city to create, manage and sustain community gardens and park/playgrounds. OSG provides best practices workshops, services, tools, donated plant material, and open space planning/mapping information and other services. Grow Truck provides tools, donated supplies, plants and horticultural advice and assistance to gardening groups all over New York City. The Plant-A-Lot Project gives substantial material and technical assistance to several new gardens each year and helps the 45 existing gardens created in prior years.

Since 2002, OSG staff has taken the lead in building and maintaining rainwater harvesting systems in community gardens across the five boroughs, leading educational workshops, assisting community gardeners in identifying alternate water resources and building low cost systems. GrowNYC is an active member of the Water Resources Group, a network of NYC greening and environmental organizations promoting sustainable water conservation practices in NYC. The New York State Department of Environmental Conservation (DEC) recognized GrowNYC's efforts with The Environmental Excellence Award in 2006. This manual was created to disseminate to a wide audience the design parameters and building techniques used by GrowNYC staff.

Summer intern was able to prepare this document thanks to a grant from The New York State Department of Environmental Conservation in 2008 for Pollution Prevention. Ms. Leung provided many of the photos, charts, and drawings used. OSG staff, Lars Chellberg, and Lenny Librizzi provided invaluable guidance, advice, and editing of the manual. GrowNYC Executive Director Marcel Van Ooyen and Assistant Executive Director Julie Walsh edited the text. Additional information and assistance was provided by NYC community gardeners and members of the Water Resources Group.

Table of Contents

Introduction of Rain Water Harvesting 2
- History of Rain Water Harvesting 5
- Benefits of Rain Water Harvesting in Urban Areas 6
- Current Efforts 7

Materials 10
- Where to obtain supplies 11
- Cost Estimates 12
- PVC Applications 14
- Sizing of the tank and roof washer 18

Construction 21
- Tank 23
- Leaders 26
- Roof Washer 30
- Overflow 33
- Anchoring 36
- Drip Irrigation 39
- Filtration Systems 41
- Treatment 42
- Aesthetics 43
- Roofing Material 45

Seasonal Maintenance 46

Living with the RWH system 47

Existing RWH Systems 48

10 Ways to Conserve Water 49

Bibliography 50

Feedback Form 51

Introduction

"It isn't easy to come up with 'one size fits all' instructions for building rainwater harvesting systems because of variations in styles of roofs, downspouts, storage tanks, and garden layouts. You have to use a combination of research, common sense, ingenuity, and dumb luck to design and build your system."

-Lenny Librizzi, Assistant Director of Open Space Greening at GrowNYC

Rain water harvesting (RWH) is the means of collecting and storing rain water in large, durable containers, usually, collecting from rooftop gutters. RWH systems come in a variety of shapes and sizes (see pictures below).

Rain water harvesting systems are fairly easy to construct. Tanks in NYC community gardens range in size from 300 to 1000 gallons but can be as small as 55 gallons and as big as 10,000 gallons. Rain water collected from the downspout of an adjacent building or shed in the garden is redirected to the water storage area in the garden. The RWH system includes 3 parts (see drawing): the tank **(1),** the first flush **(2)** and the overflow pipe **(3).**


Gutter
Existing downspout
①
Polyethelene storage tank
②
First flush
Adjacent building
③
Overflow pipe
④
Winterizing tee plunger in place in summer, removed in winter
⑤
Rain garden with drought and moisture tolerant planting
vented opening
Raised platform, 15" - 18" on gravel or concrete
Drain after rain
Sewer or splash basin

During a rainfall event water from the gutter flows into the downspout. Instead of the water going into the sewer system, the rainwater harvesting system diverts the water into pipes. This diverter consists of a 3 way tee with a plunger in place during the summer. This plunger keeps the water from entering the downspout and forces it to flow into the harvesting system. It is taken out in the winter when rainwater is no longer collected **(4).**

Here is a closer view of how the plunger works.


Summer: plunger diverts water into system
cap to remove plunger
Winter: plunger is removed so water does not enter system
④

The pipes lead to a roof washer system which is a containment area for the first few gallons of water. Since the initial flushes of water contain rooftop debris and leaves, the roof washer acts as a filtering system by separating the dirty water from the cleaner water. Once the roof washer is full, the cleaner water enters the rain tank. As soon as the tank is full, excess water flows into the overflow pipe which leads to an adjacent rain garden **(5),** is directed back to where it originally flowed or piped underground. A rain garden is a plot containing hardy plants that can survive with both saturated and dry soil.

History of rainwater harvesting

Rainwater harvesting is an ancient practice. Many different cultures have used this technology for agricultural purposes. The Philippines have been using rain water for rice terraces for thousands of years now. Indian history indicates that rain water systems have been in use since 3000 BC. Usage can also be traced back 2000 years ago in Thailand and other parts of Southeast Asia, where simple gutters were used to fill jars and pots. The earth dams of ancient Egypt were used to control runoff. Ancient rain water cisterns can still be seen on the islands of Capri and Malta.

In addition to rainwater harvesting, the Romans also used their systems as air conditioners. When the water evaporated, it created a cooling effect in the microclimate. As their populations started to increase, the Romans developed underground cisterns. This way, less water would be lost due to evaporation. They connected these cisterns to above ground pools as a means of water filtration. When these pools overflowed, the cleaner water would enter the cisterns. This design was an inspiration for modern day rain barrels. The Roman's shallow pool mirrors the modern day roof washer or first flush system.

The world's largest cistern is the Yerebatan Sarayi, built by Caesar Justinian in 527 AD. It is located in modern day Turkey and is a popular tourist attraction. It is 140 meters by 70 meters big and can store up to 80,000 meters^3 of water. This huge structure is completely underground and involves a series of intersecting vaults. Binbirdik is another cistern in Istanbul, created by Caesar Constantine in 389 AD that can store 80,000 meters^3. However construction of these cisterns stopped due to the difficulty of building underground and the outbreak of human fecal contamination in large cities. [1]

In the 1970's, a new technology of rain water harvesting was developed where storm water was stored in well storage tanks in the form of different sized ponds. A thin layer of red clay was used to line the bottom of the pond to prevent seepage and trees were planted around the pond to prevent excessive evaporation. Over 40,000 of these systems were built in the Loess Plateaus of China. [2]

Although rain water harvesting was a significant and successful design in the past, its popularity has declined over the centuries. Urbanization demanded a more centralized water supply system. Watersheds and pipelines came into use and running water became one of the world's greatest inventions. However, due to modern day water pollution and drought, rainwater harvesting techniques have come back into practice again.

Benefits of rainwater harvesting in urban areas

By keeping storm water out of the sewage system, gardeners help keep their local water bodies clean. Because most of NYC is paved over, rainwater can't be absorbed by the ground. Instead, it runs across the pavement, picking up oil, street debris, animal feces and other waste as it moves. This runoff then enters the sewer system.

Unfortunately, not all runoff makes it to a treatment plant before entering the city's rivers and harbor. This is because most of NYC is on a combined sewer system, whereby the same pipes are used to transport both storm water runoff and household waste to sewage treatment plants. If these treatment plants overflow, the contaminated water then enters the water bodies surrounding NYC.

During dry weather the sewage treatment system generally works well, but these treatment plants can only handle about twice their dry weather volume. This means that heavy rains often result in combined sewer overflows (CSOs), which release untreated wastewater, storm water and street debris into local waterways. Untreated sewage can carry disease causing pathogens and nutrient rich organic material, which can choke the Harbor's ecosystem.

Not only can rainwater harvesting prevent water pollution, it also conserves water. Typical systems can store up to 1000 gallons of water. Harvesting during rainy days in spring and summer provides a source of water for the dry spells between rain events. Instead of running the hose to water your garden, you can use the rainwater stored in your tank. This will relieve the strain on our reservoirs and also save you money on your water bill. Forty percent of household water consumption is used on domestic irrigation! [3]

Rainwater harvesting has proven to be successful. The 35 rain water harvesting systems working in NYC's community gardens collect 422,900 gallons of water every year. That's enough for 264,313 toilet flushes!

Of course small scale construction of rainwater systems is not enough to significantly impact our environment. However, if rain barrels were used more extensively and rain gardens became a larger part of city landscape planning, water conservation would have a greater environmental impact. We would experience cleaner water bodies, less flooding and lower water costs.

Rain water harvesting has great potential to reduce rainwater flow into storm drains by collecting rainwater in gardens and can reduce the dependence on the NYC watershed. Every drop of water counts and conservation is the most sustainable, cost-effective source of water supply for our region.

Current efforts

Community gardeners across North America and around the world have revived the practice of using rain barrels in their gardens out of necessity.

In **Seattle**, budget constraints and rising water prices spawned the construction of rainwater harvesting systems. Some of Seattle's rainwater harvesting systems are works of art. Here gate pillars support the flow of rainwater from the building on the right into the cistern on the left. Seattle Public Utilities have recommended changes to the land use and building codes that encourage water conservation. SPU has also sponsored some wildly successful sales of rain barrels to Seattle residents.

The special curves on this gate represent the monthly rain fall in Seattle and the amount of water collected year round.

The overflow pipe of this Seattle cistern creates a mini waterfall.

A cat enjoying the rain garden in Kansas City.

The 10,000 Rain Gardens Program in **Kansas City** is an example of regional efforts to educate and introduce water conservation to the Kansas City community. Rain gardens are areas of vegetation on porous ground that can filter and drain excess storm water. Kansas City officials encourage their residents to plant these gardens on their own property.

The City of **Vancouver** designs and manufactures rain barrels for residents to use for irrigation (see picture on right). Vancouver subsidizes the cost of the rain barrels by 50%. Over 2000 barrels have already been sold.

Portland, Oregon, granted a permit for a household to harvest rainwater for use indoors during all but the dry summer months (see sketch and picture below). The water undergoes enough filtering to meet EPA's standards for drinking water. In 1998 this system cost less than $1,500 to install.


ROOF - APPROXIMATELY 1200 SQ FT
LEAF SCREAN COVERS GUTTERS
DOWNSPOUTS
MOSQUITO SCREEN COVERS CISTERN ENTRANCE
ROOF WASHER - WASTES INITIAL 12 GALLONS TRICKLE VALVE WITH HOSE TO SWALE AT BASE
1500 GALLON CISTERN
CISTERN OVERFLOW
ULTRAVIOLET STERILIZER
TO PLUMBING FIXTURES
VALVE
VALVE
VALVE
VALVE
CHECK VALVE
PUMP
VALVE
PRESSURE TANK
20
5
MICRON
FILTERS
WATER METER
APPROVED REDUCED PRESSURE BACKFLOW PREVENTION DEVICE (INSTALLED HORIZONTALLY)
MUNICIPAL WATER SUPPLY FROM STREET-SIDE METER
VALVE
BASEMENT

Maplewood, Minnesota has forged a coalition between its water and sanitation departments and residential landowners to plant large-scale curbside rain gardens that reduce storm-water sewage (see picture on left).

The Minnesota Arboretum uses its parking lots to demonstrate best landscape practices such as planting rain gardens and using permeable pavers to reduce contamination caused by storm water runoff (see picture on right).

The City of **Toronto** Downspout Disconnection Program offers a free service to homeowners to disconnect downspouts from the sewer system and install rain barrels which are available at a discount.

Chicago also encourages its citizens to disconnect downspouts. In addition, Chicago's Water Agenda 2003 included a rooftop garden initiative, a pilot program for permeable alleys, and rain gardens planted in the City's rights-of-way.

Austin offers rebates of up to $30 for newly installed rain barrels and of up to $500 for installation of rainwater harvesting systems, following design approval by the City.

In 2001, the first Drought Emergency to be announced since 1989 was declared in **New York City**. The reservoir levels were 40% below normal which resulted in mandatory water use restrictions. The Water Resources Group (WRG) was founded as a response to this single drought year. Since then WRG and GrowNYC have built 35 rainwater harvesting systems in New York City, collecting over 422, 900 gallons of storm water per year.

"New York City currently lags behind other cities like Boston and Chicago, which capture 90% of their combined sewage overflow; New York City only captures about 70%, according to the city"[4]

Materials

Every rain water harvesting system is different but they do have similarities. Here is a comprehensive list of tools and supplies. Your system will use many of these but may not require all of them.



Tools:

- Drill
- Hole saw attachment or jigsaw
- Screw drivers
- Hammer
- Level
- PVC saw (see top saw in picture) and metal hacksaw (bottom saw)
- Tin snips or sheet metal shears
- Crimping tool (see picture on right) and cable cutting tools



Gutters:

- Gutter lengths
- Leaders and bends
- Pre-fabricated gutter hangers
- Plumbing strap (for securing pipes to wall)
- Flexible, accordion style expandable plastic pipe
- Tube of gutter sealant and caulk gun to apply it
- PVC cleaner and cement
- Teflon tape (for creating a water tight seal on threaded bushings)





Barrel storage system:

- Tanks and PVC parts or other materials to construct the manifold. Here we have a capped 4 way tee (see leftmost picture) and a 90° and 45° elbow respectively (see rightmost picture)
- Window screen or screened vents for mosquito proof vent
- Bulk head fittings (An elongated compression fitting, which will allow pipe, to run through a bulkhead)
- Platform material such as treated lumber, plastic lumber or concrete blocks
- Eyebolts (for securing tank)
- Spigot
- Metal flanges of corresponding size to spigot and hardware
- Rope or cabling supplies to secure the tank

Where to obtain supplies

Polyethylene tanks are best purchased locally because of high shipping costs. Search online for local suppliers. You can personally ship smaller tanks and save on extra expenses. Here are some websites that sell tanks:

- http://www.liquidlogictanks.com/index.html
- http://www.tank-depot.com/
- http://www.rainbarrelsource.com/
- http://www.rainbarrelsandmore.com/
- http://www.aquabarrel.com/

Drip irrigation suppliers include:

- http://www.dripdepot.com/
- http://www.dripirrigation.com/
- http://www.rainbird.com/drip/index.htm
- http://www.dripworksusa.com/
- http://www.netafim.com/
- http://www.chapindrip.com/
- http://www.farmtek.com

Downspout filters and a variety of other specialized parts for systems can be purchased from:

- http://www.starkenvironmental.com/a-1-filtration.html
- http://www.braewater.com/
- http://www.rainharvesting.com.au/default.asp
- http://downspoutfilter.com/index.php
- http://rainharvest.com/shop/default.asp

Tools and PVC gutter pieces can be purchased at your local hardware stores. Lowes or Home Depot also sells these items. For locations near you, visit their websites at http://www.lowes.com/ or http://www.homedepot.com.

Cost Estimates

Note that the prices listed indicate the values in 2008. Adjust for a 15% – 20% annual increase.

Polyethylene tanks: Generally, tanks cost $1 per gallon but it can sometimes be too big to transport on your own. Shipping costs are about an additional $1 per gallon.

Leaders and Gutters: The number of leaders and gutters needed per site will vary depending on the roof configuration. A 10-foot long gutter is $15.00, a 10 foot long 2”x 3” leader is $9.00, and a 10 foot long 3”x 4” leader is $16.00. Connecting parts, corners and bends are anywhere from $2.00 to $10.00.

Platforms: Platforms for containers can be made out of cinder blocks, plywood or any other sturdy material. While the tank is light when it is empty, remember that a full tank of water can weigh thousands of pounds. A small 55 gallon tank weighs over 400 pounds when full! Be sure that your platform is strong enough to withstand large weights. Cement blocks can be scavenged from construction sites. Should you have to purchase them, 8” x16” cement blocks are $ 1.50 each. The lumber prices are $16.00 for a pressure treated 8 foot long 2”x 10” piece or $13.00 for a pine or fir 8-foot long 2”x 10” piece. An 8 foot long 4” x 4” piece costs $12.00. 4” x 4” lumber laid lengthwise in alternating directions placed on a gravel base makes a sturdy platform (see picture on page 25). Using poured concrete pilings and a built wooden deck for a platform may cost about $500.

Miscellaneous Hardware and specialized parts: This category includes accordion connector pieces, screens, sealants, sheet metal, screws, nuts, bolts, gravel, filtering parts and supplies, roof washers, weed fabric and other specialized parts. These parts will vary by site and type of barrel.

Plumbing Supplies: The amount of plumbing you need varies depending on the system you are making. This category includes overflow pieces, PVC pipes, connector pieces, rubber fittings, spigots, bulkhead fittings and the piping needed to draw the water away from the system. Upgrades will include soaker hoses or other type of overflow disperser and roof washers. A sophisticated drip irrigation system could add $500 – 1000 to the cost.

Tool Kit: Some specialty tools are needed such as drill bits, screw bits, hacksaw blades, tin snips, hole saws, caulk gun, caulking or silicon, jig saw, pliers and tape measures.

Cost analysis for a 300 gallon rainwater system in 2008

Tank	$300
Shipping of Tank	$300
Leaders and Gutters	$100
Platform	$300
Hardware	$100
Plumbing	$100
Tool Kit	$50
Total Cost	$1250

Cost analysis for a 1000 gallon rainwater system in 2008

Tank	$1000
Shipping of Tank	$1000
Leaders and Gutters	$200
Platform	$600
Hardware	$200
Plumbing	$200
Tool Kit	$50
Total Cost	$3250

If there is not already an existing roof or shed nearby, a shade structure can be constructed. One possible design is the winged structure seen here:



Cost analysis for a 300 gallon rainwater system with winged structure in 2008

Tank	$300
Shipping of Tank	$300
Leaders and Gutters	$100
Platform	$300
Hardware	$100
Plumbing	$100
Tool Kit	$50
Materials for Shade Structure	$2500
Total Cost	$3750

PVC Applications

Up to now PVC or polyvinyl chloride has been the key piping material in the rainwater harvesting systems in NYC community gardens. This hard plastic is inexpensive, durable, easy to use and readily available. Tees, elbows, bushings and couplings are all made out of PVC. Although PVC is fairly stable, there are environmental hazards in manufacturing and burning PVC. We are currently looking for other sources that are more environmentally benign but also having the same flexibility with parts as PVC does. Although metal can be an alternative, it can be costly. If there is a material that you think can be a replacement for PVC, please add your information or comment to this wiki: http://www.waterresourcesgroup.org/wiki/index.php?title=Main_Page.

In order to join PVC pipes together, use PVC specific cleaner primer and cement. PVC cleaner primer removes dirt and melts the surface for ultimate adhesion. After the pipe is clean, you can use cement to join the two pieces together. Only apply cleaner and cement to the outside part of the male piece (see picture on left) and the inside part of the female piece (see picture on right). It is important to hold the two pieces together for 20 seconds after applying the cement because they may move apart. After 20 seconds, the two pieces are permanently joined (see bottommost picture). Wipe off excess glue.





Use bushings and reducer fittings when it is necessary to change the size of your pipes. These come in a wide variety of glue (slip) and threaded designs.

This 2”x 1 ¼” slip bushing connects a 2” (diameter) piece of pipe with a 1 ¼ “pipe. Slip bushings can be adhered using the cleaner and cement method mentioned above.

This 2”x 1” slip and thread bushing connects a 2” slip pipe with a 1” threaded pipe. Thread bushings can be adhered tightly using Teflon tape. Roll the tape starting at the end of the male thread bushing towards the middle. Two or three wraps are sufficient.



PVC parts are very versatile since no two rainwater harvesting systems are alike. Many different combinations of PVC parts can be used for the same function. Here are 5 different ways to connect a 2” pipe with a ¾ “pipe.



It is very important to align adjacent pipes. The two tees in the first picture (see picture below) must align exactly in order to connect to the same wall. Careless glueing will lead to problems. Use a hard, level surface such as a concrete floor to help you align pipes.





The pipes in the second picture (see picture on left) must be exactly perpendicular to each other. The tee on the left will connect to the barrel. The tee on the right will connect to existing pipes. Use a marker to indicate the points where the one pipe must meet the other.

The pictures above also point out the use of piping. Notice how the two tees are joined in each picture. In the second picture, the two tees are joined by using a small piece of pipe in between them, called a sleeve. The interior coupling is too short to be seen in this picture. In a situation where you want the tees to be further apart, such as in the first picture, just extend the size of the pipe to the desired length.

Although every rainwater system must be carefully planned before actual construction begins, it is very easy to miscalculate or measure incorrectly. Often times, errors are not realized at first. To fix a measurement or connection problem where the 2 pipes that were intended to connect do not match up, use two 45° degree elbows. A combination of two 45° elbows will produce almost any twist or angle desired.



Two 45° elbows can make a 90° degree twist or a 180° degree twist.



Two pipes that did not connect before can now be connected with the help of two 45° elbows.

It is also possible to shorten the PVC pipe by cutting and reconnecting it with a rubber coupling. Notice that the pipe below is too long to connect with the smaller pipes attached to the wall (see top picture). It was shortened and reconnected using a rubber coupling (see bottom picture).





Sizing of the tank and roof washer

A variety of rainwater systems can be constructed for the same downspout and roof. Here are two different systems that have been installed over the years at the 1100 Block Bergen Garden in Brooklyn. It is generally better to have a single barrel rather than multiple barrels because of possible leakage from the numerous connections. The 9 barrels in the original system had 17 connections. There were 17 locations where leakage could occur as opposed to 1 location in the current system.





The capacity of the system should be determined by two factors: the size of the roof, which determines how much water can be collected and the size of the garden, which measures how much water is needed. A 300 gallon vertical cylindrical storage tank is approximately 42 inches in diameter and 51 inches tall. A 1000 gallon polyethylene tank is approximately 92 inches in diameter by 60 inches tall or 61 inches in diameter by 100 inches tall.

The amount of water you can harvest varies depending on the size of your roof. You will be surprised how much water you will be able to collect from even the smallest roof. **The rule of thumb is 600 gallons of water per inch of rain per thousand square feet of catchment area.** Not all the rain that falls can actually be collected. Efficiency is usually presumed to be 75% depending on system design and capacity. Here is the basic formula for calculating the potential amount that can be collected:

$$\frac{\text{(Catchment area)} \times \text{(inches of rain)} \times \text{(600 gallons)} \times (.75)}{\text{1000 square feet}}$$

Remember that a roof can have several downspouts. Your catchment area only consists of the region where the downspout that is connected to the rain barrel collects from. Pay attention to the gutter and slope of the roof to determine which part is your catchment area. In order to calculate the catchment area, use measuring tape to determine the width and length of your roof in square feet. Multiply the length and width of your catchment area for the area of your roof.

The sample roof shown below (see picture below[5]) has a catchment area that is 40 feet wide and 30 feet long. Hence, it has a 1200 square feet roof (40 feet wide x 30 feet long). Assume that it rains 2 inches. We can now plug this information into our general formula (see equation above).



Catchment Area = 1200 square feet
Amount of Rain = 2 inches
Gallons of water collected per inch of rain per 1000 square feet = 600 gallons
Percent Efficiency = 75% or .75

$$\frac{\text{(1200 square feet)} \times \text{(2 inches of rain)} \times \text{(600 gallons)} \times (.75)}{\text{1000 square feet}} = \text{1080 gallons}$$

Therefore a 1200 square foot roof will collect 1080 gallons of water on a day with 2 inches of rainfall. Using this formula and your region’s average rainfall numbers combined with an estimated water need, you should be able to calculate the approximate size of your tank or barrel system.

Roof washer sizes also differ according to the size of the roof. **The rule of thumb is one to two gallons of roof washer capacity for every 100 square feet of catchment area.** A 1 foot length of 6 inch diameter PVC pipe holds 1.5 gallons. A 1 foot length of 4 inch diameter PVC pipe holds .66 gallons.

We will use the same 1200 square foot roof shown above as an example. Since the rule of thumb suggests one gallon of roof washer capacity for every 100 square feet of catchment area, the sample roof will need 12 gallons of roof washer capacity.

If you are using 6 inch diameter pipe, use the following formula:

$$\frac{\textit{Number of gallons of roof washer capacity}}{\textit{1.5 gallons/ feet}}$$

The size of our roof washer on our sample roof can be calculated by:

$$\frac{\textit{12 gallons of roof washer capacity}}{\textit{1.5 gallons / feet}} = \textit{8 feet of 6” pipe}$$

If you are using 4 inch diameter pipe, use the following formula:

$$\frac{\textit{Number of gallons of roof washer capacity}}{\textit{.66 gallons / feet}} = \frac{\textit{12 gallons}}{\textit{.66 gallons/ feet}} = \textit{18 feet of 4” pipe}$$

Therefore a 1200 square foot roof will need 8 feet of 6” diameter pipe or 18 feet of 4” diameter pipe. Remember it is possible to separate long lengths of roof washers into several, continuous pipes instead of just one long pipe.

Construction

The first step of the construction project is to make a plan drawing. The plan drawing considers the location of the downspout and the amount of space available. Each system must include the tank, the first flush and the overflow. Here are some issues that should be considered in your planning:

- The most stable place to position your barrel is against a stable wall on level ground as close to the downspout as possible.
- Gravity moves water downhill. Be sure there is available space for a downward pitch in all pipes.
- The barrel on its platform is the highest point of the garden but the lowest point of the system.
- The overflow pipe should be directed toward a rain garden not toward pathways or structures.
- The overflow pipe should flow from the barrel's highest point.
- The spigot should be at the barrel's lowest point.




overflow pipe
roof washer system


roof washer system
overflow pipe

Tanks

Tanks can be made from all sorts of materials such as cement (see picture on left[6]), metal, ceramic and wood (see picture on right[7]). In tropical countries, a terra cotta tank can be used. No wintering tee is necessary for these tanks because there is no danger of freezing.

For design purposes, bladders can also be used to store water instead of tanks. Bladders are large, flexible bags functioning in a way similar to the water balloon (see picture on left[8]). This way, engineers can create storage tanks in a variety of shapes instead of the traditional cylinder.

The tank system includes the spigot, the inflow pipe, the overflow pipe, the lid and the platform it rests on.

Spigot: A variety of bushings can be used to connect the spigot. It is preferable to use a single reducer bushing but that is often not possible. For example, the tank's spigot hole is 2 inches in diameter. The spigot pictured here is a ¾ "ball valve hose bib. In order to reduce the 2" opening to the ¾"spigot, the following 3 bushings were used:





Lid: The lid should remain closed at all times. Still water is a haven for mosquito larvae. Inspect the lid and any vents annually and clean as necessary

Inflow and Overflow pipes: Some tanks come with bulkhead fittings installed for the inflow and overflow pipes. For those that don't, a hole saw is used to drill a large hole in the barrel. Two bushing pieces, like the ones pictured below, are used to fashion a bulkhead fitting.



Use a marker to trace the hole you will cut for the threaded bushings. Make the hole tight to the threads. Once the hole is prepared, thread the first piece in from the outside.







Thread the second piece from the inside of the tank using a flexible wrench. Use gutter sealant to create a watertight seal.



Platform: The purpose of the platform is to raise the tank enough to get your watering can under the spigot and to create pressure flow for a hose. Spread a thick gravel base over an area slightly larger than the platform. This will promote good drainage and allow for final leveling once the platform is built.

A stable arrangement of cement cinder blocks, like this one, makes a great platform for small 55 gallon tanks but is not ideal for larger tanks. Since the blocks easily shift, rot resistant 4”X 4” or 6”X 6” lumber laid out in alternating rows is the best option for a platform. Steel platforms are also a possibility but are more costly. Be sure to level and compact the ground well where the tank will sit.





Warning Signs: Do not drink the water collected. Only use it to irrigate your garden. Installed PVC is inert and it is used as a water supply pipe for house trailers and other homes. The possible contamination is almost exclusively from harmful bacteria. For water to meet drinking water standards it must be treated, usually with chlorine, often filtered and sometimes treated with ultraviolet light. A warning sticker or sign should be placed on your rain barrel to avoid the possibility of anyone mistakenly drinking the water.

Leaders

The leaders of the rain water harvesting system refer to the series of pipes that lead to the tank. This includes the pipe that connects the downspout, the wintering tee, the roof washer system and the pipe that connects the barrel. Gravity keeps the water flowing. Remember to put a downward pitch on all pipes. A quarter inch down for every linear foot will create an adequate pitch. Use a level (see picture below). It may be useful for someone to stand back to visually check the pitch and help you adjust the pipes as you are pitching them.


The museum is under 24 hour video surveillance.
Council On The Environment of New York City



Keep pipes pitched downward.



DO NOT pitch pipes upward.

Keep the pitch of your pipes even and downhill. The picture on top is correct. The picture on the bottom has an upward pitch and will create problems.

Connecting the downspout: Our intent with rain water harvesting is to divert storm water, store it for future use and keep it out of the sewers. There are several options to divert the rain water: insert a 3 way tee into the downspout (see picture on left) or connect the existing downspout directly to the rain barrel (see picture on right). You can design your own custom diverter as well.


existing
downspout
wintering tee


existing
downspout

Another possibility is to replace the downspout entirely with pipes leading to your rain water harvesing system (see picture below and on the next page).


remove downspout and
connect to gutter

Connecting to the downspout is one of the last steps in construction of your system. You do not want to disconnect your downspout and start collecting rainwater with an unfinished system.

Wintering tee: The purpose of the wintering tee is to allow the water to be directed back into the sewers during freezing temperatures. Rain water should not be collected at that time because it may freeze and cause breaks in the system. A simple wintering tee utilizes a removable plunger head. The plunger head blocks water flow into the sewer and forces it to enter the system. It is removed during the winter and rain water will just flow straight down into the sewer (see picture on left and diagram on page 4). Complicated wintering tees include a filtering system. It operates with the same principle but instead of a removable plunger head, there is a removable filter which catches debris (see picture on right).





Roof washer system: Refer to 'Roof washers' on page 30.

Connecting the barrel: Refer to 'Tanks' on page 23.

Here are some ideas to help you with the design of your leader.



INFLOW
1: 90° elbow
2: 4"pipe
3: 90° elbow
4: 45° elbow
5: 4"pipe
6: 45° elbow

OVERFLOW
7: 2"bushing
8: 90° elbow
9: 2"pipe

This design uses a separate inflow and overflow pipe.



INFLOW
1: downspout
2: 4"rubber coupling
3: cap
4: 4 way tee
5: rubber coupling
6: 90° elbow
7: 4"sleeve
8: 4"rubber coupling
9: 3 way tee

OVERFLOW
10: 45° elbow
11: 90° elbow
12: 4"pipe

This design uses the same tank opening for both the inflow and overflow.

Roof Washers

Roof tops are prone to collect leaves and dirt. The rain carries all this debris with it as it enters the gutter and downspout. The roof washer or first flush system is a simple way to filter the water you collect. It is a series of pipes that storm water flows into before entering the rain barrel. Once the roof washer is full, water will begin to fill the rain barrel without mixing with the dirty water contained in the first flush. The appropriate size of the roof washer varies depending on the size of the roof. Refer to ‘Sizing of the tank and roof washer system’ on page 18 for details on how to calculate roof washer size. Small first flush systems can be a single downward pipe. However, to accommodate larger roofs, first flush systems can be constructed of multiple downward pipes.





The roof washer must be emptied promptly after a rain event and valve reset in the closed position to be ready for the next rain. Drain the roof washer to a safe location. Include another spigot or valve in your design to drain the first flush.

An alternative to the container method of the roof washer is a device like the Flow-Rate Diverter by Safe Rain. It consists of a plastic ball attached to a spring. The top of the ball contains a screen and a movable tab. During a rainfall event, water that enters the pipe will either flow into the ball or on its sides (see picture on left). The purpose of the screen on top is to gradually allow water to enter the ball. Once the ball is filled, it will sink down and block the drain (see picture on right). Water can then start filling up the pipe and start entering the tank. The moveable tab controls the amount of water that enters the ball by covering or exposing the screen as desired. For example, larger barrels that require larger roof washers require a screen that is less exposed. Larger amounts of water will have to pass through the pipe before the ball can be filled. The ball will have a small drip hole to slowly empty once the rain has ended to then return to its original position to be ready for the next rainfall.

Entering rainwater will flow into this pipe. Some will enter the ball, making it heavier and some will flow past the ball and out of the pipe.





Once the ball is saturated with water, it will sink down and block the pipe. Water will fill up the pipe and finally enter the tank.



This device allows the overflow pipe to be connected to the roof washer pipe.

gradually enters the ball through this screen.

Here is an idea to help you design a roof washer of your own.



ROOF WASHER
1: 3 way tee
2: 6"pipe
3: 90° elbow
4: 6"pipe
5: 3 way tee
6: 6"pipe
7: 3 way tee
8: 6" pipe
9: drain valve

INFLOW
10: 6"x4" rubber coupling
11: 4" pipe
12: 45° elbow
13: 4"pipe
14: 45° elbow
15: 4"pipe
16: bushing

OVERFLOW
17: bushing
18: 90° elbow
19: 2"pipe
20: 90° elbow
21: 2" pipe

ANCHORING
22: plumber's strap

Although this rainwater harvesting system has a good roof washer design, it does not have a good overflow design. Excess water will back up into the inflow pipe before the overflow pipe starts working. The overflow pipe should also be the same diameter as the inflow pipe to avoid a bottleneck situation.

Overflow pipes

When the rain barrel reaches its capacity, the overflow pipe discharges the excess water so that water won't start spilling out from around the lid. Cut a hole near the top of the barrel and connect an overflow pipe there. Be sure that the overflow pipe is not directed toward water-sensitive structures or areas where water can collect and do damage. The overflow pipe should be the same size as the inflow pipe so that a bottleneck situation is avoided during heavy rainfalls.

Here are some ideas to help you design an overflow pipe of your own.



OVERFLOW
1: bushing
2: 2"pipe
3: 45° elbow
4: 45° elbow
5: 2" pipe



The overflow pipe is connected back to the sewer. Building systems close to the downspout requires less piping.

OVERFLOW
1: 2" pipe
2: 90° elbow
3: 2" pipe

Instead of directing water back into the sewer, you can direct the water into a rain garden, gravel filled trench or connect it to a drip irrigation system. Overflow can be turned into works of art. Here the overflow is turned into a small water course (see picture on below), which ultimately ends in a rain garden.



Rain gardens are depressed plots of land (see pictures below). It should be at the lowest point in the garden so that water can flow there easily. Dig a deep trench and fill it with 5 inches of gravel for seepage. Cover this area with burlap netting so that the soil will not sink down into the gravel. Place a couple of inches of soil on top and start planting. Only plants able to survive both dry and saturated soil should be grown. Native plants are also encouraged because they are more tolerant of local climate and soil conditions. These plants include wildflowers, ferns, shrubs and small trees. [9] Brooklyn Botanic Garden provides a thorough list of rain garden plants for different regions on their website at: http://www.bbg.org/gar2/topics/design/2004sp_raingardens.html

Bioswales are alternatives to rain gardens. They are depressions in the landscape with collections of rock, gravel and vegetation that act as a filter for water. They effectively strain silt, inorganic contaminants, organic chemicals and pathogens. The longer the water is trapped inside the bioswale, the easier it is for pollutants to be trapped. They are most commonly found surrounding a parking lot so that oil runoff can be filtered before entering the sewer system.[10]

Anchoring

Because the rain barrel is fairly light and may tip or fall when it is empty, it is important to anchor the system to the platform or a structure. The easiest method to tie down your system is to use nylon rope. Steel cable is also a solution. Since cabling is more complicated, we will illustrate these steps.

Cut a piece of steel aircraft cable and slip 5 cable swedges in it Use the first piece of cable swedge **(see picture 1)** and a crimping tool to connect it into a circle **(2).** Its circumference should be a less than the circumference of the rain barrel but more than that of the lid. Cut two more long pieces of steel cable. They should be at least twice the height of the rain barrel. Use one cable and slip it through two of the metal cable swedges that are already on the circle. Making sure both lengths of cable are even; use the crimping tool to secure the metal swedges in place. Do the same with the other cable and two metal swedges **(3).**







Screw a metal eyebolt into each of the four corners of your platform. Connect a turn buckle to each metal eyebolt **(4).** Place the series of cables onto your rain barrel. The circle should be on top of the rain barrel **(5).** The four hanging ends should be facing each corner of the platform. Loop the ends of the cables into the turn buckle **(6).** Use a metal swedge to secure the loop. Do this for all four corners. Finally, twist the turn buckles until the metal cables are taut **(7)** to finish securing your rain barrel **(8).**











For cinder block platforms, nail a thick wooden plank on top and use the eyebolt method mentioned above.
Pre-fabricated steel brackets are generally used to anchor horizontal tanks.

NOTICE
AVISO

It is a good idea to anchor pipes as well. If the pipe is hugging the rain barrel, anchor the pipe to that platform using cable **(see picture 1),** perforated plumber's strap **(2)** or other methods.



Pipes that are directly against the wall of a building can be secured to the wall using plumber's strap attached with tapcon screws, which seal the hole drilled in the wall to avoid leaks **(2).**



Drip Irrigation

Drip irrigation systems reduce water use. Small amounts of water are supplied to the base of plants. Since the water is applied directly to the soil, rather than onto the plant, evaporation from leaf surfaces is eliminated. The water is also placed where it is needed rather than sprayed over the entire garden.

With a drip system, water flows into a series of thin flexible hose lines. These irrigation hoses have tiny holes at even intervals. These hoses are placed on the surface or beneath a layer of mulch. When water enters the system, it slowly trickles out of these holes and waters the roots of plants (see pictures below[11]). The overflow of rain water harvesting systems is sometimes connected to these smaller pipes.





Tubing comes in many sizes (see pictures below[12]). It is used to get the water from the source to the garden. A variety of fittings are available to go around corners and to connect pieces.

In most cases, no special tools or skills are needed. Plastic pipe is punched with an inexpensive tube punch that assures the proper hole size. Spaghetti tubes snap into the hole. No gluing is required. Because the holes are small, they can easily be plugged if you put one in the wrong place.

Gravity Feed Drip Irrigation Kits are used to connect to rain barrels and rainwater harvesting systems where the water pressure is low (see picture below[13]). This system uses small ¼ inch valves instead of emitters to avoid the problem of clogged emitters


The Premium Gravity Feed Drip Irrigation Kit contains 136 pieces ...
x 2
x 1
x 40
x 40
x 40
x 1
x 2
x 2
x 5
x 2

Drip Irrigation systems need planning, but are neither expensive nor difficult to install. Most drip irrigation suppliers will help you design a system to best meet your gardening needs. Drip systems require periodic maintenance. Check regularly for leaks and broken connections.

Filtration Systems

This rain water harvesting system already has two means of filtration, one at the gutter **(see picture 1)** and the other at the roof washer **(2).**



The gutter filters out leaves and large debris.

The roof washer filters out the particulate matter found on rooftops.

This gutter screen that is put at the mouth of the downspout (see picture on right) prevents leaves and other large debris from entering the system. If you want to buy a filter, two choices are Rain Keeper Downspout filter for smaller roofs and the Rain Keeper Downspout collection filter for smaller systems. Refer to “Where to obtain supplies” on page 11 for more information.

Treatment

During warm weather, bacteria may grow inside the storage tank. Organic matter also poses a problem as algae or other contaminants may grow in storage tanks.WRG recommends adding a small amount of chlorine, in the form of unscented household bleach, to your water storage tank. Do not use bleach with any additives like fragrances or softeners. A log should be kept to ensure the proper addition of the chemical. Store log with bleach container. Please remember to wear gloves when handling bleach, to store bleach in a cool, dry place and to label bottle clearly to avoid improper use. On the 1st of each month, add a small amount of bleach to *each* water storage container. If the tank is emptied and refilled in less than one month's time, an application of bleach should be added to the tank when it refills

Tank Size	Amount of Bleach to Add
1000 gallons	1/3 cup
750 gallons	1/4 cup
500 gallons	3 tablespoons
50 gallons	2 teaspoons

Regularly emptying the roof washer and the addition of a small amount of bleach to your tank will ensure the water is safe for watering vegetables. The water stored in the tanks is for ***irrigation purposes only*.** It is safe to use on vegetables and other plants in the garden, but it is not safe to drink. The quality of this water does not comply with local and national drinking water standards.

Aesthetics

"The most beautiful system is carefully constructed and incorporates a carefully thought out, well designed and installed plumbing system."

-Lars Chellberg, GrowNYC staff member

Although a rain barrel is considered by some to be unsightly, it is easy to beautify your rain water harvesting system. PVC pipes and tanks can be covered by plants or painted (see pictures below).



A gazebo at this Seattle community garden covers an underground cistern that stores 5,000 gallons of collected rainwater (see picture below).

Promoting the sustainable practice of rain water harvesting is also important. For example, NYC community gardens use a “This garden harvests rain water” sign (see picture on right), a good idea to put in front of your system. Have printed information for people to learn more about rain water harvesting like this Water Resources Group brochure (see picture on left).



This Garden Conserves its Water

Even when the city is not experiencing a drought, it's important to remember that freshwater is rare.

Only 3% of the world's water is fresh, or drinkable. Pollution further limits this resource. Over 1 billion people globally do not have access to good drinking water.

NYC'S WATER SUPPLY SYSTEM

Every day NYC uses 1.3 billion gallons of water from upstate reservoirs. When we waste water, we deplete these reservoirs.

...and Helps to Prevent Pollution

By harvesting rainwater, this garden helps prevent pollution during heavy rains.

Here's why...

COMBINED SEWER OVERFLOWS

In New York City, a combined sewer system uses the same pipes to transport both household waste and stormwater to sewage treatment plants.

During heavy rains, the sewer system is overloaded and untreated sewage overflows into rivers and estuaries. By reducing the amount of rainwater entering the sewer system, we limit the environmental damage from combined sewer overflows.

NONPOINT SOURCE POLLUTION

In the wilderness, rainwater is absorbed by the land. But in New York City most rainwater goes into the nearest storm drain. As stormwater runs across the pavement, it picks up contaminants like oil, grease, animal waste, chemicals and trash. This polluted runoff then flows into the nearest waterbody. This pollution, which does not come from any specific source, is known as nonpoint source pollution.

Dry Weather
Wet Weather
TRASH
STORM RUNOFF
OIL + EMISSIONS FROM CARS
New York City



This Garden Harvests Rainwater

Rainwater harvesting is the ancient practice of catching and holding rain for later use. At community gardens like this one, rain is gathered from the rooftop of an adjacent building and stored in tanks in the garden. This helps reduce both the demand on the city's upstate fresh water supply and pollution in our local waterways.

...conserves its Water

Even when the city is not experiencing a drought, it's important to remember that freshwater is rare.

Only 3% of the world's water is fresh, or drinkable. Pollution further limits this resource. Over 1 billion people globally do not have access to good drinking water.

NYC'S WATER SUPPLY SYSTEM

Every day NYC uses 1.3 billion gallons of water from upstate reservoirs. When we waste water, we deplete these reservoirs.

...and Helps to Prevent Pollution

By harvesting rainwater, this garden helps prevent pollution during heavy rains. Here's why...

When it rains, stormwater runs off the city's rooftops and paved surfaces and into the nearest storm drain. Along the way it picks up contaminants such as oil, gas, dirt, chemicals, litter and lawn fertilizers. These contaminants then end up in our rivers and estuary.

By reducing the amount of water entering the sewer system, we can keep these pollutants out of our waterways.

The Water Resources Group

BROOKLYN GREENBRIDGE
CORNELL COOPERATIVE EXTENSION
COUNCIL ON THE ENVIRONMENT
DEPARTMENT OF ENVIRONMENTAL PROTECTION (DEP)
EAST NEW YORK FARMS!
GREEN GUERILLAS
GREENTHUMB
NEW YORK RESTORATION PROJECT
NYC SOIL & WATER CONSERVATION DISTRICT
TRUST FOR PUBLIC LAND

To learn more about the Water Resources Group, contact us at 212.788.8070
or...talk to your local community gardeners.

Sometimes it is necessary to break some basic RWH rules for aesthetic reasons. This rain water harvesting system has an inflow pipe that is pitched upward which means that it must rain enough for the water to fill up the roof washer and the inflow pipe before it can enter the tank. This was done so that the roof washer could be positioned below the brick wall and not interfere with the tree limb or the neighbor’s views.



Roofing Material

Roof tops are essential to any rain water harvesting system. Popular types of roofing include corrugated metal decking, shingles, rolled asphalt and cedar shake.

Corrugated metal decking can come in two forms- zinc coated or hot dipped galvanized. Because, zinc coated roofs rust easily, hot dipped galvanized roofs are more popular. These roofs are constructed simply by nailing down with sealing washers to your structure or screwing. Apply gutter sealant on any nail or screw to make sure water doesn't leak from these spots. Metal roofs provide great structural support for long amounts of time. It has the highest efficiency rate when it comes to rain water harvesting because of its waterproof surface. Its only downfall is the noise factor. It gets very loud when rain water clashes with the rooftop. It is an ideal roofing material for non residential structures.

Shingles are small pieces of overlapping wood or slate. Place a ½ inch wide piece of plywood on top of the structure. Start nailing shingles in a horizontal, overlapping fashion starting from the gutter line.

Work your way up to the top of your roof, making sure your next row overlaps the previous row (see picture on left[14]).

Rolled asphalt or modified bitumen roofs occur most commonly on flatter rooftops. A large sheet of asphalt is simply glued down with tar or plastic. Asphalt roofs can either have a granular surface or a smooth surface. Although granular surfaces are slightly less efficient in catching rain water because it is easily trapped in the pieces of ground glass, it is preferred over smoother roofs. Granular roofs wear slowly, resist cutting and keep UV rays from degrading it. Typically, a few years after the granular roof is installed, it is painted with aluminum to lock in grains that may have fallen loose (see picture on right[15]).

Cedar shake or wooden roofs are installed in a vertically overlapping fashion. Wood is the least efficient in catching rain water because it is porous. However, once the wood is saturated, it will no longer absorb water (see picture on left[16]).

Seasonal Maintenance

To ensure your health and safety the Water Resources Group recommends the following seasonal maintenance schedule for keeping your rainwater free of contaminants.

Spring

- Close spigot
- Re-direct roof water from the drain pipe back into tank storage system by replacing the in-line plunger or changing the position of the valve
- Clean any winter debris from gutters, leader inlets and roof
- Repair any leaks in barrel or tanks
- Inspect and clean barrel tops
- Fill system with a few inches of water to check hose connections for leaks
- Inspect rope/cable retainers to assure that barrels are secure
- Be sure that your tank is labeled with a "do not drink the water" sign in all appropriate languages
- To help ensure that children do not drink the water remove the valve from spigot and store with tools

Summer

- Keep the roof, gutters and leader inlets clear of debris, check monthly

- Inspect vents at top of each barrel to insure that they are clean and intact
- Visit your system during a heavy rain or shortly after to check for leaks and overflow problems.
- Any water from the overflow system should drain within 24 hours of a rainfall; if puddles form, you should move the outflow pipe to a more porous site or consider installing a small rain garden
- Inspect pipes and connectors regularly for any damage or disrepair
- Check man-way hatch on top of your tank to make sure it is securely closed

Fall

- Remove plunger from the PVC joint to redirect water into the drain pipe to the sewer
- **Empty water from the entire system- roof washer and tank**
- Open main valve of storage tank and rain barrels
- Open valve on roof washer. Valves should remain open all winter to keep water from freezing in system
- Disconnect leader from system and re-route water as necessary for particular system
- Cover any openings in leaders

Living with the RWH System

Now that you have built your rain water harvesting system, you have helped to conserve one of the Earth's most valuable resources. A rain barrel is not something you build and walk away from. It is important to make sure there are no leaks in your barrel and to drain the first flush after every storm.

Remember to drain your roof washer and tank during the winter and to take out your wintering tee! Freezing water will BREAK the system. The cracks seen in the two pictures below are from left over water freezing and expanding.





If properly built and maintained, your rain water harvesting system will last many years. Even the smallest tanks will save thousands of gallons of water.



It is essential to learn how to manage your water usage. Seventy percent of residential water use goes to outdoor activities. One third of that water is wasted (see diagram on right[17]). Using pumps or sprinklers to water plants are one of the most inefficient ways to irrigate. Plants only need to be watered at the roots. Sprinklers relentlessly waste water by randomly shooting out water to tree branches or leaves. Drip irrigation systems with outlets placed strategically next to plant roots are the most efficient ways to irrigate.

Existing RWH Systems

Organic Gardening Magazine has been sponsoring construction of rain water harvesting systems in community gardens since 2007. Their Waterworks Project funded 30 systems in the past 2 years. Looking at existing rain water harvesting systems and talking to community gardeners may assist you in building your own. Locations in the USA and Canada include:

Alemany Farm - San Francisco, CA
Ashview Community Garden - Atlanta, GA
Aspen Farms - Philadelphia, PA
Boyd Street Urban Farm - Portland, ME
Bradner Gardens Park – Seattle, WA
Brentwood Community Garden - Portland, OR
Children Garden - Camden, NJ
City Seeds Urban Farm - St. Louis, MO
Dias y Flores – New York, NY
The Farm Garden at the Early Childhood Education Center - Columbus, OH
Fremont Community Garden - Sacramento, CA
The Garden of Dreams - New York, NY
Global Gardens - Tulsa, OK
Gloryland Community Garden, Detroit, MI
Growing Green Youth Garden, Buffalo, NY
Guadalupe Montessori School, Silver City, NM
Hope Community Garden - Toronto, ON Canada
Marigold Meadows - Phoenix, AZ
Master Peace Youth and Community Garden - Riverdale, MD
Our Saviour Community Garden - Dallas, TX
The 1100 Block Bergen Street Garden - Brooklyn, NY
Urban Ministry Center - Charlotte, NC
Wasatch Community Gardens - Salt Lake City, UT
Woodlawn Garden - Portland, OR
Xochiquetzal Peace Garden - Chicago, IL

For more information on these gardens, visit their website at:
http://www.organicgardening.com/feature/0,7518,s1-2-10-1531-1-1X2X3-4,00.html

This guide can be found on GrowNYC's website at:
http://www.GrowNYC.org/openspace/rainwater

10 Ways to Conserve Water

1. Turn off the faucet when brushing your teeth, washing your face and shaving.

2. Fix any leaky sinks, toilets or showerheads.

3. Wash only full loads- for clothing and dishes.

4. Do not run water to thaw meats.

5. Water plants at the roots.

6. Take showers instead of baths.

7. Replace showerheads and sink aerators with low flow ones.

8. Use a pitcher to store cold water in the refrigerator instead of running the tap every time.

9. Water plants during early mornings and late afternoons to reduce evaporation.

10. Do not flush the toilet unnecessarily. Dispose of bugs, cigarette butts and tissues another way. [18] [19] [20]

The Water Resources Group (WRG), a coalition of NYC greening & community garden groups is dedicated to the preservation of NYC water resources through gardening, ecological design and education programs. WRG is installing rainwater harvesting systems in gardens across NYC to conserve water and prevent pollution. For more information on how you can help conserve water in New York City, visit the Water Resources Group website at www.waterresourcesgroup.org.

If you have any questions regarding the construction of your rain water harvesting system e-mail Lenny Librizzi, Assistant Director of Open Space Greening at GrowNYC at llibrizzi@GrowNYC.org.

Endnotes

---

[1] Hasse, Rolf. "Rain water reservoirs above ground structures for roof catchment." Welcome to Energy. 19 November 2003. 20 June 2008 <http://ces.iisc.ernet.in/energy/water/paper/drinkingwater/rainwater/introduction.html>

[2] "An introduction to rain water harvesting." The WWW Virtual Library on Urban Environmental Management. 9 May 2008. 20 June 2008 <http://www.gdrc.org/uem/water/rainwater/introduction.html>

[3] 10,000 Rain Gardens. 2008. 20 June 2008 < http://www.rainkc.com/>

[4] "Water." The New York Observer. 21 April 2008: G 10.

[5] "An introduction to rain water harvesting." The WWW Virtual Library on Urban Environmental Management. 9 May 2008. 20 June 2008 <http://www.gdrc.org/uem/water/rainwater/introduction.html>

[6] "Rhizome Collective." Eco Warrior. 28 Nov 2007. 11 July 2008 <http://hurricanecandice.wordpress.com/2007/11/28/rhizome-collective/>

[7] "Oak Whiskey Barrel." Rain Barrel by Aaron. 2003. 11 July 2008 <www.ne-design.net/oak-whiskey-barrel.html>

[8] "Products." RainDrops Cisterns Rainwater Harvesting and Storage. 23 June 2008. 11 July 2008 <http://www.raindropscisterns.com/cat_photo_3.php>

[9] "Rain Garden." Wikipedia: The Free Encyclopedia. 12 June 2008. 20 June 2008 <http://en.wikipedia.org/wiki/Rain_garden>

[10] "Bioswales." Wikipedia: The Free Encyclopedia. 3 April 2008. 20 June 2008 <http://en.wikipedia.org/wiki/Bioswales>

[11] Chapin Watermatics Inc. 11 July 2008 <http://www.chapindrip.com/index.php>

[12] Drip depot. 11 July 2008 <http://www.dripdepot.com/>

[13] Drip depot. 11 July 2008 <http://www.dripdepot.com/>

[14] "Roofing." Sam Siding Home Improvement. 20 June 2008 <www.samsiding.com/Roofing.aspx>

[15] Lexis Coatings. 20 June 2008 <http://www.lexiscoatings.com/>

[16] "Cedar." Hynes Home Improvement: The Sign of Quality. 11 July 2008. <http://www.hyneshomeimprovement.com/roofing-cedar.html>

[17] "Hydrapure Water Solutions." Hydrapure. 11 July 2008. <http://www.hydrapure.net>

[18] Lenz, Ericka. "10 easy ways to conserve water." Gaiam Life- Your Guide to a Better Life. 20 June 2008 <http://life.gaiam.com/gaiam/p/10SimpleWaystoConserveWater.html>

[19] "10 ways to conserve water." Etowah Water and Sewer Authority. 2 February 2008. 2008 June 2008 <http://www.etowahwater.org/FAQs/10_Ways_to_Conserve_Water/10_ways_to_conserve_water.html>

[20] "Ten Ways To Conserve Water Around The House And Help The Environment." The Good Human. 2 July 2007. 20 June 2008. <http://www.thegoodhuman.com/2007/07/02/ten-ways-to-conserve-water-around-the-house-and-help-the-environment/>

This manual was put together by Julia Leung, Lenny Librizzi, Assistant Director of Open Space Greening at GrowNYC and Lars Chellberg.

After reading this manual, please fill out this feedback form and mail it to:

GrowNYC
51 Chambers Street, Room 228
New York, NY 10007

On a scale of 1 – 10, 10 being the most agreeable, 1 being the least, assess the following statements:

This manual is easy to understand.
1 2 3 4 5 6 7 8 9 10

This manual contains clear instructions.
1 2 3 4 5 6 7 8 9 10

This manual helped you make your rain water harvesting system.
1 2 3 4 5 6 7 8 9 10

You understand how a rain water harvesting system works.
1 2 3 4 5 6 7 8 9 10

You are no longer interested in rain water harvesting.
1 2 3 4 5 6 7 8 9 10

You would recommend this manual to your friends.
1 2 3 4 5 6 7 8 9 10

You know the importance of water conservation.
1 2 3 4 5 6 7 8 9 10

What are the strong points of this manual?

What are the weak points of this manual?

AUDEL™

THE BOOKS THAT WORK™

CARPENTER'S AND BUILDER'S MATH, PLANS & SPECIFICATIONS

ALL NEW 7TH EDITION

Mark Richard Miller & Rex Miller

Audel™

Carpenter's and Builder's Math, Plans, and Specifications

All New 7th Edition

Mark Richard Miller
Rex Miller

WILEY
Wiley Publishing, Inc.

TLFeBOOK

Vice President and Executive Group Publisher: Richard Swadley
Vice President and Publisher: Joseph B. Wikert
Executive Editor: Carol Long
Editorial Manager: Kathryn A. Malm
Development Editor: Kevin Shafer
Production Editor: Angela Smith
Text Design & Composition: TechBooks

Copyright © 2005 by Wiley Publishing, Inc., Indianapolis, Indiana. All rights reserved.

Published simultaneously in Canada

No part of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, scanning, or otherwise, except as permitted under Sections 107 or 108 of the 1976 United States Copyright Act, without either the prior written permission of the Publisher, or authorization through payment of the appropriate per-copy fee to the Copyright Clearance Center, 222 Rosewood Drive, Danvers, MA 01923, (978) 750-8400, fax (978) 646-8600. Requests to the Publisher for permission should be addressed to the Legal Department, Wiley Publishing, Inc., 10475 Crosspoint Blvd., Indianapolis, IN 46256, (317) 572-3447, fax (317) 572-4355, e-mail: brandreview@wiley.com.

Limit of Liability/Disclaimer of Warranty: The publisher and the author make no representations or warranties with respect to the accuracy or completeness of the contents of this work and specifically disclaim all warranties, including without limitation warranties of fitness for a particular purpose. No warranty may be created or extended by sales or promotional materials. The advice and strategies contained herein may not be suitable for every situation. This work is sold with the understanding that the publisher is not engaged in rendering legal, accounting, or other professional services. If professional assistance is required, the services of a competent professional person should be sought. Neither the publisher nor the author shall be liable for damages arising herefrom. The fact that an organization or Website is referred to in this work as a citation and/or a potential source of further information does not mean that the author or the publisher endorses the information the organization or Website may provide or recommendations it may make. Further, readers should be aware that Internet Websites listed in this work may have changed or disappeared between when this work was written and when it is read.

For general information on our other products and services please contact our Customer Care Department within the United States at (800) 762-2974, outside the United States at (317) 572-3993 or fax (317) 572-4002.

Trademarks: Wiley, the Wiley Publishing logo, Audel, and The Books That Work are trademarks or registered trademarks of John Wiley & Sons, Inc. and/or its affiliates. All other trademarks are the property of their respective owners. Wiley Publishing, Inc., is not associated with any product or vendor mentioned in this book.

Wiley also publishes its books in a variety of electronic formats. Some content that appears in print may not be available in electronic books.

Library of Congress Control Number: 2004110825

eISBN: 0-7645-7981-9

Printed in the United States of America

10 9 8 7 6 5 4 3 2 1

Contents

Acknowledgments xiii

About the Authors xv

Introduction xvii

Chapter 1 Nails, Screws, Bolts, and Other Fasteners 1
- Nails 1
  - The Penny System 3
  - Nail Characteristics 3
  - Selecting Nail Size 12
  - Driving Nails 13
- Screws 16
  - Material 17
  - Dimensions of Screws 18
  - Shape of the Head 18
  - How to Drive a Wood Screw 18
  - Strength of Wood Screws 21
  - Lag Screws 23
- Bolts 23
  - Manufacture of Bolts 23
  - Kinds of Bolts 27
  - Proportions and Strength of Bolts 27
- Fasteners for Plaster or Drywall 33
  - Expansion Anchors 33
  - Hollow Wall Screw Anchors 34
  - Toggle Bolts 36
  - Hanger Bolts, Dowel Screws, and Toggle Studs 37
  - Framing Fasteners 39
- Summary 39
- Review Questions 40

Chapter 2 Wood as a Building Material 41
- Growth and Structure of Wood 41
- Softwoods and Hardwoods 41

Lumber Conversion 43
Seasoning of Wood 44
  Moisture Content 47
  Density 49
  Strength 51
  Deadwood 53
  Virgin and Second Growth 54
  Time of Cutting Timber 54
  Air-Dried and Kiln-Dried Wood 54
  Sapwood Versus Heartwood 55
Defects and Deterioration 55
  Decay of Wood 57
  Nuclear Radiation 63
  Weathering 63
  Insect Damage 65
Summary 65
Review Questions 65

Chapter 3 Lumber, Plywood, and Other Wood Products 67
Standard Sizes of Lumber 67
Softwood Lumber Grades for Construction 68
  Stress-Graded Lumber 68
  Nonstress-Graded Lumber 69
  Appearance Lumber 70
Plywood 77
  Types of Plywood 79
  Grades of Plywood 79
Particle Board 79
Lumber Distribution 82
  Retail Yard Inventory 82
  Important Purchase Considerations 86
Engineered Lumber 87
Summary 88
Review Questions 88

Chapter 4 **Strength of Timbers** 89
Tension 89
Compression 90
Working Stresses for Columns 91
Shearing Stresses 92
Horizontal Shears 94
Transverse or Bending Stress 96
Stiffness 96
Modulus of Elasticity 100
Beams 100
  Allowable Loads on Wood Beams 100
  Breaking Loads on Wood Beams 102
  Distributed Load 102
  Cantilever Beams 102
Wind Loads on Roofs 104
Definitions 106
Summary 108
Review Questions 109

Chapter 5 **Mathematics for Carpenters and Builders** 111
Arithmetic 111
  Arithmetic Alphabet 111
  Notation and Numeration 111
  Roman Notation 113
  Definitions 113
  Signs of Operation 115
  Use of the Signs of Operation 116
  Fractions 117
  Decimals 122
  Compound Numbers 126
  Ratios 127
  Proportion 127
  Rule of Three 128
  Percentage 128
  Powers of Numbers (Involution) 129
  Roots of Numbers (Evolution) 129

Measures 131
- Linear Measure 132
- Square Measure 133
- Cubic Measure 133
- Dry Measure 135
- Board or Lumber Measure 136
- Liquid Measure 137
- Measures of Weight 137
- Time Measure 139
- Circular Measure 139
- The Metric System 140

Geometry 142
- Lines 142
- Angles 142
- Plane Figures 143
- Solids 146
- Geometrical Problems 146
- Mensuration 167

Trigonometry 182
- Trigonometric Functions 182

Functions of Numbers 197

Summary 197

Review Questions 197

Chapter 6 Surveying 199

The Level 199
- Construction of the Wye Level 199
- Lines of the Level 201
- Adjustments of the Wye Level 202
- Leveling Rod 205
- Methods of Leveling 206
- Directions for Using Level 209
- Trigonometric Leveling 211

The Transit 212
- Construction of the Transit 212
- Lines of a Transit 218
- Adjustments of the Transit 219

- Adjustments of the Compass 221
- Instructions for Using the Transit 222
- Gradienter 224
- Care of Instruments 224

The Stadia 225
Other Devices 226
Laser Levels 227
Summary 232
Review Questions 232

Chapter 7 The Design Process 233
Design Considerations 233
An Example of Design 236
- Conference with Builder 236
- Changes Agreed On 238

Summary 240
Review Questions 241

Chapter 8 Building Specifications 243
Example of Specifications 243
- Introduction 243
- Height of Ceilings 243
- Interpretation of Drawings 244
- Conditions 244
- Mason's Work 244
- Foundation 245
- Chimneys 245
- Mortar 245
- Installing Drywall 245
- Tiling 245
- Other Floors 246
- Coping 246
- Timber 246
- Framing 246
- Spacing and Bridging 247
- Partitions 247
- Lumber 247

Sheathing and Sheathing Paper 247
Exterior Finish 247
Shingling 247
Flashing 248
Flooring 248
Window Frames 248
Sash 248
Screens 248
Glazing 248
Blinds 248
Door Frames 248
Doors 249
Interior Trim 249
Stairs 249
Mantels 249
Pantry Cabinets 250
Closet Shelving 250
Plumbing 250
Electric Wiring 250
Water Pipes 250
Kitchen Sink 251
Wash Trays 251
Bathroom Fixtures 251
Painting 251
Condition of Bids 252
Summary 252
Review Questions 252

Chapter 9 Architectural Drawings 255
Use of Drawings 255
Reading Drawings 255
Projected Views 255
Top View or Plan 256
Right-End View (Elevation) 256
Left-End View (Elevation) 258
Sections 258

Directions of View for Sectional Views 259
The Scale 260
Drawing Development 262
Graphic Symbols 267
Summary 278
Review Questions 279

Chapter 10 Building Styles Explored 281
The Two-Story New England Colonial House 281
A House of Modern Architecture 284
The Contemporary House 285
Utility Pole-Type Building 287
Summary 291
Review Questions 292

Appendix Construction Hardware 293

Index 349

Acknowledgments

No book can be written without the aid of many people. It takes a great number of individuals to put together the information available about any particular technical field into a book. Many firms have contributed information, illustrations, and analysis of the book.

The authors would like to thank every person involved for his or her contributions. Following are some of the firms that supplied technical information and illustrations.

American Plywood Association
C. L. Berger and Sons, Inc.
David White Instruments, Div. of Realist, Inc.
Forest Product Lab
Practical Restoration Reports
Stabila
Teco
United States Steel Products Company
Vaughn and Bushnell
Wild-Heerbrugg

About the Authors

Mark Richard Miller finished his BS degree in New York and moved on to Ball State University, where he obtained the Master's degree. He went to work in San Antonio. He taught high school and went to graduate school in College Station, Texas, finishing the Doctorate. He took a position at Texas A&M University in Kingsville, Texas where he now teaches in the Industrial Technology Department as a Professor and Department Chairman. He has co-authored 11 books and contributed many articles to technical magazines. His hobbies include refinishing a 1970 Plymouth Super Bird and a 1971 Road-Runner.

Rex Miller was a Professor of Industrial Technology at The State University of New York, College at Buffalo for more than 35 years. He has taught at the technical school, high school, and college level for more than 40 years. He is the author or co-author of more than 100 textbooks ranging from electronics through carpentry and sheet metal work. He has contributed more than 50 magazine articles over the years to technical publications. He is also the author of seven civil war regimental histories.

Introduction

The Audel Carpenters and Builders Math, Plans, and Specifications: All New Seventh Edition is the second of four volumes that cover the fundamental tools, methods, and materials used in carpentry, woodworking, and cabinetmaking.

This volume was written for anyone who wants (or needs) to know how to use the math and read the plans and specifications often encountered by the carpenter, woodworker, cabinetmaker, or do-it-yourselfer. Whether remodeling an existing home or building a new one, the rewards of a good job are substantial.

This book has been prepared for use as a practical guide in the selection, maintenance, installation, operation, and repair of wooden structures. Carpenters and woodworkers (as well as cabinetmakers) should find this book (with its clear descriptions, illustrations, and simplified explanations) a ready source of information for the many problems that they might encounter while building, maintaining, or repairing houses and furniture. Both professionals and do-it-yourselfers who want to gain knowledge of woodworking and house building will benefit from the theoretical and practical coverage in this book.

This is the second of a series of four books in the Carpenters and Builders Library that was designed to be a solid reference set of materials that can be useful both at home and in the field. Other books in the series include the following:

- *Audel Carpenters and Builders Tools, Steel Square, and Joinery: All New Seventh Edition*
- *Audel Carpenters and Builders Layout, Foundation, and Framing: All New Seventh Edition*
- *Audel Carpenters and Builders Millwork, Power Tools, and Painting: All New Seventh Edition*

No book can be complete without the aid of many people. The Acknowledgments section mentions some of those who contributed to making this up to date with current design and technology available to the carpenter. We trust you will enjoy using the book as much as we did writing it.

Chapter 1

Nails, Screws, Bolts, and Other Fasteners

The strength and stability of any structure depend heavily on the fastenings that hold its parts together. One prime advantage of wood as a structural material is the ease with which wood structural parts can be joined together with a wide variety of fastenings—nails, spikes, screws, bolts, lag screws, drift pins, staples, and metal connectors of various types. For utmost rigidity, strength, and service, each type of fastening requires joint designs adapted to the strength properties of wood along and across the grain and to dimensional changes that may occur with changes in moisture content.

Nails

Nails are the most common fasteners used in construction.

Up to the end of the Colonial period, all nails used in the United States were handmade. They were forged on an anvil from nail rods, which were sold in bundles. These nail rods were prepared either by rolling iron into small bars of the required thickness or by the much more common practice of cutting plate iron into strips by means of rolling shears.

Just before the Revolutionary War, the making of nails from these rods was a household industry among New England farmers. The struggle of the Colonies for independence intensified an inventive search for shortcuts to mass production of material entering directly or indirectly into the prosecution of the war. Thus came about the innovation of cut nails made by machinery. With its coming, the household industry of nail making rapidly declined. At the close of the eighteenth century, 23 patents for nailmaking machines had been granted in the United States, and their use had been generally introduced into England, where they were received with enthusiasm.

In France, lightweight nails for carpenter's use were made of wire as early as the days of Napoleon I, but these nails were made by hand with a hammer. The handmade nail was pinched in a vise with a portion projecting. A few blows of a hammer flattened one end into a head. The head was beaten into a countersunk depression in the vise, thus regulating its size and shape. In the United States, wire nails were first made in 1851 or 1852 by William Hersel of New York.

In 1875, Father Goebel, a Catholic priest, arrived from Germany and settled in Covington, Kentucky. There he began the manufacture of wire nails that he had learned in his native land. In 1876, the American Wire and Screw Nail Company was formed under Father Goebel's leadership. As the production and consumption of wire nails increased, the vogue of cut nails, which dominated the market until 1886, declined.

The approved process in the earlier days of the cut-nail industry was as follows. Iron bars, rolled from hematite or magnetic pig, were fagotted, reheated to a white heat, drawn, rolled into sheets of the required width and thickness, and then allowed to cool. The sheet was then cut across its length (its width being usually about a foot) into strips a little wider than the length of the required nail. These plates (heated by being set on their edge on hot coals) were seized in a clamp and fed to the machine, end first. The cutout pieces, slightly tapering, were squeezed and headed up by the machine before going to the trough.

The manufacture of tacks, frequently combined with that of nails, is a distinct branch of the nail industry, affording much room for specialties. Originally it was also a household industry, and was carried on in New England well into the eighteenth century. The wire, pointed on a small anvil, was placed in a pedal-operated vise, which clutched it between jaws furnished with a gauge to regulate the length. A certain portion was left projecting. This portion was beaten with a hammer into a flat head.

Antique pieces of furniture are frequently held together with iron nails that are driven in and countersunk, thus holding quite firmly. These old-time nails were made of foursquare wrought iron and tapered somewhat like a brad but with a head that, when driven in, held with great firmness.

The raw material of the modern wire nail factory is drawn wire, just as it comes from the wire drawing block. The stock is low-carbon Bessemer or basic open-hearth steel. The wire, feeding from a loose reel, passes between straightening rolls into the gripping dies, where it is gripped a short distance from its end, and the nailhead is formed by an upsetting blow from a heading tool. As the header withdraws, the gripping dies loosen, and the straightener carriage pushes the wire forward by an amount equal to the length of the nail. The cutting dies advance from the sides of the frame and clip off the nail, at the same time forming its characteristic chisel point. The gripping dies have already seized the wire again, and an ejector flips the nail out of the way just as the header comes forward and heads the next nail. All these motions are induced by cams and eccentrics on the main shaft of the machine, and the speed of production is at a rate of 150 to 500 complete cycles per minute. At this stage, the nails are covered with a film of drawing lubricant and oil from the nail machine, and their points are frequently adorned with *whiskers*—a name applied to the small diamond-shaped pieces stamped out when the point is formed and which are occasionally found on the finished nail by the customer.

These oily nails (in lots of 500 to 5000 pounds) are shaken with sawdust in tumbling barrels from which they emerge bright, clean, and free of their whiskers, ready for weighing, packing, and shipping.

The Penny System

This method of designating nails originated in England. Two explanations are offered as to how this interesting designation came about. One is that the six penny, four penny, ten penny, and so on, nails derived their names from the fact that 100 nails cost six pence, four pence, and so on. The other explanation, which is the more probable of the two, is that 1000 ten-penny nails, for instance, weighed ten pounds. The ancient, as well as the modern, abbreviation for penny is *d*, being the first letter of the Roman coin denarius. The same abbreviation in early history was used for the English pound in weight. The word *penny* has persisted as a term in the nail industry.

Nail Characteristics

Nails are the carpenter's most useful fastener, and a great variety of types and sizes are available to meet the demands of the industry. One manufacturer claims to produce more than 10,000 types and sizes. Figure 1-1 shows some common types.



Figure 1-1 Various nails grouped as to general size: (A) tack, (B) sprig or dowel pin, (C) brad, (D) nail, and (E) spike.



Figure 1-2 Smooth and barbed box nails, lbd size (shown full size). Note the sharp point and thin, flat head.

Nails also have a variety of characteristics, including different points, shanks, finishes, and material (see Figure 1-2). The following shapes of points are available:

- Common blunt pyramidal
- Long sharp
- Chisel-shaped
- Blunt or shooker
- Side-sloped
- Duckbill or clincher

The heads may be

- Flat
- Oval or oval countersunk
- Round
- Double-headed

Each of the features or characteristics makes the nail better suited for the job at hand. For example, galvanized nails are weather-resistant, double-headed nails are good for framing where they can be installed temporarily with the second head exposed for easy pulling, and barbed nails are good when extra holding power is required.

Tacks

Tacks are small, sharp-pointed nails that usually have tapering sides and a thin, flat head. The regular lengths of tacks range from $^1/_8$ to $1^1/_8$ inches. The regular sizes are designated in ounces, according to Table 1-1. Tacks are usually used to secure carpet or fabric.

Brads

Brads are small slender nails with small deep heads (see Figure 1-3). Sometimes, instead of having a head, they have a projection on one side. There are several varieties adapted to many different

Table 1-1 Wire Tacks

Size (oz)	Length (in)	No. per Pound	Size (oz)	Length (in)	No. per Pound	Size (oz)	Length (in)	No. per Pound
1	1/8	16,000	4	7/16	4000	14	13/16	1143
1 1/2	3/16	10,666	6	9/16	2666	16	7/8	1000
2	1/4	8000	8	5/8	2000	18	15/16	888
2 1/2	5/16	6400	10	11/16	1600	20	1	800
3	3/8	5333	12	3/4	1333	22	1 1/16	727
						24	1 1/8	666

requirements. Brad sizes start at about 1/2 inch and end at 1 1/2 inches. Beyond this size they are called *finishing nails*.

Nails

The term nails is popularly applied to all kinds of nails except extreme sizes (such as tacks, brads, and spikes). Broadly speaking, however, it includes all of these. The most generally used are called



Figure 1-3 Brads are small nails. They are used to attach thin strips of wood such as moldings. *(Courtesy of The American Plywood Assn.)*

common nails, and are regularly made in sizes from 1 inch (2d) to 6 inch (60d), as shown in Table 1-2 (see Figures 1-4 through 1-8).

Table 1-2 Common Nails

	Plain			*Coated*		
Size	*Length in.*	*Gauge No.*	*No. per Pound*	*Length in.*	*Gauge No.*	*Per 50-Pound Box*
2d	1	15	876	1	16	43,800
3d	1 1/4	14	568	1 1/8	15 1/2	28,400
4d	1 1/2	12 1/2	316	1 3/8	14	15,800
5d	1 3/4	12 1/2	271	1 5/8	13 1/2	13,500
6d	2	11 1/2	181	1 7/8	13	9000
7d	2 1/4	11 1/2	161	2 1/8	12 1/2	8000
8d	2 1/2	10 1/4	106	2 3/8	11 1/2	5300
9d	2 3/4	10 1/4	96	2 5/8	11 1/2	4800
10d	3	9	69	2 7/8	11	3400
12d	3 1/4	9	63	3 1/8	10	3100
16d	3 1/2	8	49	3 1/4	9	2400
20d	4	6	31	3 3/4	7	1500
30d	4 1/2	5	24	4 1/4	6	1200
40d	5	4	18	4 3/4	5	900
50d	5 1/2	3	14	5 1/4	4	700
60d	6	2	11	5 3/4	3	500

Spikes

You can think of a *spike* as an extra large nail, sometimes quite a bit larger. Generally, spikes range from 3 to 12 inches long and are thicker than common nails. Point style varies, but a spike is normally straight for ordinary uses (such as securing a gutter). However, a spike can also be curved or serrated, or cleft to make extracting or drawing it out very difficult. Spikes in larger sizes are used to secure rails to ties, in the building of docks, and for other large-scale projects.

If you have a very large job to do, it is well to know the holding power of nails (see Table 1-3). In most instances, this information will not be required, but in more than a few cases, it is.

Tests for the holding power of nails (and spikes) ranging in size from 6d to 60d are shown in Table 1-4. It is interesting to note, in view of the relatively small force required to withdraw nails, that


40d
5 IN. = #4 GAUGE
30d
4 1/2 IN. = #5 GAUGE
20d
4 IN. = #6 GAUGE
16d
3 1/2 IN. = #8 GAUGE
12d
3 1/4 IN. = #9 GAUGE
10d
3 IN. = #9 GAUGE
9d
2 3/4 IN. = #11 1/2 GAUGE
8d
2 1/2 IN. = #10 1/4 GAUGE
7d
2 1/4 IN. = #11 1/2 GAUGE
6d
2 IN. = #11 1/2 GAUGE
5d
1 3/4 IN. = #12 1/2 GAUGE
4d
1 1/2 IN. = #12 1/2 GAUGE

Figure 1-4 Common wire nails. The standard nail for general use is regularly made in sizes from 1 inch (2d) to 6 inches (60d).

spikes take tremendous pulling power. In one test it was found that a spike 3/8 inch in diameter driven 3 1/2 inches into seasoned yellow pine required 2000 pounds of force for extraction. And the denser the material, the more difficult the extraction is. The same spike required 4000 pounds of force to be withdrawn from oak and 6000 pounds from well-seasoned locust.


d
GAUGE
3d
15½
4d
15
5d
15
6d
13
7d
13
8d
12½
FINISHING
9d
11½
8d
11½
7d
12½
6d
12½
CASING
5d
14
4d
14
3d
14½

Figure 1-5 Casing and finishing nails (shown full size). Note the difference in the head shape and size. The finishing nail is larger than a casing nail of equal length, but a casing nail is stronger.


6d
11½
COMMON
7d
11½
8d
10¼
9d
10¼
9d
10
8d
10
FLOORING
7d
11
6d
11

Figure 1-6 Flooring and common nails (shown full size). Note the variation in head shape and gauge number.



Figure 1-7 A few sizes of slating and shingle nails. Note the difference in wire gauge.



Figure 1-8 Hook-head, metal lath nail. This is a bright, smooth nail with a long, thin flat head, made for application of metal lath. It is also made blued or galvanized.

Table 1-3 Withdrawal Force of Cut vs. Wire Nails (pounds per square inch)

Wood	*Wire Nail*	*Cut Nail*
White pine	167	405
Yellow pine	318	662
White oak	940	1216
Chestnut		683
Laurel	651	1200

Roofing Nails

The *roofing nail* has a barbed shank and a large head, which makes it good for holding down shingles and roofing paper felt without damage (the material couldn't pull readily through the head).

Such nails come in a variety of sizes but usually $\frac{3}{8}$ inch to $1\frac{1}{4}$ inch long with the nail sized to the material thickness (see Figure 1-9).

Table 1-4 Holding Power of Nails and Spikes (Withdrawal)

Size of Spikes	*Length Driven In*	*Pounds resistance to Drawing, Average Lbs.*	*Max. Lbs*	*From 6 to 9 Tests Each Min. Lbs*
$5 \times {}^1/_4$ in. sq.	$4^1/_4$ in.	857	1159	766
$6 \times {}^1/_4$	5 in.	857	923	766
$6 \times {}^1/_2$	5 in.	1691	2129	1120
$5 \times {}^3/_8$	$4^1/_4$ in.	1202	1556	687



Figure 1-9 Various roofing nails (shown full size).

Drywall Nails

As the name implies, these are for fastening drywall (Sheetrock). The shank of the nail is partially barbed and the head countersunk so that if the nail bites into the stud, it takes a good bite. *Drywall nails* come in a variety of lengths for use with different thicknesses of Sheetrock (see Figure 1-10).

Masonry Nails

Masonry nails are cut (that is, stamped) out of a sheet of metal rather than drawn and cut the way wire nails are (see Figure 1-10). A masonry nail is made of very hard steel and is case hardened. It has a variety of uses but the most common is probably for securing studs or furring to block walls. Safety is important when doing any kind of nailing, but, when using masonry nails, it is particularly important to wear protective goggles to guard the eyes against flying chips.



MASONRY NAILS

SCREW SHANK

DRYWALL

Figure 1-10 Miscellaneous nails.

Spiral Nails

The most tenacious of all nails in terms of holding power is the *spiral nail* (also known as the *drive screw*). Its shank is spiral so that as the nail is driven, it turns and grips the wood. Its main use is to secure flooring, but it is also useful on rough carpentry.

Corrugated Fasteners

This fastener is a small section of corrugated metal with one sharpened and one flat edge. *Corrugated fasteners* are often used for making boxes or joining wood sections edge to edge (see Figure 1-11). They come in a variety of sizes.

Staples

Many varieties of *staples* are available, from ones used to secure cable and fencing to posts (such staples are always galvanized) to ones used in the various staple guns. Fence staples range in size from $^7/_8$ inch to $1^1/_4$ inches, and some are designed (the so-called *slash point*) so that the legs spread when the staple is driven in place. This makes it grip better.



Figure 1-11 Corrugated nails do not have great holding power, but they are for noncritical or temporary work. *(Courtesy of The American Plywood Assn.)*

Selecting Nail Size

In selecting nails for jobs, size is crucial. The first consideration is the diameter. Short, thick nails work loose quickly. Long, thin nails are apt to break at the joints of the lumber. The simple rule to follow is to use as long and as thin a nail as will drive easily.

Definite rules have been formulated by which to determine the size of nail to be used in proportion to the thickness of the board that is to be nailed:

1. When using box nails in lumber of medium hardness, the penny of the nail should not be greater than the thickness, in eighths of an inch, of the board into which the nail is being driven.
2. In very soft woods, the nails may be one penny larger, or in some cases, two pennies larger.
3. In hard woods, nails should be one penny smaller.
4. When nailing boards together, the nail point should penetrate within $1/4$ inch of the far side of the second board.

The kind of wood is, of course, a big factor in determining the size of nail to use. The dry weight of the wood is the best basis for the determination of its grain substance or strength. The greater its dry weight, the greater its power to hold nails. However, the splitting tendency of hard wood tends to offset its additional holding power. Smaller nails can be used in hard lumber than in soft lumber (see Figure 1-12). Positive rules governing the size of nails to be used as related to the density of the wood cannot be laid down. Experience is the best guide.



Figure 1-12 Application of rules 2 and 3 in determining the proper size of nail to use.

Table 1-5 shows the approximate number of wire nails per pound.

Driving Nails

In most cases, it is not necessary to drill pilot holes for nails to avoid splitting the wood. However, in some instances it is advisable to first drill holes nearly the size of the nail before driving, to guard

Table 1-5 Approximate Number of Wire Nails per Pound Length

American Steel & Wire Co's. Steel Wire Gauge	Length																			
	3/16	1/4	3/8	1/2	5/8	3/4	7/8	1	1 1/8	1 1/4	1 1/2	1 3/4	2	2 1/4	2 1/2	2 3/4	3	3 1/2	4	4 1/2	5
3/8	.....	.....	.....	.....	.....	.....	.....	29	26	23	20	17	15	15	12	11	11	8.9	7.9	7.1	6.4
5/16	.....	.....	.....	.....	.....	.....	.....	43	38	34	29	25	22	20	18	16	15	13	11	10	9.0
1	.....	.....	.....	.....	.....	.....	.....	47	44	40	34	29	26	23	21	20	18	16	14	12	11
2	.....	.....	.....	.....	.....	.....	.....	60	54	48	41	35	31	28	25	23	21	18	16	14	13
3	.....	.....	.....	.....	.....	.....	.....	67	60	55	47	41	36	32	29	27	25	21	18	16	15
4	.....	.....	.....	.....	.....	.....	.....	81	74	66	55	48	41	37	34	31	29	25	22	20	18
5	.....	.....	.....	.....	.....	.....	.....	90	81	74	61	52	45	41	38	35	32	28	24	22	21
6	.....	.....	.....	213	174	149	128	113	101	91	76	65	58	52	47	43	39	34	29	26	24
7	.....	.....	.....	250	205	174	148	132	120	110	92	78	70	61	55	51	47	40	35	31	28
8	.....	.....	.....	272	238	198	174	153	139	126	106	93	82	74	66	61	56	48	42	38	34
9	.....	.....	.....	348	286	238	213	185	170	152	128	112	99	87	79	71	67	58	50	45	41
10	.....	.....	.....	469	373	320	277	242	616	196	165	142	124	111	100	91	84	71	62	55	49
11	.....	.....	.....	510	117	366	323	285	254	233	200	171	149	136	122	111	103	87	77	69	61
12	.....	.....	.....	740	603	511	442	397	351	327	268	229	204	182	161	149	137	118	103	95	87
13	.....	.....	1356	1017	802	688	590	508	458	412	348	297	260	232	209	190	175	153	138	123	110
14	.....	2293	1664	1290	1037	863	765	667	586	536	459	398	350	312	278	256	233	201	176	157	140
15	.....	2899	2213	1619	1316	1132	971	869	787	694	578	501	437	390	351	317	290	256	220	196	177
16	.....	3932	2770	2142	1708	1414	1229	1099	973	872	739	635	553	496	452	410	370	318	277	248	226
17	.....	5316	3890	2700	2306	1904	1581	1409	1253	1139	956	831	746	666	590	532	486	418	360	322	295
18	.....	7520	5072	3824	3130	2608	2248	1976	1760	1590	1338	1150	996	890	820	740	680	585	507	448	412
19	.....	9920	6860	5075	4132	3508	2816	2556	2284	2096	1772	1590	1390	1205	1060	970	895	800	.....	.....	.....
20	18620	14050	9432	7164	5686	4795	4230	3596	3225	2893	2412	2070	1810	1620	1450	1315	1215	1035	.....	.....	.....
21	23260	17252	12000	8920	7232	6052	5272	4576	4020	3640	3040	2665	2310	2020	1830	.....	.....	.....	.....	.....	.....
22	28528	21508	14676	11776	9276	7672	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
23	35864	27039	18026	13519	10815	9013	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
24	44936	34018	22678	17008	13607	11339	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
25	57357	43243	28828	21622	17297	14414	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....

These approximate numbers are an average only, and the figures given may be varied either way by changes in the dimensions of the heads or points. Brads and on-head nails will run more to the pound than table shows, and large or thick-headed nails will run less.



Figure 1-13 To prevent a nail from splitting wood, a pilot hole is sometimes drilled. Pilot-hole drilling is common when using screws. *(Courtesy of The American Plywood Assn.)*

against it (see Figure 1-13). In addition, in fine work, where a large number of nails must be driven, such as applying cedar clapboards, holes should be drilled. This step prevents crushing the wood and possible splitting because of the large number of nails driven through each board. The size of drill for a given size nail should be slightly smaller than the shank diameter.

The right way to drive nails is shown in Figure 1-14. Figure 1-15 illustrates the necessity of using a good hammer to drive a nail. The force that drives the nail is caused by the inertia of the hammer. This inertia depends on the suddenness with which its motion is brought to rest on striking the nail. With hardened steel, there is practically no give, and all the energy possessed by the hammer is transferred to the nail. On a hammer made with soft and/or inferior metal, all the energy is not transferred to the nail. Therefore, the power per blow is less than with hardened steel.


AXIS OF HANDLE PARALLEL WITH PLANE OF NAIL HEAD
HAMMER STRIKING SQUARE ON HEAD—FULL CONTACT
(A) RIGHT WAY.
USUALLY 10° TO 45°
(B) WRONG WAY.

Figure 1-14 (A) Right way to drive a nail. Hit the nail squarely on the head. The handle should be horizontal when the hammer head hits a vertical nail. (B) Wrong way to drive a nail.


HARD STEEL
NO GIVE—INERTIA OF HAMMER NOT CUSHIONED—IMPACT IS MAXIMUM
INERTIA OF HAMMER ABSORBED BY SOFT METAL OF HAMMER—IMPACT IS ABSORBED.
(A) GOOD HAMMER.
(B) CHEAP HAMMER.

Figure 1-15 Why a cheap hammer should not be used.

Screws

Wood screws have several advantages over nails. First, screws are harder to pull out. Pull on a screw and pull on a nail—the screw will give greater resistance. Second, should you tire of an item at some time in the future; screws usually let you disassemble it without great travail. It is possible to damage the work if it is nailed together and you want to take it apart. These advantages cost more in the effort and time it takes to install screws.

Screws are normally used to fasten things such as hinges, knobs, and so on, to structures, and in the assembly of various wood parts.

They are not used in heavy building simply because, in this type of work, things are built so that there is a minimum of stress on the fasteners and the withdrawal resistance is not required. Indeed, if stress were created, even the most tenacious screw could not stand up much better than a nail (which is to say very little).

The wood screw consists of a gimlet point, a threaded portion, and a shank and head, which may be straight slot or Phillips.

Screws of many types are made for specialized purposes, but stock wood screws are usually obtainable in either steel or brass, and, more rarely, are made of high-strength bronze. Three types of heads are standard:

- The *flat countersunk head*, with the included angle of the sloping sides standardized at 82°
- The *round head*, whose height is also standardized, but whose contour seems to vary slightly among the products of different manufacturers
- The *oval head*, which combines the contours of the flat head and the round head

All of these screws are available with the Phillips slot, or crossed slots, as well as the usual single straight slot.

The Phillips slot allows a much greater driving force to be exerted without damaging the head than the usual straight-slotted head. The greater part of all wood screws used (probably 75 percent or more) used to be the flat-head type. However, this has changed to the Phillips head screw in recent years because of the advent of the inexpensive power screwdriver attachments available on electric drills. The reversible electric drill combined with the variable speed trigger makes it possible to quickly drive a screw and to extract if necessary.

Material

For ordinary purposes, *steel screws* (with or without protective coatings) are commonly used. In boat building or other such work where corrosion will probably be a problem if screws are used, the screws should be of the same metal or at least the same *type* of metal as the parts they contact. While it is possible (and indeed probable) that a single brass screw driven through an aluminum plate, if it is kept dry, will show no signs of corrosion, many brass screws driven through the aluminum plate in the presence of water or dampness will almost certainly show signs (perhaps serious signs) of galvanic corrosion.

Dimensions of Screws

When ordering screws, you must know that length varies with head type. The overall length of a 2-inch flat-head screw is not the same as a 2-inch round-head screw (see Figure 1-16 and Figure 1-17).



Figure 1-16 Various wood screws and how their length is measured.

Shape of the Head

You can find a variety of head shapes on screws, but the three standard shapes are flat, round, and oval (see Figure 1-18). These usually will more than suffice.

All of these heads are available in the straight-slotted or Phillips type.

The other forms may be regarded as special or semispecial (that is, carried by large dealers only or obtainable only on special order).

Flat heads are necessary in some cases (such as on door hinges, where any projection would interfere with the proper working of the hinge). Flat-head screws are also employed on finish work where flush surfaces are desirable. The round and oval heads are normally ornamental, left exposed. Table 1-6 shows common head diameters of screws.

How to Drive a Wood Screw

Driving wood screws is made easier by drilling shank and pilot holes in the wood. Indeed, this may be the only way to do it. A shank-clearance hole (see Figure 1-19) should be the same size as the shank diameter of the screw.


No. INCH
0 0.0578
1 0.0710
2 0.0842
3 0.0973
4 0.1105
5 0.1236
6 0.1368
7 0.1500
8 0.1631
9 0.1763
10 0.1894
11 0.2026
12 0.2158
13 0.2289
14 0.2421
15 0.2552
No. INCH
16 0.2684
17 0.2816
18 0.2947
20 0.3210
22 0.3474
24 0.3737
26 0.4000
28 0.4263
30 0.4520

Figure 1-17 Wood screw gauge numbers.

A pilot hole should be equal in diameter to the root diameter of the screw thread and about three-quarters of the thread length for soft and medium-hard woods. For extremely hard woods, the pilot-hole depth should equal the thread length.

If the screw being inserted is the flat-head type, the hole should be countersunk (see Figure 1-20).

The foregoing process involves three separate steps. All of these can be performed at once by using a device of the type shown in Figure 1-21. This tool will drill the pilot hole, the shank-clearance hole, and the countersink all in one operation. Stanley calls its device the Screw-Mate. The Stanley company also makes a Screw-Sink, which counterbores. You can set the head of the screw beneath the surface, then plug the hole with a wood plug cut with a plug cutter from matching wood.

These tools are made in many sizes, one for each screw size, and they are available in complete sets or separately. The screw size is marked on the tool.



Figure 1-18 Various wood screws showing the variety of head shapes available: (A) Flat head, (B) oval head, (C) round head, (D) piano head, (E) oval fillister head, (F) countersunk fillister head, (G) felloe, (H) close head, (I) hexagon head, (J) headless, (K) square bung head, (L) grooved, (M) pinched head, (N) round bung head, (O) dowel, (P) winged, (Q) drive, (R) winged, and (S) winged head. Heads A through G may be obtained with Phillips-type head. Most will never be needed.

Table 1-6 Head Diameters

		Head Diameter		
Screw Gauge	***Screw Diameter***	***Flat***	***Round***	***Oval***
0	0.060	0.112	0.106	0.112
1	0.073	0.138	0.130	0.138
2	0.086	0.164	0.154	0.164
3	0.099	0.190	0.178	0.190
4	0.112	0.216	0.202	0.216
5	0.125	0.242	0.228	0.242
6	0.138	0.268	0.250	0.268
7	0.151	0.294	0.274	0.294
8	0.164	0.320	0.298	0.320
9	0.177	0.346	0.322	0.346
10	0.190	0.371	0.346	0.371
11	0.203	0.398	0.370	0.398
12	0.216	0.424	0.395	0.424
13	0.229	0.450	0.414	0.450
14	0.242	0.476	0.443	0.476
15	0.255	0.502	0.467	0.502
16	0.268	0.528	0.491	0.528
17	0.282	0.554	0.515	0.554
18	0.394	0.580	0.524	0.580
20	0.321	0.636	0.569	0.636
22	0.347	0.689	0.611	0.689
24	0.374	0.742	0.652	0.742
26	0.400	0.795	0.694	0.795
28	0.426	0.847	0.735	0.847
30	0.453	0.900	0.777	0.900

Strength of Wood Screws

Table 1-7 gives the safe resistance, or safe load (against pulling out), in pounds per linear inch of wood screws when inserted across the grain. For screws inserted with the grain, use 60 percent of these values.

The lateral load at right angles to the screw is much greater than that of nails. For conservative designing, assume a safe resistance of a No. 20 gauge screw at double that given for nails of the same length,


ROOT DIAMETER
FULL LENGTH (HARDWOOD)
DRILL PILOT HOLE ABOUT $^3/_4$ THREAD LENGTH (SOFT WOOD)
DRILL HOLE FULL LENGTH OF SHAFT
DRILL SAME SIZE AS SHANK DIAMETER
DRILL ROOT DIAMETER OF THREAD

Figure 1-19 Drilling shank-clearance and pilot holes.



Figure 1-20 A typical countersink.



Figure 1-21 A tool for drilling pilot hole, shank-clearance hole, and countersink in one operation.

Table 1-7 Safe Loads for Wood Screws

	Gauge Number							
Kind of Wood	***4***	***8***	***12***	***16***	***20***	***24***	***28***	***30***
White oak	80	100	130	150	170	180	190	200
Yellow pine	70	90	120	140	150	160	180	190
White pine	50	70	90	100	120	140	150	160

when the full length of the screw thread penetrates the supporting piece of the two connected pieces.

Table 1-8 shows standard wood screw proportions.

Lag Screws

By definition, a *lag screw* (see Figure 1-22) is a heavy-duty wood screw provided with a square or hexagonal head so that it may be turned by a wrench. Lag screws are large, heavy screws used where great strength is required (such as for heavy timber work). Table 1-9 gives the dimensions of ordinary lag screws.

How to Put in Lag Screws

First, bore a hole slightly larger than the diameter of the shank to a depth that is equal to the length that the shank will penetrate (see Figure 1-23). Then bore a second hole at the bottom of the first hole, equal to the root diameter of the threaded shank and to a depth of approximately one-half the length of the threaded portion. The exact size of this hole and its depth will, of course, depend on the kind of wood (the harder the wood, the larger the hole).

The resistance of a lag screw to turning is enormous when the hole is a little small, but this can be considerably decreased by smearing the threaded portion of the screw with beeswax.

Strength of Lag Screws

Table 1-10 gives the safe resistance, to pull out load, in pounds per linear inch of thread for lag screws when inserted across the grain.

Bolts

Bolts are used to bind parts tightly together where high strength is needed.

Manufacture of Bolts

The bolt-and-nut industry in America was started on a small scale in Marion, Connecticut, in 1818. In that year, Micah Rugg, a country



Table 1-8 Standard Wood Screw Proportions

Screw Numbers	*A*	*B*	*C*	*D*	*Number of Threads Per Inch*
0	......	......	......	0.0578	30
1	......	......	......	0.0710	28
2	0.1631	0.0454	0.030	0.0841	26
3	0.1894	0.0530	0.032	0.0973	24
4	0.2158	0.0605	0.034	0.1105	22
5	0.2421	0.0681	0.036	0.1236	20
6	0.2684	0.0757	0.039	0.1368	18
7	0.2947	0.0832	0.041	0.1500	17
8	0.3210	0.0809	0.043	0.1631	15
9	0.3474	0.0984	0.045	0.1763	14
10	0.3737	0.1059	0.048	0.1894	13
11	0.4000	0.1134	0.050	0.2026	12.5
12	0.4263	0.1210	0.052	0.2158	12
13	0.4427	0.1286	0.055	0.2289	11
14	0.4790	0.1362	0.057	0.2421	10
15	0.5053	0.1437	0.059	0.2552	9.5
16	0.5316	0.1513	0.061	0.2684	0
17	0.5579	0.1589	0.064	0.2815	8.5
18	0.5842	0.1665	0.066	0.2947	8
20	0.6368	0.1816	0.070	0.3210	7.5
22	0.6895	0.1967	0.075	0.3474	7.5
24	0.7421	0.2118	0.079	0.3737	7
26	0.7421	0.1967	0.084	0.4000	6.5
28	0.7948	0.2118	0.088	0.4263	6.5
30	0.8474	0.2270	0.093	0.4546	6



Figure 1-22 Ordinary lag screw.

Table 1-9 Lag Screws (inches)

Length	*Diameter*
3	$^5/_{16}$ to $^7/_8$
$3^1/_2$	$^5/_{16}$ to 1
4	$^5/_{16}$ to 1
$4^1/_2$	$^5/_{16}$ to 1
5	$^5/_{16}$ to 1
$5^1/_2$	$^5/_{16}$ to 1
6	$^5/_{16}$ to 1
$6^1/_2$	$^7/_{16}$ to 1
7	$^7/_{16}$ to 1
$7^1/_2$	$^7/_{16}$ to 1
8	$^7/_{16}$ to 1
9	$^7/_{16}$ to 1
10	$^1/_2$ to 1
11	$^1/_2$ to 1
12	$^1/_2$ to 1

blacksmith, made bolts by the forging process. The first machine used for this purpose was a device known as a *heading block*, which was operated by a foot treadle and a connecting lever. The connecting lever held the blank while it was being driven down into the impression in the heading block by a hammer. The square iron from which the bolt was made was first rounded so that it could get into the block.

At first, Rugg only made bolts to order, and charged at the rate of 16 cents apiece. This industry developed quite slowly until 1839 when Rugg went into partnership with Martin Barnes. Together they built the first exclusive bolt-and-nut factory in the United States.

Bolts were first manufactured in England in 1838 by Thomas Oliver of Darlston, Staffordshire. His machine was built on a


D
SLIGHTLY LARGER
THAN WORM OF SCREW
1/2D
BORE
LARGE
SMALL
SLIGHTLY LARGER
THAN SHANK OF SCREW

Figure 1-23 Drilling holes for lag screws.

Table 1-10 Safe Loads for Lag Screws (Inserted across the grain)

	Diameter of Screw in Inches				
Kind of Wood	1/2	5/8	3/4	7/8	1
White pine	590	620	730	790	900
Douglas fir	310	330	390	450	570
Yellow pine	310	330	390	450	570

somewhat different plan from that of Rugg's, but no doubt was a further development of the first machine. Oliver's machine was known as the English Oliver.

The construction of the early machines was carefully kept secret. It is related that in 1842, a Mr. Clark had his bolt-forging machine located in a room separated from the furnaces by a thick wall. The machine received the heated bars through a small hole, cut in the wall. The forge man was not even permitted to enter the room.

Kinds of Bolts

One commonly used bolt is the *carriage bolt*, which got its name from its prime early use: assembling horsedrawn carriages.

To install a carriage bolt, a hole (equal to the diameter of the shank) is bored. The bolt is then slipped into the hole, and a hammer is used to pound it down so that the neck seats well in the hole. A nut on the other end completes the job. It can be screwed on without having to hold the other end of the bolt.

Another type of bolt is the *machine bolt*, used on metal and wood parts (see Figure 1-24). The machine bolt is slipped into the hole and a wrench is used to hold its large square head on one end while another wrench is used to tighten a nut.

Figure 1-25 shows various types of bolts and Figure 1-26 shows a lock washer used on some types of bolts.

Proportions and Strength of Bolts

Ordinary bolts are manufactured in certain stock sizes. Table 1-11 gives these sizes for bolts from 1/4 inch up to 1 1/4 inches, with the length of thread.

For many years, the *coarse-thread bolt* was the only type available. Now, bolts with a much finer thread (called the *National Fine thread*) have become easily available (see Table 1-12). These have hex heads and hex nuts. They are finished much better than the stock



(A) Square head and square nut.



(B) Hexagon head and hexagon nut.

Figure 1-24 Machine bolts.

coarse-thread bolts and consequently are more expensive. Cheap *rolled-thread bolts* (with the threaded portions slightly upset) should not be used by the carpenter. When they are driven into a hole, either the hole is too large for the body of the bolt or the threaded portion reams it out too large for a snug fit. Good bolts have cut threads that have a maximum diameter no larger than the body of the bolt.

When a bolt is to be selected for a specific application, Table 1-13 should be consulted.

Example How much of a load may be applied to a 1-inch bolt for a tensile strength of 10,000 pounds per square inch?

Referring to Table 1-13, we find on the line beside 1-inch bolt a value of 5510 pounds corresponding to a stress on the bolt of 10,000 pounds per square inch.

Example What size bolt is required to support a load of 4000 pounds for a stress of 10,000 pounds per square inch?

$$\begin{aligned}\text{area (at root of thread)} &= \text{given load} \div 10{,}000\\ &= 4000 \div 10{,}000 = 0.400 \text{ square inch}\end{aligned}$$

Referring to Table 1-13, in the column headed *Area at Bottom of Thread*, we find 0.419 square inch to be the nearest area. This corresponds to a $^7/_8$-inch bolt.



Figure 1-25 Various bolts. In the figure, (A) is a railroad track bolt, (B) a welded eye bolt, (C) a plain forged eye bolt, (D) a shouldered eye bolt, (E) a carriage bolt, (F) a step bolt, (G) a stove bolt, and (H) an expansion bolt.



Figure 1-26 A lock washer. When the nut is screwed onto the bolt, it strikes the rib on the washer, which is much harder than the nut. The rib on the washer is forced into the nut, thus preventing the nut from loosening.

Of course, for the several given values of pounds stress per square inch, the result could be found directly from the table, but the previous calculation illustrates the method that would be employed for other stresses per square inch not given in the table.

Example A butt joint in wood timber with metal fishplates is fastened by six bolts through each member. What size bolts should be used, allowing a shearing stress of 5000 pounds per square inch in the bolts, when the joint is subjected to a tensile load of 20,000 pounds (see Figure 1-27)?

$$\text{load (carried per bolt)} = 20,000 \div \text{number of bolts}$$

$$= 20{,}000 \div 6 = 3333 \text{ pounds}$$

Each bolt is in double shear, hence:

$$\text{equivalent single shear load} = {}^{1}\!/_{2} \text{ of } 3333 = 1667 \text{ pounds}$$

and,

$$\text{area per bolt} = {}^{1667}\!/_{5000} = 0.333 \text{ square inch}$$

Referring to Table 1-13, the nearest area is 0.302, which corresponds to a $^{3}/_{4}$-inch bolt. In the case of a dead (or quiescent) load, $^{3}/_{4}$-inch bolts would be ample. However, for a live load, take the next larger size, or $^{7}/_{8}$-inch bolts.

Table 1-11 Properties of U.S. Standard Bolts (U.S. Standard or National Coarse Threads)

Diameter	*Number of Threads Per Inch (National Coarse Thread)*	*Head* 	*Head*	*Head*
1/4	20	3/8	13/32	1/2
5/16	18	1/2	35/64	43/64
3/8	16	9/16	5/8	3/4
7/16	14	5/8	11/16	53/64
1/2	13	3/4	53/64	1
9/16	12	7/8	31/32	1 15/32
5/8	11	15/16	1 1/32	1 1/4
3/4	10	1 1/8	1 15/64	1 1/2
7/8	9	1 5/16	1 29/64	1 47/64
1	8	1 1/2	1 21/32	1 63/64
1 1/8	7	1 11/16	1 55/64	2 15/64
1 1/4	7	1 7/8	2 1/16	2 31/64
1 3/8	6	2 1/16	2 17/64	2 47/64
1 1/2	6	2 1/4	2 31/64	2 63/64
1 5/8	5 1/2	2 7/16	2 11/16	3 15/64
1 3/4	5	2 5/8	2 57/64	3 31/64
1 7/8	5	2 13/16	3 3/32	3 47/64
2	4 1/2	3	3 5/16	6 63/64

Table 1-12 National Fine Threads

Diameter	*Threads Per Inch*
1/4	28
5/16	24
3/8	24
7/16	20
1/2	20
9/16	18
5/8	18
3/4	16
7/8	14
1	14

Table 1-13 Proportions and Strength of U.S. Standard Bolts

Bolt Diameter	Area at Bottom of Threads	Tensile Strength		
		10,000 lbs/in^2	12,500 lbs/in^2	17,500 lbs/in^2
$^1/_4$	0.027	270	340	470
$^5/_{16}$	0.045	450	570	790
$^3/_8$	0.068	680	850	1190
$^7/_{16}$	0.093	930	1170	1630
$^1/_2$	0.126	1260	1570	2200
$^9/_{16}$	0.162	1620	2030	2840
$^5/_8$	0.202	2020	2520	3530
$^3/_4$	0.302	3020	3770	5290
$^7/_8$	0.419	4190	5240	7340
1	0.551	5510	6890	9640
$1^1/_8$	0.693	6930	8660	12,130
$1^1/_4$	0.890	8890	11,120	15,570
$1^3/_8$	1.054	10,540	13,180	18,450
$1^1/_2$	1.294	12,940	16,170	22,640
$1^5/_8$	1.515	15,150	18,940	26,510
$1^3/_4$	1.745	17,450	21,800	30,520
$1^7/_8$	2.049	20,490	25,610	35,860
2	2.300	23,000	28,750	40,250

The example does not give the size of the members, but the assumption is they are large enough to carry the load safely. In practice, all parts should be calculated as described in Chapter 4, "Strength of Timbers." The ideal joint is one so proportioned that the total shearing stress of the bolts equals the tensile strength of the timbers (see Figure 1-27).



Figure 1-27 Shearing stress and tensile strength.

Fasteners for Plaster or Drywall

Because of the relatively fragile nature of plaster and drywall in comparison to brick, stone, and concrete, fasteners used with the former must necessarily be different from those used with the latter. Whenever weight of any consequence is involved, or a direct outward pull is to be exerted, a fastening is best accomplished with standard wood screws or lag screws inserted through the object to be fastened and driven through the plaster or drywall directly into the studs, rafters, or other framing material beneath. When this is impossible, anchor directly to the plaster or drywall with one or more of the fastening devices discussed in the following sections.

Expansion Anchors

Metal *expansion anchors* are unsuitable for use with plaster or gypsum board because they tend to crush the walls of the hole into which they are inserted, and then fall or pull out easily (assuming they can be tightened in place to begin with). Plastic expansion anchors (see Figure 1-28) are better in this regard, perform their best with radial loads, and are the poorest of any anchor on axial loads.



Figure 1-28 Expansion anchors: (A) made from lead alloy for use with lag screws, (B) made from a softer lead alloy for use with wood screws, (C) made from plastic and best used with sheet-metal screws, and (D) made from fiber-jacketed lead—a plug-type anchor sized here for small wood screws.

This poor axial-load performance can be countered (to a degree) by using more than one anchor to support the load (as in a ceiling-mounted traverse rod, for example).

Holes for plastic expansion anchors are best bored with a twist or push drill in both plaster and gypsum board to get an accurate fit. Holes jabbed with an ice pick, screwdriver, or similar tool are seldom sized correctly for the best friction fit and may have considerable material knocked away from the edge of the hole, inside the wall, making the site useless for an anchor. Bore the hole the diameter specified on the anchor package and use the screw size specified there, also. The length of the screw should be equal to the length of the anchor, plus the thickness of the object to be fastened, as a minimum. As a rule, sheet-metal screws work better in plastic anchors than do wood screws, possibly because their comparative lack of body taper causes a more effective expansion of the anchor.

Hollow Wall Screw Anchors

These devices are manufactured by a number of different companies. They consist of a metal tube having a large flange at one end and an internally threaded collar at the other. A machine screw is inserted through a hole in the flange, extended the length of the tube, and screwed into the threaded collar (see Figure 1-29).

In use, a hole of specified diameter is bored through the gypsum board or plaster. An anchor (see Table 1-14) of the proper grip range (depending on the thickness of the drywall or plaster) and screw size


MACHINE SCREW
FLANGE
BODY SEGMENTS, WHICH BEND AS SCREW IS TURNED
THREADED COLLAR
DISTANCE SHOULD BE EQUAL TO APPROXIMATE THICKNESS OF WALL FACING.

Figure 1-29 Two sizes of hollow wall screw anchors.

Table 1-14 Allowable Carrying Loads for Anchor Bolts

		Allowable Load	
Type Fastener	***Size***	***$^1/_2$-inch Wallboard***	***$^5/_8$-inch Wallboard***
Hollow wall screw anchors	$^1/_8$-inch dia. short	50 lbs	—
	$^3/_{16}$ -inch dia. short	65 lbs	—
	$^1/_4$ -inch, $^5/_{16}$ -inch, $^3/_8$ -inch	65 lbs	—
	dia. short	—	90 lbs
	$^3/_{16}$ -inch dia. long	—	95 lbs
	$^1/_4$ -inch, $^5/_{16}$ -inch, $^3/_8$ -inch		
	dia. long		
Common toggle bolts	$^1/_8$ -inch dia.	50 lbs	90 lbs
	$^3/_{16}$ -inch dia.	60 lbs	120 lbs
	$^1/_4$ -inch, $^5/_{16}$ -inch,	80 lbs	120 lbs
	$^3/_8$ -inch dia.		

(Courtesy National Gypsum Co.)

(depending on the weight of the object to be anchored) is inserted. This is so that its length is inside the wall and its flange rests against the wall's surface. The anchor is then lightly tapped with the butt of a screwdriver to seat it and prevent it from turning in the hole. The screw is then turned clockwise with a screwdriver.

As the screw is turned, it draws the collar end of the anchor toward the flange end. Four slots cut lengthwise into the tube allow the sections of the tube between the slots to bend outward in response to pressure from the collar until they lie flat against the inside surface of the wall, drawing the flange tightly against the outside surface and locking the anchor securely in place. The screw is then removed, inserted through whatever object is to be fastened, and replaced in the anchor body, an action that can be performed repeatedly without loosening the anchor body.

Hollow wall screw anchors are also manufactured with pointed screws and tapered threaded collars. These can be driven into the wall without drilling a hole first. Very short anchors are also available for use in thin wood paneling and hollow-core flush doors.

Once they are in place, the anchors are removable only with some ingenuity if a large hole in the wall is to be avoided. One method that works (but must be done gently) is to replace the screw in the anchor with another one of the same size and thread, but longer. This replacement screw must be threaded into the anchor only one turn (if at all). Once it is in place, smack the head of the screw with a hammer. This action may straighten out the bent legs of the anchor so that it can be withdrawn from the wall intact. More frequently, it will either break off the legs or break off the flange.

Remove the screw, and in the former case, pull the flanged section of the anchor out of the wall with the fingers (if it won't come out all the way, pull it out as far as possible, cut it in two with diagonal cutters, and let the stubborn half drop down inside the wall cavity). If the flange breaks off, push the remainder of the anchor back inside the wall. The only hole to be patched will be the one originally bored for the anchor, although a too-vigorous hammer blow can produce an additional dimple in the wall surface. The method is a little risky with very soft or very thin wall facings because their relative lack of substance may allow the flange to be driven backward through the facing. Let good judgment be the guide. It may be better to leave the anchor alone.

Toggle Bolts

These differ from hollow wall anchors in that they must be attached to the object to be fastened before they are inserted into the wall. In their larger sizes, they will carry a heavier load (see Table 1-14). In all sizes, they are good for axial as well as radial loads, need a larger hole for mounting, and once mounted, cannot be reused if the screw is removed from the toggle. A longer screw is necessary in order to allow the wings of the toggle to unfold in the wall cavity.

Toggle bolts (see Figure 1-30) are simple devices consisting of a center-hinged crosspiece pierced in the middle by a long machine screw. The crosspiece (called the *toggle*) is composed of two halves (called the *wings*) hinged around a threaded center through which the screw runs. The wings are normally held at almost a right angle to the screw by spring pressure but can be folded flat along the screw to allow insertion into the wall. Once inside the wall cavity, they automatically snap upright again (they fold only one way—toward the head of the screw) and prevent removal of the unit. Tightening the screw squeezes the toggle firmly against the inner wall surface and the object to be fastened against the outer wall



Figure 1-30 Common toggle bolt.

surface. Removing the screw allows the toggle to drop into the wall cavity; hence, the unit is easily removed but, in most cases, is not reusable because the toggle cannot be recovered.

Toggle bolts are commonly available with screw diameters from $^1/_8$ inch to $^3/_8$ inch and screw lengths to 6 inches, although they can be fitted with screws of any maximum practical length by using threaded rod. Minimum screw length should equal the thickness of the object to be fastened, plus the thickness of the wall facing, plus the length of the wings when folded, plus $^1/_4$ inch. The maximum length should not exceed the minimum by much, if at all, or the screw can bottom against the opposite wall facing and be impossible to tighten.

Hanger Bolts, Dowel Screws, and Toggle Studs

Whenever a hook is to be installed in a plaster or gypsum board ceiling, it should be driven through the ceiling material and into a joist if at all possible. Since most common ornamental hooks are supplied with female machine threads, a device called a *hanger bolt* (see Figure 1-31) is necessary to accomplish this.



Figure 1-31 Hanger bolt with wood screw threads at top and machine-screw threads at bottom.

Hanger bolts are relatively short lengths of steel rod having a machine-screw thread on one end and a wood-screw thread on the other. The machine-screw thread is turned into the ornamental hook until it bottoms, and then the whole unit is turned to sink the wood-screw threads into the ceiling and ceiling joist. A pilot hole should be bored into the joist to make turning easier and to prevent possible breakage of the hook if too much twisting force is applied.

Although ornamental hooks are mentioned here as an example, almost any device can be mounted to the ceiling or wall by using a hanger bolt in a similar manner or by using a standard nut on the machine-screw threads protruding from the wall or ceiling.

Dowel screws (which are identical to hanger bolts except that they have wood-screw thread on both ends) can be used to fasten something of wood to a ceiling or wall in the same way.

If an object having female machine threads cannot be fastened to a ceiling joist or wall stud by a hanger bolt, a *toggle stud* is used



Figure 1-32 (A) One useful kind of framing fastener is the joist hanger. (B) Perforated plates such as shown can be used to make trusses. *(Courtesy of Teco.)*

instead. All this amounts to is a toggle bolt without a head on the screw. This is so that the screw can be turned into the female machine threads in the device to be mounted. A toggle stud will not bear as much weight as a hanger bolt, but it should be adequate for a small to medium-size flowerpot and hanger. It is used the same as a toggle bolt.

Framing Fasteners

Framing fasteners are stamped metal pieces (16 or 18 gauge) with predrilled nail (or screw) holes. You set the fastener between the pieces and drive the nails through the holes to lock the members together. The result is a very strong connection. It should be noted that not all building codes accept them, so their use should be checked out beforehand (see Figure 1-32).

Summary

Nails are the carpenter's most useful fastener. Many nail types and sizes are available to meet the demands of the industry. On any kind of construction work, an important consideration is the type and size of nails to use.

An important factor in selecting nails is size. Long, thin nails will break at the joints of the lumber. Short, thick nails will work loose quickly. The kind of wood is a big factor in determining the size of nail to use.

Wood screws are often used in carpentry because of their advantage over nails in strength. They are used in installing various types of building hardware because of their great resistance to pulling out and because they are more or less readily removed in case of repairs or alterations.

There are generally three standard types of screw heads: the flat countersunk head, the round head, and the oval head. All of these can be obtained in crossed slot, single straight slot, or Phillips slot.

Lag screws or lag bolts are heavy-duty wood screws that are provided with a square or hexagonal head so that they are installed with a wrench. These are large, heavy screws that are used where great strength is needed, such as when working with heavy timber and beam installations. Holes are generally bored into the wood because the diameter of lag screws is large.

A bolt is generally regarded as a rod having a head at one end and a threaded portion on the other to receive a nut. The nut is usually considered as forming a part of the bolt. Bolts are used to connect two or more pieces of material when a very strong connection is required.

Various forms of bolts are manufactured to meet the demands and requirements of the building trade. The common machine bolt has a square or hexagonal head. The carriage bolt has a round head; the stove bolt has a round or countersunk head with a single slot. Lock washers are used to prevent nuts from loosening. Other fasteners are the toggle, Molly, and expansion bolt.

Review Questions

1. What is nail holding power?
2. Explain the penny nail system.
3. What should be considered when selecting a nail for a particular job?
4. Name and describe five kinds of useful nails.
5. Name the three basic head shapes of wood screws.
6. What type of wood screw is used where great strength is required?
7. What type of head is used on lag screws? Why?
8. What is meant by the root diameter of a screw?
9. What type of head is generally found on a machine bolt?
10. What is meant by threads per inch?
11. Explain the purpose of lock washers.
12. What is an expansion bolt?

Chapter 2

Wood as a Building Material

Wood is the most versatile, most useful building material, and a general knowledge of the physical characteristics of various woods used in building is important for carpenters and builders.

Growth and Structure of Wood

Wood, like all plant material, is made up of cells (or *fibers*) that, when magnified, have an appearance similar to (though less regular than) that of the common honeycomb. The walls of the honeycomb correspond to the walls of the fibers, and the cavities in the honeycomb correspond to the hollow or open spaces of the fibers.

Softwoods and Hardwoods

All lumber is divided as a matter of convenience into two great groups: *softwoods* and *hardwoods*. The softwoods in general are the coniferous or cone-bearing trees (such as the various pines, spruces, hemlocks, firs, and cedar). The hardwoods are the non–cone-bearing trees (such as the maple, oak, and poplar). These terms are used as a matter of custom, for not all so-called softwoods are soft, nor are all so-called hardwoods necessarily hard. In fact, such softwoods as long-leaf southern pine and Douglas fir are much harder than poplar, basswood, and so on, which are called hardwoods.

Other (and perhaps more accurate) terms often used for these two groups are the needle-bearing trees (softwoods) and the broad-leaved trees (hardwoods). In general, the softwoods are more commonly used for structural purposes such as for joists, studs, girders, and posts, whereas the hardwoods are more likely to be used for interior finish, flooring, and furniture. The softwoods are also used for interior finish and, in many cases, for floors, but are not often used for furniture.

A tree consists of the following:

- *Outer bark*—The bark is living and growing only at the cambium layer. In most trees, the bark continually sloughs away.
- *Inner bark*—In some trees (notably hickories and basswood) there are long tough fibers (called *bast fibers*) in the inner bark. In other trees (such as the beech), these bast fibers are absent.
- *Cambium layer*—This can be only one cell thick. Only these cells are living and growing.

- *Medullary rays or wood fibers*—These run radially from the center to the bark.
- *Annual rings*—These are layers of wood.
- *Pith*—This is at the very center.

Around the pith, the wood substance is arranged in approximately concentric rings (see Figure 2-1). The part nearest the pith is usually darker than the parts nearest the bark and is called the *heartwood*. The cells in the heartwood are dead. Nearer the bark is the *sapwood*, where the cells carry or store nutrients but are not living (see Figure 2-2).



Figure 2-1 Cross-section of an oak nine years old, shows pith, concentric rings comprising the woody part, the cambium layer, and the bark. The tree grows in concentric rings (or layers) with one layer added each year. The rings are also called annual rings.

As winter approaches, all growth ceases. Each annual ring is separate and, in most cases, distinct. The leaves of deciduous trees (or trees that shed their leaves) and the leaves of some of the conifers (such as cypress and larch) fall, and the sap in the tree may freeze hard. The tree is dormant but not dead. With the warm days of the next spring, growth starts again strongly, and the cycle is repeated. The width of the annual rings varies greatly, from 30 to 40 or more per inch in some slow-growing species, to as few as 3 or 4 per inch in some of the quick-growing softwoods.



Figure 2-2 A piece of wood magnified to show its structure. The wood is made up of long, slender cells called fibers, which usually lie parallel to the pith. The length of these cells is often 100 times their diameter. Transversely, bands of other cells, elongated but much shorter, serve to carry sap and nutrients across the trunk radially. In addition, in the hardwoods, long vessels or tubes (often several feet long) carry liquids up the tree. There are no sap-carrying vessels in the softwoods, but spaces between the cells may be filled with resins.

Lumber Conversion

When logs are taken to the mill, they may be cut in a variety of ways. One way of cutting is *quartersawing* (see Figure 2-3). Here, each log is ripped into quarters, as shown in the figure. Quartersawing is rarely done this way, though, because only a few wide boards are yielded. There is too much waste. More often, wood is *rift-sawed*. The log is started as shown in Figure 2-4 and is plain-sawed until a good figure (pattern) shows, then turned over and rift-sawed. This way, there is less waste, and the boards are wide.

The result is *vertical-grain*, or *rift-grain* lumber. Vertical-grain lumber shrinks less in width. It is often used in door stiles and rails because it is less likely to warp.

The plain sawed stock is simply flat-sawn out of the log (see Figure 2-5). This results in *flat-grain* or *side-grain* lumber that is used where shrinkage and warping are less critical.


COMBINED RADIAL AND TANGENTIAL
RADIAL
D
A
C
B
QUARTER TANGENTIAL
TANGENTIAL

Figure 2-3 Methods of quartersawing. These are rarely used because waste is extensive.



Figure 2-4 Plain or bastard sawing, sometimes called flat or slash sawing. The log is first squared by removing boards M, S, L, and F, giving the rectangular section ABCD. This is necessary to obtain a flat surface on the log.

Seasoning of Wood

Well-developed techniques have been established for removing the large amounts of moisture normally present in green wood. Seasoning is essentially a drying process, but for uses that require them, seasoning includes equalizing and conditioning treatments to improve



Figure 2-5 (A) Quartersawed and (B) plain-sawed boards cut from a log. *(Courtesy Forest Product Lab)*

moisture uniformity and relieve residual stresses and sets. Careful techniques are necessary, especially during the drying phase, to protect the wood from stain and decay and from excessive drying stresses that cause defects and degrade. The established seasoning methods are air-drying and kiln drying.

Drying has the following effects:

- Reduces the weight of wood, with a resulting decrease in shipping costs
- Reduces or eliminates shrinkage, checking, and warping in service
- Increases strength and nail holding power; decreases susceptibility to infection by blue stain and other fungi

- Reduces chance of attack by insects
- Improves the capacity of wood to take preservative and fire-retardant treatment and to hold paint

It is common practice at most softwood sawmills to kiln-dry all upper-grade lumber intended for finish, flooring, and cut stock. Lower-grade boards are often air-dried. Dimension lumber is air-dried or kiln-dried, although some mills ship certain species without seasoning. Timbers are generally not held long enough to be considered seasoned, but some drying may take place between sawing and shipment, or while they are held at a wholesale or distributing yard. Sawmills cutting hardwoods commonly classify the lumber for size and grade at the time of sawing. Some mills send all freshly sawed stock to the air-drying yard or an accelerated air-drying operation. Others kiln-dry directly from the green condition. Air-dried stock is kiln-dried at the sawmill, at a custom drying operation during transit, or at the remanufacturing plant before being made up into such finished products as furniture, cabinet work, interior finish, and flooring.

Air-drying is not a complete drying process, except as preparation for uses for which the recommended moisture content is not more than 5 percent below that of the air-dry stock. Even when air-drying conditions are mild, air-dry stock used without kiln-drying may have some residual stress and set that can cause distortions after nonuniform surfacing or machining. On the other hand, rapid air-drying accomplished by low relative humidities produces a large amount of set that will assist in reducing warp during final kiln drying. Rapid surface drying also greatly decreases the incidence of chemical and sticker stain, blue stain, and decay.

Air-drying is an economical seasoning method when carried out in a well-designed yard or shed, with proper piling practices (see Figure 2-6) and in favorable drying weather. In cold or humid weather, air-drying is slow and cannot readily reduce wood moisture to levels suitable for rapid kiln-drying or for use.

In kiln drying, higher temperatures and fast air circulation are used to increase the drying rate considerably. Average moisture content can be reduced to any desired value. Specific schedules are used to control the temperature and humidity in accordance with the moisture and stress situation within the wood, thus minimizing shrinkage-caused defects. For some purposes, equalizing and conditioning treatments are used to improve moisture content uniformity and relieve stresses and set at the end of drying, so the material will not warp when resawed or machined to smaller sizes or irregular



Figure 2-6 Horizontal stack of lumber for air-drying. One end of the pile should be a little higher. This is so that rainwater that falls on top or drives into the pile will drain. Each layer should be separated by three or four spacers so that the air will have free access to both sides of each board. The lowest layer should be well elevated above the ground to protect it from dampness. It takes from one to three years to thoroughly season lumber, depending upon the character of the wood, climatic conditions, and so on. When the spacers are carelessly placed so that they do not lie over each other, the weight must be supported by the board, which especially in the case of a high pile, is considerable, and will in time cause the board to sag, resulting in a permanent kink.

shapes. Further advantages of kiln drying are the setting of pitch in resinous woods, the killing of staining or decay fungi or insects in the wood, and reductions in weight greater than those achieved by air-drying. At the end of kiln-drying, moisture-monitoring equipment is sometimes used to sort out moist stock for redrying and to ensure that the material ready for shipment meets moisture content specifications.

Temperatures of ordinary kiln drying generally are between 110°F and 180°F. Elevated-temperature (180°F to 212°F) and high-temperature (above 212°F) kilns are becoming increasingly common, although some strength loss is possible with higher temperatures.

Moisture Content

While the tree is living, both the cells and cell walls are filled with water to an extent. As soon as the tree is cut, the water within the cells (or *free water* as it is called) begins to evaporate. This process continues until practically all of the free water has left the wood. When this stage is reached, the wood is said to be at the fiber-saturation point (that is, what water is contained is mainly in the cell or fiber walls).

Except in a few species, there is no change in size during this preliminary drying process, and, therefore, no shrinkage during the evaporation of the free water. Shrinkage begins only when water begins to leave the cell walls themselves. What causes shrinkage and other changes in wood is not fully understood. However, it is thought that as water leaves the cell walls, they contract, becoming harder and denser, thereby causing a general reduction in size of the piece of wood. If the specimen is placed in an oven that is maintained at 212°F (the temperature of boiling water), the water will evaporate and the specimen will continue to lose weight for a time. Finally, a point is reached at which the weight remains substantially constant. This is another way of saying that all of the water in the cells and cell walls has been driven off. The piece is then said to be *oven dry*.

If it is now taken out of the oven and allowed to remain in the open air, it will gradually take on weight, because of the absorption of moisture from the air. As when placed in the oven, a point is reached at which the weight of the wood in contact with the air remains more or less constant. Careful tests, however, show that it does not remain exactly constant—it will take on and give off water as the moisture in the atmosphere increases or decreases. Thus, a piece of wood will contain more water during the humid, moist summer months than in the colder, drier winter months. When the piece is in this condition, it is in equilibrium with the air and is said to be *air dry*.

The amount of water contained by wood in the green condition varies greatly, not only with the species but also in the same species and even in the same tree, according to the position in the tree. However, as a general average, at the fiber-saturation point, most woods contain from 23 to 30 percent water as compared with the oven-dry weight of the wood. When air dry, most woods contain from 12 to 15 percent moisture.

As the wood dries from the green state (which is that of the freshly cut tree) to the fiber-saturation point, except in a few species, there is no change other than that of weight. It has already been pointed out that as the moisture dries out of the cell walls, in addition to the decrease in weight, shrinkage results in a definite decrease in size (see Figure 2-7). It has been found, however, that there is little or no decrease along the length of the grain, and that the decrease is at right angles to the grain.



Figure 2-7 Greatest shrinkage is in the direction of the annual rings (A). Characteristic shrinkage and distortion of flat boards, squares, and rounds as affected by the direction of the annual rings. Tangential shrinkage (A) is about twice as great as radial (B). There is little or no longitudinal (C) shrinkage. *(Courtesy Forest Product Lab)*

This is an important consideration to be remembered when framing a building. For example, a stud in a wall will not shrink appreciably in length, whereas it will shrink somewhat in both the 2-inch and the 4-inch way. In like manner, a joist, if it is green when put in place, will change in depth as it seasons in the building. These principles of shrinkage also explain why an edge-grain or quarter-sawed floor is less likely to open up than a flat-grain floor.

Density

The tree undergoes a considerable impetus early every spring and grows very rapidly for a short time. Large amounts of water are carried through the cells to the rapidly growing branches and leaves at the top of the tree. This water passes upward mainly in the outer layers of the tree. The result is that the cells next to the bark (which are formed during the period of rapid growth) have thin walls and large passages. Later on, during the summer, the rate of growth slows and the demand for water is less. The cells that are formed during the summer have much thicker walls and much smaller pores. Thus, a year's growth forms two types of wood: the *springwood* (characterized by softness and openness of grain) and the *summerwood* (characterized by hardness and closeness, or density, of grain). The springwood and summer wood growth for one year is called an *annual ring*.

Density and Strength

There is one ring for each year of growth. This development of springwood and summerwood is a marked characteristic of practically all woods that grow in a temperate climate. It is evident in such trees as the yellow pines and firs and less so in the white pines, maple, and the like. Careful examination will reveal this annual ring, however, in practically all species. It follows, therefore, that a tree in which the dense summerwood predominates is stronger than one in which the soft spring wood predominates. This is a point that should be kept in mind when selecting material for important members such as girders and posts carrying heavy loads. The strength of wood of the same species varies markedly with the density. For example, Douglas fir or southern pine, carefully selected for density, is one-sixth stronger than lumber of the same species and knot limitations in which the springwood predominates. Trees having approximately one-third or more of cross-sectional area in summerwood fulfill one of the requirements for structural timbers.

Estimating Density

It must be remembered that the small cells or fibers that make up the wood structure are hollow. Wood substance itself has a specific gravity of about 1.5. That means it will sink in water. It is stated that wood substance of all species is practically of the same density. Strength of wood depends upon its density and varies with its density. The actual dry weight of lumber is a good criterion of its strength, although weight cannot always be relied upon as a basis for determining strength, because other important factors frequently must be considered in a specific piece of wood.

The hardness of wood is also another factor that assists in estimating the strength of wood. A test sometimes used is cutting across the grain. This test cannot be utilized in the commercial grading of lumber because moisture content will affect the hardness and because hardness, thus measured, cannot be adequately defined. The annual rings found in practically all species are an important consideration in estimating density, although the annual rings indicate different conditions in different species. In ring-porous hardwoods and in the conifers, where the contrast between springwood and summerwood is definite, the proportion of hard summerwood is an indication of the strength of the individual piece of wood. The amount of summerwood, however, cannot always be relied upon as an indication of strength because summerwood itself varies in density. When cut across the grain with a knife, the density of summerwood may be estimated based on hardness, color, and luster.

In conifers, annual rings of average width indicate denser material or a larger proportion of summerwood than in wood with either wide or narrow rings. In some old conifers of virgin growth in which the more recent annual rings are narrow, the wood is less dense than where there has been normal growth. On the other hand, in young trees where the growth has not been impeded by other trees, the rings are wider and in consequence the wood less dense. These facts may account for the belief that all second-growth timber and all sapwood are weak. In analyzing wood for density, the contrast between summerwood and springwood should be pronounced.

Oak, ash, hickory, and other ring-porous hardwoods in general rank high in strength when the annual rings are wide. In this respect, they contrast with conifers. These species have more summerwood than springwood as the rings become wider. For this reason, oak, hickory, ash, and elm of second growth are considered superior because of fast growth and increase in proportion of summerwood. These conditions do not always exist, however, because exceptions occur, especially in ash and oak, where, although the summerwood is about normal, it may not be dense or strong. Very narrow rings in ring-porous hardwoods are likely to indicate weak and brash material composed largely of spring wood with big pores. Maple, birch, beech, and other diffuse-porous hardwoods in general show no definite relationship between the width of rings and density, except that usually narrow rings indicate brash wood.

Strength

Wood, when used in ordinary structures, is called upon to have three types of strength: tension, compression, and shear.

Tension

Tension is the technical term for a pulling stress. For example, if two people are having a tug of war with a rope, the rope is in tension. The tensile strength of wood, especially of the structural grades, is very high.

Compression

If, however, the people at opposite ends of a 2 × 4 are trying to push each other over, the timber is in *compression*. Tension and compression represent, therefore, exactly opposite forces.

Shear

If two or three planks are placed one upon the other between two blocks, and a person were to stand in the middle, the planks would bend (see Figure 2-8). It will be noted that at the outer ends the boards tend to slip past each other.



Figure 2-8 Illustrating shear in lumber.

If the planks were securely spiked through from top to bottom, the slipping would be in a great measure prevented and the boards would act more as one piece of wood. In very solid timber, there is the same tendency for the various parts of the piece to slip past each other. This tendency is called *horizontal shear*. A defect (such as a check, which runs horizontally through a piece of a timber and tends to separate the upper from the lower part) is a weakness in shear.

Suppose that the planks were spiked through at the center of span only (that is, halfway between the blocks). Such spikes would not increase the stiffness of the planks. It is clear, therefore, that there is no horizontal shear near the center of the span (see Figure 2-9), and that the shear increases as one approaches either end of the beam. This will explain why, as most carpenters have doubtlessly observed, steel stirrups are used in concrete beams (weak in shear), why there is usually none near the center, and why they are put closer and closer together near the ends of the beams.



Figure 2-9 Illustrating the different proportions of tension, compression, and shear.

For all practical purposes, the compressive strength of wood may be considered to equal its tensile strength. It has been extremely difficult to make any direct measurements of the tensile strength of wood. In an experiment designed to ascertain the tensile strength of a specimen of wood, a 4-inch × 4-inch piece was selected. A portion about a foot in length near the center was carefully cut down on all four sides until it was exactly 3/4-inch square. The test specimen was placed in a machine that gripped the 4-inch × 4-inch ends securely and a pull was exerted. The specimen did not pull apart. The 3/4-inch-square section held and actually pulled out of the end of the 4-inch × 4-inch, leaving a 3/4-inch square hole. This is an excellent illustration of how a piece may fail from shear rather than tension, the shear in this case being insufficient to prevent the 3/4-inch-square piece from pulling out.

Deadwood

Because in some instances persons are prejudiced against the use of timber cut from dead trees, it is customary for individuals to specify that only timber cut from live trees will be accepted. It is true, however, that when sound trees that are dead are sawed into lumber and the weathered or charred outside is cut away, the resulting lumber cannot be distinguished from that coming from live trees except insofar as the lumber from dead trees may be somewhat seasoned at the time it is sawed. It must be remembered that the heartwood of a living tree is fully matured and that in the sapwood only a small portion of the cells are in a living condition. Consequently, most of the wood cut from trees is already dead, even when the tree itself is considered alive.

For structural purposes, it may be said that lumber cut from fire- or insect-killed trees is just as good as any other lumber, unless the wood has been subjected to further decay or insect attack.

Virgin and Second Growth

Occasionally an order calls for lumber of either virgin growth or second growth. The terms, however, are without significance, as an individual cannot tell one type from the other when it is delivered.

The *virgin growth* (which is also called *old growth* or *first growth*) refers to timber that grows in the forest along with many other trees, and, therefore, has suffered the consequence of the fight for sunlight and moisture.

The *second growth* is considered as that timber that grows up with less of the competition for sunlight and moisture that characterizes first-growth timber.

Because of environment, the virgin growth is usually thought of as wood of slow-growing type, whereas the second growth is considered as of relatively rapid growth, evidenced by wider annual rings. In such hardwoods as ash, hickory, elm, and oak, the wider annual rings are supposed to indicate stronger and tougher wood, whereas in the conifers such as pine and fir, this condition is supposed to result in a weaker and brasher wood. For this reason, where the strength and toughness are desired, the second growth is preferred among hardwoods, and virgin growth is desired in conifers. This is because of the following:

- The variety of conditions under which both virgin and second growth timbers grow
- Virgin growth may have the characteristics of second growth
- Second growth may have the characteristics of virgin timber

It is advisable in judging the strength of wood to rely upon its density and rate of growth, rather than upon its being either virgin or second growth.

Time of Cutting Timber

The time when timber is cut has very little to do with its durability or other desirable properties if, after it is cut, it is cared for properly. Timber cut in the late spring, however, or early summer is more likely to be attacked by insects and fungi. In addition, seasoning will proceed much more rapidly during the summer months and, therefore, will result in checking, unless the lumber is shaded from the intense sunlight. There is practically no difference in the moisture content in green lumber cut during the summer or winter.

Air-Dried and Kiln-Dried Wood

There is a prevailing misapprehension that air-dried lumber is stronger or better than kiln-dried lumber. Exhaustive tests have conclusively shown that good kiln-drying and good air-drying have exactly the same results on the strength of the wood. Wood increases in strength with the elimination of moisture content. This may account for the claim that kiln-dried lumber is stronger than air-dried lumber. This has little significance because, in use, wood will come to practically the same moisture content whether it has been kiln-dried or air-dried.

The same kiln-drying process cannot be applied to all species of wood. Consequently, it must be remembered that lack of certain strength properties in wood may be because of improper kiln-drying. Similar damage also may result from air seasoning under unsuitable conditions.

Sapwood Versus Heartwood

The belief is common that in some species the heartwood is stronger than the sapwood, and that the reverse is the case in such species as hickory and ash. Tests have shown conclusively that neither is the case, sapwood is not necessarily stronger than heartwood or heartwood stronger than sapwood, but that density (rather than other factors) makes the difference in strength. In trees that are mature, the sapwood is frequently weaker, whereas in young trees the sapwood may be stronger. Density, proportion of springwood and summerwood, then must be the basis of consideration of strength rather than whether the wood is sapwood or heartwood. Under unfavorable conditions, the sapwood of most species is more subject to decay than the heartwood.

The cells in the heartwood of some species are filled with various oils, tannins, and other substances (called *extratives*) that make these timbers rot-resistant. There is practically no difference in the strength of heartwood and sapwood if they weigh the same. In most species, only the sapwood can be readily impregnated with preservatives, a procedure used when the wood will be in contact with the ground.

Defects and Deterioration

The defects found in manufactured lumber have several causes. Those defects found in the natural log include the following:

- Shakes
- Knots
- Pitchpockets

Those caused by deterioration include the following:

- Rot
- Dote

Those caused by imperfect manufacture include the following:

- Imperfect machining
- Wane
- Machine burn
- Checks and splits from imperfect drying

Heart shakes (see Figure 2-10) are radial cracks that are wider at the pith of the tree than at the outer end. This defect is more commonly found in old trees rather than in young vigorous saplings. It occurs frequently in hemlock.


STAR SHAKE
HEART SHAKE
WIND OR CUP SHAKE
ANNUAL LAYERS BULGING OUTWARD TO COVER BREAK
LIVE BRANCH
BROKEN BRANCH

Figure 2-10 The causes of some lumber defects are found in the natural log.

A *wind shake* or *cup shake* is a crack following the line of the porous part of the annual rings and is curved by a separation of the annual rings (see Figure 2-10). A wind shake may extend for a considerable distance up the trunk. Other explanations for wind shakes are expansion of the sapwood and wrenching from high wind (hence the name). Brown ash is especially susceptible to wind shake. Wind shakes cause cup checks in lumber (see Figure 2-11A). A *star shake* resembles a wind shake but differs from it in that the crack extends across the center of the trunk without any appearance of decay at that point; it is larger at the outside of the tree. Heart and star shakes cause splits in lumber (see Figure 2-11B).



(A) CUP CHECKS



(B) END SPLIT

Figure 2-11 Lumber defects caused by defects in the log. (A) Cup checks are caused by wind shakes. (B) End splits are caused by star and heart shakes. *(Courtesy Practical Restoration Reports)*

Figure 2-12 shows some common causes of black or loose knots. Figures 2-13 and 2-14 show some results of improper drying practices.

Decay of Wood

Decay of lumber is the result of one cause and one cause only: the work of certain low-order plants called *fungi*. All of these organisms require water, air, and temperatures well above freezing to live, grow, and multiply. Consequently, wood that is kept dry, or that is dried quickly after wetting, will not decay.



Figure 2-12 Black or loose knots (A) are caused by broken branches in the log. Bulging layers of growth cause a large swirl of cross grain at the surface of the board surrounding the knot. Tight red knots (B) are caused by a live branch in the log. The knot will not fall out and grain is relatively straight around the knot. *(Courtesy Practical Restoration Reports)*



Figure 2-13 A board with splits along the medullary rays. This condition is caused by too-rapid kiln-drying.



Figure 2-14 Warping is frequently caused by improper drying practices. Here the flatness of boards is distorted by irregular shrinkage. *(Courtesy Practical Restoration Reports)*

Further, if it is kept continuously submerged in water even for long periods, it is not decayed significantly by the common decay fungi regardless of the wood species or the presence of sapwood. Bacteria and certain soft-rot fungi can attack submerged wood, but the resulting deterioration is very slow. A large proportion of wood in use is kept so dry at all times that it lasts indefinitely. Moisture and temperature (which vary greatly with local conditions) are the principal factors affecting rate of decay. When exposed to conditions that favor decay, wood deteriorates more rapidly in warm, humid areas than in cool or dry areas. High altitudes, as a rule, are less favorable to decay than low altitudes because the average temperatures are lower and the growing seasons for fungi that cause decay are shorter.

The heartwoods of some common native species of wood have varying degrees of natural decay resistance. Untreated sapwood of substantially all species has low resistance to decay and usually has a short service life under decay-producing conditions. The decay resistance of heartwood is greatly affected by differences in the preservative qualities of the wood extractives, the attacking fungus, and the conditions of exposure. Considerable difference in service life may be obtained from pieces of wood cut from the same species, or even from the same tree, and used under apparently similar conditions. There are further complications because, in a few species, such as the spruces and the true firs (not Douglas fir), heartwood and sapwood are so similar in color that they cannot be easily distinguished. Marketable sizes of some species, such as southern pine and baldcypress, are becoming largely second growth. They contain a high percentage of sapwood.

Precise ratings of the decay resistance of heartwood of different species are not possible because of differences within species and the variety of service conditions to which wood is exposed. However, broad groupings of many of the native species, based on service records, laboratory tests, and general experience, are helpful in choosing heartwood for use under conditions favorable to decay (see Table 2-1). The extent of variations in decay resistance of individual trees or wood samples of a species is much greater for most of the more resistant species than for the slightly or nonresistant species.

Where decay hazards exist, heartwood of species in the resistant or very resistant category generally gives satisfactory service. However, heartwood of species in the other two categories will usually require some form of preservative treatment. For mild decay conditions, a simple preservative treatment (such as a short soak in preservative after all cutting and boring operations are complete) will be adequate for wood low in decay resistance. For more severe decay hazards, pressure treatments are often required. Even the very decay-resistant species may require preservative treatment for important structural or other uses where failure would endanger life or require expensive repairs.

Wood products sometimes are treated with preservative or fire-retarding salts (usually in water solution) to impart resistance to decay or fire. Such products generally are kiln-dried after treatment. Mechanical properties are essentially unchanged by preservative treatment.

Properties are affected to some extent by the combined effects of fire-retardant chemicals, treatment methods, and kiln-drying. A

Table 2-1 Grouping of Some Domestic Woods According to Heartwood Decay

Resistant or Very Resistant	*Moderately Resistant*	*Slightly or Nonresistant*
Baldcypress (old growth)[*]	Baldcypress (young growth)[*]	Alder
Catalpa	Douglas fir	Ashes
Cedars	Honey locust	Aspens
Cherry, black	Larch, western	Basswood
Chestnut	Oak, swamp chestnut	Beech
Cypress, Arizona	Pine, eastern white[*]	Birches
Junipers	Southern pine:	Buckeye
Locust, black[†]	Longleaf[*]	Butternut
Mesquite	Slash[*]	Cottonwood
Mulberry, red[†]	Tamarack	Elms
Oak:		Hackberry
Bur		Hemlocks
Chestnut		Hickories
Gambel		Magnolia
Oregon white		Maples
Post		Oak (red and black species)
White		Pines (other than long-leaf, slash, and eastern white)
Osage orange[†]		Poplars
Redwood		Spruces
Sassafras		Sweetgum
Walnut, black		True firs (western and eastern)
Yew, Pacific[†]		Willows
		Yellow poplar

[*] The southern and eastern pines and baldcypress are now largely second growth with a large proportion of sapwood. Consequently, substantial quantities of heartwood lumber of these species are not available.

[†] These woods have exceptionally high decay resistance.

variety of fire-retardant treatments have been studied. Collectively the studies indicate modulus of rupture, work to maximum load, and toughness are reduced by varying amounts depending on species and type of fire retardant. Work to maximum load and toughness are most affected, with reductions of as much as 45 percent. A reduction in modulus of rupture of as much as 20 percent has been observed. A design reduction of 10 percent is frequently used. Stiffness is not appreciably affected by fire-retardant treatments.

Wood is also sometimes impregnated with monomers (such as methyl methacrylate) that are subsequently polymerized. Many of the properties of the resulting composite are better. Generally, this is a result of filling the void spaces in the wood structure with plastic. The polymerization process and both the chemical nature and quantity of monomers are variables that influence composite properties.

Molding and Staining Fungi

Molding and *staining fungi* do not seriously affect most mechanical properties of wood because they feed upon substance within the structural cell wall rather than on the structural wall itself. Specific gravity may be reduced by from 1 to 2 percent, whereas most of the strength properties are reduced by a comparable or only slightly greater extent. Toughness or shock resistance, however, may be reduced by up to 30 percent. The duration of infection and the species of fungi involved are important factors in determining the extent of weakening.

Although molds and stains themselves often do not have a major effect on the strength of wood products, conditions that favor the development of these organisms are likewise ideal for the growth of wood-destroying (decay) fungi, which can greatly reduce mechanical properties.

Fungal Decay

Unlike the molding and staining fungi, the *wood-destroying (decay) fungi* seriously reduce strength. Even what appears to be sound wood adjacent to obviously decayed parts may contain hard-to-detect, early (incipient) decay that is decidedly weakening, especially in shock resistance.

Not all wood-destroying fungi affect wood in the same way. The fungi that cause an easily recognized pitting of the wood, for example, may be less injurious to strength than those that, in the early stages, give a slight discoloration of the wood as the only visible effect.

No method is known for estimating the amount of reduction in strength from the appearance of decayed wood. Therefore, when strength is an important consideration, the safe procedure is to discard every piece that contains even a small amount of decay. An exception may be pieces in which decay occurs in a knot but does not extend into the surrounding wood.

Blue Stain

In the sapwood of many species of both softwoods and hardwoods, there often develops a bluish-black discoloration known as *blue stain*. It does not indicate an early stage of decay, nor does it have any practicable effect on the strength of the wood. Blue stain is caused by a fungus growth in unseasoned lumber. Although objectionable where appearance is of importance, as in unpainted trim, blue stain need cause no concern for framing lumber. Precautions should be taken, however, to make sure that no decay fungus is present with the blue stain.

Nuclear Radiation

Very large doses of gamma rays or neutrons can cause substantial degradation of wood. In general, irradiation with gamma rays in doses up to about 1 megarad has little effect on the strength properties of wood. As dosage increases above 1 megarad, tensile strength parallel to grain and toughness decrease. At a dosage of 300 megarads, tensile strength is reduced about 90 percent. Gamma rays also affect compressive strength parallel to grain above 1 megarad, but strength losses with further dosage are less than for tensile strength. Only about one-third of the compressive strength is lost when the total dose is 300 megarads. Effects of gamma rays on bending and shear strength are intermediate between the effects on tensile and compressive strength.

Weathering

Without protective treatment, freshly cut wood exposed to the weather changes materially in color. Other changes due to weathering include warping, loss of some surface fibers, and surface roughening and checking. The effects of weathering on wood may be desirable or undesirable, depending on the requirements for the particular wood product. The time required to reach the fully weathered appearance depends on the severity of the exposure to sun and rain. Once weathered, wood remains nearly unaltered in appearance.

The color of wood is affected very soon on exposure to weather. With continued exposure, all woods turn gray. However, only the wood at or near the exposed surfaces is noticeably affected. This very thin gray layer is composed chiefly of partially degraded cellulose fibers and microorganisms. Further weathering causes fibers to be lost from the surface, but the process is so slow that only about $^1/_4$ inch is lost in a century.

In the weathering process, chemical degradation is influenced greatly by the wavelength of light. The most severe effects are produced by exposure to ultraviolet light. As cycles of wetting and drying take place, most woods develop physical changes, such as checks or cracks that are easily visible. Moderate to low-density woods acquire fewer checks than do high-density woods. Vertical-grain boards check less than flat-grain boards.

Because of weathering, boards tend to warp (particularly cup) and pull out their fastenings. The cupping tendency varies with the density, width, and thickness of a board. The greater the density and the greater the width in proportion to the thickness, the greater is the tendency to cup. Warping also is more pronounced in flat-grain boards than in vertical-grain boards (see Figure 2-15). For best cup resistance, the width of a board should not exceed eight times its thickness.



Figure 2-15 Warping can also affect straightness of a board.
(Courtesy Practical Restoration Reports)

Biological attack of a wood surface by microorganisms is recognized as a contributing factor to color changes. When weathered wood has an unsightly dark gray and blotchy appearance, it is caused by dark-colored fungal spores and mycelium on the wood surface. The formation of a clean, light gray, silvery sheen on weathered wood occurs most frequently where microorganism growth is inhibited by a hot, arid climate or where there is a salt atmosphere, such as in coastal regions.

The contact of fasteners and other metallic products with the weathering wood surface is a source of color, often undesirable if a natural color is desired.

Insect Damage

Insect damage may occur in standing trees, logs, and unseasoned or seasoned lumber. Damage in the standing tree is difficult to control, but otherwise insect damage can be largely eliminated by proper control methods.

Insect holes are generally classified as *pinholes*, *grub holes*, and *powder postholes*. The powder post larvae, by their irregular burrows, may destroy most of the interior of a piece, although the surface shows only small holes, and the strength of the piece may be reduced virtually to zero.

No method is known for estimating the amount of reduction in strength from the appearance of insect-damaged wood, and, when strength is an important consideration, the safe procedure is to eliminate pieces containing insect holes.

Summary

Wood is the most versatile building material. Softwoods and hardwoods grow as trees with a fibrous cellular structure. Logs are converted into lumber and seasoned by drying. The physical characteristics of wood affect its performance and specific uses. Defects in lumber relate to defects in the logs it was cut from and how the lumber was handled during drying and storage. After wood is installed in a building, it can deteriorate by weathering, decay, or insects unless protected.

Review Questions

1. Describe the physical structure of wood with a drawing. Label the parts.
2. What are the characteristics of softwoods and hardwoods? How is each type of wood used in building?

3. What is the difference between vertical-grain wood and flat-grain wood? How is each produced?
4. Why does wood have to be seasoned? How does the moisture content and size of wood change during seasoning?
5. How does shear affect the strength of wood?
6. What substances make some woods decay-resistant?
7. How do defects in logs relate to defects in lumber? Give some examples.
8. What causes decay in wood? How can you stop decay?
9. How does weathering affect the color of wood?
10. How long would it take for a 1-inch thick board to weather away by fiber loss?
11. Would vertical-grain or flat-grain boards hold up better on an outdoor deck? Why?

Chapter 3

Lumber, Plywood, and Other Wood Products

The basic construction material in carpentry is lumber. There are many kinds of lumber varying greatly in structural characteristics. Here, we deal with the lumber common to construction carpentry (see Figure 3-1).



Figure 3-1 Construction lumber. Note the classification kiln-dried on one member. This stock will be used inside a structure.

(Courtesy of Vaughn & Bushnell)

Standard Sizes of Lumber

Lumber is usually sawed into standard lengths, widths, and thicknesses. This permits uniformity in planning structures and in ordering material (see Table 3-1). Standards have been established for dimension differences between *nominal size* and the *standard size*. It is important that these dimension differences be taken into consideration when planning a structure. A good example of the dimension difference may be illustrated by the common 2 × 4. As may be seen in the table, the familiar quoted size (2 × 4) refers to a rough or nominal dimension, but the actual standard size to which the lumber is dressed is $1^1/_2$ inches × $3^1/_2$ inches.

Table 3-1 Your Guide to New Sizes of Lumber

Standard (What You Order)	***Nominal (What You Get)***	
	Dry or Seasoned*	***Green or Unseasoned***[†]
1 × 4	$^3/_4 \times 3^1/_2$	$^{25}/_{32} \times 3^9/_{16}$
1 × 6	$^3/_4 \times 5^1/_2$	$^{25}/_{32} \times 5^5/_8$
1 × 8	$^3/_4 \times 7^1/_4$	$^{25}/_{32} \times 7^1/_2$
1 × 10	$^3/_4 \times 9^1/_4$	$^{25}/_{32} \times 9^1/_2$
1 × 12	$^3/_4 \times 11^1/_4$	$^{25}/_{32} \times 11^1/_2$
2 × 4	$1^1/_2 \times 3^1/_2$	$1^9/_{16} \times 3^9/_{16}$
2 × 6	$1^1/_2 \times 5^1/_2$	$1^9/_{16} \times 5^5/_8$
2 × 8	$1^1/_2 \times 7^1/_4$	$1^9/_{16} \times 7^1/_2$
2 × 10	$1^1/_2 \times 9^1/_4$	$1^9/_{16} \times 9^1/_2$
2 × 12	$1^1/_2 \times 11^1/_4$	$1^9/_{16} \times 11^1/_2$
4 × 4	$3^1/_2 \times 3^1/_2$	$3^9/_{16} \times 3^9/_{16}$
4 × 6	$3^1/_2 \times 5^1/_2$	$3^9/_{16} \times 5^5/_8$
4 × 8	$3^1/_2 \times 7^1/_4$	$3^9/_{16} \times 7^1/_2$
4 × 10	$3^1/_2 \times 9^1/_4$	$3^9/_{16} \times 9^1/_2$
4 × 12	$3^1/_2 \times 11^1/_4$	$3^9/_{16} \times 11^1/_2$

*19 percent moisture content or under.

[†] More than 19 percent moisture content.

Softwood Lumber Grades for Construction

The grading requirements of construction lumber are related specifically to the major construction uses intended, and little or no further grading occurs once the piece leaves the sawmill. Construction lumber can be placed in three general categories—stress-graded, nonstress-graded, and appearance lumber. *Stress-graded* and *nonstress-graded lumber* are employed where the structural integrity of the piece is the primary requirement. *Appearance lumber* encompasses those lumber products in which appearance is of primary importance (structural integrity, although sometimes important, is a secondary feature).

Stress-Graded Lumber

Almost all softwood lumber nominally 2 to 4 inches thick is stress-graded. Lumber of any species and size, as it is sawed from the log, is quite variable in its mechanical properties. Pieces may differ in strength by several hundred percent. For simplicity and economy in use, pieces of lumber of similar mechanical properties can be placed in a single class called a stress-grade.

Visual grading is the oldest stress-grading method. It is based on the premise that mechanical properties of lumber differ from mechanical properties of clear wood because of characteristics that can be seen and judged by eye. These visual characteristics are used to sort the lumber into stress grades (see Table 3-2). The following are major visual sorting criteria:

- Density
- Decay
- Heartwood and sapwood
- Slope of grain
- Knots
- Shake
- Checks and splits
- Wane
- Pitch pockets

Nonstress-Graded Lumber

Traditionally, much of the lumber intended for general building purposes with little or no remanufacture has not been assigned allowable properties (stress-graded). This category of lumber has been referred to as *yard lumber*. However, the assignment of allowable

Table 3-2 Visual Grades Described in the National Grading Rule*

Lumber Classification	***Grade Name***
Light framing (2 to 4 inches thick, 4 inches wide)†	Construction Standard Utility
Structural light framing (2 to 4 inches thick, 2 to 4 inches wide)	Select structural, 1, 2, 3
Studs (2 to 4 inches thick, 2 to 4 inches wide)	Stud
Structural joists and planks (2 to 4 inches thick, 6 inches and wide)	Select structural, 1, 2, 3
Appearance framing (2 to 4 inches thick, 2 to 4 inches wide)	Appearance

*Sizes shown are nominal.

†Widths narrower than 4 inches may have different strength ratio.

properties to an increasing number of former yard items has diluted the meaning of the term yard lumber.

In nonstress-graded structural lumber, the section properties (shape, size) of the pieces combine with the visual grade requirements to provide the degree of structural integrity intended. Typical nonstress-graded items include boards, lath, battens, crossarms, planks, and foundation stock.

Boards (sometimes referred to as *commons*) are one of the more important nonstress-graded products. Common grades of boards are suitable for construction and general utility purposes. They are separated into three to five different grades depending upon the species and lumber manufacturing association involved. Grades may be described by number (No. 1, No. 2) or by descriptive terms (Construction, Standard).

Since there are differences in the inherent properties of the various species and in corresponding names, the grades for different species are not always interchangeable in use. First-grade boards are usually graded primarily for serviceability, but appearance is also considered. This grade is used for such purposes as siding, cornice, shelving, and paneling. Features such as knots and knotholes are permitted to be larger and more frequent as the grade level becomes lower. Second- and third-grade boards are often used together for such purposes as subfloors, roof and wall sheathing, and rough concrete work. Fourth-grade boards are not selected for appearance but for adequate strength. They are used for roof and wall sheathing, subfloor, and rough concrete formwork.

Grading provisions for other nonstress-graded products vary by species, product, and grading association. Lath, for example, is available generally in two grades, No. 1 and No. 2. One grade of batten is listed in one grade rule and six in another.

Appearance Lumber

Appearance lumber often is nonstress-graded. However, it forms a separate category because of the distinct importance of appearance in the grading process. This category of construction lumber includes most lumber worked to a pattern. Secondary manufacture on these items is usually restricted to onsite fitting, such as cutting to length and mitering. There is an increasing trend toward prefinishing many items. The appearance category of lumber includes trim, siding, flooring, ceiling, paneling, casing, base, stepping, and finish boards. Finish boards are commonly used for shelving and built-in cabinetwork.

Most appearance lumber grades are described by letters and combinations of letters (B&BTR, C&BTR, D), as shown in Table 3-3. Appearance grades are also often known as Select grades. Descriptive terms such as prime and clear are applied to a limited number of species. The specification FG (flat grain), VG (vertical grain), or MG (mixed grain) is offered as a purchase option for some appearance lumber products. In cedar and redwood (where there is a pronounced difference in color between heartwood and sapwood, and where heartwood has high natural resistance to decay), grades of heartwood are denoted as heart. In some species and products, two (or, at most, three) grades are available. A typical example is casing and base in the grades of C&BTR and D in some species and in B&BTR, C, C&BTR, and D in other species. Although several grades may be described in grade rules, often fewer are offered on the retail market.

Table 3-3 Standard Lumber Abbreviations

Abbreviation	*Meaning*
AD	Air-dried
ALS	American Lumber Standard
AST	Antistain treated. At ship tackle (western softwoods)
AV or avg	Average
AW&L	All widths and lengths
B1S	See EB1S, CB1S, and E&CB1S
B2S	See EB2S, CB2S, and E&CB2S
B&B, B&BTR	B and Better
B&S	Beams and stringers
BD	Board
BD FT	Board feet
BDL	Bundle
BEV	Bevel or beveled
BH	Boxed heart
BM	Board measure
BSND	Bright sapwood no defect
BTR	Better
c	Allowable stress in compression in pounds per square inch
CB	Center beaded

(continued)

Table 3-3 *(continued)*

Abbreviation	***Meaning***
CB1S	Center bead on one side
CB2S	Center bead on two sides
cft or cu. ft.	Cubic foot or feet
CG2E	Center groove on two edges
CLG	Ceiling
CLR	Clear
CM	Center matched
Com	Common
CSG	Casing
CV	Center V
CV1S	Center V on one side
CV2S	Center V on two sides
DBClg	Double beaded ceiling (E&CB1S)
DB Part	Double beaded partition (E&CB2S)
DET	Double end trimmed
DF	Douglas-fir
DIM	Dimension
DKG	Decking
D/S,DS, D/Sdg	Drop siding
D1S,D2S	See S1S and S2S
D&M	Dressed and matched
D&CM	Dressed and center matched
D&SM	Dressed and standard matched
D2S&CM	Dressed two sides and center matched
D2S&SM	Dressed two sides and standard matched
E	Edge
EB1S	Edge bead one side
EB2S, SB2S	Edge bead on two sides
EE	Eased edges
EG	Edge (vertical or rift) grain
EM	End matched
EV1S, SV1S	Edge V one side
EV2S, SV2S.	Edge V two sides
E&CB1S	Edge and center bead one side
E&CB2S, DB2S, BC&2S	Edge and center bead two sides

(continued)

Table 3-3 (*continued*)

Abbreviation	***Meaning***
E&CV1S, DV1S, V&CV1S	Edge and center V one side
E&CV2S, DV2S, V&CV2S	Edge and center V two sides
f	Allowable stress in bending in pounds per square inch
FA	Facial area
FAS	Firsts and Seconds
FBM, Ft. BM	Feet board measure
FG	Flat or slash grain
FJ	Finger joint. End-jointed lumber using a finger joint configuration
FLG, Fig	Flooring
FOHC	Free of heart center
FOK	Free of knots
FT, ft	Foot or feet
FT.SM	Feet surface measure
G	Girth
GM	Grade marked
G/R	Grooved roofing
HB,H.B.	Hollow back
HEM	Hemlock
Hrt	Heart
H&M	Hit and miss
H or M	Hit or miss
IN, in.	Inch or inches
J&P	Joists and planks
JTD	Jointed
KD	Kiln-dried
LBR, Lbr	Lumber
LGR	Longer
LGTH	Length
Ltt, Lt	Lineal foot or feet
UN, Un	Lineal
LL	Longleaf
LNG, Lng	Lining
M	Thousand

(continued)

Table 3-3 *(continued)*

Abbreviation	***Meaning***
MBM, MBF, M.BM	Thousand (feet) board measure
MC, M.C.	Moisture content
MG	Medium grain or mixed grain
MLDG, Mldg	Molding
Mft	Thousand feet
MSR	Machine stress rated
N	Nosed
NBM	Net board measure
No.	Number
N1E or N2E	Nosed one or two edges
Ord	Order
PAD	Partially air dry
PART, Part	Partition
PAT, Pat	Pattern
Pcs.	Pieces
PE	Plain end
PET	Precision end trimmed
P&T	Posts and timbers
P1S,P2S	See S1S and S2S
RDM	Random
REG, Reg	Regular
Rfg.	Roofing
RGH, Rgh	Rough
R/L, RL	Random lengths
R/W,RW	Random widths
RES	Resawn
SB1S	Single bead one side
SDG, Sdg	Siding
S-DRY	Surfaced dry. Lumber 19 percent moisture content or less per American Lumber Standard for softwood
SE	Square edge
SEL, Sel	Select or select grade
SE&S	Square edge and sound
SG	Slash or flat grain

(continued)

Table 3-3 (*continued*)

Abbreviation	***Meaning***
S-GRN	Surfaced green. Lumber unseasoned, in excess of 19 percent moisture content per American Lumber Standard for softwood
SGSSND	Sapwood, gum spots and streaks, no defect
SIT. SPR	Sitka spruce
S/L,SL, S/Lap	Shiplap
STD.M	Standard matched
SM	Surface measure
Specs	Specifications
SO	Square
SORS	Squares
SR	Stress-rated
STD, Std	Standard
Std. lgths.	Standard lengths
SSND	Sap stain no defect (stained)
STK	Stock
STPG	Stepping
STR, STRUCT	Structural
SYP	Southern yellow pine
S&E	Side and edge (surfaced on)
S1E	Surfaced one edge
S2E	Surfaced two edges
S1S	Surfaced one side
S2S	Surfaced two sides
S4S	Surfaced four sides
S1S&CM	Surfaced one side and center matched
S2S&CM	Surfaced two sides and center matched
S4S&CS	Surfaced four sides and calking seam
S1S1E	Surfaced one side, one edge
S1S2E	Surfaced one side, two edges
S2S1E	Surfaced two sides, one edge
S2S&SL	Surfaced two sides and shiplapped
S2S&SM	Surfaced two sides and standard matched
t	Allowable stress in tension in pounds per square inch
TBR	Timber
T&G	Tongued and grooved

(continued)

Table 3-3 *(continued)*

Abbreviation	***Meaning***
VG	Vertical (edge) grain
V1S	See EV1S, CV1S, and E&CV1S
V2S	See EV2S, CV2S, and E&CV2S
WCH	West Coast hemlock
WDR, wdr	Wider
WHAD	Worm holes a defect
WHND	Worm holes no defect
WT	Weight
WTH	Width
WRD	Western redcedar
yp	Yellow pine

Courtesy Forest Products Laboratory

Grade B&BTR allows a few small imperfections, mainly in the form of minor skips in manufacture, small checks or stains caused by seasoning, and (depending on the species) small pitch areas, pin knots, or the like. Since appearance grades emphasize the quality of one face, the reverse side may be lower in quality. In construction, grade C&BTR is the grade combination most commonly available. It is used for high-quality interior and exterior trim, paneling, and cabinetwork, especially where these are to receive a natural finish. It is the principal grade used for flooring in homes, offices, and public buildings. In industrial uses, it meets the special requirements for large-sized, practically clear stock.

The number and size of imperfections permitted increase as the grades drop from B&BTR to D and E. Appearance grades are not uniform across species and products, however, and official grade rules must be used for detailed reference. Grade C is used for many of the same purposes as B&BTR, often where the best paint finish is desired. Grade D allows larger and more numerous surface imperfections that do not detract from the appearance of the finish when painted. Grade D is used in finish construction for many of the same uses as Grade C. It is also adaptable to industrial uses requiring short-length clear lumber.

Select Lumber

Select lumber is of good appearance and finished or dressed. See Table 3-4 for grade names, descriptions, and uses.

Table 3-4 Lumber Grades

Grade	*Description*	*Use*
Select:		
A	High quality, practically clear.	Suitable for natural finishes.
B	High quality, generally clear with a few minor defects.	Suitable for natural finishes.
C	Several minor defects.	Adapted to high-quality paint finish.
D	A few major defects.	Suitable for paint finishes.
Common:		
No. 1	Sound and tight-knotted.	Use without waste.
No. 2	Less restricted in quality than No. 1.	Framing, sheathing, structural forms where strain or stress not excessive.
No. 3	Permits some waste with defects larger than in No. 2	Footings, guardrails, rough subflooring.
No. 4	Permits waste, low quality, with decay and holes.	Sheathing, subfloors, roof boards in the cheaper types of construction.

Common Lumber

Common lumber is suitable for general construction and utility purposes and is identified by the grade names shown in Table 3-4.

Plywood

Plywood is a glued wood panel made up of relatively thin layers, or plies, with the grain of adjacent layers at an angle, usually 90° (see Figure 3-2). The usual constructions have an odd number of plies. The outside plies are called *faces* (or *face* and *back* plies), the inner plies are called *cores* (or *centers)*, and the plies immediately below the face and back are called *crossbands*. The core may be veneer, lumber, or particleboard. The plies may vary as to number, thickness, species, and grade of wood.

As compared with solid wood, the chief advantages of plywood are its having properties along the length nearly equal to properties along the width of the panel, its greater resistance to splitting, and its form, which permits many useful applications where large sheets



Figure 3-2 The multilayer construction of plywood gives large thin panels greater strength and stability than solid wood. *(Courtesy of the American Plywood Assn.)*

are desirable. Use of plywood may result in improved utilization of wood, because it covers large areas with a minimum amount of wood fiber. This is because it is permissible to use plywood thinner than sawn lumber in some applications.

The properties of plywood depend on the quality of the different layers of veneer, the order of layer placement in the panel, the glue used, and the control of gluing conditions in the gluing process. The grade of the panel depends on the quality of the veneers used, particularly of the face and back. The type of the panel depends on the glue joint, particularly its water resistance. Generally, face veneers with figured grain that are used in panels where appearance is important have numerous short, or otherwise deformed, wood fibers. These may significantly reduce strength and stiffness of the panels. On the other hand, face veneers and other plies may contain certain sizes and distributions of knots, splits, or growth characteristics that have no undesirable effects on strength properties for specific uses. Such uses include structural applications, such as sheathing for walls, roofs, or floors.

Types of Plywood

Broadly speaking, two classes of plywood are available: hardwood and softwood. In general, softwood plywood is intended for construction use and hardwood plywood for uses where appearance is important.

Originally, most softwood plywood was made of Douglas fir, but western hemlock, larch, white fir, ponderosa pine, redwood, southern pine, and other species are now used.

Most softwood plywood used in the United States is produced domestically, and U.S. manufacturers export some material. The bulk of softwood plywood is used where strength, stiffness, and construction convenience are more important than appearance. Some grades of softwood plywood are made with faces selected primarily for appearance and are used either with clear natural finishes or with pigmented finishes.

Hardwood plywood is made of many different species, both in the United States and overseas. More than half of all hardwood panels used in the United States are imported. Hardwood plywood is normally used where appearance is more important than strength. Most of the production is intended for interior or protected uses, although a very small proportion is made with glues suitable for exterior service. A significant portion of all hardwood plywood is available completely finished.

Plywood of thin, crossbanded veneers is very resistant to splitting and, therefore, nails and screws can be placed close together and close to the edges of panels.

Grades of Plywood

Plywood is graded according to defects on each surface and the type of glue used. Exterior or Interior plywood refers to the type of glue used to bond plies. Each face of the plywood has a letter grade—A, B, C, or D. Grade A means the face has no defects—it's perfect. Grade B means there are some defects (perhaps an area has a small patch). Grade C allows checks (splits) and small knotholes. Grade D allows large knotholes.

The commonly available grades are AC Interior, AD Interior, AC Exterior, and CDX, which is used for sheathing.

Particle Board

The group of materials generally classified as wood-base fiber and particle panel materials includes such familiar products as insulation boards, hardboards, particleboards, and laminated paperboards. In some instances, they are known by such proprietary names as

Masonite, Celotex, Insulite, and Beaver board or, in the instance of particleboards, by the kind of particle used, such as flakeboard, chipboard, or oriented strand board (OSB).

These panel materials are all reconstituted wood (or some other lignocellulose like bagasse) in that the wood is first reduced to small fractions and then put back together by special forms of manufacture into panels of relatively large size and moderate thickness. These board or panel materials in final form retain some of the properties of the original wood, but, because of the manufacturing methods, gain new and different properties from those of the wood. Because they are manufactured, they can be and are tailored to satisfy a use, need, or group of needs.

Speaking in general terms, the wood-base panel materials are manufactured by the following methods:

- Changing wood substance, essentially to fibers and then interfelting them together again into the panel material classed as building fiberboard.
- Strictly mechanical means of cutting or breaking wood into small discrete particles and then, with a synthetic resin adhesive or other suitable binder, bonding them together again in the presence of heat and pressure. These latter products are appropriately called *particleboards*.

Building fiberboards, then, are made essentially of fiberlike components of wood that are interfelted together in the reconstitution and are characterized by a bond produced by that interfelting. They are frequently classified as fibrous-felted board products. At certain densities under controlled conditions of hot pressing, rebonding of the lignin effects a further bond in the panel product produced. Binding agents and other materials may be added during manufacture to increase strength, increase resistance to fire, moisture, or decay, or to improve some other property. Among the materials added are rosin, alum, asphalt, paraffin, synthetic and natural resins, preservative and fire-resistant chemicals, and drying oils.

Particleboards are manufactured from small components of wood that are glued together with a thermosetting synthetic resin or equivalent binder. Wax sizing is added to all commercially produced particleboard to improve water resistance. Other additives may be introduced during manufacture to improve some property or provide added resistance to fire, insects such as termites, or decay. Particleboard is among the newest of the wood-base panel materials.

It has become a successful and economical panel product because of the availability and economy of thermosetting synthetic resins, which permit blends of wood particles and the synthetic resin to be consolidated and the resin set (cured) in a press that is heated.

Thermosetting resins used are primarily urea-formaldehyde and phenol-formaldehyde. Urea-formaldehyde is lowest in cost and is the binder used in greatest quantity for particleboard intended for interior or other nonsevere exposures. Where moderate water or heat resistance is required, melamine-urea-formaldehyde resin blends are being used. For severe exposures, such as exteriors or where some heat resistance is required, phenolics are generally used.

The kinds of wood particles used in the manufacture of particleboard range from specially cut flakes an inch or more in length (parallel to the grain of the wood) and only a few hundredths of an inch thick to fine particles approaching fibers or flour in size. The synthetic resin solids are usually between 5 and 10 percent by weight of the dry wood furnish. These resins are set by heat as the wood particle-resin blend is compressed in flat-platen presses.

As floor underlayment, particleboard provides (1) the leveling, (2) the thickness of construction required to bring the final floor to elevation, and (3) the indentation-resistant smooth surface necessary as the base for resilient finish floors of linoleum, rubber, vinyl tile, and sheet material. Particleboard for this use is produced in 4- by 8-foot panels commonly $^1/_4$, $^3/_8$, or $^5/_8$ inch thick. Separate use specifications cover particleboard floor underlayment. In addition, all manufacturers of particleboard floor underlayment provide individual application instructions and guarantees because of the importance of proper application and the interaction effects of joists, subfloor, underlayment, adhesives, and finish flooring. Particleboard underlayment is sold under a certified quality program where established grade marks clearly identify the use, quality, grade, and originating mill.

Other uses for particleboard have special requirements, as for phenol-formaldehyde, a more durable adhesive, in the board. Particleboard for siding, combined siding sheathing, and use as soffit linings and ceilings for carports, porches, and the like requires this more durable adhesive. For these uses, type 2 medium-density board is required. In addition, such agencies as the Federal Housing Administration have established requirements for particleboard for such use. The satisfactory performance of particleboard in exterior exposure depends not only on the manufacture and kind of adhesive used but also on the protection afforded by the finish. Manufacturers recognize the importance by providing both paint-primed panels and those completely finished with liquid paint systems or factory-applied plastic films.

Lumber Distribution

Large primary manufacturers and wholesale organizations set up distribution yards in lumber-consuming areas to more effectively distribute both hardwood and softwood products. Retail yards draw inventory from distribution yards and, in wood-producing areas, from local lumber producers.

Retail Yard Inventory

The small retail yards throughout the United States carry softwoods required for ordinary construction purposes and small stocks of one or two hardwoods in the grades suitable for finishing or cabinetwork. Special orders must be made for other hardwoods. Trim items such as moulding in either softwood or hardwood are available cut to size and standard pattern. Cabinets are usually made by millwork plants ready for installation. Many common styles and sizes are carried or cataloged by the modern retail yard. Hardwood flooring is available to the buyer only in standard patterns. Some retail yards may carry specialty stress grades of lumber such as structural light framing for truss rafter fabrication.

Some lumber grades and sizes serve a variety of construction needs. Some species or species groups are available at the retail level only in grade groups. Typical are house-framing grades, such as joist and plank, which is often sold as No. 2 and Better (2&BTR). The percentage of each grade in a grouping is part of the purchase agreement between the primary lumber manufacturer and the wholesaler. However, this ratio may be altered at the retail level by sorting. Where grade grouping is the practice, a requirement for a specific grade, such as No. 1, at the retail level will require sorting or special purchase. Grade grouping occurs for reasons of tradition and of efficiency in distribution.

Another important factor in retail yard inventory is that not all grades, sizes, and species described by the grade rules are produced, and not all those produced are distributed uniformly to all marketing areas. Regional consumer interest, building code requirements, and transportation costs influence distribution patterns. Often small retail yards will stock only a limited number of species and grades. Large yards, on the other hand, may cater to particular construction industry needs and carry drier dimension grades along with clears, finish, and decking. The effect of these variable retail practices is that the grades, sizes, and species outlined in the grade rules must be examined to determine what actually is available. A brief description of lumber products commonly carried by retail yards follows.

Stress-Graded Lumber for Construction

Dimension is the principal stress-graded lumber item available in a retail yard. It is primarily framing lumber for joists, rafters, and studs. Strength, stiffness, and uniformity of size are essential requirements. Dimension is stocked in all yards, frequently in only one or two of the general-purpose construction woods (such as pine, fir, hemlock, or spruce):

- The 2 × 6, 2 × 8, and 2 × 10 dimensions are found in grades of Select Structural, No. 1, No. 2, and No. 3. They may also be found in combinations of No. 2 & BTR or possibly No. 3 & BTR.
- The 2 × 4 grades available would normally be Construction and Standard. They are sold as Standard and Better (STD&BTR), Utility and Better (UTIL&BTR), or Stud, in lengths of 10 feet and shorter.

Dimensional lumber is often found in nominal 2-, 4-, 6-, 8-, 10-, or 12-inch widths and 8- to 18-foot lengths in multiples of 2 feet. Dimensional lumber that is formed by structural end-jointing procedures may be found. Dimensional lumber thicker than 2 inches and longer than 18 feet is not available in large quantity.

Other stress-graded products generally present are posts and timbers, with some beams and stringers also possibly in stock. Typical stress grades in these products are Select Structural and No. 1 Structural in Douglas fir and No. 1SR and No. 2SR in southern pine.

Nonstress-Graded Lumber for Construction

Boards are the most common nonstress-graded general-purpose construction lumber in the retail yard. Boards are stocked in one or more species, usually in nominal 1-inch thickness. Standard nominal widths are 2, 3, 4, 6, 8, 10, and 12 inches. Grades most generally available in retail yards are No. 1, No. 2, and No. 3 (or Construction, Standard, and Utility). These will often be combined in grade groups. Boards are sold square-ended, dressed and matched (tongued and grooved), or with a ship-lapped joint. Boards formed by end jointing of shorter sections may form an appreciable portion of the inventory.

Appearance Lumber

Completion of a construction project usually depends on a variety of lumber items available in finished or semifinished form. The following items often may be stocked in only a few species, in only a few finishes, or in limited sizes depending on the yards:

- *Finish*—Finish boards usually are available in a local yard in one or two species, principally in grade C&BTR. Redwood and cedar have different grade designations. Grades such as Clear Heart, A, or B are used in cedar; Clear All Heart, Clear, and Select are typical redwood grades. Finish boards are usually a nominal 1-inch thick, dressed two sides to $^3/_4$ inch. The widths usually stocked are nominal 2 to 12 inches in even-numbered inches.
- *Siding*—Siding, as the name implies, is intended specifically to cover exterior walls. Beveled siding is ordinarily stocked only in white pine, ponderosa pine, western red cedar, cypress, or redwood. *Drop siding* (also known as *rustic siding* or *barn siding*) is usually stocked in the same species as beveled siding. Siding may be stocked as B&BTR or C&BTR, except in cedar (where Clear, A, and B may be available) and redwood (where Clear All Heart and Clear will be found). Vertical grain (VG) is sometimes a part of the grade designation. Drop siding sometimes is stocked also in sound knotted C and D grades of southern pine, Douglas fir, and hemlock. Drop siding may be dressed, matched, or ship lapped.
- *Flooring*—Flooring is made chiefly from hardwoods such as oak and maple, and the harder softwood species, such as Douglas fir, western larch, and southern pine. Often, at least one softwood and one hardwood are stocked. Flooring is usually nominal 1-inch thick dressed to $^{25}/_{32}$ inch, and 3- and 4-inch nominal width. Thicker flooring is available for heavy-duty floors in hardwoods and softwoods. Thinner flooring is available in hardwoods, especially for recovering old floors. Vertical and flat grain (also called quartersawed and plain-sawed) flooring is manufactured from both softwoods and hardwoods. Vertical-grained flooring shrinks and swells less than flat-grained flooring, is more uniform in texture, wears more uniformly, and the joints do not open as much.

  Softwood flooring is usually available in B and Better grade, C Select, or D Select. The chief grades in maple are Clear

No. 1 and No. 2. The grades in quartersawed oak are Clear and Select, and in plain-sawed, Clear, Select, and No. 1 Common. Quartersawed hardwood flooring has the same advantages as vertical-grained softwood flooring. In addition, the silver or flaked grain of quartersawed flooring is frequently preferred to the figure of plain-sawed flooring. Beech, birch, and walnut and mahogany (for fancy parquet flooring) are also occasionally used.

- *Casing and Base*—Casing and base are standard items in the more important softwoods and are stocked by most yards in at least one species. The chief grade, B and Better, is designed to meet the requirements of interior trim for dwellings. Many casing and base patterns are dressed to $^{11}/_{16} \times 2^1/_4$. Other sizes used include $^9/_{16} \times 3$, $3^1/_4$, and $3^1/_2$. Hardwoods for the same purposes (such as oak and birch) may be carried in stock in the retail yard or may be obtained on special order.
- *Shingles and Shakes*—Shingles usually available are sawn from western red cedar, northern white cedar, and redwood. The shingle grades are: Western red cedar, No. 1, No. 2, No. 3; northern white cedar, Extra, Clear, 2nd Clear, Clear Wall, Utility; redwood, No. 1, No. 2 VG, and No. 2 MG.

  Shingles that are all heartwood give greater resistance to decay than do shingles that contain sapwood. *Edge-grained shingles* are less likely to warp than *flat-grained shingles*; *thick-butted shingles* less likely than *thin shingles*; and *narrow shingles* less likely than *wide shingles*. The standard thicknesses of shingles are described as $^4/_2$, $^5/_2$, $^1/_4$, and $^5/_2$ (four shingles to 2 inches of butt thickness, five shingles to $2^1/_4$ inches of butt thickness, and five shingles to 2 inches of butt thickness). Lengths may be 16, 18, or 24 inches. Random widths and specified widths (dimension shingles) are available in western red cedar, redwood, and cypress.

  Shingles are usually packed four bundles to the square. A square of shingles will cover 100 square feet of roof area when the shingles are applied at standard weather exposures.

  Shakes are handsplit, or handsplit and resawn from western red cedar. Shakes are of a single grade and must be 100 percent clear, graded from the split face in the case of handsplit and resawn material. Handsplit shakes are graded from the best face. Shakes must be 100 percent heartwood free of bark and sapwood. The standard thickness of shakes ranges from

$^3/_8$ to $1^1/_4$ inches. Lengths are 18 and 24 inches, and a 15-inch Starter-Finish Course length.

Important Purchase Considerations

The following are some of the points to consider when ordering lumber or timbers:

- *Quantity*—Feet, board measure, number of pieces of definite size and length. Consider that the board measure depends on the thickness and width nomenclature used and that the interpretation of this must be clearly delineated. In other words, nominal or actual, pattern size, and so forth must be considered.
- *Size*—Thickness in inches—nominal and actual if surfaced on faces. Width in inches—nominal and actual if surfaced on edges. Length in feet—may be nominal average length, limiting length, or a single uniform length. Often a trade designation, random length, is used to denote a nonspecified assortment of lengths. Note that such an assortment should contain critical lengths as well as a range. The limits allowed in making the assortment random can be established at the time of purchase.
- *Grade*—As indicated in grading rules of lumber manufacturing associations, some grade combinations (B&BTR) are official grades; other (STD&BTR light framing, for example) are grade combinations and subject to purchase agreement. A typical assortment is 75 percent Construction and 25 percent Standard, sold under the label STD&BTR. In softwood, each piece of such lumber typically is stamped with its grade, a name or number identifying the producing mill, the dryness at the time of surfacing, and a symbol identifying the inspection agency supervising the grading inspection. The grade designation stamped on a piece indicates the quality at the time the piece was graded. Subsequent exposure to unfavorable storage conditions, improper drying, or careless handling may cause the material to fall below its original grade.

  Note that working or rerunning a graded product to a pattern may result in changing or invalidating the original grade. The purchase specification should be clear regarding regrading or acceptance of worked lumber. In softwood lumber, grades for dry lumber generally are determined after kiln drying and surfacing. This practice is not general for hardwood factory lumber, however, where the grade is generally based on grade and size prior to kiln drying.

- *Species or groupings of wood*—Douglas fir, cypress, hemlock, fir. Some species have been grouped for marketing convenience. Others are traded under a variety of names. Be sure the species or species group is correct and clearly depicted on the purchase specification.
- *Product*—Flooring, siding, timbers, boards, and so forth. Nomenclature varies by species, region, and grading association. To be certain the nomenclature is correct for the product, refer to the grading rule by number and paragraph.
- *Condition of seasoning*—Air dry, kiln dry, and so on. Softwood lumber dried to 19 percent moisture content or less (S-DRY) is defined as dry by the American Lumber Standard. Other degrees of dryness are partially air-dried (PAD), green (S-GRN), and 15 percent maximum (KD in southern pine). There are several specified levels of moisture content for redwood. If the moisture requirement is critical, the levels and determination of moisture content must be specified.
- *Surfacing and working*—Rough (unplaned), dressed (surfaced), or patterned stock. Specify condition. If surfaced, indicate S4S, S1S1E, and so on. If patterned, list pattern number with reference to the appropriate grade rules.
- *Grading Rules*—Official grading agency name, product identification, paragraph number or page number or both, date of rules or official rule volume (rule No. 16, for example).
- *Manufacturer*—Most lumber products are sold without reference to a specific manufacturer. If proprietary names or quality features of a manufacturer are required, this must be stipulated clearly on the purchase agreement.

Engineered Lumber

Some lumber has been engineered to produce a variety of improvements for use in construction of homes and office and industrial buildings. There is glued laminated lumber that is called glulam. This engineered lumber is composed of wood laminations (lams). They are bonded together with adhesives. The grain of the lams runs parallel to the length of the glulam member. Lams are $1^3/_8$ inches thick for southern pine species and $1^1/_2$ inches for western wood species. Laminated boards up to 2 inches thick may also be used to form glulam timbers. Glulam widths are standardized at

$3^1/_8$ inches, $3^1/_2$ inches, $5^1/_8$ inches, $5^1/_2$ inches, and $6^3/_4$ inches. However, almost any width can be custom made.

Glulam dates back to the early 1900s when the first patents for glulam were obtained in Switzerland and Germany. One of the first glulam structures in the United States was built for the USDA Forest Products Laboratories in 1934. Glulam manufacture has evolved to make glulam one of the most widely used engineered lumber products in the construction industry. In the past, glulam was mainly associated with heavy timber construction, such as industrial roofing systems, bridges, and marine piers. Glulam timbers are used in residential construction as well as in commercial industrial construction.

Summary

Lumber is the basic construction material used in construction. Wood is a highly variable product so lumber is standardized by sizes and grades. The three classes of grading are stress-graded, nonstress-graded, and appearance. Plywood is made up of layers of wood veneer in wide long panels that have several advantages over solid wood lumber. Particleboard is made of small chunks of wood compressed into a large panel. Understanding lumber and wood product distribution and inventories leads to more successful and economic construction projects.

Review Questions

1. Why is lumber standardized by size and grade?
2. What grades are used for structural light framing?
3. What grade of lumber would you use for kitchen cabinet construction?
4. What are the advantages of plywood over solid lumber?
5. What grades and species of select softwood lumber are available at your local retail lumberyard?

Chapter 4

Strength of Timbers

The various mechanical properties of woods have been investigated by exhaustive testing in many laboratories, most notably the Forest Products Laboratory of the U.S. Department of Agriculture in Madison, Wisconsin. In addition, much research has been done in civil and agricultural engineering laboratories at many state universities.

Tension

A tension test is made as indicated in Figure 4-1. Although modern testing machines are by no means as simple as the apparatus shown, it serves well to show how such tests are made. The specimen is placed in the machine, gripped at each end, and the load is progressively increased until the material reaches its failure point. Usually, the elongation is not of any significance unless it is desired to determine the modulus of elasticity. The allowable fiber stresses indicated by modern stress grading (such as 1200f or 1450f) apply equally to extreme fiber stress in bending and to tensile stresses.



Figure 4-1 The tension test. The specimen R is placed in the wedge grips a, b, c, and d, thus applying tension between the fixed end and the movable head of the machine. The movable head is connected to the scale lever G on which the weight W slides. This arrangement is similar to an ordinary weighing scale. Two center marks (L and F) are punched on the specimen at a standard distance (A) apart. When testing, the pull on the specimen is gradually increased by moving W to the left. Dimensions A and B are then measured after each load increase.

Example A truss member is subjected to a tensile force of 50,000 pounds. What size timber of No. 1 dense yellow pine (1600f grade) will be required?

This is the calculation:

$$\frac{5000}{1600} = 31.25 \text{ square inches cross section}$$

Therefore, either a standard-dressed 4 inches × 10 inches ($3^1/_2$ inches × $9^1/_4$ inches) or a 6 inches × 6 inches ($5^1/_2$ inches × $5^1/_2$ inches) should be adequate.

Compression

A column supporting a load that tends to crush it is said to be in *compression*. Allowable compression parallel to the grain in stress-graded lumber is usually slightly less than the allowable bending and tensile stresses. For No. 1 dense timbers, 1600f grade, the compression stress is 1500 pounds per square inch, and for No. 2 dense, 1200f grade, it is 900 pounds per square inch. The builder need have no other concern than to see that the specified stresses are not exceeded. For loads applied across the grain, these stresses are much less. For the two grades mentioned, the cross-grain stress is 455 pounds per square inch for both grades.

When making a compression test (see Figure 4-2), a prepared specimen is placed between two plates, and a measured load is



Figure 4-2 The compression test. The specimen R is placed between two plates (M and S), and a compression stress of any desired intensity is applied by moving the weight W on the lever G. As the load is gradually increased, the changes in dimensions A and B are noted, and a final result can be obtained that will indicate the amount of compression that the specimen can withstand.

applied. The load is increased progressively until the failure point is reached. Actually, modern wood-compression testing is not quite so simple. An instrument called a *compressometer* is pinned to the side of the specimen with sharp-pointed screws at points corresponding to points L and F in Figure 4-2. It is fitted with a series of levers that are connected to a dial gauge, usually reading to .0001 inch. The stem of the dial gauge is depressed until it shows a positive reading and compression in the specimen releases a part of the gauge. In this way, a sudden failure will release the gauge entirely, and jamming and ruining of the instrument is avoided. Usually, at least one of the plates through which pressure is applied is a cast iron hemisphere, thereby ensuring an evenly distributed pressure over the entire cross-section of the specimen.

Working Stresses for Columns

The amount of allowable loads on wood columns has been (and continues to be) a subject that is open to some discussion. The matter is complicated by the fact that columns of different lengths and diameters do not behave in the same manner under loadings. For the rather short column, failure will be caused by the actual crushing of the fibers of the wood, and the full compressive strength of the wood may thus be utilized. For a slightly longer column, failure may be caused by a sort of diagonal shearing action. For a long column, it will probably fail by bending sidewise and breaking. No one method can be adapted exactly for calculating allowable loads on columns of all lengths and slenderness ratios.

Column formulas are numerous. Some are based on empirical data or the results of actual testing. Only one, the *Euler* (pronounced *oiler*) *formula* seems to be based on purely mathematical calculations. It is of German origin, and, in its original form, it is so cumbersome that few designers in the U.S. care to use it. It assumes that a column will fail by *bending and breaking*. This is ensured only if the column is long and comparatively slender. However, a *modified* Euler formula is greatly favored by present-day timber designers. It is written as follows:

$$\text{Allowable load per square inch of cross section} = \frac{.3E}{(l/d)^2}$$

where the following is true:

E = modulus of elasticity of the timber used
l = unsupported length of the column (in inches)
d = least side, or diameter of a round column

This formula is applicable only when the results of its use do not indicate a higher stress than the maximum allowable unit stresses (as defined by the stress grade of the timber used). The ratio *l/d* in this equation is sometimes called the *slenderness ratio*. As an example of the use of this formula, consider the following problem.

How much of a load may safely be imposed on a 6-inch × 6-inch dressed yellow pine column that is 12 feet long?

The slenderness ratio, or *l/d*, of 6-inch × 6-inch columns 12 feet long is $^{144}/_{6} = 24$, and the modulus of elasticity of almost all good yellow pine is 1,760,000 pounds per square inch. This is the calculation:

$$\frac{0.3 \times 1{,}760{,}000}{24 \times 24} = 917 \text{ pounds per square inch}$$

The cross-sectional area of standard 6-inch × 6-inch timbers is 30.25 square inches. Therefore, the total load allowable on the column will then be:

$$917 \times 30.25 = 27{,}739 \text{ pounds}$$

An important point with respect to timber in compression is that the ends should be cut exactly square so that there will be a full bearing surface. Otherwise the timber will be subjected at the ends to more than the working stress (see Figure 4-3).

Shearing Stresses

Shearing stresses in wood are dangerous only in the direction parallel to the grain. It is almost impossible to shear the material across the grain until the specimen has been *crushed*. The crushing strength, then, and not the shearing resistance of the wood, will govern the maximum stress that can be applied to the wood.

The standard shearing test for woods with the grain was developed by the American Society for Testing Materials (ASTM), and the procedure is standardized. The specimens are standard dimensions, shaped as shown in Figure 4-4 in pairs, one with the notch at right angles to that in the other. The results of the tests on the two specimens are averaged, but usually they vary only slightly. The blocks are tested in a special shear tool that is loaded in a universal testing machine, with the load applied at a rate of .024 inch per minute.

The results of testing different types of woods vary widely. To provide for this lack of uniformity, the shear allowances in stress-rated timbers may contain a reduction factor (safety factor) of as much as


LOAD
FULL BEARING SURFACE
LOAD
M
S
L
PORTION OF BEARING SURFACE TAKING THE LOAD
PORTION OF BEARING SURFACE NOT IN CONTACT WITH LOAD
(A)
(B)

Figure 4-3 **(A) Good and (B) poor column bearing surfaces illustrate the importance of squaring columns accurately when cutting them. The entire top of the column must be in contact with the load member so that the pressure per square inch of cross section on the column will correspond to the allowable working pressure for which the column was designed. If the portion MS of the bearing surface in contact is only half the entire surface, then the stress applied on the top of the column will be twice that of full contact, as shown by (A).**


3/4 IN.
2 IN.
1/2 IN.
2 1/2 IN.
2 IN.

Figure 4-4 **The ASTM standard wood-shear test specimens.**

10, or it may be as little as 2 or 3. This is necessary because a piece that is below average in shearing resistance may appear anywhere.

The distinctions *across the grain* and *with the grain* should be carefully noted. Wet or green wood, in general, shears approximately one-fifth to one-half as easily as dry wood. A surface parallel to the rings (tangent) shears more easily than one parallel to the medullary rays. The lighter conifers and hardwoods offer less resistance than the heavier kinds, but the best pine shears one-third to one-half more readily than oak or hickory, thereby indicating that great shearing strength is characteristic of tough woods.

Horizontal Shears

The types of shears discussed in the preceding section are called *external* shears because they are caused by forces that originate outside the body of the material, and for the most part, they are evident and readily provided for (see Figure 4-5). In addition, in every loaded beam, a system of *internal* stresses is set up. This may be explained by observing that every shearing force results from *two* forces that are *unbalanced*. They do not meet at the same point, and a *stress couple* is set up that can be met and held motionless only by another couple that acts in opposition to it.

This is illustrated in Figure 4-6. It represents a particle of indefinite size, but possibly infinitely small, that has been extracted from the body of a beam that has been stressed by bending. In Figure 4-6A, the particle has been subjected to a vertical shearing force, or pair of forces, since there can be no action without an opposing and equal reaction. The particle is *unstable*. Since the two forces do not meet at a common point, the particle tends to revolve in a counterclockwise direction.

In Figure 4-6B, a pair of horizontal forces is supplied. These forces represent another stress couple that balances or neutralizes the vertical shearing forces. They are known as the *internal horizontal shears*. A reasonable deduction, therefore, is that at any point on the beam, there exist internal horizontal shears equal in intensity to the external vertical shears. The horizontal shears are dangerous in wood beams. That is because timbers have a low resistance to shearing with the grain.

Figure 4-6C shows how the four forces may be resolved into a single pair of concurrent forces that *do* meet at a common point. These are not shearing forces. They are, however, the result of shearing forces. When the material has approximately the same resistance to shears in all directions (such as concrete or steel), this is what occurs. Each particle tends to elongate in one diagonal



Figure 4-5 Examples of single and double shear. (A) The nails are in single shear. This is the assumption made as a rule when calculating the strength of nailed joints. However, nails may be placed in double shear, similar to the bolts in (B), if they are long enough to almost penetrate all three members. The nails in double shear will safely carry twice the load that could safely be placed on nails in single shear. However, most nailed joints are designed as if the nails were in single shear, though they may actually be in double shear. In (B), the bolts are truly in double shear, but the joint is not twice as strong as a plain lapped joint if the center member is not at least as thick as the combined thicknesses of the outer members. The outer members are usually both the same thickness.

and forms the diagonal tension that is so dangerous in reinforced concrete beams. In fact, it is the most dangerous stress in such beams, and to resist it, elaborate web reinforcing and bent-up bars are provided at points where this stress is highest (usually near the ends of the beams). In I-beams, diagonal tension results in buckling or wrinkling of the relatively thin webs. In wood beams, the forces are not resolved in this way, since wood is strong enough to resist the vertical components, but the horizontal components tend to split the beam (usually at or near the ends near the center of the height). Wood beams that are season-checked at the ends (as many are) are low in resistance to such stresses.



Figure 4-6 The actions of vertical and horizontal shears.

If the depth of a wood beam is greater than one-tenth to one-twelfth of its span, horizontal shears (and not bending strength) often govern its ability to carry loads. Shears are usually not dangerous in wood beams unless they are relatively deep and heavily loaded.

Transverse or Bending Stress

This is the kind of stress present on numerous building timbers (such as girders, joists, or rafters) that causes a deflection or bending between the points of support. What takes place when these or similar members are subjected to bending stress is discussed in the section titled *Beams* later in this chapter.

Stiffness

By definition, stiffness is that quality possessed by a beam or other timber to resist the action of a bending force. The action of the bending force tends to change a beam from a straight to a curved form (that is, a *deflection* takes place). When a load is applied, the beam (originally assumed straight and horizontal) sags or bends downward between the supports. The amount of downward movement measured at a point midway between the supports is the amount of deflection. The action of beams subjected to bending forces is described as follows.

If a load of 100 pounds placed in the middle of a stick that is 2 inches × 2 inches and 4 feet long, supported at both ends, bends or deflects this stick one-eighth of an inch (in the middle), then 200 pounds will bend it about 1/4 inch, 300 pounds, 3/8 inch, and so on, the deflection varying directly as the load. This is in accordance with Hooke's Law that states that stress is proportional to strain. Soon, however, a point is reached where an additional 100 pounds adds more than 1/8 inch to the deflection—the limit of elasticity has been exceeded.

Taking another piece from the straight-grained and perfectly clear plank of the same depth and width but 8 feet long, the load of 100 pounds will deflect it by approximately 1 inch. Doubling the length reduces the stiffness eightfold. Stiffness, then, decreases as the cube of the length.

If AB in Figure 4-7 is a piece of wood, and D is the deflection produced by a weight or load, then



Figure 4-7 A simple beam, loaded at the middle and supported at both ends, is used to illustrate the term deflection.

$$\text{deflection } (D) = \frac{Pl^3}{48EI}$$

where the following is true:

P = the load, concentrated at the center of the span (in pounds)

l = the length of the span (in feet)

E = the modulus of elasticity of the material

I = the moment of inertia (for rectangular beams =

$$\frac{bd^3}{12}$$

where b = width and d = height).



Figure 4-8 A beam supported at the ends. The ends of the beam are free to follow any deflection, thus offering no resistance and rendering the beam less stiff than when the ends are fixed.

The following rules (in conjunction with Figure 4-8, Figure 4-9, and Figure 4-10) define the stiffness and strength of practically all types of wood beams:

- For beams with a rectangular cross-section, equal depths, and equal spans, their load-carrying capacity varies *directly* as their widths.
- For beams with equal widths and equal spans, their strength varies directly as the square of their depth.



Figure 4-9 A beam supported at the ends. The ends are gripped or embedded in some unyielding substance so that they cannot turn or follow the deflection of the beam under an applied load. The beam then deflects in a compound curve, thus adding extensively to its stiffness. Therefore, a beam with fixed ends will deflect less than one with supported ends.


DOWNWARD THRUST
OF FIXED SUPPORT
L
TANGENT
DEFLECTION FIXED ENDS
L'
COMPOUND
CURVE
F'
STIFFENING
COUPLE
F
UPWARD THRUST
OF FIXED SUPPORT
DEFLECTION
SUPPORTED ENDS

Figure 4-10 One end of a beam illustrating the stiffening effect of fixed ends as compared with supported ends. When the ends are fixed, the deflection of the beam will be resisted by an upward thrust, indicated by F, and a downward thrust, L. These thrusts form a resisting or stiffening couple that holds the portion of the beam embedded in the bearing in a horizontal position, thereby causing the beam to deflect in a compound curve, which increases its stiffness. The dotted lines show the excess deflection for the same load if the beam were simply supported at the ends.

- If depths and widths are the same, strengths vary *inversely* as the lengths of the spans.
- Their stiffness, or resistance to deflection, will vary *inversely* as the *cubes* of their spans, other factors being equal.
- Their stiffness will vary directly as the *cubes* of their depths, other factors being equal.
- Other factors being equal, stiffness will vary *directly* as their widths.
- If a beam is split horizontally, and the two halves are laid side by side, they will carry only *one-half* as much loading as the original beam.

These relations are not strictly true for I-beams because of their irregular shapes, but they are approximately true for all types of beams. It is usually most economical with materials to use as deep a beam as can conveniently be employed. Note that double 2-inch × 4-inch trimmers over window or door heads, if set edge up, are 8 times as strong and 32 times as stiff as when placed flatwise.

Both strength and stiffness are greater in dry timber than in green or wet wood of the same species. A piece of long-leaf yellow pine is 30 percent to 50 percent stronger, and 30 percent stiffer, when in an air-dry condition than when green. In general, both strength and stiffness are proportional to densities, or dry weights, although this is not always true. Edge-grain pieces are usually stronger and stiffer because the tangent to the rings runs horizontally, but not appreciably so. There is little or no difference in the sapwood and heartwood of the same species if the densities are the same. The tool handle of red heartwood is as serviceable as the handle of white sapwood, although white sapwood handles are still called premium grade.

Modulus of Elasticity

Since it is desirable (and, for many purposes, essential) to know beforehand that a given piece with a given load will bend only by a given amount, the stiffness of wood is usually stated in a uniform manner under the term *modulus* (measure) *of elasticity*. For good grades of Douglas fir and yellow pine that are stress-rated, the modulus of elasticity is 1,760,000 pounds per square inch.

Beams

A beam is a single structural member (usually horizontal or nearly so) that carries a load or loads over a given space. At their supports, beams may be:

- *Freely supported*—This merely means the beams are resting on their bearings.
- *Restrained, or partially fixed at their bearings*—Although some designers choose to consider such restraint in their designs, the actual degree of restraint can never be accurately determined, so restrained beams are more often considered as being freely supported.
- *Fixed at their supports*—In wood beams, this condition is rarely found. In steel frames, it is not unknown. In reinforced concrete frames, it is quite common. Attempts to fix the ends of wood beams are rarely permanent. Building the ends of a beam, *any* beam, into a wall or casting it into concrete for a short distance does not fix the beams at their supports.

Allowable Loads on Wood Beams

The allowable loads on freely supported wood beams of any species are readily calculated if the timbers are stress-rated and the allowable fiber-stress is known. For a beam with a loading that is evenly distributed along its span, this is the equation to use:

$$W = \frac{f \times b \times d^2}{9 \times L}$$

where the following is true:

W = allowable evenly distributed loading, in pounds
f = allowable fiber stress in pounds per square inch
b = width of the beam, in inches
d = depth of the beam, in inches
L = length of the span, in feet

Figure 4-11 defines the dimensions of a beam—b, width; d, depth; and L, length.



Figure 4-11 A beam resting on knife-edge supports illustrates the terms length, width, and depth.

Example What will be the maximum allowable load on a beam whose nominal size is 6 inches × 12 inches and whose actual size is $5^1/_2$ inches × $11^1/_2$ inches, with an 18-foot span? The timber is to be 1500f stress-rated. This is the calculation:

$$\frac{1500 \times 5.5 \times 11.5 \times 11.5}{9 \times 18} = 6735 \text{ pounds}$$

If the loading is to be concentrated at the center of the span, use one-half the load as calculated by the formula given. Therefore, for the same timber as calculated, with the same span, the allowable concentrated load will be

$$\frac{6735}{2} = 3367 \text{ pounds}$$

Breaking Loads on Wood Beams

Breaking loads are of no interest to the builder because the term is meaningless unless some explanation is made, since wood is extremely sensitive to the *duration* of loads. The load that would break a beam over a long period of time, for example, 10 years, will be only approximately $^{9}/_{16}$ of the load that would break it in a few minutes. The stresses specified in stress-rating lumber and timbers recognize this phenomenon. It is presumed that the full design loading will not be applied for more than 10 years during the life of the structure, and the time may be either cumulatively intermittent or continuous. It is also presumed that 90 percent of the full design loading may safely be applied for the full life of the structure. These presumptions make the use of stress-rated lumber quite conservative.

Example What is the safe working load, concentrated at the center of the span, for a full-size 6-inch × 10-inch white oak timber with a 12-foot span, stress-rated 1900f, if it is laid flatwise (see Figure 4-12A)? If it is set edge up (see Figure 4-12B)?

This is the calculation for the timber laid flatwise:

$$\frac{1900 \times 10 \times 6 \times 6}{9 \times 12} = 6333$$

$$\frac{6333}{2} = 3167 \text{ pounds}$$

For the timber set edge up:

$$\frac{1900 \times 6 \times 10 \times 10}{9 \times 12} = 10{,}555$$

$$\frac{10{,}555}{2} = 5278 \text{ pounds}$$

Distributed Load

Instead of placing the load in the middle of a beam, as in the example just given, the load may be regarded as being *distributed* (that is, the beam is uniformly loaded, as shown in Figure 4-13). Although this type of loading is actually a series of concentrated loads, it is often found in actual practice, and it is usually considered as being *uniformly* distributed.

Cantilever Beams

A *cantilever beam* (see Figure 4-14 and Figure 4-15) is firmly fixed at one end, or it is freely supported but with the end running some distance to a support above it. The loading may be either



Figure 4-12 The terms width and depth of a beam depend on the position of the beam. In (A) the broad side is the width of the beam, whereas in (B), which is the same beam turned over 90°, the narrow side is the width.



Figure 4-13 A distributed load is indicated by the iron balls equally spaced along the beam between the supports.

distributed or concentrated at any point on the span. All beams that project beyond a support and that carry a load at the free end are classed as cantilevers. Stresses set up in the beam external to the outside support are the same as when the beam is rigidly fixed at the support.

Figure 4-16 illustrates the comparison between the working loads of variously supported beams, contrasting middle and distributed


L
FREE END
FIXED END
CANTILEVER
d
b
P
LOADED
AT END

Figure 4-14 A simple cantilever beam that is fixed at one end and free at the other; this beam is supporting a concentrated load at its free end.


L
CANTILEVER
DISTRIBUTED LOAD

Figure 4-15 A cantilever beam with an equally distributed load.

loads of beams supported at both ends with equal loads on cantilever beams. In Figure 4-16, P= the concentrated loads, W= the evenly distributed load, f= the fiber stress, b= the width of the beam, d= the depth of the beam, and L= the length of the span.

Wind Loads on Roofs

Snow on roofs (if the roofs are of a slope that is low enough to permit the snow to lie in place) will weigh approximately 8 pounds per square foot per foot of depth when freshly fallen. When wet, its


WORKING LOADS
SUPPORTED AT ENDS LOADED AT MIDDLE
$P = \frac{fbd^2}{18L}$
SUPPORTED AT ENDS DISTRIBUTED LOAD
$W = \frac{fbd^2}{9L}$
FIXED AT ENDS LOADED AT MIDDLE
$P = \frac{fbd^2}{9L}$
FIXED AT ENDS DISTRIBUTED LOAD
$W = \frac{fbd^2}{6L}$
CANTILEVER LOADED AT END
$P = \frac{fbd^2}{72L}$
CANTILEVER DISTRIBUTED LOAD
$W = \frac{fbd^2}{36L}$

Figure 4-16 The working loads for beams with different types of loads and different modes of support.

weight will vary with the water content. A commonly used figure is 10 pounds per cubic foot. In calculating snow load, use the depth of the heaviest snow on record multiplied by 10, but never less than 20 pounds per square foot anywhere. If a roof is designed for much less than 20 pounds per square foot of live load, it will not safely support workers.

In the past, there was considerable confusion regarding wind loads against sloping roofs, and some rather weird formulas were evolved to calculate their imaginary intensities (although no one had ever seen a roof blow *in*, and many persons have seen roofs blow *off*). In other words, wind loads are *negative* (that is, they create *suction*). This is now well recognized, and insurance companies are well informed on the subject.

In regions where hurricanes are not common, the insurance companies recommend that an uplift allowance of 30 pounds per square foot be provided for, acting at right angles to the slope of the roof. This will include the slight *positive* pressure commonly found inside buildings during windstorms. If eaves are wide and overhanging, it is recommended that a gross lifting force of 45 pounds per square foot be provided for. If the weight of the roof itself is appreciable, it may be deducted from the gross uplift allowance.

It should be recognized that a maximum snow load plus a maximum wind load could hardly occur at the same time. Thus, it cannot be considered compensating.

Definitions

In the shop and in the field, the fitness of any species of wood for a given purpose depends on various properties. When treating the strength, stiffness, hardness, and other properties of wood, many technical terms are used. For an understanding of these terms, the following definitions are worth noting:

- *Bending forces*—Forces that act on some members of a structural frame. They tend to deform them by flexure.
- *Brittleness*—Breaking easily and suddenly, usually with a comparatively smooth fracture. The opposite of *toughness* (sometimes incorrectly called *brashness*) that refers more to brittleness. Old and extremely dry wood is inclined to brashness. Green or wet wood is tougher, though not as strong in most cases.
- *Compression*—The effect of forces that tend to reduce or shorten the dimensions of a member.
- *Deformation*—A change of shape or dimension. Disfigurement, such as the elongation of a structural member under tension.

- *Ductile*—A term not applicable to wood. It is the property of a metal that allows it to be hammered thin or drawn into wires.
- *Elastic limit*—The greatest stress that a substance can withstand and still recover completely when the force or strain is removed.
- *Factor of safety*—The ratio between the stress at failure and allowable design stress. If the stress at failure in a bending beam is 4350 pounds per square inch (psi), and the timber is stress-graded at 1450f (allowable fiber stress in psi) the safety factor is $^{4350}/_{1450}$, or 3.
- *Force*—In common parlance, a *pull* or a *push* that would change the state of a body at rest, or would change the course of a body in motion (Newton's Law).
- *Load*—Pressure acting on a surface, usually caused by the action of gravity.
- *Member*—A part of a structure (such as a column, beam, or brace) that usually is subjected to compression, tension, shear, or bending.
- *Modulus, or coefficient, of elasticity*—Stress, tension, or compression, divided by the elongation or contraction per unit of length. Inside the elastic limit, the modulus of elasticity is approximately constant for most materials. In wood, it varies greatly with different species, with moisture content, and even in pieces sawed from the same log. In other words, it is subject to considerable natural variation.
- *Modulus of rupture*—The calculated fixed stress in a beam at the point of rupture. Since the elastic limit will have been passed at this point, it is not a true fiber stress, but it is a definite quantity, and the personal factor is not involved when obtaining it.
- *Permanent set*—When a member (either metal or wood) is stressed beyond its elastic limit, or subjected to stresses that may be far below its elastic limit for extremely long periods, it may take on permanent deformation. Permanent set in timbers does not mean or imply that the timbers have been weakened.
- *Resilience*—Synonym for *elasticity*. The property that enables a substance to spring back when a deforming force is removed.
- *Shear*—The effect of forces (external or internal) that causes bodies or parts of bodies to slide past each other.

- *Strain*—Alterations in the form of a member caused by forces acting on the member.
- *Strength*—The power to resist forces (which may be tensile, compressive, or shearing) without breaking or yielding.
- *Stress*—Distributed forces, such as pounds per square inch or tons per square foot. Within the elastic limit of materials, *stress* is approximately proportional to *strain*. This statement is called Hooke's Law.
- *Tenacity*—Synonym for *tensile strength*. The power to resist tearing apart.
- *Tension*—A force that tends to tear a body apart or elongate it.
- *Toughness*—Strong but flexible. Not brittle. Nearly the same as *tenacity*.
- *Ultimate strength*—The stress developed just before failure is evident.
- *Yield point*—This property is not evident in timbers. In steels, it occurs after the elastic limit has been passed. In materials that show no defined yield point, it may be arbitrarily assumed or defined as the stress where a permanent set occurs.

As an example of the uses for these terms, the tie rod in a truss resists being pulled apart because of its *tensile strength*. The *stress* thus applied *strains* the rod, *deforming* or *elongating* it. It is *stretched* and a *contraction* of the area of its cross-section results. If the *load* is not sufficient to *stress* the material past its *elastic limit*, the rod will return to its original length when the load is removed, depending on the duration of the load. If the *load* is heavy enough to stretch the rod past its *elastic limit*, it will not return to its original length when the *load* is removed, but it will remain *permanently set* if it is not pulled in two. The *elastic limit* is reached when *elongation* becomes proportionally greater than the *loading*. If the *load* is increased to the point where the rod breaks, or where its *tenacity* is overcome, it is *ruptured*. The rod itself is called a *member* of the truss.

Summary

In most shop work and in the field, the fitness of any species of wood for a given purpose depends on various properties. When treating the strength, stiffness, hardness, and other properties of wood, many factors must be considered. Stiffness is that quality possessed by a beam or other timber to resist the action of a bending force.

A beam is a single structural member (usually horizontal) that carries a load over a given space. The allowable loads on freely supported wood beams of any size can be calculated if the timber is stress-rated and the allowable fiber-stress is known. In many designs, the load is distributed uniformly over the length of the beam. Although this type of loading is actually a series of concentrated loads, it is often found in actual practice and is usually considered as being uniformly distributed.

Review Questions

1. What is meant by brittleness, bending forces, compression, and elastic limit?
2. What is meant by working stresses?
3. Explain shearing stresses.
4. Why is it important in some cases to distribute the load on a beam between the supports?
5. What is a cantilever beam? Explain its purpose.
6. What is a truss?
7. Where is compression experienced in construction?
8. When are shearing stresses in wood dangerous?
9. What are external shears?
10. What type of tension is so dangerous in reinforced concrete beams?

Chapter 5

Mathematics for Carpenters and Builders

An elementary knowledge of mathematics is essential to the carpenter to solve successfully the numerous problems encountered in almost any branch of carpentry. The branches of mathematics of which the carpenter should possess at least an elementary knowledge are the following:

- Arithmetic
- Geometry
- Trigonometry

Such knowledge will be found very useful, especially in making up estimates, solving steel square problems, and so forth.

Arithmetic

By definition *arithmetic* is the science of numbers and the art of reaching results by their use (see Figure 5-1).

Arithmetic Alphabet

In arithmetic figures are used to represent quantities or magnitudes, as follows:

Cipher	*one*	*two*	*three*	*four*	*five*	*six*	*seven*	*eight*	*nine*
0	1	2	3	4	5	6	7	8	9

A number is one or a collection of these figures to represent a definite quantity or magnitude as 1, 21, 517, 43,988, and so forth.

There are various kinds of numbers: simple, compound, integer, abstract, concrete, odd, even, prime, composite, and so forth.

Notation and Numeration

By definition, *notation* in arithmetic is *the writing down of figures to express a number,* and numeration is *the reading of the number or collection of figures already written*. By means of the ten figures given above any number can be expressed.

Figures have two values: simple and local. The *simple value* of a figure is its value when standing in units' place. The *local value* of a figure is the value that arises from its location.

<table>
<tr><td colspan="8"><i>Notation</i>
Basis—1—unit
Arithmetic Alphabet
0 1 2 3 4 5 6 7 8 9</td></tr>
<tr><td colspan="3"><i>Increased</i>
<i>By tens</i>
1, 10, 100, 1000, etc.
By varying scales</td><td colspan="5"><i>Diminished</i>
<i>By tens</i>
1, .1, .01, .001, etc.
By varying scales</td></tr>
<tr><td>1 oz</td><td>1 lb</td><td>1 cwt</td><td>${}^{1}/_{4}$</td><td>${}^{6}/_{7}$</td><td>${}^{1}/_{3}$ oz</td><td colspan="2">${}^{11}/_{23}$ etc.</td></tr>
<tr><td>1 pt</td><td>1 qt</td><td>1 gal</td><td>${}^{1}/_{6}$ lb</td><td>${}^{9}/_{8}$ oz</td><td></td><td colspan="2">${}^{3}/_{8}$ cwt</td></tr>
<tr><td>1 in.</td><td>1 ft</td><td>1 yd</td><td colspan="5">etc.</td></tr>
<tr><td colspan="8"><i>According to the Four Ground Rules</i></td></tr>
<tr><td colspan="3">Addition
Subtraction</td><td colspan="5">Multiplication
Division</td></tr>
<tr><td colspan="3">By involution (powers)</td><td colspan="5">By evolution (roots)</td></tr>
<tr><td colspan="8"><i>Relations Expressed by</i></td></tr>
<tr><td colspan="8">Ratios 2 : 3   5 : 6   8 : 9 etc.
Proportion (equality of ratios) 2 : 3 : : 4 : 6 etc.</td></tr>
<tr><td colspan="8"><i>Practical Applications</i>
Percentage, interest, profit and loss, reduction of weights and measures, measuring, etc.</td></tr>
</table>

Figure 5-1 Scheme of arithmetic.

When one of the figures stands by itself, it is called a *unit*. If two of them stand together, the right-hand one is still called a unit, and the left-hand one is called *tens*. Thus, 79 is a collection of 9 units and 7 sets of ten units each, or of 9 units and 70 units, or of 79 units and is read as "seventy-nine."

If three of them stand together, then the left-hand one is called *hundreds*. Thus 279 is read "two hundred seventy-nine."

To express larger numbers other orders of units are formed. The figure in the fourth place denotes *thousands*, and in the fifth place denotes *ten thousands*. These are called *units of the fifth order*. The sixth place denotes hundred thousands, the seventh place denotes millions, and so forth.

The French method (which is the same as that used in the United States) of writing and reading large numbers is shown in Figure 5-2. This system is called Arabic notation and is the system in ordinary everyday use.

Names of periods	Billions	Millions	Thousands	Units		Thousandths
Order of Units	Hundred-billions Ten-billions Billions	Hundred-millions Ten-millions Millions	Hundred-thousands Ten-thousands Thousands	Hundreds Tens Units	Decimal point	Tenths Hundredths Thousandths
	8 7 6,	5 4 3,	2 0 1,	2 8 2,	•	4 8 9

Figure 5-2 Numeration.

Roman Notation

This system is occasionally used for chapter headings, corner stones, and so forth. The method of expressing numbers is by letters, as shown in Table 5-1.

In the Roman notation, when any character is placed at the right-hand side of a larger numeral, its value is added to that of such numeral: VI is V + I; XV is X + V; MD, is M + D; and so on. I, X, and rarely C are also placed at the left-hand side of other and larger numerals, and when so situated, their value is subtracted from such numerals: IV is V − I; XC is C − X; and so on. Formerly, the smaller figure was sometimes repeated in such a position twice, with its value being in such cases subtracted from the larger: IIX is X − II; XXC is C − XX; and so on. The custom of using the Roman notation for chapter numbers, year of copyright, sections, and so forth continues!

Definitions

Following are some important definitions worth noting:

- *Arithmetic*—The art of calculating by using numbers.
- *Number*—A total, amount, or aggregate of units. By counting the units, we arrive at a certain number (such as *two* horses or *five* dozen).
- *Unit*—May mean a single article, but often it means a definite group adopted as a standard of measurement (such as *dozen, ton, foot, bushel*, or *mile)*. Most commonly used units are standardized and are defined and fixed by law.

Table 5-1 Roman Numeral Values

Roman Numeral	*Value*
I	1
II	2
III	3
IV	4
V	5
VI	6
VII	7
VIII	8
IX	9
X	10
XI	11
XII	12
XIII	13
XIV	14
XV	15
XVI	16
XVII	17
XVIII	18
XIX	19
XX	20
XXX	30
XL	40
L	50
LX	60
LXX	70
LXXX	80
XC	90
C	100
D	500
M	1000
$\overline{\text{X}}$	10,000
$\overline{\text{M}}$	1 million

- *Concrete number*—A number applied to some particular unit (such as *ten* nails, *two* dozen eggs, *six* miles).
- *Abstract number*—One that is *not* applied to any object or group (such as simply *two, four, ten)*.
- *Notation*—The art of expressing numbers by figures or letters. Our system of notation is the Arabic notation. The Roman notation uses letters (such as V for 5, X for 10).
- *Cardinal numbers*—Numbers used in simple counting or in reply to the question "How many?" Any number may be a cardinal number.
- *Ordinal numbers*—Indicate succession or order of arrangement (such as *first, second, tenth)*.
- *Integer*, or *integral number*—A whole number, not a fraction or part.
- *Even number*—Any number that can be exactly divided by 2 (such as 4, 16, 96, 102).
- *Odd number*—Any number that is *not* exactly divisible by 2 (such as 3, 15, 49, 103).
- *Factor of a number*—A whole number that may be exactly divided into the number. For example, 3 is a factor of 27, 13 is a factor of 91.
- *Prime number*—A number that has no factors other than itself and 1. Thus, 3, 5, 7, and 23 are prime numbers.
- *Composite number*—A number that has factors other than itself and 1 (such as 8, 49, and 100).
- *Multiple of a number*—A number that is exactly divisible by a given number. For example, 91 is a multiple of 7, 12 is a multiple of 3.
- *Digit*—Any number from 1 to 9, and usually 0.

Signs of Operation

Following are some important signs of operation worth noting:

- The *sign of addition* is +, and it is read "plus" or "add." Thus, 7 + 3 is read "seven plus three." The numbers may be taken in *any order* when adding (7 + 3 is the same as 3 + 7).
- The *sign of subtraction* is –, and it is read "minus." A series of subtractions *must* be taken in the order written (11 – 7 is *not* the same as 7 – 11).

- The *sign of multiplication* is ×, and it is read “times” or “multiplied by.” The numbers may be taken in *any order* when multiplying (4 × 7 is the same as 7 × 4).
- The sign of division is ÷, and it is read “divided by.” A series of divisions *must* be taken in the order written (100 ÷ 2) ÷ 10 = 5.
- The *sign of equality* is =, and it is read “equals” or “is equal to.” The expressions on each side of an equality sign must be numerically the same. The complete expression is called an *equation*.

Use of the Signs of Operation

Following are some examples of the use of mathematical signs of operation.

Example *Use of the sign of addition.* A builder when building a house buys 1762 board feet of lumber from one yard, 2176 board feet from another, and 276 board feet from another. How many board feet did he buy?

The problem:

$$1762 + 2176 + 276 = ?$$

The solution:

$$\begin{array}{r} 1762 \\ 2176 \\ +\ 276 \\ \hline 4214 \end{array} \text{ board feet}$$

Note how the numbers are aligned to permit addition. The units are all aligned on the right, then the tens, then the hundreds, then the thousands, each in the proper column.

Example *Use of the sign of subtraction.* A carpenter bought 300 pounds of nails for a job, and he had 28 pounds left when he finished. How many pounds of nails did he use to complete the job?

The problem:

$$300 - 28 = ?$$

The solution:

$$\begin{array}{r} 300 \\ -\ 28 \\ \hline 272 \end{array} \text{ pounds}$$

Note that the numbers must be aligned as they were for addition.

Example *Use of the sign of division.* A carpenter's pickup truck gets an average of 17 miles per gallon of gasoline. How many gallons of gasoline would be required for him to travel 2040 miles in his truck?

The problem:

$$2040 \div 17 = ?$$

The solution:

$$
\begin{array}{r@{\,}l}
 & 120 \\
17 & \big)\overline{2040} \\
 & \underline{17} \\
 & 34 \\
 & \underline{34} \\
 & 00
\end{array}
$$

Example *Use of the sign of equality.* A road contractor finds that he can lay the same amount of paving in 12 days using a 6-man crew that he can lay in 8 days using a 9-man crew. Express this statement as an equation.

$$12 \times 6 = 9 \times 8 \text{ or } 72 = 72$$

Fractions

A fraction indicates that a number or a unit has been divided into a certain number of equal parts, and shows how many of these parts are to be considered. Two forms of fractions are in common usage: the *decimal* (which is expressed in the tenths system) and the *common fraction*. The common fraction is written by using two numbers, one written over or alongside the other with a line between them. The lower (or second) number, called the *denominator*, indicates the number of parts into which the unit has been divided, and the upper (or first) number, called the *numerator*, indicates the number of parts to be considered. In the fraction $^{2}/_{3}$, the denominator shows that the unit is divided into 3 parts, whereas the numerator indicates that 2 parts are being considered (see Figure 5-3).

If the quantity indicated by the fraction is less than 1 (such as $^{1}/_{2}$, $^{3}/_{4}$, or $^{5}/_{6}$), it is called a *proper fraction*. If the quantity indicated by the fraction is equal to or greater than 1 (such as $^{3}/_{3}$, $^{5}/_{4}$, or $^{7}/_{6}$), it is called an *improper fraction*. When a whole number and a proper fraction are combined (such as $2^{1}/_{4}$, $6^{1}/_{2}$), it is called a *mixed number*.

Addition of Fractions

Fractions cannot be added without first reducing them to a common denominator.



Figure 5-3 Graphic representations of fractional parts. The figures show a rectangle ABCD, representing a unit divided into two equal parts or halves and into three equal parts or thirds. The shaded section M (or one half) is larger than the shaded section S (or one third).

Example Add $^3/_4 + {}^2/_9 + {}^2/_3 + {}^7/_{12}$

To find the common denominator, place the denominators in a row, separated by dashes. Divide them by a prime number that will divide into at least two of them without leaving a remainder, and bring down the denominators with the dividends that did not contain the divisor without a remainder. Repeat this process as often as possible until there are no two numbers remaining that can be divided by the same number. Then, multiply the divisors and the remainders together, and the result will be the smallest common denominator.

The solution:

$$\begin{array}{ll} 2\ ) & \underline{4-9-3-12} \\ 3\ ) & \underline{2-9-3-6} \\ 2\ ) & \underline{2-3-1-2} \\ & 1-3-1-1 \end{array}$$

The common denominator will then be $2 \times 3 \times 2 \times 3 = 36$. The fractions are then reduced to the common denominator of 36 by multiplying the numerator and the denominator by the same number that will produce 36 in the denominator, as follows:

$$^3/_4 = {^3/_4} \times {^9/_9} = {^{27}/_{36}}$$

$$^2/_9 = {^2/_9} \times {^4/_4} = {^8/_{36}}$$

$$^2/_3 = {^2/_3} \times {^{12}/_{12}} = {^{24}/_{36}}$$

$$^7/_{12} = {^7/_{12}} \times {^3/_3} = {^{21}/_{36}}$$

The sum of the fractions is as follows:

$$\frac{27 + 8 + 24 + 21}{36} = {^{80}/_{36}} \text{ or } {^{20}/_9}$$

Multiplication of Common Fractions

A fraction may be multiplied by a whole number by multiplying the numerator of the fraction by that number.

Example If $^3/_4$ of a keg of nails is used for siding a garage, how many kegs of nails will be used when siding eight similar garages?

The solution:

$$8 \times {^3/_4} = {^{24}/_4}$$

A fraction may be simplified by dividing both the numerator and the denominator by the same number, and its value will not be affected.

Example Divide both the numerator and the denominator of the improper fraction $^{24}/_4$ by 4.

The result will be $^6/_1$ or 6. Therefore, six kegs of nails will be required to put the siding on the eight garages.

Fractions may be multiplied by fractions by multiplying their numerators together and their denominators together.

Example Multiply

$$^2/_5 \times {^1/_4} \times {^5/_{12}} = \frac{2 \times 1 \times 5}{5 \times 4 \times 12} = \frac{10}{240} = \frac{1}{24}$$

Multiplication of Fractions by Cancellation

This may readily be done because any factor below the line may be divided by any factor above the line, and any factor above the line may be divided by any factor below the line, without altering the overall value of the expression.

Example The problem:

$$^{12}/_{30} \times {^{14}/_{56}} \times {^{10}/_{24}}$$

Now write it in this form:

$$\frac{\overset{1}{\cancel{12}} \times \overset{1}{\cancel{14}} \times \overset{1}{\cancel{10}}}{\underset{3}{\cancel{30}} \times \underset{4}{\cancel{56}} \times \underset{2}{\cancel{24}}}$$

The 30 below the line may be divided by the 10 above the line with the result of 3. The 56 below the line may be divided by the 14 above the line with the result of 4. The 24 below the line may be divided by the 12 above the line with the result of 2. The result of the cancellation, then, is as follows:

$$\frac{1}{3 \times 4 \times 2} = \frac{1}{24}$$

Division of Fractions

Fractions may be divided by whole numbers by dividing the numerator by that number or by multiplying the denominator by that number.

Example

$$\frac{7}{8} \div 7 = \frac{1}{8}$$

$$\frac{7}{8} \div 7 = \frac{7}{56} = \frac{1}{8}$$

Fractions may be divided by fractions by inverting the divisor and multiplying.

Example

$$\frac{7}{8} \div \frac{2}{7} = \frac{7}{8} \times \frac{7}{2} = \frac{49}{16}$$

which is the mixed number $3^1/_{16}$.

Subtraction of Fractions

Fractions cannot be subtracted from fractions without first reducing them to a common denominator, as is done for the addition of fractions.

Example The problem:

$$^5/_6 - {}^{13}/_{16}$$

Finding the least common denominator,

$$\begin{array}{r|l} 2 & 16 - 6 \\ \hline & 8 - 3 \end{array} \qquad 2 \times 8 \times 3 = 48$$

$$\frac{13}{16} = \frac{13}{16} \times \frac{3}{3} = \frac{39}{48}$$

$$\frac{5}{6} = \frac{5}{6} \times \frac{8}{8} = \frac{40}{48}$$

$$\frac{40 - 39}{48} = \frac{1}{48}$$

To subtract a mixed number from another mixed number, it is usually most convenient to reduce both numbers to improper fractions and then proceed as shown in the last example.

To subtract a mixed number from a whole number, borrow 1 from the *minuend* (or upper number), and reduce the 1 to an improper denominator of the fraction in the *subtrahend* (or lower number), thereby reducing the whole number by 1. Then make the subtraction in the normal manner.

Example The problem:

$$14 - 6\,^{7}/_{8}$$

The solution:

$$14 - 6\,^{7}/_{8} = 13\,^{8}/_{8} - 6\,^{7}/_{8} = 7\,^{1}/_{8}$$

Applications of Cancellation

There are countless applications where this method will save appreciable time and work, but care and thought must be given to the proper arrangement of the fractional expression if there are many factors. Also, it must be remembered that if addition or subtraction signs appear, cancellation *may not* be used.

Example A circular saw has 75 teeth with a 1-inch spacing between each tooth. To do satisfactory work, the rim of the saw should travel at approximately 9000 feet per minute. How many revolutions should this saw make per minute? (Hint: 75 inches = $^{75}/_{12}$ feet.) The solution:

$$\frac{\overset{120}{9\cancel{0}\cancel{0}\cancel{0}} \times 12}{\cancel{7}\cancel{5}} = 120 \times 12 = 1440 \text{ rpm}$$

Example If you go to a bank and borrow \$1000 to purchase a truck, how much will the interest be, at 6 percent per annum (a theoretical example only), on the money you borrow for 1 year and 3 months? (Hint: 1 year 3 months = 15 months.)

The solution:

$$\frac{\cancel{6} \times \overset{\overset{5}{1\cancel{0}}}{1\cancel{0}\cancel{0}\cancel{0}} \times 15}{1\cancel{0}\cancel{0} \times \underset{\cancel{2}}{1\cancel{2}}} = 5 \times 15 = \$75$$

Example If eight men in fifteen 8-hour days can throw 1000 cubic yards of gravel into wheelbarrows, how many men will be required to throw 2000 cubic yards of gravel into wheelbarrows in 20 days of 6 hours each?
The solution:

$$\frac{\overset{\cancel{3}}{\cancel{15}} \times \overset{2}{\cancel{8}} \times \overset{4}{\cancel{8}} \times \overset{2}{\cancel{2000}}}{\underset{\cancel{4}}{\cancel{20}} \times \underset{\cancel{2}}{\cancel{6}} \times \cancel{1000}} = 2 \times 4 \times 2 = 16 \text{ men}$$

Example A building that is 30 feet × 30 feet with a 10-foot ceiling contains approximately 700 pounds of air. What will be the weight of the air in a room 120 feet long, 90 feet wide, and 16 feet high?
The solution:

$$\frac{\overset{4}{\cancel{120}} \times \overset{3}{\cancel{90}} \times 16 \times \overset{70}{7\cancel{0}\cancel{0}}}{\cancel{30} \times \cancel{30} \times \cancel{10}} = 4 \times 3 \times 16 \times 70 = 13{,}440 \text{ pounds}$$

Decimals

Decimal means numbering that proceeds by *tens*, and *decimal fractions* (usually simply called *decimals*) are formed when a unit is divided into ten parts. When decimals are written, the point where the numbers start is called the *decimal point*. To the left of the decimal point, the numbers read in the regular manner—units, tens, hundreds, thousands, ten thousands, hundred thousands, millions, and so forth. To the right of the decimal point, the figures are fractional, reading, from the point, tenths, hundredths, thousandths, ten thousandths, hundred thousandths, millionths, and so forth. (see Figure 5-4).

The common fraction $^{6}/_{10}$ can be expressed decimally as .6, and the fraction $^{105}/_{1000}$ can be written as .105. The mixed number $106\,^{6}/_{100}$ may be expressed decimally as 106.06. The decimal .6 is read "six-tenths," the same as the common fraction $^{6}/_{10}$, and the decimal 106.06 is read "one hundred six *and* six-hundredths," the same as the mixed number.


1
2
3
4
5
6
7
8
9
10
L
A
F
R
(A)
FIRST ORDER OR "TENTHS"(.1)
L
A
SECOND ORDER
OR "HUNDREDTHS"
(.01)
F
R
(B)
l
a
THIRD ORDER OR
"THOUSANDTHS"
(.001)
f
r
(C)

Figure 5-4 Graphic representation of decimal fractions. (A) A unit divided into ten parts—1st order or tens. (B) One of the tens as LARF, divided into ten parts—2nd order or hundredths. (C) One of the hundredths as larf, divided into ten parts—3rd order or thousandths. Similarly the process of division may be continued indefinitely.

It is not necessary to place a zero before the decimal point, as 0.06, but it is sometimes convenient when it is necessary to align a column of decimals for addition. The decimal points must *always* be aligned for addition, as shown in the following example:

$$\begin{array}{r} 0.6 \\ 6.29 \\ +10.72 \\ \hline 17.61 \end{array}$$

The position of the decimal point in the sum is established directly under the column of decimal points above the line.

Note

The number 327 is *not* read "three hundred *and* twenty-seven," but "three hundred twenty-seven." However, the decimal 300.27 is read "three hundred *and* twenty-seven hundredths." The decimal .327 is read "three hundred twenty-seven thousandths," whereas the decimal 300.027 is read "three hundred *and* twenty-seven thousandths."

Reduction of Common Fractions to Decimals

Divide the numerator by the denominator, adding zeros and carrying the division to as many decimal places as are necessary or desirable (see Figure 5-5).

Example Reduce the common fraction $^{21}/_{32}$ to a decimal.

$$
\begin{array}{r}
0.65625\\
32\,\overline{)\,21.00000}\\
\underline{192}\\
180\\
\underline{160}\\
200\\
\underline{192}\\
80\\
\underline{64}\\
160\\
\underline{160}\\
00
\end{array}
$$

Count off as many decimal places in the quotient as those in the dividend *exceed* those in the divisor. The quotient is .65625.

Subtraction of Decimals

Align the decimal points in the minuend and the subtrahend as shown for addition, and proceed as explained in subtraction of whole numbers. The decimal point in the remainder is placed in exact alignment with those decimal points above the line.

Example The problem:

$$167.02 - 27.267$$

The solution:

$$
\begin{array}{r}
167.020\\
\underline{-\ 27.267}\\
139.753
\end{array}
$$

Note that it is necessary to add a zero to the decimal 167.02 in order to make the subtraction, but this does not change its value ($^{20}/_{1000}$ is the same value as $^{2}/_{100}$).

					1/64	.015625
				1/32		.03125
					3/64	.046875
			1/16			.0625
					5/64	.078125
				3/32		.09375
					7/64	.109375
		1/8				.125
					9/64	.140625
				5/32		.15625
					11/64	.171875
			3/16			.1875
					13/64	.203125
				7/32		.21875
					15/64	.234875
	1/4					.250
					17/64	.265625
				9/32		.28125
					19/64	.296875
			5/16			.3125
					21/64	.328125
				11/32		.34375
					23/64	.359375
		3/8				.375
					25/64	.390625
				13/32		.40625
					27/64	.421875
			7/16			.4375
					29/64	.453125
				15/32		.46875
					31/64	.484375
1/2						.500
					33/64	.515625
				17/32		.53125
					35/64	.546875
			9/16			.5625
					37/64	.578125
				19/32		.59375
					39/64	.609375
		5/8				.625
					41/64	.640625
				21/32		.65625
					43/64	.671875
			11/16			.6875
					45/64	.703125
				23/32		.71875
					47/64	.734375
	3/4					.750
					49/64	.765625
				25/32		.78125
					51/64	.796875
			13/16			.8125
					53/64	.828375
				27/32		.84375
					55/64	.859375
		7/8				.875
					57/64	.890625
				29/32		.90625
					59/64	.921875
			15/16			.9375
					61/64	.953125
				31/32		.96875
					63/64	.984375
						1.0000

Figure 5-5 Fractions of an inch and decimal equivalents.

Multiplication of Decimals

Proceed as in multiplication of whole numbers, and count off as many decimal places in the product as there are in *both* the multiplier and multiplicand.

Example The problem:

$$1.76 \times 0.06$$

The solution:

$$\begin{array}{r} 1.76 \\ \times\ 0.06 \\ \hline 0.1056 \end{array}$$

Compound Numbers

A compound number expresses units of two or more denominations of the same kind, such as 5 yards, 1 foot, and 4 inches. The process of changing the denomination in which a quantity is expressed without changing its value is called *reduction*. Thus, 1 yard and 2 inches = 38 inches, 25 inches = 2 feet and 1 inch, and so forth, are examples of reduction. Reduction problems occur and are explained with the various measures and weights.

Reduction Descending

To reduce a compound number to a lower denomination, multiply the largest units in the given number by the number of units in the next lower denomination, and add to the product the units of that denomination in the given number. Continue this process until the original number is reduced as far as desired. For an explanation of this rule, see the following example.

Example The problem: Reduce the quantity 6 yards, 2 feet, 7 inches to inches.

The solution:

$$\begin{array}{lrl} & 6 & \text{yards} \\ \text{Multiply.........} & \underline{\times 3} & \\ & 18 & \text{feet} \\ \text{Add..............} & \underline{+\ 2} & \\ & 20 & \text{feet} \\ \text{Multiply.......} & \underline{\times 12} & \\ & 240 & \text{inches} \\ \text{Add..............} & \underline{+\ 7} & \\ \text{Total....................} & 247 & \text{inches} \end{array}$$

Reduction Ascending

To reduce a number of small units to units of larger denominations, divide the number by the number of units in a unit of the next higher denomination. The quotient is in the higher denomination and the remainder, if any, is in the lower. Continue this process until the number is reduced as far as is desired.

Example The problem: Reduce 378 inches to a quantity of yards, feet, and inches.

The solution:

12) 378
3)31 feet, 6 inches remainder
10 yards, 1 foot remainder

Therefore, 378 inches = 10 yards, 1 foot, 6 inches.

Ratios

By definition, a *ratio* is the relation of one number to another as obtained by dividing the first number by the second. Thus, the ratio of 2 to 4 is expressed as 2 : 4. The symbol : is read "to" in the case of a ratio and "is to" in the case of a proportion. It is equivalent to "divided by." Hence:

$$2 : 4 = {}^1/_2$$

The first term of a ratio is the *antecedent*, and the second term is the *consequent*, thus:

$$\overset{\text{antecedent}}{2} \quad : \quad \overset{\text{consequent}}{4}$$

Since a ratio is essentially a fraction, it follows that if both terms are multiplied or divided by the same number, the value of the ratio is not altered. Thus:

$$2 : 4 = 2 \times 2 : 4 \times 2 = 2 \div 2 : 4 \div 2$$

Two quantities of different kinds cannot form the terms of a ratio. Thus, no ratio can exist between $5 and 1 day, but a ratio can exist between $5 and $2 or between 1 day and 10 days.

Proportion

When two ratios are equal, the four terms form a *proportion*. A proportion is, therefore, expressed by using the sign = or : : between two ratios. Thus:

(expressed) 4 : 8 :: 2 : 4

(read) 4 is to 8 as 2 is to 4

The same proportion is also expressed as follows:

$$^4/_8 = {}^2/_4$$

The first and last terms of a proportion are called the *extremes*, and the middle terms are called the *means*. Thus:

$$4 : 8 :: 2 : 4$$

The product of the extremes equals the product of the means. Thus, in proportion

$$4 : 8 = 2 : 4$$

$$4 \times 4 = 8 \times 2$$

Since the equation is not altered by dividing both sides by the same number, the value of any term can be obtained as follows:

$$\frac{4 \times 4}{4} = \frac{8 \times 2}{4}$$

$$4 = 2 \times 2 = 4$$

Rule of Three

When three terms of a proportion are given, the method of finding the fourth term is called the rule of three.

Example The problem: If 5 bundles of shingles cost $100, what will 25 bundles cost?

The solution: Let X represent the unknown term in the proportion, and, remembering that each ratio must be made up of like quantities:

$$5 \text{ bundles} : 25 \text{ bundles} = 100\ (\$) : X\ (\$)$$

Multiply the extremes by the means:

$$5 \times X = 25 \times 100$$

$$X = \frac{25 \times 100}{5} = \$500$$

Percentage

By definition, *percentage* means the rate per 100, or the proportion in 100 parts. Therefore $^1/_{100}$ of a number is called 1 percent, $^2/_{100}$ is 2 percent, and so forth. The symbol % is read as “percent.” Thus 1%, 2%, and so forth. Carefully note the following explanation with respect to the symbol %. The notation 5% means $^5/_{100}$, which, when reduced to a decimal (as is necessary when making a calculation), becomes .05, but .05% means $^{.05}/_{100}$, which, when reduced to a decimal, becomes .0005 (that is, $^{5}/_{100}$ of 1%).

If the decimal has more than two places, the figures that follow the hundredths place signify parts of 1%.

Example The problem: If the list price of shingles is \$90 per 1000, what is the net cost for 1000 shingles with a 5 percent discount for cash?

The solution: Reduce % rate to a decimal.

$$5\% = {}^{5}/_{100} = .05$$

Multiply decimal by list price.

$$\$90 \times .05 = \$4.50$$

Subtract product obtained from list price.

$$\$90 - \$4.50 = \$85.50$$

Powers of Numbers (Involution)

The word *involution* means the multiplication of a quantity by itself any number of times, and a *power* is the product arising from this multiplication. Involution, then, is the process of raising a number to a given power. The *square* of a number is its second power, the *cube* is its third power, and so forth. Thus:

$$\text{square of } 2 = 2 \times 2 = 4$$

$$\text{cube of } 2 = 2 \times 2 \times 2 = 8$$

The power to which a number is raised is indicated by a small superior figure called an *exponent*. Thus, in Figure 5-6, the exponent indicates the number of times the number, or root, has been multiplied by itself.



Figure 5-6 The root, exponent, and power of a number.

Roots of Numbers (Evolution)

The word *evolution* means the operation of extracting a root. The root is a factor that is repeated to produce a power. Thus, in the equation $2 \times 2 \times 2 = 8$, 2 is the root from which the power 8 is produced. This number is indicated by the symbol $\surd$, called the *radical sign*, which, when placed over a number, means that the root of that number is to be extracted. Thus:

$\sqrt{4}$ *means that the square root of 4 is to be extracted*

The *index* of the root is a small figure that is placed over the radical sign that denotes what root is to be taken. Thus, $\sqrt[3]{9}$ indicates the cube root of 9 and $\sqrt[4]{16}$ indicates the extraction of the fourth root of 16. When there is no index given, the radical sign alone always means the *square root* is to be extracted from the number under the radical sign.

Sometimes the number under the radical sign is to be raised to a power before extracting the root, as follows:

$$\sqrt[3]{4^3} = \sqrt[3]{4 \times 4 \times 4} = \sqrt[3]{64}$$

Example The problem: Extract the square root of 186,624.

The solution:

$$\begin{array}{rll} & \sqrt{18'66'24} & \quad 432 \\ & \;16 & \\ 83 & \sqrt{266} & \\ & \;\;249 & \\ 862 & \sqrt{1724} & \\ & \;\;\underline{1724} & \end{array}$$

From the decimal point, count off the given number into periods of two places each. Begin with the last period counted off (18). The largest square that can be divided into 18 is 4. Put this down in the quotient, and put the square (16) under the 18. Write down the remainder (2), and bring down the next period (66). Multiply 4 (in the quotient) by 2 for the first number of the next divisor; 8 goes into 26 three times. Place 3 after 4 in the quotient and also after 8 in the divisor. Multiply the 83 by 3, placing the product 249 under 266, and subtract, obtaining the remainder 17. Bring down the last period (24), and proceed as before, obtaining 432 as the square root of 186,624.

Extracting the cube root of a number is a more complicated (though similar) process, as indicated by the following procedure:

1. Separate the number into groups of three figures each, beginning at the decimal point.

2. Find the greatest cube that can be divided into the left-hand group, and write its root for the first figure of the required root.
3. Cube this root, subtract the result from the left-hand group, and annex the next group to the remainder for a dividend.
4. For a partial divisor, take three times the square of the root already found, considered as hundreds, and divide the dividend by it. The quotient (or the *quotient diminished*) will be (or be close to) the second figure of the root.
5. To this *partial divisor*, add three times the product of the first figure of the root, considered as tens, by the second figure, and to this add the square of the second figure. This sum will be the *complete divisor*.
6. Multiply the complete divisor by the second figure of the root, subtract the product from the dividend, and annex the next group to the remainder for a new dividend.
7. Proceed in this manner until all the groups have been annexed. The result will be the cube root required, as shown in the following example.

Example The problem: Extract the cube root of the number 50,653.

The solution:

$$\begin{array}{rl}
 & \sqrt[3]{50'653.}\ \ (\underline{\ 37} \\
 & \underline{27} \\
2700 & 23\,653 \\
630 & \underline{23\,653} \\
\underline{49} & \\
3379 &
\end{array}$$

Therefore, the cube root of 50,653 is 37.

Measures

To *measure* is the act or process of determining the extent, quantity, degree, capacity, dimension, volume, and so forth, of a substance by comparing it with some fixed standard, which is usually fixed by law. A measure may relate to any of these standards. There are many kinds of measures, and practically all of them are standard, but standards vary in different countries. The measures mentioned in this text are all U.S. standards unless designated otherwise. The study of measurements is sometimes called *mensuration*.

Among the many kinds of measures are the following:

- *Linear*—Measures of length
- *Square*—Used to measure areas
- *Cubic*—Used to measure volume, or volumetric contents
- *Weight*—Many systems of weights are standard
- *Time*—Almost standardized all over the world
- *Circular* or *angular*—The same all over the world

Linear Measure

Table 5-2 shows linear measurement (long) equivalents.

Table 5-2 Long Measure

Measure	*Equivalent*	*Equivalent*
12 inches	1 foot	
3 feet	1 yard	36 inches
$5^1/_2$ yards	1 rod	$16^1/_2$ feet
40 rods	1 furlong	660 feet
8 furlongs	1 mile	5280 feet
3 miles	1 league (land)	

The furlong is practically never used, except at racetracks and in some athletic events.

Table 5-3 shows land survey measurement equivalents.

Table 5-3 Land Surveyor's Measure

Measure	*Equivalent*	*Equivalent*
7.92 inches	1 link	
100 links	1 chain	66 feet
10 chains	1 furlong	660 feet
80 chains	1 mile	5280 feet

The use of the surveyor's chain, or Gunter's chain, was abandoned in the late 1800s and was superseded by the steel tape, which is much more accurate. The chain (meaning 66 feet) is still used by the U.S. General Land Office, however, when surveying very old deeds. The standard surveyor's tape is often called, from habit, a *chain*. It is

100 feet long and is graduated in feet except for the last foot, which is divided into tenths and hundredths of a foot.

Table 5-4 shows nautical measurement equivalents.

Table 5-4 Nautical Measure (U.S. Navy)

Measure	*Equivalent*
6 feet	1 fathom
120 fathoms	1 cable length
The International Nautical Mile*	6076.1033 feet
3 nautical miles	1 marine league

*Adopted in 1954.

The knot is a measure of speed, not of length, and is equivalent to 1 nautical mile per hour. A speed of 16 knots is equal to 16 nautical miles per hour.

Square Measure

Square measure is used to measure areas. In most (but not all) cases, linear units are used to measure the two dimensions, length and width, and their product is the area in square units. Expressed as an equation:

$$\text{length} \times \text{width} = \text{area}$$

The two dimensions, length and width, must be measured in the same units, but any unit of linear measurement may be used. If inches are multiplied by inches, the result will be in square inches; if feet are multiplied by feet, the result will be in square feet, and so forth (see Figure 5-7).

For the small areas commonly found in everyday life (such as tabletops or shelves), the unit most commonly used is the square inch. Plywood and lumber are commonly sold by the square foot. Carpets and other floor coverings and materials and ceilings are measured in square yards. The carpenter measures roofing by the square of 10 × 10 feet, or 100 square feet. Tracts of land are usually measured in acres or, for large areas, in square miles.

Table 5-5 shows square measure equivalents.

Cubic Measure

Cubic measure is used to determine or appraise volumes. Three dimensions are involved (length, width, and height) and their product is volume. Expressed as an equation:

$$\text{length} \times \text{width} \times \text{height} = \text{volume}$$



Figure 5-7 Square measure. If the rectangle ABCD measures 2 inches on one side and 3 inches on the other, and lines are drawn at each inch division, then each of the small squares will have an area of 1 square inch and the area of the rectangle will be area ABCD = breadth × length = 2 × 3 = 6 square inches.

Table 5-5 Square Measure

Measure	*Equivalent*	*Equivalent*
144 square inches	1 square foot	
9 square feet	1 square yard	
$30^1/_4$ square yards	1 square rod	272.25 square feet
160 square rods	1 acre	4840 square yards or 43,560 square feet
640 acres	1 square mile	3,097,600 square yards
36 square miles	1 township	

As with square measure, the usual linear units (inches, feet, and yards) are ordinarily used to measure these three dimensions. Most small measurements of capacity (such as small shipping cases or small cabinets) are measured in cubic inches. The contents of buildings, their cubage, are ordinarily expressed in cubic feet. Earthwork (either excavated and loose, or in place) is expressed in cubic yards (see Figure 5-8).



Figure 5-8 Cubic measure. If each side of the cube measures 3 feet and it is cut as indicated by the lines, each little cube as M, will have each of its sides 1 foot long and will contain 1 × 1 × 1 = 1 cubic foot. Accordingly, the large cube will contain 3 × 3 × 3 = 27 cubic feet or 1 cubic yard.

Table 5-6 shows cubic measure of volume equivalents.

Table 5-6 Cubic Measures of Volume

Measure	*Equivalent*
1728 cubic inches	1 cubic foot
27 cubic feet	1 cubic yard

Dry Measure

Quantities of loose, granular materials (such as grains, some fruits, and certain vegetables) are measured in arbitrary units that, in turn, are defined by means of cubic measures of volume, usually in cubic inches. Their value is sometimes fixed by law.

Table 5-7 shows units of dry measure equivalents for the United States and Table 5-8 shows units of dry measure equivalents for Great Britain and Canada.

Table 5-7 Dry Measure (United States)

Measure	*Equivalent*	*Equivalent*
2 pints	1 quart	67.2 cubic inches
8 quarts	1 peck	537.61 cubic inches
4 pecks	1 bushel	2150.42 cubic inches

Table 5-8 Dry Measure (British and Canadian)

Measure	*Equivalent*	*Equivalent*
1 gallon	.5 peck	277.42 cubic inches
4 pecks	1 bushel	2219.23 cubic inches

The British dry quart is not often used. It is equal to 69.35 cubic inches, or 1.032 U.S. dry quarts.

The weight, rather than the volume, of grains is the standard fixed by the U.S. government (Table 5-9).

Table 5-9 Grain Measure (U.S.)

Measure	*Equivalent*
1 bushel of wheat	60 pounds
1 bushel of barley	48 pounds
1 bushel of oats	32 pounds
1 bushel of rye	56 pounds
1 bushel of corn (shelled)	56 pounds

Board or Lumber Measure

Timbers and logs are measured in *board* or *lumber measure*. The board foot is 1 foot wide, 1 foot long, and 1 inch thick, thereby containing 144 cubic inches. In the retail market, all lumber that is less than 1 inch thick is called one inch. At the sawmills, the full sizes govern the thickness of the saw kerfs; usually about $^1/_4$ inch is allowed for and accounted as sawing loss. Actual finished (dressed) sizes of common lumber and the dimension and timbers for pine are as follows:

- The standard dressed thickness of 1-inch boards is $^3/_4$ inch.
- The standard thickness of 2-inch dimension boards is $1^1/_2$ inches.
- The standard dressed widths of lumber 2 inches thick and less are $^1/_2$ inch less for widths under 8 inches and $^3/_4$ inch less for 8-inch widths and wider.
- The standard dressed widths and thicknesses for lumber and timbers are $^1/_2$ inch less both ways under 8 inches wide and$^3/_4$ inch for 8-inch widths and over. So, a 2-inch × 8-inch board would be $1^1/_2$ inches × $7^1/_4$ inches. A 2-inch × 10-inch board would be $1^1/_2$ inches × $9^1/_4$ inches.

Liquid Measure

Liquid measure is used to measure various liquids such as oils, liquors, molasses, and water. Table 5-10 shows liquid measure equivalents.

Table 5-10 Liquid Measure

Measure	*Equivalent*	*Equivalent*
4 gills	1 pint	28.875 cubic inches
2 pints	1 quart	57.75 cubic inches
4 quarts	1 gallon	231 cubic inches

There is no legal standard barrel in the United States. By custom, a barrel of water is understood to be $31^1/_2$ gallons. The British barrel is generally 36 Imperial gallons. Crude oil is often disposed of at the wells in barrels of 50 gallons, whereas refined oils are marketed in barrels of 48 gallons. Owing to this lack of uniformity, it is safest to specify "barrels of 50 gallons," or something of that nature, to avoid misunderstanding. The barrel is sometimes used as a dry measure unit of varying value. For Portland cement, 4 bags = 1 barrel = 4 cubic feet = 376 pounds.

Measures of Weight

The simplest definition of *weight* is the force with which a body is attracted toward the earth. It is a quantity of heaviness. The three systems (or standards) of weights used in the United States are:

- *Avoirdupois*—Used for almost all ordinary purposes (see Table 5-11)

Table 5-11 Avoirdupois Weights

	Measure	*Equivalent*
U.S.	16 drams	1 ounce
	16 ounces	1 pound
	100 pounds	1 hundredweight
	20 hundredweights	1 ton
	Measure	Equivalent
England	14 pounds	1 stone
	112 pounds	1 hundredweight
	20 hundredweight	1 ton
	2240 pounds	

Note: The 2240-pound ton is sometimes used in the United States for weighing coal at the mines and at Customs houses for evaluating shipments from England.

- *Troy*—Used in weighing precious metals and jewels (see Table 5-12)
- *Apothecaries*—Used by pharmacists when compounding drugs (see Table 5-13)

Table 5-12 Troy Weights

Measure	*Equivalent*
3.086 grains	1 carat
24 grains	1 pennyweight
20 pennyweights	1 ounce
12 ounces	1 pound

Table 5-13 Apothecaries Weights

Measure	*Equivalent*
20 grains	1 scruple
3 scruples	1 dram
8 drams	1 ounce
12 ounces	1 pound

This standard of weights is fast becoming obsolete, although pharmacists must be familiar with it. Manufacturing pharmacists and chemists are rapidly changing to the metric weights, using the metric *gram* as a basis instead of the apothecaries' scruple (1 scruple = 1.296 grams).

Time Measure

Time is defined as measurable duration (see Table 5-14). It is the period during which an action or process continues. The basis (or standard) used in our ordinary determination of time is the *mean solar day*, beginning and ending at mean midnight. The word mean as used here simply means average. The direct ray of the sun does not move in an exact and uniform path around the equator.

Table 5-14 Time Measure

Measure	*Equivalent*
60 seconds	1 minute
60 minutes	1 hour
24 hours	1 day
7 days	1 week
30 days (commonly)	1 month
365 days	1 year
10 years	1 decade
100 years	1 century
1000 years	1 millennium

The length of an *astronomical* year is 365 days, 5 hours, 48 minutes, and 45.51 seconds, or approximately 365 $^1/_4$ days. This makes it necessary to add 1 day every 4 years, thus making the leap year 366 days.

Circular Measure

This measure is used in astronomy, land surveying, navigation, and in measuring angles of all kinds. Circles of all sizes are divisible into degrees, minutes, and seconds (see Table 5-15). Note that a degree is *not* a measurement of length. It is $^1/_{360}$ of the circumference of a circle with any radius. With widespread use of calculators and the need for accuracy in missiles, the degree has now been divided

Table 5-15 Circular Measure

Measure	*Equivalent*
60 seconds	1 minute
60 minutes	1 degree
360 degrees	1 circle

in decimal form rather than minutes and seconds. Most calculators can carry the degree out to 6 places after the decimal point

The Metric System

The base, or fundamental, unit in the metric system is the *meter*. The meter is defined as the distance between two scribed marks on a standard bar made of platinum-iridium kept in the vaults of the International Bureau of Weights and Measures, near Paris, France. Of course, many other standard meter bars have been made from the measurement on this bar. It is permissible and official to use this measurement in the United States, and, in fact, the yard, the basis for the English system of measurement, has been defined as exactly $^{3600}/_{3937}$ meter, or 1 meter = 39.37 inches.

The advantage (and immeasurably greater convenience) of the metric system over the English system of units lies in the fact that it is expressed in tenths, thereby readily allowing the use of decimals. However, the American public is accustomed to the English units, and as recent experience indicates, the system should continue for a long time. The metric system is, of course, in common use all over the world with the exception of some English-speaking countries. The meter is used like the yard to measure cloth and short distances.

Units of other denominations are named by prefixing to the word meter the Latin numerals for the lower denominations and the Greek numerals for the higher denominations, as shown in Table 5-16.

Table 5-16 Denominations

Lower Denomination		***Higher Denomination***	
Greek	***Equivalent***	***Greek***	***Equivalent***
Deci	$^{1}/_{10}$	Deka	10
Centi	$^{1}/_{100}$	Hecto	100
Milli	$^{1}/_{1000}$	Kilo	1000
Micro	$^{1}/_{1,000,000}$	Myria	10,000
		Mega	1,000,000

Therefore, 1 decimeter = $^{1}/_{10}$ of a meter, 1 millimeter = $^{1}/_{1000}$ of a meter, 1 kilometer = 1000 meters, and so forth. From this explanation of the metric prefixes, the linear equivalents shown in Table 5-17 can easily be understood.

Table 5-17 Metric Table of Linear Measure

Metric Denomination		***Meter***	***U.S. Value***
	1 millimeter	.001	.0394 inches
10 millimeters	1 centimeter	.01	.3937 inches
10 centimeters	1 decimeter	.1	3.937 inches
10 decimeters	1 meter	1.	39.3707 inches
			3.28 feet
10 meters	1 dekameter	10.	32.809 feet
10 dekameters	1 hectometer	100.	328.09 feet
10 hectometers	1 kilometer	1000.	.62138 miles
10 kilometers	1 myriameter	10,000.	6.2138 miles

The kilometer is commonly used for measuring long distances. The square meter (see Table 5-18) is the unit used for measuring ordinary surfaces, such as flooring or ceilings.

Table 5-18 Metric Table of Square Measure

Measure	***Equivalent***	***Equivalent***
100 square millimeters (mm^2)	1 square centimeter	0.15 + square inch
100 square centimeters (cm^2)	1 square decimeter	15.5 + square inches
100 square decimeters (dm^2)	1 square meter (m^2)	1.196 + square yards

The acre is the unit of land measure and is defined as a square whose side is 10 meters, equal to a square dekameter, or 119.6 square yards (see Table 5-19).

Table 5-19 Metric Table of Land Measure

Measure	***Equivalent***	***Equivalent***
1 centiare (ca)	1 square meter	1.196 square yards
100 centiares (ca)	1 acre	119.6 square yards
100 ares (A)	1 hectare	2.471 acres
100 hectares (ha)	1 square kilometer	0.3861 square miles

The cubic meter is the unit used for measuring ordinary solids, such as excavations or embankments (see Table 5-20).

Table 5-20 Metric Table of Cubic Measure

Measure	*Equivalent*	*Equivalent*
1000 cubic millimeters (mm^3)	1 cubic centimeter	0.061 + cubic inches
1000 cubic centimeters (cm^3)	1 cubic decimeter	61.026 + cubic inches
1000 cubic decimeters (dm^3)	1 cubic meter	35.316 + cubic feet

The liter is the unit of capacity, both of liquid and of dry measures, and is equivalent to a vessel whose volume is equal to a cube whose edge is $^1/_{10}$ of a meter, equal to 1.0567 quarts liquid measure, and 0.9081 quart dry measure (see Table 5-21).

The hectoliter is the unit used for measuring liquids, grain, fruit, and roots in large quantities. The gram is the unit of weight equal to the weight of a cube of distilled water, the edge of which is $^1/_{100}$ of a meter, and is equal to 15.432 troy grains (see Table 5-22).

Geometry

By definition, *geometry* is that branch of mathematics that deals with space and figures in space. In other words, it is the science of the mutual relations of points, lines, angles, surfaces, and solids that are considered as having no properties except those arising from extension and difference of situation.

Lines

The two kinds of lines are straight and curved. A *straight line* is the shortest distance between two points. A *curved line* is one that changes its direction at every point. Two lines are said to be parallel when they have the same direction. A horizontal line is one parallel to the horizon or surface of the Earth. A line is perpendicular with another line when they are at right angles to each other. These definitions are illustrated in Figure 5-9.

Angles

An *angle* is the difference in direction between two lines proceeding from the same point (called the *vertex*). Angles are said to be *right* (90 degrees) when formed by two perpendicular lines (see

Table 5-21 Metric Table of Capacity

10 milliliters (ml.)	= 1 centiliter	= .0338 fluid ounce
10 centiliters (cl.)	= 1 deciliter	= .1025 cubic inch
10 deciliters (dl.)	= 1 liter	= 1.0567 liquid quart
10 liters (l.)	= 1 dekaliter	= 2.64 gallons
10 dekaliters (dl.)	= 1 hectoliter	= 26.418 gallons
10 hectoliters (hl.)	= 1 kiloliter	= 264.18 gallons
10 kiloliters (kl.)	= 1 myrialiter (ml.)	
1 myrialiter	= 10 cubic meters	
	= 283.72 + bushels	= 2641.7 + gallons
1 kiloliter	= 1 cubic meter	
	= 28.372 + bushels	= 264.17 gallons
1 hectoliter	= $^{1}/_{10}$ cubic meter	
	= 2.8372 + bushels	= 26.417 gallons
1 decaliter	= 10 cubic decimeters	
	= 9.08 quarts	= 2.6417 gallons
1 liter	= 1 cubic decimeter	
	= .908 quart	= 1.0567 quart liquid
1 deciliter	= $^{1}/_{10}$ cubic decimeter	
	= 6.1022 cubic inches	= .845 gallons
1 milliliter	= 10 cubic centimeters	
	= .6102 cubic inches	= .338 fluid ounces
1 centiliter	= 1 cubic centimeter	
	= .061 cubic inches	= .27 fluid dram

Figure 5-10A), *acute* (less than 90 degrees) when less than a right angle (see Figure 5-10B), and *obtuse* (more than 90 degrees) when greater than a right angle (see Figure 5-10C). All angles except right (or 90-degree) angles are called *oblique angles*.

Angles are usually measured in degrees (circular measure) (see Figure 5-10D). The *complement* of an angle is the difference between 90 degrees and the angle. The *supplement* of the angle is the difference between the angle and 180 degrees.

Plane Figures

The term *plane figures* means a plane surface bounded by straight or curved lines, and a *plane* (or *plane surface*) is one in which any straight line joining any two points lies wholly in the surface. Figure 5-11 defines a plane surface. There is a great variety of plane

Table 5-22 Metric Table of Weight Measure

Measure	*Equivalent*	*Equivalent*
10 milligrams (mg)	1 centigram	0.15432 + grains troy
10 centigrams (cg)	1 decigram	1.54324 + grains troy
10 decigrams (dg)	1 gram	15.43248 + grains troy
10 grams (g)	1 dekagram	0.35273 + ounce avoirdupois
10 dekagrams (Dg)	1 hectogram	3.52739 + ounces avoirdupois
10 hectograms (hg)	1 kilogram	2.20462 + pounds avoirdupois
10 kilograms (kg)	1 myriagram	22.04621 + pounds avoirdupois
10 myriagrams (Mg)	1 quintal	220.46212 + pounds avoirdupois
10 quintals	1 ton	2204.62125 + pounds avoirdupois


(A)
M
SHORTEST DISTANCE BETWEEN M AND S
S
DIRECTION CHANGES AT EVERY POINT
(B)
(C)
90°
(D)

Figure 5-9 Various lines: (A) straight, (B) curved, (C) parallel, and (D) perpendicular.


RIGHT ANGLES
90°
90°
PERPENDICULAR LINES
(A)
90°
ACUTE ANGLE
(B)
OBTUSE ANGLE
90°
(C)
COMPLEMENT OF ANGLE θ
SUPPLEMENT OF ANGLE θ
θ
90°
180°
(D)

Figure 5-10 Various angles: (A) right, (B) acute, (C) obtuse, and (D) complement and supplement of an angle.


PLANE SURFACE
EVERY POINT ON LINE LIES IN THE SURFACE
S
M
STRAIGHT LINE TO ANY TWO POINTS MS

Figure 5-11 A plane surface means that every point on a straight line joining any two points in the surface lies in the surface.

figures, which are known as *polygons* when their sides are straight lines. The sum of the sides is called the *perimeter*. A regular polygon has all its sides and angles equal. Plane figures of three sides are known as triangles (see Figure 5-12), and plane figures of four sides are quadrilaterals. Figure 5-13 shows examples of these. Various plane figures are formed by curved sides and are known as circles, ellipses, and so forth, as shown in Figure 5-14. Figure 5-15 details the structure of the quadrilateral.



Figure 5-12 Various triangles. A triangle is a polygon having three sides and three angles.

Solids

Solids have three dimensions—length, width, and thickness. The bounding planes are called the *faces*, and the intersections are called the *edges*. A prism (see Figure 5-16) is a solid whose ends consist of equal and parallel polygons, and whose sides are *parallelograms*. The *altitude* of a prism is the perpendicular distance of its opposite sides or bases. A *parallelopipedon* is a prism that is bounded by six parallelograms; the opposite parallelograms are parallel and equal. A *cube* is a parallelopipedon whose faces are equal. One important solid is the *cylinder*, which is a body bounded by a uniformly curved surface and having its ends equal and forming parallel circles (see Figure 5-17). There are numerous other solids having curved surfaces (such as *cones* and *spheres*).

Geometrical Problems

The following problems illustrate the method in which various geometrical figures are constructed, and they should be solved by the


SQUARE
RECTANGLE
RHOMBUS
RHOMBOID

Figure 5-13 Various quadrilaterals. All opposite sides of a quadrilateral are equal.


TANGENT
R
RADIUS
90°
CENTER
0
A
B
DIAMETER
(AB)
CHORD
SECTOR
SEGMENT
S
AXIS
M
MAJOR
AXIS
L
MINOR
F

Figure 5-14 Curved figures. A circle is a plane figure bounded by a uniformly curved line, every point of which is equidistant from the center point O. OR is a radius, and AB is a diameter. An ellipse is a curved figure enclosed by a curved line that is such that the sum of the distances between any point on the circumference and the two foci is invariable. ML is the major axis, and SF is the minor axis.


BASE
LEG
DIAGONAL
LEG
ALTITUDE
BASE

Figure 5-15 **The parallel sides of a quadrilateral (four-sided polygon) are the bases. The distance between the bases is the altitude, and a line joining two opposite vertices is a diagonal.**


LESS THAN 90°
(A)
(B)
(C)

Figure 5-16 **Various prisms: (A) cube, or equilateral parallelopipedon; (B) parallelopipedon; and (C) oblique parallelopipedon.**



Figure 5-17 **Various solids: (A) pentagonal prism, (B) triangular prism, and (C) cylinder.**

use of pencil, dividers, compass, and scale. Many of these problems are commonly encountered in carpentry with layout work. Therefore, experience in working them out will be of value to carpenters and woodworkers.

Problem 1

To bisect (or divide into two equal parts) a straight line or arc of a circle.

In Figure 5-18, from the ends *A* and *B*, as centers, describe arcs cutting each other at *C* and *D*, and draw line *CD*, which cuts the line at *E*, or the arc at *F*.



Figure 5-18 To bisect a straight line or arc of a circle.

Problem 2

To draw a perpendicular to a straight line, or a radial line to an arc.

The line *CD* is perpendicular to *AB*; also, the line *CD* is radial to the arc *AB* (see Figure 5-18).

Problem 3

To erect a perpendicular to a straight line from a given point in that line.

In Figure 5-19, with any radius from any given point *A*, in the line *BC* describe arcs cutting the line at *B* and *C*. Next, with a longer radius describe arcs with *B* and *C* as centers, intersecting at *D*, and draw the perpendicular *DA*.

Second Method

In Figure 5-20, from any point *F* above *BC*, describe a circle passing through the given point *A* and cutting the given line at *D*. Draw *DF*, and extend it to cut the circle at *E*. Draw the perpendicular *AE*.



Figure 5-19 To erect a perpendicular to a straight line from a given point on that line.



Figure 5-20 To erect a perpendicular to a straight line from a given point on that line, second method.

Third Method (Boat Builders' Layout Method)

In Figure 5-21, let *MS* be the given line and *A* be the given point. From *A*, measure off a distance *AB* (4 feet). With centers *A* and *B* and radii of 3 and 5 feet, respectively, describe arcs *L* and *F* intersecting at *C*. Draw a line through *A* and *C*, which will be the



Figure 5-21 To erect a perpendicular to a straight line from a given point on that line, third method.

perpendicular required. This method is used extensively by carpenters when squaring the corners of buildings, but they ordinarily use multiples of 3, 4, and 5 (such as 6, 8, and 10, or 12, 16, and 20).

Fourth Method

In Figure 5-22, from *A*, describe an arc *EC*, and from *E* with the same radius describe the arc *AC*, cutting the other at *C*. Through *C*,



Figure 5-22 To erect a perpendicular to a straight line from a given point on that line, fourth method.

draw a line *ECD*. Lay off *CD* equal to *CE*, and through *D*, draw the perpendicular *AD*. The triangle produced is exactly 60 degrees at *E*, 30 degrees at *D*, and 90 degrees at *A*. The hypotenuse *ED* is exactly twice the length of the base *EA*.

Problem 4

To erect a perpendicular to a straight line from any point outside the line.

In Figure 5-23, from the point *A*, with a sufficient radius cut the given line at *F* and *G*, and from these points describe arcs cutting at *E*. Draw the perpendicular *AE*.



Figure 5-23 To erect a perpendicular to a straight line from any point outside the line.

Second Method

In Figure 5-24, from any two points *B* and *C* at some distance apart in the given line and with the radii *BA* and *CA*, respectively, describe arcs cutting at *A* and *D*. Draw the perpendicular *AD*.

Problem 5

To draw a line parallel to a given line through a given point.

In Figure 5-25, with *C* as the center, describe an arc tangent to the given line *AB*. The radius will then equal the distance from the given point to the given line. Take a point *B* on the given line remote from *C*, and describe an arc. Draw a line through *C*, tangent to this arc at *D*, and it will be parallel to the given line *AB*.

Second Method

In Figure 5-26, from *A*, the given point, describe the arc *FD*, cutting the given line at *F*; from *F*, with the same radius, describe the arc



Figure 5-24 To erect a perpendicular to a straight line from any point outside the line, second method.



Figure 5-25 To draw a line parallel to a given line through a given point.



Figure 5-26 To draw a line parallel to a given line through a given point, second method.

EA, and lay off *FD* equal to *EA*. Draw the parallel line through the points *AD*.

Problem 6
To divide a line into a number of equal parts.

In Figure 5-27, assuming line *AB* is to be divided into five equal parts, draw a diagonal line *AC* of five units in length. Join *BC* at 5 and through the points 1, 2, 3, and 4. Draw lines 1*L*, 2*a*, and so forth, parallel to *BC*. *AC* will then be divided into five equal parts, *AL, La, ar, rf*, and *fB*.



Figure 5-27 To divide a line into a number of equal parts.

Problem 7

To draw an angle equal to a given angle on a straight line.

In Figure 5-28, let *A* be the given angle, and *FG* the line. With any radius from the points *A* and *F*, describe arcs *DE* and *IH* cutting the sides of angle *A* and line *FG*. Lay off arc *IH* equal to arc *DE*, and draw line *FH*. Angle *F* is then equal to *A*, as required



Figure 5-28 To draw an angle equal to a given angle on a straight line.

Problem 8

To bisect an angle

In Figure 5-29, let *ACB* be the angle. With the center of the angle at *C*, describe an arc cutting the sides at *A* and *B*. Using *A* and *B* as centers, describe arcs that intersect at *D*. A line through *C* and *D* will divide the angle into two equal parts.

Problem 9

To find the center of a circle.

In Figure 5-30, draw any chord MS. With M and S as centers, and with any radius, describe arcs LF and $L'F'$, and draw a line through their intersection, giving a diameter AB. Applying the same construction with centers A and B, describe arcs ef and $e'f'$. A line drawn through the intersections of these arcs will cut line AB at O, the center of the circle.



Figure 5-29 To bisect an angle.

Problem 10

To describe an arc of a circle with a given radius through two given points.

In Figure 5-31, take the given points A and B as centers, and, with the given radius, describe arcs that intersect at C. From C, with the same radius, describe an arc AB, as required.



Figure 5-30 Find the center of a circle.

Second Method

In Figure 5-32, for a circle or an arc, select three points ABC in the circumference that are well apart. With the same given radius, describe arcs from these three points that intersect each other, and draw two lines, DE and FG, through their intersections. The point where these lines intersect is the center of the circle or arc.

Problem 11

To describe a circle passing through three given points.



Figure 5-31 To describe an arc of a circle with a given radius through two given points.



Figure 5-32 To describe an arc of a circle with a given radius through two given points, second method.

In Figure 5-32, let *A*, *B*, and *C* be the given points, and proceed as in Problem 10 to find the center *O* from which the circle may be described. This problem is useful in such work as laying out an object of large diameter (such as an arch) when the span and rise are given.

Problem 12

To draw a tangent to a circle from a given point in the circumference.

In Figure 5-33, from *A*, lay off equal segments *AB* and *AD*. Join line *BD*, and draw line *AE* parallel to *BD* for the tangent.

Problem 13

To draw tangents to a circle from points outside the circle.

In Figure 5-34, from *A*, and with the radius *AC*, describe an arc *BCD*. From *C*, with a radius equal to the diameter of the circle,



Figure 5-33 To draw a tangent to a circle from a given point in the circumference.



Figure 5-34 To draw tangents to a circle from points outside the circle.

intersect the arc at *BD*. Join *BC* and *CD*, which intersect the circle at *E* and *F*, and draw the tangents *AE* and *AF*.

Problem 14
To describe a series of circles tangent to two inclined lines and tangent to each other.

In Figure 5-35, bisect the inclination of the given lines *AB* and *CD* by the line *NO*. From a point *P* in this line, draw the perpendicular *PB* to the line *AB*, and on *P*, describe the circle *BD*, touching the lines and the centerline at *E*. From *E*, draw *EF* perpendicular to the center line intersecting *AB* at *F*, and from *F*, describe an arc *EG* intersecting *AB* at *G*. Draw *GH* parallel to *BP*, thus producing *H*, the center of the next circle, to be described with the radius *HE*, and so on for the next circle *IN*.



Figure 5-35 To describe a series of circles tangent to two inclined lines and tangent to each other.

Problem 15

To construct an equilateral triangle on a given base.

In Figure 5-36, with *A* and *B* as centers and a radius equal to *AB*, describe arcs *l* and *f*. At their intersection *C*, draw lines *CA* and *CB*, which are the sides of the required triangle. If the sides are to be unequal, the process is the same, taking as the radii the lengths of the two sides to be drawn.



Figure 5-36 To construct an equilateral triangle on a given base.

Problem 16

To construct a square on a given base.

In Figure 5-37, with end points *A* and *B* of the base as centers and a radius equal to *AB*, describe arcs that intersect at *C*; on *C*, describe arcs that intersect the others at *D* and *E*, and on *D* and *E*, intersect these arcs *F* and *G*. Draw *AE* and *BG*, and join the intersections *HI* to form the square *AHIB*.



Figure 5-37 To construct a square or a rectangle on a given base.

Problem 17

To construct a rectangle on a given base.

In Figure 5-37, let *AB* be the given base. Erect a perpendicular at *A* and at *B* that is equal to the altitude of the rectangle, and join their ends *F* and *G* by line *FG*. *AFGB* is the rectangle required.

Problem 18

To construct a parallelogram given the sides and an angle.

In Figure 5-38, draw side *DE* equal to the given length *A*, and lay off the other side *DF*, equal to the other length *B*, thus forming the given angle *C*. From *E*, with *DF* as the radius, describe an arc, and from *F*, with the radius *DE*, intersect the arc at *G*. Draw *FG* and *EG*. The remaining sides may also be drawn as parallels to *DE* and *DF*.

Problem 19

To draw a circle around a triangle.

In Figure 5-39, bisect two sides *AB* and *AC* of the triangle at *E* and *F*, and from these points draw perpendiculars intersecting at *K*. From *K*, with radius *KA* or *KC*, describe the circle *ABC*.

Problem 20

To circumscribe and inscribe a circle about a square.



Figure 5-38 To construct a parallelogram given the sides and an angle.



Figure 5-39 To draw a circle around a triangle.

In Figure 5-40, draw the diagonals *AB* and *CD* intersecting at *E*. With a radius *EA*, circumscribe the circle. To inscribe a circle, draw a perpendicular from the center (as just found) to one side of the square, as line *OM*. With radius *OM*, inscribe the circle.

Problem 21
To circumscribe a square around a circle.



(A) CIRCUMSCRIBED CIRCLE

(B) INSCRIBED CIRCLE

Figure 5-40 (A) To circumscribe a circle around a square. (B) To inscribe a circle inside a square.

In Figure 5-41, draw diameters *MS* and *LF* at right angles to each other. At points *M*, *L*, *S*, and *F*, where these diameters intersect the circle, draw tangents (that is, lines perpendicular to the diameters), obtaining the sides of the circumscribed square *ABCD*.



Figure 5-41 To circumscribe a square about a circle.

Problem 22

To inscribe a circle in a triangle.

In Figure 5-42, bisect two angles *A* and *C* of the triangle with lines that intersect at *D*. From *D*, draw a perpendicular *DE* to any side. With *DE* as the radius, describe a circle.

Problem 23

To inscribe a pentagon in a circle.

In Figure 5-43, draw two diameters *AC* and *BD* at right angles intersecting at *O*. Bisect *AO* at *E*, and from *E*, with radius *EB*, *AC* at *F*; from *B*, with radius *BF*. Intersect the circumference at *G* and *H*, and with the same radius, step round the circle to *I* and *K*; join the points thus found to form the pentagon *BGIKH*.

Problem 24

To inscribe a five-pointed star in a circle.



Figure 5-42 To inscribe a circle in a triangle.



Figure 5-43 To inscribe a pentagon in a circle.

In Figure 5-44, proceed as explained for the inscribed pentagon in Problem 23. Then, connect point *B* with points *K* and *I*, point *H* with points *G* and *I*, and so forth. The star is mathematically correct.

Problem 25
To construct a hexagon from a given straight line



Figure 5-44 To inscribe a five-pointed star in a circle.

In Figure 5-45, from *A* and *B*, the ends of the given line, describe arcs intersecting at *g*. From *g*, with the radius *gA*, describe a circle. With the same radius, lay off arcs *AG*, *GF*, *BD*, and *DE*. Join the points thus found to form the hexagon.



Figure 5-45 To construct a hexagon from a given straight line.

Problem 26

To inscribe a hexagon in a circle.

In Figure 5-46, draw a diameter *ACB*. From *A* and *B*, as centers with the radius of the circle *AC*, intersect the circumference at *D*, *E*, *F*, and *G*, and draw lines *AD*, *DE*, and so forth, to form the hexagon. The points *D*, *E*, and so forth, may also be found by stepping off the radius (with the dividers) six times around the circle.



Figure 5-46 To inscribe a hexagon in a circle.

Problem 27

To describe an octagon on a given straight line.

In Figure 5-47, extend the given line *AB* both ways. Now, draw perpendiculars *AE* and *BF*. Bisect the external angles *A* and *B* by using lines *AH* and *BC*. These are made equal to line *AB*. Draw *CD* and *HG* parallel to *AE* and equal to line *AB*. Draw *CD* and *HG* parallel to *AE* and equal to line *AB*. With *G* and *D* as centers, and with the radius equal to *AB*, intersect the perpendiculars at *E* and *F*, and draw line *EF* to complete the hexagon.

Problem 28

To inscribe an octagon in a square.

In Figure 5-48, draw the diagonals of the square intersecting at *e*. From the corners *A*, *B*, *C*, and *D*, with *Ae* as the radius, describe arcs intersecting the sides of the square at *g*, *h*, and so forth, and join the points found to complete the octagon.



Figure 5-47 To describe an octagon on a given straight line.



Figure 5-48 To inscribe an octagon in a square.

Problem 29

To inscribe an octagon in a circle.

In Figure 5-49, draw two diameters *AC* and *BD* at right angles. Bisect the arcs *AB*, *BC*, and so forth, at *e*, *f*, and so forth, to form the octagon.



Figure 5-49 To inscribe an octagon in a circle.

Problem 30

To circumscribe an octagon about a circle.

In Figure 5-50, describe a square about the given circle *AB*. Draw perpendiculars *h*, *k*, and so forth, to the diagonals, touching the circle, to form the octagon. The points *h*, *k*, and so forth, may be found by cutting the sides from the corners.

Problem 31

To describe an ellipse when the two axes are given.

In Figure 5-51, draw the major and minor axes *AB* and *CD*, respectively, at right angles intersecting at *E*. On *C*, with *AE* as the radius, intersect the axis *AB* at *F* and *G*, the *foci*. Insert pins through the axis at *F* and *G*, and loop a thread or cord on them equal in length to the axis *AB*, so that when stretched, it reaches extremity *C* of the *conjugate axis*, as shown in dotted lines. Place a pencil inside the cord, as at *H*, and, by guiding the pencil in this manner, describe the ellipse.

Second Method

Along the edge of a piece of paper, mark off a distance *ac* equal to *AC*, one-half the major axis, and from the same point a distance *ab* equal to *CD*, one-half the minor axis, as shown in Figure 5-52. Place the paper to bring point *b* on the line *AB*, or major axis, and point *c* on the line *DE*, or minor axis. Lay off the position of point *a*.



Figure 5-50 To circumscribe an octagon about a circle.



Figure 5-51 To describe an ellipse when the two axes are given.

By shifting the paper so that point *b* travels on the major axis and point *c* travels on the minor axis, any number of points in the curve may be found through which the curve may be traced.

Mensuration

As mentioned earlier, mensuration is the act, art, or process of measuring. It is the branch of mathematics that deals with finding the length of lines, the area of surfaces, and the volume of solids. Therefore, the problems that follow will be divided into three groups as follows:



Figure 5-52 To describe an ellipse given the two axes, second method.

- Measurement of *lines*, one dimension (length)
- Measurement of *surfaces* (areas), two dimensions (length and width)
- Measurement of *solids* (volumes), three dimensions (length, width, and thickness)

Measurement of Lines—Length

Problem 1

To find the length of any side of a right triangle given the other two sides.

Rule: The length of the hypotenuse equals the square root of the sum of the squares of the two legs. The length of either leg equals the square root of the difference of the square of the hypotenuse and the square of the other leg.

Example The two legs of a right triangle measure 3 feet and 4 feet. Find the length of the hypotenuse. If the lengths of the hypotenuse and one leg are 5 feet and 4 feet, respectively, what is the length of the other leg?

In Figure 5-53A,

$$AB = \sqrt{3^2 + 4^2} = \sqrt{25} = 5 \text{ feet}$$

In Figure 5-53B,

$$BC = \sqrt{5^2 - 3^2} = \sqrt{25 - 9} = \sqrt{16} = 4 \text{ feet}$$



Figure 5-53 To find the length of any side of a right triangle given the other two sides.

Problem 2

To find the length of the circumference of a circle.

Rule: Multiply the diameter by 3.1416.

Example What length of molding strip is required for a circular window that is 5 feet in diameter?

$$5 \times 3.1416 = 15.7 \text{ feet}$$

Since the carpenter does not ordinarily measure feet in tenths, .7 should be reduced to inches. It corresponds to $8^1/_2$ inches from Table 5-23. That is, the length of molding required is 15 feet $8^1/_2$ inches.

Problem 3

To find the length of the arc of a circle.

Rule: Arc = .017453 × radius × central angle.

Example If the radius of a circle is 2 feet, what is the length of a 60° arc?

Table 5-23 Decimals of a Foot and Inches

Inch	*0 inch*	*1 inch*	*2 inches*	*3 inches*	*4 inches*	*5 inches*	*6 inches*	*7 inches*	*8 inches*	*9 inches*	*10 inches*	*11 inches*
0	0.0000	0.0833	0.1677	0.2500	0.3333	0.4167	0.5000	0.5833	0.6667	0.7500	0.8333	0.9167
1–16	0.0052	0.0885	0.1719	0.2552	0.3385	0.4219	0.5052	0.5885	0.6719	0.7552	0.8385	0.9219
1–8	0.0104	0.0937	0.1771	0.2604	0.3437	0.4271	0.5104	0.5937	0.6771	0.7604	0.8437	0.9271
3–16	0.0156	0.0990	0.1823	0.2656	0.3490	0.4323	0.5156	0.5990	0.6823	0.7656	0.8490	0.9323
1–4	0.0208	0.1042	0.1875	0.2708	0.3542	0.4375	0.5208	0.6042	0.6875	0.7708	0.8542	0.9375
5–16	0.0260	0.1094	0.1927	0.2760	0.3594	0.4427	0.5260	0.6094	0.6927	0.7760	0.8594	0.9427
3–8	0.0312	0.1146	0.1979	0.2812	0.3646	0.4479	0.5312	0.6146	0.6979	0.7812	0.8646	0.9479
7–16	0.0365	0.1198	0.2031	0.2865	0.3698	0.4531	0.5365	0.6198	0.7031	0.7865	0.8698	0.9531
1–2	0.0417	0.1250	0.2083	0.2917	0.3750	0.4583	0.5417	0.6250	0.7083	0.7917	0.8750	0.9583
9–16	0.0469	0.1302	0.2135	0.2969	0.3802	0.4635	0.5469	0.6302	0.7135	0.7969	0.8802	0.9635
5–8	0.0521	0.1354	0.2188	0.3021	0.3854	0.4688	0.5521	0.6354	0.7188	0.8021	0.8854	0.9688
11–16	0.0573	0.1406	0.2240	0.3073	0.3906	0.4740	0.5573	0.6406	0.7240	0.8073	0.8906	0.9740
3–4	0.0625	0.1458	0.2292	0.3125	0.3958	0.4792	0.5625	0.6458	0.7292	0.8125	0.8958	0.9792
13–16	0.0677	0.1510	0.2344	0.3177	0.4010	0.4844	0.5677	0.6510	0.7344	0.8177	0.9010	0.9844
7–8	0.0729	0.1562	0.2396	0.3229	0.4062	0.4896	0.5729	0.6562	0.7396	0.8229	0.9062	0.9896
15–16	0.0781	0.1615	0.2448	0.3281	0.4115	0.4948	0.5781	0.6615	0.7448	0.8281	0.9115	0.9948

Solution:

$$2 \times .017453 \times 60 = 2.094,$$
or approximately 2 feet $1^1/_8$ inches

Problem 4

To find the rise of an arc.

Rule: Rise of an arc =

$$\sqrt{(4 \times \text{radius}^2) - \text{length}}$$

Example If the radius of a circle is 2 feet, what is the rise at the center of a 2-foot chord?

Solution:

$$^1/_2\sqrt{(4 \times 2^2) - 2} = {}^1/_2\sqrt{14} = 1.87 \text{ feet}$$
$$= 1 \text{ feet } 10^1/_2 \text{ inches}$$

Measurement of Surfaces—Area

Problem 5

To find the area of a square.

Rule: Multiply the base by the height.

Example What is the area of a square whose side is 5 feet (see Figure 5-54)?

$$5 \times 5 = 25 \text{ square feet}$$

Problem 6

To find the area of a rectangle.

Rule: Multiply the base by the height (that is, width by length).

Example What is the floor area of a porch 5 feet wide and 12 feet long (see Figure 5-55)?

$$5 \times 12 = 60 \text{ square feet}$$

Problem 7

To find the area of a parallelogram.

Rule: Multiply the base by the perpendicular height.

Example What is the area of a 5-foot × 12-foot parallelogram (see Figure 5-56)?

$$5 \times 12 = 60 \text{ square feet}$$

Problem 8

To find the area of a triangle (see Figure 5-57)

Rule: Multiply the base by one-half the altitude.


5 FT
AREA = 25 SQ FT
HEIGHT
5 FT
BASE

Figure 5-54 **To find the area of a square.**


12 FT
5 FT
AREA = 60 SQ FT
WIDTH
LENGTH

Figure 5-55 **To find the area of a rectangle.**


12 FT
5 FT
AREA = 60 SQ FT
PERPENDICULAR HEIGHT
BASE

Figure 5-56 **To find the area of a parallelogram.**



(A) (B)

Figure 5-57 To find the area of a triangle (equal to $\frac{1}{2}$ area of parallelogram ABDC).

Example How many square feet of sheathing are required to cover a church steeple having four triangular sides?

Problem 9

To find the area of a trapezoid.

Rule: Multiply one-half the sum of the two parallel sides by the perpendicular distance between them.

Example What is the area of the trapezoid shown in Figure 5-58?

LA and FR are the parallel sides, and MS is the perpendicular distance between them. Therefore,

$$\text{area} = {}^1/_2\,(LA + FR) \times MS$$

$$\text{area} = {}^1/_2\,(8 + 12) \times 6 = 60 \text{ square feet}$$

Problem 10

To find the area of a trapezium.

Rule: Draw a diagonal, dividing the figure into triangles. Measure the diagonal and the altitudes, and find the area of the triangles. The sum of these areas is then the area of the trapezium.

Example What is the area of the trapezium shown in Figure 5-59? (Draw diagonal LR and altitudes AM and FS.)

$$\text{area of triangle } ALR = {}^1/_2\,(12 \times 9) = 54 \text{ square feet}$$

$$\text{area of triangle } LRF = {}^1/_2\,(12 \times 6) = 36 \text{ square feet}$$

$$\begin{aligned}\text{area of trapezium } LARF &= ALR + LRF = 36 + 54\\ &= 90 \text{ square feet}\end{aligned}$$


8 FT
L
M
A
AREA = 60 SQ FT
6 FT
F
S
R
12 FT

Figure 5-58 To find the area of a trapezoid.


A
LR = 12 FT
AM = 6 FT
FS = 9 FT
6 FT
L
M
S
R
12 FT
9 FT
F

Figure 5-59 To find the area of a trapezium.

Problem 11

To find the area of any irregular polygon.

Rule: Draw diagonals, dividing the figure into triangles, and find the sum of the areas of these triangles.

Problem 12

To find the area of any regular polygon, such as shown in Figure 5-60, when the length of only one side is given

Rule: Multiply the square of the sides by the figure for "area when side = 1" opposite the particular polygon in Table 5-24.

Example What is the area of an octagon (8-sided polygon) whose sides are 4 feet in length?

In Table 5-24 under 8 find 4.828. Multiply this by the square of one side.

$$4.828 \times 4^2 = 77.25 \text{ square feet}$$

Problem 13

To find the area of a circle (see Figure 5-61).

Rule: Multiply the square of the diameter by 0.7854.

Example How many square feet of floor surface are there in a 10-foot circular floor?

$$10^2 \times 0.7854 = 78.54 \text{ square feet}$$

Problem 14

To find the area of a sector of a circle.

Rule: Multiply the arc of the sector by one-half the radius.

Example How much tin is required to cover a 60° section of a 10-foot circular deck?

$$\text{length of } 60^\circ \text{ arc} = {}^{60}/_{30} \text{ of } 3.1416 \times 10 = 5.24 \text{ feet}$$

$$\begin{aligned}\text{tin required for } 60^\circ \text{ sector} &= 5.24 \times {}^{1}/_{2} \times 5\\ &= 13.1 \text{ square feet}\end{aligned}$$

Problem 15

To find the area of a segment of a circle.

Rule: Find the area of the sector that has the same arc, and also find the area of the triangle formed by the radii and chord. Take the sum of these areas if the segment is greater than 180°. Take the difference if the segment is less than 180°.

Problem 16

To find the area of a ring.

Rule: Take the difference between the areas of the two circles.



Steel square cut to miter sides at 30°

$R = 2r$, or $.577\ S$
AREA $= .433\ S^2$
$= 1.299\ R^2$
$= 5.196\ r^2$
$= \frac{(R+r)}{2}\ S$

(A) Equilateral triangle (3 sides).



Steel square cut to miter sides at 45°

$R = .707\ S$, or $1.414\ r$
AREA $= S^2$
$= 2R^2$
$= 4r^2$

(B) Square (4 sides).



Steel square cut to miter sides at 36°

$R = .851\ S$, or $1.236\ r$
AREA $= 1.72\ S^2$
$= 2.378\ R^2$
$= 3.633\ r^2$

(C) Pentagon (5 sides).

Steel square cut to miter sides at 30°

$R = S$, or $1.155\ r$
AREA $= 2.598\ S^2$
$= 2.598\ R^2$
$= 3.464\ r^2$

(D) Hexagon (6 sides).



Steel square cut to miter corners at 25° 43'

$R = 1.152\ S$, or $1.11\ r$
AREA $= 3.634\ S^2$
$= 2.736\ R^2$
$= 3.371\ r^2$

(E) Heptagon (7 sides).



Steel square cut to miter corners at 22° 30'

$R = 1.307\ S$, or $1.082\ r$
AREA $= 4.828\ S^2$
$= 2.828\ R^2$
$= 3.314\ r^2$

(F) Octagon (8 sides).



Figure 5-60 Regular polygons.

Table 5-24 Regular Polygons

Number of sides	*3*	*4*	*5*	*6*	*7*	*8*	*9*	*10*	*11*	*12*
Area when side = 1	0.433	1.0	1.721	2.598	3.634	4.828	6.181	7.694	9.366	11.196



Figure 5-61 The decimal 0.7854 is used to find the area of a circle. If a square is divided into 10,000 equal parts (small squares), then a circle with a diameter D equal to one side of the large square will contain 7854 small squares. Therefore, if the area of the large square is 1 square inch, then the area of the circle will be $^{7854}/_{10,000}$, or 0.7854 square inch.

Problem 17
To find the area of an ellipse.

Rule: Multiply the product of the two diameters by 0.7854.

Example What is the area of an ellipse whose two diameters are 10 inches and 6 inches?

$$10 \times 6 \times 0.7854 = 47.12 \text{ square inches}$$

Problem 18
To find the circular area of a cylinder.

Rule: Multiple 3.1416 by the diameter and by the height.

Example How many square feet of lumber are required for the sides of a cylindrical tank (see Figure 5-62) that is 8 feet in diameter and 12 feet high? How many 4-inch × 12-feet pieces will be required?



Figure 5-62 To find the area of a cylinder.

$$\text{cylindrical surface} = 3.1416 \times 8 \times 12 = 302 \text{ square feet}$$

$$\text{circumference of tank} = 3.1416 \times 8 = 25.1 \text{ feet}$$

$$\text{number of } 4'' \times 12' \text{ pieces} = \frac{25.1 \times 12}{4} = 25.1 \times 3 = 75.3$$

Problem 19

To find the area of a cone (see Figure 5-63).

Rule: Multiply 3.1416 by the diameter of the base and by one-half the slant height.

Example A conical spire with a base 10 feet in diameter and an altitude of 20 feet is to be covered. Find the area of the surface to be covered.



Figure 5-63 To find the surface area of a cone.

$$\text{slant height} = \sqrt{5^2 + 20^2} = \sqrt{425} = 20.62 \text{ feet}$$

$$\text{circumference of base} = 3.1416 \times 10 = 31.416 \text{ feet}$$

$$\begin{aligned}\text{area of conical surface} &= 31.416 \times {}^{1}/_{2} \times 20.62\\ &= 324 \text{ square feet}\end{aligned}$$

Problem 20

To find the area of the frustum of a cone (see Figure 5-64)

Rule: Multiply one-half the slant height by the sum of the circumference.

Example A tank is 12 feet in diameter at the base, 10 feet at the top, and 8 feet high. What is the area of the slant surface?

$$\begin{aligned}\text{circumference of 10-foot diameter} &= 3.1416 \times 10\\ &= 31.416 \text{ feet}\end{aligned}$$



Figure 5-64 To find the area of the frustum of a cone.

$$\text{circumference of 12-foot diameter} = 3.1416 \times 12$$

$$= 37.7 \text{ feet}$$

$$\text{sum of circumferences} = 69.1 \text{ feet}$$

$$\text{slant height} = \sqrt{1^2 + 8^2} = \sqrt{65} = 8.12$$

$$\text{slant surface} = \text{sum of circumferences} \times {}^1\!/_2 \text{ slant height}$$

$$\text{slant surface} = 69.1 \times {}^1\!/_2 \times 8.12 = 280 \text{ square feet}$$

Measurement of Solids—Volume

Problem 21

To find the volume of a rectangular solid.

Rule: Multiply the length, width, and thickness together.

Example What is the volume of a 4-inch × 8-inch × 12-foot timber? (Before applying the rule, reduce all dimensions to feet.)

$$4 \text{ inches} = {}^1\!/_3 \text{ foot}$$

$$8 \text{ inches} = {}^2\!/_3 \text{ foot}$$

$$\text{volume of timber} = {}^1\!/_3 \times {}^2\!/_3 \times 12 = 2.67 \text{ cubic feet}$$

If the timber were a piece of oak weighing 48 pounds per cubic foot, the total weight would be calculated as follows:

$$48 \times 2.67 = 128 \text{ pounds}$$

Problem 22

To find the volume of a rectangular wedge.

Rule: Find the area of one of the triangular ends, and multiply the area by the distance between the ends.

Example An attic has the shape of a rectangular wedge. What volume storage capacity would there be for the proportions shown in Figure 5-65? In the illustration, the boundary of the attic is *LARFMS*.

$$\text{Area of triangular end } MLA = 20 \times {}^{10}/_{2} = 100 \text{ square feet}$$

$$\text{Volume of attic} = 100 \times 40 = 4000 \text{ cubic feet.}$$



Figure 5-65 To find the volume of a rectangular wedge.

Trigonometry

Trigonometry is that branch of mathematics that deals with the relations that exist between the sides and angles of triangles, and more especially with those methods of calculating the required parts of triangles from given parts. The only branch of trigonometry useful to the carpenter and builder is *plane trigonometry*, where the lines in the triangles are straight and where they all lie in the same plane.

The six elements (or parts) in every triangle are three sides and three angles. The sum of the three angles, no matter what the lengths of the sides, will always be equal to 180 degrees.

When any three of the six parts are given, provided one or more of them are sides, the other three are calculable. The angles are measured in circular measure: in degrees (°), minutes (′), and seconds (″). The term *degree* has no numerical value. In trigonometry it simply means $^1/_{360}$ of a circle, nothing more.

To the student of trigonometry, any two radii that divide a circle into anything more than 0° or less than 360° form an angle.

The first 90° division is called the *first quadrant.* Angles in this quadrant are the *acute angles* (see Figure 5-66A) mentioned earlier in this chapter. Angles from 90° to 180° are in the *second quadrant.* These are the *obtuse angles* (see Figure 5-66B) mentioned. Angles from 180° to 270° lie in the *third quadrant*, and angles from 270° to 360° lie in the *fourth quadrant.* Figure 5-67 shows these four quadrants. Only angles in the first and second quadrants, from 0° to 180°, will be discussed in this section. Note that a straight line may be considered as an angle of 180°. Trigonometry is actually based on geometry, but it makes use of many algebraic operations that can be used by carpenters and builders.



(A) An angle in the first quadrant is an acute angle.

(B) An angle in the second quadrant is an obtuse angle.

Figure 5-66 Acute and obtuse angles.

Trigonometric Functions

In mathematics, a *function* means a quantity that necessarily changes because of a change in another number with which it is connected



Figure 5-67 The four quadrants of a circle.

in some way. In trigonometry, it is probably less confusing to call the trigonometric functions simply *ratios*, which they truly are.

Refer to Figure 5-68 for an explanation of the following. There are six trigonometric ratios commonly used:

$$\text{Sine of angle} A = \frac{\text{opposite side}}{\text{hypotenuse}} \text{ or } \frac{BC}{AB}$$

$$\text{Cosine of angle} A = \frac{\text{adjacent side}}{\text{hypotenuse}} \text{ or } \frac{AC}{AB}$$

$$\text{Tangent of angle} A = \frac{\text{opposite side}}{\text{adjacent side}} \text{ or } \frac{BC}{AC}$$

$$\text{Cotangent of angle} A = \frac{\text{adjacent side}}{\text{opposite side}} \text{ or } \frac{AC}{BC}$$

$$\text{Secant of angle} A = \frac{\text{hypotenuse}}{\text{adjacent side}} \text{ or } \frac{AB}{AC}$$

$$\text{Cosecant of angle} A = \frac{\text{hypotenuse}}{\text{opposite side}} \text{ or } \frac{AB}{BC}$$



Figure 5-68 A right triangle illustrates the application of trigonometric ratios that are commonly used.

Note that these last three functions are only *reciprocals* of the sine, cosine, and tangent, respectively, or

$$\text{cosecant} = \frac{1}{\text{sine}}$$

$$\text{secant} = \frac{1}{\text{cosine}}$$

$$\text{cotangent} = \frac{1}{\text{tangent}}$$

If a proposition calls for multiplication by the sine of an angle, the same result will be obtained by dividing by the cosecant. It is convenient to do this in many calculations.

It is impossible in a discussion of this type to give a comprehensive table of the trigonometric ratios, although an adequate (but limited) number of trigonometric functions is presented in Table 5-25. Those who would like to follow up the information given here are advised to obtain a book of five- or six-place tables.

As an example of how trigonometric ratios are used to solve one of the carpenter's most common problems (determining the length of rafters given the rise and run), refer to Figure 5-69. The slope of the roof, in degrees, may be determined by dividing the opposite side, 12 feet, by the adjacent side, 18 feet. This is the tangent of the

Table 5-25 Natural Trigonometric Functions

Degree	*Sine*	*Cosine*	*Tangent*	*Secant*
0	0.00000	1.0000	0.00000	1.0999
1	0.01745	0.9998	0.01745	1.0001
2	0.03490	0.9994	0.03492	1.0006
3	0.05234	0.9986	0.05241	1.0014
4	0.06976	0.9976	0.06993	1.0024
5	0.08716	0.9962	0.08749	1.0038
6	0.10453	0.9945	0.10510	1.0055
7	0.12187	0.9925	0.12278	1.0075
8	0.1392	0.9903	0.1405	1.0098
9	0.1564	0.9877	0.1584	1.0125
10	0.1736	0.9848	0.1763	1.0154
11	0.1908	0.9816	0.1944	1.0187
12	0.2079	0.9781	0.2126	1.0223
13	0.2250	0.9744	0.2309	1.0263
14	0.2419	0.9703	0.2493	1.0306
15	0.2588	0.9659	0.2679	1.0353
16	0.2756	0.9613	0.2867	1.0403
17	0.2924	0.9563	0.3057	1.0457
18	0.3090	0.9511	0.3249	1.0515
19	0.3256	0.9455	0.3443	1.0576
20	0.3420	0.9397	0.3640	1.0642
21	0.3584	0.9336	0.3839	1.0711
22	0.3746	0.9272	0.4040	1.0785
23	0.3907	0.9205	0.4245	1.0864
24	0.4067	0.9135	0.4452	1.0946
25	0.4226	0.9063	0.4663	1.1034
26	0.4384	0.8988	0.4877	1.1126
27	0.4540	0.8910	0.5095	1.1223
28	0.4695	0.8829	0.5317	1.1326
29	0.4848	0.8746	0.5543	1.1433
30	0.5000	0.8660	0.5774	1.1547
31	0.5150	0.8572	0.6009	1.1663
32	0.5299	0.8480	0.6249	1.1792
33	0.5446	0.8387	0.6494	1.1924
34	0.5592	0.8290	0.6745	1.2062
35	0.5736	0.8192	0.7002	1.2208
36	0.5878	0.8090	0.7265	1.2361

(continued)

Table 5-25 (*continued*)

Degree	***Sine***	***Cosine***	***Tangent***	***Secant***
37	0.6018	0.7986	0.7536	1.2521
38	0.6157	0.7880	0.7813	1.2690
39	0.6293	0.7771	0.8098	1.2867
40	0.6428	0.7660	0.8391	1.3054
41	0.6561	0.7547	0.8693	1.3250
42	0.6691	0.7431	0.9004	1.3456
43	0.6820	0.7314	0.9325	1.3673
44	0.6947	0.7193	0.9657	1.3902
45	0.7071	0.7071	1.0000	1.4142
46	0.7193	0.6947	1.0355	1.4395
47	0.7314	0.6820	1.0724	1.4663
48	0.7431	0.6691	1.1106	1.4945
49	0.7547	0.6561	1.1504	1.5242
50	0.7660	0.6428	1.1918	1.5557
51	0.7771	0.6293	1.2349	1.5890
52	0.7880	0.6157	1.2799	1.6243
53	0.7986	0.6018	1.3270	1.6616
54	0.8090	0.5878	1.3764	1.7013
55	0.8192	0.5736	1.4281	1.7434
56	0.8290	0.5592	1.4826	1.7883
57	0.8387	0.5446	1.5399	1.8361
58	0.8480	0.5299	1.6003	1.8871
59	0.8572	0.5150	1.6643	1.9416
60	0.8660	0.5000	1.7321	2.0000
61	0.8746	0.4848	1.8040	2.0627
62	0.8829	0.4695	1.8807	2.1300
63	0.8910	0.4540	1.9626	2.2027
64	0.8988	0.4384	2.0503	2.2812
65	0.9063	0.4226	2.1445	2.3662
66	0.9135	0.4067	2.2460	2.4586
67	0.9205	0.3907	2.3559	2.5598
68	0.9272	0.3746	2.4751	2.6695
69	0.9336	0.3584	2.6051	2.7904
70	0.9397	0.3420	2.7475	2.9238
71	0.9455	0.3256	2.9042	3.0715
72	0.9511	0.3090	3.0777	3.2361

(continued)

Table 5-25 (*continued*)

Degree	***Sine***	***Cosine***	***Tangent***	***Secant***
73	0.9563	0.2924	3.2709	3.4203
74	0.9613	0.2756	3.4874	3.6279
75	0.9659	0.2588	3.7321	3.8637
76	0.9703	0.2419	4.0108	4.1336
77	0.9744	0.2250	4.3315	4.4454
78	0.9781	0.2079	4.7046	4.8097
79	0.9816	0.1908	5.1446	5.2408
80	0.9848	0.1736	5.6713	5.7588
81	0.9877	0.1564	6.3138	6.3924
82	0.9903	0.1392	7.1154	7.1853
83	0.9925	0.12187	8.1443	8.2055
84	0.9945	0.10453	9.5144	9.5668
85	0.9962	0.08716	11.4301	11.474
86	0.9976	0.06976	14.3007	14.335
87	0.9986	0.05234	19.0811	19.107
88	0.9994	0.03490	28.6363	28.654
89	0.9998	0.01745	57.2900	57.299
90	1.0000	Inf.	Inf.	Inf.
	–	–	–	–

angle *A* and is equal to $^{12}/_{18}$ or .6667. From Table 5-25, angle *A* is determined to be 33° 42′. The length of the rafter may be determined by the ratio:

$$\text{secant} = \frac{\text{hypotenuse}}{\text{adjacent side}}$$

or the hypotenuse (the length of the rafter) is equal to the following:

Secant 33°42′ × adjacent side

The secant of 33°42′ is equal to 1.2020. Therefore, the calculation for the length of the rafter is the following:

$$1.2020 \times 18 = 21.64 \text{ feet} = 21 \text{ feet } 7^3/_{16} \text{ inches}$$

Since the opposite side is known to be 12 feet, the calculation could just as easily be made by using the cosecant function.

Table 5-26 shows the slopes (in degrees) for all regular roof pitches. These pitches range from 12 × 1 to 12 × 12, and the three



Figure 5-69 Trigonometric ratios may be used to determine the lengths of rafters for a roof.

Table 5-26 Roof Pitches in Degrees and Minutes (Measured from the Horizontal)

Pitch	*Sine*	*Cosine*	*Tangent*
12 × 1 = 4° 46′	0.083098	0.996541	0.083386
12 × 2 = 9° 28′	0.164474	0.986381	0.166745
12 × 3 = 14° 2′	0.242486	0.970155	0.249946
12 × 4 = 18° 26′	0.316201	0.948692	0.333302
12 × 5 = 22° 37′	0.384564	0.923098	0.416601
12 × 6 = 26° 34′	0.444635	0.895712	0.496404
12 × 7 = 30° 15′	0.503774	0.863836	0.583183
12 × 8 = 33° 41′	0.554602	0.832115	0.666497
12 × 9 = 36° 53′	0.600188	0.799859	0.750366
12 × 10 = 39° 46′	0.639663	0.768656	0.832183
12 × 11 = 42° 31′	0.675805	0.737081	0.916866
12 × 12 = 45° 00′	0.707107	0.707107	1.000000

main trigonometric ratios (sine, cosine, and tangent) are provided for each pitch.

Other typical examples of how trigonometric ratios can aid carpenters are shown in the following problems.

Problem 1

A grillwork consisting of radial and vertical members is to be built in a semicircular opening with a radius of 6 feet, as shown in Figure 5-70. Find the lengths of the vertical pieces MS and LF.



Figure 5-70 The method of finding the length of vertical pieces in grillwork with the aid of trigonometric relations.

For triangle OMS, the hypotenuse is known to be 6 feet, and angle O is 30°. Line MS is the opposite side of the triangle, and

$$\text{opposite side} = 30°, \text{ or}$$

$$\frac{\text{opposite side}}{\text{hypotenuse}} = \text{sine } 30° \times \text{hypotenuse}$$

$$\text{sine } 30° = 0.500$$

This is the calculation:

$$\text{opposite side} = 0.500 \times 6 = 3 \text{ feet}$$

For triangle *OLF*, the hypotenuse is 6 feet, and angle *O* is 60°. Line *LF* is the opposite side, and

$$\frac{\text{opposite side}}{\text{hypotenuse}} = 60°,$$

$$\text{or opposite side} = 60° \times \text{hypotenuse}.$$

$$\text{sine } 60° = 0.866$$

This is the calculation:

$$\text{opposite side} = 0.866 \times 6 = 5.196 \text{ feet} = 5 \text{ feet } 2^3/_8 \text{ inches}$$

Problem 2

When laying out the grillwork in Figure 5-70, how far must the members LF and MS be spaced from the center O to be vertical?

The hypotenuse is known to be 6 feet and the length of adjacent side *OF* is to be found.

$$\frac{\text{adjacent side}}{\text{hypotenuse}} = \cos 60°, \text{ or}$$

$$\text{adjacent side} = \cos 60° \times \text{hypotenuse}.$$

$$\cos 60° = 0.500$$

This is the calculation:

$$\text{adjacent side } OF = .500 \times 6 = 3 \text{ feet}$$

For the length of the adjacent side OS

$$\frac{\text{adjacent side}}{\text{hypotenuse}} = \cos 30°, \text{ or}$$

$$\text{adjacent side} = \cos 30° \times \text{hypotenuse}.$$

$$\cos 30° = 0.866$$

This is the calculation:

$$\text{Adjacent side } OS = .866 \times 6 = 5.196 \text{ feet}$$
$$= 5 \text{ feet } 2^3/_8 \text{ inches}$$

Problem 3

A bridge is to be constructed from the top of a building to an opening in the roof of an adjacent building, as in Figure 5-71. If the rise OF to the point of entry L is 15 feet and the pitch of the roof is $^1/_2$, what length beams FL are required?



Figure 5-71 The method of finding the distance from one side of a building to a given point on an adjacent roof by employing trigonometric relations.

From Table 5-26, $^1/_2$ pitch, or 12 inches × 12 inches, is 45°. The adjacent side *OF* is known to be 15 feet. The required length of the opposite side = adjacent side × tan 45°. This is the calculation:

$$\text{opposite side } FL = 15 \times 1.00 = 15 \text{ feet}$$

Problem 4

When estimating the amount of roofing material necessary to cover the side of the roof from O to L in Figure 5-71, what is the distance from O to L?

It is required to find the hypotenuse with the adjacent side and included angle being given.

$$\frac{\text{hypotenuse}}{\text{adjacent side}} = \text{secant angle 0, or}$$

$$\text{hypotenuse} = 1.4142 \times 15 = 21.213 \text{ feet}$$

$$= 21 \text{ feet } 2^9/_{16} \text{ inches.}$$

Table 5-27 Functions of Numbers

No.	Square	Cube	Square Root	Cubic Root	Logarithm	1000 × Reciprocal	No. = Diameter	
							Circum.	Area
1	1	1	1.0000	1.0000	0.00000	1000.000	3.142	0.7854
2	4	8	1.4142	1.2599	0.30103	500.000	6.283	3.1416
3	9	27	1.7321	1.4422	0.47712	333.333	9.425	7.0686
4	16	64	2.0000	1.5874	0.60206	250.000	12.566	12.5664
5	25	125	2.2361	1.7100	0.69897	200.000	15.708	19.6350
6	36	216	2.4495	1.8171	0.77815	166.667	18.850	28.2743
7	49	343	2.6458	1.9129	0.84510	142.857	21.991	38.4845
8	64	512	2.8284	2.0000	0.90309	125.000	25.133	50.2655
9	81	729	3.0000	2.0801	0.95424	111.111	28.274	63.6173
10	100	1000	3.1623	2.1544	1.00000	100.000	31.416	78.5398
11	121	1331	3.3166	2.2240	1.04139	90.9091	34.558	95.0332
12	144	1728	3.4641	2.2894	1.07918	83.3333	37.699	113.097
13	169	2197	3.6056	2.3513	1.11394	76.9231	40.841	132.732
14	196	2744	3.7417	2.4101	1.14613	71.4286	43.982	153.938
15	225	3375	3.8730	2.4662	1.17609	66.6667	47.124	176.715
16	256	4096	4.0000	2.5198	1.20412	62.5000	50.265	201.062
17	289	4913	4.1231	2.5713	1.23045	58.8235	53.407	226.980
18	324	5832	4.2426	2.6207	1.25527	55.5556	56.549	254.469
19	361	6859	4.3589	2.6684	1.27875	52.6316	59.690	283.529
20	400	8000	4.4721	2.7144	1.30103	50.0000	62.832	314.159

21	441	9261	4.5826	2.7589	1.32222	47.6190	65.973	346.361
22	484	10648	4.6904	2.8020	1.34242	45.4545	69.115	380.133
23	529	12167	4.7958	2.8439	1.36173	43.4783	72.257	415.476
24	576	13824	4.8990	2.8845	1.38021	41.6667	75.398	452.389
25	625	15625	5.0000	2.9240	1.39794	40.0000	78.540	490.874
26	676	17576	5.0990	2.9625	1.41497	38.4615	81.681	530.929
27	729	19683	5.1962	3.0000	1.43136	37.0370	84.823	572.555
28	784	21952	5.2915	3.0366	1.44716	35.7143	87.965	615.752
29	841	24389	5.3852	3.0723	1.46240	34.4828	91.106	660.520
30	900	27000	5.4772	3.1072	1.47712	33.3333	94.248	706.858
31	961	29791	5.5678	3.1414	1.49136	32.2581	97.389	754.768
32	1024	32768	5.6569	3.1748	1.50515	31.2500	100.531	804.248
33	1089	35937	5.7446	3.2075	1.51851	30.3030	103.673	855.299
34	1156	39304	5.8310	3.2396	1.53148	29.4118	106.814	907.920
35	1225	42875	5.9161	3.2711	1.54407	28.5714	109.956	962.113
36	1296	46656	6.0000	3.3019	1.55630	27.7778	113.097	1017.88
37	1369	50653	6.0828	3.3322	1.56820	27.0270	116.239	1075.21
38	1444	54872	6.1644	3.3620	1.57978	26.3158	119.381	1134.11
39	1521	59319	6.2450	3.3912	1.59106	25.6410	122.522	1194.59
40	1600	64000	6.3246	3.4200	1.60206	25.0000	125.66	1256.64
41	1681	68921	6.4031	3.4482	1.61278	24.3902	128.81	1320.25
42	1764	74088	6.4807	3.4760	1.62325	23.8095	131.95	1385.44
43	1849	79507	6.5574	3.5034	1.63347	23.2558	135.09	1452.20
44	1936	85184	6.6332	3.5303	1.64345	22.7273	138.23	1520.53

(continued)

Table 5-27 *(continued)*

No.	**Square**	**Cube**	**Square Root**	**Cubic Root**	**Logarithm**	**1000 × Reciprocal**	**No. = Diameter**	
							Circum.	**Area**
45	2025	91125	6.7082	3.5569	1.65321	22.2222	141.37	1590.43
46	2116	97336	6.7823	3.5830	1.66276	21.7391	144.51	1661.90
47	2209	103823	6.8557	3.6088	1.67210	21.2766	147.65	1734.94
48	2304	110592	6.9282	3.6342	1.68124	20.8333	150.80	1809.56
49	2401	117649	7.0000	3.6593	1.69020	20.4082	153.94	1885.74
50	2500	125000	7.0711	3.6840	1.69897	20.0000	157.08	1963.50
51	2601	132651	7.1414	3.7084	1.70757	19.6078	160.22	2042.82
52	2704	140608	7.2111	3.7325	1.71600	19.2308	163.36	2123.72
53	2809	148877	7.2801	3.7563	1.72428	18.8679	166.50	2206.18
54	2916	157464	7.3485	3.7798	1.73239	18.5185	169.65	2290.22
55	3025	166375	7.4162	3.8030	1.74036	18.1818	172.79	2375.83
56	3136	175616	7.4833	3.8259	1.74819	17.8571	175.93	2463.01
57	3249	185193	7.5498	3.8485	1.75587	17.5439	179.07	2551.76
58	3364	195112	7.6158	3.8709	1.76343	17.2414	182.21	2642.08
59	3481	205379	7.6811	3.8930	1.77085	16.9492	185.35	2733.97
60	3600	216000	7.7460	3.9149	1.77815	16.6667	188.50	2827.43
61	3721	226981	7.8102	3.9365	1.78533	16.3934	191.64	2922.47
62	3844	238328	7.8740	3.9579	1.79239	16.1290	194.78	3019.07
63	3969	250047	7.9373	3.9791	1.79934	15.8730	197.92	3117.25
64	4096	262144	8.0000	4.0000	1.80618	15.6250	201.06	3216.99

65	4225	274625	8.0623	4.0207	1.81291	15.3846	204.20	3318.31
66	4356	287496	8.1240	4.0412	1.81954	15.1515	207.35	3421.19
67	4489	300763	8.1854	4.0615	1.82607	14.9254	210.49	3525.65
68	4624	314432	8.2462	4.0817	1.83251	14.7059	213.63	3631.68
69	4761	328509	8.3066	4.1016	1.83885	14.4928	216.77	3739.28
70	4900	343000	8.3666	4.1213	1.84510	14.2857	219.91	3848.45
71	5041	357911	8.4261	4.1408	1.85126	14.0845	223.05	3959.19
72	5184	373248	8.4853	4.1602	1.85733	13.8889	226.19	4071.50
73	5329	389017	8.5440	4.1793	1.86332	13.6986	229.34	4185.39
74	5476	405224	8.6023	4.1983	1.86923	13.5135	232.48	4300.84
75	5625	421875	8.6603	4.2172	1.87506	13.3333	235.62	4417.86
76	5776	438976	8.7178	4.2358	1.88081	13.1579	238.76	4536.46
77	5929	456533	8.7750	4.2543	1.88649	12.9870	241.90	4656.63
78	6084	474552	8.8318	4.2727	1.89209	12.8205	245.04	4778.36
79	6241	493039	8.8882	4.2908	1.89763	12.6582	248.19	4901.67
80	6400	512000	8.9443	4.3089	1.90309	12.5000	251.33	5026.55
81	6561	531441	9.0000	4.3267	1.90849	12.3457	254.47	5153.00
82	6724	551368	9.0554	4.3445	1.91381	12.1951	257.61	5281.02
83	6889	571787	9.1104	4.3621	1.91908	12.0482	260.75	5410.61
84	7056	592704	9.1652	4.3795	1.92428	11.9048	263.89	5541.77
85	7225	614125	9.2195	4.3968	1.92942	11.7647	267.04	5674.50
86	7396	636056	9.2736	4.4140	1.93450	11.6279	270.18	5808.80
87	7569	658503	9.3274	4.4310	1.93952	11.4943	273.32	5944.68

(continued)

Table 5-27 (*continued*)

No.	*Square*	*Cube*	*Square Root*	*Cubic Root*	*Logarithm*	*1000 × Reciprocal*	*No. = Diameter* *Circum.*	*No. = Diameter* *Area*
88	7744	681472	9.3808	4.4480	1.94448	11.3636	276.46	6082.12
89	7921	704969	9.4340	4.4647	1.94939	11.2360	279.60	6221.14
90	8100	729000	9.4868	4.4814	1.95424	11.1111	282.74	6361.73
91	8281	753571	9.5394	4.4979	1.95904	10.9890	285.88	6503.88
92	8464	778688	9.5917	4.5144	1.96379	10.8696	289.03	6647.61
93	8649	804357	9.6437	4.5307	1.96848	10.7527	292.17	6792.91
94	8836	830584	9.6954	4.5468	1.97313	10.6383	295.31	6939.78
95	9025	857375	9.7468	4.5629	1.97772	10.5263	298.45	7088.22
96	9216	884736	9.7980	4.5789	1.98227	10.4167	301.59	7238.23
97	9409	912673	9.8489	4.5947	1.98677	10.3093	304.73	7389.81
98	9604	941192	9.8995	4.6104	1.99123	10.2041	307.88	7542.96
99	9801	970299	9.9499	4.6261	1.99564	10.1010	311.02	7697.69

Functions of Numbers

Table 5-27 shows the functions of numbers.

Summary

All the sciences are based on arithmetic and the ability to use it. Arithmetic is the art of calculating by using numbers. A number is a total amount (or aggregate) of units. By computing the units, we arrive at a certain number or total. Similarly, a unit means a single article, often a definite group adopted as a standard of measurement (such as dozen, ton, foot, bushel, or mile).

Fractions indicate that a number or unit has been divided into a certain number of equal parts, and shows how many of these parts are to be considered. Two forms of fractions are in common usage: the decimal and the common fraction. The common fraction is written by using two numbers, one written over or alongside the other with a line between them, the lower (or second) number being called the denominator, and the upper (or first) number being called the numerator.

Geometry is a branch of mathematics that deals with space and figures in space. It is the science of the mutual relations of points, lines, angles, surfaces, and solids, which are considered as having no properties except those arising from extension and difference of situation. There are two kinds of lines—straight and curved. A straight line is the shortest distance between two points. A curved line is one that changes its direction at every point.

Trigonometry is the branch of mathematics that deals with the relations that exist between the sides and angles of triangles, especially the methods of calculating the required parts of triangles from given parts. There are six elements, or parts, in every triangle: three sides and three angles. The sum of the three angles, no matter what the lengths of the sides, will always be equal to 180 degrees.

Review Questions

1. What is the definition of arithmetic?
2. What are even numbers?
3. What are odd numbers?
4. What are fractions? How are they used?
5. What is trigonometry and how is it used in carpentry?

Chapter 6

Surveying

By definition, *surveying* means the art or science of determining the area and configuration of portions of the surface of the Earth. The two general divisions of surveying may be classified with respect to the nature of the measurements taken:

- Leveling
- Measurement of angles (transit work)

In surveying, *leveling* is the operation of determining the comparative levels of different points of land for the purpose of laying out a grade or building site, and so on, by sighting through a leveling instrument at one point to a leveling staff at another point (see Figure 6-1).

The Level

This instrument (see Figure 6-2) is employed to determine the difference in elevation between points. A common form is known as the *wye level*, so-called because its shape resembles the letter Y. It consists of a telescope mounted on two supports that from their shape are called Ys. The crossbar supporting the telescope is attached to a vertical spindle that allows it to be turned in a horizontal plane. Directly beneath the telescope and attached parallel to it is a spirit level by means of which the line of collimation of the telescope may be rendered horizontal. The *line of collimation* is the line that would connect the intersection of the crosshairs with the optical center of the objective.

Construction of the Wye Level

In construction, a circular plate is screwed to a tripod, and to this is attached a similar plate parallel to the first and connected with it by a ball-and socket joint. Four screws (sometimes only three), called *foot* or *plate screws*, hold these plates apart by resting on the lower one and passing through the other. A vertical spindle in the center of the plates supports a rod, bar, or beam, and is used to revolve the instrument. The beam is horizontal and carries at its ends two vertical standards or supports of equal size terminated by two forks of the general form of the letter Y. The inside of the Ys is Y-shaped, with an open bottom to prevent an accumulation of dirt. The top of the Ys may be closed by semicircular straps or bridles (called *clips*) that are hinged on one side and pinned on the other. The pins are tapered to permit fastening of the telescope. It is *never* clamped tightly.



Figure 6-1 The terms backsight and foresight do not necessarily mean backward and forward. Readings taken on a point of known elevation (such as a benchmark or a turning point) are called backsights, whereas readings taken on a point of unknown elevation are termed foresights. In the illustration, the backsight (to the benchmark) is + 6 feet 0 inches, and the foresight to station A is −5 feet 0 inches. The difference in the two elevations is 6 feet −5 feet = 1 foot. If the reading at station A had been greater than the 6-foot HI (height of instrument), the calculation would have shown a negative result, thereby indicating that station A was lower than the benchmark. The elevation at station B is calculated in the same manner: 6 − 3 = 3 feet. Therefore, the elevations from any number of points can be obtained in the same way, if they can be seen from the same position of the instrument. If they cannot, a new HI must be used.



Figure 6-2 A typical builder's level. *(Courtesy David White Instruments, Division of Realist, Inc.)*

The tops of the Ys and the corresponding clips are called the *rings* or *collars*, and should be of equal diameter. A *telescope* is placed on the rings that support a spirit level. A *clamping screw* just above the upper plate serves to secure the instrument in any position desired. A *tangent screw* (also above the upper plate) provides slow motion (or *vernier*) adjustment to the instrument.

The Telescope

The *objective*, or *object glass* (so-called because it faces the object looked at) is a compound lens that is made to correct spherical and chromatic aberrations of single lenses. It gathers light and forms an image at a point in the tube where crosshairs are placed. The *ocular* (or eye) *piece* is also a compound lens through which the operator looks to see a magnified view of the image. In the best precision instruments (often foreign-made), the image is often *inverted*. A good instrument worker quickly becomes accustomed to the inverted image, but most American-made instruments have an *erecting* image that shows the object right side up. Tangent screws may be used to give motion to the tubes carrying the objective and ocular.

The Crosshairs

These are made of platinum-drawn wires or spider's threads attached to a ring within the telescope at the spot where the image is formed. The ring is secured by four capstan-headed screws that pass through the telescope tube. There are commonly two hairs, one horizontal and the other vertical, with their intersection in the axis of the telescope.

Bubble Level

The spirit level attached to the telescope can be raised vertically by means of *altitude screws* at the rear end, and it may be moved laterally to a limited extent by means of *azimuth screws* at the forward end.

The Supports

These form the Ys and are supported by the bar to that they are fastened by two nuts, one above and one below. These nuts may be moved to provide an adjustment (to move the scope in a horizontal direction).

Lines of the Level

The three principal lines of a level are as follows:

- *Vertical axis*—This passes through the center of the spindle.
- *Bubble line*—The metallic supports of the spirit level are equal, and the tangent at their top or bottom is horizontal

when the bubble is centered. This tangent is the bubble line.

- *Line of collimation*—The line that would connect the intersection of the crosshairs with the optical center of the objective is the line of collimation.

The following relations must be obtained:

- The bubble line and the line of collimation must be parallel.
- The plane described by the bubble line should be horizontal, that is, perpendicular to the vertical axis.

These conditions are generally satisfied in a new level, but exposure and use may alter these relations. Therefore, occasional adjustment of the instrument may be necessary.

Adjustments of the Wye Level

Levels and transits are expensive, precision instruments and should be treated as such. Although a passable job of leveling may be done by a relatively inexperienced worker, it is questionable if a major job of adjusting should be attempted by a novice. A perfect job of adjustment is difficult, even for an experienced adjuster, and there are few instruments in perfect adjustment. For precision work, the adjustment should be checked constantly. The first relation given earlier cannot be established directly. However, it does require several adjustments.

First Adjustment

Collimating the instrument means making the line of collimation parallel to the bottom element of the collars

1. Clamp the instrument, and unclip the collars.
2. Sight at some distant point, a point that is distinct.
3. Bring the horizontal crosshair on that point.
4. Carefully turn the telescope in the collars by one-half a revolution around its axis, and sight again. If the horizontal crosshair is still on the sighted point, the telescope is collimated with regard to that crosshair. If it is off the point, bring it halfway back by means of the capstan-headed screws and the rest of the way by the plate screws.
5. Repeat the operation over another point.
6. Collimate it with regard to the other crosshair.
7. Leave the screws at a snug bearing.

Second Adjustment

This is where you set the bubble line in a plane with the bottom element of the collars.

1. Unclip the telescope, and clamp the instrument over a pair of plate screws.
2. Center the bubble by means of the plate screws.
3. Carefully (and very slowly) turn the telescope in the collars in a small arc to the right, then to the left. If the bubble moves from center, bring it back by means of the azimuth or side screws.

Third Adjustment

Setting the bubble line parallel to the bottom element of the collars.

1. Unclip the telescope, and clamp the instrument over a pair of plate screws.
2. Center the bubble by means of the plate screws.
3. Carefully take the telescope up, replacing it carefully in the Ys in the opposite direction (that is, the objective sighting in the direction where the eyepiece originally was). If the bubble has moved, bring it back halfway by means of the altitude or foot screws of the spirit level and the rest of the way by the plate screws.
4. Repeat in another direction until the adjustment is satisfactory.

The second relation is established by making the bubble line stay in the center of the graduation during a complete revolution of the instrument around its spindle.

Fourth Adjustment

Now, make the axis of the instrument (not of the telescope) vertical.

1. Pin the clips.
2. Clamp and center the bubble over a pair of plate screws.
3. Reverse the telescope over the same pair of plate screws.
4. Bring the bubble halfway back (if it has moved) by means of the plate screws.

Fifth Adjustment

Again, make the bubble remain centered during a full revolution of the instrument.

1. Center the bubble.

2. Revolve the instrument horizontally by a one-half revolution.
3. If the bubble moves, correct it halfway by means of the support screws (at the foot of the Ys). If the rings become worn and unequal, use the two-peg method of the dumpy level.

Dumpy Level Adjustment

Figure 6-3 shows the *dumpy level* (so-called because of its compactness). It is used mostly in England, although it is used to some extent in the United States because of the better stability of its adjustments over the wye level. The dumpy level differs from the wye level mainly in that the telescope of the dumpy level is permanently attached to the supports or uprights, but these uprights are adjustable. The two-peg adjustment method is as follows:

1. Drive two stakes (pegs) several hundred feet apart.
2. Set the instrument approximately halfway between them.
3. Level up and sight the rod that is held in succession on each stake. The difference in the readings is the true difference of the



Figure 6-3 A dumpy level.

elevation of the stakes, even if the instrument is not in proper adjustment.

4. Test the instrument.
5. Set it near one of the stakes (the highest one, for instance). Level up and sight the rod held on the other stake.
6. Subtract the height of the instrument from the reading. The difference should be equal to the difference of elevation of the stakes as previously found. If these differences are not equal, set the target halfway between these readings, sight on it, and center the bubble by means of the altitude screws.
7. Repeat the operation until satisfaction is obtained.

Centering the Objective and Ocular

These adjustments are made permanently by the manufacturer. Usually, four screws hold the tubes carrying the glasses. Their heads pass through the outside tube where, after permanent adjustment, they are covered by a metallic ring.

Parallax

This is the apparent motion of the crosshairs on the object sighted when the eye is moved slightly. It shows the imperfect focusing of the ocular over the crosshairs. To correct this condition, hold a white surface (such as that of a piece of paper) slightly in front of the objective, and move the ocular tube in and out until the crosshairs are perfectly defined.

Leveling Rod

This instrument, used in leveling, is usually 6$\frac{1}{2}$ feet high, graduated to hundredths of a foot and provided with a sliding target. The rod is made in two parts, arranged so that its length can be extended to 12 feet. Precision rods are of one-piece construction and have no target. Builders’ rods may be graduated in feet, inches, and eighths of an inch, with a vernier reading in 64ths of an inch. A sliding disc (called a *target*) is provided with a vernier for extremely accurate work, reading to thousandths of a foot.

In use, the rod is held in a vertical position with its lower end resting on the desired point of elevation. The target is then moved up and down until its center coincides with the crosshairs in the telescope of the level. The reading of the elevation is made from the rod on a line corresponding with the centerline of the target. There are various kinds of rods. Some are designed to be read by the rodman, while others can be read through the telescope of the level.

Methods of Leveling

The simplest type of leveling is to find the difference in level between two points that are visible from a third point, the difference in level being less than the length of the leveling rod (see Figure 6-4).



Figure 6-4 Leveling between two points whose difference in level is less than the length of the rod.

1. Set up and level the instrument at some point approximately halfway between the two points.
2. Have a worker hold the rod vertically on one of the points, and move the target up and down until its center coincides with the crosshairs of the level.
3. Take a reading. This is the HI, or height of the instrument above the benchmark *A*.
4. Turn the telescope on its spindle, have the rod held on the other point, and take a similar reading at *B*. The difference in level is equal to the difference in the readings.
5. If the difference in level is greater than the length of the rod, use the method shown in Figure 6-5. Divide the distance between the two points into sections of such length that the difference in level between the dividing points *A*, *B*, and *C* (called *stations*) are less than the length of the rod. Set up and level between points *A* and *B*.
6. Measure the distance *Aa* that is called *backsight*. Then, reverse the telescope, and take reading *Bb* that is called *foresight*.



Figure 6-5 Leveling between points whose difference in level is greater than the length of the rod.

7. Next, set up and level between *B* and *C*, and take readings *Bb′* and *Cc*.
8. Repeat the operation between *C* and *D*, taking readings *Cc′* and *Dd*. The difference in level between stations *A* and *D* is equal to the sum of the differences between the intermediate stations. That is, this difference equals $(Aa - Bb) + (Bb' - Cc) - (Cc' - Dd)$, or $(Aa + Bb' + Cc') - (Bb + Cc + Dd)$.

Usually, you'll have to find the relative elevations of several points, as in grading work, in which case it is necessary to keep more elaborate notes and to measure distances between the stations. The method employed for this type of leveling is shown in Figure 6-6, and the field notes are recorded as shown in Table 6-1.



Figure 6-6 Finding the relative elevations of several points in rough terrain.

Table 6-1 Field Notes (Corresponding to the Operations Illustrated in Figure 6-6)

Station	***Distance***	***Backsight***	***Height of Instrument***	***Foresight***	***Elevation***	***Remarks***
A	0	4.2	104.2	.....	100.0	Bench mark, top of hydrant.Turning point
B	100	.....	.....	10.1	94.1	
C	60	.....	.....	7.3	96.9	
D	50	.....	.....	5.8	98.4	
T	.....	4.1	99.1	9.2	95.1	
E	70	6.8	.....	.....	92.3	
F	110	.....	.....	9.5	89.6	
G	80	.....	.....	11.5	87.6	

1. Assume a datum or reference line below the elevation of the lowest station, and refer all elevations to this line. Start at some permanently fixed point (such as a mark on a building or the top of a hydrant). This is called a *benchmark*.
2. Let *A* in Figure 6-6 be the benchmark, and assume a datum line 100 feet below the level of *A*.
3. Start with the instrument between *A* and *B*, and take a backsight on *A*. The distance *Aa* is found to be 4.2 feet, which, when added to 100 feet, gives the height of the instrument.
4. Next, take foresights on *B*, *C*, and *D*, and record these readings in the proper column. Readings *Bb, Cc*, and so on, subtracted from the height of the instrument, will give the elevations at *B*, *C*, and so on. This is done, and the results are recorded in the proper column of field notes.
5. The ground falls away so rapidly beyond *D* that it is necessary to set up the level farther along and, therefore, establish a new height of instrument. This is done by holding the rod at some convenient point (such as at *T*) called the *turning point*, and taking a foresight, which measures the distance *Tt* (9.2 feet).
6. The level is then set up in its second position between *E* and *F*, and a backsight is taken on the rod in the same position, which gives the distance Tt' (4.1 feet).
7. The distance $t't$ then equals $9.2 - 4.1 = 5.1$ feet, and this is subtracted from the previous height of instrument, thus giving the new *HI*, that is $104.2 - 5.1 = 99.1$ feet.

8. A backsight is now taken on *E*, and foresights are taken on *F* and *G*. These are recorded in the proper columns, and the elevations are found by subtracting these distances from the new *HI*.
9. The horizontal distances between the stations are measured with a tape and recorded in the second column.
10. When plotting a cross-section from notes kept in this manner, the datum line is drawn first, and perpendiculars are erected at points corresponding to the different stations. The proper elevations are then indicated on these vertical lines, and a contour line is drawn through the points so marked.

Directions for Using Level

Note carefully the following mode of procedure in leveling:

1. Center the bubble over one pair of plate screws, then over the other pair. Plate screws should have a snug bearing. When looking at the bubble or at the crosshairs, the eyes should look naturally (that is, without strain). Try to observe with both eyes open.
2. Adjust the eyepiece to the crosshairs for parallax.
3. Turn the instrument toward the target. It is better to level up facing the target.
4. Look again at the bubble.
5. Sight the target, and have it set right by motions according to a prearranged code with the worker holding the rod.
6. Look again at the bubble.
7. Read the rod or direct the target from the intersection of the crosshairs only.
8. Approve the target when sure.
9. Have the height of the target called out by the worker holding the rod.
10. Enter this height in the field book.
11. Quickly, make needed calculations.
12. Motion the worker holding the rod to a new station or to stay for a turning point and backsight, and move yourself to another position.

The following additional hints will also be useful:

- *Guarding against the sun*—Draw the telescope shade, or use an umbrella or a hat.

- *Length of sights*—Avoid sights too short and too long (250 to 350 feet should be the limit of the sights).
- *Equal sights*—The length of the backsight should practically be the same as the length of the foresight. This may be approximated by pacing, or by sighting with the stadia crosshairs in the telescope.
- *Long sights*—When sights longer than the maximum allowable in one direction only are unavoidable, correction should be made for curvature.
- *Leveling up or down a steep slope*—The leveler, after some practice, will place the instrument to take a reading near the top or the bottom of the rod (as the case may be), thus gaining vertical distance, but this produces unequal sights. The leveler may also follow a zig-zag course.
- *Leveling across a large body of water*
  - *A running stream*—Drive a stake to the water surface on each side of the stream and in a direction normal to the flow, although the line may not run so. Take a foresight reading on the first, a backsight reading on the second, and continue to and along the line. The elevations of the two stakes may be assumed equal.
  - *Across a pond*—If a pond or lake is too wide to ensure a good sighting across, use essentially the same method as for a stream. Drive stakes on each side and to the water surface. Take a foresight reading on the first and a backsight reading on the second.
- *Across a wall*—Take a foresight reading on the rod set on a stake, driven to the natural surface on the first side of the wall. Measure the height of the wall above the stake, and enter it as a backsight reading. Drive a stake to the natural surface on the second side of the wall. Measure the height of the wall on that side above the stake. Enter it as a foresight reading. Set the rod on the stake. Take a sight on it (which will be a backsight reading). Continue using this method until the leveling has been completed.
- *In underbrush*—If it cannot be cut down on the line of sight, find a high place or provide one by piling logs, rocks, and so on, to set the instrument on.
- *Through swamp*—Push the legs of the tripod down as far as possible. The leveler lies on his or her side. Two workers may

be necessary at the level. If the ground is still unsafe, drive stakes or piles to support the instrument.

- *Elevations taken at road crossings*—Take elevations both ways for some distance.
- *Elevations taken at river crossings*—Take elevations of high-water marks and flood marks, with the dates of it. Question the local residents for these dates. Also, ask for dates and data of extreme low water.
- *Proper length of sights*—This will depend on the distance at which the rod appears distinct and on the precision required. Under ordinary conditions, sights should not exceed 300 feet where elevations are required to the nearest .01 foot, and even at a much shorter distance, the boiling of the air may prevent a precision reading of this degree.
- *Correction for refraction and earth curvature*—A level line is a curved line at which every point is perpendicular to the direction of gravity, and the line of sight of a leveling instrument is tangent to this curve. This makes it necessary to consider this curve in some leveling operations. If reasonable care is used to make the lengths of backsights and foresights approximately equal, this aberration is self-correcting. However, in extremely long lines, it is approximately 2 inches in one-half mile, or about $^2/_3 d^2$, in feet, where d is equal to the distance, in miles. This correction is usually combined with that for refraction. The combined correction is $547d^2$, and it is *negative*.

Trigonometric Leveling

Finding the difference in elevation of two points by means of the horizontal distance between them and the vertical angle is called *trigonometric leveling*. It is used chiefly in determining the elevation of triangulation stations and in obtaining the elevation of a plane-table station from any visible triangulation point of known elevation.

In triangulation work, the vertical angles are usually measured at the same time the horizontal angles are measured to obtain the elevations of triangulation points as well as their horizontal positions. The vertical angle is measured to some definite point on the signal whose height above the center mark of the station was determined when the signal was erected. The height of the instrument above its station should be measured and recorded.

In the most exact work, the angles are measured with a special vertical circle instrument. In less precise work, an ordinary Theodolite, whose vertical arc reads by verniers to 30 seconds or to 20 seconds, may be used, but with such instruments, only single readings can be made. The best results with such an instrument are obtained by taking the average of several independent readings, one-half of which are taken with the telescope direct and the other half with the telescope inverted. In every case, the *index correction* (or reading of the vertical arc when the telescope is level) must be recorded.

The Transit

This instrument is designed and used for measuring both horizontal and vertical angles. It consists of a telescope mounted in standards that are attached to a horizontal plate (called the *limb*). Inside the limb, and concentric with it, is another plate (called the *vernier plate*). The lower plate or limb turns on a vertical spindle or axis that fits into a socket in the tripod head. By means of a clamp and a tangent screw, it may be fastened in any position and made to move slowly through a small arc.

The circumference of this plate is usually graduated in divisions of either one-half or one-third of one degree, and in the common form of transit, these divisions are numbered from one point on the limb in both directions around to the opposite point, which is 180 degrees. The graduation is generally concealed beneath the plate above it, except at the verniers. This upper plate is the vernier plate that turns on a spindle fitted into a socket in the lower plate. It is also provided with a clamp by means of which it can be held in any position and with a tangent screw by which it can be turned through a small arc. A *vernier* is a device for reading smaller divisions on the scales than could otherwise be read.

The transit is generally provided with a compass so that the bearing of any given line with the magnetic meridian may be determined if desired. It also has a spirit level attached to the telescope, so that it may be brought to a horizontal position and made to serve as a level. Figure 6-7 shows a typical transit.

Construction of the Transit

Figure 6-8 shows the general features of the transit construction. The following sections describe these features.



Figure 6-7 Typical transit.

Parallel Plates

There are two *plates*, one upper and one lower. The lower plate *A* is generally formed with two parts. The outside part is a flat ring and is screwed to the tripod head. The inside part is another flat ring of a diameter larger than the opening in the outside part and has a central dome, *C*, that is perforated on the top. The inside part is movable and rests on the under side of the outside part. The upper plate *B* is generally made in the form of a central nut, with four arms at right angles (or three at 120°). The upper plate carries an inverted conical shell, the lower portion of which passes through the perforation in the dome of the inside part of the lower plate, where it expands into a spherical shape and thus forms a ball joint with the lower plate. This spherical member is perforated in the center to allow the passage of a plumb-bob string.

Foot Screws

The two plates are connected by four-foot (sometimes only three) screws *F* in order to clamp the lower and upper plates (making them fast with each other and with the inverted shell) and to serve



Figure 6-8 The transit. In the illustration, A represents the lower plate; B, the upper plate; C, the central dome; D, the divided limb; E, the spindle; F, the foot screws; G, foot-screw cups; H, the vernier plate; J, the compass circle; K, the clamp-screw vernier plate to divided limb; L, the tangent screw; M and N, spirit levels; O, standards or supports; P, the horizontal shaft; Q, the vertical arc; R, the objective; S, the ocular; T, the telescope; U, racks and pinions; V, the adjustable cross-hair ring; v, the divided-limb vernier; v′, the vertical-arc vernier; X, the spirit level; Y, the gradienter; and Z, the scaled index.

in leveling the instrument. The screws pass through the ends of the arms of the upper plate. They are surmounted by dust caps. There the feet fit into small cups, *G*, that rest on the top surface of the lower plate to avoid wear.

Shifting Center

Since these cups, as well as the central part of the lower plate, may be moved (after slightly loosening the foot screws), a slight motion may be given to the instrument to better set it over a given point of the ground. This arrangement is called a *shifting center*.

Outer Spindle

A second conical shell fits and may revolve in the conical shell attached to the upper plate. It is the outer spindle, and it carries projections to form attachments with the other parts of the transit.

Divided Limb

The upper portion of the outer spindle terminates in a horizontal disc of plate *D*, the limb of which is divided into 360°, subdivided into one-half, one-third, or one-quarter of one degree. Every ten degrees are numbered, either from 0° to 360° or from 0° to 180°, either way. The degree marks are a little longer than the subdivisions, and every fifth degree has a mark slightly longer yet.

Lower Motion

The outer spindle and the divided limb are also called the *lower motion*.

Inner Spindle

A solid inverted cone fits into the outer spindle and may revolve in it. It is the *inner spindle*, and, like the outer one, it is provided with some projections for similar purposes.

Vernier Plate

The upper portion of the inner spindle projects farther than the divided limb and also carries a horizontal disc, H, that moves in a plane parallel to the divided limb (that it covers), except for two rectangular openings in opposite directions through which the divisions of the limb may be seen. These openings each carry a vernier *v* by means of which the subdivisions of degrees are again divided. Some verniers read to 1 minute, others to 0.5 minute, and some to 10 seconds. To facilitate the reading of the vernier, the openings are sometimes fitted with a reflector and a magnifying glass.

Upper Motion

The inner spindle and vernier plate *H* are also called the *upper motion*. The vernier plate carries a compass circle, shown at *J*.

Compass Circle

This consists of a circular box, the bottom of which carries at its center a sharp pivot of hard metal (hard steel or iridium) on which a magnetic needle approximately 5 inches long is balanced by an agate cup fixed in the middle of its length (see Figure 6-9). The needle



Figure 6-9 Two typical compass boxes. The compass circles are graduated to one-half degrees and numbered in quadrants. The variation plate is provided so that the magnetic declination may be set accurately. The cardinal points shift with the graduated circle. *(Courtesy C. L. Berger & Sons, Inc.)*

is strongly magnetized. Its north end is distinguished by color or ornamentation, and its balance is regulated by a small coil of fine wire wound around one arm that can be shifted. The limb that is formed by the edge of the sides of the box is divided into 360° with half degrees shown. They are numbered from two zeros marked at the ends of a diameter to 90° right and left. The bottom of the box is marked with two rectangular diameters corresponding to the graduations 0° and 90° of the vernier and two other diameters at 45° to the first.

The forward end of the diameter marked 0° is designated by the letter N, and the rear end is designated by the letter S, corresponding to north and south. The ends of the transverse diameter marked 90° are designated by the letters E on the left and W on the right, corresponding to east and west. Note that this designation is the reverse of the standard mariner's compass. Since the telescope is fixed to sight from south to north, the compass indicates the direction of the sighting. When set to an ordinary surveyor's compass, the forward end of the frame carries a vernier and a tangent screw to read fractions smaller than one-half degree.

Controlling Clamps

A screw *K* permits clamping of the vernier plate *H* to the divided limb *D*. Another screw attached to the upper plate permits clamping of the divided limb to the upper plate.

Tangent Screws

One *tangent* (or slow motion) *screw L* accompanies each clamp screw. It is used to complete the clamping at the exact spot where the clamp is to be made.

Spirit Levels

The *spirit levels* are attached to the vernier plate—one level *M* in front (north point of the box), the other *N* on the side—thus forming an angle of 90°.

Standards

The vernier plate carries two vertical *standards* or supports *O*, which are shaped like an inverted V and placed one on each side. The center of their legs is just opposite the 90° graduation of the compass box. They are made equal.

Horizontal Axis

The standards carry between and on the top of them a movable *horizontal axis P*.

Vertical Code

To the horizontal axis is attached, by means of a clamp screw, a vertical circle or arc, *Q*, that is divided like the horizontal circle in its vertical motion just touches a circular vernier v' carried by the left standard together with a slow-motion screw.

Telescope

In the middle of the horizontal axis and perpendicular to it is attached a *telescope T* of a description similar to that of the engineer's level, with an objective *R* and an ocular *S*, racks and pinions *U* for their motions, and an adjustable crosshairs ring V, with ordinary and stadia hairs.

Telescope Level

An adjustable spirit level *X* is also attached to the under part of the telescope, as in the engineer's level. This permits the transit to also be used as a leveling instrument, if necessary.

Motions of the Telescope

The telescope can function over the full range of the horizon and can measure any horizontal angle. In addition, since the telescope is on a horizontal axis endowed with free motion, it may move in a vertical plane carrying with it the vertical arc, and it can, therefore, measure vertical angles. In the horizontal motion, the vertical crosshair of the telescope is brought exactly on the point sighted by means of the slow-motion screw *L*, carried by the vernier plate *H*. In the vertical motion, the horizontal crosshair of the telescope is brought exactly on the point sighted by means of the slow-motion screw carried on the inside of the left-hand support and by moving the vertical circle.

Lines of a Transit

The following are the principal lines of a transit:

- Vertical axis
- Horizontal axis
- Plate level line
- Attached level line
- Line of collimation

Vertical Axis

This vertical line passes through the center of the spindle *E* (see Figure 6-8).

Horizontal Axis

The axis *P* (see Figure 6-8) of the shaft by which the telescope rests on the supports; it must be made horizontal.

Plate Level Line

The top or bottom lines of the plate level case *N* (see Figure 6-8). These are level when the bubble is centered.

Attached Level Line

The level line of the bubble level *X* (see Figure 6-8) attached to the telescope. It is employed only when the instrument is used as an engineer's level.

Line of Collimation

The line determined by the optical center of the objective and the intersection of the crosshairs.

Relations Between the Lines of a Transit

The following relations must be obtained:

- The plate levels must be perpendicular to the vertical axis.
- The line of collimation must be perpendicular to the horizontal axis.

- The horizontal axis must be perpendicular to the vertical axis.
- The attached level line and the line of collimation must be parallel.
- The zero of the vertical circle must correspond to the zero of the vernier when the telescope is horizontal.

Adjustments of the Transit

The following sections describe the necessary adjustments of the transit.

First Adjustment

Make the axis of the spindle vertical and the planes of the plates perpendicular to it.

1. Set one level over a pair of plate screws. The other level will thus be set over the other pair.
2. Level up both levels by means of the plate screws.
3. Turn the vernier plate around by a one-half revolution. If the bubbles remain centered during the motion, the vernier plate is in adjustment. If they have moved, bring them halfway back by means of the adjusting screws and the rest of the way by means of the foot screws.
4. Repeat the operation, and determine if the bubbles remain centered when revolving the divided circle. If they do not, the plates are not parallel, and the transit must be sent to the manufacturer for repairs.

Second Adjustment

Collimate the telescope.

1. Set up the transit in the center of open and practically level ground. Carefully level the instrument.
2. Drive a stake or pin approximately 200 or 300 feet away.
3. Measure the distance.
4. Take a sight on that point, and clamp the plates.
5. Revolve the telescope vertically (in altitude) by one-half a revolution, thus reversing the line of sight.
6. Measure in the new direction the same distance as first measured, and drive a pin.
7. Unclamp and revolve the vernier plate by one-half a horizontal revolution.

8. Sight again at the first point and clamp.
9. Again, revolve the telescope vertically by one-half a revolution. If the line of sight falls on the pin, the telescope is collimated. If not, drive a new pin on the last sight at the same distance as before, and drive another pin at one-fourth the distance between the first pin and the second.
10. Move the vertical crosshair by means of the capstan-headed screw and an adjusting pin, until the intersection of the crosshairs covers the last pin set.
11. Repeat the operation to be certain of collimation.

Third Adjustment

Adjust the horizontal axis so that the line of collimation will move in a vertical plane.

1. Level up carefully and sight on a high, well-defined point (such as a corner of a chimney) and clamp.
2. Slowly move the telescope down until it sights the ground, and drive a pin there.
3. Unclamp. Revolve the vernier plate one-half of a revolution, and revolve the telescope vertically one-half of a revolution, thereby reversing the line of sight.
4. Look again at the high point and clamp.
5. Slowly move the telescope down until it sights the ground. If the intersection of the crosshairs covers the pin, the horizontal axis is in adjustment. If not, correct halfway by means of a support-adjusting screw and the rest of the way by means of the plate screws.
6. Repeat the operation, and verify the adjustment.

Fourth Adjustment

Make the line of collimation horizontal when the bubble of the attached level is centered.

1. Drive two stakes 300 to 400 feet apart, and set up the instrument approximately halfway between these stakes.
2. Level up and take readings on the rod held successively on the two stakes. The difference between the readings is the difference of elevation of the stakes.
3. Next, set the transit over one of the stakes, level up, and take a reading of the rod held on the other stake.

4. Measure the height of the instrument. The difference between this and the last rod reading should equal the difference of elevation as previously determined. If it does not, correct the error halfway by means of the attached level-adjusting screw.
5. Repeat the operation, and verify the adjustment.

Fifth Adjustment

Make the vernier of the vertical circle read zero when the bubble of the attached level is centered.

1. Level up the instrument.
2. Sight on a well-defined point, and take note of the reading on the vertical circle.
3. Turn the vernier plate one-half of a revolution, and also turn the telescope vertically one-half of a revolution.
4. Again, sight on the same point.
5. Read and record the reading on the vertical circle.

One-half the difference of the two readings is the index error. The error may be corrected by moving either the vernier or the vertical circle, or the error may be noted and applied as a correction to all measurements of vertical angles.

Adjustments of the Compass

It will sometimes be necessary to adjust the compass. When an adjustment is required, it may be accomplished by using the following procedure.

First Adjustment

Straighten the needle.

1. Examine to see if the ends of the needle are set on opposite divisions. If not, fix the pivot so that they are.
2. Revolve the box by one-half of a revolution. If the needle does not set on opposite divisions, bend both ends by one-half the difference.

Second Adjustment

Place the pivot in the center of the plate. If the needle is straight, move the pivot until the needle sets on opposite divisions at points such as 0°, 45°, and 90°.

Instructions for Using the Transit

The transit requires various adjustments, as explained in the preceding section. To center the transit over a stake, rest one leg of the tripod on the ground, then grasp the other legs and place the instrument as nearly over the stake as possible. Then attach the plumb bob, and center it accurately by means of the shifting head. Avoid having the plates too much out of level because this will result in unnecessary straining of the leveling screws and plates.

Once the instrument has been centered over the stake, level it up by the spirit levels on the horizontal plate. To do this, turn the instrument on its vertical axis until the bubble tubes are parallel to a pair of diagonally opposite plate screws. Then, stand facing the instrument and grasp the screws between the thumb and forefinger; turn the thumbscrew in the direction the bubble must move. When adjusting the screws, turn both thumbscrews in or out, never in the same direction. Adjusting one level will disturb the other, but each must be adjusted alternately until both bubbles remain constant.

Figure 6-10 shows the method of measuring a horizontal angle. The process of laying-off a given angle is similar to that of measuring



Figure 6-10 The general principle of transit work. The transit is placed over the apex A of the angle CAB that is to be measured. The telescope is sighted to stake B (position M), and a reading is taken. It is then turned horizontally and sighted to stake C (position S), and another reading is taken. The difference between these readings gives angle CAB.

the angle. The transit is set up at the vertex of the angle, the vernier is clamped at zero, and the telescope is pointed at the target, thereby marking the direction of the fixed line. The limb is now clamped, the vernier is unclamped, and the vernier plate is turned through the desired angle and clamped. A stake should now be driven in line with the vertical crosshair in the telescope, thus establishing the two sides of the angle.

When laying out the foundations of buildings, a corner stake is first located by measurement. Then the direction of one of the walls is laid out by driving a second stake. This direction may be determined by local conditions (such as the shape of the lot or the relation to other buildings). If the building is to be an extension to (or in line with) another building, the direction can be obtained by sighting along the building wall and driving two stakes in line with it. If it is to make a given angle with another building, this angle can be laid off as shown in Figure 6-11.



Figure 6-11 The method of laying out a new building (S) at a given angle with an old building (M). After the corner and the direction of one wall are determined, a right angle may be laid off (if the building is rectangular), thus locating two of the sides (AB and AC). The length of side AB is then measured, thereby locating corner B. The transit is set up at B, and line BD is laid off at right angles to AB. AC and BD are then laid off by the proper length, and the four corners of the building are thus located. If the building had not been rectangular, the proper angles could have been laid off instead of right angles.

Gradienter

Some transits carry a device called a *gradienter* (*Y* in Figure 6-8) that is attached to the horizontal axis by means of a clamp screw and is inside of the right-hand support. It is designed and employed for the determination of grades and distances and consists of an arm in the shape of an inverted Y with curved branches. To the extremities of this arm are attached an encased spiral spring and a nut through which moves a micrometer screw with a graduated head that revolves in front of a scaled index (*Z* in Figure 6-8) that is also carried by the arm. The ends of the screw and the spring are on opposite sides of a shoulder that is carried by the right-hand support. The head is divided into tenths and hundredths, and every revolution moves it in front of the scale by one division so that the scale gives the number of turns of the screw, and the graduated head gives the fraction of a turn.

In grading, if one revolution of the screw moves the crosshair a space of 1 foot on a rod held 100 feet away, the scope indicated by the telescope is 1 percent. To establish a grade, level up the telescope, clamp the arm of the gradienter, and turn the micrometer screw by as many divisions as are required in the grade. For example, to set the gradienter at 2.35, move the head two complete turns plus 35 subdivisions. Measure the height of the telescope from the ground. Set the rod at that height. Then hold the rod at any point on the line, raising it until the target is bisected by the crosshairs. The foot of the rod will then be on the grade.

Care of Instruments

With proper care, the usefulness of an instrument can be preserved for many years. Therefore, the following suggestions on the care of instruments should be noted:

- The lenses of the telescope, particularly the object glass, should not be removed, since this will disturb the adjustment. If it is necessary to clean them, great care should be taken, and only soft, clean linen should be used.
- To retain the sensitivity of the compass needle, the delicate point on which it swings must be carefully guarded, and the instrument should not be carried without the needle being locked. When the needle is lowered, it should be brought gently on the center pin.
- The object slide seldom needs to be removed. When removal is necessary, the slide should be carefully protected from dust.

Do not grease or oil the slide too freely; only a thin lubricant film is necessary. Any surplus of oil should be removed with a clean wiper.

- The centers, subject to considerable wear, require frequent lubrication. After a thorough cleaning, they should be carefully oiled with fine watch oil. All of the adjusting screws should be brought to a fine bearing, but they should never be tightened to such a degree that a strain is applied to the different parts. If this is done, the adjustment will be unreliable.
- When the instrument is carried on the tripod, all clamps should be tightened to prevent unnecessary wear on the centers.

The Stadia

This is a device that is used for measuring distances, and it consists essentially of two extra parallel hairs in addition to the ordinary crosshairs of the transit or a level telescope (see Figure 6-12). The stadia hairs may be adjustable, or they may be fixed permanently on the diaphragm.

When using the stadia, distances are measured by observing through the telescope of a transit the space (on a graduated rod) included between two horizontal hairs (called *stadia hairs*). If the rod is held at different distances from the instrument, different intervals on the rod are included between the stadia hairs. The spaces



Figure 6-12 The principle of stadia operation. The fixed stadia hairs are set so that they will intercept 1 foot on a rod at a distance of 100 feet. Since the image of the crosshairs is projected to a point beyond the telescope objective equal to its focal length, the rays of light converge at that point, and measurements must begin from there. Therefore, a constant must be added to all stadia readings equal to the focal length of the object lens, plus the distance from the face of the objective to the center of the instrument. This constant is the factor F + C. For transit telescopes, it is equal to approximately 1 foot.

on the rod are proportional to the distances from the instrument to the rod so that the intercepted space is a measure of the distance to the rod. This method of measurement furnishes a rapid means of measuring distances when filling in details of topographic and hydrographic surveys.

Most transits, all plane-table alidades, and some precision leveling instruments are fitted with stadia hairs. Stadia surveying has the advantage in that the intervening country does not have to be taped, and it provides a means of measuring inaccessible distances (such as across water and up steep hills and bluffs). It is well adapted to preliminary surveys for highways and railroads because the errors tend to be compensating rather than cumulative, but it should not be used for short distances (such as farms and city lots). In sights of 200 to 400 feet, it is possible to read a rod to the nearest hundredth of a foot that represents 1 foot in distance. At 600 to 1200 feet, it is possible to read to the nearest hundredth of a yard that represents 3 feet in distance. This is the precision to be expected in stadia measurements.

The rod used is preferably a one-piece stadia rod (see Figure 6-13F), but any standard leveling rod (except builders rods graduated in inches and sixteenths) may be used. When leveling with an instrument that is equipped with stadia hairs, care should be taken not to confuse the center leveling crosshair with either of the two outside stadia hairs. It has been done. Although it is by no means obsolete, stadia surveying has been superseded by aerial photography. Neither is a substitute for careful taping.

Other Devices

For the vast majority of surveying purposes, the transit and levels described are more than sufficient. Three other devices can be even more useful, however.

The *Theodolite* (see Figure 6-14) is a transit that is more expensive but more accurate than a standard transit, and the Theodolite has more capacity. If you are doing readings over 500 feet, you may want to look into this.

The *automatic level* (see Figure 6-15) is also a tool used where great precision is required. Another device, the electronic distance measurer (EDM), is good when great distances must be read. It is a tool used on the sea and in other places (such as measuring from a point to a mountain) where there is no real point of reference. The electronic distance measurer and the Theodolite are often used together (see Figure 6-16). (By the way, no one seems to know the origin of the term Theodolite.)



Figure 6-13 Various popular leveling rods: (A) is the Philadelphia rod, in English graduations; (B) the California rod; (C) the Philadelphia rod, in metric graduations; (D) the Chicago rod; (E) the architect's rod; (F) the stadia rod, in English graduations; (G) the stadia rod, in metric graduations; and (H) the broad stadia rod. *(Courtesy Eugene Dietzgen Co.)*

Laser Levels

The need for plumb walls and leveling moldings (as well as various other points straight and level) is paramount in house building. It is difficult in some locations to establish a reference point to check for level windows, doors, and roofs, as well as ceilings and steps.

The laser level (see Figure 6-17) has eliminated much of this trouble in house building. This simple, easy-to-use tool is accurate to within $^1/_8$ of an inch in 150 feet, and it has become less expensive recently so that even the do-it-yourselfers can rent or buy one.



Figure 6-14 Wild T-16 Theodolite. *(Courtesy of Wild-Heerbrugg)*



Figure 6-15 NA2 automatic level. *(Courtesy of Wild-Heerbrugg)*



Figure 6-16 Typical EDM/Theodolite setup. *(Courtesy of Wild Heerbrugg)*

The laser level can generate a vertical reference plane for positioning a wall partition or for setting up forms (see Figure 6-18). It can produce accurate height gaging and alignment of ceilings, moldings, horizontal planes, and can accurately locate doorways, windows, and thresholds for precision framing and finishing (see Figure 6-19). The laser level can aid in leveling floors, both indoors and out. It can be used to check stairs, slopes, and drains. The laser beam is easy to use and accurate in locating markings for roof pitches, and it works well in hard-to-reach situations (see Figure 6-20). The laser beam is generated by two AAA alkaline batteries that will operate for up to 16 hours.



Figure 6-17 Laser spirit level moves 360° horizontally and 360° vertically with the optional lens attachment. It sets up quickly and simply with only two knobs to adjust. *(Courtesy of Stabila)*



Figure 6-18 The laser level can be used to align ceilings, moldings, and horizontal planes. It produces accurate locations for doorways, windows, and thresholds for precision framing and finishing. *(Courtesy of Stabila)*



Figure 6-19 **The laser level can be used for indoor or outdoor leveling of floors, stairs, slopes, drains, and ceilings, and moldings around the room.** *(Courtesy of Stabila)*



Figure 6-20 **The laser beam is used to provide easy and accurate location markings on pitches and in hard-to-reach situations.** *(Courtesy of Stabila)*

The combination laser and spirit level quickly and accurately lays out squares and measures plumb. No protective eyewear is needed. The laser operates on a wavelength of 635 nm and can have an extended range up to 250 feet.

Summary

Leveling, in surveying, is the operation of determining the comparative levels of different points of land for the purpose of laying out a grade or building site by sighting through a leveling instrument at one point to a leveling staff at another point.

The transit is designed and used for measuring both horizontal and vertical angles. It is a telescope mounted in standards attached to a horizontal plate, called the limb. The transit is generally provided with a compass so that the bearing of any given line with the magnetic meridian may be determined. It also has a spirit level attached to the telescope so that it may be brought to a horizontal position and made to serve as a level.

A stadia is a device used for measuring distance. It consists essentially of two extra parallel hairs in addition to the ordinary crosshairs that are used in transit or level telescopes. When using the stadia, distances are measured by observing through the telescope of a transit.

The laser level is rather inexpensive and easily used. It can be utilized in the squaring of steps, locating doors, windows, and many other squaring and leveling operations.

Review Questions

1. What are the three lines of the level?
2. What is a transit?
3. What are the fine lines of a transit?
4. Name the various leveling rods used for measuring distance.
5. Explain the terms *backsight* and *foresight* when used in leveling.
6. What is a stadia?
7. Where is the laser level most useful?
8. What is leveling in terms of surveying?
9. Why is it important to have square corners and level floors in a building?
10. How can a laser actually establish a useable level reference?

Chapter 7

The Design Process

The first consultation the designer has with the owner results in the owner setting forth what he or she wants or requires. This may include such things as the number of rooms, their sizes, the style of house preferred, the kind of materials he or she wants to use, and probably that all-important factor—how much money he or she will need, or how much is available. The first consultations may result in the designer making a dozen or more sketches.

It is the designer's function to guide the client in such matters. Usually, the owner has no skill or aptitude for building a house. Later consultations may settle such things as lighting, heating, perhaps the quality and style of plumbing fixtures, and the make or quality of such appurtenances as air-conditioning, laundry, and dishwashing equipment. The designer usually makes sketches (probably freehand) for the owner's approval.

In some instances, the purchaser comes into the office and consults with the designer or designee. The owner will decide on small changes in the chosen house plan. The designer just makes the suggested or agreed-upon changes and then draws up the blueprints. The owner picks out wall colors, kitchen cabinets, appliances, toilet-bowl designs, and many other small details. This may take a number of visits to a builder's office, where all the samples of tile, carpet, brick, and other design features are on display. If there is a model house available, it is much easier for most people to pick out the one they want and see what changes they desire.

Design Considerations

Following are some of the particulars that should be settled before final design work:

- Owners may greatly prefer a house with a basement. However, perhaps for reasons of economy, they may be willing to accept a house on a concrete slab. On the other hand, if the house is in Texas or some other location with soil problems, it will have to be a slab house. The designer should be able to give advice as to the advantages and disadvantages of the two systems along with the comparative cost of construction.
- The owner's mind may be set on a heating plant in the basement. However, in the event that a house with no basement is agreed on, the owner should understand that the heating plant must be in a utility room or in the attic.

- The owner may insist that there be a well-equipped laundry in the basement. The person who does the laundry may have some ideas on this subject.
- The owner will probably insist that there be adequate closets for each bedroom. The owner may have some ideas as to exactly what "adequate" consists of.
- The owner will want the kitchen to be convenient, with or without a garbage-disposal unit, probably with a dishwasher in a convenient location, possibly with room for a home freezer. Although saving steps is important, sufficient room in the kitchen may be more important. Few cooks appreciate a small kitchen—it greatly inhibits style.
- The owner may want a dining room, and not just dining space in one end of the living room, and may think that a counter or bar and no partition between the kitchen and dining room is not sufficiently odor-resisting when cooking fish or corned beef and cabbage.
- The owner (or perhaps the designer) may have some ideas concerning privacy in the home. There may be some objections to so-called window walls that are supposed to "bring the outdoors indoors," and a preference may be expressed for baseball-proof walls instead. Perhaps the idea of keeping large areas of glass clean is not appealing, and the owner would be quite content to leave the "outdoors" outdoors, if there is plenty of living space indoors.
- Then, there is the constant problem of sound resistance. Modern homes are often noisy, with air-conditioning, forced air heating, laundry, and dishwashing equipment, attic fans, kitchen fans, bathroom fans, radio and television, and many other noise-generating sources. It is the designer's duty and obligation to see that such noises are isolated insofar as is possible. Partitions should be noise-resistant.

The designer must understand these and many other problems. They are with us and will be with us for many years to come. The owner probably does not (possibly cannot) understand how to handle such problems. The designer can, and should. It is the designer's function to guide the owner's ideas or simple notions so that the home environment will be satisfactory as far as the owner's means will permit. The designer will probably be blamed for any serious discrepancy, no matter if the owner *did* insist on it.

It is not only desirable, but also necessary that the designer be familiar with the dimensions of the equipment, furniture, and other appurtenances found in the home. While it is rarely necessary that they be accurately detailed, space must be allotted for each one of them, and space is expensive.

All modern building is governed by codes of some sort. In all government-financed homes, the government's minimum standards are strictly enforced, and city codes are often much more restrictive. Electrical codes occasionally seem to be unreasonable, but the building designer must be governed by them. Plumbing is often seriously skimped when no one is watching. Many states have plumbing codes. However, they do not have the force of law unless augmented and enforced by local authority. There is a *National Plumbing Code*, and, although it is advisory, it is in line with good practice. It should be used where there are no local codes. State and local boards of health may make it quite difficult for the designer of an inadequate plumbing system if the occasion arises.

For economy, kitchens and bathrooms should be placed back-to-back. A 3-inch copper soil pipe will fit into a partition of 2 × 4 studs, whereas a 4-inch cast-iron soil pipe won't.

In perhaps most cases, the designer's duty is done when he or she prepares and delivers the drawings for a job. In some cases, he or she contracts to inspect the work at stated intervals, to ensure that the work is satisfactorily done.

The designer should allow for the following thicknesses of walls in drawings:

- *Standard wood outside wall*—¾-inch plywood or insulating board sheathing, 3½-inch studs, ½-inch sheetrock inside, 4½ inches under the siding
- *Inside partitions*—3½-inch studs, sheetrock ½ inch (both sides), 4½ inches
- *Sound-resistant staggered-stud partitions*—3½-inch studs staggered 2 inches, gypsum lath and plaster (both sides) 7¼ inches
- *Single-width brick veneer*—¾-inch sheathing, 3½-inch studs, ½-inch sheetrock, 9½ inches
- *Concrete blocks (plastered against the masonry)*—8-inch, 8½ inches
- *Concrete blocks (with furring)*—8-inch, ¾-inch furring, ½-inch sheetrock, 9¼ inches

- *Cavity masonry wall*—3^3/$_4$-inch brick, 2^1/$_2$-inch air space, 4-inch concrete blocks, plaster on masonry, 10^7/$_8$ inches
- *Chimneys*—minimum wall thickness, 3^3/$_4$-inch brick liners, outside dimensions, 8^1/$_2$ inches × 8^1/$_2$ inches, 8^1/$_2$ inches × 13 inches, 8^1/$_2$ inches × 18 inches, 13 inches × 13 inches
- *Ceiling heights*—first floor, clear minimum, 7 feet 6 inches; basement, 6 feet 9 inches clear
- *Stair wells*—3 feet 2 inches × 9 feet, or clear headroom 7 feet above nosing of treads, vertically

An Example of Design

As an example of design, the series of figures presented in this section show the development of architectural drawings beginning with stock plans or plans that appear in newspapers and magazines from time to time. They give a prospective owner a good starting point, saving much time and study.

Certain things, however, should be kept in mind. The magazine drawings were doubtlessly prepared by a registered architect. While the publishing of a design may imply that the architect has given approval that the design can be copied, it is best to get the written consent of the original designer, or at least to secure this consent from the publisher. A registered architect's plans are protected from being copied, and court decisions have ruled that minor changes (regardless of how many of them there are) do not release the copier from liability. Purchasing a set of stock plans includes permission to build from the plans at least once. You might have to buy a second set to build the same design again. Determine where you stand legally before copying designs of any sort. It may save you from a costly and embarrassing situation.

Let us assume that we start with magazine plans (Figures 7-1 and 7-2). These two plans were prepared by a capable and experienced architect who has given us a practical and logical arrangement of a house plan, with stairs, doors, windows, closets, and so on. The architect has also indicated a proper and reasonable size for the various rooms. Any proposed changes or additions that the owner may desire may be taken up with the architect or builder, and may be easily whipped into form on the drawing board.

Conference with Builder

Let us now assume that the owner prefers to deal only with a carpenter or builder of his or her acquaintance, and asks the carpenter



Figure 7-1 First-floor plan from a magazine.

or builder to prepare the drawings and give an estimate on construction. We will also assume that while the builder understands his or her own business from start to finish, he or she does not pretend to be a designer. A designer is, therefore, called in for advice on the preparation of the drawings. Having decided on the main features of the plans and elevations, we will start with the first-floor plan of the house, since that is always the controlling form factor. Then, following the easy and usual method, we may trace the other plans (second floor and basement) over it.



Figure 7-2 Second-floor plan from a magazine.

Changes Agreed On

After a careful study of the first-floor magazine plan, it is decided first to place the large chimney and fireplace inside the house against the stairs to conserve as much heat as possible, since considerable heat is necessarily lost from an outside wall. Next, omit the kitchen chimney, since a gas range is to be used. Third, move the large porch to the end of the house, since it provides more privacy, and change the window to a door. Fourth, provide the paved entrance platform with a settee at the front entrance. Fifth, provide a coat closet at the front entrance. Sixth, enlarge the dining room, taking the space from the kitchen. Seventh, install a first-floor lavatory in the small new wing at the rear. These, along with other minor changes, such as turning the back steps, adding two small closets near the fireplace, and substituting round for square porch columns, create a much more convenient and valuable first-floor plan. The principal second-floor changes are made to save cost and involve a lowering of the front eaves line and decreasing the size of the front rooms.

Figure 7-3 shows the modified first-floor plan after the changes have been agreed on, and Figure 7-4 illustrates the completed drawing of the first floor, with all the specifications and dimensions given in full detail.



Figure 7-3 The modified first-floor plan.


1'-6"
9'-4"
9'-4"
1'-6"
PORCH
21'-2" × 7'-0"
1L
1L
6'-6"
RAD.
S
20'-8" × 12'-0"
LIVING ROOM
RAD.
RAD.
1L
1L
1L
12'-8"
6'-4"
21" × 110"
JOISTS OVER 16" C.C.
8'-8"
4'-6"
FACE BRICK
HEARTH
S
S
S
S
CL.
CL.
PASSAGE
LAV.
1L
7'-0"
6'-8"
12"
32'-0"
DN.
UP
3½' WIDE
S
1L
S
10'-8"
S
S
S
12'-7" × 12'-0"
DINING ROOM
2" × 10"
JOISTS OVER
16" C.C.
RAD.
4L
12'-8"
12'-6"
SHELF ABOVE
GAS
RANGE
3L
KITCHEN
KIT. CABINET
8'-4"
13'-4"
6'-4"
RAD.
REF.
SINK
RAD.
4'-10"
10'-10"
6'-0"
21'-8"

Figure 7-4 The completed drawing of the first floor with all dimensions and specifications in detail.

Summary

In architectural design, the designer usually makes several sketches (probably freehand) for the owner's approval. Among the many particulars that should be settled before the designer actually begins work are: will there be a basement (which determines the location of the heating plant); how many closets in each bedroom; will there be kitchen conveniences (such as a garbage-disposer unit, dishwasher, and room for a home freezer).

These are just a few of the problems for the designer. The owner probably does not know how to understand and handle such problems. The designer should know how to handle these problems and guide the owner so that the home environment will be more than satisfactory when the work is completed.

It is, of course, necessary that a designer know the dimensions of the equipment, furniture, and other appurtenances found in a home. Electrical codes occasionally seem to be unreasonable, but the building designer must follow them. Plumbing is often seriously skimped, unless local authorities have some kind of a ruling enforcing certain regulations.

Many times the future owner prefers to deal only with a carpenter or builder, and asks him or her to prepare the drawings and give an estimate on construction. The builder then calls the designer in for advice on the preparation of the drawing.

Review Questions

1. What must a designer know from the client before drawing up plans for a house?
2. Is it generally a good idea to change floor plans after construction has started?
3. Is the kind of material used in the construction important to the designer?
4. Are wall thickness, plumbing, and electrical wiring considered when drawing up plans?
5. Why are some localities limited to slab houses?
6. What is the difference in price of a slab foundation and a basement?
7. Where is the air-conditioning and heating placed if the house is built on a slab?
8. What are some of the concerns of someone who is trying to have a house built?
9. What is the purpose of a plumbing code?
10. What is the purpose of an electrical code?
11. Why can't you use a copy of a blueprint found in a magazine to build a house?

Chapter 8

Building Specifications

By definition, a *specification* is a specific and complete statement detailing the nature and construction of the item to which it relates. As applied to the building trades, specifications describe briefly (yet exactly) each item in a list of features and materials required to complete a contract for building an entire project.

Great care should be used when reading specifications in order to avoid misunderstandings and disputes. Each item entering into the construction is defined and described with precision so that there can be no chance of misunderstanding or double interpretation.

Example of Specifications

Specifications refer to the contract form of which they are a part. This saves repetition of statements with regard to liability of contractor, owner, and so on. The following is an example of specifications.

Introduction

Specifications for a frame dwelling to be built for Mr./Ms. ________ of ____________________ in the county of ____________________ and state of ____________________ on lot number ________________ on the ________ side of ________________________ street in the city or borough of ________________________, county of, ______, state of ________________________. These specifications relate to a set of attached drawings consisting of:

1. Plan of foundation and basement.
2. Plan of first floor.
3. Plan of second floor.
4. Plan of roof.
5. Four elevations (eight sheets in all).

Detailed working drawings furnished as required. All drawings are a part herewith, and are to be considered as such with any contract that may be made.

Height of Ceilings

The following dimensions for these heights are:

- Basement—7 feet 2 inches clear of finish.
- First-story—8 feet 6 inches between timbers.
- Second-story—7 feet 6 inches between timbers.

Interpretation of Drawings

For arrangement of floors, general finish, and measurements, reference must be made to the drawings. However, should any difference appear between the scale measurements and the figures, or between the wording of the specifications and the lettering on the drawings, the specification shall in all cases take precedence. If any errors that are not explained either by reference to the drawings or specifications become apparent, the contractor shall refer them to the architect for correction before proceeding with the work.

Conditions

The contractor must see that all the work on the said building is performed in a thorough, professional, and substantial manner by competent workers and must also furnish all materials (the best of their respective kinds), labor, implements, transportation, and so on, if not otherwise specified.

All painted parts of the exterior must have a prime coat of paint as fast as it is ready. The succeeding coats must not be applied within 3 days of the former, and then not in wet or freezing weather or other conditions specified by the paint manufacturer.

The contractor must protect all work while the building is in his or her hands, remove all superfluous materials or rubbish, and not obstruct the grounds around the foundation for grading and filling in as soon as the building is up. Figures are to take precedence over scale measurements.

Mason's Work

Excavate to the length, breadth, and depth required for the foundations, as shown on the architect's drawings. The topsoil is to be removed and placed in a separate pile from the other excavated materials—25 feet away from the excavation where directed. Also, excavate for a septic tank and overflow 75 feet from the foundation, as will be directed, containing 28 cubic yards to be built of concrete, with baffles, drains, and so on, all of which is set out in a special plan for same. The septic tank may be included in the plumbing subcontract. The main tank must be waterproof, although the overflow need not be. The tank shall be connected to the house at a point below the lowest fixture and below the frost line with a uniform declination of not less than 12 to 20 inches, and will have no running U trap. The drain is to be made of 6-inch socket-jointed Transite tile placed in tight cement joints from a point 4 feet outside the foundation.

Foundation

Foundations and footings, as shown on the plans, are to be made of poured concrete with 8-inch walls and 16-inch footings.

Chimneys

Build two chimneys, as shown, of the same size and shape. Use an approved hard-red-pressed brick for all exposed parts of the outside chimney and for topping out. The fireplaces in the parlor, dining room, and bedroom are to be faced with the same brick (smooth inside the fireplaces), with 8 inches on the sides and 24 inches at the top. Buff the joints, and straighten the arches on $3^1/_2$-inch × $3^1/_2$-inch angle irons, unexposed. Use firebrick for the backs. Lay the bricks in an approved refractory mortar (no fire clay). Spring trimmer arches for the hearths are to be laid with the same selected brick. All flues are to have tile linings, approved chimney pots, and clean outs.

Mortar

All mortar for brickwork is to be grade specified by building code regulations.

Installing Drywall

All walls, partitions, and ceilings, and all studded and furred places in all stories, are to be covered with $^1/_2$-inch-thick Sheetrock, which will have joints covered with tape and joint compound. Two coats of compound will be applied where wallpaper is used; three coats where paint is to be used. Panels shall be 4 feet × 8 feet and will be installed horizontally on walls, across the framing members on ceilings. The panels are to be secured with $1^3/_8$-inch blued ring-shank nails, and the pieces staggered. Inside corners of the paneling shall be covered with inside-corner molding, with nails placed 7 inches apart. Outside corners shall also be covered with metal molding. All joints will be smooth to the touch.

Tiling

The floors of bathrooms will be tiled with 3-inch × 3-inch octagonal and 1-inch-square vitrified tiling, colors to be selected. The side walls will be tiled 4 feet high of plain white glazed $2^1/_2$-inch × 4-inch molded base and nosing, with a narrow tinted stripe at the top of the sanitary base and under the nosing. The floors will be properly prepared by the carpenter by setting the rough floor $^1/_2$ inch below the top of the floor beams. All tiling will be set in adhesive recommended by the manufacturer, and the floors will be finished flush with the wood-finish floors.

Other Floors

There will be a concrete floor in the furnace room, in the shop, and in the area from the west end turning east to the cross wall, as shown in the plans. All floors will be $3^5/_8$ inches minimum, with 6-inch × 6-inch No. 11 reinforcing mesh. The kitchen hearth will be built in the same manner.

Coping

There will be 4-inch caps of blue stone on all piers showing them, edged on four sides, 3 inches larger than the piers. Cope area walls, which are to be 8 inches, with 2-inch × 10-inch blue stone where circular, fitted to radius. *No* patching of stone will be permitted.

Timber

All timber will be thoroughly seasoned, No. 1 common pine, square, straight, and free from any imperfection that will impair its durability or strength. *No* individual piece is to have moisture content of more than 19 percent. The architect will check this.

Framing

The framing will be as indicated on the drawings. Headers over openings will be the sizes indicated in detail. *No* header with checked moisture content of more than 15 percent will be acceptable. Frame so that sheathing will be flush with the foundation wall. All moldings are to be miter-spliced and mitered at angles. *No* butt ends will be showing in the finish.

Timber sizes will be as follows:

Design Element	***Timber Size***
Sills	2-inches × 8-inches
Girders	10-inch standard I-beams (25.4 pounds)
Corners	4 inches × 6 inches backed with 2 inches × 4 inches or built up
Main plate	4 inches × 4 inches (2 inches × 4 inches doubled)
Rafter plate	4 inches × 4 inches (2 inches × 4 inches doubled)
Studding (general)	2 inches × 4 inches
Closet studding	2 inches × 3 inches
Main rafters	2 inches × 6 inches
Dormer rafters	2 inches × 4 inches
Ridge boards	$1^1/_4$ inches × 8 inches
First floor joists	2 inches × 10 inches
Second floor joists	2 inches × 8 inches
Second story ceiling beams	2 inches × 6 inches

Spacing and Bridging

All studding, floor, and ceiling joists placed on 16-inch centers. In every span of flooring exceeding 10 feet, there will be a row of 1-inch × 2-inch bridging or 2-inch × 3-inch double nailed at each end. Rafters will be placed on 24-inch centers.

Partitions

All partitions are to be set plumb, well braced, and nailed. Studs at all angles and openings are to be doubled, and extra block is to be set at door openings for base nailing. All partitions that are not supported below are to be firmly trussed and braced. Ceilings to all closets will be furred down to within 12 inches of the door head except in closets more than 2 feet deep. There will be trued $^{7}/_{8}$-inch grounds at top of base and around all openings.

Lumber

All outside finish-lumber will be clear white pine unless otherwise specified. All exterior finish lumber is to be free from large or loose knots and will also be clear and thoroughly dry.

Sheathing and Sheathing Paper

Cover all the exterior walls with $^{3}/_{4}$-inch plywood sheathing nailed to each stud with 8d nails. With joints cut on studs or backed for end nailing, cover with Tyvek, which is to be well lapped, extending under all trim and around all corners to make a complete and tight job.

Exterior Finish

Windows, door casings, cornices, corner boards, water table, brackets, band courses, and so on are to be made to the detail furnished in the drawings. The stock moldings that are to be used are numbered on the drawings. The first story is to be covered with the best-grade cedar lap bevel siding, laid at $4^{1}/_{2}$ inches to the weather. The second story and gables are to be covered with 18-inch hand-split and resawn shakes, laid at $8^{1}/_{2}$ inches to the weather. Use hot-dipped galvanized nails, whose length will be approved by the architect. Window casings will be laid $2^{1}/_{2}$ inches to the weather, and the front door frames and casement windows will be according to detail shown in the plan.

Shingling

Cover all roofs with 8-inch × 16-inch Pennsylvania blue slate, laid 7 inches to the weather. All hips and other parts that require it are to be made secure against leaks by the proper use of slaters' cement and proper flashings. An ornamental galvanized-iron ridge crest will be placed on the main ridge. See details on drawings for this crest.

Flashing

Flash around chimneys, over all doors and windows, heads exposed to the weather, and where roofs join walls with 16-ounce sheet copper. Do the same in all valleys and wherever required to secure a tight job. Each side of a valley is to have a water check turned up 1 inch in the metal.

Flooring

First and second stories are to have double floors, with a subfloor of $^5/_8$-inch CDX plywood. The first- and second-story finish flooring is to be oak tongue-and-groove strip flooring, which is to be thoroughly seasoned and blind-nailed over building paper. There will be no joints in the main hall and only one joint in the run of boards in other rooms of the first floor. The second-story floors are to be cleaned and sandpapered to a smooth finish for the painter. Oak thresholds are to be set to all outside doorways, and hard rubber-tip doorstops are to be located behind all doors that open against a wall.

Window Frames

These are to be made of seasoned white pine.

Sash

All sash and frames are to be made by the Johnson Corporation and are to be of kiln-dried, vinyl-sheathed white pine. The numbers are given on the drawings.

Screens

All windows that open are to be fitted with bronze- or copper-wire window screens.

Glazing

All sash and outside doors, where indicated, are to be glazed with Johnson insulated windows or their equivalent. All hall doors are to be glazed with French plate. The plate in the Dutch door will be beveled. The basement sash is to be glazed with a single-strength glass.

Blinds

All windows, where indicated, are to be provided with an approved type of blind that will be $1^1/_8$ inches thick and made of the best grade of seasoned white pine. All blinds will move freely after painting. The blinds are to be hung on approved cast-iron blind hangers.

Door Frames

All inside door frames in finished parts of the house, first and second stories, are to be made of white pine $^{25}/_{32}$-inch thick, set plumb and true, and blocked in four places on each side. Outside doorframes are to be rabbeted for doors. All frames are to be flush with the plaster finish.

Doors

Unless otherwise specified, all inside doors are to be made of slab-type birch veneer with hollow cores and will be $1^{3}/_{8}$ inches thick. Outside doors are to be $1^{3}/_{4}$-inches thick and will be made of solid-core, slab-type birch veneer. The front doors are to be of the design shown in the drawings. Hang all doors throughout with loose-joint ball-tip butts of sufficient size to throw them clear of the architraves. Doors are to have three $3^{1}/_{2}$-inch × $3^{1}/_{2}$-inch butts on $1^{3}/_{8}$-inch doors and three 4-inch × 4-inch butts on $1^{3}/_{4}$-inch doors. A hardware schedule will be furnished. Hang both double-swing butlery doors on double-acting brass spring hinges. Furnish all nails, except those used for inside work, galvanized and all other hardware that will be necessary for the completion of the work in the proper manner.

Interior Trim

For the basement, the interior trim is to be selected cypress or redwood. For the first and second floors, the trim is to be unselected birch. There will be a 4-foot 6-inch paneled wainscoting in the dining room, first floor hall, and up stairway. This panel will be made of $^{1}/_{4}$-inch birch plywood, with trim as shown in the details. There will be a 5-inch cabinet plate shelf in the dining room, the bottom member of which will be a picture molding. This shelf will match the door head trim.

Stairs

The main staircase is to be made of unselected birch. The stringers and treads are to be $1^{1}/_{8}$ inches thick, as shown in details. The risers are to be $^{3}/_{4}$ inch thick. The risers and treads are to be housed into the wall stringer and return-nosed over the outside string. The rails are to be 3-inch × 3-inch molded, with ramps as shown in the details. Balusters will be $1^{5}/_{8}$ inches, taper turned, three to a thread, and proportionately more for increased widths. Newels and column newels are to be as shown in the details. The run on the first flight is to be $10^{1}/_{4}$ inches from face to face of the rise with 12-inch treads. The second flight and basement stairs are to be $9^{3}/_{4}$ inches of run with $11^{1}/_{2}$-inch treads. For the basement stairs, cut 2-inch × 12-inch boards for the stringers and 2-inch × 10-inch yellow pine for the treads.

Mantels

There will be two mantels where indicated on the drawings. The contractor will figure them to cost $2000 each complete, including linings and face and hearth tile. This amount will be allowed the owner to use at his or her option in the selection of it. The entire cost is to be figured in the contract price, including the setting of the mantels by the contractor.

Pantry Cabinets

There will be a cabinet, where indicated, with three glass doors, above the draining board. This cabinet will be 10 inches deep inside and will contain three shelves. The wall cabinets are to be constructed as shown in the details.

Closet Shelving

The trim on the inside of the cabinets is to be plain. There is to be an average of 10 feet of 12-inch shelving to a closet, with 6-inch clothes strips and 1 dozen clothes hooks, japanned. The kitchen closet and the closet under the kitchen stairs are to have suitable shelving and sufficient pothooks and other fixtures. There will be 25 feet of shelving in the shop closet. There will also be 1 dozen clothes hooks under the basement front stairs.

Plumbing

All necessary materials for completing the plumbing installation, as hereafter set forth, in a correct and sanitary manner are to be included in the general contract. The state plumbing code shall be strictly followed.

Electric Wiring

No. 12 Romex sheathed cable is to be installed under and subject to the requirements and regulations of the *National Electrical Code* and all state, county, and municipal codes. The locations for all electrical outlets will be shown in the drawings.

Water Pipes

Water is to be brought from the street main into the house through $^3/_4$-inch copper tubing, or plastic if preferred. Copper water tubing is to be used on all straight-line work. Place a hose-bib cock on the main at a point against the house for hose purposes, both front and rear, with a stop and waste cock in the basement.

Complete all necessary digging for the laying of sewer and water pipes to the house. No trenches are to be less than 36 inches below the grade at any point. The pipes are to enter the house in the basement at a suitable point for intersection with the inside piping system. The dirt is to be well rammed over the pipe in the trenches as it is refilled. The house sewer is to be installed by the plumber, and it will consist of a perfect 4-inch glazed socket-jointed tile pipe to a point exactly 4 feet outside the foundation wall. The soil pipe is to be 4-inch cast iron. All water pipes must have a gradual fall from the fixtures that they supply, and they must open at their lowest point for drainage purposes. All the cast-iron waste pipe will be furnished with the necessary fittings.

Furnish and install one 60-gallon gas-fired water heater of an approved type and manufacture. This water heater is to be supplied with water through a $^3/_4$-inch copper tube. Place a shutoff cock on the supply pipe. Take hot water from the water heater to and over the kitchen sink and to all other fixtures, except toilets, with $^1/_2$-inch copper tubing. The supply to the toilets will be through $^3/_8$-inch copper tubing. Cold water to all fixtures will be through separate pipelines. There must be no depressions in any pipe, and hot water must be kept rising from the boiler head.

Kitchen Sink

Furnish and install a cast-iron enameled kitchen sink, with a garbage disposer of (*specify make and model*). Furnish and install an automatic dishwasher (*specify make and model*) where indicated in drawings.

Wash Trays

Provide and install where indicated on drawings, one two-part stone tub on galvanized iron legs. Supply the tub with hot and cold water through $^1/_2$-inch copper tube and brass faucets, one for cold water, threaded $1^1/_2$ inches waste, with traps, plugs, and chains complete. The waste drain is to be connected with the soil pipe through a 2-inch copper pipe.

Bathroom Fixtures

All bathroom fixtures are to be (*specify name of manufacturer*) make, as listed in their catalog. The basement-bathroom water closet will be (*name and model*); lavoratory, (*name and model*); bathtub, 5-foot 6-inch (*name and model*). The other toilets are to be (*name and model*). The two second-story baths are to be (*name and model*), 18 inches × 27 inches. Before any wall finishing is done, all supply pipes must be proven perfectly tight by a satisfactory test, and they must be left perfect at the completion of the test.

Painting

The entire exterior woodwork, except shingles, is to be painted with three coats of (*manufacturer's name*) best grade of ready-mixed paints, thinned as necessary and as specified by the manufacturer.

The color of paint will be plain white, except for the shutters and shakes, which will be green and will be given two coats of (*manufacturer's name*) shake and shingle finish. The second-story floors will be sanded smooth and given three coats of (*manufacturer's name*) polyurethane varnish. The first-story floors are to be left bare for wall-to-wall carpeting or vinyl tiling. All interior birch trim is to be finished natural, with one coat of white shellac and two coats of (*manufacturer's name*) of flat varnish. The type and color of the interior wall paint for all interior walls will be specified by the owner.

Condition of Bids

The owner reserves the right to accept or reject any or all bids.

Summary

A specification is a statement containing a detailed description or enumeration of particulars, as of the terms of a contract, and details of construction usually not shown in an architectural drawing. Great care should be used when reading specifications to avoid misunderstandings and disputes. Each item entering into the construction is defined and described with such precision that there can be no chance of misunderstanding or double interpretation.

Framing will be indicated on the drawings. Specifications as to type of timber used (such as No. 1 common yellow pine, square, straight, and free from any imperfections that will impair its longevity) will be indicated. Headers over window and door openings will be indicated as for size and installation procedure.

Interior trim, including stair casing, will be shown. Moldings used throughout the house will indicate miter angles and type of lumber used. Ceiling height (as well as plastered or drywall construction) will be specified. Most plastered walls will be specified as to type of finish coat (which, in most cases, is at the option of the owner) and will also specify that exposed corners be protected with metal corner beads.

All necessary materials for completing the plumbing installation, as set forth in the specifications, shall meet all state and local regulations. Electrical wiring will be listed and meet the requirements and regulations of the *National Electrical Code,* or state and local codes.

Review Questions

1. Why should great care be used when reading specifications?
2. What information is included in the specifications on framing a house?

3. What code should be followed when plumbing a house?
4. Can a specification on a dwelling be changed or altered? If so, how?
5. What code should be followed when electric wiring is installed?
6. Why should the purchaser of a house not only read, but also study all specifications prepared by the builder?
7. What should the clearance of the ceiling be in the basement?
8. What is an elevation? Where is the word found?
9. What is Tyvek? Why would you want it on a house?
10. What is the height of the second-story ceiling (between timbers)? Is this higher or lower than that of the first story?
11. What does the architect place in the specifications sheet?
12. Who determines the number of bathrooms in a house?

Chapter 9

Architectural Drawings

Drawings provide designers with a practical method of communicating their ideas to the carpenters and builders. Drawings are a type of shorthand that not only reflects, but also fixes on paper, the ideas of the designers. They help avoid possible misinterpretation.

Use of Drawings

Contractors and estimators should retain prints on jobs that they complete so that they might be used to compare future jobs. They should also keep at least two sets of prints on a job in progress. One set is the working-drawings for the tradespeople. On the second set, the lead carpenter adds the changes made as the structure is built, to be turned over to the owner to update the original drawings issued. The final drawings will identify any changes that were made during construction. The owner may change the original drawings to reflect the changes, so that the drawings will be fully up-to-date to assist with maintenance, troubleshooting, and design of additions to the original building.

Reading Drawings

In the drawings (sometimes called *prints* or *plans*), various elevations are shown (such as the front, side, and sectional). A plan is a horizontal view of an object. An *elevation* is a vertical view of an object.

Projected Views

The various views are projected on imaginary projection planes, similar to the projection of a picture on glass. To illustrate the first (or front) view, place a clear pane of glass in front of the object with the glass parallel to the surface of the object being projected. Figure 9-1 shows a simple building with a shed roof. In front of the building is the pane of glass marked *V*, representing a vertical plane.

When an observer looks through the glass directly at the front of the object from a considerable distance, the observer will see only one side, in this case the side marked *ABCD*. The rays of light falling upon the object are reflected into the eyes of the observer, and in this manner, the observer *sees* the object. The pane of glass (vertical plane) is placed so that the rays of light from the object will pass through the glass in *straight parallel lines* to the eyes of the observer.



Figure 9-1 Rectangular object resting on a horizontal plane and facing a vertical plane.

The rays of light from points *ABCD* of the building pass through the glass at points *a*, *b*, *c*, and *d*. If these points (*a*, *b*, *c*, and *d*) are connected by lines, a view of the object as seen from the front is obtained, which is called *front elevation*.

The front elevation is identical in shape and size with the front side *ABCD* of the object (that is, *ab* = *AB*; *bc* = *BC*, and so on; angle *dab* = angle *DAB*; angle *abc* = angle *ABC*, and so on).

Top View or Plan

For this view, place a pane of glass in a horizontal position above the building that is resting on the horizontal plane (see Figure 9-2). Now, look at the object directly from above. Note that the rays of light from corners *AEFB* of the top pass through the glass at points *aefb*. If these points *aefb* are connected by lines, a view of the object as seen from the top is obtained, which is called the *top view*, or preferably *plan*.

Right-End View (Elevation)

A pane of glass is placed to the right of the building in a vertical position and parallel to the right side *BFGC* of the building (see Figure 9-3). Here, the pane of glass is marked *P*, which means *profile plane*, or plane from a side projection. Looking at the building directly from


GLASS (PARALLEL TO HORIZONTAL PLANE)
H
TOP VIEW (PLAN)
e
f
a
b
H
E
A
TOP
F
B
G
FRONT
D
C

Figure 9-2 Projection of the top of an object to obtain top view.

the right side (as in position *S*), the rays of light from corners *BFGC* of the upper left-hand side (from points *AE*) pass through the glass at points *bfgc* and *ae*. If these points are connected by lines, a view of the object as seen from the right side is obtained, which is called the *right-side view*, or preferably *right-end elevation*.


P
PROFILE PLANE
90°
E
e
H
TOP
F
a
A
f
S
B
G
b
FRONT
g
D
C
c
RIGHT END
ELEVATION
RIGHT END

Figure 9-3 Projection of the right end of an object illustrating right profile plane.

The shape of the object is such that the entire visible surface does not lie in a plane parallel to the projection plane. The points *A* and *E*, though located at the other end of the object, are visible and accordingly form part of the right-end view. Figure *aefb* does not show the top in its true size because it is projected obliquely instead of at 90°. An *oblique projection* makes an object appear smaller than its real size.

Left-End View (Elevation)

With a pane of glass shifted to the left side of the object (see Figure 9-4), and the building viewed directly from the *left* side (as position *S*), the rays of light from corners *ADHE* of the left side pass through the glass at points *adhe*. If lines connecting these points are drawn on the glass, a left side view of the object is obtained. However, the edge *FB* at the other end is invisible. It is shown by a dotted line connecting *f* and *b* projected from *F* and *B*. The completed drawing is then called a *left-side view*, or preferably a *left-end elevation*.



Figure 9-4 Projection of the left end of an object illustrating left profile plane.

Sections

Most buildings are so complex they cannot be clearly represented by a plan and elevation alone. In such a case, the parts that do not appear properly in these drawings are better represented by a *section*, or *sectional views*. A cross-section is a drawing of a building showing that part cut by a plane (see Figure 9-5).


M
H
INTERSECTING PLANE
A
B
C
LINE OF INTERSECTION
M
H
A
B
C
CROSS SECTION LINES (LIGHT)

Figure 9-5 Pictorial view of a building illustrating cross-section.

Directions of View for Sectional Views

For an unsymmetrical object, it is important to know the direction in which the sectional view is viewed. This is indicated by arrows at the end of the line representing the cutting plane (see Figure 9-6).


L
A
B
DIRECTION OF SIGHT
B
A
R
CUTTING PLANE INTERSECTION LINE
CUTTING PLANE

Figure 9-6 Direction in that a sectional view is viewed is indicated by the direction of arrows *AA*, at the ends of the cutting plane intersection line.

The arrows *AA* indicate that the object is viewed in the direction of point *L* (toward the smaller end of the object), and the arrows *BB* (in the direction of *R*) toward the larger end.

The Scale

Scale is the ratio between the actual size of the object and the size that it will be drawn. The scale is usually expressed on a drawing as full size, half size, quarter size, and so on, or it might be expressed as 1 inch = 1 foot, 1 inch = 100 feet, 1 inch = 1000 feet, or any other proportion that might be necessary to use. The scale is printed on the drawing.

On a full-size drawing, the object and drawing are of the same size. When the drawing is marked half size, the object is twice the size of the drawing. Thus, the drawing of an object is shown full size, half size, and quarter size (see Figure 9-7). If the building's height is represented by H and its diameter by D, then these dimensions will be the same for the full-size drawing. That is, $H = h$; $D = d$. For the half-size drawing, $h' = 1/2\ H$; $d = 1/2\ D$. Similarly, for the quarter-size drawing, $h'' = 1/4\ H$; $d'' = 1/4\ D$.



Figure 9-7 A drawing of an object to different scales: full size, half size, and quarter size.

From this it is seen that when the length of any edge on the drawing is made the same as the length of the corresponding edge on the object, the drawing is marked *full size* (sometimes *actual size*). If the length of any line on the drawing is half the length of the corresponding line on the object, the drawing is *half size*.

The scale is smaller than the building. In using prints, the size is important, since prints are used in the field, and if they are too large, they may not be easily handled.

In the case of a building, it would be impossible to have a print as large as the building. Thus, it is necessary to cut the print down in size. This necessitates the use of a scale. In the drawing of a building the building, designers usually express scale as 1 inch = 1 foot, 1/2 inch = 1 foot, and so on. This would indicate that 1 inch on the drawing would be equal to 1 foot on the actual structure, or 1/2 inch on the drawing would equal 1 foot on the actual structure, respectively. The architect uses the architect's scale. This is laid out in inches (1/8, 1/4, 1/2, and so on).

To lay off a distance of 2 feet 6 inches, place the 3/4 scale with division 2 at the given point *A*; then the zero division on the scale will be at a distance of 2 feet (see Figure 9-8). Because the end space is divided into twelfths, each division represents one inch on the 3/4 scale. Therefore, measuring off six divisions indicates that *AB* = 2 feet 6 inches. Notice the difference in actual length of this measurement on the 1 inch = 1 foot scale (see Figure 9-9).



Figure 9-8 A typical architect's scale with detail showing 3/4 and 1 inch to the foot.

The scale on the original would not apply to a reproduction made by photocopying. The scale on the original (see Figure 9-10) should



Figure 9-9 A typical architect's scale with detail with inch divisions instead of inches to foot.



Figure 9-10 Graphic reproduction scale.

be crossed out and a *graphic scale of proportions* corresponding to the reproduction added.

Drawing Development

Knowledge of how architectural drawings are developed will help the carpenter and builder read drawings with more complete understanding. Architectural drawings are a means of transferring the thoughts of the designer to the builders and carpenters whose responsibility it is to construct the building. Graphic symbols are used to locate specific features and where they are to be placed.

The different parts or drawings that are necessary to show the structure (such as the mechanical and electrical installations) are all shown graphically. Therefore, you must become familiar with these symbols, not only those of one particular trade, but those of all the trades. This is necessary so that complete coordination may be reached between the various trades. In the construction of a building, time and money may be saved by representatives of the different trades going over the plans and laying out the pattern to be followed. No trade can work independently of the others. If independence is attempted, confusion is created and some work must be done over to make all parts of the scheme fit together. During construction, the general contractor, the plumber, the steel workers, and the electrical and mechanical contractors must lay out the work together and determine from the drawings who installs what, where, and when.

On the job, the architect may have a representative present to assist in coordinating the work and in making decisions that may be required. In designing the building, the owner or builder will often draw a rough sketch, after which he or she sits down with the architect to discuss what the owner will need and want in a building design. The requirements are noted as to space, machinery, electrical loads, numbers of persons that will occupy the building and what the future requirements might be. The owner will sometimes have a rough sketch of ideas (see Figures 9-11 and 9-12). These need not be drawn to scale or with any degree of accuracy. They are merely ideas of what the owner might want. In this discussion, no elaborate plans are given. Simple plans are used, as they show the intent and fall into line with more detailed plans.

Notice that there are no details shown, merely a sketch of the spaces to be enclosed. After the sketch is drawn, the architect and owner can sit down and discuss details, at which time, no doubt, another freehand sketch will be drawn with more details. When a tentative solution is reached, the architect will make a preliminary drawing (see Figure 9-13).

When the owner has signed construction papers, the architect will start drawing up the final plans and all details. There are many preliminary things to do, such as surveying the land to see how much excavating will be required. The location of the property lines and the general drainage plan for the immediate vicinity must be considered, and the water, sewer, gas, telephone, and power lines that exist must be considered. Local regulations regarding types of construction permitted, setbacks, and so on, all must be taken into consideration.



Figure 9-11 Owner's sketch of the first floor of a residence.

The final drawings are sent to the plan checkers of the inspection departments having jurisdiction. Here, they are checked to see that they conform to local codes. Corrections are noted, or the plans are approved. Most specifications that accompany plans put the burden of following applicable local codes on the builders and contractors. When questions arise (such as an electrical or mechanical problem), the contractor involved takes these problems up with the architect or an assistant who, in turn, takes them to the engineer who has performed the design work.



Figure 9-12 Owner's sketch of the second floor of a residence.

There are various methods of bidding on plans. Sometimes, the general contractor gives the entire bid, and then calls for bids from subcontractors. This method has some advantages in that the general contractor is responsible for the entire job. At other times, the general contractor and each subcontractor bid their parts separately. This method has an advantage. The general contractor's percentage is removed from the subcontractors' bidding, and the owner has more control over who gets the bids. The details of the architect's sketches for the preliminary part are not important to the mechanic. Therefore, they will not be covered in this book. What the mechanic is interested in is how to perform part of the work.


FIRST FLOOR PLAN
BATH
B RM #1
9' × 11'-6"
DINING ROOM
11' × 11'-6"
KITCHEN
11'-4" × 11'-6"
REF
LINEN
HALL
OVEN BURNER
DV
CLOSET
CLOSET
B RM #2
11'-6" × 14'
LIVING ROOM
13'-6" × 22'
UP
LINEN
B RM/#4
14' × 16'
B RM #3
15'-3" × 16
BI-FOLD DOOR
CLOSET
OPEN WELL
CLOSET
BI-FOLD DOOR
SECOND FLOOR
PLAN

Figure 9-13 Architect's drawing (preliminary), without dimensions, of the owner's idea.

Typical floor plans of the first and second floors are shown in Figures 9-14 and 9-15. Figures 9-16 and 9-17 show typical floor plans of a first and second floor, with dimensions added. Figure 9-18 is a typical plan of a basement, with dimensions added. Figure 9-19 illustrates a typical detail of the basement wall, footings, and floor. Figure 9-20 shows a typical detail of the floor joists, brick veneering, and so on as they attach to the foundation.


KITCHEN
LIVING ROOM
DINING ROOM

Figure 9-14 A typical first-floor plan.


BATH
BEDROOM
BEDROOM
BEDROOM

Figure 9-15 A typical second-floor plan.

Graphic Symbols

In architectural drawings, a form of shorthand is used to illustrate what is to be installed and at what point or location the installation will be in the building. These are commonly known as *graphic symbols*.



Figure 9-16 A typical first-floor plan with dimension lines.


TILE FLOOR AND WALLS
BATHROOM
IL
DEN 8'-0" × 7'-6"
CLOSET
BEDROOM 15'-6" × 9'-6"
2" × 6" RAFTERS
BEDROOM
11'-6" × 9'-6"
FACE OF HOUSE
SHELVES
4" LEADER (COPPER)
EAVES OVERHANG

Figure 9-17 A typical second-floor plan with dimensions.


6" C I SHOE CONNECTS WITH 4" COPPER LEADER AT TOP OF WATERTABLE
7'
7'-4"
6'-8"
UNEXCAVATED
5'-8"
4'-6"
2'-10"
11'-4"
BOILER ROOM
6'-6"
22'
8" STEP UP
ASH DUMP
UNASSIGNED ROOM
20'-4" × 11'-9"
LAUNDRY
9'
3'-4"
WASHER
4'
STEEL SASH
12" × 18" CONCRETE FOOTING UNDER 10" CONCRETE WALL
4'-4"
3'-4"
3
7'-8"
UNEXCAVATED
32'-4"
3'-0"
3'-4"
4'-4"

Figure 9-18 A typical basement plan with dimensions.

Symbols are used in drawings to represent various parts and systems. You must also become familiar with these. Each trade has its own symbols, and the workers of each trade should learn to recognize the symbols of all the other trades. For example, the electrician should understand the plumber's symbols. The plumber should understand the carpenter's symbols, and so forth. In this way, each craftsperson will know what obstacles may be encountered in the work, and will be better prepared to cope with them.

In this section, the symbols shown are standards for the construction industry. However, you will find that some designers or individual institutions will deviate from these standards. Where this is done, a legend showing what the symbols mean should be added to the drawings.

A drawing consists of many different kinds of lines, each having its own purpose. Certain characteristic lines are used to convey different ideas, and the drafting practice has been rather well standardized as to the use of lines to avoid confusion in reading drawings. A good working drawing is as simple as possible, using only


2" × 8" SILL
5/8" × 10" ANCHOR BOLTS EVERY 6'
CONCRETE WATERPROOFING ASPHALT BASE
COARSE GRAVEL FILL
4" CONCRETE
6"
FLOOR REINFORCED WITH 2" MESH WIRE
6"
12"
PLASTIC WATERPROOF SHEET
4" SAND & GRAVEL
12" FILL
4" PERFORATED DRAIN TILE

Figure 9-19 **Detail of basement walls, footings, and floor.**


2" × 8" SILL
3 1/2" INSULATION
1"-T&G SHEATHING
1/2" AIR SPACE
3'-11"
ORIENTAL ROUGH BRICK SEE SPEC
1/2" WALL BOARD
BRICK TIES
1" × 4" BASE SHOE
OAK FLOORING
1/4" COPPER TUBE WEEP HOLES EVERY 2 SQ FT
2" × 10" JOISTS
5/8" CDX PLY SUB FLOORING
2" × 8" SILL
5/8" × 10" ANCHOR BOLTS

Figure 9-20 **Detail of floor, brick veneering, and so on.**


SHADE LINE FOR SHADED DRAWING
DOTTED LINE FOR INVISIBLE SURFACES
CENTER LINE
DIMENSION AND EXTENSION LINES
BROKEN LINE
FULL LINE FOR VISIBLE SURFACES
LINE FOR INDICATING POSITION OF A SECTION
USED FOR CONDITIONS NOT SPECIFIED
ABOVE AND ON GRAPHIC CHARTS, ETC.
MAY BE EITHER LIGHT OR HEAVY

Figure 9-21 Various lines used in drawing.



(A) WALL

(B) MASONRY WALL

(C) WALL

(D) SINGLE-SASH WINDOW

(E) SINGLE-SASH WINDOW (ALTERNATE)

(F) DOUBLE-SASH WINDOW

(G) DOUBLE-SASH WINDOW (ALTERNATE)

(H) DOUBLE-CASEMENT WINDOW

(I) TWO-SASH MASONRY WALL WINDOW

(J) BASEMENT SINGLE-SASH WINDOW

(K) OUTSIDE DOOR

(L) INSIDE DOOR

(M) DOUBLE-SWING DOOR

(N) SINGLE SLIDING DOOR

(O) DOUBLE SLIDING DOOR

(P) DOUBLE SWINGING DOORS

(Q) ARCH OR CASED OPENING

Figure 9-22 Symbols for walls, windows, and openings.

such lines as are necessary to give all of the required information. Moreover, the reader will not have to puzzle over a mass of lines that complicate the drawing. The same thing holds true for dimensions and other data. A good drawing is accurate and complete, though simple, and is therefore easily understood (read) by the carpenter.

Figure 9-21 shows the lines generally used on drawings.



PLAIN CHIMNEY

CHIMNEY WITH TILE

PLAIN CHIMNEY
DOUBLE FLUE

FIREPLACE WITH FLUE
FROM BELOW

FIREPLACE WITH
ASH DUMP

CORNER FIREPLACE
WITH TILE

Figure 9-23 Symbols for chimneys and fireplaces.



STAIRS GOING UP

STAIRS GOING DOWN

DOUBLE PLATFORM
OPEN STAIRS

OPEN STAIRS

BOXED IN STAIRS

Figure 9-24 Symbols for stairs.


ALL SYMBOLS ARE FOR PLANS AND SECTIONS UNLESS MARKED "ELEVATION"
ABBREVIATIONS
ALUMINUM........AL
ASBESTOS........ASB
BRASS........BR
CAST IRON........CI
CAST STONE........CS
CEMENT........DEM
CONCRETE........DONC
COPPER........DOP
GALVANIZED IRON........GI
GLASS........GL
HOLLOW METAL........HM
KALAMEIN........KAL
LIMESTONE........LS
PLASTER........PL
TERRA-COTTA........TC
WATERPROOFING........WP
WIRE GLASS........W-GL
WROUGHT IRON........WI
BRICK........
COMMON
FACE-ON
FIREBRICK-ON COMMON
STONE........
CAST STONE
CUT STONE
RUBBLE ELEVATIONS
WOOD........
FINISH
ROUGH
SHINGLES OR SIDING (ELEV)
GYPSUM........
PLASTER
BLOCK
SOLID PLASTER PART
GLASS........
LARGE SCALE
MARBLE........
INSULATION........
LOOSE FILL
BOARDS OR QUILTS
TILE (CERAMIC)...
LARGE SCALE
SMALL SCALE
CONCRETE........
STONE
CINDER
CAST BLOCK
CEMENT
TERRAZZO
EARTH, ETC. ....
EARTH
ROCK
CINDERS
SAND
METALS........
STEEL-IRON
BRASS-BRONZE
ALUMINUM
SHEET METAL
USUALLY USED FOR ALL METALS
TERRA-COTTA & HOLLOW TILE........
CLAY HOLLOW TILE
GLAZED-FACE HOLLOW TILE
HOLLOW-TILE FLOOR ARCH
ARCHITECTURAL TC ON BRICK
EXAMPLES
PLANS OF EXTERIOR WALLS........
EXTERIOR SIDE OF WALL
FACE BRICK
BRICK
CAST STONE
CUT STONE
ARCHITECTURAL TC
EXTERIOR SIDE OF WALL
CUT STONE
RUBBLE
RUBBLE
CLAY HOLLOW TILE
BRICK
CONCRETE-STONE
BRICK
CONCRETE BLOCK
GLAZED-FACE HOLLOW TILE
PLANS OF PARTITIONS........
INTERIOR
SOLID PLASTER
CONCRETE BLOCK
CLAY HOLLOW TILE
GLAZED-FACE HOLLOW TILE
BRICK-PLASTERED
GYPSUM BLOCK
STUD
SECTIONS OF FLOOR FINISHES........
TILE
MARBLE
WOOD
TERRAZZO
CEMENT
STONE
BRICK

Figure 9-25 Symbols for various materials.

Walls of frame buildings are represented on floor plans by two parallel lines spaced at a distance apart equal to the wall thickness (see Figure 9-22A). Masonry walls are shown on a floor plan by cross sectional lines, as shown in Figure 9-22B. Walls of all types of construction may also be shown as in Figure 9-22C, by heavy dark lines that save time in drawing and give a better print.

There are many and varied types of window construction, the symbols for some being shown in Figure 9-22D–J. The specifications should show the materials and types of construction, thickness of glass, and type of glass to be used. These details may be listed as a supplement to the specifications, or on the drawings if there is room.

There are many types of doors that will be used, the symbols for some of these being shown in Figure 9-22K–Q. There may also be special doors used, and where this is called for, a drawing showing the detail should accompany the main drawing. Detailed sketches or drawing inserts should show all details of sills, especially where masonry construction is to be used. In drawings, the dashed line should be avoided where it is intended to indicate some part that is in view. The dashed line is ordinarily intended to represent some hidden feature or part.

Figure 9-23 shows a few conventions or symbols for chimneys and fireplaces. There may be special features that should be shown in additional drawings. In each case where details are required, a notation should be added referring to the detail drawings.

Stairs must be identified as to their direction, and whether they are boxed or open. Figure 9-24 shows some methods of identification. Arrows show the direction of the stairs.

Figure 9-25 shows symbols for the identification of materials.

If confused as to an abbreviation while reading a drawing, considering the nature of the work will be helpful in interpreting the abbreviations. It should be understood that these abbreviations relate only to one part of the subject. For every field (such as carpentry, electrical work, and so on), there are many conventions relating to each individual field. Table 9-1 shows common abbreviations used in construction drawings.

Table 9-1 Common Abbreviations Used in Construction Prints

Construction Feature	*Abbreviation*
Access door	AD
Access panel	AP
Acoustic	ACST
Aggregate	AGGR
Aluminum	AL
Anchor bolt	AB
Angle	ANG
Apartment	APT
Area	A
Area drain	AD
Asbestos	ASB

(continued)

Table 9-1 (continued)

Construction Feature	*Abbreviation*
Asbestos board	AB
Asphalt	ASPH
Asphalt tile	A Tile
Automatic washing machine	AWM
Basement	BSMT
Bathroom	B
Bath tub	BT
Beam	BM
Bearing plat	BRG PL
Bedroom	BR
Blocking	BLKG
Blueprint	BP
Boiler	BLR
Bolts	BT
Book shelves	BK SH
Boundary	BDY
Brass	BR
Broom closet	BC
Building line	BL
Cabinet	CAB
Caulking	CLKG
Casing	CSG
Catch basin	CB
Cellar	CEL
Cement floor	CEM FL
Center	CTR
Center-to-center	C to C
Center line	C/L
Ceramic	CER
Channel	CHAN
Cleanout	CO
Clear glass	CL GL
Closet	CLO
Cold air	CA
Cold water	CW
Conduit	CND

(continued)

Table 9-1 (continued)

Construction Feature	*Abbreviation*
Counter	CTR
Cubic feet	CU FT or FT^3
Detail	DET
Diagram	DIAG
Dining alcove	DA
Dining room	DR
Double-acting door	DAD
Double-strength glass	DSG
Drain	D or DR
Electric panel	EP
End to end	E to E
Excavate	EXC
Expansion joint	EXP JT
Finished floor	FIN FL
Firebrick	FRBK
Fireplace	FP
Fireproof	FPRF
Flooring	FLG
Flush	FL
Footing	FTG
Foundation	FND
Frame	FR
Garage	GAR
Gas	G
Gage	GA
Gypsum	GYP
Hall	H
Hardware	HWD
Hose bibb	HB
Hot air	HA
Hot-water tank	HWT
I-beam	I
Inside diameter	ID
Insulation	INS
Iron	I
Kitchen	K

(continued)

Table 9-1 (continued)

Construction Feature	***Abbreviation***
Knocked down	KD
Landing	LDG
Lath	LTH
Living room	LR
Main	MN
Matched and dressed	M & D
Maximum	MAX
Medicine cabinet	MC
Minimum	MIN
Miscellaneous	MISC
Mixture	MIX
Mortar	MOR
On-center	OC
Pantry	PAN
Partition	PARTN
Plaster	PLAS
Plate	PL
Porch	P
Precast	PRCST
Prefabricated	PREFAB
Pull switch	PS
Radiator	RAD
Recessed	REC
Refrigerator	REF
Register	REG
Revision	REV
Riser	R
Rivet	RIV
Room	R or RM
Rubber tile	R Tile
Screen	SCR
Section	SECT
Sewer	SEW
Shelving	SHELV
Shower	SH
Single-strength glass	SSG

(continued)

Table 9-1 (continued)

Construction Feature	*Abbreviation*
Sink	S or SK
Soil pipe	SP
Square feet	SQ FT or FT^2
Stairs	ST
Standard	STD
Switch	SW or S
Storage	STG
Telephone	TEL
Thermostat	T or THERMO
Tongue-and-groove	T&G
Unexcavated	UNEXC
Vent	V
Vinyl tile	V Tile
Washroom	WR
Water	W
Water closet	WC
Water heater	WH
Weatherstripping	WS

Summary

Drawings are a means of communication between the designers and the builders. They are used on the construction site for reference by the trade workers and as a record of how the building was actually built. The building is represented with various views (such as plans and elevations). Complex views of the building are shown with sections. Sections are like a slice of the building that opens up the interior to a view. A floor plan is a horizontal slice.

Drawings are made to scale. There is a consistent relationship between the length of lines on the drawing and the size of the building and its parts.

Drawings are developed in phases that allow the designer to set the owner's requirements down on paper and show how the design can be changed to meet various functional and legal requirements.

A drawing is made up of symbols that represent the various parts of the building and where those parts will be installed during construction. The symbols are usually standardized so everyone knows what they mean. Simple symbols like lines are used to define the basic shape of the structure. Complex symbols indicate doors, windows, stairways, and other common parts of the building.

Review Questions

1. What is the basic purpose of using drawings in construction of a building? How is this accomplished?
2. Why are the drawings updated during construction?
3. What part of a building does an elevation show?
4. What part of a building does a section show?
5. Why are drawings reduced in size by scaling?
6. Who, besides the carpenters and builders, uses the drawings of a construction project?
7. What do graphic symbols do in a drawing?
8. Draw the symbol for a door and a window.

Chapter 10

Building Styles Explored

Today's homes may resemble those from the New England days of the 1600s, or they may look more like a manufactured-in-the-factory house. There is a large range of styles and looks available for those looking for a new home. Contractors have plans and even model homes to aid in making a selection. There are even certain suggested styles and limits to housing designed for the retired couple with no adult children living with them. Everywhere you look, you see evidence of a variety of tastes expressed in living quarters. Here, we will be exploring some of those styles and learn how to make an educated choice for your next home.

The Two-Story New England Colonial House

Many houses of the Colonial style of architecture, built in the late 1600s, are still standing in the New England states.

Many of the original houses were built to accommodate larger families, but certain architectural details were common to all of them (see Figures 10-1 and 10-2). One feature found in most of the original houses is moderate to steep roof slopes, often the one-third pitch. This was necessary to allow the use of wood shingles or shakes, about the only roof covering then generally available. Narrow eaves (with little or no projection at the gables) had the lap siding cut against wide corner boards. Plank frames were used for the windows, and there were no casings (or very narrow casings) outside. Entrances, however, were usually elaborate, sometimes with finely scrolled and carved pediments. Good, authentic replicas of many of these entrances are obtained today. In the later and more pretentious houses built in this era, sidelights were often used at the entrances, and sometimes the doors were double. The relatively wide pilasters at the sides were usually fluted or molded. A type of door that originated in England is paneled three high and two wide, with the top pair of panels smaller (nearly square). The rails in the upper part of the door form the Christian cross.

The front of the house was symmetrical about the central entrance. Although there were some exceptions to this design, symmetry was the rule. Invariably, second-story windows were placed directly over lower story openings. Small covered entrances were uncommon, porches and verandas virtually unknown. The central entrance hall was universal, with the stairway to the upper floor. In the earlier and smaller Colonial houses, the stairway


ASPHALT SHINGLE ROOF

Figure 10-1 Front elevation of a Colonial-type home.



Figure 10-2 Right side elevation of a Colonial-type home.

was often steep and tortuous, often with tricky winders. However, in the later and better homes, the stairs were often beautiful, tastefully designed and elaborately carved, with superb craftsmanship. Such stairs cannot be duplicated today.

While the basic design was rectangular, many of the Colonial homes had attached ells or sheds. With a roof continuous down over a one-story shed at the rear, this house becomes the well-known *saltbox*, with a claim to fame all its own. All types of Colonial homes use windows of small glass or lights, often rectangular, sometimes diamond-shaped. In the early days, the muntins were often made of lead. Later, wood muntins were used. Large sheets of glass were almost unknown, and very expensive.

A predominant feature in the Colonial house is the *privacy* afforded, the privacy that is lacking, and so often deplored, in many modern designs. There are no unnecessarily large areas of glass to give one the eerie feeling of being spied upon at night.

Aside from the fact that this house is excellent architecturally, it need not be an expensive house (relative to other houses) to build. The downstairs bathroom is convenient, and the two complete bathrooms upstairs help prevent congestion (see Figures 10-3 and 10-4). A complete basement is suggested for convenience to heating and



Figure 10-3 First-floor plan of a Colonial-type home.


BATH
BEDROOM
BATH
DOWN
BEDROOM
30'0"
BEDROOM
BEDROOM
36'0"

Figure 10-4 Second-floor plan of a Colonial-type home

plumbing, plus storage space. Included in the original plans is an adjacent garage. It has a covered breezeway connecting with the outside door of the family room.

A House of Modern Architecture

Architects who have pride in their originality often prefer an unusual custom design (see Figure 10-5). This does not mean that a house of unusual appearance such as this one, no matter how



Figure 10-5 A house of modern architecture.

good the appearance, can be placed on the odd lot in a street of Colonial houses and have a pleasing effect. Houses such as this one need a proper setting, preferably a rugged and individual setting.

The design is bold, and reflects the lively imagination of its designer. Usually, modern practice makes use of large areas of glass, but these areas are effectively shaded by the wide overhangs, which make them much more acceptable than the large unprotected areas of glass in many modern designs.

The outstanding feature of this house is the roof. Although decidedly unusual, the pitches are regular (all 45°), and the roof is composed of simple intersecting planes. The roof framing is actually rather simple, for there are no *warped* planes. The architect has used diagonal lines on the roof instead of the commonly used vertical and horizontal accents. The effect is striking, especially on a sloping site, but working drawings are available that adapt it to level sites as well.

Although imaginative and unusual, the plan is in right-angled shapes for ease and economy of construction. The roof is formed of intersecting planes, with steep pitches. The roof treatment is important, because it dominates the entire view.

In the plans, designations of rooms, and dimensions, are intentionally omitted (see Figure 10-6 and Figure 10-7). Naturally, the uses of the rooms will depend upon the contour of the ground. The large room with the fireplace will undoubtedly be used for a living room, depending upon whether the entrance is at the second-story level (as it may be if the house is built on a sloping site), or at the first floor level (as it may be if the ground is level). The plan is flexible enough to allow considerable leeway in deciding upon the exact room arrangements and their subsequent uses.

In general, the walls are 12-inch lightweight concrete blocks, their cavities filled with insulation, with head joints cut smooth, and horizontal joints struck. The roof is sheathed with plywood (see Figure 10-8). With a roof so steep, many types of roof coverings may be used, but probably one of the modern types of mopped-down roof covers would be most acceptable, with granule-coated roll roofing as a cap sheet. The horizontal and diagonal rooflines are obtained by the use of battens.

The Contemporary House

Figure 10-9 shows a house called *contemporary architecture*. It embodies most of the features desired in homes of the present era, including the following:



Figure 10-6 The lower-floor level of the modern house. If the entrance is at this level, the room with the fireplace will certainly be used as the living room.

- House is a split-level (not a new idea, but always popular).
- House allows adequate windows in the lower-level rooms, and the stairway down is short.
- Living room is moderately large, and, with the connected dining area, it is ample for the needs of most moderately large families.
- Bedrooms are all of practical, usable size. The spare room in the basement is a useful stand-by.
- Access door to the two-car garage is convenient.
- Family room and the party room in the basement remove some of the inevitable activities of a large family from the living room.
- Concrete patio at the rear is convenient for the usual outdoor living activities of the modern family.

Glass has been used with discretion. Although the glazed areas are moderately large, they are not unreasonably so, at the expense of privacy and to the detriment of heating and air conditioning.

Architecturally, this house is susceptible to many variations of materials. In the house illustrated in Figure 10-9, uncoursed native



Figure 10-7 The upper-floor level. If the entrance is at this level, the room with the fireplace will certainly be used as the living room.

stone has been tastefully used, with vertical siding on the overhanging upper story.

The roof has sufficient pitch to fill its primary function that is to shed water, but it also gives a lower *spread-out* look to the house.

It is possible with the proper use of a steel beam to enlarge the party or family room. This could be done by removing the wall between party room and spare room, to make one big room in an L shape (see Figure 10-10).

Utility Pole-Type Building

The pole-type building requires no foundation (see Figure 10-11). It is mounted on round pole vertical members that are set in the ground and adequately anchored to resist uplift. For most buildings of appreciable size, the poles are set in round holes about 5 feet deep. Projecting nails or lag screws are placed in the pole 6 to 8 inches from the bottom, or holes are bored through which tight-fitting pieces of rod are driven to project a couple of inches on



Figure 10-8 The roof framing plan of the modern house.



Figure 10-9 A split-level house.


GARAGE
19-8 × 23-2
LAUNDRY
12-2 × 8-7
LAV.
DINING ROOM
12-6 × 10-0
KITCHEN
10-4 × 16-7
LIVING ROOM
20-3 × 15-0
PATIO
FAMILY ROOM
20-5 × 14-6
DN
UP
ENTRY
CL.
CL.
BATH
BEDROOM 3
13-2 × 10-2
BATH
L
CL.
MASTER
BEDROOM
15-2 × 12-2
BEDROOM 2
13-2 × 10-2
PLAN 2054-1A
WIDTH 90-0
DEPTH 33-0
197 SQUARE FEET
STORAGE
8-0 × 8-9
UP
STOR.
CL
STOR.
LAV.
CL.
SPARE ROOM
12-4 × 12-8
PARTY ROOM
26-8 × 12-8
LOWER LEVEL PLAN
795 SQUARE FEET

Figure 10-10 Floor plans for the contemporary house.



Figure 10-11 A pole-type building.

each side. After the poles are placed and positioned in the holes provided, about 12 inches of concrete is poured around the bottom ends and the holes filled with earth (see Figure 10-12).

Satisfactory joining of rafters and other framing members to the round poles may be made to properly use any standard connecting device (including plain bolts, split-ring connectors, toothed-ring connectors and plain-shank common nails).



Figure 10-12 Enlarged detail of a pole-and-truss connection.

The idea of the pole-type building is not new. This type of construction was well-known at least 75 years ago, but it was generally used only on inexpensive and temporary buildings. The modern pole building can hardly be placed in this category. The poles used are now pressure-treated with a preservative and have a long life even under most adverse conditions. Modern timber fastenings are far superior to anything that our forefathers had available.

Where rafters or trusses connect to the poles, it is preferable that the poles be flattened at the contacting surfaces (see Figure 10-13). Cast-iron spike-grids, with one side curved to conform to the round side of the pole, have been satisfactorily used. However, simple bolts are also often used.



Figure 10-13 A bent of a pole-type hay storage barn, with feeding fence and canopy at the right. Roofs of these buildings may be trussed, eliminating the interior poles. Bents may be set 12 to 16 feet on centers.

Summary

Many of the two-story New England houses built in the 1600s are still standing today. Features found in most original houses were steep roof slopes, wood shingles, narrow eaves, and wide corner boards. The siding was always narrow when used in conjunction with the wide corner boards. Entrances, however, were usually elaborate, sometimes with finely scrolled and cornered pediments.

The contemporary house could be considered a modern home of the present era. Among the many styles in contemporary homes is the split-level, popularly called the tri-level. There are advantages to this type of house. The same space built in a split-level house will cost less than when it is built in a one-story.

A pole-type building (the most popular being the barn style) requires no foundation. The buildings are framed on round poles set in the ground and adequately anchored to resist uplift. The idea for pole-type buildings is not new, as this type of construction was well known at least 75 years ago.

Review Questions

1. What type of house was constructed in the 1600s?
2. What is a split-level house?
3. What are some advantages in the split-level house?
4. Give a few advantages and disadvantages of a basement.
5. What is a pole-type building?
6. What type of house is referred to as a ranch house?
7. What is the primary purpose of a roof?
8. Why would houses located in heavy snow areas have high-pitched roofs?
9. How old is the pole-type building for houses?
10. The ______ house could be considered a modern house of the present era.

Appendix

Construction Hardware

Information provided in this appendix is reproduced with permission from USP Lumber Connectors (United Steel Products Company, Inc.), a company that has been manufacturing and marketing construction hardware for more than 40 years. This information has been culled from the *Engineered Lumber Construction Hardware Product Guide and Design Manual* (Montgomery, Minnesota: United Steel Products Company, 1996).

You may contact the company's corporate offices at the following address:

Box 80
703 Rogers Drive
Montgomery, Minnesota 56069
1-800-328-5934

NDS Standards

The load resistance values presented in this appendix reflect the calculation criteria set forth in the *National Design Specification for Wood Construction* (NDS) published by the American Forest and Paper Association.

Because of this update, load values presented in previous publications may not match those presented in this catalog. The values shown in this appendix supercede those previously printed. An ongoing process is now underway to incorporate these new values in USP code reports. This will be done when each report is scheduled for reevaluation. Any questions about current code listings should be directed to the Technical Service Department at 1-800-328-5934.

NOTE

1) USP Lumber Connectors reserves the right to change specifications, designs and models without notice and liability for such changes. This appendix may not be reproduced in whole or in part without the prior written approval of USP Lumber Connectors.

2) This appendix reflects design changes and design load adjustments to some USP products. The information presented in this appendix supersedes all conflicting information published in previous documents

3) This appendix was designed as a general reference for the USP Product Line. Various specialized publications have been developed for design professionals, truss manufacturers, contractors, retail dealers, and building material wholesalers. Product load values may vary from one publication to another because of recent product testing or changes in regulations.

4) To achieve the allowable loads presented in this appendix, all specified fasteners must be used and proper installation procedures observed. Verify that the dimensions of supporting members are sufficient to receive specified fasteners. No product modifications are allowed without the written permission of USP Lumber Connectors.

5) Some connector models are listed more than once to indicate additional nailing options.

6) Nails specified as 8d, 10d, 16d, and 20d are common wire nails.

7) Bolts specified conform to ASTM A 307 standards or better

8) Products are sized for standard dimensional lumber or EWP sizes. For unusual supporting conditions, excessive shrinkage, or hostile environments, contact USP Lumber Connectors.

Code Evaluations

Most USP structural products listed in this catalog have been evaluated or are in the submittal stage for evaluation from one or more of the following code authorities:

- *CABO*—Council of American Building Officials (NER Report), National Evaluation Service.
- *ICBO*—International Conference of Building Officials.
- *BOCA*—Building Officials and Code Administrators International Inc.
- *SBCCI*—Southern Building Code Congress International, Inc.
- *METRO*—Dade County, FL.
- *DSA*—Division of State Architect, California.
- *LA CITY*—City of Los Angeles, California.
- *TDI*—Texas Department of Insurance.

Product Design Loads

The design loads listed are the lowest result obtained by one of the following methods:

- The ultimate tested load divided by three.
- Load producing 1/8-inch deflection.
- Nail I Bolt values based on 1991 NDS.

Durations of load adjustments for mechanical fastenings are as follows:

- Floor/Design Loads—No increase for duration of load.
- Roof Snow—115% of Design Load for two-month duration of load.
- Roof Nonsnow—125% of Design Load for seven-day duration of load.
- Uplift—133% or 160% of Design Load for wind I seismic loading.

All calculated load values shown in this publication reflect criteria established by the *1991 National Design Specification* (NDS).

Header Materials

- *I-Joist*—I-Joist with similar width to the supported I-joist
- *LVL*—Laminated Veneer Lumber
- *PSL*—Parallel Strand Lumber
- *LSL*—Laminated Strand Lumber
- *DF/SP*—Douglas Fir Larch/Southern Yellow Pine Grade 2 or better
- *SPF*—Spruce/Pine/Fir
- *2× Nailer*—DF/SYP Nailer

NOTE

Charts without specific header callouts ensure DF/SYP.

Testing

On all structurally rated products, USP performs full-scale testing to meet ASTM 0 1761, which is the testing standard recognized by all model agencies. All final testing is witnessed by an independent third-party testing laboratory.

Fasteners

A. *Nails*—Shall be common wire nails. Where special nails are required for the hanger, the manufacturer will furnish all 20d nails and larger, which are shorter than common wire nails of same pennyweight. Special nails shall be furnished by manufacturer.

B. *Bolts*—Where required, shall be of nominal size shown on drawings and shall be furnished by the contractor.

C. *Expanding Anchors*—Use where shown on the drawing; furnished by contractor.

D. *Lag Bolts*—Shall be nominal size shown in drawings; furnished by contractor.

Execution

Examination

A. Verify that the wood that is to support the hanger is flat, is free of large cracks or splits, and is of the species noted on the plans. If the lumber or wood is not Douglas Fir-Larch or Southern Yellow Pine, reduction of the manufacturer's published load values, in accordance with the Building Code, is required. (A design professional shall reduce the published values in accordance with UBC Chapter 23 or the National Design specification of the American Forest and Paper Association.)

Installation

A. Use only nails of size shown in manufacturer's literature.

B. Fill all nail holes with nails as shown in manufacturer's literature.

C. Except where noted in manufacturer's literature, all nails are common wire nails and should be driven at right angles to the hanger body and seated fully.

D. *Do not* use roofing nails, which are not equivalent to common wire nails. DO NOT use nails that are shorter than $1^1/_2$ inches.

E. *Do not* use pneumatic or electric driven staples.

F. If power nail drivers are used, the nails shall be driven through the hole furnished in the hanger and shall not be driven through the hanger where no hole exists.

G. If wood I-joists are used, the maximum nail that can be driven into the top or bottom flange is a 9 gauge × $1^1/_2$ inches long (10d × $1^1/_2$ inches). The maximum nail that can be driven into the web is a 16d nail.

H. When installing hangers to laminated veneer lumber (LVL), the maximum size nail that can be driven into the narrow face is 16d and the maximum size nail that can be driven into the wide face is 20d.

I. Hangers shall be installed tight against the supporting member.

J. The carried member shall be of sufficient length to maintain full bearing on the seat of the hanger. The carried member shall not fit tight (squeeze fit) against the carrying member. A gap of up to $^1/_4$ inch between the carried member and the carrying member is acceptable.

K. Before nailing the carried member into the hanger, take care to fully seat the member so that no space exists between the hanger and the bottom of the carried member. Where safe and practical, do not fasten the carried members to the hanger until floor sheathing has been installed. On some hangers, two diamond holes are located in the bottom of the seat that allow for wood screws to be installed. The screws pull the wood into the seat for positive bearing. Use 2 each #6 × $1^1/_4$-inch wood screws or #6 × $1^1/_4$-inch drywall screws.

L. Where bolting, use a wood template to accurately locate the holes. Drill hole $^1/_{32}$ inch minimum to $^1/_{16}$ inch maximum larger than the bolt diameter it is to receive. The bolt is to be tapped through the hole and connecting device with a hammer or mallet. Always use a washer under the head or nut if it is not in contact with a steel plate or hanger.

M. Lag bolts are not to be used in lieu of bolts unless specified.

N. Screws are not to be used in lieu of nails unless specified.

O. Use only stainless steel nails with stainless steel hangers.

P. Where wood connecting devices are attached to concrete, take care to install the device plumb, square, and true. If practical, use a plywood template to accurately locate the device.

Q. Anchor bolts, furnished and installed under Section 03300 *Cast-in-Place Concrete* shall be accurately located, plumb, and true before wood connecting devices are attached to the anchor bolts.

R. Where prefabricated structural wood is installed into the hanger, follow the written instructions of the prefabricated wood manufacturer in nailing, bearing support, bracing, and installation.

Wood I-Joist Installation to Wood

Sloped I-Joists

Use hangers with sloped seats whenever the slope exceeds the following: $^1/_2$:12 for seat bearing lengths of $2^1/_2$ inches or less; $^3/_8$:12 for bearing lengths between $2^1/_2$ inches and $3^1/_2$ inches; and $^1/_4$:12 for bearing lengths in excess of $3^1/_2$ inches.

Multiple I-Joists

Fasten together multiple plies of wood I-joists, in accordance with the manufacturer's installation guidelines, such that the joists act as a single unit.

Rotation on I-Joists

It may be necessary to install straps, blocking or sheathing to restrain torsional rotation of a supporting wood I-joist when using top mount I-joist hangers.

Fasteners

Install only the specified nails. The flanges of wood I-joists may split if larger diameter nails or longer nails are installed. Do not install nails larger than 16 penny common (0.162 inch diameter) into the web stiffeners in the wood I-joist.

Backer Blocks

Pattern the nails used to install backer blocks or web stiffeners in wood I-joists to avoid splitting the block. The nail pattern should be sufficiently spaced and avoid the same grain line, particularly with solid sawn backer blocks. Backer blocks must be installed on wood I-joists acting as the header, or supporting member. Install in accordance with the I-joist manufacturer's installation guidelines, with the backer blocks seated against the bottom flange of a supporting header when using the face mount hangers, and against the top flange if using top mount hangers. The nails installed to hangers mounted to an I-joist header must penetrate through the web and into the backer block on the opposite side.

Top Flange Hangers

The thickness of the metal and nail heads on top mount hangers must be evaluated for the effect on subsequent sheathing. Ensure the top mount hanger is installed such that the flanges of the hanger are not "over-spread" which tends to elevate the supported I-joist, causing uneven floor surfaces and squeaking. Similarly, ensure the hanger is installed plumb such that the face flanges of the hanger are mounted firmly against the wide-face surface of the header.



FLUSH FRAMING



HANGER OVER-SPREAD



HANGER NOT PLUMB

Support Height and Lateral Stability

Hangers without web stiffeners must support I-joist top flange and provide minimum 250-pound lateral resistance with no more than 1/8″ horizontal deflection.


1/8" Maximum Gap
Resist 250 lb.
Lateral Minimum

Without Web Stiffeners

Hangers for joists with web stiffeners must support a minimum of 60% of joist depth.


Web Stiffener
Joist Depth
60% Min.

With Web Stiffeners or Solid Members

Wood I-Joist Installation to Steel I-Beam

Correct Hanger Attachment to Nailer



Avoid direct contact between hangers and steel beams, which may cause squeaks.

A nailer or sill plate is considered to be any wood member attached to a steel beam, concrete block wall, stem wall, or other type of support which is unsuitable for nailing, and is used as a nailing surface for top mount hangers to hold beams or joists.

Nailer Sized Correctly

Top flange of hanger is fully supported and recommended nails have full penetration into nailer, resulting in a carried member hanging safely at the proper height.

The nailer must be sized to fit the support width as shown and be of sufficient thickness to satisfy recommended top flange nailing requirements.

NOTE

A design professional must specify nailer attachment to steel beams.

Wrong Nailer Size Can Cause Component Failure

Too Narrow

Top flange not fully supported can cause nail breakout. Or, by fully supporting top flange, hanger is tilted back causing lifting of carrying member which results in uneven surfaces and squeaky floors.





Too Wide

Loading can cause cross grain breaking of nailer. The recommended nailer overhang is $^1/_4''$ maximum per side.



Too Thin

Top flange nailing cannot fully penetrate nailer, causing reduced allowable loads. Never use hangers which require multiple face nails since the allowable loads are dependent on all nail holes being used.

Welded Installation

Where shown in charts, hangers may be welded.
The minimum weld to the top flange is listed in the chart below.

Steel	*Weld*
10 gauge or lighter	$^1/_8'' \times 1^1/_2''$ each end
7 gauge	$^3/_{16}'' \times 1^1/_2''$ each end
3 gauge	$^1/_4'' \times 1^1/_2''$ each end



When welding galvanized steel, remove zinc coating by grinding before welding. Chip and touch up weld with primer.

Caution

Use proper respiratory protection when welding galvanized steel.

Top-Mount Hangers THO Series

This top mount hanger is engineered for I-joist to header applications. The THO offers full lateral support of the I-joist top chord which eliminates the need for web stiffeners in most applications. Raised dimple nailing guides help assure correct 45° nailing into the I-joist bottom chord. The new Seat Cleat™ prongs allow builders to“pop” I-joists into hangers for quick, positive seating, Seat Cleats™ are not yet available on all THO models.

Finish . . . . G60 galvanizing
Code Listing . . . . NER 478
U.S. Patent . . . . #5,217,317
Seat Cleat Patent . . . . applied for



THO



Seat Cleat ™ helps lock I-joist into place for positive seating and nailing ease.

Beam and Purlin Hangers BPH and HBPH Series

These BPH hangers are used to support LVL, LSL and PSL beams and headers in light-to-medium load conditions. The slantback design incorporates strength and economy. An open back design allows the builder to install the BPH after the beam is in place.

Finish . . . . G60 galvanizing
Code Listing . . . . NER pending



Typical **BPH** Installation



BPH / HBPH Similar

Beam Hangers LBH and HLBH Series

These heavy-duty beam hangers are specially designed for use in concentrated load conditions. The continuous top angle design offers high load values with minimum nailing. Many specialty options are available.

Finish . . . . paint
Code Listing . . . . NER pending
Specialty Options . . . . see page 22



HLBH



LBH / KGLT Similar

I-Joist Hangers PHI Series

The PHI series is specifically designed to support single-ply I-joists on I-joist headers. The PHI features a continuous top flange for increased strength. These hangers have also been engineered so that the top flange "depth" will match hanger seat width. This ideally places the top flange nails behind the I-joist's center web when the support joist is the same width. Joist nailing and top lateral support allows for installation without web stiffeners.

Finish .... paint
Code Listing .... NER pending
Specialty Options .... see page 22



PHI


Assures ideal nail location on I-joist headers of similar width.
No web stiffener required.

Beam and Purlin Hangers PH, PHM, PHX Series

Used to hang LVL, LSL and PSL beams and headers in medium load conditions using standard nails. The continuous top flange offers the best loading capacity with minimum nailing. A wide range of specialty options is available for diverse applications.

Finish .... paint
Code Listing .... NER pending
Specialty Options .... see page 22



PH / PHM similar / PHX similar


Top flange reduces prying action.

Masonry Hangers MPH Series

Specially designed to work with standard 6-inch concrete block or larger wall construction. The MPH eliminates the need for masons to fabricate special seats to support I-joists or composite wood beams. They can be easily slid into position while a mason is laying block and fastened by setting two 16d duplex nails into the concrete bed. Continuous top flange style gives strength with minimal fastening.

Finish .... paint
Code Listings .... NER 505
Specialty Options ....see page 22



MPH


(2) 16d duplex nails...A 16d Duplex Nail is 0.162 inch in diameter by 3-$^1/_2$ inches long with a double head.

Top Mount Hangers

					Dimensions					Fastener Schedule		100% Allowable Loads (LBS.)								
Joist (Inches)	USP Stock No.	Reference Number	Web STFNR Reqd	Steel Gauge	W	H	D	L	TF	Header	Joist	I-Joist	LVL	PSL	LSL	DF/SYP	SPF	†2 × Nailer	††Welded	†††Masonry
7 × 30	HBPH7130	HB1430-2	√	7	$7^{1}/_{8}$	30	3	—	$2^{1}/_{2}$	(10)NA25	(6)NA25	—	—	—	—	5345	3980	—	—	—
	PHX7130	HW1430-2	√	$^{3}/_{10}$	$7^{1}/_{8}$	30	$2^{1}/_{2}$	10	3	(4)16d	(2)10d	—	6015	5680	5755	5045	4230	—	—	—
	LBH7130	GLTV430-2	√	10	$7^{1}/_{8}$	30	4	12	$3^{1}/_{8}$	(9) NA16DRS	(6)16d	—	6500	6560	6010	6400	6400	—	—	—
	HLBH7130	HGLTV430-3	√	7	$7^{1}/_{8}$	30	6	12	$3^{1}/_{8}$	(15)NA16DRS	(6)16d	—	10620	10370	9600	9600	8915	—	—	—
	KGLT3530-2	—	√	$^{3}/_{7}$	$7^{1}/_{8}$	30	5	10	$2^{1}/_{2}$	(10)NA25	(6)NA25	—	—	—	—	8205	—	—	—	—
7 × 32	PHX7132	HWI432-2	√	$^{3}/_{10}$	$7^{1}/_{8}$	32	$2^{1}/_{2}$	10	3	(4)16d	(2)10d	—	6015	5680	5755	5045	4230	—	—	—
	LBH7132	GLTV432-2	√	10	$7^{1}/_{8}$	32	4	12	$3^{1}/_{8}$	(9)NA16DRS	(6)16d	—	6500	6560	6010	6400	6400	—	—	—
	HLBH7132	HGLTV432-2	√	7	$7^{1}/_{8}$	32	6	12	$3^{1}/_{8}$	(15)NA16DRS	(6)16d	—	10620	10370	9600	9600	8915	—	—	—

NOTE: See HEADER MATERIALS on page 3 for specific header information.
†For 2× Nailer installation, substitute 10d × $1^{1}/_{2}''$ nails for header nailing and fill top and upper face nails, If any. Refer to nailer installation on page 9.
††Refer to welded installation detail on page 8.
†††Refer to masonry installation detail on page 10.

MPH, PH, PHI, PHM, and PHX Series Options

Option	*Skewed*	*Sloped*	*Sloped/Skewed*	*Top Flange Offset*	*Saddle*	*Sloped Top Flange*
RANGE	1° to 60°	1° to 45°	skew 1° to 45° sloped 1° to 45°	—	—	0° to 35°
ALLOWABLE LOADS	100% of table load.	100% of table load.	100% OF TABLE LOAD UP TO MAX LOAD OF: PHX - 3500 lbs. PHM - 3000 lbs. PH - 2500 lbs.	HANGER WIDTH: %OF TABLE LOAD: $3\frac{1}{2}''$ or less 60% $3\frac{9}{16}''$ to $5\frac{1}{2}''$ 75% $5\frac{9}{16}''$ to $7\frac{1}{2}''$ 85%	100% of Table Load per side.	Reduce-allowable table loads using Straight-Line Interpolation.
ORDERING	Add SK, angle required and right (R) or left (L), to product number. Ex. PH1795-SK45R	Add SL, slope required, and up (U) or down (D), to product number. Ex. PH1795-SL30D	See sloped and skewed. Ex. PH1795-SK45RSL30D	Add OS offset required, and right (R) or left (L), to product number. Ex. PH1795-OSL	Add SA, and saddle width required to product number. Ex. PH1795-SA = $5\frac{1}{2}''$	Add SF, angle required, and right (R) or left (L), to product number. Ex. PH1795-SF30L

Sloped/skewed hanger with skews greater than 15° may have all joist nailing on outside flange. Sloped or sloped/skewed hangers with slopes greater than 15° may have additional joist nails added.

All sloped, skewed or combinations require bevel cut on joist in all applications and bearing stiffeners with I-joists.

LBH and HLBH Series Options

Option	***Skewed***	***Sloped***	***Sloped/Skewed***	***Top Flange Offset***	***Saddle***
RANGE	1° to 50°	1° to 45°	skew 1° to 45° sloped 1° to 45°	—	—
ALLOWABLE LOADS	LBH - 4725 lbs. max. HLBH - 8070 lbs. max. LBH / HLBH - 50% of uplift load on skew greater than 15°.	LBH - 4110 lbs. max. HLBH - 7000 lbs. max.	LBH - 3900 lbs. max. HLBH - 6650 lbs. max. LBH/HLBH- 50% of uplift load on skew greater than 15°.	60% of table load for LBH. 45% of table load for HLBH.	100% of table load per side.
ORDERING	Add SK, angle required, and right (R) or left (L), to product number. Ex. LBH3595-SK 45R	Add SL, slope required, and up (U) or down (D), to product number. Ex. LBH3595-SL30D	See sloped and skewed. Ex. LBH3595-SK45RSL30D	Add OS, offset required, and right (R) or left (L), to product number. Ex. LBH3595-OSL	Add SA, and saddle width required to product number. Ex. LBH3595-SA=$5^{1}/_{2}''$

Sloped / skewed hanger with skews greater than 15° may have all joist nailing on outside flange. Sloped or sloped / skewed hangers with slopes greater than 15° may have additional joist nails added. All sloped, skewed or combinations require bevel cut on joist in all applications and bearing stiffeners with I-joists.



Left **Skewed** Seat



Down **Sloped**
& Left **Skewed** Seat



Down **Sloped** Seat



Sloped Top Flange
Down Left, Low Point



Right **Top Flange Offset**



Saddle

Face Mount Hangers HD and HHD Series

These HD/HHD models are specifically designed to support LVL, LSL and PSL beams and headers in medium load conditions. The HD's slant-back design is strong but economical. Both the HD and HHD have open backs, allowing builders to install the hanger after the header or joists are in place. An extra-wide nailing flange also allows for easy field installation.

Finish	G60 galvanizing
Code Listing	NER 478
Specialty Options	see page 27



HD



HHD

NOTE

NA20D nails included with all HHD series hangers.

Face Mount Hanger THF Series

The THF is specially designed to support the top chords of I-joists in depths up to 16 inches. This eliminates the need for web stiffeners in most applications. Reinforcement ribs give the THF added strength. Raised dimple nailing guides help assure correct 45° nailing into the I-joist bottom chord. The new Seat Cleat™ prongs (patent applied for) allow builders to "pop" I-joists into hangers for quick, positive seating. Seat Cleats™ are not yet available for all THF models.

Finish	G60 galvanizing
Code Listings	NER 478
U.S. Patent	#5,217,317
Seat Cleat Patent	applied for
Specialty Options	see page 27



THF Single



THF Double



Patented raised dimple nailing guides, help assure correct 45° nailing into I-joist bottom chord.

Seat Cleat™ helps lock I-joist in place for positive seating and nailing ease.

Heavy-Duty Hangers THD Series

Deep seats allow the THD to handle higher loads. The THD offers economical costs from an automated manufacturing process. This model features wide header flanges for easier fastening using standard nails.

Finish .... G60 galvanizing
Code Listings ....NER 478



THD Configurations

Heavy-Duty Hangers THDH Series

Special slant nailing and deep seats allow the THDH to handle higher loads. This model features wide header flanges for easier fastening using standard nails.

Finish . . . . G60 galvanizing
Code Listing . . . . NER pending
U.S. Patent . . . . #5,217,317



Drive joist nails into header at 45° to achieve listed loads.

HD, HHD and THF Series Options

Option	*Skewed*	*Sloped*	*Sloped/Skewed*	*Inverted Flange*
RANGE	1° to 67½° when width is 1¾″ or less. 1° to 50° on all others.	1° to 45°	See sloped and skewed.	Not available in widths less than 2¼″.
ALLOWABLE LOADS	100% of table load. 75% of uplift load on skews greater than 15°.	100% of table load.	80% of table load. 75% of uplift load on skews greater than 15°.	100% of table load. 65% of table load when nailing into the support members end grain.
ORDERING	Add SK, angle required, and right (R) or left (L), to product number. Ex. HD17925-SK45R	Add SL, slope required, and up (U) or down (D), to product number. Ex. HD17925-SL30D	See sloped and skewed. Ex. HD17925-SK45RSL30D	Add IF, to product number. Ex. HD410-IF

Sloped/skewed hanger with skews greater than 15° may have all joist nailing on outside flange. Sloped or sloped/skewed hangers with slopes greater than 15° may have additional joist nails added. All sloped, skewed or combinations require bevel cut on joist in all applications and bearing stiffeners with I-joists.



Inverted Flange



Left **Skewed** Seat



Down **Sloped** Seat



Down **Sloped**
& Left **Skewed** Seat

Knee Braces—KVB Series

USP		Dimensions			Fastener Schedule		Allowable Tension Loads (LBS)				
Stock No.	**Ref. No.**	**D**	**W**	**L**	**Beam**	**Joist**	**100%**	**115%**	**125%**	**133%**	**160%**
KVB5	VB5	10–15 Beam Depth	$3\frac{1}{4}$	$28\frac{5}{16}$	(4) NA25	(12) NA25	1050	1210	1315	1400	1680
KVB7	VB7	15–22 Beam Depth	$5\frac{1}{4}$	$39\frac{5}{16}$	(6) NA25	(12) NA25	1050	1210	1315	1400	1680
KVB8	VB8	$22\frac{1}{2}$–$28\frac{1}{2}$ Beam Depth	$5\frac{1}{4}$	$45\frac{5}{16}$	(6) NA25	(12) NA25	1050	1210	1315	1400	1680
KVB10	VB10	$28\frac{1}{2}$–36 Beam Depth	$6\frac{7}{8}$	$56\frac{5}{16}$	(6) NA25	(12) NA25	1050	1210	1315	1400	1680
KVB12	VB12	36–42 Beam Depth	$6\frac{7}{8}$	$68\frac{5}{16}$	(6) NA25	(12) NA25	1050	1210	1315	1400	1680
KVBI5	—	10–15 Beam Depth	$3\frac{1}{2}$	$28\frac{9}{16}$	(4) 10d	(12) 10d	475	545	595	635	760
KVBI7	—	15–22 Beam Depth	$5\frac{1}{4}$	$39\frac{5}{16}$	(6) 10d	(12) 10d	715	820	895	950	1140
KVBI8	—	$22\frac{1}{2}$–$28\frac{1}{2}$ Beam Depth	$5\frac{1}{4}$	$45\frac{5}{16}$	(6) 10d	(12) 10d	715	820	895	950	1140
KVBI10	—	$28\frac{1}{2}$–36 Beam Depth	7	$56\frac{7}{16}$	(6) 10d	(12) 10d	715	820	895	950	1140
KVBI12	—	36–42 Beam Depth	7	$68\frac{7}{16}$	(6) 10d	(12) 10d	715	820	895	950	1140

NA25 nails are included with the braces.

Knee Braces—KVB and KVBI Series

Knee Braces restrict lateral movement of beam under seismic stress. The KVB can be retrofitted into existing framing. NA25 nails are shipped with KVB Knee Brace and arrive attached to the connector in convenient poly bags.

The new KVBI Knee Brace is designed to be used with I-joist purlins and installs with 10d nails (not supplied).

Finish	G60 galvanizing
Material	12 gauge steel
Code Listings	ICBO 2725
	L.A. City RR25104



Typical **KVB** Installation



KVB

Hinge Connectors—KHC Series

			Dimensions				*Bolt Schedule*		*Allowable Loads (LBS)*	
			Min							
USP Stock No.	***Ref. No.***	***Beam Width***	***W***	***H***	***PD***	***T***	***Carrying Member***	***Carried Member***	***560 PSI***	***660 PSI***
KHC55	HCA5-5	$5^1/_8$	$5^1/_4$	12	5	$^3/_4$	$(2)^3/_4$	$(2)^3/_4$	14415	16655
KHC56	HCA5-6	$5^1/_8$	$5^1/_4$	17	6	$^3/_4$	$(2)^3/_4$	$(2)^3/_4$	17300	19990
KHC57	HCA5-7	$5^1/_8$	$5^1/_4$	$23^1/_2$	7	$^3/_4$	$(2)^3/_4$	$(2)^3/_4$	20180	23320
KHC59	HCA5-9	$5^1/_8$	$5^1/_4$	$38^1/_2$	9	$^3/_4$	$(2)^3/_4$	$(2)^3/_4$	25945	29980
KHC525	—	$5^1/_4$	$5^3/_8$	12	5	$^3/_4$	$(2)^3/_4$	$(2)^3/_4$	14415	16655
KHC526	—	$5^1/_4$	$5^3/_8$	17	6	$^3/_4$	$(2)^3/_4$	$(2)^3/_4$	17300	19990
KHC527	—	$5^1/_4$	$5^3/_8$	$23^1/_2$	7	$^3/_4$	$(2)^3/_4$	$(2)^3/_4$	20180	23320
KHC529	—	$5^1/_4$	$5^3/_8$	$38^1/_2$	9	$^3/_4$	$(2)^3/_4$	$(2)^3/_4$	25945	29980
KHC75	HCA7-5	$6^3/_4$	$6^7/_8$	13	5	1	$(2)^3/_4$	$(2)^3/_4$	18985	21940
KHC76	HCA7-6	$6^3/_4$	$6^7/_8$	19	6	1	$(2)^3/_4$	$(2)^3/_4$	22780	26325
KHC77	HCA7-7	$6^3/_4$	$6^7/_8$	$25^1/_2$	7	1	$(2)^3/_4$	$(2)^3/_4$	26580	30715
KHC79	HCA7-9	$6^3/_4$	$6^7/_8$	$43^1/_2$	9	1	$(2)^3/_4$	$(2)^3/_4$	34170	39490
KHC725	—	7	$7^1/_8$	13	5	1	$(2)^3/_4$	$(2)^3/_4$	18985	21940
KHC726	—	7	$7^1/_8$	19	6	1	$(2)^3/_4$	$(2)^3/_4$	22780	26325
KHC727	—	7	$7^1/_8$	$25^1/_2$	7	1	$(2)^3/_4$	$(2)^3/_4$	26580	30715
KHC729	—	7	$7^1/_8$	$42^1/_2$	9	1	$(2)^3/_4$	$(2)^3/_4$	34170	39490
KHC95	HCA9-5	$8^3/_4$	$8^7/_8$	13	5	$1^1/_4$	$(2)^3/_4$	$(2)^3/_4$	24610	28440
KHC96	HCA9-6	$8^3/_4$	$8^7/_8$	19	6	$1^1/_4$	$(2)^3/_4$	$(2)^3/_4$	29530	34125
KHC97	HCA9-7	$8^3/_4$	$8^7/_8$	$25^1/_2$	7	$1^1/_4$	$(2)^3/_4$	$(2)^3/_4$	34450	39815
KHC99	HCA9-9	$8^3/_4$	$8^7/_8$	$42^1/_2$	9	$1^1/_4$	$(2)^3/_4$	$(2)^3/_4$	44300	51190

The minimum height is for loads shown. For heights less than the minimum shown reduce the allowable loads in direct proportion.
All bolts are $^3/_4$ inch, and shall meet or exceed the specifications of ASTM A307.
KHC Allowable Loads are normal loads; no increase is permitted.



KHC



Typical **KHC** Installation

Seismic Straps—KHCST Series

USP Stock No.	Ref. No.	Dimensions L	Dimensions W	Bolt Schedule	Allowable Loads (LBS.) 133%	Allowable Loads (LBS.) 160%
KHCST2	HCST2	22	3 1/2	(4)3/4	6065	6065
KHCST3	HCST3	28	3 1/2	(6)3/4	8815	8815
KHCST4	HCST4	34	3 1/2	(8)3/4	11225	11225

Allowable loads are for straps used in pairs, and are increased 33% or 60% for wind or seismic loads; no further increase is permitted.
Assume a minimum wood thickness of 3 1/8 inches.
Seismic straps shall be used with the KHC hinge connectors.
To order KHCST straps with round holes, add an "R" to the part number, as in "KHCSTR2".

Hinge Connectors KHC Series
Seismic Straps KHCST Series

KHC connectors are used to connect ends of glulam beams having equal widths. These connectors allow long continuous spans, eliminating unnecessary columns. Special dimension variations and models with seismic tabs are available upon request. KHCST straps can be installed during construction or added as a retrofit item. The strap's shape is specially designed to accommodate installation over a USP hinge connector. Order one strap per side.

Material, KHC series ……………………..
……………7 gauge 3/4″, 1″ & 1 1/4″ steel
Material, KHCST series ……. 3 gauge steel
Finish……………………………paint
Code Listings………………… ICBO 2725
……..…………………L.A. City RR25104



KHCST

Skewed 45° Hangers SKH Series

The SKH series provides stock face-mount hangers at preset 45-degree skews, right or left. The hanger design allows for some installation flexibility—it will accommodate a 40- to 50-degree skew. All models provide uplift capacity and some eliminate the need for miter cuts. A convenient slant nail design provides time savings and ensures proper installation.

Finish	G60 galvanizing
Code Listing	NER 478



Typical **SKH** Installation



SKH



Adjustable Strap Hangers—MSH Series

The MSH is field adjustable; builders can use the flanges in overhang, face mount or combination style. The wide header strap allows for a double nailing row and higher load values. An open-back design allows installation after a member is placed in position.

Finish .... G60 galvanizing
Code Listings .... SBCCI 9494
.... NER pending



MSH Top Mount Max



MSH422

Adjustable Rafter-to-Plate Connectors—TMP Series

								Allowable Loads (LBS.)				
								Floor	***Roof***		***Uplift***	
				Dimensions		***Fastener Schedule***			***Snow***	***Non-Snow***		
Refter Width (Inches)	***USP Stock No.***	***Ref. No.***	***Steel Gauge***	***W***	***L***	***Plate***	***Rafter***	***100%***	***115%***	***125%***	***133%***	***160%***
$1^{1}/_{2}$	TMP2	VPA2	18	$1^{9}/_{16}$	$5^{9}/_{16}$	(6)10d	(4)10d × $1^{1}/_{2}$	990	990	990	220	220
$1^{3}/_{4}$	TMP175	VPA25	18	$1^{13}/_{16}$	$5^{9}/_{16}$	(6)10d	(4)10d × $1^{1}/_{2}$	1150	1150	1150	220	220
$2^{1}/_{3}$	TMP23	VPA35	18	$2^{3}/_{8}$	$6^{3}/_{8}$	(6)10d	(4)10d × $1^{1}/_{2}$	1785	1970	1970	220	220
$2^{1}/_{2}$ or $2^{5}/_{8}$	TMP25	VPA2.68	18	$2^{11}/_{16}$	$6^{3}/_{8}$	(6)10d	(4)10d × $1^{1}/_{2}$	1825	1970	1970	220	220
3	TMP31	—	18	$3^{1}/_{8}$	$7^{5}/_{16}$	(6)10d	(4)10d × $1^{1}/_{2}$	1955	1970	1970	220	220
$3^{1}/_{2}$	TMP4	VPA4	18	$3^{9}/_{16}$	$7^{5}/_{16}$	(6)10d	(4)10d × $1^{1}/_{2}$	1970	1970	1970	220	220

No increase for duration of load for uplift is permitted; loads governed by test results.
10d × $1^{1}/_{2}$ nails are 9 gauge (0.148 inch diameter) by $1^{1}/_{2}$ inches long.

Adjustable Rafter-to-Plate Connectors TMP Series

With the TMP, builders can make rafter-to-plate connections at pitches from $^1/_{12}$ to $^6/_{12}$. This model automatically adjusts to any pitch within its range. There's no need to preset the pitches for every connector, and there's no need for time-consuming bird's-mouth notching or bevel plate installation. This model is available in the popular I-joist sizes.

Finish	G60 galvanizing
Code Listing	NER 478
U.S. Patent	# 5,217,317



TMP



Typical **TMP** Installation



$^1/_{12}$ to $^6/_{12}$
Pitch Range

Adjustable Rafter-to-Plate Connectors—TMPH Series

Rafter Width (Inches)	USP Stock No.	Ref. No.	Dimensions			Fastener Schedule		Allowable Loads (LBS.) According to Pitch									Uplift	
			W	*L*	*H*	*Plate*	*Rafter*	$^{6}/_{12}$	$^{7}/_{12}$	$^{8}/_{12}$	$^{9}/_{12}$	$^{10}/_{12}$	$^{11}/_{12}$	$^{12}/_{12}$	$^{13}/_{12}$	$^{14}/_{12}$	*133%*	*160%*
$1^{1}/_{2}$	TMPH2	—	$1^{9}/_{16}$	$6^{9}/_{16}$	$2^{1}/_{2}$	(10) 10d	(8) 10d × $1^{1}/_{2}$	3190	3170	3110	3000	2840	2640	2420	2180	1945	200	200
$1^{3}/_{4}$	TMPH175	—	$1^{13}/_{16}$	$6^{9}/_{16}$	$2^{3}/_{8}$	(10) 10d	(8) 10d × $1^{1}/_{2}$	3190	3170	3110	3000	2840	2640	2420	2180	1945	200	200
$2^{5}/_{16}$	TMPH23	—	$2^{3}/_{8}$	$7^{3}/_{8}$	$2^{1}/_{2}$	(10) 10d	(8) 10d × $1^{1}/_{2}$	3190	3170	3110	3000	2840	2640	2420	2180	1945	200	200
$2^{1}/_{2}$	TMPH25	—	$2^{11}/_{16}$	$7^{3}/_{8}$	$2^{5}/_{16}$	(10) 10d	(8) 10d × $1^{1}/_{2}$	3190	3170	3110	3000	2840	2640	2420	2180	1945	200	200
3	TMPH31	—-	$3^{1}/_{8}$	$8^{9}/_{16}$	$2^{11}/_{16}$	(10) 10d	(8) 10d × $1^{1}/_{2}$	3190	3170	3110	3000	2840	2640	2420	2180	1945	200	200
$3^{1}/_{2}$	TMPH4	—-	$3^{9}/_{16}$	$8^{9}/_{16}$	$2^{1}/_{2}$	(10) 10d	(8) 10d × $1^{1}/_{2}$	3190	3170	3110	3000	2840	2640	2420	2180	1945	200	200

Web stiffeners are required for all wood I-joist installations.
Design Loads may not be increased.
10d × $1^{1}/_{2}$ inch nails are 9 gauge (0.148 inch diameter) by $1^{1}/_{2}$ inches long.

Adjustable Rafter-to-Ridge Connectors TMPH Series

With the TMPH, builders can make rafter-to-plate connections at pitches from $^6/_{12}$ to $^{14}/_{12}$. This model automatically adjust to any pitch within their ranges. There's no need to preset the pitches for every connector, and there's no need for time-consuming bird's-mouth notching or bevel plate installation. This model is available in the popular I-joist sizes.

Finish	G60 galvanizing
Code Listing	NER pending
U.S. Patent	#5,230,198



Typical **TMPH** Installation



TMPH

TMP and TMPH Installation Procedure:

A) Nail clip to outside edge of wall plate.

B) Insert joist with downward pressure to seat the self-adjusting support.

C) Nail joist in place being sure to nail through the matching slots.



$^6/_{12}$ to $^{14}/_{12}$ Pitch Range

Adjustable Rafter-to-Ridge Connectors—TMU Series

									Allowable Loads (LBS.)				
									Vertical Loads				
										Roof			
				Dimensions			*Fastener Schedule*		*Floor*	*Snow*	*Non-Snow*	*Uplift*	
Rafter Width (Inches)	***USP Stock No.***	***Ref. No.***	***Steel Gauge***	***W***	***H***	***L***	***Header***	***Joist***	***100%***	***115%***	***125%***	***133%***	***160%***
$1\frac{1}{2}$	TMU26	LSU26	18	$1\frac{9}{16}$	$5\frac{1}{4}$	$5\frac{1}{4}$	(10) 10d	(7) 10d × $1\frac{1}{2}$	1120	1290	1305	640	640
$1\frac{1}{2}$	TMU210	LSSU210	18	$1\frac{9}{16}$	$8\frac{5}{8}$	$5\frac{1}{4}$	(12) 10d	(11) 10d × $1\frac{1}{2}$	1340	1340	1340	770	770
$1\frac{3}{4}$	TMU175	—	18	$1\frac{13}{16}$	$5\frac{1}{4}$	$5\frac{1}{4}$	(10) 10d	(7) 10d × $1\frac{1}{2}$	1120	1290	1305	640	640
$1\frac{3}{4}$	TMU179	LSSUI25	18	$1\frac{13}{16}$	$8\frac{5}{8}$	$5\frac{1}{4}$	(12) 10d	(11) 10d × $1\frac{1}{2}$	1340	1340	1340	770	770
$2\frac{5}{16}$	TMU23	LSSUI35	18	$2\frac{3}{8}$	$8\frac{7}{8}$	$6\frac{3}{4}$	(12) 10d	(11) 10d × $1\frac{1}{2}$	1345	1545	1680	1340	1605
$2\frac{1}{2}$	TMU25	LSSUI2.68	18	$2\frac{11}{16}$	$8\frac{7}{8}$	$6\frac{3}{4}$	(12) 10d	(11) 10d × $1\frac{1}{2}$	1345	1545	1680	1340	1605
3	TMU31	LSSUI210-2	18	$3\frac{1}{8}$	7	8	(12) 10d	(11) 10d × $1\frac{1}{2}$	1345	1545	1680	1340	1605
$3\frac{1}{2}$	TMU48	LSSU410	18	$3\frac{9}{16}$	7	8	(12) 10d	(11) 10d × $1\frac{1}{2}$	1345	1545	1680	1340	1605

Uplift Loads have been increased $33\frac{1}{3}$% or 60% for wind and seismic loads; no further increases shall be permitted.
10d × $1\frac{1}{2}$ nails are 9 gauge (0.148 inch diameter) × $1\frac{1}{2}$ inches long.
Web stiffeners are required for all Wood I-joist installations.
A tie strap is required for all installations when sloped down at $\frac{7}{12}$ to $\frac{12}{12}$ pitch-use LSTI22 with (4) 10d × $1\frac{1}{2}$ nails.
per end for TMU26, TMU210, TMU175 and TMU179, use KSTI223 with (5) 10d × $1\frac{1}{2}$ nails per end for all others.
10d nails require a header thickness of 1.76 inches to achieve load values shown.
If attached to 2 × lumber, use 85% of listed values.



Pitch Range

Adjustable Rafter-to-Ridge Connectors TMU Series

The TMU is designed to connect rafters to ridge beams in vaulted roof structures. These connectors were originally developed to help builders avoid ordering custom sloped and skewed hangers for every situation. The TMU is easily field adjusted to meet a variety of skew and / or slope applications. Shapes to any pitch from 8/12 up through 12/12 down.

Finish .... G60 galvanizing
Code Listing .... NER 478
U.S. Patent .... # 5,217,317



TMU



Typical **TMU** Installation

Skewed Installation

1. Install onto end of rafter using recommended nail schedule for joist. Note: When sloping TMU26/175 up, attach hanger to web before nailing to bottom flange.
2. Bend flange to desired angle, and nail in place.
3. Bend opposite flange as shown, and finish nailing.



SKEW TO 45°

TMU26, 210, 175 & 179

3/4"×4"×7" Plywood Spacer with (6) 16d Nails



SKEW TO 30°

SKEW 31° TO 45°

TMU23, 25 ,31 & 48

TMU Installation Procedure



Web stiffeners required for all wood I-joist installations. Tie strap required for all wood I-joist installations when sloped 30° to 45°, or 7:12 thru 12:12. Use LSTI-22 for $1^{1}/_{2}''$ & $1^{3}/_{4}''$ width joists, use KSTI-223 for $2^{5}/_{16}''$ or wider joists.

Strap Ties—KSTI and LSTI22 Series

USP Stock No.	*Ref. No.*	*Steel Gauge*	*Dimensions*		*Nail Schedule*	*Allowable Loads (LBS.)*	
						Nails	
			W	*L*		*133%*	*160%*
KSTI223	MSTI23	18	$2^1/_{16}$	23	(23) 10d × $1^1/_2$	1645	1975
KSTI226	MSTI26	12	$2^1/_{16}$	26	(26) 10d × $1^1/_2$	1735	2080
KSTI236	MSTI36	12	$2^1/_{16}$	36	(36) 10d × $1^1/_2$	2400	2880
KSTI248	MSTI48	12	$2^1/_{16}$	48	(48) 10d × $1^1/_2$	2300	3840
KSTI260	MSTI60	12	$2^1/_{16}$	60	(60) 10d × $1^1/_2$	4000	4800
KSTI272	MSTI72	12	$2^1/_{16}$	72	(72) 10d × $1^1/_2$	4510	4950
LSTI22	—	20	$1^1/_4$	24	(16) 10d × $1^1/_2$	950	950

Allowable Loads have been increased $33^1/_3$% or 60% for wind and seismic loads; no further increase shall be permitted. 10d × $1^1/_2$ nails are 9 gauge (0.148 inch diameter) by $1^1/_2$ inches long.

Strap Ties KSTI and LSTI22 Series

These strap ties are designed specifically for installation along wood I-joist flanges.

Installation Note

The LSTI22 is for use with 1-$^1/_2$″ and 1-$^3/_4$″ I-joists. The KSTI is for use with $2^5/_{16}$″ and larger I-joists.

Finish . . . . G60 galvanizing
Code Listings . . . . SBCCI 9494
. . . . NER pending



Strap Ties—LSTA and MSTA Series

USP Stock No.	Ref. No.	Steel Gauge	Dimensions		*10d Nails Per End	10d Nails Allowable Loads (LBS.)			*10d × $1\frac{1}{2}$ Nails Per End	10d × $1\frac{1}{2}$ Nails Allowable Loads (LBS.)		
			W	L		100%	133%	160%		100%	133%	160%
LSTA9	LSTA9	20	$1\frac{1}{4}$	9	4	445	590	710	4	375	500	600
LSTA12	LSTA12	20	$1\frac{1}{4}$	12	5	555	740	800	5	470	625	750
LSTA15	LSTA15	20	$1\frac{1}{4}$	15	6	670	895	945	6	570	760	910
LSTA18	LSTA18	20	$1\frac{1}{4}$	18	7	790	1055	1200	7	665	885	1065
LSTA21	LSTA21	20	$1\frac{1}{4}$	21	8	900	1200	1200	8	760	1015	1200
LSTA24	LSTA24	18	$1\frac{1}{4}$	24	9	1025	1370	1605	9	865	1150	1380
LSTA30	LSTA30	18	$1\frac{1}{4}$	30	11	1200	1605	1605	11	1055	1410	1605
LSTA36	LSTA36	18	$1\frac{1}{4}$	36	11	1200	1605	1605	13	1200	1605	1605
MSTA9	MSTA9	18	$1\frac{1}{4}$	9	4	445	590	710	4	375	500	600
MSTA12	MSTA12	18	$1\frac{1}{4}$	12	5	555	740	890	5	470	625	750
MSTA15	MSTA15	18	$1\frac{1}{4}$	15	6	665	890	1065	6	565	750	900
MSTA18	MSTA18	18	$1\frac{1}{4}$	18	7	775	1035	1070	7	660	875	1055
MSTA21	MSTA21	18	$1\frac{1}{4}$	21	8	895	1195	1260	8	760	1015	1215
MSTA24	MSTA24	16	$1\frac{1}{4}$	24	9	1035	1380	1655	9	875	1165	1395
MSTA30	MSTA30	16	$1\frac{1}{4}$	30	11	1265	1685	2000	11	1065	1425	1705
MSTA36	MSTA36	16	$1\frac{1}{4}$	36	13	1495	1995	2000	13	1260	1680	2000
MSTA48	MSTA48	16	$1\frac{1}{4}$	48	14	1500	2000	2000	16	1500	2000	2000

Loads have been increased $33\frac{1}{3}$% or 60% for wind and seismic loads; no further increase shall be permitted.
When 10d nails are used, the minimum wood thickness shall be $1\frac{3}{4}$ inches.
If used on 2× lumber, use the table for 10d× $1\frac{1}{2}$ inch nails.
*Minimum number of fasteners needed in each end to develop strap strength.

Strap Ties LSTA and MSTA Series

With a 1^1/4 inch width, the 20-gauge LSTA and the heavier MSTA straps are designed especially for use with 1^1/2 inch members. The lighter gauge allows builders to bend these straps for many framing applications.

Finish	G60 galvanizing
Code Listing	NER 505



Purlin Anchors PAI Series

Purlin Anchors are engineered to meet seismic and high wind load requirements when securing I-joist purlins and beams to concrete or masonry. Loads are based on a minimum 4-inch embedment into concrete and should be reduced accordingly for masonry or other applications.

Finish	G60 galvanizing
Code Listing	NER 505



Typical **PAI** Installation



PAI

							Allowable Loads (LBS.)	
				Fastener Schedule			*Nails*	
USP Stock No.	***Ref. No.***	***Dimensions***	***Steel Gauge***	***Nails***	***Bolts***	***Minimum EMBED.***	***133**%*	***160**%*
PAI18	PAI18	$2 \times 18\frac{1}{2}$	12	(12) 10d × $1\frac{1}{2}$	—	4	1600	1920
PAI23	PAI23	$2 \times 23\frac{1}{2}$	12	(18) 10d × $1\frac{1}{2}$	—	4	2400	2880
PAI28	PAI28	$2 \times 28\frac{1}{2}$	12	(24) 10d × $1\frac{1}{2}$	—	4	3125	3125
PAI35	PAI35	$2 \times 35\frac{1}{2}$	12	(26) 10d × $1\frac{1}{2}$	—	4	3125	3125

Allowable Loads have been increased $33\frac{1}{3}$% or 60% for wind and seismic loads; no further increase shall be permitted.
10d × $1\frac{1}{2}$ nails are 9 gauge (0.148 inch diameter) by $1\frac{1}{2}$ inches long.

Bracing—N Series

Sized for Joist to Plate Lateral Bracing				
	****Joist Spacing Inches***			
I-Beam Height	***12***	***16***	***19.2***	***24***
9¼	N16	N16	N16	N27
9½	N16	N16	N16	N27
11¼	N16	N16	N27	N27
11⅞	N16	N27	N27	N27
12	N16	N27	N27	N27
14	N16	N27	N27	N30
16	N27	N27	N27	N30
18	N27	N27	N27	N30/N36
20	N27	N27	N27/N30	N36
22	N27	N30	N30	N36
24	N30	N30	N30/N36	N36
26	N30	N36	N36	N36
28	N36	N36	N36	N42
30	N36	N36	N36/N42	N42

*Requires (2) 8d common nails or NA11 nails at each end. Nails are to be driven into narrow face of each joist unless noted otherwise.

Sized for Joist to Joist X Bridging				
	****Joist Spacing Inches***			
I-Beam Height	***12***	***16***	***19.2***	***24***
9¼	N16	N16	N27	N27
9½	N16	N16	N27	N27
11¼	N16	N27	N27	N27/N30
11⅞	N16	N27	N27	N30
12	N16	N27	N27	N30
14	N16	N27	N27	N30
16	N27	N27	N27	N30
18	N27	N27	N27/N30	N30/N36
20	N27	N27/N30	N30	N36
22	N27/N30	N30	N30/N36	N36
24	N30	N30	N36	N36
26	N36	N36	N36	N42
28	N36	N36	N36/N42	N42
30	N36	N36/N42	N42	N42

*Requires (2) 8d common nails or NA11 nails at each end. Nails are to be driven into top/bottom face of each joist unless noted otherwise.

Bracing and Bridging N Series

N series bridging is quickly installed and economical. This style must be installed prior to the subfloor. Use (2) 8d nails at each end and leave a slight space between the units to avoid noise generating contact.

Material	20 gauge steel
Finish	G60 galvanizing
Code Listing	NER 505



N 16



Typical **N** Bracing Installation

Wet Anchors—WE and WA Series

									Allowable Loads (LBS.)											
									L1				L2				Uplift			
			Dimensions				Fastener Schedule		Nails		Bolts		Nails		Bolts		Nails		Bolts	
USP Stock No.	Ref. No.	Post Size	W	H1	H2	L	Nails	Bolts	133%	160%	133%	160%	133%	160%	133%	160%	133%	160%	133%	160%
WE44	PB44	4 × 4	$3^9/_{16}$	$4^{13}/_{16}$	$3^3/_8$	$3^1/_4$	(12) 16d	$(2)^1/_2$	1135	1135	910	910	1180	1180	1020	1020	1405	1405	1430	1430
WE46	PB46	4 × 6	$5^1/_2$	$4^5/_8$	$3^1/_4$	$3^3/_8$	(12) 16d	$(2)^1/_2$	1135	1135	910	910	1180	1180	1020	1020	1405	1405	1430	1430
WA44	—	4 × 4	$3^9/_{16}$	4	5	2	(12) 16d	$(2)^1/_2$	1575	1575	1525	1830	675	675	1290	1290	1375	1375	1415	1695
WA45	—	4 × 6	$3^9/_{16}$	4	5	2	(12) 16d	$(2)^1/_2$	1575	1575	1525	1830	675	675	1290	1290	1375	1375	1415	1695
WA55	—	6 × 6	$5^3/_8$	6	5	$2^1/_2$	(12) 16d	$(2)^1/_2$	1575	1575	1525	1830	675	675	1290	1290	1375	1375	1415	1695
WA77	—	8 × 8	$7^1/_8$	$7^1/_2$	7	3	(12) 16d	$(2)^1/_2$	1575	1575	1525	1830	675	675	1290	1290	1375	1375	1415	1695

Uplift Loads have been increased $33^1/_3$% or 60% for wind and seismic loads; no further increase shall be permitted.
Not recommended for non-top-supported installations, such as fences.
H2 is minimum embedment length of anchor into concrete.
Bolt and nail values cannot be combined.

Wet Anchors WE and WA Series

Wet Post Anchors secure posts to concrete in light and medium duty applications such as patio covers, carports or decks. The built-in stand-off plate keeps the post from making contact with the ground and damaging moisture. The WE features a formed, one-piece design which offers additional economy. **Not recommended for fence post applications.**

Material	12 gauge steel
Finish	G60 galvanizing
Code Listing, WA series	NER 505
Code Listings, WE series	ICBO 2039
	NER pending
Code Listing, WE44	SBCCI 9494



Typical **WE44** Installation



WE


Uplift
L1
L2
1"
Standoff

Typical **WA** Installation



WA

Heavy Column Bases—HBM, CBE, and KCB Series

										Allowable Load (LBS.)			
										Uplift			
USP		Column	Dimensions				Fastener Schedule			Bolts		Nails	
Stock No.	Ref. No.	Size	W1	W2	H	L	Bolts	Nails		133%	160%	133%	160%
HBM44	CBS44	$3\frac{1}{2} \times 3\frac{1}{2}$	$3\frac{9}{16}$	$3\frac{9}{16}$	$7\frac{5}{8}$	2	$(2)\frac{5}{8}$	—		5650	4300	—	—
HBM46	CBS46	$3\frac{1}{2} \times 5\frac{1}{2}$	$3\frac{9}{16}$	$5\frac{1}{2}$	$7\frac{5}{8}$	2	$(2)\frac{5}{8}$	—		5650	4300	—	—
HBM66	CBS66	$5\frac{1}{2} \times 5\frac{1}{2}$	$5\frac{1}{2}$	$5\frac{1}{2}$	$7\frac{5}{8}$	2	$(2)\frac{5}{8}$	—		5640	4285	—	—
CBE44	LCB44	$3\frac{1}{2} \times 3\frac{1}{2}$	$3\frac{9}{16}$	$3\frac{1}{2}$	$7\frac{1}{2}$	2	$(2)\frac{1}{2}$	(12)16d		3585	4300	2240	2690
CBE45	—	$3\frac{1}{2} \times 5\frac{1}{4}$	$3\frac{9}{16}$	$5\frac{3}{8}$	$7\frac{1}{2}$	2	$(2)\frac{1}{2}$	(12)16d		3585	4300	2240	2690
CBE47	—	$3\frac{1}{2} \times 7$	$3\frac{9}{16}$	$7\frac{1}{8}$	$7\frac{1}{2}$	2	$(2)\frac{1}{2}$	(12)16d		3585	4300	2240	2690
CBE55	—	$5\frac{1}{4} \times 5\frac{1}{4}$	$5\frac{1}{2}$	$5\frac{3}{8}$	$7\frac{1}{2}$	2	$(2)\frac{1}{2}$	(12)16d		3570	4285	2240	2690
KCB44	CB44	$3\frac{1}{2} \times 3\frac{1}{2}$	$3\frac{9}{16}$	$3\frac{9}{16}$	$8\frac{7}{8}$	2	$(2)\frac{5}{8}$	—		5650	6780	—	—
KCB45	—	$3\frac{1}{2} \times 5\frac{1}{4}$	$3\frac{9}{16}$	$5\frac{3}{8}$	$8\frac{7}{8}$	2	$(2)\frac{5}{8}$	—		5650	6780	—	—
KCB47	—	$3\frac{1}{2} \times 7$	$3\frac{9}{16}$	$7\frac{1}{8}$	$8\frac{7}{8}$	2	$(2)\frac{5}{8}$	—		5650	6780	—	—
KCB55	—	$5\frac{1}{4} \times 5\frac{1}{4}$	$5\frac{1}{2}$	$5\frac{3}{8}$	$8\frac{7}{8}$	3	$(2)\frac{5}{8}$	—		5640	6670	—	—
KCB57	—	$5\frac{1}{4} \times 7$	$5\frac{1}{2}$	$7\frac{1}{8}$	$8\frac{7}{8}$	3	$(2)\frac{5}{8}$	—		5640	6680	—	—
KCB77	—	7×7	$7\frac{1}{2}$	$7\frac{1}{8}$	$9\frac{3}{4}$	3	$(2)\frac{3}{4}$	—		8075	8185	—	—

Uplift Loads have been increased $33\frac{1}{3}$% or 60% for wind and seismic loads, no further increase shall be permitted.
Not recommended for fences.
Minimum edge distance is 3 inches.

Heavy Column Bases HBM, CBE, and KCB Series

These sturdy bases secure heavy columns to concrete footings or foundations. The base is set in position prior to the pour to assure proper alignment and installation. Designed for structural integrity in high wind or seismic applications. **These models are not recommended for fence post applications.**

Installation Note

For KCB installations, the base plate must be flush with the concrete surface to develop full bearing capacity.

Materials, HBM & CBE series . . . .
. . . . 12 gauge steel
Materials, KCB series . . . . $^3/_{16}$″ or $^1/_4$″ steel
Finish, CBE series . . . . G60 galvanizing
Finish, HBM & KCB series . . . . paint
Code Listings, KCB & CBE series . . . .
. . . . SBCCI 9494
. . . . NER pending
Code Listings, HBM . . . . ICBO 2039
. . . . L.A. City RR23888
Code Listings, KCB . . . . ICBO 2725
. . . . L.A. City RR25104



HBM



KCB



Typical **CBE** Installation



CBE

Post Caps—PCM and EPCM Series

											Allowable Loads (LBS.)					
					Dimensions				**Fastener Schedule**		**Lateral A1**		**Lateral A2**		**Uplift**	
USP Stock No.	**Ref. No.**	**Post (Inches)**	**Beam (Inches)**	**Steel Gauge**	**W1**	**W2**	**L1**	**L2**	**Post**	**Beam**	**133%**	**160%**	**133%**	**160%**	**133%**	**160%**
PCM4416	PC44-16	$3\frac{1}{2}$	$3\frac{1}{2}$	16	$3\frac{9}{16}$	$3\frac{9}{16}$	$3\frac{1}{16}$	11	(8)16d	(12)16d	1030	1030	835	835	1050	1050
PCM4516	—	$3\frac{1}{2}$	$5\frac{1}{4}$	16	$3\frac{9}{16}$	$5\frac{3}{8}$	$3\frac{1}{16}$	13	(8)16d	(12)16d	1030	1030	835	835	1050	1050
PCM4716	—	$3\frac{1}{2}$	7	16	$3\frac{9}{16}$	$7\frac{1}{8}$	$3\frac{1}{16}$	15	(8)16d	(12)16d	1030	1030	835	835	1050	1050
PCM5416	—	$5\frac{1}{4}$	$3\frac{1}{2}$	16	$5\frac{3}{8}$	$3\frac{9}{16}$	$3\frac{1}{2}$	11	(8)16d	(12)16d	1030	1030	835	835	1050	1050
PCM5516	—	$5\frac{1}{4}$	$5\frac{1}{4}$	16	$5\frac{3}{8}$	$5\frac{3}{8}$	$3\frac{1}{2}$	13	(8)16d	(12)16d	1030	1030	835	835	1050	1050
PCM44	PC44	$3\frac{1}{2}$	$3\frac{1}{2}$	12	$3\frac{9}{16}$	$3\frac{9}{16}$	$3\frac{1}{16}$	11	(8)16d	(12)16d	1930	1930	1495	1790	1050	1050
PCM45	—	$3\frac{1}{2}$	$5\frac{1}{4}$	12	$3\frac{9}{16}$	$5\frac{3}{8}$	$3\frac{1}{16}$	13	(8)16d	(12)16d	1930	1930	1495	1790	1050	1050
PCM47	—	$3\frac{1}{2}$	7	12	$3\frac{9}{16}$	$7\frac{1}{8}$	$3\frac{1}{16}$	15	(8)16d	(12)16d	1930	1930	1495	1790	1395	1395
PCM54	—	$5\frac{1}{4}$	$3\frac{1}{2}$	12	$5\frac{3}{8}$	$3\frac{9}{16}$	$3\frac{1}{2}$	11	(8)16d	(12)16d	1930	1930	1495	1790	1395	1395
PCM55	—	$5\frac{1}{4}$	$5\frac{1}{4}$	12	$5\frac{3}{8}$	$5\frac{3}{8}$	$3\frac{1}{2}$	13	(8)16d	(12)16d	1930	1930	1495	1790	1395	1395
PCM57	—	$5\frac{1}{4}$	7	12	$5\frac{3}{8}$	$7\frac{1}{8}$	$3\frac{1}{2}$	15	(8)16d	(12)16d	1930	1930	1495	1790	1395	1395
PCM75	—	7	$5\frac{1}{4}$	12	$7\frac{1}{8}$	$5\frac{3}{8}$	$5\frac{1}{2}$	13	(8)16d	(12)16d	1930	1930	1495	1790	1395	1395
PCM77	—	7	7	12	$7\frac{1}{8}$	$7\frac{1}{8}$	$5\frac{1}{2}$	15	(8)16d	(12)16d	1930	1930	1495	1790	1395	1395

(continued)

(continued)

													Allowable Loads (LBS.)			
					Dimensions				Fastener Schedule		Lateral A1		Lateral A2		Uplift	
USP Stock No.	Ref. No.	Post (Inches)	Beam (Inches)	Steel Gauge	W1	W2	L1	L2	Post	Beam	133%	160%	133%	160%	133%	160%
EPCM4416	EPC44-16	$3\frac{1}{2}$	$3\frac{1}{2}$	16	$3\frac{9}{16}$	$3\frac{9}{16}$	$3\frac{1}{16}$	$7\frac{1}{4}$	(8)16d	(8)16d	1020	1020	1055	1055	805	805
EPCM4516	—	$3\frac{1}{2}$	$5\frac{1}{4}$	16	$3\frac{9}{16}$	$5\frac{3}{8}$	$3\frac{1}{16}$	$9\frac{1}{4}$	(8)16d	(8)16d	1020	1020	1055	1055	805	805
EPCM4716	—	$3\frac{1}{2}$	7	16	$3\frac{9}{16}$	$7\frac{1}{8}$	$3\frac{1}{16}$	$11\frac{1}{4}$	(8)16d	(8)16d	1020	1020	1055	1055	805	805
EPCM5416	—	$5\frac{1}{4}$	$3\frac{1}{2}$	16	$5\frac{3}{8}$	$3\frac{9}{16}$	$3\frac{1}{2}$	$7\frac{1}{4}$	(8)16d	(8)16d	1020	1020	1055	1055	805	805
EPCM5516	—	$5\frac{1}{4}$	$5\frac{1}{4}$	16	$5\frac{3}{8}$	$5\frac{3}{8}$	$3\frac{1}{2}$	$9\frac{1}{4}$	(8)16d	(8)16d	1020	1020	1055	1055	805	805
EPCM44	EPC44	$3\frac{1}{2}$	$3\frac{1}{2}$	12	$3\frac{9}{16}$	$3\frac{9}{16}$	$3\frac{1}{16}$	$7\frac{1}{4}$	(8)16d	(8)16d	1180	1180	1495	1610	1480	1480
EPCM45	—	$3\frac{1}{2}$	$5\frac{1}{4}$	12	$3\frac{9}{16}$	$5\frac{3}{8}$	$3\frac{1}{16}$	$3\frac{1}{16}$	(8)16d	(8)16d	1180	1180	1495	1610	1480	1480
EPCM47	—	$3\frac{1}{2}$	7	12	$3\frac{9}{16}$	$7\frac{1}{8}$	$3\frac{1}{16}$	$11\frac{1}{4}$	(8)16d	(8)16d	1180	1180	1495	1610	1480	1480
EPCM54	—	$5\frac{1}{4}$	$3\frac{1}{2}$	12	$5\frac{3}{8}$	$3\frac{9}{16}$	$3\frac{1}{2}$	$7\frac{1}{4}$	(8)16d	(8)16d	1180	1180	1495	1610	1480	1480
EPCM55	—	$5\frac{1}{4}$	$5\frac{1}{4}$	12	$5\frac{3}{8}$	$5\frac{3}{8}$	$3\frac{1}{2}$	$9\frac{1}{4}$	(8)16d	(8)16d	1180	1180	1495	1610	1480	1480
EPCM57	—	$5\frac{1}{4}$	7	12	$5\frac{3}{8}$	$7\frac{1}{8}$	$3\frac{1}{2}$	$11\frac{1}{4}$	(8)16d	(8)16d	1180	1180	1495	1610	1480	1480
EPCM75	—	7	$5\frac{1}{4}$	12	$7\frac{1}{8}$	$5\frac{3}{8}$	$5\frac{1}{2}$	$11\frac{1}{4}$	(8)16d	(8)16d	1180	1180	1495	1610	1480	1480
EPCM77	—	7	7	12	$7\frac{1}{8}$	$7\frac{1}{8}$	$5\frac{1}{2}$	$13\frac{1}{4}$	(8)16d	(8)16d	1180	1180	1495	1610	1480	1480

Uplift loads and lateral loads have been increased $33\frac{1}{3}$% or 60% for wind and seismic loads. No further increase shall be permitted.
Allowable loads are for nails only.

Post Caps PCM and EPCM Series

Post caps provide a positive connection for medium duty post-to-beam applications. The extended side plate design in these products also function as tie straps where splices occur. These models fasten with standard nails.

Finish . . . . G60 galvanizing
Code Listing . . . . NER 505



Typical **PCM** Installation



PCM



EPCM

Column Caps—KCC and KECC Series

			Dimensions					*Bolt Schedule*							
						L				*Bearing Load*		*Uplift KCC*		*Uplift KECC*	
USP Stock No.	*Ref. No.*	*Steel Gauge*	*W1*	*W2*	*H*	*KCC*	*KECC*	*Beam*	*Column or Post*	*KCC*	*KECC*	*133%*	*160%*	*133%*	*160%*
KCC44	CC44	7	$3^{5}/_{8}$	$3^{5}/_{8}$	4	7	$5^{1}/_{2}$	$(2)^{5}/_{8}$	$(2)^{5}/_{8}$	15315	12030	2985	3585	1635	1960
KCC45	—	7	$3^{5}/_{8}$	$5^{3}/_{8}$	$6^{1}/_{2}$	11	$8^{1}/_{2}$	$(4)^{5}/_{8}$	$(2)^{5}/_{8}$	24065	18595	5270	6310	3210	3850
KCC47	—	7	$3^{5}/_{8}$	$7^{1}/_{8}$	$6^{1}/_{2}$	11	$9^{1}/_{2}$	$(4)^{5}/_{8}$	$(2)^{5}/_{8}$	24065	20780	5270	6310	3210	3850
KCC54	—	7	$5^{3}/_{8}$	$3^{5}/_{8}$	$6^{1}/_{2}$	11	$7^{1}/_{2}$	$(4)^{5}/_{8}$	$(2)^{5}/_{8}$	37810	25780	5255	6310	3385	4060
KCC55	—	7	$5^{3}/_{8}$	$5^{3}/_{8}$	$6^{1}/_{2}$	11	$7^{1}/_{2}$	$(4)^{5}/_{8}$	$(2)^{5}/_{8}$	37815	25780	5255	6310	3385	4060
KCC57	CC6 - $7^{1}/_{8}$	7	$5^{3}/_{8}$	$7^{1}/_{8}$	$6^{1}/_{2}$	11	$9^{1}/_{2}$	$(4)^{5}/_{8}$	$(2)^{5}/_{8}$	37815	32655	5255	6310	3385	4060
KCC75X	CC$7^{1}/_{8}$-6	3	$7^{1}/_{8}$	$5^{3}/_{8}$	8	13	$10^{1}/_{2}$	$(4)^{3}/_{4}$	$(2)^{3}/_{4}$	54600	44100	6230	7255	4665	5595
KCC77X	CC7 1/8 - $7^{1}/_{8}$	3	$7^{1}/_{8}$	$7^{1}/_{8}$	8	13	$10^{1}/_{2}$	$(4)^{3}/_{4}$	$(2)^{3}/_{4}$	54600	44100	6230	7255	4665	5595

Bearing loads are based on 560 psi perpendicular to grain loading for glulam sizes and 8× and wider, and 625 psi for all others.
Uplift loads are increased 33% and 60% for wind or seismic loads; no further increase is permitted.
Beams shall be designed to support the required loads. Beam shear may limit loads to less than listed loads for device.
Posts are assumed adequate to support listed loads.
Bearing loads shall not be increased for duration of load.

Column Caps KCC and KECC Series

Designed for heavy duty beam-to-post connections, column caps offer strong reinforcement and support at critical framing junctions. A number of special sizes and style variations are available. Straps are normally centered on the U-bracket, but any variation may be specified. For end column caps, add an "E" after the "K" in the part number, as in "KECC325-4." Straps may be rotated 90 degrees on special order where the W2 dimension is less than or equal to the W1 dimension. Welding is performed by certified welders and routinely inspected by a code-accepted quality control agency.

Finish .... paint
Code Listings ....ICBO 2725
........................L.A. City RR25104


L
W1
H
$8^1/_2$"
$2\ ^1/_2$"
W2

KCC44


L
W1
H
$8^1/_2$"
$2^1/_2$"
W2

KECC44



Typical **KCC** Installation

Typical **KECC** Installation

KCC and KECC Series Options

A number of size and style variations are available for KCC and KECC Column Caps on a custom order basis. Possible variations include rough or custom sizes and altered bolt pattern. A number of standard options are also available as detailed by the adjacent illustrations. These options include: KCCO, KCCT, KCCOB and 90° strap rotation.

NOTE

Consult retail price list or your technical assistance representative for details and ordering information.



KECC Straps Rotated 90°



KCCOB



KCCT



KCCO

Index

A
abstract number, 115
acres, 141
acute angles, 143, 145, 182
addition, 115, 116, 117–119
air-dried lumber, 54–55
air-drying, 46, 47
allowable loads, 91, 100–101, 109
altitude screws, 201
American Society for Testing Materials (ASTM), 92
American Wire and Screw Nail Company, 2
angles
  acute, 143, 145, 182
  bisecting, 154, 155
  complement of, 143
  cosecant of, 183–184
  cosine of, 183
  cotangent of, 183–184
  defined, 142
  drawing equivalents of, 154
  measurement of, 143
  oblique, 143
  obtuse, 143, 145, 182
  right, 142, 145
  secant of, 183–184
  sine of, 183
  supplement of, 143
  tangent of, 183
annual rings, 51
apothecaries weights, 138
appearance lumber, 68
  abbreviations for, 71–76
  for casing and base, 85
  common, 77
  commonly available types of, 76
  examples of, 70
  finish boards, 84
  grades of, 70, 71–76
  grains of, 71
  imperfections in, 76
  in retail yards, 84–86
  secondary manufacture of, 70
  select lumber, 76–77
  for shakes, 85–86
  for shingles, 85
  for siding, 84
architects
  drawings by (*see* architectural drawings)
  magazine plans of, 236, 237, 238
  and modern house designs, 284–285, 286, 287
  preliminary work of, 263
  registered plans of, 236
architect's rod, 227
architect's scale, 261, 262
architectural drawings
  abbreviations used in, 274–278
  architect's scale for, 261, 262
  of basements, 266, 269, 270
  bidding on, 265
  of Colonial-type home, 283–284
  of contemporary homes, 289
  development of, 262–267, 268–269, 270, 278
  elevation in, 255–256
  floor plans in, 266, 267, 268
  of foundations, 266, 270
  full-size, 260–261
  graphic scale of proportions for, 262
  graphic symbols of, 262–263, 267, 269, 271–274, 278
  half-size, 260, 261
  inspection of, 264
  interpretation of, 244
  left-end view of, 258
  legends for, 269
  lines used in, 269, 271–272
  oblique projections in, 258
  preliminary, 266
  preliminary work to, 263
  profile plane in, 256–257
  projected views of, 255–256
  purpose of, 262, 278
  quarter-size, 260
  reading, 255–262

architectural drawings (*continued*)
  right-end view of, 256–258
  scale of size in, 260–262, 278
  sectional views of, 258–260
  top view of, 256, 257
  use of, 255
architecture, contemporary, 285–287, 288–289
area
  of circles, 175, 177
  of cones, 178–180
  of cylinders, 177–178
  of ellipses, 177
  measuring, 133, 171–180
  of parallelograms, 171, 172
  of polygons, 175, 176–177
  of rectangles, 171, 172
  of rings, 175
  of squares, 171, 172
  of trapezium, 173, 174
  of trapezoids, 173, 174
  of triangles, 171, 173
arithmetic
  alphabet of, 111
  compound numbers in, 126–127
  decimals in, 122–126
  defined, 111, 197
  evolution in, 129
  factors of numbers in, 115
  fractions in, 117–122
  French notation method for, 113
  involution in, 129
  multiples of numbers in, 115
  notation in, 111
  numeration of, 111
  percentages in, 128–129
  powers of numbers in, 129
  proportions in, 127–128
  radical signs in, 130
  ratios in, 127
  Roman notation for, 113, 114
  roots of numbers in, 129
  rule of three in, 128
  signs of operation for, 117–119
  units of, 112, 113
astronomical years, 139
automatic levels, 226, 228
avoirdupois, 137–138
azimuth screws, 201

B
backsight, 200, 206, 208, 209
barn siding, 84
basements
  abbreviations for, 275
  of Colonial homes, 283–284
  considerations for design of, 233–234
  in contemporary homes, 286
  plans for, 266, 269, 270
bases, 85
bastard sawing, 44
bathrooms
  abbreviations for, 275
  building specifications for, 251
  of Colonial homes, 283
  economical location of, 235
  fixtures for, 251
  tiling for, 245
beams
  abbreviations for, 275
  allowable loads on, 100–101, 109
  breaking loads on, 102, 103
  calculating length of, 190–191
  cantilever, 102–104, 105
  distributed loads on, 102, 103
  fixed, 100
  freely supported, 100
  restrained, 100
  selecting, 99
  stiffness of, 96–100
  support of, 98–99, 100
bedrooms, 234, 275
benchmark, 208
bending stress, 96, 106
blueprints. *See* architectural drawings
blue stain, 63
board measure, 136–137
boards
  finish boards, 84
  grades of, 70
  measurement of, 136–137

  nonstress-graded, 83
  in retail yards, 83
boat builders' layout method, 150–151
bolts
  calculating strength of, 28, 30, 32
  carriage bolts, 27, 29
  coarse-thread, 27
  description of, 39
  expansion bolts, 29
  function of, 23
  hanger bolts, 37–38
  heads of, 40
  history of, 23, 25, 27
  lag bolts, 39
  lock washer for, 30
  machine bolts, 27
  manufacture of, 23, 25, 27
  National Fine thread, 28–29, 31
  plain forged eye bolts, 29
  properties of, 31
  proportions of, 32
  railroad track bolts, 29
  rolled-thread, 28
  shearing stress of, 32
  and shears in wood, 95
  shouldered eye bolts, 29
  sizes of, 27, 31
  step bolts, 29
  stove bolts, 29
  strength of, 28, 30, 32
  tensile strength of, 32
  toggle bolts, 36–37
  types of, 27, 40
  uses of, 39
  welded eye bolts, 29
box nails, 13
brads, 3, 4–5
brass screws, 17
breaking loads, 102
brick, graphic symbols for, 273
brick veneer, 235, 270
bridging, 247
bubble level, 201
bubble lines, 201–202, 203–204, 209, 220–221
builder's level, 200
buildings
  government codes for, 235
  pole-type, 287, 289–291, 292
building specifications
  for bathroom fixtures, 251
  for bridging, 247
  for cabinets, 250
  for ceilings, 243
  for chimneys, 245
  for closets, 250
  conditions of, 244
  coping in, 246
  defined, 243
  for doors, 248–249
  example of, 243–252
  for exterior finish, 247
  for flashings, 248
  for flooring, 248
  for foundations, 245
  for framing, 246, 252
  for glazing, 248
  for installation of drywall, 245
  for interior trim, 249, 252
  interpretation of drawings for, 244
  introduction to, 243
  for lumber, 247
  for mantels, 249–250
  mason's work in, 244
  for painting, 251–252
  for pantries, 250
  for plumbing, 250
  for sheathing, 247
  for sheathing paper, 247
  for shingling, 247
  for sinks, 251
  for spacing, 247
  for stairs, 249
  for tiling, 245
  for timber, 246
  understanding, 252
  for wash trays, 251
  for water pipes, 250
  for windows, 248
  for wiring, 250
bung-head screws, 20

C
cabinets, 82, 250, 275
calculations
  for allowable loads, 100–101
  for allowable loads on columns, 91–92
  for breaking loads, 102, 103
  for deflection, 97
  by Euler formula, 91–92
  with slenderness ratio, 92
  See also mathematics
California rod, 227
cantilever beams, 102–104, 105
capacity measure, 143
cardinal numbers, 115
carriage bolts, 27, 29, 40
casing nails, 8
casings, 85
ceilings, 37–38, 229, 236, 243
centimeters, 141, 142
Chicago rod, 227
chimneys, 236, 245, 272, 274
circles
  bisecting arc of, 149
  circumscribing octagon about, 166, 167
  circumscribing square about, 160–161
  describing arc of, 155, 156
  describing by passing through given points, 155–156
  describing series of, 157–158
  drawing around triangle, 159, 160
  drawing tangent to, 156–157
  finding area of, 175, 177
  finding center of, 154–155
  finding circumference of, 169
  finding length of arc of, 169, 171
  finding rise in arc of, 171
  inscribing about a square, 159–160
  inscribing hexagons in, 164
  inscribing in triangle, 161, 162
  inscribing octagons in, 165–166
  inscribing pentagon in, 161, 162
  inscribing star in, 161–162, 163
  quadrants of, 182, 183
circular measure, 139–140
circumference, calculating, 169
close-head screws, 20
closets, 250, 275
coarse-thread bolts, 27
collimating, 202
Colonial houses, 281–284, 291
columns, 91–92
common bolts, 40
common denominators, 117–119
common fractions, 117, 119–120, 122, 124, 125, 197
common lumber, 77, 137
common machine bolts, 40
common nails, 5–9
compasses, 212, 215, 216, 221, 224
complete divisor, 131
composite numbers, 115
compound numbers, 126–127
compression, 51, 53, 90–91, 106
compression tests, 90–91
compressive strength, 53, 90–91
compressometers, 90, 91
concrete beams, 52
concrete blocks, 235–236
concrete, graphic symbols for, 273
concrete number, 115
cones, finding area of, 178–180
conifers, 42, 50–51, 54
conjugate axis, 166, 167
contemporary homes, 285–287, 288–289, 292
contractors, 244, 263, 265
coping, 246
cores, 77
corrugated fasteners, 11, 12
cosecant, 183–184
cosine, 183, 185–187, 189, 190
cotangent, 183–184
countersink device, 22
countersunk fillister-head screws, 20
crossbands, 77
crushing strength, 92

cube, of numbers, 129, 192–196
cube roots, of numbers, 192–196
cubes, 146
cubic measure, 133–135, 142
cup shakes, 56–57
curved lines, 142, 149
cut nails, 1, 2, 9
cylinders, 146, 148, 177–178

D

deadwood, 53
decay
  causes of, 57, 59–63
  and fire-retarding treatments, 60, 62
  fungal, 57, 59–63
  natural resistance to, 60, 61
  and preservative treatments, 60
  and pressure treatments, 60
  preventitive conditions for, 59
deciduous trees, 42. *See also* hardwoods
decimal points, 122–123
decimals, 197
  defined, 117, 122
  expressing common fractions as, 124, 125
  expressing fractions as, 122
  of foot and inches, 170
  fraction equivalents for, 125
  graphic representation of, 123
  multiplication of, 126
  subtraction of, 124
decimeters, 140, 141, 142
deflection, 96–99
deformation, 106
dekameters, 141
denominators, 117–121
design process
  agreeing on changes during, 238–239
  for basements, 233–234
  conferencing during, 236–237
  considerations for, 233–236
  designers' responsibilities in, 234–235
  for dining rooms, 234
  example of, 236–240
  following electrical codes in, 241
  for kitchens, 234
  matters of privacy in, 234
  owner's contribution to, 233, 240
  and sound resistance, 234
  for walls, 235–236
diffuse-porous hardwoods, 51
dimensional lumber, 83, 137
dining rooms, 234, 276
distributed loads, 102, 103
division, 116, 117, 120
doors
  abbreviations for, 274, 276
  building specifications for, 248–249
  of Colonial homes, 281
  design of, 249
  frames for, 248–249
  graphic symbols for, 271, 274
  materials for, 249
double-headed nails, 4
double shear, 95
Douglas fir, 50
dowel pins, 3
dowel screws, 20, 38
drains, 276
drawings. *See* architectural drawings
drawn wire nails, 2–3
drive screws, 20
drop siding, 84
dry measure, 135–136
drywall
  building specifications for, 245
  dowel screws for, 38
  expansion anchors for, 33–34
  fasteners for, 33–39
  framing fasteners for, 39
  hanger bolts for, 37–38
  hollow wall screw anchors for, 34
  installing, 245
  toggle bolts for, 36
  toggle studs for, 38–39
drywall ceilings, 37–39

drywall nails, 10, 11
ductile, 107
dumpy levels, 204–205

E

edge-grained shingles, 85
edges, 146
elasticity
  and allowable loads on beams, 100–101
  defined, 107
  measuring, 100–104, 105, 107
elastic limit, 107
electric drills, 17
electronic distance measurer (EDM), 226, 229
elevation, 255–258, 282
ellipses, 147, 166–167, 168, 177
end splits, 57
engineered lumber, 87–88
English system of measurement, 140
equality, 116, 117
equations
  for cubic measurements, 133
  defined, 116
  example of, 117
  for measurement of area, 133
  for trigonometric functions, 183
  for volume measurements, 133
equilaterals, 146, 147, 149
equilateral triangles, 146, 158
Euler formula, 91–92
evolution, 129–131
expansion anchors, 33–34
expansion bolts, 29
exponents, 129
external shears, 94

F

face plies, 77
faces, 146
face veneers, 77, 78
family rooms, 287, 289
fasteners
  bolts (*see* bolts)
  dowel screws, 38
  for drywall, 33–39
  expansion anchors, 33–34
  framing fasteners, 38, 39
  hanger bolts, 37
  hollow wall screw anchors, 34–36
  importance of, 1
  nails (*see* nails)
  for plaster, 33–39
  screws (*see* screws)
  toggle bolts, 36–37
  toggle studs, 38–39
Federal Housing Administration, 81
felloe screws, 20
fence staples, 11
fiber-saturation point, 48
fillister-head screws, 20
finish boards, 84
finishing nails, 5, 8
fireplaces, 245, 272, 274, 276
fire-retarding salts, 60
first-grade boards, 70
first quadrant, 182, 183
flashings, 248
flat countersunk head, 17
flat-grained shingles, 85
flat-grain lumber, 43, 45
flat-grain wood, 64
flat-head screws, 18–20, 22
flooring
  abbreviations for, 276
  appearance lumber for, 84–85
  architectural drawing of, 270
  building specifications for, 248
  graphic symbols for, 273
  hardwood for, 84, 85
  softwood for, 84–85
  thickness of, 84
  vertical-grained, 84
flooring nails, 8
floor plans, 266, 267, 268
footings, 270
foot screws, 213–214
foresight, 200, 206, 208, 209
foundations, 223, 245, 276, 287
fourth quadrant, 182, 183

fractions
  addition of, 117–119
  applications of cancellation for, 121–122
  common denominator in, 117–119
  common form of, 117, 197
  decimal equivalents for, 125
  decimal form of, 117, 197
  defined, 197
  denominators in, 117
  division of, 120
  expressing as decimals, 122
  forms of, 197
  improper, 117
  mixed numbers of, 117
  multiplication of, 119
  numerators in, 117
  proper, 117
  subtraction of, 120–121
frames
  abbreviations for, 276
  building specifications for, 246–247
  lumber for, 82
  of pole-type buildings, 287, 289, 291
  shrinkage of wood in, 49
  spacing of, 247
  timber for, 246
framing, 246–247, 252
framing fasteners, 38, 39
front elevation, 282
fungi, 57, 59–63

G
galvanized nails, 4
garages, 276
geometry
  angles in, 142–143, 145
  defined, 142, 197
  lines in, 142, 144
  perimeter in, 146
  plane figures in, 143, 145
  polygons, 146
  problems for, 146, 149–167
  solids in, 146, 148
  tools for solving problems in, 146, 149
glass, 273, 286
glulam, 87–88
gradienters, 224
grain measure, 136
grams, 142
graphic scale of proportions, 262
graphic symbols
  for building materials, 273
  for chimneys, 272, 274
  defined, 267
  for doors, 274
  for fireplaces, 272, 274
  function of, 269
  importance of understanding, 263, 269
  legends for, 269
  lines used in, 271
  purpose of, 262
  for stairs, 272, 274
  of walls, 271, 273
  for windows, 273
green wood, 94
grooved screws, 20
Gunter's chain, 132
gypsum board. *See* drywall

H
hallways, 276
hammers, 15, 16
hanger bolts, 37–38
hardwoods
  annual rings of, 54
  blue stain of, 63
  for casing and base, 85
  classification of, 46
  diffuse-porous, 51
  distribution of, 82
  for flooring, 84–85
  grades of, 86–87
  growth of, 65
  hardness of, 50–51
  mouldings of, 82
  nails for, 13
  in plywood, 79

hardwoods (*continued*)
  ring-porous, 51
  shearing of, 94
  summerwood versus springwood in, 51
  types of, 41
  uses of, 41
  vessels in, 43
  virgin versus second growth of, 54
heading blocks, 25
heart shakes, 56
heartwood, 42, 43
  for appearance lumber, 71
  decay of, 61
  decay resistance of, 60, 61
  distinguishing from sapwood, 60
  for shakes, 85
  for shingles, 85
  stiffness of, 100
  strength of, 55
hectoliters, 142
hexagon-head screws, 20
hexagons, 162–163, 164
holding power, 6–7, 9, 10, 12
hollow wall screw anchors, 34–36
Hooke's Law, 97, 108
hook-head nails, 9
horizontal lines, 142, 144
horizontal planes, 229
horizontal shear, 52, 94–96
houses
  basement in, 233
  Colonial style of, 281–284, 291
  considerations for design of, 233–236
  contemporary, 285–287, 288–289, 292
  designing bedrooms in, 234
  designing dining rooms in, 234
  designing kitchens in, 234
  economical location of rooms in, 235
  entry way of, 281, 283
  example of design for, 236–240
  materials for, 286–287
  of modern architecture, 284–285, 286, 287, 288, 292
  owner's requirements for, 233
  privacy of, 283
  selection of windows for, 234
  sound resistance of, 234
  specifications for (*see* building specifications)
  split-level, 286
  two-story, 281–284
hypotenuse, 168, 187

I
I-beams, 95
improper fractions, 117
index correction, 212
index error, 221
insects, 65
insulation, 273, 276
integers, 115
internal horizontal shears, 94
involution, 129
isosceles triangles, 146

J
joists, 48, 49

K
kiln-dried lumber, 54–55
kiln-drying, 46–47
kilometers, 140, 141
kitchens, 234, 235, 276
kitchen sinks, 251
knots, 58

L
lag bolts, 39
lag screws, 23, 25, 26, 27, 39
landings, 277
land measure, 141
land survey, 132–133, 139–140
laser levels, 227, 229–231, 232
lath, 70, 277
least common denominator, 120–121
left-end views, 258

leveling
  benchmark in, 208
  across bodies of water, 210
  correction for refraction and earth curvature in, 211
  defined, 199, 232
  finding relative elevations in, 207–208
  index correction in, 212
  methods of, 206–209
  between points greater than length of rod, 207
  at river crossings, 211
  at road crossings, 211
  sights for, 211
  simplest type of, 206–207
  on steep slope, 210
  through swamp, 210–211
  tools for (*see* levels)
  for triangulation work, 211–212
  trigonometric, 211–212
  in underbrush, 210
  across walls, 210
leveling moldings, 227
leveling rods, 205, 208, 227
levels
  adjusting bubble line of, 203–204
  adjusting parallax of, 205
  adjustment of, 202–205
  automatic, 226, 228
  backsight in, 200
  across bodies of water, 210
  centering objective and ocular of, 205
  collimating, 202
  construction of, 199, 201
  correction for refraction and earth curvature in, 211
  dumpy level adjustments, 204–205
  foresight in, 200
  function of, 199
  guarding from sun, 209
  laser, 227, 229–232
  line of collimation in, 199, 202
  lines of, 201–202
  looking through, 209
  making axis vertical in, 203
  at river crossings, 211
  at road crossings, 211
  sights for, 210, 211
  on steep slopes, 210
  through swamp, 210–211
  in underbrush, 210
  using, 209–211
  across walls, 210
  wye, 199–201
linear measure, 132–133, 141
line of collimation, 199, 202, 218, 220–221
lines
  in architectural drawings, 269, 271–272
  curved, 142, 144
  dividing into equal parts,153–154
  drawing parallel to, 152–153
  horizontal, 142, 144
  mensuration of, 168–171
  parallel, 142, 144
  in plane surface, 145
  straight, 142, 144
  types of, 197
liquid measure, 137
liters, 142
living rooms, 277
loads
  allowable, 100–101
  breaking, 102, 103
  on cantilever beams, 102–104, 105
  defined, 107
  distributed, 102, 103
  from snow, 104–106
  from wind, 104–106
local values, 111
lock washers, 30
logarithms, 192
long measure, 132
loose knot, 58
lumber
  abbreviations for, 71–76
  air-dried, 54–55
  air-drying, 46, 47

lumber (*continued*)
  appearance (*see* appearance lumber)
  biological attack of, 65
  bowing of, 59
  building specifications for, 247
  calculating allowable loads on, 91–92
  categories of, 68
  causes of defects in, 55–59
  chemical degradation of, 64
  color changes in, 63–64
  common, 77
  compression of, 51
  compressive strength of, 53, 63
  converting wood into, 43–44
  cup checks in, 57
  cupping of, 59
  cup resistance of, 64
  cutting, 43, 44, 45
  from deadwood, 53
  decay of, 57, 59–63
  decay resistance of, 60, 61
  density and strength of, 50
  deterioration of, 55, 65
  dimensional, 83
  distribution of, 82–87
  driving nails into, 13, 15–16
  dry weight of, 13, 50
  effect of altitude on, 59
  effect of drying on, 45–46
  effect of light on, 64
  end splits in, 57
  engineered, 87–88
  estimating density of, 50–51
  fire-retarding treatments for, 60, 62
  flat-grain, 43, 45
  fungi on, 57, 59–63
  glued laminated, 87–88
  grades of, 77, 86
  groups of, 41
  horizontal shear in, 52
  house-framing grades of, 82
  imperfect manufacture of, 56
  insect damage of, 65
  kiln-dried, 54–55
  kiln-drying, 46–47
  knots in, 58
  loose knot in, 58
  measurement of, 136–137
  medullary splits in, 58
  molding fungi on, 62
  monitoring moisture in, 47
  monomers for, 62
  nonstress-graded, 68, 69–70, 83
  preservative treatment of, 60
  pressure treatments for, 60
  preventing splitting of, 13, 15
  pricing of, 133
  purchasing, 86–87
  resilience of, 108
  retail yard inventory of, 82–86
  rift-grain, 43
  sapwood versus heartwood for, 55
  seasoning, 44–53, 87
  of second growth, 54
  selecting nails for, 13
  select lumber, 76–77
  shear in, 52–53
  shock resistance of, 62
  shrinkage of, 48, 49
  side-grain, 43, 45
  sizes of, 86
  from softwoods, 68–77, 82
  staining fungi on, 62
  standard sizes of, 67–68
  stiffness of, 108
  strength of, 51–53, 55
  stresses on, 108
  stress-graded, 68–69, 83
  tensile strength of, 53
  tension of, 51, 53
  toughness of, 62
  twisting of, 59
  types of strength of, 51–53
  vertical-grain, 43
  of virgin growth, 54
  visual grading of, 69
  warping of, 59, 63, 64
  weathering of, 63–65
  See also timbers; wood
lumber measure, 136–137

M
machine bolts, 27, 28
machine-screw threads, 38
mantels, 249–250
masonry nails, 10, 11
masonry walls, 235–236, 271, 273
masons, 244
mathematics
  applications of cancellation for, 121–122
  arithmetic (*see* arithmetic)
  branches of, 111
  functions of numbers in, 192–197
  geometry (*see* geometry)
  measures in (*see* measures)
  mensuration (*see* mensuration)
  trigonometry, 182–191, 197
mean solar day, 139
measures
  of angles, 143
  board, 136–137
  of capacity, 143
  circular, 139–140
  cubic, 133–135, 142
  defined, 131
  dry, 135–136
  in English system, 140
  equivalents of, 132
  of grain, 136
  for land, 141
  of land surveyors, 132
  linear, 132–133, 141
  liquid, 137
  lumber, 136–137
  metric system for, 140–142
  nautical, 133
  square, 133, 134, 141
  standards of, 131
  study of (*see* mensuration)
  of time, 139
  types of, 132
  of weight, 137–138, 144
  yards versus meters, 140
medullary splits, 58
mensuration, 131
  of arc of circle, 169, 171
  of area of circles, 175, 177
  of area of cones, 178–180
  of area of ellipses, 177
  of area of parallelograms, 171, 172
  of area of polygons, 175, 176–177
  of area of rectangles, 171, 172
  of area of rings, 175
  of area of squares, 171, 172
  of area of trapezium, 173–174
  of area of trapezoids, 173, 174
  of area of triangles, 171, 173
  of circular area of cylinders, 177–178
  of circumference of circle, 169
  defined, 167
  groups of, 167–168
  of length, 168–171
  of solids, 180–181
  of surfaces, 171–180
metals, 273
meters, 140–142
metric system, 140–144
millimeters, 140, 141, 142
mixed numbers, 117, 121
modern homes, 284–285, 286, 287, 288, 292
molding fungi, 62
moldings, 229
monomers, 62
multiplication, 116, 119–120, 126, 129

N
nails
  barbed, 4
  brads, 3, 4–5
  characteristics of, 3–12
  common, 5–6, 7, 8–9
  common types of, 3
  corrugated fasteners, 11, 12
  diameter of, 12
  driving, 13, 15–16
  drywall nails, 10, 11
  for hardwoods, 13
  heads of, 4

nails (*continued*)
  history of, 1–2
  holding power of, 6–7, 9, 10
  making of, 1–3
  masonry nails, 10–11
  for nailing boards together, 13
  number per pound length, 14
  penny system of, 3
  pilot holes for, 13
  roofing nails, 9–10
  versus screws, 16
  selecting hammers for, 15, 16
  selecting size of, 12–13
  selection of, 12–13, 39
  shapes of points on, 4
  and shears in wood, 95
  sizes of, 6
  smooth, 4
  for softwoods, 13
  spikes, 6
  spiral nails, 11
  staples, 11
  tacks, 2, 4
  whiskers on, 3
  withdrawal force of, 9
National Fine thread bolts, 28–29, 31
National Plumbing Code, 235
nautical measure, 133
nominal size, 67–68
nonstress-graded lumber, 68, 69–70, 83
notation, 111–113, 115
numbers
  abstract, 115
  cardinal, 115
  composite, 115
  compound, 126–127
  concrete, 115
  cube of, 129
  defined, 113
  factor of, 115
  French notation of, 113
  functions of, 192–196
  integral, 115
  multiple of, 115
  notation of, 111
  ordinal, 115
  power of, 129
  prime, 115
  Roman notation of, 113, 114
  roofs of, 129–131
  square of, 129
numeration, 111–113
numerators, 117, 119

O
object glass, 201
object slides, 224–225
oblique angles, 143
oblique projections, 258
obtuse angles, 143, 145, 182
obtuse triangles, 146
octagons, 164–167
ordinal number, 115
oval fillister-head screws, 20
oval head, 17
oval-head screws, 18, 20
owners, 263, 264, 265

P
painting, 251–252
parallax, 205
parallel lines, 142, 144, 152–153
parallelograms, 146, 159, 160, 171, 172
parallelopipedons, 146
partial divisor, 131
particle board, 79–82
partitions, 235, 247, 273, 277
penny system, 3
pentagons, 161, 162
percentages, 128–129
perimeter, 146
permanent set, 107
perpendiculars, 149–152, 153
phenol-formaldehyde, 81
Philadelphia rod, 227
Phillips slot, 17
piano-head screws, 20
pilot-hole drilling, 13, 15, 22
pilot holes, 38
pinched head screws, 20
pipes, 250–251

pith, 42
plain forged eye bolts, 29
plane figures, 143, 145–147, 149
plane trigonometry, 182
planks, 52–53
plaster, 33–39, 277
plastic expansion anchors, 33–34
plumbing, 235, 250
plumb walls, 227
plywood, 77–79, 133
pole-type buildings, 287, 289–291, 292
polygons, 146, 175, 176–177
Portland cement, 137
power screwdrivers, 17
precision rods, 205
preservative treatments, 60
pressure treatments, 60
prime numbers, 115
prints. *See* architectural drawings
prisms, 146, 148
profile plane, 256–257
projected views, 255–256
proper fractions, 117
proportions, 127–129

Q
quadrants, 182, 183
quadrilaterals, 146, 147, 148, 149
quartersawing, 43, 44, 45

R
radical signs, 130
rafters, 187, 290, 291
railroad track bolts, 29
ratios, 127–128
rectangles, 147, 159, 171, 172, 180–181
retail yards, 82–86
rhomboid, 147
rhombus, 147
rift-grain lumber, 43
rift-sawing, 43
right angles, 142, 145
right-end views, 256–258, 282
right triangles, 146, 168–169, 184, 187–188
ring-porous hardwood, 51
rolled-thread bolts, 28
Roman numerals, 113, 114
roofing, 191, 285
roofing nails, 9, 10
roofs
  building specifications for shingles on, 247
  calculating slope of, 184, 187–188
  of Colonial homes, 281
  estimating necessary amount of roofing for, 191
  of modern homes, 285
  of pole-type buildings, 290–291
  uplift allowance of, 106
  weight of snow on, 104–106
  wind loads on, 104–106
rooms, 277, 285, 286, 287
roots, 129–131
round bung-head screws, 20
round head, 17
round-head screws, 18, 19, 20
rule of three, 128
rupture, 107
rustic siding, 84

S
safety factor, 107
sapwood, 42, 43, 55, 60, 63, 100
scale, 260–262, 278
scalene triangles, 146
screwdrivers, 17, 35
screw heads, 39
Screw-Mate, 19
screws
  brass, 17
  corrosion of, 17
  description of, 17
  dimensions of, 18, 19
  dowel screws, 38
  driving, 18–19, 22
  gauge numbers for, 19
  head diameters of, 21
  heads on, 17, 18, 20–21
  for hollow wall screw anchors, 35–36

screws (*continued*)
  inserted across grain, 21, 23
  inserted with grain, 21, 23
  lag screws, 23, 25, 26–27
  lateral load on, 21
  materials for, 17
  versus nails, 16
  ordering, 18
  pilot hole in, 19
  safe resistance of, 21, 23, 24
  shank-clearance hole of, 18, 22
  shank diameter of, 18
  slots on, 17
  standard proportions of, 24
  steel, 17
  strength of, 21, 23, 24
  for toggle bolts, 36–37
  and toggle studs, 39
  uses of, 16
screw shank, 11
Screw-Sink, 19
seasoning, 44–55, 87
secant, 183–184, 185–187, 191
second-grade boards, 70
second growth, 54
second quadrant, 182, 183
sectional views, 258–260
select lumber, 76–77
septic tanks, 244
sewers, 250
shakes, 56, 57, 85
shank-clearance holes, 18, 22
shank diameter, 18
shearing stresses, 32, 92–94
shears, 52–53, 94–96, 107
sheathing, 247
sheathing paper, 247
shifting center, 214–215
shingle nails, 9
shingles, 85, 247
shouldered eye bolts, 29
side-grain lumber, 43, 45
siding, 84
signs of operation, 115–117
simple values, 111
sine, 183, 185–187
single shear, 95
sinks, 251, 278
slating nails, 9
slenderness ratio, 92
softwood lumber, 68–77, 82
softwoods
  blue stain of, 63
  for flooring, 84–85
  grades of, 86
  growth of, 65
  mouldings of, 82
  nails for, 13
  in plywood, 79
  types of, 41
  uses of, 41
solids, 146, 148, 180–181
sound knot, 58
southern pine trees, 50
specifications. *See* building specifications
spikes, 3, 6–7, 9, 10
spiral nails, 11
spirit levels, 217
sprig pins, 3
springwood, 50, 51
square bung-head screws, 20
square measures, 133, 134, 141
square, of numbers, 129, 192–196
square roots, 130, 192–196
squares, 147, 159–161, 164, 165, 171, 172
stadia, 225–226, 232
stadia rod, 227
staining fungi, 62
stairs, 249, 272, 274, 278, 283
stairwells, 236, 249
standard size, 67–68
Stanley company, 19
staples, 11
stars, 161–162, 163
star shakes, 56, 57
steel screws, 17
steel stirrups, 52
steel tape, 132
step bolts, 29
stiffness, 96–100, 108
stone, 273
stove bolts, 29, 40

straight lines, 142, 144
  bisecting, 149
  constructing hexagon from, 162–163
  describing octagon on, 164, 165
  drawing angle equal to given angle on, 154
  drawing perpendicular line to, 149
  erecting perpendicular to, 149–152, 153
  mensuration of, 168–169
straight-slotted heads, 17
strain, 108
stress couple, 94, 96
stress-graded lumber, 68–69, 83
studs, 48, 49
subtraction, 115, 116, 120–121, 124
summerwood, 50–51
surveying
  defined, 199
  divisions of, 199
  laser levels for, 227, 229–232
  with levels (*see* leveling; levels)
  with stadia, 225–226
  Theodolite for, 226, 228, 229
  with transit (*see* transits)
surveyor's chain, 132

T

tacks, 2, 3, 4, 5
tangents, 156–157, 183, 185–187
tangent screws, 217
telescopes, 201, 209, 217–220, 224
tenacity, 108
tensile strength, 32, 51, 53, 108
tension, 51, 53, 108
tension tests, 89–90
terra-cotta, 273
Theodolite, 226, 228, 229
thermosetting resins, 81
thick-butted shingles, 85
third-grade boards, 70
third quadrant, 182, 183
tiling, 245, 273
timbers
  allowable loads on, 100–101
  bending forces on, 106
  bending stress on, 96
  breaking loads on, 102, 103
  brittleness of, 106
  building specifications for, 246
  calculating allowable loads on, 91–92
  calculating rupture in, 107
  cantilever beams, 102–104, 105
  compression of, 106
  compressive strength of, 90–91
  crushing strength of, 92
  deflection of, 96–99
  deformation of, 106
  distributed loads on, 102, 103
  elastic limit of, 107
  forces on, 94–96
  grades of, 86–87
  horizontal shears in, 94–96
  for house framing, 246
  internal stresses in, 94
  measure of, 137
  measuring elasticity of, 100–104, 105, 107
  permanent set of, 107
  purchasing, 86
  resilience of, 107, 108
  safety factor of, 107
  seasonal cutting of, 54
  seasoning, 46
  second growth of, 54
  shear in, 107
  shearing stresses in, 92–94
  shearing tests for, 92–94
  sizes of, 86
  stiffness of, 96–100, 108
  strain on, 108
  strength of, 108
  stresses on, 108
  support of, 98–99
  tenacity of, 108
  tension of, 89–90, 108
  toughness of, 108
  tranverse stress on, 96
  vertical shears in, 94, 96

timbers (*continued*)
  virgin growth of, 54
  weight of snow on, 104–106
  wind loads on, 104–106
  working stresses for columns of, 91
  yield point of, 108
  See also lumber; wood
time measure, 139
toggle bolts, 35–37
toggle studs, 38–39
top views, 256
transits
  adjusting compass in, 221
  adjusting line of collimation in, 220–221
  adjusting screws of, 222
  adjustments of, 202–205, 219
  centering over stake, 222
  collimating telescope of, 219–220
  compass for, 212, 215–216, 232
  components of, 212
  construction of, 212–217
  controlling clamps of, 217
  divided limb of, 215
  figure of, 213
  foot screws in, 213–214
  function of, 212, 232
  gradienter for, 224
  index error in, 221
  inner spindle of, 215
  laying out foundations with, 223
  leveling, 222
  lines of, 218–219
  lower motion of, 215
  lubrication of, 225
  maintenance of, 224–225
  measuring horizontal angle in, 222–223
  outer spindle of, 215
  parallel plates in, 213
  parts of, 214
  shifting center of, 214–215
  spirit levels in, 217
  stadia hairs in, 226
  standards in, 217
  tangent screws of, 217
  telescope in, 217–218, 219
  Theodolite, 226, 228, 229
  upper motion of, 215
  using, 222–223
  vernier plate of, 215
  vertical code in, 217
transverse stress, 96
trapezium, 173–174
trapezoids, 173, 174
trees
  annual ring in, 50
  bark of, 41
  blue stain of, 63
  conifers, 42
  deciduous, 42
  density and strength of, 50
  growth of, 49–50
  heart shakes in, 56
  heartwood decay of, 61
  insect damage of, 65
  layers of, 41–42
  for lumber, 87
  moisture content of, 47–48
  rate of growth of, 49–50
  resistance to decay, 61
  sapwood versus heartwood of, 55
  shakes in, 56–57
triangles
  drawing circle around, 159, 160
  elements of, 182
  equilateral, 158
  finding area of, 171, 173
  finding length of side of, 168–169
  inscribing circle in, 161, 162
  mathematics of (*see* trigonometry)
  types of, 146
trigonometric functions, 183–187
trigonometric leveling, 211–212
trigonometry, 182–191, 197
trim, 249, 252
troy weights, 138
trusses, 291

U
urea-formaldehyde, 81
utility pole-type buildings, 287, 289–291, 292

V
vents, 276
vernier plate, 212, 215, 217, 219
vertical-grain flooring, 84
vertical-grain lumber, 43
vertical-grain wood, 64
vertical shears, 94, 96
virgin growth, 54
volume, 133–135, 180–181

W
walls, 235–236, 270, 271, 273, 285, 288
warping, 63, 64
washrooms, 278
wash trays, 251
water pipes, 250–251
wax sizing, 80
weight measure, 137–138, 144
welded eyebolts, 29
wind loads, 104–106
windows, 234, 248, 271, 273, 283, 286
wind shakes, 56–57
winged screws, 20
wire nails, 1–3, 7, 9, 14
wiring, 250–251
wood
  air-dried, 54–55
  air-drying, 46, 47
  annual ring in, 50
  bending forces on, 106
  biological attack of, 65
  blue stain of, 63
  bowing of, 59
  brittleness of, 106
  calculating allowable loads on, 91–92
  calculating rupture in, 107
  causes of defects in, 55–59
  chemical degradation of, 64
  color changes in, 63–64
  compression of, 51, 53, 106
  compressive strength of, 53, 63
  converting into lumber, 43–44
  crushing strength of, 92
  cupping of, 59
  cup resistance of, 64
  deadwood, 53
  decay of, 57, 59–63
  decay resistance of, 60, 61
  deformation of, 106
  density and strength of, 50
  deterioration of, 55, 65
  effect of altitude on, 59
  effect of drying on, 45–46
  effect of light on, 64
  elastic limit of, 107
  estimating density of, 50–51
  fastening, 1
  fiber saturation point of, 48
  fire-retarding treatments for, 60, 62
  forces on, 94–96
  fungal decay on, 62–63
  fungi on, 57, 59–63
  grading of, 88
  graphic symbols for, 273
  groupings of, 87
  groups of, 41–43
  growth of, 41, 42
  hardness of, 50–51
  heart shakes in, 56
  heartwood, 42, 43
  horizontal shear in, 52
  insect damage of, 65
  kiln-dried, 54–55
  kiln-drying, 46–47
  knots in, 58
  layers of, 41–42
  measuring elasticity of, 107
  mechanical properties of, 89
  medullary fibers of, 43
  medullary splits in, 58
  moisture content of, 47–49
  molding fungi on, 62
  monitoring moisture in, 47
  monomers for, 62
  oven dry, 48

wood (*continued*)
  in particle board, 81
  permanent set of, 107
  pith of, 42
  in plywood, 79
  preservative treatment of, 60
  pressure treatments for, 60
  protecting from decay, 45
  protecting from stain, 45
  reconstituted, 80
  removing moisture from, 44–53
  resilience of, 107, 108
  ring-porous hardwoods, 51
  safety factor of, 107
  sapwood, 42, 43
  seasonal cutting of, 54
  seasoning of, 44–53
  of second growth, 54
  shakes in, 56–57
  shear in, 52–53, 107
  shearing stresses in, 92–94
  shearing tests for, 92–94
  shock resistance of, 62
  shrinkage of, 48, 49
  sound knot in, 58
  specific gravity of, 50
  springwood, 50
  staining fungi on, 62
  star shakes in, 56, 57
  stiffness of, 108
  strain on, 108
  strength of, 51–53, 55, 108
  stresses on, 108
  structure of, 41–42
  summerwood, 50
  tenacity of, 108
  tensile strength of, 53, 108
  tension of, 51, 53, 108
  toughness of, 62, 108
  twisting of, 59
  types of strength of, 51–53
  of virgin growth, 54
  warping of, 59, 63, 64
  weathering of, 63
  wind shakes in, 56–57
  yield point of, 108
  See also lumber; timbers
wood-destroying fungi, 62–63
wood screws, 16–24, 39
wye levels, 199–205

Y
yard lumber, 69–70
yield point, 108

Chainsaw Lumbermaking

Will Malloff



Chainsaw Lumbermaking

Chainsaw Lumbermaking

Will Malloff

The Taunton Press

Cover photos and text photos
by Beth Erickson.

©1982 by Will Malloff
All rights reserved

First printing: June 1982
International Standard Book Number 0-918804-12-4
Library of Congress Catalog Card Number 82-80556
Printed in the United States of America

A Fine Woodworking Book

Fine Woodworking® is a trademark of The Taunton Press, Inc.,
registered in the U.S. Patent and Trademark Office.

The Taunton Press, Inc.
52 Church Hill Road
Box 355
Newtown, Connecticut 06470

Contents

IN THE SHOP

Chapter 1 **Basic Lumbermaking** **2**

Chapter 2 **The Saw** **4**
- The Saw Engine 4
- Engine Maintenance 5
  - Carburetor 5
  - Torquing 5
  - Air filter 6
  - Spark plugs 6
  - Sprockets 8
  - Fuel 8
  - Chain oil 10
- The Sawbar 12
  - Bar noses 12
  - Bar ends 12
  - Bar maintenance 14
- Engine Modification 16

Chapter 3 **The Chain** **18**
- Ripping Chain 18
- Chain Assembly 20
- The Grinder 24
- Chain Modification 26
- Sharpening 28
- Depth Gauges 30
- Hand-Filing 32

Chapter 4 **The Mill** **34**
- Mill Selection and Assembly 34
  - Mounting the mill 36
- Mill Modification 38
  - Thrust skid 38
  - Bolting on the mill 40
  - Assembling the mill 42
- Mill-Mounting the Chain 44

Chapter 5 **The Winch Unit** **46**
- The Winch 46
- Throttle Attachment 48
- Saw Bridle Button 50
- The Winch Yoke 50

Chapter 6 **Build Your Own Tools** **52**
- Lag Driver 52
- End Dogs 54
- Kerf Wedges 56
- Jacks 56

IN THE FIELD

Chapter 7 **Felling a Tree** **60**
- Safety and Tools 60
- Tree Selection 62
- Site Preparation 64
- Felling the Tree 66
- Limbing 70
- Bucking 72

Chapter 8 **Setting Up** **76**
- Equipment for the First Cut 76
- Index Lines 80
- Changing the Bar 88

Chapter 9 **Precision Milling** **90**
- The First Cut 90
- 2x12s 112
- 2x4s and 2x8s 126

Chapter 10 **More Precision Milling** **130**
- Box-Heart Timber 130
- Quartersawn Lumber 140
- Slabsawn Lumber 146

SPECIALTY MILLING

Chapter 11 **Special Cuts** **150**
- Burls 150
- Ovals 154
- Natural Knees 158
- Big Wood 168
- Quartering a Log 176

Chapter 12 **Specialty Mills** **180**
- Homemade Edger 180
- Precision Depth Cuts 184
- Cutting Circles 186
- 2x4 Mill 190
- Mini-Mill 196
- Angle Mill 198
- Timber Notches 202

Chapter 13 **Epilogue** **208**

Preface

I started chainsaw lumbermaking in a serious way more than twenty years ago. I was never satisfied with the efficiency of the equipment and systems available, and so began to design and construct my own. Over the years, I've developed and refined several mills and saw chains, and now I feel I have the most effective, simplest system for ecological lumber production. To my surprise, a lot of people agree with me. The result is that everywhere I go, and no matter where I retreat, people want to talk about chainsaw lumbermaking. It's hard to explain by drawing on a napkin or in the sawdust with a stick, so when Beth Erickson agreed to work with me, I saw that a book would be the perfect way to give chainsaw lumbermaking to the world. I am especially grateful to Beth for helping with the writing and for taking the photographs. I also appreciate the help and support of my precious friends and dear family, and to my loving parents, John and Mabel Malloff, I dedicate this book.

Will Malloff

Lethbridge, Alberta
Canada 1982

IN THE SHOP


DUBO

Chapter 1

Basic Lumbermaking

Anyone can make lumber. The process can be as simple or as refined as you wish to make it. In its crudest form, lumbermaking can be as uncomplicated as it looks in these photos. All you need is a chainsaw attached to a mill, a straight board, a hammer and three nails **(1)**. The board, positioned **(2)** and nailed to a log **(3)**, is a guide for the mill, which is adjusted to the depth of cut plus board thickness **(4)**. The mill is pushed along the board **(5)** and the sawbar pivoted out of the log at the end of the cut **(6)**. The board and slab are removed, the mill is adjusted for the next cut, and milling continues until the work is done **(7)**. That's all there is to it.

But for efficient lumbermaking and the best results, there are a number of other considerations, and over the years I have found many ways to refine the basic techniques. Let's have a look at the complete process—from the saw engine, ripping chain and mill to felling trees, milling boards and specialty cuts.

1



2

3

4

5



6

7

Chapter 2

The Saw Engine

A chainsaw is designed to crosscut, in other words, to cut across the grain. To rip lumber, however, the chainsaw must cut into the end grain, parallel to the fibers of the tree. To demonstrate the difference, take a short piece of lumber and make two parallel cuts across the grain with a handsaw. Then take a chisel and remove the wood between the two cuts. Notice how easily the wood falls out when crosscut. Now repeat the process on the *end* of the piece, going with the grain. In ripping, every fiber must be cut before the wood can be removed.

In crosscutting, the demand for engine power is intermittent. The outside edges of the kerf are cut with the sides of the cutters, and the remainder of the kerf wood is easily removed by the tops of the cutters. Ripping requires at least three times as much engine power as crosscutting because the saw has to run wide open from the start to the finish of each cut. Partial power is only necessary when starting and finishing a cut; otherwise the engine has to run wide open or not at all. So when choosing a saw for lumbermaking, look for one that can deliver maximum sustained power.

I recommend a saw engine with a long piston stroke that works in the 6,000 RPM range, with a chain speed of around 3,000 feet per minute. (A long piston stroke is simply one that is equal to or longer than the diameter of the piston.) My choice of engine is the direct-drive Stihl 090. The direct-drive, automatic-clutch system delivers the speed of the engine directly to the sprocket, which is the gear that delivers power to the chain. In my opinion, this is the simplest, most reliable transmission system for lumbermaking. While the gear-reduction system on gear-drive saws is good for milling, especially for milling big wood, there can be problems. The design of a gear-drive engine is such that the transmission system is upside down during milling, which can cause a lack of lubrication that often shortens transmission life.

When I choose a saw, I do not consider fuel consumption, noise, handling, vibration or weight. Nor do I necessarily use the bar, chain and sprocket that come as standard equipment—there are often better components available from manufacturers who specialize in these accessories.

Engine Maintenance

Proper engine care is crucial to good chainsaw performance—carelessness will lead to problems. Establish a practical maintenance routine and stick to it. Constant engine surveillance will soon become second nature.

Maintenance should start with a thorough knowledge of your saw. Study your operator's manual and follow its maintenance recommendations. If your manual doesn't contain a full parts list, make sure the dealer supplies you with one.

Carburetor—A carburetor contains fuel-filter screens, choke, throttle, idle-adjustment screw, and high-speed and low-speed jets, which regulate the proportion of fuel and air. Most carburetors are set at the factory for average elevation and atmospheric pressure, so you may need to adjust the carburetor to your location. Use your manual to learn how.

Because ripping requires continuous power, I run my engine at a richer setting on the high-speed jet than recommended by the manufacturer. In crosscutting, this would cause heavy carbon deposits on the spark plug and exhaust ports; in ripping, the extra fuel that passes through the engine gives additional lubrication and prolongs engine life.

To adjust the carburetor for ripping, start the engine (with bar and chain on) with the carburetor set at the manufacturer's recommended setting. Gently warm up the engine and start a cut into a log to bring the saw up to normal operating temperature. (Always make carburetor adjustments while the engine is hot.) Open the throttle wide and unscrew the high-speed jet until the engine starts to falter and perhaps even smokes a little. Then release the throttle to the idle position and adjust the low-speed jet until you get smooth and steady acceleration up to high speed. Adjust the idle-adjustment screw so the chain doesn't run while the saw is idling. I find opening the high-speed jet ⅛ or ¼ turn more than the manufacturer recommends is quite satisfactory, but running your saw like this could affect the validity of its warranty.

Periodically check the spark plug for carbon deposits. Too much carbon means your engine is running too rich. If this is the case, reset the high-speed jet closer to the manufacturer's recommended setting. Never set the high-speed jet to a lower setting than is recommended, because too low a setting can ruin your saw in just a few seconds.

Torquing—Vibration is an inherent problem of chainsaws, and over the years I have noticed the struggle of manufacturers to design bolts, nuts and screws that won't shake loose. While modern design has come close to finding the proper bolt, nut, washer and lock nut combinations, proper torquing is still vital.

After the first few hours of operating a new engine, I torque down the head bolts to compensate for the shrinkage of the cylinder gaskets **(1)**. Heads and cylinders are usually a one-piece unit. If you have a two-piece unit, torque both the head and the cylinder. Also torque the carburetor-mounting gasket and muffler gasket along with any loose nuts, bolts or screws. After one or two torques, most saws usually need no further torquing, but inspect yours periodically.

I lubricate often-used screws, nuts and bolts with Never-Seez, a thread-lubricating grease, but a mixture of graphite and grease also works well. On bolts, nuts and screws that loosen, I use a bolt-and-thread locking mixture called Loctite. Use this after using the cleanser sold as a companion product. Always start nuts, bolts and screws with finger pressure to help avoid crossthreading.

Air filter—The air filter of a chainsaw must thoroughly clean the air going into the carburetor. Sawdust and debris entering with the air could cause the engine bearings or pistons to seize, ruining the engine. There are three basic types of filters: wire screen, flocked screen and foam. Ripping produces finer sawdust than crosscutting, and you should keep this in mind when selecting a filter. Wire-screen filters don't stop the finer sawdust, so I prefer flocked or foam ones.

Check filters after every two or three refuelings, more frequently if working with soft woods such as cedar, or abrasive woods such as mesquite. Before removing the filter cover, brush away sawdust and debris. When a filter shows the slightest sign of clogging, you should change it **(2)**. A fouled filter reduces engine power and increases fuel consumption by changing the proportion of air to fuel. If you notice you're using more fuel than usual, check your air filter.

Clean dirty filters in a gasoline bath or with detergent and water, and allow them to air-dry. Do not use compressed air for cleaning flocked filters because the air blows the flocking out of the screen base. I usually take several clean filters (stored in plastic bags) into the field to save myself the bother of in-the-field cleaning.

Spark plugs—Spark plugs burn out more frequently in ripping than in crosscutting. Loss of power and hard starting are often signals of a faulty spark plug. The amount of carbon, its color and the color of the spark can also indicate engine problems. Charts that identify spark plug problems are handy tools, and are available from most saw dealers and plug manufacturers.

A fairly clean electrode area and a fat, blue spark are pretty good signs of a properly functioning engine. But I have found that even a good-looking plug can be faulty, becoming a problem only under compression, when the engine is hot.



1



2

To remove a spark plug, it's safer to use a rubber-cushioned spark-plug socket **(1)** rather than the T-handled combination bar and plug wrench that usually comes with chainsaws. Loosen the plug just enough to enable you to remove it by hand. If you use a wrench during the last turns, you could damage the threads.

To change plugs, remove the new plug from its container carefully and check the gap with feeler gauges or a spark-plug tool. Always use the plug recommended by the manufacturer. The length of the plug threads is precise, and using the wrong one could result in plug-to-piston contact, which would damage both components. The wrong plug can also generate too much (or too little) heat, resulting in a burnt-out piston or head, or incomplete fuel combustion.

Lubricate the plug threads **(2)** to avoid thread wear and to aid in future removal. Start the plug into the head gently, then torque with a socket. If the plug doesn't start into the head easily, inspect the head for damaged threads.

Check and service the spark plug on your saw regularly, and always have one or two extra handy in the field.

Sprockets—The sprocket drives the chain. There are two basic types available: a rim sprocket **(3)** and a spur sprocket **(4)**. The rim sprocket stands up to milling best and is the one I prefer.

In normal chainsaw use, replace the sprocket each time you replace the chain. You can rotate two new chains with one rim sprocket for longer sprocket life, but don't couple an old sprocket to a new chain or a new sprocket to an old chain—this will damage both sprocket and chain. You can see the damage in photos 3 (right) and 4.

Fuel—Lumbermaking puts heavy stress on a saw engine, so for extra lubrication I use a lower ratio of gas to oil than is recommended by the saw manufacturer. If the manufacturer calls for twenty-four parts gas to one part oil, for example, I use twenty parts gas to one part oil.

Use the oil and gas recommended by the manufacturer of your saw, especially during the saw's warranty period. When the recommended oil wasn't available, I've used snowmobile oil made for 2-cycle, air-cooled engines. Never use outboard engine 2-cycle quick mix, detergent, nondetergent or multigrade oils in your saw, because these cannot cope with the heat range of air-cooled chainsaw engines. Some chainsaw dealers stock new oils that suggest gas-to-oil ratios of fifty and even one hundred to one. Should you feel that these offer advantages, experiment with caution. I haven't tested them.

Clean fuel and good mixing procedures are a must. I've found that a five-gallon, plastic container with an internal, fine-screen spout and capped vent is the best. Metal containers tend to generate water from condensation and rust when not kept completely full.

Before fueling up, empty and clean the plastic container. Then pour in the proper amount of oil and add about a quarter of the amount of gasoline required. Shake well, add the rest of the gasoline and shake well again. Shake the container before every fill-up to mix the oil and gas.

1

2



3



4

Never smoke when refueling or checking the fuel tank. A partially filled tank is like a Molotov cocktail—the smallest spark can ignite it.

Occasionally, when a saw is mounted for milling, the fuel filter inside the gas tank will become dislodged in an upright position. This causes the engine to falter when you pull the throttle trigger and makes the engine sound as if it's not getting enough fuel. To check for this, wipe any sawdust or debris away from the fuel tank cap and remove it. Then drain the tank and inspect it to see if the filter is positioned properly. If the filter is dislodged, hold the saw upright and let the filter drop to the bottom of the tank before refueling.

Fouled fuel filters impede the proper flow of gas and should be removed. Take a short piece of wire and bend a crook in one end. (Some saw manufacturers supply such a tool with their tool kits.) Then insert the wire into the tank and gently pull out the filter unit **(1)**. Remove the cap that covers the screened filter holder and take the filter out of its housing **(2)**. Inspect it for water or dirt. You can wash a dirty filter in fuel mix, but I usually just replace it with a new one. Put back the filter cap and put the unit into the fuel tank. Make sure it drops to its proper position at the bottom. Gently screw on the fuel tank cap, making sure it is properly threaded. Do not overtighten it.

Fuel tank caps sometimes leak through the venting hole when the saw is mounted for milling. Usually, this is caused by a factory defect. Have your dealer replace the cap until you get one that works properly. It's not a good idea to plug a leaky venting hole because this creates a vacuum in the fuel tank, which puts a lot of stress on the fuel-pump diaphragms in the carburetor.

Chain oil—High-quality chain oil is essential for good lubrication. Chain oil is unlike ordinary oil in that it is specially made to penetrate to the rivet flanges and drive-link tails of the chain, while sticking to the bar rails, groove and nose.

Some manufacturers supply both a light-viscosity winter oil and a heavy-viscosity summer oil, while others supply just one. Heavy oil is sometimes thought to be less prone to fly off the chain, but I believe it also has less chance of penetrating to the rivets inside the drive links. This results in inadequate oiling, which can cause the chain to wear excessively, stiffen or break. I use a light-viscosity oil year round. Re-refined, light-viscosity oil gives excellent results, inexpensively. My favorite oil is SAE 10 hydraulic.

If I have to use a heavy-viscosity oil, I dilute it with diesel fuel so that the automatic chain oiler can function adequately. A chain oiler is functioning adequately if the drive links always show a film of oil, and the oil tank doesn't empty before the gas tank. If the automatic oiler on your saw has an adjustable flow control, open it as wide as possible for milling, without letting the oil tank go dry before the gas tank. If the oil tank has run dry and the oiler has an auxiliary manual pump, prime it by pumping before engine start-up. You should also pump the oiler before starting the mill into each cut because it provides a surplus of oil, and a well-oiled start prolongs chain and bar life.


IMPORTANT!
SET IDLE JET NOT MORE THAN ¼ TURN OPEN,
SET HI-SPEED JET NOT LESS THAN 1¼ TURN OPEN,

1



2

The Sawbar

The bar of a saw supports and guides the chain. As ripping places great stress on a sawbar, it is especially important that the bar used in lumbermaking be made of good-quality, hard steel. Soft steel wears quickly and can cause a number of problems. I think Cannon (Cannon Machine Works, 6337 Laurel, Burnaby, B.C., Canada V5B 3P3) makes the best bars, but a variety of manufacturers and designs exist **(1)**.

To lighten the saw, chainsaw bars manufactured today are narrower in design. A narrow bar will work well with a mill up to 30 in. wide, but it will sag in the middle if the mill is improperly mounted to it. For mills over 30 in., I use a custom-built bar wide enough to support the additional length.

Bar noses—Bars are available with a choice of noses. In this photo **(2)**, the first bar on the left has an internally mounted bearing-sprocket nose. The second bar has a nose with an insert of steel harder than the bar welded to its edge. The third bar has a new style bearing-sprocket nose and the fourth bar has a bearing-roller nose.

I use a bar with a bearing-roller or bearing-sprocket nose because the bearing reduces the amount of friction between bar and chain and allows the chain to cut with up to 20 percent more power. A sprocket or roller supports the chain away from the bar and helps eliminate bar-end wear. The pitch on bearing-sprocket and bearing-roller noses must match the pitch of the chain and engine sprocket. The fraction marked on the bar that is third from the left in the photo shows the pitch of the nose.

When a mill is mounted to a bar, it must be positioned so as not to impede the work of the bar nose. The bar should be 4 in. to 6 in. longer than the length of the mill.

Bar ends—Bar-end designs vary **(3)**, but all have elements in common. Slots allow movement of the bar for chain tensioning, the large holes accommodate the chain-tension pin, and the small holes allow oil passage from the engine to the chain. Make sure the bar you select has the proper mounting configuration for your saw.

1


CANNON
PRECISION GROUND GROOVE
OREGON

2



3



Bar maintenance—The bottom edge of a bar usually leads into the cut, and so receives the most wear. To balance wear, flip the bar top to bottom after about 20 hours of operation. Always make sure before remounting that the oil hole is clean.

In proper operation, the tie straps of the chain slide along the bar rails. But as the bar rails in this photo wore down **(1)**, the drive links of the chain started to ride on the bottom of the bar groove, plowing it out. This ruined the chain and burned the bar. The point is: With regular bar inspection and maintenance, this problem could have been avoided.

As the chain slides along the bar rails and the bar begins to wear, a burr can form along the rail edge **(2)**, causing improper chain tracking. Square the rails by draw-filing **(3)**. Support the file on two blocks of wood, each positioned square to the top of the bar. Hold the file as shown in the photo.

If the rails have become too hard for draw-filing, a metal-cutting wheel mounted in a Skilsaw or table saw will do the job **(4)**. Mount the wheel 90° to the saw table and lightly pass the bar against the wheel in gentle, steady strokes the full length of the bar on both sides. A properly squared bar will balance on its edge on a level surface.

I use a belt sander to clean the sides of the bar and to remove any burrs there **(5)**. Sand evenly over the entire surface. If you don't have a belt sander, use a flat file.



1



2



3



4



5

Also on the bar-maintenance checklist should be a periodic check of bar-groove width, also called bar gauge. With feeler gauges, measure groove width all around the bar **(1)**, and compare this measurement with the known gauge of the bar.

To determine the amount of wear, subtract the new width from the original width. For example, if the new measurement is .072 in. and the original gauge was .063, the wear is .009 in. Worn bars can be rehammered and regrooved by bar-repair shops. I usually send mine in when wear exceeds .010 in.

Bar-groove depth also needs to be checked regularly. If you have a bar-groove measuring tool **(2,3)**, use it to check at intervals around the bar. If you don't have one, use a matchstick or anything else that will fit easily in the groove. Compare the length of the bottom of a drive link **(4)** to groove depth; there should be space between the bottom of the drive links and the bottom of the bar groove. This distance reveals remaining bar life.

Engine Modification

An engine sawdust guard **(5)** does several jobs. It holds the guide plate that controls chain entry into the bar and it is also the clamping bracket for the bar. In normal crosscutting, the guard allows sawdust to be directed away from the saw through a bottom opening.

However, when the saw is inverted in the milling position, the opening doesn't allow the sawdust to escape properly, which causes a sawdust buildup between the centrifugal clutch and the guard. This often leads to internal clutch problems and heavy clutch-shoe wear.

An easy modification eliminates this problem. Simply cut away the sawdust-shielding portion of the unit **(6)** and use the guide plate and clamping bracket as you normally would. This exposes additional moving parts, but because the saw is inverted during milling, the advantages make it worthwhile to me.

With this modification, you also won't have to remove the bar from the engine to mount or remove the chain.



1



2



3



4



5



6

Chapter 3

Ripping Chain

The most important factor in successful lumbermaking is properly prepared and maintained chain. Although you can use standard crosscutting chain, this will result in inefficient milling. You really need ripping chain, and in the early 1960s I invented and patented ripping chain especially for chainsaw lumbermaking. This chain is made by modifying crosscut chain and is sold today by various manufacturers of portable mills.

Over the years I grew dissatisfied with the inefficiency of the original, patented ripping chain, so I continued my research. Today I have what I consider to be the ultimate chain for lumbermaking **(1)**. This new chain is not yet available commercially, but you can modify your own chain at home, using either a grinder or a hand file. I usually use Oregon square-edge chisel chain (model 52L) made by Omark (Oregon Saw Chain Division, 9701 S.E. McLoughlin Blvd., Portland, Ore. 97222) for .063-in. gauge bars with .404-in. pitch. I've never had any success modifying round or chamfered-edge chain. I also don't recommend using safety chain. Safety chain is designed to prevent the nose of the bar from kicking back when crosscutting, but when ripping, the guard links prevent good sawdust clearance and adequate sawdust flow.

It's not hard to modify chain, but first you must have a working knowledge of its components. Chains have several variable features: pitch, gauge and number of tie straps between each cutter.

Chain pitch is the distance between the centers of one rivet and the rivet after the next, divided by two. The saw sprocket and the barnose sprocket (if your bar has one) must have the same pitch as the chain.

Chain gauge is measured by the thickness of the bottom of the drive links, which ride in the groove of the bar. Chain gauge must be coordinated with bar gauge.

Regular chain has a single tie strap separating each cutter; skip-tooth chain has two tie straps. I always use regular chain because a single tie strap gives better support to the cutters. While skip-tooth chain has fewer cutters to be modified and sharpened, I find it does not cut as smoothly or as efficiently.


Modified Square-Edge Chisel Chain
Right-hand cutter
Tie strap
Preset rivet
Drive link
Depth gauge
Top plate
Travel
Tie strap
Cutter gullet
Rivet hole
Left-hand cutter
Chain Pitch
Chain Gauge
Divided by 2 = chain pitch
Standard Chisel Chain
Top
30°
60°
Inside
75°
Outside
Modified Chisel Chain
Top
90°
40°
Inside
40°
Outside

1

Chain Assembly

I prefer to purchase chain in bulk (rolls of 25, 50 or 100 ft.), because it's usually less expensive than preassembled chain. When working with bulk chain, you need to know the length needed for the saw and bar you're using. Chain length is often referred to by the number of drive links rather than by measured length. When the model number of a chain manufactured for a particular saw is followed by a dash and another number—for example, 52L-70E—the last number (70E) refers to chain length (which means the chain has 70 drive links). Most saw dealers have length charts that give the number of links necessary for the saw and bar you're using.

Of course, you can also determine chain length by counting the drive links of an existing chain for your saw. Or you can retract the sawbar and thread the chain around the bar. Mark the tie strap where the chain ends meet, which is where the chain must be broken. Then rivet the ends of the chain together to form a continuous loop.

There are various ways to dismantle and reconstruct chain. Several types of chain breakers and spin riveters are available, and although some of these work well if you follow the directions, others don't. I prefer to use my own system.

To begin, clamp the tie strap square in the jaws of a vise at the point where the chain is to be broken. File the two rivet heads flush with the tie strap side **(1)**, or grind the heads flush on a grindstone (I usually do this freehand). Remount the chain in the vise, clamping the drive links, and complete the break by applying a little sideways pressure to the strap **(2)**. You could also use a punch to complete the break. (Wear gloves when handling chain, especially if you are unaccustomed to working with it.) Discard the dismantled tie strap **(3)** and use a new one to assemble the chain. Always break chain on a tie strap, but if you have to break at a cutter, assemble the chain using a new tie strap instead of a new cutter.

1



2



3



Occasionally it's necessary to break a used chain to repair or shorten it. Chain tends to stretch with use, and you'll have to shorten it when it stretches beyond your saw's tensioning capacity. But because tie strap width decreases with wear, you'll have to adjust the new tie strap to match the used ones before assembling the chain. First, measure the width of one used tie strap **(1)**, then file the bottoms of the new straps to the width of the used one **(2)**. Failure to do this can result in excessive bar wear and erratic cutting.

To assemble chain, place a preset tie strap (the one with the rivets attached) on the bottom **(3)**. Direct the rivets up through the drive links being connected. Place a regular tie strap over the rivets. I use vise-grips to hold the two tie straps together for peening on an anvil **(4)**. Peen the rivets gently, using the ball part of a machinist's ball-peen hammer. Then reset the vise-grips onto one of the connecting drive links for access to both rivets, and continue peening until the head is formed **(5)**.



1


2



3



4



5

The Grinder

You'll find that a good disc-wheel chain grinder **(1)** will soon pay for itself by its accuracy in modifying and sharpening ripping chain. Although you can use hand files to modify chain (p. 32), one grinding stone will do the work of several dozen files. The grinder is also the only tool able to sharpen cutters whose edges have become crystallized by contact with sand, rocks and metal. I like to use the Jolly Chain Grinder, made by Windsor Machine Co. Ltd. (3147 Thunderbird Crescent, Burnaby, B.C., Canada (V5A 3G1).

Most grinders come equipped with two stones—a fine-grit stone for grinding and sharpening chain cutters and a coarse-grit stone for grinding depth gauges. I prefer to use a coarse-grit stone for initial chain modification and a fine-grit stone for sharpening. But regardless of the grit, all grindstones tend to clog, which can cause the chain cutters to burn. I have experimented with various stone lubricants, and have found that paraffin is the best one. Rubbing a block of paraffin or a paraffin candle on the spinning stone frequently (at least several times per chain) not only reduces clogging substantially, but also reduces the number of times you need to dress the stone **(2)**.

Stone thickness is not critical when sharpening ripping chain because the most important part of the grind is done with the side of the stone. But in initial chain modification, it's best to use a stone that is thick enough to remove the total amount of metal necessary in one pass. Stone shape, however, is important. To produce the correct cutter shape (p. 26), you'll have to establish a flat edge on the stone for grinding the bottoms of the cutter gullets and a rounded edge for shaping the round part of the gullet.

Although I'm using a carborundum stone dresser in these photos, I prefer to use a star-wheel dresser to shape the stone. Star-wheel dressers actually cut away the stone, while carborundum dressers (and the diamond dressers built into some grinders) tend to clog it up. For a good cut that produces a crisp edge, you need a sharp, clean, grinding surface.

Shape the flat edge of the stone by setting the grinder cutting arm at 50° from vertical. Use the chain track on the grinder to control the movement of the carborundum stone dresser or star wheel **(3)**. Pull the grinder arm down gently to bring the stone into contact with the dresser, and slide the dresser from side to side on the chain track—in this way, the bottom of the stone is ground parallel to the chain track.

To form the rounded edge, hold the dresser freehand against the leading edge of the stone **(4)**. With short, controlled sweeps, round the edge. Wear safety glasses when using a grinder to protect your eyes from flying debris.

1



2

3

4

Chain Modification

Regular chain, beveled across the fronts of the cutters at 30°, enters the kerf at an angle, which can cause excessive side pressure on cutters and drive links. When chain is ground this way, the corner of each cutter becomes the prime cutting area; once that area dulls, cutting ability is greatly reduced. To solve this problem, I grind my ripping chain cutters straight across the fronts with the shaped grinding stone adjusted 50° from vertical (40° from horizontal). This is the way commercial sawmills grind their blades for circular saws, gangsaws and bandsaws.

To modify chain, first adjust the grinder so the stone is 90° to the chain, then tilt the stone to a 50° hook angle. Mount a square-edge chisel crosscut chain in the chain track and advance the chain so that the back of a cutter touches the tip of the pawl **(1)**. You can start with either a right-hand or a left-hand cutter, as this system allows left and right cutters to be ground one after another.

Bring down the stone and adjust the pawl backward or forward so the top of the stone will grind off the entire angled edge of the cutter—no more and no less. Then lock the cutter into position, pushing it up against the pawl. Start the grinder, and with a firm grip on the grinder arm, lower the stone gently so that it starts to cut **(2)**. Check to be sure you are only grinding off the complete pregound angle. If you have to, slack off on the lock handle and readjust the pawl.

Grind with short strokes until the bottom of the stone comes to just above the tops of the drive links **(3)**. Then let up on the grinder arm so the stone can rise. Shut off the motor, and when the stone has stopped spinning, lower the arm until the stone comes down to the bottom of the new grind. Lock the stone in that position so all the cutters will be ground to the same depth.

Now release the pressure on the grinder arm and allow the stone to return to its out-of-cut position. Examine the cutter tooth—notice how the edge of the stone has made a straight cut down the front of the cutter **(4)**. The rounded part of the stone has formed a gullet that is not only stronger than a sharp-angled gullet, but also will help direct the flow of sawdust. Also notice the amount of metal removed. The gauge in this photo **(5)** reads 40° from horizontal, which is 50° from vertical.

Repeat the process, pushing the next cutter up against the pawl. After grinding, examine the cutter to be sure it has the same grind as the previous one. Check frequently as you progress to make sure all adjustments are properly set.

As the grinding stone becomes glazed, retouch it with the stone dresser. With continued use, the flat side of the stone will wear, causing the grinding angle to drop below 50°. A decrease of a degree or two isn't important, but if the angle drops to 45°, you can compensate with an increase in the angle of the arm of the grinder. Or, dress off the flat edge of the stone and round off the leading edge, as in basic stone modification (p. 24).



1



2



4



3


GENERAL
NO 17

5

Sharpening

A dull chain is usually the cause of power loss and poor cutting in milling. Sharpen the chain as soon as it shows the slightest sign of dulling. The top edge of a cutter will not reflect light if it is sharp, but a dull edge will shine.

Use either the chain grinder or a file to maintain the shape and edge on your chain. Cutters dulled in normal use require only a little grinding to restore sharpness. You can use the same coarse-grit grinding stone for sharpening as you did for cutter modification, or a fine-grit stone (lubricated with paraffin to retard clogging), modified to the correct shape.

Mount the chain in the grinder, then adjust the pawl so the stone can pass into the cutter gullet with zero clearance between the stone and the top edge of the cutter **(1)**. The chain should be positioned so that the stone just brushes past the edge of the cutter. Gently lower the stone into the gullet and adjust its depth stop.

To make a sharpening pass, start the grinder and lower the stone to the bottom of the gullet, applying slight sideways pressure on the grinding arm toward the cutter **(2)**. At the bottom of the gullet, release the sideways pressure to allow the stone to rise out of the cut. If you don't do this, you'll get a large burr on the cutting edge. You'll also get a large burr if the stone has become glazed.

Now examine the cutter to be sure it has been completely sharpened. The shiny, dull edge should be completely gone, leaving a sharp edge that will not reflect light.

If cutters are severely damaged, you'll have to adjust the grinder to remove the whole damaged area on the top plate of each cutter **(3)**. Use the most damaged cutter in the chain as a gauge to adjust the pawl. This will ensure that the damage on all the cutters will be removed, and that they will be ground to the same length and sharpness. When excessive grinding is necessary, always check the depth-gauge height (p. 30).

For sharpening chain on the bar, I like to use a Simington sharpener (Simington Products Co., Star Route 141, Chiloquin, Ore. 97624). It's battery-powered and can go right into the woods with you **(4)**. A 12-volt motorcycle battery will power many sharpenings on a single charge. Though there are a variety of motor-powered, on-the-bar chain grinders available, I don't recommend them—they are inefficient and, above all, inaccurate.



1



3

4



2

Depth Gauges

The depth gauge controls the cutting depth of each cutter **(1)**. All depth gauges should be set at the same height so that an equal workload can be carried by all the cutters. When measuring new chain, I've often found depth gauges that are more than .010 in. off, which causes cutting inefficiency as well as chain, bar and sprocket wear.

The proper height for depth gauges varies with the species of tree to be cut, log size, engine power and bar length. For ripping, I usually set depth gauges about five or ten thousandths of an inch more than is recommended for the crosscutting chain I've modified. For example, with a Stihl 090 and a 52L Oregon chain, I normally use a .045-in. depth-gauge clearance. Set the depth gauges only after the chain has been modified; check and file them down, if necessary, after about every fourth or fifth chain sharpening.

To check depth-gauge setting, use a depth-gauge tool. These come in a number of styles and at a variety of preset depths. I prefer a depth-gauge tool with the filing slot in the center, which allows you to use both hands on the file. A tool with the filing slot on an end must be held with one hand as you file with the other. With the chain on the bar, mount the tool with its slot positioned over a depth gauge **(2)**. If the depth gauge protrudes above the slot, it needs to be filed down. Use a 6-in. mill bastard file until it won't cut anymore **(3)**. The area around the slot is harder than the file can cut, so you won't hurt the tool or overcut the depth gauge.

After filing, move the chain forward so that the next depth gauge is in the same position on the bar. It is important to file each depth gauge in the same location because curvature in the bar can cause variations in depth-gauge readings. Complete the filing of all the depth gauges on the chain, then, with the same file, round off the lead corner of each depth gauge to original factory shape **(4,5)**. I usually do this freehand.

Depth-Gauge Setting

To determine depth-gauge setting, measure the distance between a straightedge set on top of two cutters on the same side of the chain and the top of the depth gauge. All gauges should be set to the same height.


Straightedge
Cutting depth

1



4


DEPTH GAUGE

2



3



5

Hand-Filing

Chain modification with a file guide and round file is essentially the same as with a grinder, but when modifying by hand, I file a 45° hook on each cutter instead of a 50° hook. This is because the round file leaves an edge that is hollow-ground; if the hook were filed to 50°, the cutting edge would be weakened.

To modify my .404-pitch, .063-gauge 52L Oregon chain, I use the Oregon model #25892 file guide and a $\frac{7}{32}$-in. round file. Start off with the file diameter recommended for your chain, but switch to the next smallest size ($\frac{1}{32}$ in. less) when the cutters of the chain are about half-worn. Don't assume the file guide will be straight when you take it out of the package—check yours and straighten it out if necessary.

The file guide, as it comes from the manufacturer, is set to file a hook angle of approximately 5°—to increase the angle, it is necessary to shim the file in the guide at both ends, directly under both clamps **(1)**. I usually use two or three strips of a matchbook cover to start, adding strips until the file cuts a 45° hook. It's a good idea to start with a conservative number of strips, to avoid removing too much metal. For an example of shim thickness, with the $\frac{7}{32}$-in. file and guide I'm using here, the shim measures .060 in.

When hand-filing in the shop (and especially for initial chain modification), I prefer to hold the chain in a small machinist's vise, rather than to file while the chain is on the bar. (When sharpening in the field, when the chain is on the bar, I mount the bar in a holder made especially for field work.) With a square, draw a line 90° across the jaws of the vise, then mount your chain. Position the file guide flat on top of the first cutter, touching the depth gauge, and keep the guide parallel to the line **(2)**.

With both hands, file in long, controlled strokes, using the full length of the file. Don't drag the file on the back stroke, as this will wear it out. Remember to keep the guide flat on top of the cutter. Keep filing until the hook angle on the side of the cutter is 45° and the top plate is 90° across **(3)**. The bottom of the cutter gullet should be just above the tops of the drive links. To speed things up, I sometimes file the cutter back freehand, then use the guide to complete the modification accurately.

As you modify your chain, measure the length of the top plate of the cutters to make sure that they are all exactly the same. You can use a crescent wrench or caliper for a gauge.

It's a good idea to rotate the file in the guide slightly as you feel it start to dull. At least two files will usually be necessary to modify one chain. Never use a dull file to modify or sharpen chain—it's a waste of time.



1


FILE HOLDER

2


170
10
160
20
150
30
130
50

3

Chapter 4

Mill Selection and Assembly

When selecting a chainsaw lumbermaking device, consider the size of the logs you plan to mill, as well as your type of chainsaw and the bar length. For many of my milling needs, I use a Granberg Mark III Alaskan Mill (Granberg Industries Ltd., 202 S. Garrard Blvd., Richmond, Calif. 94804) **(1)**. These come in a variety of sizes from 24 in. to 56 in.; I find the most efficient mills are 48 in. and under.

The Mark III mill is lightweight, reasonably durable, accurate and inexpensive. It also has flat-bottomed, sliding guide rails, which scrape the sawdust from the milled surface as they go. (The fine sawdust not scraped away acts as a lubricant.) Roller guide rails, common on many types of mills, roll up over wood chips and sawdust, resulting in an irregular cut. If you're using a mill with roller guide rails, make a point of keeping the milling surface free of debris as you go.

If you purchase a mill, and it's not assembled, inspect the components against the parts list and drawings supplied by the manufacturer before you do anything else. Then lay out the components in the approximate order of assembly, checking each for twist, bend or warp. Correct any defects you find, and if a component is beyond repair, have it replaced. Lubricate often-used nut and bolt threads with a good lubricant, such as Never-Seez or a mixture of grease and graphite, to allow for proper torquing and adjustment. The lubricant helps reduce thread wear and also retards rust and corrosion. Then assemble the mill, following instructions carefully. Take your time—haste can lead to damaged or misaligned parts.

When the mill is assembled, double-check to be sure you've followed all procedures properly before taking the mill into the field. Remember, precision in the shop is vital to productive and enjoyable work in the field.



Standard Granberg Mark III Alaskan Mill

Riser post
Adjustable entry guide rail
Mill handle
End bracket
Sliding guide rail
Thrust-skid-end adjustment post
Nose-end adjustment post
Sawbar
Chain travel
Thrust-skid-end clamping bracket
Nose guard
Nose-end clamping bracket

1

Mounting the mill—To mount the mill on the sawbar, slack off the bar nuts and loosen the chain. Retract the bar as far as possible and draw a line across the bar where it meets the saw. This line marks the farthest point at which the mill can be mounted on the engine end of the bar. (If you're using the engine for both crosscutting and ripping, and are leaving the felling spikes on the saw, mark at the end of the spikes.)

Return the bar to its working position, readjust chain tension and secure the bar clamping nuts. Mark the tip of the bar at a point that will allow space between the bar and the nose guard or helper handle. The two vertical lines in the photograph **(1)** mark the maximum limits for mounting the mill on this bar.

Before mounting, set the height of the mill to 3 in. on both riser posts. Then mount the mill within the marked lines, as close to the engine as possible. If the mill is mounted too far forward, the weight of the engine could cause the bar to flex or the chain to track improperly, resulting in a bowed cut or even a bent bar.

After mounting, check that the bar is straight by laying a straightedge against it lengthwise or by sighting down the bar—a twisted or sagging bar can be a power robber. Then raise the mill setting to maximum cutting height, making sure to move both end brackets evenly up the riser posts. Double-check that the bar is straight by sighting down it **(2)** or using the straightedge. If the bar isn't straight at the maximum setting, loosen a mill-handle bolt at one end of the mill and the two guide-rail bolts at the same end. Adjust the mill handle until the saw straightens.

With all components in proper position, the mill aligned, and all nuts and bolts torqued, the standard mill is ready to go. But first let's have a look at a few other things you might want to do.

1



2



Mill Modification

Thrust skid—The thrust skid of the Mark III Alaskan Mill has a built-in design problem. It often loses contact with the log **(1)**, which causes the riser post to touch the side of the log, and quite often, to get hung up. The heavy vibration and stress exerted on the riser posts, guide rails and mill handle can also result in parts breaking or bending, or in misalignment of the mill.

Here's one simple solution to the problem. Mount another thrust-skid unit inboard. Purchase these Mark III parts **(2)**: #790 clamping bracket (thrust-skid end); #788 clamping bracket (nose end); two #808 $^5/_{16}$" x $3\frac{1}{2}$" carriage bolts; two #684 $^5/_{16}$-in. hex nuts. Epoxy small strips of cloth-backed sandpaper (from a worn, coarse sanding belt) to the steel pads on the brackets to prevent the thrust skid from slipping on the bar. Bolt the unit on where needed **(3)**.

There's another problem with the standard thrust skid—it often gets caught on a log's surface irregularities, causing the mill to jog and cut unevenly. I therefore find it necessary to use an additional thrust skid **(4)** that is much longer than the standard skid. You can make it from 1-in.-square steel tube if available, but angle iron will also do quite well. Heat the end of the tube and bend it while holding it in a vise. Hacksaw a slightly curved line for the nose and another line for the shoe. Remove the wedge of metal between the lines and pound the shoe up around the nose. Trim off the excess and weld or braze the nose and shoe together. Drill two $^3/_8$-in. holes in the new skid to align with the holes in the standard skid, and attach it to the mill.

The extra length and curved end of this thrust skid ensure smooth mill travel over log irregularities. The photograph **(5)** shows the thrust skid in action.


1


2


3


Thrust Skid
⅜" holes
1-in.-square steel tube
Nose
Waste
4½"
6"
9½"
1½"
Shoe

Hold the steel tube in a vise, heat the end and bend it. Hacksaw a curve for the nose and another for the shoe. Remove the waste, pound the shoe up around the nose and weld the nose and shoe together. Drill two ⅜-in. holes, in alignment with the holes in the standard skid, to attach the new skid to the mill.

4

5

Bolting on the mill—The standard Mark III Alaskan Mill clamps onto the chainsaw bar. This design lets you use the same bar for both crosscutting and milling by simply clamping on the mill, but to replace a dull chain with a sharp one, you have to remove the entire mill unit. So I use a separate bar or another saw for crosscutting and modify my mill so that it bolts onto the milling bar. This lets me change chains while the mill remains mounted.

Here's how to modify a mill for bolting on. Drill and tap ½-in. holes dead center on both riser posts **(1)**. On the thrust-skid (engine) end of the mill, drill and tap two 5/16-holes, each at a distance of ¾ in. from the center of the first hole. On both ends of the mill, drill out the two existing 5/16-in. holes in the adjustment posts and clamping brackets to ⅜ in., to accommodate ⅜" x 4" bolts. These bolts are long enough to accept spacer nuts between the modified thrust skid and the sawbar, while leaving enough space to remove the chain. The bolts also hold the sawbar nose guard in place on the mill **(2)**.

To modify the sawbar to accept the mill, measure the distance between the centers of the ½-in. holes in the riser posts with mill height set to 3 in. Mark and center-punch the bar for two corresponding holes.

On the engine end of the bar, mark and center-punch two 5/16-in. holes, each at a distance of ¾ in. from the center of the ½-in. hole.

Drill the bar holes at very low speed with a good-quality, high-speed drill or a carbide-tipped masonry drill. Be sure to have an old bar or a piece of flatstock iron under the bar to drill into **(3)**. This is the secret to drilling bars. If you drill into the hole in the drill-press bed or into a wooden support block (as is normal metalworking procedure), the drill would just start through the bar and the unfinished hole would harden because of the air-hardening qualities of bar steel. You'd end up with an unfinished, hardened hole and a burnt-out or broken drill bit. (Should this ever happen to you, grind out the hardened hole with a round stone in a high-speed grinder.)

1



2



3



Assembling the mill—When mounting the sawbar, be sure the mounting areas of saw, bar and guard are clean. Oiler holes on saw and bar **(1)** should be free of obstructions. Fit the bar on the studs and over the chain-tension pin, and clamp the bar to the engine with the clamping bracket. Tighten the nuts.

Bolt the bar to the riser posts through the ½-in. holes with 7⁄16″ x 1¼″ bolts **(2)**. Use an extra heavy, ½-in. flat washer under the bolthead for a good torquing base. On the thrust-skid end of the mill, insert 5⁄16″ x ¾″ bolts and washers through the bar and into the holes. These bolts add support and compensate for the extra pressure the long thrust skid will put on the post. It's a good idea to use thread lubricant on all nuts and bolts.

Now pass two ⅜″ x 4″ bolts through the holes in the adjustment post on the thrust-skid end of the mill. Screw four ⅜-in. nuts on each bolt and torque them down. Put the long thrust skid over the bolts and lock it with two more nuts. Torque the skid down with the first nut and use the second to lock the first.

On the nose end, pass two ⅜″ x 4″ bolts through the adjustment post and nose guard. Screw on two ⅜-in. nuts on each bolt and install the clamping bracket with the pad inverted. On the non-cutting side of the bar, screw and torque two ⅜-in. spacer nuts. Then screw and torque one ⅜-in. nut on the bolt on the cutting side of the bar. Install a ⅜-in. flat washer and then a ⅜-in. lock washer, and torque down a ⅜-in. nut. This forms one of the winch buttons necessary to hold the ropes used in the winching setup. The other button is described on p. 50.

Once you've mounted the mill, make one final modification. Drill a ⅜-in. hole through the standard thrust skid in alignment with the chain-tension screw. With this modification, you can reach the screw easily with your screwdriver **(3)** and tension the chain while in the cut.

A properly mounted, modified mill and bar will not need to be removed for chain sharpening or maintenance, but you should flip the bar every 20 hours of operation to balance bar wear. Simply unbolt the bar from the modified mill and remount it upside down.



1



3


Modified Mill
3/8" x4" bolts
Thrust-skid-end adjustment post
3/8" x4" bolts
Riser post
Sawbar
Nose-end adjustment post
1/2" flat washer
3/8" nut
Long thrust skid
Chain travel
3/8" nut
7/16" x1 1/4" bolt
5/16" x3/4" bolt and washer
Nose guard
1/2" extra heavy flat washer
7/16" x1 1/4" bolt
3/8" nut
Nose-end clamping bracket with pad inverted
3/8" nut
3/8" flat washer
3/8" lock washer
3/8" nut

2

Mill-Mounting the Chain

After modification, it becomes quite simple to mount or remove chain from the saw.

To mount the chain **(1)**, retract the bar by slacking off about a half turn on the bar nuts, just enough to enable you to loosen the chain-tension screw. (Count the number of turns it takes to loosen the chain-tension screw and you'll find it easier to tension the chain later.) Hold the chain in the proper direction of travel and insert it behind the clutch and onto the chain sprocket. The chain should be going away from the saw engine at the top of the bar and toward the engine at the bottom.

Thread the chain through the space between the thrust skid and the bar **(2)**. Place the chain between the chain-guide plates and feed it through the thrust-skid space **(3)**.

Continue threading the chain, starting it in the groove around the nose **(4)**. Make sure the chain is properly positioned on top of the bar and all the way back to the engine, then advance the chain with your fingers so it drops into the groove. Tighten the chain on the bar as you feed it into the groove.

Now, holding the chain at the center of the bar top and bottom, move it a few revolutions around the bar to remove kinks. Then hold the chain at the center of the top of the bar and lift it up out of the groove. If the drive links just clear the top of the groove under normal finger pressure, and you can easily rotate the chain by hand, the chain is properly tensioned **(5)**.

With the tension set correctly, tighten the bar nuts **(6)**. Rotate the chain around the bar, lubricating it with the manual oiler as you go. Start the engine and run the chain a bit, then stop it and check the tension, adjusting if necessary. New chain tends to stretch on break-in, so check the tension again soon after you start milling.

Adjusting chain tension is an important maintenance procedure. Chain that is too loose can whip out of the bar groove; chain that is too tight can cause a rough cut and, if not checked, will wear out quickly.

The procedure for removing a chain is essentially the same as for putting it on. Slack the bar nuts about a half turn, just enough to loosen the chain by unscrewing the chain-tension screw. Lift the chain up out of the groove on top of the bar and pull it back a bit **(7)**. Rotate the chain around the bar a little and off the nose. When the chain is off the nose, thread it back along the bar. Slip it off the sprocket and out around the clutch.

Always be careful when handling chain.



1



2



3



4



5



6



7

Chapter 5

The Winch

In lumbermaking, you normally have to push the mill and roaring chainsaw through a cut, breathing exhaust fumes and spitting out sawdust all the while. But with my setup **(1)**, you can stand back from the noise and vibration, and move the saw through the cut with minimum labor—all you have to do is crank a winch handle. Besides the winch, you'll need a remote throttle attachment for your saw, winch buttons to hold the winching ropes and a winch yoke. I'll discuss each of these in turn.

You can make a winch from parts that are readily available. I use a small boat-trailer winch as the base mechanism. You'll also need an electric hand drill, a hacksaw and a bench grinder.

Make winch dogs (to attach the winch unit to the log) by tapering ⅜-in. bolts. Hold each bolt in the chuck of the drill and, with the drill switched on, grind the taper with a bench grinder **(2)**.

Assemble the winch **(3,4)** and mount the winch rope. Cut a length of ¼-in. or 5⁄16-in. nylon or polypropylene rope a little longer than double the length of the log you'll be milling, then splice or tie an eye to each end. Fold the rope in half and attach the fold to the winch drum. Later you'll thread the rope ends through the cheek blocks on the winch yoke (p. 92).



1



2



3

The Winch

¼″ flatstock iron, 20″ x 1¼″
⅜″ bolts, washers, nuts, 3″ o.c.
⅜″ lag bolt
Metal sleeve
1½″ angle iron, 4″ long
5/16″ nylon or polypropylene rope folded double
⅜″ bolts, washers, nuts
Ends threaded through cheek blocks on winch yoke
Winch dogs ground from ⅜″ bolts, 3¼″ o.c.
Winch dog ground from ⅜″ bolt



4

Throttle Attachment

Because the operator is at one end of the log and the saw at the other when milling with my system, you need to build a remote throttle attachment **(1)** to work the saw trigger. This one is designed for a Stihl 090, so if you're using a different engine, you might have to adapt a little. The illustration **(2)** shows the parts you'll need. The surgical tubing should be long enough (about 6 in. to 8 in.) to provide proper tension in the open-throttle position. You can substitute shock cord for surgical tubing, if you wish.

When you assemble the parts, lubricate the bolt between the two flat washers so the bearing surface can move freely. Adjust the bearing tension of the two flat washers with the first nut so the arm moves easily without wobbling, and lock it with the second nut.

Through the saw handle, drill and tap a ¼-in. thread **(3)** and mount the attachment **(4)** by screwing the bolt into the hole and locking it with a nut and washer. I'll explain how to use the remote throttle attachment on p. 94.

In addition to holding the throttle open when in a cut, the remote throttle attachment also can be used as a locking throttle when hand-milling. Because the operator doesn't have to hold the throttle open manually, the amount of vibration normally endured is reduced. To use the attachment as a locking throttle, open the eye on the free end of the surgical tubing to form a hook, then drill a small hole in the engine casting to accommodate the hook **(5)**. A small piece of string tied around the ends of the surgical tubing will keep the eyes secure. Flip the attachment to an open position **(6)** for convenient hands-off, open-throttle milling.



1


The Throttle Attachment
String
Surgical tubing
¼″ bolts
¼″ flatstock iron, 1¼″ x 11″
Shortened double-headed nail forms eye.
Flat washers
¼″ lock washer
¼″ nuts
¼″ bolt

2



3



4



5



6

Saw Bridle Button

The winching rope is attached at one end to the mill (p. 42) and at the other end to the middle of a length of rope I call the bridle rope. One end of the bridle rope goes to the remote throttle attachment; the other end must attach to the saw. But since there's no place on the saw to accept a rope, you have to make a holding button. I call this the bridle button.

On the Stihl 090, I substitute a 5⁄16" x 1½" bolt for the original metric bolt **(1)** to make the bridle button. This is the logical place for it, as the bolt is in a strong position on the saw and in the line of pull when winching through a cut. If the threads on the bolt don't go all the way to the head, drill out the mating nut with a 5⁄16-in. drill. Two ⅜-in. flat washers hold the bridle rope around the nut **(2)**. I prefer to use a star lock washer, mounted against the engine casting or under the bolthead, instead of a 5⁄16-in. split lock washer, because it's easier on the aluminum. Torque the bolt assembly securely through the engine casting and into the bolt hole in the handle. The photo **(3)** shows how the bridle rope is mounted on the button.

The Winch Yoke

For the mill to be pulled at bar level in a straight path you need a winch yoke **(4)**. The yoke also helps keep the guide rails of the mill level on the top plank. The cheek blocks on the ends of the yoke direct the rope slightly downward for a well-controlled cut **(5)**.



1

3



2



5


The Winch Yoke
Ropes from winch
To bridle rope
Reinforcing bolts with flat washers
Single cheek block
To winch button on mill
8″
3″
3″
9″
2⅜″
32″
Double cheek block
1½″
Holes for lag bolts
Holes for double-headed nails, which hold better than lags in some hardwoods

4

Chapter 6

Lag Driver

To complete your milling kit, here are a few handy, work-saving tools that can easily be made from existing tools.

Using a box-end wrench or a ratchet-handled socket wrench to drive lag bolts (p. 86) is tedious work. I prefer to use a hand-drill brace and a modified short extension bar from a ⅜-in. or ½-in. socket set. Simply grind the square-holed end of the extension bar to fit the brace **(1,2,3)**. Use a hexagonal (6-point) socket for hex-head lag bolts and an octagonal (8-point) socket for square-head lags **(4)**.

If you want to make the modification permanent, weld the socket to a drill-brace collar **(5)**. Keep the collar from turning by drilling and bolting it to the ratchet head with a ¼-in. or 5/16-in. bolt and nut. Secure the nut by riveting the bolt over it, or use a center punch to expand the bolt into the nut. Keep the moving parts of the brace well oiled.



1

2



3



4



5

End Dogs

The inner tensions of a tree, caused by its reaction to the environment, often make boards twist or bend as soon as they're sawn. This distortion can throw off a properly aligned milling system. So I've designed end dogs to help keep boards straight until the cut is complete—the dogs tack board and log together, so the board can't deform during the cut.

The best end dogs can be forged from short pieces of automobile leaf spring **(1)**, though other hardened steel would probably do as well. These end dogs are durable, easy to set and rarely need maintenance. To make them, first round the ends of the spring stock. Then heat and bend the ends so that they are at right angles to the flat stock. Reheat the dog to a dull red, and allow it to cool slowly in the air to harden. Grind the upturned ends from the outside to a sharp edge and then grind the edge straight across so that it is about $\frac{1}{32}$ in. to $\frac{1}{16}$ in. wide. End dogs with edges that are too sharp deform eventually and become difficult to drive.

If you don't have access to a forge, you can make adequate end dogs from square steel, aluminum tube or even flatstock iron **(2,3)**. You can also modify an extra set of thrust skids **(4,5)**. Simply drill holes to accommodate lag bolts. Use $\frac{3}{8}$-in.-diameter lags or, for the convenience of using the same lag driver, use lags of the same diameter as those used for guide-plank supports.



1



2



4



3



5

Kerf Wedges

As a saw moves through wood, the width of the cut it makes is called a kerf. In milling, the piece being sawn tends to sag into the kerf as the saw opens up the log. This often causes the chain to pinch. Sagging also causes an uneven cut, because the flat surface on which the mill's guide rails ride becomes unparallel to the desired cutting line. At the end of a cut, the entire weight of the milled piece is carried by the bar. This causes the saw to make a deeper cut, which results in curved ends on the milled board.

To eliminate these problems, I insert kerf wedges every few feet of the cut. The wedges support the piece being milled and keep the kerf open, allowing the bar to travel freely. I also insert a wedge on each side of the log just before the end of the cut. This allows the mill to exit easily and eliminates end run-off. Six or eight wedges are sufficient for most milling jobs.

Make the wedges from pieces of hardwood that are about 1/32 in. thicker than the kerf **(1)**. Taper the ends of the wedges slightly and round the corners for easy entrance into the kerf. Rounded handle ends with chamfered edges are easy on the hands. I paint my wedges a bright color to make them easy to spot if they drop into the sawdust. The paint helps preserve the wood, too.

Jacks

One or two bumper jacks are invaluable tools for rolling or lifting large logs or cants, and for clamping wood into various positions. But the base of an unmodified jack tends to slip off its footing or sink into the ground **(2)**. To overcome this problem, I use two 3/8-in. bolts and nuts as holding dogs. Bolted to the base, they grip rocky surfaces or bite into crosspieces placed underneath the jack.

To prevent the jack from slipping at the point of contact with the log, it's necessary to weld a dog securely to the jaw of the jack **(3)**. Cut the dog from a piece of flatstock iron and grind one end to a sloping edge for good bite and easy release. Keep the moving parts of your jack well lubricated with chain oil.

1



2



3



IN THE FIELD

Chapter 7

Safety and Tools

Felling a tree is the most dangerous part of lumbermaking. To do it well is an art—fell only when you fully understand the process and hazards, and are sure you can handle the work safely. I have felled trees professionally for over 25 years and am alive and well today only because of my dedication to safety.

Safe felling requires strict working habits. When I first broke in as a feller, an old-time logger told me, "Watch out for your tools, they're out to get you." I respected his advice, and it has kept me alive long enough to learn that it isn't always the tool that's out to get you—you can also get yourself. But with well-maintained tools, you certainly have less chance of getting hurt. So always keep your ax sharp, its handle tight and your chainsaw well serviced.

In the field, always wear a hardhat and safety glasses. Loose clothing can easily get caught in a running saw, so wear only well-fitting clothing and boots. It's also a good idea to wear hearing protection, even for short work periods, because the noise of a roaring chainsaw can damage, or even destroy, your hearing. I started felling trees long before ear protection was common in the woods and have become accustomed to listening for the warning sounds of falling limbs and breaking trees, so sometimes I choose not to wear hearing protection.

Never become overconfident when felling, and never cut down a tree when you are hampered by wind or bad weather. Stay away from alcohol and drugs, and don't work when you are tired. Fatigue can cause you to work dangerously—a hot chainsaw muffler can cause a serious burn; a slip of a wrench and you could cut your hand on the chain. Also, try not to work alone, but if you must, at least tell someone when and where you're going and when you will return. Always keep a well-equipped first-aid kit nearby. If you have assistants, never assume they understand work dangers: It's up to you to insist upon safety.

In short, don't take risks. Every time I step up to a tree that I want to fell, I feel a tingle of fear run down my spine. Don't feel embarrassed if you'd rather not take on this aspect of lumbermaking. There are experienced professionals who can do the job for you.

Because this book is about lumbermaking, I won't try to cover all the details of the felling process, but I will recommend an excellent book that does. The *Faller's and Bucker's Handbook*, published by the Worker's Compensation Board of British Columbia (5225 Heather St., Vancouver, B.C., Canada V5Z 3L8), is a modestly priced, logging-industry handbook that I find quite helpful.

The felling tools you will need will vary with your situation and skills. Here is a basic list:

- a saw engine coupled to a bar equipped with crosscutting chain
- a file for sharpening chain
- a bar wrench
- a measuring tape
- safety gear
- engine fuel and oil
- a properly serviced ax

  A single-bit, 3½-lb. ax is good for felling and wedge driving. Check that the axhead is on tight, and round off the sharp edges on the back of the head to reduce wedge wear. I usually store my working axhead in water, especially in hot, dry weather, to keep the wood from loosening around the head. Always keep your ax in a safe and handy position for easy access during felling.
- two or more felling wedges

  These wedges are different from splitting wedges. You can make them from hardwood, but I usually buy the plastic ones sold by chainsaw-supply dealers because they are more durable. Never use steel wedges with a chainsaw because one slip can wipe out the chain cutters. Experiment with wedges of various lengths and thicknesses, as different timber and weather conditions require different designs. Frozen wood, for example, requires special wedges.

Keep tools and fuel in a convenient cache behind a stump or standing tree, safe from falling limbs or a misdirected tree.

Tree Selection

The usefulness of the lumber you mill in part depends on the tree species, so proper identification is crucial. Develop a working knowledge of the types of trees in your area, and learn to identify each one **(1)**.

Tree structure will also help determine usefulness—consider the number of limbs on the tree (and the number of knots hidden within). Does the tree twist? If so, the grain of the wood most likely will twist, too. Does the tree lean? Leaning trees contain reaction wood, which moves and machines abnormally.

Also consider tree size. Measure the tree's diameter to be sure your mill can handle it **(2)**.

Once you've selected a tree, see if it can be felled to a good working location. Will it leave damaged limbs on adjacent trees that could threaten your safety during milling? Does the tree have a dead top or broken limbs? Is its butt hollow or decayed? Test for soundness by thumping the tree around its base with your axhead **(3)**. An unsound butt could cause a tree to fall to an unsafe or inconvenient milling site or to hang up in an adjacent tree.



1

2

3

Site Preparation

Clear away any limbs, brush, roots, stumps and rocks from around the base of the tree you've chosen, and select a convenient site for debris. Then remove all tree limbs as high as your saw can reach, cutting them as close to the tree as possible **(1)**. Make sure your saw is getting plenty of lubrication, and until you know that it is, try not to run the chain too fast, especially on automatic-oiling saws. With a saw having a manual oiler, pump it to get lots of oil on the bar and chain.

Check the base of the tree trunk for obstructions such as spikes, wire fence and rock, and remove any with an ax. Then establish the line of fall. A straight tree can usually be directed to the desired location easily, but if the tree leans, you must take corrective steps.

To determine a tree's lean, hold your ax up to the tree with the blade edge at the center of the trunk. Sight up the handle **(2)**. Repeat in two or three other locations for an accurate reading. If the tree leans away from the proposed line of fall, wedges driven into the backcut (p. 66) can lift the tree past its center of gravity toward the desired location.

Now clear at least two escape paths away from the proposed line of fall and at least one path in the line of fall, in case wind, overcutting or other errors cause the tree to fall in the opposite direction. Select a stout tree or stump at the end of each path as shelter from flying limbs and treetops.

Bedding logs **(3)** placed across the proposed line of fall will support the tree at a convenient height and protect it from dirt and rocks. Determine the lengths of the logs you intend to buck from the tree, and place bedding logs at intervals relative to these. Bedding logs should be long enough to compensate for errors in felling direction and thick enough to support the tree. Be careful not to use thin logs, which might break on impact, but on the other hand, don't use logs that are too thick—these can cause the tree to break when it is felled across them.

Some trees are too brittle for this approach. Lift brittle logs to a convenient milling height after the tree is felled and bucked to length.

1


2

3

Felling the Tree

There are three cuts necessary to fell a tree: the first undercut, the second undercut and the backcut. While cutting, try not to stand under the lean of the tree.

With the chain well lubricated, start the undercut with the felling spikes of the saw up against the tree **(1)**. Cut into the tree a distance between a quarter and halfway, keeping the cut level **(2)**. Then remove the saw.

The second undercut meets the first to form a wedge that is later removed, allowing the tree to hinge down on the remaining wood **(3)**. Start the second undercut above the first, at an angle that will allow it to meet the end of the first cut. The height of this cut should be at least a third of the first cut's depth—too narrow a wedge will cause the tree to break the hinge prematurely. Make sure the two cuts meet exactly on each side of the wedge opening; if the second undercut slants to one side, the tree will hinge down on the narrower side first, and swing in that direction. After you complete the cut, remove the wedge with your ax if necessary.

Now place the head of your ax into the undercut **(4)** so that its handle is at a right angle to the line of the cut; the handle will point to the direction of fall **(5)**. Reposition bedding logs if you have to. Remove the ax and start the backcut opposite to and a little above the first undercut **(6)**. Keep the backcut level.



1



2



3



4



5



6

With the saw into the cut enough to allow you to drive in a wedge, but not enough to start the tree moving, set a wedge at the center of the tree **(1)**, being careful not to hit the chain. The wedge will support the tree during the remainder of the cut; if the tree doesn't fall when the cut is finished, drive the wedge in further to lift the tree and start the fall. When driving a wedge, short blows work better than long, hard drives. Always break up the frequency of wedge pounding, however, as regular rhythm can set up enough vibration in a tree to cause a brittle treetop or limb to break off and hit you on the head.

Continue the backcut **(2)**, stopping when the bar gets close to the undercut. Don't cut all the way through the tree—leave enough wood for the tree to hinge upon. Too little holding wood will cause the tree to slip or twist off the stump, and the tree won't fall in the expected direction. Experience will teach you how much hinge to leave.

The tree will usually begin to fall before the backcut is finished **(3)**. Stop the saw and put it in a safe place as you retreat. Or take it with you as you wait in safety for the tree to hit the ground. Before you move again, check for widow-makers—limbs that might be hung up in nearby trees and have yet to fall. Take your time and be certain it's safe to continue.

Carefully examine the felled tree to be sure it has settled safely on the ground. Sometimes you'll have to cut limbs off the felled tree to complete the fall. Buck off the butt section if you think it's necessary **(4)**. Remove all broken limbs on adjoining trees, even if it means having to fell another tree.

There are probably as many different felling situations as there are trees standing. These are simply the basic considerations. Learn safe felling practices, or have a professional feller do the job for you.



1



3



2



4

Limbing

I usually cut the limbs off each tree before felling the next one. This makes it easier to clear the milling site. But reposition the bedding logs where necessary **(1)** before removing any supporting limbs. Remember that the limbs may be under tension and can kick back at you or at the sawbar, which in turn can kick back at you. Sometimes it is best to relieve stress by cutting the limb in half before cutting it off **(2)**.

Begin to limb from the top side of the tree **(3)**, being careful to keep a safe footing at all times. Overcut and undercut the limbs with the nose of the sawbar.

As you near the final stages of removing the supporting limbs, be ready to move away quickly, for the tree can roll, swing or drop. Plan your moves in advance. I try to imagine where I would land, and where I'd toss the running saw, if I should stumble and fall.

After limbing, trim off any irregularities that may interfere with milling **(4)**.



1

2



4

3

Bucking

Once you've limbed the tree, buck it into logs. Measure and mark out the tree to the desired log lengths with a tape **(1)**, allowing enough length for end trimming and squaring. I usually mark off log lengths by axing straight down, then axing in at an angle **(2)**. This produces a chip that often stays attached to the log—helpful when viewing the whole tree. When marking is complete, reposition bedding logs as necessary **(3)**.

If the tree to be bucked is on a hill, try to buck it from the uphill side. Bucked logs can roll or swing, which is dangerous if you're in the line of movement.

Bucking requires at least a basic understanding of sawing problems, of which the main one is a pinched sawbar. Beaver-tailing, or boring with the nose of the bar, is a good way to deal with pinching. As you feel a pinch happening, pull the saw out of the cut. Then bore into the cut repeatedly to remove the wood that is closing in on the kerf. Be careful not to let the chain touch the ground at this point. Continue bucking when the top of the log has closed completely.

A technique to avoid pinching and also splitting, which is another problem in log bucking, is underbucking **(4)**. Start at the underside of the log and cut with the top of the bar until you feel a pinch, or until a good portion of the cut is completed. Lift the saw with your legs, not your back. Underbucking causes the saw to push toward the operator, so I usually use only enough bar to get through the log. When you've completed the undercut, start in from the top **(5)**. Be prepared for the log to drop, and free your saw accordingly. If this log had not been underbucked, it would have split, because its end was not resting either on a bedding log or on the ground.


1


2



3



4

5

If your saw does get pinched in a log, wedge, jack, or saw it out or chop it out with an ax. Remove the engine from the bar for safety.

After bucking the logs, position them so they allow plenty of working space. If you place the logs with their straightest sides up, it will be easier to mill them later.

A peavey is handy for rolling or swinging logs **(1)**. Keep the peavey hook sharp enough for good log entry, but not so sharp that it will stick. Always pull with one leg in front of the other **(2)**. You can get a stronger pull with both feet together, but if the hook lets go or the handle breaks while you are in this position, you can easily hurt yourself. If the logs are too heavy to roll, the modified jack (p. 56) comes in handy **(3)**.

When the logs are in position, block each one to keep it from moving. Now is the ideal time to seal the log ends to retard checking. You can do this after the wood is milled and the lumber stacked, but I find it best to seal fresh-cut log ends, especially when milling high-grade lumber or working under very dry conditions. Lumber end-sealing wax is common to the milling industry. I use one manufactured by Mobil Oil Corp. (150 E. 42nd St., N.Y., N.Y. 10017), called Mobil-Cer M, which is sold in 55-gal. barrels. You could also use melted paraffin wax or house paint, but these aren't nearly as good.

1

2


3

Chapter 8

Equipment for the First Cut

Before you can begin to mill any lumber, you must establish a level surface on each log to guide the first cut. My system consists of a straight guide plank resting on end boards and pairs of leveled lag bolts placed along the length of the log (**1**). The guide plank should be at least as wide as a third the width of the cut to be made. The wider the plank, the more support for the mill. The plank should also be thick enough to support the weight of the mill with minimum help from the lag bolts. Guide-plank lengths will vary according to the lengths of the logs being milled, but I find that a 10-ft.-long, dressed 2x12 works in most situations and can be easily moved from site to site. The guide plank needn't be as long as the log being milled, because you can mill in stages by sliding the plank off the end board and along the lag bolts as you go.

1

To stiffen the plank and help keep it straight, and to allow the plank to slide along the lag bolts without damage, attach two 3/16-in., 1½″ x 1½″ angle irons to the plank edges, using countersunk screws about every 12 in. The inside edges of the angle irons should be in line with the outside edges of the plank **(1)**. To retard checking and warping, I treat the plank with linseed oil periodically. This also helps the mill to slide along the plank.

The guide plank is supported at both ends of the log by end boards. I usually make pairs of end boards from common, 2-in.-thick, dressed lumber. Heights of 4 in., 6 in., 8 in. and 10 in., cut to the width of the guide plank being used, cover most milling situations **(2)**. The maximum height of your end boards is determined by the maximum cutting height of your mill, less the thickness of the guide plank and angle iron. For example, the mill I use here has a maximum cutting height of 13 in., the guide plank is 1⅝ in. thick and the angle iron is 3/16 in. thick. Therefore, the tallest end board I could use would be a little over 11 in. Because I usually allow at least an inch of clearance for the bottom of the lag bolts that run along the length of the log, the tallest board I would use would be 10 in.

Drill holes for lag bolts or double-headed nails at a variety of positions on the bottom of the boards and file notches on the top of the face of each end board. Because the angle iron I use is 1½ in. wide, each notch must be inset 1½ in. from the end. These notches will aid you later, when you align the lag bolts to support the guide plank with a taut line of string. Set shortened, double-headed nails around which to wrap the string just below the notches.

It's best to use the shortest lag bolts possible to support the guide plank (and therefore the shortest possible end boards) because short lag bolts are more rigid and have less chance of binding as the plank slides over them for successive cuts.

Lag bolts are used for a number of purposes in milling, so I routinely stock about six to ten each of ⅜-in.-diameter lags in lengths of 3 in. through 10 in. at 1-in. increments. A supply of 2½-in. lags also comes in handy. I prefer ⅜-in.-diameter lags because they're easier to drive; ½-in. lags are sturdier, but much harder to drive unless holes are predrilled with a 7/16-in. drill. Applying bar soap, paraffin wax, or chain oil to the threads makes all lags easier to drive.



1



2

Index Lines

To make square lumber from a round log, you must first establish reference points from which to calculate your milling patterns. You can either mill to the heart center (pith) of a log or to average center **(1)**. On relatively straight logs, milling to the heart center will allow you to retrieve a larger percentage of straight-grained boards than milling to average center. On logs with excessive taper, where the heart center is way off average center and parallel to the taper, you'll be able to retrieve a larger volume of boards by milling to average center rather than to the heart. But the result will be that a great number of the boards will have cross grain (grain that deviates from the long axis of the board), and therefore will be of lower grade. Also, a log formed this way is liable to contain reaction wood, which shrinks and machines abnormally.

Measuring the top end of this log **(2)** shows that the heart center is just slightly off average center. This is true of the butt of the log as well. With this log, grade as well as volume are possible, and I'll mill to the heart center.

Mark out the index lines by drawing a short vertical line through the heart center at the butt and top of the log **(3)**, and then a short horizontal mark on each **(4)**.



2



3



4



Milling Patterns

On logs where heart center is close to average center, mill to heart center.

On logs with excessive taper, where the heart is parallel to the taper, mill to heart center for lesser volume of lumber, but longer, clearer boards.

Board milled to heart center has straight grain (A).

Board milled to average center cuts across fibers of tree, resulting in cross grain (B).

1

Working at the top of the log, draw level horizontal and vertical lines end to end through the indexed heart **(1)**. Establish the width and height of the cant, and center it on the index lines **(2)**. From this 12-in. cant I will mill 2x12s, which I will later resaw into 2x8s and 2x4s.

Now go to the butt end of the log. The butt often has irregularities such as flare, which may need to be removed to accommodate the mill. Mark out the flare, then draw horizontal and vertical index lines. With a level, draw straight lines across the area to be removed **(3)**. Mark out cant lines as you did on the top end of the log **(4)**, then remove the flare with either crosscutting or ripping chain **(5)**.


1


2



3



4



5

Now decide which end boards to use. The idea here is that the top edges of the end boards will establish a plane parallel to the heart center of the log. This means that the top edges of the boards you bolt to either end of the log must be the same distance above the horizontal index lines **(1)**. At the same time, you want to use the shortest possible end boards that will still allow room for the lags to be bolted into the log. End boards that are too long will interfere with the first cut.

First go to the butt end of the log and measure from its top surface down to the junction of the index lines. Add enough height so the angle iron on the guide plank will clear the log, then lock your tape at this total. The end board at this end must reach up to this measurement, with enough overlap to be bolted into place. So must the taller board you'll need at the top end of the log.

When you've figured out the board sizes you'll need, position the top end board, hammer-start one of the lag bolts and screw it in with the lag driver. Then level the board and screw in the second lag **(2)**. Install the butt board in the same way.

Before installing the lag bolts that support the guide plank, attach a string to one of the nails on either end board and pass it through the notch **(3)**. Wrap the string around the nails on the other board **(4)**, bring it home and wrap it around the last nail. Pull it tight and secure it with a few wraps and a couple of half hitches **(5)**.



2



4



3



5

Determining End Board Size

Distance A, measured from the intersection of the index lines on the butt end of the log to the top of the end board, must equal distance B, which is measured at the top end of the log in the same way.


Butt of log
Angle iron on guide plank clears log.
Top of log
A
B

1

Measure and mark the log for the supporting lag bolts. When using a 10-ft. guide plank, I usually place a pair of lags every 4 ft. To select lags of proper length, measure from the bottom of the strings to the marked positions on the log **(1)**, and then add on about 1½ in. for holding. Check the measurement in several places as the lengths required may vary. You may have to remove high spots on the log with a chainsaw or ax—drawing a string or measuring tape from one end of the log to the other will let you see any irregularities. Remember to make sure the lags don't go so deep that they're in the path of the cut.

Drive-start the bolts on the outside of the strings (no further than 1¼ in. away) at the marked positions **(2)**, then screw them in so that the tops of the boltheads are the same height as the bottom of the string **(3)**. Make sure the lags don't touch the strings. When all the bolts are in place, sight down the log to double-check alignment of the end boards, and remove the string.

Position the guide plank, looking under it to make sure the angle irons rest securely on the lags and end boards. You'll need an overhang of at least 12 in. to support the mill as it begins the cut, so pull the plank out **(4)**.

If you're milling with a winch, you'll need a weight to hold the guide rails of the mill flat on the plank. Make this from a block of log that is slightly larger in diameter than the space between the mill guide rails. You'll have to notch out the log for the mill handle **(5)**. Mark the notch with a crayon **(6)** and make a cut deep enough to give good handle clearance. Remove the wedge of wood with a second cut and, if you need it, a third **(7)**. Then test the fit of the weight on the mill **(8)**.



1



2



3



4

5

6

7



8

Changing the Bar

If you use one saw engine both for felling and lumbermaking, you will now need to remove the felling bar and crosscut chain. Before mounting the milling bar and mill, clean the cover plate and blade area of the saw engine with a stiff brush **(1)**. Then unscrew the chain-tension screw to full slack position **(2)**. Double-check for a clean oiler hole on the engine and the bar, and mount the bar and mill. Replace the chain-guide plate, making sure the tension stud is properly positioned. Tighten the bar nuts on the lubricated bolts with your fingers **(3)**.

Now for the chain. Chain often gets tangled into what seems like a hopeless mess when it is moved around. To roll the kinks out, hold the chain in both hands. Starting with the most serious kink **(4)**, roll the chain as shown **(5)**. Pull the two loops into the final loop, and you're ready to mount the chain on the bar **(6)**.

If you're not used to handling chain, it's a good idea to wear gloves because sharp cutters can seriously injure bare hands.


1


2


3



4



6



5

Chapter 9

The First Cut

Because all logs are shaped differently, the first cut must establish a level and flat working surface that will guide the rest of the milling. If the first cut is off, the other cuts will be off, too.

Determine how high to set the mill for the first cut by measuring from the top of the guide plank to the top cant mark on the vertical index line **(1)**. For this log, I'll set my mill at 11 in. Start the saw, and pump out an excess of chain oil **(2)**; remember to check the chain frequently for good lubrication.

Mount the mill on the guide plank. As you push the mill forward to begin the cut, press down firmly on its handle **(3)** to keep the guide rails level on the plank. Gently rev up the engine to full throttle as the saw starts to cut. Keep the thrust skids against the log and enter the cut with the nose end of the sawbar. Cut at full throttle until the back guide rail of the mill just passes the end board **(4)**. Drive in both end dogs **(5)**, spacing them as far apart as possible. But make sure not to pound the dogs so close to the edges of the cut that the top slab splits.



1



2



3

5



4

Now position the winch yoke. Center it on the butt end of the log so that the outside pulleys are 1 in. or 2 in. below the top cant mark on the vertical index line **(1)**. Mount the yoke with washered lag bolts.

Drive the winch dogs into the top of the end board **(2)**. It's sometimes best to predrill the end boards to keep the dogs from splitting the wood.

Thread one end of the winch rope through the double cheek block in the center of the winch and out to an end block **(3)**. Thread the other end of the rope through to the remaining cheek block. You can remove the winch handle so that as you pull the ropes through the yoke **(4)**, the winch will not vibrate off its mounting. If you don't want to bother doing this, just pull the ropes out a little more slowly.


1


2


3



4

When you're down at the mill end of the log, thread the outside rope around the spacer nuts and set its eye over the winch button **(1)**. Then put back the winch handle, if you removed it earlier, and winch this rope to a light but snug tension **(2)**.

Now slip one end of the bridle rope over the bridle button on the saw engine, and hook the other end of the bridle rope to the eye on the remote throttle attachment **(3)**. The length of the bridle rope should be about twice the distance between the bridle button and the throttle eye. Gently take up the slack in the winch rope **(4)**, and thread it through the bridle rope so that it will pull the throttle wide open before pulling the mill forward **(5)**. When you find the proper position, mark it with a piece of tape. Try various positions for a well-synchronized pull. As a guideline, the length of rope going to the bridle button should be shorter than the length of rope going to the throttle.


1


2


3


4


5

As various ropes knot differently, on ropes of unknown material I use a double sheet bend **(1)** for easy removal. On ropes I know, I usually use a single sheet bend with a loop **(2)**. I don't recommend using a metal hook instead of a knot, because the hook could whip back at you if the rope were to break.

The piece of tape that marks the position of the winch rope on the bridle rope will soon be pulled off. But the permanent kink the knot leaves in the rope will help you realign the next hookup for a synchronized pull **(3)**.



1

Sheet Bend



To tie a single sheet bend knot, make a bight (uncrossed loop) in the longer end of the bridle rope (1). Weave the winch rope through the eye, around the bight (2),



and back under itself (3). Snug the knot securely so that it won't slip when the rope is tensed (4).

2

3



When the winch is set up, start the saw engine and position the counterweight **(1)**. As you start cranking the winch **(2)**, the engine should open up to full throttle. (You shouldn't have to put heavy pressure on the winch handle.) You will soon learn to coordinate engine speed with winching speed. Check the tension of the winch lines occasionally—rope breakage can be dangerous, so watch out for it.

To keep the top slab from sagging and pinching the bar, stop milling and place kerf wedges on both sides of the cut as needed **(3)**. The number of wedges and their placement will depend upon the weight of the slab. Wedging can be done by your partner, if you have one, but make sure he or she keeps both hands far away from the chain. To stop milling, or if the saw sticks in the cut, turn the winch handle backward quickly for several rotations. This will stop the pull and allow the engine to return to idle.

Keep an eye on the guide rails of the mill to be sure they remain flat on the guide plank, and mill up to the last set of lag bolts **(4)**. Crank the winch backward quickly to stop milling, allow the engine to idle and then turn the engine off.



1



2



3

4



Remove the counterweight and winch, leaving the ropes attached to the engine. Pull the guide plank forward to the next cutting position **(1)**. In the last position, the plank should just cover the end board **(2)**. It's a good idea to check the lag bolts to make sure they haven't been bent. With this system you can cut any length of log, as long as you accurately set the end boards and lags.

Now set the winch dogs into the end of the guide plank **(3)**, replace the counterweight and continue milling, adding kerf wedges as necessary **(4)**. When the mill comes close to the end of the cut **(5)**, remove the counterweight, winch ropes and yoke **(6)**. A final set of kerf wedges will keep the top slab from dropping on the saw as the cut is completed **(7)**.


1


2


3


4


6


5


7

Pull the guide plank forward **(1)** to support the mill as it finishes the cut. Complete the cut by hand, keeping a firm downward as well as a forward pressure on the mill **(2)**. Reducing engine speed to idle as soon as the chain completes the cut lessens the chance of rounding over the edge, and of the chain scoring the board at the back of the bar. Stop the engine and set the mill aside. Remove kerf wedges and end dogs from the end of the log **(3)**.



1



2



3

You can mill a board or two off the top slab if you invert it in place on top of the log. Estimate the center of weight of the slab and drive a plastic felling wedge on either side **(1)**. (The weight center is usually not the measured center of a log.) Absolute balance is not necessary, but the closer you guess, the easier it will be to move the slab.

Swing the slab with a peavey **(2)** so that it crosses the log. Use a peavey or jack to flip the slab over **(3)**. Swing the slab in place **(4)**, then lift it to near level and block it with a wedge **(5)**. (You can split wedges from the undercut wedge taken from the tree during felling.) For extra stability, wedge up the opposite end of the slab a little.



1



2



3



4



5

When I inspected the cut, I realized that I had a problem. New, modified ripping chain makes a surface that is close to planed, yet both sides of this cut were extremely rough. (You can see this in photo 1 on p. 109.) In a situation like this, the first thing to do is check chain tension, as this is the usual cause of a rough cut. A newly installed chain sometimes has kinks that loosen after the chain runs a while. A properly tensioned chain is easy to move around the bar by hand; pull it back and forth to test. Properly tensioned chain can also be lifted from the bar with normal finger pressure. This chain required abnormal pressure, so I realized it was too tight **(1)**.

If you stop for chain adjustment, it's a good idea to check the drive links for a film of oil. An oily buildup of sawdust on the nose end of the bar **(2)** is a good sign of proper lubrication.

After the first cut is also a good time to check the saw engine for fuel and chain oil. But before doing this, wipe sawdust away from the filling caps with a rag or stiff brush. Chain oil shouldn't be used up before fuel, as this will cause excessive bar and chain wear.

Try not to run out of fuel or chain oil before you complete a cut, unless you can add them both from the upper side of the engine. Otherwise, you'll have to back the mill out of the cut to fill up. After a few cuts, you'll learn to gauge fuel and oil consumption.

Here I'm adjusting the mill to cut a 2-in. board off the inverted top slab **(3)**. Riser posts that are free of pitch and dust allow you to raise and lower the guide-rail assembly easily. Doubling-up on the toggle adjustment nuts **(4)** will ensure that the cut stays straight.



1



2

3

4

To begin the cut, position the adjustable entry guide rail in the center of the slab **(1)**. This rail supports the mill during exit and entry. Start cutting with the nose end of the bar, keeping the guide rails flat on the slab.

Set end dogs **(2)**, or if you feel the top slab will not curl up or twist, insert kerf wedges. Set up the winch **(3)**, lifting up on the winch handle as you drive or hand-press the front dog into the slab.



1

2

3

I don't normally use the winch yoke on shallow cuts. I attach the winch rope to the bridle rope at the engine end as when using the yoke, but attach the nose-end rope by slipping the loop over the riser post **(1)**.

Once the counterweight is in position, you can start milling, setting kerf wedges as necessary. Near the end of the cut, remove the counterweight and winch, and set the final wedges **(2)**. Complete the cut by swinging off or milling straight off—use whatever works best for you to keep the final stages of the cut straight **(3)**. Experiment with different handholds to find the most comfortable position **(4)**.

Now gently take off the slabbed board **(5)**. The top slab of the log makes a good base for stacking your wood as you continue to work. Place it on the ground, support logs or level timbers. For air-drying, I use 1-in.-square stickers, but sticker size depends on how fast you want the wood to dry. The larger the sticker, the more air that circulates, and the faster the wood dries. Swing the slabbed board onto the stickered top slab **(6)**.



1



2



3



4

5

6

2x12s

Now we'll mill 2x12s. Begin by adjusting the mill to cant width (12 in.). If you intend to resaw the 2x12s into 2x4s and 2x8s (p. 126), adjust the mill to cant width plus saw kerf (here ⅜ in.) **(1)**. Kerf width varies with types of chain and narrows as the chain is ground or filed back. Measure for kerf width just behind the sawbar when the saw is stopped in a cut.

Start to mill, setting the end dogs after the mill is well into the cut **(2)**. Set up the winch, mount the counterweight and continue milling **(3)**. If your mill has square guide rails, they will scrape away the sawdust, but if your mill has roller guide rails, you'll constantly have to sweep away the sawdust ahead of them. Otherwise, the rollers will ride up on the sawdust, resulting in an irregular cut.

Insert kerf wedges as necessary and continue milling to the end of the cut. Then remove the winch and, after inserting the final two kerf wedges, complete the cut by hand-milling, as before **(4)**. Check the cut for accuracy **(5)**.


1

2



3



2
3
4
5
6
7
8
9
10
11

5



4

Before attempting to stand the cant on edge, you may have to support it for more convenient milling by placing additional bedding logs underneath **(1)**. Turn the cant (p. 104), driving two felling wedges into the cut at the estimated weight center, then swinging the cant with a peavey **(2)**. Lift and swing the cant with the peavey **(3)** or a modified jack, then block the cant upright in a stable position, using small blocks and wedges **(4)**. Once again, the rough cut shows me the chain needs to be retensioned (p. 44). Here is another good tool for turning a cant **(5)**.

Now draw a string or tape from one end of the cant to the other, to check for high spots. Remove them with an ax or chainsaw, so that you'll be able to use the shortest possible lag bolts to support the guide plank.



1



2

3

4

Albert Myshrall

5

After the cant is turned, select and position the end boards (p. 84) **(1)**. Screw in one bolt, then square the board **(2)** and screw in the second bolt. Double-check to be certain you didn't disturb the square when screwing in the second bolt.

Attach the string to the end boards, pulling it taut. Mark and set lag bolts of proper length level to the bottom of the string, being careful not to select lags that will protrude into the milling area—the length of the longest lag bolt plus the thickness of the guide plank and angle iron must be less than the mill height setting. Sight down the lag bolts to double-check level, then remove the string.

Next, mount the guide plank on an end board and the lags **(3)**, checking that the plank is supported properly. Measure and mark the desired cut from the horizontal index line **(4)**, in this case, 6 in. Now measure from the top of the guide plank to that mark, and adjust your mill to this measurement. Measure and mark the other end of the log. This double-checks all previous calculations, shows the exit line of the saw and helps in positioning the winch yoke.



1



2



3



4

Start the cut with the guide rails flat on the plank and the thrust skid against the side of the cant **(1)**. Set the end dogs, mount the winch apparatus **(2)** and counterweight, and mill **(3,4)**.

When you're finished, turn the slab, swinging it across the cant, using felling wedges at the point of balance if necessary **(5)**. Roll the slab over and swing it back onto the cant. Block as necessary to steady for milling.

From this slab we will mill one 2" x12⅜" board. Adjust the mill for a 2-in. cut and move the entry guide rail to the center of the board to support the mill **(6)**. Mill by hand until the saw is well into the cut. Set kerf wedges instead of dogs if you feel the board won't curl up too much **(7)**. Then mount the counterweight and winch, and continue milling **(8)**.


1


2

3



4



6

5



7

8

Notice how the winch rope, when used without the yoke on shallow cuts, spools unevenly **(1)**. To overcome uneven spooling, I replaced the short bolts on the winch with long ones **(2)** to act as fairleads and help even out the spooling. Improvement of milling equipment is an ongoing event, and as you read this book, you'll probably find many ways to improve your equipment and the art of milling. This simple modification certainly solved my problem.

While we're on the subject, here is another winch refinement. An adjustable winch coupler, made of a short cord with knotted ends **(3)**, allows milling closer to the winch at the end of the cut. This can replace the former cross-over system (shown in photo 1). Wrap the coupler around the winch ropes a few times and tie it with a square knot **(4)** or three or four half-hitches. Then attach the winch rope to the riser post for a direct pull **(5)**.

When you're at the end of the cut, remove the winch and counterweight, insert final kerf wedges, and hand-mill out of the cut **(6)**.


1


2


3



4



5



6

Swing off the board **(1)**, and mill all usable lumber from the top slab **(2,3)**. Swing the boards onto a pile convenient for milling into 2x4s and 2x8s **(4)**. Continue sawing 2-in. boards for 2x12s or change the mill setting for boards of different thickness.

Eventually, the problem of the mill cutting too close to the bedding logs will arise. Solve this by elevating the cant with log supports. To make them, cut two log blocks and mark out a centerline on each. Then mark two parallel lines equidistant from the center line **(5)**. This is one of the times an extra chainsaw comes in handy, and its bar makes a convenient straightedge and width gauge. Using the marked lines as guides, saw out notches **(6)**. While you can do this freehand, you will probably get better results using lines.

1



2



3

4

5

6

Position the notched blocks beside the remainder of the cant **(1)**, and swing one end at a time **(2)**, lifting with your legs and not your back. If the cant is too heavy to move manually, use jacks or other equipment. Then you're ready to continue milling **(3)**. I find it easier to stack lumber by swinging each end, rather than lifting the whole board at one time **(4)**.

Readjust the mill to take a shallow last cut **(5)**. Very thin boards can be milled quite accurately, but be sure to allow extra thickness for final dressing.

Hand-milling is much less complicated than the winch system, but certainly more tedious. I often hand-mill short and narrow cuts, but find a day's work much easier with a winch.

Swing and stack the final board from the remainder of the cant. Now you have a fine pile of 2x12s **(6)**.

1



2

3

4

5



6

2x4s and 2x8s

If you want 2x4s and 2x8s, you can resaw your 2x12s. First measure the combined width of the boards to be resawn **(1)**. As you will be stacking these boards on edge, you will need a base at least as wide as the combined width of the boards. Use the widest slab **(2)** for a base, extending its width with crossboards if necessary.

Arrange narrow and bark-edged boards in the center of the stack **(3)** and complete the assembly with a heavy, clear-edged board on each side. Use the modified jack or other device to clamp the boards together securely **(4)**. Position the jack below the proposed cutting line (in this case, the cutting line is 4 in. from the top of the stack). Pound the board tops to level, if necessary, as you clamp the stack together **(5)**, then check with a square.

1



4

2

3

5

Now adjust the mill to a cutting height of 4 in. and position the entry guide rail so it will ride on a board in the center of the stack. Start resawing **(1)**. Insert kerf wedges when the mill is well into the cut **(2)**, and attach the winching apparatus and counterweight **(3)**. You won't need the yoke for shallow cuts.

After milling, double-check for accuracy. Notice how the ⅜-in. kerf allowance on the 2x12s lets you saw perfect 4-in. and 8-in. boards **(4)**. Restack the boards for air-drying, using stickers between them **(5)**. The remaining slab **(6)** makes a good weight.



1



2



3


4

5

6

Chapter 10

Box-Heart Timber

Begin to mill a 12x12 box-heart timber by drawing vertical and horizontal index lines through the heart center at the top and butt of the log **(1)**. Then center the timber on the index lines **(2,3)**. Select your end boards: The top measurement of this log was 2 in. less than the butt, so I selected a 6-in. board for the butt end and an 8-in. board for the top. The 6-in. board allowed adequate angle-iron clearance; the 8-in. board took up the 2-in. taper.

Install and level the end boards **(4)**, set the string and mark for the supporting lags. Check the length of the lags you select to make sure they won't be in the path of the first cut **(5)**. Install the bolts to string level, sight for alignment **(6)**, then remove the string.



1



2



3



4



5



6

Position the guide plank, checking to see that the angle irons rest securely on the end board and lag bolts. Set mill height **(1)**, then pull the guide plank out to start the cut and begin milling. Set the end dogs, mount the counterweight and winching unit **(2)**, and mill to the end of the guide plank, adding kerf wedges as necessary. Slide the plank to the next position and finish milling.

Remove the kerf wedges and end dogs and flip the slab to inspect the cut **(3)**. If you want to, you can make unedged lumber from this slab.


1


3


2

Now turn the log so that its straightest side is on top and the milled surface is approximately vertical **(1)**. Block the log to prevent it from rolling over. Set up this surface for milling, making sure that you bolt the end boards square to the slabbed side of the log **(2)**. Mill **(3,4,5,6,7)**, then remove the slab **(8)**.



1



2



3



4



5



6



7



8

For the third cut, adjust your mill to the bottom line. Hold the forward guide rail down firmly as you enter the cut for an accurate start **(1)**. Before you start a down and forward push, you can change your hand to a more comfortable position. Mill the cant **(2)**, adding kerf wedges as necessary. You can mill through support blocks as long as their actual point of support is below the cutting line **(3)**, but watch out in case the sawbar pinches or the log starts to roll.



1



2



3

When the cut is complete, pull the cant off the bottom slab and onto the bedding logs **(1)**, and move the bottom slab out of the way. Roll the cant barkside down and block it **(2)**. The mill setting remains the same for this next cut. Note the smooth cutting surface that results from sharp, properly tensioned ripping chain **(3)**.

When milling is done, roll the timber off the bottom slab. From this timber **(4)**, it is possible to make edge-grain (quartersawn) lumber by milling the timber into quarters along the index lines, then milling each quarter as shown **(5)**. But quartersawing like this isn't efficient, because to get a worthwhile amount of edge-grain lumber, you have to start with large logs. I prefer the system described in the next section.


1


2


3


4


Milling Quartersawn Lumber
1st cut
3rd cut
5th cut
6th cut
4th cut
2nd cut
5

Quartersawn Lumber

My quartersawing system requires an extra edging process, but yields the maximum amount of quartersawn lumber. Start by drawing vertical and horizontal index lines through the heart of the log at the top and butt **(1)**. Mount the end boards in the usual manner. If you are milling a short log and feel the guide plank will not sag between end boards, skip the supporting lags.

Now measure from the top of the guide plank to the center of the horizontal index line. Subtract half the width of the saw kerf from this measurement and set your mill to the new measurement. If you don't subtract half the kerf width, the saw will cut below the center of the line. Double-check that the mill is set correctly by measuring the distance from the center of the chain drive links or bar groove to the bottom of the guide rail **(2)**.

Slide the guide plank out for mill entry and begin the cut **(3)**. If you want to save the time it takes to mount the winch and its accessories, mill by hand. But if you do, you'll have to endure engine noise, exhaust and sawdust, as well as the strain of holding the mill down while moving it along. It's your choice.


1


3


2

When the first cut is completed, set an end dog on each end of the halved log, to one side of the vertical index line **(1)**. Roll the log over to the second cutting position, and block or wedge it securely in place **(2)**. Mount end boards square to the vertical line **(3)**, and install lags for support if necessary. Then mount the guide plank. Measure from the top of the plank to the center of the horizontal line and again subtract half the kerf width **(4)**. Adjust the mill, double-checking to make sure the measurement is correct. As you become experienced in making a good starting cut, you won't need to overhang the guide plank **(5)**.

You'll end up with quartered cants **(6)**. A true heart cut will give you the pith of the log **(7)**, which can be removed by edging with a homemade edger (pp. 180-182), bandsaw, table saw, Skilsaw or radial-arm saw.


1


2


3


1
2
3
4
5
6
7
8
9
10

4



5



6



7

Now set one of the cants aside, and block the other in position for milling **(1)**. Short, double-headed spikes **(2)**, driven along the edge of the cutting platform, keep the cant from moving. Adjust the mill to cut at the desired thickness and start to mill in a progression of alternate sides **(3)**.

Occasionally, you may have to mill the same side two or more times to increase the number of longer, edge-grain boards **(4)**. This is often necessary when the heart center of the log is well off average center.



1

2

Quartersawing

Wood is usually quartersawn in a progression of alternate sides, but sometimes milling the same side two or more times will result in a greater number of longer, edge-grain boards.


2nd cut
1st cut
3rd cut
4th cut
5th cut
6th cut

4



3

Slabsawn Lumber

One of the simplest forms of chainsaw lumbermaking is straight slabbing. The boards are left unedged and are easily stacked and stickered for air-drying. The yield is a full assortment of flat-grain and edge-grain cuts.

Proceed using the milling methods described in Chapter 9. When you've milled the top slab, remove it and position it flat side up as a base for stacking **(1)**. Place two or more stickers on the base **(2)**. I usually use 1-in.-square stickers, but it's a good idea to look into systems used by local sawmills and lumberyards.

Now mill the rest of the slabs **(3)**, allowing a little extra thickness on each for planing and sanding. A good stack of lumber and the satisfaction of a job well done are the results **(4)**.



1



2

3

4



SPECIALTY MILLING

STIHL

Chapter 11

Burls

The techniques I've just explained don't limit you to milling only standard lumber. With different end-board and guide-plank setups, you can easily mill lumber to special shapes and with exotic grain patterns. Milling burls, for example, is one of the most delightful and exciting lumbermaking experiences. Burls are abnormal outgrowths of trees, and the unusual wood found in them can be used dramatically in decorator slabs and furniture.

When you take a saw to a burl **(1)**, be especially cautious, for although burls can reveal real treasures, they are notorious for hiding rocks, sand and dirt—all hard on a chain. Take several sharp chains to your site to ensure a good day's productivity.

After bucking the burl to length, position it to a convenient height and stabilize it for milling. Measure its widest part **(2)** to make sure your mill can handle it.

In milling burls, as in milling logs, you need a flat top surface from which to mill the wood. For a guide plank, use any straight board that is at least a third the width of the burl and strong enough to support the mill. With an ax or a chainsaw, establish three points on the burl that will support the plank parallel to the cut you want to make **(3)**. Then tack the plank at those points with short nails **(4)**.

1



3



2



4



Measure from the top of the plank to various points along both sides of the burl to determine a cutting height out of the path of ingrown rocks **(1)**. Adjust the mill and begin cutting cautiously **(2)**, so as not to damage the chain severely if you strike a hidden rock. Insert kerf wedges as necessary. Remove the top slab **(3)** and pry it from the plank, removing the nails.

For the next cut, again examine the outside edges of the burl to determine a safe cutting level **(4)**. Don't forget to add in the thickness of the guide plank when setting mill height. Tack the plank to the burl and mill through the cut, using kerf wedges as needed **(5)**. Remove the slab from the plank. Notice the internal cavities that I've uncovered here **(6)**; these often house rocks and other abrasive materials.


1


2


3



4



6



5

Ovals

To mill oval slabs, I use a modified end-board system. I usually prop up the log securely with a notched support and then mount a short end board to level at the upper end of the log. At the lower end, I mount a longer board to level **(1)**. These boards support the guide plank—tack it to the short end board with a couple of small nails **(2)**, but leave the other end untacked to allow for mill exit.

Measure from the top of the plank to the desired cut to calculate the mill setting **(3)**, then make the first cut **(4,5,6)**.


1


2


1
2
3
4
5
6
7
LUFKIN
INCHES

3



4



5



6

Remove the milling accessories **(1)**. You now have a level surface from which to saw the remainder of the log. Adjust the mill to the desired height and make the next cut **(2)**. The entry guide rail of the mill is especially important here for support **(3)**; keep it flat on the slab for a straight cut. As you continue milling, you'll eventually have to block the log in a stable position **(4)**.

Here are the results **(5)**.



1



2



3



4



5

Natural Knees

Building wooden boats requires special types and cuts of wood that are often expensive and difficult, if not impossible, to find. Making my own boat lumber frees me from the frustration of endless prowls through lumberyards and adds another dimension to the boatbuilding process: a boat from a tree.

The Lunenberg dory is my true love. For the dory in this photograph **(1)**, which I modified from traditional East Coast design to meet my needs on the West Coast, I used the following materials:

- quartersawn red cedar for the lapstrake planking, thwarts and first bottom;
- yew for the natural-knee bow stem, stern, floor cleats and rub rails;
- flatsawn Douglas fir for the second bottom and second garboard strake;
- quartersawn Sitka spruce for oars;
- Douglas fir for the ribs (natural knees). The natural-knee ribs in this dory are much stronger than ribs made by joining.

Knees are usually found in heavy, spreading roots, but they may also be found in bent limbs, forked trunks and the curved butts of trees growing on the sides of hills **(2)**. The strength of a knee depends on the type of wood and its soundness. On logs having no bark or leaves, I use a single-bit ax to slice away a little wood to identify the species by sight and smell. A few thumps with an axhead help determine soundness. Knee wood should be free of pitch seams, rot and knots. Boatbuilding manuals and local boatbuilders can be a good source of information when you're deciding which trees in your area are right to use.

After bringing down your tree and bucking it to length, nail or bolt end boards at log top and butt **(3)**. For strong knees with minimal cross-grain, the tops of the end boards on both ends of the log should be the same distance from the heart center.

Kurt Samer

1


2


3

Now stretch a line across the tops of the end boards and drive a lag bolt or nail at the center of the curve, level with the bottom of the string **(1)**. Drive a second lag to the level of the first **(2)**, spacing the lags at a distance less than the width of the guide plank you'll be using. Then remove the string.

Lay the guide plank over the top of one end board and both lag bolts and measure the distance from the heart center of the log to the top of the guide plank **(3)**. Adjust the mill to this measurement, set its entry guide rail to the center of the plank and mill **(4)**. Knees milled to each side of the pith will be close to quartersawn, which are the best for boat ribs.

Mill until the saw is well into the cut, and set the end dogs. When you reach the center of the curve, slide the guide plank to the other end board **(5)**, insert the kerf wedges and continue milling. Insert another pair of kerf wedges before the saw completes the cut. Remove the guide plank and the end boards.



1



2



3



4



5

Now flip the top slab and inspect it for a usable knee **(1)**. Wedge or block the slab in a stable position **(2)** and adjust mill height to desired knee thickness. Start the cut and insert kerf wedges or set end dogs as necessary. Mill past the center of the curve and insert another pair of wedges **(3)**. Insert a final pair of wedges before completing the cut **(4)**. Repeat the process on the other slab for a second knee.


1


2


3

4

An alternative knee-milling system is especially useful on logs with sharp curves. Buck the selected log to length **(1)**, block it to a convenient height and draw a line through the heart centers on both of its ends **(2)**. Spike or bolt long end boards of equal height and width to the log. The tops of the boards should be higher than the top surface of the log; the bottoms should be placed on or equidistant from the heart lines **(3)**. Make sure the boards are level.

Mount a guide plank on the end boards. For box-heart natural knees, measure from the top of the guide plank to a point below the centerline that is half the thickness of the knee you want **(4)**. Set your mill to this measurement.

1



3

2

4

To start the cut, pass the mill over the guide plank and around the end board **(1)**. Start to mill, setting end dogs or kerf wedges as necessary **(2)**. Mill until you need to reposition the guide plank. Do this and complete the cut **(3)**. Remove the top slab and flip it, adjust the mill to the desired knee thickness and mill **(4,5)**.



1



2

3

4



5

Big Wood

In my opinion, most conventional forest harvesting techniques are detrimental to the forest and the land that supports our woods. Clear cutting and the use of heavy equipment often permanently alter existing ecosystems, whereas logging with a chainsaw, because it is a selective process, does not. With a chainsaw, the logger decides what to harvest—trees that are mature, damaged or crowding other trees. A tree is felled and milled where it falls. Only usable lumber is removed, leaving the byproducts to feed the land. And removing the milled lumber from the woods can be done with minimal disturbance.

Techniques for milling big wood **(1)** do not vary from those used to mill trees of average size. Procedures such as bucking, however, do require special consideration. A pinched bar in a big log can be extremely hard to free and the chances of a severely damaged bar and chain are high for the inexperienced bucker.

1

Safety is a major consideration. It is especially important to think about your posture and footing when working with big wood. In this photograph **(1)**, I am shown standing a little to the side of the saw—comfortable and well balanced. If the saw needs to be removed quickly or if the log should move, I am in a good position to react. Remember, if you have to move suddenly, keep the bar and chain away from your legs.

I position big logs using two modified jacks. Once the first jack is set at the maximum safe height, set the second jack **(2)**. Alternately set and remove the jacks until the log is the way you want it. A block, in front of the third workman's foot in this photo, is used to prevent the log from rolling back.

You can mill big wood efficiently with a 4-ft. mill, but mills this large should be either custom-built or modified as discussed on p. 38. Even so, large mills can be trouble. Because the riser posts are far apart, they give only minimal support to the sawbar and bar sag becomes a real problem. And it's also difficult to generate sufficient power when using a large mill. Using two saw engines on one mill isn't the answer as it's just about impossible to synchronize them.

When milling big wood, I usually use a modified, 4-ft. Alaskan mill coupled to a Stihl 090 engine with a double-headed Cannon bar **(3)**. The Granberg Helper Handle, which is attached to the bar end, gives your partner something to hold on to.

1

2



3

Recently I have had great success with a Stihl 090G (gear drive) saw, especially on logs over 2 ft. in diameter. The only problem was the loss of gear oil from the venting hole in the top of the gear case cover with the saw in the milling position. So I removed the cotter pin and tapped the vent hole to accommodate a 90° elbow and a short piece of copper tube stuffed with a foam fuel-filter element. Without this modification, you have to check the level of gear oil constantly to guard against a ruined gear case.

The guide-plank/end-board system discussed on pp. 76-78 works well with any size log **(1,2,3)**. Homemade, square-tube end dogs, bolted on with ⅜-in.-diameter lags (p. 54), secure the top slab here.

Although one-worker operations are possible, a team of two workers is best. With one worker on the winch and the other setting wedges, the mill is kept cutting and a day's production is greatly increased.

Plastic felling wedges are invaluable for moving heavy cants. This cant is over 10 in. thick, 3 ft. wide and 24 ft. long **(4)**. The wedge in the foreground was driven in to help start the cant sliding as it pivoted on two wedges at the weight center.


1


2

3

4

You can hold one end of the cant in place with a small hatchet **(1)** while you position the other end for lifting. Then, to keep the cant from sliding, replace the hatchet with a lag bolt. Begin to lift with a jack positioned at the weight center of the log **(2)**. Use a block under the jack to increase its height. Wedge the cant with a block of wood **(3)** before you complete the lift, and position the log with a jack. The slabbed log makes an ideal working surface.

How to stabilize this mass of wood? Bolt the cant to a nearby log, stump or tree with a small log, using washered lag bolts.

For production milling, it's a good idea to have a smaller mill and bar as a companion to the 4-ft. mill. This 2-ft. Mark III **(4)** is modified for bolting to the bar, has standard thrust skids and a winching button. If you use the same saw engine for both mills, make sure to couple each new chain to a new sprocket to prolong the life of the chain.

During the milling, log ramps assist in the safe movement of slabs from the cant **(5,6)**.


1


2


3



4

5

6

Quartering a Log

If you want to mill very large trees, you will have to quarter the log first. Do this either by splitting the log with steel wedges and wooden gluts, or by freehand ripping with a chainsaw.

The drawing **(1)** shows how to split a log. To begin, mark vertical and horizontal index lines through the heart center of the butt of the log. If you find a major check, draw the vertical index line through it and make the split there. If no check exists, start one by sledge-hammering a checking or steel splitting wedge at the top of the vertical line so that it just starts to split the log. Remove the wedge and position it so that its top corner is guided by and connected to the first check. Hammer it in until the wood just starts to split, remove it and continue the process until you get to the bottom of the line. Leave the wedge in position at the bottom of the log for the next stage of splitting. These shallow checks will help the log split accurately along the line.

Now start a steel splitting wedge in the top of the check. Add other wedges at short distances below it. Pound each wedge in a short way, then go back and pound each in farther, repeating the process until all the wedges are driven home and the log begins to split. Complete the split using wooden gluts. Start the first glut into the split on the top of the log. Use more between the steel wedges. Drive the gluts in gradually until the wedges loosen.

As the top of the log begins to split, start gluts into the log's length. Double up on the gluts to complete the split. Repeat the process to quarter the halves. Use a chainsaw to cut binding splinters or redirect an offline split.

Tools For Splitting Logs


Steel collar
Sides scooped for easy striking to remove wedge

Checking wedge **Three styles of steel splitting wedges** **Hardwood glut**

Splitting Sequence



Hammer in a checking wedge at the top of the vertical index line until the log just starts to split (1). Reposition the wedge so its top corner is in the bottom of the first check, and drive it in as before (2).

Continue the process until the wedge is at the bottom of the log. Leave the wedge in that position (3). Now pound a steel splitting wedge a short way into the top of the check, and start additional wedges below it (4).



Go back and pound each wedge in a little further, repeating the process until all wedges are home and the log begins to split (5). Drive a glut into the split in the top of the log, and pound gluts between the wedges in the log face (6). The checking wedge will fall out. Hammer the gluts in gradually, until the wedges loosen. As the log top begins to split, start gluts along the log's length (7). To complete the split, remove gluts and wedges in the log face, and double up on gluts in the log's length (8).

1

For milling, block up a quarter **(1)** with one split side level. Mount end boards and lag bolts to support the guide plank, and mill off the split side. Now roll the log so that the remaining split side is level, set the end boards square to the freshly milled surface and mill. Now you're ready to quartersaw or flatsaw the quarters.

On logs that don't split readily or accurately, or on logs that are curved or knotty, I use a chainsaw to cut down a chalked line running the length of the log between the tops of the vertical index lines. If the saw won't reach all the way through the log, you may have to roll it over to complete the cut, or use wedges and gluts to split the remaining wood.

This 52-ft. Sitka spruce log **(2)** was quartered, then quartersawn to be used in the box spar of a sailboat.

1



Milling a Quartered Log

Block up a quarter so one split side is level and set up end boards, supporting lags and the guide plank. Mill off a slab. Then roll the log and level the remaining split side. Set end boards square to the milled surface and flatsaw or quartersaw the log.

Supporting lags
End board
Blocking
Split side
Milled side
End board square to milled surface
Cutting line
Blocking

2



Albert Myshrall

Chapter 12

Homemade Edger

There aren't many types of specialty mills on the market today, so I've designed a few that can be built in the home shop. The vertical edger is handy for cutting to depth, circle cutting and edging boards. Make it from two pieces of 3″ x12″ channel iron and two pieces of 1½″ x2″ flatstock iron bolted together **(3)**.

The edger is mounted to an edging table (a slab of wood will do) that is nailed down securely **(1)**. Center a short, straight line just a little longer than the width of your sawbar across the table for a sawbar slot **(2)**. It's important to have ample room on both sides of the table to support the edger when it's mounted on the saw. Plunge-cut the slot with the nose of the bar **(4)**. Then mount the edger, clamping the bar between the sandpapered mounts **(5)**. Use the shortest bar you have that will handle the work. You can use either crosscutting or ripping chain, but for production milling, I recommend new modified ripping chain.

This setup is dangerous, so it's smart to use the adjustable, clamp-on safety guard shown in the drawing, even with a short bar. The guard is off in the following photos so you can see how the vertical edger is used.

1

2


Vertical Edger and Guard
Make ends of guard box from ¾" x 3½" boards of necessary length; screw them to side boards on opposite sides, front and back.
Nail ¾" x 2" x 4" clamping blocks through guard sides into clamping boards. Face blocks with cloth-backed sandpaper.
⅜" nut
6"
Make sides of guard box from ¾" x 6" boards of necessary length.
Bolt through 2" x 4" x 10" clamping boards using ⅜" bolts of necessary length. Use double nuts front and back.
Sawbar
1⅜" x 3" x 12" channel iron
½" nut
⅜" holes for bolting edger to underside of table
¼" bolt
Lock washer
½" bolt
⅜" x 1½" x 2" flatstock iron faced with cloth-backed sandpaper for gripping sawbar
½" flatstock washer

3



4



5

Lower the bar into the slot **(1)** until the edger rests squarely on the table. Bolt the edger to the table using four ⅜-in. lags **(2)**.

Now mount the edger table to a stump with the sawbar up **(3)**, using four washered lag bolts. I use this system for small jobs, removing the table from the stump for refueling. (A tankful of fuel will cut several hundred feet of lumber.) You could also attach the edger table to sawhorses for portability and to eliminate the need to dismount the saw for refueling.

To edge quartersawn boards, first measure for desired board width **(4)**. Then, for a fence, position a dressed guide plank the distance of that measurement away from the sawbar. Measure from the inside edge of a chain cutter on both sides of the bar to make sure the fence is straight **(5)**. Clamp or nail down the fence securely **(6)**.

Start the engine with the throttle locked in the starting position. This half-open setting is adequate for edging most lumber. Or you can use the remote throttle attachment used in winch-milling.

Edge the boards **(7)**, readjusting the fence as necessary. For slabsawn boards, I mark a cutting line with chalk and remove the first edge freehand, then proceed using the fence.


1


2



3



4



5



6



7

Precision Depth Cuts

This is a good way to make some of the cuts necessary in timber joinery. Begin by marking the line of cut **(1)**. Mount the edger so that the sawbar protrudes to the desired depth. Then measure the width of the edger **(2)**, and center it on the cut line **(3)**. Tack or clamp short guide boards along the marks **(4)**. Enter the cut with the bottom of the edger level on the top of the timber **(5)**, and exit the cut in the same way **(6)**.



1



2



3

4



6

5



Cutting Circles

With the homemade edger, you can accurately cut circles in lumber of any thickness. The only limitation is the size of your sawbar. A new (or near-new) crosscut chain works best for cutting circles of small diameter. Don't use old chain—the set of a chain recedes with wear, which results in less clearance for the bar in the cut.

To begin, cut a board the length of a radius of the circle you wish to cut, plus extra for a handle. Mark a line across the board for the saw slot **(1)** and bore it out **(2)** (be careful of saw kick-back as you do this). Clamp the edger to the sawbar, insert the bar through the slot and bolt the unit to the board **(3)**. Measure from the inside edge of a chain cutter and mark the desired radius in the center of the board **(4)**. Drive a spike through the board at that mark for a pivot **(5)**, and tack the spike into the center of the circle. Start the saw and enter the cut by pushing the handle end of the board **(6)**.

1



2



3



4



5



6

Complete the cut **(1)** and remove the spike. By adjusting the depth of the sawbar and resetting the radii, you can cut curved dadoes.

An electric chainsaw works well indoors for massive cuts that would otherwise be difficult to make **(2)**. One reason I designed this mill was to make a table big enough to sit at with a lot of my friends **(3)**, a table that could be danced on when the time was right.

1



3

2



2x4 Mill

An accurate and inexpensive mill **(1)** can be built from a dressed 2x4, two feet of ½-in. threaded rod, four ½-in. flat washers, six ½-in. nuts, and a few scraps of 2x2s and plywood for spacers. Use several thicknesses of plywood, such as ¼ in., ⅜ in., ½ in., ⅝ in. and ¾ in., so you can set cutting height accurately.

Drill two ½-in. holes in the bar of your chainsaw for mounting. Lock together two of the nuts on the bottom ends of the threaded rods. Drill two ½-in. holes in the 2x4 guide rail, using the bar holes as a template. You can substitute a dressed 2x6 or a wider board for the 2x4 if you wish.



2x4 Mill

½″ nut
½″ flat washer
½″ threaded rod
Guide rail, 2″ x4″ x22½″
Plywood spacer blocks
Spacer blocks made from 2x2s
Skid spacer block made from 2x4
Chamfered spacer block won't interfere with chain.
½″ holes drilled in sawbar
½″ flat washer
½″ nut

1

To mill a square timber with the 2x4 mill, first set up the end boards and guide plank. Determine mill height by measuring from the top of the guide plank to where you want to make the first cut **(1)**. Assemble the mill with the necessary number of spacers, positioning the skid block below the bar with a regular block to keep the chain from pinching the skid. Stack surplus spacers above the guide rail **(2)** and secure the assembly with a flat washer and nut. Double-check cutting height by measuring from the edge of an inside tooth to the bottom of the guide rail **(3)**.

Mill through the first cut, as described on pp. 90-100 **(4)**. For the second cut, lay the guide plank back on top of the slab. Because the 2x4 mill has only one guide rail, you need to use the plank with every cut to control the mill during exit and entry. Reassemble the mill to adjust for your depth of cut, positioning the skid block above the bar with a regular spacer block in between **(5)** so that the skid will ride against the log during milling. The blocks next to the bar should be chamfered on one side so they can't interfere with the chain. Double-check mill height after torquing down the top nuts, then mill, using end dogs and kerf wedges **(6)**.



1



2



3



4



5



6

Now set the cant on edge and install the end boards **(1)**. Adjust the mill to the correct height and mill through the third cut, then the final cut **(2)**. Here is the completed timber **(3)**.



1



2

3



Mini-Mill

Mini-mills, which are available through many chainsaw dealers, work with the saw in a vertical position. To use one, you need a guide plank made from a straight board and the 4-ft. aluminum track sections that come with the mill **(1)**. The mill does a reasonably good job of milling small logs, but I wouldn't recommend it for serious lumbermaking. It does do a nice job of edging **(2)** and, with an adjustable rip fence **(3)**, is useful for ripsawing to width **(4)**. A variety of freehand cuts **(5)** is also possible.

1

2

3

4



5

Angle Mill

I designed this mill to edge standard lumber, to mill angled lumber, and to make straight, angled and complex-angled precision depth cuts for timber joinery. You can make this mill from materials available from metal and machine-hardware supply houses **(1)**.

You'll need a hacksaw, a drill press with drills up to ½ in., a belt sander, ¼-in. and ⅜-in. taps, and an electric welder (though brazing can be substituted for welding if you prefer).



Angle Mill

Flatstock aluminum slide rail, ½" x4" x17"
Flatstock iron clamping pads, ⅜" x1½" x2", faced with sandpaper
¼" x1⅜" bolt
Square bar stock, ⅝" x⅝" x3"
½" nut
Angle head
9¾"
2¼"
1"
1"
8"
½" threaded rod
1" angle-adjustment nut
Plug-weld sawed-off 1" bolt inside square tube.
1" nut welded to bar stock
⅜" hole drilled through 1" bolt
⅜" lock washer
⅜" x1⅜" bolt
Square iron tubing, 1" x1" x9"
⅜" flat washer
⅜" x3¼" bolt
14"
1½"
½" nut
1¾"
¾"
Flatstock aluminum slide rails, ½" x4" x17"

To use the mill, mount the sawbar to the desired cutting depth, then cut two pieces of sandpaper twice the size of the clamping pads **(1)**. Fold the pieces and insert them between the pads and the bar to hold the bar in place. Secure the bar by tightening the bolts evenly on the angle head, taking care not to overtighten **(2)**. Tighten both angle-adjustment nuts **(3)** after positioning the bar to the angle you want. With this mill, a great number of inboard and outboard cutting positions are possible, as shown in the photographs **(4,5,6)**.



1



2



3



4



6



5

Timber Notches

The angle mill **(1)** lets you cut notches of all angles and depths from either side of a timber **(2,3)**. When cutting the sides of the notch, the outside slide rail acts as a fence against the edge of the timber **(4)**. Make sure the slide rails are always parallel to each other.



1



2



3

4



The last cut, which frees the notch wood, is made with the saw held vertically in the mill. Adjust the mill while holding one side of a square against the sawbar and the other side across the slide rails **(1)**. Loosen the angle-head bolts with a wrench **(2)**, adjust the saw to depth **(3)** and tighten the bolts. Mark the cut and the placement of the guide plank **(4)**. Double-check the plank before nailing or clamping it in place **(5)**.



1



2


3


5


4

Mill carefully **(1)**, pushing the mill forward smoothly and steadily. Keep both hands away from the chain. Be sure that the bar is completely out of the cut and the chain is stopped before you lift the mill off the guide plank.

You can mill from both sides of the guide plank if you make it a width that is suitable for multiple cuts **(2)**. For cuts like these **(3)**, and for most timber joinery, I use standard crosscutting chain.

1



2



3



Chapter 13

Once you start to make your own lumber, you begin to notice usable wood everywhere you go. For example, I found these logs **(1)** washed up on a beach in the middle of a large city. I know a man who built most of his house from discarded powerline poles, which yielded beautiful, dry fir and cedar boards. Don't overlook existing timbers and beams either—resawing them often yields surprising results. You're not restricted to milling only standing trees.

If you mill your own wood, you're not limited to working with the sizes and species available at the lumberyard. Gilbert Cook, of Alert Bay, B.C., makes sure he gets attractive grain patterns for his mandolins **(2)** by milling the spruce, maple and rosewood himself. (Using my system, Cook is also rebuilding a 65-ft. boat with milled lumber.) And although oversized timbers such as these **(3)** can be difficult to find commercially, they are easy to make with a chainsaw.

1

2

Albert Myshrall

3

This sailboat was built entirely from milled wood **(1)**. Milled cedar works well as decking and skirting for this hot tub **(2)**, which in turn works well for fishing.

Master gunstock maker Byrd Pearson **(3)**, of Provo, Utah, relies on wood with fine crotch grain for his gunstock blanks. Lumberers such as Scot Wineland **(4, center)** of Chico, Calif., are able to provide these special cuts using chainsaw-lumbermaking techniques. This piece of Claro walnut is only one example.

Dale Nish **(5)**, of Provo, Utah, turns his bowls from milled local woods that are almost impossible to buy: chestnut, apple, cottonwood and apricot, to name just a few.

Michael Hawks

1

2

3


4

5

Epilogue

The Haida Indian Band Museum **(1)**, in Skidegate, B.C., is housed in a building constructed totally of milled wood. George Dyson, of Ioco, B.C., planked the inside of his baidarka, *The Mount Fairweather,* with 40-ft. Sitka spruce that he milled himself **(2)**. It's incredible to look at, on and off the water **(3)**. And Alfie Collinson, also of Skidegate, B.C., uses milled yellow cedar slabs as the raw material for his sculptures **(4)**.

With a chainsaw, a few tools and imagination, the possibilities of lumbermaking are endless. What more can I say?

Albert Myshrall



1

Peter Thomas



2

George Dyson

3

Albert Myshrall

4

Editor: Laura Cehanowicz Tringali
Designer: Roger Barnes
Layout, Illustration, Cover Design: Lee Hochgraf Hov
Consultant: John Kelsey
Editorial Assistant: Deborah Cannarella
Manager of Production Services: Cindy Lee Nyitray
Production Coordinator: Mary Galpin
Typesetting: Nancy-Lou Knapp
Pasteup: Jean Zalkind Anderheggen,
Claudia Westerbeke Chapman,
Johnette Luxeder, Karen Pease

Typeface: Compugraphic Aster 10 point
Printer: R.R. Donnelley & Sons Co., Chicago, Ill.
Paper: Warren Patina, 70 lb., Neutral pH

Chainsaw Lumbermaking

If you've ever had trouble finding the lumber you need, or wanted to build something with your own trees, *Chainsaw Lumbermaking* is the book you've been waiting for.

Will Malloff tells you everything you need to know to turn a chainsaw into a lumbermill: how to modify the chainsaw and make numerous accessories for milling, how to use the equipment in the woods, and even how to cut burls, shape ovals and mill natural knees for boatbuilding.

Malloff's method is the fruit of more than thirty years of experience felling trees and making lumber. He's logged everything from giant redwoods to desert mesquite, and has fulfilled his youthful ambition to fell timber in every major forest of North America.

Drawing on this experience, he has invented several chainsaw mills, designed and patented ripping chain, and perfected the easy, efficient method of chainsaw lumbermaking he describes in this book.



A Fine Woodworking Book

ISBN 0-918804-12-4

MCRP 3-02C

Marine Combat Water Survival

U.S. Marine Corps

PCN 144 000069 00

To Our Readers

Changes: Readers of this publication are encouraged to submit suggestions and changes that will improve it. Recommendations may be sent directly to Commanding General, Marine Corps Combat Development Command, Doctrine Division (C 42), 3300 Russell Road, Suite 318A, Quantico, VA 22134-5021 or by fax to 703-784-2917 (DSN 278-2917) or by E-mail to **morgann@mccdc.usmc.mil**. Recommendations should include the following information:

- Location of change
  - Publication number and title
  - Current page number
  - Paragraph number (if applicable)
  - Line number
  - Figure or table number (if applicable)
- Nature of change
  - Add, delete
  - Proposed new text, preferably double-spaced and typewritten
- Justification and/or source of change

Additional copies: A printed copy of this publication may be obtained from Marine Corps Logistics Base, Albany, GA 31704-5001, by following the instructions in MCBul 5600, *Marine Corps Doctrinal Publications Status.* An electronic copy may be obtained from the Doctrine Division, MCCDC, world wide web home page which is found at the following universal reference locator: **http://www.doctrine.usmc.mil**.

Unless otherwise stated, whenever the masculine gender is used, both men and women are included.

DEPARTMENT OF THE NAVY
Headquarters United States Marine Corps
Washington, D.C. 20380-1775

6 January 2003

FOREWORD

Marine Corps Reference Publication (MCRP) 3-02C, *Marine Combat Water Survival*, provides Marine Corps combat water survival techniques, procedures, and training standards. This publication also teaches Marines to cross water obstacles and perform water rescues correctly and safely.

This publication is the foundation for teaching Marines correct water survival techniques and procedures that are used throughout the Marine combat water survival program (MCWSP). Once an individual or a unit has completed the MCWSP, this publication can be used as a refresher course before water operations.

MCRP 3-02C supersedes Fleet Marine Force Reference Publication (FMFRP) 0-13, *Marine Combat Water Survival*, dated 16 September 1991.

Reviewed and approved this date.

BY DIRECTION OF THE COMMANDANT OF THE MARINE CORPS

EDWARD HANLON, JR.
Lieutenant General, U.S. Marine Corps
Commanding General
Marine Corps Combat Development Command

Publication Control Number: 144 000069 00

MCRP 3-02C Marine Combat Water Survival

Table of Contents

Chapter 1. Survival at Sea

Abandoning Ship 1-2
  Jettisoning Equipment 1-2
  Abandoning Ship Technique 1-3
  Modified Abandoning Ship Technique 1-6
  Surface Burning Oil Swim 1-9
Surviving With a Pack 1-11
  Preparing Equipment 1-12
  Tying Waterproof/Plastic Bags 1-13
  Packing the Pack 1-13
  Swimming With the Pack 1-13
Staying Afloat With a Life Preserver 1-15
  Inherently Buoyant Life Preservers 1-15
  Inflatable Life Preservers 1-15
Staying Afloat Without a Life Preserver 1-18
  Floating With an Inflated Blouse 1-18
  Floating With Inflated Trousers 1-20
    Sling Method 1-20
    Splash Method 1-26
    Blow Method 1-32
Avoiding Heat Loss in Cold Water 1-36
  Individual Protection From the Cold 1-37
  Group Protection From the Cold 1-38
Drownproofing Methods 1-39
  Crawl Stroke 1-40
  T-Method 1-44
  The Sweep 1-46

Breast Stroke..1-48
Side Stroke...1-52
Elementary Backstroke...1-57

Chapter 2. Water Rescues

Reaching Rescue Techniques...2-2
  Reach 2-2
  Reach From a Deck 2-3
  Arm Extension...2-3
  Leg Extension..2-4
  Wading Assist 2-4
  Throw 2-5
Lifesaving Approaches 2-7
  Front Surface Approach 2-7
  Rear Approach..2-7
Approach Strokes...2-8
  Crawl Stroke Approach Stroke.......................................2-8
  Breast Stroke Approach Stroke 2-11
Level Offs 2-13
  Front Surface Approach 2-13
  Single Armpit Level Off 2-14
  Double Armpit Level Off..2-16
Rescue Techniques..2-18
  Wrist Tow 2-18
  Single Armpit Tow 2-19
  Double Armpit Tow..2-21
  Collar Tow 2-22
  Cross-Chest Carry 2-22
  Tired Swimmer's Assist 2-24
Defense Against a Drowning Victim 2-25
  Block...2-25
  Wrist-Grip Escape/Wrist-Grip Escape Alternative.......2-26

Front Head-Hold Escape 2-27
Rear Head-Hold Escape 2-29
Administering First Aid/Rescue Breathing 2-31

Chapter 3. Treatment of Casualties and Avoidance of Dangerous Marine Life

Drowning 3-1
Symptoms 3-1
Treatment 3-2
Hypothermia 3-2
Symptoms 3-4
Survival Time 3-4
Treatment 3-4
Heat-Related Injuries 3-6
Burns 3-7
Common Medical Problems Associated with Sea Survival 3-8
Seasickness 3-8
Saltwater Sores 3-8
Blindness/Headache 3-9
Constipation 3-9
Sunburn and Dehydration 3-9
Dangerous Marine Life 3-10
Sharks and Barracudas 3-11
Sea Snakes 3-12
Poisonous Fish 3-12
Turtles and Moray Eels 3-12
Corals 3-12
Jellyfish, Portuguese Man-of-War, Anemones, and Others 3-12
Spiny Fish, Urchins, Stingrays, and Cone Shells 3-13

Chapter 4. Negotiating Water Obstacles

Tides....................4-1
Surf....................4-2
  Plunging Waves....................4-3
  Spilling Waves....................4-4
  Surging Waves....................4-4
Currents....................4-4
  Offshore Currents....................4-4
  Rip Currents....................4-5
  Littoral Currents....................4-5
Back Bays....................4-6
Rivers and Canals....................4-6

Chapter 5. Fording Waterways

Selection of a Ford Site....................5-1
  Determine the Slope....................5-2
    Clinometer....................5-2
    Map....................5-3
    Line of Sight and Pace....................5-3
  Determine the Current Speed....................5-4
  Measure River Width....................5-5
  Calculate Downstream Drift....................5-6
The Buddy System....................5-7
Water Crossings....................5-8
  Care of Weapons....................5-8
  ISOMAT Raft....................5-9
  Poncho Raft....................5-10
  Construction of a Pack Raft....................5-12
  Single-Rope Bridge....................5-13
  High and Dry Crossings....................5-17

    - Swift Current Crossings 5-18
    - Slow Current Crossings 5-19
    - Removal 5-19

Appendix. Knot Tying

- Square Knot Appendix-1
- Bowline Appendix-2
- Hitches Appendix-2
    - Half Hitch Appendix-2
    - Two Half Hitches Appendix-3
    - Round Turn and Two Half Hitches Appendix-3
    - Butterfly Knot Appendix-4

Throughout history, water has posed special challenges to Marines and Sailors during times of both peace and war. Therefore, the inherent dangers associated with waterborne operations demand that Marines and Sailors receive proper water survival training. Combat units that are confident in their ability to work in and around water can use the water to their advantage in combat, and history is filled with examples of how the proper preparation or training for survival in water reduced or averted disaster.

USS *Indianapolis*
On Sunday, 29 July 29 1945, the heavy cruiser USS *Indianapolis* (the *Indy*) was en route to the Philippine Sea. Shortly before midnight (about 39 hours out of port), the *Indy*, running blacked out and unescorted, was rocked by two explosions on her starboard side. With communications smashed, the ship could not signal its distress and sank within 15 minutes.

Three life rafts and a floater net supported a few survivors, but the rest of the survivors drifted about, held up by rubber life belts or Mae Wests. About 60 seamen died the first night. Survivors assumed the ship would be reported overdue in Leyte, and that they would be rescued within 2 days. By Monday evening, however, panic began to set in as some life jackets lost their buoyancy from the long immersion. Some men even fought over life jackets, which resulted in at least 25 deaths. No one dared sleep for fear of losing his jacket.

Throughout the next several days, in-transit aircraft flew nearby without spotting the desperate seamen. As best they could, the men kept together, some tying long ropes to each other, floating like corks on a net.

Not until late Thursday morning, 3 1/2 days after the ship sank, were the men discovered. Luckily, a plane on a routine flight over the area spotted the survivors. When ships picked them up that night, the survivors learned they had never been reported overdue. Every one of the 1,196-man crew was a casualty; 880 crewmembers were listed as dead or missing. Although many lives were lost, the innovative and expedient use of flotation devices and float techniques employed by the survivors helped save hundreds of lives.

USS *America*

On Thanksgiving eve, 23 November 1995, the USS *America* made its way through the Arabian Sea. Twenty-year-old, Marine Lance Corporal (LCpl) Zachary Mayo was unable to sleep and, wanting some fresh air, made his way onto an open-air platform near the aircraft hangar bay, which was three levels below the sleeping quarters. While he was on the platform, the ship veered suddenly, throwing LCpl Mayo through the platform's protective bars and into the sea, 30 feet below.

Frantic, LCpl Mayo called out in vain to the watchmen on the flight deck, which was 64 feet above him. It soon became clear to him that the USS *America* would keep its course into the Gulf of Oman until his absence was discovered at morning muster. The LCpl took a moment to consider his situation. Since land was at least 100 miles away, swimming was suicide; he would have to stay afloat until a search party found him.

Using the techniques he had learned during combat water survival training, LCpl Mayo made a flotation device out of his coveralls and tried to relax. Meanwhile, business continued as usual aboard the USS *America*. Since LCpl Mayo was on special assignment with the hazardous materials division, his absence went unnoticed until a petty officer asked several Sailors if they had seen their shipmate recently. By the time a roll call had been completed, LCpl Mayo had been adrift at sea for over 24 hours. Although three, fixed-wing Viking aircraft were deployed to search for LCpl Mayo, most people aboard ship feared the worst.

After 34 hours at sea, LCpl Mayo was discovered by fishermen on a Pakistani fishing boat. LCpl Mayo’s survival is a testament not only to his incredible physical courage, but also to the soundness of the lifesaving training and techniques he received during combat water survival training.

Chapter 1
Survival at Sea

As a Marine, you face a variety of potential water emergencies whenever you cross expanses of water: ships, watercraft, and amphibious assault vehicles (AAVs) can sink; aircraft can crash into the sea; or you can accidentally fall into the water. However, there are some basic precautionary measures you can take to protect your safety and reduce your chances of becoming a water casualty. Determine the following information as soon as you board any type of vessel. Your knowing the following information may save your life or the life of your fellow shipmates.

- How many life preservers and lifeboats/rafts are on board?
- Where are the life preservers and lifeboats/rafts located?
- What type of unit survival equipment is on board?
- Are individual survival kits issued to each person on board?
- How much food, water, and medicine do the survival kits contain? When was the last time the contents were inspected for proper quantities and shelf life expiration?
- Is there sufficient survival equipment available for the number of personnel?
- How many other personnel are there on board, and where are they located?
- What are the egress procedures for the ship, boat, watercraft, AAV, or aircraft?

Abandoning Ship

When you embark on a Navy ship, you will receive abandoning ship instructions from Navy personnel. If given the order to abandon ship, report to your designated assembly area and put on a life preserver. DO NOT inflate the life preserver until you are clear of the ship. Torn life preservers will not inflate and inflated life preservers can block you, and those behind you, from exiting the ship. A flotation device that has been inflated may also burst if you jump from a significant height. See pages 1-15 through 1-35 for staying afloat with and without a life preserver.

DO NOT remove your clothing, boots, or shoes before abandoning ship. Your trousers and blouse may be the only flotation devices available if your life preserver is faulty or becomes damaged, and your clothes can provide some insulation from the cold water. However, remove your soft cover and place it in a cargo pocket for later use. The soft cover is both lightweight and a good protection against sunburn caused by the sun's rays reflecting off the water.

Jettisoning Equipment

Equipment should be kept properly packed and waterproofed in case you have to abandon ship. If entering the water from a height greater than 30 feet, wearing your equipment (e.g., pack, helmet, gas mask) could cause injury. Upon impact with the water, the helmet will "cup" air inside of it. The chin strap may also create a "hanging effect" as you submerge from the force of the fall. Therefore, you should remove your helmet and gas mask before abandoning ship.

If you are unable to maintain buoyancy due to the amount of equipment secured to your pack and body, then jettisoning some of your equipment may become necessary. Equipment that you should always retain includes canteens of freshwater, first aid kit, soft cover, and survival kit. The survival kit should include first aid items, water purification tablets or drops, fire starting equipment, signalling items (e.g., flashlight, strobe light, chemlights), food procurement items, and shelter items. Other items in a survival kit include sunburn lotion and lip balm, knife, goggles/sunglasses, plastic bag, matches and lighter, mirror. See Marine Corps Reference Publication (MCRP) 3-02F, *Survival*, for a detailed list of survival items and applications.

Abandoning Ship Technique

When abandoning ship, safety considerations must be observed. Use the following technique when abandoning ship without your combat gear:

Place your hands on their opposite shoulders, forming a criss-cross pattern.

Step to the edge of the ship's deck and check the water below for debris or survivors. If the water is clear, look straight ahead and prepare to jump. If the water is not clear, move to another location.

> NOTE: DO NOT hold your nose as you abandon ship. If you do hold your nose, the force of impact into the water could jar your arm and hand and cause you to break your nose.



Step off the side of the ship with a smooth, 30-inch stride. DO NOT DIVE OFF THE SHIP. DO NOT LOOK DOWN AT THE WATER. LOOK STRAIGHT AHEAD. Looking down at the water can render you unconscious or cause injuries upon impact.





Bring your trailing leg forward during the fall. Cross your trailing leg behind your leading leg.

Keep your head parallel to the water's surface until hitting the water.



You should remain in the abandon ship position until your descent into the water has almost stopped. However, the weight imbalances in your body may cause you to be in a "J" shape under the water

.



Once your downward motion has ceased, your feet may be parallel with the ocean bottom or you may be nearly inverted with your feet over your head. To counteract potential disorientation, you should pause briefly and allow the natural buoyancy of your torso to bring your body to a nearly upright position.

Floating debris can cause hazards. Therefore, you should swim upward, extending one arm (hand is shaped as a fist) upward to feel for obstructions. If you encounter debris, try to push it away or surface in a different location.



Swim away from the ship. DO NOT LOOK BACK AT THE SHIP. Looking back could slow your movement away from the area. Remember, your objective is to leave the area as quickly as possible because—

- Equipment and debris may be falling from or spilling out of the ship.
- Additional casualties can occur if individuals abandoning the ship fall on top of swimmers already in the water.
- Swimmers close to the sinking ship may get pulled underneath the water by the suctioning effect of the ship as it goes under.

Modified Abandoning Ship Technique

When abandoning ship while wearing full combat gear (weapon, helmet, and a properly waterproofed pack), safety considerations must be observed. The modified abandoning ship technique is used while wearing full combat gear and exiting from a height less than 30 feet.

WARNING

When exiting from a height greater than 30 feet, remove your helmet and pack. Fasten the helmet to the pack or place it inside the pack before jettisoning. If jettisoning gear from the ship or aircraft, check the water below for survivors before throwing the gear forward of the intended jump area. Once in the water, retrieve your gear and swim out of the area.

Place your weapon over one shoulder, muzzle down, with the weapon parallel to your side.

Place your arm and hand along the weapon and hold it to your side.

Take your free hand and place it on top of your helmet to prevent neck/spinal injury from the force of the water pulling upward on the helmet as your body enters the water.



NOTE: An alternate method is to place your weapon over one shoulder, muzzle down, with the weapon parallel to your side. Reach across your body and grasp the sling of your weapon and hold it to your body. Take your free hand and place it on top of your helmet.

Step to the edge of the platform and check the water below for debris and survivors. If the water is clear, look straight ahead and prepare to jump. If the water is not clear, move to another location.



Step off the side of the platform with a smooth, 30-inch stride. DO NOT DIVE OFF THE SHIP, DO NOT LOOK DOWN AT THE WATER, LOOK STRAIGHT AHEAD. Looking down at the water can render you unconscious or cause injury upon impact.

Bring your trailing leg forward during the fall. Cross your trailing leg behind your leading leg.

Keep your head parallel to the water's surface until hitting the water.

You should remain in the modified abandoning ship position until your descent into the water has almost stopped. The buoyancy of a properly waterproofed pack will immediately pull you to the surface. Once you break the water's surface, unsling your weapon and loop the sling over your head. You may have to seesaw the sling so as to ensure the sling passes between your helmet and pack. Once over your head, loop the sling around your neck with the weapon aligned in the center of your body, muzzle down. Lean back on your pack and perform the combat travel stroke to exit the area.

> NOTE: You may also remove the pack (unsnap the quick-release strap on one side of the pack, and pass the strap to your other hand in order to maintain contact with the pack, which is functioning as your flotation device). Remain horizontal in the water with your pack under your chest. Perform a breast stroke kick.

Surface Burning Oil Swim

After you have abandoned ship, rise to the surface using the techniques shown on the page 1-6. However, you must remember that fuel from sinking ships or downed aircraft will float on the surface of the water. Therefore, you must move clear of the floating fuel by swimming away from the ship or aircraft as soon as possible. Either swim upwind (into the wind) of the ship/aircraft or swim against the current. Either method allows you to move away from the fuel and the wind/current will push the fuel past you. To properly execute a surface burning oil swim—

Extend your arms overhead as far as possible.

Wave your arms back and forth vigorously to splash a hole while moving upward.

Splash as long as possible to push burning fuel away from the surfacing area.

Use your arms and hands to sweep away fuel and debris.

Kick your legs in a constant breast stroke kick.

Extend your arms (palms outward) forward on the surface, arms shoulder-width apart.

Pull your hands in and back toward the chest.



Stop your hands in front of your face and rotate them so that your palms face forward (roughly halfway out of the water).



Sweep your arms forward to a full extension at the shoulder width. This splashes debris, oil, or burning liquids aside. To reduce the chance of fatigue, use two short splashes to the front to extend the path.



Repeat the preceding step as necessary while swimming clear of the area.

Surviving With a Pack

If packed properly, your pack will float, and it is your key piece of equipment for staying afloat and overcoming water obstacles. If the pack's contents are properly waterproofed, it can support you (with a combat load) in the water. Buoyed up by a waterproofed pack, you eventually emerge from the water with all your equipment (e.g., boots, helmet, flak jacket, weapon, survival items).

Your pack floats based on a scientific principle known as Archimedes' principle. This principle states that an object submerged in a liquid is buoyed up by a force equal to the weight of the liquid displaced (pushed aside) by the object. If the weight of the displaced liquid is greater than the weight of the object, the object floats. If the weight of the displaced liquid is less than the weight of the object, the object sinks. For example, a machine gun sinks in the water, but it still weighs less in the water than it does on land. Even though a machine gun sinks, it is still buoyed up by a force equal to the weight of the water it displaces. For this reason, you should not try to hold yourself or your equipment any higher out of the water than they would naturally float; doing so wastes both energy and body heat.

Preparing Equipment

Before packing your pack, you must prepare your gear/equipment. Tape or pad all sharp edges and equipment corners. Ideally, your gear/equipment is placed in plastic bags and the plastic bag is then placed inside the standard-issued, rubberized, waterproof bag. Waterproof bags are not completely water tight; henceforth, the added protection of first wrapping the gear/equipment in a plastic bag, then placing the plastic bag inside the waterproof bag. Large plastic bags (e.g., trash bags) work well for bulky equipment (e.g., sleeping bags, field jackets, shelter halves, gas masks). Small plastic bags work best for small items (e.g., shaving gear).

> *NOTE:* If a gas mask must be carried outside the pack, cover it with a waterproof bag.

You will need the following items, which are available through the supply system, to prepare your equipment for packing:

- Waterproof bags:
    Pistol bag, plastic size #1 (8" x 18").
    Rifle bag, plastic size #2 (10" x 56").
    Machine gun bag, plastic size #3 (15" x 56").
    Multipurpose bag, cover, plastic size #4 (20" x 84").

- Panama work vest (life preserver).
- Small plastic bag, self sealing (6" x 6" and 12" x 12").
- Riggers tape, olive drab (2 1/2").
- Willie peter bag, waterproof clothing.

Tying Waterproof/Plastic Bags

Try to remove the excess air from the waterproof/plastic bag before securing the bag's opening. If filled with air, the bag can burst if pressed from the outside. Perform the following steps to tie a waterproof/plastic bag:



Packing the Pack

Place filled and tied bags inside the pack. Carefully handle sharp items (e.g., tent pegs, poles) to prevent puncturing the bag. Place items in the pack in order of expected use. Close the pack and its compartments. Attach sleeping mats or bags as high as possible on the outside of the pack.

Swimming With the Pack

A useful technique for propelling yourself forward while wearing a pack is the combat travel stroke. This technique allows you to float nearly horizontal and to propel yourself forward with bicycle-style kicks and breast stroke-style arm sweeps. To execute the combat travel stroke—

Body position
Keep the upper part of your body prone to the water, let your legs dangle horizontally, and keep your face up.



Arm action
Extend your hands out in front of your waist. Sweep your arms slightly downward and back 90 degrees to propel your body through the water. Move your hands back to the front of your waist. Repeat.

Leg action
Continuously move your legs in a bicycle-like movement, bringing your knees up high and step out.

Breathing
Keep your face out of the water during the stroke, and breathe freely.

Staying Afloat With a Life Preserver

The best form of flotation is to find any kind of floating object that will keep you and your equipment out of the water or minimize your exposure to the water. Life preservers are the best method, as they allow you to wear your clothes for heat retention and sunburn prevention. Marines use two basic classes of life preservers: inherently buoyant life preservers and inflatable life preservers.

Inherently Buoyant Life Preservers

Inherently buoyant life preservers are either vest-type (worn like a jacket) or yoke-type (worn around the neck). The preserver's outer envelope is either a cotton or water resistant material that encloses a removable fibrous glass or plastic foam filling.

In the Marine Corps, the most common type of inherently buoyant life preserver is the vest-type with collar, known as the kapock preserver. The kapock consists of collar straps, upper front chest straps, leg straps, and waist drawstrings that secure the preserver to you. The leg straps, which are fitted on both sides of the life preserver, ensure that the preserver remains around your chest while you are in the water. A chest strap is attached to the life preserver to facilitate lifting you out of the water. The strap can also be attached to other survivors or to lifeboats to reduce the fatigue that results from holding onto a floating/secured object by hand.

Inflatable Life Preservers

Marine Corps aircraft and AAVs have inflatable life preservers on board. The inflatable life preserver issued to Marines is known as the LPP (life preserver personal). The LPP is capable of both oral inflation and CO_2 cartridge inflation. The LPP consists of buoyancy chambers, CO_2 inflator, and an oral inflation tube. The buoyancy chamber is deck gray in color and is made from a neoprene-coated nylon fabric.

Inflatable life preservers must be stored in a cool, dry place. Heat, moisture, and light cause deterioration of the life preserver material. Do not stow CO_2 cylinders near steam lines or radiators. Heat can increase the pressure inside the cylinders causing them to explode. Avoid sharp edges in stowage. Sharp edges increase wear and tear on the life preservers and may also puncture inflatable buoyancy chambers.

> **CAUTION:** Do not inflate the life preserver until you are clear of the aircraft, ship, or vehicle. Torn life preservers will not inflate and inflated life preservers can block you, and those behind you, from exiting the aircraft, ship, or vehicle.

To don and adjust the LPP—

Remove the LPP from its storage container.

Fasten the belt fasteners in front with the pouch in the rear.



Adjust the belt to fit; secure any excess belt by mating the hook and pile tape.

Rotate the pouch to the front and re-adjust the belt if necessary.



Open the snap fasteners on the pouch and unfold the life preserver.

Place the deflated life preserver over your head.

Place the storage container into the pouch after donning the life preserver.

Lift the lower end of the life preserver out of the pouch.



Inflate the life preserver by pulling on the lanyard attached to the CO_2 inflation valve or by blowing on the end of the oral inflation valve.



Staying Afloat Without a Life Preserver

You may be in open water without any floating objects or a life preserver to help you survive. If so, uniform blouses and trousers can be made into expedient flotation devices.

Floating With an Inflated Blouse

It is possible to float by a bubble of air trapped in the shoulders of your blouse. The air rises to the back and shoulders of the blouse and supports you at the water's surface. An inflated blouse is also a temporary flotation device used by weaker swimmers while trying to remove their trousers. There is a primary and an alternate way to create a bubble of trapped air in a blouse—

Primary Method
Turn the collar inside the blouse to help create a seal.

Unbutton top button and pull collar around mouth and nose.

Take a deep breath and bend forward slightly at the waist. Exhale one-half to three-quarters of a breath into the blouse.

Grasp and twist the collar with one hand to create a seal, this prevents air from escaping out from the collar.

Use your free hand and feet to stroke and kick to the surface.

Gather and hold the blouse tightly at the collar and stomach level to prevent the blouse from losing air if it floats up too high.

Splash water on the blouse periodically to prevent the material from drying, dry material allows air to escape.

Repeat inflation as required.

Alternate Method
Turn the collar inside the blouse to help create a seal.

Unbutton the second button from the top.

Take a deep breath and bend forward slightly at the waist.

Place your mouth and nose inside the hole created by the open button and exhale one-half to three-quarters of a breath into the blouse.

Grasp material at the unbutton portion and pull downward.

Use your free hand and feet to stroke and kick to the surface.

Splash water on the blouse periodically to prevent the material from drying, dry material allows air to escape.

Repeat inflation as required.

Floating With Inflated Trousers

In warm water, trousers can be used as a primary expedient flotation device. However, in cold water, submerging your head to remove and inflate your trousers results in heat and energy losses that negate the benefit of using the trousers as a flotation device. Once your trousers are inflated, you float motionlessly as if wearing a life preserver. If needed, assume the heat escape lessening posture (known as the HELP position, see page 1-37) to slow heat loss. As trousers dry, air leaks out of the legs. To slow this process, occasionally splash water on the fabric. Reinflate trousers as needed.

Sling Method

The sling method works if you are a strong swimmer or naturally very buoyant. Take the following steps to inflate trousers using the sling method:

Take a deep breath, bend over, and remove your boots.

NOTE: Retain your boots. Tie the boot laces together and suspend the boots from your blouse or hang them around your neck so that they rest on your chest.



Remove your trousers. Button or zip the trouser's fly closed. This allows you to control airflow.



Tie the bottoms of the trouser legs in a square knot. (The appendix illustrates various knots.)

Ensure that the front (fly) of the trousers faces you.



Hold the trousers above the water's surface and behind your head. Grasp both sides of the waistband and open with both hands.



Kick strongly to stay on top of the water while slinging the trousers overhead in order to trap air into them.

Once the waistband is submerged in the water, air is trapped in the legs.



Hold and seal the waistband underwater.

Slip the inflated legs over your head. Hold the waistband in toward your chest, the fly facing your body. To prevent air from escaping from the trousers, seal the waistband by either folding it or twisting it.

Lie back and relax, resting the back of your neck against the knot.



Splash water on the trousers periodically to prevent the material from drying. Dry material allows air to escape.



To replenish air in the trousers, you will use a technique known as the scooping method. With one hand on the open waistband, extend the trousers in front of you just below the surface of the water and scoop air bubbles with your free hand into the open waistband until the trousers have sufficient air. Repeat as necessary.



Splash Method

The splash method is an alternative to the sling method. As with the sling method, you must kick strongly to remain at the surface. To inflate trousers using the splash method, perform the following:

Take a deep breath, bend over, and remove your boots.



NOTE: Retain your boots. Tie the boot laces together and suspend the boots from your blouse or hang them around your neck so that they rest on your chest.

Remove your trousers. Button or zip the trouser fly closed. This allows you to control airflow.



Tie the bottoms of the trouser legs in a square knot. (The appendix illustrates various knots.)



Ensure that the front (fly) of the trousers faces you.

Hold the trousers at the water's surface out in front of you by the waistband with the fly up.



Grasp the waistband at the surface with one hand. Insert your free hand into the waistband, palm down.

Flutter your hand rapidly to create bubbles. This sends a mixture of water and air bubbles into the trousers. The water passes through the fabric. The air remains trapped in the legs.



Hold and seal the waistband underwater.



Slip the inflated legs over your head. Hold the waistband in toward your chest, the fly facing your body. To prevent air from escaping from the trousers, seal the waistband by either folding it or twisting it.

Lie back and relax, resting the back of your neck against the knot.

Splash water on the trousers periodically to prevent the material from drying. Dry material allows air to escape.



To replenish air in the trousers, you will use a technique known as the scooping method. With one hand on the open waistband, extend the trousers in front of you just below the surface of the water and scoop air bubbles with your free hand into the open waistband until the trousers have sufficient air. Repeat as necessary.



Blow Method

The blow method is an alternative to the sling method. Use the blow method if you are a weak swimmer. Take the following steps to inflate trousers using the blow method:

Take a deep breath, bend over, and remove your boots.

NOTE: Retain your boots. Tie the boot laces together and suspend the boots from your blouse or hang them around your neck so that they rest on your chest.



Remove your trousers. Button or zip the trouser fly closed. This allows you to control airflow.



Tie the bottoms of the trouser legs in a square knot. (The appendix illustrates various knots.)



Ensure that the front (fly) of the trousers faces you.

Hold the trousers at the water's surface. Grasp both sides of the waistband and open with both hands.

Take a deep breath.

Drop 2 feet below the water's surface, pulling the waistband underwater.



Hold the waistband open with both hands and blow air into the trousers.



To fill the trousers with air, surface while keeping the waistband underwater, breathe in again, drop below the water's surface, and blow air into the trousers. Repeat these steps until the trousers are filled sufficiently. Once trousers are filled—

Hold the waistband underwater. Twist and pinch it off.

Slip the inflated legs over your head. Hold the waistband in toward your chest, the fly facing your body. To prevent air from escaping from the trousers, seal the waistband by either folding it or twisting it.

Lie back and relax, resting the back of your neck against the knot.



Splash water on the trousers periodically, to prevent the material from drying. Dry material allows air to escape.



To replenish air in the trousers, you will use a technique referred to as the scooping method. With one hand on the open waistband, extend the trousers in front of you just below the surface of the water and scoop air bubbles with your free hand into the open waistband until the trousers have sufficient air. Repeat as necessary.



Avoiding Heat Loss in Cold Water



The rate of heat exchange in the water is about 25 times greater than it is in air of the same temperature. When you are immersed in cold water, hypothermia occurs rapidly due to the decreased insulating quality of wet clothing and as a result of water displacing the layer of still air that normally surrounds the body. You also lose about 50 percent of your body heat through your head; therefore, keep your head out of the water. Other areas of high heat loss are the neck, the armpits/sides, and the groin.

In cold water, DO NOT SWIM TO STAY WARM. Swimming, even with a slow and steady stroke, produces a lot of heat that is lost in the water. The heat loss can produce hypothermia that slows body functions and can result in serious injury or death. Remaining motionless conserves body heat three times longer than swimming. SWIM only if you have a flotation device and the shoreline is visible.

Individual Protection From the Cold

If you are equipped with a life preserver, assume the heat escape lessening posture (known as the HELP position) to slow heat loss and to protect major blood vessels near the body's surface. These areas lack insulating fat and are vulnerable to the chilling effects of cold water. To assume the HELP position—

Tuck your chin down tightly to cover your throat.

Draw your legs up in a fetal position to protect the groin.

Place your arms across your chest, tuck your hands into your armpits.

Wear some type of head covering (e.g., stowed cover, towel, handkerchief) to lessen heat loss through the scalp if head covering is available.



Group Protection From the Cold



If three or more Marines are in the water and are equipped with life preservers, they should wedge tightly together and lock arms to form a circle known as a huddle position. This position protects vulnerable areas from heat loss.

A casualty who is suffering from the effects of the cold can be placed within the huddle to be surrounded by warmer water. If in the water for a prolonged period, it is recommended that everyone be rotated inside the huddle to maintain or re-warm each person's internal core temperature. If there are more than five Marines, they should make clusters of huddle positions.

Contact with other swimmers provides survival advantages—

Creates a larger target for search and rescue aircraft.

Provides additional warmth in cold water.

Improves morale.

Re-establishes the chain of command.

Reduces shock and panic.

Provides opportunities to administer first aid.

Supports exhausted Marines.

Drownproofing Methods

An object that floats on the surface has positive buoyancy. An object that floats a few feet beneath the surface has neutral buoyancy. An object that sinks has negative buoyancy. Most people have positive buoyancy and will float at the water's surface. To test your buoyancy—

Stand in water that is at your chest level or deeper.

Take a full breath.

Bend forward slowly.

Relax and wait.

If you have positive buoyancy, you will slowly rise to the surface. If you have neutral buoyancy, you will float a few feet beneath the surface. If you have negative buoyancy, you will sink. Regardless of whether you naturally float or sink, you can remain at the surface for extended periods without a life preserver if you exercise the appropriate drownproofing methods or survival strokes, which are based on your buoyancy.

Drownproofing methods consist of the T-method and the sweep. The breast stroke, side stroke, and elementary backstroke are the most common survival strokes. With any drownproofing method or survival stroke, remember the acronym **SAFE**:

SLOW EASY MOVEMENTS
Move slowly to conserve energy and minimize heat loss.

APPLY NATURAL BUOYANCY
Use natural buoyancy to support the body.

FULL LUNG INFLATION
Fill the lungs with each breath. Do not hold air in the cheeks.

EXTREME RELAXATION
Tight muscles are denser than relaxed ones and do not float as well.

Crawl Stroke

The crawl stroke, sometimes called the front crawl or free style, is the fastest stroke. To execute the crawl stroke—

Body position
Lie horizontal, on your stomach, in the water.

Look forward and downward at a 45 degree angle with the waterline between your eyebrows and hairline. Your head position is important as it assists in cutting a path through the



water. If your head is too high in the water, your lower body sinks significantly, making your stroke less efficient. If your head is too low in the water, water washes over your shoulders and neck, causing unnecessary drag.

Arm action
Arm action occurs in three phases: catch, propulsion, and recovery.

Fully extend one arm forward of your body, this positions your hand to catch the water in preparation for the propulsion phase.

To catch the water, bend your wrist (with your palm pointing outboard) and make an "S" shape (or inverted "S" shape) with your hand, ensuring that your hand does not cross the center of your body. Your left hand makes an "S" shape and your right hand makes an inverted "S" shape with your hand finishing at shoulder level.



Push with your hands in a rearward fashion toward your feet until your arm is fully extended along your side, keeping your hands close to your body.

To begin the recovery phase, bend your arm at the elbow and raise your hand out of the water. Your hand breaks the surface of the water and maintains a height of 2 to 3 inches above the water's surface.

With your hand and arm moving in a forward manner, bring your hand past your head until your arm is about three-quarters of the way extended. At this point, turn your hand with your palm outboard so as to allow your thumb and forefinger to enter the water first.

Once your hand enters the water, continue to push your arm forward until it is fully extended.

You are now prepared to catch the water again. These steps are performed in an alternating pattern: when one arm is catching and propelling, the other arm is recovering.

Leg action
Use a flutter kick to create the leg action for the crawl stroke. This kick is used for both propulsion and keeping the lower body horizontal with the water's surface. The flutter kick is an alternating leg action: one leg is kicking in a downward motion while the other leg is recovering to the surface to prepare for the next kick. The size of the kick ranges from 12 to 15 inches and depends on your height.



Maintain your legs in a semi-rigid manner.

Generate power for the kick from the hips.

Keep your feet loose at the ankles, they trail behind your legs and act as "flippers."

Execute the propulsion phase of this kick with a downward thrust of your leg.

Execute the recovery phase by pushing your leg back to the surface. This phase is complete when your foot reaches the surface.

Breathing

Breathe during the recovery phase of the arm action.

Roll your body and rotate your head to the side of your body where the arm recovery is occurring, this rolls the water away from your mouth. Keep your chin pushed back toward your shoulder.

Exhale while your face is still submerged and inhale when your face breaks the surface.

Breathe either bilaterally or rhythmically. To breathe rhythmically, breathe on the same side of your body every time your arm cycle occurs. Bilateral breathing requires you to breathe every one and a half arm cycles. To breathe bilaterally, breathe when your right arm is recovering, your face goes back in the water and the next time you breathe is when your left arm is starting its recovery three arm strokes later.



Bilateral breathing is the preferred method for breathing; it prevents the chance of hyperventilation and allows your body to maintain a lateral position in the direction you are swimming.

Coordination
This stroke uses constant arm and leg action.

T-Method

The T-method is a basic drownproofing method. This is the best survival technique if you have negative buoyancy. To execute the T-method—

With your face out of the water, take a deep breath and submerge your face in the water while holding your breath.



Float with your body in a horizontal position, arms extended from your side, and legs extended and joined.

Move your hands up to your armpits by tracing an imaginary line along your ribs.

Extend your arms outward (horizontal) to your sides, your body position resembles the letter "T."

Step out and forward with one leg and point your other leg to the rear, your knees should be slightly bent. Simultaneously, bring your arms down to your sides. Then bring your legs back together. You complete the steps by exhaling most of your air and preparing to surface your face to obtain another breath of air. Hold your head out of the water. Tilt your head back slightly. Breathe normally.



Once your breath is complete, move your hands up and down directly in front of your body. Do this two or three times to slow your descent into the water.

> NOTE: To avoid hyperventilating, hold your breath below the surface of the water for no more than 10 seconds.

The Sweep

The sweep works well if you have slight to excellent positive buoyancy. To execute the sweep—

> *Float face down in the water: bend 45 degrees at the waist, arms and legs dangling, head hanging down, relax all muscles.*



> *Spread your feet slowly to prepare for a single kick (one leg is forward and one leg is rearward).*
>
> *Cross your arms in front of your chest, palms outboard with the back of each hand touching the opposite ear.*
>
> *Exhale prior to raising your head for a breath.*



Bring your legs together and sweep your arms down and out until the arms are fully extended out to the sides. This raises your face above the water and allows you to catch a breath of air.

With your air supply replenished, return your face to the water and relax while sweeping your arms in a downward motion in front of your body to prevent/slow your descent. Do not hold your breath for more than 10 seconds. More than 10 seconds enhances your chances of shallow water black out and subsequent drowning.

Breast Stroke

Use this stroke to swim underwater, through oil or debris, and in rough seas. If you are a good swimmer and not wearing combat gear, the breast stroke is the best stroke for long-range swimming because it provides good visibility and allows you to conserve your energy and maintain a reasonable speed.

Body position
Lie prone in the water. Swim with your trunk and legs projecting back and down at an angle of 20 to 30 degrees.

Extend arms out in front (hands together [side by side]), and extend legs behind (toes pointed) to prevent drag.

Face downward, looking forward at a 45 degree angle to break the water and to prevent water from washing into the collar area causing drag.



This is known as a glide.

Arm action

Turn your palms outward and bend your arms slightly.



Sweep your arms sideward and slightly downward until your hands are opposite and slightly below your shoulders.



Rotate your head up, breathe once your mouth breaks the surface.



Bring your hands and arms up along your chest and thrust them forward until they are extended and ready to execute the next arm pull.





As the arms start their recovery into the glide, the head should rotate forward, resubmerging the face.



Leg action

Draw your heels toward your buttocks, establish a 45 degree bend in the knees.





Thrust your legs outward and rearward, then squeeze them together. The whipping action of the feet aids forward propulsion.



This is known as the breast stroke kick.



Breathing
Inhale during the arm pull and exhale through your mouth and nose during the finish of the breast stroke kick and glide.

Coordination
The stroke movement is in three counts:

Begin your arm pull. Near the finish of the pull, flex your knees and bring your heels toward your buttocks. The arm pull counteracts the resistance created by the knees.

As the arm pull is completed, thrust your hands forward, kick your legs outward and rearward, and squeeze them together.

Glide through the water for approximately 1 to 3 seconds or until your forward momentum decreases, then begin the next stroke.

Side Stroke

The side stroke is a survival stroke because you use both arms for buoyancy, with each arm creating a slight propulsion. The majority of your body's propulsion comes from your kick. To execute the side stroke—

Body position
Lie on your side with your lead (bottom) arm extended beyond (with a slight bend in your elbow) your head and in line with your body. Palm is down and your hand is submerged 6 to 8 inches.

Extend your trail (top) arm down the length of your body over your thigh.

Keep your legs straight and together, toes pointed rearward.

Keep your face out of the water, this allows for free breathing.



This is known as the glide.

Arm action
With your lead arm, pull your arm downward, while flexing at the elbow, until it is straight down from your shoulder.

Rotate your shoulder and pull your elbow into your side. This should put your lead hand at shoulder level. At the same time, turn your palm toward your face and thrust forward to your original, extended position.

Draw your right hand upward in front of your chest to shoulder level. Rotate your palm toward your feet, then push it downward in front of your body toward your feet to catch the water.



Push your trail hand backward to its original position on top of your thigh. (Your trail hand starts forward and meets your lead hand at your chest/shoulder.)

Leg action

To perform the scissor kick, the top leg always goes forward and the bottom leg always goes rearward. From the extended position, draw—or recover—your feet toward your buttocks until your legs are bent at a 45 degree angle at the knees and the hips are flexed at a 45 degree angle with the thighs.



Once the legs have completed their recovery and while maintaining a 45 degree bend in the knees, extend the legs fully into a "V" shape in order to catch the water for the propulsion phase.



Once the legs are separated and extended forward and rearward to the "V" position, sweep the legs together until the feet are together.



You are now in the glide position.





Breathing

As long as your face remains clear of the water, it is a free breathing stroke. However, it is recommended that you exhale then quickly inhale when the legs are sweeping back together in the scissor kick. This is when the body reaches its highest point in the water, thus clearing the face completely from the surface of the water making it the optimum time to breathe.

Coordination

Begin the stroke with the downward pull of your lead arm. At the same time, bring your trail arm upward and draw your knees up to begin the kick. Let the thrust of the lead arm, push of your trail arm, and the kick of your legs coincide in order to finish the glide position. Glide through the water for approximately 1 to 3 seconds or until your forward momentum decreases, then begin the next stroke.

Elementary Backstroke

The elementary backstroke is also an excellent survival stroke. It relieves the muscles that you use for other strokes, and it is the recommended stroke for weak swimmers or nonswimmers. To execute the elementary backstroke—

Body position
Start on your back.

Face up, chest up, and hips up, keeping an arch in your lower back with arms pressed to your sides and your legs extended and joined to prevent drag.



Arm action
Trace your hands up your sides to an area near your armpits then extend your arms out to the sides to form the letter "T" (palms facing feet), locking out the elbows.

> *NOTE:* Don't raise your arms above your head. This creates drag, changes your body position, and submerges the head.

Slap your palms to your thighs using a strong sweeping motion.



Leg action

Bend both legs at the knee (90 degree angle) slightly separating your knees and drawing your heels downward to a point under and outside your knees. The knees are spread as wide as the hips or slightly wider depending on the body type of the swimmer.

Circle around in a whipping action, ending with legs in a glide position.



Breathing

Breathe anytime during this stroke. However, it is recommended that you exhale then quickly inhale when your arms are sweeping back toward your sides and while your legs are sweeping back together. This is when the body reaches its highest point in the water, thus clearing the face completely from the surface of the water and making it the optimum time to breathe.



Coordination

The stroke movement occurs in three counts (recovery, catch, power).

Begin the arm pull (recovery).



Near the finish of the pull, flex your knees to a 90 degree angle. The arm pull counteracts the resistance created by the knees.

Kick out your legs, and squeeze them together as the arm pull is completed (catch, power).



Glide through the water for 1 to 3 seconds or until your forward momentum decreases, then begin the next stroke as your momentum slows.



Chapter 2
Water Rescues

A drowning victim can panic and react with unexpected violence and can seize and inadvertently drown a rescuer. Therefore, if possible, a water rescue should be executed from a distance. Reaching, wading, or throwing methods are used in a distance rescue.

If a victim is too far away to use these methods, a swimming rescue may be necessary. Remove all combat gear, when possible, before entering the water. Swim within 2 to 6 yards of the victim to maintain a margin of safety, this allows you to reassess the situation and reassure the victim. If the victim is unconscious, use the wrist tow method or cross-chest carry method to pull the person to safety. If the victim is struggling, use a rear approach and then execute either a single armpit level off or a double armpit level off before towing the victim to safety.

If the victim does begin to overpower you, there are techniques that allow you to defend yourself without having to abandon the rescue. These techniques include the block, the wrist-grip escape, the front head-hold escape, and the rear head-hold escape. These techniques allow you to separate yourself from the victim, reassess the situation, and then attempt the rescue again.

> *NOTE:* In this chapter's illustrations, the rescuer is shown without a helmet.

Reaching Rescue Techniques

Reach

From a safe position at the water's edge, reach out to the victim. Talk constantly to calm the victim. Retain partial contact with land or some solid support structure (e.g., pier, bridge). If the victim is close but still beyond reach, extend an object (e.g., stick; pack; rifle with magazine removed, chamber empty, and muzzle pointing toward victim) that the victim can grasp. Pull the victim slowly to safety. Once the victim is close to shore, remove the victim from the water.



Note: You can also extend a foot to the victim if you can retain a secure grip on a solid support structure.

Reach From a Deck

Reach from a deck rescue can be executed by either a swimmer or a nonswimmer, and it can be used on an active or a passive victim. Be sure to reassure the victim during the rescue. To execute reach from a deck—

> *Lie prone on the deck with your body firmly anchored. To anchor your body, lie flat, spread legs apart, and extend one arm behind you with your palm down and on the deck.*
>
> *Keep as much of your weight on the deck as possible and extend your free hand to the victim.*
>
> *Grasp the victim's wrist from above, your thumb and index finger are facing you. The victim should never be allowed to grab you and put your life at risk. Therefore, never reach across the victim to grab his wrist, always grab the wrist that is the closest to you.*
>
> *Keep your arm straight and locked out and pull the victim to the side of the deck. The victim should never be allowed to grab you and put your life at risk. Therefore, never pull the victim into you, always pull the victim into the side.*

Arm Extension

An arm extension rescue can be used if you cannot reach the victim using the reach from a deck rescue technique and you must enter the water. An arm extension rescue technique is used for a victim who is either active or passive. Once you determine that a reach from a deck rescue technique is not viable—

> *Reassure the victim and quickly ease into the water while holding onto the deck with one hand.*

> *Grasp the victim's wrist from above, your thumb and index finger are facing you. The victim should never be allowed to grab you and put your life at risk. Therefore, never reach across the victim to grab his wrist, always grab the wrist that is the closest to you.*
>
> *Keep your arm straight and locked out and pull the victim to your side. The victim should never be allowed to grab you and put your life at risk. Therefore, never pull the victim into you, always pull the victim into the side.*

Leg Extension

If the victim is beyond the reach of your arm, ensure that you have a firm grip on the deck, extend a leg to the victim and allow him to grab it, slowly bring the victim in closer until you can grab the victim's wrist that is holding onto your leg. Once you have a firm grasp on the victim's wrist, use the steps in the arm extension to pull the victim to safety. The leg extension rescue can only be used to rescue an active victim because the victim must be able to grab the rescuer's leg.

Wading Assist

Do not wade into water that is deeper than your chest. Talk constantly to calm the victim. If possible, do not touch the victim directly. Extend an object (e.g., stick; pack; rifle with magazine removed, chamber empty, and muzzle pointing toward victim) that the victim can grasp. Once the victim grasps the object, pull the victim slowly to safety.



Throw

If the victim is not within reach, use an expedient line to throw a lifesaving device to the victim. A lifesaving device can be any weighted item that floats (e.g., a canteen that is one fourth full of water). The lifesaving device must be secured to the end of the rope so that the rope will feed out from its coil when tossed. Talk constantly to calm the victim. Once the victim grasps the line or the lifesaving device, pull the victim toward you at a steady pace that keeps the victim's head above the water's surface. DO NOT pull so strongly that you break the victim's grip on the line. To prepare and use an expedient line and lifesaving device—

Tie a bowline at one end of the rope. (The appendix illustrates various types of knots.)

Unfasten the lid of a canteen.



Place the bowline around the neck of the canteen.

Refasten the lid so the canteen hangs from the bowline loop.

Place one end of the rope under the ball of your forward foot to secure it, either tie a knot at the end of the rope or tie an object at the end of the rope to create a block. Stand with your weight on the end of the rope. DO NOT tie the rope around your ankle.

Coil 20 to 30 yards of the rope, and hold it in a nonthrowing hand.

Place the canteen in your throwing hand.

Use an underhand throw to pitch the canteen and rope a short distance over the victim's head. Keep your nonthrowing hand open so the coil can unfold freely. The rope should trail across the victim's outstretched arms.



Retrieve the rope if the throw is inaccurate or the victim fails to grasp it. Recoil the rope as it is retrieved.

Divide the coil and throw again.

Lifesaving Approaches

Properly approaching the victim is as important as any other aspect of a rescue. Knowing the appropriate and safest method needed to approach a victim is critical in ensuring your safety and the victim's survival. Determining the victim's physical state (distressed swimmer, victim that is active and drowning, or victim that is passive and drowning) is crucial and will determine which type of approach you will execute.

Front Surface Approach

The front surface approach is typically performed when the victim is passive. You must remember that approaching the victim from the front is dangerous because a distressed swimmer or victim that is active can lunge toward you.

Rear Approach

If the victim is active, you must remember that his response can change rapidly. Therefore, approaching him from the front could be extremely dangerous. The victim could easily grab you and take you under the water during a state of panic. Therefore, use a rear approach when possible. When approaching a victim from the rear, reassure the victim until you get to within 2 to 6 yards of the victim; at that point, stop talking to the victim in order to maintain an element of surprise.

Approach Strokes

Before approaching a victim, you must evaluate the victim:

- Is the victim a distressed swimmer?
- Is the victim active and drowning?
- Is the victim passive and drowning?

Select your approach stroke based on your evaluation. Remember, the safety of the rescuer is paramount. Do not endanger yourself in an attempt to reach a drowning victim.

Crawl Stroke Approach Stroke

The crawl stroke (free style) is the fastest approach stroke. This stroke is used when the victim is passive and/or unconscious in the water. That is, the victim is face down, submerged or near the surface of the water, is not breathing, or is not moving. If any of these conditions exist, there is an obvious need to reach the victim as quickly as possible.

Execution of the crawl stroke approach stroke is the same as the crawl stroke (see pages 1-40 through 1-44), except that your head remains above the water's surface to allow for free breathing and maintaining eye contact with the victim.

Maintaining eye contact is critical. If the victim becomes submerged, you will have a better chance of locating him if you know his last location. Your distance from the victim will determine if your head remains out of the water the entire time you are executing the stroke. If you are 54 yards or less from the victim, you should maintain eye contact by keeping your head raised until you reach the victim. If you must swim more than 54 yards to reach the victim, make eye contact with the victim, place your face back in the water for four or five strokes, then raise your head again to regain eye contact with the victim (repeat these steps until you reach the victim).

Body position
The position of your body is horizontal to diagonal and influenced by the position of the head. This allows you to maintain eye contact with the victim.



Arm action
While one arm is forward of your head to catch the water for the propulsion phase, extend your other arm alongside your body in what is known as the recovery phase. The recovery phase ends when your arm is extended forward of your head to begin the propulsion phase. In the propulsion phase, your arms are approximately shoulder-width apart and the pulling action is slightly wider and deeper to compensate for your raised head.



Leg action
Kick one leg in a downward motion while your other leg is recovering to the surface to prepare for the next kick (this is known as a flutter kick). This kick is used for propulsion and maintaining the lower body as horizontal to the water's surface as possible. When your head is raised, your knees are slightly bent in order to keep your feet near the surface.



Breathing
If your face is above the water, breathe as needed (free breathing).

If traveling in excess of 54 yards to reach the victim, rotate your head to the right or left during the recovery phase and inhale when your face is out of the water or wait until your head is out of the water and facing forward while regaining sight of the victim.

Coordination
This stroke uses constant arm and leg action.

Breast Stroke Approach Stroke

The breast stroke approach stroke is used when a swimmer is distressed or a victim is active and drowning. This stroke is also used when the victim has a suspected spinal injury because it minimizes the wake created around the victim, minimizes the movement of the victim's head and neck, and helps prevent further injury.

If a victim is at a distance greater than 54 yards and if the swimmer is in distress or the victim is active and drowning in open water (ocean, lake), you should use the crawl stroke approach stroke to rapidly approach the victim, stopping approximately 11 yards from the victim in order to assess the situation.

Execution of the breast stroke approach stroke is the same as the breast stroke with a few minor deviations.

Body position
The position of your body is horizontal to diagonal and influenced by the position of the head. This allows you to maintain eye contact with the victim. It also allows you to communicate with the victim in order reassure him as you approach.



Arm action

Execute the arm action for the breast stroke, except that your arm pull is wider and deeper, which allows your head to remain above the water's surface.



Leg action
Execute the leg action for the breast stroke, except that your legs open wider during the propulsion phase of the stroke.

Breathing
Keep your face above the water and breathe as needed (free breathing).

Coordination
Coordination is the same as the breast stroke, except that there is no glide period. You constantly stroke until you reach the victim.

Level Offs

A properly performed level off positions the victim's face up and horizontal to the water's surface. There are three types of level offs: front surface approach, single armpit level off, and the double armpit level off. The single armpit level off and the double armpit level off are done by performing a rear approach, which is the preferred approach when a victim is active.

Front Surface Approach

The front surface approach is performed when the victim is passive. Approaching a victim from the front may place you in danger because a distressed swimmer or a victim who is active may lunge toward you. To execute a front surface approach—

Stop 2 to 4 yards from the victim to reassess the situation and reassure the victim.

Determine which arm to use in order to rotate the victim into a face-up position (your right hand on the victim's right wrist or your left hand on the victim's left wrist).

Move into position and prepare to grasp the victim.

Turn sideways and move toward the front of victim.

Once in position, reach forward and grab the victim's wrist. Your thumb is on the inside of the victim's wrist, as if you were checking his pulse with your thumb. Your remaining fingers wrap around the victim's wrist.

Lean back immediately and execute a powerful scissor kick or inverted scissor kick and perform short, vigorous pulls with your free arm.

As the victim begins to move forward in the water, kick, pull, and twist outboard on the victim's wrist. The momentum created from the kick and the pulling and twisting action of the victim's wrist will rotate the victim into a face-up and horizontal position in the water.

Extend and lock out your towing arm down the length of your body and execute a wrist tow to move the victim to safety.

Single Armpit Level Off

Approach the victim.

Stop 2 to 6 yards from the victim to reassess the situation, reassure the victim, and maintain your margin of safety.



Approach the victim slowly and grab his armpit with your hand (your right hand to victim's right armpit or your left hand to victim's left armpit). Position yourself sideways to the victim and place your elbow in the center of his back.

Pull with your hand that is in the victim's armpit while pushing with your elbow that is in the victim's back to place the victim horizontal on the water's surface (face up). To assist in placing the victim horizontally, use your free arm to execute short, vigorous pulls and use your legs to execute a scissor kick or inverted scissor kick.



Once the victim is horizontal and on the water's surface, begin forward momentum by extending your towing arm to a fully locked-out position and executing a single armpit tow.



Double Armpit Level Off

Approach the victim.

Stop 2 to 6 yards from the victim to reassess the situation, reassure the victim, and maintain your margin of safety.

Approach the victim slowly and grab his armpits with both your hands. Place your elbows on his back.

Pull with your hands that are in the victim's armpits while pushing with your



elbows that are in the victim's back and use an inverted breast stroke kick to place the victim horizontal on the water's surface (face up).


Direction
of Movement

Once the victim is horizontal and on the water's surface, begin rearward momentum by slowly extending your arms into a fully locked-out position and executing a double armpit tow and inverted breast stroke kick.


Direction
of Movement

Rescue Techniques

Wrist Tow

Use the wrist tow method to rescue a victim who is floating face down. DO NOT use the wrist tow on a struggling victim. If time allows, remove your helmet and gear before attempting the rescue. Swim toward the victim using a modified breast stroke. Swim within 2 to 6 yards of the victim to maintain a margin of safety, this allows you to reassess the situation and reassure the victim. The following steps show proper front surface approach, wrist tow procedures:

Approach the victim from the front and grasp the underside of the victim's left wrist with your left hand or the right wrist with your right hand. Ensure that your thumb is on the underside of victim's wrist.

Lean back, pulling and kicking strongly to move the victim into a horizontal position.



Twist the victim's wrist to rotate the victim into a face-up position.

Swim toward safety using the lifesaving stroke.

> NOTE: The lifesaving stroke is a modified side stroke wherein the top arm is used to tow or carry a victim to safety and use a scissor kick or an inverted scissor kick is used for propulsion.

Keep a firm grip on the victim's wrist.

Keep your towing arm fully extended and along your side. This keeps the victim in the water column and prevents drag.

Ensure the victim's head does not go under water during the recovery.

Single Armpit Tow

You perform the single armpit tow after a victim has been properly leveled off. The single armpit tow uses the lifesaving stroke. To execute the single armpit tow—

Place one hand (top arm) in the victim's armpit. Your towing arm is straight and along your side.



Use your lead arm (bottom arm) to execute short, vigorous pulls.

Execute a scissor or inverted scissor kick in a continuous and vigorous manner.

Use either free breathing or explosive breathing during the tow. During free breathing, keep your head above the water's surface and continuously reassure the victim. During







explosive breathing, put your head under the water to plane off your body's angle and reduce drag. Execute approximately two strokes, then lift your head up to breath and reassure the victim. Return your head back underwater for the next few strokes.

Double Armpit Tow

You perform the double armpit tow after a victim has been properly leveled off. To execute the double armpit tow—

Place both hands in the victim's armpits.

Extend both arms fully along your body. You are on your back, and your face is clear of the water.

Use free breathing.

Reassure the victim at all times.



Use the inverted breast stroke kick (it is the only kick that can be used due to your body position) to tow the victim to safety. (The inverted breast stroke kick is the same kick used in the elementary backstroke.) Your kick must be continuous and vigorous in order to keep the victim's face above the water.



Collar Tow

You perform the collar tow after a victim has been properly leveled off. To perform a collar tow using the victim's blouse—

Maintain control of the victim by grasping his armpit with one hand and then with your free hand grasp either his combat gear or his blouse between his shoulder blades. If grasping the blouse, grasp the material with your palm up, then turn your hand over to tighten the material.

Release the victim's armpit once control is established and execute the lifesaving stroke to tow the him to safety.

Cross-Chest Carry

Use the cross-chest carry to carry a victim to safety if the victim is struggling or when moving through heavy surf. Remove your helmet and gear before attempting a rescue. Talk constantly to calm the victim. Swim toward the victim using a breast stroke approach stroke. Swim within 2 to 6 yards of the victim to maintain a margin of safety, this allows you to reassess the situation and reassure the victim. The following steps illustrate proper cross-chest carry procedures:

> **CAUTION:** The cross-chest carry causes fatigue even if you are in excellent physical condition.

Use a level-off technique to place the victim in a horizontal, face-up position.

Retain a grip on the victim with one hand. Reach over the victim with your free hand to encircle the victim's chest. Place your free hand on the victim's opposite rib cage, just below his armpit.

Release your grip once you have a secure hold on the victim's chest.

Swim toward safety using the lifesaving stroke while keeping a firm grip on the victim's chest and your hip on his back.



This procedure brings the victim's face and shoulders clear of the water, and typically the victim stops struggling. Sometimes, however, the victim will struggle during the swim to safety. If this happens, either tighten your grip on the victim or defend yourself with one of the techniques discussed on pages 2-25 through 2-30.

Tired Swimmer's Assist

You must maintain a 2 to 6 yards margin of safety from the victim at all times while you are getting into position to perform the tired swimmer's assist. Once behind the victim, you extend one arm, hand straight. Place your straight hand underneath the victim's opposite armpit. Maintain a 45 degree angle away from the victim, your arm is locked out. Assist the victim in propulsion until both of you reach safety.



Defense Against a Drowning Victim

DO NOT sacrifice your life in an attempt to save the victim. A struggling drowning victim poses great danger to anyone nearby. Driven by panic, the victim can grab you with great strength in an effort to climb out of the water. This can result in death for both you and the victim. The following techniques can be used to defend against a drowning victim, but the best defense against attack by the victim is to stay out of reach.

Block

The block prevents the victim from grabbing you if you have approached from the front. If the victim lunges toward you, react as follows:

> *Place one or both open hands against the victim's upper chest; being careful to avoid the victim's face, neck, and abdomen.*



Lean backwards and submerge rapidly. Keep your blocking arm(s) extended.

Swim underwater and away from the victim, and return quickly to the surface.

Stop 2 to 6 yards from the victim to reassess the situation.

Determine an appropriate course of action.

Wrist-Grip Escape/Wrist-Grip Escape Alternative

The wrist-grip escape is used when a victim grabs your arm or wrist. Submerge the victim quickly by reaching across with your free hand, pushing down on the victim's shoulder to submerge him, and kicking to propel yourself upward. While keeping the victim submerged with your hand on his shoulder, give three hard jerking pulls with your trapped hand in an attempt to break free from his grasp. Once free, swim clear of the victim and reassess the victim's condition.



If the wrist-grip escape is unsuccessful in freeing your hand, use the wrist-grip escape alternative: use your free hand to grab your trapped fist, rotate thumbs up, apply bone-on-bone contact with the victim's arm, pry your hand out of his grasp, and quickly swim away from the victim.

Front Head-Hold Escape

The front head-hold escape allows you to escape when you are facing a victim who is gripping you around your head and neck. To execute the front-head hold escape—

Take a quick breath and tuck your chin into your shoulder to protect your throat.





Clap your hands above your head (three times) to submerge instantly. This drags the victim below the water, lifts his arms from around your neck, and, typically, he releases his grasp in order to get back to the surface. If he doesn't release his grasp, apply pressure to the victim's brachial pressure points (which are located inside of the upper arm, above the elbow).



Thrust the victim's arms up and away.

Keep your chin tucked to protect your throat, and swim underwater away from the victim and return quickly to the surface at the ready position.

Stop 2 to 6 yards from the victim to reassess the situation.

Determine an appropriate course of action.

Rear Head-Hold Escape

The rear head-hold escape allows you to escape when a victim is gripping your head and neck from the rear. To execute the rear head-hold escape—

Take a quick breath. and tuck your chin down, turn your head to either side, and raise your shoulders to protect your throat.



Take a strong stroke, clap your hands above your head (three times), and submerge instantly. This drags the victim below the water and, typically, he releases his grasp in order to get back to the surface. If he doesn't release his grasp, apply pressure to the victim's brachial pressure points (which are located inside of the upper arm, above the elbow).



Thrust the victim's arms up and away.

Twist your head and shoulders until free.



Swim underwater away from the victim and return quickly to the surface.

Stop 2 to 6 yards from the victim to assess the situation.

Determine an appropriate course of action.



Administering First Aid/Rescue Breathing

To administer first aid/rescue breathing, remove the unconscious victim from the water when possible and stop any bleeding.

First, open the airway and check for breathing. If the victim is not breathing, give two breaths of air. Check for a pulse. If there is a pulse but the victim is not breathing, continue rescue breathing. If there is no pulse, start cardiopulmonary resuscitation (CPR). For detailed information on administering CPR and rescue breathing, refer to American Red Cross CPR skill cards.

WARNING

If the victim has no pulse and is not breathing, administer CPR immediately. If the victim does have a pulse but is not breathing, give rescue breathing only. If the victim has a pulse and is breathing, DO NOT give CPR—CPR could prove fatal.

Next, protect any wounds from exposure, and treat for shock.

Chapter 3
Treatment of Casualties and Avoidance of Dangerous Marine Life

To survive in the water, you will face many challenges other than just being able to swim. For example, injuries and/or fatigue can lead to drowning and exposure to the elements can lead to hypothermia or heat injuries and may require medical attention. Finally, your presence in the water may be seen as a threat to or food source for a variety of marine life and you may be attacked. This chapter advises you on how to minimize these risks in order to stay alive.

Drowning

Drowning is suffocation by a liquid. A drowning victim inhales water into the lungs or the throat closes by reflex so that little or no water can enter the windpipe. In either case, a victim can no longer breathe.

Symptoms

One symptom of drowning is that the victim may call for help and has an expression of dread or panic. But typically a victim that is active and drowning may not call for help because he is trying to conserve his air and will not speak.

Another symptom of drowning is when the victim thrashes at the water's surface. If the victim stops or grows calmer, he has likely been overcome by fatigue, hypothermia, or a lack of air. At this stage, the victim usually has 20 to 60 seconds before going under the water's surface.

Treatment

If the victim is not breathing, begin rescue breathing. Place the victim on his back, tilt head back to open airway, pinch the nose, and give two full breaths. If the victim does not inhale during the first two breaths, reposition his head and attempt two more breaths. Check for a pulse. If a pulse is present, but the victim is still not breathing, continue rescue breathing. If a pulse is not present, begin CPR. See MCRP 3-02G, *First Aid*, for rescue breathing and CPR details.

WARNING

> If the victim has no pulse and is not breathing, administer CPR immediately. If the victim does have a pulse but is not breathing, give rescue breathing only. If the victim has a pulse and is breathing, DO NOT give CPR—CPR could prove fatal. Continue first aid until medical help arrives.

A victim who is not breathing and has no pulse may appear dead. DO NOT decide that death has occurred. Continue with the prescribed treatment. A corpsman or medical officer should decide whether the victim can or cannot be revived.

Hypothermia

Hypothermia is the abnormal lowering of the body's internal (or core) temperature to 95 degrees or below. It occurs when the body loses heat faster than it produces heat. A hypothermia victim loses the ability to move quickly, becomes mentally sluggish, slips into semiconsciousness, lapses into a coma, and dies when internal body temperatures drop too low.

The chilling effects of cold air, wind, or water can produce hypothermia. Water poses the greatest threat because it transfers heat 25 times faster than air. Depending on the water's temperature, a victim can succumb to hypothermia within a few minutes. The body's sudden contact with cold water can also set off a body reaction known as the mammalian diving reflex. This reflex can greatly increase survival time (especially for women and children) in or under cold water. The mammalian diving reflex shuts off blood circulation, except for the flow between the heart, lungs, and brain. The small amount of oxygen left in the blood and lungs is saved for the body's vital organs. This reflex has allowed people to survive being under cold water for an extended period of time. Therefore, a cold water drowning victim should be treated as if still alive even though the victim is not breathing, has no pulse, and may appear dead. DO NOT decide that death has occurred. Continue with the prescribed treatment. Victims of hypothermia can appear to be dead when they are not. A corpsman or medical officer should decide whether the victim can or cannot be revived.

WARNING

If the victim has no pulse and is not breathing, administer CPR immediately. If the victim does have a pulse but is not breathing, give rescue breathing only. If the victim has a pulse and is breathing, DO NOT give CPR—CPR could prove fatal. Continue first aid until medical help arrives. Check for a pulse for at least 45 seconds.

Symptoms

Once the body's core temperature drops, the victim will show one or more of the following symptoms:

- Violent and uncontrollable shivering as the body tries to warm itself.
- Slow or slurred speech.
- Disorientation or poor coordination.
- Loss of skin color.
- Blue and pinched lips.
- A slowing or stopping of shivering that progresses into a rigid torso and limbs.

Survival Time

A hypothermia victim's survival depends on the water's temperature and the time spent in the water. A small body build cools faster than a large build. Children cool faster than adults.

To increase your chance of survival in the water, utilize the HELP position described on page 1-37. Extra clothing and inactivity (remaining motionless in the water) can also increase your survival time.

Treatment

A hypothermia victim must be warmed to prevent further heat loss; therefore, treatment should begin as soon as possible. Consciousness of the victim determines the treatment that should be pursued. See MCRP 3-02G for specific treatment information. The following treatment procedures are recommended:

- If the victim is conscious, give the victim warm fluids. Give candy or sweetened foods to a victim who is able to eat.
- If the victim is unconscious, place him on his back with his head tilted back to ensure an open airway.
- DO NOT massage the victim. Massage can break blood vessels and create swelling, internal pressure, and blocked blood circulation.
- DO NOT give alcohol to the victim. Alcohol lowers the victim's body temperature.
- Shock is a possibility, treat accordingly.
- Seek medical help immediately.

If you are able to remove the victim from the water, apply the following steps when possible:

- Get the victim into shelter.
- Remove the victim's wet clothing.
- Put the victim in dry clothing.
- Place the victim in a sleeping bag if one is available. It may be necessary to place another Marine in the sleeping bag with the victim.
- Place as much insulation as possible between the victim and the ground.
- Use hot water bottles, electric blankets, or blankets heated in an oven or by a campfire to warm the victim's neck, groin, and the sides of the chest.

CAUTION: DO NOT apply heat to extremities.

Heat-Related Injuries

Heat-related injuries include heat cramps, heat exhaustion, and/or heat stroke. They can occur when a Marine—

- Is exposed to extreme heat, such as from the sun or a combination of high air temperatures and water temperatures.
- Does not wear proper clothing or gets overexposed to the sun.
- Becomes dehydrated.

With heat cramps, muscles may cramp in the arms, legs, and/or stomach. The victim may sweat excessively. To treat, create improvised shade for the victim and have him drink water.

With heat exhaustion, the victim sweats heavily; presents pale, moist, cool skin; and complains of a headache, weakness, dizziness, and/or loss of appetite. A victim may also experience heat cramps, nausea, vomiting, an urge to defecate, chills, rapid breathing, confusion, and a tingling sensation in the hands or feet. To treat, pour water over the victim and fan him to speed up the coolant effect of evaporation, have the victim drink freshwater, and attempt to provide shade.

With heat stroke, the victim stops sweating, which results in red, flushed, hot, dry skin. The victim may first experience headaches, dizziness, nausea, fast pulse and respiration, and/or seizures and mental confusion. The victim can become unconscious and die if not treated quickly. To treat, create improvised shade for the victim. Have him drink water and elevate both legs if possible.

Burns

Apply a field dressing (or the cleanest material available) to the burn. Give sips of water to a casualty who is conscious and not nauseated. When treating burn casualties—

- DO NOT remove clothing stuck to the burns.
- DO NOT break any blisters.
- DO NOT apply grease or ointments to the burns.

For electrical burns, check for both an entry and exit burn from the passage of electricity through the body. An exit burn may appear on any area of the body, not necessarily opposite the entry burn.

For burns caused by wet or dry chemicals, flush the burns with large amounts of water and cover with a dry dressing.

For burns caused by white phosphorus, flush the area with water, then cover with a wet material, dressing, or mud to exclude air and keep the white phosphorus particles from burning.

For laser burns, apply a field dressing.

Common Medical Problems Associated with Sea Survival

Seasickness

Seasickness is the nausea and vomiting caused by the bobbing motion created by the wave action of a flotation device. Seasickness can result in—

- Dehydration and exhaustion.
- A loss of the will to survive.
- Others becoming seasick.
- Unclean conditions.

To treat seasickness—

- Wash both the Marine and the flotation device to remove the sight and odor of vomit.
- Keep the Marine from eating food until the nausea is gone.
- Have the Marine lie down and rest.
- Give the Marine seasickness pills if available. If the Marine is unable to take them orally, the pills should be inserted rectally for absorption by the body.

Saltwater Sores

Saltwater sores occur when skin that has abrasions or is cut is exposed to saltwater. The sores may form scabs and pus. Do not open or drain. Flush the sores with freshwater, if available, and allow to dry. Apply antiseptic, if available.

Blindness/Headache

Irritants or the effects of the sun's rays reflecting off the water can cause temporary blindness or headaches. If flames, smoke, or other irritants get in your eyes, flush the eyes immediately with saltwater, then with freshwater, if available. Apply an ointment, if available. Bandage both eyes for 18 to 24 hours or longer if the damage is severe. If glare from the sky and water causes your eyes to become bloodshot and inflamed, bandage the eyes lightly. Try to prevent this problem by wearing sunglasses or goggles with a sunglass insert.

Constipation

This condition is a common problem associated with dehydration. For constipation, do not take a laxative if it is available; this causes further dehydration. Drink freshwater, if available.

Sunburn and Dehydration

The sun's rays reflect at all angles off the waves of the water; therefore, sunburn and dehydration are serious problems in sea survival. Try to prevent sunburn by—

- Erecting an improvised canopy, with available floating materials, to provide shade.
- Wearing your soft cover or using a cloth, such as a handkerchief, to cover your head.
- Covering your skin with sunscreen or lip balm from your first aid kit. Your lips, nostrils, eyelids, the backs of your ears, and the skin under your chin sunburns easily. If enough sunscreen cream is available, all exposed skin should be covered.

Dehydration is caused by the loss of the body's vital fluids. Dehydration in saltwater may result from a combination of factors such as a lack of water, the effects of saltwater on skin tissue, sunburn or vomiting from seasickness, and other causes. Sleep and rest and reduced water and food intake are the best ways of enduring periods of exposure. The following measures will delay the effects of dehydration:

- DO NOT drink saltwater.
- DO NOT drink urine.
- DO NOT drink alcohol.
- DO NOT smoke.
- DO NOT EAT unless water is available.

Dangerous Marine Life

You may see many types of marine life around you, and some are more dangerous than others. Generally, sharks are your greatest danger, followed by barracudas. However, most marine life will not deliberately attack a human. The most common injuries from marine life are wounds from bites, stings, or punctures. With the exception of sharks and barracudas, most injuries are a result of either trying to catch game or from contact abrasion with marine life. To treat an injury that results from a dangerous marine animal bite—

- Pack the wound with gauze and then apply a pressure bandage, if available.
- Treat for shock.
- Obtain medical attention as soon as possible.

For a more detailed information on the treatment of casualties and dangerous marine life, see MCRP 3-02F and MCRP 3-02G.

Sharks and Barracudas

Only about 20 percent of all shark species are known to attack people. Sharks have an acute sense of smell, and the smell of blood in the water will draw them to their prey. They are also very sensitive to any abnormal vibrations in the water; therefore, the sound caused by a struggling swimmer or underwater explosions will attract them.

Barracudas are bold and inquisitive fish. They have been known to attack men who are wearing shiny objects. Barracudas may charge at lights or shiny objects at night.

A group of swimmers can maintain a 360 degree watch while in the water. Therefore, to protect yourself from sharks and barracudas, stay with other swimmers. The group members can either frighten away or fight off sharks or barracudas better than one person can. Keep all your clothing on, including footwear. Historically, sharks attack unclothed individuals in groups first, mainly in the feet. Clothing also protects you against abrasions from a shark’s tough skin should the shark brush up against you. Avoid urinating heavily, let urine dissipate between discharges. If you must defecate, do so in small amounts and toss it as far away from the group as possible. Do the same if you must vomit.

If attacked, the use of firearms by swim sentries should be used with extreme caution because of the risk of injury to other swimmers. If unarmed or unable to make an improvised weapon, kick and strike the shark. Avoid using your bare hands to strike the shark, injury can result to your hands due to a shark’s tough skin. Target areas on a shark are the gills, eyes, and underbelly. Blows to the snout are also not recommended because a shark will tilt its head up and thrust its jaws forward when biting.

Sea Snakes

Sea snakes are venomous and sometimes found in mid-ocean. They are unlikely to bite unless provoked. Your best protective measure is to avoid them.

Poisonous Fish

Many reef fish are toxic, and can kill you if eaten. Generally, poisons are present in all parts of the fish, but especially concentrated in the liver, intestines, and eggs.

Turtles and Moray Eels

Turtles and moray eels normally inflict minor bite wounds. Treat this type of injury by cleaning the wound.

Corals

Coral, dead or alive, can inflict painful cuts. Clean all coral cuts thoroughly. DO NOT use iodine to disinfect any coral cuts. Some coral polyps feed on iodine and may grow inside the flesh.

Jellyfish, Portuguese Man-of-War, Anemones, and Others

This group of marine animals inflicts injury by stinging their victims with their tentacles. Contact with their tentacles produces burning pain, a rash, and small hemorrhages on the skin. Shock, muscular cramping, nausea, vomiting, and respiratory distress may also occur. Gently remove the clinging tentacles with a towel and wash or treat the area. Use diluted ammonia or alcohol and talcum powder to treat the injury if available.

Spiny Fish, Urchins, Stingrays, and Cone Shells

These animals inject their venom by puncturing the skin with their spines. General signs and symptoms include swelling, nausea, vomiting, generalized cramps, diarrhea, muscular paralysis, and shock. Deaths are rare. Treatment consists of soaking wounds in hot water, if available, to deactivate heat-sensitive toxins.

Chapter 4
Negotiating Water Obstacles

Marines face water obstacles in saltwater, freshwater, and brackish water (where freshwater and saltwater meet). These water environments differ considerably and pose distinct problems for Marine tactical units and swimmers. Saltwater obstacles include tides, surfs, and currents. Brackish water obstacles include back bays. Freshwater obstacles include rivers and canals.

Tides

Tides are periodic changes in the surface levels of oceans, bays, gulfs, inlets, and rivers. The Moon's and Sun's gravitational pulls cause tides. Depending on the situation, tides can either help or hinder Marines in their endeavors to conduct amphibious or riverine operations. Tides can provide sufficient depths to allow for the passage of landing craft or boats over reefs, trees, and other underwater obstructions. On the other hand, tides can render a river fording site unusable to tactical vehicles. Direction, level of change, and amount of change determine tidal nomenclature.

Tides that show change in direction are flood tides and ebb tides. Rising tides are known as flood tides. Falling tides are known as ebb tides.

Tides that show extreme levels of change are high tides and low tides. High tide is the period when water is at its greatest depth. Low tide is the period when water is at its most shallow depth.

Tides that show the least and most amount of change are neap tides and spring tides, respectively. Neap tides have the least amount of change in water levels between high and low tide. Neap tides occur at the half moon, when the Sun and the Moon are aligned at a 90-degree angle with the Earth. In this position, the Sun's and Moon's gravitational pulls offset each other. Spring tides have the highest floods and lowest ebbs. Spring tides occur at or shortly after the new moon or full moon when the Sun, Moon, and Earth are approximately in line. In this position, the Sun's and Moon's gravitational pulls are combined.

Surf

Waves break upon entering shallow water and create surf. The offshore area where waves break is the surf zone, which can present many hazards. Breaking waves often trap air bubbles and create a foamy appearance. Bubbles lower the water's density and decrease buoyancy. Move through foamy surf as quickly as possible. The type of wave determines your survival technique.

Wave action moves you toward shore. Lie on your back or side with your head pointing in the direction of the beach and your feet pointing into the waves.



As one wave approaches the beach, another drains away; relax and do not swim against the draining water. When a new wave is within about 3 yards, start swimming toward shore. Continue to swim until the wave lifts you and moves you toward the beach. Once the wave loses forward momentum, relax and repeat the cycle. If nearing rocks, turn your body and approach feet first to reduce the chance of striking your head and arms.

Plunging Waves

A plunging wave is a breaker whose crest curls forward and falls ahead of its base. Because of its power and underwater turbulence, a plunging wave poses the greatest surf threat. If caught in a plunging wave, you can be pulled underwater and pitched about violently. This can cause you to panic, which can increase your chance of drowning. Perform the following steps to escape a plunging wave:

Tuck into a ball with your head against your knees and your forearms locked around your legs, just below the knees.



Relax in this position until the turbulence subsides and you float to the surface. This can take 30 seconds or more.

Swim toward shore.

> *NOTE:* If threatened by another plunging wave, dive underwater into the wave.

Spilling Waves

A spilling wave does not break. Instead, its crest slides forward without curling. A spilling wave creates less turbulence and poses less of a threat than a plunging wave. If caught in a spilling wave, relax and let the wave carry you to shore.

Surging Waves

A surging wave occurs on a beach with a steep underwater gradient. It never really breaks, but the crest rises while the base slides up the beach with great force and speed. Once the wave reaches its highest point on the beach, it rushes back as quickly as it surged forward. If you are standing on the bottom when a surging wave advances or retreats, the wave can knock you off your feet and pull you into the surf zone. Do not try to stand or walk on the bottom. Swim toward the beach as soon as possible.

Currents

Offshore Currents

An offshore current occurs outside the surf zone. Typically, it occurs at bay entrances, in island channels, and between islands and the mainland. An offshore current flows parallel to or away from shore. If the offshore current is created by tides, its current strength and direction vary at different times of the day.

If caught in an offshore current, you may be carried in a direction you do not want to go. DO NOT try to swim directly to safety. If the current is moving directly away from the shore, relax and wait until the current dies out or turns toward land. Once the current subsides, use any survival stroke to swim toward shore. If the current is moving parallel to shore, use any stroke to move at an angle across the current and toward shore.

Rip Currents

A rip current occurs when waves pile water against the shore faster than the water can drain. The water flows rapidly along the beach until it is deflected seaward by a bottom obstruction. Then the rip current flows through the surf zone and into open water at a speed of up to 2 knots. This action can cut deep trenches in the sand. A rip current dies out once it reaches open water (usually within a few hundred yards of the shore).

A rip current can pull you out to the open sea. If caught in a rip current, DO NOT try to swim against the current. A rip current moves faster than most people swim, and it is impossible to swim to shore once caught in it. Relax and stay afloat until the current runs out. Once the current subsides, use a survival stroke to move parallel to the shore until you are out of the current, then begin swimming toward shore.

Littoral Currents

A littoral current occurs when a wave breaks against a beach at an angle. This current flows parallel to the shoreline and does not pose a great threat. If caught in a littoral current, use the combat travel stroke to swim across it at an oblique angle.

Back Bays

Once on the beach, you often face one or more rows of low hills called dunes. Behind the dunes, you may encounter a low-lying stretch of ground thickly covered with scrub trees and bushes. This area gives way to wetlands known as back bays. Back bays consist of muddy islands that are almost submerged during flood tides and separated by channels of brackish water of varying depths. Channel bottoms usually contain soft mud. Back bays pose major obstacles to vehicular traffic.

Infantry can cross back bays, but only with great effort. If crossing back bays by foot, consult detailed navigation charts and use the following guidelines to plan your route:

- Avoid water less than waist deep; walking in shallow water or soft mud is extremely tiring.
- Avoid back bay islands; these low-lying islands are usually too muddy to support foot traffic.
- Seek out deep water; floating with a pack is less tiring than walking through shallow water or soft mud.
- Seek out sand, shell, gravel, or stone bottoms; these firmer bottoms generally ease travel and help conserve energy.

Rivers and Canals

A river is a large, natural stream of water that empties into a larger body of water. The slope of the riverbed and the volume of water in the river determine its current.

Canals resemble small rivers or streams in their width and depth, but usually lack any significant current. Climbing out of these waterways can be difficult if the canal is flanked by steep banks.

Chapter 5
Fording Waterways

WARNING

Fords are dangerous. Cross as quickly as possible.

A ford is any site in a river, stream, or canal where the water is shallow enough for troops or vehicles to cross without using flotation devices. Canal bottoms are usually too soft to support fording vehicles, and wading infantry frequently stumble.

The tactical situation dictates the location of the fording site. Seek fords that are protected from enemy observation and that allow for adequate supporting fires. A night fording takes at least one and a half times as long as a daylight fording.

NOTE: In this chapter, the term "river" refers to rivers, streams, and canals.

Selection of a Ford Site

The following table identifies desirable fording characteristics:

Characteristics	Comments
Concealment	The ford hides personnel and vehicle movement from enemy observation.
Accessibility	The ford should have low banks with gentle gradients. This allows a free flow of traffic at both the entrance and the exit.

Characteristics (Continued)	Comments (Continued)
Slow Current	The ford’s current should not exceed 1.5 meters per second if possible.
Firm Footing	The ford’s bottom, entry, and exit composition should be firm enough to support traffic. Do not drive a vehicle over any bottom composition that a 2-inch diameter stick can be pressed into more than 1 or 2 inches.
Gently Sloped Channels	The ford’s entry and exit points should be gently sloped. If possible, locate a portion of the stream where the channel is not actively shifting.
Depth	The fording depth is less than or equal to the least capable vehicle.

Determine the Slope

Units move into and out of water faster and more quietly if entry and exit points are not steep or muddy. Slope is the amount of change in ground horizontal distance (run) and in vertical elevation (rise) from one point to another. Slope is usually expressed as a percentage. You can use a clinometer, map, or line of sight and pace to measure the percentage of a slope.

Clinometer

A clinometer measures percentage of a slope. It is a component of the M9 armored combat excavator, and organic to many Marine engineer units. However, engineers are also taught (and often use) field-expedient methods to determine slopes and gradients.

Map

A map measures the horizontal distance along a desired path. Determine the difference in elevation between the path's starting and ending points. From a map's scale, you can determine the distance between two points. From a map's elevation lines, you can determine the difference in height between the same two points. Both figures must be in the same unit of measure (e.g., feet, meter). Divide the elevation (rise) by the distance (run) and multiply by 100.

Rise = 165 - 120 = 45 meters

Run = 200 meters

% Slope = $\frac{45}{200}$ **x 100 - 22.5%**



Line of Sight and Pace

To determine line of site and pace, stand at the bottom of the slope, keep your eyes level, pick a spot on the slope, then pace the distance. The number of paces multiplied by a standard measure of 0.75 meter determines the run. The eye-level height (usually 1.5 to 1.7 meters) determines the rise. Repeat this procedure until you have covered the entire distance you want to measure for each spot (vertical and horizontal). Add the vertical distances to provide total rise and the horizontal distances to provide total run.

Determine the Current Speed

Current speed increases as channels narrow. It may be necessary to locate a wider ford location to obtain a slower stream current. The following steps are used to calculate the speed of the current:

> *Determine points A and B along a channel. Then measure the distance between those two points.*



$$\frac{\text{Distance (meters) Between Points A and B}}{\text{Time (seconds) Between Points C and D}} = \text{Current Speed (meters per second)}$$

Sight directly across the water from points A and B to locate points C and D.

Throw a floating object (e.g., a stick) upstream from points A and C. Observe the object as it floats toward points B and D.

Subtract to find the time it takes for the object to float from start to finish.

Do not attempt to swim across currents that are moving faster than 1.5 meters per second. Equivalents of this speed include—

- Quick-time march rate of 120 counts per minute with one, 30-inch step at each count.
- 5 feet per second.
- 3.5 miles per hour.
- 5.5 kilometers per hour.

Measure River Width

A river's width can be estimated from the width of its symbol on a scaled topographic map. If this is not possible, use the following compass techniques:

Stand at the water line (A).

Shoot an azimuth to a point on the opposite bank (B).

Move upstream or downstream until you are at a point (C) where you can shoot an azimuth 45 degrees larger or smaller than the original azimuth.



Measure the distance between points A and C. The distance calculated equals the river's width.

Calculate Downstream Drift

A river's current causes personnel and equipment to drift downstream. If personnel and equipment are aimed straight across the river, they will sideslip downstream as they move across the current to the other shore. Therefore, personnel and equipment crossings must compensate for the effects of a river's current and entries are usually made upstream of the desired exit point. Use the formula below to calculate downstream drift.



$$\frac{\text{Current Speed (A)}}{\text{Crossing Speed (B)}} \times \text{River Width (C)} = \text{Downstream Drift (D)}$$

> *NOTE:* The crossing speed for a swimmer across a river may vary but is generally limited to 1 meter per second. All measurements must be in the same unit of measure (e.g., meters, feet).

The Buddy System

Whenever a Marine unit must enter into or operate on the water, a "buddy system" is employed in which every Marine is paired with a swimming partner. The buddy system matches an experienced swimmer with a weak swimmer. The experienced swimmer assists and encourages the weaker swimmer and bolsters confidence during night crossings. If a unit has an odd number of Marines, place the extra person with another pair to form a three-person team.

Water Crossings

Care of Weapons

Marine infantry weapons and munitions are designed to be able to operate after immersion. However, protect your weapons from moisture whenever possible.

A gas-operated weapon can malfunction if water travels down the barrel and enters the gas tube. To protect the gas tube—

> *Close the weapon's bolt before entering the water.*
>
> *Seal the muzzle with a condom, balloon, plastic spoon wrapper, or other form of waterproof material.*
>
> *Tie or melt the protective cover to create a watertight seal.*

When the muzzle's protective cover is no longer needed, remove it. Open the bolt and inspect the barrel. If the tactical situation permits, swab excess moisture from the barrel. Test fire automatic weapons, if possible. Field strip and clean weapons as soon as possible. If time does not allow for a complete inspection, rinse inaccessible areas with small amounts of diesel fuel, then dry.

ISOMAT Raft

Construction of an ISOMAT raft is time-consuming. This type of raft should not be employed as part of an attack, but used for logistical purposes (e.g., evacuating stretcher cases, transporting supplies). Use the following steps to build an ISOMAT raft:

Wrap ISOMAT sleeping pads around sturdy sticks.

Use parachute cord and square knots to tie the pads securely in place and to lash stick ends together in a rectangle.



NOTE: The ISOMAT raft pictured can support several hundred pounds. However, the cargo will get wet if not properly waterproofed.

Poncho Raft

A poncho raft can support two Marines and their equipment and is well suited for long crossings. Use the following steps to build a poncho raft:

Inspect two ponchos and ensure they are serviceable.

Lay one poncho flat on the ground, with the hood-side up.

Cinch the hood tightly to form a gooseneck or tie in a knot.



Pad sharp edges of equipment and place the equipment in the center of the poncho.



Place the second poncho over the equipment, rubber side up, and hood facing down.

Snap the edges of the two ponchos together.



Roll the edges toward the equipment.



Roll the edges into pigtails and tie them off.



Pull the pigtails together over the top and lash them securely.



Protect the raft from brush punctures while placing it in the water. Swim across the water obstacle while security elements are covering the far shore.



Construction of a Pack Raft

You will need two waterproofed packs and two M16A2 service rifles. The following steps are required to construct a pack raft:

Place two packs side-by-side with the pack frames on the deck. The tops of the packs are opposite of each other.

Loosen the main compartment straps on both packs.

Insert one rifle on each end between the straps and the packs. The muzzles are opposite of each other. The rifles serve as one means to secure the packs together. Place the front sight post under the top flap.

Tighten the straps so that the rifles and packs are secure.

Take the excess strap on the inner side of each pack and secure it to the opposite pack to better secure the two packs together.

Take the excess straps on the outer sides of the packs and use those straps as safety lashing for the rifles.

Tuck the excess straps and check to make sure the rifles and packs are secure.



Single-Rope Bridge

A single-rope bridge offers a temporary and quick way to cross small rivers. It also provides extra security while crossing swift waters. At night, it prevents straggling, and guides units precisely from one side of the river to the other side. If crossing a river at night, plan for at least one single-rope bridge.

If your unit is crossing a river with swift currents or water depths above 4 feet, the unit is carrying sufficient rope to span the crossing site, and the tactical situation permits, secure the rope on near and far banks to provide a hand-hold for crossing Marines. This reduces the time required for the entire unit to cross and provides a degree of comfort/confidence for poor swimmers. Use a squad-sized bridge team to construct a single-rope bridge. Station several strong swimmers at the water's edge to help anyone who has trouble crossing.

Nylon rope is normally coiled in 120 foot lengths. It is 0.6 inches in diameter and has a breaking strength of about 3,840 pounds. Over time, a nylon rope can stretch to as much as one-third more than its original length and stretching weakens the rope. If the rope is stretched, discard the rope or use it for light tasks. To prolong the life of a nylon rope, do not step on it or drag it on the ground. Pad the rope in places where it contacts rocks or sharp corners. Do not leave the rope knotted or stretched longer than necessary. Dry rope as soon as possible. Single-rope bridge construction is as follows:

Tie a sling rope around your waist using a square knot and two, separate half hitches. See the appendix for detailed information on knots.

Attach a locking steel carabiner to the sling rope.



Tie a bowline knot in the running end of the bridge rope and attach it to the carabiner.

Temporarily secure the other end of the rope to a tree on the near shore.

Enter and cross the water.

> *NOTE:* Carry only your weapon and ammunition.

Exit the water on the opposite shore.



Prepare your weapon for use. Unhook the bridge rope from the carabiner at your waist, and tie the bridge rope to a sturdy tree using a round turn and two half hitches.



Conduct a box reconnaissance of the opposite shore.

On the near shore, have another Marine prepare to tighten the rope. That Marine should place a transport tightening system in the bridge rope by tying a double butterfly *knot and placing two carabiners in the butterfly. See the appendix for detailed information on knots.*

The Marine should pass the running end of the bridge rope around the downstream side of the near shore anchor point and through the two carabiners.

Pull the butterfly knot approximately one-third of the distance across the river.

Secure the bridge rope to an anchor point using a round turn and two half-hitches.

On the near shore, the Marine helping you should pull the slack out of the bridge rope until the butterfly knot is back on the near side. The bridge rope is then tied off against itself using two half hitches with a quick release in the last half hitch.



> *Note:* The single-rope bridge must be as tight as possible so it will not sag when used.

If you lose your footing and fall into the water, swim with the current to the closest shore. Swimming against the current is dangerous and quickly causes fatigue.

High and Dry Crossings

If the single-rope bridge is high enough, suspend yourself below the single-rope bridge and above the water. Use the following steps to suspend yourself from a single-rope bridge and then pull yourself across the water:

Tie a sling rope around your waist using a bowline. Ensure that the knot is tight.

Attach a carabiner through the bowline's loop. The carabiner's gate faces up.

Secure your helmet chin strap.

Face the single-rope bridge with your left shoulder toward the far shore.



Grasp the bridge rope in both hands.

Swing your body beneath the single-rope bridge with your head toward the far shore. Cross your ankles above the bridge rope.

Arch back until the carabiner contacts the bridge rope. Connect the carabiner to the bridge rope. Allow the carabiner to bear your body's weight.

Pull yourself across the single-rope bridge, hand over hand, to the far shore.



Swift Current Crossings

A single-rope bridge prevents being knocked down and swept away by a swift current. Use the following steps to move through a swift current:

Tie one end of a sling rope around your waist using a bowline.

Tie the running end of the sling rope in another bowline, and attach a carabiner to the bowline's loop.

Step up to the bridge. Face upstream.

Hook the carabiner to the single-rope bridge.

Walk sideways into the river while grasping the bridge rope in both hands.

Use the single-rope bridge for balance and remain standing, if possible.

Continue to move sideways through the river to the far shore.

Slow Current Crossings

If you face little or no current, it is not necessary to hook up to a bridge rope with a carabiner. Lie on your back in the water beneath the single-rope bridge. Support your body weight with your waterproof pack. Use the bridge rope and pull yourself hand over hand across the river.

Removal

If you are the last Marine waiting to cross, pull on the standing end of the rope to release the knot, then tie the rope around your waist using a bowline. The Marines on the far shore will pull you through the water.

Appendix
Knot Tying

Square Knot

The square knot is used to secure two ropes of equal diameter together so they form one continuous rope that will not slip.



Bowline

The bowline forms a loop that will not tighten or slip under strain. It is easily untied.



Hitches

Hitches are used to dress (prepare) knots and secure loose ends.

Half Hitch

The half hitch is used to tie a rope to a tree or to a larger rope. It will hold against a steady pull, but is not a secure hitch. It is frequently used to secure the free end of a rope.



Two Half Hitches

Two half hitches can be used to secure the running end of a rope.



Round Turn and Two Half Hitches

A round turn and two half hitches can be used to fasten a rope to a tree. This hitch does not jam.



Butterfly Knot

The butterfly knot is used for anchor lines. Tied properly, it will not tighten on itself to the point that it cannot be easily untied. The butterfly knot can be used to pull a rope bridge taut. This knot can be used to tighten a fixed rope when mechanical means are not available. It will not jam if a stick is placed between the two upper loops.



United States Patent [19]

Rogers, Sr.

[11] **4,292,804**

[45] **Oct. 6, 1981**

[54] **METHOD AND APPARATUS FOR OPERATING AN ENGINE ON COMPRESSED GAS**

[76] Inventor: **Leroy K. Rogers, Sr.,** #5 Capistrano Ct., Ft. Myers, Fla. 33908

[21] Appl. No.: **158,303**

[22] Filed: **Jun. 10, 1980**

[51] **Int. Cl.**³ **F15B 11/06**

[52] **U.S. Cl.** **60/407**; 91/187; 91/275

[58] **Field of Search** 60/407, 412; 91/187, 91/275, 364

[56] **References Cited**

U.S. PATENT DOCUMENTS

3,881,399	5/1975	Sagi et al.	91/187 X
3,885,387	5/1975	Simington	60/407 X
4,018,050	4/1977	Murphy	60/412 X

Primary Examiner—Allen M. Ostrager
Attorney, Agent, or Firm—Burns, Doane, Swecker & Mathis

[57] **ABSTRACT**

The present invention relates to a method and apparatus for operating an engine having a cylinder and a piston reciprocable therein on compressed gas. The apparatus comprises a source of compressed gas connected to a distributor which distributes the compressed gas to the cylinder. A valve is provided to selectively admit compressed gas to the cylinder when the piston is in an approximately top dead center position. In one embodiment of the present invention the timing of the opening of the valve is advanced such that the compressed gas is admitted to the cylinder progressively further before the top dead center position of the piston as the speed of the engine increases. In a further embodiment of the present invention a valve actuator is provided which increases the length of time over which the valve remains open to admit compressed gas to the cylinder as the speed of the engine increases. A still further embodiment of the present invention relates to an apparatus for adapting a conventional internal combustion engine for operation on compressed gas.

22 Claims, 8 Drawing Figures




FIG. 1

FIG. 6


94
85
93
53
92
91
96
55
85

FIG. 7


67
49
47
45
51
67
43
99
43
85
95
53
101
85
102
6
97
6
91
41
92
93
94
96
55

FIG. 3


61
43
59
43
67
57
65
53
65
67
67
43
43


47
45
49
51
59
63
60
65
61
3
3
67
65
43
43
65
41
53
55
57

FIG. 2

Fig. 5


85
69
53
83
73
71
85

Fig. 4


67
45
47
43
71
49
69
85
75
85
67
43
5
5
83
81
73
77
72
79
53
87
89
55

Fig. 6


153
155
135
141
143
140
141
137
149
129
149
147
127
145
157

METHOD AND APPARATUS FOR OPERATING AN ENGINE ON COMPRESSED GAS

BACKGROUND AND SUMMARY OF THE PRESENT INVENTION

The present invention relates to a method and apparatus for operating an engine using a compressed gas as the motive fluid. More particularly, the present invention relates to a apparatus for adapting a pre-existing internal combustion engine for operation on a compressed gas.

Air pollution is one of the most serious problems facing the world today. One of the major contributors to air pollution is ordinary internal combustion engine which are used in most motor vehicles today. Various devices, including many items mandated by legislation, have been proposed in an attempt to limit the pollutants which an internal combustion engine exhausts to the air. However, most of these devices have met with limited success and are often both prohibitively expensive and complex. A clean alternative to the internal combustion engine is needed to power vehicles and other machinery.

A compressed gas, preferably air, would provide an ideal motive fluid for a engine since it would eliminate the usual pollutants exhausted from an internal combustion engine. An apparatus for converting an internal combustion engine for operation on compressed air is disclosed in U.S. Pat. No. 3,885,387 issued May 27, 1975 to Simington. The Simington patent discloses an apparatus including a source of compressed air and a rotating valve actuator which opens and closes a plurality of mechanical poppet valves. The valves deliver compressed air in timed sequence to the cylinders of an engine through adapters located in the spark plug holes. However, the output speed of an engine of this type is limited by the speed of the mechanical valves and the fact that the length of time over which each of the valves remains open cannot be varied as the speed of the engine increases.

Another apparatus for converting an internal combustion engine for operation on steam or compressed air is disclosed in U.S. Pat. No. 4,102,130 issued July 25, 1978 to Stricklin. The Stricklin patent discloses a device which changes the valve timing of a conventional four stroke engine such that the intake and exhaust valves open once for every revolution of the engine instead of once every other revolution of the engine. A reversing valve is provided which delivers live steam or compressed air to the intake valves and is subsequently reversed to allow the exhaust valves to deliver the expanded steam or air to the atmosphere. A reversing valve of this type however does not provide a reliable apparatus for varying the amount of motive fluid injected into the cylinders when it is desired to increase the speed of the engine. Further, a device of the type disclosed in the Stricklin patent requires the use of multiple reversing valves if the cylinders in a multi-cylinder engine were to be fired sequentially.

Therefore, it is an object of the present invention to provide a reliable method and apparatus for operating an engine or converting an engine for operation with a compressed gas.

A further object of the present invention is to provide a method and apparatus which is effective to deliver a constantly increasing amount of compressed gas to an engine as the speed of the engine increases.

A still further object of the present invention is to provide a method and apparatus which will operate an engine using compressed gas at a speed sufficient to drive a conventional automobile at highway speeds.

It is still a further object of the present invention to provide a method and apparatus which is readily adaptable to a standard internal combustion engine to convert the internal combustion engine for operation with a compressed gas.

Another object of the invention is to provide a method and apparatus which utilizes cool expanded gas, exhausted from a compressed gas engine, to operate an air conditioning unit and/or an oil cooler.

These and other objects are realized by a method and apparatus according to the present invention for operating an engine having at least one cylinder and a reciprricating piston therein using compressed gas as a motive fluid. The apparatus includes a source of compressed gas and a distributor connected with the source of the compressed gas for distributing the compressed gas to the at least one cylinder. A valve is provided for admitting the compressed gas to the cylinder when the piston is in approximately a top dead center position within the cylinder. An exhaust is provided for exhausting the expanded gas from the cylinder as the piston returns to approximately the top dead center position.

In a preferred embodiment of the present invention a device is provided for varying the duration of each engine cycle over which the valve remains open to admit compressed gas to the cylinder dependent upon the speed of the engine. In a further preferred embodiment of the present invention, an apparatus for advancing the timing of the opening of the valve is arranged to admit the compressed gas to the cylinder progressively further before the top dead center position of the piston as the speed of the engine increases.

Further features of the present invention include a valve for controlling the amount of compressed gas admitted to the distributor. Also, a portion of the gas which has been expanded in the cylinder and exhausted through the exhaust valve is delivered to a compressor to be recompressed and returned to the source of compressed gas. A gear train is selectively engagable to drive the compressor at different operating speed depending upon the pressure maintained at the source of compressed air and/or the speed of the engine. Still further, a second portion of the exhaust gas is used to cool a lubricating fluid for the engine or to operate an air conditioning unit.

In a preferred embodiment of the present invention, the valve for admitting compressed gas to the cylinder is electrically actuated. The device for varying the duration of each engine cycle over which the intake valve remains open as the speed of the engine increase comprises a rotating element whose effective length increases as the speed of the engine increases such that a first contact on the rotating element is electrically connected to a second contact for a longer period of each engine cycle. The second contact actuates the valve whereby the valve remains in an open position for a longer period of each engine cycle as the speed of the engine increases.

Still further features of the present invention include an adaptor plate for supporting the distributor above an intake manifold of a conventional internal combustion engine after a carburetor has been removed to allow air to enter the cylinders of the engine through the intake manifold and conventional intake valves. Another adaptor plate is arranged over an exhaust passageway of the internal combustion engine to reduce the cross-sectional area of the exhaust passageway.

BRIEF DESCRIPTION OF THE DRAWINGS

Preferred embodiments of a method and apparatus for operating an engine according to the present invention will be described with reference to the accompanying drawings wherein like members bear like reference numerals and wherein:

FIG. 1 is a schematic representation of an apparatus according to the present invention arranged on an engine;

FIG. 2 is a side view of one embodiment of a valve actuator according to the present invention;

FIG. 3 is a cross-sectional view taken along the line 3—3 in FIG. 2;

FIG. 4 is a cross-sectional view of a second embodiment of a valve actuator according to the present invention;

FIG. 5 is a view taken along the line 5—5 in FIG. 4;

FIG. 6 is a cross-sectional view of a third embodiment of a valve actuator according to the present invention;

FIG. 7 is a view taken along the line 7—7 in FIG. 6;

FIG. 8 is a cross-sectional view of a gearing unit to drive a compressor according to the present invention.

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENTS

With reference to FIG. 1, an engine block 21 (shown in phantom) having two banks of cylinders with each bank including cylinders 20 having pistons 22 reciprocable therein (only one of which is shown in phantom) in a conventional manner. While the illustrated engine is a V-8 engine, it will be apparent that the present invention is applicable to an engine having any number of pistons and cylinders with the V-8 engine being utilized for illustration purposes only. A compressed gas tank 23 is provided to store a compressed gas at high pressure. It may also be desirable to include a small electric or gas compressor to provide compressed gas to supplement the compressed gas held in the tank 23. In a preferred embodiment, the compressed gas is air which can be obtained from any suitable source.

A line 25 transports the gas withdrawn from the tank 23 when a conventional shut off valve 27 is open. In addition, a solenoid valve 29 preferably operated by a suitable key operated switch (not shown) for the engine is also arranged in the line 25. In normal operation, the valve 27 is maintained open at all times with the solenoid valve 29 operating as a selective shut off valve to start and stop the engine 21 of the present invention.

A suitable regulating valve 31 is arranged downstream from the solenoid valve 29 and is connected by a linkage 33 to a throttle linkage 35 which is operator actuated by any suitable apparatus such as a foot pedal (not shown). The line 25 enters an end of a distributor 33 and is connected to an end of a pipe 35 which is closed at the other end. A plurality of holes, which are equal to the number of cylinders in the engine 21, are provided on either side of the pipe 35 along the length of the pipe 35.

When the present invention is used to adapt a conventional internal combustion engine for operation on compressed gas, an adaptor plate 36 is provided to support the distributor 33 in spaced relation from the usual intake opening in the intake manifold of the engine after a conventional carburetor has been removed. In this way, air is permitted to enter the internal combustion engine through the usual passageways and to be admitted to the cylinders through suitable intake valves (not shown). The adaptor plate 36 is secured to the engine block 21 and the distributor 33 by any suitable apparatus, e.g., bolts.

Each of the holes in the pipe 35 is connected in fluid-tight manner to a single line 37. Each line 37 carries the compressed gas to a single cylinder 20. In a preferred embodiment, each of the lines 37 is $\frac{1}{2}$ inch high pressure plastic tubing attached through suitable connectors to the distributor 33 and the pipe 35. Each of the lines 37 is connected to a valve 39 which is secured in an opening provided near the top of each of the cylinders 20. In the case of a conversion of a standard internal combustion engine, the valves 39 can be conveniently screwed into a tapped hole in the cylinder 20 typically provided for a spark plug of the internal combustion engine. In a preferred embodiment, the valves 39 are solenoid actuated valves in order to provide a fast and reliable opening and closing of the valves 39.

Each of the valves 39 is energized by a valve actuator 41 through one of a plurality of wires 43. The valve actuator 41 is driven by a shaft of the engine similar to the drive for a conventional distributor of an internal combustion engine. That is, a shaft 55 of the valve actuator 41 is driven in synchronism with the engine 21 at one half the speed of the engine 21.

A first embodiment of the valve actuator 41 (FIGS. 2 and 3) receives electrical power through a wire 45 which is energized in a suitable manner by a battery, and a coil if necessary (not shown) as is conventional in an internal combustion engine. The wire 45 is attached to a central post 47 by a nut 49. The post 47 is connected to a conducting plate 51 arranged within a housing 53 for the valve actuator 41. Within the housing 53, the shaft 55 has an insulating element 57 secured to an end of the shaft 55 for co-rotation therewith when the shaft 55 is driven by the engine 21. A first end of a flexible contact 59 is continuously biased against the conducting plate 51 to receive electricity from the battery or another suitable source. A second end of the contact 59 is connected to a conducting sleeve 60 which is in constant contact with a spring biased contact 61 which is arranged within the sleeve 60. The contact 61 is biased by a spring 63 which urges the contact 61 towards a side wall of the housing 53.

With reference to FIG. 3, a plurality of contacts 65 are spaced from one another and are arranged around the periphery of the housing 53 at the same level as the spring biased contact 61. Each contact 65 is electrically connected to a post 67 which extends outside of the housing 53. The number of contacts 65 is equal to the number of cylinders in the engine 21. One of the wires 43, which actuate the valves 39, is secured to each of the posts 67.

In operation, as the shaft 55 rotates in synchronism with the engine 21, the insulating element 57 rotates and electricity is ultimately delivered to successive ones of the contacts 65 and wires 43 through the spring biased contact 61 and the flexible contact 59. In this way, each of the electrical valves 39 is actuated and opened in the proper timed sequence to admit compressed gas to each of the cylinders 20 to drive the pistons 22 therein on a downward stroke.

The embodiment illustrated in FIGS. 2 and 3 is effective to actuate each of the valves 39 to remain open for a long enough period of time to admit sufficient compressed gas to each of the cylinders 20 of the engine 21 to drive the engine 21. The length of each of the contacts 65 around the periphery of the housing 53 is sufficient to permit the speed of the engine to be increased when desired by the operator by moving the throttle linkage 35 which actuates the linkage 33 to further open the regulating valve 31 to admit more compressed gas from the tank 23 to the distributor 33. However, it has been found that the amount of air admitted by the valves 39 when using the first embodiment of the valve actuator 41 (FIGS. 2 and 3) is substantially more than required to operate the engine 21 at an idling speed. Therefore, it may be desirable to provide a valve actuator 41 which is capable of varying the duration of each engine cycle over which the solenoid valves 39 are actuated, i.e., remain open to admit compressed gas, as the speed of the engine 21 is varied.

A second embodiment of a valve actuator 41 which is capable of varying the duration of each engine cycle over which each of the valves 39 remains open to admit compressed gas to the cylinders 20 dependent upon the speed of the engine 21 will be described with reference to FIGS. 4 and 5 wherein members corresponding to those of FIGS. 2 and 3 bear like reference numerals. The wire 45 from the electrical source is secured to the post 47 by the nut 49. The post 47 has a annular contact ring 69 electrically connected to an end of the post 47 and arranged within the housing 53. The shaft 55 rotates at one half the speed of the engine as in the embodiment of FIGS. 2 and 3.

At an upper end of the shaft 55, a splined section 71 slidably receives an insulating member 73. The splined section 71 of the shaft 55 positively holds the insulating member 73 for co-rotation therewith but permits the insulating member 73 to slide axially along the length of the splined section 71. Near the shaft 55, a conductive sleeve 72 is arranged in a bore 81 in an upper surface of the insulating element 73 generally parallel to the splined section 71. A contact 75, biased towards the annular contact ring 69 by a spring 77, is arranged within the conductive sleeve 72 in contact therewith. The conductive sleeve 72 also contacts a conductor 79 at a base of the bore 81.

The conductor 79 extends to the upper surface of the insulating element 73 near an outer periphery of the insulating element 73 where the conductor 79 is electrically connected to a flexible contact 83. The flexible contact 83 selectively engages a plurality of radial contacts 85 arranged on an upper inside surface of the housing 53. A weak spring 87 arranged around the splined section 71 engages a stop member 89 secured on the shaft 55 and the insulating element 73 to slightly bias the insulating element 73 towards the upper inside surface of the housing 53 to ensure contact between the flexible contact 83 and the upper inside surface of the housing 53. As best seen in FIG. 5, the radial contacts 85 on the upper inside surface of the housing 53 are arranged generally in the form of radial spokes extending from the center of the housing 53 with the number of contacts being equal to the number of cylinders 20 in the engine 21. The number of degrees covered by each of the radial contacts 85 gradually increases as the distance from the center of the upper inside surface of the housing 53 increases.

In operation of the device of FIGS. 4 and 5, as the shaft 55 rotates, electricity flows along a path through the wire 45 down through post 47 to the annular contact member 69 which is in constant contact with the spring biased contact 75. The electrical current passes through the conductive sleeve 72 to the conductor 79 and then to the flexible contact 83. As the flexible contact 83 rotates along with the insulating member 73 and the shaft 55, the tip of the flexible contact 83 successively engages each of the radial contacts 85 on the upper inside of the housing 53. As the speed of the shaft 55 increases, the insulating member 73 and the flexible contact 83 attached thereto move upwardly along the splined section 71 of the shaft 55 due to the radial component of the splines in the direction of rotation under the influence of centrifugal force. As the insulating member 73 moves upwardly, the flexible contact 83 is bent such that the tip of the contact 83 extends further radially outwardly from the center of the housing 53 (as seen in phantom lines in FIG. 4). In other words, the effective length of the flexible contact 83 increases as the speed of the engine 21 increases.

As the flexible contact 83 is bent and the tip of the contact 83 moves outwardly, the tip remains in contact with each of the radial contacts 85 for a longer period of each engine cycle due to the increased angular width of the radial contacts with increasing distance from the center of the housing 53. In this way, the length of time over which each of the valves 39 remains open is increased as the speed of the engine is increased. Thus, a larger quantity of compressed gas or air is injected into the cylinders as the speed increases. Conversely, as the speed decreases and the insulating member 73 moves downwardly along the splined section 71, a minimum quantity of air is injected into the cylinder due to the shorter length of the individual radial contact 85 which is in contact with the flexible contact 83. In this way, the amount of compressed gas that is used during idling of the engine 21 is at a minimum whereas the amount of compressed gas which is required to increase the speed of the engine 21 to a level suitable to drive a vehicle on a highway is readily available.

With reference to FIGS. 6 and 7, a third embodiment of a valve actuator 41 according to the present invention includes an arcuate insulating element 91 having a first end pivotally secured by any suitable device such as screw 92 to the shaft 55 for co-rotation with the shaft 55. The screw 92 is screwed into a tapped hole in the insulating element 91 such that a tab 94 at an end of the screw 92 engages a groove 96 provided in the shaft 55. In this way, the insulating element 91 positively rotates with the shaft 55. However, as the shaft 55 rotates faster, a second end 98 of the insulating element 91 is permitted to pivot outwardly under the influence of centrifugal force because of the groove 96 provided in the shaft 55. A spring 93 connected between the second end 98 of the element 91 and the shaft 55 urges the second end of the element 91 towards the center of the housing 53.

A contact 99 similar to the contact 59 (FIG. 2) is arranged such that one end of the contact 99 is in constant contact with the conducting plate 51 located centrally within the housing 53. The other end of the contact 99 engages a conductive sleeve 101 arranged in bore 102. A contact element 95 is arranged in the conductive sleeve 101 in constant contact with the sleeve 101. The bore 102 is arranged generally parallel to the shaft 55 near the second end of the arcuate insulating element **91**. The contact **95** is biased by a spring **97** towards the upper inside surface of the housing **53** for selective contact with each of the plurality of radial contacts **85** which increase in arc length towards the outer peripheral surface of the housing **53** (FIG. **6**).

In operation of the device of FIGS. **6** and **7**, as the shaft **55** rotates the arcuate insulating element **91** rotates with the shaft **55** and the second end **98** of the insulating element **91** tends to pivot about the shaft **55** due to centrifugal force. Thus, as the effective length of the contact **95** increases, i.e., as the arcuate insulating element **91** pivots further outwardly, the number of degrees of rotation over which the contact **95** is in contact with each of the radial contacts **85** on the upper inside surface of the housing **53** increases thereby permitting each of the valves **39** to remain open for a longer period of each engine cycle to admit more compressed gas to the respective cylinder **20** to further increase the speed of the engine **21**.

With reference to FIG. **1**, a mechanical advance linkage **104** which is connected to the throttle linkage **35**, advances the initiation of the opening of each valve **39** such that compressed gas is injected into the respective cylinder further before the piston **22** in the respective cylinder **20** reaches a top dead center position as the speed of the engine is increased by moving the throttle linkage **35**. The advance linkage **104** is similar to a conventional standard mechanical advance employed on an internal combustion engine. In other words, the linkage **104** varies the relationship between the angular positions of a point on the shaft **55** and a point on the housing **53** containing the contacts. Alternatively, a conventional vacuum advance could also be employed. By advancing the timing of the opening of the valves **39**, the speed of the engine can more easily be increased.

The operation of the engine cycle according to the present invention will now be described. The compressed gas injected into each cylinder of the engine **21** drives the respective piston **22** downward to drive a conventional crankshaft (not shown). The movement of the piston downwardly causes the compressed gas to expand rapidly and cool. As the piston **22** begins to move upwardly in the cylinder **20** a suitable exhaust valve (not shown) arranged to close an exhaust passageway is opened by any suitable apparatus. The expanded gas is then expelled through the exhaust passageway. As the piston **22** again begins to move downwardly a suitable intake valve opens to admit ambient air to the cylinder. The intake valve closes and the ambient air is compressed on the subsequent upward movement of the piston until the piston reaches approximately the top dead center position at which time the compressed gas is again injected into the cylinder **20** to drive the piston **22** downward and the cycle begins anew.

In the case of adapting a conventional internal combustion engine for operation on compressed gas, a plurality of plates **103** are preferably arranged over an end of the exhaust passageways in order to reduce the outlet size of the exhaust passageways of the conventional internal combustion engine. In the illustrated embodiment, a single plate having an opening in the center is bolted to the outside exhaust passageway on each bank of the V-8 engine while another single plate having two openings therein is arranged with one opening over each of the interior exhaust passageways on each bank of the V-8 engine. A line **105** is suitably attached to each of the adaptor places to carry the exhaust to an appropriate location. In a preferred embodiment, the exhaust lines **105** are 1½" plastic tubing.

In a preferred embodiment, the exhaust lines **105** of one bank of the V-8 engine are collected in a line **107** and fed to an inlet of a compressor **109**. The pressure of the exhaust gas emmanating from the engine **21** according to the present invention is approximately 25 p.s.i. In this way, the compressor **109** does not have to pull the exhaust into the compressor since the gas exhausted from the engine **21** is at a positive pressure. The positive pressure of the incoming fluid increases the efficiency and reduces wear on the compressor **109**. The exhaust gas is compressed in the compressor **109** and returned through a line **111** and a check valve **113** to the compressed gas storage tank **23**. The check valve **113** prevents the flow of compressed gas stored in the tank **23** back towards the compressor **109**.

A suitable pressure sensor **115** is arranged at an upper end of the tank **23** and sends a signal along a line **117** when the pressure exceeds a predetermined level and when the pressure drops below a predetermined level. The line **117** controls an electrically actuated clutch **119** disposed at a front end of the compressor **109**. The clutch **119** is operative to engage and disengage the compressor **109** from a drive pulley **121**. Also, the signal carried by the line **117** actuates a suitable valve **123** arranged on a compressor housing **125** to exhaust the air entering the compressor housing **125** from the line **107** when the clutch **119** has disengaged the compressor **109** from the drive pully **121**.

In a preferred embodiment, when the pressure is the tank **23** reaches approximately 600 p.s.i., the clutch **119** is disengaged and the compressor **109** is deactivated and the valve **123** is opened to exhaust the expanded gas delivered to the compressor **109** from the line **107** to the atmosphere. When the pressure within the tank **23** drops below approximately 500 p.s.i., the sensor **115** sends a signal to engage the clutch **119** and close the valve **123**, thereby operating the compressor **109** for supplying the tank **23** with compressed gas.

The pulley **121** which drives the compressor **109** through the clutch **119** is driven by a belt **127** which is driven by a pulley **129** which operates through a gear box **131**. With reference to FIGS. **1** and **8**, a second pulley **133** on the gear box is driven by a belt **135** from a pulley **137** arranged on a drive shaft **139** of the engine **21**. The pulley **137** drives a splined shaft **140** which has a first gear **141** and a second larger gear **143** arranged thereon for rotation with the splined shaft **140**. The splined shaft **140** permits axial movement of the gears **141** and **143** along the shaft **140**.

In normal operation (as seen in FIG. **8**), the first gear **141** engages a third gear **145** arranged on a shaft **147** which drives the pulley **129**. The shafts **140** and **147** are arranged in suitable bearings **149** arranged at each end thereof. When the speed of the engine **21** drops below a predetermined level, a suitable sensor **151** responsive to the speed of the drive shaft **139** of the engine **21** generates a signal which is transmitted through a line **153** to a solenoid actuator **155** arranged within the gear box **131**. The solenoid actuator **155** moves the first and second gears **141**, **143** axially along the splined shaft **140** to the right as seen in FIG. **8** such that the second, larger gear **143** engages a fourth smaller gear **157** which is arranged on the shaft **147**. The ratio of the second gear **143** to the fourth gear **157** is preferably approximately 3 to 1.

In this way, when the speed of the engine **21** drops below the predetermined level as sensed by the sensor **151** (which predetermined level is insufficient to drive the compressor **109** at a speed sufficient to generate the 500-600 pounds of pressure which is preferably in the tank **23**), the solenoid actuator **155** is energized to slide the gears **143**, **141** axially along the splined shaft **140** so that the second, larger gear **143** engages the fourth, smaller gear **157** to drive the pulley **129** and hence the compressor **109** at a higher rate of speed to generate the desired pressure. When the speed of the engine increases above the predetermined level, in a preferred embodiment approximately 1500 rpm, the solenoid actuator **155** is deactivated by the sensor **151** thereby moving the gears **143** and **141** to the left as seen in FIG. **8** such that the first gear **141** re-engages with the third gear **145** to effectuate a 1 to 1 ratio between the output shaft **139** of the engine **21** and the pulley **129**.

The other bank of the V-8 engine has its exhaust ports arranged with adapter plates **103** similar to those on the first bank. However, the exhaust from this bank of the engine **21** is not collected and circulated through the compressor **109**. In a preferred embodiment, a portion of the exhaust is collected in a line **159** and fed to an enlarged chamber **161**. A second fluid is fed through a line **163** into the chamber **161** to be cooled by the cool exhaust emmanating from the engine **21** in the line **159**. The second fluid in the line **163** may be either transmission fluid contained in a transmission associated with the engine **21** or a portion of the oil used to lubricate the engine **21**. A second portion of the exhaust from the second bank of the V-8 engine is removed from the line **159** in a line **165** and used as a working fluid in an air conditioning system or for any other suitable use.

It should be noted that the particular arrangement utilized for collecting and distributing the gas exhausted from the engine **21** would be determined by the use for which the engine is employed. In other words, it may be advantageous to rearrange the exhaust tubing such that a larger or smaller percentage of the exhaust is routed through the compressor **109**. It should also be noted that since the exhaust lines **105** are plastic tubing, a rearrangement of the lines for a different purpose is both simple and inexpensive.

In operation of the engine of the present invention, the engine **21** is started by energizing the solenoid valve **29** and any suitable starting device (not shown), e.g., a conventional electric starter as used on an internal combustion engine. Compressed gas from the full tank **23** flows through the line **25** and a variable amount of the compressed gas is admitted to the distributor **33** by controlling the regulator valve **31** through the linkage **33** and the operator actuated throttle linkage **35**. The compressed gas is distributed to each of the lines **37** which lead to the individual cylinders **20**. The compressed gas is admitted to each of the cylinders **20** in timed relationship to the position of the pistons within the cylinders by opening the valves **39** with the valve actuator **41**.

When it is desired to increase the speed of the engine, the operator moves the throttle linkage **35** which simultaneously admits a larger quantity of compressed gas to the distributor **33** from the tank **23** by further opening the regulator valve **31**. The timing of the valve actuator **41** is also advanced through the linkage **104**. Still further, as the speed of the engine **21** increases, the effective length of the rotating contact **83** (FIG. **4**) or **95** (FIG. **6**) increases thereby electrically contacting a wider portion of one of the stationary radial contacts **85** to cause each of the valves **39** to remain open for a longer period of each engine cycle to admit a larger quantity of compressed gas to each of the cylinders **20**.

As can be seen, the combination of the regulating valve **31**, the mechanical advance **104**, and the valve actuator **41**, combine to produce a compressed gas engine which is quickly and efficiently adaptable to various operating speeds. However, all three of the controls need not be employed simultaneously. For example, the mechanical advance **104** could be utilized without the benefit of one of the varying valve actuators **41** but the high speed operation of the engine may not be as efficient. By increasing the duration of each engine cycle over which each of the valves **39** remains open to admit compressed gas to each of the cylinders **20** as the speed increases, conservation of compressed gas during low speed operation and efficient high speed operation are both possible.

After the compressed gas admitted to the cylinder **20** has forced the piston **22** downwardly within the cylinder to drive the shaft **139** of the engine, the piston **22** moves upwardly within the cylinder **20** and forces the expanded gas out through a suitable exhaust valve (not shown) through the adapter plate **103** (if employed) and into the exhaust line **105**. The cool exhaust can then be collected in any suitable arrangement to be compressed and returned to the tank **23** or used for any desired purpose including use as a working fluid in an air conditioning system or as a coolant for oil.

When using the apparatus and method of the present invention to adapt a ordinary internal combustion engine for operation with compressed gas it can be seen that considerable savings in weight are achieved. For example, the ordinary cooling system including a radiator, fan, hoses, etc. can be eliminated since the compressed gas is cooled as it expands in the cylinder. In addition, there are no explosions within the cylinder to generate heat. Further reductions in weight are obtained by employing plastic tubing for the lines which carry the compressed gas between the distributor and the cylinders and for the exhaust lines. Once again, heavy tubing is not required since there is little or no heat generated by the engine of the present invention. In addition, the noise generated by an engine according to the present invention is considerably less than that generated by an ordinary internal combustion engine since there are no explosions taking place within the cylinders.

The principles of preferred embodiments of the present invention have been described in the foregoing specification. However, the invention which is intended to be protected is not to be construed as limited to the particular embodiments disclosed. The embodiments are to be regarded as illustrative rather than restrictive. Variations and changes may be made by others without departing from the spirit of the invention. Accordingly, it is expressly intended that all such variations and changes which fall within the spirit and the scope of the present invention as defined in the appended claims be embraced thereby.

What is claimed is:

1. An apparatus for operating an engine having at least one cylinder and a reciprocating piston therein comprising:

a source of compressed gas;

- distributor means connected with the source of compressed gas for distributing the compressed gas to the at least one cylinder;
- valve means for admitting the compressed gas to the at least one cylinder when the piston is in approximately a top dead center position within the cylinder;
- altering means for increasing the duration of each engine cycle over which the valve means admits compressed gas to the at least one cylinder as the speed of the engine increases; and
- exhaust means for exhausting gas as the piston subsequently approaches approximately the top dead center position.

2. The apparatus of claim **1** further comprising control means for controlling the amount of compressed gas admitted to the distributor means.

3. The apparatus of claim **1** wherein the valve means is a solenoid valve secured in an opening in the cylinder above the level of the piston at the top dead center position.

4. The apparatus of claims **1** or **2** further comprising means for advancing the timing of the valve means as the speed of the engine increases such that compressed gas is admitted progressively further before the top dead center position as the speed of the engine increases.

5. The apparatus of claim **4** wherein the means for advancing the timing comprises a mechanical linkage connected to an operator actuated accelerator linkage.

6. The apparatus of claim **1** wherein a portion of the gas exhausted through the exhaust means is compressed in a compressor driven by an output shaft of the engine and is returned to the source of compressed gas.

7. The apparatus of claim **1** wherein a portion of the gas exhausted through the exhaust means is used to cool transmission fluid for a transmission associated with the engine.

8. The apparatus of claim **1** wherein a portion of the gas exhausted through the exhaust means is used as a working fluid in an air conditioning system.

9. The apparatus of claim **6** further comprising first gearing means interposed between the output shaft of the engine and the compressor for increasing the speed at which the compressor is driven.

10. The apparatus of claim **6** further comprising clutch means attached to the compressor both for disengaging the compressor from the output shaft of the engine when a first predetermined pressure at the source of compressed gas is exceeded and for engaging the compressor with the output shaft of the engine when the pressure at the source of compressed gas drops below a second predetermined pressure.

11. The apparatus of claim **9** further comprising means for both disengaging the first gearing means when a predetermined speed of the engine is exceeded and engaging a second gearing means for driving the compressor at a speed slower than the first gearing means when the predetermined speed of the engine is exceeded.

12. The apparatus of claim **1** wherein the valve means is electrically actuated and wherein the altering means comprises:

- a rotating member timed with the at least one cylinder and arranged within a housing;
- first and second contacts arranged on a first end of the rotating member and on an inside surface of the housing, respectively;
- means for increasing the distance of the first contact from the rotational axis of the rotating member as the speed of the engine increases such that the first contact moves radially outwardly within the housing; and
- said second contact presenting a longer arc length to the first contact as the distance of the first contact from the rotational axis of the rotating member increases.

13. The apparatus of claim **12** wherein the rotating member comprises an arcuate arm and wherein the means for increasing the distance of the first contact comprises pivotally mounting a second end of the arcuate arm about the axis of rotation of the rotating member and spring means for biasing the first end of the arcuate arm towards a radially inward position whereby the first end of the arcuate arm pivots radially outwardly as the speed of the engine increases.

14. The apparatus of claim **12** wherein the rotating member is axially slidably received on a rotating shaft for co-rotation therewith, said shaft having splines with a radial component in the direction of rotation, and wherein the first contact comprises a flexible contact located on an upper surface of the rotating member, said flexible contact being biased against the inside surface of the housing which carries the second contacts whereby as the speed of the engine increases the rotating member is urged axially along the splined shaft towards the inside surface of the housing such that the flexible contact is forced radially outwardly along the inside surface.

15. The apparatus of claim **12** wherein the second contact comprises of radially extending conductor arranged on an upper inside surface of the housing, said conductor increasing in arc length as the conductor extends radially outwardly from a central portion of the housing.

16. An apparatus for adapting an internal combustion engine for operation with compressed gas, the internal combustion engine having at least one cylinder, a piston reciprocable within the at least one cylinder, intake and exhaust means disposed in the at least one cylinder, and a tapped hole in the at least one cylinder adapted to receive a spark plug, the apparatus comprising:

- a source of compressed gas;
- distributor means connected with the source of compressed gas for distributing the compressed gas to the at least one cylinder;
- valve means arranged in the tapped hole for admitting the compressed gas to the at least one cylinder when the piston is in approximately a top dead center position within the cylinder; and
- altering means for increasing the duration of each engine cycle over which the valve means remains open to admit the compressed gas as the speed of the engine increases.

17. An apparatus as in claim **16** further comprising first adapter plate means for supporting the distributor means above an intake manifold of the engine, which adaptor plate means allows ambient air to enter through the intake manifold.

18. The apparatus of claim **16** further comprising second adapter plate means for reducing the exit area of the exhaust means.

19. A method of operating an engine on compressed gas, said engine having at least one cylinder and a piston reciprocable therein comprising the steps of:

delivering compressed gas from a source to a distributor;

distributing the compressed gas to the at least one cylinder;

admitting compressed gas to the at least one cylinder through an intake valve when the piston is at approximately a top dad center position;

increasing the duration of each engine cycle over which compressed gas is admitted to the at least one cylinder as the engine speed increases; and

exhausting the remaining gas when the piston subsequently reaches approximately the top dead center position.

20. The method of claim **19** further comprising the step of controlling the amount of compressed gas which is delivered to the distributor.

21. The method of claim **19** further comprising the step of advancing the timing of the opening of the intake valve as the speed of the engine increases.

22. An apparatus for operating an engine having at least one cylinder and a piston reciprocable therein on compressed gas comprising:

a source of compressed gas;

distributor means connected with the source of compressed gas for distributing the compressed gas to the at least one cylinder;

electrically actuated valve means secured in an opening in the at least one cylinder for selectively admitting compressed gas to the at least one cylinder when the piston is in approximately a top dead center position; and

means for advancing the timing of the valve means as the speed of the engine increases whereby compressed gas is admitted progressively further before the top dead center position as the speed of the engine increases.

* * * * *

THE COMPLETE HUNTER™

THE COMPLETE GUIDE TO HUNTING

Basic Techniques for Gun & Bow Hunters



GARY LEWIS

REVISED EDITION

THE COMPLETE HUNTER™

THE COMPLETE GUIDE TO HUNTING

Basic Techniques for Gun & Bow Hunters

Gary Lewis

Creative Publishing
international

Minneapolis, Minnesota

***Gary Lewis** is an outdoor writer, speaker and photographer. He has hunted and fished in five countries on two continents and much of the American West. He is a past President of the* Northwest Outdoor Writers Association (NOWA) *and is Associate Editor for* Hunting the West *magazine. Lewis is the author or co-author of seven books, including Creative Publishing International's* Black Bear Hunting *with Lee Van Tassell. Four of his books have won NOWA's Excellence in Craft awards and he has received numerous awards for his newspaper columns and magazine articles. His stories have appeared in many prestigious outdoor magazines such as* Sports Afield, Rifle, Successful Hunter, African Sporting Gazette *and* Traditional Bowhunter. *He lives in Bend, Oregon.*

Creative Publishing
international

Copyright © 2008
Creative Publishing international, Inc.
400 First Avenue North
Suite 300
Minneapolis, MN 55401
Chanhassen, Minnesota 55317
1-800-328-0590
www.creativepub.com
All rights reserved

President/CEO: Ken Fund
VP/Sales & Marketing: Kevin Hamric
Publisher: Bryan Trandem
Acquisition Editor: Barbara Harold
Production Managers: Laura Hokkanen, Linda Halls

Creative Director: Michele Lanci-Altomare
Senior Design Managers: Brad Springer, Jon Simpson
Design Managers: Sara Holle, James Kegley
Book & Cover Design: Danielle Smith
Page Layout: Danielle Smith

Contributing Photographers: Phil Aarrestad, Grady Allen, Charles Alsheimer, Erwin Bauer, Craig Blacklock, Les Blacklock, Tom Brakefield, Browning, Glenn D. Chambers, Tim Christie, Herbert Clarke, Daniel J. Cox, Gary Kramer, John Ebeling, Michael Francis, Michael Furtman, Eric J. Hansen, Larry D. Jones, Gary Kramer, Lon E. Lauber, Gary Lewis, Tom Mangelson, Bill Marchel, Tom Martinson, Jay Massey, Worth Mathewson, Bill McRae, Wyman Meinzer, Arthur Morris/Birds as Art, William H. Mullins, Doug Murphy, Scott Nielsen, Jerome B. Robinson, Lynn Rogers, Leonard Lee Rue, III, Dwight R. Schuh, Ron Shade, Jerry Smith, Dale C. Spartas, Ron Spomer, Norm Strung, Syl Strung, Ken Thommes, Charles Waterman, Chuck Wechsler, Ron Winch, James Zacks, Gary Zahm
Contributing Illustrator: Jon Q. Wright

Library of Congress Cataloging-in-Publication Data
Lewis, Gary
The complete guide to hunting : basic techniques for gun and bow hunters / Gary Lewis.
p. cm.
ISBN-13: 978-1-58923-373-7 (hard cover)
ISBN-10: 1-58923-373-5 (hard cover)
1. Hunting. I. Title.
SK33.L49 2008
799.2--dc22 2007033514

Printed in China

10 9 8 7 6 5 4 3 2 1

All rights reserved. No part of this work covered by the copyrights hereon may be reproduced or used in any form or by any means—graphic, electronic or mechanical, including photocopying, recording, taping of information on storage and retrieval systems—without the written permission of the publisher.

CONTENTS

INTRODUCTION 4

Chapter 1

ALL ABOUT WILD GAME . . . 6

Three Senses 8
Wildlife Habitat 12

Chapter 2

HUNTING SKILLS AND EQUIPMENT 20

The Hunting Rifle. 22
Rifle Ammunition. 24
Sights 26
Sighting in Your Rifle 28
Shooting a Rifle. 30
Shotguns 32
Bowhunting 35
Muzzleloaders 40
Hunting Safety 42

Chapter 3

HUNTING STRATEGIES . . . 44

Scouting for Game 46
Still-hunting 48
Stand-hunting. 49
Stalking. 50
Driving 52
Flushing 53
Hunting Dogs. 54
Float-hunting 55
How to Find Downed Game. 56

Chapter 4

HUNTING BIG GAME. 58

White-tailed Deer 60
Mule Deer. 68
Black-tailed Deer. 71
Elk 74
Moose 78
Pronghorn. 80
Black Bear 82
Wild Boar 84

Chapter 5

HUNTING SMALL GAME . . .86

Cottontail Rabbit 88
Jackrabbit 92
Snowshoe Hare 93
Gray Squirrel. 94
Fox Squirrel. 95
Prairie Dog 99
Ground Squirrel 100
Raccoon 101
Coyote 103

Chapter 6

HUNTING UPLAND GAME BIRDS 106

Ring-necked Pheasant 108
Bobwhite Quail. 114
California Quail 117
Gambel's Quail 118
Mountain Quail 119
Scaled Quail 120
Ruffed Grouse. 121
Sharp-tailed Grouse. 124
Sage Grouse. 125
Chukar Partridge. 126
Hungarian Partridge 127
Wild Turkey 128
Mourning Dove 135
Woodcock 137

Chapter 7

HUNTING WATERFOWL . . .138

Puddle Ducks 142
Diving Ducks 146
Geese. 149

INDEX. 155

INTRODUCTION

Whether the hunt takes you after Rocky Mountain elk along the western skyline or into a Carolina swamp behind a pack of beagles, the chase offers a unique challenge. Rabbit, deer, elk, moose or bear, whatever the quarry, the hunter must outsmart a wild animal with a better knowledge of its environment and keener senses.

This challenge, along with the camaraderie of the hunt, accounts for the sport's tremendous popularity. And a successful hunter can enjoy a year-round supply of lean, nutritious meat.

The Complete Guide to Hunting is intended to make the reader a better hunter. Each section of the book deals with a different facet of the sport. Together, they will help you develop the skills and savvy needed to consistently bag wild game.

The first chapter, "All About Wild Game," provides an understanding of wildlife behavior and helps you recognize good habitat. By knowing how animals sense danger, react to threats and find food, water and cover, you can improve your chances of being in the right spot at the right time.

Chapter 2, "Hunting Skills and Equipment," provides all the information needed to select rifles, shotguns, bows and muzzleloaders. Learn how to choose the best ammunition for the game and how to become a proficient shooter. This chapter goes far beyond the basics, explaining complex principles of bullet and shot performance with descriptive photos and easy-to-understand charts.

The third chapter, "Hunting Strategies," teaches how to plan the hunt and how to scout a potential spot to make sure it holds game. This chapter details the most popular hunting techniques, from stalking to driving. Learn how to tailor a hunting strategy to the terrain and time of day. It also provides valuable tips for recovering game.

The final four chapters acquaint you with North America's most popular game animals. Hundreds of informative how-to photos, along with a fact-filled text, give all the information needed to locate, pursue and bag each of these species.

Astounding photography puts you in the scene. Face-off with a huge bull moose; walk a fencerow and see a ring-necked pheasant burst from cover at your feet; experience the nerve-wracking anticipation of waiting for a wild turkey to strut close enough for a shot.

The hunting techniques found in this book are those considered most effective by the nation's top hunting authorities. Hunting regulations and legal equipment differ in every state and province, so it is possible that some of the procedures described are illegal in your area. Baiting bears, for instance, is a popular method in some states, but is against the law in others. Check the local hunting laws before going afield.

In addition to the proven high-percentage hunting methods, this book also reveals dozens of little-known but effective tips that help the experts take their game. You will learn how to attract diving ducks by waving a black flag and how to imitate a scolding squirrel by clicking quarters.

This book is a unique blend of straightforward writing and captivating photography. Never before has so much how-to hunting information and so many dramatic wildlife photographs been packed into one volume. *The Complete Guide to Hunting* is sure to make your days afield more enjoyable—and more successful.

Chapter 1

ALL ABOUT WILD GAME

From the moment of birth, a game animal faces threats from predators, weather, disease and competition. Only the strongest and wariest live long enough to reproduce. In this way, nature selects the best breeding stock to ensure that the species thrives.

All game animals have the potential to produce many more offspring than the habitat can support. Reproductive rates are high among small game and upland birds. High mortality rates are nature's way of keeping game populations in check. When too many animals survive, the population explosion causes disease, stunted growth and eventually starvation.

Among most upland birds, waterfowl and small game, 60 to 80 percent of the population dies each year. Individuals over one year old comprise only 20 to 40 percent of the fall population. Because young animals are more abundant and because they lack the savvy of older animals, they make up the bulk of the hunter's bag.

Regulations are based on the concept that game can be harvested as long as breeding stock remains to produce another crop of similar size the following year. Seasons for small game, waterfowl and upland birds are usually long and bag limits generous. Liberal regulations are possible because of the high reproductive rates of these animals. Regulations for big game are stricter because the animals produce fewer young.

Resource agencies monitor game populations and set regulations to achieve the desired harvest. Scientific wildlife management has eliminated the problems of mass slaughter associated with market hunting in years past. In fact, some of the continent's most popular game species, such as white-tailed deer and wild turkey, are more numerous today than at any time in recorded history.

THREE SENSES

Game animals have an amazing ability to elude hunters. Their keen senses of sight, smell and hearing enable them to detect danger far in advance and take evasive action. Many animals also possess unique survival adaptations that far exceed the capabilities of humans.

SIGHT. Game birds have color vision that may surpass that of humans. Their retinas have more color receptors, or cones, than most other game animals. Colored oil droplets in the retina work like a camera filter, enhancing the visibility of certain hues. The cones also give them excellent visual acuity, or sharpness.

Game mammals have retinas that contain mostly light receptors, or rods. The rods enable them to see well in dim light. The vision of most game mammals is not as sharp as that of birds or humans and they have limited color vision, if any.

Most mammals have poor accommodation capabilities; they cannot change the shape of their lenses to focus on both close and distant objects. As a result, images are often fuzzy. This explains why many types of big game animals do not seem to notice a stationary hunter.

SMELL. Game mammals collect most of the information about their environment through their sense of smell. In a laboratory test, rabbits were able to detect the smell of acetone at a concentration of only 1/50 of that detectable by humans. Hunters who pursue big or small game should try to approach from downwind to keep their scent from drifting toward the animals.

Game birds have a poor sense of smell. In one study, wild turkey were given two piles of grain, one of which contained a highly repulsive scent. The birds paid no attention to the odor, feeding equally at each pile. To a bird in flight, a highly-developed sense of smell would be of little value because odors produced by predators quickly sink to the ground.

HEARING. Because game birds lack external ears and because their ears have fewer small bones than those of mammals, they are not as well equipped for detecting faint sounds. The range of pitches they can recognize is slightly less than that of humans and substantially less than that of many game mammals.

In a test of their ability to detect various pitches, mallards recognized sounds up to a frequency of 8,000 cycles per second (cps). Humans detected higher pitched

FACTORS THAT AFFECT GAME POPULATIONS

Big game populations can reach high levels despite low reproductive rates. Predators take only an occasional young animal. In areas with good habitat and little hunting pressure, herds may grow so large that food shortages result. Hunting regulations are set to control the harvest, yet prevent overpopulation.

Game populations tend to remain stable if the habitat is not disturbed and hunting pressure is regulated. In a study of a ruffed grouse population in New York state, there were 174 adult grouse at the beginning of the breeding season. These birds produced 935 fertile eggs. As the months passed, 24 adult grouse succumbed to predators and disease, 26 to hunting and 54 to severe weather. By the following spring, 70 birds remained to breed again. Of the 935 eggs, 374 were destroyed by predators. The rest hatched, but 337 chicks were killed by predators and disease. Hunters claimed 38 of the young birds, 81 perished in winter storms and 105 survived to the breeding season. These first-year breeders, combined with the 70 second-year birds, resulted in a total of 175 adult grouse, nearly identical to the breeding population of the previous year.

sounds, up to 20,000 cps and raccoon heard sounds of up to 85,000 cps.

SPECIAL ADAPTATIONS. The process of evolution has provided almost every species of game animal with some unique physical feature or ability that gives it an advantage over other animals. These adaptations enable the species to survive the threats posed by predators, including humans.

Many of these adaptations are so foreign to humans that we fail to consider them when hunting. For example, a mallard can stay submerged for as long as 16 minutes. It accomplishes this seemingly impossible feat by slowing its heart rate by more than 50 percent while underwater. This substantially reduces its oxygen needs.

Many a hunter has winged a duck, marked it down, spent 5 to 10 minutes looking for it, then given up in frustration. After the hunter returns to the blind, the live duck reappears in the very spot it went down.



Hunters who understand the senses and special adaptations of the game they pursue stand the best chance of success.

COMPARING HUMAN AND GAME SENSES

	Vision	Hearing	Smell
Human	*Good*	*Good*	*Fair*
White-tailed Deer	*Fair*	*Excellent*	*Excellent*
Cottontail Rabbit	*Good*	*Excellent*	*Good*
Wild Turkey	*Excellent*	*Excellent*	*Poor*
Ring-necked Pheasant	*Good*	*Good*	*Poor*
Mallard duck	*Excellent*	*Good*	*Fair*



Color vision exists in some big game. In one study, white-tailed deer were rewarded with a drink from a tube when a red light went on; a white light gave no reward. Even though the lights switched between two tubes, deer consistently made the right choice.



Night vision in nocturnal animals is enhanced by the tapetum lucidum, a layer of reflective pigment below the surface of the retina. Light passes through the receptors on the retina's surface, hits the tapetum, then bounces back to stimulate the receptors again.



Internal ears of birds do not collect sounds as efficiently as exposed ears. And because the ears are close together, they are not as well suited to locating the direction of sounds.



Exposed ears gather sound waves. They also help an animal pinpoint the source of a sound by the difference in the time it takes for the signal to reach each ear.



Movable ears enable mammals to locate sounds from any direction. While one ear detects a sound from one direction, the other picks up a sound from a different source.

Positioning themselves below the crest of a wind-swept ridge enables some big game to smell anything approaching from above. They watch for anything coming from below. Scent glands warn other animals of danger. When a mule deer faces a threat, metatarsal glands on the hind legs produce an odor that alerts other herd members.

Freezing in position and pressing its body to the ground (right) reduces the amount of scent an animal gives off. Some game birds also compress their feathers so less scent escapes.

OTHER SPECIAL ADAPTATIONS



Flared rump hair alerts other animals to a threat. By flaring its rump hairs to the side, the pronghorn can greatly increase the size and visibility of its white rump patch.



Camouflage enables game animals to escape detection by predators. The woodcock, for example, blends in so well with the vegetation that it can hide in open terrain with no overhead cover.



Genetic changes may result from hunting. The tendency to run has increased among pheasants. Many hunters attribute this to the fact that fliers get shot, leaving runners to breed.

WILDLIFE HABITAT



The best wildlife environment has a variety of plant life that provides food and cover. A mixed plant community generally supports more species and higher numbers of game than an expanse of the same type of vegetation.

Good habitat is the key to an abundant wildlife population. To survive and thrive, a game animal needs food, shelter cover, room to escape and water. A reliable supply of drinking water is important, although some animals find sufficient moisture in their foods.

Most game species find the necessary plant variety along the edge between two vegetative types. Where a forest meets a marsh, for instance, the mixture of grasses, berry bushes, low-growing leafy plants and young trees provide an excellent supply of food and cover. The area where the two types of vegetation meet usually holds more kinds and higher numbers of game than either type by itself. Hunters call this "edge habitat."

Another factor that influences plant variety is succession. For example, after a forest fire or logging operation, the bare ground almost immediately begins to grow grasses, shrubs and trees. As the trees grow taller, they form a canopy that shades the forest floor. As the canopy grows denser, shrubs and grasses disappear because of the lack of sunlight. Eventually, only large trees remain. These changes in the plant community invariably affect the type and amount of game the habitat can support.

Succession begins after trees have been removed. New grasses, shrubs and trees support animals like white-tailed deer. As time goes on, trees grow taller, yet enough sunlight penetrates to promote a dense growth of underbrush ideal for animals like ruffed grouse. As the trees mature and shade the forest floor, underbrush disappears and the forest becomes best suited for animals like black bear.

Wildlife managers often set back the process of succession by periodically cutting or burning forested areas to promote growth of new vegetation. These techniques enable them to increase the production of important game species.

In most agricultural areas, the trend is toward less habitat variety. Many farms once had small, weedy crop fields combined with brushy fence lines, unmowed roadside ditches, large wetlands and dense groves. Today's clean farms have vast acreages of crops unbroken by fence lines, wetlands or trees. Even roadside ditches are often mowed for hay. These intensive agricultural practices severely reduce or eliminate populations of farmland game like pheasants and quail.

Cover Requirements

Escape cover is vital to the survival of almost every game species. Wildlife also needs other kinds of cover for bedding, loafing, protection from the elements and producing young.

A ring-necked pheasant, for example, often escapes from hunters by hiding in dense brush. It may roost in open grasslands, loaf along the grassy margin of a crop field and burrow under a clump of slough grass during a storm. Experienced hunters know where to look at different times of the day and under different weather conditions.

ESCAPE COVER. Predators pose a constant threat to most game animals. Wildlife must learn to contend with these threats or perish. Most elude predators by hiding in dense cover; others scamper to a burrow or den; in light cover, some crouch motionless or rely on camouflage.

BEDDING COVER. Some game animals bed in dens or burrows or roost in trees. Others prefer thick grassy cover for bedding sites. The grass offers concealment and warns animals of danger. Even the stealthiest predator finds it difficult to move through thick grass without making some noise.

Adequate shelter cover is crucial to ensure winter survival. Bobwhite quail roost on the ground to exchange body heat. They may be found in low-growing cover on agricultural lands and around farm equipment on old homesteads.

WHERE TO FIND EDGE HABITAT

Forest clearings, like powerline corridors, logging roads and logged or burned areas, usually hold more game than the forest interior. Marshes or grassy meadows in the forests also attract wildlife.

Farmlands abutting forests or brushlands have an abundance of edge habitat. Ample sunlight reaches the forest or brushland margin, resulting in a lush growth of seed- and berry-producing plants.

Mountain slopes often have edge habitat where grassy foothills meet mid-elevation hardwoods; where hardwoods grade into high-elevation conifers; and at the treeline, where conifers end and lichens begin.

LOAFING COVER. Most game animals feed in early morning and late afternoon, then loaf during mid day. Loafing cover is thick enough so that animals are not easily visible, but not so dense that they cannot see.

COVER FROM THE ELEMENTS. All game animals need some type of dense cover to insulate them from extremely cold temperatures. They also use cover as shelter from precipitation, strong winds and the hot summer sun.

Many birds and small mammals crawl under vegetation to escape harsh winter storms. Some burrow under the snow, creating a cozy enclosure. The animal's body heat may keep the temperature as much as 50 degrees warmer than the outside air. Big game animals may bed under conifer limbs in a heavy rain or on a cold night. The boughs shed precipitation and act like a blanket to slow the loss of body heat into the atmosphere.

Abandoned buildings serve as windbreaks for many types of game. Old farmsteads often have discarded machinery, brush piles, tall weeds and evergreen groves that offer cover from the elements.

PRODUCTION COVER. Predators and adverse weather quickly wipe out nesting adults and newly produced young unless they have good production cover. This type of cover may not hold animals during the hunting season, but it often serves as an indicator of high game populations.

BASIC COVER TYPES



Open timber (left) is used as loafing cover by some types of big game. Small game and upland birds generally loaf in areas with denser ground cover.

Thickets make good escape cover for almost every type of wild game. Brush breaks up the animal's outline and offers shade.

Tall grass makes excellent bedding cover. It provides a comfortable resting spot and offers animals camouflage from predators.

Moderately dense vegetation provides nesting cover for many upland birds. They prefer cover open enough so they can see and escape if necessary.



Glass for moose along forest edges, in willow swamps or near other feeding areas. Get to our vantage point early, so you can complete your stalk before the animals retreat to bedding areas.

Fertile croplands offer a good food supply. But expanses of corn and other row crops with little cover support few birds.

Look for early-season ringnecks scattered throughout crop fields, along grassy field edges and in brush patches.



In late season game concentrates in heavy cover like brush patches and farm groves.

Food and Water Needs

Hunters who understand the feeding habits and water needs of their quarry can better predict its daily movements. This makes it easier to select a good hunting location.

An elk may travel miles (km) to find food or quench its thirst, but most wildlife needs food and water in close proximity to cover. If an animal has to travel a long distance across open terrain to fulfill these basic needs, it is more visible to predators.

FOOD. Most game animals can adapt to a wide variety of foods. Researchers have found that bobwhite quail consume over 1,000 different foods including seeds, plants, nuts and insects.

Despite their ability to use such a wide range of foods, most animals select items that they can digest easily and that are high in proteins and calories. They seem to instinctively know which foods are most nutritious. In one study, squirrels gained weight when fed a diet consisting solely of white oak acorns. But they lost weight when fed acorns of red oak. In nature, squirrels commonly feed on acorns of white oak, but ignore those of red oak.

Like humans, game animals must have vitamins and minerals in their diet. Most animals obtain these vital elements from their food and water, but some need additional salt. They frequent springs and natural soil deposits with high salt contents. Many birds pick up grit not only to grind their food, but to provide needed minerals.

WATER. Birds generally require less water than mammals, because they can reuse water as it passes through their digestive tract. Gambel's quail can go a month or two without visiting a water hole. Pronghorns, on the other hand, need water each day.

Many game species can survive in areas with no lakes, streams or other sources of surface water. They obtain water from foods or dew.



A deer's diet varies throughout the year. Deer feed on twiggy browse, forbs (broad-leafed plants), grass, fruit, nuts, and moss. On scouting trips, identify and anticipate the food sources available during the season.

FOOD SOURCES

Natural foods are the mainstay in the diets of most game animals. A good supply of winter food is especially critical. Survival rates are generally low in years when winter food is scarce.

Food plots planted by wildlife agencies provide an additional source of food during winter, when natural food may be difficult to find. Some farmers leave a few rows of corn to sustain wildlife on their land.

Waste grain remains after farmers harvest their crops. It provides a temporary food supply for many animals like geese, ducks, pheasants and deer. They gather in large numbers to take advantage of this easy source of food. Waste grain may provide food throughout the winter where fields are left unplowed.

Common Types of Habitat

Some game animals can adapt to almost any kind of habitat. White-tailed deer, for instance, live in places as diverse as Florida swamps, southwestern deserts and river valleys of the Pacific Northwest. But most types of wildlife have more specific habitat requirements.

When hunting in unfamiliar territory, it pays to spend a good deal of time scouting. Conditions may not be right for spotting game, but you can always recognize good habitat.

Many types of wildlife have cover, food or water needs so specific that merely finding a broad habitat type is not enough. For example, moose prefer young conifer-hardwood forests. But within these forests, they seldom stray far from stream banks, lakeshores or willow bogs, their main feeding sites. Sage grouse live in semi-arid brushlands, but rarely venture more than 1.2 mile (1.93 km) from a water hole or other source of water.

As the seasons change, many species of game migrate to different types of habitat. In late fall, waterfowl leave northern marshes en masse. Most winter in the South, resting and feeding on large lakes and in crop fields. As winter approaches, some types of mountain wildlife migrate to lower elevations, wintering in grasslands that offer more food and a less severe climate.

Hunting pressure may also force animals from their preferred habitat. Elk favor grassy mountain meadows, but when hunters begin to invade their territory, they retreat to higher, more rugged terrain where a person on foot could not follow. Waterfowl abandon many small lakes and ponds once the season opens. They seek refuge in the open water of large lakes and reservoirs.

In agricultural areas, wildlife may have to use other cover once crops are harvested. Pheasant hunters usually find the birds in crop fields during early season. But when the crops are removed, the birds move to permanent heavy cover like cattail swamps and woodlots.

Throughout this book, I identify the habitats most commonly associated with each species of game. Following are the major habitat types to which I refer.

WATER SOURCES

Surface water is a requirement for many species. Popular watering sites (left) include streams, lakes, human-made ponds and natural springs.

Succulent foods, like prickly pear cactus, provide water in arid climates. Rabbits and grouse often get water from grasses and buds.

Frost or dew also provides water in dry climates. To use this water source, animals must feed in early morning before the plants dry off.

HABITAT TYPES



Grasslands usually have grasses growing in combination with broad-leaved green plants or forbs. The height of the vegetation varies from less than 18 inches (46 cm) in arid habitats to 10 feet (3 m) where the soil is moist.



Coniferous forests have dense stands of needle- or scale-leaved evergreen trees that provide some cover. Needles that fall to the ground decompose slowly, forming acidic soil which produces few wildlife foods.



Brushlands have shrubs mixed with grasses and forbs; some have widely-spaced trees. The vegetation may be so thick that it is impenetrable. Brushlands are often an intermediate stage between grassland and forest.



Deciduous forests, also called hardwood forests, contain trees that lose their leaves in the fall. The leaves rot quickly, forming rich humus. Buds, nuts, shrubs and green plants provide food for wildlife.



Mixed forests have a blend of conifers and hardwoods. The combination of a good food supply and abundant cover enables these forests to produce more wildlife than coniferous or deciduous forests alone.



Wetlands have pockets of open water and dense stands of emergent vegetation like cattails and cane. The open water produces food for waterfowl and the fringes provide cover for a wide variety of game.

Semi-arid deserts contain shrubs, grasses and cactuses and may have some trees. They support more types of game than arid deserts, which have only scattered shrubs and cactuses.

Agricultural lands with a variety of cover types support a diversity of wildlife. The fertile soil produces abundant food and larger animals than most other types of habitat.

Chapter 2

HUNTING SKILLS AND EQUIPMENT

When you choose the path of the hunter, you adopt a lifestyle and an outlook uniquely suited to the chase. It is a pursuit that quickens the heart and sharpens the focus. And the life skills and attitudes formed cross over into other facets of life. Hunting skills are gained over the course of several seasons and there is always more to learn, keeping you fit, vital and interested.

Gear to fit the small game hunter differs from that suited to the waterfowler. And the way of the traditional bowhunter is widely divergent from the style of the rifleman. Yet all share a bond and an ethos.

The complete hunter is versed in many skills and knows the operating systems and the nomenclature of a variety of tools. Most learn to hunt with a .22 rifle and then graduate to a centerfire rifle and shotgun. With knowledge of rifle and shotgun comes a passing acquaintance with ammunition and ballistics.

Some hunters opt to shoot a bow. The traditional bow (recurve or longbow) is a good place to start to learn the mechanics of archery. Next comes the compound bow, with its unique technical features and shooting style.

Hunters may opt to hunt with a muzzleloader rifle for a variety of reasons. It too comes with the need to gather knowledge and insight. There are several ignition systems, various powders and an array of projectiles designed to fit specific situations.

There is a lot to learn, but the process is rewarding. Along the way, the hunter faces challenges, but also finds satisfaction, building on successes in the field. Soon, success begins to show with meat on the table and trophies in the living room.

THE HUNTING RIFLE

A rifle that suits your style of hunting greatly increases your chances of success. When selecting a rifle, consider its action, weight and caliber.

ACTION. The action of a rifle refers to the design of the mechanism for chambering ammunition and ejecting spent cartridges. Single-shot actions, like the falling block, are extremely reliable because they have few moving parts. Their rigid mechanisms hold the cartridge firmly, resulting in a high degree of accuracy. These rifles must be reloaded after each round is fired, so they teach shooters to make the first shot count.

Repeating actions hold several cartridges in the magazine, making it possible to fire more than one shot without reloading. Like single shots, bolt actions have a rigid design and few moving parts. Many hunters consider the bolt action to be the most accurate and reliable rifle. Lever, pump and semi-automatic actions are designed for faster firing. You may need a quick second shot if you fail to kill the animal or if a branch deflects your bullet. But fast-action rifles have more moving parts, increasing the chance of mechanical failure, especially in cold weather or when dirt gets into the action.

WEIGHT. Rifles commonly weigh between 6 and 9 pounds (2.7 and 4 kg) without cartridges, slings or scopes. The recoil or kick, of a rifle depends mainly on its weight and its cartridge/caliber combination. Within a given combination, a heavy rifle has the least recoil, because the weight absorbs much of the energy that would otherwise be transmitted to your shoulder. Heavy rifles are easiest to hold steady and generally result in more accurate shots. Light rifles are easier to carry over a long distance.

The term carbine denotes a light rifle with a short barrel. Some hunters prefer carbines when hunting in heavy cover, where a longer rifle would tend to catch on brush or tree limbs.

CALIBER. The caliber of a rifle refers to the diameter of the barrel opening or bore. Caliber is measured in hundredths or thousandths of an inch or in millimeters. Hunters use rifles as small as .17 caliber for small animals and rifles up to .458 caliber for big game. Many rifle models are available in a choice of several calibers. Within a particular model of bolt action there may be fifteen different calibers.





Popular actions include: (1) falling block and (2) lever actions, which chamber and eject cartridges by means of a lever under the trigger guard; (3) bolt action, in which the cartridge locks in place by moving the bolt forward and downward, much like a door bolt; (4) pump or slide action, which chambers and ejects by sliding the forearm back and forth; (5) semi-automatic or autoloader action which chambers and ejects cartridges automatically after each shot. The action is powered by gases from the burning powder or by the recoil.

Hunters are often confused by traditional caliber designations. A .30-06 rifle has a 0.3-inch-diameter (7.6 mm) bore. The 06 refers to 1906, the year the rifle was introduced. A .30-30 rifle also shoots a .30 caliber bullet. The bullet was originally propelled by 30 grains of smokeless powder. To further complicate the matter, some caliber designations do not refer to the diameter of the bore. For example, the bore of a .308 Winchester rifle does not measure 0.308 inch (7.8 mm). The .308 refers to the groove diameter or the diameter to the outside of the rifling grooves. The bore diameter is only 0.3 inch (7.6 mm).



RIFLE AMMUNITION

A hunter's choice of ammunition depends mainly on the size of the animal hunted and the distance at which it may be encountered.

To determine the ammunition best-suited for the game, consult a ballistics table. Most ammunition catalogs contain ballistic information including bullet energy, muzzle velocity and drop, all at different ranges.

A bullet's hitting power, or energy, is determined by its weight and velocity. The heavier and faster the bullet, the more energy it delivers to the target. At normal shooting ranges, a light, fast bullet generally delivers as much energy and kills as effectively as a heavier but slower bullet. Hitting power is measured in foot-pounds (Newton-meters).

Muzzle velocity or bullet speed is measured as distance traveled per second. The faster the bullet is, for a given weight, the more energy it carries. It also flies flatter. When comparing bullets of the same size, the more powder the case holds, the more velocity a bullet has. The size of the brass case affects how much powder is behind the bullet.

The bullet's performance is affected by its size, weight and shape. The bullet's size or diameter is referred to as its caliber. This diameter corresponds to the diameter of the rifling in the gun. Caliber is measured in decimal fractions of an inch, i.e., .300 or .30 is a 30 caliber. Some calibers are expressed in millimeters. So a 7 mm is approximately a .280; 6 mm is a .240; and 7.5 mm is approximately a .300.

Bullet weight is measured in grains.

The shape of a bullet determines its friction or resistance in the air, affecting its trajectory or flight path. A long, thin, streamlined pointed bullet retains its velocity at longer ranges better than a short, stout bullet. So the longer bullet has a flatter trajectory. Trajectory is also affected by the bullet's velocity. A fast bullet flies flatter than a slow one.

The construction of a bullet also determines its ability to penetrate upon impact. The bullet should mushroom on impact and not break apart. Mushrooming transfers all the bullet's energy into the target.

Certain ammunition shoot better in your rifle; each gun is a little different. Today's factory loads can perform up to the highest standards. Try different brands and loads until you find a particular cartridge that meets your needs and with which you can shoot tight groups.

Never use ammunition other than that recommended for the rifle by the manufacturer. The result could be a damaged rifle and serious injury. The correct cartridge designation for the rifle is stamped on the barrel next to the receiver or chamber.

Center-fire cartridges (far left and below) consist of: a brass case; a primer containing a highly explosive compound that ignites when struck by the firing pin; powder, which is ignited by the priming compound; a lead bullet, which may have a copper-zinc jacket to control the bullet's expansion. With rimfires (near left), the firing pin strikes the edge of the rim, igniting the priming compound.





Cartridge types include: (1) .22 Long Rifle 40 Grain, (2) .222 Remington 50 Grain, (3) .243 Winchester 100 Grain, (4) .270 Winchester 130 Grain, (5) 7 mm Remington Magnum 150 Grain, (6) .30-30 Winchester 170 Grain, (7) .30-06 Springfield 150 Grain, (8) .300 Winchester Magnum 180 Grain, (9) .375 H&H Magnum 270 Grain.



Bullet styles include (1) pointed, streamlined for high velocity and flat trajecto-ry. (2) Pointed boat tail has a tapered base to reduce drag even more. (3) Hollow points mushroom rapidly, but no faster than (4) flat and (5) round points, often used in rifles with tubular magazines. Their blunt points do not detonate cartridges ahead of them, but result in relatively slow flight and short range. (6) Mushroomed bullet shows expansion.

TYPE OF CARTRIDGE (not actual size)	**Muzzle Velocity (in fps)**	**ENERGY (in foot pounds)**				**TRAJECTORY**				
		100 yds	**200 yds**	**300 yds**	**400 yds**	**100 yds**	**150 yds**	**200 yds**	**300 yds**	**400 yds**
.22 Long Rifle 40 Grain	1255	92	—	—	—	0.0	–11.5	—	—	—
.222 Remington 50 Grain	3140	752	500	321	202	+2.2	+1.9	0.0	–10.0	–32.3
.243 Winchester 100 Grain	2960	1615	1332	1089	882	+1.9	+1.6	0.0	–7.8	–22.6
.270 Winchester 130 Grain	3060	2225	1818	1472	1180	+1.8	+1.5	0.0	–7.4	–21.6
7 mm Remington Magnum 150 Grain	3110	2667	2196	1792	1448	+1.7	+1.5	0.0	–7.0	–20.5
.30-30 Winchester 170 Grain	2200	1355	989	720	535	+2.0	0.0	–4.8	–25.1	–63.6
.30-06 Springfield 150 Grain	2910	2281	1827	1445	1131	+2.1	+1.8	0.0	–8.5	–25.0
.300 Winchester Magnum 180 Grain	2960	3011	2578	2196	1859	+1.9	+1.6	0.0	–7.3	–20.9
.375 H&H Magnum 270 Grain	2690	3510	2812	2228	1747	+2.5	+2.1	0.0	–10.0	–29.4

Ballistics tables help determine the effective killing range of the cartridge and bullet drop at various ranges. This table lists muzzle velocity and the energy in foot-pounds delivered at ranges from 100 to 400 yards (91 to 364 m). As a rule, use a cartridge with at least 900 foot-pounds (1,220 N-m) to kill a deer, 1,500 (2,031) for an elk and 2,100 (2846) for a moose. Trajectory figures show how far the bullet strikes above (+) or below (-) the point of aim at ranges from 100 to 400 yards (91 to 364 m).

SIGHTS

The sighting system you use is as important as the rifle and ammunition. Some hunters spend as much for a rifle scope as they do for the rifle itself.

Many rifles come with iron sights. To aim, center a post at the end of the barrel in a notch or peephole in the rear sight. Iron sights are inexpensive, lightweight, durable and best-suited for short-range shooting.

For more accurate, precise shooting or for shots at longer distances, hunters prefer telescopic sights or scopes. A scope consists of a metal tube containing a system of lenses that magnify the target. The reticle, a network of lines or crosshairs inside the scope, enables you to aim precisely. The optics allow you to focus your eye on the reticle and target at the same time, so you can aim quickly. Scopes are not as durable as iron sights and are easier to knock out of adjustment.

Scopes vary in magnification power, from lx, which magnifies the target 1 time, to 12× or more. Fixed power scopes have one magnification power. Variable power scopes allow you to change the magnification with the twist of an adjustment ring. Most hunters use scopes ranging in power from 2× to 9×. Low-power scopes work best for close-range shooting. They have a larger field of view, making it easy to find your target. High-power scopes narrow the field of view, but help you see a distant animal.

A scope is attached to the gun using mounts or bases and rings. Whatever the mounting system, it must fit the scope, attach solidly to the gun and be adjusted to provide enough distance between the scope and your eye. Scopes should be at least 3 inches (7.6 cm) away from your eye, when the gun is shouldered, to allow for clearance when the gun recoils.

Most manufacturers offer a selection of special-purpose scopes designed specifically for shotguns and muzzleloaders.



Four-plex reticles have wires that are thick toward the outside. These wires stand out against the background and draw your eye to the target. The thin crosshairs enable you to aim precisely, without obscuring the animal.



Open sights have a blade or post, which must be centered in the notched rear sight. They are the most difficult of the sights to align and the rear sight covers up part of the target.



Peep sights require you to center the target in a hole in the rear sight, then place the bead directly on the animal. Hunters prefer large peep-holes so they can see most of the target.



Crosshair reticles work best for long-range shooting. The fine wires provide a precise aiming point and cover little of the target. But the wires may be difficult to see in dim light.

SIGHTING IN YOUR RIFLE

Every season, hunters miss their chance at a trophy because their rifles were not sighted in. Many people think that bore-sighting is sufficient. It is not. A bore-sighted rifle may shoot 20 inches (50.8 cm) or more from point of aim. Before hunting, take several practice sessions with your hunting ammunition.

You can sight in most easily at a shooting range. Most ranges have bench rests and sandbags to provide a steady rest and minimize human error. If sighting in your rifle in the field, make sure you shoot into a solid backstop.

To shoot accurately, take a deep breath, exhale halfway, then hold your breath as you squeeze the trigger. Do not jerk the trigger as you shoot.

Sights on a new rifle may be so far out of adjustment that you miss the target completely. To solve this problem, bore sight your rifle. Look directly through the bore of the bolt or falling block action. You cannot look directly through the bore of most other actions, so you must use a bore-sighting tool.

You can also rough-sight your rifle by simply aiming at a close target through the sights, firing, then making any adjustments needed to hit the bull's-eye.

Once you have rough-sighted at 25 yards (23 m), back off to 100 yards (91 m). Continue to fine-tune the sights until you can center the shot group on the bull's-eye. If you plan to shoot at longer ranges, sight in a few inches (cm) high at 100 yards. Then try a few long-range shots and make any necessary adjustments.

Always hunt with the same type of ammunition you used to sight in. Changing brands or bullet weights often makes it necessary to realign your sights.

Rest the forearm and butt stock on sandbags when sighting in. Do not support the barrel; the result will be inaccurate shooting. Hold the stock firmly against your shoulder. Always wear eye and ear protection when on the range.



Sight in your rifle so the bullet hits just above the point of aim at 100 yards (91 m). For most flat-shooting cartridges, you should zero-in 2 to 3 inches (5 to 7.6 cm) high; the exact distance depends on the trajectory of your bullet. By sighting in this way, you can aim dead-on at your target at any range up to 300 yards (274 m). The bullet hits slightly high or low, depending on the range, but strikes somewhere in the animal's vital area.

HOW TO ROUGH-SIGHT A RIFLE

Move the rifle barrel until the center of the bore lines up with the bull's-eye of a target 25 yards (23 m) away. Fix the rifle's position so it cannot move, then adjust the sights to aim at the bull's-eye.

Fire a three-shot group. The center of the group is the average point of impact. If the center is not in the bull's-eye, adjust the sights. With a scope you should strive to get a group size of 1 inch (2.5 cm) wide at 100 yards (91 m).

HOW TO ADJUST RIFLE SIGHTS



Adjust iron sights by moving the rear sight in the direction you want the rifle to shoot. To make the rifle shoot higher, raise the rear sight. To make it shoot to the left, move the rear sight to the left.



Move scope sights by turning elevation (up-down) and windage (right-left) screws the way you want the bullet impact to move. Read the instruction manual to see how much each click or mark changes the sight at 100 yards (91 m).

SHOOTING A RIFLE

Shooting a rifle under hunting conditions is more difficult than shooting at a target range. To shoot accurately, hunters must assume a stable position and know how to compensate for wind, uphill or downhill angles and moving animals.

Whenever possible, try to find a stable object to provide a steady rest for your rifle. If you cannot find such an object, the prone position is your next best choice. But shooting from the prone position may be impossible if ground cover or rolling terrain obscures your line of sight. Under these conditions, experienced hunters use the sitting position, which offers good stability because both elbows rest on the knees. The kneeling position is less stable, because only one elbow rests on the knee. The offhand position is the least stable. However, it may be the only choice when a moving animal offers a brief chance for a shot.

Learn how to adjust for natural forces like wind drift and the slant range effect. A strong crosswind dramatically affects a bullet's flight path. To hit a standing target, you must compensate by aiming slightly upwind.

The slant range effect causes your bullet to hit high whenever you shoot uphill or downhill. This confusing phenomenon results from the fact that gravity acts at a right angle to the horizontal. When a bullet is shot on a horizontal plane, gravity pulls at a right angle over the entire distance to the target, resulting in a curved flight path. But when a bullet is shot vertically, either straight up or straight down, gravity does not bend the flight path at all. The closer the angle to the vertical, the less the flight path curves.

A rifle is usually sighted in on the horizontal plane, so the sights are adjusted to compensate for maximum bullet drop. Since the bullet does not drop as much when shooting uphill or downhill, it always hits high. To compensate, aim low.

Most hunters tend to shoot behind running animals. A hunter using 150-grain .30-06 bullets would maintain a 4- to 5-foot (1.2 to 1.5 m) lead at a deer running at a right angle 100 yards (91 m) away. At 200 yards (183 m), he would increase the lead to about 10 feet (3 m) and at 300 yards (274 m), to about 16 feet (5 m).

Practice your lead by shooting at a rolling tire with a cardboard target wedged inside. Position yourself on a hill, then have someone roll the tire past you.

BULLET DRIFT



Wind drift increases as wind velocity and range increase. The chart shows how crosswinds of 10, 20 and 30 mph (16, 32, 48 km/h) would affect the path of a .30-06, 150 grain bullet at 100, 200 and 300 yards (91, 183, 274 m). As the chart indicates, a 10 mph crosswind would cause the bullet to drift less than 1 inch (2.5 cm) at 100 yards. But in a 30 mph crosswind, the bullet would drift over 22 inches (56 cm) at 300 yards.



Prone. Lie with your body about 30 degrees left of your line of aim. Place your left elbow just left of the rifle. Pull your right leg forward to lift your stomach off the ground, so your breathing does not affect the shot.



Kneeling. Sit on your right foot with your body 45 degrees left of the line of aim. Place your left foot forward and your left elbow on the knee.



Offhand. Stand sideways with feet perpendicular to the line of aim. Spread your legs to shoulder width. Keep your left elbow close to your body.



Solid rest. Rest your left hand or elbow on a solid object, like a tree or rock. Do not rest your rifle directly on the object.



Sitting. If you shoot right-handed, sit with your legs about 30 degrees to the right of your line of aim and rest your elbows firmly on your knees. Sitting is the most useful shooting position. You can use the position almost anywhere, assume it quickly and shoot accurately.

SHOTGUNS

Frontiersmen referred to the shotgun as a scattergun because it sprayed a swarm of lead pellets. A shot swarm is more effective than a single bullet for hitting moving targets.

When selecting a shotgun, consider the following: size of the bore, the chokes you need or the amount of barrel constriction, action, chamber length, weight and barrel type.

BORE SIZE. Shotgun bores are measured in gauge or in inches. As the gauge number increases, the size of the bore decreases. The most common gauges are 12 and 20, but gauges range from as small as 28 to as large as 10. The smallest bore is the .410, the only bore measured in inches. The larger the bore, the more pellets a gun can shoot. The denser shot pattern increases the chances for a long-range kill.

CHOKE. The amount of constriction or choke, at the end of the barrel affects the diameter and density of your shot pattern. Common chokes, from widest (most open) to narrowest (tightest), include: cylinder, skeet, improved-cylinder, modified, improved-modified and full. Open chokes are best for close-range shooting; tight chokes, long-range. The improved-cylinder is a good all-around choice.

Many modern shotguns have interchangeable screw-in choke tubes that enable you to quickly change chokes to suit the type of hunting. A gunsmith can also install screw-in chokes in some older guns.



Hinge action. The action opens when you push a lever or button at the rear of the receiver, allowing you to manually insert the shells. After firing, you break the action again. If your gun has ejectors, the spent hulls pop out automatically; otherwise, you must remove them yourself.

ACTION. Most single-shot and double-barreled shotguns have a hinge action. The simple hinge design is more reliable than repeating actions, like the pump and semi-automatic. Pump shotguns are more dependable than semi-automatics, which can malfunction in cold weather.

A pump gun ejects the spent shell and chambers another one each time you slide the fore-end back and forth. The majority hold five shells.

A semi-automatic fires one shell, ejects it and chambers another with each pull of the trigger. Most hold five shells, although a few hold up to seven.

CHAMBER LENGTH. Many shotguns are chambered for standard 2¾ shells. To shoot many types of magnum loads, you need a gun with a longer chamber. The proper shell length is usually engraved on the barrel. Never shoot a shell that exceeds that length.

WEIGHT. A light shotgun works best for quick shots in heavy cover. When you have more time to shoot, a heavier gun works better. You can hold the barrel steadier and swing on a target more smoothly.

BARREL TYPE. A long barrel provides a long sighting plane and can improve shooting accuracy. But contrary to popular belief, a longer barrel does not mean a noticeable increase in shooting range.

Many guns come with ventilated ribs. A rib makes it easier to sight down the barrel and cools it quickly, an advantage for rapid-fire shooting.

Field loads are adequate for close-range shooting at squirrels and rabbits and for small to medium-sized birds. Standard loads work better at longer ranges and for larger animals. Many hunters believe that magnum loads greatly increase their shooting range. But a magnum of the same length as a standard load may actually have a slightly lower velocity and a shorter range. The advantage of a magnum is a denser shot pattern.

Some magnum shells have longer cases that hold even more shot and powder. A 12-gauge, 3-inch (7.5 cm) magnum, for example, contains 1⅞ ounces (53 gm) of shot and 4 dr. equivalents of powder. Its effective range is about 10 yards (9 m) longer than a standard 2¾-inch (7 cm) load. Never attempt to shoot a long-cased magnum shell in a gun chambered for standard shells.

HOW CHOKE AFFECTS THE SHOT PATTERN



Choke determines how quickly your shot spreads. With a 12-gauge, improved cylinder choke and a standard-load No. 6 shell, about 13 pellets hit the vulnerable area of a stationary mallard silhouette at 40 yards (36.5 m). With a modified choke, about 16 pellets strike the target and with a full choke, about 20. Fewer pellets would strike a flying bird, because not all pellets in the shot swarm reach the target at the same time.

Proper fit should be checked while wearing your hunting clothes. You should be able to bring the gun to your shoulder in one motion, without the butt catching on your clothing. When you point the gun, the heel of your thumb should be 2 to 3 inches (5 to 7.6 cm) from your nose.

Screw-in chokes enable you to change your shot pattern for different types of hunting. These chokes screw into the barrel, so they have little effect on the gun's appearance. Use a specially designed wrench to install and remove the chokes.

RECOMMENDED SHOT SIZES

Game	*Shot Sizes*
Cottontail Rabbit	*6-7½*
Snowshoe Hare	*4-6*
Squirrel	*5-7½*
Raccoon	*6-7½*
Ring-necked Pheasant	*4-6*
Quail	*7½-8*
Grouse	*6-8*
Turkey	*4-6*
Dove	*6-8*
Woodcock	*7½-9*
Small Duck	*1-5*
Medium Duck	*1-4*
Large Duck	*BB-3*
Medium Goose	*BBB-1*
Large Goose	*T-BB*

Most often used for big-game hunting, slug loads are available in two basic styles: Sabot-type and Foster-style. While slugs are available for almost all gauges, 12-gauge slugs are the most popular.

Shooting a Shotgun

It takes little skill to hit a standing target with a shotgun, but moving game is a challenge. Expert shotgunners develop their skills through practice. You must adjust for different angles, ranges and flight speeds, all within seconds.

Because a moving animal offers only a brief shot opportunity, learn to mount the gun quickly and consistently. Place the butt against your shoulder and press your cheek against the stock. Keep both eyes open and sight down the barrel with your dominant eye, which for most right-handed shooters is the right eye.

Practice mounting the gun and operating the safety at home. Wear your hunting coat and make sure that you can bring the gun to your shoulder without it catching on your clothing. Quickly draw a bead on stationary objects. Rotate your shoulders and hips as if following a moving target. Be sure your shotgun is unloaded before you practice.

Shotgunners use three basic techniques for moving game. Snap-shooting works well at close range. But for crossing targets at longer distances, use the swing-through or sustained-lead method.

To sharpen your accuracy, shoot at practice targets or clay pigeons. Practice at a shooting range or have a friend throw clay pigeons with a hand trap. Fire at crossing, overhead and straight-away targets, so you learn how to shoot at different angles.

Most hunters tend to shoot behind crossing targets and below those that are rising, especially at long ranges. If you miss consistently, double your lead after each shot until you hit your mark.

THE SWING-THROUGH TECHNIQUE



Start your swing with the barrel behind the bird. Move the barrel smoothly and steadily, so it starts to catch up with the bird's tail.



Continue swinging so the barrel moves ahead of the bird. How far ahead depends on the distance and the speed and angle of the bird's flight.



Pull the trigger when you think you have reached the proper lead. Do not hesitate, flinch or slow down your swing as you pull the trigger.



Follow through until the barrel is well past the bird. If you stop swinging too soon, you will shoot behind the target.

BOWHUNTING

Taking a big game animal with a bow and arrow is one of hunting's biggest challenges. The hunter must practice many hours before the season begins; to learn to estimate range, draw the arrow smoothly, anchor it and place each shot in a target the size of a pie plate at 10, 20, 30, 40 and 50 yards (9, 18, 27, 36 and 46 m). And the bowhunter needs to refine his or her hunting skills as well as shooting skills.

Bowhunting is popular for many reasons: Hunters using a bow are generally allowed longer hunting seasons; this form of hunting is a big challenge; it is a relaxing and peaceful form of hunting. And it is fun!

There are basically three types of bows: the compound bow, the recurve bow and the longbow. Your choice of bow type is largely a matter of personal preference, each having its advantages and disadvantages.

The most popular hunting bow is the compound, which uses cams and cables to give the bow let-off, a reduction in the amount of force needed to hold the bow at full draw. This is an advantage when holding the bow back while waiting for a shot opportunity.

The peak draw weight, or maximum amount of weight needed to draw the bow, can be adjusted on a compound bow, whereas on a longbow or recurve, the draw weight is determined by the design of the bow. For a given draw weight a compound bow produces more energy than a recurve or longbow.

To determine draw weight, start by trying different bows. Select a bow with a draw weight that you can draw very comfortably. One of the biggest problems bowhunters have is trying to hunt with bows that have excessive draw weight.

Bows with a 60-pound (27 kg) draw weight are heavy enough for all North American game animals. In truth, it is the kinetic energy—not a bow's poundage—that matters most. Kinetic energy is a measurement based on the speed and weight of the arrow used. The higher the kinetic energy of an arrow, the more penetrating power or killing ability the arrow will have.

Kinetic energy is also affected by your draw length. This is the distance between the bowstring and the grip, when you hold a bow at full draw. Do not confuse draw length with arrow length; arrows are often shorter or longer than your draw length. For a given bow type, a longer draw length produces more energy than a short draw length.



Consistent shooting practice includes knowing how the bow and arrow combination performs from different angles and at varied distances. Practice while wearing the clothing that will be worn on the hunt.

The design of the cams or wheels on compound bows also affects the bow's ability to produce energy. The more round the cam or cams are, the less arrow speed the bow is able to produce. However, they are easier to draw, more forgiving to shoot and are more quiet. Radical cams produce faster arrow speed, flatter trajectory and more energy, but they are also harder to shoot, more noisy and more difficult to maintain.

Arrow weight also affects the amount of energy that you can deliver into a target. A heavier arrow produces more energy. However, an arrow that is too heavy for a particular bow will not perform well. Consult an arrow selection chart or archery shop to help you choose the correct shaft.

Some hunters prefer to hunt with recurve and longbows. They are lighter, quieter to shoot and less prone to mechanical failure. These more traditional bows increase the challenge and add nostalgia to the hunt.

EQUIPMENT FOR BOWHUNTING



Bows include: (left) compound bows, (middle) recurve bows, (right) longbows. Compounds deliver the most energy for a given draw weight; longbows the least. A compound's limbs are made of manufactured materials. Recurves and longbows are usually made of fiberglass-wood laminates, though some longbows are solid wood.



Arrowheads include: (1) field points for practice, (2) steel blunts, (3) rubber blunts, (4) judo points for small game and field practice and (5) broadheads for hunting larger game.

Shooting a Bow and Arrow

In the hands of an experienced shooter, the bow and arrow can be very accurate. But the average hunter stands little chance of killing an animal with a bow, unless he or she is willing to take the time to practice.

Shooting a bow and arrow accurately is more difficult than shooting a firearm. You must build up the muscles you use to shoot, use the correct shooting mechanics and be able to concentrate. You also need to practice and develop your ability to judge distances accurately.

The first key to good shooting is the ability to relax. Learn to let the bow shoot the arrow. If you try to force the arrow into the target you will not shoot consistently.

A good stance is critical for accurate shooting. If your upper body moves around, your sights and bow will be moving, too. It is your legs that hold it all still.

Begin by standing with your feet spread apart at shoulder width, 90 degrees to the target. Then take a half-step back with the front foot and pivot slightly toward the target for a mildly open stance. Keep your weight evenly distributed on both feet and stand straight up, with your head directly over the center of your body. Maintain this stance as you raise the bow to shoot. Don't lean forward or backward to pull the bow and don't cock your head to the side to line up your sights. In some cases, you will not be able to shoot standing straight up, but try to position yourself in a way that gives you good upper body stability.

Your bow hand is placed on the handle slightly differently depending on the type of bow that you shoot. After selecting the correct grip for your bow type, remember that your hand should stay very relaxed as you draw the bow. You must be consistent with your hand position. Even slight variations affect the arrow flight.

Your string hand, like the bow hand, should stay relaxed throughout the drawing process. There are two basic styles that hunters use to hold and release bowstrings. The more traditional method is to use your fingers. If you release with your fingers, start by grasping the string at the first joints of your first three fingers, with the index finger above the nock, the other two fingers below the nock. As you draw, the middle finger should hold most of the weight and the other two fingers should float on the string. The other method for releasing the bow involves using a mechanical release aid. Choose one that has a rotating head, so it does not torque the string as you draw. With a wrist-strap release, you should pull only on the strap and your fingers should remain loose. With a finger-held release, your wrist should stay straight and relaxed.

When you draw a bow, hold it at arm's length, roughly aiming at the target and begin to draw, pulling only with the muscles of your back. When you reach full draw, anchor solidly and aim at the target.

The anchor point for finger shooters is typically fairly high, with the tip of the index or middle finger planted solidly in the corner of the mouth. There is not necessarily a best way to anchor when using a release aid. With a wrist-strap release, many hunters anchor with the big knuckle of the index finger pressed behind the jaw. With a finger-held release aid, experienced shooters commonly anchor with the back of the hand pressed against the jaw.

No matter what type of equipment you use or the release method you use, the release should happen through complete relaxation. Focus your attention on pulling the bowstring with your back muscles. Release shooters pull the release trigger as their back muscles tighten up; finger shooters should let the string slip away as their hand relaxes. The shot should happen as a surprise.

Follow through a shot by holding your bow arm and release hand in the same position they were in when you released, until the arrow hits the target.

Always practice from the positions in which you hunt. If you use a tree stand, practice from an elevated platform. If you sit in your stand, practice in the sitting position. Wear your hunting clothes when practicing; they may affect your shooting. Use an arm guard to prevent the string from catching on heavy clothes.

Foot position and weight distribution are a critical part of a consistent shooting routine. Relax, spread feet to shoulder width, and orient the body toward the target in an open stance. The stance, the draw, and the release will become automatic with regular practice.

PROPER GRIP FOR SHOOTING COMPOUND, RECURVE AND LONGBOW



Low wrist position places the meaty party of the thumb on the bow handle. Maximum pressure falls about 1 inch (2.5 cm) below the big joint of the thumb. In this position, the wrist is more stable and less likely to move side to side.



Straight wrist grip is used with the recurve bow. At full draw, all pressure is between the thumb and forefinger.



Low wrist grip (left) is standard form when shooting a longbow. Pressure should fall on the back edge of the heel of the hand (right). Gripping the bow with too much of the heel on the handle can cause the bow to twist during relase, leading to poor arrow flight.

TYPICAL ANCHOR POINTS



Using a wrist-strap release aid (left), many archers anchor with the big knuckle behind the jaw. With a finger-held release (right), most archers anchor so the tip of the index or middle finger is at the corner of the mouth.


CARBON EXPRESS
THUNDERSTORM
ERSTORM

Practice is critical to ensuring a clean kill. Skills honed on the range translate well to the woods.

BOW CARE TIPS



Inspect the bowstring before shooting; frayed strings should be replaced.

Oil axles every few days when in the field.

Keep your bow away from heat. Laminated bow limbs can come apart after only a few hours in a hot vehicle.

MUZZLELOADERS

Hunters who accept the challenge of making one shot count can hunt additional seasons when they start carrying a muzzleloader. Most states have special muzzleloader regulations that extend big-game hunting opportunities beyond normal gun seasons. Muzzleloaders or black powder guns must be loaded by inserting powder and bullet or shot into the muzzle, then pressing the load down the barrel toward the breech. Reloading after a shot can take a minute or more, requiring the first shot to be a good one.

Hunters have a choice between muzzleloading shotguns and rifles. Each one of these is available in different ignition systems. The three most popular include: in-line percussion caplock, percussion caplock and flintlock. Flintlock, the oldest ignition system, has never been very reliable for the hunter. The percussion caplock, developed in 1820, increased the muzzleloader's reliability. It wasn't until the mid-1980s that the first in-line muzzleloaders were developed. These frontloaders became a very reliable hunting weapon. The in-line design allows the percussion cap to be located very close to the powder charge, promoting quicker and more positive ignition.

The most popular muzzleloading rifles for big game are 50 or 54 caliber. The projectile may be a patched round ball or a conical or a saboted bullet. An in-line rifle firing a saboted bullet can achieve good accuracy at 100 yards (91 m), comparable to modern center-fires and have a killing range on whitetail-size animals out to 150 yards (137 m). The practical accuracy range of a patched round ball is approximately 80 yards (73 m); a conical, 100 yards. A modern in-line muzzleloader properly loaded with a heavy, well-constructed bullet is up to the task of downing any North American game animal.

A hunter today has a choice of types of powder to use in his gun. He or she can use the centuries-old black powder or a synthetic black powder called Pyrodex. Either type performs well and can be tested to see which one performs best.

Muzzleloading shotguns work well on waterfowl, upland game birds and turkeys. Small caliber muzzleloading rifles are used for small game and varmints. Be sure to check the regulations in the area you plan to hunt when using these muzzleloaders.



In-line percussion caplocks have an internal striker or hammer that is cocked by pulling it rearward. When the trigger is pulled, the striker slams forward and hits the percussion cap, which is positioned on a nipple. The nipple is positioned directly behind the powder charge, so the fire from the cap reaches it instantly.

OTHER COMMON IGNITION SYSTEMS



On a percussion caplock, the hammer strikes a percussion cap, similar to the primer of a modern cartridge. A flash travels through the nipple to ignite the powder charge.



Flintlocks have a flint in the hammer. When the flint strikes a frizzen, sparks ignite the primer powder. Flame passes through a vent hole to set off the powder charge.

PROJECTILES

Plastic sabots grip the bullet securely as they are pushed into the muzzle. At the same time, the lands of the rifling groove the sabot. When the gun is fired the sabot transfers the spin of the rifling to the bullet.

Conicals fit tightly into the barrel without the aid of patching materials. As a conical is pushed down the barrel, the lands of the rifling engrave the soft lead, forming a tight seal.

Patched round balls must fit correctly in the barrel to achieve accuracy. The ball never touches the inside of the barrel. The patch grips both the soft lead ball and the grooves of the rifling.

BULLET TRAJECTORY



Bullet trajectory for saboted bullets is flatter than that of conicals and round balls. As the illustration shows, a saboted bullet sighted in at 100 yards (91 m) hits only 1½ inches (3.8 cm) high at 50 yards (46 m) and 6 inches (15 cm) low at 150 yards (137 m).

HUNTING SAFETY

Most people would be surprised to learn that hunting is not among the most dangerous sports. A National Safety Council study showed the fatality rate for hunting to be less than half that of boating or swimming.

Improved hunter education and increased use of fluorescent orange clothing account for the low accident rate. Every state and province sponsors some type of firearms safety or hunter education program. Many states require beginning hunters to pass such courses before they can purchase a license.

Nevertheless, the potential for a serious accident always exists. To avoid an accident, follow these safety rules.

- Treat every firearm as if it is loaded. Never assume a gun is unloaded because someone said so.
- Never point a weapon at anything you do not mean to shoot. This includes glassing other hunters with your rifle scope.
- Make sure your safety is on at all times, unless you intend to shoot.
- Positively identify your target before shooting. Never fire at a silhouette, a vague form or an area where you saw or heard something move. Fluorescent orange clothing greatly improves your own visibility.
- Control the direction of your muzzle at all times. If you start to fall, point the barrel away from yourself and other hunters. After a fall, check the barrel for obstructions like dirt or snow. A plugged barrel could rupture when you shoot, possibly causing serious injury.
- Never lean a gun against a tree, fencepost, vehicle or any place where it could fall over and accidentally discharge.
- Never shoot at hard surfaces or water with bullets or slugs. They could ricochet and strike another hunter or a building.
- Never drink alcoholic beverages before or during a hunt. Alcohol does not keep you warm; instead, it speeds the loss of body heat.
- Use only the ammunition recommended for your firearm. Do not carry two different types of ammunition in your pocket at the same time.
- When not hunting, keep the gun unloaded and the action open.
- Keep all firearms and ammunition out of the reach of children.
- Refuse to hunt with anyone who does not observe the basic rules of firearms safety.

Keep the safety on and your finger away from the trigger until you are ready to shoot. This eliminates the possibility of discharging the gun accidentally, especially if you stumble or fall.

PLANNING FIRING ZONES

Establish safe firing zones when hunting with others. When driving game, hunters should shoot only within their zone area.

Position your boat sideways to the shooting area. Do not position the boat lengthwise; this places one hunter in the other's shooting zone.

Split the area around your blind into 180-degree shooting zones. Each hunter scans for birds in the semicircle area around his or her half of the blind.



Never shoot unless you can see your target clearly. In dim light you may see a form that resembles a game animal (left). The right photo reveals that the form is actually that of a hunter.

OTHER SAFETY TIPS



Open your action before crossing a creek (left), climbing over a fence or in any other situation where you are unsure of your footing.

Never shoot if there is a chance of hitting buildings, livestock or any other unintended target. Avoid shooting over the tops of hills and ridges.

Carry your firearm so the muzzle points away from others. Safe positions include: shoulder carry, cradle carry and trail carry.

Chapter 3

HUNTING STRATEGIES

Whether you travel to another state or hunt the back forty, advance planning is the key to a good hunting trip. Lay the groundwork for your trip early.

Preparations for an out-of-state hunt should begin at least a year ahead. Some states conduct drawings for non-resident permits to hunt animals like elk, deer, pronghorn or moose. Most states accept applications until spring, but some set deadlines as early as mid-winter.

If you do plenty of scouting, it will pay off by helping you choose the right hunting method for the game and the area you hunt.

Begin planning your trip by requesting non-resident hunting information from the wildlife agency in the state or province where you plan to hunt. Be sure to specify the type of game you will be hunting. Ask about drawing application deadlines and information on state and federal wildlife areas that may require advance reservations. Licenses may be offered on a first-come, first-served basis. Some states require hunters to show evidence of having passed a firearms safety or hunter education course.

Reservations and permits may also be necessary when hunting in your own state. Wildlife managers and conservation officers can provide information on special hunts that require advance preparation. They can also supply current game census data to help you choose a hunting area. Managers may know of local farmers or ranchers who want hunters to thin over-abundant game populations.

Sportsmen's clubs like the Safari Club International, Rocky Mountain Elk Foundation, Mule Deer Foundation, and state hunting organizations are great places where hunters can network and share information. Some clubs lease private land where members can hunt.

SCOUTING FOR GAME

Pre-season scouting improves your odds of finding game once the hunting season begins. Best of all, scouting is enjoyable and saves valuable hunting time.

Scouting enables you to become familiar with the terrain and to identify heavily used game trails. It also helps determine any changes in habitat conditions or fluctuations in game populations that could affect the hunting.

Severe winter storms, wildlife food shortages, drought and cold or wet weather during nesting can drastically reduce game populations. New roads, housing developments and wetland drainage can permanently eliminate good wildlife habitat. So, there is no guarantee that last year's prime hunting spot will produce game this year.

Binoculars and spotting scopes help to locate game from a distant vantage point. But even if you do not see animals, you can detect their presence by the signs they leave. For instance, squirrels build nests in trees and scatter nut shells on the ground. Waterfowl preen themselves and leave feathers around resting areas. Bull elk bugle and roll in wallows during the mating period. All animals can be identified from their tracks and droppings. Damaged trees and brush result from animals rubbing velvet from their antlers, scratching trees to mark their territory or chewing bark.

Glass a potential hunting area from a nearby hill or tree. Look closely at edges between openings and cover to detect movement. You are most likely to see game early in the morning, at dusk or on cloudy days. When you spot an animal, note the time and identify a landmark to pinpoint the exact location. If the animal is not disturbed, it may appear in the same area at about the same time on subsequent days.

PLANNING TIPS



Always ask for permission to hunt on private land. Introduce yourself and specify the type of game you wish to hunt. Some landowners grant permission to a courteous hunter, even though their land is posted.

Talk to a clerk at a sporting goods store for local hunting information. Most carry maps, permit applications and other items for planning your hunt and many employ knowledgeable hunters.

Gather information from state and federal wildlife agencies. They supply maps, brochures on public hunting areas, public access lists and regulations. Tourist bureaus can recommend motels, resorts and campgrounds.

County maps identify paved and unpaved roads. They also show section lines, buildings, public lands, lakes and streams. Plat books detail property lines and identify landowners. The maps and plat books are usually available at county offices.

Aerial photographs reveal important details lacking on maps. They show isolated ponds and marshes, small streams, vegetation types, logging areas, meadows and forest trails. They can be obtained from the U.S. Department of Agriculture and private survey firms.

Topographic maps, like the U.S. Forest Service map and the U.S. Geological Survey map, provide information on land elevation and detail other features of the landscape, such as wetlands. They also show buildings, roads, trails, portages and other features useful for finding your way on a hunting trip. Geological Survey maps show forested areas in green. They generally cover a larger area than Forest Service maps.

SIGNS OF GAME ACTIVITY



Tracks in damp soil may reveal how long ago an animal passed. Fresh tracks (left) have sharp edges. Older tracks (right) have fuzzy edges. In snow, old tracks have a hard crust.



Droppings help hunters find game. Large quantities indicate feeding, loafing or bedding areas. Some animals do not digest their food completely, so you can check droppings to determine what they have been eating.



Feeding signs include damaged crops; scratched earth; nipped ends on grasses or twigs; and pits, husks and shells of fruits or nuts. Experienced hunters can often identify an animal by these signs.



Damaged trees and brush result fom animals rubbing velvet from their antlers, scratching trees to mark their territory, or chewing bark. Each species has distinctive rubs, scrapes and chews.



Beds and roosts in tall grass or on soft earth reveal the resting spots of mammals and birds. You can identify the animal from the size of its bed or roost and from nearby droppings, hair or feathers.



Game trails lead from cover to food or water. Several kinds of game often use the same trail. Inspect it closely and look for fresh tracks made by the animals you are hunting.

STILL-HUNTING

More people blow it while they're still-hunting than with any other method. The problem is that we move too fast. It's called still-hunting because most of the time the hunter should remain still, processing every sound, every movement, every smell.

Take a step, look and listen. Wait 30 seconds, 60 seconds or 5 minutes before taking the next step. Don't make a sound. Remember, you're in country you scouted. You know the game is close by. The success of the hunt hinges on the confidence you've placed in this piece of real estate.

Hunt into the wind. If the air movement shifts direction, change with it, keeping the breeze in your face. Move too fast and deer see you before you spot them. Slow down. Slow way down. Every time you take a step, a new window opens in the habitat. Look for the horizontal line of a back, the black of a nose, the flick of a tail, the crook of a leg or sunlight glinting from a nut-brown antler. Carry binoculars on a harness around the shoulders, not on the belt or in a daypack. And use them more than your boots.

In heavy cover, crouch down to look beneath the bushes. Sometimes that affords a better view through the stalks and the trunks. Maybe you'll spot a deer standing, listening to make sense of the sound you made when last you took a step. Sometimes you'll spot a deer looking back.

Place each footstep carefully to prevent snapping twigs, crunching leaves or brushing against branches. Avoid crossing open areas and places where animals could see your form above the horizon. Try to stay near cover where game will not notice your movements.

Still-hunting is usually a one-hunter method, but it also works well with two patient hunters. Game surprised by one person may run toward the other. Or an animal may be so intent on watching one human that it does not detect another approaching.

Successful still-hunting demands patience and confidence. If you lose patience and begin moving too fast, animals will spook. If you are confident of seeing game, it is easier to stay focused.

TIPS FOR STILL-HUNTING

Walk slowly and quietly (top). Avoid turning your head quickly, swinging your arms or making other movements that animals associate with humans.

Detect wind direction and rising and falling thermals (bottom) by squeezing unscented powder into the air or by tossing a small amount of down into the air.

Wear soft clothing to reduce noise. Hard-finish materials like nylon make swishing sounds as they brush the cover. Gummy boot soles enable you to walk quietly.

Look for visual clues to find game. A horizontal line among trees could be an animal's back. A glinting eye or twitching ear could also reveal game.

Avoid walking or waiting in direct sunlight. Animals are quick to notice the glare off your face and clothing. They are less likely to see a hunter in the shade.

STAND-HUNTING

To hunt from a stand, you must be positioned where you are likely to see game, but the game is not likely to see you. Concealment, awareness and confidence are the keys to success.

Hunters conceal themselves on stands or in blinds. A stand may be nothing more than a large tree that obscures your form. Or it may be an elevated platform, either free-standing or attached to a tree trunk or limb. A blind provides more cover. Many have walls of camouflage material or vegetation.

Whether hunting from a blind or stand, choose a spot where game is likely to pass. Take a scouting trip before the season to find first the water, then the feed, then the bedding ground. A deer will not make its living more than ½ mile (0.8 km) from its water source. Scout the area to find heavily-used game trails or escape routes. Take position well before game begins moving. You may have to find your spot in the dark.

Place a stand to take advantage of the view into well-used trails that lead from bedding areas to feeding areas. Or set up on the approach from bedding cover to water.

Take care to position the stand downwind from the trail and if the wind changes direction, find a different place to hunt until conditions improve. Select alternative locations for different wind conditions. To ensure that animals do not detect human scent, many hunters use odor eliminating products or masking scents.

Wind direction is also important when hunting ducks or geese on water. Choose a blind on the lee side of natural cover. Waterfowl usually land into the wind in the calmer water.

Stand-hunters sometimes wear camouflage outfits to reduce their visibility. But many types of hunting require high-visibility clothing for safety purposes. Even if you wear fluorescent orange clothing, game is less likely to see you if you keep motion to a minimum. If you must move, do so very slowly. Keep your face hidden; look at game from the side of your eye or from behind a hat brim.

Comfort is important when stand-hunting. You cannot remain quiet and motionless if you are cold, wet or in an uncomfortable position. You need warm clothing, because you must remain stationary for long periods. Some hunters build roofs to shed rain or use padded seats and stoves. Waterfowl hunters sometimes build blinds that are completely enclosed except for shooting windows.

Stand-hunting works best early or late in the day, when animals move between resting and feeding areas.

HOW TO SELECT A STAND-HUNTING LOCATION

Portable stands enable you to change location quickly. Some types clamp to the trunk in seconds. They have a comfortable seat and, when placed well above ground level, offer a wide field of vision. An elevated stand keeps your scent above the ground and places you higher than the usual sight plane of the game.

Locate your stand or blind near a watering site or stream crossing. Dove and antelope hunters often hunt near water holes. Moose hunters carefully check stream banks for heavily used trails leading to water.

Choose a site near a feeding area. Goose hunters build blinds or dig pits in harvest fields. Deer hunters take stands along the edges of corn, hay or milo fields. Bear hunters sometimes bait an area, then hunt nearby.

Select a stand site in a location where you are not silhouetted against the skyline. Game will detect your movement more easily if you do not have a backdrop.

Avoid stands that do not offer a clear field of fire. A tree or branch too close to your stand will narrow your shooting zone. A stand that restricts hip movement makes it difficult to swing your gun.

STALKING

To stalk an animal, you must see it first. Binoculars or spotting scopes help hunters to locate the quarry from far away and plan a strategy. A spotter who remains in a fixed location can signal to the stalker and direct the hunt from afar.

Like still-hunting, stalking demands fine-tuned hunting skills, because you must close the distance on game without being detected. Sneaking within shooting range can be extremely difficult, but expert stalkers may be able to approach within a few feet (m) of game.

When you spot an animal, watch it to determine whether it is likely to remain in the same area long enough for a stalk. If the animal is moving or appears nervous, you will probably not be able to get close enough for a shot. The odds are much better when the animal is feeding or is bedded.

Stalking works best where the topography or cover conceals the approach. Before beginning the stalk, plot a course that takes you into the wind, but keeps you behind hills, trees, fence lines or other natural or man-made features.

If there is no cover, use a clump of vegetation to break up your outline. Camouflage clothing makes you less visible. Move only when the animal faces away from you or when its head is down. Be sure that sunlight does not reflect off your gun, scope or wristwatch.

Move silently during the final stages of the stalk. Noise may not be important if you shoot from 300 yards (274 m). But for the bowhunter who must approach within 30 yards (27 m), the slightest noise can ruin his or her chances.

It is usually best to stay concealed until after the shot. But waterfowl hunters sometimes rush the birds before they shoot. They may gain an extra 5 to 10 yards (4.5 to 9 m) before the birds take off.

Plan your stalk so you move directly into or quarter into the wind. This prevents the wind from carrying your scent and the sound of your approach to the animal.

HOW TO STALK GAME

Pinpoint game by identifying nearby landmarks like a tree, boulder or fencepost. You can stay hidden while using the landmark to guide your approach.

Use natural cover to conceal your approach. A fenceline, a drainage ditch or a field of tall crops of grass enables you to sneak within gun range.



Bring your own cover when hunting in flat, open country. Push a clump of weeds ahead of you and stay low so game cannot spot your form above the horizon.

DRIVING

A lone hunter has little chance of rousting game from a large expanse of cover. Most animals sit tight or move off to the side rather than run or fly.

Before the drive begins, posters sneak to positions at the end of cover, where they intercept game pushed to them by drivers. The drivers spread out across the field or woods. The denser the vegetation, the closer they must be to discourage game from doubling back between them. It is generally better to have more drivers than posters.

Drives work best in a corridor or block of cover surrounded by open land. Game usually stays in the cover until pushed to the end, assuring someone of a shot. If possible, start at the widest end and work toward the narrowest. This concentrates the animals in a relatively small area, increasing your chances of a close shot.

Hunters should always know the position of other drivers and posters. Wear fluorescent orange clothing for maximum visibility and never shoot in the direction of another hunter.



Driving is an effective way to push game out of cover. You can make a drive with as few as two or more than a dozen hunters, depending on the situation.

TIPS FOR DRIVING

Drivers should stay within sight of each other. Outside drivers often move ahead to prevent game from escaping out the sides. Be especially alert as drivers approach posters; cornered game may spring from cover.

Islands of cover are ideal for drives. A patch of high brush in an open field, a shelterbelt or a woodlot is likely to hold game. If you attempt to hunt these areas alone, game may escape out the opposite side.

Corridors of cover, like roadside ditches, canyons, stream courses and railroad tracks, make good places for a drive. Game is less likely to double back in a narrow strip of cover than in a wide expanse.

FLUSHING

For many types of game, the surest way to evade hunters is to hide in dense cover. Even animals as large as a deer or as brightly colored as a rooster pheasant can hide within a few feet (m) of hunters without being noticed.

Hunters who use dogs stand the best chance of flushing tight-holding animals. Even in thick brush or other dense cover, a good dog detects and follows an animal's scent. Without a dog, you are sure to walk by some game.

A lone hunter can unnerve animals, causing them to flush. Unusual sounds and erratic movements may cause game to become nervous and burst from cover. Many hunters yell, clap their hands, crack brush or even run a few steps to convince an animal that it has been discovered.

When hunting with a partner, try to flush game toward each other. Start at opposite ends of the cover in an attempt to trap game in the middle. This cuts off possible escape routes. And because the animal detects danger from two directions, it is more likely to flush.

Stop frequently when attempting to flush game. If you walk at a steady pace, animals usually sit tight because they are confident they have not been detected. When you stop, they lose confidence and attempt to escape.

TIPS FOR FLUSHING GAME

Throw sticks or rocks to flush game from dense brush piles or other cover too thick to walk through. Game usually attempts to slip out the opposite side, so watch carefully and be ready for a shot.

Kick or step on clumps of vegetation that could hold birds or small game. With a hunter this close, game may be reluctant to flush. Tracks, droppings, feathers or hair may reveal the animal's presence.

HUNTING DOGS

One of the hunter's most valuable assets is a well-trained hunting dog. Watching a good dog in action adds to the thrill of the hunt. And a dog with flushing, pointing or retrieving skills greatly improves your hunting success.

Before selecting a dog, consider the type of game you intend to hunt, the terrain and climate. Pointing and flushing breeds were originally developed for hunting upland birds, most retrievers for waterfowl and most hounds for small game. Many breeds work well for more than one type of game. The Labrador, for example, is an excellent waterfowl retriever, but is also favored by many upland bird hunters for its flushing skills.

When hunting upland birds in a large expanse of light cover, use a dog that ranges widely. Pointing breeds work beyond gun range. When they detect a strong scent, they freeze in position or point. This gives the hunter time to walk in and flush the bird. For finding birds in thicker cover, a flushing dog may work better. These dogs work the cover slowly and thoroughly, usually staying within gun range.

Thorny cover can penetrate the fur and cut a short-haired dog. Long-haired breeds can tolerate thorns, but their fur often becomes matted with burrs.

In cold weather, a heavy-coated breed retains body heat longer than a dog with a thin coat. A thick coat is especially important for a dog that must retrieve in icy water. In extremely hot weather, a thin-coated breed works best. A dog with thick fur would overheat quickly.

Learn to read your dog, because every dog behaves somewhat differently when it smells game. With a pointing dog, a loose point usually means that the game has slipped away. A staunch point generally means game is close. Retrieving and flushing breeds perk up their ears or wag their tails rapidly. Hounds bay when they detect game.

Proper training and conditioning are the keys to developing a good dog. A poorly trained dog is worse than no dog at all. If it does not obey basic commands, it may flush game out of range. Or the dog may run off, costing you hours of hunting time.

Pre-season conditioning helps a dog maintain its stamina and toughens its feet. Run your dog at least one-half hour several times a week during summer.

POPULAR HUNTING DOG BREEDS

Retrievers include the Labrador retriever, golden retriever, Chesapeake Bay retriever and American water spaniel. These breeds are well-suited for retrieving waterfowl, because their skin secretes an oily substance that sheds water. Most retrievers also flush and retrieve upland game birds.

Pointing breeds include the English pointer, German shorthair, Brittany spaniel, English setter, Gordon setter and weimaraner. These breeds are used for upland birds, but a few hunters use them for rabbits and squirrels. Many pointers also retrieve downed game.

Flushers include several types of spaniels, like the springer, cocker and Boykin. These breeds pursue game until it flushes from cover, so they should be trained to work within gun range. The springer is especially popular among pheasant hunters.

Hounds, like the black-and-tan and redtick, have highly sensitive noses and are used mainly for trailing small game. Some, like the beagle, also work well for game birds. Other hounds include the bluetick, Walker and redbone.

FLOAT-HUNTING

Float-hunting works best for waterfowl, squirrels, deer, moose and other animals that frequent stream banks and lakeshores. You can also float up on flocks or rafts of waterfowl in open water.

Most float-hunters use small, low-profile watercraft including jon boats, canoes, semi-Vs and sculling boats. Boats are usually painted camouflage colors or draped with natural vegetation, netting or camouflage cloth.

The best boat depends on the area you hunt and the type of hunting. A jon boat is very stable, but the square bow would not slide through dense cattails. A canoe or double-pointed duck boat is less stable, but would slip through easily. A deep semi-V is best for rough water, but because of its high profile would not be a good choice for floating up on waterfowl. The birds would be less likely to notice a shallow-draft, sculling boat.

Silence is the key to float-hunting success. You can paddle very quietly in a canoe. If you row a boat, make sure the oars do not squeak or scrape the gunwales. Keep loose items tied down and try not to move around in the boat. Wood and fiberglass hulls are quieter than aluminum hulls. Many hunters glue carpet or rubber matting to the bottom, seats and gunwales to muffle sounds.

Keep safety in mind when float-hunting. Wear a life preserver. Never hunt from a tippy boat. It may flip over if you stand up to shoot or when your dog plunges into the water to retrieve game. To stabilize a canoe or other small watercraft, add pontoons or bands of buoyant material to the side of the hull. Low-profile boats make you less visible, but they can be dangerous on large, wind-swept waters.

To float-hunt a stream, float from one point to the next. The points conceal your approach, enabling you to slip up on game downstream.

You can pole through heavy cover, such as cane, cattails, bulrushes or other high vegetation to jump waterfowl and other game. Some hunters use push-poles as long as 16 feet (5 m) to propel narrow watercraft through the weeds. Or, you can use a duck-bill on your push-pole.

KEVLAR 65
Mad River Canoe

Water offers hunters an excellent means for a silent approach. A float-hunter can cover a large area with relatively little effort.

HOW TO FIND DOWNED GAME

Losing a wounded animal is one of the greatest frustrations in hunting. Finding downed game requires patience and persistence. But conscientious hunters make every effort to recover game that has been hit.

After the shot, watch the animal closely and try to determine if you made a clean kill, wounded it or missed completely. Clean kills and misses are usually obvious, but it may be more difficult to recognize a wounded animal. Even if you see no sign of a hit, look for hair or feathers, erratic movement or unusual behavior. You might hear the impact when your bullet strikes a big game animal.

Dogs with good retrieving skills greatly improve your chances of finding downed birds and small game. A dog marks a bird down and promptly retrieves it. If it runs, the dog circles to pick up the scent, then follows the scent trail.

Follow up any shot at big game, because large animals may show little evidence of being hit. Despite its size, a wounded deer can be as difficult to find as a cottontail. Unless hit in a vital area, it may run a long distance, especially if pursued by hunters.

If you are sure you hit a vital area, begin your pursuit immediately. An animal shot in the heart-lung area seldom runs farther than 100 yards (91 m). If you suspect a less damaging hit, it may be better to wait before following. A bleeding animal may lie down if not pursued. After 30 to 60 minutes, it will probably be too weak to run. Do not wait to follow if rain or snow threatens to obscure the blood trail.



Blood trails may provide clues for pursuing wounded game. Bright red, frothy blood indicates a lung shot and tells you to follow immediately. Darker blood usually means a less damaging hit; wait before following.

Mark the spot where you last saw the animal. Look for an obvious landmark, like a tree or leave a piece of clothing at the spot. Work outward in widening circles, but return if you fail to find the animal.

Look for feathers, hair or blood where you suspect the animal to be. Stand still, listen for movement, then inspect nearby cover. Hunters may fail to find game by leaving too soon, thinking the animal has run off.

Move quietly and watch ahead for movement when trailing big game. If you fail to see the animal and approach too closely, you may frighten it off, making it more difficult to find. Locating downed game is easiest with two or more hunters. While one inspects the ground for blood, the other looks for any signs of movement. If you lose the trail, mark the spot where you last saw blood. Then you can resume the search at that point.



Check likely escape routes if you cannot find the animal. Wounded game may slip into a strip of grass connected to the main cover area.



Examine thick clumps of grass or brush patches for signs of the animal. A protruding tail reveals the location of this wounded pheasant.

Work your dog just downwind of downed game. If the dog does not pick up the scent, call it to the spot where you last saw the animal.

Chapter 4

HUNTING BIG GAME

The concept of giving game "a sporting chance" is almost as old as hunting itself. It springs from the ethic of a skilled hunter who appreciates the challenge of the hunt as much as the meat or the trophy.

There is no sport with a richer tradition and no sport as demanding or rewarding as the hunt for big game. To be successful, the hunter has to develop an understanding of the quarry.

An animal's daily movements may be predictable or unpredictable, based on the species, the terrain, the weather and available feed. Scouting helps the hunter learn which trails animals are using between bedding areas and feeding areas. Such information allows the hunter to make an educated decision about where to still hunt, spot and stalk or set a tree stand.

Big game hunters should know how to use a map, a compass and survival gear. It is easy to become disoriented in the mountains, in the plains or in the fog. Study aerial photos or topographic maps before hunting and carry maps while hunting. Identify prominent landmarks in the field. Study of maps and photos will also open up new potential hunting spots.

Proper physical conditioning can make hunting more enjoyable, especially in steep or mountainous terrain. If you are out of condition or have blisters on your feet, it can be a chore to walk up a hill with a rifle and backpack, let alone drag out a large animal.

There is no sport more challenging, demanding or rewarding than the hunt for big game. The individual must match wits with an animal perfectly suited to its habitat. And the reward is great: a sense of accomplishment, perhaps a trophy and a supply of prime, high-quality meat.

WHITE-TAILED DEER

More people hunt for whitetail than for any other big game animal in North America. For many hunters, taking a trophy whitetail buck is the ultimate challenge.

The typical whitetail doe or buck is a high-strung, elusive creature that is very aware of its surroundings, whether it is at rest, feeding or on the move.

In a Michigan experiment, 39 deer including 7 bucks, 14 does and 18 fawns were fenced inside a 1-square-mile (2.6 sq km) area. Six experienced hunters attempted to find one deer. On the fourth day, one hunter finally spotted a buck. After one month, the average amount of time needed for a hunter to spot a buck was 51 hours. It took an average of 14 hours to spot any deer.

The deer's home range is small, so its very survival is based on its keen senses, its ability to find concealment and its intimate knowledge of its home range.

Whitetails rely on their sense of smell to detect danger. They can catch a whiff of human scent from hundreds of yards (m) away. Deer also hear extremely well. They do not have particularly sharp eyesight, but they are quick to detect lateral movement. Deer are not color-blind. Researchers have discovered that deer can perceive some color.



Whitetails often elude hunters by sitting tight in grassy or brushy cover. Their coats blend in perfectly. A hunter may pass within a few feet (meters) of a deer and not see it.

Deer are so familiar with their surroundings that they can quickly find an escape route or hiding place. And they are sure to notice any change in their surroundings, like a new deer stand. They avoid the area for several days until they get used to the new feature.

Whitetails usually attempt to escape danger by sneaking away unnoticed. When alarmed, bucks and does may snort loudly and stamp their feet. This serves as a warning to other deer. If threatened, a deer bounds away with its snowy white tail or flag, erect. But they normally run only a short distance, then look back to see if they are being pursued. They may stand for many minutes to ascertain if danger is approaching.

A whitetail's coat is reddish brown in spring and summer and brown or gray from fall through winter. Although the underside of the tail is white, the outside is the same color as the rest of the coat and covers up the white rump.

More than two dozen varieties of whitetails inhabit North America. The smallest variety is the Key deer, which generally weighs from 45 to 65 pounds (20 to 29 kg). It lives only in the Florida Keys. Another deer, the Coues whitetail (pronounced "cows"), is found in Arizona, New Mexico and Mexico. It reaches an average live weight of 120 pounds (54 kg) and a shoulder height of 32 inches (81 cm). The largest variety, the northern white-tailed deer, usually weighs from 130 to 190 pounds (58.5 to 85.5 kg). It is found in the northeastern states and into southern Canada. The heaviest whitetail on record, 511 pounds (230 kg), was shot in Minnesota in 1926.

The life span of a whitetail seldom exceeds 8 years. Most deer taken by hunters are 1½ or 2½ years old. You cannot tell a whitetail's age by its antlers. A 1½-year-old buck may have only spikes or it may have three or four points per side. Older bucks usually have four points on a side, but sometimes as many as seven.

The record whitetail rack came from a Saskatchewan deer shot in 1993. Both of the main beams measure 28½ inches (72.4 cm) long. The inside spread is 27¼ inches (69.2 cm). Coues deer have an average antler spread of 11.2 inches (28.5 cm) with a main beam length of 10.6 inches (26.9 cm).

Whitetails can attain speeds of 35 to 40 mph (56 to 64 km/h) and can easily jump an 8-foot (2.4 m) barrier. If they cannot escape by land, they take to water. Whitetails are strong swimmers and have been observed crossing lakes several miles (km) wide.



Shoot for the heart-lung area (red) of a big game animal. The best shot is directly from the side, where the most vital area is exposed. When an animal is quartering toward the hunter, slightly more than half as much vital area is vulnerable; slightly less than half when quartering away. An animal facing the hunter has only a small part of the vital area exposed. Facing away, none of the vital area is vulnerable and the shot would damage too much meat.



Typical antlers are fairly symmetrical, although they sometimes have a different number of tines on each side. But abnormal tines and differences between the two antlers in tine count or size of the main beam lowers the official score of the rack.



Non-typical antlers can be almost symmetrical or extremely asymmetrical. Many have a large number of oddly-shaped tines in unusual locations. Some have tines that point downward. Abnormal points add to the score of non-typical racks.

Whitetails feed primarily on buds and twigs from shrubs and small trees. They also graze on grasses, clover and other green plants. In agricultural areas, they commonly feed on alfalfa, oats, wheat and corn, but eat almost any crop available.

Does spend the summer and fall with one or two fawns. Mature bucks live alone, except during the breeding season. Whitetails mate between October and January. The rutting period lasts longer in the South that it does in the North. During the early stages of the rut, bucks and does become less cautious. Bucks are busy making scrapes to advertise their presence to does. The does move from one scrape to another looking for a suitable mate.

Where to Find Whitetails

No other big game animal has adapted to such a diversity of habitat. Whitetails can be found from the conifer forests of Canada to the chaparral plains of Mexico and from the shoreline of the Atlantic ocean to the river valleys of western Washington and Oregon. The whitetail thrives in farmlands, in suburbs and other areas where human development has severely reduced or eliminated populations of other big game.

Young hardwood forests make prime habitat. Whitetails prefer large woodlands, but can survive in smaller areas like woodlots and tree-lined stream corridors. Deer also live in grasslands, brushlands and swamps.

If you locate a good whitetail area when scouting before the season, chances are the deer will be there when the season begins. Whitetails have a surprisingly small home range. In a Texas study, marked deer were observed over a five-year period. On the average, does remained within a ⅙-square-mile (0.4 sq km) area. Bucks stayed within an area averaging 1⅔ square miles (4.3 sq km).

Your best chance of seeing whitetails is during feeding periods or when they move between resting and feeding areas. Deer feed most heavily before sunrise and after sunset. They bed down in midday. But season, weather, moon phase and hunting pressure can alter daily movements.

The changing seasons can affect whitetail movements in several ways. As the weather begins to cool in fall, deer feed for longer periods to build up their fat reserves for winter. When the acorns start to drop, deer often feed in the woods rather than moving to their usual feeding areas. Movement increases during the rutting period, as deer wander about in search of a mate.

Scouting for deer continues year-round. Use springtime turkey hunts and early bird seasons to keep track of big game movements and habits.

Changing weather increases deer movement. The animals sense impending weather changes, so they feed heavily while they can. On hot, sunny days, deer spend more time bedded down. They do not necessarily seek cover during a light drizzle. In fact, they often stand out in the open rather than lie in wet grass. But a heavy rain forces them into dense cover.

During a full moon, whitetails may not come out to feed until after dark. In the dark phase, deer begin feeding earlier. They do not feed as heavily at night, because the lack of light curtails their activity.

Hunting pressure can have a dramatic effect on deer movements. In heavily-hunted areas, whitetails change their feeding schedule once the season begins. They feed earlier and later in the day or even at night, to avoid exposing themselves during shooting light.



Rubs on small saplings result from bucks marking their territories by rubbing scent from glands on top of their heads. Bucks rub dozens of trees during the rut, seldom returning to the same ones. They also rub before the rut to remove velvet from their antlers.



Scrapes on the ground mean that a buck is attempting to attract does. As they paw the ground, whitetail bucks often thrash nearby saplings or overhanging branches with their antlers. They check their scrapes regularly, especially those visited by does.

TIPS FOR FINDING WHITETAILS



Tracks and droppings reveal how many deer are using an area. Deer tracks range from $2^1/_2$ to $3^1/_2$ inches (5 to 9 cm) long. Whitetail pellets are more elongated than those of rabbits and hares.



Day trails wind through thick brush and trees, but seldom cross clearings. Hunters wait along these trails when deer are most active.



Night trails lead through meadows or open croplands. Do not choose a stand along this type of trail, because deer seldom use them in daylight.

TYPICAL WHITETAIL HABITAT

Hardwood forests provide food and cover. A young forest is best, because sunlight can reach the forest floor to grow shrubs and grasses.

Farmlands offer ample food supplies. They can support large numbers of deer if they have cover like brushy draws or stream corridors.

Lowlands like swamps, bogs and river bottoms provide dense cover. Whitetails usually feed in surrounding fields or woodlands.

HUNTING FOR WHITETAILS

Stand-hunting, still-hunting and driving account for the vast majority of deer taken each year, but hunters use many techniques to outwit whitetails. Antler rattling, stalking, and float-hunting can also be effective.

You can greatly improve your chances by planning your hunt weeks before the season opens. It is possible for an opening-day hunter to leisurely walk into the forest, find a likely-looking spot and bag a trophy buck within minutes. But the odds against such a chance encounter are staggering.

Hunters who enjoy consistent success invest a great deal of time in pre-season scouting. Regardless of how good a spot was in previous years, make sure it still holds good numbers of deer. If you find little sign, look somewhere else. Once you locate a likely area, scout it to determine movement paths and escape routes.

Expert deer hunters know not only where, but when to hunt. Wind is an important consideration. You can approach deer more easily if a light breeze rustles the leaves. This background noise makes the sound of your footsteps less noticeable. In a strong wind, deer bed down in cover and stay extra-alert.

Some hunters prefer a light rain because it softens the leaves and twigs so they do not crackle underfoot. A light rain provides a low level of background noise, but does not reduce deer activity. In a heavy rain, the animals bed down under dense, overhead cover. Powdery snow makes for quiet walking and good tracking. But when a hard crust develops, deer can hear you coming. Snow-covered tree boughs muffle your sound and may block a deer's vision.

Temperature and cloud cover also affect hunting success, but not the way many hunters think. The common belief is that hunting is best on cool or cloudy days. But after thousands of hours of observation, members of a nationwide hunting club found that deer move about more when the weather is warm rather than cold; clear rather than cloudy.

Some hunters use bottled scents, either to mask their own odor or to attract deer. Masking scents are made with skunk or fox urine and sprinkled around the stand. Attractants, made from the urine of a doe in heat or from various fruits, are spread in the area where you want to shoot your deer.

Rattling draws bucks during the rut. Take a stand near a dense thicket where you spotted deer the previous day. Or rattle near a fresh scrape, if the spot offers a clear shot. Rub, knock and rattle two antlers together to imitate the sound of fighting bucks. If nothing appears within 15 to 30 minutes, move quietly to another spot.

You do not need high-velocity cartridges for whitetails, because most shots are at close range. Cartridges should be a minimum of .240 caliber with bullets at least 100 grains.

Stand-hunting for Whitetails

Whitetails are creatures of habit. If you have scouted an area thoroughly and selected a stand near signs of recent deer activity, you can be sure that whitetails will eventually pass your way. If you lose confidence, become impatient and decide to go after the deer, you significantly reduce your odds.

Choose a stand that offers good visibility. It should be located where the wind will not blow your scent toward a trail or other spot where you expect to see deer. You should also select a spot where the sun will not shine in your eyes. Be sure you are concealed on the sides from which deer will most likely approach.

But deer may not come from the direction you expect, so you must slowly scan in a complete circle around your stand. When you spot a deer at a distance, stay motionless and be patient. If you see a doe, watch closely because there may be a buck trailing behind.

If you hunt in the morning, walk to your stand very quietly. Get there while it is still dark. Most hunters stay at their stand until about two hours after sunrise. It often pays to wait a little longer. The commotion caused by other hunters leaving their stands may spook deer to you. If you hunt in the afternoon, stay until the close of shooting hours. Hunters often see more deer in the final minutes than during the rest of the day.



Scouting is critical to the best stand placement. Position a stand to take advantage of daily movements between bedding cover, feed, and water. Ensure that there are clear shooting lanes. On stand, keep your own movements to a minimum and be ready to stay for several hours.

TIPS FOR STAND-HUNTING



Intersections of two or more heavily used trails (left) make prime stand-hunting locations. Anther good spot is an area with many fresh scrapes.

Elevated stands place you above a deer's usual vision level. They also expand your field of view and keep your scent above the ground. But many hunters simply hide behind a tree or a pile of logs or brush.

Raise and lower your unloaded gun or bow with a rope when hunting from an elevated stand. Make sure the barrel is pointed away from you.

Tower blinds make it possible to hunt from a high elevation where there are no tall trees. Some tower blinds are permanent.

Move slower than you ever imagined you could. Expect to see a deer. If you move carefully and cautiously, you will see them before they see you.

Still-hunting for Whitetails

Technology has turned man, the ultimate predator, into man, the consumer. We consume power, petroleum, potato chips, polyester and prescriptions. We run around in circles, from home to school to job to grocery store and home again in the relentless pursuit of more goods to consume. Every year we get better at it, whirling faster and faster.

It is easy to bring our lifestyle to the woods, but it is not welcome there. In fact, it is counter-productive if the goal is to tie a tag on a deer. To succeed, we must become predators again.

The slower you move, the more deer you will see. Place each step carefully; plant your toe first, then gradually lower your heel. Let the sole of your foot feel for a stick that might snap or gravel that might grind or dry leaves that might crunch. Still hunters should wear shoes or boots with a light sole that allow the hunter to detect noisemakers before they alert game. Stop after a few steps then slowly move your head to examine the terrain. Bend down from time to time to scan the ground below the leaf line.

If you accidentally make a noise, stop. If they do not detect motion, whitetails usually forget the disturbance within a few minutes.

Wait 30 seconds or 1 minute or 5 minutes. Then take another step and scan the woods from this new vantage. You are seeing a new view of the world framed in a different series of trees, looking for the horizontal line of a deer's back or the crook of a leg against the vertical world of trees and brush.

Wind can be a hunter's ally or his worst enemy. Your scent is frightening to most deer. A deer's ability to smell is the one sense that they never question. If the wind is steady from one direction, hunt into it. A steady wind is the friend of the still-hunter.

Successful still-hunting is as much about attitude as it is about stealth. Tell yourself that you will see the deer before they see you. Convince yourself. Believe that the slower you move, the more deer you will see.

Driving for Whitetails

A deer drive's success depends on good organization. A group of hunters wandering haphazardly through the woods has little hope of shooting deer.

Every drive should have a leader who is familiar with the terrain. Before the drive, the leader gives clear instructions to each hunter. Posters take their stands first; each should wait in a spot with a good view, preferably from an elevated stand. Drivers synchronize their watches, then spread out across the upwind side of cover. Distance between the drivers may be only 15 yards (13.7 m) in dense cover or more than 50 yards (45.7 m) if the cover is sparse.

At the appointed time, drivers begin walking downwind. Deer soon detect the hunter's scent. They flush closer if drivers move quietly. Some deer move ahead, some double back and others remain bedded down.

Driving can work anytime deer are in cover. But if you drive a block of cover too large, deer slip to the side and let the drivers pass.

Deer drives can be dangerous. Limit the number of hunters so you can keep track of everyone's location. Posters in elevated stands also make a drive safer. Their shots angle toward the ground and they are above the normal shooting plane of the drivers.

Watch closely for whitetails doubling back through the driving line. Deer may sneak back though drivers are visible on both sides. As drivers approach posters, deer must double back or break into the open.



Keep adjacent drivers in sight at all times. This prevents a hunter from moving too far ahead of the others and into the firing zone.

Post near a known escape route. Deer often move from one block of woods to another by sneaking through a connecting patch of lighter cover.

MULE DEER

The mule deer is named for its long, mule-like ears, but you can tell a mule deer from whitetail by the black tip on its tail. Most of the muley's narrow tail is white, making the rump patch more evident than it is on whitetails. Their antlers also differ. The main beam of a mule deer antler is forked; whitetails have a continuous main beam.

The muley is a much sought-after trophy of the western United States, Canada and Mexico. The record mule deer rack has a spread of 30⅞ inches (78.4 cm). Its right antler has six points and a main beam that measures 30⅛ inches (76.5 cm) long; its left has five points and totals 28¾ inches (73 cm). The animal was shot in Colorado in 1972.

Like whitetails, mule deer have excellent senses of smell and hearing. But muleys have better long-distance vision. They usually bed down where they have a good view of the surrounding terrain. Unlike whitetails, they rarely sit tight and let hunters pass only yards (m) away.

When they detect something unusual, mule deer cock their large ears to pinpoint the direction of the disturbance. Then they bound off in pogo-stick fashion, with all four feet touching the ground simultaneously. This distinctive gait, called stotting, enables them to survey the terrain better and to change direction instantly.



A startled mule deer runs much farther than a whitetail, sometimes up to 4 miles (6.4 km). They usually bound uphill, often pausing for a last look before slipping over a ridge. Muleys normally run with their tails down.

Compared to whitetails, mule deer have a calm disposition. They show little fear of humans as long as enough distance separates them. But they become nervous and often slip away when a hunter disappears from sight.

Mule deer prefer terrain more open than that used by whitetails. Mountains and foothills with sparse stands of timber, rolling prairies broken by canyons and coulees and low brushlands make ideal habitat.

Where mule deer and whitetails co-exist, they eat many of the same foods. But the mule deer's diet usually differs because of the rougher terrain. Common foods include bitterbrush, mountain mahogany, serviceberry, chokecherry and sagebrush. The Pious Report, completed in 1989, found that a mule deer's diet consisted of 55 percent browse (the new growth of trees, shrubs and vines with woody stems), 22 percent forbs (broadleaf plants), 10 percent grasses, 7 percent nuts and 6 percent other materials.

Browse is abundant in mule deer habitat, but broadleaf plants are mule deer favorites. Locate these plants, confirm the deer are eating them and spend time watching in the morning and evening. Early morning and late afternoon are the prime feeding periods. Favorite areas are brushy hillsides, meadows, croplands and pastures, generally at lower elevations than bedding areas.

Mule deer move as much as 2 miles (3.2 km) from feeding to bedding areas. In midday, they often bed down on the lee side of a break. They may rest just below the crest of a hill or the lip of a ravine. They watch only the downhill side, relying on the wind to bring them the scent of anything approaching from behind. Mule deer also bed on grassy mountain terrain, in the bottom of a dry wash or near a tree on a hillside. In remote areas, they may feed in the open rather than bed down during the day.

Daily movements usually begin with mule deer moving to feeding areas like a grassy stream margin in a ravine. They feed until 1 to 2 hours after sunrise, then bed in areas like a ledge near the top of the ravine. Large bucks may bed on rocky terraces at higher elevation. Deer return to feeding areas about an hour before sunset.

Deer take their water from ponds, puddles, creeks, rivers, lakes, seeps and succulent plants. Researchers in another study found that they travel an average of 800 yards (731 m) to get it. They approach, ever watchful for predators, because coyotes, cougar and other carnivores need water too.

After a rainy period, look for mule deer on sunny hillsides. Heavy snow drives them from the mountains to lower ground. Herds migrate as far as 50 miles (80 km), often wintering in brushy draws and canyons that are blown free of snow.

Mule deer often form large herds, especially during the breeding season. Small and medium-sized bucks mix with does and fawns, but the largest bucks are usually loners.

Most mule deer breed in November and December, but the breeding period may be as early as October or as last as March. During the rut, the bucks thrash or horn bushes, poles, branches and tree trunks in a display of dominance. They do not make scrapes.

Seven varieties of mule deer inhabit the western third of North America. The desert mule deer ranges as far south as central Mexico. The most numerous variety, the Rocky Mountain mule deer, is found as far north as the Northwest Territories.

Rocky Mountain mule deer reach the largest size, generally weighing from 140 to 200 pounds (63 to 90 kg). The largest on record, 453 pounds (203.85 kg), was taken in Montana. The southern mule deer is the smallest variety; it weighs from 85 to 110 pounds (38.25 to 49.5 kg).

Hunting for Mule Deer

Mule deer live in rugged mountainous terrain and high desert landscapes. They may feed in the valley on a rancher's alfalfa, but they most often bed on the high ground where they can spot danger a long way off.

A mule deer's survival strategy includes identifying the predator, then putting distance and obstacles between himself and danger. Many hunters have scored on a buck because it stopped to take one last look before it went out of sight. Some make the mistake of thinking that mule deer are easier to outsmart than whitetails, but the truth is a big mule deer is one of the most sought-after trophies on the continent.

Mule deer hunting in open country lends itself to the spot-and-stalk method. Get to the highest part of your hunting area early in the morning, preferably before shooting light. The chances of spotting muleys in the open are best in the morning and the evening. The high elevation affords a good view.

Glass every detail of the landscape, first with binoculars then with a spotting scope. Mule deer blend in well with their surroundings and are masters at concealment in a small amount of cover. Sometimes it takes movement of the sun and shadow to reveal a feeding or bedded animal. If you spot one deer, look closely for others because mule deer often feed and bed in groups.

Glass potential feeding and bedding areas with binoculars. A spotting scope works better for long distances. Look for a reflection off shiny antlers; buff-white patches of throat or rump hair; or the symmetrical shape of a mule deer's face and ears, which resembles a three-bladed propeller.

If the animal is too far away for a shot, plan a stalk. Have a partner stay at the spotting scope and direct the approach using hand signals. Use natural features of the landscape, like ravines, for concealment. Try to approach from downwind and above, because muleys expect danger from below.

Should glassing prove futile, still-hunt your way downhill. Some hunters take stands along trails where muleys are likely to pass on the way to bed, feed or water. When hunting with companions, driving can be effective.

A running buck makes a difficult target because of its stotting gait and unpredictable turns. But it may stop and look back if you shout, whistle or make a deer call.

Mule deer hunters take shots at up to 300 yards (274 m), so sight in your rifle for long-range shooting. Use a high-velocity cartridge of at least .240 caliber with a minimum bullet weight of 95 grains.

Still-hunt a series of ravines by starting at the head of one ravine, then walking the edge. Look over the crest periodically to spot bedded deer. Cross the ravine at the lower end and walk the other side to check for deer you may have missed. Then, cross to the head of the next ravine and repeat the procedure.

Stand-hunt along corridors between feeding and bedding areas. Conceal yourself behind a natural feature like a rock outcrop or large tree or use a tree stand. Mule deer trails are usually less distinct than those of whitetails. But the animals often follow natural passes like a saddle between two ridges.

HOW TO DRIVE FOR MULE DEER



Drive for mule deer in ravines. One hunter walks up the bottom and another halfway up the side. A third hunter posts at the head of the ravine. Driving also works well along wooded or brushy stream corridors.



Never shoot at a deer when it is on top of a ridge. Always be sure there is a solid backstop behind the animal before shooting. Bullets travel completely through them.

BLACK-TAILED DEER

Due in part to their narrow geographic range, black-tailed deer are largely ignored in the popular hunting press, but this animal is one of America's most prized trophies. Blacktails are a subspecies of mule deer and their territories overlap along the eastern boundaries of the smaller deer's range. A doe weighs 70 to 140 pounds (30 to 66 kg). Bucks weigh between 120 and 250 pounds (57 to 120 kg). A buck may measure up to 36 inches (90 cm) at the shoulder.

Antler growth is similar to mule deer. Males grow branching tined antlers. Typical antlers are four-points (western count), but many blacktails mature with three-points per side (not counting eye guards).

They are called blacktails because the bottom two-thirds of the tail is black. The tail is wider than a mule deer's tail. At the base, it is brown. The underside is white. Blacktails are reddish-brown in the summer and tend to go gray-brown in the fall.

Black-tailed deer can be found throughout western Canada, western Washington, western Oregon and northern California, but certain types of habitat hold them in greater numbers. If you want to see blacktails, watch clearcuts and burns. Logging benefits these animals because it opens up the forest canopy to let in the sunshine. New growth springs up and deer can find most of what they need all in one place.

Deer need food, water, shelter and space. Sometimes they get all four in a clearcut. They also become vulnerable to hunters. That's why you only find does, fawns and immature bucks in large openings.

If you want to fill your tag with a doe (when legal) or a young buck, hunt the clearcuts in the morning, bedding areas at noon and paths leading from bedding areas in late afternoon. You will find the deer.

However, clearcuts are not as easy to find as they once were. Now, chemicals are used to control weeds, what we hunters refer to as forbs and what deer call groceries. Today's super-fast-growing tree seedlings turn clearcuts into tall timber again, a lot faster than they used to. Also, fear of fire may keep gates closed to timber company lands in low-water years, with "No Access" signs posted until the rains come.



It doesn't take much habitat to hide a deer, and many big blacktail bucks grow old without ever being seen by a hunter. Their sanctuaries provide both cover and food. Water can be reached after dark. During the general rifle season, bucks may spend most of their time in an area of just a few acres (ha).



In open country and oak savannah, black-tailed deer are vulnerable to spot-and-stalk tactics. Take up a position before first light and employ a spotting scope to cover a lot of distance from one place. An afternoon stand can pay off with a glimpse of a big buck right before dark.

WHERE TO FIND BLACKTAILS

A good strategy is to look for the pockets the crowds pass by. Sometimes they may be so obvious that no one would think to hunt there. Sometimes they are so far back in the timber or the brush is so thick that other hunters detour around it.

In oak savannah, the hills are often bare, especially the south-facing exposures. Blackberry bushes, poison oak, oak trees and scattered pines grow up the sides, with bedding cover found in the run-off washes and along the creek bottoms. Old road beds provide dependable travel corridors and trails are visible from hundreds of yards (meters) away, showing where a hunter might expect to see a deer emerge from the heavy cover.

Deer are easily seen from the tops of the hills, but usually, glimpses of does and forked horns are the pay-off. Wiser bucks know to bed in the sticker patches when the orange-clad horde takes to the ridges. The bigger bucks have seen it all before.

Finding Unpressured Deer in Pockets of Cover

To find pockets that other people pass by, use a 7.5 Minute Series, 1:24000 U.S. Geological Survey map. With the contour intervals of 40 feet (12 m) on a 7.5 minute topo, it's easy to pinpoint roadless areas, identify swamps, spot north-facing ridges and locate most of the springs and seeps. You can also identify escape routes and make an estimate at where to find the dense cover where deer bed.

In these hideouts, most big black-tailed bucks grow old without ever being seen by a hunter. Their sanctuaries provide both cover and food. Water can be reached after dark. During the general rifle season, bucks spend most of their time in an area of just a few acres (ha) and feed after the sun goes down.

Private land may be the key to access, even to public ground. Get permission to cross a neighbor's land. If parking pull-outs are few and far between, have someone drop you off along the road. If a stream is the boundary, use waders or float a boat. Whatever it takes, hunt the ground other hunters can't or won't get to. And don't fall into their patterns.

Mature blacktails seldom come easy. Examine aerial photos and topo maps to find the places where the big boys live. Locate natural escape routes such as saddles and canyons. Look for brushy shelves where a buck can watch his backtrail from his bed. Locate a trail from a nearby feeding area or water and you have found a buck's living room.

Hunt into the wind and watch every step. Move too fast and deer will see you before you spot them. Slow down. Every time you take a step, a new window opens in the heavy cover. Look for the horizontal line of a back, the black of a nose, the flick of a tail, the crook of a leg or sunlight glinting from a nut-brown antler. Carry binoculars on a harness against your chest, not in a daypack. And use them.

Learning to recognize feed, water, bedding ground and escape cover are the fundamentals of hunting these most challenging of our western deer.

Carry your lunch and stay in the woods all day. Watch a trail leading into a bedding area and let other hunters push the deer your way. In the timber, hunt from above, whether from a tree stand or looking down from a high cliff. Such stands afford greater visibility, keep you above the line of sight and keep your scent stream above the game.

In open country, use a spotting scope to scout bucks on distant hilltops. It's always better to see them first and plan a strategy.

When scouting for blacktails, think small. A strip of trees between roads can hold a deer. A half-acre (0.2 ha) behind the barn may hold a buck, as will an island in a river or a lake. You may find such a spot anywhere in blacktail country.



Black-tailed deer are among the most wary of all big game animals. Learn their habits, their preferred foods, and their bedding areas. Scouting pays off with more deer sightings during the season.

ELK

Sought after and prized for its magnificent antlers and savory meat, a mature bull elk is the big game hunter's greatest trophy. A large animal may have antlers 5 feet (1.5 m) long.

Antlers of the largest bulls, called monarchs, have eight points on a side. Imperial elk have seven points per side and royal elk six. The record elk rack has eight points on one side and seven on the other. The main beam of one antler measures 59⅝ inches (151.5 cm); the other 55⅝ inches (141.3 cm). The rack, which has a 45½ inch (115.5 cm) spread, came from an elk taken in Colorado in 1899.

Two varieties of elk provide the vast majority of hunting. Most numerous is the Rocky Mountain elk. The slightly larger Roosevelt elk lives in the coastal mountains of the Pacific Northwest. Elk are brownish-gray with long, chestnut-brown hair on the neck. The tail and rump patch are buff-white. Bulls average about 750 pounds (337.5 kg) and stand 5 feet (1.5 m) high at the shoulder. Cows weigh about one-fourth less. The smaller tule elk are found in California.

Elk prefer heavily timbered country broken by clearcuts, burns and meadows. The best habitat is in remote, mountainous terrain laced with streams and small glacial lakes. Elk also make their home in desert environs. In dry country, elk have large territories and do not tolerate human disturbance.



Cow elk live in large herds which also include calves and an occasional spike bull. An old cow leads the herd, alerting the others to danger with a sharp bark. Older bulls live alone or in small groups of up to six. Bulls wander more than cows, shunning cow herds until the mating season.

The breeding season or rut begins sometime between late August and mid-September. Bulls break out of their summer bachelor herds and locate on ridgelines. A dominant bull, called a herd bull, bugles to advertise for a harem that may number up to 30 cows. He protects them from the advances of younger males, also called satellites or of other herd bulls.

To detect danger, elk rely mainly on a keen sense of smell. They also have excellent hearing. On windy days, when swishing tree limbs would obscure the sound of a hunter's approach, they become nervous and retreat to heavy cover. Elk quickly notice movement, but usually ignore stationary objects.

An elk can run 35 mph (56 km/h) in a short burst and can maintain a 15 to 20 mph (24 to 32 km/h) trot over a long distance. A running bull carries his nose high, so his antlers lay back along his body and do not tangle in branches. Elk are strong swimmers and can jump obstructions up to 10 feet high (3 m).

Elk feed mainly on grasses. As winter nears, they browse on twigs and leaves from shrubs and trees. The morning feeding period begins about one hour before sunrise and lasts until one hour after. In late afternoon, they begin feeding about two hours before sunset and continue until dark. Elk usually have four or five shorter feeding periods during the day, each lasting from 15 minutes to one hour. Because they eat so often, elk usually bed within 1 mile (1.6 km) of where they feed. They prefer bedding areas with a good view, like a grassy terrace or bench about half of the way up on a hillside.

In summer and early fall, elk scatter over a large area at high elevation. The rugged terrain prevents intrusion by humans. In late fall, heavy snow and extreme cold push elk to lower elevations. But with a break in the weather, they may return to high altitudes. Some herds move 100 miles (161 km) to find the right conditions.

Daily movement patterns depend on hunting pressure. When not disturbed, elk feed in open meadows or areas with young trees and shrubs. They bed down at the edge of timber nearby. If threatened, they move up to 5 miles (8 km) into the timber after feeding. Or they may retreat to a steep, conifer-studded slope where they sniff rising air currents to detect danger from below.

Migrations in late fall begin when snow depth reaches 19 inches (48.25 cm) or more and temperatures plunge below zero Fahrenheit (–17°C). Elk move to snow-free, south-facing slopes at lower elevations.

Bugling consists of a series of melodious whistles, progressing from a low to high pitch. Herd bulls bugle to intimidate competing males. Challengers bugle and chuckle to lure the herd bull away from his harem. In addition to bugling, herd bulls bellow, rake trees with their antlers, display and spar with other bulls to drive them off. Occasionally, two bulls fight each other in a test of strength.

SIGNS OF ELK ACTIVITY



Droppings that are elongated and ¾ to 1½ inches (1.9 to 3.8 cm) in length mean that elk have been browsing on twigs and leaves. Droppings in a large mass are from elk that have eaten green grass.



Wallows are made by big bulls to announce their presence to cows. A bull scrapes out a depression at a spring seep. He urinates in the mud, then rolls in it, plastering his body.



Fresh rubs during the rut also advertise a large bull's presence. Elk rubs are higher than those made by deer and the bark of the sapling is stripped over a greater length.

Hunting for Elk

A successful elk hunter must earn his or her trophy. Unlike most other big game animals, elk retreat deep into the forest or climb to extreme elevations to escape hunting pressure.

Plan to spend several days on the hunt. Scout a prospective area to find fresh elk sign, then set up camp at least 1 mile (1.6 km) away.

Scent can help you locate areas used by elk. The animals emit a strong, musky odor. The scent lingers in bedding or wallowing areas long after the elk leave.

One of the most productive techniques is stand-hunting in early morning and late afternoon, especially when the stand is on or near a saddle that the elk use to move between one drainage and the next. For a morning hunt, walk to your stand in the dark, moving quietly to avoid spooking any elk in the vicinity. Remain on your stand until about two hours after sunrise, glassing to find elk that you could stalk. In the afternoon, be on your stand at least two hours before sunset.



Pack trains enable hunters to reach the remote, mountainous areas which offer the best elk hunting. Horses or mules also simplify the task of carrying out the antlers and cut-up carcasses.



Calls include: (1) flute, (2) pigtail and (3) tube types. Diaphragm calls (4) mimic small, medium and old bulls. Tapes, CDs and DVDs (5) help you learn the best calls.

In midday, when elk are bedded down, you are more likely to see them by still-hunting. The technique works best when the ground is damp or covered with soft snow. Noise doesn't spook the elk as much as scent does. Use scent control to keep the human odor in check.

Driving can be effective, but only if the hunting party is familiar with the terrain. Drivers approach from below a known bedding area and push the elk uphill to posters. The posters station themselves along game trails in thick timber or near clearings where elk are likely to break into the open. Startled elk make plenty of noise. But more often, they slip away silently, so posters must watch closely.

During the rut, hunters can bugle in bull elk. Many elk calls mimic the high-pitched, squeaky whistle of a spike bull. This call infuriates the herd bull. He thinks an unworthy youngster is making a play for his harem, so he moves toward the caller, ready to do battle. If a bull answers but does not move, he is probably guarding his harem and reluctant to leave. In this case, try stalking close enough for a shot.

Because elk are so large and shooting distances so long, most hunters prefer high-velocity cartridges of .270 caliber or larger. Use a bullet weighing at least 150 grains.

A bow hunter should use a bow set up with a pull weight of at least 50 pounds (22.5 kg) and a razor-sharp, strong, fixed-blade broadhead. Muzzleloader hunters are best equipped when using a .50-caliber or larger, stoked with a premium bullet.

Bugle for elk starting at dawn. When a bull answers, move toward him, staying downwind and calling about every five minutes as long as he continues to respond. Keep approaching until you get within about 400 yards (366 m). Then, select a blind and continue calling to lure him within shooting range.

Stand-hunt above trails or wallows or at the edge of a meadow where elk feed. Trails and feeding areas are most productive in early morning and late afternoon. Bulls usually visit wallows late in the day.

OTHER ELK HUNTING TECHNIQUES

Still-hunt to within shooting range. Bowhunters often get as close as 20 yards (18 m). Start by walking a ridge, looking for elk on terraces or hillsides. Approach elk from above because they usually watch the downhill side.

Follow fresh elk tracks in the snow. The tracks generally measure 3½ to 5 inches (9 to 13 cm). Stay on the trail as long as it goes downhill; stay above the trail if it moves across the slope. Constantly look ahead so you see the animal before it sees you.

MOOSE

Most hunters are awestruck by the sight of their first bull moose.

With antlers towering 10 feet (3 m) above the ground, a bull moose is truly a magnificent sight. A large bull weighs 1,200 pounds (540 kg) and moose up to 1,800 pounds (810 kg) have been recorded. The world-record rack has a 65⅛-inch (165.4 cm) spread. The right palm measures 54½ inches (138.4 cm) and has 19 points; the left 53¾ inches (136.5 cm) with 15 points.

Like other members of the deer family, moose have an excellent sense of smell and good hearing. But their eyesight is poorer than that of deer. Moose seldom notice a nearby hunter if he or she does not move.

Despite their size, moose can run up to 30 mph (50.8 km/h). When spooked, they crash through brush and small trees, ignoring trails. But moose can also slip quietly through cover to elude a hunter.

Young hardwood forests with scattered conifers and brushy lowlands make ideal moose habitat. The dense undergrowth provides ample food and bedding cover. But they can also live in older forests with little underbrush.



A big bull can browse on vegetation up to 11 feet (3.35 m) off the ground. If it cannot reach the upper portion of a small tree, a moose straddles the trunk, then starts walking. The animal bends down the tree, feeding on leaves and twigs as it walks. Moose feed most heavily from just before sunrise to about two hours after, and again in late afternoon. But they may feed anytime during the day or night. When not feeding, moose bed down in the thickets.

Most of the year, moose live by themselves. They lead docile lives, seldom moving more than ½ mile (0.8 km/h) in a day, but during the rut, which begins in September, bulls become ill-tempered. They have been known to attack cars and even trains. Rutting bulls regularly visit wallows. Both sexes roam widely during the rut, sometimes wandering over 10 miles (16 km) from their usual home range.

Hunters see the most moose on clear, calm days. Heavy overcast, rain, snow or high winds keep the animals bedded down.

Before you hunt, scout the area for sign. With animals of this size, the evidence will be obvious. Select a stand near a wallow, a well-used stream crossing or any spot where the topography funnels moose through a small area. Get to your stand before daylight, remain until mid-morning, then return in late afternoon.

Still-hunting can be effective at midday, especially if there is snow to quiet your footsteps. If you attempt to sneak through heavy timber and brush, you will make too much noise. During the rut, antler rattling or calling may lure bulls from dense cover. Using cupped hands or a birchbark megaphone, make a series of short grunts to imitate a cow in heat. If you hear a response, pour water in a puddle to imitate a cow urinating.

In hilly or mountainous country, hunters stalk moose after spotting them with binoculars. Float-hunting works well along streams and lakeshores.

Most moose hunters use large-caliber rifles and high-velocity ammunition, similar to those used for elk. A moose may not drop immediately after the shot. To prevent losing a wounded animal, wait 10 to 15 minutes for it to lie down, then begin to track it.

Moose have a dark brown, almost black, coat. A large bull stands 7 feet (2 m) tall at the shoulder and measures 10 feet (3 m) in length. Each antler has a large palm with numerous points along the outer edge. Moose usually stay near water. Bogs and lakes provide a source of food, a place to cool off and a refuge from swarms of insects. Excellent swimmers, moose will not hesitate to cross a fast river or even a large lake. Moose tracks measure about 5 to 7 inches (13 to 18 cm) long.

TIPS FOR FINDING MOOSE

Broken saplings indicate a bull moose in rut. A bull twists off saplings with his antlers to advertise his presence to cows.



Droppings measure 1 to 1½ inches (2.5 to 3.8 cm) long. When moose are eating browse, droppings have a consistency similar to compressed sawdust.



Brushy lowlands are favorite feeding areas. Moose prefer red-osier dogwood, willow, aspen, birch, mountain ash and aquatic plants.

MOOSE HUNTING TECHNIQUES

Glass for moose along forest edges, in willow swamps or near other feeding areas. Get to your vantage point early, so you can complete your stalk before the animals retreat to bedding areas.

Float-hunt for moose if preliminary scouting shows abundant sign along the stream bank. The technique works best in early morning and late afternoon, when moose come to drink and to feed on shoreline willows.

PRONGHORN

The fleet-footed pronghorn can reach a speed of 60 mph (96.5 km/h), unmatched among North American big game animals. According to fossil records, they are the only true native big game species on the North American continent. It is thought that all other big game are descended from animals that crossed the Bering Strait from Asia.

Hunters refer to pronghorns as antelope but they are not related to the antelope of Africa. Pronghorns get their name from the sharp prongs that project forward on the horns of bucks. Their upper body is tan; the underside and rump white. The record pronghorn rack has a right horn measuring 17¾ inches (45.1 cm) in length. Its left horn totals 17¼ inches (43.8 cm) long. The animal was shot in Arizona in 1985.

Special adaptations for stamina such as an oversized windpipe and large lung capacity compared to their body size enable pronghorns to maintain high speeds for several miles (km). Their large eyeballs are approximately 2 inches (5 cm) in diameter and their vision is unequaled.

Pronghorns prefer open plains, prairies and treeless foothills. The best habitat has rolling hills sprinkled with water holes and ample sagebrush for food. One study showed that the typical diet consisted of 55 percent sagebrush, 30 percent rabbitbrush, 7 percent grass and 5 percent forbs (broadleaf plants). They feed most heavily in early morning and late afternoon, but may graze anytime day or night. During the spring and early summer pronghorns get most of their water needs met from succulent vegetation in their diet, but in the dry seasons of midsummer and fall they go to a water hole at least once a day.

This animal is wary and nervous and constantly on the lookout for any signs of danger. The pronghorn's sense of smell is good; however, sight and speed are their primary defenses. When alarmed, an antelope flares its white rump hairs or makes a barking sound, alerting others in the herd. Contrary, however, to their skittish nature, pronghorns are remarkably curious and may move a considerable distance to investigate an unusual sight.



Most antelope weigh 80 to 130 pounds (36 to 58.5 kg), with the largest bucks weighing up to 140 (63 kg).

The breeding season begins in August in northern pronghorn range and may occur as late as November in the south. In spring, mature dominant bucks claim territories that contain the best food and water. They vigorously defend the territory against other intruding bucks. As the rut approaches, the dominant or herd buck attempts to gather and keep a large harem of does in his territory, breeding each when they come into estrus. Pronghorn buck fights, as the herd buck chases intruding bucks away, seldom result in serious injury. These distractions can last long enough for a hunter to stalk within range.

Spot-and-stalk is the primary tactic when hunting pronghorns. The hunter glasses, with binoculars or a spotting scope, from a high point of ground. After a good buck is spotted, a stalk, utilizing any available cover, is planned to get within shooting range.

Stand-hunting tactics can be used if a herd shows repeated daily movement patterns. Some hunters set up a blind and wait near a well-used waterhole or fence crossing. Pronghorns prefer to go under or through fences. They habitually cross at the same places, leaving hair on the barbed wire or on the ground. Stand-hunting near these locations is often productive.

Most hunters opt for a flat-shooting rifle, but using the contour of the land a gun hunter may be able to approach within 100 yards (91 m). Bowhunters must get much closer and have developed methods to overcome the limited range of their weapons. Decoying can be an effective method when the bucks are rutting. The hunter puts up the decoy within sight of a dominant buck, hiding behind it, hoping that the antelope will challenge this intruder. Antelope calls may also be used, when decoying, to challenge aggressive bucks. Calls may be used by a gun hunter.

TIPS FOR HUNTING PRONGHORN



Identify bucks by their black cheek patch. Mature bucks have horns that extend above the ears. Some does have buttons or spikes, but they are shorter than the ears.

Challenge a rutting buck during the archery season using a decoy. Never use a decoy during gun season.



Stand-hunt from a blind near a water hole or fence crossing. Or simply hide in a depression.

BLACK BEAR

The complete hunter not only hunts for deer, elk, caribou and moose, but does his or her part to control predator populations. Spring and fall bear hunts offer another chance to pursue your passion.

The black bear is a predator and an omnivore. To some it is a pest, to others a trophy. To all it is an icon of wilderness and wild country. Of all big game animals, bear are the most misunderstood. Black bear are dangerous game because they are unpredictable.

Black bear favor a habitat of mixed conifers and hardwoods, with clearings that produce food. A bear's diet consists mainly of berries, fruits, nuts, grasses and crops. They also eat insects, small and large mammals and fish. In spring, they may feed on carcasses of animals killed by severe winter weather. Bear have an enormous appetite in late summer and fall. A mature boar can gain over 100 pounds (45 kg) in preparation for hibernation.

Bear feed most heavily during cool morning and evening hours. They remain in the shade on hot days because their fur absorbs too much heat from the sun. Windy or rainy weather limits their activity.



With the exception of the June breeding season, males or boars, lead solitary lives. Sows stay with cubs for about 1½ years. Boars have a much larger territory than sows, often over 100 square miles (260 sq km).

They may go into hibernation between October and December depending on the latitude and weather conditions. They remain in their dens until April, although they occasionally wander about during a warm spell. In warmer climates, bear may not hibernate. If they do, hibernation begins later and does not last as long.

Black bear come in color phases. Most are glossy black, brown or cinnamon, but they may be white or even bluish. A large boar weighs 300 to 400 pounds (135 to 180 kg); some exceed 600 (270 kg). Sows weigh about one-third less. The largest black bear on record weighed 802 pounds (360.9 kg). It was taken in Wisconsin in 1885.

Biologists rate the bear among the most intelligent game animals. A bear can run 25 mph (40 km/h) and climb a tree in seconds. They rely mainly on a keen sense of smell to find food and detect danger. They have excellent hearing and fair eyesight.

Even in good bear country, the animals are not abundant, averaging only one bear for every 2 square miles (5.2 sq km). Because bear are scattered, hunters employ techniques seldom used for other big game.

To many, the music of a pack of hunting hounds is what the chase is about. Walkers, black-and-tans or Plotts are most often employed for bear hunting. A bear can run for miles (km) and often loses the dogs. When cornered, it can quickly kill or injure a hound. Some hunters pursue bear solely for the sport of the chase. Once an animal is treed or brought to bay, they call off the dogs and let it go.

Others like the intrigue and challenge of luring a bear with baits. Baiting takes advantage of the bear's highly developed sense of smell. A bear can detect the scent of bait at up to 3 miles (4.8 km) away. This method works in spring when hungry bear emerge from dens and in fall when they feed heavily to build up fat reserves.

Patient spot-and-stalk hunting pays off where the use of dogs or bait is illegal. Hunters choose a canyon where they can watch the edge of a meadow or a patch of berries to spot feeding bears.

Calling works as well. A rodent or a fawn-in-distress call can bring in a hungry or curious bear. Use an electronic call to bring the bear within range. Let the call play constantly for up to an hour or more.

In some regions, damage complaints from bears are at an all-time high. Wildlife biologists have fewer tools today to deal with problem bears. The biologist's best friend is the hunter who has mastered the art of hunting the black bear.

Bear hunters use rifles of at least .30 caliber and bullets that weigh at least 165 grains (10.7 gm). You can kill a bear with a smaller caliber, but a larger caliber is most effective.



If there's one thing a hungry bear wants more than anything else, it's an easy meal. And he's used to taking food away from smaller predators. Black bear will come to a call, but bears have a short attention span. On the way in, he may stumble across a berry patch or a spawning salmon. Keep the sound rolling to keep him on the move. And give him time. Depending on how far he's got to travel, you may see the bruin in a few minutes or an hour. Keep the wind in your favor and your confidence high. Commit to spending an hour at each call set.

TIPS FOR FINDING BEARS



Tracks (left) have distinct claw marks and measure 3½ to 5 inches (9 to 12.7 cm) wide. The front foot is 4 to 5 inches (10 to 12.7 cm) long; the hind foot 6 to 7 inches (15.25 to 17.75 cm).

Damaged trees or bushes are common feeding signs. A bear rips down a branch with its claws, then strips off the fruit or berries.

Droppings reveal what bear have been eating. They often contain berries, grass, hair and wood eaten along with insects.

Bait black bear with food scraps. Cover each bait station with logs to keep out smaller scavengers. Bait several different locations before the season, then select a stand near a bait-site that bear visit regularly.

Follow hounds on foot or horseback until they tree or corner a bear. Hunters scout a potential area to locate fresh tracks, then release the dogs. Even if the scent is cold, good dogs pick up the bear's trail.

WILD BOAR

The Spanish brought the first domestic hogs to California in the sixteenth century. Today, their descendants can be hunted in many places in the South and in California and other western states.

This isn't your average agricultural species. Adult wild hogs tip the scales between 100 and 200 pounds (45 and 90 kg). Boars can reach 375 (169 kg). Most European/feral crosses have a coat of long, coarse, dark hair. Boars grow wicked tusks and are not the kind of animals you'd like to run into on a narrow trail.

Wild hogs come in all shapes and sizes. Long, coarse, dark hair is a characteristic of wild swine, wherever they are found. The ears are small, erect and hairy and tufted at the tips. Tails are long, straight and mule-like, in comparison with domestic pigs. They are lean, with shoulders higher and wider than their hindquarters. A wild boar may stand up to 35 inches (89 cm) at the shoulder. Wild hogs also have longer snouts than domestic swine and longer, sharper tusks (up to about 3 inches/7.6 cm in length).

Wild hogs are also faster runners than their farm-bound kin. They can hit speeds of up to 35 mph (56 km/h).





In periods between rains, you can scout for hogs at watering holes and fresh wallows. Such places will be visited by hogs at least once a day. A word of warning—bag your boar before he's all covered with fresh mud.

They eat everything from acorns to alfalfa, to rattlesnakes and bird eggs. And they multiply. Starting at six months old, a sow can produce piglets at the rate of two litters per year.

There is no limit on hogs in many states. You need a hunting license and you may need a tag. And all your hunting skill.

Spot-and-Stalk for Swine

A spotting scope can help locate hogs, but often, binoculars are all you'll need. You can watch from one vantage point or move from hill to hill. Your best bet is in the first hour and the last hour of the day. Generally, the herd is bedded down for the day, but may get up to move around a little at noon.

Feeding swine don't stay in one place very long. If you spot animals a long way out, watch them long enough to get an idea where they're headed. Then meet them there.

For two or more hunters, it's often better to split up to cover more ground. But hunting should be conducted in a low-impact manner. Stay on roads and established trails and out of bedding areas. Spook the herd and they're likely to leave the area or go nocturnal. When you crest a hill, go easy. Take a few steps then glass the habitat that has just opened up to view.

Hogs aren't known for superior visual acuity, but too often hunters don't give a hog's eyes enough credit. As much as possible, use the terrain and the cover of the trees to get in close enough for a shot.

Wind direction is the biggest consideration. Let them smell you and those hogs will be heading for cover in a hurry. Better to constantly check the way the breeze is blowing and plan your hunt and your stalks to keep the wind in your face.

Hogs are creatures of habit. The same trails are used day after day, season after season, dependent on the food sources. In ranchland, you'll see dozens of broad trails leading from bedding areas to feeding areas. You'll find coarse black hair on the barbs of a fence and deep split-toed tracks at watering areas. Choose a stand where you can keep track of two or more trails at once.

In periods between rains, scout for fresh wallows. Such places are visited by hogs at least once a day.

Guns and Loads for Wild Boar

The wild boar is not easy to kill. It has a tough shoulder hide called a shield that protects it from thorns. Your bullet must penetrate this armor and retain enough energy to destroy the heart or lungs. Often the hog doesn't drop at the first shot.

Many shots have to be taken on the run. A well-balanced rifle can help you get on target fast. Keep the scope dialed down to 3× for quick acquisition of the target. Many hunters choose a 30-caliber like the .308 or the .30-06 while handgun hunters prefer the 44 Magnum.

TYPICAL BOAR BIOLOGY



Males and females both have tusks. They may grow to 5 to 9 inches (13 to 23 cm) long.

Wild hogs have a split toe (right). Large hogs leave the imprint of both the hooves and the dew claws.

SIGNS OF WILD BOAR ACTIVITY

Wallows (left) are used by hogs to coat themselves with mud to keep insects at bay. Look for tracks around water holes and the presence of stirred-up mud in the water.

Two signs of hog activity: rooting for grubs and dried mud on the side of the tree where a big boar scratched.

Between rains, hogs head for water every day. Look for tracks around water holes.

Chapter 5

HUNTING SMALL GAME

The popularity of small game hunting stems from the relative ease of finding game and access. With a little scouting, you can probably locate rabbits, squirrels, raccoons or woodchucks within a few miles (km) of your home. Even with a minimum of equipment, you can find great sport and bring home a tasty meal.

Even the novice has a reasonable chance of bagging rabbits or squirrels. But this does not mean that small game hunting is easy. Your success will improve as your level of skill increases. You can apply the skills you gain to other types of hunting.

Small game hunters have many opportunities to enjoy their sport. Most hunting seasons last at least six months and some are continuous. Because you can find these animals close to home, you can make frequent short trips, which is difficult when hunting most other types of game. Almost all states and provinces have liberal bag limits.

Most hunters use shotguns or rimfire rifles chambered at .17 or .22 caliber. But some prefer a combination gun with a .22 caliber rifle barrel on top and a 20-gauge shotgun barrel on the bottom. Combination guns are ideal for small game because you can fire one barrel at standing animals and the other at running targets. Other hunters employ handguns to bring home the game. You can also use small-caliber center-fire rifles, muzzleloading rifles, shotguns and bows with blunt-tipped arrows.

A pair of waterproof leather boots is a good investment. With the possible exceptions of brush pants, a burr-proof jacket with a game pouch, binoculars and a small knife for field dressing, you need little other equipment.

Many hunters compare rabbit and squirrel meat to chicken. Raccoon tends to be oily and has a distinctive flavor of its own. Small game tastes better if you remove the entrails soon after killing the animal.

COTTONTAIL RABBIT

Rabbits don't require a lot to thrive: a little food, water, shelter and escape cover. They can find everything they need in a few acres (ha) of ground. Best of all, rabbits may be hunted close to home.

Each year, hunters throughout North America bag more than 40 million cottontail rabbits. This staggering total results from the cottontail's tremendous reproductive rate and its ability to adapt to a wide range of habitats and foods.

Cottontails breed in the spring and summer, producing up to eight litters, each with three to six young. They prefer brushy edges and woodlots, but can live almost anywhere, with the exception of dense forests. They eat practically any type of green plant. When green vegetation dies back, they switch to twigs and bark.

Rabbits start feeding before dawn and continue for two or three hours. They resume feeding at sunset. They move about most on calm, sunny days. Rain or wind drives them into heavy cover.

A cottontail spends most of the day sitting in a form, a shallow depression in grass or snow. The grass eventually wears away or the snow melts down and compacts. Often a form is concealed by overhanging grass or other type of overhead cover.



Rabbits use their superb hearing to sense impending danger. To escape, they bolt away on established travel lanes. Cottontails run in an elusive, zig-zag pattern, but their speed is not as fast as a jackrabbit. They average 12 to 15 mph (19 to 24 km/h), but can reach 20 mph (32 km/h).

Normally, cottontails do not run far. Rather than run straight away, a rabbit circles so it can stay in familiar territory. When frightened, it often slips into a woodchuck burrow or brush pile.

You can often bag cottontails by walking through cover, looking for rabbits in their forms. Upland bird hunters flush rabbits by moving in typical walk-and-wait fashion. Like deer, a cottontail becomes nervous when a nearby hunter stands motionless and bounds from its resting spot.

Hunting with dogs offers an interesting and effective alternative. Most hunters use slow-moving hounds such as beagles and bassets. When the dogs get close, the cottontail begins moving in a large circle and eventually passes within shooting range of the hunter. Almost any dog will chase cottontails, but if it works too fast, the rabbit dashes under a brush pile or down a hole.

Rabbits may contract a bacterial disease called tularemia, which causes them to behave listlessly and eventually kills them. But the disease is rare. One researcher found it in only 2 of 12,000 rabbits he examined. Nevertheless, refrain from shooting rabbits that move slowly or otherwise behave unusually. Tularemia can be transmitted to humans who eat or handle the flesh of infected animals.

To hit zig-zagging cottontails, most hunters use shotguns with modified or improved cylinder chokes and No. 6 shot. But when rabbits are in their forms or feeding in the open, reach for a .22 rifle.



Cottontails are named for their fluffy white tail. The fur on the upper part of the body is grayish-brown with black tips. The undersides are white. Adults measure 14 to 19 inches (35.5 to 48.25 cm) long and weigh 2½ to 3½ pounds (1 to 1.5 kg).

WHERE TO FIND COTTONTAILS

Strip cover, like brushy fencelines and hedgerows, makes ideal cottontail habitat. The brush and high grass provide food and cover.



Abandoned farms offer a variety of hiding spots. Look for rabbits around groves, under old machinery or in tall grass or brush.

Brush piles provide good escape cover. A fox or owl would have little chance of reaching a rabbit beneath the logs and sticks.



Tracks of cottontails have side-by-side hind prints ahead of smaller front prints. One front foot falls ahead of the other.



Runways in tall grass serve as escape routes. Rabbits usually follow the same paths through cover, eventually matting down the vegetation.



Feeding signs include girdled shrubs or saplings and cleanly-snipped twigs. Cottontails prefer the bark of sumac and fruit trees.

HOW TO HUNT WITH HOUNDS

Release the dogs where you find plenty of sign. Beagles have excellent noses and scour the ground thoroughly to find fresh scent. They methodically follow the trail, slowly pushing the rabbit ahead.



Wait in the area where the dogs first detect fresh scent. A rabbit usually circles and returns to the spot where it was flushed. If it does not circle, try to predict its escape route, then attempt to intercept it.

OTHER COTTONTAIL HUNTING TECHNIQUES



Walk around the form in ever-widening circles. Look for the rabbit in clumps of brush, around the bases of trees, in tall grass or in any dense cover. Continue walking until you cover the entire area within a 100-foot (30 m) radius of the cottontail's form. Follow any fresh tracks you encounter.



Locate a form with fresh sign. Droppings are round and about ⅜ inch (95 mm) across. A rabbit seldom moves far from its form. Watch for rabbit tracks as you walk a strip of cover like a brushy fence line. A retriever or flushing dog will scare up tight-holding rabbits.

Hunt around abandoned farmsteads. Look for rabbits as you round the corner of a building and be ready for a quick shot. Flush cottontails by beating a brush pile with a stick. Or climb on top of the brush pile, jump up and down and yell to scare out rabbits.

JACKRABBIT

Black-tailed jackrabbits are found in low-lying semi-desert areas of the United States and Mexico. Jackrabbits (which are technically hares, not rabbits) may also be found in typical cottontail country and around tree plantations in more temperate climates. Night feeders, jackrabbits are best hunted in the low light of early morning and in the evening. Landowners are often happy to allow hunting to keep populations from destroying valuable alfalfa and other crops.

The black-tailed jackrabbit grows to a length of about 24 inches (60 cm) and adults weigh between 1 and 2 pounds (0.45 to 0.9 kg). They can reach speeds of up to 35 mph (55 km/h) and can leap up to 5 yards (6m) in a single jump.

One of the most productive methods for hunting jackrabbits is the drive. Groups of three to five hunters work the best. The hunters walk in a line through good rabbit habitat, spread out with about 10 yards (9 m) in between. The preferred tools are .22 rifles and 20-gauge shotguns. Rabbits will be pushed out ahead of the group or hold tight to run the opposite direction after the drive has moved past.



For safety's sake, high-visibility blaze orange is essential on these hunts and the group leader should ensure that the line stays intact.

When flushed, jackrabbits zig and zag, putting brush and distance between the hunter and hunted. Unlike cottontails, jackrabbits don't often circle back, they're headed for the horizon. Be ready, because you'll probably not get another chance.



Although blacktails are largely solitary animals, they may be found in large groups at certain times of the year, especially when feeding on a plot of alfalfa.

SNOWSHOE HARE

The snowshoe is named for its oversized hind feet, which provide a large surface area to support the animal on soft snow.

Snowshoes behave much like cottontails and eat similar foods. But they are more likely to feed at night. They prefer conifer swamps and young hardwood forests rather than brushy edges. Snowshoes are larger, faster and better jumpers.

A snowshoe can run up to 30 mph (48 km/h) and change direction in the middle of a leap, so a tight choke is less effective. To increase their shooting range, many still-hunters use .22 rifles.

Look for a snowshoe's black eye and black-tipped ears when hunting in snow. You can spot the animals more easily after a mid-winter thaw, because their white bodies stand out against bare ground.

Hunting with hounds works as well for snowshoes as it does for cottontails. Like cottontails, snowshoes will stay ahead of a dog and circle back toward a waiting hunter.



Snowshoes, also called varying hares, vary in color depending on the season. The coat is white in winter and brown in summer. Snowshoes are 16 to 21 inches (40.6 to 53.3 cm) long and weigh 3 to 4 pounds (1.3 to 1.8 kg).



Follow tracks after a fresh snowfall. About 2 inches (5 cm) of new snow over a hard crust makes for ideal tracking. If the snow is more than 1 foot (30 cm) deep, a pair of snowshoes make walking much easier.

GRAY SQUIRREL

Because the squirrel can provide a good meal for hawks, owls, weasels, minks, bobcats, foxes, coyotes or humans, he must be alert at all times—whether on the ground or high in a tree. A gray squirrel hunt is a test of marksmanship for any hunter. Using their wide-angle vision and sharp hearing, squirrels quickly detect danger.

To avoid being seen, a squirrel moves to the opposite side of a tree trunk or limb. Or it flattens its body against the tree. Once the hunter has walked past, it scampers to its den and stays there until it feels safe.

Good habitat produces one gray squirrel per acre (ha). Thus, 1 square mile (2.6 sq km) of prime woodlands could hold over 600 squirrels. How plentiful gray squirrels are in a given year depends mainly on the previous year's acorn crop. Other foods include walnuts, hickory nuts, pecans, berries and corn.

Gray squirrels begin feeding just before sunrise and they continue for two or three hours. They resume feeding in late afternoon and may remain active until after sunset. Squirrels move about most on calm, sunny days. Extreme cold or windy weather keeps them denned up. They seldom travel more than 300 yards (274 m) from their dens.

Mature deciduous forests throughout eastern North America hold gray squirrels. They favor mixed hardwoods with an abundance of mature oaks, dense undergrowth and few open areas.



Gray squirrels have a grayish back and sides and whitish or brownish undersides. A solid black color phase predominates in some areas. Adults measure 14 to 21 inches (35.5 to 53.3 cm) from head to tail and weigh ¾ to 1½ pounds (0.3 to 0.7 kg).

FOX SQUIRREL

Named for its reddish, fox-colored fur, the fox squirrel differs from the gray in behavior and habitat. Some hunters maintain that it is less wary and easier to outwit.

Fox squirrels spend more time on the ground than grays and rely less on treetops as escape routes. When threatened, they run straight for their dens or hide behind trunks or limbs. Unlike grays, they seldom feed in early morning. They are more active during midday and stray farther from their dens. Fox squirrels can often be seen lying on a limb basking in the sun.

Many hunters refer to fox squirrels as red squirrels. But the true red squirrel is much smaller and is not considered a game animal.

Fox squirrels prefer woodlots, farm groves and strips of timber rather than forests. Like grays, they eat acorns and other nuts. In agricultural areas, corn and other crops make up a high percentage of the diet. Squirrels get most of their water from their food.

Both gray and fox squirrels make a variety of calls. A series of rapid cherks or barks serves as a warning signal to other squirrels. The familiar chatter means squirrels are approaching one another. A low-pitched chuckle signifies contentment.



Adult fox squirrels measure 19 to 29 inches (48.25 to 73.75 cm) from head to tail and weigh 1 to 2¾ pounds (0.45 to 1.2 kg).



Hickory trees produce nuts that draw squirrels. You can easily identify hickories in early fall; they turn yellow earlier than other trees.

SIGNS OF SQUIRREL ACTIVITY



Acorn shells at the base of a tree indicate a squirrel den somewhere above. Sign in a large forest is usually left by grays.



Stripped corncobs also reveal squirrel activity. Sign along a fence line or in a small woodlot is generally that of fox squirrels.



Dens are made by squirrels gnawing at small openings like woodpecker holes. Dens are about 4 inches (10 cm) wide and at least 10 feet (3 m) off the ground.



Nests consist of twigs and leaves piled into a crotch or woven into the branches. Nests are 1 to 2 feet (30 to 60 cm) across and 20 feet (6 m) or more above ground.

Hunting for Squirrels

Look for stands of oak trees or other nut-producing trees. An old apple orchard close to timberlands may also produce good hunting.

Mast crops very from year to year and squirrels locate near this food. During late summer squirrels eat wild cherries, poplar buds, maple seeds, mulberries, gum berries and fruits, or the seeds of trees that ripen early.

As fall progresses squirrels start their heaviest feeding of the year, preparing for winter. They cut or feed on the nuts of pecan, hickory, walnut, oak or beech trees. Piles of small pieces of chewed nut hulls dropped on the ground under these trees, called cuttings, are evidence of feeding.

In agricultural areas, squirrels concentrate near cornfields; look for sign where squirrels have climbed cornstalks to eat the kernels off the cob or where they have pulled down the cobs.

During the warm days of early and mid-fall squirrels may start feeding at night and continue until after daylight, resting during the warm part of the day and feeding again in late evening. Feeding and storing nuts for winter lasts longer into the daylight hours as the season progresses. Later in the season squirrels spend more time on the ground gathering, digging and storing.

Hunting can be good during the squirrel's major breeding period, which starts in December or January. Squirrels lose their normal caution as they begin courtship, paying less attention to hunters.

The still-hunter watches for the slightest movement, the twitch of an ear, the flicker of a tail, the shine of an eye and listens for the cutting of teeth on nuts or the skittering of claws on bark. Freeze and investigate each noise. Windy or rainy weather covers your sound, allowing you to move through the woods with more stealth.

Stand-hunting can be the most productive tactic when the woods are too noisy to still-hunt. Sit quietly in a feeding area, watching for movement. Remain still after shooting one; sometimes squirrels resume normal activity after a few minutes.

Most squirrel hunters use .22 rifles with scopes up to 4×. Shotguns are a good choice; carry a .410 or a 20 or a 12-gauge with No. 6 shot.

Hiding on the opposite side of a tree trunk is the squirrel's favorite method of eluding the hunter. No matter where the hunter is, the squirrel is always on the other side of the tree.

HOW TO STAND-HUNT FOR SQUIRRELS



Sit quietly, glassing trees with binoculars. Choose a spot with the sun at your back. That way, you can see squirrels but they may not see you.



Call to coax squirrels into revealing themselves. Calls include a blow call (left) and a bellows call (right). Either can be used to produce barks and chatters.



Click coins together to imitate a scolding squirrel. Place one coin slightly lower than the other and rapidly snap the lower coin.

OTHER SQUIRREL HUNTING TECHNIQUES

Team-hunt with a companion. With this method, squirrels cannot hide on the opposite side of a tree without being seen. Be ready to shoot the moment a squirrel moves to your side of the tree.

Toss a stick or rock to the opposite side of a tree. Or tie a string to a bush on one side of the tree, then move to the other side and tug it sharply. The motion will frighten squirrels to your side.



Float-hunt along streams bordered by nut trees. The extra sunlight and moisture result in good nut crops that attract squirrels.

PRAIRIE DOG

The prairie dog is a creature of the western plains, found in the United States, Canada and Mexico. It grows to a length of 12 to 16 inches (30 to 40 cm). Prairie dogs live in large colonies or dog towns that can cover hundreds of acres (ha) of land.

They live in groups that consist of one male and two to four females. Females have one litter a year and give birth to an average of three or four pups. Prairie dogs feed on grass, insects and broadleaf plants. A great tunneler, this creature may dig 15 feet (4.5 m) downward and 100 feet (30 m) in a lateral direction. A tunnel system generally has several escape tunnels. The prairie dog has color vision and can detect danger at a great distance. To warn each other, prairie dogs use vocalizations.

Hunters can use rimfire rifles, but most hunters find that a center-fire rifle is a better choice to make shots on animals out to 400 yards (366 m). The 204 Ruger, 223 Remington and 22-250 Remington, stoked with thin-jacketed bullets are great options for prairie dog hunting.

A variable rifle scope is a big help out on the fields. And a bipod or shooting sticks can make the difference when every little bit of accuracy counts. Often the quarry is almost hidden behind a mound of dirt, leaving you a target no bigger than a silver dollar.



Prairie dogs may emerge from their dens during late winter warming trends, and are quite visible against the snow. Prairie dogs have dichromatic color vision, which allows them to detect predators over a long distance. A system of vocal communication enables them to quickly spread the alarm.

Herbivorous, the prairie dog thrives on a diet of grasses and broadleaf plants. Grasses are trimmed around the colony to remove cover that might hide a coyote, fox, or ferret.

GROUND SQUIRREL

Without food cultivated by humans, ground squirrels do not often grow out of balance. They live in small groups and are kept in check by birds of prey and sharp-toothed predators. But give a rodent an alfalfa field and everything changes. Before long, food becomes so plentiful that they don't have anything left to work at except procreation. Soon there are more ground squirrels than a rancher can feed.

Ground squirrels are members of the family Sciuridae, of the Marmotini tribe. Several different types of ground squirrels can be found. In some cases, the ground squirrel is found in small numbers and can be still-hunted. In cultivated fields, a hunter might spend all day in one place, shooting from an elevated stand.

As a team, two hunters can take turns spotting and shooting. Binoculars can help the spotter direct the shots. Such work makes both hunters more proficient. For the young shooter, looking forward to his or her first big game season, the practice is invaluable. April and May are the prime months for shooting as crops sprout and grow through last year's stubble. By mid-June, the grass may be too tall for spotting.



Property owners are often happy to let you shoot, but permission must be obtained. Keep in mind that well-traveled highways carry the most hunters and access might be easier to find off the beaten path. Establish relationships with landowners prior to the hunt or contact an outfitter for a guided shoot on private land.

For years, hunters have used rimfire .22s to good effect, but today there are better choices. The .22s, except in the most practiced hands, are rarely accurate past 100 yards (91 m).

An alternative is one of the 17 caliber rimfires. Based on the .22 Long Rifle or the .22 Magnum case, the 17-caliber bullet tips the scale at half the weight of the .22 projectile and can be accurate to 200 yards (183 m).

Abundant ground squirrel populations offer hunters the chance to improve long-range shooting skills. Over the course of a long day in the field, a marksman may fire 500 rounds or more.

RACCOON

Equipped with needle-sharp teeth and a quick temper, the raccoon is a fighter and a challenge to the houndsman/hunter. They may run for miles (km) and when cornered, can kill or maim hunting dogs twice their size.

Hardwood forests near water make good raccoon habitat. They also live in marshy lowlands and can adapt to habitats ranging from the Florida mangroves to the arid plains of New Mexico.

Raccoon eat almost any kind of food including berries, fruits, nuts, frogs, crayfish and insects. Sweet corn is a favorite. They hold their food with small, nimble paws.

An adult raccoon may travel up to 5 miles (8 km) on its nightly feeding rounds, especially in warm weather. During the day they often den up in hollow trees. But they may bed in the tall vegetation along the edge of a marsh, in a culvert or in the ground burrow of another animal. Raccoon frequently use different dens or beds on successive days. They den up for a period after heavy snow; in cold climates they may hibernate.

Ranked among the most intelligent game animals, raccoon also have excellent hearing and good eyesight.



Raccoon have a black, mask-like band across the eyes and black rings on the tail. Most raccoon weigh between 15 and 20 pounds (6.75 and 9 kg). The largest on record, 62 pounds, 6 ounces, (28.1 kg) was shot in Wisconsin in 1950.



They can run up to 15 mph (24 km/h) and are good swimmers.

The vast majority of raccoon hunting is done with hounds, especially Walkers, black-and-tans and redbones. Tracking is easiest on damp, cool nights with a slight breeze. Some dogs can pick up a cold trail, making it possible to hunt in daylight.

When pursued by hounds, raccoon usually run in large circles, crawling in and out of holes and climbing up and down trees to lose the dogs. They may jump to the ground from as high as 50 feet (15 m) and scurry away unharmed. They stay in a tree only when the hounds get so close that other avenues of escape are impossible.

Early in the season you may be able to call raccoon. After dark, take a stand along a stream bank, lakeshore or cornfield. Use calls to imitate an injured bird or rabbit.

Most raccoon hunters use .22 rifles, although some prefer 20-gauge shotguns with No. 6 or 7½ shot. Where legal, a few hunters use small-caliber handguns.

WHERE TO FIND RACCOON



Look for holes in trees that could be den sites (left). You seldom see raccoon during the day, but an area with many dens would be a good spot to hunt after dark.

Check for tracks in the soft dirt around ponds, marshes or streams. Raccoon go to water to drink and to find foods like crayfish, frogs and small fish.

HOW TO HUNT WITH HOUNDS



Release the hounds and allow them to range ahead to pick up raccoon scent. To better control the hounds, some hunters keep them on leash until the dogs detect fresh scent, then turn them loose (left).

Listen for the hounds to start baying, then follow the sound. Some hunters use orange or red headlamps to find their way through the woods. The colored light is less noticeable to a raccoon than a white light.

Continue to follow the dogs until they either tree the raccoon or lose it. Sometimes the chase goes on for miles (km). Hunters can tell when their dogs tree a raccoon, because the baying becomes more intense.

COYOTE

The coyote, once an inhabitant of the Western plains, has spread across the continent. They are thriving now because of humans. In the late-1800s and early-1900s, ranchers and trappers declared war on wolves. For decades, the coyote's ancient enemy has been largely absent from the lower 48 states. With little competition, coyotes have taken over. And, they have become educated about how to live around people. Even within the city limits of big cities, coyotes prowl golf courses and fields in search of their prey. In the suburbs, residents complain about the coyotes that roam at will, eating from dog food dishes and garbage cans or picking up unsuspecting dogs and cats.

A good place to hunt coyotes is wherever they can find their principal foods. Fields, meadows and prairies are full of mice; brushy draws hold rabbits and upland birds. Wherever there are antelope or deer, there will be coyotes close by. In the spring when ungulates are giving birth to their young, a fawn-in-distress call can draw in predators.

When you find an area that has all the right coyote foods, look for sign. Coyotes use trails and waterholes just like the other animals. If there are coyotes in the area, you'll soon see their sign.



An adult coyote stands less than 24 inches (61 cm) tall and varies in color from whitish-gray to brown with sometimes a reddish cast to its pelt. Ears and nose appear long and pointed, in relation to the size of its head. It weighs between 20 and 50 pounds (9 and 22.5 kg) and can be identified by a thick, bushy tail, which it often holds low to the ground. He is an extremely lean, fast animal that may reach speeds up to 43 mph (69 km/h).

Coyote droppings are about the same size as a dog's of similar size but the scat is small and twisted on the end. It contains undigested bits of whatever the animal has been feeding on. Deer hair, bits of rabbit and mouse fur and even berries are found in coyote droppings.

Coyotes also need a den to raise their pups in spring and summer and for shelter in extreme conditions. A good coyote hunting area will be adjacent to food sources but also give ample cover to hide from their enemies.

In September and October the young of the year are out searching for food on their own. The population is strongest at this time of the year and many coyotes are taken during deer and elk seasons. But the coyote pelt is best after the first snows and a tanned pelt or a coyote rug makes a fine trophy to remember a successful hunt.

Calling Coyotes

A fawn-in-distress or a dying rabbit predator call costs only a few dollars and can be easily mastered. Electronic calls with remote controls and motorized decoys cost more, but provide a way for the hunter to watch the call from a distance.

The first two hours and last two hours of daylight are the best times for calling. A coyote may respond anytime of day but the likelihood is greater at first and last light.

The coyote knows that the sound of a rabbit or a rodent in distress means an easy meal, if it can take the prey away from whatever is killing it. That is why sometimes a dominant coyote comes right in while a younger dog might be hesitant.

Put fright and pain in the calling. The first sounds a rabbit makes when it is captured are a series of squalls

Coyotes normally have a territory of 10 to 40 square miles (26 to 104 sq km). They can sprint up to 35 mph (56 km/h), fast enough to overtake a deer. A coyote's track looks similar to that of a domestic dog.

which then become gasping cries. If the predator shifts its grip then the squalls might come again.

Study the land and determine likely approaches a coyote might make. The wind is of paramount importance. Situate yourself downwind from where the coyote is likely to be. Situate hunting partners up to 50 yards (45 m) away from the caller.

Wear full camouflage and grease paint on hands and face. Keep all movement to a minimum. As coyotes approach they zero-in on the location of the caller.

Call in one location for at least 20 minutes. Depending on the topography you might need only move a quarter of a mile before calling again.

For a dedicated coyote rifle, the best choice might be one of the flat-shooting .22 center-fires or a 6mm or .243. Beyond these, any rifle a big-game hunter is proficient with is the perfect choice for coyotes.

For calling situations where the coyote is likely to come in close, a shotgun is ideal. Use a load with sufficient knockdown power in the range between No. 2 and 00 buckshot.

Coyotes perform a valuable function, keeping rodent and rabbit populations in check. However, as coyote populations increase they can put a severe dent in the numbers of deer and antelope herds.

Coyotes are on the move when snow is on the ground. The cold weather speeds up metabolisms, making them vulnerable to the sound of a prey animal in distress.



A shot at a coyote might be taken as close as 10 feet (3 m) or as far out as 300 yards (274 m). A good coyote gun should be able to accommodate either circumstance.

Some callers use confidence decoys to lure the coyotes in. Jackrabbit, cottontail and fawn decoys give the coyote something to look at as it approaches. Other hunters simply use an old stuffed animal that approximates the natural.

Chapter 6

HUNTING UPLAND GAME BIRDS

The memories that are made in the fall are the kind of images that stay with you for the rest of your life.

Dried stalks of corn rattling with the November breeze and the sudden rush of wings that is a gaudy ringneck rooster clawing for altitude. Chukar running the ridge top in front of a flushing dog, then a dozen birds briefly silhouetted against the sky. A German shorthair quivering on point, his eyes locked on a patch of color in the grass. The heft and grace of a fine double gun coming to your shoulder.

Upland bird hunting is a multi-faceted sport. Bird hunters cherish guns that they shoot well and spend months training their dogs for a few days afield each year. Some hunters focus on one or two species, but the continent holds a variety of game bird opportunities, from farmland pheasants to mountain quail, to the challenge of chukar.

Upland gunning is sport for hunters of any economic background and experience. Upland bird hunts are the province of anyone with a shotgun and a license, whether a nine-year-old novice or a well-traveled sportsman.

The term upland means high ground. But upland birds can also be found in and around lowlands. Pheasants frequent marsh edges and sharp-tailed grouse often live in bogs. Migratory upland birds also congregate in lowland areas. Woodcock feed along moist stream banks and mourning doves gather near water holes.

Upland bird hunters need little equipment other than waterproof boots and a thorn-proof jacket and pants. With the exception of the small-caliber rifles used for wild turkey, upland bird hunters almost always use shotguns. The choke and shot size varies with the size of the bird and the usual shooting distance.

RING-NECKED PHEASANT

Imported from Asia in the 1880s, the pheasant fast became a favorite. The bird is a walking, flying kaleidoscope of color. Flashing blue, purple, copper and iridescent green, it rises out of the amber grain in a blur of wings and sound.

The pheasant deserves its reputation as one of the most wily and elusive upland game birds. Its first instinct is to run rather than fly. And despite its large size and gaudy colors, a rooster can slink away unnoticed in ankle-high cover. Sometimes a bird sits tight, refusing to budge unless you actually step on it.

Pheasants rely on excellent eyesight and good hearing to elude hunters. They can detect ground vibrations not recognizable to humans. These vibrations often cause roosters to crow.

Ringnecks thrive in fertile agricultural areas with good nesting and wintering cover. In spring, they nest in moderately dense cover like hay meadows, clover fields and roadside ditches. They continue to use these areas as roosting sites into the fall, but also roost in weedy crop fields, short slough grass, willow patches and woodlots. They occasionally roost in trees. Pheasants need heavier cover to escape winter storms.



Primary foods include grain crops like corn, wheat, milo and soybeans. They also eat weed seeds and insects. The birds pick up grit in fields and along roads. This helps their gizzard to grind food.

From June through August, hen pheasants remain with their broods of four to eight chicks. By fall, the chicks begin to mature and the groups break up. As winter approaches, pheasants often flock together where they can find food and heavy cover. Flocks may contain hundreds of birds.

Despite the fact that pheasants are among the hardiest of game birds, their average life-span is only nine months. Normally, only 30 percent of the birds survive from one year to the next, even where there is no hunting season.

In most states and provinces, only roosters are legal game. Pheasant roosters can mate with many hens. Research has proven that hunters can harvest up to 90 percent of the roosters without affecting the next year's hatch.

Hunters can quickly distinguish the colorful rooster from the drab hen. In addition, roosters often cackle on take-off, removing any doubt about the bird's sex. The typical rooster measures 30 to 36 inches (76 to 91 cm) from head to tail and weighs 2½ to 3 pounds (1 to 1.3 kg). The hen has a much shorter tail and weighs about ½ pound less (0.25 kg).

Roosters have spurs on the lower part of the leg. The spurs grow longer and sharper as the bird gets older, reaching ¾-inch (1.9 cm) on three-year-old birds. They use their spurs in spring territorial battles. The sharp spurs on an old rooster can badly scratch a hunter or a dog.

When a rooster bursts from cover, it quickly reaches a speed of 35 to 40 mph (56 to 64 km/h). It may fly up to 1 mile (1.6 km), but usually only a few hundred yards (m). A bird generally spends its entire life in an area of ½ square mile (1.3 sq km) or less, leaving that area only if food or cover becomes inadequate.

Hunting pheasant is most glorious for what returns in memories. Good friends, a hard-working dog, long-tailed birds and sunlight on steel barrels.

WHERE TO FIND PHEASANTS

Wild ringnecks are often found in wheat, corn, barley and milo fields, feeding on grain, weed seeds and insects. Thick, brushy cover along fence rows, ditches, streams and marshes provide cover.

Pheasants feed in the morning and evening, then retreat to rest. Ideal habitat includes water, cover and feed within a short walk. Early morning and evening are good times to listen for calling.

When working brushy fence rows, one or two drivers should bust through the weeds with a dog, searching a ragged pattern back and forth. Post another hunter at the end of the row to jump skulking birds into the air. Expect pressured pheasants to seek out steep, brushy draws that defy all but the most determined.



Ringnecks get their name from the white ring around the rooster's neck. Both sexes have brownish tails with black crossbars. The rooster has a reddish-copper breast and a powder-blue rump. Its head has shades of metallic blue, green and purple with a bright red eye patch.



The hen is tan with dark flecks and creamy mottling.

TYPICAL PHEASANT HABITAT

Nesting cover is vital to pheasants (left). Hens need grassy cover at least 12 inches (30 cm) high which remains unmowed until after nesting.

Fertile croplands offer a good food supply. But expanses of corn and other row crops with little cover support few pheasants.

Winter cover includes cattail sloughs, thick brush or willows and woodlots. With good cover, pheasants can survive to –50°F (–45°C).



When hunting in standing corn, post blockers at the end of the rows to jump roosters into the air. Avoid shooting at birds until they are above the stalks to avoid endangering other hunters.

Pheasant Hunting Strategies

The pheasant hunting season can be split into two parts: the first few days and the rest of the season. Young pheasants lack the wariness of birds hatched the previous year, so the early days of the season usually offer the easiest hunting. Once the easier birds are gone, you will find it much more difficult to outwit the remaining roosters.

EARLY SEASON. You can locate a good area before the season opens by driving through the countryside and looking for pheasants. The best time to spot the birds is around sunrise on a clear, calm day with dew on the grass. You may also see pheasants in late afternoon. Another way to locate a good hunting area is to look for abundant nesting cover. Chances are there are birds in the vicinity. If you find a promising location, ask the farmer if you can return to hunt once the season begins.

Early-season hunters often find most of the land covered with crops. In this situation, pheasants may be almost anywhere. To flush birds from large crop or stubble fields, hunters conduct drives. With this much cover still standing, other techniques may not be as productive.

Ringnecks usually flush close in early season, so a shotgun with an improved cylinder or modified choke works best. Use shot no larger than No. 6.

LATE SEASON. Once farmers harvest their crops, the birds have fewer places to hide. But birds that survive to late season have learned to evade danger and often flush far ahead of approaching hunters. Or they hold extremely tight and let hunters walk past.

In late season, roosters hole up in much heavier cover than they did earlier in the year. They prefer areas with tall trees or other cover that breaks the wind. Look for them in brushy woodlots, thick fence lines and drainage ditches lined with slough grass. A favorite hiding spot is a fringe of cattails around the edge of a shallow wetland. Although it prefers heavy cover, a late-season rooster sometimes seeks refuge in a patch of grass not much larger than his body. After a snowfall, hunters often find pheasants under clumps of grass covered with snow. The birds evidently allow themselves to become snowed in.

To bag late-season roosters, one hunter blocks a possible escape route while another approaches from the opposite end of cover. If a rooster flushes too far ahead of the walking hunter, the blocker may get a shot.

For long-range shooting in late season, use a modified or full choke shotgun with No. 4 to 6 shot.

Hunting Pheasants with a Dog

Statistics show that hunters who use dogs bag twice as many ringnecks as those who do not. Most hunters agree that flushers and retrievers work best in heavy cover. Preferred breeds include springer spaniels and Labrador retrievers. Some hunters prefer pointing dogs for large expanses of light, grassy cover, but a wily rooster often runs rather than hold to a point.

A dog with good retrieving skills seldom loses a crippled ringneck. Pheasants are notoriously difficult to kill. A wounded rooster usually runs off and burrows under heavy grass or brush, where a hunter without a dog would have practically no chance of finding it. A good dog marks the bird down and relentlessly pursues it through even the thickest tangle of vegetation.

Skilled handlers refuse to work their dogs in standing cornfields or fields of other tall row crops. To a ringneck, an open row is an invitation to run. And most dogs follow, often disappearing into the field and flushing birds at the opposite end.

A novice pheasant hunter tends to over-command his dog, continually directing it to hunt likely-looking spots. Instead, let the dog use its nose to decide where to hunt. Allow it to range back and forth across cover until it finds fresh scent.

Hunt strip cover with your dog on the downwind side. When the dog detects fresh scent, it moves into the cover and flushes or points the bird. Late in the season, another hunter should post at the end of the strip.

Follow your dog through a large expanse of cover. A flushing dog may run when it picks up a scent. You must keep up so birds do not flush out of range. With pointing breeds, you do not have to stay as close.

Send your dog into a thick patch of cover to save you time and energy. Keep track of its location by watching and listening for moving grass or brush. Or, attach a bell to the dog's collar.

General Tactics

A ringneck's inclination to run rather than fly makes it one of the most difficult birds to hunt by yourself. But you can greatly improve your odds by choosing the right type of spot and by using proven techniques.

You are most likely to flush pheasants from small, isolated pieces of cover, such as a patch of short slough grass surrounded by a plowed field. In a large block of heavy cover, a rooster can easily give you the slip.

If you walk steadily in a straight line, pheasants probably sit tight and let you pass. But if you follow a zig-zag path, walking a few steps, then stopping for a moment, nearby pheasants generally become nervous and fly.

Watch and listen carefully for any indication of pheasant movement. If the cover is not too thick, you might catch a glimpse of a rooster running ahead. On a still day, you may hear the slight rustling of a rooster sneaking through the grass.

Driving for Pheasants

Driving takes advantage of the ringneck's habit of running at the sight or sound of humans. A row of hunters moves through all or part of a large block of cover, while posters wait quietly at the end.

Drivers may flush some pheasants, but more often the birds run to the end of the field. When the drivers approach the posters, the birds realize they are trapped and explode from cover.

TIPS FOR HUNTING PHEASANTS



Select manageable-sized pieces of cover. Try to push the birds toward a spot where the cover suddenly ends. Pheasants are reluctant to run into an open field and usually flush near the edge.



Look for the tallest, thickest cover, especially in cold or windy weather. Trees or tall weeds offer better shelter than the surrounding lower cover.

Hunt the sunny side of cover on frosty mornings. Pheasants move to the sunlit side to warm up and dry ant moisture on their feathers. Later in the day, the birds may retreat deeper into the cover.

Follow fresh tracks in the snow. Rooster tracks are slightly larger and farther apart than those of a hen. Often the tracks end at a snow-covered clump of grass. You may have to kick the clump to flush the bird.

Drive pheasants from the heaviest cover to the lightest. Pushing birds into sparse vegetation forces them to fly. If you drive from light to heavy cover, the birds are more likely to find a safe hiding spot.

Avoid driving into the sun, especially when it is low in the sky. The glare may blind you or prevent you from distinguishing a rooster from a hen. If you must hunt into the sun, listen for a cackle or look for a long tail.

Leapfrog stretches of cover. Drop off a partner, drive ahead, then start walking. He or she walks to the car, drives ahead of you, then resumes walking.

Choose dirty crop fields when hunting ringnecks. The weeds provide cover and food that is lacking in clean, well-manicured fields. Look for the tallest, thickest habitat, especially in cold or windy weather. Trees or tall weeds offer better shelter than the surrounding lower cover.

If the field is too wide to cover in one pass, the posters can take a vehicle to the end they are blocking. The drivers can take the vehicle back to the opposite end, then make another drive. Or the posters can return, while the drivers start another pass from the end where they finished.

When driving cover that narrows toward one end, start from the widest end. This way you will push the birds into a smaller area, increasing the likelihood of someone getting a shot.

BOBWHITE QUAIL

A covey of bobwhites exploding from cover can rattle even the veteran hunter. Often, each bird flies in a different direction. In the confusion, you may shoot hurriedly without touching a feather.

Despite their stubby wings, quail can fly up to 30 mph (48 km/h) and change direction instantly as they dodge through cover. But they usually fly less than 200 yards (183 m). Bobwhites are also excellent runners; in fact, they seldom fly unless threatened.

When alarmed, a member of the covey emits a barely audible signal which tells the others to freeze. They squat and remain motionless, relying on camouflage for concealment until the threat passes. If they feel too conspicuous, they scurry to another hiding spot.

Cocks have a white throat patch and a white line through the eye. On hens, the throat patch and line are buff-colored. Bobwhites measure about 10 inches (25 cm) long and weigh 6 to 8 ounces (170 to 226 g).

Unlike pheasants, bobwhites are monogamous, meaning that a cock breeds with only one hen. Quail eggs hatch from May to early July. The cock helps incubate the eggs and raise the chicks. By the start of hunting season, the chicks resemble the adults and the covey consists of 10 to 15 birds.





Bobwhite quail roost on the ground. During cool weather, they form a roosting ring, huddling in a plate-sized circle with their tails pointing toward the center. This tactic preserves body heat. Bobwhites prefer a roosting site with plenty of open space above them, enabling them to flush quickly should the need arise. Roosts generally have a south or west exposure, so the ground stays warm in late afternoon.

The birds thrive in areas with a mixture of grasslands, woodlands and brush adjacent to croplands. They use grasslands mainly for nesting; woodlands and brush provide roosting and escape cover. Bobwhites cannot survive in a climate with prolonged periods of deep snow or severe cold. They are unable to dig through deep snow to find food and their small bodies do not retain enough heat.

Nearly all bobwhites live within 50 to 100 feet (15 to 30 m) of field borders. They are seldom found in the middle of a crop field or woods.

The bobwhite's diet consists mainly of weed seeds, but they also eat insects, acorns and crops like corn, soybeans, wheat and milo. On hot, clear days, the birds feed in early morning and late afternoon. In midday, they take periodic dust baths along sunny field edges. But during cool, damp weather, bobwhites often stay in their roosts until mid-morning, feed intermittently until dark, then return to their roosts.

Each year, predators, severe weather and hunting take a heavy toll on the bobwhite population. On the average, a bird lives about 8½ months; only 15 to 20 percent survive to the next breeding season.

Hunting for Bobwhite Quail

To many bobwhite hunters, the biggest thrill comes from watching good pointing dogs in action.

A lone hunter who works the cover slowly and thoroughly can kick up some bobwhites by himself. But if the birds decide to hold tight, hunting can be extremely difficult without a dog.

Most hunters prefer English pointers or English setters for large expanses of cover. Brittanys and German shorthairs also work well, but do not cover quite as much ground. Handlers allow the dogs to range far ahead of the hunting party. When a dog detects fresh scent, it locks on point. The covey freezes, giving the hunters plenty of time to move into position.

Most of the birds burst from cover in unison. After the initial flush, work the area a little longer because a straggler or two may remain. Flushing the last birds is often more difficult.

Quail usually fly only a short distance, so you can flush them again. Sometimes the covey stays together, sometimes it breaks up. Watch carefully because the birds may veer off to the side just before they land.

Early season offers the best bobwhite hunting. Coveys consist mainly of young birds that have never been hunted. But as the season progresses, quail become much more unpredictable. Some birds flush when you slam your car door. Others run rather than hold. Flushed birds fly two or three times farther than they did in early season.

Finding downed quail can be difficult, even with a good dog. Some hunters maintain that the scent washes off as the birds fly. On the ground, bobwhites compress their feathers so little scent can escape. Bird dogs may walk within inches (cm) of wounded quail without finding them. Because of their small size and excellent camouflage, quail can hide in the lightest cover. Wear snakeproof chaps or leggings to protect yourself from snakebites. They also protect your legs from tough thorns and briers.

Many quail hunters prefer 20-gauge, double-barreled shotguns with improved cylinder and modified chokes. Small shot, usually No. 7½ or 8, works best.

WHERE TO FIND BOBWHITE QUAIL



Osage orange means good quail cover. Its sharp spines prevent cattle from eating the underbrush. Look for the large, yellow fruits.

Giant ragweed provides roosting and escape cover. The plants stand up to 12 feet (3.6 m) tall. Ragweed seeds may be a major source of food in fall.

Lespedeza or Japan Clover, produces seeds which quail eat in winter. Found mainly in the southern United States, it is planted for erosion control.

BOBWHITE HUNTING BASICS

Pick a single bird and concentrate on that shot. Resist the tendency to flock shoot. A wild shot at the covey rarely brings down a bird.



Learn to judge your effective shooting distance. Because bobwhites are so small, they are probably closer than you think.



Wear snakeproof chaps or leggings to protect yourself from snakebites. They also protect from tough thorns and briers.

Listen for the typical bob-bob-white whistle during the mating period. You will find birds in the same area once the hunting season opens.

CALIFORNIA QUAIL

California quail are also called valley quail. They prefer semi-arid desert brushlands. They feed on the seeds of weeds and brush and roost in dense patches of tall shrubs or low trees. The birds need water each day and are seldom far from streams, springs or water holes.

In fall, they form large flocks numbering from 50 to over 100 birds. They prefer to run rather than fly. When flushed, they usually go only a short distance, then land in bushes or trees.

A good pointing dog can pin down an entire covey by circling the birds. If they fly, watch where they land. They hold tighter on the second flush.

Ideal shotguns for California quail are 12- or 20-gauge double barrels with modified and improved cylinder chokes. These guns give you an open pattern for birds that hold and a tight pattern for those that flush at long range. Most hunters use No. 7½ shot.

California quail, also called valley quail, can be found up and down the West Coast of North America, from southern British Columbia to the tip of the Baja Peninsula. They are a ground-dwelling and foraging bird that seldom moves far from the place where they were hatched. The coveys feed on seasonal seeds, leaves, and insects and search out sunny spots to take communal dust baths.

In fall, they form large packs numbering from 50 to over 100 birds. They prefer to run rather than fly. When flushed, they are loud flyers, bursting like popcorn from cover. They scatter to confuse predators and seldom fly very far, landing in bushes and trees.

These quail are native to the Southwest, but they have been introduced to other places around the world, including Australia, New Zealand, and Hawaii.

California quail prefer semi-arid desert brushlands. They feed on the seeds of weeds and brush, and roost in dense patches of tall shrubs or low trees. The birds need water each day and are seldom far from streams, springs, or water holes.

A good pointing dog can pin down an entire covey by circling the birds. If they fly, watch where they land. They hold tighter on the second flush.

Ideal shotguns for the quail on these pages are 12- or 20-gauge double barrels with modified and improved cylinder chokes. These guns give you an open pattern for birds that hold and a tight pattern for those that flush at long range. Most hunters use No. 7½ shot.





California quail have a scaled breast, grayish brown flanks with white streaks and a teardrop-shaped plume. Males have a black throat with a white border and a chestnut patch on the belly. Females are less boldly marked. California quail weigh 6 to 7 ounces (170 to 198 g).

GAMBEL'S QUAIL

Sometimes called desert quail, Gambel's quail are usually found along brushy slopes and in river valleys of arid and semi-arid deserts. They roost in dense thickets or trees and feed on the seeds of weeds and brush. Normally the birds get enough water from their foods and the dew. But during dry conditions, they rely on a watering site.

The birds come out to feed early and late. They spend the rest of the day in brushy cover to escape the heat. In cool weather, they leave their roosts earlier and may remain in the open all day.

If you approach Gambel's quail in the open, they will probably run before you can get a shot. But if you wait until they move to cover, the birds are more likely to hold. A good pointing dog improves your odds.

Poisonous snakes are rarely a problem, but some hunters wear leather or plastic leggings.

The Gambel's quail was named after William Gambel, a 19th century explorer of the southwestern United States. Sometimes called desert quail, Gambel's quail inhabit the southwestern desert country of California, Arizona, Colorado, New Mexico, Nevada, Texas, Utah, and Sonora, Mexico. Non-migratory, they are usually found along brushy slopes and in river valleys of arid and semi-arid deserts. They roost in dense thickets or trees, and feed on the seeds of weeds and brush. Normally the birds get enough water from their foods and the dew. But during dry conditions, they rely on a watering site.

The Gambel's average length is 11 inches (30 cm). It has a wingspan of 14 to 16 inches (35 to 40 cm). It moves through cover by walking and when pushed can run surprisingly fast. Its flight, like that of its cousin the California quail, is abrupt, explosive, and terminated by a long glide to the ground.

The birds come out to feed early and late. They spend the rest of the day in brushy cover to escape the heat. In cool weather, they leave their roosts earlier and may remain in the open all day.

If you approach Gambel's quail in the open, they will probably run before you can get a shot. But if you wait until they move to cover, the birds are more likely to hold. A good pointing dog will improve your odds.

In the cooler weather of hunting season, poisonous snakes are rarely a problem, but some hunters wear leather or plastic leggings.





Gambel's quail resemble California quail, but their buff-white belly is not scaled and the cap and flanks on the male are reddish brown. Males also have a black patch on the lower part of the breast. Gambel's quail weigh 5½ to 6½ ounces (156 to 184 g).

MOUNTAIN QUAIL

Few upland game birds are as difficult to hunt as mountain quail. They run at the sight of a hunter and even a good pointing dog has difficulty pinning them down. A flusher or retriever is more likely to find single birds that sit tight.

Found at elevations of 2,000 to 10,000 feet (610 to 3,048 m), mountain quail live along brushy edges of conifer forests and streams. They eat berries, clover, wild oats and seeds of weeds and grasses; the birds roost under heavy brush or in small trees. Home territories take in large areas. They head to lower elevations in late fall to avoid severe weather.

Coveys generally number only seven to nine birds. They do not form large coveys, but hunters sometimes see loose groups of birds feeding in the same area.

Listen for the call any time of day, but pay close attention in the evening, as feeding birds reassemble near water prior to roosting. Food and cover are the keys to finding quail and to the lasting memory of a full game bag at the end of the day.

Few upland game birds are as difficult to hunt as mountain quail. They will run at the sight of a hunter, and even a good pointing dog has difficulty pinning them down.

Found at elevations of 2,000 to 10,000 feet (610 to 3048 m), the mountain quail inhabits mountainous chaparral in California, Oregon, and Washington. They live along brushy edges of conifer forests and streams. Mountain quail eat berries, clover, wild oats, and seeds of weeds and grasses; the birds roost under heavy brush or in small trees. They are not migratory, but their home territories take in large areas. They seek out seasonally available foods and head to lower elevations in late fall to avoid severe weather.

Like other quail, they move about primarily by walking. When they run, they can cover ground at an amazing rate of speed. When startled, they run through cover and flush when they hit an opening. The birds scatter when they fly then regroup by calling.

Coveys generally number only seven to nine birds. They do not form large coveys, but hunters sometimes see loose groups of birds feeding in the same area.

A flusher or retriever is more likely to find single birds that sit tight.

Listen for the call any time of day, but pay close attention in the evening, as feeding birds reassemble near water prior to roosting. Food and cover are the keys to quail, and to the lasting memory of a full game bag at the end of the day.





Mountain quail have a grayish-brown back, a chestnut throat and chestnut flank with heavy white bars. The head and breast are bluish-gray. Two long, dark feathers form the plume. The sexes look alike. Mountain quail weigh 8 to 9 ounces (227 to 255 g).

SCALED QUAIL

Some hunters refer to scaled quail as blue quail; others call them cottontops or blue racers. These birds are even more likely to run than mountain quail.

Scaled quail live in semi-arid desert grasslands and in grassy brushlands. They prefer weed and brush seeds for food. The birds roost in dense clumps of brush, grass or weeds. Their water requirements are similar to those of Gambel's quail. In some states and provinces, conservation agencies have installed watering devices, helping both quail species to survive during dry periods.

Scaled quail country can be hard on the dog. Snakes are a concern, but the most important thing is to carry enough water for both hunter and dog. Lava rock and cactus play havoc with a dog's paws. Bring boots and ointment to protect Fido's feet.

If you spot a covey, rush the birds to startle them into flying. Even if you are out of range, shoot to scatter the birds and scare up stragglers. Then hunt the singles, because they are more likely to hold.

Some hunters refer to scaled quail as blue quail; others call them cottontops or blue racers. They are named for their scaly appearance on back and breast feathers. They can be identified by their cotton-like white crest.

They are bluish-gray birds that live in semi-arid desert grasslands and in grassy brushlands. The scaled quail and its subspecies are found in parts of Colorado, New Mexico, Arizona, western Oklahoma, and Texas, as well as Sonora and Chihuahua in Mexico. The chestnut-bellied scaled quail is found in southern Texas down to northwestern Mexico.

They prefer weed and brush seeds for food. The birds roost in dense clumps of brush, grass, or weeds. Their water requirements are similar to those of Gambel's quail. In some states conservation agencies have installed watering devices, helping both quail species to survive during dry periods.

Scaled quail country can be hard on dogs. Snakes are a concern, but the cooler weather of hunting season is likely to keep them dormant. The most important thing is to carry enough water for both hunter and dog. Lava rock and cactus play havoc with a dog's paws. Bring boots and ointment to protect Fido's feet.

These birds are even more likely to run than mountain quail. If you spot a covey, rush the birds to startle them into flying. Even if you are out of range, shoot to scatter the birds and scare up stragglers. Then hunt the singles, because they will be more likely to hold.





Scaled quail have breast feathers with dark margins, giving them a scaled appearance. The breast is bluish-gray; the head grayish-brown with a distinctive white-tipped crest. The crest is larger on males. Scaled quail weigh 6 to 7 ounces (170 to 184 g).

RUFFED GROUSE

Some hunters maintain that a ruffed grouse intentionally selects a flight path that places a tree directly in the line of fire. Whether intentional or not, the ruffed grouse is a difficult target for even the best wingshooters.

Grouse accelerate rapidly, reaching a speed of 40 mph (64 km/h) in seconds. But they seldom fly more than 200 yards (183 m). Grouse do not run as fast or as far as most other upland birds. When disturbed, birds of both sexes utter a call that sounds like pete-pete-pete.

Many hunters call the birds partridge, but the term is a misnomer. The only true partridge in North America are the chukar and Hungarian. The name ruffed grouse comes from the ruff, a tuft of dark feathers on the neck.

Hardwood forests with small clearings and mixed-age aspen trees make the best ruffed grouse habitat. Aspens provide good nesting cover and a year-round source of food. Grouse also favor birch trees, but also live in many other types of hardwood and conifer-hardwood forests.

Besides aspen buds, leaves and twigs, other foods include berries, fruits, clover, nuts, insects and occasionally corn. On warm, sunny days with little wind, grouse feed most of the morning and again in late afternoon. Cold, snowy or windy weather drives the birds into dense thickets or conifer stands. Grouse usually roost on the ground or in conifer trees, but when snow depth reaches 8 to 10 inches (20 to 25 cm), they often burrow into the snow.



Before the spring breeding season, male grouse begin drumming to advertise themselves to females. A bird stands on a log, braces his body with his tail, then starts beating his wings. The sound resembles that of a one-cylinder gasoline engine starting slowly, then gradually speeding up. Some drumming continues through summer and into fall.

Grouse nest in April or May, producing a brood of eight to ten chicks. By fall, the birds are full grown and the brood scatters. Young grouse usually move at least 1 mile (1.6 km) and some relocate up to 10 miles (16 km) from the hatching site. Once they establish territories, they move very little the rest of their lives.

Young birds lack the wariness of those that have been pursued by hunters. Often a young grouse will sit on the ground or on a tree limb in full view of a hunter. But the birds gain experience quickly. They learn to flush well ahead or from behind a tree or patch of dense brush where the hunter has difficulty seeing them. In remote areas, adult grouse are no more wary than young birds.

Throughout much of the northern regions, ruffed grouse populations are cyclical, peaking about every ten years. Populations in peak years may exceed those in poor years by a ratio of 15 to 1.

Ruffed grouse are some of the most available but under-hunted upland birds. With a range from northern California to Alaska and east to the Atlantic, public land birds are available to anyone with a full tank of gas and a shotgun.

Hunting for Ruffed Grouse

Every grouse hunter has been frustrated upon hearing a whirr of wings, scanning the dense cover, then spotting a bird just as it disappears from sight.

In early season, you may scare up a dozen grouse for every one you see in time for a shot. Even though the birds generally flush close by, leaves severely limit your range of vision. By the time the leaves fall, grouse have become spookier and tend to get up farther away. But they are much easier to see and seldom flush out of shooting range.



Ruffed grouse have a broad, black or dark brown band on the tail. The band is unbroken on most males, but broken on the center two feathers on females. There are two color phases, red and gray. Red-phase birds are more common in the South and at low altitudes; grays predominate in the North and at high altitudes. Grouse measure 17 to 20 inches (43 to 51 cm) long. They weigh 16 to 24 ounces (454 to 680 g), but occasionally reach 2 pounds (0.9 kg).

A good dog improves your grouse hunting success. But a dog is not essential because grouse are easier to flush than pheasants or quail. Most hunters prefer pointing breeds, but flushers and retrievers can also be effective if they work close to the handler. Because grouse are so well camouflaged, they can be difficult to find without a good dog.

When hunting without a dog, walk through likely cover and stop frequently. You can sometimes hear the birds nervously clucking before they fly. With two or more hunters, walk on opposite sides of thick patches. One hunter is likely to get a shot when a bird flushes.

If you miss or fail to get off a shot, watch where the bird lands. A flushed bird often flies off to a dense thicket or lands in a tree. You may be able to approach close enough for a second attempt.

You can improve your success by checking the crop of a freshly killed bird to find out what it was eating. Then, hunt where these foods are plentiful.

Grouse hunting is usually best on calm, sunny days. It seldom pays to hunt in early morning because the birds are still on their roosts. They begin moving after the woods have dried off.

A short-barreled, 20-gauge shotgun with an improved cylinder choke is an ideal grouse gun. The short barrel makes the gun easy to carry through heavy brush and enables you to swing quickly. Most grouse hunters prefer No. 7½ or 8 shot.

SIGNS OF GROUSE ACTIVITY

Tracks are closely spaced and about 2 inches (5 cm) long. A grouse places one foot directly in front of the other, so the tracks form a straight line.

Droppings on a drumming log mean that ruffed grouse are nearby. The brownish or greenish droppings are about ¼ inch (6 mm) in diameter.

Holes in the snow may be burrow-roosting sites. Burrows have an entrance hole and, if the bird has left, an exit hole.

Pointing dogs pin down grouse, enabling you to get close enough for an unobstructed shot. When you move in to flush the bird, avoid walking into dense cover where shooting would be difficult.

GROUSE HUNTING TECHNIQUES

Work the edges of cover. Grouse spend much of their time feeding on fruits and berries that grow along sunlit borders. If a bird flushes, your chances of getting a clear shot are better than in a thick woods.

Walk along a logging road, powerline cut or other trail through the woods. Trails make for easy walking and the edges produce food that attracts grouse. Try to avoid backtracking along the same path.

Listen for drumming ruffed grouse while hunting. Although most drumming activity takes place in the spring, some males continue to drum into the fall, revealing their locations to hunters.

TIPS FOR HUNTING RUFFED GROUSE

Plan your strategy using detailed maps of your hunting locale. State forestry departments may publish fire-control maps that show trails and logging roads.

Attach a bell to the collar of your pointing dog. This helps you keep track of its location. When the bell stops ringing, the dog is on point.

Scan the trees as you walk. Listen for a short flutter of wings that means a grouse has hopped up to a branch. Grouse in trees evidently feel safe, often allowing hunters to approach within gun range.

Other species are quicker to run or flush, but grouse hold tight while a hunter walks by. Its plumage blends so perfectly that you may never see the bird. That is until it flushes behind you.

SHARP-TAILED GROUSE

A novice hunter may mistake a sharptail for a hen pheasant, realizing the error only after the bird sails out of range. The two are about the same size and color, but a sharptail has a short, whitish tail and usually clucks when it flushes.

Sharptails prefer large ungrazed grasslands with numerous pockets of trees and brush for cover and fields of small grain for food. They favor wheat, oats and barley, but also eat berries, seeds, clover and buds. The birds feed in grain stubble or weed patches in early morning, loaf in wooded or brushy areas in midday, then feed again in late afternoon. Sharptails normally roost on the ground.

In early fall, a flock consists of six to eight birds. Later, many flocks combine to form a large pack which may have over 200 birds. When the birds flush, the flock stays together. They usually fly at least ½ mile (0.8 km) and occasionally a mile or more. But a bird or two may hold, so work the area thoroughly. Sharptails are strong runners and sometimes elude hunters by racing out the end of a field as the hunt begins.

Early-season hunters use 12- or 20-gauge shotguns with improved cylinder or modified chokes and No. 6 shot. After the birds form packs, they are harder to approach, so a full choke may work better.





Sharptails are named for the two long feathers in the center of the tail. The brownish back and wings are covered with white spots. Males have a patch of yellow skin above each eye. These patches are less visible after the breeding season. The birds weigh up to 2 pounds (0.9 kg).

WHERE TO FIND SHARPTAILS

Look for sharptails in stubble fields early or late in the day. Carry binoculars to spot the birds and listen for clucking sounds.

Hunt along brushy ravines in windy or stormy weather. A ravine, grassy ditch or the lee side of a hill makes a good windbreak.

Check brush patches to find loafing sharptails. Other good loafing spots include shelterbelts and grassy areas around abandoned farms.

SAGE GROUSE

In the 1800s, up to 1.1 million sage grouse could be found in parts of what are now sixteen states and three provinces. Today, the sage grouse is a recluse, its population numbering around 160,000, found on sagebrush ground from Oregon through Wyoming and points north.

The birds inhabit open, semi-arid country with large sagebrush flats. Buds, leaves and shoots of sagebrush make up most of their diet. They also eat alfalfa, small grains, grasses, clover and berries. The birds feed along sagebrush edges in early morning. You can find them near water holes where they eat green vegetation. They rest in gullies and draws in midday, then feed again starting in mid-afternoon.

In early fall, birds may be found in groups of six to sixty, on open flats, plateaus, ditches and ridge tops. Hunt the edges of agricultural land, where the fields meet the flats. For best success, hunt close to stock tanks and ponds. In dry times, grouse may fly in from long distances to get the moisture they crave.

To find sage grouse, glass from a ridge in early morning. Check open areas and edges of cover. If you spot birds, attempt a stalk. If not, identify water holes, sagebrush edges and ravines that you could hunt later. A pointing dog works well in early season. But when the birds start to run, a flusher or retriever is more effective.

At the flush, the birds come up in ones and twos, giving you the time to pick a target, swing with it and shoot.

Use a 12-gauge with a modified or full choke and No. 6 shot to down sage grouse. Some hunters shoot only smaller birds. The meat of older, larger birds tends to be tough and gamey.





Sage grouse have a mottled, grayish-brown back, a pale breast and flanks and a black belly. The long, pointed tail feathers fan out in flight. Males have a black patch on the chin and upper neck and a white V across the throat. Females are much smaller than males. The mature male sage grouse can weigh up to 7 pounds (3 kg) and stretch the tape to 30 inches (76 cm) from his beak to the tip of his tail.

WHERE TO FIND SAGE GROUSE

Hunt near stock tanks, ponds, irrigation ditches or creeks, especially in dry weather. These spots are best in early morning and just before dark. Sage grouse are seldom more than ½ mile (0.8 km) from water.

Rush a flock of sage grouse once you stalk within shooting range. They cannot get off the ground as quickly as other upland birds, so this tactic enables you to gain yardage for a closer shot.

CHUKAR PARTRIDGE

Chukar habitat is steep, dry, almost inaccessible and generally unsuitable for anything but wildlife. Much of the good hunting is on public land and access is generally not a problem. Chukars use rocky slopes for roosting and escape cover.

Named for its call, the chukar was imported from India in the late 1800s. Populations became established in arid portions of the Northwest. Typical chukar habitat varies from bare rocks to sparse grasslands. Because of the open country, the coveys are easy to see, but difficult to approach. They run uphill at the sight of a hunter. When they flush, they usually fly downhill.

Seeds, grasses, leaves, insects and fruit make up most of the chukar's diet. The coveys, which average ten to twenty birds, begin feeding in mid-morning. On cool days they may feed through the afternoon. They often cover over 1 mile (1.6 km) on their feeding rounds. In hot weather, chukars spend the middle of the day loafing in the shade of rocky bluffs or near springs and water holes. In windy or stormy weather, they seek depressions or crevices in the rocks.

Early in the season, when the weather is dry and hot, chukars will not be far from water. After fall's first rains, they may be more widely dispersed. Cheatgrass is one of the chukar's principal food sources, though the birds may also be found in agricultural areas close to the river and canyon habitat they prefer.

In summer and early fall, chukars can be found at altitudes up to 11,000 feet (3,353 m). A heavy snowfall will drive them to lower elevations.

A 12- or 20-gauge modified-choke shotgun makes a good chukar gun. Most hunters use No. 6 or 7½ shot.





Chukars have a grayish-brown back, a reddish bill and legs and a black collar that passes through the eye. Black and chestnut bars cover the flanks. Chukars average about 15 inches (38 cm) long and weigh 18 to 24 ounces (510 to 680 g).

HOW TO HUNT CHUKARS

Hunt with pointing dogs to help pin down the birds and prevent them from running. When your dog detects fresh scent, move into shooting position quickly because chukars may not hold to a point for long.

Follow chukar tracks after a fresh snowfall. In addition to providing good tracking conditions, snow makes the birds hold tighter and prevents them from running as fast as they do on bare ground.

HUNGARIAN PARTRIDGE

Hungarian partridge are birds of the wide open spaces and can be found in cropland, sage and bunchgrass country in Washington, Oregon, Nevada, Idaho, Montana, Wyoming and points east. Look for foothill habitat close to irrigated ag lands for the best hunting.

Huns have an understated beauty, with a form that follows function. Wings of white and mottled brown allow the bird to hide from predators by holding still. A pastel-gray on the breast blends on the head with shades of brown. Their eyes are surrounded by a pencil-thin border of red. Flanks and breasts are splotched with markings of chocolate brown.

Hunters find the birds in short, light cover. Huns feed mainly on grains like corn, oats, wheat and barley, but also eat weed seeds and green leaves.



Huns begin feeding after most of the dew dries off the grass. They feed until late morning, loaf in a grassy area until mid-afternoon, then resume feeding until dusk. The birds roost in alfalfa fields, grain stubble, short grass or even on plowed ground. They often form roosting rings like those of bobwhite quail. In winter, huns may roost in a depression in the snow or burrow-roost under it.

Coveys normally consist of ten to twelve birds. Huns do not hold well when first approached. They tend to sneak ahead of a hunter or dog, then burst from cover in unison. The covey remains together. Early in the season, huns fly only a short distance. As the season progresses, they go farther, sometimes over ½ mile (0.6 km).

Shotguns and shells used for huns are similar to those used for chukars. Some hunters prefer 12-gauge guns with full chokes in late season.

Huns are as spooky as chukar, faster than quail and smart enough to run, circle and hide. Add to all that its taste on the table and this import from Hungary is a welcome and worthy quarry for the best dogs and hunters.

Hungarian partridge are technically named gray partridge. Native to Hungary, they have a cinnamon head and chestnut bars on the flanks. Males have a chestnut horseshoe on the breast. The birds weigh about 1 pound (0.45 kg) and measure 12 to 14 inches (31 to 35.5 cm) long.

HOW TO HUNT HUNGARIAN PARTRIDGE

Watch the covey land, then approach the spot from opposite sides. This prevents the birds from slipping away and assures someone of a shot. You can often flush the same covey again.

Hunt with a close-working retriever or flusher or use a pointing dog. Flushers and retrievers work best in high cover; wide-ranging pointers find more birds in sparse grasslands or other open terrain.

WILD TURKEY

Every year, hundreds of thousands of hunters head out in pursuit of a gobbler. Winter's weariness is receding with the snowline. Forests are coming to life. Fields of wildflowers are awash with the yellows, pinks and blues. There are spotted fawns in the thickets and new growth on the trees. To many hunters turkey hunting is a celebration of spring.

The wild turkey is the largest game bird in North America. It is found throughout North America (except for Alaska). Hawaii has an abundant (introduced) turkey population. There are five recognized subspecies, which vary slightly in color and size.

First-time turkey hunters may wonder if they could tell a male from a female. There are definite differences.

The male wild turkey, called a tom or gobbler, is a large, robust bird weighing up to 30 pounds (13.5 kg) and standing as high as 4 feet (1.2 m) tall. His body color is brownish black with a metallic, iridescent sheen. The head and neck, nearly bald, vary from white to blue to red. Bright red, fleshy bumps, called carbuncles, droop from the front and sides of the neck and a fleshy flap of skin, called a dewlap, is attached to the throat and neck. A fingerlike protrusion called a snood hangs over the front of the beak. When the tom is alert, the snood constricts and projects vertically as a fleshy bump at the top rear of the beak.

On the gobbler's breast there is a beard, a series of coarse hair-like fibers. On a jake, an immature gobbler, the beard may be only 3 inches (7.6 cm) long. A mature male has a beard approaching 8 inches (20 cm) in length and longer. This is not a feature totally exclusive to gobblers though, as some females may sport a beard.

Another feature that sets toms apart from hens is spurs. Hens have no spurs. Spurs are found on a gobbler's lower legs and average between ½ and 1½ inches (2.5 and 3.8 cm) long. These spurs are small and rounded on young birds; long, pointed and usually very sharp on mature birds.



Toms begin their breeding displays in early spring. With tail fanned, feathers fluffed, and wingtips dragging, the tom struts boldly while emitting low-pitched hums.

In the spring season, big gobblers are looking for love. This makes them vulnerable to hunters who can call a tom into range by imitating the varied calls of the hen. Several styles of turkey calls are available, making it easy for a hunter to find one that suits his hunting style and abilities.

The male is called a gobbler for good reason: his rattling, deep-toned call is one of the most recognizable sounds in all of nature. At mating time, toms gobble with full-volume gusto, attempting to attract hens for breeding. Adult males display for hens by fanning their tail feathers, puffing up their body feathers and dragging their wings as they strut. Their heads and necks turn bright red during breeding season or when the tom is otherwise excited.

Adult females, or hens, are considerably smaller than toms, rarely weighing more than 10 to 12 pounds (4.5 to 5.4 kg). Their overall body color is duller than the male's and lacks his metallic, iridescent sheen. The hen's head and neck are usually blue-gray in color and sparsely covered with small, dark feathers. Carbuncles are sometimes present, but smaller than those on toms. Some hens grow small, rudimentary beards and spurs. Although they don't gobble, hens make a variety of cluck, purr, cutt and yelp sounds. Dominant hens may assert themselves with a display resembling that of the male, though they do not strut.

Juvenile birds mature quickly. By their fifth month, the juvenile male (jake) and juvenile female (jenny) closely resemble adult birds. However, juveniles have darker legs, which turn pink as the birds age. Jakes make feeble gobbles, higher in pitch than the calls of mature toms. Their beards are shorter in length and usually have amber-colored tips.

With its powerful legs, the wild turkey is an exceptional runner and has been clocked at speeds up to 12 mph (19 km/h). Although strong short-distance fliers, turkeys usually run when threatened. When necessary for escape, turkeys launch themselves with a standing leap or a running start and accelerate to 35 mph (56 km/h) in a matter of seconds. They cannot remain in the air for more than a few hundred yards (m), but can glide for ½ mile (0.8 km) or more when coasting down from a ridge top.

Subspecies

Subspecies can be difficult to distinguish from one another, since regional variations within the group can be more dramatic than physical differences between the subspecies. In addition, where the subspecies' ranges overlap, crossbreeding produces hybrid birds that show traits of both parents. A map showing the current range of all five subspecies is a good starting point in determining where subspecies live.

Turkey Calls and Decoys

Turkey calls have been an important part of the hunt ever since man discovered he could talk turkey and the birds would respond. Calls are deadly at drawing toms to hunters.

Calling is considered by most devoted turkey hunters to be the only sporting way to take a gobbler. Calling is the fun part of turkey hunting. Mastering a variety of different calls—learning when to yelp, cluck, purr or cutt, knowing when to call softly and when to crank up the volume—this is the art of spring turkey hunting.

Under the right circumstances, turkeys can be ridiculously easy to call. But don't count on it. When hens are abundant or hunting pressure is heavy, only a



Turkey calls can be divided into two basic categories: Friction calls include the (1) push-pull call, the (2) box call and the (3) slate-and-peg call. Air-activated calls include the (4) tube call and the (5) diaphragm call.

PROPER DIAPHRAGM CALL PLACEMENT



Proper placement of a diaphragm call in your mouth is crucial to success. (1) Use your tongue to position the call against the roof of your mouth with the straight edge facing forward. (2) Position the call so the forward edge nearly touches the back of your top front teeth. (3) Place the top of your tongue lightly against the latex reed and (4) expel short bursts of air between the top of your tongue and the reed, while saying the word "chirp." Stay at it and you will soon be able to produce acceptable yelps, the first call you should learn. Once you have mastered the yelp, begin practicing other calls.

CALLING TIPS



Insert a piece of cloth or fleece under the paddle, then wrap a rubber band around paddle and box. This keeps the call from squeaking as you walk.



Dependable locator calls include: (1) owl hooter, (2) coyote howler with large bellows, (3) flute-style goose call, (4) silent whistle with adjustable frequency, (5) crow call, (6) pileated woodpecker call, (7) hawk screamer and (8) predator call.

Trim the skirt of a diaphragm call with small scissors to make it fit comfortably against the roof of your mouth.

TYPES OF DECOYS



Hen decoy styles include: (1) collapsible foam; (2) folding shell; (3) silhouette; (4) full body; (5) hen with safety orange head, which is both safe and often aggravates toms; and (6) motion decoy, which allows the hunter to move the head of the decoy by pulling on a long string.



Jake decoy styles include: collapsible foam in (1) full strut; (2) half-strut; and (3) erect position; and (4) folding shell in erect position.

hunter who has mastered the art of calling walks out of the woods with a gobbler slung over a shoulder.

Calls designed to lure gobblers to the hunter can be divided into two broad categories: friction calls and air-activated calls. Although each has its advantages and disadvantages, the friction calls are generally easier to operate.

A third category of calls, locator calls, are used to elicit a response from a turkey without attracting the bird to your position. This response is most commonly referred to as a shock gobble. Turkeys have been known to shock gobble to the sound of a squeaking fence, slamming car door or a bellowing Holstein and a host of other sudden, loud sounds. Most locator calls imitate animals such as crows, owls and coyotes, but loud cutting on a turkey call can also prompt a shock gobble.

There are dozens of commercial calls on the market and while there is no need to buy and use all of them, a hunter is wise to use a variety of calls. Wild turkeys can be fickle, preferring a box call one morning, a diaphragm the next. A well-prepared hunter is ready to switch calls on those mornings when his old standbys just aren't making the grade.

However, as important as calling is, woodsmanship is equally important. In fact, an accomplished woodsman—a hunter intimately familiar with the land and the turkeys that live on it—can take gobblers with amazing consistency without ever touching a call.

A well-positioned turkey decoy is often the final touch needed to lure a shy tom into shooting range. Especially in open country, toms responding to a hen call may grow suspicious if they can't spot the source of the call. But if they see a decoy, the reassured gobblers often commit and waltz into range. A decoy can work wonders on hard-hunted birds, which tend to be leery of even the best calling.

Understanding Daily Patterns

At first light, as turkeys begin to awaken in their roosting trees, toms begin to gobble, while hens utter soft tree yelps. Usually the birds fly to the ground as soon as there is enough light for them to spot predators, but this fly-down can be as late as two hours after sunrise if the morning is rainy or foggy. Turkeys roosting in small woodlots in relatively open areas tend to fly down sooner than birds roosting in deep timber, where daylight is longer in arriving.

When a turkey gobbles on the roost in early morning, he is trying to draw a hen to him. If successful, the tom will fly down to join the hen. If a hen doesn't appear, the tom flies down and walks to his strutting area, while continuing to gobble.

To effectively hunt wild turkeys in spring, a hunter must understand the bird's daily movement patterns. Bagging a wild turkey is largely a matter of being in the right place at the right time.

Strutting zones are located in open areas where toms can be easily seen by hens, such as a field edge, logging road or pasture. In hill country, strutting areas are often located on elevated ridges, points or hilltops. In flat country, gobblers often strut in semi-open hardwood bottoms.

When the tom arrives at the strutting zone, he continues to gobble until he attracts a hen. Once a hen arrives, however, the gobbler begins to strut and his gobbling becomes infrequent. The tom may attract several hens simultaneously.

A gobbler follows hens as they wander to feed, mating with each several times during the morning, if they permit. Identifying feeding areas can be difficult, since wild turkeys eat such a wide variety of food. In big timber, turkeys often wander along, foraging on whatever they find. In agricultural areas, turkeys feed in crop fields a good deal of the time.

Only in the arid regions of the West and Southwest do turkeys habitually seek water during their daily route. In most regions they obtain sufficient water from dew or in the plants they consume.

By mid- to late morning, after satisfying their hunger, turkeys often treat themselves to a dust bath. Bred hens may then retire to the nest to lay or incubate. Gobblers may rest at this time or resume gobbling and continue to search for new hens.

Mid-afternoon finds turkeys on the move and feeding once again. During the last hour of day, the flock feeds toward roosting sites. They usually fly up at sunset or shortly thereafter. Birds often change limbs or even roosting trees a number of times before settling in for the night.

Turkey Hunting

One wrong move and the turkey will duck his head and run. Don't move a muscle, not yet. Let him close to 30 yards (27 m). He stops to strut, fanning out his tail feathers and puffing out his chest as if to say, "Look at me, ladies. Ain't I the pretty one, though?"

Ideally, you'll want to "roost" a gobbler on the eve of the hunt, which means you actually see or hear the bird in his roost tree. Return before first light, slip within 100 yards (91 m) of this roost, sound a couple of tree yelps at dawn and odds are good the gobbler will fly down practically in your lap.

To "put a bird to bed," set up near a roosting site in early evening. Turkeys feed toward a roost tree in late evening, usually fly into them around sunset and settle in before dark.

If you cannot spot birds, listen for them. Occasionally, toms gobble a time or two after roosting and hens sometimes yelp. More often, you'll have to make them gobble by using a locator call. Walk through likely habitat, pausing every ¼ mile (0.4 km) or so to call. If a gobbler responds, move toward him, eliciting additional shock gobbles until you've pinpointed his location. Mark the site and the trail to it with strips of toilet paper or surveyor's tape so you can find your way back before dawn.

As day breaks, give a few quiet tree yelps. Chances are good that the gobbler will reply, but if he doesn't, resist the temptation to call louder or more often. Overcalling while a tom is still on the roost is a common mistake.

If you failed to put a gobbler to bed the night before, plan to be at a good listening position well before first light. Hilltops and ridges are best. On most mornings, toms begin gobbling spontaneously, but if you hear no gobbling by the time there is enough light for you to see individual limbs on trees, then try to elicit a gobble with an owl or crow call. When you hear a gobbler within reasonable distance, try to get within 100 yards (91 m) before setting up to call him.

Turkeys usually fly from the roost as soon as there is enough light for them to see predators on the ground. However, on rainy, foggy or unseasonably cold mornings, they may stay on the roost for an hour or more after sunrise.

They use the same strutting grounds day after day. These are usually in relatively open areas, such as open timber, field edges, pastures or logging roads, where toms can watch for approaching hens and hens can clearly see their strutting displays. Once you find these sites, you can hunt them productively for years, because turkeys return to the same strutting zones season after season.

Hunters often make the mistake of yelping loudly and frequently. Call just enough to let a gobbler know you are there. Every few minutes, scratch the ground to mimic the sound of a foraging turkey. This assures the gobbler that a hen is still nearby, but since she ignores his calling, he sometimes goes against his own instinct and sashays toward her.

The prime early morning strutting/gobbling period may last a few minutes to an hour. Occasionally, a tom returns to his strutting zone in late morning after his original partners abandon him.

Two strategies can produce results after the prime early morning period: run-and-gun or sit-and-wait.

To use the run-and-gun approach, walk quickly through the area, stopping frequently to blow a locator call. Search for a bird that responds to every call you make. When you find such a bird, get within 200 yards (183 m) in open country, half that distance in timber; sit down and get ready before you make a single hen call. Call just often enough to keep the bird gobbling, so you know where he is. If the bird continues to gobble in response to your calls, but moves steadily away, determine his direction and attempt to get ahead of him. If he moves steadily in your direction, call sparingly and stay ready.

The sit-and-wait tactic is most successful if you know the area well enough to predict travel routes. Picking a good feeding spot and waiting patiently for a flock of hungry birds to arrive is also a good tactic before 10:00 a.m. A blind can be a real asset when playing this waiting game, as can a decoy or two. Patience is the key. Turkeys feed at midmorning and a feeding flock is in no hurry, covering only about 200 yards (183 m) per hour, on average.

Cover lots of territory after 10 a.m. Use locator calls and loud cutting to elicit gobbles. Locator calls are better than hen calls for prompting a tom to begin gobbling. Once you've elicited a shock gobble, set up and get ready to seduce the bird with your most authentic hen calls. If you begin by making hen yelps, a tom may arrive before you are prepared to deliver the proper greeting.

The first step in a successful hunt is to find good turkey habitat. Assuming you have scouted adequately, you should know several spots that hold birds.

If you prefer to sit and wait for your bird, late morning is a good time to stake out strutting zones. Gobblers that have been deserted by hens frequently meander back to their strutting zones and readily respond to calls.

Gobblers can still be taken in the afternoon, though it takes patience and a slightly different strategy. Find a turkey hangout—a dusting area or feeding site—set out a decoy or two, relax against a big tree and give a few yelps every 15 minutes or so. If a gobbler comes to your call at this hour, he usually won't announce himself until within shooting range. Many hunters have been jarred from midday naps by tiptoeing gobblers shouting at close range.

Action picks up again in late afternoon, when turkeys begin actively feeding and, later, working toward the roost. If you have located a roosting area, determine the most likely direction from which the birds will approach and set up in their path. If you haven't pinpointed a roosting area, spend the last hour of daylight covering ground and using a locator call. If you hear a gobbler, slip in close and work the bird with hen calls. Even if you don't get a shot, you'll know where to continue the hunt in the morning.

HUNTING STRATEGIES



For typical early morning scenarios, set up in the nearest opening to the roost tree and put out a decoy. If the gobbler is alone, he will go to the field to gobble and strut. If he is with hens, he tags along as they go to feed in the field. The logging road is the obvious approach route.



If you want to set up a typical run-and-gun scenario, follow the easiest route to cover the most ground in the least amount of time when running and gunning. Skirt the edges of all openings and call every 100 to 200 yards (91 to 183 m), until you get a response.



In a tag-team setup, position the shooter (1), 30 to 100 yards (27 to 91 m) in front of the caller (2). If a gobbler hangs up short of the caller, the bird will be within range of the shooter.



For a typical sit-and-wait scenario, sit and wait for birds where you can cover locations where birds enter or exit fields (1), pastures (2) or other openings. Be patient, call sparingly and stay alert.

MOURNING DOVE

It's hard to deny the thrill of seeing dozens of doves sweeping toward you and beyond, the sound of the wind in their wings. There's no more difficult wingshooting challenge than that you find on a dove hunt. These birds are hard to hit. You need an edge if you hope to bag enough for dinner.

North American hunters harvest about 50 million doves annually, more than all other migratory game birds combined. The continent's dove population is estimated at 500 million, making it the most common game bird.

Mourning doves don't like cold weather. In northern states, the birds begin flying south after the first frost. Prior to migration, they form flocks consisting of several hundred birds.

Doves prefer open fields with scattered trees and woodlots. The birds need water each day, so there must be a pond, stock tank, flooded gravel pit or river nearby. Doves nest in grass, shrubs, stubble fields or trees, especially evergreens.

Nesting begins in early spring and continues through early fall. Doves raise up to four broods, with both parents caring for the young. After predation and weather-related losses, broods average about one bird each. This trait of raising multiple broods is unique among game birds. It ensures a relatively stable population from year to year, with or without a hunting season.

Weed seeds form the bulk of the dove's diet. They favor foxtail, dove weed, ragweed and wild hemp. Other foods include corn, soybeans, sunflowers, oats and wheat.

Doves fly to their feeding areas at dawn, feed until mid-morning, then head for water. Through midday, they rest in dead or dying trees near a feeding area, a water hole or a small pond. Doves resume feeding in late afternoon, then return to a watering site late in the day.

At dusk, they fly to their roosts, often to the same trees they used during the day. If not disturbed, doves continue to use the same roosting and watering areas.

Mourning doves can fly up to 55 mph (88.5 km/h). Their normal flight is smooth, effortless and direct. But they flare quickly at the sight of hunters, darting and weaving erratically as they fly away.





Mourning doves have a slate-blue back, a fawn-colored breast with a pinkish cast and a black spot behind the ear. They measure 11 to 13 inches (28 to 33 cm) from head to tail and weigh about 3½ to 5 ounces (99 to 142 g).

Roosting trees are usually within 2 miles (3.2 km) of water. A favorite roosting spot is a sand bar in a river where the birds find dead trees close to water.

Hunting for Doves

Most dove hunters find a stand along a flight path. It may be a route between a roosting and feeding site or between a feeding and watering area. Conceal yourself in a brush patch or near a fence line or tree, then pass-shoot as the birds fly through.

Doves often fly near a dead tree, telephone pole or any object taller than the surrounding cover. They frequently fly through a gap in a tree line to reach a feeding area or water hole. Often they skirt the end of a point of cover extending into a feeding field. If stands within gun range of these spots do not produce, watch where the birds are flying and change your location accordingly.

By stationing several hunters around the edge, you can keep the birds moving and improve shooting for everyone.

Ideal habitat includes an old dead tree and muddy water with a bank free of brush. Scout for set-ups where a fencepost or a dead tree will break up your outline.

The best way to put birds in the game bag is to improve your shooting. Train to focus on one part of one bird. Key on a dove's beak for a passing shot or the tail feathers as it goes straight away. The tighter the focus, the better your chances are of bringing birds home for dinner.

That's difficult to remember in the heat of the action, but it is easily practiced on any bird you see. In time it becomes automatic.

There are more techniques to help the bird hunter fill the game bag. The first is timing. Take it slow. With an unloaded gun, practice disengaging the safety and shouldering it. The cheekpiece should come against your cheek, with the butt anchored against your shoulder. The barrel should be in the same plane as your master eye, front bead on (or ahead of) the target.

Picture the shot leaving the barrel in a string, similar to water in a hose. Imagine swinging a spray nozzle across the sky. When you swing your barrel, following through as you squeeze the trigger, your shot will "wash" the target in the same way.

A stool can improve your shooting. Lunging from a crouched position to shoot is awkward. Rising easily from a chair promotes good stance and shooting position.

Another essential is the earplug. There may be more shooting on one dove hunt than in all the rest of your season's bird hunts combined. Earplugs keep you from flinching, but more important, they protect the auditory organs. You want to keep your hearing sharp so, on opening day of dove season twenty years from now, you can still hear the whistle of the wind in their wings.

Camouflage clothing is ideal, but any drab outerwear will do. Many hunters use semi-automatic or pump shotguns. A variable or screw-in choke enables you to vary the shot pattern, depending on the range of the birds. An improved cylinder or modified choke with No. 7½ or 8 shot usually works best.

WHERE TO FIND DOVES

Water holes used by doves often have muddy water and bare ground along the edge. The best water holes have trees with dead branches nearby.

Idle fields attract doves because they provide an ample supply of weed seeds. Doves prefer to pick seeds from bare ground. They seldom feed in dense vegetation.

Gravel roads provide grit. Doves pick up sand and small gravel along roads in early morning and late afternoon. They also find grit along streams and in fields.

WOODCOCK

Woodcock have a chunky body with a mottled brownish back and sides and black bars on top of the head. They measure 10 to 12 inches (24.5 to 31 cm), weigh 6 to 8 ounces (170 to 227 g) and have a bill about 2½ inches (5 cm) long.

Eyes on the side of the head give the birds excellent lateral vision Some researchers believe that woodcock rely on an acute sense of hearing to find worms in the ground. The birds can fly as fast as 30 mph (48 km/h). When flushed, they usually land within 100 yards (91 m).

Most woodcock breed in the northern states and Canada. They start their southerly migration in early to mid-October, leaving en masse once the ground freezes or after a heavy snow. Woodcock stop off in the same resting areas each year.

Young forests with trees 10 to 20 feet (3 to 6 m) tall make the best woodcock habitat. The soil should be damp with little grassy cover. Heavy ground cover makes it difficult for the birds to find earthworms, their favorite food.

Woodcock feed mainly around dawn and dusk. Besides earthworms, the birds eat insect larvae, seeds, berries and green leaves. During the day, they rest on the ground, feeding only occasionally. In cool weather, look for them on sunny hillsides or other sunlit areas. On a hot day, they sit in the shade, often below evergreens.

The best woodcock hunting is during the migration period. Northern hunters may get some shooting at resident birds, but when the migration peaks, they may flush up to thirty birds per hour.

Hunters who use dogs flush a least twice as many birds as those who do not. Because woodcock blend so well with the leaves, downed birds can be difficult to find without a dog.

A short-barreled 20-gauge with an improved cylinder choke is an excellent gun for woodcock. Most hunters use No. 7½ or 8 shot, but some prefer No. 9.



Many hunters who own pointing dogs consider woodcock or timberdoodle, the ideal quarry. Even with a dog holding a close point, a bird will hold tight, confident in its near-perfect camouflage.

Chapter 7

HUNTING WATERFOWL

Waterfowl are ideally suited for a life spent in and around water. Webbed feet give them extraordinary swimming ability and their long necks and broad, flattened bills allow them to feed on aquatic plant and animal life. Waterproof plumage and thick layers of insulating down keep these birds from losing body heat in cold water.

Geese are distinguished by their large size, with some approaching 15 pounds (6.75 kg). During the migration, geese may form enormous flocks numbering in the tens of thousands. Geese exhibit no coloration differences between the sexes. They rarely breed before their second year and may live for twenty-five years. Geese mate for life and maintain stronger family bonds than do ducks, with both parents caring for the young.

Ducks differ from geese in that sexes usually vary in coloration. Males have distinctive, colorful plumage, while females are camouflaged with mottled, drab browns. Pair bonds are temporary, with the drake deserting the female shortly after breeding. Most ducks are short lived, but a few have been known to live fifteen years.

Puddle ducks include some of the most widely hunted species. Puddle ducks are adept at walking and feeding on land. They can take flight almost instantly by jumping straight into the air.

Diving ducks have legs and feet positioned far back on their bodies. Rather awkward on land, they spend most of their time in the water.

Identification for species and sexes requires a great deal of practice, especially with ducks. But you can recognize the major types of waterfowl by their body size and wingbeat. Geese are larger than ducks and their wingbeat is slower. Puddle ducks have a faster wingbeat, but not as fast as diving ducks.

WATERFOWL EQUIPMENT

Waterfowling requires more equipment than most other types of hunting. In many cases, you will need decoys, camouflage clothing, waders, binoculars, calls and a duck boat.

Regulations require hunters to use nontoxic shot. Most hunters prefer a 12-gauge with a modified choke for shooting ducks and geese, increasing the size of shot when hunting larger waterfowl such as geese.



Waterfowl hunters must think total concealment when setting up a decoy spread. Camouflage the hunter and the boat, and then utilize the proper call to "sell" the spread to incoming birds.

BASIC DUCK AND GOOSE CALLS

Duck Calls. *There are two basic types of mallard calls: standard, or Reelfoot, style and Arkansas style. Reelfoot calls have a metal reed that is curved upward at the tip. Arkansas calls have a straight plastic reed. Reelfoot calls are generally harder to blow and have a narrower range of tones, but are much louder. Consult an experienced local duck hunter to determine what kind of call works best in your area. The sound of a particular call may be more effective in one region than in another.*

Calls for other species include those for wood ducks, diver ducks and pintail-widgeon-teal whistle calls.

Goose Calls. *The basic types of goose calls include the standard call and the flute call. Standard goose calls are easy to blow. They create two tones, one low and one high pitch tone, that imitate the basic sound made by Canada geese. Low grunting feeder sounds can also be imitated using standard calls. Flute goose calls are more difficult to master, but can imitate the many different communication sounds of Canada geese. Callers use both hands to operate flute calls; one to hold the call while the other is cupped over the end of the call to regulate air flow.*

Calls for other species include those for white-fronted geese and snow geese.

EQUIPMENT FOR DECOY HUNTING

Full-body floating decoys may be made of wood, cork, foam or molded plastic. A weighted or water-filled keel makes them float upright and a string and anchor keep them from drifting away. They come in standard and magnum sizes.



Field decoys: Shell decoys (bottom) are the most common among hunters because they are three-dimensional and can still be stacked for easy storage. Full-body decoys (top) add realism to your spread, but are probably the most bulky of all the styles. Silhouette decoys (middle) are very lightweight and easy to stack. Manufacturers now cut them in a wide variety of feeding, standing and resting positions, adding to the believability of the spread.



Decoy accessories include: (1) longline clip, for attaching decoy cords to longlines; (2) snap-swivels, which attach to decoy weights to prevent cord twist; decoy weights, such as (3) mushroom anchor, (4) pyramid anchor, (5) ring anchors, (6) strap anchor and (7) scoop anchor, which slips over the decoy's bill; (8) tangle-free decoy cord; (9) braided-nylon decoy cord; (10) decoy touch-up paint; and (11) grapple anchor for longlines.

Flagging devices attract the attention of waterfowl at a distance. Use a black or white flag for geese; a gray or black flag for ducks.

PUDDLE DUCKS

As their name suggests, these ducks commonly frequent small, shallow bodies of water, but they may also be found on big water. Also called dabblers, they feed on or just below the surface, mainly on aquatic vegetation. They may skim food off the water or they may tip up, submerging their upper body to feed while leaving their feet and rump pointing up. In fall, some puddle ducks also feed in grain fields. Their predominantly vegetable diet explains why they are considered better eating than most other ducks. Large wings give puddle ducks good maneuverability. They often circle a potential landing site several times, inspecting it closely before setting down. There are a total of twelve huntable puddle duck species in North America.

Puddle ducks are able to lift from the water almost instantly. They may be hunted by jump-shooting, pass-shooting, or by using decoys to draw them in.

HOW TO RECOGNIZE PUDDLE DUCKS



Tipping up or dabbling, is the usual puddle duck feeding method.



Colored wing patches are present on most puddlers. Most have a patch, called a speculum, on the wing's trailing edge. The speculum (arrow) is usually iridescent.



Legs positioned near the center of the body give a puddler good balance, so it can easily walk and feed on land.

Many waterfowl hunters prefer to use decoy spreads. Camouflage is important. Build a temporary blind from natural materials or bring in a portable blind. Permanent blinds can be built on private leases.

Puddle-duck Hunting

The widespread distribution of puddle ducks, combined with their excellent table quality, accounts for their tremendous popularity among waterfowl hunters.

As a rule, puddle ducks prefer smaller water than diving ducks; even the shallowest slough or tiniest creek may offer top-rate hunting. But puddlers are also found on some of the continent's largest waters, including the Great Lakes and Utah's Great Salt Lake. While divers are comfortable riding out big waves in open water, puddlers are usually found in calm water. In windy weather, they seek shelter along a lee shore.

You don't need a lot of expensive equipment to hunt puddle ducks. Jump-shooting and pass-shooting require nothing more than a shotgun and a few shells and you can decoy the birds into a small body of water with only a half-dozen blocks. Hunting on big water, however, is much more involved and requires considerably more equipment, including a good-sized boat and a minimum of several dozen decoys.

Mallards are the most numerous of the puddle ducks and most other puddler species feel comfortable in their company. Teal, for instance, are commonly seen flying with mallards and wood ducks often loaf in the same area as mallards. As a result, you can use mallard decoys and calls to attract most any kind of puddle duck.

In setting decoys for puddle ducks, remember that puddlers rest in looser groups than divers, so your decoys can be spread out much more. Some hunters leave as much as 10 feet (3 m) between individual blocks. Diving-duck hunters seldom leave more than 6 feet (1.8 m).

Calling is of utmost importance in puddle-duck hunting. The birds, by nature, are quite vocal and they look for reassurance from ducks on the water before making the decision to land. If you are not a competent caller, however, it's better not to call; you'll scare away more birds than you'll attract.

Puddlers are generally considered to be smarter than divers, but this "intelligence" may, in part, be a reflection of their migration and feeding habits. Because they migrate earlier than divers, they're exposed to a longer period of hunting pressure, so they're more likely to recognize the difference between decoys and the real thing.

PUDDLE-DUCK HUNTING TIPS



Float a small stream or river using a poke boat or a canoe. Hug the inside turns as long as possible. Ducks usually rest below the points and they won't see you coming until the last minute.



Use several goose decoys when hunting puddle ducks in the field. Ducks often feed with geese and the larger decoys add to the visibility of your spread.



Kick water with your boot when hunting flooded timber. The ripples indicate to circling ducks that others are dabbling in the water.



Pass-shoot from a strip of land between two lakes or between a lake and a grain field. Ducks choose the route that crosses the least land.



With the wind at hunters' backs, decoys should be set in two pods with a good-sized landing pocket between the pods. The outermost decoys should be no more than 30 yards (27 m) from the blind. The blind is positioned so the hunters are facing the pocket. Without a pocket, ducks may land beyond the decoys, out of shooting range.



With the wind from the left, arrange the decoys in a "C" formation to the left of the blind, as shown. Ducks do not like flying over decoys to land; this way, they do not have to. When the wind is from the right, reverse the entire decoy setup.

DIVING DUCKS

With legs positioned farther back on the body, these ducks are more adept at diving beneath the surface than are puddle ducks. Their feet are larger for their size, so they are better underwater swimmers. The leg position also makes it more difficult for them to walk on land, explaining why they seldom feed in agricultural fields. The diet of most divers consists mainly of invertebrates and fish, explaining their strong taste. But some, such as canvasbacks and redheads, feed heavily on wild celery and other aquatic vegetation and are considered better eating. There are nineteen huntable diving duck species in North America.

Sea ducks, a subcategory of diving duck, differ from ordinary divers in that they spend most of their life in coastal areas. They have remarkable diving ability, with some species descending to depths of more than 200 feet (61 m) to feed on mollusks, crustaceans and fish.

Mergansers, often called fish ducks, are also classified as a subcategory of diving duck. They feed even more heavily on fish than other divers and their serrated bill is ideal for catching and holding small fish until they can be swallowed whole. Their crested head easily distinguishes them from other diving ducks.

Diving ducks plunge well beneath the surface to feed.

HOW TO RECOGNIZE DIVING DUCKS



Large feet and legs positioned far back on the body account for the diving ability of these ducks. White to dark gray wing patches are found on most diving duck species.



Flying low over the water in tight flocks is typical behavior among most diver species. In flight, divers can be distinguished from puddlers by their shorter, faster wingbeat. Running on the water helps divers gain enough speed for take-off. Their small wings provide less lift than those of puddlers.



The pursuit of diving ducks takes hunters to broad rivers, estuaries, and in and around large saltwater bays. Strong fliers, they are one of waterfowling's greatest challenges.

Diving-duck Hunting

If you're looking for a wingshooting challenge, diving ducks are the perfect quarry. When a flock of divers streaks along a decoy line, it's not uncommon for a hunter to shoot at the lead bird and drop the third or fourth one back.

Due to the divers' preference for big water, hunters need more and different equipment than they ordinarily do for puddle-duck hunting. Instead of a 12- or 14-foot (3.7 to 4.3 m), shallow-draft duck boat, for instance, you'll need a 16- or 18-foot (5 to 5.5 m), deep-hulled semi-V to negotiate water that can turn rough in a hurry. You'll also need more decoys than you would for puddle-duck hunting and, possibly, a floating blind.

The divers' habit of forming large open-water rafts, particularly in late season, adds to the hunting challenge. Some hunters use low-profile sneak or sculling boats to approach birds in open water without alarming them.

Because divers migrate much later in the season than puddle ducks, you'll be hunting in considerably colder weather. Warm, waterproof clothing, including insulated boots and gloves, is a requirement.

Crippled divers often attempt to escape by swimming away underwater or with their head at water level. You'll need a determined, hardy retriever, preferably a Labrador or Chesapeake, that is capable of making long retrieves in cold, choppy water.

In puddle-duck hunting, the idea is to lure birds into the decoys and take them when they're "putting on the brakes," meaning that their wings are cupped and they are about to land. In diver hunting, the birds are less likely to slow down, so you'll probably have to take them as they're winging along a line of decoys that leads to your blind.

Instead of shooting at birds that are barely moving, you're attempting to hit birds barreling along at speeds up to 75 mph (120 km/h). To be successful, you must learn the swing-through shooting technique and do a lot of practicing to determine the proper lead.

Calling is seldom necessary in diver hunting. The birds spot the decoys from a distance and their curiosity draws them in without any vocal enticement. Nevertheless, many hunters try calling anyway, using a diver call or rolling their tongue against a mallard call to mimic the characteristic diver "purr."

Divers differ from puddlers in that they do not hesitate to land in rough water. As a result, there is no need to set your decoys off a lee shore. It's more important to set them where the birds are feeding, regardless of wind direction.

Yet another difference: divers do most all of their feeding on the water, so the field-hunting techniques that work so well for puddle ducks are not effective for divers. Practically all diver hunting is done on the water or on passes between two bodies of water.

Diver hunting is not for everyone. Not only does it require a high tolerance for inclement weather, it can be a lot of work. But if you're a hardy soul who loves the whistle of wings, there's no more exciting shooting.



The J-hook. This setup works well off a point or in open water. The long tail extends well beyond shooting range. The largest clump of decoys is placed at the hook of the J, which forms a landing zone.



The V-formation. This setup is similar to the J-hook, but it has two tails extending out into the water, rather than one, giving the birds an additional option for approaching the blind.

DIVING-DUCK HUNTING TIPS

Use silhouette sleds, which can be neatly stacked so they take up less space than ordinary decoys. Attach the sleds to longlines; each should be rigged with about twelve sleds. Tie a full-body floating decoy to each end of the line to help keep the silhouettes afloat in rough water.

Make inexpensive diver decoys by painting black patches on white bleach jugs.

Low-profile boats allow you to get close enough for a good shot on diving ducks that have rafted up on the water.

Wave a black flag when you spot distant ducks. The motion resembles other ducks flying or landing. Stop flagging once the ducks start to head your way.

Look for openings in the trees or long points that extend out into the main body of water to pass-shoot divers.

GEESE

Geese often fly in a very distinct V-formation with a much slower wingbeat than ducks. Large, powerful wings enable geese to take flight very quickly, even though some Canada geese reach a weight of 15 pounds (6.75 kg). Once in flight, geese are easily recognized by their slower wingbeat when compared to the fast wingbeat of ducks.

Flocks consist of one or two family units, each numbering between four and six birds. As the migration progresses, many flocks join to form large concentrations, which may number in the thousands.

An exceptional homing instinct draws geese to the same waters every year. And they often return to the same feeding areas on consecutive days. If the food supply holds up, they come back to the exact spot in the field.

The fall diet of geese consists of waste grain, green plants such as clover, grasses and new shoots of barley, wheat and oats. Geese feed in open fields where they can see in all directions.

About three out of four bagged geese are juveniles, but some live twenty-five years. To survive that long, they must learn to be extremely cautious. Old birds scrutinize a landing site and veer off immediately if anything looks suspicious.

Dry land goose hunting is one of waterfowling's greatest thrills. The birds are big, with a wingspan of up to 71 inches (180 cm). The birds breed in Canada and the northern United States, then travel south in the fall in long Vs. They can be enticed with large decoy sets and calling.



Canada geese have a black head with a white chin bar. The back is grayish or brownish and the belly is whitish. Biologists recognize more than 12 varieties of Canada geese, the largest being the giant Canada; the smallest, the cackling goose.



White-fronted geese, also called speckle bellies, have a brownish head, neck and back. The undersides are whitish with dark brown speckles. A distinctive white facial patch rings the base of the pinkish bill.



Snow geese are pure white with black wing tips. Two subspecies are recognized: the greater snow goose and the lesser snow goose. Lesser snow geese may sport either dark or white plumage.



Ross geese resemble the lesser snow goose, but are smaller and have a stubbier bill. Ross geese often travel with snow geese and can easily be identified in flight by their faster wingbeat.



Brant geese, both Atlantic (bottom) and Pacific (top), can be recognized in flight by their rapid wingbeat. The head, neck and chest are black and the sides of the neck are marked with white streaks. The Pacific brant has a darker underside and more pronounced neck marks.

Hunting Geese

Those minutes before first light, the barley bending with the wind, the cool of the morning and the whispered anticipation of honking geese against a paling sky—this is what brings goose hunters to the field each year. That and the thrill of seeing the birds over the barrel of a gun, ten feet off the ground, their wings cupped to land.

Scouting, prior to the hunt, is essential. Note what time birds are seen in which fields and be there with your decoys the next day. Large flocks of strategically-placed plastic impostors, with good calling, will bring geese into shotgun range.

Hunting with decoys can be done both in feeding fields and on the water. When hunting in a field, you often need a large number of decoys to entice the birds.

When hunting for Canada or white-fronted geese in the early season, set your decoys in small clusters to imitate a small family group. Fewer decoys are often required early in the season because the geese haven't grouped up for the fall migration.

When hunting snow or Ross geese, some hunters use well over a thousand decoys in order to successfully decoy the most cautious waterfowl of North America. Combining large shell decoys and silhouette decoys, hunters mix in Texas Rag style decoys, white garbage bags and wind sock style decoys to increase the mass and visibility of the spread. Hunters rarely hunt snows on the water with decoys.

Brants can also be hunted with decoys, most commonly on the water. Setting two separate groups of decoys and leaving a place for the geese to land in the middle is the most common setup.

Most pass-shooting takes place in areas surrounding goose refuges or other waters with large concentrations of birds. Flight paths to and from a lake vary, depending on wind direction and the location of the feeding field being used. To select a good pass-shooting spot, spend a few hours watching the birds, taking note of the direction of the wind.

Hunters usually stalk geese after following or spotting a flock during their feeding period, which usually occurs twice daily, once in midmorning and again toward late afternoon.

Be prepared to use any available cover to sneak on a flock of geese. Sometimes they land in a field that is impossible to sneak. Better to find another flock where you are more likely to make a successful stalk.

When geese land in an open field, try team hunting. One hunter hides along an edge of the field, while another approaches from the opposite side. When the birds fly, they may pass over the hiding hunter.

Hunters accustomed to shooting ducks often have trouble hitting geese. Because the birds are so large, the tendency is to underestimate their distance and speed. Goose hunters use 12- or 10-gauge shotguns with modified or full chokes. Shot sizes range from No. 3 to T shot.



Family spread. Set Canada or white-fronted goose decoys in small family groups when hunting early in the season. Groups consist of four to ten decoys spaced about 5 to 10 yards (0.9 to 9 m) from each group. Set your blind(s) on the downwind side, shooting geese as they approach your spread.



Combination field. Place snow goose decoys on the downwind side of the spread. On the upwind side, set your Canada decoys, leaving a large opening. Hide among the snow goose decoys or in a pit blind near the downwind side of the spread and shoot as the geese approach the landing zone from the downwind side.



Water spread. Place your decoys in the most protected area of the bay, leaving an opening about 15 yards (13 m) wide for the birds to land in the middle of the spread. The opening should be directly in front of the blind. The outermost decoys should be no more than 35 yards (32 m) from the blind, giving you a distance guide to approaching geese. Depending on the size of the water you're hunting, you'll need from one to six dozen decoys to hunt geese on the water.

HOW TO USE A SHORT REED CALL

The Short Reed Goose Call provides the most versatile range of tone and pitch of any call on the market. Today, many variations are available, made from ABS, polycarbonate and acrylic. Calls made from ABS range are the least expensive. Polycarbonate calls are more expensive. Acrylics may be the most expensive, but they have the crispest tones.

The grip is critical. To create back pressure, put your index finger at the base of your thumb to form an O at the very end of the call. Then close your pinky finger and your ring finger against your palm as if in a fist. You use your middle finger to regulate the air pressure and flow to create all the sounds.

Play the call like you would play an instrument. Don't blow with your mouth. Air pressure should originate in your diaphragm.

Use your middle finger to change tones and your off-hand to direct the sound up and down and left and right. Begin to muffle the call as the birds get closer. The subtle sound keeps them coming.

Most goose hunters use a blend of several types of decoys. Here, the hunters are setting up shells. Flags and silhouettes are handy because they take up less storage space and can add depth to a spread.



Outfitter Darren Roe demonstrates proper calling form (right), employing a Basin Abomination short reed goose call. Use your middle finger to change tones and your off-hand to direct the sound up and down, left and right. Begin to muffle the call as the birds get closer. The subtle sound keeps them coming.

GOOSE HUNTING TIPS

Locate geese midmorning or late afternoon by scouting grain fields near resting waters. Secure permission and hunt the field the next feeding period.

Use flags to gain the attention of distant geese. The waving flags imitate geese fluttering in to a flock of feeding geese.

Pass-shoot geese flying to and from feeding areas. Many refuges allow hunting along the boundaries.

INDEX

A

Action, 22, 23, 32
Ammunition, 24–25, 28
Antelope. See *Pronghorns*
Antler rattling, 64, 78
Antlers, 61
Arkansas style calls, 140
Arrows, 35, 36, 37

B

Ballistics tables, 24, 25
Bear. See *Black bear*
Beds and bedding, 3, 14, 47, 50
Bellows calls, 130
Big game, 8, 10–11, 14, 34, 40, 59–85
Binoculars, 46, 50, 70, 73, 140
Black bear, 82–83
  Breeding season, 82
  Calling for, 82
  Daily and seasonal movements, 82
  Description, 82
  Escape tactics, 82
  Food and feeding, 82
  Habitat, 12, 82
  Hibernation, 82
  Hunting techniques, 49, 82–83
  Range map, 82
  Record weight, 82
  Rifles, ammunition, 83
  Senses, 82
  Sign, 83
  Territories, 82
Black-tailed deer, 71–73
  Daily and seasonal movements, 73
  Description, 71
  Escape tactics, 73
  Food and feeding, 71, 73
  Habitat, 71, 72, 73
  Hunting techniques, 71, 72, 73
Blinds, 49, 65, 81, 133, 143
Boats, 46, 55
  Canoes, 55, 144
  Double-pointed duck, 55
  Duck, 140
  Jon, 55
  Low-profile, 147
  Sculling, 55, 147
  Semi-V, 55, 147
Bobwhite quail, 13, 114–16
  Daily and seasonal movement, 114
  Description, 114
  Escape tactics, 114–15
  Foods and feeding, 16, 114, 115
  Habitat, 114, 115
  Hunting techniques, 115, 116
  Nesting, 114
  Range map, 114
  Roosting, 114, 115
  Shotguns, chokes, shot sizes, 115
  Sounds, 114, 116
Bolt action rifles, 22–23
Bore, 23, 28, 32
Bore sighting, 28
Bowhunting, 35–39, 50, 76, 77, 81
  Energy, 35
  Equipment, 35, 36, 39
  Types of arrowheads, 36
  Types of bows, 35
Box calls, 130
Brant geese, 151
Bugling, 52, 85–87
Bullets, 23, 24–25, 28–31, 41
  Ballistics tables, 24
  Energy, 24, 25
  Factors that affect flight path, 24, 30
  Mushrooming, 24
  Slant range effect, 30
  Styles, 24, 25
  Trajectory, 24, 25, 41
  Velocity, 24, 25
  Weight, 24
  Wind drift, 30, 31

C

Caliber, 22–24, 40
California quail, 117
Calls and calling, 78, 103, 130, 140, 153
  Arkansas style, 140
  Bellows, 130
  Coyote howler, 130
  Crow call, 130
  Diaphragm, 76, 130
  Diver, 147
  Flute, 76, 130, 140
  Hawk screamer, 130
  Owl hooter, 130
  Pigtail, 76
  Pileated woodpecker, 130
  Predator, 130
  Pronghorn, 81
  Push-pull, 130
  Silent whistle, 130
  Slate-and-peg, 130
  Standard, 140
  Tube, 76, 130
Canada geese, 149, 150, 151
  Calls for, 140, 153
  Decoys, 149, 152, 153
Canoes, 55
Canvasbacks, 146
Carbines, 22
Cartridges, 24, 25
Chokes, 33
Chuckar partridge, 126
Clothing, 42, 48, 49, 50, 52, 66, 87, 104, 115, 116, 118, 136, 140, 143, 147
Color vision of game, 8, 10, 60
Compound bows, 35, 36, 38
Cottontail rabbits, 88–91
  Breeding season, 88
  Daily movements, 88
  Description, 89
  Diseases, 88
  Escape tactics, 88
  Foods and feeding, 88
  Habitat, 88, 89
  Home range, 88, 91
  Hunting techniques, 88, 90, 91
  Range map, 88
  Rifles, scopes, ammunition, 88
  Senses, 9, 88
  Shotguns, chokes, shot size, 33
  Sign, 90

Cover, 12, 13–15, 50, 51, 73
  Corridors, 52, 72
  Escape, 13
  For bedding, 13, 47
  From the elements, 14
  Islands, 52
  Midday, 14
  Types, 13–14
Coyotes, 103–5
  Calls for, 103, 104, 105
  Daily movement, 105
  Decoys, 105
  Dens and denning, 103
  Description, 103
  Foods and feeding, 103
  Habitat, 103
  Hunting techniques, 103, 104
  Range map, 103
  Rifles, ammunition, 104
  Shotguns, ammunition, 104
  Sign, 103
  Territories, 104

D

Deer, 16, 25, 49, 55, 60–73
Diaphragm calls, 76, 130
Diving ducks, 146–48
  Calls for, 147
  Decoys, 147, 148
  Description, 139, 146
  Foods and feeding, 146
  Hunting techniques, 147–48
  Migration, 147
Dogs, 53, 54, 56, 57, 88, 90, 91, 111, 115, 122–23, 126, 127, 137
  American water spaniel, 54
  Basset hound, 88
  Beagle, 54, 88
  Black-and-tan hound, 54, 82
  Bluetick hound, 54
  Boykin spaniel, 54
  Brittany spaniel, 54, 115
  Chesapeake Bay retriever, 54, 147
  Cocker spaniel, 54
  English pointer, 54, 115
  English setter, 54, 115
  German shorthair, 54, 115
  Golden retriever, 54
  Gordon setter, 54
  Labrador retriever, 54, 111, 147
  Plotts, 82
  Redbone hound, 54, 102
  Redtick hound, 54
  Springer spaniel, 54, 111
  Training, 54
  Walker hound, 54, 82, 102
  Weimaraner, 54
Doves. See *Mourning doves*
Driving, 52
  For elk, 76
  For jackrabbits, 92
  For mule deer, 70
  For pheasants, 110, 112–13
  For whitetails, 64, 67
  Safety, 52
  Where to drive, 52
Droppings, 47, 53, 63, 75, 79, 83, 91, 103, 122
Ducks, 8, 9, 142–48
  Calls for, 140
  Decoys, 141
  Description, 139
  Foods and feeding, 16,
  Hunting techniques, 49, 143–44
  Shotguns, choke, shot sizes, 33

E

Elk, 16, 74–77
  Beds and bedding, 74, 75
  Bows, 76
  Breeding season, 74, 76
  Calls for, 76–77
  Daily movements, 74, 75
  Description, 74
  Escape tactics, 74
  Foods and feeding, 16, 74, 75
  Habitat, 17, 74
  Hunting techniques, 76, 77
  Migration, 74–75
  Muzzleloading, 76
  Range map, 74
  Record antlers, 74
  Rifles, ammunition, 25, 76
  Senses, 74
  Sign, 46, 75, 76
  Sounds, 75, 76
  Territories, 74, 75
  Varieties, 74
  Wallows, 75, 77

F

Falling block action rifles, 23
Firing zone, 43
Flagging devices, 141, 153
Float-hunting, 55
  For ducks, 144
  For moose, 78, 79
  For squirrels, 98
  For whitetails, 64
Flushing, 53
  For bobwhite quail, 115
  For cottontails, 91
  For grouse, 121–23, 124, 125
  For partridges, 126
  For pheasants, 110, 111, 112–13
  For quail, 119
  For woodcock, 137
Flute call, 76, 130, 140
Fox squirrels, 95, 96–98
  Breeding season, 97
  Calls for, 98
  Daily movements, 95, 97
  Dens and denning, 96
  Description, 95
  Escape tactics, 95, 97
  Foods and feeding, 95, 97
  Habitat, 95, 97
  Hunting techniques, 97, 98
  Nests, 96
  Range map, 95
  Rifles, scopes, ammunition, 97
  Shotguns, shot size, 97
  Sign, 96
  Sounds, 95
Friction calls, 130

G

Gambel's quail, 16, 118
Game trails. See *Trails*
Geese, 149–53
  Calls for, 140, 153
  Daily movements, 152
  Decoys, 151, 152, 153
  Description, 139, 149, 150–51
  Escape tactics, 149
  Foods and feeding, 16, 149
  Habitat, 1551–52
  Hunting techniques, 49, 49, 151–53
  Migration, 149
  Shotguns, chokes, shot sizes, 33, 152
  Species, 150–51
Gray partridge. See *Hungarian partridge*
Gray squirrels, 94, 96–98
  Breeding season, 97
  Daily movements, 94, 97
  Dens and denning, 96
  Description, 94
  Escape tactics, 94, 97
  Foods and feeding, 94, 97
  Habitat, 94, 97
  Home range, 94
  Hunting techniques, 97, 98
  Nests, 96
  Range map, 94
  Rifles, scopes, ammunition, 97
  Senses, 94
  Shotguns, shot size, 97
  Sign, 96
  Sounds, 98
Ground squirrels, 100
Grouse, 8, 17, 33, 121–25

H

Habitat, 12–19, 46
Hares, 92, 93
Hearing. See *Senses*
Hounds, 54, 82, 83, 90, 93, 102. See also *Dogs*
Hungarian partridge, 127
Hunting equipment
  For big game, 59
  For small game, 87
  For upland game birds, 107
  For waterfowl, 140–41
Hunting techniques
  Antler rattling, 64
  Baiting, 82, 83
  Jump-shooting, 142
  Leapfrog technique, 113
  Pass-shooting, 136, 144, 153
  Running-and-gunning, 133, 134
  Sitting-and-waiting, 133, 134
  Sustained-lead technique, 34, 39
  Swing-through technique, 34, 47
  Tag-team, 134
  Walk-and-wait, 118, 122

J

Jackrabbits, 92
Jon boats, 55
Jump-shooting, 142

L

Leapfrog technique, 113
Lever action rifles, 23
Licenses, 45
Locator calls, 130, 131
Longbows, 35, 36, 38

M

Mallard ducks, 8, 143
Mergansers, 146
Metatarsal glands, 11
Moose, 5, 78–79
  Beds and bedding, 78
  Breeding season, 78
  Daily and seasonal movements, 78
  Description, 78, 79
  Escape tactics, 78, 79
  Foods and feeding, 78, 79
  Habitat, 17, 78, 79
  Home range, 78
  Hunting techniques, 15, 49, 78, 79
  Range map, 78
  Record antlers, 78
  Rifles, ammunition, 25, 78
  Senses, 78
  Sign, 71, 78, 79
  Wallows, 78
  Water, 49
Mountain quail, 119
Mourning doves, 49, 135–36
  Daily movements, 135
  Description, 135
  Escape tactics, 135
  Foods and feeding, 135–36
  Habitat, 135, 136
  Hunting techniques, 49, 136
  Migration, 135
  Nesting, 135
  Range map, 135
  Roosting, 135, 136
  Shotguns, chokes, shot sizes, 33, 136
  Water and watering sites, 49, 107, 135, 136
Mule deer, 11, 68–70
  Beds and bedding, 68, 70
  Breeding season, 69
  Daily movements, 68–69
  Description, 68
  Escape tactics, 11, 68, 70
  Food and feeding, 68–69, 70
  Habitat, 68, 70
  Home range, 68
  Hunting techniques, 69–70
  Migration, 69
  Range map, 68
  Record antlers, 68
  Record weight, 69
  Rifles, ammunition, 70
  Senses, 11, 68
  Sign, 71, 69
  Varieties, 69
Muzzleloaders, 40–41, 76

P

Partridge, 126–27
Pass-shooting,
  For doves, 136
  For geese, 151, 153
  For puddle ducks, 144
Pheasants. See *Ring-necked pheasants*
Pigtail call, 76
Prairie dogs, 99
Pronghorns, 11, 80–81
  Breeding season, 81
  Calls for, 81
  Daily movements, 80
  Decoys, 81
  Description, 80, 81
  Escape tactics, 11, 80
  Foods and feeding, 80
  Habitat, 80
  Home range, 80–81
  Hunting techniques, 49, 81
  Record horns, 80
  Rifles, scopes, ammunition, 81
  Senses, 80
  Territories, 81
  Water and watering sites, 16, 49
Puddle ducks, 139, 142–45
  Calls for, 143

  Decoys, 143, 144, 145
  Description, 142
  Food and feeding, 142
  Habitat, 142, 143
  Hunting techniques, 142–45
Pump action rifles, 23
Pump action shotguns, 32
Push-pull calls, 130

Q

Quail, 12, 33, 114–20

R

Rabbits, 8, 17, 54, 88–91
Raccoon, 10, 101–2
  Beds and bedding, 101
  Calls for, 102
  Daily movements, 101
  Dens and denning, 101
  Description, 101
  Escape tactics, 101, 102
  Foods and feeding, 101
  Habitat, 101, 102
  Handguns, 102
  Hibernation, 101
  Hunting techniques, 102
  Range map, 101
  Record weight, 101
  Rifles, 102
  Senses, 101
  Shotguns, shot sizes, 33, 102
  Sign, 102
Recurve bows, 35, 36, 38
Redheads, 146
Red squirrels, 95
Regulations, hunting, 7
Rifle sights, 26–29
Rifles, 5, 22–31
  Actions, 22
  Ammunition, 24–25
  Caliber, 22–23
  Combination guns, 35, 87
  Performance, 26, 28
  Shooting a rifle, 28, 30–31
  Sights, 26–29
  Weight, 22
Ring-necked pheasants, 5, 11, 15, 109–13
  Daily and seasonal movements, 108, 109
  Description, 108, 109
  Escape tactics, 11, 108
  Foods and feeding, 16, 108, 109, 113
  Habitat, 12, 13, 17, 107, 108, 109, 110, 112
  Home range, 108
  Hunting techniques, 109, 110, 111, 112
  Nesting, 108, 110
  Range map, 108
  Roosting, 108
  Senses, 9, 108
  Shotguns, chokes, shot sizes, 33, 110
  Sounds, 108, 109, 112
Ross geese, 151
Ruffed grouse, 121–23
  Breeding season, 121
  Daily and seasonal movements, 121
  Description, 122
  Drumming, 121, 122, 123
  Escape tactics, 121–23
  Foods and feeding, 121, 123
  Habitat, 12, 121
  Hunting techniques, 121–23
  Nesting, 121
  Range map, 121
  Roosting, 121, 122
  Shotguns, choke, shot sizes, 122
  Sign, 121, 122
  Sounds, 121, 122, 123
  Territories, 121
Running-and-gunning, 134

S

Sage grouse, 17, 125
Sea ducks, 146
Safety, 42–43, 55, 67, 92, 110, 136
Scaled quail, 120
Scent, 11
Scopes, 26, 29, 46, 50, 70, 73
Scouting for game, 17, 46–47, 49, 59, 62, 64, 65, 151
Sculling boats, 55
Semi-automatic action rifles, 23
Semi-automatic action shotguns, 32
Semi-Vs, 55
Senses, 8–11
Sharp-tailed grouse, 107, 124
Shotguns, 32–34
  Actions, 32
  Barrel type, 32
  Bore size, 32
  Chamber length, 32
  Chokes, 32, 33
  Shells, 32
  Shooting a shotgun, 34
  Weight, 32
Sitting-and-waiting technique, 134
Slate-and-peg calls, 130
Slugs, 34
Small game, 7, 14, 54, 87–105
Ammunition, 40, 87
Snow geese, 150
Snowshoe hares, 33 93
Squirrels, 6, 33, 46, 54, 55, 94–98, 100
Stalking, 50–51
  For black bears, 82
  For elk, 76
  For geese, 152
  For moose, 78
  For mule deer, 70
  For pronghorns, 81
  For sage grouse, 125
  For whitetails, 64
  For wild boars, 84
Stand-hunting, 49, 65
  For elk, 76, 77
  For deer, 65
  For moose, 78
  For mule deer, 70
  For pronghorns, 81
  For squirrels, 97, 98
  For whitetails, 64, 65
Still-hunting, 48, 66
  For bear, 82
  For elk, 76, 77
  For moose, 78
  For mule deer, 70
  For squirrels, 97
  For whitetails, 64, 66–67
Succession, 12
Swing-through technique, 34, 147

T

Tag-team hunting, 134
Teals, 143
Team-hunting, 98
Tracks, 47, 53, 63, 77, 83, 85, 90, 104, 112, 122
Trails, 47, 49, 85
Trajectory
  Of arrows, 37
  Of rifle bullets, 24, 25, 30
  Of muzzleloader balls, 41
Tube calls, 130
Turkey. See *Wild turkey*

U

Upland game birds, 7, 40, 54, 107–37

V

Varmints, 40
Vision. See *Senses*

W

Water, 16, 17, 49
Waterfowl, 7, 17, 21, 46, 49, 50, 54, 55, 139–53
  Calls for, 140
  Decoys, 141
  Equipment, 140–41
  Migration, 17
  Muzzleloaders, 40
  Population, 7
  Senses, 8
  Shotguns, ammunition, 32, 140
White-fronted geese, 150
White-tailed deer, 10, 60–67
  Beds and bedding, 62
  Breeding season, 62
  Daily and seasonal movements, 62
  Description, 60
  Escape tactics, 60, 61
  Foods and feeding, 16, 62
  Habitat, 12, 17, 62, 63
  Home range, 60, 62
  Hunting techniques, 61, 64–67
  Range map, 60
  Record antlers, 60
  Record weight, 60
  Rifles, ammunition, 65
  Senses, 10, 60,
  Sign, 62, 63
  Sounds, 60
  Varieties, 60
Wild boar, 84–85
  Beds and bedding, 84
  Daily and seasonal movements, 84, 85
  Description, 84
  Escape tactics, 84–85
  Foods and feeding, 84
  Hunting techniques, 84–85
  Rifles, ammunition, 85
  Senses, 84
  Sign, 85
  Wallows, 85
Wildlife management, 12, 16, 45
Wild turkey, 8, 128–34
  Breeding season, 129
  Calls for, 130–31, 132, 133
  Daily movement patterns, 131–33, 134
  Decoys, 130–31
  Description, 128–29
  Escape tactics, 129, 132
  Foods and feeding, 132, 133
  Habitat, 134
  Hunting techniques, 132–34
  Muzzleloaders, 40
  Nesting, 133
  Range map, 128
  Roosting, 131, 132, 134
  Senses, 8, 9, 129
  Shotguns, choke, shot sizes, 33
  Sounds, 128, 129, 132–33, 134
  Strutting zones, 131–33, 134
  Subspecies, 129
  Water and watering sites, 132
Wind drift, 30, 31
Woodcock, 11, 137

PHOTO CREDITS

Note: T = Top, B = Bottom, C = Center, L = left, R = Right, I = inset

© Grady Allen: pp. 101, 116BR
© Charles Alsheimer: p. 63TR
© Erwin Bauer: pp. 8R, 26, 61C, 61CR, 61BL, 76B, 83T, 123BR
© Craig Blacklock: p. 58
© Les Blacklock: p. 12
© Tom Brakefield: p. 61T, Back Cover TL
© The Browning Company: pp. 48C, 149
© Glenn D. Chambers: p. 114
© Tim Christie: p. 93I, Front Cover BC
© Herbert Clarke: pp. 117, 119
© Daniel J. Cox: p. 16, 61 far left
© John Ebeling: p. 11BC
© John Ford: Front Cover T
© Michael Francis: pp. 99B, 104, Front Cover TC
© Michael Furtman: pp. 138, 146T
© Eric J. Hansen: pp. 6, 20, 44, 62, 71
© istock photo: p. 100
© Larry D. Jones: pp. 75BC, 75BR
© Gary Kramer: pp. 72, 73R, 85TL, 86, 105BL, 122, 128, 133, 142BR
© Lon E. Lauber: pp. 35, 39T, 65T, 66, 73L, 84, 92, 105BR, 129, 132
© Gary Lewis: pp. 85TR, 85B, 153R
© Tom Mangelson: pp. 54, 109TR
© Bill Marchel: pp. 142BL, 142CR, 150T, 150BL, 150BR, Front Cover B
© Tom Martinson: p. 8L
© Jay Massey: p. 50
© Worth Mathewson: p. 94
© Bill McRae: pp. 77BR, 81TL, 109TL
© Wyman Meinzer: p. 120
© Arthur Morris/Birds as Art: pp. 151TR, 151BR
© William H. Mullins: p. 124
© Doug Murphy: p. 11TL
© Nebraska Game And Parks Commission, 13
© Scott Nielsen: p. 142T, 146BL, 146BR
© Jerome B. Robinson: p. 55
© Lynn Rogers: p. 93T
© Leonard Lee Rue III: pp. 47CR, 63TL, 89T, 102T, 135
© Dwight R. Schuh: p. 77T
© Ron Shade: pp. 69, 75T
© Jerry Smith: p. 61BR
© Dale C. Spartas: pp. 11TR, 123T, 123BL
© Ron Spomer: pp. 10TR, 11BL, 11BR, 19BL, 95, 151L
© Norm Strung: p. 65B
© Syl Strung: p. 79BR
© Ken Thommes: pp. 99T, 105TL, 105TR, Back Cover BR
© Charles Waterman: p. 125
© Chuck Wechsler: pp. 61CR, 61 far right
© Ron Winch: p. 79T
© James Zacks: p. 10TL
© Gary Zahm: pp. 10BR, 118, 136

Creative Publishing international

Your Complete Source of How-to Information for the Outdoors



Preparing Fish & Wild Game
The Complete Guide to Freshwater Fishing
Fly Fishing for Trout in Streams
Whitetail Hunting
Dog Training

Hunting Books
- Advanced Turkey Hunting
- Advanced Whitetail Hunting
- Beginner's Guide to Birdwatching
- Black Bear Hunting
- Bowhunting Equipment & Skills
- Bowhunter's Guide to Accurate Shooting
- The Complete Guide to Hunting
- Dog Training
- Elk Hunting
- How to Think Like a Survivor
- Hunting Record-Book Bucks
- Mule Deer Hunting
- Muzzleloading
- Outdoor Guide to Using Your GPS
- Waterfowl Hunting
- Whitetail Addicts Manual
- Whitetail Hunting
- Whitetail Techniques & Tactics
- Wild Turkey

Fishing Books
- Advanced Bass Fishing
- The Art of Freshwater Fishing
- The Complete Guide to Freshwater Fishing
- Fishing for Catfish
- Fishing Tips & Tricks
- Fishing with Artificial Lures
- Inshore Salt Water Fishing
- Kids Gone Campin'
- Kids Gone Fishin'
- Kids Gone Paddlin'
- Largemouth Bass
- Live Bait Fishing
- Modern Methods of Ice Fishing
- Northern Pike & Muskie
- Panfish
- Salt Water Fishing Tactics
- Smallmouth Bass
- Striped Bass Fishing: Salt Water Strategies
- Successful Walleye Fishing
- Ultralight Fishing

Fly Fishing Books
- The Art of Fly Tying + CD-ROM
- Complete Photo Guide to Fly Fishing
- Complete Photo Guide to Fly Tying
- Fishing Dry Flies
- Fly-Fishing Equipment & Skills
- Fly Fishing for Beginners
- Fly Fishing for Trout in Streams
- Fly-Tying Techniques & Patterns

Cookbooks
- All-Time Favorite Game Bird Recipes
- America's Favorite Fish Recipes
- America's Favorite Wild Game Recipes
- Backyard Grilling
- Cooking Wild in Kate's Kitchen
- Dressing & Cooking Wild Game
- The New Cleaning & Cooking Fish
- Preparing Fish & Wild Game
- The Saltwater Cookbook
- Venison Cookery
- The Wild Butcher
- The Wild Fish Cookbook
- The Wild Game Cookbook

To purchase these or other Creative Publishing international titles, contact your local bookseller, or visit our website at
www.creativepub.com

The Freshwater Angler™

THE COMPLETE HUNTER™

The Complete FLY FISHERMAN™

HURRICANE • FLASH FLOOD • FIRE • HAZARDOUS MATERIALS SPILL • EARTHQUAKE • TORNADO • WINTER STORM

Your Family Disaster Plan

Where will your family be when disaster strikes? They could be anywhere—

at work



at school



or in the car.

How will you find each other? Will you know if your children are safe?

Disaster can strike quickly and without warning. It can force you to evacuate your neighborhood or confine you to your home. What would you do if basic services–water, gas, electricity or telephones–were cut off? Local officials and relief workers will be on the scene after a disaster, but they cannot reach everyone right away.

Families can–and do–cope with disaster by preparing in advance and working together as a team. Follow the steps listed in this brochure to create your family's disaster plan. Knowing what to do is your best protection and your responsibility.

Federal Emergency Management Agency

American Red Cross

EMERGENCY SUPPLIES

Keep enough supplies in your home to meet your needs for at least three days. Assemble a Disaster Supplies Kit with items you may need in an evacuation. Store these supplies in sturdy, easy-to-carry containers such as backpacks, duffle bags or covered trash containers.



Include:

- A three-day supply of water (one gallon per person per day) and food that won't spoil.
- One change of clothing and footwear per person, and one blanket or sleeping bag per person.
- A first aid kit that includes your family's prescription medications.
- Emergency tools including a battery-powered radio, flashlight and plenty of extra batteries.
- An extra set of car keys and a credit card, cash or traveler's checks.
- Sanitation supplies.
- Special items for infant, elderly or disabled family members.
- An extra pair of glasses.

Keep important family documents in a waterproof container. Keep a smaller kit in the trunk of your car.

UTILITIES

Locate the main electric fuse box, water service main and natural gas main. Learn how and when to turn these utilities off. Teach all responsible family members. Keep necessary tools near gas and water shut-off valves.

Remember, turn off the utilities only if you suspect the lines are damaged or if you are instructed to do so. *If you turn the gas off, you will need a professional to turn it back on.*

4 Steps to Safety

1

Find Out What Could Happen to You

Contact your local emergency management or civil defense office and American Red Cross chapter—be prepared to take notes:

- ☐ Ask what types of disasters are most likely to happen. Request information on how to prepare for each.
- ☐ Learn about your community's warning signals: what they sound like and what you should do when you hear them.
- ☐ Ask about animal care after disaster. Animals may not be allowed inside emergency shelters due to health regulations.
- ☐ Find out how to help elderly or disabled persons, if needed.
- ☐ Next, find out about the disaster plans at your workplace, your children's school or daycare center and other places where your family spends time.

2

Create a Disaster Plan

Meet with your family and discuss why you need to prepare for disaster. Explain the dangers of fire, severe weather and earthquakes to children. Plan to share responsibilities and work together as a team.

- ☐ Discuss the types of disasters that are most likely to happen. Explain what to do in each case.
- ☐ Pick two places to meet:

  1. Right outside your home in case of a sudden emergency, like a fire.

  2. Outside your neighborhood in case you can't return home. Everyone must know the address and phone number.
- ☐ Ask an out-of-state friend to be your "family contact." After a disaster, it's often easier to call long distance. Other family members should call this person and tell them where they are. Everyone must know your contact's phone number.
- ☐ Discuss what to do in an evacuation. Plan how to take care of your pets.

Fill out, copy and distribute to all family members

Family Disaster Plan

Emergency Meeting Place ______________________
outside your home

Meeting Place ______________ Phone ______________
outside your neighborhood

Address ______________________

____

Family Contact ______________________
(name)

Phone (   ) ______________ Phone (   ) ______________
day evening

3

Complete This Checklist

☐ Post emergency telephone numbers by phones (fire, police, ambulance, etc.).

☐ Teach children how and when to call 911 or your local Emergency Medical Services number for emergency help.

☐ Show each family member how and when to turn off the water, gas and electricity at the main switches.

☐ Check if you have adequate insurance coverage.

☐ Teach each family member how to use the fire extinguisher (ABC type), and show them where it's kept.

☐ Install smoke detectors on each level of your home, especially near bedrooms.

☐ Conduct a home hazard hunt.

☐ Stock emergency supplies and assemble a Disaster Supplies Kit.

☐ Take a Red Cross first aid and CPR class.

☐ Determine the best escape routes from your home. Find two ways out of each room.

☐ Find the safe spots in your home for each type of disaster.

4

Practice and Maintain Your Plan

☐ Quiz your kids every six months so they remember what to do.

☐ Conduct fire and emergency evacuation drills.

Year	Drill Date

☐ Replace stored water every three months and stored food every six months.

☐ Test and recharge your fire extinguisher(s) according to manufacturer's instructions.

☐ Test your smoke detectors monthly and change the batteries at least once a year.

Jan. ☐
Feb. ☐
Mar. ☐
Apr. ☐
May ☐
June ☐

July ☐
Aug. ☐
Sep. ☐
Oct. ☐
Nov. ☐
Dec. ☐

Change batteries in ________ each year.
(month)

NEIGHBORS HELPING NEIGHBORS

Working with neighbors can save lives and property. Meet with your neighbors to plan how the neighborhood could work together after a disaster until help arrives. If you're a member of a neighborhood organization, such as a home association or crime watch group, introduce disaster preparedness as a new activity. Know your neighbors' special skills (e.g., medical, technical) and consider how you could help neighbors who have special needs, such as disabled and elderly persons. Make plans for child care in case parents can't get home.

HOME HAZARD HUNT

During a disaster, ordinary objects in your home can cause injury or damage. Anything that can move, fall, break or cause a fire is a home hazard. For example, a hot water heater or a bookshelf can fall. Inspect your home at least once a year and fix potential hazards.

Contact your local fire department to learn about home fire hazards.



EVACUATION

Evacuate immediately if told to do so:

- Listen to your battery-powered radio and follow the instructions of local emergency officials.
- Wear protective clothing and sturdy shoes.
- Take your Disaster Supplies Kit.
- Lock your home.
- Use travel routes specified by local authorities — don't use shortcuts because certain areas may be impassable or dangerous.

If you're sure you have time:

- Shut off water, gas and electricity before leaving, if instructed to do so.
- Post a note telling others when you left and where you are going.
- Make arrangements for your pets.

IF DISASTER STRIKES

If disaster strikes

Remain calm and patient. Put your plan into action.

Check for injuries

Give first aid and get help for seriously injured people.

Listen to your battery powered radio for news and instructions

Evacuate, if advised to do so. Wear protective clothing and sturdy shoes.

Check for damage in your home. . .

- Use flashlights — do not light matches or turn on electrical switches, if you suspect damage.
- Check for fires, fire hazards and other household hazards.
- Sniff for gas leaks, starting at the water heater. If you smell gas or suspect a leak, turn off the main gas valve, open windows, and get everyone outside quickly.
- Shut off any other damaged utilities.
- Clean up spilled medicines, bleaches, gasoline and other flammable liquids immediately.

Remember to. . .

- Confine or secure your pets.
- Call your family contact— do not use the telephone again unless it is a life-threatening emergency.
- Check on your neighbors, especially elderly or disabled persons.
- Make sure you have an adequate water supply in case service is cut off.
- Stay away from downed power lines.

The Federal Emergency Management Agency's Community and Family Preparedness Program and the American Red Cross Community Disaster Education Program are nationwide efforts to help people prepare for disasters of all types. For more information, please contact your local emergency management office and American Red Cross chapter. This brochure and other preparedness materials are available by calling FEMA at 1-800-480-2520, or writing: FEMA, P.O. Box 2012, Jessup, MD 20794-2012.

Publications are also available on the World Wide Web at:

FEMA's Web site: http://www.fema.gov

American Red Cross Web site: http://www.redcross.org

Ask for: *Are You Ready?, Your Family Disaster Supplies Kit* and *Food & Water in an Emergency*.

Local sponsorship provided by:

September 1991
FEMA L-191
ARC 4466

HURRICANE • FLASH FLOOD • HAZARDOUS MATERIALS SPI

Your
Family Disaster Pl

Federal Emergency
Management Agency

EARTHQUAKE • TORNADO • WINTER STORM • FIRE

FACT SHEET

Federal Emergency Management Agency

WINTER STORMS

A major winter storm can be lethal. Preparing for cold weather conditions and responding to them effectively can reduce the dangers caused by winter storms.

Be familiar with winter storm warning messages.

(See *Winter Storm Watches and Warnings)*

Service snow removal equipment and have rock salt on hand to melt ice on walkways and kitty litter to generate temporary traction.

Make sure you have sufficient heating fuel; regular fuel sources may be cut off.

Winterize your home.

- Insulate walls and attic.
- Caulk and weather-strip doors and windows.
- Install storm windows or cover windows with plastic from the inside.

Have *safe* emergency heating equipment available.

- Fireplace with ample supply of wood
- Small, well-vented wood, coal, or camp stove with fuel
- Portable space heaters or kerosene heaters (See *Kerosene Heaters*)

Install and check smoke detectors.

Contact your local emergency management office or American Red Cross chapter for more information on winter storms.

Keep pipes from freezing.

- Wrap pipes in insulation or layers of old newspapers.
- Cover the newspapers with plastic to keep out moisture.
- Let faucets drip a little to avoid freezing.
- Know how to shut off water valves.

Have disaster supplies on hand, in case the power goes out.

- Flashlight and extra batteries
- Portable, battery-operated radio and extra batteries
- First aid kit
- One-week supply of food (include items that do not require refrigeration or cooking in case the power is shut off)
- Nonelectric can opener
- One-week supply of essential prescription medications
- Extra blankets and sleeping bags
- Fire extinguisher (A-B-C type)

Develop an emergency communication plan.

In case family members are separated from one another during a winter storm (a real possibility during the day when adults are at work and children are at school), have a plan for getting back together.

Ask an out-of-state relative or friend to serve as the “family contact.” After a disaster, it’s often easier to call long distance. Make sure everyone in the family knows the name, address, and phone number of the contact person.

Make sure that all family members know how to respond after a severe winter storm.

Teach children how and when to call 9-1-1, police, or fire department, and which radio station to tune to for emergency information.

Kerosene Heaters

Check with your local fire department on the legality of using kerosene heaters in your community. Use only the correct fuel for your unit and follow the manufacturer’s instructions. Refuel outdoors only, and only when cool. Keep your kerosene heater at least 3 feet away from furniture and other flammable objects.

IF INDOORS

Stay indoors and dress warmly.

Conserve fuel.
Lower the thermostat to 65 degrees during the day and 55 degrees at night. Close off unused rooms.

If the pipes freeze, remove any insulation or layers of newspapers and wrap pipes in rags.
Completely open all faucets and pour hot water over the pipes, starting where they were most exposed to the cold (or where the cold was most likely to penetrate).

Listen to the radio or television to get the latest storm information.

IF OUTDOORS

Dress warmly.
Wear loose-fitting, layered, lightweight clothing. Layers can be removed to prevent perspiration and chill. Outer garments should be tightly woven and water repellent. Mittens are warmer than gloves because fingers generate warmth when they touch each other.

Stretch before you go out.
If you go out to shovel snow, do a few stretching exercises to warm up your body. Also, take frequent breaks.

Cover your mouth.
Protect your lungs from extremely cold air by covering your mouth when outdoors. Try not to speak unless absolutely necessary.

Avoid overexertion.
Cold weather puts an added strain on the heart. Unaccustomed exercise such as shoveling snow or pushing a car can bring on a heart attack or make other medical conditions worse. Be aware of symptoms of dehydration.

Watch for signs of frostbite and hypothermia.

Keep dry.
Change wet clothing frequently to prevent a loss of body heat. Wet clothing loses all of its insulating value and transmits heat rapidly.

Remember to help your neighbors who may require special assistance — infants, elderly people, and people with disabilities.

Mitigation

Mitigation includes any activities that prevent an emergency, reduce the chance of an emergency happening, or lessen the damaging effects of unavoidable emergencies. Investing in preventive mitigation steps now such as purchasing a flood insurance policy and installing storm windows will help reduce the impact of winter storms in the future. For more information on mitigation, contact your local emergency management office.

Wind Chill

"Wind chill" is a calculation of how cold it feels outside when the effects of temperature and wind speed are combined. A strong wind combined with a temperature of just below freezing can have the same effect as a still air temperature about 35 degrees colder.

Frostbite and Hypothermia

Frostbite is a severe reaction to cold exposure that can permanently damage its victims. A loss of feeling and a white or pale appearance in fingers, toes, or nose and ear lobes are symptoms of frostbite.

Hypothermia is a condition brought on when the body temperature drops to less than 55 degrees Fahrenheit. Symptoms of hypothermia include uncontrollable shivering, slow speech, memory lapses, frequent stumbling, drowsiness, and exhaustion.

If frostbite or hypothermia is suspected, begin warming the person slowly and seek immediate medical assistance. Warm the person's trunk first. Use your own body heat to help. Arms and legs should be warmed last because stimulation of the limbs can drive cold blood toward the heart and lead to heart failure. Put person in dry clothing and wrap their entire body in a blanket.

Never give a frostbite or hypothermia victim something with caffeine in it (like coffee or tea) or alcohol. Caffeine, a stimulant, can cause the heart to beat faster and hasten the effects the cold has on the body. Alcohol, a depressant, can slow the heart and also hasten the ill effects of cold body temperatures.

Winter Storm Watches and Warnings

A *winter storm watch* indicates that severe winter weather may affect your area. A *winter storm warning* indicates that severe winter weather conditions are definitely on the way.

A *blizzard warning* means that large amounts of falling or blowing snow and sustained winds of at least 35 miles per hour are expected for several hours.

BACKGROUNDER

WINTER STORMS

EMERGENCY INFORMATION

1. A major winter storm can last for several days and be accompanied by high winds, freezing rain or sleet, heavy snowfall, and extremely cold temperatures. People can become stranded on the road or trapped at home, without utilities or other services. *The best protection against severe winter weather is to stay inside and to dress warmly by wearing loose-fitting, layered, lightweight clothing.*

2. A serious danger during a winter storm is *hypothermia*—a condition brought on when the body temperature drops because of prolonged exposure to extreme cold. Hypothermia is not always fatal, but for those who survive there are likely to be lasting kidney, liver, and pancreatic problems.

3. Heavy snowfall and blizzards can trap motorists in their cars. Attempting to walk for help in a blizzard can be a deadly decision. Disorientation and confusion come very quickly in blowing snow. People trapped in a car during a blizzard do best to stay in the car and wait for help.



Source: Council of State Governments and FEMA

Almost the entire United States except Hawaii and the territories are at some risk from winter storms. The level of risk depends on the severity of local winter weather. Winter storms known as "northeasters" cause extensive coastal flooding, erosion, and property loss in the northeastern and middle Atlantic states.

WHAT IS A WINTER STORM?

A winter storm can range from moderate snow over a few hours to blizzard conditions with blinding wind-driven snow that last several days. Some winter storms may be large enough to affect several states while others may affect only a single community. All winter storms are accompanied by low temperatures and blowing snow, which can severely reduce visibility. A severe winter storm is one that drops 4 or more inches of snow during a 12-hour period, or 6 or more inches during a 24-hour span. An ice storm occurs when freezing rain falls from clouds and freezes immediately on impact. All winter storms make driving and walking extremely hazardous. The aftermath of a winter storm can impact a community or region for days, weeks, and even months. Storm effects such as extreme cold, flooding, and snow accumulation can cause hazardous conditions and hidden problems for people in the affected area.

HELP YOUR COMMUNITY GET READY

The media can raise awareness about winter storms by providing important information to the community. Here are some suggestions:



1. Publish a special section in your local newspaper with emergency information about winter storms. Place special emphasis on what people should do if they are caught outside.

2. Inform your community about the different National Weather Service announcements — *winter storm watch, winter storm warning, ice storm warning, heavy snow warning, blizzard warning, severe blizzard warning, high wind warning*



3. Conduct a series of presentations at the beginning of winter storm season. Include information on alternative heat sources and home insulation.

4. Interview local physicians about the dangers of hypothermia and other winter health conditions.

5. Produce a series of announcements on what to do if you are stuck in your car during a blizzard.

DID YOU KNOW...

- The leading cause of death during winter storms is from automobile or other transportation accidents. Exhaustion or heart attacks caused by overexertion are the second most likely cause of winter storm-related deaths.

- Fire during winter storms presents a great danger because water supplies may freeze and it may be difficult for fire fighting equipment to get to the fire.

- Ice storms can break power lines, causing widespread blackouts.

- Elderly people account for the largest percentage of hypothermia victims. Many older Americans literally “freeze to death” in their own homes after being exposed to dangerously cold indoor temperatures, or are asphyxiated because of improper use of fuels such as charcoal briquettes, which produce carbon monoxide.

- In March 1993, the Blizzard of '93 dumped record amounts of snow on an area that stretched from Alabama to New England. The storm left more than 170 people dead and caused hundreds of thousands of people to be without power for several days. Total damages were estimated at upward of $800 million.

HOW THE PUBLIC CAN HELP AFTER A DISASTER

When disaster strikes, people everywhere want to help those in need. To ensure that this compassion and generosity are put to good use, the media can highlight these facts:

- ▶ Financial aid is an immediate need of disaster victims. Financial contributions should be made through a recognized voluntary organization to help ensure that contributions are put to their intended use.
- ▶ Before donating food or clothing, wait for instructions from local officials. Immediately after a disaster, relief workers usually don’t have the time or facilities to setup distribution channels, and too often these items go to waste.
- ▶ Volunteers should go through a recognized voluntary agency such as the American Red Cross or Salvation Army. They know what is needed and are prepared to deal with the need. Local emergency services officials also coordinate volunteer efforts for helping in disasters.
- ▶ Organizations and community groups wishing to donate items should first contact local officials, the American Red Cross, or Salvation Army to find out what is needed and where to send it. Be prepared to deliver the items to one place, tell officials when you’ll be there, and provide for transportation, driver, and unloading.



The Master Teacher The
Imperial Grand Potentate, Noble: Rev. Dr. Malachi Z. York 33°/720°.
Defines Success"

QUESTION: What is Success?

ANSWER: Success is the progressive realization of a worthy idea. If you have a goal and you are working towards that goal, then you're on the path to success.

"A 30 Day Program "

All One Has to Do Is Apply The Method To Their Life And Your Life Will Never Be The Same Again!

~~~~~~``
SAY This for 30 days straight

I plant positive thoughts in my mind

I am practicing this for 30 days straight.

I am doing a 30 day practical method.

I am applying this method for 30 days straight.

This is going to be easy.

This will alter my life for the better and for ever.

I think and I relax.

I am writing down my want list on a card.

I am imagining and concentrating on my want list for 30 days straight and 3 times a day.

I am looking at this want list for 30 days straight and 3 times a day.

SAY This for 30 days straight

I want (state wish or want)____?

This is my reality the moment I think about it

____
~~~~~~

I create positive habits.

I always think positive.

I take control of my mind.

My mind will only think of what I allow it to think.

I Do more.

I think more.
I give myself more then I ever did before.

I don't worry about how I am going to achieve my goals.

All The answers will come to me.

I think of all the reasons I can be successful.

I write out the persons that I love to become

I am like ____
I can not live no other way after this right knowledge.

I my whole life to live in a superior way.

I am super-strong mentally.

I am a super-strong physical .

I am super-strong 9 Ethereally

I am cured of all mental diseases, namely ignorance.

I am a Supreme Being of the pure radiant Green Light.

I change my mental environment and I change my life.

I am a superior thinker.

I am bred to be superior in mind.

I am programmed by my superior mental environment

I am educated In a Superior mental environment.

Named Nuwaubu/Wu-Nuwaubu

I am physically and spiritually free.

I am a supreme being.

I am goal-minded.

I achieve anything I want to achieve in my life.

I am financially independent.

I know how to use my superior knowledge to become super-successful.

I get everything I want in my life.

I have the super-magic touch.

Anything I touch turns Into success.

I continue to become more & more successful in my life.

I always think big and successful.

I am a super-successful supreme being.

I am progressive In the realization of my worthy ideas.

I do everything in any field I choose to.
I am successful in anything I choose to do, because that's what I want to do.

I propagate the 'Message of the Most High'.

I set goals.

I am going to ....(state action)____.

I am going to ....(state action)____.

I am going to ....(state action) _______________________________________

(set date for deadline).

____

I will succeed.

I will reach all of the goals that I set for myself.

I set out to achieve all of them.

I want to become a "Supreme Being "

I am a "Supreme Being "

Success is anybody that's doing a pre-determined job.

I will (state action)____.

I am (Determine)____.

I posses a burning desire to be what I think about all the time.

I create all my opportunities in my life.

I know where I am going.
I have complete plans.
I know my directions.
I know my destination.
I know where I am going all the time.
I have the superior guidance.

I am a superior sales man.
I have no limits in ALL

I always achieve.
I sell anything, because I want to.
I sell everything.
I believe in what I am selling.

I don't hurt anybody.

I don't displease anybody.

I make everything I do marketable to all.

I am superior competitor.
I am a super-winner.
I super-succeed in my life.
I really overstand this principle completely.

My life is altered for super-success

The Bes things are always attracted to me.

Everything I want, I get.

From now on, I won't have any problems.

I won't have any worries.

I don't have any doubt, nor any fears in my life.

~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~
"THIS IS THE KEY!!"
SAY This for 30 days straight

I am what I think about all the time.

(say what you want to think about All the time)

<<<here>>>

____ _______

Everything will come if I only be patient and wait for it.

I am completing my purpose.

I alter my life for The Bes.

I alter my attitude to a superior state of mind.

I am a superior mind.

I care enough for super results.

I will achieve it.

I achieve all

I am super-rich.
I am super wealthy
I am super-healthy.
I am super-intelligent.
I am super- knowledgeable on all subjects on earth and the whole boundless universe.
~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~

Anything I think in my mind, I am it.
Anything I feel in my heart I am it.

My life is what my thoughts make it.

I posses positive, crystal clear and vivid pictures in my mind of what I want to do.

I posses positive, crystal clear and vivid pictures in my mind of what I want to become

I know my goals and purposes In my life.

I have set a target before me.

I am prepared.

I practice.

I am talented.

I am skillful.

I have the complete idea.

I achieve all of my goals when I think about them.

I am helping to save positive agreeable Nubian people

who don't believe in themselves.

Possible Nine-mind revision:
(I am helping to save positive agreeable Nubian people who don't KNOW themselves.)

I totally believe in myself.

Possible Nine-mind revision:
(I totally trust in my abilities within myself.)

I will instill this superior mind-concept in all of my children.

I am the greatest of the great.

My children are the greatest of the great.

I am a chosen child of Anu.

I have the superior-faith

I have super-determination.

I will succeed.

I succeed

I know all things are possible to me.

I think in only positive terms.
I get only positive things sent to me.

I believe and I succeed.

Possible Nine-mind revision:
(I am conscious of my ability to achieve success)

I know and I succeed.

I have no doubt in myself.

I attempt all things I want & wish for.

I make everything happen for me in my life

I become what I think about.

I think about positive, concrete, worth-while goals and ideas.

I will always become what I think about.

I think about all the positive things I want to become in my life.

I become what I think about.

Anything I plant in my mind I become it.

I plant super-success in my mind and everything I want and wish for in my life becomes reality.

I concrete on only worth-while goals.

I always value my mind, my body, my soul and my spirit.

I don't take my mind, my body, my soul and my spirit for granted.

I plan my goals in my mind.

I am making the most important decision in my life.

I plan all my goals in my mind and I achieve them.

I picture myself as a Supreme Being.

I see myself as having already achieving all goals in my life.

I am outstanding in everybody's eyes.

I am a great, supreme being.

I find everything I need in my life to help all others.

I am super-rich in personality, fame and respect.

I plant any thought In my mind and I easily achieve it.

I care and work towards achieving my goals in life and everything

I plant in my mind becomes a reality.

That is Universal law.

This always works, because this is Universal law.

I am where I want to be.

I am guided by my Inner Being

I think, I think and I think

I am learnt in this superior science.

I overstand this Supreme science.

I know this supreme science works with the forces of nature

put your want and wish in the lines

I am ________________________.

I believe in____________________________.

Possible Nine-mind revision:
(I focus on) ____________________________.

I have faith in______________________________.

Possible Nine-mind revision:
(I strive towards) ______________________________.

I am in control of____________________________.

I do the job that I love doing.

I only do super-great things in my life

I am A Supreme Being of the pure radiant GREEN LIGHT

2,100 ASANAS

THE COMPLETE YOGA POSES



DANIEL LACERDA

FOUNDER OF MR. YOGA, INC.

2,100 ASANAS

The Complete Yoga Poses

Daniel Lacerda

FOUNDER OF MR. YOGA, INC.

BLACK DOG
& LEVENTHAL
PUBLISHERS
NEW YORK



Begin Reading

Table of Contents

Newsletters

Copyright Page

In accordance with the U.S. Copyright Act of 1976, the scanning, uploading, and electronic sharing of any part of this book without the permission of the publisher constitute unlawful piracy and theft of the author’s intellectual property. If you would like to use material from the book (other than for review purposes), prior written permission must be obtained by contacting the publisher at permissions@hbgusa.com. Thank you for your support of the author’s rights.

Opening Prayer

Om

For the peaceful resolution
From the illusionary nature of dualistic existence,
I ground myself before the lotus feet of the gurus,
Who remind me that the light I search for is within me
Bringing stillness to the whirling of the cascading ego mind
I behold the awakened joy of my own Soul
Realizing the truth of pure radiance
That we are in fact the same
To the self-awakened gurus of the past, present, and future,
I salute

Om

Daniel Lacerda, Mr. Yoga

A MESSAGE FROM MR. YOGA

The ultimate goal of yoga is self-realization. You do not need to go to the mountaintop to find it or pay a teacher to show you the way. There are currencies that we exchange with one another that are much more valuable than money: kindness, selflessness, being one part of the greater good. Nor do you need to look outside yourself. If you have an open mind, a sincere desire to learn and to apply that knowledge on a daily basis, and the commitment to follow through on what you’ve begun, you can achieve self-realization.

Self-realization is the knowledge that we sentient beings are interconnected and that what we think, say, and do affects those around us. Burdened by the pressures and demands that exist outside of ourselves—of our jobs, bills, desire for status and for material possessions—we forget this. Self-realization is the ability to achieve freedom from these demands and to know that true happiness comes from fulfilling our own potential and from lifting up those around us without the thought of self-gain. Dedicating yourself to the regular practice of yoga can help bring you back to this place.

Yoga is, indeed, an excellent form of exercise that carries with it many immediate and long-term physical benefits from improved flexibility to stronger muscles and bones. However, yoga is not just about moving through the poses. Mindfulness plays an essential part in any dedicated yoga practice. If performed properly, yoga quiets the mind of all distracting thoughts from the outside world (*chittavritti*, meaning mind chatter), bringing you to a place of peace within. In turn, being mindful of your thoughts will allow you to be mindful of, and truly connected with, your body, thus completing the cycle of mental and physical health that will allow you to enjoy all the wonderful things that life has to offer.

For the past eleven years, I have dedicated my life to yoga, teaching an average of twenty-five classes seven days a week. I have done this to make a difference in the lives of my students. Now it’s my pleasure to share this passion and dedication with you.

Namaste!

A HISTORY OF YOGA

Most of us know yoga as a set of poses performed in a gym or yoga studio setting. The majority of yoga styles practiced today were invented in the last quarter of the 20th century and are either a far cry from yoga's roots or have no authentic lineage.

If we really want to examine the roots of yoga, we need to go back to the Harrapan culture, dating back 3,500 years, when yoga was a meditative practice. According to some, around 1500 BCE, Harrapan culture was diminished due to Aryan invasion. Barbarians from Normandy introduced the caste system and enforced a set of religious rituals that involved blood sacrifice practices. Along with these religious practices came sacred scriptures called the Vedas, a large body of spiritual texts originating in India. The word "yoga" was first mentioned in the oldest of the Vedas, *Rig Veda*. It referred to the concept of discipline.

Fast forward to 800 BCE. The Upanishads, a collection of texts that contain some of the earliest concepts of Hinduism, prescribed the method of achieving enlightenment by studying under a teacher and dedicating one's life to a yoga practice. The Upanishads outlined two paths to enlightenment: Karma Yoga (selfless dedication to the service of others) and Jnana Yoga (intense study of spiritual writings). Around the 3rd century BCE, the *Maitrayaniya Upanishad* prescribed a six-step process to enlightenment, which included mastering *pranayama* (breath control), *pratyaharia* (sense withdrawal), *dhyana* (meditation), *dharana* (one-pointed concentration), *tarka* (self-reflection), and *samadhi* (absolute absorption) in order to unite the Atman (individual's spirit) and Brahman (universal spirit or source of creation). The sacred syllable *om* appeared in this particular Upanishad as a symbol of union between mind and breath.

At around the same time that *Maitrayaniya Upanishad* was introduced, *Bhagavad Gita* gained prominence. This scripture combined and mythological tales that later made their way into a celebrated collection of tales, *Mahabharata*. Three methods of devotion were outlined in *Bhagavad Gita*: Karma Yoga, Jnana Yoga, and Bhakti Yoga (devotion).

Compiled around 400 CE by Patanjali, *The Yoga Sutras* introduced the eight-fold path to yoga practice, which is considered to be the classical yoga manual and the foundation of many of today's yoga practices, particularly Ashtanga Yoga. We will hear more about this eight-fold path in The Eight Limbs of Yoga (here), which include *yama* (self-restraint) *niyama* (self-purification by self-restraint and discipline), *asana* (seat or posture), *pranayama* (control of breath), *pratyahara* (sense withdrawal), *dharana* (one-pointed concentration), *dhyana* (meditation), and *samadhi* (total absorption).

Around the 4th century CE, Tantra Yoga emerged. This new form of yoga celebrated the physical body as a vehicle to enlightenment. The philosophy behind Tantra Yoga can be summarized by the idea of uniting all the dualities within a human body (e.g., male and female; good and evil), which gave

Tantra a very sexual reputation. This is, however, a common misunderstanding, since Tantra practices extend far beyond sexuality.

Hatha Yoga was introduced in the 10th century CE. It combined the physicality and conscious intent of using bodily postures, or *asana* practice, and *pranayama* breath control for the goal of self-realization.

In 14th century CE, the Yoga Upanishads were introduced. One of these sacred texts, *Tejo Bindu Upanishad*, added seven more important parts of yoga practice on top of Patanjali's eight. They were as follows: *mula bandha* (root lock), balance, undisturbed vision, *tyaga* (abandonment), *mauua* (quiet), *desha* (space), and *kala* (time).

It was not until the 20th century that yoga gained any kind of popularity in Western Europe and North America. Swami Sivananda Saraswati was one of the first yogis to travel outside of India to spread the teachings of yoga to the West. He established yoga centers in North America at the time Swami Satchidananda also delivered an opening speech at the Woodstock Festival in 1969. However, T. Krishnamacharya is arguably the father of the yoga practice with which Westerners are familiar today. In the 1930s, he began teaching his students the Mysore vigorous sequences of yoga poses that emphasize strength and athletic ability. Students were only allowed to learn the next and more challenging pose after they had grasped the previous one. His three most prominent and influential students are Pattabhi Jois, Iyengar, and Indra Devi. Pattabhi Jois established Ashtanga yoga. It is one of the most popular types of yoga practiced in the West. Iyengar became successful by creating his own sequences of yoga poses, which were characterized by a focus on the alignment of the body and the use of various props. Indra Devi is considered the first famous yogini (female yoga master). Krishnamacharya also educated his son Desikachar in yoga. An engineer by training, Desikachar saw great value in studying yoga only when he was already a college graduate. Desikachar developed Vinyoga, which is a more therapeutic and less intense approach to physical practice, as compared to Ashtanga.

The 21st century presents us with an endless variety of yoga "styles" or "brands," such as Bikram Yoga, Power Yoga, Kundalini Yoga, and countless more. It is important to be open-minded, try as many styles and approaches as possible, and figure out what gives you the best results in terms of achieving both your physical and spiritual goals. There is no wrong way to achieve self-realization. Just make sure you are mindful, patient, practical, and consistent in your practice.

A Note on the Naming of Poses:

One of the ways that the distance from yoga's roots expresses itself in Western culture is in the naming of the poses. "Seated forward bend," "eagle pose," and "dolphin pose," for example, are all imprecise translations of the original Sanskrit name. *Garudasana*, for example, is widely known as eagle pose, but traditionally this pose was named in dedication to Garuda, who is a Hindu deity, portrayed as half-man and half-eagle. He is the charioteer of Lord Vishnu, who is part of the Holy Trinity in Hinduism. Knowing this history adds a whole new dimension to our understanding of the significance, philosophical depth, and essence of the pose, and can in turn enrich our practice.

The poses throughout this book are identified by both their English and Sanskrit names. The English name is a direct translation of the Sanskrit, which sometimes differs from the more common Western name, also provided in the notes. For a literal translation of each part of the Sanskrit name, you may consult the glossary at the back of the book. The intention is to provide you with as much information about the name of the pose and its history as possible, so no matter what style of yoga you practice, you will have the most complete understanding of the names of the poses.

THE EIGHT LIMBS OF YOGA

The Yoga Sutras, also known as *The Eight Limbs (Ashtanga) of Raja (King) Yoga*, was the first fully developed and recorded system of yoga. Created by Patanjali around 400 CE, this system influences much of the yoga that is practiced today. Although most of the sutras were originally focused on mindfulness, the yoga practiced in the West today seems to focus more on the body. Somewhere along the way, it seems, we began to practice the movement of yoga in isolation from its original philosophies.

For those interested in truly integrating the mindfulness of yoga with its movement, I recommend that you read *The Eight Limbs of Yoga* in its entirety and digest it very slowly. Take time to reflect on it piece by piece so you can implement it into both your practice and your daily life. Wisdom is in the doing. The following, however, is a useful summary of *The Eight Limbs of Yoga*, which will introduce you to the basic concepts of the philosophy. A deep understanding of yoga philosophy and history will greatly enhance the benefits of your practice and put you on the path to mindfulness and self-realization.

There is a wonderful lesson in Buddhism that applies here:

Once, a very old king went to see an old hermit who lived in a bird's nest in the top of a tree. He asked the hermit, "What is the most important Buddhist teaching?" The hermit answered, "Do no evil do only good. Purify your heart." The king expected to hear a long and detailed explanation. He protested, "Even a five-year-old child can understand that!" "Yes," replied the wise sage, "but even an eighty-year-old man cannot do it."

Your biggest obstacle to self-realization is you. As it says in the *Bhagavad Gita*, "The mind is restless and hard to control, but it can be trained by constant practice (*abhyasa*) and freedom from desire (*vairagya*). A man who cannot control his mind will find it difficult to attain this divine communion; but the self-controlled man can attain it if he tries hard and directs his energy by the right means."

Pantanjali's *Eight Limbs of Yoga* will help you form the necessary groundwork to get on the right track, but you must decide to confront your problems at their roots. Reading and intellectualizing is not enough. If you want to reap the full benefits of the yoga experience, implement the Eight Limbs into every aspect of your life. You must live it, breathe it, and engage this planet and its inhabitants with the lessons below.

The first and second limbs, ***Yama*** and ***Niyama***, form your foundation. Here, awareness and realization is established. *Yama* and *Niyama* lay the footing for everything to come. A serious student should be mindful of every limb, as each of these limbs need constant reflection. As you commit yourself to their study and practice, your depth of understanding for each limb will get deeper over time. In our world that perpetuates instant gratification, many people will take shortcuts and go straight to the yoga poses. Others will go straight to meditation and neglect physical health. I highly recommend starting with Pantanjali’s first two limbs. Your practice will be at its deepest and most fulfilling if the first two limbs are practiced at a high level. If the first two limbs are not practiced at a proficient level, the rest of the limbs will be performed at a more superficial and less effective level.

FIRST LIMB **Yama** (Self-Restraint)

The focus of the first limb is on being an ethical and moral person, and on improving your relationship with the outer world. These values are as important today as they were centuries ago. The *Yamas*, as they are referred to, are not meant to be a moral straitjacket, but instead are meant to help develop a greater awareness of one’s place in the world. It is not a coincidence that this is the first limb of the practice. When taking steps to transform our inner world, our outer world becomes a total reflection of this effort. There are five *Yamas*:

1. *Ahimsa:* **Non-violence**
   Replace harmful thoughts, speech, and actions with that of loving kindness toward yourself and others.
2. *Satya:* **Truth to be expressed in thought, word, and action**
   Be honest in your thoughts, words, and actions toward yourself and others.
3. *Asteya:* **Non-stealing and non-covetousness**
   Curb desires for things that are not your own. Share the beauty of your thoughts, speech, actions, and material belongings to uplift others instead of stealing and hoarding them for yourself.
4. *Brahmacharya:* **Abstinence from sexual intercourse when not married, practicing monogamy and not having sexual thoughts about another person who is not your spouse**
   It is believed that a life built on celibacy and spiritual studies done by free will increases energy and zest for life. Celibacy may sound like an unrealistic goal today, but it may help to remember that brahmacharya is also about monogamy. When brahmacharya is fully realized in marriage, the sex lives of both partners improve because the level of trust and devotion deepens their connection. It is important that the sexual activity is an expression based on the highest level of mutual respect, love, selflessness, and wisdom.
5. *Aparigraha:* **Non-possessiveness or non-greediness**
   Replace the habit of hoarding with sharing. Do not take without giving back. If you want something, work for it. This builds appreciation for what you have. This will help minimize the insatiable desire to constantly consume. An appetite that is not wisely disciplined leads to personal ill health, financial debt or poor credit, and destruction of the planet’s natural resources. The Greek god Apollo’s motto, “Nothing in excess. All things in moderation,” is a great way to describe *aparigraha*.

SECOND LIMB **Niyama** (Self-Purification by Self-Restraint and Discipline)

The second limb helps refine your spiritual path. Discipline and self-restraint lead to a more orderly and productive life. From the perspective of ancient yoga texts, life is extremely short and we need to make the most of it while we can. This limb gives us guidance. There are five Niyamas:

1. *Shaucha:* **Purity of body and mind**
   When you develop *shaucha* (cleanliness), unwholesome thoughts that lead to foul speech and a sick body are cleared. Purity starts with your mind. Speech and action follow. So, the second limb directs you to make a habit of consuming both food and mental stimuli that support well-being for yourself and the environment (humanity and the planet). This will allow destructive habits (hatred, greed, and delusion) to dissolve.
2. *Santosha:* **Contentment with what one has**
   When you achieve *santosha* (contentment), bonds to the material world are broken and authentic peace and happiness are established within. A lack of contentment is often based on a distorted perception of what one has versus what others have. You advance on the path to self-realization when you can be content with your lot, whether you sit on a throne of dirt or gold.
3. *Tapas:* **Self-discipline, sometimes associated with austerity, and being able to conquer the body and mind through mental control**
   Tapas literally means “heat” or “glow.” This refers to a burning desire to accomplish one’s goal despite what obstacles may appear. The commitment to achieving a goal, no matter how challenging it becomes, builds character. However, note that the highest level of *tapas* is to complete one’s goal without a selfish motivation. When *tapas* is attained, laziness is overcome and willpower is developed for future use.
4. *Svadhyaya:* **Self-study that leads to introspection and a greater awakening of the soul and the source of creation; traditionally studied through Vedic scriptures**
   Svadhyaya (self-study) leads to a greater awakening of your true potential, the root of one’s place in this world and how to live in harmony with the Earth and all its inhabitants.
5. *Ishvara pranidhana:* **The surrender to God**
   When you accept that all things come from a higher power, pride and egocentric behavior are turned into humility and devotion. This strengthens your practice of all the limbs leading up to *samadhi* (the eighth limb).

Asana and *Pranayama* are the third and fourth limbs, and they relate to health and longevity, which allow us more time to achieve the ultimate goal of yoga, Self-Realization or Enlightenment. The third and fourth limbs are important, as they prepare the body for meditation, which will be the key to calming your mind and discovering your true potential.

THIRD LIMB **Asana** (Seat or Posture)

Here is a question: If Gandhi is one of the greatest yogis of our time, does that mean he can touch his toes or bring his foot behind his head? The answer is that it doesn’t matter. Gandhi’s ability to perform the *asanas* had very little to do with what he contributed to the world as a great yogi. The same applies to you. The practice of *asanas* is as much about training the mind as it is the body. How you approach your *asana* practice is often a reflection of how you approach life. Do you keep a sense of peace and calm when a challenge presents itself? Do you break down the impossible into smaller tasks, making the whole possible through commitment to and reflection on each of the parts? Do you overcome self-perceived limitations on your own or do you accept support from others?

Your practice of yoga poses should be characterized by two components: steadiness (*sthira*) and ease (*sukha*). Concentrating on the sound of your breath (*ujjayi*, the most commonly practiced breathing technique in yoga, see here), can provide the steadiness. If you lose your breath, it is most likely because you are pushing too hard; ease off the pose and let the pose cater to the breath.

There is no such thing as a perfect pose; let the poses come like the steps of a dance. Just like in dance, when we focus too much on the mechanics, we let go of the ability to enjoy the music. While the mechanics of alignment are important to prevent injury, never forget the final goal. Feel the music of life flow through you as you do each pose and your body will learn the moves naturally. There are more than enough postures to keep you busy for the rest of your life, so allow yourself to let go of ambition and enjoy the journey. Incorporating a combination of forward bends, backbends, twists, and inversions in your yoga session is optimal for health.

Remember, too, that *asanas* help prepare the mind and body for meditation, relieving tension and protecting the body from disturbances by purifying the nervous system.

FOURTH LIMB **Pranayama** (Control of Breath)

The English word “spirit” comes from the Latin *spiritus*, meaning “breath.”

The breath and the mind are interconnected. Deep, rhythmic, and fluid breathing will energize yet calm the mind and body. Rapid, irregular, and strained breathing produces a chaotic and disturbed mind. A calm mind will give you the mental space to make better decisions and a life in which you take control instead of feeling like a victim of circumstances.

Breathing properly is fundamental to our very existence. Your brain feeds on oxygenated blood, which is supplied with every inhalation. If you are unable to draw oxygen into your body, you will become brain dead after a few minutes. On the other hand, proper exhaling helps expel carbon dioxide. If your ability to exhale were impaired, you would most likely die due to the toxic buildup of carbon dioxide and poison. Stress tends to negatively affect breathing patterns, which contributes to a chain of effects that cause wear and tear on both your body’s nervous and immune systems. In fact, 90 percent of illness is stress-related and, for this reason, attention to breathing properly is, indeed, a matter of life and death.

FIFTH LIMB **Pratyahara** (Sense Withdrawal)

Our perception of reality is predominantly influenced by our sensory experience—what we see, feel, hear, touch, and taste. *Pratyahara* refers to the withdrawal of the senses from external objects and our modern-day need for constant gratification from sensory stimuli. Our minds are constantly being pulled outward to evaluate all the information the senses bring in. Evaluation involves categorizing what has been perceived; often, we hold on to what we believe is desirable, push away what we believe is undesirable, and ignore what we believe to be neutral. *Pratyahara* gives our minds a moment to rest and teaches us to be free of the grasping and clinging to the things we enjoy and avoiding the undesirable.

When you throw a pebble into a pond, your reflection becomes distorted by the resulting ripples. Your mind works in very much the same way: Every thought creates a ripple that distorts the ability to see your true self clearly. Constantly disrupted by these ripples, you begin to believe that the distorted reflection is who you really are. Practicing *pratyahar*a calms the mind, allowing you to see yourself clearly.

SIXTH LIMB **Dharana** (One-Pointed Concentration)

Asanas, *pranayamas*, and *pratyahara* help prepare us for meditation.

When the mind moves from experiencing random scattered thoughts to single one-pointed concentration, it can then find complete absorption in the present moment. By practicing one-pointed concentration, we clear the mind of all distracting thoughts. This can be achieved by focusing on your breath, counting, reciting mantras, or observing a candle flame or an image. Because we are constantly entangled in reliving past memories or living in anticipation of what is to come, it is very seldom that we live in the present moment. It is even less common to be mindful of the present moment with a calm and focused mind. However, this is crucial when trying to achieve self-realization. The power is in the now!

SEVENTH LIMB **Dhyana** (Meditation)

Just as there are many different types of yoga poses, there are many ways of meditating. Meditation is a form of inner contemplation that allows you to access a state of mind that has transcended the ego. This is a state of pure awareness of the present moment that is free of judgment. All meditation leads to a state of full awareness that does not discriminate or categorize things in a dualistic manner, which is to say the perception of what is good versus what is bad, beautiful versus ugly, pleasant versus unpleasant, etc. When we examine reasons behind such judgments, we find many of these beliefs are based on learned behavior, may vary from one culture to another, and have no fixed or concrete reality. With consistent reflection and an open mind, we can correct our biased perceptions. You will develop that part of you called “the Observer.” Once grounded in a regular seated mediation, it is important to take it into a moving mediation throughout your daily life.

EIGHTH LIMB **Samadhi** (Total Absorption)

Samadhi occurs when the analytical mind becomes absent and at one with the object of meditation. The object of meditation can be whatever you are focusing on in your meditation that is used to achieve one-pointed concentration. The word *om*, a deity, or a candle flame are all examples of objects of meditation. Total absorption involves the feeling of oneness with all creation, dissolving all lines between the act of meditation and the object being meditated upon.

It is the absorption in the present moment (*amanaska*) where dualistic thinking is transcended. Many are mistaken in believing *samadhi* is the final goal of yoga. It is but a temporary state of mind that we enter based on the conditions that we have nurtured to support it.

It’s useful to remember that every moment in your life gives you an opportunity to practice the eight limbs. Learn at your own pace, but stay focused, be consistent, and enjoy the journey!

THE *UJJAYI* BREATH

Breath is an essential staple of every yoga practice. By focusing on the breath, a yogi is able to stay in the present moment. Since the breath is neutral, a yogi neither seeks to avoid it, nor is she eager to chase it. Proper and continuous breath helps clear the mind of distracting thoughts and to remain in the present moment with one-pointed concentration.

Deep, conscious breathing also slows down the heartbeat and activates the parasympathetic nervous response, which soothes the nervous system, and allows the muscles to relax into the stretches and stay strong in the strength-based yoga poses. Maintaining deep, fluid breathing will help transform your yoga practice into a moving meditation.

Ujjayi pranayama is one of the most commonly used breathing techniques in every yoga practice. *Ujjayi* means “victorious” in Sanskrit. When practicing this breathing technique, a yogi creates what can be described as the “ocean sound” in the back of the throat by gently squeezing the glottis (the opening between the vocal cords in the throat). You’re aiming to create a breathy and whispery sound at the back of the throat. The sound is often compared to the sound Darth Vader makes when breathing! In order to practice *ujjayi* breath, first sit in a comfortable position. Inhale through the nose and, as you exhale, imagine you are trying to fog up a glass. Try to inhale with the same sound. Once you feel like you have an understanding of the *ujjayi* breath technique, seal your lips in order to prevent the throat from drying out. (A dry throat usually leads to coughing and drinking water, which distracts you from your yoga practice.) Inhale and exhale through the nose, while still maintaining the sensation in the throat of trying to fog up a glass.

Using breath to facilitate poses:

- Keep your breath deep and rhythmic.
- If your breathing becomes restricted or choppy, there is a good chance that you are pushing yourself unnecessarily. In this case, you should ease off the pose and return to a place that promotes smooth and fluid breathing.
- The body lifts up and lengthens on the inhale. For example, lift up from a forward bend into a mountain pose on the inhale, using the inhale to lengthen the limbs of the body and the spine. Use the exhales to go deeper into the pose.

THE *BANDHAS*

Bandha means "lock." *Bandhas* were traditionally believed to regulate the flow of life energy (*prana*) throughout the body. In contemporary yoga practice, *bandhas* serve a more practical purpose. They are contractions, or "body locks," that you can implement to help correct your posture or aid you in proper alignment.

There are three major *bandhas*: *mula bandha*, *uddiyana bandha,* and *jalandhara bandha*. The combination of all three *bandhas* is called *maha bandha*, or "the great lock."

Mula bandha refers to the triggering of the perineum muscle that is located between the genitals and the anus. *Mula* means "root," therefore *mula bandha* translates as "root lock." When this *bandha* is engaged, you will feel a slight pull on the inside of the thighs, similar to what you feel when trying to stop the flow of urine.

Uddiyana bandha means "flying/moving up." To engage this *bandha*, place three fingers below the belly button and pull your lower abdominal muscles slightly in and up. This will cause your pelvis to tilt forward slightly with an upward action, protecting the lower back and strengthening the lower abdominals.

Mula and *uddiyana bandhas* should be engaged throughout the yoga practice. Together they help correct the posture and create proper alignment, which will reduce the chance of injury.

Jalandara bandha is a chin lock. To practice this lock, bring the chin toward the clavicle bone while keeping your spine upright and moving your shoulder blades down the back. This *bandha* is rarely used, but can be found when engaged in *Dandasana*, Staff Pose.

THE *DRISHTIS*

Drishtis are the meditation gazing points to focus on while performing the poses. They are designed to aid with proper alignment, as well as to strengthen the focus on the present moment. While practicing we tend to look around, compare ourselves to others in the room, or look at the clock. This takes away from the focus on the internal aspects of the practice. *Drishtis* are meant help you look inward.

They are as follows:

1. *Nasagrai* or *Nasagre* (nose)
2. *Bhrumadhye* or *Ajna Chakra* (third eye, between the eyebrows)
3. *Nabhi, Nabhicakre,* or *Nabi Chakra* (belly button)
4. *Hastagrai* or *Hastagre* (hands)
5. *Padayoragrai* or *Padayoragre* (toes/feet)
6. *Parshva Drishti* (to the right)
7. *Parshva Drishti* (to the left)
8. *Angushtamadhye* or *Angushta Ma Dyai* (thumbs)
9. *Urdhva* or *Antara Drishti* (up to the sky)

Drishtis can be complicated to grasp at first. However, there are general guidelines for the gaze. It comes down to letting your eyes follow the direction of the stretch. For example, in backbends we look at our third eye in order to let the head roll back and deepen the backbend. Similarly, in seated forward bends, such as *Paschimottanasana* (Western Intense Stretch Pose), we gaze at the toes to lengthen the spine. The purpose of *drishtis* is not for you to become cross-eyed; they are a way to softly focus without intensely staring.

HOW TO APPROACH YOGA POSES

Yoga poses provide much more than a physical workout. Performing them builds character. Facing your fears and challenges that extend beyond your comfort zone with a sense of peace, calmness, and psychological equanimity will help you overcome your self-perceived limitations.

I find it helpful to think of every yoga pose as a prayer you do with your body. While you perform the pose, focus on what is good in your life with a feeling of gratitude. Being at one with your mind and body in this place of grace helps you transcend the ego, which helps you get closer to the ultimate goal of yoga, which is enlightenment.

Universal Alignment Cues

- Engage *mula* and *uddhiyana bandhas*.
- Engage the *ujjayi* breath and maintain deep conscious breathing all throughout the yoga session. If your breath is suffering, then back off a bit.
- Keep the chest open and shoulder blades down the back.
- Lengthen the body and limbs on the inhale, deepen the pose on the exhale.
- Avoid jerky and uncontrolled movements during the poses that are based on flexibility.
- Square your hips.
- Don’t let your knee go past your ankle when doing any kind of lunge.
- In Plank and the majority of arm balances, shoulders should be just over the fingertips.
- Even if you are intermediate or advanced, start with the beginner modifications in order to ensure proper form and get the blood into the targeted muscle as a warm-up.

Universal Flexibility Cues

- Hold flexibility for a minimum of 30 to 90 seconds.
- Stretch to the edge of comfort and stimulation without straining.
- Don’t overstretch to the point of pain; your muscles will tighten up in order to protect themselves and your flexibility will decrease.

RELAXATION AND MEDITATION

Relaxation

Corpse Pose (Shavasana)

(Shava in Sanskrit means "corpse")



After an intensive *asana* practice, the final resting yoga pose, Corpse Pose or *Shavasana,* helps deepen the connection between our physical body and mind and helps prepare both for meditation. *Shavasana* can be thought of as an awakening, giving us the time to contemplate the question "If I died today, would I be fully satisfied and content with what I accomplished in this lifetime?" Have you lived up to your full potential? Have you fully acknowledged the people in your life that are of great importance to you? Would you be able to pass on with no regrets?

1. Lie down on your back, shoulder blades tucked in, legs apart. Relax your arms and let your palms face the ceiling. Let your fingers naturally curl. Relax your body into a neutral, comfortable position.
2. Close your eyes. Let your jaw naturally separate as you relax your whole body as if it were sinking down to the floor. Release all tension from your body.
3. Without letting the mind wander, concentrate on your breathing to reach a deep state of conscious relaxation, both physically and mentally.

Meditation

Easy Pose (Sukhasana), Seated Lotus Pose (Padmasana)

1. Start in Staff Pose (*Dandasana*), both legs extended in front of you. Grab onto your sitting bones and pull back the flesh to lengthen your legs and spine.
2. Sit in a cross-legged position that is comfortable. You can sit on a chair, in Easy Pose (*Sukhasana*), in Half Lotus (*Ardha Padmasana*), or Full Lotus (*Padmasana*). Press your sitting bones into the ground as you extend up through the spine. Lift the crown of your head up to the sky. Place one hand on top of the other and have the thumbs lightly touch. Gently close your eyes. Perform the 1:4:2 Healing Breath Zen Meditation as follows:

   Inhale for a count of 4 and feel your lower abdomen expand as you push it out. Hold and retain the air in your lungs for the count of 16. Exhale for a count of 8 as you squeeze the belly button back to the spine. Visualize the numbers as you count throughout the set. This will help develop what is called "one-pointed concentration." Your breathing must be so fine that it would not ruffle a feather. Each count should be one second long.

   After 10 breath cycles are performed, the exercise is finished. In an authentic yoga practice, the ego may not be permitted to intrude into the process. Don't "perform" the exercises as if you had an appreciative audience. This is your personal journey. Explore and express yourself while you gain the wonderful physical and mental benefits. This breathing technique is called Abdominal Breathing and should be maintained during the entire yoga practice.

A BRIEF SUMMARY OF *CHAKRAS*



7th **Crown Chakra**/Thousand Petal or Spoked Wheel/*Sahasrara Chakra*
Location: just above the crown of the head
Color: encompasses all colors
Mantra Seed Syllable: encompasses all sounds
Element: the ultimate reality of all truth
Number of Petals: 1000 (symbolic for unlimited)
Focus: detachment from ego and illusory nature of the material world, attaining the goal of yoga (self-realization).

6th **Third Eye Chakra/**Rule or Command Wheel/*Ajna Chakra*
Location: in the middle of the forehead, between the eyebrows
Color: indigo
Mantra Seed Syllable: *om*
Element: the universal mind
Number of Petals: 12
Focus: intuition, decision-making, and the surrendering of egocentric intellect in favor of attaining nondualistic wisdom

5th **Throat Chakra**/Especially Pure Wheel/*Vishuddha Chakra*
Location: throat
Color: turquoise or blue
Mantra Seed Syllable: *ham*
Element: ether/space
Number of Petals: 16
Focus: self-expression and communication

4th **Heart Chakra**/Wheel of the Unstruck or Singular Sound/*Anahata Chakra*
Location: within the center of the chest
Color: green
Mantra Seed Syllable: *yam*
Element: air
Number of Petals: 12
Focus: peace, love, and empathy

3rd **Solar Plexus or Navel Chakra/**Wheel of the Jewel City/*Manipura Chakra*
Location: solar plexus
Color: yellow
Mantra Seed Syllable: *ram*
Element: fire
Number of Petals: 10
Focus: power, will, and self-esteem

2nd **Sacral Chakra/**One's Own Self-Based Wheel/*Svadhisthana Chakra*
Location: sacrum
Color: orange
Mantra Seed Syllable: *vam*
Element: water
Number of Petals: 6
Focus: emotions, desires, and creativity

1st **Root Chakra or Root Wheel/***Muladhara Chakra*
Location: base of the spine
Color: crimson
Mantra Seed Syllable: *lam*
Element: earth
Number of Petals: 4
Focus: physical survival, self-preservation, and security

In Sanskrit the word *chakra* can be translated into "wheel" or "turning." In the yogic interpretation, the *chakras* are based on the concept of a vortex and are visually portrayed as a lotus flower.

According to various Eastern yogic spiritual practices such as Hinduism and Tantric Buddhism, *chakras* are described as wheels or rings of energy found in the subtle (non-physical) body; the culmination of the mind, intelligence, and ego, which influences the gross physical body. Within this subtle body there are energy channels called *nadis* that carry the life force or vital energy (*prana*). The main *nadi* that runs through the *chakras* is called the *sushumna* (*brahma*) *nadi*. The *sushumna* joins two other important *nadis* (*ida* and *pingala*) together at the first and seventh *chakras*. The diameter of a singular *nadi* is believed to be no thicker than a thousandth of a hair's width and is located along the spine.

There are various opinions on how many *chakras* there are, but it is generally agreed that *chakras* spin in a "wheel-like" motion to draw in vital energy that creates a balance between the spiritual and physical body.

The earliest known recording of *chakras* dates back to the ancient Vedas (1700 BCE). The most popular *chakra* model used today is based on two Indian texts: *Shat-Cakra-Nirupana*, written by a Bengali yogi named Purnananda Swami in 1577, and the *Padaka-Panchaka*, written in the 10th century.

Chakras are activated in the following ways:
By stretching open the area where the *chakra* is located. For example, the throat *chakra* can be activated in Camel Pose (*Ushtrasana*). The head is rolled back so there is a stretch in the front of the throat.



By applying physical pressure on the area where the *chakra* is located. Throat *chakra*, for example, can be activated in Staff Pose (*Dandasana*). The Chin Lock (*Jaladhara Bandha*) is engaged by bringing the chin to the clavicle bone, therefore applying pressure to the throat area.

By combining the two methods above, throat *chakra* is activated in full version of Inverted Locust Pose (*Viparita Shalabhasana*). The head is rolling back, creating a stretch in the front of the throat. At the same time, the throat area is pressed to the floor, so there is physical pressure on that area.



BENEFITS AND CAUTIONS FOR 8 CONDITIONS

CONDITION

1. Headache & Migraine

Many headaches are caused by tension and stress. In yoga we breathe deeply and relax. The yoga practice stretches the tight muscles in the upper body, releases endorphins (a “feel good” hormone) and relaxes the mind. It helps release tension by increasing blood flow to the muscles, making the nervous system less agitated and reducing a chance of a headache or migraine.

Poses that put weight or pressure on the head and neck should be avoided. If you suffer from migraines, avoid poses that dramatically increase blood flow to the head. If your migraines are severe, avoid practicing yoga poses and lie down in a dark room.

BENEFICIAL POSES

Seated forward bends–Ex. Both Hands to Ankle Head to Knee Pose (*Dwi Hasta Kulpa Janu Shirshasana*) here. Seated forward bends release tension in the hamstrings and lower back and help prevent headaches caused by tension in the legs and lower back.

Seated twists–Ex. Half Root Lord of the Fishes Pose (*Ardha Mula Matsyendrasana*) here. Seated twisting poses can help prevent headaches caused by tension in the upper and lower back.

Hand position of the pose dedicated to Garuda–Ex. Hand Position of the Pose Dedicated to Garuda in Child’s Pose (*Hasta Garudasana in Balasana*) here. Any pose with this hand position helps stretch the upper back and back shoulder heads and can help prevent headaches caused by tension in the muscles of the upper back.

Hand position of Cow Face Pose–Ex. Hand Position of Cow Face Pose in Bound Angle Pose (*Hasta Garudasana in Baddha Konasana*) here. Any pose with this hand position helps stretch the triceps, front shoulder heads, and rotator cuffs and can help prevent headaches caused by tension in the arms and shoulder muscles.

POSES TO APPROACH WITH CAUTION

Inversions–Ex. Peacock Feather Pose (*Picha Mayurasana*) here, Leg Position of One-Legged King Pigeon 1 Version B in Headstand 5 (*Pada Eka Pada Raja Kapotasana 1 B in Shirshasana 5*) here, and Leg Position of the Pose Dedicated to Garuda in Hands Bound Supported Whole Bod Pose (*Pada Garudasana in Baddha Hasta Salamba Sarvangasana*), also known as Shoulderstand here. Avoid any intense inversions that require a lot of strength, as they increase the heart rate and blood flow to the head and may trigger headaches or migraines.

Backbends with feet and head on the floor–Ex. Bridge Pose (*Setu Bandhasana*) here. Avoid poses that put pressure on the head and neck, as they may trigger headaches or migraines.

CONDITION

2. Carpal Tunnel

To help prevent or alleviate carpal tunnel syndrome with yoga, you'll need to practice poses that strengthen and stretch the flexor muscles of the forearm, which are the muscles on the palm side of the forearm. Depending on the severity of your condition, you may want to start with poses that bear less weight on the wrist joint.

BENEFICIAL POSES

Poses that strengthen the wrist without straining it–Ex. Staff Pose (*Dandasana*) here. Stretching and gently strengthening the wrist and muscles of the forearm can help prevent or reduce carpal tunnel syndrome.

Poses with hands in the reverse prayer position–Ex. Hidden Lotus Pose (*Gupta Padmasana*) here and Reverse Prayer Mountain Pose (*Viparita Namaskar Tadasana*) here. These poses help stretch out the wrists, forearms, front shoulder heads, chest, and rotator cuffs. Releasing tension from these areas is helpful because muscles in the upper body are interconnected and carpal tunnel can be caused or worsened by a chain reaction of tense muscles.

Poses that have hands in prayer (Anjali Mudra)–Ex. Revolved Prayer Standing Rising Wind Relieving Pose (*Parivritta Namaskar Stiti Utthita Vayu Muktyasana*) here. Stretching the wrists and forearm muscles can promote blood flow and lessen tension in the area.

Poses with bound hands, palms facing out–Ex. Mountain Pose—Raised Bound Hands (*Tadasana Urdhva Baddha Hastasana*) here These poses help stretch the forearm muscles that are strained and tight in most people who have carpal tunnel syndrome.

POSES TO APPROACH WITH CAUTION

Arm balances with both feet off the floor–Ex. Crane Pose (*Bakasana*) here. These poses have the entire body weight resting on the wrists, which puts a great amount of strain on the carpal tunnel and may drastically worsen its symptoms.

Backbends with hands and feet on the floor–Ex. Upward Bow Pose (*Urdhva Dhanurasana*) here and Wild Thing Pose (*Chamatkarasana*) here. These poses are very hard on the wrists.

Backbends with straight arms–Ex. Upward Facing Dog (*Urdhva Mukha Shvanasana*) here. These poses put strain on the wrist joints because most of the upper body weight rests on the hands.

ADDITIONAL NOTES: There are some options to avoid pressure on the wrist while practicin Upward Facing Dog Pose (*Urdhva Mukha Shvanasana*) here or Downward Facing Dog (*Adho Mukha Shvanasana*) here. If you feel that these poses irritate the carpal tunnel, drop the knees to the floor and rotate the hands 45 degrees to the outside to take the pressure off the nerve. You may also experiment with placing props (rolled-up yoga mat, thin book, or slant board) under the heels of the palms to shift the weight to the knuckles and fingers to reduce the compression of the wrist.

CONDITION

3. Asthma

Yoga can help bring awareness to your breathing patterns and release tension from the neck, upper back, chest, and shoulders. Focus on developing full and complete breaths through seated mediation sitting in Easy Pose (*Sukhasana*) here. Since a symptom of asthma is short shallow breaths, developing control of the breath will help the body obtain the oxygen needed and help calm the body, preventing future attacks.

Some yoga poses may be strenuous to the respiratory system and could cause asthma attacks. It's recommended that you pace yourself, gradually raising your body temperature and gradually cooling down. Cold air can cause bronchi to contract and cause an asthma attack. Hot and humid air can cause dehydration and can also cause an asthma attack. Find a room with a comfortable temperature.

BENEFICIAL POSES

Poses on hands and knees–Ex. Going from Tiger Pose (*Vyaghrasana*) here to Unsupported Tiger Pose (*Niralamba Vyaghrasana*) here. Many people who suffer from asthma have tension in the upper back and chest from coughing during asthma attacks. Combining mild backbends with mild forward bends gently stretches the chest, upper back, and the neck, which can help reduce the symptoms of asthma worsened by tension in those areas.

Mild backbends–Ex. Fish Pose (*Matsyasana*) here. Mild backbends help open the chest and front shoulder heads and improve the quality of breathing.

Lion's Pose variations–Ex. Lion Pose Dedicated to an Avatar of Lord Vishnu in Garland Pose (*Narasimhasana in Malasana*) here. Lion's Pose variations can help release tension in the throat, neck, and jaw because you "roar" like a lion in these poses. They also can help push the stale air out of your lungs.

Seated meditation focusing on breathing–Ex. Lotus Pose (*Padmasana*) here. Bringing awareness to your breath and developing control can be useful during an asthma attack. It can also help prevent an attack from happening.

Inversions–Ex. Headstand 5 (*Shirshasana 5*), also known as Tripod Headstand here. Inversions help promote proper movement of the diaphragm during an exhalation. Since the majority of the body is upside down, gravity works with the exhalation, not against it.

POSES TO APPROACH WITH CAUTION

Inversions on the shoulders–Ex. Ear Pressure Pose (*Karnapidasana*) here. Inversions on the shoulders compress the neck and chest, especially when the knees are bent toward the head. This compression restricts your breathing and may cause an asthma attack.

Backbends on the chin and chest–Ex. Inverted Locust Pose (*Viparita Shalabhasana*) here. These poses compress the throat and restrict your breathing, and may cause an asthma attack.

Seated forward bends–Ex. Western Intense Stretch Pose (*Paschimottanasana*) here. These poses compress the lungs and restrict your breathing, and may cause an asthma attack.

Cardio-intense poses–Ex. Crocodile Pose (*Nakrasana*) here. Poses that require a lot of strength and that are demanding on the cardiovascular system can cause shortness and shallowness of breath, and may cause an asthma attack.

Intense backbends–Ex. Little Thunderbolt Pose (*Laghuvajrasana*) here. These poses can be stimulating and cause shortness of breath if you have asthma. It is recommended to start with mild backbends and progress into deeper ones slowly, according to how your body feels.

Arm balances with both feet off the floor–Ex. Uneven Half Repose Pose Dedicated to Ashtavakr (*Vishama Ardha Shayana Ashtavakrasana*) here. These types of poses require a lot of strength and endurance and may cause shortness of breath.

CONDITION

4. Neck Pain

Yoga practice can help prevent and relieve neck pain. The combination of gentle stretches and strengthening movements can open up tight muscles in the body, increasing neck flexibility and rebalancing postural muscles. Simple and slow movements will lubricate the neck and increase its range of movement. Hold each pose for 30 to 90 seconds.

While it's important to strengthen and stretch the neck muscles in order to help prevent neck injury, if you already have a neck concern it's best not to aggravate it. Poses that are most strenuous for the neck are the ones that bear the majority of the body's weight on the head or neck.

BENEFICIAL POSES

Seated neck stretches–Ex. Easy Pose with Neck Stretch (*Sukhasana*) here. Neck pain can be caused by tension in the neck muscles. Stretching these muscles can help prevent or reduce neck pain.

Seated twists–Ex. Pose Dedicated to Bharadvaja 1 (*Bharadvajasana 1*) here. Muscles in the neck are connected to the muscles in the upper back. Seated twists increase the range of motion in the upper back and neck and can help prevent or reduce neck pain caused by tension in these areas.

Poses on hands and knees–Ex. Going from Tiger Pose (*Vyaghrasana*), modification knee to the forehead, here to Tiger Pose (*Vyaghrasana*), also known as Cat Tilt here, top. Rounding the back and then going into a mild backbend can help strengthen the neck muscles and stretch the front of the neck (in Dog Tilt) and the back of the neck (in Cat Tilt).

Hand position of the pose dedicated to Garuda–Ex. Hand Position of the Pose Dedicated t Garuda in Hero Pose (*Hasta Garudasana in Virasana*) here. Any pose with this hand position helps stretch the upper back and back shoulder heads and can help prevent neck pain caused by tension in the muscles of the upper back.

POSES TO APPROACH WITH CAUTION

Full inversions–Ex. Revolved Leg Position of One-Legged King Pigeon 1 Version B in Headstan 5 (*Parivritta Pada Eka Pada Raja Kapotasana 1 B in Shirshasana 5*) here, One-Legged Unsupported Whole Body Pose (*Eka Pada Niralamba Sarvangasana*), also known as Shoulderstand here Full inversions with the head on the floor put strain on the neck since the majority of the body weight tends to rest on the head or neck. If you have a neck injury, it's best to avoid these.

Backbends with feet and head on the floor–Ex. Inverted Tip Toe Bow Pose (*Viparita Prapada Dhanurasana*), also known as Headstand Bow Pose (*Shirsha Dhanurasana*) here. Backbends with head and feet on the floor require a lot of neck strength and should be avoided if you have a neck concern.

CONDITION

5. High Blood Pressure

If you think you may be at risk or have already been diagnosed with high blood pressure, it is advisable to speak with your health care provider. Practicing yoga may help with blood pressure management since it combines the benefits of meditation, muscle relaxation, and strength training exercise. When practicing yoga poses, ensure that you are able to breathe comfortably and deeply. If you have any difficulty breathing, come out of the pose and rest or perform an easier version of the pose. If difficulty breathing persists, then consult your health care provider immediately.

BENEFICIAL POSES

Seated backbends–Ex. Hands Bound Lotus Pose (*Baddha Hasta Padmasana*) here. Seated backbends gently open the chest and improve the flow of oxygen to the lungs. They release tension in the chest and front shoulder heads often caused by stress and hunching over a computer on a daily basis. This can help lower high blood pressure that is a result of stress.

Seated twists–Ex. Revolved Easy Pose (*Parivritta Sukhasana*) here. Seated twists help release tension from the upper back and detoxify the body. This can help lower high blood pressure that is a result of tension in the upper back.

Supine forward bends–Ex. Reclining Both Hands to the Leg Pose (*Supta Dwi Hasta Padasana*) here. Supine forward bends stretch the hamstrings without increasing blood pressure, as opposed to standing forward bends where the head is below the heart. This can help lower high blood pressure that is a result of muscle tension of the lower back and legs.

POSES TO APPROACH WITH CAUTION

Inversions–Ex. Feet Spread Out Intense Stretch Pose 2 (*Prasarita Padottanasana 2*) here and Crane Pose in Headstand 5 Prep. (*Bakasana in Shirshasana 5 Prep.*) here. Inversions should be avoided if you have high blood pressure that is not controlled. They are very stimulating postures since the head is below the heart, which causes an increased demand for oxygen. These increase blood flow and heart rate, generating pressure to the blood vessels of the brain, and may cause blood pressure to rise dramatically.

Lunges with back knee off the floor–Ex. Revolved Son of Anjani (Lord Hanuman) Lunge Pose with Hands in Prayer (*Parivritta Anjaneyasana Namaskar*) here. These poses can require a lot of lower body strength if you are not used to practicing them. They can raise the heart rate and increase blood pressure.

Arm balances with both feet off the floor–Ex. Leg Position of Cow Face Pose in Pendant Pos (*Pada Gomukhasana in Lolasana*) here. These poses are demanding on the upper body and may increase heart rate, which can increase blood pressure.

Backbends with hands and feet on the floor–Ex. Elevated Both Legs Inverted Staff Pose (*Utthita Dwi Pada Viparita Dandasana*) here. Poses such as these can be demanding on the upper body and can elevate blood pressure by increasing heart rate.

CONDITION

6. Menstruation

During a period, uterine contractions can cause painful cramps in the lower abdomen and lower back. Yoga can help release endorphins to relax the body. Stretch out the lower body and back to help release the pain. Forward bends, inside hip openers, and gentle twists can help relieve the symptoms of menstruation.

Some are of the opinion that inversions can cause engorgement in the blood vessels of the uterus, which may increase blood flow, and should be avoided during a period. On the other hand, B.K.S. Iyengar's book *The Path to Holistic Health* recommends inversions during a period to reduce blood flow. You should listen to your own body and judge accordingly. If you are not feeling strong, engage in a slower-paced yoga pose practice.

BENEFICIAL POSES

Supine hip openers–Ex. Universal All-Encompassing Diamond Pose (*Vishvavajrasana*) here. Poses such as this open up the hips and groin and allow the lumbar spine to rest, which can help relieve the menstrual discomfort.

Low squats–Ex. One Leg Bound Garland Pose (*Eka Pada Baddha Malasana*) here. Practice poses such as this to stretch out the groin, the chest, and front shoulders. Releasing tension from those areas can help relieve menstrual discomfort.

Seated hip openers–Ex. One Legged King Pigeon Pose 1 Prep. (*Eka Pada Raja Kapotasana 1 Prep.*) here. Poses such as this help open up the hip and stretch the lower abdomen, which can help relieve menstrual discomfort due to tension in that area.

Backbends on the knees–Ex. Camel Pose (*Ushtrasana*) here. Poses such as this can help stretch out the lower abdomen and release tension from that region, which can help relieve menstrual discomfort.

Gentle seated twists–Ex. Easy Lord of The Fishes Pose Prep. (*Sukha Matsyendrasana Prep.*) here. Seated twists stimulate internal organs and can help relieve the symptoms of menstruation by gently encouraging the natural blood flow during menstruation.

POSES TO APPROACH WITH CAUTION

Arm balances with hands and feet on the floor–Ex. Four Limbed Staff Pose (*Chaturanga Dandasana*) here. Poses such as this are very demanding on the upper body and core, and may worsen the symptoms of menstruation due to overstraining.

Arm balances with both feet off the floor–Ex. Pose Dedicated to Galava, One-Legged Variatio (*Eka Pada Galavasana*) here. These poses demand a lot of strength and may worsen the symptoms of menstruation due to overstraining.

High squats–Ex. Tip Toe Fierce Pose (*Prapada Utkatasana*) here. Poses such as this are demanding on the legs and core, and may worsen the symptoms of menstruation due to overstraining.

Backbends on hands and feet–Ex. Partridge Pose (*Kapinjalasana*) here. Intense backbends put a lot of strain on the body, because they engage the entire body. They may worsen the symptoms of menstruation due to overstraining.

CONDITION

7. Pregnancy

Don't engage in a vigorous yoga practice with jump-through and jump-back *Vinyasas*. Jumping is dangerous during pregnancy. Avoid hot yoga classes that can dangerously elevate your core temperature or cause dehydration. After giving birth, be mindful when going into deep stretches. The levels of relaxin (the hormone that loosens the muscles and joints to accommodate birth) in the body may still be high, increasing the danger of injury due to overstretching. If you had a C-section, make sure the wound heals properly. Avoid doing any intense twists or backbends, as they may interfere with healing of the wound.

BENEFICIAL POSES

Seated inner hip openers–Ex. Knees Spread Wide Hero Pose (*Prasarita Janu Virasana*) here. Poses such as this stretch out the inner hips without compressing the abdomen.

Wide-legged squats–Ex. Lotus Hand Seal in Upward Hands Pose Dedicated to Goddess Ka (*Padma Mudra Urdhva Hasta Kalyasana*) here. Wide-legged squats strengthen quadriceps (front of the thighs), hamstrings (back of the thighs), and glutes (buttocks) without putting pressure onto the abdomen.

Standing side bends–Ex. Extended Side Angle Pose (*Utthita Parshva Konasana*) here. Standing side bends stretch out the side of the torso and lower back while strengthening the legs without putting pressure onto the abdomen.

Poses on hands and knees–Ex. Tiger Pose (*Vyaghrasana*) here. Poses on hands and knees can be done during pregnancy because they do not compress the abdomen.

Mild backbends on the knees–Ex. Half Camel Pose (*Ardha Ushtrasana*) here. Mild backbends can be practiced during pregnancy since they don't compress the abdomen.

POSES TO APPROACH WITH CAUTION

Inversions–Ex. Repose Pose (*Shayanasana*) here. Don't do any inversions where your heart is above your head beyond the first trimester. Turning your body upside down creates pressure on your internal organs and may be damaging to the developing fetus.

Forward bend twists–Ex. Two Hands Revolved Western Intense Stretch Pose (*Dwi Hasta Parivritta Paschimottanasana*) here. Don't do any forward bends or twists that compress the abdomen and squeeze the fetus and placenta.

Core poses–Ex. Revolved Boat Pose (*Parivritta Navasana*) here. Don't do strenuous core poses that compress the abdomen.

Prone poses–Ex. One-Legged Pose Dedicated to Siddhar Konganar (*Eka Pada Konganarasana*) here. Avoid prone poses since they put a lot of pressure on the abdomen.

Supine poses where the back is flat on the floor–Ex. Reclined Leg Position of Cow Face Pose (*Supta Pada Gomukhasana*) here. Supine poses with the back flat on the floor take out the natural curve in the lumbar spine that is present during pregnancy and can compress the fetus and placenta.

Intense backbends–Ex. One-Legged Pigeon Pose (*Eka Pada Kapotasana*) here. Intense backbends create too much stretch in the abdomen and should be avoided during pregnancy.

CONDITION

8. Menopause

Common symptoms of menopause such as hot flashes and mood swings can be alleviated with regular yoga pose practice. Focus on poses that open up the pelvic area as well as mediation to help control stress.

Avoid practicing hot yoga and avoid overexertion. Both can trigger menopause symptoms. It is recommended to avoid vigorous Sun Salutes, as they can increase body temperature and cause hot flashes.

BENEFICIAL POSES

Mild supine backbends–Ex. Bridge Whole Body Pose (*Setu Bandha Sarvangasana*) here. Mild backbends open up the chest and heart area. They can help balance blood pressure and hormonal secretions as well as help relieve mood swings and hot flashes.

Supine hip openers–Ex. Reclined Bound Angle Pose *(Supta Baddha Konasana*) here. These poses open up the chest, heart and pelvic areas. Blood flow is increased into the pelvic area and reproductive organs and that can help balance hormonal functions. These poses can help relieve high blood pressure, headaches, and breathing problems.

Supine thigh openers–Ex. Reclined Hero Pose (*Supta Virasana*) here. Poses such as this can help improve blood circulation in the ovarian region and stimulate the pelvic organs, which can help balance hormonal functions and relieve the symptoms of menopause.

POSES TO APPROACH WITH CAUTION

Backbends on hands and feet–Ex. Tip Toe One Hand Upward Bow Pose (*Prapada Eka Hasta Urdhva Dhanurasana*) here. Poses such as these can be too strenuous on the upper body (arms and shoulders). They can raise the body temperature and cause hot flashes.

Core poses–Ex. Boat Pose (*Navasana*) here. Avoid any vigorous core yoga poses, as it creates too much tension around the abdominal organs and may worsen the menopause symptoms.

Standing twists–Ex. Revolved Side Angle (*Parivritta Parshva konasana*) here. Avoid any intense twists, as it creates too much compression around the internal organs of the torso, which may worsen the menopause symptoms.

Inversions–Ex. Headstand 1 (*Shirshasana 1*) here. Avoid any full inversions, as they increase blood flow to the internal organs of the torso and raise heart rate which may cause hot flashes.

Standing Poses

MOUNTAIN POSE
SIDE BENDS
STANDING BACKBENDS
ONE LEG STANDING BALANCE
STANDING FORWARD BENDS
LEGS WIDE
DOWNWARD DOG
INTENSE SIDE STRETCH
TRIANGLE POSE
WARRIOR AND SIDE ANGLE POSES
LUNGES AND KNEELING POSES
SQUATS

MOUNTAIN POSE: HANDS BELOW THE HEAD

Mountain Pose

Tadasana

(tuh-DAHS-uh-nuh)

Also Known As: Equal Steady Standing, State of Balance (Samasthiti)
Modification: palms rotated forward
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)



Mountain Pose with Hands in Prayer

Tadasana Namaskar

(tuh-DAHS-uh-nuh nuh-muhs-KAHR)

Modification: hands in Anjali Mudra (Hands in Prayer); feet to the front, toes lifted
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)



Reverse Prayer Mountain Pose

Viparita Namaskar Tadasana

(vi-puh-REE-tuh nuh-muhs-KAR tuh-DAHS-uh-nuh)

Also Known As: Penguin Pose, Back of the Body Prayer Mountain Pose (Paschima Namaskara Tadasana)
Modification: feet rotated out
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)



Hands Bound Mountain Pose

Baddha Hasta Tadasana

(BUH-duh HUH-stuh tuh-DAHS-uh-nuh)

Pose Type: standing
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



MOUNTAIN POSE: HANDS ABOVE THE HEAD & TANDAVA AND LASYA DANCE MODIFICATIONS

Upward Salute Pose

Urdhva Hastasana

(OORD-vuh huh-STAHS-uh-nuh)

Also Known As: Volcano Pose
Modification: arms shoulder width apart
Pose Type: standing, mild backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Upward Salute Pose

Urdhva Hastasana

(OORD-vuh huh-STAHS-uh-nuh)

Also Known As: Volcano Pose
Modification: palms pressed together
Pose Type: standing, mild backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Mountain Pose—Raised Bound Hands

Tadasana Urdhva Baddha Hastasana

(tuh-DAHS-uh-nuh OORD-vuh BUH-duh huh-STAHS-uh-nuh)

Also Known As: Mountain Pose (Parvatasana)
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)



Mountain Pose

Tadasana

(tuh-DAHS-uh-nuh)

Modification: shoulder opener, intense version
Pose Type: standing
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Pose Inspired by Parvati’s Graceful Dance

Lasyasana

(lahs-YAHS-uh-nuh)

Modification: both legs straight; one leg extended to the front, heel up; one arm up over the head reaching to the floor, other arm reaching up to the sky; deep backbend
Pose Type: standing, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



SIDE BENDS: FEET TOGETHER, ARMS UP OVER THE HEAD & TANDAVA AND LASYA DANCE MODIFICATIONS

Standing Crescent Pose

Indudalasana

(in-doo-duh-LAHS-uh-nuh)

Modification: grabbing onto the wrist of the top hand
Pose Type: standing, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Sideways Mountain Pose—Raised Bound Hands

Parshva Tadasana Urdhva Baddha Hastasana

(PAHRSH-vuh tuh-DAHS-uh-nuh OORD-vuh BUH-duh HUH-STAHS-uh-nuh)

Also Known As: Side Bending Pose (Parshva Bhangi)
Pose Type: standing, side bend

Drishti Point: Nasagrai or Nasagre (nose)



Revolved Upward Mountain Pose—Raised Bound Hands

Parivritta Urdhva Tadasana Urdhva Baddha Hastasana

(puh-ri-VRIT-tuh OORD-vuh tuh-DAHS-uh-nuh OORD-vuh BUH-duh HUH-STAHS-uh-nuh)

Also Known As: Side Bending Pose (Parshva Bhangi)
Pose Type: standing, side bend, backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



One-Legged Standing Crescent Pose

Eka Pada Indudalasana

(EY-kuh PUH-duh in-doo-LAHS-uh-nuh)

Modification: grabbing onto the wrist
Pose Type: standing one-legged balance, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)

Side Stretch Pose

Parshvasana

(pahrsh-VAH-suh-nuh)

Modification: fingers interlocked, palms pressed together
Pose Type: standing, side bend
Drishti Point: Nasagrai or Nasagre (nose), Urdhva or Antara Drishti (up to the sky)



Pose Inspired by Shiva’s Vigorous Cycle of Life Dance

Tandavasana

(tahn-duh-VAHS-suh-nuh)

Modification: heels down, legs crossed, arms up over the head
Pose Type: standing, side bend, backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



TANDAVA AND LASYA DANCE MODIFICATIONS

Pose Inspired by Parvati’s Graceful Dance

Lasyasana

(lahs-YAHS-uh-nuh)

Modification: legs crossed, knees bent; one hand on the hip, one arm over the head
Pose Type: standing, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व ह



Pose Inspired by Parvati’s Graceful Dance

Lasyasana

(lahs-YAHS-uh-nuh)

Modification: front leg ankle stretch, both knees bent, legs crossed, one arm toward the opposite knee, other arm up over the head
Pose Type: standing, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व

SIDE BENDS: ONE ARM UP OVER THE HEAD, OTHER ARM ALONG THE SIDE OF TORSO

One Hand Side Stretch Pose

Eka Hasta Parshvasana

(EY-kuh HUH-stuh pahrsh-VAH-suh-nuh)

Modification: one arm up over the head, other hand sliding down the leg
Pose Type: standing, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Swaying Palm Tree Pose

Tiryak Tala-Vrikshasana

(TIR-yuhk TAHL-uh-vrik-SHAHS-uh-nuh)

Pose Type: standing, side bend

Drishti Point: Hastagrai or Hastagre (hands)

How to Perform the Pose:

1. Begin by standing in Mountain Pose (*Tadasana*). Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Inhale; step your feet slightly wider than shoulder-distance apart with toes facing forward and feet parallel to each other. Expand your chest and hold your arms straight out to the sides, parallel to the floor.
3. Exhale as you side bend to the left, dropping your left hand either to the side of the left thigh or the left shin. (Avoid putting pressure on the knee joint.) Bring your right arm over head and bend it at the elbow.
4. Inhale as you rotate your chest up to the sky; do not collapse it forward. Feel the deep stretch on the right side of your torso as you look toward your right hand (Pose #1).
5. On your next exhale, try to reach your right arm over your head with fingertips pointing toward the floor (Pose #2).
6. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch. Exhale as you release the pose. Inhale as you press strongly into both feet to come up.
7. Exhale, come back to Mountain Pose (*Tadasana*), and repeat on the left side.

Modification: elbow of the top arm bent
1. mild version
2. intense version

tiryak = horizontally, sideways, obliquely, across

tala-vrikshasana = palm tree

1.



2.



Hands Bound Rising Standing Locust Pose

Baddha Hasta Utthita Stiti Shalabhasana

(BUH-duh HUH-stuh UT-ti-tuh STI-ti shuh-luh-BAHS-uh-nuh)

Also Known As: Baddha Hasta Utthita Nindra Shalabhasana
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ



Sun Salutation Pose—Raised Bound Hands

Surya Namaskarasana Urdhva Baddha Hastasana

SOOR-yuh nuh-muhs-kahr-AHS-uh-nuh OORD-vuh BUH-duh huh-STAHS-uh-nuh)

Pose Type: standing, backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल र य ह ॐ



Rising Standing Cobra Pose

Utthita Stiti Bhujangasana

(UT-ti-tuh STI-ti bu-juhng-AHS-uh-nuh)

Also Known As: Utthita Nindra Bhujangasana
Modification: toes down, hands on the front of the knees
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Sun Salutation Pose

Surya Namaskarasana

(SOOR-yuh nuh-muhs-kahr-AHS-uh-nuh)

Modification: palms facing up
Pose Type: standing, backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Sun Salutation Pose

Surya Namaskarasana

(SOOR-yuh nuh-muhs-kahr-AHS-uh-nuh-uh-nuh)

Modification: fingers interlocked, pointer fingers out
Pose Type: standing, backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Reverse Facing Intense Stretch Pose

Tiryang Mukhottanasana

(TEER-yuhng mu-ko-tahn-AHS-uh-nuh)
Also Known As: Full Wheel Pose (Purna Chakrasana)
Modification: grabbing onto the shins
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reverse Facing Intense Stretch Pose

Tiryang Mukhottanasana

(TEER-yuhng mu-ko-tahn-AHS-uh-nuh)
Modification: grabbing onto the front of the knees
Pose Type: standing, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



STANDING BACKBENDS: KNEES BENT

Standing Upward Facing Intense Ankle Stretch Bow Pose

Stiti Urdhva Mukgattana Kulpa Dhanurasana

(STI-ti OORD-vuh mu-ko-TAH-nuh KUL-puh duh-nur-AHS-uh-nuh)

Also Known As: Nindra Urdhva Mukgattana Kulpa Dhanurasana
Modification: hands to the heels
Pose Type: standing, backbend, balance
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



ONE LEG STANDING BALANCE: KNEE BENT—HEEL TO THE SITTING BONES

One Hand to Foot Rising Standing One-Legged Frog Pose

Eka Hasta Pada Utthita Stiti Eka Pada Bhekasana

(EY-kuh HUH-stuh PUH-duh UT-ti-tuh STI-ti EY-kuh PUH-duh bey-KAHS-uh-nuh)

Also Known As: Eka Hasta Pada Utthita Nindra Eka Pada Bhekasana

Modification: grabbing onto the foot, arm crossed in front; foot toward the glutes

Pose Type: standing one-legged balance, binding

Drishti Point: Hastagrai or Hastagre (hands)

🔴



Lord of the Dance Pose

Natarajasana

(NAH-tuh-rahj-AHS-uh-nuh)

Modification: one hand to foot, foot toward the glutes

Pose Type: standing one-legged balance, backbend

Drishti Point: Hastagrai or Hastagre (hands)

🔴 🟢 🔵



Both Hands to Foot Rising Standing One-Legged Frog Pose

Dwi Hasta Pada Utthita Stiti Eka Pada Bhekasana

(dwi-huh-stuh PUH-duh UT-ti-tuh STI-ti EY-kuh PUH-duh bey-KAHS uh-nuh)

Also Known As: Dwi Hasta Pada Utthita Nindra Eka Pada Bhekasana

Pose Type: standing one-legged balance

Drishti Point: Nasagrai or Nasagre (nose)



ONE LEG STANDING BALANCE: KNEE BENT—HEEL TO THE SITTING BONES—HALF FORWARD BEND

Bowing with Respect Lord of the Dance Pose

Nantum Natarajasana

(NUHN-tum NAH-tuh-rahj-AHS-uh-nuh)

Modification: half forward bend, both hands to the back foot, foot toward the glutes
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Half Bound Bowing with Respect Lord of the Dance Pose

Ardha Baddha Nantum Natarajasana

(UHR-duh BUH-duh NUHN-tum NAH-tuh-rahj-AHS-uh-nuh)

Modification: grabbing onto the back foot with opposite hand
Pose Type: standing one-legged balance, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)



Half Moon Bow Pose Prep.

Ardha Chandrachapasana Prep.

(UHR-duh CHUHN-druh-chahp-AHS-uh-nuh)

Modification: grabbing onto the back foot with the hand on the same side
Pose Type: standing one-legged balance, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Hand to Foot Revolved Half Moon Bow Pose

Hasta Pada Parivritta Ardha Chandrachapasana

(HUH-stuh PUH-duh puh-ri-VRIT-tuh UHR-duh CHUHN-druh-chahp-AHS-uh-nuh)

Also Known As: Lord of the Dance Pose Modification (Natarajasana)
Pose Type: standing one-legged balance, forward bend, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Half Bound Unsupported Bound One-Legged Intense Stretch Pose Prep.

Ardha Baddha Niralamba Baddha Eka Pada Uttanasana Prep.

(UHR-duh BUH-duh nir-ah-LUHM-buh BUH-duh EY-kuh PUH-duh ut-tahn-AHS-uh-nuh)

Also Known As: Lord of the Dance Pose Prep. Modification (Natarajasana Prep.) and Half Bound Unsupported Bound One-Legged Forward Bend Prep.
Modification: one hand to the floor
Pose Type: standing one-legged balance, forward bend, binding
Drishti Point: Hastagrai or Hastagre (hands), Nasagrai or Nasagre (nose)
ल व य



ONE LEG STANDING BALANCE: KNEE BENT—HEEL TO THE SITTING BONES—FORWARD BEND

One Leg Stretched Upward Pose Prep.

Urdhva Prasarita Ekapadasana Prep.

(OORD-vuh pruh-SAH-ri-tuh EY-kuh-puh-DAHS-uh-nuh)

Modification: top leg bent, heel toward the glutes; both palms to the floor
Pose Type: standing one-legged balance, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose)



Unsupported Bound One Foot Intense Stretch Pose

Niralamba Baddha Eka Pada Uttanasana

(nir-ah-LUHM-buh BUH-duh EY-kuh PUH-duh ut-TAHS-uh-nuh)

Also Known As: Unsupported Bound One Foot Full Forward Bend
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



ONE LEG STANDING BALANCE: KNEE BENT—HALF FORWARD BEND

Revolved Half Moon Bow Pose

Parivritta Ardha Chandrachapasana

(puh-ri-VRIT-tuh UHR-duh CHUHN-druh-chahp-AHS-uh-nuh)

Pose Type: standing one-legged balance, backbend, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky), Padhayoragrai or Padayoragre (toes/feet), Hastagrai or Hastagre (hands)



Pose Dedicated to Yogi Gitananda

Gitanandasana

(geet-ah-nuhn-DAHS-uh-nuh)

Also Known As: Lord of the Dance Pose Modification (Natarajasana)
Modification: foot away from the head
Pose Type: standing one-legged balance, backbend, forward bend
Drishti Point: Hastagrai or Hastagre (hands)



Pose Dedicated to Yogi Gitananda

Gitanandasana

(geet-ah-nuhn-DAHS-uh-nuh)

Also Known As: Lord of the Dance Pose Modification (Natarajasana)
Modification: foot to the head
Pose Type: standing one-legged balance, backbend, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



ONE LEG STANDING BALANCE: HANDS BOUND BEHIND THE BACK

Toppling Tree Pose

Patan Vrikshasana

(PUH-tuhn vrik-SHAHS-uh-nuh)

Modification: both knees bent
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Toppling Tree Pose

Patan Vrikshasana

(PUH-tuhn vrik-SHAHS-uh-nuh)

Modification: both legs straight
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



ONE LEG STANDING BALANCE: KNEE BENT—FOOT TO THE ELBOW CREASE

Lord of the Dance Pose Prep.

Natarajasana Prep.

(NAH-tuh-rahj-AHS-uh-nuh)

Modification: foot to the elbow crease, arms open to the sides, elbows bent
Pose Type: standing one-legged balance, backbend
Drishti Point: Hastagrai or Hastagre (hands)



Prayer Lord of the Dance Pose

Namaskar Natarajasana

(nuh-muhs-KAHR NAH-tuh-rahj-AHS-uh-nuh)

Modification: foot to the elbow crease
Pose Type: standing one-legged balance, backbend
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Half Moon Bow Pose Prep.

Ardha Chandrachapasana Prep.

(URH-duh chuhn-druh-chahp-AHS-uh-nuh)

Modification: foot to the elbow crease
Pose Type: standing one-legged balance, backbend, forward bend
Drishti Point: Hastagrai or Hastagre (hands)



ONE LEG STANDING BALANCE: KNEE BENT BEHIND

Lord of the Dance Pose

Natarajasana

(NAH-tuh-rahj-AHS-uh-nuh)

Also Known As: Baby Dancer’s Pose (Bala Natarajasana)
Modification: hand to the foot on the same side using an under-head grip, back knee bent
1. thigh parallel to the floor
2. thigh 45 degrees to the floor, half forward bend

Pose Type: standing one-legged balance, backbend
Drishti Point: Hastagrai or Hastagre (hands)


1.


2.

Hand Position of Mermaid Pose in Bowing With Respect

Lord of the Dance Pose

Hasta Naginyasana in Nantum Natarajasana

(HUH-stuh nuh-gin-YAHS-uh-nuh in nan-toom NAH-tuh-rahj-AHS-uh-nuh)

Pose Type: standing one legged balance, backbend, forward bend

Drishti Point: Nasagrai or Nasagre (nose) or Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

How to Perform the Pose:

1. Begin by standing in Mountain Pose (*Tadasana*). Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Inhale and bring your weight onto the left foot. Exhale as you bend your right knee, grab onto the right foot with your right hand, and bring your right heel to your right sitting bone. Keep your standing leg strong and straight by pulling the knee cap up and engaging the front thigh muscles (quadriceps). Keep your knees together.
3. On the next exhale, start pushing your right foot back and up to the sky, while tipping your torso forward.
4. Exhale as you bring the right foot to the right elbow crease and bend your right arm to keep the foot in place.
5. Inhale as you reach your left arm out in front of you. Exhale, bend the left elbow, and grab onto the right hand with your left hand (Pose #2). This is the arm position of Mermaid Pose (*Hasta Naginyasana*).
6. To deepen the shoulder stretch, on the next exhale start walking your left hand down your left forearm. Grab first onto the left elbow and then to your left tricep (Pose #1).
7. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch. Exhale as you release the pose, come back to Mountain Pose (*Tadasana*), and repeat on the right side.

hasta = hand

naga = great mythological snake

nantum = to bow with respect

Nataraj = name of Shiva as a cosmic dancer

1.





2.

Open Heart Lord of the Dance Pose

Anahata Chakra Natarajasana

(uhn-AH-huh-tuh CHUHK-ruh NAH-tuh-rahj-AHS-uh-nuh)

Modification: back knee bent, arms open to the sides, foot working toward the head
Pose Type: standing one-legged balance, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



Lord of the Dance Pose

Natarajasana

(NAH-tuh-rahj-AHS-uh-nuh)

Modification: hand to opposite foot using an under-head grip, back knee bent
Pose Type: standing one-legged balance, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



Lord of the Dance Pose

Natarajasana

(NAH-tuh-rahj-AHS-uh-nuh)

Modification: standing leg bent, heel to the floor; hand to the foot on the same side using an overhead grip, foot to the shoulder

Pose Type: standing one-legged balance, backbend

Drishti Point: Hastagrai or Hastagre (hands)

ल व र य



Lord of the Dance Pose

Natarajasana

(NAH-tuh-rahj-AHS-uh-nuh)

Also Known As: Lord of the Dance Pose 1 (Natarajasana 1)

Modification: both hands grabbing onto the back foot with overhead grip, foot away from the head

Pose Type: standing one-legged balance, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व र य ह ॐ



ONE LEG STANDING BALANCE: GRABBING ONTO THE BACK KNEE

Bound Lord of the Dance Pose

Baddha Natarajasana

(BUH-duh NAH-tuh-rahj-AHS-uh-nuh)

Also Known As: Yogi Yogananda Pose (Yoganandasana)
Modification: hand binding to the knee on the same side of the body; back foot away from the head
Pose Type: standing one-legged balance, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
● ● ● ● ●



Bound Lord of the Dance Pose

Baddha Natarajasana

(BUH-duh NAH-tuh-rahj-AHS-uh-nuh)

Modification: one hand binding to the knee on the same side of the body, other arm crossed in front of the neck
1. left side view
2. right side view
Pose Type: standing one-legged balance, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)
● ● ● ● ●





Bound Lord of the Dance Pose

Baddha Natarajasana

(BUH-duh NAH-tuh-rahj-AHS-uh-nuh)

Also Known As: Yogi Yogananda Pose (Yoganandasana)
Modification: hand binding to the inside of the thigh on the same side of the body, back foot away from the head
Pose Type: standing one-legged balance, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Supported Sideways Hand to Knee Lord of the Dance Pose

Salamba Parshva Hasta Janu Natarajasana

(sah-LUHM--buh PAHRSH-vuh HUH-stuh JAH-nu NAH-tuh-rahj-AHS-uh-nuh)

Pose Type: standing one-legged balance, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Unsupported Sideways Hand to Knee Lord of the Dance Pose

Niralamba Parshva Hasta Janu Natarajasana

(nir-ah-LUHM-buh-nuh PAHRSH-vuh HUH-stuh JAH-nu NAH-tuh-rahj-AHS-uh-nuh)

Pose Type: standing one-legged balance, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



ONE LEG STANDING BALANCE: KNEE BENT IN FRONT

Hand Bound Rising Standing Wind Relieving Pose Prep.

Baddha Hasta Utthita Stiti Vayu Muktyasana Prep.

(BUH-duh HUH-stuh UT-ti-tuh STI-ti VAH-yu muk-TYAHS-uh-nuh)

Also Known As: Baddha Hasta Utthita Nindra Vayu Muktyasana Prep.
Modification: knee of the standing leg bent; fingertips to elbows, arms parallel to the floor, knee of the lifted leg to the forearm
Pose Type: standing one-legged balance
Drishti Point: Nasagrai or Nasagre (nose)

Standing Rising One-Legged Chin to Knee Pose Prep.

Stiti Utthita Eka Pada Chibi Janu Shirshasana Prep.

(STI-ti UT-ti-tuh EY-kuh PUH-duh CHI-bi JAH-nu sheer-SHAHS-uh-nuh)

Also Known As: Nindra Utthita Eka Pada Chibi Janu Shirshasana Prep.

Modification: 1. arms wrapped around the shin 2. fingers interlocked over the shin

Pose Type: standing one-legged balance, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

ल व र ह





ONE LEG STANDING BALANCE: KNEE BENT IN FRONT—BINDING & TWISTS

Standing Rising Wind Relieving Pose

Stiti Utthita Vayu Muktyasana

(STI-ti UT-ti-tuh VAH-yu muk-TYAHS-uh-nuh)

Also Known As: Nindra Utthita Vayu Muktyasana; Standing Pose Dedicated to Marichi (Nindra Marichyasana)
Modification: standing up straight
Pose Type: standing one-legged balance, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य



Revolved Prayer Standing Rising Wind Relieving Pose

Parivritta Namaskar Stiti Utthita Vayu Muktyasana

(puh-ri-VRIT-tuh nuh-muhs-KAHR STI-ti UT-ti-tuh VAH-yu mukTYAHS-uh-nuh)

Also Known As: Parivritta Namaskar Nindra Utthita Vayu Muktyasana
Modification: hands in Anjali Mudra (Hands in Prayer)
Pose Type: standing one-legged balance, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व र



Revolved Bound Standing Rising Wind Relieving Pose

Parivritta Baddha Stiti Utthita Vayu Muktyasana

(puh-ri-VRIT-tuh BUH-duh STI-ti UT-ti-tuh VAH-yu muk-TYAHS-uh-nuh)

Also Known As: Parivritta Baddha Nindra Utthita Vayu Muktyasana
Modification: binding around the back of the thigh
1. foot on the knee
2. foot away from the knee
Pose Type: standing one-legged balance, forward bend, twist, binding
Drishti Point: Nasagrai or Nasagre (nose)


1.


2.

Revolved Bound Standing Rising Wind Relieving Pose

Parivritta Baddha Stiti Utthita Vayu Muktyasana

(puh-ri-VRIT-tuh BUH-duh STI-ti UT-ti-tuh VAH-yu muk-TYAHS-uh-nuh)

Also Known As: Parivritta Baddha Nindra Utthita Vayu Muktyasana
Modification: binding around the shin
Pose Type: standing one-legged balance, forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



ONE LEG STANDING BALANCE: BOTH KNEES BENT—BINDING & TWISTS

Revolved Bound Standing Rising Wind Relieving Pose Prep.

Parivritta Baddha Stiti Utthita Vayu Muktyasana Prep.

(puh-ri-VRIT-tuh BUH-duh STI-ti UT-ti-tuh VAH-yu muk-TYAHS-uh-nuh)

Also Known As: Parivritta Baddha Nindra Utthita Vayu Muktyasana Prep.
Modification: foot resting on the knee, standing leg bent
Pose Type: standing one-legged balance, forward bend, twist, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Pose Inspired by Shiva’s Vigorous Cycle of Life Dance

Tandavasana

(tahn-duh-VAHS-uh-nuh)

Modification: knee to the opposite elbow, foot resting on the knee, standing leg bent, heel down
Pose Type: standing one-legged balance, forward bend, twist
Drishti Point: Nasagrai or Nasagre (nose), Hastagrai or Hastagre (hands)



Pose Inspired by Shiva’s Vigorous Cycle of Life Dance

Tandavasana

(tahn-duh-VAHS-uh-nuh)

Modification: both arms straight, one forearm to the opposite knee, other arm straight up to the sky, both knees bent
Pose Type: standing one-legged balance, forward bend, twist
Drishti Point: Hastagrai or Hastagre (hands)

ल व र य



ONE LEG STANDING BALANCE: HEEL UP

Tip Toe Pose Inspired by Shiva’s Vigorous Cycle of Life Dance

Prapada Tandavasana

(PRUH-puh-duh tahn-duh-VAHS-uh-nuh)

Modification: knee to the opposite elbow, foot resting on the knee, standing leg bent
Pose Type: standing one-legged balance, forward bend, twist
Drishti Point: Nasagrai or Nasagre (nose), Hastagrai or Hastagre (hands)

ल व र



Tip Toe Pose Inspired by Parvati’s Graceful Dance

Prapada Lasyasana

(PRUH-puh-duh lahs-YAHS-uh-nuh)

Modification: deep backbend, one arm reaching up to the sky, other arm reaching down to the floor; standing leg straight, other knee bent; foot to the inside of the knee of the opposite leg
Pose Type: standing one-legged balance, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Hastagrai or Hastagre (hands)
ल व र य ह ॐ



Intense Ankle Stretch Tip Toe Lord of the Dance Pose

Uttana Kulpa Prapada Natarajasana

(ut-TAHN-uh KUL-puh PRUH-puh-duh NAH-tuh-rahj-AHS-uh-nuh)

Also Known As: Tip Toe Pose Inspired by Parvati’s Graceful Dance (Prapada Lasyasana)
Modification: standing leg bent, toes curled under, overhead grip, foot to the shoulder
Pose Type: standing one-legged balance, backbend
Drishti Point: Hastagrai or Hastagre (hands)
ल व र य



ONE LEG STANDING BALANCE: KNEE BENT IN FRONT, BINDING, FORWARD BENDS

Half Standing Wind Relieving Intense Stretch Pose 1 & 2 Prep.

Ardha Stiti Vayu Muktyuttonasana 1 & 2 Prep.

(UHR-duh STI-ti VAH-yu muk-tew-ton-AHS-uh-nuh)

Also Known As: Ardha Nindra Vayu Muktyuttonasana; Standing Wind Relieving Half Forward Bend
Modification: fingers interlocked on the knee, half forward bend
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य



One Hand Bound Half Standing Wind Relieving Intense Stretch Pose

Eka Hasta Baddha Ardha Stiti Vayu Muktyuttonasana

(EY-kuh HUH-stuh BUH-duh UHR-duh STI-ti VAH-yu muk-tew-ton-AHS-uh-nuh)

Also Known As: Eka Hasta Baddha Ardha Nindra Vayu Muktyuttonasana; One Hand Bound Standing Wind Relieving Half Forward Bend
Modification: binding around the shin, palm to the rib cage, foot resting on the thigh of the standing leg
Pose Type: standing one-legged balance, forward bend, binding

Drishti Point: Hastagrai or Hastagre (hands)
ल व र य



Standing Wind Relieving Intense Stretch Pose 1

Stiti Vayu Muktyuttonasana 1

(STI-ti VAH-yu muk-tew-ton-AHS-uh-nuh)

Also Known As: Nindra Vayu Muktyuttonasana; Standing Wind Relieving Half Forward Bend 1
Modification: chin away from the shin, binding on the inside of the thigh
Pose Type: standing one-legged balance, forward bend, binding
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
ल व य



ONE LEG STANDING BALANCE: KNEE BENT IN FRONT, BINDING, TWIST FORWARD BENDS

Standing Wind Relieving Intense Stretch Pose 2

Stiti Vayu Muktyuttonasana 2

(STI-ti VAH-yu muk-tew-ton-AHS-uh-nuh)

Also Known As: Nindra Vayu Muktyuttonasana; Standing Pose Dedicated to Sage Marichi (Nindra Marichyasana) and Standing Wind Relieving Full Forward Bend

Modification: chin away from the shin, binding around the shin
Pose Type: standing one-legged balance, forward bend, binding
Drishti Point: Padhayoragrai or Padayoragre (toes/feet)
ल व र य



Revolved Half Standing Wind Relieving Intense Stretch Pose

Parivritta Ardha Stiti Vayu Muktyuttonasana

(puh-ri-VRIT-tuh UHR-duh STI-ti VAH-yu muk-tew-ton-AHS-uh-nuh)

Also Known As: Parivritta Ardha Nindra Vayu Muktyuttonasana; Revolved Standing Wind Relieving Half Forward Bend
Pose Type: standing one-legged balance, forward bend, twist, binding
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
ल व र य



ONE LEG STANDING BALANCE: KNEE BENT IN FRONT—BACKBENDS

Hand to Knee Pose Inspired by Parvati’s Graceful Dance

Hasta Janu Lasyasana

(HUH-stuh JAH-nu lahs-YAHS-uh-nuh)

Modification: arm up over the head and parallel to the floor
Pose Type: standing one-legged balance, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Hastagrai or Hastagre (hands)
ल व र य ह ॐ



ONE LEG STANDING BALANCE: KNEE BENT IN FRONT—BACKBENDS—GRABBING ONTO THE ANKLE

Standing One-Legged Hero Pose

Stiti Eka Pada Virasana

(STI-ti EY-kuh PUH-duh veer-AHS-uh-nuh)
Also Known As: Nindra Eka Pada Virasana; Standing One-Legged Thunderbolt Pose (Nindra Eka Pada Vajrasana)
Modification: hand grabbing onto the foot, heel toward the glutes, shin parallel to the floor, other arm up to the sky
Pose Type: standing one-legged balance
Drishti Point: Nasagrai or Nasagre (nose)
ल व



Hand to Foot Pose Inspired by Parvati's Graceful Dance

Hasta Pada Lasyasana

(HUH-stuh PUH-duh lahs-YAHS-uh-nuh)

Modification: arm up over the head reaching to the sky
Pose Type: standing one-legged balance, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Hastagrai or Hastagre (hands)

ल व र य ह ॐ



ONE LEG STANDING BALANCE: KNEE BENT, KNEES IN LINE, FORWARD BENDS

Hand to Ankle Half Standing Wind Relieving Intense Stretch Pose

Hasta Kulpha Ardha Stiti Vayu Muktyuttonasana

(HUH-stuh kul-puh UHR-duh STI-ti VAH-yu muk-tew-ton-AHS-uh-nuh)

Also Known As: Hasta Kulpha Ardha Nindra Vayu Muktyuttonasana; Knee to Ear Half Standing Wind Relieving Intense Stretch Pose (Janu Karna Ardha Nindra Vayu Muktyuttonasana) and Hand to Ankle Standing Wind Relieving Half For-ward Bend
Modification: one hand grabbing onto the ankle, knee to the temple; other arm up to the sky, elbow bent
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)

ल र



Hand to Foot One-Legged Half Intense Stretch Pose

Hasta Pada Eka Pada Ardha Uttanasana

(HUH-stuh PUH-duh EY-kuh PUH-duh UHR-duh ut-tahn-AHS-uh-nuh)

Also Known As: Hand to Foot One-Legged Half Forward Bend
Modification: hand to the foot from the same side, heel to the sitting bone, other palm to the floor
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल



Hand to Foot One-Legged Intense Stretch Pose

Hasta Pada Eka Pada Uttanasana

(HUH-stuh PUH-duh EY-kuh PUH-duh ut-tahn-AHS-uh-nuh)

Also Known As: Hand to Foot One-Legged Full Forward Bend
Modification: hand to the foot on the same side, heel to the sitting bone; other palm to the floor
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल र य ह ॐ



One-Legged Intense Stretch Pose 1

Eka Pada Uttanasana 1

(EY-kuh PUH-du ut-tahn-AHS-uh-nuh)

Also Known As: One-Legged Full Forward Bend 1
Modification: leg bent, heel to the sitting bone, knees together; fingertips to the floor, arms extended behind the foot
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



One-Legged Intense Stretch Pose 2

Eka Pada Uttanasana 2

(EY-kuh PUH-du ut-tahn-AHS-uh-nuh)

Also Known As: One-Legged Full Forward Bend 2
Modification: leg bent, heel to the sitting bone, knees together; fingertips to the floor, arms extended behind the foot
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Pose Inspired by Shiva’s Vigorous Cycle of Life Dance

Tandavasana

(tahn-duh-VAHS-uh-nuh)

Modification: both knees bent, both elbows bent

Pose Type: standing one-legged balance

Drishti Point: Nasagrai or Nasagre (nose)



Pose Inspired by Shiva’s Vigorous Cycle of Life Dance

Tandavasana

(tahn-duh-VAHS-uh-nuh)

Modification: standing leg straight; other knee bent, foot to the inside of the knee; one forearm to the opposite knee, other arm extended up to the sky

Pose Type: standing one-legged balance, twist

Drishti Point: Hastagrai or Hastagre (hands)



Pose Inspired by Shiva’s Vigorous Cycle of Life Dance

Tandavasana

(tahn-duh-VAHS-uh-nuh)

Modification: standing leg straight, other knee bent at 90 degrees; both elbows bent, fingertips reaching to the sky; twisting to the outside of the body
Pose Type: standing one-legged balance, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



ONE LEG STANDING BALANCE: KNEE BENT TO THE SIDE

Pose Inspired by Shiva’s Vigorous Cycle of Life Dance

Tandavasana

(tahn-duh-VAHS-uh-nuh)

Modification: knee to the tricep on the same side; both elbows bent, one arm up over the head
Pose Type: standing one-legged balance, side bend
Drishti Point: Hastagrai or Hastagre (hands)



Pose Inspired by Shiva’s Vigorous Cycle of Life Dance

Tandavasana

(tahn-duh-VAHS-uh-nuh)

Modification: standing leg straight, other knee bent, toes pointing away from the head; fingertips to the temples

Pose Type: standing one-legged balance

Drishti Point: Nasagrai or Nasagre (nose)

लं वं यं



Extended Hand to Big Toe Pose 2 Prep.

Utthita Hasta Padangushtasana 2 Prep.

(UT-ti-tuh HUH-stuh puh-DAHNG-goosh-tahn-AHS-uh-nuh)

Also Known As: Extended Hand to Big Toe Pose B Prep. (Utthita Hasta Padangushtasana B Prep.)

Modification: knee bent

Pose Type: standing one-legged balance

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)

लं वं



Easy Tree Pose Modification

Sukha Vrikshasana

(SOOK-uh vrik-SHAHS-uh-nuh)

Modification: hands on the hips
1. toes to the floor
2. foot to the calf muscle

Pose Type: standing one-legged balance
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)





Tree Pose with Hands in Prayer

Vrikshasana Namaskar

(vrik-SHAHS-uh-nuh nuh-muhs-KAHR)

Pose Type: standing one-legged balance
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs), Nasagrai or Nasagre (nose)



Reverse Prayer Tree Pose

Viparita Namaskar Vrikshasana

(vi-puh-REE-tuh nuh-muhs-KAHR vrik-SHAHS-uh-nuh)

Also Known As: Back of the Body Prayer Tree Pose (Paschima Namaskara Vrikshasana)
Pose Type: standing one-legged balance
Drishti Point: Nasagrai or Nasagre (nose)



Revolved Half Bound Tree Pose

Parivritta Ardha Baddha Vrikshasana

(puh-ri-VRIT-tuh UHR-duh BUH-duh vrik-SHAHS-uh-nuh)

Pose Type: standing one-legged balance, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)

Tree Pose with Hands in Prayer

Vrikshasana Namaskar

(vrik-SHAHS-uh-nuh nuh-muhs-KAHR)

Modification: backbend
Pose Type: standing one-legged balance, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



Tree Pose

Vrikshasana

(vrik-SHAHS-uh-nuh)

Also Known As: Upward Hands Tree Pose (Urdhva Hasta Vrikshasana) or Pose Dedicated to Royal Sage Bhagiratha (Bhagirathasana)

Pose Type: standing one-legged balance, mild backbend

Drishti Point: Angusthamadhye or Angustha Ma Dyai (thumbs)

How to Perform the Pose:

1. Begin by standing in Mountain Pose (*Tadasana*). Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing. Find a still point on the floor to keep your gaze on. This will help you find and keep your balance.
2. Inhale and bring your weight onto the right foot. Exhale as you bend your left knee, and bring it out to the left side, opening the inside of your left hip. Keep your hips leveled and parallel to the floor (don't let your left hip go higher than your right). Keep the lower abdomen engaged to take out the compression (the arch) in the lower back.
3. Exhale as you place the sole of your left foot to the left calf muscle. Make sure the toes of your left foot are pointing to the floor.
4. On the next exhale, grab onto the left ankle with your left hand and slide the left foot up to the inside of your left thigh, keeping the toes of the left foot pointing to the floor. Avoid putting pressure on your right knee. Make sure to keep the left knee out to the side as you open the inside of your left hip.
5. Inhale as you reach both arms up over your head, fingertips pointing up to the sky. Keep them straight and shoulder-width apart. Make sure to lengthen your neck and keep your shoulder blades down your back.
6. Exhale and bring your gaze to your thumbs (Pose #1). You can experiment with rolling your head all the way back, feeling the stretch in the front of your neck (Pose #2).
7. If your shoulders are open, the neck is long, and your breathing is not constricted, you can bring your palms together on the exhale and look at your thumbs (Pose #3). With your palms pressed together, you can also experiment with rolling your head all the way back, feeling the stretch in the front of your neck (Pose #4).
8. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch. Exhale as you release the pose, come back to Mountain Pose (*Tadasana*), and repeat on the other side.

Modification: arms extended up over the head
1. arms shoulder width
2. arms shoulder width, head rolling back
3. palms together
4. palms together, head rolling back

vriksha = tree

1.



2.



3.



4.



Hand Position of Cow Face Pose in Tree Pose

Hasta Gomukhasana in Vrikshasana

(HUH-stuh go-muk-AHS-uh-nuh in vrik-SHAHS-uh-nuh)

Modification: Gomukhasana arms

Pose Type: standing one-legged balance

Drishti Point: Nasagrai or Nasagre (nose)

ल व य



Hand Position of the Pose Dedicated to Garuda in Tree Pose

Hasta Garudasana in Vrikshasana

(HUH-stuh GUH-ru-duh-AHS-uh-nuh in vrik-SHAHS-uh-nuh)

Pose Type: standing one-legged balance

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)

ल व



Sideways Tree Pose

Parshva Vrikshasana

(PAHRSH-vuh vrik-SHAHS-uh-nuh)

Modification: side bend toward the bent knee
Pose Type: standing one-legged balance, side bend
Drishti Point: Hastagrai or Hastagre (hands)



Upward One Hand Half Bound Lotus Tree Pose

Urdhva Eka Hasta Ardha Baddha Padma Vrikshasana

(OORD-vuh EY-kuh HUH-stuh UHR-duh BUH-duh PUHD-muh vrik-SHAHS-uh-nuh)

Pose Type: standing one-legged balance, binding
Drishti Point: Nasagrai or Nasagre (nose)



Revolved Half Bound Lotus Tree Pose

Parivritta Ardha Baddha Padma Vrikshasana

(puh-ri-VRIT-tuh UHR-duh BUH-duh PUHD-muh vrik-SHAHS-uh-nuh)

Pose Type: standing one-legged balance, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Hand to Foot Hand to Knee Tree Pose

Hasta Pada Hasta Janu Vrikshasana

(HUH-stuh PUH-duh HUH-stuh JAH-nu vrik-SHAHS-uh-nuh)

Modification: grabbing onto the foot and the knee, knee to the outside
Pose Type: standing one-legged balance
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Hand to Foot Hand to Knee Tree Pose

Hasta Pada Hasta Janu Vrikshasana

(HUH-stuh PUH-duh HUH-stuh JAH-nu vrik-SHAHS-uh-nuh)

Modification: backbend, grabbing onto the foot and the knee, knee to the outside, looking straight ahead
Pose Type: standing one-legged balance, backbend
Drishti Point: Nasagrai or Nasagre (nose)



Hand to Foot Hand to Knee Toppling Tree Pose

Hasta Pada Hasta Janu Patan Vrikshasana

(HUH-stuh PUH-duh HUH-stuh JAH-nu PUH-tuhn vrik-SHAHS-uh-nuh)

Modification: grabbing onto the foot and the shin, knee to the outside
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



ONE LEG STANDING BALANCE: LEG STRAIGHT IN FRONT

Both Hands to Foot Pose

Dwi Hasta Padasana

(dwi-huh-stuh puh-DAHS-uh-nuh)

Also Known As: Raised Up Leg and Back Stretch Pose (Utthita Eka Pada Paschimottanasana), Standing Head to Knee Pose (Dandayamana-Janushirasana)
Modification: chin to the shin
Pose Type: standing one-legged balance, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Padayoragrai or Padayoragre (toes/feet)



Extended One Foot Pose

Utthita Ekapadasana

(UT-ti-tuh EY-kuh-puh-DAHS-uh-nuh)

Also Known As: Extended Hand to Big Toe Pose D (Utthita Hasta Padangushtasana D; found in Ashtanga Yoga System)
Modification: hands on the hips
Pose Type: standing one-legged balance
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Extended Hand to Big Toe Pose 1

Utthita Hasta Padangushtasana 1

(UT-ti-tuh HUH-stuh puhd-ahng-goosh-TAHS-uh-nuh)

Also Known As: Extended Hand to Big Toe Pose A (Utthita Hasta Padangushtasana A)
Modification: lifted leg in front of the body
Pose Type: standing one-legged balance
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Extended Pose Dedicated to Trivikrama—Conqueror of the Three Worlds (Vishnu)

Utthita Trivikramasana

(UT-ti-tuh tri-vi-kruh-MAHS-uh-nuh)

Also Known As: Extended Hand to Foot Stretch Pose (Utthita Hastha Pada Uttanasana)
Modification: knee away from the shoulder
Pose Type: standing one-legged balance
Drishti Point: Nasagrai or Nasagre (nose)



ONE LEG STANDING BALANCE: LEG STRAIGHT TO THE SIDE

Pose Dedicated to Trivikrama—Conqueror of the Three Worlds (Vishnu)

Trivikramasana

(tri-vi-kruh-MAHS-uh-nuh)

Also Known As: Leg to the Side Pose Dedicated to Trivikrama—Conqueror of the Three Worlds (Vishnu) (Parshva Pada Trivikramasana)
Modification: arm wrapping around the leg on the same side
Pose Type: standing one-legged balance
Drishti Point: Nasagrai or Nasagre (nose)
ल व



Rising Standing Sundial Pose

Utthita Stiti Surya Yantrasana

(UT-ti-tuh STI-ti SOOR-yuh yuhn-TRAHS-uh-nuh)
Also Known As: Utthita Nindra Surya Yantrasana
Modification: side bend
Pose Type: standing one-legged balance, side bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व र य



Pose Dedicated to Trivikrama—Conqueror of the Three Worlds (Vishnu)

Trivikramasana

(tri-vi-kruh-MAHS-uh-nuh)

Also Known As: Leg to the Side Pose Dedicated to Trivikrama—Conqueror of the Three Worlds (Vishnu) (Parshva Pada Trivikramasana)

Modification: both hands grabbing onto the leg, shoulder to the back of the knee, looking to the side

Pose Type: standing one-legged balance, twist

Drishti Point: Urdhva or Antara Drishti (up to the sky)



Pose Dedicated to Trivikrama—Conqueror of the Three Worlds (Vishnu)

Trivikramasana

(tri-vi-kruh-MAHS-uh-nuh)

Also Known As: Leg to the Side Pose Dedicated to Trivikrama—Conqueror of the Three Worlds (Vishnu) (Parshva Pada Trivikramasana)

Modification: one hand grabbing onto the opposite foot, shoulder to the front of the knee, other arm straight out to the side, looking straight ahead

Pose Type: standing one-legged balance

Drishti Point: Nasagrai or Nasagre (nose)



Extended Hand to Big Toe Pose 2

Utthita Hasta Padangushtasana 2

(UT-ti-tuh HUH-stuh puhd-ahng-goosh-TAHS-uh-nuh)

Also Known As: Extended Hand to Big Toe Pose B (Utthita Hasta Padangushtasana B), Standing Leg Going to the Side Pose Prep. (Utthita Parshvasahita Prep.)
Pose Type: standing one-legged balance
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Half Bound Pose Dedicated to Trivikrama—Conqueror of the Three Worlds (Vishnu)

Ardha Baddha Trivikramasana *(UHR-duh BUH-duh tri-vi-kruh-MAHS-uh-nuh)*
Also Known As: Leg to the Side Half Bound Pose Dedicated to Trivikrama—Conqueror of the Three Worlds (Vishnu) (Parshva Pada Ardha Baddha Trivikramasana)
Modification: one arm wrapping around the leg on the same side, other arm behind the back, hand to the inside of the thigh
Pose Type: standing one-legged balance, binding
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Bird of Paradise Pose

Svarga Dvijasana

(SVUHR-guh dwij-AHS-uh-nuh)

Pose Type: standing one-legged balance, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Revolved Extended Hand to Foot Pose

Parivritta Utthita Pada Hastasana

(puh-ri-VRIT-tuh UT-ti-tuh PUH-duh huh-STAHS-uh-nuh)

Also Known As: Revolved Hand to Big Toe Pose (Parivritta Hasta Padangushtasana)
Pose Type: standing one-legged balance, twist
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Revolved Bird of Paradise Pose

Parivritta Svarga Dvijasana

(puh-ri-VRIT-tuh SVUHR-guh dwij-AHS-uh-nuh)

Also Known As: Raised and Revolved Bound Leg Pose (Utthita Parivritta Baddha Padasana)
Pose Type: standing one-legged balance, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
ल व



ONE LEG STANDING BALANCE: BOTH LEGS STRAIGHT—BACKBEND

Lord of the Dance Pose

Natarajasana

(NAH-tuh-rahj-AHS-uh-nuh)

Modification: under-head grip with one hand on the same side; both legs straight
Pose Type: standing one-legged balance, backbend
Drishti Point: Hastagrai or Hastagre (hands)
ल व र य ह



Pose Dedicated to Yogi Yogananda

Yoganandasana

(yo-gah-nuhn-DAHS-uh-nuh)

Also Known As: Pose Dedicated to Vishnu Devananda (Vishnu Devanandasana)
Modification: both legs straight, grabbing onto the back leg with an under-head grip
Pose Type: standing one-legged balance, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Yogi Sivananda’s Pose

Sivanandasana

(shiv-ah-nuhn-DAHS-uh-nuh)

Modification: grabbing onto the shin
Pose Type: standing one-legged balance, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



ONE LEG STANDING BALANCE: BOTH LEGS STRAIGHT—FORWARD BEND

Pose Dedicated to Sage Sundaranandar

Sundaranandarasana

(sun-duh-RAH-nuhn-duh-RAHS-uh-nuh)

Modification: palms to the floor, forehead to the shin
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
लं वं रं यं हं ॐ



One Leg Stretched Upward Pose

Urdhva Prasarita Ekapadasana

(OORD-vuh pruh-SAH-ri-tuh ey-kuh-puhd-AHS-uh-nuh)

Modification: one hand grabbing onto the ankle on the same side, palm of the other hand to the floor, head away from the shin
Pose Type: standing one-legged balance, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet) or Nasagrai or Nasagre (nose)
लं वं रं यं हं



One Leg Stretched Upward Pose

Urdhva Prasarita Ekapadasana

(OORD-vuh pruh-SAH-ri-tuh ey-kuh-puhd-AHS-uh-nuh)

Modification: both hands grabbing onto the ankle, forehead to the shin
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose) if chin touches the shin



Unsupported One Leg Stretched Upward Pose

Niralamba Urdhva Prasarita Ekapadasana

(nir-AH-luhm-buh OORD-vuh pruh-SAH-ri-tuh ey-kuh-puhd-AHS-uh-nuh)

Modification: arms straight along the sides of the torso, fingertips to the sky
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Padayoragrai or Padayoragre (toes/feet), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Bound Unsupported One Leg Stretched Upward Pose

Baddha Niralamba Urdhva Prasarita Ekapadasana

(BUH-duh nir-AH-luhm-buh OORD-vuh pruh-SAH-ri-tuh ey-kuh-puhd-AHS-uh-nuh-uh-nuh)

Pose Type: standing one-legged balance, forward bend, binding

Drishti Point: Nasagrai or Nasagre (nose), Padayoragrai or Padayoragre (toes/feet), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



ONE LEG STANDING BALANCE: LEG STRAIGHT TO THE SIDE—HALF FORWARD BEND

Bowing with Respect Extended Hand to Big Toe Pose 2

Nantum Utthita Hasta Padangushtasana 2

(NUHN-tum UT-ti-tuh HUH-stuh puhd-ahng-goosh-TAHS-uh-nuh)

Modification: forward bend, grabbing onto the big toe of the lifted leg; other arm extended to the side parallel to the floor

Pose Type: standing one-legged balance, forward bend

Drishti Point: Nasagrai or Nasagre (nose)



Bowing with Respect Both Hands Extended to Big Toes Pose 2

Nantum Utthita Dwi Hasta Padangushtasana 2

(NUHN-tum UT-ti-tuh DWI-huh-stuh puhd-ahng-goosh-TAHS-uh-nuh-uh-nuh)

Modification: forward bend, grabbing onto the big toes with both hands, leg lifted higher than the hip
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व ह



Bowing with Respect Half Bound Hand to Leg Pose

Nantum Ardha Baddha Hasta Padasana

(NUHN-tum UHR-duh BUH-duh HUH-stuh puhd-AHS-uh-nuh)

Modification: half forward bend
Pose Type: standing one-legged balance, forward bend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व ह ॐ



ONE LEG STANDING BALANCE: STANDING KNEE BENT & STRAIGHT—FORWARD BEND

Bowing with Respect Bird of Paradise Pose Prep.

Nantum Svarga Dvijasana Prep.

(NUHN-tum SVUHR-guh dwij-AHS-uh-nuh)

Modification: 1. standing leg bent; other knee to the back of the shoulder, leg bent
2. standing leg bent; other knee to the back of the shoulder, leg straight
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व ह

1.



2.



Bowing with Respect Bird of Paradise Pose

Nantum Svarga Dvijasana

(NUHN-tum SVUHR-guh dwij-AHS-uh-nuh)

Modification: half forward bend

Pose Type: standing one-legged balance, forward bend, binding

Drishti Point: Nasagrai or Nasagre (nose)



Benu Bird Pose 2

Benvasana 2

(ben-VAHS-uh-nuh)

Modification: both knees bent, chest toward the quadriceps, arms open to the sides

Pose Type: standing one-legged balance, forward bend

Drishti Point: Nasagrai or Nasagre (nose)



ONE LEG STANDING BALANCE: ONE LEG STRAIGHT TO THE BACK, HANDS TO THE FLOOR

Half One Leg Stretched Upward Pose

Ardha Urdhva Prasarita Ekapadasana

(UHR-duh OORD-vuh pruh-SAH-ri-tuh ey-kuh-puh-DAHS-uh-nuh)

Also Known As: One Leg Stretched Upwards Pose Prep. (Urdhva Prasarita Ekapadasana Prep.), Warrior 3 Prep. (Virabhadrasana 3 Prep.)
Modification: fingertips to the floor
Pose Type: standing, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One Leg Stretched Upward Pose Prep.

Urdhva Prasarita Ekapadasana Prep.

(OORD-vuh pruh-SAH-ri-tuh ey-kuh-puh-DAHS-uh-nuh)

Modification: standing leg bent, shoulder to the back of the knee, arms extended to the back
Pose Type: standing, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Moon Pose Prep.

Ardha Chandrasana Prep.

(UHR-duh chuhn-DRAHS-uh-nuh)

Modification: with yoga block prop, hand on the hip
Pose Type: standing one-legged balance, forward bend
Drishti Point: Hastagrai or Hastagre (hands)



Half Moon Pose

Ardha Chandrasana

(UHR-duh chuhn-DRAHS-uh-nuh)

Pose Type: standing one-legged balance, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



ONE LEG STANDING BALANCE: ONE LEG STRAIGHT TO THE BACK—HANDS OFF THE FLOOR

Warrior 3

Virabhadrasana 3

(VEER-uh buh-DRAHS-uh-nuh)

Also Known As: Bird Pose A (Dikasana A)
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Warrior 3

Virabhadrasana 3

(VEER-uh buh-DRAHS-uh-nuh)

Also Known As: Bird Pose B (Dikasana B)
Modification: arms extended to the back and parallel to the floor
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Reverse Prayer Warrior 3

Viparita Namaskar Virabhadrasana 3

(vi-puh-REE-tuh nuh-muhs-KAHR VEER-uh buh-DRAHS-uh-nuh)

Also Known As: Back of the Body Prayer Warrior 3 (Paschima Namaskara Virabhadrasana 3)
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Hand Position of the Pose Dedicated to Garuda in Warrior 3

Hasta Garudasana in Virabhadrasana 3

(HUH-stuh guh-ru-DAHS-uh-nuh in VEER-uh-buh-DRAHS-uh-nuh)

Pose Type: standing one-legged balance, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Half Lotus Warrior 3

Ardha Padma Virabhadrasana 3

(UHR-duh PUHD-muh VEER-uh-buh-DRAHS-uh-nuh-uh-nuh)

Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)

Half Moon Pose

with Hands in Prayer

Ardha Chandrasana Namaskar

(UHR-duh chuhn-DRAHS-uh-nuh nuh-muhs-KAHR)

Pose Type: standing one-legged balance, forward bend

Drishti Point: 1. Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) 2. Urdhva or Antara Drishti (up to the sky)

How to Perform the Pose:

1. Begin by doing Extended Triangle Pose (*Utthita Trikonasana*) with the left foot in front and your left hand to the floor outside the left foot (either on the fingertips or with the palm flat on the floor). Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale as you slide your left palm out to the front while bending your left knee. Experiment with the distance to find your balance.
3. Inhale and lift your right foot off the floor until your right leg is parallel to the floor. Keep it straight and reaching away from your head. Straighten your standing left leg.
4. Exhale and rotate your chest to the side so that your shoulders stack one on top of the other.
5. On your next exhale, lift your left arm up off the floor and bring your hands into prayer at the center of your chest.
6. You can either find a gazing point on the floor that is not moving to help keep your balance (Pose #1) or challenge yourself by looking up to the sky (Pose #2).
7. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch. Exhale, lower your right foot to the floor, coming back into Extended Triangle Pose (*Utthita Trikonasana*), and repeat on the other side.

Modification:

1. looking down
2. looking up to the sky

ardha = half

chandra = moon

namaskar = greeting with hands in Anjali Mudra (hands in prayer)

1.



2.



Reverse Prayer Half Moon Pose

Viparita Namaskar Ardha Chandrasana

(vi-puh-REE-tuh nuh-muhs-KAHR UHR-duh chuhn-DRAHS-uh-nuh)

Also Known As: Back of the Body Prayer Half Moon Pose (Paschima Namaskara Ardha Chandrasana)
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Bound Half Moon Pose

Baddha Ardha Chandrasana

(BUH-duh UHR-duh chuhn-DRAHS-uh-nuh)

Pose Type: standing one-legged balance, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose) or Padayoragrai or Padayoragre (toes/feet)



Revolved Bound Half Moon Pose

Parivritta Baddha Ardha Chandrasana

(vi-puh-REE-tuh BUH-duh UHR-duh chuhn-DRAHS-uh-nuh)

Modification: looking up to the sky

Pose Type: standing one-legged balance, forward bend, twist, binding

Drishti Point: Urdhva or Antara Drishti (up to the sky)



Half Firelog Pose in Half Moon Pose Prep.

Ardha Agnistambhasana in Ardha Chandrasana Prep.

(UHR-duh uhg-ni-stuhm-BAHS-uh-nuh in UHR-duh chuhn-DRAHS-uh-nuh)

Modification: foot on top of the knee, palm to the lower back

Pose Type: standing one-legged balance, forward bend

Drishti Point: Hastagrai or Hastagre (hands)



Half Bound Lotus Half Moon Pose Prep.

Ardha Baddha Padma Ardha Chandrasana Prep.

(UHR-duh BUH-duh PUHD-muh UHR-duh chuhn-DRAHS-uh-nuh)

Modification: arm behind the back, binding to the inside of the thigh of the leg in Half Lotus

Pose Type: standing one-legged balance, forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Leg Position of Half Cow Face Pose in Half Moon Pose Prep.

Pada Ardha Gomukhasana in Ardha Chandrasana Prep.

(PUH-duh UHR-duh go-muk-AHS-uh-nuh in UHR-duh chuhn-DRAHS-uh-nuh)
Also Known As: One-Legged Cow Face Pose in Half Moon Pose Prep. (Eka Pada Gomukhasana in Ardha Chandrasana Prep.)
Pose Type: standing one-legged balance, forward bend, twist
Drishti Point: Hastagrai or Hastagre (hands)



ONE-LEGGED STANDING BALANCE: HALF LOTUS

Half Bound Lotus Intense Stretch Pose Prep.

Ardha Baddha Padmottanasana Prep.

(UHR-duh BUH-duh puhd-mo-tahn-AHS-uh-nuh)
Also Known As: Half Bound Lotus Half Forward Bend Prep., Half Lotus Half Intense Stretch Pose

(Ardha Padma Ardha Uttanasana), Half Lotus Half Forward Bend
Modification: half forward bend, fingertips of both hands to the floor
Pose Type: standing, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



Half Bound Lotus Intense Stretch Pose Prep.

Ardha Baddha Padmottanasana Prep.

(UHR-duh BUH-duh puhd-mo-tahn-AHS-uh-nuh)

Also Known As: Half Bound Lotus Half Forward Bend
Modification: half forward bend
Pose Type: standing one-legged balance, forward bend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



Half Bound Lotus Intense Stretch Pose

Ardha Baddha Padmottanasana

(UHR-duh BUH-duh puhd-mo-tahn-AHS-uh-nuh)

Also Known As: Half Bound Lotus Full Forward Bend
Pose Type: standing one-legged balance, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य



GARUDA LEGS

Pose Dedicated to Garuda

Garudasana

(guh-ru-DAHS-uh-nuh)
Also Known As: Eagle Pose
Modification: hands intertwined in front, low stance
Pose Type: standing one-legged balance
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व



Reverse Heart Chakra Seal in Leg Position of the Pose Dedicated to Garuda

Viparita Anahata Chakra Mudra in Pada Garudasana

(vi-puh-REE-tuh un-AH-huh-tuh chuh-kruh MU-druh in PUH-duh guh-ru-DAHS-uh-nuh)

Also Known As: Reverse Heart Chakra Seal in Leg Position of the Eagle Pose

Pose Type: standing one-legged balance

Drishti Point: Nasagrai or Nasagre (nose)



Pose Dedicated to Garuda

Garudasana

(guh-ru-DAHS-uh-nuh)

Also Known As: Eagle Pose

Modification: elbows to the knees

Pose Type: standing one-legged balance, forward bend

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Leg Position of the Pose Dedicated to Garuda

Pada Garudasana

(PUH-duh guh-ru-DAHS-uh-nuh)

Also Known As: Leg Position of the Eagle Pose
Modification: arms straight out to the sides behind the back
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य



Revolved Bound Leg Position of the Pose Dedicated to Garuda

Parivritta Baddha Pada Garudasana

(puh-ri-VRIT-tuh BUH-duh PUH-duh guh-ru-DAHS-uh-nuh)
Also Known As: Revolved Bound Leg Position of the Eagle Pose
Pose Type: standing one-legged balance, forward bend, binding, twist
Drishti Point: Nasagrai or Nasagre (nose)
ल व र



Hands Bound Leg Position of the Pose Dedicated to Garuda

Baddha Hasta Pada Garudasana

(BUH-duh HUH-stuh PUH-duh guh-ru-DAHS-uh-nuh)
Also Known As: Hands Bound Leg Position of the Eagle Pose
Pose Type: standing one-legged balance, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

लं वं रं यं



ONE-LEGGED SQUATS: TWISTS

Revolved Half Standing Wind Relieving Intense Stretch Pose

Parivritta Ardha Stiti Vayu Muktyuttonasana

(puh-ri-VRIT-tuh UHR-duh STI-ti VAH-yu muk-tew-to-NAHS-uh-nuh)

Also Known As: Parivritta Ardha Nindra Vayu Muktyuttonasana; Revolved Standing Wind Relieving Half Forward Bend

Modification: knees together; elbow to the opposite knee, other arm extended to the back

Pose Type: standing one-legged balance, forward bend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)

लं हं ॐ



Revolved Half Standing Wind Relieving Intense Stretch Pose with Hands in Prayer

Parivritta Ardha Stiti Vayu Muktyuttonasana Namaskar

(puh-ri-VRIT-tuh UHR-duh STI-ti VAH-yu muk-tew-to-NAHS-uh-nuh nuh-muhs-KAHR)

Also Known As: Parivritta Ardha Nindra Vayu Muktyuttonasana Namaskar; Revolved Standing Wind Relieving Half Forward Bend with Hands in Prayer
Modification: back leg crossed under the front leg
Pose Type: standing one-legged balance, forward bend, twist
Drishti Point: Nasagrai or Nasagre (nose)



Bound Revolved Half Standing Wind Relieving Intense Stretch Pose

Baddha Parivritta Ardha Stiti Vayu Muktyuttonasana

(BUH-duh puh-ri-VRIT-tuh UHR-duh STI-ti VAH-yu muk-tew-to-NAHS-uh-nuh)

Also Known As: Baddha Parivritta Ardha Nindra Vayu Muktyuttonasana; Bound Revolved Standing Wind Relieving Half Forward Bend
Pose Type: standing one-legged balance, forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



ONE-LEGGED SQUATS: KNEES IN LINE—HEEL TO THE SITTING BONES—GRABBING ONTO THE ANKLE

Revolved One Hand to Foot Half Standing Wind Relieving Intense Stretch Pose

Parivritta Eka Hasta Pada Ardha Stiti Vayu Muktyuttonasana

(puh-ri-VRIT-tuh EY-kuh HUH-stuh PUH-duh UHR-duh STI-ti VAH-yu muk-tew-to-NAHS-uh-nuh)

Also Known As: Parivritta Eka Hasta Pada Ardha Nindra Vayu Muktyuttonasana; Revolved One Hand to Foot Standing Wind Relieving Half Forward Bend
Modification: knees together; elbow to the opposite knee, other hand grabbing onto the ankle
Pose Type: standing one-legged balance, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



Both Hands to Foot Half Standing Wind Relieving Intense Stretch Pose

Dwi Hasta Pada Ardha Stiti Vayu Muktyuttonasana

(DWI-huh-stuh PUH-duh UHR-duh STI-ti VAH-yu muk-to-NAHS-uh-nuh)

Also Known As: Dwi Hasta Pada Ardha Nindra Vayu Muktyuttonasana
Pose Type: standing one-legged balance, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One Hand to Foot Tip Toe Half Standing Wind Relieving Intense Stretch Pose

Eka Hasta Pada Prapada Ardha Stiti Vayu Muktyuttonasana

(EY-kuh HUH-stuh PUH-duh PRUH-puh-duh UHR-duh STI-ti VAH-yu muk-to-NAHS-uh-nuh)

Also Known As: Eka Hasta Pada Prapada Ardha Nindra Vayu Muktyuttonasana
Pose Type: standing one-legged balance, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Both Hands to Foot Tip Toe Half Standing Wind Relieving Intense Stretch Pose

Dwi Hasta Pada Prapada Ardha Stiti Vayu Muktyuttonasana

(DWI-huh-stuh PUH-duh PRUH-puh-duh UHR-duh STI-ti VAH-yu muk-to-NAHS-uh-nuh)

Also Known As: Dwi Hasta Pada Prapada Ardha Nindra Vayu Muktyuttonasana
Pose Type: standing one-legged balance, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



ONE-LEGGED SQUATS: TWISTS—GRABBING ONTO THE FOOT, LEG STRAIGHT IN FRONT

One-Legged Pose Dedicated to Yogi Shankara

Eka Pada Shankarasana

(EY-kuh PUH-duh shunk-uhr-AHS-uh-nuh)

Modification: forehead to the shin

Pose Type: standing one-legged balance, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

लं रं यं हं ॐ



Revolved One-Legged Pose Dedicated to Yogi Shankara

Parivritta Eka Pada Shankarasana

(puh-ri-VRIT-tuh EY-kuh PUH-duh shunk-uhr-AHS-uh-nuh)

Modification: twisting to the inside of the leg

Pose Type: standing one-legged balance, forward bend, twist, side bend

Drishti Point: Urdhva or Antara Drishti (up to the sky)

लं रं



Revolved One-Legged Pose Dedicated to Yogi Shankara

Parivritta Eka Pada Shankarasana

(puh-ri-VRIT-tuh EY-kuh PUH-duh shunk-uhr-AHS-uh-nuh)

Modification: twisting to the outside of the leg
Pose Type: standing one-legged balance, forward bend, twist, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)
🔴 🟡



ONE-LEGGED SQUATS: FOOT ON TOP OF THE KNEE

One-Legged Fierce Pose 1

Eka Pada Utkatasana 1

(EY-kuh PUH-duh ut-kuh-TAHS-uh-nuh)

Also Known As: One-Legged Prayer Fierce Pose (Eka Pada Namaskar Utkatasana)
Modification: hands in Anjali Mudra (Hands in Prayer)
Pose Type: standing one-legged balance
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)

ल व



One-Legged Fierce Pose 2

Eka Pada Utkatasana 2

(EY-kuh PUH-duh ut-kuh-TAHS-uh-nuh)

Also Known As: Both Hands to Ankle One-Legged Fierce Pose (Dwi Hasta Kulpa Eka Pada Utkatasana)
Modification: both hands to the ankle
Pose Type: standing one-legged balance, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)
ल व र ह ॐ



One-Legged Fierce Pose 3

Eka Pada Utkatasana 3

(EY-kuh PUH-duh ut-kuh-TAHS-uh-nuh)

Also Known As: Arms Spread One-Legged Fierce Pose (Prasarita Hasta Eka Pada Utkatasana)
Modification: arms straight out to the sides, forward bend
Pose Type: standing one-legged balance, forward bend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



One-Legged Fierce Pose 4

Eka Pada Utkatasana 4

(EY-kuh PUH-duh ut-kuh-TAHS-uh-nuh)

Also Known As: Hands Bound One-Legged Fierce Pose (Baddha Hasta Eka Pada Utkatasana)
Modification: hands bound behind the back, forward bend
Pose Type: standing one-legged balance, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



ONE-LEGGED SQUATS: HALF LOTUS

Half Bound Lotus Fierce Pose

Ardha Baddha Padma Utkatasana

(UHR-duh BUH-duh PUHD-muh ut-kuh-TAHS-uh-nuh)

Modification: hips low
Pose Type: standing one-legged balance, binding
Drishti Point: Hastagrai or Hastagre (hands)
लं वं



STANDING: FORWARD BEND—FOOT TO KNEE & FOOT TO ARMPIT

Baby Cradle Pose in Intense Stretch Pose

Hindolasana in Uttanasana

(hin-do-LAHS-uh-nuh in ut-tahn-AHS-uh-nuh)
Also Known As: Baby Cradle Pose in Full Forward Bend
Modification: foot behind the knee of the standing leg
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
लं वं रं यं हं ॐ



Standing Bound Yogic Staff Pose

Stiti Baddha Yoganandasana

(STI-ti BUH-duh yo-gah-nuhn-DAHS-uh-nuh)

Also Known As: Nindra Baddha Yoganandasana
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व ह



Yogic Staff Intense Stretch Pose

Yogadananda Uttanasana

(yo-gah-nuhn-duh ut-tahn-AHS-uh-nuh)
Also Known As: Yogic Staff Full Forward Bend
Pose Type: standing one-legged balance, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose)
ल व र य ह



STANDING HALF FORWARD BEND: LEGS CROSSED

Hand Position of the Pose Dedicated to Garuda in Sideways Half Intense Stretch Pose

Hasta Garudasana in Parshva Ardha Uttanasana

(HUH-stuh guh-ru-DAHS-uh-nuh in PAHRSH-vuh UHR-duh ut-tahn-AHS-uh-nuh)

Also Known As: Hand Position of the Pose Dedicated to Garuda in Sideways Legs Crossed Half Forward Bend

Modification: legs crossed

Pose Type: standing, forward bend, twist

Drishti Point: Hastagrai or Hastagre (hands)



STANDING HALF FORWARD BEND: ONE KNEE BENT

Reverse Prayer Uneven Legs Half Intense Stretch Pose

Viparita Namaskar Vishama Pada Ardha Uttanasana

(vi-puh-REE-tuh nuh-muhs-KAHR VISH-uh-muh PUH-duh UHR-duh ut-tahn-AHS-uh-nuh)

Also Known As: Back of the Body Prayer Uneven Legs Half Intense Stretch Pose (Paschima Namaskara Vishama Pada Ardha Uttanasana), Reverse Prayer Uneven Legs Half Forward Bend

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)



Bound Uneven Legs Half Intense Stretch Pose

Baddha Vishama Pada Ardha Uttanasana

(BUH-duh VISH-uh-muh PUH-duh UHR-duh ut-tahn-AHS-uh-nuh)

Also Known As: Bound Uneven Legs Half Forward Bend

Pose Type: standing, forward bend, binding

Drishti Point: Padayoragrai or Padayoragre (toes/feet)

ल व र य हं



STANDING HALF FORWARD BEND: ONE KNEE BENT—TWISTS & BINDING

Revolved Uneven Legs Half Intense Stretch Pose

Parivritta Vishama Pada Ardha Uttanasana

(puh-ri-VRIT-tuh VISH-uh-muh PUH-duh UHR-duh ut-tahn-AHS-uh-nuh)

Also Known As: Revolved Uneven Legs Half Forward Bend

Modification: one hand to the floor, other hand up to the sky; looking down

Pose Type: standing, forward bend, twist

Drishti Point: Hastagrai or Hastagre (hands)

ल व



Reverse Prayer Revolved Uneven Legs Half Intense Stretch Pose

Viparita Namaskar Parivritta Vishama Pada Ardha Uttanasana

(vi-puh-REE-tuh nuh-muhs-KAHR puh-ri-VRIT-tuh VISH-uh-muh PUH-duh UHR-duh ut-tahn-AHS-uh-nuh)

Also Known As: Back of the Body Prayer Revolved Uneven Legs Half Intense Stretch Pose (Paschima Namaskara Ardha Parivritta Uttanasana), Reverse Prayer Revolved Uneven Legs Half Forward Bend

Pose Type: standing, forward bend, twist

Drishti Point: Urdhva or Antara Drishti (up to the sky)



Hands Bound Revolved Uneven Legs Half Intense Stretch Pose

Baddha Hasta Parivritta Vishama Pada Ardha Uttanasana

(BUH-duh HUH-stuh puh-ri-VRIT-tuh VISH-uh-muh PUH-duh UHR-duh ut-tahn-AHS-uh-nuh)

Also Known As: Hands Bound Revolved Uneven Legs Half Forward Bend

Pose Type: standing, forward bend, twist

Drishti Point: Urdhva or Antara Drishti (up to the sky)



Bound Revolved Half Intense Stretch Pose

Baddha Parivritta Ardha Uttanasana

(BUH-duh puh-ri-VRIT-tuh UHR-duh ut-tahn-AHS-uh-nuh)

Also Known As: Bound Revolved Half Forward Bend

Pose Type: standing, forward bend, twist, binding

Drishti Point: Urdhva or Antara Drishti (up to the sky)



STANDING HALF FORWARD BEND: HANDS OFF THE FLOOR

Arms Extended Half Intense Stretch Pose

Utthita Hasta Ardha Uttanasana

(UT-ti-tuh HUH-stuh UHR-duh ut-tahn-AHS-uh-nuh)

Also Known As: Arms Extended Half Forward Bend

Modification: palms pressed together

Pose Type: standing, forward bend

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs), Nasagrai or Nasagre (nose)



STANDING HALF FORWARD BEND: HANDS ON THE FLOOR

Half Foot Big Toe Pose

Ardha Padangushtasana

(UHR-duh puhd-ahng-goosh-TAHS-uh-nuh)

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)



Sideways Half Intense Stretch Pose

Parshva Ardha Uttanasana

(PAHRSH-vuh UHR-duh ut-tahn-AHS-uh-nuh)

Also Known As: Sideways Half Forward Bend

Modification: fingers interlocked, palms to the floor on the outside edge of the foot

Pose Type: standing, forward bend, side bend, twist

Drishti Point: Hastagrai or Hastagre (hands)



STANDING HALF FORWARD BEND: HANDS ON THE FLOOR—HEELS UP

Tip Toe Half Intense Stretch Pose

Prapada Ardha Uttanasana

(PRUH-puh-duh UHR-duh ut-tahn-AHS-uh-nuh)

Also Known As: Tip Toe Half Forward Bend and Downward Facing Tree Pose Prep. (Adho Mukha Vrikshasana Prep.)
Pose Type: standing, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Tip Toe Intense Stretch Pose

Prapada Uttanasana

(PRUH-puh-duh ut-tahn-AHS-uh-nuh)

Also Known As: Tip Toe Full Forward Bend
Modification: arms straight and pointing to the back, both arms on the inside of the legs
1. head up
2. forehead toward the shins
Pose Type: standing, forward bend
Drishti Point: 1. Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) 2. Nasagrai or Nasagre (nose)





STANDING FULL FORWARD BEND: BALLET TOES

Intense Ankle Stretch Intense Stretch Pose 1

Uttana Kulpa Uttanasana 1

(ut-TAHN-uh KUL-puh ut-tahn-AHS-uh-nuh)

Also Known As: Intense Ankle Stretch Forward Bend
Modification: legs together
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल



Intense Ankle Stretch Intense Stretch Pose 2

Uttana Kulpa Uttanasana 2

(ut-TAHN-uh KUL-puh ut-tahn-AHS-uh-nuh)

Also Known As: Intense Ankle Stretch Forward Bend
Modification: scissor legs
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व ह



STANDING FULL FORWARD BEND: ONE-LEGGED

Extended One Hand to Foot Intense Stretch Pose 1

Utthita Eka Hasta Pada Uttanasana 1

(UT-ti-tuh EY-kuh HUH-stuh PUH-duh ut-tahn-AHS-uh-nuh)

Also Known As: Extended One Hand to Foot Full Forward Bend 1
Modification: hand grabbing the foot on the same side
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)

ल व ह ॐ



Extended One Hand to Foot Intense Stretch Pose 2

Utthita Eka Hasta Pada Uttanasana 2

(UT-ti-tuh EY-kuh HUH-stuh PUH-duh ut-tahn-AHS-uh-nuh)

Also Known As: Extended One Hand to Foot Full Forward Bend 2
Modification: hand grabbing the foot on the opposite side
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



STANDING FULL FORWARD BEND: HANDS TO THE FLOOR & HANDS TO THE BACK OF THE LEGS

Intense Stretch Pose

Uttanasana

(ut-tahn-AHS-uh-nuh)

Also Known As: Full Forward Bend
Modification: palms to the floor, fingers pointing to the back
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Intense Stretch Pose

Uttanasana

(ut-tahn-AHS-uh-nuh)

Also Known As: Full Forward Bend and Standing Turtle Pose (Nindra Kurmasana)
Modification: feet hip width apart, grabbing onto the calves, elbows bent
Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

लं



Intense Stretch Pose

Uttanasana

(ut-tahn-AHS-uh-nuh)

Also Known As: Full Forward Bend and Locked Elbows Standing Intense Stretch Pose (Baddha Padahastasana)
Modification: grabbing onto triceps behind the calves
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)

लं यं हं



STANDING FULL FORWARD BEND: GRABBING ONTO THE FEET

Foot Big Toe Pose

Padangushtasana

(puh-ahng-goosh-TAHS-uh-nuh)

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)
ल



Hand Under Foot Pose

Pada Hastasana

(PUH-duh huh-STAHS-uh-nuh)
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल ह



Intense Stretch Pose

Uttanasana *(ut-tahn-AHS-uh-nuh)*

Also Known As: Full Forward Bend
Modification: arms crossed, grabbing onto the outside edges of the feet, half forward bend
Pose Type: standing, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet) or Nasagrai or Nasagre (nose)
ल य

Forward Bend

Uttanasana

(ut-tahn-AHS-uh-nuh)

Also Known As: Full Forward Bend and Hands to Feet Pose Modification (Pada Hastasana)
Modification: feet hip width apart, arms crossed, grabbing onto the outside edges of the feet, elbows moving toward the feet
1. half forward bend
2. full forward bend
Pose Type: standing, forward bend
Drishti Point: 1. Padayoragrai or Padayoragre (toes/feet) 2. Nasagrai or Nasagre (nose)





STANDING FULL FORWARD BEND: UNSUPPORTED

Intense Stretch Pose
Uttanasana
(ut-tahn-AHS-uh-nuh)
Also Known As: Full Forward Bend
Modification: grabbing onto the triceps, swaying from side to side
Pose Type: standing, forward bend, side bend
Drishti Point: Nasagrai or Nasagre (nose)
ल



Intense Stretch Pose

Uttanasana

(ut-tahn-AHS-uh-nuh)
Also Known As: Full Forward Bend and Unsupported Forward Stretch Pose (Niralamba Uttanasana)
Modification: arms straight out to the sides behind the back, forehead to the shins
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल य ह



Hands Bound Forward Bend Modification

Baddha Hasta Uttanasana

(BUH-duh HUH-stuh ut-tahn-AHS-uh-nuh)

Also Known As: Hands Bound Full Forward Bend and Unsupported Forward Stretch Pose (Niralamba Uttanasana)

Modification: knees bent, chest to the quadriceps

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

ल य ह



STANDING FULL FORWARD BEND: HANDS TO THE FLOOR—ARMS OPEN WIDE

Intense Stretch Pose

Uttanasana

(ut-tahn-AHS-uh-nuh)

Also Known As: Legs Crossed Full Forward Bend

Modification: legs crossed, forehead to the shins, hands to the floor in line with the feet, elbows bent

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

ल व य ॐ



Sideways Intense Stretch

Parshva Uttanasana

(PAHRSH-vuh ut-tahn-AHS-uh-nuh)

Also Known As: Sideways Full Forward Bend
Modification: one hand grabbing onto the opposite ankle, fingertips of the other hand to the floor
Pose Type: standing, forward bend, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Sideways Intense Stretch

Parshva Uttanasana

(PAHRSH-vuhut-tahn-AHS-uh-nuh)

Also Known As: Sideways Full Forward Bend and Sideward Forward Stretch (Parshva Bhaga Uttanasana)
Modification: fingers interlocked, palms to the floor on the outside edge of the foot
Pose Type: standing, forward bend, twist
Drishti Point: Nasagrai or Nasagre (nose)



Revolved Intense Stretch Prayer Pose

Parivritta Uttana Anjalyiasana

(puh-ri-VRIT-uh ut-TAHN-uh uhn-juhl-YAHS-uh-nuh)

Also Known As: Revolved Full Forward Bend Prayer Pose
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Revolved Intense Stretch

Parivritta Uttanasana

(puh-ri-VRIT-tuh ut-tahn-AHS-uh-nuh)

Also Known As: Revolved Full Forward Bend
Modification: grabbing the outside edge of the feet, feet hip width apart
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



STANDING FULL FORWARD BEND: TWISTS—FEET SLIGHTLY WIDER THAN HIPS

Revolved Intense Stretch

Parivritta Uttanasana

(puh-ri-VRIT-tuh ut-tahn-AHS-uh-nuh)

Also Known As: Revolved Full Forward Bend
Modification: feet wide; one hand grabbing onto the ankle, back of the other hand to the floor in front of the opposite foot
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Revolved Intense Stretch

Parivritta Uttanasana

(puh-ri-VRIT-tuh ut-tahn-AHS-uh-nuh)

Also Known As: Revolved Legs Crossed Full Forward Bend
Modification: feet wide, legs crossed, feet flat on the floor
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Firefly Pose 2 A

Tittibhasana 2 A

(ti-ti-BAHS-uh-nuh)

Also Known As: Intense Stretch Pose Stork Modification (Uttanasana), Standing Bound Arms Head Between Knees Pose (Utthita Baddha Hasta Janu Shirshasana)
Modification: arms wrapped around the legs, fingers interlocked behind the head
Pose Type: standing, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)
ल व ह



Firefly Pose 2 B

Tittibhasana 2 B

(ti-ti-BAHS-uh-nuh)

Also Known As: Inverted Firefly Prayer Pose (Viparita Tittibha Anjali Asana)
Modification: hands in Anjali Mudra (Hands in Prayer)
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व



Complete Firefly Pose 2

Paripurna Tittibhasana 2

(puh-ri-POOR-nuh ti-ti-BAHS-uh-nuh)

Also Known As: Firefly Pose B (Tittibhasana B), Inverted Firefly Pose (Viparita Tittibhasana), Standing Firefly Pose Modification (Utthita Tittibhasana), Bound Firefly Pose, Standing Tortoise Pose (Nindra Kurmasana)

Modification: hands bound

Pose Type: standing, forward bend, binding

Drishti Point: Nasagrai or Nasagre (nose)



Firefly Pose 3 A Prep.

Tittibhasana 3 A Prep.

(ti-ti-BAHS-uh-nuh)

Modification: hands on the ankles, heels up

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)



Firefly Pose 3 A

Tittibhasana 3 A

(ti-ti-BAHS-uh-nuh)

Also Known As: Firefly Pose C Prep. (Tittibhasana C Prep.)
Modification: hands on the ankles, one foot lifted
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
लं वं



Firefly Pose 4 A

Tittibhasana 4 A

(ti-ti-BAHS-uh-nuh)

Also Known As: Firefly Pose D (Tittibhasana D), Standing Firefly Pose (Utthita Tittibhasana)
Modification: fingers interlocked in front of the ankles
Pose Type: standing, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)
लं वं हं



Firefly Pose 4 B

Tittibhasana 4 B

(ti-ti-BAHS-uh-nuh)

Also Known As: Inverted Both Legs Prayer Pose (Viparita DwiPada Anjaliasana)
Modification: hands in Anjali Mudra (Hands in Prayer)
Pose Type: standing, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Complete Firefly Pose 4

Paripurna Tittibhasana 4

(puh-ri-POOR-nuh ti-ti-BAHS-uh-nuh)

Also Known As: Inverted Bound Legs Pose (Viparita DwiPada Baddhasana)
Modification: hands bound
Pose Type: standing, forward bend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Book Stand Pose

Grantadara

(gruhn-tah-DAH-ruh)

Also Known As: Chikkyasana
Modification: hands to the head, palms facing up, looking to the side
Pose Type: standing, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Revolved Feet Spread Mountain Pose

Parivritta Prasarita Pada Tadasana

(puh-ri-VRIT-tuh pruh-SAH-ri-tuh PUH-duh tuh-DAHS-uh-nuh)

Modification: arms straight out to the sides
Pose Type: standing, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Feet Spread Mountain Pose in Hero Succession Series

Prasarita Pada Tadasana in Vira Parampara

(pruh-SAH-ri-tuh PUH-duh tuh-DAHS-uh-nuh in VEER-uh puh-ruhm-puh-RAH)

Modification: backbend, hands on the calf muscles
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



LEGS WIDE: ARMS UP OVER THE HEAD

Easy Feet Spread Upward Hands Pose

Sukha Prasarita Pada Urdhva Hastasana

(SUK-kuh pruh-SAH-ri-tuh PUH-duh OORD-vuh huh-STAHS-uh-nuh)

Also Known As: Part of Hero Succession Series (Vira Parampara)
Modification: palms together, looking up
Pose Type: standing, mild backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Feet Spread Upward Hands Pose

Prasarita Pada Urdhva Hastasana

(pruh-SAH-ri-tuh PUH-duh OORD-vuh huh-STAHS-uh-nuh)

Also Known As: Equal Angle Pose (Sama Konasana)
Modification: legs open extremely wide; palms together, looking straight ahead
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)



Angle Pose

Konasana

(ko-NAHS-uh-nuh)

Also Known As: Triangle Pose (Konasana)
Modification: fingers interlocked, palms together; side bend
Pose Type: standing, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky), Nasagrai or Nasagre (nose)



Book Stand Pose with Upward Bound Hands

Grantadara Urdhva Baddha Hastasana

(gruhn-tah-DAH-ruh OORD-vuh BUH-duh HUH-STAHS-uh-nuh)

Also Known As: Chikkiasana Urdhva Baddha Hastasana
Modification: fingers interlocked, palms facing up, looking up
Pose Type: standing
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व य ह



KALI SQUAT: HEELS DOWN—ARMS UP OVER THE HEAD

Lotus Hand Seal in Upward Hands Pose Dedicated to Goddess Kali

Padma Mudra Urdhva Hasta Kalyasana

(PUHD-muh MU-druh OORD-vuh HUH-stuh kahl-YAHS-uh-nuh)

Modification: heels down; arms extended to the sky, fingertips open
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)
ल व



Sideways Hands Bound Pose Dedicated to Goddess Kali

Parshva Baddha Hasta Kalyasana

(PAHRSH-vuh BUH-duh HUH-stuh kahl-YAHS-uh-nuh)

Modification: side bend, fingers interlocked
Pose Type: standing, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व य



KALI SQUAT: HEELS DOWN—ARMS AT HEAD HEIGHT

Pose Dedicated to Goddess Kali

Kalyasana

(kahl-YAHS-uh-nuh)

Modification: elbows bent, palms facing the sky, heels down
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)
ल व



Hand Position of the Pose Dedicated to Garuda in Pose Dedicated to Goddess Kali

Hasta Garudasana in Kalyasana

(HUH-stuh guh-ru-DAHS-uh-nuh in kahl-YAHS-uh-nuh)

Pose Type: standing

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



KALI SQUAT: HEELS DOWN—ARMS BEHIND

Hands Bound Pose Dedicated to Goddess Kali

Baddha Hasta Kalyasana

(BUH-duh HUH-stuh kahl-YAHS-uh-nuh)

Modification: head rolling back, heels down

Pose Type: standing, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Bound Pose Dedicated to Goddess Kali

Baddha Kalyasana

(BUH-duh kahl-YAHS-uh-nuh)

Pose Type: standing, binding

Drishti Point: Nasagrai or Nasagre (nose)



KALI SQUAT: HEELS DOWN—ONE ARM SIDE BENDS

Pose Dedicated to Goddess Kali

Kalyasana

(kahl-YAHS-uh-nuh)

Modification: one hand to the forehead, arm to the knee on the same side

Pose Type: standing

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Pose Dedicated to Goddess Kali

Kalyasana

(kahl-YAHS-uh-nuh)

Modification: one arm straight and parallel to the floor, other arm bent, palm facing up
Pose Type: standing
Drishti Point: Hastagrai or Hastagre (hands)

🔴 🟠



Sideways Pose Dedicated to Goddess Kali

Parshva Kalyasana

(PAHRSH-vuh kahl-YAHS-uh-nuh)

Modification: leaning to one side, one arm out to the side—elbow slightly bent, palm facing up, other hand to the face—palm down
Pose Type: standing, side bend
Drishti Point: Hastagrai or Hastagre (hands)

🔴 🟠



Sideways Half Bound Pose Dedicated to Goddess Kali

Parshva Ardha Baddha Kalyasana

(PAHRSH-vuh UHR-duh BUH-duh kahl-YAHS-uh-nuh)

Modification: forearm to the knee on the same side

Pose Type: standing, side bend, binding

Drishti Point: Urdhva or Antara Drishti (up to the sky)



Sideways Pose Dedicated to Goddess Kali

Parshva Kalyasana

(PAHRSH-vuh kahl-YAHS-uh-nuh)

Modification: one hand to the floor, other arm up to the sky

Pose Type: standing, side bend

Drishti Point: Hastagrai or Hastagre (hands)



KALI SQUAT: HEELS DOWN—FORWARD BEND

Bound Pose Dedicated to Goddess Kali

Baddha Kalyasana

(BUH-duh kahl-YAHS-uh-nuh)

Modification: forward bend

Pose Type: standing, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)



Pose Dedicated to Goddess Kali

Kalyasana

(kahl-YAHS-uh-nuh)
Modification: forward bend, arms straight and parallel to the floor, palms together
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Pose Dedicated to Goddess Kali

Kalyasana

(kahl-YAHS-uh-nuh)
Modification: forward bend, arms crossed, hands to the floor
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



KALI SQUAT: HEELS DOWN—FORWARD BEND & FORWARD BEND TWISTS

Revolved Half Bound Pose Dedicated to Goddess Kali

Parivritta Ardha Baddha Kalyasana

(puh-ri-VRIT-tuh UHR-duh BUH-duh kahl-YAHS-uh-nuh)

Modification: arm under the opposite leg
Pose Type: standing, forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Revolved Pose Dedicated to Goddess Kali

Parivritta Kalyasana

(puh-ri-VRIT-tuh kahl-YAHS-uh-nuh)

Modification: hands to the knees
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



KALI SQUAT: HEELS UP—ARM POSITIONS

Tip Toe Pose Dedicated to Goddess Kali

Prapada Kalyasana

(PRUH-puh-duh kahl-YAHS-uh-nuh)

Modification: head down, elbows bent, back of the hands on the knees
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)



Lotus Hand Seal in Upward Hands Tip Toe Pose Dedicated to Goddess Kali

Padma Mudra in Urdhva Hasta Prapada Kalyasana

(PUHD-muh MU-druh in OORD-vuh HUH-stuh PRUH-puh-duh kahl-YAHS-uh-nuh)

Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)



Tip Toe Pose Dedicated to Goddess Kali

Prapada Kalyasana

(PRUH-puh-duh kahl-YAHS-uh-nuh)

Modification: one hand behind the back in reverse prayer, one elbow on the knee
Pose Type: standing
Drishti Point: Hastagrai or Hastagre (hands)



Reverse Prayer Tip Toe Pose Dedicated to Goddess Kali

Viparita Namaskar Prapada Kalyasana

(vi-puh-REE-tuh nuh-muhs-KAHR PRUH-puh-duh kahl-YAHS-uh-nuh)

Also Known As: Back of the Body Prayer Tip Toe Pose Dedicated to Goddess Kali (Paschima Namaskar Prapada Kalyasana)
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)



KALI SQUAT: HEELS UP—SIDE BENDS

Sideways Tip Toe Pose Dedicated to Goddess Kali

Parshva Prapada Kalyasana

(PAHRSH-vuh PRUH-puh-duh kahl-YAHS-uh-nuh)

Modification: one palm to the forehead, fingertips of the other hand to the floor
Pose Type: standing, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)



KALI SQUAT: ONE HEEL UP, ONE HEEL DOWN

Sideways Uneven Tip Toe Pose Dedicated to Goddess Kali

Parshva Vishama Prapada Kalyasana

(PAHRSH-vuh VISH-uh-muh PRUH-puh-duh kahl-YAHS-uh-nuh)

Modification: side bend
Pose Type: standing, side bend
Dristhi Point: Padhayoragrai or Padayoragre (toes/feet)

KALI SQUAT: HEELS UP—FORWARD BENDS

Tip Toe Pose Dedicated to Goddess Kali

Prapada Kalyasana

(PRUH-puh-duh kahl-YAHS-uh-nuh)

Modification: forward bend, arms crossed, hands to the floor, fingertips pointing toward each other
Pose Type: standing, forward bend
Drishti Point: Hastagrai or Hastagre (hands)



Tip Toe Pose Dedicated to Goddess Kali

Prapada Kalyasana

(PRUH-puh-duh kahl-YAHS-uh-nuh)

Modification: forward bend, arms crossed, hands to the floor, fingertips pointing away from each other
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Tip Toe Pose Dedicated to Goddess Kali

Prapada Kalyasana

(PRUH-puh-duh kahl-YAHS-uh-nuh)

Modification: forward bend, hands to the floor, fingertips to the floor facing away from each other
Pose Type: standing, forward bend
Drishti Point: Hastagrai or Hastagre (hands)



Tip Toe Pose Dedicated to Goddess Kali

Prapada Kalyasana

(PRUH-puh-duh kahl-YAHS-uh-nuh)

Modification: forward bend, arms open wide
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



KALI SQUAT: HEELS UP—BINDING

Extended Side Revolved Hands Bound Half Pose Dedicated to Goddess Kali

Utthita Parshva Parivritta Baddha Hasta Ardha Kalyasana

(UT-ti-tuh PAHRSH-vuh puh-ri-VRIT-tuh BUH-duh HUH-stuh UHR-duh kahl-YAHS-uh-nuh)

Pose Type: standing, forward bend, twist

Drishti Point: Urdhva or Antara Drishti (up to the sky)

लं वं यं



Hands Bound Pose Dedicated to Goddess Kali

Baddha Hasta Kalyasana

(BUH-duh HUH-stuh kahl-YAHS-uh-nuh)

Modification: hands bound under the leg, heels down

Pose Type: standing, forward bend, binding

Drishti Point: Nasagrai or Nasagre (nose)

लं वं यं



KALI SQUAT: HEELS UP—BINDING

Tip Toe Hands Bound Pose Dedicated to Goddess Kali

Prapada Baddha Hasta Kalyasana

(PRUH-puh-duh kahl-YAHS-uh-nuh)

Modification: hands bound under the leg
Pose Type: standing, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)



Tip Toe Half Bound Pose Dedicated to Goddess Kali

Prapada Ardha Baddha Kalyasana

(PRUH-puh-duh UHR-duh BUH-duh kahl-YAHS-uh-nuh)

Modification: one arm bound under the leg, palm to the rib cage, other forearm to the floor
Pose Type: standing, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose), Angushtamadhye or Angushta Ma Dyai (thumbs)

LEGS WIDE: HALF FORWARD BEND

Half Feet Spread Out Intense Stretch Pose

Ardha Prasarita Padottanasana

(UHR-duh pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)

Also Known As: Feet Spread Out Half Forward Bend
Modification: legs straight, hands on the shins
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व ह



LEGS WIDE: HALF FORWARD BEND, HANDS TO THE FLOOR—HEELS DOWN & HEELS UP

Half Feet Spread Out Intense Stretch Pose

Ardha Prasarita Padottanasana

(UHR-duh pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)

Also Known As: Feet Spread Out Half Forward Bend
Modification: 1. toes pointing straight ahead, palms flat on the floor 2. toes pointing slightly outward,

back of the hands to the floor, fingertips pointing toward each other
Pose Type: standing, forward bend
Drishti Point: Hastagrai or Hastagre (hands)
ल व ह


1.


2.

Tip Toe Half Feet Spread Out Intense Stretch Pose

Prapada Ardha Prasarita Padottanasana

(PRUH-puh-duh UHR-duh pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)
Also Known As: Tip Toe Feet Spread Out Half Forward Bend
Modification: toes pointing straight ahead, heels up, palms flat on the floor
Pose Type: standing, forward bend
Drishti Point: Hastagrai or Hastagre (hands)
ल व ह



LEGS WIDE: FULL FORWARD BEND—HANDS TO THE FLOOR

Feet Spread Out Intense Stretch Pose 1

Prasarita Padottanasana 1

(pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)

Also Known As: Feet Spread Out Intense Stretch Pose A (Prasarita Padottanasana A), Feet Spread Out Full Forward Bend A
Modification: palms to the floor, elbows bent at 90 degrees
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Feet Spread Out Intense Stretch Pose 1

Prasarita Padottanasana 1

(pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)

Also Known As: Feet Spread Out Intense Stretch Pose A (Prasarita Padottanasana A), Feet Spread Out Full Forward Bend A
Modification: arms straight, palms to the floor, fingertips pointing away from the head
Pose Type: standing, forward bend

Drishti Point: Hastagrai or Hastagre (hands)



Feet Spread Out Intense Stretch Pose 4

Prasarita Padottanasana 4

(pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)

Also Known As: Feet Spread Out Intense Stretch Pose D (Prasarita Padottanasana D), Hands to Big Toes Feet Spread Out Full Forward Bend (Hasta Padangushta Prasarita Padottanasana)
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



LEGS WIDE: FULL FORWARD BEND—ARMS BEHIND THE BACK

Feet Spread Out Intense Stretch Pose 2

Prasarita Padottanasana 2

(pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)

Also Known As: Feet Spread Out Intense Stretch Pose B (Prasarita Padottanasana B), Feet Spread Out Full Forward Bend

Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Feet Spread Out Intense Stretch Pose 5

Prasarita Padottanasana 5

(pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)
Also Known As: Reverse Prayer Feet Spread Out Full Forward Bend (Viparita Namaskar Prasarita Padottanasana)
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Feet Spread Out Intense Stretch Pose 3

Prasarita Padottanasana 3

(pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)
Also Known As: Feet Spread Out Intense Stretch Pose C (Prasarita Padottanasana C), Feet Spread Out Full Forward Bend, Hands Bound Wide Legs Forward Fold (Baddha Hasta Prasarita Padottanasana)

Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व य



LEGS WIDE: FULL FORWARD BEND—ARMS OPEN WIDE

Feet Spread Out Intense Stretch Pose 6

Prasarita Padottanasana 6

(pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)
Also Known As: Feet Spread Out Full Forward Bend 6
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व य



Feet Spread Out Intense Stretch Pose 7

Prasarita Padottanasana 7

(pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)
Also Known As: Feet Spread Out Full Forward Bend 7
Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)



LEGS WIDE: FULL FORWARD BEND—TWISTS

Revolved Half Feet Spread Out Intense Stretch Pose

Parivritta Ardha Prasarita Padottanasana

(puh-ri-VRIT-tuh UHR-duh pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)

Also Known As: Revolved Feet Spread Out Half Forward Bend
Modification: palm to the floor
Pose Type: standing, forward bend, twist
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Revolved Half Feet Spread Out Intense Stretch Pose

Parivritta Ardha Prasarita Padottanasana

(puh-ri-VRIT-tuh UHR-duh pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)

Also Known As: Revolved Feet Spread Out Half Forward Bend
Modification: forearm to the floor

Pose Type: standing, forward bend, twist
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Revolved Paying Homage Feet Spread Out Intense Stretch Pose

Parivritta Namasya Prasarita Padottanasana

(puh-ri-VRIT-tuh nuh-MUHS-ya pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)
Also Known As: Revolved Paying Homage Feet Spread Out Forward Bend
Modification: legs crossed, hand to the back foot, other arm extended to the sky
Pose Type: standing, forward bend, twist
Drishti Point: Hastagrai or Hastagre (hands)



Bound Revolved Feet Spread Out Intense Stretch Pose

Baddha Parivritta Prasarita Padottanasana

(BUH-duh puh-ri-VRIT-tuh pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)
Also Known As: Bound Revolved Feet Spread Out Full Forward Bend
Modification: arm straight, looking up
Pose Type: standing, forward bend, twist, binding

Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व य



Hands Bound Revolved Feet Spread Out Intense Stretch Pose

Baddha Hasta Parivritta Prasarita Padottanasana

(BUH-duh HUH-stuh puh-ri-VRIT-tuh pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)

Also Known As: Hands Bound Revolved Feet Spread Out Full Forward Bend
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व य



Revolved Paying Homage Feet Spread Out Intense Stretch Pose

Parivritta Namasya Prasarita Padottanasana

(puh-ri-VRIT-tuh nuh-MUHS-ya pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)

Modification: outside edges of the feet to the floor, legs crossed, forward bend, both hands on the back foot
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व



Revolved Feet Spread Out Intense Stretch Pose

Parivritta Prasarita Padottanasana

(puh-ri-VRIT-tuh pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)

Also Known As: Revolved Feet Spread Out Full Forward Bend
Modification: grabbing onto the knee and the foot
Pose Type: standing, forward bend, side bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Revolved Feet Spread Out Intense Stretch Pose

Parivritta Prasarita Padottanasana

(puh-ri-VRIT-tuh pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)

Also Known As: Revolved Feet Spread Out Full Forward Bend
Modification: grabbing onto the ankles
Pose Type: standing, forward bend, side bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Revolved to the Side Feet Spread Out Intense Stretch Pose

Parivritta Parshva Prasarita Padottanasana

(puh-ri-VRIT-tuh PAHRSH-vuh pruh-SAH-ri-tuh puhd-o-tahn-AHS-uh-nuh)

Also Known As: Revolved to the Side Feet Spread Out Full Forward Bend)
Modification: grabbing onto the foot with both hands
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Downward Facing Dog Pose

Adho Mukha Shvanasana

(uh-DO MUK-uh shwa-NAHS-uh-nuh)

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

How to Perform the Pose:

1. Start by lying on your stomach with your whole body flat on the floor. Place your palms on the floor at the bottom of your ribs with fingertips facing forward and elbows tucked in. Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale as you engage your core and lift your torso off the floor, and straighten your arms, coming into a distinct upside-down V shape with your sitting bones up to the sky. Your feet should be in line with your sitting bones and your hands should be shoulder width apart.
3. Try to keep your legs as straight as possible while pressing the heels to the floor. You should feel a deep stretch in the back of your thighs (the hamstrings) and your calf muscles.
4. Inhale as you lengthen your spine, keeping your neck long and your shoulder blades down your back. Try not to round your lower back, keeping it long. Exhale as you press through your chest, moving it toward your thighs. You should feel a deep stretch in the back of your shoulders.
5. You can either keep your head off the floor (Pose #1) or bring your forehead to the floor (Pose #2) if your shoulders are open.
6. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch.
7. To come out of the pose, inhale as you rock into Plank Pose, and exhale as you bend your elbows into Four Limbed Staff Pose (*Chaturanga Dandasana*) and lower all the way down to the floor into the starting position.

Modification:

1. head off the floor
2. forehead to the floor

adho = downward

mukha = face

shvana = dog

1.



2.



DOWNWARD DOG: FOREARMS AND HEAD ON THE FLOOR

Downward Facing Pose Dedicated to Makara on the Head

Adho Mukha Shirsha Makarasana

(uh-DO MUK-uh SHEER-shuh muh-kuh-RAHS-uh-nuh)

Pose Type: forward bend, inversion, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
🔴 🟢 🟣



DOWNWARD DOG: KNEES BENT

Downward Facing Dog Pose

Adho Mukha Shvanasana

(uh-DO MUK-uh shwa-NAHS-uh-nuh)

Modification: knees bent, heels up
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
🔴 🟢 🔵



Downward Facing Dog Pose

Adho Mukha Shvanasana

(uh-DO MUK-uh shwa-NAHS-uh-nuh)

Modification: knees bent, heels up, spine in Cat Tilt, forehead toward the knees
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल ह



DOWNWARD DOG: WIDE-LEGGED

Feet Spread Downward Facing Dog Pose

Prasarita Pada Adho Mukha Shvanasana

(pruh-SAH-ri-tuh PUH-duh uh-DO MUK-uh shwa-NAHS-uh-nuh)

Modification: heels down, palms down
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य



Tip Toe Feet Spread Downward Facing Dog Pose

Prapada Prasarita Pada Adho Mukha Shvanasana

(PRUH-puh-duh pruh-SAH-ri-tuh PUH-duh uh-DO MUK-uh shwa-NAHS-uh-nuh)

Modification: one palm on top of the other, fingertips to the floor, head above the arms

Pose Type: standing, forward bend

Drishti Point: Hastagrai or Hastagre (hands), Nasagrai or Nasagre (nose)

ल व र य ह



DOWNWARD DOG: ONE-LEGGED—KNEES TOGETHER

One-Legged Downward Facing Dog Pose

Eka Pada Adho Mukha Shvanasana

(EY-kuh PUH-duh uh-DO MUK-uh shwa-NAHS-uh-nuh)

Modification: back leg bent, knees together

Pose Type: standing, forward bend

Drishti Point: Padayoragrai or Padayoragre (toes/feet)

ल र य



Leg Position of the Half Cow Face Pose in Downward Facing Dog Pose

Pada Ardha Gomukhasana in Adho Mukha Shvanasana

(PUH-duh URH-duh go-muk-AHS-uh-nuh in uh-DO MUK-uh shwa-NAHS-uh-nuh)

Also Known As: Leg Position of the One-Legged Cow Face Pose in Downward Facing Dog Pose (Eka Pada Gomukhasana in Adho Mukha Shvanasana)
Pose Type: standing, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
ल व र य



DOWNWARD DOG: ONE-ARMED

Revolved Downward Facing Dog Pose

Parivritta Adho Mukha Shvanasana

(puh-ri-VRIT-tuh uh-DO MUK-uh shwa-NAHS-uh-nuh)

Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल र य



Hand to Knee One-Legged Downward Facing Dog Pose

Hasta Janu Eka Pada Adho Mukha Shvanasana

(HUH-stuh JAH-nu EY-kuh PUH-duh uh-DO MUK-uh shwa-NAHS-uh-nuh)

Modification: hand grabbing onto the opposite knee
Pose Type: standing one-legged balance, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
ल व



Hand to Ankle One-Legged Downward Facing Dog Pose 1

Hasta Kulpa Eka Pada Adho Mukha Shvanasana 1

(HUH-stuh KUL-puh EY-kuh PUH-duh uh-DO MUK-uh shwa-NAHS-uh-nuh)

Modification: grabbing onto the ankle on the same side; back leg bent, knees together
Pose Type: standing one-legged balance, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल ह



Hand to Ankle One-Legged Downward Facing Dog Pose 2

Hasta Kulpa Eka Pada Adho Mukha Shvanasana 2

(HUH-stuh KUL-puh EY-kuh PUH-duh uh-DO MUK-uh shwa-NAHS-uh-nuh)

Modification: grabbing onto the ankle on the opposite side; back leg bent, knees together
Pose Type: standing one-legged balance, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल



DOWNWARD DOG: ONE-LEGGED

One-Legged Downward Facing Dog Pose

Eka Pada Adho Mukha Shvanasana

(EY-kuh PUH-duh uh-DO MUK-uh shwa-NAHS-uh-nuh)

Modification: knee bent
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य



One Leg to the Side Downward Facing Dog Pose

Parshva Eka Pada Adho Mukha Shvanasana

(PAHRSH-vuh EY-kuh PUH-duh uh-DO MUK-uh shwa-NAHS-uh-nuh)

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

ल व र य



One-Legged Downward Facing Dog Pose

Eka Pada Adho Mukha Shvanasana

(EY-kuh PUH-duh uh-DO MUK-uh shwa-NAHS-uh-nuh)

Also Known As: One-Legged Downward Facing Dog Shoulder Press

Modification: bottom knee bent; elbows bent, fingertips to the floor

Pose Type: standing, forward bend

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)

ल व



One-Legged Downward Facing Dog Pose

Eka Pada Adho Mukha Shvanasana

(EY-kuh PUH-duh uh-DO MUK-uh shwa-NAHS-uh-nuh)

Also Known As: One Leg Raised Up Downward Facing Dog Pose (Utthita Eka Pada Adho Mukha Shvanasana)

Modification: back leg straight and extended up to the sky
Pose Type: standing, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



DOWNWARD DOG: TWISTS

Uneven Legs Revolved Downward Facing Dog Pose 1

Vishama Pada Parivritta Adho Mukha Shvanasana 1

(VISH-uh-muh PUH-duh puh-ri-VRIT-tuh uh-DO MUK-uh shwa-NAHS-uh-nuh)
Modification: one knee bent, foot crossed over
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Uneven Legs Revolved Downward Facing Dog Pose 2

Vishama Pada Parivritta Adho Mukha Shvanasana 2

(VISH-uh-muh PUH-duh puh-ri-VRIT-tuh uh-DO MUK-uh shwa-NAHS-uh-nuh)
Modification: both legs straight, one leg crossed over

Pose Type: standing, forward bend, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



INTENSE SIDE STRETCH: STRAIGHT SPINE TO BACKBEND

Upward Bound Hands Pose in Hero Succession Series

Urdhva Baddha Hastasana in Vira Parampara

(OORD-vuh BUH-duh huh-STAHS-uh-nuh in VEER-uh puh-ruhm-puh-RAH)
Modification: arms up to the sky, fingers interlocked, spine straight
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)



Hands Bound Pose in Hero Succession Series

Baddha Hastasana in Vira Parampara

(BUH-duh huh-STAHS-uh-nuh in VEER-uh puh-ruhm-puh-RAH)
Modification: grabbing onto the triceps behind the back
Pose Type: standing, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reverse Prayer Pose in Hero Succession Series

Viparita Namaskarasana in Vira Parampara

(vi-puh-REET-tuh nuh-muhs-kahr-AHS-uh-nuh in VEER-uh puh-ruhm-puh-RAH)

Also Known As: Back of the Body Prayer in Hero Succession Series (Paschima Namaskara in Vira Parampara)
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Upward Bound Hands Pose in Hero Succession Series

Urdhva Baddha Hastasana in Vira Parampara

(OORD-vuh BUH-duh huh-STAHS-uh-nuh in VEER-uh puh-ruhm-puh-RAH)

Modification: deep backbend
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Angusthamadhye or Angustha Ma Dyai (thumbs)



INTENSE SIDE STRETCH: HALF FORWARD BEND

Intense Side Stretch Pose Prep.

Parshvottanasana Prep.

(pahrsh-vo-tahn-AHS-uh-nuh)

Modification: arms straight out in front, palms pressed together
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Intense Side Stretch Pose Prep.

Parshvottanasana Prep.

(pahrsh-vo-tahn-AHS-uh-nuh)

Modification: one hand to the lower back, one arm extended out in front and parallel to the floor
Pose Type: standing, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Hastagrai or Hastagre (hands)



Intense Side Stretch Pose Prep.

Parshvottanasana Prep.

(pahrsh-vo-tahn-AHS-uh-nuh)

Modification: grabbing onto the triceps behind the back
Pose Type: standing, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Intense Side Stretch Pose Prep.

Parshvottanasana Prep.

(pahrsh-vo-tahn-AHS-uh-nuh)

Modification: arms open to the sides
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



INTENSE SIDE STRETCH: HALF FORWARD BEND—GRABBING ONTO ONE LEG

Intense Side Stretch Pose Prep.

Parshvottanasana Prep.

(pahrsh-vo-tahn-AHS-uh-nuh)

Modification: both hands on the shin on the front leg
Pose Type: standing, forward bend
Drishti Point: Padhayoragrai or Padayoragre (toes/feet)



Extended Both Hands to Foot Intense Side Stretch Pose

Utthita Dwi Hasta Pada Parshvottanasana

(UT-ti-tuh DWI-huh-stuh PUH-duh pahrsh-vo-tahn-AHS-uh-nuh)

Modification: toes of the front foot flexed in and lifted off the floor
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Intense Side Stretch Pose

Parshvottanasana

(pahrsh-vo-tahn-AHS-uh-nuh)

Modification: both hands grabbing onto the calf of the back leg

Pose Type: standing, forward bend

Drishti Point: Padayoragrai or Padayoragre (toes/feet)



INTENSE SIDE STRETCH: FULL FORWARD BEND—ARMS IN FRONT AND ARMS POINTING TO THE BACK

Intense Side Stretch Pose Prep.

Parshvottanasana Prep.

(pahrsh-vo-tahn-AHS-uh-nuh)

Modification: palms to the floor on either side of the front foot

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)



Intense Side Stretch Pose Prep.

Parshvottanasana Prep.

(pahrsh-vo-tahn-AHS-uh-nuh)

Also Known As: Hero Succession Series (Vira Parampara)
Modification: arms reaching to the back, fingertips to the floor
1. chin to the shin
2. forehead to the shin
Pose Type: standing, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose)

ल व र य ह ॐ



1.



2.

Intense Side Stretch Pose Prep.

Parshvottanasana Prep.

(pahrsh-vo-tahn-AHS-uh-nuh)

Modification: hands in Anjali Mudra (Hands in Prayer), arms wrapped around the front leg
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Revolved Intense Side Stretch Pose

Parivritta Parshvottanasana

(puh-ri-VRIT-tuh pahrsh-vo-tahn-AHS-uh-nuh)

Modification: hands in Anjali Mudra (Hands in Prayer), arms wrapped around the front leg, twist
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Intense Side Stretch Pose

Parshvottanasana

(pahrsh-vo-tahn-AHS-uh-nuh)

Also Known As: Reverse Prayer Intense Side Stretch Pose (Viparita Namaskar Parsvottanasana), Back of the Body Prayer Intense Side Stretch Pose (Paschima Namaskara Parshvottanasana)

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

ल व र य



Hands Bound Intense Side Stretch Pose

Baddha Hasta Parshvottanasana

(BUH-duh HUH-stuh pahrsh-vo-tahn-AHS-uh-nuh)

Modification: both legs straight

Pose Type: standing, forward bend

Drishti Point: Padayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose)

ल व र य ह





2.

INTENSE SIDE STRETCH: FULL FORWARD BEND—ONE ARM IN FRONT—ONE ARM BEHIND

Uneven Legs Tip Toe Intense Side Stretch Pose

Vishama Pada Prapada Parshvottanasana

(VISH-uh-muh PUH-duh PRUH-puh-duh pahrsh-vo-tahn-AHS-uh-nuh)

Modification: 1. one arm stretched out to the back and up to the sky; other arm stretched out to the front, fingertips to the floor 2. both arms stretched out in front, fingertips to the floor
Pose Type: standing, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
ल व र य ह





Intense Side Stretch Pose Prep.

Parshvottanasana Prep.

(pahrsh-vo-tahn-AHS-uh-nuh)

Modification: opposite arm wrapped around the front calf, chin to the shin
Pose Type: standing, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
ल व र य ह



TRIANGLE POSE

Extended Side Triangle Pose

Utthita Parshva Trikonasana

(UT-ti-tuh PAHRSH-vuh tri-ko-NAHS-uh-nuh)

Modification: top arm parallel to the floor
Pose Type: standing, forward bend, side bend
Drishti Point: Hastagrai or Hastagre (hands)
ल व र य



Extended Triangle Pose

Utthita Trikonasana

(UT-ti-tuh tri-ko-NAHS-uh-nuh)

Pose Type: standing, forward bend, side bend

Drishti Point: Angusthamadhye or Angustha Ma Dyai (thumbs)

How to Perform the Pose:

1. Begin by standing in Mountain Pose (*Tadasana*). Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Inhale and step your feet about elbow distance apart with toes facing forward and feet parallel to each other. Expand your chest and hold your arms straight out to the sides, parallel to the floor.
3. Keep your legs strong and straight by engaging your quadriceps and pulling the kneecaps up. Turn your left foot 90 degrees to the left. Turn your right foot as close to 45 degrees to the left as possible.
4. On your next exhale, reach over to the left as far as you can with good form and drop your left hand toward the left shin (or left foot or to the floor either on the inside or the outside of the left foot).
5. Reach your right arm up to the sky and look at your right thumb (the *drishti* point). Make sure that your chest is not collapsing down toward the floor by lengthening both arms, grabbing onto the big toe of your left foot with pointer finger and middle finger and thumb locked on top, and leaning back far enough so that your shoulders are stacked one on top of the other.
6. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch. Exhale as you release the pose. Inhale as you press strongly into both feet to come up.
7. Exhale, come back to Mountain Pose (*Tadasana*) and repeat on the other side.

Modification:
1. front view
2. back view

utittha = extended

tri = three

kona = angle

1.



2.



Half Bound Extended Triangle Pose

Ardha Baddha Utthita Trikonasana

(UHR-duh BUH-duh UT-ti-tuh tri-ko-NAHS-uh-nuh)

Pose Type: standing, forward bend, side bend, binding
Drishti Point: Nasagrai or Nasagre (nose)



Bound Extended Triangle Pose

Baddha Utthita Trikonasana

(BUH-duh UT-ti-tuh tri-ko-NAHS-uh-nuh)

Modification: fingers interlocked on the inside of the thigh
Pose Type: standing, forward bend, side bend, binding
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Bound Extended Triangle Pose

Baddha Utthita Trikonasana

(BUH-duh UT-ti-tuh tri-ko-NAHS-uh-nuh)

Pose Type: standing, forward bend, side bend, binding, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व र य



Revolved Sideways Extended Triangle Pose

Parivritta Parshva Utthita Trikonasana

(puh-ri-VRIT-tuh PAHRSH-vuh UT-ti-tuh tri-ko-NAHS-uh-nuh)

Modification: grabbing onto both shins
Pose Type: standing, forward bend, side bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व र य



TRIANGLE POSE: REVOLVED & BINDING

Revolved Triangle Pose

Parivritta Trikonasana

(puh-ri-VRIT-tuh tri-ko-NAHS-uh-nuh)

Also Known As: Revolved Intense Side Stretch Pose (Parivritta Parshvottanasana)
Modification: hands in Anjali Mudra (Hands in Prayer)
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Revolved Triangle Pose

Parivritta Trikonasana

(puh-ri-VRIT-tuh tri-ko-NAHS-uh-nuh)

Pose Type: standing, forward bend, twist
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Revolved Bound Triangle Pose

Parivritta Baddha Trikonasana

(puh-ri-VRIT-tuh BUH-duh tri-ko-NAHS-uh-nuh)

Also Known As: Bound Leg Twisted Angle Pose (Baddha Pada Parivritta Konasana)
Pose Type: standing, forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)

Extended Side Angle Pose

Utthita Parshva Konasana

(UT-ti-tuh pahrsh-vuh-ko-NAHS-uh-nuh)

Pose Type: standing, side bend

Drishti Point: Hastagrai or Hastagrahe (hands)

How to Perform the Pose:

1. Begin by standing in Mountain Pose (*Tadasana*). Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Inhale and step your feet about wrist-distance apart with toes facing forward and feet parallel to each other. Expand your chest and hold your arms straight out to the sides parallel to the floor.
3. Keep your legs strong and straight by engaging your quadriceps and pulling the kneecaps up. Turn your left foot 90 degrees to the left. Turn your right foot 45 degrees to the left as much as possible.
4. Exhale and bend your left knee until your left thigh is parallel to the floor, coming into Warrior 2 Pose (Virabhadrasana 2).
5. On the exhale, bend to the left and drop your left elbow to the left thigh. Reach your right arm over your head and rotate your chest to the side until your right shoulder is on top of your left shoulder.
6. You can experiment with bringing your left palm to the floor on the inside of your left thigh or the outside of your thigh.
7. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch. Exhale as you release the pose. Inhale as you press strongly into both feet to come up.
8. Exhale, come back to Mountain Pose (*Tadasana*) and repeat on the right side.

Modification:

1. arm to the inside of the thigh
2. elbow on the thigh
3. arm to the outside of the thigh

utthita = extended, rising, risen

parsva = side

kona = angle

1.



2.



3.



Warrior 2

Virabhadrasana 2

(veer-uh-buh-DRAHS-uh-nuh)

Also Known As: Half Side Angle Pose (Ardha Parshva Konasana)
Pose Type: standing
Drishti Point: Hastagrai or Hastagre (hands)



SIDE ANGLE POSE

Extended Side Angle Pose Prep.

Utthita Parshva Konasana Prep.

(UT-ti-tuh pahrsh-vuh-ko-NAHS-uh-nuh)

Modification: back knee on the floor, palm to the floor on the inside of the front leg
Pose Type: standing, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Both Arms Extended Side Angle Pose Prep.

Dwi Hasta Utthita Parshva Konasana Prep.

(DWI-huh-stuh UT-ti-tuh pahrsh-vuh-ko-NAHS-uh-nuh)

Modification: back knee on the floor
Pose Type: standing, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Both Arms Extended Side Angle Pose

Dwi Hasta Utthita Parshva Konasana

(DWI-huh-stuh UT-ti-tuh pahrsh-vuh-ko-NAHS-uh-nuh)

Modification: back knee off the floor
Pose Type: standing, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Tip Toe Extended Side Angle Pose Prep.

Prapada Utthita Parshva Konasana Prep.

(PRUH-puh-duh UT-ti-tuh pahrsh-vuh-ko-NAHS-uh-nuh)

Modification: front heel lifted, fingertips to the floor on the inside of the leg, other arm resting on the side of the torso

Pose Type: standing, side bend

Drishti Point: Urdhva or Antara Drishti (up to the sky)



Tip Toe Both Arms Extended Side Angle Pose

Prapada Dwi Hasta Utthita Parshva Konasana

(PRUH-puh-duh DWI-huh-stuh UT-ti-tuh pahrsh-vuh-ko-NAHS-uh-nuh)

Modification: back knee off the floor

Pose Type: standing, side bend

Drishti Point: Urdhva or Antara Drishti (up to the sky)



SIDE ANGLE POSE: BINDING

Half Bound Extended Side Angle Pose

Ardha Baddha Utthita Parshva Konasana

(UHR-duh BUH-duh UT-ti-tuh pahrsh-vuh-ko-NAHS-uh-nuh)

Modification: hand to the floor on the inside of the front leg

Pose Type: standing, side bend, binding

Drishti Point: Urdhva or Antara Drishti (up to the sky)



Bound Extended Side Angle Pose

Baddha Utthita Parshva Konasana

(BUH-duh UT-ti-tuh pahrsh-vuh-ko-NAHS-uh-nuh)

Modification: fingers interlocked on the inside of the front thigh

Pose Type: standing, side bend, binding

Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Bound Extended Side Angle Pose

Baddha Utthita Parshva Konasana

(BUH-duh UT-ti-tuh pahrsh-vuh-ko-NAHS-uh-nuh)

Also Known As: Bound Arms Side Angle Pose (Baddha Hasta Parshva Konasana)

Pose Type: standing, side bend, binding, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Pose Dedicated to Vishvamitra Prep.

Vishvamitrasana Prep.

(VISH-vah-mi-TRAHS-uh-nuh)
Modification: knee bent wrapped around the tricep, grabbing onto the foot
Pose Type: standing, arm balance
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Pose Dedicated to Vishvamitra Prep.

Vishvamitrasana Prep.

(vish-vah-mi-TRAHS-uh-nuh)
Modification: knee bent, shin to the tricep
Pose Type: standing, arm balance
Drishti Point: Hastagrai or Hastagre (hands), Padayoragrai or Padayoragre (toes/feet)



SIDE ANGLE POSE: REVOLVED

Revolved Side Angle Pose Prep.

Parivritta Parshva Konasana Prep.

(puh-ri-VRIT-tuh pahrsh-vuh-ko-NAHS-uh-nuh)

Modification: one arm under the leg, hands in Anjali Mudra (Hands in Prayer),
1. back knee on the floor, looking up to the sky 2. back knee off the floor, looking down
Pose Type: standing, twist
Drishti Point: 1. Urdhva or Antara Drishti (up to the sky)
2. Padayoragrai or Padayoragre (toes/feet)
ल व र य





Revolved Side Angle Pose Prep.

Parivritta Parshva Konasana Prep.

(puh-ri-VRIT-tuh pahrsh-vuh-ko-NAHS-uh-nuh)

Modification: hands in Anjali Mudra (Hands in Prayer)
1. back knee on the floor, looking up to the sky
2. back knee off the floor, looking up to the sky
Pose Type: standing, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)





Both Hands Free Revolved Side Angle Pose

Dwi Mukta Hasta Parivritta Parshva Konasana

(DWI muk-tuh HUH-stuh puh-ri-VRIT-tuh pahrsh-vuh-ko-NAHS-uh-nuh)

Modification: bottom hand off the floor, fingertips pointing in opposite directions
1. back knee on the floor
2. back knee off the floor
Pose Type: standing, twist, side bend
Drishti Point: Hastagrai or Hastagre (hands)





Revolved Side Angle Pose Prep.

Parivritta Parshva Konasana Prep.

(puh-ri-VRIT-tuh pahrsh-vuh-ko-NAHS-uh-nuh)

Modification: palm to the floor, other palm to lower back
Pose Type: standing, twist, side bend
Drishti Point: Hastagrai or Hastagre (hands) or Padhayoragrai or Padayoragre (toes/feet)



SIDE ANGLE POSE: REVOLVED BOUND

Revolved Side Angle Pose

Parivritta Parshva Konasana

(puh-ri-VRIT-tuh pahrsh-vuh-ko-NAHS-uh-nuh)

Modification: 1. palm to the floor, back knee on the floor 2. palm to the floor, back knee off the floor

Pose Type: standing, twist, side bend

Drishti Point: Hastagrai or Hastagre (hands)

ल व र य

1.



2.



Bound Revolved Side Angle Pose

Baddha Parivritta Parshva Konasana

(BUH-duh puh-ri-VRIT-tuh pahrsh-vuh-ko-NAHS-uh-nuh)

Also Known As: Hands Bound Revolved Side Angle Pose Prep. (Baddha Hasta Parivritta Parshva Konasana Prep.)

Modification: 1. back knee on the floor 2. back knee off the floor

Pose Type: standing, twist, binding

Drishti Point: Urdhva or Antara Drishti (up to the sky)

ल व र





REVERSE WARRIOR

Both Arms Extended Reverse Warrior Pose Prep.

Dwi Hasta Utthita Viparita Virabhadrasana Prep.

(DWI-huh-stuh UT-ti-tuh vi-puh-REE-tuh vee-ruh-buh-DRAHS-uh-nuh)

Modification: back knee on the floor, arms straight, palms together
Pose Type: standing, backbend, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व र य ह



Tip Toe Both Arms Extended Reverse Warrior Pose

Prapada Dwi Hasta Utthita Viparita Virabhadrasana

(PRUH-puh-duh DWI-huh-stuh UT-ti-tuh vi-puh-REE-tuh vee-ruh-buh-DRAHS-uh-nuh)

Modification: arms straight, palms together
Pose Type: standing, backbend, side bend
Drishti Point: Bhrumadhye (third eye, between the eyebrows) or Hastagrai or Hastagre (hands)
लं वं हं



Revolved Sideways Tip Toe Reverse Warrior Pose

Parivritta Parshva Prapada Viparita Virabhadrasana

(puh-ri-VRIT-tuh PAHRSH-vuh PRUH-puh-duh vi-puh-REE-tuh vee-ruh-buh-DRAHS-uh-nuh)

Modification: front heel up, one arm in front and parallel to the floor; other elbow bent, palm facing up, hand to the crown of the head
Pose Type: standing, backbend, twist, side bend
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
लं वं यं



Tip Toe Reverse Warrior Pose

Prapada Viparita Virabhadrasana

(PRUH-puh-duh vi-puh-REE-tuh vee-ruh-buh-DRAHS-uh-nuh)

Modification: front heel up, both elbows bent, one arm up over the head, other arm in front of the torso

Pose Type: standing, backbend

Drishti Point: Hastagrai or Hastagre (hands)

ल व र य ह



Half Bound Reverse Warrior Pose

Ardha Baddha Viparita Virabhadrasana

(UHR-duh BUH-duh vi-puh-REE-tuh vee-ruh-buh-DRAHS-uh-nuh)

Pose Type: standing, backbend, binding

Drishti Point: Hastagrai or Hastagre (hands)

ल व र य ह



Reverse Warrior Pose

Viparita Virabhadrasana

(vi-puh-REE-tuh vee-ruh-buh-DRAHS-uh-nuh)

Also Known As: Reverse Warrior Pose 2 (Viparita Virabhadrasana 2)

Modification: hand to the calf of the back leg; low lunge, low stance
Pose Type: standing, backbend
Drishti Point: Hastagrai or Hastagre (hands)



WARRIOR 1

Warrior 1 Prep.

Virabhadrasana 1 Prep.

(vee-ruh-buh-DRAHS-uh-nuh)

Modification: both legs straight, palms pressed together
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)



Warrior 1

Virabhadrasana 1

(vee-ruh-buh-DRAHS-uh-nuh)

Also Known As: Raised Arms Warrior Pose (Urdhva Hasta Veerasana), Hero Succession Series

(Vira Parampara)

Pose Type: standing

Drishti Point: Nasagrai or Nasagre (nose)



Warrior 1

Virabhadrasana 1

(vee-ruh-buh-DRAHS-uh-nuh)

Modification: arms out in front and parallel to the floor, palms facing the sky

Pose Type: standing

Drishti Point: Hastagrai or Hastagre (hands)



Bound Warrior 1

Baddha Virabhadrasana 1

(BUH-duh vee-ruh-buh-DRAHS-uh-nuh)

Modification: fingers interlocked on the inside of the front thigh

Pose Type: standing, binding

Drishti Point: Nasagrai or Nasagre (nose)



Warrior 1

Virabhadrasana 1

(vee-ruh-buh-DRAHS-uh-nuh)

Modification: arms up over the head and open to the sides; front leg, toes rotated out; deep backbend
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Open Heart Chakra Hands Bound Warrior

Anahata Chakra Baddha Hasta Virabhadrasana

(uh-NAH-huh-tuh CHUHK-ruh BUH-duh HUH-suh vee-ruh-buh-DRAHS-uh-nuh)

Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Raised Bound Hands in Warrior 1

Urdhva Baddha Hastasana in Virabhadrasana 1

(OORD-vuh BUH-duh huh-STAHS-uh-nuh in vee-ruh-buh-DRAHS-uh-nuh)

Modification: fingers interlocked deep backbend
Pose Type: standing, backbend
Drishti Point: Hastagrai or Hastagre (hands)
लं वं रं यं हं



WARRIOR 1: FORWARD BEND—TO THE SIDE

Spread Out Hands Side Angle Pose

Prasarita Hasta Parshva Konasana

(pruh-SAH-ri-tuh HUH-stuh pahrsh-vuh-ko-NAHS-uh-nuh)

Also Known As: Down Dog Lunge Pose
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
लं वं हं



Hand Position of the Pose Dedicated to Garuda in Side Angle Pose

Hasta Garudasana in Parshva Konasana

(HUH-stuh guh-ru-DAHS-uh-nuh in pahrsh-vuh-ko-NAHS-uh-nuh)

Pose Type: standing, forward bend

Drishti Point: Padayoragrai or Padayoragre (toes/feet)

● ●



Hand Position of Cow Face Pose in Side Angle Pose

Hasta Gomukhasana in Parshva Konasana

(HUH-stuh go-muk-AHS-uh-nuh in pahrsh-vuh-ko-NAHS-uh-nuh)

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

● ● ●



WARRIOR 1: FORWARD BEND—ARMS BEHIND

Bowing Warrior with Hands in Prayer

Nama Virabhadrasana Namaskar

(NUH-muh vee-ruh-buh-DRAHS-uh-nuh nuh-muhs-KAHR)

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

ल व ह



Bowing Hands Bound Warrior

Nama Baddha Hasta Virabhadrasana

(NUH-muh BUH-duh HUH-stuh vee-ruh-buh-DRAHS-uh-nuh)

Modification: grabbing onto the triceps behind the back

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

ल व ह



Bowing Reverse Prayer Warrior

Nama Viparita Namaskar Virabhadrasana

(NUH-muh vi-puh-REE-tuh nuh-muhs-KAHR vee-ruh-buh-DRAHS-uh-nuh)

Also Known As: Bowing Back of the Body Prayer Warrior (Nama Paschima Namaskara Virabhadrasana)
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
लं वं हं



Bowing Hands Bound Warrior Pose

Nama Baddha Hasta Virabhadrasana

(NUH-muh BUH-duh HUH-stuh vee-ruh-buh-DRAHS-uh-nuh)

Also Known As: Warrior Veerastambana Pose (Veerastambanasana), Bound Hands Side Angle Pose (Baddha Hasta Parshva Konasana)
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
लं वं यं ॐ



Bowing Hands Bound Warrior Pose

Nama Baddha Hasta Virabhadrasana

(NUH-muh BUH-duh HUH-stuh vee-ruh-buh-DRAHS-uh-nuh)

Also Known As: Bound Hands Side Angle Pose (Baddha Hasta Parshva Konasana)
Modification: arms bound around the front leg
Pose Type: standing, forward bend, binding
Drishti Point: Padhayoragrai or Padayoragre (toes/feet)
ल व य ह



SIDE ANGLE POSE: HEAD BEHIND LEG

One Foot Behind the Head Side Angle Pose

Eka Pada Shirsha Parshva Konasana

(EY-kuh PUH-duh SHEER-shuh pahrsh-vuh-ko-NAHS-uh-nuh)

Modification: arms crossed in front of the chest
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व



One Foot Behind the Head Side Angle Pose

Eka Pada Shirsha Parshva Konasana

(EY-kuh PUH-duh SHEER-shuh pahrsh-vuh-ko-NAHS-uh-nuh)

Modification: palms together, arms straight on the floor
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



One Foot Behind the Head Bound Side Angle Pose

Eka Pada Shirsha Baddha Parshva Konasana

(EY-kuh PUH-duh SHEER-shuh BUH-duh pahrsh-vuh-ko-NAHS-uh-nuh)

Pose Type: standing, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)



LUNGE: BACK KNEE ON THE FLOOR

Equestrian Riding Horse Lunge Pose

Ashva Sanchalanasana

(UHSH-vuh suhn-chuh-luh-NAHS-uh-nuh)

Modification: back knee on the floor, hands to the floor on either side of the front foot, looking up to the sky
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र ह ॐ



Equestrian Riding Horse Lunge Pose Prep.

Ashva Sanchalanasana Prep.

(UHSH-vuh suhn-chuh-luh-NAHS-uh-nuh)

Also Known As: Son of Anjani (Lord Hanuman) Lunge Pose Prep. (Anjaneyasana Prep.)
Modification: back knee on the floor, both hands on the front knee
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)



LUNGE: BACK KNEE ON THE FLOOR—FORWARD BEND

Hands Bound Extended Lizard Tail Lunge Pose

Baddha Hasta Uttana Pristhasana

(BUH-duh HUH-stuh ut-TAHN-uh prish-TAHS-uh-nuh)

Also Known As: Bowing Warrior Pose Prep. (Nama Virabhadrasana Prep.)
Modification: back knee on the floor, forehead to the floor
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Tip Toe Extended Lizard Tail Lunge Pose

Prapada Uttana Pristhasana

(PRUH-puh-duh ut-TAHN-uh prish-TAHS-uh-nuh)

Modification: back knee on the floor, shoulder to the back of the knee, one arm straight out in front, other arm straight to the back, forehead to the floor
Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)



Extended Lizard Tail Lunge Pose

Uttana Pristhasana

(ut-TAHN-uh prish-TAHS-uh-nuh)

Modification: back knee on the floor
1. forearms to the floor on the inside of the foot
2. forearms to the floor on either side of the foot

Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)


1.


2.

Unsupported Extended Lizard Tail Lunge Pose

Niralamba Uttana Pristhasana

(nir-AH-luhm-buh ut-TAHN-uh prish-TAHS-uh-nuh)

Also Known As: God Favour Seeking Sacrifice Ritual Pose (Yajnasana), Christ’s Cross Pose
Modification: arms straight out to the sides
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Bound Extended Lizard Tail Lunge Pose

Baddha Uttana Pristhasana

(BUH-duh ut-TAHN-uh prish-TAHS-uh-nuh)

Also Known As: Bound God Favor Seeking Sacrifice Ritual Pose (Baddha Yajnasana), Bound Christ’s Cross Pose)
Modification: back knee on the floor
Pose Type: standing, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)



Hands Spread Out Extended Lizard Tail Lunge Pose

Prasarita Hasta Uttana Pristhasana

(pruh-SAH-ri-tuh HUH-stuh ut-TAHN-uh prish-TAHS-uh-nuh)

Also Known As: God Favour Seeking Sacrifice Ritual Pose (Yajnasana), Christ’s Cross Pose
Modification: back knee on the floor, shin to the tricep
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



LUNGE: BACK KNEE ON THE FLOOR—BACKBEND—ARMS BEHIND THE BACK

Bound Hands Son of Anjani (Lord Hanuman) Lunge Pose

Baddha Hasta Anjaneyasana *(BUH-duh HUH-stuh uhn-juh-ney-AHS-uh-nuh)*

Also Known As: Open Heart Chakra Hands Bound Equestrian Riding Horse Pose (Anahata Chakra Baddha Hasta Ashva Sanchalanasana)
Modification: back knee on the floor, backbend, hands to the floor on the inside of the back knee
Pose Type: standing, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Son of Anjani (Lord Hanuman) Lunge Pose

Anjaneyasana *(uhn-juh-ney-AHS-uh-nuh)*
Also Known As: Open Heart Chakra Equestrian Riding Horse Pose (Anahata Chakra Ashva Sanchalanasana)
Modification: back knee on the floor, backbend, fingertips to the floor on either side of the back knee
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One Hand Son of Anjani (Lord Hanuman) Lunge Pose

Eka Hasta Anjaneyasana *(EY-kuh HUH-stuh uhn-juh-ney-AHS-uh-nuh)*
Also Known As: Equestrian Riding Horse Pose (Ashva Sanchalanasana)
Modification: back knee on the floor, one arm extended up over the head, other hand to the floor
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



LUNGE: BACK KNEE ON THE FLOOR—BACKBEND—ARMS UP OVER THE HEAD

Son of Anjani (Lord Hanuman) Lunge Pose

Anjaneyasana *(uhn-juh-ney-AHS-uh-nuh)*
Also Known As: Crescent Lunge Pose
Modification: front heel on the floor, back knee down, back toes curled in; arms shoulder width apart, fingertips up to the sky
Pose Type: standing, mild backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



Tip Toe Son of Anjani (Lord Hanuman) Lunge Pose

Prapada Anjaneyasana *(PRUH-puh-duh uhn-juh-ney-AHS-uh-nuh)*
Also Known As: Tip Toe Crescent Lunge Pose
Modification: front heel off the floor, back knee down, back toes curled in; arms shoulder width apart, fingertips up to the sky
Pose Type: standing, mild backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



Son of Anjani (Lord Hanuman) Lunge Pose

Anjaneyasana *(uhn-juh-ney-AHS-uh-nuh)*
Also Known As: Monkey Pose (Kapyasana), Crescent Lunge Pose
Modification: arms up over the head, back knee on the floor, palms pressed together
Pose Type: standing, mild backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Angusthamadhye or Angustha Ma Dyai (thumbs)



Standing Pose of the Heavenly Spirits Prep.

Stiti Valakhilyasana Prep. *(STI-ti VAH-luh-kil-YAHS-uh-nuh)*
Also Known As: Nindra Valakhilyasana; Son of Anjani (Lord Hanuman) Lunge Pose (Anjaneyasana), Crescent Lunge Pose)
Modification: back knee on the floor, arms up over the head, palms open to the sky, arms parallel to the floor
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Standing Pose of the Heavenly Spirits

Stiti Valakhilyasana *(STI-ti VAH-luh-kil-YAHS-uh-nuh)*
Also Known As: Nindra Valakhilyasana
Modification: back knee to the floor, grabbing the back heel with overhead grip
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



LUNGE: BACK KNEE ON THE FLOOR—TWISTS AND SIDE BENDS

Sideways Son of Anjani (Lord Hanuman) Lunge Pose

Parshva Anjaneyasana
(PAHRSH-vuh uhn-juh-ney-AHS-uh-nuh)
Modification: back knee on the floor; one hand to the inside of the opposite knee, other arm up over the head
Pose Type: standing, side bend, backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व र य



Revolved Paying Homage Lunge Pose

Parivritta Namasyasana

(puh-ri-VRIT-tuh nuh-muh-SYAHS-uh-nuh)

Also Known As: Curtsey Lunge
Modification: front leg crossed over to the side, opposite elbow over the front knee, back knee on the floor
Pose Type: standing, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Revolved Son of Anjani (Lord Hanuman) Lunge Pose

Parivritta Anjaneyasana

(puh-ri-VRIT-tuh uhn-juh-ney-AHS-uh-nuh)

Modification: back knee on the floor, toes curled in; one hand to the floor, other arm up in the sky; twisting to the inside of the front knee
Pose Type: standing, twist
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Tip Toe Sideways Son of Anjani (Lord Hanuman) Lunge Pose

Prapada Parshva Anjaneyasana

(PRUH-puh-duh PAHRSH-vuh uhn-juh-ney-AHS-uh-nuh)

Modification: back knee on the floor, toes pointed to the back, one hand to the floor, other arm up in the sky, twisting to the outside of the front knee
Pose Type: standing, twist
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Revolved Son of Anjani (Lord Hanuman) Lunge Pose

Parivritta Anjaneyasana

(puh-ri-VRIT-tuh uhn-juh-ney-AHS-uh-nuh)

Also Known As: Revolved Monkey Pose (Parivritta Anjaneyasana)
Modification: back knee on the floor
Pose Type: standing, twist
Drishti Point: Padhayoragrai or Padayoragre (toes/feet)



Tip Toe Revolved Son of Anjani (Lord Hanuman) Lunge Pose

Prapada Parivritta Anjaneyasana

(PRUH-puh-duh puh-ri-VRIT-tuh uhn-juh-ney-AHS-uh-nuh)

Pose Type: standing, twist

Drishti Point: Nasagrai or Nasagre (nose)



Horse Pose Prep.

Vatayanasana Prep.

(vah-tah-yuh-NAHS-uh-nuh)

Modification: back knee and foot on the floor

Pose Type: standing

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Fighting Warrior Pose 1

Yudhasana 1

(yu-DAHS-uh-nuh)

Pose Type: standing
Drishti Point: Hastagrai or Hastagre (hands)



Fighting Warrior Pose 2

Yudhasana 2

(yu-DAHS-uh-nuh)

Modification: back knee on the floor
Pose Type: standing
Drishti Point: Hastagrai or Hastagre (hands)



LUNGE: BACK KNEE ON THE FLOOR UNDER THE HIP SOCKET—FORWARD BEND

Half Equestrian Riding Horse Lunge Pose

Ardha Ashva Sanchalanasana

(UHR-duh UHSH-vuh suhn-chuh-luh-NAHS-uh-nuh)

Modification: spine in Cat Tilt, back knee down, toes pointing away from the head
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
● ● ● ●



Tip Toe Bound Son of Anjani (Lord Hanuman) Lunge Pose

Prapada Baddha Anjaneyasana

(PRUH-puh-duh BUH-duh uhn-juh-ney-AHS-uh-nuh)
Modification: front leg bound, back knee on the floor, toes pointing away from the head
Pose Type: standing, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)
● ●



One Foot Behind the Head Extended Lizard Tail Lunge Pose

Eka Pada Shirsha Uttana Pristhasana

(EY-kuh PUH-duh SHEER-shuh ut-TAHN-uh prish-TAHS-uh-nuh)
Modification: back knee under the hip, toes pointing away from the head
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



One Foot Behind the Head Extended Lizard Tail Lunge Pose

Eka Pada Shirsha Uttana Pristhasana

(EY-kuh PUH-duh SHEER-shuh ut-TAHN-uh prish-TAHS-uh-nuh)

Modification: legs working toward full vertical splits, toes of the back leg curled in
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



LUNGE: BACK KNEE ON THE FLOOR UNDER THE HIP SOCKET—BACKBEND

Son of Anjani (Lord Hanuman) Lunge Pose

Anjaneyasana

(uhn-juh-ney-AHS-uh-nuh)

Modification: deep backbend; chest open, arms to the side, elbows bent; back knee on the floor, toes pointing away from the head
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Tip Toe One Hand to Foot Son of Anjani (Lord Hanuman) Lunge Pose

Prapada Eka Hasta Pada Anjaneyasana

(PRUH-puh-duh EY-kuh HUH-stuh PUH-duh uhn-juh-ney-AHS-uh-nuh)

Modification: deep backbend; hand to the ankle on the same side
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Both Hands to Foot Son of Anjani (Lord Hanuman) Lunge Pose

Dwi Hasta Pada Anjaneyasana

(DWI-huh-stuh PUH-duh uhn-juh-ney-AHS-uh-nuh)

Modification: backbend
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Tip Toe Both Hands to Foot Son of Anjani (Lord Hanuman) Lunge Pose

Prapada Dwi Hasta Pada Anjaneyasana

(PRUH-puh-duh DWI-huh-stuh PUH-duh uhn-juh-ney-AHS-uh-nuh)

Modification: deep backbend, back knee on the floor, back toes curled in
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



LUNGE: BACK KNEE ON THE FLOOR—FOOT OFF THE FLOOR

One-Legged King Pigeon Pose 2 Prep.

Eka Pada Raja Kapotasana 2 Prep.

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: arms open wide and raised
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Half Bound Revolved One-Legged King Pigeon Pose 2 Prep.

Ardha Baddha Parivritta Eka Pada Raja Kapotasana 2 Prep.

(UHR-duh BUH-duh puh-ri-VRIT-tuh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Pose Type: standing, twist, binding
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
लं वं



Tip Toe Extended Lizard Tail Lunge Pose Prep.

Prapada Uttana Pristhasana Prep.

(PRUH-puh-duh ut-TAHN-uh prish-TAHS-uh-nuh)

Modification: arms straight to semi-straight, back foot lifted off the floor
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं वं हं ॐ



Bound Revolved Side Angle Pose Prep.

Baddha Parivritta Parshva Konasana Prep.

(BUH-duh puh-ri-VRIT-tuh pahrsh-vuh-ko-NAHS-uh-nuh)

Also Known As: Bound Revolved Son of Anjani (Lord Hanuman) Lunge Pose Prep. (Anjaneyasana Prep.)
Modification: back knee bent, heel toward the sitting bone
Pose Type: standing, forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व र



Foot to Knee Revolved Son of Anjani (Lord Hanuman) Lunge Pose with Hands in Prayer

Janu Pada Parivritta Anjaneyasana Namaskar

(JAH-nu PUH-duh puh-ri-VRIT-tuh uhn-juh-ney-AHS-uh-nuh nuh-muhs-KAHR)

Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व र



LUNGE: BACK KNEE ON THE FLOOR—GRABBING ONTO THE BACK FOOT

Tip Toe One-Legged King Pigeon Pose 2 Prep.

Prapada Eka Pada Raja Kapotasana 2 Prep.

(PRUH-puh-duh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: both hands grabbing onto the back foot with under-head grip
Pose Type: standing, mild backbend
Drishti Point: Nasagrai or Nasagre (nose)



Revolved One-Legged King Pigeon Pose 2 Prep.

Parivritta Eka Pada Raja Kapotasana 2 Prep.

(puh-ri-VRIT-tuh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: grabbing onto the back foot with the opposite hand using an under-head grip, twisting toward the front knee
Pose Type: standing, twist
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



One Hand in Prayer Revolved One-Legged King Pigeon Pose 2 Prep.

Eka Hasta Namaskar Parivritta Eka Pada Raja Kapotasana 2 Prep.

(EY-kuh HUH-stuh nuh-muhs-KAHR puh-ri-VRIT-tuh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: opposite hand to the back foot, other hand to the heart
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



One Hand to Foot Extended Lizard Tail Lunge Pose

Eka Hasta Pada Uttana Pristhasana

(EY-kuh HUH-stuh PUH-duh ut-TAHN-uh prish-TAHS-uh-nuh)

Modification: forward bend, elbow to the floor, grabbing onto the back foot with opposite hand, heel to the glutes
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



LUNGE: BACK KNEE ON THE FLOOR—FOOT TO THE HIP SOCKET

Spear Pose Prep.

Kuntasana Prep.

(kun-TAHS-uh-nuh)

Modification: grabbing onto the foot with one hand, arm crossed over in front, other arm parallel to the floor, foot away from the hip
Pose Type: standing, twist
Drishti Point: Hastagrai or Hastagre (hands)
ल व य



Spear Pose

Kuntasana

(kun-TAHS-uh-nuh)

Modification: grabbing onto the foot with one hand, arm crossed over in front, other hand to the knee, foot close to the hip
Pose Type: standing, twist
Drishti Point: Hastagrai or Hastagre (hands)



Both Hands Bound Revolved Spear Pose Prep.

Dwi Hasta Baddha Parivritta Kuntasana Prep.

(dwi HUH-stuh BUH-duh puh-ri-VRIT-tuh kun-TAHS-uh-nuh)

Pose Type: standing, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Spear Pose with Hands in Prayer

Kuntasana Namaskar

(kun-TAHS-uh-nuh nuh-muhs-KAHR)

Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)



Half Bound Revolved Spear Pose Prep.

Ardha Baddha Parivritta Kuntasana Prep.

(UHR-duh-BUH-duh puh-ri-VRIT-tuh kun-TAHS-uh-nuh)

Modification: foot to the inside of the elbow
Pose Type: standing, twist, binding
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Spear Pose

Kuntasana

(kun-TAHS-uh-nuh)

Pose Type: standing
Drishti Point: Hastagrai or Hastagre (hands)



Hands Bound Ankle Stretch Pose

Baddha Hasta Kulpasana

(BUH-duh HUH-stuh kul-PAHS-uh-nuh)

Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



LUNGE: BACK KNEE ON THE FLOOR—HEAD BEHIND THE FRONT LEG, GRABBING ONTO THE BACK FOOT

One Foot Behind the Head Extended Lizard Tail Lunge Pose

Eka Pada Shirsha Uttana Pristhasana

(EY-kuh PUH-duh SHEER-shuh ut-TAHN-uh prish-TAHS-uh-nuh)

Modification: grabbing onto the foot with the opposite hand, back knee under the hips
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



One Foot Behind the Head Extended Lizard Tail Lunge Pose

Eka Pada Shirsha Uttana Pristhasana

(EY-kuh PUH-duh SHEER-shuh ut-TAHN-uh prish-TAHS-uh-nuh)

Modification: grabbing onto the foot with the opposite hand, chest and quadriceps on the floor
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



LUNGE: BACK KNEE ON FLOOR—ONE-LEGGED KING PIGEON 2

One-Legged King Pigeon Pose 2 Prep.

Eka Pada Raja Kapotasana 2 Prep.

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: back knee bent toward the glutes, front heel down; arms on the sides, spine straight
Pose Type: standing
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Tip Toe One-Legged King Pigeon Pose 2 Prep.

Prapada Eka Pada Raja Kapotasana 2 Prep.

(PRUH-puh-duh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: back knee bent toward the glutes, heel of the top foot up; hands on the hips, backbend
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं वं यं हं ॐ



One-Legged King Pigeon Pose 2

Eka Pada Raja Kapotasana 2

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: prep.—arms up over the head, back knee bent toward the glutes
Pose Type: standing, mild backbend
Drishti Point: Nasagrai or Nasagre (nose)
लं वं यं



Tip Toe One-Legged King Pigeon Pose 2 Prep.

Prapada Eka Pada Raja Kapotasana 2 Prep.

(PRUH-puh-duh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: fingertips to the floor, front heel lifted

Pose Type: standing, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Intense Ankle Stretch One-Legged King Pigeon Pose 2

Uttana Kulpa Eka Pada Raja Kapotasana 2

(ut-TAH-nuh kul-puh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: prep.—fingertips to the floor, front toes curled under

Pose Type: standing, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

One-Legged King Pigeon Pose 2 Prep.

Eka Pada Raja Kapotasana 2 Prep.

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: 1. grabbing onto the foot on the same side
2. grabbing onto the foot with the hand on the same side, foot toward the hip
3. grabbing onto the foot with the opposite hand, foot twisted toward the opposite glute
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ







Revolved One-Legged King Pigeon Pose 2

Parivritta Eka Pada Raja Kapotasana 2

(puh-ree-VRIT-tuh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Pose Type: standing, forward bend, twist

Drishti Point: Parsva Drishti (to the right), Parsva Drishti (to the left)

ल व



Mermaid Pose 2

Naginyasana 2

(nuh-gin-YAHS-uh-nuh)

Pose Type: standing, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व र य ह ॐ ॐ

LUNGE: BACK KNEE ON FLOOR—ONE-LEGGED KING PIGEON 2—OVERHEAD GRIP

One-Legged King Pigeon Pose 2

Eka Pada Raja Kapotasana 2

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: grabbing onto the foot with the opposite hand, palm of the other hand to the floor on the side

1. foot to the head
2. heel to the forehead

Pose Type: standing, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





One-Legged King Pigeon Pose 2

Eka Pada Raja Kapotasana 2

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: both hands grabbing onto the foot
1. foot to the head
2. heel to the forehead

Pose Type: standing, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Half Bound One-Legged King Pigeon Pose 2

Ardha Baddha Eka Pada Raja Kapotasana 2

(UHR-duh BUH-duh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Pose Type: standing, backbend, binding

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



LUNGE: BACK KNEE ON FLOOR—ONE-LEGGED KING PIGEON 2—FOOT TO THE BACK OF THE HEAD

Necklace Pose Prep.

Graivasana Prep.

(gr-eye-VAHS-uh-nuh)
Also Known As: Chain Pose (Gaivasana)
Modification: back foot to the back of the head, hands to the floor
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Necklace Pose Prep.

Graivasana Prep.

(gr-eye-VAHS-uh-nuh)
Also Known As: Chain Pose (Gaivasana)
Modification: back foot to the back of the head, hands in Anjali Mudra (Hands in Prayer)
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



LUNGE: BACK KNEE ON FLOOR—ONE-LEGGED KING PIGEON 2—ARM CROSSED OVER IN FRONT

Bound Hand to Foot Supported One-Legged King Pigeon Pose 2

Baddha Hasta Pada Salamba Eka Pada Raja Kapotasana 2

(BUH-duh HUH-stuh PUH-duh SAH-luhm-buh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: arm crossed in front of the neck, other hand to the floor
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Bound Hand to Foot Unsupported One-Legged King Pigeon Pose 2

Baddha Hasta Pada Niralamba Eka Pada Raja Kapotasana 2

(BUH-duh HUH-stuh PUH-duh nir-AH-luhm-buh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: arm crossed in front of the neck, other arm straight out in front
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

LUNGE: FRONT LEG STRAIGHT—BACKBEND

Both Hands to Foot Son of Anjani (Lord Hanuman) Lunge Pose

Dwi Hasta Pada Anjaneyasana

(DWI-huh-stuh PUH-duh uhn-juh-ney-AHS-uh-nuh)

Modification: front leg straight
1. back knee on the floor
2. back knee off the floor

Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





2.

Gate Pose

Parighasana

(puh-ri-GAHS-uh-nuh)

Pose Type: standing, side bend

Drishti Point: Hastagrai or Hastagrahe (hands)

How to Perform the Pose:

1. Begin by standing on your knees with sitting bones lifted off the feet. (Make sure your knees are comfortable by rolling up the yoga mat a couple of times.) Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale and extend your right leg straight out to the side with the right foot on the floor. You can either point the toes to the right (Pose #1) or point your toes straight ahead, lifting the arch and pressing the outside edge of the right foot to the floor (Pose #2).
3. Inhale as you expand your chest and hold your arms straight out to the sides, parallel to the floor.
4. On your next exhale, side bend to the right and bring your right hand onto your right shin (Pose #2), while extending your left arm over your head to the right with the palm facing down. Make sure your chest is rotated to face forward and not collapsing toward the floor. Look toward your right hand. You can also experiment with dropping your right palm to the floor on the inside of your right leg (Pose #1).
5. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch. Inhale as you come up and bring your right knee back to the floor by your left knee. Repeat on the other side.

Modification: bending to the opposite side of the bent knee on the floor
1. palm to the floor, toes of the straight leg pointing to the side
2. hand on the shin, toes of the straight leg pointing straight ahead

parigha = iron bar used for locking a gate

1.



2.



Gate Pose

Parighasana

(puh-ri-GAHS-uh-nuh)

Modification: bending to the side of the bent knee on the floor, hand to the floor on the outside of the bent leg, toes of the straight leg pointing straight ahead
Pose Type: standing, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Half Bound Gate Pose

Ardha Baddha Parighasana

(UHR-duh BUH-duh puh-ri-GAHS-uh-nuh)

Modification: bending to the side of the bent knee on the floor, forearm to the floor on the side of the bent leg, toes of the straight leg pointing straight ahead
Pose Type: standing, side bend, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Gate Pose

Parighasana

(puh-ri-GAHS-uh-nuh)

Modification: bending to the opposite side of the bent knee on the floor, forearm to the floor, toes of the straight leg pointing to the side
Pose Type: standing, forward bend, side bend
Drishti Point: Hastagrai or Hastagre (hands)
लं वं यं हं



ONE LEG STRAIGHT OTHER KNEE ON THE FLOOR: SIDE BEND & BINDING

Gate Pose

Parighasana

(puh-ri-GAHS-uh-nuh)

Modification: bending to the opposite side of the bent knee on the floor, palm to the top of the foot of the straight leg, toes of the straight leg pointing to the side
Pose Type: standing, forward bend, side bend
Drishti Point: Hastagrai or Hastagre (hands)
लं वं



Gate Pose

Parighasana

(puh-ri-GAHS-uh-nuh)

Modification: bending to the opposite side of the bent knee on the floor, both hands to the top of the foot of the straight leg, toes of the straight leg pointing to the side
Pose Type: standing, forward bend, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Revolved Half Bound Gate Pose

Parivritta Ardha Baddha Parighasana

(puh-ri-VRIT-tuh UHR-duh BUH-duh puh-ri-GAHS-uh-nuh)

Modification: hand to the floor on the outside of the straight leg, rotating the chest to the sky, toes of the straight leg pointing to the side
Pose Type: standing, side bend, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Revolved Bound Gate Pose

Parivritta Baddha Parighasana

(puh-ri-VRIT-tuh BUH-duh puh-ri-GAHS-uh-nuh)

Modification: toes of the straight leg flexed in, toes of the bent leg pointing away from the head

Pose Type: standing, forward bend, side bend, binding

Drishti Point: Urdhva or Antara Drishti (up to the sky)



Revolved Bound Half Lotus Gate Pose

Parivritta Baddha Ardha Padma Parighasana

(puh-ri-VRIT-tuh BUH-duh UHR-duh PUHD-muh puh-ri-GAHS-uh-nuh)

Modification: toes of the straight leg pointing to the side

Pose Type: standing, side bend, binding

Drishti Point: Urdhva or Antara Drishti (up to the sky)



ONE LEG STRAIGHT OTHER KNEE ON THE FLOOR: TWISTS

Revolved Gate Pose

Parivritta Parighasana

(puh-ri-VRIT-tuh puh-ri-GAHS-uh-nuh)

Modification: forearm to the floor, hand grabbing onto the opposite foot, other arm straight up to the sky, toes of the straight leg pointed to the side, toes of the bent leg pointing away from the head
Pose Type: standing, forward bend, twist
Drishti Point: Hastagrai or Hastagre (hands)



Revolved Half Bound Gate Pose

Parivritta Ardha Baddha Parighasana

(puh-ri-VRIT-tuh UHR-duh BUH-duh puh-ri-GAHS-uh-nuh)

Modification: forearm to the floor, twisting toward the straight leg, toes of the straight leg pointing to the side
Pose Type: standing, forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Half Pose Dedicated to Lord Hanuman

Ardha Hanumanasana

(UHR-duh huh-nu-mahn-AHS-uh-nuh)

Also Known As: Pose Dedicated to Lord Hanuman Prep. (Hanumanasana Prep.)
Modification: back toes pointed away from the head, fingertips to the floor on the outsides of the straight leg
Pose Type: standing, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Half Pose Dedicated to Lord Hanuman

Ardha Hanumanasana

(UHR-duh huh-nu-mahn-AHS-uh-nuh)

Also Known As: Pose Dedicated to Lord Hanuman Prep. (Hanumanasana Prep.)
Modification: back toes curled in, toes of the straight leg flexed in, arms extended to the front, fingertips to the floor
Pose Type: standing, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Half Bound Half Pose Dedicated to Lord Hanuman

Ardha Baddha Ardha Hanumanasana

(UHR-duh BUH-duh UHR-duh huh-nu-mahn-AHS-uh-nuh)

Also Known As: Pose Dedicated to Lord Hanuman Prep. (Hanumanasana Prep.)
Modification: toes of the bent leg pointed away from the head
Pose Type: standing, forward bend, binding
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Half Pose Dedicated to Lord Hanuman

Ardha Hanumanasana

(UHR-duh huh-nu-mahn-AHS-uh-nuh)

Also Known As: Pose Dedicated to Lord Hanuman Prep. (Hanumanasana Prep.)
Modification: toes of the straight leg flexed in; hand grabbing onto the back foot on the same side, heel to the sitting bone
Pose Type: standing, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Half Lotus Half Pose Dedicated to Lord Hanuman

Ardha Padma Ardha Hanumanasana

(UHR-duh PUHD-muh UHR-duh huh-nu-mahn-AHS-uh-nuh)

Also Known As: Pose Dedicated to Lord Hanuman Prep. (Hanumanasana Prep.)
Modification: fingertips of both hands on the sides of the straight leg
Pose Type: standing, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
ल व



HORSE POSE: FORWARD BEND, BINDING & TWIST

Revolved Leg Position of Horse Pose with Hands in Prayer

Parivritta Pada Vatayanasana Namaskar

(puh-ri-VRIT-tuh PUH-duh vah-tah-yuh-NAHS-uh-nuh nuh-muhs-KAHR)

Pose Type: standing, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व र



Half Lotus Extended Lizard Tail Lunge Pose

Ardha Padma Uttana Pristhasana

(UHR-duh PUHD-muh ut-TAHN-uh prish-TAHS-uh-nuh)

Modification: 1. palms to the floor, elbows bent 90 degrees
2. forearms to the floor
3. one forearm to the floor; other elbow to the floor, hand to the face
Pose Type: standing, forward bend
Drishti Point: 1 & 3. Nasagrai or Nasagre (nose)
2. Padhayoragrai or Padayoragre (toes/feet) and Angusthamadhye or Angushta Ma Dyai (thumbs)
लं वं हं

1.



2.





Bound Half Lotus Extended Lizard Tail Lunge Pose

Baddha Ardha Padma Uttana Pristhasana

(BUH-duh UHR-duh PUHD-muh ut-TAHN-uh prish-TAHS-uh-nuh)

Pose Type: standing, forward bend, binding
Drishti Point: Padayoragrai or Padayoragre (toes/feet)

ल व



One Foot Behind the Head Bound Half Lotus Extended Lizard Tail Lunge Pose

Eka Pada Shirsha Baddha Ardha Padma Uttan Pristhasana

(EY-kuh PUH-duh SHEER-shuh BUH-duh UHR-duh PUHD-muh ut-TAHN-uh prish-TAHS-uh-nuh)

Pose Type: standing, forward bend, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)

ल व



HORSE POSE: SPINE STRAIGHT

Half Bound Revolved Leg Position of Horse Pose

Ardha Baddha Parivritta Pada Vatayanasana

(UHR-duh BUH-duh puh-ri-VRIT-tuh PUH-duh vah-tah-yuh-NAHS-uh-nuh)

Modification: wrist to the knee of the front leg
Pose Type: standing, binding
Drishti Point: Hastagrai or Hastagre (hands)



Horse Pose

Vatayanasana

(vah-tah-yuh-NAHS-uh-nuh)

Also Known As: Sea Horse Pose
Modification: 1. Front View
2. Side View
Pose Type: standing
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)


1.


2.

ONE KNEE BENT TOWARD THE HIP: SPINE STRAIGHT

One-Legged Frog Pose in Camel Pose

Eka Pada Bhekasana in Ushtrasana

(EY-kuh PUH-duh bey-KAHS-uh-nuh in oosh-TRAHS-uh-nuh)

Modification: spine straight

Pose Type: standing (on the knees)

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Mermaid Arm Position in Half Camel Pose

Hasta Naginyasana in Ardha Ushtrasana

(HUH-stuh nuh-gin-YAHS-uh-nuh in UHR-duh oosh-TRAHS-uhna)

Modification: spine straight
Pose Type: standing (on the knees), mild backbend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ॐ



Revolved One-Legged Frog Pose in One-Legged King Pigeon 1 Version B

Parivritta Eka Pada Bhekasana in Eka Pada Raja Kapotasana 1 B

(puh-ri-VRIT-tuh EY-kuh PUH-duh bey-KAHS-uh-nuh in EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: fingertips to the floor in front
Pose Type: standing (on the knees), twist, binding
Drishti Point: Padhayoragrai or Padayoragre (toes/feet)
ल व य



Half Bound Revolved One-Legged Frog Pose in One-Legged King

Pigeon 1 Version B

Ardha Baddha Parivritta Eka Pada Bhekasana in Eka Pada Raja Kapotasana 1 B

(UHR-duh BUH-duh puh-ri-VRIT-tuh EY-kuh PUH-duh bey-KAHS-uh-nuh in EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Pose Type: standing (on the knees), twist, binding
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



COW FACE POSE AND GARUDA ON THE KNEES

Leg Position of Cow Face Pose on the Knees

Janu Pada Gomukhasana

(JAH-nu PUH-duh go-moo-KAHS-uh-nuh)

Modification: hands on the hips
Pose Type: standing (on the knees)
Drishti Point: Nasagrai or Nasagre (nose)



Leg Position of Cow Face Pose on the Knees

Janu Pada Gomukhasana

(JAH-nu PUH-duh go-moo-KAHS-uh-nuh)

Modification: 1. one hand on the hip, other arm straight over the head, side bend
2. one arm crossed in front of the body, other arm over the head, elbow bent, side bend
Pose Type: 1. standing (on the knees)
2. standing (on the knees), side bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Hastagrai or Hastagre (hands)
लं वं





KNEES ON THE FLOOR: LOTUS POSE

Half Pose Dedicated to Sage Goraksha

Ardha Gorakshasana

(UHR-duh go-rak-SHAHS-uh-nuh)

Modification: spine straight, one hand to the heart, other hand to the side of the thigh
Pose Type: standing (on the knees), balance
Drishti Point: Nasagrai or Nasagre (nose), Hastagrai or Hastagre (hands)
लं वं



Pose Dedicated to Sage Goraksha

Gorakshasana

(go-ruhk-SHAHS-uh-nuh)

Also Known As: Yogic Seat Pose A (Yogapithasana A)
Modification: hands in Anjali Mudra (Hands in Prayer)
Pose Type: standing (on the knees), balance
Drishti Point: Nasagrai or Nasagre (nose), Hastagrai or Hastagre (hands)



LUNGE: BACK KNEE OFF THE FLOOR

Fighting Warrior Pose 2

Yudhasana 2

(yu-DAHS-uh-nuh)

Modification: back knee off the floor
Pose Type: standing
Drishti Point: Hastagrai or Hastagre (hands)



Son of Anjani (Lord Hanuman) Lunge Pose

Anjaneyasana

(uhn-juh-ney-AHS-uh-nuh)

Modification: arms open wide, forward bend, back knee bent and off the floor
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व र ह



Son of Anjani (Lord Hanuman) Lunge Pose

Anjaneyasana

(uhn-juh-ney-AHS-uh-nuh)

Also Known As: Warrior 1 Modification (Virabhadrasana 1 Modification)
Modification: hands on the hips, back knee off the floor
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)
ल व

Equestrian Riding Horse Pose

Ashva Sanchalanasana

(UHSH-vuh suhn-chuh-luh-NAHS-un-nuh)

Pose Type: standing, forward bend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) or Padhayoragrai or Padayoragre (toes/feet)

How to Perform the Pose:

1. Begin in Intense Stretch Pose (*Uttanasana*), also known as Full Forward Bend Pose. Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Inhale and bend your knees enough for your fingertips to touch the floor on the sides of the feet.
3. Exhale as you step your left foot to the back, keeping your toes curled in, your left knee off the floor and keep your left leg strong and straight. Make sure your right knee is on top of your right ankle to prevent wear and tear on your knee joint.
4. Rest your torso on your right thigh. Inhale as you lengthen your spine, stretching your body in two opposing directions: crown of the head moving to the front and the heel of the right foot pushing to the back. You can look at the toes of the right foot.
5. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch.
6. Exhale as you step your left foot to the front in line with your right foot, and repeat on the other side.

Modification: back knee off the floor, fingertips off the floor on either side of the front foot

ashva sanchala = horse, riding posture

Reverse Prayer Son of Anjani (Lord Hanuman) Lunge Pose

Viparita Namaskar Anjaneyasana

(vi-puh-REE-tuh nuh-muhs-KAHR uhn-juh-ney-AHS-uh-nuh)

Also Known As: Back of the Body Prayer Son of Anjani (Lord Hanuman) Lunge Pose (Paschima Namaskara Anjaneyasana)
Modification: back knee off the floor
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)



Son of Anjani (Lord Hanuman) Lunge Pose

Anjaneyasana

(uhn-juh-ney-AHS-uh-nuh)

Modification: palms together, thumbs to upper back, back knee off the floor
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)



Tip Toe One Hand Son of Anjani (Lord Hanuman) Lunge Pose

Prapada Eka Hasta Anjaneyasana

(PRUH-puh-duh EY-kuh HUH-stuh uhn-juh-ney-AHS-uh-nuh)

Modification: deep backbend, one arm up over the head; fingertips of the other hand to the floor, back knee off the floor
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Son of Anjani (Lord Hanuman) Lunge Pose

Anjaneyasana

(uhn-juh-ney-AHS-uh-nuh)

Also Known As: Warrior 1 Modification (Virabhadrasana 1 Modification), Crescent Lunge Pose
Modification: hands up over the head and shoulder width apart, back knee off the floor
Pose Type: standing, mild backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One Hand Rising Standing Pose of the Heavenly Spirits

Eka Hasta Utthita Stiti Valakhilyasana

(EY-kuh HUH-stuh UT-ti-tuh STI-ti vah-luh-khil-YAHS-uh-nuh)

Also Known As: Eka Hasta Utthita Nindra Valakhilyasana; Son of Anjani (Lord Hanuman) Lunge Pose (Anjaneyasana)

Modification: grabbing the back ankle overhead on the same side, other hand to the floor, back knee off the floor

Pose Type: standing, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Rising Standing Pose of the Heavenly Spirits

Utthita Stiti Valakhilyasana

(UT-ti-tuh STI-ti vah-luh-khil-YAHS-uh-nuh)

Also Known As: Utthita Nindra Valakhilyasana; Son of Anjani (Lord Hanuman) Lunge Pose (Anjaneyasana)

Modification: grabbing the back ankle overhead with both hands, back knee off the floor

Pose Type: standing, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Extended Lizard Tail Lunge Pose

Uttana Pristhasana

(ut-TAH-nuh prish-TAHS-uh-nuh)

Modification: elbows to the floor on the inside of the front leg, back knee off the floor
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
लं वं हं



Pose Dedicated to Sage Punnakeesar Lunge

Punnakeesarasana

(pu-nuh-kee-suh-RAHS-uh-nuh)

Also Known As: Bound God Favor Seeking Sacrifice Ritual Pose (Baddha Yajnasana), Bound Christ's Cross Pose
Modification: back knee off the floor
Pose Type: standing, forward bend, binding
Drishti Point: Padhayoragrai or Padayoragre (toes/feet)
लं वं हं



Extended Lizard Tail Lunge Pose

Uttana Pristhasana

(ut-TAH-nuh prish-TAHS-uh-nuh)

Modification: elbows bent at 90 degrees, palms to the floor, back knee off the floor
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Extended Lizard Tail Lunge Pose

Uttana Pristhasana

(ut-TAH-nuh prish-TAHS-uh-nuh)

Modification: forearms to the floor on either side of the front foot, back knee off the floor
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Tip Toe Extended Lizard Tail Lunge Pose

Prapada Uttana Pristhasana

(PRUH-puh-duh ut-TAH-nuh prish-TAHS-uh-nuh)

Modification: arms straight and reaching in the opposite directions, heel of the front leg up, top of the back foot to the floor, back knee off the floor
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व



LUNGE: BACK KNEE OFF THE FLOOR, BACK LEG STRAIGHT—TWISTS

Sideways Son of Anjani (Lord Hanuman) Lunge Pose

Parshva Anjaneyasana

(PAHRSH-vuh uhn-juh-ney-AHS-uh-nuh)

Modification: top of the back foot on the floor, back knee off the floor
Pose Type: standing, side bend, backbend
Drishti Point: Hastagrai or Hastagre (hands)
ल व र य



Revolved Son of Anjani (Lord Hanuman) Lunge Pose with Hands in Prayer

Parivritta Anjaneyasana Namaskar

(puh-ri-VRIT-tuh uhn-juh-ney-AHS-uh-nuh nuh-muhs-KAHR)

Modification: elbow over knee, back knee off the floor
Pose Type: standing, twist
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
ल व र य



Revolved Son of Anjani (Lord Hanuman) Lunge Pose with Hands in Prayer

Parivritta Anjaneyasana Namaskar

(puh-ri-VRIT-tuh uhn-juh-ney-AHS-uh-nuh nuh-muhs-KAHR)

Modification: arm under the knee, back knee off the floor
Pose Type: standing, twist
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
ल व र य



Bound Revolved Son of Anjani (Lord Hanuman) Lunge Pose

Baddha Parivritta Anjaneyasana

(BUH-duh puh-ri-VRIT-tuh uhn-juh-ney-AHS-uh-nuh)

Modification: back knee off the floor
Pose Type: standing, twist, binding
Drishti Point: Padhayoragrai or Padayoragre (toes/feet)
ल व र



Revolved Son of Anjani (Lord Hanuman) Lunge Pose

Parivritta Anjaneyasana

(puh-ri-VRIT-tuh uhn-juh-ney-AHS-uh-nuh)

Modification: one hand to the floor, other arm up in the sky, twisting to the inside of the front knee, back knee off the floor
Pose Type: standing, twist
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व य



Tip Toe Sideways Son of Anjani (Lord Hanuman) Lunge Pose

Prapada Parshva Anjaneyasana

(PRUH-puh-duh PAHRSH-vuh uhn-juh-ney-AHS-uh-nuh)

Modification: one hand to the floor, other arm up in the sky, twisting to the outside of the front knee, back knee off the floor
Pose Type: standing, twist
Drishti Point: Hastagrai or Hastagre (hands)



Revolved Paying Homage Lunge Pose

Parivritta Namasyasana

(puh-ri-VRIT-tuh nuh-muhs-YAHS-uh-muh)

Also Known As: Curtsey Lunge
Modification: front leg crossed over to the side, opposite elbow over the front knee, back knee off the floor
Pose Type: standing, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



SIDE LUNGE: SITTING BONES LIFTED—ARMS BELOW HEAD

Extended Leg to the Side Squat Pose

Utthita Parshva Pada Upaveshasana

(UT-ti-tuh PAHRSH-vuh PUH-duh u-puh-vey-SHAHS-uh-nuh)

Also Known As: Plyo Side Lunge
Modification: high stance, fingers interlocked in front of the chest
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)



Tip Toe Extended Leg to the Side Squat Pose

Prapada Utthita Parshva Pada Upaveshasana

(PRUH-puh-duh UT-ti-tuh PAHRSH-vuh PUH-duh u-puh-vey-SHAHS-uh-nuh)

Modification: high stance; arms straight out to the sides, toes of the straight leg flexed in
Pose Type: standing
Drishti Point: Hastagrai or Hastagre (hands)



Extended Leg to the Side Squat Pose

Utthita Parshva Pada Upaveshasana

(UT-ti-tuh PAHRSH-vuh PUH-duh u-puh-vey-SHAHS-uh-nuh)

Modification: arms crossed in front of the chest, forward bend
Pose Type: standing, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Extended Leg to the Side Squat Pose

Utthita Parshva Pada Upaveshasana

(UT-ti-tuh PAHRSH-vuh PUH-duh u-puh-vey-SHAHS-uh-nuh)

Modification: leaning toward the bent leg, one arm straight to the side, fingertips flexed in; other elbow to the side, fingertips to the back of the head
Pose Type: standing, side bend
Drishti Point: Hastagrai or Hastagre (hands)



SIDE LUNGE: SITTING BONES LIFTED—ARMS ABOVE THE HEAD

Extended Leg to the Side Squat Pose

Utthita Parshva Pada Upaveshasana

(UT-ti-tuh PAHRSH-vuh PUH-duh u-puh-vey-SHAHS-uh-nuh)

Modification: side bend toward the straight leg, one arm parallel to the floor, other arm extended to the sky

Pose Type: standing

Drishti Point: Hastagrai or Hastagre (hands)



SIDE LUNGE: SITTING BONES LIFTED—HANDS TO THE FLOOR

Tip Toe Extended Leg to the Side Squat Pose

Prapada Utthita Parshva Pada Upaveshasana

(PRUH-puh-duh UT-ti-tuh PAHRSH-vuh PUH-duh u-puh-vey-SHAHS-uh-nuh)

Modification: one palm to the floor

Pose Type: standing, forward bend

Drishti Point: Hastagrai or Hastagre (hands)



Extended Leg to the Side Squat Pose

Utthita Parshva Pada Upaveshasana

(UT-ti-tuh PAHRSH-vuh PUH-duh u-puh-vey-SHAHS-uh-nuh)

Modification: both hands to the floor, side bending toward the straight leg

Pose Type: standing, forward bend, side bend

Drishti Point: Hastagrai or Hastagre (hands)



Intense Ankle Stretch Extended Leg to the Side Squat Pose

Uttana Kulpa Utthita Parshva Pada Upaveshasana

(ut-TAH-nuh kul-puh UT-ti-tuh PAHRSH-vuh PUH-duh u-puh-vey-SHAHS-uh-nuh)

Modification: both palms to the floor, arms crossed

Pose Type: standing, forward bend, twist

Drishti Point: Urdhva or Antara Drishti (up to the sky)



SIDE LUNGE: SITTING BONES ON THE FLOOR

Lotus Hand Seal Extended Leg to the Side Squat Pose

Padma Mudra Utthita Parshva Pada Upaveshasana

(PUHD-muh MU-druh UT-ti-tuh PAHRSH-vuh PUH-duh u-puh-vey-SHAHS-uh-nuh)

Modification: forward bend, forehead to the floor, arms extended in front

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

ल व ह



Uneven Arms Extended Leg to the Side Squat Pose

Vishama Hasta Utthita Parshva Pada Upaveshasana

(VISH-uh-muh HUH-stuh UT-ti-tuh PAHRSH-vuh PUH-duh u-puh-vey-SHAHS-uh-nuh)

Modification: forward bend, one forearm to the floor, other hand to the face

Pose Type: standing, seated, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

ल व



Revolved Extended Leg to the Side Squat Pose 1

Parivritta Utthita Parshva Pada Upaveshasana 1

(puh-ri-VRIT-tuh UT-ti-tuh PAHRSH-vuh PUH-duh u-puh-vey-SHAHS-uh-nuh)

Modification: both hands to the foot of the straight leg

Pose Type: standing, seated, forward bend, side bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व य



Revolved Extended Leg to the Side Squat Pose 2

Parivritta Utthita Parshva Pada Upaveshasana 2

(puh-ri-VRIT-tuh UT-ti-tuh PAHRSH-vuh PUH-duh u-puh-vey-SHAHS-uh-nuh)
Modification: grabbing onto both feet
Pose Type: standing, seated, forward bend, side bend, twist
Drishti Point: Hastagrai or Hastagre (hands), Padayoragrai or Padayoragre (toes/feet)
ल व



SIDE LUNGE: SITTING BONES LIFTED—TWISTS AND BINDING

Extended Leg to the Side Squat Pose

Utthita Parshva Pada Upaveshasana

(UT-ti-tuh PAHRSH-vuh PUH-duh u-puh-vey-SHAHS-uh-nuh)
Modification: fingertips to the floor, toes of the straight leg flexed in
Pose Type: standing, forward bend

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Knee to Shoulder Extended Leg to the Side Squat Pose

Janu Bhuja Utthita Parshva Pada Upaveshasana

(JAH-nu BHU-juh UT-ti-tuh PAHRSH-vuh PUH-duh u-puh-vey-SHAHS-uh-nuh)

Modification: toes of the straight leg pointed
Pose Type: standing, forward bend, side bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Bound Extended Leg to the Side Squat Pose

Baddha Utthita Parshva Pada Upaveshasana

(BUH-duh UT-ti-tuh PAHRSH-vuh PUH-duh u-puh-vey-SHAHS-uh-nuh)

Modification: binding around the shin of the bent leg, toes of the straight leg flexed in
Pose Type: standing, side bend, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Revolved Half Bound Extended Leg to the Side Squat Pose

Parivritta Ardha Baddha Utthita Parshva Pada Upaveshasana

(puh-ri-VRIT-tuh UHR-duh BUH-duh UT-ti-tuh PAHRSH-vuh PUH-duh u-puh-vey-SHAHS-uh-nuh)

Modification: toes of the straight leg pointed
Pose Type: standing, side bend, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



SIDE LUNGE: SITTING BONE TO THE HEEL—ARMS HIGHER THAN HEAD LEVEL

Extended Leg to the Side Tip Toe Squat Pose

Utthita Parshva Pada Prapada Upaveshasana

(UT-ti-tuh PAHRSH-vuh PUH-duh PRUH-puh-duh u-puh-vey-SHAHS-uh-nuh)

Modification: toes of the straight leg to the floor
Pose Type: standing, forward bend
Drishti Point: Hastagrai or Hastagre (hands)



Extended Leg to the Side Tip Toe Squat Pose

Utthita Parshva Pada Prapada Upaveshasana

(UT-ti-tuh PAHRSH-vuh PUH-duh PRUH-puh-duh u-puh-vey-SHAHS-uh-nuh)

Modification: elbow to the knee of the bent leg, toes of the straight leg to the floor
Pose Type: standing, forward bend
Drishti Point: Hastagrai or Hastagre (hands)
ल व



Extended Leg to the Side Tip Toe Squat Pose

Utthita Parshva Pada Prapada Upaveshasana

(UT-ti-tuh PAHRSH-vuh PUH-duh PRUH-puh-duh u-puh-vey-SHAHS-uh-nuh)

Modification: side bend toward the straight leg, one arm parallel to the floor, other arm extended to the sky, toes of the straight leg pointed
Pose Type: standing, side bend
Drishti Point: Hastagrai or Hastagre (hands)
ल व य ह



Extended Leg to the Side Tip Toe Squat Pose

Utthita Parshva Pada Prapada Upaveshasana

(UT-ti-tuh PAHRSH-vuh PUH-duh PRUH-puh-duh u-puh-vey-SHAHS-uh-nuh)

Modification: side bend toward the straight leg, arms extended to the side and straight, toes of the straight leg to the floor
Pose Type: standing, side bend
Drishti Point: Hastagrai or Hastagre (hands), Padayoragrai or Padayoragre (toes/feet)



Both Arms Extended Leg to the Side Tip Toe Squat Pose

Dwi Hasta Utthita Parshva Pada Prapada Upaveshasana

(DWI-huh-stuh UT-ti-tuh PAHRSH-vuh PUH-duh PRUH-puh-duh u-puh-vey-SHAHS-uh-nuh)

Modification: side bend toward the bent leg, toes of the straight leg to the floor
Pose Type: standing, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)



SIDE LUNGE: SITTING BONE TO THE HEEL—HAND TO THE FLOOR

Extended Leg to the Side Tip Toe Squat Pose

Utthita Parshva Pada Prapada Upaveshasana

(UT-ti-tuh PAHRSH-vuh PUH-duh PRUH-puh-duh u-puh-vey-SHAHS-uh-nuh)

Modification: one hand on the knee, other hand to the floor, toes of the straight leg pointed
Pose Type: standing, forward bend
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Extended Leg to the Side Tip Toe Squat Pose

Utthita Parshva Pada Prapada Upaveshasana

(UT-ti-tuh PAHRSH-vuh PUH-duh PRUH-puh-duh u-puh-vey-SHAHS-uh-nuh)

Modification: one palm to the floor, other arm straight and parallel to the straight leg, toes of the straight leg to the floor
Pose Type: standing
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Hastagrai or Hastagre (hands)



SIDE LUNGE: SITTING BONE TO THE HEEL—1 ARM OVERHEAD, OTHER HAND TO THE FLOOR

Extended Leg to the Side Tip Toe Squat Pose

Utthita Parshva Pada Prapada Upaveshasana

(UT-ti-tuh PAHRSH-vuh PUH-duh PRUH-puh-duh u-puh-vey-SHAHS-uh-nuh)

Modification: side bending toward the bent knee, one hand to the floor, other arm extended up over the head, toes of the straight leg to the floor
Pose Type: standing, side bend
Drishti Point: Hastagrai or Hastagre (hands)
ल व य ह



Extended Leg to the Side Tip Toe Squat Pose

Utthita Parshva Pada Prapada Upaveshasana

(UT-ti-tuh PAHRSH-vuh PUH-duh PRUH-puh-duh u-puh-vey-SHAHS-uh-nuh)

Modification: side bending toward the straight leg, one hand to the floor, other arm extended up over the head, toes of the straight leg to the floor
Pose Type: standing, side bend
Drishti Point: Hastagrai or Hastagre (hands)



SIDE LUNGE: SITTING BONE TO THE HEEL—TWISTS & BINDING

Revolved Extended Leg to the Side Tip Toe Squat Pose with Hands in Prayer

Parivritta Utthita Parshva Pada Prapada Upaveshasana Namaskar

(puh-ri-VRIT-tuh UT-ti-tuh PAHRSH-vuh PUH-duh PRUH-puh-duh u-puh-vey-SHAHS-uh-nuh nuh-muhs-KAHR)

Modification: toes of the straight leg to the floor
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Revolved Bound Extended Leg to the Side Tip Toe Squat Pose

Parivritta Baddha Utthita Parshva Pada Prapada Upaveshasana

(puh-ri-VRIT-tuh BUH-duh UT-ti-tuh PAHRSH-vuh PUH-duh PRUH-puh-duh u-puh-vey-SHAHS-uh-nuh)

Modification: toes of the straight leg to the floor
1. knee on the floor

2. knee off the floor

Pose Type: standing, twist, binding

Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





CHAIR SQUAT: HIGH STANCE

Fierce Pose

Utkatasana

(OOT-kuh-TAHS-uh-nuh)

Also Known As: Chair Pose

Modification: palms pressed together, high squat

Pose Type: standing, mild backbend

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Fierce Pose

Utkatasana

(OOT-kuh-TAHS-uh-nuh)

Also Known As: Chair Pose
Modification: hands shoulder width apart, low squat
Pose Type: standing
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



CHAIR SQUAT: HIGH STANCE—HANDS TO THE FLOOR

Wagtail Bird Pose Prep.

Khanjanasana Prep.

(kuhn-juh-NAHS-uh-nuh)

Modification: hands to the floor, palms facing up, feet together
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye/Ajna Chakra (third eye, between the eyebrows)

लं हं ॐ



Intense Wrist Stretch Fierce Pose

Uttana Manibandha Utkatasana

(ut-TAH-nuh muh-ni-BUHN-duh OOT-kuh-TAHS-uh-nuh)

Also Known As: Intense Wrist Stretch Chair Pose
Modification: palms to the floor, fingertips facing the toes
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
लं हं



Wagtail Bird Pose

Khanjanasana

(kuhn-juh-NAHS-uh-nuh)

Also Known As: Shoulder Pressure Pose Prep. (Bhujapidasana Prep.)
Modification: shoulders to the back of the knees, fingertips to the heel
Pose Type: standing, forward bend
Drishti Point: Bhrumadhye/Ajna Chakra (third eye, between the eyebrows)
लं वं हं ॐ



Intense Wrist Stretch Half Bound

Fierce Pose

Uttana Manibandha Ardha Baddha Utkatasana

(ut-TAH-nuh muh-ni-BUHN-duh UHR-duh OOT-kuh-TAHS-uh-nuh)

Also Known As: Intense Wrist Stretch Half Bound Chair Pose

Pose Type: standing, forward bend, binding

Drishti Point: Hastagrai or Hastagrahe (hands)

How to Perform the Pose:

1. Begin by standing in Mountain Pose (*Tadasana*). Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale, bend your knees until your thighs are parallel to the floor, and drop both your hands to the floor. Rest your torso on top of your thighs.
3. Inhale as you externally rotate your right arm to point the fingertips of your right hand toward your feet.
4. On your next inhale, bring your left arm behind your back and your left hand to the inside of your right thigh. Try to seal the gap between your ribcage and your elbow.
5. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch.
6. Exhale as you release your left arm and bring your left hand to the floor. Repeat on the right side.

Modification: hand to the floor, fingertips pointing toward the toes

ut = intense

tan = to stretch, to extend

manibandha = wrist

ardha = half

baddha = bound

utkata = fierce

Elephant Old Form

Gaja Vadivu

(GUH-juh vah-dee-vuh)

Pose Type: standing, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Hand Position of the Pose Dedicated to Garuda in Half Intense Stretch Pose

Hasta Garudasana in Ardha Uttanasana

(HUH-stuh guh-ru-DAHS-uh-nuh in UHR-duh ut-tahn-AHS-uh-nuh)

Also Known As: Hand Position of the Pose Dedicated to Garuda in Half Forward Bend
Modification: knees bent, feet hip width apart
Pose Type: standing, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Hands Bound Ear Pressure Fierce Pose

Baddha Hasta Karnapida Utkatasana

(BUH-duh HUH-stuh kahr-nuh-PEE-duh ut-kuh-TAHS-uh-nuh)

Also Known As: Hands Bound Ear Pressure Chair Pose

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)



Hands Bound Revolved Fierce Pose

Baddha Hasta Parivritta Utkatasana

(Buh-duh HUH-stuh puh-ri-VRIT-tuh ut-kuh-TAHS-uh-nuh)

Also Known As: Hands Bound Revolved Chair Pose

Pose Type: standing, forward bend, twist

Drishti Point: Urdhva or Antara Drishti (up to the sky)



CHAIR SQUAT: HIGH STANCE—TWIST, ONE HAND TO THE FLOOR

Intense Wrist Stretch Revolved Half Bound Pose Dedicated to Yogi Shankara

Uttana Manibandha Parivritta Ardha Baddha Shankarasana

(ut-TAHN-uh muh-ni-BUHN-duh puh-ri-VRIT-tuh UHR-duh BUH-duh shuhng-kuhr-AHS-uh-nuh)

Pose Type: standing, forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Revolved Pose Dedicated to Yogi Shankara

Parivritta Sankarasana

(puh-ri-VRIT-tuh shuhng-kuhr-AHS-uh-nuh)

Pose Type: standing, forward bend, side bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



CHAIR SQUAT: HIGH STANCE—TWIST AND ELBOW OVER THE KNEE

Revolved Fierce Pose

Parivritta Utkatasana

(puh-ri-VRIT-tuh ut-kuh-TAHS-uh-nuh)

Also Known As: Revolved Chair Pose
Modification: feet wide apart, hands in Anjali Mudra (Hands in Prayer)
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
● ●



Revolved Fierce Pose

Parivritta Utkatasana

(puh-ri-VRIT-tuh ut-kuh-TAHS-uh-nuh)

Also Known As: Revolved Chair Pose
Modification: feet together, hands in Anjali Mudra (Hands in Prayer)
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
● ●



Revolved Fierce Pose

Parivritta Utkatasana

(puh-ri-VRIT-tuh ut-kuh-TAHS-uh-nuh)

Also Known As: Revolved Chair Pose
Modification: hands behind the head
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Revolved Fierce Pose

Parivritta Utkatasana

(puh-ri-VRIT-tuh ut-kuh-TAHS-uh-nuh)

Also Known As: Revolved Chair Pose
Modification: arm wrapped under the knee, hands in Anjali Mudra (Hands in Prayer)
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



One Hand Bound Revolved Fierce Pose

Eka Hasta Baddha Parivritta Utkatasana

(EY-kuh HUH-stuh BUH-duh puh-ri-VRIT-tuh ut-kuh-TAHS-uh-nuh)

Also Known As: One Hand Bound Revolved Chair Pose
Modification: 1. one hand to the heart
2. hand grabbing onto the biceps, other elbow over the opposite knee
Pose Type: standing, forward bend, twist, binding
Drishti Point: 1. Urdhva or Antara Drishti (up to the sky)
2. Padhayoragrai or Padayoragre (toes/feet)





Revolved One Leg Bound Fierce Pose

Parivritta Eka Pada Baddha Utkatasana

(puh-ri-VRIT-tuh EY-kuh PUH-duh BUH-duh ut-kuh-TAHS-uh-nuh)

Also Known As: Revolved One Leg Bound Chair Pose
Pose Type: standing, forward bend, twist, binding
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Revolved One Leg Bound Fierce Pose

Parivritta Eka Pada Baddha Utkatasana

(puh-ri-VRIT-tuh EY-kuh PUH-duh BUH-duh ut-kuh-TAHS-uh-nuh)

Also Known As: Revolved One Leg Bound Chair Pose
Modification: binding around one leg, hands bound overhead
Pose Type: standing, forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Revolved Both Legs Bound Fierce Pose

Parivritta Dwi Pada Baddha Utkatasana

(puh-ri-VRIT-tuh DWI-puh-duh BUH-duh ut-kuh-TAHS-uh-nuh)

Also Known As: Revolved Both Legs Bound Chair Pose
Pose Type: standing, forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



CHAIR SQUAT: HIGH STANCE HEELS UP—CHEST AWAY FROM QUADRICEPS

Tip Toe Fierce Pose 1

Prapada Utkatasana 1

(PRUH-puh-duh ut-kuh-TAHSuh-nuh)

Also Known As: Tip Toe Chair Pose 1
Modification: arms up over the head, fingers interlocked
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Tip Toe Fierce Pose 3

Prapada Utkatasana 3

(PRUH-puh-duh ut-kuh-TAHSuh-nuh)

Also Known As: Tip Toe Chair Pose 3
Modification: both elbows bent, one arm up in front, one arm down to the back
Pose Type: standing, forward bend
Drishti Point: Hastagrai or Hastagre (hands)

CHAIR SQUAT: HIGH STANCE HEELS UP—KNEES TO THE ARMPITS, VARIOUS HAND POSITIONS TO THE FLOOR

Crane Pose Prep.

Bakasana Prep.

(buhk-AHS-uh-nuh)

Modification: hands to the floor in front of the feet

1. fingertips to the floor
2. palms flat to the floor, arms shoulder width apart, fingertips pointing away from the head

Pose Type: standing, forward bend

Drishti Point: Hastagrai or Hastagre (hands), Nasagrai or Nasagre (nose)

● ●





Tip Toe Fierce Pose

Prapada Utkatasana

(PRUH-puh-duh ut-kuh-TAHS-uh-nuh)

Also Known As: Awkward Pose (Utkatasana)
Modification: arms out in front and parallel to the floor, sitting bones lifted off the heels
Pose Type: standing
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल



Tip Toe Fierce Pose 2

Prapada Utkatasana 2

(PRUH-puh-duh ut-kuh-TAHS-uh-nuh)

Also Known As: Tip Toe Chair Pose 2 and Tip Toe Diver’s Pose
Modification: arms extended to the back, chest to the quadriceps, palms facing down
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ



Head to Knees Tip Toe Fierce Pose 2

Janu Shirsha Prapada Utkatasana 2

(JAH-nu SHEER-shuh PRUH-puh-duh ut-kuh-TAHS-uh-nuh)

Also Known As: Head to Knees Tip Toe Chair Pose 2 and Head to Knees Tip Toe Diver's Pose

Modification: knees together, arms straight out to the sides, forehead to the knees

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)



CHAIR SQUAT: HIGH STANCE HEELS UP—BACK OF THE KNEE OVER THE SHOULDER

Unsupported Tip Toe Wagtail Pose 1

Niralamba Prapada Khanjanasana 1

(nir-ah-LUHM-buh PRUH-puh-duh kuhn-juh-NAHS-uh-nuh)

Modification: elbows bent, hands reaching to the front

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)



Unsupported Bound Tip Toe Wagtail Pose

Niralamba Baddha Prapada Khanjanasana

(nir-ah-LUHM-buh BUH-duh PRUH-puh-duh kuhn-juh-NAHS-uh-nuh)

Pose Type: standing, forward bend, binding

Drishti Point: Nasagrai or Nasagre (nose)



Supported Tip Toe Wagtail Pose

Salamba Prapada Khanjanasana

(sah-LUHM-buh PRUH-puh-duh kuhn-juh-NAHS-uh-nuh)

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Unsupported Tip Toe Wagtail Pose 2

Niralamba Prapada Khanjanasana 2

(nirsah-LUHM-buh PRUH-puh-duh kuhn-juh-NAHS-uh-nuh)

Modification: fingertips reaching away from the head, palms pressed together, high stance
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं वं हं ॐ



Intense Ankle Stretch Tip Toe Fierce Pose 3

Uttana Kulpa Prapada Utkatasana 3

(ut-TAH-nuh KUL-puh PRUH-puh-duh ut-kuh-TAHS-uh-nuh)

Also Known As: Intense Ankle Stretch Tip Toe Chair Pose 3

Modification: both elbows bent, one arm up in front, one arm down to the back

Pose Type: standing, balance

Drishti Point: Hastagrai or Hastagre (hands)



Revolved Intense Ankle Stretch Tip Toe Uneven Legs Half Intense Stretch Pose

Parivritta Uttana Kulpa Prapada Vishama Pada Ardha Uttanasana

(puh-ri-VRIT-tuh ut-TAH-nuh KUL-puh PRUH-puh-duh VISH-uh-muh PUH-duh UHR_duh ut-tahn-AHS-uh-nuh)

Also Known As: Revolved Intense Ankle Stretch Tip Toe Uneven Legs Half Forward Bend

Modification: fingertips off the floor

Pose Type: standing, balance, forward bend, twist

Drishti Point: Hastagrai or Hastagre (hands)



Intense Ankle Stretch Tip Toe Fierce Pose Prep.

Uttana Kulpa Prapada Utkatasana Prep.

(ut-TAH-nuh KUL-puh PRUH-puh-duh ut-kuh-TAHS-uh-nuh)

Also Known As: Intense Ankle Stretch Tip Toe Chair Pose Prep.
Modification: fingertips to the floor
Pose Type: standing, forward bend
Drishti Point: Hastagrai or Hastagre (hands)
ल र



Intense Ankle Stretch Tip Toe Fierce Pose 2

Uttana Kulpa Prapada Utkatasana 2

(ut-TAH-nuh KUL-puh PRUH-puh-duh ut-kuh-TAHS-uh-nuh)

Also Known As: Intense Ankle Stretch Tip Toe Chair Pose 2 and Intense Ankle Stretch Tip Toe Diver’s Pose
Modification: arms extended to the back, chest to the quadriceps
Pose Type: standing, balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल र य



CHAIR SQUAT: HIGH STANCE HEELS UP—ANKLES CROSSED, HANDS TO THE FLOOR

Revolved Tip Toe Pose

Parivritta Prapadasana

(puh-ri-VRIT-tuh pruh-puh-DAHS-uh-nuh)

Modification: ankles crossed, one arm to the back, other hand toward the floor in front of the feet
Pose Type: standing, forward bend, twist
Drishti Point: Hastagrai or Hastagre (hands)



Tip Toe Pose

Prapadasana

(pruh-puh-DAHS-uh-nuh)

Modification: ankles crossed, arms crossed, fingertips to the floor in front of the feet
Pose Type: standing, forward bend
Drishti Point: Hastagrai or Hastagre (hands)



Pendant Pose Prep.

Lolasana Prep.

(lo-LAHS-uh-nuh)

Modification: ankles crossed
Pose Type: standing, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs), Nasagrai or Nasagre (nose)



SQUAT: HEELS UP—LEGS CROSSED

Easy Leg Position of the Pose Dedicated to Garuda in Yoga Squat with Hands in Prayer

Sukha Pada Garudasana in Upaveshasana Namaskar

(SUK-kuh PUH-duh guh-ru-DAHS-uh-nuh in u-puh-veysh-AHS-uh-nuh nuh-muhs-KAHR)

Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Hastagrai or Hastagrahe (hands)



Easy Leg Position and Complete Arm Position of the Pose Dedicated to Garuda in Yoga Squat

Sukha Pada Paripurna Hasta Garudasana in Upaveshasana

(SUK-kuh PUH-duh puh-ri-POOR-nuh HUH-stuh guh-ru-DAHS-uh-nuh in u-puh-veysh-AHS-uh-nuh)

Pose Type: standing, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
लं वं



Revolved Easy Leg Position of the Pose Dedicated to Garuda in Yoga Squat

Parivritta Sukha Pada Garudasana in Upaveshasana

(puh-ri-VRIT-tuh SUK-kuh PUH-duh guh-ru-DAHS-uh-nuh in u-puh-veysh-AHS-uh-nuh)

Modification: both knees off the floor, arms open wide and straight
Pose Type: standing, forward bend, twist
Drishti Point: Hastagrai or Hastagrahe (hands)
लं वं यं



Revolved Easy Leg Position of the Pose Dedicated to Garuda in Yoga Squat

Parivritta Sukha Pada Garudasana in Upaveshasana

(puh-ri-VRIT-tuh SUK-kuh PUH-duh guh-ru-DAHS-uh-nuh in u-puh-veysh-AHS-uh-nuh)

Modification: bottom knee on the floor, arms open wide and straight
Pose Type: standing, forward bend, twist
Drishti Point: Hastagrai or Hastagrahe (hands)
ल व य



Revolved Easy Leg Position of the Pose Dedicated to Garuda in Yoga Squat

Parivritta Sukha Pada Garudasana in Upaveshasana

(puh-ri-VRIT-tuh SUK-kuh PUH-duh guh-ru-DAHS-uh-nuh in u-puh-veysh-AHS-uh-nuh)

Modification: elbow over the opposite knee, other arm straight out to the side
Pose Type: standing, forward bend, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
ल व र



SQUAT: HEELS UP—KNEES APART

Hand Position of the Pose Dedicated to Garuda in Half Tip Toe Hero Pose

Hasta Garudasana in Ardha Prapada Virasana

(HUH-stuh guh-ru-DAHS-uh-nuh in UHR-duh PRUH-puh-duh veer-AHS-uh-nuh)

Modification: one knee on the floor, one foot to the floor on the inside of the knee
Pose Type: standing, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Half Bound Hand to Foot Uneven Tip Toe Pose

Ardha Baddha Hasta Pada Vishama Prapadasana

(UHR-duh BUH-duh HUH-stuh PUH-duh VISH-uh-muh pruh-puh-DAHS-uh-nuh)

Modification: one hand crossed in front, grabbing onto the heel; other hand to the inner thigh on the opposite side
Pose Type: standing, forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)

Hand Position of the Pose Dedicated to Garuda in Half Lotus Tip Toe Pose

Hasta Garudasana in Ardha Padma Prapadasana

(HUH-stuh guh-ru-DAHS-uh-nuh in UHR-duh PUHD-muh pruh-puh-DAHS-uh-nuh)

Modification: 1. Both knees on the floor
2. One knee on the floor
Pose Type: standing
Drishti Point: 1. Angusthamadhye or Angustha Ma Dyai (thumbs)
2. Nasagrai or Nasagre (nose)





Tip Toe Pose

Prapadasana

(pruh-puh-DAHS-uh-nuh)

Also Known As: Noose Pose Prep. (Pasasana Prep.)
Modification: 1. fingertips to the floor on the outside of the knees
2. one hand to the heart, other hand to the floor
3. hands on the hips
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)







Hands Bound Tip Toe Pose

Baddha Hasta Prapadasana

(BUH-duh HUH-stuh pruh-puh-DAHS-uh-nuh)

Modification: arms straight out in front, palms facing out, chest to the quadriceps

Pose Type: standing, forward bend

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)

🔴 🟡



Tip Toe Pose with Hands in Prayer

Prapadasana Namaskar

(pruh-puh-DAHS-uh-nuh nuh-muhs-KAHR)

Modification: knees together, chest to the quadriceps

Pose Type: standing, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

🔴 🟡 🟢 🔵



SQUAT: HEELS UP—KNEES TOGETHER—ARMS HEAD LEVEL OR ABOVE HEAD

Tip Toe Pose

Prapadasana

(pruh-puh-DAHS-uh-nuh)

Also Known As: Garland Pose Prep. (Malasana Prep.), Full Squat Pose (Purna Utkatasana)
Modification: 1. arms straight out in front and parallel to the floor
2. arms up over the head, palms pressed together, elbows bent
Pose Type: standing
Drishti Point: Hastagrai or Hastagre (hands)
Drishti Point: 1. Hastagrai or Hastagrahe (hands)
2. Nasagrai or Nasagre (nose)





Half Bound Tip Toe Pose

Ardha Baddha Prapadasana

(UHR-duh BUH-duh pruh-puh-DAHS-uh-nuh)

Modification: one hand binding to the opposite hip behind the back, other arm straight and extended out to the side
Pose Type: standing, binding
Drishti Point: Nasagrai or Nasagre (nose)



SQUAT: HEELS UP—KNEES TOGETHER—KNEES SHOULDER LEVEL

Seated Tip Toe Pose

Upavishta Prapadasana

(u-puh-VISH-tuh pruh-puh-DAHS-uh-nuh)

Also Known As: Crouching Tip Toe Pose; Upavistha Prapadasana
Modification: elbows resting on the knees, fingers interlocked in front of the face
Pose Type: standing, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Hands Bound Seated Tip Toe Pose

Baddha Hasta Upavishta Prapadasana

(BUH-duh HUH-stuh u-puh-VISH-tuh pruh-puh-DAHS-uh-nuh)

Also Known As: Hands Bound Crouching Tip Toe Pose; Baddha Hasta Upavistha Prapadasana
Modification: arms away from the body
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Knees to the Shoulders Seated Tip Toe Pose

Janu Bhuja Upavishta Prapadasana

(JAH-nu BHU-juh u-puh-VISH-tuh pruh-puh-DAHS-uh-nuh)

Also Known As: Knees to the Shoulders Crouching Tip Toe Pose; Janu Bhuja Upavistha Prapadasana
Modification: 1. palms together to the floor
2. palms apart and to the floor, elbows bent
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)


1.


2.

Supported Seated Tip Toe Pose

Salamba Upavishta Prapadasana

(sah-LUHM-buh u-puh-VISH-tuh pruh-puh-DAHS-uh-nuh)

Also Known As: Supported Crouching Tip Toe Pose; Salamba Upavistha Prapadasana
Modification: fingertips to the floor in front of the feet
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल र य ह



Supported/Unsupported Intense Ankle Stretch Seated Tip Toe Pose

Salamba/Niralamba Uttana Kulpa Upavishta Prapadasana

(sah-LUHM-buh-/nir-ah-LUHM-buh ut-TAHN-uh KUL-puh u-puh-VISH-tuh pruh-puh-DAHS-uh-nuh)

Also Known As: Supported/Unsupported Intense Ankle Stretch Crouching Tip Toe Pose; Salamba/Niralamba Uttana Kulpa Upavistha Prapadasana
Modification: 1. hands to the floor by the hips
2. arms wrapped around the shins, grabbing onto the triceps
Pose Type: 1. standing, forward bend
2. standing, balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल र य ह ॐ




2.

SQUAT: HEELS UP—TWISTS

Tip Toe Easy Noose Pose Prep.

Prapada Sukha Pashasana Prep.

(PRUH-puh-duh SUK-kuh puh-SHAHS-uh-nuh)

Modification: elbow on the inside of the thigh, arms open wide
Pose Type: standing, twist
Drishti Point: Hastagrai or Hastagre (hands)
● ●



Uneven Legs One Hand to Foot Noose Pose

Vishama Pada Eka Hasta Pada Pashasana

(VISH-uh-muh PUH-duh EY-kuh HUH-stuh PUH-duh puh-SHAS-uh-nuh)

Modification: one heel up, one heel down
Pose Type: standing, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
●



Extended Side Tip Toe Noose Pose

Utthita Parshva Prapada Pashasana

(UT-ti-tuh PAHRSH-vuh PRUH-puh-duh puh-SHAHS-uh-nuh)

Modification: one hand to the floor, other arm extended up over the head
Pose Type: standing, forward bend, twist
Drishti Point: Hastagrai or Hastagre (hands)



Tip Toe Noose Pose with Hands in Prayer

Prapada Pashasana Namaskar

(PRUH-puh-duh puh-SHAHS-uh-nuh nuh-muhs-KAHR)

Pose Type: standing, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)

One Hand to the Foot Tip Toe Noose Pose

Eka Hasta Pada Prapada Pashasana

(EY-kuh HUH-stuh PUH-duh PRUH-puh-duh puh-SHAHS-uh-nuh)

Modification: one hand to the opposite heel, other hand binding to the opposite hip behind the back
1. right side view
2. left side view

Pose Type: standing, twist, binding

Drishti Point: Urdhva or Antara Drishti (up to the sky)


1.


2.

Tip Toe Noose Pose Prep.

Prapada Pashasana Prep.

(PRUH-puh-duh puh-SHAHS-uh-nuh)

Modification: 1. binding around one leg with a strap
2. binding around one leg without a strap

Pose Type: standing, twist, binding

Drishti Point: Urdhva or Antara Drishti (up to the sky)





Tip Toe Noose Pose

Prapada Pashasana

(PRUH-puh-duh puh-SHAHS-uh-nuh)

Modification: binding around both legs

Pose Type: standing, forward bend, twist, binding

Drishti Point: Nasagrai or Nasagre (nose)



SQUAT: HEELS DOWN—ARMS BELOW HEAD

Intense Wrist Stretch Garland Pose Prep.

Uttana Manibandha Malasana Prep.

(ut-TAH-nuh muh-ni-BUHN-duh mah-LAHS-uh-nuh)

Modification: heels down, knees together, palms to the floor, fingers facing the toes, chest to the quadriceps
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल र य



Garland Pose with Hands in Prayer Prep.

Malasana Namaskar Prep.

(mah-LAHS-uh-nuh nuh-muhs-KAHR)

Modification: heels down
Pose Type: standing, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)

Garland Pose Prep.

Malasana Prep.

(mah-LAHS-uh-nuh)

Also Known As: Full Squat Pose (Purna Utkatasana)
Modification: knees together, heels down; arms straight out to the front, palms down
Pose Type: standing, forward bend
Drishti Point: Hastagrai or Hastagre (hands)



Arms Spread Out Garland Pose Prep.

Prasarita Hasta Malasana Prep.

(pruh-SAH-ri-tuh HUH-stuh mah-LAHS-uh-nuh)

Also Known As: Full Squat Pose (Purna Utkatasana), Flying Bird Pose (Khagasana)
Modification: knees together, heels down, arms straight out to the side
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



SQUAT: HEELS DOWN—ARMS ABOVE HEAD

Upward Hands Garland Pose Prep.

Urdhva Hasta Malasana Prep.

(OORD-vuh HUH-stuh mah-LAHS-uh-nuh)

Also Known As: Full Squat Pose (Purna Utkatasana)
Modification: knees together, hands to the sky
Pose Type: standing, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Easy Noose Pose

Sukha Pashasana

(SUK-kuh puh-SHAHS-uh-nuh)

Also Known As: Revolved Yoga Squat (Parivritta Upaveshasana)
Modification: heels down, shoulder between the knees, one palm flat on the floor, other arm straight out to the back
Pose Type: standing, forward bend, twist
Drishti Point: Hastagrai or Hastagre (hands)



Extended Side Noose Pose

Utthita Parshva Pashasana

(UT-ti-tuh PAHRSH-vuh puh-SHAHS-uh-nuh)

Modification: heels down, one hand to the floor, other arm extended up over the head
Pose Type: standing, forward bend, twist
Drishti Point: Hastagrai or Hastagre (hands)



SQUAT: HEELS DOWN—TWISTS

Noose Pose with Hands in Prayer

Pashasana Namaskar

(puh-SHAHS-uh-nuh nuh-muhs-KAHR)

Modification: heels down
Pose Type: standing, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Half Bound Noose Pose

Ardha Baddha Pashasana

(UHR-duh BUH-duh puh-SHAHS-uh-nuh)

Modification: heels down
Pose Type: standing, forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Noose Pose

Pashasana

(puh-SHAHS-uh-nuh)

Modification: heels down, binding with a strap
1. binding around one leg
2. binding around both legs
Pose Type: standing, forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)





Noose Pose

Pashasana

(puh-SHAHS-uh-nuh)

Modification: heels down, binding around both legs
1. side view
2. front view
Pose Type: standing, forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)





ONE-LEGGED SQUAT: FOOT TO KNEE

One-Legged Tip Toe Pose

Eka Pada Prapadasana

(EY-kuh PUH-duh pruh-puh-DAHS-uh-nuh)

Also Known As: Half Bound Lotus Tip Toe Pose Prep. (Ardha Baddha Padma Padangushtasana Prep.)
Modification: 1. both hands to the floor on the sides
2. hands in Anjali Mudra (Hands in Prayer)
Pose Type: standing one-legged balance
Drishti Point: Nasagrai or Nasagre (nose)
ल व





One-Legged Tip Toe Pose

Eka Pada Prapadasana

(EY-kuh PUH-duh pruh-puh-DAHS-uh-nuh)

Also Known As: Half Bound Lotus Tip Toe Pose Prep. (Ardha Baddha Padma Padangushtasana Prep.)

Modification: 1. one hand on the hip, other hand to the floor
2. one hand on the hip, one arm up over the head

Pose Type: standing one-legged balance

Drishti Point: Nasagrai or Nasagre (nose)

ल व





Baby Cradle Pose with Hands in Prayer in One-Legged Garland Pose

Hindolasana Namaskar in Eka Pada Malasana

(hin-do-LAHS-uh-nuh EY-kuh PUH-duh mah-LAHS-uh-nuh)

Also Known As: Baby Cradle Pose with Hands in Prayer in One-Legged Yoga Squat (Hindolasana Namaskar in Eka Pada Upavesashana)

Pose Type: standing one-legged balance, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

ल व र य



Baby Cradle Pose in One-Legged Tip Toe Pose 1

Hindolasana in Eka Pada Prapadasana 1

(hin-do-LAHS-uh-nuh in EY-kuh PUH-duh pruh-puh-DAHS-uh-nuh)

Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Half Yogic Staff Pose Prep. in One-Legged Tip Toe Pose

Ardha Yogadandasana Prep. in Eka Pada Prapadasana

(UHR-duh yo-guh-duhn-DAHS-uh-nuh in EY-kuh PUH-duh pruh-puh-DAHS-uh-nuh)

Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



ONE-LEGGED SQUAT: FOOT UNDER THE KNEE

Baby Cradle Pose in One-Legged Tip Toe Pose 2

Hindolasana in Eka Pada Prapadasana 2

(hin-do-LAHS-uh-nuh in EY-kuh PUH-duh pruh-puh-DAHS-uh-nuh)

Pose Type: standing one-legged balance, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

ल व र य



Supported Revolved One-Legged Tip Toe Pose

Salamba Parivritta Eka Pada Prapadasana

(sah-LUHM-buh puh-ri-VRIT-tuh EY-kuh PUH-duh pruh-puh-DAHS-uh-nuh)

Modification: foot under the knee

Pose Type: standing one-legged balance, forward bend, twist

Drishti Point: Padayoragrai or Padayoragre (toes/feet)

ल व



ONE-LEGGED SQUAT: FOOT TO KNEE & ONE KNEE OVER THE SHOULDER

Tip Toe Lord of the Fishes Pose

Prapada Matsyendrasana

(PRUH-puh-duh muhts-y-eyn-DRAHS-uh-nuh)

Pose Type: standing one-legged balance, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
लं रं



Supported One-Legged Tip Toe Pose

Salamba Eka Pada Prapadasana

(sah-LUHM-buh EY-kuh PUH-duh pruh-puh-DAHS-uh-nuh)

Modification: leg wrapped around the tricep, fingertips to the floor
Pose Type: standing one-legged balance
Drishti Point: Nasagrai or Nasagre (nose)
लं वं



Supported One-Legged Tip Toe Pose

Salamba Eka Pada Prapadasana

(sah-LUHM-buh EY-kuh PUH-duh pruh-puh-DAHS-uh-nuh)

Modification: hands to the floor, shoulder to the back of the knee, other foot wrapped around the forearm
Pose Type: standing one-legged balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व ह



ONE-LEGGED SQUAT: HALF LOTUS

Half Bound Lotus Tip Toe Pose

Ardha Baddha Padma Prapadasana

(UHR-duh BUH-duh PUHD-muh pruh-puh-DAHS-uh-nuh)

Also Known As: Half Bound Lotus Tip Toe Pose (Ardha Baddha Padma Padangushtasana)
Modification: 1. fingertips to the floor, other hand to the heart
2. binding, other hand to the heart
3. binding, other arm out to the side, parallel to the floor
Pose Type: 1. standing one-legged balance

2 & 3. standing one-legged balance, binding

Drishti Point: Nasagrai or Nasagre (nose)

1.



2.



3.



Hand Position of the Pose Dedicated to Garuda in Half Lotus Tip Toe Pose

Hasta Garudasana in Ardha Padma Prapadasana

(HUH-stuh guh-ru-DAHS-uh-nuh in UHR-duh-PUHD-muh pruh-puh-DAHS-uh-nuh)

Modification: knee on the floor, forward bend

Pose Type: standing one-legged balance, forward bend

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



ONE-LEGGED SQUAT: HALF LOTUS—HEEL DOWN

Half Lotus One-Legged Garland Pose

Ardha Padma Eka Pada Malasana

(UHR-duh PUHD-muh EY-kuh PUH-duh mah-LAHS-uh-nuh)

Also Known As: Half Lotus One-Legged Yoga Squat (Ardha Padma Eka Pada Upaveshasana)
Modification: arms parallel to the floor
Pose Type: standing one-legged balance
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Half Lotus Bound One-Legged Garland Pose

Ardha Padma Baddha Eka Pada Malasana

(UHR-duh PUHD-muh BUH-duh EY-kuh PUH-duh mah-LAHS-uh-nuh)

Also Known As: Half Lotus Bound One-Legged Yoga Squat (Ardha Padma Baddha Eka Pada Upavesasana)
Pose Type: standing one-legged balance, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)



ONE-LEGGED SQUAT: ONE LEG STRAIGHT—HEEL UP & DOWN

Hand to Foot Pose Squatting Prep.

Hasta Padasana Prep.

(HUH-stuh puh-DAHS-uh-nuh)

Modification: leg straight and lifted off the floor, arms parallel to the floor
Pose Type: standing one-legged balance
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Hands to Foot Squatting Pose 1

Hasta Padasana 1

(HUH-stuh puh-DAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi Modification (Marichyasana Modification)
Modification: both hands to the foot, heel down
Pose Type: standing one-legged balance
Drishti Point: Padayoragrai or Padayoragre (toes/feet)

Drishti Point: Nasagrai or Nasagre (nose) or Padhayoragrai or Padayoragre (toes/feet)



Revolved Supported Hand to Foot Pose Squatting

Parivritta Salamba Hasta Padasana

(puh-ri-VRIT-tuh SAH-luhm-buh HUH-stuh puh-DAHS-uh-nuh)

Modification: one hand to the floor
Pose Type: standing one-legged balance, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Hand to Foot to the Side Tip Toe Pose

Hasta Pada Parshva Prapadasana

(HUH-stuh PUH-duh PAHRSH-vuh pruh-puh-DAHS-uh-nuh)

Pose Type: standing one-legged balance
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Sundial Pose in One-Legged Garland Pose

Surya Yantrasana in Eka Pada Malasana

(SOOR-yuh yuhn-TRAHS-uh-nuh in EY-kuh PUH-duh mah-LAHS-uh-nuh)

Also Known As: Sundial Pose in One-Legged Yoga Squat (Surya Yantrasana in Eka Pada Upavesasana)
Pose Type: standing one-legged balance, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Extended Hand to Big Toe Pose in Half Tip Toe Hero Pose

Utthita Hasta Padangushtasana in Ardha Prapada Virasana

(UT-ti-tuh HUH-stuh puhd-ahng-goosh-TAHS-uh-nuh in UHR-duh PRUH-puh-duh veer-AHS-uh-nuh)

Pose Type: standing one-legged balance, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



ONE-LEGGED SQUAT: ONE LEG STRAIGHT—HEEL DOWN

Baby Grasshopper Pose

Bala Shalabhasana

(BUH-luh shuh-luh-BAHS-uh-nuh)

Also Known As: Baby Locust Pose
Modification: chest facing the floor, forearm on the floor
Pose Type: standing one-legged balance, forward bend, twist
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Hand to Foot Pose 2

Hasta Padasana 2

(HUH-stuh puh-DAHS-uh-nuh)

Modification: leg crossed over, one hand to the foot, other hand to the heart
Pose Type: standing one-legged balance, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Angushtamadhye or Angushta Ma Dyai (thumbs)



ONE-LEGGED SQUAT: LEG BEHIND THE HEAD

Supported One Foot Behind the Head Tip Toe Pose Prep. 1

Salamba Eka Pada Shirsha Prapadasana Prep. 1

(SAH-luhm-buh EY-kuh PUH-duh SHEER-shuh pruh-puh-DAHS-uh-nuh)

Modification: heel up, sitting bones lifted
Pose Type: standing one-legged balance, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Supported One Foot Behind the Head Tip Toe Pose Prep. 2

Salamba Eka Pada Shirsha Prapadasana Prep. 2

(SAH-luhm-buh EY-kuh PUH-duh SHEER-shuh pruh-puh-DAHS-uh-nuh)

Modification: hands to the floor
Pose Type: standing one-legged balance
Drishti Point: Nasagrai or Nasagre (nose)



One Foot Behind the Head Tip Toe Pose

Eka Pada Shirsha Prapadasana

(EY-kuh PUH-duh SHEER-shuh pruh-puh-DAHS-uh-nuh)

Also Known As: Tip Toe Balance Foot Behind The Head Pose (Padangushta Eka Pada Shirshasana), One Foot Behind the Head Tip Toe Pose (Eka Pada Shirsha Padangushtasana)
Pose Type: standing one-legged balance
Drishti Point: Nasagrai or Nasagre (nose)



SQUAT: HEELS DOWN—KNEES WIDE

Hand Position of the Pose Dedicated to Garuda in Garland Pose

Hasta Garudasana in Malasana

(HUH-stuh guh-ru-DAHS-uh-nuh in mah-LAHS-uh-nuh)

Also Known As: Hand Position of the Pose Dedicated to Garuda in Yoga Squat (Hasta Garudasana in Upaveshasana)
Pose Type: standing, forward bend

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Lion Pose Dedicated to an Avatar of Lord Vishnu in Garland Pose

Narasimhasana in Malasana

(nuh-ruh-sim-HAHS-uh-nuh in mah-LAHS-uh-nuh)

Also Known As: Lion Pose in Yoga Squat (Simhasana in Upaveshasana)
Modification: heels down
Pose Type: standing, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Bound Revolved Garland Pose

Ardha Baddha Parivritta Malasana

(UHR-duh BUH-duh puh-ri-VRIT-tuh mah-LAHS-uh-nuh)

Also Known As: Half Bound Revolved Yoga Squat (Ardha Baddha Parivritta Upaveshasana)
Modification: forearm on the knee
Pose Type: standing, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Bound Garland Pose

Baddha Malasana

(BUH-duh mah-LAHS-uh-nuh)

Also Known As: Bound Yoga Squat (Baddha Upaveshasana)
Pose Type: standing, binding
Drishti Point: Nasagrai or Nasagre (nose)



One Leg Bound Garland Pose

Eka Pada Baddha Malasana

(EY-kuh PUH-duh BUH-duh mah-LAHS-uh-nuh)

Also Known As: One Leg Bound Yoga Squat (Eka Pada Baddha Upaveshasana)
Modification: heels down, binding around one of the legs, knees open wide
Pose Type: standing, binding, forward bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)



SQUAT: ONE HEEL UP, ONE HEEL DOWN—KNEES WIDE

Uneven Legs Garland Pose

Vishama Pada Malasana

(VISH-uh-muh PUH-duh mah-LAHS-uh-nuh)

Also Known As: Uneven Legs Yoga Squat (Vishama Pada Upaveshasana)
Modification: one knee higher than the other; fingertips of one hand to the floor, other elbow on the knee
Pose Type: standing, forward bend
Drishti Point: Hastagrai or Hastagre (hands)



Sideways Uneven Legs Garland Pose

Parshva Vishama Pada Malasana

(PAHRSH-vuh VISH-uh-muh PUH-duh mah-LAHS-uh-nuh)

Also Known As: Sideways Uneven Legs Yoga Squat (Parshva Vishama Pada Upaveshasana)
Modification: one heel up, one heel down, one arm up over the head into a side bend, back of the other hand on the floor
Pose Type: standing, forward bend, side bend

Drishti Point: Hastagrai or Hastagre (hands)

ल व



SQUAT: HEELS DOWN—KNEES WIDE, FORWARD BENDS

Garland Pose

Malasana

(mah-LAHS-uh-nuh)

Also Known As: Yoga Squat (Upaveshasana)
Modification: 1. hands in Anjali Mudra (Hands in Prayer)
2. arms straight out in front; palms down, head up
3. arms straight out in front; palms down, head down
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)

ल व





2.



3.

Hands Bound Garland Pose

Baddha Hasta Malasana

(BUH-duh HUH-stuh mah-LAHS-uh-nuh)

Also Known As: Hands Bound Yoga Squat (Baddha Hasta Upaveshasana)
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



SQUAT: HEELS DOWN—KNEES WIDE, FORWARD BENDS—BINDING

Garland Pose

Malasana

(mah-LAHS-uh-nuh)

Also Known As: Tortoise Pose Squat (Kurmasana Modification)
Modification: grabbing onto heels
1. head off the floor
2. forehead to the floor
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)





Garland Pose

Malasana

(mah-LAHS-uh-nuh)

Also Known As: Golden Belt Pose (Kanchyasana)
Modification: hands bound, heels down
Pose Type: standing, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)



SQUAT: HEELS UP—KNEES WIDE, FORWARD BENDS—BINDING

Garland Pose

Malasana

(mah-LAHS-uh-nuh)

Modification: heels up, arms stretched out to the back, palms facing up, forehead to the floor
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Garland Pose

Malasana

(mah-LAHS-uh-nuh)

Also Known As: Golden Belt Pose (Kanchyasana)
Modification: heels up, hands bound
1. front view
2. side view
Pose Type: standing, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)


1.


2.

Garland Pose

Malasana

(mah-LAHS-uh-nuh)

Modification: heels up, arms binding around the shins, hands between thighs and rib cage
Pose Type: standing, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)



SQUAT: HEELS UP—KNEES WIDE, FORWARD BENDS—FOREARMS & ELBOWS ON THE FLOOR

Garland Pose

Malasana

(mah-LAHS-uh-nuh)

Modification: forehead to the floor, thumbs to the upper back
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Garland Pose

Malasana

(mah-LAHS-uh-nuh)

Modification: forearms to the floor
1. grabbing onto the triceps
2. forearms on the floor, palms pressed together
Pose Type: standing, forward bend
Drishti Point: 1. Nasagrai or Nasagre (nose)
2. Angusthamadhye or Angustha Ma Dyai (thumbs)



2.



Garland Pose

Malasana

(mah-LAHS-uh-nuh)

Pose Type: standing, forward bend

Drishti Point: 1 & 2. Angusthamadhye or Angustha Ma Dyai (thumbs) 3 & 4. Nasagrai or Nasagre (nose)

How to Perform the Pose:

1. Begin by standing in Mountain Pose (*Tadasana*). Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale as you bend your knees, lift your heels, and drop your sitting bones to your heels.
3. Inhale as you open your knees out to the sides. Exhale as you drop your chest between your knees and lower your forearms to the floor. Your knees should end up on the outsides of your shoulders.
4. You can experiment with various arm positions. Start with your palms flat on the floor (Pose #1), then bring either one hand to your face (Pose #2) or both hands to your face (Pose #3) and then spread your fingers out (Pose #4).
5. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch.
6. To come out of the pose, inhale as you lift your chest and bring your knees together. Exhale as you press into your feet, straighten your legs, and come back to Mountain Pose (*Tadasana*).

Modification:

1. forearms and palms to the floor
2. one forearm and palm to the floor, other elbow to the floor hand to the face
3. both hands to the face, elbows on the floor
4. both hands to the face, fingers spread open in a Padma Mudra - Lotus Hand Seal elbows, on the floor


1.

2.



3.



4.



Garland Pose

Malasana

(mah-LAHS-uh-nuh)

Also Known As: Full Squat Pose (Kunthasana)
Modification: hands wide, knees on top of the triceps
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)

लं वं यं हं



Garland Pose

Malasana

(mah-LAHS-uh-nuh)

Modification: heels up

1. knees to the armpits; hands out to the sides, fingertips to the floor
2. forehead to the floor; elbows bent at 90 degrees, fingertips to the floor
3. forehead to the floor; hands off the floor, arms out to the sides

Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)

लं वं यं हं ॐ







SQUAT: HEELS UP—KNEES WIDE, ARMS TO THE FLOOR & BALLET TOES

Supported Tip Toe Pose

Salamba Prapadasana

(SAH-luhm-buh pruh-puh-DAHS-uh-nuh)

Modification: knees open, elbows and wrists together, fingertips touching the floor in front of the feet
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य



Intense Wrist Stretch Supported Tip Toe Pose

Uttana Manibandha Salamba Prapadasana

(ut-TAH-nuh muh-ni-BUHN-duh SAH-luhm-buh pruh-puh-DAHS-uh-nuh)

Modification: knees open wide; palms on the floor, fingertips toward the feet
Pose Type: standing, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Lion Pose Dedicated to an Avatar of Lord Vishnu in Tip Toe Pose

Narasimhasana in Prapadasana

(nuh-ruh-sim-HAHS-uh-nuh in pruh-puh-DAHS-uh-nuh)

Also Known As: Lion Pose in Tip Toe Pose (Simhasana in Prapadasana)
Modification: feet wide apart
Pose Type: standing, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Unsupported Intense Ankle Stretch Tip Toe Pose

Niralamba Uttana Kulpa Prapadasana

(nir-AH-luhm-buh ut-TAH-nuh KUL-puh pruh-puh-DAHS-uh-nuh)

Modification: hands on the knees
Pose Type: standing, balance
Drishti Point: Nasagrai or Nasagre (nose)
● ●



Supported Intense Ankle Stretch Tip Toe Pose

Salamba Uttana Kulpa Prapadasana

(SAH-luhm-buh ut-TAH-nuh KUL-puh pruh-puh-DAHS-uh-nuh)

Modification: fingertips to the floor
Pose Type: standing, balance
Drishti Point: Nasagrai or Nasagre (nose)
● ● ●



SQUAT: HEELS UP—KNEES WIDE, ARM MODIFICATIONS

Tip Toe Pose

Prapadasana

(pruh-puh-DAHS-uh-nuh)

Modification: knees open wide; palms together, elbows together
Pose Type: standing
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व



Tip Toe Pose

Prapadasana

(pruh-puh-DAHS-uh-nuh)

Modification: knees open wide, hands in Anjali Mudra (Hands in Prayer)
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)
ल व



One Hand in Reverse Prayer Tip Toe Pose

Eka Hasta Viparita Namaskar Prapadasana

(EY-kuh HUH-stuh vi-puh-REE-tuh nuh-muhs-KAHR pruh-puh-DAHS-uh-nuh)

Modification: knees open wide; one hand to the knee
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)



Upward Hands Tip Toe Pose

Urdhva Hasta Prapadasana

(OORD-vuh HUH-stuh pruh-puh-DAHS-uh-nuh)

Modification: knees open wide; arms extended up to the sky, head rolling back
Pose Type: standing, mild backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



SQUAT: HEELS UP—KNEES WIDE, KNEES ON THE FLOOR—ARM MODIFICATIONS

Reverse Prayer Root Lock Pose Prep.

Viparita Namaskar Mulabhandasana Prep.

(vi-puh-REE-tuh nuh-muhs-KAHR moo-luh-buhn-DAHS-uh-nuh)

Also Known As: Back of the Body Prayer Tip Toe Pose (Paschima Namaskara Prapadasana)
Modification: knees open wide; knees to the floor
Pose Type: standing
Drishti Point: Nasagrai or Nasagre (nose)



Root Lock Pose Prep.

Mulabhandasana Prep.

(moo-luh-buhn-DAHS-uh-nuh)

Also Known As: Tip Toe Pose Modification (Prapadasana Modification)
Modification: knees open wide; palms and elbows together; knees to the floor
Pose Type: standing
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Root Lock Pose Prep.

Mulabhandasana Prep.

(moo-luh-buhn-DAHS-uh-nuh)

Also Known As: Tip Toe Pose Modification (Prapadasana Modification)
Modification: knees open wide; elbows and ankles crossed; knees to the floor, fingertips to the floor
Pose Type: standing, forward bend
Drishti Point: Hastagrai or Hastagre (hands)



ROOT LOCK POSE

Root Lock Pose Prep.

Mulabhandasana Prep.

(moo-luh-buhn-DAHS-uh-nuh)

Also Known As: Twisted Feet Bound Angle Pose (Parivritta Pada Baddha Konasana)
Modification: fingertips to the floor behind the hips, sitting bones off the floor
Pose Type: standing, mild backbend

Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व ह



Womb Staff Pose

Yoni Dandasana

(YO-ni duhn-DAHS-uh-nuh)
Also Known As: Root Lock Pose Modification (Mulabandhasana Modification)
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose)
ल व



Root Lock Pose

Mulabhandasana

(moo-luh-buhn-DAHS-uh-nuh)
Also Known As: Perineal Contraction Pose (Mula Bandhasana)
Modification: palms up on the knees, head rolled back
Pose Type: seated, mild backbend
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व ह

Pose Dedicated to Sage Vamadeva 1

Vamadevasana 1

(vah-muh-dey-VAHS-uh-nuh)

Modification: both hands binding to the top foot
Pose Type: seated, twist, binding
Drishti Point: Parsva Drishti (to the right), Parsva Drishti (to the left)



Seated Poses

EASY POSE

ACCOMPLISHED ONE POSE

FIRE LOG POSE

HALF LOTUS AND LOTUS POSE

BOTH KNEES BENT

BOUND ANGLE POSE

STAR POSE

LEGS IN FRONT

HORIZONTAL SPLITS

LEGS STRAIGHT IN FRONT

GARUDA LEGS

LEG CRADLE

HEAD TO KNEE

HERO POSE

THUNDERBOLT POSE

ONE KNEE BENT (VARIATIONS)

COW FACE POSE

SAGE VAMADEVA’S POSE

ONE-LEGGED KING PIGEON POSE

VERTICAL SPLITS

Easy Pose

Sukhasana

(suk-AHS-uh-nuh)

Pose Type: seated, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

How to Perform the Pose:

1. Begin by sitting on the floor with both your legs straight out in front of you. Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale as you bring your feet toward you and cross them at the ankles. Keep the soles of your feet flat on the floor and your knees in line with your shoulders.
3. Inhale, stretch your arms up to the sky to lengthen your spine, and exhale as you bring your elbows together on the inside of your knees.
4. Inhale as you open your palms up to sky with your fingertips pointing to the outsides. Exhale as you bring you thumbs and pointer fingers together.
5. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch.
6. Exhale as you release the pose, coming back to starting position with both your legs straight out.

Modification: knees in line with the shoulders, elbows to the inside of the knees

sukha = easy, lightness

Easy Pose

Sukhasana

(suk-AHS-uh-nuh)

Modification: knees to the chest, elbows to the outside of the knees, palms covering the face
Pose Type: seated, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Easy Pose

Sukhasana

(suk-AHS-uh-nuh)

Modification: knees high, forearms to the shins
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Easy Pose

Sukhasana

(suk-AHS-uh-nuh)

Modification: elbows crossed, backs of both hands to the knees

Pose Type: seated, mild backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

लं वं हं ॐ



EASY POSE: SPINE STRAIGHT

Easy Pose

Sukhasana

(suk-AHS-uh-nuh)

Modification: on the yoga block

Pose Type: seated

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

लं वं



Easy Pose

Sukhasana

(suk-AHS-uh-nuh)

Pose Type: seated

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Bound Hands Easy Pose

Baddha Hasta Sukhasana

(BUH-duh HUH-stuh suk-AHS-uh-nuh)

Modification: arms in front, arms straight

Pose Type: seated

Drishti Point: Hastagrai or Hastagre (hands), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Embryo in the Womb Pose in Easy Pose

Garbha Pindasana in Sukhasana

(GUHR-buh pin-DAHS-uh-nuh in suk-AHS-uh-nuh)

Modification: grabbing onto the outside edges of the feet

Pose Type: seated, forward bend, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व ॐ



EASY POSE: TWISTS & SIDE BENDS

Easy Pose

Sukhasana

(suk-AHS-uh-nuh)
Modification: neck stretch
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose)
ल व



Revolved Easy Pose

Parivritta Sukhasana

(puh-ri-VRIT-tuh suk-AHS-uh-nuh)
Pose Type: seated, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Sideways Easy Pose

Parshva Sukhasana

(PAHRSH-vuh suk-AHS-uh-nuh)

Modification: one forearm to the floor, other arm extended up over the head
Pose Type: seated, side bend
Drishti Point: Hastagrai or Hastagre (hands)



Revolved Bound Easy Pose

Parivritta Baddha Sukhasana

(puh-ri-VRIT-tuh BUH-duh suk-AHS-uh-nuh)

Modification: elbow to the floor
Pose Type: seated, forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)

ACCOMPLISHED ONE POSE

Accomplished One Pose

Siddhasana

(sid-DAHS-anna)

Modification: 1. one heel in front of the other
2. one foot tucked between the hamstring and the calf
Pose Type: seated
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)


1.


2.

FIRE LOG POSE

Fire Log Pose

Agnistambhasana

(uhg-ni-stuhm-BAHS-anna)

Modification: 1. spine straight, fingertips to the floor behind the hips
2. leaning forward, palms on the floor by the thighs
Pose Type: 1. seated
2. seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Revolved Fire Log Pose

Parivritta Agnistambhasana

(puh-ri-VRIT-tuh uhg-ni-stuhm-BAHS-uh-nuh)

Modification: hands in Anjali Mudra (Hands in Prayer)
1. elbow to the knee
2. elbow to the foot
Pose Type: seated, forward bend, twist

Drishti Point: Urdhva or Antara Drishti (up to the sky); Parshva Drishti (to the right), Parshva Drishti (to the left)


1.


2.

Revolved Bound Fire Log Pose

Parivritta Baddha Agnistambhasana

(puh-ri-VRIT-tuh BUH-duh uhg-ni-stuhm-BAHS-uh-nuh)

Modification: one elbow to the sole of the top foot, other arm behind the back, hand to the inside of the thigh
Pose Type: seated, forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Revolved Fire Log Pose

Parivritta Agnistambhasana

(puh-ri-VRIT-tuh uhg-ni-stuhm-BAHS-uh-nuh)

Modification: forearms to the floor

Pose Type: seated, forward bend, twist

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Fire Log Pose

Agnistambhasana

(uhg-ni-stuhm-BAHS-uh-nuh)

Modification: forward bend, palms together, fingers spread wide; elbows and forehead on the floor

Pose Type: seated, forward bend

Drishti Point: Nasagrai or Nasagre (nose)



HALF LOTUS POSE

Half Lotus Pose

Ardha Padmasana

(UHR-duh puhd-MAHS-uh-nuh)

Modification: back of the hands on the knees

Pose Type: seated

Drishti Point: Nasagrai or Nasagre (nose)

लं वं



Half Lotus Pose

Ardha Padmasana

(UHR-duh puhd-MAHS-uh-nuh)

Modification: Salute to the Buddha Mudra Hand Position: one palm facing up, fingertips of the other hand to the floor

Pose Type: seated

Drishti Point: Nasagrai or Nasagre (nose)

लं वं



Reverse Prayer Revolved Half Lotus Pose

Viparita Namaskar Parivrtta Ardha Padmasana

(vi-puh-REE-tuh nuh-muhs-KAHR puh-ri-VRIT-tuh UHR-duh puhd-MAHS-uh-nuh)

Also Known As: Back of the Body Prayer Revolved Half Lotus Pose (Paschima Namaskara Parivritta Ardha Padmasana)

Modification: top foot resting on the bottom knee

Pose Type: seated, twist

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Embryo in the Womb Pose in Half Lotus Pose

Garbha Pindasana in Ardha Padmasana

(guhr-buh-pin-DAHS-uh-nuh in UHR-duh puhd-MAHS-uh-nuh)

Modification: knees lifted toward the chest

Pose Type: seated, forward bend, core

Drishti Point: Nasagrai or Nasagre (nose)



LOTUS POSE: ARMS IN FRONT

Lotus Pose

Padmasana

(puhd-MAHS-uh-nuh)

Modification: back of the hands on the knees

Pose Type: seated

Drishti Point: Nasagrai or Nasagre (nose)



Lotus Pose

Padmasana

(puhd-MAHS-uh-nuh)

Modification: fingers interlocked, hands resting on the lap

Pose Type: seated

Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



LOTUS POSE: ARMS BEHIND

Reverse Prayer Lotus Pose

Viparita Namaskar Padmasana

(vi-puh-REE-tuh nuh-muhs-KAHR puhd-MAHS-uh-nuh)

Also Known As: Back of the Body Prayer Lotus Pose (Paschima Namaskara Padmasana)
Modification: 1. fingertips pointing down
2. fingertips pointing up
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose)





Bound Lotus Pose

Baddha Padmasana

(BUH-duh puhd-MAHS-uh-nuh)

Modification: both hands to one foot, one arm behind the back
Pose Type: seated, mild backbend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Bound Lotus Pose

Baddha Padmasana

(BUH-duh puhd-MAHS-uh-nuh)

Modification: both arms behind the back

Pose Type: seated, mild backbend, binding

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

लं वं रं यं हं ॐ



Hands Bound Lotus Pose

Baddha Hasta Padmasana

(BUH-duh HUH-stuh puhd-MAHS-uh-nuh)

Modification: backbend

Pose Type: seated, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

लं वं रं यं हं ॐ



Lotus Pose

Padmasana

(puhd-MAHS-uh-nuh)

Modification: palms to the floor behind the hips; fingertips facing forward, backbend
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



LOTUS POSE: FINGERS BOUND - BICEPS BY THE EARS

Raised Bound Hands Lotus Pose

Urdhva Baddha Hasta Padmasana

(OORD-vuh BUH-duh HUH-stuh puhd-MAHS-uh-nuh)

Also Known As: Seated Mountain Pose A (Parvatasana A)
Pose Type: seated, mild backbend
Drishti Point: Angushtamadhye (Thumbs)



Simple Yoga Seal

Laghu Yoga Mudra

(LUH-gu YO-guh MU-druh)

Also Known As: Seated Mountain Pose B (Parvatasana B)
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य



Sideways Simple Yoga Seal

Parshva Laghu Yoga Mudra

(PAHRSH-vuh LUH-gu YO-guh MU-druh)

Modification: fingers interlocked, palms facing out; arms straight to the side, forward bend
Pose Type: seated, forward bend, side bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य ह



Pose Dedicated to Siddhar Vaasamuni—Easy Version

Sukha Vaasamunvasana

(SUK-uh vah-sah-moo-NYAHS-uh-nuh)

Pose Type: seated, side bend, forward bend, twist

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Arms of Twist Dedicated to Sage Bharadvaja 2 in Revolved Lotus Pose

Hasta Bharadvajasana 2 in Parivritta Padmasana

(HUH-stuh buh-ruhd-vuhj-AHS-uh-nuh in puh-ri-VRIT-uh puhd-MAHS-uh-nuh)

Pose Type: seated, twist, binding

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Revolved Lotus Pose

Parivritta Padmasana

(puh-ri-VRIT-uh puhd-MAHS-uh-nuh)

Modification: hands in Anjali Mudra (Hands in Prayer)
Pose Type: seated, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



LOTUS POSE: SIDE BEND & TWISTS

Sideways Lotus Pose

Parshva Padmasana

(PAHRSH-vuh puhd-MAHS-uh-nuh)

Modification: forearm to the floor
Pose Type: seated, side bend
Drishti Point: Hastagrai or Hastagre (hands)



Revolved Western Intense Stretch Pose Lotus Pose

Parivritta Paschimottana Padmasana

(puh-ri-VRIT-uh puhsh-chi-mo-TAHN-nuh puhd-MAHS-uh-nuh)

Also Known As: Revolved Forward Bend Lotus Pose
Modification: shoulder to the floor, other arm extended to the sky
Pose Type: seated, forward bend, twist
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व



Pose Dedicated to Siddhar Vaasamuni—One Hand Modification

Eka Hasta Vaasamunvasana

(EY-kuh HUH-stuh [vah-sah-moo]-NYAHS-uh-nuh)

Pose Type: seated, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व ह



Pose Dedicated to Siddhar Vaasamuni

Vaasamunvasana

([vah-sah-moo-NYAHS-uh-nuh)

Pose Type: seated, forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



LOTUS POSE: FORWARD BEND

Yogic Seal Pose

Yoga Mudrasana

(YO-guh mu-DRAHS-uh-nuh)

Also Known As: Yoga Pose (Yogasana)
Modification: grabbing onto the wrist behind the back
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose) or Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Hands Bound Lotus Pose

Baddha Hasta Padmasana

(BUH-duh HUH-stuh puhd-MAHS-uh-nuh)

Also Known As: Yoga Seal (Yoga Mudra)
Modification: chin to the floor, forward bend
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose) or Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
● ● ● ● ● ●



Reverse Prayer Yogic Seal Pose

Viparita Namaskar Yoga Mudrasana

(vi-puh-REE-tuh nuh-muhs-KAHR YO-guh mu-DRAHS-uh-nuh)

Also Known As: Back of the Body Prayer Yogic Seal Pose (Paschima Namaskara Yoga Mudrasana)
Modification: forehead to the floor
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
● ● ●



Yogic Seal Pose Prep.

Yoga Mudrasana Prep.

(YO-guh mu-DRAHS-uh-nuh)

Modification: 1. using a yoga strap
2. wrists crossed behind the back, reaching toward the feet
Pose Type: seated, forward bend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व य ह ॐ



1.



2.

Sideways Yogic Seal Pose

Parshva Yoga Mudrasana

(PARHSH-vuh YO-guh mu-DRAHS-uh-nuh)

Also Known As: Sideways Bound Lotus Pose (Parshva Baddha Padmasana)
Modification: chin to the knee
Pose Type: seated, forward bend, binding, twist
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य



Yogic Seal Pose

Yoga Mudrasana

(YO-guh mu-DRAHS-uh-nuh)

Also Known As: Bound Lotus Pose (Baddha Padmasana)
Modification: 1. side view
2. front view
Pose Type: seated, forward bend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ





2.

LOTUS POSE: EMBRYO IN THE WOMB POSE

Embryo in the Womb Pose

Garbha Pindasana

(guhr-buh pin-DAHS-uh-nuh)

Modification: arms wrapped around the legs

Pose Type: seated, forward bend, core

Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व र य



Hand Position of the Pose Dedicated to Garuda in Yoga Pose A

Hasta Garudasana in Yogasana A

(HUH-stuh guh-ru-DAHS-uh-nuh in yo-GAHS-uh-nuh)

Pose Type: seated, forward bend, core

Drishti Point: Angushtamadhye or Angustha Ma Dyai (thumbs)

ल व र य ह



Embryo in the Womb Pose

Garbha Pindasana

(guhr-buh pin-DAHS-uh-nuh)

Pose Type: seated, forward bend, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) or Nasagrai or Nasagre (nose)



BOTH KNEES BENT: BINDING & TWISTS

Bound Sundial Pose

Baddha Surya Yantrasana

(BUH-duh SOOR-yuh yuhn-TRAHS-uh-nuh)

Modification: both knees bent
Pose Type: seated, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)



Revolved Pose Dedicated to Sage Marichi

Parivritta Marichyasana

(puh-ri-VRIT-tuh muh-ree-CHYAHS-uh-nuh)

Modification: twisting to the inside, foot to the thigh, binding under the leg
Pose Type: seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Half Lord of the Fishes Pose 3

Ardha Matsyendrasana 3

(UH-ruh muhts-yeyn-DRAHS-uh-nuh)

Modification: looking to the back
Pose Type: seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Pose Dedicated to Sage Marichi 4

Marichyasana 4

(muh-ree-CHYAHS-uh-nuh)

Modification: binding under the knee
Pose Type: seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
ल व



BOTH KNEES BENT: BINDING & TWISTS—ARM THREADED UNDER

Half Pose Dedicated to Sage Agasthiyar

Ardha Agasthiyarasana

(UHR-duh uh-guhs-ti-yahr-AH-suh-nuh)

Modification: 1. one arm threaded through
2. full expression of the pose
Pose Type: 1. seated, forward bend, twist, binding
2. seated, forward bend, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky), Nasagrai or Nasagre (nose), or Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

1.



2.



Revolved Half Pose Dedicated to Sage Agasthiyar

Parivritta Ardha Agasthiyarasana
(puh-ri-VRIT-tuh UHR-duh uh-guhs-ti-yahr-AH-suh-nuh)
Pose Type: seated, forward bend, binding, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Pose Dedicated to Sage Agasthiyar

Agasthiyarasana

(uh-guhs-ti-yahr-AH-suh-nuh)

Modification: 1. prep. one arm threaded under the knee, fingertips of the other hand to the floor
2. full expression of the pose

Pose Type: seated, forward bend, binding

Drishti Point: 1. Hastagrai or Hastagre (hands)
2. Nasagrai or Nasagre (nose)

1.



2.



BOTH KNEES BENT: BINDING & TWISTS—KNEES TOGETHER

Seated Noose Pose Prep.

Upavishta Pashasana

(u-puh-VISH-tuh puh-SHAHS-uh-nuh)

Also Known As: Half Noose Pose (Ardha Pashasana), Upavistha Pashasana

Modification: 1. grabbing onto the knees
2. elbow over the opposite knee

Pose Type: seated, forward bend, twist

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)





Seated Noose Pose Prep.

Upavishta Pashasana

(u-puh-VISH-tuh puh-SHAHS-uh-nuh)

Also Known As: Upavistha Pashasana
Modification: heels lifted; elbow over the opposite knee, hands in Anjali Mudra (Hands in Prayer)
Pose Type: seated, forward bend, twist, core
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Seated Noose Pose

Upavishta Pashasana

(u-puh-VISH-tuh puh-SHAHS-uh-nuh)

Also Known As: Upavistha Pashasana

Modification: binding around both legs under the knees

Pose Type: seated, forward bend, twist, binding

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Seated Noose Pose

Upavishta Pashasana

(u-puh-VISH-tuh puh-SHAHS-uh-nuh)

Also Known As: Upavistha Pashasana

Modification: binding around both shins

Pose Type: seated, forward bend, twist, binding

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Half Lord of the Fishes Pose

Ardha Matsyendrasana

UHR-duh muhts-yeyn-DRAHS-uh-nuh

Pose Type: seated, forward bend, side bend, twist

Drishti Point: Padhayoragrai or Padayoragre (toes/feet)

How to Perform the Pose:

1. Begin by sitting on the floor with both your legs straight out in front of you. Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale as you bend the right knee toward your right shoulder and then bring it over your left leg so that your right foot is flat on the floor on the outside of your left shin.
3. Exhale and bend your left knee, bringing your left heel toward your right sitting bone. Keep the left knee and both your sitting bones evenly on the floor.
4. Exhale as you bring your right elbow to your right knee. Inhale as you bring your left arm up over your head and look towards your left foot (Pose #1).
5. To execute pose #2, exhale as you bring your left elbow over the right knee. Inhale as you bring your right arm up and exhale as you bend your right elbow and look over toward your right foot.
6. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch.
7. Inhale as you release the twist and exhale as you bring both your legs out in front of you. Repeat on the other side.

Modification: side bend twist:
1. elbow to the knee on the same side
2. elbow to the opposite knee

ardha = half

Matsyendra = a Hindu sage and one of the first teachers of Hatha yoga, a legend, king of the fish

1.

2.

Half Lord of the Fishes Pose

Ardha Matsyendrasana

(UHR-duh muhts-yeyn-DRAHS-uh-nuh)

Modification: backbend
Pose Type: seated, backbend, forward bend
Drishti Point: Hastagrai or Hastagre (hands)



Half Lord of the Fishes Pose

Ardha Matsyendrasana

(UHR-duh muhts-yeyn-DRAHS-uh-nuh)

Modification: twisting to the inside
1. grabbing onto the ankle
2. elbow over the knee
Pose Type: seated, forward bend, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)





Half Lord of the Fishes Pose

Ardha Matsyendrasana

(UHR-duh muhts-yeyn-DRAHS-uh-nuh)

Modification: twisting to the outside, elbow over the knee; palm of the other hand to the floor
Pose Type: seated, forward bend, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
● ●



Half Lord of the Fishes Pose 1

Ardha Matsyendrasana 1

(UHR-duh muhts-yeyn-DRAHS-uh-nuh)

Modification: grabbing onto the ankle, other arm behind the back, hand to the inside of the thigh
Pose Type: seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
● ●



BOTH KNEES BENT: BINDING FORWARD BEND & TWIST

Pose Dedicated to Sage Marichi 3 Prep.

Marichyasana 3 Prep.

(muh-ree-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi B (Marichyasana B)
Modification: top foot to the bottom thigh, binding around the shin, nose to the knee
Pose Type: seated, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)
ल व र



Pose Dedicated to Sage Marichi 4 Prep.

Marichyasana 4 Prep.

(muh-ree-CHYAHS-uh-nuh)

Modification: sitting in a cross-legged position, one knee dropped to the side, foot by the sitting bones; other knee bent toward the shoulder, binding around the shin on the outside of the leg
Pose Type: seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



BOTH KNEES BENT: BINDING & TWIST

Pose Dedicated to Sage Marichi 3 Prep.

Marichyasana 3 Prep.

(muh-ree-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi B (Marichyasana B)
Modification: spine straight, bottom knee wrapped around the foot, fingers interlocked on the shin
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Pose Dedicated to Sage Marichi 3 Prep.

Marichyasana 3 Prep.

(muh-ree-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi B Modification (Marichyasana B Modification)
Modification: bottom knee wrapped around the foot, binding under the thigh

Pose Type: seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
ल व य



Pose Dedicated to Sage Marichi 3 Prep.

Marichyasana 3 Prep.

(muh-ree-CHYAHS-uh-nuh)
Also Known As: Pose Dedicated to Sage Marichi B Modification (Marichyasana B Modification)
Modification: knee wrapped around the foot, binding over the shin
Pose Type: 1. seated, forward bend, binding
2. seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
ल व र य





Half Lord of the Fishes Pose 1 Prep.

Ardha Matsyendrasana 1

(UHR-duh muhts-yeyn-DRAHS-uh-nuh)

Modification: foot under the knee, twisting to the outside
Pose Type: seated, forward bend, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
ल व र



HALF LOTUS POSE: KNEE BENT TOWARD THE CHEST

Pose Dedicated to Sage Marichi Prep.

Marichyasana Prep.

(muh-ree-CHYAHS-uh-nuh)

Modification: prep.-—elbow to the knee on the same side, palm to the floor behind the hips
Pose Type: seated, forward bend
Drishti Point: Hastagrai or Hastagre (hands)
ल व



Pose Dedicated to Sage Marichi Prep.

Marichyasana Prep.

(muh-ree-CHYAHS-uh-nuh)

Modification: prep.—arms wrapping around the leg
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
● ● ● ●



HALF LOTUS POSE: BINDING & TWISTS—KNEE BENT TOWARD THE CHEST

Pose Dedicated to Sage Marichi 3

Marichyasana 3

(muh-ree-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi B (Marichyasana B)
Modification: sitting up straight
Pose Type: seated, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)
● ●



Pose Dedicated to Sage Marichi 3

Marichyasana 3

(muh-ree-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi B (Marichyasana B)
Modification: full forward bend
Pose Type: seated, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)



Pose Dedicated to Sage Marichi 4

Marichyasana 4

(muh-ree-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi D (Marichyasana D)
Modification: sitting bones on the floor
Pose Type: seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



LOTUS POSE: BINDING & TWISTS—KNEE BENT TOWARD THE CHEST

Full Lord of the Fishes Pose Prep.

Paripurna Matsyendrasana Prep.

(puh-ri-POOR-nuh muhts-yeyn-DRAHS-uh-nuh)

Modification: one palm to the floor behind the hips, grabbing onto the knee with the opposite hand
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
● ●



Full Lord of the Fishes Pose

Paripurna Matsyendrasana

(puh-ri-POOR-nuh muhts-yeyn-DRAHS-uh-nuh)

Also Known As: Full Lord of the Fishes Pose (Poorna Matsyendrasana)
Pose Type: seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
● ●

FOOT TO THE BACK: TWISTS—KNEE BENT TOWARD THE CHEST

Root Lord of the Fishes Pose Prep.

Mula Matsyendrasana Prep.

(MOOL-uh muhts-yeyn-DRAHS-uh-nuh)

Modification: heel to the perineum, other foot resting on the knee, fingertips to the floor by the hips
Pose Type: seated, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Half Root Lord of the Fishes Pose

Ardha Mula Matsyendrasana

(UHR-duh MOOL-uh muhts-yeyn-DRAHS-uh-nuh)

Modification: heel to the perineum, other foot resting on the knee, fingertips of one hand to the floor by the hips, other hand grabbing onto the opposite knee
Pose Type: seated, forward bend, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)

Root Lord of the Fishes Pose Prep.

Mula Matsyendrasana Prep.

(MOOL-uh muhts-yeyn-DRAHS-uh-nuh)

Modification: backbend, heel to the perineum, other foot resting on the knee, fingertips to the floor behind the hips
Pose Type: seated, backbend, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Pose Dedicated to Sage Marichi 6 Prep.

Marichyasana 6 Prep.

(muh-ree-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi F (Marichyasana F)
Modification: opposite hand grabbing onto the foot, heel resting on the knee, other arm behind the back to the inside of the thigh, looking over the shoulder to the back
Pose Type: seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Pose Dedicated to Sage Marichi 6 Prep.

Marichyasana 6 Prep.

(muh-ree-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi F (Marichyasana F)
Modification: opposite hand grabbing onto the foot, foot flat to the floor, other arm behind the back to the inside of the thigh, looking toward the foot
Pose Type: seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



BOUND ANGLE POSE: ARMS IN FRONT

Bound Angle Pose with Hands in Prayer

Baddha Konasana Namaskar

(BUH-duh ko-NAHS-uh-nuh nuh-muhs-KAHR)

Modification: hands in Anjali Mudra (Hands in Prayer)
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose) or Hastagrai or Hastagre (hands)

Bound Angle Pose

Baddha Konasana

(BUH-duh ko-NAHS-uh-nuh)

Modification: fingertips touching the floor
Pose Type: seated
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Bound Angle Pose

Baddha Konasana

(BUH-duh ko-NAHS-uh-nuh)

Modification: half forward bend, opening the soles of the feet up to the sky
Pose Type: seated, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BOUND ANGLE POSE: ARMS BEHIND

Bound Angle Pose

Baddha Konasana

(BUH-duh ko-NAHS-uh-nuh)

Modification: one hand to the knee; other hand behind, grabbing onto the bicep
Pose Type: seated, binding
Drishti Point: Nasagrai or Nasagre (nose)
ल व य



Bound Hands Bound Angle Pose

Baddha Hasta Baddha Konasana

(BUH-duh HUH-stuh BUH-duh ko-NAHS-uh-nuh)

Modification: arms behind, grabbing onto the elbows
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose)
ल व य



Reverse Prayer Bound Angle Pose

Viparita Namaskar Baddha Konasana

(vi-puh-REE-tuh nuh-muhs-KAHR BUH-duh ko-NAHS-uh-nuh)

Also Known As: Back of the Body Prayer Bound Angle Pose (Paschima Namaskara Baddha Konasana)
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose)



Hand Position of Cow Face Pose in Bound Angle Pose

Hasta Gomukhasana in Baddha Konasana

(HUH-stuh go-muk-AHS-uh-nuh in BUH-duh ko-NAHS-uh-nuh)

Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose)



BOUND ANGLE POSE: SIDE BEND & BINDING

Sideways Bound Angle Pose

Parshva Baddha Konasana

(PAHRSH-vuh BUH-duh ko-NAHS-uh-nuh)

Pose Type: seated, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Sideways Star Pose

Parshva Tarasana

(PAHRSH-vuh tahr-AHS-uh-nuh)

Pose Type: seated, side bend
Drishti Point: Hastagrai or Hastagre (hands)



Sideways Bound Leg Bound Angle Pose

Parshva Baddha Pada Baddha Konasana

(PAHRSH-vuh BUH-duh PUH-duh BUH-duh ko-NAHS-uh-nuh)

Modification: binding around one leg, arm wrapped around the shin
Pose Type: seated, forward bend, side bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)
● ● ●



BOUND ANGLE POSE: HEELS CLOSE, FEET LIFTED, SITTING BONES LIFTED AND FORWARD BEND

Pose Dedicated to Sage Goraksha

Gorakshasana

(go-rahk-SHAHS-uh-nuh)

Modification: feet in Bound Angle Pose (Baddha Konasana), sitting on the heels
1. one hand to the centre of the chest, other hand to the floor behind the hips
2. hands in Anjali Mudra (Hands in Prayer)
Pose Type: seated, balance
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)


1.


2.

Equilibrium Bound Angle Pose 1

Tulya Baddha Konasana 1

(TUL-yuh BUH-duh ko-NAHS-uh-nuh)

Modification: feet lifted off the floor
Pose Type: seated, forward bend, core
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Equilibrium Bound Angle Pose 2

Tulya Baddha Konasana 2

(TUL-yuh BUH-duh ko-NAHS-uh-nuh)

Modification: sitting bones lifted off the floor
Pose Type: seated, forward bend, core
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Bound Angle Pose

Baddha Konasana

(BUH-duh ko-NAHS-uh-nuh)

Modification: forward bend; arms straight to the front, palms down
Pose Type: seated, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs) or Nasagrai or Nasagre (nose)



BOUND ANGLE POSE: FORWARD BEND

Bound Angle Pose

Baddha Konasana

(BUH-duh ko-NAHS-uh-nuh)

Modification: 1. half forward bend
2. full forward bend, chin to the floor
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose) or Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Bound Angle Pose

Baddha Konasana

(BUH-duh ko-NAHS-uh-nuh)

Modification: elbows bent and to the floor, forehead to the floor, palms together, fingers spread wide
Pose Type: seated, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) or Nasagrai or Nasagre (nose)

STAR POSE

Easy Embryo in the Womb Pose

Sukha Garbha Pindasana

(SUK-uh GUHR-buh pin-DAHS-uh-nuh)

Modification: arms under the legs
1. hands to the feet
2. fingertips to the temples
3. hands to the sides; heels touching, feet to the sides

Pose Type: seated, forward bend, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)


1.


2.



Easy Embryo in the Womb Pose

Sukha Garbha Pindasana

(SUK-uh GUHR-buh pin-DAHS-uh-nuh)

Also Known As: Yoga Pose A Prep. (Yogasana A Prep.)
Modification: shins into armpits, hands in Anjali Mudra (Hands in Prayer)
Pose Type: seated, forward bend, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Star Pose

Tarasana

(tahr-AHS-uh-nuh)

Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Upward Star Pose

Urdhva Tarasana

(OORD-vuh tahr-AHS-uh-nuh)

Pose Type: seated, forward bend, core
Drishti Point: Padhayoragrai or Padayoragre (toes/feet) or Nasagrai or Nasagre (nose)
लं वं ॐ



LEGS IN FRONT: KNEES BENT

Seated Eastern Intense Stretch Pose

Upavishta Purvottanasana

(u-puh-VISH-tuh poor-vo-TAHS-uh-nuh)

Also Known As: Reverse Plank Prep.; Upavistha Purvottanasana
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं रं यं हं ॐ



One Hand Seated Eastern Intense Stretch Pose

Eka Hasta Upavishta Purvottanasana

(EY-kuh HUH-stuh u-puh-VISH-tuh poor-vo-TAHS-uh-nuh)

Also Known As: One Hand Reverse Plank Prep.; Eka Hasta Upavistha Purvottanasana
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Hastagrai or Hastagre (hands)
ल र य ह ॐ



LEGS IN FRONT: KNEES BENT—LEGS OUTSIDE OF THE SHOULDERS

Seated Knee to Shoulder Pose

Upavishta Janu Bhujasana

(u-puh-VISH-tuh JAH-nu buj-AHS-uh-nuh)

Also Known As: Upavistha Janu Bhujasana
Modification: hands in Anjali Mudra (Hands in Prayer)
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Broken Wing Pose

Avabhinna Pakshakasana

(uh-vuh-BIN-uh puhk-shuh-KAHS-uh-nuh)

Pose Type: seated, forward bend

Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Tortoise Pose Prep.

Kurmasana Prep.

(koor-MAHS-uh-nuh)

Modification: grabbing onto the ankles

Pose Type: seated, forward bend

Drishti Point: Padhayoragrai or Padayoragre (toes/feet) or Nasagrai or Nasagre (nose)

Tortoise Pose Prep.

Kurmasana Prep.

(koor-MAHS-uh-nuh)

Modification: 1. arms straight
2. elbows bent
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose,) Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Sleeping Tortoise Pose Prep.

Supta Kurmasana Prep.

(SUP-tuh koor-MAHS-uh-nuh)

Modification: feet unhooked

Pose Type: seated, forward bend, binding

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Sleeping Tortoise Pose

Supta Kurmasana

(SUP-tuh koor-MAHS-uh-nuh)

Pose Type: seated, forward bend, binding

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



HORIZONTAL SPLITS: LEGS LIFTED—KNEES BENT

Half Upward Seated Angle Pose Prep.

Ardha Urdhva Upavistha Konasana Prep.

(UHR-duh OORD-vuh u-puh-VISH-tuh ko-NAHS-uh-nuh)

Modification: shoulders to the back of the knees, palms to the floor, knees bent
Pose Type: seated, forward bend, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



Bound Legs in Half Pose Dedicated to Sage Koormamuni

Baddha Pada Ardha Koormamunyasana

(BUH-duh PUH-duh UHR-duh koor-muh-mun-YAHS-uh-nuh)

Pose Type: seated, forward bend, core, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



HORIZONTAL SPLITS: LEGS LIFTED

Half Upward Seated Angle Pose Prep. in One Hand to Foot Boat Pose

Ardha Urdhva Upavishta Konasana Prep. in Eka Hasta Pada Navasana

(UHR-duh OORD-vuh u-puh-VISH-tuh ko-NAHS-uh-nuh in EY-kuh HUH-stuh PUH-duh nuh-VAHS-uh-nuh)

Also Known As: Ardha Urdhva Upavistha Konasana Prep. in Eka Hasta Pada Navasana
Modification: one leg straight, back of the other knee to the shoulder
Pose Type: seated, forward bend, core
Drishti Point: Hastagrai or Hastagre (hands) or Padhayoragrai or Padayoragre (toes/feet)



Half Upward Seated Angle Pose

Ardha Urdhva Upavishta Konasana

(UHR-duh OORD-vuh u-puh-VISH-tuh ko-NAHS-uh-nuh)
Also Known As: Ardha Urdhva Upavistha Konasana
Modification: palms to the floor, one leg straight up to the sky; other foot to the floor, knee to the chest
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Upward Seated Angle Pose

Urdhva Upavishta Konasana

(UHR-duh OORD-vuh u-puh-VISH-tuh ko-NAHS-uh-nuh)

Also Known As: Urdhva Upavistha Konasana
Modification: arms open to the sides, triceps to the back of the knees
Pose Type: seated, forward bend, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)
● ● ●



HORIZONTAL SPLITS: LEGS LIFTED & STRAIGHT

Seated Firefly Pose

Upavishta Tittibhasana

(u-puh-VISH-tuh ti-ti-BAHS-uh-nuh)
Also Known As: Upward Seated Angle Pose Prep. (Urdhva Upavishta Konasana Prep.), Pose Dedicated to Sage Koormamuni Prep. (Koormamunyasana Prep.), Upavistha Tittibhasana
Modification: palms to the floor, shoulders to the back of the knees
Pose Type: seated, forward bend, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)
● ●



Pose Dedicated to Sage Koormamuni

Koormamunyasana

(koor-muh-mun-YAHS-uh-nuh)

Modification: hands in Anjali Mudra (Hands in Prayer)

Pose Type: seated, forward bend, core

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



Pose Dedicated to Sage Koormamuni—Bound Legs

Baddha Pada Koormamunyasana

(BUH-duh PUH-duh koor-muh-mun-YAHS-uh-nuh)

Modification: legs straight

Pose Type: seated, forward bend, core, binding

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



Hands to Feet Upward Seated Angle Pose

Pada Hasta Urdhva Upavishta Konasana

(PUH-duh HUH-stuh OORD-vuh u-puh-VISH-tuh ko-NAHS-uh-nuh)

Also Known As: Pada Hasta Urdhva Upavistha Konasana
Modification: grabbing onto the outside edges of the feet
Pose Type: seated, forward bend, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Urdhva or Antara Drishti (up to the sky)



Big Toe Upward Seated Angle Pose

Padangushta Urdhva Upavishta Konasana

(puhd-ahng-GOOSH-tuh OORD-vuh u-puh-VISH-tuh ko-NAHS-uh-nuh)

Also Known As: Padangushta Urdhva Upavistha Konasana
Modification: grabbing onto the big toes, arms parallel to the floor
Pose Type: seated, forward bend, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) or Urdhva or Antara Drishti (up to the sky)



Upward Seated Angle Pose

Urdhva Upavishta Konasana

(OORD-vuh u-puh-VISH-tuh ko-NAHS-uh-nuh)

Also Known As: Urdhva Upavistha Konasana

Modification: palms to the floor, heels of the palms touching, fingertips pointing to the sides; feet lifted, toes pointed

Pose Type: seated, forward bend, core

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Urdhva or Antara Drishti (up to the sky)



HORIZONTAL SPLITS: FORWARD BEND

Tortoise Pose

Kurmasana

(koor-MAHS-uh-nuh)

Modification: 1. knees bent

2. legs straight

Pose Type: seated, forward bend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Equal Angle Pose

Samakonasana

(suh-muh-ko-NAHS-uh-nuh)

Modification: forward bend, forearms to the floor
Pose Type: seated, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
● ● ●



Big Toe Seated Angle Pose

Padangushta Upavishta Konasana

(puhd-ahng-GOOSH-tuh u-puh-VISH-tuh ko-NAHS-uh-nuh)

Also Known As: Padangushta Upavistha Konasana
Modification: forward bend, chin to the floor
Pose Type: seated, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



Equal Angle Pose

Samakonasana

(suh-muh-ko-NAHS-uh-nuh)

Modification: forward bend, arms crossed in front
Pose Type: seated, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)
ल व र य ॐ



Equal Angle Pose

Samakonasana

(suh-muh-ko-NAHS-uh-nuh)

Modification: forward bend, arms extended to the front
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य ॐ



Reverse Prayer Equal Angle Pose

Viparita Namaskar Samakonasana

(vi-puh-REE-tuh nuh-muhs-KAHR suh-muh-ko-NAHS-uh-nuh)

Also Known As: Back of the Body Prayer Equal Angle Pose (Paschima Namaskara Samakonasana)
Pose Type: seated, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Hands Bound Equal Angle Pose

Baddha Hasta Samakonasana

(BUH-duh HUH-stuh suh-muh-ko-NAHS-uh-nuh)
Modification: forward bend
Pose Type: seated, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



HORIZONTAL SPLITS: SPINE STRAIGHT

Seated Angle Pose

Upavishta Konasana

(u-puh-VISH-tuh ko-NAHS-uh-nuh)
Also Known As: Upavistha Konasana

Modification: mild version, backbend
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं वं रं यं हं ॐ



Seated Angle Pose

Upavishta Konasana

(u-puh-VISH-tuh ko-NAHS-uh-nuh)
Also Known As: Upavistha Konasana
Modification: 1. hands in Anjali Mudra (Hands in Prayer), toes flexed in
2. hands in reverse prayer, toes flexed in
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose) or Hastagrai or Hastagre (hands)
लं वं





Seated Angle Pose

Upavishta Konasana

(u-puh-VISH-tuh ko-NAHS-uh-nuh)

Also Known As: Upavistha Konasana
Modification: palms to the floor in front of the hips, heels of the palms touching, fingertips pointing to the side, straight spine, toes pointed
Pose Type: seated
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Equal Angle Pose

Samakonasana

(su-muh-ko-NAHS-uh-nuh)

Modification: hands on the knees, spine straight
Pose Type: seated
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



Bound Equal Angle Pose

Baddha Samakonasana

(BUH-duh su-muh-ko-NAHS-uh-nuh)

Pose Type: seated, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)
ल व य



HORIZONTAL SPLITS: TWISTS

Half Bound Seated Angle Pose

Ardha Baddha Upavishta Konasana

(UHR-duh BUH-duh u-puh-VISH-tuh ko-NAHS-uh-nuh)

Also Known As: Ardha Baddha Upavistha Konasana
Modification: toes pointed, one hand binding behind the back, fingertips of the other hand to the floor in front of the hips
Pose Type: seated, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)

Revolved Half Bound Equal Angle Pose

Parivritta Samakonasana

(puh-ri-VRIT-tuh suh-muh-ko-NAHS-uh-nuh)

Modification: 1. toes pointed, both hands on one leg
2. toes flexed in, one hand to the leg, other hand to the floor
Pose Type: seated, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)





Revolved Bound Equal Angle Pose

Parivritta Baddha Samakonasana

(puh-ri-VRIT-tuh BUH-duh suh-muh-ko-NAHS-uh-nuh)

Modification: 1. toes pointed
2. toes flexed in
Pose Type: seated, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)





HORIZONTAL SPLITS: SIDE BENDS

Sideways Equal Angle Pose

Parshva Samakonasana

(PAHRSH-vuh suh-muh-ko-NAHS-uh-nuh)

Modification: side bend, fingertips to the back of the head; elbow to the floor
Pose Type: seated, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Both Hands to Foot Revolved Seated Angle Pose

Dwi Hasta Pada Parivritta Upavishta Konasana

(DWI-huh-stuh PUH-duh puh-ri-VRIT-tuh u-puh-VISH-tuh ko-NAHS-uh-nuh)

Also Known As: Dwi Hasta Pada Parivritta Upavistha Konasana
Pose Type: seated, side bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व र य



LEGS STRAIGHT IN FRONT: SPINE STRAIGHT & BACKBEND

Staff Pose

Dandasana

(duhn-DAHS-uh-nuh)

Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose), Padhayoragrai or Padayoragre (toes/feet)
ल



Reverse Prayer Staff Pose

Viparita Namaskar Dandasana

(vi-puh-REE-tuh nuh-muhs-KAHR duhn-DAHS-uh-nuh)

Also Known As: Back of the Body Prayer Staff Pose (Paschima Namaskara Dandasana)
Pose Type: seated
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose)
ल ह



Staff Pose

Dandasana

(duhn-DAHS-uh-nuh)

Modification: 1. fingertips pointing to the heels
2. fingertips pointing away from the heels, head rolling back
Pose Type: seated, mild backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल य ह ॐ





LEGS STRAIGHT IN FRONT: FORWARD BEND

Western Intense Stretch Pose

Paschimottanasana

(puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Seated Forward Bend
Modification: grabbing onto the big toes
Pose Type: seated, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose)
● ● ●



Western Intense Stretch Pose

Paschimottanasana

(puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Seated Forward Bend
Modification: grabbing onto the balls of the feet
Pose Type: seated, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose)



Western Intense Stretch Pose

Paschimottanasana

(puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Seated Forward Bend
Modification: grabbing onto the wrist
Pose Type: seated, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose)



Western Intense Stretch Pose

Paschimottanasana

(puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Seated Forward Bend
Modification: palms down
Pose Type: seated, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose)

लं रं यं



Bound Hands Western Intense Stretch Pose

Baddha Hasta Paschimottanasana

(BUH-duh HUH-stuh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Seated Forward Bend
Pose Type: seated, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose)

लं रं यं



Reverse Prayer Western Intense Stretch Pose

Viparita Namaskar Paschimottanasana

(vi-puh-REE-tuh nuh-muhs-KAHR puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Back of the Body Prayer Western Intense Stretch Pose (Paschima Namaskara Paschimottanasana), Reverse Prayer Forward Bend

Pose Type: seated, forward bend

Drishti Point: Padayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose)



LEGS STRAIGHT IN FRONT: TWISTS

Revolved Staff Pose

Parivritta Dandasana

(puh-ri-VRIT-tuh duhn-DAHS-uh-nuh)

Pose Type: seated, twist

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Revolved Upward One Arm Extended Hand to Foot Staff Pose

Parivritta Urdhva Eka Hasta Utthita Hasta Pada Dandasana

(puh-ri-VRIT-tuh OORD-vuh EY-kuh HUH-stuh UT-tu-tuh HUH-stuh PUH-duh duhn-DAHS-uh-nuh)

Pose Type: seated, forward bend, twist

Drishti Point: Hastagrai or Hastagre (hands)



One Hand Revolved Western Intense Stretch Pose

Eka Hasta Parivritta Paschimottanasana

(EY-kuh HUH-stuh puh-ri-VRIT-tuh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: One Hand Revolved Seated Forward Bend

Modification: one hand to the foot

Pose Type: seated, forward bend, side bend, twist

Drishti Point: Urdhva or Antara Drishti (up to the sky)



Two Hands Revolved Western Intense Stretch Pose

Dwi Hasta Parivritta Paschimottanasana

(DWI-huh-stuh puh-ri-VRIT-tuh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Two Hands Revolved Forward Bend

Pose Type: seated, forward bend, side bend, twist

Drishti Point: Urdhva or Antara Drishti (up to the sky)

लं



LEGS STRAIGHT: ON THE SIDE & SCISSOR LEGS

Upward Side Infinity Pose

Urdhva Parshva Anantasana

(OORD-vuh PARSH-vuh uh-nuhn-TAHS-uh-nuh)

Pose Type: seated, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)
लं हं



One Leg Upward Hand to Knee Revolved Staff Pose

Urdhva Eka Pada Janu Hasta Parivritta Dandasana

(OORD-vuh EY-kuh PUH-duh JAH-nu HUH-stuh puh-ri-VRIT-tuh duhn-DAHS-uh-nuh)

Pose Type: seated, forward bend, twist
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
लं वं रं



One Leg Upward Hand to Foot Revolved Staff Pose

Urdhva Eka Pada Hasta Pada Parivritta Dandasana

(OORD-vuh EY-kuh PUH-duh HUH-stuh PUH-duh puh-ri-VRIT-tuh duhn-DAHS-uh-nuh)

Pose Type: seated, forward bend, twist
Drishti Point: Parsva Drishti (to the right), Parsva Drishti (to the left)
ल व



One Hand to Foot Archer’s Pose

Eka Hasta Pada Akarna Dhanurasana

(EY-kuh HUH-stuh PUH-duh AH-kuhr-nuh duh-nur-AHS-uh-nuh)

Modification: both legs straight, knee behind the shoulder, other palm to the floor
Pose Type: seated, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व य



Bound Leg Archer’s Pose

Baddha Pada Akarna Dhanurasana

(BUH-duh PUH-duh AH-kuhr-nuh duh-nur-AHS-uh-nuh)

Pose Type: seated, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व य



ONE LEG STRAIGHT, ONE LEG BENT

Archer’s Pose Prep.

Akarna Dhanurasana Prep.

(AH-kuhr-nuh duh-nur-AHS-uh-nuh)

Modification: knee wrapping around the arm
Pose Type: seated, mild backbend
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व ह



Archer’s Pose

Akarna Dhanurasana

(AH-kuhr-nuh duh-nur-AHS-uh-nuh)

Modification: foot to the ear
Pose Type: seated, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Foot Behind the Head Pose

Eka Pada Shirshasana

(EY-kuh PUH-duh sheer-SHAHS-uh-nuh)

Also Known As: Foot Behind the Head Pose A (Eka Pada Shirshasana A)
Modification: leg straight
1. palms to the floor by the hips
2. hands in Anjali Mudra (Hands in Prayer)
Pose Type: seated
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)


1.


2.

Pose Dedicated to Skanda

Skandasana

(skuhn-DAHS-uh-nuh)

Also Known As: Foot Behind the Head Pose B (Eka Pada Shirshasana B)
Pose Type: seated, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)
● ● ● ● ●



ONE LEG STRAIGHT, ONE LEG BENT: TWISTS

Easy Lord of the Fishes Pose Prep.

Sukha Matsyendrasana Prep.

(SUK-uh muhts-yeyn-DRAHS-uh-nuh)

Modification: one leg straight, arm wrapped around the bent knee
Pose Type: seated, forward bend, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Easy Lord of the Fishes Pose

Sukha Matsyendrasana

(SUK-uh muhts-yeyn-DRAHS-uh-nuh)

Pose Type: seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



ONE LEG STRAIGHT, ONE LEG BENT: KNEE TO THE CHEST

Pose Dedicated to Sage Marichi 1 & 2 Prep.

Marichyasana 1 & 2 Prep.

(muh-ree-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi A & C Prep. (Marichyasana A & C Prep.)
Modification: arms parallel to the floor in front of the chest
Pose Type: seated, forward bend
Drishti Point: Hastagrai or Hastagre (hands)



Pose Dedicated to Sage Marichi 1 & 2 Prep.

Marichyasana 1 & 2 Prep.

(muh-ree-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi A & C Prep. (Marichyasana A & C Prep.)
Modification: both hands grabbing onto the foot of the straight leg
Pose Type: seated, forward bend
Drishti Point: Padhayoragrai or Padayoragre (toes/feet)



Revolved Pose Dedicated to Sage Marichi 1 Prep.

Parivritta Marichyasana 1 Prep.

(puh-ri-VRIT-tuh muh-ree-CHYAHS-uh-nuh)

Modification: twisting to the inside of the bent knee, elbow to the knee

Pose Type: seated, forward bend, twist

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



ONE LEG STRAIGHT, ONE LEG BENT: KNEE TO THE CHEST—BINDING & TWIST

Pose Dedicated to Sage Marichi 1

Marichyasana 1

(muh-ree-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi A (Marichyasana A)

Modification: 1. spine straight
2. half forward bend
3. full forward bend, nose to the shin

Pose Type: seated, forward bend, binding

Drishti Point: 1. Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
2 & 3. Padhayoragrai or Padayoragre (toes/feet) or Nasagrai or Nasagre (nose)

1.



2.



3.



Pose Dedicated to Sage Marichi 2 Prep.

Marichyasana 2 Prep.

(muh-ree-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi C (Marichyasana C)
Modification: elbow over the bent knee
Pose Type: seated, forward bend, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Pose Dedicated to Sage Marichi 2 Prep.

Marichyasana 2 Prep.

(muh-ree-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi C (Marichyasana C)
Modification: grabbing onto the knee of the straight leg
Pose Type: seated, forward bend, twist, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) or Padhayoragrai or Padayoragre (toes/feet)



Pose dedicated to Sage Marichi 2

Marichyasana 2

(muh-ree-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi C (Marichyasana C)
Pose Type: seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



ONE LEG STRAIGHT & LIFTED, ONE LEG BENT

Seated Revolved Upward One Hand to Foot Pose

Upavishta Parivritta Urdhva Eka Pada Hastasana

(u-puh-VISH-tuh puh-ri-VRIT-tuh OORD-vuh EY-kuh PUH-duh huh-STAHS-uh-nuh)

Also Known As: Upavistha Parivritta Urdhva Eka Pada Hastasana
Modification: straight leg lifted, grabbing the foot with the opposite arm, other forearm on the floor
Pose Type: seated, forward bend
Drishti Point: Padhayoragrai or Padayoragre (toes/feet)



One Leg Extended Full Lord of the Fishes Pose

Utthita Eka Pada Paripurna Matsyendrasana

(UT-ti-tuh EY-kuh PUH-duh puh-ri-POOR-nuh muhts-yeyn-DRAHS-uh-nuh)

Pose Type: seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



ONE LEG STRAIGHT, OTHER LEG CROSSED OVER: FOREARM & ELBOW TO THE FLOOR

Revolved Western Intense Stretch Pose Hand to Foot Side Infinity Pose

Parivritta Paschimottana Hasta Pada Parshva Anantasana

(puh-ri-VRIT-tuh puhsh-chi-mo-TAHN-uh HUH-stuh PUH-duh PAHRSH-vuh uh-nuhn-TAHS-uh-nuh)

Also Known As: Revolved Seated Forward Bend Hand to Foot Side Infinity Pose

Pose Type: seated, forward bend, twist

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs), Nasagrai or Nasagre (nose)



Revolved Western Intense Stretch Pose Uneven Arms Upward Side Infinity Pose

Parivritta Paschimottana Vishama Hasta Urdhva Parshva Anantasana

(puh-ri-VRIT-tuh puhsh-chi-mo-TAHN-uh VI-shuh-muh HUH-stuh OORD-vuh PAHRSH-vuh uh-nuhn-TAHS-uh-nuh)

Also Known As: Revolved Seated Forward Bend Uneven Arms Side Infinity Pose

Pose Type: seated, forward bend, twist

Drishti Point: Angushtamadhye or Angustha Ma Dyai (thumbs), Nasagrai or Nasagre (nose)



Revolved Western Intense Stretch Pose Bound Arms Upward Side

Infinity Pose

Parivritta Paschimottana Baddha Hasta Urdhva Parshva Anantasana

(puh-ri-VRIT-tuh puhsh-chi-mo-TAHN-uh BUH-duh HUH-stuh OORD-vuh PAHRSH-vuh uh-nuhn-TAHS-uh-nuh)

Also Known As: Revolved Seated Forward Bend Bound Arms Upward Side Infinity Pose
Modification: arms wrapped around the foot, elbows toward the floor
Pose Type: seated, forward bend, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
● ●



ONE LEG STRAIGHT, OTHER LEG CROSSED OVER: SIDE & BACKBEND

Upward Side Infinity Pose

Urdhva Parshva Anantasana

(OORD-vuh PAHRSH-vuh uh-nuhn-TAHS-uh-nuh)

Modification: top leg crossed over, outside edge of the foot to the floor
1. looking to the side
2. head rolling back
Pose Type: 1. seated, side bend, twist
2. seated, side bend, twist, backbend
Drishti Point: 1. Hastagrai or Hastagre (hands), Padhayoragrai or Padayoragre (toes/feet)
2. Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
1. ● ● ●
2. ● ● ● ●

1.



2.



HALF COW FACE POSE: FORWARD BEND & SIDE BEND

Half Cow Face Western Intense Stretch Pose Prep.

Ardha Gomukha Paschimottanasana Prep.

(UHR-duh GO-muk-uh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: One-Legged Cow Face Western Intense Stretch Pose (Eka Pada Gomukha Paschimottanasana), Half Cow Face Seated Forward Bend
Modification: half forward bend
Pose Type: seated, forward bend
Drishti Point: Padhayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose)



Half Cow Face Western Intense Stretch Pose

Ardha Gomukha Paschimottanasana

(UHR-duh GO-muk-uh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: One-Legged Cow Face Western Intense Stretch Pose (Eka Pada Gomukha Paschimottanasana), Half Cow Face Seated Forward Bend
Modification: 1. grabbing onto the wrist, chin to the knee
2. chin to the knee, arms straight, palms down in front of the foot
Pose Type: seated, forward bend
Drishti Point: Padhayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose)
ल व र य

1.



2.



Revolved Sideways Half Cow Face Western Intense Stretch Pose

Parivritta Parshva Ardha Gomukha Paschimottanasana

(puh-ri-VRIT-tuh PAHRSH-vuh EY-kuh PUH-duh GO-muk-uh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Revolved Sideways One-Legged Cow Face Western Intense Stretch Pose (Parivritta Parshva Eka Pada Gomukha Paschimottanasana), Revolved Sideways Half Cow Face Seated Forward Bend
Modification: top leg straight
Pose Type: seated, forward bend, side bend, twist
Drishti Point: Padhayoragrai or Padayoragre (toes/feet), Hastagrai or Hastagre (hands), Parshva

Drishti (to the right), Parshva Drishti (to the left)



Revolved Hand to Foot Sideways Half Cow Face Western Intense Stretch Pose

Parivritta Hasta Pada Parshva Ardha Gomukha Paschimottanasana

(puh-ri-VRIT-tuh HUH-stuh PUH-duh PAHRSH-vuh UHR-duh GO-muk-uh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Revolved Hand to Foot Sideways One-Legged Cow Face Western Intense Stretch Pose (Parivritta Hasta Pada Parshva Eka Pada Gomukha Paschimottanasana), Revolved Hand to Foot Sideways Half Cow Face Seated Forward Bend
Modification: bottom leg straight, looking up to the sky
Pose Type: seated, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



HALF COW FACE POSE: LEG LIFTED

Upward Half Cow Face Western Intense Stretch Pose

Urdhva Ardha Gomukha Paschimottanasana

(OORD-vuh UHR-duh GO-muk-uh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Upward One-Legged Cow Face Western Intense Stretch Pose (Urdhva Eka Pada Gomukha Paschimottanasana), Upward Half Cow Face Seated Forward Bend
Modification: bottom leg straight, grabbing onto the foot
Pose Type: seated, forward bend, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Urdhva or Antara Drishti (up to the sky)



Upward Half Cow Face Western Intense Stretch Pose

Urdhva Ardha Gomukha Paschimottanasana

(OORD-vuh UHR-duh GO-muk-uh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Upward One-Legged Cow Face Western Intense Stretch Pose (Urdhva Eka Pada Gomukha Paschimottanasana), Upward Half Cow Face Seated Forward Bend
Modification: top leg straight, grabbing onto both feet
Pose Type: seated, forward bend, core
Drishti Point: Padhayoragrai or Padayoragre (toes/feet)



Sundial Pose 2

Surya Yantrasana 2

(SOOR-yuh yuhn-trahn-AHS-uh-nuh)

Pose Type: seated, forward bend

Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व य



Sundial Pose 1

Surya Yantrasana 1

(SOOR-yuh yuhn-trahn-AHS-uh-nuh)

Pose Type: seated, twist

Drishti Point: Urdhva or Antara Drishti (up to the sky)

ल व य ह



Upward Bound Hands Sundial Pose 1

Urdhva Baddha Hasta Surya Yantrasana 1

(OORD-vuh BUH-duh HUH-stuh SOOR-yuh yuhn-trahn-AHS-uh-nuh)

Pose Type: seated, twist, binding

Drishti Point: Urdhva or Antara Drishti (up to the sky)

ल व य



Downward Bound Hands Sundial Pose 1

Adho Baddha Hasta Surya Yantrasana 1

(uh-DO BUH-duh HUH-stuh SOOR-yuh yuhn-trahn-AHS-uh-nuh)

Pose Type: seated, forward bend, binding

Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व



ONE LEG STRAIGHT, ONE LEG BENT: HALF LOTUS & BINDING

Half Bound Lotus Western Intense Stretch Pose Prep.

Ardha Baddha Padma Paschimottanasana Prep.

(UHR-duh BUH-duh PUHD-muh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Half Bound Lotus Seated Forward Bend Prep.
Modification: arm extended to the sky
Pose Type: seated, binding
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Bound Lotus Western Intense Stretch Pose

Ardha Baddha Padma Paschimottanasana

(UHR-duh BUH-duh PUHD-muh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Half Bound Lotus Seated Forward Bend
Modification: 1. half forward bend
2. full forward bend
Pose Type: seated, forward bend, binding
Drishti Point: Padhayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





ONE LEG STRAIGHT, ONE LEG BENT: HALF LOTUS, TWISTS & BINDING

Revolved Half Bound Lotus Western Intense Stretch Pose

Parivritta Ardha Baddha Padma Paschimottanasana

(puh-ri-VRIT-tuh UHR-duh BUH-duh PUHD-muh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Revolved Half Bound Lotus Seated Forward Bend and Half Lord of the Fishes Pose (Ardha Matsyendrasana)
Modification: grabbing onto the big toe
Pose Type: seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
ल व य



Half Lord of The Fishes Pose 2

Ardha Matsyendrasana 2

(UHR-duh muhts-yeyn-DRAHS-uh-nuh)

Also Known As: Sage Warrior Bharadvaja Prep. (Bharadvajasana Prep.)
Modification: 1. looking toward the foot
2. looking over the shoulder
Pose Type: seated, forward bend, twist, binding

Drishti Point: 1. Padhayoragrai or Padayoragre (toes/feet)
2. Parshva Drishti (to the right), Parshva Drishti (to the left)





ONE LEG STRAIGHT, ONE LEG BENT: HALF LOTUS—LEG LIFTED

Half Lotus Extended Hand to Big Toe Pose in Infinity Pose

Ardha Padma Utthita Hasta Padangusthasana in Anantasana

(UHR-duh PUHD-muh UT-ti-tuh HUH-stuh puhd-ahng-goosh-TAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Pose Type: seated, mild backbend

Drishti Point: Urdhva or Antara Drishti (up to the sky), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Lotus Extended Revolved Hand to Foot Pose in Infinity Pose

Ardha Padma Utthita Parivritta Pada Hastasana in Anantasana

(UHR-duh PUHD-muh UT-ti-tuh puh-ri-VRIT-tuh PUH-duh huh-STAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Modification: grabbing onto the foot on the opposite side

Pose Type: seated, mild backbend, forward bend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



ONE LEG STRAIGHT, ONE LEG BENT: HALF LOTUS & BACKBEND—BINDING

Half Lotus Upward Infinity Pose

Ardha Padma Urdhva Anantasana

(UHR-duh PUHD-muh OORD-vuh uhn-uhnt-AHS-uh-nuh)

Pose Type: seated

Drishti Point: Urdhva or Antara Drishti (up to the sky), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Bound Lotus Infinity Pose

Ardha Baddha Padma Anantasana

(UHR-duh BUH-duh PUHD-muh uhn-uhnt-AHS-uh-nuh)

Modification: Arm 1: forearm to the floor
Arm 2: grabbing onto the foot
Pose Type: seated, mild backbend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Bound Lotus Infinity Pose

Ardha Baddha Padma Anantasana

(UHR-duh BUH-duh PUHD-muh uhn-uhnt-AHS-uh-nuh)

Modification: Arm 1: elbow to the floor
Arm 2: hand to the hip socket
Pose Type: seated, mild backbend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ONE LEG STRAIGHT, ONE KNEE BENT TO THE BACK: FORWARD BEND & TWIST

Three Limbed Face to Foot Western Intense Stretch Pose

Trianga Mukhaikapada Paschimottanasana

(tri-UHNG-uh muk-EYE-kuh-puh-duh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Three Limbed Face to Foot Seated Forward Bend
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य



Churning Pose

Chalanasana

(chuh-luh-NAHS-uh-nuh)

Pose Type: seated, forward bend, twist
Drishti Point: Hastagrai or Hastagre (hands)
ल व र य



ONE LEG STRAIGHT, ONE KNEE BENT TO THE BACK: TWIST, SIDE BEND & FORWARD BEND

Revolved Half Bound Half Hero Half Seated Angle Pose

Parivritta Ardha Baddha Ardha Vira Ardha Upavishta Konasana

(puh-ri-VRIT-tuh UHR-duh BUH-duh UHR-duh VEER-uh UHR-duh u-puh-VISH-tuh ko-NAHS-uh-nuh)

Also Known As: Parivritta Ardha Baddha Ardha Vira Ardha Upavistha Konasana
Konasana Modification: spine straight
Pose Type: seated, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Gate Pose

Parighasana

(puh-ri-GAHS-uh-nuh)

Modification: side bend toward the straight leg; grabbing onto the heel of the bent leg with both hands
Pose Type: seated, side bend, forward bend, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Gate Pose

Parighasana

(puh-ri-GAHS-uh-nuh)

Modification: seated: 1. palm to the floor by the ankle, other arm up over the head
2. elbow to the floor by the knee
3. both hands grabbing onto the foot, chest rotated up to the sky
Pose Type: 1 & 2. seated, side bend
3. seated, side bend, twist
Drishti Point: 1. Hastagrai or Hastagre (hands)
2 & 3. Urdhva or Antara Drishti (up to the sky)



2.



3.



Benu Bird Pose 1

Benvasana 1

(ben-VAHS-uh-nuh)

Modification: seated; sitting bone on the heel, forward bend; arms to the side and to the back
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य ह



ONE LEG STRAIGHT, ONE KNEE BENT TO THE BACK: LEG LIFTED—BACKBEND

Reclined Half Hero Extended Hand to Foot Pose

Supta Ardha Vira Utthita Hasta Padasana

(SUP-tuh UHR-duh VEER-uh UT-ti-tuh HUH-stuh PUH-duhs-uh-nuh)

Modification: 1. right side view
2. left side view
Pose Type: seated, mild backbend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व ह ॐ





ONE LEG STRAIGHT, ONE KNEE BENT TO THE BACK: LEG LIFTED

Heron Pose

Krounchasana

(crown-CHAHS-uh-nuh)

Modification: grabbing onto the wrist, toes pointed
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Sundial Pose 3

Surya Yantrasana 3

(SOOR-yuh yuhn-TRAHS-uh-nuh)

Modification: foot turned to the back
Pose Type: seated, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Revolved Heron Pose

Parivritta Krounchasana

(puh-ri-VRIT-tuh crown-CHAHS-uh-nuh)

Also Known As: Revolved Sundial Pose 3 (Parivritta Surya Yantrasana 3)
Pose Type: seated, forward bend, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



GARUDA LEGS: BACKBEND, TWIST, FORWARD BEND & BINDING

Seated Leg Position of the Pose Dedicated to Garuda

Upavishta Pada Garudasana

(u-puh-VISH-tuh PUH-duh guh-ru-DAHS-uh-nuh)

Also Known As: Upavistha Pada Garudasana
Modification: backbend, one hand to the sky
Pose Type: seated, backbend
Drishti Point: Hastagrai or Hastagre (hands)
ल व य



Revolved Hand to Foot Seated Leg Position of the Pose Dedicated to Garuda

Parivritta Hasta Pada Upavishta Pada Garudasana

(puh-ri-VRIT-tuh HUH-stuh PUH-duh u-puh-VISH-tuh PUH-duh guh-ru-DAHS-uh-nuh)

Also Known As: Parivritta Hasta Pada Upavistha Pada Garudasana
Pose Type: seated, forward bend, twist
Drishti Point: Hastagrai or Hastagre (hands)



Seated Leg Position of the Pose Dedicated to Garuda

Upavishta Pada Garudasana

(u-puh-VISH-tuh PUH-duh guh-ru-DAHS-uh-nuh)

Also Known As: Upavistha Pada Garudasana
Modification: forehead to the knee
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Revolved Seated Leg Position of the Pose Dedicated to Garuda

Parivritta Upavishta Pada Garudasana

(puh-ri-VRIT-tuh u-puh-VISH-tuh PUH-duh guh-ru-DAHS-uh-nuh)

Also Known As: Parivritta Upavistha Pada Garudasana
Modification: hands in Anjali Mudra (Hands in Prayer), one arm threaded through the legs
Pose Type: seated, forward bend, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Bound Revolved Seated Leg Position of the Pose Dedicated to Garuda

Baddha Parivritta Upavishta Pada Garudasana

(BUH-duh puh-ri-VRIT-tuh u-puh-VISH-tuh PUH-duh guh-ru-DAHS-uh-nuh)

Also Known As: Baddha Parivritta Upavistha Pada Garudasana
Pose Type: seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



GARUDA LEGS: KNEES TO THE FLOOR ON THE SIDE

Seated Leg Position of the Pose Dedicated to Garuda in Upward Side Infinity Pose

Upavishta Pada Garudasana in Urdhva Parshva Anantasana

(u-puh-VISH-tuh PUH-duh guh-ru-DAHS-uh-nuh in OORD-vuh PAHRSH-vuh uhn-uhnt-AHS-uh-nuh)

Also Known As: Upavistha Pada Garudasana in Urdhva Parshva Anantasana
Modification: one hand to the floor, one arm extended out
Pose Type: seated, side bend
Drishti Point: Hastagrai or Hastagre (hands)



Seated Leg Position of the Pose Dedicated to Garuda in Upward Side Infinity Pose

Upavishta Pada Garudasana in Urdhva Parshva Anantasana

(u-puh-VISH-tuh PUH-duh guh-ru-DAHS-uh-nuh in OORD-vuh PAHRSH-vuh uhn-uhnt-AHS-uh-nuh)

Modification: palms flat on the floor, fingertips pointing away from the heels, backbend
Pose Type: seated, side bend, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BOTH KNEES BENT: ANKLES HOOKED—TWIST & SIDE BEND

Twist Dedicated to Sage Bharadvaja 3

Bharadvajasana 3

(buh-ruhd-vahj-AHS-uh-nuh)

Pose Type: seated, forward bend, twist
Drishti Point: Padhayoragrai or Padayoragre (toes/feet)

Sideways Twist Dedicated to Sage Bharadvaja 3

Parshva Bharadvajasana 3

(PAHRSH-vuh buh-ruhd-vahj-AHS-uh-nuh)

Modification: forearm to the floor
Pose Type: seated, mild backbend, side bend
Drishti Point: Hastagrai or Hastagre (hands)



LEG CRADLE: ONE LEG STRAIGHT

Baby Cradle Pose

Hindolasana

(hin-do-LAHS-uh-nuh)

Also Known As: One Foot Behind the Head Pose A & B Prep. (Eka Pada Shirshasana A & B Prep.)
Modification: leg straight
1. spine straight, front view
2. half forward bend, side view

Pose Type: seated, forward bend

Drishti Point: Nasagrai or Nasagre (nose), Padhayoragrai or Padayoragre (toes/feet), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Baby Cradle Pose

Hindolasana

(hin-do-LAHS-uh-nuh)

Also Known As: One Foot Behind the Head Pose A Prep. (Eka Pada Shirshasana A Prep.)

Modification: leg straight, hands to the face

Pose Type: seated, forward bend

Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



HEAD TO KNEE POSE: FORWARD BEND

Head to Knee Pose Prep.

Janu Shirshasana Prep.

(JAH-nu sheer-SHAHS-uh-nuh)

Modification: palms to the floor by the hips, spine straight
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose), Padhayoragrai or Padayoragre (toes/feet)



Both Hands to Ankle Head to Knee Pose

Dwi Hasta Kulpa Janu Shirshasana

(DWI-huh-stuh KUL-puh JAH-nu sheer-SHAHS-uh-nuh)

Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Padhayoragrai or Padayoragre (toes/feet)



Both Hands to Foot Head to Knee Pose

Dwi Hasta Pada Janu Shirshasana

(DWI-huh-stuh PUH-duh JAH-nu sheer-SHAHS-uh-nuh)

Modification: 1. grabbing onto the foot; fingers interlocked, half forward bend
2. grabbing onto the wrist, half forward bend
Pose Type: seated, forward bend
Drishti Point: Padhayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose)

1.



2.



HEAD TO KNEE POSE: HEEL UP—FORWARD BEND

Head to Knee Pose C Prep.

Janu Shirshasana C Prep.

(JAH-nu sheer-SHAHS-uh-nuh)

Also Known As: Half Root Lock Pose (Ardha Mula Bandhasana)
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose), Padhayoragrai or Padayoragre (toes/feet), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Head to Knee Pose C

Janu Shirshasana C

(JAH-nu sheer-SHAHS-uh-nuh)

Modification: 1. half forward bend
2. full forward bend
Pose Type: seated, forward bend
Drishti Point: Padhayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose)





HEAD TO KNEE POSE: TWISTS

Revolved Half Bound Angle Pose

Parivritta Ardha Baddha Konasana

(puh-ri-VRIT-tuh UHR-duh BUH-duh ko-NAHS-uh-nuh)

Modification: hand to the knee, other hand to the floor behind the hips for support
Pose Type: seated, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Revolved Half Bound Angle Pose

Parivritta Ardha Baddha Konasana

(puh-ri-VRIT-tuh UHR-duh BUH-duh ko-NAHS-uh-nuh)

Pose Type: seated, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Revolved Sideways Half Bound Angle Pose

Parivritta Parshva Ardha Baddha Konasana

(puh-ri-VRIT-tuh PAHRSH-vuh UHR-duh BUH-duh ko-NAHS-uh-nuh)

Modification: grabbing onto the big toe of the bent leg
Pose Type: seated, twist, side bend, binding
Drishti Point: Padhayoragrai or Padayoragre (toes/feet)



Revolved Half Bound Angle Pose

Parivritta Ardha Baddha Konasana

(puh-ri-VRIT-tuh UHR-duh BUH-duh ko-NAHS-uh-nuh)

Modification: looking back Arm 1: grabbing onto the outside edge of the opposite foot
Arm 2: grabbing onto the shin of the opposite leg behind the back
Pose Type: seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



HEAD TO KNEE POSE—SIDE BENDS

Half Bound Angle Pose in Infinity Pose

Ardha Baddha Konasana in Anantasana

(UHR-duh BUH-duh ko-NAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Modification: elbow to the floor, head rolling back
Pose Type: seated, mild backbend, side bend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं वं यं हं ॐ



Revolved Head to Knee Pose Prep.

Parivritta Janu Shirshasana Prep.

(puh-ri-VRIT-tuh JAH-nu sheer-SHAHS-uh-nuh)

Modification: grabbing onto the foot, other hand to the knee
Pose Type: seated, forward bend
Drishti Point: Padhayoragrai or Padayoragre (toes/feet)
लं वं



Sideways Head to Knee Pose

Parshva Janu Shirshasana

(PAHRSH-vuh JAH-nu sheer-SHAHS-uh-nuh)

Also Known As: Sideways Half Bound Angle Pose (Parshva Ardha Baddha Konasana)
Pose Type: seated, side bend
Drishti Point: Hastagrai or Hastagre (hands)



Sideways Head to Knee Pose

Parshva Janu Shirshasana

(PAHRSH-vuh JAH-nu sheer-SHAHS-uh-nuh)

Also Known As: Sideways Half Bound Angle Pose (Parshva Ardha Baddha Konasana)
Modification: elbow to the floor on the inside of the leg, other hand on the hip
Pose Type: seated, forward bend, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)

Half Bound

Half Seated Angle Pose

Ardha Baddha Ardha Upavishta Konasana

(UHR-duh BUH-duh UHR-duh u-puh-VISH-tuh ko-NAHS-uh-nuh)

Also Known As: Ardha Baddha Ardha Upavistha Konasana

Pose Type: seated, side bend, binding

Drishti Point: Nasagrai or Nasagre (nose)

How to Perform the Pose:

1. Begin by sitting on the floor with both your legs straight out in front of you. Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale as you bend your left knee and bring the sole of your left foot toward your right thigh.
3. On the next exhale, bring your right leg out to the right side, keeping it strong and straight by pulling up the kneecap and engaging the thigh muscles (quadriceps). Press your right toes and your right heel to the floor, lifting the right leg slightly on off the floor.
4. Inhale as you expand your chest and hold your arms straight out to the sides, parallel to the floor.
5. Exhale as you bend your left arm and reach your left hand behind the back to the inside of your right thigh to bind.
6. Inhale as you reach your right arm up to the sky. Exhale as you bend your right elbow and look toward your left knee.
7. Hold the pose for at least 30, and up to 90, seconds in order to receive full benefits of the stretch.
8. Inhale as you release the bind. Exhale as you bring both your legs straight out in front of you. Repeat on the other side.

Modification: side bend toward the bent knee

ardha = half

baddha = bound

ardha = half

upavishta = seated

kona = angle

Half Bound Sideways Head to Knee Pose

Ardha Baddha Parshva Janu Shirshasana

(UHR-duh BUH-duh PAHRSH-vuh JAH-nu sheer-SHAHS-uh-nuh)

Also Known As: Sideways Half Bound Angle Pose (Parshva Ardha Baddha Konasana)
Modification: 1. toes pointed
2. toes flexed in
Pose Type: seated, forward bend, side bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व





Revolved Head to Knee Pose

Parivritta Janu Shirshasana

(puh-ri-VRIT-tuh JAH-nu sheer-SHAHS-uh-nuh)

Modification: elbow to the floor
1. forearm to the floor, chest to the side
2. head on the knee, chest to the sky
Pose Type: seated, side bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व र य


1.


2.

Both Hands to the Head Sideways Head to Knee Pose

Dwi Hasta Shirsha Parshva Janu Shirshasana

(DWI-huh-stuh SHEER-shuh PAHRSH-vuh JAH-nu sheer-SHAHS-uh-nuh)

Also Known As: Sideways Half Bound Angle Pose (Parshva Ardha Baddha Konasana)
Modification: 1. slight side bend
2. elbow to the knee
3. elbow to the floor
Pose Type: seated, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)


1.

2.



3.



HEAD TO KNEE POSE: LEG LIFTED

Hands Free Sundial Pose 1

Mukta Hasta Surya Yantrasana 1

(MUK-tuh HUH-stuh SOOR-yuh yuhn-TRAHS-uh-nuh)

Modification: foot to thigh, fingertips of both hands to the floor
Pose Type: seated, forward bend, side bend, core
Drishti Point: Hastagrai or Hastagre (hands)



Sundial Pose 1

Surya Yantrasana 1

(SOOR-yuh yuhn-TRAHS-uh-nuh)

Modification: foot to thigh, grabbing onto the foot on the same side
Pose Type: seated, forward bend, side bend
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
ल व



Unsupported Seated Revolved Upward One Hand to Foot Pose

Niralamba Upavishta Parivritta Urdhva Eka Pada Hastasana

(nir-AH-luhm-buh u-puh-VISH-tuh puh-ri-VRIT-tuh OORD-vuh EY-kuh PUH-duh huh-STAHS-uh-nuh)

Pose Type: seated, forward bend, twist, core
Drishti Point: Hastagrai or Hastagre (hands)
ल व र



HERO POSE: TOES CURLED IN

Tip Toe Hero Pose

Prapada Virasana

(PRUH-puh-duh veer-AHS-uh-nuh)

Also Known As: Thunderbolt Pose (Vajrasana)
Modification: toes curled in, hands in Anjali Mudra (Hands in Prayer)
Pose Type: seated
Drishti Point: Hastagrai or Hastagre (hands) or Nasagrai or Nasagre (nose)
🔴



Tip Toe Hero Pose

Prapada Virasana

(PRUH-puh-duh veer-AHS-uh-nuh)

Also Known As: Thunderbolt Pose (Vajrasana)
Modification: head down, arms open wide
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
🔴 🟢



HERO POSE: SITTING ON THE HEELS

Hero Pose

Virasana

(veer-AHS-uh-nuh)

Also Known As: Thunderbolt Pose (Vajrasana)

Modification: arms to the sides; modified version for tight ankles

Pose Type: seated

Drishti Point: Nasagrai or Nasagre (nose)



HERO POSE: SITTING ON THE HEELS—HANDS ON THE KNEES

Hero Pose

Virasana

(veer-AHS-uh-nuh)

Also Known As: Thunderbolt Pose (Vajrasana)

Modification: hands on the knees, palms up

Pose Type: seated

Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Lion Pose Dedicated to an Avatar of Lord Vishnu in Hero Pose

Narasimhasana in Virasana

(nuh-ruh-sim-HAHS-uh-nuh in veer-AHS-uh-nuh)

Also Known As: Lion Pose in Thunderbolt Pose (Simhasana in Vajrasana)
Modification: sitting on the heels
1. Cat Tilt
2. Dog Tilt
Pose Type: seated
1. forward bend
2. mild backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
● ● ●





HERO POSE: SITTING ON THE HEELS—ARMS UP & FORWARD BEND

Hero Pose—Raised Bound Hands

Virasana Urdhva Baddha Hastasana

(veer-AHS-uh-nuh OORD-vuh BUH-duh huh-STAHS-uh-nuh)

Also Known As: Thunderbolt Pose Raised Bound Hands (Vajrasana Urdhva Baddha Hastasana)

Modification: palms facing up
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose)



Hero Pose

Virasana

(veer-AHS-uh-nuh)

Also Known As: Thunderbolt Pose (Vajrasana)
Modification: forward bending, ankles crossed, palms to the floor by the knees
Pose Type: seated, forward bend
Drishti Point: Angushtamadhye or Angustha Ma Dyai (thumbs), Nasagrai or Nasagre (nose)



Hand Position of the Pose Dedicated to Garuda in Hero Pose

Hasta Garudasana in Virasana

(HUH-stuh guh-ru-DAHS-uh-nuh in veer-AHS-uh-nuh)

Also Known As: Hand Position of the Pose Dedicated to Garuda in Thunderbolt Pose (Hasta Garudasana in Vajrasana)
Modification: 1. half forward bend

2. spine straight

Pose Type: 1. seated, forward bend

2. seated

Drishti Point: Angushtamadhye or Angustha Ma Dyai (thumbs)

1. लं रं हं

2. लं





HERO POSE: SITTING ON THE HEELS—KNEES OFF THE FLOOR

Hero Scale Pose with Hands in Prayer

Vira Tolasana Namaskar

(VEER-uh to-LAHS-uh-nuh nuh-muhs-KAHR)

Modification: hands in Anjali Mudra (Hands in Prayer)

Pose Type: seated, balance, core

Drishti Point: Nasagrai or Nasagre (nose) or Hastagrai or Hastagre (hands)

लं



Hero Scale Pose

Vira Tolasana

(VEER-uh to-LAHS-uh-nuh)

Modification: grabbing onto the knees, Cat Tilt
Pose Type: seated, balance, core
Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)



THUNDERBOLT POSE: SITTING BONES ON THE FLOOR—VARIOUS ARM POSITIONS

Hero Pose

Virasana

(veer-AHS-uh-nuh)

Also Known As: Thunderbolt Pose (Vajrasana)
Modification: sitting bones to the floor
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose)



Both Hands to Feet Hero Pose

Dwi Hasta Pada Virasana

(DWI-huh-stuh PUH-duh veer-AHS-uh-nuh)

Also Known As: Both Hands to Feet Thunderbolt Pose (Dwi Hasta Pada Vajrasana)
Modification: sitting bones to the floor, arms crossed behind the back
1. back view
2. front view, mild backbend
Pose Type: 1. seated, binding
2. seated, mild backbend, binding
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



1.



2.

One Arm Upward Hero Pose

Eka Urdhva Hasta Virasana

(EY-kuh OORD-vuh HUH-stuh veer-AHS-uh-nuh)

Also Known As: One Arm Upward Thunderbolt Pose (Eka Urdhva Hasta Vajrasana)
Pose Type: seated
Drishti Point: Hastagrai or Hastagre (hands)



Hero Pose—Raised Bound Hands

Virasana Urdhva Baddha Hastasana

(veer-AHS-uh-nuh OORD-vuh BUH-duh huh-STAHS-uh-nuh)

Also Known As: Thunderbolt Pose Raised Bound Hands (Vajrasana Urdhva Baddha Hastasana)
Modification: palms facing up
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose)



Revolved Hero Pose

Parivritta Virasana

(puh-ri-VRIT-tuh veer-AHS-uh-nuh)

Also Known As: Revolved Thunderbolt Pose (Parivritta Vajrasana)
Pose Type: seated, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
●



Pose Dedicated to Sage Bharadvaja 1

Bharadvajasana 1

(buh-ruhd-vuhj-AHS-uh-nuh)

Modification: ankles crossed, grabbing onto the bicep
Pose Type: seated, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
● ●



Sideways Pose Dedicated to Sage Bharadvaja 1

Parshva Bharadvajasana 1

(PAHRSH-vuh buh-ruhd-vuhj-AHS-uh-nuh)

Modification: one arm crossed in front; other arm over the head, elbow bent

Pose Type: seated, side bend

Drishti Point: Hastagrai or Hastagre (hands)

🔴



Pose Dedicated to Bharadvaja 1

Bharadvajasana 1

(buh-ruhd-vuhj-AHS-uh-nuh)

Modification: 1. grabbing onto the inside of the hip with opposite hand, other hand on the knee, looking over the shoulder

2. grabbing onto the tricep of the opposite arm, looking over the shoulder

Pose Type: seated, twist, binding

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)

🔴 🟢





2.

THUNDERBOLT POSE: SITTING BONES ON THE FLOOR—KNEES OPEN WIDE

Lion Pose Dedicated to an Avatar of Lord Vishnu in Knees Spread Wide Hero Pose

Narasimhasana in Prasarita Janu Virasana

(nuh-ruh-sim-HAHS-uh-nuh in pruh-SAH-ri-tuh JAH-nu veer-AHS-uh-nuh)

Also Known As: Lion Pose (Simhasana)
Modification: sitting bones on the floor
Pose Type: seated, mild backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



Knees Spread Wide Hero Pose

Prasarita Janu Virasana

(pruh-SAH-ri-tuh JAH-nu veer-AHS-uh-nuh)

Also Known As: Frog Pose (Mandukasana)
Modification: sitting bones off the floor
Pose Type: seated

Drishti Point: Nasagrai or Nasagre (nose)



Half Bound Revolved Knees Spread Wide Hero Pose

Ardha Baddha Parivritta Prasarita Janu Virasana

(UHR-duh BUH-duh puh-ri-VRIT-tuh pruh-SAH-ri-tuh JAH-nu veer-AHS-uh-nuh)

Pose Type: seated, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



THUNDERBOLT POSE: SITTING BONES ON THE FLOOR—FEET TURNED OUT

Complete Thunderbolt Pose

Paripurna Vajrasana

(puh-ri-POOR-nuh vuhj-RAHS-uh-nuh)

Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose)



Revolved Complete Thunderbolt Pose

Parivritta Paripurna Vajrasana

(puh-ri-VRIT-uh puh-ri-POOR-nuh vuhj-RAHS-uh-nuh)

Pose Type: seated, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Western Intense Stretch Pose in Complete Thunderbolt Pose

Paschimottanasana in Paripurna Vajrasana

(puhsh-chi-mo-tahn-AHS-uh-nuh in puh-ri-POOR-nuh vuhj-RAHS-uh-nuh)

Also Known As: Seated Forward Bend in Complete Thunderbolt Pose
Modification: forward bend, toes turned out
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)

Half Pose Dedicated to Sage Marichi in Revolved Half Thunderbolt Pose

Ardha Marichyasana in Parivritta Ardha Vajrasana

(UHR-duh muh-ree-CHYAHS-uh-nuh in puh-ri-VRIT-uh UHR-duh vuhj-RAHS-uh-nuh)

Modification: 1. looking straight ahead
2. looking over the shoulder
Pose Type: seated, forward bend, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)





Half Bound Pose Dedicated to Sage Marichi in Half Thunderbolt Pose

Ardha Baddha Marichyasana in Ardha Vajrasana

(UHR-duh BUH-duh muh-ree-CHYAHS-uh-nuh in UHR-duh vuhj-RAHS-uh-nuh)

Pose Type: seated, forward bend, twist, binding

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)

● ●



THUNDERBOLT POSE: SITTING BONES ON THE FLOOR—FEET TURNED OUT—ARMS UP OVER THE HEAD

Complete Thunderbolt Pose—Raised Bound Hands

Paripurna Vajrasana—Urdhva Baddha Hastasana

(puh-ri-POOR-nuh vuhj-RAHS-uh-nuh OORD-vuh BUH-duh huh-STAHS-uh-nuh)

Modification: 1. looking straight ahead
2. head rolling back

Pose Type: 1. seated
2. seated, mild backbend

Drishti Point: 1. Nasagrai or Nasagre (nose)
2. Angushtamadhye (thumbs)

1. ●
2. ● ● ●



1.



Revolved Complete Thunderbolt Pose—Raised Bound Hands

Parivritta Paripurna Vajrasana—Urdhva Baddha Hastasana

(puh-ri-VRIT-tuh puh-ri-POOR-nuh vuhj-RAHS-uh-nuh OORD-vuh BUH-duh huh-STAHS-uh-nuh)

Pose Type: seated, twist

Drishti Point: Angushtamadhye (thumbs)



Sideways Complete Thunderbolt Pose—Raised Bound Hands

Parshva Paripurna Vajrasana—Urdhva Baddha Hastasana

(PAHRSH-vuh puh-ri-POOR-nuh vuhj-RAHS-uh-nuh OORD-vuh BUH-duh huh-STAHS-uh-nuh)

Pose Type: seated, side bend

Drishti Point: Angushtamadhye (thumbs)



One Hand Sideways Complete Thunderbolt Pose

Eka Hasta Parshva Paripurna Vajrasana

(EY-kuh HUH-stuh PAHRSH-vuh puh-ri-POOR-nuh vuhj-RAHS-uh-nuh)

Pose Type: seated, side bend
Drishti Point: Hastagrai or Hastagre (hands)



THUNDERBOLT POSE: SITTING BONES ON THE FLOOR—FEET TURNED OUT—ONE-LEGGED & FORWARD BENDS

Half Pose Dedicated to Sage Marichi in Half Thunderbolt Pose

Ardha Marichyasana in Ardha Vajrasana

(UHR-duh muh-ree-CHYAHS-uh-nuh in UHR-duh vuhj-RAHS-uh-nuh)

Modification: grabbing onto the knee with both hands
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Half Pose Dedicated to Sage Marichi in Half Thunderbolt Pose

Ardha Marichyasana in Ardha Vajrasana

(UHR-duh muh-ree-CHYAHS-uh-nuh in UHR-duh vuhj-RAHS-uh-nuh)

Modification: palms to the floor in front of the hips
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

लं वं



Half Star Pose in Half Frog Pose

Ardha Tarasana in Ardha Mandukasana

(UHR-duh tahr-AHS-uh-nuh in UHR-duh muhn-doo-KAHS-uh-nuh)

Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)

लं वं हं



Pose Dedicated to Virancha (Brahma) 1 Prep.

Viranchyasana 1 Prep.

(vir-uhn-CHYAHS-uh-nuh)

Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



ONE KNEE BENT TO THE BACK: OTHER FOOT TO THE THIGH—SPINE STRAIGHT, TWIST & SIDE BEND

Easy Pose Dedicated to Sage Bharadvaja 2 Prep.

Sukha Bharadvajasana 2 Prep.

(SUK-uh buh-ruhd-vuhj-AHS-uh-nuh)

Modification: neutral spine, back of the hands on the knees
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose)



Easy Pose Dedicated to Sage Bharadvaja 2

Sukha Bharadvajasana 2

(SUK-uh buh-ruhd-vuhj-AHS-uh-nuh)

Modification: foot to the inside of the thigh
Pose Type: seated, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
ल व



Sideways Easy Pose Dedicated to Sage Bharadvaja 2

Parshva Sukha Bharadvajasana 2

(PAHRSH-vuh SUK-uh buh-ruhd-vuhj-AHS-uh-nuh)

Modification: foot to the inside of the thigh, side bend
Pose Type: seated, side bend
Drishti Point: Hastagrai or Hastagre (hands)
ल व



ONE KNEE BENT TO THE BACK: OTHER FOOT TO THE THIGH—SIDE BEND

Easy One-Legged King Pigeon Pose 1

Sukha Eka Pada Raja Kapotasana 1

(SUK-uh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Pose Type: seated, side bend
Drishti Point: Hastagrai or Hastagre (hands)
ल व य ह



Sideways Half Hero Half Bound Angle Pose

Parshva Ardha Vira Ardha Baddha Konasana

(PAHRSH-vuh UHR-duh VEER-uh UHR-duh BUH-duh ko-NAHS-uh-nuh)

Modification: forearm to the floor
Pose Type: seated, side bend
Drishti Point: Hastagrai or Hastagre (hands)
ल व

Half Hero Half Bound Angle Pose

Ardha Vira Ardha Baddha Konasana

(UHR-duh VEER-uh UHR-duh BUH-duh ko-NAHS-uh-nuh)

Modification: arm behind the back, hand to the hip; backbend
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Twist Dedicated to Sage Bharadvaja 2

Bharadvajasana 2

(buh-ruhd-vuhj-AHS-uh-nuh)

Pose Type: seated, twist, binding

Drishti Point: Parsva Drishti (to the right), Parsva Drishti (to the left)

How to Perform the Pose:

1. Begin by sitting on the floor with both your legs straight out in front of you. Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Inhale as you lean over to the left side, bending your right knee and bringing your right knee, shin, and ankle to the floor. Your right heel should be close to your right hip to protect the knee and your right knee should be open slightly to the side.
3. Exhale as you bend your left knee and bring your left foot to your right hip socket in the Half Lotus (*Ardha Padmasana*), rotating the sole of your left foot up to the sky. Try to keep both knees on the floor.
4. Inhale as you expand your chest and hold your arms straight out to the sides, parallel to the floor.
5. Exhale as you twist to the left, bringing your left arm behind your back and grabbing your left foot with your left hand to bind. Grab onto the left knee with your right hand and look over your left shoulder (Pose #2).
6. Inhale as you lengthen your spine. Exhale as you bring the back of your left hand under your right knee (Pose #1). On the next exhale, look over your right shoulder to deepen the twist (Pose #3).
7. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch.
8. Inhale as you release the bind and look forward. Exhale as you bring both your legs straight out in front of you. Repeat on the other side.

Modification:

1. palm under the knee, twisting to the inside of the body
2. hand on the knee, twisting to the inside of the body
3. palm under the knee, twisting to the outside of the body

Bharadvaja = Pindola Bharadvaja was one of four Arhats asked by Buddha to stay on earth to propagate Buddhist law or Dharma

1.



2.



3.



Half Fire Log Pose in Half Bound Hero Pose

Ardha Agnistambhasana in Ardha Baddha Virasana

(UHR-duh uhg-ni-stuhm-BAHS-uh-nuh in UHR-duh BUH-duh veer-AHS-uh-nuh)

Modification: 1. grabbing onto the hip
2. grabbing onto the heel
Pose Type: seated, binding
Drishti Point: Nasagrai or Nasagre (nose), Hastagrai or Hastagre (hands)





Pose Dedicated to Sage Bharadvaja 2 Prep.

Bharadvajasana 2 Prep.

(buh-ruhd-vuhj-AHS-uh-nuh)

Modification: palms together, heels of the palms resting on the crown of the head, neutral spine
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Pose Dedicated to Sage Bharadvaja 2 Prep.

Bharadvajasana 2 Prep.

(buh-ruhd-vuhj-AHS-uh-nuh)

Also Known As: Root Lock Pose (Mula Bandhasana)
Modification: sitting on the heel, both hands grabbing onto the foot, neutral spine
Pose Type: seated, binding
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



ONE KNEE BENT TO THE BACK: KNEE TO THE CHEST, BINDING, TWIST & BACKBEND

Pose Dedicated to Sage Marichi 5 & 6 Prep.

Marichyasana 5 & 6 Prep.

(muh-ree-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi E & F Prep. (Marichyasana E & F Prep.)
Modification: spine straight
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Pose Dedicated to Sage Marichi 5

Marichyasana 5

(muh-ree-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi E (Marichyasana E)
Pose Type: seated, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)



Pose Dedicated to Sage Marichi 6

Marichyasana 6

(muh-ree-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Sage Marichi F (Marichyasana F)
Pose Type: seated, forward bend, twist, binding
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



One-Legged King Pigeon Pose 3

Eka Pada Raja Kapotasana 3

(EY-kuh PUH-duh RAHJ-uh kuh-po-TAHS-uh-nuh)

Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



LEG CRADLE & FOOT TO THE KNEE

Baby Cradle Pose in Half Hero Pose

Hindolasana in Ardha Virasana

(hin-do-LAHS-uh-nuh in UHR-duh veer-AHS-uh-nuh)

Also Known As: Baby Cradle Pose in Half Thunderbolt Pose (Hindolasana in Ardha Vajrasana)
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Baby Cradle Pose Prep.

Hindolasana Prep.

(hin-do-LAHS-uh-nuh)

Modification: palms to the floor behind the hips, heel of the bottom foot to the sitting bone
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Half Fire Log Pose in Half Yogic Staff Pose Prep.

Ardha Agnistambhasana in Ardha Yogadandasana Prep.

(UHR-duh uhg-ni-stuhm-BAHS-uh-nuh in UHR-duh yo-guh-duhn-DAHS-uh-nuh)

Pose Type: seated, forward bend, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Yogic Staff Pose Prep.

Yogadandasana Prep.

(yo-guh-duhn-DAHS-uh-nuh)

Modification: grabbing onto the foot with one hand
Pose Type: seated, forward bend
Drishti Point: Hastagrai or Hastagre (hands)
ल व



Yogic Staff Pose Prep.

Yogadandasana Prep.

(yo-guh-duhn-DAHS-uh-nuh)

Modification: grabbing onto the foot with both hands, foot to the chest
Pose Type: seated, forward bend
Drishti Point: Padhayoragrai or Padayoragre (toes/feet)
ल व य



LEG CRADLE: FOOT TO THE HIP & HALF LOTUS

Baby Cradle Pose Prep.

Hindolasana Prep.

(hin-do-LAHS-uh-nuh)

Modification: both hands grabbing onto the foot, fingers interlocked
Pose Type: seated, forward bend
Drishti Point: Padhayoragrai or Padayoragre (toes/feet)



Baby Cradle Pose

Hindolasana

(hin-do-LAHS-uh-nuh)

Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Four Corner Pose

Chatushkonasana

(chuh-tush-ko-NAHS-uh-nuh)

Pose Type: seated, forward bend, binding
Drishti Point: Nasagrai or Nasagre (nose)
ल व



Half Lotus Baby Cradle Pose

Ardha Padma Hindolasana

(UHR-duh PUHD-muh hin-do-LAHS-uh-nuh)

Also Known As: Pose Dedicated to Virancha (Brahma) 1 or A Prep. (Viranchyasana 1 or A Prep.)
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व



FOOT TO THE ARMPIT: BOTH KNEES BENT

Yogic Staff Pose with Hands in Prayer

Yogadandasana Namaskar

(yo-guh-duhn-DAHS-uh-nuh nuh-muhs-KAHR)

Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Hastagrai or Hastagre (hands)
● ●



Yogic Staff Pose

Yogadandasana

(yo-guh-duhn-DAHS-uh-nuh)

Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Hastagrai or Hastagre (hands)
● ●



Half Bound Fire Log Pose in Half Yogic Staff Pose Prep.

Ardha Baddha Agnistambhasana in Ardha Yogadandasana Prep.

(UHR-duh BUH-duh uhg-ni-stuhm-BAHS-uh-nuh in UHR-duh yo-guh-duhn-DAHS-uh-nuh)

Pose Type: seated, forward bend, twist, binding

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Bound Fire Log Pose in Half Yogic Staff Pose Prep.

Baddha Agnistambhasana in Ardha Yogadandasana Prep.

(BUH-duh uhg-ni-stuhm-BAHS-uh-nuh in UHR-duh yo-guh-duhn-DAHS-uh-nuh)

Pose Type: seated, forward bend, twist, binding

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Hands Bound Half Lotus Pose in Half Yogic Staff Pose Prep.

Baddha Hasta Ardha Padmasana in Ardha Yogadandasana Prep.

(BUH-duh HUH-stuh UHR-duh puhd-MAHS-uh-nuh in UHR-duh yo-guh-duhn-DAHS-uh-nuh)

Pose Type: seated, twist, binding

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)

ल व



Hands Bound Half Hero Pose in Half Yogic Staff Pose Prep.

Baddha Hasta Ardha Virasana in Ardha Yogadandasana Prep.

(BUH-duh HUH-stuh UHR-duh veer-AHS-uh-nuh in UHR-duh yo-guh-duhn-DAHS-uh-nuh)

Pose Type: seated, twist, binding

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)

ल व



ONE LEG OVER THE SHOULDER: BOTH KNEES BENT

Sundial Pose 2 Prep.

Surya Yantrasana 2 Prep.

(SOOR-yuh yuhn-TRAHS-uh-nuh)

Modification: shoulder to the back of the knee, knee bent
Pose Type: seated, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



FOOT BEHIND THE HEAD

Pose Dedicated to Virancha (Brahma) 1

Viranchyasana 1

(vir-uhn-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Virancha (Brahma) A (Viranchyasana A)
Pose Type: seated, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Seated Moonbird Pose

Upavishta Chakorasana

(u-puh-VISH-tuh chuh-kor-AHS-uh-nuh)

Also Known As: Upavistha Chakorasana
Pose Type: seated, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One Foot Behind the Head Pose

Eka Pada Shirshasana

(EY-kuh PUH-duh sheer-SHAHS-uh-nuh)

Modification: palms on the floor by the hips, knee bent toward the chest
Pose Type: seated, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Pose Dedicated to Virancha (Brahma) 1

Viranchyasana 1

(vir-uhn-CHYAHS-uh-nuh)

Also Known As: Pose Dedicated to Virancha (Brahma) A (Viranchyasana A)
Modification: hands in Anjali Mudra (Hands in Prayer)
Pose Type: seated
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



COW FACE POSE: SPINE STRAIGHT

Leg Position of Cow Face Pose

Pada Gomukhasana

(PUH-duh go-muk-AHS-uh-nuh)

Modification: hands on the top knee, one palm on top of the other
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose)

Ganesh Seal in Leg Position of Cow Face Pose

Ganesh Mudra in Pada Gomukhasana

(guh-NEYSH MU-druh in PUH-duh go-muk-AHS-uh-nuh)

Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose)



Both Hands to Feet Leg Position of Cow Face Pose

Dwi Hasta Pada Gomukhasana

(DWI-huh-stuh PUH-duh go-mu-KAHS-uh-nuh)

Modification: arms crossed behind the back, grabbing onto the feet
1. back view
2. front view
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Cow Face Pose

Gomukhasana

(go-mu-KAHS-uh-nuh)

Pose Type: seated

Drishti Point: Nasagrai or Nasagre (nose)



Leg Position of Cow Face Pose

Pada Gomukhasana

(PUH-duh go-mu-KAHS-uh-nuh)

Modification: elbows touching behind the head
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose)
ल व ह



COW FACE POSE: FORWARD BEND

Leg Position of Cow Face Pose

Pada Gomukhasana

(PUH-duh go-mu-KAHS-uh-nuh)

Modification: hands in Anjali Mudra (Hands in Prayer), thumbs to third eye; elbows together
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose) or Angushtamadhye or Angustha Ma Dyai (thumbs)
ल व ॐ



Western Intense Stretch Pose in Leg Position of Cow Face Pose

Paschimottanasana in Pada Gomukhasana

(puhsh-chi-mo-TAHS-uh-nuh in PUH-duh go-mu-KAHS-uh-nuh)

Also Known As: Seated Forward Bend in Leg Position of Cow Face Pose and Long Horn Pose

(Dighasrngasana)
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य



Hand Position of the Pose Dedicated to Garuda in Leg Position of Cow Face Pose

Hasta Garudasana in Pada Gomukhasana

(HUH-stuh guh-ru-DAHS-uh-nuh in PUH-duh go-mu-KAHS-uh-nuh)
Modification: forward bend
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



COW FACE POSE: SIDE BEND

Sideways Leg Position of Cow Face Pose

Parshva Pada Gomukhasana

(PAHRSH-vuh PUH-duh go-mu-KAHS-uh-nuh)

Pose Type: seated, side bend

Drishti Point: Hastagrai or Hastagre (hands)



Hand to Foot Sideways Leg Position of Cow Face Pose

Hasta Pada Parshva Pada Gomukhasana

(HUH-stuh PUH-duh PAHRSH-vuh PUH-duh go-mu-KAHS-uh-nuh)

Pose Type: seated, side bend

Drishti Point: Hastagrai or Hastagre (hands)



Sideways Leg Position of Cow Face Pose

Parshva Pada Gomukhasana

(PAHRSH-vuh PUH-duh go-mu-KAHS-uh-nuh)

Modification: intense shoulder stretch

Pose Type: seated, side bend

Drishti Point: Urdhva or Antara Drishti (up to the sky)



Hand to Foot Revolved Leg Position of Cow Face Pose

Hasta Pada Parivritta Pada Gomukhasana

(HUH-stuh PUH-duh puh-ri-VRIT-tuh PUH-duh go-mu-KAHS-uh-nuh)

Modification: grabbing onto the big toe, arm behind the back; other arm in front of the body, hand on the hip
Pose Type: seated, twist, binding
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



COW FACE POSE: KNEES LIFTED TO THE CHEST

Upward Leg Position of Cow Face Pose

Urdhva Pada Gomukhasana

(OORD-vuh PUH-duh go-mu-KAHS-uh-nuh)

Modification: arms under the legs, knees lifted to the chest
Pose Type: seated, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Hastagrai or Hastagre (hands)

ल व र य



Upward Hands Upward Leg Position of Cow Face Pose

Urdhva Hasta Urdhva Pada Gomukhasana

(OORD-vuh HUH-stuh OORD-vuh PUH-duh go-mu-KAHS-uh-nuh)

Pose Type: seated, forward bend, core
Drishti Point: Hastagrai or Hastagre (hands), Nasagrai or Nasagre (nose)

ल व र य



Both Hands to Feet Upward Leg Position of Cow Face Pose

Dwi Hasta Pada Urdhva Pada Gomukhasana

(DWI-huh-stuh PUH-duh OORD-vuh PUH-duh go-mu-KAHS-uh-nuh)

Modification: grabbing the outside edges of both feet
Pose Type: seated, forward bend, core
Drishti Point: Nasagrai or Nasagre (nose)

ल व र य

COW FACE POSE: ELBOW & FOREARM ON THE FLOOR

Half Bound Sideways Easy Leg Position of Cow Face Pose

Ardha Baddha Parshva Sukha Pada Gomukhasana

(UHR-duh BUH-duh PAHRSH-vuh SUK-uh PUH-duh go-mu-KAHS-uh-nuh)

Modification: forearm to the floor, sitting on the bottom heel
1. front view
2. back view
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Half Bound Sideways Easy Leg Position of Cow Face Pose

Ardha Baddha Parshva Sukha Pada Gomukhasana

(UHR-duh BUH-duh PAHRSH-vuh SUK-uh PUH-duh go-mu-KAHS-uh-nuh)

Modification: elbow to the floor
Pose Type: seated, backbend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



SAGE VAMADEVA’S POSE: LEANING TO THE SIDE

Pose Dedicated to Sage Vamadeva Prep.

Vamadevasana Prep.

(vahm-uh-dey-VAHS-uh-nuh)

Modification: 1. palm flat on the floor, chest rotating up
2. one arm crossed over in front, hand grabbing onto the back foot; top hand to the head
Pose Type: seated, side bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)


1.


2.

Pose Dedicated to Sage Vamadeva

Vamadevasana

(vahm-uh-dey-VAHS-uh-nuh)

Modification: binding:
1. hand to the hip socket
2. hand to the knee
Pose Type: seated, side bend, twist, binding
Drishti Point: 1. Urdhva or Antara Drishti (up to the sky)
2. Padayoragrai or Padayoragre (toes/feet)
ल व ह


1.


2.

Revolved One-Legged King Pigeon Pose 1 Prep.

Parivritta Eka Pada Raja Kapotasana 1 Prep.

(puh-ri-VRIT-tuh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: grabbing onto the back foot
1. one arm crossed over, other arm to the side, elbow bent
2. arms crossed in front of the body, free hand to the opposite knee
Pose Type: seated, side bend, twist
Drishti Point: Hastagrai or Hastagre (hands), Parshva Drishti (to the right), Parshva Drishti (to the left)





Pose Dedicated to Sage Vamadeva 2

Vamadevasana 2

(vahm-uh-dey-VAHS-uh-nuh)

Pose Type: seated, twist
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



ONE-LEGGED KING PIGEON: HIPS OFF THE FLOOR

One-Legged King Pigeon Pose 1 Version B

Eka Pada Raja Kapotasana 1 B

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Pose Type: standing (on the knees), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Easy One-Legged King Pigeon Pose 1

Sukha Eka Pada Raja Kapotasana 1

(SUK-uh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: hips lifted off the floor, grabbing onto the foot on the opposite side with overhead grip
1. free arm extended to the front
2. free hand to the floor by the opposite knee
Pose Type: standing (on the knees), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Easy One-Legged King Pigeon Pose 1

Sukha Eka Pada Raja Kapotasana 1

(SUK-uh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: hips off the floor; fingertips to the floor by the hips, foot touching the head
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



ONE-LEGGED KING PIGEON: UNDER-HEAD GRIP

One-Legged King Pigeon Pose 1 Prep.

Eka Pada Raja Kapotasana 1 Prep.

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: 1. back knee bent
2. grabbing onto the back foot with one arm on the same side
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

1.



2.



One-Legged King Pigeon Pose 1

Eka Pada Raja Kapotasana 1

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: one hand on the front knee on the same side, other hand pressing the back foot toward the hip
Pose Type: seated, backbend
Drishti Point: Nasagrai or Nasagre (nose), Hastagrai or Hastagre (hands)



One-Legged King Pigeon Pose 1

Eka Pada Raja Kapotasana 1

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: one hand on the back knee, one hand on the front knee; foot to the back of the head
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



One-Legged King Pigeon Pose 1

Eka Pada Raja Kapotasana 1

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: foot to the opposite armpit
Pose Type: seated, backbend, twist
Drishti Point: Nasagrai or Nasagre (nose) or Hastagrai or Hastagre (hands)
ल व र य



Revolved One-Legged King Pigeon Pose 1

Parivritta Eka Pada Raja Kapotasana 1

(puh-ri-VRIT-tuh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: foot to the armpit on the same side
Pose Type: seated, backbend, twist
Drishti Point: Hastagrai or Hastagre (hands)
लं वं रं यं



Revolved One-Legged King Pigeon Pose 1

Parivritta Eka Pada Raja Kapotasana 1

(puh-ri-VRIT-tuh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: foot under the chin
Pose Type: seated, backbend, twist
Drishti Point: Hastagrai or Hastagre (hands)
लं वं रं यं हं



Pose of the Heavenly Spirits Prep.

Valakhilyasana Prep.

(vah-luh-kil-YAHS-uh-nuh)

Modification: under-head grip
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



ONE-LEGGED KING PIGEON: OVERHEAD GRIP

One-Legged King Pigeon Pose 1

Eka Pada Raja Kapotasana 1

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: grabbing onto the foot with one hand on the same side, overhead grip; other hand resting on the front knee
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged King Pigeon Pose 1

Eka Pada Raja Kapotasana 1

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: grabbing onto the foot with both hands, overhead grip; heel of the back foot to the forehead

Pose Type: seated, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

लं वं रं यं हं ॐ



ONE-LEGGED KING PIGEON: ASYMMETRICAL ARMS—CROSS OVER & UNDER-HEAD/OVERHEAD GRIP

One Hand to Foot Bound One-Legged King Pigeon Pose 1

Eka Hasta Pada Baddha Eka Pada Raja Kapotasana 1

(EY-kuh HUH-stuh PUH-duh BUH-duh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: arm crossed over in front of the neck, other hand on the knee

Pose Type: seated, backbend

Drishti Point: Nasagrai or Nasagre (nose)

लं वं रं यं हं



Both Hands to Feet Bound One-Legged King Pigeon Pose 1

Dwi Hasta Pada Baddha Eka Pada Raja Kapotasana 1

(DWI-huh-stuh PUH-duh BUH-duh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: arm crossed over in front of the neck
Pose Type: seated, backbend, binding
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य ह



Mermaid Pose 1

Naginyasana 1

(nah-gin-YAHS-uh-nuh)

Pose Type: seated, backbend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य



ONE-LEGGED KING PIGEON: ASYMMETRICAL ARMS—CROSS OVER & UNDER-HEAD/OVERHEAD GRIP

Both Hands to Feet Bound One-Legged King Pigeon Pose 1

Dwi Hasta Pada Baddha Eka Pada Raja Kapotasana 1

(DWI-huh-stuh PUH-duh BUH-duh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: grabbing onto the opposite foot with overhead grip
Pose Type: seated, backbend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged King Pigeon Pose 1

Eka Pada Raja Kapotasana 1

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: one hand on the back knee, one hand grabbing onto the opposite foot with overhead grip
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



ONE-LEGGED KING PIGEON: FOOT TO THE BACK OF THE HEAD

One-Legged King Pigeon Pose 1

Eka Pada Raja Kapotasana 1

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: grabbing onto the back knee with both hands under-head grip; foot to the back of the head
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



One Legged King Pigeon Pose 1

Eka Pada Raja Kapotasana 1

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Pose Type: seated, backbend

Drishti Point: Angusthamadhye or Angustha Ma Dyai (thumbs)

How to Perform the Pose:

1. Begin by sitting on the floor with both your legs straight out in front of you. Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale and bend your left knee, keeping the knee on the floor, and slide the left heel toward the inside of your right thigh.
3. Inhale as you lean forward. Exhale, extend the right leg straight out behind you with your right thigh, knee, shin, and front of the right foot on the floor. Square your hips by pulling the left hip to the back and right hip to the front.
4. Inhale as you lengthen the spine, pressing both hands to the floor by your hips for support. Exhale as you let your head roll back into a backbend.
5. Exhale as you bend your right knee, bringing your right foot toward your head. Once your right foot touches your head, slide your right foot under the back of your head and fix it in place.
6. Inhale as you stretch both arms up over your head. Exhale as you bring your palms together, keeping your arms straight and strong (Pose #1). Push through your chest. You can experiment with interlocking your fingers and letting your pointer fingers and thumbs be straight. You can also bring your foot to the side of your head (Pose #2).
7. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch.
8. Exhale as you release the right foot from under your head and lower it to the floor. Inhale and straighten your spine. Exhale as you bring both your legs straight out in front of you. Repeat on the other side.

Modification: both arms extended to the sky
1. foot to the back of the head, palms together
2. foot to the side of the head, fingers interlocked, pointer fingers free

eka = one

pada = foot or leg

raja = king, royal

kapota = pigeon

1.





2.

Easy One-Legged King Pigeon Pose 1

Sukha Eka Pada Raja Kapotasana 1

(SUK-uh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: hips lifted, back leg straight, arms open wide
Pose Type: standing (on the knees), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged King Pigeon Pose 1 Prep.

Eka Pada Raja Kapotasana 1 Prep.

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: hips off the floor, back leg straight; hands on the hips
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Upward Hands One-Legged King Pigeon Pose 1

Urdhva Hasta Eka Pada Raja Kapotasana 1

(OORD-vuh HUH-stuh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: hips off the floor, back leg straight; arms extended to the sky

Pose Type: seated, backbend

Drishti Point: Angushtamadhye or Angustha Ma Dyai (thumbs)

लं वं रं यं हं



One-Legged King Pigeon Pose 1 Prep.

Eka Pada Raja Kapotasana 1 Prep.

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: back leg straight; palms facing up, back of the hand on the foot and the knee

Pose Type: seated, backbend

Drishti Point: Nasagrai or Nasagre (nose)

लं वं रं यं



ONE-LEGGED KING PIGEON: BACK LEG STRAIGHT—FORWARD BEND & TWIST

One-Legged King Pigeon Pose 1

Eka Pada Raja Kapotasana 1

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: back leg straight; forward bend, forearms to the floor, foot and knee to the elbow creases

Pose Type: seated, forward bend

Drishti Point: Nasagrai or Nasagre (nose)



One-Legged King Pigeon Pose 1

Eka Pada Raja Kapotasana 1

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: back leg straight; forehead to the floor, palms to the floor, elbows on top of the wrists

Pose Type: seated, forward bend

Drishti Point: Nasagrai or Nasagre (nose)



Hand Position of Cow Face Pose in One-Legged King Pigeon Pose 1

Hasta Gomukhasana in Eka Pada Raja Kapotasana 1

(HUH-stuh go-muk-AHS-uh-nuh in EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: back leg straight, forward bend with Gomukhasana Arms
Pose Type: seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य ॐ



Revolved One-Legged King Pigeon Pose 1

Parivritta Eka Pada Raja Kapotasana 1

(puh-ri-VRIT-tuh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)
Modification: twisting to the inside of the body, back leg straight; foot to the armpit
Pose Type: seated, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व



Revolved One-Legged King Pigeon Pose 1

Parivritta Eka Pada Raja Kapotasana 1

(puh-ri-VRIT-tuh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)
Modification: twisting to the outside of the body, back leg straight; knee to the armpit
Pose Type: seated, forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)

VERTICAL SPLITS: SPINE STRAIGHT

Pose Dedicated to Hanuman

Hanumanasana

(huh-nu-mahn-AHS-uh-nuh)

Also Known As: Pose Dedicated to Hanuman A (Hanumanasana A)
Modification: hands in Anjali Mudra (Hands in Prayer)
1. side view
2. front view
Pose Type: seated
Drishti Point: Nasagrai or Nasagre (nose) or Hastagrai or Hastagre (hands)



2.



Upward Hands in

Pose Dedicated to Hanuman

Urdhva Hasta Hanumanasana

(OORD-vuh HUH-stuh huh-nu-mahn-AHS-uh-nuh)

Also Known As: Pose Dedicated to Hanuman B (Hanumanasana B)

Pose Type: seated, backbend

Drishti Point: Angusthamadhye or Angustha Ma Dyai (thumbs)

How to Perform the Pose:

1. Begin by standing on your knees with sitting bones lifted off the heels. Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale, step your left foot to the front into a lunge. Keep your left knee on top of your left ankle and your right knee under your right hip.
3. Inhale as you slide your left foot out to the front, lifting your left toes off the floor until your left leg is straight.
4. Inhale and stretch your arms up to lengthen your spine. Exhale as you hinge forward from your hips, bringing your hands to the floor on either side of the left leg.
5. On your next exhale, start sliding your left foot out to the front and your right knee to the back, reaching your legs in two opposite directions, coming into a full vertical split. Keep your hips square by pulling your left hip back and your right hip forward.
6. Inhale and reach both your arms up to the sky. Exhale as you deepen the backbend by letting your head roll back and your arms reach in the direction of your back foot.
7. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch.
8. Inhale as you come out of the backbend. Exhale and place both your palms to the floor on the inside of the left leg. Inhale. As you exhale, swing your left leg back and bring your left knee to the floor by your right knee. Inhale and come up to the starting position with both knees on the floor. Repeat on the other side.

Modification: deep backbend

urdhva = upward

hasta = hand

Hanuman = Hindu Deity, Lord of the Monkeys

Hands Bound Pose Dedicated to Hanuman

Baddha Hasta Hanumanasana

(BUH-duh HUH-stuh huh-nu-mahn-AHS-uh-nuh)

Modification: forward bend

1. side view
2. front view

Pose Type: seated, forward bend

Drishti Point: Padayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose)

ल व र य ह


1.


2.

VERTICAL SPLITS: TWISTS & SIDE BENDS

Revolved Pose Dedicated to Hanuman

Parivritta Hanumanasana

(puh-ri-VRIT-uh huh-nu-mahn-AHS-uh-nuh)

Pose Type: seated, twist

Drishti Point: Padayoragrai or Padayoragre (toes/feet)

ल व



Revolved Sideways Pose Dedicated to Hanuman

Parivritta Parshva Hanumanasana

(puh-ri-VRIT-uh PAHRSH-vuh huh-nu-mahn-AHS-uh-nuh)

Modification: twisting to the inside of the body
Pose Type: seated, forward bend, twist, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व य



Revolved Sideways Pose Dedicated to Hanuman

Parivritta Parshva Hanumanasana

(puh-ri-VRIT-uh PAHRSH-vuh huh-nu-mahn-AHS-uh-nuh)

Modification: twisting to the outside of the body
Pose Type: seated, forward bend, twist, side bend
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व र य



VERTICAL SPLITS: BACK FOOT TOWARD THE HIP & MERMAID POSE

Revolved One-Legged King Pigeon Pose 4 Prep.

Parivritta Eka Pada Raja Kapotasana 4 Prep.

(puh-ri-VRIT-tuh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: 1. hand to the floor by the hip, other hand pressing the foot toward the hip
2. grabbing onto the big toe of the front foot on the same side, other hand pressing the back foot toward the hip
Pose Type: seated, backbend, twist
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Parshva Drishti (to the right), Parshva Drishti (to the left)
ल व र य





Mermaid Pose 4

Naginyasana 4

(nuh-gin-YAHS-uh-nuh)

Pose Type: seated, backbend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ॐ



VERTICAL SPLITS: BACK KNEE BENT—OVERHEAD GRIP & FOOT TO THE BACK OF THE HEAD

One-Legged King Pigeon Pose 4

Eka Pada Raja Kapotasana 4

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: one hand grabbing onto the back foot on the same side with overhead grip
Pose Type: seated, backbend
Drishti Point: Hastagrai or Hastagre (hands)
ल व र य ह



One-Legged King Pigeon Pose 4

Eka Pada Raja Kapotasana 4

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: one hand grabbing onto the back foot on the opposite side with overhead grip, foot reaching toward the head; other hand on the knee of the front leg

Pose Type: seated, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged King Pigeon Pose 4

Eka Pada Raja Kapotasana 4

(EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Also Known As: One-Legged Stretched Out King Pigeon Pose (Prasarita Pada Raja Kapotasana), Pose of the Lord Kailasha (Kailashasana), Saw Pose A (Kroukachasana A)

Modification: both hands grabbing onto the back foot with overhead grip

Pose Type: seated, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

Foot to the Head One-Legged King Pigeon Pose 4

Shirsha Pada Eka Pada Raja Kapotasana 4

(SHEER-shuh PUH-duh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)

Also Known As: Hanuman Salutation Pose (Hanumana Namaskara)
Modification: both arms extended to the sky, back foot to the back of the head
Pose Type: seated, backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व र य ह



Core Poses

BOAT POSE

SIX TRIANGLES POSE

SUPINE POSES

BOAT POSE: BOTH KNEES BENT

Easy Boat Pose

Sukha Navasana

(SUK-uh nah-VAHS-uh-nuh)

Modification: knees bent, arms wrapped around the shins
Pose Type: core, seated
Drishti Point: Nasagrai or Nasagre (nose)

● ● ●



Easy Boat Pose

Sukha Navasana

(SUK-uh nah-VAHS-uh-nuh)

Modification: knees bent, grabbing the back of the thighs, toes touching the floor
Pose Type: core, seated
Drishti Point: Nasagrai or Nasagre (nose)

● ●



Easy Boat Pose

Sukha Navasana

(SUK-uh nah-VAHS-uh-nuh)

Modification: knees bent, arms wrapped around the back of the thighs, shins parallel to the floor

Pose Type: core, seated

Drishti Point: Padayoragrai or Padayoragre (toes/feet)

ल र य



Easy Boat Pose

Sukha Navasana

(SUK-uh nah-VAHS-uh-nuh)

Modification: grabbing onto the heels, toes touching the floor

Pose Type: core, seated

Drishti Point: Nasagrai or Nasagre (nose)

ल र य



Easy Boat Pose

Sukha Navasana

(SUK-uh nah-VAHS-uh-nuh)

Modification: grabbing onto the outside edges of the feet, shins parallel to the floor

Pose Type: core, seated

Drishti Point: Nasagrai or Nasagre (nose)



Pendant Pose

Lolasana

(lo-LAHS-uh-nuh)

Modification: knees in front of chest, ankles crossed

Pose Type: core, arm balance

Drishti Point: Nasagrai or Nasagre (nose)



BOAT POSE: BOTH KNEES BENT

Boat Pose

Navasana

(nah-VAHS-uh-nuh)

Pose Type: core, seated

Drishti Point: Padhayoragrai or Padayoragre (toes/feet)

How to Perform the Pose:

1. Begin by sitting on the floor with both your legs straight out in front of you. Keep your hands on the floor at the sides of your hips for support. Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale, bend your knees, and slide your feet toward your sitting bones. Keep your feet and knees together.
3. Inhale as you lengthen your spine. Engage your core and lean back. Make sure your spine is straight and your lower back is off the floor.
4. Exhale and lift your feet off the floor until your shins are parallel to the floor.
5. Once you have your balance, exhale and lift your arms off the floor, keeping them parallel to the floor.
6. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of pose.
7. Inhale as you release the pose by lowering your hands and feet to the floor. Exhale and slide your feet out in front until your legs are straight to come back to the starting position.

Variation: arms straight and parallel to the floor, knees bent, shins parallel to the floor

nava = boat

Easy Boat Pose

Sukha Navasana

(SUK-uh nah-VAHS-uh-nuh)

Modification: knees bent, ankles crossed, arms straight and parallel to the floor
Pose Type: core, seated
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Easy Boat Pose

Sukha Navasana

(SUK-uh nah-VAHS-uh-nuh)

Modification: knees bent, fingertips to the floor, toes touching the floor
Pose Type: core, seated
Drishti Point: Nasagrai or Nasagre (nose)



Easy Boat Pose

Sukha Navasana

(SUK-uh nah-VAHS-uh-nuh)

Modification: knees bent, fingertips to the floor, shins parallel to the floor
Pose Type: core, seated
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
● ● ●



BOAT POSE: BOTH LEGS STRAIGHT

Supported Boat Pose

Salamba Navasana

(SAH-luhm-buh nah-VAHS-uh-nuh)

Modification: palms to the floor behind the hips
1. both legs straight, fingertips pointing toward the hips
2. both legs straight, both arms straight, fingertips pointing to the back
Pose Type: core, seated
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Padayoragrai or Padayoragre (toes/feet)
● ●





Supported Boat Pose

Salamba Navasana

(SAH-luhm-buh nah-VAHS-uh-nuh)

Modification: both arms wrapped around both legs, legs straight
Pose Type: core, seated
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Supported Boat Pose—One-Handed

Eka Hasta Salamba Navasana

(EY-kuh HUH-stuh SAH-luhm-buh nah-VAHS-uh-nuh)

Modification: both legs straight; one arm straight, fingertips to the sky; other arm wrapping behind the ankles of both legs
Pose Type: core, seated
Drishti Point: Urdhva or Antara Drishti (up to the sky) or Hastagrai or Hastagre (hands)



Supported Boat Pose

Salamba Navasana

(SAH-luhm-buh nah-VAHS-uh-nuh)

Modification: fingertips on the floor, pointing to the front
Pose Type: core, seated
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Supported Boat Pose

Salamba Navasana

(SAH-luhm-buh nah-VAHS-uh-nuh)

Modification: grabbing behind the knees, legs straight
Pose Type: core, seated
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Complete Boat Pose

Paripurna Navasana

(puh-ri-POOR-nuh nah-VAHS-uh-nuh)

Modification: arms straight and parallel to the floor, legs straight

Pose Type: core, seated

Drishti Point: Padayoragrai or Padayoragre (toes/feet)

लं



Half Boat Pose

Ardha Navasana

(UHR-duh nah-VAHS-uh-nuh)

Modification: fingers interlocked behind the head

Pose Type: core, seated

Drishti Point: Padayoragrai or Padayoragre (toes/feet)

लं रं हं



Boat Pose

Navasana

(nah-VAHS-uh-nuh)

Modification: palms and elbows together, elbows bent
Pose Type: core, seated
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Unsupported Boat Pose

Niralamba Navasana

(nir-AH-luhm-buh nah-VAHS-uh-nuh)

Modification: arms shoulder width apart
Pose Type: core, seated
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BOAT POSE: TWIST

Revolved Boat Pose with Hands in Prayer

Parivritta Navasana Namaskar

(puh-ri-VRIT-tuh nah-VAHS-uh-nuh nuh-muhs-KAHR)

Pose Type: core, seated, twist
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Supported Boat Pose—One-Handed

Eka Hasta Salamba Navasana

(EY-kuh HUH-stuh SAH-luhm-buh nah-VAHS-uh-nuh)

Modification: both legs straight, ankles crossed; one arm straight, palm to the floor behind the hips; other arm wrapping behind the ankles of both legs
Pose Type: core, seated
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Revolved Supported Boat Pose—One-Handed

Parivritta Eka Hasta Salamba Navasana

(puh-ri-VRIT-tuh EY-kuh HUH-stuh SAH-luhm-buh nah-VAHS-uh-nuh)

Modification: both legs straight, ankles crossed; arms straight, fingertips to the floor behind the hips, one hand grabbing onto the heel

Pose Type: core, seated, twist

Drishti Point: Hastagrai or Hastagre (hands)

ल य



Revolved Supported Boat Pose—One-Handed

Parivritta Eka Hasta Salamba Navasana

(puh-ri-VRIT-tuh EY-kuh HUH-stuh SAH-luhm-buh nah-VAHS-uh-nuh)

Modification: one foot under the knee, other leg straight; one arm threaded under the bent leg, fingertips of the other hand on the floor

Pose Type: core, seated, twist

Drishti Point: Hastagrai or Hastagre (hands)

ल व



Revolved Supported Boat Pose

Parivritta Salamba Navasana

(puh-ri-VRIT-tuh SAH-luhm-buh nah-VAHS-uh-nuh)

Modification: ankles crossed, legs wrapped around the forearm
Pose Type: core, seated, twist
Drishti Point: Parshva (far to the right), Parshva (far to the left)



BOAT POSE: TWIST, SCISSOR LEGS

Revolved Boat Pose

Parivritta Navasana

(puh-ri-VRIT-tuh nah-VAHS-uh-nuh)

Modification: one leg over the shoulder, toes of the other leg to the floor
1. front view
2. back view
Pose Type: core, seated, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)





Revolved Boat Pose

Parivritta Navasana

(puh-ri-VRIT-tuh nah-VAHS-uh-nuh)

Modification: one leg over the shoulder, both legs straight
1. front view
2. back view
Pose Type: core, seated, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)




2.

BOAT POSE: ONE LEG STRAIGHT, ONE LEG BENT

One-Legged Supported Boat Pose

Eka Pada Salamba Navasana

(EY-kuh PUH-duh SAH-luhm-buh nah-VAHS-uh-nuh)

Modification: one leg straight, one knee bent and dropped to the side for support
Pose Type: core, seated
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) or Padayoragrai or Padayoragre (toes/feet)



One-Legged Supported Boat Pose

Eka Pada Salamba Navasana

(EY-kuh PUH-duh SAH-luhm-buh nah-VAHS-uh-nuh)

Modification: grabbing onto the back of the thighs for support; one leg straight, one leg bent—toes touching the floor
Pose Type: core, seated
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



One-Legged Unsupported Boat Pose

Eka Pada Niralamba Navasana

(EY-kuh PUH-duh nir-AH-luhm-buh nah-VAHS-uh-nuh)

Modification: one leg straight; one knee bent toward the chest, foot off the floor
Pose Type: core, seated
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



BOAT POSE: SCISSOR LEGS

One-Legged Supported Boat Pose—One-Handed

Eka Pada Eka Hasta Salamba Navasana

(EY-kuh PUH-duh EY-kuh HUH-stuh SAH-luhm-buh nah-VAHS-uh-nuh)

Modification: grabbing the outside edge of the foot with the opposite hand for support, leg straight, other arm up to the sky
1. other leg bent, toes touching the floor
2. other leg straight, foot off the floor
Pose Type: core, seated
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Padayoragrai or

Padayoragre (toes/feet)





BOAT POSE: ONE FOOT TO KNEE

Upward Half Firelog Western Intense Stretch Pose

Urdhva Ardha Agnistambha Paschimottanasana

(OORD-vuh UHR-duh uhg-ni-STUHM-buh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Upward Half Firelog Seated Forward Bend
Modification: 1. forehead to the shin
2. forehead away from the shin
Pose Type: core, seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Padayoragrai or Padayoragre (toes/feet)

1.



2.



Baby Cradle Pose in Boat Pose

Hindolasana in Navasana

(hin-do-LAHS-uh-nuh in nah-VAHS-uh-nuh)

Modification: foot of the bent leg to the back of the knee of the straight leg
Pose Type: core, seated, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Revolved Yogic Staff Boat Pose

Parivritta Yogadanda Navasana

(puh-ri-VRIT-tuh yo-guh-DUHN-duh nah-VAHS-uh-nuh)

Modification: both knees bent; one arm behind the back, grabbing onto the ankle; other arm grabbing the outside edge of the foot

Pose Type: core, seated, twist, binding

Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Revolved Bound Yogic Staff Boat Pose

Parivritta Baddha Yogadanda Navasana

(puh-ri-VRIT-tuh BUH-duh yo-guh-DUHN-duh nah-VAHS-uh-nuh)

Modification: binding around the straight leg

Pose Type: core, seated, twist, binding

Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Revolved Yogic Staff Boat Pose

Parivritta Yogadanda Navasana

(puh-ri-VRIT-tuh yo-guh-DUHN-duh nah-VAHS-uh-nuh)

Modification: foot to the triceps; one arm grabbing onto the heel of the straight leg, other arm open to

the side
Pose Type: core, seated, twist
Drishti Point: Hastagrai or Hastagre (hands)
ल व



BOAT POSE: ONE FOOT TO HIP SOCKET

Upward One-Legged Half Lotus Western Intense Stretch Pose

Urdhva Eka Pada Ardha Padma Paschimottanasana

(OORD-vuh EY-kuh PUH-duh UHR-duh PUHD-muh puhsh-chi-mo-tahn-AHS-uh-nuh)
Also Known As: Upward One-Legged Half Lotus Seated Forward Bend
Modification: one hand grabbing onto the big toe, one hand on the hip
Pose Type: core, seated, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
ल व



Upward One-Legged Half Bound Lotus Western Intense Stretch Pose

Urdhva Eka Pada Ardha Baddha Padma Paschimottanasana

(OORD-vuh EY-kuh PUH-duh UHR-duh BUH-duh PUHD-muh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Upward One-Legged Half Bound Lotus Seated Forward Bend
Pose Type: core, seated, forward bend, binding
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Upward One-Legged Half Bound Lotus Western Intense Stretch Pose

Urdhva Eka Pada Ardha Baddha Padma Paschimottanasana

(OORD-vuh EY-kuh PUH-duh UHR-duh BUH-duh PUHD-muh puhsh-chi-mo-tahn-AHS-uh-nuh)
Also Known As: Upward One-Legged Half Bound Lotus Seated Forward Bend
Modification: grabbing onto the foot, hand between the calf muscle and the hamstring
Pose Type: core, seated, forward bend, binding
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Upward One-Legged Half Lotus Western Intense Stretch Pose

Urdhva Eka Pada Ardha Padma Paschimottanasana

(OORD-vuh EY-kuh PUH-duh UHR-duh PUHD-muh puhsh-chi-mo-tahn-AHS-uh-nuh)
Also Known As: Upward One-Legged Half Lotus Seated Forward Bend
Modification: 1. grabbing onto the wrist, hands over the foot

2. grabbing onto the foot, nose to the shin

Pose Type: core, seated, forward bend

Drishti Point: Padayoragrai or Padayoragre (toes/feet) or Nasagrai or Nasagre (nose)

1.



2.



BOAT POSE: GRABBING ONTO FEET/TOES

Big Toes Pose

Ubhaya Padangusthasana

(u-beye-uh puhd-ahng-goosh-TAHS-uh-nuh)

Modification: grabbing onto the big toes, toes flexed in

Pose Type: core, seated

Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Upward Facing Western Intense Stretch

Urdhva Mukha Paschimottanasana

(OORD-vuh MUK-uh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Upward Facing Seated Forward Bend
Modification: grabbing onto the heels, arms straight
Pose Type: core, seated, forward bend, quadriceps to the chest
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Upward Facing Western Intense Stretch

Urdhva Mukha Paschimottanasana

(OORD-vuh MUK-uh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Upward Facing Seated Forward Bend
Modification: grabbing onto the heels
1. forehead away from the shins
2. forehead to the shins
Pose Type: core, seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)





Upward Facing Supported Western Intense Stretch

Urdhva Mukha Salamba Paschimottanasana

(OORD-vuh MUK-uh SAH-luhm-buh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Upward Facing Seated Forward Bend

Modification: arms reaching to the front, fingertips to the floor, 1. forehead away from the shins 2. forehead to the shins

Pose Type: core, seated, forward bend

Drishti Point: Padayoragrai or Padayoragre (toes/feet) or Nasagrai or Nasagre (nose)





Bound Hands Upward Facing Western Intense Stretch

Baddha Hasta Urdhva Mukha Paschimottanasana

(BUH-duh HUH-stuh OORD-vuh MUK-uh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Bound Hands Upward Facing Seated Forward Bend
Pose Type: core, seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
● ● ● ●



Upward Facing Western Intense Stretch

Urdhva Mukha Paschimottanasana

(OORD-vuh MUK-uh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Upward Facing Seated Forward Bend
Modification: grabbing onto the ankles, forehead to the shins
Pose Type: core, seated, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
● ● ● ●



Upward Facing Western Intense Stretch

Urdhva Mukha Paschimottanasana

(OORD-vuh MUK-uh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Upward Facing Seated Forward Bend
Modification: grabbing onto the outside edges of the feet, feet hip distance apart, toes pointed
Pose Type: core, seated, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



ARM BALANCE: SITTING BONES & FEET OFF THE FLOOR

Celibate Pose

Brahmacharyasana

(bruh-muh-chahr-YAHS-uh-nuh)

Also Known As: Lifted Up Staff Pose (Dandasana Utpluti)
Modification: fingers to the floor, thumbs pointing to the back
Pose Type: core, arm balance
Drishti Point: Nasagrai or Nasagre (nose)



SIX TRIANGLES POSE

Six Triangles Pose

Shatkonasana

(shuht-ko-NAHS-uh-nuh)

Modification: top foot on the bottom knee
1. fingertips to the temples
2. one forearm to the floor, other arm wrapped around the top knee
3. fingertips to the temples, elbow toward the top knee
4. one elbow to the floor, other elbow to the top knee on the same side

Pose Type: core, seated, twist

Drishti Point: 1. Urdhva or Antara Drishti (up to the sky)
2. Nasagrai or Nasagre (nose)
3. Nasagrai or Nasagre (nose)
4. Hastagrai or Hastagre (hands)



2.



3.



4.



SUPINE: ONE LEG STRAIGHT, ONE LEG BENT

Half Wind Relieving Pose

Ardha Vayu Muktyasana

(UHR-duh VAH-yu muk-TYAHS-uh-nuh)

Also Known As: Wind-Relieving Pose (Pavana Muktasana)
Pose Type: core, supine
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य ह



Revolved Half Wind Relieving Pose

Parivritta Ardha Vayu Muktyasana

(puh-ri-VRIT-tuh UHR-duh VAH-yu muk-TYAHS-uh-nuh)

Modification: one knee bent, one leg straight
Pose Type: core, supine, twist
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye (third eye, between the eyebrows)



SUPINE: BOTH LEGS STRAIGHT “SCISSORS”

One-Legged Upward Extended Legs Pose

Eka Pada Urdhva Prasarita Padasana

(EY-kuh PUH-duh OORD-vuh pruh-SAH-ri-tuh puh-DAHS-uh-nuh)

Modification: 1. one arm extended to sky, other palm to the floor, head on the floor
2. one arm extended to sky, other palm to the floor, head and shoulders off the floor
3. fingers interlocked behind the back of the head, head and shoulders off the floor
Pose Type: core, supine
Drishti Point: Padayoragrai or Padayoragre (toes/feet)







SUPINE: BOTH LEGS STRAIGHT

Abdominal Lift Pose

Jatharasana

(jah-tuh-RAHS-uh-nuh)

Modification: head on the floor, palms down by the hips
Pose Type: core, supine
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Upward Extended Legs Pose

Urdhva Prasarita Padasana

(OORD-vuh pruh-SAH-ri-tuh puh-DAHS-uh-nuh)

Pose Type: core, supine

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Abdominal Lift Pose

Jatharasana

(jah-tuh-RAHS-uh-nuh)

Modification: head and shoulders off the floor, feet off the floor

Pose Type: core, supine

Drishti Point: Padayoragrai or Padayoragre (toes/feet)



SUPINE: BOTH LEGS STRAIGHT

Two-Legged Abdominal Lift Upward Extended Legs Pose

Dwi Pada Jathara Urdhva Prasarita Padasana

(DWI-puh-duh JAH-tuh-ruh OORD-vuh pruh-SAH-ri-tuh puh-DAHS-uh-nuh)

Modification: with a yoga block
Pose Type: core, supine
Drishti Point: Urdhva or Antara Drishti (up to the sky), Padayoragrai or Padayoragre (toes/feet)
🔴 🟡



Abdominal Lift Upward Facing Western Intense Stretch

Jathara Urdhva Mukha Paschimottanasana

(JAH-tuh-ruh OORD-vuh MUK-uh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Abdominal Lift Upward Forward Bend
Modification: head lifted off the floor, forehead to the shins
Pose Type: core, supine
Drishti Point: Nasagrai or Nasagre (nose)
🔴 🟡 🟢 🔵 🟣



Abdominal Lift Upward Facing Western Intense Stretch

Jathara Urdhva Mukha Paschimottanasana

(JAH-tuh-ruh OORD-vuh MUK-uh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Abdominal Lift Upward Forward Bend
Modification: head lifted off the floor, legs crossed modification
Pose Type: core, supine
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
ल व र



SUPINE: ONE LEG STRAIGHT, ONE KNEE BENT

Revolved Stomach One Leg Extended Pose

Parivritta Jathara Utthita Eka Padasana

(puh-ri-VRIT-tuh JAH-tuh-tuh UT-ti-tuh EY-kuh puh-DAHS-uh-nuh)

Modification: foot to the elbow
Pose Type: core, supine, twist
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
ल व र



SUPINE: GARUDA LEGS ON THE BACK

Reclining Abdominal Lift Pose Dedicated to Garuda

Supta Jathara Garudasana

(SUP-tuh JAH-tuh-ruh guh-ru-DAHS-uh-nuh)

Pose Type: core, supine
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Reclining Abdominal Lift Pose Dedicated to Garuda

Supta Jathara Garudasana

(SUP-tuh JAH-tuh-ruh guh-ru-DAHS-uh-nuh)

Modification: fingers to the temples, elbows to the knees
Pose Type: core, supine
Drishti Point: Urdhva or Antara Drishti (up to the sky), Padayoragrai or Padayoragre (toes/feet)



Abdominal Lift Pose Dedicated to Garuda

Jathara Garudasana

(JAH-tuh-ruh guh-ru-DAHS-uh-nuh)

Modification: palms to the floor, arms straight, sitting bones lifted off the floor
Pose Type: core, supine
Drishti Point: Urdhva or Antara Drishti (up to the sky), Padayoragrai or Padayoragre (toes/feet)
ल व र



Revolved Stomach Reclining Pose Dedicated to Garuda

Parivritta Jathara Supta Garudasana

(puh-ri-VRIT-tuh JAH-tuh-ruh SUP-tuh guh-ru-DAHS-uh-nuh)

Modification: fingers to the temples, elbows out to the sides
Pose Type: core, supine, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
ल व र



SUPINE: FULL LOTUS

Reclining Abdominal Lift Lotus Pose

Supta Jathara Padmasana

(SUP-tuh JAH-tuh-ruh puhd-MAHS-uh-nuh)

Modification: fingers to the temples, knees up to the sky
Pose Type: core, supine
Drishti Point: Nasagrai or Nasagre (nose)
लं वं रं हं



Revolved Stomach Reclining Lotus Pose

Parivritta Jathara Supta Padmasana

(puh-ri-VRIT-tuh JAH-tuh-ruh SUP-tuh puhd-MAHS-uh-nuh)

Modification: fingers to the temples, elbows out to the sides
1. back view
2. front view
Pose Type: core, supine, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)


1.


2.

Abdominal Lift Lotus Pose

Jathara Padmasana

(JAH-tuh-tuh puhd-MAHS-uh-nuh)

Modification: palms on the floor, arms straight, sitting bones lifted off the floor
Pose Type: core, supine
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Unsupported Abdominal Lift Lotus Pose

Niralamba Jathara Padmasana

(nir-AH-luhm-buh JAH-tuh-tuh puhd-MAHS-uh-nuh)

Modification: arms extended in front, knees to the forearms

Pose Type: core, supine

Drishti Point: Nasagrai or Nasagre (nose)



Quadruped Poses

CHILD’S POSE

RABBIT POSE

COW POSE

ALL FOURS (VARIATIONS)

PLANK POSE

PLANK ON FOREARMS

FOUR LIMBED STAFF POSE

SIDE PLANK

Child’s Pose

Balasana

(bah-LAHS-uh-nuh)

Also Known As: Child’s Pose (Garbhasana)
Modification: arms extended to the back, palms up; toes pointed to the back
Pose Type: forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Child’s Pose

Balasana

(bah-LAHS-uh-nuh)

Also Known As: Child’s Pose (Garbhasana)
Modification: arms extended to the front, palms down; toes pointed to the back
Pose Type: forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Child’s Pose

Balasana

(bah-LAHS-uh-nuh)

Modification: arms extended to the front, palms down; toes curled in

Pose Type: forward bend

Drishti Point: Nasagrai or Nasagre (nose)



Hands to the Side Child’s Pose

Parshva Hasta Balasana

(PAHRSH-vuh HUH-stuh bah-LAHS-uh-nuh)

Pose Type: forward bend, side bend

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Hand Position of the Pose Dedicated to Garuda in Child’s Pose

Hasta Garudasana in Balasana

(HUH-stuh guh-ru-DAHS-uh-nuh in bah-LAHS-uh-nuh)

Pose Type: forward bend

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)

ल र य ह



Child’s Pose

Balasana

(bah-LAHS-uh-nuh)

Modification: knees open wide; palms pressed together, fingers spread wide, thumbs to the upper back

Pose Type: forward bend, mild backbend

Drishti Point: Nasagrai or Nasagre (nose)

ल य ॐ



CHILD’S POSE: TWISTS

Revolved Side Child’s Pose

Parivritta Parshva Balasana

(puh-ri-VRIT-tuh PAHRSH-vuh bah-LAHS-uh-nuh)

Pose Type: forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
● ●



Both Hands to Legs Bound Revolved Child’s Pose

Dwi Hasta Pada Baddha Parivritta Balasana

(DWI-huh-stuh PUH-duh BUH-duh puh-ri-VRIT-tuh bah-LAHS-uh-nuh)
Pose Type: forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)
● ●



Leg Position of the Pose Dedicated to Garuda in Revolved Child’s Pose

Pada Garudasana in Parivritta Balasana

(PUH-duh guh-ru-DAHS-uh-nuh in puh-ri-VRIT-tuh bah-LAHS-uh-nuh)
Modification: hands in Anjali Mudra (Hands in Prayer)
Pose Type: forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
● ● ●



Revolved Child’s Pose

Parivritta Balasana

(puh-ri-VRIT-tuh bah-LAHS-uh-nuh)

Also Known As: Turned Child’s Pose (Parshva Balasana)
Modification: bottom arm straight out to the side; top arm bent at 90 degrees, palm to the floor overhead
Pose Type: forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
● ●



One Hand Bound Revolved Child’s Pose

Eka Hasta Baddha Parivritta Balasana

(EY-kuh HUH-stuh BUH-duh puh-ri-VRIT-tuh bah-LAHS-uh-nuh)

Modification: grabbing onto the quadricep
Pose Type: forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)
● ●



CHILD'S POSE: TWISTS & HALF LOTUS BINDING

Hand to Foot Revolved Side Child's Pose

Hasta Pada Parivritta Parshva Balasana

(HUH-stuh PUH-duh puh-ri-VRIT-tuh PAHRSH-vuh bah-LAHS-uh-nuh)

Modification: foot resting on the back of the knee
Pose Type: forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
● ● ●



Both Hands to Feet Half Bound Lotus Revolved Child's Pose

Dwi Hasta Pada Ardha Baddha Padma Parivritta Balasana

(DWI-huh-stuh PUH-duh UHR-duh BUH-duh PUHD-muh puh-ri-VRIT-tuh bah-LAHS-uh-nuh)

Pose Type: forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)
● ● ●



Half Bound Lotus Revolved Child's Pose

Ardha Baddha Padma Parivritta Balasana

(UHR-duh BUH-duh PUHD-muh puh-ri-VRIT-tuh bah-LAHS-uh-nuh)

Modification: torso twisting to the outside of the body, hand binding to the foot
Pose Type: forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Half Bound Lotus Revolved Child's Pose

Ardha Baddha Padma Parivritta Balasana

(UHR-duh BUH-duh PUHD-muh puh-ri-VRIT-tuh bah-LAHS-uh-nuh)

Modification: torso twisting to the inside of the body, hand binding to the shin
Pose Type: forward bend, twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



CHILD’S POSE: TWISTS—ONE-LEGGED—BACK FOOT IN THE AIR

Equilibrium One-Legged Revolved Child’s Pose with Hands in Prayer

Tulya Eka Pada Parivritta Balasana Namaskar

(TUL-yuh EY-kuh PUH-duh puh-ri-VRIT-tuh bah-LAHS-uh-nuh nuh-muhs-KAHR)

Modification: knee of the top leg bent
Pose Type: forward bend, twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
● ● ●



Half Bow Pose in Equilibrium One-Legged Revolved Child’s Pose

Ardha Dhanurasana in Tulya Eka Pada Parivritta Balasana

(UHR-duh duh-nur-AHS-uh-nuh in TUL-yuh EY-kuh PUH-duh puh-ri-VRIT-tuh bah-LAHS-uh-nuh)

Pose Type: forward bend, twist, backbend
Drishti Point: Hastagrai or Hastagre (hands)
● ● ● ● ●



Revolved Half Bow Pose in Equilibrium One-Legged Revolved Child’s Pose

Parivritta Ardha Dhanurasana in Tulya Eka Pada Parivritta Balasana

(puh-ri-VRIT-tuh UHR-duh duh-nur-AHS-uh-nuh in TUL-yuh EY-kuh PUH-duh puh-ri-VRIT-tuh bah-LAHS-uh-nuh)

Pose Type: forward bend, twist, backbend
Drishti Point: Hastagrai or Hastagre (hands)
ल व र य



Half Bow Pose in Equilibrium One-Legged Revolved Child’s Pose

Ardha Dhanurasana in Tulya Eka Pada Parivritta Balasana

(UHR-duh duh-nur-AHS-uh-nuh in TUL-yuh EY-kuh PUH-duh puh-ri-VRIT-tuh bah-LAHS-uh-nuh)

Modification: back heel toward the sitting bone
Pose Type: forward bend, twist, backbend
Drishti Point: Hastagrai or Hastagre (hands)
ल व र य ॐ



Equilibrium One-Legged Revolved Child’s Pose

Tulya Eka Pada Parivritta Balasana

(TUL-yuh EY-kuh PUH-duh puh-ri-VRIT-tuh bah-LAHS-uh-nuh)

Modification: one leg straight, other knee bent, heel toward the sitting bone
Pose Type: forward bend, twist
Drishti Point: Hastagrai or Hastagre (hands)



Hands Bound

Rabbit Pose

Baddha Hasta Sasangasana

(BUH-duh HUH-stuh shuh-shahng-AHS-uh-nuh)

Pose Type: forward bend

Drishti Point: Nasagrai or Nasagre (nose) or Nabhi, Nabhicakre, or Nabi Chakra (belly button)

How to Perform the Pose:

1. Begin by sitting on your heels in Hero Pose (*Virasana*). Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale and bend forward, letting the crown of your head touch the floor, and lift your sitting bones off your heels. Grab onto your heels with both your hands, keeping your arms on the outsides of your shins.
3. Exhale as you rock forward, bringing your forehead toward your knees. Feel the stretch in the upper back between your shoulder blades.
4. Inhale as you lift your hands off your heels and interlock your fingers behind your back. Try to press your palms together. Exhale and stretch your arms up to the sky behind your back. Feel the stretch in your front shoulder heads and your chest (Pose #1). You can experiment by leaving your sitting bones on the heels and moving your forehead away from your knees (Pose #2).
5. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch.
6. Inhale as you release the arms. Exhale as you straighten your spine, coming back to Hero Pose (*Virasana*).

Modification:

1. forehead to the knees, sitting bones lifted
2. forehead away from the knees, sitting bones to the heels

baddha = bound

hasta = hand

sasanga = rabbit

1.



2.



ल र य ह ॐ

Rabbit Pose

Sasangasana

(shuh-shahn-GAHS-uh-nuh)

Also Known As: Rabbit Foot Pose
Pose Type: forward bend, inversion
Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)



COW POSE ON THE HEAD: HALF LOTUS & GARUDA LEGS

Half Bound Lotus Cow Pose on the Head

Ardha Baddha Padma Shirsha Bitilasana

(UHR-duh BUH-duh PUHD-muh SHEER-shuh bee-til-AHS-uh-nuh)

Also Known As: Ardha Baddha Padma Shirsha Gavasana*
Modification: crown of the head to the floor
Pose Type: forward bend, inversion, binding
Drishti Point: Nasagrai or Nasagre (nose), Nabhi, Nabhicakre, or Nabi Chakra (belly button)



Reverse Prayer in Leg Position of the Pose Dedicated to Garuda in Cow Pose on the Head

Viparita Namaskar in Pada Garudasana in Shirsha Bitilasana

(vi-puh-REE-tuh nuh-muhs-KAHR in PUH-duh guh-ru-DAHS-uh-nuh in SHEER-shuh bee-til-AHS-uh-nuh)

Also Known As: Back of the Body Prayer Leg Position of the Pose Dedicated to Garuda in Cow Pose on the Head (Paschima Namaskara Pada Garudasana in Shirsha Bitilasana)
Pose Type: forward bend, inversion
Drishti Point: Nasagrai or Nasagre (nose), Nabhi, Nabhicakre, or Nabi Chakra (belly button)



COW POSE ON THE HEAD: HEELS TO THE SITTING BONES & HEELS TO THE OUTSIDE OF THE HIPS

Both Hands to the Legs Cow Pose on the Head

Dwi Hasta Pada Shirsha Bitilasana

(DWI-huh-stuh PUH-duh SHEER-shuh bee-til-AHS-uh-nuh)

Modification: heels toward the sitting bones
Pose Type: forward bend, inversion
Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)



Both Hands to the Feet Cow Pose on the Head

Dwi Hasta Pada Shirsha Bitilasana

(DWI-huh-stuh PUH-duh SHEER-shuh bee-til-AHS-uh-nuh)

Modification: heels to the outside of the hips
Pose Type: forward bend, inversion
Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)



ALL FOURS: NEUTRAL SPINE

Cow Pose

Bitilasana

(bee-til-AHS-uh-nuh)

Also Known As: Table Pose (Bharmanasana)
Pose Type: standing (hands and knees)
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Intense Wrist Stretch Cow Pose

Uttana Manibandha Bitilasana

(ut-TAHN-uh muh-ni-BUHN-duh bee-til-AHS-uh-nuh)

Also Known As: Table Pose Modification (Bharmanasana)
Pose Type: standing (hands and knees)
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One Hand Cow Pose

Eka Hasta Bitilasana

(EY-kuh HUH-stuh bee-til-AHS-uh-nuh)

Also Known As: Table Pose (Bharmanasana)
Pose Type: standing (hands and knees)
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Leg Position of the Pose Dedicated to Garuda in Cow Pose

Pada Garudasana in Bitilasana

(PUH-duh guh-ru-DAHS-uh-nuh in bee-til-AHS-uh-nuh)

Also Known As: Table Pose Modification (Bharmanasana)
Pose Type: standing (on hands and knees)
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs), Nasagrai or Nasagre (nose)



Lotus Pose in Cow Pose

Padmasana in Bitilasana

(puhd-MAHS-uh-nuh in bee-til-AHS-uh-nuh)

Also Known As: Table Pose Modification (Bharmanasana)
Pose Type: standing (on hands and knees)
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs), Nasagrai or Nasagre (nose)

ALL FOURS: NEUTRAL SPINE—ONE LEG EXTENDED TO THE BACK

Tiger Pose

Vyaghrasana

(vyah-GRAHS-uh-nuh)

Also Known As: Table Pose Modification (Bharmanasana)
Modification: neutral spine
Pose Type: standing (hands and knees)
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
● ●



One Hand One-Legged Cow Pose

Eka Hasta Eka Pada Bitilasana

(EY-kuh HUH-stuh EY-kuh PUH-duh bee-til-AHS-uh-nuh)

Also Known As: Cat Pose (Marjarasana), Balancing Table Pose Modification (Dandayamana Bharmanasana)
Modification: neutral spine
1. arm reaching to the front, opposite leg reaching to the back
2. arm reaching to the back, opposite leg reaching to the back

3. arm reaching to the back, leg reaching to the back on the same side

Pose Type: standing (hands and knees)

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)







One Knee Cow Pose

Eka Janu Bitilasana

(EY-kuh JAH-nu bee-til-AHS-uh-nuh)

Also Known As: Unsupported Balancing Table Pose Modification (Niralamba Dandayamana Bharmanasana)

Pose Type: standing (on the knee), balance

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



ALL FOURS: NEUTRAL SPINE—ONE LEG EXTENDED TO THE BACK—HALF LOTUS

Downward Facing Pose Dedicated to Kashyapa

Adho Mukha Kashyapasana

(uh-DO MUK-uh kah-shyuh-PAHS-uh-nuh)

Modification: Leg 1: knee on the floor Leg 2: foot on the floor

Pose Type: arm balance, binding

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs), Nasagrai or Nasagre (nose)



Downward Facing Pose Dedicated to Kasyapa

Adho Mukha Kasyapasana

(uh-DO MUK-uh kah-shyuh-PAHS-uh-nuh)

Modification: Leg 1: knee on the floor Leg 2: foot off the floor

Pose Type: arm balance, binding

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



ALL FOURS: CAT TILT

Downward Facing Cat Pose

Adho Mukha Marjarasana

(uh-DO MUK-uh mahr-jah-RAHS-uh-nuh)

Modification: toes pointing away from the head
Pose Type: standing (on hands and knees), forward bend
Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)



Downward Facing Cat Pose

Adho Mukha Marjarasana

(uh-DO MUK-uh mahr-jah-RAHS-uh-nuh)

Modification: arms straight to the front, fingertips to the floor; rocking back, toes curled in
Pose Type: standing (on hands and knees), forward bend
Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)



Tiger Pose

Vyaghrasana

(vyah-GRAHS-uh-nuh)

Also Known As: Cow Pose Modification (Bitilasana)
Modification: knee to the forehead
Pose Type: standing (on hands and knees), forward bend
Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)



Tiger Pose

Vyaghrasana

(vyah-GRAHS-uh-nuh)

Also Known As: Cow Pose Modification (Bitilasana)
Modification: knee to the shoulder on the same side
Pose Type: standing (on hands and knees), forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Tiger Pose

Vyaghrasana

(vyah-GRAHS-uh-nuh)

Also Known As: Cow Pose Modification (Bitilasana)
Modification: knee to the opposite tricep
Pose Type: standing (on hands and knees), forward bend, twist
Drishti Point: Nasagrai or Nasagre (nose)



Tiger Pose

Vyaghrasana

(vyah-GRAHS-uh-nuh)

Also Known As: Cow Pose Modification (Bitilasana)
Modification: shoulder to the back of the knee; back leg, toes curled in
Pose Type: standing (on hands and knees), forward bend
Drishti Point: Nasagrai or Nasagre (nose), Padayoragrai or Padayoragre (toes/feet)

Tiger Pose

Vyaghrasana

(vyah-GRAHS-uh-nuh)

Also Known As: Cow Pose Modification (Bitilasana)
Modification: one hand to the heart
1. back of the knee to the shoulder, leg bent
2. back of the knee to the shoulder, leg straight
Pose Type: standing (on hands and knees), forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)





Upward Facing Dog Pose Tilt

Urdhva Mukha Shvanasana Tilt

(OORD-vuh MUK-uh shvuh-NAHS-uh-nuh)

Pose Type: standing (on hands and knees), backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows



Tiger Pose

Vyaghrasana

(vyah-GRAHS-uh-nuh)

Also Known As: Balancing Table Pose Modification (Niralamba Dandayamana Bharmanasana)

Modification: one leg straight out, toes pointing away from the head

Pose Type: standing (on hands and knees), backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Unsupported Tiger Pose

Niralamba Vyaghrasana

(nir-AH-luhm-buh vyah-GRAHS-uh-nuh)

Also Known As: One-Legged Bow Pose from All Fours (Eka Pada Dhanurasana), Balancing Table Pose Modification (Dandayamana Bharmanasana)
Modification: grabbing onto the foot with under-head grip on the same side
Pose Type: standing (on hands and knees), backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Unsupported Tiger Pose

Niralamba Vyaghrasana

(nir-AH-luhm-buh vyah-GRAHS-uh-nuh)

Also Known As: One-Legged Bow Pose from All Fours (Eka Pada Dhanurasana), Balancing Table Pose Modification (Dandayamana Bharmanasana)
Modification: grabbing onto the shin with under-head grip on the opposite side
Pose Type: standing (on hands and knees), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Unsupported Tiger Pose

Niralamba Vyaghrasana

(nir-AH-luhm-buh vyah-GRAHS-uh-nuh)

Also Known As: Balancing Table Pose Modification (Dandayamana Bharmanasana)
Modification: grabbing onto the foot with overhead grip on the same side, foot toward the head
1. toes pointing away from the head
2. toes curled in
Pose Type: standing (on hands and knees), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Unsupported Tiger Pose

Niralamba Vyaghrasana

(nir-AH-luhm-buh vyah-GRAHS-uh-nuh)

Also Known As: Balancing Table Pose Modification (Dandayamana Bharmanasana)
Modification: grabbing onto the foot with overhead grip on the opposite side, foot away from the head, toes curled in
Pose Type: standing (on hands and knees), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ALL FOURS: FOREARMS

Cow Pose

Bitilasana

(bee-til-AHS-uh-nuh)

Also Known As: Table Pose Modification (Bharmanasana)
Modification: forearms to the floor
Pose Type: standing (on forearms and knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं रं हं ॐ



Frog Pose in Cow Pose

Mandukasana in Bitilasana

(muhn-doo-KAHS-uh-nuh in bee-til-AHS-uh-nuh)

Also Known As: Frog Pose in Table Pose Modification (Mandukasana in Bharmanasana)
Modification: forearms to the floor, knees open wider than hips
Pose Type: standing (on forearms and knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Uneven Wounded Duck Pose Prep.

Vishama Pungu Karandavasana Prep.
(VISH-uh-muh pung-u kahr-uhn-duh-VAHS-uh-nuh)
Modification: one forearm to the floor, toes of both feet on the floor
Pose Type: standing (on forearms and feet), forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Supported Tiger Pose

Salamba Vyaghrasana *(SAH-luhm-buh vyah-GRAHS-uh-nuh)*
Also Known As: Cow Pose Modification (Bitilasana)
Modification: forearm on the floor, one hand to the heart; back of the knee to the shoulder, leg straight
Pose Type: standing (on forearms and knees), forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



Supported Tiger Pose

Salamba Vyaghrasana *(SAH-luhm-buh-nuh vyah-GRAHS-uh-nuh)*
Also Known As: Cow Pose Modification (Bitilasana)
Modification: forearm on the floor, grabbing onto the foot with under-head grip on the opposite side
Pose Type: standing (on forearms and knees), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



ALL FOURS: FOREARMS—TWISTS

Hand to Leg Sideways Leg Position of Cow Face Pose in Cow Pose

Hasta Pada Parshva Pada Gomukhasana in Bitilasana
(HUH-stuh PUH-duh PAHRSH-vuh PUH-duh go-mu-KAHS-uh-nuh in bee-til-AHS-uh-nuh)
Modification: forearm to the floor
Pose Type: standing (on forearms and knees), twist
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Half Bound Sideways Leg Position of Cow Face Pose in Cow Pose

Ardha Baddha Parshva Pada Gomukhasana in Bitilasana

(UHR-duh BUH-duh PAHRSH-vuh PUH-duh go-mu-KAHS-uh-nuh in bee-til-AHS-uh-nuh)

Modification: forearm to the floor
Pose Type: standing (on forearms and knees), twist, binding
Drishti Point: Urdhva or Antara Drishti (up to the sky)



ALL FOURS: FOREARMS—HALF LOTUS

Half Lotus Cow Pose

Ardha Padma Bitilasana

(UHR-duh PUHD-muh bee-til-AHS-uh-nuh)

Also Known As: Half Lotus Table Pose Modification (Ardha Padma Bharmanasana)
Modification: forearms to the floor
Pose Type: standing (on forearms and knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Revolved Half Lotus Cow Pose

Parivritta Ardha Padma Bitilasana

(puh-ri-VRIT-uh UHR-duh PUHD-muh bee-til-AHS-uh-nuh)

Also Known As: Revolved Half Lotus Table Pose Modification (Parivritta Ardha Padma Bharmanasana)
Modification: forearm on the floor, other hand behind the back
Pose Type: standing (on forearms and knees), twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व



Half Bound Lotus Cow Pose

Ardha Baddha Padma Bitilasana

(UHR-duh PUHD-muh bee-til-AHS-uh-nuh)

Also Known As: Half Bound Lotus Table Pose Modification (Ardha Baddha Padma Bharmanasana)
Modification: forearm to the floor
Pose Type: standing (on forearms and knees), binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व ॐ



Revolved Half Lotus Cow Pose

Parivritta Ardha Padma Bitilasana

(puh-ri-VRIT-uh UHR-duh PUHD-muh bee-til-AHS-uh-nuh)

Also Known As: Revolved Half Lotus Table Pose Modification (Parivritta Ardha Padma Bharmanasana)
Modification: forearm on the floor, top arm up to the sky
1. back view
2. front view
Pose Type: standing (on forearms and knees), twist
Drishti Point: Hastagrai or Hastagre (hands)

1.



2.



PLANK POSE: ON THE FINGERTIPS & ARMS CROSSED

Extended Four Limbs Staff Pose

Utthita Chaturanga Dandasana

(UT-ti-tuh chuh-tur-UHNG-guh-uh duhn-DAHS-uh-nuh)

Also Known As: High Plank
Modification: on the fingertips
Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)



Extended Four Limbs Staff Pose

Utthita Chaturanga Dandasana

(UT-ti-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: High Plank
Modification: arms crossed
1. knees on the floor
2. knees off the floor
Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)

1.

2.

PLANK POSE: LEG MODIFICATIONS

Extended Four Limbs Staff Pose

Utthita Chaturanga Dandasana

(UT-ti-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: High Plank Modification
Modification: 1. knees on the floor
2. knees off the floor
Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)

1.





One-Legged Extended Four Limbs Staff Pose

Eka Pada Utthita Chaturanga Dandasana

(EY-kuh PUH-duh UT-ti-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: One-Legged High Plank Modification
Modification: knee to the nose
Pose Type: arm balance, forward bend, core
Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)
ल व र ह ॐ



One-Legged Extended Four Limbs Staff Pose

Eka Pada Utthita Chaturanga Dandasana

(EY-kuh PUH-duh UT-ti-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: One-Legged High Plank Modification
Modification: knee to the shoulder on the same side
Pose Type: arm balance, forward bend, core
Drishti Point: Nasagrai or Nasagre (nose)
ल व र



One-Legged Extended Four Limbs Staff Pose

Eka Pada Utthita Chaturanga Dandasana

(EY-kuh PUH-duh UT-ti-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: One-Legged High Plank Modification
Modification: foot wrapping around the calf muscle
Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)



Revolved Extended Four Limbs Staff Pose

Parivritta Utthita Chaturanga Dandasana

(puh-ri-VRIT-tuh UT-ti-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: Revolved High Plank Modification
Pose Type: arm balance, twist, core
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



PLANK POSE: ARM AND LEG MODIFICATIONS

One-Legged Extended Four Limbs Staff Pose

Eka Pada Utthita Chaturanga Dandasana

(EY-kuh PUH-duh UT-ti-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: One-Legged High Plank Modification
Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)



One Hand Extended Four Limbs Staff Pose

Eka Hasta Utthita Chaturanga Dandasana

(EY-kuh HUH-stuh UT-ti-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: One Hand High Plank Modification
Pose Type: arm balance, core
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs), Nasagrai or Nasagre (nose)



One Hand Extended Four Limbs Staff Pose

Eka Hasta Utthita Chaturanga Dandasana

(EY-kuh HUH-stuh UT-ti-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: One Hand High Plank Modification
Modification: hand to the heart
Pose Type: arm balance, core
Drishti Point: Angushtamadhye or Angushtha Ma Dyai (thumbs), Nasagrai or Nasagre (nose)



One Leg One Hand Extended Four Limbs Staff Pose

Eka Pada Eka Hasta Utthita Chaturanga Dandasana

(EY-kuh PUH-duh EY-kuh HUH-stuh UT-ti-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: One Hand High Plank Modification
Pose Type: arm balance, core
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs), Nasagrai or Nasagre (nose)



Tree Pose in One-Legged Extended Four Limbs Staff Pose

Vrikshasana in Eka Pada Utthita Chaturanga Dandasana

(vrik-SHAHS-uh-nuh in EY-kuh PUH-duh UT-ti-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: Tree Pose in One-Legged High Plank Modification
Modification: 1. knees on the floor
2. knees off the floor
Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)


1.


2.

Extended Four Limbs Staff Pose

Utthita Chaturanga Dandasana

(UT-ti-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: High Plank Modification
Modification: arms extended to the front, tops of the feet on the floor
1. knees on the floor
2. knees off the floor
Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)





PLANK POSE: TWISTS

Leg to the Side Revolved One Hand Extended Four Limbs Staff Pose

Parshva Pada Parivritta Eka Hasta Utthita Chaturanga Dandasana

(PAHRSH-vuh PUH-duh puh-ri-VRIT-tuh EY-kuh HUH-stuh UT-ti-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: Leg to the Side Revolved One Hand High Plank Modification
Modification: 1. back knee on the floor
2. back knee off the floor, knee bent
3. back knee off the floor, both legs straight
4. back knee off the floor, knee bent, toes of the straight leg pointed
Pose Type: arm balance, twist, core

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)

ल व य

1.



2.



3.



4.



Revolved One Hand Extended Four Limbs Staff Pose

Parivritta Eka Hasta Utthita Chaturanga Dandasana

(puh-ri-VRIT-tuh EY-kuh HUH-stuh UT-ti-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: Revolved One Hand High Plank Modification
Modification: 1. knees on the floor
2. knees off the floor
Pose Type: arm balance, twist, core
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)





Revolved Leg to the Side Extended Four Limbs Staff Pose

Parivritta Parshva Pada Utthita Chaturanga Dandasana

(puh-ri-VRIT-tuh PAHRSH-vuh PUH-duh UT-ti-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: Revolved Leg to the Side High Plank Modification
Modification: leg sweeping under the torso
Pose Type: arm balance, twist, core
Drishti Point: Nasagrai or Nasagre (nose)



PLANK POSE: ONE LEG TO THE SIDE

Leg to the Side Extended Four Limbs Staff Pose

Parshva Pada Utthita Chaturanga Dandasana

(PAHRSH-vuh PUH-duh UT-ti-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: Leg to the Side High Plank Modification
Modification: 1. back knee on the floor
2. back knee off the floor
Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)

1.



2.



Upward One Leg to the Side Extended Four Limbs Staff Pose

Urdhva Parshva Eka Pada Utthita Chaturanga Dandasana

(OORD-vuh PAHRSH-vuh EY-kuh PUH-duh UT-ti-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: Leg to the Side One-Legged High Plank Modification
Modification: back knee off the floor, other leg off the floor
Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)



PLANK ON FOREARMS

Staff Pose Dedicated to Makara

Makara Dandasana

(MUH-kuh-ruh duhn-DAHS-uh-nuh)

Also Known As: Dolphin Plank Modification
Pose Type: forearm balance, core
Drishti Point: Nasagrai or Nasagre (nose), Angushtamadhye or Angushta Ma Dyai (thumbs)



One Hand Staff Pose Dedicated to Makara

Eka Hasta Makara Dandasana

(EY-kuh HUH-stuh MUH-kuh-ruh duhn-DAHS-uh-nuh)

Also Known As: One Hand Dolphin Plank Modification
Pose Type: forearm balance, core
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



One-Legged Staff Pose Dedicated to Makara

Eka Pada Makara Dandasana

(EY-kuh PUH-duh MUH-kuh-ruh duhn-DAHS-uh-nuh)

Also Known As: One-Legged Dolphin Plank Modification
Pose Type: forearm balance, core
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



PLANK ON ELBOW

Uneven Repose Staff Pose

Vishama Sayana Dandasana

(VISH-uh-muh SHUH-yuh-nuh duhn-DAHS-uh-nuh)

Also Known As: Uneven Elbow Plank Pose Modification

Modification: one hand to the face, one forearm to the floor

Pose Type: forearm/elbow balance, core

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Repose Staff Pose

Sayana Dandasana

(SHUH-yuh-nuh duhn-DAHS-uh-nuh)

Also Known As: Elbow Plank

Pose Type: elbow balance, core

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Leg Position of One-Legged King Pigeon 1 Version B in Repose Staff

Pose

Pada Eka Pada Raja Kapotasana 1B in Sayana Dandasana

(PUH-duh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh in SHUH-yuh-nuh duhn-DAHS-uh-nuh)

Pose Type: elbow balance, mild backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



PLANK ON FOREARMS: TWIST

Revolved One Hand Staff Pose Dedicated to Makara

Parivritta Eka Hasta Makara Dandasana

(puh-ri-VRIT-tuh EY-kuh HUH-stuh MUH-kuh-ruh duhn-DAHS-uh-nuh)

Also Known As: Revolved Dolphin Plank Modification

Modification: 1 & 2. knees on the floor, front and back view

3 & 4. knees off the floor, front and back view

Pose Type: forearm balance, twist, core

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



2.



3.



4.



PLANK ON FOREARMS: UNEVEN LEG AND ARM POSITIONS

Uneven Staff Pose Dedicated to Makara

Vishama Makara Dandasana

(VISH-uh-muh MUH-kuh-ruh duhn-DAHS-uh-nuh)

Also Known As: Uneven Dolphin Plank Modification
Modification: one elbow bent at 90 degrees, other forearm to the floor, knees on the floor
Pose Type: arm/forearm balance, core
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Hand to the Leg Sideways Uneven Legs Staff Pose Dedicated to Makara

Hasta Pada Parshva Vishama Pada Makara Dandasana

(HUH-stuh PUH-duh PAHRSH-vuh VISH-uh-muh PUH-duh MUH-kuh-ruh duhn-DAHS-uh-nuh)

Also Known As: Hand to the Leg Sideways Dolphin Plank Modification
Pose Type: forearm balance, twist, core
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Uneven Staff Pose Dedicated to Makara

Vishama Makara Dandasana

(VISH-uh-muh MUH-kuh-ruh duhn-DAHS-uh-nuh)

Also Known As: Uneven Dolphin Plank Modification
Modification: one elbow bent at 90 degrees, other forearm to the floor, knees off the floor 1. left forearm on the floor, right arm at 90 degrees
2. right forearm on the floor, left arm at 90 degrees
Pose Type: arm/forearm balance, core
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)

1.



2.



FOUR LIMBED STAFF POSE: KNEES ON THE FLOOR

Four Limbed Staff Pose

Chaturanga Dandasana

(chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Modification: knees on the floor
Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)



One Hand Four Limbed Staff Pose

Eka Hasta Chaturanga Dandasana

(EY-kuh HUH-stuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Modification: knees on the floor
1. starting position
2. end position

Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)





Lion Pose Dedicated to an Avatar of Lord Vishnu in Four Limbed Staff Pose

Narasimhasana in Chaturanga Dandasana

(nuh-ruh-sim-HAHS-uh-nuh in chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Also Known As: Lion Pose (Simhasana)
Modification: 1. on the fingertips
2. on the fists
Pose Type: arm balance, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Leg Position of One-Legged King Pigeon 1 Version B in Four Limbed Staff Pose

Pada Eka Pada Raja Kapotasana 1 B in Chaturanga Dandasana

(PUH-duh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh in chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Modification: bottom knee bent and on the floor; top leg straight—knee resting on the sole of the bottom foot
Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)



Four Limbed Staff Pose

Chaturanga Dandasana

(chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)



Crocodile Pose

Nakrasana

(nuh-KRAHS-uh-nuh)

Modification: feet and hands off the floor and up in the air
Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)



Revolved Four Limbed Staff Pose

Parivritta Chaturanga Dandasana

(puh-ri-VRIT-tuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Pose Type: arm balance, twist, core
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
लं



One-Legged Four Limbed Staff Pose

Eka Pada Chaturanga Dandasana

(EY-kuh PUH-duh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Pose Type: arm balance, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)
लं वं हं ॐ



Upward One Leg to the Side Four Limbed Staff Pose

Urdhva Parshva Eka Pada Chaturanga Dandasana

(OORD-vuh PAHRSH-vuh EY-kuh PUH-duh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Pose Type: arm balance, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



FOUR LIMBED STAFF POSE: KNEE TO THE ARM

One-Legged Four Limbed Staff Pose

Eka Pada Chaturanga Dandasana

(EY-kuh PUH-duh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Modification: knee to the forearm
Pose Type: arm balance, forward bend, core
Drishti Point: Nasagrai or Nasagre (nose)



One-Legged Four Limbed Staff Pose

Eka Pada Chaturanga Dandasana

(EY-kuh PUH-duh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Modification: knee on top of the tricep
Pose Type: arm balance, forward bend, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



FOUR LIMBED STAFF POSE: ONE ARMED

One Hand Four Limbed Staff Pose

Eka Hasta Chaturanga Dandasana

(EY-kuh HUH-stuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Modification: hand to the heart
Pose Type: arm balance, core
Drishti Point: Hastagrai or Hastagre (hands) or Nasagrai or Nasagre (nose)



Hand to the Side Four Limbed Staff Pose

Parshva Hasta Chaturanga Dandasana

(PAHRSH-vuh HUH-stuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Modification: 1. knees on the floor
2. knees off the floor
Pose Type: arm balance, core
Drishti Point: Hastagrai or Hastagre (hands) or Nasagrai or Nasagre (nose)





One Hand to the Side Four Limbed Staff Pose

Parshva Eka Hasta Chaturanga Dandasana

(PAHRSH-vuh EY-kuh HUH-stuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Modification: one knee on the floor, other knee off the floor
Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)



One Hand to the Side Four Limbed Staff Pose

Parshva Eka Hasta Chaturanga Dandasana

(PAHRSH-vuh EY-kuh HUH-stuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Modification: knees off the floor

Pose Type: arm balance, core

Drishti Point: Nasagrai or Nasagre (nose)



One Hand to the Side One-Legged Four Limbed Staff Pose

Parshva Eka Hasta Eka Pada Chaturanga Dandasana

(PAHRSH-vuh EY-kuh HUH-stuh EY-kuh PUH-duh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Modification: one knee on the floor

Pose Type: arm balance, core

Drishti Point: Hastagrai or Hastagre (hands)



FOUR LIMBED STAFF POSE: PUSH UPS

Diamond Four Limbed Staff Pose

Vajra Chaturanga Dandasana

(VAHJ-ruh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Modification: knees on the floor
1. start position
2. end position
Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)





Diamond Four Limbed Staff Pose

Vajra Chaturanga Dandasana

(VAHJ-ruh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Modification: knees off the floor
1. start position
2. end position
Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)





Hands Spread Wide Four Limbed Staff Pose

Prasarita Hasta Chaturanga Dandasana

(pruh-SAH-ri-tuh HUH-stuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Modification: knees on the floor
1. start position
2. end position
Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose)





Hands Spread Wide Four Limbed Staff Pose

Prasarita Hasta Chaturanga Dandasana

(pruh-SAH-ri-tuh HUH-stuh chuh-tur-UHNG-guh duhn-DAHS-uh-nuh)

Modification: knees off the floor

1. start position
2. end position

Pose Type: arm balance, core

Drishti Point: Nasagrai or Nasagre (nose)





SIDE PLANK: TOP LEG CROSSED OVER

Pose Dedicated to Sage Vasistha

Vasisthasana

(vuh-sish-TAHS-uh-nuh)

Also Known As: Side Plank Modification
Modification: top leg crossing over
1. arm alongside of the torso
2. arm extended up
Pose Type: arm balance, core
Drishti Point: Nasagrai or Nasagre (nose), Angushtamadhye or Angushta Ma Dyai (thumbs)



1.



2.

Pose Dedicated to Sage Vasistha

Vasisthasana

(vuh-sish-TAHS-uh-nuh)

Also Known As: Side Plank Modification
Modification: bottom knee to the floor
1. arm alongside of the torso
2. arm extended up
Pose Type: arm balance, core
Drishti Point: Angushtamadhye or Angushtha Ma Dyai (thumbs)





Pose Dedicated to Sage Vasishta

Vasishtasana

(vuh-sish-TAHS-uh-nuh)

Also Known As: Side Plank Modification

Modification: both knees bent, shin of the top leg on the inside of the knee of the bottom leg

1. bottom leg bent at 90 degrees
2. bottom leg slightly bent

Pose Type: arm balance, core

Drishti Point: Urdhva or Antara Drishti (up to the sky)





SIDE PLANK: LEGS STRAIGHT

Pose Dedicated to Sage Vasishta

Vasishtasana

(vuh-sish-TAHS-uh-nuh)

Also Known As: Side Plank Modification
Modification: both legs straight
1. arm alongside of the torso
2. arm extended up
Pose Type: arm balance, core
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)





SIDE PLANK: BOTTOM LEG OFF THE FLOOR

Revolved Pose Dedicated to Sage Vasistha

Parivritta Vasisthasana

(puh-ri-VRIT-tuh vuh-sish-TAHS-uh-nuh)
Also Known As: Revolved Side Plank Modification
Modification: bottom knee bent, foot resting on the thigh of the top leg; the wrist of the top arm to the knee of the bottom leg
Pose Type: arm balance, twist, forward bend, core
Drishti Point: Hastagrai or Hastagre (hands)
लं वं



Revolved Leg to the Side Pose Dedicated to Sage Vasistha

Parivritta Parshva Pada Vasisthasana

(puh-ri-VRIT-tuh PAHRSH-vuh PUH-duh vuh-sish-TAHS-uh-nuh)
Also Known As: Revolved Leg to the Side Plank Modification
Modification: both legs straight, bottom foot lifted off the floor, leg crossing over in front of the body
Pose Type: arm balance, twist, core
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs), Padayoragrai or Padayoragre

(toes/feet)



Hand to Foot Pose Dedicated to Sage Vasistha

Hasta Pada Vasisthasana

(HUH-stuh PUH-duh vuh-sish-TAHS-uh-nuh)

Also Known As: Hand to Foot Side Plank Modification

Modification: both legs straight; bottom leg crossing over in front of the body, foot in line with the center of the chest

Pose Type: arm balance, forward bend, core

Drishti Point: Padayoragrai or Padayoragre (toes/feet)



SIDE PLANK: FOOT TO THE THIGH & HALF LOTUS

Tree Pose in Pose Dedicated to Sage Vasista

Vrikshasana in Vasishtasana

(vrik-SHAHS-uh-nuh in vuh-sish-TAHS-uh-nuh)

Also Known As: Tree Pose in Side Plank Modification

Modification: top foot to the inner thigh
Pose Type: arm balance, core
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Half Lotus Pose in Pose Dedicated to Sage Vasishta

Ardha Padmasana in Vasishtasana

(UHR-duh puhd-MAHS-uh-nuh in vuh-sish-TAHS-uh-nuh)

Also Known As: Half Lotus Pose in Side Plank Modification
Modification: bottom knee on the floor
Pose Type: arm balance, core
Drishti Point: Hastagrai or Hastagre (hands)



SIDE PLANK: TOP LEG OFF THE FLOOR

One Big Toe Pose Dedicated to Sage Vasishta

Eka Padangushta Vasisthasana

(EY-kuh puhd-ahng-GOOSH-tuh vuh-sish-TAHS-uh-nuh)

Also Known As: Big Toe Side Plank Modification
Modification: 1. bottom knee on the floor—leg bent, toes pointing to the back; on the fingertips
2. bottom knee off the floor; palm flat to the floor
Pose Type: arm balance, forward bend, core
Drishti Point: Urdhva or Antara Drishti (up to the sky), Padayoragrai or Padayoragre (toes/feet)





VISHVAMITRA’S POSE

Pose Dedicated to Vishvamitra

Vishvamitrasana

(vish-vuh-mi-TRAHS-uh-nuh)

Modification: knee on the floor, grabbing onto the outside edge of the foot
Pose Type: arm balance, side bend, twist, core
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Pose Dedicated to Vishvamitra

Vishvamitrasana

(vish-vuh-mi-TRAHS-uh-nuh)

Modification: arm alongside of the torso
Pose Type: arm balance, core
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Pose Dedicated to Vishvamitra

Vishvamitrasana

(vish-vuh-mi-TRAHS-uh-nuh)

Modification: knee off the floor, top arm straight and extended up to the sky
Pose Type: arm balance, side bend, core
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Pose Dedicated to Vishvamitra

Vishvamitrasana

(vish-vuh-mi-TRAHS-uh-nuh)

Modification: knee off the floor
1. grabbing onto the outside edge of the top foot
2. grabbing onto the ankle of the top leg
Pose Type: arm balance, side bend, twist, core
Drishti Point: Urdhva or Antara Drishti (up to the sky)
ल व र य

1.



2.



KALA BHAIRAVA’S POSE

Pose Dedicated to Shiva the Destroyer

Kala Bhairavasana

(KAH-luh beye-ruh-VAHS-uh-nuh)

Modification: 1. arm extended up
2. top hand to the inside of the bottom thigh
Pose Type: arm balance, core
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs), Padayoragrai or Padayoragre (toes/feet)





SIDE PLANK: TOP LEG OVERHEAD GRIP

Partridge Pose

Kapinjalasana

(kuh-pinj-uh-LAHS-uh-nuh)

Modification: overhead grip
1. bottom knee on the floor
2. bottom knee off the floor
Pose Type: arm balance, backbend, core

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

1.



2.



SIDE PLANK ON FOREARMS: KNEES ON THE FLOOR

Pose Dedicated to Sage Vasishta

Vasishtasana

(vuh-sish-TAHS-uh-nuh)

Also Known As: Dolphin Side Plank Modification
Modification: forearm on the floor, both knees to the floor
1. arm up to the sky
2. arm alongside the torso
Pose Type: forearm balance, core
Drishti Point: 1. Angushtamadhye or Angushta Ma Dyai (thumbs)
2. Nasagrai or Nasagre (nose)

1.



2.



SIDE PLANK ON FOREARMS: KNEES OFF THE FLOOR

Pose Dedicated to Sage Vasishta

Vasishtasana

(vuh-sish-TAHS-uh-nuh)

Also Known As: Dolphin Side Plank Modification
Modification: forearm on the floor, arm crossed over in front of the chest, looking down
Pose Type: forearm balance, twist, core
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Pose Dedicated to Sage Vasishta

Vasishtasana

(vuh-sish-TAHS-uh-nuh)

Also Known As: Dolphin Side Plank Modification
Modification: forearm on the floor, top hand on the hip
Pose Type: forearm balance, core
Drishti Point: Nasagrai or Nasagre (nose)
🔴



Pose Dedicated to Sage Vasistha

Vasishtasana

(vuh-sish-TAHS-uh-nuh)

Also Known As: Dolphin Side Plank Modification
Modification: forearm on the floor, top arm up to the sky
Pose Type: forearm balance, core
Drishti Point: Hastagrai or Hastagre (hands)
🔴 🟢



Pose Dedicated to Sage Vasishta

Vasishtasana

(vuh-sish-TAHS-uh-nuh)

Also Known As: Dolphin Side Plank Modification

Modification: forearm on the floor, top hand to the back of the head

Pose Type: forearm balance, core

Drishti Point: Nasagrai or Nasagre (nose)



SIDE PLANK ON FOREARMS: ONE LEG CROSSED OVER

Pose Dedicated to Sage Vasishta

Vasishtasana

(vuh-sish-TAHS-uh-nuh)

Also Known As: Dolphin Side Plank Modification

Modification: forearm on the floor; top leg crossed over, foot flat on the floor; top hand by the bottom hip socket

Pose Type: forearm balance, core

Drishti Point: Urdhva or Antara Drishti (up to the sky)



Pose Dedicated to Sage Vasishta

Vasishtasana

(vuh-sish-TAHS-uh-nuh)

Also Known As: Dolphin Side Plank Modification

Modification: forearm on the floor; top leg crossed over, heel lifted; top arm extended up to the sky

Pose Type: forearm balance, core

Drishti Point: Hastagrai or Hastagre (hands)



Pose Dedicated to Sage Vasishta

Vasishtasana

(vuh-sish-TAHS-uh-nuh)

Also Known As: Dolphin Side Plank Modification

Modification: forearm on the floor; top leg crossed over, foot flat on the floor, bottom leg lifted off the floor, top hand on the hip

Pose Type: forearm balance, core

Drishti Point: Urdhva or Antara Drishti (up to the sky)



Half Lotus Pose in Pose Dedicated to Sage Vasishta

Ardha Padmasana in Vasishtasana

(UHR-duh puhd-MAHS-uh-nuh in vuh-sish-TAHS-uh-nuh)

Also Known As: Half Lotus Pose in Dolphin Side Plank Modification

Modification: forearm on the floor, top arm extended up to the sky

Pose Type: forearm balance, core

Drishti Point: Hastagrai or Hastagre (hands)



SIDE PLANK ON FOREARMS: TOP LEG LIFTED

Pose Dedicated to Sage Vasishta

Vasishtasana

(vuh-sish-TAHS-uh-nuh)

Also Known As: Dolphin Side Plank Modification

Modification: forearm on the floor; top knee toward the top elbow, bottom knee on the floor; leg bent, toes pointing to the back

Pose Type: forearm balance, forward bend, core

Drishti Point: Hastagrai or Hastagre (hands)



Pose Dedicated to Sage Vasishta

Vasishtasana

(vuh-sish-TAHS-uh-nuh)

Also Known As: Dolphin Side Plank Modification
Modification: forearm on the floor; top knee toward the top elbow; bottom leg straight, knee off floor
Pose Type: forearm balance, forward bend, core
Drishti Point: Hastagrai or Hastagre (hands)



One Big Toe Pose Dedicated to Sage Vasishta

Eka Padangushta Vasishtasana

(EY-kuh puhd-ahng-GOOSH-tuh vuh-sish-TAHS-uh-nuh)

Also Known As: Big Toe Dolphin Side Plank Modification
Modification: forearm on the floor
1. knee bent
2. leg straight
Pose Type: forearm balance, forward bend, core
Drishti Point: Padayoragrai or Padayoragre (toes/feet)

1.



2.



SIDE PLANK ON FOREARMS: BOTTOM LEG LIFTED

Revolved Leg to the Side Pose Dedicated to Sage Vasishta

Parivritta Parshva Pada Vasishtasana

(puh-ri-VRIT-tuh PAHRSH-vuh PUH-duh vuh-sish-TAHS-uh-nuh)

Also Known As: Revolved Leg to the Side Dolphin Side Plank Modification
Modification: forearm on the floor; both legs straight, bottom leg lifted in front of the body
Pose Type: forearm balance, twist, core
Drishti Point: Hastagrai or Hastagre (hands)



Revolved Pose Dedicated to Sage Vasishta

Parivritta Vasishtasana

(puh-ri-VRIT-tuh vuh-sish-TAHS-uh-nuh)

Also Known As: Revolved Dolphin Side Plank Modification

Modification: forearm on the floor; bottom knee bent, foot resting on the thigh of the top leg; the elbow of the top arm to the knee of the bottom leg

Pose Type: forearm balance, forward bend, twist, core

Drishti Point: Urdhva or Antara Drishti (up to the sky)

ल व र



SIDE PLANK ON FOREARMS: TOP LEG UNDER-HEAD GRIP

Partridge Pose

Kapinjalasana

(kuh-pinj-uh-LAHS-uh-nuh)

Modification: forearm on the floor, under-head grip:

1. knee on the floor
2. knee off the floor

Pose Type: forearm balance, backbend, core

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व य ह ॐ

1.



2.



SIDE PLANK ON FOREARMS: HALF LOTUS & LOTUS

Half Lotus Pose in Pose Dedicated to Sage Vasistha

Ardha Padmasana in Vasishtasana

(UHR-duh puhd-MAHS-uh-nuh in vuh-sish-TAHS-uh-nuh)

Also Known As: Half Lotus Dolphin Side Plank Modification

Modification: forearm on the floor, bottom leg in half lotus, top knee bent, toes to the floor

Pose Type: forearm balance, core

Drishti Point: Hastagrai or Hastagre (hands)

ल व य ह



Half Lotus One Big Toe Pose Dedicated to Sage Vasistha

Ardha Padma Eka Padangushta Vasisthasana

(UHR-duh PUHD-muh EY-kuh puhd-ahng-GOOSH-tuh vuh-sish-TAHS-uh-nuh)

Also Known As: Half Lotus Big Toe Dolphin Side Plank Modification
Modification: forearm on the floor
Pose Type: forearm balance, forward bend, core
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Urdhva or Antara Drishti (up to the sky)
लं वं यं हं



Half Lotus Half Bow Pose in Pose Dedicated to Sage Vasishta

Ardha Padma Dhanurasana in Vasishtasana

(UHR-duh PUHD-muh duh-nur-AHS-uh-nuh in vuh-sish-TAHS-uh-nuh)

Also Known As: Half Lotus Half Bow Pose in Dolphin Side Plank Modification
Modification: forearm on the floor, bottom leg in half lotus, grabbing onto the top foot with under-head grip
Pose Type: forearm balance, backbend, core
Drishti Point: Hastagrai or Hastagre (hands)
लं वं रं यं



Lotus Pose in Pose Dedicated to Sage Vasishta

Padmasana in Vasisthasana

(puhd-MAHS-uh-nuh in vuh-sish-TAHS-uh-nuh)

Also Known As: Lotus Pose in Dolphin Side Plank Modification
Modification: forearm on the floor
Pose Type: forearm balance, core
Drishti Point: Hastagrai or Hastagre (hands)



SIDE PLANK ON THE ELBOWS

Pose Dedicated to Sage Vasishta

Vasishtasana

(vuh-sish-TAHS-uh-nuh)

Also Known As: Elbow Side Plank Modification
Modification: on the elbow; both legs straight, ankles crossed
Pose Type: elbow balance, core
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Pose Dedicated to Sage Vasishta

Vasishtasana

(vuh-sish-TAHS-uh-nuh)

Also Known As: Elbow Side Plank Modification

Modification: on the elbow; bottom leg straight; top leg crossed over, foot flat on the floor; fingertips of the top arm to the floor in front of the body

Pose Type: elbow balance, core

Drishti Point: Urdhva or Antara Drishti (up to the sky)



Pose Dedicated to Sage Vasishta

Vasishtasana

(vuh-sish-TAHS-uh-nuh)

Also Known As: Elbow Side Plank Modification

Modification: on the elbow, top foot to the side of the bottom leg

Pose Type: elbow balance, core

Drishti Point: Nasagrai or Nasagre (nose)



Half Lotus Pose in Pose Dedicated to Sage Vasistha

Ardha Padmasana in Vasisthasana

(UHR-duh puhd-MAHS-uh-nuh in vuh-sish-TAHS-uh-nuh)

Also Known As: Half Lotus Pose in Elbow Side Plank Modification
Modification: on the elbow
Pose Type: elbow balance, core
Drishti Point: Hastagrai or Hastagre (hands)



Backbends

COW FACE POSE AND GARUDA ON KNEES

KNEES ON THE FLOOR

BACKBEND ON THE KNEES

BACKBEND

UPWARD BOW POSE

WILD THING POSE

Pose Dedicated to Garuda on the Knees

Janu Garudasana

(JAH-nu guh-ru-DAHS-uh-nuh)

Pose Type: standing (on the knees), backbend

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Leg Position of Cow Face Pose in Camel Pose

Pada Gomukhasana in Ushtrasana*

(PUH-duh go-moo-KAHS-uh-nuh in oosh-TRAHS-uh-nuh)

Modification: Gomukhasana legs modification

Pose Type: backbend, standing (on the knees)

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



KNEES ON THE FLOOR: LOTUS POSE

Half Pose Dedicated to Siddhar Kamalamuni

Ardha Kamalamunyasana

(UHR-duh KUH-muh-luhmoo-nyAHS-uh-nuh)

Also Known As: Upward Facing Lotus Pose (Urdhva Mukha Padmasana)
Modification: fingertips pointing to the back, thumbs pointing to the front, knees close to the hands
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



ONE KNEE TO THE FLOOR: ONE LEG BENT & ONE LEG STRAIGHT UP TO THE SKY

One-Legged Camel Pose

Eka Pada Ushtrasana

(EY-kuh PUH-duh oosh-TRAHS-uh-nuh)

Modification: Leg 1: knee to the floor Leg 2: foot to the floor in semi-lunge position
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged Camel Pose

Eka Pada Ushtrasana

(EY-kuh PUH-duh oosh-TRAHS-uh-nuh)

Modification: Leg 1: knee to the floor
Leg 2: sole of the foot to the quadricep
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



Extended Hand to Big Toe Pose in Half Camel Pose

Utthita Hasta Padangushtasana in Ardha Ushtrasana

(UT-ti-tuh HUH-stuh puhd-AHNG-goosh-TAHS-uh-nuh in UHR-duh oosh-TRAHS-uh-nuh)

Modification: 1. toes pointed to the back
2. toes curled in
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ





KNEES TO THE FLOOR: BACKBEND

Camel Pose Prep.

Ushtrasana Prep.

(oosh-TRAHS-uh-nuh)

Modification: 1. hands to the lower back
2. hands in Anjali Mudra (Hands in Prayer)
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ





Upward Salute Pose in Camel Pose

Urdhva Hastasana in Ushtrasana

(OORD-vuh huh-STAHS-uh-nuh in oosh-TRAHS-uh-nuh)

Also Known As: Pigeon Pose Prep. (Kapotasana Prep.)
Modification: palms together
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Angushtamadhye or Angushta Ma Dyai (thumbs)



Raised Bound Hands in Camel Pose

Urdhva Baddha Hastasana in Ushtrasana

(OORD-vuh BUH-duh huh-STAHS-uh-nuh in oosh-TRAHS-uh-nuh)

Modification: 1. hips pushed back
2. hips pushed forward
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

1.



2.



KNEES ON THE FLOOR: BACKBEND—HANDS TO THE HEELS AND TO THE FLOOR

Camel Pose

Ushtrasana

(oosh-TRAHS-uh-nuh)

Modification: 1. grabbing onto both ankles
2. palms to the heels, fingertips pointing to the back
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

1.



2.



Pose Dedicated to King Nahusha

Nahushasana

(nuh-hu-SHAHS-uh-nuh)

Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One Hand Graceful Thunderbolt Pose

Eka Hasta Laghuvajrasana

(EY-kuh huh-stuh luh-gu-vuhj-RAHS-uh-nuh)

Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Pigeon Pose

Kapotasana

(kuh-po-TAHS-uh-nuh)

Also Known As: Sage Korakar Pose (Korakarasana), Graceful Thunderbolt Pose (Laghuvajrasana)
Modification: arms over the head, palms to the floor, feet toward the head
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



KNEES ON THE FLOOR: ONE ARM EXTENDED

Half Camel Pose

Ardha Ushtrasana

(UHR-duh oosh-TRAHS-uh-nuh)
Also Known As: One Arm Camel Pose (Eka Hasta Ustrasana)
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Hastagrai or Hastagre (hands)



Half Camel Pose

Ardha Ushtrasana

(UHR-duh oosh-TRAHS-uh-nuh)

Modification: arm crossed behind the back to the opposite leg

1. hand to the outside of the hip
2. hand to the inside of the knee

Pose Type: backbend, standing (on the knees)

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Hastagrai or Hastagre (hands)

ल र य ह ॐ

1.



2.



Leg Position of the Pose Dedicated to Garuda in Half Camel Pose

Pada Garudasana in Ardha Ushtrasana

(PUH-duh guh-ru-DAHS-uh-nuh in UHR-duh oosh-TRAHS-uh-nuh}

Modification: one hand to the floor; other arm up, elbow bent

Pose Type: backbend, standing (on the knees)

Drishti Point: Hastagrai or Hastagre (hands), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व र य ह ॐ



Half Camel Pose

Ardha Ushtrasana

(UHR-duh-oosh-TRAHS-uh-nuh)

Modification: one foot to the armpit on the same side; opposite arm straight up over the head
Pose Type: backbend, standing (on the knees)
Drishti Point: Hastagrai or Hastagre (hands), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



Half Bound Lotus Camel Pose

Ardha Baddha Padma Ushtrasana

(UHR-duh BUH-duh PUHD-muh oosh-TRAHS-uh-nuh)

Modification: free arm straight up over the head
Pose Type: backbend, standing (on the knees), binding
Drishti Point: Hastagrai or Hastagre (hands) or Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



ONE KNEE BENT TOWARD THE HIP: BACKBEND

One-Legged Frog Pose in Camel Pose

Eka Pada Bhekasana in Ushtrasana

(EY-kuh PUH-duh bey-KAHS-uh-nuh in oosh-TRAHS-uh-nuh)

Pose Type: backbend, standing (on the knees)

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व र य ह ॐ



Mermaid Arm Position in Camel Pose

Hasta Naginyasana in Ushtrasana

(HUH-stuh nuh-gin-YAHS-uh-nuh in oosh-TRAHS-uh-nuh)

Pose Type: backbend, standing (on the knees)

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल र य ह ॐ

BACKBEND ON THE KNEES, HEAD AND SITTING BONES: BED POSE

Bed Pose

Paryankasana

(puhr-yuhng-KAHS-uh-nuh)

Also Known As: Reclined Thunderbolt Pose (Supta Vajrasana)
Modification: 1. head off the floor
2. crown of the head on the floor
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



1.



2.

Bed Pose

Paryankasana

(puhr-yuhng-KAHS-uh-nuh)

Also Known As: Reclined Thunderbolt Pose (Supta Vajrasana)
Modification: 1. hands in Anjali Mudra (Hands in Prayer), fingertips pointing to the sky
2. grabbing onto the forearms, arms to the floor up over the head
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



1.



2.

BACKBEND ON THE KNEES AND HEAD: LITTLE THUNDERBOLT POSE

Little Thunderbolt Pose

Laghuvajrasana

(lluh-goo-vuhj-RAHS-uh-nuh)

Modification: 1. grabbing onto the knees, head off the floor
2. forehead to the floor, hands on the quadriceps
3. head to feet, grabbing onto the knees
Pose Type: backbend, standing (on the knees)

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)


1.


2.


3.

Little Thunderbolt Pose

Laghuvajrasana

(luh-goo-vuhj-RAHS-uh-nuh)

Modification: back of the head on the floor, grabbing onto the knees
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BACKBEND ON THE KNEES AND HEAD: PIGEON POSE

Little Thunderbolt Pose Prep.

Laghuvajrasana Prep.

(luh-goo-vuhj-RAHS-uh-nuh)

Modification: crown of the head to the floor, arms in Headstand 5 (see here) position
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One Hand Pigeon Pose

Eka Hasta Kapotasana

(EY-kuh HUH-stuh kuh-po-TAHS-uh-nuh)

Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Pigeon Pose

Kapotasana

(kuh-po-TAHS-uh-nuh)

Modification: grabbing onto the ankles
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Pigeon Pose

Kapotasana

(kuh-po-TAHS-uh-nuh)

Modification: fingertips toward the knees, palms flat down
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



PIGEON POSE: ONE-LEGGED

One-Legged Pigeon Pose Prep.

Eka Pada Kapotasana Prep.

(EY-kuh PUH-duh kuh-po-TAHS-uh-nuh)

Modification: arms over the head palms to the floor, head away from the foot
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
● ● ● ● ●



One-Legged Pigeon Pose Prep.

Eka Pada Kapotasana Prep.

(EY-kuh PUH-duh kuh-po-TAHS-uh-nuh)

Modification: 1. knee bent, foot to the floor
2. leg straight, foot to the floor
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
● ● ● ● ● ● ●



1.



2.

One-Legged Pigeon Pose

Eka Pada Kapotasana

(EY-kuh PUH-duh kuh-po-TAHS-uh-nuh)

Modification: foot to the quadriceps

Pose Type: backbend, standing (on the knees)

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged Pigeon Pose

Eka Pada Kapotasana

(EY-kuh PUH-duh kuh-po-TAHS-uh-nuh)

Modification: leg straight

Pose Type: backbend, standing (on the knees)

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व र य ह ॐ ॐ



TOES CURLED IN: BACKBEND—SHOULDERS ON THE FLOOR & HEAD ON THE FLOOR

One-Legged Tip Toe Bridge Pose

Eka Pada Prapada Setu Bandhasana

(EY-kuh PUH-duh PRUH-puh-duh SEY-too buhn-DAHS-uh-nuh)

Modification: back of the head on the floor, arms up to the sky

1. knee bent, foot resting on the knee
2. leg straight and extended to the sky

Pose Type: supine, backbend

Drishti Point: Angushtamadhye or Angustha Ma Dyai (thumbs)

ल व र य





Tip Toe Bridge Pose

Prapada Setu Bandhasana

(PRUH-puh-duh SEY-too buhn-DAHS-uh-nuh)

Also Known As: Tip Toe Bed Pose (Prapada Paryankasana), Big Toe Bridge Pose (Padangushta Setu Bandhasana)
Modification: 1. grabbing onto the shins, elbows to the floor
2. grabbing onto the shins, arms straight
3. hands on the quadriceps, arms straight
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)






3.

TOES CURLED IN: BACKBEND—HANDS TO THE FLOOR & TOE BALANCE

Thunderbolt Pose

Vajrasana

(vuhj-RAHS-uh-nuh)

Also Known As: Tip Toe Bed Pose Prep. (Prapada Paryankasana Prep.)
Modification: toes curled in, fingertips pointing away from the feet, intense backbend
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य हं ॐ



Tip Toe Camel Pose

Prapada Ushtrasana

(PRUH-puh-duh oosh-TRAHS-uh-nuh)

Modification: palms flat to the floor, fingertips pointing to the front
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य हं ॐ



Unsupported Tip Toe Camel Pose

Niralamba Prapada Ushtrasana

(neer-AH-luhm-buh PRUH-puh-duh oosh-TRAHS-uh-nuh)

Modification: knees lifted off the floor, hands in Anjali Mudra (Hands in Prayer)
Pose Type: standing, balance, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



TOES CURLED IN: BACKBEND—GRABBING ONTO THE HEELS & KNEES, HANDS ON THE FLOOR & HEAD TO THE HEELS

Tip Toe Camel Pose

Prapada Ushtrasana

(PRUH-puh-duh oosh-TRAHS-uh-nuh)

Modification: hands in Anjali Mudra (Hands in Prayer)
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Tip Toe Camel Pose

Ardha Prapada Ushtrasana

(UHR-duh PRUH-puh-duh oosh-TRAHS-uh-nuh)

Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Hastagrai or Hastagre (hands)

ल र य ह ॐ



Tip Toe Camel Pose

Prapada Ushtrasana

(PRUH-puh-duh oosh-TRAHS-uh-nuh)

Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल र य ह ॐ



Tip Toe Camel Pose

Prapada Ushtrasana

(PRUH-puh-duh oosh-TRAHS-uh-nuh)

Modification: hands on the knees

Pose Type: backbend, standing (on the knees)

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

लं रं यं हं ॐ



Tip Toe Pigeon Pose

Prapada Kapotasana

(PRUH-puh-duh kuh-po-TAHS-uh-nuh)

Also Known As: Big Toe Pigeon Pose (Padangushta Kapotasana)

Modification: arms straight up over the head, palms to the floor

Pose Type: backbend, standing (on the knees)

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Hastagrai or Hastagre (hands)

लं रं यं हं ॐ



Tip Toe Pigeon Pose

Prapada Kapotasana

(PRUH-puh-duh kuh-po-TAHS-uh-nuh)

Also Known As: Big Toe Pigeon Pose (Padangustha Kapotasana), Little Wheel Pose (Laghu Chakrasana)
Modification: arms up over the head, elbows bent, palms to the floor, forehead to the heels
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



TOES CURLED IN: BACKBEND—ARMS STRAIGHT, PALMS TOGETHER

Raised Bound Hands in Tip Toe Camel Pose

Urdhva Baddha Hastasana in Prapada Ushtrasana

(OORD-vuh BUH-duh huh-STAHS-uh-nuh in PRUH-puh-duh oosh-TRAHS-uh-nuh)

Modification: hips pushing back
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Angushtamadhye or Angushta Ma Dyai (thumbs)

Tip Toe Pigeon Pose

Prapada Kapotasana

(PRUH-puh-duh kuh-po-TAHS-uh-nuh)

Also Known As: Big Toe Pigeon Pose (Padangushta Kapotasana), Full Camel Pose (Purna Ushtrasana), or Little Wheel Pose (Laghu Chakrasana)
Modification: 1. arms extended to the sky
2. arms parallel to the floor
Pose Type: backbend, standing (on the knees)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

1.



2.



BACKBEND: HEADSTAND 5 ARM POSITION

Upward Bow Pose in Headstand 5

Urdhva Dhanurasana in Shirshasana 5

(OORD-vuh duh-nur-AHS-uh-nuh in sheer-SHAS-uh-nuh)

Pose Type: backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Upward Bow Pose with Leg Position of the Pose Dedicated to Garuda in Headstand 5

Urdhva Dhanurasana Pada Garudasana in Shirshasana 5

(OORD-vuh duh-nur-AHS-uh-nuh PUH-duh guh-ru-DAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Pose Type: backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Upward Tip Toe Bow Pose in One Hand Headstand 5

Urdhva Prapada Dhanurasana in Eka Hasta Shirshasana 5

(OORD-vuh PRUH-puh-duh duh-nur-AHS-uh-nuh in EY-kuh HUH-stuh sheer-SHAHS-uh-nuh)

Pose Type: backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Inverted Tip Toe Bow Pose

Viparita Prapada Dhanurasana

(vi-puh-REE-tuh PRUH-puh-duh duh-nur-AHS-uh-nuh)

Also Known As: Headstand Bow Pose (Shirsha Dhanurasana)

Pose Type: backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BACKBEND: HEADSTAND 1 ARM POSITION—KNEE/KNEES BENT

Upward Bow Pose in Headstand 1

Urdhva Dhanurasana in Shirshasana 1

(OORD-vuh duh-nur-AHS-uh-nuh in sheer-SHAHS-uh-nuh)

Pose Type: backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

● ● ● ● ●



Upward Tip Toe Bow Pose in Headstand 1

Urdhva Prapada Dhanurasana in Shirshasana 1

(OORD-vuh PRUH-puh-duh duh-noor-AHS-uh-nuh in sheer-SHAHS-uh-nuh)

Pose Type: backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

● ● ● ● ●



One-Legged Inverted Staff Pose

Eka Pada Viparita Dandasana

(EY-kuh PUH-duh vi-puh-REE-tuh duhn-DAHS-uh-nuh)

Modification: knee of the bottom leg bent

Pose Type: backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BACKBEND: HEADSTAND 1 ARM POSITION—LEGS STRAIGHT

One-Legged Inverted Staff Pose

Eka Pada Viparita Dandasana

(EY-kuh PUH-duh vi-puh-REE-tuh duhn-DAHS-uh-nuh)

Also Known As: Inverted Staff Pose B (Viparita Dandasana B)
Modification: both legs straight
Pose Type: backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Two-Legged Inverted Staff Pose

Dwi Pada Viparita Dandasana

(DWI-puh-duh vi-puh-REE-tuh duhn-DAHS-uh-nuh)

Also Known As: Inverted Staff Pose A (Viparita Dandasana A)
Pose Type: backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BACKBEND: FOREARMS ON THE FLOOR, BOUND HANDS

Bound Arms Tip Toe Bound Wheel Pose

Baddha Hasta Prapada Chakra Bandhasana

(BUH-duh HUH-stuh PRUH-puh-duh CHUHK-ruh buhn-DAHS-uh-nuh)

Pose Type: backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Bound Arms Both Legs Inverted Staff Pose

Baddha Hasta Dwi Pada Viparita Dandasana

(BUH-duh HUH-stuh DWI-puh-duh vi-puh-REE-tuh duhn-DAH-suh-nuh)

Pose Type: backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BACKBEND: FOREARMS ON THE FLOOR, HEELS DOWN

Bound Wheel Pose

Chakra Bandhasana

(CHUHK-ruh buhn-DAHS-uh-nuh)

Modification: forearms to the floor, heels down, fingertips touching the heels
Pose Type: backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ



Bound Wheel Pose

Chakra Bandhasana

(CHUHK-ruh buhn-DAHS-uh-nuh)

Also Known As: Bound Wheel Pose (Bandha Chakrasana)
Modification: grabbing onto ankles
1. looking straight ahead
2. head rolling back
Pose Type: backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





BACKBEND: FOREARMS ON THE FLOOR, HEELS LIFTED

Tip Toe Bound Wheel Pose

Prapada Chakra Bandhasana

(PRUH-puh-duh CHUCK-ruh buhn-DAHS-uh-nuh)

Pose Type: backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Uneven Tip Toe Bound Wheel Pose

Vishama Prapada Chakra Bandhasana

(VI-shuh-muh PRUH-puh-duh CHUCK-ruh buhn-DAHS-uh-nuh)

Pose Type: backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ



BACKBEND: FOREARMS ON THE FLOOR, ONE-LEGGED

One-Legged Inverted Staff Pose

Eka Pada Viparita Dandasana

(EY-kuh PUH-duh vi-puh-REE-tuh duhn-DAHS-uh-nuh)

Modification: forearms to the floor, head off the floor
Pose Type: backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



Bound Foot One-Legged Inverted Staff Pose

Baddha Pada Eka Pada Viparita Dandasana

(BUH-duh PUH-duh EY-kuh PUH-duh vi-puh-REE-tuh duhn-DAHS-uh-nuh)

Modification: forearms to the floor, head off the floor

Pose Type: backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व र य ह ॐ



Tip Toe Bound Foot One-Legged Inverted Staff Pose

Prapada Baddha Pada Eka Pada Viparita Dandasana

(PRUH-puh-duh BUH-duh PUH-duh EY-kuh PUH-duh vi-puh-REE-tuh duhn-DAHS-uh-nuh)

Pose Type: backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

How to Perform the Pose:

1. Begin by lying flat on your back. Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing. Inhale and bring your hands under your shoulders with elbows bent and close to your head, with the fingertips pointing away from your head.
2. Exhale and bend your knees, keep your feet flat on the floor and slide your heels toward your sitting bones. Keep your feet in line with your sitting bones and parallel to each other with your toes pointing straight ahead.
3. Exhale as you lift your sitting bones and your back off the floor. Place the crown of your head onto the floor, balancing on your hands, head, and feet.
4. Exhale as you slide your right palm in the direction of your feet until your forearm is flat on the floor. On the next exhale, slide your left palm to meet your right. Interlock your fingers at the back of your head.
5. Exhale and lift your head off the floor.
6. On the next exhale, walk your feet toward your hands. Grab onto your left ankle with both hands.
7. Exhale as you lift your right foot off the floor, keeping your right leg strong and straight with toes pointing up to the sky.
8. Inhale and lift your left heel, coming onto the toes of the left foot, while holding onto the left toes with both hands. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch on the right side.
9. Inhale and lower the left heel to the floor, followed by the right foot. Exhale and grab onto the right ankle with both hands. On the following exhale, lift your left foot off the floor, keeping your left leg strong and straight with toes pointing up to the sky.
10. Inhale and lift your right heel, coming onto the toes of the right foot while holding onto the right toes with both hands. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch on the left side.
11. Inhale and lower your right heel to the floor, followed by your left foot. Exhale and lower your head to the floor. Exhale and tuck your chin to your chest and lower your spine to the floor, coming

out of the pose.

Modification: forearms to the floor, head off the floor

prapada = tip of the feet

baddha = bound

pada = foot or leg

eka = one

pada = foot or leg

viparita = inverted

danda = stick or staff

Foot to the Head One-Legged Inverted Staff Pose

Shirsha Pada Eka Pada Viparita Dandasana

(SHEER-shuh PUH-duh EY-kuh PUH-duh vi-puh-REE-tuh duhn-DAHS-uh-nuh)

Modification: forearms to the floor, head off the floor
Pose Type: backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



UPWARD BOW POSE

Upward Bow Pose

Urdhva Dhanurasana

(OORD-vuh duh-nur-AHS-uh-nuh)

Modification: heels down
Pose Type: backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Tip Toe Upward Bow Pose

Prapada Urdhva Dhanurasana

(PRUH-puh-duh OORD-vuh duh-nur-AHS-uh-nuh)

Pose Type: backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Elevated Both Legs Inverted Staff Pose

Utthita Dwi Pada Viparita Dandasana

(UT-ti-tuh DWI-puh-duh vi-puh-REE-tuh duhn-DAHS-uh-nuh)

Also Known As: Upward Bow Pose (Urdhva Dhanurasana)

Modification: head rolling back

Pose Type: backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Tip Toe One-Legged Upward Bow Pose

Prapada Eka Pada Urdhva Dhanurasana

(PRUH-puh-duh EY-kuh PUH-duh OORD-vuh duh-nur-AHS-uh-nuh)

Pose Type: backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged Upward Bow Pose

Eka Pada Urdhva Dhanurasana

(EY-kuh PUH-duh OORD-vuh duh-nur-AHS-uh-nuh)

Also Known As: Two Limb Upward Bow Pose (Dwi Anga Urdhva Dhanurasana)

Modification: one hand to the thigh

Pose Type: backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Tip Toe One Hand Upward Bow Pose

Prapada Eka Hasta Urdhva Dhanurasana

(PRUH-puh-duh EY-kuh HUH-stuh OORD-vuh duh-nur-AHS-uh-nuh)

Pose Type: backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



WILD THING POSE

Wild Thing Pose

Chamatkarasana

(kuh-muht-kar-AHS-uh-nuh)

Modification: forearm to the floor
Pose Type: backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) or Hastagrai or Hastagre (hands)
See the glossary for a more precise translation of chamatkarasana.



Wild Thing Pose

Chamatkarasana

(kuh-muht-kar-AHS-uh-nuh)

Pose Type: backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) or Hastagrai or Hastagre (hands)



Wild Thing Pose

Chamatkarasana

(kuh-muht-kar-AHS-uh-nuh)

Modification: foot to inside of the thigh
Pose Type: backbend
Drishti Point: Hastagrai or Hastagre (hands)



Wild Thing Pose

Chamatkarasana

(kuh-muht-kar-AHS-uh-nuh)

Modification: grabbing the ankle with overhead grip on the same side
Pose Type: backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) or Hastagrai or Hastagre (hands)



Wild Thing Pose

Chamatkarasana

(kuh-muht-kar-AHS-uh-nuh)

Modification: grabbing the ankle with overhead grip on the same side; other foot off the floor—knee bent
Pose Type: backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) or Hastagrai or



Arm Balances

- LOTUS POSE
- PENDANT POSE
- ONE LEG OVER THE SHOULDER
- CRANE POSE
- FIREFLY POSE
- SCISSOR LEGS
- GARUDA LEGS
- PEACOCK AND SWAN POSES

Half Fire Log Celibate Pose

Ardha Agnistambha Brahmacharyasana

(UHR_duh uhg-ni-STUHM-buh bruh-muh-chahr-YAHS-uh-nuh)

Pose Type: core, arm balance
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



One Leg Over Shoulder Pose

Eka Hasta Bhujasana

(EY-kuh HUH-stuh buj-AHS-uh-nuh)

Also Known As: Comfortable Bird Pose (Sukha Chakorasana)
Pose Type: core, arm balance
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Moonbird Pose

Chakorasana

(chuh-kor-AHS-uh-nuh)

Pose Type: core, arm balance
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
● ● ● ●



ARM BALANCE: LOTUS

Rooster Pose

Kukkutasana

(ku-ku-TAHS-uh-nuh)

Pose Type: arm balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
● ●



Scales Pose

Tolasana

(to-LAHS-uh-nuh)

Modification: 1. fingertips pointing to the back, thumbs pointing to the front
2. palms flat on the floor, fingertips pointing to the front
Pose Type: arm balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)





Pose Dedicated to Sage Galava

Galavasana

(gah-luh-VAHS-uh-nuh)
Modification: 1. hips low
2. hips high
Pose Type: arm balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)

Upward Rooster Pose

Urdhva Kukkutasana

(OORD-vuh ku-ku-TAHS-uh-nuh)

Modification: 1. hips at shoulder height
2. hips higher than the shoulders
Pose Type: arm balance, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Angushtamadhye or Angushta Ma Dyai (thumbs)





Side Rooster Pose

Parshva Kukkutasana

(PAHRSH-vuh ku-ku-TAHS-uh-nuh)

Also Known As: Revolved Rooster Pose (Parivritta Kukkutasana), Wounded Rooster Pose (Pungu Kukkutasana)
Modification: 1. elbows bent
2. arms straight
Pose Type: arm balance, forward bend, twist
Drishti Point: Nasagrai or Nasagre (nose)
लं वं रं हं





Pendant Pose

Lolasana

(lo-LAHS-uh-nuh)

Modification: ankles crossed
Pose Type: arm balance, forward bend, core
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs) or Nasagrai or Nasagre (nose)



Pendant Pose

Lolasana

(lo-LAHS-uh-nuh)

Pose Type: arm balance, forward bend, core

Drishti Point: Angusthamadhye or Angustha Ma Dyai (thumbs) or Nasagrai or Nasagre (nose)

How to Perform the Pose:

1. Begin by sitting on the floor with both your legs straight out in front of you. Keep your fingertips on the floor on the sides of your hips. Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale and lean forward, lifting your sitting bones off the floor. Bend your right knee, sliding your foot back. On the next exhale, bend your left knee, sliding your left foot back to meet your right. Your left shin should end up on top of your right calf muscle. Sit on your heels with ankles crossed under your sitting bones.
3. Inhale and rock forward. Exhale, engage your core, pull your quadriceps toward your chest, and lift your knees and feet off the floor, balancing on your fingertips. Make sure your arms are strong and straight and your shoulders are on top of your fingertips.
4. Aim to hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the pose.
5. Inhale and lower your feet and knees to the floor. Exhale and bring both legs straight out in front of you. Repeat on the opposite side.

Modification: on the fingertips; ankles crossed

lola = pendant

Pendant Pose

Lolasana

(lo-LAHS-uh-nuh)

Modification: fingertips pointing to the back, thumbs pointing to the front
Pose Type: arm balance, forward bend, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



Leg Position of Cow Face Pose in Pendant Pose

Pada Gomukhasana in Lolasana

(PUH-duh go-muk-AHS-uh-nuh in lo-LAHS-uh-nuh)

Modification: fingertips pointing to the back, thumbs pointing to the front
Pose Type: arm balance, forward bend, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



ARM BALANCE: ONE LEG OVER THE SHOULDER

Pose Dedicated to Viranchi (Brahma) 1 Prep.

Viranchyasana 1 Prep.

(vir-uhn-CHYAHS-uh-nuh)

Modification: back of the knee toward the shoulder
Pose Type: arm balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
🔴 🟠 🟡



One-Legged Crane 2 Prep.

Eka Pada Bakasana 2 Prep.

(EY-kuh PUH-duh buh-KAHS-uh-nuh)

Modification: both knees bent, back of one knee over the shoulder, other knee toward the chest
Pose Type: arm balance, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
🔴 🟠



One Foot Behind Head Crane Pose

Eka Pada Shirsha Bakasana

(EY-kuh PUH-duh SHEER-shuh buh-KAHS-uh-nuh)

Modification: 1. hips at shoulder height
2. hips at elbow height, head lifted
Pose Type: arm balance, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)


1.


2.

ARM BALANCE: CRANE POSE

Crane Pose

Bakasana

(buh-KAHS-uh-nuh)

Also Known As: Crow Pose (Kakasana)
Modification: elbows bent
Pose Type: arm balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Crane Pose

Bakasana

(buh-KAHS-uh-nuh)

Modification: 1. knees off the triceps
2. knees on the triceps
Pose Type: arm balance, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs), Nasagrai or Nasagre (nose)





ARM BALANCE: SHOULDER PRESSURE POSE & FIREFLY POSE

Two-Handed Arm Balance

Dwi Hasta Bhujasana

(DWI-huh-stuh buj-AHS-uh-nuh)

Modification: 1. feet off the floor
2. toes touching the floor
Pose Type: arm balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Padayoragrai or Padayoragre (toes/feet)





Shoulder Pressure Pose

Bhujapidasana

(buj-uh-peed-AHS-uh-nuh)

Also Known As: Shoulder Pressure Pose (Bhujapidasana A)
Modification: head off the floor
Pose Type: arm balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Padayoragrai or Padayoragre (toes/feet)



Firefly Pose 1

Tittibhasana 1

(ti-ti-BAHS-uh-nuh)

Also Known As: Firefly Pose A (Tittibhasana A)
Modification: elbows bent, legs on top of the shoulders
Pose Type: arm balance, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), or Nasagrai or Nasagre (nose)
ल व ह ॐ



Firefly Pose 1

Tittibhasana 1

(ti-ti-BAHS-uh-nuh)

Also Known As: Firefly Pose A (Tittibhasana A)
Modification: arms straight, feet extended to the sky
Pose Type: arm balance, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) or Nasagrai or Nasagre (nose)
ल व ह ॐ

Firefly Pose 1

Tittibhasana 1

(ti-ti-BAHS-uh-nuh)

Also Known As: Firefly Pose A (Tittibhasana A), Raised Tortoise Pose (Utthita Kurmasana)
Modification: arms straight, legs parallel to the floor
Pose Type: arm balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व ह



ARM BALANCE: FIREFLY POSE

Firefly Pose

Tittibhasana

(ti-ti-BAHS-uh-nuh)

Also Known As: Raised Up Feet Spread Out Resting on the Arms Pose (Utthita Dwi Pada Vrishtasana)
Modification: elbows bent, legs on triceps, wide legged
1. side view
2. front view

Pose Type: arm balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)


1.


2.

Lifted Feet Spread Out Pose

Utthita Dwi Pada Vrishtasana

(UT-ti-tuh DWI-puh-duh vrish-TAHS-uh-nuh)

Modification: arms straight, heels of the palms touching, fingertips pointing to the sides
Pose Type: arm balance, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



One-Legged Crane 1

Eka Pada Bakasana 1

(EY-kuh PUH-duh buh-KAHS-uh-nuh)

Modification: knee to the tricep
Pose Type: arm balance, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



One-Legged Crane 1

Eka Pada Bakasana 1

(EY-kuh PUH-duh buh-KAHS-uh-nuh)

Modification: knee to the outside of the shoulder
Pose Type: arm balance, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



One-Legged Crane 2

Eka Pada Bakasana 2

(EY-kuh PUH-duh buh-KAHS-uh-nuh)

Modification: shin of the bent leg to the tricep

Pose Type: arm balance, forward bend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) or Nasagrai or Nasagre (nose)

लं वं हं ॐ



Pose Dedicated to Galava, One-Legged Modification

Eka Pada Galavasana

(EY-kuh PUH-duh gah-luh-VAHS-uh-nuh)

Pose Type: arm balance, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

लं वं हं



Dragonfly Pose 1

Maksikanagasana 1

(muhk-shi-kah-nah-GAHS-uh-nuh)

Also Known As: Stick Arm to the Side Grasshopper Pose (Parshva Bhuja Danda Salabhasana)
Pose Type: arm balance, forward bend, twist
Drishti Point: Nasagrai or Nasagre (nose)



Moonbird Pose

Chakorasana

(chuh-kor-AHS-uh-nuh)

Pose Type: arm balance, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Uneven One-Legged Crane 1

Vishama Eka Pada Bakasana 1

(VISH-uh-muh EY-kuh PUH-duh buh-KAHS-uh-nuh)

Modification: one forearm to the floor, other elbow bent at 90 degrees
Pose Type: arm/forearm balance, forward bend, inversion

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व ह



Arm to the Side Pose Dedicated to Sage Koundinya One-Legged Version 1

Parshva Hasta Eka Pada Koundinyasana 1

(PAHRSH-vuh HUH-stuh EY-kuh PUH-duh kown-din-YAHS-uh-nuh)
Modification: bottom knee bent
Pose Type: arm balance, forward bend, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)
ल व र



ARM BALANCE: SCISSOR LEGS

Pose Dedicated to Sage Koundinya One-Legged Version 1 Prep.

Eka Pada Koundinyasana 1 Prep.

(EY-kuh PUH-duh kown-din-YAHS-uh-nuh)
Modification: ear to the floor, bottom knee bent

Pose Type: arm balance, forward bend, twist
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Pose Dedicated to Sage Koundinya One-Legged Version 1 Prep.

Eka Pada Koundinyasana 1 Prep.

(EY-kuh PUH-duh kown-din-YAHS-uh-nuh)
Modification: head on the floor
Pose Type: arm balance, forward bend, twist
Drishti Point: Nasagrai or Nasagre (nose)



Pose Dedicated to Sage Koundinya One-Legged Version 2

Eka Pada Koundinyasana 2

(EY-kuh PUH-duh kown-din-YAHS-uh-nuh)
Modification: 1. prep. back foot on the floor, toes curled in
2. back foot lifted
Pose Type: arm balance, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre

(nose)





ARM BALANCE: GARUDA LEGS

Revolved Leg Position of the Pose Dedicated to Garuda in Swan Pose

Parivritta Pada Garudasana in Hamsasana

(puh-ri-VRIT-tuh PUH-duh guh-ru-DAHS-uh-nuh in huhms-AHS-uh-nuh)

Pose Type: arm balance, forward bend, twist

Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Revolved Leg Position of the Pose Dedicated to Garuda in Uneven Swan Pose

Parivritta Pada Garudasana in Vishama Hamsasana

(puh-ri-VRIT-tuh PUH-duh guh-ru-DAHS-uh-nuh in VISH-uh-muh huhms-AHS-uh-nuh)

Modification: forearm to the floor
Pose Type: arm balance, forward bend, twist
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Revolved Leg Position of the Pose Dedicated to Garuda in Uneven Swan Pose

Parivritta Pada Garudasana in Vishama Hamsasana

(puh-ri-VRIT-tuh PUH-duh guh-ru-DAHS-uh-nuh in VISH-uh-muh huhms-AHS-uh-nuh)

Modification: elbow to the floor
Pose Type: arm balance, forward bend, twist
Drishti Point: Nasagrai or Nasagre (nose) or Padayoragrai or Padayoragre (toes/feet)



Two-Legged Pose Dedicated to Koundinya

Dwi Pada Koundinyasana

(DWI-puh-duh kown-din-YAHS-uh-nuh)

Pose Type: arm balance, forward bend, twist
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Uneven Two-Legged Pose Dedicated to Koundinya

Vishama Dwi Pada Koundinyasana

(VISH-uh-muh DWI-puh-duh kown-din-YAHS-uh-nuh)

Modification: one forearm to the floor, knees bent
Pose Type: arm balance, forward bend, twist
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Pose Dedicated to Ashtavakra Prep.

Ashtavakrasana Prep.

(uh-shtuh-vuh-KRAHS-uh-nuh)

Also Known As: Eight Angle Pose Prep.

Modification: feet unhooked

Pose Type: arm balance, forward bend, twist

Drishti Point: Nasagrai or Nasagre (nose)



ARM BALANCE: BOTH LEGS TO THE SIDE—ASHTAVAKRA’S POSE

Pose Dedicated to Ashtavakra

Ashtavakrasana

(uh-shtuh-vuh-KRAHS-uh-nuh)

Also Known As: Eight Angle Pose

Pose Type: arm balance, forward bend, twist

Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Uneven Pose Dedicated to Ashtavakra

Vishama Ashtavakrasana

(VISH-uh-muh uh-shtuh-vuh-KRAHS-uh-nuh)

Also Known As: Uneven Eight Angle Pose
Modification: one forearm to the floor
Pose Type: arm/forearm balance, forward bend, twist
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
ल व



Uneven Half Repose Pose Dedicated to Ashtavakra

Vishama Ardha Shayana Ashtavakrasana

(VISH-uh-muh UHR-duh shuh-yuh-nuh uh-shtuh-vuh-KRAHS-uh-nuh)

Also Known As: Uneven Half Repose Eight Angle Pose
Modification: one elbow to the floor, hand to the face
Pose Type: arm/elbow balance, forward bend, twist
Drishti Point: Nasagrai or Nasagre (nose)
ल व ह



ARM BALANCE: BOTH LEGS TO THE SIDE—KNEES BENT AND TOGETHER

Side Crane Pose

Parshva Bakasana

(PAHRSH-vuh buh-KAHS-uh-nuh)

Also Known As: Revolved Crane Pose (Parivritta Bakasana), Sideways Crow Pose (Parshva Kakasana)
Modification: 1. elbows bent
2. arms straight
Pose Type: arm balance, forward bend, twist
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)





Two-Legged Pose Dedicated to Koundinya Modification on the Fists

Mushti Dwi Pada Koundinyasana

(mush-ti DWI-puh-duh kown-din-YAHS-uh-nuh)

Modification: ankles crossed
Pose Type: arm balance, forward bend, twist
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Uneven Arms Side Crane Pose

Vishama Hasta Parshva Bakasana

(VISH-uh-muh HUH-stuh PAHRSH-vuh buh-KAHS-uh-nuh)

Pose Type: arm balance, forward bend, twist
Drishti Point: Nasagrai or Nasagre (nose)
लं वं हं



ARM BALANCE: LOTUS PEACOCK

Bound Angle Pose in Peacock Pose

Baddha Konasana in Mayurasana

(BUH-duh ko-NAHS-uh-nuh in muh-yoor-AHS-uh-nuh)

Pose Type: arm balance
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं वं हं ॐ



Lotus Pose in Peacock Pose

Padmasana in Mayurasana

(puhd-MAHS-uh-nuh in muh-yoor-AHS-uh-nuh)

Pose Type: arm balance, hip opener

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Fist Lotus Peacock Pose

Mushti Padma Mayurasana

(mush-ti PUHD-muh muh-yoor-AHS-uh-nuh)

Pose Type: arm balance

Drishti Point: Nasagrai or Nasagre (nose)



ARM BALANCE: PEACOCK AND SWAN

Peacock Pose

Mayurasana

(muh-yoor-AHS-uh-nuh)

Modification: 1. feet lifted higher than the hip level
2. body parallel to the floor
Pose Type: arm balance
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)





Swan Pose

Hamsasana

(huhms-AHS-uh-nuh)

Also Known As: Swan Pose (Hansasana)
Pose Type: arm balance
Drishti Point: Nasagrai or Nasagre (nose)



One Hand Peacock Pose

Eka Hasta Mayurasana

(EY-kuh HUH-stuh muh-yoor-AHS-uh-nuh)

Also Known As: Wounded Peacock Pose (Pungu Mayurasana)
Pose Type: arm balance
Drishti Point: Nasagrai or Nasagre (nose)



Inversion Poses

- DUCK POSE
- DOLPHIN POSE
- PEACOCK FEATHER POSE
- BACKBENDS ON FOREARMS
- HANDSTANDS (VARIATIONS)
- HEADSTANDS (VARIATIONS)
- SHOULDERSTAND (VARIATIONS)
- PLOW POSE

Duck Pose

Karandavasana

(kahr-uhn-duh-VAHS-uh-nuh)

Also Known As: Baby Duck Pose

Modification: thumbs grabbing onto the biceps, fingers grabbing onto the triceps; knees to the armpits, feet together

Pose Type: forearm balance, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Duck Pose

Karandavasana

(kahr-uhn-duh-VAHS-uh-nuh)

Also Known As: Baby Duck Pose

Modification: forearms to the floor, knees to the armpits, feet together

Pose Type: forearm balance, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Downward Facing Pose Dedicated to Makara

Adho Mukha Makarasana

(uh-DO MUK-uh muh-kuh-RAHS-uh-nuh)

Also Known As: Dolphin Pose
Pose Type: forward bend, inversion, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ



One-Legged Uneven Peacock Feather Pose

Eka Pada Vishama Picha Mayurasana

(EY-kuh PUH-duh VISH-uh-muh pich-chuh muh-yoor-AHS-uh-nuh)

Also Known As: Eka Pada Vishama Pincha Mayurasana
Pose Type: forearm balance, inversion, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व ह



Half Lotus Downward Facing Pose Dedicated to Makara

Ardha Padma Adho Mukha Makarasana

(UHR-duh PUHD-muh uh-DO MUK-uh muh-kuh-RAHS-uh-nuh)

Also Known As: Half Lotus Dolphin Pose
Modification: heel down
Pose Type: forward bend, inversion, core
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व य ह



Leg Position of the Pose Dedicated to Garuda in Downward Facing Pose Dedicated to Makara

Pada Garudasana in Adho Mukha Makarasana

(PUH-duh guh-ru-DAHS-uh-nuh in uh-DO MUK-uh muh-kuh-RAHS-uh-nuh)

Also Known As: Leg Position of the Pose Dedicated to Garuda in Dolphin Pose
Pose Type: forward bend, inversion, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



PEACOCK FEATHER POSE

Peacock Feather Pose

Picha Mayurasana

(pich-chuh muh-yoor-AHS-uh-nuh)

Also Known As: Upright Scorpion Pose (Avakra Vrishchikasana), Pincha Mayurasana
Pose Type: forearm balance, inversion
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल य ह



One-Legged Peacock Feather Pose

Eka Pada Picha Mayurasana

(EY-kuh PUH-duh pich-chuh muh-yoor-AHS-uh-nuh)

Also Known As: Eka Pada Pincha Mayurasana
Pose Type: forearm balance, inversion, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व य ह



One-Legged Scorpion Pose

Eka Pada Vrishchikasana

(EY-kuh PUH-duh vrish-chi-KAHS-uh-nuh)

Modification: biceps in line with the ears

Pose Type: forearm balance, inversion, backbend
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य ह



Pose Dedicated to Lord Hanuman in Peacock Feather Pose

Hanumanasana in Picha Mayurasana

(huh-nu-mahn-AHS-uh-nuh in pich-chuh muh-yoor-AHS-uh-nuh)
Also Known As: Hanumanasana in Pincha Mayurasana
Pose Type: forearm balance, inversion, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



One-Legged Stretched Out Scorpion Pose

Eka Pada Paripurna Vrishchikasana

(EY-kuh PUH-duh puh-ri-POOR-nuh vrish-chi-KAHS-uh-nuh)
Pose Type: forearm balance, inversion, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



One-Legged Scorpion Pose

Eka Pada Vrishchikasana

(EY-kuh PUH-duh vrish-chi-KAHS-uh-nuh)

Modification: forearms to the floor, foot away from the head
Pose Type: forearm balance, inversion, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BACKBENDS ON FOREARMS, LOTUS ON FOREARMS, AND ELBOW BALANCES

Inverted Puppy Dog Pose in Peacock Feather Pose

Viparita Shvanakasana in Picha Mayurasana

(vi-puh-REE-tuh shvuh-nuh-KAHS-uh-nuh in pich-chuh muh-yoor-AHS-uh-nuh)

Also Known As: Viparita Shvanakasana in Pincha Mayurasana
Modification: knees bent, backbend
Pose Type: forearm balance, inversion, backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Scorpion Pose

Vrishchikasana

(vrish-chi-KAHS-uh-nuh)

Modification: forearms to the floor, feet to the head
Pose Type: forearm balance, inversion, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged Scorpion Pose

Eka Pada Vrishchikasana

(EY-kuh PUH-duh vrish-chi-KAHS-uh-nuh)

Modification: forearms to the floor, foot to the head, other leg parallel to the floor
Pose Type: forearm balance, inversion, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Upward Lotus Pose in Peacock Feather Pose

Urdhva Padmasana in Picha Mayurasana

(OORD-vuh puhd-MAHS-uh-nuh in pich-chuh muh-yoor-AHS-uh-nuh)

Also Known As: Raised Lotus Scorpion Pose (Urdhva Padma Vrishchikasana), Duck Pose (Karandavasana)
Pose Type: forearm balance, inversion
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व ह



Uneven Repose Pose

Vishama Shayanasana

(VISH-uh-muh shuh-yuh-NAHS-uh-nuh)

Modification: both knees bent
Pose Type: forearm/elbow balance, inversion, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ



Repose Pose

Shayanasana

(shuh-yuh-NAHS-uh-nuh)

Modification: both knees bent
Pose Type: elbow balance, inversion, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं रं यं हं ॐ



HANDSTANDS: BOTH LEGS STRAIGHT

Feet Spread Intense Stretch Pose in Downward Facing Tree Pose

Prasarita Padottanasana in Adho Mukha Vrikshasana

(pruh-SAH-ri-tuh puh-do-tahn-AHS-uh-nuh in uh-DO MUK-uh vriks-SHAHS-anna)

Also Known As: Feet Spread Full Forward Bend Pose in Downward Facing Tree Pose, Prasarita Padottanasana in Adho Mukha Vrksasana
Pose Type: inversion, arm balance, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
लं वं यं हं



One-Legged Downward Facing Tree Pose

Eka Pada Adho Mukha Vrikshasana

(EY-kuh PUH-duh uh-DO MUK-uh vrik-SHAHS-uh-nuh)

Also Known As: Eka Pada Adho Mukha Vrksasana
Pose Type: inversion, arm balance, forward bend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Downward Facing Tree Pose

Adho Mukha Vrikshasana

(uh-DO MUK-uh vrik-SHAHS-uh-nuh)

Also Known As: Adho Mukha Vrksasana
Modification: legs crossed
Pose Type: inversion, arm balance
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)

Seated Angle Pose in Downward Facing Tree Pose

Upavishta Konasana in Adho Mukha Vrikshasana

(u-puh-VISH-tuh ko-NAHS-uh-nuh in uh-DO MUK-uh vrik-SHAHS-uh-nuh)

Also Known As: Upward Spread Feet Pose A (Urdhva Prasarita Padasana A), Upavista Konasana in Adho Mukha Vrikshasana
Pose Type: inversion, arm balance
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व य ह



Leg Position of the Pose Dedicated to Garuda in

Downward Facing Tree Pose

Pada Garudasana in Adho Mukha Vrikshasana

(PUH-duh guh-ru-DAHS-uh-nuh in uh-DO MUK-uh vrik-SHAHS-uh-nuh)

Also Known As: Pada Garudasana in Adho Mukha Vrksasana

Pose Type: inversion, arm balance

Drishti Point: Angusthamadhye or Angustha Ma Dyai (thumbs)

How to Perform the Pose:

1. Begin by standing in Mountain Pose (*Tadasana*). Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale and hinge from the hips, coming into a forward bend, placing the palms on the floor on the outsides of your feet. Your hands should be shoulder width apart or slightly wider. Make sure your arms are straight and your shoulders are on top of your fingertips.
3. There are many ways to come into a handstand. When you start practicing handstands, make sure you can balance on your hands against the wall for at least 60 seconds. Then you can experiment with jumping into a handstand or lifting your legs using your core. Press strongly into your hands.
4. Once you find your balance in a Downward Facing Tree Pose (*Adho Mukha Vrikshasana*), also known as Handstand, exhale and bend your knees; cross your right leg over your left leg, hooking your right foot around your left calf muscle. Hold for 30, and up to 90, seconds to receive the full benefits of the stretch.
5. Inhale and bring your legs back to the straight position. Exhale and switch legs as you bend your knees and cross your left leg over your right leg, hooking your left foot around your right calf muscle. Hold for 30, and up to 90, seconds to receive the full benefits of the stretch.
6. Inhale and bring your legs back to the straight position. On the following inhale, lower your feet to the floor. Inhale as you come back to Mountain Pose (*Tadasana*).

pada = foot or leg

Garuda = Hindu Deity, half-man half-eagle, carrier of Lord Vishnu

adho = downward

mukha = facing

vriksha = tree

Frog Pose in Downward Facing Tree Pose

Mandukasana in Adho Mukha Vrikshasana

(muhn-doo-KAHS-uh-nuh in uh-DO MUK-uh vrik-SHAHS-uh-nuh)

Also Known As: Mandukasana in Adho Mukha Vrksasana
Pose Type: inversion, arm balance
Drishti Point: Nasagrai or Nasagre (nose) or Angusthamadhye or Angustha Ma Dyai (thumbs)



Bound Angle Pose in Downward Facing Tree Pose

Baddha Konasana in Adho Mukha Vrikshasana

(BUH-duh ko-NAHS-uh-nuh in uh-DO MUK-uh vrik-SHAHS-uh-nuh)

Also Known As: Baddha Konasana in Adho Mukha Vrksasana
Pose Type: inversion, arm balance
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Svastika Legs in Downward Facing Tree Pose

Pada Svastikasana in Adho Mukha Vrikshasana

(PUH-duh svuh-sti-KAHS-uh-nuh in uh-DO MUK-uh vrik-SHAHS-uh-nuh)

Also Known As: Pada Svastikasana in Adho Mukha Vrksasana
Modification: both knees bent, one knee bent toward the chest, other foot pointing to the back
Pose Type: inversion, arm balance, mild backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)

ल व य ह



Scorpion Pose Prep.

Vrishchikasana Prep.

(vrish-chi-KAHS-uh-nuh)

Also Known As: Pose Dedicated to the Demon Taraka A (Tarakasana A)
Modification: knees bent, feet away from the head
Pose Type: inversion, arm balance, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल र य ह ॐ



Half Lotus Pose in Downward Facing Tree Pose

Ardha Padmasana in Adho Mukha Vrikshasana

(UHR-duh puhd-MAHS-uh-nuh in uh-DO MUK-uh vrik-SHAHS-uh-nuh)

Also Known As: Ardha Padmasana in Adho Mukha Vrksasana
Pose Type: inversion, arm balance
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व य ह



HANDSTAND, LEGS CROSSED: GARUDA LEGS & LOTUS

Leg Position of the Pose Dedicated to Garuda in Downward Facing Tree Pose

Pada Garudasana in Adho Mukha Vrikshasana

(PUH-duh guh-ru-DAHS-uh-nuh in uh-DO MUK-uh vrik-SHAHS-uh-nuh)

Also Known As: Pada Garudasana in Adho Mukha Vrksasana
Modification: arms bent at 90 degrees
Pose Type: inversion, arm balance
Drishti Point: Nasagrai or Nasagre (nose)
ल व ह



Upward Lotus Pose in Downward Facing Tree Pose

Urdhva Padmasana in Adho Mukha Vrikshasana

(OORD-vuh puhd-MAHS-uh-nuh in uh-DO MUK-uh vrik-SHAHS-uh-nuh)

Also Known As: Urdhva Padmasana in Adho Mukha Vrksasana
Pose Type: inversion, arm balance
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



HEADSTAND 1 ARM POSITION: LEG MODIFICATIONS

Headstand 1

Shirshasana 1

(sheer-SHAHS-uh-nuh)

Also Known As: Supported Headstand (Salamba Shirshasana*), Bound Hands Headstand A (Baddha Hasta Shirshasana A)
Modification: 1. back view
2. side view
Pose Type: inversion
Drishti Point: Nasagrai or Nasagre (nose)




2.

One-Legged Headstand 1

Eka Pada Shirshasana 1

(EY-kuh PUH-duh sheer-SHAHS-uh-nuh)

Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Padayoragrai or Padayoragre (toes/feet)



Leg Contraction Knee Bend Pose in Headstand 1

Pada Akunchanasana in Shirshasana 1

(PUH-duh uh-kunch-uh-NAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Modification: one knee bent toward the chest
Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Upward Staff Pose in Headstand 1

Urdhva Dandasana in Shirshasana 1

(OORD-vuh duhn-DAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Also Known As: Half Headstand Pose (Ardha Shirshasana), Headstand B (Shirshana B)
Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



HEADSTAND 1 ARM POSITION: VARIOUS LEG POSITIONS

Svastika Legs in Headstand 1

Pada Svastikasana in Shirshasana 1

(PUH-duh svuh-sti-KAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Pose Type: inversion, mild backbend
Drishti Point: Nasagrai or Nasagre (nose)



Leg Position of One-Legged King Pigeon 1 Version B in Headstand 1

Pada Eka Pada Raja Kapotasana 1 B in Shirshasana 1

(PUH-duh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Modification: both knees bent, one knee to the sky, other foot to the knee

Pose Type: inversion, mild backbend

Drishti Point: Nasagrai or Nasagre (nose)



Feet to Head Pose

Shirsha Padasana

(SHEER-shuh puh-DAHS-uh-nuh)

Pose Type: inversion, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Bound Angle Pose in Headstand 1

Baddha Konasana in Shirshasana 1

(BUH-duh ko-NAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Pose Type: inversion
Drishti Point: Nasagrai or Nasagre (nose)



Sideways Bound Angle Pose in Headstand 1

Parshva Baddha Konasana in Shirshasana 1

(PAHRSH-vuh BUH-duh ko-NAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Pose Type: inversion, side bend
Drishti Point: Nasagrai or Nasagre (nose)



Pose Dedicated to Hanuman in Headstand 1

Hanumanasana in Shirshasana 1

(huh-nu-mahn-AHS-uh-nuh in sheer-SHAH-suh-nuh)

Pose Type: inversion
Drishti Point: Nasagrai or Nasagre (nose)
● ● ●



Seated Angle Pose in Headstand 1

Upavishta Konasana in Shirshasana 1

(u-puh-VISH-tuh ko-NAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Also Known As: Upavista Konasana in Adho Mukha Vrikshasana, Upavista Konasana in Adho Mukha Vrksasana
Pose Type: inversion
Drishti Point: Nasagrai or Nasagre (nose)
● ● ●

Leg Position of the Pose Dedicated to Garuda in Headstand 1

Pada Garudasana in Shirshasana 1

(PUH-duh guh-ru-DAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Pose Type: inversion
Drishti Point: Nasagrai or Nasagre (nose)



HEADSTAND 1 ARM POSITION: LOTUS LEG POSITION

Upward Lotus in Headstand 1

Urdhva Padmasana in Shirshasana 1

(OORD-vuh puhd-MAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Modification: 1. back view
2. side view
Pose Type: inversion
Drishti Point: Nasagrai or Nasagre (nose)

Sideways Upward Lotus in Headstand 1

Parshva Urdhva Padmasana in Shirshasana 1
(PAHRSH-vuh OORD-vuh puhd-MAHS-uh-nuh in sheer-SHAHS-uh-nuh)
Pose Type: inversion, twist
Drishti Point: Nasagrai or Nasagre (nose)



Embryo Pose in Headstand 1 Prep.

Pindasana in Shirshasana 1 Prep.
(pin-DAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Modification: thighs parallel to the floor
Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व ॐ



Embryo Pose in Headstand 1

Pindasana in Shirshasana 1

(pin-DAHS-uh-nuh in sheer-SHAHS-uh-nuh)
Modification: 1. knees to the triceps
2. knees to the chest
Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य ॐ





HEADSTAND 1 & 3 ARM POSITIONS: VARIOUS ARM AND LEG POSITIONS

One Hand Headstand 1

Eka Hasta Shirshasana 1

(EY-kuh HUH-stuh sheer-SHAHS-uh-nuh)

Modification: both knees bent toward the chest, one forearm on the floor
1. other arm straight, fingertips to the sky
2. other arm behind the back, fingertips pointing to the upper back
Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose)





Sideways Uneven Upward Staff Pose

Parshva Vishama Urdhva Dandasana

(PAHRSH-vuh VISH-uh-muh OORD-vuh duhn-DAHS-uh-nuh)

Modification: forearm to the floor in front of the face, palm down; legs parallel to the floor
Pose Type: inversion, forward bend, twist
Drishti Point: Hastagrai or Hastagre (hands)



Leg Contraction Pose in Headstand 3

Pada Akunchanasana in Shirshasana 3

(PUH-duh uh-kunch-AHS-uh-nuh in sheer-SHAHS-uh-nuh)

Modification: one leg straight and out to the side, other knee to the chest
Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Leg Contraction Pose in Uneven Headstand (Fusion of Headstand 5 and Headstand 3 Arm Position)

Pada Akunchanasana in Vishama Shirshasana

(PUH-duh uh-kunch-AHS-uh-nuh in VISH-uh-muh sheer-SHAHS-uh-nuh)

Modification: one forearm to the floor, other elbow on top of the wrist, knee to the tricep on the same side

Pose Type: inversion, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

● ● ● ●



HEADSTAND 5 ARM POSITION: VARIOUS LEG POSITIONS

Leg Position of the Pose Dedicated to Garuda in Headstand 5

Pada Garudasana in Shirshasana 5

(PUH-duh guh-ru-AHS-uh-nuh in sheer-SHAHS-uh-nuh)

Pose Type: inversion

Drishti Point: Nasagrai or Nasagre (nose)

● ● ●



Leg Position of Cow Face Pose in Headstand 5

Pada Gomukhasana in Shirshasana 5

(PUH-duh go-muk-AHS-uh-nuh in sheer-SHAHS-uh-nuh)

Modification: bottom knee to the opposite tricep

Pose Type: inversion, forward bend

Drishti Point: Nasagrai or Nasagre (nose)



Headstand 5

Shirshasana 5

(sheer-SHAHS-uh-nuh)

Also Known As: Tripod Headstand

Pose Type: inversion

Drishti Point: Nasagrai or Nasagre (nose)



Frog Pose in Headstand 5

Mandukasana in Shirshasana 5

(muhn-doo-KAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Pose Type: inversion

Drishti Point: Nasagrai or Nasagre (nose)



Seated Angle Pose in Headstand 5

Upavishta Konasana in Shirshasana 5

(u-puh-VISH-tuh ko-NAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Also Known As: Tripod Headstand Same Angle Pose (Utripada Shirsha Samakonasana), Upavista Konasana in Shirshasana
Pose Type: inversion
Drishti Point: Nasagrai or Nasagre (nose)



Leg Position of One-Legged King Pigeon 1 Version B in Headstand 5

Pada Eka Pada Raja Kapotasana 1 B in Shirshasana 5

(PUH-duh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Modification: knee to the tricep on the same side, other knee resting on the foot
Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Revolved Leg Position of One-Legged King Pigeon 1 Version B in Headstand 5

Parivritta Pada Eka Pada Raja Kapotasana 1 B in Shirshasana 5

(puh-ri-VRIT-tuh PUH-duh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Modification: knee resting on the foot
1. top leg straight
2. top knee bent at 90 degrees
Pose Type: inversion, forward bend, twist
Drishti Point: Nasagrai or Nasagre (nose)



1.



2.

Headstand 5 Prep.

Shirshasana 5 Prep.

(sheer-SHAHS-uh-nuh)

Modification: one knee to the tricep, other foot to the floor on the side
Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Crane Pose in Headstand 5 Prep.

Bakasana in Shirshasana 5 Prep.

(buh-KAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Modification: knees on the triceps
Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Side Crane Pose in Headstand 5

Parshva Bakasana in Shirshasana 5

(PAHRSH-vuh buh-KAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Modification: knees together, knee to the opposite tricep

Pose Type: inversion, forward bend, twist

Drishti Point: Nasagrai or Nasagre (nose)

● ● ● ●



Embryo in the Womb Pose in Headstand 5

Garba Pindasana in Shirshasana 5

(guhr-buh-pin-DAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Pose Type: inversion, forward bend

Drishti Point: Nasagrai or Nasagre (nose)

● ● ● ● ●



Side Rooster Pose in Headstand 5 Prep.

Parshva Kukkutasana in Shirshasana 5 Prep.

(PAHRSH-vuh ku-ku TAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Modification: crown of the head on the floor

Pose Type: inversion, forward bend, twist

Drishti Point: Nasagrai or Nasagre (nose)



HEADSTAND 5 ARM POSITION: VARIOUS ARM POSITIONS BASED ON HEADSTAND 5 & VARIOUS LEG POSITIONS

Baby Cradle Pose in Headstand 5

Hindolasana in Shirshasana 5

(hin-do-LAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Modification: Side 1: ankle to the inside of the elbow joint of the opposite arm, knee bent to the inside of the same arm, toes touching the floor.
Side 2: other knee bent to the side, heel toward the sitting bone
Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Baby Cradle Pose in Headstand 5

Hindolasana in Shirshasana 5

(hin-do-LAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Modification: Side 1: arm bent at 90 degrees, fingertips to the floor, knee to the elbow on the same side.
Side 2: arm bent at 90 degrees, palm flat on the floor, ankle to the inside of the elbow joint, toes lifted off the floor
Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Extended Hand to Big Toe Pose in One Hand Headstand 5

Utthita Hasta Padangushtasana in Eka Hasta Shirshasana 5

(UT-ti-tuh HUH-stuh puhd-ahng-goosh-TAHS-uh-nuh in EY-kuh HUH-stuh sheer-SHAHS-uh-nuh)

Modification: Side 1: arm and leg straight out, grabbing onto the big toe.
Side 2: arm bent 90 degrees, knee resting on the tricep on the same side
Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Hastagrai or Hastagre (hands)



One-Legged Crane Pose 1 in One Hand Headstand 5

Eka Pada Bakasana 1 in Eka Hasta Shirshasana 5

(EY-kuh PUH-duh buh-KAHS-uh-nuh in EY-kuh HUH-stuh sheer-SHAHS-uh-nuh)

Modification: Side 1: arm and leg straight out.
Side 2: arm bent 90 degrees, knee resting on the tricep on the same side
Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Hastagrai or Hastagre (hands)



HEADSTAND 6 ARM POSITION: VARIOUS ARM POSITIONS BASED OFF HEADSTAND 6 & VARIOUS LEG POSITIONS

Extended Hand to Big Toe Pose in Uneven Headstand (Fusion of Headstand 5 and Headstand 6 Arm Position)

Utthita Hasta Padangushtasana in Vishama Shirshasana 5 & 6

(UT-ti-tuh HUH-stuh puhd-ahng-goosh-TAHS-uh-nuh in VISH-uh-muh sheer-SHAHS-uh-nuh)

Modification: Side 1: arm and leg straight out, grabbing onto the big toe
Side 2: arm bent 90 degrees, knee bent to the tricep on the same side
Pose Type: inversion, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Hastagrai or Hastagre (hands)



Crane Pose in Uneven Headstand (Fusion of Headstand 5 and Headstand 6 Arm Position)

Bakasana in Vishama Shirshasana 5 & 6

(buh-KAHS-uh-nuh in VISH-uh-muh sheer-SHAHS-uh-nuh)

Modification: Side 1: arm straight out, fingertips to the floor, knee to the tricep.
Side 2: arm bent 90 degrees, knee bent to the tricep on the same side
Pose Type: inversion, forward bend
Drishti Point: Hastagrai or Hastagre (hands)



Headstand 6

Shirshasana 6

(sheer-SHAHS-uh-nuh)

Also Known As: Hands Free Headstand (Mukta Hasta Shirshasana)
Pose Type: inversion
Drishti Point: Nasagrai or Nasagre (nose), Hastagrai or Hastagre (hands)



Upward Staff Pose in Headstand 6

Urdhva Dandasana in Shirshasana 6

(OORD-vuh duhn-DAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Modification: on the fingertips
Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Hastagrai or Hastagre (hands)



HEADSTAND 7 ARM POSITION: VARIOUS ARM POSITIONS BASED OFF HEADSTAND 7 & VARIOUS LEG POSITIONS

Headstand 7A

Shirshasana 7A

(sheer-SHAHS-uh-nuh)

Also Known As: Spread Hands Headstand (Prasarita Hasta Shirshasana), Hands Free Headstand C (Mukta Hasta Shirshasana C)
Pose Type: inversion
Drishti Point: Nasagrai or Nasagre (nose)



Bound Angle Pose in Headstand 7B

Baddha Konasana in Shirshasana 7B

(BUH-duh ko-NAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Also Known As: Bound Angle Pose in Free Hands Headstand (Baddha Konasana in Mukta Hasta Shirshasana)
Pose Type: inversion
Drishti Point: Nasagrai or Nasagre (nose)



Leg Position of the Pose Dedicated to Garuda in Uneven Headstand (Fusion of Headstand 5 and Headstand 7 Arm Positions)

Pada Garudasana in Vishama Shirshasana 5 & 7A

(PUH-duh guh-ru-DAHS-uh-nuh in VISH-uh-muh sheer-SHAHS-uh-nuh)

Pose Type: inversion
Drishti Point: Nasagrai or Nasagre (nose)



Upward Lotus Pose in Headstand 7B

Urdhva Padmasana in Shirshasana 7B

(OORD-vuh puhd-MAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Also Known As: Supported Lotus Headstand Pose (Salamba Padma Shirshasana), Upward Lotus Pose in Spread Hands Headstand (Urdhva Padmasana in Prasarita Hasta Shirshasana), Upward Lotus in Hands Free Headstand (Urdhva Padmasana in Mukta Hasta Shirshasana)

Modification: 1. neutral spine
2. backbend

Pose Type: 1. inversion
2. inversion, backbend

Drishti Point: Nasagrai or Nasagre (nose)





HEADSTAND 8 & 5 ARM POSITIONS: LEG STRAIGHT OUT TO THE SIDE

Leg to the Side Revolved Uneven Headstand (Fusion of Headstand 5 and Headstand 8 Arm Positions)

Parshva Pada Parivritta Vishama Shirshasana 5 & 8

(PAHRSH-vuh PUH-duh puh-ri-VRIT-tuh VISH-uh-muh sheer-SHAHS-uh-nuh)

Modification: Side 1: arm bent at 90 degrees, palm flat on the floor, knee resting on the opposite elbow
Side 2: arm bent at 90 degrees, fingertips to the floor, leg straight out to the side

Pose Type: inversion, forward bend, twist
Drishti Point: Hastagrai or Hastagre (hands)



Leg to the Side One Hand Headstand 5

Parshva Pada Eka Hasta Shirshasana 5

(PAHRSH-vuh PUH-duh EY-kuh HUH-stuh sheer-SHAHS-uh-nuh)

Modification: Side 1: arm bent at 90 degrees, palm flat on the floor, knee resting on the same elbow
Side 2: arm straight, grabbing onto the shin of the leg, leg straight out to the side
Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



Leg to the Side Revolved One Hand Headstand 5

Parshva Pada Parivritta Eka Hasta Shirshasana 5

(PAHRSH-vuh PUH-duh puh-ri-VRIT-tuh EY-kuh HUH-stuh sheer-SHAHS-uh-nuh)

Modification: Side 1: arm bent at 90 degrees, palm flat to the floor, leg straight out to the side
Side 2: arm straight up to the sky, knee resting on the opposite tricep
Pose Type: inversion, forward bend, twist

Drishti Point: Hastagrai or Hastagre (hands), Nasagrai or Nasagre (nose)



Leg to the Side Revolved One Hand Headstand 8

Parshva Pada Parivritta Eka Hasta Shirshasana 8

(PAHRSH-vuh PUH-duh puh-ri-VRIT-tuh EY-kuh HUH-stuh sheer-SHAHS-uh-nuh)

Modification: Side 1: arm bent at 90 degrees, fingertips to the floor, leg straight out to the side
Side 2: arm straight out to the side, knee resting on the opposite tricep
Pose Type: inversion, forward bend, twist
Drishti Point: Hastagrai or Hastagre (hands), Nasagrai or Nasagre (nose)



HEADSTAND 8 ARM POSITION: VARIOUS LEG POSITIONS

Feet Spread Intense Stretch Pose in Headstand 8

Prasarita Padottanasana in Shirshasana 8

(pruh-SAH-ri-tuh puh-do-tahn-AHS-uh-nuh in sheer-SHAHS-uh-nuh)

Also Known As: Feet Spread Full Forward Bend in Headstand 8
Modification: fingertips on the floor

Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Hastagrai or Hastagre (hands)



Revolved Leg Position of One-Legged King Pigeon 1 Version B in Headstand 8

Parivritta Pada Eka Pada Raja Kapotasana 1 B in Shirshasana 8

(puh-ri-VRIT-tuh PUH-duh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Modification: palms flat on the floor
Pose Type: inversion, forward bend, twist
Drishti Point: Nasagrai or Nasagre (nose), Hastagrai or Hastagre (hands)



Headstand 8

Shirshasana 8

(sheer-SHAHS-uh-nuh)

Modification: knees resting on the triceps, ankles crossed

1. hands apart, elbows touching, fingertips to the floor
2. hands together, elbows together, palms flat on the floor

Pose Type: inversion, forward bend

Drishti Point: Nasagrai or Nasagre (nose), Hastagrai or Hastagre (hands)

1.



2.



HEADSTAND 2 ARM POSITION: LOTUS

Upward Lotus Pose in Headstand 2

Urdhva Padmasana in Shirshasana 2

(OORD-vuh puhd-MAHS-uh-nuh in sheer-SHAHS-uh-nuh)

Also Known As: Upward Lotus in Hands Bound Headstand (Urdhva Padmasana in Baddha Hasta Shirshasana)

Pose Type: inversion

Drishti Point: Nasagrai or Nasagre (nose)

SHOULDERSTAND: BOTH LEGS STRAIGHT—DIFFERENT ARM POSITIONS

Inverted Pose Dedicated to Mythological Khimi Karani Pond

Viparita Khimi Karanyasana

(vi-puh-REE-tuh kuh-HEE-mee kuh-ruh-NEE-uhs-uh-nuh)

Also Known As: Inverted Lake Seal (Viparita Karani Mudra), Half Whole Body Pose (Ardha Sarvangasana)
Pose Type: inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Supported Whole Body Pose

Salamba Sarvangasana

(SAH-luhm-buh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Shoulderstand
Pose Type: inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Hands Bound Supported Whole Body Pose

Baddha Hasta Salamba Sarvangasana

(BUH-duh HUH-stuh SAH-luhm-buh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Shoulderstand
Pose Type: inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं यं हं ॐ



Unsupported Whole Body Pose

Niralamba Sarvangasana

(nir-AH-luhm-buh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Shoulderstand
Pose Type: inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nabhi, Nabhicakre, or Nabi Chakra (belly button)
लं हं ॐ



SHOULDERSTAND: ONE LEG UP, ONE LEG DOWN

Leg Contraction Pose in Supported Whole Body Pose

Pada Akunchanasana in Salamba Sarvangasana

(PUH-duh uh-kunch-AHS-uh-nuh in SAH-luhm-buh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Shoulderstand
Modification: one knee bent toward the forehead
Pose Type: inversion, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged Supported Whole Body Pose

Eka Pada Salamba Sarvangasana

(EY-kuh PUH-duh SAH-luhm-buh suhr-vuhng-GAHS-uh-nuh)

Also Known As: One-Legged Plow Pose (Eka Pada Halasana), Shoulderstand
Pose Type: inversion, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged Sideways Supported Whole Body Pose

Parshva Eka Pada Salamba Sarvangasana

(PAHRSH-vuh EY-kuh PUH-duh SAH-luhm-buh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Shoulderstand
Pose Type: inversion, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



SHOULDERSTAND: ONE LEG UP, ONE LEG DOWN—DIFFERENT ARM POSITIONS

One-Legged Unsupported Whole Body Pose

Eka Pada Niralamba Sarvangasana

(EY-kuh PUH-duh nir-AH-luhm-buh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Shoulderstand
Modification: both hands to the calf of the bottom leg
Pose Type: inversion, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Extended Hand to Big Toe Pose in Unsupported Whole Body Pose

Utthita Hasta Padangushtasana in Niralamba Sarvangasana

(UT-ti-tuh HUH-stuh puhd-ahng-goosh-tahn-AHS-uh-nuh in nir-AH-luhm-buh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Shoulderstand
Pose Type: inversion, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged Unsupported Whole Body Pose

Eka Pada Niralamba Sarvangasana

(EY-kuh PUH-duh nir-AH-luhm-buh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Shoulderstand
Modification: both arms along the sides of the torso
Pose Type: inversion, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Bound Inverted Tortoise Pose

Ardha Baddha Viparita Kurmasana

(UHR-duh BUH-duh vi-puh-REE-tuh koor-MAHS-uh-nuh)

Pose Type: inversion, forward bend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



SHOULDERSTAND: GARUDA LEGS

Leg Position of the Pose Dedicated to Garuda in Hands Bound Supported Whole Body Pose

Pada Garudasana in Baddha Hasta Salamba Sarvangasana

(PUH-duh guh-ru-DAHS-uh-nuh in BUH-duh HUH-stuh SAH-luhm-buh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Shoulderstand
Modification: knees toward the forehead
Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Leg Position of the Pose Dedicated to Garuda in Hands Bound Supported Whole Body Pose

Pada Garudasana in Baddha Hasta Salamba Sarvangasana

(PUH-duh guh-ru-DAHS-uh-nuh in BUH-duh HUH-stuh SAH-luhm-buh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Shoulderstand
Modification: legs extended toward the sky
Pose Type: inversion, forward bend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Leg Position of the Pose Dedicated to Garuda in Supported Whole Body Pose

Pada Garudasana in Salamba Sarvangasana

(PUH-duh guh-ru-DAHS-uh-nuh in SAH-luhm-buh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Shoulderstand
Pose Type: inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



SHOULDERSTAND: BOUND ANGLE & LOTUS

Bound Angle Pose in Whole Body Pose

Baddha Konasana in Sarvangasana

(BUH-duh ko-NAHS-uh-nuh in suhr-vuhng-GAHS-uh-nuh)

Also Known As: Shoulderstand
Pose Type: inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Upward Lotus in Whole Body Pose

Urdhva Padmasana in Salamba Sarvangasana

(OORD-vuh puhd-MAHS-uh-nuh in SAH-luhm-buh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Shoulderstand
Pose Type: inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Upward Lotus in Whole Body Pose

Urdhva Padmasana in Salamba Sarvangasana

(OORD-vuh puhd-MAHS-uh-nuh in SAH-luhm-buh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Shoulderstand
Modification: arms straight to the back, palms on the floor
Pose Type: inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Upward Lotus in Unsupported Whole Body Pose

Urdhva Padmasana in Niralamba Sarvangasana

(OORD-vuh puhd-MAHS-uh-nuh in nir-AH-luhm-buh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Shoulderstand
Pose Type: inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Inverted Ear Pressure Raised Up Lotus Pose

Viparita Karnapida Urdhva Padmasana

(vi-puh-REE-tuh kuhr-nah-PEED-uh OORD-vuh puhd-MAHS-uh-nuh)

Pose Type: inversion
Drishti Point: Nasagrai or Nasagre (nose)
ल व ह



SHOULDERSTAND: LOTUS—BACKBEND & FORWARD BEND

Intense Lotus Peacock Prep.

Uttana Padma Mayurasana Prep.

(ut-TAHN-uh PUHD-muh muh-yoor-AHS-uh-nuh)

Also Known As: Intense Front Body Stretching and Rejuvenating Lotus Pose (Purvottana Padma Sarvangasana)
Modification: knees off the floor, fists to the lower back
Pose Type: inversion, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ॐ

Upward Lotus Pose in Whole Body Pose

Urdhva Padmasana in Sarvangasana

(OORD-vuh puhd-MAHS-uh-nuh in suhr-vuhng-GAHS-uh-nuh)

Also Known As: Shoulderstand

Modification: 1. thighs parallel to the floor, elbows bent

2. arms straight

Pose Type: inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Embryo Pose in Whole Body Pose

Pindasana in Sarvangasana

(pin-DAHS-uh-nuh in suhr-vuhng-GAHS-uh-nuh)

Also Known As: Inverted Embryo Pose (Viparita Pindasana), Embryo Pose in Plow Pose (Pindasana in Halasana), Shoulderstand

Pose Type: inversion, forward bend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व र य ह ॐ



SHOULDERSTAND: LOTUS—KNEES ON THE FLOOR

Lotus Pose in Plow Pose

Padmasana in Halasana

(puhd-MAHS-uh-nuh in hul-AHS-uh-nuh)

Pose Type: inversion, forward bend

Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)

ल व र य ह



Sideways Embryo Pose in Whole Body Pose

Parshva Pindasana in Sarvangasana

(PAHRSH-vuh pin-DAHS-uh-nuh in suhr-vuhng-GAHS-uh-nuh)

Also Known As: Side Embryo Pose (Parshva Pindasana), Embryo Pose in Plow Pose (Pindasana in Halasana), Shoulderstand

Pose Type: inversion, forward bend, twist

Drishti Point: Nasagrai or Nasagre (nose)

ल व र य ह



SHOULDERSTAND: EAR PRESSURE POSE—FEET ON THE FLOOR

Inverted Tortoise Pose

Viparita Kurmasana

(vi-puh-REE-tuh koor-MAHS-uh-nuh)

Modification: 1. grabbing onto the feet

2. palms to the floor, fingertips facing to the back

Pose Type: inversion, forward bend

Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)

ल व र ह





Bound Inverted Tortoise Pose

Baddha Viparita Kurmasana

(BUH-duh vi-puh-REE-tuh koor-MAHS-uh-nuh)

Pose Type: inversion, forward bend, binding

Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)



SHOULDERSTAND: EAR PRESSURE POSE—FEET OFF THE FLOOR

Ear Pressure Pose Prep.

Karnapidasana Prep.

(kuhr-nah-pee-DAHS-uh-nuh)

Modification: knees to the temples, palms to the lower back

Pose Type: inversion, forward bend

Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)



Ear Pressure Pose Prep.

Karnapidasana Prep.

(kuhr-nah-pee-DAHS-uh-nuh)

Modification: one hand to the lower back; other arm up over the head, elbow bent, fingertips to the floor; both knees bent, one knee to the elbow of the front arm, heel of the other foot toward the sitting bone
Pose Type: inversion, forward bend
Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)
● ● ●



Ear Pressure Pose

Karnapidasana

(kuhr-nah-pee-DAHS-uh-nuh)

Modification: both knees bent, feet off the floor; arms straight behind the back and off the floor, palms up
Pose Type: inversion, forward bend, balance
Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)
● ● ●



SHOULDERSTAND: EAR PRESSURE POSE—HEELS TO THE SITTING BONES, GRABBING ONTO THE SHINS

Ear Pressure Pose

Karnapidasana

(kuhr-nah-pee-DAHS-uh-nuh)

Modification: both heels to the sitting bones, grabbing onto the ankles, elbows bent
Pose Type: inversion, forward bend
Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)



SHOULDERSTAND: EAR PRESSURE POSE—KNEES ON THE FLOOR—DIFFERENT ARM POSITIONS

Ear Pressure Pose

Karnapidasana

(kuhr-nah-pee-DAHS-uh-nuh)

Modification: palms to the lower back
Pose Type: inversion, forward bend
Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)



Sideways Ear Pressure Pose

Parshva Karnapidasana

(PAHRSH-vuh kuhr-nah-pee-DAHS-uh-nuh)

Also Known As: Side Contraction Pose (Parshva Akunchanasana)
Modification: palms to the lower back
Pose Type: inversion, forward bend, twist
Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)



Hands Bound Ear Pressure Pose

Baddha Hasta Karnapidasana

(BUH-duh HUH-stuh kuhr-nah-pee-DAHS-uh-nuh)

Modification: fingers interlocked
Pose Type: inversion, forward bend
Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)



Shivalinga Pose

Lingasana

(ling-GAHS-uh-nuh)

Also Known As: Ear Pressure Pose (Karnapidasana)
Pose Type: inversion, forward bend
Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)



Bound Hands Shivalinga Pose

Baddha Hasta Lingasana

(BUH-duh HUH-stuh ling-GAHS-uh-nuh)

Also Known As: Ear Pressure Pose (Karna Pidasana)
Pose Type: inversion, forward bend
Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)



Ear Pressure Pose

Karnapidasana

(kuhr-nah-pee-DAHS-uh-nuh)

Modification: grabbing onto the heels

Pose Type: inversion, forward bend

Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)

लं रं हं



PLOW POSE: LEGS STRAIGHT AND TOGETHER—DIFFERENT ARM POSITIONS

Plow Pose

Halasana

(huh-LAHS-uh-nuh)

Modification: palms to the lower back, toes pointed to the front

Pose Type: inversion, forward bend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

लं रं यं हं ॐ



Plow Pose

Halasana

(huh-LAHS-uh-nuh)

Modification: fingers to the toes, palms up
Pose Type: inversion, forward bend
Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)
लं रं हं



Plow Pose

Halasana

(huh-LAHS-uh-nuh)

Modification: arms straight to the back, palms on the floor
Pose Type: inversion, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं रं यं हं ॐ



Bound Hands Plow Pose

Baddha Hasta Halasana

(BUH-duh HUH-stuh huh-LAHS-uh-nuh)

Pose Type: inversion, forward bend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



PLOW POSE: LEGS TO THE SIDE & LEGS WIDE APART

Sideways Plow Pose

Parshva Halasana

(PAHRSH-vuh huh-LAHS-uh-nuh)

Modification: palms to the lower back

Pose Type: inversion, forward bend, twist

Drishti Point: Nabhi, Nabhicakre, or Nabi Chakra (belly button)



Hands Bound Feet Spread Wide Intense Stretch Pose in Plow Pose

Baddha Hasta Prasarita Padottanasana in Halasana

(BUH-duh HUH-stuh pruh-SAH-ri-tuh puh-do-tahn-AHS-uh-nuh in huh-LAHS-uh-nuh)

Also Known As: Hands Bound Feet Spread Wide Full Forward Bend in Plow Pose
Pose Type: inversion, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



PLOW POSE: ONE LEG STRAIGHT, ONE LEG BENT

One-Legged Elbow to Knee Plow Pose

Eka Pada Kurpara Janu Halasana

(EY-kuh PUH-duh kuhr-PAH-ruh JAH-nu hul-AHS-uh-nuh)

Modification: one hand to the lower back; other arm up over the head, elbow bent, fingertips to the floor; knees together, one leg straight; knee to the elbow, other knee bent, heel to the sitting bone
Pose Type: inversion, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र ह ॐ



Reclined Upward Foot Thunderbolt Pose

Supta Urdhva Pada Vajrasana

(SUP-tuh OORD-vuh PUH-duh vuhj-RAHS-uh-nuh)

Also Known As: Half Bound Lotus Pose in Whole Body Pose (Ardha Baddha Padmasana in Sarvangasana), Shoulderstand
Modification: 1. front side view
2. back side view
Pose Type: inversion, forward bend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ





Prone Poses

STOMACH ON THE FLOOR
CHEST FACING THE FLOOR
LOCUST POSE
SPHINX POSE
COBRA POSE
KING PIGEON POSE
UPWARD DOG POSE
COBRA POSE 2
BOW POSE
HALF LOTUS AND LOTUS BACKBENDS
SAGE GHERANDA’S POSE
BACKBENDS
CHIN AND CHEST ON THE FLOOR
CHEST AND KNEES ON THE FLOOR

Pose Dedicated to Makara—Prone Modification

Makarasana

(muh-kuh-RAHS-uh-nuh)

Also Known As: Crocodile Pose

Modification: whole body flat on the floor; arms straight out in front, palms together

Pose Type: prone

Drishti Point: Nasagrai or Nasagre (nose)

● ● ● ● ●



Side Corpse Pose

Parshva Shavasana

(PAHRSH-vuh shuh-VAHS-uh-nuh)

Pose Type: prone

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)

● ● ● ●



Downward Facing One Leg to the Side Pose

Adho Mukha Parshva Eka Padasana

(uh-DO MUK-uh PAHRSH-vuh EY-kuh puh-DAHS-uh-nuh)

Pose Type: prone

Drishti Point: Nasagrai or Nasagre (nose)

ल व र य ह



STOMACH ON THE FLOOR: ONE LEG STRAIGHT, ONE KNEE BENT—FOOT TO THE FLOOR ON THE SIDE

Intense Stretch Slithering Lizard Lunge Pose

Utthana Sarpa Godhasana

(ut-TAHN-uh SUHR-puh go-DAHS-uh-nuh)

Also Known As: Extended Lizard Tail Lunge Pose (Uttana Pristhasana)

Modification: foot to the elbow crease

Pose Type: prone

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व र य ह ॐ



Intense Stretch Slithering Lizard Lunge Pose

Utthan Sarpa Godhasana

(ut-TAHN-uh SUHR-puh go-DAHS-uh-nuh)

Also Known As: Extended Lizard Tail Lunge Pose (Uttana Pristhasana)
Modification: foot to the outside of the rib cage, arm binds around the leg
Pose Type: prone
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



STOMACH ON THE FLOOR: FROG POSE & LOTUS POSE

Frog Pose

Mandukasana

(muhn-doo-KAHS-uh-nuh)

Also Known As: Thavaliasana
Pose Type: prone
Drishti Point: Nasagrai or Nasagre (nose)



Lotus Staff Surrender Salutation Pose

Padma Danda Namaskarasana

(PUHD-muh DUHN-duh nuh-muhs-kahr-AHS-uh-nuh)

Modification: arms straight in front, palms down to the floor
Pose Type: prone
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य ॐ



Hidden Lotus Pose

Gupta Padmasana

(GUP-tuh puhd-MAHS-uh-nuh)

Pose Type: prone, mild backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



CHEST FACING THE FLOOR: TWISTS

Downward Facing Twisted Stomach Pose

Adho Mukha Jatara Parivartanasana

(uh-DO MUK-uh JAHT-uh-ruh puh-ri-vuhr-tuh-NAHS-uh-nuh)

Modification: knees together, legs bent
Pose Type: prone, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Downward Facing Twisted Stomach Pose

Adho Mukha Jatara Parivartanasana

(uh-DO MUK-uh JAHT-uh-ruh puh-ri-vuhr-tuh-NAHS-uh-nuh)

Modification: top leg straight, bottom knee bent
Pose Type: prone, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Downward Facing Twisted Stomach Pose

Adho Mukha Jatara Parivartanasana

(uh-DO MUK-uh JAHT-uh-ruh puh-ri-vuhr-tuh-NAHS-uh-nuh)

Modification: legs straight
Pose Type: prone, twist

Drishti Point: Nasagrai or Nasagre (nose)
ल



Pose Dedicated to St. Brighid of Kildare

Brighidasana

(bree-gid-AHS-uh-nuh)
Modification: bottom leg crossed under, looking straight ahead
Pose Type: prone, twist
Drishti Point: Nasagrai or Nasagre (nose)
ल व ह



CHEST FACING THE FLOOR: TWISTS—LEGS TO THE SIDE

Pose Dedicated to Sage Koundinya One-Legged Version 1—Prone Modification

Eka Pada Koundinyasana 1

(EY-kuh PUH-duh kown-din-YAHS-uh-nuh)
Modification: one arm straight to the side, bottom knee bent

Pose Type: arm balance, forward bend, twist
Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Pose Dedicated to Ashtavakra—Prone Modification

Ashtavakrasana

(uh-shtuh-vuh-KRAHS-uh-nuh)
Also Known As: Eight Angle Pose—Prone Modification
Modification: legs unhooked, bottom knee wrapped around the opposite forearm, top leg straight
Pose Type: arm balance, forward bend, twist
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Pose Dedicated to Ashtavakra—Prone Modification

Ashtavakrasana

(uh-shtuh-vuh-KRAHS-uh-nuh)
Also Known As: Eight Angle Pose—Prone Modification
Pose Type: arm balance, forward bend, twist
Drishti Point: Padayoragrai or Padayoragre (toes/feet)

ल व



CHEST FACING THE FLOOR: TWIST & VERTICAL SPLITS

Svastika Legs in Downward Facing Twisted Stomach Pose

Pada Svastikasana in Adho Mukha Jatara Parivartanasana

(PUH-duh svuh-sti-KAHS-uh-nuh in uh-DO MUK-uh JAHT-uh-ruh puh-ri-vuhr-tuh-NAHS-uh-nuh)

Modification: one arm straight out in front, palm down to the floor; other elbow bent, temple resting on the forearm of the bent arm

Pose Type: prone, twist

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)

ल व र य



Downward Facing Pose Dedicated to Trivikrama—Prone Modification

Adho Mukha Trivikramasana

(uh-DO MUK-uh tri-vi-kruhm-AHS-uh-nuh)

Pose Type: prone

Drishti Point: Hastagrai or Hastagre (hands)



Bound Downward Facing Pose Dedicated to Trivikrama—Prone Modification

Baddha Adho Mukha Trivikramasana

(BUH-duh uh-DO MUK-uh tri-vi-kruhm-AHS-uh-nuh)

Modification: back leg bent—toes pointing to the sky

Pose Type: prone, binding

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



LOCUST POSE: LEGS ON THE FLOOR, ARMS BEHIND

Cobra Pose 1

Bhujangasana 1

(buj-uhng-GAHS-uh-nuh)

Modification: palms lifted off the floor, elbows bent

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Locust Pose

Shalabhasana

(shuh-luh-BAHS-uh-nuh)

Modification: arms straight, palms facing up by the hips; feet on the floor
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



LOCUST POSE: LEGS AND CHEST OFF THE FLOOR—ARMS BEHIND ON THE FLOOR

Locust Pose

Shalabhasana

(shuh-luh-BAHS-uh-nuh)

Also Known As: Locust Pose B (Shalabhasana B)
Modification: palms to the floor by the bottom of the ribs, elbows bent at 90 degrees
Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Locust Pose

Shalabhasana

(shuh-luh-BAHS-uh-nuh)

Also Known As: Locust Pose A (Salabhasana A)
Modification: palms to the floor by the hips, arms straight, legs and chest lifted
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



LOCUST POSE: LEGS AND CHEST OFF THE FLOOR—ARMS BEHIND

Fingers to Head Reverse Prayer Locust Pose

Anguli Shirsha Viparita Namaskar Shalabhasana

(UHNG-goo-lee SHEER-shuh vi-puh-REE-tuh nuh-muhs-KAHR shuh-luh-BAHS-uh-nuh)

Also Known As: Back of the Body Prayer Fingers to Head Locust Pose (Paschima Namaskara Anguli Shirsha Shalabhasana)

Modification: feet on the floor
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



Pose Dedicated to Makara

Makarasana

(muh-kuh-RAHS-uh-nuh)
Also Known As: Crocodile Pose
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



Locust Pose

Shalabhasana

(shuh-luh-BAHS-uh-nuh)
Modification: arms open wide, fingertips pointing to the toes
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Hands Bound Locust Pose

Baddha Hasta Shalabhasana

(BUH-duh HUH-stuh shuh-luh-BAHS-uh-nuh)

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



LOCUST POSE: LEGS AND CHEST OFF THE FLOOR—ARMS IN FRONT

Locust Pose

Shalabhasana

(shuh-luh-BAHS-uh-nuh)

Also Known As: Crocodile Pose (Makarasana), Boat Pose (Navasana)

Modification: both arms straight in front, palms facing down

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) or Angushtamadhye or Angushta Ma Dyai (thumbs)



Hand Position of the Pose Dedicated to Garuda in Locust Pose

Hasta Garudasana in Shalabhasana

(HUH-stuh guh-ru-DAHS-uh-nuh in shuh-luh-BAHS-uh-nuh)

Pose Type: prone, backbend

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Inverted Locust Pose

Viparita Shalabhasana

(vi-puh-REE-tuh shuh-luh-BAHS-uh-nuh)

Modification: chin to the floor, legs lifted

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



LOCUST POSE: ONE LEG

Half Locust Pose

Ardha Shalabhasana

(UHR-duh shuh-luh-BAHS-uh-nuh)

Modification: hands to the floor by the hips, palms facing up, arms straight

Pose Type: prone, backbend

Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व र य ह ॐ



Hand Position of the Pose Dedicated to Garuda in Half Locust Pose

Hasta Garudasana in Ardha Shalabhasana

(HUH-stuh guh-ruh-DAHS-uh-nuh in UHR-duh shuh-luh-BAHS-uh-nuh)

Pose Type: prone, backbend

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)

ल व र य ह



Half Locust Pose

Ardha Shalabhasana

(UHR-duh shuh-luh-BAHS-uh-nuh)

Also Known As: Crocodile Pose (Makarasana)
Modification: one arm straight to the front—palm facing down, other hand to the floor by the hip—palm down
Pose Type: prone, backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व र य ह



One-Legged Frog Pose in Locust Pose

Eka Pada Bhekasana in Shalabhasana

(EY-kuh PUH-duh bey-KAHS-uh-nuh in shuh-luh-BAHS-uh-nuh)

Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) or Hastagrai or Hastagre (hands)
ल व र य ह ॐ



Mermaid Pose in Locust Pose

Naginyasana in Shalabhasana

(nuh-gin-YAHS-uh-nuh in shuh-luh-BAHS-uh-nuh)

Pose Type: prone, backbend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



SPHINX POSE: BOTH AND ONE LEG STRAIGHT

Supported Cobra Pose

Salamba Bhujangasana

(SAH-luhm-buh buj-uhng-GAHS-uh-nuh)

Also Known As: Sphinx Pose or Crocodile Pose (Makarasana)
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged Frog Pose

Eka Pada Bhekasana

(EY-kuh PUH-duh bey-KAHS-uh-nuh)

Modification: open ankles modification, heel to the floor by the hip socket
Pose Type: prone, backbend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ॐ



Leg Extended Uneven Supported Cobra Pose

Utthita Pada Vishama Salamba Bhujangasana

(UT-ti-tuh PUH-duh VISH-uh-muh SAH-luhm-buh buj-ung-GAHS-uh-nuh)

Also Known As: Uneven Sphinx Pose
Modification: 1. knee bent 2. leg straight
Pose Type: prone
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व ॐ





SPHINX POSE: BOTH KNEES BENT

Supported Cobra Pose

Salamba Bhujangasana

(SAH-luhm-buh buj-uhng-GAHS-uh-nuh)

Also Known As: Sphinx Pose or Crocodile Pose (Makarasana)
Modification: knees bent
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Feet to the Head Supported Cobra Pose

Shirsha Pada Salamba Bhujangasana

(SHEER-shuh PUH-duh SAH-luhm-buh buj-uhng-GAHS-uh-nuh)

Also Known As: Feet to the Head Sphinx Pose
Modification: toes to the forehead
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



Feet to the Face Supported Cobra Pose

Mukha Pada Salamba Bhujangasana

(MUK-uh PUH-duh SAH-luhm-buh buj-uhng-GAHS-uh-nuh)

Also Known As: Feet to the Face Sphinx Pose
Modification: heels to the forehead
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Padayoragrai or Padayoragre (toes/feet)
ल व र य ह ॐ



Downward Facing Bound Angle Pose

Adho Mukha Baddha Konasana

(uh-DO MUK-uh BUH-duh ko-NAHS-uh-nuh)

Modification: forearms to the floor

1. top view
2. side view

Pose Type: prone, backbend

Drishti Point: Nasagrai or Nasagre (nose)





Hidden Lotus Pose

Gupta Padmasana

(GUP-tuh puhd-MAHS-uh-nuh)

Modification: hands to the face on the elbows

Pose Type: prone, backbend

Drishti Point: Nasagrai or Nasagre (nose)

COBRA POSE

Cobra Pose

Bhujangasana

(buj-uhng-GAHS-uh-nuh)

Modification: palms on the floor, elbows bent
1. mild backbend
2. intense backbend
Pose Type: prone, backbend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)


1.


2.

Cobra Pose

Bhujangasana

(buj-uhng-GAHS-uh-nuh)

Modification: 1. elbows bent, fingertips to the floor 2. arms straight, palms to the floor

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)



1.



2.

Cobra Pose

Bhujangasana

(buj-uhng-GAHS-uh-nuh)

Modification: palms on the floor, arms straight, head to the glutes

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



KING PIGEON POSE: HANDS TO THE FLOOR

Half King Pigeon Pose

Ardha Raja Kapotasana

(UHR-duh RAH-juh kuh-po-TAHS-uh-nuh)

Modification: palms to the floor, one foot to the head
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged One Hand King Pigeon Pose

Eka Pada Eka Hasta Raja Kapotasana

(EY-kuh PUH-duh EY-kuh HUH-stuh RAH-juh kuh-po-TAHS-uh-nuh)

Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Hastagrai or Hastagre (hands)



King Pigeon Pose

Raja Kapotasana

(RAH-juh kuh-po-TAHS-uh-nuh)

Modification: palms to the floor, feet away from the head
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ



King Pigeon Pose

Raja Kapotasana

(RAH-juh kuh-po-TAHS-uh-nuh)

Modification: head touching the glutes, knees bent, feet away from the head
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Padayoragrai or Padayoragre (toes/feet)
ल व र य ह ॐ ॐ



King Pigeon Pose

Raja Kapotasana

(RAH-juh kuh-po-TAHS-uh-nuh)

Modification: palms to the floor, feet to the head
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
● ● ● ● ● ●



King Pigeon Pose

Raja Kapotasana

(RAH-juh kuh-po-TAHS-uh-nuh)

Modification: palms to the floor, feet to the shoulders
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
● ● ● ● ●

King Pigeon Pose

Raja Kapotasana

(RAH-juh kuh-po-TAHS-uh-nuh)

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

How to Perform the Pose:

1. Begin by lying flat on your stomach with your legs straight out behind you. Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale and bring your forearms to the floor with your shoulders on top of your elbows. Inhale, lengthen your neck, roll your shoulder blades down, and feel the backbend in your upper back.
3. On the next exhale, press strongly into your hands and straighten your arms. Walk your hands as close as you can toward you.
4. Exhale and bend both your knees, reaching your feet toward your head.
5. Inhale and shift your weight to your left hand. Exhale, bring your right arm behind you, and grab onto your right knee. On the next exhale, bring your left arm behind you and grab onto your left knee.
6. Exhale as you push through your chest, keeping the backbend in the upper back and pressing your feet to the crown of your head (Pose #1).
7. To deepen the pose, exhale and bring your feet to your shoulders (Pose #2).
8. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch.
9. Inhale as you release the pose, letting go of your knees. Bring your hands to the front and lower your chest and feet to the floor.

Modification: grabbing onto the knees
1. feet to the head
2. feet to the shoulders

raja = king, royal

kapota = pigeon

1.



2.



King Pigeon Pose Prep.

Raja Kapotasana Prep.

(RAH-juh kuh-po-TAHS-uh-nuh)

Modification: one hand to the floor, other hand grabbing onto the knee
Pose Type: prone, backbend
Drishti Point: Nasagrai or Nasagre (nose)



King Pigeon Pose Prep.

Raja Kapotasana Prep.

(RAH-juh kuh-po-TAHS-uh-nuh)

Modification: both hands grabbing onto the knees
1. looking straight ahead
2. head rolling back
Pose Type: prone, backbend
Drishti Point: 1. Nasagrai or Nasagre (nose)
2. Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)




2.

Feet to the Back King Pigeon Pose

Pada Paschima Raja Kapotasana

(PUH-duh PUHSH-chi-muh RAH-juh kuh-po-TAHS-uh-nuh)

Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



UPWARD DOG POSE: BOTH LEGS STRAIGHT

Upward Facing Dog Pose

Urdhva Mukha Shvanasana

(OORD-vuh MUK-uh shvuh-NAHS-uh-nuh)

Modification: toes pointed to the back, knees on the floor
1. looking straight ahead
2. head rolling back
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ





Upward Facing Dog Pose

Urdhva Mukha Shvanasana

(OORD-vuh MUK-uh shvuh-NAHS-uh-nuh)

Modification: toes pointed to the back, knees off the floor
1. looking straight ahead
2. head rolling back
Pose Type: prone, backbend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)




2.

UPWARD DOG POSE: BOTH LEGS STRAIGHT—ONE LEG, ONE ARM, & TO THE SIDE

Uneven One-Legged Upward Facing Dog Pose

Vishama Eka Pada Urdhva Mukha Shvanasana

(VISH-uh-muh EY-kuh PUH-duh OORD-vuh MUK-uh shvuh-NAHS-uh-nuh)

Modification: both toes pointed

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Sideways Upward Facing Dog Pose

Parshva Urdhva Mukha Shvanasana

(PAHRSH-vuh OORD-vuh MUK-uh shvuh-NAHS-uh-nuh)

Pose Type: prone, backbend, side bend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One Hand Upward Facing Dog Pose

Eka Hasta Urdhva Mukha Shvanasana

(EY-kuh HUH-stuh OORD-vuh MUK-uh shvuh-NAHS-uh-nuh)

Modification: toes pointed to the back
1. knees on the floor
2. knees off the floor

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





UPWARD DOG POSE: TOES CURLED IN

Upward Facing Dog Pose

Urdhva Mukha Shvanasana

(OORD-vuh MUK-uh shvuh-NAHS-uh-nuh)

Modification: toes curled in
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ



Sideways One-Legged Upward Facing Dog Pose

Parshva Eka Pada Urdhva Mukha Shvanasana

(PAHRSH-vuh EY-kuh PUH-duh OORD-vuh MUK-uh shvuh-NAHS-uh-nuh)

Modification: toes curled in
Pose Type: prone, backbend, twist
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ॐ



One-Legged Upward Facing Dog Pose

Eka Pada Urdhva Mukha Shvanasana

(EY-kuh PUH-duh OORD-vuh MUK-uh shvuh-NAHS-uh-nuh)

Modification: toes of the straight leg curled in; knee of the other leg bent, toes pointing up to the sky

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Big Toe Bow Pose in One-Legged Upward Facing Dog Pose

Ardha Padangushta Dhanurasana in Eka Pada Urdhva Mukha Shvanasana

(UHR-duh puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh in EY-kuh PUH-duh OORD-vuh MUK-uh shvuh-NAHS-uh-nuh)

Modification: grabbing onto the foot with overhead grip on the same side

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



UPWARD DOG POSE: TOES CURLED IN—LEGS CROSSED

Upward Facing Dog Pose

Urdhva Mukha Shvanasana

(OORD-vuh MUK-uh shvuh-NAHS-uh-nuh)

Modification: toes curled in, ankles crossed

1. knees on the floor
2. knees off the floor, looking straight ahead
3. knees off the floor, head rolling back

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)


1.


2.


3.

One-Legged Upward Facing Dog Pose

Eka Pada Urdhva Mukha Shvanasana

(EY-kuh PUH-duh OORD-vuh MUK-uh shvuh-NAHS-uh-nuh)

Modification: toes curled in, foot of the bent leg to the inside of the knee of the straight leg
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
● ● ● ● ●



UPWARD DOG POSE: ONE LEG BENT

Uneven One-Legged Upward Facing Dog Pose

Vishama Eka Pada Urdhva Mukha Shvanasana

(VISH-uh-muh EY-kuh PUH-duh OORD-vuh MUK-uh shvuh-NAHS-uh-nuh)

Modification: Leg 1: knee bent and on the floor, toes pointed to the sky Leg 2: straight and off the floor, toes pointed away
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
● ● ● ●



Half Bow Pose in One-Legged Upward Facing Dog Pose

Ardha Dhanurasana in Eka Pada Urdhva Mukha Shvanasana

(UHR-duh duh-nur-AHS-uh-nuh in EY-kuh PUH-duh OORD-vuh MUK-uh shvuh-NAHS-uh-nuh)

Modification: grabbing onto the opposite foot with under-head grip
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Bow Pose in One-Legged Upward Facing Dog Pose

Ardha Dhanurasana in Eka Pada Urdhva Mukha Shvanasana

(UHR-duh duh-nur-AHS-uh-nuh in EY-kuh PUH-duh OORD-vuh MUK-uh shvuh-NAHS-uh-nuh)
Modification: under-head grip on the same side
Pose Type: prone, backbend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Pose Dedicated to Siddhar Konganar in One-Legged Upward Facing Dog Pose

Ardha Konganarasana in Eka Pada Urdhva Mukha Shvanasana

(UHR-duh kong-guh-nuh-RAHS-uh-nuh in EY-kuh PUH-duh OORD-vuh MUK-uh shvuh-NAHS-uh-nuh)
Modification: grabbing onto the knee with under-head grip on the same side—foot to the armpit

Pose Type: prone, backbend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



COBRA POSE: UNDER-HEAD GRIP

Half King Pigeon Pose in One-Legged Big Toe Bow Pose

Ardha Raja Kapotasana in Eka Pada Padangushta Dhanurasana

(UHR-duh RAH-juh kuh-po-TAHS-uh-nuh in EY-kuh PUH-duh puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh)

Modification: Hand 1: grabbing onto the knee on the same side.
Hand 2: grabbing onto the big toe of the opposite foot with overhead grip
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Cobra Pose

Bhujangasana

(buj-uhng-GAHS-uh-nuh)

Also Known As: Supported Cobra Pose (Alamba Bhujangasana), King Pigeon Pose Prep. (Raja Kapotasana Prep.)
Modification: grabbing onto the knees with under-head grip
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



COBRA POSE: OVERHEAD GRIP

Upward Facing Unsupported Cobra Pose

Urdhva Mukha Niralamba Bhujangasana

(OORD-vuh MUK-uh nir-AH-luhm-buh buj-uhng-GAHS-uh-nuh)
Pose Type: prone, backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Unsupported Complete Cobra Pose

Niralamba Paripurna Bhujangasana

(nir-AH-luhm-buh puh-ri-POOR-nuh buj-uhng-GAHS-uh-nuh)

Pose Type: prone, backbend

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Complete Cobra Pose

Paripurna Bhujangasana

(puh-ri-POOR-nuh buj-uhng-GAHS-uh-nuh)

Modification: 1. grabbing onto the shins with overhead grip
2. grabbing onto the knees with overhead grip
3. grabbing onto the shins with overhead grip, toes curled in

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





2.



3.

BOW POSE: UNDER-HEAD GRIP—BOTH KNEES BENT

Bow Pose

Dhanurasana

(duh-nur-AHS-uh-nuh)

Modification: hands grabbing onto the ankles
1. on the inside of the ankles
2. on the outside of the ankles
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



1.



Bow Pose

Dhanurasana

(duh-nur-AHS-uh-nuh)

Modification: legs bent at 90 degrees; ankles and knees together, toes pointed to the sky
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Bow Pose

Dhanurasana

(duh-nur-AHS-uh-nuh)

Modification: legs bent at 90 degrees; ankles and knees together, toes flexed away from the head
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)

Sideways Bow Pose

Parshva Dhanurasana

(PAHRSH-vuh duh-nur-AHS-uh-nuh)

Pose Type: supine, prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged

Pose Dedicated to Siddhar Konganar

Eka Pada Konganarasana

(EY-kuh PUH-duh kong-guh-nuh-RAHS-uh-nuh)

Pose Type: prone, backbend

Drishti Point: Nasagrai or Nasagre (nose) or Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

How to Perform the Pose:

1. Begin by lying flat on your stomach with your legs straight out behind you. Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale and bring your forearms to the floor with your shoulders on top of your elbows. Inhale, lengthen your neck, roll your shoulder blades down, and feel the backbend in your upper back.
3. On the next exhale, press strongly into your hands and straighten your arms.
4. Exhale and bend both your knees, reaching your feet toward your head.
5. On the next exhale, reach your right hand behind you and grab onto your right shin. Keep sliding your right hand until your right foot reaches your right armpit and your right hand rests on your right knee.
6. Inhale and reach your left arm up and over your head. Exhale and grab onto your left foot with your left hand, keeping your left elbow close to your ear.
7. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch.
8. Inhale, let go of your legs one by one, and lower your chest and feet to the floor to come back to the starting position. Repeat on the opposite side.

eka = one

pada = foot or leg

Konganar = one of the Siddhars



Little Bow Pose

Laghu Dhanurasana

(LUH-gu duh-nur-AHS-uh-nuh)

Pose Type: prone, backbend

Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

● ● ● ●



Feet to the Head Little Bow Pose

Shirsha Pada Laghu Dhanurasana

(SHEER-suh PUH-duh LUH-gu duh-nur-AHS-uh-nuh)

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

● ● ● ● ● ●



Pose Dedicated to Siddhar Konganar

Konganarasana

(kong-guh-nuh-RAHS-uh-nuh)

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BOW POSE: OVERHEAD GRIP—BOTH KNEES BENT

One Hand Both Feet Big Toe Bow Pose

Eka Hasta Dwi Pada Padangushta Dhanurasana

(EY-kuh HUH-stuh DWI-puh-duh puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh)

Modification: grabbing onto the toes of both feet with one hand, other palm to the floor

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Big Toe Bow Pose

Padangushta Dhanurasana

(puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh)

Modification: head rolling back

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Big Toe Bow Pose

Padangushta Dhanurasana

(puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh)

Modification: 1. feet to the face
2. heels to the forehead

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



1.



2.

One Hand One-Legged Big Toe Bow Pose

Eka Hasta Eka Pada Padangushta Dhanurasana

(EY-kuh HUH-stuh EY-kuh PUH-duh puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh)

Modification: 1. one hand grabbing onto the foot on the opposite side with overhead grip
2. with backbend
Pose Type: prone, backbend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ


1.


2.

One Hand One-Legged Big Toe Bow Pose

Eka Hasta Eka Pada Padangushta Dhanurasana

(EY-kuh HUH-stuh PUH-duh puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh)

Modification: one hand grabbing onto the foot on the same side with overhead grip
Pose Type: prone, backbend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Both Hand One-Legged Big Toe Bow Pose

Dwi Hasta Eka Pada Padangushta Dhanurasana

(DWI-huh-stuh EY-kuh PUH-duh puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh)

Modification: both hands grabbing onto the foot with overhead grip
Pose Type: prone, backbend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BOW POSE: OVERHEAD GRIP—ONE KNEE BENT, ONE LEG STRAIGHT AND OFF THE FLOOR

Pose Dedicated to Goddess Kamala

Kamalasana

(kuh-muh-LAHS-uh-nuh)

Also Known As: Upward Facing One-Handed Big Toe Boat Pose (Urdhva Mukha Eka Hasta Padangushta Navasana)
Modification: 1: grabbing onto the ankle

2. foot to the shoulder

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)


1.


2.

BOW POSE: CRISS-CROSS LEGS AND ARMS

Revolved Bow Pose

Parivritta Dhanurasana

(puh-ri-VRIT-tuh duh-nur-AHS-uh-nuh)

Pose Type: prone, backbend, twist

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Padhayoragrai or Padayoragre (toes/feet)



Bow Pose

Dhanurasana

(duh-nur-AHS-uh-nuh)

Modification: legs crossed
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ॐ



Big Toe Bow Pose

Padangushta Dhanurasana

(puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh)

Also Known As: Difficult Bow Pose (Dur Dhanurasana)
Modification: one hand grabbing opposite ankle with under-head grip, other hand grabbing the opposite foot with overhead grip
1. one knee on the floor
2. both knees off the floor
Pose Type: prone, backbend
Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Big Toe Bow Pose

Padangushta Dhanurasana

(puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh)
Modification: one foot toward the shoulder
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



HALF LOTUS BACKBENDS

Half Lotus Frog Pose

Ardha Padma Bhekasana

(UHR-duh PUHD-muh bey-KAHS-uh-nuh)

Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ॐ



Half Lotus Bow Pose

Ardha Padma Dhanurasana

(UHR-duh PUHD-muh duh-nur-AHS-uh-nuh)

Modification: both hands grabbing onto the ankle with under-head grip
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



Half Lotus One Hand One-Legged Big Toe Bow Pose

Ardha Padma Eka Hasta Eka Pada Padangushta Dhanurasana

(UHR-duh PUHD-muh EY-kuh HUH-stuh EY-kuh PUH-duh puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh)

Modification: grabbing onto the foot with overhead grip on the same side, other hand to the floor

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व र य ह ॐ



LOTUS BACKBENDS

Lotus Cobra Pose

Padma Bhujangasana

(PUHD-muh buj-uhng-GAHS-uh-nuh)

Modification: both hands to the floor, hips off the floor, arms straight

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व र य ॐ



Lion Pose Dedicated to an Avatar of Lord Vishnu

Narasimhasana

(nuh-ruh-sim-HAHS-uh-nuh)

Also Known As: Lion Pose (Simhasana)
Modification: full lotus leg position
1. elbows bent, fingers in lion claw
2. arms straight, palms flat on the floor
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



1.



2.

One Hand Lotus Cobra Pose

Eka Hasta Padma Bhujangasana

(EY-kuh HUH-stuh PUHD-muh buj-uhng-GAHS-uh-nuh)

Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Lotus Cobra Pose

Padma Bhujangasana

(PUHD-muh buj-uhng-GAHS-uh-nuh)

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



[SAGE GHERANDA’S POSE: UNDER-HEAD GRIP](#)

Revolved Pose Dedicated to Sage Gheranda 1

Parivritta Ardha Gherandasana 1

(puh-ri-VRIT-tuh UHR-duh gey-ruhn-DAHS-uh-nuh)

Pose Type: prone, backbend, twist

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Half Pose Dedicated to Sage Gheranda 1

Ardha Gherandasana 1

(UHR-duh gey-ruhn-DAHS-uh-nuh)

Pose Type: prone, backbend
Drishti Point: Nasagrai or Nasagre (nose)
ल व र य



Pose Dedicated to Sage Gheranda 5B

Gherandasana 5 B

(gey-ruhn-DAHS-uh-nuh)

Modification: under-head grip, grabbing onto the ankle, elbow on the floor instead of the forearm
Pose Type: prone, backbend, twist
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



Pose Dedicated to Sage Gheranda 1B

Gherandasana 1 B

(gey-ruhn-DAHS-uh-nuh)

Modification: under-head grip
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Pose Dedicated to Sage Gheranda 6

Gherandasana 6

(gey-ruhn-DAHS-uh-nuh)

Modification: under-head grip
Pose Type: prone, backbend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



SAGE GHERANDA’S POSE: OVERHEAD GRIP

Pose Dedicated to Sage Gheranda 5

Gherandasana 5

(gey-ruhn-DAHS-uh-nuh)

Pose Type: prone, backbend, binding

Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व र य ॐ



Pose Dedicated to Sage Gheranda 1

Gherandasana 1

(gey-ruhn-DAHS-uh-nuh)

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व र य ह ॐ



Pose Dedicated to Sage Gheranda 2

Gherandasana 2

(gey-ruhn-DAHS-uh-nuh)

Pose Type: prone, backbend, binding

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Pose Dedicated to Sage Gheranda 3

Gherandasana 3

(gey-ruhn-DAHS-uh-nuh)

Pose Type: prone, backbend, binding

Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Pose Dedicated to Sage Gheranda 4

Gherandasana 4

(gey-ruhn-DAHS-uh-nuh)

Modification: 1. back view
2. front view
Pose Type: prone, backbend, binding, twist
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)


1.


2.

BACKBENDS: GARUDA LEGS: UNDER-HEAD GRIP

Twined Legs Cobra Pose

Parivitta Pada Bhujangasana

(puh-ri-VRIT-tuh PUH-duh buj-uhng-GAHS-uh-nuh)

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Supported Twined Legs Cobra Pose

Salamba Parivid Pada Bhujangasana

(SAH-luhm-buh PUH-ri-vid PUH-duh buj-uhng-GAHS-uh-nuh)

Also Known As: Supported Twined Legs Sphinx Pose

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Leg Position of the Pose Dedicated to Garuda in One Hand Bow Pose

Pada Garudasana in Eka Hasta Dhanurasana

(PUH-duh guh-ru-DAHS-uh-nuh in EY-kuh HUH-stuh duh-nur-AHS-uh-nuh)

Modification: one forearm to the floor, one hand to the ankle, under-head grip

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BACKBENDS: GARUDA LEGS: OVERHEAD GRIP

Leg Position of the Pose Dedicated to Garuda in One Hand Big Toe Bow Pose

Pada Garudasana in Eka Hasta Padangushta Dhanurasana

(PUH-duh guh-ru-DAHS-uh-nuh in EY-kuh HUH-stuh puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh)

Modification: forearm to the floor

1. grabbing onto the top foot
2. grabbing onto the bottom foot

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Unsupported Leg Position of the Pose Dedicated to Garuda in One Hand Big Toe Bow Pose

Niralamba Pada Garudasana in Eka Hasta Padangushta Dhanurasana

(nir-AH-luhm-buh puh-ri-vid-PUH-duh guh-ru-DAHS-uh-nuh in EY-kuh HUH-tuh puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh)

Also Known As: One Handed Twined Legs Bow Pose (Eka Hasta Parivid Pada Dhanurasana)
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Leg Position of the Pose Dedicated to Garuda in Big Toe Bow Pose

Pada Garudasana in Padangushta Dhanurasana

(PUH-duh guh-ru-DAHS-uh-nuh in puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh)

Also Known As: Difficult Bow Pose (Dur Dhanurasana)
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

CHIN ON THE FLOOR & EAR ON THE FLOOR

One-Legged Inverted Locust Pose

Eka Pada Viparita Shalabhasana

(EY-kuh PUH-duh vi-puh-REE-tuh shuh-luh-BAHS-uh-nuh)

Pose Type: prone, backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Ear Pressure Staff Formidable Face Pose

Karnapida Danda Ganda Bherundasana

(kuhr-nah-PEED-uh DUHN-duh GUHN-duh bey-run-DAHS-uh-nuh)

Pose Type: prone, backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



CHEST ON THE FLOOR: BOTH LEGS STRAIGHT

Inverted Locust Pose

Viparita Shalabhasana

(vi-puh-REE-tuh shuh-luh-BAHS-uh-nuh)

Modification: 1. chin to the floor
2. chest to the floor, chin lifted off the floor
Pose Type: prone, backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ



1.



2.

Formidable Face Staff Pose

Danda Ganda Bherundasana

(DUHN-duh GUHN-duh bey-run-DAHS-uh-nuh)

Also Known As: Intense Stretch Locust Pose A (Uttana Shalabhasana A)
Pose Type: prone, backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं रं यं हं ॐ



Inverted Locust Pose

Viparita Shalabhasana

(vi-puh-REE-tuh shuh-luh-BAHS-uh-nuh)

Also Known As: Raised Locust Pose—Urdhva Shalabhasana)
Modification: arms straight on the floor, palms down, chin lifted off the floor
Pose Type: prone, backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं रं यं हं ॐ



CHEST ON THE FLOOR: BOTH FEET TO HEAD

Formidable Face Pose

Ganda Bherundasana

(GUHN-duh bey-run-DAHS-uh-nuh)

Also Known As: Full Locust Pose (Purna Shalabhasana), Intense Stretch Locust Pose B (Uttana Shalabhasana B)

Modification: fingers pointing to the front of the body, feet to the head, chest on the floor 1. side view 2. front view

Pose Type: prone, backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

1.



2.



Formidable Face Pose

Ganda Bherundasana

(GUHN-duh bey-run-DAHS-uh-nuh)

Modification: fingers pointing to the back

1. knees apart
2. knees together, chin lifted off the floor

Pose Type: prone, backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Inverted Locust Pose

Viparita Shalabhasana

(vi-puh-REE-tuh shuh-luh-BAHS-uh-nuh)

Also Known As: Full Locust Pose (Purna Shalabhasana)
Modification: arms straight on the floor, palms down; feet to the head
Pose Type: prone, backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Formidable Face Pose

Ganda Bherundasana

(GUHN-duh bey-run-DAHS-uh-nuh)

Modification: feet to the head, grabbing onto both feet, chin off the floor

Pose Type: prone, backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

लं रं यं हं ॐ



CHIN ON THE FLOOR: FULL LOTUS

Inverted Lotus Peacock Pose

Viparita Padma Mayurasana

(vi-puh-REE-tuh PUHD-muh muh-yoor-AHS-uh-nuh)

Pose Type: prone, backbend, inversion

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

लं वं रं यं हं ॐ



Inverted Locust Pose with Lotus Legs

Padma Viparita Shalabhasana

(PUHD-muh vi-puh-REE-tuh shuh-luh-BAHS-uh-nuh)

Pose Type: prone, backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



CHEST ON THE FLOOR: FEET TO THE FLOOR

Inverted Locust Pose

Viparita Shalabhasana

(vi-puh-REE-tuh shuh-luh-BAHS-uh-nuh)

Modification: arms straight on the floor, palms down; feet toward the floor over the head, legs bent
1. heels up
2. heels down

Pose Type: prone, backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ


1.


2.

Formidable Face Pose

Ganda Bherundasana

(GUHN-duh bey-run-DAHS-uh-nuh)

Modification: feet on the floor, grabbing onto both ankles, chin off the floor
Pose Type: prone, backbend, inversion
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



CHEST AND KNEES ON THE FLOOR: KNEES UNDER THE HIPS

Intense Extended Puppy Dog Pose

Uttana Shvanakasana

(ut-TAHN-uh shvuh-nuh-KAHS-uh-nuh)

Also Known As: Heart Pose (Anahatasana Modification), Extended Dog Pose (Utthita Shvanasana)
Modification: 1. palms down to the floor 2. grabbing onto the heels
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

1.



2.



Intense Extended Puppy Dog Pose

Uttana Shvanakasana

(ut-TAHN-uh shvuh-nuh-KAHS-uh-nuh)

Also Known As: Prayer Heart Pose (Namaskar Anahatasana), Extended Dog Pose (Utthita Shvanasana)
Modification: thumbs to the upper back
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Water Grove Pose

Nirakunjasana

(neer-uh--kunj-AHS-uh-nuh)

Also Known As: Heart Pose (Anahatasana Modification)

Modification: arms in front, elbows bent; palms together; chin off the floor; heels toward the sitting bones

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Angushtamadhye or Angushta Ma Dyai (thumbs)



Hands Bound Water Grove Pose

Baddha Hasta Nirakunjasana

(BUH-duh HUH-stuh neer-uh-kunj-AHS-uh-nuh)

Also Known As: Heart Pose (Anahatasana Modification)

Modification: heels toward the sitting bones

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Pose Dedicated to Goddess Arani Prep.

Aranyasana Prep.

(uh-rah-NYAHS-uh-nuh)

Also Known As: Dragon Pose

Modification: 1. hands underneath the shoulders, elbows tucked in
2. arms reaching toward the knees, palms up

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

● ● ● ● ●

1.



2.



Pose Dedicated to Goddess Arani

Aranyasana

(uh-rah-NYAHS-uh-nuh)

Also Known As: Dragon Pose

Modification: 1. grabbing onto the shins
2. grabbing onto the hamstrings

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

● ● ● ● ●

1.



2.



CHEST AND KNEES ON THE FLOOR: KNEES UNDER THE HIPS—HALF LOTUS

Intense Extended Puppy Dog Pose

Uttana Shvanakasana

(ut-TAHN-uh shvuh-nuh-KAHS-uh-nuh)

Also Known As: Heart Pose (Anahatasana Modification), Extended Dog Pose (Utthita Shvanasana)
Modification: arms extended to the front
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Angushtamadhye or Angushta Ma Dyai (thumbs)
ल र य ह ॐ



Half Lotus Intense Extended Puppy Dog Pose

Ardha Padma Uttana Shvanakasana

(UHR-duh PUHD-muh ut-TAHN-uh shvuh-nuh-KAHS-uh-nuh)

Also Known As: Half Lotus Heart Pose (Ardha Padma Anahatasana), Half Lotus Extended Dog Pose (Ardha Padma Utthita Shvanasana)
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व र य ह ॐ



Half Bound Lotus Intense Extended Puppy Dog Pose

Ardha Baddha Padma Uttana Shvanakasana

(UHR-duh BUH-duh PUHD-muh ut-TAHN-uh shvuh-nuh-KAHS-uh-nuh)

Also Known As: Half Bound Lotus Heart Pose (Ardha Baddha Padma Anahatasana), Half Bound Lotus Extended Dog Pose (Ardha Baddha Padma Utthita Shvanasana)
Pose Type: prone, backbend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व र य ह ॐ



Lotus Intense Extended Puppy Dog Pose

Padma Uttana Shvanakasana

(PUHD-muh ut-TAHN-uh shvuh-nuh-KAHS-uh-nuh)

Also Known As: Lotus Heart Pose (Padma Anahatasana), Lotus Extended Dog Pose (Padma Utthita Shvanasana)
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Angushtamadhye or Angushta Ma Dyai (thumbs)



Upward Hands Bound Lotus Pose in Pose Dedicated to Goddess Arani

Urdhva Baddha Hasta Padmasana in Aranyasana

(OORD-vuh BUH-duh HUH-stuh puhd-MAHS-uh-nuh in uh-rah-NYAHS-uh-nuh)

Also Known As: Dragon Pose, Upward Bound Hand Lotus Heart Pose (Urdhva Baddha Hasta Padma Anahatasana)
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Feet Spread Wide Pose in Inverted Locust Pose

Prasarita Padottanasana in Viparita Shalabhasana

(pruh-SAH-ri-tuh puh-do-tahn-AHS-uh-nuh in vi-puh-REE-tuh shuh-luh-BAHS-uh-nuh)

Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व य ह ॐ



CHEST AND KNEES ON THE FLOOR: KNEES BEHIND HIPS—ARMS IN FRONT AND BEHIND THE BACK

Water Grove Pose

Nirakunjasana

(neer-uh-kunj-AHS-uh-nuh)

Also Known As: Heart Pose (Anahatasana Modification)
Modification: arms straight and crossed in front
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ



Water Grove Pose

Nirakunjasana

(neer-uh-kunj-AHS-uh-nuh)

Also Known As: Heart Pose (Anahatasana Modification)
Modification: chin and feet on the floor
1. knees on the floor
2. knees off the floor
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

1.



2.



Eight Limbs Pose

Ashtangasana

(uhsh-tahng-AHS-uh-nuh)

Also Known As: Eight Point Bow Pose (Ashtanga Namaskara)
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं रं यं हं ॐ



Reverse Prayer Water Grove Pose

Viparita Namaskar Nirakunjasana

(vi-puh-REE-tuh nuh-muhs-KAHR neer-uh-kunj-AHS-uh-nuh)

Also Known As: Back of the Body Prayer Water Grove Pose (Paschima Namaskara Nirakunjasana), Heart Pose Modification
Modification: toes curled in
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं रं यं हं ॐ



Hands Bound Water Grove Pose

Baddha Hasta Nirakunjasana

(BUH-duh HUH-stuh neer-uh-kunj-AHS-uh-nuh)

Also Known As: Heart Pose (Anahatasana Modification)

Modification: 1. knees on the floor, toes pointed to the back
2. knees on the floor, toes curled in
3. knees off the floor

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)







One-Legged Water Grove Pose

Eka Pada Nirakunjasana

(EY-kuh PUH-duh neer-uh-kunj-AHS-uh-nuh)

Also Known As: Heart Pose (Anahatasana Modification)
Modification: 1. forearms on the floor, toes pointed
2. palms to the floor by the rib cage, elbows bent, toes curled in
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ


1.


2.

Hands Bound One-Legged Water Grove Pose

Baddha Hasta Eka Pada Nirakunjasana

(BUH-duh HUH-stuh EY-kuh PUHD-uh neer-uh-kunj-AHS-uh-nuh)

Also Known As: Heart Pose (Anahatasana Modification)
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reverse Prayer One-Legged Water Grove Pose

Viparita Namaskar Eka Pada Nirakunjasana

(vi-puh-REE-tuh nuh-muhs-KAHR EY-kuh PUH-duh neer-uh-kunj-AHS-uh-nuh)

Also Known As: Back of the Body Prayer One-Legged Water Grove Pose (Paschima Namaskara Eka Pada Nirakunjasana), Heart Pose

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



CHEST AND KNEES ON THE FLOOR: KNEES BEHIND HIPS—ONE LEG STRAIGHT AND LIFTED—BOTTOM KNEE BENT

One-Legged Inverted Locust Pose Prep.

Eka Pada Viparita Shalabhasana Prep.

(EY-kuh PUH-duh vi-puh-REE-tuh shuh-luh-BAHS-uh-nuh)

Modification: forearms on the floor, knee of straight leg resting on the foot of the bottom leg

Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं वं यं हं ॐ



Revolved One-Legged Inverted Locust Pose Prep.

Parivritta Eka Pada Viparita Shalabhasana Prep.

(puh-ri-VRIT-tuh EY-kuh PUH-duh vi-puh-REE-tuh shuh-luh-BAHS-uh-nuh)

Modification: bottom leg bent, top leg straight, top knee resting on the sole of the bottom foot
Pose Type: forward bend, twist
Drishti Point: 1. Urdhva or Antara Drishti (up to the sky)
2. Hastagrai or Hastagre (hands)
लं वं रं यं



Upward Bound Hands One-Legged Inverted Locust Pose

Urdhva Baddha Hasta Eka Pada Viparita Shalabhasana

(OORD-vuh BUH-duh HUH-stuh EY-kuh PUH-duh vi-puh-REE-tuh shuh-luh-BAHS-uh-nuh)

Also Known As: Flying Locust Pose (Uddayate Shalabhasana)
Modification: 1. knee of the straight leg resting on the foot of the bottom leg
2. bottom foot away from the top leg
Pose Type: prone, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



1.



2.

CHEST AND KNEES ON THE FLOOR: KNEES BEHIND HIPS—BOTH LEGS BENT—ARMS IN FRONT

One-Legged Water Grove Pose

Eka Pada Nirakunjasana

(EY-kuh PUH-duh neer-uh-kunj-AHS-uh-nuh)

Also Known As: Heart Pose (Anahatasana Modification)
Modification: both knees bent; arms straight out in front, palms down
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Angushtamadhye or Angushta Ma Dyai (thumbs)



Half Bow Pose in One-Legged Water Grove Pose

Ardha Dhanurasana in Eka Pada Nirakunjasana

(IUHR-duh duh-nur-AHS-uh-nuh in EY-kuh PUH-duh neer-uh-kunj-AHS-uh-nuh)

Also Known As: Heart Pose (Anahatasana Modification)
Modification: 1. right front side view
2. right back side view
Pose Type: backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व र य ह ॐ


1.


2.

One-Legged Water Grove Pose

Eka Pada Nirakunjasana

(EY-kuh PUH-duh neer-uh-kunj-AHS-uh-nuh)

Also Known As: Heart Pose (Anahatasana Modification)
Modification: both knees bent
1. arms straight to the back, palms down
2. arms lifted off the floor
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Bow Pose in One-Legged Water Grove Pose

Dhanurasana in Eka Pada Nirakunjasana

(duh-nur-AHS-uh-nuh in EY-kuh PUH-duh neer-uh-kunj-AHS-uh-nuh)

Also Known As: Heart Pose (Anahatasana Modification)
Modification: both hands grabbing the top foot with under-head grip; the knee of the bottom leg on the floor, toes pointing to the sky
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Bow Pose in One-Legged Water Grove Pose

Ardha Dhanurasana in Eka Pada Nirakunjasana

(UHR-duh duh-nur-AHS-uh-nuh in EY-kuh PUH-duh neer-uh-kunj-AHS-uh-nuh)

Also Known As: Heart Pose (Anahatasana Modification)

Modification: grabbing onto the foot on the opposite side, under-head grip; other hand to the lower back, palm up

Pose Type: prone, backbend, binding

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



CHEST AND KNEES ON THE FLOOR: KNEES BEHIND HIPS—BOTTOM KNEE BENT—OVERHEAD GRIP

Big Toe Bow Pose in One-Legged Water Grove Pose

Padangushta Dhanurasana in Eka Pada Nirakunjasana

(puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh in EY-kuh PUH-duh neer-uh-kunj-AHS-uh-nuh)

Also Known As: Heart Pose (Anahatasana Modification)

Pose Type: prone, backbend

Drishti Point: Padayoragrai or Padayoragre (toes/feet), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One Leg to the Head Water Grove Pose

Eka Pada Shirsha Nirakunjasana

(EY-kuh PUH-duh SHEER-shuh neer-uh-kunj-AHS-uh-nuh)

Also Known As: Heart Pose (Anahatasana Modification)
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



CHEST AND KNEES ON THE FLOOR: KNEES BEHIND HIPS—BOTTOM KNEE BENT—UNDER-HEAD & OVERHEAD GRIP

One-Legged Inverted Locust Pose

Eka Pada Viparita Shalabhasana

(EY-kuh PUH-duh vi-puh-REE-tuh shuh-luh-BAHS-uh-nuh)

Modification: one palm to the floor at the bottom of the ribs, other arm straight, palm down; both

knees bent, knee of the top leg resting on the foot of the bottom leg
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



One Hand to Foot Inverted Locust Pose

Eka Hasta Pada Viparita Shalabhasana

(EY-kuh HUH-stuh PUH-duh vi-puh-REE-tuh shuh-luh-BAHS-uh-nuh)

Modification: grabbing onto the top foot with the opposite hand; other arm straight, palm down to the floor; both knees bent, knee of the top leg resting on the foot of the bottom leg
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ॐ



Both Hands to One Foot Inverted Locust Pose

Dwi Hasta Eka Pada Viparita Shalabhasana

(DWI-huh-stuh EY-kuh PUH-duh vi-puh-REE-tuh shuh-luh-BAHS-uh-nuh)

Modification: both hands grabbing the top foot with under-head grip; top knee resting on the sole of the bottom foot

Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One Foot to the Shoulder Inverted Locust Pose

Eka Pada Bhuja Viparita Shalabhasana

(EY-kuh PUH-duh buj-uh vi-puh-REE-tuh shuh-luh-BAHS-uh-nuh)

Modification: grabbing onto the toes of the top foot; the quadriceps of the top leg resting on the sole of the bottom foot
Pose Type: prone, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Supine Poses

- SHOULDER ON THE FLOOR
- TRICEPS ON THE FLOOR
- ELBOW ON THE FLOOR
- FOREARM ON THE FLOOR
- EASTERN INTENSE STRETCH
- BRIDGE POSES
- HEAD AND SITTING BONES ON THE FLOOR
- BOUND ANGLE POSE
- KNEES BENT
- HAPPY BABY POSE
- ONE AND BOTH FEET BEHIND HEAD
- HORIZONTAL SPLITS
- ONE KNEE BENT TO THE BACK (VARIATIONS)
- VERTICAL SPLITS
- BOTH LEGS STRAIGHT AND TOGETHER
- SUPINE LOTUS AND CORPSE POSE

Sideways Wind Relieving Pose

Parshva Vayu Muktyasana

(PAHRSH-vuh VAH-yu muk-TYAHS-uh-nuh)

Modification: palms together in front of the face, knees together
Pose Type: supine (on the side)
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Arms Raised Sideways Wind Relieving Pose

Urdhva Hasta Parshva Vayu Muktyasana

(OORD-vuh HUH-stuh PAHRSH-vuh VAH-yu muk-TYAHS-uh-nuh)

Pose Type: supine (on the side)
Drishti Point: Urdhva or Antara Drishti (up to the sky)



Sideways Wind Relieving Pose

Parshva Vayu Muktyasana

(PAHRSH-vuh VAH-yu muk-TYAHS-uh-nuh)

Modification: bottom leg straight; top knee bent, foot to the knee of the straight leg

Pose Type: supine (on the side)

Drishti Point: Nasagrai or Nasagre (nose)



Infinity Pose

Anantasana

(uhn-uhnt-AHS-uh-nuh)

Also Known As: Sleeping Vishnu Pose

Modification: top leg lifted in front of the body, bottom leg straight

Pose Type: supine (on the side), forward bend

Drishti Point: Nasagrai or Nasagre (nose), Padayoragrai or Padayoragre (toes/feet)



Infinity Pose

Anantasana

(uhn-uhnt-AHS-uh-nuh)

Also Known As: Sleeping Vishnu Pose

Modification: top leg straight and lifted; bottom leg bent, toes pointing to the back
Pose Type: supine (on the side)
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
लं वं



SHOULDER ON THE FLOOR: TWISTS AND BINDING

Svastika Legs in Twisted Stomach Pose

Pada Svastikasana in Jatara Parivartanasana

(PUH-duh svuh-sti-KAHS-uh-nuh in JAH-tuh-ruh puh-ri-vuhrt-ahn-AHS-uh-nuh)
Modification: grabbing onto the back foot, heel toward the glutes
Pose Type: supine (on the side), twist
Drishti Point: Hastagrai or Hastagre (hands)
लं वं हं ॐ



Revolved One-Legged King Pigeon Pose 1

Parivritta Eka Pada Raja Kapotasana 1

(puh-ri-VRIT-tuh EY-kuh PUH-duh RAH-juh kuh-po-TAHS-uh-nuh)
Modification: back knee bent, both hands to the back foot; front foot to hip socket

Pose Type: supine (on the side), twist
Drishti Point: Urdhva or Antara Drishti (up to the sky)
● ● ● ●



One-Legged Bound Infinity Pose

Eka Pada Baddha Anantasana

(EY-kuh PUH-duh BUH-duh uhn-uhnt-AHS-uh-nuh)

Also Known As: One-Legged Bound Sleeping Vishnu Pose
Modification: bottom leg bent, heel toward the glutes; top leg bent
Pose Type: supine (on the side), twist, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
● ● ● ● ●



SHOULDER ON THE FLOOR: HALF LOTUS BACKBEND—UNDER-HEAD & OVERHEAD GRIP

Sideways Half Lotus Bow Pose

Parshva Ardha Padma Dhanurasana

(PAHRSH-vuh UHR-duh PUHD-muh duh-nur-AHS-uh-nuh)

Modification: grabbing onto the bottom foot with both hands with under-head grip

Pose Type: supine (on the side), backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

● ● ● ● ● ●



Sideways Half Lotus One-Handed Big Toe Bow Pose

Parshva Ardha Padma Eka Hasta Padangushta Dhanurasana

(PAHRSH-vuh UHR-duh PUHD-muh EY-kuh HUH-stuh puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh)

Modification: grabbing onto the bottom foot with overhead grip on the same side, top arm straight, fingertips to the sky

Pose Type: supine (on the side), backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

● ● ● ● ● ● ●



Sideways Half Lotus Two-Handed Big Toe Bow Pose

Parshva Ardha Padma Dwi Hasta Padangushta Dhanurasana

(PAHRSH-vuh UHR-duh PUHD-muh DWI-huh-stuh puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh)

Modification: overhead grip, both hands grabbing onto the foot

Pose Type: supine (on the side), backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



SHOULDER ON THE FLOOR: FOOT TO THE THIGH, HALF LOTUS & LOTUS

Mermaid Pose in Infinity Pose

Naginyasana in Anantasana

(nuh-gin-YAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Also Known As: Mermaid Pose in Sleeping Vishnu Pose
Pose Type: supine (on the side), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Sideways Half Lotus Bow Pose

Parshva Ardha Padma Dhanurasana

(PAHRSH-vuh UHR-duh PUHD-muh duh-nur-AHS-uh-nuh)

Modification: grabbing onto the top foot with the bottom hand; grabbing onto the bottom foot with top hand

1. front view
2. back view

Pose Type: supine (on the side), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं वं रं यं हं ॐ


1.


2.

Hands Bound Lotus Pose in Infinity Pose

Baddha Hasta Padmasana in Anantasana

(BUH-duh HUH-stuh puhd-MAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)
Also Known As: Hands Bound Lotus Pose in Sleeping Vishnu Pose
Pose Type: supine (on the side), mild backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं वं रं यं हं ॐ



Hands Bound Infinity Pose

Baddha Hasta Anantasana

(BUH-duh HUH-stuh uhn-uhnt-AHS-uh-nuh)

Also Known As: Hands Bound Sleeping Vishnu Pose

Modification: 1. bottom leg bent, top leg straight and lifted; resting on the arms and the bent knee for support

2. bottom leg straight, top leg straight and lifted; arms lifted off the floor

Pose Type: supine (on the side), backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Hands Bound Half Lotus Pose in Infinity Pose

Baddha Hasta Ardha Padmasana in Anantasana

(BUH-duh HUH-stuh UHR-duh puhd-MAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Also Known As: Hands Bound Half Lotus Pose in Sleeping Vishnu Pose

Modification: 1. front view

2. back view

Pose Type: supine (on the side), backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)


1.


2.

TRICEPS ON THE FLOOR: HAND TO THE HEAD—LEGS TOGETHER & LEGS APART

Infinity Pose

Anantasana

(uhn-uhnt-AHS-uh-nuh)

Also Known As: Sleeping Vishnu Pose
Modification: both legs straight and together; bottom leg on the floor
Pose Type: supine (on the side), side bend
Drishti Point: Padhayoragrai or Padayoragre (toes/feet)



Infinity Pose

Anantasana

(uhn-uhnt-AHS-uh-nuh)

Also Known As: Sleeping Vishnu Pose
Modification: legs straight, together and lifted off the floor
Pose Type: supine (on the side), core, side bend
Drishti Point: Nasagrai or Nasagre (nose)



Infinity Pose

Anantasana

(uhn-uhnt-AHS-uh-nuh)

Also Known As: Sleeping Vishnu Pose
Modification: both legs straight, top leg lifted, bottom leg on the floor
Pose Type: supine (on the side), core, side bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Urdhva or Antara Drishti (up to the sky)



Extended Hand to Big Toe Pose in Infinity Pose

Utthita Hasta Padangushtasana in Anantasana

(UT-ti-tuh HUH-stuh puhd-ahng-goosh-TAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Also Known As: Extended Hand to Big Toe Pose in Sleeping Vishnu Pose
Pose Type: supine (on the side), forward bend, side bend
Drishti Point: Nasagrai or Nasagre (nose)



Sundial Pose in Infinity Pose

Surya Yantrasana in Anantasana

(SOOR-yuh yuhn-TRAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Also Known As: Sundial Pose in Sleeping Vishnu Pose
Modification: 1. grabbing onto the heel on the outside of the calf
2. grabbing onto the heel on the inside of the calf
Pose Type: supine (on the side), forward bend, side bend
Drishti Point: Nasagrai or Nasagre (nose)


1.


2.

TRICEPS ON THE FLOOR: BOTH KNEES BENT

Infinity Pose

Anantasana

(uhn-uhnt-AHS-uh-nuh)

Also Known As: Sleeping Vishnu Pose
Modification: top knee to the top shoulder; both knees bent
Pose Type: supine (on the side), forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) or Padhayoragrai or Padayoragre (toes/feet)



Bound Angle Pose in Infinity Pose

Baddha Konasana in Anantasana

(BUH-duh ko-NAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Also Known As: Bound Angle Pose in Sleeping Vishnu Pose
Modification: 1. top wrist on the top knee
2. top hand grabbing onto the top foot
Pose Type: supine (on the side), side bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) or Hastagrai or Hastagre (hands)





TRICEPS ON THE FLOOR: BOTTOM LEG STRAIGHT—BACKBENDS

Half Frog Pose Prep. in Infinity Pose

Ardha Bhekasana in Anantasana

(UHR-duh bey-KAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Also Known As: Half Frog Pose Prep. in Sleeping Vishnu Pose
Modification: hand in beginner modification; neutral spine, top leg moving into a half-frog leg position

Pose Type: supine (on the side), mild backbend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
लं वं रं यं



Half Bow Pose in Infinity Pose

Ardha Dhanurasana in Anantasana

(UHR-duh duh-nur-AHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)
Also Known As: Half Bow Pose in Sleeping Vishnu Pose
Pose Type: supine (on the side), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं वं रं यं हं ॐ



Half Big Toe Bow Pose in Infinity Pose

Ardha Padangushta Dhanurasana in Anantasana

(UHR-duh puhd-ahng-GOOSH-tuh duh-nur-AHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)
Also Known As: Half Big Toe Bow Pose in Sleeping Vishnu Pose
Pose Type: supine (on the side), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं वं रं यं हं ॐ



TRICEPS ON THE FLOOR: ONE LEG STRAIGHT, OTHER FOOT TO THE HIP SOCKET

Infinity Pose

Anantasana

(uhn-uhnt-AHS-uh-nuh)

Also Known As: Sleeping Vishnu Pose
Modification: top foot to the hip socket, toes touching the floor; bottom leg straight on the floor
Pose Type: supine (on the side), side bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Half Lotus Pose in Infinity Pose

Ardha Padmasana in Anantasana

(UHR-duh puhd-MAHS-uh-nuh in anan-TAHS-annauhn-uhnt-AHS-uh-nuh)

Also Known As: Half Lotus Pose in Sleeping Vishnu Pose
Modification: bottom foot in half lotus, top leg lifted and straight
Pose Type: supine (on the side), side bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



TRICEPS ON THE FLOOR: HALF LOTUS & FULL LOTUS

Half Lotus Mermaid Pose in Infinity Pose

Ardha Padma Naginyasana in Anantasana

(UHR-duh PUHD-muh nuh-gin-YAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Also Known As: Half Lotus Mermaid Pose in Sleeping Vishnu Pose
Pose Type: supine (on the side), backbend, side bend
Drishti Point: Hastagrai or Hastagre (hands)



Lotus Pose in Infinity Pose

Padmasana in Anantasana

(puhd-MAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Also Known As: Lotus Pose in Sleeping Vishnu Pose
Pose Type: supine (on the side), side bend, knee, ankle opener
Drishti Point: Hastagrai or Hastagre (hands)



[ELBOW ON THE FLOOR: BOTTOM LEG STRAIGHT, TOP LEG CROSSED OVER](#)

Infinity Pose

Anantasana

(uhn-uhnt-AHS-uh-nuh)

Also Known As: Sleeping Vishnu Pose
Modification: elbow to the floor, top knee bent, leg crossed over in front of the body; bottom leg straight
1. palm of the top hand on the floor
2. top hand on the top knee
Drishti Point: Urdhva or Antara Drishti (up to the sky)





Infinity Pose

Anantasana

(uhn-uhnt-AHS-uh-nuh)

Also Known As: Sleeping Vishnu Pose

Modification: elbow to the floor, hands in Anjali Mudra (Hands in Prayer); top knee bent, foot by the hip, bottom leg straight

1. bottom leg on the floor
2. bottom leg lifted off the floor

Pose Type: 1. supine (on the side), side bend

2. supine (on the side), side bend, core

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

● ● ●





Infinity Pose

Anantasana

(uhn-uhnt-AHS-uh-nuh)

Also Known As: Sleeping Vishnu Pose
Modification: top leg crossed over in front, toes on the floor; bottom leg bent, toes to the back; elbow to the floor, other arm straight fingertips to the sky
Pose Type: supine (on the side)
Drishti Point: Hastagrai or Hastagre (hands)



Half Lotus Pose in Infinity Pose

Ardha Padmasana in Anantasana

(UHR-duh puhd-MAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Also Known As: Half Lotus Pose in Sleeping Vishnu Pose
Modification: top leg in half lotus; bottom leg bent, heel to the sitting bone; elbow to the floor, other arm straight fingertips to the sky
Pose Type: supine (on the side)
Drishti Point: Hastagrai or Hastagre (hands)



Leg Position of the Pose Dedicated to Garuda in Infinity Pose

Pada Garudasana in Anantasana

(PUH-duh guh-ru-DAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Also Known As: Leg Position of the Pose Dedicated to Garuda in Sleeping Vishnu Pose
Modification: elbow to the floor, hands behind the head
Pose Type: supine (on the side)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



FOREARM ON THE FLOOR: ONE LEG CROSSED OVER & HALF LOTUS

Infinity Pose

Anantasana

(uhn-uhnt-AHS-uh-nuh)

Also Known As: Sleeping Vishnu Pose
Modification: top leg crossed over; forearm to the floor, top elbow resting on the top knee
Pose Type: supine (on the side)
Drishti Point: Hastagrai or Hastagre (hands)



Extended Hand to Big Toe Half Cow Face Western Intense Stretch in Infinity Pose

Utthita Hasta Padangushta Ardha Gomukha Paschimottanasana in Anantasana

(UT-ti-tuh HUH-stuh puhd-ahng-GOOSH-tuh UHR-duh go-MUK-uh puhsh-chi-mo-tahn-AHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Also Known As: Extended Hand to Big Toe Half Cow Face Forward Bend in Infinity Pose, Extended Hand to Big Toe Half Cow Face Western Intense Stretch in Sleeping Vishnu Pose
Modification: forearm to the floor; top leg crossed over; grabbing onto the big toe of the bottom foot, leg off the floor
Pose Type: supine (on the side), forward bend
Drishti Point: Hastagrai or Hastagre (hands)



Half Lotus Pose in Infinity Pose

Ardha Padmasana in Anantasana

(UHR-duh puhd-MAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Also Known As: Half Lotus Pose in Sleeping Vishnu Pose
Modification: top foot to the bottom knee; top forearm to the top knee

Pose Type: supine (on the side), mild backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Lotus Extended Hand to Leg Pose in Infinity Pose

Ardha Padma Utthita Pada Hastasana in Anantasana

(UHR-duh PUHD-muh UT-ti-tuh PUH-duh huh-STAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Also Known As: Half Lotus Extended Hand to Leg Pose in Sleeping Vishnu Pose
Pose Type: supine (on the side), forward bend, mild backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



FOREARM ON THE FLOOR: TOP LEG STRAIGHT, BOTTOM FOOT TO THE THIGH

Half Bound Angle Pose in Infinity Pose

Ardha Baddha Konasana in Anantasana

(UHR-duh BUH-duh ko-NAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Also Known As: Half Bound Angle Pose in Sleeping Vishnu Pose
Modification: forearm to the floor

1. finger tips of the top arm to the floor in front of the abdomen, elbow bent
2. top arm straight and parallel to the top leg

Pose Type: supine (on the side), side bend

Drishti Point: Padayoragrai or Padayoragre (toes/feet), Hastagrai or Hastagre (hands)





EASTERN INTENSE STRETCH: SITTING BONES BELOW KNEES—ONE LEG OFF FLOOR & TWISTS

Tip Toe Half Eastern Intense Stretch Pose

Prapada Ardha Purvottanasana

(PRUH-puh-duh UHR-duh poor-vo-tahn-AHS-uh-nuh)

Also Known As: Tip Toe Half Reverse Plank Pose

Modification: prep—sitting bones below the knee level, on the fingertips

Pose Type: standing, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Eastern Intense Stretch Pose

Ardha Purvottanasana

(UHR-duh poor-vo-tahn-AHS-uh-nuh)

Also Known As: Half Reverse Plank

Modification: mild prep—sitting bones slightly off the floor, feet flat on the floor; palms flat on the floor, fingertips pointing to the heels

Pose Type: standing, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Fire Log Pose in Half Eastern Intense Stretch Pose

Ardha Agnistambhasana in Ardha Purvottanasana

(UHR-duh uhg-ni-stuhm-BAHS-uh-nuh in UHR-duh poor-vo-tahn-AHS-uh-nuh)

Also Known As: Half Firelog Pose in Half Reverse Plank

Modification: prep—sitting bones slightly off the floor; elbows bent, fingertips pointing to the heels

Pose Type: standing, forward bend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Intense Ankle Stretch Pose in One-Legged Half Eastern Intense Stretch Pose

Uttana Kulpasana in Eka Pada Ardha Purvottanasana

(ut-TAHN-uh kul-PAHS-uh-nuh in EY-kuh PUH-duh UHR-duh poor-vo-tahn-AHS-uh-nuh)

Also Known As: Intense Ankle Stretch Pose in One-Legged Half Reverse Plank
Modification: knee bent toward the chest, fingertips pointing away from the heels
Pose Type: standing, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)



Revolved Half Eastern Intense Stretch Pose

Parivritta Ardha Purvottanasana

(puh-ri-VRIT-tuh UHR-duh poor-vo-tahn-AHS-uh-nuh)

Also Known As: Revolved Half Reverse Plank Pose
Modification: opposite elbow to knee of the straight leg
Pose Type: arm balance, forward bend, twist
Drishti Point: Hastagrai or Hastagre (hands)



EASTERN INTENSE STRETCH: KNEES BENT

Half Eastern Intense Stretch Pose

Ardha Purvottanasana

(UHR-duh poor-vo-tahn-AHS-uh-nuh)

Also Known As: Reverse Table Top and Half Reverse Plank Pose
Modification: prep—knees bent and on top of the ankles, fingertips pointing away from the heels
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
● ● ● ● ●



Uneven Leg Position of Cow Face Pose in Half Eastern Intense Stretch Pose

Vishama Pada Gomukhasana in Ardha Purvottanasana

(VISH-uh-muh PUH-duh go-muk-AHS-uh-nuh in UHR-duh poor-vo-tahn-AHS-uh-nuh)

Also Known As: Uneven Leg Position of Cow Face Pose in Reverse Table Top and Uneven Leg Position of Cow Face Pose in Half Reverse Plank
Modification: knees bent, fingertips pointing to the heels

Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं वं रं यं हं ॐ



One-Legged Half Eastern Intense Stretch Pose

Eka Pada Ardha Purvottanasana

(EY-kuh PUH-duh UHR-duh poor-vo-tahn-AHS-uh-nuh)
Also Known As: One-Legged Reverse Table Top and One-Legged Half Reverse Plank Pose
Modification: prep—one knee bent, foot on the floor; other leg straight; knees in line, fingertips pointing to the heels
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं रं यं हं ॐ



One-Legged Half Eastern Intense Stretch Pose

Eka Pada Ardha Purvottanasana

(EY-kuh PUH-duh UHR-duh poor-vo-tahn-AHS-uh-nuh)
Also Known As: One-Legged Reverse Table Top and One-Legged Half Reverse Plank
Modification: prep—both knees bent, top foot to the knee, fingertips pointing to the heels

Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged Half Eastern Intense Stretch Pose in Pose Dedicated to Sage Vasistha on the Forearm

Eka Pada Ardha Purvottanasana in Vasishtasana

(EY-kuh PUH-duh UHR-duh poor-vo-tahn-AHS-uh-nuh in vuh-sish-TAHS-uh-nuh)

Also Known As: One-Legged Reverse Table Top in Pose Dedicated to Sage Vasistha on the Forearm, One-Legged Half Reverse Plank Top in Pose Dedicated to Sage Vasistha on the Forearm
Modification: both knees bent, foot to the knee
Pose Type: standing (on the forearm and the foot)
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One Hand Half Eastern Intense Stretch Pose

Eka Hasta Ardha Purvottanasana

(EY-kuh HUH-stuh UHR-duh poor-vo-tahn-AHS-uh-nuh)

Also Known As: One Hand Reverse Table Top or One Hand Half Reverse Plank

Modification: knees bent, fingertips pointing away from the heels
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं यं ॐ



EASTERN INTENSE STRETCH: LEGS STRAIGHT

Eastern Intense Stretch Pose

Purvottanasana

(poor-vo-tahn-AHS-uh-nuh)
Also Known As: Reverse Plank and Upward Plank Pose
Modification: legs straight, fingertips pointing to the heels
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं रं यं हं ॐ



Foot to the Side

Half Eastern Intense Stretch Pose

Parshva Eka Pada Ardha Purvottanasana

(PAHRSH-vuh EY-kuh PUH-duh UHR-duh poor-vo-tahn-AHS-uh-nuh)

Also Known As: Foot to the Side Reverse Table Top, Foot to the Side Half Reverse Plank and Foot to the Side Half Upward Plank Pose

Pose Type: standing, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

How to Perform the Pose:

1. Begin by sitting on the floor with both your legs straight out in front of you. Keep your hands on the floor on the sides of your hips with fingertips pointing toward your feet. Engage your *mula bandha*, *uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale, bend your knees, and slide your feet toward your sitting bones. Keep your feet and knees hip-width apart.
3. On the next exhale, press into your hands and feet and lift your sitting bones off the floor. Your shoulders should be on top of your wrists, your knees on top of your ankles, and your torso and thighs parallel to the floor.
4. Exhale, straighten your right leg, and bring it out to the side, flexing the toes of your right foot out to the side. Hold the pose for at least 30, and up to 90, seconds in order to receive full benefits.
5. Inhale and bring your right leg back to the center in line with your left leg. Repeat on the other side. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch.
6. Inhale and lower your hips to the floor, coming back to the starting position.

Modification: one knee bent, other leg straight out to the side, fingertips pointing to the heels

parshva = side

eka = one

pada = foot or leg

ardha = half

purva = east, the front of the body

ut = intense

tan = to stretch, to extend



Feet Wide Eastern Intense Stretch Pose

Prasarita Pada Purvottanasana

(pruh-SAH-ri-tuh PUH-duh poor-vo-tahn-AHS-uh-nuh)

Also Known As: Feet Wide Reverse Plank and Feet Wide Upward Plank Pose
Modification: legs straight, toes flexed in, fingertips pointing to the heels
1. side view
2. front view
Pose Type: standing, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





EASTERN INTENSE STRETCH: FOREARMS ON THE FLOOR

Easy Fish Pose

Sukha Matsyasana

(SUK-uh muhts-YAHS-uh-nuh)

Also Known As: Eastern Intense Stretch Pose Prep. (Purvottanasana Prep.), Reverse Plank Prep.
Modification: head off the floor, forearms on the floor, legs straight
Pose Type: seated, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Eastern Intense Stretch Pose

Purvottanasana

(poor-vo-tahn-AHS-uh-nuh)

Also Known As: Reverse Plank on the Forearms and Upward Plank Pose on the Forearms
Modification: legs straight, forearms on the floor
Pose Type: standing (on the forearms), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Easy Fish Pose

Sukha Matsyasana

(SUK-uh muhts-YAHS-uh-nuh)

Also Known As: Eastern Intense Stretch Pose Prep. (Purvottanasana Prep.), Reverse Plank Prep.
Modification: head off the floor, forearms to the floor; one leg straight, other knee bent, foot flat on the floor
1. straight leg on the floor

2. straight leg off the floor, toes flexed in

Pose Type: seated, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व र य ह ॐ





EASTERN INTENSE STRETCH: FOREARMS TO FLOOR—ONE LEG OFF FLOOR

Half Fire Log Pose in Easy Fish Pose

Ardha Agnistambhasana in Sukha Matsyasana

(UHR-duh uhg-ni-stuhm-BAHS-uh-nuh in SUK-uh muhts-YAHS-uh-nuh)

Also Known As: Eastern Intense Stretch Pose Prep. (Purvottanasana Prep.), Reverse Plank Prep.

Modification: forearms to the floor, head off the floor

Pose Type: seated, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व य ह ॐ



Easy Fish Pose

Sukha Matsyasana

(SUK-uh muhts-YAHS-uh-nuh)

Also Known As: Eastern Intense Stretch Pose Prep. (Purvottanasana Prep.), Reverse Plank Prep.
Modification: forearms to the floor, head off the floor, sole of the foot to the opposite knee
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Revolved Hand to Foot Pose in Half Eastern Intense Stretch Pose on the Forearm

Parivritta Hasta Padasana in Ardha Purvottanasana

(puh-ri-VRIT-tuh HUH-stuh puh-DAHS-uh-nuh in UHR-duh poor-vo-tahn-AHS-uh-nuh)

Also Known As: Revolved Hand to Foot Pose in Reverse Table Top, Revolved Hand to Foot Pose in Half Reverse Plank
Modification: forearm on the floor; grabbing onto the outside edge of the foot, leg straight
Pose Type: standing (on the forearm and the foot), twist
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



EASTERN INTENSE STRETCH: FOREARMS TO FLOOR—GRABBING ONTO TRICEPS—KNEES BENT

Hands Bound Easy Fish Pose

Baddha Hasta Sukha Matsyasana

(BUH-duh HUH-stuh SUK-uh muhts-YAHS-uh-nuh)

Modification: knees bent, feet to the floor
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं रं यं हं ॐ



Hands Bound Half Eastern Intense Stretch Pose

Baddha Hasta Ardha Purvottanasana

(BUH-duh HUH-stuh UHR-duh poor-vo-tahn-AHS-uh-nuh)

Also Known As: Hands Bound Reverse Table Top, Hands Bound Half Reverse Plank
Pose Type: standing (on the forearms), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं रं यं हं ॐ



Reverse Prayer One-Legged Easy Fish Pose

Viparita Namaskar Eka Pada Sukha Matsyasana

(vi-puh-REE-tuh nuh-muhs-KAHR EY-kuh PUH-duh SUK-uh muhts-YAHS-uh-nuh)

Also Known As: Back of the Body Prayer One-Legged Easy Fish Pose (Paschima Namaskara Eka Pada Sukha Matsyasana)
Modification: both knees bent, heel to the knee
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ



Hands Bound One-Legged Half Eastern Intense Stretch Pose

Baddha Hasta Eka Pada Ardha Purvottanasana

(BUH-duh HUH-stuh EY-kuh PUH-duh UHR-duh poor-vo-tahn-AHS-uh-nuh)

Also Known As: Hands Bound One-Legged Reverse Table Top, Hands Bound One-Legged Half Reverse Plank
Modification: heel to the knee; grabbing onto the triceps
Pose Type: standing (on the forearms), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ



EASTERN INTENSE STRETCH: FOREARMS TO FLOOR—GRABBING ONTO THE TRICEPS

Hands Bound Easy Fish Pose

Baddha Hasta Sukha Matsyasana

(BUH-duh HUH-stuh SUK-uh muhts-YAHS-uh-nuh)

Modification: one leg straight to the floor; other knee bent, foot to the floor
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Hands Bound Easy Intense Leg Stretch

Baddha Hasta Sukha Uttana Padasana

(BUH-duh HUH-stuh SUK-uh ut-TAHN-uh puh-DAHS-uh-nuh)

Modification: knees bent at 90 degrees, feet off the floor
Pose Type: seated, backbend, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



EASTERN INTENSE STRETCH: ELBOWS ON THE FLOOR—HALF LOTUS

Half Lotus Easy Fish Pose

Ardha Padma Sukha Matsyasana

(UHR-duh PUHD-muh SUK-uh muhts-YAHS-uh-nuh)

Also Known As: Eastern Intense Stretch Pose Prep. (Purvottanasana Prep.), Reverse Plank Prep.
Modification: elbows to the floor, palms to the lower back; one leg in half lotus, other knee bent; heel up
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Lotus Half Eastern Intense Stretch Pose

Ardha Padma Ardha Purvottanasana

(UHR-duh PUHD-muh UHR-duh poor-vo-tahn-AHS-uh-nuh)

Also Known As: Half Lotus Reverse Table Top, Half Lotus Half Reverse Plank
Modification: elbows to the floor, palms to the lower back; one leg in half lotus, other knee bent; heel up
1. right side view

2. left side view

Pose Type: standing (on the elbows, knee and foot), backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व र य ह ॐ





BRIDGE: HEELS DOWN, SPINE ON THE FLOOR

Bridge Whole Body Pose Prep.

Setu Bandha Sarvangasana Prep.

(SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: spine flat on the floor, palms down by the hips, heels down

Pose Type: supine

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल



Reclined Hands Bound Twisted Stomach Pose in Bridge Whole Body Pose Prep.

Supta Baddha Hasta Jatara Parivartanasana in Setu Bandha Sarvangasana Prep.

(SUP-tuh BUH-duh HUH-stuh JAH-tuh-ruh puh-ri-vuhrt-uhn-AHS-uh-nuh in SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: ear resting on a yoga block

Pose Type: supine, twist

Drishti Point: Parshva Drishti (to the right), Parshva Drishti (to the left)



Reclined Hands Bound One Leg Extended Pose in Bridge Whole Body Pose Prep.

Supta Baddha Hasta Utthita Eka Padasana in Setu Bandha Sarvangasana Prep.

(SUP-tuh BUH-duh HUH-stuh UT-ti-tuh EY-kuh puh-DAHS-uh-nuh in SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: arms straight in front, palms facing up

Pose Type: supine

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



Reclined Half Bound Lotus Pose in Bridge Whole Body Pose Prep.

Supta Ardha Baddha Padmasana in Setu Bandha Sarvangasana Prep.

(SUP-tuh UHR-duh BUH-duh puhd-MAHS-uh-nuh in SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: grabbing onto the ankle
Pose Type: supine, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BRIDGE: HEELS DOWN, ARMS BEHIND THE BACK

Bridge Whole Body Pose

Setu Bandha Sarvangasana

(SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: palms to the floor, arms straight; feet in front of the knees
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Uneven Bridge Whole Body Pose

Vishama Setu Bandha Sarvangasana

(VISH-uh-muh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Desk Pose Modification (Dwipadapitam)
Modification: palms down by the heel of the bent leg, other leg straight
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Bridge Whole Body Pose

Setu Bandha Sarvangasana

(SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Shoulder Pose (Kandharasana)
Modification: palms down by the heels
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Bridge Whole Body Pose

Setu Bandha Sarvangasana

(SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: palms to the lower back
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं रं यं हं ॐ



BRIDGE: HEELS DOWN, ARMS OVERHEAD & BEHIND THE BACK

Bridge Whole Body Pose

Setu Bandha Sarvangasana

(SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Desk Pose Modification (Dwipadapitam)
Modification: arms straight to the floor over the head, palms facing up
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं रं यं हं ॐ



Bridge Whole Body Pose

Setu Bandha Sarvangasana

(SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Upward Bow Pose Prep. (Urdhva Dhanurasana Prep.)
Modification: palms under the shoulders, fingertips pointing to the heels
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं रं यं हं ॐ



Upward Hands Bound Bridge Whole Body Pose

Urdhva Baddha Hasta Setu Bandha Sarvangasana

(OORD-vuh BUH-duh HUH-stuh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Desk Pose Modification (Dwipadapitam)
Pose Type: supine, backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
लं रं यं हं



Hands Bound Bridge Whole Body Pose

Baddha Hasta Setu Bandha Sarvangasana

(BUH-duh HUH-stuh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Pose Type: supine, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BRIDGE: HEELS DOWN, GRABBING ONTO THE ANKLES

Hand to Ankle Bridge Whole Body Pose

Hasta Kulpa Setu Bandha Sarvangasana

(HUH-stuh KUL-puh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Desk Pose Modification (Dwipadapitam)

Pose Type: supine, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Hand to Ankle Bridge Whole Body Pose

Hasta Kulpa Setu Bandha Sarvangasana

(HUH-stuh KUL-puh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Desk Pose Modification (Dwipadapitam)
Modification: arms crossed
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BRIDGE: HEELS DOWN—ONE FOOT OFF THE FLOOR

One Hand to Ankle Bridge Whole Body Pose

Eka Hasta Kulpa Setu Bandha Sarvangasana

(EY-kuh HUH-stuh KUL-puh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: yoga block under the sitting bones; grabbing onto the ankle on the same side, top of the foot to the floor
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One Hand to Ankle Bridge Whole Body Pose

Eka Hasta Kulpa Setu Bandha Sarvangasana

(EY-kuh HUH-stuh KUL-puh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: Arm 1: grabbing onto the ankle of the opposite leg Arm 2: grabbing onto the opposite arm

Pose Type: supine, backbend, binding

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Fire Log Pose in One-Legged Hands Bound Bridge Whole Body Pose

Ardha Agnistambhasana in Eka Pada Baddha Hasta Setu Bandha Sarvangasana

(UHR-duh uhg-ni-stuhm-BAHS-uh-nuh in EY-kuh PUH-duh BUH-duh HUH-stuh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: ankle on top of the knee heel down, toes of the top foot pointed

Pose Type: supine, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Bound Lotus One Hand to Ankle Bridge Whole Body Pose

Ardha Baddha Padma Eka Hasta Kulpa Setu Bandha Sarvangasana

(UHR-duh BUH-duh PUHD-muh EY-kuh HUH-stuh KUL-puh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Desk Pose Modification (Dwipadapitam)
Modification: heel down
Pose Type: supine, backbend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BRIDGE: HEELS DOWN—ONE LEG TO THE SKY

One-Legged Bridge Whole Body Pose

Eka Pada Setu Bandha Sarvangasana

(EY-kuh PUH-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: palms down, arms straight on the floor; both knees bent
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged Bridge Whole Body Pose

Eka Pada Setu Bandha Sarvangasana

(EY-kuh PUH-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: palms down, arms straight on the floor; one leg up and straight, knees toward each other
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged Bridge Whole Body Pose

Eka Pada Setu Bandha Sarvangasana

(EY-kuh PUH-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Desk Pose Modification (Dwipadapitam)
Modification: palms down by the heel
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged Bridge Whole Body Pose

Eka Pada Setu Bandha Sarvangasana

(EY-kuh PUH-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Also Known As: Peacock Stretch Pose (Uttana Mayurasana)
Modification: palms to the lower back
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



Both Hands to Ankle One-Legged Bridge Whole Body Pose

Dwi Hasta Kulpa Eka Pada Setu Bandha Sarvangasana

(DWI-huh-stuh KUL-puh EY-kuh PUH-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: grabbing onto the ankle with both hands
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ

One-Legged Upward Hands Bound Tip Toe

Bridge Whole Body Pose

Eka Pada Urdhva Baddha Hasta Prapada Setu Bandha Sarvangasana

(EY-kuh PUH-duh OORD-vuh BUH-duh HUH-stuh PRUH-puh-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Pose Type: supine, backbend

Drishti Point: Angusthamadhye or Angustha Ma Dyai(thumbs)

How to Perform the Pose:

1. Begin by lying with your back flat on the floor. Keep your arms by the sides of your torso, hands by the sides of the hips, palms facing down. Engage your *mula bandha, uddhiyana bandha*, and *ujjayi* breathing.
2. Exhale, bend your knees, and slide your feet toward your sitting bones. Keep your feet flat on the floor, parallel to each other and in line with your sitting bones.
3. On the next exhale, push into your arms and feet and lift your hips off the floor until your thighs are parallel to the floor.
4. Inhale, interlock your fingers behind your back, and press your palms together. Exhale as you push through your chest and straighten the arms.
5. Exhale, bring your ankles and feet together. On the next exhale, lift your right leg, pointing your right toes up to the sky (Pose #2).
6. Exhale, bring your left heel up. Inhale, release your arms and bring them out in front of your chest. Exhale as you interlock your fingers, rotate your palms up to the sky and straighten the arms (Pose #1).
7. Hold the pose for at least 30, and up to 90, seconds in order to receive the full benefits of the stretch. Inhale, lower your right leg, and repeat on the opposite side.
8. On the next inhale, lower your spine to the floor and stretch the legs out in front of you, coming back to the starting position.

Modification: arms extended up to the sky, fingers interlocked, palms facing up, heel up

eka = one

pada = foot or leg

urdhva = upward

baddha = bound

hasta = hand

prapada = tip of the feet

setu = bridge, dam or dike

bandha = lock

sarvanga = the whole body

1.



2.



Tip Toe Bridge Whole Body Pose Prep.

Prapada Setu Bandha Sarvangasana Prep.

(PRUH-puh-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: spine flat on the floor, palms down by the hips, heels up

Pose Type: supine

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Tip Toe Bridge Whole Body Pose

Prapada Setu Bandha Sarvangasana

(PRUH-puh-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: palms down

Pose Type: supine, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Tip Toe Bridge Whole Body Pose

Prapada Setu Bandha Sarvangasana

(PRUH-puh-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: palms to the lower back
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Hands Bound Tip Toe Bridge Whole Body Pose

Baddha Hasta Prapada Setu Bandha Sarvangasana

(BUH-duh HUH-stuh PRUH-puh-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Upward Hands Bound Tip Toe Bridge Whole Body Pose

Urdhva Baddha Hasta Prapada Setu Bandha Sarvangasana

(OORD-vuh BUH-duh HUH-stuh PRUH-puh-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Pose Type: supine, backbend
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)



BRIDGE: HEELS UP—ONE LEG CROSSED OVER

Half Fire Log Pose in One-Legged Hands Bound Tip Toe Bridge Whole Body Pose

Ardha Agnistambhasana in Eka Pada Baddha Hasta Prapada Setu Bandha Sarvangasana

(UHR-duh uhg-ni-stuhm-BAHS-uh-nuh in EY-kuh PUH-duh BUH-duh HUH-stuh PRUH-puh-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: heel up; ankle on top of the knee, toes flexed in
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Uneven Leg Position of Cow Face Pose in One-Legged Tip Toe Bridge Whole Body Pose

Vishama Pada Gomukhasana in Eka Pada Prapada Setu Bandha Sarvangasana

(VISH-uh-muh PUH-duh go-muk-AHS-uh-nuh in EY-kuh PUH-duh PRUH-puh-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: Arm 1: grabbing onto the foot of the opposite leg Arm 2: grabbing onto the opposite arm

Pose Type: supine, backbend, binding

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Bound Lotus One Hand to Ankle Tip Toe Bridge Whole Body Pose

Ardha Baddha Padma Eka Hasta Kulpa Prapada Setu Bandha Sarvangasana

(UHR-duh BUH-duh PUHD-muh EY-kuh HUH-stuh KUL-puh PRUH-puh-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: heel up

Pose Type: supine, backbend, binding

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BRIDGE: HEELS UP—ONE LEG EXTENDED TO THE SKY

One-Legged Tip Toe Bridge Whole Body Pose

Eka Pada Prapada Setu Bandha Sarvangasana

(EY-kuh PUH-duh PRUH-puh-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: palms down
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged Tip Toe Bridge Whole Body Pose

Eka Pada Prapada Setu Bandha Sarvangasana

(EY-kuh PUH-duh PRUH-puh-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: palms to the lower back
1. fingertips pointing to the heel
2. fingertips pointing to the head
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





One-Legged Hands Bound Tip Toe Bridge Whole Body Pose

Eka Pada Baddha Hasta Prapada Setu Bandha Sarvangasana

(EY-kuh PUH-duh BUH-duh HUH-stuh PRUH-puh-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: leg straight and extended to the sky, heel up
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BRIDGE: HEELS UP—ONE LEG EXTENDED TO THE SKY—“BALLET TOES”

Intense Ankle Stretch One-Legged Bridge Whole Body Pose

Uttana Kulpa Eka Pada Setu Bandha Sarvangasana

(ut-TAHN-uh KUL-puh EY-kuh PUH-duh PRUH-puh-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: palms to the lower back; both knees bent
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Intense Ankle Stretch One-Legged Bridge Whole Body Pose

Uttana Kulpa Eka Pada Setu Bandha Sarvangasana

(ut-TAHN-uh KUL-puh EY-kuh PUH-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: palms to the lower back; top leg straight
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One Hand One-Legged Tip Toe Bridge Whole Body Pose

Eka Hasta Eka Pada Prapada Setu Bandha Sarvangasana

(EY-kuh HUH-stuh EY-kuh PUH-duh PRUH-puh-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: lifted leg bent; palm to the lower back, heel up
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BRIDGE: LEGS STRAIGHT—BACK OF THE HEAD TO THE FLOOR

Extended Hand to Big Toe Pose Intense Ankle Stretch One-Legged Bridge Whole Body Pose

Utthita Hasta Padangushtasana in Uttana Kulpa Eka Pada Setu Bandha Sarvangasana

(UT-ti-tuh HUH-stuh puhd-ahng-goosh-TAHS-uh-nuh in ut-TAHN-uh KUL-puh EY-kuh PUH-duh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Pose Type: supine, backbend, forward bend
Drishti Point: Padayoragrai or Padayoragre (toes/feet)
ल व र य



BRIDGE: LEGS STRAIGHT—BACK OF THE HEAD TO THE FLOOR

Complete Bridge Whole Body Pose

Paripurna Setu Bandha Sarvangasana

(puh-ri-POOR-nuh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: palms to the lower back
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ



One-Legged Complete Bridge Whole Body Pose

Eka Pada Paripurna Setu Bandha Sarvangasana

(EY-kuh PUH-duh puh-ri-POOR-nuh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)
Modification: palms to the lower back
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र य ह ॐ



HEAD AND SITTING BONES ON THE FLOOR: KNEES BENT

Half Fish Pose

Ardha Matsyasana

(UHR-duh muhts-YAHS-uh-nuh)
Modification: knees bent; feet flat on the floor, heels toward the sitting bones; palms down to the

floor by the heels, elbows to the floor
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Fish Pose

Ardha Matsyasana

(UHR-duh muhts-YAHS-uh-nuh)
Modification: knees bent
1. arms over the head, feet flat on the floor
2. hands by the navel, palms pressed together, fingertips pointing up, both feet in the tip toe position
3. hands by the navel, palms pressed together, fingertips pointing up; one foot in the tip toe position, other leg raised
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

1.







HEAD AND SITTING BONES ON THE FLOOR: LEGS STRAIGHT

Fish Pose

Matsyasana

(muhts-YAHS-uh-nuh)

Modification: legs straight on the floor, elbows to the floor, palms down to the floor by the hips
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ ॐ



Reverse Prayer Fish Pose

Viparita Namaskar Matsyasana

(vi-puh-REE-tuh nuh-muhs-KAHR muhts-YAHS-uh-nuh)

Also Known As: Back of the Body Prayer Fish Pose (Paschima Namaskara Matsyasana)
Modification: legs straight to the floor
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Intense Leg Stretch

Uttana Padasana

(ut-TAHN-uh puh-DAHS-uh-nuh)

Modification: legs straight on the floor, arms straight in front of the chest, palms pressed together
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



HEAD AND SITTING BONES ON THE FLOOR: ONE LEG STRAIGHT, ONE KNEE BENT

Fish Pose

Matsyasana

(muhts-YAHS-uh-nuh)

Modification: 1. one leg straight, other knee bent
2. one leg straight, other knee bent, bent leg crossed over
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)


1.


2.

Half Bound Lotus Fish Pose

Ardha Baddha Padma Matsyasana

(UHR-duh BUH-duh PUHD-muh muhts-YAHS-uh-nuh)

Modification: sitting bones on the floor, palm to the floor by the hip
Pose Type: seated, backbend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Bound Lotus Fish Pose

Ardha Baddha Padma Matsyasana

(UHR-duh BUH-duh PUHD-muh muhts-YAHS-uh-nuh)

Modification: one arm straight up to the sky, other arm grabbing onto the inside of the thigh behind the back; leg straight
Pose Type: seated, backbend, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



HEAD AND SITTING BONES ON THE FLOOR: HANDS AND FEET ON FLOOR—BINDING & GARUDA ARMS AND LEGS

Half Bound Lotus Half Fish Pose

Ardha Baddha Padma Ardha Matsyasana

(UHR-duh BUH-duh PUHD-muh UHR-duh muhts-YAHS-uh-nuh)

Modification: grabbing onto the foot with arm behind the back, fingertips of the other arm touching the floor overhead, elbow bent; knee of the free leg bent
1. heel down
2. heel up

Pose Type: seated, backbend, binding

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Hastagrai or Hastagre (hands)

ल व र य ह ॐ ॐ





Intense Leg Stretch Pose Dedicated to Garuda

Uttana Pada Garudasana

(ut-TAHN-uh PUH-duh guh-ru-DAHS-uh-nuh)

Modification: fingertips and bottom foot to the floor

Pose Type: seated, backbend

Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)

ल व र य ह ॐ



RECLINED BOUND ANGLE POSE & FISH POSE

Reclined Bound Angle Pose

Supta Baddha Konasana

(SUP-tuh BUH-duh ko-NAHS-uh-nuh)

Modification: hands to the inner thighs, palms up
Pose Type: supine
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reclined Bound Angle Pose

Supta Baddha Konasana

(SUP-tuh BUH-duh ko-NAHS-uh-nuh)

Also Known As: Bound Legs Fish Pose (Baddha Pada Matsyasana)
Modification: crown of the head to the floor, grabbing onto the shins, arms on top of the legs
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Fish Pose

Matsyasana

(muhts-YAHS-uh-nuh)

Modification: 1. palms up on the inside of the thighs
2. grabbing onto the big toes, elbows to the floor
3. grabbing onto the forearms, arms up over the head

Pose Type: seated, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)







Reverse Prayer Intense Leg Stretch

Viparita Namaskar Uttana Padasana

(vi-puh-REE-tuh nuh-muhs-KAHR ut-TAHN-uh puh-DAHS-uh-nuh)

Also Known As: Back of the Body Prayer Intense Leg Stretch (Paschima Namaskara Uttana Padasana)
Modification: legs straight and off the floor, ankles crossed
Pose Type: seated, backbend, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Intense Leg Stretch

Uttana Padasana

(ut-TAHN-uh puh-DAHS-uh-nuh)

Modification: legs straight and off the floor; arms straight in front of the chest, palms pressed together
Pose Type: seated, backbend, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Intense Leg Stretch Pose Dedicated to Garuda

Uttana Pada Garudasana

(ut-TAHN-uh PUH-duh guh-ru-DAHS-uh-nuh)

Modification: legs and arms lifted off the floor
Pose Type: seated, backbend, core
Drishti Point: Angushtamadhye or Angushta Ma Dyai (thumbs)
ल व र य ह ॐ



BRIDGE POSE

Complete Bridge Whole Body Pose

Paripurna Setu Bandha Sarvangasana

(puh-ri-POOR-nuh SEY-tu BUHN-duh suhr-vuhng-GAHS-uh-nuh)

Modification: palms to the floor under the shoulders, fingertips pointing to the heels; elbows tucked in, shoulder width apart
Pose Type: supine, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल र य ह ॐ



Vajra Cutter Sutra Bridge Pose

Vajracchedika Prajnaparamita Sutra Setu Bandhasana

(vahj-ruh-CHEY-di-kuh pruhj-NAH-puh-ruh-mi-TAH SU-truh SEY-tu buhn-DAHS-uh-nuh)

Modification: forehead to the floor, elbows splaying to the side, arms in “diamond” shape
Pose Type: standing (on the head and feet), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Bridge Pose

Setu Bandhasana

(SEY-tu buhn-DAHS-uh-nuh)

Modification: fingertips to the floor and pointing toward the heels
Pose Type: standing (on the head and feet), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Bridge Pose

Setu Bandhasana

(SEY-tu buhn-DAHS-uh-nuh)

Modification: arms crossed in front of the chest, hands to the shoulders

Pose Type: standing (on the head and feet), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं रं यं हं ॐ



One-Legged Bridge Pose

Eka Pada Setu Bandhasana

(EY-kuh PUH-duh SEY-tu buhn-DAHS-uh-nuh)
Modification: fingertips pointing toward the heels, palms flat on the floor
Pose Type: standing (on the head and feet), backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
लं वं रं यं हं ॐ



BOUND ANGLE POSE & LOTUS: BACKBEND

Reclined Bound Angle Pose

Supta Baddha Konasana

(SUP-tuh BUH-duh ko-NAHS-uh-nuh)
Also Known As: Bound Legs Fish Pose (Baddha Pada Matsyasana)
Modification: crown of the head to the floor, grabbing onto the shins under the legs

1. elbows to the floor
2. arms straight, elbows off the floor

Pose Type: backbend, standing (on the knees)

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Intense Lotus Peacock

Uttana Padma Mayurasana

(ut-TAHN-uh PUHD-muh muh-yoor-AHS-uh-nuh)

Also Known As: Intense Front Body Stretching and Rejuvenating Lotus Pose (Purvottana Padma Sarvangasana), All Body Parts Lotus Pose (Sarvangasana Padmasana)

Modification: knees on the floor

Pose Type: supine, backbend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BOTH KNEES BENT: ONE LEG CROSSED OVER

Eye of the Needle Pose

Sucirandrasana

(soo-chi-ruhn-DRAHS-uh-nuh)

Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reclined Leg Position of Cow Face Pose

Supta Pada Gomukhasana

(SUP-tuh PUH-duh go-muk-AHS-uh-nuh)

Modification: knees to the chest, grabbing onto both feet
1. front view
2. side view
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)


1.


2.

Reclined Twisting Fire Log Pose

Supta Parshva Agnistambhasana

(SUP-tuh PAHRSH-vuh uhg-ni-stuhm-BAHS-uh-nuh)

Pose Type: supine, forward bend, twist

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reclined Leg Position of Half Cow Face Pose

Supta Pada Ardha Gomukhasana

(SUP-tuh PUH-duh UHR-duh go-muk-AHS-uh-nuh)

Modification: knees apart, top foot on the floor
1. one hand to the forehead, other hand on the top knee
2. grabbing onto the shoulders, arms crossed in front of the neck
3. one hand to the top ankle, other hand to the bottom foot
Pose Type: supine, forward bend, twist
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)


1.


2.


3.

BOTH KNEES BENT: ONE LEG CROSSED OVER—KNEES TO THE FLOOR

Reclined Leg Position of Cow Face Pose

Supta Pada Gomukhasana

(SUP-tuh PUH-duh go-muk-AHS-uh-nuh)

Modification: knees to the floor

Pose Type: supine

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Universal All-Encompassing Diamond Pose

Vishvavajrasana

(vish-vuh-vuhj-RAHS-uh-nuh)

Also Known As: Double Diamond Pose

Modification: foot on top of the knee; hand to the sole of the back foot, other hand resting on the thigh of the front leg, looking straight ahead

Pose Type: supine, twist

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Revolved Universal All-Encompassing Diamond Pose

Parivritta Vishvavajrasana *(puh-ri-VRIT-tuh vish-vuh-vuhj-RAHS-uh-nuh)*

Also Known As: Revolved Double Diamond Pose

Modification: hand grabbing onto the foot; other hand grabbing onto the opposite knee, looking up to the sky
Pose Type: supine, forward bend, twist
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Revolved Universal All-Encompassing Diamond Pose

Parivritta Vishvavajrasana *(puh-ri-VRIT-tuh vish-vuh-vuhj-RAHS-uh-nuh)*
Also Known As: Revolved Double Diamond Pose
Modification: hand grabbing onto the ankle, arm under the thigh; other hand grabbing onto the ankle of the bottom leg, looking straight ahead
Pose Type: supine, forward bend, twist
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



BOTH KNEES BENT: KNEES TOGETHER

Reclined Child’s Pose

Supta Balasana

(SUP-tuh bah-LAHS-uh-nuh)

Also Known As: Pelvic Pose (Apanasana)
Modification: binding arms, grabbing onto the triceps
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Wind-Relieving Pose

Vayu Muktyasana

(VAH-yuh muk-TYAHS-uh-nuh)

Also Known As: Wind Releaser Pose (Pavana Muktasana)
Modification: fingers interlocked on top of the shins
Pose Type: supine, forward bend, core
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Twisted Stomach Pose

Jatara Parivartanasana

(JAH-tuh-ruh puh-ri-vuhrt-uhn-AHS-uh-nuh)

Also Known As: Reclining Waist Pose Prep.(Supta Madhyasana), Sideways Wind Releaser Pose (Pavana Muktasana)
Modification: knees bent, arms straight out to the sides
Pose Type: supine, forward bend, twist
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल य ॐ



ONE LEG STRAIGHT, ONE KNEE BENT

One-Legged Wind Relieving Pose

Eka Pada Pavana Muktasana

(EY-kuh PUH-duh puh-vuh-nuh muk-TAHS-uh-nuh)

Also Known As: Reclined Big Toe Pose A Prep. (Supta Padangushtasana A Prep.)
Modification: head on the floor, fingers interlocked on top of the shin
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व र ॐ



Reclining Tree Pose

Supta Vrikshasana

(SUP-tuh vrik-SHAHS-uh-nuh)

Also Known As: Reclined Big Toe Pose B Prep. (Supta Padangushtasana B Prep.)
Modification: hand to the bent knee, other hand along side of the torso, toes flexed in
Pose Type: supine
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

● ● ●



BOTH LEGS STRAIGHT: ONE LEG TO THE SIDE

Revolved Reclining Hand to Foot Pose

Parivritta Supta Hasta Padasana

(puh-ri-VRIT-tuh SUP-tuh HUH-stuh puh-DAHS-uh-nuh)

Modification: legs straight, grabbing onto the inside arch of the foot
Pose Type: supine, forward bend, twist
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

● ● ● ●



Reclining Big Toe Pose 2

Supta Padangushtasana 2

(SUP-tuh puhd-ahng-goosh-TAHS-uh-nuh)

Pose Type: supine, forward bend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



ONE LEG STRAIGHT, ONE KNEE BENT: TWIST

Reclined Lord of the Fishes Pose

Supta Matsyendrasana

(SUP-tuh muhts-yeyn-DRAHS-uh-nuh)

Also Known As: Revolving Reclined Big Toe Pose Prep. (Parivritta Supta Padangushtasana Prep.), Revolved Reclining Tree Pose (Parivritta Supta Vrikshasana)

Modification: knee bent at 90 degrees

Pose Type: supine, forward bend, twist

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



GARUDA LEGS: TWISTS

Sideways Reclining Leg Position of the Pose Dedicated to Garuda

Parshva Supta Pada Garudasana

(PAHRSH-vuh SUP-tuh PUH-duh guh-ru-DAHS-uh-nuh)

Modification: hand resting on the top knee, other arm to the floor along side the torso, looking to the side; arms straight out to the side, looking straight ahead
Pose Type: supine, twist
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Hastagrai or Hastagre (hands)

1.



2.



BOTH LEGS STRAIGHT AND TOGETHER: TWIST

Twisted Stomach Pose

Jathara Parivartanasana

(JAH-tuh-ruh puh-ri-vuhrt-uhn-AHS-uh-nuh)

Also Known As: Reclining Waist Pose (Supta Madhyasana)
Modification: legs and arms straight
Pose Type: supine, forward bend, twist
Drishti Point: Hastagrai or Hastagre (hands)



ONE LEG STRAIGHT, ONE KNEE BENT: LEG CRADLE & HALF HAPPY BABY POSE

Reclined Baby Cradle Pose

Supta Hindolasana

(SUP-tuh hin-do-LAHS-uh-nuh)

Modification: back leg straight
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reclined One Hand to Foot Pose

Supta Eka Hasta Padasana

(SUP-tuh EY-kuh HUH-stuh puh-DAHS-uh-nuh)

Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



HAPPY BABY POSE & ONE FOOT BEHIND THE HEAD

Happy Baby Pose

Sukha Balasana

(SUK-uh bahl-AHS-uh-nuh)

Also Known As: Happy Baby Pose (Ananda Balasana)
Modification: grabbing onto the big toes of the feet
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reclined Star Pose

Supta Tarasana

(SUP-tuh tah-RAHS-uh-nuh)

Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Padayoragrai or Padayoragre (toes/feet)



Happy Baby Pose

Sukha Balasana

(SUK-uh bahl-AHS-uh-nuh)

Also Known As: Happy Baby Pose (Ananda Balasana)
Modification: arms crossed, grabbing onto the outside edges of the feet
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reclined One Hand to Foot Pose

Supta Eka Hasta Padasana

(SUP-tuh EY-kuh HUH-stuh puh-DAHS-uh-nuh)

Modification: grabbing onto the back foot, heel to the sitting bone, toes pointed to the floor
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reclined One Hand to Foot One Leg Behind the Head Pose in Infinity Pose

Supta Eka Hasta Pada Eka Pada Shirshasana in Anantasana

(SUP-tuh EY-kuh-HUH-stuh PUH-duh EY-kuh PUH-duh sheer-SHAS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Modification: bottom knee to the floor, toes pointing up to the sky
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One Leg Behind the Head in Infinity Pose

Eka Pada Shirshasana in Anantasana

(EY-kuh PUH-duh sheer-SHAHS-uh-nuh in uhn-uhnt-AHS-uh-nuh)

Modification: bottom heel toward the hip
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



ONE AND BOTH FEET BEHIND THE HEAD

Pose Dedicated to Bhairava in Half Upward Facing Western Intense Stretch 2

Bhairavasana in Ardha Urdhva Mukha Paschimottanasana 2

(b-eye-ruh-VAHS-uh-nuh in UHR-duh OORD-vuh MUK-uh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Pose Dedicated to Bhairava in Half Upward Facing Forward Bend 2
Modification: 1. front view
2. back view
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)





Hands Bound Yogic Sleep Pose

Baddha Hasta Yoganidrasana

(BUH-duh HUH-stuh yo-guh-ni-DRAHS-uh-nuh)

Modification: hands bound
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



HORIZONTAL SPLITS

Reclined Angle Pose

Supta Konasana

(SUP-tuh ko-NAHS-uh-nuh)

Modification: back flat on the floor, feet lifted off the floor, grabbing onto the big toes
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reclined Angle Pose

Supta Konasana

(SUP-tuh ko-NAHS-uh-nuh)

Modification: back flat on the floor, toes to the floor, grabbing onto the outside edges of the feet
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reclined Angle Pose

Supta Konasana

(SUP-tuh ko-NAHS-uh-nuh)

Modification: back flat on the floor, feet lifted off the floor, arms straight out to the sides, palms down to the floor
Pose Type: supine
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

Sideways Reclined Angle Pose

Parshva Supta Konasana

(PAHRSH-vuh SUP-tuh ko-NAHS-uh-nuh)

Modification: back flat on the floor, head turning to side Side 1: leg in the air; arm straight on the floor, palm facing up
Side 2: leg on the floor, grabbing onto the big toe
Pose Type: supine, twist
Drishti Point: Hastagrai or Hastagre (hands)



Revolved Half Bound Reclined Angle Pose

Parivritta Ardha Baddha Supta Konasana

(puh-ri-VRIT-uh UHR-duh BUH-duh SUP-tuh ko-NAHS-uh-nuh)

Modification: both legs straight Side 1: leg pointing to the sky; arm wrapping around the back, hand to the inside of the hip on the opposite side
Side 2: leg on the floor, opposite hand grabbing onto the foot
Pose Type: supine, twist, binding
Drishti Point: Hastagrai or Hastagre (hands), Padayoragrai or Padayoragre (toes/feet)



ONE LEG STRAIGHT TO THE SKY, ONE LEG CROSSED OVER

Upward Facing Western Intense Stretch

Urdhva Mukha Paschimottanasana

(OORD-vuh MUK-uh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Upward Facing Forward Bend
Modification: legs crossed, one arm threaded through the legs, other hand to the center of the chest
Pose Type: supine, forward bend, twist
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Padayoragrai or Padayoragre (toes/feet)



Reclined Hands Bound Pose Dedicated to Astavakra

Supta Baddha Hasta Ashtavakrasana

(SUP-tuh BUH-duh HUH-stuh uhsh-tuh-vuh-KRAHS-uh-nuh)

Also Known As: Reclined Hands Bound Eight Angle Pose
Modification: ankles crossed
Pose Type: supine, forward bend, twist, binding
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



ONE KNEE BENT TO THE BACK, OTHER LEG STRAIGHT

One-Legged Reclined Hero Pose

Eka Pada Supta Virasana

(EY-kuh PUH-duh SUP-tuh veer-AHS-uh-nuh)

Modification: straight leg lifted, fingers interlocked on the back of the thigh
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged Reclined Hero Pose

Eka Pada Supta Virasana

(EY-kuh PUH-duh SUP-tuh veer-AHS-uh-nuh)

Modification: leg straight out to the side, grabbing onto the outside edge of the foot
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged Reclined Hero Pose

Eka Pada Supta Virasana

(EY-kuh PUH-duh SUP-tuh veer-AHS-uh-nuh)

Modification: leg straight on the floor, toes flexed in; arms straight out to the sides, palms facing up
Pose Type: supine
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



ONE KNEE BENT TO THE BACK, OTHER LEG BENT

One-Legged Reclined Hero Pose

Eka Pada Supta Virasana

(EY-kuh PUH-duh SUP-tuh veer-AHS-uh-nuh)

Modification: Leg 1: in Hero Pose (Virasana)
Leg 2: knee up to the sky, heel to the sitting bones; arms up over the head, palms facing up
Pose Type: supine
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



One-Legged Reclined Hero Pose

Eka Pada Supta Virasana

(EY-kuh PUH-duh SUP-tuh veer-AHS-uh-nuh)

Modification: Leg 1: in Hero Pose (Virasana)
Leg 2: knee toward the chest, toes flexed in; fingertips interlocked on top of the knee
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Half Bound Angle Pose in One-Legged Reclined Hero Pose

Ardha Baddha Konasana in Eka Pada Supta Virasana

(UHR-duh BUH-duh ko-NAHS-uh-nuh in EY-kuh PUH-duh SUP-tuh veer-AHS-uh-nuh)

Modification: arms up over the head, palms facing upward
Pose Type: supine
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reclined Hero Pose

Supta Virasana

(SUP-tuh veer-AHS-uh-nuh)

Also Known As: Bed Pose B (Paryankasana B)
Modification: arms up over the head, palms facing upward
Pose Type: supine
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)
ल व य ॐ



TOES TURNED OUT TO THE SIDE: ONE KNEE BENT TO THE BACK, OTHER LEG BENT

Reclined One-Legged Thunderbolt Pose

Supta Eka Pada Vajrasana

(SUP-tuh EY-kuh PUH-duh vuhj-RAHS-uh-nuh)

Modification: Leg 1: in Thunderbolt Pose (Vajrasana)
Leg 2: knee up to the sky, heel to the sitting bones; arms up over the head, fingers interlocked, palms facing out
Pose Type: supine
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reclined One-Legged Thunderbolt Pose

Supta Eka Pada Vajrasana

(SUP-tuh EY-kuh PUH-duh vuhj-RAHS-uh-nuh)

Modification: Leg 1: in Thunderbolt Pose (Vajrasana)
Leg 2: knee up to the sky, sole of the foot to the thigh; arms up over the head, fingers interlocked, palms facing out
Pose Type: supine
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reclined One-Legged Thunderbolt Pose

Supta Eka Pada Vajrasana

(SUP-tuh EY-kuh PUH-duh vuhj-RAHS-uh-nuh)

Modification: Leg 1: in Thunderbolt Pose (Vajrasana)
Leg 2: knee bent at 90 degrees, heel off the floor; arms up over the head, fingers interlocked, palms facing out
Pose Type: supine

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reclined Complete Thunderbolt Pose

Supta Paripurna Vajrasana

(SUP-tuh puh-ri-POOR-nuh vuhj-RAHS-uh-nuh)

Modification: arms up over the head, fingers interlocked, palms facing out
Pose Type: supine
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



TOES TURNED OUT TO THE SIDE: ONE KNEE BENT TO THE BACK, OTHER LEG STRAIGHT & FOREARM POSES

Reclined One-Legged Thunderbolt Pose

Supta Eka Pada Vajrasana

(SUP-tuh EY-kuh PUH-duh vuhj-RAHS-uh-nuh)

Modification: leg straight to the floor, toes flexed in; arms up over the head, fingers interlocked, palms facing out

Pose Type: supine
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reclined One-Legged Thunderbolt Pose

Supta Eka Pada Vajrasana

(SUP-tuh EY-kuh PUH-duh vuhj-RAHS-uh-nuh)
Modification: leg straight and lifted off the floor by using a Yoga strap
Pose Type: supine
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reclined One-Legged Thunderbolt Pose

Supta Eka Pada Vajrasana

(SUP-tuh EY-kuh PUH-duh vuhj-RAHS-uh-nuh)
Modification: forearms to the floor in a backbend, one leg straight to the floor, toes flexed in, other leg in Thunderbolt Pose (Vajrasana)
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reclined Complete Thunderbolt Pose

Supta Paripurna Vajrasana

(SUP-tuh puh-ri-POOR-nuh vuhj-RAHS-uh-nuh)

Modification: forearms to the floor in a backbend
Pose Type: seated, backbend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



VERTICAL SPLITS: SCISSOR LEGS—BOTH KNEES BENT & ONE KNEE BENT, ONE LEG STRAIGHT

Reclining Both Hands to the Leg Pose

Supta Dwi Hasta Padasana

(SUP-tuh DWI-huh-stuh puh-DAHS-uh-nuh)

Modification: elbows bent, triceps on the floor, fingers interlocked behind the back of the thigh Leg 1: slight knee bend, foot flat on the floor Leg 2: knee bent at 90 degrees, knee toward the chest
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows) or Padayoragrai or

Padayoragre (toes/feet)



Reclining Half One Leg Extended Pose

Supta Ardha Utthita Eka Padasana

(SUP-tuh UHR-duh UT-ti-tuh EY-kuh puh-DAHS-uh-nuh)

Modification: palms flat to the floor on the sides.
Leg 1: straight up to the sky Leg 2: knee bent, foot flat to the floor, heel to the sitting bones
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Padayoragrai or Padayoragre (toes/feet)



Reclining Both Hands to the Leg Pose

Supta Dwi Hasta Padasana

(SUP-tuh DWi-huh-stuh puh-DAHS-uh-nuh)

Modification: grabbing onto the calf muscle, elbows bent Leg 1: straight and toward the chest Leg 2: knee bent, foot flat to the floor
Pose Type: supine, forward bend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Padayoragrai or Padayoragre (toes/feet)



Reclining Both Hands to the Leg Pose

Supta Dwi Hasta Padasana

(SUP-tuh DWI-huh-stuh puh-DAHS-uh-nuh)

Modification: grabbing onto the calf muscle, elbows bent at 90 degrees, nose toward the shin Leg 1: straight and toward the chest Leg 2: knee bent, foot flat to the floor
Pose Type: supine, forward bend, core
Drishti Point: Padayoragrai or Padayoragre (toes/feet), Nasagrai or Nasagre (nose)



VERTICAL SPLITS: SCISSOR LEGS—BOTH LEGS STRAIGHT

Reclining One Leg Extended Pose

Supta Utthita Eka Padasana

(SUP-tuh UT-ti-tuh EY-kuh puh-DAHS-uh-nuh)

Modification: palms flat to the floor on the sides Leg 1: straight up to the sky Leg 2: straight out on

the floor, toes flexed in
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Padayoragrai or Padayoragre (toes/feet)



Reclining Big Toe Pose 1

Supta Padangushtasana 1

(SUP-tuh puhd-uhng-goosh-TAHS-uh-nuh)
Modification: back flat on the floor
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Padayoragrai or Padayoragre (toes/feet)



Reclining Big Toe Pose 1

Supta Padangushtasana 1

(SUP-tuh puhd-uhng-goosh-TAHS-uh-nuh)
Modification: head and shoulders off the floor, nose to the shin

Pose Type: supine, forward bend

Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Nasagrai or Nasagre (nose)

ल व र ह ॐ



Reclining Both Hands to the Leg Pose

Supta Dwi Hasta Padasana

(SUP-tuh DWI-huh-stuh puh-DAHS-uh-nuh)

Modification: head and shoulders off the floor, nose to the shin, toes pointed

Pose Type: supine, forward bend, core

Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)

ल व र ह ॐ



Reclining One Hand to the Leg Pose

Supta Eka Hasta Padasana

(SUP-tuh EY-kuh HUH-stuh puh-DAHS-uh-nuh)

Modification: hand to opposite leg, head and shoulders off the floor, nose to the shin, toes flexed in

Pose Type: supine, forward bend, core

Drishti Point: Nasagrai or Nasagre (nose), Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Reclining One Leg Extended Pose

Supta Utthita Eka Padasana

(SUP-tuh UT-ti-tuh EY-kuh puh-DAHS-uh-nuh)

Modification: palms flat to the floor on the sides, head and shoulders off the floor, nose to the knee, bottom toes flexed in
Pose Type: supine, forward bend
Drishti Point: Nasagrai or Nasagre (nose)



BOTH LEGS STRAIGHT AND TOGETHER

Reclining Legs Extended Pose

Supta Utthita Padasana

(SUP-tuh UT-ti-tuh puh-DAHS-uh-nuh)

Modification: arms crossed in front of the chest

Pose Type: supine
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Padayoragrai or Padayoragre (toes/feet)



Reclining Legs Extended Pose

Supta Utthita Padasana

(SUP-tuh UT-ti-tuh puh-DAHS-uh-nuh)

Modification: arms straight up to the sky
1. arms and legs perpendicular to the floor
2. arms and legs slightly lowered toward the floor
Pose Type: supine
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Padayoragrai or Padayoragre (toes/feet), Hastagrai or Hastagre (hands)



1.



Half Upward Facing Western Intense Stretch 2

Ardha Urdhva Mukha Paschimottanasana 2

(UHR-duh OORD-vuh MUK-uh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Half Upward Facing Forward Bend, Upward Facing Western Intense Stretch Pose 2 Prep. (Urdhva Mukha Paschimottanasana 2 Prep.)
Modification: grabbing onto the calf muscles
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Padayoragrai or Padayoragre (toes/feet)



Upward Facing Western Intense Stretch 2

Urdhva Mukha Paschimottanasana 2

(OORD-vuh MUK-uh puhsh-chi-mo-tahn-AHS-uh-nuh)

Also Known As: Upward Facing Forward Bend 2
Pose Type: supine, forward bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Padayoragrai or Padayoragre (toes/feet)

SUPINE LOTUS & CORPSE POSE

Reclining Lotus Pose

Supta Padmasana

(SUP-tuh puhd-MAHS-uh-nuh)

Also Known As: Fish Pose (Matsyasana)
Modification: back flat on the floor; arms up over the head, palms facing up
Pose Type: supine
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



Side Corpse Pose

Parshva Shavasana

(PAHRSH-vuh shuh-VAHS-uh-nuh)

Also Known As: Belly Twist (Jataraparivritti)
Modification: 1. head turned to the opposite side of feet
2. looking straight ahead
Pose Type: supine, side bend
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows), Hastagrai or Hastagre

(hands)





Corpse Pose

Shavasana

(shuh-VAHS-uh-nuh)

Also Known As: Dead Pose (Mrtasana)
Pose Type: supine
Drishti Point: Bhrumadhye or Ajna Chakra (third eye, between the eyebrows)



ACKNOWLEDGMENTS

Meet the talented people of Mr. Yoga, Inc. who have contributed their energy, passion, and skills to this project.

Mr. Yoga

Victoria B.

Tatiana U.

Aggie M.

Susan M.

Olga Q. B.

Laura Lisa

Vanessa D. S.

Snow W.

Paul M.

Kat D.

Paula O.

Venessa S.

Additional special thanks to: Adrienne Yau, Silvia Bogers, Antoine Bogers, Evelyn Lacerda, Chris
Morino, Scott Mendel, Black Dog & Leventhal Publishers, Hachette Book Group

Welcome to the Mr. Yoga, Inc. global family. All of the models selected to appear in this book are students of Daniel Lacerda, aka Mr. Yoga.

Frances L.

Cristine C.

Carolyn L.

Tatiana U.

Elena B.

Stephanie M. & Iva M.

Matthew B.

Shriya M. D.

Mariah A.

Erin B.

Valeryia G.

Michael C.

Brent J.

Kristen S.

Christina D. F.

Laura M.

Victoria B.

Eva M.

Jemma B.

Menaka I.

Hagar E.

Kellys E.

Diana M.

Alessandra F.

Neelam P.

Katerina D.

Crio C.

Paula O.

Dasha C.

Elissa R.

Eli M.

Josiah B.

Nicki B.

Rachel M.

Hue N.

Deanna D.

Aggie M.

Corrado R. M.

Taylor K.

Susan M.

Neil F.

Justin L.

Thank you to special guest, Danny Paradise.

GLOSSARY

A

adho mukha = having the face downward

agni = fire

ahimsa = nonviolence; the word has not merely the negative and restrictive meaning of “nonkilling or nonviolence,” but the positive and comprehensive meaning of “love embracing all creation”; one of the *yamas*

ajna = to command

ajna chakra = energy or command *chakra*, energy center/the nerve plexus located between the eyebrows, the third eye, the seat of command, the sixth *chakra*

akarna = near the ear

akuncha = contraction or bend

alamba = a prop or support

anahata = unstruck

anahata chakra = spiritual heart *chakra*, energy center situated near the heart, the nervous plexus situated in the cardiac region, the fourth *chakra*

ananda = joy, happiness, bliss, ecstasy

ananta = infinite, without end; a name of Vishnu and also of Vishnu’s couch, the serpent Sesa

anga = limb, points, step, the body; a limb or a part of the body; a constituent part

angushta (angula) = finger or digit, the thumb

anjali = hands held together as in prayer

anjali-mudra = the gesture of *anjali*

Anjaneya = son of Anjani (Hanuman’s mother’s maiden name is Anjani)

antara = within, interior

apanasana = pelvic floor yoga pose

aparigraha = non-greediness, freedom from greed, desire, hoarding or collecting; one of the *yamas*

Arani = Hindu Goddess of Fire

aranya = wild animal

asana = a physical posture, the third limb or stage of yoga, originally this meant “meditation posture” or “seat”

ashta (asta, astau) = eight

Ashtavakra = one having eight bends (crooked in eight places), in reference to a Hindu Sage who was born with eight physical deformities in his body, and went on to become a spiritual preceptor of King Janaka of Mitila

ashva (asva) = horse

ashva sanchala = horse, riding posture

asteya = nonstealing, freedom from avarice; one of the *yamas*

atman = individual soul, the true self, consciousness; the term Vedanta uses instead of *purusha*

avabhinna = broken

avatara = divine manifestation, descent, advent or incarnation of God. There are ten avataras o Vishnu: Matsya (the Fish), Kurma (the Tortoise), Varaha (the Boar), Narasimha (the Man-Lion) Vamana (the Dwarf), Parasurama, Rama (hero of the epic *Ramayana*), Krishna (hero of the epic *Mahabharata*, who related the *Bhagavad Gita*), Balarama, and Kalki

B

baddha = bound

baka = crane, heron, a wading bird

bala = young, childish, not fully grown

bandha = a bond, tying, energetic lock, contraction, bondage, or fetter; a posture in which certain organs or body parts are contracted and controlled

Benu = the mythological bird of ancient Egypt symbolic of rebirth and creation, also associated wit the Sun

bhaga = strength

Bhagavad Gita = one of India's most beloved and sacred texts, the divine song of the Lord, the most influential of all *shastras*; the epic story of Arjuna, a warrior prince who confronts moral dilemmas through sacred dialogues with Krishna (one of Lord Vishnu's Avatars) and is led to a better understanding of reality by learning the teachings of Samkhya, Yoga, and Vedanta

Bhagavata Purana = also called Shrimad Bhagavatam, a *purana* that deals with devotion to the Supreme Being in the form of Lord Vishnu and describes some of the avatars of Vishnu, includin Krishna

bhairava = terrible, gruesome, formidable; one of the fierce manifestations of Shiva

bhakti = devotion, worship or love; from *bhaj*, (to divide), the belief that there is an eternal divide between the Supreme Being and the world that cannot be overcome through knowledge, hence the Supreme Being must be met with an attitude of devotion

bhangi = position

Bharadvaja (Bharadwaja) = a Vedic *rishi*, great warrior described in the *Mahabharata*, Pindola Bharadvaja was one of four *arhats* asked by Buddha to stay on earth to propagate Buddhist law, or *dharma*

bharman = load, nourishment, care, burden, maintenance load

bheka = a frog

bherunda = terrible, frightful; it also means a species of a bird or a name of a yogi

bhuja = arm or shoulder

bhujanga (bhujagga) = serpent, snake

bhuja-pida = pressure on the arm or shoulder

bidala = cat

bija-mantra = a mystical syllable with a sacred prayer repeated mentally during *pranayama*, and the seed thus planted in the mind germinates into one-pointedness

bindu (bindhu) = seed, point, dot, the creative potency of anything where all energies are focused, the third eye

bitila = cow

Brahma = a five-headed first deity of the Hindu Trinity; the Supreme Being, the creator; responsibl for the creation of the world, he is the first being to appear at the dawn of each universe to create it based on its subconscious conditioning: the Brahma of the present universe is called Prajapati (progenitor), the predecessor of humankind

brahmachari = a religious student vowed to celibacy and abstinence; one who is constantly moving (*charin*) in *brahman* (The Supreme Spirit); one who sees divinity in all

brahmacharya = chastity or teacher of the soul, abstinence, a life of celibacy, religious study and self-restraint, recognition of Brahma in everything; one of the *yamas*

Brahman = the absolute, or divinity itself, infinite consciousness, universal soul, deep reality, the reality that cannot be reduced to a deeper layer; the Supreme Being, the cause of the Universe, the all-pervading spirit of the Universe

Buddha = enlightened one

C

chakora = a type of bird like a partridge (Greek partridge), moonbeam bird, said to feed on moonbeams

chakra = literally, a wheel or circle, the wheel of a wagon; metaphorically, psycho-energetic subtle centers of the subtle body in which energy flows, located along the spine, believed to transform cosmic energy into spiritual energy when activated. Energy (*prana*) is said to flow in the human body through three main channels (*nadis*), namely, *sushumna*, *pingala,* and *ida*; *sushumna* is situated inside the spinal column. *Pingala* and *ida* start respectively from the right and the left nostrils, move up to the crown of the head, and course downward to the base of the spine. These two *nadis* intersect with each other and also the *sushumna*. These junctions of the *nadis* are known as *chakras* of the flywheels, which regulate the body mechanism. The important *chakras* are: (a) *muladhara* (*mula* = root, source; *adhara* = support, vital part) situated in the pelvis, above the anus; (b) *svadhishtana* (*sva* = vital force, soul; *adhishtana* = seat of abode) situated above the organs of gestation; (c) *manipuraka* (*manipura* = navel) situated in the navel; (d) *manas* (mind) and (e) *surya* (the sun) which are situated between the navel and the heart; (f) *anahata* (= unbeaten) situated in the cardiac area; (g) *vishuddha* (= pure) situated in the pharyngeal region; (h) *ajna* (= command) situated between the eyebrows; (i) *sahasrara* (= a thousand) which is called a thousand-petaled lotus in the cerebral cavity; and (j) *lalata* (= forehead) which is at the top of the forehead.

chalana = to churn

chamatkara = delight or savoring; the refined pleasure that a connoisseur takes in a lovely poem, painting, or fine wine. Chamatkarasana is translated as “Wild Thing Pose” probably because the posture looks like someone who has just seen something so amazing and beautiful that they are “bowled over” or “blown away.”

chandra (candra) = moon

chapa = bow, rainbow, arc

chatur (chatuari, chatura) = four

chatush = four times

chatushpada = quadruped

chikitsa = therapy

chitta = consciousness that comprises mind, intellect, the restraint of consciousness; a mind in its total or collective sense, being composed of three categories: (a) mind, having the faculty of attention, selection, and rejection; (b) reason, the decisive state which determines the distinction between things; and (c) ego, the I-maker, the aggregate of intellect (*buddhi*), egoity (*ahamkara*) and thinking agent (*manas*)
chittavritti (chitta-vritti, chitta vritti) = an imbalance of the mental state, fluctuations of the mind, movement of the consciousness; a course of behavior, mode of being, condition, or mental state
cibi = chin

D

dakshina = the right side
danda = stick, staff (refers to the spine)
dasha = ten
dhanu (dhanura) = bow
dharana = concentration, sixth limb of Ashtanga yoga, orienting the mind toward a single point
dhyana = generally translated as meditation, freedom from attachments, an ongoing stream of awareness from the meditator toward the object of meditation, and of information from the object toward the meditator; the seventh limb of Ashtanga yoga
dhyana-yoga = yoga of meditation
Diti = the mother of the demons, also called Daityas
drishti = focal point, perception or looking place, “view” or “sight”: yogic gazing, such as at the tip of the nose or the spot between the eyebrows
dur = difficult
Durvasa = a very irascible, notoriously angry sage
dvija = twice-born
dwi (dve) = two
dwihasta = two hands
dwipada = two feet or legs

E

eka (ekam) = one
eka-pada (ekapada) = one leg, one-legged, one-footed

G

gaja = elephant
Galava = the pupil or son of Viswamitra
ganda = the cheek or side of the face including the temple
gandha = subtle earth element; quantum of (*tanmatra*) earth; smell
gandha-bherunda = a species of bird, also a two-headed mythological bird that embodies immense powers and destructive forces
garbha = an infant, womb, fetus

garbha kosha = uterus

garbha pinda (garbha-pinda) = fetus, embryo in the womb

Garuda = Hindu deity, half-man half-eagle, fierce bird of prey, vehicle (*vahana*) of Lord Vishnu, king of birds; Garuda is represented as a vehicle of Vishnu and as having a white face, an aquiline beak, red wings, and a golden body

gava = cow

Gheranda = author of *Gheranda Samhita*, an important text on Hatha Yoga which he taught to Chanda Kapali

Gheranda Samhita = a Tantric treatise describing Hatha Yoga written by the sage Gheranda in the 15th century

Gitananda = a well-known *yogi*, living in the 20th century CE

go = cow

godha = iguana

gomukha = cow face, face resembling a cow, cow head; it is also a kind of musical instrument, narrow at one end and broad at the other, like the face of a cow

Goraksha (Goraksha, Gorakshanath) = an 11th to 12th Century Hindu Nath*yogi*, one of Matsyendranath's two most important disciples; tending to or breeding cattle, cowherd

graiva = a chain worn around the neck of an elephant; necklace or collar

guru = "he who is heavy, weighty," a spiritual teacher or preceptor, one who illuminates the darkness of spiritual doubt, one who hands down a system of knowledge to a disciple; heavy one or dark/light, dispeller of darkness, one who helps to gain knowledge

guru-shishya parampara = the tradition of teaching dating back centuries, where a guru imparts his knowledge to his students

H

ha = first syllable of the word *hatha*, which is composed of the syllables *ha* (= sun) and *tha* (= moon); the object of Hatha Yoga is to balance the flow of solar and lunar energy in the human system

hala = plow

hamsa (hansa) = a swan; a metaphor for the soul; a vehicle of Lord Brahma; the name of the mantra by which *prakriti* permeates the universe; also refers to the breath as it moves within the body

Hanuman = a powerful monkey chief, a mythological entity, of extraordinary strength and prowess, whose exploits are celebrated in the epic *Ramayana*; he was the son of Anjana and Vayu, the god of wind, monkey-god, hero of *Ramayana*, egoless superhero and perfect devotee, who resembles a monkey leaping

hasta = hand

hastasana = forward stretch of the arms

hatha = force; the word *hatha* is used adverbially in the sense of "forcibly" or "against one's will"; Hatha Yoga is so called because it prescribes rigorous discipline in order to find union with the Supreme

hatha-vidya = the science of Hatha Yoga

Hatha Yoga = "Forceful Yoga," a major branch of yoga, developed by Goraksha and other adepts c.

1000–1100 CE, emphasizing the physical aspects of the transformative path, notably postures (*asana*), cleansing techniques (*shodhana*) and breath (*pranayama*); literally, sun/moon yoga (*ha* = sun, *tha* = moon), it emphasizes balancing the solar and lunar energy channels in the body. Hatha Yoga shifted the focus away from the mysticism and philosophy of the older Upanishadic types of yoga toward using the body as a tool; combines opposing forces to achieve balance, sighting the soul through the restraint of energy, yoga concerned with mastering control over the physical body as a path to enlightenment (self-realization)

Hatha Yoga Pradipika = a celebrated treatise on yoga compiled in the 12th century by the sage Svatmarama

himsa = violence, killing

Hindola = cradle or swing; also Hindu Religious Festival associated with baby Krishna being rocke in a decorated swing

I

ida = a *nadi*, a channel through which *prana* moves, starting from the left nostril, then moving to the crown of the head and then descending to the base of the spine on the left side; in its course it conveys lunar energy and so is called *chandra nadi,* "channel of the lunar energy"; associated with pale or blue (left/feminine)

Indra = ruler, lord of thunder, king of the heavens

indudala = crescent moon

Ishvara = God, the Supreme Being, Brahman, with form

ishvara pranidhana = one of the *niyamas*; centering on the divine, devotion or surrender to God, dedication to the Lord of one's actions and one's will

J

jalandhara bandha (jalandharabandha) = a *bandha* that locks the throat, chin lock; straightening the back of the neck by keeping your head straight while slightly receding your chin; a yoga pose where the neck and throat are contracted and the chin is rested in the notch between the collarbones at the top of the breast-bone

janu = knee

jatara = stomach, belly, or the interior of anything

jatara-parivartana = an action of an *asana* (yoga pose) in which the abdomen is made to move to and fro

Jnana Yoga = the emphasis is on questioning, contemplation, and meditation as a path to enlightenment, yoga that seeks to teach the identity of the individual self (*atman*) and the infinite consciousness (*brahman*)

K

kaka = crow

Kala Bhairava = Shiva in his terrible or gruesome form as Destroyer of the Universe

Kali = Hindu Goddess of Time and Change

Kamala = Hindu Goddess of Wealth, “One of the Lotus”

Kamalamuni = one of the 18 Siddhars believed to be over 4,000 years old

kanda = a bulbous root, a knot, egg, stem, stalk, trunk; the *kanda* is a round shape of about four inches situated twelve inches above the anus and near the navel, where the three main *nadis* (*sushumna*, *ida*, and *pingala*) unite and separate; it is covered as if with a soft white piece of cloth

kapala = skull

kapalabhati = bellow-like breathing technique with sharp, quick inhalations and exhalations; a cleansing ritual for the respiratory tract, lungs, and sinuses; skull shining

kapila = a sage or *rishi*, the founder of the Samkhya system, one of the six orthodox systems of Hindu philosophy, noted in the *Bhagavad Gita* and *Bhagavata Purana* as a manifestation of the Supreme Being

kapinjala = a kind of partridge, the *chataka* bird, which is supposed to drink only raindrops

kapota = dove, pigeon

kapya = monkey

karanda = duck

karani = making, doing

karma (karma law) = action, activity of any kind, including ritual acts; said to be binding only so long as engaged in a self-centered way; the law of cause and effect, or the movement toward balanced consciousness: everything that you do, say, or think has an immediate effect on the universe that will reverberate back to you in some way

karma yoga (karma-yoga) = yoga of action, path to enlightenment is through selfless acts and service to others, the achievement of union with the Supreme Universal Soul through action; in its original Vedic sense, Karma Yoga is any yoga that employs ritualistic action, such as *asana*, meditation, or *mantra*, to produce spiritual gain. The term excludes Jnana Yoga and Bhakti Yoga, which are thought to operate beyond spiritual gain

karna = the ear; also one of the heroes in the *Mahabharata*

karna-pida = pressure around the ear, blocked ears

Kashyapa = an ancient Hindu sage, husband of Aditi and Diti; he is one of the lords or progenitors o living things

khaga = bird

khanjana = a wagtail bird

Khimi Karani = mythological pond of milk in which Garuda drowned a snake to give birth to the Shami Tree

kona = angle

Konganar = one of the Siddhars, student of Siddhar Bogar

Koormamuni = Hindu Sage

Korakar = one of the 18 Siddhars, a well-known sage, author of works on philosophy, medicine, and alchemy

Koundinya (Kaundinya) = Hindu sage, Vedic scholar, and a descendant of Vasishta

kriya = act, action, cleansing

kriya yoga = the yoga of action and participation in life, preliminary yoga consisting of simplicity (*tapas*), the reading of sacred texts (*svadhyaya*), and acceptance of the existence of a Supreme Being (*ishvarapranidhana*); also, a Tantric mode of yoga using breath, *mantra*, and visualization.

krakacha = a saw
krounch (krouncha, krauncha) = heron
kukkuta = rooster, cock
kulpa = ankle
kundalini = a coiled female serpent; the divine cosmic energy, the obstacle that closes the mouth of *sushumna*; the rising of *shakti* in the *sushumna*; this force or energy is symbolized as a coiled and sleeping serpent lying dormant in the lowest nerve center at the base of the spinal column, the *muladhara-chakra*. This latent energy has to be aroused and made to ascend the main spinal channel, the *sushumna* piercing all the *chakras* right up to the *sahasrata*, the thousand-petaled lotus in the head. Then the *yogi* is in union with the Supreme Universal Soul.
Kundalini Yoga = a mode of yoga that focuses on the raising of the life force
kunja = grove, alcove
kunta = spear, lance
kurma (koorma) = a tortoise, it is also the name of one of the subsidiary vital airs whose function is to control the movements of the eyelids to prevent foreign matter or light that is too bright going into the eyes

L

laghu = little, small, simple; it also means “handsome”
lasya = beauty, happiness, and grace; also a dance performed by Goddess Parvati in response to her husband Shiva’s *tandava*
Linga (Lingam, Shivalinga) = symbol of union and origin of all life associated with Lord Shiva and Goddess Shakti
lola = tremulous, dangling, pendant; charm, swing; swinging like a pendulum, moving to and fro

M

madhya (madya) = middle of the body, central
maha = great, mighty, powerful, lofty, noble
maha bandha = the great lock
maha mudra = the great seal
Mahabharata = the celebrated epic, the largest piece of literature created by humankind, authored by Rishi Vyasa and containing the *Bhagavad Gita*, dating to the first century BCE;*dharma shastra* (scripture dealing with right action), which comes to the conclusion that however hard you try, you can never be completely right
makara = a mythological sea creature, who is the vehicle of the river Goddess Ganga; a crocodile
makshika = fly
mala = a garland or a wreath, often of prayer beads or flowers
manas-chakra = nervous plexus situated between the navel and the heart
mandala = a circle ambulation, a circular drawing or design that exemplifies sacred geometry that draws your eye to the center and is used as a focal point while meditating; it also means a “collection,” a division of Rig Veda
manduka = frog

manipuraka = a nervous plexus situated in the region of the navel; the third *chakra*, the navel *chakra*, the fire energy center, site of the sense of fear and apprehension

mantra = a mystical syllable designed to create and alter reality by influencing the vibrational patterns that make up creation; a sacred sound or phrase that has a transformative effect

Marichi = a sage, son of Brahma, the great-grandfather of Manu, the Vedic Adam and the father of humanity, the creator of the universe, and the father of Kasyapa

marjarai = cat

matsya = fish

Matsyendra = a Hindu sage and one of the first teachers of Hatha Yoga; a legend, king or lord of the fish

mayura = peacock

moksha (moksha) = liberation from bondage, final emancipation of the soul from recurring births

mrita (mrta, mritra) = dead, corpse

mudra = a seal; a pleasant hand gesture or seal posture; directs the life current (life energy) through the human body, usually a combination of *asana*, *pranayama*, and *bandha*

mukha = face

mukta = free, unbound, liberated

mukti = release, liberation, final absolution of the soul from the chain of birth and death

mula = root, foundation, bottom; a yoga pose where the body from the anus to the navel is contracted and lifted toward the spine

mula bandha (mula-bandha) = rectal lock, root lock; contraction of the pubococcygeus, a yoga pose where the body from the anus to the navel is contracted and lifted up and toward the spine

muladhara = root foundation, the name of the first *chakra*

muladhara chakra = the first *chakra*, the base *chakra*, the earth energy center situated at the root of the spine, nervous plexus situated in the pelvis above the anus at the base or root of the spine, the main support of the body that controls sexual energy

mushti = fist

mutra kosa = bladder

N

nabi = navel

nadi = river; nerve or conduit, channels that distribute energy from the *chakras* throughout the body, a tubular organ of the subtle body through which energy flows, subtle vibratory passages of psychospiritual energy; it consists of three layers, one inside the other, like insulation of an electric wire. The innermost layer is called the *sira* and the middle layer, *damani*. The entire organ as well as the outer layer is called *nadi*; they connect at special points of intensity (*chakras*).

naga = great mythological snake; one of the subsidiary vital airs that relieves abdominal pressure, causing one to belch

Nahusha = Hindu King of Aila Dynasty

nakra = crocodile

namaskar = greeting, worship, salutation with hands in prayer

namaste mudra = a *mudra* in which the hands are placed together in a prayerlike fashion to honor the

inner light
nantum = to bow with respect
nara = a man
Narasimha = an avatar of the Hindu god Vishnu in his fourth incarnation, often visualized as half-man, half-lion
nasika = nose
nata = actor, dancer, mime
Nataraj = name of Shiva as a cosmic dancer, the lord of the dancers
natya = dancing
nauka = boat
nava = boat
nava = nine
nidra = deep, dreamless sleep; the third state listed in the *Mandukya Upanishad*. The others are waking state (*jagrat*), dream (*susupt*), and consciousness (*turiya*); also the fourth fluctuation of the mind listed by Patanjali in *Yoga Sutra* I.6 (the others are correct cognition, wrong cognition, perceptualization, and memory).
nindra (nantra) = sage, praise, wonder
nindra (nitara) = standing firm, standing
nir = without
nira = water
niralamba = self-supported, independent, without support
niyama = self-restraint, personal observances, self-purification by discipline, the Vedic system of logic; the second stage or limb of Ashtanga Yoga mentioned by Patanjali; five personal disciplines, as defined by Patanjali in his *Yoga Sutras*: *shaucha, santosha, tapas, svadhyaya,* and ishvarapranidhana

O

om (aum) = the original *mantra* symbolizing the ultimate reality, the sacred syllable emitted by the Supreme Being, the sound that produces all other sounds and into which all other sounds return. Like the Latin word *omne*, the Sanskrit work *aum* means "all" and conveys concepts of Omnipotence, Omnipresence, and Omniscience.

P

pada = foot or leg; also a part of a book or text
pada-hasta = hand(s)-to-feet
padangushta = big toe
padma = lotus
pakshaka = wing
pakshi = bird
pancha = five
parampara = tradition, uninterrupted series, convention, a succession
parigha = iron bar used for locking, bolting, or shutting a gate

parigraha = hoarding, possessiveness
paripurna = full, entire, complete
parivartana = turning around, revolving
parivartana-pada = with one leg turned around
parivid = twined, twisted around
parivritta = revolved, turned around
parivritti = crossed or with a twist, turning, rolling
parshva = the side, flank, lateral
parshvaika = *parsva* (side) + *eka* (one)
parshvaika-pada = with one leg turned sideways
parvata = mountain
paryanka = a bed, a couch
pasa (pasha) = snare, trap, noose, fetter
paschima = the back of the whole body from head to heels, west side, western
paschimatana = intense stretch of the back side of the body from the nape to the heels
pakshya = being in or belonging to the wings
patan = to collapse
Patanjali = a sage, the author of the *Yoga Sutras*, a treatises on Sanskrit and *Ayurveda*; the founder of yoga, most likely lived between 200 BCE and 300 CE; a manifestation of the serpent of infinity
pavanamuktasana = wind release pose
perineum = the area between the thighs, behind the genitals, and in front of the anus
pichamayura = peacock with stretched feathers
pid = squeeze
pida = pain, discomfort, pressure
pincha = a feather of a tail, the chin
pinda = a fetus, an embryo in an early stage of gestation, ball, the body
pingala = a channel on the right side of the spine through which *prana* moves, associated with reddish color, a *nadi* or channel of masculine energy starting from the right nostril, then moving to the crown of the head and then downward to the base of the spine; as the solar energy flows through it, it is also called *surya-nadi*
pitam = stool, chair
plavana = jump through
pliha = the spleen
poorna = full
prana = breath, life, vitality, wind, energy, strength; connotes the soul, life force or inner breath; sometimes refers to anatomical or outer breath; vital upward energy current
pranayama = breath control, energy control through breathing, consisting of conscious inhalation (*puraka*), retention (*kumbhaka*), and exhalation (*rechaka*), breath extension, breathing exercises to harmonize the flow of life force; the fourth stage or limb of Ashtanga Yoga
prapada = tip of the feet
prasarita = spread, stretched out
pratyahara = internalization of the senses, independence from sensory stimuli; the fifth stage or limb of Ashtanga Yoga, withdrawal and emancipation of the mind from the domination of the senses and

sensual objects; withdrawal of the mind, mental detachment from the external world
prishta = back
Punakeesar (Punnakeesar) = one of the Siddhars, a *guru* of Machamuni (also referred to as Matsyendra)
pungu = Telugu word for “wounded”
purna = complete
purva = eastern
purvottana = intense stretch of the front side of the body

R

raja = king, royal
raja yoga (raja-yoga) = royal yoga; a term generally applied to the three higher limbs of Ashtanga Yoga, that is *dharana, dhyana,* and *samadhi*; the royal road to self-realization through the control of the mind. The achievement of union with the Supreme Universal Spirit by becoming the ruler of one’s own mind by defeating its enemies, sighting the soul through a restraint of consciousness
raja-kapota (rajakapota) = king pigeon
Ramayana = literally, Rama’s way; a famous ancient epic (*itihasa*) authored by Sage Valmiki that describes the life of Rama, an *avatar* of Lord Vishnu
Rig Veda = literally “Knowledge of Praise,” it consists of 1,028 hymns and is the oldest known reference to *yoga* and possibly the oldest known text in the world
rishi = a Vedic seer, a liberated sage or saint, one who through suspension of the mind can see to the bottom of his heart
Ruchika (Richika, Ruschika) = name of a Hindu sage, dedicated to the grandfather of an incarnation of Vishnu

S

sa = with
sahaja = easy, natural
sahasrara chakra = energy center situated at the crown of the head, the thousand-petaled lotus in the cerebral cavity, the most important seventh *chakra* which, when uncoiled, brings the seeker to freedom
St. Brighid = known for establishing numerous monasteries
sakti = power
salamba = with support
sama = same, equal, even, upright
samadhi = “putting together”: the ecstatic or state in which the mediator becomes one with the object of meditation, forgetting him/herself completely (the Supreme Spirit pervading the universe) where there is a feeling of unutterable joy and peace, absorption, ecstasy, enlightenment, self-realization; the state of meditation in which ego disappears and all becomes one; a state of absolute bliss; the eighth limb or stage of Ashtanga Yoga
samadhi yoga = yoga of absorption
samastiti = a state of balance

Sankarar = yogi from the eighth century BC
Sanskrit = the programming language used to write the operating system of the subtle body; the language of the gods
santosha (santosa) = contentment; one of the *niyamas*
sapta = seven
sarpa = serpent, snake
sarva = all, whole
sarvanga = all parts, the whole body
sasanga = rabbit
satya = truth; one of the yamas
Shesha = a celebrated serpent, said to have a thousand heads; Sesa is represented as the couch of Vishnu, floating on the cosmic ocean, or as supporting the world on his hoods; other names of Shesha are Ananta and Vasuki
setu = a bridge, dam, dike
setu-bandha = the construction of a bridge; name of an *asana* in which the body is arched
shalabha = grasshopper, locust
Shankara, Adi = world teacher, yoga master, propounder of Jnana Yoga and Advaita Vedanta; author of commentaries on the *Brahma Sutra*, the *Upanishads*, the *Bhagavad Gita* and thirty other texts; founder of ten monk orders and four large monasteries whose abbots today still carry the title Shankaracharya. His dates are disputed. Western academics often place him at 800 CE. Tradition places him at 1800 BCE. Also known as Shankaracharya or Shankara Bhagavatpada
shanti = peace
shat = six
shaucha = purity or inner and outer cleanliness; one of the *niyamas*
shava (shava) = corpse
shayana = bed, couch, sleeping
shirsha = head
Shiva (Siva) = the most Powerful God in Hinduism, the Destroyer, a name of the Supreme Being pure consciousness, Brahman with form
shvana (swana) = dog; inspiration
shvnaka = puppy dog
siddha = accomplished, fulfilled, perfected; a sage, seer, or prophet; also a semi-divine being of great purity and holiness, a perfected being, a yoga master who has become an immortal, ethereal being
siddhi = divine attribute, perfection, supernatural power, proof
simha = lion
Skanda = a name of Kartikeya, the god of war, general of the celestial army, Lord of War, second son of Lord Shiva and Godmother Uma Parvat
stamba = transition
steya = theft, robbery
sucirandra = threading the needle
sukha = ease, lightness, comfort, happiness, delight, joy, pleasure; literally, agreeable mental space
Sundaranandar = one of the eighteen Siddhars, author of numerous works on medicine

supta = lying down or sleeping, reclining, supine
surya = sun
surya yantra = sun dial
surya-chakra = nervous plexus situated between the navel and the heart
surya-nadi = the *nadi* of the Sun; another name for *pingala-nadi*
sushumna = the main *nadi* channel situated inside the spinal column, a hollow passageway between *pingala nadi* and *ida nadi* that runs through the spinal cord, and through which *kundalini* can travel once it is awakened
sutra = thread: a work consisting of aphoristic statements such as Patanjali's *Yoga Sutra*
sva = one's own, innate, vital force; soul, self
svadhyaya = education of self by study of divine literature, self-study, to study one's body, mind, intellect, and ego; one of the *niyamas*
svarga = heaven
svastika = good fortune
Svatmarama = the author of *Hatha-yoga-pradipika*, a classical textbook on Hatha Yoga
swadhishtana chakra = site of worldly desires, energy center located above the organ of generation
Swami Sivananda = a well-known *yogi* of the 20th century, founder of Sivananda Yoga
Swami Vishnu Devananda = a close disciple of Swami Sivananda

T

taal-vrksa = palm tree
tada = mountain, straight tree
tadasana-samasthiti = a state of balance; an even distribution of weight while standing
tan = stretch, lengthen out or extend
tana = to stretch out, extend
Tandava (Thandava) = sacred frantic dance representing the cosmic cycles of creation and destruction performed by the Hindu Deity Lord Shiva
tantra = thread on the loom
Tantra (Tantric) Yoga = this yoga is characterized by certain rituals designed to awaken the *kundalini*
tap = to burn, to blaze, to shine, to suffer pain, to be consumed by heat
tapa = austerity
tapas = a burning effort, glow, heat; austerity gained through the committed practice of yoga, self-discipline; practice with discipline, devotion and religiosity; one of the *niyamas*
tara = star
Taraka = a demon slain by Kartikeya, the god of war
tha = the second syllable of the word *hatha*; the first syllable *ha* stands for the sun, while the second syllable *tha* stands for the moon; the union of these two is represented in Hatha Yoga
thavali = frog in Tamil
tirieng = horizontal, oblique, transverse, reverse, upside down
tiryak= horizontally, sideways, obliquely, across
tiryang-mukha = backward facing
tittibha = a small bird living along the coastline; firefly; or insect

tola = balance, scale
tolana = weighing
tri (tri, tra) = three
tryanga = three limbs
trikona = three angle or triangle
Trivikrama = Vishnu in his fifth incarnation, The Dwarf *avatar* of Lord Vishnu, who with his three steps (*krama*) filled the earth, heaven and hell, the conqueror of three worlds
tulya = equilibrium, balance

U

ubhaya = both
uddayate = fly, soar, fly up
uddiyana = a fetter or bondage, a yogic abdominal lock; here the diaphragm is lifted high up the thorax and the abdominal organs by tilting your pelvic floor up and pulling your belly button back toward your spine; the *uddiyana-bandha,* the great bird *prana* (life), is forced to fly up through the *shushumna-nadi*; to fly up
ujjayi = a *pranayama* that produces sound in the throat with the inhalation, literally meaning "extended victory"; the lungs are fully expanded and the chest is puffed out, slow throat breathing
Upanishad = the word is derived from the prefixes *upa* (near) and *ni* (down) added to the root *shad* (to sit); it means sitting down near a *guru* to receive spiritual instruction. The *Upanishad* scriptures of ancient Hindu philosophy are the philosophical portion of the Vedas, the most ancient sacred literature of the Hindus, dealing with the nature of man and the universe and the union of the individual or self with the Universal Soul
upavishta (upavistha) = seated, sitting, with legs spread
urdhva (urdhwa) = upward, raised, elevated, inverted
urdhva-mukha = face upward
ushtra (ustra) = camel
ut = intense, a particle denoting intensity
utkata = fierce, powerful, exceeding the usual measure, excessive, squat
utpluti = lifting or pumping up
utripada = upright tripod
uttana = an intense stretch, upright
utthita = extended, risen or rising, raised up, stretched

V

Vaasamuni Siddhar = a disciple of Shiva
vadivu = old form; Gaja Vadivu is an animal posture from Kalari Yoga, a mystical tantric form of *yoga*, which stems from Kalarippayat
vajra = thunderbolt, Indra's weapon
Vajracchedika Prajnaparamita Sutra = Diamond Cutter Sutra, one of the *sutras* of Mahayana Buddhism focusing on non-attachment
vakra = bent, curved, crooked

Valakhilya = flying wise and virtuous companions, celestial beings; a class of divine personages of the size of a thumb, produced from the Creator's body, and said to precede the chariot of the sun

Valmiki = known as the father of Sanskrit classical poetry

vama = left side

Vamadeva = the name of the preserving aspect of the God Shiva

vamana = Vishnu in his fifth incarnation, when he was born as a dwarf to humble the demon king Bali

Vasishta = a celebrated sage, author of Yoga Vasistha; several Vedic hymns, most excellent, best, richest

vatayana = horse

vayu = air, vital force, wind, vital air

Vedas = the sacred scriptures of the Hindus, revealed by the Supreme Being

vibhuti = might, power, greatness

vimshati = twenty

vini = single movement

vinyasa = a steady flow of connected yoga *asanas* linked with breath, work in a continuous movement, going progressively, variation

viparita = reversed, inverted, turned

vira = a brave or eminent man, heroic, chief, hero

virabhadra = a legendary warrior, a powerful hero created out of Shiva's matted hair

Virancha (Viranchi) = one of the names of Lord Brahma

vishama = uneven, unequal

Vishnu (Vishnu, Narayana, Hari) = the second deity of the Hindu Trinity, All-Pervading essence of all beings, one who supports, Preserver God

vishuddhi chakra = seat of intellectual awareness, energy center situated behind the throat, the nervous plexus in the pharyngeal region

vishva = entire, whole

Vishvamitra = a celebrated Hindu Sage, ruler so impressed with Vasistha's knowledge and contentment that he became his disciple

vrischika = scorpion

vriksha = tree

vrishta = fallen or dropped as rain

vyaghra = tiger

Y

yajna = Hindu Sacrificial Ceremony

yama = ethical codes for daily life, self-restraint

Yama = the god of death; Yama is also the first of the eight limbs or means of attaining yoga. Yamas are universal ethical codes for daily life, self-restraint, and moral commandments or ethical disciplines transcending creeds, countries, age, and time. The five mentioned by Patanjali are: non-violence, truth, non-stealing, continence, and non-coveting

yantra = to sustain

yoga = union, communion, the path which integrates the body, senses, mind, and the intelligence with the self, derived from "yuj", meaning to join or to yoke, to concentrate one's attention on. It is the union of our will to the will of God, a poise of the soul which enables one to look evenly at life in all its aspects. The chief aim of yoga is to teach the means by which the human soul may be completely united with the Supreme Spirit pervading the universe and thus secure absolution

yoga-mudra = a posture, a seal

yoga-nidra = the sleep of yoga, where the body is at rest as if in sleep while the mind remains fully conscious, though all its movements are stilled; *yoga-nidra* is also the name of an *asana*

Yogananda = a great yogi of the twentieth century

yogasana = yogic posture

Yoga Sutra (yoga-sutra) = a classical collection of aphorisms on the practice of yoga, attributed to the sage Patanjli. It consists of 185 terse aphorisms on yoga and it is divided into four parts dealing respectively with *samadhi*, the means by which yoga is attained, the powers the seeker comes across in his quest, and the state of absolution

yogi or yogini = one who follows the path of *yoga*, a student, a seeker of truth

yogic = an adjective describing things that are associated with *yoga*

yoni = the womb

yoni-mudra = womb or female seal or awakened *kundalini*, the sealing; the breeding place, and *mudra* is a seal; *yoni-mudra* is a sealing posture where the apertures of the head are closed and the aspirant's senses are directed within to enable him to find out the source of his being

yudha = from Yudhisthira, a legendary warrior mentioned in the ancient Hindu epic *Mahabharata*

yuj = to join, to yoke, to use, to concentrate one's attention on

yukti = union

[*] “Bitilisana” may also be translated as “Gavasana” in the following cow poses.

[*] “Ushtrasana” may also be spelled as “Ustrasana” in the following camel poses.

[*] “Shirshasana” may also be spelled as “Sirsasana” in the following headstand poses.

Thank you for buying this ebook, published by Hachette Digital.

To receive special offers, bonus content, and news about our latest ebooks and apps, sign up for our newsletters.

Sign Up

Or visit us at hachettebookgroup.com/newsletters

CONTENTS

Cover

Title Page

Welcome

Opening Prayer

A Message from Mr. Yoga

A History of Yoga

The Eight Limbs of Yoga

The *Ujjayi* Breath

The *Bandhas*

The *Drishtis*

How to Approach Yoga Poses

Relaxation and Meditation

A Brief Summary of *Chakras*

Benefits and Cautions for 8 Conditions

STANDING POSES

SEATED POSES

CORE POSES

QUADRUPED POSES

BACKBENDS

ARM BALANCES

INVERSION POSES

PRONE POSES

SUPINE POSES

Acknowledgments

Glossary

Newsletters

Copyright

Copyright

The information herein is not intended to replace the services of trained health professionals or be a substitute for medical advice. You are advised to consult with your health care professional with regard to matters relating to your health, and in particular regarding matters that may require diagnosis or medical attention.

Neither this exercise program nor any other exercise program should be followed without first consulting a health care professional. If you have any special conditions requiring attention, you should consult with your health care professional regularly regarding possible modification of the program contained in this book.

Copyright © 2015 Mr. Yoga, Inc.
Photographs copyright © 2015 Daniel Lacerda, Mr. Yoga, Inc.

All rights reserved. In accordance with the U.S. Copyright Act of 1976, the scanning, uploading, and electronic sharing of any part of this book without the permission of the publisher constitute unlawful piracy and theft of the author's intellectual property. If you would like to use material from the book (other than for review purposes), prior written permission must be obtained by contacting the publisher at permissions@hbgusa.com. Thank you for your support of the author's rights.

Black Dog & Leventhal Publishers
Hachette Book Group
1290 Avenue of the Americas, New York, NY 10104
hachettebookgroup.com
blackdogandleventhal.com

First ebook edition: December 2015

Management of layout and design by Tatiana Usova
Cover design by Christopher Lin
Cover photograph by Daniel Lacerda
Cover © 2015 Hachette Book Group, Inc.
Interior design by Sheila Hart Design, Inc.
Additional proofreading by: Aggie Metford, Victoria Bergin, Susan Marchese

Black Dog & Leventhal Publishers is an imprint of Hachette Books, a division of Hachette Book Group.
The Black Dog & Leventhal Publishers name and logo are trademarks of Hachette Book Group, Inc.

The Hachette Speakers Bureau provides a wide range of authors for speaking events. To find out more, go to www.HachetteSpeakersBureau.com or call (866) 376-6591.

The publisher is not responsible for websites (or their content) that are not owned by the publisher.

ISBN 978-0-316-27062-5

E3

2,100 ASANAS

THE COMPLETE YOGA POSES



DANIEL LACERDA

FOUNDER OF MR. YOGA, INC.

BKS IYENGAR

FOREWORD BY YEHUDI MENUHIN

The Illustrated Light on Yoga

An Easy-to-follow Version
of the Classic
Introduction to Yoga



FOR SALE IN THE INDIAN SUBCONTINENT ONLY

'Mr Iyengar's *Light on Yoga* has, since it was first published over 25 years ago, enabled many to follow his example . . . This new concise edition will bring the basic art of yoga to a much wider audience and will enable it to be practised at the very highest level.'

Yehudi Menuhin

The Illustrated Light on Yoga is a straightforward and comprehensive introduction for the beginner by the acknowledged expert on the subject. Illustrated throughout with150 photographs carefully positioned in the relevant part of the text for easy reference, it includes:

- **An introduction to the philosophy and practice of yoga**
- **Detailed descriptions of 57 key postures**
- **Techniques for stilling the mind through breathing exercises**
- **A 35-week course progressing from beginner to intermediate level**
- **A full glossary of yoga terms**

B K S Iyengar has been teaching and demonstrating yoga for more than 50 years. He has several million students and has established centres all over the world.

Rs. 250
ISBN 81-7223-606-9
9788172236069 00250
HEALTH/YOGA

For sale in the Indian subcontinent only

The Illustrated Light on Yoga

B. K. S. Iyengar's classic book *Light on Yoga* is a comprehensive introduction to yoga with detailed descriptions of over 200 postures (āsanas) and 14 breathing exercises (prānāyāmas). This book, *The Illustrated Light on Yoga,* introduces 57 key āsanas and provides a brief summary of prānāyāma. The book is illustrated throughout with photographs positioned in the relevant part of the text. The student can, therefore, practise a posture without the aid of a teacher. An Appendix provides an āsana course for the continuing student. *The Illustrated Light on Yoga* is a comprehensive yet straightforward introduction for the beginner by the acknowledged expert on the subject.

By the same author:

LIGHT ON YOGA
LIGHT ON PRĀṆĀYĀMA
LIGHT ON THE YOGA SŪTRAS OF PATAÑJALI
THE TREE OF YOGA

THE ILLUSTRATED

Light on YOGA

Yoga Dipika

B. K. S. IYENGAR

Foreword by Yehudi Menuhin

HarperCollins *Publishers* India
a joint venture with
THE INDIA TODAY GROUP
New Delhi

HarperCollins *Publishers* India
a joint venture with
The India Today Group
by arrangement with
HarperCollins *Publishers* Limited

First published by George Allen & Unwin 1966
This abridged edition first published as
The Concise Light on Yoga by Unwin Paperback 1980
Large format edition first published by the Aquarian Press 1993
Thorsons edition 1995

First published in India by
HarperCollins *Publishers* India 1997

Tenth impression 2005

Copyright © George Allen & Unwin (Publishers) Ltd 1966, 1968, 1976, 1980

B.K.S. Iyengar asserts the moral right
to be identified as the author of this work.

All rights reserved. No part of this publication may be reproduced,
stored in a retrieval system, or transmitted, in any form or by any
means, electronic, mechanical, photocopying, recording or otherwise,
without the prior permission of the publishers.

HarperCollins *Publishers*
1A Hamilton House, Connaught Place, New Delhi 110 001, India
77-85 Fulham Palace Road, London W6 8JB, United Kingdom
Hazelton Lanes, 55 Avenue Road, Suite 2900, Toronto, Ontario M5R 3L2
and 1995 Markham Road, Scarborough, Ontario M1B 5M8, Canada
25 Ryde Road, Pymble, Sydney, NSW 2073, Australia
31 View Road, Glenfield, Auckland 10, New Zealand
10 East 53rd Street, New York NY 10022, USA

Printed and bound at
Thomson Press (India) Ltd.

DEDICATED TO MY REVERED GURUJĪ

Sāmkya-yoga-Śikhāmaṇi; Veda-kesari; Vedāntavāgīśa;
Nyāyāchārya; Mīmāmsa-ratna; Mīmāmsa-thīrtha

Professor, Śrīmān, T. Krishnamāchārya of
Mysore (South India), India

PRAYER

'I bow before the noblest of sages, Patañjali, who brought serenity of mind by his work on yoga, clarity of speech by his work on grammar and purity of body by his work on medicine.'

'I salute Ādīśvara (the Primeval Lord Śiva) who taught first the science of Haṭha Yoga – a science that stands out as a ladder for those who wish to scale the heights of Rāja Yoga.'

Contents

page

FOREWORD BY YEHUDI MENUHIN xi

PREFACE xiii

Part I: What is Yoga? 1

The Stages of Yoga 3

Part II: Yogāsanas 37

Hints and Cautions 37

Technique and Effects of Āsanas 41

Part III: Prāṇāyāma 117

Hints and Cautions 117

Technique and Effects of Prāṇāyāma 123

APPENDIX: ĀSANA COURSES 131

TABLE OF ĀSANAS 139

GLOSSARY 141

INTERNATIONAL ADDRESSES 157

INDEX 159

Foreword

by Yehudi Menuhin

The practice of Yoga induces a primary sense of measure and proportion. Reduced to our own body, our first instrument, we learn to play it, drawing from it maximum resonance and harmony. With unflagging patience we refine and animate every cell as we return daily to the attack, unlocking and liberating capacities otherwise condemned to frustration and death.

Each unfulfilled area of tissue and nerve, of brain or lung, is a challenge to our will and integrity, or otherwise a source of frustration and death. Whoever has had the privilege of receiving Mr Iyengar's attention, or of witnessing the precision, refinement and beauty of his art, is introduced to that vision of perfection and innocence which is man as first created – unarmed, unashamed, son of God, lord of creation – in the Garden of Eden. The tree of knowledge has indeed yielded much fruit of great variety, sweet, poisonous, bitter, wholesome according to our use of it. But is it not more imperative than ever that we cultivate the tree, that we nourish its roots?

The practice of Yoga over the past thirty years has convinced me that most of our fundamental attitudes to life have their physical counterparts in the body. Thus comparison and criticism must begin with the alignment of our own left and right sides to a degree at which even finer adjustments are feasible: or strength of will may cause us to start by stretching the body from the toes to the top of the head in defiance of gravity. Impetus and ambition might begin with the sense of weight and speed that comes with free-swinging limbs, instead of the control of prolonged balance on foot, feet or hands, which gives poise. Tenacity is gained by stretching in various Yoga postures for minutes at a time, while calmness comes with quiet, consistent breathing and the expansion of the lungs. Continuity and a sense of the universal come with the knowledge of the inevitable alternation of tension and relaxation in eternal rhythms of which each inhalation and exhalation constitutes one cycle, wave or vibration among the countless myriads which are the universe.

What is the alternative? Thwarted, warped people condemning the order of things, cripples criticizing the upright, autocrats slumped in expectant coronary attitudes, the tragic spectacle of people working out their own imbalance and frustration on others.

Yoga, as practised by Mr Iyengar, is the dedicated votive offering of a man who brings himself to the altar, alone and clean in body and mind, focussed in attention and will, offering in simplicity and innocence not a burnt sacrifice, but simply himself raised to his own highest potential.

It is a technique ideally suited to prevent physical and mental illness and to protect the body generally, developing an inevitable sense of self-reliance and assurance. By its very nature it is inextricably associated with universal laws: respect for life, truth, and patience are all indispensable factors in the drawing of a quiet breath, in calmness of mind and firmness of will.

In this lie the moral virtues inherent in Yoga. For these reasons it demands a complete and total effort, involving and forming the whole human being. No mechanical repetition is involved and no lip-service as in the case of good resolutions or formal prayers. By its very nature it is each time and every moment a living act.

Mr Iyengar's *Light on Yoga* has, since it was first published in 1966, enabled many to follow his example and become teachers to carry on his work. I was glad at the time to share in its presentation and I welcome this new concise edition equally enthusiastically. It will bring the basic art of Yoga to a much wider audience and will enable it to be practised at the very highest level.

London, 1980

Preface

It is only thanks to the persistent encouragement of my devoted friends and pupils that this book is now achieved – for alone I would have repeatedly faltered not only because of my inadequate command of the English language but because I would have lost heart without their buoyant support and assurance.

Yoga is a timeless pragmatic science evolved over thousands of years dealing with the physical, moral, mental and spiritual well-being of man as a whole.

The first took to systematize this practice was the classic treatise the *Yoga Sutras* (or Aphorisms) of Patañjali dating from 200 BC. Unfortunately most of the books published on Yoga in our day have been unworthy of both the subject and its first great exponent, as they are superficial, popular and at times misleading. I have even been asked by their readers whether I can drink acid, chew glass, walk through fire, make myself invisible or perform other magical acts. Scholarly and reliable expositions of the religious and philosophical texts already exist in most languages – but the practice of an art is more difficult to communicate than a purely literary or philosophical concept.

The original title of this book was *The Concise Light on Yoga*. Based upon my *Light on Yoga*, which describes *simply* but in great detail the āsanas (postures) and prānāyāmas (breathing disciplines), this book provides a comprehensive introduction to yoga. It describes the techniques for 57 āsanas with the aid of 146 photographs and it also covers prānāyāma with the aid of another four photographs. This new large format edition makes it even more accessible.

The Western reader may be surprised at the recurring reference to the Universal Spirit, to mythology and even to philosophical and moral principles. He must not forget that in ancient times all the higher achievements of man, in knowledge, art and power, were part of religion and were assumed to belong to God and to His priestly servants on earth. The Catholic Pope is the last such embodiment of divine knowledge and power in the West. But formerly, even in the Western world, music, painting, architecture, philosophy and medicine, as well as wars, were always in the service of God. It is only very recently in India that these arts and sciences have begun to shake off the Divine – but with due respect, for the emancipation of man's will, as distinct from the

Divine will, we in India continue to value the purity of purpose, the humility of discipline and the selflessness that are the legacy of our long bondage to God. I consider it important as well as interesting that the reader should know the origin of āsanas, and I have, therefore, included legends handed down by practising yogis and sages.

All the ancient commentaries on yoga have stressed that it is essential to work under the direction of a GURU (Master), and although my experience proves the wisdom of this rule, I have endeavoured with all humility in this book to guide the reader – both teacher and student – to a correct and safe method of mastering these āsanas and prāṇāyāmas.

In the Appendix, I have introduced a 35 weeks' course for the intense practitioner, grouping the āsanas stage by stage according to their structure.

Study in detail the hints and cautions before attempting the āsana and prāṇāyāma techniques.

I am sincerely grateful to my esteemed friend and pupil Mr Yehudi Menuhin for his foreword and immeasurable support.

I am indebted to my pupil Mr B. I. Taraporewala for his collaboration in the preparation of this book.

I express my sincere gratitude to Messrs G. G. Welling of Poona (India), for their personal supervision and interest in taking innumerable photographs for me and for placing the resources of their studio at my disposal.

B. K. S. IYENGAR

PART I

What is Yoga?

The word Yoga is derived from the Sanskrit root yuj meaning to bind, join, attach and yoke, to direct and concentrate one's attention on, to use and apply. It also means union or communion. It is the true union of our will with the will of God. 'It thus means, says Mahadev Desai in his introduction to the *Gita according to Gandhi,* 'the yoking of all the powers of body, mind and soul to God; it means the disciplining of the intellect, the mind, the emotions, the will, which that Yoga presupposes; it means a poise of the soul which enables one to look at life in all its aspects evenly.'

Yoga is one of the six orthodox systems of Indian philosophy. It was collated, co-ordinated and systematized by Patañjali in his classical work, the *Yoga Sutras,* which consists of 185 terse aphorisms. In Indian thought, everything is permeated by the Supreme Universal Spirit (Paramātmā or God) of which the individual human spirit (jīvātmā) is a part. The system of yoga is so called because it teaches the means by which the jīvātmā can be united to, or be in communion with the Paramātmā, and so secure liberation (mokṣa).

One who follows the path of Yoga is a yogi or yogin.

In the sixth chapter of the *Bhagavad Gītā,* which is the most important authority on Yoga philosophy, Śri Krishna explains to Arjuna the meaning of Yoga as a deliverance from contact with pain and sorrow. It is said:

> 'When his mind, intellect and self (ahaṁkāra) are under control, freed from restless desire, so that they rest in the spirit within, a man becomes a Yukta – one in communion with God. A lamp does not flicker in a place where no winds blow; so it is with a yogi, who controls his mind, intellect and self, being absorbed in the spirit within him. When the restlessness of the mind, intellect and self is stilled through the practice of Yoga, the yogi by the grace of the Spirit within himself finds fulfilment. Then he knows the joy eternal which is beyond the pale of the senses which his reason cannot grasp. He abides in this reality and moves not therefrom. He has found the treasure above all others. There is nothing higher than this. He who has achieved it, shall not be moved by the greatest sorrow. This is the real meaning of Yoga – a deliverance from contact with pain and sorrow.

> As a well cut diamond has many facets, each reflecting a different colour of light, so does the word yoga, each facet reflecting a different shade of meaning and revealing different aspects of the entire range of human endeavour to win inner peace and happiness.

The *Bhagavad Gītā* also gives other explanations of the term yoga and lays stress upon Karma Yoga (Yoga by action). It is said: 'Work alone is your privilege, never the fruits thereof. Never let the fruits of action be your motive; and never cease to work. Work in the name of the Lord, abandoning selfish desires. Be not affected by success or failure. This equipoise is called Yoga.'

Yoga has also been described as wisdom in work or skilful living amongst activities with harmony and moderation. 'Yoga is not for him who gorges too much, nor for him who starves himself. It is not for him who sleeps too much, nor for him who stays awake. By moderation in eating and in resting, by regulation in working and by concordance in sleeping and waking, Yoga destroys all pain and sorrow.'

The *Kaṭhopanishad* describes Yoga thus: 'When the senses are stilled, when the mind is at rest, when the intellect wavers not – then, say the wise, is reached the highest stage. This steady control of the senses and mind has been defined as Yoga. He who attains it is free from delusion.'

In the second aphorism of the first chapter of the *Yoga Sutras*, Patañjali describes Yoga as *'chitta vṛtti nirodhah'*. This may be translated as the restraint (nirodhah) of mental (chitta) modifications (vṛtti) or as suppression (nirodhah) of the fluctuations (vṛtti) of consciousness (chitta). The word chitta denotes the mind in its total or collective sense as being composed of three categories:

(a) mind (manas, that is, the individual mind having the power and faculty of attention, selection and rejection; it is the oscillating indecisive faculty of the mind);
(b) intelligence or reason (buddhi, that is, the decisive state which determines the distinction between things);
(c) ago (ahaṁkāra, literally the I-maker, the state which ascertains that 'I know').

The word vṛtti is derived from the Sanskrit root vṛt meaning to turn, to revolve, to roll on. It thus means course of action, behaviour, mode of being, condition or mental state. Yoga is the method by which the restless mind is calmed and the energy directed into constructive channels. As a mighty river which when properly harnessed by dams and canals, creates a vast reservoir of water, prevents famine and provides abundant power for industry; so also the mind, when controlled, provides a reservoir of peace and generates abundant energy for human uplift.

The problem of controlling the mind is not capable of easy solution, as borne out by the following dialogue in the sixth chapter of the *Bhagavad Gītā*. Arjuna asks Śri Krishna:

> 'Krishna, you have told me of Yoga as a communion with Brahman (the Universal Spirit), which is ever one. But how can this be permanent, since the mind is so restless and inconsistent? The mind is impetuous and stubborn, strong and wilful, as difficult to harness as the wind.' Śri Krishna replies: 'Undoubtedly, the mind is restless and hard to control. But it can be trained by constant practice (abhyāsa) and by freedom from desire (vairāgya). A man who cannot control his mind will find it difficult to attain this divine communion; but the self-controlled man can attain it if he tries hard and directs his energy by the right means.'

THE STAGES OF YOGA

The right means are just as important as the end in view. Patañjali enumerates these means as the eight limbs or stages of Yoga for the quest of the soul. They are:

1. Yama (universal moral commandments);
2. Niyama (self purification by discipline);
3. Asana (posture);
4. Prāṇāyāma (rhythmic control of the breath);
5. Pratyāhāra (withdrawal and emancipation of the mind from the domination of the senses and exterior objects);
6. Dhāraṇa (concentration);
7. Dhyāna (meditation);
8. Samādhi (a state of super-consciousness brought about by profound meditation, in which the individual aspirant (sādhaka) becomes one with the object of his meditation – Paramātmā or the Universal Spirit).

Yama and Niyama control the yogi's passions and emotions and keep him in harmony with his fellow man. Ásanas keep the body healthy and strong and in harmony with nature. Finally, the yogi becomes free of body consciousness. He conquers the body and renders it a fit vehicle for the soul. The first three stages are the outward quests (bahiranga sādhanā).

The next two stages, Prāṇāyāma and Pratyāhāra, teach the aspirant to regulate the breathing, and thereby control the mind. This helps to free the senses from the thraldom of the objects of desire. These two stages of Yoga are known as the inner quests (antaranga sādhanā).

Dhāranā, Dhyāna and Samādhi take the yogi into the innermost recesses of his soul. The yogi does not look heavenward to find God. He knows that HE is within, being known as the Antarātmā (the Inner Self). The last three stages keep him in harmony with himself and his Maker. These stages are called antarātmā sādhanā, the quest of the soul.

By profound meditation, the knower, the knowledge and the known become one. The seer, the sight and the seen have no separate existence from each other. It is like a great musician becoming one with his instrument and the music that comes from it. Then, the yogi stands in his own nature and realizes his self (Ātman), the part of the Supreme Soul within himself.

There are different paths (mārgas) by which a man travels to his Maker. The active man finds realization through Karma Mārga, in which a man realizes his own divinity through work and duty. The emotional man finds it through Bhakti Mārga, where there is realization through devotion to and love of a personal God. The intellectual man pursues Jñana, Mārga, where realization comes through knowledge. The meditative or reflective man follows Yoga Mārga, and realizes his own divinity through control of the mind.

Happy is the man who knows how to distinguish the real from the unreal, the eternal from the transient and the good from the pleasant by his discrimination and wisdom. Twice blessed is he who knows true love and can love all God's creatures. He who works selflessly for the welfare of others with love in his heart is thrice blessed. But the man who combines within his mortal frame knowledge, love and selfless service is holy and becomes a place of pilgrimage, like the confluence of the rivers Gangā, Saraswatī and Jamunā. Those who meet him become calm and purified.

Mind is the king of the senses. One who has conquered his mind, senses, passions, thought and reason is a king among men. He is fit for Rāja Yoga, the royal union with the Universal Spirit. He has Inner Light.

He who has conquered his mind is Rāja Yogi. The word rāja means a king. The expression Rāja Yoga implies a complete mastery of the Self. Though Patañjali explains the ways to control the mind, he nowhere states in his aphorisms that this science is Rāja Yoga, but calls it Aṣṭāṅga Yoga or the eight stages (limbs) of Yoga. As it implies complete mastery of the self one may call it the science of Rāja Yoga.

Sważtmàrâma, the author of the *Hatha Yoga Pradīpikā* (haṭha = force or determined effort) called the same path Haṭha Yoga because it demanded rigorous discipline.

It is generally believed that Rāja Yoga ànd Haṭha Yoga are entirely distinct, different and opposed to each other, that the *Yoga Sutras* of Patañjāli deal with Spiritual discipline and that the *Haṭha Yoga Pradīpikā* of Swātmārāma deals solely with physical discipline. It is not so, for

Haṭha Yoga and Rāja Yoga complement each other and form a single approach towards Liberation. As a mountaineer needs ladders, ropes and crampons as well as physical fitness and discipline to climb the icy peaks of the Himālayas, so does the Yoga aspirant need the knowledge and discipline of the Haṭha Yoga of Swātmārāma to reach the heights of Rāja Yoga dealt with by Patañjali.

This path of Yoga is the fountain for the other three paths. It brings calmness and tranquillity and prepares the mind for absolute unqualified self-surrender to God, in which all these four paths merge into one.

Chitta Vṛtti (*Causes for the Modification of the Mind*)

In his *Yoga Sutras* Patañjali lists five classes of chitta vṛtti which create pleasure and pain. These are:

1. Pramāṇa (a standard or ideal), by which things or values are measured by the mind or known, which men accept upon (a) direct evidence such as perception (pratyakṣa), (b) inference (anumāna) and (c) testimony or the word of an acceptable authority when the source of knowledge has been checked as reliable and trustworthy (āgama).

2. Viparyaya (a mistaken view which is observed to be such after study). A faulty medical diagnosis based on wrong hypotheses, or the formerly held theory in astronomy that the Sun rotates round the Earth, are examples of viparyaya.

3. Vikalpa (fancy or imagination, resting merely on verbal expression without any factual basis). A beggar may feel happy when he imagines himself spending millions. A rich miser, on the other hand, may starve himself in the belief that he is poor.

4. Nidrā (sleep), where there is the absence of ideas and experiences. When a man is sleeping soundly, he does not recall his name, family or status, his knowledge or wisdom, or even his own existence. When a man forgets himself in sleep, he wakes up refreshed. But, if a disturbing thought creeps into his mind when he is dropping off, he will not rest properly.

5. Smṛti (memory, the holding fast of the impressions of objects that one has experienced). There are people who live in their past experiences, even though the past is beyond recall. Their sad or happy memories keep them chained to the past and they cannot break their fetters.

Patañjali enumerates five causes of chitta vṛtti creating pain (kleśa). These are:

1. Avidyā (ignorance or nescience);
2. asmitā (the feeling of individuality which limits a person and distinguishes him from a group and which may be physical, mental, intellectual or emotional);
3. rāga (attachment or passion);
4. dveśa (aversion or revulsion);
5. abhiniveśa (love or thirst for life, the instinctive clinging to worldly life and bodily enjoyment and the fear that one may be cut off from all this by death).

These causes of pain remain submerged in the mind of the sādhaka (the aspirant or seeker). They are like icebergs barely showing their heads in the polar seas. So long as they are not studiously controlled and eradicated, there can be no peace. The yogi learns to forget the past and takes no thought for the morrow. He lives in the eternal present.

As a breeze ruffles the surface of a lake and distorts the images reflected therein, so also the chitta vṛtti disturb the peace of mind. The still waters of a lake reflect the beauty around it. When the mind is still, the beauty of the Self is seen reflected in it. The yogi stills his mind by constant study and by freeing himself from desires. The eight stages of Yoga teach him the way.

Chitta Viksepa (*Distractions and Obstacles*)

The distractions and obstacles which hinder the aspirant's practice of Yoga are:

1. Vyādhi – sickness which disturbs the physical equilibrium
2. Styāna – languor or lack of mental disposition for work
3. Saṁśaya – doubt or indecision
4. Pramāda – indifference or insensibility
5. Ālasya – laziness
6. Avirati – sensuality, the rousing of desire when sensory objects possess the mind
7. Bhrānti Darśana – false or invalid knowledge, or illusion
8. Alabdha Bhūmikatva – failure to attain continuity of thought or concentration so that reality cannot be seen
9. Anavasthitattva – instability in holding on to concentration which has been attained after long practice.

There are, however, four more distractions: (a) duḥkha – pain or misery, (b) daurmanasya – despair, (c) aṅgamejayatva – unsteadiness of the body and (d) śvāsa-praśvāsa – unsteady respiration.

To win a battle, a general surveys the terrain and the enemy and plans counter-measures. In a similar way the Yogi plans the conquest of the Self.

1. *Vyādhi.* It will be noticed that the very first obstacle is ill-health or sickness. To the yogi his body is the prime instrument of attainment. If his vehicle breaks down, the traveller cannot go far. If the body is broken by ill-health, the aspirant can achieve little. Physical health is important for mental development, as normally the mind functions through the nervous system. When the body is sick or the nervous system is affected, the mind becomes restless or dull and inert and concentration or meditation become impossible.

2. *Styāna.* A person suffering from languor has no goal, no path to follow and no enthusiasm. His mind and intellect become dull due to inactivity and their faculties rust. Constant flow keeps a mountain stream pure, but water in a ditch stagnates and nothing good can flourish in it. A listless person is like a living corpse for he can concentrate on nothing.

3. *Samśaya.* The unwise, the faithless and the doubter destroy themselves. How can they enjoy this world or the next or have any happiness? The seeker should have faith in himself and his master. He should have faith that God is ever by his side and that no evil can touch him. As faith springs up in the heart it dries out lust, ill-will, mental sloth, spiritual pride and doubt, and the heart free from these hindrances becomes serene and untroubled.

4. *Pramāda.* A person suffering from pramāda is full of self-importance, lacks any humility and believes that he alone is wise. No doubt he knows what is right or wrong, but he persists in his indifference to the right and chooses what is pleasant. To gratify his selfish passions and dreams of personal glory, he will deliberately and without scruple sacrifice everyone who stands in his way. Such a person is blind of God's glory and deaf to His words.

5. *Ālasya.* To remove the obstacle of laziness, unflagging enthusiasm (vīrya) is needed. The attitude of the aspirant is like that of a lover ever yearning to meet the beloved but never giving way to despair. Hope should be his shield and courage his sword. He should be free from hate and sorrow. With faith and enthusiasm he should overcome the inertia of the body and the mind.

6. *Avirati.* This is the tremendous craving for sensory objects after they have been consciously abandoned, which is so hard to restrain. Without being attached to the objects of sense, the yogi learns to enjoy them with the aid of the senses which are completely under his control. By the practice of pratyāhāra he wins freedom from attachment and emancipation from desire and becomes content and tranquil.

7. *Bhrānti Darśana.* A person afflicted by false knowledge suffers from delusion and believes that he alone has seen the true Light. He has a powerful intellect but lacks humility and makes a show of wisdom. By remaining in the company of great souls and through their guidance he sets his foot firmly on the right path and overcomes his weakness.

8. *Alabdha Bhūmikatva.* As a mountain climber fails to reach the summit for lack of stamina, so also a person who cannot overcome the inability to concentrate is unable to seek reality. He might have had glimpses of reality but he cannot see clearly. He is like a musician who has heard divine music in a dream, but who is unable to recall it in his waking moments and cannot repeat the dream.

9. *Anavasthitattva.* A person affected with anavasthitattva has by hard work come within sight of reality. Happy and proud of his achievements he becomes slack in his practice (sādhanā). He has purity and great power of concentration and has come to the final cross-roads of his quest. Even at this last stage continuous endeavour is essential and he has to pursue the path with infinite patience and determined perseverance and must never show slackness which hampers progress on the path of God realization. He must wait until divine grace descends upon him. It has been said in the *Kaṭhopanisad*: 'The Self is not to be realized by study and instruction, nor by subtlety of intellect, nor by much learning, but only by him who longs for Him, by the one whom He chooses. Verily to such a one the Self reveals His true being.

To overcome the obstacles and to win unalloyed happiness, Patañjali offered several remedies. The best of these is the fourfold remedy of Maitri (friendliness), Karuṇa (compassion), Muditā (delight) and Upekṣā (disregard).

1. Maitri is not merely friendliness, but also a feeling of oneness with the object of friendliness (ātmīyatā). A mother feels intense happiness at the success of her children because of ātmīyatā, a feeling of oneness. Patañjali recommends maitri for sukha (happiness or virtue). The yogi cultivates maitri and ātmīyatā for the good and turns enemies into friends, bearing malice towards none.

2. Karuṇa is not merely showing pity or compassion and shedding tears of despair at the misery (duḥkha) of others. It is compassion coupled with devoted action to relieve the misery of the afflicted. The yogi uses all his resources – physical, economic, mental or moral – to alleviate the pain and suffering of others. He shares his strength with the weak until they become strong. He shares his courage with those that are timid until they become brave by his example. He denies the maxim of the 'survival of the fittest', but makes the weak strong enough to survive. He becomes a shelter to one and all.

3. Muditā is a feeling of delight at the good work (punya) done by another, even though he may be a rival. Through muditā, the yogi saves himself from much heart-burning by not showing anger, hatred or jealousy for another who has reached the desired goal which he himself has failed to achieve.

4. Upekṣā: It is not merely a feeling of disdain or contempt for the person who has fallen into vice (apuṇya) or one of indifference or superiority towards him. It is a searching self-examination to find out how one would have behaved when faced with the same temptations. It is also an examination to see how far one is responsible for the state into which the unfortunate one has fallen and the attempt thereafter to put him on the right path. The yogi understands the faults of others by seeing and studying them first in himself. This self-study teaches him to be charitable to all.

The deeper significance of the fourfold remedy of maitri, karuṇa, muditā and upekṣā cannot be felt by an unquiet mind. My experience has led me to conclude that for an ordinary man or woman in any community of the world, the way to achieve a quiet mind is to work with determination on two of the eight stages of Yoga mentioned by Patañjali, namely, āsana and prāṇāyāma.

The mind (manas) and the breath (prāṇa) are intimately connected and the activity or the cessation of activity of one affects the other. Hence Patañjali recommended prāṇāyāma (rhythmic breath control) for achieving mental equipoise and inner peace.

Śiṣya and Guru (*A Pupil and a Master*)

The *Śiva Samhitā* divides sādhakas (pupils or aspirants) into four classes. They are (1) mṛdu (feeble), (2) madhyama (average), (3) adhimātra (superior) and (4) adhimātratama (the supreme one). The last, the highest, is alone able to cross beyond the ocean of the manifest world.

The feeble seekers are those who lack enthusiasm, criticize their teachers, are rapacious, inclined to bad action, eat much, are in the power of women, unstable, cowardly, ill, dependent, speak harshly, have weak characters and lack virility. The Guru (Teacher or Master) guides such seekers in the path of Mantra Yoga only. With much effort, the sādhaka can reach enlightenment in twelve years. (The word mantra is derived from the root 'man', meaning to think. Mantra thus means a sacred thought or prayer to be repeated with full understanding of its meaning. It takes a long time, perhaps years, for a mantra to take firm root in the mind of a feeble sādhaka and still longer for it to bear fruit.)

Of even mind, capable of bearing hardship, wishing to perfect the work, speaking gently, moderate in all circumstances, such is the average seeker. Recognizing these qualities, the Guru teaches him Laya Yoga, which gives liberation. (Laya means devotion, absorption or dissolution.)

Of stable mind, capable of Laya Yoga, virile, independent, noble, merciful, forgiving, truthful, brave, young, respectful, worshipping his teacher, intent on the practice of Yoga, such is a superior seeker. He can reach enlightenment after six years of practice. The Guru instructs this forceful man in Haṭha Yoga.

Of great virility and enthusiasm, good looking, courageous, learned in scriptures, studious, sane in mind, not melancholic, keeping young, regular in food, with his senses under control, free from fear, clean, skilful, generous, helpful to all, firm, intelligent, independent, forgiving, of good character, of gentle speech and worshipping his Guru, such is a supreme seeker, fit for all forms of Yoga. He can reach enlightenment in three years.

Although the *Śiva Samhitā* and the *Haṭha Yoga Pradīpikā* mention the period of time within which success might be achieved, Patañjali nowhere lays down the time required to unite the individual soul with the Divine Universal Soul. According to him abhyāsa (constant and determined practice) and vairāgya (freedom from desires) make the mind calm and tranquil. He defines abhyāsa as effort of long duration, without interruption, performed with devotion, which creates a firm foundation.

The study of Yoga is not like work for a diploma or a university degree by someone desiring favourable results in a stipulated time.

The obstacles, trials and tribulations in the path of Yoga can be removed to a large extent with the help of a Guru. (The syllable gu means darkness and ru means light. He alone is a Guru who removes darkness and brings enlightenment.) The conception of a Guru is deep and significant. He is not an ordinary guide. He is a spiritual teacher who teaches a way of life, and not merely how to earn a livelihood. He transmits knowledge of the Spirit and one who receives such knowledge is a śiṣya, a disciple.

The relationship between a Guru and a śiṣya is a very special one, transcending that between parent and child, husband and wife or friends. A Guru is free from egotism. He devotedly leads his śiṣya towards the ultimate goal without any attraction for fame or gain. He shows the path of God and watches the progress of his disciple, guiding him along that path. He inspires confidence, devotion, discipline, deep understanding and illumination through love. With faith in his pupil, the Guru strains hard to see that he absorbs the teaching. He encourages him to ask questions and to know the truth by question and analysis.

A śiṣya should possess the necessary qualifications of higher realization and development. He must have confidence, devotion and love for his Guru. The perfect examples of the relationship between a Guru and a śiṣya are those of Yama (the God of Death) and Nachiketā in the *Kaṭhopaniṣad* and of Śri Krishna and Arjuna in the *Bhagavad Gīta*. Nachiketā and Arjuna obtained enlightenment through their one-pointed mind, their eagerness and questioning spirit. The śiṣya should hunger for knowledge and have the spirit of humility, perseverance and tenacity of purpose. He should not go to the Guru merely out of curiosity. He should possess śraddhā (dynamic faith) and should not be discouraged if he cannot reach the goal in the time he had expected. It requires tremendous patience to calm the restless mind which is coloured by innumerable past experiences and saṁskāra (the accumulated residue of past thoughts and actions).

Merely listening to the words of the Guru does not enable the śiṣya to absorb the teaching. This is borne out by the story of Indra and Virochana. Indra, the king of Gods, and Virochana, a demon prince, went together to their spiritual preceptor Brahmā to obtain knowledge of the Supreme Self. Both stayed and listened to the same words of their Guru. Indra obtained enlightenment, whereas Virochana did not. Indra's memory was developed by his devotion to the subject taught by the love and faith which he had for his teacher. He had a feeling of oneness with his Guru. These were the reasons for his success. Virochana's memory was developed only through his intellect. He had no devotion either for the subject taught or for his preceptor. He remained what he originally was, an intellectual giant. He returned a doubter. Indra had intellectual humility, while Virochana had intellectual pride and imagined that it was condescending on his part to go to Brahmā. The approach of Indra was devotional while that of Virochana was practical. Virochana was motivated by curiosity and wanted the practical knowledge which he believed would be useful to him later to win power.

The śiṣya should above all treasure love, moderation and humility. Love begets courage, moderation creates abundance and humility generates power. Courage without love is brutish. Abundance without moderation leads to over-indulgence and decay. Power without humility breeds arrogance and tyranny. The true śiṣya learns from his Guru about a power which will never leave him as he returns to the Primeval One, the Source of His Being.

Sādhanā *(A Key to Freedom)*

All the important texts on Yoga lay great emphasis on sādhanā or abhyāsa (constant practice). Sādhanā is not just a theoretical study of Yoga texts. It is a spiritual endeavour. Oil seeds must be pressed to yield oil. Wood must be heated to ignite and bring out the hidden fire within. In the same way, the sādhaka must by constant practice light the divine flame within himself.

> 'The young, the old, the extremely aged, even the sick and the infirm obtain perfection in Yoga by constant practice. Success will follow him who practises, not him who practises not. Success in Yoga is not obtained by the mere theoretical reading of sacred texts. Success is not obtained by wearing the dress of a yogi or a sanyāsi (a recluse), nor by talking about it. Constant practice alone is the secret of success. Verily, there is no doubt of this.'
>
> *Haṭha Yoga Pradīpikā*, chapter 1, verses 64–6.

> 'As by learning the alphabet one can, through practice, master all the sciences, so by thoroughly practising first physical training one acquires the knowledge of Truth (Tattva Jñāna), that is the real nature of the human soul as being identical with the Supreme Spirit pervading the Universe.'
>
> *Gheraṇḍa Saṁhitā*, chapter 1, verse 5.

It is by the co-ordinated and concentrated efforts of his body, senses, mind, reason and Self that a man obtains the prize of inner peace and fulfils the quest of his soul to meet his Maker. The supreme adventure in a man's life is his journey back to his Creator. To reach the goal he needs well developed and co-ordinated functioning of his body, senses, mind, reason and Self. If the effort is not co-ordinated, he fails in his adventure. In the third valli (chapter) of the first part of the *Kaṭhopaniṣad*, Yama (the God of Death) explains this Yoga to the seeker Nachiketā by way of the parable of the individual in a chariot.

> 'Know the Ātman (Self) as the Lord in a chariot, reason as the charioteer and mind as the reins. The senses, they say, are the horses, and their objects of desire are the pastures. The Self, when united with the senses and the mind, the wise call the Enjoyer (Bhoktṛ). The undiscriminating can never rein in his mind; his senses are like the vicious horses of a charioteer. The discriminating ever controls his mind; his senses are like disciplined horses. The undiscriminating becomes unmindful, ever impure; he does not reach the goal, wandering from one body to another. The discriminating becomes mindful, ever pure; he reaches the goal and is never reborn. The man who has a discriminating charioteer to rein in his mind reaches the end of the journey – the Supreme Abode of the everlasting Spirit.
>
> 'The senses are more powerful than the objects of desire. Greater than the senses is the mind, higher than the mind is the reason

> and superior to reason is He – the Spirit in all. Discipline yourself by the Self and destroy your deceptive enemy in the shape of desire.'
>
> *Bhagavad Gītā*, chapter III, verses 42–3.

To realize this not only constant practice is demanded but also renunciation. As regards renunciation, the question arises as to what one should renounce. The yogi does not renounce the world, for that would mean renouncing the Creator. The yogi renounces all that takes him away from the Lord. He renounces his own desires, knowing that all inspiration and right action come from the Lord. He renounces those who oppose the work of the Lord, those who spread demonic ideas and who merely talk of moral values but do not practise them.

The yogi does not renounce action. He cuts the bonds that tie himself to his actions by dedicating their fruits either to the Lord or to humanity. He believes that it is his privilege to do his duty and that he has no right to the fruits of his actions.

While others are asleep when duty calls and wake up only to claim their rights, the yogi is fully awake to his duty, but asleep over his rights. Hence it is said that in the night of all beings the disciplined and tranquil man wakes to the light.

Aṣṭāṅga Yoga – The Eight Limbs of Yoga

The *Yoga Sutra* of Patañjali is divided into four chapters or pāda. The first deals with samādhi, the second with the means (sādhanā) to achieve Yoga, the third enumerates the powers (vibhūti) that the yogi comes across in his quest, and the fourth deals with absolution (kaivalya).

Yama

The eight limbs of Yoga are described in the second chapter. The first of these is yama (ethical disciplines) – the great commandments transcending creed, country, age and time. They are: ahimsā (non-violence), satya (truth), asteya (non-stealing), brahmacharya (continence) and aparigraha (non-coveting). These commandments are the rules of morality for society and the individual, which if not obeyed bring chaos, violence, untruth, stealing, dissipation and covetousness. The roots of these evils are the emotions of greed, desire and attachment, which may be mild, medium or excessive. They only bring pain and ignorance. Patañjali strikes at the root of these evils by changing the direction of one's thinking along the five principles of yama.

1. *Ahimsā*. The word ahimsā is made up of the particle 'a' meaning 'not' and the noun himsā meaning killing or violence. It is more than a negative command not to kill, for it has a wider positive meaning, love. This love embraces all creation for we are all children of the same Father – the Lord. The yogi believes that to kill or to destroy a thing or being is to insult its Creator. Men either kill for food or to protect themselves from danger. But merely because a man is a vegetarian, it does not necessarily follow that he is non-violent by temperament or that he is a yogi, though a vegetarian diet is a necessity for the practice of yoga. Bloodthirsty tyrants may be vegetarians, but violence is a state of mind, not of diet. It resides in a man's mind and not in the instrument he holds in his hand. One can use a knife to pare fruit or to stab an enemy. The fault is not in the instrument, but in the user.

Men take to violence to protect their own interests – their own bodies, their loved ones, their property or dignity. But a man cannot rely upon himself alone to protect himself or others. The belief that he can do so is wrong. A man must rely upon God, who is the source of all strength. Then he will fear no evil.

Violence arises out of fear, weakness, ignorance or restlessness. To curb it what is most needed is freedom from fear. To gain this freedom, what is required is a change of outlook on life and reorientation of the mind. Violence is bound to decline when men learn to base their faith upon reality and investigation rather than upon ignorance and supposition.

The yogi believes that every creature has as much right to live as he has. He believes that he is born to help others and he looks upon creation with eyes of love. He knows that his life is linked inextricably with that of others and he rejoices if he can help them to be happy. He puts the happiness of others before his own and becomes a source of joy to all who meet him. As parents encourage a baby to walk the first steps, he encourages those more unfortunate than himself and makes them fit for survival.

For a wrong done by others, men demand justice; while for that done by themselves they plead mercy and forgiveness. The yogi on the other hand, believes that for a wrong done by himself, there should be justice, while for that done by another there should be forgiveness. He knows and teaches others how to live. Always striving to perfect himself, he shows them by his love and compassion how to improve themselves.

The yogi opposes the evil in the wrong-doer, but not the wrong-doer. He prescribes penance not punishment for a wrong done. Opposition to evil and love for the wrong-doer can live side by side. A drunkard's wife whilst loving him may still oppose his habit. Opposition without love leads to violence; loving the wrong-doer without opposing the evil in him is folly and leads to misery. The yogi knows that to love a person whilst fighting the evil in him is the right course to follow. The battle is won because he fights it with love. A loving mother will sometimes beat her child to cure it of a bad habit; in the same way a true follower of ahimsā loves his opponent.

Along with ahimsā go abhaya (freedom from fear) and akrodha (freedom from anger). Freedom from fear comes only to those who lead a pure life. The yogi fears none and none need fear him, because he is purified by the study of the Self. Fear grips a man and paralyses him. He is afraid of the future, the unknown and the unseen. He is afraid that he may lose his means of livelihood, wealth or reputation. But the greatest fear is that of death. The yogi knows that he is different from his body, which is a temporary house for his spirit. He sees all beings in the Self and the Self in all beings and therefore he loses all fear. Though the body is subject to sickness, age, decay and death, the spirit remains unaffected. To the yogi death is the sauce that adds zest to life. He has dedicated his mind, his reason and his whole life to the Lord. When he has linked his entire being to the Lord, what shall he then fear?

There are two types of anger (krodha), one of which debases the mind while the other leads to spiritual growth. The root of the first is pride, which makes one angry when slighted. This prevents the mind from seeing things in perspective and makes one's judgement defective. The yogi, on the other hand, is angry with himself when his mind stoops low or when all his learning and experience fail to stop him from folly. He is stern with himself when he deals with his own faults, but gentle with the faults of others. Gentleness of mind is an attribute of a yogi, whose heart melts at all suffering. In him gentleness for others and firmness for himself go hand in hand, and in his presence all hostilities are given up.

2. *Satya.* Satya or truth is the highest rule of conduct or morality. Mahātma Gandhi said: 'Truth is God and God is Truth. As fire burns impurities and refines gold, so the fire of truth cleanses the yogi and burns up the dross in him.

If the mind thinks thoughts of truth, if the tongue speaks words of truth and if the whole life is based upon truth, then one becomes fit for union with the Infinite. Reality in its fundamental nature is love and truth and expresses itself through these two aspects. The yogi's life must conform strictly to these two facets of Reality. That is why ahimsā, which is essentially based on love, is enjoined. Satya presupposes perfect truthfulness in thought, word and deed. Untruthfulness in any form puts the sādhaka out of harmony with the fundamental law of truth.

Truth is not limited to speech alone. There are four sins of speech: abuse and obscenity, dealing in falsehoods, calumny or telling tales and lastly ridiculing what others hold to be sacred. The tale bearer is more poisonous than a snake. The control of speech leads to the rooting out of malice. When the mind bears malice towards none, it is filled with charity towards all. He who has learnt to control his tongue has attained self-control in a great measure. When such a person speaks he will be heard with respect and attention. His words will be remembered, for they will be good and true.

When one who is established in truth prays with a pure heart, then things he really needs come to him when they are really needed: he does not have to run after them. The man firmly established in truth gets the fruit of his actions without apparently doing anything. God, the source of all truth, supplies his needs and looks after his welfare.

3. *Asteya.* The desire to possess and enjoy what another has, drives a person to do evil deeds. From this desire spring the urge to steal and the urge to covet. Asteya (a = not, steya = stealing), or non-stealing includes not only taking what belongs to another without permission, but also using something for a different purpose to that intended, or beyond the time permitted by its owner. It thus includes misappropriation, breach of trust, mismanagement and misuse. The yogi reduces his physical needs to the minimum, believing that if he gathers things he does not really need, he is a thief. While other men crave for wealth, power, fame or enjoyment, the yogi has one craving and that is to adore the Lord. Freedom from craving enables one to ward off great temptations. Craving muddies the stream of tranquillity. It makes men base and vile and cripples them. He who obeys the commandment *Thou shalt not steal,* becomes a trusted repository of all treasures.

4. *Brahmacharya.* According to the dictionary brahmacharya means the life of celibacy, religious study and self-restraint. It is thought that the loss of semen leads to death and its retention to life. By the preservation of semen the yogi's body develops a sweet smell. So long as it is retained, there is no fear of death. Hence the injunction that it should be preserved by concentrated effort of the mind. The concept of brahmacharya is not one of negation, forced austerity and prohibition. According to Śankarāchārya, a brahmachārī (one who observes brahmacharya) is a man who is engrossed in the study of the sacred Vedic lore, constantly moves in Brahman and knows that all exists in Brahman. In other words, one who sees divinity in all is a brahmachārī. Patañjali, however, lays stress on continence of the body, speech and mind. This does not mean that the philosophy of Yoga is meant only for celibates. Brahmacharya has little to do with whether one is a bachelor or married and living the life of a householder. One has to develop the higher aspects of Brahmacharya in one's daily living. It is not necessary for

one's salvation to stay unmarried and without a house. On the contrary, all the smṛtīs (codes of law) recommend marriage. Without experiencing human love and happiness, it is not possible to know divine love. Almost all the yogis and sages of old in India were married men with families of their own. They did not shirk their social or moral responsibilities. Marriage and parenthood are no bar to the knowledge of divine love, happiness and union with the Supreme Soul.

Dealing with the position of an aspirant who is a householder, the *Śiva Saṁhitā* says: Let him practise free from the company of men in a retired place. For the sake of appearances, he should remain in society, but not have his heart in it. He should not renounce the duties of his profession, caste or rank; but let him perform these as an instrument of the Lord, without any thought of the results. He succeeds by following wisely the method of Yoga; there is no doubt of it. Remaining in the midst of the family, always doing the duties of the householder, he who is free from merits and demerits and has restrained his senses, attains salvation. The householder practising Yoga is not touched by virtue or vice: if to protect mankind he commits any sin, he is not polluted by it. (Chapter V, verses 234–8.)

When one is established in brahmacharya, one develops a fund of vitality and energy, a courageous mind and a powerful intellect so that one can fight any type of injustice. The brahmachārī will use the forces he generates wisely: he will utilize the physical ones for doing the work of the Lord, the mental for the spread of culture and the intellectual for the growth of spiritual life. Brahmacharya is the battery that sparks the torch of wisdom.

5. *Aparigraha.* Parigraha means hoarding or collecting. To be free from hoarding is aparigraha. It is thus but another facet of asteya (non-stealing). Just as one should not take things one does not really need, so one should not hoard or collect things one does not require immediately. Neither should one take anything without working for it or as a favour from another, for this indicates poverty of spirit. The yogi feels that the collection or hoarding of things implies a lack of faith in God and in himself to provide for his future. He keeps faith by keeping before him the image of the moon. During the dark half of the month, the moon rises late when most men are asleep and so do not appreciate its beauty. Its splendour wanes but it does not stray from its path and is indifferent to man's lack of appreciation. It has faith that it will be full again when it faces the Sun and then men will eagerly await its glorious rising.

By the observance of aparigraha, the yogi makes his life as simple as possible and trains his mind not to feel the loss or the lack of anything. Then everything he really needs will come to him by itself at the proper time. The life of an ordinary man is filled with an unending series of disturbances and frustrations and with his reactions to them. Thus there is hardly any possibility of keeping the mind in a state of equilibrium. The sādhaka has developed the capacity to remain satisfied with whatever happens to him. Thus he obtains the peace which takes him beyond the realms of illusion and misery with which our world is saturated. He recalls the promise given by Sri Krishna to Arjuna in the ninth chapter of the *Bhagavad Gītā*: 'To those who worship Me alone with single-minded devotion, who are in harmony with Me every moment, I bring full security. I shall supply all their wants and shall protect them for ever.'

Niyama

Niyama are the rules of conduct that apply to individual discipline, while yama are universal in their application. The five niyama listed by Patañjali are: saucha (purity), santoṣa (contentment), tapas (ardour or austerity), svādhyāya (study of the Self) and Iśvara praṇidhāna (dedication to the Lord).

1. *Śaucha*. Purity of blood is essential for well-being. While good habits like bathing purify the body externally, āsana and prāāyāma cleanse it internally. The practice of āsanas tones the entire body and removes the toxins and impurities caused by over-indulgence. Prāṇāyāma cleanses and aerates the lungs, oxygenates the blood and purifies the nerves. But more important than the physical cleansing of the body is the cleansing of the mind of its disturbing emotions like hatred, passion, anger, lust, greed, delusion and pride. Still more important is the cleansing of the intellect (buddhi) of impure thoughts. The impurities of the mind are washed off in the waters of bhakti (adoration). The impurities of the intellect or reason are burned off in the fire of svādhyāya (study of the Self). This internal cleansing gives radiance and joy. It brings benevolence (saumanasya) and banishes mental pain, dejection, sorrow and despair (daurmanasya). When one is benevolent, one sees the virtues in others and not merely their faults. The respect which one shows for another's virtues, makes him self-respecting as well and helps him to fight his own sorrows and difficulties. When the mind is lucid, it is easy to make it one-pointed (ekāgra). With concentration, one obtains mastery over the senses (indriyajaya). Then one is ready to enter the temple of his own body and see his real self in the mirror of his mind.

Besides purity of body, thought and word, pure food is also necessary. Apart from cleanliness in the preparation of food it is also necessary to observe purity in the means by which one procures it.

Food, the supporting yet consuming substance of all life, is regarded as a phase of Brahman. It should be eaten with the feeling that with each morsel one can gain strength to serve the Lord. Then food becomes pure. Whether or not to be a vegetarian is a purely personal matter as each person is influenced by the tradition and habits of the country in which he was born and bred. But, in course of time, the practitioner of yoga has to adopt a vegetarian diet, in order to attain one-pointed attention and spiritual evolution.

Food should be taken to promote health, strength, energy and life. It should be simple, nourishing, juicy and soothing. Avoid foods which are sour, bitter, pungent, burning, stale, tasteless, heavy and unclean.

Character is moulded by the type of food we take and by how we eat it. Men are the only creatures that eat when not hungry and generally live to eat rather than eat to live. If we eat for flavours of the tongue, we over-eat and so suffer from digestive disorders which throw our systems out of gear. The yogi believes in harmony, so he eats for the sake of sustenance only. He does not eat too much or too little. He looks upon his body as the rest-house of his spirit and guards himself against over-indulgence.

Besides food, the place is also important for spiritual practices. It is difficult to practise in a distant country (away from home), in a forest, in a crowded city, or where it is noisy. One should choose a place where food is easily procurable, a place which is free from insects, protected from the elements and with pleasing surroundings. The banks of a lake or river or the sea-shore are ideal. Such quiet ideal places are hard to find in modern times; but one can at least make a corner in one's room available for practice and keep it clean, airy, dry and pest-free.

2. *Santoṣa.* Santoṣa or contentment has to be cultivated. A mind that is not content cannot concentrate. The yogi feels the lack of nothing and so he is naturally content. Contentment gives bliss unsurpassed to the yogi. A contented man is complete for he has known the love of the Lord and has done his duty. He is blessed for he has known truth and joy.

Contentment and tranquillity are states of mind. Differences arise among men because of race, creed, wealth and learning. Differences create discord and there arise conscious or unconscious conflicts which distract and perplex one. Then the mind cannot become one-pointed (ekāgra) and is robbed of its peace. There is contentment and tranquillity when the flame of the spirit does not waver in the wind of desire. The sādhaka does not seek the empty peace of the dead, but the peace of one whose reason is firmly established in God.

3. *Tapas.* Tapas is derived from the root 'tap' meaning to blaze, burn, shine, suffer pain or consume by heat. It therefore means a burning effort under all circumstances to achieve a definite goal in life. It involves

purification, self-discipline and austerity. The whole science of character building may be regarded as a practice of tapas.

Tapas is the conscious effort to achieve ultimate union with the Divine and to burn up all desires which stand in the way of this goal. A worthy aim makes life illumined, pure and divine. Without such an aim, action and prayer have no value. Life without tapas, is like a heart without love. Without tapas, the mind cannot reach up to the Lord.

Tapas is of three types. It may relate to the body (kāyika), to speech (vāchika) or to mind (mānasika). Continence (brahmacharya) and non-violence (ahimsā) are tapas of the body. Using words which do not offend, reciting the glory of God, speaking the truth without regard for the consequences to oneself and not speaking ill of others are tapas of speech. Developing a mental attitude whereby one remains tranquil and balanced in joy and sorrow and retains self-control are tapas of the mind.

It is tapas when one works without any selfish motive or hope of reward and with an unshakable faith that not even a blade of grass can move without His will.

By tapas the yogi develops strength in body, mind and character. He gains courage and wisdom, integrity, straightforwardness and simplicity.

4. *Svādhyāya.* Sva means self and adhyāya means study or education. Education is the drawing out of the best that is within a person. Svādhyāya, therefore, is the education of the self.

Svādhyāya is different from mere instruction like attending a lecture where the lecturer parades his own learning before the ignorance of his audience. When people meet for svādhyāya, the speaker and listener are of one mind and have mutual love and respect. There is no sermonizing and one heart speaks to another. The ennobling thoughts that arise from svādhyāya are, so to speak, taken into one's bloodstream so that they become a part of one's life and being.

The person practising svādhyāya reads his own book of life, at the same time that he writes and revises it. There is a change in his outlook on life. He starts to realize that all creation is meant for bhakti (adoration) rather than for bhoga (enjoyment), that all creation is divine, that there is divinity within himself and that the energy which moves him is the same that moves the entire universe.

According to Śri Vinobā Bhāve (the leader of the Bhoodan movement), svādhyāya is the study of one subject which is the basis or root of all other subjects or actions, upon which the others rest, but which itself does not rest upon anything.

To make life healthy, happy and peaceful, it is essential to study regularly divine literature in a pure place. This study of the sacred books of the world will enable the sādhaka to concentrate upon and solve the difficult problems of life when they arise. It will put an end to ignorance and bring knowledge. Ignorance has no beginning, but it has an end. There is a beginning but no end to knowledge. By svādhyāya the sādhaka understands the nature of his soul and gains communion with the divine. The sacred books of the world are for all to read. They are not meant for the members of one particular faith alone. As bees savour the nectar in various flowers, so the sādhaka absorbs things in other faiths which will enable him to appreciate his own faith better.

Philology is not a language but the science of languages, the study of which will enable the student to learn his own language better. Similarly, Yoga is not a religion by itself. It is the science of religions, the study of which will enable a sādhaka the better to appreciate his own faith.

5. *Īśvara praṇidhāna.* Dedication to the Lord of one's actions and will is Īśvara praṇidhāna. He who has faith in God does not despair. He has illumination (tejas). He who knows that all creation belongs to the Lord will not be puffed up with pride or drunk with power. He will not stoop for selfish purposes; his head will bow only in worship. When the waters of bhakti (adoration) are made to flow through the turbines of the mind, the result is mental power and spiritual illumination. While mere physical strength without bhakti is lethal, mere adoration without strength of character is like an opiate. Addiction to pleasures destroys both power and glory. From the gratification of the senses as they run after pleasures arise moha (attachment) and lobha (greed) for their repetition. If the senses are not gratified, then, there is śoka (sorrow). They have to be curbed with knowledge and forbearance; but to control the mind is more difficult. After one has exhausted one's own resources and still not succeeded, one turns to the Lord for help for He is the source of all power. It is at this stage that bhakti begins. In bhakti, the mind, the intellect and the will are surrendered to the Lord and the sādhaka prays: 'I do not know what is good for me. Thy will be done.' Others pray to have their own desires gratified or accomplished. In bhakti or true love there is no place for 'I' and 'mine'. When the feeling of 'I' and 'mine' disappears, the individual soul has reached full growth.

When the mind has been emptied of desires of personal gratification, it should be filled with thoughts of the Lord. In a mind filled with thoughts of personal gratification, there is danger of the senses dragging the mind after the objects of desire. Attempts to practise bhakti without emptying the mind of desires is like building a fire with wet fuel. It makes a lot of smoke and brings tears to the eyes of the person who builds it and of those around him. A mind with desires does not ignite and glow, nor does it generate light and warmth when touched with the fire of knowledge.

The name of the Lord is like the Sun, dispelling all darkness. The moon is full when it faces the sun. The individual soul experiences fullness (pūrṇatā) when it faces the Lord. If the shadow of the earth comes between the full moon and the sun there is an eclipse. If the feeling of 'I' and 'mine' casts its shadow upon the experience of fullness, all efforts of the sādhaka to gain peace are futile.

Actions mirror a man's personality better than his words. The yogi has learnt the art of dedicating all his actions to the Lord and so they reflect the divinity within him.

Āsana

The third limb of yoga is āsana or posture. Āsana brings steadiness, health and lightness of limb. A steady and pleasant posture produces mental equilibrium and prevents fickleness of mind. Āsanas are not merely gymnastic exercises; they are postures. To perform them one needs a clean airy place, a blanket and determination, while for other systems of physical training one needs large playing fields and costly equipment. Āsanas can be done alone, as the limbs of the body provide the necessary weights and counter-weights. By practising them one develops agility, balance, endurance and great vitality.

Āsanas have been evolved over the centuries so as to exercise every muscle, nerve and gland in the body. They secure a fine physique, which is strong and elastic without being muscle-bound and they keep the body free from disease. They reduce fatigue and soothe the nerves. But their real importance lies in the way they train and discipline the mind.

Many actors, acrobats, athletes, dancers, musicians and sportsmen also possess superb physiques and have great control over the body, but they lack control over the mind, the intellect and the Self. Hence they are in disharmony with themselves and one rarely comes across a balanced personality among them. They often put the body above all else. Though the yogi does not underrate his body, he does not think merely of its perfection but of his senses, mind, intellect and soul.

The yogi conquers the body by the practice of āsanas and makes it a fit vehicle for the spirit. He knows that it is a necessary vehicle for the spirit. A soul without a body is like a bird deprived of its power to fly.

The yogi does not fear death, for time must take its toll of all flesh. He knows that the body is constantly changing and is affected by childhood, youth and old age. Birth and death are natural phenomena but the soul is not subject to birth and death. As a man casting off worn-out garments takes on new ones, so the dweller within the body casting aside worn-out bodies enters into others that are new.

The yogi believes that his body has been given to him by the Lord not for enjoyment alone, but also for the service of his fellow men during every wakeful moment of his life. He does not consider it his property. He knows that the Lord who has given him his body will one day take it away.

By performing āsanas, the sādhaka first gains health, which is not mere existence. It is not a commodity which can be purchased with money. It is an asset to be gained by sheer hard work. It is a state of complete equilibrium of body, mind and spirit. Forgetfulness of physical and mental consciousness is health. The yogi frees himself from physical disabilities and mental distractions by practising āsanas. He surrenders his actions and their fruits to the Lord in the service of the world.

The yogi realizes that his life and all its activities are part of the divine action in nature, manifesting and operating in the form of man. In the beating of his pulse and the rhythm of his respiration, he recognizes the flow of the seasons and the throbbing of universal life. His body is a temple which houses the Divine Spark. He feels that to neglect or to deny the needs of the body and to think of it as something not divine, is to neglect and deny the universal life of which it is a part. The needs of the body are the needs of the divine spirit which lives through the body. The yogi does not look heaven-ward to find God for he knows that He is within, being known as the Antarātmā (the Inner Self). He feels the kingdom of God within and without and finds that heaven lies in himself.

Where does the body end and the mind begin? Where does the mind end and the spirit begin? They cannot be divided as they are inter-related and but different aspects of the same all-pervading divine consciousness.

The yogi never neglects or mortifies the body or the mind, but cherishes both. To him the body is not an impediment to his spiritual liberation nor is it the cause of its fall, but is an instrument of attainment. He seeks a body strong as a thunderbolt, healthy and free from suffering so as to dedicate it in the service of the Lord for which it is intended. As pointed out in the *Muṇḍakopaniṣad* the Self cannot be attained by one without strength, nor through heedlessness, nor without an aim. Just as an unbaked earthen pot dissolves in water the body soon decays. So bake it hard in the fire of yogic discipline in order to strength and purify it.

The names of the āsanas are significant and illustrate the principle of evolution. Some are named after vegetation like the tree (vṛkṣa) and the lotus (padma); some after insects like the locust (śalabha) and the scorpion (vṛśchika); some after aquatic animals and amphibians like the fish (matsya), the tortoise (kūrma), the frog (bheka or maṇḍūka) or the crocodile (nakra). There are āsanas called after birds like the cock (kukkuṭa), the heron (baka), the peacock (mayūra) and the swan (haṁsa). They are also named after quadrupeds like the dog (śvāna), the horse (vātāyana), the camel (uṣṭra) and the lion (siṁha). Creatures that crawl like the serpent (bhujaṅga) are not forgotten, nor is the human embryonic state (garbha-pinda) overlooked. Āsanas are named after legendary heroes like Vīrabhadra and Hanumān, son of the Wind. Sages like Bharadvāja, Kapila, Vasiṣṭha and Viśvāmitra are remembered by having āsanas named after them. Some āsanas are also called after gods of the Hindu pantheon and some recall the Avatārās, or incarnations of Divine Power. Whilst performing āsanas the yogi's body assumes many forms resembling a variety of creatures. His mind is trained not to despise any creature, for he knows that throughout the whole gamut of creation, from the lowliest insect to the most perfect sage, there breathes the same Universal Spirit, which assumes innumerable forms. He knows that the highest form is that of the Formless. He finds unity in universality. True āsana is that in which the thought of Brahman flows effortlessly and incessantly through the mind of the sādhaka.

Dualities like gain and loss, victory and defeat, fame and shame, body and mind, mind and soul vanish through mastery of the āsanas, and the sādhaka then passes on to prāṇāyāma, the fourth stage in the path of yoga. In prāṇayāma practices the nostrils, nasal passages and membranes, the windpipe, the lungs and the diaphragm are the only parts of the body which are actively involved. These alone feel the full impact of the force of prāṇa, the breath of life. Therefore, do not seek to master prāṇāyāma in a hurry, as you are playing with life itself. By its improper practice respiratory diseases will arise and the nervous system will be shattered. By its proper practice one is freed from most diseases. Never attempt to practice prāṇāyāma alone by yourself. For it is essential to have the personal supervision of a Guru who knows the physical limitations of his pupil.

Prāṇāyāma

Just as the word yoga is one of wide import, so also is prāṇa. Prāṇa means breath, respiration, life, vitality, wind, energy or strength. It also connotes the soul as opposed to the body. The word is generally used in the plural to indicate vital breaths. Āyāma means length, expansion, stretching or restraint. Prāṇāyāma thus connotes extension of breath and its control. This control is over all the functions of breathing, namely, (1) inhalation or inspiration, which is termed pūraka (filling up); (2) exhalation or expiration, which is called rechaka (emptying the lungs), and (3) retention or holding the breath, a state where there is no inhalation or exhalation, which is termed kumbhaka. In Haṭha Yoga texts kumbhaka is also used in a loose generic sense to include all the three respiratory processes of inhalation, exhalation and retention.

A kumbha is a pitcher, water pot, jar or chalice. A water pot may be emptied of all air and filled completely with water, or it may be emptied of all water and filled completely with air. Similarly, there are two states of kumbhaka namely (1) when breathing is suspended after full inhalation (the lungs being completely filled with life-giving air), and (2) when breathing is suspended after full exhalation (the lungs being emptied of all noxious air). The first of these states, where breath is held after a full inhalation, but before exhalation begins, is known as antara kumbhaka. The second, where breath is held after a full exhalation, but before inhalation begins is known as bāhya kumbhaka. Antara means inner or interior, while bāhya means outer or exterior. Thus, kumbhaka is the interval or intermediate time between full inhalation and exhalation (antara kumbhaka) or between full exhalation and inhalation (bāhya kumbhaka). In both these types breathing is suspended and restrained.

Prāṇāyāma is thus the science of breath. It is the hub round which the wheel of life revolves. 'As lions, elephants and tigers are tamed very slowly and cautiously, so should prāṇa be brought under control very slowly in gradation measured according to one's capacity and physical limitations. Otherwise it will kill the practitioner,' warns the *Haṭha Yoga Pradīpikā* (chapter II, verse 16).

The yogi's life is not measured by the number of his days but by the number of his breaths. Therefore, he follows the proper rhythmic patterns of slow deep breathing. These rhythmic patterns strengthen the respiratory system, soothe the nervous system and reduce craving. As desires and cravings diminish, the mind is set free and becomes a fit vehicle for concentration. By improper practice of prāṇāyāma the pupil introduces several disorders into his system like hiccough, wind, asthma, cough, catarrh, pains in the head, eyes and ears and nervous irritation. It takes a long time to learn slow, deep, steady and proper inhalations and exhalations. Master this before attempting kumbhaka.

As a fire blazes brightly when the covering of ash over it is scattered by the wind, the divine fire within the body shines in all its majesty when the ashes of desire are scattered by the practice of prāṇāyāma.

'The emptying the mind of the whole of its illusion is the true rechaka (exhalation). The realization that "I am Ātmā (spirit)" is the true pūraka (inhalation). And the steady sustenance of the mind on this conviction is the true kumbhaka (retention). This is true prāṇāyāma,' says Śankarāchārya.

Every living creature unconsciously breathes the prayer 'So'ham' (Saḥ = He: Aham = Aham = I–He, the Immortal Spirit, am I) with each inward breath. So also with each outgoing breath each creature prays 'Haṁsaḥ' (I am He). This ajapa-mantra (unconscious repetitive prayer) goes on for ever within each living creature throughout life. The yogi fully realizes the significance of this ajapa-mantra and so is released from all the fetters that bind his soul. He offers up the very breath of his being to the Lord as sacrifice and receives the breath of life from the Lord as his blessing.

Prāṇa in the body of the individual (jīvātmā) is part of the cosmic breath of the Universal Spirit (Paramātmā). An attempt is made to harmonize the individual breath (piṇḍaprāṇa) with the cosmic breath (Brahmāṇḍa-prāṇa) through the practice of prāṇāyāma.

It has been said by Kariba Ekken, a seventeenth-century mystic: 'If you would foster a calm spirit, first regulate your breathing; for when that is under control, the heart will be at peace; but when breathing is spasmodic, then it will be troubled. Therefore, before attempting anything, first regulate your breathing on which your temper will be softened, your spirit calmed.'

The chitta (mind, reason and ego) is like a chariot yoked to a team of powerful horses. One of them is prāṇa (breath), the other is vāsanā (desire). The chariot moves in the direction of the more powerful animal. If breath prevails, the desires are controlled, the senses are held in check and the mind is stilled. If desire prevails, breath is in disarray and the mind is agitated and troubled. Therefore, the yogi masters the science of breath and by the regulation and control of breath, he controls the mind and stills its constant movement. In the practice of prāṇāyāma the eyes are kept shut to prevent the mind from wandering. 'When the prāṇa and the manas (mind) have been absorbed, an undefinable joy ensues.' (*Haṭha Yoga Pradīpikā*, chapter IV, verse 30.)

Emotional excitement affects the rate of breathing; equally, deliberate regulation of breathing checks emotional excitement. As the very object of Yoga is to control and still the mind, the yogi first learns prāṇāyāma to master the breath. This will enable him to control the senses and so reach the stage of pratyāhāra. Only then will the mind be ready for concentration (dhyāna).

The mind is said to be twofold – pure and impure. It is pure when it is completely free from desires and impure when it is in union with desires. By making the mind motionless and freeing it from sloth and distractions, one reaches the state of mindlessness (amanaska), which is the supreme state of samādhi. This state of mindlessness is not lunacy or idiocy but the conscious state of the mind when it is free from thoughts and desires. There is a vital difference between an idiot or a lunatic on the one hand, and a yogi striving to achieve a state of mindlessness on the other. The former is careless; the latter attempts to be carefree. It is the oneness of the breath and mind and so also of the senses and the abandonment of all conditions of existence and thought that is designated Yoga.

Prāṇa Vāyu. One of the most subtle forms of energy is air. This vital energy which also pervades the human body is classified in five main categories in the Haṭha Yoga texts according to the various functions performed by the energy. These are termed vāyu (wind) and the five main divisions are: prāṇa (here the generic term is used to designate the particular), which moves in the region of the heart and controls respiration; apāna, which moves in the sphere of the lower abdomen and controls the function of eliminating urine and faeces; samāna, which stokes the gastric fires to aid digestion; udāna, which dwells in the thoracic cavity and controls the intake of air and food; and vyāna, which pervades the entire body and distributes the energy derived from food and breath. There are also five subsidiary vāyūs. These are: nāga, which relieves abdominal pressure by belching; kūrma, which controls the movements of the eyelids to prevent foreign matter or too bright a light entering the eyes; kṛkara, which prevents substances passing up the nasal passages and down the throat by making one sneeze or cough; devadatta, which provides for the intake of extra oxygen in a tired body by causing a yawn, and lastly dhanaṁjaya, which remains in the body even after death and sometimes bloats up a corpse.

Pratyāhāra

If a man's reason succumbs to the pull of his senses he is lost. On the other hand, if there is rhythmic control of breath, the senses instead of running after external objects of desire turn inwards, and man is set free from their tyranny. This is the fifth stage of Yoga, namely, pratyāhāra, where the senses are brought under control.

When this stage is reached, the sādhaka goes through a searching self-examination. To overcome the deadly but attractive spell of sensual objects, he needs the insulation of adoration (bhakti) by recalling to his mind the Creator who made the objects of his desire. He also needs the lamp of knowledge of his divine heritage. The mind, in truth, is for mankind the cause of bondage and liberation; it brings bondage if it is bound to the objects of desire and liberation when it is free from objects. There is bondage when the mind craves, grieves or is unhappy over something. The mind becomes pure when all desires and fears are annihilated. Both the good and the pleasant present themselves to men and prompt them to action. The yogi prefers the good to the pleasant. Others driven by their desires, prefer the pleasant to the good and miss the very purpose of life. The yogi feels joy in what he is. He knows how to stop and, therefore, lives in peace. At first he prefers that which is bitter as poison, but he perseveres in his practice knowing well that in the end it will become as sweet as nectar. Others hankering for the union of their senses with the objects of their desires, prefer that which at first seems sweet as nectar, but do not know that in the end it will be as bitter as poison.

The yogi knows that the path towards satisfaction of the senses by sensual desires is broad, but that it leads to destruction and that there are many who follow it. The path of Yoga is like the sharp edge of a razor, narrow and difficult to tread, and there are few who find it. The yogi knows that the paths of ruin or of salvation lie within himself.

According to Hindu philosophy, consciousness manifests in three different qualities. For man, his life and his consciousness, together with the entire cosmos are the emanations of one and the same prakṛti (cosmic matter or substance) – emanations that differ in designation through the predominance of one of the guṇās. The guṇās (qualities or attributes) are:

1. Sattva (the illuminating, pure or good quality), which leads to clarity and mental serenity.
2. Rajas (the quality of mobility or activity), which makes a person active and energetic, tense and wilful, and
3. Tamas (the dark and restraining quality), which obstructs and counteracts the tendency of rajas to work and of sattva to reveal.

Tamas is a quality of delusion, obscurity, inertia and ignorance. A person in whom it predominates is inert and plunged in a state of torpor. The quality of sattva leads towards the divine and tamas towards the demonic, while in between these two stands rajas.

The faith held, the food consumed, the sacrifices performed, the austerities undergone and the gifts given by each individual vary in accordance with his predominating guṇa.

He that is born with tendencies towards the divine is fearless and pure. He is generous and self-controlled. He pursues the study of the Self. He is non-violent, truthful and free from anger. He renounces the fruits of his labour, working only for the sake of work. He has a tranquil mind, with malice towards none and charity towards all, for he is free from craving. He is gentle, modest and steady. He is illumined, clement and resolute, being free from perfidy and pride.

A man in whom rajō-guṇa predominates has inner thirst. As he is passionate and covetous, he hurts others. Being full of lust and hatred, envy and deceit, his desires are insatiable. He is unsteady, fickle and easily distracted as well as ambitious and acquisitive. He seeks the patronage of friends and has family pride. He shrinks from unpleasant things and clings to pleasant ones. His speech is sour and his stomach greedy.

He that is born with demonic tendencies is deceitful, insolent and conceited. He is full of wrath, cruelty and ignorance. In such people there is neither purity, nor right conduct, nor truth. They gratify their passions. Bewildered by numerous desires, caught in the web of delusion, these addicts of sensual pleasures fall into hell.

The working of the mind of persons with different predominating gunās may be illustrated by their different ways of approach towards a universal commandment like 'Thou shalt not covet.' A man in whom tamō-guṇa predominates might interpret it thus: 'others should not covet what is mine, no matter how I obtained it. If they do, I shall destroy them.' The rajō-guṇa type is a calculating self-interested person who would construe the commandment as meaning: 'I will not covet others' goods lest they covet mine.' He will follow the letter of the law as a matter of policy, but not the true spirit of the law as a matter of principle. A person of sattvika temperament will follow both the letter and the spirit of the precept as a matter of principle and not of policy, as a matter of eternal value. He will be righteous for the sake of righteousness alone, and not because there is a human law imposing punishment to keep him honest.

The yogi who is also human is affected by these three guṇās. By his constant and disciplined study (abhyāsa) of himself and of the objects which his senses tend to pursue, he learns which thoughts, words and actions are prompted by tamas and which by rajas. With unceasing effort he weeds out and eradicates such thoughts and he works to achieve a sattvika frame of mind. When the sattva-guṇa alone remains, the human soul has advanced a long way towards the ultimate goal.

Like unto the pull of gravity is the pull of the guṇās. As intensive research and rigorous discipline are needed to experience the wonder of weightlessness in space, so also a searching self-examination and the discipline furnished by Yoga is needed by a sādhaka to experience union with the Creator of space when he is freed from the pull of the guṇās.

Once the sādhaka has experienced the fullness of creation or of the Creator, his thirst (tṛṣṇā) for objects of sense vanishes and he looks at them ever after with dispassion (vairāgya). He experiences no disquiet in heat or cold, in pain or pleasure, in honour or dishonour and in virtue or vice. He treats the two imposters – triumph and disaster – with equanimity. He has emancipated himself from these pairs of opposites. He has passed beyond the pull of the guṇās and has become a guṇātīta (one who has transcended the guṇās). He is then free from birth and death, from pain and sorrow and becomes immortal. He has no self-identity as he lives experiencing the fullness of the Universal Soul. Such a man, scorning nothing, leads all things to the path of perfection.

Dhāranā

When the body has been tempered by āsanas, when the mind has been refined by the fire of prāṇāyāma and when the senses have been brought under control by pratyāhāra, the sādhaka reaches the sixth stage called dhāraṇā. Here he is concentrated wholly on a single point or on a task in which he is completely engrossed. The mind has to be stilled in order to achieve this state of complete absorption.

The mind is an instrument which classifies, judges and co-ordinates the impressions from the outside world and those that arise within oneself.

Mind is the product of thoughts which are difficult to restrain for they are subtle and fickle. A thought which is well guarded by a controlled mind brings happiness. To get the best out of an instrument, one must know how it works. The mind is the instrument for thinking and it is therefore necessary to consider how it functions. Mental states are classified in five groups. The first of these is the kṣipta state, where the mental forces are scattered, being in disarray and in a state of neglect. Here the mind hankers after objects, the ragō-guṇa being dominant. The second is the vikṣipta state, where the mind is agitated and distracted. Here there is a capacity to enjoy the fruits of one's efforts, but the desires are not marshalled and controlled. Then in the mūḍha state the mind is foolish, dull and stupid. It is confounded and at a loss to know what it wants and here the tamō-guṇa predominates. The fourth state of the mind is the ekāgra (eka = one; agra = foremost) state, where the mind is closely attentive and the mental faculties are concentrated on a single object or focussed on one point only, with the sattva-guṇa prevailing. The ekāgra person has superior intellectual powers and knows exactly what he wants, so he uses all his powers to achieve his purpose. At times the ruthless pursuit of the desired object, irrespective of the cost to others, can create great misery, and it often happens that even if the desired object is achieved it leaves behind a bitter taste.

Arjuna, the mighty bowman of the epic Mahābhārata, provides us with an example of what is meant by dhāraṇā. Once Drona, the preceptor of the royal princes, organized an archery contest to test their proficiency. They were called upon one by one to describe the target, which was pointed out to them. It was a nesting bird. Some princes described the grove of trees, others the particular tree or the bough on which the nest stood. When Arjuna's turn came, he described first the bird. Then he saw only its head, and lastly he could see nothing but the shining eye of the bird, which was the centre of the target chosen by Droṇa.

There is danger, however, of an ekāgra person becoming supremely egotistical. Where the senses start roaming unchecked, the mind follows suit. They cloud a man's judgement and set him adrift like a battered ship on a storm-tossed sea. A ship needs ballast to keep her on an even keel and the helmsman needs a star to steer her by. The ekāgra person needs bhakti (adoration of the Lord) and concentration on divinity to keep his mental equilibrium so that he goes on always in the right direction. He will not know happiness until the sense of 'I' and 'mine' disappears.

The last mental state is that of niruddha, where the mind (manas), intellect (buddhi) and ego (ahaṁkāra) are all restrained and all these faculties are offered to the Lord for His use and in His service. Here there is no feeling of 'I' and 'mine'. As a lens becomes more luminous when great light is thrown upon it and seems to be all light and undistinguishable from it, so also the sādhaka who has given up his mind, intellect and ego to the Lord, becomes one with Him, for the sādhaka thinks of nothing but Him, who is the creator of thought.

Without ekāgratā or concentration one can master nothing. Without concentration on Divinity, which shapes and controls the universe, one cannot unlock the divinity within oneself or become a universal man. To achieve this concentration, what is recommended is eka-tattva-abhyāsa or study of the single element that pervades all, the inmost Self of all beings, who converts His one form into many. The sādhaka, therefore, concentrates upon AUM, which is His symbol, to achieve ekāgratā.

Aum: According to Śri Vinobā Bhāve, the Latin word Omne and the Sanskrit word Aum are both derived from the same root meaning all and both words convey the concepts of omniscience, omnipresence and omnipotence. Another word for Aum is praṇava, which is derived from the root nu meaning to praise, to which is added the prefix pra denoting superiority. The word, therefore, means the best praise or the best prayer.

The symbol AUM is composed of three syllables, namely the letters A, U, M, and when written has a crescent and dot on its top. A few instances of the various interpretations given to it may be mentioned here to convey its meaning.

The letter A symbolizes the conscious or waking state (jāgrata-avasthā), the letter U the dream state (svapna-avasthā) and the letter M the dreamless sleep state (suṣupta-avasthā) of the mind and spirit. The entire symbol, together with the crescent and the dot, stands for the fourth state (turīya-avasthā), which combines all these states and transcends them. This is the state of samādhi.

The letters A, U and M symbolize respectively speech (vak), the mind (manas) and the breath of life (prāṇa), while the entire symbol stands for the living spirit, which is but a portion of the divine spirit.

The three letters also represent the dimensions of length, breadth and depth, while the entire symbol represents Divinity, which is beyond the limitations of shape and form.

The three letters A, U and M symbolize the absence of desire, fear and anger, while the whole symbol stands for the perfect man (a sthitaprajñā), one whose wisdom is firmly established in the divine.

They represent the three genders, masculine, feminine and neuter, while the entire symbol represents all creation together with the Creator.

They stand for the three guṇās or qualities of sattva, rajas and tamas, while the whole symbol represents a guṇātīta, one who has transcended and gone beyond the pull of the guṇās.

The letters correspond to the three tenses – past, present and future – while the entire symbol stands for the Creator, who transcends the limitations of time.

They also stand for the teaching imparted by the mother, the father and the Guru respectively. The entire symbol represents Brahma Vidyā, the knowledge of the Self, the teaching which is imperishable.

The A, U and M depict the three stages of yogic discipline, namely, āsana, prāṇāyāma and pratyāhāra. The entire symbol represents samādhi, the goal for which the three stages are the steps.

They represent the triad of Divinity, namely, Brahmā – the creator, Viṣṇu – the Maintainer, and Śiva – the Destroyer of the universe. The whole symbol is said to represent Brahman from which the universate emanates, has its growth and fruition and into which it merges in the end. It does not grow or change. Many change and pass, but Brahman is the One that ever remains unchanged.

The letters A, U and M also stand for the mantra 'Tat Twam Asi' ('That Thou Art'), the realization of man's divinity within himself. The entire symbol stands for this realization, which liberates the human spirit from the confines of his body, mind, intellect and ego.

After realizing the importance of AUM, the yogi focusses his attention on his beloved Deity adding AUM to the name of the Lord. The word AUM being too vast and too abstract, he unifies his senses, will, intellect, mind and reason by focussing on the name of the Lord and adding the word AUM with one pointed devotion and so experiences the feeling and meaning of the mantra.

The yogi recalls the verses of the *Muṇḍakopaniṣad*: 'Taking as a bow the great weapon of the Upaniṣad, one should put upon it an arrow sharpened by meditation. Stretching it with a thought directed to the essence of That, penetrate the Imperishable as the mark, my friend. The mystic syllable AUM is the bow. The arrow is the Self (Ātmā). Brahman is the target. By the undistracted man is It penetrated. One should come to be in It, as the arrow in the mark.'

Dhyāna

As water takes the shape of its container, the mind when it contemplates an object is transformed into the shape of that object. The mind which thinks of the all-pervading divinity which it worships, is ultimately through long-continued devotion transformed into the likeness of that divinity.

When oil is poured from one vessel to another, one can observe the steady constant flow. When the flow of concentration is uninterrupted, the state that arises is dhyāna (meditation). As the filament in an electric bulb glows and illumines when there is a regular uninterrupted current of electricity, the yogi's mind will be illumined by dhyāna. His body, breath, senses, mind, reason and ego are all integrated in the object of his contemplation – the Universal Spirit. He remains in a state of consciousness which has no qualification whatsoever. There is no other feeling except a state of SUPREME BLISS. Like a streak of lightning the yogi sees LIGHT that shines beyond the earth and the heavens. He sees the light that shines in his own heart. He becomes a light unto himself and others.

The signs of progress on the path of Yoga are health, a sense of physical lightness, steadiness, clearness of countenance and a beautiful voice, sweetness of odour of the body and freedom from craving. He has a balanced, serene and a tranquil mind. He is the very symbol of humility. He dedicates all his actions to the Lord and taking refuge in Him, frees himself from the bondage of karma (action) and becomes a Jīvana Mukta (a Liberated Soul).

'What becomes of him who strives and fails to reach the end of Yoga, who has faith, but whose mind wanders away from Yoga?' To this query of Arjuna, the Lord Śri Krishna replied:

> 'No evil can befall a righteous man. He dwells long years in the heaven of those who did good, and then he is reborn in the house of the pure and the great. He may even be born in a family of illumined yogis; but to be born in such a family is most difficult in this world. He will regain the wisdom attained in his former life and strives ever for perfection. Because of his former study, practice and struggle which drive him ever onwards, the yogi ever strives with a soul cleansed of sin, attains perfection through many lives and reaches the supreme goal. The yogi goes beyond those who only follow the path of austerity, knowledge or service. Therefore, Arjuna, be thou a yogi. The greatest of all yogis is he who adores Me with faith and whose heart abides in Me.'
>
> *Bhagavad Gītā*, chapter VI, verses 38 to 47.

Samādhi

Samādhi is the end of the sādhaka's quest. At the peak of his meditation, he passes into the state of samādhi, where his body and senses are at rest as if he is asleep, his faculties of mind and reason are alert as if he is awake, yet he has gone beyond consciousness. The person in a state of samādhi is fully conscious and alert.

All creation is Brahman. The sādhaka is tranquil and worships it as that from which he came forth, as that in which he breathes, as that into which he will be dissolved. The soul within the heart is smaller than the smallest seed, yet greater than the sky, containing all works, all desires. Into this the sādhaka enters. Then there remains no sense of 'I' or 'mine' as the working of the body, the mind and the intellect have stopped as if one is in deep sleep. The sādhaka has attained true Yoga; there is only the experience of consciousness, truth and unutterable joy. There is a peace that passeth all understanding. The mind cannot find words to describe the state and the tongue fails to utter them. Comparing the experience of samādhi with other experiences, the sages say: 'Neti! Neti!' – 'It is not this! It is not this!' The state can only be expressed by profound silence. The yogi has departed from the material world and is merged in the Eternal. There is then no duality between the knower and the known for they are merged like camphor and the flame.

There wells up from within the heart of the yogi the Song of the Soul, sung by Śankarāchārya in his *Ātma Ṣaṭkam.*

Song of the Soul

I am neither ego nor reason, I am neither mind nor thought,
I cannot be heard nor cast into words, nor by smell nor sight ever
caught:
In light and wind I am not found, nor yet in earth and sky –
Consciousness and joy incarnate, Bliss of the Blissful am I.

I have no name, I have no life. I breathe no vital air,
No elements have moulded me, no bodily sheath is my lair:
I have no speech, no hands and feet, nor means of evolution –
Consciousness and joy am I, and Bliss in dissolution.

I cast aside hatred and passion, I conquered delusion and greed;
No touch of pride caressed me, so envy never did breed:
Beyond all faiths, past reach of wealth, past freedom, past desire,
Consciousness and joy am I, and Bliss is my attire.

Virtue and vice, or pleasure and pain are not my heritage,
Nor sacred texts, nor offerings, nor prayer, nor pilgrimage:
I am neither food, nor eating, nor yet the eater am I –
Consciousness and joy incarnate, Bliss of the Blissful am I.

I have no misgiving of death, no chasms of race divide me,
No parent ever called me child, no bond of birth ever tied me:
I am neither disciple nor master, I have no kin, no friend –
Consciousness and joy am I, and merging in Bliss is my end.

Neither knowable, knowledge, nor knower am I, formless is my form,
I dwell within the senses but they are not my home:
Ever serenely balanced, I am neither free nor bound –
Consciousness and joy am I, and Bliss is where I am found.

PART II

Yogāsanas

HINTS AND CAUTIONS

THE REQUISITES

1. Without firm foundations a house cannot stand. Without the practice of the principles of yama and niyama, which lay down firm foundations for building character, there cannot be an integrated personality. Practice of āsanas without the backing of yama and niyama is mere acrobatics.

2. The qualities demanded from an aspirant are discipline, faith, tenacity, and perseverance to practice regularly without interruptions.

CLEANLINESS AND FOOD

3. Before starting to practise āsanas, the bladder should be emptied and the bowels evacuated. Topsy-turvy poses help bowel movements. If the student is constipated or it is not possible to evacuate the bowels before the practice of āsanas, start with Śīrṣāsana and Sarvāngāsana and their variations. Attempt other āsanas only after evacuation. Never practice advanced āsanas without having first evacuated the bowels.

BATH

4. Āsanas come easier after taking a bath. After doing them, the body feels sticky due to perspiration and it is desirable to bathe some fifteen minutes later. Taking a bath or a shower both before and after practising āsanas refreshes the body and mind.

FOOD

5. Āsanas should preferably be done on an empty stomach. If this is difficult, a cup of tea or coffee, cocoa or milk may be taken before doing them. They may be practised without discomfort one hour after a very light meal. Allow at least four hours to elapse after a heavy meal before starting the practice. Food may be taken half an hour after completing the āsanas.

TIME

6. The best time to practise is either early in the morning or late in the evening. In the morning āsanas do not come easily as the body is stiff.

The mind, however, is still fresh but its alertness and determination diminish as time goes by. The stiffness of the body is conquered by regular practice and one is able to do the āsanas as well. In the evening, the body moves more freely than in the mornings, and the āsanas come better and with greater ease. Practice in the morning makes one work better in one's vocation. In the evening it removes the fatigue of the day's strain and makes one fresh and calm. Do all the āsanas in the morning and stimulative āsanas (like Śīrṣāsana, Sarvāngāsana and their variations and Paśchimottānāsana) should be practised in the evening.

SUN

7. Do not practise āsanas after being out in the hot sun for several hours.

PLACE

8. They should be done in a clean airy place, free from insects and noise.

9. Do not do them on the bare floor or on an uneven place, but on a folded blanket laid on a level floor.

CAUTION

10. No undue strain should be felt in the facial muscles, ears and eyes or in breathing during the practice.

CLOSING OF THE EYES

11. In the beginning, keep the eyes open. Then you will know what you are doing and where you go wrong. If you shut your eyes you will not be able to watch the requisite movements of the body or even the direction in which you are doing the pose. You can keep your eyes closed only when you are perfect in a particular āsana for only then will you be able to adjust the bodily movements and feel the correct stretches.

MIRROR

12. If you are doing the āsanas in front of a mirror, keep it perpendicular to the floor and let it come down to ground level, for otherwise the poses will look slanting due to the angle of the mirror. You will not be able to observe the movements of placing the head and shoulders in the topsy-turvy poses unless the mirror reaches down to the floor. Use a mirror without a frame.

THE BRAIN

13. During the practice of āsanas, it is the body alone which should be active while the brain should remain passive, watchful and alert. If they are done with the brain, then you will not be able to see your own mistakes.

BREATHING

14. In all the āsanas, breathing should be done through the nostrils only and not through the mouth.

15. Do not restrain the breath while in the process of the āsana or while staying in it. Follow the instructions regarding breathing given in the technique sections of the various āsanas as described hereafter.

ŚAVĀSANA

16. After completing the practice of āsanas always lie down in Śavāsana for at least 10 to 15 minutes, as this will remove fatigue.

ASANAS AND PRĀṆĀYĀMA

17. Read carefully the hints and cautions for the practice of prāṇāyāma before attempting it (see Part III). Prāṇāyāma may be done either very early in the morning before the āsanas or in the evening after completing them. If early in the morning, prāṇāyāma may be done first for 15 to 30 minutes: then a few minutes of Śavāsana, and after allowing some time to elapse during which one may be engaged in normal activities, practise āsanas. If, however, these are done in the evening, allow at least half an hour to elapse before sitting for prāṇāyāma.

SPECIAL PROVISIONS FOR PERSONS SUFFERING FROM DIZZINESS OR BLOOD PRESSURE

18. Do not start with Śīrṣāsana and Sarvāṅgāsana if you suffer from dizziness or high blood pressure. First practise Paśchimottānāsana Uttānāsana, and Adho Mukha Śvānāsana before attempting topsy-turvy poses like Śīrṣāsana and Sarvāṅgāsana and after doing these poses repeat Paśchimottānāsana, Adho Mukha Śvānāsana and Uttānāsana in that order.

19. All forward bending poses are beneficial for persons suffering from either high or low blood pressure.

SPECIAL WARNING FOR PERSONS AFFECTED FROM PUS IN THE EARS OR DISPLACED RETINA

20. Those suffering from pus in the ears or displacement of the retina should not attempt topsy-turvy poses.

SPECIAL PROVISIONS FOR WOMEN

21. *Menstruation:* Avoid āsanas during the menstrual period. But if the flow is in excess of normal, Upaviṣṭha Koṇāsana, Baddha Koṇāsana, Vīrāsana, Jānu Śīrṣāsana, Paśchimottānāsana and Uttānāsana will be beneficial. On no account stand on your head nor perform sarvāngāsana, during the menstrual period.

22. *Pregnancy:* All the āsanas can be practised during the first three months of pregnancy. All the standing poses and the forward bending āsanas may be done with mild movements, for at this time the spine should be made strong and elastic and no pressure be felt on the abdomen. Baddha Koṇāsana and Upaviṣṭha Koṇāsana may be practised throughout pregnancy at any time of the day (even after meals, but not forward bending immediately after meals) as these two āsanas will strengthen the pelvic muscles and the small of the back and also reduce labour pains considerably. Prāṇāyāma without retention (kumbhaka) may be practised throughout pregnancy, as regular deep breathing will help considerably during labour.

23. *After delivery:* No āsanas should be done during the first month after delivery. Thereafter they may be practised mildly. Gradually increase the course as mentioned in the Appendix. Three months after delivery all āsanas may be practised with comfort.

EFFECTS OF ĀSANAS

24. Faulty practice causes discomfort and uneasiness within a few days. This is sufficient to show that one is going wrong. If you cannot find the fault yourself, it is better to approach a person who has practised well and get his guidance.

25. The right method of doing āsanas brings lightness and an exhilarating feeling in the body as well as in the mind and a feeling of oneness of body, mind and soul.

26. Continuous practice will change the outlook of the practiser. He will discipline himself in food, sex, cleanliness and character and will become a new man.

27. When one has mastered an āsana, it comes with effortless ease and causes no discomfort. The bodily movements become graceful. While performing āsanas, the student's body assumes numerous forms of life found in creation – from the lowliest insect to the most perfect sage – and he learns that in all these there breathes the same Universal Spirit – the Spirit of God. He looks within himself while practising and feels the presence of God in different āsanas which he does with a sense of surrender unto the feet of the LORD.

TECHNIQUE AND EFFECTS OF ĀSANAS

(After the name of each āsana, there is a number with an asterisk. These numbers before an asterisk indicate the intensity of the āsana; the lower the number, the easier the āsana, the higher the number, the more difficult the āsana.)

1| *Tāḍāsana*

(also called Samasthiti)

ONE*

Tāda means a mountain. Sama means upright, straight, unmoved. Sthiti is standing still, steadiness. Tāḍāsana therefore implies a pose where one stands firm and erect as a mountain. This is the basic standing pose.

TECHNIQUE

1. Stand erect with the feet together, the heels and big toes touching each other. Rest the heads of metatarsals on the floor and stretch all the toes flat on the floor.

2. Tighten the knees and pull the knee-caps up, contract the hips and pull up the muscles at the back of the thighs.

3. Keep the stomach in, chest forward, spine stretched up and the neck straight.

4. Do not bear the weight of the body either on the heels or the toes, but distribute it evenly on them both.

5. Ideally in Tāḍāsana the arms are stretched out over the head, but for the sake of convenience, one can place them by the side of the thighs. In this case, keep the arms parallel with the body. The fingers together and pointing downwards. Each of the standing poses described below can then be followed easily, starting with the pupil standing in Tāḍāsana with palms by the side of the thighs.

EFFECTS

People do not pay attention to the correct method of standing. Some stand with the body weight thrown only on one leg, or with one leg turned completely sideways. Others bear all the weight on the heels, or on the inner or outer edges of the feet. This can be noticed by watching where the soles and heels of the shoes wear out. Owing to our faulty method of standing and not distributing the body weight evenly on the feet, we acquire specific deformities which hamper spinal elasticity. Even if the feet are kept apart, it is better to keep the heel and toe in a line parallel to the median plane and not at an angle. By this method, the hips are contracted, the abdomen is pulled in and the chest is brought forward. One feels light in body and the mind acquires agility. If we stand with the body weight thrown only on the heels, we feel the centre of gravity changing; the hips become loose, the abdomen protrudes, the body hangs back and the spine feels the strain and consequently we soon feel fatigued and the mind becomes dull. It is therefore essential to master the art of standing correctly.



1

2| *Utthita Trikoṇāsana*

THREE*

Utthita means extended, stretched. Trikoṇa (tri = three; koṇa = angle) is a triangle. This standing āsana is the extended triangle pose.

TECHNIQUE

1. Stand in Tāḍāsana. (Plate 1)

2. Inhale deeply and with a jump spread apart the legs sideways 3 to 3½ feet. Raise the arms sideways, in line with the shoulders, palms facing down. Keep the arms parallel to the floor. (Plate 2)

3. Turn the right foot sideways 90 degrees to the right. Turn the left foot slightly to the right, keeping the left leg stretched from the inside and tightened at the knee.

4. Exhale, bend the trunk sideways to the right, bringing the right palm near the right angle. If possible, the right palm should rest completely on the floor. (Plates 3 and 4)

5. Stretch the left arm up (as in the illustration), bringing it in line with the right shoulder and extend the trunk. The back of the legs, the back of the chest and the hips should be in line. Gaze at the thumb of the outstretched left hand. Keep the right knee locked tight by pulling up the knee-cap and keep the right knee facing the toes.

6. Remain in this position from half a minute to a minute, breathing deeply and evenly. Then lift the right palm from the floor. Inhale and return to position 2 above.

7. Now, turn the left foot sideways 90 degrees to the left, turn the right foot slightly to the left, keep both knees tight and continue from position 2 to 6, reversing all processes. Inhale and come to position 2. Hold the posture for the same length of time on the left side.

8. Exhale, and jump, coming back to Tāḍāsana. (Plate 1)

EFFECTS

This āsana tones up the leg muscles, removes stiffness in the legs and hips, corrects any minor deformity in the legs and allows them to develop evenly. It relieves backaches and neck sprains, strengthens the ankles and develops the chest.



2



3



4

3| *Utthita Pārśvakoṇāsana*

FOUR*

Pārśva means side or flank. Koṇa is an angle. This is the extended lateral angle pose.

TECHNIQUE

1. Stand in Tāḍāsana. (Plate 1) Take a deep inhalation and with a jump spread the legs apart sideways 4 to 4½ feet. Raise the arms sideways, in line with the shoulders, palms facing down. (Plate 2)

2. While exhaling slowly, turn the right foot sideways 90 degrees to the right, and the left foot slightly to the right, keeping the left leg stretched out and tightened at the knee. Bend the right leg at the knee until the thigh and the calf form a right angle and the right thigh is parallel to the floor.

3. Place the right palm on the floor by the side of the right foot, the right armpit covering and touching the outer side of the right knee. Stretch the left arm out over the left ear. Keep the head up. (Plates 5 and 6)

4. Tighten the loins and stretch the hamstrings. The chest, the hips and the legs should be in a line and in order to achieve this, move the chest up and back. Stretch every part of the body, concentrating on the back portion of the whole body, specially the spine. Stretch the spine until all the vertebrae and ribs move and there is a feeling that even the skin is being stretched and pulled.


5


6

5. Remain in this pose from half a minute to a minute, breathing deeply and evenly. Inhale and lift the right palm from the floor.

6. Inhale, straighten the right leg and raise the arms as in position 1.

7. Continue with exhalation as in positions 2 to 5, reversing all processes, on the left side.

8. Exhale and jump back to Tāḍāsana. (Plate 1)

EFFECTS

This āsana tones up the ankles, knees and thighs. It corrects defects in the calves and thighs, develops the chest and reduces fat round the waist and hips and relieves sciatic and arthritic pains. It also increases peristaltic activity and aids elimination.

4| *Vīrabhadrāsana I*

THREE*

Dakṣa once celebrated a great sacrifice, but he did not invite his daughter Satī nor her husband Śiva, the chief of the gods. Satī, however, went to the sacrifice, but being greatly humiliated and insulted threw herself into the fire and perished. When Śiva heard this he was gravely provoked, tore a hair from his matted locks and threw it to the ground. A powerful hero named Vīrabhadra rose up and awaited his orders. He was told to lead Śiva's army against Dakṣa and destroy his sacrifice. Vīrabhadra and his army appeared in the midst of Dakṣa's assembly like a hurricane and destroyed the sacrifice, routed the other gods and priests and beheaded Dakṣa. Śiva in grief for Satī withdrew to Kailās and plunged into meditation. Satī was born again as Umā in the house of Himālaya. She strove once more for the love of Śiva and ultimately won his heart. The story is told by Kālidāsa in his great poem Kumāra saṁbhava *(The Birth of the War-Lord). This āsana is dedicated to the powerful hero created by Śiva from his matted hair.*



7



8



9

TECHNIQUE

1. Stand in Tāḍāsana. (Plate 1)

2. Raise both arms above the head; stretch up and join the palms. (Plate 7)

3. Take a deep inhalation and with a jump spread the legs apart sideways 4 to 4½ feet.

4. Exhale, turn to the right. Simultaneously turn the right foot 90 degrees to the right and the left foot slightly to the right. (Plate 8) Flex the right knee till the right thigh is parallel to the floor and the right shin perpendicular to the floor, forming a right angle between the right thigh and the right calf. The bent knee should not extend beyond the ankle, but should be in line with the heel.

5. Stretch out the left leg and tighten at the knee.

6. The face, chest and right knee should face the same way as the right foot, as illustrated. Throw the head up, stretch the spine from the coccyx and gaze at the joined palms. (Plate 9)

7. Hold the pose from 20 seconds to half a minute with normal breathing.

8. Repeat on the left side as in positions 4 to 6, reversing all processes.

9. Exhale and jump back to Tāḍāsana. (Plate 1)

All standing poses are strenuous, this pose in particular. It should not be tried by persons with a weak heart. Even people who are fairly strong should not stay long in this āsana.

EFFECTS

In this pose the chest is fully expanded and this helps deep breathing. It relieves stiffness in shoulders and back, tones up the ankles and knees and cures stiffness of the neck. It also reduces fat round the hips.



10

5| *Vīrabhadrāsana II*

ONE*

TECHNIQUE

1. Stand in Tāḍāsana. (Plate 1)

2. Take a deep inhalation, and with a jump spread the legs apart sideways 4 to 4½ feet. Raise the arms sideways in line with the shoulders, palms facing down. (Plate 2)

3. Turn the right foot sideways 90 degrees to the right and the left foot slightly to the right, keeping the left leg stretched out and tightened at the knee. Stretch the hamstring muscles of the left leg.

4. Exhale and bend the right knee till the right thigh is parallel to the floor, keeping the right shin perpendicular to the floor, thus forming a right angle between the right thigh and the right calf. The bent knee should not extend beyond the ankle, but should be in line with the heel. (Plate 10)

5. Stretch out the hands sideways, as though two persons are pulling you from opposite ends.

6. Turn the face to the right and gaze at the right palm. Stretch the back muscles of the left leg fully. The back of the legs, the dorsal region and the hips should be in one line.

7. Stay in the pose from 20 seconds to half a minute with deep breathing. Inhale and return to position 2.

8. Turn the left foot sideways 90 degrees to the left and the right foot slightly to the left, flex the left knee and continue from positions 3 to 6 on the left side, reversing all processes.

9. Inhale, again come back to position 2. Exhale and jump back to Tāḍāsana. (Plate 1)

EFFECTS

Through this pose the leg muscles become shapely and stronger. It relieves cramp in the calf and thigh muscles, brings elasticity to the leg and back muscles and also tones the abdominal organs.

Mastery of the standing poses prepares the pupil for the advanced poses in forward bending, which can then be acquired with ease.



11



12

6| *Pārśvōttānāsana*

SIX*

Pārśva means side or flank. Uttāna (ut = intense, and tān = to extend, stretch, lengthen) means an intense stretch. The name implies a pose in which the side of the chest is stretched intensely.

TECHNIQUE

1. Stand in Tāḍāsana. (Plate 1) Inhale deeply and stretch the body forward.

2. Join the palms behind the back and draw the shoulders and elbows back.

3. Exhale, turn the wrists and bring both palms up above the middle of the back of the chest, the fingers at the level of the shoulder-blades. You are doing 'namaste' (the Indian gesture of respect by folding the hands) with your hands behind your back. (Plate 11)

4. Inhale and with a jump spread the legs apart sideways 3 to 3½ feet. Stay in this position and exhale.

5. Inhale and turn the trunk to the right. Turn the right foot 90 degrees sideways to the right keeping the toes and heel in a line with the trunk; turn the left foot with the leg 75 to 80 degrees to the right and keep the left foot stretched out and the leg tightened at the knee. Throw the head back. (Plate 12)

6. Exhale, bend the trunk forward and rest the head on the right knee. Stretch the back and gradually extend the neck until the nose, then the lips and lastly the chin touch and then rest beyond the right knee. (Plate 13) Tighten both the legs by pulling the knee-caps up.

7. Stay in the pose from 20 seconds to half a minute with normal breathing. Then slowly move the head and trunk towards the left knee by swinging the trunk round the hips. At the same time turn the left foot 90 degrees towards the left and the right foot 75 to 80 degrees to the left. Now raise the trunk and head as far back as you can, without bending the right leg. This movement should be done with one inhalation.

8. Exhale, bend the trunk forward, rest the head on the left knee and gradually extend the chin beyond the left knee by stretching the neck as in position 6.

9. After holding the pose from 20 seconds to half a minute with normal breathing, inhale, move the head to the centre and the feet to their original position so that the toes point forward. Then raise the trunk up.

10. Exhale and jump back to Tāḍāsana (Plate 1), releasing the hands from the back.

11. If you cannot fold the hands together behind the back, just grip the right wrist and follow the above technique. (Plate 14)



13

EFFECTS

This āsana relieves stiffness in the legs and hip muscles and makes the hip joints and spine elastic. While the head is resting on the knees, the abdominal organs are contracted and toned. The wrists move freely and any stiffness there disappears. The posture also corrects round and drooping shoulders. In the correct pose, the shoulders are drawn well back and this makes deep breathing easier.



14

7| *Prasārita Pādottānāsana*

FOUR*

Prasārita means expanded, spread, extended. Pāda means a foot. The pose is one where the expanded legs are stretched intensely.

TECHNIQUE

1. Stand in Tāḍāsana. (Plate 1)

2. Inhale, place the hands on the waist and spread the legs apart 4½ to 5 feet. (Plate 15)

3. Tighten the legs by drawing up the knee-caps. Exhale, and place the palms on the floor in line with the shoulders between the feet. (Plate 16)

4. Inhale and raise the head up, keeping the back concave.



15



16

5. Exhale, bend the elbows and rest the crown of the head on the floor, keeping the weight of the body on the legs. (Plates 17 and 18) Do not throw the body weight on the head. Both feet, both palms and the head should be in a straight line.

6. Stay in the pose for half a minute, breathing deeply and evenly.

7. Inhale, raise the head from the floor and straighten the arms at the elbows. Keep the head well up by making the back concave as in position 4. (Plate 16)

8. Exhale and stand as in position 2. (Plate 15)

9. Jump back to Tāḍāsana. (Plate 1)

EFFECTS

In this pose the hamstring and abductor muscles are fully developed, while blood is made to flow to the trunk and the head. People who cannot do Sīrṣāsana (Plate 90) can benefit from this pose, which increases digestive powers.

All the standing poses described above are necessary for beginnings. As the pupil advances he attains better flexibility and then the standing poses can be dispensed with, though it is advisable to do them once a week. All these standing poses help to reduce the body weight.



17



18

8| *Uṣṭrāsana*

THREE*

Uṣṭra means a camel.

TECHNIQUE

1. Kneel on the floor, keeping the thighs and feet together, toes pointing back and resting on the floor.

2. Rest the palms on the hips. Stretch the thighs, curve the spine back and extend the ribs. (Plate 19)

3. Exhale, place the right palm over the right heel and the left palm over the left heel. If possible, place the palms on the soles of the feet.

4. Press the feet with the palms, throw the head back and push the spine towards the thighs, which should be kept perpendicular to the floor.

5. Contract the buttocks and stretch the dorsal and the coccyx regions of the spine still further, keeping the neck stretched back. (Plate 20)

6. Remain in this position for about half a minute with normal breathing.

7. Release the hands one by one and rest them on the hips. (Plate 19) Then sit on the floor and relax.

EFFECTS

People with drooping shoulders and hunched backs will benefit by this āsana.

The whole spine is stretched back and is toned. This pose can be tried conveniently by the elderly and even by persons with spinal injury.



19



20



21

9| *Pādānguṣṭhāsana*

THREE*

Pāda means the foot. Anguṣṭha is the big toe. This posture is done by standing and catching the big toes.

TECHNIQUE

1. Stand in Tāḍāsana. (Plate 1) Spread the legs a foot apart.

2. Exhale, bend forward and hold the big toes between the thumbs and the first two fingers, so that the palms face each other. Hold them tight. (Plate 21)

3. Keep the head up, stretch the diaphragm towards the chest and make the back as concave as possible. Instead of stretching down from the shoulders, bend forward from the pelvic region to get the concave shape of the back from the coccyx.

4. Keep the legs stiff and do not slacken the grip at the knees and toes. Stretch the shoulder-blades also. Take one or two breaths in this position.



22

5. Now exhale, and bring the head in between the knees by tightening and pulling the toes without lifting them off the floor. (Plate 22) Remain in this pose for about 20 seconds, maintaining normal breathing.

6. Inhale, come to position 2 (Plate 21), release the toes and stand up. Return to Tāḍāsana. (Plate 1)

10| *Pādahastāsana*

SIX*

Pāda means the foot. Hasta means the hand. This posture is done by bending forward and standing on one's hands.

TECHNIQUE

1. Stand in Tāḍāsana. (Plate 1) Spread the legs a foot apart.

2. Exhale, bend forward and without bending the legs at the knees insert the hands under the feet so that the palms touch the soles. (Plate 23)

3. Keep the head up and make the back as concave as possible. Do not slacken the grip at the knees and take a few breaths in this position.

4. Now exhale, and move the head in between the knees by bending the elbows and pulling the feet up from the palms. (Plate 24) Stay in the pose for about 20 seconds with normal breathing.

5. Inhale, raise the head and come back to position 2 (Plate 23), with the head well up. Take two breaths.

6. Inhale, stand up and return to Tāḍāsana. (Plate 1)



23



24

EFFECTS OF PĀDĀNGUṢṬHĀSANA AND PĀDAHASTĀSANA

The second āsana is more strenuous than the first, but the effects of both are the same. The abdominal organs are toned and digestive juices increase, while the liver and spleen are activated. Persons suffering from a bloating sensation in the abdomen or from gastric troubles will benefit from practising these two āsanas.

Slipped spinal discs can only be adjusted in the concave back position as in Plates 21 and 23. Do not bring the head in between the knees if you have a displaced disc. I have experimented with persons suffering from slipped discs and the concave back position proved a boon to them. It is imperative to get guidance from a guru (master) before trying this pose, because it may not be possible to achieve the concave back position immediately. One has to master other minor poses before attempting this one.

11| *Uttānāsana*

EIGHT*

Ut is a particle indicating deliberation, intensity. The verb tān means to stretch, extend, lengthen out. In this āsana, the spine is given a deliberate and an intense stretch.

TECHNIQUE

1. Stand in Tāḍāsana (Plate 1), keeping the knees tight.

2. Exhale, bend forward and place the fingers on the floor. Then place the palms on the floor by the side of the feet, behind the heels. Do not bend the legs at the knees.

3. Try to hold the head up and stretch the spine. Move the hips a little forward towards the head so as to bring the legs perpendicular to the floor.

4. Remain in this position and take two deep breaths.

5. Exhale, move the trunk closer to the legs and rest the head on the knees. (Plate 25)

6. Do not slacken the grip at the knees, but pull the knee-caps well up. Hold this position for a minute with deep and even breathing.

7. Inhale and raise the head from the knees, but without lifting the palms from the floor as in position 3.

8. After two breaths, take a deep inhalation, lift the hands from the floor and come back to Tāḍāsana. (Plate 1)



25

EFFECTS

This āsana cures stomach pains and tones the liver, the spleen and the kidneys. It also relieves stomach pain during menstrual periods. The heart beats are slowed down and the spinal nerves rejuvenated. Any depression felt in the mind is removed if one holds the pose for two minutes or more. The posture is a boon to people who get excited quickly, as it soothes the brain cells. After finishing the āsana, one feels calm and cool, the eyes start to glow and the mind feels at peace.

Persons who feel heaviness in the head, flushing or any discomfort while attempting Śīrṣāsana (Plate 90), should do Uttānāsana first; then they will be able to do Śīrṣāsana (the head stand) with comfort and ease.

12| Śalabhāsana

ONE*

Śalabhā means a locust. The pose resembles that of a locust resting on the ground, hence the name.

TECHNIQUE

1. Lie full length on the floor on the stomach, face downwards. Stretch the arms back.

2. Exhale, lift the head, chest and legs off the floor simultaneously as high as possible. The hands should not be placed and the ribs should not rest on the floor. Only the abdominal front portion of the body rests on the floor and bears the weight of the body. (Plate 26)

3. Contract the buttocks and stretch the thigh muscles. Keep both legs fully extended and straight, touching at the thighs, knees and ankles.

4. Do not bear the weight of the body on the hands but stretch them back to exercise the upper portion of the back muscles.

5. Stay in the position as long as you can with normal breathing.

6. In the beginning it is difficult to lift the chest and the legs off the floor, but this becomes easier as the abdominal muscles grow stronger.



26



27

EFFECTS

The pose aids digestion and relieves gastric troubles and flatulence. Since the spine is stretched back it becomes elastic and the pose relieves pain in the sacral and lumbar regions. In my experience, persons suffering from slipped discs have benefited by regular practice of this āsana without recourse to enforced rest or surgical treatment. The bladder and the prostate gland also benefit from the exercise and remain healthy.

A variation of the pose may also be tried to relieve aches in the lower part of the back. Here, the legs are bent at the knees and the thighs are kept apart while the shins are kept perpendicular to the floor. Then with an exhalation, the thighs are lifted off the floor and brought closer together until the knees touch, the shins still being kept perpendicular. (Plate 27)

13| *Dhanurāsana*

FOUR*

Dhanu means a bow. The hands here are used like a bowstring to pull the head, trunk and legs up and the posture resembles a bent bow.

TECHNIQUE

1. Lie full length on the floor on the stomach, face downwards.

2. Exhale and bend the knees. Stretch the arms back and hold the left ankle with the left hand and the right ankle with the right hand. Take two breaths.

3. Now exhale completely and pull the legs up by raising the knees above the floor, and simultaneously lift the chest off the floor. The arms and hands act like a bow-string to tauten the body like a bent bow. (Plate 28)



28

4. Lift up the head and pull it as far back as possible. Do not rest either the ribs or the pelvic bones on the floor. Only the abdomen bears the weight of the body on the floor.

5. While raising the legs do not join them at the knees, for then the legs will not be lifted high enough. After the full stretch upwards has been achieved, join together the thighs, the knees and the ankles.

6. Since the abdomen is extended, the breathing will be fast, but do not worry about it. Stay in the pose to your capacity from 20 seconds to one minute.

7. Then, with an exhalation, release the ankles, stretch the legs straight, bring the head and the legs back to the floor and relax.

EFFECTS

In this posture the spine is stretched back. Elderly people do not normally do this, so their spines get rigid. This āsana brings back elasticity to the spine and tones the abdominal organs. In my experience, persons suffering from slipped discs have obtained relief by the regular practice of Dhanurāsana and Śalabhāsana (Plate 26) without being forced to rest or to undergo surgical treatment.

14| *Chaturaṅga Daṇḍāsana*

ONE*

Chatur means four. Aṅga means a limb or a part thereof. Daṇḍa means a staff. Lie flat on the floor, face down and take the weight of the body on the palms and toes, exhale and keep the body parallel to the floor, stiff as a staff. The four limbs supporting the body are the hands and feet. The pose is similar to dips in western gymnastics.

TECHNIQUE

1. Lie flat on the floor, face downwards.

2. Bend the elbows and place the palms by the side of the chest. Keep the feet about a foot apart.



29



30

3. With an exhalation, raise the whole body a few inches above the floor, balancing it on the hands and the toes. (Plate 29) Keep the body stiff as a staff, parallel to the floor from head to heel and the knees taut. Stay for some time with normal breathing.

4. Then gradually extend the whole body forward so that the feet rest on the upper portion of the toes on the floor. (Plate 30)

5. Stay in the pose for about 30 seconds with normal or deep breathing. The movement may be repeated several times. Then relax on the floor.

EFFECTS

The pose strengthens the arms and the wrists develop mobility and power. It also contracts and tones the abdominal organs.

15| *Bhujaṅgāsana I*

ONE*

Bhujanga means a serpent. In this posture, lie flat on the floor, face downwards, lift the body up from the trunk and throw the head back like a serpent about to strike.

TECHNIQUE

1. Lie on the floor face downwards. Extend the legs, keeping the feet together. Keep the knees tight and the toes pointing.

2. Rest the palms by the side of the pelvic region.

3. Inhale, press the palms firmly on the floor and lift the body up from the trunk until the pubis is in contact with the floor and stay in this position with the weight on the legs and palms. (Plate 31)

4. Contract the anus and the buttocks, tighten the thighs.

5. Maintain the pose for about 20 seconds, breathing normally.

6. Exhale, bend the elbows and rest the trunk on the floor. Repeat the pose two or three times and then relax.

EFFECTS

The posture is a panacea for an injured spine and in cases of slight displacement of spinal discs the practice of this pose replaces the discs in their original position. The spinal region is toned and the chest fully expanded.



31

16| Ūrdhva Mukha Śvānāsana

ONE*

Ūrdhva Mukha means having the mouth upwards. Śvāna means a dog. The pose resembles a dog stretching itself with the head up in the air, hence the name.

TECHNIQUE

1. Lie on the floor on the stomach, face downwards.

2. Keep the feet about one foot apart. The toes should point straight back. Place the palms on the floor by the side of the waist, the fingers pointing to the head.

3. Inhale, raise the head and trunk, stretch the arms completely and push the head and trunk as far back as possible, without resting the knees on the floor.

4. Keep the legs straight and tightened at the knees, but do not rest the knees on the floor. The weight of the body rests on the palms and toes only. (Plate 32)



32

5. The spine, thighs and calves should be fully stretched, and the buttocks contracted tight. Push the chest forward, stretch the neck fully and throw the head as far back as possible. Stretch also the back portions of the arms.

6. Stay in the pose from half a minute to a minute with deep breathing.

7. Bend the elbows, release the stretch and rest on the floor.

EFFECTS

The pose rejuvenates the spine and is specially recommended for people suffering from a stiff back. The movement is good for persons with lumbago, sciatica and those suffering from slipped or prolapsed discs of the spine. The pose strengthens the spine and cures backaches. Due to chest expansion, the lungs gain elasticity. The blood circulates properly in the pelvic region and keeps it healthy.

17| Adho Mukha Śvānāsana

FIVE*

Adho Mukha means having the face downwards. Śvāna means a dog. The pose resembles a dog stretching itself with head and forelegs down and the hind legs up, hence the name.

TECHNIQUE

1. Lie full length on the floor on the stomach, face downwards. The feet should be kept one foot apart.

2. Rest the palms by the side of the chest, the fingers straight and pointing in the direction of the head.

3. Exhale and raise the trunk from the floor. Straighten the arms, move the head inwards towards the feet and place the crown of the head on the floor, keeping the elbows straight and extending the back. (Side view: Plate 33. Back view: Plate 34)

4. Keep the legs stiff and do not bend the knees but press the heels down. The heels and soles of the feet should rest completely on the floor, while the feet should be parallel to each other, the toes pointing straight ahead.

5. Stay in the pose for about a minute with deep breathing. Then with an exhalation lift the head off the floor, stretch the trunk forward and lower the body gently to the floor and relax.



33

EFFECTS

When one is exhausted, a longer stay in this pose removes fatigue and brings back the lost energy. The pose is especially good for runners who get tired after a hard race. Sprinters will develop speed and lightness in the legs. The pose relieves pain and stiffness in the heels and helps to soften calcaneal spurs. It strengthens the ankles and makes the legs shapely. The practice of this āsana helps to eradicate stiffness in the region of the shoulder-blades, and arthritis of the shoulder joints is relieved. The abdominal muscles are drawn towards the spine and strengthened. As the diaphragm is lifted to the chest cavity the rate of the heart beat is slowed down. This is an exhilarating pose.

Those who are afraid to do Śīrṣāsana (Plate 90) can conveniently practise this position. As the trunk is lowered in this āsana it is fully stretched and healthy blood is brought to this region without any strain on the heart. It rejuvenates the brain cells and invigorates the brain by relieving fatigue.

Persons suffering from high blood pressure can do this pose.



34

18| *Daṇḍāsana*

TWO*

Daṇḍa means a staff or rod.

TECHNIQUE

Sit on the floor with the legs stretched in front. Place the palms on the floor by the hips, the fingers pointing to the feet. Stretch the hands straight and keep the back erect. (Plate 35)



35

19| *Paripūrṇa Nāvāsana*

TWO*

Paripūrṇa means entire or complete. The posture here resembles that of a boat with oars, hence the name.

TECHNIQUE

1. Sit on the floor as in Daṇḍāsana (18 above).

2. Exhale, recline the trunk slightly back and simultaneously raise the legs from the floor and keep them stiff as a poker with the knees tight and the toes pointing forwards. Balance is maintained only on the buttocks and no part of the spine should be allowed to touch the floor, from which the legs should be kept at an angle of 60 to 65 degrees. The feet are higher than the head and not level with it as in Ardha Nāvāsana. (Plate 37)

3. Remove the hands from the floor and stretch the arms forward, keeping them parallel to the floor and near the thighs. The shoulders and the palms should be on one level, and the palms should face each other. (Plate 36)

4. Stay in the pose for half a minute, with normal breathing. Gradually increase the time to one minute. One feels the effect of the exercise after only 20 seconds.

5. Then exhale, lower the hands, rest the legs on the floor and relax by lying on the back.



36



37

EFFECTS

This āsana gives relief to persons who feel a bloating sensation in the abdomen due to gas and also to those suffering from gastric complaints. It reduces fat around the waistline and tones the kidneys.

20| Ardha Nāvāsana

TWO*

Ardha means half. Nāva is a ship, boat or vessel. This posture resembles the shape of a boat, hence the name.

TECHNIQUE

1. Sit on the floor. Stretch the legs out in front and keep them straight. (Plate 35)

2. Interlock the fingers and place them on the back of the head just above the neck.

3. Exhale, recline the trunk back and simultaneously raise the legs from the floor, keeping the thighs and knees tight and the toes pointed. The balance of the body rests on the buttocks and no part of the spine should be allowed to touch the floor. (Plate 37) One feels the grip on the muscles of the abdomen and the lower back.

4. Keep the legs at an angle of about 30 to 35 degrees from the floor and the crown of the head in line with the toes.

5. Hold this pose for 20 to 30 seconds with normal breathing. A stay for one minute in this posture indicates strong abdominal muscles.

6. Do not hold the breath during this āsana, though the tendency is always to do it with suspension of breath after inhalation. If the breath is held, the effect will be felt on the stomach muscles and not on the abdominal organs. Deep inhalation in this āsana would loose the grip on the abdominal muscles. In order to maintain this grip, inhale, exhale and hold the breath and go on repeating this process but without breathing deeply. This will exercise not only the abdominal muscles but the organs also.

7. The difference between Ardha Nāvāsana and Paripūrṇa Nāvāsana should be noted; in the latter, the legs are moved higher and the distance between them and the stomach is less than in the former.

EFFECTS

The effects of Ardha Nāvāsana and that of Paripūrṇa Nāvāsana (Plate 36) differ due to the position of the legs. In Paripūrṇa Nāvāsana the exercise is effective on the intestines; whereas, Ardha Nāvāsana works on the liver, gall bladder and spleen.

In the beginning, the back is too weak to bear the strain of the pose. When power to retain this pose comes, it indicates that the back is gaining strength. A weak back is a handicap in many ways, especially to women as they need strong backs for child-bearing. These two āsanas coupled with lateral twistings of the spine will help to strengthen the back.

The importance of having a healthy lower back can be realized if we watch old people when they sit down, get up and walk, for consciously or unconsciously they support their backs with their hands. This indicates that the back is weak and cannot withstand the strain. As long as it is strong and needs no support, one feels young though advanced in age. The two āsanas bring life and vigour to the back and enable us to grow old gracefully and comfortably.

21| *Siddhāsana*

ONE*

Siddha means a semi-divine being supposed to be of great purity and holiness, and to possess supernatural faculties called siddhis. Siddha means also an inspired sage, seer or prophet.

'The Siddhas say that as among niyamas, the most important is not to harm anyone, and among the yamas a moderate diet, so is Siddhāsana among the āsanas.'

'Of the 84 lacs of āsanas, one should always practise Siddhāsana. It purifies 72,000 nāḍīs. (Nāḍīs are channels in the human body through which nervous energy passes.)

'The yogin practising contemplation upon Ātman and observing a moderate diet, if he practises Siddhāsana for twelve years, obtains the yoga siddhis.' (Ātman means the Self and the supreme Soul. Siddhīs are supernatural faculties.)

'When Siddhāsana is mastered, the Unmanī Avasthā (Samādhi) that gives delight follows without effort and naturally.'

The soul has three avasthās or conditions which are included in a fourth. They are waking, dreaming, sleeping and what is called Turīya.

'The first condition is that of wakefulness, where the self is conscious of the common world of gross objects. It enjoys gross things. Here the dependence of body is predominant. The second condition is that of dreaming, where the self enjoys subtle things, fashioning for itself a new world of forms from the material of its waking experience. The spirit is said to roam freely unfettered by the bonds of the body. The third condition is that of sound sleep, where we have neither dreams nor desires. It is called suṣupti. In it the soul is said to become temporarily one with Brahman and to enjoy bliss. In deep sleep we are lifted above all desires and freed from the vexations of spirit. . . . The soul is divine in origin, though clogged with the flesh. In sleep it is said to be released from the shackles of the body and to regain its own nature. . . . But this (that is, the eternal dreamless sleep) is likely to be confused with sheer unconsciousness. . . . The highest is not this dreamless sleep, but another, a fourth state of the soul, a pure intuitional consciousness where there is no knowledge of objects internal or external. In deep sleep the spirit dwells in a region far above the changeful life of sense in absolute union with Brahman. The turīya condition brings out the positive aspect of the negative emphasized in the condition of deep sleep.'

Radhakrishnan in Philosophy of the Upanishads.

This fourth condition has been thus described in the Māṇḍūkya Upanishad as follows:

'The fourth, say the wise, is not subjective experience, nor objective experience, nor experience intermediate between the two, nor is it a negative condition which is neither consciousness nor unconsciousness. It is not the knowledge of the senses, nor is it relative knowledge, nor yet inferential knowledge. Beyond the senses, beyond understanding, beyond all expression, is the fourth. It is pure unitary consciousness, wherein all awareness of the world and of multiplicity is completely obliterated. It is the supreme good. It is One without a second. It is the Self. Know it alone!'

'Rāja-Yoga, Samādhi, Unmanī, Manomanī, Immortality, Concentration, Śūnyāśūnya (void and yet non-void), Parama Pāda (the Supreme State), Amanaska (suspended operation of the mind), Advaita (non-duality), Nirālamba (without support), Nirañjana (pure), Jīvanmukti (emancipated state), Sahajāvasthā (natural state) and Turīyā (literally the Fourth), all mean the same thing. As a grain of salt thrown into water unites and becomes one with it, a like union between the Mind and the Ātman is Samādhi. When Praṇa and Manas (mind) are annihilated (absorbed), the state of harmony then arising is called Samādhi.'

Haṭha Yoga Pradīpikā, *chapter IV, verses 3 to 6.*

There is no āsana like Siddha, no kumbhaka like Kevala, no mudrā like Khecharī, and no laya (absorption of the mind) like Nāda.

(Khecharī Mudrā, literally roaming through space, is described in the Gheranda Saṁhitā *as follows in verses 25 to 28 of the third chapter:*

'Cut the lower tendon of the tongue and move the tongue constantly; rub it with fresh butter, and draw it out (to lengthen it) with an iron instrument. By practising this always, the tongue becomes long and when it reaches the space between the eyebrows, then Khecharī is accomplished. Then (the tongue being lengthened) practise turning it up and back so as to touch the palate, till at

length it reaches the holes of the nostrils opening into the mouth. Close those holes with the tongue (thus stopping inspiration), and gaze on the space between the eyebrows. This is called Khecharī. By this practice there is neither fainting, nor hunger, nor thirst, nor laziness. There comes neither disease, nor decay, nor death. The body becomes divine.')

(Nāda is the inner mystical sound. Verses 79 to 101 of the fourth chapter describes it in great detail with a variety of similes. Yoga is defined as control over the aberrations of the mind. In order to control the mind it is necessary that it should first be absorbed in concentration of some object, then it is gradually withdrawn from that object and made to look within one's own self. This is where the yogi is asked to concentrate upon the inner mystical sounds. 'The mind is like a serpent, forgetting all its unsteadiness by hearing Nāda, it does not run away anywhere.' Gradually as Nāda becomes latent so does the mind along with it. 'The fire, catching the wood, is extinguished along with it (after burning it up); and so the mind also, working with Nāda, becomes latent along with it.')

TECHNIQUE

1. Sit on the floor, with legs stretched straight in front. (Plate 35)

2. Bend the left leg at the knee. Hold the left foot with the hands, place the heel near the perineum and rest the sole of the left foot against the right thigh.



38

3. Now bend the right leg at the knee and place the right foot over the left ankle, keeping the right heel against the pubic bone.

4. Place the sole of the right foot between the thigh and the calf of the left leg.

5. Do not rest the body on the heels.

6. Stretch the arms in front and rest the back of the hands on the knees so that the palms face upwards. Join the thumbs and the forefingers and keep the other fingers extended. (Plate 38).

7. Hold this position as long as you can, keeping the back, neck and head erect and the vision indrawn as if gazing at the tip of the nose.

8. Release the feet and relax for some time. Then repeat the pose for the same length of time, now placing the right heel near the perineum first and then the left foot over the right ankle as described above.

EFFECTS

This posture keeps the pubic region healthy. Like Padmāsana (Plate 53), it is one of the most relaxing of āsanas. The body being in a sitting posture is at rest, while the position of the crossed legs and erect back keeps the mind attentive and alert. This āsana is also recommended for the practice of prāṇāyāma and for meditation.

From the purely physical point of view, the āsana is good for curing stiffness in the knees and ankles. In it the blood circulates in the lumbar region and the abdomen, and this tones the lower region of the spine and the abdominal organs.



39



40

22| *Vīrāsana*

ONE*

Vīra means a hero, warrior, champion. This sitting posture is done by keeping the knees together, spreading the feet and resting them by the side of the hips.

The pose is good for meditation and prāṇāyāma.

TECHNIQUE

1. Kneel on the floor. Keep the knees together and spread the feet about 18 inches apart.

2. Rest the buttocks on the floor, but not the body on the feet. The feet are kept by the side of the thighs, the inner side of each calf touching the outer side of its respective thigh. Keep the toes pointing back and touching the floor. Keep the wrists on the knees, palms facing up, and join the tips of the thumbs and forefingers. Keep the other fingers extended. Stretch the back erect. (Back view: Plate 42. Front view: Plate 43)

3. Stay in this position as long as you can, with deep breathing.

4. Now interlock the fingers and stretch the arm straight over the head, palms up. (Plate 44)

5. Stay in this position for a minute with deep breathing.

6. Exhale, release the fingerlock, place the palms on the soles, bend forward and rest the chin on the knees. (Plate 45)

7. Stay in this position for a minute with normal breathing.

8. Inhale, raise the trunk up, bring the feet forward and relax.

9. If you find it difficult to perform the pose as described above, try placing the feet one above the other and rest the buttocks on them. (Plate 39) Gradually move the toes further apart, separate the feet (Plates 40 and 41) and bring them to rest outside the thighs. Then, in time the buttocks will rest properly on the floor and the body will not rest on the feet.

EFFECTS

The pose cures rheumatic pains in the knees and gout, and is also good for flat feet. Due to the stretching of the ankles and the feet, proper arches will be formed. This, however, takes a long time and requires daily practice of the pose for a few minutes for several months. Those suffering from pain in the heels or growth of calcaneal spurs there will get relief and the spurs will gradually disappear.

The pose can even be done immediately after food and will relieve heaviness in the stomach.



41



42



43



44

45



23| *Supta Vīrāsana*

TWO*

Supta means lying down. In this āsana one reclines back on the floor and stretches the arms behind the head.

TECHNIQUE

1. Sit in Vīrāsana. (Plate 43)

2. Exhale, recline the trunk back and rest the elbows one by one on the floor. (Plate 46)

3. Relieve the pressure on the elbows one after the other by extending the arms.

4. At first rest the crown of the head on the floor. (Plate 47) Gradually rest the back of the head and then the back on the floor. (Plate 48) Take the arms over the head and stretch them out straight. (Plate 49) Hold this pose as long as you can while breathing deeply. Then place the arms beside the trunk, press the elbows to the floor and sit up again with an exhalation.

5. The hands may be stretched over the head or placed beside the thighs. When they are stretched over the head, do not raise the shoulder-blades from the floor.

6. Beginners may keep the knees apart.


46


47


48


49

EFFECTS

This āsana stretches the abdominal organs and the pelvic region. People whose legs ache will get relief from holding this pose for 10 to 15 minutes and it is recommended to athletes and all who have to walk or stand about for long hours. It can be done after meals and if before retiring at night the legs feel rested next morning. Several of my pupils who were cadets at the National Defence Academy after long route marches found great relief by combining this āsana with Sarvāngāsana I. (Plate 102)

24| *Baddha Koṇāsana*

THREE*

Baddha means caught, restrained. Koṇa means an angle. In this posture, sit on the floor, bring the heels near the perineum, catch the feet and widen the thighs until the knees touch the floor on either side. This is how Indian cobblers sit.

TECHNIQUE

1. Sit on the floor with the legs stretched straight in front. (Plate 35)

2. Bend the knees and bring the feet closer to the trunk.

3. Bring the soles and heels of the feet together and catching the feet near the toes, bring the heels near the perineum. The outer sides of both feet should rest on the floor, and the back of the heels should touch the perineum.

50





51

4. Widen the thighs and lower the knees until they touch the floor.

5. Interlock the fingers of the hands, grip the feet firmly, stretch the spine erect and gaze straight ahead or at the tip of the nose. (Plate 50) Hold the pose as long as you can.

6. Place the elbows on the thighs and press them down. Exhale, bend forward, rest the head, then the nose and lastly the chin on the floor. (Plate 51) Hold this position from half a minute to a minute with normal breathing.

7. Inhale, raise the trunk from the floor and come back to position 5. (Plate 50)

8. Then release the feet, straighten the legs and relax.



52

EFFECTS

The pose is specially recommended for those suffering from urinary disorders. The pelvis, the abdomen and the back get a plentiful supply of blood and are stimulated. It keeps the kidneys, the prostate and the urinary bladder healthy. It is well known that diseases of the urinary tract are rarely found among the Indian cobblers and the reason for that is that they sit all day in this pose.

It relieves sciatic pain and prevents hernia. If practised regularly, it relieves pain and heaviness in the testicles.

The pose is a blessing to women. Coupled with Sarvāngāsana I (Plate 102) and its cycle (Plates 113 to 125) it checks irregular menstrual periods and helps the ovaries to function properly. It is found that pregnant women who sit daily in this pose for a few minutes will have much less pain during delivery and will be free from varicose veins. (It is recommended for pregnant women in Dr Grantly Dick Reed's book *Childbirth Without Fear*.)

Along with Padmāsana (Plate 53) and Vīrasana (Plate 43) this āsana is recommended for Prāṇāyāma practice and for meditation. When sitting in meditation in this pose the palms should be folded in front of the chest (Plate 52), but to do this with the back erect requires practice. This asana can be done without fear even after meals as long as the head is not rested on the floor.

25 *Padmasana*

FOUR*

Padma means a lotus. This is the lotus posture, one of the most important and useful āsanas. It is the posture for meditation and the Buddha is often depicted in it.

Verse 48 of the first chapter of the Hatha Yoga Pradīpikā *describes the posture and the practice of breath control while seated in it thus:*

'Assuming Padmasana and having placed the palms one upon another, fix the chin firmly upon the breast and contemplating upon Brahman, frequently contract the anus and raise the apana up; by similar contraction of the throat force the prana down. By this he obtains unequalled knowledge through the favour of Kundalinī (which is roused by this process).'

Kundalini is the Divine Cosmic Energy in bodies. It is symbolized by a coiled and sleeping serpent in the lowest bodily centre at the base of the spinal column. This latent energy has to be awakened and made to go up the spine to the brain through Suṣumnā Naḍi, a channel through which nervous energy passes, and through the six chakras, the subtle centres in the body, the fly-wheels in the nervous system of the human machine. The awakening of Kundalini is discussed in detail in Arthur Avalon's (Sir John Woodroffe's) book entitled The Serpent Power.

This is one of the basic postures and is often used in the variations of Śirṣāsana and Sarvangāsana.

TECHNIQUE

1. Sit on the floor with the legs straight. (Plate 35)

2. Bend the right leg at the knee, hold the right foot with the hands and place it at the root of the left thigh so that the right heel is near the navel.

3. Now bend the left leg, and holding the left foot with the hands place it over the right at the root, the heel being near the navel. The soles of the feet should be turned up. This is the basic Padmāsana pose. (Plate 53)

4. People not used to sitting on the floor seldom have flexible knees. At the start they will feel excruciating pain around the knees. By perseverance and continued practice the pain will gradually subside and they can then stay in the pose comfortably for a long time.

5. From the base to the neck the spine should remain erect. The arms may be stretched out, the right hand being placed on the right knee and the left hand on the left knee. The forefingers and the thumbs are bent and touch each other.

6. Change the leg position by placing the left foot over the right thigh and the right foot over the left thigh. This will develop the legs evenly.



53

EFFECTS

After the initial knee pains have been overcome, Padmāsana is one of the most relaxing poses. The body being in a sitting posture, it is at rest without being sloppy. The position of the crossed legs and the erect back keeps the mind attentive and alert. Hence it is one of the āsanas recommended for practising prāṇāyāma (breath control).

On the purely physical level, the pose is good for curing stiffness in the knees and ankles. Since the blood is made to circulate in the lumbar region and the abdomen, the spine and the abdominal organs are toned.

26| *Parvatāsana*

FOUR*

Parvata means a mountain. In this variation of Padmāsana the arms are stretched over the head with the fingers interlocked.

TECHNIQUE

1. Sit in Padmāsana. (Plate 53)

2. Interlock the fingers, and stretch the hands vertically up over the head. Keep the head bent forward with the chin on the breast bone.

3. Stretch the arms up from the latissimus dorsi (near the floating ribs at the back) and the shoulder-blades. The palms should face upwards. (Plate 54)

4. Hold the pose for a minute or two with deep and even breathing. Change the crossing of the legs and the interlock of the fingers and repeat the pose, keeping the back erect.

EFFECTS

The āsana relieves rheumatic pains and stiffness in the shoulders. It helps draw free movement and to develop the chest. The abdominal organs are drawn in and the chest expands fully.



54

27| *Matsyāsana*

FIVE*

Matsya means a fish. This posture is dedicated to Matsya the Fish Incarnation of Viṣṇu, the source and maintainer of the universe and of all things. It is related that once upon a time the whole earth had become corrupt and was about to be overwhelmed by a universal flood. Viṣṇu took the form of a fish and warned Manu (the Hindu Adam) of the impending disaster. The fish then carried Manu, his family and the seven great sages in a ship, fastened to a horn on his head. It also saved the Vedas from the flood.

TECHNIQUE

1. Sit in Padmāsana. (Plate 53)

2. Lie flat on the back with the legs on the floor.

3. Exhale, arch the back by lifting the neck and the chest, take the head back and rest the crown on the floor. Drag the head further back by holding the crossed legs with the hands and increase the back arch. (Plate 55)

4. Now take the hands from the legs, bend the arms, hold the elbows with the hands and rest the forearms on the floor behind the head. (Plate 56)

5. Stay in this position from 30 to 60 seconds while breathing deeply.

6. Rest the back of the head on the floor, lie flat on the back, inhale and then come up to Padmāsana, release the legs and relax.

7. Recross the legs the other way and repeat the pose for the same length of time.

8. If positions 3 and 4 are difficult to achieve, lie flat on the back with the arms stretched straight over the head. (Plate 57)

EFFECTS

The dorsal region is fully extended in this posture and the chest is well expanded. Breathing becomes fuller. The thyroids benefit from the exercise due to the stretching of the neck. The pelvic joints become elastic. The āsana relieves inflamed and bleeding piles.



55



56



57

28| *Baddha Padmāsana*

SIX*

Baddha means caught, restrained. In this position the hands are crossed at the back and the big toes are caught from behind. The body is caught between the crossed legs in front and the crossed hands behind, hence the name.

TECHNIQUE

1. Sit in Padmāsana. (Plate 53)

2. Exhale, swing the left arm back from the shoulders and bring the hand near the right hip. Catch the left big toe, hold the position and inhale.

3. Similarly, with an exhalation, swing the right arm back from the shoulder, bring it near the left hip and catch the right big toe. (Front view: Plate 58. Back view: Plate 59)

4. If the toes are difficult to catch stretch the shoulders back, so that the shoulder-blades are brought near each other. A little practice in swinging the arms back with an exhalation will enable one to catch the big toes.

5. If the right foot is placed over the left thigh and then the left foot over the right thigh, catch the left big toe first and then the right big toe. If, on the other hand, the left foot is placed over the right thigh first and then the right foot over the left thigh, catch the right big toe first and then the left big toe. Catch first the big toe of the foot which is uppermost.



58



59

6. Throw the head as far back as possible and take a few deep breaths.

7. Inhale deeply, and then with an exhalation bend the trunk forward from the hips and rest the head on the floor, without releasing the toes from the hand grip. Bending the head forward in Baddha Padmāsana (Plate 58) and touching it on the floor is called:

29| *Yoga Mudrāsana*

SIX*

This āsana is especially useful in awakening Kuṇḍalinī.

EFFECTS

Crossing the hands behind the back expands the chest and increases the range of shoulder movement. Yoga Mudrāsana (Plate 60) intensifies the peristaltic activity and pushes down the accumulated waste matter in the colon and thereby relieves constipation and increases digestive power.

30| *Mahā Mudrā*

FIVE*

Mahā means great or noble. Mudrā means shutting, closing or sealing. In this sitting posture the apertures at the top and bottom of the trunk are held fast and sealed.

TECHNIQUE

1. Sit on the floor with the legs stretched in front. (Plate 35)

2. Bend the left knee and move it to the left, keeping the outer side of the left thigh and the left calf on the floor.

3. Place the left heel against the inner side of the left thigh near the perineum. The big toe of the left foot should touch the inner side of the right thigh. The angle between the extended right leg and the bent left leg should be a right angle of 90 degrees.



60

4. Stretch the arms forward towards the right foot and hook the big toe with the thumbs and forefingers.

5. Lower the head to the trunk until the chin rests in the hollow between the collar bones just above the breast-bone.

6. Keep the spine fully stretched and do not allow the right leg to tilt to the right.

7. Inhale completely. Tighten the entire abdomen from the anus to the diaphragm. Pull the abdomen back towards the spine and also up towards the diaphragm.

8. Relax the abdominal tension, then exhale, again inhale and hold the breath, maintaining the abdominal grip. Hold this posture as stated above from one to three minutes. (Plate 61)

9. Relax the abdominal tension, exhale, raise the head, release the hands and straighten the bent leg.

10. Repeat on the other side, keeping the left leg straight and the right one bent for an equal length of time.



61

EFFECTS

This āsana tones the abdominal organs, the kidneys and adrenal glands. Women suffering from a prolapsed womb find relief as it pulls the womb up to its original position. Persons suffering from spleen ailments and from enlargement of the prostate gland will benefit by staying in this pose longer. It cures indigestion.

'This Mahāmudrā destroys death and many other pains. 'There is nothing that one cannot eat or has to avoid (if one has practised it). All food regardless of taste and even when deadly poisonous is digested.' 'He who practices Mahāmudrā, overcomes consumption, leprosy, piles, enlargement of the spleen, indigestion and other complaints of long duration.' (*Haṭha Yoga Pradīpikā*, chapter 3, verses 14, 16 and 17.)

31| *Jānu Śīrṣāsana*

FIVE*

Jānu means the knee. Śīrṣa is the head. In this posture sit with one leg stretched out on the ground and the other bent at the knee. Then catch the extended foot with both the hands and place the head on that knee.



62



63

TECHNIQUE

1. Sit on the floor, with legs stretched straight in front. (Plate 35)

2. Bend the left knee and move it to the left, keeping the outer side of left thigh and the left calf on the floor.

3. Place the left heel against the inner side of the left thigh near the perineum. The big toe of the left foot should touch the inner side of the right thigh. The angle between the two legs should be obtuse. Do not keep the left knee in line with the left thigh at a right angle to the extended right leg. Try and push the left knee as far back as possible, so that the body is stretched from the bent leg.

4. Extend the arms forward towards the right foot and hold it with the hands. First catch the toes of the right foot, then gradually catch the sole, then the heel and finally extend the arms and catch the wrist of one hand with the other, beyond the outstretched foot. (Plate 62)

5. Keep the right leg stretched throughout by tightening the knee. See that the back of the right knee rests on the floor.

6. Exhale, move the trunk forward by bending and widening the elbows, and rest first the forehead, then the nose, then the lips and lastly the chin beyond the right knee. (Plate 63) The right foot will tilt to the right in the beginning. Do not allow the leg to tilt.

7. Stretch the back fully, pull the trunk forward and keep the chest against the right thigh.

8. Stay in this position with deep breathing from half a minute to a minute. One can also do the pose holding the breath after each exhalation.

9. Inhale, raise the head and trunk, straighten the arms and gaze up for a few seconds, extending the spine and trying to make it concave. (Plate 62)

10. Release the hand grip on the right foot, straighten the left leg and come back to position 1.

11. Repeat the pose keeping the left leg stretched out and bending the right leg at the knee. Stay in the pose for the same length of time on both the sides.

EFFECTS

This āsana tones the liver and the spleen and thereby aids digestion. It also tones and activates the kidneys, the effect on which can be felt while one is performing the pose as explained above.

Persons suffering from enlargement of the prostate gland will benefit by staying longer in this pose. They should practice this āsana along with Sarvāngāsana. (Plate 102)

The pose is also recommended for people suffering from low fever for a long time.

32| *Ardha Baddha Padma Paschimottānāsana*

EIGHT*

Ardha means half, baddha means caught, restrained and padma a lotus. Paschimottānāsana (Plate 81) is the posture where the back of the whole body is intensely stretched.

TECHNIQUE

1. Sit on the floor, with the legs stretched straight in front. (Plate 35)

2. Bend the left leg at the knee, and place the left foot over the right thigh. The left heel should press the navel and the toes should be stretched and pointing. This is the half lotus posture.



64



65

3. Bring the left arm round the back from behind and with an exhalation catch the big toe of the left foot. If the toe cannot be grasped easily, swing back the left shoulder.

4. After holding the left big toe, move the bent left knee nearer to the extended right leg. Stretch the right arm forward and catch the right foot with the right hand, the palm touching the sole. (Plates 64 and 65)



66



67

5. Inhale, stretch the back and gaze up for a few seconds, without releasing the grip on the left big toe.

6. Exhale, move the trunk forward by bending the right elbow outwards. Rest the forehead, then the nose, then the lips and lastly the chin on the right knee. (Plate 66)

7. In the initial stages, the knee of the extended leg will be lifted off the floor. Tighten the thigh muscles and rest the entire back of the extended right leg on the floor.

8. Stay in this position from 30 to 60 seconds, breathing evenly.

9. Inhale, raise the head and trunk, release the hands, straighten the left leg and come to position 1.

10. Repeat the pose on the other side, keeping the left leg stretched out on the ground, bending the right knee and placing the right foot on the left thigh. Stay for the same length of time on both sides.

11. If you cannot hold the toe with the hand from behind, hold the extended leg with both hands and follow the above techniques. (Plate 67)

EFFECTS

Due to the half lotus pose, the knees become flexible enough to execute the full lotus pose. While placing the chin on the knee of the extended leg, the bent knee is brought close to the stretched leg. This gives a good pull to the navel and abdominal organs. Blood is made to flow round the navel and the genital organs. The navel is considered to be a nerve centre, and the Svādhiṣṭhāna Chakra, one of the purificatory fly-wheels in the human nervous system, is situated there. This chakra corresponds to the hypo-gastric plexus. The pose is recommended for persons with rounded and drooping shoulders.

33| Triangā Mukhaikapda Paschimottānāsana

FIVE*

Trianga means three limbs or parts thereof. In this posture the three parts are the feet, knees and buttocks. Mukhaikapāda (a compound of three words, mukha = face, eka = one, and pāda = leg or foot) corresponds to the face (or mouth) touching one (extended) leg. In Paschimottānāsana (Plate 81) the back of the whole body is intensely stretched.


68


69

TECHNIQUE

1. Sit on the floor, with the legs stretched straight in front. (Plate 35)

2. Bend the right leg at the knee and move the right foot back. Place the right foot by the side of the right hip joint, keep the toes pointing back and rest them on the floor. The inner side of the right calf will touch the outer side of the right thigh.

3. Balance in this position, throwing the weight of the body on the bent knee. In the beginning, the body tilts to the side of the outstretched leg, and the foot of the outstretched leg also tilts outwards. Learn to balance in this position, keeping the foot and toes stretched and pointing forward.

4. Now hold the left foot with both the palms, gripping the sides of the sole. If you can, then extend the trunk forward and hook the wrists round the outstretched left foot. (Plate 68) Take two deep breaths. It usually takes several months before one can hook the wrists in this way, so do not despair after the first few attempts.

5. Join the knees, exhale and bend forward. Rest first the forehead, then the nose, next the lips and ultimately the chin on the left knee. (Plate 69) To achieve this, widen the elbows and push the trunk forward with an exhalation.

6. Do not rest the left elbow on the floor. In the beginning, one loses balance and topples over to the side of the extended leg. The trunk should, therefore, be slightly bent towards the side of the bent leg and the weight of the body should be taken by the bent knee.

7. Stay in this position from half a minute to a minute, breathing evenly.

8. Inhale, raise the head and trunk, release the hands, straighten the right leg and come to position 1.

9. Repeat the pose on the other side, keeping the right leg stretched out on the ground, bending the left knee and placing the left foot by the left hip joint. Stay for the same length of time on both sides.

EFFECTS

This āsana is recommended for persons suffering from dropped arches and flat feet. It cures sprains in the ankle and the knee, and any swelling in the leg is reduced.

Along with Jānu Śīrṣāsana (Plate 63) and Ardha Baddha Padma Paschimottānāsana (Plate 66), this āsana tones the abdominal organs and keeps them free from sluggishness. We abuse our abdominal organs by over-indulgence or by conforming to social etiquette. Abdominal organs cause a majority of diseases and ancient sages emphasized that their health was essential for longevity, happiness and peace of mind. These forward bending āsanas keep the abdominal organs healthy and in trim. Apart from keeping the muscles in shape, they work on the organs as well.

34| *Marīchyāsana I*

FIVE*

This āsana is dedicated to the sage Marīchi, son of the Creator, Brahmā. Marīchi was the grandfather of Sūrya (the Sun God).

TECHNIQUE

1. Sit on the floor with the legs stretched straight in front. (Plate 35)

2. Bend the left knee and place the sole and heel of the left foot flat on the floor. The shin of the left leg should be perpendicular to the floor and the calf should touch the thigh. Place the left heel near the perineum. The inner side of the left foot should touch the inner side of the outstretched right thigh.

3. Stretch the left shoulder forward till the left armpit touches the perpendicular left shin. Turn the left arm round the left shin and thigh, bend the left elbow and throw the left forearm behind the back at the level of the waist. Then move the right hand behind the back and clasp the left hand with the right at the wrist or vice versa. If that is not possible then clasp the palms or the fingers. (Plate 70)

4. Now, turn the spine to the left, keeping the outstretched right leg straight. Remain in this position gazing at the outstretched right big toe and take a few deep breaths.



70

5. Exhale, and bend forward. Rest the forehead, then the nose, next the lips and lastly the chin on the right knee. (Plate 71) While in this position, keep both shoulders parallel to the floor and breathe normally. Stay in the pose for about 30 seconds and see that the back of the entire extended leg rests on the floor throughout.

6. Inhale, raise the head from the right knee (Plate 70), release the hands, straighten the left leg and come to position 1.

7. Repeat the pose on the other side for an equal length of time.

EFFECTS

The fingers gain in strength by the practice of this āsana. In the preceding āsanas (namely, Jānu Śīrṣāsana (Plate 63), Ardha Baddha Padma Paschimottānāsana (Plate 66) and Triang Mukhaikapāda Paschimottānāsana (Plate 69) the abdominal organs are made to contract by gripping a leg with the hands. In this pose the hands do not hold the legs. To bend forward and to rest the chin on the knee of the extended leg the abdominal organs have to contract vigorously. This creates a better circulation of blood round the abdominal organs and keeps them healthy. In the beginning it is very difficult to bend forward at all after gripping both hands behind the back, but it comes with practice. The dorsal region of the spine is also exercised in this pose.

NOTE

The four poses, Jānu Śīrṣāsana, Ardha Baddha Padma Paschimottānāsana, Triang Mukhaikapāda Paschimottānāsana and Marīchyāsana I, are preparatory poses for the correct Paschimottānāsana. (Plate 81) It is difficult for many to get a good grip on the feet in Paschimottānāsana even after several attempts. These four āsanas give one sufficient elasticity in the back and legs so that one gradually achieves the correct Paschimottānāsana (Plate 81) as described later. Once this is done with ease, these four āsanas can be practised once or twice a week instead of daily.



71

35| *Upaviṣṭha Koṇāsana*

NINE*

Upaviṣṭha means seated. Koṇa means an angle.

TECHNIQUE

1. Sit on the floor with the legs stretched straight in front. (Plate 35)

2. Move the legs sideways one by one and widen the distance between them as far as you can. Keep the legs extended throughout and see that the back of the entire legs rests on the floor.

3. Catch the big toes between the respective thumbs and index and middle fingers.

4. Keep the spine erect and extend the ribs. Pull the diaphragm up and hold the pose for a few seconds with deep breaths. (Plate 72)



72

5. Now clasp the feet with the hands. Exhale, bend forward and rest the head on the floor. (Plate 73) Then extend the neck and place the chin on the floor.

6. Then, try to rest the chest on the floor. (Plate 74) Stay in this position from 30 to 60 seconds with normal breathing.

7. Inhale, raise the trunk off the floor (Plate 72) and release the hold on the feet, bring them together and relax.



73



74

EFFECTS

The āsana stretches the hamstrings and helps the blood to circulate properly in the pelvic region and keeps it healthy. It prevents the development of hernia of which it can cure mild cases and relieves sciatic pains. Since the āsana controls and regularizes the menstrual flow and also stimulates the ovaries, it is a boon to women.

36| *Paschimottānāsana (also called Ugrāsana or Brahmacharyāsana)*

SIX*

Paschima literally means the west. It implies the back of the whole body from the head to the heels. The anterior or eastern aspect is the front of the body from the face down to the toes. The crown of the head is the upper or northern aspect while the soles and heels of the feet form the lower or southern aspect of the body. In this āsana the back of the whole body is intensely stretched, hence the name.

Ugra means formidable, powerful and noble. Brahmacharya means religious study, self-restraint and celibacy.

TECHNIQUE

1. Sit on the floor with the legs stretched straight in front. Place the palms on the floor by the side of the hips. Take a few deep breaths. (Plate 35)

2. Exhale, extend the hands and catch the toes. Hold the right big toe between the right thumb and the index and middle fingers and likewise the left big toe. (Plate 75)

3. Extend the spine and try to keep the back concave. To start with the back will be like a hump. This is due to stretching the spine only from the area of the shoulders. Learn to bend right from the pelvic region of the back and also to extend the arms from the shoulders. Then the hump will disappear and the back will become flat as in Plate 75. Take a few deep breaths.

4. Now exhale, bend and widen the elbows, using them as levers, pull the trunk forward and touch the forehead to the knees. (Plate 76) Gradually rest the elbows on the floor, stretch the neck and trunk, touch the knees with the nose and then with the lips. (Plate 77)



75



76



77



78



79



80

5. When this becomes easy, make a further effort to grip the soles and rest the chin on the knees. (Plate 78)

6. When this also becomes easy, clasp the hands by interlocking the fingers and rest the chin on the shins beyond the knees. (Plate 79)

7. When position 6 becomes easy, grip the right palm with the left hand or the left palm with the right hand beyond the outstretched feet exhale and rest the chin on the shins beyond the knees. (Plate 80)

8. If position 8 also becomes easy, hold the right wrist with the left hand or the left wrist with the right hand and rest the chin on the shins beyond the knees. (Plate 81)

9. See that the back of the legs at the knee joints rests firmly on the ground. In the initial stages the knees will be lifted off the floor. Tighten the muscles at the back of the thighs and pull the trunk forward. Then the back of the knee joints will rest on the floor.

10. Try and stay in whichever of the above positions you can achieve from 1 to 5 minutes, breathing evenly.

11. Inhale, raise the head from the knees and relax.

EFFECTS

This āsana tones the abdominal organs and keeps them free from sluggishness. It also tones the kidneys, rejuvenates the whole spine and improves the digestion.

The spines of animals are horizontal and their hearts and below the spine. This keeps them healthy and gives them great power of endurance. In humans the spine is vertical and the heart is not lower than the spine, so that they soon feel the effects of exertion and are also susceptible to the heart diseases. In Paschimottānāsana the spine is kept straight and horizontal and the heart is at a lower level than the spine. A good stay in this pose massages the heart, the spinal column and the abdominal organs, which feel refreshed and the mind is rested. Due to the extra stretch given to the pelvic region more oxygenated blood is brought there and the gonad glands absorb the required nutrition from the blood. This increases vitality, helps to cure impotency and leads to sex control. Hence, this āsana was called Brahmacharyāsana. Brahmacharya means celibacy and a Brahmachāri is one who has controlled the sex appetite.



81

37| *Pūrvottānāsana*

ONE*

Pūrva literally means the East. It means the front of the whole body from the forehead to the toes. Uttāna means an intense stretch. In this posture, the whole front of the body is stretched intensely.

TECHNIQUE

1. Sit on the floor with the legs stretched straight in front. Place the palms on the floor by the hips, with the fingers pointing in the direction of the feet. (Plate 35)

2. Bend the knees and place the soles and heels on the floor.

3. Take the pressure of the body on the hands and feet, exhale and lift the body off the floor. Straighten the arms and the legs and keep the knees and elbows tightened. (Plate 82)

4. The arms will be perpendicular to the floor from the wrists to the shoulders. From the shoulders to the pelvis, the trunk will be parallel to the floor.

5. Stretch the neck and throw the head as far back as possible.

6. Stay in this posture for one minute, breathing normally.

7. Exhale, bend the elbows and knees, lower the body to sit on the floor and relax.

EFFECTS

This posture strengthens the wrists and ankles, improves the movement of the shoulder joints and expands the chest fully. It gives relief from the fatigue caused by doing other strenuous forward bending āsanas.

38| *Sālamba Śīrṣāsana I*

FOUR*

Sālamba means with support. Śīrṣa means the head. This is the head stand pose, one of the most important Yogi āsanas. It is the basic posture. It has several variations, which are described later as the Śīrṣāsana cycle. Its mastery gives one balance and poise, both physically and mentally. The technique of doing it is given at length in two parts; the first is for beginners, the second for those who can remain balanced in the pose. Attention is specially directed to the hints on Śīrṣāsana given after the two techniques.



82

TECHNIQUE FOR BEGINNERS

1. Spread the blanket fourfold on the floor and kneel near it.

2. Rest the forearms on the centre of the blanket. While doing so take care that the distance between the elbows on the floor is not wider than the shoulders.

3. Interlock the fingers right up to the finger-tips (Plate 83), so that the palms form a cup. Place the sides of the palms near the little fingers on the blankets. While going up on to your head or balancing, the fingers should be kept tightly locked. If they are left loose, the weight of the body falls on them and the arms ache. So remember to lock them well.



83



84



85

4. Rest the crown of the head only on the blanket, so that the back of the head touches the palms which are cupped. (Plate 84) Do not rest the forehead nor the back but only the crown of the head on the blanket. To do this move the knees towards the head.

5. After securing the head position, raise the knees from the floor by moving the toes closer to the head. (Plate 85)

6. Exhale, take a gentle swing from the floor and lift the legs off the ground with bent knees. Take the swing in such a way that both feet leave the floor simultaneously, to come to position as in Plate 86. When once this position is secured, follow the various stages of the leg movements as in Plates 87, 88 and 89, step by step.

7. Stretch the legs and stand on the head, keeping the whole body perpendicular to the floor. (Front view: Plate 90. Back view: Plate 91. Side view: Plate 96)

8. After staying in the final position to capacity, from one to five minutes, flex the knees and slide down to the floor in the reverse order as in Plates 89, 88, 87, 86, 85, 84 and raise head from the floor.

9. A beginner must have the assistance of a friend or do the āsana against a wall. While practising against a wall, the distance between it and the head should not be more than 2 or 3 inches. If the distance is greater, the spine will curve and the stomach will protrude. The weight of the body will be felt on the elbows and the position of the head may change. The face will appear to be flushed and the eyes either strained or puffed. It is, therefore, advisable for a beginner to do the head stand in a corner where two walls meet, placing the head some 2 to 3 inches from either wall.


86


87


88


89

10. While doing the head stand against a wall or in a corner, the beginner should exhale, swing the legs up, support the hips against the side of the wall and move the feet up. In a corner, he can touch the heels to either side of the walls. He should then stretch the back vertically up, gradually leave the support of the wall and learn to master the balance. While coming down, he can rest the feet and hips against the wall, slide down and kneel, resting his knees on the floor. The movements of coming down and going up should be done with an exhalation.

11. The advantage which the beginner has of balancing in a corner is that his head and legs will be in the right angle formed by the walls, and he will be sure of his right position. This will not be the case if he balances against a straight wall. For while his balance is insecure he may sway from the wall, or his body may tilt or swing to the stronger side, while his legs may rest against the wall with a bend either at the waist or the hips. The beginner will not be in a position to know that he has tilted to one side, much less to correct it. In time he may learn to balance on the head, but by habit his body may still tilt or his head may not be straight. It is as hard to correct a wrong pose in the head stand as it is to break a bad habit. Moreover this wrong posture may well lead to aches and pains in the head, neck, shoulders and back. But the two walls of a corner will help the beginner to keep the āsana symmetrical.


90


91



92



93

12. When once balance is secured, it is advisable to come down to the floor with the legs straight (that is, without bending the knees at all) and with a backward action of the hips. At first, it is not possible to go up and come down without bending the legs, but the correct method should be learnt. Once the beginner has confidence in the head stand, he will find it more beneficial to go up and down with the legs together and straight, without any jerks.

13. It takes time for the beginner to become oriented to his surroundings while he is balancing on his head. Everything will seen at first to be completely unfamiliar. The directions and instructions will appear confusing and he will find it an effort to think clearly or to act logically. This is due to fear of a fall. The best way to overcome fear is to face with equanimity the situation of which one is afraid. Then one gets the correct perspective, and one is not frightened any more. To topple over while learning the head stand is not as terrible as we imagine. If one overbalances, one should remember to loosen the interlocked fingers, relax, go limp and flex the knees. Then one will just roll over and smile. If the fingers are not loosened they will take the jerk of the fall which will be painful. If we do not relax and go limp while falling we hit the floor with a hard bump. If we flex the knees, we are unlikely to graze them in the fall. After one has learnt to balance against a wall or in a corner, one should try the head stand in the middle of the room. There will be a few spills and one must learn the art of falling as indicated above. Learning to do Śīrṣāsana in the middle of a room gives the beginner more confidence.

TECHNIQUE FOR THOSE WHO CAN BALANCE EIGHT*

1. Follow the technique described for beginners from positions 1 to 4.

2. After securing the head position, stretch the legs straight by raising the knees from the floor. Move the toes nearer to the head and try to press the heels to the floor, keeping the back erect. (Plate 92)

3. Stretch the dorsal or middle region of the spine and stay in this position for about 30 seconds while breathing evenly.

4. Exhale, raise the heels and take the toes off the floor with a backward movement of the hips. Raise both legs simultaneously, keeping them poker stiff. (Plate 93) Take a breath.

5. Again with an exhalation move the legs up until they are parallel to the floor. This position is called:

39| *Ūrdhvā Daṇḍāsana*

EIGHT*

(Ūrdhvā = up, daṇḍ = a staff)
Stay in this position for 10 seconds with normal breathing.

6. Exhale, move the legs up as in Plate 95, and then pull them up to the vertical position. (Side view: Plate 96) Stay in this pose from 1 to 5 minutes while breathing evenly.

7. Come down gradually, observing the above technique in a reverse order. (Plates 95, 94, 93 and 92) Rest the feet on the floor, bend the knees (Plate 84) and raise the head from the floor or blanket. (Plate 83)

8. While coming down, it is advisable to stay in Ūrdhvā Daṇḍāsana according to capacity up to one minute while breathing normally. In this position, the neck and trunk will not be perpendicular to the floor but will sway slightly backwards. The neck, shoulders and spine will be put to a very great strain and in the initial stages one cannot stay with the legs parallel to the floor for more than a few seconds. The stay will become longer as the neck, shoulders, abdomen and spine become stronger.



94



95

HINTS ON ŚĪRṢĀSANA

1. In Śīrṣāsana the balance alone is not important. One has to watch from moment to moment and find out the subtle adjustments. When we stand on our feet, we need no extra effort, strength or attention, for the position is natural. Yet the correct method of standing affects our bearing and carriage. It is, therefore, necessary to master the correct method as pointed out in the note on Tāḍāsana. In Śīrṣāsana also, the correct position should be mastered, as a faulty posture in this āsana will lead to pains in the head, neck and back.

2. The whole weight of the body should be borne on the head alone and not on the forearms and hands. The forearms and hands are to be used only for support to check any loss of balance. In a good pose you feel a circle, about the size of an Indian rupee, of the head in contact with the blanket on the floor.

3. The back of the head, the trunk, the back of the thighs and the heels should be in a line perpendicular to the floor and not inclined to one side. The throat, chin and breast-bone should be in one line, otherwise the head will tilt to one side or move forward. As regards the interlocked hands behind the head, the palms should not be stuck into the head. The upper and the lower sides of the palms should be in a line, otherwise the crown of the head will not rest on the floor correctly.

4. The elbows and the shoulders should be in a line and the elbows should not be widened. The shoulders should be kept as high above the floor as possible

by moving them up and stretching them sideways. In order to learn the correct shoulder stretch, release the interlocked fingers and remove the hands from behind the head and widen the wrists from the forearms, keeping the elbows stationary. Place the wrists on the floor with the palms facing up, touch the shoulders with the fingers, keeping the wrists on the floor and maintain the balance. (Plate 97) This will not only improve the balance but also prepare you for the other Śīrṣāsana poses described later.

5. As to the position of the trunk, the dorsal region should be pushed forward as well as up. The lumbar (waist) and pelvic regions should not be pushed forward, while the trunk from the shoulders to the pelvis should be kept perpendicular. If the pelvic area juts forward, it means that you are bearing the weight of the body not on the head alone but also on the elbows for you have not stretched the dorsal region (the chest) correctly. When viewed from the side, the body from the neck to the heels should appear straight.

6. As far as possible try and join the thighs, knees, ankles and toes. Stretch the legs fully, especially the back of the knees and thighs. If the legs swing back tighten the knees and the lower median portion of the abdomen above the pubes. This will keep the legs perpendicular. Keep the toes pointing up. If the legs swing forward, stretch the dorsal region and push the pelvic area slightly back until it is in line with the shoulders. The body will then feel light and the pose will be exhilarating.

7. While going up or holding the head stand the eyes should never become bloodshot. If they do, the pose is faulty.*

8. The time limit for Śīrṣāsana depends upon individual capacity and the time at one's disposal. One can hold it comfortably from 10 to 15 minutes. A beginner can do it for 2 minutes and go up to 5 minutes. It is always difficult for a beginner to balance for one minute, but once he succeeds he can be sure that from then on he will be able to master Śīrṣāsana soon.

9. While going up or coming down, move both legs together, inch by inch. All the movements should be done with exhalation. Inhale while waiting in a position. The effect of going down and coming up straight without bending the legs at the knees is that harmonious slow movement is gained and the flow of blood to the head is controlled. The face does not flush from jerky and fast movements, as the flow of blood to the waist and the legs is also controlled.


96

---

* I have taught this pose to a lady of 65 who was suffering from glaucoma. Now she finds the eyes are completely rested and the pain in them is much lessened. Medical examination revealed that the tension in the eyeballs had decreased. I am mentioning this to prove the value of the correct head stand.



97

Then there is no danger of losing balance from giddiness or numbness of the feet when one stands up immediately after the head balance. In course of time the whole movement of going up, staying and coming down should become as effortless as possible. In a perfect Śīrṣāsana your body feels completely stretched and at the same time you experience a feeling of complete relaxation.

10. It is always safe to perfect Sarvāngāsana (Plate 102) first before attempting Śīrṣāsana. If the standing poses described earlier (Plates 1 to 18) and the various movements of Sarvangāsana and Halāsana (Plates 108 to 125) are mastered first, Śīrṣāsana will come without much effort. If these elementary āsanas have not been mastered, the period taken to learn Śīrṣāsana will be longer.

11. After one has learnt to balance in Śīrṣāsana, however, it is preferable to perform Śīrṣāsana first before practising any other āsana. This is because one cannot balance or hold the head stand if the body is exhausted by doing other poses or if the breathing becomes fast and shaky. Once the body is tired or the breathing is not free and easy, the body will shake and it will be difficult to maintain the balance. It is always better to do Śīrṣāsana first when one is fresh.

12. Śīrṣāsana should always be followed by Sarvāngāsana and its cycle. It has been observed that people who devote themselves to Śīrṣāsana alone without doing the Sarvāngāsana poses are apt to lose their temper over trifling things and become irritated quickly. The practice of Sarvāngāsana coupled with Śīrṣāsana checks this trait. If Sarvāngāsana is the Mother, then Śīrṣāsana may be regarded as the Father of all āsanas. And just as both parents are necessary for peace and harmony in a home, so the practice of both these āsanas is essential to keep the body healthy and the mind tranquil and peaceful.

EFFECTS OF ŚĪRṢĀSANA

The ancient books have called Śīrṣāsana the king of all āsanas and the reasons are not hard to find. When we are born, normally the head comes out first and then the limbs. The skull encases the brain, which controls the nervous system and the organs of sense. The brain is the seat of intelligence, knowledge, discrimination, wisdom and power. It is the seat of Brahman, the soul. A country cannot prosper without a proper king or constitutional head to guide it; so also the human body cannot prosper without a healthy brain.

The *Bhagavad-Gītā* says: 'Harmony (sattva), mobility (rajas), inertia (tamas), such are the qualities, matter-born; they bind fast, O great armed one (Arjuna), the indestructible dweller in the body.' (Fourteenth Discourse, verse 5) All these qualities stem from the brain, and sometimes one quality prevails and sometimes the others. The head is the centre of sattvic qualities which control discrimination; the trunk of Rājasic qualities which control passion, emotion and actions; and the region below the diaphragm of tāmasic qualities which control sensual pleasures like the enjoyment of food and drink, and the thrills and pleasures of sex.

Regular practice of Śīrṣāsana makes healthy pure blood flow through the brain cells. This rejuvenates them so that thinking power increases and thoughts become clearer. The āsana is a tonic for people whose brains tire quickly. It ensures a proper blood supply to the pituitary and pineal glands in the brain. Our growth, health and vitality depend on the proper functioning of these two glands.

People suffering from loss of sleep, memory and vitality have recovered by the regular and correct practice of this āsana and have become fountains of energy. The lungs gain the power to resist any climate and stand up to any work, which relieves one from colds, coughs, tonsillitis, halitosis (foul breath) and palpitations. It keeps the body warm. Coupled with Sarvāngāsana movements (Plates 108 to 125), it is a boon to people suffering from constipation. Regular practice of Śīrṣāsana will show marked improvement in the haemoglobin content of the blood.

It is not advisable to start with Śīrṣāsana and Sarvāngāsana when one suffers from high or low blood pressure.

Regular and precise practice of Śīrṣāsana develops the body, disciplines the mind and widens the horizons of the spirit. One becomes balanced and self-reliant in pain and pleasure, loss and gain, shame and fame and defeat and victory.



98

40| *Sālamba Sarvāngāsana I*

TWO*

Ālamba means a prop, a support and sa together with or accompanied by. Sālamba, therefore means supported or propped up. Sarvānga (Sarva = all, whole, entire, complete; anga = limb or body) means the entire body or all the limbs. In this pose the whole body benefits from the exercise, hence the name.

TECHNIQUE FOR BEGINNERS

1. Lie flat on the back of the carpet keeping the legs stretched out, tightened at the knees. Place the hands by the side of the legs, palms down. (Plate 98) Take a few deep breaths.

2. Exhale, bend the knees and move the legs towards the stomach till the thighs press it. (Plate 99) Take two breaths.

3. Raise the hips from the floor with an exhalation and rest the hands on them by bending the arms at the elbows. (Plate 100) Take two breaths.

4. Exhale, raise the trunk up perpendicularly supported by the hands until the chest touches the chin. (Plate 101)



99

5. Only the back of the head and the neck, the shoulders and the backs of the arms up to the elbows should rest on the floor. Place the hands in the middle of the spine as in Plate 101. Take two breaths.

6. Exhale and stretch the legs straight with the toes pointing up. (Front view: Plate 102. Back view: Plate 103)

7. Stay in this position for 5 minutes with even breathing.

8. Exhale, gradually slide down, release the hands, lie flat and relax.

9. If you cannot do the āsana without support use a stool and follow the technique. See Plate 104.



100



101



102



103



104

TECHNIQUE FOR ADVANCED PUPILS

1. Lie flat on the back on the carpet.

2. Keep the legs stretched out, tightened at the knees. Place the hands by the side of the legs, palms down. (Plate 98)

3. Take a few deep breaths. Exhale slowly and at the same time raise both legs together and bring them at a right angle to the body. (Plate 105) Remain in this position and inhale, keeping the legs steady.

4. Exhale, again raise the legs further up by lifting the hips and back from the floor, pressing the palms gently against the floor as in Plate 106.

5. When the whole trunk is raised off the ground, bend the elbows and place the palms on the back of the ribs, resting the shoulders well on the floor.

6. Utilize the palm pressure and raise the trunk and legs up vertically as in Plate 107 so that the breast-bone presses the chin to form a firm chinlock. The contraction of the throat and pressing the chin against the breast-bone to form a firm chinlock is known as Jālandhara Bandha. Remember to bring the chest forward to touch the chin and not to bring the chin towards the chest. If the latter is done, the spine is not stretched completely and the full effect of this āsana will not be felt.

7. Only the back of the head and neck, the shoulders and the upper portion of the arms up to the elbows should rest well on the floor. The remainder of the body should be in one straight line, perpendicular to the floor. This is the final position. (Side view: Plate 108)

8. In the beginning, there is a tendency for the legs to swing out of the perpendicular. To correct this, tighten the back thigh muscles and stretch up vertically.



105

9. The elbows should not be placed wider than the shoulders. Try and stretch the shoulders away from the neck and also to bring the elbows close to each other. If the elbows are widened, the trunk cannot be pulled up properly and the pose will look imperfect. Also see that the neck is straight with the centre of the chin resting on the sternum. In the beginning, the neck moves sideways and if this is not corrected, it will cause pain and injure the neck.



106

10. Remain in this pose for not less than 5 minutes. Gradually increase the time to 15 minutes; this will have no ill effects.

11. Release the hands, slide to the floor, lie flat and relax.

As the weight of the whole body is borne on the neck and shoulders and as the hands are used to support the weight this āsana is called Sālamba Sarvāṅgāsana. In Sarvāṅgāsana there are various movements which can be done in addition to the basic pose described above.



107



108

EFFECTS

The importance of Sarvāngāsana cannot be over-emphasized. It is one of the greatest boons conferred on humanity by our ancient sages. Sarvāngāsana is the mother of āsanas. As a mother strives for harmony and happiness in the home, so this āsana strives for the harmony and happiness of the human system. It is a panacea for most common ailments. There are several endocrine organs or ductless glands in the human system which bathe in blood, absorb the nutriments from the blood and secrete hormones for the proper functioning of a balanced and well developed body and brain. If the glands fail to function properly, the hormones are not produced as they should be and the body starts to deteriorate. Amazingly enough many of the āsanas have a direct effect on the glands and help them to function properly. Sarvāngāsana does this for the thyroid and parathyroid glands which are situated in the neck region, since due to the firm chinlock their blood supply is increased. Further, since the body is inverted the venous blood flows to the heart without any strain by force of gravity. Healthy blood is allowed to circulate around the neck and chest. As a result, persons suffering from breathlessness, palpitation, asthma, bronchitis and throat ailments get relief. As the head remains firm in this inverted position, and the supply of the blood to it is regulated by the firm chinlock, the nerves are soothed and headaches – even chronic ones – disappear. Continued practice of this āsana eradicates common colds and other nasal disturbances. Due to the soothing effect of the pose on the nerves, those suffering from hypertension, irritation, shortness of temper, nervous breakdown and insomnia are relieved. The change in bodily gravity also affects the abdominal organs so that the bowels move freely and constipation vanishes. As a result the system is freed from toxins and one feels full of energy. The āsana is recommended for urinary disorders and uterine displacement, menstrual trouble, piles and hernia. It also helps to relieve epilepsy, low vitality and anaemia. It is no over-statement to say that if a person regularly practises Sarvāngāsana he will feel new vigour and strength, and will be happy and confident. New life will flow into him, his mind will be at peace and he will feel the joy of life. After a long illness, the practice of this āsana regularly twice a day brings back lost vitality. The Sarvāngāsana cycle activates the abdominal organs and relieves people suffering from stomach and intestinal ulcers, severe pains in the abdomen and colitis.

People suffering from high blood pressure should not attempt Sālamba Sarvāngāsana unless they do Halāsana (Plate 113) first and can stay in it for not less than 3 minutes.

Do not perform Sarvāngāsana during menstruation.

Halāsana is described on the following pages.

THE SARVĀNGĀSANA CYCLE

These various movements can be practised at one stretch after staying in Sarvāngāsana (Plate 102) from 5 to 10 minutes or more according to capacity; do them for 20 to 30 seconds at a time each side except Halāsana, which should last from 3 to 5 minutes at a stretch.

41| Halāsana

FOUR*

Hala means a plough, the shape of which this posture resembles, hence the name. It is a part of Sarvāngāsana I and a continuation thereof.

TECHNIQUE

1. Do Sālamba Sarvāngāsana (Plate 103) with a firm chinlock.

2. Release the chinlock, lower the trunk slightly, moving the arms and legs over the head and resting the toes on the floor. (Plate 109)

3. Tighten the knees by pulling up the hamstring muscles at the back of the thighs and raise the trunk. (Plate 110)

4. Stretch the arms on the floor in the direction opposite to that of the legs. (Plate 111)



109



110



111

5. Interlock the fingers (Plate 112) and turn the wrists so that the thumbs rest on the floor. (Plate 113) Stretch the palms along with the fingers, tighten the arms at the elbows and pull them from the shoulders.

6. The legs and the hands are stretched in opposite directions and this stretches the spine completely.

7. While interlocking the fingers, it is advisable to change the interlock. Suppose that the right thumb touches the floor first, maintain the position for a minute. Then release the grip and bring the left thumb first on the floor, follow the interlock, finger by finger, and stretch out the arms for the same length of time. This will lead to harmonious development and elasticity of both the shoulders, elbows and wrists.

8. In the beginning interlocking will be difficult. By gradual practice of the above mentioned positions, you will interlock the fingers easily.

9. In the beginning it is also difficult to keep the toes firmly on the floor behind the head. If you lengthen the timing and stretch of Sarvāngāsana (Plate 102) before going into Halāsana, the toes will remain longer on the floor.

10. Remain in the attainable pose from one to five minutes with normal breathing.

11. Release the hands. Raise the legs up to Sarvāngāsana and gradually slide down to the floor. Lie flat on the back and relax.



112



113

EFFECTS

The effect of Halāsana is the same as that of Sarvāngāsana. (Plate 102) In addition, the abdominal organs are rejuvenated due to contraction. The spine receives an extra supply of blood due to the forward bend and this helps to relieve backache. Cramps in the hands are cured by interlocking and stretching the palms and fingers. People suffering from stiff shoulders and elbows, lumbago and arthritis of the back find relief in this āsana. Griping pain in the stomach due to wind is also relieved and lightness is felt immediately.

The pose is good for people with a tendency for high blood pressure. If they perform Halāsana first and then Sarvāngāsana, they will not feel the rush of blood or the sensation of fullness in the head.

Halāsana is a preparatory pose to Paschimottānāsana. (Plate 81) If one improves in Halāsana, the resulting mobility of the back will enable one to perform Paschimottānāsana well.

NOTE

For persons suffering from high blood pressure the following technique is recommended for doing Halāsana before they attempt Sālamba Sarvāngāsana.

1. Lie flat on the back on the floor.

2. Exhale, slowly raise the legs to a perpendicular position and stay there breathing normally for about 10 seconds.

3. Exhale, bring the legs over and beyond the head and touch the toes on the floor. Keep the toes on the floor and the legs stiff at the knees.

4. If you have difficulty in keeping the toes on the floor, then place a chair or a stool behind the head and rest the toes on it.

5. If the breathing becomes heavy or fast do not rest the toes on the floor, but on a stool or chair. Then fullness or pressure is not felt in the head.

6. Extend the arms over the head, keep them on the floor and stay in this position with normal breathing for 3 minutes.

7. Throughout the āsana, gaze at the tip of the nose with the eyes shut.

42| *Karṇapīdāsana*

ONE*

Karṇa means the ear. Pīda means pain, discomfort or pressure. This is a variant of Halāsana and can be done along with it.

TECHNIQUE

1. Do Halāsana (Plate 113) and after completing the time limit for that pose, flex the knees and rest the right knee by the side of the right ear and the left knee by the side of the left.

2. Both knees should rest on the floor, pressing the ears.

3. Keep the toes stretched out and join the heels and toes. Rest the hands either on the back of the ribs (Plate 114a), or interlock the fingers and stretch out the arms (Plate 114b).

4. Remain in this position for half a minute or a minute with normal breathing.

EFFECTS

This āsana rests the trunk, heart and legs. The spine is stretched more while bending the knees, and this helps the circulation of blood round the waistline.



114A



114B

43| *Supta Koṇāsana*

TWO*

Supta means lying down and koṇa an angle. It is a variation of Halāsana in which the legs are spread apart.

TECHNIQUE

1. From Karṇapīdāsana (Plates 114a, 114b), stretch the legs straight and spread the legs as far apart as you can.

2. Pull the trunk up and tighten the knees.

3. Hold the right toe with the right hand and the left toe with the left one. Keep the heels up. After gripping the toes, move the dorsal region of the spine still further up and extend the hamstring muscles. (Plate 115).

4. Stay in the pose from 20 to 30 seconds with normal breathing.

EFFECTS

This pose tones the legs and helps to contract the abdominal organs.



115

44| *Pārśva Halāsana*

FOUR*

In Halāsana (Plate 114) both the legs rest behind the head. In this pose they rest sideways on one side of and in line with the head. This is the lateral plough pose.

TECHNIQUE

1. Do Supta Koṇāsana (Plate 115) and come back to Halāsana.

2. Place the palms on the back of the ribs.

3. Move both the legs as far as you can to the left.

4. Tighten both knees, raise the trunk up with the help of the palms and stretch the legs. (Plate 116)

5. Remain in this position for half a minute with normal breathing.

6. Exhale, move the legs to the right until they are in line with the head and hold the pose for half a minute. Do not disturb the position of the chest and trunk when the legs are moved. The chest and trunk should remain as in Sarvāṅgāsana or Halāsana.



116

EFFECTS

In this āsana, the spine moves laterally and becomes more elastic. The colon, which is inverted during the movements, is exercised properly and elimination will be complete. People suffering from acute or chronic constipation which is the mother of several diseases derive great benefit from this āsana. If rubbish is dumped outside our house we feel sick. How much more so when waste matter which creates toxins is allowed to accumulate in our own system? If this waste matter is not eliminated, diseases will enter the body like thieves and rob us of health. If the bowels do not move freely, the mind becomes dull and one feels heavy and irritable. This āsana helps us keep the bowels free and thereby win the prize of health.

45| *Eka Pāda Sarvāngāsana*

FIVE*

Eka means one, single. Pāda means the foot. In this variation of Sarvāngāsana, one leg is on the floor in Halāsana, while the other is in a vertical position along with the trunk.

TECHNIQUE

1. Do Sālamba Sarvāngāsana I. (Plate 102)

2. Keep the left leg up in Sarvāngāsana. Exhale and move the right leg down to the floor to Halāsana. (Plate 117) It should remain stiff and straight and not bend at the knee. If it is not possible to touch the floor, lower the leg as far as possible.

3. While resting the right leg on the floor, the left knee should be kept taut and not allowed to tilt sideways. The left leg should be kept straight, facing the head.

4. Stay in the pose for 20 seconds maintaining normal breathing.

5. Exhale, lift the right leg back to Sarvāngāsana, and then move the left leg down to the floor in Halāsana, keeping the right leg vertically up and stiff. Lifting the leg from the floor back to Sarvāngāsana exercises the abdominal organs more than if one brings both legs down to Halāsana.

6. Stay on this side for the same length of time.

EFFECTS

This āsana tones the kidneys and the leg muscles.



117

46| *Pārśvaika Pāda Sarvāṅgāsana*

SIX*

Pārśva means the side. In Eka Pāda Sarvāṅgāsana (Plate 117) the lower leg rests behind the head, whereas here it rests sideways in line with the trunk.

TECHNIQUE

1. Perform Eka Pāda Sarvāṅgāsana on both sides as described above and come back to Sarvāṅgāsana.

2. Exhale, move the right leg down sideways to the floor until it is in line with the trunk. (Plate 118) Keep the right leg straight and stiff and do not bend it at the knee. If it is not possible to touch the floor, lower the leg as far as possible.

3. The left leg which is vertically up should be kept straight and not allowed to tilt to the right. The ribs should be lifted with the palms to expand the chest fully.

4. Remain in the pose for 20 seconds with normal breathing, exhale, and go back to Sarvāṅgāsana. Repeat with the other leg for the same length of time and return to Sarvāṅgāsana.

EFFECTS

This pose relieves constipation and also tones the kidneys.



118

47| *Setu Bandha Sarvāngāsana (also called Uttāna Mayūrāsana)*

TEN*

Setu means a bridge and Setu Bandha means the formation or construction of a bridge. In this position, the body is arched and supported on the shoulders, soles and heels. The arch is supported by the hands at the waist.

Ut means intense and tān means to stretch. This āsana resembles a stretched peacock (Mayūra), hence the name.

TECHNIQUE

1. Do Sālamba Sarvāngāsana. (Plate 102)

2. Rest the palms well on the back, raise the spine up, bend the knees (Plate 119) and throw the legs back over the wrists to the floor. (Plate 120) Stretch out the legs and keep them together. (Plate 121)

3. The whole body forms a bridge, the weight of which is borne by the elbows and the wrists. The only parts of the body in contact with the ground will be the back of the head and neck, the shoulders, the elbows and the feet. Stay in the pose from half a minute to a minute with normal breathing.

4. It is possible to lessen the pressure on the elbows and the wrists by stretching the spine towards the neck, keeping the heels firmly on the ground.



119



120



121

EFFECTS

This āsana gives the spine a backward movement and removes the strain on the neck caused by the other various movements of Sarvāngāsana.

A healthy and flexible spine indicates a healthy nervous system. If the nerves are healthy a man is sound in mind and body.

48| Ūrdhva Padmāsana in Sarvāngāsana

FOUR*

Ūrdhva means above, high. Padma means a lotus. In this Sarvāngāsana variation, the legs, instead of being kept straight up, are bent at the knees and crossed so that the right foot rests on the left thigh and the left foot on the right thigh as in the lotus pose. (Plate 53)

TECHNIQUE

1. From Sālamba Sarvāngāsana, bend the legs at the knees and cross them. First place the right foot over the left thigh, and then the left foot over the right thigh.

2. Stretch the crossed legs vertically up, move the knees closer to each other and the legs as far back as possible from the pelvic region. (Plate 122)

3. Stay in this pose from 20 to 30 seconds with deep and even breathing.



122

4. Uncross the legs, return to Sālamba Sarvāngāsana and repeat the pose by first placing the left foot over the right thigh and then the right foot over the left thigh. Stay for an equal length of time in all these positions as in the earlier ones.

49| Pinḍāsana in Sarvāngāsana

FIVE*

Pinḍa means embryo or foetus. In this variation of Sarvāngāsana which is a continuation of the earlier posture, the bent crossed legs are brought down until they rest on the head. The posture resembles that of an embryo in the womb, hence the name.

TECHNIQUE

1. From Ūrdhva Padmāsana in Sarvāngāsana (Plate 122), exhale, bend and lower the crossed legs from the hips towards the head.

2. Rest the legs over the head. (Plate 123)

3. Remain in this position from 20 to 30 seconds with normal breathing and go back to Ūrdhva Padmāsana in Sarvāngāsana.



123

50| *Pārśva Piṇḍāsana in Sarvāṅgāsana*

EIGHT*

Pārśva means the side or flank. In this Piṇḍāsana variation of the earlier pose, both the bent knees are moved sideways and placed on the floor on the same side of the trunk. This is the lateral embryo pose in Sarvāṅgāsana.

TECHNIQUE

1. After staying in Pindāsana (Plate 123) turn the hips sideways to the right, exhale and lower both knees to the floor. The left knee should be by the side of the right ear. (Plate 124)

2. The left shoulder will be raised off the floor in the beginning. Push the shoulder against the floor and press the left hand firmly against the back. If this is not done, you will lose balance and roll over to one side.

3. Due to the lateral twist, breathing will be fast and difficult as the diaphragm is pressed in this position.

4. The knee near the ear will not rest on the floor to start with, but only after long practice.

5. Stay in this position for 20 to 30 seconds, with normal breathing.

6. Exhale, come up from the right side and move the crossed legs over to the left, so that the left foot will be near the left ear. (Plate 125) Stay here also for the same length of time.



124



125

7. Go back to Ūrdhva Padmāsana. (Plate 122) Release the lotus pose by uncrossing the legs and return to Sālamba Sarvāṅgāsana.

8. Now change the position of the crossed legs. Cross the legs again by putting the left foot over the right thigh first and then the right foot over the left thigh instead of the other way as done earlier.

9. Repeat the movements again on both the sides as described earlier.

EFFECTS OF ŪRDHVA PADMĀSANA AND PĀRŚVA PINḌĀSANA MOVEMENTS IN SARVĀNGĀSANA

The change of crossing the legs brings equal pressure on both sides of the abdomen and colon and relieves constipation. For those suffering from chronic constipation a longer stay in Pārśva Pinḍāsana is recommended, and one minute on each side will prove most efficacious. Griping pain in the stomach is relieved by these poses.

Persons with extremely flexible knees, can easily perform these positions. It is, however, difficult for many people to cross the legs in Padmāsana. For them a longer stay in Pārśva Halāsana (Plate 116) – (there also the spine and trunk get a lateral twist but the legs remain straight) – is recommended.

In all these positions breathing at first will be fast and laboured. Try to maintain normal breathing.

NOTE

The spine is given the forward, lateral and backward movements in these variations of Sarvāngāsana. In Halāsana, Eka Pāda Sarvāngāsana, Karṇa Pīdāsana and Pinḍāsana the spine moves in the forward direction. In Pārśvaika Pāda Sarvānga, Pārśva Halāsana and Pārśva Pinḍāsana the spine moves laterally. In Setu Bandha it is given a backward movement. These movements tone the spine on all sides and keep it healthy.

It is related that in the Krita Age (the first Age of the Universe) a host of Dānavās (giants and demons) became invincible in battle under the leadership of Vṛtra and scattered the Devas (or Gods) in all directions. Realizing that they could not regain their power until Vṛtra was destroyed, the gods appeared before their Grandsire, Brahmā, the creator. Brahmā instructed them to consult Viṣṇu who asked them to obtain the bones of a sage called Dadhīcha, from which to make a demon-slaying weapon. The gods appeared before the sage and begged the boon according to Viṣṇu's advice. The sage renounced his body for the benefit of the gods. From the spine of Dadhīcha was fashioned Vajra, the thunderbolt, which Indra the king of the gods hurled and slew Vṛtra.

The story is symbolical. The Dānavās represent the tāmasic qualities in men and diseases. The Devas represent health, harmony and peace. To destroy the tāmasic qualities and the diseases due to them and to enjoy health and happiness, we have to make our spines strong as a thunderbolt like the spine of Dadhīcha. Then we shall enjoy health, harmony and happiness in abundance.

51| *Jaṭara Parivartanāsana*

FIVE*

Jaṭara means the stomach, the belly. Parivartana means turning or rolling about, turning round.

TECHNIQUE

1. Lie flat on the back on the floor. (Plate 98)

2. Exhale, raise both legs together until they are perpendicular to the floor. They should remain poker stiff, so do not bend them at the knees. (Plate 105)

3. Stretch out both arms sideways in line with the shoulders, so that the body resembles a cross.

4. Remain in this position for a few breaths. Then exhale, and move both the legs sideways (Plate 126) down towards the floor to the left until the toes of the left foot almost touch the finger-tips of the outstretched left hand. (Plate 127) Try and keep the back well on the floor. In the initial stages, the right shoulder will be lifted off the floor. To prevent this ask a friend to press it down, or catch hold of a heavy piece of furniture with the right hand when the legs are turned sideways to the left.



126



127

5. Both legs should go down together, the knees being kept tight throughout. As far as possible keep the lumbar portion of the back on the floor and turn the legs only from the hips. When the legs are near the outstretched left hand, move the abdomen to the right.

6. Stay in the pose for about 20 seconds, keeping the legs stiff throughout. Then move the still stiffened legs slowly back to the perpendicular with an exhalation.

7. Remain with the legs perpendicular for a few breaths and then repeat the movements by lowering the legs to the right and turning the abdomen to the left. (Plate 128) Stay here also for the same length of time and with an exhalation, come back to the perpendicular legs position and then gently lower the legs to the floor (Plate 98) and relax.



128

EFFECTS

This āsana is good for reducing excess fat. It tones and eradicates sluggishness of the liver, spleen and pancreas. It also cures gastritis and strengthens the intestines. By its regular practice all the abdominal organs are kept in trim. It helps to relieve sprains and catches in the lower back and the hip region.

52| *Supta Pādānguṣṭhāsana*

THIRTEEN*

Supta means lying down. Pāda is the foot. Anguṣṭha means the big toe. Hence the name.

TECHNIQUE

1. Lie flat on the back, stretch both legs and keep the knees tight. (Plate 98)

2. Inhale, raise the left leg from the floor until it is perpendicular. Keep the right leg stretched fully on the floor and rest the right hand on the right thigh.

3. Raise the left arm and catch the left big toe between the thumb and the fore and middle fingers. (Plate 129) Take 3 or 4 deep breaths.

4. Exhale, raise the head and trunk from the floor, bend the left arm at the elbow and pull the left leg towards the head without bending it at the knee. Pull the leg down, lift the head and trunk up together and rest the chin on the left knee. (Plate 130) Stay in this position for about 20 seconds, keeping the right leg fully stretched straight along the floor while breathing normally.

5. Inhale, move the head and trunk back to the floor and the left leg back to the perpendicular. (Plate 129) This completes the first movement.

6. Exhale, release the toe grip, rest the left leg on the floor beside the right one and keep the left hand on the left thigh.

7. Take a few deep inhalations and then repeat on the right, substituting the word 'left' for the word 'right'.

EFFECTS

The legs will develop properly by the practice of this āsana. Persons suffering from sciatica and paralysis of the legs will derive great benefit from it. The blood is made to circulate in the legs and hips where the nerves are rejuvenated. The pose removes stiffness in the hip joints and prevents hernia. It can be practised by both men and women.



129



130



131



132

53| *Bharadvājāsana*

ONE*

Bharadvāja was the father of Droṇa, the military preceptor of the Kauravas and Pāṇḍavas, who fought the great war described in the Mahābhārata. This āsana is dedicated to Bharadvāja.

TECHNIQUE

1. Sit on the floor with the legs stretched straight in front. (Plate 35)

2. Flex the knees, move the legs back and bring both feet to the right side beside the hip.

3. Rest the buttocks on the floor, turn the trunk about 45 degrees to the left, straighten the right arm and place the right hand on the outer side of the left thigh near the left knee. Insert the right hand underneath the left knee, the palm touching the floor.

4. Exhale, turn the left arm from the shoulder behind the back, bend the left elbow and with the left hand clasp the right upper arm above the right elbow.

5. Turn the neck to the right and gaze over the right shoulder. (Plates 131 and 132)

6. Hold the position for half a minute with deep breathing.

7. Loosen the hand grip, straighten the legs and repeat the pose on the other side. Here, bring both the feet beside the left hip, turn the trunk to the right, straighten the left arm, place the left palm underneath the right knee and catch the left upper arm near the elbow with the right hand from behind the back. Stay there for an equal length of time.

EFFECTS

This simple āsana works on the dorsal and lumbar regions of the spine. People with very stiff backs find the other lateral twisting positions extremely difficult. This pose helps to make the back supple. People with arthritis will find it very beneficial.

54| *Marīchyāsana II*

TEN*

This is one of the sitting lateral twisting postures.

TECHNIQUE

1. Sit on the floor with the legs stretched straight in front. (Plate 35)

2. Bend the left knee, place the sole and heel of the left foot flat on the floor. The shin of the left leg should be perpendicular to the floor and the calf should touch the thigh. Place the left heel near the perineum. The inner side of the left foot should touch the inner side of the outstretched right thigh.

3. With an exhalation, turn the spine about 90 degrees to the left, so that the chest goes beyond the bent left thigh and bring the right arm over the left thigh. (Plate 133)

4. Place the right shoulder beyond the left knee and stretch the right arm out forwards by turning the spine still more to the left and stretching the region at the back of the right floating ribs. (Plate 134) Take two breaths.

5. With an exhalation, twist the right arm round the left knee, flex the right elbow and place the right wrist at the back of the waist. Inhale and hold the pose.

6. Exhale deeply and turn the left arm from the shoulder behind the back. Either clasp the left hand behind the back with the right hand or vice versa. (Plates 135 and 136) In the beginning, one finds it difficult to twist the trunk sideways, but with practice, the armpit touches the bent knee. After one has twisted the arm round the knee, one also finds it difficult to clasp the fingers of one hand with the other. Gradually one learns to clasp the fingers, then the palm and lastly to hold the hand at the wrist behind the back.



133



134

7. The right arm should lock the left bent knee tightly. There should be no space between the right armpit and the bent left knee.

8. After clasping the hands at the back, turn the spine still more to the left by tugging at the clasped hands.

9. The whole of the outstretched right leg should remain straight and securely on the floor, but you will not be able to achieve this to start with. Tighten the muscles of the outstretched thigh so that the knee-cap is pulled up towards the thigh and also tighten the muscles of the calf of the outstretched leg. Then the leg will remain firm and extend on the floor.



135



136

10. Stay in this position from half a minute to a minute with normal breathing. The neck may be turned either way to gaze at the toes of the extended leg on the floor or to look over the shoulder.

11. Unclasp the hands at the back and turn the trunk back to its original position. Lower the bent leg and extend it fully on the floor.

12. Then repeat the pose on the other side. This time bend the right knee and place the right foot firmly on the floor so that the right heel touches the perineum and the inner side of the right foot touches the outstretched left thigh. Turn the trunk about 90 degrees to the right so that the left armpit touches the bent right knee. With an exhalation, twist the left arm round the right knee and bring the left hand to the back of the waist. Then throw the right arm behind the back from the shoulder and flexing the right elbow, bring the right hand to the left hand and clasp them. Turn still more to the right and gaze at either the toes of the outstretched left leg or over the right shoulder. Stay on this side also for the same length of time. Unclasp the hands, turn the trunk back to normal, stretch the right leg on the floor and relax.

EFFECTS

By the regular practice of this āsana, splitting backaches, lumbago and pains in the hips disappear rapidly. The liver and the spleen are contracted and so are toned and cease to be sluggish. The muscles of the neck gain power. Sprains in the shoulder and displacement of the shoulder joints are relieved and the shoulder movements become free. The intestines also benefit from this āsana. Its effects will be less on lean persons, for whom there are better poses described later. It also helps to reduce the size of the abdomen.

55| *Ardha Matsyendrāsana*

EIGHT*

Ardha means half. In the Haṭha Yoga Pradīpikā, *Matsyendra is mentioned as one of the founders of Haṭha Vidyā. It is related that once Lord Śiva went to a lonely island and explained to his consort Pārvati the mysteries of Yoga. A fish near the shore heard everything with concentration and remained motionless while listening. Śiva, realizing that the fish had learnt Yoga, sprinkled water upon it, and immediately the fish gained divine form and became Matsyendra (Lord of the Fishes) and thereafter spread the knowledge of Yoga.*

TECHNIQUE

1. Sit on the floor, with the legs stretched straight in front. (Plate 35)

2. Bend the left knee and join the thigh and calf; raise the seat from the floor, place the left foot under the buttocks and sit on the left foot so that the left heel rests under the left buttock. The foot used as the seat should be kept horizontal on the floor, the outer side of the ankle and the little toe of the foot resting on the ground. If the foot is not so placed, it will be impossible to sit on it. Balance securely in this position.

3. Then bend the right knee and lifting the right leg from the floor, place it by the outer side of the left thigh so that the outer side of the right ankle touches the outer side of the left thigh on the floor. Balance in this position, keeping the right shin perpendicular to the floor. (Plate 137)

4. Turn the trunk 90 degrees to the right until the left armpit touches the outer side of the right thigh. Bring the armpit over the right knee. (Plate 138) Exhale, stretch the left arm from the shoulder and twist it round the right knee. Bend the left elbow and move the left wrist to the back of the waist.



137



138

5. The left arm should lock the bent right knee tightly and there should be no space between the left armpit and the bent right knee. To achieve this, exhale and move the trunk forward. Stay in this position and take 2 breaths.

6. Now exhale deeply and swing back the right arm from the shoulder, bend the right elbow, move the right hand behind the waist and either clasp it with the left hand or vice versa. At first you will be able to catch a finger or two. With practice it will be possible to catch the palms and then the wrists behind the back.

7. The neck may be turned to the left and the gaze directed over the left shoulder (Plate 139), or to the right, and the gaze fixed at the centre of the eyebrows. (Plate 140) The spinal twist will be greater if the neck is turned to the left than when to the right.

8. As the diaphragm is squeezed by the spinal twist, the breathing will at first become short and fast. Do not be nervous. After some practice the pose can be held from half a minute to a minute with normal breathing.

9. Release the hands, remove the right foot from the floor and straighten the right and then the left leg.

10. Repeat the pose on the other side and hold it for the same length of time. Here, bend the right leg and sit on the right foot so that the right heel is under the right buttock. Place the left leg over the right leg and rest the left foot on the floor so that the outer side of the left ankle touches the outer side of the right thigh on the floor. Turn the trunk 90 degrees to the left, placing the right armpit over the left knee and twist the right arm round the left knee. Flex the right elbow and move the right hand behind the waist. Hold the pose and take 2 breaths. Again exhale completely and swing the left arm back from the shoulder, bend the left elbow and clasp the hands behind the back at the wrist. Then release and relax.

11. In the beginning it may not be possible to twist either arm round the opposite knee. In that case try and hold the opposite foot, keeping the arm straight at the elbow. It also takes time to clasp the hands behind the back. Gradually, the backward stretch of the arms will increase, and one will be able to catch at first the fingers, next the palms, then the wrist and as the pose is mastered even the forearms above the wrists. Beginners who find it difficult to sit on the foot can sit on the floor.



139



140

EFFECTS

By the practice of this āsana, one derives the benefits mentioned under Marīchyāsana III. (Posture 54 and Plate 135) But here as the range of movement is more intensified, the effects will also be greater. In Marīchyāsana III the upper part of the abdomen is squeezed. Here the lower part of the abdomen has the benefit of the exercise. The prostate and bladder are not enlarged if one practises regularly.

56| Ūrdhva Dhanurāsana

SEVEN*

Ūrdhva means upwards. Dhanu means a bow. In this posture the body is arched back and supported on the palms and soles.

TECHNIQUE

1. Lie flat on the back on the floor. (Plate 48)

2. Bend and raise the elbows over the head, and place the palms under the shoulders. The distance between the palms should not be wider than the shoulders and the fingers should point towards the feet.

3. Bend and raise the knees, then bring the feet nearer until they touch the hips. (Plate 141)

4. Exhale, raise the trunk and rest the crown of the head on the floor. (Plate 142) Take two breaths.

5. Now exhale, lift the trunk and head and arch the back so that its weight is taken on the palms and the soles. (Plate 143)

6. Stretch the arms from the shoulders until the elbows are straightened, at the same time pulling the thigh muscles up. (Plate 144)

7. To get a better stretch, exhale and pull the thigh muscles still higher by lifting the heels off the floor. (Plate 145) Extend the chest, stretch up the sacral region of the spine until the abdomen is taut as a drum and then lower the heels to the floor, maintaining the stretch of the spine.

8. Remain in this position from half a minute to a minute, with normal breathing.

9. With an exhalation, lower the body to the floor by bending the knees and elbows.



141



142



143



144



145

EFFECTS

This āsana is the beginning of the advanced and difficult back-bending poses. It tones the spine by stretching it fully and keeps the body alert and supple. The back feels strong and full of life. It strengthens the arms and wrists and has a very soothing effect on the head. It gives one great vitality, energy and a feeling of lightness.

57| Śavāsana (also called Mṛtāsana)

Śava or Mṛta means a corpse. In this āsana the object is to imitate a corpse. Once life has departed, the body remains still and no movements are possible. By remaining motionless for some time and keeping the mind still while you are fully conscious, you learn to relax. This conscious relaxation invigorates and refreshes both body and mind. But it is much harder to keep the mind than the body still. Therefore, this apparently easy posture is one of the most difficult to master.

TECHNIQUE

1. Lie flat on the back full length like a corpse. Keep the hands a little away from the thighs, with the palms up.

2. Close the eyes. If possible place a black cloth folded four times over the eyes. Keep the heels together and the toes apart.

3. To start with breathe deeply. Later the breathing should be fine and slow, with no jerky movements to disturb the spine or the body.

4. Concentrate on deep and fine exhalations, in which the nostrils do not feel the warmth of breath.

5. The lower jaw should hang loose and not be clenched. The tongue should not be disturbed, and even the pupils of the eyes should be kept completely passive.



146

6. Relax completely and breath out slowly.

7. If the mind wanders, pause without any strain after each slow exhalation.

8. Stay in the pose from 15 to 20 minutes.

9. One is apt to fall asleep in the beginning. Gradually, when the nerves become passive, one feels completely relaxed and refreshed.

When well refreshed one feels energy flow from the back of the head towards the heels and not the other way round. One also feels as if the body is elongated.

EFFECTS

Verse 32 of the First Chapter of the *Haṭha Yoga Pradīpikā* states: 'Lying upon one's back on the ground at full length like a corpse is called Śavāsana. This removes the fatigue caused by the other āsanas and induces calmness of mind.'

Mṛtāsana is thus described in verse 11 of the Second Chapter of the *Gheraṇḍa Saṁhitā*:

'Lying flat on the ground (on one's back) like a corpse is called Mṛtāsana. This posture destroys fatigue, and quiets the agitation of the mind.'

'The mind is the lord of the Indriyas (the organs of senses); the Praṇa (the Breath of Life) is the lord of the mind.' 'When the mind is absorbed it is called Mokṣa (final emancipation, liberation of the soul); when Prāṇa and Manas (the mind) have been absorbed, an undefinable joy ensues.'

Verses 29 and 30, chapter IV, Haṭha Yoga Pradīpikā.

To tame Prāṇa depends upon the nerves. Steady, smooth, fine and deep breathing without any jerky movements of the body soothes the nerves and calms the mind. The stresses of modern civilization are a strain on the nerves for which Śavāsana is the best antidote.

PART III

Prāṇāyāma

HINTS AND CAUTIONS

Read and digest thoroughly the following hints and cautions before attempting the prāṇāyāma techniques mentioned later.

QUALIFICATIONS FOR FITNESS

1. Just as post-graduate training depends upon the ability and discipline acquired in mastering the subject in which one graduated, so prāṇāyāma training demands mastery of āsanas and the strength and discipline arising therefrom.

2. The fitness of the aspirant for training and advancement in prāṇāyāma is to be gauged by an experienced Guru or teacher and his personal supervision is essential.

3. Pneumatic tools can cut through the hardest rock. In Prāṇāyāma the yogi uses his lungs as pneumatic tools. If they are not used properly, they destroy both the tool and the person using it. The same is true of prāṇāyāma.

CLEANLINESS AND FOOD

4. One does not enter a temple with a dirty body or mind. Before entering the temple of his own body, the yogi observes the rules of cleanliness.

5. Before starting prāṇāyāma practices the bowels should be evacuated and the bladder emptied. This leads to comfort in the bandhas.

6. Preferably prāṇāyāma should be practised on an empty stomach, but if this is difficult, a cup of milk, tea, coffee or cocoa may be taken. Allow at least six hours to elapse after a meal before practising prāṇāyāma.

7. Light food may be taken half an hour after finishing prāṇāyāma practices.

TIME AND PLACE

8. The best time for practice is in the early morning (preferably before sunrise) and after sunset. According to the *Haṭha Yoga Pradīpikā,* prāṇāyāma should be practised four times a day, in the early morning, noon, evening and midnight, with 80 cycles at a time (chapter II, verse 11). This is hardly possible in the fast modern age. What is therefore recommended is to practice at least 15 minutes a day, but the 80 cycles are for intensely devoted practitioners, and not for the average householder.

9. The best seasons in which to start the practice are spring and autumn when the climate is equable.

10. Prāṇāyāma should be done in a clean airy place, free from insects. Since noise creates restlessness practice during quiet hours.

11. Prāṇāyāma should be practised with determination and regularity at the same time and place and in the same posture. Variation is permissible only in the type of prāṇāyāma practised, that is to say, if Sūrya Bhedana Prāṇāyāma is done one day, Śitalī may be done the next day and Bhastrikā be done on the third day. Nāḍī Sodhana Prāṇāyāma, however, should be practised daily.

POSTURE

12. Breathing in prāṇāyāma practices is done through the nose only, except in Śitalī and Śitakāri.

13. Prāṇāyāma is best done sitting on the floor on a folded blanket. The postures suitable are Siddhāsana, Vīrāsana, Padmāsana and Baddhakoṇāsana. Any other sitting posture may be taken provided the back is kept absolutely erect from the base of the spine to the neck and perpendicular to the floor. Some types, however, may be done in a reclining position as detailed later.

14. During practice no strain should be felt in the facial muscles, eyes and ears, or in the neck muscles, shoulders, arms, thighs and feet. The thighs and arms should be relaxed deliberately since they are unconsciously tensed during prāṇāyāma.

15. Keep the tongue passive or saliva will accumulate in the mouth. If it does, swallow it before exhalation (rechaka) and not while holding the breath (kumbhaka).

16. During inhalation and retention the rib cage should expand both forwards and sideways, but the area below the shoulder-blades and armpits should only expand forwards.

17. To start with there will be perspiration and trembling which will disappear in course of time.

18. In all the prāṇāyāma practices done in a sitting posture, the head should hang down from the nape of the neck, the chin resting in the notch between the collar-bones on the top of the breast-bone. This chin-lock or Jālandhara Bandha should be used except where specifically stated in the techniques hereafter given.

19. Keep the eyes closed throughout as otherwise the mind will wander after outside objects and be distracted. The eyes, if kept open, will feel a burning sensation, and irritability.

20. No pressure should be felt inside the ear during the practice of prāṇāyāma.

21. The left arm is kept straight, the back of the wrist resting on the left knee. The forefinger is bent towards the thumb, its tip touching the tip of the thumb. This is the Jñāna Mudrā described later in the technique.

22. The right arm is bent at the elbow and the hand is kept on the nose to regulate the even flow of breath and to gauge its subtlety. This is felt through the tips of the ring and little fingers which control the left nostril and through the tip of the thumb which controls the right nostril. Details of the right hand position are discussed in the technique. In some methods of prāṇāyāma both the hands rest on the knees in the Jñāna Mudrā.

23. When a baby learns to walk by itself, the mother remains passive bodily, but alert mentally. In an emergency, as when the child stumbles, her body springs into action to save it from a fall. So also, in the practice of prāṇāyāma the brain is kept passive but alert. Whenever the organs of the body fail to work properly, the watchful brain sends messages of warning. The ear is told to listen for the proper sound of the breath (which is described below). The hand and nose are told to observe the sensitivity of the breath flowing through the nasal passages.

24. It may be asked that if the brain is required to send warnings to the senses, how can one concentrate on prāṇāyāma? A painter absorbed in his work notes various details like perspective and composition, the colour tones and shades, the foreground and background and the strokes of the paint-brush all at once. A musician playing a melody watches his finger movements and sound patterns, the tuning of the instrument and its pitch. Though the artist and the musician are both observing and correcting the details, they are concentrating on their work. So also the yogi observes details like time, posture and an even breath rhythm, and is alert and sensitive to the flow of prāṇa within him.

25. As a careful mother teaches her child to walk carefree, so the careful mind of the yogi teaches the senses to be carefree. By continued practice of prāṇāyāma the senses become free of obsession for the things they once pined for.

26. Each should measure his own capacity when doing prāṇāyāma and not exceed it. This may be gauged as follows: suppose one can with comfort inhale and exhale for 10 seconds each in rhythmic cycles for a given length of time, say 5 minutes. If there is any change in the rhythm in which the period of inhalation decreases, to say 7 or 8 seconds, one has reached one's capacity. To go beyond this point, strains the lungs unduly and brings in its wake a host of respiratory diseases.

27. Faulty practice puts undue stress on the lungs and diaphragm. The respiratory system suffers and the nervous system is adversely affected. The very foundation of a healthy body and sound mind is shaken by faulty practice of prāṇāyāma. Forceful and strained inhalation or exhalation is wrong.

28. Evenness of breathing leads to healthy nerves and so to evenness of mind and temper.

29. Āsanas should never be practised immediately after prāṇāyāma. If prāṇāyāma is done first, allow an hour to elapse before starting āsanas, for the nerves which are soothed in prāṇāyāma are liable to be ruffled by the bodily movement of the āsanas.

30. Prāṇāyāma, however, may be done not less than 15 minutes after mild practice of āsanas.

31. Strenuous āsanas cause fatigue. When exhausted do not practise prāṇāyāma in any sitting posture, as the back cannot stay erect, the body trembles and the mind becomes disturbed. Deep breathing as in Ujjāyī done in a reclining position relieves fatigue.

32. When deep, steady and long breathing cannot be maintained rhythmically, stop. Do not proceed further. The rhythm should be gauged from the nasal sound produced in inhalation ('ssssssa' which sounds like a leak in a cycle tube) and exhalation (the aspirate 'huuuuuuuuum' sound). If the volume of the sound is reduced, stop.

33. Try to achieve an even ratio in inhalation (puraka) and exhalation (rechaka). For example, if one is for 5 seconds during a given continuous cycle, the other should be for the same time.

34. The Ujjāyī and Nāḍī Śodhana types of prāṇāyāma are the most beneficial ones which can be practised by pregnant women, preferably in Baddhakoṇāsana. During pregnancy, however, the breath should never be held without the guidance of an experienced teacher.

35. After completing any prāṇāyāma practice always lie down on the back like a corpse in Śavāsana (Plate 146) for at least 5 to 10 minutes in silence. The mind should be completely switched off and every limb and sense organ completely passive as if dead. Śavāsana after prāṇāyāma refreshes both the body and the mind.

KUMBHAKAS

36. Thorough mastery of inhalation (puraka) and exhalation (rechaka) is essential before any attempt is made to learn antara kumbhaka (retention following inhalation).

37. Bāhya kumbhaka (restraint following exhalation) should not be tried until antara kumbhaka has become natural.

38. During the practice of kumbhaka there is a tendency to draw in air as well as to tighten and loosen the diaphragm and abdominal organs for the sake of increasing the period of retention. This is unconscious and unintentional. Care should be taken to avoid it.

39. If it is found difficult to hold the breath (khumbaka) after each inhalation or exhalation, do some cycles of deep breathing and then practise kumbhakas. For instance, 3 cycles of deep breathing may be followed by one cycle of kumbhaka. Then there should be another 3 cycles of deep breathing followed by a second cycle of kumbhaka, and so on.

40. If the rhythm of inhalation or exhalation is disturbed by holding the breath, lessen the duration of kumbhaka.

41. Persons suffering from eye or ear trouble (like glaucoma and pus in the ear) should not attempt to hold the breath.

42. Sometimes constipation occurs in the initial stages following upon the introduction of kumbhaka. This is temporary and will disappear in due course.

43. The normal rate of breaths per minute is 15. This rate increases when the body is upset by indigestion, fever, cold and cough, or by emotions like fear, anger or lust. The normal rate of breathing is 21,600 breaths inhaled and exhaled every 24 hours. The yogi measures his span of life not by the number of days, but of breaths. Since breathing is lengthened in prāṇāyāma, its practice leads to longevity.

44. Continuous practice of prāṇāyāma will change the mental outlook of the practitioner and reduce considerably the craving of his senses for worldly pleasures like smoking, drinking and sexual indulgence.

45. In the practice of prāṇāyāma the senses are drawn inwards and in the silence of the kumbhaka the aspirant hears his inner voice calling: 'Look within! The source of all happiness is within!' This also prepares him for the next stage of yoga, pratyāhāra, which leads to freedom from the domination and tyranny of the senses.

46. Since the eyes are kept closed throughout the practice of prāṇāyāma, the passage of time is noted by the mental repetition (japa) of a sacred word or name. This repetition of the sacred words or names is the seed (bīja) planted in the yogi's mind. This seed grows and makes him fit for dhyāna or concentration, the sixth stage of Yoga. Ultimately it produces the fruit of samādhi, where there is experience of full consciousness and supreme joy, where the yogi merges with the Maker of the Universe and feels what he can never express – yet cannot entirely conceal. Words fail to convey the experience adequately, for the mind cannot find words with which to describe it. It is a feeling of that peace which passeth all understanding.

TECHNIQUE AND EFFECTS OF PRĀṆĀYĀMA

58| *Ujjāyī Prāṇāyāma*

The prefix ud attached to verbs and nouns, means upwards or superiority in rank. It also means blowing or expanding. It conveys the sense of pre-eminence and power.

Jaya means conquest, victory, triumph or success. Looked at from another viewpoint it implies restraint or curbing.

Ujjāyi is the process in which the lungs are fully expanded and the chest puffed out like that of a proud conqueror.

TECHNIQUE

1. Sit in any comfortable position like Padmāsana (Plate 53), Siddhāsana (Plate 38) or Vīrāsana (Plate 43).

2. Keep the back erect and rigid. Lower the head to the trunk. Rest the chin in the notch between the collar-bones just above the breast-bone. (This is the Jālandhara Bandha. Jāla means a net, web, lattice or a mesh.)

3. Stretch the arms out straight and rest the back of the wrists on the knees. Join the tips of the index fingers to the tips of the thumbs, keeping the other fingers extended. (This position or gesture of the hand is known as the Jñāna Mudrā, the symbol or seal of knowledge. The index finger symbolizes the individual soul and the thumb the Universal Soul. The union of the two symbolizes knowledge.)



147

4. Close the eyes and look inwards. (Plate 147)

5. Exhale completely.

6. Now the Ujjāyi method of breathing begins.

7. Take a slow, deep steady breath through both nostrils. The passage of the incoming air is felt on the roof of the palate and makes a sibilant sound (sa). This sound should be heard.

8. Fill the lungs up to the brim. Care should be taken not to bloat the abdomen in the process of inhalation. (Observe this in all types of Prāṇāyāma.) This filling up is called puraka (inhalation).

9. The entire abdominal area from the pubes up to the breast-bone should be pulled back towards the spine.

10. Hold the breath for a second or two.

11. Exhale slowly, deeply and steadily, until the lungs are completely empty. As you begin to exhale, keep your grip on the abdomen. After two or three seconds of exhalation, relax the diaphragm gradually and slowly. While exhaling the passage of the outgoing air should be felt on the roof of the palate. The brushing of the air on the palate should make an aspirate sound (ha). This exhalation is called rechaka.

12. Wait for a second before drawing a fresh breath. This waiting period is called bāhya kumbhaka.

13. The process described from para. 7 to para. 12 completes one cycle of Ujjāyi Prāṇāyāma.

14. Repeat the cycles for five to ten minutes keeping the eyes closed throughout.

15. Lie on the floor for Śāvāsana. (Plate 146)

16. Ujjāyi Prāṇāyāma may be done without the Jālandhara Bandha even while walking or lying down. This is the only prāṇāyāma which can be done at all times of the day and night.

EFFECTS

This type of prāṇāyāma aerates the lungs, removes phlegm, gives endurance, soothes the nerves and tones the entire system. Ujjāyi without kumbhaka, done in a reclining position, is ideal for persons suffering from high blood pressure or coronary troubles.

59| *Sūrya Bhedana Prāṇāyāma*

Sūrya is the sun. Bhedana is derived from the root bhid meaning to pierce, to break or pass through.

In Sūrya Bhedana Prāṇāyāma, the breath is inhaled through the right nostril. In other words the prāṇa passes through the Piṅgāla or Sūrya nāḍī. A kumbhaka is then performed and the breath is then exhaled through the left nostril which is the path of the Idā nāḍī.

TECHNIQUE

1. Sit in any comfortable position like Padmāsana (Plate 53), Siddhāsana (Plate 38) or Vīrāsana (Plate 43).

2. Keep the back erect and rigid. Lower the head to the trunk. Rest the chin in the notch between the collar-bones just above the breast-bone. (This is Jālandhara Bandha.)

3. Stretch the left arm. Rest the back of the left wrist on the left knee. Perform Jñāna with the left hand (as stated in stage 3 of the technique of Ujjāyi).

4. Bend the right arm at the elbow. Bend the index and middle fingers towards the palm, keeping them passive. Bring the ring and little fingers towards the thumb. (Plate 148)



148

5. Place the right thumb on the right side of the nose just below the nasal bone, the ring and little fingers on the left side of the. nose just below the nasal bone, just above the curve of the fatty tissue of the nostrils above the upper jaw.

6. Press the ring and the little finger to block the left side of the nose completely.

7. With the right thumb, press the fatty tissue on the right side so as to make the outer edge of the right nostril parallel to the lower edge of the cartilage of the septum.

8. The right thumb is bent at the top joint and the tip of the thumb is placed at a right angle to the septum. (Plate 149)

9. Now inhale slowly and deeply controlling the aperture of the right nostril with the tip of the thumb nearer the nail. Fill the lungs to the brim (puraka).

10. Then block the right nostril so that both are now blocked.

11. Hold the breath for about 5 seconds (antara kumbhaka).

12. Keeping the right nostril completely blocked, open the left nostril partially and exhale through it slowly and deeply (rechaka).

13. During the exhalation regulate the rhythmic flow of air from the left nostril by adjusting pressure with the ring and little fingers, so that the outer edge of the left nostril is kept parallel to the septum. The pressure should be exerted from the inner sides of the tips of the fingers (away from the nails).

14. This completes one cycle of Sūrya Bhedana Prāṇāyāma. Continue with more cycles at a stretch from 5 to 10 minutes, according to capacity.

15. All the inhalations in Sūrya Bhedana are from the right nostril and all the exhalations from the left nostril.



149

16. Throughout the process, the passage of air is felt at the tips of the fingers and the thumbs and in the nasal membranes where pressure is applied. The passage of air makes a sound similar to air escaping from a cycle tube. This sound should be maintained constant throughout by varying pressure on the nostrils.

17. The eyes, temples, eyebrows and the skin on the forehead should remain completely passive and show no sign of strain.

18. The mind should be absorbed completely in listening to the proper sound of the passage of air and in maintaining a proper rhythm in breathing.

19. Each inhalation and exhalation should last for the same length of time.

20. The inhalation and the exhalation should not be forced. An even and slow rhythm should be maintained throughout.

21. Lie down in Śavāsana after completing prāṇāyāma. (Plate 146)

EFFECTS

By reason of the pressure on the nostrils, in this Prāṇāyāma the lungs have to work more than in the case of Ujjāyi. In Sūrya Bhedana they filled more slowly, steadily, and fuller than in Ujjāyi. Sūrya Bhedana increases digestive power, soothes and invigorates the nerves, and cleans the sinuses.

NOTE

It often happens that the passages of both the nostrils are not of the same width, one being bigger than the other. In that case the pressure of the fingers has to be adjusted. In some cases the right nostril is completely blocked while the left one is clear. In that case, inhalation may be done only through the left nostril, while exhalation is done only through the right nostril. In course of time due to the manipulation of the fingers the right nostril clears and inhalation through it becomes possible.

Persons suffering from low blood pressure will derive benefit but those with high blood pressure or heart trouble should not hold their breath after inhalation (antara kumbhaka) whilst practising this prāṇāyāma.

60| *Nāḍī Śodhana Prāṇāyāma*

Nāḍī is a tubular organ of the body like an artery or a vein for the passage of prāṇa or energy. A nāḍī has three layers like an insulated electric wire. The innermost layer is called sirā, the middle layer damanī and the entire organ as well as the outer layer is called nāḍī.

Śodhana meaning purifying or cleansing, so the object of Nāḍī Śodhana Prāṇāyāma is the purification of the nerves. A little obstruction in a water pipe can cut off the supply completely. A little obstruction in the nerves can cause great discomfort and paralyse a limb or organ.

TECHNIQUE

1. Follow the technique in paras 1 to 8 of Sūrya Bhedana Prāṇāyāma. (Plate 149)

2. Empty the lungs completely through the right nostril. Control the aperture of the right nostril with the inner side of the right thumb, away from the nail.

3. Now inhale slowly, steadily and deeply through the right nostril, controlling the aperture with the tip of the right thumb near the nail. Fill the lungs to the brim (puraka). During this inhalation the left nostril is completely blocked by the ring and little fingers.

4. After full inhalation, block the right nostril completely with the pressure of the thumb and release the pressure of the ring and little fingers on the left nostril. Readjust them on the outer edge of the left nostril and keep it parallel to the septum. Exhale slowly, steadily and deeply through the left nostril. Empty the lungs completely. The pressure should be exerted from the inner sides of the tips of the ring and little fingers (away from the nails) (rechaka).

5. After full exhalation through the left nostril, change the pressure on it by adjusting the fingers. In the changed position, the tips of the ring and little fingers nearer the nails exert the pressure.

6. Now inhale through the left nostril slowly, steadily and deeply, filling the lungs to the brim (puraka).

7. After full inhalation through the left nostril, block it and exhale through the right nostril, adjusting the pressure of the right thumb on the right nostril as stated in para. 2 above (rechaka).

8. This completes one cycle of Nāḍī Śodhana Prāṇāyāma. Here the rhythm of breathing is as follows:

(a) Exhale through the right nostril.
(b) Inhale through the right nostril.
(c) Exhale through the left nostril.
(d) Inhale through the left nostril.
(e) Exhale through the right nostril.
(f) Inhale through the right nostril.
(g) Exhale through the left nostril.
(h) Inhale through the left nostril.
(i) Exhale through the right nostril.
(j) Inhale through the right nostril . . . and so on.

Stage (a) above is the preparatory one. The first real Nāḍī Śodhana Prāṇāyāma cycle starts at stage (b) and ends at stage (e). The second cycle starts at stage (f) and ends at stage (i). Stage (j) is the safety measure in order to prevent gasping, breathlessness and strain on the heart.

9. Do 8 to 10 cycles at a stretch as described above. This may take 6 or 8 minutes.

10. Inhalation and exhalation from each side should take the same time. In the beginning the duration will be unequal. Persevere until equality is achieved.

11. After achieving mastery over the equal duration and precision over inhalation and exhalation on either side an attempt may be made to retain breath (antara kumbhaka) after inhaling.

12. This precision is only achieved after long practice.

13. Retention should not disturb the rhythm and equality of inhalation and exhalation. If either are disturbed curtail the period of retention or hold the breath on alternate cycles.

14. Do not attempt to hold the breath after exhalation (bāhya kumbhaka) until you have mastered retention after inhalation (antara kumbhaka).

15. Retention and the lengthening of inhalation and exhalation should only be attempted with the help and under the guidance of an experienced Guru.

16. Always conclude by lying down in Śavāsana. (Plate 146)

EFFECTS

The blood receives a larger supply of oxygen in Nāḍī Śodhana than in normal breathing, so that one feels refreshed and the nerves are calmed and purified. The mind becomes still and lucid.

NOTE

In the beginning the body perspires and shakes, while the thigh and arm muscles become tense. Such tension should be avoided.

Persons suffering from high blood pressure or heart trouble should never attempt to hold their breath (kumbhaka). They can practise Nāḍī Śodhana Prāṇāyāma without retention (kumbhaka) with beneficial effect.

Persons suffering from low blood pressure can do this prāṇāyāma with retention after inhalation (antara kumbhaka) *only*, with beneficial effects.

61| *Viloma Prāṇāyāma*

Loma means hair. The particle vi is used to denote negation or privation. Viloma thus means against the hair, against the grain, against the natural order of things.

In Viloma Prāṇāyāma inhalation or exhalation is not one uninterrupted continuous process, but is interrupted by several pauses. For instance, if continuous inhalation to fill the lungs or continuous exhalation to expel the air were to take 15 seconds in each case, in Viloma there would be a pause of about 2 seconds after every third second of inhalation or of exhalation. The process of inhalation or of exhalation is thus lengthened to 25 seconds. The technique given below is in two stages, which are distinct.

TECHNIQUE: STAGE I

1. Viloma Prāṇāyāma can be done either in a sitting posture or while lying down.

2. If done when seated, keep the back erect, lower the head to the trunk so that the chin rests in the notch between the collar-bones on the top of the breast-bone. This is Jālandhara Bandha. Keep the hands in Jñāna Mundra (see p. 119, para 21).

3. Inhale for 2 seconds, pause for 2 seconds holding the breath, again inhale for 2 seconds, again pause for 2 seconds holding the breath, and continue like this until the lungs are completely full.

4. Now hold the breath for 5 to 10 seconds (antara kumbhaka) according to capacity.

5. Exhale slowly and deeply as in Ujjāyi with an aspirate sound (huuuum).

6. This completes one cycle of the first stage of Viloma Prāṇāyāma.

7. Repeat 10 to 15 cycles of this first stage at a stretch.

STAGE II

8. Rest for a minute or two.

9. Then take a deep breath without any pauses as in Ujjāyi with a sibilant sound (sssssssa), keeping the chin on the top of the breast-bone. Fill the lungs completely.

10. Hold the breath from 5 to 10 seconds (antara kumbhaka), keeping the Mūla Bandha grip.

11. Exhale for 2 seconds and pause for 2 seconds. Again exhale for 2 seconds, pause for 2 seconds and continue like this until the lungs are completely emptied.

12. This completes one cycle of the second stage of Viloma Prāṇāyāma.

13. Repeat the second stage of Viloma 10 to 15 times at a stretch.

14. This completes Viloma Prāṇāyāma.

15. Then lie down in Śavāsana. (Plate 146)

EFFECTS

Viloma Prāṇāyāma in the first stage helps those suffering from low blood pressure. In the second stage it benefits persons suffering from high blood pressure.

The second stage of Viloma should only be done when lying down by persons suffering from high blood pressure.

Those suffering from heart complaints should not attempt it until they have mastered the Nāḍī Śodhana and Ujjāyi Prāṇāyāmas.

As a wind drives smoke and impurities from the atmosphere, prāṇāyāma drives away the impurities of the body and the mind. Then, says Patañjali, the DIVINE FIRE within blazes forth in its full glory and the mind becomes fit for concentration (dhāraṇā) and meditation (dhyāna). (*Yoga Sutras*, chapter II, 52 and 53.) This takes a long time. By degrees is the darkness banished by the dawn.



Appendix

Āsana Courses

I am giving the āsanas in a serial order for practice and the possible time it may take to gain control of them.

(The figures within the brackets after the āsanās denote the number.)

1ST AND 2ND WEEK

Tādāsana (1); Utthita Trikoṇāsana (3 and 4); Utthita Pārśvakoṇāsana (5 and 6); Sālamba Sarvāngāsana (102); Halāsana (113); Savāsana (146).

3RD AND 4TH WEEK

Utthita Trikoṇāsana (3 and 4); Utthita Pārśvakoṇāsana (5 and 6); Vīrabhadrāsana I and II (9 and 10); Pārśvottānāsana (13); Sālamba Sarvāngāsana (102); Halāsana (115); Śavāsana (146).

5TH AND 6TH WEEK

Utthita Trikoṇāsana (3 and 4); Utthita Pārśvakoṇāsana (5 and 6); Vırabhadrāsana I and II (9 and 10); Pārśvottānāsana (13); Prasārita Pādottānāsana (17); Stay ½ a minute on each side in all these āsanās. Paripūrna Nāvāsana (36); Sālamba Sarvāngāsana (102); Halāsana (113); Paschimottānāsana (81); Śavāsana (146).

7TH AND 8TH WEEK

Utthita Trikoṇāsana (3 and 4); Utthita Pārśvakoṇāsana (5 and 6); Vīrabhadrāsana I and II (9 and 10); Pārśvottānāsana (13); Prasārita Pādottānāsana (17); Pādānguṣṭhāsana (22); Pāda Hastāsana (24); Uttānāsana (25); Sālamba Sarvāngāsana (102); Halāsana (113); Karṇapīdāsana (114); Daṇḍāsana (35); Paripurṇa Nāvāsana (36); Ardha Nāvāsana (37); Paschimottānāsana (81); Poorvottānāsana (82); Savāsana (146).

9TH WEEK

Consolidate the āsanās and increase the length of stay in all of them.

10TH WEEK

Repeat all the āsanās and do Ujjāyī Prāṇāyāma (Section 58) without sitting in Siddhāsana (38) for 5 minutes and do Śavāsana (146) for 5 minutes.

11TH AND 12TH WEEK

Utthita Trikoṇāsana (3 and 4); Utthita Pārśvakoṇāsana (5 and 6); Vīrabhadrāsana I and II (9 and 10); Pārśvottānāsana (13); Prasārita Pādottānāsana (17) Pādānguṣṭhāsana (22); Pāda Hastāsana (24); Uttānāsana (25); Daṇḍāsana

(35); Paripūrna Nāvāsana (36); Ardha Nāvāsana (37); Mahā Mudrā (61); Jānu Śirsāsana (63); Paschimottānāsana (81); Poorvottānāsana (82); Chaturanga Daṇḍāsana (30) Bhujangāsana (31); Śalabhāsana (26); Dhanurāsana (28) Urdhva Mukha-Śvānāsana (32); Uṣṭrāsana (20); Adho Mukha Śvānāsana (33); Baddha Koṇāsana (51); Sālamba Sarvāngāsana (102); Halāsana (113); Karṇapīdāsana (114); Supta Koṇāsana (115); Pārśva Halāsana (116); Savāsana (146) for 5 minutes; Ujjāyī Prāṇāyāma without retention (Section 58) in Siddhāsana (38) for 5 minutes.

13TH WEEK

Repeat. Do Ujjāyī Prāṇāyāma with inhalation retention (Section 58) in Siddhāsāna (38) or in Śavāsana (146).

14TH TO 18TH WEEK

(Observe the change in the order of the āsanās)
Sālamba Śīrṣāsana (90); Utthita Trikoṇāsana (3 and 4); Utthita Pārśvakoṇāsana (5 and 6); Vīrabhadrāsana I and II (9 and 10); Pārśvottānasana (13); Prasārita Pādottānāsana (17); Pādānguṣṭhāsana (22); Pāda Hastāsana (24); Uttānāsana (25); Mahā Mudrā (61); Jānu Śīrṣāsana (63); Ardha Baddha Padma Paschimottānāsana (66); Paschimottānāsana (81); Paripoorṇa Nāvāsana (36); Ardha Nāvāsana (37); Pūrvottanāsāna (82); Uṣṭrāsana (20); Śalabhāsana (26); Dhanurāsana (28); Chaturanga Daṇḍāsana (30); Bhujangāsana (31); Ūrdha Mukha Svānāsana (32); Adho Mukha Śvānāsana (33); Virāsana (42); Baddha Koṇāsana (51); Sālamba Sarvāngāsana (102); Halāsana (113); Karṇapīdāsana (114); Supta Koṇāsana (115); Pārśva Halāsana (116); Eka Pāda Sarvāngāsana (117); Pārśvaika Pāda Sarvāngāsana (118); Jatara Parivartanāsana (127 and 128); Śavāsana (146). Do Ujjāyī Prāṇāyāma (without inhalation retention) (Section 58) in Siddhāsana (38) or in Vīrāsana (42) or in Baddhakoṇāsana (50).

19TH AND 20TH WEEK

Repeat.

If you now find all the standing āsanās are easy enough, you can do them on alternate days or twice a week. The day you do not do the standing āsanās, devote your time to Ujjāyī Prānāyāma (Section 58) first without inhalation retention for 5 minutes and then with inhalation retention for 5 minutes and then with inhalation retention for 5 minutes.

21ST AND 23RD WEEK

Sālamba Sīrṣāsana (90); if possible Ūrdhva Daṇḍāsana (94); Sālamba Sarvāngāsana (102); Halāsana (113); Karṇapīdāsana (114); Supta Koṇāsana (115); Pārśva Halāsana (116); Ekapāda Sarvangāsana (117); Pārśvaika Pāda Sarvangāsana (118); Supta Pādānguṣṭhāsana (130); Jaṭara Parivartanāsana (127 and 128); Jānu Śīrṣāsana (63); Ardha Baddha Padma Paschimottānāsana (66); Triang Mukhaika-pāda Paschimottānāsana (69); Marichyāsana I (71); Paschimottānāsana (81); Upaviṣṭha Koṇāsana (74); Baddhakoṇāsana (51); Pūrvottānāsana (82); Bharadwājāsana (131 and 132); Virāsana (42);

Chaturangadanḍāsana (30); Bhujangāsana (31); Ūrdhva Mukha Śvānāsana (32); Adho Mukha Śvānāsana (33); Śalabhāsana (26); Dhanurāsana (28); Uṣṭrāsana (20); Uttānāsana (25); Savāsana (146); Ūjjāyī Prānāyāma (Section 58) without inhalation retention in Śavāsana for 5 minutes and with inhalation retention in Siddhāsana (38); or in Padmāsana (53); or in Vīrāsana (42) or in Baddha Koṇāsana (52).

23RD TO 25TH WEEK

Follow the serial order up to Padmāsana (53) as in the 21st week. Then Parvatāsana (54); Matsyāsana (56); Vīrāsana (42); Supta Vīrāsana (49); Bharadwājāsana (131 and 132); Marichyāsana II (135 and 136); Poorvottānāsana (82); Chaturanga Danḍāsana (30); Urdva Mukha Śvānāsana (32); Adho Mukha Śvānāsana (33); Salabhāsana (26); Dhanurāsana (28); Uṣṭrāsana (20); Ūrdhva Dhanurāsana (144); Śavāsana (146); then do Viloma Prāṇāyāma (Section 61) Stage I for 5 minutes and stage II for 5 minutes in Siddhāsana (38) or Padmāsana (53).

When you do the standing positions, eliminate the various movements of Sarvāngāsana cycle and do the rest. For some it is easy to get Padmāsana earlier than the stipulated period and for some it may take a little longer time to get mastery in the position.

26TH TO 30TH WEEK

Sālamba Śīrṣāsana (90); Ūrdhva Danḍāsana (94); Sālamba Sarvāngāsana (102); Halāsana (113); Karṇapīdāsana (114); Supta Koṇāsana (115); Pārśva Halāsana (116); Eka Pāda Sarvāngāsana (117); Pārśvaikapāda Sarvāngāsana (118); Ūrdva Padmāsana in Sarvāngāsana (122); Pinḍāsana in Sarvāngāsana (123); Setu Bandha Sarvāngāsana (121); Jaṭara Parivartanāsana (127 and 128); Paripūrṇa Nāvāsana (36); Ardha Nāvāsana (37); Jānu Śīrṣāsana (63); Ardha Baddha Padma Paschimottānāsana (66); Triang Mikhaika Pāda Paschimottānāsana (69); Marichyāsana I (71); Paschimottānāsana (81); Upaviṣṭha Koṇāsana (74); Baddha Koṇāsana (51); Padmāsana (53); Parvatāsana (54); Baddha Padmāsana (58 and 59); Yoga Mudrāsana (60); Matyāsana (56); Vīrāsana (42); Supta Vīrāsana (49); Bharadwājāsana (131 and 132); Marichyāsana II (135 and 136); Ardha Matsyendrāsana (139 and 140); Adho Mukha Śvānāsana (33); Ūrdhva Mukha Śvānāsana (32); Chaturanga Danḍāsana (30); Śalabhāsana (26); Dhanurāsana (28); Bhujangāsana (31); Poorvottānāsana (82); Uṣṭrāsana (20); Ūrdhva Dhanurāsana (144) for 4 times; Śavāsana (146). Ujjāyī Prāṇāyāma with Antar Kumbhaka (inhalation retention Section 58) and Viloma Prāṇāyāma (Section 61) in Siddhāsana (38); or in Vīrāsana (42) or in Padmāsana (53).

31ST TO 32ND WEEK

Consolidate all the āsanās concentrating on perfection as well as timings. Stay in all the forward bendings for a minute on each āsanā and Paschimottānāsana for 5 minutes.

32ND TO 35TH WEEK

Follow the serial order up to Pinḍāsana in Sarvāngāsana (123) as in the 26th week. Then Pārśva Pinḍāsana in Sarvāngāsana (124 and 125) and continue the serial order from Setu Bandha Sarvāngāsana (121) as in the 26th week up to Śavāsana (146). Do Sūrya Bhedana Prāṇāyāma for 5 minutes and Nāḍi Śodhaṇa Prāṇāyāma 8 cycle only without retention. Sit in Dhyāna (Plate 150) for 3 to 5 minutes.

One Week Course

The following is a course which covers one week and will benefit the body and bring harmony to the mind.

FIRST DAY OF THE WEEK

Sālamba Sīrṣāsana (90) for 10 minutes; Ūrdhva Danḍāsana (94) for 1 minute; Sālamba Sarvāngāsana (10 minutes; Halāsana (113) for 5 minutes; Utthita Trikoṇāsana (3 and 4) for 30 seconds on each side; Utthita Pārśva Konāsana (5 and 6) for 30 seconds on each side; Virabhadrāsana I and II for 20 seconds on each side; Pārśvottānāsana (13) for 1 minute on each side; Prasārita Padottānāsana (17) for 1 minute; Pādānguṣṭāsana (22) for 30 seconds; Pāda Hastāsana (24) for 30 seconds; Uttānāsana (25) for 1 minute; Paschimottānāsana (81) for 5 minutes; Poorvottānāsana (82) for 30 seconds; Marīchyāsana II (135 and 136) for 30 seconds on each side; Ardha Matsyendrāsana (139 and 140) for 30 seconds on each side; Ūrdhva Dhanurāsana for 8 to 10 times staying 15 seconds each time; Śavāsana (146) for 5 minutes. Ūjjāyi Prāṇāyāma (with inhalation retention) (Section 58) for 15 minutes and meditation (150) to the capacity, in any āsana. Again Śavāsana (146) for 5 minutes.

SECOND DAY OF THE WEEK

Sālamba Śīrṣāsana (90) for 10 minutes; Ūrdhva Danḍāsana (94) from 30 seconds to 1 minute; Sālamba Sarvāngāsana (102) for 10 minutes; Halāsana (113) for 5 minutes; Jaṭara Parivartanāsana (127) for half a minute on each side; Supta Pādānguṣṭāsana (130) for 20 seconds on each side; Paripūrṇa Nāvāsana (36) for 1 minute; Ardha Nāvāsana (37) 20 to 30 seconds; Paschimottānāsana (81) for 5 minutes; Bharadwājāsana (131 and 132) for 30 seconds each side; Marīchyāsana II (135 and 136) for 30 seconds each side; Ardha Matyendrāsana (139 and 140) for 30 seconds on each side; Parvātāsana (54) for 1 minute; Vīrāsana (42) for 1 minute; Supta Vīrāsana (49) for 1 minute; Uṣṭrāsana (20 for 30 seconds; Śalabhāsana (26) for 20 to 30 seconds; Dhanurāsana (28) for 30 seconds; Urdhva Mukha Śvānāsana (32) for 20 to 30 seconds; Adho Mukha Śvānāsana (33) for 1 minute; Uttānāsana (25) for 1 to 2 minutes; Śavāsana (146) for 5 minutes and Sūrya Bhedana Prāṇāyāma (Section 59) in Padmāsana (53) or in Siddhāsana (38) or in Vīrāsana (42) for 5 minutes and Nādi Śodhana Prāṇāyāma without retention for 10 minutes and sit in Dhyāna (150) for 2 minutes. Again do Śavāsana (146) for 5 minutes.

THIRD DAY OF THE WEEK

Sālamba Śīrṣāsana (90) for 10 minutes, Ūrdhva Daṇḍāsana (94) for 1 minute; Sālamba Sarvāngāsana (102) for 10 minutes; Halāsana (113) for 5 minutes; Karṇapīdāsana (114) for 30 seconds; Supta Koṇāsana (115) for 30 seconds; Pārsva Halāsana (116) for 30 seconds on each side; Eka Pāda Sarvāngāsana (117) for 30 seconds on each side; Pārśvaikapada Sarvāngāsana (118) for 30 seconds on each side; Setu Bandha Sarvāngāsana (121) from 30 seconds to 2 minutes; Ūrdhva Padmāsana in Sarvāngāsana (122) for 30 seconds; Pinḍāsana in Sarvāngāsana (123) for 30 seconds; Pārśva Pinḍāsana in Sarvāngāsana (124) for 30 seconds on each side; Jaṭara Parivartanāsana (127 and 128) for 30 seconds on each side twice; Supta Pādānguṣṭhāsana (130) for 30 seconds on each side; Marīchyāsana II (135 and 136) from 30 seconds to 60 seconds on each side; Ardha Matsyendrāsana (139 and 140) from 30 seconds to 60 seconds on each side; Paschimottānāsana (81) for 5 minutes; Śavāsana (146) for 5 minutes. Nādiśodhana Prāṇāyāma (Section 60) without Kumbhaka or retention 10 minutes, Sūrya Bhedana Prāṇāyāma (Section 59) 10 cycles; Dhyāna (150) for 5 minutes.

FOURTH DAY OF THE WEEK

Sālamba Śīrṣāsana (90) for 5 minutes; Ūrdhva Daṇḍāsana (94) for 1 minute; Sālamba Sarvāngāsana (102) for 5 minutes; Halāsana (113) for 5 minutes; Mahā Mudra (61) for 30 seconds on each side; Jānu Śīrṣāsana (63) for 1 minute on each side; Ardha Baddha Padma Paschimottānāsana (66 and 67) for 1 minute on each side; Trianga Mukhaika Pāda Paschimottānāsana (69) for 1 minute on each side; Marīchyāsana I (71) for 1 minute on each side; Upaviṣṭha Koṇāsana (74) for 1 minute; Vīrāsana (42) for 1 minute; Supta Vīrāsana for 1 minute; Baddha Padmāsana (58 and 59) for 1 minute; Yoga Mudrāsana (60) for 1 minute; Parvatāsana (54) for 30 seconds; Baddha Koṇāsana (51) for 1 minute; Paschimottānāsana (81) for 5 minutes; Ujjāyi Prāṇāyāma (Section 58) with inhalation retention to capacity for 8 times. Śavāsana (146) with Viloma Prāṇāyāma (Section 61) Stage I for 5 minutes.

FIFTH DAY OF THE WEEK

Sālamba Śīrṣāsana (90) for 10 minutes; Ūrdhva Daṇḍāsana (94) for 1 minute; Sālamba Sarvāngāsana (102) for 10 minutes; Halāsana (113) for 5 minutes; Paschimottānāsana (81) for 5 minutes; Bharadwājāsana (131 and 132) for 30 seconds on each side; Marīchyāsana II (135 and 136) for 30 seconds on each side; Ardha Matsyendrāsana (139 and 140) for 30 seconds on each side; Baddha Padmāsana (58 and 59) for 1 minute; Matsyāsana (56) for 30 seconds; Supta Vīrāsana (49) for 1 minute; Śalabhāsana (26) three times of 15 seconds duration; Dhanurāsana (28) for 20 seconds; Bhujangāsana (31) for 30 seconds; Ūrdhva Mukha Śvānāsana (32) for 30 seconds; Ūrdhva Dhanurāsana (144) for 15 times staying to capacity; Śavāsana (146) with Viloma Prāṇāyāma (Section 61) Stage I and Stage II for 5 minutes each. Dhyāna (150) for 5 minutes.

SIXTH DAY OF THE WEEK

Sālamba Śīrṣāsana (90) for 5 minutes; Utthita Trikoṇāsana (3 and 4) for 15 seconds on each side; Utthita Parśvakoṇāsana (5 and 6) for 15 seconds on each side; Vīrabhadrāsana I and II (9 and 10) for 10 seconds on each side; Pārśvottānāsana (13) for 10 seconds on each side; Prasārita Pādottānāsana (17) for 15 seconds; Uttānāsana (25) for 20 seconds; Sālamba Sarvāngāsana (102) for 5 minutes; Halāsana (113) for 5 minutes; Karṇapīdāsana (114) for 15 seconds; Suptakoṇāsana (115) for 15 seconds; Parśva Halāsana (116) for 15 seconds on each side; Ekapāda Sarvāngāsana (117) for 15 seconds on each side; Pārśvaikapāda Sarvāngāsana (118) for 15 seconds on each side; Setu Bandha Sarvāngāsana (121) for 1 minute; Ūrdhva Padmāsana and Piṇḍāsana in Sarvāngāsana (122 and 123) for 15 seconds; Pārśva Piṇḍāsana (124 and 125) for 15 seconds on each side; Jānu Sīrṣāsana (63); Ardha Baddha Padma Paschimottānāsana (66); Triang Mukhaikapāda Paschimottānāsana (69); Marīchyāsana I (71) all for 15 seconds on each side; Upaviṣtha Koṇāsana (74) for 15 seconds; Paripūrṇa Nāvāsana (36) for 30 seconds; Ardha Nāvāsana (37) for 30 seconds; Baddha Koṇāsana (51) for 30 seconds; Paschimottānāsana (81) for 1 minute; Poorvottānāsana (82) for 15 seconds; Vīrāsana (42) and Supta Vīrāsana (49) for 15 seconds each; Parvatāsana in Padmāsana (54) for 30 seconds; Marichyāsana II (135 and 136) for 30 seconds on each side; Ardha Matyendrāsana (139 and 140) for 30 seconds on each side; Ūrdhva Dhanurāsana (114) for 3 times to capacity; Śavāsana (146) for 5 minutes. Nādi Śodhana Prāṇāyāma (Section 60) 8 cycles with inhalation retention. Dhyāna (150) for 3 minutes.

On Sundays do Nādi Śodhana Prāṇāyāma (Section 60) for 15 minutes with inhalation retention and Viloma Prāṇāyāma (Section 61) Stages I and II for 10 minutes in Śavāsana (146).

If one finds the number of āsanās or the length of time to do them has increased one can adjust according to capacity and the time at one's disposal.

Do Śavāsana (146) after Prāṇāyāma. Do Antarkumbhaka (inhalation retention) only when you have mastered the art of deep inhalation and deep exhalation without any jerks.

Do not do the āsanās and Prāṇāyāma together. You may feel strained and fatigued.

If you do Prāṇāyāma in the mornings then āsanās can be done in the evenings or half an hour after the āsanās.

Never do āsanās immediately after Prāṇāyāma, but one can practise Prāṇāyāma after āsanās if one is still fresh.

Those who wish to prostrate to the Sun (Sūryanamaskar) and to develop the arms and chest, can do the following āsanās in sequence at first for six rounds, increasing the number according to capacity.

	Asanās	*Method of breathing*
1	Tāḍasana (1)	Inhalation
2	Uttānāsana (25)	Exhalation, inhalation with head up
3	Chaturanga Danḍāsana (30)	Exhalation
4	Ūrdhva Mukha Svanasana (32) and go back to	Inhalation
5	Chaturanga Danḍāsana (30)	Exhalation, inhale
6	Adho Mukha Śvānāsana (33) and from here jump to	Exhale
7	Uttānāsana (25) and then back to	Inhalation
8	Tāḍāsana (1)	Exhalation

Table of Asanas

The following table correlates the āsanas with the plates that illustrate them:

NAMES OF ĀSANAS, ETC.	INTERMEDIATE ĀSANAS PLATE NO.	FINAL ĀSANAS PLATE NO.
1. Tāḍāsana	—	1
2. Utthita Trikoṇāsana	2	3 and 4
3. Utthita Pārśvakoṇāsana	—	5 and 6
4. Vīrabhadrāsana I	7 and 8	9
5. Virabhadrāsana II	—	10
6. Pārśvōttānāsana	11 and 12	13 and 14
7. Prasārita Pādottānāsana	15 and 16	17 and 18
8. Ustrāsana	19	20
9. Pādānguṣṭhāsana	21	22
10. Pāda Hastāsana	23	24
11. Uttānāsana	—	25
12. Śalabhāsana	27	26
13. Dhanurāsana	—	28
14. Chaturanga Daṇḍāsana	29	30
15. Bhujangāsana	—	31
16. Ūrdhva Mukha Śvānāsana	—	32
17. Adho Mukha Śvānāsana	—	33 and 34
18. Danḍāsana	—	35
19. Paripūrṇa Nāvāsana	—	36
20. Ardha Nāvāsana	—	37
21. Siddhāsana	—	38
22. Vīrāsana	39 to 41	42 to 45
23. Supta Vīrāsana	46 to 48	49
24. Baddha Koṇāsana	50	51 and 52
25. Padmāsana	—	53
26. Parvatāsana	—	54
27. Matsyāsana	55 and 57	56
28. Baddha Padmāsana	—	58 and 59
29. Yaga Mudrāsana	—	60
30. Mahā Mudrā	—	61
31. Jānu Śīrṣāsana	62	63
32. Ardha Baddha Padma Paschimottānāsana	64 and 65	66 and 67

33. Triang Mukhaikapāda Paschimottānāsana	68	69
34. Marīchyāsana I	70	71
35. Upaviṣṭha Konāsana	72 and 73	74
36. Paschimottānāsana (or Urgrāsana or Brahmacharyāsana)	75 to 80	81
37. Pūrvottānāsana	—	82
38. Sālamba Śīrṣāsana	83 to 89 and 92 to 95, 97	90, 91 and 96
39. Ūrdhva Daṇḍāsana	—	94
40. Sālamba Sarvāngāsana	98 to 101 and 104 to 107	102, 103 and 108
41. Halāsana	109 to 112	113
42. Karṇapīdāsana	—	114
43. Supta Koṇāsana	—	115
44. Pārśva Halāsana	—	116
45. Eka Pāda Sarvāngāsana	—	117
46. Pārśvaika Pāda Sarvāngāsana	—	118
47. Setu Bandha Sarvāngāsana (or Uttāna Mayūrāsana)	119 and 120	121
48. Ūrdhva Padmāsana in Sarvāngāsana	—	122
49. Pindāsana in Sarvāngāsana	—	123
50. Pārśva Piṇḍāsana in Sarvāngāsana	—	124 and 125
51. Jaṭhara Parivartanāsana	126	127 and 128
52. Supta Pādānguṣṭhāsana	129	130
53. Bharadvājāsana	—	131 and 132
54. Marīchyāsana II	133 and 134	135 and 136
55. Ardha Matsyendrāsana	137 and 138	139 and 140
56. Ūrdhva Dhanurāsana	141 to 143 and 145	144
57. Śavāsana	—	146
Prānāyāma		
58. Ujjāyi	—	147
59. Sūrya Bhedana	148	149
60. Nāḍi Śodhana	—	—
61. Viloma	—	—
— Dhyāna	—	150

Glossary

A	Negative particle meaning 'non', as in non-violence.
Abhaya	Freedom from fear.
Abhiniveśa	Instinctive clinging to life and the fear that one may be cut off from all by death.
Abhyāsa	Constant and determined study or practice.
Ādhaḥ	Down, lower.
Adhāra	A support.
Adhimātra	Beyond measure, superior.
Adhimātratama	The supreme one, the highest.
Adho-mukha	Face downwards.
Ādīśvara	The primeval Lord; an epithet of Śiva.
Advaita	Non-duality of the Universal Spirit with the individual soul.
Āgama	Testimony or proof of an acceptable authority when the source of knowledge has been checked and found trustworthy.
Ahaṁkāra	Ego or egotism; literally 'the I-Maker', the state that ascertains 'I know'.
Ahimsā	Non-violence. The word has not merely the negative and restrictive meaning of 'non-killing or non-violence', but the positive and comprehensive meaning of 'love embracing all creation'.
Ajapa-mantra	Unconscious repetitive prayer. Every living creature unconsciously breathes the prayer 'So'ham' (Saḥ = He (the Universal Spirit), aham = am I) with each inward breath, and with each outgoing breath prays 'Haṁsah' (Aham = I am, Saḥ = He (the Universal Spirit)).
Akrodha	Freedom from anger.
Alabhdha-bhūmikatva	Failure to attain firm ground or continuity in practice, feeling that it is not possible to see reality.
Ālamba	Support.
Ālasya	Idleness, sloth, apathy.
Amanaska	The mind which is free from thoughts and desires.
Ananta	Infinite; a name of Viṣṇu as also of Viṣṇu's couch, the serpent Śeṣa.
Anavasthitattva	Instability to continue the practices feeling that it is not necessary to continue as he thinks that he has reached the highest state of Samādhi.

Aṅga	The body; a limb or a part of the body; a constituent part.
Aṅgamejayatva	Unsteadiness or tremor of the body.
Aṅgula	A finger; the thumb.
Aṅguṣṭha	The big toe.
Antara	Within; interior.
Antara Kumbhaka	Suspension of breath after full inhalation.
Antaranga Sādhanā	The inward quest of the soul by Prāṇāyāma and Pratyāhāra whereby the mind is brought under control and the senses are emancipated from the thraldom of objects of desire.
Antarātmā	The Supreme Soul residing in the heart of man.
Antarātmā Sādhanā	The innermost quest of the soul by means of Dhāranā (concentration), Dhyāna (meditation) and Samādhi.
Anumāna	An inference.
Apāna	One of the vital airs which move in the sphere of the lower abdomen and control the function of elimination of urine and faeces.
Aparigraha	Freedom from hoarding or collecting.
Apuṇya	Vice or demerit.
Ardha	Half.
Arjuna	A Pāṇḍava prince, the mighty bowman and hero of the epic Mahābhārata.
Āsana	Posture. The third stage of yoga.
Asmitā	Egotism.
Aṣṭa	Eight.
Aṣṭāṅga Yoga	The eight limbs of Yoga described by Patañjāli.
Asteya	Non-stealing.
Ātmā or *Ātman*	The Supreme Soul or Brahman.
Ātma Ṣaṭkam	A group of six verses written by Śankarāchārya describing the soul in the state of Samadhi.
Ātmīyatā	The feeling of oneness, as a mother's feeling for her children.
Auṁ	Like the Latin word 'Omne', the Sanskrit word 'Auṁ' means 'all' and conveys concepts of 'Omniscience', 'Omnipresence' and 'Omnipotence'.
Avasthā	State or condition of the mind.
Avatāra	Descent, advent or incarnation of God. There are ten avatāras of Viṣṇu: Matsya (the Fish); Kūrma (the Tortoise); Varāha (the Boar), Narasiṁha (the Man-lion); Vāmana (the Dwarf); Paraśurāma; Rāma (hero of the epic Rāmāyaṇa); Krishna (hero of the epic Mahābhārata who related the Bhagavad Gīta); Balarāma and Kalki.
Avidyā	Ignorance.
Avirati	Sensuality.
Āyāma	Length, expansion, extension. It also conveys the idea of restraint, control and stopping.

Baddha	Bound, caught, restrained, firm.
Bahiraṅga Sādhanā	The outward quest of the soul for its Maker. The first three stages of Yoga, namely, Yama, Niyama and Āsana, are the outward quest and keep the seeker in harmony with his fellow men and nature.
Bāhya Kumbhaka	Suspension of breath after full exhalation when the lungs are completely empty.
Bandha	Bondage or fetter. It means a posture where certain organs or parts of the body are contracted and controlled.
Bhagavad Gītā	The Song Divine, the sacred dialogues between Krishna and Arjuna. It is one of the source books of Hindu philosophy, containing the essence of the Upanishads.
Bhagavān	Lord; venerable, holy.
Bhakti	Worship, adoration.
Bhakti-mārga	The way or path to realization through adoration of a personal god.
Bharadvāja	A sage.
Bhaya	Fear.
Bhedana	Piercing, breaking through, passing through.
Bhoga	Enjoyment; an object of pleasure.
Bhoktṛ	One who enjoys or experiences.
Bhrānti-darśana	Erroneous (bhrānti) vision or knowledge (darśana), delusion.
Bhu	Land.
Bhūdāna	The donation of land.
Bhuja	The arm or the shoulder.
Bhujaṅga	A serpent, a snake.
Bhūmikatva	Firm ground.
Bīja	Seed or germ.
Bīja-mantra	A mystical syllable with a sacred prayer repeated mentally during prāṇāyāma, and the seed thus planted in the mind germinates into one-pointedness.
Brahmā	The Supreme Being, the Creator. The first deity of the Hindu Trinity entrusted with the work of creation of the world.
Brahma-vidyā	The knowledge of the Supreme Spirit.
Brahmachāri	A religious student vowed to celibacy and abstinence. One who is constantly moving (chārin) in Brahman (the Supreme Spirit); one who sees divinity in all.
Brahmacharya	A life of celibacy, religious study and self-restraint.
Brahman	The Supreme Being, the cause of the universe, the all-pervading spirit of the universe.
Brahmāṇḍa-prāna	The cosmic breath.
Buddhi	Intellect, reason, discrimination, judgement.

Chandra	The moon
Chatur	The number four.
Chitta	The mind in its total or collective sense, being composed of three categories: (a) Mind, having the faculty of attention, selection and rejection; (b) Reason, the decisive state which determines the distinction between things and (c) Ego, the I-maker.
Chitta-vikṣepa	Distraction, confusion, perplexity.
Chitta-vṛtti	Fluctuations of the mind. A course of behaviour, mode of being, condition or mental state.
Dadhīcha	A celebrated sage, who donated his bones to the gods. From these bones was fashioned the thunderbolt, with which Indra, the king of the gods, slew the demon Vṛtra.
Dakṣa	A celebrated prajāpati, a lord of created beings.
Dakṣiṇa	The right side.
Damanī	A layer with a nāḍī or channel for the passage of energy.
Dānava	A demon.
Daṇḍa	A staff.
Daurmanasya	Despair, dejection.
Deva	A god.
Devadatta	One of the vital airs which provides for the intake of extra oxygen in a tired body by causing a yawn.
Dhanu	A bow.
Dhāraṇā	Concentration or complete attention. The sixth stage of Yoga mentioned by Patañjali.
Dhasañjaya	One of the vital airs which remains in the body even after death, and sometimes bloats up a corpse.
Dhṛ	To hold, to support, to maintain.
Dhyāna	Meditation. The seventh stage of Yoga mentioned by Patañjali.
Droṇa	The preceptor of the Pāṇḍava and Kaurava princes in the arts of war, especially archery. He was the son of the sage Bharadvāja.
Duḥkha	Pain, sorrow, grief.
Dveṣa	Hate, dislike, repugnance.
Dwi-hasta	Two hands.
Eka	One, single, alone, only.
Eka-tattvābhyāsa	The study of the single element, the Supreme Spirit that pervades the innermost self of all beings.
Ekāgra	(Ek = one; agra = foremost.) Fixed on one object or point only; closely attentive, where the mental faculties are all focused on a single object.
Ekāgratā	One-pointedness.

Gaṇa	A troop of demigods, who were Śiva's attendants.
Gaṅgā	The river Ganges, the most sacred river in India.
Gheraṇḍa	A sage, the author of Gheraṇḍa-Saṁhitā, a classical work on Haṭha-yoga.
Gheraṇḍa-Saṁhitā	*See* above.
Gu	First syllable in the word 'Guru', meaning darkness.
Gulma	The spleen.
Guṇa	A quality, an ingredient or constituent of nature.
Guṇātīta	One who is freed from and gone beyond or crossed the three guṇas of Sattva, Rajas and Tamas.
Guru	Spiritual preceptor, one who illumines the darkness of spiritual doubt.
Ha	First syllable of the word 'Haṭha', which is composed of the syllables 'ha' meaning the sun, and 'ṭha' meaning the moon. The object of Haṭha-yoga is to balance the flow of solar and lunar energy in the human system.
Hala	A plough.
'Haṁsaḥ'	'I am He, the Universal Spirit', the unconscious repetitive prayer that goes on with each exhalation within every living creature throughout life.
Hanumān	A powerful monkey chief of extraordinary strength and prowess, whose exploits are celebrated in the epic Rāmāyana. He was the son of Añjana and Vāyu, the god of wind.
Hasta	The hand.
Haṭha	Force. The word 'hatha' is used adverbially in the sense of 'forcibly' or 'against one's will'. Haṭha-yoga is so called because it prescribes rigorous discipline, in order to find union with the Supreme.
Haṭha-vidyā	The science of Haṭha-yoga.
Haṭha-yoga	The way towards realization through rigorous discipline.
Hatha-yoga-pradīpikā	A celebrated textbook on Haṭha-yoga written by Svātmārāma.
Himālaya	The abode of ice and snow. Name of the mountain ranges on the northern borders of India.
Hiṁsā	Violence, killing.
Iḍā	A nāḍī, a channel of energy starting from the left nostril, then moving to the crown of the head and thence descending to the base of the spine. In its course it conveys lunar energy and so is called chandra nāḍī (channel of the lunar energy).
Indra	Chief of the gods. The god of thunder, lightning and rain.

Indriya	An organ of sense.
Indriya-jaya	Conquest, restraint or mastery of the senses by controlling desires.
Īśvara	The Supreme Being, God.
Īśvara-praṇidhāna	Dedication to the Lord of one's actions and one's will.
Jāgrata-avasthā	The complete awareness of the state of the mind.
Jālandhara-bandha	Jālandhara is a posture where the neck and throat are contracted and the chin is rested in the notch between the collar-bones at the top of the breast-bone.
Jamunā	A tributary of the Ganges.
Jānu	The knee.
Japa	A repetitive prayer.
Jatara-parivartana	An āsana, in which the abdomen is made to move to and fro.
Jaṭhara	The abdomen, stomach.
Jaya	Conquest, victory. It also means control, mastery.
Jīva	A living being, a creature.
Jīvana	Life.
Jīvana-mukta	A person who is emancipated during his lifetime by true knowledge of the Supreme Spirit.
Jīvana-mukti	The emancipated state.
Jīvātmā	The individual or personal soul.
Jñāna	Sacred knowledge derived from meditation on the higher truths of religion and philosophy, which teaches a man how to understand his own nature.
Jñāna-mārga	The path of knowlege by which man finds realization.
Jñāna-mudrā	The gesture of the hand where the tip of the index finger is brought in contact with the tip of the thumb, while the remaining three fingers are kept extended. The gesture is a symbol of knowledge (jñāna). The index finger is the symbol of the individual soul, the thumb signifies the Supreme Universal Soul, and the union of these two symbolizes true knowledge.
Jñānendriya	Hearing, touch, sight, taste and smell.
Kailāsa	A mountain peak in the Himālayas, considered as tne abode of Śiva.
Kaivalya	Final emancipation.
Kaivalya-pāda	The fourth and last part of Patañjāli's Yoga Sūtra, dealing with Absolution.
Kālidāsa	The most renowned dramatist and poet in Sanskrit literature, whose work 'Śakuṅtalā' is universally respected.
Kapila	A sage, the founder of the Sāankhya system, one of the six orthodox systems of Hindu philosophy.
Karma	Action.

Karma-mārga	The way of an active man towards realization through action.
Karma-yoga	The achievement of union with the Supreme Universal Soul through action.
Karmendriya	Organs of excretion, generation, hands, feet and speech.
Karṇa	The ear, also one of the heroes in the Mahābhārata.
Karṇa-pīdā	Pressure around the ear.
Karuṇā	Compassion, pity, tenderness. It also implies devoted action to alleviate the suffering of the afflicted ones.
Kaṭhopaniṣad	One of the principal Upanishads in verse and in the form of a dialogue between the seeker Nachiketā and Yama, the god of Death.
Kauravas	Descendants of Kuru, who fought the fratricidal Mahābhārata war with their cousins the Pāṇḍavas.
Kāyā	The body.
Kāyika	Relating to the body.
Kevala	Whole, entire, absolute, perfect, pure.
Klésa	Pain, anguish, suffering.
Koṇa	An angle.
Krishṇa	The most celebrated hero in Hindu mythology. The eighth incarnation of Viṣṇu.
Kṛkara	Name of one of the subsidiary vital airs, whose function is to prevent substances going up the nasal passages and throat by bringing on sneezes and coughing.
Kṛta	Name of first of the four ages of the world of men.
Kṣatriya	A member of the warrior class.
Kṣipta	Distracted, neglected.
Kumbha	A water pot, a pitcher, a chalice.
Kumbhaka	Kumbhaka is the interval of time or retention of breath after full inhalation or after full exhalation.
Kuṇḍalinī	The Kuṇḍalinī (kuṇḍala = the coil of a rope; Kuṇḍalinī = a coiled female serpent) is the divine cosmic energy. This force or energy is symbolized as a coiled and sleeping serpent lying dormant in the lowest nerve centre at the base of the spinal column, the Mūlādhāra-chakra. This latent energy has to be aroused and made to ascend the main spinal channel, the Suṣumṇa piercing the chakras right up to the Sahasrāra, the thousand-petalled lotus in the head. Then the Yogi is in union with the Supreme Universal Soul.
Lac	100,000.
Laya	Dissolution; absorption of the mind, devotion.
Laya-yoga	The achievement of union with the Supreme Universal Soul through adoration or devotion.
Lobha	Greed.
Loma	Hair.

Madhyama	Middling, average, mediocre.
Mahā	Great, mighty, powerful, lofty, noble.
Mahābhārata	The celebrated epic composed by Vyāsa. It includes the Bhagavad Gītā.
Maharṣi	A great sage.
Maitri	Friendliness coupled with a feeling of oneness.
Man	To think.
Manas	The individual mind having the power and faculty of attention, selection and rejection. The ruler of the senses.
Mānasika	Of the mind, mental.
Manomanī	The state of samādhi.
Mantra	A sacred thought or a prayer.
Manu	Name of the father of the human race.
Mārga	A way, road, path.
Marīchi	Name of one of the sons of Brahmā. He was a sage and the father of Kaśyapa, q.v.
Matsya	A fish.
Matsyendra	One of the founders of Haṭha-yoga.
Moha	Delusion, infatuation.
Mokṣa	Liberation, final emancipation of the soul from recurring births.
Mṛdu	Soft, gentle, mild.
Mṛta	Dead, a corpse.
Mūdha	Perplexed, confounded, foolish, dull, stupid.
Muditā	Joy, delight.
Mudrā	A seal: a sealing posture.
Mukha	Face, mouth.
Mukta	Liberated.
Mukti	Release, liberation, final absolution of the soul from the chain of birth and death.
Muṇḍakopaniṣad	Name of a Upanishad dealing with the mystic syllable Auṁ.
Nachiketā	Name of the seeker and one of the principal characters in the Kaṭhopaniṣad. His father Vājaśravas wanted to give away all his possessions so as to acquire religious merit. Nachiketā felt puzzled and asked his father again and again: 'To whom will you give me?' His father said: 'I give you to Yama (the god of Death).' Nachiketā went down to the realm of Death and obtained three boons, the last of which was the knowledge of the secret of life after death. Yama tried to divert Nachiketā from obtaining his wish by offering the greatest earthly pleasures, but Nachiketā was not swayed from his purpose and ultimately Yama gave him the knowledge desired.
Nāda	Inner mystical sound.

Nāḍī	A tubular organ of the subtle body through which energy flows. It consists of three layers, one inside the other, like insulation of an electric wire. The innermost layer is called the 'sirā' and the middle layer 'damanī'. The entire organ as well as the outer layer is called 'nāḍī'.
Nāḍī-śodhana	The purification or cleansing of the nāḍīs.
Nāga	One of the subsidiary vital airs which relieves abdominal pressure, causing one to belch.
Nāva	A boat.
'Neti Neti'	'Not This! Not this!' The experience of samādhi is not like other experiences, which can be described in words. About it the sages say 'It is not this! It is not this!', for speech fails to convey the feeling of joy and peace experienced in that state.
Nirālamba	Without support.
Niranjana	Unstained; free from falsehood, pure.
Nirodha	Restraint, suppression.
Niruddha	Restrained, checked, controlled.
Niyama	Self-purification by discipline. The second stage of yoga mentioned by Patañjāli.
Pāda	The foot or leg; also part of a book.
Pādāṅguṣṭha	The big toe.
Padma	A lotus.
Pāṇḍava	Name of any of the five sons of Pāṇḍu, the heroes in the Mahābhārata.
Paramapāda	The highest step, the supreme state, final beatitude.
Paramātmā	The Supreme Spirit.
Parigraha	Hoarding.
Paripūrṇa	Entire, complete.
Parivartana	Turning round, revolving.
Parivṛtta	Turned around, revolved.
Parivṛttaika-pāda	With one leg turned around.
Pārśva	The side, flank; lateral.
Parśvaika-pāda	With one leg turned sideways.
Parvata	A mountain.
Pārvati	A goddess, consort of Śiva, daughter of Himālaya.
Paśchima	West; the back of the whole body from head to heels.
Paśchimottana	Intense stretch of the back side of the body from the nape to the heels.
Patañjali	The propounder of Yoga philosophy. He was the author of the Yoga Sūtras, the Mahābhāśya (a classical treatise on grammar) and a treatise on medicine.
Pīḍā	Pain, suffering, pressure.
Piṇḍa	The foetus or embryo, the body.
Piṇḍa-prāṇa	The individual breath, as contrasted with the cosmic or Universal breath.

Piṅgalā	A nāḍī or channel of energy, starting from the right nostril, then moving to the crown of the head and thence downwards to the base of the spine. As the solar energy flows through it it is also called the sūrya-nāḍī. Piṅgalā means tawny or reddish.
Plīhā	The spleen.
Prajñā	Intelligence, wisdom.
Prajñātmā	The intelligential self.
Prakṛti	Nature, the original source of the material world, consisting of three qualities, sattva, rajas and tamas.
Pramāda	Indifference, insensibility.
Pramāṇa	A standard or ideal; authority.
Prāṇa	Breath, respiration, life, vitality, wind, energy, strength. It also connotes the soul.
Prāṇa-vāyu	The vital air which pervades the entire human body. It moves in the region of the chest.
Praṇava	Another word for the sacred syllable Auṁ.
Prāṇāyāma	Rhythmic control of breath. The fourth stage of yoga.
Praṇidhāna	Dedication.
Prasārita	Spread out, stretched out.
Praśvāsa	Expiration.
Pratyāhāra	Withdrawal and emancipation of the mind from the domination of the senses and sensual objects. The fifth stage of yoga.
Pratyakṣa	Direct evidence.
Puṇya	Virtue, merit, righteous, just, good.
Puraka	Inhalation.
Pūrṇatā	Fullness, perfection.
Pūrva	East. The front of the body.
Pūrvottana	The intense stretch of the front side of the body.

Rāga	Love, passion, anger.
Rāja	A king, a ruler.
Rāja-mārga	The royal road to self-realization through the control of the mind.
Rāja-yoga	The achievement of union with the Supreme Universal Spirit, by becoming the ruler of one's own mind by defeating its enemies. The chief of these enemies are: Kāma (passion or lust), krodha (anger or wrath), lobha (greed), moha (delusion), mada (pride) and matsara (jealousy or envy). The eightfold yoga of Patañjāli shows the royal road (rāja-mārga) for achieving this objective.
Rāja-yogī	One who has complete mastery over his mind and self. One who has conquered himself.
Rajas	Mobility or activity; one of the three qualities or constituents of everything in nature.
Rajo-guṇa	The quaity of mobility or activity.

Rechaka	Exhalation, emptying of the lungs.
Rṣi	An inspired sage.
Ṙu	The second syllable in the word 'guru', meaning light.
Sādhaka	A seeker, an aspirant.
Sādhanā	Practice, quest.
Sādhana-pāda	The second part of Patañjāli's Yoga Sūtras, dealing with the means.
Sahajāvasthā	The natural state of the soul in samādhi.
Śalabha	A locust.
Sālamba	With support.
Sama	Same, equal, even, upright.
Sama-sthiti	Standing still and straight.
Samādhi	A state in which the aspirant is one with the object of his meditation, the Supreme Spirit pervading the universe, where there is a feeling of unutterable joy and peace.
Samādhi-pāda	The first part of Patañjali's Yoga Sūtras, dealing with the state of samādhi.
Samāna	One of the vital airs, whose function is to aid digestion.
Saṁśaya	Doubt.
Saṁskāra	Mental impression of the past.
Śankarāchārya	A celebrated teacher of the doctrine of Advaita.
Ṣaṇmukhī-mudrā	A sealing posture where the apertures in the head are closed and the mind is directed inwards to train it for meditation.
Santoṣa	Contentment.
Saraswatī	A tributary of the Ganges. Also the name of the goddess of speech and learning, the consort of Brahmā.
Sarva	All, whole.
Sarvāṅga	The whole body.
Satī	The daughter of Dakṣa Prajāpati. She immolated herself for the insult offered to her husband Śiva by her father, and was then reborn as the daughter of Himālaya and again won Siva as her husband. She was the mother of Kārtikeya (the god of war) and of Ganapati (the god of learning, wisdom and good luck).
Sattva	The illuminating, pure and good quality of everything in nature.
Sattva-guṇa	The quality of goodness and purity.
Śaucha	Purity, cleanliness.
Śava	A corpse, a dead body.
Setu	A bridge.
Setu-bandha	The construction of a bridge. Name of an āsana in which the body is arched.
Siddha	A sage, seer or prophet; also a semi-divine being of great purity and holiness.

Sirā	A tubular organ in the body. *See* nāḍī.
Śirṣa	The head.
Śiṣya	A pupil, a disciple.
Śiva	Name of the third god of the Hindu Trinity, who is entrusted with the task of destruction.
Śiva-saṁhitā	A classical textbook on Haṭha-yoga.
Smrti	Memory, a code of law.
Śodhana	Purification, cleansing.
'Soham'	'He am I'; the unconscious repetitive prayer that goes on with every inhalation within every living creature throughout life.
Śoka	Anguish, distress, grief, sorrow.
Śraddhā	Faith, trust.
Steya	Theft, robbery.
Sthita-prajñā	One whose wisdom is firmly established and does not waver; one who is unmoved by the dualities of pleasure and pain, gain and loss, joy and sorrow, victory and defeat.
Sthiti	Stability.
Styāna	Languor, sloth.
Sukha	Happiness, delight, joy, pleasure, comfort.
Sumanasya	Benevolence.
Śunyāśūnya	The mind is in a state of void (Śūnya) and yet a state that is not void (aśūnya).
Supta	Sleeping.
Sūrya	The sun.
Sūrya-bhedana	Piercing or passing through (bhedana) the sun. Here the inhalation is done through the right nostril, from where the Piṅgalā-nāḍī or Sūrya-nāḍī starts. Exhalation is done through the left nostril, from where the Iḍā-nāḍī or Chandra-nāḍī starts.
Sūrya-nāḍī	The nāḍī of the sun. Another name for Piṅgalā-nāḍī.
Suṣumṇā	The main channel situated inside the spinal column.
Suṣupti-avasthā	The state of the mind in dreamless sleep.
Sva	One's own, innate, vital force, soul, self.
Svādhyāya	Education of the self by study of divine literature.
Śvāna	A dog.
Svapnāvasthā	The state of the mind in a dream.
Śvāsa	Inspiration.
Śvāsa-praśvāsa	Heaving and sighing.
Svātmārāma	The author of the Haṭha-yoga-pradīpikā, a classical textbook on Haṭha-yoga.
Tāḍa	A mountain.
Tamas	Darkness or ignorance, one of the three qualities or constituents of everything in nature.
Tamo-guṇa	The quality of darkness or ignorance.
Tan or *Tān*	To stretch, extend, lengthen out.

Tap	To burn, to blaze, to shine, to suffer pain, to be consumed by heat.
Tapas	A burning effort which involves purification, self-discipline and austerity.
'Tat twam asi'	'Thou that art.' The realization of the real nature of man as being part of the divine, and of the divinity within himself, which liberates the human spirit from the confines of his body, mind, intellect and ego.
Tattva	The true or first principle, an element or primary substance. The real nature of the human soul or the material world and the Supreme Universal Spirit pervading the universe.
Tattva-jñāna	The knowledge of the true principle.
Tejas	Lustre, brilliance, majesty.
Ṭha	The second syllable of the word 'haṭha'. The first syllable 'ha' stands for the sun, while the second syllable 'ṭha' stands for the moon. The union of these two is Haṭha-yoga.
Tirieng	Horizontal, oblique, transverse, reverse and upside down.
Tri	Three.
Triaṅga	Three limbs.
Trikoṇa	A triangle.
Tṛṣṇā	Thirst, longing, desire.
Turīyāvasthā	The fourth state of the soul, combining yet transcending the other three states of waking, dreaming and sleeping state – the state of samādhi.
Ubhaya	Both.
Udāna	One of the vital airs which pervades the human body, filling it with vital energy. It dwells in the thoracic cavity and controls the intake of air and food.
Ugra	Formidable, powerful, noble.
Ujjāyi	A type of prāṇāyāma in which the lungs are fully expanded and the chest is puffed out.
Unmanī	The state of samādhi.
Upaniṣad	The word is derived from the prefixes 'upa' (near) and 'ni' (down), added to the root 'sad' (to siṭ). It means sitting down near a Guru to receive spiritual instruction. The Upanishads are the philosophical portion of the Vedas, the most ancient sacred literature of the Hindus, dealing with the nature of man and the universe and the union of the individual soul or self with the Universal Soul.
Upaviṣṭha	Seated.
Upekṣā	Disregard. Upekṣā is not only a feeling of disdain for a person who has fallen into vice or a feeling of

	indifference or superiority towards him. It is also a self-examination to find out how one would have behaved in like circumstances and also how far he is responsible for the state of the fallen one and to help him on to the right path.
Ūrdhva	Raised, elevated, tending upwards.
Ūrdhva-mukha	Face upwards.
Uṣṭra	A camel.
Ut	A particle, denoting intensity.
Uttāna	An intense stretch.
Utthita	Raised up, extended, stretched.
Vāchā	Speech.
Vāchika	Relating to speech, oral.
Vairāgya	Absence of worldly desires.
Vajra	A thunderbolt, the weapon of Indra.
Valli	A chapter of the Upanishads.
Vāma	The left side.
Vāsanā	A celebrated sage, author of several Vedic hymns.
Vāyu	The wind, the vital airs.
Veda	The sacred scriptures of the Hindus, revealed by the Supreme Being.
Vibhūti	Might, power, greatness.
Vibhūti-pāda	The third part of the Yoga Sūtras of Patañjāli, dealing with the powers that the yogi comes across in his quest.
Vidyā	Knowledge, learning, lore, science.
Vikalpa	Fancy, resting merely on verbal expression, without any factual basis.
Vikṣepa	Distraction, confusion, perplexity.
Vikṣipta	Agitated state of the mind.
Viloma	Against the hair, against the order of things. The particle 'vi' denotes negation or privation.
Viparyaya	A mistaken view, which is later observed to be such, after study.
Vīra	A hero, brave.
Vīrabhadra	A powerful hero created out of Śiva's matted hair.
Virochana	A demon prince, who was the son of Prahlāda and the father of Bali.
Vīrya	Vigour, strength, virility, enthusiasm.
Viṣama-vṛtti	Uneven or vehement movement while breathing.
Viṣṇu	The second deity of the Hindu trinity, entrusted with the preservation of the world.
Viśvāmitra	A celebrated sage.
Vitasti	A span.
Vṛkṣa	A tree.
Vṛt	To turn, to revolve, to roll on.

Vṛtti	A course of action, behaviour, mode of being, condition or mental state.
Vyādhi	Sickness, disease, illness.
Vyāna	One of the vital airs, which pervades the entire body and circulates the energy derived from food and breathing all over the body.
Yama	The god of death. Yama is also the first of the eight limbs or means of attaining yoga. Yamas are universal moral commandments or ethical disciplines transcending creeds, countries, age and time. The five mentioned by Patañjali are: non-violence, truth, non-stealing, continence and non-coveting.
Yoga	Union, communion. The word 'yoga' is derived from the root 'yuj' meaning to join, to yoke, to concentrate one's attention on. It is the union of our will to the will of God, a poise of the soul which enables one to look evenly at life in all its aspects. The chief aim of yoga is to teach the means by which the human soul may be completely united with the Supreme Spirit pervading the universe and thus secure absolution.
Yoga-mudrā	A posture.
Yoga Sūtra	The classical work on yoga by Patañjali. It consists of 185 terse aphorisms on yoga and it is divided into four parts dealing respectively with samādhi, the means by which yoga is attained, the powers the seeker comes across in his quest and the state of absolution.
Yogi or *Yogin*	One who follows the path of yoga.
Yoni-mudrā	Yoni means the womb or source and mudrā a seal. Yoni-mudrā is a sealing posture where the apertures of the head are closed and the aspirant's senses are directed within to enable him to find out the source of his being.
Yuga	An age.
Yuj	To join, to yoke, to use, to concentrate one's attention on.
Yukta	One who has attained communion with the Supreme Spirit pervading the universe.

International Addresses

Main Associations and Centres Worldwide

AUSTRALIA

BKS Iyengar Association of Australasia
1 Rickman Avenue
Mosman 2088
NSW

Bondi Junction School of Yoga
First Floor
2A Waverley Street
Bondi Junction
Sydney 2022
NSW

CANADA

BKS Iyengar Yoga Association
27–F Meadowlark Village
Edmonton
Alberta
T5R 5X4

Centre de Yoga Iyengar de Montreal
919 Mont-Royal Oest
Montreal
PQ H2J 1X3

BKS Iyengar Yoga Association
PO 65694, Station F
Vancouver, BC
V5N 5K7

Victoria Yoga Centre
3918 Olympic View Drive
RR4, Victoria, BC
V9B 5T8

BKS Iyengar Yoga Association of Ontario
c/o 85 Glenforest Road
Toronto, Ontario
M4N 2A1

FRANCE

Centre de Yoga Iyengar de Paris
also Association Francaise de Yoga Iyengar
35 ave Victor Hugo
75116 Paris

Centre de Yoga Iyengar de Lyon
Clos de Fourviere
40 Rue Roger Rodisson
69005 Lyon

Centre de Yoga Iyengar de Montpellier
5 bis Enclos Tissie Sarrus
34000 Montpellier

For classes in Marseille, Strasbourg, Toulouse, Nice, Tours, Grenoble, Nantes and Rouen, contact the Centre de Yoga Iyengar de Paris.

INDIA

R.I.M. Yoga Institute
1107 B/1 Shivajinagar
Pune 411 016

ITALY

Associazione Light on Yoga Italia
Via delle Route 49
50129 Firenze

JAPAN

Japanese Iyengar Yoga Association
Sembon Minami 557
Nishinari-Ku
Osaka Shi, Osaka Fu
Japan T557

HOLLAND

Iyengar Yoga Centre of Amsterdam
also Iyengar Yoga Association of Holland
8 Karthuizersdwars St
1015 KP Amsterdam

NEW ZEALAND

Information available from BKS Iyengar Association of Australasia (*see* Australia)

RUSSIA

Iyengar Yoga Centre of Moscow
c/o 16–49 Leninsky Prospect
Moscow 117 071

SOUTH AFRICA

BKS Iyengar Institute
58 Trelawney Road
Pietermaritzburg
Natal 3201

Iyengar Yoga Association of South Africa
PO Box 78648
Sandton 2146

SPAIN

EYI—Centro de Yoga Iyengar de Madrid
Carrera de San Jeronimo 16
5 28014
Madrid

Scola de Yoga
C—Hortes 2
17600 Figueres

UK

Manchester & District Institute of Iyengar Yoga
134 King Street
Dukinfield
Tameside
Greater Manchester

Edinburgh Iyengar Yoga Centre
195 Bruntsfield Place
Edinburgh EH10 4DQ

Contact the above for information about other local Institutes:

Birmingham Iyengar Yoga Institute
Bradford & District Institute of Iyengar Yoga
Bristol Iyengar Yoga Institute
Cambridge Iyengar Yoga Institute
Hampshire Iyengar Yoga Association
Light on Yoga Association
Liverpool & District Institute of Iyengar Yoga
North East Institute of Iyengar Yoga
Nottingham Iyengar Yoga Institute
Oxford Region Iyengar Yoga Group
South West Iyengar Yoga Institute
Sussex Iyengar Yoga Institute

USA

BKS Iyengar Yoga Institute of Los Angeles
also BKS Iyengar Yoga National Association of the United States, Incorporated
and Iyengar Yoga Association of Southern California
8223 W. Third Street
Los Angeles
CA 90038

Iyengar Yoga Institute of San Francisco
also Iyengar Yoga Association of Northern California
2404–27th Avenue
San Francisco
CA 94116

Ann Arbor 'Y' Iyengar Yoga
350 S 5th Avenue
Ann Arbor
MI 48014

Iyengar Yoga Institute of New York
also BKS Iyengar Yoga Association of Greater New York
27 W 24th Street
Suite 800
New York
NY 10011

Iyengar Yoga Association of Massachusetts, Inc.
240–A Elm Street
Somerville
MA 02114

Iyengar Yoga Association of Minnesota
Box 10381
Minneapolis
MN 55458–3381

Iyengar Yoga Assocaiation of Wisconsin
Route 2
Box 70E
La Crosse
WI 54601

Iyengar Yoga Association of the Midwest Bioregions
310 Gralake
Ann Arbor
MI 48103

Iyengar Yoga Association of Northern Michigan
2319 W. Midland Road
Auburn
MI 48611

Index

abhaya 15
abhiniveśa 6
abhyāsa 3, 10, 29
action 2, 4, 9–13, 20, 27, 33
adoration 18, 20, 27, 31
Advaita 60
āgama 5
ahaṁkāra 1, 31
ahiṁsā 14, 20
ajapa-mantra 25
akrodha 15
Alabhdha bhūmikatva 6, 8
Ālasya 6
amanaska 26, 60
Anavasthitattva 6, 8
Angamejayatva 6
antaranga sādhanā 3
antarātmā sādhanā 4
apāna 66
aparigraha 13, 17
apuṇya 9
Arjuna 1, 3, 11, 18, 30, 33
āsana 3, 18, 22–4, 30, 32 *see also* names of industrial āsanas; courses 131–7
Aṣṭāṅga Yoga 4, 13
asteya 13, 16
Ātmā or Ātman 4, 12, 25, 32, 60
ātmīyatā 8
Auṁ 31–2
avasthā 31, 60
Avatāra 24
avidyā 6
avirati 6

bahiraṅga sādhanā 3
bandha jalandhara 123–4, 128
Bhagavad Gītā 1, 12, 18, 33, 89
bhakti 18, 20, 21, 27
bhakti-mārga 4
Bharadvāja 24, 109
Bharadvājāsana 109
bhoga 20
Bhoktṛ 12
Bhrānti darśana 6
Bhujaṅgāsana 55
body 1, 3–6, 12, 15, 18, 20, 22–4, 30, 33, 37, 60, 120
Brahmā 11, 32, 76, 105
Brahma Vidyā 32
brahmacharya 13, 16–17, 20, 79, 81
Brahman 16, 18, 24, 32, 34, 60, 66, 89
breathing 3, 6, 9, 18, 24–8, 33, 39, 67, 116, 118, 121 *see also* prāṇāyāma
buddhi 2, 18, 31

celibacy 16–17
chakras 66
chitta 2, 26
chitta-vikṣepa 6–8
chitta-vṛtti 2, 5
cleanliness 18, 37, 117
compassion 8
concentration 3, 7, 18, 26, 31, 60, 121, 128
consciousness 28, 31, 60, 121

Dakṣa 44
Daṇḍāsana 57; Chaturaṅga 54–5
daurmanasya 6, 18
death 11, 15, 19, 22, 29
desire 3, 10, 12, 16, 19, 21, 25, 30, 60
despair 6, 18
devadatta 27
Dhanurāsana 54; Ūrdhva 114–15
dhāranā 3, 30, 128
dhyāna 3, 26, 33, 122, 128
discipline 3, 10, 12, 18, 20, 22, 23, 29, 32, 37, 117
Droṇa 30, 109

duḥkha 6, 8
duty 4, 13, 17
dveṣa 6

ego 2, 26, 31, 32
Eka-tattvābhyāsa 30
ekāgra 18
ekāgratā 31
emotions 1, 13, 18, 26, 28, 33, 121
energy 2, 17, 18, 20, 24, 27, 60, 66, 121
enlightenment 10, 11
ethics 13, 37

food 14, 19, 28, 37, 60, 117

Gandhi 1, 15
God 1, 4, 7, 12, 16, 26, 27, 29, 40, 122
guṇas 28–9, 32
guṇātīta 29, 32
guru 9, 24, 32, 52, 117, 127

Halāsana 95–6; Pārśva 99–100
'Hamsah' 25
Hanumān 24
Hastāsana Pāda 51
Haṭha-vidya 112
Haṭha-yoga 4, 10, 24, 26, 27
headstand pose 82–90; *see also* Sīrṣāsana
health 6–7, 19, 33

Iḍā 124
imagination 5
immortality 29, 60
individuality 6, 26
indriya-jaya 18
intellect 1, 4, 8, 11, 17, 21, 31, 32
Iśvara praṇidhāna 18, 21

jāgrata-avasthā 30
japa 122
Jaya 123
Jīvana-mukta 33
Jīvana-mukti 60
jīvatmā 1, 26

Kaivalya 13
Kālidāsa 44
Kapila 24
Karma 33
Karma-mārga 4
Karma-yoga 2
Karṇapīdāsana 98–9
karuṇā 8
Kaṭhopaniṣad 2, 8, 11
kleśa 5
Koṇāsana: Baddha 65–6, 118, 120;
  Supta 99; Upaviṣṭha 78–9
Krishṇa 1, 3, 11, 18, 33
kṛkara 27
kṣipta 30
kumbhaka 25, 60, 118, 121, 127
  antara 25, 121, 124, 125, 127, 128
  bāhya 25, 121, 124, 127
Kuṇḍalinī 66

Laya 60
Laya-yoga 10
lobha 21
lotus posture 66–7; *see also* padmāsana

madhyama 9
maitri 8
manas 2, 9, 26, 31, 60, 116
Manomanī 60
Mantra-yoga 9
Marīchyāsana I 76–8
Matsyāsana 68
Matsyendra 112
Matsyendrāsana Ardha I 112–13
Marūrāsana Uttāna 102–3
meditation 3, 7, 32–3, 60, 61, 66, 128
mind 1, 9, 12, 15, 20, 25, 30, 39, 52, 61,
  116, 119
mindlessness 26
moderation 2, 10, 11
moha 21
Mokṣa 1, 116
morality 13, 14
mṛdu 9
Mrtāsana 116
mūdha 30
muditā 8

Mudrā: jñāna 119, 123, 128; khecharī
  60–1; mahā 70–1
Mudrāsana Yoga 70

Nāda 60–1
Nāḍi 60, 126
Nāḍī Śodhana Prāṇāyāma 117, 126–7
nāga 27
names, sacred 122
Nāvāsana: Ardha 58–9; Paripūrna 58–9
'Neti! neti!' 34
Nirālamba 60
Niraṅjana 60
Nirodha 2
niruddha 31
Niyama 3, 18, 37, 60
non-violence 13, 20

Pādahastāsana 51–2
Padāngusṭhāsana 50–1; Supta 108
Padmāsana 66–7, 118; Baddha 70;
  Ūrdhva 103
Padottānāsana 48; Prasārita 48–9
pain 6, 8, 13, 18, 29
Parama Pāda 60
Paramātmā 1, 3, 26
Parivartānasana Jaṭara 106–8
Pārśvakoṇāsana Utthita 43
Pārśvottānāsana 46–7
Parvatāsana 68
Pārvati 112
Paschimottānāsana 79–81; Ardha
  Baddha Padma 73–4; Trianga
  Mukhaikapāda 75–6
Patañjali 1, 5, 8, 9, 13, 16, 18
peace 2, 12, 18, 19–20, 26, 34, 122
pinda-prāṇa 26
Pindāsana Parsva 104
Piṅgalā 124
pleasure 5
posture 3, 18, 22–4, 118; *see also* āsana
practice 3, 8, 9, 38, 40, 118, 119
prakṛti 28
pramāda 6
pramāṇa 5
prāṇa 9, 24, 25, 31, 116, 121, 124, 128
praṇava 31
prāṇa-vāyu 27
prāṇāyāma 3, 9, 18, 24–6, 30, 32, 39, 66,
  117–28
pratyāhāra 3, 18, 27–9, 32, 121
pratyaksa 5
prayer 9, 20, 25
puṇya 9
puraka 25, 120, 123, 125, 126
pūrnatā 22
Pūrvottānāsana 22, 82

rāga 6
Rāja-yoga 4, 60
rajas 32
rajo-guṇa 28
reason 2, 4, 12, 14, 26, 33
rebirth 12, 120
rechaka 25, 124, 125, 127
relaxation 116, 118
renunciation 13, 17

sacred words 122
sādhanā 8, 11–12, 13
Sahajāvasthā 60
Śalabhāsana 53
samādhi 3, 13, 34, 60, 122
samāna 27
Saṁśaya 6
saṁskāra 11
Sankarāchārya 25
santoṣa 18–19
Sarvāngāsana 37, 90–7; Eka Pāda
  100–101; Pārśva Pinḍāsana in 104;
  Pārśvaika Pāda 101; Pinḍāsana in 104;
  Sālamba 90–4; Setu Bandha 102–103;
  Ūrdhva Padmāsana in 103
Satī 44
sattva 28, 32
Sattva-guṇa 29
Śavāsana 39, 116, 120
Self 2, 6, 8, 11, 15, 18, 20–1, 22, 31, 60
self-surrender 5, 12–13
senses 2, 7, 10, 12, 18, 21, 26, 32, 60,
  116, 119, 121
Siddha 60–1
Siddhāsana 60–1, 118, 123
Sīrṣāsana 82–90; Jānu 72–3; Salamba 82–6

Siva 32, 44, 112
'So'ham' 25
Soka 21
soul 1, 4, 12, 21, 24, 33, 60, 116;
  conditions of 60
sound, inner 61
sraddhā 11
sthita-prajñā 32
Styāna 6
Śunyāśūnya 60
Sūrya 76
Sūrya Bhedana Prāṇāyāma 124–6
suṣumṇá nāḍí 66
Suṣupti-avasthā 31, 60
svādhyāya 18, 20–1
Śvānāsana: Adho Mukha 39, 56–7;
  Ūrdhva Mukha 56
svapnāvasthā 31
Śvāsa-praśvāsa 6

Tādāsana 41
Tamas 28, 32
Tamo-guṇa 29
tapas 19, 20
'Tat Twam Asi' 32
Tattva-jñāna 12
Tṛṣṇa 29
turīyā-avasthā 31, 60

udāna 27
Ujjāyi 123
Ujjāyi Prāṇāyāma 123–4
Upaniṣads 32, 60
upėkṣā 8
Uṣṭrāsana 50–1
Uttānāsana 39, 52

Vāchika 20
Vairāgya 3, 10, 29
Vasiṣṭha 24
vāyu 27
vegetarianism 14, 18–19
Vibhūti-pāda 13
Vikalpa 5
Viloma Prāṇāyama 128
Vinoba Bhave 31
viparyaya 5
Vīrabhadrāsana I 44–5
Vīrabhadrāsana II 45
Vīrāsana 62, 118, 123; Supta 64–5
virtue 8, 17
vīrya 7
Viṣṇu 32, 68, 105
Viśvāmitra 24
Vṛtti 2
Vyādhi 6
vyāna 27

will xii, 21–2
women 40, 52, 59, 66, 79; pregnant
  40, 66
work 4

Yama 3, 13, 18, 37
Yoga Sūtra 1, 4, 13
Yukta 1

CHINESE MEDICAL QIGONG THERAPY:

A Comprehensive Clinical Text

中国气功医疗

DR. JERRY ALAN JOHNSON PH.D., DTCM, DMQ (CHINA)

CHINESE MEDICAL QIGONG THERAPY:

A COMPREHENSIVE CLINICAL TEXT

JERRY ALAN JOHNSON, PH.D., D.T.C.M., D.M.Q. (CHINA)

EDITED BY
JAMPA MACKENZIE STEWART, D.O.M., L.AC.
AND
MADELEINE H. HOWELL, M.F.T., M.Q.T.

First published in May 2000 by:
The International Institute of Medical Qigong
P.O. Box 52144
Pacific Grove, CA 93950
U.S.A.

© 2000 Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)

All rights reserved under the International and Pan-American copyright conventions. No part of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording or otherwise, without the prior written permission of the publisher (The International Institute of Medical Qigong). Reviewers may quote brief passages.

ISBN# 1-885246-08-0
Printed in the United States of America.

Disclaimer:

Qigong medicine is not intended to replace orthodox medicine, but rather to complement it. The meditations, practices, techniques and prescriptions described herein are powerful and may be too mentally and physically demanding for some people. The readers should therefore use their own discretion and consult a doctor of Medical Qigong therapy, an acupuncturist, medical doctor, or mental health professional before engaging in these exercises and meditations. The author, the International Institute of Medical Qigong, and the publishers are neither liable or responsible to any person or entity with respect to any loss or damage caused, or alleged to be caused, directly or indirectly by reading or following the instructions for any condition, or interpreting information provided in this text. The treatments mentioned in this book are not meant to be used as symptomatic prescriptions. The treatment of specific organs, channels, channel points, and prescriptions must always be selected based on the thorough understanding of the origin of the patient's disease. If an ailment is severe, or if symptoms persist, please consult a medical professional immediately.

Throughout the text I will refer the doctor to prescribe herbs for certain conditions along with Medical Qigong therapy. All Medical Qigong prescriptions, exercises and "homework" assigned to patients in Section X "Treatment of Internal Diseases with Qi Emission Therapy" and Section XI "Specialized Qi Emission Therapy for Pediatrics, Geriatrics, Gynecology, Neurology, Psychology, Oncology, and Surgery" should also be included with herbal prescriptions, as well as the regulation of the patient's diet and living environment. Herbal prescriptions will vary according to the patient's constitution, condition and specific illness, and must be treated accordingly only by a doctor or herbalists qualified to prescribe Chinese medical herbs.

Throughout the text I have used the term *doctor* when referring to professional practitioners who use energetic medicine to treat patients. The word "doctor" means "to teach". I believe that the foremost duty of any doctor of medicine (Western or Chinese) should be as educator, to teach his or her patients knowledge and skills for the prevention and treatment of disease and injury. Currently, the official title, *Doctor of Medical Qigong Therapy* is only licensed and used in China.

TABLE OF CONTENTS

FORWARD XXIII

PREFACE XXXI

ACKNOWLEDGMENTS XXXV

INTRODUCTION XXXVII

SECTION I
FOUNDATIONS OF CHINESE ENERGETIC MEDICINE 1

CHAPTER 1 INTRODUCTION TO MEDICAL QIGONG 3
- THE FIVE DOMINIONS OF ENERGY 3
- DEFINING THE ENERGY OF YIN AND YANG 5
- UNDERSTANDING THE CONCEPT OF QI 5
- DIFFERENT SCHOOLS OF QIGONG 5
- MEDICAL QIGONG DEFINED 6
- MEDICAL QIGONG TRAINING IN CHINA 7
- MEDICAL QIGONG TRAINING IN THE UNITED STATES 8
- TRADITIONAL CHINESE MEDICINE AND MEDICAL QIGONG THERAPY 14
- ACUPUNCTURE THERAPY 15
- HERBAL THERAPY 18
- CHINESE MASSAGE THERAPY 19
- MEDICAL QIGONG THERAPY 22

CHAPTER 2 ENERGETIC FORMATION OF THE HUMAN BODY 25
- ENERGETIC EMBRYOLOGICAL DEVELOPMENT 25
- ENERGY, MATTER, AND SPIRITUAL INTERACTIONS 26
- UNDERSTANDING FETAL TOXINS 26
- DEVELOPMENTAL SEQUENCE 27
- THE TEN LUNAR MONTHS OF CREATION 29
- POSTNATAL ENERGY DEVELOPMENT 41
- ENERGETIC EMBRYOLOGICAL OVERVIEW 41
- THE ETERNAL SOUL 42
- SUMMARY 51

CHAPTER 3 PHYSICAL DEVELOPMENT AND STRUCTURAL FORMATION 53
- FASCIAL DEVELOPMENT AND ENERGY FLOW 53
- YIN AND YANG STRUCTURAL FORMATION 53
- THE YIN AND YANG OF BODY ASPECTS 55
- THE FIVE ELEMENTS 56
- CONGENITAL CONSTITUTIONS 57
- CLASSIFICATION OF THE FIVE CONSTITUTIONS 57
- THE WOOD CONSTITUTION 58
- THE FIRE CONSTITUTION 60
- THE EARTH CONSTITUTION 61
- THE METAL CONSTITUTION 62
- THE WATER CONSTITUTION 63

COMBINED CONSTITUTIONS 64
PERSONALITY CONSTITUTIONS OF THE EIGHT EXTRAORDINARY VESSELS 65
THE YAO IMAGE AND PHYSICAL ANATOMY 66
IDENTIFYING INTROVERTED AND EXTROVERTED STRUCTURES 71
CONGENITAL AND ACQUIRED CELLULAR PATTERNS 73
SUMMARY 73

CHAPTER 4 THE FIVE ENERGIES OF THE HUMAN BODY 75
SOUND ENERGY RESONANCES 75
LIGHT ENERGY 77
MAGNETIC ENERGY 82
GENERATED HEAT 84
ELECTRICITY 86

CHAPTER 5 THE THREE DANTIANS AND THE TAIJI POLE 89
THE THREE DANTIANS 89
THE LOWER FIELD OF ELIXIR 90
THE MIDDLE FIELD OF ELIXIR 95
THE UPPER FIELD OF ELIXIR 98
THE FUNCTIONAL ASPECTS OF THE THREE DANTIANS 102
THE DANTIAN'S YIN AND YANG ENERGETIC CHAMBERS 104
THE DOCTOR'S PROJECTED AURA FIELDS 105
THE TAIJI POLE 105
THE TWELVE GATES OF THE CHAKRA SYSTEM 109
TAKING PRECAUTIONS 115
THE TWELVE EARTHLY BRANCHES AND THE TWELVE CHAKRA GATES 115

CHAPTER 6 THE TWELVE PRIMARY CHANNELS AND ORGANS 117
INTRODUCTION 117
CLASSIFICATION OF CHANNELS 118
THE CHANNELS' RELATIONSHIP TO QI AND BLOOD 121
FUNCTION OF THE CHANNELS 122
INTERNAL AND EXTERNAL CHANNEL FLOW 122
ORGAN AND CHANNEL FUNDAMENTALS 123
THE GALL BLADDER CHANNELS 124
THE LIVER CHANNELS 126
THE LUNG CHANNELS 128
THE LARGE INTESTINE CHANNELS 130
THE STOMACH CHANNELS 132
THE SPLEEN CHANNELS 134
THE HEART CHANNELS 136
THE SMALL INTESTINE CHANNELS 138
THE BLADDER CHANNELS 140
THE KIDNEY CHANNELS 142
THE PERICARDIUM CHANNELS 145
THE TRIPLE BURNER CHANNELS 147
UNDERSTANDING CHANNEL PATHOLOGY 151

CHAPTER 7 THE EIGHT EXTRAORDINARY VESSELS AND COLLATERALS 155
THE EIGHT EXTRAORDINARY VESSELS 155
THE FUNCTION OF THE EIGHT EXTRAORDINARY VESSELS 155
THE EIGHT EXTRAORDINARY VESSELS AND MEDICAL QIGONG THERAPY 157

CLINICAL USE OF THE EIGHT EXTRAORDINARY VESSELS 157
ENERGETIC FUNCTIONS OF THE EIGHT EXTRAORDINARY VESSELS 158
THE GOVERNING AND CONCEPTION VESSELS 158
THE GOVERNING VESSEL OR DU VESSEL 159
THE CONCEPTION VESSEL OR REN VESSEL 162
THE THRUSTING VESSELS AND THE BELT VESSELS 164
THE BELT VESSEL OR DAI VESSEL 166
THE YIN AND YANG HEEL VESSELS OR QIAO VESSELS 168
THE YIN HEEL VESSELS 168
THE YANG HEEL VESSELS 169
THE YIN AND YANG LINKING VESSELS OR WEI VESSELS 171
THE YIN LINKING VESSEL 171
THE YANG LINKING VESSELS 172
SUMMARY OF EIGHT EXTRAORDINARY VESSEL PATHOLOGY 173
THE FIFTEEN MAJOR COLLATERALS (CONNECTING VESSELS) 175
THE TWELVE DIVERGENT CHANNELS 180
THE TWELVE MUSCLE/TENDON CHANNELS 186
THE TWELVE SKIN ZONES 197
THE CONNECTIVE TISSUE OF THE TWELVE SKIN ZONES 197
CHANNEL AND COLLATERAL THERAPY 200
CONTROLLING QI EXTENSION THROUGH THE CHANNELS 201

CHAPTER 8 THE BODY'S ENERGETIC POINTS 203
INTRODUCTION TO ENERGETIC POINTS 203
THE FOUR WAYS POINTS ARE FORMED 203
SCIENTIFIC RESEARCH OF ACUPOINTS 203
THE FOUR CATEGORIES OF ENERGETIC POINTS 204
THE TWO GATES OF ENERGETIC POINTS 204
THE THREE FUNCTIONS OF ENERGETIC POINTS 205
POINT NAMES 207
CLASSIFICATION OF ENERGETIC POINTS 207
SUMMARY OF POINTS 212

CHAPTER 9 THE EXTRAORDINARY YANG ORGANS 215
THE UTERUS 215
THE BRAIN 217
THE GALL BLADDER 218
THE MARROW 218
THE BONES 218
THE BLOOD VESSELS 221

SECTION II
THE THREE OUTER FORCES: HEAVEN, EARTH & MAN 223

CHAPTER 10 INTRODUCTION TO THE THREE OUTER FORCES 225
THE NATURAL POWER OF THE THREE OUTER FORCES 225
THE THREE OUTER FORCE'S NINE TREASURES 225
THE THREE OUTER FORCES AND CHINESE ALCHEMY 225
HEAVENLY QI 226
EARTHLY QI 228
MAN'S QI 229

CHAPTER 11 THE THREE TREASURES OF HEAVEN: SUN, MOON, AND STARS 231
- DEFINING HEAVEN QI 231
- INFLUENCES OF HEAVENLY QI ON THE HUMAN BODY 232
- BODY RHYTHMS AND ENERGETIC PATTERNS 232
- CYCLES OF THE SUN 234
- THE TWELVE PI HEXAGRAMS 234
- THE FOUR PRINCIPAL TIME PERIODS OF QIGONG PRACTICE 236
- THE FOUR SEASONAL PEAK TRANSITIONS 237
- THE SIX PRINCIPAL SEASONS OF TRANSITION 239
- THE DAILY QI, BLOOD, AND HEAT CYCLE 239
- GATHERING THE SUN'S ESSENCE MEDITATION 240
- CYCLES OF THE MOON 242
- PRENATAL EIGHT TRIGRAMS AND THE MOON 244
- CHOOSING THE PROPER DIRECTION FOR TRAINING QI 244
- CYCLES OF THE STARS 248
- EARTHLY BRANCHES, HEAVENLY STEMS, AND NINE PALACES 254
- SUMMARY 255

CHAPTER 12 THE THREE TREASURES OF EARTH:EARTH, WATER, AND WIND 259
- INTRODUCTION TO THE THREE TREASURES OF EARTH 259
- GATHERING ENERGY FROM THE EARTH'S ENERGETIC FIELDS 260
- TECHNIQUES FOR CULTIVATING EARTH QI 260
- GATHERING QI FROM TREES, BUSHES, AND FLOWERS 261
- GATHERING QI FROM MOUNTAINS, VALLEYS, AND DESERTS 263
- GATHERING QI FROM OCEANS, LAKES, AND STREAMS 263
- GATHERING QI FROM THE SIX DIRECTIONS 264
- ADDITIONAL TECHNIQUES FOR TRAINING EARTH QI 265
- THE EARTHLY TREASURE OF FOOD 266
- UNDERSTANDING THE YIN OR YANG ASPECT OF FOOD 266
- UNDERSTANDING THE YIN OR YANG ASPECT OF HERBS 266
- ENERGY, FOOD, AND DIET 267
- USING THE FIVE FLAVORS OF FOOD 268
- GUIDELINES FOR THE FIVE ELEMENTAL TASTES 270
- OVERVIEW OF THE FIVE ELEMENTAL TASTES 271
- SUMMARY 271

CHAPTER 13 THE THREE TREASURES OF MAN: JING, QI, AND SHEN 273
- PRENATAL AND POSTNATAL JING, QI, AND SHEN TRANSFORMATIONS 274
- JING: ESSENCE OF LIFE 276
- THE YIN AND YANG ASPECTS OF JING 276
- PRENATAL JING 276
- POSTNATAL JING 277
- THE INTERACTION OF PRENATAL AND POSTNATAL JING 277
- QI: VITAL LIFE-FORCE ENERGY 278
- EIGHTEEN CLASSIFICATIONS OF QI 279
- THE SIX FUNCTIONS OF QI 281
- QI AND ENERGETIC MEDICINE 283
- QI AND THE BODY'S ENERGETIC STRUCTURE 283
- SHEN: THE SPIRIT OF LIFE 290
- SHENGONG SCHOOLS OF MEDITATIONS AND TRAINING 290
- PRENATAL AND POSTNATAL SHEN 291

THE FIVE SPIRITUAL ASPECTS AND YIN ORGAN COMPONENTS OF SHEN 291
THE LIVER STORES THE ESSENCE SPIRIT "HUN" 292
THE HEART STORES THE ESSENCE SPIRIT "SHEN" 295
THE SPLEEN STORES THE ESSENCE SPIRIT "YI" 296
THE LUNGS STORE THE ESSENCE SPIRIT "PO" 296
THE KIDNEYS STORE THE ESSENCE SPIRIT "ZHI" 298
THE FIVE YIN ORGAN CULTIVATION OF SHEN 298
SHENGONG CULTIVATION METHODS 300
THE SIX TRANSPORTATION'S OF SHEN 301
THE EIGHT SUPERNATURAL POWERS 304
SOUL PROJECTION, SPIRIT PROJECTION AND ENERGY PROJECTION 306

SECTION III

DAO YIN TRAINING 311

CHAPTER 14 INTRODUCTION TO DAO YIN TRAINING 313
STATIC QIGONG TRAINING 314
DYNAMIC QIGONG TRAINING 314
PRINCIPLES OF YIN AND YANG IN DAO YIN TRAINING 314
THREE FOUNDATIONAL METHODS OF DAO YIN TRAINING 315

CHAPTER 15 POSTURAL DAO YIN TRAINING 317
STATIC POSTURE DAO YIN TRAINING 317
CHOOSING THE PROPER POSTURE 318
PRIMARY AND SECONDARY POSTURES 318
THE EIGHTEEN RULES OF PROPER MEDICAL QIGONG STRUCTURE 321
DYNAMIC POSTURE DAO YIN TRAINING 330
USING THE ENERGY OF THE HANDS TO LEAD QI 332
MEDICAL QIGONG WALKING THERAPY 334
WALKING COMBINED WITH COLOR THERAPY 338
WALKING COMBINED WITH SOUND THERAPY 338
THE THERAPEUTIC EFFECTS OF MEDICAL QIGONG WALKING THERAPY 338
THREE STEPPING METHODS USED TO TREAT CANCER 342
ENDING AND CLOSING THE WALKING THERAPY 344

CHAPTER 16 RESPIRATORY DAO YIN 349
THE PURPOSE OF RESPIRATORY DAO YIN 349
THE ROLE OF THE LUNGS IN QI CULTIVATION 349
DEEP INHALATION AND EXHALATION BREATHING METHODS 349
SEVEN DAO YIN BREATHING TECHNIQUES 350
RESPIRATORY GUIDING AND REGULATING 353
RESPIRATORY TONIFICATION AND PURGING METHODS 354
BASIC ESSENTIALS OF RESPIRATORY TRAINING 354
BREATHING PATTERNS FOR COLLECTING AND REGULATING QI 355
THE FOUR PROGRESSIVE STAGES OF RESPIRATION 356
DURATION TIME FOR RESPIRATION THERAPY 357
EMOTIONAL EFFECTS ON BREATHING PATTERNS 357
RESPIRATORY DAO YIN CANCER PRESCRIPTIONS 357

CHAPTER 17 MENTAL DAO YIN TRAINING 359
INTRODUCTION 359
THE PRENATAL AND POSTNATAL MIND 360

BENIGN AND MALIGNANT THOUGHT PATTERNS 361
THE IMPORTANCE OF MIND CONCENTRATION 361
REGULATING THE MIND 362
THE THREE CATEGORIES OF MENTAL CONCENTRATION 363
ESSENTIALS OF TRAINING MIND CONCENTRATION 364
CONCENTRATIVE MEDITATION AND INSIGHT MEDITATION 365
THE THREE STAGES OF MENTAL TRANQUILITY 366
THE THREE PROCESSES OF THE MIND 366
CREATING THE BRIDGE OF LIGHT 367
REPROGRAMMING THE MIND TO HEAL 369
USING THE IMAGINATION 369
TWELVE STAGES TO TRANSCEND AND TRANSFORM 370
SUMMARY 374

SECTION IV
QI DEVIATIONS IN QIGONG TRAINING 375

CHAPTER 18 INTRODUCTION TO QI DEVIATIONS 377
THE MAIN CAUSES OF QI DEVIATIONS 377
CORRECTING QI DEVIATIONS 379
SHEN DISTURBANCES AND EMOTIONAL DYSFUNCTIONS 386
UNCONTROLLABLE MUSCLE DEVIATIONS 391
RECTIFYING QI DEVIATIONS USING TAIJI RULER 391

CHAPTER 19 DISORDERS AND DEVIATIONS OF THE SOUL AND SPIRIT 393
INTRODUCTION TO SPIRITUAL DIMENSIONS 393
EVIL STATES AND MENTAL DELUSIONS 395
PROJECTED SPIRIT DEMONS FROM THE SUBCONSCIOUS MIND 397
ACTUAL ENCOUNTERS WITH SPIRIT DEMONS 397
OVERVIEW 399
MULTIPLE PERSONALITY DISORDER (DISSOCIATIVE IDENTITY DISORDER) 400
SOUL RETRIEVAL AND MEDICAL QIGONG THERAPY 401
WOUNDING AND CLOSING THE SPIRIT 403
HEALING THE SPIRIT 405
EMOTIONAL REBIRTHING PATTERNS 406
SOUL RETRIEVAL MEDITATION 406
THE DOOR TO THE CHAMBER OF MEMORIES 411
FINDING THE LIFE PURPOSE 411

SECTION V
DIFFERENTIAL DIAGNOSIS OF ENERGETIC PRINCIPLES 413

CHAPTER 20 INTRODUCTION TO DIFFERENTIAL DIAGNOSIS 415
DIAGNOSIS IN ENERGETIC MEDICINE 415
ETIOLOGY IN MEDICAL QIGONG THERAPY 415
THE GROWTH AND PEAK CYCLES OF JING, QI AND SHEN 416
DISORDERS OF THE HUMAN BODY 417
THE DIFFERENTIATION OF SYNDROMES 419
THE CATEGORIZATION OF SIGNS AND SYMPTOMS 420
DIAGNOSIS AND TREATMENT OF THE PATIENT 420
UNDERSTANDING THE THEORY OF ENERGETIC COUNTERACTION 422

CHAPTER 21 DIAGNOSIS ACCORDING TO THE EIGHT ENERGETIC PRINCIPLES 423
INTERNAL AND EXTERNAL PATHOGENIC FACTORS 423
HOT AND COLD 428
EXCESS AND DEFICIENT 430
YIN AND YANG THEORY 431
DIAGNOSING YIN AND YANG IN THE BODY 432
SIGNS OF YIN AND YANG 435
YIN AND YANG CATEGORIZATION OF TRAINING 436
PULSE DIAGNOSIS OF THE EIGHT ENERGETIC PRINCIPLES 436
PULSE QUALITIES AND CLASSIFICATIONS 437
THE CLASSICAL PULSE DIAGNOSTIC POSITIONS AND DEPTH 438
OVERVIEW 439

CHAPTER 22 DIAGNOSIS ACCORDING TO QI, BLOOD, AND BODY FLUID DYSFUNCTIONS 441
INTRODUCTION 441
DISORDERS OF THE QI 441
LEAKAGE AND LOSS OF QI 442
EXCESS QI DISORDERS 444
QI STAGNATION DISORDERS 444
REBELLIOUS QI DISORDERS 445
TURBID QI 445
RECTIFYING QI DISORDERS 446
DISORDERS OF THE BLOOD 447
DEFICIENCY OF BLOOD 447
THREE DISORDERS OF BODY FLUIDS 448
TYPES OF PHLEGM 450

CHAPTER 23 DIAGNOSIS ACCORDING TO THE FIVE-ELEMENT THEORIES 451
INTRODUCTION TO THE FIVE ELEMENTS 451
THE FIVE ELEMENTS AND YIN AND YANG THEORY 451
THE CREATIVE OR GENERATIVE CYCLE 453
THE CONTROLLING OR RESTRICTIVE CYCLE 453
THE INVADING OR OVERACTING CYCLE 454
THE INSULTING OR COUNTERACTING CYCLE 455
THE FIVE ELEMENTAL TONIFICATION CYCLE 456
FIVE YIN ENERGETIC ORGAN MANIFESTATIONS 456

CHAPTER 24 OTHER DIAGNOSTIC SYSTEMS AND TECHNIQUES 459
DIAGNOSIS ACCORDING TO THE SIX STAGES 459
DIAGNOSIS ACCORDING TO THE FOUR LEVELS 460
DIAGNOSIS ACCORDING TO THE TRIPLE BURNERS 462

CHAPTER 25 CLINICAL EXAMINATION AND DIAGNOSIS 465
SENSORY, INTUITIVE AND PERCEPTUAL DIAGNOSIS 465
SENSORY DIAGNOSIS 465
CLINICAL INTAKE, EXAMINATION AND EVALUATION 465
EXAMINATION FOR DIAGNOSIS 467
DEVISING A TREATMENT PRINCIPLE 468
TREATMENT STRATEGY 468
TREATMENT 469
AFTER THE TREATMENT 469

ALTERNATIVE TREATMENT STRATEGIES 470
INTUITIVE AND PERCEPTUAL DIAGNOSIS 470
THE METAPHYSICAL DIMENSIONS OF MEDICAL QIGONG HEALING 470
THE AWAKENING 471
LEARNING INTUITIVE AND PERCEPTUAL DIAGNOSIS 471
RECEIVING AND INTERPRETING THE PATIENT'S FIELDS OF BIO-INFORMATION 472
ACCESSING THE KNOWLEDGE STORED WITHIN THE WUJI 473
UNDERSTANDING PAST-LIFE REGRESSION 474
LEARNING MEDICAL QIGONG TECHNIQUES 476
PERCEPTUAL COMMUNICATION TRAINING 477
APPLICATIONS OF INTUITIVE AND PERCEPTUAL QI DIAGNOSIS 479
DIAGNOSIS BASED ON FLAT-PALM DETECTION (HAND SENSING) 479
DIAGNOSIS BASED ON KINESTHETIC AND EMPATHIC QI ABSORPTION 480
HAND DIAGNOSIS BASED ON BODY ASSOCIATION 481
DIAGNOSIS BY OBSERVING AURA FIELDS 483
DIAGNOSIS BASED ON INTENTION 487
LONG DISTANCE MEDICAL QIGONG THERAPY 487
FAITH PROJECTION AND MEDICAL QIGONG THERAPY 490
AUXILIARY MEDICAL QIGONG HEALING MODALITIES 492
USING MEDICAL QIGONG TO HEAL BY PROJECTING CHINESE CHARACTERS 492
USING MEDICAL QIGONG WITH SUPPLEMENTARY APPARATUSES 492

SECTION VI
ESTABLISHING THE MEDICAL QIGONG CLINIC 497

CHAPTER 26 TREATING THE PATIENT 499
SETTING A SPACE/TIME FOUNDATION 499
ESTABLISHING THE MEDICAL QIGONG TREATMENT ROOM 500
ESTABLISHING A RAPPORT WITH THE PATIENT 500
THE FOUR MAJOR PRIORITIES OF CLINICAL QIGONG HEALING 503
PREPARING THE SELF TO TREAT THE PATIENT 504
TREATING THE PATIENT 509
MEDICAL QIGONG TREATMENTS 515
TREATING MULTIPLE PATIENTS 519
ENDING THE TREATMENT 520

CHAPTER 27 COMBINING MEDICAL QIGONG THERAPY WITH OTHER HEALING MODALITIES .. 523
COMBINING MEDICAL QIGONG THERAPY WITH TCM MODALITIES 523
COMBINING MEDICAL QIGONG THERAPY WITH WESTERN MEDICAL MODALITIES 525

CHAPTER 28 PRECAUTIONS AND ETHICAL CONSIDERATIONS FOR THE QIGONG DOCTOR 527
AVOIDING ENERGETIC DEPLETION 527
PREVENTING THE INVASION OF TURBID QI 528
GUIDELINES FOR THE MEDICAL QIGONG DOCTOR 529
WU ZANG (FIVE ORGAN) MEDITATION FOR ENERGETIC PROTECTION 530
CREATING A PROTECTIVE ENERGETIC FORCE FIELD 533
CLINICAL ETHICS 534
CONSCIOUS AND SUBCONSCIOUS CLINICAL INTERACTIONS 535
ESTABLISHING DOCTOR AND PATIENT AGREEMENTS 536
POWER DYNAMICS AND ETHICAL BEHAVIOR 537
PITFALLS 538

CLINICAL BURNOUT AND MEDICAL QIGONG THERAPY 538
ENERGETIC BOUNDARY INVASION 539
STRENGTHENING THE DOCTOR'S ENERGETIC BOUNDARIES 540
CAUSES OF SPIRITUAL DRYNESS 540

SECTION VII
THE TREATMENT PRINCIPLES OF MEDICAL QIGONG THERAPY 543

CHAPTER 29 PRINCIPLES AND PARAMETERS OF MEDICAL QIGONG THERAPY 545
THE FIVE METHODS FOR TREATING PATIENTS 545
THE NINE STAGES OF TREATMENT 545
THE THREE WONDERS OF MEDICAL QIGONG THERAPY 546
CONTRAINDICATIONS FOR MEDICAL QIGONG THERAPY 548

CHAPTER 30 BALANCING THE BODY'S ENERGETIC SYSTEM 551
PURGING, TONIFYING, AND REGULATING 551
THE THREE TREATMENT MODALITIES 551
PURGATION TECHNIQUES 552
TONIFICATION AND PURGATION METHODS 552
TONIFICATION AND PURGATION GUIDELINES 554
UNDERSTANDING MEDICAL QIGONG REGULATION 554
QI REGULATION AND GUIDING PRINCIPLES 555
ENERGY BALANCING PROCEDURES 555
CLINICAL OBSERVATIONS OF PATHOLOGICAL ENERGETIC PATTERNS 556
LOCATIONS OF ENERGETIC BLOCKAGES 556
TYPES OF ENERGETIC COMPLICATIONS 559
PATIENT'S ENERGETIC FACIAL DISTORTION 562
PATIENT RESISTANCE TO ENERGETIC THERAPY 562
UNBLOCKING THE FIVE PASSES 562
FURTHER COMPLICATIONS 564

CHAPTER 31 THE MAGIC SQUARE OF THE YELLOW RIVER 565
THE MAGIC SQUARE AND EIGHT TRIGRAMS 568
THE MAGIC SQUARE AND THE EIGHT EXTRAORDINARY VESSELS 569
UNDERSTANDING THE METAPHYSICAL ASPECT OF NUMBERS 569
THE FIVE ELEMENT ENERGETIC FLOW OF THE MAGIC SQUARE 570
CROSSOVER ENERGY PATTERNS 570

CHAPTER 32 HEALING THE PATIENT'S EMOTIONAL TRAUMAS 573
INTRODUCTION 573
THE PHYSIOLOGICAL EFFECTS OF BENIGN AND CHRONIC EMOTIONS 573
FIVE LEVELS OF FEELING AND THEIR GOVERNING ORGANS 573
STAGES OF EMOTIONAL HISTORY AND RESOLUTION 576
ASSISTING THE PATIENT IN ESTABLISHING HEALTHY BOUNDARIES 578
REJECTION, BETRAYAL, AND ABANDONMENT 578
EMOTIONAL SECURITY 579
HEALING EMOTIONAL TRAUMAS 580
PULLING OUT THE PAIN MEDITATION 581
UNDERSTANDING WHY A PATIENT WON'T HEAL 582
FACING THE DEATH OF A PATIENT 583
SUMMARY 585

SECTION VIII
QI EMITTING METHODS 587

CHAPTER 33 ENERGY EXTENSION AND QI MANIPULATION TECHNIQUES 589
ENERGY PROJECTION 589
TYPES OF ENERGY EXTENSION 589
CONTROLLING ENERGETIC PROJECTIONS 591
HAND POSTURES FOR QI EMISSION 592
THE EXTENDED FAN PALM 592
THE SWORD FINGERS 594
THE ONE FINGER SKILL 595
THE INVISIBLE NEEDLE PALM 597
THE DRAGON'S MOUTH PALM 598
THE KNEADING TIGER PALM 598
THE FIVE THUNDER FINGERS 599

CHAPTER 34 QI EXTENSION, GUIDANCE, AND REGULATION TECHNIQUES 601
QI EXTENSION TECHNIQUES 601
GUIDING THE LINEAR FLOW OF ENERGY 601
CIRCULATING THE QI IN A CIRCLING PATTERN 603
SPIRALING ENERGY FLOW 605
ENERGETIC CUPPING 607
GUIDING THE STATIONARY FLOW OF ENERGY 607
GUIDING THE HOT AND COLD FLOW OF ENERGY 610
CLINICAL APPLICATION OF YIN AND YANG ENERGY EXTENSION 612
GUIDING THE ENERGETIC FLOW OF THE FIVE ELEMENTS 612
SUMMARY OF QI EMITTING METHODS 616

CHAPTER 35 THE INVISIBLE NEEDLE THEORY AND APPLICATION 619
INTRODUCTION 619
PREPARATION 619
ANGLE OF INSERTION FOR TONIFICATION OR SEDATION 620
THE HAND POSTURES OF THE INVISIBLE NEEDLE 621
TIME AND DURATION OF TREATMENT 622
REMOVING THE INVISIBLE NEEDLES AND ENDING THE TREATMENT 622

CHAPTER 36 ENERGETIC POINT THERAPY 623
CHANNEL POINT TREATMENTS AND PRESCRIPTIONS 623
CONTRAINDICATIONS 627
CHANNEL POINT MEDITATION 627

CHAPTER 37 MEDICAL QIGONG MASSAGE 631
INTRODUCTION TO TISSUE FUNCTION 631
TWO APPROACHES IN TREATMENT 632
TISSUE REGULATION THROUGH MEDICAL QIGONG MASSAGE 633
THE FIVE ELEMENTAL QI MASSAGE THERAPY 633
YIN AND YANG ENERGETIC POINT MANIPULATION 636
TREATING THE TISSUE AREA OR ENERGETIC POINT 637
ADDITIONAL GUIDELINES 637

SECTION IX

MEDICAL QIGONG EXERCISES AND PRESCRIPTIONS 639

CHAPTER 38 INTRODUCTION TO MEDICAL QIGONG PRESCRIPTIONS AND REGULATION EXERCISES 641
- HISTORY OF MEDICAL QIGONG PRESCRIPTIONS 641
- THE FUNCTION OF MEDICAL QIGONG PRESCRIPTIONS 641
- MEDICAL QIGONG AND THE IMMUNE SYSTEM 642
- THE FIVE STAGES OF HEALING 645
- THE THREE CATEGORIES OF MEDICAL QIGONG PRESCRIPTIONS 645
- CHOOSING PRESCRIPTIONS ACCORDING TO THE PATIENT'S QI CIRCULATION 646
- MEDICAL QIGONG PRESCRIPTIONS FOR GENERAL SYNDROMES 647
- NUMBER OF BREATHS REQUIRED IN MEDICAL QIGONG PRESCRIPTIONS 647

CHAPTER 39 SPECIFIC ORGAN SELF-MASSAGE PRESCRIPTIONS 649
- INTRODUCTION 649
- HEART MASSAGE 649
- LIVER MASSAGE 651
- LUNG MASSAGE 652
- SPLEEN & STOMACH MASSAGE 652
- KIDNEY MASSAGE 653

CHAPTER 40 HEALING SOUND THERAPY AND PRESCRIPTIONS 657
- INTRODUCTION AND HISTORY 657
- SOUND VOLUME RESONATION 657
- HIGH-, MIDDLE-, AND LOW-PITCHED SOUND 658
- BREATH AND MIND CONTROL 658
- AUDIBLE AND INAUDIBLE SOUND RESONATION 659
- THE SIX HEALING SOUND PRESCRIPTIONS 660
- THE PROPER NUMBER OF BREATHS FOR HEALING SOUND PRACTICE 665
- COMBINING MULTIPLE ORGAN SOUNDS 666
- OLD MAN SEARCHING FOR THE REFLECTION OF THE MOON AT THE BOTTOM OF TIDE POOL 666
- CONTRAINDICATIONS FOR THE SIX HEALING SOUND THERAPY 668
- SOUND RESONATION THERAPY FOR TUMOR AND CANCER 668
- PREPARATION FOR TUMOR AND CANCER SOUND THERAPY 668
- THE PROPER AMOUNT OF TONE REGULATIONS 669
- SPECIALIZED PRESCRIPTIONS FOR TUMORS AND CANCER 669
- CONTRAINDICATIONS FOR TUMOR AND CANCER SOUND THERAPY 673

CHAPTER 41 MEDICAL QIGONG REGULATION EXERCISES 675
- INTRODUCTION 675
- STARTING AND ENDING THE PRESCRIPTIONS 675
- MEDICAL QIGONG CULTIVATION EXERCISES 676
- EXTERNAL QI CULTIVATION 676
- INTERNAL QI CULTIVATION 677
- REGULATING THE BODY'S QI 678
- THE FIRE PATH OF THE MICROCOSMIC ORBIT 678
- THE WATER PATH OF THE MICROCOSMIC ORBIT 681
- THE WIND PATH OF THE MICROCOSMIC ORBIT 681
- MEDICAL QIGONG PRESCRIPTIONS 682
- DESCEND THE QI AND CLEANSE THE ORGANS 682

GATHERING QI IN THE UPPER AND LOWER DANTIANS 684
ROLLING THE BALL WITH BOTH PALMS 686
OPENING AND CLOSING THE UPPER, MIDDLE, AND LOWER BURNERS 687
SUN AND MOON ROTATING TECHNIQUE 689
EXPANDING AND CONTRACTING THE RINGS 691
DESCENDING THE YANG AND ASCENDING THE YIN TECHNIQUE 691
TURNING AND WINDING THE BELT VESSEL TECHNIQUE 693
OPENING AND CLOSING THE HEAVEN AND EARTH TECHNIQUE 695
COLLECT THE QI AND RETURN TO THE LOWER DANTIAN TECHNIQUE 697
QIGONG SELF-HEALING MASSAGE AND POINT THERAPY 698
WASH THE FACE 698
MASSAGE THE HEAD 698
BEATING THE HEAVENLY DRUM 699
PRESSING THE EARS 699
RUBBING THE EYES 699
MASSAGING THE NOSE 700
CLICKING THE TEETH 700
WAGGING THE TONGUE 701
SWALLOWING THE SALIVA 701
WHIRLING THE NAPE AND TURNING THE NECK 701
MASSAGING THE CHEST AND ABDOMEN 702
MASSAGE TAPPING THE HANDS (LI-4) 702
MASSAGE TAPPING THE FOREARMS (PC-6) 702
MASSAGE TAPPING THE ELBOWS (LI-11) 702
MASSAGING UNDER THE ARMS (HT-1) 703
MASSAGE TAPPING THE UPPER SHOULDERS (GB-21) 703
MASSAGING THE ARMS 703
MASSAGE TAPPING THE LOWER DANTIAN (CV-6) 703
MASSAGE TAPPING THE BACK OF THE WAIST (GV-4) 704
MASSAGE TAPPING THE SIDES OF THE HIPS (GB-30) 704
MASSAGE TAPPING THE THIGHS (GB-31) 704
MASSAGE TAPPING THE OUTSIDE OF THE KNEES (GB-34) 704
MASSAGE TAPPING THE INSIDE OF THE KNEES (SP-9) 705
MASSAGE TAPPING THE BACK OF THE KNEES (BL-40) 705
MASSAGE TAPPING BELOW THE KNEES (ST-36) 705
MASSAGE TAPPING ABOVE THE MEDIAL MALLEOLUS (SP-6) 706
MASSAGE TAPPING THE HEELS (KD-1) 706
TREMBLING THE KNEES 706
CIRCLING THE ABDOMEN 706
COMPLETING THE EXERCISE 707

CHAPTER 42 DAOIST QIGONG REGULATION EXERCISES 709
DAOIST FIVE YANG ORGAN REGULATION EXERCISE 709
DAOIST FIVE YIN ORGAN TONIFICATION AND REGULATION EXERCISES 710

SECTION X

TREATMENT OF INTERNAL DISEASES WITH QI EMISSION THERAPY 723
INTRODUCTION 724

CHAPTER 43 QI EMISSION THERAPY FOR LIVER DISEASES 725
INTRODUCTION 725
LIVER COMPLICATIONS AND SYMPTOMS 726

General Treatment for Liver Diseases 726
Medical Qigong Therapy for Liver Qi Dysfunction 726
Liver Qigong Prescriptions 728
Medical Qigong Therapy for Specific Liver Diseases 730
Disorders of the Biliary Tract 730
Gallstones 731
Cirrhosis 732
Cholecystitis 733
Hypochondriac Pain 734

Chapter 44 Qi Emission Therapy For Heart Diseases 735
Introduction 735
Heart Complications and Symptoms 735
General Treatment for Heart Diseases 736
Medical Qigong Therapy for Heart Qi Dysfunction 737
Heart Qigong Prescriptions 737
Specific Medical Qigong Therapy for Heart Diseases 738
Hypertension 738
Palpitation 742
Rheumatic Heart Disease 743

Chapter 45 Qi Emission Therapy for Spleen/Stomach Diseases 745
Introduction 745
Spleen Complications and Symptoms 745
General Treatment for Spleen Diseases 746
Medical Qigong Therapy for Spleen Qi Dysfunction 747
Specific Medical Qigong Therapy for Spleen Diseases 749
Diabetes 749
Medical Qigong Therapy and Stomach Diseases 750
Stomach Complications and Symptoms 750
General Treatment for Stomach Diseases 751
Specific Medical Qigong Therapy for Stomach Diseases 751
Abdominal Pain 751
Chronic Gastritis 754
Gastric and Duodenal Ulcers 755
Chronic Constipation 756

Chapter 46 Qi Emission Therapy and Lung Diseases 759
Introduction 759
Lung Complications and Symptoms 759
General Treatment for Lung Diseases 761
Medical Qigong Therapy for Lung Qi Dysfunction 761
Lung Qigong Prescriptions 761
Specific Medical Qigong Therapy for Lung Diseases 762
Treating the Common Cold and Influenza 762
Chronic Bronchitis 764
Asthma 764
Bronchiectasis 766
Sinusitis 767

CHAPTER 47 QI EMISSION THERAPY FOR KIDNEY DISEASES 769
- INTRODUCTION 769
- KIDNEY COMPLICATIONS AND SYMPTOMS 770
- GENERAL TREATMENT FOR KIDNEY DISEASES 770
- MEDICAL QIGONG THERAPY FOR KIDNEY QI DYSFUNCTION 771
- KIDNEY QIGONG PRESCRIPTIONS 772
- SPECIFIC MEDICAL QIGONG THERAPY FOR KIDNEY DISEASES 773
- TINNITUS AND DEAFNESS 773
- LUMBAGO 774
- INSOMNIA 775
- PYELONEPHRITIS 776
- IMPOTENCE 777

CHAPTER 48 QI EMISSION THERAPY FOR MISCELLANEOUS DISEASES 781
- INTRODUCTION 781
- DEFICIENT DANTIAN QI 781
- PRESCRIPTIONS FOR REGULATING THE THREE DANTIANS 781
- IMPROPER YIN AND YANG ENERGY BALANCE 782
- DISORDERS OF THE QI 783
- REBELLIOUS QI DISORDERS 784
- ARTHRITIS 784
- VERTIGO 786
- HEADACHES 787
- MIGRAINE HEADACHES 789

SECTION XI

SPECIALIZED QI EMISSION THERAPY FOR PEDIATRICS, GERIATRICS, GYNECOLOGY, NEUROLOGY, PSYCHOLOGY, ONCOLOGY, AND SURGERY 793

INTRODUCTION 794

CHAPTER 49 QI EMISSION THERAPY FOR PEDIATRICS 795
- INTRODUCTION 795
- EARLY STAGES OF CHILD GROWTH AND DEVELOPMENT 795
- PATHOLOGY 796
- DEFICIENT LUNGS 796
- DEFICIENT SPLEEN 796
- DEFICIENT KIDNEYS 796
- LIVER YANG EXCESS 796
- HEART (SHEN) IMBALANCE 796
- HOT AND COLD EXOGENOUS FACTORS 797
- THERAPY 797
- ENERGETIC MOVEMENT AND FLOW 797
- MEDICAL QIGONG EXERCISE PRESCRIPTIONS FOR CHILDREN 797

CHAPTER 50 QI EMISSION THERAPY FOR GERIATRICS 801
- TREATING THE PATIENT'S EMOTIONAL STABILITY 802
- ENERGIZING THE PATIENT'S QI CIRCULATION 802
- TAPPING THE KNEES TO PREVENT SENILITY 803
- CULTIVATING THE PATIENT'S YUAN QI BY ABSORBING ENERGY FROM NATURE 803
- FURTHER OBSERVATIONS AND INSIGHTS ON GERIATRIC PATIENTS 804

Chapter 51 Qi Emission Therapy for Gynecology 807
Introduction 807
Menstrual Flow 807
Qi and Blood Regulation 807
Etiology and Pathology of Gynecological Diseases 808
Vaginal Discharge 809
Menstrual Complications 810
Dysmenorrhea 810
Menoxenia 812
Cysts and Tumors 812
Breast Cysts and Benign Tumors 812
Level-1 Breast Cysts (Benign Lumps, Nodules or Fibroadenoma) 813
Level-2 Breast Cysts (Mastitis or Carbuncle) 813
Level-3 Breast Tumors 813
Overview of Treatment 814
Ovarian Cysts and Uterine Tumors 815
Uterine Complications 816
Miscarriage 816
Uterine Complications Due to Abortions 818
Understanding Energetic Abortions 819

Chapter 52 Qi Emission Therapy For Neurology (Stroke, Coma, Paralysis, and Multiple Sclerosis) 821
Introduction 821
Stroke (Wind-Stroke) 821
Coma 823
Facial Paralysis (Bells Palsy) 824
Multiple-Sclerosis (MS) 825

Chapter 53 Qi Emission Therapy for Psychology 827
Introduction to Energetic Psychology 827
The Emotional Energy Stored within the Five Yin Organs 828
Excessive Anger Injures the Liver (Wood) 829
Excessive Joy Injures the Heart (Fire) 830
Excessive Worry Injures the Spleen (Earth) 831
Excessive Sadness and Grief Injures the Lungs (Metal) 832
Excessive Fear Injures the Kidneys (Water) 834
Five Yin Organ Emotional Responses 835
Emotional Disharmony 836
Emotional Frequency Resonation 838
Differentiation of Psycho-Emotional Disorders 839
Self-Treatment Prescriptions for Psycho-Emotional Disorders 840
Treating Emotional Anxieties, Phobias, and Addictions 840
Treating Phobias and Depression Using "The Windows of the Sky" Points 844
Treating Psycho-emotional Disorders Related to Stress 848
Treating Stagnant Lung Qi and the Repression of Grief 850

Chapter 54 Qi Emission Therapy for Oncology 853
History of Cancer Treatments 853
Categorization of Tumors 853
Three Formations of Cancer Growth 854

ETIOLOGY, THE SIX PATHOGENIC EVILS THAT CAUSE CANCER 855
EMOTIONAL COMPONENTS OF CANCER FORMATION 856
CANCER FORMATION AND THE PATIENT'S MIND, EMOTIONS, AND SPIRIT 857
STRESSFUL LIFE ACTIVITIES AND THE IMMUNE SYSTEM 858
USING MEDICAL QIGONG TO STRENGTHEN THE IMMUNE SYSTEM 859
CANCER TREATMENT METHODS 860
SOCIAL ONCOLOGY—ESTABLISHING A CANCER SUPPORT GROUP 861
SOCIAL ONCOLOGY WITHIN THE HOSPITALS 861
CANCER RESEARCH 862
MEDITATIONS FOR CANCER PATIENTS 862
SUMMARY 864
TREATING TUMORS AND CANCER WITH MEDICAL QIGONG THERAPY 864
BRAIN TUMORS 864
BREAST CANCER 865
UTERINE CANCER 866
CERVICAL CANCER 867
PROSTATE CANCER 869
LUNG CANCER (PULMONARY CARCINOMA) 871
LIVER CANCER 871
ESOPHAGEAL CANCER 872
STOMACH CANCER 873
PANCREATIC CANCER 873
COLON AND RECTUM CANCER 874

CHAPTER 55 QI EMISSION THERAPY FOR RADIATION AND CHEMOTHERAPY 877
MEDICAL QIGONG THERAPY AND RADIATION THERAPY 877
MEDICAL QIGONG THERAPY AND CHEMOTHERAPY 877
RELIEVING SYMPTOMS ASSOCIATED WITH RADIATION AND CHEMOTHERAPY 878

CHAPTER 56 QI EMISSION THERAPY FOR SURGERY 879
MEDICAL QIGONG AND PREOPERATIVE THERAPY 879
USING MEDICAL QIGONG FOR ANESTHESIA 880
MEDICAL QIGONG THERAPY AND SURGERY 882
MEDICAL QIGONG AND POSTOPERATIVE THERAPY 882
MEDICAL QIGONG THERAPY AND RECREATING ORGAN ENERGY 883
MEDICAL QIGONG THERAPY AND ORGAN TRANSPLANTATION 885
FOLLOW-UP AND REMEDIAL PRESCRIPTIONS 885
PHANTOM PAINS OF AMPUTATED ORGANS 887
MEDICAL QIGONG THERAPY AND THE TREATMENT OF SCAR TISSUE 887

SECTION XII
MEDICAL QIGONG APPENDICES 889

INTRODUCTION TO THE APPENDICES 890

APPENDIX 1A MEDICAL APPLICATIONS OF QIGONG 891
ABSTRACT 891
INTRODUCTION TO MEDICAL QIGONG 891
EXAMPLES OF MEDICAL APPLICATIONS OF QIGONG 892
THERAPEUTIC BALANCING OF THE CHANNELS AND FUNCTIONS OF THE BODY 892
HYPERTENSION 893
PREVENTION OF STROKE AND MORTALITY 893

Improvements in Heart Function and Microcirculation ... 894
Improvement in Sex Hormone Levels ... 895
Increased Bone Density ... 895
Cancer ... 896
Reversing Senility ... 897
Mind-Body Regulation ... 898
Brain Waves ... 898
Blood flow to the Brain ... 898
Effect of Rapid and Large Changes in Altitude ... 898
Cardiac Function ... 898
Microcirculation Disorders ... 899
Study of Lung Function ... 899
Summary and Conclusions ... 899
References ... 900

Appendix 1B Anti-Aging Benefits of Qigong ... 903
Introduction ... 903
Clinical Studies Indicating the Anti-aging Benefits of Qigong ... 903
Therapeutic Balancing of the Channels and Functions of the Body by Qigong ... 904
Blood Pressure ... 904
Mortality and Stroke ... 904
Improvements in Heart Function and Mircrocirculation ... 905
Enhanced Activity of Anti-aging Enzyme SOD ... 905
Cardiovascular Function ... 905
Combination of Medical Qigong and Drugs Therapy ... 906
Conclusions ... 906
References ... 907
Endnotes ... 907

Appendix 1C The Effect of Qigong on Therapeutic Balancing Measured by Elextroacupuncture According to Voll (EAV): A Preliminary Study ... 910
Abstract ... 910
Introduction ... 910
Materials and Methods ... 911
Results and Discussion ... 911
Conclusions ... 913
Acknowledgements ... 913
References ... 913

Appendix 2 Scientific Investigations into Chinese Medical Qigong Therapy ... 917
Introduction ... 917
Qigong Masters and Energetic Medicine ... 918
The Science of China ... 918
Qigong's Long History ... 919
Simulation of Emitted Qi ... 920
Scientific Plausibility of Qi, the Human Energy Field ... 920
References ... 921
The Future of Qigong ... 921
Infrasonic Qigong Research ... 922
Infrasonic Simulation of Emitted Qi from Qigong Masters ... 922
Summay of Research ... 922
Doubts about Emitted Qi ... 922

BACKGROUND 923
THE BRAIN AS A DETECTOR OF EMITTED QI 923
SCIENTIFIC CONTROLS 924
INFRASONIC VS. ELECTROMAGNETIC INTERFERENCE 925
SUMMARY 925
SECONDARY ACOUSTIC BIOLOGICAL RESPONSE 925
MEASUREMENT AND ANALYSIS OF INFRASONIC WAVES FROM EMITTED QI 927
NEURO SCIENCE—NERVE IMPINGEMENT AND EMITTED QI 928
INFRASONIC TREATMENT OF ASTHMA 929
TREATMENT METHOD 930
OBSERVATION CRITERIA—FOUR GRADES 930
THERAPEUTIC RESULTS 930
LABORATORY RESULTS 930
THE INFRASONIC SIGNAL FROM THE QIGONG PERSPECTIVE 931
MECHANISMS OF THE QGM 931
RELIEVES PAIN AND EDEMA 931
STRENGTHENS IMMUNE FUNCTION AND REDUCES INFLAMMATION 931
NORMALIZES AUTONOMIC NERVOUS SYSTEM 931
RELIEVES SOME SYMPTOMS OF HEART DISEASE 932
EMITTED QI TRAINING INCREASES INFRASONIC SOUND EMISSION OF HEALERS 932
SCIENTIFIC QIGONG RESEARCH 933
EFFECTS OF THE EMITTED QI ON HEALING OF EXPERIMENTAL FRACTURE 934
MEASURING QI IN THE BLOOD 935
EFFECTS OF QIGONG ON NEUROTRANSMITTERS 936
PHYSICAL CHARACTERISTICS OF EMITTED QI 937
RESULTS 938
SUPERCONDUCTING MAGNETOMETER MEASURES CHANGES DURING QIGONG 938
QIGONG AND CANCER 938
THE EFFECT OF THE EMITTED QI ON CARCINOMA CELLS 939
THE EFFECT OF EMITTED QI ON THE GASTRIC ADENOCARCINOMA CELLS: 939
SUMMARY: 940
QIGONG AS A THERAPEUTIC AID FOR ADVANCED CANCER PATIENTS 940
THE EFFECT OF EMITTED QI ON LEUKEMIA IN MICE 941
EFFECTS OF QIGONG ON MALIGNANT TUMOR 942
EFFECTS OF PATIENT TUMORS ON KIRLIAN IMAGES OF HEALTHCARE PROVIDERS 943
CHAOS AND CONSCIOUSNESS 945
LOW DIMENSIONAL CHAOS IN PRACTICING QIGONG 945
QIGONG TRAINING AND COHERENCE OF EEG 946
VIBRATIONAL TREMBLING, CHAOS, AND EEG 946
LABORATORY TESTING 947
CHAOS AND THE COLLEGE ENTRANCE EXAM 947
SEARCHING FOR JING, QI, AND SHEN IN WESTERN SCIENCE 948
CONCLUSION 949
THE ROLE OF CHAOS IN DISEASE AND HEALING 950
THERAPEUTIC CHAOS 951
IMPLICATIONS OF SCIENTIFIC QIGONG RESEARCH 952

APPENDIX 3 THE PSYCHOLOGICAL AND ENERGETIC MECHANISMS TRIGGERED IN THE HUMAN SYSTEM BY THE SELF-APPLIED HEALTH ENHANCEMENT METHODS QIGONG, TAIJI, AND YOGA 957
OXYGEN 957
LYMPH SYSTEM FUNCTION 960
BRAIN AND NERVOUS SYSTEM FUNCTION 964
ENERGETIC MECHANISMS 967
CONCLUSION 968
REFERENCES 970

GLOSSARY OF TERMS 973

BIBLIOGRAPHY 1003

CLINICAL REFERENCES 1009

INDEX 1011

ABOUT THE AUTHOR 1029
MEDICAL BACKGROUND 1029
MARTIAL ARTS BACKGROUND 1031

ADDITIONAL BRANCHES OF THE INTERNATIONAL INSTITUTE OF MEDICAL QIGONG 1033
BRANCHES WITHIN THE UNITED STATES 1033
INTERNATIONAL BRANCHES 1035

FORWARD

Dr. Jerry Alan Johnson's book on Medical Qigong and its clinical practices provides an important and necessary guide for students and advanced practitioners of Medical Qigong and Traditional Chinese Medicine.

The relevance of Dr. Johnson's Medical Qigong textbook can be seen against the larger back drop of alternative medicine. Alternative Medicine (also called complementary medicine) has become a catch word in the West and an increasingly important factor in health care. An article authored by David Eisenberg and others of the Harvard Medical School reported that in 1993, 30% of a group of people used some kind of Alternative Medicine for which they paid out of their own pockets. Extrapolated to the United States population, this group spent about $14 billion dollars, which was more than the amount spent on conventional Western care that year.

Among alternative medical therapies, Medical Qigong has blossomed explosively in Western countries during the past few years. Awareness of Medical Qigong in the United States was heightened by two international conferences on Qigong in 1990. In 1997, there were three conferences on Medical Qigong, in San Francisco, Minneapolis, and New York. Another catalyst was Bill Moyer's television documentary, "Healing and the Mind," which had a segment on Medical Qigong and Chinese medicine. In more recent years, dozens of books have been published on Qigong in English and presently there are at least 15 web sites on the World Wide Web devoted to Qigong. At this writing, many articles on Qigong have appeared in the newspapers and magazines, and several documentaries have been videotaped and others are in progress.

In China, almost everyone knows about Qigong and about 100 million people are said to practice it daily. Qigong dates back thousands of years. Many believe that it was responsible for the early development of Chinese medicine, which now includes therapy by acupuncture, herbs, massage, and nutrition.

Medical Qigong therapy was a secret art that was passed on from a master to selected persons. In the 1970s, Qigong became more accessible to the people when the Chinese government ordered that Medical Qigong be made public and serve alongside Western medicine to improve national health care. During the Cultural Revolution, Medical Qigong was suppressed because the government suspected that Qigong had religious and superstitious roots incompatible with communism. In the early 1980s, scientist in China were encouraged to carry out experimental and clinical studies into almost every aspect of how Medical Qigong affected the human body and contributed to healing. Starting in 1986, research findings were reported at international conferences on Medical Qigong held mostly in China but also in Japan, Canada, and the United States. The substance of the research studies are available in English in the Computerized Qigong Database, which was developed by the Qigong Institute. This database has provided a basis for the preparation of at least five books, three dissertations, and several research projects on Medical Qigong.

In 1992, the United States Congress recognized the potential of alternative / complementary medicine by mandating that the National Institutes of Health develop programs to evaluate the validity of selected alternative therapies. Since that time, the Office of Alternative Medicine has funded many research programs and disseminated valuable information to medical practitioners, scientists, and the public.

The swell in the interest in Medical Qigong and the recognition of its health and healing benefits have been recognized by schools of Traditional Chinese Medicine, many of which mandate that Qigong be a required course. The Qigong taught at these schools is still on a basic level and needs to be expanded to include the medical aspects of Qigong, such as described in this book.

The future of Medical Qigong and Chinese medicine appears bright. However, the need for well-trained and qualified teachers and practitioners is paramount to meeting the growing demand. Dr. Johnson's book provides the first guide in English for teachers, students, and practitioners.

Kenneth M. Sancier, Ph.D.
President Qigong Institute

FORWARD

In 1998, the Academy of Oriental Medicine at Austin gave me the opportunity to establish one of the first formal Medical Qigong training programs in the country to be offered within the context of a college of Oriental medicine. My greatest difficulty was in finding a reliable textbook for my classes. Of the numerous books on Qigong available in English, most devote only a few pages, at best, to Medical Qigong. Over the past few years, several books from China on Medical Qigong have been translated into English. Although presenting much new and valuable information, they are poorly translated and fraught with errors, making them unreliable as textbooks.

Therefore, it has been a great pleasure for me to have collaborated with Dr. Jerry Alan Johnson to some small extent on this book. Jerry Alan Johnson is one of the world's foremost authorities on the subject of Medical Qigong. This work distills several decades of his personal study, practice, and clinical experience in the United States and the People's Republic of China into an in-depth practical manual for all levels of Qigong healers.

Currently China is in the midst of what can only be called a Qigong renaissance. Today, more people are studying and practicing Qigong than in any previous time in Chinese history. In the not too distant past, Qigong was only available to monks and priests, nobles and the wealthy. Now Qigong is taught in China's primary schools and colleges, parks, temples, clinics, and hospitals to anyone who wants to learn.

China's literacy rate has increased exponentially since 1949, and now there are thousands of books, tapes, videos, and magazines on every aspect of Qigong, systems both ancient and modern, all available for general public consumption. Many regional, national, and international Medical Qigong associations have been formed, with an unprecedented exchange of information.

Although Medical Qigong has been a part of Traditional Chinese Medicine since the time of the Yellow Emperor, it has only been since 1982 that Medical Qigong hospitals and clinics have begun to spring up all over China. In the early days after the Communist Revolution of 1949, Qigong was more or less a state secret, and the Medical Qigong clinics were, for the most part, only available to high party officials. Over the past two decades, China has also devoted a great deal of effort to Qigong research and education. There are now large Medical Qigong hospitals in all of China's major cities, some of which have over 300 beds and 40 or more Qigong specialists and nurses on staff. There are hundreds of medium-and small-sized Medical Qigong clinics throughout the country, some treating inpatients and others treating only outpatients.

Before the revolution, the miracles of modern Western medicine, with its wonder drugs and surgical procedures, had caused many Chinese to see their own native traditional medicine as old-fashioned and outdated. The government encouraged the development of Western medical schools and hospitals. After the revolution, Chairman Mao recognized that with China's huge population they would need to take advantage of every form of medicine available even to begin to meet the nation's fundamental health care needs.

China is the only county in the world where Medical Qigong has been truly integrated and enthusiastically accepted as part of the national health care delivery system. According to current estimates, Medical Qigong doctors are now meeting 15% of China's national medical needs. That percentage is still growing. For decades, Chinese hospitals have successfully offered Traditional

Chinese Medicine alongside of Western medical services. Patients may receive Qigong or acupuncture anesthesia during Western surgical procedures and be treated by Medical Qigong, acupuncture, and Chinese herbal medicines during recovery. Chronic patients may be diagnosed by Western physicians, sent to Medical Qigong clinics for treatment, and have their Western doctors monitor their progress. In this respect, China has truly set the standard for the twenty-first century medicine.

Medical Qigong training and practice takes many forms in China. Some practitioners/healers are thoroughly trained in both Traditional Chinese Medicine and Western medicine, in addition to Medical Qigong. Others are heirs of family Medical Qigong systems, some dating back over a thousand years. Not all of these family practitioners have received additional training in either traditional Chinese medicine or Western medicine, yet they have been very efficient in treating disease and disorders that these conventional medicines have given up on. Still other practitioners come from martial arts backgrounds, such as Shaolin Gongfu or Daoist martial Qigong, with their own effective and unique blend of warrior training, spiritual discipline, Qigong and healing arts. Each of these categories contributes to the richness and diversity of the art of Medical Qigong.

Jerry Alan Johnson presents for us the art of Medical Qigong as it is being taught in two of the major Medical Qigong training centers in China today: the Xi Yuan Hospital of Traditional Chinese Medicine and its associated Hai Dian Medical Qigong College. Although each Qigong hospital in China defines its own program of training and practice, the material Johnson includes in this work represents the mainstream curriculum of study and practice widely accepted nationwide as a high standard of competence in Medical Qigong.

In addition to sharing the high-level protocols of Medical Qigong training in China, Johnson also draws from the reservoirs of his own decades of personal training and teaching in the internal martial arts to further enrich this work. Martial Qigong is generally practised to improve one's martial arts prowess. It includes Qigong exercises for strengthening the body; increasing power of one's strikes by emitting Qi; mind and will training; learning the vulnerable points to strike on an opponent's body to cause pain and paralysis; learning to cause serious injury or death by disrupting or destroying an opponent's internal organs, Qi and blood vessels, joints or bones; and toughening the body to withstand strikes and blows.

In what might at first seem a case of strange bedfellows, the martial Qigong tradition also has its medical side. Martial artists need to learn how to set bones and dislocations, as these injuries are commonly encountered in training and combat. Martial artists who train in the more secret arts of tien xue (vital point striking) and dim mak (death touch) are also taught how to heal the injuries that they have caused, both to heal themselves if struck by someone and to heal their opponents if the opponent is penitent. Furthermore, the martial artist who learns the methods for destroying the internal organs by emitting Qi can effectively adapt the same method to destroying pathogens and tumors in a patient for healing. Internationally recognized by his peers for his mastery of the most esoteric aspects of the internal martial arts, Johnson is eminently qualified to present its healing traditions, which he generously and openly does in this work.

I am grateful to know Dr. Jerry Alan Johnson as a colleague, teacher, and friend, and am happy to recommend this work to all students of Medical Qigong with confidence. Johnson's contribution contained herein represents the most thorough and comprehensive presentation of the art and science of Medical Qigong in the world to date. It is sure to become a modern standard of reference for anyone seeking knowledge of Medical Qigong.

Jampa Mackenzie Stewart, D.O.M.
Dean of Medical Qigong
Academy of Oriental Medicine at Austin

FORWARD

In the summer of 1995, I was sitting on the floor of Dr. Johnson's studio waiting for the start of the intermediate class in Medical Qigong. David Nakahara leaned over to introduce himself and asked me if I was a healer. Wow! It was one of those seminal moments in one's life. I considered all the implications of this question and the only relevant reply I, as a medical doctor, could muster was an ironic chuckle.

That question speaks to the heart of the current crisis in health care. Allopathic medicine lends itself to standardization of care and computer algorithms, since the structure of the clinical visit is based on protocol-derived diagnosis and treatment. The challenge is the diagnosis, but the treatment, especially high-tech treatment, gets all the press. It is incredibly satisfying to take care of people in this manner since the issues are clear and everyone gets better, unless they fail treatment; in this paradigm, the patient fails the treatment, the treatment does not fail the patient.

However, over time, you accumulate a number of patients for whom your therapeutic protocol fails, and I think that all thoughtful physicians recognize that it is these patients that teach us the most. There are women who have serious difficulty with PMS, infertility, and menopause. The cancer patients often wonder what caused the cancer to occur, what supports it, and what the meaning of this potentially fatal illness is for them. As physicians, once we emerge from the narcosis of fatigue and busyness that accompanies the daily practice of medicine in the late twentieth century, we also ask these same questions.

And we seek answers. Each physician develops his or her own rationale for treatment failures. They may rely on an unshakable faith in the scientific method, their religious upbringing or in their cultural ideals, or perhaps close themselves off entirely. I inadvertently found my answer within the martial arts.

It was clear to me from my Aikido practice that the superior martial artist must understand Qi in all its manifestations. This quest for deeper knowledge and experience of Qi led me to study Qigong with Dr. Johnson.

In my earliest lessons with Dr. Johnson, I was told that a Qigong therapist must observe and treat patients' *three treasures*: the physical body (jing or essence), their energy (Qi), and their mind/spirit/intention (shen). These three form the whole of a human being, and the parts can only be understood within the context of the whole. Furthermore, I learned that in life these three are so interrelated that it is difficult to tell where one leaves off and the other begins. Over 2,000 years ago, the Chinese philosopher Lie Zi described this by saying, "The mind leads and the Qi follows; the Qi leads and the body follows."

As a scientist, I could not help but draw the parallel between these fundamental Qigong principles and the revolutionary views of advanced modern physics: that at the deepest sub-atomic levels, matter, energy, and the person viewing them are so inextricably intertwined that they are seen as virtually one and the same, merely different manifestations of the same pattern. No longer is energy defined as a wave while matter is composed of particles. In quantum physics they have coined the term *wavicle* beause particles act as waves in one situation and as particles in another, as "probabilities" rather than concrete fixed entities and as subjective reality rather than objective.

The application of the discoveries of quantum physics to biology is just beginning. It is starting not only in the laboratory but also in many consulting rooms across the United States, as physicians search for the answers to help their patients.

I think that quantum physics is the only "hard" science that you can research just by thinking about it. As one observes the processes of nature, the thoughtful observer comes to the conclusion that there must be something else that accounts for the medical journey of the exceptional patient. The early practitioners of Ayurvedic and Chinese Medicine were careful observers of nature and through observation formulated the basic principles of Indian and Asian medical systems that are also corollaries of the principles of quantum physics.

Western awareness of the potential for the integration of the East and West began in 1971 when Nixon first went to China. James Reston, a *New York Times* correspondent covering the historic visit, developed acute appendicitis. After his emergency appendectomy, he was successfully treated with acupuncture for post-surgical pain.

Despite the dynamic nature of the penultimate Western nonbeliever confronting a totally novel experience ("only Nixon could go to China"), nothing much shifted or changed in medical practice at that time. What was missing was the readiness and ability to experience a paradigm shift in the conceptual basis of the causation of disease. Paradigm shifts in basic research have been eloquently discussed in Thomas Kuhn's landmark book, *The Structure of Scientific Revolutions*. Kuhn's brilliant analysis of the development of knowledge has recently been applied to medical science in a new book, *From Doctor to Healer: The Transformative Journey*, by Robbie Davis-Floyd and Gloria St. John. After 30 years, we are finally mature enough to begin to reassess the structure of our medical belief systems and to incorporate both world medicine and the principles of quantum physics. I have no doubt that this will take decades, but there is no doubt that the shift is beginning to occur.

Dr. Jerry Alan Johnson's book represents a major advance in this journey. This textbook is the first comprehensive treatise on the principles of Chinese energetic medical practice available to the Western medical practitioner. It also forms a bridge for the Western trained practitioner of Traditional Chinese Medicine and the allopathic (Western) practitioner. Dr. Johnson's book represents decades of research and study, and a nonjudgmental openness to any healing modality that is in the patient's best interest. I have no doubt that this book will represent a significant advance in that long awaited paradigm shift. I look forward to that time because it will address the deeper human values that have been neglected in protocol-based medicine and will bring a new depth of engagement and satisfaction to patient care.

Stephanie S. Taylor M.D., Ph.D.

Footnotes:

Kuhn, Thomas S., *The Structure of Scientific Revolutions*, University of Chicago Press, Chicago, Illinois 1962.

Davis-Floyd and Gloria St. John, *From Doctor to Healer: The Transformative Journey*. Rutgers University Press, New Brunswick, N.J., available March 1998.

FORWARD

In the Western nations at the turn of the millennium, following a century of remarkable medical breakthroughs, there still remains a major list of unsolved medical mysteries and health care challenges. Chronic disease has not been alleviated (asthma, arthritis, etc.); stress has been recognized as a major cause in many diseases; tumors and cancers are being diagnosed in exponentially growing numbers; AIDS is a world wide epidemic; negative (Western) drug interactions have grown to become the fourth leading cause of death, and medical error has emerged as the eighth cause of death. According to the Department of Health and Human Services, over 70% of medical visits are for symptoms and illnesses that are preventable, yet the health care system is still primarily focused on treatment of the symptoms rather than health maintenance or prevention.

The public, the government, and health care providers all agree that there is a crisis in Western medicine and health care. Fortunately, at the same time, there is increasing support for innovative and alternative solutions. Among the many powerful strategies for solving this crisis, Chinese Medical Qigong (Chi Kung) and its offspring Taijiquan (Tai Chi Chuan), meditation, and focused breath practice, are probably the most comprehensive systems of self-care and healing available to compliment both conventional Western and alternative medical therapies.

The public hunger for natural healing, safety from medical side effects, lower medical costs, and health self-reliance is triggering powerful and profound changes in health care. It has become obvious that in the near future the benefits of Chinese medicine will be as fully integrated here in the U.S., as the benefits of Western medicine are in China. Through this global exchange of health care wisdom and practical applications, we are entering an unprecedented era of new possibilities to resolve suffering and foster well-being.

This definitive work on Medical Qigong, the remarkable healing art from Chinese traditional medicine, will play a significant role in the immense and profound transformation in health care that is now occurring with tremendous social and economic force.

Like the revolution in training and licensing acupuncturists that quickly unfolded in the final years of the 20th century, the momentum of training and licensing Medical Qigong Therapists is rapidly increasing in the beginning of the 21st century. Clinical Qigong, including both Medical Qigong Prescriptions and Medical Qigong Therapy, will arise in America as it has done so robustly in China.

There are a number of excellent books on various aspects and methods of Qigong. However, there has not been, in English, a comprehensive exploration of Medical Qigong. Dr. Johnson has created a breakthrough work on Medical Qigong, which is a clear and useful revelation of the Medical Qigong curriculum at the Hai Dian University Medical Qigong College of Beijing, China, and an excellent synthesis of Medical Qigong theory from throughout China. This textbook will very likely remain the definitive compendium of Medical Qigong in the West for many years, and become the foundation from which the field of Medical Qigong will evolve in Western society.

Roger Jahnke, O.M.D.
Chair, Department of Medical Qigong
Santa Barbara College of Oriental Medicine

PREFACE

As we enter the new millennium, a new era of medical therapy is beginning to blossom. Alternative medicine is now capturing an estimated $14 billion in out-of-pocket health care revenues from Americans each year, according to a 1993 study published in the *New England Journal of Medicine*. By 1997, according to the *Journal of American Medical Association*, that figure had more then doubled. What this trend means in real terms, is that despite the historical lack of official recognition by the American Medical Association, despite the lack of endorsement and coverage by Medicare and the majority of health insurance plans, men and women, in ever increasing numbers, are going to acupuncturists, energetic healers, herbalists, chiropractors, massage therapists, ayurvedic specialists, homeopathic doctors, and other traditional "healers" to meet some portion of their health care needs.

This growth of public reliance on alternative medicine has caused the Western medical establishment to sit up and take notice. In fact, some of the most vocal proponents of combining alternative medical traditions with Western medicine are medical doctors. Visionary physicians such as Deepak Chopra, Andrew Weil, Larry Dossey, Dean Ornish, and Bernie Seigel have led the way toward creating a new climate of respect for ancient medical philosophies and modalities. They have pioneered the advent in the West of health care facilities where Western medical and alternative health modalities are available under the same roof, with the goal of providing patients with the best of both worlds. This combination of ancient and modern medical traditions has been dubbed *integrative* or *complementary* medicine.

In comprehending the full implications of this unlikely marriage, one must understand the divergent approaches to healing between conventional Western medicine and traditional Eastern medicine.

Contemporary Western medicine grew out of the scientific revolution of the seventeenth century. The philosophy of science, rooted in Aristotle's "empirical materialism," was given a new spin by the French mathematician, Descartes. Viewing reality as that which could be substantiated materially, Descartes applied an analytical reductionist logic to penetrating the secrets of nature, including biology. These views were echoed in the physics of Sir Isaac Newton, applying a linear cause-and-effect model to explain the workings of a material universe.

Man was seen as being separate from nature, mind was seen as separate from body, and all of these processes, in nature and in humans, were seen as similar to the workings of a machine composed of discreet parts. Mechanical laws were seen to govern all processes. Structure determines function; therefore, the physician's role developed into that of a mechanic: repairing, removing, transplanting, and replacing broken down-parts. Diseases had isolated causes, which need to be removed from the rest of the parts. Because of this approach, Western medicine has the most highly developed pharmaceuticals to kill specific organisms and the finest surgical procedures in the world today.

By contrast, Eastern medicine grew out of the empirical observation of nature, beginning at least 4,700 years ago. Oriental philosophy, from the Vedas of India to the Yellow Emperor of China, views reality as an interdependent whole. This "prescientific" understanding equates to the broader view of modern quantum physics and the general systems theory. Rather than limiting reality to that which is material, the Eastern philosophers recognized the interdependence of mind and body, the nonlinear nature of time and space, and the interweaving patterns of relationship between man and nature; in fact, they believed, we *are* nature. Anatomy, the study of human structure, takes a back seat to physiology, the study of human function. Thus, the Orientals formulated a general systems theory, in which the patterns of change that exist in nature are the same patterns that govern human biology, wherein function is viewed from a holographic perspective, and each part reflects the whole. Rather than being fixed and stable, the whole is in a dynamic process of constant change. For the whole to function harmoniously, every part must remain in balance. Therefore, the role of the Oriental physician is more similar to a gardener, following the patterns of change, diagnosing functional disharmony and restoring overall balance. Because of this approach, Oriental medicine has some of the most highly developed procedures for preventative medicine and for treating chronic diseases in the world today.

Western medical science, with its fundamental distrust of subjective diagnostic reliability, has progressed toward developing more and more expensive high-tech laboratory tests and diagnostic equipment. Thus we have the modern miracles of x-rays, MRI's, and ultrasound. Eastern medicine, trusting in human capacity, has progressed in a low-tech direction toward ever deeper training of the physician's sensory and spiritual diagnostic tools. Thus, we have the miracles of pulse diagnosis, tongue reading, and Qigong hand scanning.

With such fundamental divergencies in philosophy and technique, it is almost inconceivable that these two medical systems could ever operate together in the same setting. The fact is that they do function together, and quite effectively, too. We can thank Mao Zedong for the union of these two unlikely bedfellows.

Recognizing that there were far too few Western trained physicians and nurses to meet the primary health care needs of China's vast population, from the outset of his leadership Mao advocated the systemization of Traditional Chinese Medicine (TCM), and advocated its implementation alongside Western medicine in China's hospitals and clinics. The results of this integration have been astonishing, as witnessed in the effective use of acupuncture anesthesia during surgery.

Nonetheless, in his efforts to create a "modern" Chinese medicine, Mao shunned some of the traditional theoretical aspects of Chinese medicine, such as the concept of Qi, which he considered as feudalistic and counterrevolutionary. For this reason, he actively discouraged Medical Qigong practice as superstitious. It was not until the end of the Cultural Revolution in 1975 that Qigong reclaimed its rightful place as one of the major branches of Chinese medicine.

A high party official in Beijing was suffering from an "incurable" disease. Both Western medicine and TCM had failed to alleviate his suffering. In desperation, he went to one of the few Medical Qigong clinics operating in the country and was cured. The official then lent his support to the promotion of Medical Qigong for the benefit of the Chinese people. Before long, there were hundreds of Medical Qigong hospitals and clinics throughout China.

Since that time, Qigong has experienced an unprecedented growth in China. Qigong is now available to the general populace for the first time in history. Qigong is now taught in the public education system, beginning at the elementary school level. Qigong departments have been added to large urban hospitals. Colleges of Traditional Chinese Medicine have developed Medical Qigong training programs. According to one recent survey, one third of the population of Beijing, China's capital city, practices Qigong daily.

It has taken acupuncture and Chinese herbology nearly 20 years to develop into a respected profession in the United States. As this book goes to press, 37 states now have legislation licensing professional acupuncture practice, with an additional 10 states in which legislation has currently been introduced. Medical Qigong is still at the very early stages of public recognition, understanding, and acceptance by comparison. Oriental medical schools around the United States, as well as independent Medical Qigong masters, are only now beginning to establish comprehensive

Medical Qigong training programs. I am heartened by this development.

Traditional Chinese medical therapy is divided into four main branches: acupuncture, herbs and diet, massage therapy, and Medical Qigong. It is important for TCM practitioners to have exposure to all four branches to be able to understand the relative strengths and limitations of their particular field of expertise, so that they will be able to select the most effective and appropriate treatment modality for their patients. Until very recently, most schools in America have been relatively unaware of the extent to which Medical Qigong therapy has developed in China, and have been lacking in presenting Medical Qigong as a significant part of their training programs for students of Oriental medicine.

The purpose of this book is twofold. The first purpose is to apprise the reader of the professional standards of knowledge and skill required in contemporary China for licensing a "Doctor of Medical Qigong Therapy" (D.M.Q.). The second purpose is to describe how to effectively diagnose and treat patients with Medical Qigong therapy as set forth by the Hai Dian Medical Qigong College of Beijing and to provide a textbook for training to that standard under the guidance of a qualified instructor. Hai Dian is recognized as one of the top Medical Qigong colleges in China.

Although this book is primarily written for students and practitioners of Oriental medicine, it is also my hope that practitioners and students of Western medicine and other forms of alternative healing will benefit from the information contained herein, and that it may serve to enrich their practice in the healing arts.

This book is divided into twelve sections. The first four sections focus on building a comprehensive foundation in energetic medicine. The second four sections focus on guidelines for establishing a Medical Qigong clinic, as well as for diagnosing and treating problems of Qi deviations. The last four sections focus on treatment modalities, Medical Qigong prescriptions, Medical Qigong regulation exercises and scientific research in Medical Qigong clinical therapy.

I have done my best to present the knowledge and wisdom of this ancient Chinese art as it was passed onto me personally by my respected teachers, to whom I owe undying gratitude. Qigong has survived nearly five thousand years of growth and refinement and is now available to you, the reader, for your own personal and professional benefit. I sincerely hope that this book may serve to further bridge the partnership between Eastern and Western medicine, that all humanity may be the beneficiary of the interchange between these two great schools of healing. May all doctors and healers, Western and alternative, return to the "heart" of medicine, that each may view the patient as a complete integration of body, mind, emotion, energy, and spirit. May we support each other's skills and techniques in alleviating our patients' suffering.

Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
Dean of Medical Qigong Science
Director of Medical Qigong Clinic
Five Branches Institute, College & Clinic of TCM
Santa Cruz, California
May, 2000

ACKNOWLEDGMENTS

I would like to express my sincere gratitude to my many friends and colleagues who helped encourage and support me in writing this book: Roger Jahnke, O.M.D.; Hu Jiting, D.T.C.M.; Zhang Jingchuan, D.T.C.M.; Xu Zhuoqun, D.T.C.M.; Guo Xianhe, D.T.C.M.; Wan Taowang, D.M.Q.; William H. Lewington, L.Ac., M.Q.T.; Adam Atman, L.Ac. M.Q.T.; Tim M. Haun, D.C.; Kerrean D. Smith; Geoffrey Greenspahn M.Q.T.; Michael Winn; Mark Johnson; and my good friend Joseph Crandall.

I am also indebted to Dr. Pang Donghui, the Executive Deputy President of the Hai Dian Qigong College of Beijing, China, and to Li Fudong, D.M.Q. the university's chief director of Medical Qigong Science, and his assistants, Lu Guohong, D.M.Q. and Niu Yuhua, D.M.Q. for their constant support and encouragement, and for sharing their innermost secrets on Medical Qigong therapy.

I am very grateful to Dr. Teng Yingbo, D.M.Q., president and secretary general of the Beijing Western District Qigong Science and Research Institute, for his constant support and openness in sharing the knowledge of the Institute's clinical modalities.

A special thanks to Doctor Bi Yongsheng, D.M.Q.; Yu Wenping, D.M.Q.; and the Shandong Provincial Qigong Association for their wealth of knowledge and enthusiastic support, in sharing their clinical Qigong modalities, and to Dr. He Sihai, D.M.Q., of the Zhe Jiang Qigong Hospital for his openness and kindness in sharing his knowledge.

A special thanks to Qigong Master Zheng Zhanding, D.M.Q., for being my mentor, taking me under his wing, and teaching me advanced clinical modalities of energetic diagnosis and treatments, and to Qigong and Taiji Master Zhang Yufei for teaching, supporting, and encouraging my energetic and healing practice.

I am also indebted to Professor Lu and doctors Xu Hongtao, D.M.Q.; Ren Shuntu, D.M.Q.; Xu Zongwei, D.M.Q.; and the directors, teachers, interpreters and staff at the Xi Yuan Hospital of Traditional Chinese Medicine for their help and support.

I am very grateful to Sun Shuchun, D.T.C.M., the assistant professor and dean of the Beijing Academy of Acupuncture, Orthopedics, and Traumatology and the Hu Guo Si Hospital of Traditional Chinese Medicine for his assistance and support.

I would like to thank Doctor Meng Xiantong and Tara Peng, D.M.Q., of the Beijing Chengjian Integrated Traditional Chinese Medicine and Western Medical Experts Clinic for sharing their clinical modalities and their support.

I am very grateful to Madame Wang Yan of the China, Beijing International Acupuncture Training Center, the Acupuncture Institute of China Academy of Traditional Chinese Medicine, and the World Health Organization Collaborating Center for Traditional Medicine for supporting and believing in me.

I would also like to thank President Yue Licui, D.T.C.M., of the World Academic Society of Medical Qigong and all my friends and colleagues at the Beijing College of Traditional Chinese Medicine for their help and support.

A special thanks to Stephanie Taylor, M.D., Ph.D., whose encouragement and support has enabled Chinese Medical Qigong therapy to expand far into the terrain of conventional Western medicine, bridging the gap between these two schools with complementary modalities of healing.

A special thanks to Jason Gill, L.Ac., for his unselfish heart of giving and his invaluable help and technical input on Traditional Chinese Medicine, and his own personal experiences with Medical Qigong therapy.

A special thanks to Kenneth M. Sancier, Ph.D., and the Qigong Institute of Menlo Park, CA. Dr. Sancier's extensive research in Medical Qigong therapy, and the validity of its effect as a clinical modality is disclosed in Appendix 1 at the back of this text. Dr. Sancier is a council board member of the World Academic Society of Medical Qigong, sanctioned in Beijing, China.

A special thanks to Richard H. Lee. and the China Healthways Institute of San Clemente, CA. Mr. Lee's extensive research in the scientific investigations into Medical Qigong therapy and the validity of its effect as a clinical modality is disclosed in Appendix 2 at the back of this text. Mr. Lee is also a council board member of the World Academic Society of Medical Qigong, sanctioned in Beijing, China.

I greatly appreciate the assistance of Robert Collier, Jed Friedland, Stephanie Hensey, Terri Vandercook and Rose Mary Stewart, who spent many painstaking hours typing and deciphering my personal notes and course manuals. I would especially like to thank Jampa Mackenzie Stewart, D.O.M., L.Ac., Gaeir L. Dietrich, and Jean Vlamynck, M.Q.T., L.Ac., for their invaluable help and contribution in editing this textbook.

A special thanks to Madeleine H. Howell, M.F.T., as the senior editor of this manuscript for publication. Her keen eye for detail and constant encouragement to rewrite, explain and expound on the contents within this textbook, has resulted in a more comprehensive resource for future Medical Qigong students and Western medical professionals.

A special thanks to Robert Blaisdell and Tomo Y. for their excellent artwork and graphics, and to Y. S. Lim for his many painstaking hours of Translating Chinese Medical Qigong texts, which enabled me to draw from more comprehensive and clinical resources.

I am grateful to Willis Campbell and Niki Norrell, L.Ac., Dipl.Ac. (NCCA), M.T.C.M. for taking several of the photos.

A special thanks to Irene Morris for her excellent work on designing the front and back cover of this textbook.

Above all, I would like to express my love, gratitude, and respect to my parents Antoinette and Lt. Cdr. (Rt.) Perry E. J. Johnson for their years of love, understanding, encouragement, and support.

Finally, to my three beautiful daughters Laura, Leah, and Hannah, whom I will love forever.

INTRODUCTION

The Eastern approach in explaining medical concepts is generally expressed through a three dimensional convergence, seeing the physical body as an energetic hologram, and observing the physical, mental, emotional, energetic and spiritual reality of the tissues. By stimulating any one of these five energetic matrices, you affect the other four, and influence the body to initiate either health or disease. Diagnosis and treatment is therefore approached in a nonlinear progression, working towards the health and healing of the whole person.

The Western mind, however, is taught to view the physical body on a linear progression of cause and affect, separating the reactions of the tissues from the effect of the mind and emotions, as well as the universal and environmental influences. In order to help the Western mind understand the concept of Chinese energetic medicine, this Medical Qigong textbook was written with the goal of instructional comprehension and practical application of Chinese energetic medicine. It embraces the concepts of traditional Chinese medicine, in particular Medical Qigong therapy, from a progressive linear format. Beginning with Energetic Embryology in Section 1, it provides a basic understanding of complex energetic structure, theory, and practical application, ending in advanced clinical treatments in Section 11. The final chapters of this textbook, consists of scientific research collected from various doctors and research scientists which validate the claims made of Medical Qigong therapy being an effective clinical modality, in Section 12.

Chinese medical terminology is extremely metaphoric and is used to describe the many aspects of the human body through physical, mental, emotional, energetic, and spiritual domains of existence. Many technical terms in Traditional Chinese Medicine have numerous meanings, depending on the context of the subject.

For clarity, the Chinese terms in this book are capitalized along with the English words for which Traditional Chinese Medicine assigns a special meaning. Such words include, but are not limited to, the following: Gall Bladder, Small Intestine, Spleen, Pericardium, Bladder, Liver, etc. There is one exception to this rule; the word "energy" meaning Qi, is capped only in the first few chapters of this book for the sake of easier legibility, as it appears so often within each chapter.

When you see words such as Blood, Heart, and Marrow capitalized, assume that their meaning differs from that ascribed by Western medicine. In Traditional Chinese Medicine, the word Marrow, for instance, does not refer to bone marrow as it is traditionally recognized in the West, but rather describes the substance which is the common matrix of bones, bone marrow, the brain and spinal cord. Non-capitalized terms retain their traditional Western meanings.

One decision I have made when writing this textbook is to use the term "divine" when expressing the energy of the Dao or God. In China, many of the Qigong doctors and masters that I have trained with asked me to keep these spiritual theories in confidence for fear of governmental reprisal. Therefore, having decided to openly share these ancient energetic theories concerning the interactions of the spirit, soul and divine, I have done so without revealing my sources.

Finally, many of the energies used to describe the natural forces of nature (existing within Heaven, Earth, and Man) were historically changed into "gods" or "spirits" in order to compete with the colorful deities imported into China from India. Therefore, when reading this textbook, the reader should not become confused by certain terminologies describing "deities" which govern specific energetic principles. For example, when reading the section on the Eternal Soul, the title "Lords of the Three Dantians" implies the fact that the soul has three primary, separate, yet interconnected, energetic properties, rooted, divided and sustained within each of the Three Dantians.

Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)

SECTION I

FOUNDATIONS OF CHINESE ENERGETIC MEDICINE

CHAPTER 1
INTRODUCTION TO MEDICAL QIGONG

More than 5000 years ago, Chinese physicians came to understand that everything is composed of the same energetic substance called Qi (pronounced "chee"). These ancient masters concluded that there is a oneness and wholeness in all existence, and that energetically everything is interconnected as one body, although energy may appear to take on many different forms. All things in nature and, in fact, all things in the universe are woven together so that we are, quite literally, all symbiotically one with the universe through the system of Qi. Qi is always in motion within all things, and is the catalyst for everything to relate and interrelate within the universe.

In modern times, the laws of physics have demonstrated that matter and energy are interchangeable, and that matter is simply another form of energy. Matter is constantly vibrating in the form of tangible solids and intangible gases, and is constantly altering, being affected by, or interacting with energy. Energy is inherent in the living human body, and the human body is sustained by energy (Figure 1.1).

The ancients mastered techniques to balance the body's energy (Qi) in order to live in harmony with the environmental (Earthly) Qi as well as the universal (Heavenly) Qi. Traditional Chinese Medicine maintains that when living things start to lose their Qi, they lose their vitality. An ancient Chinese saying states, "Life comes into beginning because Qi is amassed; when Qi is scattered, the person dies."

Qi is stored within the body in the form of pools, creating the structures of the internal organs. From these internal pools, the body's life-force energy flows in the form of rivers and streams. These energetic rivers and streams form the body's vessels, channels, and collateral systems.



Figure 1.1. The Body's External Qi Field

THE FIVE DOMINIONS OF ENERGY

The ancient masters observed that Qi can be divided into five manifestations of matter and energy: mineral, plant, animal, human, and divine. Each form draws on the energy of the next, resonating and interacting with the divine through the form's relationship in Wuji (infinite space). The five manifestations of matter and energy are explained as follows.

1. The mineral's energetic field is considered the densest (i.e., the slowest) or lowest form of energetic vibration. The disintegration or division of the mineral's particles combine with the elements of air and water to form the Earth's soil. Every particle in the soil still retains the original primordial energy force of the mineral, which interacts with the energy of the divine.
2. The plant's energetic field is considered the next higher form of energetic vibration. All of

the Earth's vegetation (trees, bushes, flowers, herbs, etc.) absorbs a part of its life-energy from the mineral's energetic field, increasing and multiplying its energetic potential. The plant's energetic field is considered the next higher step in energetic evolution towards the divine energetic field.

3. The animal's energetic field is considered the next higher form of energetic vibration. The animal consumes and absorbs the energy from the plant's energetic field, further increasing and multiplying its energetic potential, bringing it one step closer towards the divine energetic field. Within each higher frequency of vibration there is also an increase in consciousness and level of awareness.
4. The human energetic field is considered the next highest form of energetic vibration. Mankind stands between Heaven and Earth, partaking of both energy fields. Through diet, Qigong practice, prayer, and meditation, humans can further refine and multiply their energetic potential.
5. The divine energetic field is the highest vibrational expression of energy known. As it envelops and becomes active within the human body, it further increases and multiplies the body's energetic potential, allowing man to attain divine consciousness.

All these energetic fields originate from one source, and all contain the vibrations of the one divine life-force. Likewise, with an attitude of deep respect for plants and animals that give up their life-force energy for our consumption, it is possible to enhance the nutritional value of the substances they provide us with. The blessing of food, and food prepared with a loving attitude, allows for the absorption of not only the vitamins and minerals contained therein, but also the absorption of the higher vibrations of the one divine energy inherent in all things. This is why many ancient cultures, often referred to as "primitive," prayed before hunting so that the animal spirit would willing give itself for sacrifice. Prayers were also given after the kill to free the animal's spirit so that it could return back to the divine.

Yang . .	**. . Yin**
active . .	. . passive
creative . .	. . receptive
masculine . .	. . feminine
front . .	. . back
left . .	. . right
fire . .	. . water
hot . .	. . cold
dry . .	. . wet
hard . .	. . soft
light . .	. . heavy
bright . .	. . dark
heaven . .	. . earth
sun . .	. . moon



Figure 1.2. The table above shows some characteristics of Yang and Yin. Below is the Yin/Yang symbol: white represents Yang and black represents Yin. The small circles, one white and the other black, symbolize the fact that Yin is always transforming into Yang and Yang into Yin. (For more on Yin and Yang, see Chapter 3.)

Once individuals becomes aware of the divine energetic field, they begin to experience the refined vibrational energy fields of minerals, plants, animals and human beings. This increased awareness of the divine life-force energy strengthens the awareness of one's own energetic fields and that of others. This in turn can deepen the conscious and unconscious energetic connections between ourselves and others, be they human, animal, plant or mineral.

DEFINING THE ENERGY OF YIN AND YANG

Each of the five energetic fields can be further divided into Yin and Yang aspects. In Traditional Chinese Medicine (TCM), the theory of Yin and Yang energy represents the duality of balance and harmony within the body, as well as within the universe (Figure 1.2). Earth energy is Yin, while Heaven energy is Yang.

Yin exists within Yang, and Yang within Yin. Yang manifests as active, creative, masculine, hot, hard, light, and bright. Yin manifests as passive, receptive, feminine, cold, soft, and dark. The dynamic balance of Yin and Yang always changes and transforms the body's life-force energy. (See Chapter 3 for more on Yin and Yang energy.)

Successful practitioners in balancing the body's Yin-Yang energies were considered masters or "immortals," able to harmonize the body with the mind, the mind with the will, the will with the breath, the breath with the spirit, the spirit with motion, and finally, motion with the surrounding environment (Earth), the universe (Heaven), and the divine (Dao).

UNDERSTANDING THE CONCEPT OF QI

While the concept of Qi may seem complicated, it is actually very simple. Matter progresses to energy and energy to spirit. Qi is the medium, or bridge, between matter and spirit. Once we become aware of the reality of Qi, it becomes easily recognized.

Through observation and study, Chinese Qigong (pronounced chee-gung) masters discovered that each organ in the human body has a different function and a different speed of energetic vibration. By tracing the pathways (channels) Qi takes through each organ and observing the effects on bodily functions, the Chinese developed the basic theories upon which Qigong practice is founded. For thousands of years, Chinese medicine has successfully cured serious illnesses by stimulating the body's energy in very specific ways.

Through the study of Qigong, anyone wishing to cultivate awareness of the energy vibrations and their own individual pathways can learn to influence and even control them. Qigong practitioners use these skills to heal and strengthen the immune system, and to improve the functioning of various organ systems within the body. China Healthways International estimates that in Beijing alone more than 1.3 million people practice some form of Qigong every day, whereas, in China as a whole, around 80 million people practice Qigong.

DIFFERENT SCHOOLS OF QIGONG

Qi means "life-force energy" and gong means "skill," so Qigong is the skillful practice of gathering, circulating, and applying life-force energy. In China today, Qigong practice is divided into three main schools: medical, martial, and spiritual. The three schools are all based on the same philosophical system and share many of the same meditations and techniques. The schools differ primarily in focus. Students choose a school based on the use to which they want to put their Qigong training. Briefly, each school focuses on one of the following specialties:

1. The medical school trains doctors and healers in special Qigong methods for health maintenance and longevity, disease prevention, and the diagnosis and treatment of diseases and disorders. The three primary techniques of Medical Qigong therapy include the following.
    a. Purging to detoxify the body of pathogens,
    b. Tonifying to strengthen the body's internal organs and systems, and
    c. Regulating to balance the body's internal energy.
2. The martial school trains martial artists to

build their strength and power for performing martial arts applications. The three primary techniques of martial Qigong training include the following.

   a. Obvious Power (Ming Jing) techniques emphasize the training and conditioning of the muscles, strengthening the bone structure, and increasing the individual's overall stamina. This school also includes such techniques as pounding the body (arms, hands, legs, and torso) to strengthen and toughen the tissues.
   b. Hidden Power (An Jing) techniques emphasize stretching and twisting the tendons and ligaments (known as Reeling and Pulling the Silk) to cultivate resonant vibration within the body for striking and issuing power.
   c. Mysterious Power (Hua Jing) techniques emphasize the training and conditioning the mind's imagination and intention, to project and utilize the power of the individual's Shen (Spirit).

3. The spiritual school trains practitioners who seek spiritual transformation and enlightenment (Daoism, Buddhism, and Confucianism each have their own unique techniques). Their techniques include meditations for fusing, as well as releasing the Three Ethereal Souls (Hun). These souls can best be understood as personifications of moral qualities (or archetypes). When the Hun are fully developed, the practitioner acquires certain extraordinary powers and abilities, such as soul travel. The goal however, is to achieve transformation and a state of enlightenment, and not be led astray by the glamor of extra powers. The three primary techniques of spiritual Qigong training include the following:
   a. Nourishing the Spirit (Shen), to strengthen and refine the power of the individual's Shen,
   b. Housing the Shen by disciplining both thoughts and emotions, to relax and tranquilize the individual's Shen, and to become more receptive to divine energy and guidance, and
   c. Combining the Shen with the Qi, to coordinate the breath and intention for directing the spirit to guide the body's life-force energy.

Qigong training involves all of the individual's physical senses. The concentration is focused on breathing, hearing, visualizing, and muscle relaxation. Massage, and movement are also used to develop and control the body's intrinsic energy. Studying Qigong requires not only comprehending the immeasurable wisdom gathered for medical, martial, or spiritual development but also studying the ancient Chinese culture inherent within these systems.

MEDICAL QIGONG DEFINED

All living bodies generate an external field of energy called Wei Qi (pronounced "whey chee"), which translates as "protective energy." The definition of Wei Qi in Medical Qigong is slightly different than that of Traditional Chinese Medicine (TCM). In classical TCM texts, the Wei Qi field is seen to be limited to the surface of the body, circulating within the tendon and muscle tissues. In Medical Qigong, however, the Wei Qi field also includes the three external layers of the body's auric and subtle energy fields. This energy originates from each of the internal organs and radiates through the external tissues. There the Wei Qi forms an energy field that radiates from the entire physical body. This field of Qi protects the body from the invasion of external pathogens and communicates with, as well as interacts with, the surrounding universal and environmental energy fields.

Both internal and external pathogenic factors affect the structural formation of the Wei Qi. The internal factors include suppressed emotional influences (such as anger and grief from emotional traumas); The external factors include environmental influences when they are too severe or chronic, such as Cold, Damp, Heat, or Wind, etc. Physical traumas also affect the Wei Qi field.

Any negative interchange affects the Wei Qi by literally creating holes within the matrix of the individual's external energetic fields. When left unattended, these holes leave the body vulnerable to penetration, and disease begins to take root in the body. Strong emotions, in the form of toxic energy, become trapped within the body's tissues when we hold back or do not integrate our feelings. These unprocessed emotions block the natural flow of Qi, thus creating stagnant pools of toxic energy within the body.

Medical Qigong consists of specific techniques that use the knowledge of the body's internal and external energy fields to purge, tonify, and balance these energies. Medical Qigong therapy offers patients a safe and effective way to rid themselves of toxic pathogens and years of painful emotions that otherwise, can cause mental and physical illness. This therapy combines breathing techniques with movement, creative visualization, and spiritual intent to improve health, personal power, and control over one's own life.

MEDICAL QIGONG TRAINING IN CHINA

There are numerous colleges of Traditional Chinese Medicine throughout China today that focus on Medical Qigong training. The majority support the scientific study and expansion of Medical Qigong applications and Traditional Chinese Medicine treatments.

According to Qigong master and doctor of Traditional Chinese Medicine, Professor Zhou Qianchuan, all of the most famous Chinese doctors of acupuncture and moxibustion, herbal medicine, bone setting, and massage therapy, either practiced Qigong or incorporated Qigong into their clinical practices.

Major traditional Chinese medical colleges in China offer comprehensive, government-sponsored, three-year programs in Medical Qigong therapy. Programs include classes, labs, and seminars on traditional Chinese medical theory. These studies include: The foundations of Chinese medicine for internal diseases according to *the Yellow Emperor's Inner Canon, Spiritual Axis, Essential Questions,* and *the Canon of Perplexities*. The Medical Qigong classes also include energetic anatomy and physiology, diagnosis and symptomatology, energetic psychology, Qigong pathology, Medical Qigong therapy, as well as a survey of other related medical modalities. The other related modalities include: a comprehensive understanding of herbal medicine, acupuncture therapy, and Chinese massage. Classes of Western anatomy and physiology, Western internal diseases, and health and recovery, are also required.

During the certification program, three to five training hours a day accompany the standard six-day-a-week classroom curriculum. Course content, personal mastery of energy extension, and diagnosis techniques are rigorously tested each week. Upon completing the required courses and passing the final exams, the student receives a certificate of completion. Next, a six-month to one-year internship is required at a program-affiliated hospital or clinic. Upon successful completion of this internship, the new doctor is licensed as a doctor of Medical Qigong therapy by the People's Republic of China's Bureau of Scientific Technology.

Each internship program is assigned a separate wing in the selected Chinese hospitals. Both inpatient and outpatient facilities are available to the public. Each branch has specific approaches to healing a patient, with its own unique set of ground rules for diagnosis and treatment.

There are three distinct supervisory levels working within each clinical branch of Traditional Chinese Medicine in China. The first and lowest position is that of a "doctor of Medical Qigong," who is responsible for the treatment of all clinical patients (including patients in both the inpatient and outpatient clinics). The positions of Medical Qigong doctor are generally filled by the medical college graduates who have spent four to five years in clinical study and practice. The next level is called a "physician or doctor in-charge," and denotes a senior position within the clinic. This individual is responsible for the supervision of all the Qigong doctors' clinical procedures. This position is usually obtained after spending a minimum of five years as a Qigong doctor. The final and highest level is called a "director or professor;" this position requires overseeing the doctors in-charge, as well as teaching, treating, and training of other doctors to pass on Qigong clinical knowledge to future generations. This position is usually obtained after spending a minimum of five to six years as a doctor in-charge.

The licensing is reviewed and issued by either the People's Republic of China's Bureau of Scientific Technology (that issues a license in local city hospitals) or by the Ministry of Scientific Technology (that licenses to practice in any clinic or hospital throughout China). The Qigong doctor's skills are tested through oral, written and practical examinations, and a license is issued accordingly. In China today, there are five positions available for a doctor of Traditional Chinese Medicine. These five positions are described as follows.

1. A Doctor of Acupuncture Therapy (D.Ac.) specializes in the five main modalities of Chinese acupuncture.
2. A Doctor of Herbal Medicine (D.H.M.) specializes in the five main modalities of Chinese herbology.
3. A Doctor of Massage Therapy (D.M.T.) specializes in the five main modalities of Chinese massage and tissue regulation.
4. A Doctor of Medical Qigong Therapy (D.M.Q.) specializes in the five main modalities of Chinese Medical Qigong.
5. A Doctor of Traditional Chinese Medicine (D.T.C.M.) is a doctor who has trained in all four branches of Traditional Chinese Medicine (acupuncture, herbs, massage, and Medical Qigong).

MEDICAL QIGONG TRAINING IN THE UNITED STATES

The Five Branches Institute, College and Clinic of Traditional Chinese Medicine became the first TCM / Acupuncture College in the United States to open a Medical Qigong Clinic on April 7th., 2000. This clinic not only serves as an invaluable teaching resource for the Five Branches acupuncture students, but also serves as an affordable alternative medical clinic for the general public.

Founded in 1984, the Five Branches Institute has been known not only for its leadership in TCM education, but also as an academic innovator as well. It was the first, and remains the only, TCM College to establish a Neurology Center (founded in 1995) for the specialized treatment of paralyzed patients, under the directorship of the world-famous Chinese physician Doctor Ming Qing Zhu, L.Ac., Dipl. Ac. (NCCA), M.D. (China).

THE FIVE BRANCHES MEDICAL QIGONG CLINIC

The Five Branches Medical Qigong Clinic is currently divided into 3 treatment areas. The main area (Clinic A) is used to treat patients with less severe conditions; the second area (Clinic B) is used specifically for the treatment of cancer patients. The third treatment area is designed for video taping the patient's Medical Qigong prescription exercises and meditations.

Clinic A is the primary care facility of all patients. The patients are first assessed, and then assigned to a treatment team. Each team is comprised of at least one senior intern and several clinical students. Each team diagnoses, treats, and then prescribes Medical Qigong exercises and meditations for each patient. Some patients with potentially terminal illnesses (cancer, tumors etc.) may require specialized treatments, and are referred to the Clinic B.

The main goal of the Clinic B is to specialize in Oncology, and to work closely with the Academic Dean and Clinical Medical Director Dr. Joanna Zhao, L.Ac., Dipl. Ac. (NCCA), D.T.C.M. (China), who prescribes herbal therapy to complement the Qi Emission therapy and Medical Qigong prescriptions.

The Director of the Medical Qigong Clinic is Dr. Jerry Alan Johnson, whose duty is to oversee the "Doctors in Charge" of the 3 treatment areas, as well as regulate the patient load between Clinics A and B.

The Doctors in Charge of the Medical Qigong Clinics are: Jean Ruth Vlamynck, L.Ac., Dipl.Ac., M.T.C.M., M.Q.T., and Adam Atman, L.Ac., Dipl.Ac., M.T.C.M., M.Q.T. Their duty is to oversee the Medical Qigong doctors on staff within the three treatment areas, supervise the current interns, and make themselves available for consultations when needed.

The front entrance of the Medical Qigong College at the Hai Dian University in Beijing, China.



Dr. Lu Guo Hong, Director of the Hai Dian Medical Qigong College, treats a patient suffering from hypertension by dispersing Excess Heat from her body.

Right: The graduate students of the Hai Dian Medical Qigong College intern at the Xi Yuan Hospital in Beijing, China, for a period of 6 months to a year. They are licensed through the government's Medical Qigong Science and Research Institutes, which monitor the student programs.



Left to right: Dr. Li Fu Dong, Associate Professor and Chief Director of Medical Qigong Science, Dr. Jerry Alan Johnson the author and director of the International Institute of Medical Qigong, and Dr. Pang Dong Hui, Executive Deputy President of the Hai Dian University.



Dr. Niu Yu Hua, Assistant Director of the Hai Dian Medical Qigong College, treats a patient by regulating the Qi of her Upper and Lower Dantian.



The Xi Yuan Hospital in Beijing, China, is the equivalent of the Stanford or Harvard Medical Center in the United States; it specializes in five distinct branches of healing therapies: Medical Qigong, acupuncture, herbs, Chinese massage, and Western medicine.



The Xi Yuan Hospital is equipped with both inpatient and outpatient Qigong clinics. Here, Dr. Xu Hongtao administers "distance" Qigong therapy to patients in one of the many Medical Qigong wards.



Three Americans completed their internships at the Xi Yuan Clinic in 1995. They are shown here posing with Dr. Xu Hongtao, the Xi Yuan Hospital staff supervising physician. *Left to right:* Dr. Seth Lefkowitz, the author Dr. Johnson, Dr. Xu Hongtao, and Dr. Arnold Tayam.

Left to right: Qigong Master Zheng Zhanding, Jonathan Liu, and the author discussing advanced Medical Qigong theories and modalities.

Right: The China Beijing International Acupuncture Training Center is a facility in which doctors from around the world culminate their training in Chinese medicine with Chinese doctors who are experts in their medical specialties.

CHINA BEIJING INTERNATIO
ACUPUNCTURE TRAINING CE



Dr. Teng Yingbo *(left)*, the president and secretary general of the Beijing Western District Qigong Science and Research Institute, with the author treating a patient.

WORLD CONFERENCE ON MEDICAL
WORLD ACADEMIC SOCIETY OF MEDICAL QIGONG

The author lecturing at the World Academic Society of Medical Qigong 1996 World Conference, on the psychophysical manifestations associated with tumor formation.



Left: The International Institute of Medical Qigong is one of the few American Medical Qigong colleges that maintains the same strict standards as the Medical Qigong Universities in China. The initial training programs generally require three to four years of training.

The 1997 graduating class of the International Institute of Medical Qigong (*left to right*):

Back row: Dr. Stephanie Taylor, Pamela Lee Espinoza, Anne Elderfield, and Dr. Carole Marie Kelly.

Front row: Dr. Arnold E. Tayam, Dr. Johnson (director of the institute), Shannon K. Brown, and Dr. Seth Lefkowitz.

The 1999 graduating class of the International Institute of Medical Qigong (*left to right*):

Back row: Matthew B. Weston, William H. Lewington, William H. De Groat, Paul E. Miller.

Middle row: Katy Reed, Madeleine H. Howell, Brooks M. Fiske, Diane de Terra.

Front row: Michael J. Finch, Jean R. Vlamynck, Dr. Johnson, Dennis M. Earnest.

Not pictured: Todd Mathew Gedryn, Luc Arnauld Logan, Geoffrey Greenspahn and Rose Mary Stewart.



The Five Branches Institute, College and Clinic of Traditional Chinese Medicine became the first TCM/ Acupuncture College in the United States to open a Medical Qigong Clinic on April 7th., 2000.



In the main treatment area (Clinic A), patients are categorized according to the severity of their condition. For serious conditions (e.g., multiple sclerosis) patients are encouraged to lie on the treatment tables.

The resident Doctors in Charge of the Five Branches Medical Qigong Clinic are Adam Atman L.Ac., Dipl.Ac., M.T.C.M., M.Q.T. (positioned on the left), and Jean Ruth Vlamynck L.Ac., Dipl.Ac., M.T.C.M., M.Q.T. (located in the middle). They are seen here is discussing the current patient load with Dr. Arnold Tayam D.M.Q. (China).



Pictured from left to right are the Five Branches President and CEO Ron Zaidman, M.B.A., M.T.C.M.; the Academic Dean and Clinical Medical Director Dr. Joanna Zhao L.Ac., Dipl. Ac (NCCA), D.T.C.M. (China); and the Dean of Medical Qigong Science and Director of the Medical Qigong Clinic Dr. Jerry Alan Johnson.



In Clinic A of the Five Branches Medical Qigong Clinic, patients with less serious conditions (e.g., hypertension and migraine headaches) are encouraged to relax on one of the treatment chairs.





The second treatment area (Clinic B), is used specifically for the treatment of tumor and cancer patients.

The Five Branches Medical Qigong students are also taught Energetic Psychology and how to deal with the emotional discharges coming from their patients.





Doctors of the Five Branches Medical Qigong Clinic combine their energies to treat a specific type of cancer, observed here, in Clinic B.



Within the first semester, the Medical Qigong students at the Five Branches TCM College have learned and experienced basic applications of Medical Qigong purgation, tonification and regulation exercises. They have also been taught the underlying principles for each exercise and meditation. Furthermore, they are able to discriminate when to assign these prescriptions to patients, and when not to.

In the first phase of internship, the Medical Qigong students work as part of a Qigong treatment team, assisting a senior intern.

The Medical Qigong Clinic also includes a psychotherapist, Madeleine Howell, L.M.F.T., M.Q.T., who is trained in Medical Qigong therapy. She is available to patients who may need professional consultation after undergoing Medical Qigong treatments, as these may bring painful emotions to the surface as part of the healing process.

On the first official day of the clinic, 15 Qigong interns and doctors from the International Institute of Medical Qigong performed Qi Emission through Distance therapy on more than 80 patients. Treatments ranged from a general treatment (purging excess, tonifying deficiencies and dispersing stagnations) to the treatment of several potentially terminal cancer patients.

THE FIVE BRANCHES MEDICAL QIGONG COURSE AND CLASSES

The Medical Qigong students at the Five Branches college learn and experience basic applications of Medical Qigong purgation, tonification and regulation exercises during the first semester. Classes, include lectures and labs. They are also taught to understand the underlying principles of each Medical Qigong exercise and meditation, and learn when and when not to assign these exercises in cases for clinical application. The students are also taught Energetic Psychology and how to deal with the emotional discharges coming from their patients.

In the second semester the Medical Qigong students are led through a progressive series of advanced Shengong meditations and exercises, for developing advanced intuitive diagnostic skills. The students also learn basic Medical Qigong treatment protocols, and begin the initial phase of clinical internship. During this phase they assist the senior interns.

From the third semester on, the students begin an in depth study in Medical Qigong theory and its application. The goal is to complete a three year certification program in Medical Qigong Therapy.

MEDICAL QIGONG CLINICAL THEATRE

Conducted in a small class setting, the Medical Qigong Clinic gives the students exposure and first hand experience at Medical Qigong diagnoses and treatments. This is a hands on experience where the different aspects of energetic dysfunctions and symptom manifestations are studied, treated and observed by the Medical Qigong students. Through the careful guidance of the instructor, the Medical Qigong students are allowed to assist in all phases of diagnosis and treatment.

After completing the Clinical practicum, Medical Qigong students at the Five Branches TCM College will be qualified to diagnose and treat patients, as well as document and maintain accurate clinical records.

CLINICAL INTERNSHIP

In the first phase of internship, the Medical Qigong students work as part of a Qigong treatment team, assisting a senior intern.

In the second phase of internship, the Medical Qigong students work with their own patients, under the supervision of the instructor.

By the end of their Clinical Internship, the Medical Qigong therapists will receive their Masters degree, and will be fully qualified to diagnose and treat patients without supervision.

TRADITIONAL CHINESE MEDICINE AND MEDICAL QIGONG THERAPY

Medical Qigong therapy is the oldest of the four branches of Traditional Chinese Medicine and provides the energetic foundation from which acupuncture, herbal healing, and Chinese massage originated. It is through the understanding of Qigong that the other branches of Traditional Chinese Medicine are elevated to a spiritual path of self-realization and internal transformation. Doctors of Traditional Chinese Medicine address the patients' physical, energetic, and spiritual needs simultaneously. According to the principles of Traditional Chinese Medicine, the root cause of all disease can be traced to a critical imbalance within the body's vital energies. Therefore, the best way to prevent or cure disease requires establishing a healthy energetic balance and harmony between the body's energy field and the forces of nature and the cosmos.

Traditional Chinese Medicine is divided into four branches of clinical healing: Acupuncture


Needling Therapy
Cupping
Bloodletting
Moxa
Magnetic Therapy
Tea & Soups
Tinctures & Wines
Oils, Balms & Liniments
Compresses, Powders & Pills
Nutritional Education
Jie Gu—Bone Setting
Tui Na—Muscle Manipulation
Gua Sha—Scraping Therapy
An Mo—Visceral Manipulation
Jing Point Therapy
Distance Therapy
Self-regulation Therapy
Energetic Massage Therapy
Energetic Point Therapy
Invisible-needle Therapy
Acupuncture Therapy
(1)
Herbal Therapy
(2)
Chinese Massage Therapy
(3)
Medical Qigong Therapy
(4)
4 Main Branches of Traditional Chinese Medicine
5 Main Roots
Six Stages
Five Elements
Eight Principles
Triple Burners
Four Levels
Tai Yang
Yang Ming
Shao Yang
Tai Yin
Shao Yin
Jue Yin
Wood
Fire
Earth
Metal
Water
Deficient & Excess
Internal & External
Cold & Heat
Yin & Yang
Lower Burner
Middle Burner
Upper Burner
Lg Intestine
Kidneys
Bladder
Liver
Spleen
Stomach
Heart
Lungs
Blood Level
Qi Level
Ying Qi Level
Wei Qi Level
River of Blood
Core of Light
Sea of Marrow
Wind of Nurturing Energy
Body Energy
Emotional Energy
Spiritual Energy

Figure 1.3. The Four Main Branches of Traditional Chinese Medicine

therapy, Herbal therapy, Chinese Massage therapy, and Medical Qigong therapy. All of the four main branches are built on the same foundation of energetic diagnosis known as the Five Main Roots of Traditional Chinese Medicine. The five main roots are used for internal organ diagnosis according to the Six Stages, Five Elements, Eight Principles, Triple Burners and Four Levels theories (Figure 1.3).

ACUPUNCTURE THERAPY

By inserting very thin metal needles into specific points, the acupuncturist manipulates the patient's energy (Qi) to achieve an overall physical balance. In an acute or emergency situation, a patient's symptoms are treated first, after which the focus is directed to rerouting Qi Deviations or removing the original cause of the symptoms (e.g., stagnations).

The energetic points are specific areas both on and in the body where Qi emerges from deep within the body's organs and tissues, or submerges to travel deep within the body. The Qi moves along specific pathways known as channels and collaterals. Collaterals are the smaller streams of Qi that branch off from the main ener-



Figure 1.4. The Five Main Branches of Chinese Acupuncture Therapy

getic rivers (channels). Each Primary Channel takes its name from one of the six Yin or six Yang organs to which it corresponds. Each organ has two channels, one on each side of the body.

Often in Chinese medical diagrams and procedures, you will see abbreviations referring to specific energetic points. Traditional Chinese Medicine names the points based upon the channel on which the point lies and its distance along the channel. The first points on each side of the Gall Bladder Channels (GB), for example, are GB-1. Some channels contain over 60 points, each numbered sequentially from beginning to end. These points are also given descriptive names according to their location and energetic affect upon the body when treated. The GB-1 points, for example, are located next to the eyes, on the outer canthus, level with the pupils, and are called the Pupil's Seam.

Acupuncture therapy includes five major treatment techniques (Figure 1.4): needling, cupping, bloodletting, moxa burning, and magnet healing.

1. Needling uses acupuncture needles of various sizes that are inserted into channel points. These points are tiny areas where the Qi pools along the streams of an energy channel (Figure 1.5). The needles stimulate the nerves and energy flow to tonify or reduce Excess Qi.
2. Cupping uses wooden, clay, or glass cups that adhere to the patient's skin by suction (Figure 1.6). This suction drains, or removes, pathogenic Qi from the body's pores. This technique can also be used to tonify specific areas of the body. This modality of treatment has been successfully combined with bloodletting to treat acute sprains accompanied by Blood stagnation.
3. Bloodletting is done with instruments such as blood needles or seven- and five-star hammers to remove Toxic Qi, Blood stagnation, Heat, and other pathogenic factors (Figure 1.7). The hammer has five to seven sharp projections that pierce the skin and cause slight bleeding. The acupuncturist diagnoses and then monitors the patient's condition by the



Figure 1.5. A doctor is inserting an acupuncture needle into the patient's Channel Point. Acupuncture needles of various sizes are used to stimulate nerve and energy flow for the tonification of Deficient Qi or the reduction of Excess Qi.

different shades of the patient's Blood. Trapped or diseased Blood is released until a healthy color is observed. This therapy is considered useful for treating disorders of the nervous system, physical trauma, and extremely serious febrile diseases.

4. Moxa Burning employs lighted herbal cones or sticks that are inserted on top of acupuncture needles (or held over specific channel points) to infuse heat and Qi into specific body areas for tonification (Figure 1.8). This technique is also used to expel Cold in order to disperse Blood stagnation.
5. Magnets use magnetic patches or strips that are attached to various channel points of the patient's body to stimulate a response in the electromagnetic field (Figure 1.9). Magnet therapy has been used since the Tang Dynasty (618–907 A.D.). The magnets are applied to specific points for a period of 3–5 days, removed for one day, then reapplied. Whether used for tonification or sedation, this therapy facilitates constant treatment of the channel point.



Figure 1.6. In Cupping, heated air is directed into wooden, clay, or glass cups, which are then placed on the patient's skin. The cooling air creates suction that drains, or removes, pathogenic Qi from the body's pores.



Figure 1.7. The doctor is lightly tapping with the Five-Star Hammer that has five sharp projections to pierce the skin and cause slight bleeding. The color of the patient's Blood provides the doctor with information about the patient's condition.



Figure 1.8. The doctor has inserted a needle with burning Moxa (herbal cones/sticks) on top of it. Burning moxa may also be held over specific channel points or placed directly on the skin.



Figure 1.9. A Magnetic Patch is being worn on the Wrist. Magnets may be attached to various parts of the body or may be worn in shoes or wristbands.



Figure 1.10. The Five Main Branches of Chinese Herbal Therapy

HERBAL THERAPY

Herbal formulas have been used successfully to treat a variety of illnesses for over 5000 years. Historically, herbal medicine has been the worldwide basis for pharmaceuticals used in most cultures, prior to modern times. Today, herbs provide the source for many of the pharmaceuticals used in contemporary Western medicine, especially for the treatment of viral and bacterial diseases, pain, tumors, chronic diseases, internal and external tissue regeneration, and many other medical problems.

Herbology is both a science and an art. An herbalist spends many years studying the herbs used to create herbal formulas. The herbalist must understand the effects of individual herbs, as well as their synergistic effects when combined.

Herbs are used for tonifying, purging, dispersing, warming, cooling, nourishing the Yin, nourishing the Yang, and clearing Heat, as well as moving Qi, Blood, Phlegm, and Fluids within the body. They cause the Qi in the body to either ascend or descend, affecting the upper or lower parts of the body.

Chinese medicine prescribes specific parts of plants (leaves, roots, bark, etc.) for particular medicinal purposes. Parts of trees, shrubs, herbs, vines, and flowers are selected for their specific properties (Hot, Cold, Warm, Cool) and taste (Sweet, Bitter, Pungent, Sour, and Salty). These properties either tonify or disperse Qi and Blood.

Chinese medical herbology not only includes the cultivation and gathering of seeds, fruits, flowers, leaves, barks, stems, and roots but also prescribes non-herbal components (such as minerals, animal or insect parts) that are sometimes added to enhance the herbs' healing effect.

Chinese herbs cure energetically by moving Qi in the channels. Different herbs enter different channels and affect different internal organs. Herbs are extremely powerful. The herbalist uses herbs to tonify (strengthen) and move Qi and Blood as well as eliminate Heat from the patient's Blood. When tailored to an individual's constitution or combined into a formula for specific symptoms, herbs can greatly help the body; however, taking the improper herbal formula can have deleterious effects.

Chinese herbal therapy includes five major clinical applications (Figure 1.10): nutritional education (food and diet); teas and soups (tang); tinctures and wines (jin); oils, balms, and liniments (you and gao); and compresses, powders (san), and pills (wan).

1. Nutritional education is stressed to assist patients in choosing foods for the body's nourishment and optimum health, as well as for the treatment of disease. Foods have many similar properties to herbs. An old Chinese saying asks, "Are herbs food or food herbs?", thus stressing the importance of a good diet
2. Teas and Soups are water-based herbal formulas traditionally prepared from raw or processed herbal ingredients. These are traditionally ingested for the treatment of internal and external disorders of both acute and chronic natures.
3. Tinctures and Wines are both alcohol-based herbal formulas. Tinctures are a concentrated alcohol-based formulas prepared from raw herbs that are used similarly to teas and soups. Wines are traditionally applied externally to alleviate pain, or ingested as a tonic, depending on the specific formula and the disease being treated.
4. Oils, Balms, and Liniments are oil-based herbal formulas usually applied externally for the treatment of muscle, tendon, and ligament trauma, to alleviate pain, disperse Excess Qi, or to draw Qi into specific areas for tonification.
5. Compresses, Powders, and Pills consist of herbs that have been pulverized into a paste, powder, or poultice and are then applied externally for the treatment of acute or chronic injuries. They can also be ingested for internal organ tonification and the rebalancing of the body's energy system. Pills are herbs specifically prepared from traditional formulas, rolled into little balls, and orally ingested for the treatment of Internal disorders.

CHINESE MASSAGE THERAPY

Chinese Massage Therapy is a generic term used for all tissue manipulation techniques currently used in China. This particular branch of Traditional Chinese Medicine consists of five popular systems that include manipulation of not only external skin, muscles, tendons, joints, nerves, and inner fascia but also the internal organs and organ systems.

This ancient therapy is used as a preventative treatment as well as a healing modality. By applying specific methods of tissue manipulations, obstructions in the channel's pathways can be removed, promoting and increasing both Qi and Blood circulation.

This therapy focuses on improving the structural alignment of the body and on healing soft-tissue injuries. It also corrects any deviant functions of the internal organs, nerves, and joints. Chinese bodywork and tissue therapy are the foundational source for modern Swedish massage, myofascial trigger point therapy, reflexology, and therapeutic neuromuscular therapy.

Chinese massage therapy is divided into five different schools of instruction: Jie Gu, Tui Na, Gua Sha, An Mo, and Jing Point therapy (Figure 1.11). Jie Gu, Tui Na, and Gua Sha employ external tissue manipulations. These three external manipulations are used to treat the bones, muscles, ligaments, and tendons, and also to treat fevers. An Mo and Jing Point therapy utilize soft-tissue manipulation. These treatment modalities are similar to those used in chiropractic, osteopathy, Western physical therapy, and massage therapy.

1. Jie Gu Therapy is used for bone setting and



Figure 1.11. The Five Main Branches of Chinese Massage

to adjust the patient's body alignment (Figure 1.12). The literal translation for Jie Gu is "knotted bone," which describes the art of manipulating the bones and ligaments to unravel the trapped junctions of Blood and Qi channels in the patient's joints.

2. Tui Na Therapy focuses on external tissue manipulation and adjustment of the muscles and tendons to adjust abnormal Qi circulation within the body's muscular system (Figure 1.13). The translation for Tui Na is to "push and grasp." It was developed primarily for correcting the misalignment of the body's bones and muscles due to traumatic physical injuries. Reflexology is historically rooted in the use of Tui Na therapy in Chinese pediatric care.
3. Gua Sha Therapy is used to regulate febrile conditions, such as flu, cholera and malaria, and to treat musculoskeletal conditions. The translation for Gua is "to scrape or scratch" and Sha is defined as "cholera," or sand-like maculae (referring to the red discoloration that is raised on the skin by the application of scraping). This therapy focuses on external surface tissue scraping, usually around the neck and thorax areas (Figure 1.14). It is commonly used for promoting Qi and Blood circulation, removing toxins, clearing Heat, cooling the Blood, removing stagnation, and dissolving masses. A jade scraper (coin, bowl, or spoon) is used for purifying the Qi and transforming the Shen (Spirit). A water buffalo horn is commonly used for pulling Heat and toxins from the patient's body (occasionally ceramic is used, but never glass or plastic).

The two internal manipulations are used to treat the organs and nerves.

4. An Mo Therapy is used for internal organ



Figure 1.12. Jie Gu Therapy is used to set the bones and ligaments in order to unravel the trapped junctions of Blood and Qi channels at the patient's joints.



Figure 1.13. Tui Na Therapy is used to adjust the muscles and focuses on external tissue manipulation and adjustment of the muscles and tendons in order to correct abnormal Qi circulation within the body's muscular system.



Figure 1.14. Gua Sha Therapy is commonly used for clearing Heat, cooling the Blood, removing stagnation, and dissolving masses.



Figure 1.15. An Mo Therapy allows organ manipulation for internal visceral regulation and concentrates directly on treating specific Internal diseases.

regulation. An Mo focuses primarily on Qi extension and soft-tissue and internal organ manipulation (Figure 1.15). Although the literal translation means to "press and rub," this therapy focuses primarily on internal visceral regulation, concentrating directly on the treatment of specific Internal diseases.

5. Jing Point Therapy is employed for channel and internal organ regulation. Jing point therapy uses pressing, pinching, clapping, and tapping techniques on specific energetic points and energetic channels. These techniques are employed to promote Qi and Blood circulation, balance the body's Yin and Yang energy, tonify weak organs, dredge the channels, and expel pathogenic factors (Figure 1.16).



Figure 1.16. Jing Point Therapy is used to promote Qi and Blood circulation, balance the body's Yin and Yang energy, tonify weak organs, dredge the channels, and expel pathogenic factors.



Figure 1.17. The Five Main Branches of Chinese Medical Qigong Therapy

MEDICAL QIGONG THERAPY

The objective for healing disease in Medical Qigong training is threefold:

- First, eliminate Internal pathogenic factors (the accumulation of Excessive emotions such as anger, grief, worry, fear, etc.) as well as External pathogenic factors (the invasion of Cold, Hot, Damp, etc., from the environment).
- Second, increase or decrease the patient's Qi as needed to counteract the Deficient or Excess condition within the internal organs and channels.
- Third, regulate and balance the patient's Yin and Yang energy to bring it back into harmony.

This unique therapy consists of regulating the body's three external Wei Qi fields (physical, mental/emotional and spiritual), and the four Internal fields of life-force energy (Ying Qi, Sea of Blood, Sea of Marrow, and the Taiji Pole). Some of the most common diseases treated in Medical Qigong clinics are: diabetes, arthritis, high blood pressure, breast and ovarian cysts and tumors, migraine headaches, fibromyalgia, insomnia, acute abdominal pain, irritable bowel syndrome, deep tissue obstruction, muscle atrophy, brain tumors, stroke, coma retrieval, and certain types of cancer. The medical treatment focuses on relieving pain, detoxifying the body of toxic emotions (e.g., excessive anger, fear, worry, etc.), correcting internal organ dysfunctions, and balancing Excess or Deficient Qi and Blood conditions.

Medical Qigong therapy uses five major clinical modalities (Figure 1.17): Distance therapy, Self-

Regulation therapy, Qigong Massage therapy, Energetic Point therapy, and Invisible Needle therapy.

1. Distance Therapy (also called Qi Emission) requires the Qigong doctor to manipulate a patient's Qi by focusing on the energetic properties of the patients' channels, collaterals, and points, as well as internal organs, from a distance of several inches, several feet, or even several miles away (Figure 1.18).
2. Self-Regulation Therapy (also called Qigong Prescriptions and Patient Homework) are Qigong exercises (postures, movements, sound vibrations, visualizations, etc.) given to patients by a doctor (Figure 1.19). Patients can use these Qigong techniques to regulate their own health, using various lying, sitting, moving, and standing postures. The patients may also use their own spiritual belief system as a healing tool.
3. Qigong Massage Therapy, a soft-tissue regulation technique, differs from Tui Na or An Mo (Chinese External Massage Therapy), in that the doctor's hand skims the patient's body as lightly as a feather, never exceeding the pressure one would place on an eyeball (Figure 1.20). The light skimming action is used to dredge the patients' external channel Qi, causing energy to be released from the internal channels themselves, which serve as pathways for Qi transference.
4. Energetic Point Therapy is used by the doctor to extend Qi into specific internal and external areas of the patient's body to lead and direct the Qi. This type of therapy requires the doctor and the patient to focus their attention onto a specific energetic point (Figure 1.21). This therapy demonstrates the power of the mind as an active tool in healing, and is used for purgation, tonification, and regulation.
5. Invisible Needle Therapy involves the visualization of imaginary needles of light being inserted into specific points on the patient's body. The needles of light are used to stimulate and direct the patient's Qi (Figure 1.22).



Figure 1.18. In Distance Therapy, the Qigong doctor manipulates a patient's Qi by focusing on the energetic properties of the patient's external channels, collaterals, and points from a distance of several inches, several feet, or even several miles.



Figure 1.19. In Self-Regulation Therapy, the patients are required to self-regulate by performing Qi Qigong "prescriptions" or "homework" (postures, movements, chants, visualizations, etc.). Here the patient regulates his own *Liver Qi*.



Figure 1.20. In Qigong Massage Therapy, the doctor softly dredges the patient's external channels in order to release energy from the internal channels themselves, which serve as pathways for Qi transference.



Figure 1.21. In Energetic Point Therapy, the doctor extends energy into the patient's body as both the doctor and the patient focus their attention on a specific channel point, in this case the Kd-1 point.



Figure 1.22. In Invisible Needle Therapy, the doctor visualizes inserting energetic acupuncture needles into the patient's channel points in order to stimulate the patient's Qi.

CHAPTER 2
ENERGETIC FORMATION OF THE HUMAN BODY

In 1993 when I began my internship at the Xi Yuan Hospital in Beijing, China, I became aware that most Qigong doctors had a limited understanding of basic anatomy and physiology as we teach it in the West. When I asked why more attention was not paid to the subject, I was told, "The perspective and priority we place on gross physical anatomy and physiology is quite different from yours -- Westerners only study the dead -- we study life, the living pools, rivers, and currents of life-force energy that can only be found in the living body."

Eastern medicine believes that when the body dies, the substance, or energy, that gave the body life returns to its original source (Heaven and Earth) and all that remains of the individual is a mass of lifeless tissue. They believe that the tangible and the energetic exist in a twofold, cohesive relationship. A Qigong doctor must understand this concept of energy in order to comprehend and prescribe appropriate Medical Qigong therapy for the patient.

The concept of the energetic formation of the human body is new to Western thought with its primary focus on the physically tangible. The philosophical foundation of Traditional Chinese Medicine, on the other hand, includes studying the whole human being in all of his or her aspects, physical, mental, emotional, energetic, and spiritual. The conception results not only in the tangible physical form of a new human being but also in various contributing energies and energetic fields. Medical Qigong studies these energies, as well as the interplay between the Heavenly and Earthly influences.

ENERGETIC EMBRYOLOGICAL DEVELOPMENT

The study of the embryological development of the body's inner fascia and connective tissues explains many of the traditional Chinese medical ideas about energy, health, and disease. The cells, tissues, and organs of the human body interrelate as a result of the "energetic patterning" that occurs at conception.

Heaven (which the ancient Chinese considered a state of subtle and non-material energies and beings) and Earth both have energetic fields that influence life. If we consider Heaven Qi (the universal energy related to the sun, moon, and stars) to be electro-positive and Earth Qi (the environmental energy related to the earth, water and wind) to be electro-negative, we can begin to understand the duality of the energetic fields and their pull on the human body.

Think of the body as being suspended between two enormous fields of energy (Figure 2.1): the sun extends its energetic field down, and the Earth's small "sun," i.e. its core, extends its energetic field upwards through the Earth's crust. Man is, therefore, suspended between the electrically positive energy field of Heaven and the electri-



Figure 2.1. Man's energetic field is suspended between the two energy fields of Heaven and Earth.

cally negative energy field of Earth and is affected by both celestial and environmental phenomena.

ENERGY, MATTER, AND SPIRITUAL INTERACTIONS

The *Yellow Emperor's Classic of Internal Medicine* states that the woman's physiology is dominated by Blood, which serves as the foundation of her menstrual cycle, fertility, conception, pregnancy, and childbirth. A man's physiology is dominated by Qi, which serves as the basis of his physical interactions.

At conception, a myriad of energetic interactions begin. The mother, father, Heaven, and Earth all contribute energetically to conception. These four energies condense upon impact and form the nucleus of the energetic cellular patterning of the new life (Figure 2.2). Every part of the resulting human body is affected by this energetic patterning.

An old Chinese saying in Medical Qigong states that, "When people are born, Heaven gives them Jing (Essence) and Shen (Spirit) -- which align to form the mind -- and Earth gives them bones and shape, which unite to form the body. Joined together, these sources of energy cause human beings to develop. When people die, their Essence and Spirit return to Heaven, and their bones and shape go back to Earth."



Figure 2.2. The blending of Heaven (universal energy) and Earth (environmental energy) as well as father and mother energies creates a fusion of Yin and Yang energies within the body's tissues and cells during creation. These energies are responsible, on a psychophysical level, for transferring talents and traits from generation to generation.

Pairs of channels from the mother's internal organs carry Qi that creates and nourishes the baby at each stage of development. As the baby develops, sustained through the umbilical cord, the child's navel, Kidneys, and lower abdominal area become the collection points for Prenatal Qi (energy stored within the baby's body before it is born).

Every life begins with inherent strengths and weaknesses. It is believed that when conception occurs, if the mother achieves orgasm, the child's inherent energy will become very strong. However, if the mother does not achieve orgasm during conception, the results will be a normal or weak energetic constitution. Prenatal care is mandatory for the healthy formation of the embryo. Before cell division, the DNA mass must be duplicated exactly in order to transfer normal genetic characteristics to the next generation. Although heredity plays a large part in the transference of both parents' genetic history, a weakness in the mother's channels can result in congenital problems, or toxins, that the fetus can acquire during one of the corresponding stages of development.

UNDERSTANDING FETAL TOXINS

The External invasions of pathogenic toxins (known as fetal toxins) can penetrate the zygote with latent Heat that can cause diseases during early childhood development. It is, therefore, important for both parents, especially the mother, to take responsibility for being strong and healthy at the time of conception and for the duration of the pregnancy. Toxins can be transferred into the embryo in utero in one of two ways:

- First, from either the mother or father at the moment of conception. Toxins transferred from the parents can create an inherited toxicity due to a retention of Hot Evil stored from within either of the parents' Essence and Blood; or
- Second, from Internal Heat generated by the

mother during pregnancy due to improper diet or life-style.

During pregnancy, a fetus is aware of light and sound and of the mother's reaction to the surrounding influences of her environmental energy fields. The fetus is strongly influenced by its mother's physical activities, as well as her mental, emotional, and spiritual states.

Regulating the mother's behavior to improve her child's physical, emotional, and mental health is called "fetal education" in Traditional Chinese Medicine, and is important in the development of the child's Prenatal Essence, Energy, and Spirit. This viewpoint is based on the fact that the mother's Heart and uterus are connected via the mother's internal channels, allowing Qi and Blood to flow into the uterus. Anything that influences the mother's mind, emotions, and spirit affect her Heart, which in turn, affect the fetus via the internal channels.

DEVELOPMENTAL SEQUENCE

The following description of the body's developmental sequence is but one of many theories used in order to explain Chinese energetic embryology. The ancient Chinese did not have a conception of the body's cells and cellular division; however, modern theories have postulated that the channels were formed at the earliest stages of cell division, creating an energy matrix for the developing fetus. This particular theory is being taught at the Hai Dian Medical Qigong College in Beijing, China.

Three important energies (Figure 2.3) combine in the developing fetus: Jing (Essence), Qi (Energy), and Shen (Spirit). Jing is the body's foundational substance, responsible for nourishing the tissues. Qi emerges out of Jing circulating through the tissues and promotes the body's metabolism. Shen governs the body. (see Chapter 11, "The Three Treasures of Man," for more on Jing, Qi, and Shen.)

Both parents contribute energetically to the baby's conception (Figure 2.4). The father's sperm and the mother's egg consist of Jing (Essence), Qi (Energy), and Shen (Spirit). This combination of Jing, Qi, and Shen is referred to collectively as fa-

Prenatal Energies—The Three Treasures		
Substance	**Physical Function**	**Energetic Prenatal Function**
Shen (Spirit)	governs the body	the Original Spirit
Qi (Energy)	promotes metabolism	body's Energy extending into Infinite Space (also called Wuji, or the Void)
Jing (Essence)	nourishes the tissues	body's innate true Essence, the foundational substance

Figure 2.3 Qi is the medium between matter (Jing) and Spirit (Shen) and is responsible for the embryo's transformational processes.



Figure 2.4. The human body is composed primarily of water. The Essence of man (sperm) and woman (egg) unite in the uterine sea to form the fetus. The ova is polarized at the entry point of the sperm, creating the original polar axis (the *Taiji Pole*) that determines the complex pattern of cellular division that occurs along the polar axis throughout development.

ther Qi and mother Qi. The combination of father Qi and mother Qi is known as Yuan Qi or Original Qi.

The quality and quantity of Original Qi that the baby receives at birth depends on three main factors:

- First, the purity and potency of both parents' genetic plasma (sperm and egg);
- Second, the condition of both parents' health and vitality and the state of their physical, mental, emotional and spiritual relationship at the time of conception; and
- Third, the spiritual factors surrounding the conception (i.e., karma that is brought into this life by the incoming spirit/soul).

As the sperm (containing the father's Qi) fertilizes the egg (containing the mother's Qi), Heaven (universal) Qi and Earth (environmental) Qi blend together within the zygote. The swirling and blending of these four energies form energetic pools (which will later evolve into organs), rivers (which later evolve into channels), and streams (which later evolve into collaterals).

When the sperm enters the ovum, it produces a polar axis that creates an energetic vortex. This vortex not only forms the central Taiji Pole, but also draws Qi from Heaven and Earth and the Eternal Soul into the fetus's body. This polarization also determines a ventral and dorsal surface, which become the embryo's Conception and Governing Vessels, respectively, at the first cell division (Figure 2.5). The Governing Vessel controls the cell division that eventually forms the back of the body, while the Conception Vessel controls the cell division of the body's front. This first cell division also establishes a right and left side. The Heel Vessels control the balance of Yin and Yang energy development in the two sides of the body.

The Belt Vessel and Thrusting Vessels form at the time of the second cell division. The four vessels formed at this point (Governing Vessel, Conception Vessel, Thrusting Vessels, and Belt Vessel) are interlinked for the production, circulation, and regulation of the body's Jing-Essence. The body's entire energy system becomes established and maintained within these four vessels when cell division occurs (Figure 2.6).


Left Yin and Yang Heel Vessels
Right Yin and Yang Heel Vessels
Conception Vessel
Governing Vessel

Figure 2.5. The electrical polarity and field of energy in the polar axis is related to the Original or Yuan Qi from which the Conception and Governing Vessels form the seas of Yin and Yang energy during the first cellular division. The Yin and Yang Heel Vessels are also established, forming the left and right sides. The exterior of the egg is determined by the Yang Linking Vessels. The interior of the egg by the Yin Linking Vessels.



Figure 2.6. The second cellular division is caused by the development of the Belt Vessel and the Thrusting Vessel. The Eight Extraordinary Vessels have now formed.

While the embryo is forming, both the Yang and Yin Linking Vessels are respectively responsible for the exterior and interior development of the embryo (see Chapter 3 for more on Yang and Yin energy). Each of the Eight Extraordinary Vessels has a specific role in the development of the embryo.

1. The Governing Vessel (Yang) controls development of the body's back.
2. The Conception Vessel (Yin) controls development of the body's front.
3. The Thrusting Vessels carry energy through the center of the body and controls the body's center core.

4. The Yang Heel Vessels control the development of the body's right and left Yang energy.
5. The Yin Heel Vessels control the development of the body's right and left Yin energy.
6. The Yang Linking Vessels control the development of the exterior of the body (and correlates to Heaven energy).
7. The Yin Linking Vessels control the development of the interior of the body (and correlates to Earth energy).
8. The Belt Vessel binds all the channels together.

These eight vessels—Governing, Conception, Thrusting, Yang Heel, Yin Heel, Yang Linking, Yin Linking, and Belt—are also known as the Eight Extraordinary Vessels or Eight Prenatal Vessels.

The Eight Extraordinary Vessels form a vortex of energy at the center of the embryo's body—from the area between what will become the Kidneys. The Taiji Pole and Thrusting Vessels are at the center of this vortex and will form the Sea of Five Yin and Six Yang Organs, the Sea of Twelve Primary Channels, and the Sea of Blood (see Chapter 13). From the Taiji Pole and Thrusting Vessels, the body's Qi and Blood are distributed at the energetic level through small channels, or rivers of energy. This energetic vortex creates the energy for the growth of the embryo's physical form.

After the initial cell division is complete, the embryo's ten Yang channels and ten Yin channels begin the development and formation of the embryo's tissues and organs. These twenty channels are divided into two separate groups of energetic rivers known as the Eight Extraordinary Vessels and Twelve Primary Channels. As the embryo develops into a fetus and continues to grow, the twenty channels also continue to develop.

During the formation of the embryo, nine Yang channels begin to flow out of the Governing Vessel (Sea of Yang Qi) and form the nine Yang rivers known as: the Bladder Channels, Gall Bladder Channels, Stomach Channels, Small Intestine Channels, Triple Burner Channels, Large Intestine Channels, Yang Heel Vessels, Yang Linking Vessels, and Belt Vessel.

Consecutively, the nine Yin channels begin to flow out of the Conception Vessel (Sea of Yin Qi) and form the nine Yin rivers known as: the Kidney Channels, Liver Channels, Spleen Channels, Heart Channels, Pericardium Channels, Lung Channels, Yin Heel Vessels, Yin Linking Vessels, and Thrusting Vessels (see Chapter 8).

THE TEN LUNAR MONTHS OF CREATION

The following description of the sequence of embryological development was established by the late Chinese Medical Qigong expert Dr. Chao Yuan Fang during the Sui Dynasty, around 610 A.D. The months that Dr. Chao refers to are the ten lunar

Lunar Month	**Mother's Channels**	**Channel's Activity**	**Energetic Activity**
Month 1	Liver Channels	stop menses, begin embryonic growth	energies combine at conception, channels develop
Month 2	Gall Bladder Channels	saturate embryo with Jing	embryonic Qi transforms into amniotic fluid
Month 3	Pericardium Channels	mother's Qi and Body Fluids purify and cleanse the fetal Shen	Hun and Po establish in the fetus's internal organs
Month 4	Triple Burner Channels	the Yin organs develop	Water Jing accepted into fetus's body
Month 5	Spleen Channels	the Five Agents enter the Five Orbs (Yin organs)	Fire Jing accepted into fetus's body
Month 6	Stomach Channels	Six Pitches established within the Six Storage Areas	Metal Jing accepted into fetus's body
Month 7	Lung Channels	Seven Essential Stars open orifices to the light from Heaven and Earth	Wood Jing accepted into fetus's body
Month 8	Large Intestine Channels	Heart is harmonized and breath is quieted	Earth Jing accepted into fetus's body
Month 9	Kidney Channels	Kidney Channel controls the energetic intake from the umbilicus	energetic boundaries completed
Month 10	Bladder Channels	spatial cavities surrounding major organs are completed	Heaven & Earth Qi settle into baby's Lower Dantian and birth begins

Figure 2.7. Prenatal Energy Development

months. These months compose the 40 weeks of a normal pregnancy (Figure 2.7).

MONTH ONE

The first lunar month of pregnancy is traditionally called the Beginning of Form. This stage covers conception and early cell division.

At conception, the mother's Liver Channels stop her menses and begin to nourish the growth of her embryo (Figure 2.8). During pregnancy, the mother's Blood is transformed into Jing-Essence, that nourishes the mother's body as well as the embryo's. The mother's Liver Channels cause Essence and Blood to coagulate in her womb. This Blood coagulation continues after the initial cellular division.

At this stage the mother's Shen (Spirit) becomes part of a threefold activity:

- First, the mother's Shen projects through the umbilical cord like a light reflecting off a prism, sustaining and energizing the production of Jing (see Chapter 13), Qi, and Blood for the embryo (Figure 2.9).
- Second, the mother's Shen influences the embryo's Qi and Blood, and the embryo's Shen (Spirit) is stimulated, bringing it into active being (see Chapter 12).
- Third, the embryo's Original Jing combines with the embryo's Original Qi to create the embryo's Original Shen (Prenatal Spirit), which appears as multicolored light and contains the inherited knowledge of the fetus's ancestors, including talents, skills, and natu-



Figure 2.9. Sustained through the umbilical cord, the embryo absorbs the mother's Blood, Essence, Energy, and Spirit.


The energy of the Liver Channels flows up the inside of both legs into the uterus, stopping menses as the growth cycle begins.

Figure 2.8. The mother's and father's Essence (Jing), Energy (Qi), and Spirit (Shen) blend with the Heaven and Earth energies during the fusion of the sperm and egg. During the first lunar month, the mother's Liver Channels stop her menses and begin the embryonic growth cycle. After the initial cell division, the ten Yin and ten Yang Channels develop within the embryo.

ral abilities. This knowledge is stored deep within the fetus's cells, tissues, and consciousness.

MONTH TWO

The second lunar month of pregnancy is traditionally called the Beginning to Gel stage. During this period, the responsibility of the mother's Gall Bladder Channels is to create the environment for the development of the mesenteric membrane sac (Figure 2.10). The Gall Bladder Channels will also saturate the embryo, uterus, and placenta with Jing, causing the embryonic Qi to become denser, until it transforms into a thick liquid (amniotic fluid). The embryonic fluid will regulate the embryo's Body Fluids. At this stage, the embryo begins to take shape inside the uterine lining (Figure 2.11). The Lungs, Liver, Kidneys and major blood vessels are forming.

With the formation of the major blood vessels, the Yin and Yang energies begin to occupy the embryo's channels. As the Yin and Yang energies actively balance themselves:

- Energy that will later coalesce into Lung Qi moves to the upper part of the body;
- Original Qi (Yuan) of the Kidneys begins to collect deep in the center of the body;
- Earth Qi (the energy absorbed by the embryo from the mother's exposure to the outside environment) begins to collect in the lower front and upper back areas of the embryo's body.

All of these energies seek their own location



Figure 2.11. During the second month, the embryo begins to take shape as the energetic boundaries begin to form.



The energy of the Gall Bladder Channels flows down the outside of the mother's body, saturating the embryo with Jing.

Figure 2.10. The mother's Gall Bladder Channels saturate the embryo with Jing during the second lunar month, causing the embryonic Qi to transform into amniotic fluid. The embryo begins to take shape as the energetic boundaries, pools, spatial cavities, and energetic channels and collaterals create internal and external form.

within the embryo's developing body, creating their own pools of Qi with their own discrete energetic boundaries. These boundaries will later form the spatial cavities that surround the major organs. The areas where the energetic pools settle and begin to create a balance within themselves, will be called the organ's place of origin. This flux and movement creates tiny energy currents, eddies, and whirlpools that flow within the body. As the energy shifts, seeking balance, the larger pools of energy begin to form the major organs. This process continues, creating the brain, bones, and skin.

Once the energetic pools and rivers have formed, all of the currents and eddies evolve to form the energetic channels and collaterals, through which energy will flow continuously. These energetic currents will move in accordance with the mother's energetic respiratory patterns and will later (after birth) follow the rhythmic patterns of the child's respiration. As the energy currents continue to spiral within the channels, energetic points are established, following the body's energetic blueprint. Some of these areas spiral outward to form energetic exit points, while others spiral inward to form entry points.

MONTH THREE

The third lunar month of pregnancy is traditionally called the Beginning of the Pregnant uterus. During this period, the embryo becomes a fetus and begins micro-movement. Its heartbeat can now be detected.

The mother's Pericardium Channels control the presence and amount of Jing and Shen in the fetus's vessels, channels, and collaterals (Figure 2.12). The Jing and Shen that flow from the mother are ultimately rooted (firmly established) in the energy of her Blood. The combination of the mother's Qi and Body Fluids purifies and cleanses the Shen of the fetus, which was formed at conception. This purifying action transforms into Heat, causing the Yang energy to arouse the Hun-Three Ethereal Souls (the energy of the fetus's spirit), into life. The Five Agents, energies that stem from the Three Ethereal Souls, are currently in a state of awakening and will later reside in the organs.


The energy of the Pericardium Channels flow from the Heart down the center of the mother's body into the uterus cleansing the fetus's Shen.

Figure 2.12. The mother's Pericardium Channels control the third lunar month of creation. The mother's Qi and body fluids purify and cleanse the fetus's Shen (Spirit). The Hun from Heaven and the Po from Earth are established within the fetus's internal organs.

The Five Agents are energies that are linked to a person's moral qualities and can be categorized as the five virtues of the Five Yin Organs. The Five Agents are also categorized into Five Elements. The psycho-emotional components of the Prenatal Five Agents and Postnatal Five Emotions are both stored within the body's Five Yin Organs, and are expressed as the child grows into adulthood (Figure 2.13). When one of the internal organs is stimulated, a Yin or Yang psycho-emotional reaction is created. Psycho-emotional energetic interactions are feeling manifestations expressed through either the positive moral qualities of the congenital Five Agents (Yang - kindness, order, trust, integrity, and wisdom) or the negative developed emotional experiences of the Acquired Five Emotions (Yin - anger, joy, worry, grief, and fear).

The Five Agents are connected to the Wu Jing Shen-Five Essence Spirits (Hun, Shen, Yi, Po, and Zhi), and stored within the energetic elemental nature of the body's Essence (Jing) of Wood, Fire, Earth, Metal, and Water. The Five Elemental Energies however, encompass not only the body, but all of the myriad phenomena of the body and nature, combining and recombining in infinite ways to produce manifested existence.

1. The Wood Agent (the Virtue of Kindness) represents benevolence and compassion. This agent is connected to the Hun-Three Ethereal Souls, and stored in the Liver. Wood affects the energetic channels' flow, tendons, ligaments, small muscles, peripheral nerves, iris of the eyes, vision, tears, bile, nails, and external genitalia. After birth, the Liver will also store the emotions of anger, irritability, blame, rage, resentment, and jealousy. When excess anger is eliminated, benevolence, compassion, and love for others is allowed to flourish.
2. The Fire Agent (the Virtue of Order) represents peace and boundary setting to foster social harmony. This agent is connected to the Shen-Spirit, and stored in the Heart, affecting the energetic channels' flow, blood vessels, complexion, perspiration, and the tongue. After birth, the Heart will also store the emotions of shock, nervousness and excitement. Eliminating excess nervousness allows love, forgiveness, and joy to be experienced. The environment is then conducive for peace, contentment, and orderliness, which allow self-esteem to grow.
3. The Earth Agent (the Virtue of Trust) represents faith, honesty, openness, acceptance, and truthfulness. This agent is connected to the Yi-Intention (thoughts and ideas) and stored in the Spleen, affecting the energetic channels' flow, large muscles, lymph and saliva secretions, mouth, lips, and taste. After birth, the Spleen will also store the emotions of worry, remorse, regret, obsessiveness, and self-doubt. Eliminating excess worry allows trust and peace of mind to exist.
4. The Metal Agent (the Virtue of Integrity) represents righteousness and dignity. This agent is connected to the Po-Seven Corporeal Souls (the material aspect of the spirit) and stored in the Lungs, affecting the energetic channels' flow, skin and mucous membranes, body hair, nose, and the sense of smell. After birth, the Lungs will also store the emotions of grief, sorrow, anxiety, sadness, shame, disappointment, and guilt. Once excess sorrow is relieved, a deeper sense of righteousness, integrity, dignity, and social responsibility exists.

The Five Elements	**Congenital Agents**	**Acquired Emotions**
Wood	Kindness	Anger
Fire	Order	Joy
Earth	Trust	Worry
Metal	Integrity	Grief
Water	Wisdom	Fear

Figure 2.13. The Five Agents

5. The Water Agent (the Virtue of Wisdom) represents rationality, clear perception, and self-understanding. This agent is connected to the Zhi-Will (mental drive and determination) and stored in the Kidneys, affecting the energetic channels' flow, brain, inner ear, hearing, spinal cord, cerebrospinal fluid, bones, bone marrow, ovaries, testes, head and pubic hair, anus and urethra, and sexual fluids. After birth, the Kidneys will also store the emotions of fear, loneliness, and insecurity. Once excess fear is eliminated, the mind becomes rational and, therefore, wise.

The energy of the Three Ethereal Souls (Hun) is composed of three separate parts and flows with the Blood as it moves. The energy of the Corporeal Souls (Po) is composed of seven separate parts and follows the Jing as it moves. The Hun and the Po are characterized by their movements. The Po are also referred to as the supernatural Ling (A Moving Spirit). The Hun are also referred to as the supernatural Shen (Mind / Spirit). The Shen is the "active impulse" and Ling is the "active, enabling mover." As the Jing and Blood combine, the fetus's Shen continues to be created.

At the end of the third month, the internal organs, limbs, and external sex organs of the fetus are fully formed, and the nails have developed.

MONTH FOUR

During the fourth lunar month, the mother's Triple Burner Channels, which are connected with the Yang organs, stabilize the fetus's blood vessels (Figure 2.14). The Water Jing is beginning to be accepted by the fetus's body allowing the Yin organs to develop normally.

Beginning in the fourth month and continuing throughout the ninth month, each of the Five Element's energetic nature and the specific characteristics of each element's Essence will be progressively activated and developed within the fetus's body. The first to enter is the Water Jing.

The Water Jing energy supervises the genetic developmental phase of the fetal growth. This energy encompass the fetus's unconscious reservoir of innate and intuitive intelligence, will, and life-force energy, relating to divine love, power,



The energy of the Triple Burners Channels flows up both arms into the Heart and down the center of the body into the uterus, directing the development and formation of the fetus's connective tissue and fascial surfaces.

Figure 2.14. The mother's Triple Burners Channels are responsible for the changes in the fourth lunar month of creation. The Water Jing (Essence) is beginning to be accepted by the fetus.

and spirit. Any faltering of this energy (due to the influence of fetal toxins) is associated with both pervasive and subtle neurological disorders, and a predisposition to severe psychological disorders (e.g., schizophrenia).

As the fetus develops, the mother's Triple Burners will direct the development of the connective tissues and fascial surfaces. This process is referred to as "the development of Blood and Qi penetrating to the ears and eyes and circulating throughout the fetus's channels and connecting vessels."

Through the later stages of fetal development the embryo's seemingly homogenous tissues transform into the fetus's differentiated tissues of muscles, bones, and organs (an important part of which is connective tissues). A very large part of the body consists of connective tissues and membranes functioning in such a way as to hold together and maintain the body's external and internal structures.

From a gross anatomical level, the body's structures connect not only through the fascial planes but microscopically through the connective tissues. This internal network facilitates the body's intercellular communication. These structures, both energetic and physical, connect the fetus's body, forming a vast reservoir capable of regulating and transferring the body's Jing-Essence, Qi-Energy, and Shen-Spirit.

MONTH FIVE

During the fifth lunar month, the Spleen Channels become responsible for completing the development of the four limbs (Figure 2.15). The fetus begins its own respiratory movement along with the mother's respiration. The Fire Jing is accepted into the fetus, creating Internal Qi, that stabilizes the fetus's Five Yin Organs' Qi.

The Fire Jing energy generates and controls, protects and integrates, divides and harmonizes the fetus's internal energies to promote emotional/spiritual well-being. Any faltering of the Fire Jing energy is associated with problems of right (Yin) and left (Yang) brain communication (e.g., the correct balance of male/rational and female/intuitive energies).



The energy of the Spleen Channels flows up the inside of both legs into the uterus, developing the fetus's extremities.

Figure 2.15. The mother's Spleen Channels are responsible for the fifth lunar month of creation. The development of the fetus's four limbs is completed. The Five Agents are distributed within the fetus's Five Orbs (Five Yin Organs). The Fire Jing is beginning to be accepted by the fetus.

At this stage of development, the Five Agents are distributed to the Five Orbs. These Orbs are energetic spheres of influence or energetic spatial cavities (i.e., internal organ tissue chambers). These Orbs pertain to the Essence, Blood, Qi pools and channels of the Five Yin Organs. The Five Orbs also pertain to and encompass all of the areas in the body that the Five Yin Organs influence. The Five Agents are distributed as follows: Kindness to the Liver, Order to the Heart, Trust to the Spleen, Integrity to the Lungs, and Wisdom to the Kidneys. This distribution causes the Hun to stabilize within the fetus's organs, which contributes to keeping the fetus's Shen at peace.

At the end of the fifth month the fetus's body systems develop rapidly. Its head is less disproportionate to the rest of the body, and its spontaneous muscular movements are commonly felt by the mother.

MONTH SIX

In the sixth lunar month of creation, the mother's Stomach Channels create the fetus's muscles. The Metal Jing is established in the fetus's body, stabilizing the sinews and connective tissues (Figure 2.16).

The Metal Jing energy is also responsible for fetal formation and the ability to form and maintain emotional bonding with others. Any faltering of the Metal Jing energy is associated with problems of emotional attachment (e.g., autism).

During the sixth month the Yang organs are in the process of developing. The Essence of the Yang organs receives, moves, transforms, digests, and excretes substances. The Six Storage Areas of the body's Yang organs constantly fill and empty, and include the Bladder, Gall Bladder, Stomach, Large Intestine, Small Intestine, and Triple Burners.

1. The Bladder controls, stores, and releases the urine. This Yang organ is responsible for receiving, storing, and releasing urine at the proper time.
2. The Gall Bladder stores and secretes bile. This Yang organ is responsible for storing and releasing bile at the proper time.
3. The Stomach stores the food. This Yang or-


The energy of the Stomach Channels flows down from the head and torso into the uterus, developing the fetus's muscles and connective tissues.

Figure 2.16. The mother's Stomach Channels are responsible for the sixth lunar month of creation. The Six Pitches are established within the body's storage areas. The Metal Jing is beginning to be accepted by the fetus's body.

gan is responsible for the receiving, storing, rotting, and ripening of food at the proper time.

4. The Large Intestine stores the solid waste. This Yang organ receives, stores and absorbs food and releases waste at the proper time.
5. The Small Intestine stores and transforms liquid matter. This Yang organ receives, stores, transforms, and digests food, and releases its waste products at the proper time.
6. The Triple Burners store the body's Qi. This area of the body receives, stores, absorbs, and moves Qi.

At this stage of development, the Six Pitches which support and stabilize the Lower Burners (see Chapter 6) and nourish the Qi are established in the organs known as the Six Yang Organs, also called the Six Storage Areas.

The Six Pitches are six specific tone resonances (notes) that vibrate within the body's internal organs and stimulates specific organ and tissue areas. These Six Pitches relate to the Five Prenatal (Heaven) Elemental Sounds of Jue-Wood, Zhi-Fire, Gong-Earth, Shang-Metal, and Yu-Water. The sixth note Xi relates to the Postnatal (Earth) Fire Element and corresponds to the Pericardium and Triple Burners. The ancient Chinese used these Six Pitches for specific clinical treatments. The sound "Yu" for example, spoken in a low tone, will vibrate the lower abdominal area and is used for the treatment of Kidney and Bladder problems.

In the sixth lunar month of formation, the fetus's eyelids separate and eyelashes form, and its skin is wrinkled.

MONTH SEVEN

During the seventh lunar month, the mother's Lung Channels create the bones, skin, and hair (Figure 2.17). The Wood Jing is beginning to be accepted by the fetus's body.

The Wood Jing energy supervises the assertion and direction of the fetus's emotional/spiritual aspects. Any faltering of the Wood Jing energy is associated with severe psychological problems (e.g., passive-aggressive personality disorder).

In the seventh lunar month, the fetus's Stom-


The energy of the Lungs' Channels flows down from the center of the torso into the uterus, creating the fetus's bones, skin, and hair.

Figure 2.17. The mother's Lung Channels are responsible for the seventh lunar month of creation. The Seven Essential Stars open the orifices to let in the light from Heaven and Earth. The Wood Jing is beginning to be accepted by the fetus's body.

ach and Intestines are stabilized, and the Seven Essential Stars open the body's orifices to absorb the light from Heaven and Earth. These stars consist of the sun, moon, and five planets: Mars, Venus, Mercury, Saturn, and Jupiter. Each star is associated with one of the body's orifices: eyes, ears, nostrils, mouth, anus, and urethra. These orifices serve as receiving and projecting energetic portals for Jing-Essence, Qi-Energy, and Shen-Spirit. They also serve as messengers of the body's Five Yin Organs. Thus the Liver receives messages through observation, the Heart through speech, the Spleen through taste, the Lungs through smell, and the Kidneys through hearing.

These energetic messages are received by the body's Wu Jing Shen and emotionally and energetically interact through the body's Six Openings.

1. The eyes absorb images into the Liver which affect the Hun (The Three Ethereal Souls).
2. The ears absorb sounds into the Kidneys which affect the Zhi (Will Power).
3. The nose absorbs smells into the Lungs which affect the Po (The Seven Corporeal Souls).
4. The tongue absorbs tastes into the Spleen which affect the Yi (Intent / Intellect).
5. The physical body absorbs sensations into the tissues which affect the Shen.
6. The spirit (along with the physical body) absorbs sensations into the Heart which also affect the Shen (Spirit).

Physically, during this lunar month, there is a substantial increase in the fetus's weight and its head and body are more proportionate. The fetus can survive if born prematurely (between 27 and 28 weeks); however, its hypothalamic temperature regulation and the Lungs' production of surfactant (a phospholipid substance important in controlling the surface tension of the air-liquid emulsion present in the lungs) are still inadequate.

MONTH EIGHT

In the eighth lunar month, the mother's Large Intestine Channels complete the formation of the fetus's skin, harmonizing the Heart (the Shen), and quieting the breathing. As the fetus receives the Zong Qi-Essential Qi (energy collected from Heaven and Earth and accumulated within the


The energy of the Large Intestine Channels flows up the arm and down the center of the torso into the uterus, completing the formation of the skin, harmonizing the Heart, and quieting the breathing.

Figure 2.18. The mother's Large Intestine Channels are responsible for the eighth lunar month of creation. The Earth Jing is beginning to be accepted by the fetus's body.

chest) from the mother's Spleen, the Earth Jing begins to be accepted by the fetus's body, completing the formation of the skin (Figure 2.18)

The Earth Jing energy supervises the quality and maturation of the fetus's emotional and spiritual bonding and boundaries. Any faltering of the Earth Jing energy is associated with problems of severe psychological disturbances (e.g., schizophrenia). These psychological disturbances may be evident at birth or develop later in life.

The mother's Large Intestine Channels control the fetus's orifices. At this stage in development, the fetus's muscles and flesh are formed. The formation and consolidation of the fetus's Jing is now completed, along with the fetus's developing Zhen Qi-True Qi (energy that circulates in the body's channels and collaterals which nourishes the Yin and Yang organs and fights disease).

At the end of the eighth month, the bones of the fetus's head are soft, its skin is less wrinkled, and there is subcutaneous fat deposited throughout its body. If it is a male child, its testes will now descend into the scrotum.

At this stage, the fetus will normally assume an upside-down position to prepare for its birth descent. If the fetus is born prematurely, its chances for survival are now much greater.

MONTH NINE

During the ninth lunar month, the mother's Kidney Channels control the amount of energetic intake the fetus absorbs through its connection to the umbilicus (Figure 2.19). Qi, Blood and food nutrition are absorbed into the fetus's body, after they pass through the umbilical vein to the fetus's Liver. From the Liver, the nutrients are processed and absorbed into the Blood to be distributed throughout the fetus's body.

The flexible structure of the umbilical cord is attached to the placenta. The placenta, which formed on the uterine wall after the first week of pregnancy, consists of tissues from both the mother and the embryo. The function of the umbilical cord is to carry away the baby's waste products and pass food, energy, and oxygen from the mother's blood stream to the embryo. The mother's Kidney Channels will regulate the re-


The energy of the Kidney Channels flows up the inside of the legs and into the uterus, stabilizing the fetus's energetic boundaries.

Figure 2.19. The mother's Kidney Channels are responsible for the ninth lunar month of creation. All the fetus's spatial cavities and energetic boundaries are now established.

lease and absorption of Qi and Shen flowing into the fetus's Liver through the umbilical cord.

After the umbilical cord has been severed, the baby's umbilical veins still remain. These umbilical veins eventually become the ligamentum teres that connect from the umbilicus, up along the interior surface of the abdominal wall, through the free margin of the falciform ligament, to the right and left lobes of the Liver. This maintains the baby's connection between its Liver and its Lower Dantian (navel).

At this stage in development, all the fetus's energetic spatial cavities (internal organ tissue chambers) and energetic boundaries are arranged to keep the fetus safely prepared for its birth journey.

Also in this month, the Internal Palaces and Nine Dantian Chambers (the nine internal cavities established within the fetus's Three Dantians (the body's three energetic reservoirs) are arranged and securely established to keep the fetus's Jing-Essence safe.

In the ninth month, additional subcutaneous fat accumulates throughout the fetus's body. Externally, the fetus's fingernails will extend to the tips of the fingers and sometimes beyond.

MONTH TEN

At the tenth lunar month, the mother's Bladder Channels control all Five Yin Organs (Liver, Heart, Spleen, Lungs, and Kidneys) and Five Yang Organs (Gall Bladder, Small Intestine, Stomach, Large Intestine, and Bladder) (Figure 2.20). The baby's energetic reservoirs (the Three Dantians)



Figure 2.21. Heaven and Earth Qi settle into the baby's Lower Dantian and the process of birth begins.


The energy of the Bladder Channels flows down the back of the head and back and into the uterus, securing the fetus's Dantians and the spatial cavities surrounding the major organs.

Figure 2.20. The mother's Bladder Channels are responsible for the tenth lunar month of creation. The baby's Dantians, and spatial cavities surrounding the major organs are completely developed to maintain the safety of the baby's Jing. Heaven and Earth Qi settle into the baby's Lower Dantian and birth begins.

and the internal spatial cavities that surround the major organs are developed to maintain the safety of the baby's Jing. The child is ready to be released into the world. The process of birth begins when Heaven Qi and Earth Qi settle into the baby's Lower Dantian (Figure 2.21).

The energy of the Seven Corporeal Souls (Po) is responsible for the first physiological processes after birth, allowing the child's eyes to see, ears to hear, and Heart to perceive. The Po are also responsible for the movements of the hands and feet and the breathing pattern.

The purpose for the Qigong doctor's study of the ten lunar month developmental process, is to create a foundation for understanding the patient's physical development. This knowledge of the patient's physical development establishes a comprehension of the structural formation of the Five Elemental Constitutions. The Five Elemental Constitutions are described in the next chapter.

POSTNATAL ENERGY DEVELOPMENT

Throughout prenatal development, the Eight Extraordinary Vessels (see Chapter 7) were responsible for transporting, transforming, and producing Qi and Blood for the fetus, while the Twelve Primary Channels (see Chapter 6) were still in the process of gradual development. The focus of energetic activity generated from the fetus's Lower Dantian and Eight Extraordinary Vessels, resonates throughout the fetus's body creating tissue development.

Once the umbilical cord is severed, the primary focus of energy shifts, becoming diverted from the Lower Dantian to the Middle Dantian (located in the baby's chest area). After birth, Gu Qi (food energy) flows into the baby's Stomach while it nurses and begins the movement of Blood and Qi within the Twelve Primary Channels. These Twelve Primary Channels will now assume the responsibility of circulating Qi and Blood throughout the baby's entire physical and energetic structure. The Eight Extraordinary Vessels shift their function to regulating the baby's channel Qi. The Taiji Pole (which has been in the process of dropping from the fetus's Mingmen area to the Huiyin area) is now stabilized in the perineum.



Figure 2.22. As the child develops, the energetic rivers and pools regulate the formation and production of his or her growth.

The natural resonant vibration of the baby's Taiji Pole (energetic core) causes an energetic expansion and contraction, projection and reception that simultaneously affects the baby at five distinct levels: physical, mental, emotional, energetic and spiritual. Balanced physical growth will only occur when all five levels are in equilibrium. The physical body is generally the slowest realm to respond to physical growth. Matter does not develop at the same rate as energy, mind, or spirit. This being the case, the energy, mind, and spirit must wait patiently for the physical body to evolve before progressing as a whole (Figure 2.22).

ENERGETIC EMBRYOLOGICAL OVERVIEW

Understanding the energetic process of fetal development provides the Qigong doctor with an overview of the energetic factors in tissues, organs, and channel function. This understanding is essential for diagnosing the origin and causes of disease as being either congenital or acquired. Unlike Western medicine, Chinese medicine treats the root of the illness, not just its symptoms. In Medical Qigong therapy, cases of congenital insufficiency of Qi or congenital disorders of Qi activities, are treated by either tonifying (strengthening) the Eight Extraordinary Vessels or purging (eliminating) the pathogenic energy from the Eight Extraordinary Vessels. This consolidates and regulates the patient's Prenatal Qi.

For acquired diseases, the patient can only be cured when a selection of points and the methods of emitting Qi for purgation or tonification are determined according to the imbalances of Qi circulation in the Twelve Primary Channels. Both congenital and acquired factors should be considered in every case because both the origination and development of diseases may result from either source, or a combination of both sources.

THE ETERNAL SOUL

In Chinese energetic medicine, the Original Spirit differs from the body's Eternal Soul. The Original Spirit (Yuan Shen) is rooted in the combined Jing, Qi, and Shen of the mother and father. Later the Yuan Shen is integrated and sustained through the embryo's own Five Spiritual Essences or Wu Jing Shen (see Chapter 13), which are created from the energy of the Five Yin Organs. The Eternal Soul, however, is absorbed into the mother's egg at the time of conception, as the sperm enters.

The Eternal Soul is rooted into the Heart and Middle Dantian area by a silver cord, which is additionally rooted within the body's Taiji Pole. When the Eternal Soul becomes rooted within the body's Taiji Pole, it is described as "emitting the spark of the supreme fire" (Light of God), and is considered a divine fragment of God, or the Dao. It is from this divine resonating light that the body's Taiji Pole becomes energized and all Three Dantians become interconnected. The rooting of the Eternal Soul is therefore considered the first emanation from the divine source within the human body.

To travel, and receive spiritual guidance and insight, the Eternal Soul can leave the body in the form of an "Astral Body," departing through the Baihui point at the crown of the head. The silver


Tai Yi "Great Divinity"
Resides in the head (Light)
Upper Dantian (Intuitive Communication)
Resides in the Heart (Vibration)
Si Ming "Administer of Destiny"
Middle Dantian (Empathic Communication)
Bai Yuan Regulates the Seven Po
Wu Ying Regulates the Three Hun
Xia Taō Kang "Below Healthy Reach" (Life)
Resides in the Navel (Heat)
Lower Dantian (Kinetic Communication)

Figure 2.23 The Lords of the Three Dantians: Tai Yi, Si Ming, and Xia Tao Kang

cord, which is connected to the Astral Body, is located at the fifth and sixth thoracic vertebrae. This physical area is the place on the spine where the silver cord lifts off when an individual astral travels. This area also corresponds to the back of the Heart center, between Ling Tai GV-10 (Spirits Platform) and Shen Dao GV-11 (Spirits Gate). The astral travels of the Eternal Soul are generally to one of the nine higher spiritual planes.

The Eternal Soul becomes the intermediator between the divine, the Original Spirit (Yuan Shen), the Acquired Spirit (Zhi Shen), and the body's Soul Extensions (various traits and characteristics). These Soul Extensions manifest in the energetic field, and influence behavior and perception.

Once the Eternal Soul has established its residence, it separates its Yin and Yang spiritual energy into three spiritual energies which are the energizing forces of the body's Three Dantians, and are called Tai Yi, Si Ming, and Xia Tao Kang. These three spiritual energies are referred to as the Lords of the Three Dantians, and are named according to their function: Tai Yi translates to mean Great Divinity, Si Ming translates as The Administrator of Destiny, and Xia Tao Kang translates as Below Healthy Peach (Life).

The Chinese medical terminology, which describes the Eternal Soul as consisting of three spiritual energies called the Lords of the Three Dantians, is extremely metaphoric and is used to describe the many energetic aspects of the human soul.

The Eternal Soul radiates through the physical, energetic, and psycho-emotional domains of human existence (Figure 2.23). Whole-body consciousness is the main characteristic of the Eternal Soul. Without the interactive process of the Eternal Soul, energy would have no specific direction and would remain in meaningless activity. The Eternal Soul radiates energy in all directions throughout the body and is responsible for life and health, as well as the formation and growth of the body.

In the scope of energetic manifestations, the Eternal Soul expresses its innate qualities as energetic movement, functioning through the physical form. It is led by the Shen and is connected to all parts of the body. The light of the Eternal Soul is revealed through the light or energy of the eyes. Through the influence of the Eternal Soul, all of the body's energetic processes seek wholeness. The Eternal Soul knows exactly what is needed in every situation for survival and health preservation.

The distinction between the Eternal Soul and the Yuan Shen is that the Eternal Soul, although spiritual in nature and connected to the Wuji (infinite space), is still considered individuated. The Yuan Shen, however, although individual in its conditioned state, can also be universal. The connection between you and others, for example, is considered a spirit connection (kindred spirits uniting). The connection between you and the divine is considered a soul connection (your true innate nature reconnects with its origin), and relates only to the connection between one's self and the divine.

When the Qigong doctor meditates, the Eternal Soul consciously enters a spiritual realm wherein the doctor perceives the ideal of things rather than the things themselves. The doctor no longer depends on the senses, but upon a clear inner-vision that perceives the whole picture. It is here, within this spiritual state, that the higher knowledge of things unfolds through divine intelligence and all things reveal their true nature.

When conserved and amplified through practice, the energy of the doctor's Eternal Soul reveals a bright radiant quality, which permeates and penetrates the cells, tissues, organs, and external energy fields. These energetic fields create for the Qigong doctor a strong luminous shield of energy, capable of guarding the body against an attack of hostile energy by enabling it to:

- ward off the invasion of External pathogens and harmful electromagnetic fields,
- ward off the negative influences of malevolent spirits,
- ward off ill intentions and spiritual malice projected unconsciously or deliberately by others, and
- ward off the parasitic influences of demonic forces.

At conception, when the sperm enters the ovum, a polar axis that forms the embryo's Taiji Pole is created. The energetic vortex thus created draws spiritual energies into the body from Heaven and Earth. After birth, the degree to which an individual can draw upon, and absorb, spiritual energy depends on his or her karma (previous thoughts, actions and level of consciousness), and course of destiny.

During conception, three spiritual energies are given to each individual from the divine to create and maintain the existence of the Eternal Soul. These three spirit energies, called the Lords of the Three Dantians, reside in the innermost subtle aspect of the body and are described as follows:

1. The Tai Yi (Great Divinity) resides in the head and Upper Dantian, and is considered the Lord of the Nei Wan (Innermost Palace). It governs a multitude of the body's spirits, causing man's Yuan Shen to shine externally. The Tai Yi facilitates awareness of the Three Ethereal Souls (Hun), and advocates for personal spiritual enlightenment.
2. The Si Ming (The Administrator of Destiny) resides in the Heart and Middle Dantian, regulates the body's Qi, and is the source of the mind and its emotional connections. The Si Ming is considered the Eternal Soul (some believe that this soul reincarnates). The Si Ming controls the spirits Wu Ying and Bai Yuan, that directly affect the body's Jing, Qi, and Shen. The Si Ming challenges our reactions to various internal and external obstacles.
   a. The Spirit Wu Ying (Without Excess) occupies the left side of the body, and regulates man's Three Ethereal Souls (Hun), which are called:
      (1) Tai Guang (Eminent Light),
      (2) Shang Ling (Pleasant Soul) and the Five Agents, and
      (3) Yu Jing (Hidden Essence).
   b. The Spirit Bai Yuan (Pure Origin) occupies the right side of the body, regulates the Seven Corporeal Souls (Po), which are called:
      (1) Flying Poison
      (2) Unclean Evil
      (3) Stinking Lungs
      (4) Corpse Dog
      (5) Fallen Arrow
      (6) Yin Bird
      (7) Devouring Robber

Both the Hun (that come from Heaven) and the Po (that come from Earth) are established within the fetus's internal organs at conception but lie dormant until the third month. This is because, at the third lunar month, the fetus's Orbs are sufficiently formed. One belief maintains that the Hun and Po, although residing in the energetic form of the fetus, frequently leave and return to gather and absorb universal and environmental Qi. The Hun will connect with divine spiritual beings, as well as with God. The Po will connect with surrounding environmental spirits.

Note: The Three Ethereal Souls are traditionally referred to as the "Hun" with the assumption that this term depicts all three Hun, thus in Traditional Chinese Medicine the Hun are sometimes referred to in the singular case. The Seven Corporeal Souls are traditionally referred to as the "Po" with the assumption that this term depicts all seven Po, thus in Traditional Chinese Medicine the Po are sometimes also referred to in the singular case.

3. The Xia Tao Kang (Below Healthy Peach/Life) resides in the navel and Lower Dantian and preserves the root of the body's Jing-Essence.

Upon the death of the body, the Hun return to Heaven, the Po return to Earth, and the spiritual energies of Tai Yi and Xia Tao Kang combine with the Eternal Soul stored in the Si Ming (Administrator of Destiny). These three spiritual energies (Tai Yi, Xia Tao Kang, and Si Ming) blend together, combining into one energy that completes the integration of the Eternal Soul. This soul leaves the body and returns back through the tunnel of light to the divine light for judgement, or wanders the Earth becoming a Gui (ghost).

In Western culture, our internal dialogues are sometimes associated with encounters with good or evil spiritual influences. In Chinese medicine the internal dialogues that influence the patient's psyche are also divided into good and evil; these spiritual/emotional influences are considered to be specific good and evil characteristics in man's Hun and Po. The spiritual components and influences of the Hun and Po are considered to be separate entities, or archetypes, acting upon man's Shen, which in turn affects the Eternal Soul.

These archetypes are regarded as spirit souls that can exert a positive or negative influence on a individual's life depending on the nature of the individual's Eternal Soul. The good internal influences manifest through the Hun. The evil internal influences manifest through the Po. The Hun or Po can motivate personal growth, or can hinder it and cause illness, and even the demise of the body.

THE THREE ETHEREAL SOULS (HUN)

The Three Ethereal Souls are the spiritual part of man that ascends to Heaven upon the death of the body. The Three Ethereal Souls are composed of the Three Hun, that originate from Heaven, reside in the Liver, and resonate from the Three Dantians. The Hun have the following associations: light, Yang, Heavenly soul, Shen, as well as positive emotions and feelings (Figure 2.24). The Three Ethereal Souls are the Tai Guang, Shang Ling, and Yu Jing. They are described as follows:

1. The Tai Guang resonates within the Upper Dantian, and is situated in the cranial cavity, just below the Baihui GV-20 (Meeting of Yin) point. This Hun's name means "eminent light," and it is considered the ultimate balance of pure Yin and Yang energy in harmony. It is connected energetically with the Upper Dantian and Heaven, and always strives for physical, mental, emotional, and spiritual purity.
2. The Shang Ling resonates with the Middle Dantian and is situated in the Heart and corresponding vessels and is linked to the body's Five Agents. This Hun's name translates to "pleasant soul," and it is considered changed (or transformed) Yin energy. It is connected with the Middle Dantian and is a soul that is concerned for others. It is associated with the Five Agents, and produces our desire to be involved in a diversity of social interests and responsibilities.
3. The Yu Jing resonates with the Lower Dantian. Translated, the name means "hidden essence." This Hun is considered mixed (or combined) Yin energy. It is connected with the Lower Dantian and is associated with the Earth, producing our desire for enjoying life's pleasures and comforts, as well as the pure passions of life.



Figure 2.24. The Three Ethereal Souls are composed of the three Hun, that originate from Heaven and reside in the Liver. The Hun represent spiritual consciousness, provide the energetic movement of the mind, and are associated with Heaven Qi and the Five Agents. The Hun are the spiritual part of man which ascends to Heaven after death. The Hun are associated with positive emotions and feelings, light, Yang, Heaven, and Shen.

The Three Ethereal Souls are named (1) Tai Kuang, (2) Shang Ling, and (3) Yu Jing.

The Hun are classified as Yang spirits and are to be cultivated and refined. Imagination, visualization, and positive affirmation in the form of prayer and meditation are needed to awaken and establish an active relationship with the Three Ethereal Souls.

The Hun can be accessed through the Hunmen Bl-47 (Gate to the Hun) point on the back of the body (below the shoulders). It is used clinically to spread Liver Qi and harmonize the Middle

Burner. The Hun respond to Heaven's energetic grids (universal energetic fields). The stars and planets within these Heavenly grids exert an influence on the Hun causing each individual's body to react to certain astrological configurations. The positive or negative reaction is based on the affinity of the vibrational rate of the Hun and the energies of a particular astrological alignment.

THE SEVEN CORPOREAL SOULS (PO)

The Seven Corporeal Souls are closely linked to our body's Jing-Essence. The Po manifest the body's Essence in the form of hearing, sight, and tactile sensations.

The Po pertain to the animal nature of man's instincts and drives and are considered inferior souls to the Hun (Figure 2.25). The Po are passionate and advocate experiencing life in its fullest measure. They are, however, in a constant state of dying. The Po will return to the Earth with the body after death. The Po have the following associations: heavy, Yin, Earthly Spirit, Essence, and negative emotions and feelings.

The Po are a composite of Seven Corporeal Souls, which originate from Earth, reside in the Lungs, and resonate from specific areas in the body. The Po can be accessed through the Pohu Bl-42 (Door to the Po) point on the back of the body (between the shoulders). This point is used clinically to treat energetic imbalances of the Lungs. The Po respond to the Earth's energetic grids (see Chapter 10) and cause each of us to resonate in harmony or disharmony to certain ecological configurations. An individual's attraction, or feeling of not belonging, depends on the vibratory affinity, or lack thereof, between the body's Po and the environmental energy of a particular area.

When the fetus begins its movement, its Yin energy tranquilizes the Po, which act as guardians of the fetus's body. The Po's nature is one of survival, and their energies can be directed towards self-preservation or self-destruction (devouring and robbing the body of life-force energy).

The Seven Po are located along the line between the Huiyin CV-1 and the Baihui GV-20 points, embracing the body's Taiji Pole (also called the Center Thrusting Channel) at the following locations:

Figure 2.25. The Seven Corporeal Souls are composed of the Seven Po, which originate from Earth and reside in the Lungs. The Po are regarded as the animal nature or drive. They provide energetic movement to the body's Essences, and are considered inferior Souls. The Po will return to the Earth with the body after death, and are associated with negative emotions and feelings, heaviness, Yin, Earth, and Jing.

The negative thoughts and emotions of the Seven Corporeal Souls are named (1) Flying Poison, (2) Unclean Evil, (3) Stinking Lungs, (4) Corpse Dog, (5) Fallen Arrow, (6) Yin Bird, (7) Devouring Robber.

1. The Po of Essence (Soul of the Five Element Earth) is located at the midpoint of the Taiji Pole. This Po is the counterpart to the Hun's Earth Agent (the Virtue of Trust). This Po manifests through the acquired emotions of worry, regret, remorse, obsessiveness, and self-doubt.
2. The Po of Qi (Soul of the Five Element Wood) is located below the diaphragm. This Po is the counterpart to the Hun's Wood Agent (the Virtue of Kindness). This Po manifests through the acquired emotions of anger, irritability, blame, rage, resentment, and jealousy.
3. The Po of the Spirit (Soul of the Five Element Metal) is located posterior of the Tanzhong (CV-17) point, inside the mediastinum, near the Middle Dantian. This Po is the counterpart to the Hun's Metal Agent (the Virtue of Integrity). This Po manifests through the acquired emotions of grief, anxiety, sadness, shame, disappointment and guilt.

4. The Po of Yin (Soul of the Five Element Water) is located posterior of the navel, in front of the Taiji Pole. This Po is the counterpart to the Hun's Water Agent (the Virtue of Wisdom). This Po manifests through the acquired emotions of fear, loneliness, and insecurity.
5. The Po of Yang (Soul of the Five Element Fire) is located anterior of the Mingmen (GV-4) point behind the Taiji Pole. This Po is the counterpart to the Hun's Fire Agent (the Virtue of Order). This Po manifests through the acquired emotions of nervousness, shock and excitement.
6. The Po of Sex (Soul of Heaven) is located below the Baihui (GV-20) point in the Ni Wan (Upper Dantian) area.
7. The Po of Life (Soul of Earth) is the only one not located on the Taiji Pole, but is located at the bottom of the feet in the Yongquan (Kd-1) points and is considered a neighbor of the Soul of Essence.

The Seven Corporeal Souls (Po) are also called the "seven animals," or "sentient souls of the body," and "seven turbid demons." When afflicted or restless, the animal nature of the Seven Po quickly becomes hostile, and their names change to express the different negative thoughts and emotions expressed from each Po soul. Each Po has a favorite mantra that it whispers inside a person's mind to influence the individual. The Po's Seven Turbid Demon Natures are described as follows.

1. The Flying Poison (or Quick Evil) suddenly explodes with rage and venomous thoughts of evil intention (e.g., "I'll kill you for that!" "How dare they!").
2. The Unclean Evil (or Shame) entices by tempting and luring an individual into a place or situation from which escape is difficult, and then creates distress in the form of guilt, which generates shame. This spirit creates a feeling of being discredited, dishonored, or disgraced (e.g., "I'm worthless;" "No one has or will ever love me.").
3. The Stinking Lungs (or The Smell of Death) destroys hope, which can lead to a sense of despair (e.g., "I just want to die;" "Just kill me and get it over with!").
4. The Corpse Dog (or Being Scorned) is like a dog that has been beaten and starved, the presence of this spirit intensifies depression by despising itself and holding itself in contempt to a point of no return (e.g., "I'm not worth keeping alive;" "Leave me alone to die!").
5. The Fallen Arrow generates the foregone conclusion that attempting goals is fruitless (e.g., "I'll never be able to accomplish that." "Why even try? I'll never make it.").
6. The Yin Bird (or Night Tormentor) harasses the individual, causing him or her to experience extreme pain and severe anguish (e.g., nightmares and restless sleep).
7. The Devouring Robber (or Sipping Thief) steals the individual's life-force energy by devouring it through negative emotions such as jealousy, envy, and bitterness (e.g., "You love him/her more than you do me;" "I'll never forgive you!").

The Seven Po help in developing the growth of consciousness by providing obstacles to test the individual's faith and devotion. Many times the Seven Corporeal Souls will work in conjunction with outside spiritually hostile forces to test the individual's spiritual endurance.

After the child has been born, enlightened parents can assist the child in facing his or her own internal demons. Once the child is self-aware, he or she can be taught to restrain and control the Seven Po so as to prevent them from taking control. To minimize the effects of these souls on the body, one can learn special meditations, involving visualization, imagination, positive affirmation, and mantras (literally "protections of the mind" or "mind protectors").

A mantra is a word, phrase, or sound, repeated silently or aloud, that one can consciously use as a tool to guide one's own mental, physical, and emotional states. People naturally repeat both positive (self-affirming) mantras and negative (self-destructive) mantras as part of their internal self-talk. When positive mantras are used by an


The Eternal Soul
The 12 Soul Extensions of the Yuan Shen
Extensions or Personality Characteristics

Figure 2.26. The Eternal Soul, Yuan Shen and 144 Soul Extensions

individual who holds them in high regard, they enable that individual to combat the Seven Corporeal Souls' mantras. These mantras also facilitate connecting the individual to the divine. Used consciously, mantras and/or prayers can uplift and maintain the individual's self-esteem.

The Chinese view meditation as a deep spiritual contemplation that results in openness to the divine. They view prayer as energy focused towards the divine. Individuals choose what to focus their attention on; therefore, any chronic detrimental thoughts can be countered with positive affirmations to change self-destructive habits.

THE ORIGINAL SPIRIT (YUAN SHEN)

The Original Spirit (Yuan Shen) radiates and extends from the interior of the Eternal Soul. This spiritual light crystallizes a spiritual body, gradually becoming consciously effective and moving into action. It envelops the body and communicates through innermost thoughts, sensory feelings, and emotions. Although the body's Jing and Qi will degenerate, the Original Spirit is immortal, as it is the expression of the Eternal Soul.

The Shen develops and contains Twelve Soul Extensions. These Twelve Soul Extensions contain the body's different personality characteristics (Figure 2.26). Although Si Ming controls the residence of the Eternal Soul, the body's Shen is free to make decisions that affect life and health based upon the individual's free will (the interaction between the Yuan Shen and the Zhi Shen), which then manifests through the Twelve Soul Extensions.

THE EFFECT OF THE HUN AND PO ON THE YUAN SHEN

The Yuan Shen is a manifestation of the Eternal Soul and is primary to the Hun and Po. The combination of the Seven Corporeal Souls (Yin Souls) and the Three Ethereal Souls (Yang Souls) creates the sustaining energy for the body's Original Spirit (Yuan Shen). The Yuan Shen also controls and organizes the psycho-emotional aspect of the body's Five Yin Organs, called the Wu Jing Shen or Five Essence Spirits.

The ancient Chinese viewed the Shen as an Emperor, seated within the Heart; the Hun are viewed as a Loyal Minister, seated within the Liver; and the Po are viewed as a Violent General, seated within the Lungs. If the General (Po), is left in control (being only concerned with the survival of self and the body), he will start to dominate (a condition referred to as a rebellious General and a weak Emperor). At the point when the General (Po) dominates, the individual's acquired mind takes over and the individual becomes concerned only with his or her own survival, and thus becomes self-absorbed. The goal for spiritual cultivation is to control the rebellious General, making him into a servant. Once the inner government is orderly, the strong and violent nature becomes tame. Then, through the wise council of the Loyal Minister (Hun), the individual can walk a path of virtue. Virtue is the path that leads the individual's Shen so that even his or her human consciousness is dominated by the Hun and the Yuan Shen.

When the Hun control the energy body and are nourished by the virtues, the energy body then becomes a vehicle for the Heart's Shen, which is non-local and non-linear in terms of time and space.

When the Heart's Shen is no longer dominated by the Yin and Yang souls (Hun and Po) and the Five Element energies of the lower energetic plane (Wu Jing Shen), the individual returns to an awareness of his or her connection to the universe (Wuji) and the divine. This state of consciousness is sustained through prayer and meditation.

When beginning to develop the Heart's Shen, the first separation of the individual's energetic spirit body or "dream body" from the physical body generally leaves the Shen in a weakened state (referred to as Yin Shen). The weakened Yin Shen must be protected. This Yin Shen is part of the Hun, and leaves the body naturally whenever the patient is weak, sick, in shock, or asleep. It may also leave during the early stages of Qigong meditation or Taijiquan practice. The astral travels of the Yin Shen are generally confined to the lower spiritual planes, and it sometimes needs to be reclaimed through "soul retrieval" (see Chapter 19). Once the Shen has been cultivated, refined, strengthened, fortified, and controlled through the development of the energy body, it is then referred to as a Yang Shen. When the energy body spiritually travels, the developed Yang Shen can transverse the Nine Levels of Heaven or the Nine Levels of Earth in an instant.

The Nine Levels of Heaven are nine spiritual planes which exist within Heaven's energetic grids. Within the lower levels there exists enlightened beings coexisting with other spiritual entities. The Nine Levels of Earth are nine spiritual planes which exist within Earth's energetic grids. Within these levels of Earthly spiritual planes there exists various dimensions of animal, vegetable and mineral powers, as well as Earthly spiritual beings.

YIN AND YANG ASPECTS OF THE ETERNAL SOUL

The human soul has an endless source of vitality from the infinite high-frequency force of the divine. This divine energy descends from the Heavens into the body's Taiji Pole, taking up residence and interacting on the physical plane. The body serves as a medium of transformation for the Eternal Soul. The soul's activity extends and expresses its essence through the physical form and through consciousness. As we grow and change, the Eternal Soul maintains stability by providing the energetic blueprint for orderly development. On the spiritual plane, when referring to the energetic dynamics of the Eternal Soul, there are two basic movements: (1) Yin - the downward movement and (2) Yang - the upward movement.

1. The Yin aspects of the Eternal Soul spirals downward. The spiralling movement of the energetic soul results in the energy transforming from the highest divine energetic frequencies to the lowest. Within this spiritual transformation process, there is a parallel gradual decrease in levels of consciousness. The lowest frequency creates matter, and is the bases for all the prenatal transformations. At the higher frequencies, the principles by which Qi operates are difficult to perceive because our lower state of consciousness does not resonate in harmony with the information being

Spiritual Energy	Resides in...	Associated Dantian	Purpose	
Tai Yi Great Divinity	the head as light	Upper Dantian (intuitive communication)	Governs the body's Spirits, makes life shine forth, and encourages man to know the spirits of his Ethereal Soul	
Si Ming Administrator of Destiny	the Heart as vibration	Middle Dantian (empathic communication)	The Eternal Soul—regulates the prime energy of life (Qi) and is the source of the emotions and mind	Wu Ying (Without Essence), occupies the left side of the body and regulates the Three Hun (Ethereal Souls), associated with the Liver
			Controls the Wu Ying and Bai Yuan Spirits	Bai Yuan (Pure Origin) occupies the right side of the body and regulates the Seven Po (Corporeal Souls), associated with the Lungs
Xia Tao Kang Below Healthy Peach (life)	the navel as heat	Lower Dantian (kinetic communication)	Preserves the root of the body's Essence (Jing)	

Figure 2.27. The patient's soul resides in the body's Taiji Pole, connected with Si Ming, the Administrator of Destiny. Upon the death of the physical body, the Three Hun return to Heaven, the Seven Po return to Earth, and the energy of Tai Yi and Xia Tao Kang envelope the Eternal Soul (stored in Si Ming) becoming one energy. The Eternal Soul leaves the body through the specific gate (solar plexus, third eye, or top of the head) associated with the patient's degree of spiritual evolution, returning back through the tunnel of light to the divine.

presented. As energy slows down its resonance, it is more readily perceived by our five senses; this gives matter the quality of hardness, form, and smell, and allows us to observe its energetic patterning.

2. The Yang aspects of the Eternal Soul spirals upward. The spiraling movement of the energetic soul results in energy transforming from the lowest level of consciousness to the highest divine energetic frequencies during postnatal transformation. Spiritual evolution involves a progressive opening up of all of the body's energy centers (Three Dantians) along the Taiji Pole, until a state of absolute unity of body, mind, emotion, energy, and spirit is achieved (known as enlightenment).

In the evolutionary process of the soul, both stability and change become as one when there is a deep connection to wholeness. This soul serves as a pivotal point for the body's Jing, Qi, Shen, Body Fluids, connective tissues, and emotions, all of which express wholeness. Without this connection the patient experiences a serious psychic splitting of his or her energies. The part that is open to change will experience resistance from the part that demands stability.

THE FINAL EXIT OF THE ETERNAL SOUL

As the body begins to die, the Yuan Shen begins to prepare the Eternal Soul for its final journey home. This change of residence for the patient's spiritual energies is crucial. At the time of death the Eternal Soul must disconnect from the Heart and Middle Dantian area, and the soul must exit the dying patient through one of the Nine Orifices. The lower orifices include the anus and urethra, while the upper orifices include the eyes, ears, nostrils, mouth, as well as the Yintang and Baihui areas (Figure 2.27). It is believed that the area from which the patient's soul exits the body determines the state of its spiritual evolution and to which area the patient is most attached (i.e., if the patient is attached to vision, they are more inclined to leave through the eyes, etc.).

When the Medical Qigong doctor is assisting a terminally ill patient, treatment focuses primarily on purging stagnant spiritual energy from the patient's body. Spiritual purging is required to purify and cleanse the patient's Eternal Soul. Once the patient's soul has been cleansed, the patient becomes peaceful as all material, emotional, and spiritual attachments to this life are released. The patient attains a sense of completion and welcomes the final adventure of going home. The last rites performed by various clergy and ministers in Western culture serve a similar purpose.

The Qigong doctor then guides and encourages the patient's Eternal Soul into leaving the body through the top of the head (Baihui). Souls that are more highly evolved exit the body through this area (at the top of the head), while souls of lesser evolution exit the body through lower portions of the physical structure.

The formation of a Gui or ghost is said to derive from the untransformed energy of the Eternal Soul (see Chapter 19).

SUMMARY

One of the unique aspects of Traditional Chinese Medicine is that it addresses all aspects of the body's energy and spirit. It explores in great detail the spiritual transformations in the body's prenatal state, their relationship to the formation of the body, and to the dying and after-death states. Traditional Chinese Medicine further addresses the potential of spiritual involvement as a cause or cure of specific psychophysical diseases. It is through the complete study of the body's physical, mental, emotional, energetic, and spiritual aspects that doctors of Medical Qigong therapy comprehend when and how to treat their patients.

CHAPTER 3

PHYSICAL DEVELOPMENT AND STRUCTURAL FORMATION

FASCIAL DEVELOPMENT AND ENERGY FLOW

According to the *American Medical Association Encyclopedia of Medicine,* "fascia is the fibrous connective tissue that surrounds many structures in the body. One layer of the tissue, known as the superficial fascia, envelopes the entire body just beneath the skin. Another layer, the deep fascia, encloses muscles, forming a sheath for individual muscles, and also separates them into groups. The deep fascia also holds in place the soft organs, such as the Kidneys. The thick fascia in the palm of the hand and sole of the foot have a cushioning, protective function."

In Traditional Chinese Medicine, the fascia is referred to as Huang (meaning any membranous tissue). Fascial development is divided into two stages: prenatal (congenital) and postnatal (acquired). The prenatal fascia is fixed and determined by the combination of the parents' Jing, Qi, and Shen. The postnatal fascia is formed through diet, exercise, and environmental stresses.

Qi is stored within the tissues and inner fascia layers, where it envelops and protects the internal organs. Energy (that has been stored within the body's organs) is available through the fascia for transformation to nourish the patient's body, mind, emotions, energy, and spirit.

The body consists of three tissue layers:

1. The first and innermost layer is made up of the internal organs, which produce and transform Qi.
2. The second layer consists of the body's fascia, tendons, ligaments, and bones, which assist in transporting Qi to the extremities.
3. The third and outermost layer of tissue consists of the muscles and skin, where Wei (Protective) Qi circulates to protect the organism from invasion of external pathogens (Cold, Heat, Wind, and Dampness, etc.).

After being generated within the body's internal organs, Qi is distributed throughout the body's entire energetic network through the channels and collaterals, via the fascia. Each organ has its own layer of weblike fascia, that covers, connects, protects, and nourishes the tissues. The fascia forms the energetic chambers of the body's organs and channel systems. Qi within the body flows between the fascial sheaths and along the channel system. Through trauma, infection, surgery, disease, or chronic muscular tension, areas of the fascia can become stuck together, inhibiting the flow of Qi and Blood.

Our constitutions are formed, in part, by conditions from the environment that affect the innermost layers of fascial development. Traditional Chinese Medicine divides the observation and diagnosis of the physical developments of these inner fascia into Yin and Yang structures and Five Elemental Constitutions.

YIN AND YANG STRUCTURAL FORMATION

Chinese philosophy teaches that the universe is composed of a pair of opposite forces or energies -- Yin and Yang. Everything in the natural world contains both Yin and Yang. Yin and Yang are interdependent; without Yang, Yin cannot grow; without Yin, Yang cannot develop. The energetic transformation of Yin into Yang and Yang into Yin produces the various observable changes of form and matter (see Chapter 21).

Yin and Yang are the principles governing all things within the human body. Life and death originate from the energies of Yin and Yang, and they are the forces that create all physiological change. In Medical Qigong therapy, the physical structure of the human body is divided into Yin and Yang organs and substances, as well as Yin and Yang energetic functions (e.g., Qi that expands and flows outward is Yang, while Qi that contracts and flows inward is Yin).

Yin and Yang are in a constant state of waxing and waning (Figure 3.1). If this waxing and waning exceeds the body's normal energetic limits and loses its dynamic equilibrium, Deficient or Excess Yin and Yang will occur, leading to the development of abnormalities and illness.

Yin Qi naturally ascends (e.g., Spleen Qi ascends the Clear Qi). When Yin Qi becomes pathological or destructive, it moves downward, descending like cascading water (e.g., descending Spleen Qi causes diarrhea or prolapse of the viscera). Another example of the effects of pathogenic Yin Qi descending would be edema.

Yang Qi naturally descends (e.g., Stomach Qi flows downward). When Yang Qi becomes pathological or destructive, it ascends like the flames of a fire, moving upward (e.g., Rebellious Stomach Qi ascends, causing nausea and vomiting). An-

	Yang	**Yin**
Attributes	active, creative, masculine, Fire, Hot, Heaven, light	passive, receptive, feminine, Water, Cold, Earth, heavy
Organs	the six hollow organs (Gall Bladder, Small Intestine, Stomach, Large Intestine, Bladder, and Triple Burners)	the five solid organs (Liver, Heart, Spleen, Lungs, and Kidneys), along with the Pericardium
Respiration	exhalation	inhalation
Time of Day	the 12 hour cycle from 11 p.m. (before midnight) to 11 a.m. (before high noon)	the 12 hour cycle from 11 a.m. (before noon) to 11 p.m. (before midnight)
Seasons	spring and summer	autumn and winter
Normal Movement	outward	inward

Figure 3.1 Yin and Yang are the Principles Governing All Things Within the Body



Figure 3.2. The superior aspect of the body's structure is Yang; the inferior portion is Yin. Think of the sun shining on the upper torso, illuminating the body from the waist to the head, while from the hips downward the lower torso is in the shade.



Figure 3.3. The posterior portion (back side) of the body is Yang; the anterior portion (front side) is Yin. Think of the sun shining on the back, while the abdomen is in the shade.



Figure 3.4. The superficial aspect (exterior) of the body is Yang; the deep portion (interior) of the body is Yin. Think of the sun shining on the external surfaces of the body, while the internal organs remain in the dark.



Figure 3.5. The left side of the body is Yang; the right side is Yin. Think of facing south in the morning, while performing medical Qigong practice. The sun will rise in the east, illuminating the left side (Yang) while the right side remains shaded (Yin).

other example of the effects of pathogenic Yang Qi ascending would be the temperature of a rising fever.

THE YIN AND YANG OF BODY ASPECTS

Comparable to Western anatomy, Traditional Chinese Medicine also divides the body into aspects or planes. In TCM, these classifications are divided into Yin and Yang physical planes and anatomical directions. These divisions assist the Qigong doctor in defining and categorizing the patient's external tissues, and in determining the collection and movement of Qi (i.e., energy moving into and coalescing in the patient's Yin or Yang areas of the body). The structural aspects are categorized as follows.

- The cranial or superior aspect (towards the head) of the body's structure is considered Yang; the caudal or inferior portion of the body (towards the feet) is considered Yin (Figure 3.2).
- The posterior or dorsal portion (back side) of the body is Yang; the anterior or ventral portion (front side) is Yin (Figure 3.3).
- The superficial aspect (exterior) of the body is Yang; the deep portion (interior) of the body is Yin (Figure 3.4).
- The left side of the body is Yang; the right side is Yin (Figure 3.5).

Aspect	Yang	Yin
upper/lower surface	superior (upper)	inferior (lower)
front/rear surfaces	posterior (back)	anterior (front)
position from midline/middle	lateral (away from center)	medial (middle)
near to/far from the surface	superficial (external)	deep (internal)
sides	left	right

Figure 3.6. A Summery Diagram of the Yin and Yang Aspects of the Body

The Seven Emotions			
Chinese Word	English Translation	Organ Association	Qi Manifestation
Xi	joy, happiness, excitement, pleasure	Heart	slows down and relaxes the Qi
Nu	anger, irritation	Liver	causes Qi to rise
Si	meditation, contemplation, pensiveness, worry	Spleen	stagnates the Qi
You	anxiety, sorrow, grief	Lungs	obstructs the Qi
Kong	fear, extreme anxiety	Kidneys	causes Qi to descend
Jing	shock (sudden intense fear), fright	Heart then Kidneys	scatters and deranges the Qi
Bei	grief, affliction, sadness	Lungs	disperses and consumes the Qi

Figure 3.7. The Seven Emotions and Their Effects on the Organs

- The lateral aspect (further from the center) of the body is Yang; the medial portion (middle) is Yin.

The aspects are summarized in Figure 3.6.

As Yin and Yang are in a constant state of change, always waxing and waning, two points of reference alone are not enough to aptly classify the many phases and stages of transformation; for example, day (Yang) can be further split into dawn (waxing Yang), midday (peaking Yang), and late afternoon (waning Yang). To fill this descriptive gap, the Chinese developed the theory of the Five Elements.

THE FIVE ELEMENTS

The Five Elements (Wu Xing), also translated as the Five Phases, are Wood, Fire, Earth, Metal, and Water. These Five Elements paint a clear and natural image of the changing cycles of Yin and Yang (see Chapter 23).

Furthermore, each of the Five Elements can also be divided into Yin and Yang, making a total of ten subdivisions. Wood, for example, can be subdivided into Yin Wood and Yang Wood.

The Chinese use this framework of the Five Elements to understand and categorize many different areas of knowledge, from the movements of the Heavens and the land forms of Earth to the workings of human anatomy, physiology, and psychology. Earlier in this chapter, it was noted that our organs and their associated energy channels are divided into Yin and Yang. In addition, each of the organs is also related to one of the Five Elements. The Liver and Gall Bladder relate to the Wood Element; the Heart and Small Intestine to the Fire Element; the Spleen and Stomach to the Earth Element; the Lungs and Large Intestine to the Metal Element; and the Kidneys and Bladder to the Water Element. The organs help to regulate the functional aspects of the Five Elements within the human body as they interact with each other to promote and maintain life.

The Yin organs, in particular, are said to store the Jing of the Five Elements. They share this Essence with their elementally paired Yang organs to assist with the Yang organs' functions. The Yin organs also store the Five Agents (the Five Virtues), and are more readily disrupted by the Seven Emotions (anger, joy, worry, grief, sadness, fear, and shock) than are the Yang organs.

The emotions are said to be the primal force behind energy transformation; however, each individual will have a separate reaction to specific emotional changes, based on his or her dominant elemental pattern. Five internal organ emotions are associated with the energy of the Five Elements:

1. Anger - Liver - Wood
2. Joy - Heart - Fire
3. Worry - Spleen - Earth
4. Grief and Sorrow - Lungs - Metal
5. Fear - Kidneys - Water

In this way, the energies of the Five Elements shape all aspects of a human being: physical, energetic, mental, emotional and spiritual (Figure 3.7).

CONGENITAL CONSTITUTIONS

Most individuals are born with a dominant element, which will determine the individual's physical, energetic, and psycho-emotional constitution. When in Excess, the body's emotions can create an energetic imbalance, which in turn, can cause a destructive physical pattern within the body. An example of this process is excessive anger leading to hypertension.

The previous chapter on energetic embryology described how, from month four to month eight, the different Five Elemental Jings (Essences) enter the fetus from each of the mother's organs. Depending on the relative strength or weakness of the mother's internal organ energies during her pregnancy, the fetus will inherit a greater or lesser degree of elemental Jing from the mother. If the mother's Liver energy is dominant, then the child will have a tendency to develop a Wood constitution; if the Kidney energy is dominant, then the child develops a Water constitution, and so forth.

In addition, traditional Chinese astrology states that the various Heavenly influences at the time of birth influence the relative Five Elemental strengths and weaknesses in the newborn's constitution. Years, months, days, and hours all occur in separate cycles of five, corresponding to the Five Elements. Thus both the astrological influences at birth as well as the prenatal maternal transmission of Jing, Qi, and Shen, determine each person's congenital constitution.

After birth, the congenital Jing is cultivated and sustained through prayer, meditation, physical exercise, and sleep. In medical Qigong theory, the health of the congenital Jing determines the health and balance of the overall constitution; it determines the level of vitality and resistance to disease, as well as the mental and emotional nature of the individual. The congenital Jing, with its unique balance of the Five Elements, becomes the foundation for an individual's Qi and Shen.

The congenital influence is, however, not absolute. Postnatal factors, such as diet, life-style, environmental factors, and internal belief structures, can also influence the constitution, for better or for worse. Thus, patients with congenital deficiencies can still improve their health by prayer, meditation, medical Qigong, adequate sleep, proper diet and exercise, herbs, medicines, stress management, and other therapeutic modalities.

On the negative side, patients with strong inherited constitutions may develop serious constitutional imbalances through intemperate lifestyles such as: excess stress, overwork, excessive sexual activity, and poor eating habits. Therefore, the Qigong doctor must consider both prenatal (congenital) and postnatal (acquired) constitutional factors to understand and differentiate between the patient's innate constitution and his or her current condition.

CLASSIFICATION OF THE FIVE CONSTITUTIONS

Over the centuries, much has been written in Chinese medical literature about the Five Elemental Constitutions. The following interpretation was developed by Dr. Zhou Qianchuan, a Daoist master from Qi Cheng Shan and reputed by some to be the master of *The Yellow Emperor's Classic of Internal Medicine* (a 2500 year old three-volume text that is still one of the pivotal texts of Chinese medicine).

Dr. Zhou perceived that each of the Five Elemental Constitutions has both a characteristic physical appearance and a psycho-emotional profile. Through observing these aspects, the Qigong doctor determines a patient's Five Elemental Constitution, and from this diagnosis, the doctor discovers much about the balance or imbalance of the patient's physical and mental health.

In Traditional Chinese Medicine, somatic-build type and psyche are closely intertwined. Physical aspects, such as coloring, proportion, dominant tissue (muscle, fat, sinew, etc.), tone, movement, posture and holding patterns, as well as general vitality all express the patient's internal energetic and psycho-emotional matrices. The body type reveals to the trained Qigong doctor not only the patient's emotional history but also his or her innate personality and acquired personality characteristics.

Dr. Zhou subdivided each of the Five Elemental Constitutions into three categories: balanced nature, Yin nature, or Yang nature. The ideal is to have a balanced nature, regardless of one's elemental type. Note that the treatment addresses the mental, emotional, and spiritual balance of the five constitutions. Since the mind is so closely tied with Jing and Qi, it is not enough to simply tell patients how to change their personality to restore balance. The Qigong doctor must work with patients on all levels (physical, energetic, mental, emotional, and spiritual) to help them restore balance. Specific healing methods are discussed at length in later chapters. In general, the Qigong doctor selects treatment principles based on the Five Elements' Creative (Figure 3.8) and Controlling (Figure 3.9) Cycles to help restore balance (see Chapter 23).

For instance, a patient with a Yin Earth nature would tend to have weak or Deficient Spleen energy. Therapeutically, the Qigong doctor would choose one of the three following treatments.

1. Direct tonification of the Earth Element,
2. Tonification of the Fire Element in accordance with the principle, "To nourish the child, strengthen the mother"), or
3. Disperse or reduce the Wood Element (Wood, the "grandmother", may be overcontrolling Earth, the "grandson").



Figure 3.8 The Five Elements' Creative Cycle



Figure 3.9. The Five Elements' Controlling Cycle

In the instance of Yang Earth nature, the patient would tend to have Excess Earth. In this case, the Qigong doctor could:

1. Use a method to reduce the Earth Element directly; or,
2. Strengthen the Wood Element (the weak "grandmother" may be unable to restrain an overly strong "grandson" without help).

THE WOOD CONSTITUTION

WOOD OUTER APPEARANCE

Wood constitution types usually have a tall and slender body with a small head and a long face. They also have small, nicely formed hands and feet, broad shoulders, and a straight, flat back (Figure 3.10). By nature, they enjoy spring and summer but dislike autumn and winter. This preference is due to the vulnerability of the Wood constitution and its susceptibility to pathogenic invasion and disease during these time periods. Their dominant features include strong sinews and green-blue facial color. Their note is "jue."

WOOD PERSONALITY

The Wood personality can be divided into three subdivisions.

1. A Balanced Wood nature predisposes individuals to be confident, strong, independent, and intuitive, with a clear understanding of themselves and their goals. They are patient, able to allow things to develop naturally, and express their personality in a relaxed harmonious way. They are kind when communicating with others, creative, free-flowing in self-expression, and display merciful and unselfish traits when dealing with the needs of others.
2. A Yin Wood nature predisposes individuals to feel externally insecure, and to be always cautious. They have a tendency to worry and have a weak sense of their own abilities and potential. They are unassertive and are unsure of their identities and life purpose. They also have difficulty expressing their egos and have weak boundaries. They are timid, lack confidence, and display considerable doubt.

   Treatment for Yin Wood nature individuals involves establishing a sense of inner strength and security by teaching them self-trust and building self-esteem. These individuals need to strengthen their boundaries to avoid the intrusion and domination of others. They need to trust in their intuition, develop a greater degree of confidence, enhance their personal power, and find a stronger sense of spiritual growth.
3. A Yang Wood nature predisposes individuals to manifest their internal insecurity through acting irritable and impatient. Such individuals are intolerant, rude, stubborn, and selfish, and tend to expand their egos without consideration for others. They are domineering, angry, aggressive, and generally known as



Figure 3.10. The Wood Constitution in Males and Females

overachievers; however, they are easily frustrated and depressed. Their self-esteem is elevated by acquiring higher political (influential) positions or bullying others.

Treatment for Yang Wood nature individuals should focus on cultivating a discipline of inner peace, following the Dao, to harmonize with life. In situations of conflict, they need to learn to relax, slow down, and act out of stillness. They need to surrender to a higher will, relying on their spiritual intuition and inner direction. They also need to learn to respect others.

THE FIRE CONSTITUTION

FIRE OUTER APPEARANCE

Fire constitution types usually have broad paravertebral muscles and well-proportioned shoulders, upper back, and thighs. They have small pointed heads, pointed chins, small hands, and feet, and curly, or no hair, on top of their head (Figure 3.11). By nature, they enjoy spring and summer but dislike autumn and winter. This preference is due to the vulnerability of the Fire constitution and its susceptibility to pathogenic invasion and disease during these time periods. Their dominant features include a strong circulatory system and a red facial color. Their note is "zhi."

FIRE PERSONALITY

The Fire personality can be divided into three subdivisions.

1. A Balanced Fire nature predisposes individuals to be trusting, open-minded, complacent, social, unconcerned about wealth, and fond of beauty. They love themselves and others, and are very expressive of their affection. They are calm, peaceful, happy, lively, spontaneous, funny, and fun to be with.
2. A Yin Fire nature predisposes individuals to be solemn and depressed. They tend to lack interest in life, and have a tendency to become isolated, feeling unloved and unlovable.

Treatment for Yin-Fire nature individuals requires teaching them how to store and conserve their energy, to use moderation in what



Figure 3.11. The Fire Constitution in Males and Females

they do, and to avoid extremes. They also need to engage in activities that create personal enjoyment, to find simple pleasures that awaken their affection, and to learn how to express their feelings, wants, and needs.

3. A Yang Fire nature predisposes individuals to be arrogant, ignorant, and troublesome. They are restless, excitable, and talk excessively. They always exaggerate and are overenthusiastic. They are socially and sexually overactive and seek every opportunity to assert themselves. They are foolish and display careless behavior. They are overconfident, slightly lazy, irresponsible, and less than truthful. They can be manic, get exhausted, then burnout and become suicidal (e.g., bipolar disorder).

   Treatment for Yang-Fire nature individuals requires teaching them to learn how to stop, slow down, and look for their contentment from within. They should balance their feelings of love with contemplation and wisdom, avoid over-enthusiasm, and allow their inner spirit to radiate through in a more sober way.

THE EARTH CONSTITUTION

EARTH OUTER APPEARANCE

Earth constitution types usually have a somewhat large body, large head, large belly, strong thighs, round face, and wide jaw (Figure 3.12). They are categorized as having excessive flesh, with upper and lower limbs mutually well-proportioned. By nature, they enjoy autumn and winter but dislike spring and summer. This preference is due to the vulnerability of the Earth constitution and its susceptibility to pathogenic invasion and disease during these time periods. Their dominant features include strong muscles and yellow facial color. Their note is "gong."

EARTH PERSONALITY

The Earth personality can be divided into three subdivisions.

1. A Balanced Earth nature predisposes individuals to lead quiet, stable, and peaceful lives, unconcerned about fame or wealth. They are always at ease, calm, generous, forgiving, sincere, and unambitious. They usu-



Figure 3.12. The Earth Constitution in Males and Females

ally have open minds and rarely live in fear, or make excessive demands. They have analytical minds and are logical and practical; they use sound reasoning to convince others of their opinions. They are quite adaptable to changing situations, and rarely use coercion to achieve power. They are kind and gentle with an earnest and well-mannered attitude. They are pleasant, sweet, sympathetic and caring, and are able to maintain boundaries.

2. A Yin Earth nature predisposes individuals to worry endlessly, becoming suspicious and self-centered. They think too much, with not enough follow-through action. Because they feel empty inside, they find it difficult to be nurturing to themselves and others.

   Treatment for Yin Earth nature individuals requires teaching them to learn how to let go of their inner feelings of worry and defensiveness. These individuals need to examine their assumptions, connect with their physical bodies, come out of their shells, and begin to live in the real world. They need to replace their negative thought patterns with positive affirmations, and realistically look at their true potential and abilities for powerful actions.

3. A Yang Earth nature predisposes individuals to cling to others; they are co-dependent, pushy, and possessive. Such individuals try to dominate in a passive-aggressive way while limiting the independence of others.

   Treatment for Yang Earth nature individuals consist of teaching them to develop their inner strength to control the fear, insecurity, and feelings of inner emptiness that make them want to hold on to others. They need to create and establish love as a source of security from within themselves. They need not depend on, or build their lives exclusively on, the praise or presence of others. They must learn to become emotionally independent.

THE METAL CONSTITUTION

METAL OUTER APPEARANCE

Metal constitution types usually have a triangular face with broad, square shoulders, a strong voice, and a strong, muscular build (Figure 3.13). By nature, they enjoy autumn and winter but dislike spring and summer. This preference is due to the vulnerability of the Metal constitution and its susceptibility to pathogenic invasion and disease during these time periods. Their dominant features include strong Lungs and white facial color. Their note is "shang."

METAL PERSONALITY

The Metal personality can be divided into three subdivisions.

1. A Balanced Metal nature predisposes individuals to process their grief, letting go of their past emotional baggage. They believe that they cannot be in the present without cleaning up and being released from their past. They are able to gain knowledge and wisdom by gathering and releasing their emotional bonds while learning and growing from each emotional attachment. They participate in life and form new bonds without fear of loss. They are also generous, just, and bright.
2. A Yin Metal nature predisposes individuals to have a difficult time creating lasting bonds because they are fearful of establishing new relationships due to past losses and emotional trauma. They avoid joining in with others and withdraw from active participation. Living in past remorse, they grieve over lost opportunities. They are also haughty and coldhearted. They are jealous, cunning, sneaky, and furtive. They become angry when they do not have things that others possess. Because they are covetous, they only obtain happiness by possessing certain objects.

   Treatment for Yin Metal nature individuals requires teaching them how to strengthen their physical body, as well as the energy of their Heart, Spleen, and Lower Dantian. They also need to strengthen their abilities to form close emotional bonds with people, reduce their fears of rejection and abandonment, and gain the strength and courage to let go of their past hurts. They need to come out from inside of themselves emotionally and experience the warmth and compassion of life.
3. A Yang Metal nature predisposes individuals

to suppress their emotions and hold on to their grief. They are generally considered whiners and complainers, talking to others about their complaints in order to unload their grief. They use new relationships as an emotional bandage to avoid the unprocessed grief of their past relationships. They are also meticulous, independent, and strong-willed.

Treatment for Yang Metal nature individuals requires teaching them how to let go of the need to control and suppress their emotional feelings, and how to genuinely grieve over past wounds. They need to face the truth and be honest about their feelings, instead of selfishly using people and new relationships to cover up their grief. They also need to learn to be sympathetic with the pain and sorrows of others, and put their feelings of grief into perspective.



Figure 3.13. The Metal Constitution in Males and Females

THE WATER CONSTITUTION

WATER OUTER APPEARANCE

Water constitution types usually have a big round face, head and body (Figure 3.14). They have a long upper back, and unbalanced or uneven physical features. They, by nature, enjoy autumn and winter but dislike spring and summer. This preference is due to the vulnerability of the Water constitution and its susceptibility to pathogenic invasion and disease during these time periods. Their dominant features include their digestive system and black or dark facial color. Their note is "yu."

WATER PERSONALITY

The Water personality can be divided into three subdivisions.

1. A Balanced Water nature predisposes individuals to be skilled negotiators, that are not discouraged by difficulty, and do not take foolish risks. They are sympathetic and loyal to their employer and friends. They have a clear perspective and are sensitive and intuitive. They are powerful, tender, and soft. They have a firm will and know their boundaries and limitations. They are known for their inner strength and strong faith in themselves.

2. A Yin Water nature predisposes individuals to lack spiritual, emotional, mental, and physical energy. They give up on life and surrender the control of their own destinies. They lack the determination to achieve their goals, do everything halfheartedly, and become easily discouraged by difficult challenges.

   Treatment for Yin Water nature individuals requires teaching them how to conserve and strengthen their energy by not attempting to do what's beyond their capacity. They should complete their projects, however, once they have started them, and not procrastinate or leave tasks unfinished. They need to find the strength to overcome their fear of failure by learning to take action through the completion of their goals.
3. A Yang Water nature predisposes individuals to be ambitious overachievers and to live under great stress. They lack consideration for others, and can be reckless and foolhardy. They can also be greedy, ruthless, and cold-blooded. Seemingly modest, they are actually insidious and sinister, concealing their true emotions by suppressing their fears. Because they fear loss of control, their safety lies in dominating others. They only perform duties that are self-serving and blame others for their problems.

   Treatment for Yang Water nature individuals requires that they learn how to act from inner stillness and gain strength and courage from their inner true self. They also need to emotionally and physically slow down, and to balance their activities with rest. They need to learn to gain consideration for themselves and others, as well as to open up their heart and begin to love.

COMBINED CONSTITUTIONS

In ancient China, The Yellow Emperor's physician Shao Shi taught that the Five Elemental constitutions consist of Five Elemental forms, which can be further divided into five additional shapes depending on the strength or development of the individual's Jing, Qi, and Blood. After establishing the patient's physique (Wood, Fire, Earth,



Figure 3.14. The Water Constitution in Males and Females

Metal, or Water), the patient is then classified in terms of five separate colors, and differentiated according to the five prenatal (Heavenly) notes. This system recognizes 25 constitutional types.

The Five Elemental Constitutions are therefore, guidelines for the Qigong doctor to evaluate the patient. These guidelines are not fixed, as the doctor is most likely to encounter combinations of two or more of these elements within one person.

When two constitutions combine in an individual, the combination may be congenital or acquired. The Qigong doctor must evaluate the patient, differentiating between his or her congenital and acquired tissue formations.

A woman who has large hips (Water) and small chest and shoulders (Wood), for example, probably inherited this structure from her parents. This woman's physical structure and personality would then be considered a combination of both Water and Wood (depending on which internal organ characteristic dominates).

A female patient who swims, on the other hand, may be congenitally Wood but may have developed a dominant Metal upper physique through years of physical training. If, through intense physical activity, someone acquires a Metal physique, he or she may also acquire a Metal personality, depending again on his or her psychological format, which is rooted within the internal organs.

The external physical structure serves as a visual guide to the interaction and balance of the internal organs.

PERSONALITY CONSTITUTIONS OF THE EIGHT EXTRAORDINARY VESSELS

Another system of identifying personality traits is practised by observing the four personality constitutions of the patient's Eight Extraordinary Vessels.

Through observation and inspection of the patient's personality and overall energetic and emotional demeanor, the Qigong doctor can further determine which organ and organ system, is Deficient or has an Excess condition and set up a treatment plan.

To begin, the Qigong doctor will first observe the patient's dominant Yin or Yang emotional characteristics and determine which of the Eight Extraordinary Vessels are governing his or her present state of feelings. These personality traits may appear in different combinations, or oscillate from one type of characteristic to another, due to the crossover of acquired and congenital organ energy. This crossover can change with the patient's age (maturation) or situation (environment).

THE PATHOLOGICAL PERSONALITY TYPE OF THE GOVERNING AND YANG HEEL VESSELS

The Governing and Yang Heel Extraordinary Vessels are located on the back and lateral sides of the body and affect the Bladder, Stomach, and Gall Bladder Channels. To "open" and increase the flow of energy within these channels, the Qigong doctor stimulates the patient's SI-3 and Bl-62 points simultaneously (see Chapter 8).

The pathological personality types of the Governing and Yang Heel Vessels are divided into Yin and Yang emotional characteristics. These characteristics are as follows.

1. Patients with Deficient Qi in the Governing and Yang Heel Vessels tend to be weak-willed and spineless. They tend to be overly submissive, and easily give up their personal power. They lack determination, courage, clarity, and inner strength, and have no control over their lives. They participate as little as possible in life for fear of failure.
2. Patients with Excess Qi in the Governing and Yang Heel Vessels tend to be tense, overpressured, stiff, rigid, inflexible, stubborn, and awkward. They are narrow-minded and overcontrolling. Fearful of letting go, they overcompensate and attempt to restrict reality.

THE PATHOLOGICAL PERSONALITY TYPE OF THE CONCEPTION AND YIN HEEL VESSELS

The Conception and Yin Heel Extraordinary Vessels are located on the front and inside of the body. They affect the Lung and Kidney Channels, which in turn affect the Kidneys, Lungs, and Heart organs. To open these channels, the Qigong doctor stimulates the patient's Lu-7 and Kd-6 points simultaneously. These character diagnoses are as follows.

1. Patients with Deficient Qi in the Conception and Yin Heel Vessels tend to be weak and depressed. They live in the past, lack interest in life, have no ambition, and also lack interest in sex. It is hard for them to form new relationships because they fear forming emotional bonds due to past losses, failures, and emotional traumas. They constantly daydream and live in their own world of past memories.
2. Patients with Excess Qi in the in the Conception and Yin Heel Vessels tend to participate in life, but hold on to, and suppress, their grief. They fail to let go of emotional attachments and fear being alone. The female patients usually develop Qi stagnations resulting in breast cysts, tumors, and cancer, as well as uterine fibroids and cancer.

THE PATHOLOGICAL PERSONALITY TYPE OF THE BELT AND YANG LINKING VESSELS

The Belt and Yang Linking Extraordinary Vessels are located around the waist and on the outside of the body. They affect the Gall Bladder and Triple Burner Channels, which in turn, affect the Kidneys, Liver, and Gall Bladder organs. To open these channels, the Qigong doctor stimulates the patient's GB-41 and TB-5 points simultaneously. These character diagnoses are as follows.

1. Patients with Deficient Qi in the Belt and Yang Linking Vessels are considered weak, indecisive, and unproductive. They fear criticism and are touchy, snappy, irritable, and hypersensitive. They have low self-esteem and also lack interest in sex.
2. Patients with Excess Qi in the in the Belt and Yang Linking Vessels are aggressive, angry, resentful, bitter, and vindictive. They are also opinionated, inflexible, intolerant, domineering, selfish, and frustrated, with a sex life based on anger or rage.

THE PATHOLOGICAL PERSONALITY TYPE OF THE THRUSTING AND YIN LINKING VESSELS

The Thrusting and Yin Linking Extraordinary Vessels are located within the center of the body (internally) and on the medial and anterior aspect of the body (externally). They affect the Kidney and Stomach Channels, which in turn, affect the Kidneys, Spleen, and Heart organs. To open these channels, the Qigong doctor stimulates the patient's Sp-4 and Pc-6 points simultaneously. These character diagnoses are as follows.

1. Patients with Deficient Thrusting and Yin Linking Vessels are physically and emotionally weak. They quickly become exhausted and depressed. They easily have their feelings hurt and take a long time to recover from emotional upsets. Their internal world of emotional existence is made up of fear, anxiety, worry, and tension. They do not connect well with the outside world or gain much pleasure from life or relationships.
2. Patients with an Excess in the Thrusting and Yin Linking Vessels tend to participate in life, but have difficulty expressing their affections and communicating their needs in relationships. They are inclined to have stagnant Qi and Blood in their chests, epigastrium, or uterus areas due to fear, anxiety, worry, and sorrow. In their personal relationships, they fear loss of control and cannot make a commitment or a deep emotional connection with others. They also fear surrendering and letting go in their love and sexual relationships.

THE YAO IMAGE AND PHYSICAL ANATOMY

Sometimes because of surgery, congenital deformity, or traumas, it is not possible, nor is it recommended, to directly treat certain areas of the patient's body. The Qigong doctor must then choose an indirect method of treatment to ensure better results. One such method available to the doctor utilizes the understanding of the Yao image and the patient's physical anatomy. In order to better comprehend the complexity of this diagnostic and treatment modality, the Qigong doctor must first understand the energetic origin of the Yao images.

All matter is composed of different proportions of Yin and Yang energy. Within the Void (infinite space or Wuji) both Yin and Yang energy gather or disperse to balance the forces of nature. This interaction causes the Yin and Yang energies



Figure 3.15. This diagram shows a hexagram, composed of an upper and lower trigram. In this particular example, the upper trigram is all Yin lines (symbolized by broken lines), the lower all Yang (symbolized by solid lines).

to develop and transform themselves into four phases of energetic powers or stages: Great Yin, Small Yin, Great Yang, and Small Yang. These four phases can be explained as follows.

1. Great Yin (Tai Yin), is affiliated with midnight and the new-moon phase. Modern physicists associate the Great Yin with a weak nuclear force.
2. Small Yin (Shao Yin), is affiliated with the sunset and the waning-moon phase. Modern physicists associate the Lesser Yin with a heavy force, and gravity.
3. Great Yang (Tai Yang), is affiliated with high noon and the full-moon phase. Modern physicists associate the Strong Yang with a strong nuclear force.
4. Small Yang (Shao Yang), is affiliated with the sunrise and the waxing-moon phase. Modern physicists associate the Lesser Yang with a light force and electromagnetism.

These four solar and lunar energetic phases transform themselves into the energies of the eight foundational trigrams. These trigrams further combine to form sixty-four hexagrams, and manifest as the ancient binary system known as the Yi Jing (I Ching). The formation and pattern of these energetic powers or stages vary according to the composition of Yin and Yang, and can be expressed through the energetic symbols of the Yao.

A Yao is a line that represents either Yin or Yang energy. The lines fall into two categories:

- The negative Yao is symbolized by broken lines (Yin energy).
- The positive Yao is symbolized by solid lines (Yang energy).

When these lines are stacked in combinations of three, they form what are known as trigrams (a group of three Yao lines). When pairs of trigrams are joined, hexagrams (six lines) are formed. The lines are arranged from bottom to top, with the first Yao being on the bottom (Figure 3.15).

The Yao trigrams and their relationship to the body's physical and energetic structure can be utilized by the Qigong doctor for diagnosis and treatment. The doctor applies the Yao image as a template and arranges its pattern alongside the physical form of the patient's body. This arrangement of Yao images is designed by the doctor to assist him or her in recognizing the physical and energetic imbalances within the patient's body. This type of physical Yao image diagnosis has been used in China for centuries.

Knowing that each different region of the human body corresponds to one of the six Yaos in the hexagram, as well as a different aspect of Qi, the ancient masters explained the energetic Yao and physical body interaction as follows.

1. The two lowest Yaos align with the feet and legs and correspond to the body's interaction with the Earth's energy.
    a. The 1st Yao extends from the patient's feet, ankles, and shins, to the knees.
    b. The 2nd Yao extends from the knees to the upper thighs.
2. The middle two Yaos align with the lower and upper abdominal regions, and correspond to the body's interaction with human energy, or "Man's energy" (emotional responses).
    a. The 3rd Yao extends from the perineum to the navel.
    b. The 4th Yao extends from the navel to the xiphoid process in the diaphragm.
3. The upper two Yaos align with the upper chest, neck and head, and correspond to the body's interaction with Heaven's energy.
    a. The 5th Yao extends from the xiphoid process of the diaphragm to the top of the manubrium, at the base of the throat.



- The top or 6th Yao is from the neck to the top of the head. (Heaven)
- The 5th Yao is from the diaphragm to the neck. (Heaven)
- The 4th Yao is from the navel to the diaphragm. (Man)
- The 3rd Yao is the lower perineum to the navel. (Man)
- The 2nd Yao is from the knee to the top of the thigh. (Earth)
- The bottom or 1st Yao is from the foot to the knee. (Earth)
- The Categorization of the arms are as follows: From the fingers to the elbow represents the Bottom or 1st Yao; From the elbows to the base of the shoulder represents the 2nd Yao; From the base to the top of the shoulder represents the 3nd Yao.

Figure 3.16. Yao Image and the Human Body

b. The 6th Yao extends from the manubrium, at the base of the throat, to the top of the head.

The doctor further divides the patient's body into six upper and lower Yaos, to determine the dominant energetic and emotional patterns (where the patient's Qi is gathering, collecting, and stagnating). Through observation and study, the Qigong doctor is able to determine the energetic association the patient has with the natural environment. This diagnosis is achieved by observing the body's relationship to the three energetic Yao divisions of Heaven, Earth, and Man (Figure 3.16). When observing the body, for example, if the upper Yao is out of harmony with the patient's middle and lower Yaos, the patient's energetic balance may be compromised, and he or she may experience a spiritual disconnection with his or her body. This can result in either a Yang condition (heaviness, restlessness) due to an Excess spiritual "Heaven" state, or a Yin condition (tired, dizziness) due to a Deficient spiritual "Heaven" state.

In addition to diagnosing the hexagram for the body's Yin and Yang relationship to Heaven, Earth, and Man, the ancient Chinese Qigong masters also studied two other hexagrams for clinical evaluation. These hexagrams were known as the Upper and Lower Hexagrams.

UPPER AND LOWER HEXAGRAMS

In the Ming Dynasty (1368-1644), Tang Rongchuan stated in his book *Detailed Explanations of Application of the Book of Changes to Medicine*, "In the clinical environment, the body may be divided into two different sets of hexagram constructions [the upper and the lower hexagram partition] for the purpose of making a diagnosis, detecting Qi, and for performing Qigong therapeutic treatments." This relationship of Yao positioning is suitable to both the channel system and the nervous system.

Physical disorders located within these hexagrams are generally expressed as symptoms manifesting in the extremities. If stagnant Qi or other abnormal conditions occur in any particular part of the body, an imbalance of both Internal and External Qi may be detected in either that specific area of the body or its corresponding area.

The ancient Qigong masters used the body's hexagrams to explain the etiology, pathology, clinical manifestations, and treatment principles of disease.

The body's upper torso, arms, neck, and head are divided into what is known as the upper hexagram partitions, while the body's lower limbs and torso are divided into the lower hexagram partitions. The six Yao of the upper and lower hexagram partitions interlock at the chest and abdomen. By using these sets of hexagrams, the Qigong doctor has a template or guiding pattern with which to understand the patient's body.

The Upper Hexagram Construction

The Upper Hexagrams range from the base of the lower perineum to the top of the patient's head. These six Yaos are organized as follows.

1. The 1st or bottom Yao encompasses the pubic symphysis to the navel. Reproductive, digestive, and urinary tract diseases are ascribed to this area.
2. The 2nd Yao encompasses the navel to the xiphoid process. Malfunctions in digestion, elimination and the transportation of nutrients are assigned to this area, as well as diseases of the Kidneys, adrenal glands, Liver, Spleen and pancreas.
3. The 3rd Yao encompasses the xiphoid process to the supraclavicular notches. Respiratory and circulatory diseases are ascribed to this area.
4. The 4th Yao encompasses the supraclavicular notch to the tip of the nose. Teeth, jaw, and thyroid diseases are ascribed to this area.
5. The 5th Yao encompasses the tip of the nose to the eyebrow. Sinus problems and headaches, as well as ear, nose, and eye diseases are manifest in this area.
6. The 6th or top Yao encompasses the eyebrows to the top of the head. Several types of headaches, brain tumors, and upper cranial dysfunctions are ascribed to this area.

The Lower Hexagram Construction

The Lower Hexagrams range from the bottom of the patient's feet to the base of the patient's throat. These six Yaos are organized as follows:

1. The 1st or bottom Yao encompasses the bottom of each foot to the ankle. Foot, toe and ankle dysfunctions are ascribed to this area.
2. The 2nd Yao encompasses the ankles to the knees. Shinsplints and calf and ankle dysfunctions are ascribed to this area.
3. The 3rd Yao encompasses the knees to the pubic symphysis. Thigh, knee, and quadriceps dysfunctions are ascribed to this area.
4. The 4th Yao encompasses the pubic symphysis to the navel. Reproductive, digestive, and urinary tract diseases are ascribed to this area.
5. The 5th Yao encompasses the navel to the xiphoid process. Digestion, elimination, and the transportation of nutrients, as well as diseases of the Kidneys, adrenal glands, Liver, Spleen and pancreas are ascribed to this area.
6. The 6th or top Yao encompasses the xiphoid process to the supraclavicular notches at the base of the throat. Respiratory and circulatory diseases are ascribed to this area.



The diagram at left depicts the correspondence of the yaos of the body to the yaos of the hands and feet.

6 The second joint of the toes or fingers pertains to the top Yao and the energy of Heaven.

5 The first joint of the toes or fingers pertains to the 5th Yao and the energy of Heaven.

4 The area below the first joint of the toes or fingers pertains to the 4th Yao and the energy of Man.

3 The ball of the foot or upper palm pertains to the 3rd Yao and the energy of Man.

2 The instep on the midpalm with the thumb pertains to the 2nd Yao and the energy of Earth.

1 The heel or lower palm pertains to the bottom Yao and the energy of Earth.

Figure 3.17. The Therapeutic Use of the Yaos and the Upper and Lower Hexagrams

THERAPEUTIC USE OF THE YAOS

The entire body can be treated by focusing on one small area. When Excess, Deficient, or stagnant Qi occurs in one part of the body, the imbalance of Internal and External Qi is detectable in that area or its corresponding region on one of the body's extremities. This ancient Chinese modality of treatment is popularly called reflexology in the West.

The Yao images can be superimposed onto the patient's body, and the patient diagnosed according to the energetic symptoms expressed through either the patient's extremities (the hands, forearms and arms; or the feet, shins, and thighs), or the six divisions located on the patient's torso and head. A Yao hexagram can additionally be visualized on specific locations of the patient's body such as the face, nose, ears, hand or foot for diagnosis. The base of the palm's heel, for example, corresponds to the lower abdominal area and reproductive organs, which relate to the 1st, or lower, Yao in the hexagram of the hands. These six Yao areas of the hand provide a basis for diagnosis, for treatment of certain diseases, and even for perception and prediction of certain future diseases (Figure 3.17).

As an example of how the Qigong doctor can use the six Yaos of the body for emitting Qi therapy, consider the following situation: An elderly patient with a problem in his prostate area visits the Qigong doctor. The prostate is located in the lower abdominal area, which is located in the 1st Yao of the upper hexagram. Since the six Yao positions can be transferred to the hands, feet, etc., the doctor knows that this particular Yao is congruent to the 1st Yao of the foot. Therefore, as an energetic entry point into the patient's prostate area, the doctor may focus his or her attention on a specific area on the foot.

Dividing the foot into six Yaos, the doctor knows that the 1st Yao of the foot is the heel area. In order to treat the prostate gland, the doctor will



6 The fruit or flower of the herb pertains to the top Yao and the energy of Heaven.

5 The leaf of the herb pertains to the 5th Yao and the energy of Heaven.

4 The branch of the herb pertains to the 4th Yao and the energy of Man.

3 The upper stem of the herb pertains to the 3rd Yao and the energy of Man.

2 The stalk of the herb pertains to the 2nd Yao and the energy of Earth.

1 The root of the herb pertains to the bottom Yao and the energy of Earth.

Figure 3.18. The Yao Image Applied to Plants

focus his or her treatment on the patient's heel and ankle area. Alternatively, the doctor could also have chosen the 1st Yao area of the hand, which is considered the 1st Yao position of the arm. The 1st Yao of the hand corresponds to the prostate and urogenital area.

HERBS AND THE YAOS

Affirming the ancient Chinese belief that the energy of Heaven, Earth, and Man combine as "one," and exist in the same world of energetic dynamics, herbs are also structured and prescribed in accordance with the six Yao hexagram concept. With plants, the following correspondences apply (Figure 3.18):

1. The roots correspond to the bottom or 1st Yao.
2. The stalk corresponds to the 2nd Yao.
3. The upper stem corresponds to the 3rd Yao.
4. The branches correspond to the 4th Yao.
5. The leaves correspond to the 5th Yao.
6. The flowers and fruit of the plant correspond to the top or 6th Yao.

When plants are utilized as a medicine, the part of the plant corresponding to the number and position of the Yao may manifest its energetic properties, affecting the ascending, descending, floating, or sinking action of the patient's Qi. The achyranthes root (Niu Xi), for example, corresponds to the bottom Yao, and leads healing Qi downward, to heal the patient's knees and joints; whereas the chrysanthemum flower (Ju Hua) corresponds to the top Yao, and leads healing Qi up into the patient's head and eyes.

IDENTIFYING INTROVERTED AND EXTROVERTED STRUCTURES

Qi flows through the matrix of the connective tissue and adapts to the postural and structural demands of the body by changing the density and direction of the body's connective tissues and inner fasciae. A postural habit will create an imprint or tissue memory in the supporting connective tissue, as well as an energetic memory in the supporting field of Qi. These imprints result in introverted as well as extroverted postural structures.

Each introverted (Yin) and extroverted (Yang) postural structure has a predictable impact on the


Head held off-center
6th yao
Shoulders sunken and forward
5th yao
Wide back
Narrow chest
4th yao
Pelvis tilted back
3rd yao
Genitals retracted
2nd yao
Thighs bowed
bottom yao

Figure 3.19. The Introverted Structure


6th yao
Head held level
Shoulders Extended back
5th yao
Narrow back
Wide chest
4th yao
Pelvis tilted forward
3rd yao
Genitals extended
2nd yao
Thighs turned inward
bottom yao

Figure 3.20. The Extroverted Structure

myofascial webbing, as well as a natural emotional response. Emotions respond to changes in breathing patterns and vice versa. Both the prevalent breathing pattern and the patient's general mood affect the body's posture and eventually the body's structure. All chronic stress creates postural imprinting or tissue memory, and a corresponding energetic memory in the supporting field of Qi.

INTROVERTED STRUCTURE

When observing the introverted type of structure, the doctor will notice that the back (Yang) area of the patient is expanded, and the muscle structure is usually well-developed. The front of the body (Yin), especially around the chest and Heart area, is retracted, resulting in a narrow chest. The patient's head is generally held off-center, shoulders are sunken and forward, and the pelvis is tilted back, with the genitals retracted (anterior tilt). This condition is commonly referred to as "extended Yang" and "retracted Yin" of the upper torso (Figure 3.19).

EXTROVERTED STRUCTURE

When observing the extroverted type of structure, the doctor will notice that the back (Yang) area of the patient is retracted, while the front of the body (Yin) is expanded and overly exposed. The head is usually held vertically, the shoulders are extended back (military posture), the chest is wide, and the pelvis is tilted forward, with genitals extended (posterior tilt). This condition is commonly referred to as "extended Yin" and "retracted Yang" of the upper back (Figure 3.20).

COMBINED STRUCTURAL FORMATIONS

As with the Five Elemental Constitutions, the introverted and extroverted structures are guidelines for the Qigong doctor to evaluate the patient. These guidelines are not fixed, as the doctor is most likely to encounter combinations of both introverted and extroverted structures within one person.

When two structures combine in an individual, the combination may be due to a congenital or acquired formation. The Qigong doctor must evaluate and assess the patient, differentiating between his or her congenital and acquired tissue formations.

CONGENITAL AND ACQUIRED CELLULAR PATTERNS

The Qigong doctor evaluates the physical condition according to the congenital or acquired patterns manifested within the patient's tissues. The doctor may ask questions to determine if the condition was acquired through exposure to environmental pathogens, diet, trauma, occupation, or inherited. This information aids the Qigong doctor in understanding and assisting the patient in reprogramming any congenital or acquired cellular patterns, as well as internal disease functions.

1. Congenital Cellular Patterns and disease predispositions are locked within the patient's congenital Jing and can be released like a biological time bomb. This is a similar concept to the Western medical concept of genetic congenital disease. The goal of the Qigong doctor is to alter (if possible) the Toxic Qi patterns and help the patient's body recognize that the formation of the disease is a mistake. In order to reprogram these patterns, the Qigong doctor often assists the patient in using guided meditations that employ vivid imagination, colorful visualizations, and positive affirmations. These images are used to encapsulate the disease and return it to the divine light. While in the presence of the divine light, the Toxic Qi (Xie Qi) will be energetically transformed and recycled back to the patient as healing energy. Patients with a direct family history of cancer, for example, can benefit from this type of medical Qigong imagery.
2. Acquired Cellular Patterns and disease functions arise from either external exposure to pathogens, or the suppression of extreme emotions. The goal of the Qigong doctor is to first assist the patient in discovering the origin of the disease. The next step is to teach the patient to alter the toxic patterns and help the patient's body recognize that the development of the disease is a mistake. In order to reprogram these patterns, the Qigong doctor will assist the patient in learning meditations that employ healing mental imagery, colorful visualizations, and positive affirmation. The patient must encapsulate the disease and return it to the divine light, to be energetically transformed and recycled. A patient who has been experiencing severe headaches, for example, could benefit from this kind of treatment given that most headaches are stress related.

SUMMARY

Through the observation of the patient's physical and structural development, a clear understanding can be obtained as to the strength and weakness of the patient's internal organs and immune system.

The four patterns of physical development and structural formation (The Five Elemental Constitutions, The Yao Hexagram Formations, The Yin or Yang Structures, and The Congenital and Acquired Cellular Patterns) are determined as follows.

1. The doctor first begins to diagnose the patient's physical body according to the Five Elemental Constitutions and the dominant element. This helps the doctor to understand the dominant condition of the patient's internal organs.
2. The doctor further divides the patient's body into six upper and lower Yaos, to determine the dominant energetic and emotional patterns (where the patient's Qi is gathering, collecting, and stagnating).
3. Next, the doctor evaluates the patient's external structure according to his or her body's Yin and Yang characteristics, to understand whether the patient has a dominant introverted or extroverted physique.
4. Finally, the Qigong doctor determines whether the patient's condition is congenital, acquired, or a combination of both. This information helps the doctor to understand the innate cellular patterns that dominate the patient's physique.

CHAPTER 4

THE FIVE ENERGIES OF THE HUMAN BODY

The study of various forms of energy and their transformations from one form to another have led to one of the greatest generalizations in physics -- the Law of Conservation of Energy, which states, "Energy cannot be created or destroyed. It may be transformed from one form into another, but the total amount of energy never changes."

Physics defines four types of energy: mechanical, electromagnetic, chemical, and thermal. All four types of energy are related to and convert from one another. Electricity, for example, can be converted into sound, light, mechanical energy and into heat. Sound, light, mechanical energy and heat can all be reconverted into electricity.

Western Science is still for the most part, founded on the principles of Newtonion Physics, that views energy as an impersonal and inanimate force. The Traditional Chinese view of energy is much more akin to the theories of Quantum Physics. Both Chinese energetic theories and Quantum Physics hypothesize that energy cannot be studied without taking into account the mind's influence over it. Furthermore, energetic behavior cannot be studied independently of matter.

From a medical Qigong perspective, the entire human body is suffused with energy, which converts within the human organism. Light energy, for example, is absorbed, stored and converted into the various energies of the body, the same way that plants convert absorbed and stored light into chemical energy.

The human body possesses five energies which resonate within the very core of one's being. Sound, light, magnetic fields, heat, and electricity envelop and permeate our very existence; these energies sustain, govern, control, and determine our psychology as well as our physiology. In Medical Qigong therapy, these energies are considered the spiritual reality that governs the physical reality. These energies are observed in both diagnosis and treatment of illness. Research in China confirms the fact that the body emits sound, light, magnetic energy, electricity, and heat.

SOUND ENERGY RESONANCES

When the body experiences any type of sound, the cell tissues respond to the tone frequency and have either a negative or positive automatic response. The human body both receives and generates sound energy. These subtle sounds resonate from three distinct physical energetic actions. The following subtle sounds are natural tones that resonate as a result of three physical actions.

1. Breathing creates respiratory sound resonances that follow the breath in and out of the lungs mouth, and nose.

2. Muscle movements create somatic and visceral sound resonances that include the clicking sound of the joints, beating of the Heart, gurgling of the Stomach and intestines, etc.

3. Qi activities can produce energetic sound resonances (i.e., when Liver Yang, Liver Fire, or Liver Wind rise, a high-pitched tone is heard in the ears. When the Kidney Yin is Deficient, this sound is like rushing wind, etc.).

SOUND THERAPY THROUGH EMITTED QI

As sound waves vibrate through the body, crystalline structures within the tissues transform the vibration into pulsed currents. These currents are then conducted to the various corresponding organs and glands, depending on the frequency and amplitude of the incoming wave signal. This tissue transformation (due to wave vibrations) automatically changes the function and flow of energy in the body. Thus sound vibrations have a profound effect on both human psychology and physiology. Sound or tone resonances, have been used for centuries as an effective healing tool and are currently used as an adjunct to modern Qigong Medicine.

For centuries in China, patients have used healing sound therapy to resonate certain parts of the body, stimulating the flow of Blood and Qi to and from specific internal organs to cure disease. These healing sounds specifically relate to the Five Agents and the Five Elemental aspects of the patient's internal organs (see Chapter 2). According to the Five Elements' Cycle, each of the Five Elements has a note:

- Gong - C = Earth
- Shang - D = Metal
- Jue - E = Wood
- Zhi - G = Fire
- Yu - A = Water

The Qigong doctor can project resonant sound vibrations by first focusing on all three Dantians at the center of the Taiji Pole. This focused concentration is used first to vibrate the doctor's specific internal organs and then to treat the patient. The Qigong doctor can use vibrating sound therapy by:

1. Audibly speaking the healing sounds to fill the Qigong doctor's energetic field with healing sound vibration. This energetic field of sound is then projected onto his or her patient. Audible sound resonation is considered a Jing to Qi level energy projection, and is generally used when the patient is armored and not energy sensitive.
2. Inaudibly speaking the healing sounds and projecting these mental vibrations into the patient. In this case, the Qigong doctor will begin by internally focusing his or her mind on the healing sound. As this internal sound fills the Qigong doctor's energetic field, it is then emitted into the patient's body. To increase the intensity of energy sound projection, the doctor needs only to increase the mind's intention and the pressure of his or her exhalation. Inaudible sound resonation is considered a Qi to Shen level energy projection, and is generally used when the patient is energy sensitive.
3. Both the doctor and patient simultaneously resonate the sound to enhance the synchronization of both their energy fields. As the Qigong doctor resonates his or her own internal organs, both the doctor and patient can modulate the sound and energy patterns as needed.

THREE MODALITIES OF SOUND THERAPY

The resonant sounds produced by Qigong doctors are effective because the patients' energetic matrix is sensitive to the sound resonances. The modulated, yet unpredictable, nature of sound pulsation affects the vibrational structures which shape and maintain the patient's physical structure. Once the patient's vibrational structures have been disturbed, their body must immediately begin its reconstructive process, thereby creating new energetic patterns to restructure and heal the tissues.

There are three modalities used for sound therapy:

1. Characteristic Sound Therapy refers to the sound from musical instruments (flute, guitar, piano, drum, etc.) and their effect on the subconscious mind. This type of musical energy creates an emotional, physical, and spiritual release of energy within the listener.
2. Extraordinary Sound Therapy refers to the vocal resonances used in silent chanting, prayer and singing. Such techniques include the Daoist six-word healing sound method, Zhuang Zi's breath listening method, Lao Zi's sound-voice method, etc. This type of therapy uses the patients' energy to produce the sound and inner vision to direct the vibration within the body. It is also practised in conjunction with breathing techniques that are guided by the Yuan Shen (the intuitive consciousness of the spirit). All of these techniques are combined to achieve physiological and psychological healing.
3. Infrasonic Sound Therapy refers to the low frequency sound waves emitted from the hands of Qigong doctors. These chaotic, low frequency sound waves, inaudible to the human ears, are naturally produced by the hands

of experienced Qigong doctors when emitting Qi. This infrasonic sound resonance affects the central nervous system, changing the body's neurophysiological functions. Extensive research performed by Richard H. Lee of China Healthways Institute in Los Angeles, California, as well as research performed by the Beijing College of Traditional Chinese Medicine, and the Department of Natural Science in Beijing China, confirms that all humans have a very high degree of acoustic activity in the subsonic range below 20 Hertz (infrasonic). This subsonic activity is similar to the alpha rhythm of an EEG (see Appendix #2).

Qigong doctors may combine the characteristic, extraordinary, and infrasonic sound therapies into one treatment modality to facilitate a deeper and more thorough transformation within their patients. The choice of sound prescriptions vary according to each patient's cultural upbringing, religious beliefs, emotional temperament, and comprehension of energetic healing modalities.

Sound therapy can be prescribed to relieve a patient's feelings of uneasiness or extreme depression. Music, for example, has always been acknowledged as a powerful medium for emotional enhancement. Sounds and tones stimulate the cerebral centers creating a wide range of results from enhancement of memory retention, to facilitating certain emotions, and creative inspirations.

Music therapy specifically created for the harmonizing the Five Elements within the Yin and Yang organs is also used in conjunction with Feng Shui training to regulate any imbalances of the body and mind stemming from the changes of seasons. During autumn, for example, when dryness is prevalent and there is a transition from warm to cool, music can help to stabilize the body's response to these external conditions.

WESTERN SOUND THERAPY

Sound therapy is actively being used in Western medicine. The following are examples of current clinical modalities:

- music therapy for postoperative healing,
- ultrasound therapy for sore muscles and back injuries, and
- shock-wave lithotripsy therapy for kidney stones and calcified gallstones.

LIGHT ENERGY

All matter produces, radiates, transports, or transmits light, and therefore has properties of color vibration. Matter and light are fundamentally inseparable. Matter can be considered a condensation of photons. Its transformation can be viewed as a result of light interacting with atoms and molecules. All life on Earth, whether plant, animal, or human, is dependent upon light and its miraculous qualities for existence.

All living cells emit units of light called "biophotons." Biophoton emissions radiate from the internal organs, as well as the body's surface tissues, to create the body's auric field.

This interaction of light on the body's tissues and within the body's internal organs has a profound healing effect, especially when activated by the Qi emission from a Qigong doctor. When muscles or nerves are activated through medical Qigong therapy and / or exercises, the intensity of the biophoton emission increases. Studies performed on the healing potential of light and color therapies demonstrate that it is clinically effective. Like sound resonances, light therapy is also being researched further as an adjunct to modern clinical medicine.

The body both absorbs and projects light energy. The divine light that enters at the time of conception continues to reside in our Taiji Pole throughout our lives. This light responds and reacts to the doctor's emitted therapeutic light energy. Emitted light and color resonance are absorbed into the patient's body, causing the energies of Heaven and Earth to fuse inside the tissues; this facilitates the healing process.

In Traditional Chinese Medicine, the early diagrams illustrating the body's internal organs, channels, routes of Body Fluids, and arteries were called Charts of the Hall of Light. These detailed maps of Qi and Blood flow illustrated the energetic organs, as well as the body's Jing and Shen (which are rooted in the Blood). The Shen flows inside of the body, transforming into light and radiating from inside of the tissues outward. The



Figure 4.1. Light resonates within the body's Taiji Pole. From the body's Yang Governing Vessel flows a sea of electropositive energy. From the body's Yin Conception Vessel flows a sea of electronegative energy.

light radiating from the physical body spontaneously interacts with the mental, emotional, and spiritual light energy released from other beings.

Light energy can also be accumulated in the storage chambers of the Three Dantians. The Upper Dantian, is called the "peak of Yang energy," and is considered electropositive; it is the doorway to the chamber of Heavenly or divine light. The Lower Dantian, is called the "peak of Yin energy," and is considered electronegative, and the direct root to the Earth.

In time, with Qigong training, the postnatal Heat circulating up the Governing (Yang) and down the Conception (Yin) Vessels can awaken the Prenatal Qi stored in the brain, causing it to unite with the body's nervous system. This is considered a full integration of Yin and Yang energy and manifests as a shimmering white light glowing in the center of the Upper Dantian.

White light is stored in and released from the Upper Dantian, where the spiritual energy is stored. Once white light energy manifests, it should be drawn down the Taiji Pole into the center of the Lower Dantian. By using inner vision to focus the eyes on the center core of the body, the Qigong doctor can concentrate on the white light energy vibration and fuse this energy into one column of light, stemming from the Upper to the Lower Dantian. When the Microcosmic Orbit is completed (i.e., when the Governing and Conception Vessels are energetically fused), the first center column of light can be accessed via the body's five Center Thrusting Channels into the Taiji pole. This column of light runs through the center of the body, connecting all Three Dantians together (Figure 4.1). Accumulated Qi is stored as a golden glowing ball in the Lower Dantian.

COLOR VIBRATIONAL PROJECTIONS

Qigong doctors project light of different colors by first drawing the divine light energy into their Taiji Pole, then focusing on the light energy and releasing it either through the arms and out the hands into the patients, or through a visualization of divine light traveling from the Yin Tang (Third Eye) area into the patients.

When Qigong doctors connect with the divine healing white light energy, they absorb massive quantities of this energy into their Taiji Pole. This white light energy prisms into six color projections of light and energy vibration. As the white light energy transforms into multicolored beams of light, the colors can be either absorbed to strengthen the internal organs, or projected out for Qi emission.

The Qigong doctors use inner vision techniques to connect with the correct color for energy projection. One such technique used by doctors allows the color to naturally develop by mentally focusing both eyes to the back of the head. The color that is observed in the back of the mind is projected into their patients' body. This visualization technique is only performed after connecting with the patients' energetic field.

LIGHT THERAPY THROUGH EMITTED QI

The human body produces light which is visible to both clairvoyants and Qigong doctors (Figure 4.2). In China, doctors of TCM have discovered that light therapy is effective in treating certain diseases because of the light field's ability to penetrate the tissues, and interact with the patients' energetic fields.

Extending the image of the color is an important part of the Qigong doctor's ability to treat


Frequency (in hertz)
Type of Radiation
Examples of Sources
Wavelength (in meters)
Ionizing
Nonionizing
10^{23}
10^{22}
10^{21}
10^{20}
10^{19}
10^{18}
10^{17}
10^{16}
10^{15}
10^{14}
10^{13}
10^{12}
10^{11}
10^{10}
10^{9} (GHz)
10^{8}
10^{7}
10^{6} (MHz)
10^{5}
10^{4}
10^{3} (KHz)
10^{2}
10^{1} (Hz)
Heavenly rays
Sun
Gamma rays
X-rays
Ultraviolet radiation
Visible light
Infrared radiation
Microwaves
EHF
SHF
UHF
VHF
HF
MF
LF
Radio waves
Short wave
Med. wave
Long wave
Extremely low frequency (ELF)
Nuclear material, diagnositc and thearapeutic X-ray equipment
Welding equipment, mercury-vapor lamps, black lingt (UV) devices, flourescent and incandescent lights
White light devices
Arc processes, lasers, hot furnaces, molten metals/glass, alarm systems, motion detectors
Cellular phones, microwave ovens, radar, medical diathermy equipment, ultrasound, smoke detectors, MRI
Communications equipment, CB radios, AM/FM transmitters
Power-generating equipment, 60 Hz appliances like stoves, hair dryers, etc.
10^{-15}
10^{-14}
10^{-13}
10^{-12}
10^{-11}
10^{-10}
10^{-9}
10^{-8}
10^{-7}
The visible spectrum
10^{-6}
10^{-5}
10^{-4}
10^{-3}
10^{-2}
10^{-1}
1
10
10^{2}
10^{3}
10^{4}
10^{5}
10^{6}
10^{7}
red
orange
yellow
green
blue
violet

Figure 4.2. Light Spectrum Chart

and heal patients. To treat patients with emitted light therapy, the Qigong doctor first focuses his or her intention on visualizing a certain color and cultivating the energetic vibrations of this color. By visualizing a certain color, the Qigong doctor is activating the light energy within his or her own body. The doctor then focuses on projecting the healthy color light energy into the organs, channels, and organ systems of his or her patients.

Energy color therapy is divided into eight healing colors, ranging from low frequency (red) to high frequency (violet) and white. These energetic projections are associated with the color ranges emanating from the body's Taiji Pole, and range from a dark to a lighter color band.

When projecting color vibrations, it is important to note that there are four levels, or intensities, of color gradations within each color (Figure 4.3). In the soft color range, there are two levels: a light and a medium-light color used for gentler, less potent projections (usually for healing and cleansing wounds). Medium-light color projections are especially effective for treating young children and the elderly. In the intense range, there are two levels of intensities: a bright and a very bright color range, both of which are used for full-force projection (for destroying cells and pathogenic factors or stabilizing a Deficient organ or organ area). The bright color is used to begin with, later on the very bright color can be used as the patient's strength increases.



Figure 4.3. The Four Levels of Color Light Projection

Research has demonstrated that the use of color in Qigong treatments can effectively change a patient's pulse beat, body rhythms and depth of breathing. Advanced Qigong doctors modulate and switch energetic color projections during treatment. To avoid overstimulating the patient's tissues, the doctor starts with a lighter shade of color projection then increase the color's intensity until the proper color is obtained.

Medical Qigong uses the following eight colors for color projection: red, orange, yellow, blue, indigo, violet and white. Based on a modern study of the prismatic division of light energy, color projection is categorized as follows.

1. The ruby red color simultaneously heats and activates the body. Red improves blood circulation and stimulates the Small Intestine, Heart, Triple Burners, Pericardium, and Fire Qi of the body. The color red can be used to repair tissues or increase cellular growth, as well as to vitalize tissues, Blood, and the skeletal system. It is used for treating paralysis, broken bones, and internal and external wounds.
2. The color orange expels pathogenic factors and disintegrates Blood clots. It is also used in treating cysts. Orange can also be used to stimulate the Spleen and Stomach. (Contraindications: The doctor must avoid projecting orange color Qi into the brain, eyes, or Heart of the patient. The color orange is extremely potent and may cause damage.)
3. The lemon yellow color stimulates the nerves, reconstructs cells, and heals wounds. Yellow or orange yellow can stimulate the Stomach, Spleen, pancreas, digestive system, nervous system, and the Earth Qi of the body. Yellow is also used in the treatment of skin rashes and topical problems.
4. The emerald green color detoxifies and disperses pathogenic Qi. Green can stimulate the Liver, Gall Bladder, and the Wood Qi of the body. Green is used in combination with other colors; for example, shades of green are combined with shades of orange for treating tumors. Green color vibration is not as powerful as orange and may be used on elderly

patients to establish a more gentle healing session.

5. The flame blue color cools the body and is beneficial in soothing and calming a patient's anxiety. Blue can be used to stimulate the Bladder, Kidneys, the reproductive system, skeletal system, and the Water Qi of the body. The color blue is also excellent for relieving inflammation and fever and can be used as a mild anesthetic.
6. The indigo or dark blue color has a deep penetrating property and is used for knitting bones and creating "energetic casts" (used for enveloping wounds and specific internal organs). The color indigo can also be used to stimulate the Bladder, Kidneys, skeletal system, reproductive system, and the Water Qi of the body.
7. The reddish-blue color of violet is known for its purifying force, which facilitates the rapid healing of difficult infections, e.g., pneumonia.
8. White energy extension indicates a fusion of all colors. White energy is the most neutral and can be used when one is not sure which other color is appropriate. White is useful for calming the mind and placing a protective field around an organ or around the body. White stimulates the Large Intestine, Lungs, the respiratory system, and the Metal Qi of the body.

USING HEALING COLOR IMAGERY

Specific color meditations can be prescribed to assist patients in their healing. The patients are encouraged to visualize specific organ colors while the Qigong doctor projects that same color into their body and energetic fields (Wood-Liver-Green, Fire-Heart-Red, Earth-Spleen-Yellow, Metal-Lungs-White, and Water-Dark Blue/Indigo-Kidneys). This treatment technique is successful for tonifying, regulating, or purging all the body's major organs and is often combined with healing sounds.

When using healing color imagery, the patients are encouraged to first visualize the diseased organ as being dull, dark, and impure in color. In cases of Liver Heat, patients might imagine a dull, turbid brownish-green, tinged with red. For a Heart imbalance, the red color may be first imagined as a dull, weak or darkish red, tinged with brownish-red or purplish-red (like the color of stagnant Blood). Patients begin the meditation by concentrating on exhaling the toxic, pathological colors. As the patients inhale, they imagine a pure, vibrant ruby-red color flowing into their body from the Heavens or Earth, energizing, cleansing, and replacing the toxic energetic color of the diseased Heart.

Note: The image of the vibrant ruby-red color is prohibited in cases of Excess Heart Fire.

EXPOSURE TO EXTERNAL COLOR FIELDS

In this type of color therapy, patients are required to sit and meditate in rooms painted in the specific color relating to their condition. A healthy color is chosen in accordance with either the Five Elements' Creative Cycle or a Controlling Cycle, depending upon the nature of the patient's disease and which particular Yin organ (or organs) are involved. One example is using the Five Elements' Creative Cycle to tonify a patient's Deficient organ. The theory of the creative cycle is to stimulate and energize the "mother" in order to strengthen its proceeding "child" organ. For a Liver imbalance, for example, the patient can be placed in a blue room for tonifying the Kidneys (the Liver's "mother" organ). The Kidney color indigo (the mother) is used to nourish the Liver organ (the child). For a Liver Excess, the Qigong doctor would use the Five Elements' Controlling Cycle and place the patient in a white room, allowing the Lungs (the grandmother) white Metal color to control the Liver Wood (the child) organ.

Also specific colors can be worn by the patient, or the patient can surround him or herself with certain natural colors to initiate healing (e.g., emerald green for Liver conditions).

FOOD AND COLOR

Another treatment method requires the presentation of food (diet) as a form of color and light therapy. In this treatment the doctor makes sure that the Five Elemental colors are present within the patient's food. Each color will start a resonance within the patient's organs (i.e., Green-Liver, Red-Heart, Yellow-Spleen, White-Lungs, and Dark Blue/Indigo-Kidneys).

When eating the food the patient focuses his or her intention on ingesting the color, light, and energy of the food being eaten.

USING DISTANCE AND RANGE

When using color projection, an important factor is the doctor's ability to maintain focused intention. If the doctor becomes distracted or looses visual concentration, the color resonance being emitted becomes degraded, and the projected color transforms back into non-differentiated white-light energy. Since it is the vibratory rate of the specific color that promotes healing, a strong connection between the doctor and patient is vital in distance color therapy projection.

WESTERN LIGHT THERAPY

Light therapy is currently being used in Western medicine through the following modalities:

- Laser-light therapy surgery,
- Full-spectrum light therapy for SAD (seasonal affective disorder),
- Color-light therapy for eye problems and various other illnesses, and
- UV-light therapy for "blue babies" with hyperbilirubinemia.

MAGNETIC ENERGY

Magnetism can influence energetic flows of energy current within the body. It is difficult to separate the energetic properties of magnetism (Yin) and electricity (Yang), as they are almost two aspects of the same energetic field. The movement of electrical currents generate magnetic fields. By establishing different magnetic polarities, the Qigong doctor can influence the electrical flow in the body.

The body's cells carry electromagnetic fields that both attract and repel each other, resulting in a magnetic pull between the body's tissues, organs, and extremities, as well as the body's electromagnetic interaction with the Earth. Clinical research in China demonstrates that the iron in the hemoglobin of the Blood is attracted to the magnetic pull of the body's tissues, as well as the magnetic pull of the Earth.

The Earth, like the body, has both a Yin (magnetic) field and a Yang (electrical) charge. These energetic fields are interdependent. The magnetic

Figure 4.4. The Earth is enveloped with electromagnetic currents, affecting both weather and vegetation.



Figure 4.5. The body is enveloped with electromagnetic currents, affecting both internal and external organ functions.

field is caused by the movement of charged particles and spans the circumference of the Earth creating a strong electrical field (Figure 4.4).

Some modern researchers believe that the physical body's channel system (see Chapter 6) charges its field of magnetic flux through movement. It is further believed that the channel system creates an electrical field that attracts electrons into the body's Taiji Pole.

Richard Lee of the China Healthways Institute found that the Yin magnetic substances stored within the body's water molecules align with the electrically conducting structure of the body's channels (see Appendix 2). When the body's magnetic energy field is low, these channels become weakened and the conductivity is lowered. This magnetic energy can be replenished either from ingesting and transforming food, air and water, or gathered directly from the Earth's magnetic field.

The body's magnetic field conforms to the Earth's magnetic field through the energetic exchange within the body's electromagnetic fields (Figure 4.5). The body maintains this electromagnetic connection through the energetic resonance of the Taiji Pole. Within the structure of the body's Taiji Pole are located two major conductive poles of energy. These two conductive poles are located at the opposite ends of the Taiji Pole, positioned at the top of the head and the base of the perineum. The purpose of these energetic poles is to absorb Qi from universal and environmental fields, connecting and integrating the energy into the body's Three Dantians (see Chapter 5).

The electromagnetic lines in the body's force field begin from the at top of the head (traditionally considered the south pole) where the Heaven Qi flows into the body, and end at the at the base of the perineum (traditionally considered the north pole) where the Earth Qi flows into the body (Figure 4.6). Each of these two magnetic poles (the Lower and Upper Dantian) have a different energy influx. The energy originates and converts in the Lower Dantian and eventually flows to the Upper Dantian. The bottom pole, located in the Lower Dantian, converts Jing (Essence) into Qi (Energy) and increases the body's overall life-force energy. The upper pole, located in the Upper Dantian, converts Shen (Spirit) into perceptual insight and spiritual light.



Figure 4.6. Magnetic field around a spiral coil



Figure 4.7. Flux lines around current-carrying conductor

There are several ways in which the Qigong doctor can manipulate the electromagnetic field which surrounds the body. The doctor can directly absorb Heaven and Earth energy from the bottom of his or her feet, top of the head, and through both palms (called Absorbing Qi from the Five Gates). The doctor can also, through creative visualization, gather and loop the different types of environmental energy around his or her body, increasing the thickness and power of the electromagnetic field (the energetic boundary that surrounds the doctor's body). This looping action is similar to wrapping a magnet with wire to increase its magnetic field potential (Figure 4.7). Stronger lines of magnetic force will be produced around the body, thus creating a stronger "energy bubble" (Figure 4.8).

The direction of electromagnetic wrapping should be done in accordance with the natural flow of the surrounding environmental fields. Each individual should remain sensitive as to which technique works better for them, as there are individual variations used in accordance to the doctor's intention and belief.

MAGNETIC THERAPY THROUGH EMITTED QI

Qigong doctors are trained to manipulate their patient's electromagnetic field by extending emitted energy into the patient's tissues. This stimulation of the body's magnetic field is extremely effective for regulating the flow of channel energy, as well as stimulating the activity of the nervous system.

Magnetic therapy is also used as a companion to acupuncture therapy. Acupuncturists use magnetic patches, placing them on various channel points on the patient's body, to induce energy flow and tissue stimulation.



Figure 4.8. Qigong doctors can create a strong energetic field by absorbing Qi into their Lower Dantian. This energy extends into the Earth (like an anchor), and the Wei Qi field surrounding the doctor's body automatically increases and expands.

The negative north magnetic field pole of the magnet is placed in contact with the patient's skin in treating conditions due to Excess Heat and stagnation. The negative north pole is found to have a cooling and calming effect on tissues. Herbal teas used for purgation, dispersing, anti-inflammatory or sedative properties can be augmented by placing the tea on the north pole of a magnetized surface for a minimum of an hour before drinking.

The positive south magnetic field pole of the magnet is placed in contact with the patient's skin in treating Deficiencies, Cold and blockages. The positive south pole is said to have a stimulating and warming effect on tissues. Herbal teas used for warming and tonification can be augmented by placing the tea on the south pole of a magnetized surface for a minimum of an hour before drinking.

WESTERN MAGNETIC THERAPY

In 1990, Dr. Arthur Trappier submitted a paper on "Evaluating Perspectives on the Exposure Risks from Magnetic Fields" to the *Journal of the National Medical Association*. In his article, Dr. Trappier explained that exposing cancer cells to a negative magnetic field discourages the growth of the cancer, while exposing cancer cells to a positive magnetic field encourages their growth. Magnetic therapy is currently being used in Western medicine through the following clinical modalities:

- Permanent magnet therapy for localized pain and inflammation relief,
- Super-magnet therapy for stimulation of the thymus for immune enhancement in cancer patients, and
- Pulsed magnetic therapy for the treatment of arthritic joints.

GENERATED HEAT

Electricity passing through any substance will produce heat. The amount of heat that will be generated depends upon the resistance of the substance and the density of the current's flow. Heat is generated at the electron level by the friction created through molecular motion. By increasing the motion of the molecules, more heat is generated. Molecules in living organisms are in constant motion, increasing or decreasing their rate of acceleration according to the environmental temperature. In order for heat to have any effect on the body, enough Qi has to be transferred to increase the movement of the molecules.

The heat within the body causes increased electron movement, resulting in more heat being generated on a cellular level. Heat is also caused by cellular metabolism. The body's metabolism produces 75% of the energy being created in the form of heat. Cellular activity is increased through electrical, magnetic, heat, sound, and light stimulation.

From a Medical Qigong perspective, Heat in the body is generated from the accumulation of Three Fires which emanate from specific locations within the body. Within the body's chest cavity is the Heart Fire, located within the abdominal cavity is the Kidney Fire, and all through the body flows the Bladder Fire. When the Heart Fire first awakes, the Kidney Fire responds to it, and when the Kidneys Fire moves the Bladder Fire follows it.

When these Three Fires follow their normal course of energetic movement, they issue and lead the body's life-force energy, creating and sustaining life. The Three Fires are responsible for regulating the Yin and Yang energy of the body by fusing the Five Elemental energies (stored within the body's Wood, Fire, Earth, Metal, and Water organs) with the energy of the Three Dantians. As the Shen from the Heart Fire is drawn into the Lower Dantian, the Bladder Fire fuses with the Kidney Fire, creating the body's True Fire. This action causes the body's Jing to create Qi in the Lower Dantian and then transform Qi into Shen in the Middle Dantian. Once this fusion is obtained, the mind, breath and body connections all become regulated.

The Three Fires also represent the regions of vital Heat responsible for the circulation of energy that sustains the Eternal Soul. Accessing the energy of the three Fires is used for cultivation and spiritual liberation, and is brought about through Qigong practice, prayer and meditation.

1. The Heart Fire, also called the Commanding or Emperor's Fire, is located in the center of the chest. The Heart Fire is responsible for transforming the body's energy into Shen.
2. The Kidney Fire or Mingmen Fire, is located in the back of the body, just below the last floating rib. Qigong masters in ancient times regarded the Mingmen Fire as the motivating force of the body and paid special attention to its training during Qigong exercises. A Deficiency of the Mingmen Fire may lead to decreased sex-drive, hypogonadism and impotency. Conversely, if the Mingmen Fire is in Excess, increased sex-drive or sexual obsession and hypergonadism will occur.

   Dr. Zhao Xianke, an expert on medicine during the Ming Dynasty period, states that "the Mingmen Fire dominates all Twelve Primary Channels. Without it the Kidneys would be weak, the Spleen and Stomach could not digest food, the Liver and Gall Bladder would not give any energy to think or plan, the urine and feces would not be moved, and the Heart would malfunction causing dizziness and endangering life."
3. The Bladder Fire, also called the Common People's Fire, is located in the lower abdominal area by the perineum and is responsible for evaporating water.

The Three Fires are not the Triple Burners, as the purpose of the Triple Burners is to regulate the major internal organs and is a completely different energy system. The physical locations of the Three Fires however, coincides with the locations of the Triple Burners.

HEAT THERAPY THROUGH EMITTED QI

Stimulating the body's tissues through Heat therapy is extremely effective for treating Deficient and Cold syndromes. In China, Qigong doctors use the extension of Heat through their emitted field of electromagnetic energy to stimulate their patients' tissues. This therapy helps to regulate the flow of the patients' channel energy, and tonifies the Blood and Qi.

Heat therapy is also used in the form of moxibustation as a companion to acupuncture therapy. Acupuncturists will use moxa sticks and/or cones, lighting and placing them on or over various channel points of the patients' body. This is practiced to induce Qi flow and tissue stimulation.

WESTERN HEAT THERAPY

Radiant and conductive heat therapy are currently being used in Western medicine for vasodilation and pain relief. These heat therapies can further be broken down and categorized into dry-heat therapy and moist heat therapy.

Dry-heat therapies include the following:

- Dry packs
- Hot-water bottles
- Heliotherapy-sun therapy
- Ultraviolet-heat therapy
- Infrared-heat therapy
- Diathermy therapy

Moist-heat therapies (hydrocolators) include the following:

- Hot bath packs
- Hot wet packs
- Hot foot baths
- Fomentations
- Poultices
- Vapor and paraffin baths

ELECTRICITY

A flow of electrons is called a current. Just as a current produces a magnetic field, a magnetic field, when it moves in relation to a conductor, induces an electrical current. In Medical Qigong therapy, the body's channels are also considered electrical circuits, and the points existing within each channel can be considered booster amplifiers (or step-up transformers) that maintain the current's strength. According to Dr. Robert O. Becker, research scientist and author of the book *Cross Currents,* acupuncture needles have the capacity to act as antennae, drawing charged particles (ions) from the atmosphere into the body. The acupuncture needle delivers a low-level electrical stimulation to the channel points and can be used to charge up, or decrease the energetic potential of these "step-up transformers," affecting the current along the channel.

The human body is an excellent conductor of electricity and contains both alternating and direct electrical currents. The alternating current is responsible for the transformation of the body's magnetic field into the body's electrical field. The direct current is responsible for the body's positive Yang and negative Yin flow of electrical charges.

The friction produced by rubbing the feet on a carpet creates a charge that is stored within the body until touching another conductor (metal, another person, etc.) to release the charge. This normal and common occurrence demonstrates the storage, conductance, and discharging of electrons from the body. Any time electrons travel, heat, or thermal radiation is produced.

According to Swedish Physician and medical research scientist Dr. Bjorn Nordenstrom, the biological circuits of the body are driven by the accumulated charges, which, unlike a battery, oscillate between positive and negative. The body's system of channels and blood vessels act as insulated cables, while the blood plasma acts as the conductor. In the permeable tissue, the fluid between the cells conducts ions. A key component of the body's electrical circuit is the natural electrodes in the capillary walls, known as the lipid bilayers of the electron transport chain.

A myriad of electrical forces work within the body. Every human thought and action is accompanied by the conduction of electrical signals along the fibers of the nervous system. In fact, life would not exist at all without a constant flow of ions across the membranes of cells.

The electromagnetic energy in the body's cells is continuously being generated through the biochemical transformation of food, and air, and is circulated by the electromagnetic fields being generated within the tissues. Perineural cells, or nerve sheaths, carry the direct current of the body's electricity. These cells are responsible for motivating the body to heal, regenerate, and repair itself. Healing is always affected by a change within the body's electromagnetic field. The rate and efficiency of healing is based on the strength and polarity of the body's field of energy. This electricity is one of the primary energy sources responsible for maintaining life itself.

Dr. Becker's research demonstrates that bones are "piezoelectric": when stressed, mechanical energy is converted into electrical energy that produces an increased electrical current. Dr. Becker discovered that running a minute electrical current through a fractured bone will stimulate the reproduction of the cells, creating a healing current similar to the body's natural healing mechanism.

According to Richard Lee of China Healthways Institute, electrostatic waves are observed in the body through EEGs (electro-encephalograms) and EMGs (electro-myograms). Different types of therapies affect the EEGs (sound therapy, meditation therapy, self-regulation Qigong therapy, light therapy, etc.). By controlling their thoughts, Qigong doctors can affect the current in their body and thus affect the EEG measurements. These thought patterns will in turn influence the Qigong doctors' electrical field. Experiments show that EEG measurements in test subjects receiving energy from healers tend to synchronize. Qigong doctors, when treating patients, can produce voltages as high as 190 volts, 100,000 times greater than regular EEG voltages.

The body's natural ability to gather, store, and move Qi increases the body's abilities to gather, store, and move electrical charges. The gathering of these electrical charges can cause a gradual electric buildup within the tissues and internal organs, developing into an Excess Qi condition within the body. Excess Qi conditions often manifest mood swings and are responsible for the energetic circuit overloads that occur spontaneously within the body. Excess Qi manifests as a sudden "explosion" or "release" of emotions such as rage, fear, grief, worry, fright, anxiety, and joy. An excess electromagnetic charge, internally combined with the Qi from a patient's on-going emotions can be drawn into an organ's tissue area and absorbed by the internal organ that is in the most elevated state of energy conversion. This energetic reaction can cause the already overcharged internal organ to spontaneously release emotions. Sometimes the release is physiological, e.g., sudden sweating, blushing, twitching or jerking, yawning, stretching, sighing, burping, passing gas, etc. These can all be ways that the organ seeks to regain hemostasis.

ELECTRICAL THERAPY THROUGH EMITTED QI

The idea that an electric current can stimulate bodily repair, alert defence mechanisms, and control the growth and function of cells is not a new concept in Western medicine. In fact, the use of bio-electromagnetism dates back at least 200 years. Electrotherapy is found to be very useful in relieving pain by signaling the brain to activate and alter the body's neurochemicals. The insertion of electrically stimulating needles into a patient's body, for example, causes a release of endorphins, and is used for pain management.

Medical Qigong, acupuncture, and Chinese massage likewise, stimulate the peripheral and cutaneous nerves that carry sensory information, via the spinal cord, to the brain. This stimulation of the cutaneous nerves activates the brain's opiates (endorphins - endogenously generated morphine) and facilitates the closure of the body's pain relay gates, killing pain, and is the basis for anesthesia. Because medical Qigong therapy also has an analgesic affect on the body's cutaneous tissues, it is being increasingly used in hospitals for pre- and postoperative procedures.

WESTERN ELECTROTHERAPY

Electrotherapy is currently being used in Western medicine through the following modalities:

- Giga-TENS therapy for stimulation of healing,
- TENS therapy for pain relief,
- CES-cranial electro-stimulation therapy-for depression and substance abuse, etc., and
- Micro-stimulation therapy for micro-current stimulation below the threshold of awareness, to stimulate nonspecific healing, the reduction of inflammation and the harmonization of tissue polarity.

CHAPTER 5
THE THREE DANTIANS AND THE TAIJI POLE

THE THREE DANTIANS

According to Chinese energetic physiology, humans have three important energy centers, located in the center core of the body, that store collected energy in much the same way as a battery does. These three centers are called the Three Dantians (Figure 5.1). The word Dan literally translates to mean "cinnabar," while the word tian means "field." In terms of Medical Qigong tian is referred to as a field of energy. Together, the characters for Dantian literally translates as "cinnabar field" or "field of elixir."



Figure 5.1. The Anatomical Locations of the Three Dantians and Center Core (Taiji Pole)

Cinnabar is mercury sulfide, a bright red or vermillion mineral, which is the principal ore of mercury. Cinnabar was an important mineral in ancient China, the source material needed to manufacture vermillion ink, which could be used only by the emperors. Cinnabar was -- and is today -- also used in Chinese medicine to sedate the Heart and calm the Shen, but always in small doses for short periods due to its highly toxic nature.

Cinnabar was also a vital elixir in Daoist alchemy, as it was discovered to be very balanced in its Yin and Yang properties. Daoist alchemy, like Western alchemy, was practiced in two ways: outer alchemy (Wai Dan) and inner alchemy (Nei Dan). Outer alchemy was the ancestor of modern chemistry. Outer alchemists set up laboratories and experimented with many substances from mineral, animal, and plant sources with the goal of discovering how to turn base metals into gold. Secretly, they were also seeking to discover an elixir, or drug, that would confer immortality or, at the least, greater longevity. Along the way they made many important discoveries, such as gunpowder, medicines, and many other substances vital to the world today.

Inner alchemy was concerned with purifying human nature and transforming the spirit into its most pure and radiant potential without the use of outer agents. Instead, they used Qigong and meditation to circulate and gather the "inner elixirs" of sexual energy, Qi, and consciousness at various locations within the body. The Three Dantians, or "elixir fields," in addition to storing energy, act like an alchemist's crucible, or cauldrons in the role of gathering and transforming vital substances, energies, and various elements of awareness. The ingredients of the inner elixir are Jing, Qi, and Shen. The inner alchemists kept their work secret by using mineral code words such as "gold," "lead," and "cinnabar" to describe the movement and transformation of energetic and spiritual substances within the body.

The goal of the inner alchemists is immortality, a complete transformation of Jing, Qi, and Shen. Jing, Qi, and Shen are collectively called the Three Treasures and are the three fundamental energies necessary for human life. To accomplish this transformation, alchemists first gather and transform Jing into Qi in the Lower Dantian. They then gather and transform Qi into Shen in the Middle Dantian. Next, they transform Shen into Wuji (the absolute openness of infinite space) in the Upper Dantian. Finally, they merge Wuji into Dao (divine energy). The Three Dantians serve as the inner crucibles for these transformations.

These transformations can be compared to the changes of water (the consistencies and not the temperature), which when heated, can change from solid ice, to a liquid, and then to vapor.

The Three Treasures (Jing, Qi, and Shen) are also connected with the Three Outer Forces or Powers known as Heaven, Earth, and Man. Jing (reproductive essence) is the most substantial and therefore the most Yin of the three, and it is closely linked with Earth Qi. In Medical Qigong practice and Daoist inner alchemy, the Earth energy is gathered in the Lower Dantian and is associated with heat. Qi is a mixture of Yin and Yang and is closely connected with the atmospheric energy, which is a blend of Heaven and Earth Qi and gathered into the Middle Dantian, (which is associated with vibration). Shen (Spirit) is the most insubstantial and, therefore, the most Yang of the three; it corresponds with Heaven Qi, and is gathered in the Upper Dantian which is associated with light.

The Three Dantians are connected to each other through the Taiji Pole. The Taiji Pole acts as a passageway for communication between the Three Dantians, and as a highway for the movement of the various life-force energies. The Eternal Soul is drawn into the body at the moment of conception through the Taiji Pole, and departs through it at death. The Taiji Pole also serves as a transport for the body's Hun.

Regardless of whether or not a modern Qigong practitioner is concerned with spiritual transformation, from a Medical Qigong standpoint the Three Dantians are still vital centers for the cultivation of energy. They are important areas for diagnosis and self-healing, as well as for projecting Qi to patients.

The following is an exploration of the Three Dantians and their individual relationships to the Three Treasures of Jing, Qi, and Shen.

THE LOWER FIELD OF ELIXIR

The Lower Dantian is the Dantian most familiar to martial artists and Zen meditators. It is regarded as the center of physical strength and the source of stamina. Called the "Hara" in Japanese, it is located in the lower abdomen, in the center of the triangle formed by drawing a line between the navel, Mingmen (lower back), and perineum. These three points form a pyramid facing downward. This configuration allows the Lower Dantian to gather the energy from the Earth.

The Lower Dantian is the major storage area for the various types of Kidney energies. The Kidney energies are, in turn, closely linked with our prenatal energies and provide the foundation for all other types of Jing, Qi, Yin, and Yang energies in the body.

The Lower Dantian is connected to the first level of Wei Qi (Protective Qi) circulating outside the body, extending from the body's tissues to about one inch. As the Lower Dantian fills with Qi, the Wei Qi field naturally becomes thicker.

THE LOWER DANTIAN AND JING

The Lower Dantian collects Earth energy and represents the body's physical energy of Jing. The Earth energy that is transformed in the Lower Dantian is a dense, full energy with a thick quality to its texture. In our analogy with the transformations of water, the energy in the Lower Dantian is dense, like ice.

The Lower Dantian is closely linked to the Jing Gong (Essence Palace) located in the perineum, which serves as a reservoir of Jing. Our Prenatal Essence (Yuan Jing), determines our constitutional strengths and vitality, and is stored in the Lower Dantian. It interacts with the Kidney energies to form Kidney Jing. The Kidney energies are all closely intertwined: Kidney Jing, Kidney Qi, Kidney Yin, Kidney Yang, and Kidney Fire. The Mingmen Fire, also called Kidney Yang, helps transform the Jing into steam (Kidney Qi).

Kidney Jing circulates throughout the body via the Eight Extraordinary Vessels, in particular, the Governing, Conception, and Thrusting Vessels, all of which originate in the Lower Dantian.

Kidney Jing controls the reproductive energies and life cycles in the body. Some of the ancient alchemical texts describe the Lower Dantian in women as being located in the Bao or uterus, and it is related to the function of Jing in a woman's body. In men, the reproductive essence is located in the Jing Gong (Essence Palace) or prostate and seminal vesicles. In some Chinese medical, Daoist, and Qigong literature, the term Kidneys is used as a synonym for the testes and ovaries.

The location of the Jing Gong is affected by the different anatomical locations of the male and female reproductive organs. In men, this area is located in the center of the body, at the level of the superior border of the pubic bone, posterior to the Qugu CV-2 (Crooked Bone) point. The Jing Gong area in women is located higher, centered in the uterus, about an inch above the superior border of the pubic bone, posterior to the Zhongji CV-3 (Utmost Center) point.

This difference in location, in turn, affects the storage of Jing (i.e., the testicles in the male cause the transformation of energy to occur lower in the body than in females, due to the higher position of the woman's ovaries).

Jing is the most physical, material form of Qi within the body (corresponding to Yin and Earth energy). The Lower Dantian is the place where Qi of the Earth is drawn into the body and transformed by heat.

The Lower Dantian acts as a reservoir for heat and energy and is associated with the Kidneys. The Kidneys control the Water element in the body. Jing is said to be like the water in the cauldron. Through focused concentration and meditation, the Jing (Essence) in the Lower Dantian is refined and transformed to produce Qi (Energy). When heat is generated as a result of the Heart and Mingmen Fire mixing with the Kidney Water, the alchemical transformation of Jing in the Lower Dantian area transforms Jing into the steam of Qi (the character for Qi is composed of steam rising from a cooking pot). This alchemical transformation is known as "changing Jing into Qi," and takes place within the Lower Dantian.

THE LOWER DANTIAN AND QI

The Lower Dantian is often called The Sea of Qi. It is the place where Qi is housed, the body's Mingmen Fire is aroused, the Kidney Yin and Yang Qi is gathered, and the Yuan Qi is stored. Also called Source Qi, the Yuan Qi is the foundation of all the other types of Qi in the body. The Yuan Qi is closely linked with the Prenatal Essence (Yuan Jing). Together, the Yuan Qi and Yuan Jing determine our overall health, vitality, stamina, and life span.

The Yuan Qi is the force behind the activity of all of the organs and energies in the body. It is closely related to the Mingmen and works to provide body heat. The body's Yuan Qi is the catalytic agent for transforming the food we eat and the air we breath into Postnatal Qi. It also facilitates the production of Blood.

Yuan Qi is housed in the Lower Dantian, and it also flows out to the internal organs and channels through the Triple Burners. Yuan Qi is said to enter the Twelve Primary Channels (the body's twelve major energy pathways) through the Yuan points (sometimes called Source points) in acupuncture theory.

Of the Three Dantians, the Lower Dantian is closest to the Earth, is the most Yin, and has the strongest ability for gathering Earth Qi. In Medical Qigong, once students have learned to conserve and circulate their own Qi, they can increase it by connecting to the unlimited reservoirs of Qi in the natural environment. Earth energy is the first form of external Qi with which the Qigong practitioner connects. This energetic connection to the Earth is important for several reasons.

1. First, Qigong practitioners need the Yin grounding power of the Earth Qi to counterbalance the gathered active Yang energy from Qigong exercises. Without grounding in Earth Qi, many Qigong practitioners develop Qi deviations in the form of Excess Heat.
2. Second, each person's supply of Qi is limited. When Qigong doctors extend their Qi to heal others, they deplete their personal supply of Qi unless they are able to simultaneously replenish their supply from outside sources.

Even people who do not practice Medical Qigong draw Earth Qi into their Lower Dantians. By practicing Qigong and using conscious intent, the amount of Earth Qi drawn into the body is vastly increased.

THE LOWER DANTIAN AND SHEN

The Lower Dantian itself is considered a center of consciousness. The consciousness of the Lower Dantian is more kinesthetic or physical given its Yin nature and close proximity to the Earth.

The body's Jing is connected with the Po (Seven Corporeal Souls). The Po control our survival instinct and the subconscious physical reflexes associated with survival. For this reason, Oriental martial artists spend many hours cultivating their lower elixir field to have the integration of Jing, Qi, and Shen needed for the split-second clarity of focus demanded in life-and-death struggles.

THE LOWER DANTIAN AND KINETIC COMMUNICATION

Not only is the Lower Dantian the center of physical strength and the source of stamina, but it is also considered the "house" of physical (kinetic) communication, awareness and feelings. The level of awareness referred to as "the intuition of the physical body," or kinetic communication, is stimulated by the subconscious. The subconscious mind picks up many signals from the environment that are not processed by the logical mind. These signals can motivate spontaneous body movements and responses and are sometimes referred to as gut feelings.

Kinetic means "characterized by movement." It is usually felt as a movement in the body or of the body. It is in this kinetic state of awareness that allows Qigong doctors to naturally feel the patient's internal resonant vibrations within their own body. When the doctors' body suddenly feels hot or cold, starts shaking or trembling, this may indicate that their subconscious mind is trying to communicate the location and condition of the diseased area within the patient's tissues.

Most of the time, the feelings experienced in the Lower Dantian are very subtle, but Qigong doctors, with a heightened degree of awareness of their own body, are able to pick up subtle variations of energetic shifts within themselves and others. When doctors collect energy in the Lower Dantian, an increased awareness and sensitivity naturally occurs. Cultivating this ability simply requires practice in paying attention to the physical body. A high level of awareness of the physical body, the surrounding environment, and the relationship between the two is required to maximize kinetic communication. When awareness is increased, perceptual feeling and kinetic body movements happen naturally. These are subtle senses that allow Qigong doctors to feel, smell, or hear energetic phenomena as they are released from the diseased tissues of patients.

According to research conducted by Dr. Michael Gershon, a professor of anatomy and cell biology at Columbia Presbyterian Medical Center in New York, the Lower Dantian sends and receives impulses, records experiences, and responds to emotions. Its nerve cells are bathed in and influenced by the same neurotransmitters as the brain. The Lower Dantian's "brain," known as the enteric (intestinal) nervous system, mirrors the body's central nervous system and is a network of 100 million neurons (more then the spinal cord contains), neurotransmitters, and proteins that can act independently of the body's brain, and can send messages, learn, remember, and produce feelings.

Dr. Gershon explains that active within the neural system of the lower abdominal area are major neurotransmitters like serotonin, dopamine, glutamate, norepinephrine, nitric oxide, enkephalins (one type of natural opiate), and benzodiazepines (psychoactive chemicals that relieve anxiety). The lower abdomen also has two dozen small brain proteins called neuropeptides. Dr. Gershon's research results provide modern scientific verification of what Eastern wisdom has taught for millennia -- that centers of consciousness exist at places in the body besides the brain and that the abdomen is one of the body's major centers of awareness.

ANATOMICAL LOCATION OF THE LOWER DANTIAN

The Lower Dantian is centered below the umbilicus, inside the lower abdomen, forming a downward pointing triangle. It occupies the first three lower Chakra gates. Chakras are small energy centers that originate from the Taiji Pole and have one or more gates.

1. The lowest point of the Lower Dantian extends to the Huiyin CV-1 (Meeting of Yin) point at the perineum. The name refers to the area on the body responsible for gathering and absorbing the Earth energy. This area is responsible for gathering the Yin energy into the body and Lower Dantian area via the three Yin leg channels (Liver, Spleen, and Kidney). This area is sometimes known as the Lower Gate of the Taiji Pole, or the Bottom Gate of the Lower Chakra.
2. The front area of the Lower Dantian is located posterior to the Shenque CV-8 (Spirit's Palace) point at the navel. The name refers to the place where the mother's Qi and Shen enter the embryo during fetal development. This area is sometimes known as the Front Dantian, or the Front Gate of the Second Chakra.
3. The back area of the Lower Dantian is located at the Mingmen GV-4 (Gate of Life) point on the lower back, anterior to the second lumbar vertebra. The Mingmen occupies the place between both Kidneys. It is the root of Yuan Qi, and therefore determines life and death. The Mingmen provides the body's True Fire; it supplies the heat for the Triple Burners, and is responsible for stabilizing the Kidneys and Lower Dantian area. This area is sometimes known as the Back Dantian, or the Back Gate of the Second Chakra.
4. Medical Qigong schools in China differ in their belief as to where the center of the Lower Dantian is located. Some schools teach that the center of the Lower Dantian is affected by the different anatomical locations of the male and female reproductive organs. In these particular schools, the students are taught that in men, the center of the Lower Dantian is located posterior to the Guanyuan CV-4 (Gate of Original Qi) point. The center of the Dantian area in a women is said to be located internally higher, and posterior to the Qihai CV-6 (Sea of Qi) point. This area is sometimes called the Middle of the Dantian, referring to its position between the navel and Mingmen areas.

THE NINE CHAMBERS OF THE LOWER DANTIAN

The human body is viewed as a microcosmic replica of the power of Heaven. Just as Heaven is said to be divided into nine different levels, each containing various palaces, our bodies also are said to contain a large variety of palaces and chambers. The nine stars of the Big Dipper are said to correspond to the Nine Chambers of each of the Three Dantians.

The functional aspects of the body's psyche were described by ancient Qigong masters as "spirits" that lived within the nine chambers of the Lower Dantian. These "spirits" linked the body's energetic channels and vital internal organs into an organic harmony of life-force energy. Qigong masters believed that as each Dantian became energized, it would initiate specific reactions within the body's energetic system, causing certain energetic / spiritual awareness to manifest within the practitioner's psyche.

Each of the nine chambers is several inches in diameter and is numbered in accordance to its en-


Liver
Stomach
Large Intestine
Small Intestine
Pubic Symphasis
Urinary Bladder
Vagina
Uterus
Huiyin
Rectum
Aorta
Spleen
Kidney
Mingmen
Overies
9
2
5
3
6
4
7
8
1

Figure 5.2A. The Nine Chambers of the Lower Dantian are shown here in the female body. Each number encompasses the entire chamber.


Liver
Stomach
Large Intestine
Small Intestine
Urinary Bladder
Pubic Symphasis
Penis
Testes
Prostate Gland
Huiyin
Rectum
Aorta
Spleen
Kidneys
Mingmen
9
5
2
6
3
7
4
8
1

Figure 5.2B. The Nine Chambers of the Lower Dantian are shown here in the male body. Each number encompasses the entire chamber.

ergetic stimulation (Figure 5.2 A-B). This vertical abdominal set of Lower Dantian chambers relates to many cavities of the body's internal viscera. The Nine Chambers of the Lower Dantian are named as follows.

1. The Palace of Jade (Jade Stem or Jade Cave)
2. The Official Health Monitor (Kidneys)
3. The Minister of the Orchard Terrace
4. The Chamber of Moving Pearls
5. The Minister of House Cleaning (Large Intestine)
6. The Palace of Mystical Spirits (Small Intestine)
7. The Chamber of Mysterious Elixir
8. The Spirit of the Jade Court (Bladder)
9. The Spirit of the Yellow Court (Spleen)

ENERGETIC FOCUS OF TRAINING THE LOWER DANTIAN

All Qigong training begins with the focus on the Lower Dantian. In the beginning stages of Medical Qigong training, the doctor will encourage students to focus their mind and breath on the Lower Dantian. The purpose of this training is to gather the body's Yuan Qi into the Lower Dantian (called "returning to the source"), to strengthen the foundational root for the body's energy.

It is dangerous for Medical Qigong students to bypass the discipline of Lower Dantian cultivation training to progress more quickly to the more advanced intuitive and psychic training of the Upper Dantian. Such an approach to training may lead to Qi deviations (see Chapter 18) and cause emotional instability.

THE MIDDLE FIELD OF ELIXIR

The Heart is the primary organ related to the Middle Dantian; the second organ is the Lungs. In Medical Qigong, the thymus gland is also of primary importance to the Middle Dantian.

In children, the thymus gland is quite large. As the child matures into adulthood, the thymus gland shrinks in size. Until recently, Western biologists thought that the thymus gland became vestigial and inactive in adults. Beginning in the 1980's, however, with the advent of the AIDS epidemic and the increase in cancer cases, intensive new research was launched into the immune system. As a result, scientists discovered that the thymus gland plays a major role in educating and maturing the white blood cells to become immunocompetent. This thymus function continues throughout one's life.

The Middle Dantian collects Qi and represents the body's energetic reservoir for mental and emotional vibrations and energy. The energy of man that is transformed in the Middle Dantian has a fluid quality—like water.

A refining process also takes place in the Middle Dantian, transforming the fluid energy into more steam-like energy that is then transferred to the Upper Dantian. The Middle Dantian transforms Qi into Shen by bringing the transformed Qi into the Heart Fire. This alchemical process is commonly called "changing Qi into Shen" and refers to kinetic energy transforming into spiritual consciousness.

The Middle Dantian is connected to the second level of Wei Qi, circulating about one-and-a-half feet outside the body. As the Middle Dantian fills with Qi, the colors of the student's middle field of Wei Qi change, becoming even more pronounced. The reason for this change is that the Middle Dantian is connected to the Five Agents, which in turn govern the Five Yin Organs and organ emotions. As the students begin to experience various stresses and emotional releases their aura (resonating from the internal organs, throughout the second energetic field) changes its colors.

THE MIDDLE DANTIAN AND JING

The Heart is related to the Fire element. The Heart derives its Yang Fire from the Kidneys. Modern research in Chinese medicine equates the function of the adrenal glands to the traditional function of Kidney Yang. In Western physiology, the adrenal glands help to regulate the pace of the heart.

To keep the Heart Fire in balance, the Heart also needs Yin. Heart Yin is derived from Kidney Yin (Jing is one aspect of Kidney Yin).

In traditional Chinese physiology, the Heart is said to govern the Blood. Not only is the Heart responsible for the circulation of Blood, but in the Chinese view, the transformation of Gu Qi into Blood takes place in the Heart. Food Qi (energy derived from the consumption and transformation of food matter) is a form of postnatal Jing, derived from the Spleen and Stomach. Blood is composed of Nutritive Qi (Ying Qi), Jing and Fluids (see Chapter 22). The Kidneys also send prenatal Kidney Jing to the Heart to make Blood. Therefore, Jing - particularly postnatal Jing - is vital to the Heart's function of governing Blood.

THE MIDDLE DANTIAN AND QI

Similar to the Lower Dantian, the Middle Dantian is also considered to be a Sea of Qi. The Qi of the Middle Dantian is called Zong Qi. Zong Qi is translated as Ancestral Qi, Gathering Qi, Genetic Qi, or Essential Qi. In English translation, it is sometimes confused with the Original Qi (Yuan Qi), but they are not the same. The Zong Qi is a form of postnatal Qi, whereas the Yuan Qi is housed in the

Lower Dantian and is a form of prenatal Qi. Zong Qi and the Yuan Qi assist each other to maintain the healthy function of the Heart and Lungs.

The Zong Qi nourishes both the Heart and Lungs, controls the speech and the strength of the voice, and interacts with the Kidneys to aid in respiration. According to Traditional Chinese Medicine, the Kidneys assist the Lungs in holding and stabilizing the breath when inhaling.

Qi and Blood are closely related. In Chinese medicine, it is often said, "Qi is the master of Blood; Blood is the mother of Qi." Qi gives the Heart and blood vessels the strength to circulate Blood and gives life to the Blood. Blood, on the other hand, houses and carries Qi to all the cells in the body. When one loses Blood, one also loses Qi. Therefore, one should consider Qi and Blood to be inseparable.

Qi is also inseparable from the mind and spirit. According to the teachings of ancient Tibetan Qigong masters, the channels are, metaphorically speaking, the road, the Qi is the horse, and the mind is the rider. Through refining the Qi, the mind and spirit are refined and purified. The Middle Dantian is the main focal point for this refinement of Qi into spirit.

THE MIDDLE DANTIAN AND SHEN

Classically, the Chinese locate the Mind in the Heart. In Chinese, the word for "mind" (Xin) is also the Chinese word for Heart. In Medical Qigong, a distinction is made between the Acquired Mind (Ren Xin) and the Original Mind (Yuan Xin).

The Middle Dantian is said to house the Shen and control all of the other functions of Shen that are attributed to the other Yin organs. Thus the Heart is often referred to as the Heavenly Emperor.

Throughout the world, people relate the heart to emotions and feelings. Emotions and feelings are one important aspect of the spirit. Any type of emotion will have an effect on the Shen.

The negative emotions are sometimes called "the five thieves" because even though negative emotions are necessary for life, chronic states of negative emotions drain the Qi.

The human mind easily falls under the influence of the Po (the Seven Corporeal Soul), that are concerned with survival. When the Po dominate the Heart, their overexaggerated self-concern gives rise to a chronic state of fear, sadness, worry, anger, and defensive arrogance.

The redeeming virtue of the Heart is a sense of propriety and discriminating awareness. The Hun (the Three Ethereal Souls) control the smooth flow of Qi throughout the body and are nourished by the Five Virtues of kindness, order, trust, integrity, and wisdom. These Five Virtues give peace and clarity to the Heart and allow the higher qualities of the Yuan Shen to overrule the Po.

An important relationship regarding the Middle Dantian and Shen is found in the Heart's role of governing the Blood. The ancient classics state that the Shen also resides in the Blood and pervades the body through Blood circulation. This relationship between Blood and Shen is one reason why anemic patients are often restless and suffer from insomnia. Through nourishing the Heart Blood, many forms of spiritual unrest can be treated.

According to Dr. Candace Pert's information on neurotransmitters (stated in *Psychoneuro Immunology*), the brain and white blood cells both contain the same neurotransmitters and biochemical constitutes that are prerequisite for consciousness awareness to exist. These same neurotransmitters and biochemical constitutes which are linked to consciousness are synthesized and created by the white blood cells. This similarity indicates that not only do the brain and abdomen have their own consciousness and nervous system but so does the Blood. This similarity also implies that consciousness is possible anywhere in the body, substantiating the ancient Chinese understanding that consciousness is pervasive throughout the body via the Shen, which resides in the Blood.

THE MIDDLE DANTIAN AND EMPATHIC COMMUNICATION

The Middle Dantian is also considered the "house" of emotional (empathic) communication, awareness, and feelings. Emotional communication is analogous to the feelings of empathy felt within the Heart. Empathy is the means by which the Qigong doctor will most frequently get in touch with the emotional components of the patient's energetic blocks and imbalances.

Empathic communication is felt as an emotion and originates in the Heart and Middle Dantian area. When Qigong doctors focus on the Middle Dantian area, a line of communication is created with their higher self. We are all born with this ability, but as we grow older, we tend to override this type of emotional communication with our logical mind. These impressions slowly atrophy, eventually causing us to lose this natural empathic ability of communication. We disconnect from this higher perception due to the negative and double messages received from our parents and from society. The way to reconnect with the intuitive self is to look inward and become one with our true self, which is connected to the divine.

ANATOMICAL LOCATION OF THE MIDDLE DANTIAN

The Middle Dantian is shaped like a tetrahedron (four points): one area points toward the Upper Dantian and the Heavens, one area points toward the Lower Dantian and the Earth, one area points toward the front, and one area points to the back .

1. The front lower point of the Middle Dantian is located at the Zhongwan CV-12 (Middle Stomach Cavity) point on the midline of the abdomen, just below the sternum. This area is the master point of the Middle Burner and is sometimes known as the Front Gate of the Third Chakra.

   This emotional storage area is also called the Yellow Court because it reflects the emotions stored from the Heart, (the Heart was sometimes referred to as Suspended Gold in ancient China).

   The back lower point of the Middle Dantian is located on the Jinzhong GV-6 (Middle of the Spine) point. The name refers to the point's location. This area is sometimes known as the Back Gate of the Third Chakra.

2. The front center point of the Middle Dantian is located at the Shanzhong CV-17 (Central Altar) point, on the middle of the sternum at the level of the fourth intercostal space. The name refers to the "place of worship" where the Shen resides. This area is sometimes known as the Front Gate of the Fourth Chakra.

   The back center point is located two inches up from the shoulder blades, at the Shendao GV-11 (Spirit Path) point located at the hollow between the fifth and sixth thoracic vertebrae. The name refers to the easy accessibility into the patient's Shen residence (within the Heart) through this particular area on the back. This area is sometimes known as the Back Gate of the Fourth Chakra.

3. The upper front point of the Middle Dantian is located at the Tiantu CV-22 (Heaven's Chimney) point, at the throat. The name refers to the visceral cavity area at the base of the throat responsible for "pooling" escaped Heaven Qi from the Lungs. This area is sometimes known as the Front Gate of the Fifth Chakra.

   The upper back point is located on the Dazhui GV-14 (Big Vertebra) point on the back. The name refers to the point's location below the seventh cervical vertebra and above the first thoracic vertebra. This area is sometimes known as the Back Gate of the Fifth Chakra.

4. The center of this Middle Dantian area is located in the right atrium of the heart, centered between the SA (sinoatrial) and the AV (atrioventricular) nodes. The center of the Heart is considered the seat of all emotions.

THE NINE CHAMBERS OF THE MIDDLE DANTIAN

The Middle Dantian regulates the body's Heart—Mind connection. The Heart-Mind connection includes both the all pervasive consciousness of the entire body and the Shen. It distributes the flow of Yuan Qi into the Yin and Yang aspects of the body's mental and emotional functions. These functions within the psyche are controlled by the interaction of the body's Wu Jing-Shen or Five Essence Spirits (Hun, Po, Zhi, Yi, and Shen). The energy of the Middle Dantian is also



Figure 5.3. The Nine Chambers of the Middle Dantian are identical for men and women. Each number encompasses the entire chamber.

associated with the Spleen and Stomach energies. The vertical thoracic set of nine chambers (Figure 5.3), located within the Middle Dantian, originate around the auricles and ventricles of the heart (especially the pericardial and pleural cavities). The Nine Chambers of the Middle Dantian are named as follows.

1. The Chamber of Mysterious Elixir
2. The Lower Court of the Heart
3. The Chamber of the Ultimate
4. The Chamber of Splendor
5. The Heaven's Cover
6. The Twelve Storied Chamber
7. The Chamber of Government
8. The Purple Chamber
9. The Heaven's Chimney

ENERGETIC FOCUS OF TRAINING THE MIDDLE DANTIAN

In Medical Qigong training the doctors encourage their students to focus their mind and breath on the Middle Dantian to regulate the Heart. Techniques are used for treating Deficient conditions by drawing Qi into the Heart and Middle Dantian area, then regulating the body's energetic fields. For treating Excess conditions, the students are encouraged to lead and purge the Excess Qi from the Heart and Middle Dantian area through the body's extremities. The purpose of this training is to release the toxic Excess Qi gathered in the patient's Heart and Yellow Court areas. These areas of Excess tend to cause disease.

THE UPPER FIELD OF ELIXIR

The Upper Dantian is the collector of Heaven Qi and represents the spiritual aspect of man and his connection to the divine. The Heaven energy that is transformed in the Upper Dantian is of a thinner more ethereal quality—like vapor.

The Upper Dantian is connected to the third level of Wei Qi, circulating several feet outside the body. As the Upper Dantian fills with Qi, the spiritual intuition and psychic perception of the individual increases.

In Chinese physiology, the brain controls memory, concentration, sight, hearing, touch, and smell. These senses stay in close communication with the Heart and Shen.

THE UPPER DANTIAN AND JING

The Jing and Qi form the material foundation for the Shen. In Chinese, the term Jing-Shen means mind or consciousness. Jing-Shen may also mean vigor, vitality, or drive. In China both Western and Chinese doctors use the term Jing-Shen Bing to refer to all types of mental illness. The term Shen is rarely used by itself in a medical context without the concept being connected to the close relationship between the power of the mind and spirit.

The term Wu Jing Shen is used in Medical Qigong to describe the body's Five Essence Spirits (Hun, Po, Zhi, Yi and Shen). These five spirits combine the energetic essence of the Five Yin Organs in order to create the body's innate spiritual consciousness.

The Jing itself is considered the basis for, and ruler of Marrow (a substance derived from the Kidneys that nourishes the brain, spinal cord and forms bone marrow). The brain, is one of the six Extraordinary Organs and is called The Sea of Marrow, and is considered to be a form of Marrow. The six Extraordinary Organs are hollow Yang organs that store Yin Jing. Deficiency of Jing may lead to poor concentration, poor memory, dizziness, and absentmindedness. Deficiency of Prenatal Jing is related to mental retardation and attention deficit disorder (ADD) in children.

In some styles of Qigong, the Jing is intentionally conserved and its energy is drawn upwards from the Lower Dantian through the spine to nourish the brain. Such nourishment benefits the mind and spiritual consciousness.

THE UPPER DANTIAN AND QI

The head is the most Yang part of the body since it is the closest part of the body to Heaven. The Qi that operates in the Upper Dantian is, therefore, Yang in nature. The Spleen and Kidneys send the Clear Yang Qi (pure, light, and insubstantial) upwards to the brain to facilitate mental clarity and activity.

The Upper Dantian is also the place where we connect with the Yang Qi of Heaven. Qigong practitioners consciously absorb Heavenly Qi through the upper doorway, Baihui GV-20. The Heaven Qi is composed of the Qi from the celestial bodies: the sun, moon, planets, and stars.

The Upper Dantian is located in the center of the brain, in an area that encompasses the pineal, pituitary, thalamus, and hypothalamus glands. The pineal gland and hypothalamus have been shown to be extremely sensitive to the influence of light. In his book, *The Body Electric*, Dr. Robert Becker cites experiments with bees and several species of birds that indicated that these animals navigate by the light of the sun. Birds have disproportionately large pineal glands. He also discovered that birds seem to have a backup system of navigation based upon a sensitivity to the electromagnetic fields of the earth.

There are three forms of Qi to which the brain responds and interacts: light, electricity, and magnetism. These particular forms of energy stimulate the pineal, pituitary, thalamus, and hypothalamus glands, affecting and influencing the emotional responses.

THE UPPER DANTIAN AND SHEN

We have already discussed the relationship of the Jing and the Shen with the Upper Dantian. Of particular interest to the alchemists is the opening of the center of the Upper Dantian, called the Crystal Room, where psychic perceptions and intuitive knowing take place. Higher communications, a sense of great bliss, and perceptions that transcend the seeming bonds of time and space are associated with the Upper Dantian. These experiences are particularly valuable to Qigong doctors, who use these heightened perceptions to diagnose illness. Their efficacy is well documented in the works of such authors as C. Norman Shealy and Caroline Myss, who use the term "medical intuitive" to describe this paranormal ability.

The Upper Dantian is also the place where the Eternal Soul connects with the Wuji, and with the Dao. The awareness associated with this union is beyond description, as its unity supersedes the differentiation inherent in conceptual thought.

Although the Upper Dantian is responsible for intuitive and psychic perceptions, the combined energetic properties of all three Dantians establishes the foundation for all psychic perceptions. The steam-like quality of the energy with the Upper Dantian fuses within the light now existing in this center. As this energy disperses, it travels out into the Wuji, returning back to the divine. This interaction is also responsible for what the Chinese call "receiving the message," which describes the ability of connecting with the patients' subtle energy field to acquire the hidden knowledge stored within the patients' tissues.

While in a state of tranquillity and inner peace, the Qigong doctors' Upper Dantian will also intuitively process information from the environment and universe. This intuitive knowledge provides Qigong doctors with a greater ability to explore both their own consciousness and the patients'. The ancients called this ability "knowing without knowing."

THE UPPER DANTIAN AND INTUITIVE COMMUNICATION

As the Shen is developed and the Upper Dantian is opened, spiritual communications may reveal themselves in a flash of an image or a vision in the mind's eye. These images and visions are sometimes very abstract and short lived. Interpreting images takes practice because the images streaming from the Yuan Shen cannot be interpreted easily by the logical mind.

The Qigong doctors must be able to distinguish between true and false messages reflected through their visions. True visions are received from the divine connection to the Dao or Wuji; false visions reflect the messages from the subconscious. The ability to accurately separate these visions is an another example of "knowing without knowing."

Although communication from within usually makes itself felt as a strong impulse, Qigong doctors must learn to keep the logical mind from interfering by practicing spiritual meditations. These meditations involve the forging of links in the chain of communication with the higher self. They should be practiced again and again until this connection becomes a natural, recurring phenomenon. The more one practices at stilling the logical mind and circumventing the ego, the easier it will be to get a clear communication from the higher self. When the higher self initiates a communication, it does not demand or impose itself, and if ignored it will usually stop sending signals.

Five Elements must be in place before the communication lines become fully open and operational:

1. Purity in intention,
2. No hidden agendas,
3. Surrender to the divine will,
4. Complete trust and faith in success (believe and expect), and
5. A quiet and receptive stillness of mind.

The lines of communication with the higher self are severed by the logical mind through doubt, fear, and disbelief. Strong faith is required to open this line of communication. Faith requires no logical proof; if proof is needed, then doubts interfere and breed failure. The logical mind cannot know absolute faith and, therefore, faith must come from deep within one's true self. Any form of cynicism will lead to the death of spiritual growth, for it strikes at the root of faith itself.

Faith is not something that can be forced. Even after practicing Medical Qigong for many years, Qigong doctors may still have to battle their own questions. However, through successful practice, the seed of faith is established, allowing it to grow and blossom. The opposite of faith is doubt combined with fear. Suppression and denial of fear builds and armors the ego, which leads to further pain. If the fears are accepted and acknowledged, they can be overcome by faith.

ANATOMICAL LOCATION OF THE UPPER DANTIAN

The Upper Dantian is located in the head, approximately three inches posterior to the Yintang point (between the eyebrows). It is shaped like a pyramid, facing upward to gather the energy from Heaven. This pyramidal reservoir houses light.

1. The front point of the Upper Dantian is the Yintang (Hall of Impression) point. The name refers to the ancient tradition of placing a red mark or "seal" over the Bright Hall, or Entrance of the Spirit, this point represents wisdom and enlightenment. This area is sometimes known as the Front Gate of the Sixth Chakra, or the Third Eye point.


Cerebral Veins
Corpus Callosum
Tian Men
Yin Tang
Front Sinus
Hypothalamus
Pituitary
Mamillary Body
GV-20
Falx Cerebri
Third Ventricle
Thalamus
Epithalamus (Pineal)
GV-16
Cerebellum
Occipital Sinus
Pons
Medulla
Spinal Cord
1
2
3
4
5
6
7
8
9

Figure 5.4. The Nine Chambers of the Upper Dantian are portrayed in this drawing. Each number encompasses the entire chamber.

2. The back point of the Upper Dantian is located below the external occipital protuberance, on the Fengfu GV-16 (Wind Palace) point. This area is also connected with and surrounded on both sides by the Bl-10 (Heavenly Pillar) point. The energy field connected to this point may be likened to an antennae receiving messages; it allows Qigong doctors to regulate their state of consciousness. The Governing Vessel 16 point is also a Sea of Marrow point, which is used to affect the flow of Qi and Blood to the brain, and a Window of Heaven Point (one of eleven points used for treating Shen disturbances), as well as one of the thirteen points identified by the famous Daoist physician Sun Simiao as a Ghost Point (points used for treating spirit possession). It has been my personal observation that students with a more prominent occipital protuberance tend to see auras more easily and receive psychic intuition faster. This area is sometimes known as the Back Gate of the Sixth Chakra.
3. The highest point of the Upper Dantian is lo-

cated on the vertex of the crown, on the Baihui GV-20 (One Hundred Meetings) point. The name refers to the ancient tradition that one receives divine messages and spiritual intuition from this point into the Upper Dantian's Chamber of Mysterious Elixir, located within the third ventricle of the brain. This area is sometimes known as the Upper Gate of the Taiji Pole or the Upper Gate of the Seventh Chakra.

It is also said in Traditional Chinese Medicine that all of the body's major channels send a connecting vessel to the Baihui so that at death the Qi can leave the body through this upper doorway and ascend to the Heavenly realms.

4. The center of the Upper Dantian is located in the pineal gland. It is the area where the Shen transcends and merges with the Wuji and then progresses on to the Dao. The Upper Dantian is also considered the house of spiritual (intuitive) communication, awareness, and feelings.

THE NINE CHAMBERS OF THE UPPER DANTIAN

The horizontal cephalic set of nine chambers, located within the Upper Dantian (Figure 5.4) is based on the different ventricles of the brain. The Nine Chambers of the Upper Dantian are named as follows.

1. The Chamber of Mysterious Elixir (Mystical Medicine)
2. The Palace of Jade Emperor
3. The Palace of Moving Pearls
4. The Chamber of Splendor
5. The Hall of the Upper Dantian (Medicine Field)
6. The Chamber of the Ultimate Truth
7. The Cover of Heaven (Palace of the Heavenly Court)
8. The Chamber of Government
9. The Entrance of the Spirit (Bright Hall)

ENERGETIC FOCUS OF THE UPPER DANTIAN

In Medical Qigong training, the Upper Dantian pertains to gathering spiritual intuition and light to advance the doctor's intuitive and psychic ability (see Six Transportations of Shen, Chapter 13).

The Qigong doctor may also absorb universal and environmental Qi into the Upper Dantian through the Yin Tang (Third Eye region) and the Tian Men areas (located in the center of the forehead), and emit healing Qi to patients through either one or both of these points. The Shen can both exit and enter the body from the area in the Upper Dantian by way of the Baihui, Yin Tang, and Tian Men (Heavenly Gate) areas.



Figure 5.5. Qi Dispersion From the Center Taiji Pole Through the Dantians into the Body

THE FUNCTIONAL ASPECTS OF THE THREE DANTIANS

The three energy reservoirs of the Dantians are linked externally through the Governing and Conception Vessels and internally through the Thrusting Vessels and the Taiji Pole.

The center of each Dantian is penetrated by and attached to the Taiji Pole, which exits from the Baihui at the top of the head to the Huiyin point at the perineum. Each of the Dantians corresponds to anatomical locations that are centers for magnetic and electrical vibration and charge. The body's intensity of vibration and charge is dependent on the mental intention, the posture, and the respiration.

Qi moves into the body's Dantians through the body's Taiji Pole. The energy is then absorbed into the body's major organs and surrounding tissues as it flows out of the Dantians and into the body's internal and external channels and collaterals.

Each Dantian acts like a reservoir, collecting energy and redistributing it into all of the internal organs. This energy projects through the surface of the body into the Wei Qi field. The same energy also projects inward flowing through the energy channels, along the nervous system and endocrine glands, and then through the Blood, to nourish the body (Figure 5.5).

You can visualize this energy transformation as follows: Qi flows into the body like rainwater flowing into a lake (the body absorbing and collecting Qi into the Dantians). The rainwater is then absorbed into the surrounding soil, foliage, and root systems (skin, tissues, and cells) before it gathers, collects, and pools into deep artesian wells (the Dantians). Pressure begins to build up as these artesian wells fill with the rainwater, and eventually overflow, pouring into smaller pools (the organs) before combining with the rushing action of underground streams (the channels).

Another popular analogy is to consider the Dantians as batteries, the body's Taiji Pole as a magnetic bar connecting the batteries together, the channels as the wires, and the Wei Qi fields as the electromagnetic fields manifesting from the energy contained within the structure.

Mental and emotional awareness of a specific tissue area can be heightened through increasing the flow of energy to that location. When energy fills the tissues, a cellular release of energy causes the tissues to either store or release emotions, depending on the body's overall Excess or Deficient Qi.

If an increase of Qi is focused into the Lower Dantian, the result is a more powerful and stable feeling in the body. When an increased amount of Qi is focused into the Middle Dantian, the result



Figure 5.6. The Three Dantians and Their Relationship to the Three External Wei Qi Fields

is a heightened feeling of emotional perception and awareness. If an increase of Qi is focused into the Upper Dantian, a heightened spiritual awareness and sense of connection to the divine occurs. The greater these energies flow, the healthier the individual becomes, and the stronger his or her energetic fields become (Figure 5.6).

THE DANTIAN'S YIN AND YANG ENERGETIC CHAMBERS

Each of the Three Dantians can be divided into Yin and Yang energetic chambers. The Yang chambers relate to each Dantian's upper chambers and the spiritual aspects of the Hun. The Yin chambers relate to each Dantian's lower chambers and the carnal aspects of the Po. The chambers and their energetic potential are described as follows.

THE LOWER DANTIAN

1. The Yang Energetic Chamber of the Lower Dantian relates physically to the upper quadrant of the abdomen, located within the small intestine in men and the uterus in women. When influenced by the Hun, quiescence and serenity are enhanced.
2. The Yin Energetic Chamber of the Lower Dantian relates physically to the lower quadrant of the abdomen, which includes the reproductive organs and the Bladder, urethra, and anus. This chamber is responsible for reproduction and sexuality. When influenced by the body's Po, raw physical power and sexual vitality are aroused.

THE MIDDLE DANTIAN

1. The Yang Energetic Chamber of the Middle Dantian relates physically to the upper quadrant of the Heart, which includes the left and right atrium, the upper portions of the left and right ventricles, and the atrioventricular node. This chamber is responsible for spiritual attitudes and virtues related to the influence of the body's Hun. The Hun are responsible for:
   - gathering and transmitting divine inspirations and spiritual insights,
   - giving and receiving unconditional love, and
   - motivating spiritual growth through prayer, devotion, and commitment.
2. The Yin Energetic Chamber of the Middle Dantian relates physically to the lower quadrant of the Heart, which includes the left and right ventricles. This chamber is responsible for sensual passions, conquests, and conditional love. It deals with actions which are often based on hidden agendas. These emotions are related to the influence of the body's Po. The influence of both the Po and the Yin Energetic Chamber of the Upper Dantian activates, energizes and enhances:
   - biological drives (for food and self preservation,
   - sexuality, lust and desire, and
   - sensuality.

THE UPPER DANTIAN

1. The Yang Energetic Chamber of the Upper Dantian relates physically to the upper quadrant of the brain, often referred to as the third ventricle or higher brain centers. When stimulated, the higher brain centers manifest spiritual intuition and divine insight, related to the influence of the Hun. Such insight is responsible for spiritual growth and maturation. Insights eventually lead to the emergence of extrasensory perceptions (ESP), e.g., clairvoyance, clairaudience, telepathy, psychokinesis, and spiritual enlightenment.
2. The Yin Energetic Chamber of the Upper Dantian relates physically to the lower quadrant of the brain, often referred to as the "reptilian" brain. When stimulated, the reptilian brain activates the thalamus, hypothalamus, cerebellum, and cortex, which awaken the body's intuition, as well as animalistic and primordial instincts of survival. When the Yin Energetic Chamber dominates, the sensory, animalistic nature of the Po emerges full force. This phenomenon sometimes occurs when coma patients begin to recover. As energy begins to fill the lower chambers of the Three Dantians, their initial reactions are basic and carnal in nature, i.e., to either engage in sexual activity or strike out in violence. As the Qi begins to fill the upper chambers of the Three Dantians, the energy balances in the patient's

Taiji Pole and the patients' impulses return to normal.

THE DOCTOR'S PROJECTED AURA FIELDS

In China, Qigong doctors are tested and categorized according to the predominant color of their Qi emissions. The healing color will depend upon which of the three Dantians is dominant (corresponding to either the Lower Dantian, Middle Dantian, or Upper Dantian), and the energetic strength and potential of the individual being tested. The emitted color is observed in the visible-light spectrum projected from the Qigong doctor's hands.

YELLOW EMITTED COLOR

Individuals who have just begun their training will emit a yellow glow around their external energy field. The Qi will naturally overflow from the Lower Dantian area and the color yellow will dominate the aura. This is actually a normal aura color observed from most beginning Qigong doctors, indicating that the energy field is still too weak to treat serious diseases.

RED EMITTED COLOR

Qigong doctors who have mastered their body and mind will emit a red radiant glow around their external energy field. The Qi will also overflow from the Lower Dantian area, and the color red will dominate the aura. This is actually a normal range of aura color observed from the many Qigong doctors who have just graduated from Medical Qigong colleges, indicating that the energy field is at the intermediate stage.

PURPLE EMITTED COLOR

Qigong doctors who have evolved to the next level of mastering the emotions will emit a purple radiant glow around their energy field. These doctors' Qi will naturally overflow from the Middle Dantian area, and the color purple will dominate the aura. This aura color is observed in strong and advanced Qigong doctors.

BLUE EMITTED COLOR

Qigong doctors who have further refined their energy will emit a blue radiant glow around their energy field. These doctors' Qi will also overflow from the Middle Dantian area, and the color blue will dominate the aura. This aura color is observed in very advance Qigong doctors, and is developed only after many years of clinical practice and personal spiritual transformations.

WHITE EMITTED COLOR

The Qigong doctors who have mastered their spiritual life, as well as surrendered their body, mind, emotions, and spirit to a divine or higher calling will emit a white radiant glow around their energy field. These doctors' Qi will naturally overflow from the Upper Dantian area, and the color of the aura is considered the strongest and most powerful.

CLEAR-OPALESCENT EMITTED COLOR

The divine energy is emitted through a clear-opalescent color. This Qi emission is different then the white radiant glow, and is a sign of divine intervention and healing. These times of divine intervention can occur in any stage of the doctor's energetic development, and are a testimony to the healing virtue of the divine.

Although every Qigong doctor uses a combination of all Three Dantians when projecting Qi into patients, the color of the aura surrounding the doctor's body reflects which Dantian's reservoir is predominantly used. Through time, patience, and much practice, the Qigong doctor will be able to transform from a yellow to red, purple, blue, and finally to white-light healer.

THE TAIJI POLE

The Taiji Pole can be observed as a vertical column (or pole) of brilliant white light, full of vibration and energetic pulsation. This energetic channel flows from the Baihui point at the top of the head, through the center core of the body, connecting the Three Dantians. The Taiji Pole roots its energy at the base of the perineum at the Huiyin area.

In Chinese energetic embryology, as the father's sperm enters the mother's egg, it creates the upper or Heavenly vortex point of the Taiji Pole. At this stage of energetic development, the Heavenly vortex creates and connects the Three

Dantians together, rooting the column of white light energy into the Kidneys and Mingmen area. As the fetus continues to grow and develop, the Taiji Pole slowly descends, shifting its energetic root to the base of the perineum. After birth, the Taiji Pole can be observed as a vertical column of brilliant white light, surrounded by a veil of golden spiraling light.

HEAVEN, EARTH, AND MAN RELATIONSHIPS

The Taiji Pole of the body is comparable to the central axis of the Earth, which is known as the Taiji Pole of the Earth. At the end of the Earth's Taiji Pole are the North and South Poles, which are compared to the body's Baihui at the top of the head and Huiyin at the base of the perineum. The Earth's Taiji Pole (or central axis) aligns to the North Star.

The North Star is seen as the Taiji Pole of Heaven and is sometimes called the Pole Star or Taiji. It is sometimes said that the original Chinese character for Taiji means Yin and Yang. While the original meaning of the Chinese character for Yin is the shady side of the mountain, and Yang depicts the sunny side of the mountain, the mountain's peak is considered a Taiji, where both Yin and Yang meet (or the center of Yin and Yang).

The center Taiji is also called the Still Point, because although all of the changes of Yin and Yang occur in the Heavens within the course of a day, and all of the stars seem to make a 360 degree rotation (as the Earth rotates) the Pole Star remains stationary as Heaven's Still Point. In a similar manner, the body has the Taiji Pole as the "still point of man." A great stillness is experienced when a Qigong practitioner gathers Qi into the Taiji Pole.

INTERNAL ENERGY INTERACTIONS

Extending from the body's Taiji Pole are the Three Dantians, Five Jing-Shen, and the Eight Extraordinary Vessels. These vital energetic systems feed all the major organs and the body's Twelve Primary Channels. As the Three Dantians absorb energy from the body's Taiji Pole, they also extend, or "feed," and energize the body's Yin and Yang organs, Twelve Primary Channels, and Eight Extraordinary Vessels. Each individual Dantian is connected to the body's Taiji Pole and is responsible for creating its own alchemical transition in the process of converting Jing into Qi, Qi into Shen, Shen into Wuji, and Wuji back to the Dao (see Chapter 13).

In my clinical experience, the closer I work to the patient's Taiji Pole the more powerful the energies become. Accessing the patient's Taiji Pole, Three Dantians, and Eight Extraordinary Vessels for whole body tonification and regulation is faster and less draining on my energetic reservoirs then emitting Qi into the patient's Twelve Primary Channels to accomplish the same type of treatment.

THE FIVE THRUSTING CHANNELS

Five internal Thrusting Channels connect to and transverse the body's center Taiji Pole. These five internal channels begin at the perineum and spiral up through the center of the body's core, flowing into the upper crown of the head. They connect the Baihui area at the top of the head to the Huiyin area at the bottom of the perineum. These five internal channels absorb the Five Elemental energies of Heaven and Earth (Wood, Fire, Metal, Earth, and Water) into the body.

The Taiji Pole is responsible for absorbing the energy from Heaven and Earth and distributing the collected Qi into the body's major internal organs. Similar to the Earth's central axis, the Taiji Pole is divided into two main energetic polarities: The Five Portals of the Heavenly Yang Gate, located at the top of the head, and the Five Portals of the Earthly Gate, located at the perineum (Figure 5.7).

When the body's internal and external energetic wave patterns become synchronized through prayer or meditation, a rhythmic pulsation occurs within the Taiji Pole. This pulse begins deep within the center core of the body and vibrates outward towards infinite space connecting the Wuji with the Dao.

SPIRITUAL MANIFESTATIONS

When doctors penetrate the outside veil surrounding the center core of a patient's Taiji Pole and extend their intention into the light's center, they experience the sensation of falling into space



Top of Head

Figure 5.7. The Five Portals of the Heavenly Yang Gate are portrayed here as seen looking down at the top of the head. The Universal Energy is absorbed into the Taiji Pole through the Five Portals of the Heavenly Yang Gates, located at the center of the Baihui (One Hundred Meetings) and Sishencong (Four Spirits Hearing) areas, at the top of the head.



The Five Portals of the Earthly Yin Gate as seen from the perineum. The environmental energy is absorbed into the Taiji Pole through the Five Portals of the Earthly Yin Gates, located at the center of the anal sphincter, between the Huiyin (Meeting of Yin) and the Changqiang (Long Strength) areas, at the base of the perineum.

or shooting through space. This sensation is followed by seeing flashing colors and moving shapes, as the surrounding core dissolves into infinite space itself. As the Qigong doctors continue to extend their intention to reach this area, time and space feels as if they stretch into eternity. This experience is considered the true connection with the Wuji returning back to the Dao. The potential for this experience exists within everyone and can be accessed through deep prayer and meditation. It is quite a normal phenomenon within deep spiritual practices and is sometimes known as accessing the river of God.

ENERGETICALLY OPENING THE TAIJI POLE

When we are born, we are connected to great spiritual wisdom and power through our center core. During the maturation process, this connection slowly fades away, yielding to masks and defense mechanisms, that seek to shield us from our pain and self-hatred (shame). In childhood, every time we repressed the flow of painful feelings connected to an event, we froze that particular event in both energy and time, and locked it within our muscles. Since the external Wei Qi is composed of energy consciousness, a block of frozen psychic energy is formed within the Wei Qi at the moment we inhibit the pain. By walling off our wounds, we also wall off our connection to our deeper core self (Figure 5.8). We pretend not to feel the pain anymore, we block off the memory of the event. Thus, we prevent a natural resolution to the pain and the trauma of the event. Through denying our true feelings we disconnect from our core self and put on masks. We smile when angry, for example, or pretend indifference to our hurts. Since creative inspiration comes from our core, we lose our creative ability. When we stop the negative experiences of anger, pain, or fear, we also stop the positive healing of the physical, mental, and emotional aspects of the experience.

During Medical Qigong treatments, patients regress layer by layer through the pain and fear associated with the blocked energy that gives rise to the disease. Even though the memories may be very strong and frightening, as the emotions



Figure 5.8. The True Self is Contained Within the Core Self

release, the pain decreases with the dispersal of the original trauma.

I have found in my clinical practice that most of the patients' pain comes not from the original trauma but from the unconscious belief system established to protect them from the original trauma. In other words, more pain and illness is created in our bodies by avoiding working through the original trauma (through our habitual defense and avoidance patterns) than was present in the original trauma. It requires enormous amounts of energy to suppress feelings, and each time we do so, we create further injuries to ourselves.

SPIRITUAL AWAKENING

When patients become aware of their spiritual connection to the divine, it is called an "awakening." This change can be observed through the spiritual transitions experienced within the patients' center core through their Taiji Pole. When the center Taiji Pole (which connects all three Dantians) begins to awaken, certain physical, emotional, and energetic reactions may occur within the patients' body. These transformations occur because the tissues of the energetic fascia (that connect to the major organs of the body) are enveloped within the energetic structure and webbing of the Taiji Pole.

THE TWELVE GATES OF THE CHAKRA SYSTEM

Although the body's major internal energy centers are contained within the interacting network of the Three Dantians, the Three Dantians also connect to the body's major energy doors (located on the Governing and Conception Vessels), known as the Twelve Gates of the Chakras. These Chakra gates are superficial, on the surface of the skin, and are not as deep as the Chakra Cores and Three Dantians which are all connected to the Taiji Pole (Figure 5.9).

The word Chakra is Sanskrit for "wheel." The Chakras look like small, colored disks, usually about the size of a silver dollar. Energetically the Chakra gates look like funnels or vortices of Qi. Qigong doctors and sages have for centuries described their perceptions of these gates as resembling energetic wheels or vortexes within the subtle energy body. Each funnel extends and expands its energetic vortex out into the body's Wei Qi field. As energy travels up and down the Taiji Pole it creates an energetic pulse. This energetic pulse resonates out from the body through the Twelve Chakra Gates, and can be felt several feet from the body. The bottom Chakra is located at the perineum and only has one gate, as does the top Chakra located at the top of the head; the second, third, forth, fifth, and sixth Chakras have two gates each, one on the front of the body and the other on the back of the body. These Chakra Gates serve the following different energetic functions:

1. The top or Crown Chakra gate is responsible for absorbing Heavenly Qi and light into the body, as well as energizing the center core's Taiji Pole.
2. The front Chakra gates are responsible for the patient's feelings and emotional activity. They are related to the patient's Shen and the Heart Fire energy. They are connected to the Conception Vessel.
3. The back Chakra gates are responsible for the patient's willpower and determination. They are related to the patient's Zhi and the Kidney Water energy. They are connected to the Governing Vessel.



Figure 5.9. The body's Twelve Chakras Gates extend from the Taiji Pole and expand outward into the three external Wei Qi fields.

4. The center of the Chakras are actually deep inside the body's center core, located within the middle of the Taiji Pole.
5. The bottom or Base Chakra gate is responsible for absorbing Earthly Qi and heat into the body, as well as energizing the Taiji Pole. Generally, when treating a patient, the Qigong

doctor extends energy into the patient's back Chakra gates to stabilize the emotions and to access control over the patient's will and determination. The doctor can, for example, connect with the Heart Chakra back gate, located on the patient's Shendao, GV-11 point, to access the emotions stored within the tissues of the Heart. The front Chakra gates are used to remove Excess emotions from the patient's tissues. Although the treatment approach differs, the Three Dantians system and Twelve Chakra Gate system, mutually support each other, both in the location of the energy centers, and in their physical manifestations of energetic function.

The Yin and Yang polarity of the Chakra gates are opposite in men and women (Figure 5.10). The Twelve Chakra Gates serve as subtle energy distributors, that help absorb and distribute environmental Qi to the patient's organs, tissues, and major nerve plexus areas closest to each gate. Each Chakra gate is connected to its own potential of psychic perception, interfaces with the body's nervous system, and is associated with a different endocrine gland. Any energy extended from the Qigong doctor towards a patient's Chakra gate will affect the patient's physical body. As the patient begins to energetically open the Chakra gates, the external energetic Chakra wheels begin to spin in half-circle rotations, opening and closing with the core's energetic pulse. The energetic action is similar to the centripetal (closing) and centrifugal (opening) action of the body's energetic channels.

Each opening of a Chakra gate may result in a spontaneous emotional release. Some of these releases can involve painful memories that have been dislodged from the energetic filter (or veil) that envelops the Chakra gates. This energetic filter prevents external emotional traumas from entering into the body's center core.

A Chakra gate can become stuck open, closed, or may also tilt out of alignment with the Taiji Pole, causing Qi Deviations that may result in a distorted or obstructed flow of energy. This obstruction may cause physical, as well as psychological, stress or trauma. The release of these emotional

Polarity		
Chakra	**Men**	**Women**
7th	+ Yang	– Yin
6th	– Yin	+ Yang
5th	+ Yang	– Yin
4th	– Yin	+ Yang
3rd	+ Yang	– Yin
2nd	– Yin	+ Yang
1st	+ Yang	– Yin

Figure 5.10. The energetic Yin and Yang polarity of the Chakra Gates are opposite in men and women. The Chakra Gates of a man start from a Yang (+) energetic field (at the Lower Chakra Gate) and change to Yin (-) at the second Chakra Gate, alternating from Yang to Yin up the body, ending at Yang in the Upper Chakra Gate. Women display the opposite energetic polarity in each Chakra Gate.


Crown Chakra Area
Pituitary
Pineal
Thyroid Parathyroid
Lungs
Thymus
Heart
Adrenals
Pancreas
Spleen
Liver
Kidneys
Ovaries
Testes
Testes or Adrenals (varies depending on the energy system)
6th Chakra Area
5th Chakra Area
4th Chakra Area
3rd Chakra Area
2nd Chakra Area
1st Chakra Area
Cerebral Cortex
Carotid Plexus
Pharyngeal Plexus
Pulmonary & Cardiac Plexus
Solar Plexus
Sacral Plexus
Coccygeal Plexus

Figure 5.11. The body's Chakra system is connected by the Taiji Pole and extends outward into the body's nerve plexus, affecting the glandular system and both anterior and posterior external energetic fields.

traumas can be overwhelming and painful if the patient has not prepared for, or does not understand the nature of, these transitional energetic malfunctions. These manifestations usually occur when the patient's system has been energized and the body is actively seeking to release and get rid of toxic emotions from certain areas. Qigong doctors should be aware of these strong emotional reactions to assist their patients in facing and working through their fears and pain as the Qi Deviations along the Taiji Pole are corrected. Sometimes these experiences unwind at a rapid rate, stimulating the patient's central and anterior nervous system; this can release a flood of mental and emotional images and sensations, that are sometimes accompanied by shaking, thrashing, and other unusual movements of the body (Figure 5.11).

THE BOTTOM CHAKRA GATE

The bottom or first Chakra gate is sometimes called the Meeting of Yin (referring to the Earth energy), and is located near the perineum, in front of the anal sphincter on the Huiyin CV-1 point. This energy center controls the reproductive system and the urogenital organs and intersects with the Bladder and Kidney Channels. It is associated with survival instincts (the "fight or flight" response), security, tribal power (group acceptance), and the "grounding" or "rooting" of the body.

The first Chakra is associated with the Lower Dantian. Its energetic elemental nature relates to Earth, and its color is red. It connects to the Taiji Pole at the base of the perineum and exits at the top, or Crown Chakra.

The bottom Chakra is associated with the kinesthetic, tactile, and proprioceptive senses. It supplies energy to the spinal column, adrenal glands (in some systems), testicles/ovaries, and Kidneys. This Chakra gate is also connected to both the Conception and Governing Vessels.

The bottom Chakra gate will immediately open in any emergency situation, or when there is danger, to release stored information to ensure survival. Energetic malfunctions caused by stored emotional trauma in this Chakra can cause a massive amount of fear for one's life to be released. The retention of massive amounts of fear, or the sudden energetic release of panic, can cause the following symptoms: lower back pain, sciatica, constipation, hemorrhoids, rectal tumors and cancer, knee problems, and varicose veins.

THE SECOND CHAKRA GATES

The second Chakra core can be accessed through two energetic gates. The front gate is sometimes called the Spirit's Palace Gate and is located at the navel around the Shenque CV-8 point. The back gate is sometimes called the Gate of Life and is located on the lower back at the Mingmen GV-4 point.

This second energetic area is considered the "gateway of the Lower Dantian." Its energetic elemental nature relates to Water, and its color is orange. It is the energy center through which other people's emotions are perceived (kinesthetic perception), allowing one to be sensitive to other people and to sense dangerous situations.

The second Chakra is the energy center for sexuality, sensuality, the hunger for power, and financial issues. It supplies the sexual organs (ovaries and testicles) and the immune system with energy.

When the second Chakra gate opens the patient feels the release of sexual desires, waves of orgasm, and sexual fantasy. Because this area is also associated with the desire for power, sometimes the desire to destroy is released. Energetic malfunctions caused by stored emotional trauma in this Chakra can cause lower back problems, frigidity or impotence. Second Chakra dysfunction can also cause Kidney, uterine, Bladder, and urinary problems.

THE THIRD CHAKRA GATES

The third Chakra core can be accessed through two energetic gates. The front gate is sometimes called the Solar Plexus Center, in this system of Chakra diagnosis it is located between the navel and the xiphoid process (at the level of the pancreas), at the Zhongwan CV-12 (Middle Stomach Cavity) point. The back gate is called the Middle of the Spine and is located on the middle of the back at the Jizhong GV-6 point.

The third Chakra area is associated with the Middle Dantian and is known as the Yellow Court in Medical Qigong therapy. Its energetic elemental nature relates to Fire, and its color is yellow. It is the body's distribution point for psychic energies (gut instinct and intuition), personal power, and self-image. It is the area where the body's Qi transforms into Shen. It is also a storage chamber for severe emotional pain and anger.

This area supplies energy to the Liver, Gall Bladder, Stomach, Spleen, pancreas, adrenal glands, and nervous system. The third Chakra is the center for personal power-storing issues of responsibility, self-esteem, personal honor, and fear of rejection.

When the third charka's energy gates open, feelings of power and waves of anger, rage, fear, greed, jealousy, judgment, and criticism can be released. Energetic malfunctions caused by stored emotional trauma in this Chakra area can cause ulcers, hypoglycemia and diabetes, as well as Liver and / or adrenal problems.

THE FOURTH CHAKRA GATES

The fourth Chakra core can be accessed through two energetic gates. The front gate is sometimes called the Heart Center and is located at the center of the breastbone, at the Shangzhong CV-17 point. The back gate is sometimes called the Spirit Path and is located on the Shendao GV-11 point on the back, between the scapula.

The fourth Chakra area is associated with the Middle Dantian. Its energetic elemental nature relates to Wind, and its color is green. This energy center is associated with love, compassion, empathy, clairsentience, and intuition. This area supplies energy to the Heart, Lungs, circulatory system, thymus gland, vagus nerve, diaphragm, and upper back.

When this energy center opens, it can be physically painful (the patient may experience feelings of a weight on the chest, heart attack sensations, or the release of tears) as the patient becomes aware of being attached to the personal ego. The feelings associated with the fourth Chakra have to do with our internal world, while feelings associated with the third Chakra have to do with the external world. Energetic malfunctions can cause Heart and Lung diseases.

THE FIFTH CHAKRA GATES

The fifth Chakra core can be accessed through two energetic gates. The front gate is sometimes called the Throat Center and is located just above the hollow of the throat, at the Tiantu CV-22 point. The back gate is sometimes called the Big Vertebra and is located on the back, at the base of the neck on the Dazhui GV-14 point.

This energy center is associated with sound vibration, personal and divine will, and communication. The fifth Chakra area is associated with the Middle Dantian. Its energetic elemental nature relates to sound, and its color is bright blue. It is the center for psychic clairaudience, and the power source for the Qigong doctor's "inner voice" guidance. This area supplies energy to the throat, thyroid and parathyroid glands, neck vertebrae, mouth, Lungs, and alimentary canal (the digestive tube from the mouth to the anus).

When the fifth Chakra energetic center opens, a compulsive urge to sing and chant arises. This area is also where Heat from the Liver Fire sometimes becomes entangled with Phlegm (a viscid substance that is a product and a cause of disease) from the Lungs, forming what is known as "plum pit Qi" (an energetic knot within the throat). Energetic malfunctions caused by stored emotional trauma in this Chakra area can cause stiff neck, sore throat, throat "plum pit Qi" symptom, thyroid problems and swollen glands. The patient sometimes experiences a release of unexpressed grief and anger, resulting in the physical reactions of excessive swallowing, coughing, or laryngitis.

THE SIXTH CHAKRA GATES

The sixth Chakra core can be accessed through two energetic gates. The front gate is sometimes called the Third-Eye Center and is located at the middle of the forehead at the Yintang or Hall of Impression point. The back gate is located on the back of the head, between GV-16 (Wind Palace) and GV-17 (Brain's Door), at the external occipital protuberance.

The sixth Chakra area is the center for psychic intuition, clairvoyant seeing (inner vision), and energy projection. The sixth Chakra area is associated with the Upper Dantian. Its energetic elemental nature relates to light, and its color is indigo (deep violet blue). This area of the body is responsible for enabling the Qigong doctor to see auras, Chakras, and other energetic images. This center is also responsible for mental telepathy, allowing the doctor to sometimes know the patient's thoughts and feelings. This area of the body supplies energy to the pituitary gland, lower brain, ears, nose, eyes, and nervous system.

When the sixth Chakra energy center opens, energetic malfunctions can result in headaches, eye strain, pain around the eyes, distorted or blurred vision, and sometimes blindness. Inaccurate interpretations of events, projections of personal fears and other emotions and motivations onto others may sometimes occur. Reoccurring nightmares and misguided fantasies may also be incurred.


(Noon)
Wu
Descent of Yin
(Purification Phase)
Wei
Si
Ch'en
Shen
(Sunrise)
Mao
You
(Sunset)
Yin
Xu
Ch'ou
Hai
Ascent of Yang
(Cleansing Phase)
Zi
(Midnight)

Figure 5.12. This figure shows the Twelve Earthly Branch Relation to the Twelve Chakra Gates. The Governing and Conception Vessels flowing through the middle of the back and front of the body correspond to the ecliptic path of the sun along the Twelve Chakra Gates, and are related to the Twelve Earthly Branches.

THE UPPER CHAKRA GATE

The upper or top Chakra gate is sometimes called the Crown Center and is located on top of the head at the Baihui GV-20 point. This energy center is associated with higher knowledge, understanding, pure intuition, and ecstasy. The upper Chakra area is associated with the Upper Dantian. Its energetic elemental nature relates to infinite space (Wuji), and its color is violet. This area supplies energy to the pineal gland and upper brain.

When the upper Chakra energetic center opens, it is like a golden flower opening, accompanied by a dazzling bright light and a strong, powerful connection with the divine. Energetic malfunctions result in confusion, apathy, alienation, boredom, depression, and a state of incomprehension.

TAKING PRECAUTIONS

When any of the energetic reactions to opening the Chakra gates take place, it is important for the student or patient to realize that these are only transitional stages and are normal phenomena which occur as a sign of energetic and spiritual transformations. The student or patient should take certain precautions, however, like being under the care of a qualified Qigong doctor when beginning any type of energy training.

It is also important not to allow patients to experience these emotional transitions alone. Because these energy transitions, malfunctions, and deviations are new to the Western mode of thinking, they can easily be misdiagnosed by doctors unfamiliar with energetic medicine. Patients should be encouraged to find or establish a support group consisting of advanced practitioners of energetic meditation. Having a support group of experienced practitioners allows these emotional and spiritual transitions to occur in a safe environment, where other experienced practitioners can monitor the patient's feelings, if and when, unfamiliar emotions start to emerge.

THE TWELVE EARTHLY BRANCHES AND THE TWELVE CHAKRA GATES

The body is viewed as a small and complete universe unto itself. The internal organs are influenced by the celestial movements of the sun, moon, planets, and stars. The Governing and Conception Vessels, where the Twelve Chakra Gates are located, are also affected by the Heavenly cycles.

In ancient China, the day was divided into twelve separate time divisions. Each time division corresponds to two hours of the day and was named after one of the Twelve Earthly Branches. These twelve time divisions were further organized into months and seasons (see Chapter 11). The ancient Qigong doctors discovered that the body's Qi and Blood mirror the Earth's seasonal ebb and flow, rising and falling like the lunar tides.

Each of the time periods corresponding to the Twelve Earthly Branches is regarded as having a specific influence on each of the Twelve Gates of the body's Chakra system. The rhythmic variations of the waxing and waning of Qi and Blood is associated to the waxing and waning of Yin and Yang energy, as well as the circulation of Qi following the Microcosmic Orbit (Fire) cycle.

Each of the Twelve Chakra Gates relates to one of the Twelve Earthly Branches following the Microcosmic Orbit (Fire) cycle (see Chapter 41). These Twelve Chakras Gates extend their energy from the patient's Taiji Pole outward, along the center of the body, through the anterior and posterior fields of Qi. Beginning at the bottom Chakra gate (the "Zi" Branch, representing midnight), the energy follows the Fire Cycle of the Microcosmic Orbit, traveling up the Governing Vessel, following the "ascent of Yang." After the Yang Qi reaches its peak, the Yin begins to grow. Starting at the upper Chakra gate (the Wu Branch, representing noon time), the energy travels down the Conception Vessel, following the "descent of Yin" (Figure 5.12).

CHAPTER 6
THE TWELVE PRIMARY CHANNELS AND ORGANS

INTRODUCTION

According to Traditional Chinese Medicine, a system of channels exists that integrates all the body's separate parts and functions into a unified organism. The understanding of these channels and their energetic function and interactions provides the Qigong doctor with the basis for understanding the relationships among the various physiological, pathological, diagnostic, and therapeutic relationships in Traditional Chinese Medicine.

The study of Chinese medicine rests on, and is inspired by, the circulation of Qi, as many diseases follow a predictable course of development. The pathology in an internal organ will often manifest itself in certain external or systemic symptoms; therefore, understanding the circulation of Qi flow allows the doctor to control each organ's energetic function. By stimulating specific sites on the body's surface, diseases in both the superficial tissues and internal organs can be treated.

A doctor of Medical Qigong uses various techniques that facilitate the opening of the major energetic connectors of the body's internal organs. These connectors, called channels and vessels, are responsible for connecting the flow of Qi within the whole body to transfer Qi both internally and externally.

The channels are also known as meridians or Jing-luo. The Chinese character for this type of Jing means "to move through," while the translation of the character luo means "a net" (the body's inner fascia). Along these channels are major trunks and lesser branches that connect internally with the vital organs and externally with the major channels, limbs, sensory organs, and orifices.

The smaller branches are known as collaterals. The tiny areas along these channels and collaterals where the Qi pools are called points. These points are the spots where the patient's spirit and energy enter and leave the body. When stimulated, these channel points (sometimes also called "acupuncture points"), cause an energetic response from within the internal organs and channels, resulting in internal Qi flowing from organ to channel, from channel to channel, or from point to point along the same channel.

The channels unite the body as one unit. Channel theory is interrelated with organ theory. Traditionally, the internal organs have never been regarded as simply independent anatomical entities. Rather, Traditional Chinese Medicine focuses on the functional and pathological interrelationships between the channel network and the organs. The internal organs and their systems are sometimes known as "orbs" or "spheres of influence."

Qi travels throughout the physical body along the channels and collaterals much as water flows through rivers and streams. An ancient Chinese medical text explains this concept as follows: "Heaven is covered with the constellations, Earth with the waterways, and man with channels." Qigong doctors of ancient China paid much more attention to the Body Fluids and energies circulating through the body than to the physical anatomical structures. The ancient Chinese considered the Body's Fluids and energies much more fundamental.

The channels serve as the link between the energies, such as Jing, Qi, Shen, and the ingredients, such as Blood and Body Fluids, that feed and enliven the tissues. The human body's main energetic rivers are the Twelve Primary Channels and Eight Extraordinary Vessels (see Chapter 7).

CLASSIFICATION OF CHANNELS

The channels are classified into four main categories: Jing, Luo, Muscle Tendon, and Skin Zones.

1. The Jing Channels are the Primary Channels. These channels include the Eight Extraordinary Vessels, the Twelve Primary Channels, and the Twelve Divergent Channels.
2. The Luo Channels are the Collaterals. These collaterals include the Fifteen Major Collaterals, the Minute Collaterals, and the Superficial Collaterals.
3. The Muscle/Tendon Channels consist of twelve channels that serve as external connections to the major channels, flowing through the body's muscles, tendons, and ligaments.
4. The Cutaneous Regions are skin zone areas where the channels surface on the external tissues.

JING CHANNELS

The Jing Channels are the major trunks of the circulatory tree. They generally flow vertically through the body through relatively deep tissues. They also transverse the limbs peripherally and penetrate the body cavities to connect with the internal organs (Figure 6.1). They are the body's main interior and exterior rivers of Qi.

1. The Eight Extraordinary Vessels connect with, and regulate, the Qi and Blood of the Twelve Primary Channels by either absorbing any energetic "runoff" in times of channel Excess, or by replenishing energy in times of Deficiency.
2. The Twelve Primary Channels are bilateral and symmetrical. They can be identified in three specific ways: (1) according to the corresponding Yin or Yang organ to which they are connected, (2) by the arms or legs in which the channels originate or end, and (3) according to the six divisions of Yin or Yang Qi to which the channels relate (i.e., Tai Yang, Yang Ming, Shao Yang, Tai Yin, Shao Yin, and Jue Yin).

   The Yin channels run along the medial and anterior aspects of the body. They are associated with the solid Yin organs and connect with the hollow Yang organs. The Yin channels include the Kidneys, Spleen, and Liver Channels that flow from the feet to the torso, a well as the Heart, Pericardium, and Lung Channels that flow from the torso to the hands.

   The Yang channels run along the lateral aspect of the body. They belong to the hollow Yang organs and connect with the solid Yin organs. The Yang channels include the Small Intestine, Triple Burners, and Large Intestine Channels that flow from the hands to the head, as well as the Bladder Gall Bladder and Stomach Channels that flow from the head to the feet. The interaction between the internal/external, Yin/Yang relationship of the organs and channels results in an alchemical transference between energy and matter.
3. The Twelve Divergent Channels branch off the Twelve Primary Channels. They are mainly distributed on the chest, abdomen, and head. The Divergent channels have the energetic functions of connecting internally and externally related channels, strengthening the connection of the Twelve Primary Channels to their related organs, and serving as extensions of the Twelve Primary Channels.

LUO OR COLLATERALS

The Twelve Primary Channels are connected by collaterals, which are small, interlinking streams. These collaterals are the connecting branches of the energetic circulatory system. They generally flow superficially, in horizontal and vertical energetic directions. They are the body's secondary streams of Qi that form an intricate network that traverses the body's surface and interconnects the main rivers, connective tissues, and cutaneous regions (Skin Zones).

1. The Fifteen Major Collaterals (Luo) transfer Qi and Blood from the Twelve Primary Channels to all parts of the body and link the body's interior with its exterior, connecting the body's internal and superficial channels, as well as the Governing and Conception Vessels and the Great Luo of the Spleen (see Chapter 7).


Divine Energy
(Descent of the Soul)
Yang Heavenly Energy
(Universal Energy: Sun, Moon, Stars)
Yin Earthly Energy
(Environmental Energy: Earth, Wind, Water)
Mother's Substance
(Egg: Essence, Energy, Spirit)
Father's Substance
(Sperm: Essence, Energy, Spirit)
The four energies combine and attract the Soul. The center of the energies becomes the Taiji Pole.
Upper Dantian
(Field of Light)
Middle Dantian
(Field of Vibration)
Lower Dantian
(Field of Heat)
3 Dantians
(3 Fields of Energetic Elixir)
9 Channels
(In each Dantian—Taiji Pole is center chamber)
9 Stars
(Taiji Pole + 8 Extraordinary Vessels)
Taiji Pole
(Center Core of Light)
Qi overflows when in excess
Qi moves to strengthen
10 Heavenly Stems
(10 Energetic Pools)
5 Yin Organs
Liver
Heart
Spleen
Lungs
Kidneys
5 Yang Organs
Gall Bladder
Small Intestine
Stomach
Large Intestine
Bladder
Qi overflows when in excess
Qi moves to strengthen
Qi overflows when in excess
Qi moves to strengthen
6 Arm Channels
3 Yin Channels
Lungs
Pericardium
Heart
3 Yang Channels
Large Intestine
Triple Burners
Small Intestine
Qi moves to strengthen
Qi overflows when in excess
8 Extraordinary Vessels
(8 Energetic Reservoirs)
12 Earthly Branches
(12 Primary Channels or 12 Energetic Rivers)
6 Leg Channels
3 Yin Channels
Spleen
Liver
Kidneys
3 Yang Channels
Stomach
Gall Bladder
Bladder
Conception
Thrusting
Yin Linking
Yin Heel
4 Yin Vessels
Governing
Belt
Yang Linking
Yang Heel
4 Yang Vessels
12 Earthly Branches branch into and flow alongside
12 Earthly Branches flow under skin zones and are absorbed into muscles and tendons
12 Earthly Branches come to the skin surface
Provide connections between the 12 Earthly Branches
12 Divergent Channels
(12 Secondary Rivers)
12 Muscle/Tendon Channels
12 Skin Zones
(12 Dermal Segmentations)
15 Collaterals
(15 Connecting Streams)

Figure 6.1. Channel and Organ Energy Flow



Figure 6.2. The Human Body's Energetic Matrix

2. The Minute Collaterals are smaller branches of the Fifteen Major Collaterals. They are countless in number.
3. The Superficial Collaterals are smaller branches of the Minute Collaterals. They are also countless in number.

MUSCLE TENDON CHANNELS

The Twelve Muscle / Tendon Channels are the external connections of the major channels. They generally flow superficially, traversing the body's surface and serve to join the main rivers, connective tissues, and Cutaneous Regions. The Twelve Muscle / Tendon Channels are also regions of the body where the Qi and Blood of the Twelve Primary Channels nourish the muscles, tendons, and ligaments.

CUTANEOUS REGIONS

The Twelve Cutaneous Regions (also called Twelve Skin Zones) are areas of the body where the Blood and Qi of the Twelve Primary Channels surface and connect to the body's skin tissues. These cutaneous regions have a continuous and direct contact with the external environment.

The body resonates in a continuous interplay of Yin and Yang harmony, balancing the channels' and organs' energy flows. The channels help create the body's external Yin and Yang polarities and create the energetic matrices around which the body's energetic fields can flow. Together these energetic matrices establish the foundation of the body's energetic tissues (Figure 6.2).

THE CHANNELS' RELATIONSHIP TO QI AND BLOOD

The channels transport Qi and Blood to nourish, moisten, and vitalize the whole body. Healthy bodily function depends on the balanced circulation of Qi and Blood. Qi is Yang and provides the energy or force necessary for the body's functional activity (i.e., movement and transportation, warming, containing, transforming, and defending). Blood is Yin and is the source of the body's moistening, nourishment, and lubrication.

The Blood, Qi, and heat circulate through the Twelve Primary Channels every two-hours, ebbing and peaking in energetic flow. The maximum peak of a channel's Qi, or "high-tide," occurs at the time of day when the Qi in that channel is at its fullest. The minimum period of a channel's Qi, or "low tide," occurs twelve hours from the peak time (Figure 6.3).



Figure 6.3. The Body's High and Low Energetic Tides

The connective tissues of the body's fasciae transmit a variety of biological energies. Think of the inner fascia as lubricated linings that cover the muscles and internal organs, allowing the tissues to slide and move easily. Within the lining of the superficial fasciae, the channels are webbed; this webbed network conducts energy in the form of electron, proton, and ion transmission, and is influenced by light and sound.

According to Traditional Chinese Medicine theory, each of the Twelve Primary Channels has its own individual resources of Qi and Blood; however, the energetic quality varies in accordance with the amount of Blood and Qi available in each organ and its particular channels. From a traditional Chinese medical perspective, the Spleen plays two important roles in regard to Qi and Blood. First, it converts food into Gu Qi which, when further refined by the Liver and Kidneys, becomes Ying (Nutritive) Qi; and second, it manages the Blood by keeping it in the channels. Ying Qi secretes Body Fluids that enter into the blood vessels and are transformed into Blood by the Heart. The Heart both creates and governs the Blood; whereas, the Liver stores it and spreads Qi throughout the body. Blood is considered to be a denser, more material form of Qi. Qi and Blood

Organs & Channels	Qi	Blood
Liver	less	more
Lungs	more	less
Large Intestine	balanced	balanced
Stomach	balanced	balanced
Spleen	more	less
Heart	more	less
Small Intestine	less	more
Bladder	less	more
Kidney	more	less
Pericardium	less	more
Triple Burners	more	less
Gall Bladder	more	less

Figure 6.4. The Body's Organ and Channel Relationship to the Proportions of Qi to Blood

are interdependent: Qi moves the Blood, but the Blood nourishes Qi; both flow together.

The chart in Figure 6.4 shows each of the Twelve Primary Channels and the proportion of Qi and Blood each channel carries.

FUNCTION OF THE CHANNELS

The channels are responsible for responding to any malfunction in the body. They can also, however, be disseminators of energetic dysfunction and disease. Disease passes in to the internal organs, or from one organ to another, via the channels. Exogenous diseases progress from the body's skin pores to the tiny collaterals, then to primary channels, and finally, to the internal organs. The channels are affected by disease in a predictable fashion.

1. Diseases and symptoms manifest along the channel pathway.
2. Points along the channels become tender, painful, tight, or flaccid.
3. When in a deficient state, the electrical resistance and heat tolerance diminish on the skin at the diseased point(s).
4. The body's sensory organs (sight, smell, taste, hearing and touch) are affected through channel relationship.

From a traditional Chinese medical perspective, the functions and flow of the channels and collaterals, as well as the internal organs' health can be affected by Medical Qigong, acupuncture, Chinese massage, and herbal medicine. Each system of Traditional Chinese Medicine disperses Excess, moves stagnation, stimulates and nourishing the Qi to tonify Deficiency, and stimulates the Wei Qi to fight External pathogens via the channels. In fact, each time the body's channels and collaterals are trained or regulated, they become thicker with Qi.

INTERNAL AND EXTERNAL CHANNEL FLOW

As the Qi of an internal channel flows into or out from its "primary organ," it generates a current that is similar to a river rushing back into the sea. The moment that energy flowing through the internal channel permeates the primary organ, an energetic connection and reaction is immediately created in the organ tissues. When the Qi of an internal channel flows into its "associated organ," however, the energetic reaction is quite different. Instead of immediately permeating the organ, the channel's energy "spirally wraps" the organ's tissues through the internal fascia that envelops the associated organ. The associated organ tissues then absorb the energy from the surrounding fascia. This difference in energetic penetration and absorption rate is an important factor when working with the body's internal energetic channels. When Qigong doctors extend their energy into a patient's channels, they must be aware that the absorption rate will be immediately felt in the channels pertaining organ, and will have a gradual effect on the organ's associated organ.

Channel Name	Yin or Yang	Associated Organ	Element	Blood Heat Cycle	Qi Blood Cycle	Abbreviation
Gall Bladder	Yang	Liver	Wood	11 p.m.– 1 a.m.	more Qi less Blood	G.B.
Liver	Yin	Gall Bladder	Wood	1 a.m.– 3 a.m.	less Qi more Blood	Liv.
Lungs	Yin	Large Intestine	Metal	3 a.m.– 5 a.m.	more Qi less Blood	Lu.
Large Intestine	Yang	Lung	Metal	5 a.m.– 7 a.m.	balanced Qi and Blood	L.I.
Stomach	Yang	Spleen	Earth	7 a.m.– 9 a.m.	balanced Qi and Blood	St.
Spleen	Yin	Stomach	Earth	9 a.m.– 11 a.m.	more Qi less Blood	Sp.
Heart	Yin	Small Intestine	Fire	11 a.m.– 1 pm.	more Qi less Blood	H.
Small Intestine	Yang	Heart	Fire	1 p.m.– 3 p.m.	less Qi more Blood	S.I.
Bladder	Yang	Kidney	Water	3 p.m.– 5 p.m.	less Qi more Blood	Bl.
Kidney	Yin	Bladder	Water	5 p.m.– 7 p.m.	more Qi less Blood	K. or Kid.
Pericardium	Yin	Triple Burner	Fire	7 p.m.– 9 p.m.	less Qi more Blood	P.
Triple Burner	Yang	Pericardium	Fire	9 p.m.– 11 p.m.	more Qi less Blood	T.B.

Figure 6.5. The Twelve Primary Channels are divided into Yin and Yang. The Yin channels are connected to the solid organs, and the Yang channels are connected to the hollow organs.

ORGAN AND CHANNEL FUNDAMENTALS

The purpose for energetic anatomy and physiology is to understand the fundamental actions of each organ and each channel's unique energetic characteristics. This understanding includes the learning of differential diagnosis to categorize the various symptoms into meaningful patterns of disharmony. This ability to categorize the various symptoms will enable the doctor to analyze and recognize specific pathologies indigenous to specific organs and channel energies (Figure 6.5).

In Chinese medical science, the study of energetic physiology is called Zhang Xiang Xue Shou, which literally translates as "the theory of the phenomena of internal organs." Here, the word "phenomena" means visible external manifestations. The organ's physical structure is of little consequence; whereas, its function in the body is of primary importance. While Western anatomy and physiology are primarily concerned with the physical body in its most concrete form (investigating the structures of the major body systems and organs), energetic anatomy and physiology focuses mainly on the underlying energy that enlivens and sustains the physical form.

In Chinese medical science, the body's internal organs are responsible for creating and distributing Qi, Blood and Body Fluids. Traditional Chinese Medicine divides Body Fluids into two distinct categories: Jin, which are the body's clear, light fluids, and Ye, which are the body's thick and heavy liquids.

1. The Jin Body Fluids are the Yang Fluids of the Upper Burner that move with Wei Qi. They are fast, light, and clear fluids, such as: sweat, tears, saliva, and mucus. The Lungs control the Jin.
2. The Ye Body Fluids are the Yin Liquids of the Middle and Lower Burners that move with Ying Qi. These are slow, heavy, and thick liquids. These liquids include those that moisten the joints, spine, brain, and Bone Marrow and lubricate the eyes, ears, nose, and mouth. The Spleen and Kidneys control the Ye.

This internal action of creating and distributing Qi, Blood and Body Fluids is manifested throughout the body's tissues through the Blood's Heat Cycle, which actively follows a peak (high-tide) and ebb (low-tide) energetic time period. Each organ and channel has either a Yin or Yang characteristic and is grouped and paired according to its Five Element nature.

This chapter focuses on the Twelve Primary Channels and their relationship to the organs. Most Traditional Chinese Medical texts begin the sequence of these channels with the Lung Channels. In this text, however, due to the energetic waxing and waning of the Yin and Yang Yao Cycles, and the Twelve Pi Hexagrams (see Chapter 11), I will start with the Gall Bladder Channels. The Twelve Primary Channels are described as follows: Gall Bladder, Liver, Lung, Large Intestine, Stomach, Spleen, Heart, Small Intestine, Bladder, Kidney, Pericardium, and Triple Burner.

THE GALL BLADDER CHANNELS

The Gall Bladder Channels are Yang channels. The external branches flow from the head to the feet on both sides of the body (Figure 6.6). The internal branches of the Gall Bladder Channels flow from the head to the Gall Bladder. The internal and external branches of these two rivers originate from the outer canthus of each eye. The external branches zigzag around the side of the head, flowing down the sides of the torso. The internal branches leave the outer canthus of the eye and descend the neck, entering the supraclavicular fossa, where they meet the main channels at the St-12 and Pc-1 points, and pass through the diaphragm, spirally wrapping the Liver, and permeating the Gall Bladder. From there they encircle the genitals and enter deeply into the body to emerge at the sacrum.

The external rivers continue to descend the lateral aspects of the torso and legs, ending at the lateral sides of the tips of the fourth toes.

THE GALL BLADDER ORGAN

The Gall Bladder's associated organ is the Liver; its element is Wood. The Gall Bladder's function of storing and excreting bile depends on the Liver's function of maintaining a smooth flow of Qi throughout the body.

The Gall Bladder also helps the Liver control the sinews, tendons, and ligaments. The Liver provides Blood to the sinews, while the Gall Bladder provides Qi to the sinews in order to ensure proper movement and agility.

PSYCHO-EMOTIONAL ASPECTS

The Gall Bladder is responsible for making decisions and judgments, as well as providing courage and initiative. This organ is sometimes called The Court of Justice or The General's Advisor. Although the Kidneys control drive and vitality, the Gall Bladder provides the capacity to turn this drive and vitality into decisive action.

The Gall Bladder has an influence on the quality and length of sleep. If the Gall Bladder is Deficient, the patient will often wake up suddenly, very early in the morning, and be unable to fall asleep again.

Patient's who are timid, indecisive, and easily discouraged by slight adversity, are said to have a weak Gall Bladder; conversely, decisive and determined patients are said to have a strong Gall Bladder.

GALL BLADDER'S ENERGY FLOW

The Gall Bladder Channels are often used to drain off the energy from an overheated or Excess Liver condition. Energetically, the Gall Bladder Channels store more Qi than Blood, acting more on energetic and nervous functions than on physical substances and Blood functions. At the


GB-17
GB-16
GB-18
GB-15
GB-14
GB-8
GB-4
GB-19
GB-1
GB-20
GB-3
GB-10
GB-9
GB-2
GB-21
GB-22
GB-23
GB-24
St-12
GB-25
Pc-1
GB-26
GB-27
GB-28
GB-29
GB-30
Lv-13
GB-31
GB-32
St-30
GB-33
GB-34
GB-35
GB-36
GB-37
GB-38
GB-39
GB-41
GB-40
GB-42
GB-43
GB-44

Flowing down from the head, the internal channels of the Gall Bladder pass through St-12 and Pc-1 then spiral wrap the Liver organ. From there, they circle the inside lining of the ribs (on the side of the body) then descend to the St-30 points.

Figure 6.6. The Internal and External Qi Flow of the Gall Bladder (GB) Channels

high-tide time period (11 p.m. to 1 a.m.) Qi and Blood abound in the Gall Bladder, and so the Gall Bladder organ and channels can more easily be dispersed and purged. During low-tide (11 a.m. to 1 p.m.) they can be easily tonified. The Gall Bladder Channels' energy acts on the skin, muscles, and nerves found along their pathways.

WESTERN MEDICAL PERSPECTIVE

The gall bladder stores then releases bile through the cystic duct into the common bile duct that flow into the small intestine to aid in the digestion of fats.

PATHOLOGICAL MANIFESTATIONS

The main symptoms of the Gall Bladder Channel diseases are:

- pain in the right-and left-upper quadrants of the abdomen,
- disorders of the head, which include the eyes, ears, and face, and
- disorders of the external sides of the legs along the channels' pathways.

THE LIVER CHANNELS

The Liver Channels are Yin channels that flow externally from the feet to the torso (Figure 6.7). These two rivers originate externally from the inside of the big toes and flow upward on the inside the legs, to circle the groin. From there they continue to ascend externally to the lateral aspects of the thorax, where they enter internally and permeate the Liver. They then connect to and spirally wrap the Gall Bladder. From there, they flow to the Lungs, ascend internally into the thorax, and connect with the eyes, cheeks, and inner surface of the lips. They emerge from the forehead and connect with the Governing Vessel at the Baihui GV-20 point (Figure 6.8).

THE LIVER ORGAN

The Liver is responsible for the "free and easy wandering" of Qi in the body, i.e., the Liver makes the Qi flow smoothly in and around the body. The Liver governs the Belt and Thrusting Vessels, as well as the body's Qi flow and circulation. The smooth flow of Qi ensures normal mental and emotional activity, as well as normal secretion of bile. Impairment of this Liver function leads to a "binding depression of Liver Qi," associated with impatience, hasty decisions impulsive actions, and a hot temper.

The Liver's associated organ is the Gall Bladder; its element is Wood. The Liver energy opens externally at the eyes and manifests externally through the fingernails and toenails. The Liver stores the Blood, and serves as a reservoir of Blood to regulate the circulation of Blood volume. In women it assists the uterus and regulates the menses. The Liver regulates the function and control of the muscles, tendons, and ligaments and is the source of the body's physical strength. It also stores the emotion of anger.

PSYCHO-EMOTIONAL ASPECTS

The Liver is responsible for planning and creativity, as well as instantaneous solutions or sudden insights; it is therefore considered The General in Charge of Strategy. The Liver houses the body's Hun and governs fright.

Its positive psycho-emotional attributes are kindness, benevolence, compassion, and generosity; its negative attributes are anger, irritability, frustration, resentment, jealousy, rage, and depression.

The Liver is also called the "root of resistance to fatigue." Whenever the Liver is not functioning properly (stagnate or excessively Hot due to suppressed emotions) the patient can experience fatigue as well as physical weakness.

THE LIVER'S ENERGY FLOW

The Liver Channels move the Qi to the whole body, storing and distributing the Blood. The Liver Channels contain more Blood than Qi, thus they affect physical substances more than they affect energetic functions. At the high-tide time period (1 a.m. to 3 a.m.), Qi and Blood abound in the Liver, and so the Liver organ and channels can more easily be dispersed and purged.; whereas, during low tide (1 p.m. to 3 p.m.), they can be easily tonified. The Liver Channel's energy acts on the skin, muscles, and nerves found along their pathways.

WESTERN MEDICAL PERSPECTIVE

The liver stores vitamins A, B-12, D, E, and K, and regulates blood volume. It is one of the main


GV-20
Lv-14
Lv-14
Lv-13
Lv-13
CV-12
Lv-12
Lv-12
Lv-11
Lv-11
Lv-10
Lv-10
Lv-9
Lv-8
Lv-7
Lv-6
Lv-5
Lv-4
Lv-3
Lv-2
Lv-1

Figure 6.7. The Internal and External Qi Flow of the Liver (Lv) Channels


GV-20
St-12
Lu-1
CV-12

Figure 6.8. Side View of the Liver Channel's Internal Flow of Energy

sources of the body's heat. The liver manufactures cholesterol and functions in lipid metabolism and controls bile secretion.

PATHOLOGICAL MANIFESTATIONS

Diseases of the Liver Channels cause swelling and a distended sensation of the hypochondrium. The Liver Channels also correspond to diseases of the lower abdomen and genital organs.

Since the Liver supplies the tendons with nutrients to develop physical strength, Liver impairment causes numbness, tremors, or spasms of the muscles, and sluggishness in joint movements.

The Liver and Kidneys are mutually dependant upon each other. The Liver stores the Blood that nourishes the Kidney Jing; whereas the Kidneys store Jing that helps produce the Blood. Deficient Kidneys may lead to Blood Deficiency, and Deficient Liver Blood may cause weakness of the Kidney Jing due to lack of nourishment from the Blood. The hair on top of the head is also nourished by the Blood. When the hair turns grey, it is often alleged to be caused by insufficient Blood stored in the Liver, as well as a Kidney Jing weakness.

THE LUNG CHANNELS

The Lung Channels are Yin channels and flow externally from the torso to the hands. The main river originates internally from the Middle Burner, in the middle of the chest, and descends downward, connecting with and spirally wrapping the Large Intestine. From there, it ascends along the upper surface of the Stomach passage and through the diaphragm, where it branches and permeates both Lungs (Figure 6.9).

From the Lungs, the rivers of Qi merge and ascend into the pit of the throat, where they separate again into two channels that transverse below the clavicle. These two main channels then surface externally to descend down the arms, and end on the outer side of each thumb. A small stream of energy branches off each wrist at the Lu-7 point and runs directly to the radial side of the tip of the index finger, where it connects with a branch of the Large Intestine Channels.

THE LUNG ORGAN

Since the Lungs are the uppermost organs, they are compared to canopies that shelter and protect all other internal organs. The Lungs' associated organ is the Large Intestine; its element is Metal. The Lung Qi opens externally at the nose and manifests itself through the voice (i.e., when the Lung Qi is in Excess the voice is too loud; when Deficient the voice is too soft). The Lungs govern the body's Qi and respiration. They regulate the metabolism of Water passages (sweat and Body Fluids), the opening and closing of the pores, the skin and the hair's texture.

The Lungs also control the circulation of Qi in both vessels and channels, as well as the dispersing or spreading of the body's Wei Qi (protective energy). They control the descending and holding functions of the body's Qi and Body Fluids.

All blood vessels lead to the Lungs, i.e., all Blood within the body must pass through the Lungs.

PSYCHO-EMOTIONAL ASPECTS

It is said that the Lungs are "the priest" or The Minister of Heaven and are responsible for establishing the foundation of Qi for the entire body (see Chapter 12). The Lungs house the body's Seven Corporeal Souls (Po) and are responsible for self-protection and self-preservation.

The Lungs positive psycho-emotional attributes are righteousness, dignity, integrity, and high self-esteem; their negative attributes are disappointment, sadness, grief, despair, anxiety, shame, and sorrow.

THE LUNGS' ENERGY FLOW

Functionally, the Lung Channels' energy acts on the Lungs, bronchi, throat, and larynx. If the Lung Qi is combined with Liver Qi and becomes stagnate in the throat area, a condition known as a "plum pit," or knot in the throat, develops. The Lung Channels store more Qi than Blood, thus they have a greater affect on energetic and nervous functions than on physical substances and Blood functions. At the high-tide time period (3 a.m. to 5 a.m.), Qi and Blood abound in the Lung organs and channels. They can therefore be more


Lu-1
Lu-2
Lu-3
Lu-4
Lu-5
Lu-6
Lu-7
Lu-8
Lu-9
Lu-10
Lu-11
Lu-1
Lu-2
Lu-3
Lu-4
Lu-5
Lu-6
Lu-7
Lu-8
Lu-9
Lu-10
Lu-11

Figure 6.9. The Internal and External Qi Flow of the Lung (Lu) Channels

easily be dispersed and purged at this time period; whereas during low-tide (3 p.m. to 5 p.m.), they can more readily be tonified. The Lung Channels' energy acts on the skin, muscles, and nerves found along their pathways.

WESTERN MEDICAL PERSPECTIVE

The action of inhaling air introduces oxygen into the lungs; exhaling expels carbon dioxide from the lungs. The heart pumps blood into the lungs. Blood passing through the lungs receives oxygen, and is then delivered back into the heart, where it is circulated throughout the body via the circulatory system.

PATHOLOGICAL MANIFESTATIONS

The Lung Channels' dysfunctions can result in chest and Lung diseases, as well as diseases on the radial side of the upper arm and palmar area of the hand.

The Lungs keep the pathway of air unobstructed and disseminate vital Qi throughout the body. If these functions are impeded, obstructions of the nose, coughing, dyspnea, and fullness of the chest may occur.

The Lungs cleanse the inhaled air and keep the Qi flowing downward. If these functions are impeded, coughing, asthma, oliguria (diminished amount of urine formation), and edema may occur.

Since the Lungs have their external orifice at the nose, stuffy nose, nasal discharge, and impairment of smell are common symptoms when the Lungs are being attacked by a pathogenic invasion of Wind and Cold.

THE LARGE INTESTINE CHANNELS

The Large Intestine Channels are Yang channels and flow externally from the hands to the head. These two rivers originate externally from the tips of the index fingers, ascend up the arms, and cross the shoulders, where they connect with the 7th cervical vertebra and then split into two branches. One set of branches (one branch from the left Lung and its corresponding branch from the right Lung) descends internally and spirally wraps the Lungs before moving through to permeate the Large Intestine. The other set continues ascending externally through the neck and cheek to the gums of the lower teeth. It curves around the upper lip and flows to the opposite side of the nose, where it connects with the Stomach Channels (Figure 6.10).

THE LARGE INTESTINE ORGAN

The Large Intestine's associated organ is the Lungs; its element is Metal. The main function of the Large Intestine is to receive food essence from the Small Intestine. The Large Intestine organ is said to govern humor (any fluid or semifluid substance in the body). It absorbs fluid that was separated by the Small Intestine and controls the transformation and transportation of solid waste in the body. The Large Intestine also controls the throat, teeth, and the drainage of the nose.

PSYCHO-EMOTIONAL ASPECTS

The Large Intestine relationship to the Lungs makes it equally affected by the emotions of sadness, grief, and worry. An energetic imbalance in the Large Intestine can result in physical weakness and provoke emotional introversion, accompanied by feelings of depression, irritability, discouragement, distress and apathy.

Strong emotions of fear or panic can produce an energetic-stool reflex reaction in the Large Intestine resulting in a spontaneous defecation.

THE LARGE INTESTINE'S ENERGY FLOW

The Large Intestine Channels have equally abundant amounts of Qi and Blood, acting equally on the body's energetic and nervous functions, as well as on physical substances and Blood functions. At the high-tide time period (5 a.m. to 7 a.m.), Qi and Blood abound in the Large Intestine organ and channels and can therefore be more easily dispersed or purged at this period; whereas during low-tide (5 p.m. to 7 p.m.), they can be more readily tonified. The Large Intestine Channels' energy acts on the skin, muscles, and nerves found along their pathways.

WESTERN MEDICAL PERSPECTIVE

The large intestine, sometimes called the "colon," is divided into four quadrants; the ascending, transverse, descending, and sigmoid or pelvic colon. The function of the large intestine is to reabsorb the fluid from the contents of indigest-


LI-20
LI-19
LI-18
LI-17
St-12
LI-16
LI-15
LI-14
LI-13
LI-12
LI-11
LI-10
LI-9
LI-8
LI-7
LI-6
LI-5
LI-4
LI-3
LI-2
LI-1

Figure 6.10. The Internal and External Qi Flow of the Large Intestine (LI) Channels

ible food residues moving through the intestines and to eliminate them from the body in the form of semisolid feces.

Whatever digestion takes place in the large intestine results from bacterial action. The fermentative bacteria (found in the middle part of the large intestine) and putrefying bacteria (found in the lower part of the large intestine) may produce toxic products, such as indole and skatol; however, if absorbed into the body, such bacterial decompositions undergo detoxification in the liver. In intestinal obstructions these bacterial decompositions are absorbed and eliminated in the urine in the form of indican.

PATHOLOGICAL MANIFESTATIONS

Dysfunctions in the Large Intestine Channels can result in diseases of the lower part of the face (including the nose, oral cavity, and teeth), throat, and front part of the neck, as well as disease of the back and radial sides of the upper extremities.

Tonification of the Large Intestine can be used to eradicate eye pain, toothache, earache, and to prevent hemorrhages, as well as to greatly reduce excessive menstrual bleeding.

Because of its relationship to the Lungs, the Large Intestine can be purged to treat coughing and asthma caused from Excessive Heat in the Lungs; whereas replenishing the vital Qi of the Lungs can cure constipation in debilitated patients.

The Large Intestines' energetic functional patterns generally relate to disturbances in bowel movements. Disturbances of the Large Intestine's energetic function usually gives rise to one of the two following complications:

1. Excess Conditions of the Large Intestines can result in symptoms of: Heat, Heat obstruction, Damp Heat, or Cold invading the Large Intestine.
2. Deficient Conditions of the Large Intestines can lead to an invasion of Cold or Dryness, and in severe cases of Deficiency, to the Collapse of the Large Intestine.

THE STOMACH CHANNELS

The Stomach Channels are Yang channels, and flow externally from the head to the feet (Figure 6.11). These two rivers originate externally from the lateral sides of the nose (LI-20), ascending upward to the base of the eye and bridge of the nose, where they meet the Bladder Channels. They then descend under the eyes, down the face, winding along the angle of the mandible, then ascend in front of the ears, following the anterior hairline till they reach the forehead. From the St-5 point, the primary branches on each side descend the neck and torso. Externally, these branches continue down the torso and legs and end at the lateral tips of the second toes. A second set of branches separate from the St-12 points and internally permeate the Stomach before spiral wrapping the Spleen and joining the primary channel branches at the St-30 points.

THE STOMACH ORGAN

The Stomach organ's associated organ is the Spleen; its element is Earth. The Stomach is considered the origin of the Body's Fluids. Its main function is to accept and decompose food. It separates the "clean" (pure) and "turbid" (impure) parts of ingested food and transfers the clean, energetically usable portion upwards to the Spleen, while sending the turbid unusable portion downward to the Small Intestine, to be further processed. Both the Stomach and the Spleen are considered the roots of Postnatal Qi and are often called The Ministers of Food Storage.

PSYCHO-EMOTIONAL ASPECTS

The Stomach influences the mental state; an Excess condition can agitate the mind and cause mental symptoms such as: mania or hypomania, confusion, severe anxiety, and hyperactivity.

THE STOMACH'S ENERGY FLOW

The Stomach Channels have equally abundant amounts of Qi and Blood, acting equally on the body's energetic and nervous functions, as well as on physical substances and Blood functions. At the high-tide time period (7 a.m. to 9 a.m.), Qi and Blood abound in the Stomach organ and channels, and can therefore be more easily dispersed or purged at this period; whereas during low-tide (7 p.m. to 9 p.m.), they can be more readily tonified. The Stomach Channels' energy acts on the skin, muscles, and nerves found along their pathways.


St-8
St-1
St-2
St-3
St-7
St-6
St-5
St-4
St-9
St-10
St-11
St-12
St-13
St-15
St-17
St-18
St-19
St-25
St-30
St-31
St-32
St-33
St-34
St-35
St-36
St-37
St-38
St-39
St-40
St-41
St-42
St-43
St-44
St-45
St-12
St-30

A second set of branches separate from the St-12 points and internally permeate the Stomach before spiral wrapping the Spleen and joining the primary channel branches at the St-30 points.

Figure 6.11. The Internal and External Qi Flow of the Stomach (St) Channels

WESTERN MEDICAL PERSPECTIVE

The stomach secretes gastric juice for food digestion. The proteins are converted into peptones; the stomach then regulates the passage of food to the other digestive organs.

PATHOLOGICAL MANIFESTATIONS

Diseases of the Stomach Channels include diseases of the face (nose, oral cavity, and teeth), throat, front of the neck, the abdomen, the frontal part of the legs and gastrointestinal area. Stomach disease can also induce certain psychiatric diseases.

Diseases of the Stomach organ are primarily caused by improper diet. To determine the root of the disease, the following five areas are considered:

1. The patient's Five Elemental Constitution and present state of health,
2. The type and energetic quality of the foods ingested (Hot or Cold), and whether the food is in season or out of season,
3. The scheduling of meals (This not only includes eating meals at regular times, but also eating a balanced meal, not too fast, and not too late at night),
4. The Yin/Yang balance of the types of food digested (This includes balancing the foods Five Tastes and Five Colors), and
5. The emotional factors surrounding meal time. This includes having the proper mental attitude (being relaxed and calm) and avoiding emotional distress (such as feeling rushed, upset, and so on).

The Stomach easily suffers from Excess patterns (e.g., Fire or Phlegm Fire), which in turn agitate the Shen. When the Shen is disturbed, it can cause manic symptoms such as: inappropriate laughter, pressured speech, unconscious talking, laughing, or singing, violent or otherwise inappropriate behavior (e.g., taking off one's clothes in public). In milder cases, symptoms may include mental confusion, severe anxiety, hypomania (a milder form of mania), and hyperactivity.

Since the Stomach has the function of sending the preliminarily digested food downward, an impairment of this function often causes vomiting.

THE SPLEEN CHANNELS

The Spleen Channels are Yin channels and flow externally from the feet to the torso (Figure 6.12). These two rivers originate externally from the medial tips of the big toes, ascend upwards along the inner thighs, then enter the abdomen (connecting to the CV-3 and CV-4 points) and further up the upper torso (connecting to the CV-12 point). The external Spleen Channels meet at the CV-12 point, enter the body, where the left channel flows into the Spleen, and then spirally wraps the Stomach organ. An internal branch ascends from the CV-12 point into the Heart. At the CV-12 point both left and right main channels meet and separate again to ascend through the diaphragm, up the torso and throat, alongside the esophagus, to reconnect at the base of the tongue. From the Sp-20 points external branches descend along the lateral aspects of the torso and terminate on the mid-axillary line in the seventh intercostal space.

THE SPLEEN ORGAN

The Spleen's associated organ is the Stomach; its element is Earth. In Traditional Chinese Medicine, the pancreas (a gland that produces insulin and is connected to the Spleen) is considered part of the Spleen/Stomach function. The Spleen organ is responsible for transforming food received from the Stomach into Gu Qi. The Gu Qi is then sent to the Liver and Kidneys to be "cooked" and further refined. The Spleen's main function is to govern or oversee this transportation and transformation of Gu Qi. It also controls the Blood by keeping it in the blood vessels, and governs the muscles, flesh, and limbs. The Spleen organ's energy opens externally at the mouth, controlling taste, and connects externally by the lips. The Spleen is sometimes called The Minister of Grains, because it is responsible for distributing what the Stomach has stored. Energetically, the Spleen controls the body's central cavity, and maintains the internal organs in their places.

PSYCHO-EMOTIONAL ASPECTS

The Spleen houses the body's thoughts and intentions (Yi), and is responsible for analytical thinking, memory, cognition, intelligence, and ideas. The Spleen is responsible for directing


Sp-20
Sp-19
Sp-18
Sp-17
Sp-21
Sp-16
CV-12
Sp-15
Sp-14
CV-4
Sp-13
Sp-12
CV-3
Sp-11
Sp-10
Sp-9
Sp-8
Sp-7
Sp-6
Sp-5
Sp-4
Sp-3
Sp-2
Sp-1
Sp-20
Sp-19
Sp-18
Sp-17
Sp-21
Sp-16
Sp-15
Sp-14
Sp-13
Sp-12
Sp-11
CV-12

The external Spleen Channels meet at the CV-12 point, enter the body, where the left channel flows into the Spleen, and then spirally wraps the Stomach organ. An internal branch ascends from the CV-12 point into the Heart. At the CV-12 point both left and right main channels meet and separate again to ascend through the diaphragm, up the torso and throat to reconnect at the base of the tongue.

Figure 6.12. The Internal and External Qi Flow of the Spleen (Sp) Channels

memories to the Kidneys for short-term storage. The Kidneys will later transfer these memories to the Heart for long-term memory storage (see Chapter 12).

The Spleen's positive psycho-emotional attributes are trust, honesty, openness, acceptance, equanimity, balance, and impartiality; its negative attributes are worry, excessive thinking, pensiveness, obsessiveness, remorse, regret, obsessions, and self-doubt.

THE SPLEEN'S ENERGY FLOW

The Spleen Channels store more Qi and less Blood, acting more on energetic and nervous functions than on physical substance and Blood functions. At the high-tide time period (9 a.m. to 11 a.m.), Qi and Blood abound in the Spleen organ and channels, and can therefore be more easily dispersed and/or purged at this period; whereas during low-tide (9 p.m. to 11 p.m.), they can be more readily tonified. The Spleen Channels' energy acts on the skin, muscles, and nerves found along their pathway.

WESTERN MEDICAL PERSPECTIVE

The spleen is responsible for blood formation, filtration, and storage. In the embryo, all types of blood cells are formed by the spleen, but in the adult, only lymphocytes and monocytes are formed.

PATHOLOGICAL MANIFESTATIONS

The main diseases of the Spleen Channels include gastrointestinal dysfunctions (disturbances of digestion and absorption of food), and diseases of the tongue and throat. Spleen disorders also affect the inner side of the lower extremities along the Spleen's Channels.

Since the Spleen has the function of sending food essence upwards (to the Lungs), if this function is impeded, diarrhea or prolapse of the viscera may occur.

The Spleen also has the function of keeping the Blood flowing in the blood vessels; impairment usually leads to chronic hemorrhagic diseases.

The Spleen has the function of nourishing the flesh (muscles). A person with a healthy Spleen will usually have a healthy figure and a toned body; a diseased Spleen makes the patient lose muscle definition.

The Spleen nourishes the limbs. Strength of the limbs depends upon the nourishment guaranteed by the normal functioning of the Spleen. A diseased Spleen usually causes weakness of the limbs.

THE HEART CHANNELS

The Heart Channels are Yin Channels and flow externally from the torso to the hand (Figure 6.13). Three rivers originate internally from the Heart on each side of the body. The first bilateral set ascends and connects to the tissues connecting the eyeball. The second set descends, first to permeate the Pericardium, then descends further to connect with and spirally wrap the Small Intestine. The third set flows up into the Lungs, emerges externally at the armpits, then descends the medial aspect of the arms and ends on the inside of the little fingers.

THE HEART ORGAN

The main function of the Heart organ consists of controlling the Blood and vessels, regulating the Blood flow, perspiration, and housing the Shen. The Heart organ's energy opens externally at the tongue and is expressed through the complexion.

PSYCHO-EMOTIONAL ASPECTS

The Heart's associated organ is the Small Intestine; its element is Fire. Long-term memory, thinking, emotions, intimacy, cognition, intelligence, and ideas are all dominated by the function of the Heart. The Heart is sometimes called The Emperor, or "supreme controller of all Yin and Yang organs" (see Chapter 12). The Heart houses the body's Spirit (Shen). The Heart dominates sleep; if the Heart is strong the patient will fall asleep easily and sleep soundly. If the Heart is weak, the patient's mind will "float," resulting in an inability to fall asleep, disturbed sleep, or excessive dreaming.

The Heart's positive psycho-emotional attributes are love, joy, peace, contentment, propriety, insight, wisdom, orderliness, forgiveness, and courtesy. Its negative attributes are hate, guilt,


The first points of the Heart (Ht-1) are located in the armpits.
Ht-1
Ht-2
Ht-3
Ht-4
Ht-5
Ht-6
Ht-7
Ht-8
Ht-9
Ht-1
Ht-2
Ht-3
Ht-4
Ht-5
Ht-6
Ht-7
Ht-8
Ht-9

Figure 6.13. The Internal and External Qi Flow of the Heart (Ht) Channels

shock, nervousness, excitement, longing, and craving.

THE HEART'S ENERGY FLOW

The Heart Channels store more Qi than Blood; that is to say, its dominant action affects the energy. This energetic action controls the morale, the spirit of enterprise, and provides the energy required for respiration. At the high-tide time period (11 a.m. to 1 p.m.), Qi and Blood abound in the Heart organ and channels, and can therefore be more easily dispersed or purged at this period; whereas during low-tide (11 p.m. to 1 a.m.), they can be more readily tonified. The Heart Channel's energy acts on the skin, muscles, and nerves found along their pathways.

WESTERN MEDICAL PERSPECTIVE

The heart provides the propulsive force for circulating the blood throughout the vascular system. The blood circulation distributes the nutrients and oxygen needed for cell and tissue survival. The heart's propulsion also aids in the removal of wastes and other substances through the interconnecting blood vessels.

PATHOLOGICAL MANIFESTATIONS

The main diseases of the Heart Channels include diseases that exert pressure on the brain, eyes, or pharyngeal wall, as well as diseases of the Heart itself, and the lateral side of the chest. The Heart also relates to diseases of the ulnar palmar side of the arm.

The Heart is in charge of mental activities, including consciousness and thinking. Dysfunctions of the Heart can lead to insomnia, impairment of consciousness, amnesia, and psychosis.

The Heart and Kidneys have a mutual energetic relationship of supporting and checking each other. The Heart controls the body's Fire, while the Kidneys control the body's Water. Normally, the Fire of the Heart is sent down to warm the Kidneys, and the Water of the Kidneys is sent up to irrigate the Heart. If this balanced relationship breaks down (especially when the Kidney Water is insufficient to check the Heart Fire), a series of Fire symptoms of the Heart, such as hypertension, hyperactivity, palpitations, and insomnia may result.

Since the Heart has its external opening in the tongue, the condition of the Heart is reflected in the tongue:

1. A dark purple tongue indicates Blood Stasis of the Heart.
2. A pale tongue reveals Deficient Blood of the Heart.
3. An ulcer on the tongue reveals Excess Fire of the Heart.

THE SMALL INTESTINE CHANNELS

The Small Intestine Channels are Yang channels and flow externally from the hands to the head. These two rivers originate externally from the lateral tips of the little fingers (ulnar side) then ascend the arms to the shoulders, where they divide into two sets of branches. One set of branches descends the supraclavicular fossa internally, spiral wrapping the Heart, then continues down the esophagus, diaphragm, and Stomach, before permeating the Small Intestine (Figure 6.14).

The other set of branches ascends externally up the sides of the neck, then divides again into two more sets of branches at the cheek; one set will end at the ears, the other at the lateral sides of the nose and inner canthus of the eyes.

THE SMALL INTESTINE ORGAN

The Small Intestine temporarily stores partially digested food, absorbing the essential substances of the undigested food and a portion of the liquid content. It later transfers the residue (with a considerable amount of liquid) to the Large Intestine, and that is why it is said that the Small Intestine "governs liquid."

The Small Intestine is sometimes called "The Official in Charge of Separating the Pure from the Impure, because it separates the "clean" (reusable) food essence (Gu Qi) from the "dirty, turbid" food essence. The clean Gu Qi is transported throughout the body to nourish the tissues. The turbid is transported to the Large Intestine and Bladder organs to be further processed.

The Small Intestine's associated organ is the Heart; its element is Fire.

PSYCHO-EMOTIONAL ASPECTS

The Small Intestine influences the patient's


SI-19
SI-18
SI-17
SI-16
SI-15
SI-12
SI-14
SI-13
SI-10
SI-11
SI-9
SI-8
SI-7
SI-6
SI-5
SI-4
SI-3
SI-2
SI-1

SI-8 is located on the opposite side of the elbow.

Figure 6.14. The Internal and External Qi Flow of the Small Intestine (SI) Channels

mental clarity, judgement, and powers of discernment. The ability to distinguish relevant issues with clarity before making a decision is attributed to the Small Intestine.

THE SMALL INTESTINE'S ENERGY FLOW

The Small Intestine Channels store more Blood than Qi, and act more on the physical substances and Blood functions than on energy. At the high-tide time period (1 p.m. to 3 p.m.), Qi and Blood abound in the Small Intestine organ and channels, and can therefore be more easily dispersed and purged at this period; whereas during low-tide (1 a.m. to 3 a.m.), they can be more readily tonified. The Small Intestine Channels' energy act on the skin, muscles, and nerves found along their pathway.

WESTERN MEDICAL PERSPECTIVE

The small intestine's function is to receive the food mass from the stomach through the pylorus, the bile from the liver and gall bladder, and the pancreatic juices for digestion and absorption. The small intestine then passes what it doesn't absorb into the large intestine.

PATHOLOGICAL MANIFESTATIONS

Diseases of the Small Intestine Channels include diseases of the face, ear, cheek, lower jaw, the neck, and throat, as well as the dorsal ulnar side of the upper extremities.

In TCM, food and herbs are divided into Yin (Cold) or Yang (Hot) properties. The Small Intestine is easily affected by the type and temperature of food eaten. An excess consumption of "cold" and raw foods, for example, can create a Cold condition within the Small Intestines, while an excess consumption of "hot" foods can create a Hot condition.

Disturbances of the Small Intestine's energetic function usually gives rise to one of the following complications:

1. Excess Conditions of the Small Intestines can result in symptoms of: Full Heat, Qi pain, Knotted Qi, and the infestation of worms in the Small Intestine.
2. Deficient Conditions of the Small Intestines can manifest as: Deficient and Cold Small Intestine.

Pathologic Heart Heat may be transmitted to the Small Intestine, resulting in urodynia (painful urination) and hematuria (blood in the urine). Herbal prescriptions used to dispel Heat from the Heart are also effective in treating these urinary symptoms, which are alleged to be caused by dysfunctions of the Small Intestine.

THE BLADDER CHANNELS

The Bladder Channels are Yang channels and flow externally from the head to the feet. Two rivers originate externally from the inner canthus of the eyes, ascend upward over the head to join the Governing Vessel at the GV-20 point, where they divide into two additional branches that flow into each temple, and into the brain. From there, they then divide into two sets of branches (at the Bl-10 point), which descend the back, and internally connect to and spiral wrap the Kidneys, before they descend to permeate the Bladder. They continue externally down the thigh, the popliteal fossa at the back of the knee, calf, and foot, and end on the lateral sides of the tips of the little toes (Figure 6.15).

THE BLADDER ORGAN

The function of the Bladder is to remove water by Qi transformation. The Bladder receives the "impure" parts of the fluids separated by the Small Intestine and temporarily stores and transforms these fluids into urine, to discharge it when the Bladder is full. The Bladder and the Small Intestine work together to remove Body Fluids from the Lower Burner.

The Bladder Channels activate the Yang aspect of the Kidney's function and are sometimes called The Water District Officials or "the controllers of the storage of waste water." The Bladder's associated organ is the Kidney; its element is Water.

PSYCHO-EMOTIONAL ASPECTS

An imbalance in the Bladder can cause such psychological symptoms as habitual fear, lack of decision making capability and a diminished moral character. If the imbalance becomes chronic, it results in such emotional responses as jealousy, suspicion, and a holding on to long-standing grudges.


Bl-7
Bl-8
Bl-8
Bl-9
Bl-9
Bl-10
Bl-10
Bl-11
Bl-11
Bl-41
Bl-41
Bl-46
Bl-46
Bl-17
Bl-17
Bl-47
Bl-47
Bl-51
Bl-51
Bl-52
Bl-52
Bl-24
Bl-24
Bl-31
Bl-53
Bl-53
Bl-54
Bl-54
Bl-35
Bl-36
Bl-36
Bl-37
Bl-37
Bl-38
Bl-38
Bl-39
Bl-39
Bl-40
Bl-55
Bl-55
Bl-56
Bl-56
Bl-58
Bl-58
Bl-57
Bl-59
Bl-59
Bl-62
Bl-62
Bl-63
Bl-63
Bl-60
Bl-65
Bl-65
Bl-61
Bl-67
Bl-67
Bl-64
Bl-66
Bl-66


Bl-6
Bl-6
Bl-5
Bl-5
Bl-4
Bl-4
Bl-3
Bl-3
Bl-2
Bl-2
Bl-1
Bl-1



The internal flow of the Bladder Channels rushes into the lower back and lumbar area, passing through the renal arteries, to spiral wrap the Kidneys. From the Kidneys, the energy flows downward, following into the ureter, to permeate the Bladder.

Figure 6.15. The Internal and External Qi Flow of the Bladder (Bl) Channels

THE BLADDER'S ENERGY FLOW

The Bladder Channels regulate the functions of the Kidneys. The Bladder Channels store more Blood than Qi, acting more on the physical substances and the Blood functions than on the energy. At the high-tide time period (3 p.m. to 5 p.m.), Qi and Blood abound in the Bladder organ and channels, and can therefore be more easily dispersed and purged at this period; whereas during low-tide (3 a.m. to 5 a.m.), they can be more readily tonified. The Bladder Channels' energy acts on the skin, muscles, and nerves found along their pathway.

WESTERN MEDICAL PERSPECTIVE

The bladder is a reservoir for the urine received from the kidneys; it discharges urine from the body through the urethra.

PATHOLOGICAL MANIFESTATIONS

The main diseases of the Bladder Channels include:

- Diseases of the top of the head,
- Brain disorders,
- Disorders of the neck and back, especially the lumbar and sacral regions,
- Disorders of the back of the legs and thighs, and
- Disorders of the lateral side of the feet.

Diseases of the Bladder Organ manifest in changes in urine and urination; these changes will reflect a Deficient or Excess condition of the Bladder.

1. Deficient Conditions are attributed to Deficient Kidney Qi which affects the Bladder's ability to transform Qi. This dysfunction causes frequent urination, dribbling, or enuresis (involuntary discharge of urine).
2. Excess Conditions are attributed to Damp Heat in the Bladder, resulting in symptoms such as:
   - heat and pain during urination,
   - the short release of murky or reddish urine,
   - frequent difficulty in urination,
   - pus, or Blood in the urine, and
   - Bladder stones which cause a urinary block and painful distention of the lower abdomen.

   The most common pathological factor in the diseases of the Bladder organ is due to the accumulation of Dampness (e.g., Damp Heat or Damp Cold). Other pathological conditions include: emotional fears, anxieties and insecurities, excessive sex, and Deficient and Cold Bladder.

THE KIDNEY CHANNELS

The Kidney Channels are Yin channels and flow externally from the feet to the torso (Figure 6.16). These two rivers originate externally from underneath the little toes, circling the inside of the heels, ascending through the medial aspect of the legs, where they merge and enter into the coccyx and lower lumbar vertebrae. Dividing again, one branch permeates the Kidneys, while the other branch continues ascending into the cerebral cortex. From the Kidney organs, two additional sets of channels internally emerge. One set descends and spiral wraps the Bladder. The other set ascends into the Liver, diaphragm, and Lungs, then spiral wraps the Heart and travels up the throat, stopping at the root of the tongue (Figure 6.17).

THE KIDNEY ORGANS

The Kidneys store Jing substances, produce Marrow, and control the development of the bones. They also control respiration, reproduction, growth and development, and govern the Body Fluids. The Kidney Jing is the biological basis for the woman's menstrual blood. The Kidneys are the root of the Yin and Yang Qi of all the body's organs. The Kidneys energetically open externally through the ears and are sometimes called The Minister of Ingenuity and Vitality, or "the controller of water" (see Chapter 12).

The Kidney organs' associated organ is the Bladder and it's element is Water. Kidney Yin Qi flows to the Liver, Heart, and Lungs. It is responsible for the body's fluid-like essences and rules the birth, growth, maturation, and reproduction cycle. Kidney Yang Qi flows to the Spleen, Liver, Heart, and Lungs. It supports the Yang of all the body's organs via the Mingmen.

PSYCHO-EMOTIONAL ASPECTS

The Marrow produced from the Kidney Jing flows into the brain. The thinking ability is strengthened when Qi and Blood in the cerebral



From the Kd-16 points, the Qi follows the Belt Vessel and enters into and permeates the Kidneys. From the Kidneys, the Qi descends into the ureters, where it spirally wraps the Bladder.

The internal flow of the Kidney Qi passes the GV-1 point, moving up and down the spine, and exiting the body at the Kd-11 points. From Kd-11, the energy ascends superficially up to the Kd-16 points.

Figure 6.16. The Internal Flow of the Kidney Qi


Kd-27
Kd-27
Kd-24
Kd-24
Kd-23
Kd-23
Kd-22
Kd-22
Kd-21
Kd-21
Kd-17
Kd-17
Kd-16
Kd-16
Kd-11
Kd-11
Kd-10
Kd-9
Kd-8
Kd-7
Kd-3
Kd-1
Kd-2
Kd-4
Kd-6
Kd-5

Figure 6.17. The Internal and External Qi Flow of the Kidney (Kd) Channels

cortex are abundant. With the increase of thinking activity, a circle of light develops within the body's Taiji Pole. The individual's innate intelligence (Yuan Shen) is represented by the intensity of light. The degree of accumulated spiritual energy is reflected by the number of light circles developed within the Taiji Pole. These circles of light can be best observed when first waking. By placing slight pressure on the external eye lids the inner light of the Taiji Pole is projected onto the optic nerves, reflecting an image of the circle of light. If the circle of light is complete, it reflects a strong, healthy condition. If the circle of light is dark within its center (similar to a doughnut), this reflects a Deficient condition. If the circle of light is broken or interrupted, it reflects an extreme Deficiency (Figure 6.18).

The "memory zone," as well as the "thought center" are also located in the cerebral cortex and will not develop until the Kidney Channels travel through the spine, along with the Liver Channels, to reach the cortex. When the Qi of these two channels is abundant, the memory function is keen.

The Kidneys house the body's will power (Zhi). They control short-term memory and store data. The Kidneys provide the capacity and drive for strength, skill, and hard work. A patient with strong Kidneys can work hard and purposefully for long periods of time. Consequently, when the Kidneys are in a state of disharmony, the patient can sometimes be driven to a state of excessive-compulsive working habits (a workaholic). A patient with weak Kidneys will lack strength and endurance.

The Kidney's positive psycho-emotional attributes are wisdom, rationality, clear perception, gentleness, and self-understanding. The negative attributes are fear, loneliness, insecurity, and shock (which attacks the Heart first then descends into the Kidneys to become fear).



Figure 6.18. The individual's Yuan Shen is represented by the intensity of the light, and the degree of accumulated spiritual energy is reflected by the number of light circles developed within the Taiji Pole.

THE KIDNEYS' ENERGETIC FLOW

The Kidney Channels store more Qi than Blood, acting more on energetic and nervous functions than on physical substances and Blood functions. At the high-tide time period (5 p.m. to 7 p.m.), Qi and Blood abound in the Kidney organ and channels, and can therefore be more easily dispersed and purged at this period; whereas during low-tide (5 a.m. to 7 am.), they can be more readily tonified. The Kidney Channels' energy acts on the skin, muscles, and nerves found along their pathways.

WESTERN MEDICAL PERSPECTIVE

The function of the kidneys is to regulate water and electrolytes and to process the body's urine.

PATHOLOGICAL MANIFESTATIONS

Kidney Channel diseases cause general deterioration of the entire body, weakness in the lower extremities, lumbar pain, and hot sensations deep inside the feet.

The Kidneys open through the urogenital orifices and the anus. The energetic condition of the Kidneys can be, partially reflected by the condition of the patient's urination and defecation; in males, this includes the ejaculation process.

Since the Kidneys are responsible for concentration and memory retention, poor concentration and loss of memory are common symptoms of Kidney hypofunction.

THE PERICARDIUM CHANNELS

The Pericardium Channels are Yin channels and flow externally from the torso to the hands. These two rivers originate internally from the center of the chest, flowing out of the Pericardium. They descend through the center of the body, spi-


Pc-1
Pc-1
Pc-2
Pc-2
Pc-3
Pc-3
Pc-4
Pc-4
Pc-5
Pc-5
Pc-6
Pc-6
Pc-7
Pc-7
Pc-8
Pc-8
Pc-9
Pc-9

Figure 6.19. The Internal and External Qi Flow of the Pericardium (Pc) Channels

ral wrapping the Upper, Middle, and Lower Burners. Two rivers surface and branch externally by the nipples to proceed down the center of each arm, ending at the tips of the middle fingers. A second branch arises from the center of each palm at the Pc-8 point and flows into the ring fingers to connect with the Triple Burner Channels (Figure 6.19).

PERICARDIUM ORGAN

The Pericardium is associated with the Triple Burners; its element is Fire. The Pericardium is not considered an independent organ, as much as a protective covering for the Heart, that protects the Heart from pathogenic factors. The Pericardium activates, energizes and controls the Yin channel's distribution of the Kidney Yang Qi to the Yin organs. Along with the Heart, it governs the Blood, and houses the Shen. The Pericardium is considered the Prime Minister, or the official who protects the heart.

PSYCHO-EMOTIONAL ASPECTS

The Pericardium has a powerful influence on the patient's mental and emotional states. Its goal is to "create feelings of joy and/or pleasure for the emperor (Heart)."

THE PERICARDIUM'S ENERGY FLOW

The Pericardium Channels have an affect on the body's circulation of Blood. They are considered the "mother of Yin" and are connected to the Mingmen. The Pericardium Channels store more Blood than Qi, acting more on the physical substance and Blood functions than on the energy. At the high-tide time period (7 p.m. to 9 p.m.), Qi and Blood abound in the Pericardium organ and channels and can therefore be more easily dispersed and purged at this period; whereas during low-tide (7 a.m. to 9 a.m.), they can be more readily tonified. The Pericardium Channel's energy acts on the skin, muscles, and nerves found along their pathways.

WESTERN MEDICAL PERSPECTIVE

The function of the pericardium is to provide a protective covering for the heart. It contains a thin serous fluid that allows the heart to work in a relatively friction-free environment.

PATHOLOGICAL MANIFESTATIONS

The main diseases of the Pericardium Channels include diseases of the Heart, front of the chest, major blood vessels, and diseases on the midline to upper palmar side of the upper extremities. Mental abnormalities may also manifest.

THE TRIPLE BURNER CHANNELS

The Triple Burner Channels are Yang channels that flow externally from the hands to the head. These two rivers originate externally from the tips of the ring fingers and ascend along the lateral aspect of the arms, over the shoulders to the clavicles, then branch internally and spiral wrap the Pericardium. They circle the diaphragm and permeate the Upper, Middle, and Lower Burners. A set of branches originate internally from the chest CV-17 point at the Heart, or center of the Middle Dantian. Flowing upwards, these branches emerge from the supraclavicular fossa at the St-12 points to ascend up the neck, head, and then circle the ears. Another set of branches flows downward to the cheek, terminating in the infraorbital region; the other set ends above the ears, by the outer canthus of the eyes.

THE TRIPLE BURNERS ORGAN

The Triple Burners' associated organ is the Pericardium; its element is Fire. The Triple Burners are not regarded as an independent organ, but are assigned to specific energy areas, and are a part of the function of the Yin and Yang organs. The function of the Triple Burners' energy is to produce Heat, and to regulate the body's temperature. This Heat is increased through such meditative disciplines as the Microcosmic Orbit (which connects the Governing and Conception Vessels), and the Macrocosmic Orbit (which connects all Twelve Primary Channels with the Governing and Conception Vessels). The main function of the Triple Burners (Figure 6.20) is to regulate the general ingestion and digestion of food and fluids throughout the body.

The Triple Burners are known as The Official of Balance and Harmony, because they govern Water metabolism, control the production of Wei


TB-21
TB-22
TB-23
TB-20
TB-19
TB-18
TB-17
TB-16
TB-15
TB-14
TB-13
TB-12
TB-11
TB-10
TB-9
TB-8
TB-7
TB-6
TB-5
TB-4
TB-3
TB-2
TB-1
St-12
CV-17

The internal flow of the Triple Burner Channels moves from St-12 down to CV-17, where it disperses into the chest and envelops the Pericardium. From the Pericardium, as the energy flows down through the diaphragm, it circulates through the chest and permeates the Triple Burners (a continuing branch flows upward to the St-12 points).

Figure 6.20. The Internal and External Qi Flow of the Triple Burners (TB) Channel

Qi, and transport Yuan Qi from the Kidneys to all the other organs of the body. This name refers to the Triple Burners' role in regulating metabolic functions, as well as their production of Qi, Blood, Body Fluids, and waste.

The Triple Burners' energy is composed of Zong Qi (Essential Qi). The Zong Qi assists the Heart in circulating the Blood and the Lungs in respiration. The Zong Qi also assists in conveying the Ying Qi (Nourishing Qi) to nourish the Blood, organs, and tissues of the body, as well as strengthens the Wei Qi (Protective Qi) that protects the external body (see Chapter 14).

1. The Upper Burner

   The Upper Burner is formed from the Fire created from the combined energies of the Heart, Pericardium, and both Lungs. The Upper Burner's energy is housed from the area of the head, throat, and upper chest, to the diaphragm. The Upper Burner is responsible for respiratory and cardiac functions. It moves the body's finer energy, circulating and distributing nutrients and Qi throughout the body like a "mist."

2. The Middle Burner

   The Middle Burner is formed from the Fire created from the combined energies of the Stomach, Spleen, pancreas, and Gall Bladder. The Middle Burner's energy is housed from the upper abdomen (the diaphragm) and the umbilicus.

   The Middle Burner is responsible for digestion, fermentation, and transformation of food and drink into nutrients for distribution. In the Middle Burner area, the Small Intestine connects downward to the Bladder. The Small Intestine transforms waste, that is then sent down to the Large Intestine, and also distills the body's fluids, sending them down to the Bladder.

   The Ying Qi (Nourishing Qi) of the Middle Burner receives its nourishment from the Stomach and Spleen. The Spleen extracts Gu Qi from the food "prepared" by the Stomach, churning the food essence into "foam." The Spleen refines this energetic foam and sends the processed Gu Qi to the Lungs. The Lungs further refine the Gu Qi, sending the impure part to the Kidneys (for additional refinement of the Gu Qi). The Kidneys return the Clean Qi to the Lungs and send the turbid part to the Bladder to be expelled from the body. The Qi from the air mixes with the Gu Qi in the Lungs to produce Zong Qi. The Lungs circulate the refined Gu Qi in the form of vapor or mist which is housed in the Upper Burner. The Heart then produces Blood from this vapor.

3. The Lower Burner

   The Lower Burner is formed from the Fire created from the combined energies of the Liver, Kidneys, Bladder, Intestines, and genitalia. The Lower Burner's energy is housed in the area which starts just below the umbilicus and extends to the lower perineum.

   The Lower Burner is responsible for the reproductive functions and for the filtering and elimination of waste products (Figure 6.21). It moves the body's coarser energy, acting as a "channel for water."

The Triple Burners contribute to the process of the three stages of transformation and ais in the distribution of Ying and Wei Qi throughout the body as follows:

- After the Gu Qi (food energy) has been separated into Clean and Turbid Qi, the Upper Burner releases the body's clean Wei Qi, directing it to the Lungs;
- the Middle Burner releases the body's clean Ying Qi, directing it to all of the body's organs and tissues; and
- the Lower Burner releases the body's Body Fluids, directing the turbid part to the Bladder.

PSYCHO-EMOTIONAL ASPECTS

The Triple Burners are considered the Ambassadors or "intermediaries" for the body's Yuan Qi. On a psychological level, they can be used to move Qi and lift depression derived from stagnation of Liver Qi.

When the Triple Burners, which regulate the consciousness, are full, the consciousness becomes stable and the Mind's intent is benevolent and kindhearted. The Triple Burners are also linked


Dispersing
Body Fluids To Skin & Muscles
Pure
Body Liquids To Whole Body
3rd Dantian
Upper Burner
Lungs
Ascending Steam To Moisten Lungs
Pure
Spleen Transports Pure Upwards
Descending Fluids & Qi
2nd Dantian
Spleen Stomach
Middle Burner
Stomach Transports Impure Downwards
Left Kidney
Kidneys
Right Kidney
1st Dantian
Small Intestine
Pure
Lower Burner
Ming Men Fire
Impure
Large Intestine
Re-Absorbed
Bladder
Pure
Impure
Impure
Feces
Urine

Figure 6.21. The Metabolic Functions of the Triple Burners are divided into three parts or functions: the Upper Burner, Middle Burner, and Lower Burner. These different functions of the Triple Burners control the movement of various types of Qi in the three stages of energy production:

Receiving—The Upper Burner, also known as mist, includes the organs from the diaphragm upwards (the Pericardium, head, throat, Lungs, and Heart). The Upper Burner assists the Spleen in directing the body's clean fluids upwards and helps the Lungs in dispersing and scattering the fluids to the skin and muscles.

Rotting and Ripening—The Middle Burner, also known as the muddy pool, and includes the area between the diaphragm and umbilicus (Stomach, Spleen, and Gall Bladder). The Middle Burner assists the Stomach in the transformation and transportation of Fluids and Liquids and in directing the impure part downwards.

Excreting—The Lower Burner, also known as the drainage ditch, includes the organs below the umbilicus (Liver, Kidneys, Intestines, and Bladder). The Lower Burner assists the Small Intestine, the Blood, and the Kidneys in transforming and transporting liquids and wastes.

with the Heart and Pericardium and are affected by the emotion of joy.

When the energy of the Heart is strong and pure (without guilt), and the desires and thoughts of an individual are at peace, then the energy of the body's sexual essence (Jing) will spread into the Triple Burners, and the Blood will flourish within the individual's vessels. If the "fire of desire" is allowed to Heat and combine with the energy of the Triple Burners, the energy of the individual's sexual essence will overflow, mixing itself with the energy of the Mingmen and will leave the body via the reproductive organs and tissues. This leads to Jing and Qi depletion.

THE TRIPLE BURNERS' ENERGY FLOW

The Triple Burner Channels store more Qi than Blood, and act more on the energetic and nervous functions of the body than on physical substance and Blood functions. At the high-tide time period (9 p.m. to 11 p.m.), Qi and Blood abound in the Triple Burner Channels, and can therefore be more easily dispersed and purged at this period; whereas during low-tide (9 a.m. to 11 a.m.), they can be more readily tonified. The Triple Burner Channels' energy acts on the skin, muscles, and nerves found along their pathways.

WESTERN MEDICAL PERSPECTIVE

Western medicine recognizes no translation of, or reference to the Triple Burners.

PATHOLOGICAL MANIFESTATIONS

The main diseases along the Triple Burner Channels involve the face, ear, cheek, larynx, and neck. Diseases of the Triple Burner Channels also include disorders of the back of the upper extremities from the midline to the upper arm and forearm.

When diagnosing problems due to dysfunctions of the Triple Burners, the Qigong doctor considers the following.

1. A blockage of the Wei Qi located within the Upper Burner causes an impairment of the Lungs' dispersing function. This can result in the invasion of the Lungs by External Evils (e.g., Wind and Heat, etc.), that penetrate the Pericardium (which corresponds to the initial stage of externally contracted Heat diseases).
2. A blockage of the Ying Qi located within the Middle Burner causes an impairment of the Spleen's transporting function. This can result in gastrointestinal Heat stagnation, and cause Spleen and Stomach Damp Heat (which corresponds to the second stage of externally contracted Heat diseases).
3. A blockage of the Body Fluids located within the Lower Burner causes an impairment of the Bladder's transformation function. This results in the deep penetration of Toxic Evils, weakening the body's Kidney Yin. This in turn can cause Deficient Liver Blood, and Wind stirring due to Empty Yin (this corresponds to the advance stages of externally contracted Heat diseases).

UNDERSTANDING CHANNEL PATHOLOGY

Channel pathology is the oldest of all the modes of pathological pattern classification, dating back to the Spiritual Axis from the *Yellow Emperor's Classics on Internal Medicine*. In understanding a channel's pathology, the Qigong doctor takes into consideration several aspects of the patient's energy flow (i.e., the channels are viewed as exterior, whereas the organs are viewed as interior). Channel pathology is often related to organ disturbances, but it can also be distinct from organ pathology (Figure 6.22).

The disease of one channel may cause disease in other channels and organs. Likewise, tonification of one channel may cause a tonification of other channels and organs.

THE FOUR CAUSES OF CHANNEL PATHOLOGY

1. The Invasion of External Pathogens such as Cold, Wind, Heat, and Damp leads to channel pathology. The exogenous pathogenic factors often settle in the joints, causing Bi Syndrome (painful obstruction). Channel pathology is quite closely related to joint pathology. In Traditional Chinese Medicine, joints are important to the circulation of Qi and Blood. Qi and Blood gather and concentrate in the joints. Qi enters and exits the channels at the joints. The Five Source Points, also called Shu Points (see Chapter 8), are usually located on

of near the joints. It is at these points that the External pathogenic influences may enter the body and settle in the joints. These External pathogenic influences upset the Yin and Yang balance and block the flow of Qi and Blood, causing pain and swelling. The body's joints are also affected by Deficient Qi and Blood, causing local weakness and pain from lack of movement.

2. Physical strain or the overuse of certain joints can cause local stagnation that creates pain and weakness.
3. Injuries, trauma, and strain can cause local stagnation resulting in stiffness, bruising, and pain.
4. Internal organ disharmonies may also affect the channels.

DIFFERENTIATION BY CHANNEL FULL/EXCESS AND EMPTY/DEFICIENT

When a channel is too full, its pattern characteristics are that of intense pain, stiffness, contractions, and cramps. A red color along the flow of the channel indicates Heat; a bluish color along the flow of the channel indicates Cold.

When a channel is Empty, its pattern characteristics are that of a dull ache, weakness in the muscles, numbness, and muscle atrophy along the channel.

DIFFERENTIATION OF CHANNEL PATTERNS BY SPECIFIC CHANNELS

This clinical overview of the body's channels was originally expressed through the knowledge found in the Spiritual Axis (for more in-depth dissertation please see *The Foundations of Chinese Medicine* by Giovanni Maciocia).

1. The diseases of the Gall Bladder Channels may cause: Alternating chills and fever, headache, acute onset of deafness, pain in the hip and the sides of the body, pain along the lateral sides of the legs, and pain and distention of the breasts.
2. The diseases of the Liver Channels may cause: Headache, pain and swelling of the eyes, and cramps in the legs.
3. The diseases of the Lung Channels may cause: Fever, aversion to cold, stiffness in the chest, pain in the shoulders, clavicle, and arms.
4. The diseases of the Large Intestine Channels may cause: Sore throat, toothache, nosebleed, runny nose, swollen and painful gums, swollen eyes, and pain along the channels.
5. The diseases of the Stomach Channels may cause: Pain in the eyes, nosebleed, neck swelling, facial paralysis, cold legs and feet, and pain along the channels.
6. The diseases of the Spleen Channels may cause: Vaginal discharge, weakness of the leg muscles, and a cold feeling along the channels.
7. The diseases of the Heart Channels may cause: Pain in the eyes, pain along the scapula, and pain along the inner side of the arms.
8. The diseases of the Small Intestine Channels may cause: Pain and stiffness in the neck, and pain along the lateral side of the scapula, elbow, and arms.
9. The diseases of the Bladder Channels may cause: Fever and aversion to cold, headache, stiff neck, pain in the lower back, pain in the eyes, pain in the backside of the leg along the channels.
10. The diseases of the Kidney Channels may cause: Lower back pain and pain in the sole of the feet.
11. The diseases of the Pericardium Channels may cause: Stiff neck, contraction of the elbow and hand, and pain along the course of the channels.
12. The diseases of the Triple Burner Channels may cause: Alternating chills with fever, acute onset of deafness, pain and discharge from the ear, pain at the top of the shoulders, pain in the elbow, and pain along the course of the channels.

SUMMARY OF TWELVE PRIMARY CHANNEL PATHOLOGY

The clinical significance of studying the Twelve Primary Channels is evident through the observation of certain pathological manifestations that indicate specific patterns peculiar to that channel and its internal organ. The quality, quantity and proportions of Qi and Blood circulation

Twelve Primary Channels	**Pathologies**
Bladder	• Diseases of the top of the head, brain, neck, back, lumbar and sacral region • Diseases of the back of the leg and thigh and the external side of the foot
Gall Bladder	• Pain in upper right- and left-quadrants of abdomen • Diseases of the head, face, eye, ear • Diseases of the external sides of the lower extremities
Heart	• Diseases that exert pressure on the brain, eyes, or pharyngeal wall • Diseases of the Heart and lateral side of the chest • Diseases of the ulnar palmar side of the upper extremities • Insomnia, impairment of consciousness, amnesia, and psychosis
Kidneys	• Diseases that cause general deterioration of the entire body • Weakness in the lower extremities and lumbar pain • Hot sensations deep inside the feet
Large Intestine	• Diseases of the lower part of the face, nose, oral cavity, teeth, throat, and front part of the neck • Diseases of the back and radial side of the upper extremities
Liver	• Swelling and a distended sensation of the hypochondrium • Diseases of the lower abdomen and genital organs
Lungs	• Chest and Lung diseases • Diseases on the radial side of the upper arm and palmar area of the hand
Pericardium	• Diseases of the Heart, front of the chest, major blood vessels • Diseases of the midline to upper palmar side of the upper extremities • Mental abnormalities
Small Intestine	• Diseases of the face, ear, cheek, lower jaw, neck, and throat • Diseases of the back ulnar side of the upper extremities
Spleen	• Diseases of the tongue and throat • Gastrointestinal diseases (disturbances of digestion and absorption of food) • Diseases of the inner side of the lower extremities
Stomach	• Diseases of the face, nose, oral cavity, teeth, throat, and front of the neck • Diseases of the abdomen, the frontal part of the lower extremities and gastrointestinal area • Certain psychiatric diseases
Triple Burners	• Diseases of the face, ear, cheek, larynx, and neck • Diseases of the back of the upper extremities from the midline of the torso to the upper arm and forearm

Figure 6.22. Pathologies of the Twelve Primary Channels

through each of the Twelve Primary Channels has a vital impact on all the body's organ systems. These Qi and Blood flow concepts define the reciprocal relationships existing between the body's internal organs, channels, and energetic points situated throughout the body.

Figure 6.22 describes some of the most common Twelve Primary Channel pathologies, and their clinical manifestations along the "root and branches" of these channels.

The term "root and branch," is used to describe the difference between the medial and lateral, upper and lower orientations of the channels and their points of origin. They are also used to describe the progression of a disease, as well as the priorities and sequence of the Qigong doctor's treatment.

Specifically, the word "branch" is used to describe the channels' flow of Qi and Blood and the progression and direction of a disease. The word "root" is used to described the channels' internal organ, or the origin of a disease.

CHAPTER 7

THE EIGHT EXTRAORDINARY VESSELS AND COLLATERALS

THE EIGHT EXTRAORDINARY VESSELS

Extending from the body's Taiji Pole are the Three Dantians, Five Jing Shen, and the Eight Extraordinary Vessels. These energy systems feed all the vital organs and the body's Twelve Primary Channels. The Eight Extraordinary Vessels are so called because of they differ in energetic function from the Twelve Primary Channels. These eight vessels have an extraordinary ability to regulate the deeper energetic reservoirs of the body. They are the first vessels (or channels) to form in the developing fetus, and are sometimes called the Eight Ancestral Channels, Eight Prenatal Channels, Eight Preheaven Channels, or Eight Psychic Channels.

These vessels represent the merging of the mother's and father's energy, and the linking of the body's prenatal and postnatal energies. They functionally connect to the Twelve Primary Channels and circulate the Jing Qi (Essence Energy) throughout the body.

The energetic expansion and contraction of the Eight Extraordinary Vessels affects the creation and development of the baby's tissues up until the time of birth. In energetic embryology, the three-dimensional space of the impregnated egg is viewed as an object that can be described by eight different surfaces along four axes. Each of the Eight Extraordinary Vessels corresponds with one of these directions:

- anterior/posterior—Governing and Conception Vessels
- superior/inferior—Yin and Yang Linking Vessels
- right/left—Yin and Yang Heel Vessels
- interior/exterior—Thrusting and Belt Vessels

THE FUNCTION OF THE EIGHT EXTRAORDINARY VESSELS

The Eight Extraordinary Vessels have neither a direct connection nor an internal/external relationship with the internal organs. Similar to the Three Dantians' function of distributing the body's energy, these Eight Extraordinary Vessels are also reservoirs that regulate the distribution and circulation of Jing and Qi inside the body. They are the foundation of the body's energy, bridging the Yuan Qi (Original Prenatal Energy) with the body's postnatal energy.

The Eight Extraordinary Vessels serve as reservoirs of Qi. When these reservoirs become full, the energy overflows into the center channel or Taiji Pole. This stimulation of the Taiji Pole expands consciousness and increases perceptual intuition.

The Eight Extraordinary Vessels have five main functions: They serve as reservoirs of Qi, store and circulate Jing Qi, circulate the Wei Qi, regulate the body's life cycles, and integrate the six primary Yang organs with the Six Extraordinary Organs and with the Kidneys.

1. They Serve as Reservoirs of Qi. If the Qi flow of the Twelve Primary Channels becomes Excessive, they overflow into the Eight Extraordinary Vessels, which act as Qi reservoirs, receiving the Excess Qi for storage and distribution, while at the same time regulating the energy flow. If the Qi flow of the Twelve Primary Channels becomes Deficient, they can draw from the reservoirs of energy stored within the Eight Extraordinary Vessels which again regulate the body's energy flow, bringing it back into balance.
2. They Store and Circulate Jing Qi. The Eight Extraordinary Vessels draw their energy from the Kidneys and are responsible for storing and circulating the body's Jing Qi throughout the tissues, particularly to the skin and hair and to the Six Extraordinary (Curious) Organs, also known as the Six Ancestral Or-

gans. The Six Extraordinary Organs are the Brain, Bone, Marrow, Blood, and Gall Bladder (also included is the Uterus in women).

3. They circulate the Wei Qi (Protective Energy) to protect the body against invasion by External pathogens. The Governing, Conception, and Thrusting Vessels are primarily responsible for circulating the body's Wei Qi over the thorax, abdomen, and back.

   The Eight Extraordinary Vessels provide the link between the Kidneys Jing and the Wei Qi. Although the Wei Qi is circulated by the Lungs, its root is in the Kidneys. This illustrates how the Kidneys play an important role in supporting the Lungs function of circulating the body's Wei Qi. The Kidneys function on the Wei Qi field and therefore the immune system can become vulnerability to pathogenic factors, as well as in causing allergic diseases, e.g., asthma. It also demonstrates why the Kidneys are always at the root of latent Heat syndromes (chronic fatigue), caused by Kidney Deficiency.
4. The Eight Extraordinary Vessels regulate the body's Life Cycles. In the first chapter of *the Yellow Emperor's Classic of Internal Medicine*, the life changes in women (every seven years) and men (every eight years) are governed by the Conception and Thrusting Vessels. These life cycles are related to the body's Jing and the Eight Extraordinary Vessels' role in moving and circulating the body's Jing (see Chapter 13).
5. They Integrate the Six Extraordinary (Curious) Organs with the Six Primary Yang Organs and the Kidneys. The Eight Extraordinary Vessels provide the link between the body's brain, uterus, blood vessels, Gall Bladder, Marrow and bones, and the body's internal energy flow.
   a. The Brain is Regulated by the Governing Vessel and the Yin and Yang Heel Vessels.
   b. The Uterus is regulated by the Thrusting and Conception Vessels.
   c. The Blood Vessels are regulated by the Thrusting Vessels.
   d. The Gall Bladder is regulated by the Belt Vessel.
   e. The Marrow is regulated by the Thrusting Vessels.
   f. The Bones are regulated by the Thrusting and Conception Vessels.
6. They Integrate the Four Seas. The *Magic Pivot (Ling Shu, Hai Lun)* states, "People have Four Seas... the Sea of Marrow, the Sea of Blood, the Sea of Qi, and the Sea of Grain and Water." The Eight Extraordinary Vessels provide the link between the body's Four Seas and the body's internal energy flow.
   a. The Sea of Marrow is the brain, and it is related to the Governing Yin and Yang Heel Vessels. The Sea of Marrow points are located on the Governing Vessel GV-16 and GV-20. When the Sea of Marrow is Deficient, there will be headaches and dizziness.
   b. The Sea of Qi is located in the chest of the center, and is regulated by the Conception Vessel CV-17. Some Medical Qigong schools maintain that there are two reservoirs of Qi: the Middle Dantian, being the Sea of Postnatal Qi, and the Lower Dantian, being the Sea of Prenatal Qi (which is regulated by the Qihai CV-6 point). When the Sea of Qi is in Excess, there is a feeling of fullness in the chest, dyspnea (urgent breathing), and a red complexion. When the Sea of Qi is Deficient, there is weak energy and insufficient speech.
   c. The Sea of Nourishment (also known as the Sea of Grain and Water) is the Stomach, and it is regulated by the Thrusting Vessels, which are accessed by the St-30 points. When the Sea of Water and Grain is in Excess, there is a feeling of fullness in the abdomen. When the Sea of Water and Grain is Deficient, there is a feeling of hunger with an inability to eat.
   d. The Sea of Blood (also known as the Sea of the Twelve Primary Channels) is related to the Thrusting Vessels, the Liver, and Xuehai Sp-10 points. The points can

also be accessed through Bl-11, St-37, and St-39. When the Sea of Blood is in Excess, the body feels big; When the Sea of Blood is Deficient, the body feels small.

THE EIGHT EXTRAORDINARY VESSELS AND MEDICAL QIGONG THERAPY

The energetic pathways, functions and use of the Eight Extraordinary Vessels and points in Medical Qigong are often quite different than those taught in acupuncture colleges, even though they may sometimes bear the same names.

Most acupuncturists, with the exception of some Japanese researchers, often pay little attention to the Eight Extraordinary Vessels in diagnosis and treatment. One Medical Qigong doctor from China has claimed that a study done in China showed that the Eight Extraordinary Vessel treatments were far more effective than those of the Traditional Chinese medical protocols. The results, however, were not released because officials did not want to disturb the TCM institutional operations. The reason Medical Qigong makes use of the Eight Extraordinary Vessels, is that they are much easier to access through Qi emission and Medical Qigong self-regulation prescriptions than through acupuncture therapy.

The Eight Extraordinary Vessels have been of special importance to Medical Qigong practitioners for thousands of years, and are viewed as the foundation of the body's energy, the bridge between the Yuan Qi (Prenatal Qi) and the Postnatal Qi. These Eight Extraordinary Vessels affect the body on the deepest level of our basic constitutional energy. In Medical Qigong regulation exercises, the focus on opening the flow of energy through the Eight Extraordinary Vessels is a prerequisite for opening the energy flow in the Twelve Primary Channels. The major purpose of opening the Eight Extraordinary Vessels is to provide a container for storing the Three Forces: Heaven Force (absorbing universal energy), Earth Force (absorbing environmental energy), and Man's Force: Jing, Qi and Shen (Essence, Energy and Spirit).

It is essential for the Qigong doctors to open their Eight Extraordinary Vessels to attain mastery of their energetic body. The Microcosmic Orbit is introduced for purgation, fusion, tonification, and regulation of the Governing and Conception Vessels in the first stages of training. This exercise restores a healthy flow of energy throughout all of the channels and vessels creating a healthy and balanced body.

Through the refinement of their energy, Qigong doctors receive more Qi, and the quality of their Blood changes, i.e., its energetic potential changes to contain more Qi and less Blood. At this advanced state of transformation, Qigong doctors rechannel the flow of energy through their body's Three Dantians, including the "mystical pass" (located within the Upper Dantian chambers of the brain). When the flow of energy is directed to stimulate the Mystical Pass, the Qigong doctors acquire greater awareness and control over their own bodies (physical, mental, emotional, energetic and spiritual), and are then able to enhance their perception and communication with all the other energetic planes of the world (mineral, plant, animal, and human), and with the Dao (or divine).

CLINICAL USE OF THE EIGHT EXTRAORDINARY VESSELS

The Eight Extraordinary Vessels form and establish the foundational energetic pattern for the developing fetus's tissues, as well as the adult's entire body. The clinical use of the Eight Extraordinary Vessels can be divided into several different approaches of energy manipulation to change the energetic patterns within the patient's tissues.

One approach divides the Eight Extraordinary Vessels into four pairs of Yin and Yang vessels. Each of the vessels is grouped according to the same polarity, two pairs of Yin and two pairs of Yang. When paired this way, each set of the Yin and Yang Extraordinary Vessels has a common range of energetic action in terms of the patient's body area.

1. The Conception and Yin Heel Vessels affect the energetic flow to the patient's abdomen, chest, Lungs, throat, and face.
2. The Governing and Yang Heel Vessels affect the energetic flow to the back of the patient's legs, as well as the back, spine, neck, head, eyes, and brain.

3. The Thrusting and Yin Linking Vessels affect the energetic flow to the inner aspect of the patient's legs, as well as the abdomen, Stomach, chest, and Heart.
4. The Belt and Yang Linking Vessels affect the energetic flow to the outer aspect of the patient's legs, as well as the sides of the body, shoulders, and sides of the neck.

ENERGETIC FUNCTIONS OF THE EIGHT EXTRAORDINARY VESSELS

The Eight Extraordinary Vessels can also be categorized is according to their energetic functions.

1. The Conception, Governing and Thrusting Vessels are considered the source of all the other Extraordinary Vessels These three vessels affect the patient's energy at a deep constitutional level. They originate directly from the Kidneys and are connected to the body's Jing.
2. The Yin and Yang Heel Vessels are complementary in that they both flow from the legs (controlling the state of the muscles of the legs) into the eyes (controlling the muscles that open and close the eyes).
3. The Yin and Yang Linking Vessels complement each other by linking the body's Yin and Yang Channels.
4. The Belt Vessel is the only horizontal vessel in the body, encircling the main channels. Its energetic influence is in its ability to affect the circulation of energy in the body, especially within the legs.

Each of the Eight Extraordinary Vessels is also connected to one of the Eight Trigrams (or Eight Natural Manifestations), and can be energetically regulated through the use of the Magic Square. For further treatment and clinical protocol see Chapter 31 regarding the Eight Extraordinary Vessel and the Magic Square.

THE GOVERNING AND CONCEPTION VESSELS

The Governing and Conception Vessels are the main rivers of the body's Yin and Yang energies. They are polar aspects of the body, perfectly complementary, like midnight and midday. They are responsible for the formation of the holoblastic cleavage and the first cellar division of the fertilized ovum in embryological development (see Chapter 2).

In China, Dr. Li Shi Zhen was the first to believe that the Governing and Conception Vessels are two branches of the same source, an inseparable Yin-and-Yang, front-and-back duality. These vessels connect the uterus with the Kidneys, Heart, and Brain.

They originate externally at Huiyin CV-1 point, ascend the front and back of the torso, and form a small circle when the tip of the tongue touches the upper palate in the mouth and the anal sphincter is squeezed. Not only does this action complete the balance of Fire (Heart) and Water (Kidneys) energy, it also increases the body's protective Wei Qi.

Regulating the Conception and Governing Vessels is a priority in Medical Qigong practice. Along these vessels, the Qigong practitioner draws the Yang Fire and Yin Essence up and down his or her body, fusing the Water and Fire energies together. This fusion facilitates a Yin and Yang balance throughout the body.

The Governing and Conception Vessels each have two energy flows on the anterior and posterior vertical midline of the body. Each vessel's pathway is complete, being composed of an ascending energetic flow and a descending energetic flow. The duality of these two medial lines joins at the extremities (the head and perineum), forming one complete circle of energetic current (Figure 7.1).

Both vessels are superimposed on each other, with the energy of the Governing Vessel being predominant up the back and inferior down the front (behind the Conception Vessel); the energy of the Conception Vessel is predominant up the front and inferior down the back (behind the Governing Vessel).

The energetic flow of the Conception Vessel corresponds to Yin, negative polarity, the female aspect, and responds to bass tones; while the energetic flow of the Governing Vessel corresponds to Yang, positive polarity, the male aspect, and responds to treble tones.


The Top of the Head
(Baihui Point)
Descending Qi flow of the Governing Vessel
Descending Qi flow of the Consеption Vessel
Front of Body
Back of Body
Ascending Qi flow of the Conception Vessel
Ascending Qi flow of the Governing Vessel
The Base of the Perineum
(Huiyin Point)

Figure 7.1. The Energetic Flow of the Conception and Governing Vessels

It is important to understand the energetic potential of these two currents flowing in both an ascending and descending direction on the posterior and anterior vertical midline in the body. The energetic movement of these two currents explains why there are two opposite directions of focused concentration used in energy cultivation meditations. One direction follows the Microcosmic Fire cycle along the Governing Vessel (up the spine and down the chest) to stimulate the emotional regulation of the acquired mind (Zhi Shen); the other direction follows the Microcosmic Water cycle along the Conception Vessel (up the chest and down the spine) to stimulate spiritual intuition and activate the perceptions of the Yuan Shen.

THE GOVERNING VESSEL OR DU VESSEL

The word Du translates as "governing," and refers to a general, someone who controls and is in charge. During the development of the embryo, the Governing Vessel is responsible for the development and formation of the medulla oblongata and cerebrum. The Governing Vessel controls all the Yang Channels in the body, and is called the Sea of Yang Channels. It is responsible for nourishing the brain and spinal cord and for consolidating the Yuan Qi in the Kidneys.

The Governing Vessel originates in the Lower Dantian in both men and women. It is composed of many energetic branches, emerging externally at the perineum. The primary branch ascends externally on the midline of the back, over the head and ends in the frenulum of the upper lip. As the Qi flows up the Governing Vessel one branch enters the interior of the spinal column and enters the Kidneys. Another set of branches enters the brain at the Fengfu GV-16 point and ascends internally to the vertex at the Baihui GV-20 point.

From the lower perineum, another set of branches encircles the anus and envelops the external genitals, ascends past the navel, Heart, and throat to circle the mouth. After circling the mouth, it further ascends to the eyes, emerging just below the middle of the eyes. From the inside of the eyes (at the Jingming Bl-1 point), a set of branches follows the Bladder Channels along the forehead, converging at the vertex of the Baihui GV-20 point and enters the brain. From the brain, the Vessel emerges at the Fengfu GV-16 point, and divides into two additional branches which descend the



Figure 7.2. The Governing Vessel (Side View)

back, passing through the Fengmen Bl-12 points along the sides of the spine and enter into the Kidneys (Figure 7.2).

The Governing Vessel tonifies the Kidney Yang and strengthens the spine and back. When the Governing Vessel is excessive, the back becomes stiff; when it is depleted, the head becomes heavy, unstable, and shaky (Figure 7.3).

CLINICAL MANIFESTATIONS

The functions and clinical uses of the patient's Governing Vessel are as follows.

1. To strengthen and control all the Yang Channels of the patient's body (particularly in relation to the Kidney Yang and the brain);
2. To tonify the Kidney Yang and strengthen the patient's spine and back (especially in cases of chronic lower back pain due to Kidney Deficiency);
3. To purge External Wind from the patient's body when symptoms are present, such as runny nose, head ache, fever, and stiff neck;
4. To purge Internal Wind from the patient's body when symptoms are present, such as dizziness, tremors, convulsions, epilepsy, or the condition of Wind Stroke;
5. To strengthen and nourish the patient's brain and Marrow, and for treating such symptoms as poor memory, dizziness, and tinnitus; and
6. To treat depression, due to the Governing Vessel's connection to the body's Jing (Kidneys, lack of willpower), Qi (Heart), and Shen (Brain).

Note: In men, the Governing Vessel is generally treated by itself, and in women, its treatment is combined with treating the Conception Vessel.

PATHOLOGICAL MANIFESTATIONS

1. Symptoms of Excess include diseases of the head (apoplexy, aphasia, epilepsy, headaches, tetanus, etc.), the back, neck, and Kidneys (pain and stiffness in the spinal column), spastic muscle movement of the extremities, night sweating, and Jing Shen disorders (hyperexcitability, hallucinations, etc.).
2. Symptoms of Deficiency result in shaking of the head along with a feeling of heaviness, instability, and an inability to concentrate. The patient lacks physical and mental stamina, displays weakness in character, and may also experience hemorrhoids, sterility, and impotence.


GV-21
GV-20
GV-19
GV-18
GV-17
GV-16
GV-15
GV-14
GV-13
Fengmen
Bl-12
GV-12
Fengmen
Bl-12
GV-11
GV-10
GV-9
GV-8
GV-7
GV-6
GV-5
GV-4
GV-3
GV-2
GV-1
GV-22
GV-23
GV-24
Bl-1
GV-28
GV-25
GV-26
GV-27

Figure 7.3. The Governing Vessel (GV)

THE CONCEPTION VESSEL OR REN VESSEL

The word Ren translates as Conception, and refers to pregnancy, responsibility, or obligation. It can also mean "to accept." The Conception Vessel governs all the Yin Channels of the body and is called the Sea of Yin Channels. It nourishes the Yuan Qi of all Five Yin Organs. The Conception Vessel originates from the Lower Dantian, and specifically in the uterus in females (Figure 7.4).

Functionally, the upper third of the Conception Vessel, on the sternum, controls respiratory functions; the middle third, on the epigastrium, controls digestive functions; and the lower third, on the abdomen, controls the urogenital functions (Figure 7.5).

In women the Conception Vessel is primarily responsible for nourishing the uterus and the genital system and determines the seven-year life cycles. It links the Yin energy with all aspects of conception and reproduction. The Conception Vessel, along with the Thrusting Vessels, have an important relationship with obstetric diseases related to the development of the fetus, delivery, and menstruation.

CLINICAL MANIFESTATIONS

The functions and clinical uses of the patient's Conception Vessel are as follows.

1. To strengthen and nourish the Yin energy of the patient's body (especially in women after menopause) and harmonize the Lungs and Kidneys;
2. To regulate the energy of the reproductive system, tonifying the Blood and Yin, and to reduce the effects of Heart Empty-Heat symptoms developed from Kidney Yin Deficiency after menopause (i.e., night sweating, hot flashes, anxiety, mental irritability, insomnia and dizziness, etc.);
3. To promote Blood supply to the uterus and regulate menstrual disorders (i.e., dysmenorrhoea, menorrhagia, amenorrhoea, and metrorrhagia);
4. To move the Qi in the patient's Lower Burner and treat abdominal lumps, as well as myomas, fibroids, and carcinoma in the woman's uterus, and hernia in men; and
5. To stimulate the energetic interaction of the Lungs Channels descending Qi function, and the Kidneys' function of receiving and holding the Lung Qi, which can, when malfunctioning, result in asthma.



Figure 7.4. The Conception Vessel (Side View)

PATHOLOGICAL MANIFESTATIONS

1. Symptoms of Excess include diseases of the reproductive and gastrointestinal systems (hemorrhoids, diarrhea, decreased urination, etc.). In the male, problems in the Conception


St-1
CV-24
CV-23
CV-22
CV-21
CV-20
CV-19
CV-18
CV-17
CV-16
CV-15
CV-14
CV-13
CV-12
CV-11
CV-10
CV-9
CV-8
CV-7
CV-6
CV-5
CV-4
CV-3
CV-2
CV-1

After emerging externally at the Huiyin (CV-1) point in the perineum, the main branch of the Conception Vessel ascends through the midline of the front of the torso, flowing to the mouth. After encircling the mouth it branches to connect with the Yinjiao (GV-28) points, and both branches ascend to the Chengqi (St-1) points beneath the eyes.

The internal branch of the Conception Vessel originates from the pelvic cavity and ascends the body along the spine, ending at the mouth.

Figure 7.5. The Conception Vessel (CV)

Vessel produce sterility. In the female, the Conception Vessel can cause menstruation problems such as leukorrhea and dysmenorrhea. Other female problems include breast pain, paralysis after delivery, emaciation, and sterility. Other problems of the female reproductive system include the external genitalia and vulva, vagina, and cervix disorders.

2. Symptoms of Deficiency include abdominal pains (hernia), pruritus, and a heavy feeling in the hips, lower ribs, and lumbar area.

THE THRUSTING VESSELS AND THE BELT VESSELS

The Thrusting and Belt Vessels balance the external tissues and internal organ energies, controlling an Excess or Deficient condition by regulating the upper and lower, as well as left and right, energetic quadrants.

The Belt Vessel is responsible for the second cellular division of the fertilized ovum in embryological development (see Chapter 2).

THE THRUSTING VESSELS OR CHONG VESSELS

The word Chong translates as "a street" and expresses the idea of passing or penetrating through something. This passing through action refers to its function as the vital pathway for alchemical transformation, used to produce energetic change (Jing to Qi, Qi to Shen and vise versa). The Thrusting Vessels, also called the Penetrating Channel, and are regarded as the Sea of Blood and the Sea of the Twelve Regulating Channels. They regulate both the Qi and Blood of all Twelve Primary Channels and extend to the anterior, posterior, upper, and lower parts of the body. During the development of the embryo, the Thrusting Vessels are responsible for the development of the adrenal glands and the cortex.

The Thrusting Vessels originate in the Lower Dantian. The Qi of the Thrusting Vessels travel to the head and face to flow into the Chong and penetrate the lower limbs, irrigating the body's Yin (Figure 7.6). According to some Chinese doctors, all energetic points that have Chong in their names relate to the Thrusting Vessels (i.e., Qichong St-30, Taichong St-42, and Shaochong Ht-9).

Along with the Conception Vessel, the Thrusting Vessels are responsible for regulating the changes in life cycles that occur every eight years in men, and every seven years in women. Abnormalities of the Thrusting Vessels during the beginning of pregnancy result in the mother's body aborting the fetus. Abnormalities of the Thrusting Vessels during the end of pregnancy result in an inability to expel the placenta.

The Thrusting Vessels control the woman's menstruation in all aspects, influencing the supply and amount of Blood in the uterus, and nourishing the woman's Jing. They also flow along the Kidney Channels and are related to the muscles of the abdomen and the penis (and are responsible for tightening the abdominal muscles).

THE ENERGETIC PATHWAY OF THE THRUSTING VESSELS

The classical description of the Thrusting Vessels' energy flow begins inside the uterus in women (the corresponding lower abdominal area in men), continuing down to the perineum. From the perineum, one branch ascends inside the spinal column, while four other branches flow externally.

Two external energetic rivers ascend up the front of the body alongside the Kidney Channels and enter into the chest. They then ascend through the throat, encircling the lips, and end at the corner of the eyes. When the Thrusting Vessels are full and overflowing (through meditation), they radiate a sparkling white-light energy, which can be observed to extend from the upper chest to the eyes.

From the perineum, two other external energetic rivers descend down the inner aspect of the thighs (one on each leg), along the Spleen Channels. They divide again at the medial malleolus. One set of branches flows into the big toes, a second set of branches terminates at the bottom of each foot.

CLINICAL MANIFESTATIONS

The functions and clinical uses of the patient's Thrusting Vessels are as follows.

1. To strengthen, nourish, and regulate weak


Kd-21
Kd-20
Kd-19
Kd-18
Kd-17
Kd-16
Kd-15
CV-7
Kd-14
Kd-13
Kd-12
St-30
Kd-11
Kd-21
Kd-20
Kd-19
Kd-18
Kd-17
Kd-16
Kd-15
Kd-14
Kd-13
Kd-12
St-30
CV-1

Figure 7.6. The Thrusting Vessels

constitutions with digestive symptoms (e.g., abdominal distension, poor appetite, and poor assimilation of food);

2. To move the Blood of the Heart to relieve symptoms of pain and stiffness of the chest (the Thrusting Vessels control all the Blood in the connecting channels);
3. To purge Qi and Blood stagnation in the abdomen and chest;
4. To treat feelings of anxiety (within the chest) caused by Rebellious Qi; One of the Thrusting Vessels' most important pathologies is Rebellious Qi (Qi that moves in the wrong direction, going upwards instead of downwards). Feelings of anxiety that arise in the patient's abdomen and ascend to their chest are especially indicative of this malfunction;
5. To treat gynecological problems (hot flashes), when the Qi of the Thrusting Vessels rises upwards, and causes the patient's hands and feet to get cold, the face to get hot, and a feeling of fullness in the chest. The treatment is to regulate the Thrusting Vessels and subdue the Rebellious Qi in the Chong Vessel. If there are accompanying emotional problems and Liver Qi stagnation, then also treat the patient's Lv-3 points; and
6. To treat Rebellious Qi caused by the energy of the Thrusting Vessels rebelling upwards; the symptoms are oppressive feelings in the chest, as well as dizziness, nausea, and vomiting.

PATHOLOGICAL MANIFESTATIONS

The main diseases associated with the patient's External Thrusting Vessels include diseases of the Heart, fullness in the chest and abdomen, gastritis, abdominal pain, and convulsive diseases. If a woman's Thrusting Vessels are Deficient or Empty she may develop such conditions as amenorrhoea, scanty periods, or late periods. If there is stagnant Qi and / or Blood in the Thrusting Vessels, she may experience dysmenorrhoea. Abnormalities of the Thrusting Vessels also result in the mother aborting the fetus.

The Thrusting Vessels work with the Qi of the Kidney Channels to control the brain's physiological functions. If the energy from the Thrusting Vessels to the cortex becomes Deficient, this can inhibit the development of the brain.

THE BELT VESSEL OR DAI VESSEL

The word Dai translates as a "belt" or "girdle," and refers to the action of supporting something. The Belt Vessel is the only horizontal vessel in the body. Beginning at the Mingmen, this vessel encircles the waist like a belt, dipping down into the lower abdominal region anteriorly and running across the lumbar region posteriorly. It connects with the Gall Bladder's -26, -27, and -28 points and crosses the Conception Vessel at CV-4. Many sources say that it connects with the Liver -13 (at the free ends of each 12th rib). It binds, joins, and controls all the channels of the body, exerting an influence on the energetic circulation of the body's Governing and Conception Vessels (Figure 7.7).

Medical Qigong schools teach that the Belt Vessel circle wraps the entire body, like a enveloping cocoon, flowing from the feet to the head. The waist is considered the "hub" of the energetic wheel, and the access points of the Belt Vessels center channel (which circles the waist) is used to control the entire vessel. As the energy of the body increases (through Qi cultivation), the Qi within the entire Belt Vessel increases, circle wrapping the tissues from feet to head, increasing the body's Wei Qi fields (Figure 7.8).

In addition, the Belt Vessel keeps both the Yin and Yang Channels under control, connecting all of the leg Yin and Yang channels as they traverse the body's trunk. As a result, the Belt Vessel assists in regulating the circulation of Qi in those channels, especially from the waist down.

The Belt Vessel has an important influence on the body's physiology by encircling the leg channels, influencing the circulation of energy to and from the legs, as well as influencing the energetic actions of the genitals, waist, and hips. This vessel not only restrains the flow of the body's Liver and Gall Bladder Qi, but also harmonizes the ascending and descending flows of energy from the Kidneys and Spleen through its connection with the Kidney Divergent Channel.



Figure 7.7. The Center of the Belt Vessel



Figure 7.8. The Belt Vessel winds up the body like an energetic coil.

CLINICAL MANIFESTATIONS

The functions and clinical uses of the patient's Belt Vessel are as follows.

1. To treat impaired circulation of Qi in the leg channels resulting in such symptoms as cold legs and feet, or tense leg muscles (gastrocnemius and tibiales). This condition is due to Liver Blood not moistening the sinews of the legs;
2. To treat impaired circulation of Qi and Blood that cause numbness, weakness, atrophy, or motor impairment of the leg muscles, due to a Deficiency of energy in the Stomach and Spleen Channels;
3. To tonify and harmonize the circulation of

Liver and Gall Bladder Qi due to Excess patterns of Liver energy;
4. To disperse Damp Heat in the genitals that has resulted in symptoms such as difficulty or burning during urination;
5. To treat hip pain caused by Deficient Liver Blood (leading to sinew and joint malnourishment and Excess of Liver Yang; and
6. To regulate the lower abdomen due to a Belt Vessel imbalance, causing symptoms such as a sagging waist or bloated abdomen.

PATHOLOGICAL MANIFESTATIONS

1. Symptoms of Excess include pain in the back (lumbar region), and sides of the lower abdomen, as well as weakness in the shoulders, upper extremities, and lower limbs. Symptoms may also include weakness in the opposite sides of the body (e.g., eye, breast, ovary, etc.), and a feeling of heaviness in the body and abdomen (as if carrying 5,000 coins) due to exposure to Dampness.
2. Symptoms of Deficiency have physical sensations similar to that of "sitting in cold water" up to the waist. This description generally refers to pain, weakness, and a cold, heavy sensation in the patient's lumbar and sacral regions. Other symptoms include umbilical, abdominal and lumbar pain, as well as a feeling that something like a stick is pressing against the groin. There can also be abdominal fullness and distention. In women, there may be an abnormal white vaginal discharge, and a prolapse of the uterus.

THE YIN AND YANG HEEL VESSELS OR QIAO VESSELS

The word Qiao translates as "the heel" or "to stand on the toes," and refers to the action of kicking one's foot as high as possible. The Yin and Yang Heel Vessels flow along the medial and lateral aspects of the lower legs and torso, connecting at the inner canthus (by the eyes). They link the channel energy of the body's Yin and Yang Channels and regulate the movement of all four limbs. They also control the amount of energy being used by all the other channels in the body. Once these vessels are full, they relax the tissues, enabling the limbs to become more dexterous.

The Yin and Yang Heel Vessels are sometimes called Bridge Channels, because they act like a bridge linking the stored Qi in the body with the areas in need of Qi. When any channel uses more than its share of energy, other channels become Deficient. Thus the Heel Vessels seek to ensure that energy is always distributed in a balanced way.

The Yin Heel Vessels are an offshoot of the Kidney Channels at the front of the body, while the Yang Heel Vessels are an offshoot of the Bladder Channels at the back of the body. Together, the Yin and Yang Heel Vessels can be used to treat structural imbalances and to harmonize the right and left sides of the body.

Because the Heel Vessels cause the motor nerves to develop during the formative stages of the embryo, the Chinese believe the Yang Heel Vessels cause little boys to be more physically active (running, jumping, etc.), while the Yin Heel Vessels cause little girls to be less actively inclined.

THE YIN HEEL VESSELS

The Yin Heel Vessels control the Yin of the left and right sides of the body. The Yin Heel Vessels influences the male and female reproductive system, as well as the lower abdomen in women.

When Yang energy is slowed down in the Heel Vessels, the Yin energy moves more rapidly. The Excess Yin causes the following problems: sleepiness, the inability to keep the eyes open while trying to stay awake, hypotension, choking, painful urination, stomach rumbling, vomiting, diarrhea, difficult bowel movements, and unconsciousness. Excess Yin in women also causes a difficult labor. Also, when the Yin Heel Vessels are in Excess, the inner leg muscles are tight, while the outer leg muscles are loose. Weakness in the Yin Heel Vessels can cause the feet and ankles to invert, whereas an Excess condition can cause the feet to turn outwards.

The Yin Heel Vessels begin at the superficial part of the ankles, just below the medial malleolus of the tibial bones at the Kd-2 points. They continue up the front of the body, ending at the inner



Figure 7.9. The Yin Heel Vessels

corners of the eyes, where they join the Yang Heel Vessels (Figure 7.9).

CLINICAL MANIFESTATIONS

The functions and clinical uses of the patient's Yin Heel Vessels are:

1. To treat symptoms of Excess conditions in the Lower Burner in women (e.g., abdominal distension, difficult delivery, or the retention of the placenta, abdominal masses, lumps, and fibroids);
2. To structurally balance the left and right sides of the body;
3. To treat disturbances of sleep (e.g., insomnia or somnolence); and
4. To treat certain cases of atrophy (e.g., when the muscles of the inner aspect of the leg are loose and the outer leg muscles are tight).

PATHOLOGICAL MANIFESTATIONS

1. Symptoms of Excess of the Yin Heel Vessels include: lower abdominal pain, vomiting, difficult bowel movements, and spasms on the medial side of the legs. The Yin Heel Vessels also control diseases of the eyes (watery eyes, heavy sensations of the eyelids or an inability to open the eyes), migraines, congestive headaches, and hypersomnia. Abnormalities of the Yin Heel Vessels cause pregnant women to have difficult labor.
2. Symptoms of Deficiency include: Aggravations of symptoms during the evening time, nocturnal headaches, insomnia, cramps, or convulsions.

THE YANG HEEL VESSELS

The Yang Heel Vessels control the Yang of the left and right sides of the body. Abnormalities of the Yang Heel Vessels in newborns cause vomiting of milk.

When Yin energy is slowed down in the Heel Vessels, the Yang energy moves more rapidly. The Excess Yang causes the following problems: insomnia, difficulty in closing the eyes, painful eyes, hypertension, stiff back and waist (inability to bend down), thigh tumors, bad colds, spontaneous sweating, headaches, paralysis of the arms and legs, deafness, epilepsy, nose bleeding, swelling of the body, pain in the joints, and head sweating. Excess Yang can also cause the vomiting of milk in infants.

Weakness in the Yang Heel Vessels can cause foot and ankle eversion, while Excess can cause foot inversion. Also, when the Yang Heel Vessel is in Excess, the inner leg muscles are loose and the outer leg muscles are tight.

The Yang Heel Vessels begin on the outer side of the ankles below the lateral malleolus, at the Bl-62 points. From there, they continue to ascend the outside of the thigh and the back to end just below the eyes at the Bl-1 points, where they communicate with the Yin Heel Vessels near the eyes (Figure 7.10).

CLINICAL MANIFESTATIONS

The functions and clinical uses of the patient's Yang Heel Vessel are:

1. To treat acute Excess conditions of the lower back (e.g., aches due to spasm or invasion of Cold) and pain along the Bladder Channels of the legs;
2. To subdue Internal or External Wind from the head (e.g., facial paralysis, severe dizziness, and aphasia); and
3. To purge Wind-Heat and Wind-Cold manifesting in symptoms, such as sneezing, head ache, runny nose, and stiff neck.

PATHOLOGICAL MANIFESTATIONS

1. Symptoms of Excess include: Stiffness of the back and waist, lumbar pain, spasms on the outer side of the legs, tumors of the thighs, nocturnal epileptic seizures, and insomnia or restless sleep. The Yang Heel Vessels are also involved with diseases of the eyes such as dry and itchy eyes.
2. Symptoms of Deficiency include: Fatigue, lassitude and weakness during the day, and aggravations of symptoms from stress during the day. These symptoms improve as the night progresses.

According to some Traditional Chinese Medical Classics, if epilepsy occurs during the daytime, Qigong and moxa are given on the Yang Heel Vessels; however, if epilepsy occurs at night, Qigong and moxa are given on the Yin Heel Vessels.



Figure 7.10. Side View of the Left Yang Heel Vessel

THE YIN AND YANG LINKING VESSELS OR WEI VESSELS

The word Wei translates as "to link" or "bind" and refers to a rope that is tied around something, pulling it down and securing it. The Linking Vessels are sometimes called the Regulator Channels. The Linking Vessels are divided into Yin and Yang energetic pathways.

Both Yin and Yang Linking Vessels start at the lower legs and flow upwards to the head, along the medial and lateral aspects of the lower legs and torso. When the Linking Vessels reach the neck and back of the head, they join the Conception and Governing Vessels. Secondary Vessels, called the Yu (surplus) Vessels, branch away from the energetic flow of the major Vessel, connecting the energetic flow of each Yin and Yang Linking Vessel to the hands.

Instead of serving as streams transporting Qi and Blood, these two vessels act as lakes that store Qi and Blood that overflows from other vessels. Together, these four vessels regulate the circulation of Qi and Blood for the whole body, store the overflowing Qi and Blood, and release the Qi and Blood into the channels in the event of insufficiencies.

THE YIN LINKING VESSEL

The Yin Linking Vessels lie on the medial axis of the body. They help maintain the connection to all the Yin Channels. They begin at the Kd-9 points at the inner side of the lower legs and ascend up the sides of the abdomen and chest. They move toward the front of the body, along the sides of the chest to the tips of the nipples. At the Ruzhong (St-17) Breast Center points they split into two sets of branches. One set of branches connects with the Conception Vessel at the neck. The other set of branches becomes the Yin Yu Vessels, and extends from the chest, over the shoulders and down the inside of the arms following the route of the Pericardium Channels. Just above both wrist folds on each arm, each branch energetically pools at the Neiguan (Pc-6) Inner Pass points, before it flows into the palms. The Pc-6 points are therefore considered the Master Points for the Yin Linking Vessels (Figure 7.11).



Figure 7.11. The Yin Linking Vessels

The Yin Linking Vessels are responsible for moving the Yin energy and regulating the Blood and inner parts of the body. They connect with all the body's Primary Yin Channels: Liver, Heart, Spleen, Lung, Kidney, and Pericardium. When the Yin energy is slowed down in the Linking Vessels, the Yang energy moves more rapidly. Therefore, if the Yin Linking Vessels become unbalanced, the Excess Yang condition can cause the patient to suffer from Heart pain.

CLINICAL MANIFESTATIONS

The functions and clinical uses of the patient's Yin Linking Vessels are:

1. To tonify the Heart (for symptoms of pain, stiffness, tightness and oppression in the chest, as well as mental depression, anxiety, apprehension, and nightmares);
2. To treat Deficient Yin and Blood conditions, especially if accompanied by psychological conditions, such as mental restlessness, anxiety, and insomnia; and
3. To treat headaches located in the back of the neck due to Blood Deficiency.

PATHOLOGICAL MANIFESTATIONS

1. Symptoms of Excess include diseases of the Heart such as hypertension, delirium, nightmares, etc., as well as, cardialgia (tightness and oppression in the chest), difficulty in swallowing, convulsive diseases, contracted feeling in the Lungs, and dyspnea. Diseases of the Yin Linking Vessels also include prolapse of the rectum and diarrhea.
2. Symptoms of Deficiency include timidity or fear, apprehension, nervous laughter, mental depression, hypotension, and weak respiration.

THE YANG LINKING VESSELS

The Yang Linking Vessels lie on the lateral aspects of the body. They serve to maintain and communicate with all the Yang Channels in the exterior portion of the lateral aspects of the body. They begin at the external part of the ankles, just below the lateral malleolus at Bl-63 points, ascend the sides of each leg, up each side of the back of the body, through the shoulder areas to the Naoshu (SI-10) Scapula's Hollow points. The SI-10 points



Figure 7.12. Side View of the Left Yang Linking Vessel

are the intersecting points of the Yang Linking and Yang Heel Vessels located on the Small Intestine Channels. From the SI-10 points, both Yang Linking Vessels split into two sets of branches. One set of branches flows up the sides of the neck and head connecting with the GB-20 points (at the lower occipital part of the head), where it communicates with the Governing Vessel. The other set of branches becomes the Yang Yu Vessels. The Yang Yu Vessels extend from the shoulders, down the back sides of the arms, following the route of the Triple Burner Channels. Just above both wrists on the outside of each arm, each of the branches pools at the Weiguan (TB-5) Outer Pass points, before flowing into the back of the hands. The TB-5 points are therefore considered the Master Points for the Yang Linking Vessels (Figure 7.12).

The Yang Linking Vessels are responsible for moving the Yang energy and controlling the Protective Qi, regulating the Wei Qi's resistance to external infections, and regulating the external parts of the body. They connect with all of the body's Primary Yang Channels: Gall Bladder, Small Intestine, Stomach, Large Intestine, Bladder, and Triple Burners. When the Yang energy is slowed down in the Linking Vessels, the Yin energy moves more rapidly; therefore, if the Yang Linking Vessels become unbalanced, the Excess Yin condition may cause the patient to catch colds and fevers more easily.

CLINICAL MANIFESTATIONS

The functions and clinical uses of the patient's Yang Linking Vessels are:

1. To treat ear problems due to the rising of Liver Fire, resulting in conditions such as tinnitus and deafness;
2. To treat ear diseases due to a Gall Bladder disharmony;
3. To treat hypochondriac pain;
4. To treat sciatic pain in the lateral aspects of the legs (along the Gall Bladder Channels);
5. To treat intermittent fevers that alternate between chills and fever.

PATHOLOGICAL MANIFESTATIONS

1. Symptoms of Excess include: Alternating chills and fever; pain on the lateral sides of the neck, trunk and legs, as well as pain in the head. Symptoms also include pains and skin problems during weather changes, sensitivity to changes in climate (aching muscles, skin rashes, etc.), swelling, pain and fever in the joints, diarrhea and night sweats.
2. Symptoms of Deficiency include: Coldness and lack of body heat, loss of energy, and physical strength. Symptoms also include cold knees, stiffness, and fatigue (especially during cold or rainy weather).

SUMMARY OF EIGHT EXTRAORDINARY VESSEL PATHOLOGY

The Eight Extraordinary Vessels link all of the Yin and Yang Channels in the body and regulate the flow of energy in these channels to maintain a state of energetic balance. The clinical significance of the Eight Extraordinary Vessels is manifested through certain pathological indications that are particular to the vessels' intersection with their specific Primary Channel(s). Their symptomatology is therefore not distinct from, but rather a composite of, the pathological symptoms associated with their joining Primary Channel(s).

Figure 7.13 describes some of the Eight Extraordinary Vessels pathologies and the clinical manifestations indicated along their root (beginning) and ending branches.

The Eight Extraordinary Vessels' energetic pathways used in certain esoteric Qigong meditations are somewhat different from the ones seen in Traditional Chinese Medical texts and acupuncture charts. The reason for this uniqueness is because their purposes are different.

The goal of Chinese acupuncture is to restore sick people to health. The energetic points being treated by an acupuncturist must be along the superficial channels, so that they can be activated by acupuncture needles.

Medical Qigong exercises and meditations aim to maximizing health, and to take the individual beyond mere physical health to spiritual enlightenment. In Medical Qigong training the channels and points can be deep within the body, since the energy is guided by the mind or by postures and movements, rather than by needles.

Eight Extraordinary Vessels	**Pathologies**
Belt	• Pain in the back, lumbar region, and sides of the navel • Weakness in the lower limbs
Conception	• Diseases of the reproductive and gastrointestinal systems (hemorrhoids, diarrhea, decreased urination, etc.) • In the male, sterility • In the female, the menstruation problems such as leukorrhea and dysmenorrhea; also breast pain, paralysis after delivery, emaciation, and sterility; all reproductive system problems, including internal and external genitalia (vulva, vagina, and cervix)
Governing	• Diseases of the head (apoplexy, aphasia, epilepsy, headaches, tetanus, etc.), back, neck, and Kidneys • Stiffness in the spinal column, spastic muscle movements of the extremities, night sweating, and circulatory disturbances around the anus
Thrusting	• In women, amenorrhoea, scanty periods or late periods, dysmenorrhoea, spontaneous abortion, inability to expel the placenta, menopause problems • Diseases of the Heart, fullness in the chest and abdomen, gastritis, abdominal pain, convulsive diseases • Brain dysfunction of physiological origin
Yang Heel	• In newborns, vomiting of milk • Stiffness of the back and waist, lumbar pain, spasms on the outer side of the legs, and tumors of the thighs • Diseases of the eyes
Yang Linking	• Diseases from Cold— fevers resulting in a sensitivity to changes in climate; cold knees; stiffness and fatigue; swelling, pain, and fever in the joints and extremities; and night sweating
Yin Heel	• Lower abdominal pain, vomiting, difficult bowel movements, and spasms on the medial side of the legs • Diseases of the eyes • Difficult labor in women
Yin Linking	• Diseases of the Heart (cardialgia), tightness of the chest, difficulty in swallowing, convulsive diseases • Diseases also include prolapse of the rectum and diarrhea

Figure 7.13. Pathologies of the Eight Extraordinary Vessels

THE FIFTEEN MAJOR COLLATERALS (CONNECTING VESSELS)

The Fifteen Collaterals are also known as the Fifteen Luo. Luo is translated to mean a net or web, and in Traditional Chinese Medicine it refers to the Connecting Vessels. These vessels are the major "passage ways" for the circulation of the body's channel energy, emerging out of the Luo (pathway) points on the Twelve Primary Channels, plus the Governing and Conception Vessels. The Luo points are located below the elbows and knees and provide an additional energetic barrier to keep Evil Winds from affecting the Primary Channels, being somewhat deeper then the Muscle / Tendon Channels. The Collaterals are the streams of energy that connect the paired Primary Channel rivers.

The Fifteen Collaterals are superficial and much thinner in formation than the Primary Channels running through the interior aspect of the body. The collaterals distribute Qi and Blood to those areas not directly traversed by other channels. Flowing out of each Primary Channel's Luo point are two Luo vessels, which are counted as one:

1. The Transverse Luo Vessels connect to the Source Points on the Yin and Yang coupled Primary Channels. They act as a safety valve to maintain balance between Yin and Yang channels by diverting Excess energy from one channel to tonify Deficiencies in the Orb (internal organ and energetic field) of their paired Primary Channel. When a channel is Deficient (Empty) and its paired channel is in Excess (Full), for example, the tonification of the Luo point on the Deficient channel is enough to replenish it, while normalizing the channel previously in Excess.
2. Longitudinal Luo Vessels flow out of the Luo points, but do not connect with the coupled Primary Channels. The Luo Vessels usually flow proximally toward the channel's organ.

The Luo vessels' main function is to transfer Qi and Blood from the Primary Channels to all parts of the body to nourish the tendons, the bones, the skin, and the five sense organs (nose, eyes, ears, lips, and tongue). The Luo vessels also link the body's interior with its exterior, connecting the internal and superficial channels (Figures 7.14 through 7.19).

The Fifteen Major Collaterals have smaller branches, known as the Minute and Superficial Collaterals, extending from them. The Superficial Collaterals are sub-branches similar to capillaries serving to transport Qi and Blood to the surface of the body. Both Minute and Superficial Collaterals, which can be seen beneath the surface as blood vessels, are called Blood Luo Vessels.

PATHOLOGY

The pathology of the Fifteen Major Collaterals are categorized in terms of Excess and Deficient syndromes.

1. Excessive Conditions of the collaterals are due to exogenous invasion if (1) the organ associated with the Luo is in Excess or (2) the body's Wei Qi is weak. Evil Winds enter the body through Jing Well or Wind points, and start moving up the channel. The Longitudinal Luo Vessels provide a route for the diversion of Evil Winds. The Longitudinal Luo Vessels have more Wei Qi then the Primary Channels and can better fight pathogens. Sometimes with a Wind Cold invasion, a blue color is visible along the path of the Longitudinal Luo Vessel. If the invasion is due to Wind Heat, there may be a red color along the vessel.
2. Deficient Conditions of the collaterals are due to: (1) the organ associated with the Luo being Deficient or (2) the patient's Qi is Deficient due to exogenous factors.

POINT LOCATION OF THE FIFTEEN MAJOR COLLATERALS

1. The Foot Taiyin-Spleen 4 Point is located on the Spleen Channel of each foot, on the medial side, just posterior to the base of the first metatarsal bone. This Lou's energy flows downward to connect with the Stomach Channel on each foot. A second branch flows upward along the medial aspect of the inner thigh, passing the abdomen and connecting with the Stomach and Small Intestines (Figure 7.14).


Major Collaterals
YANG CHANNEL
YIN CHANNEL
CONNECTING LINE
Lv-5
Kd-4
Sp-4
St-40
Bl-58
GB-37

Figure 7.14. The figure at left shows the three Luo points of the Yin Collaterals of the left foot located on the Primary Channels of the Kidneys, Spleen, and Liver. The figure on the right shows the three Luo points of the Yang Collaterals of the left foot located on the Primary Channels of the Stomach, Bladder, and Gall Bladder.

   a. Symptoms of Excess include sharp intestinal pain, vomiting, and diarrhea.
   b. Symptoms of Deficiency include abdominal swelling.
2. The Foot Shaoyin-Kidney 4 Point is located on the Kidney Channel of each foot, just posterior to the medial malleolus. The Lou's energetic flow runs downward, crossing the heel, and connects with the Bladder Channel on each foot. A second branch flows upward along the medial aspect of the inner thigh, following the Kidney Channel. It passes the abdomen and connects with the pericardium of the Heart then flows laterally to connect with the lumbar vertebrae (Figure 7.14).
   a. Symptoms of Excess include enuresis, emotional irritability, and depression.
   b. Symptoms of Deficiency include lower back pain.
3. The Foot Jueyin-Liver 5 Point is located on the Liver Channel of each foot, on the medial side, several inches above the medial malleolus. The Lou's energetic flow connects with the Gall Bladder Channel on each foot and flows upward along the medial aspect of the inner thigh. It connects with the genitals and terminates at the penis in males, and the clitoris in women (Figure 7.14).
   a. Symptoms of Excess include swelling of the testicles.
   b. Symptoms of Deficiency include itching in the pubic region.
4. The Foot Taiyang-Bladder 58 Point is located on the Bladder Channel of each foot, on the lateral side, several inches above the external malleolus. The Lou's energy flows downward to connect with the Kidney Channel on each foot (Figure 7.14).
   a. Symptoms of Excess include nasal congestion, headache, and back pain.
   b. Symptoms of Deficiency include clear mucus nasal discharge and nosebleed.
5. The Foot Shaoyang-Gall Bladder 37 Point is located on the Gall Bladder Channel of each foot, on the lateral side, several inches above the external malleolus. The Lou's energy flows downward to connect with the Liver Channel on each foot, then continues downward to disperse over the dorsum on each foot (Figure 7.14).
   a. Symptoms of Excess include fainting.
   b. Symptoms of Deficiency include weak and flaccid muscles of the feet.
6. The Foot Yangming-Stomach 40 Point is located on the Stomach Channel of each foot, on the lateral side, several inches above the external malleolus. The Lou's energy flows downward to connect with the Spleen Channel on each foot. A second branch flows along the lateral aspect of the tibia, upward to the top of the head where it divides, with one branch converging with the other Yang Channels on the neck and head, and the other branch connecting with the throat (Figure 7.14).
   a. Symptoms of Excess include epilepsy and insanity.
   b. Symptoms of Deficiency include pharyngitis, sudden aphasia, and flaccid or atrophied muscles in the legs or feet.
7. The Hand Taiyang-Small Intestine 7 Point is located on the Small Intestine Channel of each hand, on the dorsal side, several inches above the wrist, on the ulnar side. The Lou's energy flows upward past the elbow and connects with the Large Intestine 15 point (Figure 7.15).
   a. Symptoms of Excess include fever, headaches, and blurred vision.
   b. Symptoms of Deficiency include atrophy of the muscles in the elbow and arm, and a looseness in the joints.
8. The Hand Yangming-Large Intestine 6 Point is located on the Large Intestine Channel of each hand, several inches above the dorsal side of the wrist on the radial side. The Lou's energy flows upward on each arm to the jaw and pours into the area of the teeth. Another branch ascends into each ear, connecting with the Thrusting Vessels which supply energy to the head (Figure 7.15).
   a. Symptoms of Excess include deafness and toothache.

   b. Symptoms of Deficiency include a sensation of coldness in the teeth, as well as fullness and congestion in the chest.

9. The Hand Shaoyang-Triple Burner 5 Point is located on the Triple Burner Channel of each hand, located just above the dorsal transverse crease of the wrist. The Lou's energy flows upward past the arm and over the shoulder, dispersing into the chest and connecting with the Pericardium Channel (Figure 7.15).
   a. Symptoms of Excess include muscle spasms of the elbow.
   b. Symptoms of Deficiency include flaccid muscles in the arm and elbow joint.
10. The Hand Taiyin-Lung 7 Point is located on the Lung Channel of each hand and arises from the cleft of the tendons and bones on the radial side of the wrist, where it flows down into the palm, spreading through the thenar eminence (Figure 7.15).
    a. Symptoms of Excess include hot palms or wrists.
    b. Symptoms of Deficiency include enuresis and shortness of breath.
11. The Hand Shaoyin-Heart 5 Point is located on the Heart Channel of each hand, just above the transverse crease of the wrist. The Lou ascends along the Heart Channel and enters the Heart then continues up the chest into the head, flowing into the root of the tongue, then ascends to connect with each eye (Figure 7.16).
    a. Symptoms of Excess include fullness and pressure in the chest.
    b. Symptoms of Deficiency include aphasia.
12. The Hand Jueyin-Pericardium 6 Point is located on the Pericardium Channel of each hand, just a few inches above the medial transverse crease of the wrist, between the two tendons. The Lou's energy flow follows the Pericardium Channel, connecting with the Heart (Figure 7.16).
    a. Symptoms of Excess include chest pain.
    b. Symptoms of Deficiency include irritability.
13. The Governing Vessel 1 Point is located on the



Figure 7.15. The three Yang Collaterals and their Luo points located on the hand and on the Primary Channels of the Large Intestine (LI), Triple Burners (TB), and Small Intestine (SI).



Figure 7.16. The three Yin Collaterals and their Luo points located on the hand and on the Primary Channels of the Heart, Pericardium, and Lungs.



Figure 7.17. The main collateral and Luo point of the Governing Vessel is located on the Governing Vessel (GV) 1 point.



Figure 7.18. The main collateral and Luo point of the Conception Vessel is located on the Conception Vessel (CV) 15 point.



Figure 7.19. The major collateral and Luo point of the Spleen is located on the Spleen (Sp) 21 point.

base of the Governing Vessel, at the perineum. The Lou's energy flows upward along both sides of the spine to the nape of the neck, spreading to the top of the head. It continues flowing into the scalp regions on both sides of the head and connects with the Bladder Channel and merges with the spine (Figure 7.17).

  a. Symptoms of Excess include stiffness along the spine.
  b. Symptoms of Deficiency include dizziness or heaviness in the head.

14. The Conception Vessel 15 Point is located on the Conception Vessel of the chest, just below the xiphoid process. The Lou's energy flows downward, pouring over the abdomen (Figure 7.18).
    a. Symptoms of Excess include pain on the surface skin of the abdomen.
    b. Symptoms of Deficiency include itching on the surface skin of the abdomen.
15. The Major Luo of the Spleen 21 Point is located on the Spleen Channel of the chest, just below the auxiliary fold of each arm. The Lou's energy flow spreads through the chest and hypochondriac region, gathering the Blood like a net (Figure 7.19).
    a. Symptoms of Excess include general aches and pains throughout the entire body.
    b. Symptoms of Deficiency include weakness in the muscles of the limbs and joints.

THE TWELVE DIVERGENT CHANNELS

The Twelve Divergent Channels comprise an important part of the body's channel system. These channels are branches off the Twelve Primary Channels and share the energetic function of circulating Qi throughout the body. The energetic field of the Twelve Divergent Channels forms an enormous web of complex interconnections within the body's Twelve Primary Channels.

Because the area over which the energy of the Twelve Divergent Channels is distributed is quite extensive, they are considered a separate component of the channel system. They are secondary streams that parallel the primary rivers, yet each has its own functional characteristics and clinical application independent of the Primary Channels. The Twelve Divergent Channels run deeper in the body, supplementing the areas along the pathways that the Primary Channels do not reach. They have no points of their own, although there are intersection points where they cross the major channels (Figures 7.20 through 7.25).

One of the primary functions of the Twelve Divergent Channels is to integrate all parts of the body with the Twelve Primary Channels. There are areas in the body which are not traversed by the pathways of the Twelve Primary Channels, as well as internal organs that are otherwise unconnected, or only remotely connected, by the Primary Channels. These areas are more securely linked by the energetic flow of the Twelve Divergent Channels, which strengthen the bonds between the Twelve Primary Channels and the physical areas that are connected to, or adjoining, their pathways.

Another primary function of the Twelve Divergent Channels is to facilitate the connection between pairs of Yin and Yang Primary Channels and Organs. Therefore, all primary Yin and Yang organs are connected by the Divergent Channels. Both Yin and Yang Divergent Channels ultimately connect with the body's Yang Primary Channels.

1. The Yang Divergent Channels complete a cycle of leaving the primary channels (e.g., Primary Gall Bladder Channel) and entering their associated organs (e.g., The Gall Bladder Organ) before they resurface on the neck and reconnect with their original channels (e.g., The Primary Gall Bladder Channel).
2. The Yin Divergent Channels leave their primary channels (e.g., Primary Liver Channel), then join their associated Yang Divergent Channels (e.g., The Divergent Gall Bladder Channel), which then join with the Yang Primary Channels (e.g., The Primary Gall Bladder Channel).

Similarly, within the body's cavities, most of the Twelve Divergent Channels first join with their pertaining Yin or Yang organ and then connect with the associated organ (belonging to the associated channel) in the Yin / Yang pair. Through this interaction, the connection between paired Yin and Yang organs and channels is strengthened.

An understanding of the relationship between the paired Yin and Yang interactions is important to the Qigong doctor, as sometimes a disease affecting a Yang channel can be treated by selecting certain areas on its associated Yin channel, and vice versa. The same theory holds true for diseases of the internal organs.

The Twelve Divergent Channels are paired into six confluences according to their internal and external relationship.

1. Bladder Divergent Channel (Foot Tai Yang) and Kidney Divergent Channel (Foot Shao Yin)
2. Stomach Divergent Channel (Foot Yang Ming) and Spleen Divergent Channel (Foot Tai Yin)
3. Gall Bladder Divergent Channel (Foot Shao Yang) and Liver Divergent Channel (Foot Jue Yin)
4. Small Intestine Divergent Channel (Hand Tai Yang) and Heart Divergent Channel (Hand Shao Yin)
5. Large Intestine Divergent Channel (Hand Yang Ming) and Lung Divergent Channel (Hand Tai Yin)
6. Triple Burners Divergent Channel (Hand Shao Yang) and Pericardium Divergent Channel (Hand Jue Yin)


Divergent Channels
Yang Channels
Yin Channels
Connecting Line
Gall Bladder Divergent Channel
Liver Divergent Channel

Figure 7.20. The Divergent Channels of the Gall Bladder and Liver


Large Intestine Divergent Channel
Lung Divergent Channel

Figure 7.21. The Divergent Channels of the Lungs and Large Intestine


Spleen Divergent Channel
Stomach Divergent Channel

Figure 7.22. The Divergent Channels of the Stomach and Spleen


Kidney Divergent Channel
Bladder Divergent Channel

Figure 7.23. The Divergent Channels of the Bladder and Kidneys


Small Intestine Divergent Channel
Heart Divergent Channel

Figure 7.24. The Divergent Channels of the Heart and Small Intestines


Triple Burners
Divergent
Channel
Pericardium
Divergent
Channel

Figure 7.25. The Divergent Channels of the Pericardium and Triple Burners

THE TWELVE MUSCLE/TENDON CHANNELS

The Twelve Muscle / Tendon Channels are the muscle and soft tissue regions of the body where the Qi and Blood of the Primary Channels nourish the skin, muscles, and tendons. They are very superficial in relationship to the Primary Channels and form a capillary network that travels in the depressions and planes between muscles and tendons. The Twelve Muscle / Tendon Channels, subsequently spread over the whole of the epidermis, through its close connection with the cutaneous tissues.

Originating in the extremities, these channels ascend to the head and torso. Physiologically, they do not enter into the internal organs but coordinate the movement of the bones and limbs. The Twelve Muscle / Tendon Channels are connected to the inner fascia of the body's muscles, tendons, and ligaments, as well as other connective tissues. They are affiliated with the channels and collaterals (Luo) systems on the exterior of the body, and serve as mediators between any energetic reactions (trauma, stress, etc.) that vibrate from the body's exterior surface to the deep internal organs.

These channels are found along the four extremities on the surface of the body, as well as along the head, neck, back, chest, and abdomen. The name of each Muscle / Tendon Channel comes from the Twelve Primary Channels whose external energy flow they follow. They also receive Blood and Qi nourishment for their functional activity from and through the Twelve Primary Channels. There are points of connection, as well as intersecting points along these channels (Figure 7.26 through 7.37).

Treatment at these conjunctive points consistently responds successfully to stimulation; therefore, the Qigong doctor can effectively apply Jing Point Therapy to specific areas and points along the Muscle / Tendon Channels.

These channels are responsible for extending and flexing the muscles, tendons, ligaments and joints; their pathology is reflected in symptoms of impaired movement (i.e., pulled, twisted, strained, cramped or atrophied muscles, spasms, etc.).

In Traditional Chinese Medicine the muscles and tendons are described in characteristics of Yin (flexion, contraction, internal rotation, etc.) and Yang (extension, expansion, external rotation, etc.) which balance each other. When the Yin and Yang action of the muscles and tendons fail to balance and regulate each other, Muscle Channel Dysfunction results; for example, when exposed to cold, the muscles / tendons become tense and over-contract; when exposed to heat, muscles / tendons become loose and overextend.

The pathology of the Muscle / Tendon Channels also reflects the symptoms of corresponding groups of muscles and other connective tissues. The connective tissues are divided into three groups: the large, the small, and the membranous connective tissue.

Therapeutically, a local Muscle / Tendon Channel symptom can be treated by stimulating an area located next to the origin of the pain; for example, if the area is Yang (lateral) and overactive, then the Yin (medial) will be underactive and vice versa. Treatment is directed towards restoring the balance between the Yin and Yang Muscle / Tendon Channels.

Being superficial, the Twelve Muscle / Tendon Channels contain Wei Qi; thus, they provide the body's third line of defence against any unfavorable exogenous influence (the first being the body's Wei Qi field, and second being the Wei Qi stored within the skin). Only after overcoming the resistance of the body's Muscle / Tendon Wei Qi can the Evil Exogenous pathogens travel down the length of the channel to penetrate the corresponding Primary Channel at the Jing-Well point. Jing-Well points are points of energetic union, connecting Primary Channel points together with the points where the Muscle / Tendon Channel have their origin.


Baihui point
(GV-20)
levator labii superioris
temporalis
masseter
sternocleidomastoid
pectoralis major
serratus anterior
external oblique
gluteus maximus
tensor fascia lata
tibialis anterior
extensor digitorum longus

Figure 7.26. The Muscle Region of the Gall Bladder Channel: High Tide is 11p.m.–1 a.m. Pathological symptoms include strained muscles from the fourth toe to the knee upon lateral rotation, with an inability to bend the knee; muscle spasms or stiffness within the popliteal fossa; strained muscles of the sacrum, pelvis, and lower ribs; pain in the hypochondria, chest, and clavicle region; and an inability to turn the eyes to the left or right.


rectus abdominis
pectineus
vastus medialis
soleus

Figure 7.27. The Muscle Region of the Liver Channel: High Tide is 1 a.m.–3 a.m. Pathological symptoms include strained muscles of the big toe; pain in the anterior internal malleolus of the ankle; pain at the medial aspect of the knee and thigh; and dysfunction of the reproductive organs, i.e., impotence.


subclavius
anterior deltoid
biceps brachii
brachio radialis
abductor pollicis brevis

Figure 7.28. The Muscle Region of the Lung Channel: High Tide is 3 a.m.–5 a.m. Pathological symptoms include strained muscles of the thumb; stiff, strained or muscle spasms, and/or pain along the course of the Lung Channel. In more serious cases, there will be muscle spasms over the rib area and spitting of blood.


temporalis
masseter
platysma
middle/anterior deltoid
trapezius
brachialis/ biceps brachii
extensor digitorum

Figure 7.29. The Muscle Region of the Large Intestine Channel: High Tide is 5 a.m.–7 a.m. Pathological symptoms include strained muscles of the index finger; stiffness, strained, or muscle spasms along the course of the Large Intestine Channel, resulting in frozen shoulder; and an inability to rotate the neck from side to side.


orbicularis oculi
levator labii superioris
masseter
orbicularis oris
platysma
pectoralis major
rectus abdominis
external obliques
latissimus dorsi
adductor longus
vastus lateralis
vastus medialis
tibialis anterior
extensor digitorum longus

Figure 7.30. The Muscle Region of the Stomach Channel: High Tide is 7 a.m.–9 a.m. Pathological symptoms include strained muscles of the big toe; spasms or hardening of the muscles in the foot; knotted or twisted muscles in the lower leg and thigh; swelling in the anterior pelvis region; hernia; spasms of the abdominal muscles; spasms or stiffness of neck and cheek muscles; and eye spasms.


rectus abdominis
oblique muscles
sartorius
soleus
flexor digitorum longus
extensor hallucis longgus

Figure 7.31. The Muscle Region of the Spleen Channel: High Tide is 9 a.m.–11 a.m. Pathological symptoms include strained muscles of the big toe; pain in the internal malleolus of the ankle upon rotation; pain along the medial aspect of the knee and adductor muscles of the thigh; groin strain; and pain due to strained upper abdominal muscles and mid-thoracic vertebrae.


pectoralis major
long head of the triceps brachii
brachialis tendon
abductor digit minimi
flexor digitorum superficialis

Figure 7.32. The Muscle Region of the Heart Channel: High Tide is 11 a.m.–1 p.m. Pathological symptoms include strained muscles of the little finger; stiff or strained muscles with spasm and/or pain along the course of the Heart Channel, including internal cramping within the diaphragm and upper abdominal area.


temporalis
upper trapeziusr
masseter
infraspinatus
middle deltoid
triceps
extensor carpi ulnaris

Figure 7.33. The Muscle Region of the Small Intestine Channel: High Tide is 1 p.m.–3 p.m. Pathological symptoms include strained muscles of the little finger; pain along the medial and posterior aspects of the elbow; pain in the posterior aspect of the axilla, neck, and scapula region; tinnitus related to ear ache; and poor vision.


frontalis
levator anguli
oris/superioris
sternocleidomastoid
platysma
pectoralis
major
serratus
anterior
occipitofrontalis
infraspinatus
latissimus
dorsi
erector spinae
(longissimus,
spinalis,
iliocostalis)
gluteal
muscles
semitendinosus
biceps
femoris
popliteal fossa
peroneus
longus
both heads of
gastrocnemius
extensor tendons

Figure 7.34. The Muscle Region of the Bladder Channel: High Tide is 3 p.m.–5 p.m. Pathological symptoms include strained muscles of the big toe; swelling and pain in the heels; stiffness or spasms along the spine and back area; frozen shoulder; stiffness or spasms in the axillary and clavicle regions.


gracilis
gastrocnemius
flexor digitorum brevis
flexor digiti minimi brevis

Figure 7.35. The Muscle Region of the Kidney Channel: High Tide is 5 p.m.–7 p.m. Pathological symptoms include strained muscles on the bottom of the foot; spasms or stiffness along the Kidney Channel, resulting in an inability to bend forward (Yang disorder) or backward (Yin disorder), with difficulty in flexing or extending the head.


biceps brachialis
flexor carpi radialis
palmaris longus
flexor digitorum superficialis tendons

Figure 7.36. The Muscle Region of the Pericardium Channel: High Tide is 7 p.m.–9 p.m. Pathological symptoms include strained muscles of the middle finger; stiff or strained muscles, or spasms and/or pain along the course of the Pericardium's Channel; and chest pain and spasms.


masseter
platysma
middle deltoid
brachialis
extensor digitorum

Figure 7.37. The Muscle Region of the Triple Burner Channel: High Tide is 9 p.m.–11 p.m. Pathological symptoms include strained muscles of the ring finger; stiff or strained muscles, or spasms and/or pain along the course of the Triple Burners' Channel.

THE TWELVE SKIN ZONES

Based on the Twelve Primary Channels, their collaterals, and the body's Muscle/Tendon Channels, the surface tissue is divided into Twelve Skin Zones. These Skin Zones are the surface contact areas for the body's channel and collateral systems. These twelve regions (sometimes called the Twelve Cutaneous Channels) are located in the superficial layers of the skin and have continuous and direct contact with the external environment. They are, therefore, the most sensitive to climactic changes and must adapt to protect the body from External pathogenic factors.

Both the Qi and the Blood at the Twelve Skin Zones rely on the collaterals for their nourishment. The Twelve Skin Zones circulate Wei Qi, which in addition to its defensive function, is also in charge of opening and closing the pores. The skin relies primarily upon the strength of the Wei Qi for resistance to the invasion of External pathogenic influences, as these harmful influences must first penetrate the skin before they can affect the body's internal tissues and organs. Since the Lungs rule the skin, weak Lung Qi can allow pathogens to penetrate the skin and affect the Lungs.

Pathological symptoms associated with the Twelve Primary and connecting Channels manifest along the surface of the Twelve Skin Zones, before progressing deeper into the body's connective tissue. The early stages of disease are called Exterior conditions; if the exterior Wei Qi is strong enough, pathogens will be stopped at the external level. The order of pathogenic progression is as follows.

1. The Body's Wei Qi is the body's first line of defense. A healthy body will project a strong, protective, external energetic field, which will maintain a capable defensive boundary. If the patient becomes weak, tired, or stressed, however, External pathogens may advance onto the patient's skin and begin attacking his or her health.
2. The Skin is the body's second line of defence. If the body's Wei Qi is not strong enough to resist an External attack and the skin is not capable of warding off the pathogens, then the pathogens will attack the skin, causing the sweat pores to open, thus allowing the pathogens to advance towards the patient's collaterals.
3. The Collaterals are the third line of defense. If the body's collaterals are unable to redirect or purge the advancing pathogens, the pathogens will then advance into the patient's channels.
4. The Channels are the last line of defense before the advancing External pathogens invade the patient's internal organs. If the body's channels are unable to redirect or purge the pathogens, and the pathogens are allowed to continue their progression, they will advance further into the body's internal organs.
5. The Internal Organs are affected once the pathogens have breached all the outer defences and disease can now begin to establish its residence.

Pathologies associated with the Primary Channels manifest diagnostically through the body's skin, channels, and points. The observation of pimples, moles, discoloration, and changes in electro-conductivity are all valuable signs of pathogens, or obstructions, invading the skin.

A disease of external origin that first lodges within the patient's skin can be treated by the Qigong doctor. The doctor stimulates the Wei Qi in the affected skin zone through external Qi projection before it progresses further into the body's connective tissue. An alternate treatment would be to apply herbal ointments and/or moxa therapy.

THE CONNECTIVE TISSUE OF THE TWELVE SKIN ZONES

The connective tissue always responds to the outside stimulation of the Twelve Skin Zones. The body's connective tissue is just below the skin, and is regarded as one of the largest, most extensive tissue organs in the body. Its function is to support, connect, contain, and transmit. It is a continuous network of structure that binds tissues into their organ shape. It also supplies the internal organ's life support with vessels and ducts, and securely fastens each organ within the body


Small Intestine, Bladder
Lungs, Spleen
Large Intestine, Stomach
Kidney, Heart
Triple Burner, Gall Bladder
Pericardium, Liver

Figure 7.38. The Body's Twelve Skin Zones, Based on the External Flow of Qi from the Twelve Primary Channels and Their Collaterals

cavity. This connective tissue surrounds and anchors the vessels within the muscles, bones, and organ tissue. Its fluid nature supports the entire body structurally by hydrostatic pressure. Any stimulation on one of the body's Twelve Skin Zones will directly affect the body's connective tissue, and will stimulate the corresponding internal organ associated with that particular zone.

The superficial fascia (the connective tissue just under the skin) divides into a top and bottom layer. The top layer is the fatty layer, which constitutes the main fatty tissue of the outer surface of the body and fascia. This fatty layer acts as an insulator, helping to maintain a constant body temperature. It is metabolically active, functionally storing fat as fuel, releasing it in response to nerve and hormonal stimuli. It corresponds to the greasy layer where the Wei Qi circulates throughout the body's tissues. The deeper layer of the superficial fascia envelopes the nerves, veins, arteries, lymph vessels, and nodes.

From a Traditional Chinese Medical perspective, the Qi circulating within the body's inner fascial connective tissue can be stimulated through the external energy stimulation of the Twelve Skin Zones. Heat and movement help maintain the body's connective tissue's base fluids, facilitating movement and the conduction of energy. Any obstruction occurring on the body's surface tissues can result in the binding or thickening of the connective tissue, thus creating adhesions. This obstruction slows the metabolic process and compromises the body's immunity (Figure 7.38).

If the integrity of the connective tissue is compromised, the body's immune system declines. Compartments of connective tissue influence the spread of toxins, diseases, infections, and tumors. The fibrous walls, as well as chemicals in the fluid of the connective tissue, prevent the spread of pathogens from one area of the body to another.

CLINICAL DIAGNOSIS AND THE TWELVE SKIN ZONES

Clinically, the diagnosis and treatment techniques relating to the use of the Twelve Skin Zones is quite extensive. In diagnosis, the skin's surface area along these zones is examined for evidence of discoloration or tissue obstruction. Changes in skin color and tissue formations are observed and categorized as follows.

1. A darkish hue reflects obstruction of Qi and Blood.
2. A bluish-purple color indicates local pain.
3. Change in color from yellow to red shows evidence of Heat.
4. A white or pallid skin tone signifies Deficiency or Cold.
5. Boils, pimples (especially on the back), hives, and eczema, as well as hard lumps or nodules beneath the surface of the skin, indicate diseases associated with the Twelve Primary Channels (manifesting through the Twelve Skin Zones).

A palpable lump can develop from a variety of sources, including congealed or stagnant Blood. There are generally eight types of lumps observed in the clinical environment:

1. The Shrimp Lump, is shaped in the form of a shrimp.
2. The Turtle Lump, is named for its shape and multiple lump formations.
3. The Blue Lump, derives its color from the superficial blood vessels on which it forms.
4. The Single Lump, is diagnosed as opposed to multiple lump formations.
5. The Dry Lump, indicates an obstruction.
6. The Blood Lump, relates to congealed Blood.
7. The Abdominal Lump, is named for its physical location.
8. The Yellow Lump, is named because of the yellow pallor in the specific region of the lump.

PALPATING THE PATIENT'S SKIN

Before palpating and diagnosing the skin, the Qigong doctor first scans the patient's body to feel the temperature, moisture, and texture of the patient's tissues.

1. The doctor scans and palpates the patient to diagnose the condition according to the temperature:
    a. If the skin feels hot to the touch it often indicates a presence of a Damp-Heat condition.

   b. When first touching the patient with light pressure if the skin feels immediately hot, and as the pressure is maintained the feeling of heat increases, this indicates an invasion of Exterior Wind-Heat (with a pathogenic factor still on the exterior surface).
   c. If the skin over a blood vessel feels hot on medium pressure, it indicates Interior Heat in the Middle Burner or Heart area.
   d. If the skin feels hot on deep, heavy pressure, it indicates an Empty-Heat condition from a Yin Deficiency.
   e. If the skin feels cold to the touch, it often indicates a Cold condition. This condition is often manifested in the lower back and lower abdominal region, indicating a Deficiency of the Kidney Yang.
2. The doctor scans and palpates the patient to diagnose the condition according to the amount of moisture:
   a. A moist feeling of the skin may indicate an invasion of the Exterior by Wind-Cold or Wind-Heat.
   b. If the skin feels moist due to spontaneous sweating, it indicates a Deficiency of the Lungs' Qi (in the absence of exterior symptoms).
3. The doctor scans and palpates the patient to diagnose the condition according to the texture:
   a. If the skin is scaly and dry, it indicates an exhaustion of the Body's Fluids.
   b. If the skin feels dry, it indicates either a Yin condition of the Lungs or a Blood Deficiency.
   c. If the skin is swollen and an indentation is left visible after pressing, it indicates Edema (called Water Swelling).
   d. If the skin is swollen and no indentation is left visible after pressing, it indicates a retention of Dampness (called Qi swelling).

CHANNEL AND COLLATERAL THERAPY

Because the Yin and Yang organs' Qi flows within the body's internal and external surfaces, all the internal and external channels and collaterals, five tissues (tendons, blood vessels, muscles, skin, and bones), and five sense organs (eyes, ears, nose, mouth, and tongue), together create an energetic network. Through practicing sitting meditations, patients as well as Qigong practitioners become aware of the circulation of Qi along the body's channels and collaterals. The awareness of what the Qi feels like enables the meditators to feel the flow and function of each channel, as well as the Blood and heat cycle in each Skin Zone. This makes it possible to control the Qi circulation through intention and imagination.

Balancing the Conception and Governing Vessels is of the utmost importance in the practice of any Qigong regulation. Along these two Vessels the Qigong practitioner draws the Yang Fire and Yin essences up and down the body, thus fusing the Water and Fire energies. This fusion is utilized by the doctor in every Qigong treatment, and is responsible for balancing the patient's Yin and Yang energy. This balance is created through the discipline of the Microcosmic Orbit meditation, which connects the Governing and Conception Vessels.

The students' awareness of Qi flowing through the body usually develops in three distinct stages:

1. First, they begin to feel the energy flow along the surface channels of the body, especially within the areas of the extremities. Usually at this stage, the students will feel heat and tingling sensations within the body's surface muscles.
2. Next, they begin to feel the energy flow deeper within their tissues, especially along the tendons, deeper muscles, and visceral organs. Usually at this stage, they begin to feel mild electric shocks and vibrations within their muscles, bones, and visceral organs.
3. In the final stage, they feel the Earth and Heaven energy penetrate through their body's

outside channels and inner organs, connecting into their Taiji Pole, and then turning outward again. Usually at this stage, they will feel their entire energized body vibrate. This vibration may be triggered through either universal or environmental changes, as the Medical Qigong practitioner becomes hypersensitive to any form of external energetic disturbance.

CONTROLLING QI EXTENSION THROUGH THE CHANNELS

The Qigong doctor must first be able to control his or her own energy circulation, causing it to flow in or out, expand or contract at will, before beginning to extend energy for the treatment of any patient. This energetic control is gained through specific imagination and visualization techniques. The fundamental theory for these techniques is "The imagination leads the Mind, the Mind leads the Qi." The doctor must be able to utilize energy from the natural environment (trees, waterfalls, ocean, desert, etc.) in order to replenish and facilitate his or her own energy.

By drawing in Heavenly Qi and combining it with his or her body's connection to Earthly Qi, the doctor may mobilize and activate the Qi of the patient. This combining method establishes an energetic healing field of Qi, which responds to the Qigong doctor's own Qi circulation, as well as to that of the natural environment, which includes the patient. This ability must be achieved in order to activate the patient's Qi and then regulate it by purging the Excess Qi, replenishing the Deficient Qi, dredging the channel Qi, and guiding the Qi back to its origin.

CHAPTER 8
THE BODY'S ENERGETIC POINTS

INTRODUCTION TO ENERGETIC POINTS

The Chinese word for point is Xue or Xue Wei, meaning "cavity place, cave, den, hole, or hollow." Although the Chinese word Xue is usually translated into English as "point" or "acupoint," it is valuable for the English-speaking student to understand the word's different connotations. Points are almost always located in hollows or depressions, which are physically palpable and found in over 1,000 locations all over the body. Many, but not all, are located along the channels and vessels. Sometimes when touching a point, it feels as if your fingertip has found the entrance of a small cave or opening hidden by the skin covering it.

The word Xue also implies a den or lair: thus, it is not only a cave but a home for some type of powerful life form. In the human body, our living Qi gathers and pools within these protected hollows (Figure 8.1). For this reason, some writers have preferred to translate Xue as "vital hollow," rather than "point." Because of its popular acceptance, I have chosen to use the term "point" throughout this book.

THE FOUR WAYS POINTS ARE FORMED

Generally, points are formed in four ways. The first type of point occurs when two muscles, tendons, or ligaments intersect or overlap in a way that creates a small depression at the area of convergence. To form the depression, the two muscles either come together, separate, overlap, or run parallel to each other. Usually the channels lie under a protective layer of muscle, but at the aforementioned junctures, the channels may be exposed, and thus closer to the surface.

The second type of point occurs when a nerve is exposed in an area without much muscle tissue to cover and protect it. Because the nerve is exposed, such points are especially sensitive, and may cause a sharp pain or an electric shock sensation when stimulated.


Figure 8.1. The energetic points are considered the body's small energetic pools.

The third type of point lies under a protective superficial layer of muscle. It can however, still be stimulated due to its natural sensitivity and because the overlying layer of muscle is thin.

The fourth type of point lies in depressions on the surfaces of the bones and cartilage. These depressions may take the form of grooves, pits, hollows, indentations, fissures, or crevices.

SCIENTIFIC RESEARCH OF ACUPOINTS

In the early 1970's, shortly after President Nixon's historic visit to China, Dr. Robert O. Becker, M.D., a Syracuse University orthopedist, received a grant from the National Institutes of Health to research how acupuncture works. Dr. Becker reasoned that the channels were electrical conductors (independent of the nervous system yet communicating with it) that carried an injury message to the brain, which responded by sending back the appropriate level of direct current (DC) to stimulate healing in the troubled area."

Becker also suggested in his book *The Body Electric,* that "any current grows weaker with distance, due to resistance along the transmission cable. The smaller the amperage and voltage, the faster the current dies out. Electrical engineers solve this problem by building booster amplifiers every so often along a power line to get the signal back up to strength. For currents measured in nanoamperes and microvolts (such as those generated in the human body), the amplifiers would have to be no more than a few inches apart—just like the acupuncture points."

Dr. Becker and his assistant, Maria Reichmanis, a young biophysicist, designed special equipment to measure and map the electrical conductivity along the channels. They found the predicted electrical characteristics along the channels and at half the points. These same points showed up on all the people tested. They suggested that the other traditional points may simply be weaker, or of a different kind, than the ones that their instruments detected.

Each point that they found was electrically positive compared to its surrounding tissue, and each point had an electrical field surrounding it with its own characteristic shape.

Later research (see appendices) in China, France, and the United States has shown not only that these points and channels have electrical properties but that they also emit and absorb light and sound, both of which are vital to healthy biological functions.


Four Categories of Energy Points
Channel Points
Extra Points
New Points
Ahshi Points or " Trigger" Points

Figure 8.2. The Four Categories of Energetic Points

THE FOUR CATEGORIES OF ENERGETIC POINTS

Points are divided into four categories (Figure 8.2) and are described as follows.

1. Channel points are the Primary points that are distributed along the Twelve Primary Channels and the Conception and Governing Vessels. There are 365 channel points.
2. Extra points are not regarded as having a specific origin in the fourteen main channels, although they are named and are in definite locations. These points are also called "miscellaneous points."
3. New points are a fairly large group of points discovered since the Communist "Liberation" of 1949, in many cases through electric point detection. These points generally have no energetic description, but do have indications. Combined with the Extra points, there are more than 700.
4. Ahshi Points are tender or painful spots near a diseased or injured area and can be anywhere, on or off of traditional points and channels. They function like trigger points, as they are points of tension or pain. Ahshi points are not given specific names or definite locations as they are mostly used for pain syndromes.

THE TWO GATES OF ENERGETIC POINTS

Another way of categorizing the points is into the two general types commonly used by the Qigong doctor.

1. The Outer Qi Gates are points through which the patient's Shen and Qi enter and leave the body. The Qigong doctor or patient may gather healing Qi from the outer environment through these gates. In terms of pathology, these points are especially vulnerable to the Six External Pathogens, i.e., Cold, Hot, Wind, Damp, Dry, and Fire invasion (see Chapter 21), which may enter the body through these gates. These same pathogens may also be ex-

pelled through these gates. For this reason, many of these outer Qi gates have the word Feng (Wind) in their names, such as Fengchi GB-20 (Wind Pool).

2. The Inner Qi Gates are points through which the Qi of the Yin and Yang organs and channels is transported back and forth internally and externally, deeply and superficially. These points are more involved with the movement of Qi within the body and are less involved in the exchange with the outer environment. In this way, the Inner Qi Gates enable the Qi to communicate between the different parts of the body.

These two types of points (or gates) are specific areas where the Qigong doctors concentrate their intention and focus their energy extension. Point locations have a greater amount of accumulated Qi, and are used for dispersing or tonifying the body's organ energy, to promote the correct balanced circulation of Qi and Blood.

THE THREE FUNCTIONS OF ENERGETIC POINTS

The points can be used for three clinical functions: to manipulate Qi and Blood, for diagnosis, and to serve as pathways for the elimination of disease.

1. Qi and Blood can be manipulated to purge Excess conditions, tonify Deficient conditions, or for regulation.
   a. To disperse Excess conditions, the Qigong doctor emits Qi over a specific point (or points) and begins to purge, or disperse, the energy in the area (to purge is to remove toxins directly from the organ, whereas to disperse is to lead the toxins out through the channels). The goal of this treatment is to move any Excess, particularly stagnant Qi and Blood. If only Qi is stuck, the pain will move and feel dull. If only Blood is stuck, the pain will not move and will be sharp. This distinction, however, is more important in Chinese herbology than it is for medical Qigong, acupuncture, or massage because, as stated in the classics, "Qi is the commander of Blood"; therefore, moving the Qi in the latter therapies will also move stagnant Blood.
   b. To tonify a Deficient condition, the Qigong doctor emits Qi over a specific point or points, and begins to tonify or strengthen the patient's Qi, Blood, Yin, Yang, or specific organs and tissues. The Qigong doctor uses varying techniques according to the patient's needs (e.g., in order to prevent feeling discomfort, the doctor will tonify weak patients slowly).
   c. To regulate, the Qigong doctor emits Qi over a specific point or points, and allows the body's natural homeostasis to take over and restore healthy function. This type of treatment is also used when a patient has a combined Excess / Deficiency syndrome (such as stagnant Qi in the chest due to a Qi Deficiency in the Lungs and Kidneys).

   The healing potential of point stimulation can be accomplished through various modalities, such as Energy Projection, Energetic Point Therapy, Jing Point Therapy or Invisible Needle Therapy.

2. Diagnosis through point palpation and inspection is an important diagnostic tool in all the branches of Chinese medicine. If a point hurts when touched with light pressure, is hard or swollen, or is purple, black and blue, or red, this indicates an Excess condition. If the point hurts on deep pressure or is soft to the touch, lacks resilience, or is sallow in color, it indicates an underlying Deficiency.

   The skin over points often feels sticky, in contrast to the slippery or smooth quality of the skin surrounding the point. When passing the fingers over a point, the doctor generally feels the energetic pulse of the channel. When touched, the point energetically responds like an echo, vibrating along the channel into the organ and then back again to the



Figure 8.3. Weak or Deficient tissue will naturally pull and absorbe Qi into the surrounding areas.



Figure 8.4. Strong, Excess, or Armored tissue will naturally repel Qi from the surrounding areas.

doctor's finger. The doctor can use this energetic response for diagnostic evaluation by sending a pulse along the flow of the channel or against it (into the organ itself). Once sufficient stimulation is applied to the point, its organ or region is "reminded" of its normal function. In this way, diagnosis and treatment are accomplished simultaneously.

Once the location and energy flow of the channel to be treated is diagnosed, the doctor must take into consideration that each patient will react differently in accordance with the severity of symptoms, as well as the individual's constitutional type. Before beginning treatment, the doctor should extend Qi between the energetic point's boundary (the space separating the Wei and Ying energy levels), until the soreness or distention is felt on the tips of the doctor's fingers or palms (which act like a barometer). This form of diagnosis determines the condition of the channel and the area needing treatment. Although the feelings and sensations will vary with each patient, energetic truths remain constant. For example:

a. Weak or Deficient areas will feel like an empty hole or deep well. Deficient Blood or Qi will actually pull the energy into the area and will feel something like a subtle vacuum suction. If the area that the doctor is treating attacks his or her Qi and begins to absorb it, the doctor should tonify that area immediately. Think of this reaction as a dry house plant starving for water. The minute the water touches its soil, the plant immediately absorbs it into its roots (Figure 8.3).
b. Strong or Excess areas will repel the doctor's Qi. If the diseased area repels the doctor's Qi, he or she must immediately dredge the Excess. First, the doctor should focus on the region surrounding the Excess to drain the Excess energy away from the damaged points, then dredge the Excess energy away from the original trauma area. This technique is excellent for damaged or sprained joints. The doctor should focus on the patient's breathing when dredging. As the patient inhales, the doctor exhales and vice-versa. As the patient exhales, he or she releases pathogenic factors; by inhaling when the patient exhales, the doctor facilitates this process, and prevents depletion of his or her own Qi (Figure 8.4).

3. Disease transmission may occur due to the External invasion of pathogenic Qi into the body through the points. Some points are particularly vulnerable to exogenous invasions, especially Wind invasion. Wind-susceptible points usually have the word Feng in their names.

POINT NAMES

Traditionally, each point has a name, which either describes its location, its energetic function, or both. In addition, modern acupuncture texts have assigned a name and number for each point, according to its channel and its order along the natural course of the channel.

Sometimes a point may have several different traditional names, varying according to whether they are being used by medical Qigong doctors, acupuncturists, martial artists, or religious practitioners; for example, GV-1 is called Changqiang (Long Strength) in Traditional Chinese Medicine, and Weilu (Tail Gate) in medical Qigong and Daoist inner alchemy.

The history of point naming and the different terminologies used can be traced back to the different Buddhist and Daoist temples in ancient China. Each religious sect had its own specific names given to certain points, in accordance with the temple's spiritual and energetic needs. Giving the points different names was a form of secret code, used to keep the system pure and to prevent the knowledge from falling into the hands of the uninitiated or unscrupulous.

Sometimes the same name may refer to different points or areas on the body; for example, Yuzhen (Jade Pillow), located in the occipital region on the posterior base of the skull, is the name commonly used for Bl-9 in Traditional Chinese Medicine. However, in medical Qigong and Daoist inner alchemy, Yuzhen instead refers to an entire area the size of one's fist placed between the bilateral Bl-9 points.

CLASSIFICATION OF ENERGETIC POINTS

The points are further classified according to their energetic potential. This classification will assist the doctor of Traditional Chinese Medicine in choosing the right point or points to treat. The following is a list of energetic point classifications.

THE FIVE ANTIQUE SHU POINTS

Like the internal organs and channels, some points have a more powerful influence on the body then others. Each point has an action on the quantity of energy of an organ. Along each of the Twelve Primary Channels lie five specific points below the elbow or the knee called Antique Shu points (also called Transporting points and Command points). These points belong to the oldest classification of points, and are described in water images, comparing each section of the channel to the course water takes as it emerges from the ground and makes its way to the ocean. They are identified as follows: Jing (Well), Ying (Spring), Shu (Stream), Jing (River), and He (Sea). These five points are situated along the flow of energy from the extremities to the torso (running from the fingers to the elbows and from the toes to the knees), occupying the same progressive location along the patient's channels (Well, Spring, Stream, River, and Sea).

Centrifugal and Centripetal Energy Flow

All of the body's channel points energetically progress in two opposite currents according to the direction and flow of the channel's energy. These two energy currents are described as follows.

1. The Channel's Outward Centrifugal Flow of Qi passes from the organ, through the channel, to the point, and is expressed or intensified through the patient's exhalation. The outward centrifugal flow of energy is manifested in channel points and in areas of the body where there are conditions of Excess.
2. The Channel's Inward Centripetal Flow of Qi passes from the point, through the channel, to the organ. The inward centripetal flow of energy is manifested in channel points and areas of the body where there are conditions of Deficiency.

Through stimulation, channel points fulfill a double function. Centrifugally, they inform the doctor of impending internal disorders by discharging Excess energy. Centripetally, they transmit the energetic action placed on them, absorbing energy to supply the body's internal insufficiencies.

Yin and Yang Channels and the Five Elements

Each of the Five Antique Shu points also corresponds to the Five Elements, in the progression of the Creative Cycle. Each Yin channel begins

Points	Yin Channel Elements (Ethereal Soul—Hun)	Yang Channel Elements (Corporeal Soul—Po)
Jing-Well Points	Wood	Metal
Ying-Spring Points	Fire	Water
Shu-Stream Points	Earth	Wood
Jing-River Points	Metal	Fire
He-Sea Points	Water	Earth

Figure 8.5. The Five Antique Shu Points and their Correspondence to the Five Elements

with the Hun progression through the Five Elements, starting with Wood, then Fire, Earth, Metal, and Water. Each Yang channel begins with the Po progression through the Five Elements, starting with Metal, then Water, Wood, Fire, and Earth (Figure 8.5).

Similar to the eyes relationship to Wood (Hun) and Metal (Po), the beginning points on the Twelve Primary Channels also have a relationship to either a Wood (Ethereal Soul) or Po (Corporeal Soul) connection. Hence, in meditation exercises, when specific finger tip points are connected, the blending of the Hun and Po energies are established. The practice of connecting specific finger tip points is sometimes referred to as the connection (or fusion) of the body's Ethereal and Corporeal Soul.

The Five Antique Shu points energetically flow from superficial to deep and are susceptible to external pathogens and climatic changes. The distal points on the feet tend to be more powerful than those on the hands. After the manipulation of the patient's distal points, the local channel points are used according to their feeling of tenderness. The Five Transporting points are explained as follows.

1. Jing-Well points are the first points along the extremities of the channels and are located at the tips of the fingers and toes. These points are where the energy of the channel pools and is at its most superficial and thinnest.

   These points are where the energy of the channels leaves the body moving centrifugally outward. At the end of the fingertips and toes, the channel's energetic polarity changes from Yin to Yang or vice versa. Due to this shift in polarity, the energy at the channel's extremities tends to be unstable, and therefore more easily influenced.

   Due to their outward movement of energy, the Well points can be used by the Qigong doctor to eliminate the patient's pathogenic factors quickly, especially when the Yin organs are affected. The Well points will also have a strong effect on the patient's mental state, quickly changing the patient's mood. These points are generally used for acute disorders, expelling exogenous pathogens, and mental disorders. They are used as "revival" points for loss of consciousness from fainting and heat stroke, convulsions, a feeling of fullness below the Heart, and local neuropathy (tingling, numbness, burning pain). In mental disorders, they are commonly used for irritability, mental restlessness, anxiety, hysteria, mania, and insomnia.
2. Ying-Spring points are the second points along the channels and, in all cases, are located in the second position of the channels' energetic progression up the arms or legs, and are located next to the Well points. These points are where the channel's energetic flow quickens its progression of Qi into the body.

At the location of the Spring points, the Qi in the channels is very dynamic and powerful. Slipping and gliding like the swirling movement of cascading water, the energy in these points can change quickly. The Spring points are generally used to eliminate Internal and External pathogenic factors (especially Heat) from the patient's body. They are also used when a disease effects a color change in the patient's complexion.

In the Yin channels, this point is always a Fire Element. Purging the Spring point in the Yin channels reduces Heat and clears Fire. In the Yang channels, the Spring point is always the Water Element point. The doctor can reduce Heat in the patient's Yang channel by tonifying this Water point.

3. Shu-Stream points are the third points along the channels and are located in the third position in the channels' energetic progression up the arms or legs, next to the Spring point (except for the Gall Bladder's Channel where it is the fourth point). These points are where the channel's energy rapidly pours through and slightly deepens its flow into the body.

   At these points, the external pathogenic factors penetrate deep into the channels and can be "transported" into the body's interior. These points are used to clear Wind and Dampness from the patient's channels or when a disease manifests intermittently.

4. Jing-River points are the fourth of the Five Transporting points; they are, however, not always located on the fourth point along the channel. The points are, however, always located between the wrist and elbow on the arms and between the ankle and knee on the legs. These points are where the channels broaden, and the energy flow continues to increase.

   At these points, the energy current flows wider, deeper, and more irregularly, like a large river, directing the invasion of external pathogenic factors towards the body's tendons, joints, and bones. These points are generally used when there is stagnation of Qi and Blood in the patient's channels, as well as for coughing, asthma, dyspnea, sore throat, and upper respiratory diseases.

5. He-Sea points are the fifth points of the Five Transporting points and, in all cases, are located at the elbows and knees. These points are where the energy of the channels is vast and plunges deep into the body.

   The Qi at the He-Sea points moves centripetally inward, flowing much slower, joining, collecting, and fusing with the general circulation of the body's energy (like a mighty river flowing into the sea). The He-Sea points are generally used for all Stomach and Intestinal diseases and for Internal disorders of the organs.

THE FIVE ELEMENTAL POINTS

Each of the Five Elemental points correspond to the Five Antique Shu points. The Five Elemental points are aligned in the progression of the Creative Cycle. Each Yin Channel begins with the Three Ethereal Souls (Hun) progression through the Five Elements, starting with Wood, then Fire, Earth, Metal, and Water. Each Yang channel begins with the Seven Corporeal Souls (Po) progression through the Five Elements, starting with Metal, then Water, Wood, Fire, and Earth.

THE SIXTEEN XI CLEFT (ACCUMULATION) POINTS

These points are used for purging acute conditions of Excess in the channels and organs. There is one point on each of the Twelve Primary Channels, plus one point on the Yin and Yang Heel Vessels, and one point on the Yin and Yang Linking Vessels. The Yin Channel Accumulation points are Lu-6, Pc-4, Ht-6, Sp-8, Lv-6, Kd-5, Yin Heel Kd-8, and Yin Linking Kd-9. The Yang Channel Accumulation points are LI-7, TB-7, SI-6, St-34, GB-36, Bl-63, Yang Heel Bl-59, and Yang Linking GB-35.

THE TWELVE FRONT MU (ALARM, COLLECTING) POINTS

The energy of the organs collect at these points; therefore, they can be used for both diagnosis and treatment. These points are palpated for diagnosis and may feel tender to the patient, either spontaneously or upon pressure. If they respond to light pressure or feel tight or swollen, the patient has an Excess condition; if the points respond to deep pressure or feel hollow or deflated the patient has a Deficient condition. The Twelve Front Alarm points are: Lungs Lu-1, Pericardium CV-17, Liver Lv-14, Spleen Lv-13, Gall Bladder GB-24, Kidneys GB-25, Heart CV-14, Stomach CV-12, Large Intestine St-25, Triple Burners CV-5, Small Intestine CV-4, and Bladder CV-3.

THE EIGHTEEN BACK SHU (ASSOCIATED, TRANSPORTING) POINTS

These points are all located on the Bladder Channel and are used for both diagnosis and treatment. These points transport Qi very effectively and directly to the internal organs. They can be used for treating the corresponding sense organs. The Eighteen Back Transporting points are: Lungs Bl-13, Pericardium Bl-14, Heart Bl-15, Governing Vessel Bl-16, Diaphragm Bl-17, Liver Bl-18, Gall Bladder Bl-19, Spleen Bl-20, Stomach Bl-21, Triple Burners Bl-22, Kidneys Bl-23, Sea of Qi Bl-24, Large Intestine Bl-25, Gate to the Yuan Qi (Guan Yuan) Bl-26, Small Intestine Bl-27, Bladder Bl-28, Sacrum Bl-29, and Anus Bl-30.

THE FIFTEEN LUO (CONNECTING) POINTS

One of these points is located on each of the Twelve Primary Channels, as well as the Governing and Conception Vessels and the Great Luo point of the Spleen. These points are used to treat channel pathology. The Fifteen Collateral points are divided into Yin and Yang channel points. Yin Channel points include: Lu-7, Pc-6, Ht-5, Sp-4, Lv-5, Kd-4, CV-15, and the Great Luo Channel Sp-21. The Yang Channel points include LI-6, TB-5, SI-7, St-40, GB-37, Bl-58, and GV-1.

THE TWELVE ENTRY POINTS

These points are where the energy from a Primary Channel enters its coupled channel in the Horary Cycle. The entry point is the first point on each channel in all cases, except for the Large Intestine's Channel in which it is LI-4.

THE TWELVE EXIT POINTS

These points are where the Qi leaves the Primary Channel to flow into its coupled channel in the Horary Cycle. The Yin Channel Exit points include: Lu-7, Pc-8, Ht-9, Sp-21, Lv-14, and Kd-



Figure 8.6. Locations of the Body's Master and Couple Points

Channel	Open with Master Point	Complete with Couple Point
Governing	Hand (SI-3)	Foot (Bl-62)
Conception	Hand (Lu-7)	Foot (Kd-6)
Thrusting	Foot (Sp-4)	Hand (Pc-6)
Belt	Hand (TB-5)	Foot (GB-41)
Yin Linking	Hand (Pc-6)	Foot (Sp-4)
Yang Linking	Foot (GB-41)	Hand (TB-5)
Yin Heel	Foot (Kd-6)	Hand (Lu-7)
Yang Heel	Foot (Bl-62)	Hand (SI-3)

Figure 8.7. The Vessels with their Associated Master Points and Couple Points

22. The Yang Channel Exit points include: LI-20, TB-23, SI-19, St-42, GB-41, and Bl-67.

THE EIGHT INFLUENTIAL POINTS

These points have specific effects on their respective organs, substances, and tissues. They affect the body's Qi, Blood, sinews, blood vessels, bones, and Marrow, as well as the Yin and Yang organs. The Eight Influential points are as follows: Yin Organs Lv-13, Yang Organs CV-12, Qi CV-17, Blood Bl-17, sinews GB-34, blood vessels Lu-9, Bones Bl-11, and Marrow GB-39.

THE EIGHT CONFLUENT POINTS

These eight points communicate with the Eight Extraordinary Vessels. The Confluent points are divided into Master and Coupled points. The Master point is the primary point chosen for treatment, its Coupled point is the connecting or secondary point used to open the specific Vessel. Each of the Eight Extraordinary Vessels has both a Master and Coupled Confluent point on the upper or lower limbs.

All of the Eight Extraordinary Vessels can be treated in various combinations according to their specific Master and Coupled point locations (Figure 8.6). If, for example, the Qigong doctor causes Qi to flow from the patient's Master point on the hand (SI-3) to its Coupled point (Bl-62) on the foot, the Governing Vessel will open. To complete the treatment, the doctor must first remove stimulation from the Coupled point then disconnect from the Master point (Figure 8.7).

The Eight Confluent points are as follows: Governing Vessel SI-3, Conception Vessel Lu-7, Belt Vessel GB-41, Thrusting Vessels Sp-4, Yang Heel Vessel Bl-62, Yin Heel Vessel Kd-6, Yang Linking Vessel TB-5, and Yin Linking Vessel Pc-6.

THE TWELVE YUAN-SOURCE POINTS

Each of the Twelve Primary Channels has a Yuan-Source point, where the body's Original Qi surfaces and pools. On the Yin Channels, the Yuan-Source points are always the Shu-Stream points. On the Yang Channels, however, the Yuan-Source points are separate points located between the Shu-Stream and the Jing-River points. These points are usually the fourth point from the distal end of the channel, except in the case of the Gall Bladder Channel, where the Yuan-Source point is the fifth point.

The Yuan Qi originates and resides in the Lower Dantian area and is dispersed to the Yin and Yang organs and then to the limbs by the Triple Burners.

The Yuan-Source points can be used clinically in diagnosis for the Yin organs. The Qigong doctor examines the points by both palpation and visual diagnosis.

The Yuan-Source points are the primary points on the Yin channel for tonifying and regulating their respective Yin organs. On the Yang Channels, the Yuan-Source points are quite different in terms of their importance and energetics. These points generally have a negligible tonifying effect on their related Yang organs and comparatively little Qi regulating effect. Their main functions are to expel various pathogenic factors, and to treat disorders along their channel pathways. The Twelve Yuan points are as follows: Gall Bladder GB-40, Liver Lv-3, Lungs Lu-9, Large Intestine LI-4, Stomach St-42, Spleen Sp-3, Heart Ht-7, Small Intestine SI-4, Bladder Bl-64, Pericardium Pc-7, and Triple Burners TB-4.

THE POINTS OF THE FOUR SEAS

The human body has four seas: the Sea of Qi, Sea of Blood, Sea of Marrow, and the Sea of Nourishment (literally Water and Grain). To access these seas, the Qigong doctor stimulates the following points:

1. The Sea of Qi points include: Bl-10, St-9, CV-17, GV-14 and GV-15. When the Sea of Qi is in Excess, symptoms include fullness in the chest, flushed complexion, and dyspnea. When the Sea of Qi is Deficient, symptoms include fatigue or low energy and an inability to speak.
2. The Sea of Blood points include: Bl-11, St-37, and St-39. When the Sea of Blood is in Excess, symptoms include anxiety, uneasiness, and unrest, and the entire body feels big. When the Sea of Blood is Deficient, symptoms include the body feeling too small for no apparent reason.
3. The Sea of Marrow points include: GV-15, GV-

16, GV-17, and GV-20. When the Sea of Marrow is in Excess, symptoms include sensations relating to that of Excess energy (lightness, feelings of strength and vitality). When the Sea of Marrow is Deficient, symptoms include fatigue, vertigo, dizziness, tinnitus, pain in the lower legs, impaired vision, and a desire to sleep.

4. The Sea of Nourishment points include: St-30 and St-36. When the Sea of Nourishment is in Excess, the abdomen feels distended. When the Sea of Nourishment is Deficient, symptoms include hunger with an inability to eat.

UPPER (UNITING) HE-SEA POINTS

There are three points on the upper arm that have a powerful effect on the Yang organs. The affected organs and their points include the Stomach LI-10, Large Intestine LI-9, and the Small Intestine LI-8.

LOWER (UNITING) HE-SEA POINTS

Each of the Yang organs has a uniting He-Sea point on the leg, which can be used to treat Yang organ problems. The three Yang channels of the feet also correspond to the three Yang channels of the hands. The Lower Six Lower He-Sea points are as follows: Stomach St-36, Large Intestine St-37, Small Intestine St-39, Triple Burners Bl-39, Bladder Bl-40, and Gall Bladder GB-34.

THE ELEVEN GHOST POINTS

In ancient times, these eleven points were traditionally used for spirit possession and have a specific effect on the mind's psychological functions. In traditional Chinese medical clinics today, these points are commonly used to treat emotional disorders. The Eleven Ghost points are as follows: GV-26, Lu-11, Sp-1, Pc-7, Bl-62, GV-16, St-6, CV-24, Pc-8, GV-23, and LI-11.

THE TEN WINDOW OF THE SKY POINTS

These ten points also have a specific effects on the mind's psychological functions and are also commonly used to treat emotional disorders. The Ten Window of the Sky points are as follows: Lu-3, LI-18, TB-16, Bl-10, St-9, CV-22, GV-16, SI-16, SI-17, and Pc-1.

SUMMARY OF POINTS

Understanding the origin and function of the body's energetic points, as well as the Qi flow along the energetic channels, allows the Qigong doctor to emit energy through these energetic cavities to easily access the tissues and internal organs of the patients body. It is through this understanding that the doctor can also lead and purge the Toxic or pathogenic Qi (which has become stagnant or detrimentally active within the patient's body) away from the diseased organs, through the channels and out the body.

The following graph (Figure 8.8) is a basic categorization of the body's points and their descriptions.

Category	Points	Description
Five Antique Shu Points	Jing-Well, Ying-Spring, Shu-Stream, Jing-River, He-Sea	Transporting and Command Points
Sixteen Xi Cleft Points	Yin: Lu-6, Pc-4: Ht-6, Sp-8, Lv-6, Kd-5, Yin Heel Kd-8, and Yin Linking Kd-9 Yang: LI-7, TB-7, SI-6, St-34, GB-36, Bl-63, Yang Heel Bl-59 and Yang Linking GB-35	Accumulation Points
Twelve Front Mu Points	Lungs Lu-1, Pericardium CV-17, Liver Lv-14, Spleen Lv-13, Gall Bladder GB-24, Kidneys GB-25, Heart CV-14, Stomach CV-12, Large Intestine St-25, Triple Burners CV-5, Small Intestine CV-4, and Bladder CV-3	Alarm, Collecting Points
Eighteen Back Shu Points	Lungs Bl-13, Pericardium Bl-14, Heart Bl-15, Governing Vessel Bl-16, Diaphragm Bl-17, Liver Bl-18, Gall Bladder Bl-19, Spleen Bl-20, Stomach Bl-21, Triple Burners Bl-22, Kidney Bl-23, Sea of Qi Bl-24, Large Intestine Bl-25, Gate to the Original Qi (Guan Yuan) Bl-26, Small Intestine Bl-27, Bladder Bl-28, Sacrum Bl-29 and Anus Bl.30	Associated, Transporting Points
Fifteen Luo Points	Yin: Lu-7, Pc-6, Ht-5, Sp-4, Lv-5, Kd-4, CV-15, the Great Luo Channel Sp-21 Yang: LI-6, TB-5, SI-7, St-40, GB-37, Bl-58 and GV-1	Connecting Points
Twelve Entry Points	The first point on each channel except for the Large Intestine Channel in which it is LI.4	Qi enters Channel
Twelve Exit Points	Yin: Lu-7, P-8, Ht-9, Sp-21, Lv-14 and Kd-22 Yang: LI-20, TB-23, SI-19, St-42, GB-41 and Bl-67	Qi exits Channel
Eight Influential Points	Yin Organs Lv-13, Yang Organs CV-12, Qi CV-17, Blood Bl-17, Sinews GB-34, Blood Vessels Lu-9, Bones Bl-11 and Marrow GB-39	Influence Internal Organ Function
Eight Confluent Points	Governing Vessel SI-3, Conception Vessel Lu-7, Belt Vessel GB-41, Thrusting Vessels Sp-4, Yang Heel Vessels Bl-62, Yin Heel Vessels Kd-6, Yang Linking Vessels TB-5 and Yin Linking Vessels Pc-6	Master and Couple Points
Twelve Yuan-Source Points	Gall Bladder GB-40, Liver Lv-3, Lungs Lu-9, Large Intestine LI-4, Stomach St-42, Spleen- Sp-3, Heart Ht-7, Small Intestine SI-4, Bladder Bl-64, Pericardium Pc-7, and Triple Burners TB-4	Source of Original Qi Points
Four Seas Points	Sea of Qi Points: Bl-10, St-9, CV-17, GV-14 and 15 Sea of Blood Points: Bl-11, St-37 and 39 Sea of Marrow Points: GV-15, 16, 17, and 20 Sea of Nourishment Points: St-30 and 36	Give Access to the Four Seas
Upper He-Sea Points	Stomach LI-10, Large Intestine LI-9 and the Small Intestine LI-8	Affect the Yang Organs
Lower He-Sea Points	Stomach St-36, Large Intestine St-37, Small Intestine St-39, Triple Burners Bl-39, Bladder Bl-40, and Gall Bladder GB-34	Affect the Yang Organs
Eleven Ghost Points	Governing Vessel 26, Lungs 11, Spleen 1, Pericardium 7, Bladder 62, Governing Vessel 16, Stomach 6, Conception Vessel 24, Pericardium 8, Governing Vessel 23, and Large Intestine 11	Affect the Mind, Emotion, and Spirit
Ten Windows of the Sky Points	Lung 3, Large Intestine 18, Triple Burners 16, Bladder 10, Stomach 9, Conception Vessel 22, Governing Vessel 16, Small Intestine 16, Small Intestine 17, and Pericardium 1	Affect the Mind, Emotion, and Spirit

Figure 8.8. Point Graph

CHAPTER 9
THE EXTRAORDINARY YANG ORGANS

Besides the six Yin organs (Liver, Heart, Pericardium, Spleen, Lungs, and Kidneys) and six Yang organs (Gall Bladder, Small Intestine, Triple Burners, Stomach, Large Intestine, and Bladder), the body has six Extraordinary Yang organs, also called the "curious organs." These Extraordinary organs function like Yin organs (storing Yin Essence, i.e., Blood, Marrow, or Kidney Essence) but look like Yang organs (they are hollow). These six curious organs include the Uterus, Brain, Marrow, Bones, Blood Vessels, and Gall Bladder. The body's Eight Extraordinary Vessels integrate the Extraordinary Yang organs with the main six Yang organs and the Kidneys.

THE UTERUS

In Chinese medicine, the uterus encompasses the fallopian tubes and the ovaries and has the function of regulating menstruation, conception, and pregnancy (Figure 9.1). The uterus connects to the Kidneys (which provide the uterus with Jing), the Conception Vessel (which provides the uterus with Qi and nourishes the fetus), and the Thrusting Channel (which provides the uterus with Blood). Only when the Jing of the Kidneys is sufficient can the menstrual period occur regularly, the woman become pregnant, and fetal growth become possible. The Qi and Blood of the Twelve Primary Channels pass into the uterus through the Thrusting and Conception Vessels, affecting the amount of menstrual flow and its cycle.

The three Yin organs of the Heart, Liver, and Spleen also energetically connect to the uterus through their relationships with the Blood. The Heart governs the Blood. The Liver stores the Blood and regulates the volume of circulating Blood, which is responsible for normal menstruation. The Spleen controls the Blood.



Figure 9.1. The Female Reproductive Organs, including the Uterus, Fallopian Tubes, and Ovaries


right and left lateral ventricles (phantom view)
cerebrum
fourth ventricle
third ventricle
cerebellum
cerebrum
thalamus
epithalamus (pineal)
midbrain
hypothalamus
pituitary
pons
cerebellum
medulla oblongata

Figure 9.2. The Human Brain

THE BRAIN

The Brain is considered the house of the Yuan Shen, and the seat of mental function. It is believed that the senses and control of the body's physical movements are related to the Brain. The Brain is functionally related to the Kidneys and controls memory, concentration, hearing, touch, sight, and smell. The Brain is also called the Sea of Marrow, extending from the top of the head to the GV-16 Wind Palace point, just below the external occipital protuberance. The Kidney Essence produces Marrow, which fills the spinal cord and Brain. The Brain also depends on the Heart's Blood for its nourishment. Because the Kidneys store the Jing and the Heart governs the Blood, the Brain depends on the balanced state of the Heart and Kidneys for vitality. The Brain is considered a transformation chamber of both Prenatal and Postnatal Essence (Jing) and Energy (Qi). The Brain is regulated by the Governing Vessel, as well as the Yin and Yang Heel Vessels.

This viewpoint is quite different from the Western approach, which views the brain's anatomy as consisting of five regions (Figure 9.2), including:

1. The cerebral hemispheres or cerebrum (the neocortex (neopallium),
2. The thalamus, hypothalamus, and epithalamus (pineal),
3. The midbrain/mesencephalon (the colliculi and cerebral peduncles),
4. The pons and cerebellum, and
5. The medullae oblongata.

In Western medicine, the oldest part of the Brain (situated at the top of the Brain stem) is often called the "reptilian Brain" because its anatomical formation is similar to that found in lizards, alligators, and turtles. Surrounding it is the mammalian Brain, which is called the limbic system. The third part of the Brain is called the neocortex, which wraps itself around the limbic system. All three parts of the Brain (reptilian, mammalian, and neocortex) are viewed as biologically distinct, both in their chemistry and in their structure. The older formations of the Brain are responsible for the autonomic nervous system, whereas the neocortex is responsible for thinking and voluntary movement.

In Chinese energetic medicine, each selective set of the human brain cells absorbs and records sets of vibrations. The Brain receives these vibrations through the skin, eyes, ears, nose, and mouth, and records them in its cells. The mind interprets these incoming vibrations as images, sounds, smells, and sensations, and organizes these into memories. The extent to which the mind interprets the incoming data depends upon the level of consciousness and awareness of the individual at the time of the recording. When a Qigong doctor, attunes his or her vibrations to the patient's energetic field and emits Qi, the brain cells responsible for storing the vibrations are stimulated. When these vibrations are stimulated through the energy projected by a Qigong doctor, the patient's tissues respond and reproduce an energetic pattern similar to the original one used to record the patient's physical, mental, emotional, energetic and spiritual experiences. This energetic tissue reaction occurs only because the patient's cells are held directly to their same consistent vibrational patterning.

One set of selective brain cells receives, records, and maintains the vibrations of the thoughts, actions, movements, and pictures that other forms project. These vibrations can also be reproduced and projected, being received by the Qigong doctor as images from within his or her own mind through inner-vision. The Qigong doctor can arrange his or her cells' energetic pattern in such a way as to reproduce the words and motions of these forms or objects, even the thoughts of those that sent them. Through these cells, the Qigong doctor can assist his or her patient, as well as him or herself, in controlling their thoughts, as it is through these cells that accidents and disease are brought into existence; for example, someone either observes or imagines a specific thing happening. The corresponding vibration is fixed in the cells, sent out to be imprinted on the corresponding cells of anothers' Brain, then projected back until the incident is so fixed that the occurrence actually happens (self-fulfilling prophecy).

Another set of selective brain cells receives, records, and maintains the vibrations of the thoughts and activities of the divine. The divine energy vibration pervades every substance and is always sending out divine knowledge and true wisdom. Stored within the body are the cells that receive and project the vibrations of the divine Mind. If the doctor separates him or herself from the divine in thought, he or she will also separate from the divine in manifestation.

THE GALL BLADDER

The Gall Bladder stores the bile, which is considered a "pure" fluid. The function of the Gall Bladder is to aid digestion, as well as drain off Excess Heat from the Liver (Figure 9.3). The Gall Bladder is regulated by the energy of the Belt Vessel.



Figure 9.3. The Gall Bladder

THE MARROW

In Chinese medicine the term Marrow (Sui) is different from bone marrow as defined in Western medicine. The Marrow is the substance which is the common matrix of bones, bone marrow, the spinal cord and the Brain. The Marrow is rooted in the Jing and is connected to the Lower Dantian through the Governing Vessel. It is regulated by the energy of the body's Thrusting Vessels.

The Kidney Jing is the origin of the Marrow. The Marrow functions to form the bone marrow, as well as nourish the Brain and spinal cord. When the Mingmen warms and nourishes the body, the Marrow becomes full (which sustains the body's vertical posture and gives strength to both the Brain and the bones). When the Marrow is full, thinking is clear. Too much thinking leads to Excess Fire, which burns the Brain, causing dizziness, blurred vision, and tinnitus.

Both red and white blood cells are produced in the Marrow of the bones. The red blood cells (which circulate oxygen and eliminate carbon dioxide) are produced within the body's long bones (humerus, femur, tibia, etc.). The white blood cells (vital to the body's immune system) are produced within the body's flat bones (skull, sternum, scapulae, pelvis, etc.) The type of blood cells that are produced depends on the type of Marrow that predominates.

When all of the Postnatal energy acquired from the combination of physical (diet, food, and drink), mental/emotional (thoughts and emotions), and spiritual (prayer, meditation, and sex) cultivations is circulated through the Microcosmic Orbit (Fire Cycle), the Prenatal Qi stored in the bone marrow and Brain become stimulated, awaking the spiritual consciousness. This combination and circulation of physical, mental, emotional, and spiritual energy is why the brain marrow is considered to be constructed from the finest and most subtle essences, manifesting the original and hidden power of the Kidneys.

THE BONES

The bones are related to the Kidney's Jing. The bones support the body's structure, strength, and mobility, as well as store the bone marrow (Figure 9.4). The bones are extremely porous and are always "breathing," they are regulated by the energy of both the body's Conception and Thrusting Vessels. The pores of the bones allow Qi and Blood to be absorbed and released, the same way a sponge absorbs and releases water.

There is a natural union between the energetic function of the Marrow and the bones. The Marrow, held within the bones, assures the power and


temporal
frontal
maxilla
mandible
hyoid
manubrium
sternum
xiphoid process
radius
ulna
clavicle
humerus
ischium
femur
patella
tibia
fibula
parietal
occipital
scapula
cervical
thoracic
lumbar
ilium
sacrum
coccyx
talis
calcaneus

Figure 9.4. The human skeleton consists of 200 bones.


external carotid
internal carotid
vertebral
subclavian
common carotid
axillary
aortic arch
brachial
heart
thoracic aorta
abdominal aorta
radial
ulnar
iliac
femoral
popliteal
anterior tibial
posterior tibial

Figure 9.5. The blood-vascular system of the human body consists of the heart and blood vessels.

smooth suppleness of the bones. The bones, in return, prevent the dissipation of the essential richness of the Marrow.

The bones are the only solid crystalline substance in the body capable of generating piezoelectric charges. These electromagnetic charges generate fields of energy that receive and send impulses to the blood cells, tissues, organs, and channels. The Brain, nervous system, Heart, and lower abdomen also generate electromagnetic fields that resonate with the bones, as well as other crystalline-like structures. The crystalline structures of the bones amplify, radiate, and transmit energy, as well as bio-information, to the rest of the body. The rhythmic oscillation of bone-generated electromagnetic fields is released through the transmission of the bones acting as tuning forks. These living tuning forks vibrate the Qi throughout the body's entire physical structure, extending outward into the body's external Wei Qi fields.

THE BLOOD VESSELS

In Chinese medicine, the concept of Blood is different in characteristic and function from that of Western medicine. Blood originates from the transformation of food and drink by the Spleen, which then transfers the refined food energy to be further enhanced by the Heart Qi, Lung Qi, and the Qi of the air.

Qi and Blood flow together, with Qi being the active force that makes the Blood circulate and keeps it within the blood vessels (Figure 9.5). Both Qi and Blood flow within the channels and blood vessels, continuously circulating throughout the body to nourish, maintain, and moisten the tissues. Qi is an energetic form and is considered a Yang substance, while Blood is a liquid form of energy and is considered a Yin substance.

The blood vessels contain Blood and are indirectly related to the Kidneys, because the Kidney Essence (Jing) produces Marrow, which contributes to the production of Blood. The function of the blood vessels is to transport Qi and Blood throughout the body for nutrition and regeneration. The blood vessels are regulated by the energy of the body's Thrusting Vessels, and the Blood is contained in the blood vessels by the Spleen.

SECTION II

THE THREE OUTER FORCES: HEAVEN, EARTH & MAN

CHAPTER 10
INTRODUCTION TO THE THREE OUTER FORCES

THE NATURAL POWER OF THE THREE OUTER FORCES

The Three Outer Forces (Powers) of Heaven, Earth, and Man represent the sum total of all natural forces and energetic factors, which affect the human body on all levels of existence (physical, mental, emotional, energetic, and spiritual). In ancient times, the relationship between the waxing and waning of Heavenly (universal) and Earthly (environmental) energy, as well as the corresponding shifts, changes, and adjustments occurring within the human body, provided the Chinese sages with the theory of the Three Outer Forces. These ancient Chinese masters discovered that the human body's internal network of systems is directly affected by the influences and variations of energetic cycles of the sun, moon, and stars. We now know that these natural influences also affect atmospheric pressures, causing high and low temperatures, which in turn, affect the body's tissues. Recently, Ukrainian physicists found that human DNA vibrates at the same frequency as solar energy.

The Heaven and Earth Powers are responsible for the energetic field changes that cause adjustments and shifts within man's Jing, Qi and Shen (known as the Three Treasures), stored within the internal organs and tissues. Together the combination of Heavenly and Earthly influences affect the functional status of the body's internal organs and the distribution of Qi and Blood throughout the body.

Each of the body's cells, tissues, organs, and organ systems emanates its own specific electromagnetic energy field. This energetic field pulsates at its own particular frequency, regulating the body's internal energy currents and radiating an energetic field that extends outside the body. The body's energetic field (Wei Qi) interacts with and is influenced by the larger energetic fields surrounding it (i.e., power lines, crowds of people, geological formations in the Earth, and the cosmic fields of the solar system).

THE THREE OUTER FORCE'S NINE TREASURES

Each of the Three Outer Forces manifest through a secondary triad of Treasures. These Three Treasures complete the energetic matrix that encompasses the Outer Forces unified energetic field.

1. The Three Treasures of the Heavenly Power are the energy fields of the sun, moon, and stars;
2. The Three Treasures of the Earthly Power represent the energy of the Earth (soil and rock), wind, and water;
3. The Three Treasures of Man are contained within man's Essence (Jing), Energy (Qi), and Spirit (Shen).

These three intricate networks exchange their energetic influence and affect the functional status, as well as the distribution of the body's Qi and Blood.

THE THREE OUTER FORCES AND CHINESE ALCHEMY

Each of the Three Outer Forces and their Three Treasures also constitute the basis of Chinese internal alchemy, whereby Jing (Essence) is transformed into Qi (Energy), Qi is transformed into Shen (Spirit), and Shen is transformed into Wuji (infinite space), and then released back to the Dao (or divine).

The Powers of Heaven and Earth are not only interlinked, but also exist as a microcosm or "small universe" within man's physical body. The human body is an active interaction of two basic elements of Yin and Yang polarity. Yang energy ascends and is expressed through expansive, active, hard, and aggressive energetic movements. Yin energy descends and is expressed through contractive, passive, soft, and yielding movements. All matter, from the smallest molecular particles to enormous planets and stars, is composed of energy and bound into various patterns of vibration. These matter formations are held in place by electromagnetic and nuclear forces interconnected by the power of Yin and Yang polarity, and are expressed through the Three Outer Forces. The seasonal cycles are an example of Yin Earthly movements, while the solar and lunar cycles are expressions of Yang Heavenly energy.

The creation and manifestation of matter is composed and regulated by what are known as the Five Elemental patterns. In traditional Chinese understanding, it is believed that perfect health and longevity depend largely on man's ability to harmonize with the transitions and five seasonal changes of Heaven and Earth, in accordance with the Five Elemental patterns. In the winter, for example, there is less sunlight, and the temperature can be very cold (Yin), and the Kidneys (Water Element) can easily be overworked; therefore, man should endeavor to lighten his work load and rest more in winter, conserving his Qi to avoid energy depletion.

The principles of Chinese cosmology, Yin and Yang Theory, Five Elements Theory, the *Book of Changes (Yi-Jing),* and Traditional Chinese Medicine are all incorporated into the study of Medical Qigong. This culmination of knowledge reveals the basic structures of energetic dynamics relating to the universal and environmental energy gathered from the Heavens and Earth, and their relationship with man.

HEAVENLY QI

The first of the Three Outer Forces is known as the Universal Force, Original Force, or Heavenly Energy. This force manifests as the energy of the entire Cosmos. Each life born into human form is not only developed and structured but is also influenced by its own unique group of stars within the Heavenly realm. This particular group of stars (including the sun, moon, planets, and constellations), controls or influences the persons life-force energy (Figure 10.1).

Heaven is the realm that predetermines the energetic cycles of birth and death, as well as the seasons and times of planting, fertility, and harvest. It is the source of the Yuan Shen and the Virtue of Dao, as it manifests through universal awareness (divine inspiration, enlightenment and spiritual communion), and free will. Heaven is the residence of spiritual deities and the Jade Emperor (or Divine Creator), and it manifests its prenatal power in man's life through the mysterious forces of fate, destiny, karma, and reincarnation.

According to the ancient Chinese, we exist in a three-dimensional world that exists within the relative parameters of time and space. Heaven represents time, which is symbolized by the circle. Because time moves in circles, hours and days are defined by the circular rotation of the Earth on its axis; months are defined by the circling of the moon around the Earth, and years are defined by the Earth's orbit around the sun.

PHILOSOPHICAL CORRELATION

Man is constantly absorbing energy from the sun, moon, planets, and constellations. In order to explore the patterns of Heavenly energy in detail, the ancient masters developed the science of Chinese astrology, which includes the study of Twelve Animals and Five Elements, as well as the interactions of the Twenty Eight Constellations, Twelve Earthly Branches, Ten Heavenly Stems, Five Planets, and Lunar and Solar Energy Cycles.

The ancient sciences of astrology and divination evolved as a means to analyze, interpret, and predict how the various forces of Heaven influence and guide man's life on Earth. The study of Chinese astrology involves four elements of comprehension: the study of the Signs, the study of the Five Elements, the study of Yin and Yang, and the study of the Sixty-Year Cycle.

1. The Study of the Signs involves the twelve animals of the Chinese zodiac (meaning circus of animals) that encircle the Earth and are divided into twelve equal parts, called "signs." Each sign of the zodiac has certain



Figure 10.1. The Three Outer Forces of Heaven Consists of the Energy Released from the Sun, Moon and Stars.

characteristics that are determined by a particular planet and constellations. The signs affect the character of a person born under them. Each person is given three animal characteristics: one according to the year, the second according to the month, and the third according to the hour of his or her birth. You might, for example, be a Snake according to the year of your birth, a Boar according to the month, and a Dragon according to the hour. The animal governing your birth year represents your external self (the part you show others) and is said to exert a profound influence over your life. The month animal (known as the lunar animal) represents the emotional and psychological aspects of man's relationships. The hour animal represents the inner self (the part hidden from the rest of the world). The combination of the three determines the uniqueness of each individual.

2. The Study of the Five Elements is the next division involved in the study of signs. Each of the twelve animal signs is further differentiated into one of the Five Elements (Wood, Fire, Earth, Metal, and Water). The year of birth determines the element of the sign. Each element rules for a two-year cycle (e.g., January 27, 1952-February 13, 1953 was the year of the Dragon under the element of Water; February 14, 1953-February 2, 1954, was the year of the Snake under the element of Water. The next Water cycle of Dragon and Snake will be in 2012, based on the sixty-year cycle). These Five Elements display an energetic force that affects the formation of the internal organs in the growing fetus, as well as influences the physical, mental, emotional, energetic, and spiritual changes after the child is born.
3. The Study of Yin and Yang is the third division of the study of signs. Each of the twelve animal signs is also governed by a Yin (passive) or Yang (active) direction. The Yin and Yang cycles alternate each year, with Yang being the even years, and Yin the odd years.
4. The Study of the Sixty-Year Cycle is the final division of the study of signs. The yearly correspondence of the twelve animals of the Chinese zodiac also relates to the Twelve Earthly Branches, and is based on a sixty-year cycle. Every sixty years, the sun, moon, Earth, and the North (Pole) Star are in alignment, and a new sixty-year cycle begins. A sixty-year cycle also completes the rotation of the twelve animals through each of the Five Elements. The Chinese consider sixty years a "century" in terms of the human life cycle.

PHYSICAL CORRELATION

Heavenly Qi relates to the congenital strength and formation of the body's internal organs, as determined by the Universal Energetic Fields (which include the energy emitted from the sun, moon, planets, and Twenty-Eight Constellations).

HEAVEN'S ENERGETIC GRID

Similar to the grid system imprinted on the body's energetic field, there exists a massive interconnected Heavenly grid extending throughout the entire universe. This Heavenly grid connects the sun, moon, stars, planets, and constellations throughout our universe, and extends to other solar systems outside our celestial sphere. There are pockets of Heavenly energy (like energetic points), as well as subtle frequency pathways (similar to energetic channels), that follow a progression of universal order.

EARTHLY QI

The second of the Three Outer Forces is known as the Environmental Force, Acquired Force, or Earthly Qi. This force manifests as the energy of the entire planet. Each life born into human form is not only developed and structured but also influenced by its own unique environment within the Earthly realm. The Qi of the individual's particular geographic location includes the energy of the plants, soil, water, animals, and all natural formations responsible for controlling or influencing the person's life-force energy.

The Chinese believed that the Earth is the realm that predetermines the abundance of harvest, as well as the temperance of man's physical stamina. Both harvest and man's physical stamina is determined through the cyclic changes of the five seasons and their relationship to the Five Phases (birth, maturation, peak, decay, and death). The Earth is the source of the natural forces and rhythms of nature, as well as the basic elements and energies that compose the material world of soil and water, mountains and valleys, oceans and rivers, plants and animals. The Earth is the foundational base of the Five Elements through the cyclic transformations of nature, which in turn, shape the human body's physiological form and govern the biological functions of the tissues.

The ancient Chinese viewed the Earth as the center, and as the ground on which we stand looking outward toward the four directions. Just as Heaven defines our movement through life in terms of time, Earth defines the space in which we live, providing the energetic field for our unfolding, within the boundaries of time.

In Chinese symbology, the Earth is symbolized by the image of the square, whose walls face the four cardinal directions. This concept of the energetic interaction of Heaven (symbolized by the circle) and Earth's (symbolized by the square) was so fundamental to ancient Chinese thought that they even designed the coinage of the imperial realm to reflect this interconnection (a round coin with a square center).

PHILOSOPHICAL CORRELATION

Earthly Qi relates to the study of Feng Shui (Harmony of Wind and Water). Feng Shui is divided into two prominent schools of study, the Form School and the Compass School.

1. The Form School is the original school of Feng Shui, originating in Southwest China. This school focuses primarily on developing environmental harmony, by observing the shape and form of the terrain in conjunction with the Five Elemental animals.
2. The Compass School is the second school of Feng Shui. It focuses primarily on developing universal and environmental harmony through the directional orientation of the compass, in relationship to the Ten Heavenly Stems, Twelve Earthly Branches, Twenty-Four Solar Compass Directions, and Twenty-Eight Constellations, as well as the Magic Square and the Bagua (Eight Trigrams).

PHYSICAL CORRELATION

Earthly Qi relates to the "acquired" strength (muscular and skeletal development after birth), as well as the formation of the body's internal organs. Tissue development is determined by the environmental energetic fields (which include the energy emitted from the Earth, Water, and Wind/weather). The Earth energy also expresses its power in man's life through the basic instincts for survival and the primal drives for sex and reproduction.

EARTH'S ENERGETIC GRID.

Similar to the Heavenly energetic grid system imprinted in the cosmos, there exists a massive interconnected Earthly grid extending throughout the entire planet. This Earthly grid connects the planet's eight energetic directions into one energetic field. There are pockets of Earthly energy (like energetic points), as well as subtle frequency pathways (similar to energetic channels), that follow a progression of environmental order. One example of the Earth's axial grid system in Western folklore is the "Ley lines," which are energetic pathways that connect energy vortices or places of power on the planet. This understanding of an Earthly energetic grid system is also reflected in American Indian and South American traditional understanding.

MAN'S QI

The third of the Three Outer Forces is known as the Human Force, or Man's Energy. This force manifests as the energy of the entire body (Figure 10.2). Each life born into human form is not only developed and structured, but also influenced by the individual's adaptations to his or her own physical, mental, emotional, energetic, and spiritual energies.

It is believed that within man, the realm of the Dao or divine conscious spirit exists, wherein both the energies of Heaven and Earth coexist in harmonious balance. Man is formed from the cosmic particles of exploded stars that have descended onto the Earth. These particles are absorbed into the soil, water, and foliage, creating sustenance for human life. This constant internal connection, absorption, and regeneration of vibrating energy from Heaven and Earth is the reason that human life is considered to be the highest physical manifestation of the divine energetic field (see Chapter 1).

PHILOSOPHICAL CORRELATION

Man's Qi relates to the study of the Yi-Jing (I-Ching), or Book of Changes. The Yi-Jing is composed of two sections: the Book of Oracles and the Book of Commentaries.

1. The Book of Oracles is the original text by King Wen and the Duke of Zhou. This book is based on the formation of eight trigrams and their various energetic attributes. These eight trigrams combine to form the sixty-four hexagrams of the Yi-Jing, which were later used for divination.
2. The Book of Commentaries is based on the commentaries of Confucius and his followers, and is also called the Ten Wings. The commentaries are called "wings" because each



Figure 10.2. The Three Outer Forces of Man's Energy is composed of the Energetic Fields Released from Jing, Qi, and Shen.

wing helps the reader to soar higher in comprehension of the original text.

PHYSICAL CORRELATION

Man's Qi relates to the waxing and waning of man's physical, mental, emotional, energetic, and spiritual biorhythmic cycles.

A Qigong doctor must become proficient at understanding, respecting, and adopting these laws of natural variations between nature and man. Through this understanding the doctor can attain a deeper comprehension of the principles and application of Medical Qigong Dao Yin training (mind concentration methods, respiration regulation, and postural manipulation).

MAN'S ENERGETIC GRID

Similar to the Energetic grid system of Heaven and Earth, the human body is imprinted with a massive interconnected grid that extends throughout the body's tissues into the environment. The body's energetic grid is responsible for transforming energy frequencies from cell to cell, tissue to tissue, and from the body's internal energetic field to its external energetic field. These are known in Traditional Chinese Medicine as the 'Jing Luo' channels and collaterals (or the meridian system). The body's energetic grids are also responsible for maintaining the production, growth, and development of energy and tissue formation, and are influenced through intention, thought, and emotion.

CHAPTER 11

THE THREE TREASURES OF HEAVEN: SUN, MOON, AND STARS

DEFINING HEAVEN QI

The Outer Force (Power) of Heaven's Three Treasures (the Sun, Moon, and Stars) manifests as electromagnetic radiation from the sun, reflected light and energy from the moon, starlight energy, and the gravitational forces and interactions of the above mentioned heavenly bodies. The Outer Force of Heaven's Three Treasures also include the twenty-eight constellations, five major planets, and their energetic and gravitational forces.

Heaven Qi is the energy emitted from the universe outside of the realms of Earth and man. The sun and moon, first five planets (Jupiter, Venus, Saturn, Mars, and Mercury), North Star, Big Dipper, and the twenty-eight constellations are the most easily observed natural Heavenly energies, which have a direct connection to life on Earth. The diagram below (Figure 11.1) shows the Five Elements relationship between the universal treasures of Heaven, the environment of Earth and Man's internal organs.

The sun and moon are the primary Heavenly manifestations of Yin and Yang energy. The sun is Yang and is considered the Spirit Soul (Hun) of the sky. The moon is Yin and considered the Corporeal Soul (Po) of the Earth. This interaction of Heavenly Yin and Yang energy affects and governs the Earthly Yin and Yang energy, as well as the Qi within the human body. The sun and moon each have their own cyclic rhythms and energies, changing their relative degrees of Yin to Yang at different times of the day, month, and year.

To cleanse, purify, and strengthen the body, Qigong doctors absorb the essence of the Heavenly Qi by guiding the star's energy into certain areas of the body. The energy of the stars may also be used to reinforce the circulation of Wei Qi for

Organ	Element	Time of Day	Direction	Planet	Associated Animal
Liver	Wood	Early Dawn	East	Jupiter	Green Dragon
Heart	Fire	Midday	South	Mars	Red Phoenix
Spleen	Earth	Midafternoon	Center	Saturn	Yellow Phoenix
Lungs	Metal	Late Dusk	West	Venus	White Tiger
Kidneys	Water	Night	North	Mercury	Indigo Tortoise

Figure 11.1. Natural Heavenly Transformations

added protection against external pathogenic invasion.

INFLUENCES OF HEAVENLY QI ON THE HUMAN BODY

The body's physical fluctuations work in harmony with the cycles of the sun, moon, and nature. The science that deals with the study of these biological clocks is known as chronobiology. The levels of corticosterone and plasma adrenocorticotropic hormone (ACTH), for example, follow a cyclical pattern during the course of a day. Generally, the body's emotional and menstruation cycle in women follow the changing patterns of the moon (i.e., approximately every 28 days). Additionally, approximately every 23 days, the male body releases stored toxins, changing the smell of the sweat in accordance with the body's physical biological cycle. The smooth functioning of natural biological rhythms can at times be disrupted. The "jet lag" phenomenon, for example, is due to the interruption of circadian rhythms in the body.

There are daily, weekly, monthly, and annual solar and lunar cycles to which the human body responds. Other human physical, emotional, and mental cycles are strongly influenced by the types of life-style chosen, and other environmental factors involved. The body's circadian rhythms influence not only the immune system, but also the Yin and Yang energies of the internal organs. The activities of the cells, glands, Kidneys, Liver, and nervous system are coordinated with one another and with the day-night rhythm of the environment. Hunger, excretion, and body temperature are influenced by the body's ability to respond to the micropulsations of the subtle energy fields within the internal organs and tissues, as well as the body's biological clocks.

In China, clinical scientist Liu Bing, from Beijing Medical University, notes in his research that the human body undergoes rhythmic variations within a 24-hour time period. These physical changes include temperature, oxygen consumption, blood pressure, pulse rate, content of hemoglobin, blood sugar, blood amino acids, blood adrenocortical hormone, hepatic glycogen, metabolic rate of fat absorption, and pace of cell metabolism. The natural clockwork of the body can also be altered by food, drink, drugs, and abnormal sleeping patterns.

BODY RHYTHMS AND ENERGETIC PATTERNS

The prenatal and postnatal energetic patterns of the body are also determined by the time and place of conception. The time and place of conception establishes the patient's spiritual energy and ancestral traits (food preferences, manner of dress, preferences of art, spiritual beliefs, and so on). The time and place of birth also determine the patient's energetic biorhythms (physical, emotional, and intellectual cycles).

PRENATAL ANCESTRAL TRAITS

The time and location of conception determine the nature of the ancestral spiritual influence on the patient. As the divine infuses the fetus's soul, the energy of the Eternal Soul combines with the environmental spiritual influences of the geographic location (e.g., the Orient, Europe, North America, etc.). This infusion of geographic spiritual energy creates within the patient a predisposition towards specific ancestral traits and cultural attractions.

At conception and throughout pregnancy, the mother absorbs the natural environmental energy through respiration (breathing through the mouth, nose, and pores), ingesting food (grown in the soil), and visual/auditory ingestion (observing and experiencing the cultural environment). The energetic history of each cultural environment exists within the memories stored in the natural energetic fields contained within that environment. Therefore, someone conceived within a particular geographic location in the Orient may find him or herself, unconsciously drawn to the social and cultural influences of that particular Asian population. This subconscious attraction is considered a natural phenomenon due to the geographic influences of the country's spiritual/ancestral power, causing an effect, indirectly, on the individual.


Physical Cycle

The Physical Cycle is 23 days long. The first 11 1/2 days are the positive side of the cycle. One experiences a feeling of good physical strength and endurance. The second 11 1/2 days are the negative side of the cycle, marked by having less endurance and a tendency towards fatigue.


Emotional Cycle

The Emotional Cycle is 28 days long. The first 14 days are the positive side of the cycle. One feels optimistic, cheerful, and cooperative. For the second 14 days, a negative stage of the cycle results in tendencies to be moody, irritable, and pessimistic.


Intellectual Cycle

The Intellectual Cycle is 33 days long. The first 16 1/2 days are the positive side of the cycle. One has greater success in learning new material and pursuing creative, intellectual activities. The next 16 1/2 days are the negative side of the cycle; one is encouraged to review old material rather than attempting to learn new concepts.

Figure 11.2. The physical, emotional, and intellectual cycles begin on the day of birth.

1. The natural environment of the location at conception exerts a strong influence, such as a preference, or attraction to similar geological formations throughout the individual's life. People conceived by the ocean, for example, may find within themselves an unconscious need to live by the ocean. Likewise, people conceived in the mountains, valleys, tropics, deserts, etc. may find an energetically calm feeling of peace envelop them when visiting such places.
2. The time of conception also exerts a strong influence. The energetic formation, as well as strength or weakness, of the fetus's internal organs is also determined by the positions of the sun, moon, and stars. These Heavenly energies begin their effect on the fetus at the time of conception and continue influencing the fetus's formation throughout the entire pregnancy.

BIRTH-POSTNATAL ENERGETIC PATTERNS

The time and location of birth determines the biorhythmic patterns of each individual. These biorhythms are developed according to the influence of the Heavenly energy (position of the sun, moon, and stars), as well as the Earthly energy (i.e., geographic location, e.g., mountains, valleys, by the ocean, etc.). This infusion of the Earth's geographic energy and Heaven's constellation energy creates within the individual a predisposition towards specific psychological traits.

1. The location of birth strongly influences the individual's desire to seek out and/or surround him or herself with the familiar environment.
2. The Time of Birth may also have an unconscious influence on his or her living patterns, as certain individuals born at night naturally become "night people," while others born in the morning function better during the morning hours.

The body's biorhythms, which react to universal and environmental energetic vibrations, are divided into three distinct cycles and energy flows (Figure 11.2). Each rhythm is cyclical, waxing and waning, creating and contributing to times of physical, emotional, and intellectual triumph, as well as times of reflection and withdrawn behavior. These three cycles begin at the moment of birth and continue with absolute regularity until death. The conditions of the cycle are divided into positive (the first half) and negative (the second half) attributes.

The body's biorhythms are but one example of the effects that Heavenly energy has on the physical, emotional, and intellectual cycles of mankind. By understanding the cycles of the sun, moon, and stars and their energetic potential, the Qigong doctor can utilize the universal energy of Heaven to regulate and balance the patient's Qi. The biological rhythms influence the time at which many illnesses occur or worsen, as well as how fast a medication takes effect and how long the effect lasts. Therefore, Medical Qigong therapy, as well as herbal therapy are prescribed at specific times to enhance their effect on the patient's body.

CYCLES OF THE SUN

The Earth's rotation around the sun causes seasonal changes and instigates cyclic metabolic patterns in the human body. The body's entire metabolic function is influenced by its ability to respond to the seasonal micropulsations of these subtle energetic fields.

The Chinese use both a solar and a lunar calendar. The Heavenly cycle of the moon has 12 lunar month divisions, which correspond to man's 12 internal organs and channels: Lungs, Large Intestine, Stomach, Spleen, Heart, Small Intestine, Bladder, Kidneys, Pericardium, Triple Burners, Gall Bladder and Liver. The Heavenly cycle of the sun has 12 periods of the day, which correspond to man's 12 sections of the body. These 12 internal cycles are sometimes called the 12 Blood / Heat Cycles because they affect the Qi, Blood and temperature within the Twelve Skin Zones (see Chapter 7).

The Earth's rotation and the rhythm of the five seasons (the usual four plus late summer) influence the body's internal organs and channels, affecting their energetic activity. In each of the five seasons, a specific pair of internal organs reaches an energetic peak.

1. In the summer, the Heart and Small Intestine are at their energetic peak.
2. In the late summer, the Spleen and Stomach reach their energetic peak.
3. In the autumn, the Lungs and Large Intestines reach their energetic peak.
4. In the winter, the Kidneys and Bladder reach their energetic peak.
5. In the spring, the Liver and Gall Bladder reach their energetic peak.

THE TWELVE PI HEXAGRAMS

The Twelve Pi Hexagrams symbolize the seasonal changes, which cause the waxing and waning of Yin and Yang energy. The trigrams and hexagrams are used to illustrate the movement of energy in Man (see Chapter 5) as well as Heaven. The Twelve Pi Hexagrams were also used to study and comprehend the interactive energetic fields of man and nature that govern growth and development. The interactive energetic fields engender the creation of energy channels and influence the circulation and transformations of Qi, which in turn, create and maintain the body's internal organs. The ancients believed that the human physique reflects the structure of the universe, and that prenatal Heaven and Earth energy fuse with postnatal Heaven and Earth energy at birth (see Chapter 2). The trigrams reflect the twelve hours of the day, the daily fluctuations of Yin and Yang energy, and the Qi of the Five Elements (Figure 11.3).

The Twelve Pi Hexagrams represent "the laws of hardness and softness," domination and yielding of Yin and Yang, the relationship between the seasons, time of day, major organs, channels, and the transformation and circulation of Qi.

THE YANG YAO CYCLES

When studying the Twelve Pi Hexagrams, it is important to examine the first six (from Fu — 11 p.m. to Qian — 11 a.m.), that represent the gradual increasing of the energetic potential of the Yang Yao (see Chapter 5) and the gradual decreasing of the Yin Qi. The Yang Qi rises and expands during this time period; it is the best time for training techniques that emit external Qi and for treat-


Yin Waxing & Yang Waning
9am–11am
Qian
Spleen
7am–9am
Guai
Stomach
11am–1pm
Gou
Heart
Si
May
Chen
Wu
Dazhuang
5am–7am
Dun
1pm–3pm
L.Intestine
Apr.
⑤
⑥
⑦
June
S.Intestine
Mao
Mar.
④
⑧
July
Wei
3am–5am
Lungs
Yin
Feb.
③
⑨
Aug.
Shen
Bladder
3pm–5pm
Tai
Pi
Jan.
②
⑩
Sept.
Chou
You
①
⑫
⑪
Liver
Dec.
Nov.
Oct.
Kidneys
1am–3am
Zi
Xu
5pm–7pm
Hai
Lin
Guan
G.Bladder
Triple Burners
Pericardium
Fu
Kun
Bo
11pm–1am
9pm–11pm
7pm–9pm
Yang Waxing & Yin Waning
Yang Line
Yin Line
6
Yang
Periods
Fu
①
Lin
②
Tai
③
Dazhuang
④
Guai
⑤
Qian
⑥
Full Yang
6
Yin
Periods
Gou
⑦
Dun
⑧
Pi
⑨
Guan
⑩
Bo
⑪
Kun
⑫
Whole Yin

Figure 11.3. The circular figure depicts the Heavenly cycle of the sun and the Twelve Pi Hexagrams. Solid lines in the trigrams and hexagrams represent Yang, and broken lines represent Yin. The hexagrams on the left depict the Yang Yao Cycle (from Fu to Qian), with the gradual increase in Yang and decrease in Yin, so that the last hexagram, Qian, is full Yang. The hexagrams on the right depict the Yin Yao Cycle (from Guo to Kun), with the gradual increase in Yin and decrease of Yang, so that the last hexagram, Kun, is full Yin.

ing patients who suffer from insufficiency of Yang Qi. This time period is called the "time of the living breath," and represents the beginning of energetic harvesting. When training in the morning time, the practitioner should progress from still, relaxed, quiescent Qigong meditations to active forms of dynamic Qigong movement.

THE YIN YAO CYCLES

The last six hexagrams (from Gou — 11 a.m. to Kun — 11 p.m.) indicate a gradual increasing of the energetic potential of the Yin Yao and the gradual decreasing of the Yang Qi. This time period is called the "time of the dead breath," and represents the beginning of energetic planting. The Yin Qi increases and expands in this time period; it is the best time for patients suffering from an insufficiency of Yin Qi to train, nurture, and restore the Kidneys' Yin Essence, which in turn will facilitate the preservation of Yang Qi. When training in the afternoon, the practitioner should progress from active forms of dynamic Qigong movement to gradually slower, relaxed, quiescent Qigong meditations.

When prescribing Medical Qigong for patients, the time for practice should be selected in accordance with the philosophy of Yin and Yang theory, the Five Elemental theory, the circadian rhythms of Qi and Blood circulation, as well as the severity of the illness.

USING THE YANG AND YIN YAO CYCLES

Each of the broken lines represents a Yin Yao and can be used to symbolize an inhalation, while a straight line represents a Yang Yao and symbolizes an exhalation. A hexagram consisting of three bottom Yang Yaos and three top Yin Yaos, for example, represents a balanced respirational pattern. When the Qigong doctor writes out a prescription for the patient, the doctor can adjust the patient's respiration in accordance with the Yao hexagrams, taking into consideration each Yao line as representing an inhalation or exhalation. The basic theory of Yin and Yang Yao cycles is also used to determine the time and direction for Qigong practice, as well as the methods of respiration and mind concentration required to establish proper Yin and Yang balance.



Figure 11.4. The Four Principle Time Periods

When practicing Medical Qigong at the hour of the Fu Hexagram, for example, the Yao indicates there is more Yin than Yang, so the practitioner should regulate his or her body with the intent to nourish the Yang through longer inhalation (Yin) and shorter exhalation (Yang).

At the stage of the Gou Hexagram, the Yao indicates there is more Yang and less Yin so the Qigong practitioner should perform regulation through shorter inhalations (Yin) and longer exhalations (Yang).

THE FOUR PRINCIPAL TIME PERIODS OF QIGONG PRACTICE

Practicing Medical Qigong during the "four principal time periods" (Zi, Mao, Wu, and You) facilitates the vigorous growth of internal energy in harmony with the changes of energy in nature (see Figure 11.4). To nourish energy, practice during the sunrise and / or sunset (Mao and You) periods. To stabilize energy, practice during the periods of midnight and / or high noon (Zi and Wu).

Due to the differences between individual constitutions (Excess or Deficient Yang or Yin), the selection of the proper time for practice and the number of Yin or Yang respirations varies between patients. The following is a brief discussion and explanation of the four principal time periods.

1. Zi Time Period corresponds to the Fu Hexagram, and has one Yang and five Yin lines or Yaos. The Zi time period is at midnight (11 p.m. – 1 a.m.). It is related to the beginning of the Yang cycle and is perfect for gathering energy to store the Yuan Qi (Prenatal Qi). The Yuan Qi is the root of life, formed through the divine combination of the primordial Yin and Yang; it is stored primarily in the Kidneys' Water energy. The Zi period of time corresponds to the Fu Hexagram. During this time the Earth energy and the Kidney's Yang Qi are in full harmony, continuously combining and accumulating energy. Practice during this period of time results in twice the effect with half the effort.
2. Mao Time Period corresponds to the Dazhuang Hexagram, and has four Yang and two Yin lines or Yaos. The Mao time period is at sunrise (5 a.m. – 7 a.m.). As the sun rises, warming the air, and natural Yang progresses. At this time of the day, the Yang Qi of the body is in full bloom. Practice during this period of time aids the vigorous growth of Yang.
3. Wu Time Period corresponds to the Gou Hexagram, and has one Yin and five Yang lines or Yaos. The Wu time period is at high noon (11 a.m. – 1 p.m.), and is regarded as the Heart's Fire. At high noon, the Heart Channel (considered the Supreme Yang) will naturally manifest the energetic peak of Yang energy. Because the first line is a Yin Yao, however, the Yang energy Yaos tend to wane rather than grow. Therefore, practicing during this period helps the growth of Yin energy and suppresses the hyperactivity of Yang energy.
4. You Time Period corresponds to the Guan Hexagram, and has four Yin and two Yang lines or Yaos. The You time period is at sunset (5 p.m. – 7 p.m.). At this time, the energy of the environment turns from clear and radiant to dark. Qigong practice at this time nurtures the increase of the primordial Yin energy and the conservation and nourishment of Yang energy.

THE FOUR SEASONAL PEAK TRANSITIONS

Another theory maintained by Qigong doctors is that the sun's light during the day represents Yang, and the energy from the moon's light at night represents Yin. The observation that light coincides with heat and that darkness coincides with cool, led to the division of the year into four seasonal peak transitions (which also correspond to the four principal time periods of the day) (see Figure 11.5).

At the time of the equinoxes and solstices, the sun passes through transitional regions: The Palace of Eternal Frost in the North is entered in the winter; The Golden Gate in the East is entered in the spring; The Palace of Universal Yang in the South is entered in the summer; and The Gate of the Moon in the West is entered in the autumn. The four seasonal peak transitions in the northern hemisphere are described as follows.

1. The Palace of Eternal Frost at the Winter Solstice (December 22–25) indicates the time period when the sun is furthest south from the equator. This is a time of maximum Yin or darkness in the northern hemisphere, with the shortest days and longest time of cold and darkness. This energetic transition corresponds to "midnight" within the four principal time periods.
2. The Golden Gate at the Spring Equinox (March 21) indicates the time period when the sun's center crosses the Heavenly equator, creating an energetic balance between the days and nights. Although light and darkness and Yin and Yang energies are in balance, this seasonal time period is a transitional harmony, as Yang energy is growing. The weather is also moderate. This energetic transition corresponds to the "sunrise" within the four principal time periods.
3. The Palace of Universal Yang at the Summer Solstice (June 21–23) indicates the time period when the sun is furthest north from the equator, a time of maximum Yang or brightness, with the longest days and times of light and warmth. This energetic transition corresponds to "noon" within the four principal time periods.


5th Moon
4th Moon
6th Moon
3rd Moon
7th Moon
Summer Solstice
Spring Equinox
Autumn Equinox
Winter Solstice
③
②
④
①
2nd Moon
8th Moon
1st Moon
9th Moon
12th Moon
10th Moon
11th Moon

Figure 11.5. Four Season Peak Transitions

4. The Gate of the Moon at the Autumn Equinox (September 22) indicates the time period when the sun's center crosses the Heavenly equator, creating an energetic balance between the days and nights. Although light and darkness and Yin and Yang energies are in balance, this seasonal time period is in transitional harmony, as Yin energy is growing. The weather is also moderate. This energetic transition corresponds to the "sunset" within the four principal time periods.

The energy of these four principal time periods enters the practitioner's Taiji Pole during meditation and regulates the "auspicious powers" located within the five regions of space inside and outside of the doctor's body:

- Front—energy of the Heart
- Back—energy of the Kidneys
- Right—energy of the Lungs
- Left—energy of the Liver
- Center—energy of the Spleen

THE SIX PRINCIPAL SEASONS OF TRANSITION

In Traditional Chinese Medicine, the year is divided into six primary periods of seasonal transitions (wind, heat, damp, fire, dry, and cold). Each season represents the ruling Qi, or expected weather, dominant in that particular season (Figure 11.6).

These six periods delineate the differences between and transitional transformations of Heaven energies (through the Ten Heavenly Stems) and Earthly energies (through the Twelve Earthly Branches). In terms of weather, the first half of the year is governed by the Qi of Heaven, while the second half of the year is administered by the Qi of Earth. The Ten Heavenly Stems are the ten energies of Heaven that rule the changes of the Five Elemental Seasonal Transitions, and are represented in the human body as the Yin and Yang aspect of the Five Elements (represented as the ten major internal organs). The Twelve Earthly Branches are the twelve energies of the Earth that determine the six Qi factors of the seasonal transitions (represented in the body as the Twelve Primary Channels). In accordance with the Creative Cycle of the Five Elemental Seasonal Transitions: summer creates late summer, late summer engenders autumn, autumn gives rise to winter, and winter gives birth to spring.

THE DAILY QI, BLOOD, AND HEAT CYCLE

These four principal time periods and seasonal peak transitions affect the body's Blood, Heat, and Qi Cycles. The daily cycle of Heat, Blood, and Qi flow along the body's Twelve Primary Channels, organs, and tissues, according to the two hour Yin and Yang time table are:

- Gall Bladder (GB) - 11 p.m. to 1 a.m. - (Yang)
- Liver (Lv) - 1 a.m. to 3 a.m. - (Yin)
- Lungs (Lu) - 3 a.m. to 5 a.m. - (Yin)
- Large Intestine (LI) - 5 a.m. to 7 a.m. - (Yang)
- Stomach (St)- 7 a.m. to 9 a.m. - (Yang)
- Spleen (Sp) - 9 a.m. to 11 a.m. - (Yin)
- Heart (Ht) - 11 a.m. to 1 p.m. - (Yin)
- Small Intestine (SI) - 1 p.m. to 3 p.m. - (Yang)

Season	Date
1. Spring Begins	Feb. 5
Rainwater	Feb. 20
Insects	March 7
Spring Equinox	March 22
2. Clear and Bright	April 6
Grain Rains	April 21
Summer Begins	May 6
Grain Filling	June 7
3. Grain Full	June 22
Summer Solstice	June 22
Slight Heat	July 8
Great Heat	July 24
4. Autumn Begins	Aug. 8
Limit of heat	Aug. 24
White Dew	Sept. 8
Autumn Equinox	Sept. 24
5. Cold Dew	Oct. 9
Frost Descent	Oct. 24
Winter Begins	Nov. 8
Slight Snow	Nov. 23
6. Great Snow	Dec. 7
Winter Solstice	Dec. 22
Slight Cold	Jan. 6
Great Cold	Jan. 21

Figure 11.6. Six Principal Seasons of Heaven and Earth Energy Transition (1-6), and the Twenty Four Diagram Chart

- Bladder (Bl) - 3 p.m. to 5 p.m. - (Yang)
- Kidneys (Kd)- 5 p.m. to 7 p.m. - (Yin)
- Triple Burners (TB) - 7 p.m. to 9 p.m. - (Yin)
- Pericardium (Pc) 9 p.m. to 11 p.m. - (Yang)

The body's active high and low heat, Blood, and Qi time periods, reflect its relationship with the Twelve Primary Channels. For instance, every morning during the time period of 3–5 a.m., the strongest energy streams down along the Lung Channels, making the Lungs quickly responsive to treatment.

GATHERING THE SUN'S ESSENCE MEDITATION

The ancient Qigong masters used this meditation to absorb the essence of the sun. By gathering pure Yang energy to tonify the body's Deficiencies, as well as to consolidate the Zheng Qi (Gathering energy), they were able to eliminate pathogenic factors and prevent premature aging. This particular exercise is considered part of the foundational base from which the ancient Qigong doctors replenished any depleted life-force energy.

The gathering the Sun's Essence Meditation must only be practised on a clear day, when the sun is not obstructed. Avoid practising this meditation in times of fog, smog, thick clouds, and solar eclipses, as cultivation during these times will cause the unnatural cultivation of Turbid Qi.

1. While outside on a bright sunny day, face the sun, and assume a Wuji standing posture, hands by your sides, with the feet slightly wider then shoulder-width apart; stand in a relaxed and tranquil state, breath evenly and naturally, and rid your mind of any stray thoughts (Figure 11.7).
2. If the sun is rising above the horizon, slightly close your eyes; you should still be able to see soft, gentle, reddish sunlight. If the sun has already risen, close your eyes and use your inner vision to visualize the sun.
3. Inhale through the nose and imagine filling your mouth with energy from the sunlight's essence. Still facing the sun, with your eyes half open, "infuse," or absorb into the eyes, the energy from the horizon. Blend the energy



Figure 11.7. Gathering the Sun's Essence Meditation. Step one, stand and face the sun.



Figure 11.8. Step two, imagine embracing the sun.



Figure 11.9. Step three, imagine embracing the sun and gently placing it in front of your Lower Dantian.

absorbed from your eyes into your Upper Dantian. Close your eyes and imagine blending the sun's golden light energy with the Qi you inhaled through your nose. Hold your breath and focus the mind, mixing both energies; swallow the energies slowly while exhaling, and send the energy down to the Lower Dantian. Repeat this process for several minutes.

4. Stretch your hands towards the sun and imagine embracing it (Figure 11.8). Point your index fingers toward the center of the sun, and imagine pulling the sun down in front of your Lower Dantian. Keep it positioned there for several minutes (Figure 11.9).
5. Imagine the sun gently rolling and turning itself in front of your lower abdomen (Figure 11.10–11). Keep your elbows at your sides and gently shift, or sway from side to side, imagine that it is the sun's movement that causes both your arms and body to move. Using this image keeps the sun in an energetic power position.
6. Place both hands around the sun as if embracing it (Figure 11.12). Next, imagine the sun slowly moving into your navel. Allow both hands to follow the sun into the navel, ending with your left palm on top of your right palm (opposite for women) (Figure 11.13). With one deep breath inhale and absorb the sun's energy into the Lower Dantian while imagining the sun (beneath the navel) transforming into a luminous ball of golden energy. With each inhalation, this golden ball shines brightly; with each exhalation, the sun's rays extend, spreading throughout the entire body.
7. To end, relax the mind and imagine Heavenly Qi melting down the body, pouring through the front, back and center of the body like warm oil, into the Earth. This ending exercise (sometimes called Pulling Down The Heavens), allows the Qi to sink into the Lower Dantian, and the body, mind, and spirit to come into a state of peaceful rest and tranquillity.



Figure 11.10. Step four, imagine the sun gently rolling and turning itself in front of the Lower Dantian.



Figure 11.11. The energy of the sun moves the entire body rather than the arms.



Figure 11.12. Step five, embrace the sun and absorb it into the navel and then into the Lower Dantian.



Figure 11.13. Each breath transforms the sun's energy into luminous golden Qi.

CYCLES OF THE MOON

The ancient Qigong masters believed that the sun has a Yang nature, emitting enormous amounts of hot, thermal energy, whereas the moon has a Yin nature and emits a much cooler type of energy, by reflecting the light of the sun. The energy of the moon is used to replenish the body's Yin Qi, and follows a comprehensive cycle every 28 days (Figure 11.14). Following the cycle of the moon, the energy of the body completes a full rotation, flowing along the Governing Vessel to the top of the head, and down the Conception Vessel to the base of the perineum. When the moon is full, the body's Blood and Qi reach a crest, filling the Baihui point on the top of the head. At the new moon, the body's Blood and Qi gather at the Huiyin point, in the perineum.

Since the lunar cycle at its extreme (full moon and new moon) activates the top and bottom points of the Taiji Pole, these are said to be the most productive times to perform Taiji Pole Qi practice.

The appearance of the moon during the first half of the lunar month symbolizes the waxing of Yang and waning of Yin Qi. As Yang grows and Yin declines, regulation of breathing at this period of time should be aimed at absorption of the Moon's Essence. The second half of the lunar month symbolizes the waxing of Yin and waning of Yang Qi. As Yin grows and Yang declines, regulation of breathing at this period of time should be aimed at replenishing Yang to help the Yin nourish the Yin Jing-Essence (Figure 11.15-20).

As the moon increases the amount of light it reflects, the body's Qi and Blood become more nourished; when the moon is full, the Qi and Blood become substantial. As the moon begins to decrease the amount of light it reflects, the muscles start to lose their energetic substance. This decrease in energy causes the body's Eight Extraordinary Vessels and Twelve Primary Channels to empty themselves to support the muscles that are slowly becoming Deficient. Qi and Blood are influenced by the gravitational pull of the sun and moon, just as the tides of the sea are influenced. Therefore the ancient Qigong masters described the energetic tonifying and purging principles of Qigong regulation in these specific terms: when treating a patient, perform no tonifying when the moon is full, or when the Blood and Qi are sufficient. Perform no purging when the moon is dark, or when the Blood and Qi are Deficient. This observation explains the effect of the "full-moon phenomenon" on patients who are hypersensitive to energy and become restless when the moon's Qi is "full Yang in Yin."

The waxing and waning of the sun and moon affect the adjustment time for Medical Qigong practice and the methods of breathing regulation. In order to facilitate the intake of Heavenly Es-



Figure 11.14. The waxing and waning cycles of the moon correspond to the moon's orbit around the Earth.



Figure 11.15. From the 1st to the 5th night of a lunar month, more Yang absorption and Yin nourishment can be obtained by performing breathing regulations while facing the west. The crescent surface of the Moon is reflecting less sunlight.



Figure 11.16. From the 6th to the 10th night of a lunar month, more Yang absorption and Yin nourishment can be obtained by performing breathing regulations while facing the south. The surface of the moon is turning from a crescent to half-full Yang, and its surface is reflecting more sunlight.



Figure 11.17. From the 11th to the 15th night of a lunar month, equal amounts of Yang absorption and Yin nourishment can be obtained by performing breathing regulations while facing the direction of the moon, as both Yang and Yin energies are plentiful at this time. At this point, the moon is full with its surface reflecting the most sunlight (called "Full Yang in Yin").



Figure 11.18. From the 16th to the 20th night of a lunar month, the Yin grows and Yang declines. Regulation of breathing at this period of time should be aimed at replenishing Yang to help the Yin nourish the Yin Essence, while facing the west. At this time, the crescent surface of the moon is reflecting less sunlight. The reflected sunlight on the moon's surface decreases as Yang wanes and Yin waxes.



Figure 11.19. From the 21st to the 25th night of a lunar month, Yin continues to grow and Yang declines. Regulation of breathing at this period of time should be aimed at replenishing Yang to help the Yin nourish the Yin Essence, while facing the south. At this time, the crescent surface of the moon's shape is turning to half-full Yin, and its surface is reflecting less sunlight. The reflected sunlight on the moon's surface continues to decrease as Yang wanes and Yin waxes.



Figure 11.20. From the 26th to the 30th night of a lunar month, no absorption of Yang is possible when the moon appears in the east at nightfall and its surface is dark, leading to the period of "Pure Yin." Breath regulation should be performed facing east.

sence to nourish the body, the ancient Qigong masters used a system wherein each month is divided into 6 separate sections (a total of 5 days was assigned to each section).

PRENATAL EIGHT TRIGRAMS AND THE MOON

The symbols on the Prenatal Eight Trigrams represent the appearance of the moon, while the Ten Heavenly Stems represent the positions of the moon. Each trigram embraces one or two of the Ten Heavenly Stems. The following chart of Prenatal Trigrams, Ten Heavenly Stems, moon and tide regulation, as well as the principles of purgation and tonification of Qi and Blood is a reference for Qigong doctors for clinical treatments (Figure 11.21).

In this chart, the Yang energy of the Earth gradually increases from the 11th to the 15th. Influenced by this action, the spring tide occurs on the 15th when the moon is full, inducing both the Qi and Blood to become extremely active. This is a good time for Qigong patients who suffer from energy Deficiencies to replenish their Qi. However, if the patient's energy is abundant, he or she should not try to replenish at this time, or an Excess condition of Qi will occur.

CHOOSING THE PROPER DIRECTION FOR TRAINING QI

Since ancient times, Qigong doctors have placed great emphasis on facing certain directions when cultivating energy. Observing that energy training and practicing should be adapted to nature, each routine is selected according to the season, month, and time of day, as well as the physical conditions of the practitioner. The four directions, as well as the sun (solar cycle), moon (lunar cycle), and stars (four sets of seven constellations, each one grouped in the N, S, E, or W), have a direct influence on the human body.

One example of directional training is in setting up treatment schedules according to the energy emitted from the Heavens. It is generally advised when conducting energetic regulations that:

- Patients with Yang Deficiencies should face east or south, to develop Yang Qi;
- Patients with Yin Deficiencies should face west or north, to help develop the Yin Qi;
- Patients with a Kidney Deficiency should face the north;
- Patients with a Liver Deficiency should face east;
- Patients with a Heart Deficiency should face south;
- Patients with a Lung Deficiency should face west;
- Patients with a Spleen Deficiency should focus their attention on the center, i.e., the Earth.

Generally, when first beginning Qigong exercises and meditations, practitioners are taught to face the south or southeast. When practicing specific cultivation exercises, however (such as Gathering the Sun's Essence), the practitioners are taught to face the direction of the sun. In the evening time, unless practicing specific cultivation exercises (such as Gathering the Moon's Cream), it is best to have the patient face the corresponding direction for the Deficient organ. These cultivation methods train the Yang energy to fuse with the Zhen Qi (True Qi), as well as with the Heavenly Qi and Environmental Qi. The timing and methods of training are based on the increase and decrease of Yin and Yang energy.

It is important to note that although these training methods are effective, the most experienced Qigong doctors often choose the place and direction according to their own intuition. To select the appropriate direction, the doctors start by facing south (sitting or standing). As they begin to feel the body filling with Qi, they may feel that they are being pulled towards a specific direction, and that they cannot stand or sit comfortably without facing that direction. The doctors feel more rooted and stable by following their intuition. Through understanding the proper directions, concentration, breath regulation, and assuming the appropriate postures, Qigong doctors are able to help regulate and increase their patients' energetic activities, while avoiding many Qi deviations (see Chapter 18).

Heavenly Stems	Date	Appearance of the Moon	Prenatal Trigrams	Position of Moon you face ○	Cause & Reason	Tide	Qi & Blood	Regulation
Geng ䷡	1st	Waxing Crescent	Zhen ☳	West N Ⓦ—E S	Moon between Sun & Earth	Spring Tide Max. Amplitude when Sun/Moon Pull Together	Turning Excessive	No Tonifying
Ding ䷫	8th	First Quarter	Dui ☱	South N W—E Ⓢ	Moon is 90° East of Sun	Neap Tide Min. Amplitude Sun/Moon work against each other	Deficient	No Purging
Jia ䷗	15th	Full	Qian ☰	East N W—Ⓔ S	Moon opposite Sun, Earth in between to East	Spring Tide Max. Amplitude Sun/Moon pull together	Excessive	No Tonifying
Xin ䷊	16th	Last Quarter	Xun ☴	West N Ⓦ—E S	Moon opposite Sun, Earth in between to West	Medium Tide	Turning Deficient	No Purging
Bing ䷁	23rd	Waning Crescent	Gen ☶	South N W—E Ⓢ	Moon is 90° West of Sun	Neap Tide Min. Amplitude Sun/Moon work against each other	Deficient	No Purging
Yi ䷒	30th	New	Kun ☷	East N W—Ⓔ S	Moon between Sun & Earth	Medium Tide	Deficient	No Purging

Figure 11.21. Medical Qigong Doctor's Chart for Clinical Reference

GATHERING MOON'S CREAM QIGONG MEDITATION

Qigong doctors use this particular exercise in conjunction with the Gathering the Sun's Essence meditation for replenishing depleted energy. The vital essence of moon is called the Cream or "cool light" and is used to nourish the Kidneys and strengthen the Jing, Marrow, and brain, while contributing to longevity. It is practiced only nine days a month, three days before, during, and after the full moon, which are the brightest nights of the month. It is prohibited during new moon transitions because there is too little vital essence of the moon to gather.

Gathering the Moon Cream meditation must only be practiced on clear nights, when the moon is not obstructed. Avoid practicing this meditation in times of fog, smog, thick clouds, and lunar eclipses, as cultivation during these times will cause the unnatural cultivation of Turbid Qi

1. Stand outside in the fresh air, while facing the moon. Stand in a relaxed and tranquil state, breath evenly, and rid your mind of any stray thoughts (Figure 11.22).
2. Lower your eyelids until you only faintly see the moonlight. Inhale through the nose and imagine softly "sipping" one mouthful of the moon cream. At the same time, with your eyes half open, visualize "inhaling" the energy of the moon cream with your eyes into your Upper Dantian. Close your eyes and imagine mixing the moon cream with the energy you inhaled through your nose. Slightly hold your breath and concentrate on feeling the moon cream's silvery energetic essence. Swallow this essence slowly, sending it down to the Lower Dantian.
3. Stretch your hands towards the moon (Figure 11.23). Imagine embracing the moon and pulling it out of the sky, placing it just above your Upper Dantian, at your Baihui point (on top of your head). Hold this image for several minutes (Figure 11.24).
4. Next, imagine a second moon forming out of the first moon, and bring it downward with both hands until level with, and in front of, the Middle Dantian (Shanzhong CV-17 point) at the center of the chest. Hold this image for several minutes (Figure 11.25).
5. Finally, imagine a third moon forming out of the second moon, and bring it down to the level of the Lower Dantian, suspended in front of the lower abdomen. Hold this image for several minutes (Figure 11.26).
6. Continue to imagine all three moons suspended (two in front, and one above your body) and inhale, raising both of your arms over your head. Imagine pressing the first moon into your head through the Baihui point, filling the Upper Dantian with the moon cream's silvery white light. As both hands press the moon into the head, allow the left hand to remain on top of the right hand (opposite for women). As you exhale, visualize the light of the moon filling the entire cavity of the Upper Dantian (Figure 11.27).
7. Next, bring both hands to the front of your body. Inhale and press the second moon into your chest through the Middle Dantian, imagining the moon cream's silvery white light filling the chest. As you exhale, visualize the light of the moon filling the entire cavity of the Middle Dantian (Figure 11.28).
8. Finally, bring both hands in front of your lower abdomen. Inhale and press the third moon into your Lower Dantian, imagining the moon's silvery white light filling the abdomen. As you exhale, visualize the light of the moon filling the entire cavity of the Lower Dantian (Figure 11.29).
9. Allow both hands to rest by your sides then slowly raise your left hand (opposite for women) and tap the top of your Baihui point softly nine times. As you tap, imagine that all three moons fuse into a brilliant white-light energy throughout your Taiji Pole, connecting all three Dantians together (Figure 11.30).
10. Relax and perform Pulling Down The Heavens, letting your body, mind and spirit sink into tranquility.



Figure 11.22. Stand facing the moon.



Figure 11.23. Stretch your hands to embrace the moon.



Figure 11.24. Suspend the moon above your Upper Dantian.



Figure 11.25. Suspend a second moon in front of your Middle Dantian.



Figure 11.26. Suspend a third moon in front of your Lower Dantian.



Figure 11.27. Absorb the first moon into your Upper Dantian.



Figure 11.28. Absorb the second moon into your Middle Dantian.



Figure 11.29. Absorb the third moon into your Lower Dantian.



Figure 11.30. Tap lightly until all three moons flow into your Taiji Pole.

CYCLES OF THE STARS

The most influential Heavenly Treasures, other than the sun and moon, are the stars composed of the Big Dipper, Polaris, and the five planets, existing within the twenty-eight constellations.

The North Star is believed to be the unchanging area of Heaven, from which the Heavenly order began (often called the Axis of the Vault of Heaven), and so it was named The Divine Center of the Earth and Sun Cycles. It is also believed that from this star the entire universe expands outward. By placing the North Star in the center of a circle of the Heavens, the circle can be divided into four directions, each containing seven constellations that have a different color energy and sound frequency.

In ancient China, the seven constellations were divided into four sections or directions (north, south, east, and west). In the region of the north was believed to exist the energy of the Tortoise-Snake, in the south was the Red Phoenix, in the east was the Green Dragon, and in the west was the White Tiger. Each of these regions was further divided into twenty-eight constellations or posts (xiu).

According to traditional Chinese belief, the moon travels twenty-eight days from west to east, resting at each post as it circles the Earth. In other words, the twenty-eight days are further divided into twenty-eight regions which are courier stations or travelling houses for the moon.

It was further believed that the Pole Star axis stemming from the North Star traveled downward from the center of Heaven, connecting with the Earth's center core (through the north and south poles). The north pole was regarded as the peak (or Baihui) of the Earth, and was believed to be comprised of seven stars (making it a fifth constellation). The energies of each of the four animals and their seven constellations moved around the Earth's central Pole creating the Five Elemental changes in weather (see Chapter 11). If the weather changes progressed in their expected order, they were considered normal; however, if the weather transition occurred either earlier or later than expected, the result was considered an environmental Evil Qi.

Therefore, the ancient Chinese believed that one could predict the changes of weather by studying the interrelationships between the Five Elements and the cycles of the sun, moon, Polaris, the Five Planets, and the twenty-eight constellations.

THE ENERGY OF THE BIG DIPPER

As the Earth orbits the sun, the angle at which the Big Dipper can be viewed changes on a daily, monthly, and yearly basis (Figure 11.31). These changing angles correspond to the different cycles of the moon as they are arranged in the Twelve Earthly Branches and repeat themselves after completing an orbit (360° rotation of twelve moon cycles). These twelve lunar cycles determine the twelve seasonal periods (Figure 11.32). The beginning part of each month marks the beginning of the seasonal periods of the Twelve Earthly Branches and the beginning of the energy cycle of that month. When the Big Dipper points in the direction of the "lunar month," facing the direction of the Big Dipper will invigorate the practitioner's energy. The Big Dipper is related to the energetic transformations of germinating, beginning, and growing.

There are three kinds of practice centered around the Big Dipper:

1. The first consists of invoking its power for protection;
2. The second consists of ascending into it and pacing its rotation;
3. The third involves gathering the star's essence or star cream into the body.

In ancient times, the Big Dipper was considered the bridge between the energies of the sun and the moon, and the source of "10,000 things." The sun and moon are considered a bipolar energy field, whereas the Big Dipper is considered unipolar.

The sun corresponds to the Heart and Fire energy, which is related to the front area of the body. The moon corresponds to the Kidneys and Water energy, which is related to the back area of the body. The Big Dipper corresponds to the Spleen, which is related to the Taiji Pole.


Winter
North
Spring
East
North
Star
Fall
West
Summer
South

Figure 11.31. The handle of the Big Dipper can be used to determine the season: (1) in winter, the handle points to the northern horizon, (2) in spring, the handle points to the eastern horizon, (3) in summer, the handle points to the southern horizon, and (4) in fall, the handle points to the western horizon. The North Star is positioned in the center of the diagram.


5th Lunar Month
June
Wu
South
Heart
4th Lunar Month
May
Si
Spleen
6th Lunar Month
July
Wei
Small Intestine
3rd Lunar Month
April
Chen
Stomach
7th Lunar Month
August
Shen
Bladder
North
Star
March
2nd Lunar Month
Mao
East
Large Intestine
West
Kidneys
You
September
8th Lunar Month
Lungs
Vin
February
1st Lunar Month
Chinese New Year
Pericardium
Xu
October
9th Lunar Month
Triple Burners
Liver
Chou
January
12th Lunar Month
Gall Bladder
North
Zi
December
11th Lunar Month
Hai
November
10th Lunar Month

Figure 11.32. The beginning of the seasonal periods of the Twelve Earthly Branches and the twelve moon cycles is determined by the angle of the Big Dipper.



Figure 11.33. The Big Dipper is considered a reservoir of heavenly energy, collecting Qi from all of the other stars and constellations as it moves through the sky.

THE STARS OF THE BIG DIPPER

The Big Dipper represents the foundational base for the Gate of Access in Chinese mysticism, which is considered the spiritual passageway between life and death. Through this gate the individual may obtain knowledge and insight concerning past, present and future events.

The energy from the stars of the Big Dipper is used to balance the body's Five Agents (stored within the body's Five Yin Organs) and can be arranged internally to enhance internal perception of time and space (Figure 11.33).

One example used in ancient China for invoking the powerful protection of the Big Dipper energy is for the Qigong doctor to cover himself - or herself - with the stars of the Big Dipper by visualizing the stars descending and arranging themselves in a specific order around the doctor's body The stars can be arranged in four ways:

- above the doctor's head,
- in front of or behind the doctor's body,
- placed within the doctor's Three Dantians, or
- placed with the bowl of the Dipper in the Lower Dantian and the handle along the spine.

The doctor imagines placing the stars of the Big Dipper into the center of his or her body. The star's energetic function is to govern the front, back, right, and left of the body, thus regulating the doctor's Yin and Yang energy. The star's energetic function can also be used for absorbing energy from the four seasons into the doctor's body.

The stars of the Big Dipper are also considered responsible for opening the Seven Orifices of the embryo's body and for giving the embryo life. These stars also correspond to the Nine Chambers in the Three Dantians. Usually, meditations dealing with gathering energy from the sun and moon are followed by meditations involving the Big Dipper to further stimulate and energize the body's energetic fields.

THE FIRST FIVE PLANETS

The five planets (Saturn, Jupiter, Mars, Venus, and Mercury) are responsible for the internal Yin organ energy formation within the body during fetal development. These planets are the focus of several Qigong meditations because of their connection to color resonations within each internal Yin organ.

1. Of the first five planets in our solar system, Saturn is coupled with Earth and is considered the central force of planetary energy. It takes twenty-eight years for Saturn to make a complete revolution around the sun. Each year, when Saturn enters into another constellation, it is called "Saturn holding authority over that constellation for one year."

   Saturn's position in the sky relates to the Taiji Pole. The planet Saturn represents the Stomach and Spleen (Earth Element) and emits a golden-yellow light energy.
2. Jupiter represents the easterly direction and the Liver (Wood Element), it emits a green light energy; its position relates to the left side of the Taiji Pole.
3. Mars represents the southerly direction and the Heart (Fire Element). It emits a red light energy and relates to the front side of the Taiji Pole.
4. Venus represents the westerly direction and the Lungs (Metal Element). It emits a white light energy and relates to the right side of the Taiji Pole.
5. Mercury represents the northerly direction and the Kidneys (Water Element). It emits a dark blue/indigo light energy and relates to the back side of the Taiji Pole.

GATHERING ENERGY FROM THE FIVE PLANETS

To absorb energy from the five planets, start by quieting your mind while standing in a Wuji posture and facing the direction of the Big Dipper. Visualize yourself absorbing the energetic essence and color of each planet, one by one, into your body, filling each organ's entire Orb (the organs complete system, channels and tissues). Imagine filling the body with each planet's Heavenly energy from the top of your head, through the center Thrusting Channels.

Begin with the energy of Saturn, imagine it flowing into and filling your body through the Taiji Pole. Next, imagine the energy of Mars flowing into your front Center Thrusting Channel. Now imagine the energy of Mercury filling your body through the back Center Thrusting Channel, Venus's energy filling the body by descending into the right Center Thrusting Channel, and Jupiter's energy filling the body by flowing into the left Center Thrusting Channel. Gather the energy from their corresponding Orbs and lead the Qi downward into the Lower Dantian. After collecting and storing the Heavenly Qi, end the meditation with the Fire Cycle of the Microcosmic Orbit meditation.

THE TWENTY-EIGHT CONSTELLATIONS

Since the year 2000 B.C., the ancient Chinese Qigong Masters observed and used the movements and energy of the twenty-eight constellations, the sun and moon, and the first five planets with the Chinese zodiac, to forecast auspicious times for matters of state and war, and to predict weather and natural disasters. Each of these energetic systems has its own cyclic pattern as well as a direct and indirect influence on human life.

The Chinese practised gathering energy from the Heavenly stars, believing that the study of astrology, like alchemy, united the body's inner world with that of the outer. According to ancient divination practices, the celestial bodies exert forces and exhibit personalities that influence people and events on Earth. A person's character and destiny throughout life is based upon the positions of the planets and constellations at the exact time and place of birth. These influences can be determined by mapping the positions of the twenty-eight constellations in the sky at various times.

So important was this belief, that in ancient China, the Emperor was considered the high priest of the Heavens and frequently made sacrifices to the stars to maintain harmony with the universe. The four corners of the Emperor's palace represented the cardinal points in space (the equinoxes and solstices), and he and his family would move from one corner to another as the seasons changed.

GATHERING ENERGY FROM THE CONSTELLATIONS

At night time, when the moon is not suitable for absorbing Qi (new moon), the Qigong doctor can absorb the energy of the twenty-eight constellations into his or her body.

The energy of all five planets and twenty-eight constellations can be drawn into the body's internal organs and tissues through the five energetic Thrusting Channels which envelop and support the body's Taiji Pole. These Channels flow through the center of the doctor's body, connecting the top of the head to the perineum.

Externally, the twenty-eight day constellation cycle can be arranged externally on the body's Governing and Conception Vessels. The "ecliptic" path of the sun follows the Fire Cycle of the Microcosmic Orbit, which correlates to the individual's emotional/mental and physical health.

There are several meditations used in order to absorb the energy of the five planets and twenty-eight constellations into the doctor's body; one of which is known as The Heavenly Five Yin Organ Meditation.

HEAVENLY FIVE YIN ORGAN MEDITATION (TIAN WU ZANG)

This meditation is very popular in China. It focuses on fusing the energy from the five planets and the constellations into the body through the Five Thrusting Channels that surround the core center of the body's Taiji Pole. These Five Thrusting Channels should not to be confused with the TCM perspective of the Five Thrusting Vessels (as seen in Figure 11.34). Each of these Five Thrusting Channels relates to a specific organ energy and element (Figure 11.35).

When practicing this meditation and gathering the energy from the stars, it is important to first absorb the energy into the Five Thrusting Channels, then spiral the energy in a clockwise downward and counterclockwise upward direction through the body's Taiji Pole. This spiralling action allows the energy to balance itself and stabilizes the body's internal organs (Figure 11.36).

In order to perform the Heavenly Five Yin Organ Meditation and gather the Qi of the twenty-eight constellations, assume a Wuji posture, with your arms suspended by your sides. Face the direction of the North Star and Big Dipper (Figure 11.37). This exercise is performed for thirty-six breaths in each direction.



Figure 11.34. The Thrusting Vessels

1. To begin, imagine golden energy pouring out of the Big Dipper and flowing into the center of the Baihui area, at the top of your head. As you inhale, this golden energy fills the center core of your body, and flows into the extremities. As you exhale, this golden energy gathers into your Spleen.
2. Next, imagine drawing in a red energetic mist from the seven constellations in front of your body. This red mist flows into your body from the front side of the Baihui area, filling your entire body as you inhale. As you exhale, the energy coalesces into your Heart.
3. Now focus your attention on the back of your body. Inhale and imagine drawing in the dark blue energy from the seven constellations behind you into the back side of the Baihui area, filling your entire body as you inhale. This energy gathers into and fills the Kidneys as you exhale.
4. Next, focus on the right side of your body and imagine drawing in white energy from the


Spleen
Fire
Wood
Metal
Water
Top of Head
Spleen
Fire
Metal
Wood
Water

Figure 11.35. Each of the Center Thrusting Channels relates to a specific organ energy and element. Each channel has its own entry point that is positioned either on the top of the head, or on the base of the perineum.


Heart
Shen
Front
Liver
Hun
Left
Side
Spleen
Yi
Right
Side
Lungs
Po
Back
Kidneys
Zhi

Figure 11.36. The body's Yuan Spirit is stored within the body's Five Yin Organs. The placement of the Five Energetic Houses is maintained throughout many Medical Qigong meditations and is used to tonify, strengthen, extend, and project the body's Shen.


FIRE
The Southern 7 Constellations
The Red Phoenix — 64 Stars
WOOD
The Eastern 7 Constellations
The Green Dragon — 32 Stars
The North Star
METAL
The Western 7 Constellations
The White Tiger — 51 Stars
WATER
The Northern 7 Constellations
The Black Turtle — 35 Stars

Figure 11.37. The energy of the Twenty-Eight Constellation Stars is absorbed into the body through the same structural pattern as the placement of the Five Energetic Houses of the body's Shen.

seven constellations to your right into the right side of the Baihui area, filling your entire body as you inhale. This energy gathers and fills the Lungs as you exhale.

5. Finally, focus your attention on the left side of your body and imagine drawing in green energy from the seven constellations on your left into the left side of the Baihui area, filling your entire body as you inhale. This energy gathers and fills the Liver as you exhale.

EARTHLY BRANCHES, HEAVENLY STEMS, AND NINE PALACES

There are many relationships between the macrocosm and the microcosm of man, through the Twelve Earthly Branches, the Ten Heavenly Stems, and the Nine Palaces outlined in the Chinese Classics on Internal Medicine. The Twelve Earthly Branches are Earth energies and are represented in Man as the Twelve Primary Channels. The Ten Heavenly Stems relate to the energies of Heaven and are represented in man as the Yin and Yang aspects of the Five Element organs of Wood, Fire, Earth, Metal, and Water (as seen in Figure 11.38). The Nine Palaces are related to the Eight Extraordinary Vessels (corresponding with the Eight Postheaven Trigrams) in addition to the body's energetic Taiji Pole.

The Twelve Earthly Branches, Ten Heavenly Stems, and the Nine Palaces are interwoven into almost all aspects of Chinese culture, arts and medicine. In Chinese divination, as well as Chinese medicine, the temporal cycles of the Earthly Branches and Heavenly Stems form the foundation for these practices. They can be used to explain the physiology, pathology, diagnosis, and treatment of each clinical case. For each year, month, day, and hour there is a Stem and Branch association. By studying the Stem and Branch association, the Qigong doctor can identify patterns (i.e., determine the cycles and diagnose the patterns of the patient's disharmony) and design treatment protocols, depending on the time of year and the time of day.

The yearly cycles of the Stems and Branches are based on a sixty-year cycle, when the sun, moon, Earth, and North Star are aligned (Figure 11.39). The last sixty-year cycle began in 1984. The exact origin of the Ten Heavenly Stems and Twelve Earthly Branches is not known. They were used, however, to mark the hours, days, years, and planetary cycles as early as 1500 to 2000 B.C. Some historians attribute their origin to the legendary emperor Huang-Di (as early as 2600 B.C.). Each cycle was regarded by the Chinese as being a "century" in the life span of the average man. Those who lived past the age of sixty were regarded as living a "second life." During this second life, the person would experience similar occurrences as in the "first life," but would be able to apply the wisdom and maturity gained from his or her first life. The individual can then further his or her spiritual growth and use the knowledge to benefit society as a whole.



Figure 11.38. The Five Element Chart and Its Relationship to the Ten Celestial Stems

The twelve animals of the Chinese zodiac correlate with the Twelve Earthly Branches and are arranged as follows.

- Zi branch corresponds to the Rat
- Chou to the Ox
- Yin to the Tiger
- Mao to the Rabbit



Figure 11.39. The beginning of the sixty-year cycle is based on the alignment of the sun, moon, earth, and North Star.

- Chen to the Dragon
- Si to the Snake
- Wu to the Horse
- Wei to the Sheep
- Shen to the Monkey
- You to the Rooster
- Xu to the Dog
- Hai to the Boar

The first year of the sixty-year cycle is associated with the first Branch and the first Stem. The first Branch, "Zi," corresponds with the Rat; the first Stem, Chia, corresponds with the element Wood. Thus, the first year of the sixty-year cycle is the year of the Wood Rat in Chinese astrology.

The second year of the cycle represents the second Branch and second Stem, and so on. When you reach the 11th Branch, there are no more Stems and, thus, the 11th year of the cycle represents the eleventh Branch and the first Stem. The cycle continues in this manner until it has transitioned through six cycles of Stems and five cycles of Branches and returns to the first Branch and first Stem paired together.

Figure 11.40 shows these yearly cycles; for example, 1997 was the year of the Fire/Ox, so the year 1998 is the year of the Earth/Tiger.

The Ten Heavenly Stems represent Yang, and the higher form of Heaven's vitality (Figure 11.41). The Twelve Earthly Branches represent Yin and the lower form of Earth's vitality (Figure 11.42). Together they manifest the transformation of all natural events expressed through the growing, thriving, declining, and dying of all living things.

1. Each lunar year the Earthly Branch time divisions are divided into 12 separate month divisions.
2. Each day is divided into 12 two-hour Earthly Branch time divisions during a 24-hour cycle.

SUMMARY

In comprehending the energetic potential of the Three Treasures of Heaven, the Qigong doctor evaluates the patient's condition and treats the disease according to the patient's energetic rhythm and flow, which is blended with the Heavenly and Earthly energies. The treatment also includes prescribing homework (the Medical Qigong prescriptions needed to support and maintain the doctor's treatments).

Although mankind is terrestrial, there can be no separation from the influence of the celestial. For mankind is born on Earth in physical form, created through the integration of both celestial (Heavenly) and terrestrial (Earthly) energies. According to statements recorded in the *Canon of Internal Medicine*, ancient doctors had already rec-


Yearly Correspondences of Stems and Branches
Dog
Boar
Rat
Ox
Tiger
Rabbit
Dragon
Snake
Horse
Sheep
Monkey
Rooster
Dog
Boar
Rat
Ox *
Tiger
Rabbit
Dragon
Snake
Horse
Sheep
Monkey
Rooster
Dog
Boar
Rat
Ox
Tiger
Rabbit
Dragon
Snake
Horse
Sheep
Monkey
Rooster
Dog
Boar
Rat
Ox
Tiger
Rabbit
Dragon
Snake
Horse
Sheep
Monkey
Rooster
Dog
Boar
Rat
Ox
Tiger
Rabbit
Dragon
Snake
Horse
Sheep
Monkey
Rooster
Water
Wood
Fire
Earth
Metal
Water
Wood
Fire
Earth
Metal
Water
Wood
Fire
Earth
Metal
Water
Wood
Fire
Earth
Metal
Water
Wood
Fire
Earth
Metal
Water
Wood
Fire
Earth
Metal

Figure 11.40. The asterisk (*) shows the year 1997, which was the year of Fire/Ox. Each year, one of the twelve animals of the Chinese zodiac flourishes and brings its energy into action. Every two years, a new Element (Fire, Wood, Water, Earth, Metal) dominates in the cycle of creation. The chart moves clockwise, so 1998 was the year of Earth/Tiger.

Character	Name	Number	Animal	Month	Time	Branch	Channel	Image	Element
子	Zi	1	Rat	Nov. 22– Dec. 21	11-1 am	**Little Yang**	Gall Bladder	Reproduction of Life	**Water**
丑	Ch'ou	2	Ox	Dec. 22– Jan. 20	1-3 am	**Decreasing Yin**	Liver	Initial Growth	**Earth**
寅	Yin	3	Tiger	Jan. 21– Feb. 19	3-5 am	**Great Yang**	Lungs	Breaking Ground	**Wood**
卯	Mao	4	Rabbit	Feb. 20– Mar. 20	5-7 am	**Bright Yin**	Large Intestine	Thick Vegetation	**Wood**
辰	Ch'en	5	Dragon	Mar. 21– Apr. 19	7-9 am	**Bright Yang**	Stomach	Full Awakening	**Earth**
巳	Si	6	Snake	Apr. 20– May 20	9-11 am	**Great Yin**	Spleen	Preparation for Ripening	**Fire**
午	Wu	7	Horse	May 21– June 21	11-1 pm	**Little Yang**	Heart	Peak of Growth	**Fire**
未	Wei	8	Sheep	June 22– July 21	1-3 pm	**Great Yin**	Small Intestine	Taste of Full Ripeness	**Earth**
申	Shen	9	Monkey	July 22– Aug. 21	3-5 pm	**Great Yang**	Bladder	Time of Harvest	**Metal**
酉	You	10	Rooster	Aug. 22– Sept. 22	5-7 pm	**Little Yin**	Kidneys	Resting after Harvest	**Metal**
戌	Xu	11	Dog	Sept. 23– Oct. 22	7-9 pm	**Decreasing Yang**	Pericardium	Moving Inward	**Earth**
亥	Hai	12	Boar	Oct. 23– Nov. 21	9-11 pm	**Little Yin**	Triple Burners	Seed Awaiting Growth	**Water**

Figure 11.41. Environmental Energetic Interactions of the Twelve Earthly Branches

ognized the close relationship between the body's Qi and Blood and the influences of the natural environment. In ancient China, the Twelve Earthly Branches represented time units, each of them corresponding to a two-hour period. They are primarily used to represent the 12 months in the Lunar Calendar.

The Ten Heavenly Stems are made up of the Five Elements, each of which is divided into pairs of corresponding Yin and Yang, resulting in a ten-step system of numerology. Using the Ten Heavenly Stems allows the Qigong doctor to determine the ebb and flow of the Qi of Heaven and its corresponding relationship to the Qi of Man.

Both the Ten Heavenly Branches and Twelve Earthly Stems represent the characteristics of growing, thriving, declining, and dying of all living things in the universe, as well as the development and transformation of all natural phenomena.

The energy of the Ten Heavenly Stems can be observed within five energetic movements (front, back, right, left, and center), as well as within the elemental energy of the body's major internal organs.

Character	Name	Number	Element	Yin-Yang	Organ	Planet	Image
甲	Jia	1	Wood	Yang	G.B.	Jupiter	Sprouting Growth
乙	Yi	2	Wood	Yin	Liver		Early Growth
丙	Bing	3	Fire	Yang	S.I.	Mars	Expansive Growth
丁	Ding	4	Fire	Yin	Heart		New Life Fully Grown
戊	Wu	5	Earth	Yang	Stomach	Saturn	Prosperous Development
己	Ji	6	Earth	Yin	Spleen		Maturation
庚	Geng	7	Metal	Yang	L.I.	Venus	Retreating Inward
辛	Xin	8	Metal	Yin	Lungs		Hibernation
壬	Ren	9	Water	Yang	Bladder	Mercury	Inward Nourishment
癸	Kui	10	Water	Yin	Kidneys		Gathering New Life Energy

Figure 11.42. The Ten Celestial Stems and their Universal Energetic Interactions

CHAPTER 12

THE THREE TREASURES OF EARTH: EARTH, WATER, AND WIND

INTRODUCTION TO THE THREE TREASURES OF EARTH

The Outer Force (Power) of Earth's Three Treasures consists of the Yin and Yang interaction of energy and light, emitted, absorbed, and reflected back from the land, water, and wind. The Three Earthly Treasures are brought about by the waxing and waning of the five Yin and Yang climatic transformations (the five seasonal growth cycles), which in turn are caused by the sun, moon, and stars. Each seasonal change brings a life transforming gift that affects the mind, body, emotions, and spirit (Figure 12.1). The wind (weather) reflects the various conditions and transformations of energy in the sky, and is viewed as an Earthly manifestation of Heaven's moods.

1. Earth Qi consists of the Yin and Yang interactions of energy and light, manifesting as hot and cold energy originating from the Earth's surface.
2. Water Qi consists of the Yin and Yang interactions of energy and light, manifesting as hot and cold energy originating from the vast oceans, lakes, and rivers of the world.
3. Wind Qi consists of the Yin and Yang interactions of energy and light, manifesting as hot and cold air circulation created from the interaction of the sun's heat on the surface of the planet. This interaction includes all cloud and barometric pressure formations (e.g., tornadoes, hurricanes, lightning storms, etc.).

UNDERSTANDING HEAT AND LIGHT INTERACTIONS

Heat and light are manifested both externally on and from the Earth's surface, and internally within the Earth.

1. Externally, the greater the intensity of the sun's light absorbed into the surface of the Earth, the more heat is manifested from the Earth's surface. Cloudy days diminish the

Natural Earthly Transformations					
Organs	**Element**	**Season**	**Elemental Factor**	**Temperature**	**Transition**
Liver	Wood	Spring	Wind	60– 70° F	Germination
Heart	Fire	Summer	Heat	above 90 F	Growth
Spleen	Earth	Late Summer	Damp	75– 90° F	Transformation
Lungs	Metal	Autumn	Dry	60– 70° F	Gathering
Kidneys	Water	Winter	Cold	below 60° F	Storage

Figure 12.1. The Natural Earthly Transitions

sun's thermal interaction and tend to bring coolness.

2. Internally, heat and light, as well as other natural forces, are contained within the Earth itself. The sun's intense energetic fields draw the heat and light from within Earth, which are then reflected back to the Earth by the atmosphere.

The Earth's air extends only a comparatively short distance out from the Earth's surface, and the effects of the heat rays decrease as you leave the Earth's surface and ascend toward the outer regions of the atmosphere. As the air becomes less dense, there is less reflection. The higher you ascend, the cooler the air becomes. When you have reached the limit of air, you have reached the limit of the Earth's heat.

The heat and light form a protective energetic field around the Earth's surface similar to the body's Wei Qi field. Once you have reached the limit of heat and light, you reach what is called the Great Cold. This cold is considered far more solid than steel, and it presses down upon the Earth's energetic field and atmosphere with an almost irresistible force, holding them together.

UNDERSTANDING THE EARTH'S YIN AND YANG INTERACTIONS

Between Heaven and Earth there is an on-going interaction of Yin and Yang energy exchange. When the Earth Qi is in balance, plants grow and animals thrive. Power, in the form of energetic fields, is created by the integration of Yin and Yang. This power directly and indirectly affects the body's electromagnetic field, as well as the regulation and formation of the body's tissues. Visualize the Earth's energy as Qi resonating and emitting from the Earth itself. This energy includes the electromagnetic fields, subterranean radiations, and thermoluminescence (light and heat emitting from the center of the Earth).

The closer the Qigong doctor bonds physically, mentally, emotionally, and spiritually with the Earth and nature, the easier it is to tap into the Earth's energy and vibration. The development of Earth Qi in the body and the body's connection to the energy of the Earth are mutually supportive. The first step in internal cultivation involves focusing the mind on the Lower Dantian (with the aid of breathing techniques) to enhance the mind-body connection; this interactive connection develops a relationship with the Earth Qi.

GATHERING ENERGY FROM THE EARTH'S ENERGETIC FIELDS

The ability to gather energy from nature and the environment is extremely important to the Qigong doctor. The energy of the Earth stays within the structural components of the planet, flowing like mighty rivers of Qi. It is absorbed into the terrain and vegetation, as well as the water that we drink. Environmental Qi is specific to each geographic area. It is the energy that has been collected from the structural components of the Earth itself (i.e., soil, fields, deserts, plants, trees, forests, mountains, streams, rivers, lakes and oceans, etc.). The energetic potential of the Earth's Qi changes from Yang to Yin energy with the rising and setting of the sun, and therefore directly affects the environmental energy.

Although food and water are excellent sources for gathering energy, the Qigong doctor cannot continually ingest food, or drink herbal teas while treating patients, without overtaxing his or her digestive system. It is, therefore, important for the doctor to find an alternative source of energy, to replenish his or her system once it becomes depleted. By studying the waxing and waning of the Earth's Yin and Yang energies the doctor can optimize the absorption of Yin and Yang energy.

TECHNIQUES FOR CULTIVATING EARTH QI

Generally, several meditations are used to cultivate and absorb energy from the Earth by utilizing the energy of trees, bushes, flowers, lakes, etc. The primary objective of these meditations is to first cleanse the body of pathogenic factors, then cultivate and absorb the environmental Qi to replenish the body's energetic field. Practitioners and patients should visualize themselves immersed in a focused environmental field of energy, filled with its vibration, color, and light. They should allow this energized field to envelop their entire body.

CLEANSING THE BODY

One of the most popular cleansing techniques used in the Xi Yuan Hospital's Qigong Clinics begins from a lying, sitting, or standing posture (usually in a Wuji posture) while in front of a natural object, such as a tree.

To cleanse the body's energy, extend both hands towards the tree, as if to embrace it (it does not matter if the tree is actually being touched). Upon inhalation, begin to guide the energy from the tree into your torso through the Laogong (Pc-8) points at the center of your palms, and the Baihui (GV-20) point at the top of your head. Absorb this energy deep into your body. Once you feel that the body is fully saturated with Qi, exhale through the mouth and guide the Turbid Qi down the legs and out of the body through the Yongquan (Kd-1) points at the bottom of the feet. Continue to guide the Turbid Qi down through the Earth into the root system of the tree. Then inhale through the nose, as you absorb the purified energy from the upper part of the tree leading it down your body through the top of your head. Continue this process until you feel totally cleansed. Remember to synchronize breathing in through your nose as you focus on absorbing the Earth Qi, and to exhale through the mouth, as you focus on dispersing and releasing the Turbid Qi.

For tonification, extend your Qi and intention deep into the root system of the tree and imagine absorbing its natural energy through the Baihui point at the top of your head (Figure 12.2).

GATHERING QI FROM TREES, BUSHES, AND FLOWERS

Earth Qi and environmental energy saturate all types of foliage, allowing the Qigong doctor to select, gather, and absorb Qi from many botanical sources. Throughout history, the Chinese have used trees, bushes, and flowers for healing and medicine. Trees and plants absorb air, light, energy, water, and minerals. When Heavenly Qi is combined together with the environmental energy of the tree or plant, the result is a powerful invigorating energy source.


Figure 12.2. A Qigong doctor can extend Qi and intention deep into the root system of the tree and absorb its natural energy through the Baihui point at the top of the doctor's head.

In China, I noted that every Medical Qigong clinic I visited had its own garden. Each garden was full of healthy trees, bushes, and beautiful flowers from which the patients could draw energy. The patients could choose from different plants and bushes, each type of foliage having its own unique strengths and benefits. Any combination of healthy plant energies can be absorbed by the patients to improve their health.

The best time for absorbing energy from trees, bushes, and flowers is between the hours of sunrise (Mao: 5 - 7 am.) and noon (Wu: 11 a.m. – 1 p.m.).

It is important to note that, within the differing regions of a specific country, each type of tree and plant will have either minor or major variances regarding its energetic potential. This difference in energetic potential is due to the diverse environmental influences affecting each plant. We in the West, for example, have many different varieties of plants and trees similar to those in Asia, however, because of the energetic continental differences, the quality and quantity of Qi in each plant or herb can vary. This energetic difference is brought about by the various Qi fields produced by each region's altitude, the mineral content of the soil and water, and the amount of exposure to the energy of the sun. Even herbs of the same name, but grown in different countries, can have different affects on the body's energetic system, slightly altering their clinical potential (e.g., American Ginseng is sweet, slightly bitter and cold, and enters the body affecting the Heart, Lung and Kidney Channels; Siberian Ginseng is sweet, slightly bitter and slightly warm, and enters the body affecting the Lung and Spleen Channels).

GATHERING ENERGY FROM TREES

Trees are tremendously powerful plants and are commonly used by both doctors and patients to absorb and transform the negative pathogenic Qi into clean, healthy, life-giving energy. Pine trees tend to be one of the most powerful, as they radiate a great deal of Qi. Once an individual has connected with a tree, the primary goal is to:

1. remove stagnation from the channels,
2. tonify the internal organs,
3. stabilize and replenish any depleted energy within the body,
4. nourish the Blood, and
5. strengthen the nervous system.

The following is a brief description of various trees, their Yin or Yang potential, and their energetic affect on the body's internal organ system:

- Apple - slightly Yin - St and Sp
- Bamboo - Yin - Ht, Lu, GB, and St
- Birch - Yin - St
- Cassia (Cinnamon) - Yang - Sp, Kd, and Bl
- Cherry - Yang - Lv, Lu, Kd, and St
- Chestnut - Yang - Sp, St, and Kd
- Cranapple - neutral - Lv, Lu, and Ht
- Elm - neutral - St, SI, and LI
- Fig - neutral - Lu, LI, and Sp
- Ginkgo - neutral - Lu, Kd, and Ht
- Hawthorn - slightly Yang - Sp, St, Lu, and LI
- Magnolia - Yang - Lu, St, GB, LI, and Sp
- Maple - neutral - Sp, Kd, and LI
- Mulberry - Yin - Lu, LI, Sp, and Kd
- Oak - slightly Yang - LI, Sp, Kd, and Ht
- Pine - Yang - Ht, Lu, LI, and Kd
- Willow - Yin - Ht and Sp

GATHERING ENERGY FROM BUSHES

Bushes are an extremely effective source for gathering and ingesting different forms of healing energy. Similarly to trees, each bush has its own energetic properties and causes a specific reaction in the body's energetic field. Bushes, however, are not as powerful an energy source as trees for gathering massive quantities of Qi.

GATHERING ENERGY FROM FLOWERS

Flowers are unique in their effect on stimulating the nervous system. Different colors, shapes, and sizes can affect the emotions, causing the individual's spirit to open. Each color can be absorbed into the body in order to facilitate the stimulation of internal organ energy. The gift of flowers has had a long history in soothing emotional pain and bringing relief to patients.

CULTIVATION AND REGULATION TECHNIQUES

Techniques used in the Qigong clinics for cultivation, absorption and regulation of energy generally begin by having the patient face a tree, bush, flower, etc. Although the hands and body postures are similar to the last meditation, the mind's intention is quite different. In this meditation the patient absorbs Qi from the tree, by inhaling it through his left palm, to draw the energy into his body. The energy is guided down the patient's chest, into his or her Lower Dantian. From there the patient circulates this gathered energy through his or her Microcosmic Orbit. As the patient exhales, the Qi exits the right palm into the tree, and begins the cycle again. This meditation is practiced to replenish the body's energetic field.

Patients should be monitored regularly to prevent Qi deviations, which may occur while absorbing Qi through their pores. For best results, choose a quiet, safe, and healthy environment. Select trees, bushes, and flowers with a stable root, or thick trunks. The color is also very important, as the leaves and flowers should be bright, full, and healthy.

Because the body's internal energy matches that of the external environment, it is important to avoid selecting any area which is unpleasant or unhealthy. Avoid any tree, bush, or flower that is sick, dying, has lost its color, or has just been pruned. Using trees, bushes, or flowers for cleansing the body, as well as to absorb energy, is forbidden at night, because their oxygen production diminishes after the sun has set.

PRECAUTIONS

It is important not to meditate in front of any tree, bush, or flower that has parasites, or has been poisoned or polluted, since such vegetation will induce an impure energetic resonation within the Qigong doctor's body.

GATHERING QI FROM MOUNTAINS, VALLEYS, AND DESERTS

The mountains, valleys, and deserts absorb and release light, energy, and heat from the sun. These energies are absorbed and released from the structures of the land quicker than from the oceans, lakes, and streams. Environmental energy is also gathered and stored by the geological formations and local ecology. The ancient Chinese Qigong masters viewed the Earth as a living entity, with rivers and pockets of energy similar to that of the human body. Certain altitudes, densities of colors, and structural formations can affect the Earth's energetic potential.

GATHERING ENERGY FROM MOUNTAINS

Mountains are extremely powerful conduits of energy. They act as peak areas, or collection points for energy. The higher the mountain, the more the air is charged with electromagnetic potential. In ancient times, for prayer and meditation, Taoist and Buddhist temples, shrines, and caves were constructed on energetic pockets high within the mountains of China. In fact, all high, mountains that are far from human civilization are regarded as superior places for energetic cultivation, due to the clarity of light and extraordinarily potent energies which include a very high negative ion count in the air.

GATHERING ENERGY FROM VALLEYS

The Earth's valleys act as channels for Earth energy, collecting and carrying energy throughout the natural terrain. Systems of valleys extend through the plains, hills, and mountains, and generally flow towards the ocean. By standing at the "floor" of the valley (surrounded by its walls), energy can be easily absorbed into the body for cultivation.

GATHERING ENERGY FROM DESERTS

The deserts are considered seas of dry heat energy. They are excellent environments for meditations when used to gather Qi into the body, especially for combating diseases pertaining to Wind, Cold, and Damp invasion (which give rise to many diseases).

CULTIVATION TECHNIQUES

Generally there are several meditations used to cultivate and absorb energy from mountains, valleys, and deserts. The primary objective of these meditations is either to cleanse the body of pathogenic factors, or to cultivate and absorb Qi. When cultivating energy from mountains, valleys, or deserts, practitioners should visualize themselves immersed in the Earth's field of energy, filled with vibration, color, and light. The practitioners should allow this energized field of Earth Qi to envelop them completely.

For best results, select mountains, valleys, and deserts with a stable foundation. The color is also very important, as the Earth, soil, rocks, and surrounding area should be clean.

Also, there are certain locations on the planet known as "power spots" which can produce remarkably powerful effects in the body's energetic fields.

Patients should be monitored regularly in order to prevent Qi deviations, which may occur while absorbing Qi through their pores.

PRECAUTIONS

Because the body's internal energy matches that of the external environment, it is important not to meditate in front of any mountain, valley, or desert area that has eroded, is dying, has lost its color, or is polluted. Also prohibited are areas where there is ongoing seismic, or volcanic activity, as such areas will induce unstable resonation within the Qigong doctor's body.

GATHERING QI FROM OCEANS, LAKES, AND STREAMS

The oceans, lakes, and streams retain and release the sun's light, energy, and heat slowly and are, therefore, important in energy cultivation. The body instantly absorbs the light, energy, and resonant vibrations stored within water. Energized water (sometimes in the form of herbal teas) is often used by Qigong doctors in clinics throughout China. This energetically transformed water provides the patient's body with the basic components necessary for restoration and regeneration, and is considered the "elixir of life" by many Qigong doctors.

GATHERING ENERGY FROM OCEANS

The energy from the ocean has a strong cleansing and purifying effect on the body's Qi. Meditating by the ocean is used extensively for dispersing negative emotions and regulating the body's internal organs. The active rhythm and sound of the waves allows the patient to harmonize his or her internal energetic rhythms with that of the tide, thus quieting the nervous system.

GATHERING ENERGY FROM LAKES

The energy from a lake has a strong calming affect on the body's energetic field. The quiescent solitude of a lake can be used to sedate active emotions, balance any Excess or Deficiency, and calm the body's Shen.

GATHERING ENERGY FROM STREAMS

The energy of a stream can be used to replenish and restore depleted Qi, sedate active emotions, balance any Excess or Deficiency, and also to calm the body's Shen.

CULTIVATION TECHNIQUES

Generally there are several meditations used to cultivate and absorb energy from oceans, lakes, and streams. The primary objective of these meditations is to either cleanse the body of pathogenic factors, or cultivate and absorb Qi to replenish the body's energetic field. When cultivating energy from oceans, lakes, or rivers, patients should visualize themselves immersed in a pool of water, filled with energy, color, and light. The patient should allow this energized water to absorb, cleanse, and invigorate the entire body.

Patients should be monitored regularly to prevent Qi deviations, which may occur while they are absorbing Qi through their pores. For best results, select oceans, lakes, and streams with a calm, stable current. The color is also very important, it should be clear and clean. The water and the surrounding areas should also be clean.

PRECAUTIONS

Because the body's internal energy matches that of the external environment, it is important to avoid selecting any oceans, lakes, or streams that are turbulent, have become dull in color, polluted, or stagnant.

GATHERING QI FROM THE SIX DIRECTIONS

Absorbing Qi from the six directions (Heaven, Earth, and the Four Winds), focuses on gathering environmental energy into the center core of the body (Taiji Pole) from: Heaven, Earth, and the four directions: South corresponds to the front of the body, North to the back of the body, West to the right of the body, and East to the left of the body. The Taiji Pole is considered the central axis, with two directions, above and below. This is a tonification exercise that is used for gathering and absorbing the Earth's environmental Qi, to energize a weakened or Deficient condition.

CULTIVATION TECHNIQUES

There are several meditations used to cultivate and absorb energy from the four directions of the horizon, with the fifth and sixth directions being at the top and bottom of the Taiji Pole. The primary objective of these meditations is to first cleanse the body of pathogenic factors, then to cultivate and absorb environmental Qi. Each direction of energy (N, S, E, W, Heaven, and Earth) has its own unique field of power and vibration, and is assigned a specific color. Each vibration and color stimulates the energy field of one of the five major Yin organs through the body's Heaven and Earth connection (i.e., the Taiji Pole).

When cultivating energy from the horizon, practitioners should face the direction of the south and visualize themselves surrounded in an energetic mist. This mist contains six different colors and light vibrations. From the four directions (N, S, .E, and W) emanate the corresponding following four colors: ruby red, brilliant white, indigo and emerald green. Each of these colors are associated with a particular Yin organ: ruby red with the Heart, brilliant white with the Lungs, indigo with the Kidneys, and emerald green with the Liver. From the Earth itself arises a golden yellow mist; this color is associated with the Spleen. From Heaven descends a silvery white mist entering the body at the top of the head; this color is associated with the Taiji Pole. These six different colored mists permeate and envelop the body with their healing light vibrations.

To perform this meditation, stand in a Wuji posture as you visualize:

1. A silvery white mist descending from the center of the Heavens to penetrate and envelop your Taiji Pole. This silvery white mist enters your body through the top of the head at the Baihui (GV-20) point, and flows into and fills up the Taiji Pole, saturating and absorbing into your center core.
2. A golden yellow mist, ascending from the center of the Earth, entering the body through the bottom of your feet at Yongquan (Kd-1) points. This golden yellow mist saturates your Spleen as it penetrates and envelops your center core;
3. A ruby red mist, flowing from the horizon in front of you enters your Heart, as it saturates and envelops the front of your body.
4. An indigo or dark blue mist flowing from the horizon behind you enters your Kidneys, as it saturates and envelops your back.
5. A brilliant white mist flowing from the horizon on your right side enters your Lungs, as it saturates and envelops the right side of your body.
6. An emerald green mist flowing from the horizon on your left side enters your Liver, as it saturates and envelops the left side of your body.

Patients should be monitored regularly to prevent Qi deviations which may occur while the patient is absorbing Qi through his or her pores. For best results while absorbing environmental Qi, the color of the energy should be clean, clear and bright.

PRECAUTIONS

Because the body's internal energy matches that of the external environment, it is important to avoid selecting any areas that are windy, turbulent, polluted, or stagnant. Also avoid cultivating energy in storms, during hurricanes, sweltering heat, or blistering cold. Avoid any type of extreme weather condition.

ADDITIONAL TECHNIQUES FOR TRAINING EARTH QI

The following exercises at one time were secretly practiced throughout China, as a means for Medical Qigong doctors and Qigong masters to practice advanced methods of environmental energy manipulation. The purpose of these Qigong exercises is to allow the doctors the chance to practice connecting and infusing their energetic field with the environmental energetic field.

PULLING CLOUDS OUT OF THE SKY

This exercise requires the Qigong doctors to first root and immerse themselves with the vibrational resonance of the Earth (this can be accomplished by practicing the One through Ten Meditation, described in Chapter 26). Next, the doctors extend an energetic line from the Earth into the sky, connecting to and enveloping a specific cloud. Through focused intention, the doctors imagine sucking the cloud out of the sky and down into the Earth, rooting its energetic form into the Earth's energetic field. As the cloud's energy is absorbed into the Earth, it dissolves from the sky.

Once the doctors have rooted the cloud into the Earth's energetic field, they have two choices: either to release the cloud back into the sky by attaching its energetic form onto an already existing cloud, or to allow the cloud to disperse into the energy of the surrounding environmental field.

DIVIDING A CLOUD IN HALF

After connecting and rooting into the Earth's energetic field, the Qigong doctors extend their intention into the sky, connecting with a particular cloud formation. Next, the doctors condense their upward intention, and like a laser beam, begin dividing and separating the cloud into two halves. After the cloud has been divided into two separate formations, the doctors can either continue to further divide and dissect the cloud or reconnect its structure.

THE EARTHLY TREASURE OF FOOD

The Earth's natural energetic forms and transformations affect the flow of the body's life-force energy. Food and water are examples of a natural form of Earth Qi, and are viewed as Earthly Treasures. Although the air we breath is representative of Heaven Qi, due to the influence of environmental energetic fields, it is also viewed as an Earthly Treasure. The objective of self-cultivation work is to continually purify the energy within the Microcosm of Man, and increase the awareness of the pure energy within the Macrocosm of the universe.

Because of its connection to the Earth's Yin and Yang energy fields, the body's life-force energy can be replenished through the consumption of food and herbs. Both food and herbs have Yin or Yang properties which, when consumed, help the body in moving, tonifying, purging or regulating the life-force energy.

UNDERSTANDING THE YIN OR YANG ASPECT OF FOOD

When trying to determine whether a food is more Yin or Yang, several characteristics should be evaluated. Yin foods take less time to grow, are more watery or wet, and are colder, and sweeter. Yang foods take more time to grow, are drier, hotter, and less sweet. The more Yin the food, the more expanded it will become (e.g., a pumpkin); the more Yang the food, the more contracted or dense it will become (e.g., a turnip).

Diet directly influences the body's ability to generate Qi. The body's ability to effectively digest food plays a big part in how efficiently the body utilizes the nutrients it receives.

UNDERSTANDING THE YIN OR YANG ASPECT OF HERBS

Food is a powerful healing tool. Medicinal herbs are considered "special foods," and are divided into Yin and Yang aspects throughout China. They are prescribed to be taken in soups (tang), teas, or as additives to other dishes; for example, Chinese Qigong doctors, as well as many martial arts masters, frequently drink herbal teas to help regulate their body's energies during seasonal changes. The herbal teas are consumed according to the following sequence.

1. The summer is considered the season of maximum Yang; green herbal tea is drunk in order to cool down the body and regulate the internal organ systems.
2. The autumn is the season when Yin and Yang energies balance; however, the Yin energy is increasing, so flower tea is drunk to help stabilize the body's Yin and Yang balance.
3. The winter is considered the season of maximum Yin; black or red tea is drunk to warm the body and regulate the internal organ systems.
4. The springtime is the season when Yin and Yang energies balance; however, the Yang energy is increasing, so flower tea is drunk to help stabilize the body's Yin and Yang balance.

Teas are frequently prescribed for their particular healing properties. Each herb has a specific nature. Herbs that are considered Hot or Warm are used to treat Cold conditions, and herbs that are considered Cold or Cool are used to treat Hot conditions. Herbs are also categorized according to their flavor (sour, bitter, sweet, pungent, or salty) and are used to affect the body's internal organ energy. Herbs help the Qi ascend or descend in order to purge or tonify an internal organ or channel. Herbs are also used in moving the Blood. Specific herbs are also chosen for prescription, based on the Differential Diagnosis according to the Eight Energetic Principles (see chapter 21), the Five Elements (see chapter 23), and the Six Stages (see chapter 24) theories .

Generally, because all herbs have medical uses and contraindications, they are collected and divided into three categories: superior herbs - which consist of tonics, common herbs - which are slightly toxic, and inferior herbs - which are toxic. To gather herbs, the doctor must have an extensive knowledge of the environment (season, place, time, etc.), and the specific herb (roots, bark, leaves, flowers, fruits, etc.) The doctor must also possess the harvesting skill required for gathering the herb. Once the herbs have been gathered, the doctor must then begin the procedure of processing them. The process work is important as some herbs are poisonous and need to be detoxified, while others have their properties enhanced through the extracting process.

ENERGY, FOOD, AND DIET

Many generations have asked the same question, "Is food medicine or medicine food?" An old Chinese proverb states, "To tonify with food is better than with medicine, but to tonify with Qi is better than food." Several decades of nutritional, epidemiological, and clinical studies point to a powerful link between disease and dietary habits.

For centuries, Chinese healers have studied food, discovering the properties of specific foods and the secrets of using them to achieve health and longevity. Chinese nutrition focuses on the energetic properties of food and their qualitative actions on the body as a whole, as well as their influences on the various internal organs and channels. Unless the patient eats correctly, Qigong, acupuncture, Chinese massage, and even herbal therapy will not be as effective, or long standing. In the Tang Dynasty, the great physician Sun Simiao wrote the medical classic *One Thousand Ounces Of Gold*, which described the dietary treatments of several diseases, including night blindness and goiter.

What we eat can either aggravate or enhance the healing of a particular condition. When Gu Qi (food energy) is being generated, strong surges of energy from the Spleen and Stomach (in the Middle Dantian) cause the body to generate more Yang Qi. As the body's Yin aspect weakens, its energetic nature becomes dryer and wanes; the Yang is no longer held in check and an overexuberant Yang begins to generate Heat, which produces, and sometimes releases, emotions.

Emotions begin with, and stem from, the energetic properties of Postnatal Qi. When ministering to patients, the doctor should ensure a healthy physical and social environment (e.g., clean air and a loving support system), as well as monitor the quality and quantity of food consumption. Hostile surroundings interfere with the proper digestion of food and cause toxic Qi. Food, air, and water become the fuel that generates energy in the body. When life-force energy becomes impure from poor diet, Heat accumulates in the organs, creating Excess Yang, or Excess Fire Qi.

One essential skill for harvesting the Earth's Treasures is controlling the intake of food and diet. It is important that a patient not eat foods that are excessively Cold, Hot, spicy, or greasy. If food is ingested while the food is too Yin (Cold) or out of harmony with the seasons, an external pathogenic factor can be created. When a Cold or Yin factor is created (a condition where Cold and Excess Yin consumes the Kidneys Yang, preventing the body's Yang Heat from warming the body), the Qi becomes sluggish, thus blocking the channels or collaterals. These blockages cause pain and damage to the Stomach and intestines and affect the Heart and Lungs.

If food is ingested while the food is too Yang (Hot) or out of harmony with the seasons, a Yang factor is created, causing internal energy to be released, which damages both the Blood and Qi. Because of its turbid nature, food that is too greasy may damage the Stomach Qi, causing boils and pyogenic infections, along with ulcerous skin diseases. Excessive eating may cause too much Gu Qi to develop, generating an excessive amount of power. This Excess power produces an upward reaction of Stomach Qi, which is detrimental to both the Spleen and Stomach, causing the breath to become obstructed (mother/Spleen affecting child/Lungs), and the psychic centers (Shen within the Heart) to become blocked. Many postnatal illnesses result from eating the wrong kinds of food in the wrong season, not eating enough of the right kind of food, overeating, or all of the above.

Balancing the diet in accordance with the cycles of nature and the principles of Yin and Yang

Balancing the Diet					
	Liver	**Heart**	**Spleen**	**Lungs**	**Kidneys**
Excess	Sour	Bitter	Sweet	Pungent	Salty
Controlled By	Pungent	Salty	Sour	Bitter	Sweet
Counteracts	Sweet	Pungent	Salty	Sour	Bitter

Figure 12.3. The Five Flavors and their Controlling and Counteracting Cycles

should be an integral part of the daily practice. In some situations, the body can compensate for an improper or unbalanced diet. To counteract this imbalance, however, the body will expend a great quantity of energy. Eating similar foods all the time results in the accumulation of toxins from those foods and can cause mildly allergic reactions. A balance of the different food groups is the key to dietary success.

USING THE FIVE FLAVORS OF FOOD

The energetic properties of the Five Flavors of food (sour, bitter, sweet, pungent, or salty) can be used to balance and control the energy of each organ. Any excess or deficiency of one flavor affects not only the organ to which it corresponds, but all the other organs as well (Figure 12.3). In the clinics in China, the theory of the Five Flavors or tastes is combined with the theory of the Five Elements to describe the interaction of the different "flavors" on the body's internal organs and energetic systems (Figure 12.4). The Five Flavors and their affect on the body are described in the following sections.

SOUR TASTE, ELEMENT WOOD

Some examples of Sour foods include: lemons, pickles, liver, vinegar, wheat, salad oils, and sour cream. Sour foods affect the Liver, eyes, and tendons. They are also excellent for stimulating the energy of the Liver and Gall Bladder.

1. Sour foods are astringent (causes shrinking), and can be prescribed to achieve the following treatment goals:
   - to prevent or reverse the abnormal leakage of Qi and Fluids,
   - to counteract diarrhea and excessive perspiration by slowing the movement of fluids,
   - to drain the Liver of Excess Qi, thereby indirectly strengthening the Lungs, and
   - to correct an irregular, slow heartbeat.
2. An excess of sour foods can cause the following dysfunctions:
   - injures the muscles,
   - hardening and wrinkling of the skin, and
   - stiffness spreading along the tendons that are controlled by the Liver. As the Liver controls the tendons, patients with Liver trouble should also eat less sour food.

BITTER TASTE, ELEMENT FIRE

Some examples of Bitter foods include: coffee, black and green teas, asparagus, celery, turnips, leeks, cabbage, broccoli, and cauliflower. Bitter foods affect the Heart, tongue, and Blood. They are also excellent for stimulating the energy of the Heart and Small Intestine.

1. Bitter foods are used for draining and drying, and can be prescribed to achieve the following treatment goals:
   - to stimulate the energy of the Heart, control the Heart Fire,
   - to reducing fever and Excess body Heat,
   - to stimulate digestion,

Five Elemental Cycle					
Element	Fire	Metal	Wood	Earth	Water
Season	Summer	Autumn	Spring	Late Summer	Winter
Organ	Heart	Lungs	Liver	Spleen/ Pancreas	Kidneys
Bowel	Small Intestine	Large Intestine	Gall Bladder	Stomach	Urinary Bladder
Superficial Organ	Blood Vessels	Skin	Nerves	Muscles	Bones
Release Point (Sense Organ)	Tongue	Nose	Eyes	Mouth	Ears
Taste	Bitter	Pungent	Sour	Sweet	Salty

Figure 12.4. The Five Flavors in Relationship to the Body's Internal Organs, Seasons, and Elements

- to drain Excess Spleen Qi, and
- to remove obstructions in the upper respiratory tract.

2. An excess of Bitter foods can cause the following dysfunctions:
   - dryness and congestion of the Spleen and Stomach; and
   - hyperactivity of the Heart Fire, and the consumption of Kidney Yin fluids.

SWEET TASTE, ELEMENT EARTH

Some examples of Sweet foods include: honey, sugar cane, orange juice, pecans, snow peas, corn, milk, and sweet potatoes. Sweet foods affect the Spleen, mouth, and muscles. They are also excellent for stimulating the energy of the Spleen, Stomach, and pancreas.

1. Sweet foods are used for tonifying, regulating and sometimes moistening, and can be prescribed to achieve the following treatment goals:
   - to stimulate the digestive Fire,
   - to tonify the Spleen, Stomach and pancreas, and
   - to drain the Heart of Excess Qi.
2. An excess of sweet foods can cause the following dysfunctions:
   - an imbalance in the Kidneys,
   - an aching in the bones,
   - hair loss from the head,
   - muscle dysfunctions, and
   - injury to the Spleen and Stomach. The Sweet flavor spreads through the muscles, so patients with diseases of Spleen, Stomach, or muscles (diabetes, hypoglycemia, systemic candida, fibriomyalgia, chronic fatigue, etc.) should limit their intake of Sweet foods.

PUNGENT TASTE, ELEMENT METAL

Some examples of Pungent foods include: garlic, onions, ginger, black and white pepper, mustard, and chilies. Pungent foods affect the Lungs, nose, skin, and body hair. They are also excellent for the stimulating the energy of the

Lungs and Large Intestine. Because the Lungs control the Qi, the Lungs are very quick in absorbing the energy of Pungent foods.

1. Pungent foods are used for dispersing and moving, and can be prescribed to achieve the following treatment goals:
    - to induce perspiration,
    - to improve circulation of Qi and Blood,
    - to stimulate the digestion,
    - to activate the Lung energy and promote the Lung's function,
    - to expand the Lung Qi,
    - to drain the Lungs of Excess Qi, and
    - to increase Fluids and saliva secretions.
2. An excess of Pungent foods can cause the following dysfunctions:
    - great loss of Lung energy and damage to the Lung organs,
    - knots in the muscles, and
    - withering or decay of the fingernails and toenails.

SALTY TASTE, ELEMENT WATER

Some examples of Salty foods include: shellfish, cheese, soy sauce, salt, ham/pork, and margarine. Salty foods affect the Kidneys, ears, and bones. They are also excellent for stimulating the Kidney Qi and Bladder Qi.

1. Salty foods are used for purging and softening, and can be prescribed to achieve the following treatment goals:
    - to soften hard nodules such as cysts,
    - to purge inflamed lymph glands, and
    - to soften knotted muscles.
2. An excess of Salty foods can cause the following dysfunctions:
    - cause damage to the Kidneys and Bladder,
    - cause the Blood to coagulate or clot,
    - cause Blood diseases,
    - harden the pulse, and
    - cause changes in the complexion.

GUIDELINES FOR THE FIVE ELEMENTAL TASTES

During each season, the five separate extremes in flavors serve as a catalyst to draw Qi into the Deficient organ. Overexposure to the seasonal elements (Cold, Wind, Damp, etc.) is responsible for external pathogenic factors that invade the body and affect the body's Jing, Qi, and Shen. The development of disease is due to an imbalance in the struggle between the body's health preserving Qi and the pathogenic influences. If the pathogenic factors are excessive, they can obstruct the body's normal physiological function, creating illness. If, however, the body's Qi is strong, the pathogenic factors will have a difficult time causing any energetic imbalances.



Figure 12.5. The quality of the body's pulse is constantly changing according to the rhythm of the five seasons.

Traditional Chinese Medicine divides the effects of these tastes into five seasons, each with its own unique function and flow of energy affecting the human body. One example of the effects of nature's rhythms on man is that the pulse quality in the viscera constantly changes in accordance with the five seasons (Figure 12.5). The Liver pulse is relatively strong in spring, compared to the other organs; in the summer the Heart is stronger, in the late summer - the Spleen, in the autumn - the Lungs, and in winter - the Kidneys.

Basic guidelines are developed for eating in accordance with the flow of the Five-Element cycle. These guidelines will help train the body to recognize what foods it needs. The food types and tastes are divided into five categories, which relate to the five seasons of the year, the Five Elements, and the Yin and Yang organs (Figure 12.6).

To achieve overall balance, food and energy must be equally balanced. If the Liver is weak, for example, eating Sour food will help correct it and Salty food will also help. This prescription is based on the Five Element theory, which focuses primarily on two cycles—the Generating Cycle and the Controlling Cycle (Figure 12.7).

OVERVIEW OF THE FIVE ELEMENTAL TASTES

The overall understanding of the Five Elemental tastes empowers the Qigong doctor to accurately assist in prescribing better eating habits for his or her patients. By understanding the seasonal eating patterns (i.e., in the winter eating root food, which is grown under the ground, and in the summer eating food that is grown via branches and flowers) the doctor can observe whether the patient is further compounding his or her disease condition through improper diet.

SUMMARY

In comprehending the energetic potential of the Three Treasures of Earth, the Qigong doctor will be able to evaluate the patient's eating and living conditions and their affect on the patient's disease. This also includes prescribing the Medical Qigong exercises, meditations, diets, and eating habits needed in order to support and maintain the doctor's treatments.

Through monitoring the patient's connection to their environment and eating patterns, the Qigong doctor is able to understand the Earthly influence on the patient's physical, mental, emotional, and spiritual being.



Figure 12.6. The Five Elements' Interaction of the Five Flavors

In the Creative or Generating Cycle—		
Salty Kidney (Water)	generates	(Wood) Sour Liver
Sour Liver (Wood)	generates	(Fire) Bitter Heart
Bitter Heart (Fire)	generates	(Earth) Sweet Spleen
Sweet Spleen (Earth)	generates	(Metal) Pungent Lung
Pungent Lung (Metal)	generates	(Water) Salty Kidney

In the Controlling Cycle—		
Salty Kidney (Water)	controls	(Fire) Bitter Heart
Bitter Heart (Fire)	controls	(Metal) Pungent Lungs
Pungent Lungs (Metal)	controls	(Wood) Sour Liver
Sour Liver (Wood)	controls	(Earth) Sweet Spleen
Sweet Spleen (Earth)	controls	(Water) Salty Kidneys

Figure 12.7. The Creative (or Generating) and Controlling Cycles of the Five Flavors

CHAPTER 13

THE THREE TREASURES OF MAN: JING, QI, AND SHEN

The Outer Force (Power) of the Three Treasures of Man are expressed through Jing (Essence), Qi (Energy), and Shen (Spirit). The human body is made up of vibrational frequencies that interact to create energetic fields and substances, or energetic materials ranging in structure from less dense to more dense (Figure 13.1). In order of increasing density, these energetic materials manifest as Spirit (Shen), Energy (Qi), Essence (Jing), Blood (Xue), Body Fluids (Ye/Jin), Marrow (Sui), and Bone (Gu). Of these energetic substances, Essence (Jing), Energy (Qi), and Spirit (Shen) are regarded as the most important. These three materials perform the most important functions in the human body, and are known as the Three Treasures of Man or San Bao.

The energy of the human body, or Man's Qi, is created from and through different interacting rates of vibration and energy fields that combine to form the body's cells, tissues, and organs, creating a living organism. In Chinese philosophy, the Three Treasures of Man also represent the interaction of Heaven and Earth within the human body.

Man is composed of these combined Heaven and Earth energies:

1. The Jing is the body's tangible essence, composed of a morphogenic field of energy that creates and sustains the body's physical form. It is the lower vibrational frequency of the human energy matrix. During the healing process, the patient's Jing directs the proper cells to multiply so that the body can heal rapidly and completely.
2. The Qi is the life-force energy that maintains the body's Jing. It is the electromagnetic body of the channel system and distributes vitality to the body through energetic transference. It

Natural Human Transformations									
Yin Organ	**Yang Organ**	**Sense Organ**	**Taste**	**Color**	**Body Smell**	**Sound**	**Tissue**	**Positive Emotion**	**Negative Emotion**
Liver	Gall Bladder	Eyes	Sour	Green	Rancid or goatish	Shout	Nerves & tendons	Kindness, benevolence	Anger
Heart	Small Intestine	Tongue	Bitter	Red	Scorched or burned	Laugh	Blood vessels	Love, joy, respect	Elation, arrogance, impatience
Spleen	Stomach	Mouth	Sweet	Yellow	Sweet, fragrant	Sing	Muscles & fascia	Fairness, openness	Worry, anxiety
Lungs	Large Intestine	Nose	Pungent	White	Tidepool, fishy	Weep	Skin & hair	Righteous, courageous	Sadness, grief
Kidneys	Bladder	Ears	Salty	Blue	Putrid, rotten	Groan	Bones	Gentleness, wisdom	Fear

Figure 13.1. This diagram shows the natural transformations of man's internal organs, energy, and matter, as well as their natural manifestations.

is the middle vibrational frequency of the human energy matrix. The vibrational field of Qi sustains and contains the thoughts and emotions, and interacts between the vibrational fields of Jing and Shen.

3. The Shen is the spirit and psyche which maintains the body's Qi. It is the higher vibrational frequency of the human energy matrix. It is also the energetic field which sustains the vibration of the Mind (the process of awareness and consciousness located throughout the body, not limited to the brain), interfacing between the Mind and Qi.

These three substances resonate at different frequencies and are mutually dependent upon each other for maintenance and survival. Low frequencies are attributed to the resonance of Jing, medium frequencies to the resonance of Qi, and high frequencies to the resonance of Shen. Metaphorically speaking, Jing can be compared to a dense, solid material such as ice, Qi to a flowing material such as water, and Shen to a vapor.

In Chinese medicine, the Qigong doctor uses the Three Treasures of Man for assessing and diagnosing the patient. Observing the state and interaction of the patient's Jing, Qi, and Shen allows the doctor to determine the patient's prognosis and chances for successful treatment. The doctor can assess the Jing, Qi, and Shen by:

1. Observing the general vitality of the patient's Jing through pulse reading and tongue diagnosis,
2. Noting the general vitality of the patient's Qi through observation of the Wei Qi field, and
3. Observing the general vitality of the patient's Shen by the quality of glitter in the patient's eyes.

Within this model, Jing, Qi, and Shen are viewed as layers of energetic fields between the body and the Mind. Jing is the innermost energetic layer, the blueprint which holds the physical body to the desired form. Shen is the outer energetic layer of the body through which the Mind experiences and directs the activity of the body. Qi is the intermediate energetic layer, the medium which allows the Jing and Shen (the energetic fields of the body and spirit) to communicate.



Figure 13.2. The Three Treasures of Man

PRENATAL AND POSTNATAL JING, QI, AND SHEN TRANSFORMATIONS

Jing is the body's foundational substance, responsible for nourishing the tissues. Qi emerges out of Jing circulating through the tissues. It promotes the body's metabolism. Shen governs the body. The body contains both prenatal and postnatal versions of Jing, Qi and Shen.

1. Prenatal Jing (Yuan Jing) is the body's innate and true Original Essence, which determines the constitutional makeup, strength, and vitality. It is not the reproductive Essence (sperm and ovary essence), which is considered Postnatal Jing.
2. Prenatal Qi (Yuan Qi) is the body's Original Energy, extending into the Wuji (infinite space or Void). It is the motivative energetic force linking the Prenatal Jing with the Prenatal Shen. It is not inhaled air (oxygen), which is considered Postnatal Qi.
3. Prenatal Shen (Yuan Shen) is the Original Spirit, that is able to perceive and intuit truth and knowledge (knowing without knowing). It is not cognitive thinking or consciousness, which is considered Postnatal Shen.

Through meditation, the body's alchemical processes of internal energy transmutations can be cultivated. Jing can be used to create or increase Qi; likewise, Qi can be used to create or expand the Shen. This creative cycle also works in reverse order by transforming Shen to Qi, and Qi to Jing (Figure 13.2).


Prenatal Transition
Dao - Divine
Wuji - Infinate Space
The Formless Void
Yuan Shen - Original Spirit
Perceptive and Intuitive Knowledge
Yuan Qi - Original Energy
Extends into the Wuji
Yuan Jing - Original Essence
Determines Constitutional Form,
Strength and Vitality
Postnatal Transition
Dao - Divine
Wuji - Infinate Space
The Formless Void
Shen - Acquired Spirit from
Cognative Thinking
Qi - Acquired Energy from
Food, Air and Water
Jing - Reproductive Essence

Figure 13.3. The Prenatal and Postnatal Alchemical Transitions of Jing, Qi, and Shen

PRENATAL TRANSFORMATIONS

The following transformations describe the origin and creation process of the Three Treasures within the body of the fetus (Figure 13.3). Through comprehending these transformations, the Qigong doctor can teach individuals how to cultivate their Jing. The body's prenatal energies, which support the body's postnatal Jing, are sustained by prayer, meditation, and sleep. This quiescence state is necessary for the body to reenergize its Prenatal Qi.

1. Divine Energy (Dao) transforms into infinite space (Wuji). At this beginning stage, the spirit of the God envelops infinite space, including the energetic fields of the Heavenly universe and the environmental Earthly fields.
2. Infinite space (Wuji) transforms into Spirit (Yuan Shen). At this transition, the spirit of God descends to permeate, unite, and dwell within the Original Spirit (Yuan Shen) of the forming fetus.
3. Spirit (Yuan Shen) transforms into Energy (Yuan Qi). At this stage of transition, the Original Spirit of the fetus transforms into Original Energy (Yuan Qi).
4. Energy (Yuan Qi) Transforms into Essence (Yuan Jing). At this final stage, the Original Energy of the fetus is transformed into Original Essence (Yuan Jing).

POSTNATAL TRANSFORMATIONS

The following transformations describe the origin and creation process of the Three Treasures within the body after birth. Through comprehending these transformations, the Qigong doctor is able to achieve a harmonious balance between the three energies through Postnatal Jing cultivation. The body's postnatal energies are supported and sustained first of all through food, drink, and air.

1. Essence (Jing) Transforms into Energy (Qi). At this beginning stage, the body's Jing is Heated within the Lower Dantian to create Qi. This transition is similar to ice melting into water.
2. Energy (Qi) Transforms into Spirit (Shen). At this transition the body's Qi is steamed within the Middle Dantian, to be transformed into Shen. This transition is similar to water transforming into vapor.
3. Spirit (Shen) Transforms into infinite space (Wuji). At this stage, the body's Shen fuses with the resonant light of the Upper Dantian

and is transformed and released into the Heavenly and Earthly fields of energetic space. This transition is similar to vapor diffusing into space.

4. Infinite Space (Wuji) Reunites with the Divine (Dao). At this final stage, the Shen is reunited with the divine.

The Shen directs the increased amount and flow of Qi during the transformation process of Jing into Qi and Qi into Shen through conscious intention. Through this soft focused intention an alchemical cycle of transformation is created whereby Jing, Qi, and Shen can then be gathered, refined, and trained.

TRANSFORMATIONAL ATTAINMENT MODALITIES

Each of these prenatal and postnatal transformations include training exercises and meditations that are either developed in low, medium, or high attainment approaches. The low attainment approach is known as the physical attainment approach; the medium attainment approach is known as the mental attainment approach; and the high attainment approach is known as the spiritual attainment approach. Qigong regulation encompasses all three attainment modalities in order to facilitate the ultimate in energetic transformation. The three attainment approaches for increasing to maximum capacity the body's energy are described as follows.

1. The Physical Attainment Approach concentrates on the development and cultivation of the body's energy by focusing on Dynamic (energetic movement) and Quiescent (stillness) Qigong meditations to fully realize one's energetic potential.
2. The Mental Attainment Approach concentrates on increasing mental power by focusing on symbolic drawings, reciting prayers, or mantras to manifest fully one's mental potential.
3. The Spiritual Attainment Approach concentrates on the development and cultivation of the body's Original Spirit (Yuan Shen) by focusing on Shengong meditations (meditations that focus on spiritual cultivation) to harvest one's spiritual potential.

JING: ESSENCE OF LIFE

Jing refers to the indispensable bioenergetic substance of all living things (i.e., the energetic matrix of the body's cells, tissues, etc.). In Medical Qigong therapy, Jing is considered the most Yin form of Qi. Jing, as a pure Essence of living matter, is more dense than Qi but more refined than Blood or Fluids. When Jing is cultivated and allowed to arise naturally within the body, the outer surface of the body's tissues becomes harmonized and glows. Deep within the tissues, the Jing pools like a deep spring. The greater the degree of harmony between the individual's physical, mental, energetic, emotional, and spiritual fields, the more Jing is transformed into Qi.

THE YIN AND YANG ASPECTS OF JING

Jing can be divided into the functional aspects of Yin and Yang properties. The Yin aspect of Jing provides the material basis for growth, development and reproduction, and is the substratum for the formation of the materials associated with the Marrow and Blood. The Yang aspect of Jing activates transformations, growth, development and reproduction, and is associated with the Yuan Qi, Blood and Body Fluids (Figure 13.4).

As a subtle energy, Jing has a tendency towards downward movement, flowing like water, it fills the Lower Dantian, adrenals, Kidneys, and urogenital organs. Essence originates from two sources and can be divided into Prenatal and Postnatal Jing.

PRENATAL JING

Prenatal Jing is also called Original Essence (Yuan Jing). It is inherited from the Jing of both parents and is considered the root of life. It is created upon conception through the blending of both parents' sexual energies and substances. Prenatal Jing constitutes the original substance of the body, and serves as the material base for growth, development, and reproduction. With the help of the Qi and Blood acquired from the mother, the Jing is responsible for the nourishment and development of the embryo's and fetus's brain, bones, muscles, tendons, skin, and hair. The Pre-


Prenatal Jing
(from both parents)
Yang aspect of Jing
Activates transformation, growth, development and reproduction.
Yuan Qi
(Original Qi)
Jing
(Essence)
Brain
Postnatal Jing
(from food and drink)
Yin aspect of Jing
Provides the material basis for growth, development and reproduction.
Marrow
Bone Marrow
Blood

Figure 13.4. The Formation of Jing

natal Jing determines each person's basic constitution, strength, and vitality.

POSTNATAL JING

Postnatal Jing is also called the Acquired Essence. It is the Essence of the body's main organs, derived from air and Gu Qi (produced from food and drink by the transformation process of the Spleen and Stomach) which is transported through the channels and vessels to nourish the body's Yin organs, and to irrigate the Yang organs. Postnatal Jing is the material basis for the functional activities of the body's internal organs and metabolism. It is transported (through the function of the Lungs) to all the Yin and Yang organs where it becomes reproductive Yin and Yang Jing. The Kidneys are responsible for storing any surplus Jing to be distributed when needed.

THE INTERACTION OF PRENATAL AND POSTNATAL JING

The Prenatal and Postnatal Jing are interdependent and contribute equally to the growth and development of each other. Postnatal Jing is continually being used by the body and replenished with food and drink. Only with the nourishment of the Postnatal (Acquired) Jing can the Prenatal (Congenital) Jing be enriched and function optimally. Without the function of the Prenatal Jing, the Postnatal Jing cannot be transformed into Qi.

Postnatal Jing is continually being used and replenished through the Spleen's production of Gu Qi from food and drink. This is why so much emphasis is placed on the first postnatal alchemical transition of changing Jing into Qi. Through Medical Qigong exercises, the body is able to stimulate, nourish, and preserve its Jing.

Both Prenatal and Postnatal Jing are related to the Kidneys, which generate bone growth as well as nourish the brain, memory development, and body stamina. The *Yellow Emperor's Classic of Internal Medicine* states that women are on a seven year developmental cycle, while men are on an eight year cycle. Problems with the body's Jing result in developmental problems (i.e. improper maturation, sexual dysfunction, infertility, and premature aging).

The Kidney Jing is responsible for extending the life-force energy up the Governing Vessel into the brain. The Kidney Jing also transforms into Marrow and is responsible for the production of bone marrow, which fills up the spinal cord and brain. When the Jing becomes exhausted, the memory begins to fail and the spirit becomes fatigued. It is important to remember that all types of Jing do not exist as separate substances, but support, interact with, and transform into one another.

The Kidney Jing also works in conjunction with the Qi to establish the body's state of mind and emotional health, which together determine the development of the Five Elemental Constitutions.

QI: VITAL LIFE-FORCE ENERGY

Qi is the energetic substance from which the entire universe was created. Through the interaction and transformation of Yin and Yang Qi, the various substances of form and matter are produced. This vital life-force energy comprises both material and functional aspects of the body.

Qi is the medium between matter (Jing) and Spirit (Shen). Chinese medicine describes many different kinds of Qi. Qi can assume an infinite number of forms according to its state of condensation or dispersion. When Qi condenses, matter is created, and when Qi disperses, energy is created. Although Qi in the body can assume different forms, that have different functions, it is essentially all one energy. The patient's Jing, for example, may be ready to receive a new energetic pattern for accelerated healing, and the Shen may be ready to send this required pattern. But, if the body's Qi is weak or turbulent, it will not transmit this information from the Shen to the patient's Jing, thus delaying or impeding the healing process.

The body's Qi can be classified into two primary forms of energy: Prenatal and Postnatal Qi.

PRENATAL QI

Prenatal Qi (or Xian Tian Zhi Qi, which translates as, "before the baby sees the sky energy") is also called Yuan Qi, or Original Qi. This is the energy that the baby inherits from his or her parents during conception. It is stored in the sexual glands and adrenal cortex, and it is essential for the growth and development of the fetus.

It is Jing in the form of energy, that is cultivated through Qigong practice. Yuan Qi is the innate or inborn energy that is the original force which maintains normal growth and development, and promotes the functional activities of the internal organs. Its role is to bring into existence the vital mechanisms of the human body according to their genetic pattern, conforming them to the models transmitted by each person's lineage.

Prenatal Qi contains elements of all of one's predecessors and gives rise to the Prenatal Jing, and is seen as a means of transmitting the Deoxyribonucleic Acid (DNA) code. Prenatal Qi relies on nourishment from Postnatal Jing. Through Prenatal Qi, each individual is energetically connected with everything in existence. Prenatal Qi also relies on Postnatal Qi for nourishment.

Methods of training Qi and regulating it include counting respirations as the Mind focuses on rooting the Qi into the Lower Dantian, Mingmen, or Kidneys' area.

There are three types of prenatal energy regulations used for circulating and harmonizing the body's internal energy or Dantian Qi:

1. The first type of Qi regulation focuses on moving energy through the body's main channels and torso. This is the most common type of Prenatal Qi circulation, directing the energy to flow along the course of the body's Conception and Governing Vessels, i.e., the "small" Heavenly cycles (Microcosmic Orbits). This type of Qigong exercise is commonly referred to as an Inner Cultivation and Regulation method.
2. The second type of Qi regulation focuses on moving energy through the body's channels and extremities. In this type of Qi circulation, the body's Prenatal Qi is directed to flow only along specific channels (i.e., being led from one channel out from the torso into an extremities and then back into the body through another channel). This type of energetic balancing is commonly seen in the "large" Heavenly cycles (Macrocosmic Orbits) and bone marrow regulation.
3. The third type of Qi regulation focuses on

moving the energy of Heaven (Universal Qi), Earth (Environment Qi) and Man (Qi of the physical body) through the channels. In this type of circulation, these three types of energy are integrated or merged into one energy and then regulated. Upon inhalation, the individual imagines Prenatal Qi circulating from Heaven through the body's channels into the Earth. Then upon exhalation, the energy is imagined flowing from the Earth, through the channels, back into Heaven.

POSTNATAL QI

Postnatal Qi (or Hou Tian Zhi Qi, which translates as, "after the baby sees the sky energy") is also called acquired or Post-Heaven Qi. This is the energy that the baby derives from air, food, and drink after it has been born. Postnatal Qi relies on Prenatal Qi for development.

Prenatal and Postnatal Qi form the foundation for the body's vital energy. In Traditional Chinese Medicine it is believed that the parents' health and their state of Jing, Qi, and Shen at the time of conception determines the general health of the child. If the parents are sick, or their health has is compromised by drinking, smoking, or drug use, the baby's health will suffer. If the parents are old, or have suffered an emotional shock during the pregnancy, this too will negatively impact the baby's health.

Methods of training Postnatal Qi include deep, tranquil abdominal respiration. This method trains the respiratory system to improve both the respiratory and digestive systems, enhancing both the Lung and Spleen Qi.

EIGHTEEN CLASSIFICATIONS OF QI

The distribution and function of life-force energy can be further divided and classified according to the source and function of the Qi. Below is a description of eighteen transitions of Qi and their energetic effects on the body.

1. Prenatal Qi (Yuan Qi), is often referred to as Original Qi, and includes the Original Yin and Original Yang energies of the body. Yuan Qi has its root in-between the Kidneys and Mingmen area, it is distributed throughout the entire body via the Triple Burners.
2. Postnatal Qi, is an external energy derived from the consumption of food and drink (from the Earth), and air (from the Heavens), and is a term used to describe the Qi which is cultivated after one is born.
3. Heavenly Qi (Tian Qi), is energy that has been developed from the energies of the sun, moon and stars. Tian Qi is absorbed into the Lung Qi as Air Qi (oxygen) through respiration.
4. Earthly Qi (Di Qi), is energy that has been developed from the energies of the soil, water and wind. Di Qi is absorbed into the Stomach and Spleen where it is converted into Gu Qi (food energy); Di Qi is also directly absorbed through the pores from the environment.
5. Food Qi (Gu Qi), is the first stage of energy transformation derived from food and drink. It is also called Qi of the Water and Grain in the digestive system. After food essence is cooked in the Stomach, the Spleen transforms it into Gu Qi. At the first stage of development Gu Qi is a coarse, unusable form of food essence. The Spleen divides the energy it derives from the food essence into Pure (Clear) Yang Qi and Impure (Turbid) Yin Qi. The Clear Yang essence of Gu Qi is transported by the Center Qi (Zhong Qi) via the Middle Burner, sending it upwards into the chest, first to the Lungs where it combines with Heavenly (Tian) Qi to form Gathering (Zong) Qi, then to the Heart where it combines with the Yuan Qi (from the Kidneys) to create the Blood. The Turbid Yin essence of Gu Qi is transported downwards through the gastrointestinal tract to be expelled as waste.
6. Clear Yang Qi (Qing Qi), is the clean, pure energetic essence of Gu Qi, transported by the Spleen, via the Middle Burner, up towards the Upper Burners, and chest area. While in the chest, it is combined with Gathering (Zong) and Yuan Qi to form True Qi.
7. Turbid Yin Qi (Zhou Qi), is the clouded, impure energetic essence of Gu Qi, transported by the Spleen, via the Middle Burner, down

towards the Lower Burner, Small Intestine, and Bladder organs, to be further refined. It is a more coarse, unrefined, polluted energy.

8. Center Qi (Zhong Qi), is the energy generated from the Middle Burner, derived from the Spleen and Stomach. Its primary function is to transport the Gu Qi into the chest, to be blended with the Heart and Lungs' Qi.
9. Gathering Qi (Zong Qi), is also called Respiratory Qi. Gathering Qi is considered the "essence of life," manifested through the conversion of the purest and most potent forms of the body's Jing (particularly sexual fluids, hormones, and neurochemicals). It is essential for the formation of the fetus and is the initial motivating power of life. It promotes vitality and increases stamina; it also enhances the immune system, promotes mental clarity and prolongs life. Gathering Qi combines the Heavenly Qi (inhaled by the Lungs) and the Gu Qi (derived by the Stomach and Spleen), and accumulates these energies within the chest in order to assist the Heart in circulation the Blood, and the Lungs in respiration. It controls the speech and strength of the voice, as well as the Blood circulation to the extremities. Gathering Qi gathers in the chest and is controlled by the Middle Dantian.
10. True Qi (Zhen Qi), is also called Anti-pathogenic Qi. It originates in the Lungs and is the last stage of refinement and transformation of Qi. Gathering Qi and Yuan Qi combine their substances to form the True Qi in the chest area. True Qi fills and nourishes the body as it is further broken down into Nourishing (Ying) and Protective (Wei) Qi. True Qi is the energy that circulates inside and outside of the body, in the channels and collaterals, nourishing the Yin and Yang organs. It is called True Qi because it is the most refined and pure, and is in harmony with the environment. It is opposed by Evil Qi (Xie Qi), also called Toxic Qi, which is disharmonious and thus untrue to the body's essential nature.
11. Nourishing Qi (Ying Qi), is another form assumed by the True Qi and is the Yin aspect of the Channel Qi. Ying Qi has two major functions: to nourish the Blood, organs and tissues, and to link the mind and intention to the body. It flows within the blood vessels, as well as the channels, and is the fuel of the body's metabolism. Its potency depends upon the quality of food and water consumed, the purity of air breathed, and the efficiency of the body's digestive, respiratory, and circulatory systems. Since it is Yin, it is considered the more refined form of True Qi, as it flows in the body's inner layers and internal organs. Being directed by thoughts, it is thereby closely related to the emotions.
12. Protective Qi (Wei Qi), is a second form of True Qi and is the Yang aspect of the channel Qi. It protects the Blood, organs, and tissues from invasion of external pathogenic factors such as: harsh weather conditions, microorganisms, and harmful emotional influences. It also protects the individual from evil spiritual forces. It is the coarser Yang aspect which flows through the outer layers of the body's skin. Its texture is slippery in nature and cannot enter into the channels. It therefore circulates under the skin and in between the muscles. The Wei Qi vaporizes in between membranes, and diffuses over the chest and abdominal area to form a kind of energetic armor. It also warms, moistens, and contributes to the nourishment of the skin and muscles. The Wei Qi also helps regulate the perspiration by opening and closing the pores.

   Wei Qi has its root in the Lower Burner (Kidneys), is nourished in the Middle Burner (Stomach / Spleen), and spreads from the Upper Burner (Lungs) to the outside of the body. Wei Qi is said to be located at the superficial level of the body during the day, in the muscles, skin, hair, etc. At night it sinks to a deeper level to circulate through the viscera. If the Wei Qi is obstructed in some manner from moving inward, insomnia may result. Also, Wei Qi becomes thick and extends outside its normal realm during Medical Qigong practice and may, therefore, take longer to move inward at night, causing some practitioners to experience difficulty falling asleep after evening Qigong practice.

13. Channel Qi (Jing-Luo Qi), is also called Meridian Qi. This energy flows throughout the body's deep internal and superficial channels, as well as through the collaterals and blood vessels like rivers and streams.
14. Organ Qi (Zang and Fu Qi), is the energy of the physiological activity of the body's internal organs and manifests as a major aspect of its physiological function. Individual pools of Qi are formed within the pairs of Yang-Fu (hollow) bowels and Yin-Zang (Solid) viscera. The Yang organs are responsible for transforming food and drink to produce Qi and Blood. The Yin organs are responsible for storing vital substances. Each organ can be additionally divided into pairs of Yin and Yang energetic aspects.

    Each of the body's organs has its own energy, which is governed by, and corresponds to, one of the Five Elemental energies. These Five Elemental energies respond to the external energetic fields drawn from the universal and environmental energetic fields. The internal processes of thinking and feeling, as well as the physiological process such as metabolism and hormonal production influence the Organ Qi.
15. Evil Qi (Xie Qi), is also called Pathogenic Qi, and Toxic Qi. This usually refers to any harmful external pathogenic factor (especially the Six Climatic factors). However, it also refers to the evil spirits and stuffed toxic emotions, which affect the individual's physical, energetic, and emotional balance.
16. Righteous Qi (Zheng Qi), is the defensive aspect of the True Qi, which protects the body from Evil Qi. This is not actually another type of energy, but a term used to indicate the True Qi's function of protecting the body from invasion by external pathogenic factors. The occurrence and development of disease is directly related to either the hyperactivity or hypoactivity of the Righteous Qi.
17. Spiritual Qi (Ling Qi), is the supernatural energy associated with the most highly refined energy in the human body manifesting through the Eternal Soul. This type of energy enhances spiritual awareness and constitutes the foundation for advanced levels of spiritual conditioning, and the attainment of an enhanced energetic body, and enlightened states of mind and spirit.
18. Divine Qi (Shangdi Qi), is also called Holy Energy or God's Healing Light. It is the supernatural energy associated with the Divine (Dao). The divine energy is the true source of spiritual awareness and constitutes the foundation for advanced levels of spiritual healing, as well as attaining enlightenment.

THE SIX FUNCTIONS OF QI

A Qigong doctor will primarily focus on a patient's combination of Original Qi (Yuan), Gathering Qi (Zong), Nourishing Qi (Ying), and Protective Qi (Wei) when treating or prescribing homework. Initially, Qi has six main functions in regulating the body. Although these functions may seem to overlap, their individual responsibilities are distinct.

1. Qi transforms substances into energy (one example of its transforming nature is changing food into energy).
2. Qi transports the substances it creates.
3. Qi holds and contains energy, Blood and organs, etc., within the energetic and visceral structures.
4. Qi protects against both external and internal pathogenic factors.
5. Qi raises and elevates things (for example, Blood, associated Fluids, and the body's temperature).
6. Qi keeps the body warm (for example, strong Qi will warm the body, while weak Qi makes the body cold).

The normal physiological activity of Qi in the body is a constant harmonious movement, similar to the ebb and flow of a tide. When the body's Qi is in constant motion, it moves in eight primary Yin and Yang directions: ascending and descending, gathering and dispersing, expanding


Sun, Moon, Stars
Environmental Qi
Soil, Water, Wind
Heaven Qi
Tian Qi
Earth Qi
Di Qi
Intestinal Tract
Bladder
Skin,
Muscles,
Tears,
Sweat,
Saliva,
Mucus
Center Qi
Zhong Qi
Stomach
Food
Drink
Triple
Burners
Body Fluids
Jin
Lungs
Food Qi
Gu Qi
Spleen
Turbid Yin Qi
Zhou Qi
Body Liquids
Ye
Gathering Qi
Zong Qi
Clear Yang Qi
Qing Qi
Nourishing Qi
Ying Qi
Joints,
Lubricate
Sensory
Organs
Heart
True Qi
Zhen Qi
Channel Qi,
Blood Vessels,
All Organs
Kidneys
Blood
Xue
Bone
Marrow
Marrow
Sea of Sui
Jing
Original Qi
Yuan Qi
Protective Qi
Wei Qi
Muscles,
Skin,
Outside,
Channels
Brain
Spinal Cord
Prenatal Jing
Yuan Jing
Postnatal Jing
Righteous Qi
Zheng Qi
Protects
against
Evil Qi
Heaven Qi
Tian Qi
Kidney Yin
Mother's Ovum
Jing, Qi, Shen
Yuan Jing
Father's Sperm
Jing, Qi, Shen
Kidney Yang
Moistens &
Nourishes
all Organs
Earth Qi
Di Qi
Mingmen
Warms and
Activates all Organs

Figure 13.5. The Body's Intricate Interactions of Qi, Blending and Flowing through Internal Reservoirs of Pooled Energy.

and contracting, and entering and leaving. If however, there develops a Qi obstruction, or a Deficiency of Qi, the Qi will deviate from its natural course, and may cause Rebellious Qi, disharmony and disease.

Qigong doctors carefully examine the energetic ebb and flow of Qi to comprehend the complexity of the energetic hologram in which we exist as a living energy. As the human body absorbs, stores, utilizes, and releases energy, its natural function of transforming energy promotes health and allows us to live in harmony with the natural environment. However, once an internal organ or organ system develops a Rebellious, Excess, Deficient, or stagnant condition within the body's energetic flow, disease develops. By understanding the energetic pattern and function of each energetic organ and organ system, the Qigong doctor can diagnose the disease by retracing the energetic dysfunction to the root cause. The following graph denotes the function and flow of the body's life-force energy patterns (Figure 13.5).

QI AND ENERGETIC MEDICINE

The utilization of the Three Regulations (posture, respiration and mental Dao Yin concentrations) enable Qigong doctors not only to disperse any Toxic Qi acquired from patients, but also to regulate their own channels, through gathering energy, and increasing their own energetic fields. Through the proper use of the Mind (whole body consciousness and awareness), the doctor can simultaneously influence the energy flows within the patient's body, as well as his or her own Wei Qi fields.

As the doctor begins to focus on specific goals (i.e., dispersing Toxic Qi from a particular organ, tissue area, or channel), the patient may experience a surge and release of strong emotions and memories that had been stored in that area. The patient's energy field then shifts and moves throughout the body according to the specific emotion(s) elicited and released. This energy field is closely related to the thinking activities of the brain. As the Mind begins to release certain specific memories, the field of energy shifts and moves through the body in accordance with the specific emotions that are activated and released. During treatment, the shape, flow, rhythm, nature, and thickness of this energetic field can be perceived by the doctor who has become highly sensitive to perception of energy through "inner-vision" (see Chapter 25).

By training in the Three Dao Yin Regulations (see Chapter 14), internal energy can be guided to surge not only in the natural direction of flow within the channels, but also against it. Internal energy can also be guided along several channels at the same time, in any given direction or to specific areas of the body. By directing Qi against the flow of a channel, the doctor arrives at the source of the river (or energy). This technique is sometimes used by the Qigong doctor to collect or tonify the Qi within the patient's internal organs. This technique for storing and collecting energy is called "following the river to reach the sea." An example of this technique would be extending Qi from the patient's St-36 points, up the Stomach Channels to root, strengthen and stabilize a Deficient or Rebellious condition within the Stomach organ itself. Conversely, by directing Qi with the flow of the stream, one can disperse energy (purgation) and pull Qi out of an area leading it away from the source (e.g., pulling Liver-Stomach Heat down and out the Stomach Channel to cool an overheated Stomach).

QI AND THE BODY'S ENERGETIC STRUCTURE

Similar to the biomechanics of the respiratory, circulatory, and digestive systems, the body's energetic system has its own organization and established rules of action for regulating organ and tissue functions. The adaptability of Qi to the outside environment enables the body to absorb not only healthy energy, but also to expel Toxic Qi.

The nature of Qi is to endlessly gather and disperse, expand and contract, to flow inward and outward, to rise and fall, as it circulates. When a Qigong doctor begins to treat a patient's channels or points, he or she stimulates and activates the patient's Qi, which may arouse muscle movement and sensations which can last for quite some time.

If the frequency and nature of the doctor's Qi is similar to that of the patient's, both energetic resonance and synchronization will synergize, allowing the patient's Qi activities to be regulated and balanced at a rapid rate.

Because people vary in sensitivity to energy, some patients can be treated with Medical Qigong therapy immediately. Sensitive patients are usually taught Medical Qigong exercises allowing them to ingest energy from trees, plants, and other things of the natural world. Patients with low sensitivity may have difficulty in perceiving energy and often dissociate from their body during treatment. These patients should be given Shengong meditations to restore conscious awareness of the toxic emotions trapped within the body, thereby reestablishing a harmonious relationship with the Mind (see Chapter 32). The patient's insensitivity to the doctor's energy extension is an indication that the patient's spirit has gone out of the body in order to avoid feeling the emotions which arise from Medical Qigong therapy.

A patient insensitive to energy projection can still be in touch with basic surface feelings (i.e., hot, cold, tired, etc.); however, the deeper emotions are hidden, or energetically walled off through denial. The better the relationship between the patient and the doctor, the greater the patient's trust and surrender to the doctor's energy.

When observing the patient's Qi and energetic structure, the doctor is able to perceive and enter the patient's five energetic fields. These fields form the matrix of the patient's energetic structure, which constitute a blueprint for the body's physical structure. These energy fields have their own biological components and degree of fluidity.

These five energetic fields form the body's Sea of Energy. The term Sea of Energy (Qi), in this context, refers to the description used to explain the internal and external currents of life-force energy which surround, permeate, and function within the physical body. These energetic fields are described as follows.

1. The External Fields of Wei Qi (Protective Energy),
2. The Internal Current of Ying Qi (Nourishing Energy),
3. The Internal Sea of Blood (Xue Hai),
4. The Internal Sea of Marrow (Sui Hai), and
5. The Center Core of Light (Taiji Pole).

Within these five energetic fields, the protective and nourishing energetic fields of Wei and Ying Qi expand and contract, move and adjust their energetic flow according to the body's respiration patterns. The Sea of Blood resonates within the pulse rhythm established by the heartbeat. The Sea of Marrow undulates from the rhythm established within the body's micropulsation of the sacrum and cranium bones' flexion and extension. The energetic pattern of the Taiji Pole vibrates at the same frequency as divine light (the Dao).

THE THREE EXTERNAL FIELDS OF PROTECTIVE ENERGY (WEI QI)

There are three external energy fields that create the body's Wei Qi field. The Wei Qi field's energy flows from around the regions of the body's external muscles, skin surface, channels, collaterals and channel points, and extends several feet out from the body's tissues. All energetic forms of the physical body, including the internal organs, blood vessels, nervous systems, etc., can be accessed and treated through the three extended fields of Wei Qi.

These three fields are distinguishable from each other by gradations of density, vibrational rate, light, and temperature. All three energy fields communicate with each other, interacting so as to form the body's subtle energetic boundaries.

Enveloped within these energetic boundaries are the body's external "energetic grids," spanning the body's energetic structure like a giant web. These energetic grids are the body's external energetic field patterns, etched through the three fields of Wei Qi like a three dimensional webbed hologram (similar to a three dimensional blueprint).

It is important to note, that any disease within the body's internal structure is also imprinted in this external energetic grid. Disharmony of the body's tissues often appears first in the Wei Qi fields, before manifesting within the body. If the energetic grid is not transformed (through emitted light, sound, and resonant vibration), the disease cannot alter its destructive course, because it follows the patterns dictated within the grid. Thus, for example, a tumor surgically removed often quickly reappears. Trauma, be it physical, mental, emotional, or spiritual, as well as drug and alcohol abuse, distorts, damages, and destroys the delicate energetic web which constitutes the body's external energetic grids, making the patient more susceptible to external environmental influences.

The external energetic grids function to protect the body from external pathogenic factors, as well as to receive and transmit environmental energy. Thus, for example, a person can receive, absorb, and digest other people's emotions. The five senses are constantly receiving on outside environmental influences, which directly and indirectly affect the body's major organs. This constant influx of data, changes the body's emotional patterns, and forces individuals to adjust their emotional perspective frequently.

Researchers conducting tests in San Antonio, Texas, for example, determined that when subjects are being stared at, galvanic skin responses are considerably increased. These increases occurred even though the subjects were not consciously aware of being observed. The research determined that the body has its own expansive field of subtle awareness, which reacts even when the individual is not consciously aware of the body's energetic extension.

By reconnecting the spirit and emotions with the mind and body, the Qigong doctor is able to perceive the subtle Messages that the patient is unconsciously conveying (see Chapter 25).

THE THREE ENERGETIC BARRIERS

The Wei Qi fields are experienced at three different levels. These levels are differentiated by energetic barriers, which protect the body's boundary system. These barriers not only protect and contain the body, they help establish the individual's sense of reality, and sense of self. The third energetic field or "outer spiritual barrier" is depicted in the illustration as the outside speckled field of energy, and affects the second energetic field or "middle emotional / mental barrier." The second field of Wei Qi is depicted in the illustration as the middle white field of energy, which in turn influences the first energetic field or "physical barrier," seen as the black field of energy in the illustration (Figure 13.6).



Figure 13.6. The Three External Fields of Wei Qi

These three Wei Qi barriers are always interesting for the doctor to feel, because they change so much from patient to patient, and sometimes from moment to moment. Some patients have very strong energetic fields, they are very palpable and full. Emotions strongly affect this type of energy field. The Wei Qi field of a patient who is armoring out of fear, reticence, or self-protectiveness, can actually repel the doctor's hand back, if their field and intention is strong enough. This repelling reaction is helpful because it lets the doctor know how to pace the treatment, and encourage the patient to let go of the armoring. This allows the patient to consciously focus on relaxing and sensing the areas in the body that he or she was trying to protect.

The energetic boundaries, act as gateways to the next level of energetic field energy. To perceive the patient's three fields of Wei Qi, the patient's energetic boundaries must be gently palpated. These boundaries are more easily sensed due to a thickening of energy which serves as a barrier to external pathogenic factors. Sometimes the doctor may have to move back into the patient's third or "outer" energetic field, and telepathically let the patient know that he or she will not be violated, and is safe. The doctor waits until the patient exhales (thereby expelling some tension) before entering and palpating the outer Wei Qi field. Once a release in the energetic field is felt, the doctor moves forward into the next energetic field. Because this same process occurs at all three levels, the Qigong doctor responds accordingly, waiting for the exhalation that allows them to proceed deeper into the next level of the patient's Wei Qi.

THE FIRST EXTERNAL FIELD OF WEI QI

The first external field of energy is confined to about one to two inches outside the physical body, and composed of lower etheric matter. It is related to the Lower Dantian and manifests as a holographic energy template for the physical body. It provides the spatial guidance for morphological development during the creation and formational stages of the embryo, as well as the morphological energetic patterns that assist in the repair of damaged tissues. Its energetic boundary is responsible for armoring the body against invasion of external pathogenic factors. This physical energy body is connected to the somatic tissues and cells, thus any physical-energetic interaction stimulates the body's external channels and points. This first layer is very dense and most Qigong doctors get the impression of physically contacting the patient several inches before actually touching the patient's material body. Its resonant vibrational pattern is very broad and slower than the other Wei Qi fields.

THE SECOND EXTERNAL FIELD OF WEI QI

This energy flows through the regions of the internal organs and tissues. It extends about a foot or more outside the body's tissues, and is composed of astral matter. It is related to the Middle Dantian and the emotional energy body. It contains a form of disembodied consciousness that can astral travel, and at times leave the physical body, as in near death experiences. This second layer of Wei Qi interfaces with the limbic system of the brain (the neurobiological seat of emotions) and is also linked with the sympathetic and autonomic nervous system. The second Wei Qi field's energetic boundary is responsible for protecting the body from negative emotions, destructive feelings and criticism from others. It is automatically activated when the patient is placed in a position where a lack of trust exists, or there is unwanted physical touch. The emotional energy body is connected to the visceral organs. Its main function is to receive, interpret, and verify an individual's emotions, feelings, desires, impulses, and thought patterns. It is through this energetic field that the patient's aura is typically observed as colors and light patterns. The second layer is more subtle then the first layer. When physically palpating, the sensations are similar to a magnetic attraction and repulsion. Its resonant vibrational pattern is faster than that of the first layer.

THE THIRD EXTERNAL FIELD OF WEI QI

This field extends a few feet to several hundred yards depending upon the spiritual evolution of the individual, and is composed of ketheric matter or substance. It is related to the Upper Dantian and the spiritual energy body. It is associated with intuition, inspiration, creativity, and visionary insights. Its energetic boundary is responsible for establishing security by informing the body of impending encounters, conflicts, or environmental transitions. This spiritual energy body is connected to the body's Taiji Pole, and is a container for karmic-related illnesses within the physical body. The Taiji Pole is known as the "root with many branches," as it is a repository of the soul's ancestral memories and experiences. Its function is to receive the subtle energy of the finest and fastest vibrations. It senses and interprets the data received from its environmental awareness and universal connection to the divine. The third layer is most subtle in physical sensations and requires delicate, intuitive contact. Usually the first impression when palpating this energetic field, is one of contact without a material component (like wind). It is sometimes cold, sometimes warm but always "breezy." Its resonant vibrational patterns are the highest and fastest of all the Wei Qi layers.

INTERNAL CURRENT OF NOURISHING ENERGY (YING QI)

The Ying Qi level of internal energy flows within the underlying tissues of the body and sweeps through the torso like a fast wind, expanding and falling with each respiration (Figure 13.7). The Lungs act as a great energy pump; each breath is like a gust of air flowing in and out, in a cycle of expansion and contraction through the entire body. Ying Qi swirls like a breeze; its function is to nourish the Blood, organs and, tissues. It flows within the blood vessels, as well as the channels and links the mind and intention to the body. It is responsible for the organization, construction, completion, and reconstruction of the vitality of the individual. It is integrated with the breath, and extends outward to the body's physical boundaries (skin and body hair).

The internal current of Ying Qi is most palpable when the doctor is gently touching the patient's surface tissue with his or her finger tips, and it feels almost like electromagnetic energy. Feeling the wind of Ying Qi can be likened to falling into "space" after passing through the denser outer field of Wei Qi. The action of Ying Qi, in most cases, is free flowing and connected with the breath. When listening to certain patients, the Qigong doctor may feel the Ying Qi flowing through the patient's channels, wrapping itself around the whole body like a vapor. It feels light, thin, and fairly cool compared to the next River of Blood level.

To access the "current of Ying Qi," the Qigong doctors begin by suspending their hands above the patient's first level of Wei Qi. They imagine dipping their hands into water as they allow their hands to slowly make contact with the patient's body. Once contact is made, the doctors extend their intention under the patient's skin. The doctors should match the patient's respiration and stay connected to the body until they feel the patient relax. Matching their respiration almost always slows the patient's respiratory rate, moving the patient into an altered state of consciousness. Sometimes at this point, age regression can be sensed, as the patient's body memory is triggered.



Figure 13.7. The internal current of Ying Qi flows from the Lungs and center of the chest through the entire body like a mighty wind.

SEA OF BLOOD (XUE HAI)

The Sea of Blood and its pathways constitute the body's internal network for circulating and maintaining the individual's life-force, under the direction of the Wu Jing Shen (the five separate fields that encompass the psycho-spiritual energetic transformations of the Five Yin Organs). The

Sea of Blood's energy flows through the blood arteries, vessels, capillaries, and the tissues of the major organs (Figure 13.8). By extending further into the body, the Qigong doctor perceives the patient's Sea of Blood; it feels like a warm watery pool in the center of the Heart, and flows through the entire body. The transition from Ying Qi to Xue Qi (Blood Qi) is easy to detect.

The energetic sensation of Blood is more substantial than the Wei or Ying Qi. The Blood being a liquid, is a denser form of Qi, and flows through the vessels, organs, and channels propelled by the Ying Qi. It is thick (this thickness varies from person to person), warm and somewhat "slick." The Heart's energy itself feels warm, substantial, and very alive.

As doctors gently touches the patient's surface tissue with his or her fingertips, the doctor extends intention deep into the patient's Heart. Upon contacting the Xue Qi, the doctor immediately becomes connected to the heartbeat of the patient. In some cases, the pulsing will connect and merge with the doctor's own heartbeat. Once the doctors encapsulates the patient's Heart, the strong emotions emanating from patients will usually subside. These feelings may be replaced by sporadic spurts of emotions such as relief, peace, or comfort, which sometimes invite the doctor further into the patient. On the other hand, some patients may react with feelings of fear, intense emotional pain, or even panic causing the doctor's hand to "bounce" away.

If the doctor's energy is "bounced back," he or she should immediately disperse the energetic charge into the Earth for ground purposes. The doctor should then either move to a more superficial energy level within the patient's body, or extend Qi into the patient's thorax or extremities. This technique allows the patient to relax after experiencing a Heart energy discharge. Since the pulse is simply another form of energy, circulating, expanding, and contracting with each heartbeat, the doctor should be able to ride the pulse out into the patient's extremities and viscera by listening to the Heart. This is similar to the listening ability of a master acupuncturist who, when reading a patient's pulse, extends his or her energy and intention through the patient's channels and into the organ of the Heart to diagnose the strengths and weakness of its congenital formation and current condition.



Figure 13.8. The Sea of Blood flows from the Heart through the body like a dense form of Qi.

SEA OF MARROW (SUI HAI)

This energy flows through the central core of the spine into the brain and enters the center core of the bones. In Traditional Chinese Medicine, the Marrow is not the same thing as bone marrow, but the stage prior to becoming bone marrow. Marrow is the pre-substantial Jing that forms the matrix for bone marrow, the spinal cord, and the brain (Figure 13.9). This flow of Sea of Sui energy is much slower than that of the River of Blood. It flows from the Kidneys' Jing, into the center of the spine, brain, and bone marrow. It has sometimes been called the "cranio-sacral rhythm" in Western medical terminology, and can be accessed from anywhere in the body. The Marrow energy generally feels cool and slick or slippery, with a texture like soft silicone gel. Once contact is made with the Sea Of Sui, it is very easy to utilize this pathway and travel throughout the patient's body. Its rhythm is slow yet manifests as a strong energetic pulse.

As the doctor gently touches the patient's surface tissue by dipping in with fingertips, into the Sea of Marrow, he or she can project intention into the center of the patient's spinal column. This connects the doctor with the rhythmic pulse of the Sea of Marrow. It is from this pulse that the doctor can determine the strength of the patient's Original Essence (Yuan Jing), Energy (Qi), and Spirit (Shen).

THE CENTER CORE OF LIGHT (THE TAIJI POLE)

This energy flows through the very center core of the body, uniting the three reservoirs of life-force energy (the Upper, Middle, and Lower Dantians). The fifth and final level of energy feels like a still, quiet place deep inside of the center core of the body's Taiji Pole structure. In China, Qigong doctors describe it as a holy place that almost defies description. It is observed as a vertical column or pole, of brilliant white light, full of pulsating vibrations. This energetic pole is surrounded by a vale of gold spiralling light which travels from the perineum to the top of the head.

When both the body's internal and external energetic wave patterns become synchronized through prayer or meditation, a resonate pulsation occurs within the Taiji Pole. This pulse begins deep within the center core of the body and resonates outward towards space. The Qigong doctors may also feel a powerful stream of energy leaving the body from the top of the head, connecting the Taiji Pole with the energy of the divine. The center core is a very reverent and special place, as it contains the essence of the patient's Eternal Soul, devoid of all ego, masks, or defense mechanisms (the patient's True Self).



Figure 13.9. The Sea of Marrow flows from the kidneys through the spinal cord, brain, and bone marrow.

If the doctor penetrates the outside veil surrounding the patient's Taiji Pole, and extends his or her intention into the light's center, the doctor experiences the sensation of falling into space, or stretching out into eternity. Sometimes the sensation of shooting through space is followed by flashing colors and moving shapes, as the surrounding core dissolves into the Void (Wuji) itself. This same sensation and experience can also be personally accessed through deep prayer and meditation, and is quite a normal phenomena within deep spiritual practices (Figure 13.10).

SHEN: THE SPIRIT OF LIFE

The Chinese character ideogram for Shen is formed to symbolize "that which drops from the sky," and "that which passes through the body." In Medical Qigong therapy, Shen is considered the subtle energy of the spirit, associated with the Heart. It is associated with the spiritual energy and has a radiant nature.

When energized, Shen flows upward like fire, extending through the body's Eight Extraordinary Vessels creating a healthy nervous system. When Shen is gathered in the Upper Dantian, it can be projected as light and energy through the eyes, and the Yin Tang (Third Eye) point. According to Traditional Chinese Medicine, all illness has spiritual roots. The Shen (Spirit) is regarded as an integral part of the diagnosis and treatment process. An old Chinese saying states, "When the Shen is abundant there will be cheerfulness, when it is insufficient there will only be dullness and sorrow."

Shen is developed from Jing and Qi. According to Medical Qigong theory, when the patient's Shen is strong the individual is able to lead energy to an injured area and speed up the healing process. This strong Shen energizes the Qi, enabling it to increase cellular production. When Shen is scattered, the functions of the human body are weak from fatigue, the Shen becomes unsettled, and the mind restless. When the Shen and Qi combine together they form a solid connection of light and vibrational energy. This union is utilized to infuse energy and transfer thought through intention. This can be achieved by either conscious or unconscious intent by the doctor.

SHENGONG SCHOOLS OF MEDITATIONS AND TRAINING

The Shengong (Spirit Skill) meditations emphasize the transformations of consciousness, as well as the development of perceptual insight and the birth of wisdom. From an ancient Chinese energetic perspective, the three primordial qualities of true wisdom, or divine universal consciousness are:

1. The experience of emptiness within the Wuji (the Void), corresponds to the manifestation of the primal virtue of Wisdom.
2. The light manifested from the Shen's luminosity, corresponds to the primal virtue of Love.
3. The life-force energy inherent in all things, corresponds to the primal virtue of Power.

In China, there are three major schools of Shengong training. These spiritual schools of Qigong are described as follows.



Figure 13.10. The body's center core Taiji Pole spreads from the base of the perineum to the top of the head.

- The Daoist School focuses on strengthening the body and mind equally with an emphasis on contemplating nature. Religious Daoism has its roots in Siberian Shamanism.
- The Buddhist School focuses on tempering the mind while giving little thought to the body.
- The Confucianist School focuses on regulating the mind to reach a state of quiet rest and peace through sincerity and the cultivation of moral character.

PRENATAL AND POSTNATAL SHEN

The body's Shen is the Supreme Yang aspect of the psycho-emotional components, the Heavenly Emperor or "master controller." It can be divided and classified into two primary forms through which the Spirit manifests: the Prenatal Spirit (Yuan Shen) and the Postnatal Spirit (Zhi Shen).

1. Yuan Shen is the body's spiritual element derived from Prenatal Jing (Yuan Jing) and Prenatal Qi (Yuan Qi). This aspect of the body's Shen is considered to be the intuitive Mind of the Dao. It is unborn and undying. It shines brightly and clearly. The Yuan Shen transcends conceptual thinking (which is the Postnatal aspect of the mind). It is immortal, unconditioned, primordial, and constitutes the mind's Yang nature.

   The Yuan Shen is produced and developed by the blending of both the male and female elements at conception (Body Fluids, Jing, Qi and Shen), and develops further with the nourishment from food and water. The Yuan Shen dominates all of the body's vital activities (heartbeat, digestion, motor function, etc.) and is also responsible for all intuitive and perceptive insight. The Prenatal Shen constitutes the true spiritual aspect of the Mind.

   By returning to a state of inner quiet and peace, through prayer, meditation, and adequate sleep, the Yuan Shen and the body's health are restored and maintained.
2. Postnatal Spirit (Zhi Shen) is the spiritual element derived from Postnatal Jing and Postnatal Qi. This aspect of the body's Shen is considered to be the conditioned mind or "will," also known as the discriminating, or acquired mind, and constitutes the mind's Yin nature.

   The Postnatal Shen is produced and developed by mental stimulation through contact with the environment after birth. The Postnatal Shen dominates all mental activity and is responsible for thinking and learned behavior. The Postnatal Shen constitutes the true analytical aspect of the mind.

   Prenatal and Postnatal Shen usually interact intermittently with each other in maintaining the body's health. Continual exhaustion of the Postnatal Shen impairs and suppresses the Prenatal Shen. Excessive studying or sleep depravation, for example, can lead individuals to mistake the projection of their deepest fears and desires for genuine intuitive perceptions.

THE FIVE SPIRITUAL ASPECTS AND YIN ORGAN COMPONENTS OF SHEN

Prenatal Shen affects the spiritual disposition which presides over man at the moment of conception. Closely tied to the Yuan Shen are five important, although seldom discussed outside of China, energies or "spiritual entities" called the Five Agents (see Chapter 2). The function of the Five Agents establishes the foundation for the psychological aspect of the Five Element theory used in clinical diagnosis throughout China today.

Each of these Five Agents is connected to, or said to "reside in" one of the Five Yin Organs. The Three Hun reside in the Liver and embody the virtue of Kindness, the Shen resides in the Heart and embodies the virtue of Order, the Yi resides in the Spleen and embodies the virtue of Trust, the Seven Po reside in the Lungs and embody the virtue of Integrity, and the Zhi resides in the Kidneys and embodies the virtue of Wisdom (Figure 13.11). Whereas each of the Five Agents embodies a virtue, each of the Five Yin Organs embodies the energetic qualities of one of the primordial elements. The Liver embodies the element of Wood, the Heart embodies the element of Fire, the Spleen embodies the element of Earth, the Lungs embody the element of Metal, and the Kidneys embody the element of Water.

Each of these Five Agent energies are connected to the five separate yet functionally interactive Yin organs, and thus create complex, multidimensional energy fields (Figure 13.12). These energy fields encompass emotional, mental, and spiritual shifts, as well as energetic transformations. The fluctuations depend upon which of the Five Agents is dominating from moment to moment. The psycho-spiritual attributes engendered are sometimes known as the Wu Jing Shen (Five Essence Spirits). As the universal energy flows through the Taiji Pole, these Five Agents are continuously being energized. The cultivation of the five virtues of these Five Agents nourishes the Eternal Soul.

The Qigong doctor needs to comprehend these multidimensional interactions to trace the complex spiritual, mental, emotional, and physical manifestations of Excess or Deficient conditions to the source or "root." Although Jing and Qi form the physical basis for the Shen, the Five Elemental Yin organs form the components for the Shen and the Five Essence Spirits. The energy of the Five Agents continually circulates through the patient's body, and are described below.

THE LIVER STORES THE ESSENCE SPIRIT "HUN"

The Liver stores the Three Ethereal Souls, also called the Hun. The Hun or Three Ethereal Souls are rooted in the Liver Yin (which includes the Liver Blood). The Liver organ is responsible for the free and easy flow of Qi throughout the body.

The Hun are typically characterized as the Yang, brighter, Heavenly souls. It is through the influence of the Hun that the five virtues of the Five Agents manifest. The Hun leave the body, ascending back to Heaven at the time of death. The ideogram for the Three Hun has two parts. One part is the character for Earthly spirits-Gui (Ghost), represented by a head suspended above a vaporous form of a body, with an appendage (symbolizing the whirlwind that accompanies the movements of the Earthly spirits). The other part of the character is the image for clouds that are seen as vapor rising from the Earth and gathering in the Heavens. The Hun move within the body as freely as clouds, following the Yi (Will) of the "Heavenly breath, within the celestial vault" (following the will of the Eternal Soul stored within the Heart, and originating in the Taiji Pole).

Five Agents		**Yin Organs**	
志	**Zhi**	腎	**Kidneys**
意	**Yi**	脾	**Spleen**
魄	**Po**	肺	**Lungs**
魂	**Hun**	肝	**Liver**
神	**Shen**	心	**Heart**

Figure 13.11. The Five Agents and Yin Organs

From the ideogram we also get a distinct picture of the spirit rising to the Heavens. The Eternal Soul is different from the spirit in the context of classical Chinese theology, in that the soul is seen as the more personal of the two, whereas spirits are seen as more universal temperaments or as archetypes. The ancient medical classics say that there are Three Ethereal Souls (Hun) and Seven Corporeal Souls (Po) that symbolize different attributes of the human being. The Hun's spiritual energy is said to be able to leave the body and then return, thus indicating a relationship with out of body travel into the spirit world.

The Hun and Po are expressions of the body's "true spirit." When disorder exists (physical, mental, emotional, or spiritual), the Hun may sometimes fly away (like startled birds in a yard), and the Po will either stir about thoughtlessly, in the absence of effective control, or become animalistic in nature and attack.


Yuan Shen
Prenatal Shen
from both parents
(dominates all of the body's activities and is responsible for all intuitive and preceptive insights)
Zhi Shen
Postnatal Shen
from the interaction of Jing and Qi
(conditioned or acquired mind, dominates all mental activity and is responsible for thinking)
Yi
(Spleen)
Trust
Zhi
(Kidneys)
Wisdom
Shen
(Heart)
Order
The Five Agents
Hun
(Liver)
Kindness
Po
(Lungs)
Integrity

Figure 13.12. Formation of Shen

FUNCTIONS OF THE HUN

1. The Hun control sleep and dreaming. They reside in the eyes during the day and lodge in the Liver at night. When residing in the eyes, they see; when they lodge in the Liver, they dream. Dreams are the roaming of the Three Ethereal Souls. It is the nature the Hun to wander, and it happens easily. At night the Hun must be anchored or rooted in the Liver, so the Liver Blood and Liver Yin must be strong. If they are not, the Hun wanders, and the person dreams too much or has unpleasant dreams. Patients who suffer from severe Deficiency of Yin, may experience a floating sensation just before falling asleep. This condition is due to the Hun not being rooted in the patients' Yin.

   Dreams are an example of the information gathered during the Hun's traveling. The ancient Chinese Qigong masters understood that the body's Hun can traverse the Nine Levels of Heaven or Nine Levels of Earth instantaneously (see Chapter 2).

   The Hun store the sum total of past experiences. The expressions of the Three Ethereal Spirits are manifested through images, symbols and ideas from the divine and Wuji. These images, symbols and ideas emerge into the patient's mind, affecting his or her spiritual life. Without this interaction, the patient's mental and spiritual life would be deficient in images, ideas, and dreams.

   The Hun also controls dreams and daydreaming, as well as the ideals, aims, and direction in life. The absence of these objectives and goals results in feelings of depression. If the body's Liver Yin is depleted, the Hun are deprived of their residence, resulting in such conditions as: fear, excessive day dreaming, insomnia, and a lack of sense of direction or purpose in life (one of the main features of depression).

   Traditionally, sleepwalking is believed to be a function of the Hun. In sleepwalking, the body's Shen is not active and functioning, however the Hun are moving the individual. This is why when treating a patient for sleepwalking, the doctor will emit Qi into the patient's Hunmen Bl-47 (The Door of the Ethereal Soul). In modern research, however, some Qigong doctors have begun to theorize that the Po may take an active role in sleep walking, especially when the sleep state is related to incoherent trauma (patients who thrash about, hurt people, or destroy things when sleeping).

When using hypnosis or "creative visualization" in psychotherapy (the therapist may suggest a specific image or scene for the patient), the therapist is trying to bypass the patient's acquired mind and bring psychic material from the Hun, to avoid the judging aspect of the Postnatal Shen.

With regard to sleep and herbal medicine, if the patient does not sleep well because the Hun are wandering, the Qigong doctor can prescribe sour and astringing herbs (i.e., Bai Shao, Mu Li, Suanzao Ren) which will encourage the Hun back into the body.

2. The Hun assist the Shen in mental activities. This relationship is very important, as the energy of the Shen and the Hun must continually be coordinated. The Shen is related to rational thinking and inspiration. The Hun gives the Shen a sense of direction, projecting outwards, relating to other people. The Shen needs to direct the Hun, to "gather the Hun." The Hun give the Shen its movement and direction, encouraging the Shen to relate with people, to socialize and bond. The Hun, however, also need to be gathered and restrained by the Shen. Otherwise if the Shen is weak and does not control the Hun, then the Hun move about too much and have lots of ideas, but never accomplish anything, leading to frustration.

It is important that the Shen allow the Hun to move in and out of the body, but in so doing must give the Hun direction and purpose. The Hun inspire and give us dreams. That is why the words "movement," "coming and going," and "swimming" are often used in connection with the Hun. In fact, many doctors say that the Hun are the coming and going of the body's Shen. In mediumistic trances, when the spirit of one person enters another's body, it is the Hun that come in; the host's Shen is disabled at that time.

Because knowledge is dependent on the awareness of the Three Ethereal Souls, the Hun are therefore considered the collectors of information. The Hun however, do not interpret, rationalize or analyze the knowledge, they just pass the information on to the Shen, which is responsible for rational thinking, intuition, and inspiration. The Shen helps distinguish between the useful and non-relevant information.

There is an interesting correlation with the Hun controlling sleep and dreaming, and the Hun being rooted in the Liver Blood and Yin. The Hun's moving in and out of the Liver governs the free flow of Liver Qi and vice-versa; the free flow of Liver Qi is a manifestation of the swimming energy of the Hun, moving in and out of the tissues.

3. The Hun maintain balance in one's emotional life, under the leadership of the Shen.

Everyone experiences emotions in life; that is normal. The Hun are responsible for keeping a balance, so that the emotions do not become excessive and thus become the cause of disease. The Hun have a regulatory function, closely related to the balance between Liver Blood (Yin), and Liver Qi (Yang). The Hun's function here is the mental equivalent of the Liver's emotional regulating and harmonizing function.

Due to its acquired nature, the Postnatal Shen discriminates, while the Hun does not. The relationship between the Shen and the Hun is very similar to concepts of consciousness and unconsciousness in Jungian terms. The Hun are a repository of images and archetypes, connecting the (personal) subconscious mind and the collective unconscious. If the Hun are unsettled, then the Shen (consciousness) is cut off, confused, isolated, aimless, sterile, and without dreams. The movement of ideas within the body has to be controlled or it gets out of hand, resulting in madness. This madness occurs to the degree that the Shen doesn't control the Hun anymore, and the patient receives an uncontrolled amount of emotional, mental, and spiritual input. All the energies and symbols coming through the Hun have to be integrated and assimilated. Otherwise there can be serious mental illness and possibly psychosis (except in young children who are continually full of ideas and have active imaginations). In a child, the Hun are very active and the Shen is not as restraining, so there is a continual flow of energies streaming from the unconscious world of symbols, without the result of insanity.

4. The Hun are responsible for the eyes. When the Hun wander in through the eyes, the eyes can see. The Hun give us vision, both mentally and spiritually.
5. The Hun influence a person's courage. If the Hun are not strong, the person is timid and fearful. If the Hun are strong, the person is fearless, can face up to the difficulties in life and dares to take action. A patient with weak Hun will have difficulty gathering information, making decisions, will lack courage, and become easily discouraged and apathetic.
6. The Hun control planning with the aid of the Shen and the sense of direction. The mental and spiritual confusion about one's role in life, what to do, what goals to set, can be compared to the aimless wandering of the Hun. This is a strong feature of major depression. If the Liver is strong and the Hun are strong and rooted, the person has a strong sense of direction.
7. The Hun control Spirit Travel. By housing the Shen for "spirit travel" (the spirit journeying outside of the physical body), it is possible for the Qigong doctor to consciously direct the Hun's travelling. This is different than Astral Travel, which is the Eternal Soul journeying outside of the physical body, connected to the Middle Dantian by a silver "cord of life." The Three Ethereal Souls, accompanied by the individual's consciousness, act as one unit which is sometimes referred to as the Spirit-Soul. The Spirit-Soul allows the doctor to know the exact location of the "spirit routes" travelled, as well as which path and direction it takes when it leaves the body. Otherwise, when the Hun wonder, the doctor "Shens out" and has no recollection of where he or she has been in the spiritual realms.



Figure 13.13. Two Ways to Feed the Shen

THE HEART STORES THE ESSENCE SPIRIT "SHEN"

The Heart stores the Shen and is responsible for mental and emotional activity, intelligent consciousness, long term memory, and sleep. It is responsible for organizing mental concepts and activities, and has the capacity to judge.

The Shen is divided into two kinds of energies, Prenatal Shen and Postnatal Shen.

The Prenatal Yuan Shen is associated with the congenital spiritual energy that descends from Heaven. It is the universal divine spirit that is implanted in each person, uniting man to the spiritual realm (that which exists beyond the physical and mental reality). It has been compared to the "Christ within us," or "higher self." This is the energy Qigong doctors attempt to become filled with during sitting meditation practice and prayer.

The Postnatal or Acquired Shen is associated with the wisdom of the five senses and the acquired knowledge of the individual's experiences.

There are two ways to "feed" the Shen. One way is through dreams or unconscious information coming from the Hun of the Liver; the other way is through thoughts and ideas from the Yi of the Spleen (Figure 13.13). A person who has a well-developed, strong, and abundant Shen comprehends things immediately and is able to apply what he or she has learned.

The Hun give the Shen movement allowing the mind the capacity of self insight and introspection, as well as the ability to project outwards from the body and envelop, as well as relate to, other people.

THE SPLEEN STORES THE ESSENCE SPIRIT "YI"

The Chinese term Yi, is typically translated as mind, thought, opinion, idea, sentiment, inclination, intention, intellect, scholar mind, analytical thinking, and memorization in scholastic learning. Because the Spleen stores the Yi, it is responsible for the transformation and transportation of all thoughts and ideas on an intellectual level, through study, concentration, and memorization. This is different from the Hun's creativity. It is the interaction between the Yi of the Spleen and the Shen of the Heart that allows man to place how he thinks, speaks, and acts into sounds, thoughts, and actions.

Concerning memory, there is a lot of overlap between the functions of the Spleen (responsible for memory in terms of concentration and studying), the Kidneys (responsible for storing things on a day to day basis), and the Heart (responsible for storing past events).

The Postnatal Qi and Blood form the physiological basis for the intellect. A person with well-developed Yi has total recall of events experienced in their personal past, and is able to memorize things easily. A patient with an Excess of Yi will be obsessed with the past, while a patient with Deficient Yi will be absentminded, suffer memory loss, be inattentive, and have problems in maintaining concentration and mental focus. Although all physical pain is registered by the Po, and all psychological pain is registered by the Hun, only the memory of the pain is registered by the Yi (Figure 13.14). Therefore, a Deficient Yi condition can often lead to the phenomenon of transference and countertransference. Transference involves the incorrect attribution of certain emotions and intentions onto another person (usually onto the doctor by a patient). Countertransference involves the same type of projection of one's feelings, colored by one's own expectations in response. In countertransference, the doctor or therapist is doing the projecting.



Figure 13.14. Three Ways the Body Registers Pain

Yi also has the meaning of divine purpose when applied to the Yuan Shen energy. Whenever the physical energy is purified by self-cultivation and through connecting to the divine, the intention of the Shen and the divine purpose become one and the same. It is said when the Yi is conserved, it will help build the Zhi (or willpower). The Yi is filled with information from the past along with current knowledge and sensations.

THE LUNGS STORE THE ESSENCE SPIRIT "PO"

The Lungs store the Seven Corporeal Souls (Po), which are physical in nature and are attached to the body's Jing and Qi. The word Po is defined as vigor, animation, or life. There are two parts to the Po ideogram; one is the character for Gui, the spirits of the Earth, and the other represents the color white. Thus, the Po are linked with a descending movement of energy and with the Jing. The Seven Corporeal Souls are also said "to come and go, enter and exit," in association with the body's Essences.

In Medical Qigong therapy, the body's Eternal Soul is seen as being strongly influenced by two main divisions of internal spiritual energies, the Hun and the Po. The Hun are the Three Ethereal Souls and represent the positively charged aspects of the Eternal Soul, while the Po are the Seven Corporeal Souls and are considered the physical, negative, Yin, heavy, and Earthly aspects of the Eternal Soul. The Po are the counterpart of the Hun and can be described by its following six manifestations.

1. The Po are the somatic expressions of the Eternal Soul, related to the reflexive nervous system and limbic system (the "reptilian brain"). They manifest through the body's sensations of feeling, hearing, and seeing. They have an impulsive tendency towards action and correspond to the deep animal instincts within the Mind (personal subconscious) and cells (our reflexes are a Po reaction). The Po also provide us with the animal strength and resources necessary to mobilize the body and perform incredible feats of power. The "animal within" is driven by the Po. They are the manifestation of the body's Jing in the sphere of sensations and feelings. Just as the Three Hun provide the individual with the energetic movement for the Shen, the Po provides the individual with the energetic movement of the body's Jing.
2. The Po are responsible for all physiological processes in childhood. In the beginning of life, the Po are responsible for the sensations of pain and itching. The Po serve as the intermediary between the Jing and the body's other vital substances. At conception the interaction of the body's Jing not only forms the embryo, but also establishes the Po within the body. Although the Po are stored in the Lungs, they stay attached to the body until death, there upon returning their energy back to the Earth within a few days.
3. The Po are related to weeping and crying. The interconnection between the Po and Lungs is very important from an emotional point of view. When the Po's movement in the Lungs is constricted, grief and sadness are suppressed in the chest through shallow breathing.

   In the morning time, when waking, if the patient feels dull and depressed, it is a sign that his or her Shen is clinging to the body, i.e., the patient's Shen is clinging to the excessive energy of the Po.
4. The Po are closely linked to breathing. Because the Po reside in the Lungs, all meditation systems, breathing exercises, and forms of breath control are methods used to regulate the Po, calm the Shen, and access the higher Hun states. Breathing is the pulsation of the Po. Each emotional change the body experiences is related to a shift in the body's respiration rhythm. Because breath control relies on the Lungs which influence the sympathetic and parasympathetic nervous systems, the quality of Qi and its circulation are dependent upon the method, speed, and quality of the breath. To support the greatest longevity possible, it is important to breathe with a long, slow, and even quality to the breath. The breath (air from Heaven) interacting with the Po in the Lungs, plays a significant role in the Heaven-Man-Earth concept for balancing the emotions.

   The Lungs' virtues are righteousness and courage. These virtues give a person the drive and strength to do the "right thing" when the need arises. These virtues manifest and promote good health when a correct energetic and balanced alignment with the Po is achieved (between the Lungs breathing pattern and the Po).
5. The Po are connected to sexuality on the sensation level. All instinctive sexual reactions and passions come under the authority of the Po. In human life, the Po are linked to the basic instincts and perceptions of the body. The Po provide the fundamental biological energy, and are the source of biological needs and impulses. They are driven by basic instincts and urges, and their sole concern is the immediate gratification of biological needs and impulses (emotional and physical survival, reproductive urges, etc.). Most self destructive behavior, such as an attraction to unhealthy and dangerous life-styles, is due to the Po.
6. Because of the Corporeal Souls' relationship with the Lungs and Large Intestine, the anus is considered the "Po Men" or "the door of the Po." It acts as a doorway for the elimination of the waste products for the Five Yin Organs, through draining off impure liquids and waste.

THE KIDNEYS STORE THE ESSENCE SPIRIT "ZHI"

The Chinese term Zhi (translated as "will") is the prenatal spiritual entity associated with the Kidneys, and is not the personal will of the ego that is driven by our desires. The term Zhi has two meanings. It means memory, but it also means willpower. Both are primary features of the Zhi. The word Zhi can also be used to mean the Mind (whole body consciousness and awareness). In connection with the five mental aspects of the Mind, the Three Ethereal Souls, Seven Corporeal Souls, the Shen, the "intellect," and the "willpower" are sometimes referred to as the Five Zhi.

MEMORY

Memory is defined as the ability to remember information when studying or learning a particular subject or pattern. The Kidneys keep a determined focus on our goals, not forgetting where we are going and what we are working to achieve; they maintain a vital mindfulness. The Kidneys relate to short term memory, whereas, the Heart governs the body's long term memory (Figure 13.15). This is why elderly patients, whose Kidneys are declining, often cannot remember what day or year it is, but can remember events long past.

WILLPOWER

This is the most important aspect of the Zhi, because it is responsible for supplying the mental drive, willpower, determination, and single minded pursuit of goals and aspirations. It enables the realization of ambitions by providing the focussed energy necessary to carry ideas to fruition. A powerful Zhi creates the magnetism and charisma necessary to manifest and materialize our dreams.

Even though a person has acquired all the information available via the Hun, Po, and Yi, without the Zhi there can be no action. Although the Hun give us the goal (thinks of something), the Zhi is needed to accomplish it (decides and acts on it). A person with well-developed Zhi demonstrates perseverance, determination, and a tenacity to complete personal goals. Patients with Deficient Zhi become indecisive and fearful. Patients with Excess Zhi have a blind obedience to authority, or tend to be fanatics.



Figure 13.15. Three Ways the Body Stores Memory

The goal of the Qigong doctor is to reach such a level of attainment that his or her personal will merges with Heaven's will (Tian Zhi) becoming one and the same. Tian Zhi is considered the movement of the divine expressed in man as his personal virtue (De).

A man's virtue is defined as his spiritual righteousness, the authenticity of his heart and actions. It is through the acquisition of virtue that man finds and possesses his true nature. If man's virtue is initiated into the "mysterious" (embracing Heaven's will), his intuitive evolution will give way to limitless perception.

Tian Zhi is a divine inner prompting that guides us on our spiritual quest, if we are open to its message. Tian Zhi is what we can call the divine will and carries within it man's purpose in life.

THE FIVE YIN ORGAN CULTIVATION OF SHEN

The Shen indicates the vitality level, and the state of physical, mental, emotional, energetic, and spiritual being. A flourishing vitality is a manifestation of the Jing, Qi, and Blood inherent within the Five Yin Organs. These five components of the Shen are expressed through psychological manifestations (Figure 13.16). They form the bases of the patient's emotional characteristics. Each of the emotional components of the Five Yin Organs contribute to the patient's spiritual manifestation; adding or detracting from the natural harmony of the patient's spiritual nature.

The activity of conscious thinking, insight, and intelligence are the foundational aspects of the body's Shen, activated by the patient's Heart (wherein the Shen resides). The Heart is also responsible for the long term memory of the body's sensory memories (the perceptions, feelings and sensations related to hearing, seeing, smelling, tasting, and touching) and sleep. These sensory activities carry over from the other internal organs, due to their relationship with the Five Yin Organs. Emotional disturbances that affect the Heart can cause energetic changes in the patient's body, influencing health, toward recovery from diseases or illness by impeding or facilitating bodily functions (see Healing the Patient's Emotional Pain, Chapter 31).

When cultivating the Shen, it is important for the Qigong doctor to keep in mind that the spirit is indivisible from matter, and that an individual's emotional and spiritual well-being and development depend upon the healthy functions of the internal organs. When the Shen leaves the body (through shock, trauma, stress, depression, guilt, shame etc.), the Qigong doctor can observe a diminishment of glow in the patient's complexion, lack of luster in the eyes, along with changes in the respiration rate and state of mind.

Once the patient's Shen is disturbed, the Qi is affected. This in turn leads to the body's Jing becoming weakened. Patients with this condition are generally taught Medical Qigong exercises and prescriptions to not only tonify and strengthen their body's internal organs to improve their immune system, but also to improve the overall condition of their emotional/spiritual state. Even a low vitality of spirit can cause emotional disturbances that can scatter or stagnate the body's Qi.



Figure 13.16. The body's Shen is physically housed in the Five Yin Organs. Each Yin organ houses a particular psycho-spiritual and energetic aspect of the human being. For example: The pulse is stored in the Heart, which is the residence of the Shen (Spirit), and placed in the front of the body, the Blood is stored in the Liver, which is the residence of the Hun (Three Ethereal Souls), and placed on the left side of the body, the Jing is stored in the Kidneys, which is the residence of the Zhi (Willpower), and placed on the back, and the Qi is stored in the Lungs, which is the residence of the Po (Seven Corporeal Souls) and placed on the right side of the body.

The Yi (Intention) resides in the Spleen and is placed in the center of the body, governing the Qi of the four aspects of spiritual manifestation, distributing them along the body's Taiji Pole. When Jing and Blood combine Shen is born. The Hun follow the Blood along in all its movements. The Po follow the Jing along in all its movements. The state of Qi and Blood of each organ can influence the Mind and the Spirit, any alteration of the Mind or Spirit affects one or more of the internal organs.

Advanced cultivation methods utilize the energy of the Five Yin Organs, flowing to and from the body's Taiji Pole. It is from the Thrusting Channels along side the Taiji Pole that the energy of the Shen is dispersed into the body's Yin and Yang Organs and then into the extremities (Figure 13.17 - 13.18).

SHENGONG CULTIVATION METHODS

The key to enhancing the Qigong doctor's development of energy, is through learning how to control the vast amount of Qi within the body, without compulsively "Shening out" (allowing the spirit to leave because the body feels uncomfortable). To avoid disconnecting from the body, the Qigong doctor practices several specific training methods of Shengong cultivation. When focusing on Shengong cultivation and regulation, there are four traditional disciplines the doctor must adhere to: Nourishing and Strengthening the Shen, Housing the Shen, Combining the Shen with Respiration, and Combining the Shen with Qi (Figure 13.19).

NOURISH AND STRENGTHEN THE SHEN

The Qi is able to nourish and strengthen the Shen through proper Qigong regulation. This is brought about through a form of coherent light meditation, that focuses the doctor's Shen on a small circle of light (generally about the size of a marble or pearl). The doctor's focus of concentration can extend either externally onto a specific point outside the body, or internally on a specific point inside the body (e.g., the Upper Dantian). Through this focused "coherent light" (light with wave patterns that are all in step or in phase), it is possible to build the Shen's strength and refine its power. Through focused intention on a specific area, the Qi and Shen condenses together forming a more powerful type of energetic projection.

HOUSING THE SHEN

By disciplining (i.e., quieting) both the emotions and thoughts the Shen becomes relaxed and tranquil, and remains in its residence (the Heart). The Shen must not be allowed to become attracted to outside emotional disturbances. The goal is to allow the Shen to be energized but not excited.



Figure 13.17. The Five Thrusting Channels as seen from the top of the head. Located within the Five Thrusting Channels are the "Five Portals of the Heavenly Gate." These gates include four entry points which surround the Baihui (One Hundred Meetings) point. These four points are known as the Sishencong or "Four Spirit Hearings" and are the access points for the upper spiritual matrix surrounding the body's Taiji Pole, and connect the Five Thrusting Channels of the upper gates with the Five portals of the Earthly Gates.



Figure 13.18. The Five Thrusting Channels as seen from the perineum. Located on base of the Five Thrusting Channels are the "Five Portals of the Earthly Gate." The Fire point is at the location of the Huiyin point on the Conception Vessel (CV-1), the Water point is at the location of the Changqiang point on the Governing Vessel (GV-1), the Wood and Metal points are located just below the ischial tuberosity, lateral to the anal sphincter. These points are known as the access points for the lower spiritual matrix surrounding the body's Taiji Pole.

COMBINING THE SHEN WITH THE RESPIRATION

Once the Shen has been nourished, strengthened, and housed, it is then connected with the doctor's breath. Once the Shen is combined with the respiration, maximum healing results can be obtained by releasing Healing Sounds and Qi projection simultaneously.

COMBINING THE SHEN WITH THE QI

The final stage is for the doctor to be able to direct the Shen in coordination with the life-force energy being emitted into the patient. Since Shen projects as light and Qi projects as vapor, this combination of Spirit and Energy projection is very powerful, especially when combined with healing colors and sounds.


HOUSING THE SHEN #2
NOURISH AND STRENGTHEN THE SHEN #1
Shen
COMBINING THE SHEN WITH RESPIRATION #3
COMBINING THE SHEN WITH QI #4

Figure 13.19. Four Ways to Cultivate the Shen

THE SIX TRANSPORTATION'S OF SHEN

The psychic abilities developed in Medical Qigong training result from a well-developed intuitive faculty, brought about through Shengong meditations. Through these meditations the Yuan Shen can transcend the space-time continuum, as both space and time are multidirectional and interconnected.

Shengong meditations cause altered states of consciousness that differ substantially in subjective and objective observation from the general norms for that individual. As the Qigong doctor dissolves his or her Shen into the Wuji, the subconscious will be able to see forward and backward in time, unhampered by distance.

The conscious mind acts as a filter, seeking to analyze every perception, and attempts to identify and categorize each perception. Once the conscious mind is engaged, the flow of perception usually stops because the perceptions arising from the subconscious are usually vague (often with multiple messages). Qigong doctors must train themselves to first root (ground/stabilize) the acquired mind, in order for their perceptions to come through in a pure form, void of thoughts and judgments.

The ancient Qigong masters explained the ability to access the manifestations of Shen as follows: "by rooting the acquired mind (Zhi Shen), the Heart (Yuan Shen) opens up to 10,000 voices (Wuji)." Meaning that, when the "chattering mind" is anchored into the Earth through focused intention, the Heart is able to perceive the spiritual realm (the 10,000 voices), or be aware of its connectedness to the multidirectional space-time continuum.

Extraordinary abilities that develop from the cultivated spiritual consciousness include: telepathy, clairvoyance, clairaudience, precognition, time travel into the past, levitation, and teleportation.

The Qigong doctor experiences different psychological adjustments when opening to the deep spiritual transitions of Shengong meditations. The adjustments the doctor will experience include:

1. Time distortion,
2. Deep mystical states of perception and intuition,
3. Deeper and more powerful levels of self healing,
4. A more spontaneous reaction to movement and sound, and
5. Difficulty communicating verbally.

CULTIVATING THE SPIRITUAL CONSCIOUSNESS TO OBTAIN THE SIX TRANSPORTATION'S OF SHEN

In Shengong meditations, it is through the use of imagery and creative visualization that the doctor's altered states are developed, and a connection is forged with the Yuan Shen and Eternal Soul.

After the doctor's Shen has entered into a quiescent state, his or her altered state of spiritual conscious can be initiated through choosing one of the following five images.

1. The doctor is instructed to go inward into the center of the Taiji Pole to connect with his or her Yuan Shen and Eternal Soul.
2. The doctor is instructed to go into an imaginary temple or sacred place located within the astral plane to connect with his or her Yuan Shen and Eternal Soul.
3. The doctor is instructed to float upwards into the Heavens to connect with the eternal source of his or her Yuan Shen and Eternal Soul.
4. The doctor is instructed to ascend out of the body (after reliving the death of a past life experience) and receive the knowledge learned from that experience collected from by the Yuan Shen and Eternal Soul.
5. The doctor is instructed to allow the Yuan Shen to directly connect with the Eternal Soul and transmit information.

The Higher Self and Eternal Soul are usually considered as the same thing, and are often regarded as the "Master Within." In Jungian psychology, the collective unconscious (Wuji) is accessed through the subconscious mind (Shen) in the form of dreams or directly through "visions." The personal subconscious (Shen) has several elements:

- the anima, which is the wise man (influenced by the Hun)-for males, or
- the animus, which is the wise woman (influenced by the Hun)-for females, plus
- the shadow, which is the individual's dark side (influenced by the Po).

Once the Qigong doctor has cultivated the Shen into a high level of effective energy (absorbing and projecting energy from the universal, as well as the immediate environment), the result is a gradual unveiling of six supernatural diagnostic powers known as the Six Transportations of Shen.

These six metaphysical abilities not only enable the Qigong doctor to accurately evaluate a patient's state, but also to predict the probable future progressions of the patient's life as well as of his or her disease. The Six Transportations of Shen are: Observing the Present, Comprehending the Past and Observing the Future, Knowing a Person's Thoughts, Perceiving a Person's Destiny, Hearing the Sounds of the Universe, and Examining the Universe (Figure 13.20).

OBSERVING THE PRESENT

The Qigong doctor must first quiet the Zhi Shen's (acquired mind) analytical chattering by housing its energy within the Five Yin Organs. As the Mind becomes rooted, the doctor's breathing slows and the Lung Qi harmonizes with the Heart Qi. Once the Seven Po are quieted in their residence and the Zhi Shen is rooted, the Yuan Shen's messages can come through clearly without interference. The Yuan Shen is always connected to the Wuji where all knowledge is stored. The Yuan Shen is always at the "center of time" where it can gather and absorb the patient's past and present experiences, emotional reactions and thought patterns. It is from the Qigong doctor's intention and focus to be at the "center of time" that he or she can observe the present state of "now."

Observing the past is the ability to analyze and accurately discern the actual state of present situations (the here and now). By keeping away from conscious intervention, the Yuan Shen is free to truly listen and perceive as an "observer." The doctor's ego is not engaged and his or her mind's subconscious observer receives and reviews the patient without bias.

This enables the doctor to thoroughly analyze and comprehend events and situations clearly and unambiguously. It is through this state of perception that the Qigong doctor can accurately discern the true emotional problems which disturb his or her patient's energetic balance.

COMPREHENDING THE PAST AND OBSERVING THE FUTURE

Comprehending the past and observing the future is the ability to analyze and understand the thought patterns of the patient, the reasons these patterns take place, and to accurately predict the outcome of future events based upon those pat-


The Six Transportations of Shen
Observing the Present
Comprehending the Past and Observing the Future
Knowing a Person's Thoughts
Perceiving a Person's Destiny
Hearing the Sounds of the Universe
Examining the Universe

Figure 13.20. The Six Transportations of Shen

terns. By observing the patient from the active state of being in the "present," the Qigong doctor is free to travel within the infinite space (Wuji) enveloped within the patient's tissues. The doctor's Yuan Shen has no need to astral travel to obtain this information. The doctor's energetic connection to the patient's energy body gives him or her direct access to the personal information needed. It is from this internal space that the Qigong doctor can begin to access the memories existing within the patient's body (stored within the cells of the tissues).

At the subatomic level, the body and its cells contain a great deal more energetic space than matter. The doctor can directly access the internal Wuji enveloped within the patient's tissues and cells to retrieve the patient's past memories and emotions. Through tracing the patient's emotional, mental and spiritual development a greater understanding of the patient's present condition is achieved. After the doctor's Yuan Shen has gathered this information, it can be further analyzed by the doctor's Zhi Shen, and organized to accurately determine the cause and effects on the patient's present state.

Through understanding past patterns of thought and emotional reactions, the doctor can then predict future patterns of change and transition. These predictions are quite accurate, since people are prone to repeat programmed patterns indefinitely, unless there is an internal spiritual transition that frees them from this subconscious patterning.

Knowing a Person's Thoughts

This is the ability to sense the thoughts, judgments, fears, and emotions of another person, knowing their innermost fears and subconscious thoughts. The subconscious mind of the doctor communicates with the subconscious mind of the patient. This is a nonverbal, telepathic communication. It is therefore important for the doctor to monitor his or her thoughts and feelings, as they are automatically being projected into the subconscious mind of the patient. After the treatment is over the doctor may discuss with the patient any important information received that would be helpful to the patient.

Perceiving a Person's Destiny

This is the ability to predict future events and upcoming transitions in an individual's life based on the doctor's understanding of the patient's past energetic patterns. Through the Yuan Shen's ability to perceive the past and present, the doctor is able to understand the patient's mind, thoughts, acquired characteristics and personality. Above all, however, the doctor is able to perceive the individual's true nature that exists behind all of the patient's external masks. The doctor's Zhi Shen (postnatal mind) is then able to analyze and categorize the individual's patterns. Through deductive thinking, the doctor is able then to perceive the probable outcome and development of these repetitive patterns. This enables the doctor to help the patient to identify the patterns that require restructuring and give added encouragement and advice, when needed.

This spiritual counsel or guidance is extremely important for healing transitions since old patterns established in the three energy matrixes (Jing, Qi, and Shen) must be changed together to achieve a more permanent healing. Otherwise, the illness is likely to reappear. The spiritual matrix sets the foundation for the energetic matrix, which in turn sets the foundation for the physical matrix.

HEARING THE SOUNDS OF THE UNIVERSE

This is the ability to hear sounds, music, and voices not audible to the normal hearing. This is not to be confused with schizophrenia -- a mental illness that causes a person to hear voices; the difference is that the schizophrenic cannot think clearly, the mind is very confused and unordered.

The ability to hear the sounds of the universe is also the ability to be aware of, and receive, divine inspiration or messages (clairaudience). These abilities allow the doctor to affect the lives of those they know or soon will know. The doctor's own inner-voice can guide, instruct, teach, and lead the doctor to ever higher states of enlightenment.

Through inner hearing, the Qigong doctor is able to listen to, as well as understand, the resonant sounds generated by life-force energy and spiritual entities. This enables the doctor to tap into an unlimited source of divine knowledge and wisdom, which in turn allows the doctor to be present for the patient's highest good.

EXAMINING THE UNIVERSE

This is the ability to actually perceive current objects, events, or people that may not be discerned through the normal senses. It is the ability to perceive both time and space on a spiritual dimension (clairvoyance), to understand and acknowledge one's part, and to accept one's divine calling in life. It is also the ability to understand how one's spiritual calling affects both the cosmos and mankind. Through inner-vision the Qigong doctor is able to see inner-visions of divine enlightenment, observe and exchange information with celestial beings, and find holy places for spiritual sanctuary.

The metaphysical abilities of the Six Transportations of Shen are spiritual manifestations from the Eternal Soul. Once the Qigong doctor regulates his or her spiritual life, these abilities become a natural course of experience, giving way to the development of eight supernatural powers. A chart describing the interaction of the body's Eternal Soul with the energetic functions of the Three Dantians and Five Yin Organs' Wu Jing Shen (Five Essence Spirits) is depicted in Figure 13.21.

THE EIGHT SUPERNATURAL POWERS

Once an individual has obtained the Six Transportations of Shen, his or her psychic abilities develope into eight supernatural powers. These powers can be utilized in the individual's personal spiritual practice. Through these eight supernatural powers the doctor's Yuan Shen can allow him or her the ability to transcend all physical boundaries and invoke certain spiritual manifestations. The eight supernatural powers are described as follows.

1. The ability to make the one's physical body light.
2. The ability to make the one's physical body heavy.
3. The ability to reduce one's energetic body to the size of an energetic particle. This allows an individual the ability to astral travel into the subtle energetic and spiritual realms of existence.
4. The ability to expand one's energetic body to an infinite size. This allows an individual the ability to connect to, through, or envelop objects, as well as energetically protect people, places and things.
5. The ability to call into existence and attain one's specific needs or desires. Due to the individual's strong connection to the divine,


Chamber of Light
(Upper Dantian)
Tai Yi (Great
Divinity
Taiji Pole
Heat
Vibration
Light
Vibration
Heat
Intuitive Communication
Astral
Travel
Cord Attached to the Astral
Soul
Resides in the
Upper Dantian
Tai Guan -Hun
(Eminent Light)
Yu Jing - Hun
(Hidden Essence)
Resides in the
Middle Dantian
Shang Ling - Hun
(Pleasant Soul)
Five Agents
Leaves
Body
through
Dreams
Hun
Liver
Kidneys
Spleen
Lungs
Heart
Zhi
Yi
Po
Shen
Wu
Jing
Shen
Chamber of Vibration
(Middle Dantian)
Si Ming
(Administrator of
Destiny)
Cord Attached to Soul
Empathic
Communication
Eternal Soul
Rooted Behind
the Heart
Core Self
(Eternal Soul)
True Self
Five
Yin
Organs
Taiji Pole
Heat
Vibration
Light
Vibration
Heat
Kinetic Communication
Six
Transportations
of Shen
Chamber of Heat
(Lower Dantian)
Xia Tao Kang
(Below Healthy
Peach)
Intuitive
Wisdom of
the Eternal
Soul
Prenatal
Spirit
(Yuan Shen)
Postnatal
Spirit
(Zhi Shen)
Soul Extensions
(Personality
Characteristics)
Eight
Supernatural
Powers
Acquired
Wisdom of the
Five Senses
Resides in the Lower Dantian
Bottom of
Feet (Kd-1)

Figure 13.21. The Body's Intricate Interactions of the Eternal Soul

he or she may manifest through faith that which is desired.

6. The ability to experience and enjoy one's desires fulfilled.
7. The ability to gain authority over one's situations. First and foremost, the individual will obtain the spiritual authority over a specific situation, then the authority over the emotional, mental and physical realms follow.
8. The power to attract and control things. This allows an individual the ability to engender help and security (in the form of outside council, finances, and spiritual and emotional support) in order to exercise power over specific situations.

SOUL PROJECTION, SPIRIT PROJECTION AND ENERGY PROJECTION

The phenomena of Soul Projection, Spirit Projection and Energy Projection is known and accepted as a natural part of existence in almost every culture in the world. The holy men and women, shamans, and energy healers of many primitive societies were required to prove their powers by exercising these spiritual and energetic abilities.

Tibetan Buddhism (influenced by the energetic practices of Indian cosmology) contains elaborate doctrines about Soul Projection (also known as Astral Projection), Energy Projection, the Astral Body, and also describe the feats individuals can perform while out of their physical bodies. Some of these doctrines are quite similar to the traditional Daoist teachings which are evident in advanced Daoist Shengong training.

All Chinese systems used for inducing Shen and Qi projections use visualization, concentration, willpower and the individual's innate skill. The three types of external projections are: Soul Projection, Spirit Projection, and Energy Projection.

- Soul Projection occurs when the body's Eternal Soul is externally projected out of the body, while still attached to the Middle Dantian through a Silver Cord;
- Spirit Projection occurs when the body's Shen is externally projected outside of the body as an energetic vehicle of light;
- Energy Projection occurs when the body's Qi is externally projected out of the body like an energetic vapor (Figure 13.22).

In Soul Projection, Spirit Projection and Energy Projection, the effects of time are not acknowledged outside of the physical realm. Within the Astral Plane, time is omnipresent, there is no past or future, only the individual's perception of it.

The body has an established relationship to both the physical and spiritual world. The physical world of the living is considered a Yang state of existence, while the supernatural-spiritual world is in a Yin state of existence (see Chapter 19). As the Qigong doctor's Shen reaches a high state of sensitivity, he or she can transcend the ordinary senses and normal conscious perceptions. These abilities enable the doctor to observe, communicate and even travel within the "higher" and "lower" spiritual Yin world. There are nine energetic levels of Heaven (i.e., the higher astral planes), and nine energetic levels within the Earthly spiritual realm (or lower astral plane).

It is important to note that the term "higher" and "lower" astral realm has nothing to do with the actual space, but with the energetic and spiritual vibrational levels. The higher and lower astral planes overlap and exist within the same space as the physical plane. This blending between the higher planes, lower planes and the physical plane creates energetic dimensions (or places) where the separation between these worlds is thin. In these energetic dimensions, lower beings can reach and attach onto an individual -- even though the individual is not directly within the astral regions.

The energetic frequency of each astral being determines the spiritual level wherein it exists. Beings of higher frequency, for example, vibrate at a faster rate and reside in the higher, less dense astral dimensions; whereas beings of lower energetic frequency can only dwell in the dense lower astral levels.

Negative feelings (e.g., worry, fear, anger, etc.) produce a lower vibrational rate that can not only keep an individual's spiritual vibration at a lower level, but can also attract lower level astral beings to that individual.

Soul Projection	The Eternal Soul is projected out of the body, attached to the Middle Dantian through a Silver Cord.
Spirit Projection	The Shen is projected outside of the body as an energetic vehicle of light.
Energy Projection	The Qi is projected out of the body like an energetic vapor.

Figure 13.22. Soul Projection, Spirit Projection and Energy Projection

SOUL PROJECTION

Soul Projection is the skill of sending the body's Eternal Soul (at will) to other places, times and dimensions (or worlds) in order to retrieve knowledge and experiences that assist the individual in his or her spiritual evolution. It is a nonphysical world in which time and space have no meaning or influence. The astral dimensions form a parallel universe that exists both within and outside ourselves.

The Eternal Soul is a fluid energetic form that can disengage from the physical body and travel about as a disembodied apparition taking the human consciousness along with it. It can pass through walls, travel to higher dimensional worlds, and encounter nonhuman creatures and mystical masters. Many Qigong masters use Soul Projection to seek spiritual knowledge, travel through time to view the past, explore other spiritual dimensions, engage in astral sex, or view the "infinite knowledge" (i.e., Messages) contained within the Wuji.

When the Eternal Soul begins to leave its energetic chamber, the brain wave patterns slow to a theta pulse. The body may feel paralyzed, and begin to vibrate as if an electrical current were passing through it.

There is also an odd roaring sound heard in the ears before the Eternal Soul separates from the body's tissues, or sometimes buzzing noises, musical notes, humming sounds, or chattering voices can be heard. When leaving the physical body, sometimes a swaying sensation can be felt as the astral body separates from its physical shell. The astral body can either spin out or float out of the physical body. When traveling in the astral body individuals may observe streaks of light flashing behind them as they travel.

As the Eternal Soul travels, a silver energetic cord is attached from either the top of the head (at the Baihui area) or at the Lower Dantian (at the umbilical area). This energetic cord is the media through which an individual retains his or her awareness of the physical self while projecting. This energetic cord is constructed of subconscious spiritual energy and maintains the individual's protective perceptual awareness of his or her physical body. It is believed by some that if this cord is severed the individual will die.

When the Eternal Soul (in its astral form) approaches someone, there is a feeling of electricity and coolness that is general felt. While in its phantom form, the Eternal Soul can display telekinetic powers (e.g., knocking on walls or tables, closing a half open door, etc.).

Warnings and Contraindication

Do not practice Soul Projection just before, or during, thunderstorms as the electromagnetic buildup in the atmosphere can hamper your ability to leave or return to the body. Also avoid approaching any kind of power-line during Soul Projection, there is a risk of getting caught by the power-line and becoming "stuck" (like a fly in a spider web).

1. A Body of Light	This energetic form resembles an energetic duplicate of the individual's physical self. It involves creating a near exact energy body duplicate of oneself (often with improvements, e.g., no wheelchair, or the elimination of other physical challenges).
2. An Animal Form	This energetic form resembles that of an animal (known as Shape Shifting). It is an ancient Daoist Shamanistic skill used to transcend the astral plane, and to take on the consciousness and energetic behavior, skills and perceptions of the animals the shamans assumed.
3. A Ghost or Saint	This energetic form resembles that of a Ghost or Saint (also known as an Invocation). It involves energetically taking on the image, form, and personality characteristics of a departed individual or spiritual deity.
4. The Immortal Observer	This energetic form resembles that of an All Seeing Eye (also known as The Astral Eye). It involves creating an energetic ball of light in the Upper Dantian at the Yin Tang (Third Eye) area. The large eye surrounded by a sphere of light is released from the Yin Tang area to gather psychic impressions via a long energetic cord attached to the Upper Dantian. As the eye returns, its energetic form is absorbed back into the individual's Upper Dantian. These gathered images are then analyzed and the information is assimilated before the energy is dispersed into the individual's Lower Dantian (and then down the legs and into the Earth).
5. The Element Body	This energetic form usually resembles that of different elements of nature, such as wind (as vaporous mist), Water, Earth (the terrain) or Fire. The ancient Daoist would use these elemental forms of nature as a disguise in order to obtain information or spy on hostile intruders.

Figure 13.23. Types of Spirit Bodies Used in Spirit Projection

Do not practice Soul Projection while recovering from an acute sickness (the drain on your energetic reserves can make you more susceptible to further illness).

SPIRIT PROJECTION

Spirit Projection is the skill of sending the body's Shen (at will) to other places, times and dimensions (or worlds) to retrieve knowledge and experiences to assist the individual in his or her spiritual evolution.

Spirit Projection (also known as mind projection, remote viewing, mind travel or traveling clairvoyance) can entail a combination of "genuine" observation with an extrasensory perceptional ability to gather information. When individuals perform traveling clairvoyance in the form of Spirit Projection, they can send their consciousness anywhere in the world. Awareness is not physical in nature, it is experiential, totally nonmaterial and cannot be limited to, or fully contained within the body.

Spirit Projection is practised through the creation of an energetic vehicle for the spirit body, such as a body of light, an energetic form of an animal, or a ball of light. An energetic shape is formed through the imagination and intention. The individual then transfers the energetic consciousness from his or her physical body into the energetic vehicle. This energetic form can resemble various patterns shapes and sizes to serve the individual's purpose (Figure 13.23).

As the individual thinks about a person or place, his or her body will be pulled to that object like a magnet, followed by a flood of images. The spirit body can fly over various terrains as it travels (e.g., oceans of water, deserts, mountains, forests, etc.). Once the spirit body arrives at its destination, the individual is able to feel and experience the area's environmental Qi (e.g., the humidity, wind, cold, heat, light, darkness, etc.).

After traveling in the spirit body the individual must reabsorb the energetic body back into his or her physical body to retain a clearer memory of the experiences.

Warnings and Contraindication

Do not perform too many Spirit Projections within a relative short time span. Excessive Spirit Projection has a tendency to weaken the Kidneys and drains the body's Wu Jing Shen.

While traveling, be careful of what your intentions are, as like begets like. Any negative projection, emotion or evil intention brought into the astral plane will quickly rebound back to the individual, or may attract negative entities that feed off of these lower vibrations.

ENCOUNTERING ASTRAL BEINGS

Within the subtle realm of the spiritual world, the existence of spiritual entities and ghosts are divided into Yin and Yang. While traveling in the astral realm, an individual can encounter either type of spiritual entity.

1. The Yang Beings native to the higher astral realm vibrate at a faster energetic rate, and are associated with more advanced, highly evolved beings, such as angels, guides, beings of the light, and enlightened masters.
2. The Yin Beings native to the lower astral realm vibrate at a slower energetic rate, and are associated with lower, less evolved beings, such as devils, demons, spirits of darkness, evil spirits, and other similar negative spiritual manifestations.

In all truth, the astral body cannot be hurt the same way that the physical body can. The astral body can, however, carry back to the physical body mental, emotional, and spiritual scars, or hitchhiking negative astral beings, all of which can negatively affect the physical body.

All actions and reactions on the astral plane, whether productive or destructive, are a product of the individual's belief system (you bring about each condition according to your faith).

ENERGY PROJECTION

Another type of life-force energy that the body can project outside its physical structure is Qi. Qi Projection is emitted outside the body like a fine vaporous mist, enveloping and sensing everything that it touches. Similar to Soul Projection and Spirit Projection, Qi Projection is directed according to the individual's intention, imagination, will, and faith. Distance therapy, pertaining to Qi emission, can be observed as energy leaving the doctor's hand like heat waves emanating towards an external object. Within this emitted life-force energy is contained the doctor's Shen (Spirit), as well as the energetically encoded "Messages" that the doctor sends to his or her patient. This constitutes the energetic foundation for Medical Qigong therapy.

SECTION III

DAO YIN TRAINING

CHAPTER 14
INTRODUCTION TO DAO YIN TRAINING

Qigong developed into a systematic healing art for health preservation during the "Warring States" period in Chinese history (476–221 B.C.). Records from that time contain documentation of symptoms, treatments, and specific points of attention given within the body and energy channels, by doctors practicing Medical Qigong, as well as details of the effects of these Qigong exercises.

The Huang Di Nei Jing (*The Yellow Emperor's Classic of Internal Medicine*) states, "to treat diseases it is important to use both Dao Yin and An Qiao." These are two names given to Medical Qigong therapy in ancient times.

"Dao" refers to physical movements, which are guided by the strength of the mind to stimulate the body's Qi and bring about a state of relaxation. "Yin" refers to the fact that with the aid of physical movements the body's Qi can reach the extremities (feet, fingers, and head). Dao and Yin together mean to lead and guide the energy through both motion and quiescence. This therapy includes mental, respiratory, and postural exercises.

"An" has two meanings, "massage" and the "up and down movement of the wrists." "Qiao" means "to lift up." An Qiao refers to the methods of the postural Dao Yin exercises. The basic hand and body methods of postural Dao Yin training are as follows:

- Kai (Opening)
- Fen (Separating)
- He (Closing)
- Tui (Pushing)
- Rou (Rubbing)
- Xuan (Rotating)
- An (Pressing)

These are the foundational movements a Qigong doctor will use in order to purge, disperse, gather, tonify, emit and guide Qi. The training of energy is achieved and implemented primarily through a combination of dynamic (active) and static (quiescent) exercises and meditations. Although Medical Qigong schools are diverse and complex in their form and content, they can all be divided into two main branches of energetic cultivation: Static Qigong and Dynamic Qigong (Figure 14.1).


Static Qigong Training
1.Dispersing into the Wuji
2.Breath Regulation
3.Mind Concentration
4.Imagination and Observation
5.Static Relaxation Qigong
6.Inner Nourishing and Strengthening Qigong
Dynamic Qigong Training
1.Guiding and Inducing
2.Massage
3.Tapping and Striking
4.Self-inducing
5.Hard Qigong

Figure 14.1. Two Main Branches of Energetic Cultivation: Static Qigong and Dynamic Qigong

STATIC QIGONG TRAINING

This training involves bringing about and keeping a quiescent state of mind and breath. In fixed postures (lying, sitting, or standing) the practitioners can train to accumulate substantial Qi in their Lower Dantian, while circulating it through their bodies. Static Qigong training is further divided into six different schools of practice: Dispersing into the Wuji, Breath Regulation, Mind Concentration, Imagination and Observation, Static Relaxation Qigong, and Inner Nourishing and Strengthening Qigong.

1. Dispersing into the Wuji requires the practitioner to dissolve his or her energy into infinite space, or the Void, without focusing or directing their attention on any object from the external environment.
2. Breath Regulation requires moving Qi internally or externally while inhaling, exhaling, or swallowing the breath, etc.
3. Mind Concentration requires concentrating the mind on one fixed internal or external point.
4. Imagination and Observation require disciplining the imagination with vivid, colorful visualizations.
5. Static Relaxation Qigong requires the relaxation of both body and mind, keeping them in a constant state of quiescence.
6. Inner Nourishing and Strengthening Qigong require the use of multiple Static Qigong modalities (for example; Breath Regulation combined with Imagination and Observation).

DYNAMIC QIGONG TRAINING

This involves training the body, mind and Qi simultaneously, to promote the functional activities of Qi and to enhance its free flow throughout the body's channels. These exercises often require standing or walking, and affect muscular tension, weight distribution, Blood and Qi circulation, as well as the functional activities of the major organs. These exercises are differentiated by various kinds of body movements and can be divided into five different schools of training: Guiding and Inducing, Massage, Tapping and Striking, Self-inducing, and Hard Qigong.

1. Guiding and Inducing requires physical movements such as dancing, mimicking animal movements, and gymnastics.
2. Massage focuses on both the manipulation of specific points and channels, as well as on the knowledge of muscles, tendons, and bone structure.
3. Tapping and Striking focus on using patting, slapping, tapping, and striking techniques with the fingers, palm, fist, wooden stick, or material in a cloth bag.
4. Self-inducing training encompasses small to large physically strenuous Qigong movements.
5. Hard Qigong focuses on martial arts training in Iron Palm Training, Iron Body Training, etc.

The incorrect employment of dynamic or static principles of Qigong exercises and meditations can cause energetic deviations which are capable of either hindering, or harming, the individual's health. There are two purposes for Medical Qigong development: To Protect and Strengthen the Body's Health, and To Treat Diseases.

1. To protect and strengthen the body's health: Medical Qigong exercises are prescribed in accordance with the individual's physical constitution, state of health, emotional constitution, climate, and different seasons.
2. To treat diseases: Medical Qigong exercises are prescribed in accordance with the individual's symptoms, pathological condition, and degree of severity, complications, and the constitution of the patient.

PRINCIPLES OF YIN AND YANG IN DAO YIN TRAINING

Both static and dynamic Qigong methods supplement each other when combined equally. No matter which static or dynamic method is practiced, one of the four principles of Yin and Yang will always be adhered to: Quiescence in Motion, Action within Motion, Motion in Quiescence, and Stillness within Quiescence.

1. Quiescence in Motion is referred to as a Yin within Yang technique, and requires being quiet, calm, and still on the inside while being active on the outside.



Figure 14.2. Dao Yin Chart

2. Action within Motion is referred to as a Yang within Yang technique, and requires being active both on the inside and on the outside.
3. Motion in Quiescence is referred to as a Yang within Yin technique, and requires being active on the inside while being quiet, calm, and still on the outside.
4. Stillness within Quiescence is referred to as a Yin within Yin technique, and requires being quiet, calm, and still both on the inside and on the outside.

THREE FOUNDATIONAL METHODS OF DAO YIN TRAINING

The diverse methods of practicing Medical Qigong exercises fall within three categories of Dao Yin training: Posture Dao Yin training, Respiratory Dao Yin training, and Mental Dao Yin training.

1. Posture Dao Yin consists of posture training for Medical Qigong therapy. It is divided into six specific types of training: walking, standing, sitting, kneeling, lying, and massaging.
2. Respiratory Dao Yin consists of breathing exercises for Qigong training, and therapy that includes various techniques of inhaling, exhaling, aspirating, blowing, and holding the breath.
3. Mental Dao Yin training requires that the thoughts be concentrated on one object, placing the cerebral cortex into a special inhibitory state. In various Medical Qigong circles in China this method is commonly referred to as "the internal keeping of the mental state."

The Dao Yins are taught in a postnatal energetic progression of Jing (posture) to Qi (respiration), to Shen (mind and emotion). In this way, the body regulates and supports the production of energy, which in turn regulates and supports the production of Spirit (Figure 14.2).

Despite the fact that many postures and movements may vary according to the specific styles of each Medical Qigong school, the primary benefit of each exercise will:

- improve and strengthen the patient's metabolism,
- smooth the Qi of the channels and collaterals,
- strengthen the body and mind,
- emotionally detoxify the internal viscera, and
- facilitate the increased flow of Righteous Qi (the Qi that fights the pathogenic invasion of Evil Qi) within the body.

CHAPTER 15
POSTURAL DAO YIN TRAINING

The goal of Postural Dao Yin training is to promote the regulation and circulation of Qi. Part of this training involves learning the techniques to guide the internal energy to flow using the movements and changes in the electromagnetic fields of the hands and body.

Success in Medical Qigong training is directly related to the correctness of the body's alignment. Correct posture regulates the Heart, and results in a calm mind; with a relaxed mind it is easy to lead the flow of Qi downward, to affect the Blood circulation and pulse. When the body is incorrectly aligned, it disturbs the smooth flow of Qi; energy then becomes obstructed or deviates, resulting in a restless Mind (both the thinking mind and the whole body consciousness).

The proper sequence of relaxation and energy circulation within the body is as follows:

1. the muscles are first to relax,
2. followed by the tendons and ligaments,
3. next, the nerves relax, and
4. finally the bones.

Once the muscles, tendons, and ligaments relax, the Qi can circulate freely through the channels and collaterals. The skin and muscles are generally the first level of awareness cultivation. The sensations of Qi and Blood circulation are usually experienced by the practitioner as heat, tingling, fullness, and expansion. The Chinese call these sensations the Eight Energetic Touches, which are known as the first of three transformations of energy (also known as the Subtle Wonders, see Chapter 29).

The next level of awareness involves the deeper flows of Qi within the nerves; this feels like an electric vibration, or an energetic current traveling through the body. Sometimes, due to an energetic surge released from within the body's organ system or channels, an electric shock is felt through the extremities or through the entire body.

The final level of Qi circulation awareness involves the Qi circulation within the bones and the Marrow. In the beginning stages it sometimes feels cold and arthritic in the joints (especially within the extremities). These sensations will later develop into a vibrational resonance which is felt deep within the bones.

The main point of Postural Dao Yin is to seek a state of physical and energetic balance. Postural Dao Yin is also divided into two distinct methods of treatment: Static Posture and Dynamic Posture training.

STATIC POSTURE DAO YIN TRAINING

This method includes quiet movement while in the position of lying, sitting, standing, or walking, and is used to accumulate and strengthen the practitioner's internal Qi. Before performing the static posture forms for Medical Qigong therapy, it is important to note that static posture training is divided into three basic modalities: Choosing the Proper Beginning Posture, the Inhaling and Exhaling Methods, and Opening and Closing the Lower Dantian.

1. The purpose of the choosing the proper beginning posture is to calm the Heart and relax the mind, and focus on a specific goal for training the body's life-force energy.
2. When the energy begins to flow freely, the practitioner focuses his or her attention on each inhalation and exhalation for the specific goal of tonification, purgation or regulating the life-force energy.
3. The purpose of the "opening and closing" of the Lower Dantian ending postures is to bring the body's energy back down into the Lower Dantian and to root the Qi. Rooting the Qi in the Lower Dantian after Qigong practice

avoids creating Excess conditions within the body's internal organs.

CHOOSING THE PROPER POSTURE

Medical Qigong meditations and prescriptions are not limited to sitting practice alone. Each of the different lying, sitting, standing, and walking postures has its own specific form of meditation.

The lying, sitting, and standing postures create the foundational base for Static Posture Dao Yin training. Each static posture can induce the body's energy to descend quickly into the Lower Dantian. The selection of the appropriate technique and body position is determined by each practitioner's body type (structural formation) and the condition of the individual's physical health. The length of time that a practitioner focuses on the Medical Qigong prescription is also determined by the individual's specific disease as shown in the following examples.

- Patients with digestive problems, gastroptosis, or prolapse of the internal organs should begin their training while lying supine (on their back), with their knees pointing upward, their buttocks elevated 4 inches off the ground, and their feet flat on the floor.
- Patients with gastrointestinal diseases should begin their training lying flat on their backs. As the condition improves, they should combine lying and sitting meditations to promote the digestion and absorption of food.
- Patients with Heart disease, hypertension, or nervous disorders should begin training from a sitting position. Later, they should combine sitting and standing meditations in order to direct their Qi and Blood downward.
- Patients with Lung diseases, asthma, chronic bronchitis, emphysema, or cardiopulmonary function disorders should begin their training from a semi-reclining position (usually a 45 degree angle) to help respiration flow smoothly and to alleviate stress on the Lungs.

  In the hospital, each pillow that the patient uses for elevation represents the degree of strain that is placed on the Lungs. The patient is said to have strong Lungs, for example, if he or she is reclining and breathing comfortably on one pillow. If however, it takes three pillows before the patient is reclining comfortably, the Lungs are considered weak and congested (e.g., in cases of dyspnea).
- Patients with severe physical weakness (e.g. chronic fatigue syndrome and fibromyalgia) should begin their training from a lying or sitting position. Later, they can combine sitting and standing meditations as their constitution improves.

PRIMARY AND SECONDARY POSTURES

Patients are taught a primary and a secondary posture to prevent fatigue, and increase the healing effect of the Medical Qigong prescriptions. A primary standing posture is performed, for example, in the morning when the patient is strongest, and the energy is cleanest. A secondary sitting posture is performed in the afternoon, or evening when the patient is tired, with a focus on quiet regulation.

After a patient has learned a particular lying, sitting, or standing meditation, he or she can be taught the secondary posture without the risk of depleting his or her Qi.



Figure 15.1. Sleeping Dog Posture



Figure 15.2. Supine Posture (Hibernation Posture)

LYING POSTURES

The Chinese saying, "The body should lie like a bow," is a perfect description of the curled position of the patient's body, while in the Sleeping Dog posture (Figure 15.1). This particular position is beneficial for aiding digestion and the absorption of food.

In prescribing the Sleeping Dog posture, the patient should lie on their right side with the left knee bent and the right leg extended straight. To avoid compressing the Heart, do not allow the patient to lie on their left side. Keep the patient's head raised slightly to allow the Blood to flow downward into the torso. Have the patient bend the right arm at the elbow.

When the patient is chronically ill, however, an exception is made. In this case it is important that the patient lie on the "healthy side" and not the side of the diseased organ (e.g., in cases of Liver disease, patients might lie on their left side). Remember to always adjust the patients' postures as needed and encourage them to practice "natural breathing."

Another popular posture is called the Hibernation posture. By lying supine in the Hibernation posture, the patient will regulate the functional activities of the central nervous system (Figure 15.2). Lying supine is also suitable for patients with serious diseases who are debilitated (this is also a sleep inducing method of training).

SITTING POSTURES

The Chinese saying, "The body should sit like a bell," describes the secure (or rooted) position of the patients' body, especially the lower legs and torso. Sitting is the most commonly used position for Medical Qigong therapy. This position helps the patients to relax and focus their mind's intent.

There are several sitting postures used in Medical Qigong therapy, and are prescribed according to the patient's flexibility: sitting upright on a chair (Figure 15.3), a cross-legged posture called the Full Lotus, another called Half Lotus, or with the legs loosely crossed (Figure 15.4-6). Make sure the patients sit on a raised cushion in order to keep their buttocks slightly higher than their knees.



Figure 15.3. Upright Sitting Posture



Figure 15.4. Cross-Legged Zi Wu Posture



Figure 15.5. Cross-Legged Buddhist Greeting Posture



Figure 15.6. Cross-Legged Buddha's Warrior Attendant Posture

One of my Medical Qigong instructors in China suggested elevating the hips at least four inches off the floor when meditating, to avoid undue stress on the lower back, spine, and leg circulation. This elevation of the hips forms a triangle between both knees and the Lower Dantian, establishing a firmer connection to the Earth energy. This allows the Earth Qi to easily flow from the patients' knees and coccyx into their body.

When sitting in a chair meditating, the feet should touch the ground firmly, instead of being suspended in midair. This allows the Earth Qi to flow easily from the patients' feet into their body. Otherwise patients may develop swollen feet and lumbago due to Blood stagnation, or even hallucinations.

Keep the patients' spine straight by aligning the tip of the nose on a vertical line with the navel, to release pressure and tension on the cervical nerves.

STANDING POSTURES

The Chinese saying, "The body must stand like a pine tree," describes a relaxed position of the body's structure, standing with the bones stacked on top of each other, from the ground up. Standing meditations are particularly tonifying in nature, and are absolutely essential for accumulating Qi. The advantage of the standing position is that the flow of energy can be easily regulated and promoted. This posture helps to normalize blood pressure, and calm the Heart. Standing meditations also produce a unique psychophysiological change within the patients, allowing them to shed energetic obstructions, and to create a healthier body, mind, and spiritual awareness. Standing meditations are also essential for the Qigong doctors, as it facilitates the accumulation of Qi that is necessary for the emitting of energy.

Standing meditations, however, are not suitable for patients who are extremely ill or in poor health. Therefore, exercises in the standing postures should only be prescribed for minimal durations during convalescence, to build up the patients' constitution, promote health and to enhance their strength slowly.

The body should be held in an upright posi-


Figure 15.7. Wuji Posture


Figure 15.8. Immortal Post Posture


Figure 15.9. Buddhist Greeting Posture


Figure 15.10. Extending Palm Posture


Figure 15.11. Embracing Dantian Posture


Figure 15.12. Square-Round Posture

tion, with three points connected in a straight line: Baihui GV-20 point at the top of the head, Huiyin CV-1 point at the bottom of the perineum, and the Yongquan K-1 point at the bottom of the feet. The patient's posture should be kept relaxed, still, solid, and rooted like a tree. The patient should also imagine their feet growing roots deep into the ground, to absorb the Earth's energy from the soil.

Standing exercises are usually accompanied by a variety of hand positions (Figures 15.7–15.12). The most popular are (1) Wuji: hands hang down by sides, (2) Immortal Post: hands embrace an invisible ball, (3) Buddhist Greeting: both hands press together at the solar plexus level, (4) Extending Palm: both hands press downward, (5) Embracing the Dantian: folding the hands and resting them on lower Dantian, and (6) Square-Round: left palm's heel rests inside the right palm's center.

In each posture, whether lying, sitting, or standing, the function and flow of body energy shifts and changes in relationship to, and as a manifestation of, the patient's mental belief structure.

If, for example, the patient while standing, shifts his or her weight and mental focus onto the balls of the feet, the energy will naturally flow through the front of the body via the front Yin channels. If the patient shifts his or her weight and mental focus onto the back on the heels, the energy will naturally flow through the back of his or her body via the back Yang channels. The center of the feet connect the patient's flow of energy to the Taiji Pole and can be used either to transfer the energy forward or backwards.

Generally, before beginning standing meditations, patients are encouraged to relax, sink, and shift their body weight back and forth between their heels and their toes. This practice massages their internal organs and disperses any blockages by stimulating the corresponding organ areas at the bottom of the feet as described in the therapeutic use of the Lower Hexagram Yaos (see Chapter 3).

Patients should inhale while shifting their weight backwards and exhale while shifting forwards. Their attention should be placed on their internal organs and the body's surrounding field of energy. The patients' awareness is also focused on the body moving back and forth, like the rhythm of an ocean tide.

Women are generally encouraged to practice meditation in the standing position (especially around the time of their menstruation), as the sitting position tends to decrease energy circulation, and may cause energy blockages in their lower abdominal area.

THE EIGHTEEN RULES OF PROPER MEDICAL QIGONG STRUCTURE

The most important basic techniques of Medical Qigong training are guided by eighteen rules of proper form and structure. The main point of Postural Dao Yin training is to relax and seek quiescence while in the various postures. Tension in any area of the body restricts the whole structural system, since the body seeks to balance its structure naturally by shifting its energy and weight. The general function of the muscles is to guide the flow of energy through the channels.

The following is a list of the Eighteen Rules for proper standing postures, these rules apply to every school of energy cultivation:

1. Stand with the feet flat,
2. Bend the knees,
3. Relax the hips,
4. Round the perineal area,
5. Close the anal sphincter,
6. Pull in the Stomach,
7. Relax the waist,
8. Tuck the chest in,
9. Stretch the back,
10. Relax the shoulders,
11. Sink the elbows,
12. Hollow the armpits,
13. Relax the wrists,
14. Suspend the head,
15. Tuck the chin,
16. Close the eyes for inner vision,
17. Close the mouth and turn your hearing inwards, and
18. Touch the tongue to the upper palate,

Each of these eighteen rules is described in detail as follows.

RULE 1—STAND WITH THE FEET FLAT

Stand with the feet flat, parallel to the outside of the shoulders. Weight should be distributed evenly on both feet about an inch and a half inward (anterior) from the heels, and perpendicular to the tibia. Focus on dropping the weight down behind the legs, not down the front. This action takes the pressure away from the knees and places it in the center of the feet (Figure 15.13).

Stretch the feet and let the toes softly grasp the ground to keep the body firmly rooted as you tuck the sacrum under (Figure 15.14). Relaxing is important. Rigid, contracted feet disrupt the flow of energy from the Earth into the body. The Kidney energy flowing within the bone can be accessed by shifting the weight onto the heels. The Heart energy can be accessed by shifting the weight onto the balls of the feet. The weight in the center of the feet accesses the Taiji Pole.

While training, the feet may vibrate or feel hot, as if on fire. This is a normal reaction to correct postural training and is beneficial because it dissolves the calcium deposits stored within the extremities of the feet. If, however, the Fire in the feet is too intense (due to Excess Liver Fire), hit the heels on the ground and rub the lumbar spine, using the mind's intention to send more of the Kidney Yin (Water) down to the feet to cool the Fire.

RULE 2—BEND THE KNEES

The knees should be slightly bent and facing the same direction as the feet. The knee caps should be directly aligned and extended no further than the tips of the middle toes. Do not allow the knees to twist inward.

To secure the structure, imagine holding a large beach ball between the knees. Many patients develop knee problems because they extend their knees too far forward or allow their knees to twist to the side, rather than aligning them with the toes. If pressure is felt on the sides or front of the knees, check the positioning. Knees that are unable to point in the direction of the toes are most often the result of tight hip joints (Figure 15.15). If the energy in the legs is tightly constricted around the knee area, Qi flow will be severely limited. A relaxed knee-joint, on the other hand, will increase



Figure 15.13. Stack the bones on top of each other from the bottom of the feet to the skull.



Figure 15.14. The three points (Baihui, Huiyin, and Yong quan) can be connected by a straight line.



Figure 15.15. Keep the center of the body's weight aligned to the center of the knees, to relax the connective tissue surrounding the knees.

the Qi and Blood flowing through the legs, making it easier to relax the hip and to round the perineal area.

Relaxing the knees also permits free flow of energy through the three descending Yang channels on the outside of the leg, and the three ascending Yin channels on the inside of the leg (Figure 15.16). The techniques for relaxing the knees will vary according to the emotional and structural pattern of each individual, as emotions of fear, etc., have a tendency to gather and pool behind the knees.



Figure 15.16. Relaxing the knees also permits the free flow of energy through the ascending Yin channels and descending Yang channels of the legs.

RULE 3—RELAX THE HIPS

Drop the buttocks slightly while sinking the Qi from the upper torso into the Lower Dantian, and relax the hips. Keep the hips facing forward. The buttocks should be gently tucked under the body to facilitate straightening of the spine and the keeping the Qi in the Lower Dantian.

Imagine a weight of a thousand pounds hanging from the coccyx (Figure 15.17). As the weight pulls down, tilt the sacrum under the body. When the hip-joints are relaxed, the lower limbs will be able to move freely.



Figure 15.17. Imagine a 1000-pound weight hanging from the coccyx and a heavenly cord suspending the head.

RULE 4—ROUND THE PERINEAL AREA

There are three parts to rounding the perineal area. First, set the knees apart, turning them both outward. This allows the groin and hips to shift to an anterior tilt. Second, bring the knees back together and turn them inward, while also relaxing the hips. This allows the groin and hips to shift to a posterior tilt. Third, suspend the perineal area to lift the perineum and the anus slightly. This allows the groin and hips to come to a center balance and to sink. Rounding the perineal area keeps the perineum free from pressure, yet sealed. This ensures better functional activities of the Qi, and allows the "lower door" (the anus) to remain closed to avoid leakage of vital energy.

RULE 5—CLOSE THE ANAL SPHINCTER

The anus is called the Lower Bridge and it is where the Yang and Yin channels meet and combine. The anus is considered the door of the Seven Corporeal Souls (Po). Although the anal sphincter is held closed, it is important that the perineum remain relaxed. There are three stages in controlling the anal sphincter:

1. In the first stage, the anus is contracted with slight muscle control, and the energy is directed into different energy centers along the Microcosmic Orbit. When first beginning, inhale and expand the abdomen while imagining that the anus is connected to the navel and is pulling up towards it. On the exhalation, contract the abdomen and draw the energy from the navel back down towards the anus. Next, inhale and create a connection between the anus and the Mingmen. On the exhalation, draw the energy from the Mingmen back down towards the anus. It is important to synchronize the drawing up of the anus towards the navel and Mingmen area with the expansion and contraction of inhalation and exhalation. This will facilitate a

sacral-cranial rhythm throughout the body.

2. In the next stage of training, the constriction of the anus is used to lead the energy up the Governing Vessel in the Microcosmic Orbit (Figure 15.18). Upon inhalation, draw the mind's intention from the navel towards the anus and then down to the tip of the spine (the coccyx), allowing the Qi to flow up the spinal column towards the Mingmen, past the Shendao to the base of the skull. Upon exhalation, roll the eyes back into the head and use the intention to meet the energy at the base of the skull. Next, lead the energy over the Baihui at the top of the head and down the Conception Vessel and back down to the naval.
3. At the third stage, imagine twisting the energy of the anal sphincter, spiraling the Qi up the center of the body, to connect with the Baihui area at the top of the head. Close the anal muscle gently, inhale and imagine the energy vibrating and spiraling in a counterclockwise direction up the body's Taiji Pole. This connects the Lower, Middle, and Upper Dantians through the Taiji Pole. Upon exhalation, lead the vibrating Qi down the Taiji Pole in a clockwise spiral ending within the Lower Dantian area. Continue this meditation until the entire body pulses with the rhythm of the Taiji Pole.

The anus is divided into five regions: Front, Middle, Back, Left, and Right. By contracting the anus in different parts, you can bring more Qi to the various organs and glands.

1. The Front region opens the gate to the sexual organs, as well as to the Conception Vessel when it is contracted.
   - For Men, this will affect the prostate gland, Bladder, Small Intestine, thymus gland, thyroid gland, parathyroid gland, mouth, nose and front part of the brain (Figure 15.19).
   - For Women, this will affect the vagina, uterus, vena cava, aorta, Stomach, thymus gland, thyroid gland, parathyroid gland, mouth, nose, pituitary gland, and front part of the brain (Figure 15.20).
2. By contracting and pulling the middle region of the anus, more Qi is drawn into the Thrusting Vessel and Taiji Pole, as well as to the genitals, aorta, vena cava, Stomach, Heart, thyroid gland, parathyroid gland, tongue, pituitary gland, pineal gland, and Baihui area (Figure 15.21).



Figure 15.18. The anus is used to draw the Qi from the navel into the Lower Dantian and lead the Qi up the Governing Vessel.

3. By contracting the back region of the anus the Qi is connected to the Governing Vessel, as well as the sacrum, lumbar, thoracic and cervical vertebrae, and the cerebellum (Figure 15.22).
4. By contracting the left side of the anus the Qi connects to the left side of the body.
   - For Men, this affects the left testicle, Large Intestine, left Kidney, left adrenal gland, Spleen, the left side of the Heart, left Lung, left ear, left eye, and left hemisphere of the brain (Figure 15.23).
   - For Women, this affects both ovaries, both Kidneys and both adrenal glands, Spleen, Liver, Heart, both Lungs, thyroid gland, parathyroid gland, and both hemispheres of the brain (Figure 15.24).
5. The Right Side. By contracting the right side of the anus the Qi connects to the right side of the body.
   - For Men, this affects the right testicle, Large Intestine, right Kidney, right adrenal gland, Liver, Gall Bladder, right side of the Heart, right Lung, right ear, right eye, and the right hemisphere of the brain (Figure 15.25).



Figure 15.19. The Front of the Anus



Figure 15.20. The Front of the Anus



Figure 15.21. The Middle of the Anus



Figure 15.22. The Back of the Anus



Figure 15.23. The Left Side of the Anus



Figure 15.24. The Left Side of the Anus



Figure 15.25. The Right Side of the Anus



Figure 15.26. The Right Side of the Anus

- For Women, this affects both ovaries, both Kidneys and both adrenal glands, Spleen, Liver, Heart, both Lungs, thyroid gland, parathyroid gland, and both hemispheres of the brain (Figure 15.26).

RULE 6—PULL IN THE STOMACH

Pull the stomach in above the pubic bone, and avoid tensing of the abdominal muscles. This helps to restrain the Yuan Qi, thereby increasing the internal pressure and promoting the flow of internal Qi throughout the whole body.

RULE 7—RELAX THE WAIST

If the waist is not relaxed the Qi can not sink back to the Lower Dantian. Relax the waist by relaxing the hips and bending the knees. When the waist is relaxed, the spine will stand upright, yet remain relaxed.

The waist and the abdomen are two important areas in training and guiding Qi. The abdomen is considered to be the furnace for refining Qi. The waist is the residence of the Kidneys and Mingmen Fire and is an important junction for Qi and Blood circulation.

The waist is considered the master of the body and must be kept sunken and relaxed (Figure 15.27). As the buttocks tuck under and the waist sinks, small pockets should form on the inner thighs where the pelvic bones meet the femur bones of the legs. Most people usually keep the pelvis area tight and immobile, as it is associated with shock, fear, and sexual trauma (when this area becomes loosened, such emotions are often released).

The specific actions to relax the waist are as follows: lift both shoulders in order to stretch the back, then release them downward immediately as you exhale, relaxing the waist. To achieve genuine waist relaxation, you must also relax and tuck the sacrum, this action opens the sacrum. When the sacrum is opened, the Lower Dantian will expand and the storehouse of Yuan Qi will be enlarged. Be sure that the waist and hips face forward in the same direction as the knees and feet.

RULE 8—TUCK THE CHEST IN



Figure 15.27. Relax and sink the waist, allowing the hips to drop.

The chest should relax inward so that air flows freely and the Qi sinks down into the Lower Dantian. Fill the abdomen with air while relaxing the chest inward. The back should be open and expanded. Relax the scapulae and allow them to sink to their lowest point, this will help the shoulders to sink. Rounding the scapulae (pushing to the sides and forward) will help open and expand the back.

Do not thrust the shoulders inward, nor intentionally close the thoracic cavity. The intentional tucking in of the vertebral area requires the outward opening of the ribs and expansion of the intercostal muscles. The action of opening the chest outward, then tucking the chest inward, helps to relax the thoracic cavity and avoids tension in the thoracic muscles.

RULE 9—STRETCH THE BACK

The key point to stretching the back is to hang the shoulders and "open the scapulae." When the two shoulders drop evenly, the lumbar vertebrae straighten out. The function of tucking the chest and stretching the back calms the Heart and Lungs.

The Heart controls mental and emotional activities, and also directs Blood circulation. When the thoracic cavity is spacious and the back is upright, the Heart and mind will be calm, and the Lungs will be clear and free from Heat. Tucking the chest and stretching the back allows the chest and back to relax, permitting the Conception and Governing Vessels to communicate with each other and improve energy movement.

Imagine a weight hanging from the coccyx and a rope pulling up on the crown point of the head. Feel the elongation of the spine with each inhalation and exhalation. Remain relaxed (Figure 15.28), do not hold yourself unnaturally erect and avoid contracting the abdomen to straighten the lower back. The abdomen must remain relaxed. When sinking the body's weight, try to feel the spine press into the heels of the feet.

RULE 10—RELAX THE SHOULDERS

If you relax the shoulder joints and let them hang naturally, the shoulders and neck will relax. If you elevate your shoulders when you are standing or sitting, the energy will not sink and you will begin to feel tired, the shoulders will be stressed, and the flow of Blood and Qi will become blocked.

When the shoulders are encouraged to relax and are allowed to drop and roll forward, this action facilitates the hollowing of the chest and the expanding and opening of the back, allowing the energy to flow into the arms (Figure 15.29). Try to feel your arms link up with the scapulae as the clavicles press downward. Your shoulders should remain very loose and free.

RULE 11—SINK THE ELBOWS

When practicing the Immortal Post posture (refer back to Figure 15.8), and the hands are positioned by the Heart, it is important to bend the elbows slightly at the elbow joint, holding them lower than the hands.

While in a Wuji posture, imagine that a weight is hanging from the elbows, or a sensation of compression will be felt at the shoulder and elbow joints. The elbows should be slightly bent and relaxed, remaining structurally correct and not weak. This will help to roll the shoulders forward



Figure 15.28. By imagining a rope pulling on the head and coccyx, the spine is allowed to naturally stretch, expanding the body's Qi in all directions.



Figure 15.29. When the shoulder (here viewed from above) relaxes, the Qi flow into the arm increases.

and open up the back. If the elbows are not bent, there will be decreased energy flow (Figure 15.30).

RULE 12—HOLLOW THE ARMPITS

Hollow the armpits as if each one is holding an egg, this allows the Qi and Blood to flow freely in the upper limbs. To relax the shoulders, move the tips of the elbows outward to the left and right. Avoid sloping or squaring the shoulders.

When practicing the Immortal Post Posture (refer back to Figure 15.8), the arms must embrace inward as if holding a large ball or barrel. Do not push the elbows out so far that you loose the curve in your arm, this is of extreme importance. Your arms should not bend inward more than 45 degrees. The energy flowing in your arms is like water running through a hose. If you bend it too sharply, much of the supply will be cut off.

RULE 13—RELAX THE WRISTS

This includes hollowing the palm, and the comfortable curling of the fingers. Relaxation of the wrist allows the Shu-Stream points in the wrist to communicate with the fingers (see the Five Antique Shu Points in Chapter 8). Hollowing the palm and curling the fingers allows for the natural stretching and curving of the hand, which prevents the Qi from diffusing. It is important to avoid being rigid and purposefully bending the fingers, as all hand postures effects the brain and the body's Qi flow.

Relaxing the wrists helps to regulate the three Yang and three Yin channels of the hands so that Qi and Blood can flow freely. The wrist must form a line with the shoulders. Do not bend the wrists, but hold them straight so that the middle finger forms a line with the forearm, allowing the hands and fingers to hang relaxed but not limp.

RULE 14—SUSPEND THE HEAD

The classics say that "the head is held aloft not by force, but as if it were placed there by a ruling power." Hold the head as if it were suspended, keeping the Baihui point pointed to Heaven (Figure 15.31). This produces space in the body by elongating the spine. When suspended, the head must be kept upright, positioned in the middle of the chest and shoulders. This helps to set the whole body in the upright position, and



Figure 15.30. Allow the bones in the arms to feel heavy, naturally stretching the tissues and increasing Qi flow to the extremities.



Figure 15.31. Suspending the head allows the body to become sensitive to the surrounding environment and external fields of Qi.

also directs the Qi and Blood to flow upward to nourish the brain and the mind. The Shen will be reinforced while the Jing and the Qi will be invigorated (it is the Shen which controls all the physical activities). An effective visualization is to imagine your head lifting high into space, your waist positioned in the clouds, and your feet sunk deep into the Earth.

RULE 15—TUCK THE CHIN

The head cannot be properly suspended if the chin is not tucked in. Only then can the Baihui point on the top of the head be correctly positioned and the nasal respiration kept free.

Tuck the chin and slightly lean forward to stretch and straighten the spine. You should feel the stretch all the way down into the coccyx. Next, slowly shift the weight backwards, stacking each vertebra on top of the next, starting from the bottom of the coccyx and sacrum and moving upwards.

RULE 16—CLOSE THE EYES FOR INNER VISION

The Chinese have a saying: "close the curtain." This refers to dropping the eyelids to facilitate inner-vision, and focusing on any specific areas where Qi is being trained or circulated. The eyes are of great importance in Medical Qigong exercises. It is said that the functional activities of Qi are determined by the eyes, and that the eyes are the messengers of the mind, and the mind is the residence of the Shen.

Completely closed eyes induce an absolute Yin state which is generally used in meditations for tonifying any Deficiencies. However, when used excessively (with all Yin and no Yang energy), the Qi can become too inactive.

Completely open eyes induce an absolute Yang state which is generally used in meditations for dispersing any Excesses. However, if overused, or if the patient has an Excess Yang condition, this type of meditation can make the practitioner too restless.

When the goal is to regulate the body's energy, slightly open the eyes in order to leave a small thread of light inside the eyes. This will keep the Yang (light) within the Yin (dark), so that the Qi will be more balanced. Because energy leaves the body through the eyes, after performing various Medical Qigong exercises, or prescriptions, allow your eyes to close halfway to continue the cultivation of life-force energy.

Tightly shutting the eyes causes tension in the upper and lower eyelids. Closing the eyelids gently, however, will restrain the vision, which helps to calm the Shen and the mind.

When meditating, if the eyes look to the distant horizon, they should not be focused but stare into infinity, this technique is also called the One Thousand Yard Stare, and it helps in regulating the venous pressure in the cranial cavity.

Strive for balance. Each eye has its own specific responsibility and energetic function.

- The right eye is generally used to project intention and extend emotion, energy, and spirit out from the body. The right eye relates to Water, the Kidneys, Qi, moon, Yin, Earth, Metal, and the Po.
- The left eye is generally used to receive, drawing in images, emotion, energy, and spirit into the body. The left eye relates to Fire, the Heart, Shen, sun, Yang, Heaven, Wood, and the Hun.
- If both eyes look upwards towards the Upper Dantian, the body's energy will draw up into the infinite space of the Wuji and merge with the divine.
- If both eyes look towards the tip of the nose, the Middle and Lower Dantians are linked together for transforming Yuan Qi.
- Crossing the eyes results in the union of the Wood and Metal, the elements of alchemic transition, for increasing the development of psychic energy. This intensification of psychic development is due to the union of the Hun and Po within the body, and is said to connect the meditator with his or her Yuan Shen.
- After meditation, store the Qi of the eyes behind the posterior orbital surface of the eyeballs themselves. This prevents the eyes from overheating and drying out.

RULE 17—CLOSE THE MOUTH AND TURN YOUR HEARING INWARD

In order to enhance the Yang during Medical Qigong exercises, close the lips with the teeth gently touching. Closing the lips will prevent the internal Qi from flowing out.

The Chinese use the expression: "Stopping the ears," which means to focus the hearing inward so as to be free from outside interference.

RULE 18—TOUCH THE TONGUE TO THE UPPER PALATE

When the tongue touches the upper palate, it forms what is called the Bird's Bridge. The connection of the tongue links both the Governing Vessel (which ends at the nose and upper palate) and the Conception Vessel (which ends in the mouth). As the tongue touches the upper palate, the body's field of Wei Qi expands. This can help to eliminate diseases and prolong life. The belief is that when someone has a disease, the Governing and Conception Vessels are to some extent disconnected.

Some Qigong doctors test their patients' progress by having them meditate with their tongue suspended in their mouth. Upon command, they connect the tongue to the upper palate. The suddenly increased expansion and strength of the patients' Wei Qi, observed by the doctor, indicates the degree of their progress.

1. The technique called "Gathering the Saliva," begins when the tongue touches the upper palate, causing the saliva secretion to be increased. Saliva contains many enzymes, which not only aid digestion, but also benefit the patient's physiology. In ancient China, this practice was called Gathering the Immortal's Water or the Juice of Jade to create the Immortal Pill.

   There is an exchange of Yin and Yang energy within the saliva, as Heaven Qi and Earth Qi are gathered within man's Fluid Essence in order to create the Immortal Pill.

   Before swallowing the saliva, it is important to tilt the head slightly forward (after inhaling). Swallow the saliva three times with three big gulps, using the breath as a cork to enclose the saliva. Send the Immortal Pill, i.e., the combined saliva and air down the Conception Vessel, bathing the Five Yin Organs, and ending at the Lower Dantian. Next, draw the energy up the Governing Vessel into the brain to replenish and nurture the Upper Dantian.
2. There are Five Elemental Tongue Positions. Each tongue position is related to one of the Five Yin Organs and can be used to direct the Qi to that specific organ. Sometimes, while practiscing Medical Qigong prescriptions, if too much Heat is created, the patient will be instructed to "change the tongue position" as well as meditation. These Elemental tongue positions are described as follows.
   a. The Earth (Spleen) position requires that the tongue be placed on the bottom of the jaw at the base of the lower palate, beneath the teeth and gum line (Figure 15.32).
   b. The Metal (Lungs) position requires that the tongue be placed between the maxilla and mandible bones, suspended, behind the teeth (Figure 15.33).
   c. The Fire (Heart) position requires that the tongue be placed on the hard palate, at the front of the upper palate, behind the teeth and gum line (Figure 15.34).
   4. The Wood (Liver) position requires that the tongue be placed on the hard palate, at the middle of the upper palate at the center of the roof of the mouth (Figure 15.35).
   e. The Water (Kidneys) position requires that the tongue be placed on the soft palate, at the back of the upper palate (Figure 15.36).

DYNAMIC POSTURE DAO YIN TRAINING

While Static Qigong exercises accumulate and strengthen the Qi internally, Dynamic Qigong exercises train the channels, collaterals, muscles, and bones externally. The more dynamic movement a patient makes, the more the energy will be converted and transformed inside the body. When dynamic movement is discontinued, some of the accumulated energy will begin to dissipate, while the remainder will flow through the channels and increase the patient's Qi circulation.



Figure 15.32. For the Earth position, which is related to the Spleen, the tongue is placed on the bottom of the jaw at the base of the lower palate, beneath the teeth and gum line.



Figure 15.33. For the Metal position, which is related to the Lungs, the tongue is placed between the maxilla and mandible bones, suspended, behind the teeth.



Figure 15.34. For the Fire position, which is related to the Heart, the tongue is placed on the front of the upper palate, behind the teeth and gum line.



Figure 15.35. For the Wood position, which is related to the Liver, the tongue is placed on the middle of the upper palate at the center of the roof of the mouth.

The lymphatic system is pumped by normal muscular contraction. When a patient performs Dynamic Postural Movements, the lymphatic system is flushed, thus freeing the body of toxins.

Dynamic Qigong is divided into two methods of training: The Yun (Yin) Method and the Dong (Yang) Method.

1. The Yun Method is a more Yin approach, and employs slow, even, graceful movements. The focus of the mind's intention is placed on the internal organs, resulting in emotional relaxation.
2. The Dong Method is a Yang approach, and employs intense physical movements. Focus is placed on the movement of the body's ex-



Figure 15.36. For the Water position, which is related to the Kidneys, the tongue is placed on the soft palate at the back of the upper palate.



Figure 15.37. Hands Rise, Leading to the Ascending of the Qi.



Figure 15.38. Hands Fall, Leading to the Descending of the Qi.

tremities, resulting in tissue regulation.

Both Yin and Yang (Yun and Dong) training methods must be balanced when prescribing proper Medical Qigong exercises. With the Yin method, the patient will experience external quietness with internal energetic movement. With the Yang method the patient will develop internal quietness with external, physically active movement.

USING THE ENERGY OF THE HANDS TO LEAD QI

Dynamic Postural training is performed by the extensive movements of the hands and torso. Because the palms have a stronger electromagnetic field than any other part of the body, the hands are used for leading and guiding the Qi. These movements are in harmony with the rotating, bending and stretching movements of the head, neck, torso, and limbs. Any change of the body's position or movement can change the direction or position of the electromagnetic fields of the hand. Likewise, any change or movement of the hands or palm positions, also changes the direction and flow of the electromagnetic field of the body. In Medical Qigong therapy the Dao Yin Hand Techniques have the following four functions:

- Hands Rise—Qi Ascends (Figure 15.37)
- Hands Fall—Qi Descends (Figure 15.38)
- Hands Open—Qi is Spread (Figure 15.39)
- Hands Close—Qi is Restrained (Figure 15.40)

The positions of these hand techniques can be further divided into three ranges: upper, middle, and lower. These ranges can relate to either the position of the body's Triple Burners, or the body's three Dantian areas, depending on the specific Medical Qigong prescription, and the doctor's intention for the exercise. The directions of these hand movements can further divide a posture into four front and four oblique types of Qi regulations. Moreover, depending on the arm movements, each posture can be divided into Yin (palms facing down) or Yang (palms facing up), as well as half Yin or half Yang regulations (Figure 15.41).

The actions of these methods supplement, regulate, smooth, and reinforce the vital Qi. Using these techniques will improve Blood and Qi circulation, as well as sharpen the sensory nerves. Since all hand postures relate to the brain and the function and flow of the body's energy, they also have a psychological and physiological affect on the nervous system.

When training, posture and Qi movement are



Figure 15.39. Hands Open, Leading to the Spreading of the Qi



Figure 15.40. Hands Close, Leading to the Restraining of the Qi

sometimes in unity, and at other times proceed in opposite directions. Raising the arms, for example, causes the energy to rise; if the torso also rises, the rising power of the energy increases. This is an example of synergistic promotion of Qi regulation.

The following are three examples of the use of each separate hand action, and demonstrate how the body's reaction to energy can be used to treat patients with Medical Qigong therapy.

1. If you have hyperactive ascending Qi (e.g., hypertension) place your hands, palms facing downward, at the side of your body. Inhale quickly and move your hands quickly upward. Allow the middle fingers on each hand to touch each other, connecting the Pericardium Channels. Exhale, while slowly moving the hands downward along the front and side of the body. Purge and guide the Toxic Qi to descend the Liver and Gall Bladder Channels down the


Four Hand Techniques
(Ascend, Descend, Spread, Restrain)
Three Ranges
(Upper, Middle, Lower)
Four Front Directions
Yin and Yang Postures
Four Oblique Directions
Yin and Yang Postures

Figure 15.41 Hand Position Techniques

torso to the hips (GB-30), and then to the outside of the legs (Figure 15.42).

2. If you have a Yin and Yang imbalance (e.g., chronic illness) place your palms facing your Lower Dantian and slowly raise them upwards to the chest. At the level of the Heart, turn the palms away from the body as you move your arms outward. Once the hands are extended away from the body begin moving them downward. Regulate the speed of motion of the hands and breath in order to guide and induce the Clear Yang to ascend (as you raise your arms), allowing the Turbid Yin Qi to descend (as you lower your arms). This balances the body's Yin and Yang Qi (Figure 15.43).
3. If you have a Deficiency of ascending Qi (e.g., hypotension or prolapse of the viscera) begin with the palms facing upward, in front of your Lower Dantian. Slowly inhale while gradually raising the palms close to your body. When exhaling, move the hands downward quickly away from the body to avoid any excessive downward flow that would counteract the tonifying upward flow (Figure 15.44).

MEDICAL QIGONG WALKING THERAPY

Dynamic postural training can be performed by keeping the feet stationary and rocking the weight between the heels to the balls of the feet, or by walking. The Chinese saying, "The body must walk like the wind," describes the relaxed placement of the feet and supple stepping techniques used in Medical Qigong Walking therapy. Walking, or Toe-Raised Stepping, as it is commonly called in China, is excellent in treating the diseases of the Five Yin Organs. It can stimulate the Qi of the Spleen and Liver (due to their channels originating on the big toes), and can cause the body's internal Qi to rise and flow vigorously, thus reinforcing the function of Qi and Blood.

With each step of the Walking Meditation, the patient should practice tranquil mind and body balancing. This is the same imaginative technique as is used in standing, sitting, or lying meditations. The inner stillness and outer motion are in harmony. Touching the heel to the ground, with the



Figure 15.42. With palms facing downward (1), move the hands quickly upward (2). As the hands move slowly downward (3), allow the middle fingers on each hand to touch (4).



Figure 15.43. With palms facing the body (1), move the hands upward (2). Face the palms away from the body (3) as the hands move downward (4).



Figure 15.44. With the palms facing upward (1), raise the hands slowly close to the body (2). When moving the hands downward (3) in order to start again, quickly move them away from the body (4).

toes raised can also activate the Yin and Yang Heel Vessels (which originate from the center of the heel), and allow the energy to flow between both vessels so that the internal energy, exiting from the Yin Vessel, can enter the Yang Vessel, and vice versa. This allows the vessels to be dredged and the Yin and Yang energies to be regulated.

The heel is also stimulated when stepping, thus increasing the flowing action of the Bladder and Kidney Qi (due to their channel placement on the ankle). While stepping, focus the intention on the Lower Dantian to guide downward any abnormal rising of Lung Qi, which can cause shortness of breath, and affect the Heart and blood pressure. Each step is placed deliberately, with intention, and without collapsing of the feet. This stepping action relieves any Excess Qi syndrome of the upper torso and coordinates the balance of both the upper and lower portions of the body's Qi. Medical Qigong walking therapy consists of three training methods.

1. The Preparation (before walking), consists of the following steps:
   - The Opening and Closing of the Three Dantians, and
   - The Stationary Qi Strengthening and Regulating Exercises.
2. The Walking Therapy, consists of one or several prescriptions of the Toe Raised-Stepping techniques.
3. The Ending (after walking), consists of the following steps:
   - Leading the Qi back into the Lower Dantian,
   - Kneading the abdomen, and
   - Closing the Dantians and self-massage.

THE FUNCTIONS AND BENEFITS OF THE PREPARATION STAGE (THE OPENING AND CLOSING OF THE THREE DANTIANS)

Before beginning Medical Qigong Walking Therapy, the Opening and Closing of the Three Dantians must be practiced. In Medical Qigong training there is a saying, "When the body is Open, the Evil Qi will be expelled. When the body's surface is free from Evil Qi, it is better to Close it." The terms "opening" and "closing" refer to the purification of the body by means of Opening (purging) and Closing (sealing) specific areas of the body. The Opening and Closing of the Three Dantians can regulate either an Excess or Deficiency syndrome that is caused by an imbalance between the upper and lower, or interior and exterior parts of the patient's body. The purpose of the preparation stage is to:

- Eliminate the body's Evil Qi,
- Descend the Turbid Yin Qi, and
- Circulate the Clean Yang Qi through the organs and channels before walking.

The focus of this particular technique opens and closes the Upper Dantian (at the Yintang point), the Middle Dantian (at the Shanzhong CV-17 point), and the Lower Dantian (at the Qihai CV-6 point).

The Opening and Closing technique utilizes four specific disciplines:

- Using the Mind's Intention,
- Dividing the Yin and Yang Energy (ascending the Clear Yang Qi and descending the Turbid Yin Qi),
- The Hand Postures for Opening and Closing the Dantian, and
- The Focus on the Breath.

The Opening and Closing of the Three Dantians also requires multiple soft focusing that becomes easier with each practice session. Arm movements and the breath need to be perfectly coordinated; the expelling of Toxic Qi from the internal organs needs to be visualized; and the abdomen needs to be contracted while inhaling, and expanded while exhaling. The mind's intention must assist in the Opening and Closing of each Dantian, the coordinated movements alone do not suffice.

1. When focusing the mind's intention while performing the Opening and Closing techniques, imagine a dark Turbid energy from deep inside the body exiting through the body's pores. As the energy leaves, seal off the tissues to prevent it from returning to the body. Imagine the dark Turbid energy being absorbed into the ground, and being purified by the Earth.
2. The Dividing the Yin and Yang Energy refers

to separating the Yin and Yang energy within the body for healing. The Yin Qi stores the substance of vital energy, and the Yang Qi guards against pathogenic Evils and protects the body.

a. Ascending the Clear Yang Qi. When the Upper Dantian is Opened and Closed it allows the Clear Yang Qi to ascend to the upper orifices. The increased circulation of Clear Yang Qi through the channels and organs of the body stimulates and energizes the body's surface, as well as strengthens the four extremities. When the Clear Yang Qi moves upward its pure nature helps to tranquilize the Shen.
b. Descending the Turbid Yin Qi. When the Middle and Lower Dantians are Opened and Closed, it allows the Turbid Yin Qi to descend and facilitates the storing of the Clear Yang Qi.

3. The hand postures for Opening and Closing the Dantian is described as follows. The action for the Opening of Qi is directed by the outward movement of the hands and arms, and the mind's intent on Opening (or expanding) the abdomen.

   The Closing of Qi is directed by the inward movement of the hands and arms towards the abdomen, and the mind's intent on Closing (or contracting) the abdomen.

   The function of the Dao Yin Posture training, while regulating the breath and reinforcing the body's Qi, relies primarily on the movement of the hands and arms to arouse and invigorate the Qi circulating in the Large Intestine and the Lungs' channels. The action of opening and closing the Upper, Middle and Lower Dantians causes the Turbid Yin Qi to descend and be expelled, while the Clear Yang Qi ascends to the upper orifices of the body.
4. The focus is placed on the breath. The Opening and Closing exercise uses Reversed Breathing, i.e., the abdominal muscles contract while inhaling and relax and expand during exhalation (Figures 15.45 and 15.46).


Exhale while separating the hands and arms.
Expand the abdomen.

Figure 15.45. The Opening of Qi is directed by the outward movement of the hands and arms and an opening (or expanding) intention in the abdomen.

This method of breathing is also referred to as Daoist breathing. The action of abdominal compression acts as a bellow to purge any Toxic (Yin) Qi from the body. These contractions and expansions of the abdomen are combined with the mental focus on the Lower Dantian. The nerve plexuses in the Lower Dantian area are considered, in modern Medical Qigong theory, to connect the Tai Yang Channels (Major Yang channels). If the mind is concentrated on the Lower Dantian for a long period of time, a conditioned reflex will occur that causes the nerve plexuses to produce bioelectricity, which spreads into the surrounding areas of the Tai Yang channels. This reflex causes the small blood vessels and capillaries to dilate. This reaction reduces the pressure in the blood vessels and improves Blood circulation to the Heart.

- Contraindications:

  It is important to note that Reversed Breath-


Inhale while bringing hands and arms together.
Contract the abdomen.

Figure 15.46. The Closing of Qi is directed by the inward movement of the hands and arms toward the abdomen for a closing (or contraction).

ing is contraindicated for young children, older patients and for people suffering from high blood pressure, stroke, or Heart diseases. In these cases, the Reversed Breathing techniques should be replaced with Natural Breathing. When practicing with Natural Breathing, the patients imagine Heavenly Qi descending into their body, filling and expanding the Lower Dantian, as they inhale. This expansion of the abdomen (upon inhalation) allows their Lower Dantian to Open, causing the Heavenly Qi to naturally purge the body of Toxic Qi. Upon exhalation, the patients contract their lower abdominal muscles to Close and seal their Lower Dantian.

THE OPEN AND CLOSE THE THREE DANTIANS METHOD

Normally an exercise begins with an equal number of inhalations and exhalations receptively, as the arms move toward the body, and away from the body. In this particular exercise, however, when approaching each separate Dantian, the first Open and Close action is to be performed by inhaling through the entire movement, without any exhalation. This action stimulates the opening of the Dantians. For the second through fourth Open and Close movements, the patients exhale when Opening and inhale when Closing. Practice the Opening and Closing of the exercise, step by step.

- Begin from Wuji posture. Raise your arms and hands to face the Upper Dantian. As you inhale, sperate your arms outward away from the body as you contract the abdominal muscles, then while still inhaling, bring the arms back to the Dantian. Exhale as you separate the arms away from the Dantian, allowing the abdomen to expand, inhale and contract the abdomen as you bring the hands back together. Repeat this action two more times.
- Place your arms and hands in front of your Middle Dantian. As you inhale, separate your arms outward away from the body as you contract the abdominal muscles, then while still inhaling, bring the arms back to the Dantian. Exhale as you separate the arms away from the Dantian, allowing the abdomen to expand; inhale and contract the abdomen as you bring the hands back together. Repeat this action two more times.
- Place your arms and hands in front of your Lower Dantian. As you inhale, sperate your arms outward away from the body as you contract the abdominal muscles, then while still inhaling, bring the arms back to the Dantian. Exhale as you separate the arms away from the Dantian, allowing the abdomen to expand; inhale and contract the abdomen as you bring the hands back together. Repeat this action two more times.

STATIONARY REGULATING EXERCISES (PREPARATION FOR WALKING)

This next preparation exercise is good for the patient's general tonification and for increasing respiration for Lung cancer patients.

- Start from a Wuji posture, inhale and exhale through the nose. Place your palms facing your lower abdominal area and begin extending Qi into the naval. Imagine the energy flowing into your navel, extending deep into your Mingmen and Lower Dantian area (Figure 15.47).

- Next, face your palms toward the ground and absorb the Earth Qi into your Lower Dantian (Figure 15.48). Absorb the Earth's energy for a few minutes.
- Turn your palms upwards, towards the Heavens, and begin absorbing the Universal Qi for several minutes (Figure 15.49). Finally, begin to close the exercise by allowing your palms to turn back towards your navel, absorbing and rooting the Qi back into the Lower Dantian

WALKING COMBINED WITH COLOR THERAPY

In China, to help visualize specific colors for therapeutic use, patients will carry brightly colored silk ribbons while walking. The colors and their affect on the internal organs are matched in accordance with the Five Elemental colors.

WALKING COMBINED WITH SOUND THERAPY

In China, in order to help the patients step with a structured rhythm, coordinate breathing patterns, and improve mental intention, Medical Qigong practitioners beat large wooden drums, click wooden sticks, and clang large metal cymbals. These rhythmic wooden and metal sounds resonate the walking area with an energetic field vibrating with Yin and Yang Qi. The patients, while walking in a circle, naturally absorb the Yin and Yang energy resonating from the instruments and seek to naturally regulate their internal organs.

THE THERAPEUTIC EFFECTS OF MEDICAL QIGONG WALKING THERAPY

The purpose of "raising your toes when stepping" is to invigorate the Yin and Yang channels and vessels of the legs. The energetic nature of the Spleen necessitates walking slowly during this exercise. The Spleen is the source of Postnatal Energy and is responsible for the activity of the muscles and extremities. The movements of the four limbs therefore strengthen the Spleen; this is why "toe-raised walking" and the "hand swaying" methods have both been adopted into the exercises and postures of most Medical Qigong therapies.



Figure 15.47. Begin by placing the palms toward the navel, in order to stimulate the Lower Dantian Qi.

Waist rotation plays a leading role in regulating the Liver Channels, as well as invigorating the circulation of Kidney Qi. This is achieved through all activities that initiate the actions of dropping, bending, relaxing, and turning the waist.

The opening and closing actions, combined with the rising and falling movements, and the swaying action of all four limbs, promote a pumping action within the muscles. This action is further intensified with the bending and leaning of the upper body, squatting and crouching of the lower body, and the alternate weight shifting when stepping. This pumping action greatly benefits the circulation of the lymphatic system.

Clinically, the Medical Qigong walking exercises result in increased appetite, strengthening



Figure 15.48. Next, begin to absorb the Earth energy into the Lower Dantian and Mingmen areas.



Figure 15.49. Turn the palms up to absorb Heaven Qi into the Lower Dantian Area.

of the patient's body, tonification of the Kidneys, Lungs, Liver, and Spleen, and the strengthening of Heart function.

Cancer patients need to regulate the function of their tissues and Yin and Yang organs to increase their healing potential. The initial goal in treating cancer with Medical Qigong, is to have the patient focus on the condition of the tumor, and its collection of energy. The patient imagines that the tumor area is beginning to soften, and the tissues are gradually transforming back into insubstantial energy. This technique is used to gradually dissolve tumors and certain types of less aggressive cancer.

The following are examples of Toe-Raised Slow Walking therapeutic exercises and prescriptions used in Medical Qigong therapy:

- Dynamic Regulation Walking Therapy
- Lung Tonification Walking Therapy
- Kidney Tonification Walking Therapy
- Liver and Spleen Tonification Walking Therapy
- Heart Tonification Walking Therapy
- Cancer-treatment Prescriptions

The explanation of these walking and breathing exercises and prescriptions are described as follows:

1. Dynamic Regulation Walking Therapy is a good exercise for regulating the Yin and Yang Qi of the patient's entire body. It can be prescribed for general tonification and nourishing of the patient's body, as well as strengthening the "anti-pathogenic" or True Qi. The Dynamic Regulation Walking Therapy is the primary walking exercise used to treat cancer patients.

In every exercise the patient starts and ends with the Opening and Closing the Lower Dantian method. When stepping, the toes should be raised with the heels touching the ground (rocking back and forth), stimulating the Yin and Yang Heel Vessels of the legs, to strengthen the Kidney and Bladder Channels. As you step forward with the heel of the right foot, the Kidney and Bladder Channels open up. Swing your left hand up to the center of your Heart (CV-17 point) while your right hand swings to your right hip around and near the GB-30 point (Figure 15.50).

It is important to utilize the mind's concentration in conjunction with the breath. The breathing pattern is as follows:

- First step—inhale through the nose
- Second step—inhale through the nose
- Third step—exhale through the mouth
- Fourth step—hold the breath

The same details of stepping and hand movements apply to stepping forward with the left foot.

2. Lung Tonification Walking Therapy is a good exercise for tonifying the Qi of the patient's entire body. It can be prescribed for nourishing the patient's skin, as well as strengthening the True Qi. It is used for treating Lung Qi Deficiencies, bronchitis, tuberculosis, asthma, emphysema, and sinusitis.

The heel stepping pattern is similar to the Dynamic Regulation Walking exercise, however, when stepping, the hand postures will now switch from a normal relaxed position to the thumbs and first fingers touching at the tips (Figure 15.51).

Some Medical Qigong hospitals encourage the patients to rub their thumb and index fingers together when practising the Lung Tonification Walking Therapy. This rubbing action causes friction to develop between the Shaoshang Lu-11 and the Shangyang LI-1 points, which in turn stimulates and invigorate the flow of Qi along the Lung and Large Intestine Channels, strengthening the Lungs.

The breathing pattern is as follows:

- First step—inhale, inhale
- Second step—inhale, inhale
- Third step—exhale
- Fourth step—no breath

3. Kidney Tonification Walking Therapy. This exercise will purge the Liver Fire and tonify the Kidney Yin. It can be prescribed for patients who suffer from Kidney Qi Deficiencies, edema, blood diseases, gynecological diseases, and cancer of the Kidneys.



Figure 15.50. With each step, the opposite hand swings up to the Heart and Middle Dantian area.



Figure 15.51. Tonification Hand Position for the Lungs

Begin this exercise with the palms embracing an imaginary ball at the naval and Lower Dantian area. This walking therapy causes the Qi to tonify your Lower Dantian.

Step forward so that the toes of the right foot touch the ground first, followed by the heel. This stepping action will open up the Yang Channels on the outside of your foot. Next, step with the left heel and point the toes up. This stepping pattern should be toe, heel, then step with heel (Figure 15.52).

On the first step, inhale through the nose while imagining the Qi filling your thorax. On the second step, sound the tone "Xu" (pronounced Shu) as you exhale. This particular sound is used to purge Toxic Liver Qi out the patient's body, allowing the Kidneys to fill with the rising Earth Qi.

- First step—inhale
- Second step—exhale "Shu"

The breathing pattern is as follows: inhale for the toe and heel, step and exhale on the heel step (all three actions equal one set). After walking in a circle for nine complete rotations, pause and begin again, starting with the left foot as the downward foot that makes the toe heel step as you exhale.

While stepping, keep both palms on your Lower Dantian. Regulate your breathing, while drawing the Earth Qi upward from the Yongquan Kd-1 point at the bottom of each foot. Press the Mingmen area backwards while breathing in the Earth Qi; this reinforces the Kidneys' Yuan Qi.

When ending the Kidney exercise, place both hands at the center of your chest at the CV-17 point. For men the right hand is on the outside, the left hand is on the inside, touching the chest. The hand position is opposite for woman. Make the sound "Shu" three times. End with the Opening and Closing of the Lower Dantian.

4. Liver and Spleen Tonification Walking Therapy activates the Liver's function of storing Blood and the Spleen's function of transforming Blood. It is used to treat digestive and blood diseases, hepatitis, Liver cancer, sclerosis of the Liver, and Gall Bladder stones.



Figure 15.52. The Kidney Strengthening Step is as follows. While stepping, place both palms on the Lower Dantian, regulate your breath and draw the Qi upward from the bottom of each foot. Press your Mingmen area backwards while breathing in the essence of the Qi.

The starting position is similar to the exercise for tonifying the Kidneys with the toes pointing down, except that you step forward with the left toes. Step forward so that the toes of the left foot touch the ground first followed by the left heel. While this step is taken inhale twice through the nose. Then step out 45 degrees with the right heel while inhaling twice more through the nose. Next, step out with your left heel 45 degrees, exhale through your nose twice, then step out with your right foot with the toes pointed down as you exhale once.

- First step—inhale, inhale
- Second step—inhale, inhale
- Third step—exhale, exhale
- Fourth step—exhale

When walking with the toes raised, let the big toe touch the ground to stimulate the Yinbai Sp-1 and the Dadun Lv-1 points on the big toe. This promotes the ascension of the Qi flowing upward along the Liver and the Spleen Channels. The internal energy of these two channels is then reinforced, and the Liver and Spleen are strengthened.

After walking in a circle for nine complete rotations, pause and begin again starting with your right foot. Spleen and Liver Channels are activated when the toes pull up and the heel steps down.

The hand postures are as follows:

a. For Spleen problems the thumbs touch your ring fingers only when you step out to the fourth step (Figure 15.53).
b. For Liver problems the thumbs continuously touch your ring finger.

5. The Heart Tonification Walking Therapy calms the mind while tonifying the Qi and Blood. It is used for treatment of coronary Heart diseases, arthritis, palpitations, and angina pectoralis.

The starting position is the same as for the Liver and Spleen Walking therapy. The stepping is exactly like the last exercise, with the exception of the hand positions. In this exercise, the hands are opened and relaxed until they reach the chest (CV-17 point) at which point the middle fingers of each hand touches the Pc-8 point at the center of each palm (Figure 15.54).

When breathing, focus your Mind on inhaling the Qi upward from the Earth. When exhaling, imagine that the Qi within your chest is flowing downward.

- First step—inhale
- Second step—exhale

This walking exercise is practiced at a slightly slower speed then the previously described exercises. On the third step, the middle finger of each hand touches the center of your palms. This stimulates the Zhonchong Pc-9 point on each finger and is used to invigorate the flow of internal energy along the Pericardium Channels.

THREE STEPPING METHODS USED TO TREAT CANCER

These supplementary Medical Qigong Step-



Figure 15.53. Hand Position for Tonification of the Liver and Spleen



Figure 15.54. The Heart Strengthening Step is practiced at a slightly slower speed. On the third step, the middle finger of each hand touches the center of the palm.


The Fast Walking Method
(for Liver, Lung and Stomach Cancer)
1st Step - **Inhale**
2nd Step - **Exhale**
70 - 100
Steps per Minute
The Moderate Walking Method
(for Gastric and Intestinal Cancer)
Inhale - Exhale
Each Step
60 - 80
Steps per Minute
The Slow Walking Method
(for Kidney and Urogenital Cancer)
Each Step
Inhale - Inhale - Exhale
Heel
Toe
Under- 60
Steps per Minute

Figure 15.55. Cancer Walking Therapy

ping exercises are given to cancer patients for breath regulating and Qi reinforcement. These breathing methods are applied with the Dynamic Regulation Walking therapy (the first walking exercise taught in this section). These walking methods use the "exhaling method" to strengthen the Kidneys, increase oxygen intake and enhance the patients' immune system.

The stepping methods are performed at three different speeds depending on the patients' symptoms (Figure 15.55). The patients are encouraged to walk at least once a day for 15-20 minutes. These walking exercises are classified into three kinds of prescriptions according to the following breathing rates.

THE FAST EXHALING METHOD

This walking method is mainly prescribed for patients in the early stages of cancer and is especially suitable for patients with Liver, Lung, and Stomach cancer. This exercise is practised using even breathing, inhaling for one step, followed by exhaling for another step. The patient steps out with the left foot, while inhaling through the nose. Then steps out with the right foot, and exhales through the nose. Both hands swing naturally up to the chest, while walking.

The main point to remember while stepping, is that the head leads the waist in turning and swinging the arms. The speed should be 70-100 steps per minute. When practicing the Fast Exhaling method it is important not to overexert yourself, as this would be counterproductive, and would lead to depleting the immune system.

THE MODERATE EXHALING METHOD

This walking method is mainly prescribed for patients in the early stages of cancer and is especially suitable for patients with gastric and intestinal cancer. The patient breathes in and out through the nose with each step taken. When taking each step, focus is on the respiratory rhythm. The speed should be between 60-80 steps per minute.

THE SLOW EXHALING METHOD

This walking method is mainly prescribed for patients with Kidney and urogenital cancer. The patient steps out with the left foot first and then with the right foot. Each step is accompanied by two inhalations and one exhalation. The patient steps out with the heel while taking two inhalations and then touches the ground with the ball of the foot, while exhaling. Because one step involves three breathing movements, the walking speed should be a bit slower, under 60 steps per minute.



Figure 15.56. Secure the Upper and Middle Dantians in order to come to a tranquil state of relaxation.

ENDING AND CLOSING THE WALKING THERAPY

To end the Medical Qigong Walking therapy, the following exercises are taught to the patients in order to bring their Qi back into their Lower Dantian and to return to a state of quiescence. The Ending and Closing procedures are divided into three forms of practice: (1) Leading the Qi back into the Lower Dantian; (2) The official Closing of the prescription; and (3) Self-massage Regulation. These three ending procedures are described as follows.

LEADING THE QI BACK INTO THE LOWER DANTIAN.

This particular exercise is divided into four separate stages: (1) Securing the Three Dantians, (2) Kneading and Rooting the Lower Dantian, (3) Circle Massaging the Lower Dantian, and (4) Rooting the Qi.

1. The Securing the Three Dantians exercise has three purposes: to initiate a tranquil state of relaxation, to secure a harmonious balance of the body's Yin and Yang organs, as well as to bring the Qi back into the Lower Dantian.

   From a standing Wuji Posture, imagine embracing a ball of energy at the Lower Dantian (hold this posture for several breaths). After exhaling, separate the hands without inhaling, moving, and massaging the Qi along the hub of the body's Belt Vessel (at the waist).

   Inhale and begin raising the palms above the head. Imagine inhaling the Earth Qi into the body while the palms are facing the ground. At hip level, rotate the palms to face the sky, and begin inhaling Heaven Qi into the body. Continue raising the palms until they are positioned above the Baihui area on top of the head (left hand on top, opposite for women).

   Exhale and imagine the combined Earth and Heaven Qi flowing into the Taiji Pole, connecting all Three Dantians together. Descend the palms in front of the body, facing the Yintang, throat, Heart, upper abdomen (at the Yellow Court), and navel, then end by embracing the Lower Dantian. Begin again and repeat this exercise nine times (Figure 15.56).
2. Kneading and Rooting the Lower Dantian fills the Liver and Spleen with Blood and Qi, helping to further detoxify these organs.



Figure 15.57. Knead the abdomen 36 clockwise then 24 counterclockwise.

After performing the Securing the Three Dantians exercise, secure the Qi in the Lower Dantian and knead the abdomen until it is sufficiently stimulated.

3. Circle Massaging the Lower Abdomen combines the body's organ energy together, thus forming the One True Qi. This allows the body to alleviate any Excess or Deficient conditions which may be caused from the excessive accumulation of Qi, due to the previous Qigong Walking exercises.

   Begin at the navel and start to circle massage the lower abdominal area thirty-six times in a counterclockwise direction (the movement should be directed against the flow of Qi in the Large Intestine). Begin with small and end with large circles, completing the movements at the base of the Lower Dantian. Next, reverse the direction of Qi flow by circle massage twenty-four times in a clockwise direction (with the flow of the Large Intestine), starting with big and finishing with small circles that end at the base of the Lower Dantian (Figure 15.57).

4. Rooting the Qi is sometimes referred to as "leading the Qi back to its origin." Rooting, extending, and stabilizing the energy into the Lower Dantian will facilitate the regulation of the Conception Vessel, Lower Burner, and Water pathways. Rooting the Qi also tonifies the Kidneys, Qi, Blood, and Yuan Qi, and allows the Toxic Qi to be easily expelled from the body.

   Leave the hands on the Lower Dantian and push the Mingmen backwards while inhaling the Qi and heat from the hands into the Lower Dantian (right hand on outside, opposite for women).

THE CLOSING

The closing procedure should be initiated after each practice period. After three deep breaths, click your teeth together thirty-six times (to stimulate the Kidney Qi), then circle the tongue eighteen times in each direction (to stimulate the Spleen Qi). Circle thirty-six times from the bottom of the teeth to the back of the throat. Tilt your head forward slightly, then swallow the saliva three times while imagining the Clear Qi of Heaven and Earth mixing with the saliva and flowing down to the Lower Dantian.

SELF-MASSAGE REGULATION

This method shifts the attention slowly off the area of concentration, while leading the Qi back down to the Lower Dantian. After the mind disengages from the specific point, relax the body, slowly open the eyes and perform self-massage.

Self-massage includes rubbing the hands, bathing the face (rubbing the face with the palms), combing the hair with the fingertips, and dredging the Twelve Primary Channels.

1. After rubbing the hands to heat the palms, place both hands on the face, cup the eyes, and draw the heat in through the eyes, into the Upper Dantian.
2. Next, comb the hair with your fingertips and drain the Excess Qi from off the head and neck area (Figure 15.58).
3. Then, rub from the feet to the abdomen to dredge the three Yin channels of the feet (Figure 15.59).



Figure 15.58. After rubbing the hands to heat the palms, place both hands on the face and draw the heat in through the eyes and into the Upper Dantian (1). Next, comb the hair with the fingertips (2), and drain the excess Qi from the head and neck area (3).

4. Rub from the chest to the hands to dredge the three Yin channels of the hands (Figure 15.60).
5. Rub from the hands, shoulders and lateral sides of the head, down the sides of the chest and abdomen to dredge the three Yang channels of the hands (Figure 15.61).
6. Rub from the waist and hips to the feet to dredge the three Yang channels of the feet (Figure 15.62).

These closing and self-massage procedures should be performed seven times each, followed by stretching to end the exercise.



Figure 15.59. Rub from the feet to the abdomen (1–2) to dredge the three Yin channels of the foot.



Figure 15.60. Rub from the chest (1) to the hands (2-3) to dredge the three Yin channels of the hand.



Figure 15.61. To dredge the three Yang channels of the hand, rub from the hands (1), shoulders (2), and lateral sides of the head (3).



Figure 15.62. Continue down the sides of the chest (1) and abdomen (2). Next, rub from the waist and hips (3) to the feet (4) to dredge the three Yang channels of the foot.

CHAPTER 16
RESPIRATORY DAO YIN

THE PURPOSE OF RESPIRATORY DAO YIN

Respiratory Qigong therapy is often called Tu Gu Na Xin which means "expelling the old, drawing in the new." The purpose of Respiratory Dao Yin is to increase the intake and absorption of Clear Qi through regulating the breath. The extra absorption of Qi enhances the body's vitality, and harmonizes the Blood and Qi to promote health and eliminate disease.

Because the breath is also the link between the body and mind, by controlling the pace and quality of the breath, individuals can affect deep changes in their physiological functions. Breathing exercises have proven to be effective in reducing anxiety, depression, irritability, muscle tension, and fatigue. These techniques are also used in the treatment and prevention of agoraphobia, hypertension, hyperventilation, shallow breathing, and cold hands and feet.

THE ROLE OF THE LUNGS IN QI CULTIVATION

The Lungs control the body's Qi, although the Kidney Qi is responsible for aiding the Lungs by regulating the respiration (i.e., upon inhalation, as the Qi descends into the thorax, the Kidneys hold down and stabilize each breath). The Yuan Qi stored in the Kidneys must be continuously supplemented by the Gathering Qi derived from air, food, and water.

The internal absorption of air, food, and water rely on the smooth circulation of the Lungs' energy. Because of the significant role the Lungs play in absorbing universal and environmental Qi, the ancient Qigong masters placed a great deal of importance on breathing exercises. They believed that a patient's health and emotional condition were deeply affected by their breathing patterns, and by the amount of oxygen consumed in proportion to the amount of carbon dioxide released.

Through the study of these ancient Qigong observations, modern research confirms that relaxed and natural breathing patterns cause every tissue and cell to decrease its consumption of energy, while increasing its storage of Qi.

The ancient Qigong masters recommended that "vigorous breathing," in the form of Dynamic Breath Regulation, should be used when training Qi, and "gentle breathing," in the form of Quiescent Breath Regulation be used after training practice for nourishing and replenishing the Qi. Each breathing regulation exercise has long been considered a powerful prescription used to balance the patient's health.

DEEP INHALATION AND EXHALATION BREATHING METHODS

In breathing regulation exercises and prescriptions, the patient's inhalation is used to gather universal and environmental Qi into the body for tonification. Exhalation is used to eliminate Turbid or Toxic Qi from the body through purgation. Once the patients are in the prescribed posture, relaxed and free from distractions, they should, for example, exhale and imagine releasing Turbid Qi from out the mouth, nose, and pores of the body.

Clinical studies show that the Deep Inhalation of Medical Qigong prescriptions can have the following effects on the patient's body:

- increase stimulation of the sympathetic nervous system,
- cause the blood vessels to contract,
- raise the blood pressure, and
- increase the pulse rate.

On the other hand, the Deep Exhalation methods of Medical Qigong prescriptions can also have the opposite affects on the patient's body:



Dao Yin Breathing

1. Natural Abdominal Breathing Method
(increases Qi in the Kidneys and Lower Dantian)

2. Long and Deep Abdominal Breathing Method
(calms the Shen and creates feelings of euphoria)

3. Reverse Abdominal Breathing Method
(increases Qi flow to the extremities)

4. The Deep Exhalation Method
(excites the parasympathetic nerves, dilates the blood vessels and decreases blood pressure)

5. Abdominal Breath Holding Method
(invigorates the circulation of Blood and quickly improves the microcirculation of Qi and Blood)

6. The Windy Breathing Method
(stimulates the pituitary gland, and strengthens and regulates the endocrine system)

7. The Aspirating Method
(purges the internal organs of pathogenic factors)

Figure 16.1. The Seven Dao Yin Breathing Techniques

- increase the stimulation of the parasympathetic nervous system,
- dilate the blood vessels,
- lower the blood pressure, and
- decrease the pulse rate.

Deep exhalation helps to keep the body's Yin energy moving downward, and so has a downward regulating action on diseases caused by Yang Qi domination. Deep inhalation helps to keep the body's Yang energy moving upward, and has the effect of sustaining the Yang and tranquilizing the mind.

Students beginning Medical Qigong practice should focus their mind's intention primarily on the method of exhalation, to simultaneously stimulate the parasympathetic system and to relax. Once health is regained, patients will begin to alternate between deep inhalation and deep exhalation. This alternation produces a diastolic and systolic action of the blood vessels that also enhances the elasticity of the blood vessels' walls.

SEVEN DAO YIN BREATHING TECHNIQUES

The Seven Dao Yin Breathing Techniques are intended to regulate the symptoms caused by the Excess of Yang and Deficiency of Yin, which are characterized by too much energy in the upper part of the body and a weakness in the lower portion of the body.

Today, in China's Medical Qigong clinics, the breathing regulation exercises employ seven types of Dao Yin breathing techniques (Figure 16.1). Normally, all inhalation is done gently through the nose and exhalation is released slowly through the mouth. Inhalation and exhalation through the nose is also important, but should only be used when a higher state of "stillness" is obtained by the patient. This is to prevent the patient from falling back into his or her old shallow breathing patterns, until the Deep Abdominal Breathing method has been perfected.

1. The Natural Abdominal Breathing Method is also called Natural Breathing, and is used in

conjunction with mental concentration. In this method the abdomen expands upon inhalation and contracts upon exhalation. It naturally increases the body's peristaltic action, massages the internal organs, invigorates and increases the movement of Qi from the Kidneys into the Lower Dantian. Because of the differences in energetic physiology between men, women, and the breathing habits of each individual, Natural Breathing is further divided into Natural Thoracic Breathing, Natural Abdominal Breathing, and a combination of the two.

2. The Long and Deep Abdominal Breathing Method is also called Wen Huo Breathing. It is a gentle breathing method that consists of natural, deep, and full breathing. This results in a relaxed and comfortable feeling of euphoria. This method of breathing is performed as follows:
    a. At the beginning of the breath, inhale all the way down into the perineum, feeling the lower abdomen expanding in all six directions:
- from the bottom - at the base of the perineum,
- from the front - to the pubic bone and navel,
- from the back - to the coccyx and Mingmen,
- from the right - to the hip and lower ribs,
- from the left - to the hip and lower ribs, and
- from the top - at the base of the diaphragm.
    b. While continuing to inhale, feel the oxygen expanding and filling the upper thoracic cavity completely. The entire torso, from the perineum to the collar bones is expanded in six directions:
- from the bottom - at the top of the diaphragm
- from the front - to the solar plexus, Heart, and collar bones,
- from the back - to the base of the ribs, spine and top of the shoulders,
- from the right - to the rib area,
- from the left - to the rib area, and
- from the top - to the throat and neck area (Figure 16.2).
    c. Upon complete expansion, tuck the pelvic bowl under to increase the capacity of storing more energy. On the inhalation the pelvis performs a slight posterior tilt, on the exhalation the pelvis tilts slightly in the anterior direction. These actions will naturally ripple the spine. Exhale the breath from the upper thoracic cavity downward, to the lower abdomen.



Figure 16.2. Inhale all the way down to the perineum. Make sure that the anal sphincter is closed in order to keep the Qi full and expanded in the Lower Dantian.

3. The Reverse Abdominal Breathing Method is an example, and subcategory of Long and Deep Abdominal Breathing. This method is performed by contracting the abdomen (and anus) when inhaling and expanding the abdomen upon exhaling. This is the primary breathing method used in Qigong training for guiding and emitting Qi, because the quality of air pressure and exertion of energetic pressure is greater. The Reverse Abdominal Breathing method results in superior efficiency in leading Qi to the extremities and has a much greater effect in raising the Qi from the legs into the brain.

However, when prescribing Medical Qigong therapy to treat diseases and alleviate physical stress, the Reverse Abdominal Breathing Method is prohibited except for very specific conditions. The reason it is not encouraged in Medical Qigong prescriptions is because patients with clinical hypertension or Heart disease often practice Reversed Breathing automatically. Scientific studies confirm that 90% of these patients practice reverse breathing chronically, as do most individuals with anxiety problems. Reverse Abdominal Breathing can also cause a constriction of the blood vessels and thus exacerbate problems such as cardiac diseases (i.e., angina) and migraine headaches.

4. The Deep Exhalation Method is often referred to as Wu Huo, which means "vigorous breathing." It is conducted with strong conscious intent. It can excite the parasympathetic nerves, dilate the blood vessels and decrease blood pressure.

   When practicing the Deep Exhalation method, the patient expels the Qi through the mouth, followed by a shallow inhalation.

5. The Abdominal Breath Holding Method invigorates the circulation of Blood and reduces swelling within the tissues, quickly improving the microcirculation. This method is also used to deepen the breath by stopping or holding the respiration for a short period of time.

   One Abdominal Breath Holding Method, known as Two Breathings, consists of inhaling through the nose, deep into the Lower Dantian, with one breath, pausing, then exhaling out through the mouth. The pause should be sustained for as long as possible without feeling tension (although a feeling of slight pressure building up is normal). After practicing deep abdominal breath holding, the breath will begin to develop its own stopping patterns. This stage involves the discipline and interdependence of the Heart and mind (Emotion and Spirit) with the breath.

6. The Windy Breathing Method consists of inhaling and exhaling through the nose. It is often referred to as "Windy" because it employs shallow breathing which resonates in the nasal passages. This kind of breathing purifies and warms the air as it passes through the nasal tract, resulting in air oscillation which stimulates the pituitary gland, thus strengthening and regulating the endocrine system. This method is designed to be used by patients with Lung disease because "the Lung energy opens at the nose."



Figure 16.3. An example of tone resonation by aspirating the body's Excess Heat from the Liver is by using the sound "Shu."

7. The Aspirating Method refers to the method of drawing out by suction. This popular method can be used with healing sounds (or "tones") to purge pathogenic factors, or to regulate the body's internal organs. The pronunciation is based on resonating the sounds to stimulate specific organs such as the Heart, Spleen, Lungs, Kidneys, Liver and Triple Burners (Figure 16.3). There are two primary



Figure 16.4. The body has seven main spatial cavities, as well as individual spatial cavities that surround the Yin and Yang organs.

sound systems of tone resonation used in Medical Qigong therapy, The Six Healing Sounds and the Tumor and Cancer Tone Resonations. These two healing sound methods are described as follows.

- The Six Healing Sounds are used to regulate, strengthen or detoxify the body's Yin and Yang Organs. This healing sound system is generally prescribed for patients with acute, or less serious conditions such as indigestion, insomnia, or Excess Heat in the organs, etc.
- Tumor and Cancer Tone Resonation Therapy is used to vibrate and destroy malignant tissue and cell growth in patients with chronic and serious organ diseases (see Chapter 40). This healing sound system is prescribed for diseases such as cysts, tumors, and cancer.

The choice of organ, and the number of times to pronounce each sound or character, is determined by the physical and energetic constitution of each individual. Each sound vibrates a specific organ or organ system, and surrounding set of involuntary muscles. Through repetition, the muscles acquire a kinesthetic memory of the vibrational sound. The doctor, or patient, can then trigger this memory by mental concentration alone to produce the desired results. As the patient performs the Sound Therapy, not only are the channels and organs cleansed, but also the spatial cavities (or Orbs) which surround the specific organs (Figure 16.4). For more information on Sound Therapy, see Chapter 40.

RESPIRATORY GUIDING AND REGULATING

There are four Respiratory Dao Yin methods the Qigong doctor can prescribe to regulate the


Respiratory Dao Yin Breath Regulation Methods
1. The Counting the Breath Method
2. The Following the Breath Method
3. The Observing the Breath Method
4. The Listening to the Breath Method

Figure 16.5. The Four Methods to Prescribe Respiratory Dao Yin For Breath Regulation

patient's breath (Figure 16.5): Counting the Breath, Following the Breath, Observing the Breath, and Listening to the Breath.

1. The Counting the Breath Method can be utilized to eliminate distractions of the mind during Walking Qigong Therapy by having patients silently count the number of their breaths. This method is also performed silently to regulate the body. In this particular method, one inhalation and one exhalation equals one breath.
2. When practicing the Following the Breath Method, the patients will contemplate each inhalation and exhalation of breath without counting. The patients mind, free from distractions or thoughts, follows each breath into and out of the body.
3. When practicing the Observing the Breath Method, the patients will observe their body's tissues conforming to the tranquil mental images from their subconscious imagination (e.g., relaxing, sinking, etc.).
4. When practicing the Listening to the Breath Method, patients are encouraged to listen to the "sounds" of their breathing (used in the Windy Breathing Method) to achieve a state of tranquillity.

RESPIRATORY TONIFICATION AND PURGING METHODS

Medical Qigong Respiration Therapy has its own unique methods and techniques for tonifying and purging the body's Qi. The primary technique used is focused concentration on the breathing. Through breath regulation, syndromes of Excess and Deficiency may be brought into balance either through tonification or through purgation.

1. Inhalation is used for tonifying the Qi in cases of Deficiency. The duration of the patient's inhalation should be longer than that of the exhalation. Tonification or Qi reinforcement patterns are created by applying the following methods:
   - more inhalation, and less exhalation
   - long inhalation, and short exhalation
   - focusing the mind on the inhalation
2. Exhalation is used for purging and reducing the Qi in cases of Excess. The duration of the exhalation should be longer than that of the inhalation. Purgation or Qi reducing patterns are created by applying the following methods:
   - more exhalation, and less inhalation
   - long exhalation, and short inhalation
   - focusing the Mind on the exhalation

BASIC ESSENTIALS OF RESPIRATORY TRAINING

Medical Qigong Respiratory training consists of the regulating, tonifying or purging exercises practiced in accordance with the doctor's treatment and specific homework prescriptions. There are four basic essential guidelines used to assist the patient in achieving maximum results in respiratory therapy, these guidelines consists of: Ensuring the Correct Posture Before Beginning, Purifying and Cleansing the Body's Qi, Tonifying and Purging the Qi, and Regulating the Body's Qi.

1. Before beginning Respiratory Dao Yin training, it is important that the doctor make sure the patient's posture is correct. When prescribing dynamic and static Medical Qigong therapy, it is best to start with a solid foundation and proper structure. Breath training should only begin when the patient becomes proficient in Postural Dao Yin, otherwise adverse effects may occur, (i.e., emotional trauma, headaches, chest stuffiness, or respiratory distress).
2. After their posture has been corrected, have the patients open their mouth and focus on their exhalation. As the patients exhale, they imagine all of the obstructed channels and collaterals being simultaneously purged of Turbid Qi. Each time the patients exhale they are to relax their body, more and more.

   Next, the patients close their mouth, and focus on inhaling clean, fresh Qi in to their body (through the nose). Have the patients practice this method using Natural Breathing. Each time the patients inhale and exhale they are to continue to relax the body.
3. After the body's Qi has been cleansed, the patients will focus their intention on any and all internal organs that specifically need to be purged. Breathing exercises used for purgation include focusing the patients' intention on the exhalation, as well as exhaling specific healing sounds. The patients continue to purge their body in this manner in accordance to the doctor's instructions.

   Having completed the purgation exercises, the patients are free to begin their tonification prescriptions. Breathing exercises used for tonification include the focus of the patients' intention on the inhalation, as well as visualizing specific colors being ingested into certain internal organs.
4. After practicing the tonifying or purgation prescriptions, the final goal of respiratory training is to achieve a long, natural, even and deep respiration. Urgent respiration causes the body's internal Fire to escape into the pores, resulting in uncontrolled Heat, feverish conditions and irritability. Normal breath regulation consists of even inhalation and exhalation patterns. The patient must avoid speeding up their breath, as this will also interrupt the breathing rhythm and lead to deviations of Qi.

BREATHING PATTERNS FOR COLLECTING AND REGULATING QI

The following are examples of exercises used for regulating and collecting Qi in the Lower Dantian. The doctor or patient will perform the breathing patterns as follows:

1. Collecting Qi in Lower Dantian is used to tonify and increase the collection of Qi gathered in the Lower Dantian.
   a. Inhale through the nose, filling the lower Dantian (expanding the abdomen), pause, then exhale through the mouth. Repeat and continue this breathing pattern for three times then proceed to b.
   b. Take three partial inhalations through the nose, filling the lower Dantian, pause, then complete one exhalation through the mouth. Next, inhale 50% of the breath into the Lower Dantian (expanding the abdomen), hold for three heartbeats, inhale remaining 50% into the Lower Dantian and hold for five heartbeats, relax and slowly exhale. Repeat and continue the pattern for thirty minutes a day (for three months), or until it becomes effortless.
2. Regulating Qi in Lower Dantian is used to stabilize the energetic balance of the Lower Dantian.
   a. Inhale through the nose, filling the lower Dantian (expanding the abdomen), exhale through the mouth, and

then pause. Repeat and continue this breathing pattern for three times then proceed to b.

   b. Inhale through the nose, then perform three partial exhalations through the mouth, pause, then one complete inhalation through the nose. Next, exhale 50% of the breath out of the Lower Dantian (contracting the abdomen), hold for three heartbeats, exhale remaining 50% out of the Lower Dantian and hold for five heartbeats, relax and slowly inhale. Repeat and continue the pattern for thirty minutes a day (for three months), or until it becomes effortless.

3. The Mysterious Pass is the pause between the inhalation and the exhalation. The ancient Qigong Masters believed that in the pause was the realm of infinite space (Wuji), existing between the Earthly Heaven (the congenital form of energy) and the Later Heaven (the acquired form of energy) where time and space stands still.

   For clinical practice, the Qigong doctors train in the method of accessing the Mysterious Pass in order to extend Qi through the entire body and to access the energy of the Wuji (Infinite Space). In the clinic, the training is divided into two stages (a and b).

   a. Begin this training by holding the breath from three to twelve counts (known as the "Small Count Breathing Regulation").
   b. Eventually increase to the "Big Count Breathing Regulation," which consists of 120 counts. This method enriches the Yuan Qi by breathing in more and exhaling less, and is sometimes used in Medical Qigong prescriptions to cure specific types of illness. When used with a strong intent, breath holding can constrict the blood vessels and raise the blood pressure; it is therefore sometimes prescribed for patients with hypotension. This Qigong method is, however, contraindicated for patients or doctors with hypertension.

THE FOUR PROGRESSIVE STAGES OF RESPIRATION

There are four progressive phases of difficulties that patients may experience during the beginning stages of their Medical Qigong Respiratory training: The Wind Phase, The Gasp Phase, The Unbalanced Air Phase, and The Quiescent Phase.

1. During the Wind Phase, the breathing is audible and may prove distracting to a beginner. The goal of focused concentration is to allow the energy to become gathered and collected. If the goal of the breathing prescription is to focus on a Deficient internal organ or specific tissue area, for example, and the patient's concentration becomes diverted (shifting to the noise of their own breath), it may disrupt the patient's mind. This can result in the patients collected Qi being dispersed instead of gathered.
2. During the Gasp Phase, the breathing is no longer audible, but any stagnant air, or obstructed air in the throat may disrupt the mind's concentration. Focused concentration on the stagnant air or obstruction may cause a sense of physical obstruction and mental anxiety, resulting in Qi stagnation in the throat (known as Plum Pit Qi).
3. During the Unbalanced Air Phase, the breath remains silent and there is no sensation of obstructed air in the throat. The patient's breathing, however, may be uneven, or unbalanced. Focused concentration at this phase may cause strain in the patient's mental awareness. If the mind becomes overstrained (trying to balance the inhalations and exhalations) the result will be fatigue.
4. During the Quiescent Phase, patients are able to achieve a long, natural, even and deep respiration without sound or stagnation, resulting in a state of extreme quietness. Concentration on this phase will result in a restful peace of mind.

DURATION TIME FOR RESPIRATION THERAPY

Patients in relatively good health should practice for about five minutes a day in the first week, when seeking to regulate their body's internal energy. In the second week patients should increase to ten minutes a day, and in the third week, fifteen minutes a day. Thereafter, five more minutes each day should be added until the patients reach a minimum of twenty minutes and a maximum of forty minutes per day for optimal Qi development.

When treating patients (for general tonification) using multiple standing meditation postures, have them begin by counting up to sixteen breaths per each posture. As the patients progress, the respiratory rate during meditation begins to slow down naturally. Normally, within a few months of training, respiratory rate drops from an average of sixteen breaths per minute, to three or five breaths per minute. This naturally increases the time spent in each posture, extending each posture from one to five minutes in duration.

Qigong doctors, on the other hand, should practice a minimum of forty minutes of standing posture each day to recharge and increase the efficacy of their treatments.

EMOTIONAL EFFECTS ON BREATHING PATTERNS

Breathing patterns are directly related to both the patients' thoughts and emotions. Any shift in one will affect the other. Each of the five primary emotions is associated with a specific breathing pattern as follows.

1. An angry patient's exhalation will be much stronger than the inhalation.
2. A grieving or sad patient's inhalation will be much stronger than the exhalation.
3. A fearful or scared patient's breathing will be fast, held high in the Lungs, and shallow because of the Kidneys' inability to hold the Lung Qi down.
4. A happy patient's inhalation and exhalation will be moderate, and irregular, with quick bursts.
5. When worried or deep in thought, the patient's inhalation will be shallow and weak, sometimes held for long periods of time, followed by a long gulping burst of inhalation and exhalation. The patient may also experience spontaneous sighing for prolonged periods of time.
6. When a patient experiences fright or shock, the breath immediately stops as the Qi attacks the Heart.

RESPIRATORY DAO YIN CANCER PRESCRIPTIONS

Respiratory prescriptions such as the Deep Relaxed Breathing Method described below, are used in treating cancer, and require the patient to combine the use of two methods of exercise and treatments:

1. The Opening and Closing Methods of Qi regulation (see Chapter 41), and
2. The Deep Relaxed Breathing methods for purgation, rather than tonification purposes.

The purpose of these treatment methods is to purge Excess Qi from the body, remove Blood stasis, and disperse Qi stagnations.

THE DEEP RELAXED BREATHING METHOD

The function of this exercise is to purge the channels and collaterals and to promote the circulation of Qi. It is also used to harmonize the ascension of Yang and the descending of Yin. Calming the Yin and suppressing the Yang promotes the flow of Qi and Blood through the organs, and has the effect of eliminating Evil pathogenic factors, and supporting healthy energy.

The Deep Relaxed Breathing method requires the patient to inhale through the nose and exhale through the mouth. The main points to remember in this method are as follows:

1. The patients inhalation and exhalation should be gentle, thin, even and long. They should focus their mind on the Hibernation Breathing Method. This method requires inhaling and exhaling through every pore on the body's surface while lying supine. The patients should not focus on their lower abdomen or the expansion of the upper chest and

Lung region. Instead, they should imagine inhaling through the pores into the Taiji Pole, and exhaling out from the Taiji Pole through the tissues and out the pores.

2. When breathing, the patients' whole body should stay relaxed; the key part to relaxing the whole body is to relax the waist.

Through training in these respiratory methods, the patients' immune system is enhanced and their vital Qi is nourished.

CHAPTER 17
MENTAL DAO YIN TRAINING

INTRODUCTION

There are two divisions of the Mind (Yin and Yang), each consisting of three different levels. The Yin part belongs to the energy of the Earth and is a more body-oriented type of mind. The Yang part of the Mind belongs to the energy of Heaven and is a more consciousness-oriented type of mind. The three levels of the Mind are as follows.

1. The first and deepest level exists within the Jing and the Shen, and represents the Original (Yuan) and primordial form of the mind.
2. The second or middle level exists within the Seven Corporeal Souls (Po) and Three Ethereal Souls (Hun) and represent the moving and active aspects of the mind (e.g., body movements, reflexes, instincts, drives, and astral projection - when accompanied by the Yuan Shen).
3. The third and superficial level exists within the Will (Zhi) and Intention (Yi) and represents the mind's everyday function (i.e., cognitive thinking). The Zhi is considered the "thinking body," while the Yi is considered the "thinking mind" (for more information refer to the Five Yin Organ components of Shen in Chapter 13).

These different levels of energies create the body, as well as activate the mental and emotional transitional states of the Mind. All three levels of the Mind are interactive and interdependent (Figure 17.1).

Energetic Division (Qi)	Yin	Yang
Energy of the Mind	Earth	Heaven
First Level of the Mind	Essence (Jing) Kidneys	Spirit (Shen) Heart
Middle Level of the MInd	Corporeal Soul (Po) Lungs	Ethereal Soul (Hun) Liver
Third Level of the Mind	Will (Zhi) Kidneys	Intention (Yi) Spleen

Figure 17.1. Mental and Emotional Transitional States of the Mind

Traditional Chinese Medicine believes that the Heart stores the Spirit (Shen). The Shen is further divided into Yuan Shen (the intuitive congenital spirit) and Zhi Shen (the analytical acquired spirit). The Shen is responsible for feeling and controlling the body's mental and emotional activities. The Zhi Shen is generally strong and can be stubborn and suspicious, therefore, it must be led by a master; the Yuan Shen must be that master, and must lead the Heart's Shen as one unit.

The brain is considered the house of the Yuan Shen, and the seat of mental function. It is believed that the senses and control of the body's physical movements are related to the brain. If the Heart has any functional disorder, the mental activities of the brain, and the emotional activities of the Heart also become disorganized. The Heart, which is the seat of all emotions, controls not only the Shen, but also the blood vessels, therefore Blood circulation is also influenced by the emotions.

The preservation of Jing depends on the cultivation of Qi, which in turn depends on the mental focus of the Shen. The mental focus of the Shen is to Qi as a mother is to her child. Mind concentration must combine with Qi; without the Shen


Mind
Acquired Postnatal Mind (Zhi Shen)
Acquired Benign Thought Patterns
Internal: Subconscious Praise
External: Environmental Praise
Acquired Malignant Thought Patterns
Internal: Subconscious Condemnation
External: Environmental Condemnation
Congenital Prenatal Mind (Yuan Shen)
Congenital Spiritual Patterns
Innate Connection to the Divine
Congenital Energetic Patterns
Vital Activities of the Major Viscera

Figure 17.2. The Differentiation Between the Prenatal and Postnatal Patterns of the Mind

guiding it, the body consumes the energy. The concentration of the Shen and Yi (intention) causes Qi to consolidate, while any distraction to the Shen and Yi causes Qi to disperse.

This concept is considered similar to that of regulating the emission of light, because Qi is emitted similar to the wave patterns of rippling water, and Shen is emitted similar to the wave patterns of light. When the Mind begins to focus concentration on the projection of Qi, both Qi and Shen unite, enabling the Qigong doctor to regulate the emitted Qi, changing its form from an expanded energy field to a finely honed beam.

THE PRENATAL AND POSTNATAL MIND

In Traditional Chinese Medicine, it is believed that the cerebral activity of the mind falls into two distinct categories: the Prenatal (Yuan Shen) Mind, and the Postnatal (Zhi Shen) Mind.

1. The Prenatal Mind (Yuan Shen) is inherited from the Jing of both parents and dominates the vital activities of the major viscera, as well as the function of the body's entire energetic organism and spiritual matrix.
2. The Postnatal Mind (Zhi Shen) is developed through interaction with people and the en-

vironment after birth. It dominates thought and interaction, and engages in unlimited mental activity.

The Yuan Shen and Zhi Shen are interactive and interdependent. If the Zhi Shen is active and chattering (sometimes called the Monkey Mind), it is difficult for the Yuan Shen to convey its perceived information. Regulating the Mind is therefore needed to harmonize the analytical and intuitive aspects of the Mind.

BENIGN AND MALIGNANT THOUGHT PATTERNS

Mental activity and thought processes can also be categorized into two clinical syndromes: benign and malignant thought activity (Figure 17.2).

BENIGN EMOTION AND THOUGHT ACTIVITY

This is a gentle or favorable belief structure of the subconscious mind, resulting in relaxed, pleasant thoughts. This thought pattern will both improve and regulate the excitation and inhibitory processes of the cerebral cortex. These positive thoughts and beliefs help to restore strength to the Yin and Yang organs, and thus promote health. Benign emotional thought activity can be further divided into internal and external influences:

1. Internal benign thought activities stem from the inner Hun's influences over the subconscious mind. These positive thought patterns tend to enhance self-esteem, by complementing and encouraging our thinking and actions.
2. External benign thought activities consist of praise and encouragement received from others (parents, friends, co-workers, etc.), which have been accepted and believed. These positive thought patterns promote confidence and self-esteem.

MALIGNANT EMOTION AND THOUGHT ACTIVITY

This is a harmful belief structure causing excited, nervous, stressful, and unpleasant thought patterns that interfere with the performance of the cerebral cortex, resulting in internal organ dysfunction and disease. Malignant emotional thought activity can be further divided into internal and external influences.

1. Internal malignant thought activities are the thoughts stemming from the subconscious mind, which tend to destroy self-esteem, cause obsessions, and discourage productive thoughts and actions. This thought pattern extends from the influences of the Po.
2. External malignant thought activities are internalized negative cynical beliefs and criticisms that originated from the surrounding environment (work, parents, teachers, friends, mate, etc.). External malignant thought activities cause thought distortions that destroy our self-esteem and discourage us.

THE IMPORTANCE OF MIND CONCENTRATION

An essential requirement for training the Qi is the training of mind concentration. If the concentration is forced, the Qi from the Lower Dantian rises up to the head causing the Stomach to become nauseated. If the Qi continues to ascend to the head, the result will be dizziness, headaches, and Qi deviations.

Thoughts and mental activities are reflexes of the brain and cerebral cortex. A Mind (whole body consciousness and awareness) agitated or depressed over a long period of time causes a long-term disorder to the whole nervous system, and leaves the body vulnerable to various kinds of chronic diseases. Long-term anger, for example, leads to the contraction of the blood vessels, sclerosis of the arterioles, gastric ulcers, and hypertension. Long-term emotional disturbances disrupt the endocrine system, and lead to a weakened immune system.

Psycho-neuro immunological research confirms that the Mind (whole body consciousness and awareness) can both cause and cure diseases. Healing visualizations sometimes act as a catalyst, increasing the rate of chemical reaction within the tissues. Improper concentration, however, can transform good Qi into Toxic Qi, and can lead to chemical imbalances that perpetuate the diseased condition. This is especially true when guiding and emitting energy.

According to medical statistics in China, with certain types of cancer, patients whose worry and anxiety were the main cause of their disease made up about 52% of the patients. These patients had been emotionally upset for half a year before becoming sick. The focus of the patients' mental concentration was directed on detrimental thoughts. It is a fact that chronic diseases are closely related to the patients' thoughts, emotions, and mood swings. To treat chronic diseases, it is necessary for the Qigong doctor to first relieve the patients' depression, irritability, and resentment and then place the patients, when possible, in a quiet comfortable environment.

It is important for the patients to relax their Mind (i.e., mind and body). Relaxation can be achieved through tissue manipulation (massage), or by inducing meditations, or trance states. To relax the Mind the Heart must be regulated. To regulate the Heart means to adjust the agitated or depressed Mind and place it into tranquility. One of my teachers in China, Qigong Master Zheng Zhan Ding would often say, "When the spirit, like a lake, is undisturbed, it mirrors the Heavens perfectly." Meaning that, the clarity of the Mind emerges gradually (or slowly) when entering into stillness, much like mud slowly settling in water. This allows ones true inner nature to be revealed.

According to research published by Dr. Karl Lashley, specific memory is not located in any one place in the brain. He found that destroying a portion of the brain does not destroy the memory assigned to that specific area, and also that memory could not be located in specific brain cells. His observation is that memory is distributed all over the brain as an energy field. Other researchers have made similar observations that support the conclusion that the human brain functions as a hologram, collecting and reading information from a holographic universe.

REGULATING THE MIND

Mental Dao Yin training involves regulating the Mind. This requires the Qigong doctor to diminish the mental activities (or judgements) of the Zhi Shen to prevent interference with the intuitive understanding of the Yuan Shen. The diminished mental activity allows for true relaxation, peace, and inner tranquility.

If the Zhi Shen is allowed to become unbridled through excessive internal chatter, it can become injured by the Excess accumulation of energy attributed to the Seven Internal Emotions: anger, worry, joy, fear, fright, sorrow, and grief; as well as the Four Desires that become pathogenic when in Excess: sex, money, fame, and power. These Seven Internal Emotions and Four Desires engage the mind, robbing the body of its life-force energy by depleting the Yin and Yang organs, disrupting their balance, and causing obstruction in Qi and Blood circulation that results in disease.

All thoughts carry within them emotional reactions, these in turn have a significant physiological as well as psychological effect on an individual's health. The degree of intensity as well as the frequency of returning thoughts determines the extent of the internal transitions experienced in the individual's body.

To illustrate this difficulty, when I began my initial Qigong training, my instructor informed me that the internal training would keep me warm in the winter and cool in the summer. Excited about the possibility of possessing my own internal air conditioner, I practiced diligently.

After three years of difficult training I had not yet developed this ability. I slowly began to lose trust in my instructor, and approached him to inquire about the promised skill. He informed me that it was the "imagination" that changes our thoughts and belief structures, enabling the body's tissues to feel what the mind directs. Stating that, "The Imagination leads the mind, the mind leads the Qi." My teacher further stated, "Whenever training in the summer when the heat is unbearable, focus your mind on the coolness of the sweat and imagine the air around your body as a cloud of cold air. In the winter time, when the cold is severe, focus your mind on the heat that your body is producing and imagine the air around yourself as a circle of hot fire." After applying these principles to my training, I experienced both the warmth and cool sensations that I was trying to achieve, and regained trust in my teacher.

Thoughts and emotions create electromagnetic waves in the brain. Your breath can also create or control these waves and cause your mind to take


Mental Dao Yin Concentration
Internal Objects: Localized and Directed Mind Concentration
External Objects: Symbolic and Suggestive Mind Concentration
Both Internal and External Objects: Rhythmic Mind Concentration

Figure 17.3. The Three Categories of Mental Concentration

on the thought wave patterns of specific emotions. When the mind is tranquilized after certain Medical Qigong exercises, all disturbances stop, there is a quiet and comfortable feeling sensation (produced by the deep inhibitory state of the cerebral cortex) that facilitates the expansion of consciousness and awareness throughout one's entire being. This state of being is referred to as the Mind.

The Three Categories of Mental Concentration

Mental Dao Yin training can be summarized by the following three foundational modalities: concentrating on internal objects, concentrating on external objects, and concentrating on both internal and external objects (Figure 17.3).

These three modalities of mental concentration encompass regulation of both the benign and malignant emotional thought activities which influence our everyday lives. People focus their mental concentration everyday on either benign or malignant internal objects (inner thoughts and feelings), external objects (outer thoughts and feelings), or engage in both internal and external thoughts and feelings through conversation.

Concentrating on Internal Objects

In China, the method of concentrating on internal objects is called "localized" and "directed" mind concentration. In this type of training, the mind is absorbed in concentrating on a specific area of the body. Patients, for example, are directed to focus their eyes downward along the nose in the direction of their navel, while simultaneously using inner-vision to concentrate on their Lower Dantian. Patients can also focus their concentration on other external or internal areas of the body such as:

1. The palms or feet to lead Excess Qi away from the head or torso.
2. A specific channel point (called "energetic point therapy") or pathway, to direct Qi into or away from specific areas of the patient's body, or
3. A Yin or Yang organ to direct Qi into or away from specific internal organs.

The ancient Qigong Master Li Shizhen once said, "When the mind is concentrated upon the inner channels, the practitioner is able to look within his own self." Qigong doctors and patients who are energy sensitive can feel the channels along which their own vital energy flows. This sensitivity is experienced in the more advanced stages of tranquility.

Concentrating on External Objects

In China, the method of concentrating on external objects is called "symbolic" and "suggestive" mind concentration, and is focused through vivid imagery. In this type of training the patient's mind is absorbed in concentration on some form of object outside of the body. As the mind enters a state of tranquility, it focuses through vivid imagery, or energizes through sound vibrations. Some excellent examples of external objects are: music, the sound of rain or water flowing, a calm ocean, the sky, clouds, light, sound vibrations, mantras, a golden or white glowing ball, specific colors, trees, etc. In this type of concentration, the patient's internal vibration connects with and matches the external form of some object in nature or some specific symbol (such as a lit candle).

When focusing on external objects, it is important for patients with high blood pressure to choose low lying objects, such as a meadow, quiet stream, flower, etc. Patients with low blood pressure should choose objects that are eye level, such as a small pine tree, to balance the energy of the Heart.

When practicing this particular method of mental concentration it is important to focus on external objects that can be physically observed without straining. This way if distracting thoughts interfere with the concentration, the patients can return to the real image, or sound, to reestablish their concentration. The focus should never be forced or too intense. Dr. Xu, of the Xi Yuan Hospital in China, once stated, "In the state of emptiness you will see an image through your imagination. This image will arouse your emotions. These emotions help you to form a more colorful image. From these colorful images you will obtain a deeper state of emptiness. This is the state of Mind sought after in order to obtain emptiness and maintain tranquility." In this particular case the patient's mind is like still water, free from expectations or desires. In quietness you become the observer of images, allowing what will unveil itself to occur naturally.

CONCENTRATING ON BOTH INTERNAL AND EXTERNAL OBJECTS

These methods employ "rhythmic Mind concentration" and are the primary methods used in Medical Qigong therapy. They are simple, easy, safe, and effective. In this type of mental training, the patient's body responds to their thoughts. Patients focus their attention on the breath as it flows in and out of the body, listening to the sounds of their breathing and sensing the expanding and contracting movements of their abdomen. During this type of mental concentration the patients are sometimes given a mantra, such as thinking the word "quiet" during the inhalation and "relax" during the exhalation, or they are instructed to silently count numbers. Sometimes, the patients are also directed to imagine the feeling of quietness, like a mist, flow from their feet into their head (absorbing quiescent Earthly Qi), or from their head down into their feet (absorbing quiescent Heavenly Qi).

When first teaching patients the methods of mind concentration, keep the images simple. When the patients have recovered from their illness, they can begin to concentrate on either an internal or external object to further strengthen their health.

ESSENTIALS OF TRAINING MIND CONCENTRATION

These three mental Dao Yin techniques can be utilized to their full potential once the Qigong doctor understands the essentials of training the mind, the three stages of mental tranquility, and the skill of regulating the mind.

Mental activities should be coordinated naturally with respiration and posture. In Dynamic Qigong Dao Yin exercises, for example, mental activities must be adapted to the posture and the lifting, opening, and closing manipulations of the hands. When using an active (Yang) posture (if the goal is to regulate the patients' Qi), the inner concentration should be motionless (Yin). The ultimate goal is to combine both physical and mental activities that promote harmony in the body's energetic fields. The Qigong doctor should monitor their patients' mental concentration, making sure that they comprehend the following three concepts: Relaxing the Mind, Being Self-Confident, and Being Mentally and Emotionally Stable.

1. The purpose of relaxing the mind is to allow all mental activities to be carried out (without straining) in a composed state of mind. The mind should be kept clear and all distracting thoughts expelled gently. During concentration, the mental focus should never be forced. Mental concentration can be either strong (active) or mild (motionless).
2. Self-Confidence is a prerequisite, for without it, the training of mind concentration cannot happen. No matter what kind of mental activity the patients train in, they should be confident that they can reach their goal. This establishes a strong faith, which is the root of all mental Qigong projection abilities. Patients should also be realistic about not expecting quick results. Although miracles do happen, healing often takes time. The dynamic or active postures and exercises train the body's Qi, while quiescent or motionless exercises sustain and nourish the patients' Qi.
3. The purpose of being mentally and emotionally stable is to assist patients in not becoming overjoyed or frightened if something unexpected happens, or is perceived, during the Qigong exercise. It is important that patients take advantage of this time to keep their mind concentrated and the Qi consolidated. If patients feel weary, remind them that sleep and food can reinforce their mind and Qi.

CONCENTRATIVE MEDITATION AND INSIGHT MEDITATION

When Medical Qigong practitioners begin their meditative practices, they are generally encouraged to keep their mind focused and under control, this is known as "concentrative meditation." Concentrated power is manifested through silence; when the mind is noisy (distracted by physical sensations and chatty), the internal power becomes diffused. When Qigong doctors reach the place of silence in their Mind, they can connect with the divine power, a place of true power, and a place where "all is one." Through concentrated intention, Qigong doctors can bring all of their energies to bear on one point of focused power or force. At the same time, they contact and connect with the divine in silence (the hookup), and become one with the divine healing power.

This transition and conscious union with the divine occurs only when the Qigong doctors turn from the chaotic external world of sensory input (sight, hearing, smelling, etc.), to the quiescent state of silence. This divine energy is then manifested as power, substance and true intelligence, flowing through the Qigong doctors for healing.

Contact with the divine is only obtained in the deepest part of silence. Within oneself, and within this silence abides a state, or dimension, where the true "Gate of Heaven" can be opened and enlightenment obtained. Ideas conceived in this divine state of consciousness come into expression and can manifest as form. All Jing, Qi, and Shen can be transformed and transmuted into form, through this change in consciousness. When the doctor's Intention (Yi) and Will (Zhi) are aligned with the Dao (or divine will) all things are possible. The doctor is in direct contact with the universal Mind, and can manifest in physical form, that which is needed through faith. The divine energy resides within the body's Eternal Soul as power, substance, and intelligence and is brought into form and expression through consciousness. The degree to which the doctor can tap into and utilize the consciousness imbedded in the infinite Mind of the divine, is determined by the concept, or belief, that is held in the doctor's as well as the patient's conscious and subconscious mind.

In the silent state of quiescence, when the Qigong doctor sees a mental pattern or mold, a template is created into which will flow the substance (Qi) needed to bring it into being. The pattern will manifest into the form intended by the doctor's consciousness. Through the power or process of faith and thought, the doctor (or patient) can transmute and evolve the body or outer conditions and surroundings, by recognizing the divine consciousness within themselves.

As the practitioners advance in ability, they are encouraged to focus their attention indiscriminately on all sensual stimuli they receive, this is known as "insight meditation." In practicing insight meditation, practitioners are encouraged to reevaluate their experiences and world views according to the cause and effect of their disease(s). Patients are also taught to use this type of insight to observe their physical and mental processes. This self-observer is used as a vehicle through which to observe, scrutinize, and carefully examine the fundamental energy transformations within the body for spiritual growth.

THE THREE STAGES OF MENTAL TRANQUILITY

Before the mind surrenders to a state of tranquility, it must first transition through three stages. The Qigong doctor must experience all three of these stages in his or her effort to become effective when treating patients. In China, Qigong masters have a saying, "When you root the Mind, the Heart will open up to ten thousand voices." This means that when the Mind is removed from all distractions and excess chatter, the Yuan Shen is free to receive intuitive perceptions. This state of "tranquility" or "stillness" also dissolves time perception, allowing time to disperse into nothingness (Wuji). The three stages of mental tranquility are described as follows:

STAGE 1

In the first stage, the doctor's four extremities and Lower Dantian may experience heat and tingling as the mind slowly eliminates distracting thoughts and begins to withdraw from the external world. The doctor's mental focus and concentration, however, is not consistent. While emitting Qi, distracting thoughts still emerge, and the doctor must patiently wait for the chattering mind to subside.

In this stage of training, especially in male Qigong doctors, the cognitive, analytical thinking and speaking may sometimes become sporadically impeded. This is due to the thin energetic field within the corpus callosum that separates the right (intuitive) from the left (analytical) hemispheres of the brain. This makes it more difficult for men to access both hemispheres simultaneously. Men should therefore train to rely more on their intuitive perceptions instead of analyzing (they must feel the energy, and not think it).

This however, is not a problem in female Qigong doctors, as the energetic field which separates the corpus callosum is much wider and already active. This allows female Qigong doctors to easily access both sides of their brain simultaneously, enabling them to draw upon the perceptive, intuitive as well as cognitive, analytical thinking and speaking hemispheres of their brain.

STAGE 2

In the second stage, there is an increase in heat to all four of the doctor's extremities from the Lower Dantian. Through intention, the connection to the Lower Dantian is strengthened and the body's Qi feels like a rushing wind flowing throughout the doctor's torso.

While diagnosing and treating, the doctor experiences one or several of the patient's "eight manifestations of Qi" (also called the Eight Energetic Touches). These manifestations consists of the following physical and sensory phenomena of energy: shaking, rippling, heat, coldness, sinking, floating, itching, and heaviness. As the doctor focuses on extending energy, he or she will be able to remove internal distracting thoughts, but will still hear the distracting sounds from the external world.

STAGE 3

In the third stage, all of the doctor's sensory input (seeing, hearing, tasting, touching, smelling, and perceiving) is sealed from outside distractions. The doctor's Yuan Shen and Zhi Shen are now relaxed and in a state of mental tranquility. The Qigong doctor can now approach the patient free of chattering thoughts, judgments and all outside distractions. This enables the doctor to intuitively perceive and sense the patient's energetic traumas, stagnations, deviations, and energetic clusters.

THE THREE PROCESSES OF THE MIND

The mind can be divided into three separate but interdependent processes, which are responsible for our everyday actions, responses and health (Figure 17.4). Thoughts, ideas, and feelings are constantly being implanted, influencing and affecting the spiritual, emotional, mental, energetic, and physical process of healing. The heal-


The Three Interdependent Processes of the Mind
The Conscious Mind:
Perceives reality through the five senses.
The Personal Subconscious Mind:
Records and stores our interpretations of reality.
The Creative Subconscious Mind:
Maintains reality by making us act like the people we see ourselves to be.

Figure 17.4. The three interdependent processes of the Mind, which are responsible for our everyday actions.

ing process includes reprogramming and regulating the conscious, personal subconscious and creative subconscious mind.

1. The Conscious Mind perceives reality through the five ordinary senses. It evaluates reality by investigating and interpreting the data through the filter of the past experiences. The conscious mind makes decisions based on personal goals, and manifests conscious thinking patterns. It is considered to be the Postnatal Mind (related to the Zhi Shen).
2. The Personal Subconscious Mind records and stores the conscious mind's interpretations of reality. It consists of the personal, perceptual data that were received through our five senses. The personal subconscious mind shares responsibility for how we think, what we say and imagine about ourselves and our emotional and behavioral reactions to those experiences. It is also responsible for the automatic function of the living mechanism (i.e., heartbeat, breathing, digestion, etc.) through its energetic connection to the autonomic nervous system. It is considered to be influenced by the spiritual aspects of the Wu Jing Shen (especially the Hun and Po).
3. The Creative Subconscious Mind maintains our reality by making us act like the people we see ourselves to be. It solves problems and provides the drive and energy to succeed or fail, heal or become sick. It is the center core energy of our innate spirit or soul consciousness. It is considered to be influenced by the spiritual aspects of the Yuan Shen.

CREATING THE BRIDGE OF LIGHT

The Bridge of Light is an energetically patterned wave frequency which consists of three main components of the body's energetic field. Its energetic connection to the body's tissues functionally envelops the conscious, personal subconscious and creative subconscious mind, and is considered to be the bridge between the three process of the mind. It consists of three separate but intertwining threads: the thread of life, the thread of consciousness, and the thread of creativity.

1. The thread of life comes directly from the Eternal Soul and is rooted in the Heart during conception. It is connected to all feelings that stem from the divine higher energy field and is considered the "seat of life."
2. The thread of consciousness also comes directly from the Eternal Soul and is rooted in the pineal gland within the brain. It embod-


Personal Subconscious Mind:
Records and stores our interpretations of reality (Related to the Zhi Shen).
Thread of Consciousness:
Rooted in the brain (pineal gland)
Creative Subconscious Mind:
Maintains reality by making us act like the people we see ourselves to be (Related to the Wu Jing Shen).
Bridge of Light
Thread of Life:
Rooted in the Heart
Conscious Mind:
Perceives reality through the five senses (Related to the Yuan Shen).
Thread of Creativity:
Rooted in the throat

Figure 17.5. The Bridge of Light

ies portions of the energies of consciousness and is considered to be the "seat of consciousness."

3. The thread of creativity is rooted in the throat and is unique in that it is created and specifically constructed by each individual. It is also an extension, or synthesis, of the thread of life and thread of consciousness.

   The thread of creativity is in itself made up of three main components. These three components, or additional threads, intertwine as one unified thread of creativity and are explained as follows.

   a. The first portion of this thread extends from the physical Heart to the Spleen, and is connected from the body to the first external field of Wei Qi.
   b. The second portion of this thread extends from the solar plexus to the Heart and eventually extends and connects from the body to the second external field of Wei Qi.
   c. The third portion of this thread extends from the Yintang (Third Eye) through the brain, ascending through the Baihui region and beyond. This energy field is connected from the body to the third external field of Wei Qi.

After all three threads of creativity have been activated, energized, and developed, the next goal is to align and integrate the Qi of the thread of life and the thread of consciousness, with the frequencies of the thread of creativity.

Because the thread of life is connected to the Eternal Soul, the integration of the three threads allows an individual the direct connection to his or her core self (Figure 17.5). This enables the individual the ability to consciously access his or her true inner voice (the voice of his or her soul) and receive information and guidance from the divine. The goal in accessing the Bridge of Light is to unite these three energetic threads into one powerful and functional energy field.

When all three major threads (which compose the Bridge of Light) are connected as one harmonious cord of light (extending upward through the Taiji Pole), a spiritual gateway is opened that enables access to the Pure Heavenly Sound (also known as Hearing the Sounds of the Universe) (see the Six Transportations of Shen in Chapter 13).

REPROGRAMMING THE MIND TO HEAL

The mind holds specific energetic patterns which maintain a patient's physical, mental, emotional, and spiritual belief structures. These patterns are maintained by the dictates of the personal subconscious mind and can only be changed when the creative subconscious mind is engaged.

To change specific destructive patterns, the personal subconscious mind must be reprogrammed. There are three things that are needed in order to reprogram the personal subconscious mind: imagination, visualization, and positive affirmation. Imagination combines with vivid pictures, sounds, sensations, etc., and creates a new reality on a creative subconscious level. It is the awakening to this new reality that reconnects the individual to the creative subconscious mind.

If patients do not use imagery and affirmations to change their present personal subconscious representation of reality, the patient's personal subconscious mind will automatically seek to correct any newly made change. The personal subconscious mind views any new deviation from the normal energetic pattern as a mistake, and will automatically resist, or sabotage, any change of pattern, returning the patient back to his or her original state of mind and body sickness.

It is a simple fact that "we bring about what we think about," and act in accordance with the truth that we have come to believe. If we act out of a particular new state of mind and feeling over a sufficient time period, it will become a permanent reality of the self. In using the mind to make transitions, it is important to note that words, images, and sensations have tremendous power, and the spirit behind the intent is the key to any permanent transformation.

Because patients trust their doctor, it is the doctor's responsibility to direct the patients into a healing mental state for the purpose of restoring health. The doctor must never be guilty of "clinical hexing." Clinical hexing occurs when a patient (who completely trusts the doctor) is told by that doctor, that there is no hope. The patients, believing the doctor, may give up their desire to change and heal. Thus, through accepting the inevitability of death, they suppress their desire to live. Qigong doctors are therefore taught to always encourage their patients on their recovery, and to never destroy their hope.

Through positive affirmation and reinforcement, it is possible for the patients to turn around the progression of their disease. Scientific studies in China have proven, for example, that through imagination, visualization (which include using all of the five senses) and positive affirmation, the rate of phagocytosis (the ability of the immune cells to engulf and destroy invading germ cells) greatly increases and enhances the body's immune function.

USING THE IMAGINATION

The Yi (which consists of the imagination and intention) leads the Shen (composed of the thought, emotion and spirit) which in turn leads the Qi (the body's life-force energy). The power of the imagination has a strong influence on health, and can be used to help cure diseases, or to further complicate the condition. If, for example, patients imagine that their immune cells are effectively destroying the cancer cells, Western medical treatments such as chemotherapy or radiation can become more effective. Research from China reveals that patients with a positive belief structure produce certain physical transformations, which manifest in the increased production and release of hormones and immune cells. The imagination is the inner form of all things, the primal inspiration from which reality later manifests. In a sense, patients bring about what they think about. While treating disease, Qigong doctors encourage their patients to imagine healing energy from the divine being directed into the diseased area. Once the treatment is finished, the patients are instructed to imagine that their disease has become completely healed.

During the state of relaxed meditation, the foundational aspect of the patients' disease, which is normally hidden from consciousness, reveals itself in the form of images and impressions. After a Medical Qigong treatment, or meditation, the patients may describe to the doctor any unusual thoughts, images, or feelings that they may have experienced while in the deep state of relaxation. The doctor then helps the patients find the origin of the image (a past incident, unhealthy belief structure, or trauma, etc.) through the doctor's ability to trace the images and emotions associated with it to the patients' internal organ or organ systems involved in the creation of the illness. Once the connection is made to the patients' disease, and the Medical Qigong homework is prescribed.

Medical Qigong prescriptions initiate energy movement. This energetic movement brings about the release of trapped emotion and energetic feelings. As the emotions unravel, a new level of awareness surfaces that allows the patients to become cognizant of certain mental functions that were previously unconscious. This awareness in turn allows patients to access their creative subconscious Mind to change the conditioned programming of their Zhi Shen (Figure 17.6).


The Creative Subconscious Mind and the Conditioned Programming of the Zhi Shen
Mental Function of Conscious and Personal Subconscious Mind
Release of Emotion and Energetic Feelings
Energy Movement
Medical Qigong Prescriptions

Figure 17.6. Five stages of transition and energy awareness allow patients to access their creative subconscious energy in order to reprogram their initial belief structures.

Through creative imagination, the patients' spirit is expressed and the patients' body is spiritualized. The imagination is an energetic world founded on the interrelation of various levels of spiritual, imaginative and physical realities. These energetic dimensions lie between what the Chinese call the "realm of the unfathomable hidden mystery" and the "world of animated physical forms." The imagination is an energetic and spiritual world that exists between the reality within oneself, and the reality outside of oneself. This energetic and spiritual world seems imaginary, but in fact it is very real, in that the patients live in it, and through it create a new belief system and self.

TWELVE STAGES TO TRANSCEND AND TRANSFORM

During the Ming Dynasty there began to surface twelve specific poems accompanied with twelve pictures, describing the twelve stages to enlightenment through contemplation. In this series there are ten pictures which describe the first ten stages of mental, emotional, and spiritual transcendence, and two additional pictures which describe the last two stages of mental, emotional, and spiritual transformation. These pictures and poems use the image of the ox (water buffalo) to describe man's animal nature, which in the first stage of spiritual training is identical to man's spiritual nature. The image of a young man is used to depict human intention and will. The interaction of the ox and young man reflects the idea that by coming to terms with our own animal nature, we can move toward transformation and arrive at a new way of being.

The images of the ox changing from dark, Turbid Yin, to bright, white Yang, represent the field of consciousness transforming through the controlled deliberate intention of one's Zhi (Will). Such metaphors as capturing and controlling the ox represent an explanation of the difficulties and dangers of transforming one's self, as well as the inner changes of alchemical purification and the reconciliation with one's darker side. These pictures suggest the combination of both the sacred and the natural within Man.

These stages of controlling the mind are described as follows.

1. In the wild, the first stage of training is divided into three separate phases:
    a. The Searching for the Ox phase depicts the state in which the young man is unaware of his own true nature. Although he is not sure what he is seeking, he has begun searching for something he is desperately missing within his life. He is in a state of omnidirectional searching, without an instinctive direction.
    b. The Finding the Tracks phase depicts the young man undergoing the first traces of mental, emotional and spiritual transformation. Realizing that other people have walked along this path, the young man begins to rediscover his own spiritual instincts. He is in the beginning phase of achieving focus and direction.
    c. The First Glimpse of the Ox phase depicts the young man experiencing his first "awakening." He has the first glimpse of the true union of nature and spirit in the form of a spiritual vision. The animal nature, however, is still uncontrollable and in the wild state (due to its connection to the painful memories of the past). The young man must chase after and entice the ox, which displays its horns, bellows aloud, runs away, and is overshadowed by a dark cloud (anger, despair, grief and fear). It tramples the wheat seedlings (beginning moments of spiritual insight) wherever it goes. In this phase the ox is unruly, Yin, and pure black in color (Figure 17.7).
2. The Initial Training Begins with this next stage. The ox is controlled by a rope through its nose, and runs swiftly under the young man's whip. The young man struggles hard to control the ox's willful temper. He begins talking and listening to the ox, matching its consciousness with his own. At this stage the ox is still Yin, and pure black (Figure 17.8).
3. The Ox Comes Under Control through con-


Figure 17.7. The Ox is in the Wild


Figure 17.8. The Initial Training Begins


Figure 17.9. The Ox Comes Under Control


Figure 17.10. A Time of Transition

stant training. The ox stops its dashing about, and begins to follow the young man. In spite of his fatigue, the young man tends the ox all day long, not daring to loosen his control of the whip or his grip on the rope. Gaining control of the ox requires the young man to also become more vulnerable and honest, using less force to control the situation. In this stage only the ox's head, which is under control, is Yang and white, the rest of his body is Yin and black (Figure 17.9).

4. During the Time of Transition, the young man feeds and takes care of the ox with respect. He also does not abuse it. At this stage, the natural strength of the ox harmonizes with the will of the young man. A long time has passed and the restless temper of the ox gradually has turned gentle. However, still not trusting the ox, the young man maintains control of the rope. The ox is one third Yang and white and two thirds Yin and black (Figure 17.10).
5. The Ox Is Now Tamed and moves in harmony with nature. It follows the young man, who no longer uses a rope to lead the ox, but still maintains control of the whip. The ox is half Yang-white and half Yin-black (Figure 17.11).
6. The Ox Is Freed of Worldly Hindrance. The ox no longer needs the whip for control. The young man can begin to experience and enjoy the inherent rhythm of life, because he now has the ox's undivided attention. The ox is three quarters Yang-white and one quarter Yin-black (Figure 17.12).
7. The Ox Is Under Complete Control. After a long stage of struggling against its instincts, the ox is now tamed and free from worldly distractions. It drinks when it is thirsty and eats when it is hungry. The young man can now enter into deep sleep. If he so desires, he can sit atop the ox and play his flute, because the ox knows where its going and the young man does not have to direct it. The ox is now completely Yang-white (Figure 17.13).
8. The Young Man and the Ox Unite With Heaven. The white ox wanders among the heavenly clouds. The young man is free from



Figure 17.11. The Ox Is Now Tamed



Figure 17.12. The Ox Is Freed of Worldly Hindrance



Figure 17.13. The Ox Is Under Complete Control



Figure 17.14. The Young Man and the Ox Unite With Heaven

worldly concerns, and so is the ox. Penetrated by moonlight, the Heavenly clouds grow whiter and drift away (Figure 17.14).

9. The Ox Transcends and A Single Light Remains. The clouds drift away and the ox vanishes. The young man finally enjoys his leisure time, singing under the moon (Figure 17.15).
10. Both the Ox and Young man Transcend and Return to the state of Wuji. As the moon continues to illuminate the vast void, both the young man and the ox vanish into Wuji and are nowhere to be found. Everything is formless, quiet, and pure. Existence is nonexistence and vice versa (Figure 17.16).
11. The Young Man and Ox Transform and Return to the Source. There is a difference between transcendence and transformation. Transcendence is a temporary or periodic experience of unity within the divine, the heavens and the earthly environment. It is a state, or condition of consciousness. Whereas transcendence implies a unifying experience that informs one of a new way of being, transformation is a process and a means to arrive at a new way of being. Mature transformation leads to an all-inclusive way of being that embraces the physical, mental, emotional, energetic, and spiritual existence of everything. In this stage man returns back to the original source of prenatal understanding, and is able to harmonize with Heaven and Earth (Figure 17.17).
12. The Young Man and Ox Transform and Live in the World. This stage depicts what happens after the transformation experience, and the reentry through nature into the everyday world. In this stage, man reenters the world as a transformed person with a new connection to his center core. He is able to become a guiding light to others. When needed, he can instantly return to a deeper state of enlightenment for additional instruction and personal guidance. Living in the world he can be in the seductions and temptations of the world, without being in any way affected by them (Figure 17.18).


Figure 17.15. The Ox Transcends and A Single Light Remains


Figure 17.16. Both the Ox and Young Man Transcend and Return to the State of Wuji


Figure 17.17. The Young Man and Ox Transform and Return to the Source


Figure 17.18. Transformation and Living in the World


Seven Steps of Awareness
1. Respect
2. The Interception of Karma
3. Controlling the Mind
4. Detachment from Worldly Affairs
5. True Observation of Self and Others
6. Intense Concentration
7. Realization of the Dao

Figure 17.19. The Seven Steps Needed to Transform the Mind

SUMMARY

During mental, emotional and spiritual transformations, individuals undergo stages of physical and psychological purification, as they begin to experience the active, conscious introspection into their mind, body and soul. These individuals are able to eventually identify and connect their own personal will to that of the divine, and begin to lose their attachment to the ego, developing a new and more expansive identity. These individuals will also begin to see themselves as truly spiritual beings that are merely housed in fragile, physical frameworks, which are subject to all the transformations that their spirit must transcend. Generally, when using Medical Qigong as a vehicle for transformation, individuals will evolve through seven steps to awaken the spirit and reach a stage of enlightenment: Respect, The Interception of Karma, Controlling the Mind, Detachment from Worldly Affairs, True Observation of Self and Others, Intense Concentration and Realization of the Dao (Figure 17.19).

1. The first stage, Respect, encompasses the self, others and the divine. Through the cultivation of respect a stronger faith develops.
2. During the second stage, The Interception of Karma, individuals begin to accept accountability for all their actions, deeds, and thoughts. At this stage individuals receive instant karma for all their actions.
3. During the third stage, Controlling the Mind, individuals begin to discipline their conscious actions (Taming the Ox).
4. The fourth stage begins the process of Detachment from Worldly Affairs. At this stage individuals begin to develop and maintain a spiritual priority.
5. The fifth stage of True Observation of Self and Others, enables individuals to perceive themselves and others clearly. At this stage they begin perceiving the universe and environment from a deeper, more spiritually evolved understanding.
6. The sixth stage involves the development of Intense Concentration. At this stage individuals transform thought, through faith, into manifestation. They can now initiate into reality what they focus their intention on.
7. In the final stage to transformation, Realizing the Dao, individuals become aware of their relationship with the divine, not only believing in God, but personally knowing God or the Dao.

SECTION IV

QI DEVIATIONS IN QIGONG TRAINING

CHAPTER 18
INTRODUCTION TO QI DEVIATIONS

Energetic deviations occur naturally through the course of everyday life, however, the body's energetic constitution quickly corrects any disharmony in energy flow. The difficulty when cultivating Qi is not in the development of large amounts of energy, but in the creation of a constitutional system strong enough to use this energy without being damaged by it. This is one reason why Qigong doctors initially spend a lot of time developing the safety measures and internal reservoirs necessary to ensure that their body will not be damaged by creating too much energy too fast. These alterations of energetic patterns can result in feelings that can range from simple discomfort to an abnormal susceptibility to disease. Through proper Medical Qigong therapy, Qi deviations can be rectified.

Qi deviations can be precursors to disease. In recent years, medical researchers in China have reported that some patients admitted to the Medical Qigong clinics had developed mental as well as physical disorders as a result of Qi deviations. A deviation refers to abnormal phenomena occurring within the patient or Qigong practitioner. The clinical symptoms include abnormalities in perception, thinking, and behavior.

If the Qigong doctor has not been adequately trained in internal purging techniques, his or her body's increased energetic field can act as a magnet and begin to attract the toxic energy from the surrounding environment (including the patient's pathogenic Qi). Once toxic energy enters into the body, it can immediately create a Qi deviation. Qi deviations should be treated immediately if possible. If Qi deviations occur during Qigong exercises or meditations, the practitioner should stop the practice immediately and guide the Turbid Qi (and bad feelings) out from the body, discharging the toxic energy out through the four extremities and into the ground.

The process of Medical Qigong meditations and exercises is said to cause an alchemic transformation of Shi Shen (Turbid Spirit) into Yuan Shen (Original Spirit). This transformation occurs when first beginning Qigong practice, at the "laying a foundation" stage of the workout. If the Turbid Qi is not removed at the beginning of practice, the Qi concentrated in the Dantian areas (or other parts of the body) will also become Turbid. This may bring about internal disturbances when the practitioner encounters unfavorable external factors such as suddenly being startled or becoming angry. Too much concentration and hard focus on the exercises and meditations can also lead to Qi deviations. Turbid Qi can create Turbid Shen.

When Turbid Qi travels along the Governing Vessel to the head, there is a feeling of heavy pressure in the head. In severe cases, psychosis can occur. Turbid Qi that escapes into the body's channels can result in distending or numbing of the body. To avoid such side effects, it is extremely important to establish an equilibrium between the Five Yin Organs. No matter which Medical Qigong system is followed, the primary task is always to dredge or purge the channels of pathogenic Qi, to regulate the Yin and Yang organs and to cultivate the body's Jing, Qi, and Shen.

THE MAIN CAUSES OF QI DEVIATIONS

Mental disorders and personality disorders may exist in some individuals prior to their study of Medical Qigong. Sometimes, individuals with a family history of psychosis and certain other mental disorders (such as bipolar disorder and depressive disorder) may be more predisposed towards these diseases. The practice of Medical Qigong meditations and exercises may trigger the onset of symptoms in predisposed individuals, especially if Qi deviations are not properly addressed.

1. A Week Constitution	From severe disease and weak respiration
2. Improper Dao Yin Qigong Regulation	From forced practice, hastily and indiscriminately training
3. Disbelief and Suspiciousness	From a closed mind, superficial mind, or preoccupied mind
4. Too Much Mental Concentration	From concentrating too hard, resulting in Qi and Blood to stagnation

Figure 18.1. The Main Causes of Qi Deviations

The main causes believed to contribute to Qigong deviations, according to research gathered by Dr. Wei Lin Shen of Shanghai, China, include the person's constitution and pathological state, improper Dao Yin Qigong regulation, disbelief in and distrust of the Qigong exercises and meditations, or too much mental concentration (Figure 18.1).

1. A week constitution can lead to a pathological condition. Patients with a weak constitution should not be required to sit or stand for long periods of time. Patients with severe disease and weak respiration incur Qi deviations if they are allowed to stand too long.
2. Improper Dao Yin Qigong regulation can result in Qi deviations. Qigong deviations may also occur as a result of forced practice (when the state of illness does not allow relaxation), or when individuals hastily and indiscriminately train in the techniques that circulate internal Qi. Lack of proper instruction from a qualified master of Medical Qigong therapy often results in a failure to train in the correct way. The failure to correctly apply the three Dao Yin principles and methods (proper regulation of the body's Jing, breath's Qi, and mind's Shen) in training practice, for example, leads to Qi deviations. Creating new techniques, training recklessly before mastering the primary techniques, or changing the techniques at random can also result in Qi deviations. For this reason the practitioners should be patient when practicing Dao Yin regulations. The goal is to achieve a tranquil, quiet, and empty state.
3. Disbelief, and suspiciousness can induce Qi deviations. Disbelief or an inability to adopt a correct attitude toward Medical Qigong effects (such as extreme suspiciousness), results in mental tendencies that will become deviations over the course of time. Qi deviations can result from: A Closed Mind, A Superficial Mind, and A Preoccupied Mind.
    a. A closed mind, full of fear, pride or bitterness may prevent the patients from connecting with their True Self.
    b. A superficial mind, or lack of commitment and belief in energetic healing, may cause the patient to fail in taking the Medical Qigong prescriptions seriously.
    c. A preoccupied mind may cause the patient's spirit (Hun) to "wander off" while practicing Medical Qigong therapy.
4. Too much mental concentration is the most frequent cause of Qi deviations. The strong focus of mental attention on the flow of Qi can distort its path and lead to Qi deviations. It can cause too much concentrated Qi and Blood to flow into the brain. Concentration on internal objects with too intense a focus can actually cause a stagnation, or Excess of

Qi in the area (e.g., concentrating too hard on a tumor can actually cause it to grow instead of dispersing it). Mild concentration is always preferred when practicing Medical Qigong exercises and meditations. A relaxed mind and body allows the Qi to flow freely.

CORRECTING QI DEVIATIONS

To correct any Qi deviation, it is important to understand the root cause of the deviation. The Medical Qigong doctor should check for the following causes of Qi deviations.

1. Postural Dao Yin deviations result from incorrect postural changes.
2. Respiratory Dao Yin deviations result from improper breathing methods.
3. Mental Dao Yin deviations result from improper mental activities and emotional disturbances. These emotional disturbances (due to the accumulation of toxic emotions within the internal organs) may manifest as spontaneous emotional outbursts.
4. Stressful life activities resulting from an improper balance of work and play, lack of sleep, or an improper diet may likewise cause Qi deviations.
5. Environmental disturbances during Medical Qigong practice such as the phone or doorbell ringing, may startle the practitioner and cause Qi deviations.

To correct the Qi deviation, the Qigong doctor addresses each possible cause separately, beginning with the patient's posture.

POSTURAL DAO YIN DEVIATIONS

To diagnose Qi deviations due to incorrect postural alignment it is important to observe whether:

- relaxation is being achieved,
- the posture is structurally correct to facilitate relaxation, and
- the appropriate tonifying, purging, or regulating technique is being used.

When a deviation occurs, the patient should examine it in accordance with the basic laws of postural alignment. A beginner is more prone to some disorders due to incorrect postures that cause headaches, dizziness, and a stiff neck.

MANIFESTATIONS OF POSTURAL QI DEVIATIONS

If postural deviations occur, first review the Eighteen Rules of Proper Medical Qigong Structure in relationship to the sitting or standing positions, and then review the other Dao Yin Qigong patterns (respiratory and mental Dao Yin training). The following are examples of specific Qi deviations related to improper postural alignment.

1. Eye distention results from excessively staring at external objects during the meditations and exercises. To prevent this type of Qi deviation, encourage the patients to always use a soft focus.
2. A stiff or painful neck is usually caused by forcefully attempting to suspend the head. To prevent this type of Qi deviation, have the patient relax the neck muscles and sink the shoulders.
3. Shoulder and back pain can occur when patients fail to relax the muscles of the shoulders and back, stretch the back excessively, hollow their chest too much, or hold an unfamiliar posture too long. To prevent this type of Qi deviation, have the patients relax and sink their shoulders and imagine the back melting down into the hips and legs.
4. Waist and hip pain (Lumbago) come from several factors.
    a. Tension in the hip muscles causes pain in the hips that extends to the waist.
    b. Twisting the waist without first relaxing the hips can result in both hip and waist pain.
    c. Forcefully twisting the waist may also cause pain.

    To prevent this type of Qi deviation, have the patients relax their waist and hips and sink the energy into the Earth via the feet.
5. Abdomen and lower extremity distention or flatulence results from the forceful pulling-in of the Stomach, or too much concentration of the mind on the lower extremities. To prevent this type of Qi deviation, have the patients relax their abdomen and lower extremities, allowing the Qi to sink naturally.
6. A swollen and painful anus, or dry stool, can

result from raising the anus too forcefully. Also, hemorrhoids can develope from holding the breath too forcefully while focusing on the lower abdominal area during the Abdominal Breathing Holding method. To prevent this type of Qi deviation, have the patients close their anal sphincter softly and relax their buttock muscles.

7. Sore knees are a result of crouching too low, over-bending the knees, or extending them past the toes. To prevent this type of Qi deviation, have the patients keep their knees in proper alignment and guide the pressure of the body weight to flow behind the legs and not in front.
8. Heel pain can be caused by shifting the body's weight excessively onto the heels during walking or standing practice. Heel-ache can also occur if the patients focus too much attention on their heels instead of the center of their feet for balance. Knocking, stomping, or excessively dropping the heels against the ground, as well as sexual Excess, or a Kidney Deficiency can all cause pain in the heels. To prevent this type of Qi deviation, have the patients relax their legs and waist and imagine that their feet are kneading the ground. This squashing and kneading action is used to encourage the free flow of Yin Qi from the Earth into the body.
9. Improper hand movements occur when patients fail to distinguish between Yin and Yang energetic properties, or apply either too much or too little strength in the raising and lowering of the arm movements during Qigong practice. Both the alignment and energetic function of the patients' arms, hands, and fingers should be checked.
    a. If the arm movements are too dynamic, they will cause an abundant amount of energy to become either gathered or dispersed; this results in Qi deviations.
    b. While performing a tonification exercise, if the palms of the hands are turned outward, away from the body (instead of inside facing the body) this can easily cause diarrhea or a Qi Deficiency.
    c. If the fingers move up to point at the chest, the energy released from the hands can cause tightness in the patients' chest. If the patients' hands point obliquely at their neck and face, the emitted Qi can cause dizziness, nausea, and edema of the face in those patients who are sensitive to the energy movement within their channels and collaterals.

RESPIRATORY DAO YIN DEVIATION

Deviations in breathing often result from the incorrect practice of the deep inhalation and exhalation methods, when first starting Qigong meditations. Both inhaling and exhaling should be gentle, thin, even, and long. When practicing, the patient should breathe properly and naturally to regulate the breath and should avoid holding the breath.

1. Deviations can be due to improper exhalation. Determine whether the exhalation is long enough for relaxation and quiescence when sinking the breath. Excessive sinking of the breath, however, can cause pain in the legs by depleting Qi flow to the upper torso, and by increasing the weight and gravitational pressure within the tissues of the lower torso. Exhalations that are too long or too deep can cause shortness of breath, headaches, tightness in the chest, discomfort in the Heart, and abdominal distention.
2. Deviations can be due to improper inhalation. Determine whether the inhalation is long enough for relaxation and quiescence. For example, when practicing the Abdominal Breath Holding technique (the Two Inhaling and One Exhaling Method, which employs Reverse Breathing), the two inhalations should not be connected, for tightness in the chest will occur. Pause, therefore, between each breath and allow the exhalation to be fast and short rather than sustained and drawn out. Otherwise, the condition will cause general weakness and fatigue.

To rectify this condition, when you inhale twice through the nose, simultaneously pull in the navel and perineum area as if to lift your body. When you exhale through the nose, guide the Qi down into the Middle Dantian.

If this method is applied, the symptoms such as tightness in the chest, shortness of breath, and abdominal distention will disappear (The Rectifying Respiratory Qi Deviations exercise can also be used). When the breath is well regulated there will be no difficulty sinking the Qi down to the Lower Dantian.

3. Deviations can be due to improper tone resonation. Another Respiratory and Mental Dao Yin deviation can be created through the improper use of healing words or tone resonations. The improper use of tones (with too much breath or mental concentration placed on the rising and falling sound) may cause symptoms such as dizziness and slight fever, tightness in the chest, weakness in the legs, foul breath, and bloody stool.

These symptoms cannot be relieved by Western medicine. Some patients, however, have succeeded in rectifying such deviations by practicing the Opening and Closing the Three Dantians exercise (see Chapter 15). This exercise is used to regulate the Excess Yang, and to restore the body's energetic equilibrium.

Some patients are given the prescription of uttering one pitch sounds (known in China as the first or straight tone). This straight sound has a steady tone, and a rising volume, which can easily cause the energy to ascend. After the patients have completed their prescription and ended the exercise, if the energy continues to rise, the Qi deviation will cause dizziness and nausea. In this particular case, the patients should stop the exercise immediately. To rectify this condition, have the patients utter the sound in the third tone (the descending and ascending tone), and by deepening his or her voice, then raising the pitch. This increasing volume and deepening tone relaxes the body and causes the Qi to descend.

This example illustrates the fact that if the patient is allowed to select any prescription at random for mental concentration, without understanding the theory of Medical Qigong, he or she can easily get into trouble.



Figure 18.2. Rectifying Respiratory Qi Deviations

4. To rectify respiratory Qi deviations, the following exercise can be used. It will amend respiratory deviations and balance the Yin and Yang Qi, as well as clear any stagnant Qi.

When the practitioner feels uncomfortable after Medical Qigong exercises, practice this method for 20 minutes. This is an alternate nostril breathing exercise and requires both inhaling and exhaling through the nose. The abdomen expands upon inhalation and contracts upon exhalation.

From a seated posture, begin by imagining that there are three channels that start at your tailbone and travel up the body. The first channel intersects with the right nostril, the second channel joins the Baihui GV-20 point and the third channel intersects with the left nostril (Figure 18.2).

Place your left hand on your Lower Dantian, with the right hand resting on the nose. It is important to focus the mind on the energetic flow of the breath. Inhale through the left nostril and allow the Qi to flow down the Conception Vessel into the Lower Dantian and tailbone area. Hold the breath, pinch the nose and draw the Qi up the Governing Vessel into the Baihui area, and then circle the energy down to the Conception Vessel to the coccyx to complete the Microcosmic Orbit. Exhale through the right nostril. Repeat this sequence, alternating the focus of the mind's concentration to follow the beginning flow of energy from the left to right nostril and visa versa.

When training in Medical Qigong prescriptions, it is equally as important to relax the mind as the body. Therefore, this exercise should be practiced in a leisurely manner, with a carefree attitude, and a smile.

MENTAL DAO YIN DEVIATIONS

Deviations in mental activities are primarily caused from excessive thinking and too much focused concentration. These type of mental deviations should be rectified by controlling one's mental activities. It is important to fully understand the foundational principle of the Shen controlling all mental activities that determine the physical, emotional, and energetic activities. Any mental deviation should be regulated and controlled through intention.

It is sometimes difficult for patients who have just started Medical Qigong prescriptions to become absolutely tranquil; this may lead to mental Qi deviations. One way mental Dao Yin deviations can be rectified is by a mantra, or counting breaths (using one thought to replace many thoughts). After this technique is mastered the patients can advance to concentrating their mind on an external object in the surrounding area.

1. The cerebral cortex plays an important role in Qi deviations of the mind. Medical Qigong regulates the cerebral cortex to restore balance to the energetically unbalanced parts of the brain. If the mind is agitated or depressed for a long time, it can cause a long term disorder of the whole nervous system and, thus, cause various kinds of chronic diseases. A healthy nervous system takes the leading role in adjusting, regulating, and unifying all functional activities. It is responsible for maintaining a dynamic equilibrium.

If deviations occur during Medical Qigong practice, the cerebral cortex loses control of the nervous system. Abnormal phenomena may occur and mental and emotional activities may become uncontrollable. If patients are not careful, they can actually develop meditation induced diseases, or meditation induced psychosis known as Tsou Huo Ru Mo, which translates to "the Fire becomes Excessive and the demons enter." In other words, the patient's Heart and Liver become overheated, causing the Hun to leave and Po to take control of the body. This in turn can lead to chronic psychoses or demon possession.

Because Qi deviations can have serious consequences, the Qigong doctor must have an extensive knowledge of Medical Qigong principles to prevent and correct Qi deviations, stagnations, and adverse Qi flow. The mind should, for example, always be free from overconcentration or "distortions of consciousness" during practice. If a beginning patient feels a hot sensation in certain parts of the spine, and tries to force its energetic movement up through the Five Passes of the Governing Vessel (see Chapter 30), this can cause "distortions of consciousness" and mental confusion, which may result in hallucinations.

A deviation caused by excessive focused mental concentration can also lead to a loss of self-control and produce such disorders as uncontrollable head-shaking, shoulder shrugging, hand and leg quivering, stumbling, staggering, uncontrolled crying or laughing, or even stiff and twisted extremities and opisthotonosis. To avoid this loss of self-control, do not allow the patients to use their mental intention and focused concentration at random, but rather have them focus their attention on quiescence to tranquilize the mind and recuperate their health.

Failure to properly lead and guide energy during Medical Qigong practice may also cause adverse deviations of Qi in the patient's Middle Dantian. In the Middle Dantian, the patient's Lung Qi rises and returns through the opening and closing actions of the Shan Zhong CV-17 point. If the Qi within the Middle Dantian begins to deviate, it can condense and cause stiffness, pain, and a feeling of suffocation in the chest region. To correct this condition the Qigong doctor extends energy into the patient's Middle Dantian to regulate and tonify the patient's Qi, and especially the Gathering (Zong) Qi. This treatment also regulates and tonifies the patient's Lungs and Upper Burner, as well as diffuses any Rebellious Lung Qi (see Chapter 22) as it unburdens the emotions of the Heart.

2. There are three rules for determining proper mental focus. The following three rules determine the focus of the patient's mental activities and are implemented to help avoid Qi deviations while practicing Mental Dao Yin training:
    a. Concentrate the mind on a motionless object. A patient suffering from hypertension can, for example, concentrate on still lake water, but not on a stormy sea.
    b. Concentrate the mind on a near object. A patient with Liver trouble can, for example, concentrate on a nearby pine tree. If the patient is at a park, absorbed in concentration on a pine tree that is far away, the patient must mentally trace and locate the pine tree with painstaking effort. This is achieved through expanding and extending the imagination. If the patient suddenly becomes mentally distracted or preoccupied, the purpose of the meditation is defeated. Once distracted, it will be very difficult for the patient to reconnect to the pine tree because of its distance. As a result, the patient's mind wanders and the patient may become discouraged.
    c. Concentrate the mind on a familiar object. Concentrate on something which creates a peaceful, emotional connection. The emotional connection will facilitate the proper attitude and diminish any likelihood of mental strain.

    When deciding on which familiar object to focus the attention on, patients must not choose a person, their own work or creations, or obscene things. Objects that have been used to do harm or evil should also be avoided. Patients are also forbidden to shift their thoughts from one thing to another or back and forth without stopping. Remember that it is the individual's Shen (Spirit) which guides all mental activity and determines the body's energetic actions, therefore the mental concentration should have purpose.

Adjust each technique according to the specific case. When prescribing Medical Qigong therapy, it is important for the doctor to adjust each meditation and exercise according to the patient's specific case. In all cases, the Yi (imagination and intention) must lead the Shen and the Shen must lead the Qi.

The following examples demonstrate how to adjust prescriptions for different patient's needs.

- Patients with hypertension should concentrate on a low place instead of a high place, or on an object below eye level.
- Patients with hypotension (including other Deficient conditions such as anemia) should concentrate on a high place instead of a low place, or on an object placed above eye level.
- Patients with Lung problems such as tuberculosis should concentrate on white and light objects (e.g., white clouds).
- Patients with Spleen and Stomach diseases should concentrate on yellow objects (e.g., yellow chrysanthemum, dahlia).
- Patients with Liver problems like hepatitis should concentrate on green objects (e.g., pine and cypress trees).
- Patients with a Heart Deficiency should concentrate on red objects. Patients with an Excess conditions of the Heart, however, should

never concentrate on the color red, and should only choose pink objects instead. A pure red color is too energetic for patients with Excess conditions and may overexcite their Heart, making it difficult for the patient to become relaxed.

- In Medical Qigong, the color black is sometimes assigned to the Kidneys. Focussing on this color can, however, easily cause the Kidney energy to sink downward, creating an emotional state of depression or anxiety. Therefore, when treating patients with Kidney diseases, it is preferable to choose things of purple, indigo and vibrant blue color.
- Mentally depressed patients (in a severe cases) should not practice any dynamic Qigong exercises until their depression has passed. Otherwise, they may develop headaches, tightness in the chest, or in severe cases, shock. To rectify this condition, the Qigong doctor must lead the toxic and stagnant Qi downward along the channels and out of the body.
- Patients with uncomfortable light or heavy sensations should concentrate on the opposite side on their body instead of the afflicted area. If they feel that their lower limbs are too heavy to lift during the exercises, for example, they can correct this symptom by focusing on the Baihui GV-20 point at the top of the head. If the patients feel that their body is too light and unsteady, they can focus on the Yongquan Kd-1 point located on the soles of the feet.

STRESSFUL LIFE ACTIVITIES

Stressful life activities create a flood of adrenaline within the body. This occurs not only from the core of the adrenal gland in the medulla (which responds to stress by releasing adrenaline in to the blood stream), but also from the endings of the vertebral lumbar division at the core segment of the major internal organs. Adrenaline spreads throughout the body and activates not only the body's sympathetic nervous system, but also the adrenal glands. The Heart rate, respiratory rate, blood pressure, and Blood flow to the muscles are all increased as they respond to the "fight or flight syndrome."

When this happens, the immune system is called upon to balance the whole stress mechanism and is, therefore, called away from its normal activities which include monitoring cellular activity and fighting the growth of disease. A life of constant stress, therefore increases susceptibility to illness. Meditation takes the patient out of the stress mode, thereby shutting down the adrenal glands, and allowing the immune system to return to its normal functioning.

Chronic stress wears down the mind and body, thereby producing anxiety or depression. Stress begins with an overexcitement of the nervous system and then slowly works its way deep into the body like wet cement, causing the shoulders and upper back to become tense and rigid. Happy occasions (such as weddings) and other normally pleasant events, also produce stress, which can be detrimental when the patient's life style is not properly balanced. An unstable life style is very stressful and can lead to depression, anxiety, and Qi deviations. The capacity to bear stress depends upon the individual's constitution, diet, support system (or lack thereof), the nature of the stress, and the congenital strength of the nerves. When stress levels surpass the nervous system's capacity to handle them, "the nerves break down", resulting in all sorts of physical, mental, and emotional disturbances. Certain neurotransmitters are depleted, leading to a chemical imbalance which can be aggravated by self medication (e.g., alcohol or drug abuse). These disturbances, if unheeded can eventually lead to organ malfunctions, cysts, tumors, cancer, and premature death. In order to avoid such states, a balance between work and rest must be maintained.

At a conference of the International Society for Neuro-immunomodulation (entitled *The Effects of Stress and Depression on Physical Disease*) Dr. Philip Gold, of the National Institute of Mental Health, stated that stress and depression cause the body to secrete high levels of hormones; (for example, cortisol) into the bloodstream. These hormones, if unregulated, can destroy the appetite, cripple the immune system, shut down the processes that repair tissue, inhibit sleeping patterns, breakdown bone density, aid the onset of infection, and even instigate cancer cell growth.

An individual's emotional past determines his or her present state of health, both physical and emotional. Past emotional belief structures are responsible for both creating and healing diseases. Just as thoughts drift through the mind but do not manifest until they reside within a belief structure, so emotional wounding resides within the tissues and cells waiting to be activated by emotional upheavals. Our thoughts materialize via choices and manifest within the body.

In American society, sharing traumatic wounds is often the first act of intimacy and bonding. It provides a common ground for relationships and supports the "pain structure" that deepens the bond. People can become addicted to empowering their wounds which, in turn, support and empower the disease. This exchange of painful personal traumas is reinforced by receiving sympathy and strong empathy, but does not fully release the pain from the tissues.

Although talking about past traumas can begin the process of healing, problems can emerge when these past traumas manifest through the following belief structures.

1. The individuals believe that they can only receive affection and attention when they suffer, and use their "neediness" to keep their significant other(s) from leaving or becoming more independent.
2. The individuals become stuck in one emotion -- anger, grief, fear, worry, or hurt -- and are unable to express a healthy range of emotions.
3. The individuals do not have an adequate support system.
4. The individuals do not have the incentive to heal themselves or the belief that they can be healed.
5. The individuals bond to anyone, out of fear of being alone, as long as they receive the attention they crave.
6. The individuals have low self-esteem and do not seek help or work out their emotional issues; they have difficulty trusting anyone to understand their pain.

The desire for sharing ones pain in order to feel loved can lead to a habitual way of relating to those closest and dearest. When such individuals feel taken for granted, or unappreciated, they may immediately resort to past traumas. If this fails to illicit the desired response, a new trauma or wounding may be unconsciously created to get back the attention and love and need. The individuals may, for example, physically injure themselves in an accident, or manifest a physical illness. This in turn can become an addiction, empowering old wounds and creating new ones, and may lead to chronic illness. The Shen becomes divided to support the new belief structure, and the Qi deviates from its assigned job of protecting the body, thus creating illness. This is not a conscious process, but an unconscious one, which needs to be brought into the patient's awareness to be healed. Then, and only then, can the Yuan Shen and Zhi Shen act as one unit directing the body's Qi towards its proper function of healing.

Because energetic healing occurs in the present and not in the past, victims of past traumas will never heal if their energy continuously regresses to the armored traumatic belief structure. Both the doctor's and the patient's Yi (Intent) must therefore, focus on forgiveness (of self, others and the specific tragic situations) to free the patient from toxic wounds. The patient's desire and determination to be well must reach the degree that they are willing to do anything to get well, including giving up on the "secondary gains" of illness (i.e., risking abandonment, or loss of attention received during the illness). Patients must be encouraged to find new ways to fulfill their needs, and must be encouraged and supported through this difficult transition. This point is illustrated effectively in the following traditional Chinese story.

> There once was a palace official named Cheng Guang Wei who owned a servant named Song Li. As the pressures of life wore on Director Cheng, he began to sink into a deep depression. Soon he began to lose all hope in life and desperately sought relief. Not content with the wine and festivities at hand, his attention soon turned to his servant Song Li, who always seemed to be happy. Song Li was plowing the fields, up to his ankles in

mud, singing and seemingly enjoying his life. Upon observing this, Director Cheng walked up to the edge of the field and called out, "Song Li, why are you so happy? What is the secret of your contentment?" To which Song Li responded, "Sir, come into the field with me, and I will tell you." The director, not wanting to get himself muddy said, "No, tell me from where you are." To which Song Li replied, "I cannot explain everything to you if you do not come into the field." Director Cheng, aggravated by this reply, answered, "Very well, since you refuse to tell me, tomorrow you will work in the stables." Song Li answered, "If that is your wish, sir," and went about his work contentedly.

Two weeks went by, and the pressures of the palace were starting to take a serious toll on Director Cheng. All of his problems, it seemed, were insurmountable. Locked in turmoil, he began to roam his property seeking peace until he heard singing coming from one of the stalls in the stables. Director Cheng went to investigate and sure enough, it was Song Li, now up to his knees in horse manure and still singing as beautifully and joyfully as a bird. At first Director Cheng was enraged at Song Li's contentment, but then became perplexed, because the duties of Song Li's new job were much more difficult than the previous work.

Director Cheng approached the edge of the stables and called, "Song Li, why are you so happy? What is the secret of this contentment you possess?" To which Song Li responded, "Sir come into the stall with me, and I will tell you." Repulsed by the stench of the horse manure and filth, not to mention feeling protective of his royal robe, Director Cheng answered, "Song Li, tell me the secret of this joy and contentment that you possess even in the midst of a barn full of stench and dung." Song Li answered, "I will tell you sir, but first you must come in to where I am." "If that is your answer, then tomorrow you will work in the hog pens!" shouted Director Cheng. To which Song Li answered, "If that is your wish, sir," and went about his work contentedly.

Well, things went from bad to worse for Director Cheng in the palace; seeing that he was about to lose everything, he contemplated taking his own life. Making one last round of his property, he again heard singing, this time from the hog pens. Realizing it was Song Li, Director Cheng slowly approached. Sure enough, there was Song Li, up to his thighs in pig dung, slop and filth, and still singing. Leaning against the fence, Director Cheng called out, "Song Li, why are you so happy? What is the secret of your contentment and joy?" To which Song Li responded, "Sir, come into the pen with me, and I will tell you." Director Cheng, now at the end of his rope, answered, "Very well, I will come in with you," and began to climb the fence to enter the hog pen. "Stop!" shouted Song Li, "I will come over to you, it is not right that you defile yourself on my account. But now you will truly listen to what I have to share and are ready to hear the words I speak. For now you are willing to sacrifice all, even your physical comfort, to receive spiritual knowledge and insight."

The moral of the story is clear: unless we are ready to abandon all masks (pretenses and defence mechanisms) of the emotional ego, it is extremely difficult to free ourselves from the toxic emotions that steal our life-force energy and direct our lives. If we are not intimate with our emotions, we cannot perceive the dynamics behind those emotions. After all, emotions are only energy currents which flow in, out, and through our bodies. Because our emotions reflect our intentions, any awareness of unprocessed emotions will lead to an awareness of deep-seated intentions. It is through this understanding that Qigong doctors train their emotions and mental thinking to regulate the Shen.

SHEN DISTURBANCES AND EMOTIONAL DYSFUNCTIONS

All Shen disturbances relate to emotional energetic dysfunctions. Generally, Shen disturbances can be divided into two categories: Yin disturbances and Yang disturbances (Figure 18.3). These

Yin and Yang disturbances affect the patient's thoughts and emotions.

A thought is energy that has been shaped by consciousness. Every experience, or change in experience, reflects intention, desire, and will. Any discrepancy between intention and emotions leads to a splintering reaction of the energetic self, which can cause a breakdown of the body's life-force energy and ultimately lead to disease.

Emotional energetic currents have different frequencies, resonating between low (fear, anger, worry, etc.) and high (love, forgiveness, joy, compassion, etc.). Lower frequencies deplete the physical body, draining it of its precious reserve of life-force energy. This deterioration begins to manifest in the spiritual fields of energy surrounding the body, and percolates down to the emotional, mental, and finally the physical level. Conversely, high frequency emotional energy raises the body's energetic frequency and begins to radiate outside the physical body. This does not mean that the patient must learn to suppress feelings of anger, hurt, etc. These are natural emotions that serve a positive function in protecting the individual from harm. It is only when emotions are suppressed, denied, and accumulated that they become highly toxic to the body. When this happens, new anger is fueled by old anger. The new hurts are suddenly blown out of proportion (related to the event), fueled by ancient emotional pain, until the patient's physical structure is overwhelmed.

Patients may become overactive and overemotional when under stress, when their energy becomes disrupted. Every emotional disturbance alters the breathing pattern, changing from slower to faster respirations (each breathing pattern varying according to the internal organs involved).

According to *The Yellow Emperor's Inner Cannon* (Spiritual Axis), the Blood, Ying, Jing, Qi, and Shen are stored in the Five Yin Organs (Liver, Heart, Spleen, Lungs, and Kidneys). An Excess condition will cause any of these components to leave their respected organs. This will:

- deplete the patient's Jing (Essence),
- cause the patient's Hun (Ethereal Soul) and Po (Corporeal Soul) to become unsettled,
- cause the patient's Zhi (Will) and Yi (Intention) to become muddled, and
- cause the patient's Shen (Spirit) to leave the patient's body.

Shen Disturbances	
Yin	**Yang**
Qi is compressed.	Qi is expanded.
Patient is depressed, withdrawn.	Patient is manic, expressive, impulsive, volatile.
Patient is too quiet.	Patient is too loud.
Patient avoids feelings.	Patient inappropriately expresses feelings.
Patient is too introverted.	Patient is too extroverted.

Figure 18.3. Shen Disturbances

When emotionally upset, energy literally rises upward, affecting the organs and releasing additional emotions stored within the tissues. To become free from these emotional reactions, patients must be taught to relax and release the energetic charge of emotions. This will allow stagnant Qi to become energetically discharged from the body. By cultivating a healthy attitude, and not holding onto, or suppressing, the emotions, the body will begin to seek its energetic balance naturally. This is initiated by having the patient sink his or her Mind and breath deep into the Lower Dantian to rebalance the life-force energy.

TREATMENT TECHNIQUES

When treating patients with Shen disturbances, the Qigong doctor categorizes the emotional and thought dysfunctions into Yin and Yang Shen disturbances.

1. In Yin Shen disturbances the patient's energy compresses inward. These patients have a tendency to avoid feelings, becoming quiet, withdrawn, and depressed. They also tend towards an introverted personality and posture.

   When treating patients with a Yin Shen disturbance it is important for the Qigong doctor to redirect the patient's Shen towards specific actions, and encourage them to use spiritual mantras and affirmations to gain inner strength and confidence.

2. In Yang Shen disturbances the patient's energy expands outward. These patients have a tendency to express their feelings, are loud, impulsive, volatile, and manic. They also tend to be extroverted in personality and posture.

   When treating patients with a Yang Shen disturbance it is important for the Qigong doctor to redirect the Shen (with a "reality check" towards the patient's actions) and set parameters for their boundaries. A sudden awakening to the responsibility of personal actions will generally send the patient into emotional shock.

   One treatment technique commonly used in the clinic to calm and restore harmony in the patient's Shen (due to a Deficient condition) is for the Qigong doctor to extend Qi into the patient's Middle Dantian and Yellow Court areas. Once this area has been sufficiently balanced, the doctor then ends the treatment by rooting the patient's Qi, by drawing it into the Lower Dantian.

PRESCRIPTIONS AND HOMEWORK

Several of the most recommended meditations used for the purpose of calming the patient's Shen are listed as follows.

1. The Energy Melting Meditation is used to relax the body and reduce stress. Relax and imagine melting from the top of the head to the bottom of the feet, like ice melting into water and water flowing downward into the Earth. This image centers, grounds and roots the Mind.



Figure 18.4. During the exchange of Fire and Water meditation, the fusion of Heart Fire and Kidney Water creates steam.

   If the patients are lying down, have them feel the upper layers of their body melting through the lower layers and into the Earth. Ice melts into water and pours into the Earth.

2. The Exchange of Fire and Water Meditation unifies the energies of the Kidneys (Water) and the Heart (Fire) and is often called the Fusion of Kan and Li. It is used to unify opposite principles within the body, to balance the energies of the mind, body, and Prenatal and Postnatal Shen for creating wholeness. It also strengthens the immune system and the bones, thus slowing or preventing osteoporosis.

   Sit and begin by breathing naturally, while inhaling and exhaling through the nose. Visualize the Lower Dantian as an ocean of water, and the Heart as a ball of fire. Imagine the waters of the Lower Dantian beginning to flow up the center of the body, reversing their natural flow. Now imagine the Fire of the Heart beginning to descend the center of the body, reversing its natural flow. As the Water and the Fire join in the Yellow Court (located in the lower part of the solar plexus), the Water vaporizes and becomes steam (Figure 18.4). This hot mist travels throughout the entire body. It should feel warm and pleasant.

Next allow the hot mist to enter into your bones and flow through the Marrow. Imagine this mist beginning to solidify and harden making your bones solid and radiant with white light. Upon completion of the meditation, relax and allow the images to disperse as you sink into the Wuji.

These following exercises are a series of meditations used in the clinic for detoxifying emotional stasis.

3. The Sun and Moon Meditation is used to detoxify emotional stagnation and establish physical, emotional, and spiritual clarity.

Begin from a sitting or Wuji posture (Figure 18.5). Inhale and exhale through the nose. Imagine the sun over the left eye, and the moon over the right eye, appearing side by side over the head. Feel their presence over the Baihui point, at the top of the head. Imagine that the sun (on the left side of the body) pours golden light, and the moon (on the right side of the body) pours silver light. Both streams of light meet at the Baihui point on the top of the head, combining into white light energy. This white light energy pours into the body, filling the entire body from the feet to the top of the head (like a pitcher of water filling a glass). Once the body is completely full, the energy begins to spill out of the pores. At first a thick, black, sticky energy pours out of the pores, and flows down to the ground. This energy contains all the physical, mental, emotional, and spiritual toxins that are being released from the body. As more and more of these toxic substances leave the body, they start turning from black to gray, then from gray to white. Feel the body radiate this white energy in all six directions (front, back, right, left, up, and down) filling the entire room. After several minutes of purging and tonifying the body, relax the mind and focus your attention on to the Lower Dantian, before ending the meditation.



Figure 18.5. During the Sun and Moon Meditation imagine that the white light energy that is pouring down the body, is purging toxins from the internal organs, releasing the Evil Qi out from the pores.

4. The Releasing Emotional Blockages and Energetic Armoring Meditation is used to dissolve emotional blockages from the internal organs. When these blockages are released, the emotions are restored to balance. Begin from a Wuji posture, and inhale through the nose and exhale through the mouth.
    a. Direct your attention to your Liver. Every time you inhale, visualize and feel the emotions of kindness and compassion entering into your Liver. As you exhale, release anger or jealousy. Repeat for 18 breaths.
    b. Direct your attention to your Heart. Every time you inhale, visualize and feel the emotions of joy, contentment, and tranquillity entering into your Heart. As

you exhale, release nervousness and excitement. Repeat for 18 breaths.

c. Direct your attention to your Spleen. Every time you inhale, visualize and feel the emotions of trust, openness, and sincerity entering into your Spleen. As you exhale release worry, obsessiveness, and self-doubt. Repeat for 18 breaths.

d. Direct your attention to your Lungs. Every time you inhale, visualize and feel the emotions of dignity, integrity, and courage entering into your Lungs. As you exhale release grief and anxiety. Repeat for 18 breaths.

e. Direct your attention to your Kidneys. Every time you inhale, visualize and feel the emotions of self-confidence and inner strength entering into your Kidneys. As you exhale release fear and loneliness. Repeat for 18 breaths.

f. Finally, inhale, visualize and feel the emotion of a full-bodied state of peace and bliss. As you exhale, ripple and resonate this feeling into the room, filling the surrounding energetic space with this emotional enlightenment. Repeat for 18 breaths.

DISTURBANCES DURING QIGONG PRACTICE

The patient should carefully choose a safe and quiet environment for Medical Qigong exercises and meditations. Most often a patient is already in a state of relaxation when they become startled by disturbances generally caused by an unexpected sound or event. This sudden disturbance can disrupt the Heart Qi. When training, if you become startled, do not open your eyes. If you open your eyes, the disturbed energy will be thrown into disarray, causing a blockage of vital Qi (usually in the Heart). This reaction will cause deviations which can be difficult to rectify.

If instead you continue exercising with your eyes shut as if nothing had happened, you can restore your mind to a normal state of quiescence, by guiding the Qi up the Governing Vessel and down the Conception Vessel (i.e., the Microcosmic Orbit). Even if you were shocked by the un-



Figure 18.6. The doctor strikes the patient's Mingmen area and focuses his or her attention to lead the disruptive Qi downward into the Earth. This helps the patient stop the uncontrollable muscle deviation spasms.



Figure 18.7. The doctor directs energy into the patient's foot, through the Lv-3 point, rooting the patient's Rebellious Qi into the Earth.

expected sound or event, restore the mind to a normal state of calmness by immediately performing the Opening-and-Closing the Two Dantians technique. The two Dantians refer to the Upper Dantian (Yintang point) and the Lower Dantian (Qihai point) areas (see Chapter 20).

To perform this technique, raise both hands to the lower jaw and breathe in with a hissing sound as if inhaling a mouthful of cold air. After the inhalation, the hands will move up to the Upper Dantian, and perform the opening exercise while exhaling slowly. Next, exhale while closing slowly. After four repetitions move the hands to the lower abdomen and perform the Opening and Closing of the Lower Dantian four times.

Usually the emotions will calm down after performing this exercise four times. If you still feel uncomfortable, you can perform the exercise eight times or more, until you become calm.

Note: It is good to ensure a quiet, safe environment in which to practice, preferably a place outside, with fresh air, among flowers, grass or thick, healthy green trees. Because the inside of the body matches the outside environment, when searching for specific directions to face while practicing Medical Qigong, it is important to avoid training in or near:

- extremely intense direct hot sunshine,
- a cold strong wind,
- a thunder and lightning storm,
- old withered trees,
- old graves or tombs,
- electric generators, power lines or power plants,
- dump sites,
- polluted sites, rivers, etc., and
- do not practice shortly after earthquakes, tornadoes, hurricanes, hailstorms, etc.

UNCONTROLLABLE MUSCLE DEVIATIONS

Sometimes a patient's body begins to automatically quiver, shake, tremble, or vibrate, revealing an energetic re-patterning causing muscle movement which cannot be stopped. When this happens, part of the body often keeps moving for several hours, causing exhaustion. Sometimes Qi in the legs and Heart rushes into the head, compounding the problem.

For older patients this is considered a dangerous symptom because their lower extremities are generally weaker. In mild cases the patients feel energy rushing upward into their head. In severe cases the whole body trembles because the Qi leaves the Conception and Governing Vessels and empties into the body itself. In these extreme cases energy muscle patterning should be controlled in the following manner.

1. Advise the patient by saying, "It is time to relax and calm down. You need to end your exercise and rest." This method is usually very effective when repeated over and over, again. If the patient is unable to stop, perform the next method.
2. Direct the patient to place their left hand on the Middle Dantian and the right hand on top of the left hand. Tell the patient that you will help them stop by striking their Mingmen area (Figure 18.6). Press their right hand with your left hand, to compress their Middle Dantian, while using your right palm to strike the patient's Mingmen three times, directing your attention down to their feet. This can help them stop moving.
3. If the above two methods do not help, direct the patients to turn their right foot inward with the big toe pointing at the heel of the left foot. If they cannot do it without help, take their left hand in your right hand and with your foot push the big toe of the patient's right foot to point at the left heel. That should stop the movement.

   Next, touch the patients' Taichong Lv-3 point, between the big toe and second toe, with the "sword fingers" Qi emitting technique. In this technique, the doctor uses the index and middle fingers to emit Qi into the patient and guide their Toxic Qi down into the ground (Figure 18.7).

RECTIFYING QI DEVIATIONS USING TAIJI RULER

If patients are experiencing too much Heat, they are concentrating too much and need to change the position of their tongue and perhaps



Figure 18.8. The Qi regulation exercises of the Taiji Ruler system are excellent for correcting Qi deviations.

switch meditations. The Taiji Ruler is very effective in rectifying deviations caused by inappropriate tonification or purgation, and can be used to dredge the channels and collaterals to promote the flow of Qi and Blood.

When performing this exercise, the rotation of the Ruler upward and outward (away from the body) is generally used for leading and increasing the energetic flow of Qi and Blood in the upper extremities. The downward and inward rotation of the Ruler is generally used for leading and increasing the energetic flow of the Qi and Blood in the lower extremities.

The purgation of energy blocks are usually cleared through downward movements (from Heaven to Earth). Tonification is implemented through upward movements (from Earth to Heaven). Using these methods, the patients can amend their deviations and promote the increase of Qi (Figure 18.8).

CHAPTER 19

DISORDERS AND DEVIATIONS OF THE SOUL AND SPIRIT

INTRODUCTION TO SPIRITUAL DIMENSIONS

An accepted reality in Medical Qigong therapy is the body's relationship to both the physical and spiritual world. The physical world of the living is considered a Yang state of existence, while the supernatural-spiritual world is in a Yin state of existence. Once the Qigong doctors' Shen has reached a high state of sensitivity, they can transcend their normal conscious perceptions and senses, to observe, and even communicate with the spiritual Yin world (see Six Transportation's of Shen, Chapter 13).

Within the subtle realm of the spiritual world, the existence of spiritual entities and ghosts are divided into two divisions of Yin and Yang (Figure 19.1). There is a significant difference between spiritual entities and ghosts.

1. A spiritual entity belongs to the Yang category of the Subtle Realm, and comes from the formation of nature. Spirits are considered the ethereal beings of the universe, who depend on the absorption of natural energy and are affected by the energetic cycles of the Earth. They are conscious beings, able to transform themselves into any size, shape, animal, or being (shape-shifting). A spiritual entity can affect changes in electrical current within the body's energy fields, or control certain areas on the body's nervous system. Spiritual entities can be separated into two divisions: Yang (good) and Yin (evil) influences.
    a. Yang spiritual entities are commonly referred to as angels, guides, spirits of the light, enlightened masters, and similar positive beings. These spiritual entities assist mankind (communicating through the body's Hun) in their quest for enlightenment. They assist individuals to make beneficial decisions that promote spiritual maturity.


Physical World
Spiritual World
Yang
Yin
Yang
Yin
Qi
Shen
Jing
Projection of Qi and Shen, Spirit Travel, Soul Travel
Yang Spiritual Entities
Yin Ghosts
Yang
Angles, Guides, Spirits of the Light
Yin
Devils, Demons, Spirits of Darkness
Yang
Phantoms, Free-Floaters
Yin
Poltergeists, Banshees

Figure 19.1. The Spirit World

   b. Yin spiritual entities are commonly referred to as devils, demons, spirits of darkness, evil spirits, and other similar negative spiritual manifestations. Yin spiritual entities challenge mankind (communicating through the body's Po) by confusing the human spirit. If given the opportunity, these spiritual entities can possess an individual and become extremely territorial.

2. Ghosts or Gui, as they are commonly called in China, belong to the Yin category of the subtle realm. Ghosts are developed from the subtle form of the combined spiritual essence of an individual's Eternal Soul. When the body dies, the energies of the Corporeal Soul (Po) enter into a state of rest, returning back to the Earth, thus allowing the Ethereal Soul's (Hun) to return back to Heaven. The individual's Eternal Soul then fuses with the energies of the Three Dantians (within the Taiji Pole) and is projected outside the body, entering the tunnel of light to return back to the divine. Sometimes, however, because of unprocessed emotional issues, traumatic death, unfinished business, or extreme attachment to people, places, or possessions, an individual's Eternal Soul can begin to wander the Earth, becoming a Gui or ghost. Generally, it is believed that it takes three days for the Corporeal Soul to withdraw their energy completely from a deceased body. Ghosts are considered Eternal Souls that have departed from human life and are unable to detach from their life experiences; they are bound by their unprocessed issues. Ghosts can also be separated into two divisions of Yang (good) and Yin (evil).
   a. Yang Ghosts are commonly referred to as phantoms and free floaters. These disembodied souls can either be lost, confused, delusional, or purposely return in order to guide and protect the living.
   b. Yin Ghost are commonly referred to as poltergeists, banshees, or other names varying by location. These disembodied souls are angry, malicious, mischievous, and destructive.

It is difficult, if not impossible, to be immune to the influence, or encroachment, of the spiritual world. Spiritual manifestations are usually evident through audible sounds, unusual unexplainable smells, extreme cold, and the displacement of objects. Other phenomena include tactile sensations, visual images, voices, and the apparent psychokinetic movement of objects. Spiritual entities seem to move through solid matter and can appear or disappear abruptly. They can also cast shadows and be reflected in mirrors; some seem corporeal, while others are luminous, transparent, or ill defined. Many spiritual entities have jerky or limited movements, while others are lifelike in movement and speech. Encounters with spiritual entities can be divided into five main categories.

1. Spiritual manifestations of the dead generally occur within a short time after the death of the person. Visits from the departed are usually to bring comfort, to announce their role as a guardian, or to complete unfinished business. If an individual's life ends in an untimely manner, or so violently that the soul does not realize the body is dead, the disembodied soul often goes about its daily routines. Occasionally these souls will manifest as mischievous entities, attempting to get the attention of the living, but they lack the malevolence of an evil poltergeist manifestation.
2. Deathbed phenomena are generally of divine beings, religious figures, or luminous apparitions. Visions of previously deceased loved ones, who come to guide the dying soul into the next level of existence, are common occurrences.
3. Manifestations of impending tragedy are visual images of an entity which usually appears in a "waking vision" or in dreams. When they appear, these spiritual entities either communicate about the death or severe crisis of a loved one, or to give warning of an impending tragedy.
4. Reincarnating spiritual entities sometimes appear in a dream to a member of the family into which they will be born. Such dreams are referred to as "announcing dreams."

5. Manifestations of poltergeists are generally mischievous and often malevolent. They may be either disembodied souls, or demon-like entities (see Chapter 18). These disembodied souls were often extremely dissatisfied and bitter while living, and may be unable to reintegrate into the Earth after death, or to ascend into the Heavens. This may cause spiritual hauntings, either around the location of their death or around a person, or persons, that the disembodied souls blame for their life's misery. They make their presence known by assaulting the living, either human or animal. The most common phenomena include: battering with a rain of small stones or sand, throwing and moving of objects, loud noises and shrieks, strange lights and vile smells.
6. The ghostly images of the astral body can be projected and manifested in distant locations as a disembodied apparition. Sometimes the astral body can travel to other locations and actually appear in holographic-like form to others. This image is not actually considered a ghostly apparition (although it may appear so), but the extension and material form of an individual's Eternal Soul.

   One example of this type of phenomenon was demonstrated in France in 1908 by scholar Hector Durville, who was researching "traveling clairvoyance." In one series of tests, Mr. Durville and a colleague hypnotized a female psychic to facilitate her astral projection to another location. An observer was placed in another part of the house. The experimenter's instructed the female psychic's to touch, hit, or pull at the observer's body while in her astral body. The observer had no idea what to expect, but felt the touches, strikes and pulling on his body by invisible hands. The astral body was even visible as a whitish apparitional figure to some of the people Durville used as witnesses.

EVIL STATES AND MENTAL DELUSIONS

Sometimes the "spirit world" itself can affect the physical body through a subconscious emotional connection with the individual's Shen. These affected subconscious emotions can never be totally repressed because they will continually surface as dreams, visions, flashes of images, etc., and can only be redirected into either positive or negative actions.

Seeing a spiritual entity or ghost is a normal part of Medical Qigong training and is accepted as a natural energetic phenomena; however, disorders such as schizophrenia and psychosis (delusions and hallucinations, etc.) are considered Qi deviations and can be caused by improper Medical Qigong practice. These mental states are known as "evil states" and are difficult to correct. Evil states also include: infatuation, delusions, obsessions, encounters with seductive spirits, demon oppression or possession, and multiple personality disorder. This does not mean, however, that the individuals suffering from these disorders are themselves evil.

INFATUATION WITH THE TREATING DOCTOR

Infatuation is culturally regarded in China as an evil state. This generally refers to the occurrence of deceptions of the subconscious mind during, or after, Medical Qigong healing, which lead to mental derangement. While under the influence of these self-deceptions, patients display intensely amorous affection towards the doctor. As the doctor's energy becomes more intensified within the patients' nervous system, the patients experience a type of biological euphoria which gives way to feelings of unexpressed emotions, suppressed fantasies, and symptoms of eccentric disposition, such as sluggishness, apathy, or elation.

During treatment, patients become extremely open and vulnerable, as their boundary systems completely dissolve under the influence of the doctor's emitted Qi. The Qigong doctor's ability to channel divine light and compassion may easily be mistaken for displays of personal love toward the patients. Sometimes this divine love has never before been experienced by these patients, making them infatuated with the doctor, who is the apparent source of this love. This is an illusion which can usually be dispelled by the doctor's explanation. When the doctor is unable to dispel this illusion by conversing with the patients, this indicates an underlying, often long standing, mental disorder. Such patients should be referred out to a mental health practitioner for professional counseling.

ENCOUNTERS WITH SEDUCTIVE SPIRITS

On rare occasions, individuals who do not have a strong enough connection with the divine may become susceptible to encounters with seductive spirits. These spirits are known as Incubus (male) or Succubus (female), and tend to manifest in dreams. These dreams can range from the romantic and seductive, to rape and sodomy. Although these encounters occur during the individual's sleep, physical sensations are always a large part of the encounter. Often, once the victim has awakened, the physical sensations continue.

DELUSIONS

This is the occurrence of delusions of the subconscious mind during or after Medical Qigong treatment or training, which lead to mental derangement. A delusion is a false belief brought about without appropriate external stimulation (seen most often in psychoses), and is inconsistent with the individual's own knowledge and experience. Patients suffering from delusions display unsociable and eccentric dispositions, sluggishness, apathy, and trance. Some patients may become very disillusioned and depressed. They may lose confidence in life, and think about committing suicide; others may have symptoms similar to those of psychosis, such as persistent visual or auditory hallucinations. These symptoms occur because of preexisting emotional problems, which the patient has not worked through, or has consistently avoided facing.

In all truth, the practice of Medical Qigong does not create these problems; Medical Qigong can, however, occasionally allow patients to become extremely sensitive to the preexisting unresolved problems that continue to surface into their subconscious mind due to their overactive denial system.

SPIRIT DEMONS

An encounter with the phenomenon known as demon oppression or demon possession rarely occurs during clinical practice, but never the less, it must be addressed. Demon oppression or possession describes the state of mind attributed to the patient who has come under the influence of the "spirits of the objective world." These spirits of the objective world (also called "fallen angles," "spiritually hostile forces," or "demons") can either influence, or inhabit, a patient's thoughts and body. They can affect anyone who becomes open to their influence. Any practice or situation which opens the individual's subconscious mind may increase the person's vulnerability to such states. Spirit demon oppression or possession can occur from:

- misguided or improper use of meditations,
- misguided or improper use of hypnosis, or self-hypnosis,
- indulging in the practice of astral projection,
- meditations that cause adverse psychological side-effects,
- general anesthesia,
- drug and alcohol abuse,
- indulging in the practice of channeling, or Ouija board playing,
- deep emotional or physical traumas,
- indulging in the practice of deviant psychosexual encounters (Tantric sex with the wrong individual)
- exposure to places that are haunted by evil spirits when the individual is very stressed out, or deeply fatigued and depleted, and
- indulging in the practice of "black magic."

When the patient's connection to their Shen becomes extremely Deficient, to a point that they surrender their Hun, the patient's Hun may leave their body and wonder, making them vulnerable to the possibility of spirit oppression or possession.

One of the first things a demon seeks, once it enters a body, is to fulfill its sensual appetite (be it sexual pleasures, rage, or emotional addictions, etc.). A disembodied spirit lacks the ability to feel physical sensations due to the disconnection with its bodily senses (touching, feeling , smelling, tasting, etc.). Thus, it can only satisfy these cravings through someone else's living body. Consequently, if a patient is disassociated from the divine center core, or has little or no boundary system, a condition of oppression or spirit possession may occur. In China this condition is commonly described as, "the Spirit (Hun) leaves and the demon enters, uniting with the body's Po" and must be rectified with spiritual atonements and soul retrieval.

Although such encounters in the clinic are rare, it is still important to recognize and treat these conditions when they occur. While treating patients in China, I was fortunate enough to share my experiences with demon oppressed or possessed patients with certain doctors at the Xi Yuan Hospital. It was refreshing to talk with another doctor about this particular subject, as in America it is difficult, if not impossible, to find other individuals who can discuss such a topic in a clinically sound manner.

In understanding the phenomenon of spirit demons, it is important to realize that in the clinics in China, encounters with these types of spirits are divided into two categories: Projected Spirit Demons from the Subconscious Mind, and Actual Encounters with Spirit Demons.

PROJECTED SPIRIT DEMONS FROM THE SUBCONSCIOUS MIND

Sometimes through meditation, the subconscious mind will release visions into the conscious mind in the form of ghosts, phantoms, spirits, demons, etc. These energetic visions are subjective projections of part of the self, released through emotional arousal. Each color image represents certain feelings and repressed memories within the organ which the subconscious mind is trying to communicate to the conscious mind. This also applies to dreams and nightmares in which the patient is continually being haunted by certain spirits, demons, or monsters. For example:

- A green demon represents the deeply suppressed emotions of anger, rage, and irritation which are connected to the Liver.
- A red demon represents the deeply suppressed emotions of excitement, panic, and even anxiety which are connected to the Heart.
- A yellow demon represents the deeply suppressed emotions of worry and pity which are connected to the Spleen.
- A white demon represents the deeply suppressed emotions of sadness, grief, sorrow, guilt, anxiety, distress, and heartache which are connected to the Lungs.
- A black demon represents the deeply suppressed emotions of fear, paranoia, horror, panic, and terror which are connected to the Kidneys.

The patient's subconscious demonic images may tend to be culturally influenced. Each patient may find himself or herself observing something quite different, but with the same underlying emotion. In modern Western culture, individuals are more likely to dream of thugs and assassins that are threatening and pursuing them, as well as monsters.

ACTUAL ENCOUNTERS WITH SPIRIT DEMONS

These spiritual encounters have an objective reality, as they are true spiritual entities which exist outside an individuals thoughts or feelings. For obvious reasons it is extremely important for Medical Qigong doctors to have a strong spiritual foundation. Without a powerful connection to the divine, the doctor risks absorbing the patients' pathogenic Qi, and may become more vulnerable to "evil states" that may place him, or her, at the mercy of spirit demons who seek to dominate, control, and feed off of the negative emotions of the human body.

The spiritual state of the energetic field controls the emotional field, the emotional field in turn controls the mental, and the mental controls the physical field. This is the spiritual template used in the Medical Qigong clinics in China for initiating the energetic laws of dominance and control over the body's tissues. When there is a spiritual interaction involved, the emotions manifest the outcome. There are two ways a spirit demon can attach itself to the body; through spirit oppression, or through spirit possession.

1. Demon or spirit oppressed patients tend to first have had severe emotional trauma, resulting in extremely low self-esteem, depression, fear, rage, and so on (these are the emotional energies on which the evil spirit feeds). The spirit demon becomes attached to the patient's second field of Wei Qi, drawing energy and sustenance from the patient's chronic release of negative emotions.

   These spirit demons are external energy feeders. They are spiritual parasites which provoke and increase negative emotional reactions. Once the patient discharges these negative emotions into their second field of Wei Qi, the spirit demons then ingest and absorb this energy as food. If, for any reason, the spirit demons leave or abandon the patient's second field of Wei Qi, they will, like a predator, continue to look for their next feeding ground. This is why, in certain families, oppressive dynamics are passed from generation to generation, due to certain congenital spiritual patterns.

2. Demon or spirit possession occurs when the patient's Spirit/Mind (i.e., the focused power of their consciousness) becomes too attached to something; it may leave the patient (becoming a wondering spirit) and not return. The vacuum that is left by the original consciousness leaving its residence can become filled by the spirit of other beings. These alien energies tend to enter the patient's body, replacing their original consciousness (Yuan Shen), which is now lost. The resulting state is one of demon or spirit possession. Because the spiritual quality and stability of the patient's mind is lost, the patient will become increasingly dependent on the alien spiritual consciousness for orientation towards others, and the outside environment.

When either a demon or spirit entity possesses a patient's body, it tends to be extremely territorial and protective. This is because, as the demonic spirit surrounds the very core of the patient's energetic body, it initially has a strangle hold on the patient, feeding and distorting the patient's reality. This results in wild mood swings, and sometimes, in displays of extraordinary intuitions, perceptions, and incredible physical powers.

In most cases the spirits causing the pathology are not of a high order of intelligence; they are more on the level of spiritual bacteria, viruses, or parasites. In some cases, however, spirits can be of a high order of demonic intelligence, such as depicted in the movie "The Exorcist."

EXAMPLES FROM PERSONAL CLINICAL EXPERIENCE

Through my personal clinical practice, I have treated several patients who were actually demon possessed, or demon oppressed. One example occurred in 1992, when a patient came to me with a tumor located on her pituitary gland. The Western doctor who was treating her had suggested that she receive immediate surgery, so as a last resort she came to me.

Knowing that she had written several books that were currently being used in a major university as a standard text, I was quite impressed and even intimated by her reputation as an intellectual. She, being the mentor of several of my students who were psychotherapists, did not ease my apprehension. Although she was elderly, she was very strong willed, and quite opinionated. She requested that I lower the treatment table to the floor before starting the therapy. I thought that this was a little strange, but complied never the less, and so we began the initial treatment with the patient lying supine on the table, placed on the floor.

I always begin each treatment with a connection or "hookup" to the divine After connecting with the divine, the energy of the treatment room changes, as the room's energetic field transforms into a divine healing energetic field. Immediately upon "hookup" something in the patient shifted. Although her eyes were closed, the patient began to thrash about on the table like a wild animal, literally snarling, and gnashing her teeth. The power radiating from her body was quite incredible. I knew and believed, that if she wanted to, this elderly, frail woman, could now lift my body up, and toss it across the room like a rag-doll. I was quite aware of the supernatural power and spiritual demonic form that I was now facing, and knew that my 27 years of martial arts training would not serve me in this situation. To my advantage, I had previous exposure to such spiritual demonic phenomena, and had been successful in dealing with demon possessed individuals. Believing that the current healing work was part of my ministry and life purpose, and having participated in several demonic exorcisms, I was aware of the procedure which needed to transpire.

I began dredging and casting out the demons


Evil Essence
Devils, Demons,
Spirits of Darkness
Divine Essence
Angels, Guides,
Spirits or Light
False Self
Masks and Defense Mechanisms
True Self
Core Self
Personal Subconscious Mind
(filters information in accordance with prior experiences and belief structure)
Creative Subconcsious Mind
(intregrates new knowledge, shifting and changing old belief structure, shedding new light on past expieriences)
Conscious Mind
Perceives,
Adds
Intention and Will
Reacts,
Engages the Denial System
Acts,
Analyzes new information and takes action

Figure 19.2. All human beings are subject to divine and evil spiritual influences. These influences can affect the subconscious and conscious mind, as well as the sensory perceptions and physical performance.

one by one, claiming each portion of her body for the glory of Christ (my divine authority). This procedure continued for six weeks, each treatment involved reclaiming certain areas of her body. Beginning at her head, I continued treatment down the patient's body. On the sixth week, when I reached her Lower Dantian, the last spirit demon left her body, and she immediately curled up into a fetal position and began to cry. Her Hun then returned to her body, and for the first time in many years she could feel loving emotions again.

It is important to note, that while the treatments were being administered, the patient was not consciously aware that anything out of the ordinary was happening. She had been so completely detached from her body, that she had no conscious recollection of her own emotional-spiritual field of existence, or its affect on her physical body. She had literally hid within the confines of her intellect, where she felt safe. She was also not aware of being demon possessed, or even that her body thrashed about during each treatment. In effect, she had disassociated from her Yuan Shen during childhood, and thus became dissociated from her emotions. After six weeks of treatment her brain tumor had completely dissolved. But, far more remarkable, was the change in her personality, for she became both friendly and courteous.

OVERVIEW

As mentioned before, once the Qigong doctors' Shen has reached a high state of sensitivity, they are able to transcend their conscious perceptions to sense, observe, and communicate with the spiritual world (Figure 19.2). This ability to see disembodied spirits or ghosts is a normal part of Medical Qigong training and a natural part of energy observation.

These spiritual presences can be seen or felt for either brief moments in time (usually as a hovering image of light, or a dark shadow), or for extended periods of time (usually an encounter). Some of these spiritual entities can also take the form of animals.

Some doctors view these energetic entities as either individuals who are astral-projecting (from the past, present, or future), or forms of energy that can either be ascended spirits of light (divine guides or angels), or fallen spirits of light (demons and hostile forces). In any case, encounters with such entities of the spiritual world should not startle or scare the Qigong doctor, but be expected as a part of the existence of the spiritual domain.

A final important note to make is that, although demon possession is real, the location, or type of the patient's disease, has nothing to do with demonic possession. Demonic possession is related to the disassociation from the Yuan Shen and the absence, or suppression, of the patient's Hun. It is not caused by obstructed tissue formations or physical disease.

After helping the patient uncover any severe emotional trauma, the Qigong doctor should assist the patient in "soul retrieval" meditations, in order to return the patient's Hun back into its residence (the patient's physical body) and to facilitate a strong reconnection to the Yuan Shen. During soul retrieval meditations, patients sometimes talk about viewing certain traumas from different visual perspectives, such as: watching the incident from above their body, or watching from a different corner of the room. The reason for this change in visual perspective is due to the displacement of the patient's Hun once it leaves the body. Although the Hun are outside the body, they still observe, listen, and record. This accounts also for the numerous cases of astral projection during surgery, as well as during near death experiences. Under anesthesia, many patients travel out-of-body and observe in fine detail what the doctors and nurses are saying and doing. They accurately recall the doctors' and nurses' conversations, and the experience of viewing the operation from above the body. These experiences are becoming more documented in recent years partly due to modern techniques in resuscitation, that have made such experiences more frequent. First hand accounts of out-of-body experiences abound in "near death experience" literature.

Similar experiences have been recounted by many physically and sexually abused patients, who, as children, learned to dissociate from the body, and observe the abuse from the ceiling, or corner of the room. In most cases, these adults, and children, do not suffer from multiple personality disorder. Only in the most severe cases does the personality fracture and become multiple.

MULTIPLE PERSONALITY DISORDER (DISSOCIATIVE IDENTITY DISORDER)

Occasionally the Qigong doctor may encounter a patient with a multiple personality disorder. The condition of a multiple personality disorder is generally due to extreme sexual, physical, and emotional abuse during childhood; in some cases, demon possession may also occur. This is a condition in which the patient has developed a split in their consciousness, resulting in the development of two or more distinct identities or personalities that recurrently take control of the patient's behavior and consciousness, one at a time.

It is believed that the original personality splinters during childhood (usually around the age of 6 or 7 years, or as early as 3) creating several different personalties, or personality states, that are disassociated from the patient's original whole personality. The different personalities created can number as few as two, or upwards of one hundred. They are often referred to as alternate identities or simply 'alters.' These alters, in fact, often themselves give birth to more fractured alters, each with its own gender, age (corresponding to the fracturing trauma) and function (or role). Some alters may be very aggressive and protective, others will be more passive and submissive.

Some alters will have different medical conditions from the others, which inhabit the same body. As the patient changes personalities (alters), the internal and external energetic fields likewise undergo changes. Each personality can differ in age and stage of development. In most cases, the personalities are usually unaware of the words, actions, and feelings of the other personalities, especially at the beginning of the treatment. Each personality can exhibit a different set of symptoms, as well as diseases. One personality may have chronic asthma and allergies, but when switching to another personality, the patient may suddenly display healthy lungs but display nearsightedness or high blood pressure.

Usually one personality becomes a helper to the doctor, while another personality may be psychotic, indifferent, and so on. Some of the alters may have access to highly advanced transpersonal states of consciousness, i.e., a finely honed and active psychic realm which may have provided a haven, or sanctuary during the abuse.

TYPES OF ALTERS

Over time, an alter's role in the patient's personality changes. There is a difference between an established personality which maintains both an internal and external role and just a fragment personality (e.g., washes the dishes only). Also, there will usually be a number of child personalities included, as well as adult personalities. The patient's past history of violence is the best indicator of whether there are dangerous alters. Some of the most prevalent personality types of alters are described as follows.

1. The first personality encountered by the doctor, or psychologist, is usually the patient's host personality, not the patient's original personality.
2. The demonic or spiritual personality type is generally found in very religiously oriented patients.
3. The persecutor personality type is generally responsible for the patient's attempts at self mutilation (a very common type syndrome with multiple personality disorder) or suicide. They tend to be children or teenagers. It is believed that these types of personalities are either interjections of the patient's original abuser, or have evolved from "helper" personalities.
4. The helper personality type is generally responsible for providing the patient with the emotional support to counteract some of the self-destructive behavior of the patient's persecutors.
5. The administrator or obsessive-compulsive personality type is often responsible for allowing the patient to earn a living. They generally appear cold and aloof.
6. The imitator, or impostor, personality type generally mimics other personalities and is responsible for handling certain situations that are difficult for the patient to bear.
7. The autistic or handicapped personality type generally emerges when the patient feels that he or she is under intense scrutiny, or feels that he or she is being controlled or confined. They may manifest autistic or catatonic states or become functionally deaf or blind.
8. The promiscuous personality type is generally responsible for the patient's overactive or uncontrollable sexual urges (e.g., nymphomania).

While treating patients with multiple personality disorder, the therapeutic goal is usually to integrate all the different personalities, merging them together through creative visualization (usually using hypnosis). This is achieved by having the patient imagine each personality and subset "alters" merge into one.

Some patients, however, opt to remain multiple, as merging incurs the "death" of others. In such cases, contracts are made with the different alters to keep each other informed of events occurring during their "coming out," and some of the more responsible personalities keep watch over the more self-destructive ones. Due to the complexity of treating multiple personality disorder, and due to the high potential of suicide in multiple personality cases, it is recommended that the Qigong doctor refer these type of patients out to specialists who are familiar with such conditions and their recovery.

SOUL RETRIEVAL AND MEDICAL QIGONG THERAPY

According to the Medical Qigong perspective, one of the major causes of illness is "soul loss" (the loss of parts or memories of the Eternal Soul). On the spiritual plain, the Eternal Soul is the manifestation and sum total of our energetic associations and the energy of the Wu Jing Shen (see

Chapter 2). The Eternal Soul serves as a middle point between the source and organization of all life-force energy. The Eternal Soul is considered the seat of all emotions, feelings, and sentiments. As a crystal grows around a central matrix, so the body grows around the Eternal Soul. In revue, the Eternal Soul radiates energy in all directions, like the sun, and is responsible for life, health, and the formation and growth of the body. In the scope of energetic manifestations, the Eternal Soul expresses its innate qualities as energetic movement, functioning through the physical form (led by the Shen). It is connected to all parts of the body, and its light or energy is reflected through the eyes via the Hun. It is through the influence of the Eternal Soul that all of the body's energetic processes (organs and organ systems) seek wholeness. It knows exactly what is needed in every situation for survival and health preservation, and takes action via the Po. Whole body consciousness is the main characteristic of the Eternal Soul. Without the process of the Eternal Soul, energy would have no specific direction and remain in meaningless activity.

"Soul loss" is not demon possession, but a spiritual illness that causes emotional, mental, and physical disease. When disturbed, the Hun leave the body and the Mind (Shen) wanders off on its own. When the Hun leave and the Shen wanders off for very short periods of time, it is sometimes called, "dissociating" or "spacing out." When the Hun leave for extended periods of time, it is called soul or spirit travel, which generally happens when the patient is asleep. It is believed that if the Hun completely vacate the body, the patient will die. A coma is one example of a chronic physical state where the Hun have left, but are still attached to the body, through the Hun's connection with the patient's energetic Qi field. When a patient is in a coma, the Hun and Shen abandon their residence, wandering about in the astral plane of existence.

The Hun and Po create the sustaining energy for the Wu Jing Shen, which provides the energy for the Yuan Shen. If the Qigong doctor can retrieve the lost parts of the patient's Eternal Soul (the suppressed memories attached to the Hun and Po), then the individual's Shen can be restored back to harmony and health.

REASONS THE ETHEREAL SOUL LEAVES THE BODY

In ancient times, disease was attributed to the Hun having strayed away, or having been stolen. It was believed that the Hun would leave the body through three main incidents: they could be stolen (through deep infatuation), frightened away, or simply wander off. In addition to soul theft or "rape of the soul," some Qigong doctors relate Hun loss to the interference of Gui (ghosts, demon spirits), as well as other human beings (i.e., a broken heart or severe trauma).

Soul retrieval is an essential part of Medical Qigong therapy; the body and mind without the Hun, or the spiritual connection of the Yuan Shen, remain in a suspended state of spiritual and emotional shock. When the spiritual needs of the Eternal Soul are neglected, the Shen begins to disassociate, and symptoms of addiction to drugs or alcohol, obsessions, violence, or deep depression take over (see Chapter 32).

Because we are born understanding hidden spiritual realities, patients will inevitably succumb to various mood swings; these are due to deep emotional pain and experiences that stay within their memory and touch their Heart. A spiritual life of some kind is absolutely essential for psychological health. Traditionally, the Hun are said to suspend themselves midway between the conscious and the unconscious, and that their perceptual modality is neither the mind's nor the body's, but the imagination's (i.e., the Creative Subconscious).

From a clinical perspective it has been noted that the Hun leave the body during severe emotional traumas (i.e., surgery, the death of a loved one, miscarriages, abortions, incest, molestations, physical and emotional abuse, the end of a deep relationship, and the stress of combat). Whenever we experience trauma, our Hun, which are part of our vital spiritual essence, separates from us to survive the experience and to escape the full impact of the pain (Figure 19.3). When patients be-


Gui
(ghosts, demon spirits)
Humans
(a broken heart, the end of a relationship, the death of a loved one)
Severe Trauma
(surgery, miscarriages, abortions,incest, molestations, physical abuse, emotional abuse, the stress of combat, etc.)
Soul
Stolen
Frightened Away
Wander Off

Figure 19.3. Reasons for the Ethereal Soul Leaving the Body

come dissociated, aspects of their personality separate from the mainstream of their consciousness, resulting in gaps of memory loss. An extreme example of personality separation occurs in multiple personality disorder.

When a patient has been violated or wounded in some way and remains in an emotionally present state of mind, within the body, the result usually encompasses feelings of anger from past hurts, grief from present pain, or fear of future harm. If an over-stimulation of the energetic organs occurs, it may wound the patient's Shen, causing the patient to close off from the Yuan Shen, to shut off all emotions. This action is similar to that of a sea-anemone, whose natural response (for the purpose of survival) is to immediately close itself after being touched.

THE PURPOSE OF SOUL RETRIEVAL

The purpose of Medical Qigong soul retrieval therapy (called age regression therapy in Western psychology) is to bring the awareness of emotions back into areas of the physical body, allowing the patient to express and release the feelings and reactions that are the cause and symptoms of his or her disease. This will help the patient transform the trapped, or frozen energy (stagnated Qi), back into its energetic potential to be reintegrated with the Shen.

A Qigong doctor will accompany and tend to the patient's Eternal Soul in times of emotional transformation, including times of crisis, illness, and emotional death and rebirth. This allows the patient to remain in the energetic present time mode. This also results in the relief from symptoms of illness and the return of the patient's personal power, creating the potential for fulfillment in work and rewarding relationships. Some patients may come to the realization that they must quit their job and find another that is more spiritually rewarding. They may also find themselves discarding old friendships and making new ones, as their energetic, emotional, and spiritual fields undergo growth and change.

WOUNDING AND CLOSING THE SPIRIT

The body's Yuan Shen is the main expression of the Eternal Soul as it moves from its inactive state to a state of dynamic activity. The Yuan Shen is the medium or active environment of the Eternal Soul. The Yuan Shen also expresses its energetic influence through a continual interchange between the personal-self and the higher-self through the act of breathing. The Eternal Soul expresses itself specifically through the Yuan Shen, and the Yuan Shen manifests itself through the physical body.

If a person's Yuan Shen becomes wounded (feels attacked, violated, taken for granted, etc.), it begins to close itself off from its environment. When the Yuan Shen "closes", the emotions begin to shut down, and the Hun wander. Depending upon the patient's set patterns, this entire process can occur within seconds. Once the Hun wander, the acquired (analytical) Zhi Shen and surviving Seven Corporeal Souls (Po) take over the body, and the patient responds like a machine (i.e., the patient can still think and function; reflexes remain intact, but he or she is void of interpersonal feelings). Patients whose Shen have closed down cannot make emotional attachments, and live in a state of perpetual hunger. These patients go through three stages of isolation before their spirit leaves.

1. The first stage involves anger and grief.

   Once a patient has been hurt (before his or her spirit begins to close), his or her natural survival energy immediately affects the Liver and Lungs, causing emotional reactions that are a natural response to feeling attacked. Hurt, sadness and anger are natural responses to feelings of rejection, betrayal and abandonment. These emotions reflect a spiritual, emotional and mental protest to feeling insignificant, excluded, and dis-empowered.

   a. The patient's congenital emotions of kindness and compassion, stored within their Liver, instantaneously shut down as the Liver Qi expands violently outward. This energetic reaction gives way to releasing the patient's acquired feelings of anger and rage, stored within the Liver. The energy of anger and rage is projected outward to protect the patient's emotional boundaries. If the patient has deep seated emotional problems, however, the energy can also implode inward creating self-hate.
   b. If this protective emotional reaction is not effective in obtaining the needed results (being heard, honored, valued, etc.), the patient's energetic field rebounds inward affecting the Lungs. Once the congenital emotions of integrity and dignity stored within the patient's Lungs become effected, the Lung Qi becomes obstructed, and the acquired emotions of grief and sorrow are released. The energy of grief and sorrow is encapsulated internally to encase the patient's wounded spirit.

2. During the second stage anger and grief transform into depression and despair.

   As the patient begins to lose hope, the Shen begins to close, causing two reactions.

   a. The patient's Liver Qi becomes obstructed and stagnant. This in turn transforms the emotion of anger into depression;
   b. At the same time the patient's Lung Qi transforms grief into despair.

   The patient slowly begins to feel helpless, hopeless, and empty inside. Because of the increased depression and despair, the patient becomes physically, mentally, emotionally, energetically and spiritually tired, and gives in to feelings of insignificance, unfulfillment and loss of control over his or her life.

3. During the third stage depression and despair transform into indifference and detachment.

   In the final stage, the patient has lost all hope of resolution and gives up entirely. The Shen closes down, and the Hun wander. The patient feels emotionally detached from people, the surrounding environment, and his or herself. The patient wanders around "dead to the world," isolated, internally unfilled, and alone. This creates what is known as a "depersonalization disorder."

   A depersonalization disorder involves the persistent, recurring episodes of depersonalization, characterized by a feeling of detachment, or estrangement from one's self. The individual may feel as if he, or she, is living in a dream, or movie, and responds to life like

Three Stages of Emotional Transitions before the Spirit Closes


Stage #1
Stage #2
Stage #3
Liver
(Qi expands outward, rising upwards)
Anger
Depression
Heart
becomes hurt
Disassociation
(Indifferent, withdrawn, antisocial)
Lungs
(Qi withdraws inward, becomes obstructed)
Grief
Despair

Figure 19.4. There are three stages of emotional transition the patient must experience before their Shen closes and their denial system engages. After these stages are experienced the patient's defense mechanisms take over.

a robot. They may also have the sensation of being an outside observer (to their mental processes, body, or specific parts of the body). This feeling is often accompanied by sensory anesthesia, a lack of affective response, and a feeling of lack of control over their actions (including speech).

Voluntary induced expressions of depersonalization or derealization that are meditative, or cultural trance practices, should not be confused with this involuntary disorder. It is believed that approximately 50% of the population may experiences a single, brief episode of depersonalization, usually precipitated by severe stress. Approximately one-third of individuals exposed to life-threatening danger incur a brief episode of depersonalization. Depersonalization episodes may be accompanied by visual distortions, such as the shape or size of objects, and other people may appear unfamiliar or mechanical. Other common associated features include: anxiety or depressive symptoms, obsessions, somatic concerns, and time distortion. Depersonalization and derealization are some of the symptoms of panic disorders (not due to drugs or medication), which are usually caused by long-standing anxiety and stress. Panic disorder can also be brought on by emphysema and asthma due to the difficulty in breathing.

When the Eternal Soul becomes wounded, the first two stages in closing down the Yuan Shen are caused by the patient trying to repress feelings of anger (stored within the Liver), and sadness and grief (stored within the Lungs). This reaction is incurred because the Liver stores the body's Three Ethereal Souls (Hun), while the Lungs store the body's Seven Corporeal Souls (Po). These two emotions are expressions of the patient's natural protest against the lack of love that their Yuan Shen (which encompasses or contains both the Hun and Po) is experiencing (Figure 19.4).

HEALING THE SPIRIT

The first stage of healing in soul retrieval is to open the patient's Yuan Shen by giving them hope and encouragement. Hope helps the patient's perspective to be positive and restores meaning to life. Once the patient has closed his or her Yuan Shen, it cannot be opened through argument or logic. Instead the Qigong doctor must use a gentle, soft tone of voice expressing compassion and high regard for the patient. The patient must feel honored and valued by the doctor to feel safe enough to release the hurtful and negative emotions.

Praise must be used carefully and gradually, since some patients may be as yet, unable to accept a higher concept of themselves. Too much praise may cause the patient to feel "mocked" or "lied to", given his or her very low self-esteem. This type of healing only happens when the patient's spirit is engaged, stimulating the inner emotions and not just the intellect.

Once the patient's Yuan Shen begins to open, it is important for the doctor to increase the patient's hope for interpersonal relationships. This is initiated by using silent mental affirmation, or prescribing positive affirmations in conjunction with vivid visualizations. The patient's imagination can reengage his or her feelings and return them to the body's organs and tissues. Instilling hope and giving encouragement allows the doctor's influence on the patient to be increased.

As the patient's Shen begins to open, it is important for the Qigong doctor to take the time to energetically and emotionally travel with the patient back into the memories of the past, to encounter the precise moment in which the patient's Hun left the body. The choice to return the emotional spirit back into the body must come from the patient's desire to retrieve his or her original feelings, no matter how painful the process. The patient must be ready to reexperience and release these feelings. It is important that the patient's "adult observer" be present in retrieving these painful memories. The "adult observer" refers to the patient's ability to suspend his or her judgemental attitude towards his or herself, and to observe the events that are being released with compassion (i.e., as if they were happening to a friend to whom loving support can be given). This allows the patient to experience true healing with the help of a compassionate companion (his or herself).

Tears often come as the memory of the original trauma releases from the patient's body or flows back into the Mind. Many patients notice that after these experiences their dreams change significantly, becoming more vivid. Also, their life environment as well as their relationships tend to change drastically.

EMOTIONAL REBIRTHING PATTERNS

Often, when patients experience deep emotional and spiritual traumas, they also experience physical sensations which reflect the trauma of their biological birth. These psychophysical sensations are due to the physical, energetic, and spiritual connection each individual has with the maternal host while inside the womb. Although these experiences are natural, they can sometimes be disturbing and even frightening to patients unfamiliar with deep emotional and spiritual transitions. The following are but a few examples of physical rebirthing patterns, and the emotional reactions related to these types of spiritual transformations.

- In patients born with the umbilical cord wrapped around their neck, each time they experience deep emotional and spiritual changes it will feel as if they are being strangled.
- In patients born through C-section, each time they experience deep emotional and spiritual changes it will feel as if they are being torn asunder.
- In patients born through the natural birth cannel, each time they experience deep emotional and spiritual changes it will feel as if they are falling through space with nothing to support them.
- In patients born breech, each time they experience deep emotional and spiritual changes it will feel as if they are being crushed in by all sides and suffocated.
- In patients with mothers who were heavily sedated, each time they experience deep emotional and spiritual change they will feel mentally disoriented and unstable.

SOUL RETRIEVAL MEDITATION

The following comes from my clinical experiences in dealing with patients who are very eager to heal, but reluctant, or unable to tolerate rapid change within themselves. The patients' family dynamics, as well as the quality of traumatic and nourishing experiences they received while growing up, play an important role in shaping their individual personalities. It is an accepted fact within modern psychology that an individual's present emotional life is shaped by the events occurring in the "formative" years (especially the years before the individual can articulate their thoughts and feelings). These experiences sink deep into the individual's psyche, hidden from consciousness through repression and denial. This repression is generally due to the inability to understand and express in words the traumas they suffered.

This particular Shengong (which literally means working with spirit) technique involves creative visualization (in a very relaxed, quiescent state of mind), and is used to gain access to the patient's unconscious past emotional experiences. The goal of this meditation is to allow the patient to free him or herself from the repressed emotional material which systematically surfaces during daily life. These programed emotional responses systematically affect the patient's behavior, causing neurotic symptoms, slips of the tongue, associated dreams, and fantasies.

Many patients believe they are ready for this experience, but in reality they are not yet able to deal with such intense pain. These patients are likely to unconsciously choose the least painful memories in order to test how the doctor will handle their feelings, or fail in the attempt to retrieve the lost parts of the soul. Gradually, as trust grows, these patients will be able to access more painful and relevant memories (this is similar to peeling an onion layer by layer). Sometimes patients try very hard to access the memories and obtain nothing, or very little information, leaving them feeling frustrated. This frustration must then be processed and resolved.

The doctor must instill hope and dispel this frustration by explaining to the patients that they have made an important step forward by seeding the unconscious mind with the request, or concept, that past memories must be recalled. In time, this seed will sprout and give forth results. It just needs a little time to incubate. It is extremely important that the doctor never show disappointment or take away the patients' hope.

In such cases, the patient must be reassured that their higher-self (the observer self) senses that the timing is not right. There may be current issues or events, that must first be worked through for a successful soul retrieval to take place. To have done so now would have resulted in more trauma, or more precisely, re-traumatization. They may need to strengthened and develop more self-trust before trying again. Counseling may be recommended, and in time they will succeed.

Some patients may need several sessions before feeling comfortable enough with just entering and surfacing from trance states, before undergoing soul retrieval. It may be necessary to first retrieve pleasant memories that build self-trust and self-confidence before re-attempting soul retrieval (i.e., learning to fly a kite, etc.).

The Qigong doctor should have some training in hypnosis and hypnotic trances before giving this type of trance inducing meditation to their patients. The doctor should know what to do and be able to identify whether or not the patient is able to connect with their Yuan Shen or "higher self." As the doctor induces trance in the patient through this meditation, the following changes in the patient may be noted:

- a change of color in the complexion,
- a relaxation of the facial muscles,
- a change in breathing patterns, and
- sporadic eye movement (behind closed eyes).

If none of the above signs are noted, the patient may need more time to relax deeply before continuing with the meditation. Suggestions of imagining and feeling the body's tissues melting into the Earth may be given, along with suggestions of taking deep relaxing breaths to calm the patient's Shen.

While performing this meditation the patient may experience all the sensory, emotional, and physical sensations of these repressed memories, causing specific core memories (that have been repressed from infancy and childhood) to be brought to the surface and relived. As the patient experiences these memories, his or her facial expressions and demeanor, will often change, regressing to reveal the appropriate age and period of time during which the original trauma occurred.

This particular method of soul retrieval is divided into two stages. The first stage involves locating the body's three storage chambers of past, present, and future emotions. The second stage focuses on accessing the location of, and coming in contact with, the patient's unconscious repressed emotional traumas.

This meditation must first be understood in depth before it is given to the patient. It is very complex, and is not meant to be simply read through to the patient. Also, the doctor should set aside sufficient time to process what the patient experienced after ending the meditation.

STAGE 1. ACCESSING THE ENERGETIC CHAMBERS

The purpose of this meditation is to locate the patient's three storage chambers which access his or her past, present, and future emotions. This meditation also allows the patient to acquire a starting point, or outlet, for removing these painful experiences.

In this meditation, the patient first concentrates on feeling his or her entire body. Begin by having the patient sit comfortably in a chair, both feet on the floor, hands resting on the thighs, eyes closed, tongue on the upper pallet, and breathing naturally through the Lower Dantian. It is important that the patient relax, feel, and experience the body completely. The patient should also be encouraged to accept and feel everything as one unit, to connect with the Yuan Shen or "higher self."

The Storage Chamber of Past Emotional Memories

In order to find the chamber of past emotional feelings, the patient begins to focus attention on remembering and feeling a painful childhood experience. Once the patient has retrieved the memory and is experiencing the painful trauma, he or she points to the tissue area of the body where the feelings are located. This area is considered to be the current storage chamber, where the patient stores the energy of past emotional memories.

The storage areas change over a period of time, given the fact that the patient continues to process emotions throughout life. Each emotional healing causes the previous energetic holding pattern to die, and a new pattern is to be born within the patient's energetic structure. The chamber of the patient's past usually coincides with a tissue area where the patient is already experiencing disease or discomfort.

The Storage Chamber of Present Emotional States

In order to find the chamber of the present emotional states, the patient focuses attention on feeling the doctor's voice within his or her body. As the doctor continues to speak, the patient feels where the sounds are resonating. Once the patient experiences and locates this tissue resonation, he or she points to that area. This area is considered to be the current storage chamber, where the patient stores the energy of present emotional states.

The Storage Chamber of Future Emotions

To find the chamber of future emotional states, the patient focuses on a specific project that he, or she, is planning to do in the near future. Once the patient experiences slight physical sensations, he or she points to the area where the feelings are located. This area is considered to be the current storage chamber, where the patient stores the energy for future endeavors and future expectations. The patient's current ambitions may change as the patient begins to heal from past emotional wounds and makes life-style changes.

STAGE 2. RETRIEVING THE LOST MEMORIES

The final part of this meditation explores the patient's unconscious feelings and reprograms the destructive subconscious patterning. It is used to access the repressed memories stored within the patient's individual Personal Subconscious, which is hidden from through their denial or defense mechanisms. Sometimes after practicing this meditation, patients will not only gain access to the repressed memories of their infancy and childhood, but will also connect to their life within the womb, as well as their birth-process.

1. Begin by having the patient sit comfortably in a chair, both feet should be placed on the floor, hands resting on the thighs, eyes closed,

tongue on the upper pallet, anal sphincter lightly closed. The patient should breathe naturally, expanding the Lower Dantian with each inhalation, contracting the abdomen with each exhalation.

2. The patient focuses attention on the area of the body where the energy of the past emotions is stored. The doctor directs the patient to imagine opening the chamber of the past emotions, allowing the energy, like steam, to release itself from this area. This steam is gathered to the left side of the body. Once all of the energy has been released, it begins to form into a cocoon shaped cylinder of past emotional memories.
3. Next, the patient focuses attention on the area in the body that stores the energy of the present emotions. The patient imagines releasing this energy from out of the body like steam, creating a second cocoon shaped cylinder. The patient places this second cocoon in front of the body, next to the first cylinder.
4. The patient then focuses attention on the area in the body that stores the energy of future emotions. The patient imagines releasing this energy from out of the body like steam, forming a third cocoon shaped cylinder. The patient places this third cocoon to the right side of the body, next to the second cylinder.
5. Next, the patient imagines that all three separate energetic cocoons are joined together. The energetic cocoons are to be connected end to end, in a straight line, with the past on the left, the present in the middle, and the future on the right side of the patient's body.
6. The patient then focuses attention on his or her Taiji Pole, imagining the energy of the Upper Dantian descending and combining with the energy of the Middle Dantian (where the Eternal Soul is stored). Next, the patient imagines the collected energies of the Upper Dantian, Middle Dantian, and his or her Eternal Soul, descending and combining with the energy of the Lower Dantian. The patient uses the collected energies of the Three Dantians to create an "energy bubble" within the Lower Dantian to surround the Eternal Soul. While focusing on the center of the energy bubble, the patient imagines the Eternal Soul transforming into a small energetic form of his or herself.
7. Encapsulated within the energetic bubble, the small energetic form of the patient's self manifests within the physical body. The patient's Eternal Soul, now in small energetic form, begins slowly ascending the Taiji Pole, leaving the body through the Baihui GV-20 point. As the patient's Eternal Soul leaves, it is still connected to the physical body through a silver energetic cord.
8. The patient's Eternal Soul floats over the three energetic cocoons, hovering over the cocoon shaped cylinder on the left side of the body (to access the past emotional memories). Next, the patient observes the black, oval shaped cylinders, imbedded within the structures of the energetic cocoon of past emotional memories. These dark cylinders are energetic emotional clusters. They contain the memories of hurtful feelings and specific times in the life of the patient when he or she felt humiliation, degradation, shame, rejection, or emotional deprivation.
9. The patient descends into the energetic cocoon of past memories and allows the Eternal Soul to find the particular cylinder which currently needs addressing. In choosing a specific area to work on, the patient's Yuan Shen automatically selects the most relevant material from the patient's unconsciousness.
10. The patient then removes his or her Eternal Soul from the energetic cocoon, bringing with it a specific dark cylinder. The cylinder is removed from its webbing within the walls of the energetic cocoon and placed in front of the hovering soul. The cylinder is still connected to the energetic cocoon through an attached energetic cord. Through vivid concentration the patient focuses on the color of the cylinder emitting light from the Yin Tang (Third Eye) point of the little energetic self. This projected light pulsates and changes the dark cylinder, from black to white. As the cylinder pulsates and changes its color, it begins

to open and reveal the lost memories and unresolved feelings. These memories of emotional traumas are brought to the surface. Some of these experiences may be memories of events where the survival or integrity of the patient's physical body was threatened.

11. Next, the patient connects with the divine (God or "higher power") and begins the process of feeling, expressing, understanding, forgiving, and letting go of the emotional charge attached to the memories. This process of emotional purging is connected to the emotions stored within the patient's Five Yin Organs, and are expressed through the following stages:
    a. Anger, blame, and resentment are stored in the patient's Liver.
    b. Hurt, pain, sadness, and disappointments are stored in the patient's Lungs.
    c. Fear and insecurity are stored in the patient's Kidneys.
    d. Remorse, regret, and responsibility for keeping the painful memories and feelings alive are stored in the patients's Spleen.
    e. Love, understanding, and forgiveness are stored in the patient's Heart.
12. As the emotions begin to release themselves from the energetic cylinder, the energetic debris transforms into a vaporous cloud. After understanding and resolving the emotions contained within the energetic cloud, the patient divides the released energy into either a receiving or discharging cloud of energy.
13. At this point, the patient focuses on the energetic cloud and begins separating the pain and hurtful memories from the knowledge and wisdom gathered from the experience.
    a. First, the patient places those memories gathered from the knowledge and wisdom of the experience on the right side of the room, imagining them as sparkling gold, silver, and white light energy.
    b. Second, the patient places those memories gathered from the pain and hurt of the experience on the left side of the room, imagining them as thick, dark, black energy.
14. The patient focuses on the right side of the room, imagining this energy as bright, pure, and illuminating. The patient then inhales, absorbing the knowledge and wisdom gathered from the past experience into his or her small energetic body. Since this is actually the energy of the patient's soul, the patient's body immediately feels the emotion, energy and spirit becoming empowered, as it can now review these past experiences without the feelings of hurt, pain, and judgment.
15. Next the patient focuses on the left side of the room where the feelings of hurt and pain are stored. The patient imagines this hurt and painful energy as a dark, turbid cloud. Because the cylinder has a direct life line connected to the patient's past, the energetic cord attached from the cylinder to the energetic cocoon must be severed. Once the cord connecting the cylinder to the patient's past is severed, the patient is then truly released from the spiritual and energetic connection of the memory. This is initiated by imagining an angelic being, with the "sword of truth," severing the energetic life line connected to the patient's cylinder. The sword of truth represents the patient's decision to regain his or her power by deciding to no longer suppress and carry the painful memories. Once the energetic cord is severed, it causes the cylinder to vaporize, forming an energetic cloud. The patient then imagines severing any last connection or attachment to these toxic emotions, and releases this cloud of hurt and pain, visualizing it floating up out of the room, through the ceiling, out into space.
16. The patient then imagines that God (the patient's divine healing power) is seated in the Heavens, with ripples and pulsations of love and mercy emanating from the center of this divine presence. The patient visualizes one of these waves of love and mercy form the divine descending towards the Earth. As the wave of love and mercy touches the as-

cending dark cloud of hurt and pain, it immediately explodes and destroys the dark cloud. The moment that this dark cloud explodes, the patient sees the cloud's negative energy transforming into blue crystal drops of divine healing energy.

17. Next, the patient visualizes these bright, fluorescent blue, drops of pure, clean energy descending from the heavens and pouring down like rain on his or her small energetic self, saturating it completely. This energy immediately transfers into the patient's physical body. The patient inhales and absorbs this energy flowing into every tissue of the body, allowing the divine healing light to penetrate and radiate throughout his or her entire being.
18. Next, the patient observes the changes created within the three energetic cocoons. The energy in each cocoon will have shifted slightly, revealing an energetic alteration of the patient's present state of mind, and a change in the patient's future. By transforming the past, the patient has altered the present and initiated a change in the future course of events.
19. Finally, the patient returns his or her energetic bubble (containing the small energetic self) back down through the Baihui point into the Taiji Pole, drawing the energy back into the Lower Dantian. From the Lower Dantian the patient's soul energy will return back into the Middle and Upper Dantians, as well as the surrounding tissues. Finally, the patient reabsorbs the energetic cocoons back into the body, and returns to a quiescent meditation.

THE DOOR TO THE CHAMBER OF MEMORIES

A simple visual meditation can also be used to access the patient's suppressed past memories. This exercise is a form of guided meditation, in which the doctor leads the patient into the imagined hidden parts of his or her own soul.

Begin by having the patient lie supine. Ask the patient to close the eyes and imagine walking down a flight of stairs. Lead the patient through three separate doors, descending three separate staircases (this is performed in order to arrive at the patient's "chamber of memories").

After entering through the last door, the patient descends one final staircase until he or she reaches the chamber of memories. This is where all of the memories of the patient's past traumas have been kept, hidden deep within the subconscious mind.

Inside the Chamber of Memories, the patient discovers dark cylinders of past emotional pain. Each cylinder represents a specific trauma experienced and stored within the patient's energetic field. The patient then makes a decision to heal and free the body of the enormous energetic field used to suppress certain memories. To heal and dissolve the energetic cyst, the patient follows the same process of eliminating past memories (repeating section 8 through 15 from the previous meditation).

Once this process is completed, the Qigong doctor guides the patient back up the flight of stairs, through the three doors, and back to consciousness. Because these meditations have a profound affect on the patient's constitution (affecting their physical, mental, emotional, energetic, and spiritual nature) it is important for the patient to be referred to a psychotherapist while undergoing this type of Qigong therapy to further facilitate the patient's healing transformation.

FINDING THE LIFE PURPOSE

Another aspect of Soul Retrieval consists of an exercise that assists the patient in finding his or her purpose in life. Finding the purpose of the patient's life encourages interpersonal healing, and fills the empty space deep within the patient's heart. This in turn increases the healing potential by providing the patient with hope.

1. The first step is to ask patients to write down on paper what is was they wanted to be when they were very young. Have them list the people that they imagined or fantasized being while they were still children (e.g., a super hero, doctor, fireman, etc.). This exercise allows patients to access their emotional past, and to feel and recover pleasant, lost memories, and phantasies.

2. Next, have the patients link all the peak experiences of each imaginary character (e.g., a doctor and fireman possess power to save lives, and can be considered heroes, as they are both admired for their skills, etc.). This knowledge informs patients regarding the underlying nature of each imaginary character and may also reveal hidden talents, passions and ideas.
3. Then, have the patients write down a list of their personal priorities. This list should contain the patients' present state of active priorities, and their current value system.
4. Then, have the patients write down their own "code of conduct," i.e., their conscious value system. The patients' code of conduct represents the ethical standards by which they strive to act. This code of conduct influences feelings, thoughts, and beliefs. It affects the patients' personal priorities and reflects the quality and nature of their interpersonal relationships. It is from this personal code of conduct that they accept, or condemn, themselves and others. By physically writing down these moral conducts, patients can emotionally connect with new found feelings of moral integrity, as well as a establish a stronger connection with their True Self.
5. Finally, have the patients write down a "life purpose" statement, linking together the collected emotions gathered from the peak experiences of their childhood and their code of conduct.

It is important that patients know and feel that what they are writing is a true and accurate account of their thoughts and emotions. The patients' live purpose statement can always be modified and changed, as they undergo personal transformation and spiritual growth through experience and expanding knowledge.

SECTION V

DIFFERENTIAL DIAGNOSIS OF ENERGETIC PRINCIPLES

CHAPTER 20
INTRODUCTION TO DIFFERENTIAL DIAGNOSIS

DIAGNOSIS IN ENERGETIC MEDICINE

Chinese Medicine developed into a comprehensive and extremely effective diagnostic system, over many centuries of accumulated clinical experiences. The symptomatology to identify disease patterns and their underlying disharmony follows the way of nature in its relationship to cause and effect. To identify the patterns of disharmony, the Qigong doctor combines diagnosis of pathology and treatment principles into one continuum. The identification of the disease pattern is not only developed through categorizing a list of symptoms, but also through observing the pathogenesis of the disease. A symptom is a feeling, or reaction, that is a sign of disease, resulting from certain disorders (physical, mental, emotional, energetic, and spiritual).

Treatment must be aimed at finding and treating the cause of the disease. This is one of the most fundamental principles of Traditional Chinese Medicine in terms of differential diagnosis and treatment. The fundamental purpose of diagnosis is to find:

- the cause of the disease,
- the root of the disease, and
- the location of the disease.

Finding the primary cause (or root) of the disease requires understanding its nature, and allows the doctor to focus treatment on the most important etiological and pathological aspects of the disease. When diagnosing a disease, emphasis is placed on observing the energetic movement (or lack thereof), as well as energetic transformation, and not on the present set structures of the existing tissues. The tissues's structures are temporarily generated by the existing energetic changes and are therefore of secondary interest to the changes themselves.

ETIOLOGY IN MEDICAL QIGONG THERAPY

The etiology, or study of the causes of diseases in Medical Qigong therapy can be divided into what is commonly called in Traditional Chinese Medicine as the "three periods of life." These three periods encompass the developmental activities of the patient's Jing, Qi, and Shen formations during the transitional periods of their life, i.e., within the womb, childhood, and adulthood. Each patient's constitution results from the continuous interaction between his or her inherited form and the environment.

Within each period of life Three Stars develop and determine some of the major characteristics and traits of each person. Each group of Three Stars accounts for one third of what, and who, the person is. They combine together to form and complete a Nine Star System of life evaluation.

ETIOLOGY WITHIN THE WOMB

Problems arising during the Three Star Period within the womb (and during birthing) encompass the formative time span of 40 weeks. This time period can be influenced by the following factors.

1. The state of the patient's Jing prior to conception. If the Jing of one or both parents is deficient, the sperm and/or ovum will be weakened.
2. The mother's mental state during pregnancy has a deep affect on fetal formation, and directly affects the developmental activities of the fetus's Jing, Qi, and Shen. If the mother is malnourished, ill, emotionally disturbed, or taking alcohol or drugs during pregnancy the development of the fetus will be affected.
3. If the birth is abnormal, difficult and/or prolonged, it can cause an emotional shock within the newborn.

Diseases may originate from one or more of these factors causing the baby to be born with an illness or a predisposition to illness. This predisposition can be manifested as a particular type of emotional or mental imbalance, a diseases of particular Yin and Yang organs (or organ systems), or a general weakness as a whole. These conditions are commonly observed as "prenatal shock," and are indications of active fetal toxins. Prenatal shock can also be indicated when newborn babies are restless sleepers, continually opening and closing their eyes, and / or having fevers.

These problems are sometimes difficult to diagnose; simple observations however, can help the Qigong doctor to determine if the patient has experienced prenatal shock. A bluish color on the forehead of the patient, for example, is one indication of this condition.

ETIOLOGY DURING CHILDHOOD

Problems arising during the Three Star Period of childhood encompass the formative time span of 18 years. These internal problems can result from abuse, malnutrition, trauma and excess sex (during the teenage years). The subconscious mind of a child is extremely impressionable to both positive and negative influences.

If, as children, the patients experienced any physical, emotional, or sexual abuse, suffered a traumatic loss (of a relationship with either or both parents, siblings, peers, etc.), then they may become predisposed to illness later in life, or develop a disease during this time period. These traumas can affect the adolescent developmental activities of the patient's Jing, Qi, and Shen formations, as this is the child's greatest time of physical growth and development.

ETIOLOGY DURING ADULTHOOD

Problems arising during the Three Star Period of adulthood (from the age of 18 onwards), encompassing the time span of 60 years. These problems are caused by the patient's internal emotions and reactions to surrounding environmental factors. Environmental factors include: diet, relationships (be they social, work related, family or other), frequency of sex, and so on, and will affect the continual developmental activities of the patient's Jing, Qi and Shen formations. An adult, although less impressionable than a child, is less resilient than the child to trauma and illness.

PROGNOSIS

If the patient's constitution has been poor since birth, or if a specific disease has been present since birth, the prognosis is generally poor. If, however, the specific disease is acute, or has only developed during the patient's adult time period, the prognosis is more favorable.

There are always energetic interactions between these Three Periods of life. If, for example, a young female patient has a hereditary imbalance between her Conception and Governing Vessels, and also has severe emotional strain during puberty, she may suffer mental problems later on in her life.

THE GROWTH AND PEAK CYCLES OF JING, QI AND SHEN

By studying the physical, mental, emotional, spiritual, and energetic qualities inherent within the human body, the Qigong doctor is able to observe and predict the various changes according to the Nine Star System of life evaluation. It is believed that the body is given specific time periods in which to flourish during the three periods of life. The following chart depicts the body's natural time frame of each physical, mental, emotional, spiritual, and energetic peak (Figure 20.1).

- From birth to age ten represents a time of growth and development on each dynamic level. The child is in a formative stage, growing physically, mentally, emotionally, spiritually, and energetically.
- From age ten to age twenty represents a time of peak physical growth. Within this time frame the child physically enters into puberty, and is able to reproduce; the growing process is stabilizing.
- From age twenty to age thirty represents a time of peak mental growth. Within this time frame the adult actively acquires knowledge for survival sake. He or she is now able to work, produce results and begins planning for the future.



Figure 20.1. Chart of Physical, Mental, Emotional, Spiritual, and Energetic Peak

- From age thirty to age forty represents a time of peak emotional growth. Within this time frame the adult actively acquires knowledge for emotional comprehension of his or her surrounding environment. The adult is now able to creatively express his or her emotions in a civil manner and deal well with emotional disruptions.
- From age forty to age fifty represents a time of peak spiritual growth. Within this time frame the adult actively acquires knowledge for spiritual growth. Now comprehending his or her mortality, the adult begins to actively seek spiritual peace.
- From age fifty to age sixty represents a time of peak energetic growth. Within this time frame the adult's previous experiences come into fruition. If the adult has successfully acquired physical, mental, emotional, and spiritual harmony, the energetic peak will prepare the adult for the rebirth. If the physical, mental, emotional, and spiritual energy is not in harmony, the life-force is terminally exhausted, and the patient dies.

  It is commonly noted that when martial arts masters practice their training excessively or incorrectly, it is within this energetic time frame that they die. The cause of death is generally due to the over exertion of the master's Liver and Lungs, and the weakening of the Spleen, Heart, and Kidneys. This energetic disharmony stems from an improper balance of combat training with little or no spiritual training.
- From age sixty on is a time of new beginnings. This time frame represents new challenges of leadership within the family and the community.

DISORDERS OF THE HUMAN BODY

Disorders of the human body are generally due to three factors: constitutional failure of the body's Prenatal or Postnatal Qi, pathogenic factors and unrestrained Evil Qi, or one or more of the Eight Miscellaneous Factors.

CONSTITUTIONAL FAILURE OF PRENATAL AND/OR POSTNATAL QI

Prenatal and postnatal constitutional failure results in a constitutional Qi Deficiency, disease, or stagnation of the vital energy.

The Prenatal Constitution is determined by the strength of the parents when a child is being conceived, or during the pregnancy. If the parents are weak, sick, drunk, or on drugs during pregnancy or conception, the parents' Qi, Blood, and Body Fluids will be deranged and the child will be affected.

In uterus, if the mother is sick, the energy of the child will be affected. Also, negative emotions, poor nutrition, smoking, drugs, and alcohol used by the mother can affect the child within the womb and predispose the child to illness after birth (e.g., prenatal alcohol syndrome and crack babies are born addicted and with mental and physical defects). The prenatal constitution is inherited from both parents and is unchangeable.

The Postnatal Constitution is determined once the child is born. Proper nutrition and a nurturing environment enhances his or her constitution. While it is not possible to entirely erase the effects of the patient's prenatal constitutional patterning, it is possible to enhance it through a balanced life-style and development of their postnatal constitution.

PATHOGENIC FACTORS AND UNRESTRAINED EVIL QI

Pathogenic factors and Evil Qi are derived from Six External Factors and Seven Internal Factors.

The Six External Factors arise from the six climatic changes (Wind, Summer Heat, Damp, Dryness, Cold, and Fire). When the patient's energy system is not well balanced, or the Qi is Deficient, the body is unable to adapt to climatic factors. These climatic factors can then invade the patient's Wei Qi fields and penetrate deeply into the channels and internal organs of the body.

The Seven Internal Factors arise from excessive internal emotions (anger, joy, worry, grief, sadness, fear, and shock). These feelings overwhelm the patient's mental state as the individual responds to social, emotional, and environment interactions. Under normal circumstances, emotions in and of themselves do not cause problems, if they are allowed to be expressed and released. The excessive accumulation of one or more emotions can, however, cause Qi deviations, affecting the corresponding organ or organs of the body.

EIGHT MISCELLANEOUS CAUSES OF DISEASE

Sometimes a patient's disease is caused by what is known in Traditional Chinese Medicine as the Eight Miscellaneous Factors (Diet, Overexertion, Sex, Excessive Child Bearing, Exposures to Poisons, Parasites, and Iatrogenic Disorders). The Eight Miscellaneous Factors offset the patient's balance of Yin and Yang energy and are described as follows.

1. An improper diet can throw the patient's body and mind out of harmony. Nutritional problems can be divided into three main categories:
    a. The excess intake of certain particular foods, as well as overeating food in general.
    b. Unwise eating habits such as:
    - eating foods that are inconsistent with the seasons,
    - eating a diet of too many Cold, Damp, Dry, Hot, greasy, spicy or raw foods,
    - eating irregular meals,
    - oscillating from feasting to fasting, or
    - eating while hurrying or emotionally upset.

    c. Malnutrition, which is developed from a deficient intake of the basic requirements needed to maintain a balanced diet. This condition can be caused from ignorance, poverty, or an impaired digestion, absorption and metabolism.
2. Overexertion consumes the Qi and results in energetic deviations. This condition pertains to both mental/emotional and physical exhaustion, and can stem from loss of sleep, inadequate rest, etc.
    a. Mental and emotional overexertion can stem from a dissatisfaction with one's work (or the lack of work), or a dissatisfaction with one's life. It can lead to stress, frustration, boredom, apathy, or depression.
    b. Physical overexertion varies according to the individual's occupation, as each job has its own characteristics hazards to the patient's health. Problems arising in this area can range from structural damage to organs and tissues (caused from Qi and Blood stagnation), to sensory impairment.
    c. Lack of sleep and inadequate rest can also be either a contributing factor or direct cause in the development of Qi deviations.
3. An unbalanced sex life can cause disease. An individual's sex life is innately connected to the personal spiritual qualities of his or her Hun and Po. Therefore, the majority of sexual problems are rarely of purely physical origin, and reflect the energetic balance of each individual's emotional and spiritual passions.
    a. An Excessive sex life: what is excessive for one individual may not necessarily be excessive for another. The condition of Sexual Excessiveness should therefore be based on the individual's con-

stitution. When an individual exceeds his or her body's normal sexual function, the excessive sexual act can burn up the body's Yin, Jing, and Kidney Qi, causing Deficient syndromes (this condition is more prone in men then women). The act of sex itself is considered a Hot and Damp state.

b. A Deficient sex life: when an individual abstains from sex, his or her Jing production begins to increase. If this increased energy buildup is not transformed into spiritual energy, it can overflow into the Sea of Marrow affecting the brain. The prolonged lack of sex sometimes creates an emotional need and dependency towards addictions to replace the need for intimacy.

4. Excessive childbearing injures the mother's Blood and weakens her Qi. Women suffer loss of Jing during childbirth, therefore excessive childbirth can cause a Deficient condition.
5. Traumatic accidents and injuries pertain to physical traumas which disperse or congeal the body's Qi and Blood, resulting in energetic deviations. Even after the physical trauma has healed, a site for potential weakness often remains. As the patient ages, the site becomes vulnerable to further injury due to old age, physical exhaustion, stress, and exposure to cold. All traumatic accidents and injuries also pertain to emotional trauma as they are energetically inseparable.
6. Exposure to poisons pertains to any substance taken into the body by ingestion, inhalation, injection, or absorption that interferes with the patient's normal physiological functions. These poisons include both chemical as well as environmental toxins (e.g., pesticides, carbon monoxide, electromagnetic fields, and radiation).
7. Parasites include infections and infestations, and pertain to the numerous organisms capable of living within the body.
8. Iatrogenic disorders pertain to any adverse mental, emotional, or physical condition induced through medical treatment.

THE DIFFERENTIATION OF SYNDROMES

The essence of Chinese medical diagnosis is holistic and based on the concept that all things and events are interrelated. Thus the Chinese physician takes into account not only the physical symptoms of the disease, but also spiritual, mental, emotional, and environmental factors or events, that both interrelate and interact to form "patterns of disharmony" within the patient. The doctor studies and seeks to understand these patterns of disharmony, called "syndromes," to provide the framework for treatment.

Syndromes can include External or Internal factors, congenital or acquired disorders, and symptoms of stagnation, Excess, and Deficiency, or traumatic injuries to the organs and tissues. The Qigong doctor must first determine whether the patient's disease is primarily due to an energetic disorder (e.g., an Excess or Deficient condition) or a physical disorder (i.e., structural damage). Once this determination has been made, the goal or goals of treatment can be set, and the means of treatment chosen. In the treatment of the lower back, for instance, if lumbar pain is due to a subluxation of the vertebra, caused by external injuries, the doctor should first reposition the vertebra through hand manipulations, by using Tui Na therapy, then remove the Qi stagnation. If the doctor is unfamiliar with such techniques, it is better that he or she first refer the patient out for spinal adjustment, and then remove the Qi stagnation. Only in this way can a satisfactory curative effect be obtained. If, on the other hand, the back pain is due to abdominal distention or a Kidney malfunction (i.e., primarily an energetic disorder) then treatment must proceed through Qi emission.

Several methods can be used singly, or in combination, to diagnose syndromes. They are described as follows.

1. Diagnosis according to the identification of the Eight Energetic Principles.
2. Diagnosis according to the identification of Qi, Blood and body fluid distinctions.
3. Diagnosis according to the identification of

the Five Elemental patterns.

4. Diagnosis according to the identification of the Six Stages.
5. Diagnosis according to the identification of the Four Levels.
6. Diagnosis according to the identification of the Triple Burners' System.

THE CATEGORIZATION OF SIGNS AND SYMPTOMS

In order to categorize symptoms into syndromes, the Qigong doctor must determine: The Onset, Location, Aggravating or Relieving Factors, Type of Pain or Sensation, and Course Since Onset.

1. The Onset includes the date the symptoms first appeared, whether they appeared suddenly, or had a gradual onset, and the order of their appearance.
2. The Location specifies whether the symptoms remain fixed, or migrate throughout the body.
3. The Aggravating or Relieving Factors indicate the specific conditions that affect the symptoms in a positive or negative way. Aggravating or Relieving Factors may include:
   - if the symptoms feel better or worse during daytime or nighttime,
   - if the condition is better with application of warmth or cold,
   - if the condition is better with pressure or worse with pressure,
   - if the condition is relieved by movement or aggravated by movement, and
   - if the condition is relieved by eating or made worse by it.
4. The Type of Pain or Sensation describes the nature of the symptoms, such as:
   - sharp or dull
   - pounding
   - stiffness
   - burning
   - itching
   - intermittent (coming and going)
   - electrifying
   - pulling or shooting
   - nauseated
   - distended
5. The Course Since Onset includes the incidence, progress, and the effectiveness of the treatments received.

The syndromes do not equal the patient's disease, but are the patterns of the illness. In determining the patient's syndrome, the Qigong doctor takes into account that these patterns can occur simultaneously, and vary in degree of severity. The purpose for assigning the patient's disease a syndrome is not merely to classify the disease, but to understand its process. Not all the symptoms listed for a particular illness need to be present in order to properly determine the patient's syndrome.

DIAGNOSIS AND TREATMENT OF THE PATIENT

The assessment and evaluation of the patient generally proceeds in eight stages. The first seven of the eight stages are performed prior to the initiation of the actual treatment. The final stage is undergoing the treatment plan and the periodical reevaluation of the course of the disease since the beginning of the treatment (Figure 20.2). During these eight stages, the Qigong doctor assess: The Whole Person, The Patient's Constitution, The Signs and Symptoms of the Disease, The Syndrome, The Patient's Organs, The Etiology of the Disease, The Treatment Goal, and the Treatment Plan.

1. The Whole Person must first be evaluated according to his or her whole being. This process involves assessing the patient's:
   a. physical appearance (e.g., is the patient disheveled or appropriately groomed),
   b. energetic demeanor (is the patient very nervous, calm, manic, etc.),
   c. structural build:
   - according to the physical Yao formations,
   - introverted or extroverted features, and
   - Yin or Yang appearance.
2. The Patient's Constitution is assessed according to the Five Elemental Constitutions and their subdivisions of balance, and Yin or Yang predominant element.
3. The Signs and Symptoms of the Disease are then classified as:
   a. Objective Signs that are apparent to the doctor,



Figure 20.2. The Qigong doctor begins to diagnose the patient by first observing the patient as a whole. Next the doctor observes the patient's constitution, symptoms, syndrome, health and state of the internal organs, and the cause of the energetic dysfunction, before treating the disease. All the acquired knowledge is placed against the different diagnostic templates of the Eight Parameters, Five Element Theory, Qi, Blood and Body Fluid Dysfunctions, etc. This entire process is initiated in order to assist the Qigong doctor in prescribing the correct treatment. The treatment focuses on the specific cause of the disease and how it affects the patient's internal organs. The primary goal being to relieve the patient's symptoms, strengthen the constitution, and return the patients to a state of wholeness.

- b. Subjective Symptoms that the patient reports to the doctor,
- c. Cardinal Symptoms and Signs that are used for differential diagnosis of disease, and
- d. Constitutional Symptoms and Signs that are indicative of a systemic disorder.

4. The Syndrome (a pattern of disease) is then determined according to the patient's symptoms and signs of disordered function, by assessing their relationship to one another.
5. The Patient's Organs are then evaluated according to any pathological changes occurring within the internal organs.
6. The Etiology (or root causes) of the syndrome is determined to complete the comprehensive diagnosis.
7. The Treatment Plan is then formulated, taking into account all the data gathered by the doctor. The Qigong doctor devises a treatment goal and determines a strategy of treatment

that addresses the patient's syndrome or disease, in accordance with the agreed upon goal and needs of the patient.

8. The Treatment is implemented and prescriptions are assigned to initiate the healing process. Over time, the treatment plan is reevaluated, as the patient improves or suffers setbacks (for various reasons). Prescriptions, likewise undergo changes in accordance with the patient's changing condition.

Once treatment begins, the process of the development of the disease is usually reversed, or the symptoms are alleviated. After the initial treatment begins, the causes of the disease are addressed, thus affecting the organs, which in turn changes the syndrome and the symptoms. This process strengthens the constitution and establishes a dynamic balance of health and well being.

UNDERSTANDING THE THEORY OF ENERGETIC COUNTERACTION

When treating patients it is important for the Qigong doctor to understand the theory of Energetic Counteraction. This theory describes the body's natural regulation, wherein no two specific symptoms (affecting the patient's general constitution) can occur at the same time, for any considerable period, within the same system.

Generally as a disease progresses, the old symptoms will give way to the newer ones. Consider, for example, a patient who has asthma, which is brought about by Wind Cold invading the Lungs (resulting in a dyspnea, wheezing, coughing, and severe mucous). If this patient unexpectedly suffers from an attack of gout (a painful inflammation and swelling of the joints), caused from the Wind Damp invading the joints and channels, the sudden attack of gout will cause the patient's asthmatic symptoms to disappear. When the gout subsides, the asthmatic symptoms will return. The new disease naturally prevails over the original condition.

CHAPTER 21

DIAGNOSIS ACCORDING TO THE EIGHT ENERGETIC PRINCIPLES

The method of diagnosis according to the Eight Energetic Principles was formulated by doctor Cheng Zhong Ling during the early Qing Dynasty. The Ba Gan or Eight Principles of Differential Diagnosis is a system using four pairs of opposite symptoms viewed in Traditional Chinese Medicine as being essential to the understanding and treatment of disease. In most cases, knowledge of the diagnostic systems and treatment principles of general Yin and Yang conditions is enough to give the Qigong doctor some good guidelines for steering the patient's training program. Similar principles can be found in most ancient healing traditions.

The four opposite pairs are Yin-Yang and the three subdivisions of Yin and Yang into: Internal-External, Hot-Cold, and Deficient-Excess.

1. Internal and External Symptoms inform the doctor of the origin of the pathogenic condition.
2. Hot and Cold Symptoms inform the doctor of the disease's onset (how it came on) and whether the patient's temperature has been altered due to a viral infection or a metabolic change.
3. Excess or Deficient Symptoms inform the doctor whether the condition is either to be tonified or purged, and the strength of the patient's constitution.
4. Yang and Yin Symptoms inform the doctor how to establish a physical (external), as well as energetic (internal) balance.

A detailed knowledge of the Eight Energetic Principles is required to pinpoint more subtle patterns of disharmony. This understanding allows the Qigong doctor to unravel complicated patterns and identify the basic contradictions within them. The main purpose for applying these principles is to understand the etiology of the disease and the nature of the dysfunctions; not simply to categorize the illness. Only then can a treatment pattern be initiated.

INTERNAL AND EXTERNAL PATHOGENIC FACTORS

Diagnosis according to internal and external pathogenic factors is not based on the etiology but on the basis of the disease's location. If a disease is caused, for example, by an "external" pathogenic factor but is currently affecting the internal organs it is classified as an Interior condition. An Exterior condition affects the patient's skin, muscles and channels, known as an "exterior pattern" of pathogenic factors. An Interior condition will affect the bones and internal organs, known as an "interior pattern" of pathogenic factors.

EXTERIOR CONDITIONS: SIX EXOGENOUS PATHOGENIC FACTORS

The external pathogenic factors—Wind, Cold, Dampness, Fire, Heat, and Dryness—are the six "evil" factors that come from the environment outside of the body. Under normal circumstances they are good for the health, but can be very harmful when they become abnormal.

Unseasonable weather (weather that is too cold or too hot for the body to tolerate) can make people ill by impeding the normal flow of internal energy thus making the body vulnerable to disease.

Each external factor, once it enters the body can manifest as an internal factor (i.e., External Wind can penetrate and become Internal Wind, etc.). It is also important to know that an external invasion once it penetrates the organ can transform into another internal factor (i.e., an External Cold invasion can give rise to Internal Heat).

These external factors are seen as not only the cause of disease, but also as manifestations of the disease. A disease may be due to any one of these Six External Pathogenic Factors, or simply manifest as an external "evil," even though that pathogenic factor was not present at the time the patient got sick (e.g., Damp-Heat). Treatment is therefore based on how a disease manifests itself, rather then the specific cause. However, it is wise to have a sense of the etiology of the disease to determine where to intervene and what might be expected next.

The Six External Pathogenic Factors are categorized in China according to the seasons, temperature, and climate. These transitions are explained as follows.

1. The Heat Season is characterized by temperatures that are usually above 90 degrees Fahrenheit. The Heart, Small Intestines, and blood vessels are the most vulnerable at this time. This is most evident in summer.

   Heat is a Yang pathogenic factor that rises and spreads excessively, consuming and diminishing the Prenatal (Yuan) Qi, Body Fluids and Lung Qi. As Heat rises, the body's Qi is drawn upward and dispersed, causing the Yin energy to descend. Symptoms can range from restlessness, anger, delirium, loss of consciousness to even coma. This condition is most evident during the summer. The Heart organ benefits from bitter tasting foods which directly stimulate and enhance the Heart's Qi.

   a. Mild Heat that has been created within the body, causes an ascending action of Qi. This ascending action causes the body's Yin energy to become disturbed creating an energetic imbalance.
   b. Fire (Extreme Heat) is a Yang pathogenic factor and spreads excessively, consuming and diminishing the Yuan Qi, Body Fluids, and the Lung's Qi. It produces an explosive reaction, causing the Qi to flow up into the head and disturb the Blood. This action causes symptoms ranging from nosebleeds, skin infections, swelling, and skin eruptions, to hemorrhaging and vomiting Blood.

2. The Damp Season most often affects the Spleen, Stomach and muscles that are at their most vulnerable time. The Spleen organ benefits from sweet tasting food. The temperature is usually between 75 and 90 degrees Fahrenheit. This is evident in the late summer, during the rainy season.

   Dampness is a Yin pathogenic factor that easily obstructs the body's production of Qi and impairs the Yang. It is considered a Yin pathogenic factor because, as the invasion of Dampness moves downward, it manifests as a heavy and turbid energy, resulting in a full chest, nausea, vomiting, and a sticky sweet taste in the mouth. During the damp season, an invasion of Dampness may affect the urinary organs, causing stagnation of Qi. Once pathogenic Dampness enters the body, it becomes foul in nature. If the body becomes obstructed, the results will become evident in skin diseases with abscesses, and oozing ulcers with turbid, cloudy urination. Disease also manifested through infections, in combination with Heat.

3. The Dry Season is characterized by temperatures that are usually between 60 and 70 degrees Fahrenheit. The Lungs and skin are the most vulnerable at this time. This is most evident in autumn, because of the lack of humidity.

   Dryness is a Yang pathogenic factor because as the Heat rises, dryness consumes the body's Yin Qi, especially in the Lungs. This results in dry, chapped skin, cracked skin, and dry cough with sputum, throat pain, or asthma. The Lungs themselves benefit from pungent tasting foods, which directly stimulate and enhance the Lung's Qi.

4. The Cold Season is characterized by temperatures that are usually below 60 degrees Fahrenheit. The Kidneys, Bladder, and bones are most vulnerable at this time. This is most evident in the winter.

   Cold is a Yin pathogenic factor characterized by astringency of the tissues. During the Cold season the Yin pathogenic factors consume the Yang Qi. Cold blocks the channels and collaterals, causing pain and damage to the Heart, as well as consuming the Kidney Yang. Pathogenic Cold also causes the channels and collaterals to contract, resulting in the slowing down of Qi and Blood circulation. As the Yin energy moves downward consuming the body's Kidney Yang, the body's Yang is unable to generate heat causing chills, pallor, shivering, diarrhea with undigested food, stiffness, pain, numbness, and clear urine. Internal Cold is characterized by conditions of overall stagnation and contraction. The Kidneys themselves benefit from salty tasting foods which directly stimulate and enhance the Kidney's Qi.

5. The Wind Season affects the Liver, Gall Bladder, and tendons that are at their most vulnerable time. The beneficial taste is sour. The climate in the Wind season, depending on the area, is usually between 60 and 70 degrees Fahrenheit. This is most evident in the spring. Wind is Yang in nature and tends to injure the patient's Blood and Yin. It is divided into both internal and external pathogenic Wind conditions. External Wind is called "the mother of one thousand pathogenic factors," and is responsible for the propagation and growth of the pathogenic environment, because it combines with other pathogenic factors to create Wind Heat, Wind Cold, Damp Wind, Dry Wind, etc.

   In the Wind season the Yang pathogenic factors are in the upper portion of the body, weakening the Wei Qi, and causing derangement of the opening and closing of the pores on the body's surface. The pathogenic Wind tends to move constantly causing abnormal motion and rigidity in the trunk and limbs. External Wind affects the upper part of the body, shifting and moving the pain like blowing a leaf. Once External Wind invades the body, the symptoms are stiff neck, itchy sore throat, watery eyes, headache, nasal obstruction, facial puffiness, aversion to Wind, irritability, abnormal sweating, migrating joint pain, tremoring, convulsions, rigidity, and facial paralysis.

   Internal Wind is manifested through the same symptoms. Because of its serious nature, it can also cause tremors, convulsions, and paralysis throughout the body (with the exception of the face, which is due to External Wind invasion).

INTERNAL PATHOGENIC FACTORS

An interior disharmony is diagnosed when the internal organs have become affected by pathogenic factors, creating an Interior syndrome. Interior syndromes are the pathological conditions which have resulted from one of three factors: (1) the invasion of the channels by external pathogens, which can be transmitted to the body's Yin and Yang organs; (2) the direct attack on the Yin and Yang organs by external pathogens; and (3) sudden emotional changes due to improper diet and stress which directly affect the body's Yin and Yang organs leading to functional disturbances.

1. A Persistent Exterior Invasion by one of the Six Exogenous pathogenic factors can penetrate deeper into the body creating an Interior syndrome, if it is not purged from the patient's body.
2. A Direct Invasion of the Yin and Yang organs can also occur from an Exterior Invasion of pathogens. In such cases, the affected organ will manifest as an Interior Excess or Deficient condition depending on the syndrome.
3. Emotional Factors can likewise cause damage to one of the Yin organs, which in turn can cause damage to the other Yin and Yang organs. People encounter emotional upheavals in everyday activities. Under normal circumstances, the Seven Emotions are good for health (see Chapter 21). Appropriate anger helps to disperse stagnant Liver Qi, preventing stasis of Liver energy and helps the patient to establish a healthy boundary system. Rage, on the other hand, leads to the abnormal increase and ascension of Liver Qi, resulting in a flushed face and dyspnea (shortness of breath). If the pattern continues (i.e., the person is a rage-aholic), the violent and uncontrolled anger may lead to serious disorders of the Liver, including eye injury, fainting due to inadequate Blood flow to the brain,



Figure 21.1. Cycle of Disharmony

cerebral hemorrhaging, or even death. It is believed therefore, that Internal conditions can arise from either an Excess emotional condition caused by emotional suppression, or a Deficient emotional condition caused by excessive emotional discharging.

It is also believed that a person's personal emotional history determines his or her biology (life processes). Each person creates this reality through his or her belief system. Hence the patient creates the disease by embracing traumatic past wounds and formulating belief structures that support these traumas. These energetic clusters are then fed via the major viscera by the excessive emotional energy. This pathological emotional process can result in the formation of cysts, tumors, cancer, etc.

Any imbalance of the Seven Emotions leads to the unnecessary consumption, or blockage of, the internal Qi flowing through the channels of the viscera. In either instance, this results in abnormal Qi activity and creates a functional disorder of the cerebral cortex.

Emotional disharmony induces a vicious cycle which affects the mind, body and spirit. Any factors (Yin and Yang disharmony, emotional disharmony, disturbed behavior, or environmental disharmony) can trigger the cycle (Figure 21.1). When caught in this cycle, emotional energy can deplete the physical body.

Anger, for example, generally causes the Qi to rise; however, when anger turns inward it can transform into depression. Mental depression may obstruct the functional activities of Qi and this stagnation may cause Fire. The Fire syndrome is caused by the disorders of the Seven Emotions and may burn up the fluid of the organ related to the predominant emotion.

In Western culture, people are generally not encouraged to acknowledge painful emotions; feelings are usually disregarded and conquered by a strong will. The storage of emotional energy in the muscles and organs of the body leads to tension, stress, and illness. The Qi cannot circu-



Figure 21.2. Five Elemental Controlling Cycle

late with emotional blocks. Many specialists in Western medicine today agree that a large percentage of diseases being treated are, indeed, caused or aggravated by stress.

The Five Elements have a creating (generating) and restrictive (controlling) relationship. The sequence of the creative relationship of the Five Elements is: Wood creates Fire; Fire creates Earth; Earth creates Metal; Metal creates Water; Water creates Wood. This circle is endless.

The sequence of the controlling relationship of the Five Elements is: Wood controls Earth; Earth controls Water; Water controls Fire; Fire controls Metal; Metal controls Wood. This circle is also endless.

The controlling relationship can be applied to problems with emotions. Anger, for example, belongs to the rising of Excess Liver energy and can be counteracted by descending the Lung's Qi (Figure 21.2). The Lungs control sadness, and sadness may lead to the consumption of abnormal rising Liver Qi (Metal controlling Wood).

Excessive sadness may lead to the extravagant consumption (and depletion) of Lung Qi, which damages the body's Yin and the Heart. The consumption of the Lung Qi can be stopped by the Heart's energetic release of the emotion of joy. Joy causes the rapid rising of the Heart's Qi. It can be regulated by fright and terror, which are controlled by the rapid descending energy of the Kidneys. Terror leads to the abnormal falling of Qi, it therefore counters the abnormal rapid rising of Heart's Qi. Excessive fright and terror may lead to the abnormal sinking of Gathering Qi, which damages the Kidney's Qi (Figure 21.3).

Because over-thinking can cause Qi to gather, it can be used as a tool to help bring back dispersed energy. Over-thinking and anxiety, however, may lead to the depression and stagnation of Qi, which weakens the transporting and converting ability of the Spleen's energy, and causes a lack of appetite. Mild cases of this condition can manifest as dyspepsia (indigestion), abdominal distention and diarrhea. In severe cases, the Qi

The Seven Emotions

Chinese Word	English Translation	Organ Association	Qi Manifestation
Xi	joy, happiness, excitement, pleasure	Heart	slows down and relaxes the Qi
Nu	anger, irritation	Liver	causes Qi to rise
Si	meditation, contemplation, pensiveness, worry	Spleen	stagnates the Qi
You	anxiety, sorrow, grief	Lungs	obstructs the Qi
Kong	fear, extreme anxiety	Kidneys	causes Qi to descend
Jing	shock (sudden intense fear), fright	Heart then Kidneys	scatters and deranges the Qi
Bei	grief, affliction, sadness	Lungs	disperses and consumes the Qi

Figure 21.3. The Seven Emotions Chart

and Blood stagnate in the chest and abdomen, causing a feeling of fullness in the chest or upper abdomen. This stagnated, ever-sinking Spleen energy can be smoothed and aroused by anger (the Liver's energy expanding upward and outward). In short, the hyperactivity of Yin is treated with Yang to check the unnecessary consumption of internal energy, and to promote a mild Yin energy. Then the Qi and Blood can flow without interruption and disease can be prevented.

One effective technique to avoid an emotional and energetic overload or depletion of a Yin organ's Qi, is to apply the Five Elemental counter-emotion to restore emotional balance (see Chapter 53).

OVERVIEW OF EXTERNAL AND INTERNAL CONDITIONS

The internal and external diagnostic parameters locate the depth of the condition of the disharmony and are fairly easy to distinguish, relative to the other pairs of opposites. Thus, determining the internal or external nature is usually the first step in diagnosis of a disorder.

Internal conditions are usually caused by internal disharmonies, such as excessive emotional energy in the form of anger, excitement, sorrow, anxiety, fear, and mourning, or other imbalances associated with the Seven Emotions. Excessive thinking and stress can also lead to an imbalance that is characterized as internal. Internal conditions are often chronic and tend to have a gradual onset and a longer duration.

Conditions of External disharmony are typically caused by the external influences on the body, known in Chinese medicine as "pernicious influences." They are Wind, Cold, Heat, Damp, Dryness, and Summer Heat. Pernicious influences usually invade the body when the body's Wei Qi is weak.

Typical External diseases are colds, influenza, skin eruptions, or diseases caused by injury or shock. Excessive amounts of eating, drinking, working, and sexual activity can also lead to both Internal and External disharmony. External conditions are often acute, with sudden onset, and of short duration.

Many times Internal conditions will develop when an External condition moves inward. This represents a further weakening of Wei Qi and the body's natural immune system. Before the condition has developed into a full Internal sickness, it will go through a stage of being half-external and half-internal.

Examples of conditions which may be considered as being half-internal and half-external are: alternating fever / chills, heaviness in the chest, restlessness, nausea, vomiting, no appetite, dry throat, irritation of the mouth, and dizziness. A bounding pulse is also an indication of this type of condition.

This is one reason why treatment of an External disease (colds and flu) requires sweating therapy to encourage the disease to remain external. The contractile mechanism of the skin is a specific external representation of the body's Yang immune system at work.

When treating extreme cases, such as internal injuries and shock, conserve the patient's Yang Qi by keeping them warm.

HOT AND COLD

Hot and Cold describes whether the condition is the result of a Hot or Cold state and is determined by hot or cold sensations. The nature of this clinical manifestation depends on whether it is combined with a Full or Empty condition.

HOT CONDITIONS

Hot conditions usually arise when there is excess activity of the body's Yang functions, or if there is an insufficiency of Yin Qi or Fluids in the body. A Hot condition can be further divided into either Full Heat or Empty Heat.

1. A Full Heat conditions manifest as the following physiological and mental / emotional symptoms.
   a. Physical symptoms include:
   - increased energy and metabolism, i.e., physiological hyperfunction
   - fever with thirst, and desire for cold liquids
   - dry stool and constipation
   - dark yellow and reduced urine
   - flushed face, red eyes, hot red skin
   - warm extremities
   - aversion to warmth
   - a rapid, full pulse and a red tongue with yellow fur

b. Mental and emotional symptoms include:

- irritability
- restlessness
- loud voice, talkativeness
- extroverted and aggressive behavior

Inflammations, ulcers, and infections are typical of Full Heat diseases. There are many other symptoms depending upon which organ is affected.

These Full Heat symptoms arise when there is an Excess of Yang energy in the body. Excess Yang energy can be caused from overconsumption of Hot foods (which cause Stomach or Liver Heat), or long-standing emotional problems (which cause Liver or Heart Heat) due to Qi stagnation. Full Heat can also develop from the invasion of external pathogenic factors which have transformed into Heat.

2. An Empty Heat conditions manifest as the following physiological and mental/emotional symptoms.

a. Physical symptoms include:

- dry mouth and throat (at night)
- night sweats
- afternoon fever
- a feeling of heat in the chest, palms and bottoms of feet (Five Palms Hot)
- dry stool
- scanty, dark urine
- a floating, empty and rapid pulse, with a red, peeled tongue

b. Mental and emotional symptoms include:

- fidgeting and mental restlessness
- vague anxiety
- insomnia

There are many other symptoms depending upon which organ is affected.

These Empty Heat symptoms arise from a Deficiency of Yin. If the patient's Yin becomes Deficient (usually due to a Deficiency of Kidney Yin), this affects the Yin of the Liver, Heart, and Lungs and causes a relative Excess Yang condition.

COLD CONDITIONS

Cold conditions usually arise when there is excess activity of the body's Yin functions, or if there is an insufficiency of Yang Qi in the body. A Cold condition can be further divided into either Full Cold or Empty Cold.

1. A Full Cold conditions manifest as the following physiological and mental/emotional symptoms.

a. Physical symptoms include:

- diminished physiological function and lowered immunity
- decreased energy
- aversion to cold and craving for warmth
- cold extremities
- lack of thirst
- clear urine, watery stool
- desire for hot drinks
- white face
- a slow pulse and a pale, white tongue with moist fur

b. Mental and emotional symptoms include:

- timid behavior and soft speech
- slow movement
- a lack of motivation

Generally, discomfort is increased by cold and reduced by warmth. Cold symptoms may also appear at later stages of fevers and chronic peptic ulcers, denoting a weakening of the body's ability to overcome the disease.

These Full Cold symptoms arise when there is an excess of Yin Qi in the body. Excess Yin Qi can be caused from the direct invasion of External Cold into the body's interior. In this particular condition, the External Cold can either invade the Stomach causing vomiting and epigastric pain, invade the Intestines causing diarrhea and abdominal pain, invade the uterus causing dysmenorrhea, or it can invade the Liver Channels causing pain and swelling in the scrotum. One of the main manifestations of Interior Full Cold is abdominal pain caused from the Cold constricting and obstructing the circulation of Yang Qi. Full Cold can also develop from the invasion of external pathogenic factors which have transformed into Cold.

2. An Empty Cold conditions manifest as the following physiological and mental/emotional symptoms.

a. Physical symptoms include:

- cold limbs and chills
- pale face
- fatigue
- no thirst
- loose stools
- clear, abundant urination
- sweating
- pale tongue with thin, white coating and a deep, slow or weak pulse

b. Mental and emotional symptoms include:

- tiredness and lack of motivation
- slow movement

An Empty Cold disharmony usually arises when the Yang Qi of the body is insufficient, and fails to warm the body. This is caused by a Deficiency of Spleen Yang, Kidney Yang, or Heart Yang (sometimes Lung Qi Deficiency). The most common cause is related to the Spleen Yang Deficiency, which fails to warm the muscles and thereby causes chills. If the Spleen does not receive heat for its function of transforming food, the result will also be loose stools.

COMBINATION OF HOT AND COLD SYMPTOMS

While distinguishing Hot diseases from Cold diseases may appear to be fairly straightforward, the doctor may find that there are many circumstances where both Hot and Cold symptoms appear simultaneously. The use of sensory input is just a general indicator, however, because it provides the doctor with only partial data; it can sometimes be misleading if other considerations are not taken into account. The doctor needs to consider the other symptom characteristics according to Yin-Yang or Deficient-Excess patterns.

1. An External Cold with Internal Heat syndrome manifests when a patient has a preexisting internal Heat condition and is subsequently invaded by External Wind Cold. This condition can also occur in attacks of latent Heat combined with the invasion of Wind Cold. Symptoms can include fever with an aversion to cold, body aches, irritability, and thirst.
2. An External Heat with Internal Cold syndrome manifests when a patient with a preexisting Cold condition is attacked by exterior Wind Heat. Symptoms can include fever with an aversion to cold, chills, headache, sore throat, and thirst.
3. A Heat Above-Cold Below syndrome manifests when a patient's pathogenic Heat rises resulting in Heat above and a Cold syndrome below. Symptoms can include thirst, bitter taste, sour regurgitation, irritability, Herpes Simplex I, borborygmus, loose stools, and pale and profuse urination.

Qigong patients must be aware of these signs of Hot and Cold disharmony. If a patient's training routine is too Yang, this will burn the body's Fluids, thus diminishing the Yin Qi's ability to contain the Excess Yang, which in turn produces a Hot condition. An overactive metabolism can also induce a Hot condition, while a sluggish metabolism can produce a Cold condition. Less extreme conditions are classified as warm, cool, or neutral.

EXCESS AND DEFICIENT

The capacity of an individual to maintain resistance to the invasion of pathogens is relative to the strength of the disease and the strength of the individual. An Excess condition is characterized by the presence of a pathogenic factor (interior or exterior) and by the fact that the body's Qi is still functioning normally. The battle against the pathogenic factors results in the symptoms and signs of an Excess condition. A Deficient condition is characterized by a weakness of the body's Qi and the absence of a pathogenic factor. If the body's Qi is weak, but the pathogenic factor continues to attack, the condition is considered Deficient and is characterized by an Excess.

EXCESS CONDITIONS

An Excess condition will usually occur when a bodily function becomes overactive or Qi accumulates unnaturally due to a blockage. It is characterized by strength, buoyancy of spirits and often acute symptomatic reactions. Disharmonious conditions which begin and end suddenly are due to Excess. Yang Excess can be quickly improved, in most cases, with a diet of predominately vegetables and fruits.

It is not unusual for patients whose diets are heavy in meat proteins, to suffer from Excess diseases. Many Naturopaths advocate the predominant use of raw fruits and vegetables and have experienced outstanding results due to the elimination of Excess Yang (from meat toxins) from the body.

Such a diet is not good therapy for individuals who eat a relatively balanced vegetarian diet, because it serves to make them more Yin and threatens to throw them off balance. This is a good reason to avoid "fad" diets. A diet or method that works well for one person may have the opposite affect for someone else; each case must be considered separately.

Some indications of an Excess condition are as follows: flushed face, loud voice, coarse and full breathing, acute pain, extreme menstrual pains, a tender abdomen, which worsen with the application of heat. A strong pulse can also be a sign of an Excess condition.

In cases of Excess, to expel pathogenic evils, the patient imagines that the Toxic Qi is being expelled from specific channel points upon exhalation. The results are always more effective when Qigong prescriptions are given in conjunction with the treatments.

Any interior pathogenic factor (Heat, Cold, Damp, Wind, Fire, and Phlegm) can give rise to an Excess condition, including the stagnation of Qi and stasis of Blood.

DEFICIENT CONDITIONS

Although Deficiency is characterized by insufficient Jing, Qi, Shen, Blood, and Fluids, it does not generally mean a lack of some nutrient as it does in Western medicine. It is more a statement about the body's inability to find, or produce, what is necessary for its immune function to provide a functional integrity in the body. Deficiency, therefore, is taken in a more general sense and denotes the overall condition of the patient, or of the disease.

Conditions which linger are usually due to Deficiencies. The general indications are: great weakness, inconsistent energy, shallow and rapid respiration, pain characterized by soreness, weak or inconsistent volume of voice, moderate menstrual pains, withered face, low spirits, and abdominal pain. A Deficient condition will generally respond well to heat and pressure. A weak pulse can also be an indication of a Deficient condition. There are four types of deficiencies: Deficient Qi, Deficient Blood, Deficient Yin, and Deficient Yang.

1. Deficient Qi is the first and least severe stage of Deficiency. Most symptoms arise from a weakness of the Lungs' Qi (which fails to control the breathing) and a weakness of the Spleen's Qi (which fails in its function of transforming and transporting).
2. Deficient Blood is caused from a dysfunction of various internal organs. Most symptoms arise from a weakness of the Liver, Heart, and Spleen.
3. Deficient Yin is caused by a dysfunction of various internal organs. Most symptoms arise from a deficiency of Yin within the patient's Liver, Heart, Stomach, Lungs, and Kidneys.
4. Deficient Yang is caused by a dysfunction of various internal organs. Most symptoms arise from a deficiency of Yang in the patient's Liver, Heart, Spleen, Lungs, and Kidneys.

In cases of Deficiency, when replenishing Qi is required, the best effect can be obtained when the patient cooperates with the doctor's extension of Qi through mental concentration and focused inhalation.

COMBINED EXCESS AND DEFICIENT CONDITIONS

Sometimes Excess and Deficiency conditions can occur simultaneously. Although Excess is one of the characteristics of a Yang disease, this condition can also give rise to certain symptoms of Deficiency. These are mostly a result of Qi being blocked in the utilization of its own vital nutrients.

YIN AND YANG THEORY

Yin and Yang energy is usually represented through the image of the Taiji symbol. Yang Qi is represented through the color white and Yin Qi is represented through the color black. Through the image of the Taiji symbol the interrelationship of Yin and Yang represent the stages of waxing and waning of energy (Figure 21.4). In Traditional Chi-


Yang - hot, bright, strong, upward, outward, clear, movement. Qi (non-substantial matter) function of an organ
Yin - cold, dark, weak, downward, inward, muddled, stillness. Blood (substantial matter) substance of an organ.

Figure 21.4. In Traditional Chinese Medicine the theory of Yin and Yang represent the dynamic duality of balance and harmony within the body, as well as within the universe itself, and as represented through the image of the Taiji Symbol. There is always Yin within Yang and Yang within Yin. These two energies are always changing and transforming the body's life force energy.

nese Medicine, the theory of Yin and Yang is also used to explain both the psychological and pathological phenomena of the body. It is considered a major principle for diagnosing and treating diseases.

Generally speaking, an Excess of Yang may lead to a Deficiency of Yin, and vice versa. A Hot syndrome can be the result of either Excess Yang or Deficient Yin. A Cold Syndrome can be the result of either Excess Yin or Deficient Yang (Figure 21.5).

The Qi activities of these Yin and Yang aspects unite and regulate the body's internal organs and tissues. The direction and energetic nature of Qi (Excess or Deficient, strong or weak, evil or vital) can be detected at corresponding body surfaces so that information for diagnosis and treatment can be obtained. For example:

A strong, dense, dry, and hot sensation of Qi in the head area may be a symptom of Excess Yang in the upper portion of the body and a Yin Deficiency in the lower portion. This would require the Qigong doctor to guide the Yang Qi to descend and the Yin Qi to ascend to restore the balance of Yin and Yang energy.

To treat patients with an overabundance of Yang Qi and hyperactivity of Fire, the Qigong prescription meditations should be practiced during the Yin periods (11 a.m. to 11 p.m.) while facing north, with emphasis placed on exhaling to purge the Heat. The doctor should adhere to the principle of replenishing the patient's Yin to regulate the Yang, or leading the Yang to descend to supplement the Yin.

Once the nature of Yin and Yang disequilibrium is determined, the proper method of treatment can be selected to regulate the Excess or Deficiency. The doctor always treats Yin for Yang diseases and Yang for Yin diseases. A Yang syndrome, for example, should be treated with Yin herbs, and a Yin syndrome should be treated with Yang herbs. The treatment should be aimed at purging the Excess, replenishing the Deficiency, and regulating the Deficient Yin or Yang to restore a normal balanced state of energy with in the body.

In Medical Qigong therapy, the principle of "using Yin for treatment of a Yang disease and using Yang for treatment of a Yin disease" must be strictly adhered to. It is important to dredge or purge the Excess before replenishing and tonifying any Deficiencies. The intake of cold foods (fruit, salad, ice cream, etc.) or drinks, for example, may lead to an Excess of Yin, which gives rise to a Cold syndrome of the Spleen and Stomach. This manifests as pain, diarrhea, aversion to cold, and cold extremities.

To treat this Excess, the doctor guides the Cold Qi out of the body by way of St-36 and Sp-9 points, then projects Hot Yang Qi towards specific channel points on the patient's body, such as CV-12 and St-25.

DIAGNOSING YIN AND YANG IN THE BODY

Every person has both Yin and Yang elements, but will tend to be predominantly one or the other in terms of personality, physique, life-style pref-



In cases of Excess, the doctor should Purge.

In cases of Deficiency, the doctor should Tonify.

In cases of Excess and Deficieny combined, the doctor should Regulate.

Figure 21.5. Yin and Yang Energetic Diagnosis

erences, speech patterns, mannerisms, etc. Within a general constitution there will be more subtle fluctuations within the Yin/Yang continuum as the body reacts to external and internal energetic movements. In designing the patient's exercise program, diet, or herbal remedies, it is necessary to first determine whether the patient is predominantly Yin or Yang in constitution.

YIN/YANG CONSTITUTION CHART

There are general indications that will help the doctor diagnose a patient's condition as predominantly Yin or predominantly Yang. The patient's basic Yin/Yang constitution, and an analysis of the current Yin/Yang balance of the body will play an important role in determining the type of exercise and the time of day that it will be performed. In most cases, a Yang condition should be balanced by a Yin exercise and vice versa.

There are varying levels of disharmony in the patient's body. Yin and Yang are only relative terms, and they are often not enough to adequately describe the character of the body's condition. Other factors such as Hot - Cold, Deficient - Excess, Internal - External must be considered in more detail. Yin and Yang are never in a permanent state; there is always dynamic movement. All relationships based on Yin/Yang are relative, and their mutual interaction must be considered.

Yin and Yang theory is valuable because it provides a tool for understanding the patient's constitution at a given point in time. This information enables the doctor to determine the best course of treatment, including exercise, food, or herbal formulas that the patient's body needs. Consideration of the patient's inherited and acquired attributes (developed through diet and life-style, environmental influences, natural energy cycles, and other miscellaneous influences such as sleep, work conditions, and relationships) should be based on observation and contemplation of the patient's physical, mental, emotional, and spiritual state of mind.

Designing a program to establish balance and harmony requires a keen awareness of energetic and mental states. In evaluating the patient's condition the doctor takes into account the location and nature of the disharmony, the severity of the condition and the overall physical, mental, and emotional condition of the patient (Figure 21.6). Furthermore, the doctor may notice a combination of both Yin and Yang symptoms or any of the other contrasting pairs be they Hot/Cold, Internal/External, Excess/Deficient. A combination of such symptoms creates a challenge when diagnosing a patient, since symptoms and indicators tend to be more extreme in a person who is ill (Figure 21.7).

YIN CONDITIONS

Primary Yang generates primary Yin. Everything in the universe needs support from Yin. On a basic level, Yin conditions in the body tend to be Cold, internal, Deficient, and degenerative in nature. If a condition becomes overly Yin, it may express some Hot or Yang symptoms. Extreme cold in the form of snow, for example, can cause frostbite. This is called a "false Yang" condition because the condition created is manifested as Yang instead of Yin.

Type of Sign	Yin	Yang
General	• Cool skin temperature • Pale, dark, dull, or yellow complexion • Cold hands and feet • Aversion to cold • Discomfort relieved by warmth and pressure • Senses dull • Curled lying posture	• Warm skin temperature • Red, oily, shiny complexion • Warm hands and feet • Aversion to heat and pressure • Five senses strong • Stretching posture in sleep
Diet	• Prefers warm food and drinks • Poor appetite • Poor sense of taste • Indigestion	• Prefers cold drinks and cold food • Strong appetite • Thirsty, dry mouth
Energy	• Tired • Weak	• Forceful, restless • Strong, stout
Behavior	• Underactive • Quiet, withdrawn	• Overactive • Noisy, outgoing
Breathing & Voice	• Weak, shallow breathing • Weak voice, quiet	• Deep, heavy breathing • Loud, coarse voice, talkative
Excretion	• Copious clear urine • Watery stool	• Scanty dark urine • Hard solid stool
Reproduction	• Sexually underactive • Scanty, pale menses • White leukorrhea	• Sexually overactive • Profuse, red menses • Yellow leukorrhea
Pulse	• Deep, slow • Empty, weak • Fine	• Superficial, rapid • Full, strong • Flooding
Tongue	• Pale, fat body • Moist, thin white coat	• Red, solid, sharp body • Dry, thick yellow coat

Figure 21.6 Signs of Yin and Yang Conditions

Yin conditions are typically characterized by the following: watery stool, clear and copious urine; depression; pale, dull, and yellow complexion; weak, tired, and thin constitution; cool skin, cold hands and feet; dulled senses; curled lying posture when sleeping; soft voice; silent, shallow breathing; preference for warm food; and a tendency towards indigestion. A Yin condition will also be reflected in a deep, weak, fine, slow, or sluggish pulse and a fat, pale, moist, and smooth tongue with possibly a white coating.

YANG CONDITIONS

Yang conditions tend to be Hot, External and Excessive. A Yang disease is generative. Under cer-

Attribute	Progression from Extreme Yang to Extreme Yin
Spirit	Aggressive, outgoing, joyful, sad, fearful, anxious, depressed (The degree of outward expression determines the yangness of the spirit, not so much the emotion itself.)
Body Type	Large and muscular, normal build, thin, emaciated
Posture	Stiff, erect, relaxed, hunched over, limp
Activity	Very animated, normally active, little movement, still
Respiration	Heavy and loud, loud sighing and stretching, breathing heavily through mouth, shallow light breathing, soft intermittent sighs
Voice	Loud, rough, high pitched, regulated and moderate, soft, murmuring, almost inaudible
Skin Cast	Red, yellow, green, pink, white
White of Eye	Red, yellow, blue-green, pink, white
Lip Color	Red, yellow, blue-green, pink, white
Moistness of Lips	Cracked, dry, moist, overly wet
Sputum	Yellow and thick, white and thick, thin, clear
Smell of Breath	Strong, mild, faint
Body Odor	Strong, mild, faint
Urine	Thick, yellow, smelly, thin, whitish, no odor
Feces	Dark, strong smelling, soft, loose, light color

Figure 21.7. The Continuum of Yin and Yang Constitutional Signs and Symptoms

tain conditions, an overabundance of Heat (Yang) may transform into Cold (Yin) to bring about a condition known as "false Yin." Extreme heat and sun, for example, can cause sunstroke. This is called a "false Yin" condition because the condition created manifests as Yin instead of Yang. If an acute Yang condition persists, it will become Yin.

Yang conditions are typically characterized by the following: hard, solid, dry stool; thick, yellow urine; outwardly excited appearance; strong, stout, muscular constitution; restless, active, irritable in character; warm hands and feet and overall warm skin and temperature; strong senses; tendency to stretch frequently; loud voice, talkative; heavy breathing; thirsty, dry mouth; and a preference for cold drinks. A Yang condition will also reflect a floating, flooding, fast, or strong pulse, and a red or yellow, solid, dry tongue with cracks and little or no coating.

SIGNS OF YIN AND YANG

Determining true from false Yang may seem confusing. Yin Deficient people who are very thin and emaciated are often quite hypertensive, this can be seen in their excessive loud talking, rest-



Figure 21.8. The Nine Regions of Pulse Diagnosis

lessness and insomnia. Such individuals can also develop erratically feverish symptoms which usually change from Hot to Cold.

Generally, a true Yin or Yang condition is determined by three or more symptoms that simultaneously manifest either one of those conditions.

False Yin symptoms occur when the Yang becomes overly strong, causing a weakening of the Yin. (Again, the overall condition should be assessed before making a differential diagnosis.) False Yin symptoms include weakness, coldness, wetness, and other Yin symptoms in an otherwise Yang condition. One should bear in mind that there are seldom purely Yin or Yang symptoms because Yin and Yang are so interdependent on each other.

Furthermore, stages of Yin and Yang may change during the course of the day, or over the course of an illness. If a Yang stage is allowed to progress, it can degenerate into weakness described as a Yin stage. Therefore, if a Yang condition changes to Yin it is probably not a good sign, but if a Yin condition changes to an acute Yang condition it may be a positive sign of movement towards overall balance. The focus is to understand that it takes active energy (Yang) to manifest an acute condition, and the stronger the manifestation, the stronger the energy.

YIN AND YANG CATEGORIZATION OF TRAINING

Chinese herbs and foods are typically classified in terms of Yin and Yang, as are Qigong exercises and meditations. With exercises and meditations the state of mind and level of relaxation during the exercise or meditation is critical in determining the Yin or Yang categorization. It is important to be aware of this when developing a patient's program to provide the proper energy adjustments to maintain a healthy balance. If a disharmonious condition develops and the wrong prescription is given, the patient can be thrown further off balance, making it more difficult to restore good health.

PULSE DIAGNOSIS OF THE EIGHT ENERGETIC PRINCIPLES

The body's pulse in considered another form of energy manifestation. The pulse is imagined as waves of various Fluids flowing within the body, originating from within the Heart, where the Shen resides. Pulse diagnosis can give the Qigong doctor detailed information on the state of the patient's internal organs, as it reflects the patient's flow of Qi and Blood, as well as Yin and Yang energy. The pulse is felt at the radial artery, which is divided into three areas (front, middle, and lower), and at three different levels (superficial, middle, and deep), creating "nine regions" of pulse diagnosis (Figure 21.8).

The three areas of the wrist relate to the energetic manifestations of the Triple Burners. The front position corresponds to Heaven and reflects the diseases from the head to the chest; the middle position corresponds to Man and reflects the diseases



Figure 21.9. Pulse Correspondence with the Triple Burners

from the diaphragm to the umbilicus; the lower position corresponds to Earth and reflects the diseases from the umbilicus to the feet (Figure 21.9).

The three different levels relate to the energetic manifestations of the body's diseases. The superficial level corresponds to exterior diseases, the body's Qi and Yang organ energy; the middle level corresponds to the condition of the Blood, as well as the energy of the Stomach and Spleen; the lower level corresponds to interior diseases, the body's Yin energy and Yin organ energy.

The important thing is to diagnose how the body's energy is flowing, taking into consideration the relationship of the Yin and Yang on the pulse, i.e., whether it is superficial or deep, fast, or slow, Excess or Deficient. The quality of the pulse may also vary according to the patient's:

1. General Constitution and Body Build, with bigger frame patients generally having a stronger pulse then smaller frame individuals,
2. Level of Activity, with patients who engage in heavy physical work having a stronger pulse then those who engage in mental work, and
3. Exposure to Seasonal Weather, as a deeper pulse is generally felt in the winter and a more superficial pulse is felt in the summer.

PULSE QUALITIES AND CLASSIFICATIONS

In China, attention is placed primarily on the overall quality of the pulse. While reading the superficial pulses, it is important to note that they indicate the condition of the patient's Qi and Yang Organs. The deep pulses indicate the condition of the patient's Jing, and Yin Organs. Pulses can be divided into three main classifications, which are related to either Yin and Yang qualities: The Depth, The Speed, and The Strength (Figure 21.10).

1. The Depth at which the pulse can be felt is considered first.
    a. Superficial/Floating Pulses are felt with a light touch, barely touching the artery. They indicate an Exterior syndrome (e.g., Wind-Cold or Wind-Heat), chronic illness, or a general weakness. This informs the doctor that there is an Excess at the patient's Qi level (or a Deficiency at the Yin level).

- Superficial and Weak (Empty) pulses are felt in Yang Excess diseases (superficial diseases), when the patient's Wei Qi is fighting the pathogenic factors at the superficial level.
- Superficial and Forceful (Full) pulses are felt in interior diseases due to Yin or Jing Deficiency.

    b. Deep Pulses are felt on heavy pressure, near the bone. They indicate an interior syndrome (problems within the Yin Organs), and relate to the patient's Jing.

- Deep and Weak (Empty) pulses are felt in diseases due to a Deficiency of Qi and Yang.
- Deep and Forceful (Full) pulses are felt in deep diseases (when the disease has penetrated into the patient's internal organs). They confirm an Excess at the Yin level, or Deficiency at the Qi level, and point to a stasis of Qi or Blood, and to a Cold or Heat condition.

2. The Speed of the pulse is considered next.
    a. Slow Pulses are less then 4 beats per the patient's breath; they indicate a Cold syndrome.

- Slow and Weak (Empty) pulses indicate Empty Cold and Yang Deficiency.
- Slow and Forceful (Full) pulses indicate Full Cold and Yin Excess.

    b. Rapid Pulses are more then 5 beats per patient's breath and indicate a Heat syndrome.

- Rapid and Weak (Empty) pulses indicate Empty Heat and Yin Deficiency.
- Rapid and Forceful (Full) pulses indicate Full Heat and Yang Excess.

	YANG	YIN
DEPTH	Superficial — Exterior	Deep — Interior
SPEED	Rapid — Hot	Slow — Cold
STRENGTH	Forceful — Excess	Weak — Deficient

Figure 21.10. The Eight Energetic Principles are manifested through the body's pulses.

	LEFT HAND **Superficial - Deep**	**RIGHT HAND** **Superficial - Deep**
FRONT POSITION	Small Intestine - Heart	Large Intestine - Lungs
MIDDLE POSITION	Gall Bladder - Liver	Stomach - Spleen
LOWER POSITION	Bladder - Kidneys' Yin	TB & Pc - Kidneys' Yang

Figure 21.11. Left and Right Hand Correspondence

3. The Strength of the pulse is considered last.
    a. Weak (Empty) Pulses are weak and disappear on heavy pressure; they indicate a Deficient syndrome.
    b. Forceful (Full) Pulses are forceful and are felt on deep pressure; they indicate an Excess syndrome.

- Forceful (Full) and rapid pulses indicate Full Heat.
- Forceful (Full) and slow pulses indicate Full Cold.

THE CLASSICAL PULSE DIAGNOSTIC POSITIONS AND DEPTH

Traditionally the best time to take the patient's pulse is when the patient is calm and relaxed. There are several schools of pulse diagnosis, each one with its own specific methods of approach to understanding the patient's symptoms. The most important aspect in listening to the patient's pulse is to feel the strength, quality, and spirit of the pulse. Only then can the doctor receive accurate information about his patient's condition (Figure 21.11).

Pattern	Signs	Pulse	Tongue
Internal	Vomitting, high fever, gradual onset, chronic, long duration	Deep	Changes in texture and coating
External	Cold, flu, skin eruptions, sudden onset, acute, short duration	Superficial	Changes in coating
Cold	Diminished physiological function, decreased energy, lowered resistance, lowered immunity, white face, aversion to cold, cold extremities, lack of thirst, craving for warmth, clear urine, watery stool, desire for hot drinks, diarrhea, coolness of limbs, timid behavior, soft voice, slow movement, lack of motivation	Slow, tight	White coat, pale body, moist fur
Heat	Physiological hyperfunction, increased energy, increased metabolism, acute pains, fever, thirst, desire for cold liquids, flushed face, red eyes, restlessness, irritabiliity, dry stool, dark yellow urine, reduced urine secretions, aversion to warmth, hot red skin, constipation, warm extremities, loud voice, talkative, extroverted manner, aggressive behavior	Rapid	Red tongue with yellow fur
Deficiency	Great weakness, low syptomatic reactions, inconsistent energy, shallow and rapid respiration, less severe pain, pain characterised by soreness, weak or inconsistent voice, dull menstrual pain, withered face, low spirits, abdominal pain	Empty, weak	Little or no coat
Excess	Flushed face, loud voice, coarse and full breathing, sharp and acute pain, extreme menstrual pain, tender abdomen, condition worsens with apllication of heat	Full	Thick coat

Figure 21.12. Signs of Internal, External Cold, Hot, Deficient and Excess Conditions

Usually, in men, the pulse on the left (Yang) side of the body should be slightly stronger then that of the pulse on the right (Yin) side, and vice versa for women. Also in men, the front (Yang) positions should be slightly stronger, while in women the lower (Yin) positions should be stronger.

OVERVIEW

In the clinic we have a saying, "Where the Qi goes, the Blood flows." Although a patient's pulse is produced by the movement of Blood in the arteries, the activity of that movement is initiated by the force of the patient's Qi. By feeling the movement of Blood in the vessels, the activity of the patient's Qi, Blood, and Body Fluids are diagnosed. This internal communication is summarized in the above chart (Figure 21.12).

CHAPTER 22
DIAGNOSIS ACCORDING TO QI, BLOOD, AND BODY FLUID DYSFUNCTIONS

INTRODUCTION

This method of diagnosis identifies patterns on the basis of disharmonies according to Qi, Blood, and Body Fluids. It is used in clinical practice (especially for internal diseases) for diagnosing according to the pathological changes occurring in the internal organs.

The essential cause of disease is due to an imbalance of Qi, Blood, or Body Fluids. When one or more of these substances are unbalanced, the body's normal physiological function is disrupted and sickness results. This can be caused by the effect of the Six Exogenous Pathogenic Factors, Seven Emotional Pathogenic Factors, and is influenced by the patient's general constitution. Each of the patient's organs and channels have sets of symptoms or syndromes of these types of imbalances, which can then be identified for treatment. The Qigong doctor's ability to identify problems based on the pathological manifestations of Qi, Blood, and Body Fluids is founded on clinical observations of Excess, Deficient, Stagnant, and Rebellious patterns (Figure 22.1). These patterns can be further defined as predominantly Yin or Yang. These patterns also described as the various disorders of Qi, Blood, and Body Fluids, and sometimes overlap, for example:

- Excess conditions can give rise to Rebellious Qi and also create stagnation;
- Deficient conditions can give rise to Rebellious Qi and also create stagnation.

DISORDERS OF THE QI

Whenever energy movement is impeded, disorders in Qi functions occur. Generally, these dis-



Figure 22.1. Pathological Manifestations of Qi, Blood, and Body Fluids

Fire		**Water**
Constraint of Qi	**First Stage**	Stasis of Qi
Arrogant/Agitated	**Second Stage**	Fluid Builds Up
Full on Fire is Created	**Third Stage**	Phlegm is Created
Heart Fire is Created	**Final Stage** ——> Mania <——	Phlegm Fire is Created

Figure 22.2. Disorders caused from the obstruction of Qi flow result in either Fire or Water energetic dysfunctions.

turbances cause either disorders of Fire, or disorders of Water (Figure 22.2).

The cause and progression to these disorders can be further broken down and classified according to their energetic dysfunction (Figure 22.3). There are several types of Qi disorders observed in the clinic and are generally described as follows.

LEAKAGE AND LOSS OF QI

During or after the training practice, the patient may feel that Qi is continuously and uncontrollably leaking out of the body from the genitalia and anus or anywhere else on the body. This loss of Qi can lead to Qi Deficiencies, and manifest through the following symptoms: emaciation, weakness of the limbs, grayish and dull complexion, nervousness, mental disturbances, distractibility, failing memory, spontaneous sweating, night sweats, seminal emission, insomnia, lassitude, and sluggishness.

DEFICIENT QI DISORDERS

Deficient Qi exists when the entire body, or particular organ, is not being sufficiently nourished by the Qi. This results in there being too little energy to maintain proper organ function. This condition is usually caused by a weakness of the Lungs, Spleen, or Kidneys, by chronic illness, or a weak constitution, poor diet, or fatigue. Deficient Qi is unable to:

- transform, resulting in symptoms such as diarrhea,
- transport, resulting in symptoms such as stagnation of Qi,
- hold, resulting in symptoms such as bruising,
- warm, resulting in symptoms such as cold extremities,
- protect, resulting in symptoms such as sickness, and
- raise, resulting in symptoms such as prolapse.

Deficient Qi is divided into three subcategories from which the patient can suffer. These subcategories are Empty Qi, Sinking Qi, and Qi Collapse. Each of these subdivisions can further be divided into Yin and Yang types.

1. Empty Qi is considered the first type of Deficiency. If not treated, Deficient Qi may progress to a condition known as Empty Qi. Diseases that are classified as Empty Qi are characterized by a serious weakness or Deficiency of the body's Qi. Empty Qi, especially Empty Yang Qi manifests as a weakness


Turbidity flowing against the course of the channels
Turbidity flowing with the course of the channels
Deficient Rebellious Qi
Excess Rebellious Qi
Turbid Qi
Rebellious Qi Disorders
Excess Qi Disorders
Disorders of Qi
Qi Stagnation
Deficient Qi Disorders
Qi and Blood Stagnation
Obstructed Qi
Empty Yang Qi
Empty Qi
Wind Obstruction
Sinking Qi
Cold Obstruction
Qi Collapse
Damp Obstruction
Heat Obstruction
Collapse of Yang
Collapse of Yin

Figure 22.3. Whenever energy movement is impeded or in excess, disorders in Qi function occur, resulting in Qi Deviations.

in the function of holding, moving, and transforming Qi.

   a. Empty Qi originates primarily from the patient's constitution and manifests as malnutrition, fatigue, premature signs of old age, and an excess of extreme emotions.
   b. Empty Yang Qi belongs to the category of Yang. Because Yang Qi has the function of warming, Empty Yang manifests as an inability to adequately warm the energy, resulting in Cold symptoms. Empty Yang is generally caused by a weak constitution, poor diet (excessive raw, cold food and drink), overwork, old age, and excess sex.

2. Qi Sinking is also a subcategory of Deficient Qi, and is considered the second type of Deficiency. If not treated, Empty Qi may progress to a more serious Deficient condition known as Qi Sinking. This condition results in symptoms such as tiredness, listlessness, and mental depression, and may eventually lead to the prolapse of one or more of the organs.
3. Qi Collapse is a subcategory of Deficient Qi and is considered the third and most severe type of Deficiency. A Qi collapse exists when the Qi is so Deficient that it can no longer hold the internal organs in place. This Qi depletion not only causes a weakness of the body's Righteous Qi, which leads to the prolapse of the organs (Stomach, uterus, intestines, rectal area, vagina, or Bladder), but also induces prolonged diarrhea, upper abdominal distention, and dizziness.
   a. The Collapse of Yin results in pure Fire. The main manifestations are abundant perspiration and external tissue, which is hot to the touch.
   b. The Collapse of Yang results in pure Cold. The main manifestations are chills and external tissues which are cold to the touch.

EXCESS QI DISORDERS

An Excess Qi condition is caused from too much Qi, which overacts on an organ, affecting its function, and usually produces too much transformation and Heat in a given organ. This can be due to over-energizing the organs and channels, from excessive Qigong exercises and meditations, or too much energy stimulation during a Qigong doctor's treatment.

QI STAGNATION DISORDERS

Qi stagnation exists when the Qi is not flowing smoothly, and becomes sluggish when moving within the body's channels, organs, or tissues. Qi stagnation can be caused by many different factors such as: suppressed emotions, trauma, contraction of microorganisms, poor diet, and weak digestion. Qi stagnation, over time, results in localized pain, distention, cysts, tumors, etc. Qi stagnation disorders have two subcategories: Qi and Blood Stasis, and Obstructed Qi.

1. Qi and Blood Stasis refers to the sensation of local pain, heaviness, soreness, distention, and compression, which are caused by the stagnant Qi and Blood in certain areas of the body. These sensations do not disappear by themselves. This stasis may occur during or after Medical Qigong training practice from Qi disorders and visceral malfunctions.
2. Obstructed Qi is also considered a subcategory of Qi stagnation, and exists when the Qi becomes so stagnant that it no longer flows. At this stage the Qi can not move the Blood. This can be caused by trauma, surgery, and acute Qi stagnation.

When Qi becomes obstructed inside the body, certain clinical manifestations result, such as:

- Cold Obstruction causes Qi to become fixed with local numbness that improves with heat;
- Damp Obstruction causes Qi to become fixed with local swelling;
- Heat Obstruction causes Qi to become inflamed, red, and swollen;
- Damp Heat Obstruction is a combination of Damp and Heat. It is called "summer Damp Heat," and results in poor appetite, dizziness, diarrhea, heaviness of the head, and sensations of chest suffocation;
- Wind Obstruction causes migrating pain that moves from joint to joint.

Organ	Normal Flow	Rebellious Flow	Symptoms
Liver	Upwards	Excessively Upwards Horizontally to Stomach Horizontally to Spleen Horizontally to Intestines Downwards	Dizziness, Headache, Irritation Nausea, Belching, Vomiting Diarrhea Dry Stool Burning Urination
Heart	Downwards	Upwards	Insomnia, Mental Restlessness
Spleen	Upwards	Downwards	Diarrhea, Prolapse of Organs
Stomach	Downwards	Upwards	Hiccup, Nausea, Belching, Vomiting
Lungs	Downwards	Upwards	Coughing, Asthma
Kidneys	Downwards	Upwards	Asthma

Figure 22.4. Chart of Rebellious Qi Flow

REBELLIOUS QI DISORDERS

Rebellious Qi disorders manifest as Qi flowing in the wrong direction (a direction different from its normal physiological progression); this causes a disturbance within the harmonious flow of energy and affects the organs' functions. The symptoms have to be analyzed according to the internal organ which is involved. There are two types of Rebellious Qi, the Excess and Deficient type. Rebellious Qi is categorized as follows:

DISORDERS OF EXCESS REBELLIOUS QI

Disorders of Excess Rebellious Qi occur when the vital Qi increases and forces the pathogenic Qi to move; leading to local sensations of pain, soreness, distention, heaviness, cold or heat, which can develop during a patient's Qigong practice (Figure 22.4).

DISORDERS OF DEFICIENT REBELLIOUS QI

Disorders of Deficient Rebellious Qi refers to the disorderly flow of Qi and Blood during or after the training practice, which causes dizziness, fright, a heavy feeling in the chest, shortness of breath, shaking limbs, trembling of the hands and feet, or fainting. Generally, energy sensitive patients know the location and direction of the disorderly flow of Qi in their tissues.

TURBID QI

While transforming and transporting energy, the body divides ingested and absorbed Qi into Clear and Turbid energy for distribution (keeping and redistributing the clean, while disposing of the turbid). Turbid Qi refers to any dark, murky energy which can originate within, or from outside of the body's organ system, and sometimes travels throughout the body's channel system. Turbid Qi attaches to the body's wounds (physical, emotional, or spiritual), manifesting as dark, discolored clouds of energy. This energy can adversely affect the body's physical, emotional, and energetic balance, especially when combined with any pathogenic internal or external factor.

PATHOGENIC SENSING OF TURBID QI

Feeling the sensations of Turbid Qi is referred to as "pathogenic sensing." This skill is acquired by the doctor while projecting energy to his patients. While emitting energy, the Qigong doctor can sense the patient's Yuan Qi, as well as the Turbid Qi inside the patient's body. This enables the doctor to diagnose and treat their patients' diseases according to the various Qi sensations, and to categorize the patients' Turbid Qi. The Turbid Qi is also called Evil or "pathogenic Qi." The flow of Turbid Qi within the patient's channels is characterized as follows:

- Turbidity flowing with the course of the channel indicates transference of Turbid Qi towards the body's interior.
- Turbidity flowing against the course of the channel indicates the beginning production of Turbid Qi.

Turbid Qi differs from the pathogenic factors of infectious diseases referred to in Western medicine. According to clinical experience, the pathogenic sense of Turbid Qi can be classified as: Dry or Hot Sensations, Cold or Chilly Sensations, Soreness or Numbing Sensations, Impure or Foul Sensations, The Sensations of The Seven Emotions, and The Sensations of The Six Climate Conditions.

1. Dry or Hot Sensations are considered Yang signs or symptoms of Heat. This type of Turbid Qi feels feverish and flaccid; it can cause perspiration, irritation, etc. The sensations of dry-heat on the body or hands of the doctor often cause the doctor to fidget, as if being scorched by a fire. It may also serve as an indicator of syndromes of Excess Heat and hyperactivity of Fire due to a Yin Deficiency.
2. Cold or Chilly Sensations are considered Yin signs or symptoms of Cold. This type of Turbid Qi feels cold, rigid, and stagnant. It may be so cold that the doctor's fingertips turn cold immediately. This coldness transmits from the doctor's fingertips upward, causing shivering and contractions of the sweat glands ("goose-bumps"). This gives the doctor a particular feeling of cold and discomfort. Cold feelings often serve as a message of Deficiency and Cold syndromes such as rheumatism, rheumatoid disease, Deficiency of the Kidney Yang, and certain types of cancer.
3. Soreness or Numbing Sensation often indicate syndromes of hyperactivity of the Liver Yang and Excess of Wind, Cold, Dampness or Phlegm, as well as arthralgia syndrome and cancer. The doctor may experience an uncomfortable feeling of local soreness or pain, heaviness, numbness, tingling and itching.
4. Impure or Foul Sensations can be felt when the doctor is standing opposite the patient, or when extending energy towards the patient. It is an indescribable unpleasant feeling that is often felt when the open palm and fingers are used to detect a disease.
5. The Seven Emotions (joy, anger, worry, anxiety, fear, shock, and grief) in excess will cause discomfort to the doctor. During treatment, the doctor may detect and feel the different natures of these emotional pathogenic Evils flowing through the doctor's body. The doctor may, for example, have a specific feeling of anger if the disorder of the patient is due to excessive anger. Once these pathogenic emotions are discovered, the doctor must purge or disperse them, as well as determine their origin, and cause.
6. The Six Climate Conditions (Wind, Cold, Summer Heat, Dampness, Dryness, and Fire) will also cause discomfort to the doctor. During treatment, the doctor may detect and feel the different natures of these pathogenic Evils. The doctor may, for example, have a specific feeling of slippery wet ooze if the disorder of the patient is due to Dampness.

RECTIFYING QI DISORDERS

The primary treatment principles for rectifying Qi Disorders are as follows:

- for Qi leakage - tonify
- for Deficient Qi - tonify
- for Empty Qi - tonify
- for Qi sinking - raise and tonify
- for Collapsed Qi - tonify
- for Excess Qi - reduce
- for Stagnant Qi - move
- for Obstructed Qi - move
- for Rebellious Qi - calm and subdue
- for Turbid Qi - remove, dredge, and purge

These are often found in combination with other patterns. Here are some examples of treating combined patterns:

- for Excess and Rebellious Qi, reduce Excess and calm Rebellious Qi;
- for Deficient and Rebellious Qi, tonify Deficient and calm Rebellious Qi;



Figure 22.5. Whenever Blood movement is impeded or in excess, disorders in Blood function occur.

- for Excess and Stagnant Qi, reduce Excess and move the Stagnant Qi;
- for Deficient and Stagnant Qi, tonify Deficient and move the Stagnant Qi;
- for Excess and Deficient Qi, drain Excess and tonify Deficient Qi; and
- for Rebellious and Stagnant Qi, calm Rebellious and move the Stagnant Qi.

DISORDERS OF THE BLOOD

To understand Blood disorders it is important to understand the concept of Blood from the perspective of Traditional Chinese Medicine. In Chinese Medicine, Blood is different in concept, characteristics and function from that of Western medicine. Blood originates from the transformation of food and drink by the Spleen, which then transfers the refined food energy (Gu Qi) to be further enhanced by the Heart, Lungs, and air energy. Blood is therefore considered a transformation of constructive energies.

Disorders of the Blood can relate to disorders of the Qi. Qi and Blood flow together, Qi being the active force which makes the Blood circulate and keeps it within the blood vessels. Both Qi and Blood flow within the channels and blood vessels, continuously circulating throughout the body nourishing, maintaining, and moistening the tissues. Qi is an energetic form and is considered a Yang substance, while Blood is a liquid form of energy and considered a Yin substance. The cause and progression to Blood disorders can be further broken down and classified according to their energetic dysfunction (Figure 22.5). There are several types of Blood disorders observed in the clinic and are generally described as follows.

DEFICIENCY OF BLOOD

A Deficiency of Blood exists when the entire body, or a particular organ, is insufficiently nourished by the Blood, or not enough Blood is present to nourish the organs and channels, to support the Qi. Blood Deficiency is usually caused from Blood loss, chronic illness, poor diet, or Spleen Qi Deficiency, which weakens the Qi. This in turn affects the Liver (causing symptoms of dizziness, blurred vision, and numbness) and Heart (causing symptoms effecting the mind, memory, and Shen).

LOSS OF BLOOD

Loss of Blood is considered a subcategory of Deficient Blood. Loss of Blood is caused by Spleen Qi failing to control the Blood, resulting in the Blood spilling out of the vessels and organs, etc. Loss of Blood is divided into two main types:

- Deficient loss of Blood is caused by an insufficiency of Qi to hold the Blood.
- Excess loss of Blood, is caused by either Blood-Heat pushing the Blood out of the vessels, or by Blood stagnation and Yin Deficiency which causes the Blood to pool.

EMPTY BLOOD

Although Empty Blood is a subcategory of Deficient Blood, it is considered a serious Deficient condition, mostly due to the Blood of the whole body becoming Deficient. Empty Blood corresponds to a Deficiency of Qi, caused by:

- Inadequate nutrition,
- Loss of Blood through accident or disease,
- Loss of Body Fluids through excessive sweating, urination, vomiting, or diarrhea,
- Extreme emotions (e.g., rage, terror and shock),
- Blood stagnation, which leads to poor Blood circulation.

Since the Empty Blood fails to nourish the tendons and muscles, it results in shaking in the extremities and head, dizziness, and blurred vision.

Empty Yin

Blood belongs to the category of Yin. Because Yin Qi has the function of cooling and moistening, when an Empty Yin condition is present, the symptoms manifest as Excess Heat and Dryness. Empty Yin is caused by a weak constitution and a poor diet (overcooked foods and hot liquids). The organs most likely to be effected by the Empty Yin condition are the Kidneys, Lungs, Heart, Liver, and Stomach.

BLOOD STAGNATION

Blood Stasis exists when the Blood is unable to flow smoothly, and becomes obstructed or congeals. Blood stasis is usually caused by an impact trauma, Deficient Blood, stagnant Blood, Blood Heat, Blood Cold, or stagnant Qi. It results in localized pain which worsens with pressure, swelling of the internal organs, cysts, and tumors. The organ most often affected by Blood stasis is the Liver.

BLOOD HEAT

Blood Heat is mostly due to Liver Heat and External Wind. When toxic Heat enters the Blood, the Blood may break out of the vessels and cause: nose bleeding, hemorrhaging, and broken blood vessels. Heat consumes the Blood and Yin, injuring the tendons and muscles, causing spasms and rigidity. The Blood Heat also injures the Governing Vessel, Pericardium, and the Shen.

The Four Main Treatment Principles

- for a Deficiency of Blood, tonify
- for Empty Blood, tonify
- for Blood Stasis, move Stasis
- for Blood Heat, cool down

THREE DISORDERS OF BODY FLUIDS

To understand disorders of the Body Fluids it is important to understand the concept of Body Fluids, from the perspective of Traditional Chinese Medicine. Body Fluids are a denser form of Qi, and depend on Qi for transformation and transportation. Qi occupies and directs the movement of Blood and Body Fluids. The function of the Fluids is to moisten and nourish the body's tissues, as well as thin the Blood to prevent stasis. Body Fluids are formed from ingested food and drink, and are then transported by the energy of the Spleen to the Lungs and Small Intestines for distribution.

Disorders of the Body Fluids can relate to disorders of the Blood. There is a constant interchange between Fluids and Blood, such as, for example, a Deficiency of Fluids can be developed from a heavy loss of Blood. Body Fluids are divided into two categories:



Figure 22.6. Whenever Body Fluid movement is impeded or in excess, disorders in Body Fluid function occur.

1. Jin refers to the light, thin, watery, clear, quick-moving Fluids and is considered Yang. These Fluids are under the control of the Lungs which circulate them with the Wei Qi. These Fluids also permeate and moisten the skin and have the function of warming and nourishing the muscles. The Upper Burner is responsible for controlling the Jin transformation and moving it towards the skin. The Jin is manifested in the body in the form of sweat, tears, saliva, mucus, and parotid serum.
2. Ye refers to the heavier, thicker, turbid, dense, slow moving Fluids and is considered Yin. These Fluids are under the control of the Middle and Lower Burners, which circulate the Ye with the Ying Qi. The Spleen and Kidneys are responsible for controlling the Ye transformation. This Fluid lubricates the joint cavities (synovial fluid), nourishes and lubricates the brain and spinal cord (cerebrospinal fluid), bone marrow and the orifices of the sensory organs (eyes, ears, nose, and mouth).

There are three primary disorders of Body Fluids observed in the clinic, they are described as follows (Figure 22.6).

1. Deficient Body Fluids exists when the entire body, or a particular organ, is insufficiently nourished by Body Fluids. This is generally due to insufficient Yin to create or nourish the body's organs or joints. Deficient Body Fluids are usually caused by prolonged loss of Fluids (sweating, diarrhea, and vomiting), prolonged illness, a Heat condition, or a Yin Deficiency which leads to Dryness. A Deficiency of Body Fluids usually affects the Lungs, Kidneys, Stomach, and Large Intestines.
2. Excess Body Fluid accumulation is usually caused by an Excess Yin and one of three factors, or a combination of all of them. They are:
   - A Lung Qi Deficiency, which affects the top of the body, face and hands,
   - A Spleen Qi Deficiency, which affects the middle part of the body, and abdomen,
   - A Kidney Qi Deficiency, which affects the lower part of the body, legs and ankles.

   If there is a Deficiency within one or all three of these organs, and the Body Fluid is not able to transform properly, it will overflow the channels and settle under the skin.
3. Retention of Phlegm is due primarily to a Deficiency of the Spleen failing to transport

and transform the Body Fluids. If Phlegm is retained for long periods of time, disease of the organs (Substantial Phlegm), as well as channels, skin, and joints (Non-Substantial Phlegm), can form.

The Three Main Treatment Principles

- for Deficient Body Fluids, moisten;
- for Excess Body Fluids, dry or drain;
- for Retention of Phlegm, resolve.

TYPES OF PHLEGM

The concept of Phlegm is an important pathological and etiological factor in Traditional Chinese Medicine. If Phlegm is allowed to accumulate and becomes retained within the body, it causes disease.

The main cause of Phlegm formation is Spleen Deficiency. If the Spleen becomes weak and fails to transform and transport the Body Fluids, these will accumulate and transform into Phlegm. However, Phlegm formation can also occur if the Lungs fail to disperse and lower Fluids, or if the Kidneys fail to transform and excrete Fluids.

In Traditional Chinese Medicine, there are two types of Phlegm: Substantial Phlegm and Non-Substantial Phlegm.

1. Substantial Phlegm is described in ancient texts as "having a form." It can be observed as the thick mucus that collects within the Lungs and spat out during bronchial infections and other Lung diseases. As the Lung disease progresses, the patient's mucus changes color, progressing from clear watery to yellow and thick, then to green and pussy, and finally brown and red.
2. Non-Substantial Phlegm is described in ancient texts as "having no form." This type of Phlegm can accumulate within:

- the body's organs forming stones,
- the joints forming arthritic bone deformations,
- the skin forming lumps or cysts, and
- the channels causing stagnation of Qi and Blood, resulting in numbness.

Both Substantial and Non-Substantial Phlegm can assume different forms of disease, developing in accordance to its associations with Heat, Cold, Damp, Wind, Qi, and Fluids. For example:

1. Phlegm Heat is a type of Substantial Phlegm that affects the Lungs, Stomach, or Heart. It manifests as yellow sticky phlegm, a red face and a red tongue with sticky yellow coating.
2. Cold Phlegm is a type of Substantial Phlegm that affects the Lungs and Stomach. It manifests as white watery phlegm expectoration, cold feelings in the back and extremities, and a pale tongue with a white and wet coating.
3. Damp Phlegm is a type of Substantial Phlegm that affects the Lungs. It manifests as a profuse white sticky phlegm, feelings of stuffiness in the chest and epigastrium region, and a sticky tongue coating.
4. Wind Phlegm is a type of Non-Substantial Phlegm and is seen in Wind Stroke. It causes dizziness, nausea, vomiting, coughing up of Phlegm, numbness of the limbs, rattling throat, and aphasia.
5. Qi Phlegm is a type of Non-Substantial Phlegm which affects the throat. It manifests as a "plum pit" syndrome within the throat. Its formation is related to emotional problems, created when the Liver Qi rises and stagnates within the throat. Its condition manifests as a feeling of swelling in the throat, difficulty in swallowing, and stiffness in the chest and diaphragm.
6. Phlegm Fluids is a type of Substantial Phlegm which has a fluid or watery nature, and is called Yin in Chinese medicine. There are four types according to their location:

- Phlegm Fluids located in the Stomach and intestines manifest as abdominal fullness, distension, and vomiting;
- Phlegm Fluids located above the diaphragm manifest as coughing, asthma, edema, and dizziness;
- Phlegm Fluids located within the hypochondrium manifest as distension in the hypochondrium area, with pain and coughing;
- Phlegm Fluids located in the four limbs manifest as heaviness and pain in the muscles.

CHAPTER 23
DIAGNOSIS ACCORDING TO THE FIVE-ELEMENT THEORIES

INTRODUCTION TO THE FIVE ELEMENTS

This method of diagnosis is based on the interpretation of clinical manifestations according to the creative, controlling, invading, and insulting sequences of the Five Elements. The Five Elements are five phases of transition used in Chinese Medicine and are sometimes referred to as the Wu Xing. Wu translates to mean the number five, Xing translates to mean a process of movement or walking. The concept of the Five Elemental theory began to first appear in documents in China during the Zhou Dynasty (from 1000 to 770 B.C.). This theory classified tangible and intangible substances into five categories for observation and study, as well as diagnosis and treatments.

1. The Wood Element is associated with the active functions of birth in nature's growth stage of development.
2. The Fire Element is associated with maximum functional activity in nature's growth stage of development.
3. The Earth Element is associated with the function of stabilization in nature's growth stage of development.
4. The Metal Element is associated with nature's declining functions of the growth stage of development.
5. The Water Element is associated with the maximum state of rest in nature's growth stage of development.

The Five Elemental theory is used to explain the classifications and characteristics along with the laws of universal cycles (creating, controlling, invading and insulting). These interactions are studied today in Traditional Chinese Medicine to assist the doctor's diagnosis in comprehending the growth and development of the body's energetic anatomy, physiology, disease processes, and symptom development (Figure 23.1).



Figure 23.1 The Five Elements

THE FIVE ELEMENTS AND YIN AND YANG THEORY

It is important to understand the Five Elemental theory's energetic origin and its interaction with Yin and Yang Qi to appreciate its energetic categorizations.

The ancient Chinese Qigong masters believed that the creation, development, and declining transitions of all things throughout the universe were the result of the interaction of Yin and Yang Qi. The Yin and Yang theory was therefore used to describe the opposing, interdependent, as well as waxing and waning transitions of all things, especially the interactions of the Five Elements (Wood, Fire, Earth, Metal, and Water). Fire and Wood are considered active Yang elements, while Water and Metal are considered quiescent Yin elements. The Earth is considered a balance point between Yang and Yin.

Qigong doctors assign the Five Elements of Traditional Chinese Medicine to the body's organs and tissues. The Five Elements are considered the Jing of the body's Yin and Yang energy pools. Imagine each element organ as a pool of liquid energy. The energetic movement, much like water, flows from element to element. This flowing movement of liquid energy is considered to be the body's energetic pulse, moving Qi to and from these pools.

The rivers of Qi cannot exist without the pools of Jing to nourish their flow and function; and the pools of Jing cannot act without the rivers of Qi stimulating their action. Therefore the principle action of the Five Elements is the circulation of the Yin and Yang Qi.

The human body is like a living Taiji symbol (see Chapter 21). Its back channels are considered Yang; its front channels are considered Yin; and its center channel is contained through the energetic actions of the Taiji Pole. The Taiji Pole produces Yang Qi by the inhalation of life-force energy through the breath. When Yang Qi reaches its peak, it rests, while the Yin Qi begins to increase. When the Yin Qi reaches its peak and comes to rest, then the Yang Qi begins to increase once more. This continuous interaction of Yang energy with Yin energy produces and enhances within the body, the Five Elemental organ energies of the Liver (Wood), Heart (Fire), Spleen (Earth), Lungs (Metal), and Kidneys (Water).

The first stage of Qigong exercises and meditations create an energetic transformation which regulate, refine, and reduce these Five Elemental organ energies into two primary Yin and Yang energies known as Fire and Water Qi. The second stage of transformation consists of combining the Water and Fire energy into one union of Three Human Treasures (Jing, Qi, and Shen). This energetic transformation is responsible for "bringing 10,000 things into being" (Figure 23.2). In China, these meditation stages are used for exploring the stimulation of the energetic functions of the central nervous system, the peripheral nervous system, cardiovascular system, digestive system, reproductive system, etc.

The Five Elemental theory assists the Qigong doctor in examining the energetic correspondences for clinical evaluation. This is only one phase of clinical observation however, and should always be applied with the Yin and Yang theory.



Figure 23.2 Stages of Energetic Transformation

THE CREATIVE OR GENERATIVE CYCLE

Within every Qi cycle each element has two main aspects: it is either (1) creating or being created, or (2) restricting and / or being restricted. In the process of growth and development, both creative and restrictive patterns are needed. Without creation, growth would have no origin, and growth without restriction can create harm. The creative element is called the Mother, and the element created is called the Child. This is the "Mother and Child" relationship referred to in Traditional Chinese Medicine. The Creative Cycle is generally used for tonification, as the stimulation of one organ enhances the function of the next (Figure 23.3). The Five Elemental Creative Cycle and its organ correspondences are as follows.

1. The Liver's element is Wood, which is used to create the Heart's element Fire. The Liver is the Mother of the Heart, which is the Child. The Liver stores the Blood and Blood houses the Shen. If the Mother (Liver) becomes Stagnant, the Child's Heart (Shen) will suffer. Clinical manifestations include indecision, timidity, lack of courage, palpitations, and early morning insomnia.
2. The Heart's element is Fire, which is used to create the Spleen's element Earth. The Heart is the Mother of the Spleen. The Heart's Qi pushes the Blood, thereby helping the Spleen in its function of transporting. If the Mother (Heart) becomes stagnant, the Child (Spleen) will suffer, creating a Spleen Yang Deficiency. This is due to failure of Heart Fire in providing Heat to the Spleen. Clinical manifestations include chills, weakness in the limbs, and loose stools.
3. The Spleen's element is Earth, which is used to create the Lungs' element Metal. The Spleen is the Mother of the Lungs. The Spleen Qi provides Gu Qi (food energy from the Earth) to the Lungs where it combines with air (energy from Heaven) to form Gathering (Zong) Qi. If the Mother (Spleen) becomes Deficient, the Child (Lungs) will suffer, creating Phlegm which obstructs the Lungs. Clinical manifestations include Phlegm in the chest, coughing, and general weakness.



Figure 23.3 The Five Elemental Creative Cycle

4. The Lungs' element is Metal, which is used to create the Kidneys' element Water. The Lungs are the Mother of the Kidneys. The Lungs send Qi down to meet the Kidney Qi, as well as Fluids to nourish the Kidneys. If the Mother (Lungs) becomes stagnant, the Child (Kidneys) will suffer, due to the Kidneys not receiving enough Qi. Clinical manifestations include breathlessness, loss of voice, coughing, and asthma.
5. The Kidneys' element is Water, which is used to create the Liver's element Wood. The Kidneys are the Mother of the Liver. The Kidneys' Yin nourishes the Liver Blood. If the Mother (Kidneys) become Deficient, the Child (Liver) will suffer (i.e., Liver Yin Deficiency). Clinical manifestations include headaches, blurred vision, dizziness, and vertigo.

THE CONTROLLING OR RESTRICTIVE CYCLE

This is a condition in Traditional Chinese Medicine where one element brings under control, or restrains, a corresponding element, thus ensuring that a dynamic balance is maintained among the Five Elements. The element that restricts is considered successful, while the element being controlled is in check. It is commonly referred to as "the strong controlling the weak," and is generally used for sedation, to ensure that the Creative Cycle does not over-create and cause imbalances. The element prior to the Mother is commonly referred to as the Grandmother. In the Controlling Cycle, it is the Grandmother who controls the Child (Figure 23.4). The Five Elemental Controlling Cycle and its organ correspondences are explained as follows.

1. The Wood absorbs nutrients from the Earth, i.e., the Liver (Grandmother) controls the Spleen and its paired organ the Stomach (Child). Two of the Liver's energetic functions are to help the Stomach "rot and ripen" the food and the Spleen to transform and transport the Gu Qi.
2. The Earth restricts Water, i.e., the Spleen (Grandmother) controls the Kidneys (Child). Both the Spleen and Kidneys control the transformation of Body Fluids.
3. The Water extinguishes Fire, i.e., the Kidneys (Grandmother) control the Heart (Child). The energetic aspect of the Kidneys' Water controls the energetic balance of the Heart's Fire.
4. The Fire melts Metal, i.e., the Heart (Grandmother) controls the Lungs (Child). The Heart governs the Blood, while the Lungs govern Qi (both Qi and Blood mutually assist and nourish each other).
5. The Metal chops Wood, i.e., the Lungs (Grandmother) control the Liver (Child). If the Lungs' Qi is weak it will not descend thus allowing the Liver Qi to rise.



Figure 23.4. The Five Elemental Controlling Cycle

THE INVADING OR OVERACTING CYCLE

This is a condition in Traditional Chinese Medicine where an element overacts, overcontrols and invades, the element it is supposed to control (Figure 23.5). Instead of the role of checking and restraining, one element severely attacks another element, stealing Qi from its energetic pool. This is generally observed in cases of Excess or Deficiency conditions of the organs. The Five Elemental Overacting Cycle and its organ correspondences are as follows.

1. The Wood invades the Earth, i.e., the Liver (Grandmother) overcontrols the Spleen (Child) and its paired organ the Stomach. In the clinic, this is commonly called "Liver invading the Spleen." Clinical manifestations include hypochondriac and epigastric pain and distension, irritability, poor appetite, loose stool, and a green face color.
2. The Earth invades the Water, i.e., the Spleen (Grandmother) overcontrols the Kidneys (Child). This occurs when a Deficient Spleen fails to transform and transport Fluids. These Fluids accumulate and obstruct the Kidneys' function of transforming and excreting Fluids. Clinical manifestations include edema, difficulty urinating, and a yellow face color.
3. The Water invades the Fire, i.e., the Kidneys (Grandmother) overcontrol the Heart (Child). This pattern is almost never seen in clinical practice since the Kidneys are rarely in Excess.
4. The Fire invades the Metal, i.e., the Heart (Grandmother) overcontrols the Lungs (Child). This results in Full Heat in the Lungs.

Pulmonary disease can be caused by cardiac disorders, this is known as "Fire Overacting and Invading Metal." Clinical manifestations include cough with yellow sputum, a feeling of Hot sensations, and a red face color.

5. The Metal invades the Wood, i.e., the Lungs (Grandmother) overcontrols the Liver (Child). Clinical manifestations include irritability, a feeling of distension, fatigue, and a white face color.

THE INSULTING OR COUNTERACTING CYCLE

This is a condition in Traditional Chinese Medicine where the elements reverse their restrictive cycle and the Child insults the controlling element, the Grandmother (Figure 23.6). This is generally observed in cases of Excess or Deficiency within the Five Elements. The Five Elemental Insulting Cycle and its organ correspondences are as follows.

1. The Wood dulls the Metal ax, i.e., the Liver (Child) insults the Lungs (Grandmother). If the Child (Liver Qi or Liver Fire) becomes stagnant, it can obstruct and prevent the Lung's Qi (Grandmother) from descending. Clinical manifestations include coughing, a feeling of distension in the chest and hypochondrium area, and asthma. If pulmonary disease is due to the impairment of the Liver, it is explained as "Wood Insulting or Counteracting Metal."
2. The Metal controls the spread of Fire, i.e., the Lungs (Child) insult the Heart (Grandmother). If the Child becomes Deficient, it can cause the Heart Qi (Grandmother) to become Deficient. Clinical manifestations include palpitations, breathlessness and insomnia.
3. The Fire dries up the Water, i.e., the Heart (Child) insults the Kidneys (Grandmother). If the Grandmother (the Kidneys' Yin) becomes Deficient, then the Heart (Child) can become excessive, giving rise to Heart Empty Heat. Clinical manifestations include dizziness, lower back pain, night sweating, insomnia, malar flushes, and dry mouth (at night).
4. The Water erodes the Earth, i.e., the Kidneys



Figure 23.5 The Five Elemental Invading Cycle



Figure 23.6 The Five Elemental Insulting Cycle

(Child) insult the Spleen (Grandmother). In this case, the Child (the Kidneys' Yang) becomes Deficient causing the Grandmother (Spleen) to become Deficient. Clinical manifestations include weak limbs, fatigue, edema, and loose stools.

5. The Earth resists the Wooden plow, i.e., the Spleen (Child) insults the Liver (Grandmother). If the Spleen (Child) fails to transform Fluids, a Damp condition can result. This Dampness can accumulate and begin to obstruct the flow of the Liver's Qi (Grandmother). Clinical manifestations include hypochondriac pain and distension, bile obstruction, and jaundice.

THE FIVE ELEMENTAL TONIFICATION CYCLE

The Five Elemental tonification cycle can be used for balancing the life-force energy of the body in conjunction with nature. Wood corresponds to spring, Fire corresponds to summer, Metal corresponds to autumn, Water corresponds to winter, and Earth corresponds to the late stage of each season (late spring, late summer, late autumn and late winter). The element Earth is centrally placed, associated with the 18 days of transformation at the end of each of the four seasons. The object of using the Five Elemental Tonification Cycle is to support and strengthen the next organ in the cycle (Figure 23.7).



Figure 23.7 The Five Elemental Tonification Cycle

FIVE YIN ENERGETIC ORGAN MANIFESTATIONS

The Five Elemental energies are manifested through five different directions of movement. The Qigong doctor studies the movements and actions of a patient while they are in a meditative state (usually a sitting or standing posture), to diagnose their energetic disposition. After being in a meditative state for awhile, the patient's organs will overflow with Qi. When the organs overflow with Qi, certain physical reactions are evident, indicating which particular element has a problem.

1. Wood or Liver Qi is responsible for the dispersing effect of Qi, and is manifested by expansive outward movements in all directions, causing the body to sway with gentle and soft motions. When the Liver's energy is overabundant the torso makes a gentle, soft movement like a pine tree swaying in the wind. This is caused by the sprouting and branching manifestation of the Liver Qi's rising warm current.
2. When Fire or Heart Qi is overabundant, it is evident through the physical manifestation of the upward ascending actions of the torso caused by the flaring up of Yang Heat. This affects the energetic body and is manifested by upward movements and sometimes jerky actions (like a flame crackling in a fire).
3. Earth or Spleen Qi is generally manifested by stable movements, however, when overabundant, it is evident through movements that are both smooth and swift. This allows the body to progress in a limber, flexible, and free moving action (think of the body movement similar to a spinning ball).
4. When Metal or Lung Qi is overabundant, it is evident through the twitching actions of the torso and is manifested by contracted, inward movements, causing the body to violently jerk from side to side (think of the body as a metal bell being violently struck).
5. When Water or Kidney Qi is overabundant, it

is evident through the clumsy, awkward, heavy downward moving action of the torso (think of a waterfall descending onto rocks).

When the patient's body, unintentionally or unconsciously, rocks or sways gently as a result of a meditative state, the patient does not feel tired upon completing the meditation. However, when a patient consciously tries to force relaxation or augment the movement of his or her body while meditating, he or she will be tired by the end of the meditative session.

Note: While interning at the Medical Qigong Ward at the Xi Yuan Hospital in China, I found it fascinating to observe meditating patients displaying the results of both energetic organ manifestations or consciously induced augmentation of movement. All the above listed energetic manifestations were evident.

CHAPTER 24
OTHER DIAGNOSTIC SYSTEMS AND TECHNIQUES

DIAGNOSIS ACCORDING TO THE SIX STAGES

This system of diagnosis was formulated by Dr. Zhang Zhong Jing in the early Han Dynasty. The application of the six stages of diagnosis provides the key link in treating febrile diseases which are due to an attack of Cold. The six stages are described as Tai Yang, Shao Yang, Yang Ming, Tai Yin, Shao Yin, and Jue Yin.

THE THREE YANG SYNDROMES

The signs and symptoms of these pathological changes result from attacks by exogenous factors, especially cold weather. The first three syndromes describe the pathological changes occurring in the six Yang organs and channels (Small Intestine, Bladder, Large Intestine, Stomach, Triple Burners and Gall Bladder), and are called the Three Yang Stages. In the Three Yang Stages, the pathogenic factors predominate, but the body's energy is still relatively strong. The major symptoms are signs of Heat, and the treatment is directed at eliminating the pathogenic factors. These are the external conditions which can progress from the superficial Tai Yang Stages to the deeper Shao Yang Stages.

1. The Tai Yang or Great Yang Stage affects Qi on the exterior surface of the body and all three Wei Qi levels. This energetic disturbance affects the Small Intestine and Bladder Channels and organs that govern the exterior of the body. Although they are the most superficial channels, they are very rich in Wei Qi.
   - Clinical Manifestations of an Attack of Cold include: Aversion to cold, stiff neck, headache, no sweating, fever, body aches, floating-tight pulse, and shortness of breath.

   The focus of the Qigong treatment is to first open the pores to eliminate pathogenic factors by purging and dispersing, followed by tonification of the Lungs.

   - Clinical Manifestations of an Attack of Wind include: Aversion to wind, stiff neck, sweating, body aches, floating pulse, and fever.

   The focus of the Qigong treatment is to first open the pores to eliminate pathogenic factors by purging and dispersing, then to relax the muscles for diaphoresis (profuse sweating) in order to regulate the Ying and Wei Qi, and finally to prescribe herbs (or refer out for herbal treatment).
2. The Shao Yang or Lesser Yang Stage affects the interior and exterior levels of the body equally. This energetic disturbance affects the Triple Burners and Gall Bladder organs and channels. The patient experiences an alteration of fever and chills with a fullness of the costal and hypochondriac regions, blurred vision, loss of appetite, irritability, and wiry pulse with a white-slippery tongue coating.

   The focus of the Qigong treatment is on dispersing Heat with purging techniques and promoting the production of Body Fluids using herbs.
3. The Yang Ming or Bright Yang Stage affects Qi at the interior level of the body. This energetic disturbance affects the Large Intestine and Stomach organs and channels. The pathogenic factors transform into Heat.
   - Clinical Manifestations of the Bright Yang Channel Stage include: Pure Interior Heat known as the Four Bigs (fever, thirst, sweating, and pulse). In addition the patient also experiences an aversion to heat and has a red tongue with a yellow coating.

   The focus of the Qigong treatment is on dispersing Heat with purging techniques and on promoting the production of Body Fluids through herbs.

   - Clinical Manifestations of the Bright Yang Organ Stage include: Interior Heat and the Four Bigs with constipation, profuse sweating, high fever which worsens in the afternoon, fullness and pain in the abdomen (which becomes worse if you press it), and a red tongue with a dry, yellow or black coating.

The focus of the Qigong treatment is on eliminating pathogenic factors with purging and dispersing techniques, and relieving constipation.

THE THREE YIN SYNDROMES

The second three syndromes are those of the Three Yin Channels. They are based on the pathological changes of the Six Yin Organs and channels (Lungs and Spleen, Heart and Kidneys, Pericardium and Liver). These syndromes are the reflection of pathological changes within the Yin and Yang organs, channels, and collaterals. In the three Yin stages, the pathogenic factors are still present but diminishing. The body's Qi has become weakened, and there are Deficient signs of Cold. The treatment is focused on strengthening the body's Qi. These are internal conditions that progress from the Tai Yin stages deeper into the body until they reach the Jue Yin stage.

1. The Tai Yin or Great Yin Stage affects the Yin organs, as the penetration of pathogenic factors flow deep into the energetic layers. This energetic disturbance affects the Lung and Spleen organs and channels, resulting in a Deficiency and Cold syndrome. The clinical manifestations are: Vomiting and diarrhea, abdominal fullness, absence of thirst, and a slow, deep pulse with a pale tongue.

   The focus of the Qigong treatment is on heating and energizing the Middle Burner and dispersing the Cold using herbs. It is also important to tonify the patient's organ Qi.
2. The Shao Yin or Lesser Yin Stage affects the Heart and Kidney organs and channels. Clinical manifestations are as follows:
   - The transformation of Cold Deficiency to Kidney Yang Deficiency: Aversion to cold, chills, cold limbs, diarrhea, listlessness, lethargy, abundant-pale urine, deep-fine pulse, and pale tongue.

     The focus of the Qigong treatment is on tonifying the patient's organ Qi, preventing the Yang from collapsing and treating with herbs.
   - The transformation of Heat Deficiency to Kidney Yin Deficiency: insomnia, fever, irritability, dry throat and mouth, scanty-dark urine, fine-rapid pulse, and a red tongue without coating.

     The Qigong treatment should focus on tonifying the patient's organ Qi, nourishing the Yin, and dispersing Fire using herbs.
3. The Jue Yin or Terminal Yin Stage affects the Pericardium and Liver organs and channels. This is the final stage of pathogenic invasion before the life-force energy vanishes altogether.

   Clinical manifestations are as follows: cold limbs, diarrhea, vomiting, pain, feeling of heat and energy expanding in the chest, and feeling of hunger with no desire to eat.

   The focus of the Qigong treatment is on purging, tonifying and regulating the patient's organ Qi. Applying Cold and Hot herbal medicines simultaneously can be used to drive out the patient's pathogenic factors and aid in purgation. Herbal tonics can also be used to increase the patient's resistance to pathogenic diseases and aid in tonification (Figure 24.1).

DIAGNOSIS ACCORDING TO THE FOUR LEVELS

This system of diagnosis was formulated by the famous Chinese physician, Dr. Ye Tian Shi in the late 1600's. These syndromes are used to explain the etiology and pathogenesis of febrile diseases. The differentiation of syndromes pertaining to the Four Levels of Diagnosis is concerned with febrile diseases caused by externally contracted Heat. Because exogenous diseases are always developing and changing, by studying the transmission of pathological changes the Qigong doctor is able to deduce the prognosis. These four levels are identified by four types of energy, and are classified as follows: The Wei Qi Level, Qi Level, Ying Qi Level, and Blood (Xue) Level.

1. At the Wei Qi Level (Protective Energy), the



Figure 24.1. The Six Stages of Pathogenic Invasion are illustrated here. The invasion of external pathogenic factors follows a systematic progression through the body's Six Levels of Qi.

1. The Great Yang Stage (Tai Yang)

Affects the Small Intestine and Bladder Organs and channels. At this stage the pathogens are at the superficial level of the body's Wei Qi, caused by an attack of Wind and/or Cold Invasion. This stage is considered an External Cold Invasion at the Wei Qi level.

2. The Lessor Yang Stage (Shao Yang)

Affects the Triple Burners and Gall Bladder Organs and channels. At this stage the pathogens are half Exterior and half Interior, flowing in and out of the body, causing alternating chills and fever. This stage is also considered an Internal condition at the Qi level.

3. The Bright Yang Stage (Yang Ming)

Affects the Large Intestine and Stomach Organs and channels. At this stage the pathogens absorb deeper into the body's tissues, transforming into Heat affecting the internal organs and/or channels. This stage is considered an Internal condition at the Qi level.

- Bright Yang Organ Stage: Results in Interior Heat with constipation.
- Bright Yang Channel Stage: Results in pure Internal Heat with "Four Bigs" (fever, thirst, sweating, and pulse).

4. The Great Yin Stage (Tai Yin)

Affects the Lungs and Spleen Organs and channels. At this stage the penetration of pathogenic factors flow deep into the energetic layers affecting the Yin organs, invading the Middle Burner (affecting the Spleen) causing a Deficient condition. This stage is considered an Internal condition at the Ying Qi level.

5. The Lesser Yin Stage (Shao Yin)

Affects the Heart and Kidney Organs and channels. At this stage the pathogenic factors transforms either into Cold or Heat, causing further Deficient conditions. This stage is also considered an Internal condition at the Ying Qi level.

- Pathogens will transform into Cold due to a Deficiency of Kidney Yang.
- Pathogens will transform into Heat due to a Deficiency of Kidney Yin.

6. The Terminal Yin Stage (Jue Yin)

Affects the Pericardium and Liver Organs and channels. At this stage the pathogenic factors continue to deplete the body's life-force energy. This is the final stage of pathogenic invasion before death occurs. This stage is also considered an Internal condition at the Blood level.

pathogenic Heat invades the outer level of Wei Qi, causing the human body to manifest certain disorders which are clinically observed as fever, aversion to wind and cold, excessive or absence of sweating, sore throat, coughing, headache, red tongue with thin coating, and a floating and rapid pulse.

The Qigong treatment should focus on dispersing pathogenic factors and tonifying the exterior by utilizing pungent tastes and cooling herbs. Points are generally selected from the Lungs, Large Intestine, and Bladder Channels, as well as from the Governing Vessel.

2. At the Qi Level, the pathogenic Heat continues to progress deeper into the body, attacking and affecting the Qi system. At this stage, the body system is still strong, but the normal functions of the Yin and Yang organs are impaired. Because of the different functions of the Yin and Yang organs the manifestations differ. The three conditions associated with this stage of pathogenic invasion are as follows:

- Heat in the chest and diaphragm is the first stage and is not considered a severe syndrome. The symptoms manifest as fever, burning sensation in the epigastrium, thirst, and a yellow coated tongue.

  The Qigong treatment should focus on dispersing pathogenic Heat accumulated in the chest and diaphragm.
- Heat in the Stomach Channel is the second stage, and is considered a more severe Heat syndrome. These symptoms manifest as Heat, thirst, a dry tongue with yellow coating, and a slippery, rapid pulse.

  The Qigong treatment should focus on purging pathogenic Heat, and tonifying the body's Fluids.
- Heat in the Lesser Yang Channel is considered the final stage of Qi invasion. This syndrome is similar to the Lesser Yang Stage of the Three Yang Syndromes (according to the Six Stages), except that there is Dampness.

  The Qigong treatment should focus on purging pathogenic Heat from the Lesser Yang Channel, dispelling Dampness and dispersing Phlegm.

3. At the Ying Qi Level (Nutritive Energy), the pathogenic factors have penetrated deeper to the level of the Ying Qi and the organs, the Blood, blood vessels, and the Heart are therefore all affected. The symptoms in this stage are generally caused by the burning up the Yin. Clinical manifestations include: irritability, insomnia, mental restlessness, fever that worsens at night, dry mouth, absence of thirst, faint skin eruptions, a deep red tongue with little or no coating, and a fine-rapid pulse.

   Focus the Qigong treatment on purging pathogenic Heat from the Ying Qi level, using dispersing techniques. As an auxiliary method, bleeding may be performed by pricking the Heart and Pericardium Channels, as well as the Governing Vessel.
4. The Blood (Xue) Level, is the deepest and final level of pathogenic invasion. This stage contains the most serious manifestations that the disease can cause. Clinical manifestations include: high fever, skin that is hot to touch, Bloody stool, vomiting of Blood, Blood in urine, delirium, skin eruptions of purple or black color, a deep red tongue, a fine-rapid pulse, and in severe cases convulsions.

   The Qigong treatment should focus on purging pathogenic Heat from the Blood using bloodletting techniques (points are mainly selected from the Heart, Pericardium, Liver, Stomach, and Large Intestine Channels, along with the Governing Vessel), Cool the Blood, relieve convulsions, calm the mind, and reduce pathogenic factors with herbs.

DIAGNOSIS ACCORDING TO THE TRIPLE BURNERS

This system of diagnosis was developed by the famous Chinese physician, Dr. Wu Ju-Tong in the late 1700's. This system is concerned with febrile diseases caused by externally-contracted Heat, invading the body's Triple Burners. This Heat syndrome generally proceeds from the Upper Burner to the Middle and ends up at the Lower Burner. However, in cases of diseases due to Damp Heat, the pathogenic invasion of Heat begins at the Middle Burner in the Spleen.

1. The Upper Burner encompasses the body from the top of the head to the diaphragm. This area includes the Heart, Lungs, Pericardium, throat and head, and is responsible for respiratory and cardiac functions. The Upper Burner moves the body's Clean Qi, circulating and distributing nutrients and Qi throughout the body like a mist.

   Clinical manifestations of diseases in the Upper Burner correspond to those of a pathogenic invasion of the Lungs and Pericardium.

   a. When Wind Heat invades the Lungs, it is either manifested at the Wei Qi level or deeper in the Lungs themselves. The symptoms include: fever, sweating, coughing, stiffness and pain in the chest, wheezing, thirst, a red tongue with a yellow coat, and a rapid pulse.
   b. When pathogenic Heat invades the Pericardium, it is manifested at the Wei Qi level. These symptoms include: fever, coldness of the limbs, delirium, aphasia, burning sensation in the epigastrium, and a deep red tongue with spots.

   The Qigong treatment should focus on purging pathogenic Heat and dispersing Phlegm.

2. The Middle Burner encompasses the area from the diaphragm to the umbilicus. This area includes the Stomach, Spleen, pancreas, and Gall Bladder and is responsible for digestion, fermentation, and transformation of food and drink into nutrients for distribution. It moves the body's energy, circulating it like a swamp.

   Manifestations of diseases in the Middle Burner from pathogenic Heat are divided into two syndromes: Heat in the Bright Yang and Damp Heat in the Spleen.

   a. Heat in the Bright Yang include: symptoms of interior Heat and the Four Bigs (severe excess fever, sweating, thirst, and pulse) with constipation, profuse sweating, high fever which worsens in the afternoon, fullness and pain in the abdomen (which becomes worse when pressure is applied), and a red tongue with a dry, yellow or black coating.
   b. Damp Heat in the Spleen include: symptoms that are identical to the early stages of diseases caused by externally-contracted Heat.

   The clinical manifestations include: aversion to cold, fever that worsens in the afternoon, a heavy sensation in the head, body and limbs, fullness of the chest and epigastrium, nausea and vomiting, a white, sticky tongue, and floating or slippery pulse.

   The Qigong treatment should focus on Heating the Middle Burner, tonifying any Deficiency, purging Dampness, and prescribing herbs.

3. The Lower Burner encompasses the area from the umbilicus to the feet. This area includes the Liver, Kidneys, Bladder, intestines, external genitalia for men, and the uterus for women. The Lower Burner is responsible for filtering and eliminating waste products and for reproductive functions. It moves the body's Turbid Qi, circulating it like a drainage ditch.

   Manifestations of diseases in the Lower Burner are caused from pathogenic Heat attacking the Kidneys or Liver and are divided into two syndromes:

   a. Invasion of the Kidneys by pathogenic Heat dries up the Kidneys' Yin causing Heat symptoms due to a Yin Deficiency. Clinical manifestations include: lingering fever, hot hands and feet, dryness of the mouth, deafness, lassitude, a red-peeled tongue, and a rapid, floating or empty pulse.

   Focus the Qigong treatment on tonifying Yin, and purging the Heat.

   b. Invasion of the Liver by Heat occurs after the Kidney Yin has been exhausted. A condition known as Liver Wind is created. Clinical manifestations include: low-grade fever, cold limbs, dry and cracked lips, convulsions and trembling, a dry, reddish-purple tongue, and a rapid-deep pulse.

   The Qigong treatment should focus on tonifying Yin, and purging the Heat and Wind.

CHAPTER 25
CLINICAL EXAMINATION AND DIAGNOSIS

SENSORY, INTUITIVE AND PERCEPTUAL DIAGNOSIS

Clinical diagnosis can be categorized into two primary methods of energetic examination and treatment: Sensory Diagnosis and Intuitive and Perceptual Diagnosis. The clinical methods of Sensory Diagnosis are quite prevalent throughout China, especially within the acupuncture, massage, and herbal clinics. The methods of Intuitive or Perceptual Diagnosis, however, have been kept secret for many years, and are primarily found only within the Medical Qigong clinics. The latter methods (Intuitive or Perceptual Diagnosis) will be explained later in this chapter.

The root of any disease can be drawn from its complex symptoms and signs, by using the two main methods of Sensory and Intuitive and Perceptual Diagnostic principles. These two main methods of diagnosis serve as guidelines for the Medical Qigong doctor in clinical evaluation. Once the cause and extent of the disease is known, a treatment plan can be developed. There are four main types of Qigong treatment, which are chosen according to the treatment goals:

- a routine treatment (basic or nonspecialized),
- a specialized treatment (designed for the specific patient and his or her condition),
- a treatment aimed at etiology, or
- a treatment focused on alleviating the symptoms and signs.

It is therefore important to determine and assess the cause (root) and the manifestations (branches) of the patient's disease.

SENSORY DIAGNOSIS

Before treatment begins, the Qigong doctor performs a clinical intake, examining and evaluating the patient's condition, using various methods of sensory diagnosis. This clinical format involves taking a history of the patient's complaints. Next the doctor inquires about the patient's medical history. The doctor then conducts an examination for diagnosis, and devises a treatment principle on which the treatment plan is based, before implementing the treatment.

CLINICAL INTAKE, EXAMINATION AND EVALUATION

It is important that the doctor clearly identify the patient's problem before any treatment may be given. Never treat a patient without first making a diagnosis. The diagnosis is developed from the doctor's sensory examination and is evaluated according to symptom observation.

Both the root (the source and cause of the disease) and its branches (the symptoms or manifestations of the disease) should be examined carefully before treating the patient. In the case of an emergency, the doctor may choose to treat the urgent symptom first before treating its source.

The diagnosis and treatment of each patient traditionally begins by observing the patient as a whole, followed by an evaluation of the patient's individual constitution. Next, the doctor observes the symptoms and syndromes of the individual's organs. From these observations the cause of the disease is determined and treatment is begun. The treatment usually focuses on addressing the cause of the disease, to return the organ or organ system back into harmony with the rest of the patient's body. This affects changes within the patient's constitution and returns him or her back to a normal state of health.

Sensory examination for diagnosis is divided into five primary methods: diagnosis by visual observation, diagnosis by listening, diagnosis by smelling, diagnosis by palpation, and diagnosis by questioning the patient. By looking, listening, smelling, touching, and asking the patient specific questions, a Qigong doctor is able to diagnose the patient's syndrome (this includes the etiology of the disease).

DIAGNOSIS BY VISUAL OBSERVATION

1. Observe the patient's Shen, overall appearance, spirit, emotional nature, energy field, and composure. Look at the Shen of the patient's face; a healthy patient should have a brightness or vibrant shininess to his or her countenance. The Shen of the face should be checked against the state of the patient's eyes.
2. Observe the patient's eyes, especially the spirit in their eyes -- the glitter or dullness, and the expression of a controlled or uncontrolled emotional state. The eyes manifest the Essence of all the organs, and are the messengers of the Heart. There are two things to look at in the eyes -- glitter and focus.
    a. Are the patient's eyes bright and do they glitter? The less the glitter, the more long-standing the emotional and mental problems. It is said that there are three emotions that make the eyes lack glitter: sadness, grief, and shock. If the patient's eyes are dull, it looks as if he or she is seeing through a mist or film.
    b. Are the eyes focused, is the attention sustained and penetrating or uncontrolled? Uncontrolled attention is actually worse then having no glitter. If the patient has unfocused eyes it means that there is an obstruction of the patient's Shen and mind, generally due to guilt, preoccupation, or anxiety. It is said that Excess joy makes the "eyes uncontrolled."
3. Observe the color of the patient's face, complexion, eyes, ears, nose, mouth, tongue, skin zones, and ask about the discharges (mucus, vaginal, urine, and stool). Anger manifests as a greenish tinge on the cheeks or forehead (if it is affecting the Stomach); worry manifests as a grayish color, pensiveness as a sallow complexion, fear as a white complexion (unless combined with Kidney Yin which turns the cheeks red). Shock creates a bluish tinge on the forehead. A change in the complexion often indicates a deeper and longer-standing psycho-emotional problem. Also, if the eyes show no Shen but the face does, it indicates a recent problem.
4. Observe the patient's body and any outstanding structural features. Are they thin, emaciated, obese, or paralyzed? Are there deviations or obstructions in or on the body, face, head, mouth, teeth-gums, eyes, nose, and ears? Are there blemishes on the skin? Observe the appearance of the nails, hair and so on.
5. Observe the way the patient moves. Do they shake and tremor? Are they rigid or loose? Notice if the movements are fast or slow, and so on. When you shake hands upon meeting for the first time, are his or her hands clammy or dry; is his or her grip strong or weak?
6. Observe the patient's tongue. Is it cracked, serrated, fat, thin, or thick? If you observe a central crack, the deeper it is, the more long-standing the emotional problem. A red tipped tongue can also indicate a Shen disturbance.
7. Observe the patient's channels and points. Are there darkened red blotches, blemishes, swelling, sweat, etc.?

DIAGNOSIS BY LISTENING

1. Listen to the patient's speech for slurring or clarity.
2. Listen to the patient's tone. Is it high, low, loud, or quiet?
3. Listen to the patient's tempo. Is it fast or slow?
4. Listen to the patient's words. Do they make sense? Are his or her thoughts well ordered, or does the patient change subjects abruptly and frequently (if so, the patient may be suffering from a severe mental disorder).
5. Listen to the patient's respiration. Is it loud, strong, weak, or wheezing?
6. Listen to the patient's cough. Is it loud, dry, or wet?
7. Listen to the patient's Stomach and Intestines. Are they gurgling or quiet?

DIAGNOSIS BY SMELLING

1. Does the patient smell strong, weak, or odorless? Does the patient smell of medications, or alcohol?
  - For Liver problems, the patient's body or breath will smell like a goat.
  - For Heart problems, the patient's body or breath will smell like something has been burnt.
  - For Spleen problems, the patient's body or breath will smell fragrant or sweet.
  - For Lung problems, the patient's body or breath will smell like fish or a tide pool.
  - For Kidney problems, the patient's body or breath will smell rotten.

DIAGNOSIS BY PALPATION

1. How does the patient's pulse feel? Is it strong or weak? The pulse shows more about the patient's Qi than the state of his or her Shen. Because the pulse reflects the short-term state of the patient's Qi, it should always be integrated with tongue and complexion diagnosis.
2. How do the patient's channels and points feel? Are there tender areas, movable nodules (Qi stagnation), or fixed nodules (Blood stagnation) along the patient's channels?
3. How does the patient's abdomen feel?

DIAGNOSIS BY QUESTIONING

1. Ask about the history of the patient's main complaint (illness, disorder, or injury).
  - When did it begin?
  - What other signs or symptoms accompany it?
  - Ask about the course of the illness, is it improving or getting worse?
  - What makes it better or worse (i.e., pressure, warmth, cold, and so on)?
  - What other treatments has he or she tried?
2. Ask about the patient's general medical history.
  - Has the patient had any surgeries?
  - Has the patient experienced any past or recent physical or emotional traumas?
  - Ask if the patient is on any medication(s).
  - Ask about self-medication with alcohol or drugs.
  - Ask about his or her current coffee, soft drink and sugar intake.
  - Ask about the patient's extremities, do they feel hot or cold?
  - Ask about his or her sweat.
  - Ask about his or her thirst.
  - Ask about his or her appetite and diet (how often does the patient eat, and how regular are the meals?).
  - Ask about his or her digestion (gas, belching, etc.).
  - Ask about his or her stool (loose, well formed, hot, smelly, cold, fishy, color, etc.).
  - Ask about his or her urine (frequency, urgency, and color).
  - Ask about his or her sleeping patterns (difficulty falling asleep, remaining asleep, or recurring nightmares).
  - Ask for an energetic self-evaluation on a scale of 1 to 10.
  - Ask about current emotional and mental problems or concerns.
  - Ask about his or her current physical exercise program.

EXAMINATION FOR DIAGNOSIS

There are certain general principles used by all doctors of Traditional Chinese Medicine to become proficient in diagnostic skills. In Medical Qigong therapy, becoming skilled and accurate in clinical diagnosis requires the Qigong doctor to become proficient in combining perceptual and mental skills with spiritual understandings and insights. The following is a thorough and systematic approach for arriving at an accurate diagnosis.

1. Record all information observed and gathered as meticulously and impartially as possible. When first encountering a patient, be open minded, but note all first impressions.
2. Organize all the information according to the Eight Energetic Principles or Five Elemental Theories.
  - When diagnosing according to the Eight Energetic Principles, the doctor should first determine whether the condition is Yin or Yang (chronic or acute), then classify the patient's

symptoms according to the condition's general location (External or Internal), followed by the disease's symptomatic appearance (Hot or Cold), and finally, the physio-energetic nature of the disease (Excess or Deficient condition).

Next, the Qigong doctor focuses on the Yin or Yang aspects of the patient's body, in terms of the physiological properties of the patient's disease, noting which is more affected, the Qi and Blood, Yin and Yang organs, etc.

The Qigong doctor then determines the precise depth and severity of the patient's disease, observing whether it is the patient's surface channels which are being affected, or the patient's internal organs. If it is determined that the condition is an internal problem, the Qigong doctor then differentiates the energetic level of penetration into the patient's body. This level of pathogenic penetration is diagnosed according to either the Six Stages, Four Levels, or the Triple Burners method of diagnosis.

- If the doctor is diagnosing according to the Five Elemental Theory, he or she should first determine the condition of the patient's pulse to assess which organ or organs are Excess or Deficient. The doctor must then decide whether the imbalance is attributed to either an individual internal organ or a combination of internal organs. If the patient's pulse does not match with the information gathered through the examination, the doctor must reconsider whether the patient's disorder will in fact conform to a Five Elemental pattern.

3. Evaluate all information: The doctor should evaluate the gathered information according to the patient's signs and symptoms, determining what is of primary and secondary importance. It is in this stage of evaluation that the Qigong doctor determines the "root and branch" of the patient's disease. If the disease is External in origin, the doctor determines what pathogenic factors are involved. If the disease is Internal in origin, the doctor determines whether the cause is emotional, hereditary, dietary, or an energetic charge remaining from a previous external disruption.

Finally, the doctor should determine whether the cause of the disease is still active within the patient's life. If it still is, the doctor must take this factor into consideration before treating the patient and prescribing homework.

DEVISING A TREATMENT PRINCIPLE

In devising a treatment principle, the Qigong doctor should always include the Condition of the disease, Location of the disease, and Possible Cause of the disease.

1. The Condition of the Disease refers to the categorization of the disease, and may be diagnosed according to a combination of the Eight Energetic Principle's criteria. The patient's condition could, for example, be considered Excess or Deficient, Hot or Cold, Internal or External, or a combination thereof, such as: Excess Heat, Internal Heat, Deficient Heat, etc.
2. The Location of the Disease refers to the physio-energetic level of the patient's body that the disease is affecting (whether it is in the Upper, Middle or Lower Burner, or affecting certain Yin or Yang organs, channels, or muscles, etc.).
3. The Possible Cause of the Disease is either a result from a congenital or acquired illness. If congenital, consider the patient's DNA patterns, and all hereditary and ancestral traits. If acquired, consider environmental exposure to toxic poisons, diet, trauma (physical or emotional), electromagnetic fields, etc.

TREATMENT STRATEGY

Once the working diagnosis and treatment principle has been established, it is time to determine a treatment strategy. A treatment strategy consist in applying the treatment principle. It is the foundation from which the Qigong doctor chooses the approach in treating the patient's disease (Figure 25.1). The doctor will choose to treat the internal organs, channels, collaterals, points, and tissue areas which are the primary cause of the patient's disease. These areas are specifically chosen in order to facilitate a rapid affect on the patient's disease, to purge, tonify, or regulate the tissue area.

TREATMENT

The treatment usually focuses on the specific cause of the disease and how it affects the patient's internal organs. The primary goal is to relieve the patient's symptoms, strengthen the constitution and return the patient to a state of wholeness. This process may involve restructuring the patient's belief structure, to emotionally release old traumas.

AFTER THE TREATMENT

After treating the patient's condition, the Qigong doctor explains to the patient in clear, comprehensive terminology, what the doctor has discovered, and his or her approach in rectifying the condition. The more the patient understands the


1. History of the Patient's Complaint
2. Patient's Medical History
3. Examination for Diagnosis
4. Treatment Principle
5. Treatment Plan
6. Treatment

Figure 25.1. Examination, Diagnosis, and Treatment: The Qigong doctor begins diagnosing the patient by taking a "history of the patient's complaint." Next the doctor inquires about the "patient's medical history." Then, the doctor begins the "examination for diagnosis," observing the patient's constitution, symptoms and signs and determines the syndrome(s), health and state of the patient's internal organs, and the cause of the energetic dysfunction. Next, all the acquired knowledge is assessed in accordance with the different diagnostic templates of the Eight Parameters, Five Elemental Theory, Qi, Blood and Body Fluid Dysfunctions, etc. and the doctor "devises a treatment principle." Before treating the disease the doctor "develops a treatment plan." The treatment focuses on the specific cause of the disease and how it affects the patient's internal organs. The primary goal is to relieve the patient's symptoms, strengthen the constitution and return the patient to a state of wholeness. This entire process is initiated to assist the Qigong doctor in prescribing the correct treatment.

doctor's diagnosis and approach in addressing the treatment, homework prescriptions, and suggestions for life-style modifications, the greater the likelihood of a successful healing.

After the initial treatment, it is important for the Qigong doctor to establish a treatment schedule. This establishes a realistic goal and time frame for the therapy. With each treatment, the doctor monitors the patient's progress, and may choose to modify the treatment approach in accord with the patient's changing condition.

As the patient's symptoms improve, the doctor lengthens the time between treatments. This continues until the symptoms are completely relieved, and the doctor is satisfied that the disease will not return.

ALTERNATIVE TREATMENT STRATEGIES

As the human body is in a constant state of change, the doctor's diagnosis and treatment approach will sometimes have to be altered. The doctor may also choose to modify each treatment according to the patient's changing symptoms or disease development. When choosing alternative treatment strategies, it is important that the doctor choose adjunctive therapies that enhance the primary goal of purging, tonifying, and regulating the patient's condition.

INTUITIVE AND PERCEPTUAL DIAGNOSIS

THE METAPHYSICAL DIMENSIONS OF MEDICAL QIGONG HEALING

The dictionary describes "metaphysical" as "the study of psychic phenomena beyond the limits of ordinary or orthodox psychology." There are other dimensions of reality that are very tangible, and access to them is only limited by fear and ignorance. Since theories on the nature of the mind and spirit cannot be easily verified or disproved by intellectual analysis or scientific experiment, sometimes certain kinds of knowledge are disbelieved, ridiculed, and dismissed. The advanced energy theories that are presented in this textbook are based upon the five thousand years of cultivation and experience of Chinese medical healing. The energetic form of Qi is neither good nor evil, it is simply another aspect of matter. The ancient Chinese Qigong masters refined the ability to analyze and diagnose these different forms of energy into an effective healing modality.

The existence of energy and its multidimensional patterns is embraced and accepted by many other cultures and societies, with the exception of Western conventional thinking, which is unfamiliar with this unorthodox approach to healing.

These energetic realms, which form the reality of the Medical Qigong doctor's clinical healings, are actually normal perceptional skills that the doctors have developed and trained within themselves. These doctors have simply rediscovered and trained their sensitivity to energies that they were open to during childhood. These energies encompass more then just the physical world. These perceptive skills and abilities of Shen are actually our natural, energetic "birthright," and have been with us since birth. Shen Gong skills, and all psychic powers, lie within the Eternal Soul of an individual, although in most people these skills are undeveloped and largely unused. Often we fear the most the things we understand the least. It has also been my observation that individuals are taught to ignore these skills because of one or more of the following reasons:

1. They have become frightened of them, because as children they were told that these abilities do not exist;
2. They were told that such abilities were evil, or of the 'devil';
3. Unable to understand them, they do not know how to integrate them into their personal lives;
4. They may fear the emotional and spiritual responsibility of knowing the truth about themselves and others; or
5. The known is familiar and therefore more comfortable then the unknown and new.

Sometimes even facing our own human potential alarms us so greatly (fear bordering on terror) that we are willing to deny empirical evidence that these paranormal skills and abilities are real.

We live, therefore, with a paradox. These paranormal abilities seem to be part of our nature, yet they can disturb us so greatly that we often violently reject them. Medical Qigong doctors are healers who have learned to accept these paranormal abilities and direct their energy, spirit and psychic skills towards the focus of alleviating pain and suffering. They are "wounded healers" who have learned to face their fears, and have the courage to walk through and overcome them.

THE AWAKENING

For the Qigong doctor to understand spiritual insights, three phases of energetic transformation must first be experienced. These three phases are collectively known as "the awakening" and are described as follows.

1. The awakening describes the beginning phase or "opening" of the Qigong doctors' Mind and Spirit to their energetic potential. This acceptance becomes rooted within the doctors' intention, emotion, and thought, and sets into motion the correct vibrational field for accessing their higher consciousness.
2. Entering the inner sanctuary describes the phase wherein Qigong doctors begin to receive greater clarity of mind and an elevated consciousness. The doctors receive information on a multidimensional level and are now able to access, as well as better understand their inner core being. This sets into motion the Qigong doctors' understanding of their interconnectedness to everything in the universe. At this point, the doctors must accept responsibility for their actions and non-actions.
3. Accessing the Wuji through the Creative Subconscious Mind describes the Qigong doctors' ability to access and reprogram their Mind and core vibration. This sets into motion the doctors' personal contact with their higher-self, or Eternal Soul.

LEARNING INTUITIVE AND PERCEPTUAL DIAGNOSIS

Before beginning the primary methods of Intuitive and Perceptual Energy Diagnosis, it is important to understand the initial training needed to access and train these skills. Without an understanding of these subtle energies, the risk of misdiagnosis of the microprojections of life-force energy is high. The subconscious mind communicates within ourselves and the outside world through the Three Dantians, by way of three distinct mechanisms:

- Physical or kinetic communication is established through the Lower Dantian.
- Emotional or empathic communication is established through the Middle Dantian.
- Spiritual or intuitive communication is established through the Upper Dantian.

These three modalities of energetic communication must be finely honed into effective, receptive listening tools.

Memories, thoughts, emotions, and knowledge are stored in the patient's tissues throughout the body at the pre-atomic and pre-cellular levels. They are arranged and structured similar to the way sounds and images are recorded on the magnetic molecules of a video cassette tape. Not only are emotions and sounds stored, but tastes, smells, and touch can be invoked simultaneously in vivid detail as the cells are stimulated. The patient feels that they are actually reliving the event from the past exactly as if it were occurring now.

The Qigong doctor must be ready to recognize, uncover, and be able to feel his or her patient's pain when interceding as an empath. Sometimes the doctor will not only stumble upon pockets of unresolved pain, but also suppressed memories hidden deep within the patient's tissues. When this occurs, the doctor diagnoses the patient's toxic emotional symptoms through his or her own body and spirit. To perform this type of diagnostic technique successfully, doctors must be secure in their established emotional boundaries. Otherwise they might project their own feelings onto the patient, or absorb the patient's pathogenic energy into their own body, where it may become trapped.

The goal is to absorb and receive the patient's symptoms briefly for diagnosis, and then release them by exhaling out the mouth (away from the patient). This expels the Toxic Qi into the ground, and allows the patient's feelings to pass through the doctor's body without harm.

The state of consciousness in which the doctor listens and feels the patient is more important than the technique or modality used. This is why there are so many diagnostic tools available to assist doctors in their evaluation. The patient's body maintains the energetic pattern of trauma until it is released and dispersed. The amount of energy required to neutralize this traumatic charge and return the tissues back to their normal state is in direct proportion to the intensity of the original trauma.

RECEIVING AND INTERPRETING THE PATIENT'S FIELDS OF BIO-INFORMATION

The human body emits several "bio-fields" of energy, varying in density and frequency and resonating within a holographic field. Like radio waves and other modern technological wave transmissions, these fields are encoded with information. The key to what we absorb and radiate lies in the energetic qualities of the rate or frequency of vibration, amplitude, and wave length of these bio-fields.

The physical world as we know it is made up of energetic fields. These energetic fields hold our universe together (Figure 25.2). Matter is simply the temporary expression of these energetic fields as they interact. The human body consists of Shen, Qi, and Jing actively resonating within the cells and tissues. Qi, as energy, is considered both substantial and insubstantial. Qi creates matter and acts as a medium between matter and spirit; it carries their mutual interactions in the form of waves. Because matter manifests as a distinctive type of consciousness, it operates at discreet levels of awareness, differing only in its complexity of structure and degree of freedom. Matter also manifests itself at every level of organization, from fundamental particles in physics, to biological organisms within the human body. The cells are governed by these bio-fields which determine their growth.

It is the conscious aspect of energy that dictates how, where and in what form energy is manifested within the body. This energetic consciousness releases bio-information which transmits encoded information about the patient both internally and externally. Form, force, and medium are three aspects of energy held in dynamic patterns by consciousness. The bio-information released from the patient's consciousness is read and diagnosed by the Qigong doctor before treatment begins.



Figure 25.2. The Energetic Fields

The body's bio-information resonation Xin Xi or the "message" as it is called in China, is not limited by space or time. This Message refers to the energy fields that emanate to and from the Wuji or Void (infinite space embodied in between matter and energy).

The Wuji is the state of no boundaries, of pure openness, of complete oneness. Its essence is emptiness (as depicted by the empty circle), which relates to the awareness aspect of our Yuan Shen. When it begins to manifest within the relative universe of Qi, Yin, and Yang (referred to as Taiji), its nature appears as clear light which dispels darkness. When it manifests as a pure and tangible physical form, it appears as an enlightened being (saint or immortal) or as the "divinity" inherent within each one of us.

All of these levels exist within each individual, on both a pure level and pathological level. These levels can be detected and interpreted by the trained Qigong doctor as bio-information resona-


The Body's Chemical and Electrical Messages Expressed through the Five Levels of Bio-information
1. Jing (form or tangible matter)
2. Qi (intangible energy)
3. Shen (spiritual energy)
4. Wuji (infinite space of the Void)
5. Dao (Divine Energy)

Figure 25.3. The Five Levels of Bio-information

nce. Bio-information resonance is subdivided into five levels of expression:

1. Jing (form or tangible matter) contains the least amount of encoded information which is emitted at the lowest frequency.
2. Qi (intangible energy) contains more encoded information which is emitted at a higher frequency than Jing.
3. Shen (spiritual energy) emits an even higher frequency containing still more encoded information than Qi.
4. Wuji (the infinite space of the Void) contains even more encoded information than Shen which is emitted at a still higher frequency.
5. Dao (Divine Energy) emits the highest, most complete encoded information or Message and is the most powerful of all the emissions.

Medical Qigong views congenital disease as a form of distorted bio-informational vibration. The body's cellular systems internally regulate themselves via communication through these coded Messages. Messages are sent and received both on the energetic level (Shen, Qi, and Jing) and on the biochemical-electrical level. These two different levels interact continuously. Distortions on the energetic level interfere with the necessary transformations of Jing into Qi, Qi into Shen, and vice versa. Failures in energetic transformations also affect and distort chemical and electrical Messages between the different types of cells in the body (blood cells, tissue cells, nerve cells, and so on).

The maturity of the physical body depends on the transference of these Messages as the source of its evolution. Each time the egg cell divides (morula, embryonic, and fetal stages) the Message is transcribed into the newly-generated cells. Some encoded Messages are transformed but, due to the adverse evolutionary conditions or pathogenic factors, some become latent. Germ cell Messages, however, are not restricted by these evolutionary conditions since they multiply, evolve, and transform at an accelerated pace.

Information of the body's disharmonies is received as a distorted, biological resonation, which indicates the location and severity of the patient's condition. All diagnostic scanning techniques utilize this type of perception. The body's cellular systems internally regulate themselves via communication through coded bio-informational signals. This biological information exists in energetic, electrical, and chemical forms which are constantly being transformed from one form into another (Figure 25.3). The function of Medical Qigong therapy is to provide the correct bio-informational instructions (or Message) to the patient's body in the form of Qi emission (or coded energetic bio-informational signals) to initiate healing. By receiving Messages from the patient, the Qigong doctor can project energy while receiving and diagnosing the patient's energetic patterns.

ACCESSING THE KNOWLEDGE STORED WITHIN THE WUJI

When the Qigong doctors emit healing energy to the patient, they are sending healing Messages encoded within the Qi. When these Messages are received by the patient's cells the healing process is initiated. Qigong doctors access the knowledge needed to treat patients, by remaining receptive to the Messages stored within the patient's Jing, Qi, Shen, and surrounding energetic space (Wuji or Void).

Within the energy of the Wuji is the knowledge stored throughout time. In Medical Qigong practices, accessing the knowledge of the Wuji is the Chinese equivalent of the Sanskrit concept of accessing the Akashic Records. "Akasha" is a Sanskrit term used to describe the all-pervasive space of the universe. There are two kinds of Void: the first type of Void is internal, limited by the material plane (or matter) and can be associated with the enveloping of the internal human form. Matter can be described as consisting of more space then actual physical matter and, therefore, is considered infinite in its internal division of energetic properties. Within this Void forms the foundation for the matter or the body's personality by way of physical forms, sensations, perceptions, mental formations, and consciousness.

The second type of Void is external, unlimited, beyond all description, unbound by the material, yet contains all things material. It is the vehicle for all life, resonating through sound and light, permeating everything in the universe. In the practice of Medical Qigong the Wuji is one of three universal principles, along with Qi and Shen, which form a trinity of sources of intuitive and psychic power. These three universal principles also manifest the Eternal Soul, allowing divine thought to infuse matter.

The knowledge of the Wuji records the vibrational resonance of every action (all thought and emotion), as well as light and sound. These energetic impressions are stored within the astral plane. These records exist as impressions in the astral/spiritual dimension, providing a sort of accessible filing system for those who wish to receive information about past history or past lives, or even for the examination of their own spiritual progress. Admittance to this sea of knowledge and wisdom can be triggered in the hypothalamic limbic system of the brain, and is accessible through the energetic stimulation of the third ventricle of the Qigong doctor's brain.

The body is composed of literally billions of energetic molecules. Each molecule is a hologram of ancestral particles, knowledge, and experiences existing throughout time, spanning our entire history as we know it. These molecules gather together to form and create matter. They function for specific purposes of life transitions and energetic interaction, and then dissolve, and transform back into Qi and Shen. Each molecule stores its energetic experiences, to be later accessed through spiritual intention.

As the molecules gather to form a fetus, energy as well as ancestral history is stored within the tissues and cells of the child via the environmental, universal, mother and father's energetic fields.

Once the Qigong doctor has fused with his or her patient, he or she will be able to access specific information about the patient through the internal connection to the energetic impressions of the patient's Void. This allows the doctor to study and learn about the patient's past history of disease formations, as well as the information contained within the molecular structures of the patient's tissues.

UNDERSTANDING PAST-LIFE REGRESSION

Although seldom talked about, and much less understood, the clinical significance about past-life regression is quite important. Psychiatrists Sigmund Freud and Carl G. Jung both believed that the patients' worst fears, pain, and traumas are buried deep within their unconscious mind. Sometimes the patients' emotional traumas are so deeply entrenched that they can only be expressed through the energetic presence of a different time-space reality. One metaphor used by patients to describe this other form of reality is through a "past-life trauma."

During Medical Qigong treatments, patients will sometimes describe traumas or situations that do not relate to present life experiences. These experiences might be explained through past life theories. There are six major theories used to explain past-life recall (Figure 25.4). These theories are described as follows.



Past-Life Regression

1. Projections of the wounded ego
2. Ancestral traits, inherited skills, and memories stored within the molecular structures, cells, and energetic prenatal Jing
3. External emotional histories from other people that have been absorbed into the subconscious mind
4. The spirit of a past individual's consciousness that has been absorbed into the body of the fetus upon conception
5. The spiritually recycled and refined Eternal Soul
6. A combination of some or all of the above theories

Figure 25.4. The Six Major Theories of Past Life Regression

1. Some Qigong doctors contend that these past-life memories are the projections of the patient's wounded ego, used by the subconscious mind to assist the patient in dealing indirectly and symbolically with life's present painful experiences. These are painful memories that are consciously avoided by the patient, but are necessary for healing to take place.
2. Other doctors believe that these past-life phenomena are the ancestral traits, inherited skills, and memories stored within the molecular structures, cells, and energetic Prenatal Jing of the patient, that periodically surface from time to time and generation to generation.
3. Some doctors believe that apparent memories of past-life regressions, as well as of past-life traumas, are external emotional histories from other people that have been absorbed into the patient's subconscious mind. The patient responds like an energetic empath to sensations of telepathy, registered by the patient's hypothalamic limbic system. These external memories are triggered when the patient accesses the knowledge of the Wuji.
4. Other doctors believe that the spirit of a past individual's consciousness can be absorbed into the body of the fetus upon conception. This means that wherever a child is conceived, the environmental energy, as well as any native hovering spiritual entity, can be implanted into the forming energetic field of the fetus.
5. Other doctors believe that one's Eternal Soul is constantly being recycled and refined through generation after generation, constantly being reborn in order to evolve into a higher plane of consciousness.
6. Still other doctors believe that past-life memories can be a combination of some or all of the above theories.

Some patients feel that they experience spontaneous past-life recall through the treatment of Medical Qigong therapy. While receiving treatments or performing Medical Qigong prescriptions these patients may experience intuitive flashes or visions. Whether the patients' memories actually are of their own historical past lives, or are reconstructions from subconscious material, is a matter of controversy. The primary objective is for the doctor to accept the patients' reality, supporting them in this belief system to facilitate their healing process.

It is the doctor's responsibility to respect the patient's reality and not impose his or her own interpretations on everything the patient says. By accessing the knowledge of the Wuji, the doctor can assist the patient to connect with and benefit from these past life recollections or "reconstructions" to facilitate the healing process. Ultimately it matters not if the memories are reconstructions of subconscious material, true past life events, or even telepathic experiences. What is important, however, is that these memories are processed, learned from, and integrated to promote a better balance within the patient.

PAST-LIFE HEALING THERAPY

Clinically, past-life regression therapy has been effective in treating such problems as chronic fears and phobias, detrimental habits and cravings, suppressed hostility and guilt, depression, the fear of death, sexual dysfunctions, chronic pains and headaches, as well as many physical disorders. It is also used for understanding relationship problems, since the theory maintains that we often meet the same souls in different lives (and bodies) until the problems are worked out.

The Qigong doctor is not qualified to perform past-life regression therapy. This requires a specialist or at least supervision by an expert. The Qigong doctor can, however, facilitate healing by accepting the patient's experience and validating it to prepare the way for the healing process. In Medical Qigong therapy, the doctor accepts the patient's belief that the causes of his or her present physical or psychological problems can be traced to past-life traumas or death experiences. The improvement attained through past-life memories is said to be achieved through the release of the energetic charge that is trapped in the patient's body from a former life. This energetic charge keeps the patient's emotions prisoner, chained to the old feelings that are associated with the painful past-life experience. It is important for the Qigong doctor to realize that the same therapeutic benefits as the retrieval of current-life real memories can be achieved by allowing the patient to relate any images, impressions and so on, that may or may not stem from his or her present life experiences. The foundational base of the emotional trauma will often be rooted in feelings associated with rejection, betrayal, and abandonment. The psychological and physiological reactions to the patient's past-life memories, whether they be real or contrived, will have a profound affect on the patient's healing.

LEARNING MEDICAL QIGONG TECHNIQUES

According to Qigong Master Zheng Zhan Ding from Beijing, China, when learning Medical Qigong techniques, the doctors experience what is known as the Three-Part Wisdoms.

1. The Upper Dantian Wisdom is achieved through divine calling. When the full potential of the Upper Dantian is tapped, the doctor suddenly finds him or herself able to utilize skills and techniques that were previously completely beyond his or her ability. This is a major energetic breakthrough for the doctor, enabling him or her to perform supernatural feats that he or she immediately recognizes and accepts as part of a personal spiritual calling.
2. The Middle Dantian Wisdom is achieved through inspirational observation. Upon seeing energetic techniques performed, the doctor immediately establishes an emotional belief that he or she possesses that same energetic ability. This is a kind of "if they can do it, I can do it" observation and belief structure.
3. The Lower Dantian Wisdom is achieved through practice. This is a type of "practice makes perfect" method of transition which allows the doctor time to accept and integrate new beliefs and abilities through long hours of constant practice, observation, and tutelage.

All Qigong techniques are based on the imagination and spiritual belief. It is necessary to create an image (a spiritual belief) within the mind, to create a positive environment for healing transformations (the spirit transforms energy, and energy transforms matter). Sometimes the Qigong doctor will want to utilize a certain image of his or her belief, but because of certain doubts, is unable to bring it into existence. In order to successfully cultivate this image, the doctor must use creative thinking to focus his or her life-force energy on this specific objective, accept it as true and know it will happen. To create this image the doctor must use his or her imagination, emotional feelings, unwavering belief, visualization, affirmation, and acceptance.

Energy (Qi) is the bridge between the material and the spiritual, and is the medium through which consciousness interacts with the world. Through intention, Qi is gathered, focused, and used to transform light, sound, and other resonations. Through intention, the Qigong doctor is able to change structural formations, and to transform tangible and intangible forms and vice versa, to dissolve tumors, cysts, and so on. Of the many methods of healing available in Medical Qigong, it is important for the Qigong doctor to explore the healing skills suited to his or her body and personality, to become most effective. Once the doctor has learned and mastered these healing techniques, he or she will no longer need to think about the methods, or when they need to be employed, they will become second nature.

PERCEPTUAL COMMUNICATION TRAINING

Subconscious communications are divided into physical, emotional, and intuitive forms of interaction and perception. The internal-vision techniques required to utilize energetic perception in a clinical setting are expressed and enhanced through these types of communication. These types of communications are realms of perception that can be explored, wherein, the Qigong doctor is so present in "the moment" that his or her attention begins to dissolve the perceptual realities of all five senses, and begins to perceive and diagnosis patients on a spiritual level. At this level, all feelings, sounds, colors, or any combination of the doctor's senses take on new dimensions of reality.

DIAGNOSIS THROUGH DANTIAN COMMUNICATION

Any treatment, exercise, or meditation the Qigong doctor prescribes must connect with the energetic resonation of the patient's disease. This connection is established through the doctor's ability to communicate with the patient's body via the Three Dantians.

1. The Upper Dantian's perceptional awareness is received through a type of spiritual/intuitive communication. Through this intuitive subconscious communication the doctor is able to interact and perceive the patient's spiritual and energetic disturbances. This allows the doctor to perceive the patient's spiritual condition without bias.
2. The Middle Dantian's perceptional awareness is received through a type of emotional/empathic communication. Through this empathic subconscious communication the doctor is able to interact and perceive the patient's feelings, actively empathizing, listening, and hearing what patients communicate about their pain and problems. This allows the doctor to perceive the patient's true emotional condition by bypassing the person's ego.
3. The Lower Dantian's perceptional awareness is received through a type of kinesthetic communication. Through this physical subconscious communication the doctor is able to interact and perceive the active condition of the patient's physical tissues. This allows the doctor to perceive (through his or her hands and physical body) the patient's physical symptoms, such as pain, Heat, and so on.

UTILIZING INTERNAL-VISION AS A CLINICAL MODALITY

The brain has the ability of receiving and recording the vibrations of any object that the senses see, hear, smell, taste or feel. The vibrations of light, sound, smell, color, and object's shape are all recorded. This also holds true for thoughts, words, and actions. The brain also has the ability of reproducing these vibrations and projecting them out again through the use of inner vision and the imagination.

Before beginning internal Qi diagnosis it is important that the Qigong doctor have a thorough understanding of the internal energy's function and flow within his or her own body. Dr. Li Shi Zhen pointed out during the Ming Dynasty that, "The internal organs and channels can be perceived as unobstructed and free from disease only by those who can see internally."

This is achieved by performing the Nei Guan or Internal Viewing Meditation. The purpose for internal-vision is to carefully examine, through conscious introspection, the energetic flow and structure of the body and mind. Most doctors in the Ming Dynasty studied the Nei Guan Meditation as part of their clinical practice to develop the light for internal viewing. It is believed that light enters the body through the Baihui Point (at the top of the head), the Yin Tang Point (the Third Eye area) and through both eyes. Since internal-vision uses light that has a higher vibration than visual light, it is able to penetrate through the skin deep into the tissues.

Many years ago I was truly skeptical of this phenomenon, although I met many Qigong masters who possessed such skills. After acquiring this skill, however, I was able to demonstrate its effectiveness quite thoroughly while interning in the Qigong hospitals of Beijing, China. It is actually a simple matter of consistent practice and focused concentration which allows this sense of perception to become tangible. It is important to remember that to know something, one must first think it, then feel it in order to integrate the knowledge fully. Always watch as an observer, void of emotional attachment, noticing what is actually there.

Nei Guan—Internal Viewing Meditation

The best way to practice the Nei Guan Meditation is through relaxed, quiescent breathing. Begin from a Wuji posture. After quieting the mind, relax and focus the imagination. Imagine that the left eye is a bright radiant sun, while the right eye is a bright and luminous moon. Both the sun and moon join together at the Yin Tang (Third Eye point). As their energies come together, they form a bright white ball. This light actually gathers around the pituitary gland, illuminating the optic chiasm, filling the occipital lobes (for internal perceptual vision) and the thalamus (for oculomotor control) (Figure 25.5).

As the light expands it stimulates the corpus callosum and penetrates the pineal gland (which acts as a projector for internal vision) (Figure 25.6).



Figure 25.5. The Internal Viewing Meditation

Next, focus your intention on directing this ball of white light, allowing it to shine down into the body, illuminating all the internal organs. This enables you to see directly inside your own body and view each organ. Observe and feel the energetic strengths and individual weaknesses of the bones, organs, and tissues. Allow both energy and information to gather and expose itself through the Third Eye region of the Upper Dantian. After a while, relax and return to Wu Wei (i.e., No Mind), allowing all of these images to settle.

After a relatively short time of constant practice Qigong doctors learn to discern the state of their own organs, and are able to regulate their own physical and energetic body. This internal diagnostic ability sets the foundation for doctors to extend their Internal-viewing capability outside their own body to use on patients.

Once this occurs, doctors find it possible to effectively diagnose patients while scanning and using the Flat Palm Detection technique. The patient's points and areas for diagnosis are revealed to the doctors through this modality of energetic extension.

When using internal-vision, extend your intention as deep into the patient as possible, to slowly scan the patient's tissues, layer after layer, observing any cellular changes and distortions. Use the internal light resonating from inside the patient's body to identify the pathogenic factors. Then, look deeper into the energetic currents to find the root and origin of the patient's disease.

When you use your hands to read the patient's internal organs through Flat Palm Detection or any other diagnostic modality, it is extremely important to use internal-vision to determine the severity of the disease. You may observe a specific color, texture, or feel pools of emotional energy. According to Dr. Zheng Zhang Ding, doctors will be able to determine the condition of the diseased organ by its shade of color. The internal-vision colors most commonly observed in internal-vision diagnosis are as follows:

- A red or yellow color represents a healthy or normal organ;
- A white color signals the beginning of energetic dysfunction, but is not serious enough for treatment;
- A gray color signifies sickness; and
- A black color denotes, tumors, cancer, etc.

APPLICATIONS OF INTUITIVE AND PERCEPTUAL QI DIAGNOSIS

There are a variety of methods concerning the application of intuitive and perceptual diagnosis of diseases. The specific physiological methods such as remote sensing, hand detection and physical body observation are very popular in the Medical Qigong clinics in China today. Five of the most favorite modalities of intuitive and perceptual Qi diagnosis are described as follows.



Figure 25.6. The inner light gathers at the pituitary gland, illuminating the optic chiasm, filling the occipital lobes and thalamus, stimulating the corpus callosum and penetrating the pineal gland.

DIAGNOSIS BASED ON FLAT-PALM DETECTION (HAND SENSING)

Because the body's energetic field reflects the state of health or dysfunctions of the physical body, any changes occurring in the tissues and organs are detectable through sensing this energetic field. Detection of these changes with the palm is termed Flat-Palm Detection.

To perform this technique, the doctor begins by asking the patient to take a standing, sitting or lying posture. The patient's whole body should be relaxed, the mind focused on breathing naturally. The doctor positions his or her palm several inches from the patient's energy field, with the Laogong Pc-8 point or fingertips facing the direction of the patient's body.

The doctor then emits a little energy, slowly, followed by Pushing, Pulling and Leading manipulations used to detect the Qi of the patient's energetic body. The patient's surface tissue is divided into upper and lower, left and right aspects. The doctor focuses on the surface tissue area first, specifically the area corresponding to the region of the patient's disease. The doctor then determines the energetic nature of the corresponding regions by making comparisons between the sensations gained in different areas to find where energy feels abnormal. Gradually, the doctor's emitted energy is extended deeper into the body to purge, disperse, tonify or regulate the patient's organs and organ systems (Figure 25.7).

The Qigong doctor then analyzes these energetic sensations, comparing how they feel from the different areas of the body (both on the superficial and deep layers). The doctor categorizes the pathological findings (the location, nature, and severity of the disease) in accordance with the Eight Principles of Diagnosis and the energetic patterns of The Five Elemental Theory.

Feeling a great difference in energy intensity between the two sides of the Stomach Channels, for example, indicates a Yin and Yang imbalance of energy circulation between the left and right sides of the body. The Deficiency and Cold syndrome of the Spleen and Stomach may be manifested by a cold and contracted sensation in the epigastric region.

When an acupuncture needle is inserted into an obstructed point the energy grabs the needle and vibrates it. Once this energy block is removed, the needle ceases to vibrate because the channel is now open. This same phenomenon occurs when the palm is placed on an area of stagnant Qi. The palm vibrates until the obstructed energy is dispersed.

Energy blocks are commonly cleared by dredging in a downward direction from the head (Heaven) to the feet (Earth). When treated this way, patients will experience a temporary feeling of fatigue as the stored toxins are released from the body. Tonification is facilitated by bringing the energy current up the patient's body from the feet to the head (Earth to Heaven). This action will sometimes cause patients to have psychic experiences and see visions, as the energy enters the patient's Upper Dantian region.



Figure 25.7. In Flat Palm Detection, the Qigong doctor uses the entire palm to sense the condition of his or her patient's internal organs and tissues.

DIAGNOSIS BASED ON KINESTHETIC AND EMPATHIC QI ABSORPTION

There are some individuals who tend to easily absorb the feeling and emotions of other people, even without trying. Sometimes when treating a patient, a Qigong doctor will inadvertently ingest a small amount of their patient's energy. As this energy absorbs into the doctor's body, it infuses throughout his or her entire energetic field. This energetic fusion sometimes causes the doctor to experience abnormal feelings in the locations that correspond to the pathogenic areas of the patient's body. From these feelings, the doctor can diagnose the location and the nature of the patient's disease.

To actively perform this method of Kinesthetic and Empathic Qi Absorption, the Qigong doctor stands facing the patient (Figure 25.8) and projects white healing light energy toward the top of the patient's head (Baihui GV-20 point). The patient is thus enveloped by the white healing light energy, from the top of the head, to the bottom of the feet. Next, the doctor directs the Qi to flow from the bottom of the patient's feet into the bottom of his or her own feet, absorbing the patient's energy. This energetic action forms a complete cycle of energy between the doctor and the patient's body. The Qigong doctor then begins to carefully feel the sensations of the patient's energy in his or her own tissues and organs. The locality of abnormal feelings, their shape, and/or prominent characteristics reflect the locality and nature of the patient's illness.

Note: It is generally encouraged to avoid this type of body detection on cancer patients, because the risk of pulling in the patient's excessively Hot pathogens into the doctor's body is too high, especially if the doctor's energy has become depleted.

HAND DIAGNOSIS BASED ON BODY ASSOCIATION

A small percentage of energy absorbed from the patient can suffice to diagnose the whole energetic system. Because the law of bio-holograms holds that one part of the body contains information about the whole (including various parts of the body, such as the viscera, Qi, and Blood, etc.), information obtained from certain isolated areas can reflect the condition of the whole body. Such parts may include the hand, foot, eye, ear, nose, face, etc. The location on these parts that represent different areas and organs are termed as "points" or "zones:" they include hand points, foot points, ear points, and so forth.

Hand diagnosis (called Shou Zhen) is used to evaluate the physical predispositions and ailments of patients. This diagnostic technique first appeared in Chinese medical literature during the Sui Dynasty (618-581 B.C.) from the clinical writings of Dr. Chao Yuan Fang, who authored the "General Treatise on the Origin and Symptoms of Various Diseases." To begin diagnosis through hand-body association, the Qigong doctor first neutralizes his or her left palm (by releasing the energy into the Earth) to balance and stabilize its sensitivity. The left hand is generally used for reviewing energy and diagnosing diseases.



Figure 25.8. In Diagnosis based on Kinesthetic or Empathic Absorption of the patient's Qi, the Qigong doctor temporarily absorbs the patient's energy field into his or her own body.

Once the left palm has been neutralized, the doctor uses his or her intention to gather the patient's Qi into the left palm, distributing the absorbed energy evenly throughout the hand. Focused concentration on any one specific area of the hand should be avoided. The doctor imagines the patient's energy enveloping the left hand and fingers, like an energetic glove. The doctor carefully begins to sense the sensations of the patient's energy on his or her palm. The center and front of the doctor's palm is considered the center and front of the patient's body, while the back of the hand is considered the back of the patient's body. The doctor feels various kinds of sensations on specific areas of the left palm, which indicate the location of the patient's disorders. These different sensations,



Figure 25.9. Diagnosis through Hand/Body Association

such as distention, heaviness, numbness, heat, cold, itching, and throbbing correspond with the features of the disorders (Figure 25.9).

While in Beijing, China, I was fortunate to study under Qigong Master Zheng Zhan Ding. Master Zheng had a remarkable gift for diagnosis and was compassionate enough to share his particular skills and training with me and two of my senior Medical Qigong students.

There are many schools of teaching for hand diagnosis. I have used several methods with great success in diagnosing and treating patients in both China and North America. The primary requirement for correct diagnosis is the use of the mind's intention. The imagination sets the foundation for the "energetic blueprint" of the patient's body (Figure 25.10). The method for employing this technique is described as follows.

1. Begin to scan the left palm and feel for Hot (Excess) or Cold (Deficient) areas. These areas will relate to specific locations of illness. The doctor begins to treat these regions of disease by using one of the following three methods:
    a. The doctor uses intention to tonify or purge the troubled areas inside his or her own left palm;
    b. The doctor uses his or her right hand (usually with the index and middle finger) to tonify or purge the energy from his or her left palm; or
    c. The doctor extends and treats the patient's body with his or her right hand while reading and diagnosing with the left palm.
2. Another variation of hand diagnosis is practiced by first having the patient breathe evenly into the Lower Dantian. Next, the patient focuses on his or her entire body, while placing the right palm (facing outward) towards the direction of the doctor. The patient is encouraged to relax while keeping his or her palm steady.

The doctor slowly moves the index or middle finger of his or her right hand towards the patient's right palm. While continuing to focus on the patient's energetic field (emitted from the patient's extended right palm), the


Nasal Cavity
Head
Oral Cavity
Eyes
Notch
Hyoid Bone
Throat/Thyroid
Wrist
Wrist
Elbow
Elbow
Ankle
Breasts/Chest
Knee
Shoulder
Hip
Liver
Heart
Lungs
Ankle
Stomach
Gall Bladder
Spleen
Knee
Pancreas
Hip
Large Intestine
Urinary Bladder
Ovaries or Testes
Small Intestine
External Genitals
Occiput
Cervical Vertebrae
Thoracic Vertebrae
Lumbar Vertebrae
Sacral Vertebrae (sacrum)

Figure 25.10. Front and Back View of the Hand/Body Association

Qigong doctor gently points to where he or she feels a particular energetic sensation (Figure 25.11). This special feeling or sensation that the doctor is receiving, represents the location of an energetic problem or disease. While scanning the patient's right palm, each different feeling or sensation represents a diversity of energetic manifestations related to the patient's disorder.

DIAGNOSIS BY OBSERVING AURA FIELDS

Some Medical Qigong doctors use aura readings to determine the physical, mental, emotional, energetic, and spiritual health of the patient. Aura colors will sometimes appear in the form of waves or other energy patterns (for example: evenly layered, blotchy, mixed together, etc.). Aura colors are in a state of constant flux, shifting their colors and patterns with each shift of the patient's moods and emotional thoughts. These colors merge and blend as they fluctuate, weaving in and around the patient's field of Wei Qi.



Figure 25.11. Variation of Finding the Patient's Disease Area by Diagnosing the Patient's Hand



Figure 25.12. Diagnosis by Observing the Patient's Aura Fields.

To begin observing auras, ask the patient to relax his or her whole body, while sitting or standing in front of you. The patient should breathe evenly, to release any distractive thoughts, and then concentrate on the location of the specific disorder. The Qigong doctor focuses his or her attention on the space surrounding the patient's body, while simultaneously concentrating on his or her own Upper Dantian.

Focusing on the Upper Dantian to view the patient's body facilitates seeing the patient's aura field. The patient's aura field may be observed in the form of transparent or opaque Qi flow, or masses of different densities and colors. This may be used as a basis for determining the location and features of diseases (Figure 25.12). Each Yin and Yang organ will have its own color vibration.

When the energy of an organ is healthy, the Qi color is clean, clear and lucid. When an organ is diseased its Qi becomes dark gray and turbid. These colors reveal whether an organ is in an abnormal state and to what extent it has been affected.

COLOR VIBRATIONAL CLASSIFICATIONS

The variety of shifting colors can be interpreted according to their density and tone. The following chart displays the color frequency correlation in nanometers. All living organisms vibrate at a frequency between 300-2,000 nanometers. When analyzed, specific colors emanate consistent frequencies and wave forms. The slower frequencies register in the infrared light spectrum. The highest vibrational frequencies register in the ultraviolet light spectrum (for more information see Chapter 4).

Red	700 nm	Infrared
Orange	600 nm	
Yellow	550 nm	
Green	500 nm	
Blue	450 nm	
Violet	400 nm	Ultraviolet

SEEING AURAS AND EMOTIONAL ENERGY

Seeing auras is a visual phenomenon which occurs after many hours of regular Qigong training. This ability to see the external energy field is not limited to Medical Qigong training; many people are born with this special gift. The word "aura" literally means "breeze," manifesting as shimmering layers of luminous, colored energy that circulate around and penetrate into the physical body. These colors are part of the body's biophoton emissions (radiant light energy that emanates from all living systems). These colors are constantly in motion, reacting to thoughts, feelings, emotional patterns, and environmental influences.

Through the stimulation and physical dilation of the occipital lobe of the brain, the doctor begins to develop this unique perceptual ability. In the beginning stages the doctor may see energy coming off the patient's body like steam.

Later, brilliant, luminous colors become visible. The doctor is actually observing the infrared and ultraviolet radiation color patterns that the patient's body emits. The infrared spectrum is just below the average body's visual spectrum, while the ultraviolet is just above the average visual spectrum. By stimulating and dilation the occipital lobe, the visual spectrum expands to include the infrared frequency, allowing the doctor to observe from a much greater range of colors.

It has been my personal observation that students who possess a large bump on the back of the cranium, specifically between the channel points GV-16 and GV- 17, begin to see auras at a very early stage. These points are below and just above the external occipital protuberance and surround the internal branches off the occipital arteries, veins and nerves. When energy fills this area, the stimulation and dilation of these nerves and arteries causes the visual receptors of the brain to observe certain phenomena at a faster rate, which causes time to seem to slow down (Figure 25.13).



Figure 25.13. As the occipital lobe fills with Qi, the visual spectrum changes.

It is very important to note that these observations are all possible due to the occipital membranes being dilated. To maintain this dilation the doctor must remain calm and relaxed. Any tension brought about by stress only diminishes this ability. Auras are generally seen through the peripheral field of vision.

If the doctor begins to stare at any particular object, focused concentration will contract the occipital membranes, causing tension and pressure that inhibit the dilation process. The secret in maintaining this altered state of observation is to anchor the mind deep into the ground. By focusing the mind on a specific area, focus can be shifted to receiving and observing auras in addition to extending energy without distraction.

The following meditation can be used to stimulate the occipital membrane and enhance the perception of auras.

Seeing Aura Meditation

This meditation can be practiced either sitting or standing. The mind must be free of all distractions and tensions in order for the energy to permeate the occipital lobe. Draw an imaginary line from the top of the head (Baihui) down the spine, down the back of the legs, out the heels and deep into the Earth. This is your mental anchor line which is used to drain your mind of all thoughts (Figure 25.14).

By continuing to drain your thoughts deep into the Earth, you free your Yuan Shen to rely on intuitive perceptions that allow for this altered enhanced peripheral field of vision. This meditation should be practiced for a period of 15 to 30 minutes each day to establish a pattern of relaxation.

As you scan a patient, look to the sides of the patient's body, observing the silhouette of the outer shell of the patient's Wei Qi. It is important not to stare, but just observe the patient's external Wei Qi field (e.g., observing where the field is large, full, thin, or broken). Sometimes different lighting will affect the dilation of the occipital lobe, enhancing visual receptivity.

Next, allow the silhouette to become different colors. Usually, in the beginning, you can see only two or three different colors. With time and practice you will be able to differentiate more colors, with finer detail.

DIAGNOSIS BASED ON THE BODY'S EXTERNAL CHANNELS AND AURA COLORS

Each of the five emotions are related to both the Yin and Yang organs and their Yin and Yang natures. These five emotions are also related to five major colors, both inside and outside of the body's physical structure. By comprehending the colors and understanding their connection to the emotions of the body, the Qigong doctor can successfully analyze the abundance or depletion of energy in his or her patient's major organs. Not only will this reveal the patient's present psychological state of being, but will also expose which internal organs are weakened.

The color chart (Figure 25.15) is used to correlate the patient's energetic fields. These colors are similar, yet have their own unique variations from the physical body's tissue colors.

Think of these colors as extensions from the original organ pools. The mist of the organ pools flows into the body's aura fields, and can be observed in the patient's external energy fields. They are generally very vibrant colors and veil themselves around the first two layers of the Wei Qi. Observe their location around the body, whether they are static or pulsing. If a particular body organ malfunctions, or if any disease is present, then certain parts of the aura may become dim, murky, or produce a dark void.



Figure 25.14. Root the Mind deep into the Earth.

It is important to remember that each patient has his or her own color schemes. When observing the color spectrums of the patient's energy field the most important characteristic is the clarity of the colors. Observe if the colors are sharp, murky, or too concentrated.

The Yang patient's colors will vary in tone and brilliance from the color spectrums of Yin patients. Each aura adjusts to match the patient's mood and temperament. People also often choose for their environment colors that reflect the characteristics of their aura and emotional spectrum (e.g., clothing, furniture, house, and room color, etc.).

When using color energy for healing, the Qigong doctor chooses which specific color to emit, e.g., using blue to cool the Qi or red to heat the Qi (see Chapter 4). Generally, when treating patients, the Qigong doctor will either wear all white (which is the combination of all colors, and is used to naturally project energy), or all black (which is the absence of all colors, and is used to naturally absorb energy), but never the color red (the color red is too intense or "Hot" for Qi extension).

DIAGNOSIS BASED ON INTENTION

The doctor's own developed inner vision can provide a diagnosis through observation of a mental image of the patient. The doctor begins by observing an image of the patient as a complete and whole energy system. Next, the doctor imagines the energetic form of the patient's internal organs (Figure 25.16).

If any part or organ is dark or gives a feeling of turbidness, this indicates the location of the disease. When using this type of energetic diagnosis, the sense of smell, the sense of taste, direct perspective, and remote sensing are also helpful diagnostic skills to enhance detection.

LONG DISTANCE MEDICAL QIGONG THERAPY

Long Distance Medical Qigong Therapy has been with us for centuries. One of the ministers of Huang Di, the Yellow Emperor and patriarch of Chinese medicine, was a shaman named Zhu You. Zhu You was a famous doctor who advocated exorcistic prayer over the use of acupuncture needles and herbs to treat illness. Some scholars believed that Zhu You practiced Qi emission healing at the same time that he prayed for his patients. So effective was this healing approach that The Yellow Emperor's Classics states that, in ancient times, most illnesses were treated according to the methods of Zhu You. In fact, at one time, professional "prayer healers" were once widespread throughout China.

There are several schools of thought on the modalities of long distance healing. Each school

Internal Organ	Aura Color
Lungs	Pure White
Large Intestines	Off-white
Stomach	Deep Yellow
Spleen	Orange Yellow
Heart	Red with Slight Blue Tint
Small Intestine	Pink
Bladder	Deep Blue
Kidneys	Light Flame Blue
Pericardium	Purple Red
Triple Burners	Orange Red
Gall Bladder	Yellow Green
Liver	Deep Green

Figure 25.15. The internal organs are each associated with a specific aura color.



Figure 25.16. The Qigong doctor can diagnose the patient's body through energetic observation and intention.

has its own unique, yet extremely effective application of this esoteric skill.

Although I believe in the effectiveness of prayer, at one time I sincerely doubted the existence of long distance healing. I was thoroughly convinced that it was a matter of projected influential visual and auditory input, similar to hypnotherapy. I expected the doctor to talk to the patient and have him or her close the eyes to facilitate an emotional and mental healing over the telephone. The difficulty in this kind of healing is that if the patient does not trust you, his or her consciousness will not cooperate and will sabotage any healing energy extended in his or her direction.

As fate would have it, one of my Medical Qigong instructors called me one day. As we were conversing, my Kidneys began to heat up. This heat was quite intense, and I was extremely startled because no prior warning of this particular kind of treatment had been given. Yet, I could not dismiss the overwhelming searing heat that I felt in my lower back, Kidneys, and Mingmen area. This healing was done without my conscious consent or foreknowledge! My instructor laughed and explained that as she was talking to me, she was holding a pillow (which represented my body) and visualizing treating my Kidneys with her right hand.

At that point, my beliefs surrounding long distance Medical Qigong healing began to change radically. I began to inquire as to the qualifications needed to treat with that modality of therapy. I learned from my instructor that long distance energy transformation is similar to close range energy transformation. The only difference is that in long distance healing, the doctor's faith and psychic faculty has to be extremely developed and accurate.

To become proficient at long distance therapy, the Qigong doctor must extend his or her thought vibration into the atmosphere, which connects with the thought vibration of the distant patient. Both vibrations collect and blend, drawing together at a selected point on, or within, the patient, creating and reproducing the patient's energetic fields, organs, and tissues.

Zhu You's long distance healing through prayer may be compared to the effectiveness of prayer groups today. Larry Dossey, M.D., for example, documents one double-blind experiment involving nearly 400 patients admitted to the coronary care unit of San Francisco General Hospital for heart attacks or suspected heart attacks. These patients were evenly subdivided into two groups. Both groups received "state of the art" medical care; the only difference was that one group was prayed for by Protestant and Catholic prayer groups throughout the country. These prayer groups had only the patients' first names and sketches. The patients in the experimental group had no idea they were being prayed for; yet when the study was concluded, they experienced significantly fewer complications and deaths than did the non-prayed for control group.

SPACE/TIME AND ENERGY

To study long distance energetic healing, we need to look at a three-dimensional energetic pattern which includes Positive Space / Time, Negative Space / Time, and Energy.

1. Positive Space / Time Energy includes commonly accepted forms of energy (such as electromagnetism, nuclear energy and gravity), and all vibrations ranging from extremely slow to the speed of light. It includes lower vibrations (from inanimate objects) and the higher vibrations of thoughts.
2. Negative Space / Time Energy includes all vibrations which travel faster then the speed of light (super-luminal), and accounts for such phenomenon as telepathy, psychokinesis, precognition, and levitation. In negative space-time, particles have a negative mass and are known as antimatter. When activated to super-luminal speeds, these particles appear to dematerialize, and produce a levitation force which balances the gravitational effects of positive space / time. This also accounts for the Qigong doctor's ability to transmit energy through all known force shields (excluding mirrors, due to their ability to reflect light-energy).
3. Energy and matter form a continuum as does space / time. Energy is the medium between

the positive and negative forms of space. It is the medium between which matter and spirit interact with the space/time continuum, through which heat, light, sound, and resonant vibrations travel.

Matter is composed mostly of space with a minute amount of mass, bound in a particular pattern. This pattern is unique for every form of matter, including the human body. Particles of matter in the human body are constantly vibrating in intermediate stages of energy interaction. Consciousness (the qualitative and directional aspect of energy), acts as a medium for the Qigong doctor's intention to project into the time/space energy field. Consciousness functions as the energy source for resonant vibrations which create the physical world.

To perform long distance healing, the Qi in the Lower and Middle Dantians (the body's Fire and Water energy) must overflow and transform into Shen. The Shen is then united with the divine Qi and extended outside the body for long distance healing of the patient. This allows the energy to cross both spatial and temporal boundaries, thus enabling the Qigong doctor to heal patients in the absence of physical contact.

The first priority in long distance healing, is to establish a connection between all three Dantians through the absorption of divine Qi into the Taiji Pole; this process is called the "empowerment with divine Qi," or simply, the "hookup." This action surrounds the doctor's Wei Qi with Tian Qi (Heavenly Energy), which then is transformed into Tian Shen (Heavenly Spirit).

The doctor then visualizes a long stream of white light extending from the Yin Tang (Third Eye) point, which connects to the patient's body (Figure 25.17).

Once the doctor feels this connection, he or she may now begin the treatment. The physical manifestations of long range healing are the result of the Shen affecting the Qi, and the Qi affecting the body's Jing.

LONG DISTANCE SCANNING EXERCISE

Long distance scanning can be develop by practicing the following mediation exercise.



Figure 25.17. The Qigong doctor absorbs divine Qi through the Baihui area, filling the center Taiji Pole, then projects the divine energy out the body through the Yin Tang or Third Eye area.

- The patient sits in front of the doctor. After connecting with the divine, close your eyes and start to scan the patient's external and internal energetic body. Try to feel the patient's different shades of light and different color spectrums, as well as the patient's temperature, projections, resonant vibrational essence, and varying qualities of texture in the patient's electromagnetic fields.
- Next, open your eyes and scan the patient, comparing and contrasting any differences from your initial readings. Continue to practice this modality of distant scanning until your reading and diagnosing abilities become very accurate. Perfecting your long distance scanning abilities may require several months of training.

LONG DISTANCE THERAPY

To dredge the channels, tonify and regulate the patient's energetic fields using long distance energy transformation, the Qigong doctors sometimes practice the two following meditation exercises.

Long Distance Dispersing Meditation

The doctor begins by placing his or her patient in the next room. After the doctor connects with the divine, he or she imagines his or her body surrounded by a ball of brilliant white light. The doctor then extends a stream of this white light energy out from the top of his or her head and onto the top of the patient's head, enveloping the patient's entire body.

As this white light energy descends down the patient's body, the doctor visualizes the patient's diseased energy dispersing and melting away into the ground. The patient's pathogenic energy is extended into the center core of the Earth, where it is transformed by the Earth's center core fire and then recycled back into the patient as pure, refined Earth Qi.

Next, the doctor focuses on specific areas of the patient's body. The doctor visualizes any area which needs specific attention such as dark areas in the patient's body. The doctor imagines these areas becoming brighter until all the dark areas are dispersed. After energizing the patient's diseased area, it is important for the doctor to disconnect from the patient and withdraw his or her projected Shen (Spirit) back into his or her body.

Long Distance Purging Meditation

The doctor begins by sitting on the edge of a chair with both feet firmly on the ground. Next, the doctor brings both palms up in front of his or her body, at throat level (middle fingers pointing straight upwards), and imagines a ball of white light suspended in-between the palms.

The doctor now pulls the Heavenly Qi towards the center of the ball via the fingers. As the ball fills completely, the doctor imagines the Excess Qi beginning to overflow into the center of his or her palms (Laogong points), descending down the arms and spine, and collecting into his or her Kidneys and Lower Dantian area. The goal is to first collect and store Heavenly Qi in the doctor's Lower Dantian and Taiji Pole (Figure 25.18).

To facilitate long distance healing, the doctor imagines the patient in the center of the ball of light. The doctor focuses on the Excess energy no longer overflowing into the palms, but flowing into his or her patients body, cleansing, filling, and healing the disease (Figure 25.19).

FAITH PROJECTION AND MEDICAL QIGONG THERAPY

This technique is a combination of both psychosomatic and visceral healing. It entails speaking to the patient and establishing a curative relationship through belief modalities, similar to those of "faith healing" used in the West.

It is a form of mind projection; the stronger the Qigong doctor's faith and intention, the better the healing will be. It is important for the patient to have an extremely strong faith in the doctor and to feel secure in the healing environment. The stronger the patient's and doctor's faith, the better the healing.

One popular example of this faith projection ability comes from the famous Qigong Master Shen Chang. Master Shen, lecturing at a conference sponsored by the China Ministry of Broadcast, Film and Television (with hundreds of witnesses present), extended Qi into a woman patient (in her 50's) with a three inch tumor on her leg. As Master Shen began his transmission he began to shout "Gone!" Instantly the tumor started to shrink. After shouting "Gone!" two more times, the tumor had completely disappeared. To the astonishment of everyone, Master Shen then shouted "Grow!" and caused the tumor to reappear. After this amazing demonstration, he then removed the tumor, and completely healed the patient.

Perhaps the body manifests what the mind believes and the Heart feels. It then adjusts itself according to the belief structure and forms a new holding pattern (both physically and energetically). Usually, the doctor will say an instructional phrase four times to the patient, intensifying his



Figure 25.18. The Qigong doctor imagines creating a ball of divine healing white light, suspended between his or her palms.



Figure 25.19. The Qigong doctor imagines that his or her patient is positioned in the center of the ball of divine healing light.

or her intention and instruction each time. The doctor's intention begins to reprogram the holding patterns of the tissues by shocking the system into a new and healthier pattern; a kind of "Be Healed Now!" approach. It is important to know that the energetic field surrounding the patient is strongly affected by either positive emotions and support, or negative emotions, suspicion and disbelief.

To illustrate this fact, I would like to recall an incident that took place in a Santa Cruz bible college in the late 1980's. One morning a colleague was lecturing in an auditorium full of 250 young seminary students. Suddenly, the back door of the auditorium swung open, and a young woman carrying a small baby came walking in. She was crying, and asked for help. She told my colleague that "God" had spoken to her in a dream and told her that if she came to this particular bible college and asked for help, that he would heal her child of a serious disease.

My colleague was both startled and shocked. Not knowing what to do, or even how to handle the situation, he quickly turned the meeting over to a local spiritual elder who was monitoring the lecture. This elder, seasoned in these types of spiritual phenomena, again asked the woman what the problem was. After hearing her story a second time, he informed her that while "God" had not spoken to him directly about the situation, he would be obedient to whatever "God" wished.

Next he looked up to the 250 young seminary students sitting in the auditorium and stated, "If anyone here does not believe that God can and will heal this child instantly, please leave now." All but three seminary students left the auditorium. The elder called to the three remaining students to join him with my colleague in praying for the baby. The child was instantly healed (a follow-up visit confirmed this fact), and the mother left, smiling. My colleague, perplexed by the whole event, turned to the elder and inquired as to how he knew what to do. The elder responded, "Even Jesus, who was the greatest healer of all time, couldn't heal in his own home town because of everyone's disbelief. Here in this auditorium it would have been five of us who had the faith in healing, versus 247 who were skeptical and full of doubt. It is better to have a few with great unwavering faith than to have many with little faith at all."

AUXILIARY MEDICAL QIGONG HEALING MODALITIES

The following are auxiliary Qigong modalities used by various Qigong doctors in hospitals and clinics, as well as their personal practices throughout China.

One of the methods used for these Medical Qigong therapies is the projection of Qigong Messages into specific material objects (i.e., a liquid, food, a scroll of calligraphy, a talisman, a cloth, a necklace, etc.). Once the object contains the Qigong doctor's Message it will have a powerful effect on the patient's body. This is a form of "transmission of intention" which is a form a Qi and Shen projection. Qi and Shen projection transcend time and space, lasting an indefinite amount of time depending upon the belief of the Qigong doctor and patient.

Certain Qigong doctors can transfer their energy or "thought message" through works of art. I experienced this technique quite accidently while lecturing at the Third World Conference on Medical Qigong in Beijing, China in 1996. I was in the back of the lecture hall sketching while one speaker was sharing his dissertation. Another Qigong Master seated in front of me noticed my artwork and asked to see it. Curious as to what he would do, I gave him my notebook. He placed his hand above my drawing and began projecting Qi into the picture. Immediately energy flooded my being from head to toe. I was literally vibrating all over, being filled with light and sound resonation (that felt similar to a strong electrical current). Since my original piece of art contained a direct connection to my physical energy, the Qigong doctor was able to extend energy into my body, by simply projecting his Qi into my artwork.

The doctor can transmit healing energy through any object which has had contact with or was created by the patient. This technique is possible because creative artwork, or any object touched or created by hand, is imprinted with the person's energy. This energy contains a unique blend of the individual's encoded energy patterns. This information regarding the individual can be retrieved through psychometry (the act of sensing the thoughts, images and so on, with which the object has been imprinted). A connection to the person who created or held the object can thus be established through the Wuji. This object can then serve as a focusing point to send healing to that person, through the doctor's intent.

Energy, in the form of waves, is expressed in the abstract form of thoughts, accessible to the vibrational medium of space and time. This allows for the energetic transformation of the individual's emotional patterning.

USING MEDICAL QIGONG TO HEAL BY PROJECTING CHINESE CHARACTERS

There are other Qigong doctors who draw specific Chinese characters in the air and send them encapsulated in a bright white light ball of energy into their patient's body to initiate healing (Figure 25.20). This projected energy is created through the doctor's intention and is absorbed into the patient's body, through the patient's receptive attitude and desire to heal.

USING MEDICAL QIGONG WITH SUPPLEMENTARY APPARATUSES

There are certain Qigong doctors who will use specific objects ranging from such supplementary equipment as rubber acupuncture dolls to pillows, in order to perform long distance healing. To utilize these objects for long distance healing, these Qigong doctors place the object, a doll for example, on the table in front of them and begin to draw their patient's Essence (from many miles or even across other countries) into the doll. The doctors then treats the patient by draining off the pathogenic excess from the doll (Figure 25.21). Once the doctors feel that the patient has been sufficiently cleansed and the disease dispersed, they begin to tonify the patient's weak organs. While



Figure 25.20. Another skill utilized by Qigong doctors, is to create different colored balls of energy to encapsulate specific Chinese characters (or Messages) within them, which are then projected into the patient's body as a form of treatment.

the Qigong doctors work on a patient, you can actually feel hot and cold spots emitting from the rubber acupuncture doll. Several of my students have been able to successfully implement this modality of training and find it fascinating.

USING MEDICAL QIGONG TO ENERGIZE HEALING CLOTHS

Some Qigong doctors extend Qi into pieces of paper or cloth, to be placed on the patient's body to invoke a healing. This is similar to the "prayer



Figure 25.21. Some Qigong doctors use a rubber acupuncture doll (man or woman) as an energetic medium, while treating patients at a distance. The Qigong doctor is removing pathogenic Qi and throwing it into a glass of salt water (used to neutralize the Turbid Qi).

cloths" and other techniques used today in the Pentecostal Churches. The energy stored within the cloth or paper, will last indefinitely, however, the most important component of this type of healing is the patient's belief structure (Figure 25.22-23).

USING MEDICAL QIGONG WITH CRYSTALS

The energy in the human body produces a polarity similar to that present in crystals. Because crystals emit a very strong white light energy, they can be used for energetic surgery, allowing the

Qigong doctor to cut into the patient's energetic field like a laser beam. Crystals can additionally be used for scooping energetic toxins, cleansing and purging the patient's body, and for cutting loose pathogenic Qi within the patient's tissues and external fields of Qi. Crystals can also be used for tonification, by enhancing the doctor's energetic extension and projection abilities.

USING MEDICAL QIGONG TO ENERGIZE LIQUID COMPONENTS

Other Qigong doctors extend their energy into herbal teas, wines, and I.V. fluids, as well as simple components such as water, to energize and utilize these liquids for healing. These doctors send the energized liquid substance to the patient, who ingests the medicine to tonify deficiencies. Water is an excellent repository for electromagnetic energy, and absorbs vibration better then any other substance (Figure 25.24).

USING MEDICAL QIGONG TO ENERGIZE FOOD

There is an ancient Chinese proverb which poses the question, "Is food medicine or medicine food?" Because a basic principle of Traditional Chinese Medicine states that anything ingested is transformed into energy (Gu Qi) by the body, some Qigong doctors extend their energy into the patient's food before it is ingested. This belief is not isolated to the Orient, but is also part of the Western culture, hence the practice of praying and blessing over food before eating it.



Figure 25.22. Emitting Qi into Cloth



Figure 25.23. Emitting Qi into Paper



Figure 25.24. Emitting Qi into Liquid

SECTION VI

ESTABLISHING THE MEDICAL QIGONG CLINIC

CHAPTER 26
TREATING THE PATIENT

SETTING A SPACE/TIME FOUNDATION

Before treating patients, and to establish a sacred healing space, the Qigong doctor must first bring his or her true self into what is called the center of space and the center of time before performing the divine hook-up.

This establishes a foundation for treating patients, and allows the doctor to fuse with the patient, while accessing the energies of the divine, as well as the universal and environmental energies. Once this is achieved the doctor can allow him or herself to act as an observer, viewing the patient from a non-judgemental position.

FINDING THE "TRUE SELF"

The Qigong doctor's "true self" is defined as his or her pure innate spiritual existence, void of all ego masks and personalities. The "true self" is spiritually connected to, and rooted in, the energy of the divine. It is the part of the soul that unconditionally accepts self and others, and is more in the role of a compassionate observer than a judge. The "true self" allows the doctor to observe the patient's condition (spiritual, emotional, mental, energetic, and physical), void of any personal emotional biases. The "true self" is a state where unconditional love and acceptance is fostered and supported by the divine.

To discover the "true self", the Qigong doctor is trained through special Shengong (Spirit skill) meditations. One such meditation asks the question "Who are You?" This is repeated over and over until the doctor realizes and experiences his or her "true self". Who you are is not determined through expressing a correct answer, but by actually experiencing the spiritual quest. It is through the realization of this innate truth, which is inherent within one's own enlightenment, that the doctor is freed from the ego (known as the "Death of the Ego Fear"). Once the doctor realizes who he or she truly is, the answer is reflected from the light within the doctor's eyes and not through any specific mental concepts. There is a saying from Lao Zi, written in the *Dao De Jing* (The Way and Its Power) that explains this phenomenon: "The Dao that can be named is not the true Dao."

FINDING THE CENTER OF SPACE

Before treating a patient, the Qigong doctor must also place his or her body, mind, emotions, energy, and spiritual essence into a place of infinite existence called the center of space. The center of space is actually a spiritual and energetic concept, wherein the doctor imagines him or herself as being the actual center of the universe. This concept and image maintains that all energy, light, and energetic fields extend from the middle of the doctor's center core, expanding outward into infinite space (Wuji). This energy continues to extend and envelop the entire universe and all the energetic dimensions beyond.

To access the center of space the doctor must place his or her "true self" into the Taiji Pole, connecting the core self with the divine. It is from the orientation of the core self that the Qigong doctor accesses the deeper, hidden, spiritual, and energetic fields of the patient's body.

FINDING THE CENTER OF TIME

The final image that the Qigong doctor visualizes before the divine hook-up is to place himself or herself into the space known as the center of time. The center of time is the place of "Now." It is a dimension where infinite future is forever flowing into the doctor's center core, while the infinite past is forever rushing away.

To grasp the center of time concept, think of time as a linear progression of light and energy. The concept of future time is rushing directly into the front of your body. Within a split second, the Yang changes into Yin and the future transforms into the past, and continues rushing out the back of your body. You must find the still point, inside of your body, where Yang transforms into Yin, and the future transforms into the past - this is the center of time. From the center of time the Qigong doctor brings the patient into the present moment. This process enables the doctor to access the hidden past memories trapped deep within the patient's tissues.

ESTABLISHING THE MEDICAL QIGONG TREATMENT ROOM

Before receiving patients it is important to establish an environment that is conducive to healing. The density and quality of energy in the healing room is a very critical factor. Filling both the treatment room and clinic with the energy that flows from the Heavens to the Earth sets up an energetic vortex. Through the creation of this energetic vortex the patient's pathogenic factors will automatically flow into the ground once they are dispersed from the patient's body. The more energy that the healing room contains, the more successful the treatment will be. It is important to cleanse the healing room before and after each patient. This cleaning is achieved through the doctor's divine hook-up.

When establishing a treatment room it is also important to have adequate lighting and clean air ventilation. Avoid fluorescent lighting; if this is impossible, then use a full spectrum light.

It is important to also keep the patient's living quarters and bed energetically cleansed, as pathogens have a habit of collecting in areas of sickness and disease. The patient is encouraged to burn salt with a little alcohol to cleanse the treatment room (at least once a day) and fill the room with fresh air and light. Often neglected is the living space of the patient. Energetically cleaning the entire house or apartment often, during and after there has been an illness, allows the toxic energy to be purified from the patient's home.

One example of how energy stagnates is observed in hospital wards. Each ward has an energetic "feeling," associated with the different types of diseases or conditions treated there. The cancer ward, for example, feels entirely different from the maternity ward, emergency room, etc.

The treatment room must also be kept uncluttered, as energy stagnates in cluttered environments. Also, after each treatment, always change the bedding and energetically clean the clinic or treatment room.

WHEN TO AERATE, ILLUMINATE, OR SMUDGE

It is important to daily cleanse the energetic field of the treatment room. This facilities a fresh uncontaminated environment, allowing the next patient to feel safe and protected from any previous contaminants which may have been left from a prior patient. The three most common ways to cleanse the clinic before and after each patient (besides changing the table coverings), are:

1. Aerate by ventilating the clinic, making sure that the air circulation is fresh and clean (free from pathogens, Toxic Qi, dust and pollens, foul orders, smoke, etc.).
2. Illuminate by exposing the clinic to bright sunlight, or divine healing light (through prayer).
3. Smudging is performed by burning fragrant herbs in the form of certain incense (such as, sandalwood, myrrh, frankincense, or sagebrush, etc.). Remember to aerate after smudging.

The Qigong doctor may wish to incorporate either one or several modalities of cleansing. Each particular technique offers its own advantages and disadvantages, depending on the size and location of the clinic and its surrounding environment.

ESTABLISHING A RAPPORT WITH THE PATIENT

It is important to establish a foundation of trust between the doctor and patient before the treatment begins. This trust is enhanced by: Talking with the Patient to Establish Treatment Goals, Explaining and Reaching Agreements on the Treatment Modalities to be Used, Honoring the Patient's Spiritual Belief System, Receiving the Patient's Consent Before Treating, Matching the


Doctor
1. Talking with the Patient to Establish Treatment Goals
2. Explaining and Reaching Agreements on Treatment Modalities
3. Honoring the Patient's Spiritual Belief System
4. Receiving the Patient's Consent Before Treating
5. Matching the Patient's Respiration
6. Maintaining the Doctor-Patient Relationship
7. The Four Major Priorities of Clinical Qigong Healing
Patient

Figure 26.1. Establishing a rapport with the patient begins with trust.

Patient's Respiration, Maintaining the Doctor-Patient Relationship, and The Four Major Priorities of Clinical Qigong Healing (Figure 26.1).

TALKING WITH THE PATIENT TO ESTABLISH TREATMENT GOALS

After completing the diagnosis, establishing the treatment principle, and determining the treatment strategy, the Qigong doctor discusses with the patient the treatment goal (i.e., which internal organs, channels, and tissue areas are affecting the primary cause of the patient's disease, and how to address it). The treatment areas are specifically chosen to facilitate a rapid affect on the functioning process of the patient's disease. The doctor explains the intended goal of using the purging, tonifying, or regulating techniques, and how they will affect the patient's body.

EXPLAINING AND REACHING AGREEMENTS ON THE TREATMENT MODALITIES TO BE USED

The Qigong doctor explains, in clear, comprehensive terminology, what he of she has determined as to the best way of approaching and rectifying the patient's condition (e.g., having the patient in a lying, sitting or standing posture), and what treatment modalities the doctor will be using (i.e., through Qi Emission, Qigong Massage, Sound Therapy, Light Therapy, etc.).

The more the patient understands the doctor's approach in addressing the condition, the greater the likelihood of the patient relaxing during the treatment. This explanation also assists the doctor and patient in developing trust, which will encourage the patient when practicing the homework prescriptions, or in receiving suggestions on life-style modifications.

HONORING THE PATIENT'S SPIRITUAL BELIEF SYSTEM

When treating patients, it is important that the Qigong doctor not become distracted by the illusion of solid tissue matter, remembering that we are spirit, and that healing begins in this fifth dimension. The primary belief in Medical Qigong therapy is that tangible and intangible energy, through faith, will merge at the highest level of cultivation. Prayer is an invocation that extends the mind, emotion, and spirit to the divine, while meditation is a state of mental, emotional, and spiritual receptivity for divine inspiration, guidance, and manifestation. Both actions (prayer and meditation) connect the doctor and patient to the divine to bring patients back into awareness of their body and to initiate divine healing.

In China, Qigong doctors have a saying, "train your virtue and morality to increase your energy, allow your Spirit to lead your Qi and the Qi will flow pure." Meaning, the stronger the individual's virtue has been developed, the more powerful his or her spiritual intention will flow, and Qi move.

The healing modality choosen by the doctor must be congruent with the patient's spiritual belief structure. The patient must be connected to his or her own unique interpretation of universal consciousness (God) in order for divine healing to take place.

When the patient disbelieves in a Higher Power -- be it God or a universal consciousness -- the doctor can still help the patient heal, providing the patient has established sufficient trust and hope in the doctor. If the patient feels understood and listened to by the doctor, this can empower the patient to heal, regardless of his or her own conscious belief system.

If the doctor, on the other hand, does not believe that a true healing can take place unless the patient believes in a Higher Power or God - then no healing will take place, for the doctor will lack confidence, hope, and trust. The therapeutic bond between the doctor and patient will be broken and replaced by a battle of wills.

For patients who lack faith, applying a hands on Qigong technique may be more effective. Gradually, over the course of time, the doctor may incorporate other healing modalities as greater trust is built.

The Qigong doctor should always begin treatment in harmony with the patient's spiritual belief system (that may change in time), through touch, verbal conversation and unconditional love (empathy). The doctor should also communicate mind to mind, for this will facilitate trust at the subconscious level.

RECEIVING THE PATIENT'S CONSENT BEFORE TREATING

The treatment modalities should be decided together by the doctor and the patient. It is important for the Qigong doctor to provide the patient with enough information about the type of therapy he or she will receive, so that informed consent can be given for the treatment. This empowers the patient and allows relaxation and trust to occur.

MATCHING THE PATIENT'S RESPIRATION

Another technique to relax the patient is called "matching and pacing." The Qigong doctor matches the patient's breath and breathing patterns, and gradually shifts his or her own breathing to a slower and deeper pace. It is important to note that the patient's physiology affects his or her energy, which in turn affects his or her emotions and respiration. This technique of matching the patient's and doctor's breath and leading it into a state of quiescence is very often used by Medical Qigong doctors to relax their patients. It not only connects the doctor with the patient on an energetic and emotional level, but also provides a strong spiritual connection.

Note: Do not match an asthmatic patient's breathing, as this is disruptive to the flow of Qi within your own body.

MAINTAINING THE DOCTOR-PATIENT RELATIONSHIP

Whenever the doctor begins to judge or formulate negative opinions of a patient, he or she is no longer operating in the divine "present" state of spiritual intuition, but has shifted into the "past" (as all judgements are based on past experiences and emotional encounters). The doctor is then in danger of absorbing the discharged energetic pathogens from the patient, or projecting subconscious biased opinions onto the patient. Whenever the doctor relates, relives, or orients from his or her own personal past (the feelings can be either positive or negative), the doctor is at high risk of absorbing the patient's energetic pathogens.

When the patients come to the doctor, they are giving their consent for the doctor to learn about personal things which the patient has often withheld from their mate, family, or even themselves. They are further giving the doctor permission to utilize their combined energies to affect changes within their physical, mental, emotional, energetic, and spiritual fields and body.

Each treatment will be different for the patient, as each experience will vary according to the patient's present state of mind and emotional spirit. The patient's willingness to allow the Qigong doctor's emitted energy to penetrate deeper into his or her body with each session will depend upon the level of trust established, as well as any outside influences that may have a positive or negative effect on the patient's ability to be open and vulnerable. Patients who experience ridicule or criticism from family and friends for their choice of a non-Western form of treatment, may temporarily shut down their receptivity in self-defence against others. At times, patients may also close-off as a result of an event that has a strong impact on their emotional and spiritual well-being, such as a death of a friend, a physical trauma, or other upsetting news.

The patient always has the final control over the doctor's emitted energy, and can choose to either absorb and utilize the energy, or disperse and sabotage the doctor's treatment. It is for this very reason that the doctor-patient trust factor, as well as the goal orientation, must be securely established before the treatment begins.

Be sure the patient's arms and legs are not crossed, as this can impede, or "short-circuit," any energetic flow, causing Qi obstructions. The patient should close his or her eyes, but should not be allowed to internally guide or direct the Qi unless specifically instructed to do so by the doctor. A patient's unguided imagery can cause the body's energy to increase, alter, or obstruct the flow of the doctor's energy, which may cause Qi deviations or aggravate an existing condition. Usually the patient is given the image of dissolving his or her tissues into space, which encourages relaxation and freedom from distractions. If the patient is lying down, he or she is given certain visualizations, such as floating on a sea of warm water (or basking in the sun on the beach or shore of a lake). These images relax the patient and enable the Qigong doctor to disperse the patient's armoring. Once the patient's "street armor" is down, the doctor will have easier access into the patient's tissues.

After the treatment, the doctor and patient evaluate each session, discussing any and all feelings, observations, transitions, and sensations that both the doctor and patient experienced. Homework, in the form of Medical Qigong prescriptions are then generally given, in addition to follow-up treatments (depending on the patient's case and condition).

THE FOUR MAJOR PRIORITIES OF CLINICAL QIGONG HEALING

According to China's prominent Qigong Grand Master Pang Ming, clinical Qigong healing is based on four basic priorities. In establishing a clinical environment it is important to inform the patient about the structures of these four priorities: A Strong Faith, Group Healing, Medical Qigong Therapy, and Medical Qigong Prescriptions and Exercises.

1. A strong faith that Qi or life-force energy can heal the patient's specific ailment is built up by the patient listening to testimonials. These testimonials are given by other patients who have recovered from the same type of disease, as well as those patients who are experiencing improvement through Medical Qigong therapy.

   Qigong deals directly with the psychological aspects of diseases. It is well known that two side effects of cancer are depression and fear. A very popular theory maintains that depression (being the suppression of anger) can cause cancer. Even before the cancer patients begin their treatment program, their confidence is bolstered by the positive experiences of more advanced students of Qigong, who at one time also suffered from these particular kinds of cancer. In addition, as part of the Qigong exercises, the new patient's mind is focused on pleasant images or memories. All of this creates a positive mental attitude in the patient.

Sometimes patients come to the doctor for healing, yet at a deeper level they feel that they need or deserve the illness. Sometimes the secondary gain of illness (for example, to keep the wife or husband underfoot) outweighs the benefits of healing completely. If a patient is subconsciously unwilling to be healed, his or her attitude or disbelief will sabotage all clinical modalities of healing (both Western and Eastern). You cannot make someone better against his or her own will. Illness, like health, is often a matter of choice.

2. Before a group of patients begin Qigong, the doctor verbally synchronizes the thinking of the group by absorbing Heavenly Qi (the divine hook-up), and bringing it down into the healing energy field which surrounds everyone including the doctor. The healing effect is enhanced because the group is acting as one unit, with one faith.
3. The doctors initiate the actual Qigong healing by bringing divine healing energy to each individual patient.
4. The patients are taught how to easily follow Medical Qigong exercises and meditations, practicing them over and over again.

When a patient enters a Qigong hospital in China, they are diagnosed by a doctor and then assigned a specific Qigong class for a twenty-four day treatment period. The patient spends eight hours a day practicing Qigong without television, newspaper, or telephone. This is required to help the patient avoid regression into a previously established belief structure or subconscious pattern. Those who are able, practice Qigong from a standing posture. Other patients with limited mobility practice Qigong sitting or while lying in bed. After the twenty-four day treatment program is over, the patient is again diagnosed by a Qigong doctor. The diagnoses is classified into one of four categories for statistical purposes.

1. The patient has been cured: symptoms have disappeared and appropriate instruments (e.g., EKG, ultrasound, etc.) register normal tissue.
2. The treatment has been very effective: symptoms have almost disappeared and allopathic tests indicate great improvement.
3. The treatment has been effective, in that the patient is now able to eat, sleep, and feel good.
4. The treatment has been noneffective: there has been no change, or the condition has worsened.

PREPARING THE SELF TO TREAT THE PATIENT

This section prepares the Medical Qigong doctor to treat patients. The "preparation" sets the energetic ambiance for the clinical treatment and secures the foundation for dispersing pathogens. The preparation includes: The One through Ten Meditation, Creating a Sacred Healing Space, The Divine Hook-Up, Rooting to Prevent Energetic Shock, and The Energetic Circle Drawing Pattern (Figure 26.2).

THE ONE THROUGH TEN MEDITATION

The following is called the One through Ten Meditation and is used to prepare the Qigong doctor for clinical work. It allows the Qigong doctor to relax, sink, and root the mind. This meditation allows the doctor to extend his or her energetic field before connecting with the divine. This meditation is used to create a sacred healing space and is taught in a rhyming one through ten counting format, described as follows.

1. One Is Fun, therefore take pleasure in your work. Imagine a smile melting down the front of your body like warm oil, melting all stress and tension into the Earth. A second smile melts down the back of your body, dissolving all stress and tension down into the Earth. A third and final smile melts down the center of your head, relaxing all thoughts, judgments and feelings, and flows down your shoulders and arms and out your hands. The melting continues to flow down the center of your torso, like warm oil, melting all emotional blocks and tension, then flows down your legs and into the ground. At this point your mind and body should feel content, relaxed, and peaceful.
2. Two Is Shoe, thus imagine your feet melting into the Earth, like ice melting on a hot side-


The Qigong Doctor's Energetic Preparation for Clinical Therapy
1. The One through Ten Meditation
2. Creating a Sacred Healing Space
3. The Divine Hook-Up
4. Rooting to Prevent Energetic Shock
5. The Energetic Circle Drawing Pattern

Figure 26.2. The Qigong Doctor's Preparation for Treating the Patient

walk. The energy of the feet fuses with the Earth, melting in five directions (forward, backward, right, left, and down). This connects your mind and body with Earth energy.

3. Three Is Tree, therefore feel yourself extending tree-roots twice your body's height deep into the ground. The roots expand in five directions (forward, backward, right, left, and down), securing your rooting and connection with the Earth energy.
4. Four Is Core, thus imagine your roots extending deep into the core of the planet. The Earth energy flows into these roots, ascending up the legs, spine, over your head, down the chest, and enters your Lower Dantian. This action allows you to draw Earth energy into your body and circulate it through the Microcosmic Orbit. A solid connection to the Earth roots your physical, mental, emotional, and spiritual energies, and fills up your Lower Dantian with Earth energy.
5. Five Is Alive, therefore feel the Earth energy building up within your Lower Dantian. The energy increases to the point that your Dantian can no longer contain its power. It rushes up the center of your chest like a mighty river, dividing into two streams which flow out each palm into the earth. This action releases and emits the energy stored within your Lower Dantian.
6. Six Is Thick, thus imagine the room or environment where you are standing being filled with energy. This energy becomes so thick, it is as if you are submerged under water. This fuses the environmental energy with your energy, and the Earth's energy into one dynamic field of energy.
7. Seven Is Heaven, therefore allow your Baihui point to open up and draw in the divine healing white light into your Upper Dantian. Let the divine light fill your head and the entire Upper Dantian area till it floods and shines down from the Upper Dantian into your chest, filling up the entire Middle Dantian. Finally, the light shines down from the Middle Dantian filling up the lower abdominal area and the entire Lower Dantian. This light connects you with the Heavenly healing white light energy from the divine, filling up all three Dantians and your Taiji Pole. Thus Heavenly and Earthly energies fuse within your body.
8. Eight Is Open the Gates, therefore imagine opening every pore on your surface tissues, and begin to draw the environmental energy into your Taiji Pole upon inhalation. Upon exhalation imagine your center core vibrating and glowing like a neon light. This visualization energizes your center core, harmonizes your energy and breath, and prepares you for Qi and Shen (energy and light) projection.
9. Nine Is Shine, therefore imagine that your center core becomes completely full of energy and overflows by shining (from the Taiji Pole outward) through your pores until it fills up the entire room, like a bright phosphorus flare. This visualization fuses Heaven Qi, Earth Qi, and Man's Qi with the external clinical environment.

10. Ten Is Begin, with all things now in order, you are physically, mentally, emotionally, energetically, and spiritually in harmony, with your body, the Heavenly energy, and Earthly energy. You can now begin treating patients.

CREATING A SACRED HEALING SPACE

After completing the preparation, the Qigong doctor creates a sacred healing space in which to treat patients. Creating the sacred healing space allows the doctor and patients to interact in a safe environment without outside distractions.

The Qigong clinic should be a place of complete sanctuary, a consecrated place of refuge, where the patient feels safe, warm, and cared for (spiritually, emotionally, mentally, energetically, and physically). The patient should experience the peaceful ambiance of the treatment room as being enveloped in unconditional love and security.

To create the sacred healing space, the Qigong doctor performs the divine hook-up. Only after completing the divine hook-up should the Qigong doctor treat his or her patients.

THE DIVINE HOOK-UP

Once the doctor has established energetic grounding, the next step in establishing a clinical environment is to connect with his or her spiritual center through the divine hook-up. From this spiritual center the Qigong doctor observes the patient, void of personal thoughts, feelings, and judgments. This spiritual state of open receptivity allows patients to feel secure and to release their guarded emotions. Lacking a safe environment, patients may feel the need to repress emotions or to be distracted from experiencing and letting go of the original trauma.

The Qigong doctor, once healing has begun, enters into a state of "oneness" with the patient and the divine, in which the doctor's will and intention envelops and fuses together with the divine will and wisdom. Both doctor and patient begin to communicate through deep subconscious interactions. The doctor's success or effectiveness as a Qigong healer depends on a willingness and ability to connect with the patient and the divine healing light. Drawing from this interpersonal communication with the patient, and the deep spiritual connection with the divine, the doctor begins the treatment.

According to Dr. Meng Xian Tong of the Beijing Chengjian Integrated Traditional Chinese Medicine and Western Medicine Experts Clinic, when Qigong doctors perform the divine hook-up, they increase their own body's Righteous Qi, which then extends the energetic Message encoded in their Qi into the patient's body. The doctor's Righteous Qi is then absorbed by the patient's body and fused together with his or her Qi. This fusion empowers the patient to heal his or her disease.

Before contact with any patient the doctor first connects with the divine to purify and stabilize, not only him or herself, but also the treatment room (with a constant flow of Heavenly Qi pouring into the room). This divine hook-up enables the Qigong doctor to not only establish a sacred healing space, but also to access both spiritual insights and divine healing power.

ROOTING THE DIVINE HEALING LIGHT

Rooting the divine healing light is accomplished by visualizing a beam of healing light (the doctor can also choose specific colors) streaming into his or her body via the Baihui and Sishencong points (at the top of the head), and entering into the Taiji Pole. The doctor holds this frequency until the divine healing light becomes rooted or "anchored" within the Lower Dantian.

Next, the doctor brings the healing light vibration up the Taiji Pole to energize each Dantian until the healing light infuses and harmonizes all of the body's tissues. As the doctor feels the healing light reach the Middle Dantian, he or she visualizes the light intertwining with the "bridge of light," which connects the doctor's Heart (Middle Dantian), throat and Yintang (Upper Dantian) areas together. This energetic connection fuses at the Upper Dantian, becoming one unified cord. The healing light is then stored within the doctor's body and released during Qi emission.

USING THREE DIVINE INVOCATIONS

To assist the doctor in rooting the divine healing light, I encourage my students to begin each treatment with a small prayer and three invocations, for example:



Figure 26.3. As the divine healing Qi absorbs into his or her body, the Qigong doctor expands this field to envelop the entire treatment room.

1. "Lord God, fill me with your Holy Spirit and divine healing power. Increase my skill, power, knowledge, and wisdom and use me for Your Glory." The first invocation connects the doctor to the healing energy of the divine and roots the doctor deep into the Earth. This prevents the patient's pathogenic Qi from entering into and contaminating the doctor's body.
2. "Fill this room with your Holy presence and healing virtue, and let your Glory shine through me into this room." This second invocation connects the doctor and the treatment room to the divine and secures a sacred healing space (or sanctuary) for the patient. It also establishes an expansive divine energetic field by causing the doctor's Wei Qi field to overflow with divine healing light, filling the treatment room. This divine energetic field produces a dynamic field of healing energy (Figure 26.3).
3. "I lift (the doctor will mention the patient's name) before Your Holy Presence, and ask that you may heal these wounds and free him or her from these chains of despair, agony and disease. Thank you, God. Amen." After this final invocation, the doctor envelops the patient with an energetic bubble of light and love.

Next, the doctor roots the patient's energetic bubble deep into the Earth, and creates an energetic vortex underneath the patient. The energetic vortex will spiral clockwise, deep into the center of the Earth. This energetic rooting technique is practiced to purge and drain the patient's Toxic Qi into the Earth, where it is cleansed and then recycled back into the patient's body.

ROOTING TO PREVENT ENERGETIC SHOCK

Rooting (sometimes called "energetic grounding") is an important technique used by the Qigong doctors to establish and maintain a firm physical, mental, emotional, energetic, and spiritual connection to the Earth. Connecting to the Earth is essential to prevent energetic shock (a jolt of energy which flows from the patient into the doctor's body), which can result in the doctor ab-



Figure 26.4. The Qigong doctor envelops the patient in an energetic bubble (or healing circle) before beginning the treatment.

sorbing the patient's energetic pathogenic disease. To prevent energetic shock from happening, Qigong doctors go through several steps to prepare themselves and the clinical environment before treating patients. Energetic rooting is utilized in all phases of meditation and allows doctors to maintain a strong physical connection to the Earth. It is especially used when the doctor is absorbing and emitting environmental and universal energy.

- From a Wuji posture, imagine an energetic cord extending from your Lower Dantian, down the Taiji Pole and out the Huiyin point (at the base of the spine) deep into the center of the Earth. This energetic cord will root your energy into the Earth. It is also affected and maintained by your will and intention. The energetic cord follows the doctor's movements smoothly and easily.
- If the patient is lying, sitting, or standing in front of you, extend your energy to envelop the patient within an energetic cocoon called "energetic circle drawing."
- Imagine extending an energetic cord from the patient's Lower Dantian through this energetic cocoon, to root the patient's body deep into the Earth. This process energetically grounds the patient's body, mind, emotion, and spirit.

THE ENERGETIC CIRCLE DRAWING PATTERN

Once the divine hook-up is completed, the doctor grounds the patient by drawing an energetic circle around the patient's body. This is used to charge the patient's energy field. This energetic projection also roots the doctor's intention around the patient and strengthens the doctor's concentration. This circular field changes the patient's static field to a divine dynamic field and enables the Qigong doctor's energy to enter the patient's body with ease.

The enveloping of the patient's body allows the patient's body and energetic fields to become even more accessible to the Qigong doctor, while keeping the patient's pathogens isolated from the doctor's body (Figure 26.4). As the doctor steps into the energetic bubble, he or she is able to treat the patient's tissues, feeling absorbed and enveloped within the Messages expressed from the patient's energetic fields.

The energetic bubble is created by emitting Qi towards the patient, and enveloping and circle wrapping the patient in a clockwise energetic rotation. This energetic bubble forms a shield, maintaining protection for the patient and the doctor. Next, the doctor creates an anchoring line to root the patient's energetic field deep into the ground. Finally, the doctor creates an energetic vortex (spiraling in a clockwise direction) underneath the patient, to pull any dispersed pathogens deep into the Earth (this helps when the doctor is dredging and purging the patient's energetic fields).

USING THE ENERGETIC CIRCLE DRAWING PATTERN TO PURGE PATHOGENS

The energetic circle drawing pattern helps to facilitate energetic cleansing. Energetic purging facilitates the absorption of Clear Qi and also reduces the risk of contamination within the body's channels and collaterals by expelling energetic toxins and other pathogenic factors.

After creating the energetic circle, the doctor begins using dredging and purging techniques to expel pathogens from the patient's body. Next, the doctor treats the patient with tonification and regulating techniques, ending the treatment by closing the diseased area and sealing the patient's three energetic fields (three Wei Qi fields). This ending technique will securely close the energetic holes in the patient's outer field of Wei Qi (see Chapter 13). Without this sealing, the healing process is hindered due to the patient's Qi having a tendency to leak or disperse itself (even after tonification). Once the sealing is completed, any Excess Qi will be evenly distributed throughout the patient's body, establishing a Yin and Yang balance within the visceral organs.

USING THE ENERGETIC CIRCLE DRAWING PATTERN TO PURGE TOXIC HEAT

Before treating patients who have received radiation or chemotherapy, the Qigong doctor should wrap the patient with an energetic bubble and then purge the Toxic Heat from the patient's body. The Toxic Heat is dispersed into the energetic vortex created under the patient's body, and then released deep into the Earth. The Qigong doctor can then step into the energetic bubble and begin combing, dredging and purging the patient's tissues.

USING THE ENERGETIC CIRCLE DRAWING PATTERN TO PURGE TOXIC COLD

When using the circle drawing method to purge pathogenic Cold, the doctor stands outside of the energetic bubble, and extends energy deep into the patient's Taiji Pole. Once the doctor feels the patient's center core Qi, he or she draws the pathogenic Cold or Hot energy out from the patient's tissues (in all directions), filling the energetic bubble. The doctor, standing outside the energetic bubble, observing the patient's energetic field, waits for an energetic shift which is immediately followed by Toxic Cold (or Hot) Qi filling up the energetic bubble. Once this occurs, the Qigong doctor must drain the pathogenic Cold (or Hot) Qi down into the Earth to rid the patient of the Toxic Qi.

TREATING THE PATIENT

After the Qigong doctor has "circle wrapped" the patient, the treatment begins. First, the doctor dredges the patient's external energetic fields, channels and collaterals (from head to feet). The doctor senses the patient's Qi with his or her hands, changing the depth of penetration of the touch by extending intention deeper into the patient's tissues. Once the patient's pathogenic Qi has been reached, the doctor feels various energetic sensations (vibration, warmth, thickness, etc.) and removes any pathogenic energy from around the patient's body.

The doctor continues the treatment by extending his or her intention deep into the patient's body, purging and dispersing the toxic pathogens from out of the patient's internal organs and channels. It is usually during this deep internal purging that the patient experiences profound emotional discharges, observes flashes of light, patterns of colors, see visions, or relives deep seated past emotional traumas. This purging releases toxic emotions which are generally the cause or contributing factor to the patient's disease.


Treating the Patient
1. Use Energetic Circle Drawing to Purge Hot and Cold Pathogens.
2. Dredge and Purge the Patient's Body.
3. Perform Energetic Diagnosis.
4. Find, Locate, Detach, andRemove Energetic Cords.
5. Purge, Tonify and Regulate the Patient's Body.
6. Dispose of Pathogenic Toxins.

Figure 26.5. The Different Steps Involved in Treating a Patient

After the patient has been sufficiently purged and cleansed of pathogenic energy, the Qigong doctor begins to tonify the patient's internal organs, channels, collaterals, and Righteous Qi. This is done to help the patient build a stronger immune system, and fight or avoid any future complications caused by an Excess or Deficient internal organ condition (Figure 26.5).

DREDGING AND PURGING TECHNIQUES

When treating a patient, the doctor purges an internal organ and dredges a channel. The technique of dredging is a particular type of purging method. The energetic circle drawing techniques are always performed with dredging techniques (using the pulling and stroking methods of energy manipulation), to drain the energy into the Earth. These techniques can be initiated with the patients either sitting, standing, or lying.

It should also be noted that the diseased area of a patient's body must be thoroughly dredged and prepared before any kind of tonification or energizing is performed. This technique is similar to a Western doctor cleaning a wound before operating.

If the Qigong doctor does not dredge and purge the pathogens from the patient's body before treating, the patient can suffer adverse reactions when the doctor's clean energy fuses with the patient's Turbid Qi.

DREDGING AND PURGING THE PATIENT

There are two stages of clinical purgation which are described as follows.

1. The doctor dredges and purges the surface pathogens from the patient's body. The doctor moves to the right lateral side of the patient's body and energetically combs the patient's body from head to toes using the Tiger Kneading and/or Extended Fan Palm techniques (in this particular example the patient is lying supine on a treatment table). The combing technique is performed to energetically evaluate the patient's reaction to the doctor's emitted Qi, while dredging the patient's three energetic fields of Wei Qi.
2. The doctor purges from the bottom of the patient's feet. The Qigong doctor stands by the patient's feet and continues to dredge the patient's body by energetically combing the patient from head to toes. This action further purges the patient's body of pathogenic energy.

ENERGETIC DIAGNOSIS

After performing the clinical purgation, the Qigong doctor begins the energetic diagnosis. Some examples of energetic diagnosis are described as follows.

- The doctor can begin energetic diagnosis by first connecting with patient's heels (either by touching or not touching). This particular method and approach to diagnosing allows the Qigong doctor to energetically connect with the patient's inner-fascia. It is through this connection that the Qigong doctor feels the energetic flow of Qi moving through the patient's internal organs. By extending energy from the patient's heels up to the head (like a rippling ocean wave or sonar), the doctor can "listen" for obstructions or deviations of Qi flow.

- Next, the doctor can use the Flat Palm diagnosing technique to scan the patient's entire body for any Excess or Deficient areas within the patient's Wei Qi fields. This second type of diagnosis serves to verify the obstructions or deviations of Qi flow that the doctor discovered while first connecting with the patient's heels.

PURGING, TONIFYING AND REGULATING THE PATIENT'S BODY

After diagnosing the patient's body, the Qigong Doctor purges, tonifies, or regulates the energetic fields, channels, tissues, organs, and organ systems, according to the etiology and prognosis of the disease.

While dredging and purging the patient's body, the Qigong doctor may discover several energetic cords attached to the patient's tissues and internal organs. These energetic cords may sometimes contribute to the cause of the disease.

UNDERSTANDING THE BODY'S ENERGETIC CORDS

The human body attaches, extends, absorbs, and collects energetic cords. The size and shape of these cords can be big, small, thick, or thin, depending on the amount of emotion invested in their attachment. These cords are located within the Three Dantians and Chakra Gates, and form the spiritual, emotional, mental, and physical connection of the patient to the outside world. Generally, what makes the patient sick is not his or her genetic predisposition, but the negative, co-dependent bonds the patient creates in his or her relationship with others. It is the spiritual, emotional, mental, and physical reactions to these relationships that either promote health or disease. Energetic cords are also formed towards objects, pets and places that have special sentimental or emotional value (be they positive or negative) to the patient. Energetic cords are also sometimes used to feed the formation of the preexisting energetic clusters and cysts, which later transform into the patients' diseases.

Energetic cords are the psychophysical connection between what the patient feels, believes and knows to be true; they represent the connection to the patient's personal reality. This does not mean that the patient's reality is valid, only that the patient has come to believe it to be true. By removing these cords an energetic shift is initiated, allowing the patient to reprogram his or her feelings, thinking processes, and behavior, by becoming proactive instead of reactive. Energetic cords are full of light and energy and can be categorized into two distinct divisions: prenatal (congenital) and postnatal (acquired) energetic cords.

- Prenatal Energetic Cords originate in the fetus, when the baby is still in the womb. They form the strong congenital attachment and permanent bond the child has with the mother and father. Because of the mother's energetic/spiritual connection with her egg, and the father's energetic/spiritual connection with his sperm, when the egg and sperm unite, the energetic cords of each parent fuse together with the universal and environmental energy creating the energetic structure of the child. It is through the parents' energetic cords that inherited talents and defects are passed along to the infant.
- Postnatal Energetic Cords are acquired after the baby is born through interaction with siblings, relatives, and other individuals (in some cases animals or places are involved). These cords will either form the emotional attachments which can help the child through life by being a means of support, or set the foundation for disease by depleting the child of his or her life-force energy. They represent the emotional bonding (positive or destructive) inherent within each one of us.

In a clinical environment, the attachment of these cords (prenatal and postnatal) will affect the healing relationship of both the patient and the doctor.

- The Patient's Energetic Cords are still connected to the patient after the pathogenic Qi has been removed from the patient's body. These small cords are the energetic attachments to part of the patient's old belief structure (which created the disease or emotional attachment). Although there is still an energetic connection to the departed pathogenic Qi, these energetic cords will soon disperse once the patient's Creative Subconscious is able to reprogram the individual's belief structures. Only then can the physical body, as well as the mental, emotional and spiritual energetic Wei Qi fields maintain the new energetic pattern. This new belief structure creates an energetic transformation, allowing the patient to release his or her hold on to the painful past and begin to heal. The patient is encouraged to emotionally disconnect from old emotional belief structures through creative visualization, and by affirming the new belief structure. Through affirmation and positive emotional, spiritual visualizations, the patient is able to "sever" any energetic cords that connect to the pain and disease.

- Energetic Cords between the doctor and patient are formed during healing sessions. These new energetic cords are passed back and forth between the Qigong doctor and the patient. Sometimes this occurs without either party being aware of this energetic connection. Usually, as the doctor steps away from the patient and reconnects with the divine, an energetic purging is automatically initiated, freeing the doctor from the attachment to the patient's energetic cords. If, however, there has been an emotional connection between the doctor and the patient, these cords can remain attached even when the patient leaves the office.

  The doctor should make every effort to disconnect from the emotional attachment of the patient's cords, otherwise the increased energetic pull on the doctor's center will affect the doctor on every level. Staying connected to the patient through an energetic cord can cause not only emotional, but physical and spiritual influences on the doctor. Any remaining cord can be used by the patient to unconsciously project thoughts and feelings onto the doctor. This can result in the doctor being depleted of energy either through direct draining of his or her Qi, or through obsessing about the patient's well-being, long after the treatment has ended. The drain of the energetic cord can lead to either clinical "burnout" from absorbing excessive negative emotions, or deep emotional bonding, which can lead to unethical sexual indiscretions.

FINDING, DETACHING, AND REMOVING ENERGETIC CORDS

Energetic cords manifest through their effects on behavior and emotional responses of the patient. They are relationship based patterns, located within the patient's tissues. Energetic based patterns can evoke certain reoccurring emotional responses, such as attractions, addictions, etc.

1. To assist the patients in removing the toxic energetic cords, the Qigong doctor must first locate the cords.
    a. Through the emission of Qi, the doctor may elicit (from the patient) either an attraction or repulsion response. This response occurs when certain memories are stimulated within the patient's body, indicating that there is an energetic cord attached within the tissues.
    - The attraction response causes the patients to experience deep emotional release through laughing, crying, shouting, etc.
    - The repulsion response causes a physical jerking of the patient's muscles, anywhere within the patient's body (observed by the wincing and grimacing of the patient's face). Often the patient will "Shen-out" (emotionally and spiritually leave their body) to avoid feeling the painful surfacing emotions.

    b. The doctor locates the origin and entry point of the energetic cord through Flat Palm detection. The root of an energetic cord acts as an open receptor to a specific psychophysical problem that the patient is experiencing. When stimulated, these cords may manifest physical symptoms such as nausea, hot flashes, vertigo, dizziness, headache, and muscle contractions. The patient may also experience emotional reactions such as momentary panic, fear and so on.

2. Before detaching the energetic cords, the doctor requests the patient's permission to do so either verbally, or silently through mind to mind communication.
3. To remove the energetic cord, the doctor dredges and purges the patient's body, while silently communicating through the Creative Subconscious mind. The doctor encourages the patient to let go of, and fully release, the toxic cords along with the memories that sustain them. To ensure against their recreation, the doctor discusses with the patient any images, emotions or sensations that surfaced during the removal of these cords; through this process the doctor brings the patient's conscious awareness of the fears, pain and major unresolved issues that resulted in the disease. The patient thus gains a clear identification of his or her traumas to facilitate the reprogramming of his or her dysfunctional relationships through affirmations and creative visualizations.

If the patient is not ready for such a transition (feeling scared, unprepared, undeserving, etc.), his or her subconscious mind will sabotage any effort made in that direction, and the energetic cord, emotional cluster and all energetic attachments to the disease will be recreated and reintegrated. It is important in cases such as these, that the Qigong doctor refer the patient out to a psychotherapist for additional support.

In Western society, the Twelve Step Programs (such as Alcoholics Anonymous) are but one example of a pattern based reprogramming of energetic cord attachments. Alcohol and Narcotics Anonymous groups, for example, help detach energetic cords toward illegal substances, whereas, CODA meetings help reprogram the energetic cord attachments to co-dependant relationships. In a co-dependent relationship, both parties rely too heavily on one another, instead of being interdependent. One person usually dominates the other, as both parties base their self-esteem on the partner's approval, or disapproval, thus avoiding the personal responsibility of their own actions.

Energetic reprogramming encourages the participants to take responsibility for filling and replacing the energetic gap that the toxic cord has left with a connection and attachment to the divine, or "Higher Power."

DISPOSING OF PATHOGENIC TOXINS

One problem a doctor may confront when dredging and purging is where to dispose of the patient's toxic and noxious Qi. To maintain a clean treatment room it is essential for this pathogenic energy to be disposed of properly. This will keep both the doctor and other patients from contamination. If the doctor's Qi becomes toxic or contaminated during treatment, this turbid energy may be transmitted to other patients.

Because the patient is in a state of energetic shock (after the therapy), attention must be placed on the patient avoiding contact with the contaminated Qi. Otherwise, there is a possibility of the diseased Qi returning into the patient's body via the energetic cords of attachment connected to the Toxic Qi.

Imagination and visualization are two of the most powerful and widely used techniques employed in healing today for disposing of Toxic Qi. Since we experience reality through creative imagination, pictures, words, and feelings are extremely powerful techniques which can be used to restructure our physical, mental, emotional, energetic, and spiritual foundations. This also holds true for the disposing of the patients' pathogenic Qi.

There are several methods for disposing of the patients' pathogenic energy in the treatment room. These methods include purification by either sound, light, or the Five Elements, in conjunction with disposing of the toxic energy through the energetic vortex.

PURIFICATION BY SOUND AND LIGHT

- Sound penetrates any substance and causes profound shifts in energy, quickly breaking up clusters of stagnant energy. Some examples of sounds used for purifying the treatment room include: music, toning, chanting, singing, wind chimes, gongs, singing bowls, bells, drumming, and clapping the hands.

- Light can be used to cleanse and purify the treatment room of toxic energy, due to the radiant heat emanating from the light source. Some examples of light being used to purify the clinic include: exposure to sunlight, candles, and imagining the divine healing light incinerating any energetic toxic debris.

PURIFICATION BY THE FIVE ELEMENTS

Some Qigong doctors utilize the energy stored within the Five Elements to cleanse the treatment room of toxic debris. This works best in conjunction with the light and sound purification methods. When using one or more of the elements, it is best to consider how much debris has accumulated from the previous treatment and choose accordingly.

1. Dispose of the Toxic Qi through Fire. By burning fire-water (alcohol with salt), lighting a candle, or releasing the Toxic Qi into the Earth's molten core, Toxic Qi can be transformed and purified.
   - To create fire-water, the Qigong doctor places a small amount of alcohol in a round dish and sprinkles a cone of salt (or camphor) in the center of the dish. Next, the doctor lights the salt and allows the smoke to purge the treatment room, making sure that the doors and windows are open to secure clean ventilation.
   - Other Qigong doctors may imagine the center of the Earth as an incinerator. This image is used to purge the patient's Toxic Qi by directing it to the Earth's molten core. Once the patient's Toxic Qi is incinerated (at the speed of thought), the transformed / purified energy is reabsorbed back into the patient's body.
2. Dispose of the Toxic Qi through Water. Water can also be used to absorb toxic energy and for healing and purifying. Some examples of water usages include: Holy Water and salt water. Some doctors use a container of salt water as their disposal unit for the patient's Toxic Qi (Figure 26.6). Once the patient's toxic energy reaches the container of salt water (usually placed underneath the treatment table), it is immediately absorbed due to the molecular structure of the salt crystals. Sometimes it is advisable for the Qigong doctor (after a full day at the clinic, or at the end of a busy week) to submerge him or herself in a baking soda or take an Epsom salt bath in order to cleanse and purify the body.
3. Dispose of the Toxic Qi through Wind / Air. Wind and air can be used to purify the room of toxic energy. Some examples of this include open air ventilation along with the placement of indoor plants.
4. Dispose of the Toxic Qi through Divine Healing Light. Some doctors dispose of the patient's pathogens into the air, where it is immediately incinerated by a divine healing light. Because of the preestablished divine healing field of energy, once the patient's toxic energy leaves the doctor's hand, it is immediately absorbed by the divine healing light and is instantly transformed into purified energy and reabsorbed back into the patient's body.
5. Dispose of the Toxic Qi through Wood. Wood can also be used to purge toxic energy from the treatment room. Some examples of the Wood Element used to cleanse the room are: the burning of incense or herbs such as myrrh, frankincense, cedar, sage (an old American Indian method), sandalwood or camphor.
6. Dispose of the Toxic Qi through the Earth. Certain stones can be used in the clinic because of their ability to absorb Toxic Qi. Strategically placed in the clinic, these Earth Elements can be used as a natural filtering device. Some examples of this include: amethyst, salt, clear and colored quartz, as well as many other minerals or gemstones. These crystals require cleaning at the end of each treatment day to dispose of the toxic Qi they have absorbed, and should be cleansed by placing them in salt water till they are clean, or burying them in the ground for three days.



Figure 26.6. One example of a Qigong doctor using a rubber acupuncture doll for treating and disposing of the patient's toxic energy into salt water.

MEDICAL QIGONG TREATMENTS

The following is a clinical procedure that a Medical Qigong doctor will use when treating a patient. The clinical procedure known as the "preparation" remains the same for all Medical Qigong treatments (i.e., the hook-up, dredging and purging the patient, as well as energetic diagnosing). However, the initial treatment will vary depending on the patient's constitution, disease, and personal goals.

After scanning the patient the doctor has a solid understanding of which areas or organs in the patient's body are currently in a state of Excess or Deficiency. The doctor then chooses which area to begin dredging and purging in accordance with the treatment plan. Only after purging all areas of Excess should the doctor then move to tonifying those areas that are Deficient.

TONIFYING A PATIENT'S BODY

After completing the diagnosis, if you have determined that the patient's body is not in an Excess condition, but is instead constitutionally weak or depleted due to Kidney exhaustion, the treatment may be continued as follows.

1. Begin by extending energy through the patient's Yongquan Kd-1 point at the bottom of each foot. Imagine that the Qi is ascending up the patient's legs, via the Yin channels, filling the Lower Dantian, Kidneys, thorax and spinal column into the brain. Hold this position for several breaths, then proceed to the next area.
2. Physically embrace the area of the patient's ankle with one palm, while the other palm embraces the Kd-1 point on the same foot. Start with the right ankle first and then the

left. Project energy into the foot and ankle, by holding the mind's intention on that specific area for several breaths, then begin circling the energy up the Yin channels and down the Yang channels. Hold this position for several breaths, then proceed to the next area.

3. Energize each of the patient's knees (back and sides) by holding the mind's intention on those specific areas for several breaths, then connect each knee to the Yongquan Kd-1 point at the bottom of each foot (the right foot first, then the left). Connect and emit energy into the bottom of each foot to the knee, circling the Qi up the Yin channels and down the Yang channels. Hold this position for several breaths, then proceed to the next area.
4. Energize each of the patient's hips, by holding the mind's intention on that specific area for several breaths, then connect each hip to the Yongquan Kd-1 point at the bottom of each foot (right first, then the left). Connect and project energy into the bottom of each foot to the hips, circling the Qi up the Yin Channels and down the Yang Channels. Hold for several breaths, then proceed to the next area.
5. Energize the patient's Lower Dantian by holding the mind's intention on that specific area for several breaths, allowing the Qi to completely fill up the energetic chamber. Place your left hand on the patient's Mingmen GV-4 point. Your right hand is placed on the patient's navel (CV-8) with your fingers extending down to the patient's Qihai CV-6 point. Mentally connect the Lower Dantian with both Yongquan Kd-1 points on the bottom of the patient's feet and imagine the energy simultaneously traveling down the outside of both legs into the feet. Imagine the energy from the feet continuing to travel along the inside of both legs back into the patient's Lower Dantian area. Hold this intention for several breaths, then proceed to the next area.
6. Energize the patient's Yellow Court by holding the mind's intention there for several breaths. Your left hand is placed on the Jizhong GV-6 point, your right hand should be placed on the Juiwei CV-15 point. Mentally connect the Yellow Court with the patient's Lower Dantian, allowing this energy to connect and fuse both areas. Hold this intention for several breaths, then proceed to the next area.
7. Energize the patient's Middle Dantian by holding the mind's intention there for several breaths. Place your left hand on the Shendao GV-11 point, while your right hand is placed on the Shanzhong CV-17 point. Mentally connect the Middle Dantian area with the patient's Lower Dantian. Hold this position for several breaths, then proceed to the next area.
8. Energize the patient's throat area by holding the mind's intention on that specific area for several breaths. Your left hand is placed on the Dazhui GV-14 point, while your right hand is placed on the Tiantu CV-22 point. Mentally connect the throat area to the Middle Dantian area, then to the patient's Lower Dantian. Hold this intention for several breaths, then proceed to the next area.
9. Energize the patient's Upper Dantian area by holding the mind's intention there for several breaths. Your left hand should be placed to stimulate the occipital region at the Naohu GV-17 point. Your right hand is simultaneously stimulating the Yintang (Third Eye) and Baihui (GV-20) areas. Mentally connect the Upper Dantian area to the Middle Dantian first, and then to the patient's Lower Dantian. Hold this intention for several breaths, then proceed to the next area.
10. Regulate the patient's Microcosmic Orbit, to balance the Heart Fire and Kidney Water energy. Remove your hands from the patient's body, yet still remain energetically connected through your intention. Having stepped away from the treatment table, continue treating the patient with external Qi emission, regulating the patient's Microcosmic Orbit (extending energy up the Governing Vessel and down the Conception Vessel). Hold this intention for several breaths, then proceed to the final step in the treatment.

11. Envelop and seal the patient's three external fields of Wei Qi by connecting the patient's body with the divine energetic field. Hold this intention for several breaths, then proceed to the "closure."
12. Disconnect yourself from the patient and close the healing session. Be sure to disconnect physically, mentally, emotionally, energetically, and spiritually from the patient by willfully detaching all energetic connections to the patient.
13. After disconnecting from the patient, center yourself, then regulate your own energetic fields to balance, recharge, and replenish any energetic depletion.
14. Finally, after you have completed centering yourself, finish the cleansing by washing your hands to purge any of the patient's lingering pathogens which may still be attached to your body.

GENERAL THERAPEUTIC TREATMENT

The following is an example of a clinical routine used in the Medical Qigong Clinic for "emotional purging." The following purging routine is separate from the previous clinical modalities for tonifying a patient. It is important to note that when treating a patient, the Qigong doctor usually purges the patient's Liver and Lungs before tonifying the Spleen and Kidneys.

After completing the diagnosis, if you have determined that the patient has both Excess and Deficient conditions, you may decide to continue the treatment as follow.

1. Begin by dredging, purging, and activating (energizing) the patient's Upper Dantian area to reconnect the patient to the divine, to activate the patient's spiritual/emotional presence.
   a. Start by purging the patient's Upper Dantian.
   b. Then regulate and energize the patient's Upper Dantian by performing a small Microcosmic Orbit within the patient's head.
   c. Finally energize the patient's Taiji Pole through the Baihui area.
2. Purge and dredge the patient's Lungs, to disperse the emotions of grief and despair caused by "rejection, betrayal, and abandonment issues" which are stored in the patient's Lungs.
   a. Start by dredging the patient's neck (trapezius, clavicle, and manubrium) of grief and despair. Begin by standing on the right side of the patient's body, and use the Kneading Tiger Palm and Dragon's Mouth Palm hand techniques (see Chapter 33) to pull the Toxic Qi from the patient's body. Switch from the right to the left side and continue purging.
   b. Then roll the patient's shoulders back to open the Lungs and to facilitate their purging of any deep seated grief. Start on the left Lung first. This area is responsible for storing the emotions related to the patient's mother.
   c. Next dredge the inside Yin Channels of the patient's left arm by using Qi Massage techniques (see Chapter 37).
   d. Regulate and treat the patient's body through "hand diagnosis and treatment" (based on energetic hand/body association, see Chapter 25) by focusing on the patient's left hand.
   e. Finally, begin the entire Lung purging procedure again, this time focusing the attention on the right side of the patient's body. This side reflects the patient's issues with his or her father.
3. Regulate and tonify the patient's Heart to calm the Spirit.
   a. Your left hand connects and extends energy deep into the patient's Shendao GV-11 point, the area in-between the patient's shoulder blades. Your right hand connects to the Shanzhong CV-17 point above the patient's Heart, purging emotional toxins.
   b. Finally, regulate the Heart by circulating Qi through the patient's upper Microcosmic Orbit (between patient's Upper and Middle Dantian). This reconnects the divine light emanating

from the Upper Dantian back with the spiritual emotions (unconditional love, devotion, etc.) stored within the upper chamber of the Heart (see Chapter 5).

4. Purge and dredge the patient's Yellow Court to rid the body of toxic emotions stored within the tissues of the Yellow Court. Your left hand remains secure on the patient's back, at the Shendao point to maintain contact with the Heart Qi. The patient's true feelings are stored within the Yellow Court and expressed through the patient's Heart. Place your right hand on patient's Juiwei CV-15 point, located below the patient's xiphoid process. Sometimes you may see images of the patient's past as traumas are released from the tissues.
5. Your left hand remains secure on the patient's back, at the Shendao point while your right hand purges the patient's Liver organ of anger and depression caused through the storing of "rejection, betrayal and abandonment issues." As you dredge the Liver's Hot toxic emotions from out of the patient's body, purge the pathogens out the patient's right Gall Bladder Channel.
6. Keep your left hand on the patient's back, at the Shendao point while you tonify and regulate the patient's Spleen with your right hand.
7. With your left hand on the patient's back, at the Shendao point, tonify and regulate the patient's Kidneys with your right hand.
8. Maintain contact with the patient's back, at the Shendao point, as your right hand connects with the patient's Mingmen (GV-4) area to regulate all three Dantians. This is initiated through the Microcosmic Orbit (extending energy up the Governing Vessel and down the Conception Vessel), to balance all of the patient's energetic reservoirs.
9. Then slowly remove your hands from the patient's body, but remain energetically connected through intention. Step away from the treatment table, as you continue to regulate the patient's Microcosmic Orbit. Hold this intention for several breaths, then proceed to end the treatment.
10. Envelop and seal the patient's three external fields of Wei Qi, by connecting the patient's body with the divine energetic field. Hold this intention for several breaths, then proceed to the "closure."
11. Disconnect physically, mentally, emotionally, and spiritually from the patient to close the healing session. It is important to shake or whip your palms to completely disconnect from the patient's energy. The shaking or whipping action frees the doctor from any energetic attachment which may have occurred while treating the patient.
12. After disconnecting from the patient, center yourself, then regulate your own energetic field. This balances, recharges, and replenishes any energetic depletion you may have suffered during the treatment session. If you are affected by any pathogenic Qi, immediately expel it from your body.
    a. Next, focus your attention on your Taiji Pole, imagining both the universal and environmental energy collecting, absorbing, and resonating deep within your Lower Dantian and center core. This image draws Qi into your body like a magnet, replenishing any energetic depletion you may have experienced. By placing the fingertips together in front of the Lower Dantian, you will further facilitate the replenishment of the energy.
    b. During this time the patient is allowed to continue relaxing on the treatment table and to slowly come out of the trance state induced by the treatment. The patient should then allow the Yuan Qi to settle back to its origin (the Lower Dantian), by relaxing and calming the mind, breathing, and posture. Instruct the patient not to wash the area that was treated for several hours because water absorbs some of the Qi that was projected into the diseased area.
13. Finally, wash your hands, using tepid water (hot water allows turbid Qi to enter the



Figure 26.7. As the patients practice their own individual Medical Qigong prescriptions, the Qigong doctor extends energy into the patients, helping to facilitate a stronger therapeutic reaction.

doctor's channels, cold water closes off the channels) to purge any of the patient's lingering pathogens.

ADJUSTING AND FORTIFYING THE PATIENT'S ENERGETIC GRIDS

At the end of the treatment the doctor regulates the patient's energetic fields by adjusting and fortifying the patient's energetic grids (the webbing within the patient's energetic fields). This keeps the patient's energy in harmony, allowing both his or her internal and external fields to operate at their maximum potential for health and healing.

The Qigong doctor adjusts and fortifies the patient's energetic grids, to initiate a permanent energetic transformation for healing within the patient's energetic fields, tissues, and cells. The body's energetic grids are responsible for tissue formation and for maintaining the production, growth, and development of energy. These grids are influenced by thoughts and emotions.

The creative subconscious mind maintains the body's energetic grid formations and causes the physical body to act (grow stronger or weaker) in accordance with the energetic "blueprint" encoded within the structure or webbing. After the Qigong doctor has changed, or corrected, the energetic grid, the patient is given Medical Qigong prescriptions (homework) in the form of visualizations and affirmation meditations, as well as Qigong exercises.

TREATING MULTIPLE PATIENTS

Once an energetic field in the treatment room is established, the patients can begin their individual Qigong regulations. The doctors position themselves according to the number of patients needing treatments; for example, one doctor may be positioned in front of several patients and extend Qi into the patients' energetic fields (Figure 26.7). The doctors' postures and energy extension varies according to their individual skill and energy projection level. It is important for Qigong



Figure 26.8. The Qigong doctors will position themselves back to back, in the center of a circle, in order to induce energetic movement within the multiple patients' tissues.

doctors to set the pace for treatment. The patients' rhythm is based on the pulse and vibration of the Qigong doctors.

In China, doctors usually rotate every fifteen minutes when treating patients. This prevents the doctors from fatiguing while allowing the patients to absorb new and fresh Qi every fifteen minutes.

If only one or two Qigong doctors are available when treating several patients, then the doctors will position themselves back to back in the middle of the room, with their patients surrounding them in a circle (Figure 26.8). After several minutes the doctors will slowly begin to rotate the center circle extending their energy, and treating each patient individually. The doctor's emitted Qi combines and synergizes with the patient's Qi to produce a much stronger energetic healing field.

By establishing a treatment room that facilitates the regulation of the patients' Qi, the treatments tend to become more effective with faster results. In China, patients are treated in a group treatment room environment three times every day (sunrise, sunset, plus one time before bed).

ENDING THE TREATMENT

When the treatment is over, encourage each patient to relax and then return the patients' Qi back to its origin (the Lower Dantian). The duration of the treatment time, and proper recuperation after Medical Qigong treatment will be addressed next.

DURATION OF TREATMENT TIME

The duration of treatment time varies according to each patient's disease, condition, constitution, and age. A long treatment is usually between twenty and thirty minutes and is generally performed on cancer patients, senior citizens, or for severe traumatic or chronic illnesses. A short treatment is generally between three to fifteen minutes and is usually administered for athletic sprains and ligament dislocations.

PROPER RECUPERATION AFTER MEDICAL QIGONG TREATMENT

Proper recuperation is very important for the replenishment of strength and energy after the treatment session (even after the patient's own prescription practice). This may include having the patient change his or her life activities. The patient must incorporate a balance of work and rest, and acquire regular healthy eating habits (with reasonable nutritional goals). Establishing adequate sleeping patterns is also necessary. Of equal importance is an open-minded positive attitude by the patient, for this reason, a supportive network can be invaluable.

After the Qigong treatment the patient is also encouraged to avoid cold showers, the consumption of alcohol, excessive sex, and recreational drugs. Also prohibited is anything that will emotionally shock the patient, as remaining in a quiet state of mind and spirit is essential.

CHAPTER 27
COMBINING MEDICAL QIGONG THERAPY WITH OTHER HEALING MODALITIES

COMBINING MEDICAL QIGONG THERAPY WITH TCM MODALITIES

Traditional Chinese Medical treatments in conjunction with clinical Qigong modalities are generally broken down into exclusive Medical Qigong Therapy, Medical Qigong and Chinese Massage Therapy, Medical Qigong and Acupuncture/Moxa Therapy, and Medical Qigong and Herbal Medicine Therapy.

EXCLUSIVE MEDICAL QIGONG THERAPY

Medical Qigong therapy can be administered by the Qigong doctor (Figure 27.1) to tonify and promote energy circulation or to sedate the body's energetic channels and collaterals. Qigong prescriptions can also be given for the patient to practice alone. Medical Qigong therapy by itself is excellent for the treatment of ailments such as:

- Insomnia
- Neurasthenia (Chronic Fatigue)
- Hypertension
- Stroke
- Acute abdominal pain
- Injuries to the nerves
- Hemopleura (Blood in the walls of the thorax and diaphragm, along the pleural space)
- Myopia
- Migraines
- Muscle atrophy
- Sprains
- Cancer
- Tumors
- Cysts

MEDICAL QIGONG AND CHINESE MASSAGE THERAPY

Medical Qigong therapy in conjunction with Chinese Massage therapy is a powerful form of combined clinical modalities (Figure 27.2). It enhances tissue response as well as the activation of psychophysical reactions within the body. These therapies can be combined to clear the joints before setting the bones (as in Jie Gu therapy), to purge and dredge the channels to adjust the Qi circulation before regulating the body's muscular system (as in Tui Na and Gua Sha therapies), or to disperse toxins before regulating the body's internal viscera



Figure 27.1. Medical Qigong Therapy



Figure 27.2. Medical Qigong Therapy with Chinese Tissue Regulation Therapy

(as in An Mo and Jing Point therapies). Qigong and Chinese Massage therapy are most commonly used in the treatments of patients with:

- Deep tissue obstruction
- Stiff muscles
- Frozen shoulder
- Low sensitivity to emitted energy

MEDICAL QIGONG AND ACUPUNCTURE/MOXA THERAPY

Acupuncture needles are inserted into the patient's body before the doctor extends Qi into the patient to facilitate healing (Figure 27.3). This also applies in the treatment of Moxa sticks in which the doctor extends energy into the patient through the burning herb. The combined energies (the Moxa heat and doctor's own Qi) initiates increased Qi flow within the patient's channels resulting in a stronger tonification. Moxa is especially beneficial in the treatment of arthritis. Qigong and Acupuncture therapy are combined in tonification or purgation treatment.

MEDICAL QIGONG AND HERBAL MEDICINE

Medical Qigong Therapy in combination with herbal therapies (or with pharmaceutical prescriptions) are becoming more popular. There is ample evidence that the combination of self-applied Medical Qigong therapy and drug therapy is far superior to that of drug therapy alone. In China, this data is reported in several studies of patients with hypertension as well as in cancer patients.

Medical Qigong therapy relaxes the body, promotes the flow of Qi, Blood, oxygen, and nutrients to all cells of the body, as well as promotes the removal of waste products from the cells. Medical Qigong also promotes drug uptake by the cells and tissues by means of increased microcirculation within the body's microcirculatory system. This increased Qi flow through the body's microcirculation nourishes diseased or stressed tissues.

One diagnostic herbal technique I observed at the Xi Yuan Hospital was performed by a Qigong doctor who absorbed into his body the effects of a specific medicine by touching the bottle that contained the herbs. He then extended energy to his patient and began absorbing the patient's Qi to see if the patient's body was affected by the herbal prescription (Figure 27.4).

The Qigong doctor is encouraged to prescribe herbs along with certain of the Medical Qigong exercises. If the Qigong doctor is not qualified to prescribe Chinese medical herbs, then a referral can be made to an acupuncturist/herbalist. The herbal prescriptions will vary according to the patient's condition, constitution and illness.



Figure 27.3. Medical Qigong Therapy with Acupuncture



Figure 27.4. A Qigong Doctor Testing the Efficacy of a Specific Herbal Medicine for his Patient

Qigong and herbal therapies are most commonly used in the treatments of:

- Tumors
- Stomach cancer
- Lung cancer
- Hepatitis
- AIDS
- Stroke

COMBINING MEDICAL QIGONG THERAPY WITH WESTERN MEDICAL MODALITIES

Traditional Chinese Medical Qigong serves as a powerful tool in aiding Western medical approaches in alleviating patients' suffering. Because of its emphasis on mental, emotional, energetic, and spiritual approaches to healing, Medical Qigong therapy has been successfully combined as a complementary source of medical treatment with the following Western professional approaches:

- Pediatrics
- Geriatrics
- Gynecology
- Neurology
- Psychology
- Oncology
- Surgery

CHAPTER 28
PRECAUTIONS AND ETHICAL CONSIDERATIONS FOR THE QIGONG DOCTOR

AVOIDING ENERGETIC DEPLETION

Because Medical Qigong therapy consumes energy, as long as the Qigong doctor's quantity of energy is higher than that of the patient's, the doctor can transmit energy into the patient with no ill effect. If, however, the doctor is very tired or depleted and tries to treat a patient, the energy that the doctor is able to produce may become weaker than that of the patient.

It is important to note that energy currents flow from high to low (much like water). Therefore, the doctor may, if in a weakened state, absorb the Turbid Qi or disease energies from the patient. Any imbalance in the doctor's organ system can increase the doctor's vulnerability to foreign pathogens. These pathogenic sensations may also be transmitted into the body of healthy people, or other patients as well. Individuals who have not practiced Qigong, however, and whose energy circulation and channel points are not open, are not as prone to interference by these sensations. These individuals have a natural barrier, or to put it plainly, they are not sensitive to energetic fields of transmission and because of their denial system, cannot perceive energy sensations.

If the Qigong doctor already has a tendency towards a particular illness, exposure to pathogens may instigate or intensify the disease. If the doctor is suffering from any energetic Deficiencies, for example, the end result may be that the doctor performing the treatment may experience Qi deviations due to absorbing the patient's Toxic Qi. This means that more Qi and energy have been extended outside of the doctor's body than can be replenished, weakening the doctor's energetic constitution.

When treating patients the doctors receive and diagnose information from their Six Openings (also called the Six Windows of the Body). These Six Openings are described as follows:

- The eyes -- open for seeing energy patterns and colors,
- The ears -- open for hearing energy patterns and tones,
- The nose -- opens for smelling different odors,
- The tongue -- opens for tasting or flavor sensing,
- The body -- opens for energetic feeling sensations, and
- The Spirit (Heart/Mind) -- opens for energetic perceptions of emotions, thoughts, and spiritual insight.

While using the Six Openings for diagnosis, the doctor naturally depletes some life-force energy. Since all five organs (eyes, ears, nose, tongue, and body) are directed by the doctor's Spirit (Shen), the expenditure of energy is considerable. Any imbalance due to organ depletion will cause the doctor to absorb Turbid Qi from the patient. This Turbid Qi can move within the doctor's body causing Qi deviations, especially if it mixes with the doctor's Clear Qi.

1. If this happens within the doctor's Upper Dantian, the symptoms may include mental fatigue, dizziness, headaches, etc.
2. If this happens within the doctor's Middle Dantian, the symptoms may include emotional fatigue, discomfort in the Liver (hepatic region), etc.
3. If this happens within the doctor's Lower Dantian, the symptoms may include physical fatigue, cold in the extremities, discomfort in the lower abdomen, etc.

This is why Qigong doctors must constantly be refilling and rebalancing themselves energetically. It is important to note that if the Qigong doctor has indeed ingested the patient's pathogens, and Qi deviations have resulted, no Western doctor, acupuncturist, or herbalist can help him or her. Only the doctor with the Qi deviation (or with the help of another Qigong doctor) can change the Turbid Qi back to Clear Qi, by using divine energy and purging the body's Shen, Qi, and finally the Jing. This supports the doctor's Righteous Qi and fights the invasions of the patient's pathogens.

Emission of Qi should also be avoided if the doctor becomes sick, tired, hungry, overfed, deeply grieved, indignant, or drunk. Also, if the doctor is unable to stay in the present mind-frame he or she will inevitably fall asleep or "Shen out." To avoid this state of depletion, the Qigong doctor should:

- Cut back on the number of patients,
- Decrease treatment time—from 25 to 20 minutes maximum,
- Maintain a consistently healthy diet with supplements,
- Receive frequent exposure to fresh air and sunlight, and
- Perform the Microcosmic or other regulating Qi meditations in between patients.

Note: When treating patients with Medical Qigong therapy the doctor should never wear the color red. The color red is too hot and has a dispersing affect on Qi, which tends to scatter the body's energetic fields, distorting the Qigong doctor's Qi emission.

PREVENTING THE INVASION OF TURBID QI

When Turbid Qi enters the doctor's body, it interferes with normal Qi circulation, causing disorders in part of, or in all of the energy circulatory system. In mild cases, Qi may stagnate in a certain areas of the body (i.e., shoulder, arm, chest, or back), causing physical and mental symptoms.

- Physical symptoms may include: tingling, pain, cold, contraction, heaviness, soreness, and distention and stuffiness in the chest; and
- Mental symptoms may include: interference with mental activity, causing dizziness, headache, heaviness in the head, vexation, and restlessness.

In severe cases, the doctor may experience the same symptoms as the patient, but upon physical examination there is no verification of any existing disease. The doctor should therefore be on the alert to avoid any danger of developing symptoms from the patient after Turbid Qi is perceived.



Figure 28.1. In order to disperse the patient's Evil Qi, the Qigong doctor exhales while slinging the toxic energy into the Earth.

It is very important for doctors who treat patients with Medical Qigong therapy to possess the ability to prevent and expel Turbid Qi so that it will not disturb their own energetic activities. Qi deviations are most often seen in those individuals who treat patients after they have gained some knowledge of Medical Qigong but have no experience, though they can occur even to some veterans of Medical Qigong practice. The interference by Turbid Qi is often an important factor in the the doctor's health.

When the interference by Turbid Qi is perceived, the doctor should use proper hand manipulations and readjust energy activities to expel the Turbid Qi immediately. If the Turbid Qi invades the doctor's fingers, or penetrates into certain channels or points, the doctor should guide the Qi to the specific points, channels, and infected areas and then relax and shake the hands to discharge the Turbid Qi while exhaling.



Figure 28.2. The Qigong doctor gathers energy into his or her Lower Dantian and expels any and all pathogenic invasions out through the hands and feet.



Figure 28.3. To avoid absorbing the emotions from an energetic discharge (released from dissolving an energetic cluster), the Qigong doctor turns his or her head and expels the patient's toxic emotions.

The doctor should be able to stop the Turbid Qi before it reaches the Dazhui GV-14 point on the upper back, Tiantu CV-22 point at the base of the throat, Quepen St-12 points on the front of the shoulders, and the Fengfu GV-16 and Fengchi GB-20 points on the back of the head. It is important to expel the Turbid Qi when it has reached the fingers, wrists, elbows, and at most the shoulders.

When this occurs the doctor should drive the Evil Qi out and regulate his or her Qi circulation as soon as possible. There are several ways to do this:

- Exhale while swinging the arms toward the ground, driving the Evil Qi deep into the center of the Earth. When treating tumors, be careful to disperse the pathogens out your fingers and do not allow the toxins to stick to your palms (Figure 28.1).
- Exhale while "blowing Qi" (extending Qi) out of the palms (Pc-8) and feet (Kd-1) (Figure 28.2).
- Exhale out of the mouth (but never over the patient, or towards anyone else). A shift in breathing is a common reaction when the emotions are discharged, or when an energetic cluster is reached (Figure 28.3).

GUIDELINES FOR THE MEDICAL QIGONG DOCTOR

1. The Qigong doctor must avoid practicing Medical Qigong in wet clothes. If the doctor perspires a little when training, he or she should avoid standing in the wind; if the doctor perspires profusely, practicing should be discontinued as it is liable to damage the doctor's Yin Qi.
2. The doctor should not go to the toilet within half an hour after practicing in order to avoid developing a conditioned reflex. This will help prevent the leakage of vital energy.
3. Patients suffering from cancer may affect the doctor's Qi circulation more seriously. Care should be taken when treating these patients, or avoid treating them completely, until sufficient energy has been cultivated, and sufficient experience has been gained.
4. The doctor must always wash his or her hands

with soap after each patient's treatment to prevent the energetic transference of diseases. It is important to note that washing the hands in cold water immediately after Qi emission is harmful to the doctor's energetic field because of the sudden shock to the system. Washing with hot water immediately after treatment, opens the channels on the doctor's hands and arms, sending the Toxic Qi deep into the doctor's body. To avoid these complications, the doctor should wait several minutes after completing the treatment, before washing his or her hands.

While waiting, the doctor should touch his or her finger tips together and focus on the Lower Dantian, allowing the Qi to settle back into its origin (minimum of three minutes). The doctor then washes up to the elbows with water that is room temperature to reduce the possibility of absorbing the patient's Turbid Qi.

If the doctor is not able, during treatment, to expel the Turbid Qi right away because of some distraction, or if the doctor's internal energy is not substantial, the Turbid Qi may enter his or her body through the fingers traveling up the wrists, elbows, or entering the Baihui GV-20, Tanzhong CV-17, Fengchi GB-20, Yintang (Extra Point) and Yongqauan Kd-1 points. If this begins to happen, the doctor should not continue to extend energy, but should stop the treatment immediately and perform a "closing," expelling the Turbid Qi by flicking the fingers, wrists, and shaking the arms until all discomfort has been eliminated. If any Turbid Qi still lingers, the doctor should practice Medical Qigong exercises to regulate the energetic activities.

5. It is important that doctors, as well as patients, avoid strenuous activities (such as running immediately after Medical Qigong exercises) to prevent the wrong flow of vital energy or pain in the legs. It is always better for the doctors and patients to be active first (running, swimming, forms training, etc.) and then cool down with the Medical Qigong Quiescent exercises (unless otherwise prescribed).

WU ZANG (FIVE ORGAN) MEDITATION FOR ENERGETIC PROTECTION

Even after the treatment of diseases, the doctor must perform certain Medical Qigong exercises to prevent and expel any undetected pathogenic Qi. Otherwise the doctor may develop the symptoms of the illness of the patient in corresponding locations. For instance, if the patient has a headache or pain in the hepatic area, the doctor may also acquire a feeling of discomfort, numbness, itching, and pain in the head and hepatic region. Therefore, in clinical practice, a deep understanding and correct judgment of the pathogenic Evils is compulsory.

Today in China, the Wu Zang meditation is still taught to Qigong doctors for clinical use to prevent invasion from the patient's pathogenic Qi. This meditation requires the doctor's Shen to guide the Qi of the Five Yin Organs (also known as the Wu Jing Shen, see Figure 28.4), to make the body's Qi substantial. The ending of the meditation, which causes the doctor's Qi to be reabsorbed into the Taiji Pole, allows the transformed Qi to flow into the appropriate organs, strengthening the doctor's energetic fields.

When a Qigong doctor enters the space of a diseased patient, the potential for absorbing the patient's pathogenic Qi is high. Noting this potential for harm, the ancient Chinese Qigong masters developed certain meditations to protect themselves from the patient's diseased or Turbid energy.

The Yellow Emperor's Classics on Internal Medicine states that before treating patients of any kind, the doctor should first perform the Wu Zang Energy meditation. It encouraged doctors to practice this meditation before treating patients in a clinical environment and before entering the treatment room, because it surrounds them with a strong field of protective energy (Wei Qi).

The Wu Zang meditation focuses on six directions (north, south, east, west, Heaven and Earth). It is very powerful and can be used to gather environmental Qi at the beginning of each season. The focus of the meditation is to extend each of the five organs' energy far into the horizon to gather the Qi. When practicing the Wu Zang


Fire
Front
Heart
(Red Phoenix)
Spirit
Left
Wood
Liver
(Green Dragon)
Spirit/Soul
Golden Sun
Intention
Spleen
Center
Lungs
(White Tiger)
Material Soul
Right
Metal
Kidneys
Dark-Blue Turtle
Essence
Back
Water

Figure 28.4. The Wu Jing Shen Relationship of the Wu Zang Meditation

meditation the Qigong doctor should:

- face east during the spring equinox;
- face south on the day of the summer solstice;
- concentration on the center of the Earth during late summer, before the fall equinox;
- face west on the day of the fall equinox;
- face north on the winter solstice.

Start by focusing on the center of the body. Imagine opening up the Baihui point (at the top of the head) and begin to pull in the Qi from the Heavens. Imagine the divine light as a bright shining white light, illuminating and filling your entire body through the Baihui. Feel the body radiating this divine white light energy. Next, imagine this white light energy coalescing into the body's center core, forming an energetic tube of Heavenly energy that extends from the Baihui point to the Huiyin point. The center core vibrates and resonates with the divine white light energy.

1. Now, imagine a golden yellow mist of Qi arising from under the Earth and filling your body and connecting with the Spleen organ. Next, feel this golden light Earth energy envelop the center core of divine white light energy, merging together and synergizing. This represents the energy of your Yi (Intention), to root and stabilize your power.
2. Begin to focus on your Heart and imagine a portal opening and the Qi flowing out of your Heart like a red swirling wind in front of you, full of power, protecting you with your Shen and the fire of a red phoenix. This represents your innate spirit, alive, graceful yet powerful.
3. Focus your attention on your back and the Kidneys and Mingmen area. Imagine a portal opening and the Qi flowing out of your Mingmen behind you like water. Out of this water grows an enormous dark blue turtle,



Figure 28.5. The Wu Zang Meditation

whose shell protects you like a mighty shield. This represents the energy of your Zhi (Willpower), and the Jing and Zhi of all your ancestors, backing you and supporting you.

4. Place your attention on your Lungs and visualize a portal opening on your right side of your body, under the right ribs. Imagine the Lung Qi flowing out of to the right side of your body like steam, forming a white tiger, as strong as steel. This represents the Po and the body's animal nature, that guards and protects you with an animal passion for survival.
5. Next, place your attention on your Liver and visualize a portal opening on your left side of your body, under the left ribs. Imagine the Liver Qi flowing out of to the left side of your body like steam, forming a green dragon, sinewy and resilient as bamboo. This represents the Hun and the body's divine nature, guarding and protecting you with a spiritual passion for victory.
6. Each animal begins to rotate to the left, protecting, stalking, and defending the previous animal's position (Figure 28.5). Slowly begin

to circle these energies, then increase their speed (like a mighty wind) counterclockwise around your body, blending these colors together, to form an energy bubble.

After forming a protective rainbow hue around your body, draw the energies back in through the Baihui point and return the energy of each organ color back to its origin (the color red returns back to the Heart, dark blue to the Kidneys, white to the Lungs, and green back to the Liver). As the colors return back to their organ of origin, imagine steam (white light) flowing out of the pores and filling up the energy bubble created by the animal rotation. This forms a solid connection between the body's internal organs and the body's external field of energy.

7. When the protection of the body with the Five Elements is done, imagine that there are many sparkling lights like the Big Dipper above your head. Then you can enter the room of the patient, safe and protected.

Keep in mind that you can send the five organ energy outside of your body instantly, any time you need protection. Some schools teach the doctor to extend his or her energy like mist out through the eyes, enveloping the body with the five organ colors (green, red, yellow, white, and dark blue/indigo).

CREATING A PROTECTIVE ENERGETIC FORCE FIELD

This second meditation also establishes a powerful energetic force field, needed to protect the doctor from any attack or attachment of external pathogenic Qi. It consists of wrapping the doctor's external fields of Wei Qi to increase the energetic field's power.

This is similar to wrapping a magnet with coils of wire to increase its magnetic field (Figure 28.6).



Figure 28.6. Creating a Protective Energetic Forcefield

1. Begin from a standing Wuji posture. Focus on all the body's energy collecting into the Lower Dantian. Concentrate the Qi in the Lower Dantian, condensing it into a dense ball of white light energy. Imagine this ball of white light energy exiting the body through the navel and circling the body, spinning in a counterclockwise direction nine times, wrapping the Belt Vessel, Mingmen GV-4 and Shenque CV-8 points.
2. Move the energy ball down to the perineum and continue circling the lower body in a counterclockwise direction nine times, spinning and wrapping the Huiyin CV-1 and Changqiang GV-1 points.
3. Move the energy ball down to the knees and continue circling in a counterclockwise direction nine times, spinning and wrapping the ascending Yin channels and descending Yang channels of the legs.
4. Move the energy ball down to the ankles and continue circling in a counterclockwise direc-

tion nine times, spinning and wrapping the ascending Yin channels and descending Yang channels of the legs.

5. Move the energy ball down to the bottom of the feet and continue circling in a counterclockwise direction nine times, spinning and wrapping the Yongquan Kd-1 points.
6. Move the energy ball several feet into the ground and continue circling in a counterclockwise direction nine times, spinning and wrapping the body's Earth Transpersonal point. This energetic point (under the ground) is responsible for establishing the body's rooted connection to the Earth and for absorbing the Earth energy into the body's internal organs, channels, and collaterals.
7. Next, imagine the energy ball slowing down and stopping its rotation, pulsing for several heartbeats, then reversing its energetic rotation, and beginning to spin in a clockwise direction nine times. The direction and flow of the energetic ball now reverses its orbit, ascending and circling the same areas and points nine times, until it returns back to the navel.
8. From the navel move the energy ball up to the solar plexus area and continue circling the body in a clockwise direction nine times, spinning and wrapping the Jiuwei CV-15 and Zhiyang GV-9 points.
9. Move the energy ball up to the Middle Dantian at the center of the chest, and continue circling in a clockwise direction nine times, spinning and wrapping the Heart, Shanzhong CV-17 and Shendao GV-11 points.
10. Move the energy ball up to the throat and continue circling in a clockwise direction nine times, spinning and wrapping the Tiantu CV-22 and Dazhui GV-14 points.
11. Move the energy ball up to the Upper Dantian at the Third Eye area, and continue circling in a clockwise direction nine times, spinning and wrapping the Yintang and Naohu GV-17 points.
12. Move the energy ball up to the top of the head and continue circling in a clockwise direction nine times, spinning and wrapping the Baihui GV-20 point.
13. Move the energy ball several feet above the head and continue circling in a clockwise direction nine times, spinning and wrapping the body's Heavenly Transpersonal point. This energetic point (above the head) is responsible for establishing the body's extended connection to the Heavens and for absorbing the divine energy into the body's internal organs, channels, and collaterals.
14. Next, imagine the energy ball slowing down and stopping its rotation, pulsing for several heartbeats, then reversing its energetic rotation, and beginning to spin in a counterclockwise direction nine times. The direction and flow of the energetic ball now reverses its orbit, descending and circling the same areas and points nine times, until it returns back down to the navel. The body should now be encircled, above and below, with several haloes of white light energy.
15. Finally, imagine the white light energy ball absorbing back into the body through the navel. As the energy ball descends back into the Lower Dantian, imagine energetic steam filling the entire body.
16. Once the body is completely full, the steam begins to exit the body through the pores and begins connecting and filling the space outside the body with white light energy, forming an energetic cocoon. This cocoon creates an energetic force field which protects the Qigong doctor from pathogenic invasion.

CLINICAL ETHICS

The study of clinical ethics refers to the morality of the Qigong doctor and the ability to set boundaries. The study of morals in the therapeutic relationship involves reflecting upon the ideals the doctor assumes as a professional care giver and the enforcement of these professional standards in his or her actual behavior. Both the morality and the self reflection are engaged, both consciously and unconsciously, to align the doctor's values with his or her actions.

Ethical behavior stems from the doctor's internal values and actions (emotionally, cognitively, and spiritually) and his or her sense of external connection (physically, existentially, and socially). The Qigong doctor's behavior should be always congruent with high ethical standards and in harmony with his or her values, intuition, knowledge, and feelings.

The importance of establishing ethical standards for the doctor-patient relationship is to avoid those behaviors which prove to be counter therapeutic, and encourage those that are most effective therapeutically for the patient. The patient, as well as the doctor, rely upon each others' trust and boundaries. It is the Qigong doctor's responsibility to create a context for the patient, in which the patient can make a change in his or her life in safety.

When patients are treated energetically, they relax into an altered state of consciousness. This causes the patient's boundaries to become relaxed or nonexistent. Because Medical Qigong therapy often reveals intimate knowledge of the patient's life and life-style, there is a danger of enmeshment, i.e., of co-dependent relationships forming (see Chapter 19).

When working with patients, doctors sometimes encounter intense physical, mental, emotional, and spiritual reactions from the patients. These experiences tend to disperse the patients' boundaries and can confuse the roles between the doctor and patients, intensifying transference and triggering countertransference.

When both the doctor and patient have a personal relationship with a divine higher power, it naturally brings them into a state of divine healing and spiritual wisdom. The acknowledgment and honor of this divine relationship should establish ethical boundaries. This is especially true as the doctor begins to see the bigger picture of how his or her intentions and actions (in relationship with patients) affect others in a rippling outward motion. It is important that doctors also see the effect on themselves when they take certain actions towards others, including their patients.

CONSCIOUS AND SUBCONSCIOUS CLINICAL INTERACTIONS

Clinical experiences are divided into two states of interactions: the body / mind and emotional / spiritual.

- The body / mind interaction deals with ordinary states of consciousness, such as: talking, thinking, analyzing, working, interacting with the material world and other human beings. These different qualities of interactions help the doctor to define and categorize, educate, and establish his or her solid belief structures.
- The emotion / spirit interaction deals with subconscious states of communication, such as: perceiving, sensing, intuiting, interacting with the spiritual / metaphysical world, as well as with energetic fields. Every day people go into states of light trance (daydreaming, spacing-out, etc.) allowing their focus of attention, thoughts, feelings, sensations, and intuitions to interconnect with their environment and that of the divine. This allows access to information and facilitates the healing and understanding of themselves and their life experiences.

Because most wounding involves an emotional / spiritual trauma at the time of the incident, the patients must relive this trauma during their healing process. Through the emotional / spiritual interaction between the Qigong doctor and his or her patients, ingrained habits of thought, feelings, and perceptual understandings begin to recede, diffuse and break down. This causes the patients to find a new understanding of certain traumas and allows them to reclaim disconnected parts of their past (soul retrieval).

Each time patients transcend to a new level of understanding of their fears and belief structures, they change, mature, and expand to adjust to the new mental, emotional, and spiritual growth. The moment that patients break out of their old boundary structure, feelings of emotion rush through their body / mind, followed by a sense of either expansiveness or disorientation as they find themselves in unfamiliar territory.

It is not useful for patients to relive their emotional traumas without the awareness, understanding, and insight of the process they are undergoing. To relive the trauma without this awareness leads to re-traumatization. That is why the Qigong doctor coaxes the patients through the "five stages of emotional healing" (see Chapter 19). The patients can then experience their past emotions in the present time, and become free of them through present awareness, rather then repeating the past through a continuous loop of repression and denial. In the clinic, this is known as "emotional time traveling" and refers to the practice of allowing the patients the experience of reliving past traumas through their presently increased state of awareness and knowledge. At this point of transition, the patients will not only experience the emotions and sensations from their past, but may also experience the motivations and emotions of the perpetrators as well.

The empathic knowledge of the perpetrator's emotions is due to the victim's identification process with the abuser. This phenomenon is well recognized in helpless hostage situations, and is a major contributor to childhood victims of physical, sexual or emotional abuse "acting out" their repressed fears, angers, and pain, in similar ways to the manner in which they were abused.

ESTABLISHING DOCTOR AND PATIENT AGREEMENTS

For the protection and integrity of both the doctor as well as the patients, it is important that a description of the clinical procedures that are to be used, their physical and energetic boundaries, as well as their limitations, be firmly established. The following seven principles are used to establish the foundation of clinical ethics.

1. The Qigong doctor will cause no harm (physical, mental, emotional, or spiritual). The Qigong doctor will maintain a high standard of skill, knowledge, and professional conduct, offering his or her services without favoritism, prejudice, or discrimination with regards to race, religion, nationality, gender, or sexual orientation.

   The Qigong doctor is committed to the patients' education and personal development of practicing Medical Qigong methods that relieve pain, suffering, and other symptoms of illness. The doctor will exercise his or her best judgement to determine if the therapeutic techniques prescribed for patients are contraindicated, dangerous, or not in the best interest of the patients.

   The doctor will never make negative suggestions, criticize, or tell the patients that they will get worse or are in bad shape, as that destroys the patients' hopes and is counterproductive to healing (this is known as "clinical hexing"). Clinical hexing will cause patients, who trust the doctor, to sabotage their own healing potential by succumbing to the doctor's particular beliefs about their conditions.

   One example of trusting a doctor's diagnosis to ruin, happened last year in 1999, when two patients' lab tests were accidently switched. The healthy patient, whose lab test had been switched, was informed by the Western doctor that she had terminal cancer; and the patient with terminal cancer, on the other hand, was given a clean bill of health. The healthy patient died several months later as a result of believing the doctor's diagnosis of having a terminal condition; whereas the patient with terminal cancer (believing that there was nothing wrong) resumed a normal, active life-style, and the patient's cancer went into remission.

2. The Qigong doctor will keep all sessions in confidence. The Qigong doctor will keep all patient information strictly confidential, in keeping with ethical and legal standards held by other health care professionals. This allows patients to experience the treatment in safety and give honest feedback.

   Exceptions to the rule of confidentiality are as follows: when the patient is a danger to self (intending suicide), or others (intending homicide), when the patient has a life threatening emergency, in cases of suspected child abuse (sexual, physical, or neglect), and elderly abuse (sexual, physical, neglect or fiduciary).

3. The Qigong doctor will first receive informed consent from the patient before starting the treatment, or informed consent of the patient's legal guardian. Before treatment, the Qigong doctor explains to the patient the therapeutic goal of the treatment, and what the patient may energetically and emotionally expect to experience. The doctor will respect the patient's boundaries at all times, before, during, and after each treatment. At times the doctor may have to impose boundaries for patients who cannot do so for themselves, in order to avoid total enmeshment, which would endanger the professional relationship.
4. The Qigong doctor and the patient will tell the truth to each other. No part of the Medical Qigong diagnosis should ever be hidden from the patient, yet the truth should always be delivered with hope, since no one can be certain of the future.

   The Qigong doctor should never make unrealistic, inaccurate, or false claims about Medical Qigong therapy, or give the patient false hope. A realistic assessment of the patient's condition should always be conveyed, and if need be, the patient should be referred for additional medical or psychological modalities of treatment.
5. The Qigong doctor will honor all agreements established with the patient. It is important for the patient to be able to rely on the doctor's trust. Because this is a critical factor, the doctor is never allowed to borrow money, cars, etc. from patients.
6. The Qigong doctor and the patient will not act sexually or romantically with each other. The Qigong doctor will not instigate or tolerate sexual advances while interacting with his or her patients. Although there are times that the patient, or doctor, may experience certain attractions towards each other, acting out on these feeling will cause an emotional / sexual entanglement which will be detrimental to the patient's healing.
7. The Qigong doctor and the patient will agree on the time, place, duration of treatment, and fee. The Qigong doctor must be consistent in maintaining an established clinical treatment time and location. This instills a stable security for the patient and doctor. If this boundary is not maintained, patients without strong boundaries will take advantage and hurt both doctor and themselves. The Qigong doctor is responsible for giving adequate advance notice (two weeks) to the patient of any and all treatment or fee changes. If, for example, the original agreement was for six or fewer sessions and the doctor changes fees after the first session, the original agreement must be upheld (new patients however, will be charged the new fee).

POWER DYNAMICS AND ETHICAL BEHAVIOR

In any clinical setting there is an active power dynamic at work. Generally it is the doctor who maintains the power over the patient, as the purpose of the patient's visit is for help or assistance in specific healing. As the patient has come to the doctor with expectations, it is important for the doctor to be congruent with these expectations. These expectations set both the standard of the patient's healing and the power dynamics of the relationship. Through the power dynamics of the doctor-patient relationship there can develop three classical problems: Transference, Counter-transference, and Emotional-Sexual Entanglement.

1. Transference is the process whereby a patient unconsciously transfers feelings, thoughts, beliefs, and patterns of behavior that had been previously experienced towards others onto the doctor.
2. Counter-transference is the process whereby a doctor loses his or her objectivity and unconsciously transfers feelings, thoughts, beliefs, and patterns of behavior to the patient.
3. Emotional-Sexual Entanglement is the process whereby the doctor and patient both lose their objectivity and transfer emotional-sexual feelings, thoughts, beliefs, and patterns of behavior onto each other.

In order to prevent these types of enmeshment and co-dependent relationships from happening, it is important for the doctor to constantly maintain his or her boundaries. The doctor and patient both must remember that it is the patient who actually does the healing in energy work, the doctor merely creates the situation in which this energetic transformation can transpire.

PITFALLS

There are certain pitfalls the Qigong doctor should be aware of and may experience, if a boundary has already been, or is beginning to be violated. These experiences are described as follows.

- The doctor begins to identify with the patient's problem and feels the need to discuss his or her own similar problems with the patient.
- The doctor begins to become emotionally attached or attracted to a patient sexually and feels the need to act on it (i.e., asks for a date, inappropriate touching or sexual contact).
- The doctor begins to feel the need to go out of the way above and beyond the normal course of responsible treatment to meet a patient's needs.
- The doctor begins to treat the patient for free.
- The doctor begins to find him or herself becoming overprotective, or worrying about a patient at inappropriate times.
- The doctor begins to need validation from his or her patient (this approval can be either as a healer, emotionally, or sexually).
- Arranging an exchange of services with a patient can often lead to the patient feeling abused or hurt.
- Allowing the patient to build up a large bill to be paid back later is unethical and may lead to legal action.
- Disclosing too much personal information regarding self (the doctor) in order to help the client can make the patient feel responsible for the doctor's well-being. Self-disclosure can be used very sparingly when the patient can benefit from solutions that worked for the doctor. It is safer, however, to pretend that these situations came from someone else.
- The doctor does not listen carefully to what the patient is saying, thinking that he or she knows what the problem is in advance.

It is important for the doctor to remember that the patient's emotional / spiritual safety and health must always come first. To avoid sinking into one of these pitfalls, the Qigong doctor is encouraged to constantly monitor his or her own actions and motivations. This is a broad and important topic that is often neglected in professional training and education. Because it is well dealt with in Kylea Taylor's book entitled, *The Ethics of Caring*, I encourage the reader to refer to this work for indepth treatment of this subject.

CLINICAL BURNOUT AND MEDICAL QIGONG THERAPY

One classic problem all healers encounter is clinical burnout. The condition known as clinical burnout results from chronic job stress, and may sometimes occur to the Qigong doctor. This condition is characterized by extreme frustration, disappointment, physical and emotional exhaustion, and sometimes physical illness. The result of this condition is the doctor's loss of concern for the patients, or the loss of fulfillment with his or her performance as a healer. The Qigong doctor is susceptible to experiencing clinical burnout, especially if he or she feels that:

- There are too many or too few patients;
- Too little time is spent for recreation;
- There is too much stress in his or her life;
- Not enough attention is placed on self care and personal psychological growth; and
- Not enough attention is placed on a personal spiritual path and practice.

If the Qigong doctor's life revolves primarily around the clinic (which is usually the case), he or she will disproportionately come into contact with the patients' pain and emotional traumas, as well as be chronically bombarded with toxic energetic discharges released from the patients.

Sometimes patients, in order to heal their intense emotional traumas, require an enormous amount of spiritual, emotional, and mental support from the doctor. If the doctor does not carefully monitor his or her own energetic reservoir, this may result in Qi depletion.

If Qigong doctors expend all their spiritual/emotional energy from intense personal interaction and enmeshment with their patients during treatment, the toxic interaction will deplete the doctors, resulting in complete physical and mental exhaustion. If Qigong doctors become depleted in the middle of a treatment, they may abandon their Upper Dantian (psychic) connection with patients (spiritually, emotionally, and/or energetically), and begin to suddenly express feelings of criticism, anger, disappointment, or grief. This reaction occurs when the Qigong doctors' own internal organ energy, depleted and worn, becomes susceptible to absorbing the patients' powerful emotional discharges. The problem of clinical burnout usually stems from energetic boundary invasion. Remember, Medical Qigong healing requires that the doctor heal him or herself first.

Often, a Qigong doctor's clinical burnout is primarily related to the unresolved personal issues and not the number of patients on the case load, or the amount of environmental stress the doctor experiences.

ENERGETIC BOUNDARY INVASION

In understanding clinical burnout due to energetic boundary invasion and its relationship between the doctor and patient interaction, it is important to review seven important factors which control and transform the body's energetic fields.

1. Energy exists on different planes. The body is like a complex hologram, composed of physical, mental, emotional, and spiritual planes of energy. The spiritual field of energy controls the emotional and mental energetic field, which in turn controls the physical energetic field. These energetic planes affect and control the energetic formation of the body's cells, tissues, organs, and organ systems.
2. Because the body produces heat, light, electricity, magnetic energy, and resonate vibrations, these natural energetic releases create a basic Yin (negative) and Yang (positive) polarity, which is found in all manifestations of energy.
3. Everything in the body is in vibratory motion. Various forms of tissue develop from different energetic vibrations. When the body's energy begins to slow down, it begins to take on a denser form of resonant vibration. The impediment of this resonant energetic vibration can stem from trauma or shock to the system (physical or emotional), resulting in energetic stagnations and disease.
4. The body's internal organs collect and store emotional energy, both positive and negative. As any suppressed, or "stuffed," emotional energy begins to culminate, the body will naturally (and quite frequently) disperse these internal emotional charges. They are generally released externally through: the Respiration, the Posture, and the Mental Dialogue.
    - The respiration, (which includes sighing and laughing), is released from the Heart, shouting released from the Liver, groaning from the Kidneys, crying from the Lungs, and singing from the Spleen.
    - The posture includes the body's physical structure adapting or conforming to an Expanded-Yang or Contracted-Yin energetic influence.
    - The mental dialogue includes both benign and malignant thought patterns.
5. The body has three primary energy centers known as Dantians. Each Dantian resonates at its own distinct vibration and is responsible for specific modes of interacting with others in interpersonal communication.
    - The Lower Dantian is considered the most physical energetic base. It is the most dense and has the slowest vibratory rate of the Three Dantians and communicates kinetically with the outside environment.
    - The Middle Dantian is considered the emotional and mental base. It has moderate resonances and communicates empathetically with the outside environment.
    - The Upper Dantian is considered the spiritual base and has the fastest and most delicate of the vibrational interactions. The Upper Dantian functions at an intuitive level.

6. When communicating, the body will interact from all five levels: physical, mental, emotional, energetic, and spiritual. This interactive communication will sometimes energetically fuse with the external environment, including people.
7. Our external and internal thoughts and feelings, as well as tissues and cells are all byproducts of energetic interactions, stemming from communication from within ourselves and our environment.

After reviewing the following facts, the Qigong doctor can understand why every time he or she connects with a patient, the patient's energetic fields will automatically be energetically ingested by the doctor. The doctor does this consciously in order to analyze the patient's emotional past, as well as present emotional outbursts. Although the doctor and patient's energies fuse together, the fields of energy around the doctor's internal organs generally protect the doctor from absorbing negative emotions. These energetic boundaries also extend out into the doctor's Wei Qi field.

Both the patient's and doctor's Wei Qi fields are fused during interaction and treatment. It is therefore imperative that the doctor's energetic boundary system maintain its structure (both internally and externally), yet be permeable while treating the patient. The doctor must not lose sight of his or her purpose. Any criticism aimed at the doctor should not be taken seriously, nor should any inappropriate behavior by the patient. The doctor's Wei Qi field should be at maximum strength. If not, the cords of energetic attachment flowing from both the doctor and the patient allow energetic emotional transference to happen. If the doctor, for example, has a preexisting Liver Heat condition, it will be further compounded by the inflowing of the patient's released of anger and rage. If and once this happens, the patient may feel relieved, but the doctor will become quite agitated.

STRENGTHENING THE DOCTOR'S ENERGETIC BOUNDARIES

It is important for the Qigong doctors to allow the patients' emotions to constantly flow through their own bodies, feeling, understanding, then releasing these feelings. If at any one point in this transition, a doctor (because of personal issues) suddenly stops the flow of emotions and begins to focus, or dwell on, a particular type of energetic charge, the patients' discharging emotions will invade the doctor's body.

To avoid energetic boundary invasion the doctor should maintain a regular Qigong meditation and exercise program. This program should include the following exercises and meditations.

1. Practice Qi dredging and emotional dispersing exercises and meditations to release your own emotional traumas.
2. Perform Qi and organ strengthening exercises and meditations to strengthen both your internal organ energies, as well as the three fields of Wei Qi. Since the emotions are stored within the body's internal organs, strengthening these organs will facilitate a stronger control of the body's emotional energy.
3. Practice Qi regulation and balancing exercises and meditations to balance the body's Yin and Yang, as well as internal and external energetic channels, organs, and organ systems. This helps to control the energetic surges released from internal emotional discharges.
4. Maintain emphasis on the energetic grounding and the divine hook-up meditations before treating patients. These meditations are important for establishing an emotional as well as spiritual boundary, and will assist you in avoiding clinical burnout and energetic boundary invasion.
5. Maintain emphasis on personal time, including any and all spiritual, social, and recreational times away from the clinic.

CAUSES OF SPIRITUAL DRYNESS

Sometimes clinical burnout can result from "spiritual dryness." This type of burnout can result from experiencing a "dry period" of spiritual insight and perception. It can occur during clinical observations and treatments, resulting in frustration for the doctor. Spiritual dryness is commonly due to one or more of the following five conditions.

1. If the doctor is tired, hungry, or sick, the fo-

cus will tend to be on the doctor's own particular needs instead of the patient's.

2. A disconnection from the divine is caused by guilt, lack of forgiveness (self-blame), shame, etc., resulting in a loss of spiritual vision. It is important for the Qigong doctor to have an open and honest connection with the divine to receive the more subtle spiritual insights. Without this type of transpersonal relationship, the Qigong doctor's ability to dissolve into the Wuji surrounding the patient's tissues can be hindered.
3. Rushing personal meditation time is caused by failing to relax during the preparation meditation practice (the divine hook-up). This condition is normally caused by worries or preoccupations due to hidden agendas, that disturb the doctor's Shen prior to meditation. It is important for the doctor to relax and return to a state of quiescent peace, in order to truly listen to the divine.
4. Getting into a rut is caused by the doctor performing repetitive Shengong meditations in a mechanical way (i.e., the same way an individual will routinely brush his or her teeth), thus losing the emotional and spiritual connection with the core self. The meditation then becomes meaningless and powerless (just words and no spirit). To avoid getting into a rut, the doctor should try to experience each meditation as a time of new beginnings and enlightenment, and not as a mandatory routine.
5. It is important for the doctor to be able to share emotional and spiritual insights with other colleagues in the same field of work, and when appropriate, with the patient. This sharing of spiritual insights, observations, fears, and triumphs renews the doctor's confidence in his or her spiritual gifts, and maintains a strong faith in the healing potential of Medical Qigong therapy.

SECTION VII

THE TREATMENT PRINCIPLES OF MEDICAL QIGONG THERAPY

CHAPTER 29

PRINCIPLES AND PARAMETERS OF MEDICAL QIGONG THERAPY

The foundational factors of the patient's state of health originate from their actions, thoughts, and feelings. A Qigong doctor, studying a patient's physical problems, understands that the origin and solution to these problems are to be found within a patient's recurring thought patterns, both conscious and unconscious.

The brain processes data consistent with what it is familiar with; patients will generally experience and accept information that coincides with their own belief system. Their consciousness then, creates its own reality, resulting in either health or disease.

Good health is a result of bringing the patient's own unique spiritual and emotional essence back into consciousness and increasing the awareness of the physical body. Both health and disease are created through this process which is the foundational base for clinical Qigong treatments.

THE FIVE METHODS FOR TREATING PATIENTS

Qigong doctors generally use five methods for treating their patients' diseases (Figure 29.1). These methods initiate an energetic restructuring within the patient's body. The five methods are described as follows.

1. The doctor uses his or her own Qi to initiate the healing.
2. Qi is drawn, by the doctor, from the surrounding natural environment (from the energetic fields of the Earth) to be emitted to the patients.
3. Qi is drawn, by the doctor, from the surrounding universe (from the energetic fields of the Heavens) to be emitted to the patients.
4. Divine energy is channeled through the doctor to treat the patients.
5. Homework is prescribed in the form of self-regulation exercises and meditations to support the healing process.

THE NINE STAGES OF TREATMENT

Using these five methods of treatment, the Qigong doctor initiates nine stages of healing within the patient's body. The healing process will always vary according to the belief structure of the patients, their acceptance and performance of the Medical Qigong prescriptions, and their willingness to change. The Qigong doctor's nine specific stages in treating a patient are described as follows.



Figure 29.1. Five Methods Used For Treating Patients

The Subtle Wonders	Expensive or Contracted, Heavy or Weightlessness, Cold or Hot, and Tingling, or Vibrating Sensations
The Mysterious Wonders	Flashing Light Sensations, Sound Sensations, Smell Sensations, and Fainting (Syncope) Sensations
The Incredible Wonders	The patient will experience various colored lights, sounds, smells and other sensations according to the doctor's intention.

Figure 29.2. The Three Wonders

1. Activate, connect, and energize the patient's energetic field;
2. Dredge the patient's channels and collaterals;
3. Purge and eliminate any energetic Excess;
4. Tonify any energetic Deficiencies;
5. Regulate the Qi and Blood content of the patient's Yin and Yang organs (harmonize the organ Jing);
6. Regulate the patient's Prenatal and Postnatal Qi (harmonize the Qi of the Three Dantians and Taiji Pole);
7. Balance the patient's Yin and Yang Shen (harmonize the Heart/Mind and Emotions);
8. Seal the patient's external field of energy;
9. Give prescriptions.

THE THREE WONDERS OF MEDICAL QIGONG THERAPY

The cultivation of Qi and Shen through Medical Qigong therapy generates what is described as the Three Wonders. These Three Wonders consist of the three separate transformations of energetic abilities that the Medical Qigong doctor and, sometimes, the patients experience (Figure 29.2). The Three Wonders are explained as follows:

THE SUBTLE WONDERS

The Subtle Wonders consist of subtle changes inside and outside the body, known as the Eight Energetic Touches. These interactions of tissue and energy form the physical sensations and manifestations of Yuan Qi. When the doctor emits Qi to treat diseases, involuntary phenomena can occur instantly, or gradually, in local areas of the limbs, or the patient's whole body. In some cases the muscles stir slightly, while in other cases the limbs, or the body, will perform extreme, harsh movements. This results from the patient's external energy (Wei Qi) inducing spontaneous movements.

When the Qigong doctor emits energy to treat diseases, some patients produce, in local areas, electromagnetic, or stimulating, sensations of Qi similar to those felt in Qigong circulation/cultivation exercises and meditations. This includes: cold or hot sensations, feelings of compression or tugging, impressions of creeping or tingling, experiences of heaviness or lightness, and of floating or sinking, as well as other sensations. The Subtle Wonders result from energy in the channels circulating and responding to the doctor's intention.

Generally, the effects of Qi on the body are manifested in physical sensations and sensory phenomena during Qigong exercises. These phenomena are all manifestations of the free movement of Qi in the channels, collaterals, and inner body circulation.

The doctor may also experience these same sensations while extending energy into the patient. The doctor should be able to sense the patient's Qi circulation, density, direction, as well as his or her own energy. The sensations known as the Eight Energetic Touches of the Subtle Wonders are: Expansive, Contracted, Heavy, Light or Weightlessness, Cold, Hot, Tingling or Itching, and either Vibrating, Shaking, Rippling or Moving.

1. When the Qi is circulating freely within the body, the capillaries expand as the body's energetic field expands, resulting in the sensation of being very large, tall, and expanded.
2. When the Qi enters from the outside of the body to gather in the Lower Dantian, the patient experiences the sensation of feeling very small or contracted.
3. When the Qi sinks down (upon exhalation), the body feels heavy, condensed, and solid as a rock.
4. When the Qi rises upward (overflowing the channels), the body feels light and weightless.
5. When the Qi circulates through the Microcosmic Orbit (balancing the Qi of the Heart and Kidneys), the Kidney-Yang becomes sufficient to allow the Kidney Yin to well up; this results in a pleasant cool sensation.
6. When the Qi is vigorous and thermal energy is gathered, the parts of the body where the Qi passes will feel hot.
7. Once Qi circulates vigorously and passes through the body's obstructed channels, collaterals and minute collaterals, the result is itching or tingling of the skin and scalp. This is an energetic manifestation of the body's obstructed channels, collaterals, and minute collaterals being cleansed.
8. When the Qi passes through the channels, collaterals, and parts of the body it has opened, the patient feels electrical and creeping sensations in the extremities as well as the body, causing the tissues to vibrate, shake, ripple, or move, etc.

These are all normal phenomena of Qi cultivation and circulation. As long as the patient remains calm and present, these sensations will appear and disappear as spontaneously as they were formed.

THE MYSTERIOUS WONDERS

Patients may also experience elusive as well as dynamic transitions inside and outside of the body, called the Mysterious Wonders. These energetic changes are sometimes present, but are rare, and may be confusing to the patient. The sensations known as the Mysterious Wonders are: Flashing Light Sensations, Sound Sensations, Smell Sensations, and Fainting (Syncope).

1. Flashing Light Sensations sometimes occur in some patients during Qigong treatment. The photoelectric phenomena is due to the interaction of light with matter. In some cases, patients feel electric sensations in the limbs and body, and in other cases light patterns may be seen in different forms, most of which present as round, sheet light, or lightning patterns.

   One of the manifestations of the Qigong doctor's cultivation through Shen Gong meditations is a flashing light sensation which is seen and felt within the doctor's head and body. This glow may sway back and forth, pulse like a white neon light, or pierce into the doctor's brain, and illuminate the spinal column. It may also appear as a ball of white light rotating at high speed through the Microcosmic Orbit.

   This ball or beam of light may exist continuously at the Qigong doctor's Baihui GV-20 point throughout the duration of the meditation and several hours afterwards. The degrees of light sensations and their colors will vary in accordance with the doctor's skill level. Also, it is this beam of light that the Qigong doctor will later utilize for inner vision diagnosis.
2. Sound Sensations are sometimes experienced during treatment, such as a rustling, rumbling, or high-pitched sound.
3. Specific Smell Sensations may occur, such as the sweet scent of sandalwood, or fragrances of various flowers, or incenses.
4. Fainting (Syncope) can occur during Qigong treatment. A few patients may suffer from perspiration and accelerated heart rate, fol-

lowed by syncope (fainting). When this occurs, the doctor lightly presses the patient's channel points: Baihui (GV-20), Mingmen (GV-4), Jiangjing (GB-21), and Yintang (Extra Point). The doctor then grasps the shoulders and presses down on the GB-21 points with force. Finally, the doctor emits Qi along the Governing and Conceptual Vessels and leads the patient's Qi to the Lower Dantian. This allows the patient to recover consciousness.

THE INCREDIBLE WONDERS

The Qigong doctor's ability to have complete conscious and automatic control over the patient's reaction to energetic projections constitutes what is known as the Incredible Wonders. When the Qigong doctor takes control over the patient's energetic projections, he or she can willfully initiate the patient to experience various colored lights, sounds, smells and other sensations according to the Qigong doctor's will. This procedure is commonly known as Cultivating the Spirit to Generate Wonders.

When the Qigong doctor emits energy towards patients to treat their diseases, most patients will either instantly or gradually feel some form of energetic sensation from the increased life-force energy. The degree of energetic sensation felt by patients is in accordance with their emotional/spiritual sensitivity and degree of connection to their own physical body.

The sensations of Yuan Qi are the most common reactions felt by both the Qigong doctors and their patients. In rare instances some patients display no physical effects and experience no Qi sensations during treatment. These patients can still achieve good therapeutic results by improving the degree of their emotional/spiritual connection to their body.

In some cases, patients may even feel miserable or uncomfortable. When this occurs, they should continue training so that their Righteous Qi can overcome their Evil Qi. This ongoing battle will also affect their spiritual and emotional being. Fear usually arises at this point causing them to question their ability to continue in their practice. This is a normal transition and can be resolved through encouragement, patience and continual practice.

CONTRAINDICATIONS FOR MEDICAL QIGONG THERAPY

There are several contraindications that the Qigong doctor should be aware of before treating patients, or even prescribing Medical Qigong exercises. The following is a list of different personality types that may be encountered in the clinical settings that require special treatment modifications.

1. The very "nervous" type of patient should not practice Medical Qigong, or must be under strict supervision due to the patient's emotional instability.
2. The "extreme temperament" type of patient who has a fanatical type of personality should also avoid Medical Qigong training or remain under strict supervision. Patients of extreme temperament generally suffer from Excess disorders and compulsive overtraining. They are therefore prone to Qi deviations.
3. The "extremely introverted" type should be careful when practicing Medical Qigong meditations because strong emotions may be set into motion, and even certain mental disorders may be violently released that the patient may have been unaware of.
4. The "narrow minded" type will generally condense Qi into smaller areas of the body causing stagnations. Such patients should be instructed to relax and let go of their stress to allow the condensed energy to disperse.
5. Patients with the following conditions should be restricted to very specific Medical Qigong therapy: serious mental disorders, congestive Heart failure and severe organ failure, severe hemorrhaging, menstruation, nerve suppression, bone fracture, pregnancy, geriatric patients, young children, and cancer patients (Figure 29.3).

- Patients with mental disorders such as schizophrenia and bipolar (previously called manic depression) disorders (or individuals with a family history of such mental diseases), should refrain from training. The Qigong exercises and meditations could induce symptoms of these said disorders, or could enhance


Medical Qigong Prescriptions must be Modified
Mental Disorders
Congestive Heart Failure and Severe Organ Failure
Severe Hemorrhaging
Menstruation
Nerve Suppression
Bone Fracture
Pregnancy
Geriatric Patients
Young Children
Cancer Patients

Figure 29.3. Restricted Conditions for Prescribing Medical Qigong Exercises and Meditations

the symptoms due to the patient's mental and emotional instability.

- Patients with congestive Heart failure and severe organ failure (any internal organ that has experienced an energetic collapse), require that the treatment be specifically oriented towards this condition.
- Patients with severe hemorrhaging require prescriptions that prevent the leakage of Blood and Qi, since Blood and Qi flow together.
- Women during their menstruation cycle should not store Qi in their Lower Dantian. Any Blood and Qi stored in the uterus will purge from the woman's body naturally, drawing with it any Qi stored within the Lower Dantian.
- Patients suffering from nerve suppression (cervical spondylosis) may experience a worsening of their condition. In severe cases, the additional pressure on the nerve roots may complicate the patient's condition, especially when the body's energy field expands causing the Marrow within the spinal column to ascend.
- Patients with bone fractures must first have the bones set correctly and immobilized to prevent further injury. The subtle involuntary movements of the limbs during Qigong treatment or practice can disturb the bone's healing process.
- Pregnant women must be treated by a Medical Qigong doctor who specializes in obstetrics, otherwise the risk of involuntary abortion (miscarriage) or other complications can arise.
- The treatment of geriatric patients prohibits Dynamic Qigong because of the delicate nature of their internal tissues. All exercises and meditations should be kept slow, quiescent, and tranquil.
- The treatment of young children requires that all exercises and meditations be age appropriate, and be specifically oriented toward healing his or her disease. Some Qigong exercises, meditations and treatment methods may interfere with the natural development of the child's internal organs and tissues.
- The treatment of cancer patients requires modified prescriptions in accordance to the specific disease. With certain cancers, Dynamic Qigong is contraindicated to prevent the cancer from further metastasizing.

CHAPTER 30
BALANCING THE BODY'S ENERGETIC SYSTEM

PURGING, TONIFYING, AND REGULATING

In Medical Qigong therapy, successful results can be achieved only when the doctor adheres to the principle of "treating Deficient syndromes with tonification and Excess syndromes with purgation." Tonification supplements the insufficiency and strengthens the body's resistance, while purgation reduces the Excess and expels pathogenic factors. The final aim is to balance Yin and Yang to regulate the physiological functions of the body.

Medical Qigong Therapy adheres to the traditional Chinese medical explanations of illnesses and general principles of healing. Only the techniques used during treatment differ. Qigong doctors Purge the patient's body, then emit Hot or Cold Qi in conjunction with the Five Elemental energies, using various hand manipulations, including: pushing, pulling, rotating, leading, and shaking.

Through energy extension, the doctor can reinforce the patients body's resistance to pathogenic factors, replenish the Yin and Yang organ energy and enhance mental clarity.

THE THREE TREATMENT MODALITIES

Medical Qigong therapy is divided into three treatment modalities (Figure 30.1). These treatment modalities enable the Qigong doctor to purge, tonify, and regulate the patients' body. These techniques are described as follows.

1. Medical Qigong Purging techniques are used by the doctor to treat the patient's Excess syndromes, and to detoxify the body of pathogenic Qi. The "lower aspect" of classical Chinese medicine governs the treatment of the patient's illness and corresponds to Earth. It involves purging pathogenic influences and dispersing stagnations in order to cure the patient's illnesses. This allows the patient the ability to remove Excess Qi from organs and tissues.
2. Medical Qigong Tonification techniques are used by the doctor to treat the patient's Deficient syndromes, as well as strengthen and stabilize the organs and organ systems. The "middle aspect" of classical Chinese medicine governs the nourishment of the patient's nature and corresponds to Man. It involves helping the patient prevent illness by tonifying



In cases of Excess, the doctor should Purge.

In cases of Deficiency, the doctor should Tonify.

In cases of Excess and Deficieny combined, the doctor should Regulate.

Figure 30.1. Purgation, Tonification, and Regulation

Heaven — Regulation — Balance Qi and Blood — Nourish the Patient's Destiny

Man — Tonification — Treat Deficient Conditions — Strengthen the Body to Prevent Illness

Earth — Purgation — Treat Excess Conditions — Detoxify the Body to Treat Illness

Figure 30.2. Ancient Chinese Perspective on Purgation, Tonification, and Regulation

organ energy Deficiencies. This allows the patient the ability to replenish organ energy depletions and tissue emaciation.

3. Medical Qigong Regulation techniques are used by the doctor to balance the patient's Yin and Yang energy, as well as organ Qi. The "highest aspect" of classical Chinese medicine governs the nourishment of the patient's destiny and corresponds to Heaven. It involves regulating the patient's Three Dantians, Taiji Pole, Yin and Yang organs and energy fields. Regulation techniques promote a balance of Jing, Qi and Shen for the optimal development of all the aspects of man, i.e., body, mind, emotion, spirit and energy. Thus, in China, Medical Qigong regulation is said to "nourish the patient's destiny" (Figure 30.2).

PURGATION TECHNIQUES

The patient's body can be dredged and purged by using two different expelling methods. The first method is the direct removal of pathogens from the patient's tissues and organs. The second method is the indirect purging of the patient's tissues and organs through the channels and points of the patient's body. These two methods serve two different purposes: The Direct Removal of Pathogenic Factors, and The Purgation of Channels and Points.

1. The Direct Removal of Pathogenic Factors is achieved through extending Qi into the tissues and organs where they are lodged, and dredging the Toxic Qi directly out of these locations. This method is used to expel pain due to Excess Heat or Cold. The various techniques used in this type of purging employs stationary Qi-guiding manipulations. The various hand manipulations used for the direct removal of pathogenic factors consists of such techniques as: The Five Thunder Fingers Hand Posture, Shaking and Trembling Hand Posture, Bellows Palm, Vibrating Palm, Dragon's Mouth Palm, Tiger Kneading Palm, and Spiraling Palm (see Chapter 33).
2. The Purgation of Channels and Points techniques are used to expel External pathogenic Evils (such as the invasion of Wind, Fire, Heat, Dry, Damp, Cold, and environmental toxins, etc.), or Internal pathogenic Evils (such as fear, anger, and grief, etc.) from the organs and tissues of the body. It is also used to redirect Rebellious Qi (e.g., Stomach Qi). The various techniques used in this type of purging employs dynamic-linear Qi-guiding manipulations such as the Pulling, Leading, and Guiding methods (see Chapter 34).

TONIFICATION AND PURGATION METHODS

The doctor should always purge before tonifying the patient's body. In the clinical setting, these two methods are often used together in combination with other methods in treatment. These combined methods are as follows.

TONIFICATION AND PURGATION WITH RESPIRATION

Tonification occurs as the doctor exhales while guiding and directing Qi into the channels, points, and the internal organs and tissues of the patient's body. Purgation happens when the doctor inhales while guiding, emitting, and leading the patient's Qi, or pulling the pathogenic Evils out of the patient's body.

During treatment, it is important that the patient cooperate with the doctor by matching (if possible), per the doctor's instruction, his or her breathing rhythm to the doctor's treatment. The patient should assume a proper posture (lying, sitting or standing), relax, and concentrate his or her mind on the location being worked on. When the doctor exhales and emits Qi toward the patient, the patient should inhale to absorb the doctor's Qi into the designated location. When the doctor performs purgation, the patient should exhale to release Toxic Qi out of his or her body.

TONIFICATION AND PURGATION ALONG AND AGAINST THE CHANNEL FLOW

With regard to acupuncture therapy, the classics say that, "puncturing along the direction of the channels yields a tonifying effect, while going against it induces purgation." In Medical Qigong, however, due to the Qigong doctor's nature of emitting, leading and guiding the energetic flow of Qi, certain modifications are used. The following are a few examples of tonification and purgation techniques used along and against the energetic flow of the channels:

- Causing Qi to flow up the Yin channels of the legs and into their associated organs in the torso is considered tonification (think of following the river to the sea). One example of this type of treatment therapy is emitting energy into the base of the patient's feet (at the Kd-1 points); this causes the energy to flow into the torso to strengthen the Kidneys.
- Moving Qi from the torso down the legs against the flow of the leg Yin channels is considered purgation (following the river from the sea). One example of this treatment therapy would be pulling Excess Qi from the Liver organ, down the right Liver channel and out the feet to sedate the Liver Fire (the Gall Bladder Channels can be used to purge Excess energy from the Liver organ down the leg Yang channels).
- Moving Qi against the flow of the arm Yin channels into their associated organs is considered tonification (think of following the river to the sea). One example of this treatment would be emitting energy from the base of the thumbs, at the Lu-11 points, into the torso to strengthen the Lungs.
- Moving Qi against the flow of the arm Yang channels into their associated organs is considered purgation (following the river from the sea). One example of this treatment would be pulling Qi against the flow of the Large Intestine Channels down and out the hands to purge Excess Qi in the head.

TONIFICATION AND PURGATION POINT THERAPY WITH THE HORARY CYCLE

When prescribing Jing Point therapy as a means of self-regulated homework, the Qigong doctor encourages the patients to follow the formula of tonification and purgation according to the energetic flow of the Horary cycle. According to ancient Chinese medical theory, the ebb and flow of Qi and Blood along the different channels is related to designated days and hours (see Chapter 11). This theory applies to two specific tissue manipulations: Holding the Point for Tonification, and Closing the Point for Purgation.

- Holding the point for tonification requires the patient to use the Massage Tapping method (see Chapter 37) on specific points two hours prior to its opening or peak flourishing time (high-tide).
- Closing the point for purgation of the internal organs or channels requires that the Qigong doctor drain the diseased area at high-tide (when it is most full of Qi and Blood). When the patient is applying Jing Point therapy for homework prescriptions, however, the application is quite different. This technique requires the patient to use the Massage Tapping method on specific points two hours after its opening time.

The patients may also be instructed in self-massage using the Tapping method for self-healing. If the patient has a Kidney disease, for example, the specific points should not be tapped during its peak time (5–7 p.m.), but rather two hours prior to its peak time (3–5 p.m.). This will improve the Kidneys' function.

TONIFICATION AND PURGATION GUIDELINES

When the Qigong doctor purges and tonifies a patient, he or she must remember to adhere to the following guidelines carefully.

GUIDELINES FOR THE DOCTOR

When treating the patient, the doctor must always consciously direct and be aware of the movements of each hand.

- Generally, the right hand is used for tonification, while the left hand is for purgation. Diseases that require purgation are treated by draining Toxic Qi with the left hand. Diseases that require tonification are treated by extending Qi through the right hand.
- Turning hands towards the body is used for tonification, while turning the hands away from the body is used for purgation.
- Moving the hands away from the body and upward can regulate the Yang energy, causing it to rise, and is inclined to tonify. Moving the hands downward pulls the Yang energy down, and is inclined to purge.
- Clockwise drilling (the palm or extended fingers move in a clockwise direction over an area) is used for tonification and increasing Qi; counterclockwise drilling is used for purgation and decreasing Qi.

GUIDELINES FOR THE PATIENT

The patient, (like the Qigong doctor), must be aware of hand movements when practicing Qigong prescriptions. In addition, the patient must be aware of his or her posture, respiration, and mental attitude.

- The eyes are open for purgation; closed eyes are used for tonification. The patient should apply these principles according to the symptoms of the disease.
- Inhalation is used for tonification, exhalation is used for purgation. During purgation treatments, the patients assume the proper postures, relax, and concentrate their mind on the disease area while exhaling the pathogenic Qi. This exhalation technique is used not only to promote the removal of the surfacing toxins, but is also used to enhance the doctor's efficacy in purging the diseased area.
- The audible and silent tone resonations (see Chapter 40) also have the function of either tonification and purgation. Speaking the silent tone when inhaling can be used for tonification; while exhaling, the tone is used for purgation.

UNDERSTANDING MEDICAL QIGONG REGULATION

The Qigong doctor must master three main techniques of Qi regulation to facilitate clinical healing through Qi emission. These techniques include: Training the Qi, Guiding and Inducing, Tonifying and Purging the Qi, and Emitting the Qi.

1. Training the Qi exercises and meditations are used to gather Qi and to promote its circulation within the body. The Qigong doctor must have an extensive comprehension of several Medical Qigong techniques used to gather and circulate energy throughout the body. This includes a complete understanding of Postural, Respiratory, and Mental Dao Yin modalities, as well as the static and dynamic clinical modalities. These training techniques provide the Qigong doctor with the ability to regulate and balance the patients' Qi, and set the foundation for the patients' Medical Qigong prescriptions.
2. Guiding and Inducing, Tonifying and Purging the Qi are used to circulate Qi within the external field of energy (Wei Qi). These techniques require a complete understanding of guiding and inducing (leading the Qi), and tonifying and purgation techniques, to being able to rectify Qi deviations and remove energy blocks.

These training techniques provide the Qigong doctor with the foundation for the patients' Medical Qigong therapy.

3. Emitting Qi techniques must be learned and perfected by the doctor. The Qigong doctor must have an extensive understanding of the multiple techniques used to extend Qi into the patient's body. These include electromagnetic energy, light, sound, and hot and cold Qi projections. These training techniques and abilities also set the foundation for the patients' Medical Qigong therapy (see Chapter 34).

QI REGULATION AND GUIDING PRINCIPLES

Qi regulation is considered a combination technique for reinforcing and reducing. It is used to readjust and balance the Yin and Yang energy. If the patient's Qi rises adversely, the doctor should guide and secure it downward. The same principle is applicable for any Deficiency or Excess of Qi in the left or right sides of the patient's body.

Qi regulation also includes purgation after tonification, and tonification after purgation. This method of guidance is used when Qi stagnation, stasis of Blood, or disorders of the channel Qi develop. Under pathogenic conditions, Qi of the viscera and channels may become weak and stagnant. This is manifested by symptoms such as listlessness, general weakness, and the hypofunction of certain organs or tissues. Stagnation of Qi and stasis of Blood can also obstruct the channels causing pain. Pain may also be caused by outside pathogenic factors such as trauma, inflammation, muscular spasms, and adhesive degeneration. In these circumstances, the channels are dredged to promote Blood circulation, and to remove the stasis in order to relieve spasms, and dispel pain.

Every organ in the body has its own Qi that circulates and interacts with the rest of the body. When the normal function of the organ is affected, the circulation of Qi may become disturbed. This disturbance of Qi in one organ may influence the functional balance of the whole Qi system.

The doctor regulates the patient's channel Qi by dredging the channels and collaterals. This facilitates Qi circulation and leads Qi back to its origin. In the case of a weak and hypofunctional Lung Qi, for example, emitting Metal-Qi plus Pushing, Shaking and Leading manipulations (see Chapter 34) can be adopted to activate the Lungs' Qi. The combination of these techniques causes the channels' Qi to overflow freely, thus improving the function of the Lungs.

ENERGY BALANCING PROCEDURES

When extending energy into the patient the main emphasis is placed on balancing the patient's energetic fields. The doctor must have both physical and emotional releases from the patient's body, to detoxify and liberate the trapped Qi.

It is important to not let the patients avoid facing their problems; keep them centered around the troubled area, focused on the awareness of what they are feeling. Basic energy balancing procedures are as follows.

1. If the treatment area is Hot, cool it down. The doctor must continue treating the patient until the Hot area has cooled. A strong and quick moving hand gesture is best used to treat a Heat syndrome.
2. If the treatment area is Cold, heat it up. For a Cold syndrome, use a longer treatment to warm up the channel in the area treated, to eliminate the Cold.
3. If the tissue's energy is dark or cloudy, change it to light and clear.
4. If you feel tingling on any area or organ, remain there until the tingling subsides and the organ or area completes its energetic unwinding. Tingling in an area indicates that the patient's body is releasing an energetic cluster. The patient may or may not be aware of any feelings or sensations when this occurs.
5. If the area is emitting electric shocks, dampen or sedate it by connecting it with its associated organ. Connecting Yang (positive) into Yin (negative) will ground the energy.
6. If you sense pressure or Excess, dredge the area, and circulate the Qi.
7. If you feel intense pulsation, decrease the intensity and make it rhythmical.
8. When treating an energetic field that is De-



Figure 30.3. Locations of Energetic Blockages

pressed (sinking or contracting inward), use an "ascending method" of Qi manipulation for tonification (i.e., move and emit Qi from the lower areas of the body upwards). Some examples of this type of ailment are:

- Lower Burner Depression
- Middle Burner Depression
- Immune System Depression and Breakdown
- Autoimmune Diseases (Lupus and Fibromyalgia)
- Chronic Fatigue Syndrome
- Heart Failure
- Kidney Failure
- Prolapse of the Stomach

9. Assign Medical Qigong prescriptions for patients, including meditations and exercises, as needed.
10. Treat patients with severe diseases by:
    - Stopping and controlling the spread and development of the disease,
    - Stopping the patient's Excess consumption of Qi,
    - Treating the cause and root of the disease, after the patient's condition is under control, and
    - Assigning homework.
11. For chronic diseases, use the method of purging and dredging stagnation to move any impacted Qi.
12. For sprains, use Qi compression (using the Qi to press the tissues) around the local area. Close the channels surrounding the sprain first, isolating the trauma. Then pull out the stagnant Qi. If the doctor immediately treats the local area, he or she will disturb and further complicate the injury. It is important to close off the surrounding channels around the wound first, leaving only the affected channel open, before pulling out the stagnant Qi. This controls the flow of energy in to the stagnated area.

Check the patient after seven treatments to determine if the therapy has been effective. Reevaluate each patient according to each individual's constitution.

CLINICAL OBSERVATIONS OF PATHOLOGICAL ENERGETIC PATTERNS

When the Qigong doctor begins to treat patients, certain energetic observations and phenomenon will be experienced while diagnosing the energy inside the patient's tissues. These energetic experiences are quite different from the Eight Energetic Touches which focus on the feelings of the body after meditation practice (see Chapter 29). The Internal conditions of the patients' disease, its energetic nature, as well as its clinical manifestation, are expressed through the following: Hot, Cold, Deficient, Excess, moving, stagnant, Damp, Dry, Clear (Clean), Turbid (Impure), open (accessible), closed (armored), and leaking.

LOCATIONS OF ENERGETIC BLOCKAGES

In clinical practice we generally observe six main areas in the patient's body where energy becomes trapped and blocked. Each energetic blockage is an expression of the patient's ability to armor and protect him or herself from emotional wounding. These six main areas in the patient's body can be the foundational base and the root cause for the patient's disease (Figure 30.3). These six main areas are described as follows.

THE AREA OF THE HEAD

The area in the cranium that is most commonly obstructed is within the base of the occiput, at the back of the head. This obstruction is usually noted within patients who suffer from migraine headaches and brain tumors. This barrier is often created through chronic stress patterns which cause the Liver's Heat to rise up the patients' back and become trapped inside the head. This condition is usually caused by intense concentration. Too much hard focusing can also cause Qi to condense and stagnate. The location of Qi obstructions due to physical trauma vary according to each type of trauma, and the and the severity of the injury.

THE AREA OF THE THROAT

This area separates the Upper Dantian (the spiritual/perceptive center) from the Middle Dantian (the emotional/empathic center). Messages of divine inspiration and awareness descend downward from the Heavens through the Baihui area seeking to stir the emotions of the Heart. If the patient is not receptive (due, for example, to a disconnection or even a resistance to spiritual growth) a barrier is sometimes formed within the patient's throat, dividing the Upper Dantian from the Middle and Lower Dantians.

This barrier can also be created to stop emotions from flowing through the Heart and rising upward to be released through the windows and caverns of the soul (the eyes, ears, nose, tongue, body, and spirit). If, for example, the teeth become clenched and the throat tightens from feelings of grief or anger, these emotions can become trapped in the throat, forming a "plum seed" or "knot." When the Lungs' Qi congeals in the areas of the upper chest, shoulder blades, neck and the back of the occiput, this indicates chronic suppression of these emotions. It is also evidence of the mind and body struggling to reconnect and express the emotional and spiritual self.

THE AREA OF THE HEART

The Heart is energetically divided into two main chambers. The upper chamber houses and responds to spiritual emotions, while the lower chamber houses and responds to sensual emotions.

Patients will tend to suffer not only from repressing their basic biological drives (the sensual emotions based in the lower chamber of the Heart), but also by repressing their emotional connections with the divine (by failing to accept their higher spiritual calling or spiritual enlightenment associated with the upper chamber of the Heart). The higher self is the focal point of the superconscious realm; it is all-inclusive and at the very center of our being where individuality and universality blend (center core).

Patients who have chronically armored their Heart tend to exist in a state of guarded suspicion. This pattern of emotional suppression tends to lead to Qi stagnation and the creation of disease. When patients armor their upper chamber, they tend to hide in the emotions of their lower chamber and visa versa. Patients who armor the upper chambers of the Heart, for example, may become involved in relationships of extreme sensual passions related to the Heart's lower chamber, to avoid painful unresolved issues hidden within the past. The deeper and more energetically charged the issues, the stronger the sensual passions. Whereas, patients who armor the lower chamber of the Heart, might become involved in relationships of extreme spiritual, or religious passions related to the Heart's upper chamber to hide from their painful unresolved issues. The deeper and more energetically charged the issues, the stronger the spiritual or religious passion.

THE AREA OF THE DIAPHRAGM

The diaphragm area separates the Middle Dantian (the emotional center) from the Lower Dantian (the physical/sexual center). When a barrier in this particular area is created, it separates the emotional Heart from feeling the sexual passion which rises up from the Lower Dantian and the Kidneys' area.

It is interesting to note that patients with a


Energetic Complications and Stagnations
Compressed Energy Stagnation
Contracted Energy Stagnation
Bloated Energy Stagnation
Expanded Energy Stagnation
Energetic Armoring
Energetic Depletion
Energetic Leakage
Migrating Qi Deviation
Psychosexual Qi Deviations

Figure 30.4. The Body's Energetic Complications and Stagnations

barrier in the diaphragm sometimes enjoy the physical sensations of sexual intercourse, but are separate from their spiritual/emotional connection to true bonding or "oneness" with their partner. Again, the connection between the emotional spirit and body/mind has been severed.

THE AREA OF THE YELLOW COURT

The Yellow Court (CV-12) is an area located in the center of the chest, just below the diaphragm and xiphoid process of the sternum. Its function is that of being the access area to release the body's internal organs' emotional memories. Its location is also attributed to the Third (solar plexus) Chakra.

To access the patient's stored emotional memories and release them from the Yellow Court, the Qigong doctor supports the patient's Shendao GV-11 (Spirit Gate) with the left hand while energetically manipulating the patient's Yellow Court area with the right hand. If the patient is not energy sensitive, the doctor uses a slight Compression/Release technique (see Chapter 37) to disperse the patient's armoring system.

The patient should be in a supine position, with knees pointed upward, feet flat, arms by his or her sides, mouth open, inhaling deeply into the Lower Dantian. As the patient exhales, the doctor lightly compresses the patient's Yellow Court until a deep groaning sound begins to resonate from the patient's thorax. The doctor circulates the energy from the patient's Yellow Court into the Shendao, filling up the patient's Heart with energy. The doctor then moves this energy back into the patient's Yellow Court. This process continues until the patient's suppressed emotions surface and are released.

Note: It is important to first purge and release the Lungs of grief before attempting to access the patient's Yellow Court.

THE AREA OF THE LOWER ABDOMEN

This area also separates the Lower Dantian from the Middle Dantian, insulating the sexual feelings from the middle and lower torso. This energetic freezing of the pelvis is usually found in victims of rape, sexual molestation, or in women who have had one or more abortions. The Qi flowing into the lower pelvis and legs becomes blocked due to stored fear, shame, guilt, and sorrow. Sometimes the patient's physiology in that particular area may become obese; the abdomen, thighs or hips may be heavily padded and armored due to Qi stagnation. Often times, victims of childhood sexual abuse become overall obese to avoid attracting the opposite sex, or to block and pacify these hidden traumatic memories.

TYPES OF ENERGETIC COMPLICATIONS

Each organ and channel has the potential to carry or create several types of energetic complications and stagnations. The doctor should observe and feel the shifts in the patient's energetic balance to determine the specific conditions of the disorder (Figure 30.4).

COMPRESSED AND CONTRACTED ENERGY STAGNATION

Compressed or Contracted energy stagnations are sometimes considered a Yin condition due to the type of energetic compression involved in its formation.

- Compressed Stagnation is caused by the patient's energy pressing downward (externally moving inward) and will feel armored and hollow (Figure 30.5). When this type of energetic stagnation disperses it does not energetically unwind, but disperses and dissolves into the surrounding tissue areas. Because the patient's surrounded consciousness has armored the tissue area, the energetic dispersion can sometimes cause spontaneously released emotions or behavior such as crying, laughing, shouting, screaming, sighing, coughing, etc.
- Contracted Stagnation is caused by the patient's energy pulling inward, and will generally feel armored and solid (Figure 30.6). This type of energetic stagnation can be formed by an emotional core, or focused concentration, that draws additional Qi into its center, compacting the belief structure, layer after layer with energy. When this type of energetic stagnation disperses it can sometimes begin energetically unwinding throughout the entire body. This energetic unwinding sometimes creates involuntary muscle twitches and physical undulations.

Body tissues and muscles accumulate emotional energy, becoming hard and tense in the adjacent areas. Denseness indicates the accumulation of pathogenic stagnant Qi. If this energy block remains, disease can manifest as ovarian cysts and tumors, or even in extreme cases as cervical cancer. Breast cysts, tumors, and cancer can result from stagnant Qi in the Lungs, or from a combination of Lung and Liver Qi stagnation. This type of stagnant energy feels very Hot and volatile because of the accumulated anger and rage.



Figure 30.5. Compressed Stagnation



Figure 30.6. Contracted Stagnation

Treatment Principals for Compressed and Contracted Energy Stagnation

The Qigong doctor disperses and purges the patient's stagnant Qi using the Thunder Palm technique, Tiger Kneading techniques, and counterclockwise Circular Spiraling (see Chapter 34).

BLOATED AND EXPANDED ENERGY STAGNATION

Bloated and Expanded energy stagnations are sometimes considered a Yang conditions due to the type of energetic expansion involved in their formation. Qi stagnation, with a characteristically expansive or bloated appearance, can be caused from an accumulation of Phlegm and Body Fluids (in addition to Qi and Blood) in the adjacent tissue areas of the body (Figure 30.7 and 30.8). This type of stagnation usually occurs in the Lower Dantian and abdominal areas. These are examples of Excess syndromes of stagnant energy and manifest as: distending, turbid, leaking, tingling, and dense Qi.

If this type of energy stagnation remains obstructed, the resulting disease can manifest as edema within the tissues, colitis, or angina pectoralis due to unprocessed despair and grief (in the Lungs) with anxiety (in the Spleen). The energy of grief and despair feels thick, heavy, and slimy like phlegm or mucus. Often this energy is felt in the Lungs, as well as in the Spleen.

Treatment Principals for Bloated and Expanded Energy Stagnation

The Qigong doctor disperses or dissolves the patient's stagnant Qi by using the Tiger Kneading, Vibrating Palm, and Shaking Palm techniques (see Chapter 34).

ENERGETIC ARMORING

This condition can result from the patient protecting specific tissues, organs, or areas of the body. Energetic armoring is initiated when the patient freezes certain emotional feelings to maintain the denial system. Patients may be unaware of this armoring condition because they dissociate from the original trauma, or minimizing its severity. Emotions attributed to energetic armoring are generally manifested as anger, fear, guilt, and shame. The angry patient's denial system is maintained through physically or emotionally attacking others; the anxious patient, full of fears, guilt, and shame, copes by "Shening out." Both of these reactions shield the patients in emotional situations from their own feelings, while reinforcing the energetic armoring.



Figure 30.7. Bloated Stagnation



Figure 30.8. Expanded Stagnation

Armoring results in tense organs and tissues. When patients cannot feel their body, other complications can arise, such as compressed, contracted, bloated or expanded energetic stagnations.

Treatment Principals for Energetic Armoring

The Qigong doctor can assist the patient through "soul retrieval" to unlock the feelings logged deep within the body's tissues (see Chapter 19). The primary goal is to first help the patients acquire a sense of security within their own body, then address the root of the disease.

ENERGETIC DEPLETION

Whole body depletion results from the following conditions:

- Not receiving enough Postnatal Qi for restoration, resulting in improper internal organ functioning,
- From suppressing emotions (e.g., worry or fear),
- Experiencing a damaged energetic field due to trauma, or
- Being born with a Deficient prenatal constitution.

Generally, energetic depletion can result in physically undeveloped areas in the body. In some cases, emotional traumas can cause specific organs or tissues to become energetically depleted to the degree that their natural development cannot take place.

Treatment Principals for Energetic Depletion

The Qigong doctor, if qualified, can assist the patient by prescribing herbal tonics. The patient should also be encouraged to eat regular, nutritional meals and to balance work with relaxation time. If the patient's energetic field has been damaged, the Qigong doctor can repair it by using Flat Palm and Circle Spiraling techniques (see Chapter 34).

ENERGETIC LEAKAGE

Energetic leakage is a result of the patients releasing Qi from out of their joints, due to injury or unconscious sabotage. When energy drains from the patients' joints, the specific areas along the channels become depleted, resulting in a Deficient Qi which can cause an atrophy syndrome. Any type of energetic thinness along the Wei Qi field indicates an insufficiency of Qi. A Deficient energetic field can result in an empty, numb, or weak feeling of Qi within the tissue areas.

Treatment Principals for Energetic Leakage

The doctor envelops the patient's depleted tissue area (which is leaking) with Spiral Wrapping techniques to create an energetic cast that allows the patient's energetic field to completely heal (see Chapter 34).

MIGRATING QI DEVIATION

Migrating Qi Deviations can result from either the patient's suppressing and avoiding feelings, or from Wind invasion (either Internal or External). In Traditional Chinese Medicine this condition is known as Wind Bi (Wind Pain) or Wandering Bi (Migrating Pain). Once patients feel cornered by a specific memory, they subconsciously shift the toxic energy to another part of their body; this energetic shifting requires the treatment to be restarted. When treating these patients, it is important to first connect the original trauma to the Heart to prevent these energetic shifts, and to stabilize the condition. Once stabilized, disperse the Wind Invasion and tonify any Deficient organ.

Treatment Principals for Migrating Qi Deviation

The Qigong doctor first envelops the primary area of complaint, isolating the pain, and then begins to internally Spiral Circulate the patient's internal Qi. Once the energy is in motion, the doctor leads the Toxic Qi out of the patient's body.

PSYCHOSEXUAL QI DEVIATION

Psychosexual Qi Deviations can result from an immediate energetic tissue over-stimulation. Patients with this condition experience intense sexual undulations and orgasms when being treated in a safe clinical environment. This reaction is due to their avoidance issues, brought about by an energetic trigger mechanism. This psychosexual reaction usually takes place when touching any part of the torso or extremities. Because the energy seeks balance (much like water), when it flows into the genital area, the sexual neurons become overstimulated, activating and releasing the energetic turbulence already stored therein. This condition is mostly found within patients who have either been raped or molested as children.

Treatment Principles for Psychosexual Qi Deviation

The doctor is encouraged to refer the patient to a psychotherapist who specializes in such trauma. Meanwhile, the doctor continues to treat the patient by rooting the patient's Heart (emotional chamber) to the patient's Lower Dantian (sexual chamber). Once this connection is established, the doctor reconnects the patient's Lower Dantian to the patient's Upper Dantian (spiritual chamber), forming a complete body connection within the patient's Taiji Pole. By reconnecting the sexual chamber with the spiritual chamber, the doctor empowers the patient, allowing the patient to reclaim his or her true sexual/spiritual identity.

PATIENT'S ENERGETIC FACIAL DISTORTION

Sometimes, when treating a patient, the Qigong doctor will notice the patient's facial features energetically distort, changing their facial pattern. These facial distortions can appear and disappear rapidly, or maintain their illusion for several seconds. The cause for the patient's energetic facial distortion can be brought on by several factors: The Patient Reliving A Past Trauma, The Ancestral Patterning of the Patient's Jing, or The Energetic Manifestations of the Patient's Active Spiritual Guardians.

1. The patient reliving a past trauma can release an energetic distortion that expresses itself on the energy field of the patient's face. This projected image reflects the age and time frame wherein the patient received the initial trauma. Often, as the doctor connects with the energetic root of the patient's disease, the patient's face will regress to reveal the delicate features of the patient as a young child. This visual facial pattern of energetic age regression reveals the exact age the patient suffered the initial trauma.
2. The ancestral patterning of the patient's Jing can also be released as energetic distortions that express themselves on the energy field of the patient's face. Occasionally, these projected images can reflect the patient's ancestry, or reveal an ancestral guide. Multiple projections of racially identifying features; images of men, women, and sometimes children will appear to shadow the patient's features, much as a projected image over an original form.
3. The energetic manifestations of the patient's spiritual guardians are believed to project their image onto the face of the patient during treatment. Some cultures accept that these guides manifest in the form of animals. The animal form will appear to flicker across the patient's face and then dissipate. This phenomenon is the most rarely seen of all the energetic facial distortions.

PATIENT RESISTANCE TO ENERGETIC THERAPY

Sometimes, in order to avoid the painful memories, the patient will subconsciously sabotage the treatments. Resistance can manifest in one of four ways.

1. Falling asleep is a form of physical escape.
2. Excessive talking is a mental form of avoidance behavior.
3. Irritability or sexual response is a form of emotional escape.
4. "Shening out," also called "spacing out," is a form of spiritual escape.

When observing these patterns, the doctor encourages the patient back into the body to feel the emotions and memories trapped in the particular areas being treated. It is important for the doctor to let the patient know the cause and effect of the patient's chosen defense mechanism. These personal conversations are necessary for the patient's growth and emotional healing. In cases of sexual response, tact and appropriate professional boundaries are especially important.

When emitting Qi, the doctor can encourage the patient's Shen to stay in its residence by asking the patient to focus his or her breathing on the tissue areas being treated. This focused attention causes the patient's Po to settle and calm themselves within the patient's body, allowing the patient's Hun to communicate the feelings surfacing within the patient's Heart.

UNBLOCKING THE FIVE PASSES

The Wu Guan or Five Passes refer to the five important gates on the Governing Vessel. These gates, or passes, are sometimes called Tie Bi, which translates as the "iron wall," and are the areas of the body where it is most difficult for the energy to pass through when circulating the Microcosmic Orbit. Free passage through the Governing Vessel is important, especially when tonifying the patient's body or regulating the patient's Qi. To circulate the Qi up the Governing and down the Conception Vessels, these five gates must remain open.

Opening these Five Passes are essential for the treatment of diseases in the neck and lumbar-sacral regions. In Medical Qigong therapy, disease is sometimes an indication that both the Governing and Conception Vessels have been, or are, in a state of disconnection. If disorders of Qi, along with Qi obstruction, develop along the Governing and Conception Vessels, the doctor should emit Qi into one of the Five Passes (depending upon the affected area) to facilitate the regulation of Qi (Figure 30.9).

THE LOWER SPINAL PASS

The Lower Spinal Pass or "Coccyx Pass" (Wei Lu Guan) is located on the lowest segment of the spine just posterior to the anus, near the Chang Qiang GV-1 point. If Qi becomes blocked in this area the patient suffers a dull persistent pain by the coccyx, along with feelings of heaviness.

To treat, have the patient direct energy up the Lower Spinal Pass, using mild or gentle intention; have the patient position the tongue against the upper palate and inhale deeply while gently contracting the anus and abdominal muscles. These gentle contractions of the muscles along with the position of the tongue on the upper palate create an energetic sacral pump, which facilities the release of the energetic block.

THE MIDDLE SPINAL PASS

The Middle Spinal Pass consists of the Mingmen (GV-4) area and two points (Jia Ji Guan) located on the lateral sides of the Mingmen. If Qi becomes blocked in these areas the patient suffers a dull persistent pain in the middle of the spine, or on one or both sides of the Mingmen. This obstruction causes a physical sensation that feels like a spinal rupture, break, or herniated disc near the waist area when Qi circulates through these points.

To treat this disorder, the doctor extends Qi into the patient's Middle Spinal Pass, while leading the patient's energy upward along the Governing Vessel.

THE UPPER SPINAL PASS

The Upper Spinal Pass is located between the shoulders on the Shendao point (GV-11) Spirit Gate. If Qi becomes blocked in this area, the patient suffers a dull persistent pain on the midline of the upper back below the fifth thoracic vertebra. This obstruction causes a physical sensation that feels like a spinal rupture, or causes intense Heart pain when Qi circulates through this point.



Figure 30.9. The Five Spinal Passes

To treat this condition, the doctor extends Qi into the patient's Upper Spinal Pass, while leading the patient's energy upward along the Governing Vessel.

THE OCCIPITAL PASS

The Occipital Pass (Yu Zhen Guan) is located just inferior to the occipital bone where the brain originates. If the Qi becomes blocked at this area, the patient suffers a dull persistent pain around the occiput, stiff neck, feelings of heaviness, as if there is something were stuck inside the back of the head.

To treat this problem, the doctor should instruct the patient to close the eyes, raise the head slightly and look upward, while gently concentrating on the Baihui GV-20 point. Have the patient imagine the energy block as a cube of ice. The ice melts into water, the water dissolves into vapor, and travels upward along the Governing Vessel into (and through) the Baihui area, then proceeds down the Conception Vessel toward the Lower Dantian.

THE CRANIAL PASS

The Cranial Pass is located at the vertex on the midline of the skull. If the Qi becomes blocked at this area, the patient suffers a dull persistent pain around the eyes and the top of the head, as well as feelings of heaviness, as if there is something were stuck inside the top of the head.

To treat this condition, the doctor instructs the patient to close the eyes, raise the head slightly, while gently concentrating on the Lower Dantian. Have the patient imagine the energy block as a cube of ice. The ice melts into water, the water dissolves into vapor, and travels downward along the Conception Vessel toward the Lower Dantian.

FURTHER COMPLICATIONS

In balancing the patient's energetic body, the doctor first locates the Excess or Deficient condition, determines if the tissues should be tonified, purged, or regulated, then ascertains which energetic complications have initiated the patient's disease.

The doctor must also determine if the patient is sensitive to treatment or resistant to energetic therapy. Below is a summary listing several energetic complications and suggestions on how to rectify them.

1. For Compressed Stagnation, break up the stagnation, purge the pathogens, then tonify and regulate the patient's Qi.
2. For Contracted Stagnation, break up the stagnation, purge the pathogens, then tonify and regulate the patient's Qi.
3. For Bloated Stagnation, break up the stagnation, purge the pathogens, then tonify and regulate the patient's Qi.
4. For Expanded Stagnation, break up the stagnation, purge the pathogens, then tonify and regulate the patient's Qi.
5. For Energetic Armoring, access the patient's Heart (through the Shendao GV-11 area), and induce "soul retrieval" (see Chapter 19).
6. For Energetic Depletion, tonify and regulate the patient's Qi.
7. For Energetic Leakage, envelop the patient's tissues creating an energetic cast to stabilize the energetic fields.
8. For Migrating (Wandering) Qi Deviations, purge the pathogens and then isolate and stabilize before tonifying and regulating the patient's Qi.
9. For Psychosexual Deviations, root the patient's Heart, then regulate the patient's Taiji Pole with divine healing light.

CHAPTER 31
THE MAGIC SQUARE OF THE YELLOW RIVER

The configuration known as the Lo Shu (Lo Writings) or Magic Square of the Yellow River, is shown below. It is said to have been derived from markings on the shell of a "spiritual turtle" that crawled out of the River Lo when the Emperor Yu was draining off the floods. It is considered a mathematical model of the universe. The relationship between the numbers presented in this chart may be used to diagnose the energetic relationship between universal and environmental phenomena, as well as the various pathologies within the occurring internal organ correspondence.

It corresponds to the Later Heaven sequence of the trigrams of the Yi-Jing (I-Ching) and is arranged in accordance with the directions of the compass, with the number "5" at the center of the compass, in an arrangement known as the "Magic Square."

The numerals 1–9 are assigned to each position in accordance with the Lo Scroll markings and represent the Acquired Essences (Postnatal Jing).

Understanding the concept of balance is paramount in Qigong medicine. When Yin and Yang energies in the body are balanced, health is established. The Chinese have given numerical relationships to Yin and Yang properties representing this dynamic connection.

Yang energy is represented by all the odd numbers (1, 3, 5, 7, and 9). Yin energy is represented by all the even numbers (2, 4, 6, and 8).



Figure 31.1. Yin and Yang Number Balance



Figure 31.2. The Magic Square

The cycling of Yang (odd numbers) and Yin (even numbers) indicates the law of motion of Yin and Yang in all things. In Chinese medicine the numerical configuration is based on the sum totaling ten (Figure 31.1).

The numbers arranged together create what is known as the Magic Square. Investigation will uncover several numerological correspondences (Figure 31.2). The sum of any two numbers opposite each other in a row, column, or diagonal (with the number "5" between them) equals 10; thus the sum in any of these rows, columns, or diagonals equals 15. Fifteen is the number that represents "Man," who lives between Heaven above (the number being 20, which equals the sum total of the four primary directions) and Earth below (the number also being 20, which equals the sum total

SW =	2 }		SE =	4}		
NE =	8 }		NW =	6}		
	10	+		10	=	20 Yin Earth Qi
S =	9 }		W =	7}		
N =	1 }		E =	3}		
	10	+		10	=	20 Yang Heaven Qi

Figure 31.3. Heaven and Earth Numbers

of the four secondary directions). The numbers in the four primary directions (north, south, east and west) are odd and represent Yang Heaven Energy, while the numbers on the corners are even and represent Yin Earthly Energy (Figure 31.3).

EARTHLY YIN ENERGETIC FLOW

The numbers on the corners of the Magic Square are "terrestrial" in design. All the terrestrial numbers are even numbers. They represent the Earth's energetic field and flow counterclockwise in their circular progression. These terrestrial cycle phases are expressions of Earthly Yin energy and are designed in progressions of "times two." For example, (2) Fire: 2 x 2 = (4) Metal: 4 x 2 = (8) Wood: 8 x 2 = (16) Water (which is reduced to 6, as the ten position is not counted): 16 x 2 = 32 (which is reduced to 2). This completes one cycle in the terrestrial progression, which then returns to the element Fire and begins all over again in the same fashion, continuing in an endless progression of "times two." (Figure 31.4).

Through understanding the Yin energetic progression, the Qigong doctor rotates the patient's energy in a counterclockwise direction to purge Excess conditions and expel pathogenic Qi (called "Yin destroying Evils").

HEAVENLY YANG ENERGETIC FLOW

The numbers on the sides of the Magic Square are "celestial." All the celestial numbers are odd numbers. They represent the Heaven's energetic field and flow in a clockwise circular progression. These celestial cycle phases are expressions of Heavenly Yang energy and are designed in progression of "times three." For example, (1) North: 1 x 3 = (3) East: 3 x 3 = (9) South: 9 x 3 = (27) West (which is reduced to 7, as the ten position is not counted): 7 x 3 = 21 (which is reduced to 1). This completes one cycle in the celestial progression, which then returns to the North and begins all over again in the same fashion, continuing in an endless progression of "times three."

In understanding the Yang energetic progression, the Qigong doctor will rotate the patient's energy in a clockwise direction to tonify. This technique facilitates the continuous circulation of Yang Qi and is used in order to help the tonification of Qi and Blood and replenish Deficiencies (called "Yang promoting growth").


South
Front
Heaven Cycle
Yang
Metal
Fire
Left
East
Center
Earth
Right
West
Earth Cycle
Yin
Back
North
Wood
Water
Lo Scroll



	South East	South	South West	
	☴ (GB-41) 4 Belt Vessel	☲ (Lu-7) Heart 9 Fire Conception	(Kd-6) ☷ 2 Yin Heel	
East	Liver (TB-5) ☳ 3 Wood Yang Linking	5 Spleen Earth	(SI-3) Metal Lungs 7 ☱ Governing	West
	Yin Linking 8 ☶ (Pc-6)	Yang Heel (Bl-62) Kidneys 1 Water ☵	Thrusting 6 (Sp-4) ☰	
	North East	North	North West	

The Magic Square

Figure 31.4. The reason the South is positioned on the top of the page is because, in China, maps were specifically designed for the convenience of the Emperor, whose throne was always positioned facing South, the direction of Yang energy. As the magistrates of his court unrolled the maps before him, the East would be positioned on his left, the West to his right, and the South furthest away at the top of the map (whereas, in the Western culture North is at the top).

THE MAGIC SQUARE AND EIGHT TRIGRAMS

The following Eight Trigram Hand chart represents the terrestrial aspect of the body's acquired structures, evolution, and exchange of Yin / Yang energy.

It should be noted that if the trigrams associated with the numbers shown in the Magic Square are placed in their correct positions, the postnatal or "Later Heaven" trigram arrangement will form. The middle number "5" does not correspond to a trigram because it is the unifying number placed in the center.

In order to use the Eight Trigrams in conjunction with the Magic Square, the patient's palm is divided into nine sections. The Eight Trigrams form the exterior of the palm, while the heart of the palm (known as the Bright Hall or Ming Tang) aligns the Magic Square to the patient's internal organs. The Qigong doctor observes the color, luster, sinking or bulging of skin, as well as any prominent blue veins appearing on the surface of the patient's skin. These observations are compared to the organs and functions associated with each trigram that rules that particular area of the patient's palm (Figure 31.5).



Figure 31.5. The "Magic Square" can be superimposed on the human body for observation, diagnosis, and treatment. For example:

2 and 4 represent the location of the Lungs

3 and 7 represent the location of the Liver and Spleen

8 and 6 represent the location of the Kidneys

9 represents the location of the Upper Burner

5 represents the location of the Middle Burner

1 represents the location of the Lower Burner

1. The Trigram Kan, located at the base of the palm's heel, is associated with the patient's Kidney and Bladder organs, as well as the function of their urogenital and reproductive systems.
2. The Trigram Kun, located on the palm just below the little finger, is associated with the patient's left Lung organ and the left side of the chest (the left breast in women).
3. The Trigram Zhen, located on the upper part of the patient's thenar eminence, is associated with the function of the patient's Liver and Gall Bladder organs.
4. The Trigram Sun, located on the palm, just under the index finger, is associated with the patient's right Lung, and the right side of the chest (the right breast in women).
5. The Bright Hall (Ming Tang), located on the center of the palm is associated with the patient's Heart, blood vessels, and mental health.
6. The Trigram Qian, located on the lateral edge of the palm's heel, just above the wrist crease, is associated with the patient's descending and sigmoid colon.
7. The Trigram Dui, located on the lateral edge of the palm's heel, midway between the little finger and the wrist crease, is associated with the patient's Spleen, pancreas, and Stomach organs.
8. The Trigram Gen, is located on the lower half of the thenar eminence, is associated with

Trigram Correspondences

Trigram	Name	Meaning	Channel	Shu Point	Direction	Number	Season
☲	Li	Fire (Clinging)	Conception	Lu-7	South	9	Mid Summer
☷	Kun	Earth (Receptive)	Yin Heel	**Kd-6**	South West	2	Start of Fall
☱	Dui	Lake (Joyful)	Governing	**SI-3**	West	7	Dividing of Fall
☰	Qian	Heaven (Creative)	**Thrusting**	Sp-4	North West	6	Beginning of Winter
☵	Kan	Water (Abysmal)	Yang Heel	**Bl-62**	North	1	Absolute Winter
☶	Gen	Mountain (Keeping Still)	Yin Linking	**Pc-6**	North East	8	Start Of Spring
☳	Zhen	Thunder (Arousing)	Yang Linking	**TB-5**	East	3	Dividing of Spring
☴	Sun	Wind (Gentle)	Belt	GB-41	South East	4	Start of Summer

Figure 31.6. The Eight Trigram Correspondence

patient's appendix and ascending colon.

9. The Trigram Li, located on the palm between the middle and ring finger, is associated with the patient's blood circulation, Heart and eyesight.

THE MAGIC SQUARE AND THE EIGHT EXTRAORDINARY VESSELS

In Chinese medicine, the Lo Writings and their correspondences form the model which is the basis for the Ling Gui Pa Fa (The Eight Techniques of the Mysterious Turtle) system of acupuncture. In this system there are Eight Confluential Points that are associated with the Eight Trigrams (Figure 31.6). These points are where the Eight Extraordinary Vessels and Twelve Primary Channels intersect each other.

This method describes the theory that all the points on the body are dominated by the Shu Points, which are in turn dominated by the Eight Confluential Points. The confluential points and their trigram correspondences are Kd-6 (Kun Gua), Lu-7 (Li Gua), GB-41 (Sun Gua), TB-5 (Zhen Gua), Pc-6 (Gan Gua), Sp-4 (Qian Gua), SI-3 (Dui Gua), and Bl-62 (Kan Gua).

UNDERSTANDING THE METAPHYSICAL ASPECT OF NUMBERS

The Chinese medical text of the Nei Jing explains numerology and its mystical significance, as well as the practical utilization of the correspondences between numbers and natural phenomena. Man's physical, mental, emotional, energetic, and spiritual form manifest as part of the microcosm of these nine correspondences, and are explained as follows.

1. Number One corresponds to Heaven, the Center Taiji Pole, and represents the skin.
2. Number Two corresponds to Earth and represents the muscles. The number two also cor-

responds to the two primary forms of Yin and Yang.

3. Number Three corresponds to Man and represents the blood vessels. The number three also corresponds to the Triple Burners, Three Powers, Three Treasures, Three Dantians, and Three External Fields of Wei Qi.
4. Number Four corresponds to the four seasons and represents the muscles corresponding to the body's four extremities, the Four Earthly Quadrants and the Four Divisions of Heaven (N.S.E.W.), and the Four Prenatal Trigram Essences (Great Yang, Small Yang, Great Yin, and Small Yin).
5. Number Five corresponds to the Five Notes of the Chinese pentatonic scale and represents the voice. The number five also corresponds to the Five Elements, Five Colors, Five Tastes, Five Planets, and the Five Elemental Constitutions.
6. Number Six corresponds to the Six Divisions (Tai Yang, Shao Yang, Yang Ming, Tai Yin, Shao Yin, Jue Yin) and represents the union of Yin and Yang. The number six also corresponds to the Six Yao lines and their correspondence to the body, and the Six Accomplishments (intelligence, humanity, holiness, sincerity, moderation, and benevolence).
7. Number Seven corresponds to the Seven Luminaries (sun, moon, and the five planets), which represent the Seven Openings of Man (two eyes, two ears, two nostrils, and one mouth). The number seven also corresponds to the Seven Emotions, and the Seven Stars of the Big Dipper.
8. Number Eight corresponds to the Eight Extraordinary Channels from which the body's prenatal energy flows and represents the breath. The number eight also relates to the Eight Trigrams and their various correspondences.
9. Number Nine corresponds to the formless Void or Wuji, as well as the Nine Heavens (one is centered, and the others are in the eight separate divisions of the Lo Pan compass) and the Nine Lo River Chart (Magic Square). The number nine also represents the nine openings of man (two eyes, two nostrils, two ears, one mouth, one anus, and one urethra).

THE FIVE ELEMENT ENERGETIC FLOW OF THE MAGIC SQUARE

The number formations on the Magic Square are not only considered the energetic ebb and flow, evolution and exchange of Yin and Yang Qi, but also correspond to the energetic harmony of the Five Elements. The energetic harmony of the Five Elements are arranged as follows.

- The Kidneys are positioned in the North; their element is Water and number is 1.
- The Liver is positioned in the East; its element is Wood and number is 3.
- The Heart is positioned in the South; its element is Fire and number is 9.
- The Lungs are positioned in the West; their element is Metal and number is 7.
- The Spleen is positioned in the Center; its element is Earth and number is 5.

These five numbers are arranged in accordance to their energetic progression and are used as a templet for observation and diagnosis of the patient's body, according to their Five-Elemental postnatal structure.

CROSSOVER ENERGY PATTERNS

According to the theory of energetic harmony, when one area of the body lacks Qi, there is generally an Excess energy accumulation in another area. Because the body is symmetrical, one can naturally look on the opposite side for the misplaced Qi. The Qigong doctor may dredge the full side in order to drain the Excess and support the Deficient area.

If the imbalance is not on the opposite side, the doctor can scan for Excess Qi using a figure eight pattern (Figure 31.7). Classically, the Crossover Energy Pattern is one of the most powerful pathways by which Qi flow in the body can be stimulated, and is excellent for balancing internal body energy. The figure "8" pattern can also be used in order to balance all sides of the body (top and bottom, as well as left and right).

When the Qigong doctor must balance the energy in the left and right sides of the brain, the patient may be assigned homework that requires them moving Qi in a figure "8" pattern sideways (i.e., drawing the infinity symbol). This exercise prescription stimulates, strengthens, and balances the right and left hemispheres of the patient's brain. It is used successfully in the treatment of patients with dyslexia.

When patients have internal problems that affect the function of the whole body, it may be necessary to treat two areas simultaneously. The Spleen and Stomach areas, for example, may be tonified along with the Lung areas to strengthen and increase the patient's resistance to External pathogenic factors.

Because organ imbalances are deeper, and tend to be the result of years of energetic deviations, they may take longer to reverse.



Figure 31.7. In this Crossover Energy Pattern, area 4 is treated using area 6 and so on.

CHAPTER 32
HEALING THE PATIENT'S EMOTIONAL TRAUMAS

INTRODUCTION

In my personal practice I feel the main problem for patients is in dealing with their own "hurt," which may have been inflicted upon them several years prior to the manifestation of their disease. It is a recognized truth that when people isolate themselves from each other, their environment, and their spiritual life, it is because they feel the need to guard themselves.

They guard and protect themselves and their belief structures from invasion, criticism, exploitation, or attacks, whether real or imagined, allowing interchange only if it supports their beliefs.

People build energetic walls, and when the walls are penetrated they often experience anger, self-hatred, pain, fear, and shame. Consequently, masks and defence mechanisms are created to hide and support these hidden belief structures.

How the patients develop and maintain their energetic patterning will determine which clinical modality the Qigong doctor will utilize to initiate healing. To free themselves from personal hurt the patients must reconnect with their anger, pain, fear, or worry. Eventually, with the unconditional loving support of the doctor, patients are able to reintegrate the hurt and anger, and accept parts of themselves they had rejected for so long. This acceptance of painful feelings and memories affects the Heart and frees the patients from the emotional traumas of the past.

To heal and release these pathogenic emotions, the patients go through a five-stage detoxifying process during which they feel, experience, and release the emotional trauma that initiated their disease. This is a natural progression in the process of Medical Qigong therapy and healing.

THE PHYSIOLOGICAL EFFECTS OF BENIGN AND CHRONIC EMOTIONS

Within the clinic it is observed that benign emotions (love, joy, peace, etc.) bring about a calm and restful condition within the patient's physiology. Chronic emotions however, create a detrimental stressful physiology, adversely affecting the quality of the patient's life-force energy. As discussed previously, emotional internal and external environmental factors can and do affect the quality of the body's Qi.

1. Excessive joy from the Heart slows down the Qi.
2. Excessive worry and thinking from the Spleen stagnates the Qi.
3. Excessive sadness from the Lungs obstructs the Qi.
4. Fear from the Kidneys descends the Qi.
5. Excessive anger from the Liver ascends the Qi.

FIVE LEVELS OF FEELING AND THEIR GOVERNING ORGANS

To complete their initial healing, the patients go through five stages of emotional resolution. These stages act as a template for the patients' emotional healing, allowing them to progress through, and detoxify each of their Five Yin Organs. The Five Yin Organs store the patients' emotional history in their tissues. Each of the Five Yin Organs also affects different functions and parts of the body (Figure 32.1).

1. The Liver governs the emotions dealing with the past. The Liver stores the negative emotions of irritability, jealousy, anger, rage, blame, and resentment. These emotions and mental states affect the flow of Qi in the channels, influencing the patient's tendons, ligaments, nails, small muscles, peripheral nerves,


(1)
Heart
Seat of all Emotions
(Affects Blood Circulation,
Mental and Emotional Activity)
Hurt Triggers
Emotional Reactions
(2)
Liver
(Stores Anger from Past)
Affects
External Strength
and
Decision Making
(3)
Lungs
(Stores Grief of the Present)
Affects
Breath, Skin and
Metabolism of Body
Fluids
(4)
Kidneys
(Stores Fear of the Future)
Affects
Will Power, Jing,
Sexuality and Short Term
Memory
(5)
Spleen
(Stores Worry of the Future)
Affects
Concentration,
Memorization,
Digestion and Muscles

Figure 32.1. Diagram of Five Elemental Emotional Transitions

external strength, the iris of the eyes, vision, tears, the Gall Bladder, bile, decision making, the external genitalia, and the Hun (Three Ethereal Souls).

2. The Lungs govern the emotions dealing with the present. The Lungs store the negative emotions of grief, sorrow, sadness, anxiety, shame, guilt and disappointment. These emotions and mental states affect the flow of Qi in the channels, as well as the patient's breath, skin, Large Intestine, mucous membranes, the metabolism of the Body Fluids, body hair, smell, and the Po (Seven Corporeal Souls).
3. The Kidneys govern the emotions dealing with the future. The Kidneys store the negative emotions of fear, loneliness, and insecurity. These emotions and mental states affect the patient's energetic channel flow, as well as the Jing, bones, brain, bone marrow, inner ear, hearing, head hair, pubic hair, spinal cord, cerebrospinal fluid, ovaries, testes, anus and urethra, sexual fluid, reproduction, short term memory, and the Zhi (Will Power).
4. The Spleen governs the emotions dealing with resolution and responsibility. The Spleen also stores the negative emotions of worry, remorse and regret, which can create obsessions. These emotions and mental states affect the flow of Qi within the channels, as well as the patient's large muscles, lymph and saliva secretions, the mouth, lips, taste, the Stomach, digestion, concentration, the ability to memorize, and the Yi (Intention).
5. The Heart governs the emotions dealing with

shock, nervousness and excitement, as well as the final stages of healing (i.e., peace, love and forgiveness). These emotions and mental states affect the patient's energetic channel flow, as well as the patient's blood vessels and circulation, complexion, perspiration, mental and emotional activity, long term memory, Small Intestine, and the Shen (Spirit).

In the process of forgiveness, the anger and resentment are traversed to reach through to the levels of original hurt, sadness and grief. Only after reaching this level, and working through the pain, can the patient begin the process of letting go of the anger, blame, and resentments that protect them from feeling the full impact of the original trauma. Forgiveness begins only after the anger and crying ends. There are three stages of forgiveness: forgiving oneself, accepting the situation, and forgiving the abuser.

1. The forgiving oneself stage deals with the energy involved in healing oneself, and is divided into two specific stages:
   - Forgiving oneself for allowing the hurt to occur in the first place (even if the patient had no choice in being victimized), or for not fighting back strongly enough, if at all, and
   - Forgiving oneself for hanging on to all that anger and pain for so many years.
2. The accepting the situation stage deals with releasing the energetic emotional charge within the environment, or the unwanted consequences connected to the original trauma (e.g., forgiving the accident, injury, handicap, illness, trauma) within the patient.
3. The forgiving the abuser stage is the most difficult final step. Many factors can interfere with this process, such as the patient's fear of re-abuse or continued abuse if forgiveness is genuinely given. Another major factor is the negative, toxic, external energy projected by the abuser upon the patient, sometimes over many years. This energy is absorbed by the patient over time and often leads to the patient identifying with the abuser. The fear of being, or becoming, just like the abuser can be overwhelming. Anger at the abuser may seem to be the only thing standing between them; and allowing any feelings of love, compassion, or understanding may appear to be an acceptance of "evil," not only within the abuser, but within the patient's own self. An acceptance of a dark side within each of us is necessary to forgive the abuser. Often victims of abuse cannot tolerate the idea that they are anything like their abuser. Only the conscious mind, working in concert with the patient's spirit, can reintegrate this essential part of the self that has been utterly rejected and denied.

Children who have experienced abuse may be especially hard pressed to accept anger as a natural, integral part of themselves without which they cannot feel whole. They frequently view all and any anger as not only dangerous but an "evil" force. Thus, forgiveness of the abuser requires restructuring of belief systems, and the acceptance of one's own dark side, as well as the abuser's.

Through conscious intent and creative subconscious intuition, it is possible to come to an understanding that the "evil" experienced stems not from the devil, but from ignorance and pain. In most cases the abuser's intent was not to harm and destroy, but ironically, to teach and discipline for the good of the patient. The abuser did the best that he or she could at the time, given all the unresolved pain and anger within the self.

When patients experience extreme abuse, or prolonged abuse, they may lose the ability to distinguish the difference between wrong actions and the abuser. The abuser is not evil incarnate though evil deeds were done. This often leads victims to see the world only in terms of black and white with no shades or colors. The true healing requires acquiring the ability to see anew (as a little child), to reawaken to the amazing diversity of life.

These skills sometimes require teaching the patient and may necessitate referring the person out to a professional, especially if the patient suffers from a character disorder (e.g., borderline personality disorder, schizo-affective disorder, and so on).

Generally, after performing specific Qigong exercises and meditations which release the patient's pent-up, toxic emotions, the patient begins to come out of denial and awaken to genuine spontaneous emotions and feelings. This transition can be very painful at first. I usually tell the patients that this transition is similar to having their arm frozen, and then thawed out.

Imagine if the arm is placed into ice cold water, and left there. The first thing the body would feel is shock, followed by pain. As the feelings slowly begin to leave, the pain begins to diminish, and the arm becomes numb. As the mind shifts its attention away from the feelings in the arm, it begins to establish a denial system, ignoring, minimizing, or suppressing the condition in which the arm has been placed. When first removing the arm from the ice water, the tissues are still numb. After awhile, however, as the numbness begins to wear off, feelings begin to return to that particular area of the body, and pain is felt. The body is no longer in shock and is now feeling the pain and the memory of the past experience.

Our lives are the same way, in regard to physical, mental, emotional, and spiritual pain. While growing up, we are subject to constant trauma on all four levels of existence. Through an instinctive ability, we adapt and learn to become numb to our true feelings in order to survive. When we begin to awaken, we are suddenly thrust into shock, then pain, as we begin to face the source and cause of our trauma.

From a Traditional Chinese Medical perspective, pain is a means by which the body communicates its needs to the mind. In cases of chronic pain, the patient generally learns to divert awareness away from the area of pain through distracting thoughts and emotions. This helps the patient to cope with the pain, but also interferes with the healing process. If the patient reduces conscious awareness of the painful area(s) in the body, the mind/body connection becomes blocked and slows or prevents healing. The initial clarification of the "Message" regarding the disturbance can cause both a sensation of increased pain and an activation of the healing process.

By comprehending the five levels of feeling and their progressive transitions, the patient gains understanding and healing from these past traumas.

STAGES OF EMOTIONAL HISTORY AND RESOLUTION

After the patient understands the five levels of feeling and how they affect their respective organs, the Qigong doctor can assist patients in the cognitive restructuring of their disease-causing belief structures. This emotional re-patterning is initiated through the unveiling of several stages of painful emotional history, which affect the energetic healing abilities within the patient's body.

It is important for the Qigong doctor to remember that all physical matter is conscious energy activated and focused by consciousness. The patient's perceptions create the physical presence of the disease. Since all matter and energy is unified, all matter down to the smallest subatomic particle has awareness, makes choices, and communicates simultaneously with all other matter in the universe. Choices are initiated in the patient's body through the active fields of environmental and universal energy.

Understanding these subatomic communications allows the Qigong doctor to assist the patient in discharging toxic energy trapped and stored within the tissues. The experience of the emotional trauma, and its destructive emotional energetic patterning, is clinically explained and described in the following stages.

1. The patient is hurt (physically, mentally, emotionally, and/or spiritually). The patient receives the original trauma through either an aggressive, direct attack (i.e., being struck, screamed at, belittled, or shamed, etc.), or by a passive, indirect attack (i.e., being abandoned, rejected, ignored, betrayed, etc.). In this stage of development, the patient's trusting connection to life is violated.
2. The patient registers the hurt, feels the pain, and naturally expresses this trauma in an outburst of emotion (i.e., screaming, crying, laughing, groaning, etc.). In this stage the patient recognizes the wounding.
3. The patient seeks attention and looks for a

human emotional response, seeking validation and self-affirmation. In this stage, if the patient does not seek and receive attention for healing the trauma or, if the individual is not free to express his or her real feelings, healing will not take place.

4. The patient's hurt remains unresolved and becomes history. At this point in the transition it is important that the patient feel the hurt, understand the circumstances surrounding the hurt, then discharge the pain. If the patient's hurt does not become completely discharged from the body, it becomes stored within the patient's tissues. Thus, the patient's hurt becomes internalized; the emotions of unexpressed anger, fear, pain, and shame begin to accumulate in the body. The trauma remains as an active charge of unexpressed emotional energy.
5. The patient's whole body stores the distressful emotional memories. This distress gets restimulated in the present (through various trigger mechanisms), and alters or blocks the patient's flow of energy and thinking.
6. The patient learns defense mechanisms to survive. The patient develops strong defense mechanisms instead of healing from the emotional wounds (known as a pathological recovery). At this point the patient's denial system is reinforced, and kept active to protect the patient from any further hurt, in order to ensure survival and maintain at least the semblance of a normal, functional life.
7. A dynamic polarity arises that seems to take on a life of its own. The patient swings back and forth between overcontrolling emotions and loosing control over them completely. The patient becomes obsessed with the painful feelings, either hiding from them or becoming overwhelmed by them. The patient then chooses either one of two options:
   - To become isolated, emotionally removed and distant, or
   - To become needy, co-dependent and attention hungry.
8. The patient develops addictions to continually hide from the pain. The patient's actions become based on the unhealed feelings resulting in four overlapping ways to hide:
   - Physically through sports, excessive exercise, food, sleeping, etc.,
   - Mentally through compulsive behavior (e.g., studying, being a work-a-holic, compulsive book reading, etc.).
   - Emotionally through either chronic rage, grief, obsessive worrying, and chronic fear, or through a compulsive search for love, joy, and excitement (sex / love addiction), etc., and
   - Spiritually through fanaticism of various types, or extreme spirituality.
9. The patient begins to recover from the trauma. To heal and recover, the patient must cease concentrating on the pain and redirect his or her full attention towards setting healthy boundaries and positive affirmations. Some patients' boundaries are too solid and immovable (i.e., they won't allow for any meaningful interaction with others). These patients do not really need to set boundaries, they need to allow their boundaries to become more permeable. Patients' boundaries need to be flexible in order for them to be healthy. Patients must learn when to open and when to close their boundary system, and not just constantly shut everything out (people, relationships, responsibilities, etc.) or let everyone and everything in.

It is important for patients to understand that perpetrators of abuse are in a state of denial of their own shame and imperfection; thus they inflect pain and suffering onto anyone present at the time. Some perpetrators single out one family member as a recipient for their pain. Sometimes the chosen victim reminds the perpetrator of his or her younger innocent self; thus all the accumulated self-hate is projected onto this one child through no fault of the victim. The resemblance may be real (slight physical similarities for instance) or imaginary (the child's vulnerability, for example, or a singled out personality trait that triggers the abuser's anger). The one common factor among abusers is their inability to see their victims for who they really are. Abusers make no effort to know the victim, to really see the whole person; instead they see a distorting mirror which reflects their own image back to them, magnifying their own flaws and fears. Through setting boundaries and affirming their own self-worth, the patients will be able to release years of toxic emotions stored within their tissues. This can initiate health and healing on every level of their being (physical, mental, emotional, and spiritual).

ASSISTING THE PATIENT IN ESTABLISHING HEALTHY BOUNDARIES

The patient is generally informed that in order to make it through the spiritual, emotional, and mental transitions brought about by Medical Qigong therapy, it is important to establish an active but flexible boundary system. The patients are then taught to divide their relationships into three categories: True Friends, Acquaintances, and Toxic Relationships (Figure 32.2).

1. True Friends consist of people with whom the patient can share and expose his or her most intimate hidden secrets and emotional feelings, without worrying about being judged. In the presence of true friends, the patient feels emotionally accepted and loved unconditionally. The boundary system should be down, and the patient should feel completely open. It is safe to be completely vulnerable.
2. Acquaintances consist of people with whom the patients should share only limited amounts of information regarding their personal/emotional life experiences. The most hidden secrets could be judged, misconstrued, and gossiped about. All conversation with these individuals should, and must be, kept on a fairly superficial level. The patient's boundary system should be up, and the patient should monitor the conversation, as it is not safe to be totally vulnerable.
3. Toxic Relationships consist of people with whom the patient cannot and should never share any knowledge of their personal/emotional life. These individuals chronically abuse, mistreat, belittle, and attack others (whether they are members of the patient's own family, work, or neighborhood). All conversation with these individuals should be kept to a minimum. The patient's boundary system should be on full armor, and whenever possible, these individuals should be avoided.



Figure 32.2. Types of Relationships for Setting Flexible Boundaries

REJECTION, BETRAYAL, AND ABANDONMENT

From a young age, people are introduced to the multidimensional experience of being hurt (physical, mental, emotional, and spiritual). This affects the individual's center core and initiates a coping response due to feelings of rejection, betrayal, and abandonment. The normal reaction to such emotions results in experiencing emotions ranging from fear to frustration. These individuals begin to develop masks, that warp and scar their developing personality. As these individuals continue to grow, the illusions of these masks demand more Qi to sustain their form, which in turn drains vital energy from the growing body, and weakens the immune system. This denial system, fortified by the individual's emotional patterning,



Figure 32.3. The True Self is contained within the Core Self.

sustains him or her until they can heal and re-pattern the no longer beneficial belief system.

To re-pattern their belief systems, patients and Qigong practitioners must first be made aware of their initial programming patterns and the reasons for which these were created in the first place. The following "spiritual template" is applied to all patients, regardless of culture, race, or religion.

To access the patient's center core, the Qigong doctor must help the patient identify the masks which have taken on a life of their own and created the false "ego self." Next, the patient must address personal self-hate issues, which have driven the patient to develop the masks and defense mechanisms. Finally, the patient must face the foundational fear that has severed his or her connection with their "true self" contained within the center core (Figure 32.3).

In the Medical Qigong clinics in China there is a saying, "Patients must first stop running from their fears, and face the "Paper Tiger" (i.e., the illusions and fantasies that have been chasing them); in the West, it is considered "stopping and facing your internal demons."

MASKS AND DEFENSE MECHANISMS

To armor the ego, individuals resort to what Sigmund Freud labeled as "ego defense mechanisms." There are nine strategies; and with the exception of the last one listed, i.e., "sublimation," they serve to mask the core self. The nine defense mechanisms and their strategies are: Repression, Displacement, Projection, Intellectualization, Regression, Fixation, Denial, Reaction-Formation, and Sublimation.

1. Repression is the pushing down of unwanted ideas and emotions into the unconscious;
2. Displacement is the shifting of impulses aroused by one person, or situation on to a safe target;
3. Projection is the attribution of unacceptable impulses within oneself to other people;
4. Intellectualization is an elaborate rationalization of a naked impulse, to justify it;
5. Regression is the return to an earlier childhood stage of behavior to reduce the demands on the ego;
6. Fixation has the same result as Regression, but the person becomes fixated at a particular stage of mental and emotional development;
7. Denial is a conscious refusal of an impulse-evoking fact, feeling or memory;
8. Reaction-Formation is the conversion of one feeling into its opposite, typically seen in love turning into hate;
9. Sublimation is the channeling of unacceptable impulses into acceptable, refined social forms and is the only defense mechanism considered to be a healthy reaction.

The ego mediates between the "id" (i.e., the primordial survival drives and impulses) and the "super ego." The super ego consists of the ideals and conscience of the individual.

EMOTIONAL SECURITY

Each individual has basic emotional needs that must be met to feel secure. Without the comfort of these needs being met an individual will sometimes lash out and react in an antisocial behavior. This reaction is generally due to the individual fostering feelings of rejection, betrayal, and abandonment. The three personal needs required


Significance
self worth, personal value and importance
Inclusion
affirming social value
Power
control and authority to speak and act

Figure 32.4. The Three Personal Needs That Foster Emotional Security

to foster emotional security are as follows: Significance, Inclusion and Power (Figure 32.4).

1. For an individual to feel significant, he or she must be given self worth, personal value and importance. Without personal value the individual will feel insignificant, unimportant, and worthless.
2. For an individual to feel included, he or she must be given affirming social value (knowing that they play an important role in the family, relationship, or society as a whole). Without personal acknowledgment the individual feels isolated, segregated, and separated.
3. For an individual to feel powerful, he or she must be given the ability to control and the authority to speak and act. Without personal power the individual feels powerless, weak, and incapable.

In addressing the patient's disease, it is important to sometimes address his or her living and work environment, as both can contribute and influence the patient's healing potential.

HEALING EMOTIONAL TRAUMAS

There are several techniques and methods used to assist patients in healing through emotional traumas (Figure 32.5). Such meditations as Pulling out the Pain are often prescribed as homework along with other treatment methods of Medical Qigong therapy. Some of these methods used to heal emotional trauma are described as follows.

1. Medical Qigong Distance Therapy affects the body, mind and emotions. The Qigong doctor alters the patient's energetic tissues and fields to re-pattern the patient's emotional responses.
2. Medical Qigong Massage Therapy and Bodywork involves lightly touching and stimulating the patient's tissues, to release the trapped emotions so that they may be appropriately reprocessed.
3. Medical Qigong Respiration Therapy unites the body, mind, and emotions by moving the energy through specific breathing techniques. By changing the breathing pattern, the Qigong doctor changes the patient's energetic emotional patterns, releasing trapped memories deep within the patient's tissues.
4. Medical Qigong Dynamic Postural Therapy expands and stretches the patient's tissues. This active adjustment of the patient's body alignment increases the flow of Qi and Blood through his or her internal organs, facilitating an emotional release (e.g., the Dry Crying exercise).
5. Medical Qigong Imagery and Meditation Therapy uses awareness meditations and images to sedate the patient's reactive mind in order to connect with the higher self-identity. The doctor interrupts the patient's emotional


Healing Emotional Trauma
1.Medical Qigong Distance Therapy
2.Medical Qigong Massage Therapy and Bodywork
3.Medical Qigong Respiration Therapy
4.Medical Qigong Dynamic Postural Therapy
5.Medical Qigong Imagery and Meditation Therapy
6.Music and Art Therapy

Figure 32.5. Six Methods Used For Healing Emotional Trauma

thought patterns by changing the patient's sequence of sensations, word pictures and feelings. This emotional reforming changes the meaning of the patient's interpretation and challenges his or her self-limiting beliefs.

6. Music and Art Therapy are sometimes prescribed to change the patient's mood and awareness. Through playing a musical instrument, dancing, singing, or creative free-association drawings, sculptures, pottery, and so on, patients can access their Creative Subconscious Mind to repattern old belief structures and enhance the body's energy. Some patients will resist this form of therapy as they do not consider themselves to be good artists. It is vital to explain that these creative endeavors are not for the purpose of creating art, but for expressing feelings and emotions. These art forms need not be pretty, perfect, or shared with anyone if the patient does not desire to do so. They need not even be kept so long as the patient has released some feelings and emotions. The process itself is the healing. This type of therapy is used to help the patient recreate, identify, and release trapped emotions deep within the subconscious mind.

PULLING OUT THE PAIN MEDITATION

This meditation uses part of the guided imagery used in the Soul Retrieval Meditation (found in Chapter 19). It releases and transforms the patient's conscious feelings and helps to change or remove the Personal Subconscious toxic holding patterns.

After the meditation, patients should feel as if they have been cleansed and purified of toxic emotional debris. This is, however, only the first level. Patients can only release and transform the surfacing emotions one level at a time. Like peeling an onion, the patients must continue to work through each level until reaching their core issues. These core issues surround the suppressed feelings of hurt and pain.

The doctor instructs and guides patients through this meditation matching the rhythm of his or her words to the patient's exhalations. Patients draw their painful memories and traumas out of their body in the form of dark smoke; they then separate the distilled wisdom and knowledge from this dark cloud, reabsorbing the healing light into every pore and cell of their body. The dark cloud must then be released with the help of an angelic being who severs the energetic cord(s) still attaching the patients to their pain and suffering. When the patients reach this sixth step, the doctor assists them by clapping his or her hands as the patients visualize the "sword of truth", held by this holy being, severing the dark energetic cord(s). The sword of truth represents the patients' decision to regain their power by letting go of their attachment to their illness. This attachment creates very real energetic cords that bind the patients to their painful memories and toxic emotions. Severing these cords, or cord, symbolizes the end of the patients' investment in their disease, and the beginning of true healing. This releases all the pain and despair, i.e., the black cloud ascending into the Heaven into the hands of God or a "higher power," in accordance with the belief structure of the patients. As the cloud reaches the first wave of love and compassion emanating from God or a "higher power," a mighty explosion transmutes the black despair and pain into divine healing light. The doctor then assists the patients in accepting this healing, loving light back into their body to experience, perhaps for the first time in their lives, true forgiveness and a state of grace.

1. Begin by sitting comfortably in a chair, with both feet on the floor, hands resting on your thighs, eyes closed, tongue on the upper palette. Breathe naturally through the Lower Dantian.
2. Focus your attention on the Yellow Court area below the diaphragm where you store painful memories and trauma. Imagine opening up this area to release the toxic energy out of your body as a stream of dark steam releasing from a pot.
3. As the dark steam flows out of your body you are releasing feelings and memories of guilt, anger, rage, humiliation, abandonment, degradation, rejection, insecurity, and sorrow. These toxic emotions have, until now, prevented your healing through creating a deep distrust of self and others.
4. Focus your attention on this energetic cloud, and begin separating the pain and hurtful memories from the knowledge and wisdom gathered from these experiences. Visualize this knowledge and wisdom in the form of golden, white, and silver light energy gathering on the right side of the room. Continue to drain the dark cloud of misery and pain, now occupying the left side of the room, until you have extracted all the new insights from it. As you do so, you will notice the dark cloud becoming heavier and darker.
5. Focus on the right side of the room. Through your intention, begin to inhale and imagine this bright, illuminating energy flowing back into your body. Absorb this knowledge and wisdom gathered from past experiences, void of any feeling of hurt, pain, and judgement into every cell of your body. This distilled knowledge and wisdom empowers you to heal from your wounds on a physical, mental, emotional, energetic, and spiritual level.
6. Next focus your attention on the dark black cloud containing all your pain and suffering. Imagine an angelic being, righteous and holy, holding a "sword of Truth," standing by your side, ready to sever the dark energetic cord(s) still connecting your physical body to this dark cloud of despair. The sword descends and severs the cord(s) (*the doctor claps his or her hands as the sword severs the cord(s)*.
7. The cloud of darkness begins to float up, through the ceiling, through the sky into space. Far in the distance you begin to perceive God or a "higher power" emanating waves of compassion, love, and mercy descending towards the Earth. One of the waves touches the dark cloud of hurt and pain, exploding it into a brilliant light. The cloud is immediately transmuted into fluorescent crystal blue drops of light. This pure, clean energy descends from the Heavens like gentle rain. Breathe in this crystal blue healing energy, let it penetrate deeply into every pore, every tissue and cell, saturating your body completely. Feel the light cleansing and radiating throughout your being.

UNDERSTANDING WHY A PATIENT WON'T HEAL

Normally, in a clinical setting, 80% of the patients will respond favorably to Medical Qigong therapy. In some cases, complete remission of the disease is achieved. An additional 10% will improve, but stabilize in their condition, while a final 10% will not respond at all to the treatments and will progressively get worse. When the patient does not respond to the treatments, the reason can usually be related to the following conditions: Failing to Carry Out the Prescriptions, The Pathogens are Just Too Strong, and Divine Will Guides the Outcome.

- Failing to carry out the prescriptions can be caused by the patient subconsciously sabotaging the healing. Refusing to practice is usually due to deep unresolved emotional issues, e.g., feeling unworthy to heal, fear of abandonment by spouse or others, and so on.
- The pathogens are just too strong to be healed by Medical Qigong therapy alone; when an illness is long-standing, additional complementary treatments, i.e., herbs, Western medicine, or surgery may become necessary to achieve healing.
- Divine will guides the outcome in some cases. The patient's time in the physical realm may be complete, and the soul is preparing to return back to the divine.

Sometimes the healing process takes more time then expected. I explain to patients that permanent transitions can sometimes be instantaneous, but are more likely to be gradual. I explain that they are like a sea captain, standing at the helm of a great ocean liner. If the captain decides that the present course is unsafe, and destructive to the ship and its crew, he quickly orders an immediate change in the course of the ship's direction. With a flick of a switch and a hard spin of the steering wheel, the direction of the rudder is immediately changed. However, because of the perpetual inertia of the massive ship, it will take some time to observe any alteration in the course of the ship's current direction. Although the eyes of the captain can be focused on the new direction, the ship still requires enough time to effectively move in the new direction. It is the patient's spiritual intentions and focused goals that eventually direct the patient's emotional belief system, which in turn, redirects their thoughts and body's physical reactions.

Sometimes, toxic emotions and memories are released through diligent Qigong practice and treatments. With some patients, however, although major changes have already occurred in their conscious attitude, belief structure, and spirit, it may take longer for the unconscious reprogramming to take hold and stop reinforcing the old fears, and traumas. This impediment of unconscious reprogramming is due to the patient's conscious mind not being able to fully integrate the new reality and belief structure. A cancer patient may, for example, have been diligently practicing the prescriptions and the disease may now be in remission, but, the patient still visualizes the cancer as all-invasive. Rather then starting with an image of less cancer in the body, the patient continues to start the meditations with the cancer condition visualized at its worst peak. This sends a double message to the subconscious mind (heal and don't heal).

The same thing applies to observing the patient's transitions of chronically programmed patterns. New behaviors and attitudes cannot become habits overnight. It simply takes time, endurance, and constant encouragement in order to make progress. It is important for the patients to keep their eyes focused on their intended goal and not give up hope.

It is also important not to force mental imagery when feeling angry, depressed or upset. To be effective, creative visualization requires a quiescent mind and soft focus; it should not be hard work. Time allotted to creative visualization can be brief (only a couple of minutes), several times a day, for it to be effective.

FACING THE DEATH OF A PATIENT

Because human beings are created from the energies of Heaven and Earth, they are subject to the transitions of nature, death being part of that transition. Sometimes, no matter who the doctor is, or what his or her specific training has been, there is nothing that can be done to physically heal the patient. Because patients have made attachments during their stay on Earth (physical, men-



Figure 32.6. The Five Stages and Transitions of Accepting Death

tal, emotional, and spiritual), it is important for the doctor to assist them in their final transitions of releasing and letting go. The fear of death often causes patients to feel loss of control of their life, facing and conquering this fear allows them to regain a sense of control.

According to Dr. Elisabeth Kubler Ross, there are five stages of dying that facilitate closure for patients, especially in the life and death transition (denial, anger, bargaining, depression, and acceptance). These transitions also occur when facing the death and closure of any personal relationship or job, as well as the termination of one's life (Figure 32.6). Although these stages were originally believed to follow each other in an orderly fashion, further research has indicated that these stages need not, and most often do not occur one at a time. The different "stages" can occur at any time going from "denial" to "acceptance," back to "bargaining," etc., (sometimes in just a few minutes). Every individual reacts differently. Some never accept death and struggle to the very end. Medical Qigong therapy describes these transitions as follows: Shock, Numbness and Disbelief, Denial and Isolation, Anger and Rage, Bargaining, Depression, and Acceptance.

1. Shock, numbness, and disbelief occur when an individual is faced with the fact that his or her own death is near. Because of shock, the mind will generalize, rationalize, delete, or distort information to make the information acceptable to the patient's belief system. When these initial feelings of shock, numbness, or stoicism begin to disappear, most patients then experience disbelief. They can not believe or will not accept what is happening to them.

   Some patients bypass this stage all together. They feel great relief at learning of their impending death. They look forward to the cessation of pain and rejoining those close to them who have passed on.
2. Denial and isolation is the first semi-conscious choice the patient makes after hearing the news. The patients' disbelief allows them to establish their own denial system. This denial system functions as a shield to protect them, as they emerge from the shock. Denial and isolation further allows these patients time to gather additional knowledge, hoping that the original diagnosis was incorrect.
3. Anger and rage arise as the denial system breaks down. Patients experience anger, rage, envy, and resentment, as they view their terminal progress as an injustice. The patients' discomfort and anger are usually displaced and projected towards anything and everyone (usually people and God). Patterned, fear-based behaviors get stored in the body and mind. These emotions affect the patients' future perceptions, diminishing their belief system in personal survival.

4. Bargaining is the next stage in the process of adjusting to the verdict. Patients offer counterproposals (usually with God), hoping to change or alter the course of events and postpone the inevitable from happening.
5. Depression replaces hope and the patient experiences a deep sense of loss. Still resisting the outcome, patients sink into depression, sometimes lingering for quite some time before death. Depression is divided into two different categories, each one is different in nature.
   - Regretful depression is caused by guilt and shame for not having lived life to the fullest. The patients regret having given in to fears and having held on to past hurts (both real and imaginary) for so long, that many dreams were abandoned. Opportunities for healing and enjoyment were missed, and old sorrows and conflicts never resolved. Patients with this type of depression often seek to voice their regrets. Many ask to let go of the bitterness and open up to a spiritual healing, rather than a physical healing.
   - Preparatory depression is not caused by regrets, but by mourning the loss of projected future experiences. These patients are usually quiet and reflective, as they face the process of losing everything and everyone that they love.
6. Acceptance is the final stage before death. Having nowhere else to go, patients evaluate what was learned in life. They are now able to express their feelings of envy for the living and the healthy, as well as anger at those who do not have to face their fate so soon. They finally accept the inevitability of death. Depression gives way to a time of rest before the divine journey home. The patients, having faced their life's work, fears, and feelings, now have a new outlook on life and are prepared for the spiritual transition of death.

Facing death is an important transition in life and must be approached with a reverent respect for spiritual transformation. When a patient is dying it is extremely important for the doctor to accept the "higher order" or "divine will" for the patient, and not harbor a win or lose attitude. No matter what stage of transition the patients are in, they will almost always maintain some glimmer of hope, even though they may claim otherwise, to the very last moment of their life. It is the doctor's responsibility to accept and support patients to their inevitable end and not cease to treat them for reasons of personal fears, sorrows, or regrets. Listen to your patients, and allow them to release their fears. This continued support, acceptance, and encouragement for the patient allows them to die in peace and with dignity.

SUMMARY

Death is considered merely a change of residence for the patient's spirit. The ailing body is sometimes viewed as "a house with rotting walls." Once the dying body becomes unusable, it is best to abandon it, and look for another place to stay. The spirit-body is immortal and will exists forever in accordance with the will of the divine. This is why one is taught to be unattached to the physical transformations of this world and accept and embrace death as part of the natural process of existence.

Think of the transition of death as similar to that of a baby chick which is about to be hatched. Although it has lived and existed within its shell all its formative life, as the baby chick continues to develop, it has slowly begun to outgrow its place of existence. The baby chick is now becoming harshly compressed and crushed within the security of its own shell. As the little chick exhausts itself, trying to get free from what has now become its prison, it seemingly faces death. With its apparent last breaths, the little chick shatters the surrounding shell. Immediately, an intense light appears, followed by a whole new world that reveals itself in new wonderment. The baby chick is now reborn into a fresh new realm of existence, with new room to grow and the ability to experience true freedom.

Once, while in China, I was talking to Dr. Wong of the Xi Yuan Hospital, in Beijing. He made the profound statement that everyone he had ever treated had gotten healed. I have never heard such a bold statement being made by a Qigong master, or by any doctor for that matter, so I immediately began to inquire as to what his special techniques were. Dr. Wong responded, "Everyone I treat gets healed; some get healed spiritually, others emotionally, some mentally, and some physically. Not all get cured, but all do get healed. Some patients that come to me for therapy are supposed to die. It is their time of passage, and I help them accept death with dignity and honor. This is achieved by helping the patients heal their spiritual, mental and emotional wounds before they pass on. Other patients that come to me are in an active stage of energetic transition, and I help these patients to see where they've become stagnant, Excessive, or Deficient in their bodies and release their pathogenic Qi." Life is a pathway of transition and change, and so, in the field of energetic medicine, all patients are moving toward or away from healing their relationship with themselves and others.

SECTION VIII

QI EMITTING METHODS

CHAPTER 33
ENERGY EXTENSION AND QI MANIPULATION TECHNIQUES

ENERGY PROJECTION

The body's energetic constitution is a combined matrix of sound, light, heat, and electromagnetic energy. Studies on the effects of Qi projection conducted by Chinese scientists concluded that energy released by a Qigong doctor into a patient carries the properties of infrasound, electromagnetics, static electricity, infrared radiation, gamma rays, particle and wave flows, organic ion flows, and light. These properties produce the physiological changes in the patient's tissues during the Qigong treatment.

A Qigong doctor can emit energy during a treatment with or without touching the patient. The treatment with the doctor's hand moving at a distance from the patient's body is considered Qi Emission. If the doctor's hand touches the patient's body, it is considered Qi Massage, which combines both tissue manipulation and energy flow. Functionally, it is also helpful if the Qigong doctor also has a thorough grasp of the tissue manipulation skills of Chinese massage therapy (Jie Gu for bone setting, Tui Na for traumatology, and An Mo for Internal diseases and visceral manipulation), as well as acupressure and TCM theory, to ensure a highly proficient quality of treatment and to avoid misdiagnosis and erroneous treatments.

Qi is projected outside the body and travels in ripples and vibrational pulses similar to the ripples of an ocean wave. The frequency of this energy wave can be modulated into dense or dispersed resonating patterns depending on the Qigong doctor's needs.

Shen is projected outside the body as light and travels in light beam particles. This particle light extension can change in color and intensity depending on the doctor's intention. When Qi and Shen are combined, the light and wave frequencies facilitate maximum energy projection.



Figure 33.1. Palm Qi Extension

TYPES OF ENERGY EXTENSION

There are nine types of energy extension and projection skills that are divided into three categories based on the source of the projected energy. The first three are projected from the extremities: palms, fingers, and soles of feet. The next category of Qi projection originates from the three Dantians: Upper, Middle, and Lower Dantian. The third category includes Qi emission from the eyes, throat (sound resonation), and thought projection.

ENERGETIC PROJECTION FROM THE EXTREMITIES

The first three energetic projections are released from the extremities (palms, fingers, and the soles of feet) in accordance with the doctor's imagination and intention.

- Palm extension is the ability to release emitted energy through the center of the doctor's palm (Pc-8). It is considered the primary hand posture used by all Medical Qigong doctors for emitting Qi (Figure 33.1).
- Finger extension is the ability to release emitted energy through the extended fingers (usually through the index and middle fingers).

The finger extension techniques allow the Qigong doctors the ability to finely hone their energetic projections into a smaller, condensed energetic beam (Figure 33.2).

- Soles of feet extension is the ability to release energy through the bottom of the feet (Kd-1); this method is usually used to surround and envelop the treatment room as well as the patient (Figure 33.3).

ENERGETIC PROJECTION FROM THE DANTIANS

The next three energetic projections are released from the Upper, Middle, and Lower Dantians. These energetic projections are based upon the doctor's kinesthetic, empathic and intuitive abilities.

- Upper Dantian (Yin Tang) extension from the Qigong doctor's Third Eye area can be used in conjunction with the eyes for intensifying the doctor's Shen projection towards the patient.
- Middle Dantian (CV-17) extension from the Qigong doctor's Heart area can be used in conjunction with projection from the doctor's hands or throat, for vibrational resonation. This technique intensifies the emotional connection between the doctor and the patient.
- Lower Dantian (CV-6) extension from the Qigong doctor's abdominal area can be used in conjunction with Qi emission from the feet for expansion or extension of Wei Qi. This method intensifies the projected External field of Qi around the patient (Figure 33.4).

ENERGETIC THOUGHT PROJECTION OF QI AND SHEN

The last three energetic projections are released from the eyes, throat and mouth (sound resonation) and thought projection. These techniques are a form of long-distance thought projections, based upon the doctor's ability to project Qi and Shen.

- Projection from the eyes releases energy through the eyes and is generally used to increase the doctor's intention and focus of Qi (Figure 33.5).
- Sound resonation projects the voice to tonify or disperse the patient's energy through visceral resonations (Figure 33.6).



Figure 33.2. Finger Qi Extension



Figure 33.3. Extending Energy from the Soles of the Feet



Figure 33.4. Qi Extension. When treating a patient, all Three Dantians extend their energy into the patient.

- Thought projection is another way to release Qi. It is used for long distance energy therapy and is a form of transmuting Qi into Shen, which is transmuted through the Wuji into the patient's Yuan Shen (Figure 33.7).

CONTROLLING ENERGETIC PROJECTIONS

The problem with energy extension lies not in releasing life-force energy but in controlling the power and flow of its projection. If the doctor is distracted or unstable in his or her projection of energy, the doctor may induce more problems in the patient's body. Qi projection can be stabilized in two specific ways:

- First, by visualizing and projecting specific colors (blue, red, violet, etc.) with the energy extension. This causes the Qi to take on a dense and fuller projection, which facilitates the rooting and stabilizing of the energy into the patient's tissues.
- Second, by using intention to mentally focus the size and shape of the projected energy (like a laser), to intensify the Qi projection.

When treating a patient, the diseased tissue must be sufficiently energized. Inadequate energizing results in only slight improvement or a slower rate of healing; over-energizing may cause Qi congestion.

The degree of curative effect depends on the competence and versatility of the doctor, as well as the responsiveness of the patient. If the patient is not responsive, repeated stimulation and regulation of Qi is needed to raise their sensitivity.

Sometimes the patient's emotion and spirit are outside and disconnected from their body and mind. Although this is a perfect adaptation for a military environment, it is not conducive for an energetic healing environment. The patient must undergo a series of Shen Gong training sessions to retrieve their emotional spirit. This training is commonly referred to as "soul retrieval" because the patient's soul is in a state of shock (or suspended animation) due to severe emotional trauma, and must be returned to its Yuan Jing within the patient's tissues. (See Chapter 19).



Figure 33.5. Energy Projection from the Eyes



Figure 33.6. Sound Resonation Projection



Figure 33.7. Thought Projection

In addition to Shen Gong training, the Qigong doctor must make the patient's Qigong meditations and prescriptions more active so that a satisfactory effect can be achieved. However, a desirable effect can only be attained when the patient is cooperative with the doctor and is consistent with the assigned homework.

HAND POSTURES FOR QI EMISSION

There are many hand postures used in emitting and drawing in energy. Each variation depends on the skill and particular background of the doctor. Generally the doctor uses the entire hand to extend energy, constantly changing the intensity of the Qi being extended. By expanding and contracting the hand and fingers, the "beam of Qi" being emitted into the patient's body will expand and contract. Presented here are six hand postures most preferred by myself and many other Medical Qigong doctors in clinics throughout China.

THE EXTENDED FAN PALM

This first hand posture is the most popular in terms of Qi emission. It releases the widest field of Qi emission. In the Extended Fan Palm hand posture, all five fingers stretch naturally, separate, and open like a Chinese fan (Figure 33.8). There should be no tension, and the focus of the energy should be in the center of the palm (Pc-8). This Extended Fan Palm is the primary hand posture for extending energy because it can be easily used for emitting either Hot or Cold energy. It can also be used in conjunction with other techniques as a reinforcing method to strengthen the flow of energy extension.

Note: Before beginning these exercises, it is important not to eat a heavy meal (at least one and a half hours before practicing).

PALM BREATHING ENERGY EXERCISE—STAGE 1

1. From a Wuji posture, bring both hands up in front of the body, with the palms facing the Lower Dantian. Breathe naturally while concentrating on the Lower Dantian. Next, place



Figure 33.8. The Extended Fan. This palm is the primary hand posture used for emitting Qi.



Figure 33.9. The Image of Holding a Ball of Energy

the left palm facing the right palm, as if holding an imaginary ball. Allow the energy between both hands to build and increase its energetic field (Figure 33.9).

2. Press the Mingmen backwards and feel the energy absorbing through the arms into the Lower Dantian. Next, release the pressure from the Mingmen and feel the Qi return back into the center of the palms.
3. Shift the attention to the center of the right palm, and begin to extend energy into the center of the left palm. Next, shift the attention from the center of the right palm, and begin extending energy into the center of the left palm.
4. As a feeling of pressure begins to build between the hands, perform the "Pushing" (energy extension) and "Pulling" (energy retraction) manipulation technique. This technique is practiced by pushing the Qi of the right palm into the center of the left palm. Hold it there, feeling the pressure mount, then withdraw the Qi back into the center of the right palm. Repeat for several minutes, then move to step five.
5. After several minutes switch the mind's focus to the opposite hand and perform the exercise again. Do this exercise twice a day for 15-30 minutes each practice. Be careful not to let the hands touch when running the energy back and forth between the palms. After 100 days go to Stage #2.

When training to increase their own energetic field, the Qigong doctors must strive to overcome the Pituitary Pain Syndrome. This is a state of transition during which the body is overcome by pain to the extent that the mind gives up and the doctor quits practicing (e.g., feeling fatigue when practicing a Holding the Ball posture). It is important that as the doctor become stronger, the training posture be maintained longer, so that the pituitary gland is challenged to activate the hypothalamus. The hypothalamus causes the body to produce endorphins such as ACTH, which is a natural form of cortisone that helps to escalate the doctor's healing potential. This physical reaction is similar to a runner who must overcome physical cramping when racing to obtain a second wind.



Figure 33.10. Posture for Palm Breathing Exercise

PALM BREATHING ENERGY EXERCISE—STAGE 2

1. Light a candle and place it on a table. From a Wuji posture place the center of the right palm several inches to the right of the tip of the flame (Figure 33.10). The left palm should be placed on the opposite side of the candle, facing the right palm. The Laogong points and the tip of the candle should be in a straight line with each other.
2. Breathe naturally while concentrating on the Lower Dantian. Shift the attention onto the center of the right palm, and begin extending energy into the center of the left palm.
3. Once a feeling of pressure begins to build between the palms, begin the Pushing and Pulling energy manipulation technique. Push the Qi of the right palm into the left palm. Hold it there for several minutes, feeling the pressure mount, then draw the Qi back into the center of the right palm. Practice this exercise for several minutes.
4. Next place the left palm on the Lower Dantian while continuing to extend and retract energy from the right palm. After several minutes, switch hands. Notice that as the Qi is being extended out of the palm that the flame bends away, and as the Qi is retracted back

into the palm the flame bends towards the center of the palm. Practice this exercise twice a day for 15-30 minutes each time.

Note that the Yin Tang area (the Upper Dantian's projection point) can grasp the flame and hold it stationary. Since this technique (grasping and rooting) is used for rooting and securing the patient's Qi, its application can be counter productive when trying to move the flame tip. To avoid this condition, the doctor should relax the mind and use the imagination when projecting Qi.

THE SWORD FINGERS

In this second hand posture, the expansive field of Qi being released is reduced and condensed into a more solid beam of light. In the Sword Fingers hand posture, the index and middle fingers of the right hand are extended and joined together, the ring and little fingers curl into the center of the palm (Figure 33.11). The thumb should rest on the nails of the ring and little fingers forming a circle where Qi is gathered.

The index finger indicates Wood or Liver's Qi, and the middle finger indicates Fire or the Heart's Qi. Together, both fingers activate the Qi of Fire and Wood, which is a catalyst for the Yang energy needed for guiding Yang Heat with the intention (Yi). When extending energy, the Qi is gathered first in the palm and the circle between the thumb and last two fingers, then it is released through the tips of the index and middle fingers.

SWORD FINGER QI EXTENSION—STAGE 1

1. From a Wuji posture, extend both hands to form an imaginary circle of energy in front of the Lower Dantian. As soon as the Dantian is activated and full, bring the ball of energy in front of the body, level with the Middle Dantian (Heart / solar plexus level). Direct the Qi from the Lower Dantian into both hands (Figure 33.12).
2. Point the middle and index fingers of the right hand towards the left palm (Pc-8) and feel the energy press into the tissues (Figure 33.13). After a while, neutralize the energy by turning the palms towards each other, then switch and feel the energy of the left sword fingers



Figure 33.11. The Sword Fingers Technique



Figure 33.12. Imagine a ball of energy in front of the Lower Dantian, then raise it up to the level of the Middle Dantian.



Figure 33.13. Point the Sword Fingers of the right hand towards the center of the left hand.

(index and middle finger) press into the center of the right palm. Practice this exercise twice a day for 15-30 minutes each practice. After 100 days go to the next stage.

SWORD FINGER QI EXTENSION—STAGE 2

1. Light a stick of incense and place it in a standing upright position on a table. From a Wuji posture, place the center of the left palm (Pc-8) several inches to the left of the incense. The right hand sword fingers point through the tip of the incense, extending Qi into the center of the left palm. All three points - left center palm (Pc-8), tip of the incense, and the right sword fingers - should be in a straight line (Figure 33.14).
2. Breathe naturally while concentrating on the Lower Dantian. Shift your attention onto the tip of the incense and focus your concentration there. Continue to extend Qi until you have a strong feeling of Qi in the center of your left palm. After a while switch to the right palm. Practice this exercise twice a day for 15-30 minutes each time.

THE ONE FINGER SKILL

In this third hand posture, the field of Qi being released is further condensed into an more solid beam of light. In the One Finger Skill hand posture, the hand forms a soft fist with one appendage (finger or thumb) extended (Figure 33.15). The energy is projected in a straight line (like a laser beam) and can be used to Heat the patient's tissues, channels, or points, as well as to lead, extend, and tonify the energetic field (Figure 33.16).

One Finger Skill can be used to extend long range energy into the patient's channels, or for tissue and channel point regulation. The former technique is regarded as an internal application, and the later technique is regarded as an external application.

- The external application requires that the doctor make physical contact with the patient's tissues, extending the mind deep into the specific areas, channels, or points to be treated. The Qigong doctor physically rotates and shakes a specific finger (or thumb) from side



Figure 33.14. The Sword Fingers point at the tip of the lit incense.



Figure 33.15. The use of the finger or thumb to emit Qi is an example of the One Finger Skill technique.



Figure 33.16. Energy is extended through the One Finger Skill technique.

to side while emitting Qi into the patient's tissues or energetic fields (Figure 33.17).

- The internal application requires that the Qigong doctor extend his or her arm, pointing a specific finger at a particular area on the patient's body. The doctor then focuses on that specific channel point, leading and directing the emitted Qi into or out of the patient's body.

ONE FINGER SKILL ENERGY EXTENSION EXERCISE

1. From a Wuji posture, focus the concentration on the Lower Dantian area and bring both arms up to chest level and form an energy ball. Once the Qi in the Lower Dantian becomes activated, direct its energy flow to the tip of the right index finger. Once a feeling of heat and expansion of energy is felt within the right index finger, point the energy beam into the heart of the left palm (Figure 33.18).
2. Once the energy is felt pressing into the left palm, begin to circle-rotate the energy beam in a clockwise direction for several minutes, then in a counterclockwise direction for several minutes.
3. Next, extend and focus the Qi from the Dantian into the left index finger, and repeat the exercise.

SOARING DRAGON TECHNIQUE

The Soaring Dragon technique is a variation of the One Finger Skill energy extension technique. If the pathogens are strong and too much Heat is being emitted from the patient's tissues (as in certain types of cancer), the Qigong doctor may decide to use this particular variation to avoid absorbing the dangerous toxins being released from the patient's body. The Qi is emitted out the doctor's middle finger into the patient's body while the other four fingers disperse the pathogenic Heat into the ground (Figure 33.19).

Before initiating the Soaring Dragon technique, it is important for the Qigong doctor to use his or her mind's intention to seal the wrist. This enables the doctor to pull the patient's Qi into the palm and to disperse it into the Earth via the other four fingers, while avoiding the absorption of the patient's pathogenic Qi.



Figure 33.17. The doctor makes contact with the patient's tissues, extending his or her intention along the patient's channels, leading the Toxic Qi out her body.



Figure 33.18. One Finger Skill Energy Extension Exercise



Figure 33.19. Soaring Dragon Hand Posture Technique

I have found this technique very effective in my personal practice. As the pathogenic Heat from the patient's tissues releases upward, the dispersing energy that flows from the four fingers cause the patient's toxic Heat to dissipate and be carried away from the doctor.

BELLOWS PALM TECHNIQUE

Another variation of the One Finger Skill is the Bellows Palms technique, which uses the Lao Gong Pc-8 point at the center of the palm as a pump, to expel Qi out the middle finger. Originally, while treating patients, the palm is Hot (in a Yang state). However, when pulling Qi from the center of the palm and directing it out the middle finger, the polarity of the palm changes from Yang to Yin, causing the center of the palm and the middle finger to turn white (Figure 33.20).

Because this technique is used to pull out Heat from the patient's body, before initiating the Bellows Palm it is important for the Qigong doctor to use his or her mind's intention to seal the wrist. The doctor then pulls the patient's Qi into the palm and disperses it into the Earth via his or her middle finger to avoid absorbing any of the patient's pathogenic Qi (Figure 33.21).

THE BACK BRIDGE BAR TECHNIQUE

The Bellows Palm technique is also used with the "back bridge bar" (where the trapezius muscles join both arms across the doctor's shoulders) to aspirate toxic energy from the patient's body. In this particular technique, the doctor's left palm is used as a vacuum to aspirate a specific area inside the patient's body. The toxic energy travels through the doctor's left arm, across the shoulders and back (never the front), and out through the right palm into the Earth. The right palm applies the "bellows" technique used to create the energetic suction applied by the left palm, for removing Toxic Qi. This technique is contraindicated when treating cancer patients.

THE INVISIBLE NEEDLE PALM

In this fourth hand posture, the field of Qi being released is further condensed into an intense beam of light, similar to that of a laser beam (Figure 33.22). In the Invisible Needle Palm hand posture,



Figure 33.20. When using the Bellows Palm technique, the center of the palm and middle finger remain white in color, while the rest of the palm remains red.



Figure 33.21. Absorb the patient's Toxic Qi from the middle of the palm and disperse the pathogens out the middle finger into the Earth.



Figure 33.22. The Invisible Needle Palm

three fingers on the right hand are curled into the center of the palm with the thumb resting against the tip of the index finger (see Chapter 35 for Invisible Needle Theory and Application).

THE DRAGON'S MOUTH PALM

This hand posture is sometimes also called the Duck's Bill Palm, and is used to pull energy (like pulling a silk thread). The thumb and all four fingers perform the action of "pulling the golden thread" in order to lead or pull energy along and through the body's channels and points. The intensity of the Qi and movement between the thumb and fingers is determined by the relaxed movements of the wrist and finger joints. This hand technique is often used to purge energy away from specific points when treating areas of Excess (Figure 33.23).


Figure 33.23. The Dragon's Mouth Palm

THE KNEADING TIGER PALM

In this hand posture, all five fingers naturally curl as if embracing a ball. The wrist action is very fluid and supple, allowing the fingers to expand open like the Extended Fan Palm, and then gently close as if kneading a cotton ball. The entire action should be similar to a jellyfish moving in the ocean. This is an excellent technique for pulling, shaking, and rotating energy (Figure 33.24).


Figure 33.24. The Kneading Tiger Palm

KNEADING TIGER TECHNIQUE

This hand posture is used for dispersing stagnations and dissolving energy blocks. Once the doctor has selected the proper hand posture and the area to be treated, the doctor places his or her hands and fingers above the patient's body, performing a circular kneading action (slightly opening and closing the palm) while simultaneously extending energy into the patient's body. The spiraling energetic frequency should be synchronized with the doctor's hand kneading and the patient's pulse and respiration. Both the pressure and the strength of energy extended into the patient are determined according to the severity of the illness. The Tiger Kneading technique is used for extending energy into energetic points of the chest, abdomen, and extremities to purge Qi stagnation and improve energetic circulation.


Figure 33.25. The Five Thunder Finger Palm



Figure 33.26. The Five Thunder Fingers. This technique is used primarly to destroy cysts, tumors and pathogens.

THE FIVE THUNDER FINGERS

This hand posture is one of the most popular techniques used for dispersing stagnations, dissolving energy blocks and treating tumors and cysts. In the Five Thunder Fingers hand posture, all four fingers curl into the center of the palm with the thumb resting against the nail of each finger. Keep the center of the palm hollow. Qi is gathered and collected there upon inhalation (Figure 33.25).

When emitting or extending Qi, the doctor exhales while suddenly stretching the palm open like "a tiger exposing its claws." After extending the energy, the doctor inhales and resumes the Five Thunder Fingers posture while gathering Qi back into the center of the palm (Figure 33.26).

Note: Because it builds up the doctor's guiding and gathering skill, this is an important technique and should be practiced consistently.

QI BLAST EXERCISE

From a Wuji posture, raise both palms upward to shoulder level. Both hands form the Five Thunder Fingers posture. Concentrate on the Lower Dantian when inhaling. Imagine drawing the Qi up through the chest, gathering the energy into both palms as the arms raise upward. Upon exhalation, sink the body's weight, and suddenly stretch out the fingers (like a claw) at chest level, striking the air. This action should look like each hand is heaving a rubber ball. Perform this exercise once or twice a day, using 24 or 48 breaths each practice time.

CHAPTER 34

QI EXTENSION, GUIDANCE, AND REGULATION TECHNIQUES

Qi extension is most effective in activating and balancing the patient's flow of Qi, since both the doctor and patient are enveloped in a strong field of Wei Qi. In Qigong massage the patient's channels are more easily dredged and their Yin and Yang energy are often adjusted much more quickly because of the stimulation produced by the doctor's hand on the patient's channels and points.

Therefore, both modalities - Qigong massage and Qi extension - are usually combined to provide the most effective and efficient means of energetic therapy.

QI EXTENSION TECHNIQUES

The clinical guiding and directing of Qi is performed by extending energy outside of the doctor's body. The energy follows the dictates of the doctor's mind as to the pattern, amount, and direction in which to flow. Qi is emitted in three basic formats: linear, circular/spiral, and stationary flows of energy. The combination of these three forms insures that the patient is receiving the maximum benefit from the treatments, and may be combined with Hot and Cold energy extension, the Five Elemental energy extension, as well as with Qigong massage. These following exercises lay a foundation for guiding and directing the patient's Qi within the channels, points, and Wei Qi fields.

GUIDING THE LINEAR FLOW OF ENERGY

This method refers to a straight line of energy being emitted either between both hands or between one of the doctor's hands (usually the right) and a certain point or area on the patient's body. This is the primary Qi guiding method used in Medical Qigong therapy to sweep over the patient's body in a straight line in the direction of the outgoing flow of energy.



Figure 34.1. An example of a Qigong doctor using the Pushing Energy technique in a Straight Linear energy flow

Because patients vary in their sensitivity to transverse energy wave flow, the doctor should be aware of the influence of the different wave patterns affecting the patient during treatment. Linear energy is relatively mild and often gives the patient a sensation of constriction, of heat or cold, or of heaviness, pressing, tugging, tingling, or pulling. This is the basic means of inducing the channel Qi to purge Excess and to supplement any Deficiencies. Energy is directed within the body through either pushing, pulling, or leading the patient's Qi.

PUSHING ENERGY

Pushing energy is initiated by first extending energy over the surface area of the patient's body (Figure 34.1). Once the doctor has selected the appropriate hand posture above the patient (between 4 inches to 3.5 feet from the channel point or area), he or she will decide whether to push the energy in a linear or circular fashion.

Using intention, the Qigong doctor gently extends energy to the desired area and begins treatment. Pushing energy is an essential energetic



Figure 34.2. An example of a Qigong doctor using the Pulling Energy technique in a Straight Linear energy flow



Figure 34.3. An example of a Qigong doctor using the Leading Energy technique (with the left hand) while Pulling Toxic Energy (with the right hand) from the patient's body

manipulation used to open up the points to activate or replenish the body's Qi. The patient feels pressure from the doctor's Qi, and may experience heat, tingling, condensation, expansion, swelling, or heaviness.

Sometimes when the doctor uses the pushing energy technique, the patient may spontaneously lift the stimulated body area towards the hand of the doctor. This spontaneous reaction enables the doctor to implement a combination of manipulation therapies such as push-pull, push-pull-rotate (spiral), push-pull-shake, etc.

PULLING ENERGY

Pulling energy is initiated first by extending energy over the surface area of the patient's body. After selecting the appropriate hand position, the doctor chooses to either pull the energy in a straight line or spiral it along the channels.

Using intention, the Qigong doctor usually begins to pull the patient's toxic energy along the channels while extending clean energy to the affected area (Figure 34.2). Pulling energy is an essential energetic manipulation used for dredging and expelling pathogenic factors from the patient's body, and can also be used to open up channel points to activate or replenish the patient's Qi.

During treatment the doctor actually feels the pathogenic factors being pulled out of the patient's body. This causes the patient to feel heavy, tingling, dryness, heat, cold, or chills. When combining multiple manipulation methods, the pushing and pulling actions cause the energy inside and outside of the patient's body to flow into each other, opening up the patient's channel points.

The combination of pulling and shaking techniques promotes the flow of the patient's Qi, and induces spontaneous reactions of the tissue's energetic fields.

LEADING ENERGY

Leading energy is initiated first by extending energy over the surface area of the patient's body. After selecting the appropriate hand posture, the doctor extends energy towards the affected area and begins to lead the patient's channel Qi up, down, left, right, with, or against the flow of the body's channels (Figure 34.3).

The Qigong doctor bases the decision of whether or not to lead the patient's energy (and which technique should be used) upon the patient's condition and severity of the illness. This manipulation technique is used for guiding the circulation of channel Qi, regulating any Excess or Deficiency of Yin and Yang energy and to transfer Qi back to its origin. Once the channel Qi and point Qi have been stimulated, it is important that the doctor immediately use the "leading energy" technique to guide the patient's energy in as smooth a transition as possible.

CIRCULATING THE QI IN A CIRCLING PATTERN

Emitting a flow of energy in a circling pattern is used to move and circulate stagnant Qi. The flow of energy can be moved in a continuous pattern with or against the channel flow, and is used to regulate the patient's channel and organ Qi (Figure 34.4).

This method refers to techniques of rotating Qi in a circle pattern inside the patient's body. When using circling energy, the doctor extends Qi into the patient's body and implements the circle technique with the right (Yang) hand, while rooting and discharging the patient's toxic Qi with the left (Yin) hand, which points to the Earth. There are many variations of this technique and the doctor must become familiar with each modality of healing and its potential for treating the patient.

ENERGETIC CIRCULAR PATTERNS

The following patterns are specific templates used for circulating the body's internal and external Qi. Each pattern has an advantage over the others when used for the regulation of Yin and Yang disharmony. The depth of energetic penetration will vary in accordance with the doctor's intention. Each pattern's movement will utilize the ring of energy that surrounds the center of each Dantian (Figure 34.5).



Figure 34.4. An example of a Qigong doctor using the Circling Energy technique to regulate the Heart Fire and Kidney Water, through the Microcosmic Orbit

1. **The Eternity Pattern** is used for balancing the energy between the Lower Dantian and the Middle Dantian. The doctor moves the energy in a figure "8" pattern, Guiding and Leading the Qi from the Lower Dantian


Throat
Middle Dantian
Yellow Court
Lower Dantian
Huiyin
Eternity Pattern
Baihui
Upper Dantian
Throat
Middle Dantian
Yellow Court
Lower Dantian
Huiyin
Train of Pearls Pattern
Upper Dantian
Taiji Pole
Front of Body (CV)
Back of Body (GV)
Lower Dantian
Microcosmic Orbit Pattern
Middle Dantian
Right Side of Body
Left Side of Body
Lower Dantian
Yin and Yang Pattern

Figure 34.5. A Qigong Doctor Using Circling Energy

(through the Yellow Court) to the Middle Dantian, and back again. The doctor continues this pattern until the patient's energy is regulated. If the patients are suffering from an Excess Yang condition in the upper part of the body, and a Deficient Yin condition in the lower part of the body, the doctor must regulate this condition by using the Eternity Pattern of Qi regulation.

2. **The Train of Pearls Pattern** is used for balancing the energy between all three Dantians. The doctor moves the energy from the Lower Dantian (through the Yellow Court) to the Middle Dantian (through the throat), and into the Upper Dantian, then back down again. The Qi is swept up and down the entire torso, combining and regulating the energies of the patient's Wei Qi, Channel Qi and Organ Qi. The doctor continues this pattern until the patient's energy feels regulated. If the patients are energetically disconnected from the upper and lower parts of their body due to emotional congestion and energetic stagnation in the throat and Yellow Court areas, the doctor reconnects these areas by using the Train of Pearls Pattern of Qi regulation.

3. **The Microcosmic Orbit Pattern** is used for balancing the energy between the Three Dantians, Taiji Pole, the Heart's Fire and the Kidneys' Water. The doctor moves the energy from the Lower Dantian (Mingmen area) to the Middle Dantian (Shendao Area), then back down again, completing the Fire Cycle of the Microcosmic Orbit. The doctor continues this pattern until the patient's energy is regulated. The Microcosmic Orbit Pattern is used for the complete regulation of the body's Yin and Yang energy, naturally purging, tonifying, and regulating any Excess or Deficient condition along the Governing and Conception Vessels.

4. **The Yin and Yang Pattern** is used for balancing the energy between the right and the left sides of the body. The doctor moves the energy in a horizontal figure "8" pattern, Guiding and Leading the Qi through the left and right quadrants of the patient's body. In cases of paralysis after a stroke, for example, the doctor regulates the Qi of the patient's left and right quadrants and energetically balance these areas by using the Yin and Yang Pattern of Qi regulation.



Figure 34.6. An example of a Qigong doctor moving the incense smoke, using the image of an energy ball

The Qigong doctor selects the appropriate energetic pattern according to the patient's condition.

ENERGY BALL ROTATION FOR DEVELOPING CIRCLE ENERGY FLOW

- Light a stick of incense and stand it on a table. From a Wuji posture, place the center of both palms on opposite sides of the tip of the incense. All three points, the tip of the incense, and the heart of each palm (Pc-8), should form a triangle (a tree or flower can be substituted for the incense).
- Breathe naturally while focusing on the Lower Dantian. Slowly shift the attention to lead the energy into the center of each palm to form a ball of energy (basketball size). Concentrate and

imagine the ball condensing to form a powerfully compacted ball of energy (about the size of a marble). Next, imagine a circle or rounded triangle between both palms and the tip of incense. Exhale lightly while extending the energy ball toward the tip of the incense. Imagine the ball of energy moving counterclockwise from the right palm to the incense and then to the left palm, moving in a circle. The right hand pushes while the left hand pulls. The incense smoke should move in accordance with the Qi movement. After a while reverse the flow of the circle. Practice this exercise twice a day for 15-30 minutes each time (Figure 34.6).

SPIRALING ENERGY FLOW

A spiraling flow of energy moves the energy in a spiral pattern (clockwise or counterclockwise) to drill the energy deep inside the patient's body (Figure 34.7). This "drilling" action, caused by the spiraling energy, allows for deeper penetration and is excellent for breaking up stagnations when combined with the Kneading Tiger Palm or the Five Thunder Fingers techniques.

Spiraling energy can also be used in the clinic to regulate the patient's Qi activities. Patients may feel the energy penetrating deep into their body and experience light, sound, and mild electric shock. When patients are lying supine, the doctor may choose to spiral the energy superior to the internal organs to pull toxic Qi out of the tissues of the organ; or the doctor may spiral the energy inferior to the internal organs to push the Qi back into the tissues of the organs (Figure 34.8).

Spiraling energy is an essential energetic manipulation used for activating the channel Qi, guiding the energy to spiral in, up, or down, much like a cyclone. The Qigong doctor chooses to use either the circle or spiral energy flow, based upon the patient's condition. Most often these two energetic flows are combined to achieve a more functional treatment. The Qigong doctor will, for example, use "spiraling" energy to drill deep into the body to access the toxic energy stored deep inside the patient's organs. Once the patient's toxic Qi has been reached, the doctor utilizes purging techniques to remove the energetic debris. After purging the doctor can circulate the patient's energy to move the stagnant Qi out of the organs. This may be followed by the Microcosmic Orbit to regulate the patient's energy.



Figure 34.7. A Qigong doctor using the Spiraling Energy technique, to purge Toxic Qi from the patient's body



Figure 34.8. A Qigong doctor Spiraling the Qi in order to penetrate the patient's tissues

CLOCKWISE AND COUNTERCLOCKWISE ENERGY FLOW

The doctor focuses on sensing and creating an internal energy vortex within the Lower Dantian that moves up the body in a clockwise or counterclockwise spiral pattern. Only then is the spiraling Qi projected out through the doctor's right hand into the patient's body.

Using the appropriate hand position, the doctor slowly spirals the energy in either a clockwise direction to guide the patient's energy into the affected area, or in a counterclockwise direction



On Yang Channels

As Yang Qi travels down the body, reinforce the patient's descending channel with a clockwise rotation along the flow of energy.

Reduce the energy with a counterclockwise rotation against the flow of the descending Yang channel.

On Yin Channels

As Yin Qi travels up the body, reduce the energy flow in the patient's ascending channel with a clockwise rotation against the flow of energy.

Reinforce the energy with a counterclockwise rotation against the flow of the ascending Yin channel.

Figure 34.9. The reinforcing and reducing techniques of moving energy along the patient's channels is determined by the direction of the Spiraling Energy flow.

to remove the patient's Toxic Qi out of the diseased area.

- The counterclockwise rotation is considered Yin and is used to reduce Heat and to cool the patient. It is generally used to purge conditions of Excess (think of unscrewing the pathogens from the diseased area when purging).
- The clockwise rotation is considered Yang and is used to increase energy and warm the patient. Generally, it is used to tonify conditions of Deficiency (think of drilling and filling the Deficient area when tonifying).

The clockwise spiraling energy originating in the Lower Dantian is emitted and synchronized with the doctor's circling hand movements to reinforce the patient's Qi. To reduce the flow of the channel's Qi, the counterclockwise spiraling technique is used (Figure 34.9).

The Qigong doctor must cultivate these movements into a conditioned reflex before applying these treatment methods in a clinical environment.

SPIRALING ENERGY EXERCISE

- From a Wuji posture, place the left palm on the Lower Dantian. Slowly extend the right palm (keep elbow bent) in front of the chest, aligned with the center line at the Middle Dantian (CV-17), palm facing outward.
- Breathe naturally, while focusing on the Lower Dantian. With the mind's intention, begin to spiral the Qi in the Lower Dantian in a clockwise circle. Lead the energy up through the chest and out the extended right palm. Make sure that the spiraling of the Lower Dantian is synchronized with that of the right palm, making the inner Lao Gong Pc-8 points the center of concentration (Figure 34.10). Start off slowly, and gradually increase speed. The energy circle spirals outward with increasing or decreasing radius, depending upon the doctor's intent.

Repeat the exercise, only this time use counterclockwise spiraling.

ENERGETIC CUPPING

One popular clinical technique called "energetic cupping" is initiated by creating an energetic vortex which remains on the patient, pulling or drawing in energy, similar to that of an acupuncturist's cupping method. These energetic vortices can be used to drain or purge pathogens from a specific point or area on the patient's body. These energetic vortices can also be used to fill or tonify the patient's body. For example, when the patient is prone, the Qigong doctor can stimulate points LI-15, GV-4, and GV-14 (Figure 34.11). Then, using his or her intention, the doctor can pull with one hand while the other hand pushes, increasing the spiraling action already set in motion. This initiated energetic torque can sometimes cause the patient's body to turn, twist, bend, and sway. This modality of treatment simultaneously activates the patient's channel Qi, regulates the Yin and Yang organs, and balances the patient's Yin and Yang energies.

The doctor is advised to rely on intuition or divine guidance in choosing the right method, after careful consideration of the patient's condition (age, sex, personality, illness, etc.).

Note: If combined with the "shaking" technique, the circle/spiraling energy becomes especially effective for relieving pain.

GUIDING THE STATIONARY FLOW OF ENERGY

Stationary energy is emitted from a non-mobile position and can be used to stimulate the channel Qi, points, and Dantians, while restoring and replenishing the patient's Qi. After selecting the appropriate hand posture, the doctor positions his or her hand above the area being treated and emits energy from a fixed or stationary position. This is the most common energy projection technique, in which Qi flows like dense waves or is spaced like a chain of moving pearls flowing outward one after another (Figure 34.12). The patient often feels the sensation of vibration, tingling, or heat. It is not uncommon for the patient to develop spontaneous involuntary reactions such as full body spasms or shaking, leg jerking, etc.

Stationary energy is emitted from a station-



Figure 34.10. An example of a Qigong doctor practicing the Spiraling Energy exercise



Figure 34.11. An example of a Qigong doctor performing multiple point stimulation with the Energetic Cupping Technique



Figure 34.12. When a Qigong doctor extends energy from a stationary position, the Qi flows either like a dense wave, or is spaced like a chain of moving pearls.



Figure 34.13. An example of a Qigong doctor using the Shaking Energy technique along with the Kneading Tiger Palm



Figure 34.14. An example of a Qigong doctor using Vibrating Energy through the Extended Fan Palm technique

ary palm position. There are two main energetic pulsations utilized in the Stationary Palm techniques: Shaking Energy technique and Vibrating Energy technique.

SHAKING ENERGY TECHNIQUE

The Shaking Energy technique is initiated by the doctor first extending his or her energy over the surface area of the patient's body. After using the Tiger Kneading Palm technique to grasp the Turbid Qi, the doctor slowly begins to guide the patient's Qi out of the tissue area with a stationary manipulation. The doctor then shakes his or her hand from side to side, while continuing to pull the Qi from the area being treated (Figure 34.13).

To practice this particular skill, the Qigong doctor begins from a Wuji posture, using natural and slow breathing. The doctor imagines the waist as the axis and the abdomen as a pump and vibrates the Qi inside his or her Lower Dantian. The doctor then allows the energy to flow upward and out the palm, into the patient. It is important for the doctor to use the mind's intent to follow, guide, and direct this vibration of energy flow, instead of forcing the muscles and palm to shake.

VIBRATING ENERGY TECHNIQUE

Vibrational trembling is one way that memory is stored or processed in the physical body. The Qigong doctor's vibration penetrates the patient's field of "vibrational activity" (the body's natural vibrational rhythm), awakening this memory, allowing the patient to release trapped thoughts and emotions (Figure 34.14).

Qi naturally oscillates and vibrates in the doctor's Three Dantians, each Dantian vibrating at its own unique frequency pattern. The body's bone structure is built with natural formations similar to that of "tuning forks," positioned in both the arms and the legs. These tuning forks are connected together through the body's spinal column and are used to vibrate and increase the body's energetic resonance. Through a balanced interplay of stretching and releasing the body's tendon, ligament, and muscle fibers (in a rhythmic pattern), a natural vibration is produced. After some time of training (through naturally twisting and stretching the tendons), the Qigong doctor, using proper hand postures and intention, is able to direct and lead this vibration throughout his or her entire torso and extend it outwards through the hands.

Vibration is released through three forms of resonation:

1. Jing vibrational resonance is felt within the patient's external tissues and bones. It is related to the energetic release of Heat and the energy of the doctor's Lower Dantian.
2. Qi vibrational resonance is felt deep within the patient's internal organs. It is related to the energetic release of the patient's emotions and the energy of the doctor's Middle Dantian.
3. Shen vibrational resonance is felt within the patient's center core. It is related to the ener-

getic release of the patient's spirit and the energy of the doctor's Upper Dantian.

The release of energetic vibration is primarily used to activate the patient's channel Qi. Clinically, it is most effective when the frequency of the doctor's hand vibrations matches and synchronizes with the vibrational frequency of the patient.

While treating the patient, the doctor's palm usually gets hot and vibrates when coming in contact with Qi stagnation. If a patient's channel point becomes blocked, energy builds up causes Qi stagnation. Once the Qi stagnation is removed, the doctor's hands will cease to vibrate as the channels open and flow freely. When cleared, the patient feels fatigue as the toxins are released from the body and the energy seeks to balance itself.

To apply the Vibrating Technique, the doctor selects the proper hand posture and the area to be treated, then barely touches the patient's body. Any firm pressure should be avoided so as not to hinder the extending and directing of Qi. The doctor initiates the vibrational extension of Qi from the Lower Dantian, slowly turning clockwise or counterclockwise, while directing the vibration out through the hands. The doctor focuses on his or her own breath to adjust the frequency and amplitude of the vibration, the shape and nature of the emitted Qi (Yin or Yang, etc.), and the strength of the energy.

Some examples of hand postures and tissue regulation techniques for emitting vibrational energy include:

a. The Extended Fan Palm is used for activating and regulating Qi activities by:
   - Vibrating the Extended Fan Palm on the Baihui GV-20 point, to descend the patient's Yang Qi, tranquilize the patient's mind, regulate Qi in the Upper Burner, and induce sleep;
   - Vibrating the Zhong Wan CV-12 point to replenished the patient's Qi, to regulate the Stomach's energy and to induce sleep;
   - Vibrating the patient's Lower Dantian, to Lead the Qi back to its origin through supplementing its Qi;
   - Vibrating the Mingmen GV-4 and Da Zhui GV-14 points, to activate Qi in the Governing Vessel.

b. The Sword Finger Palm is used for directing and emitting concentrated vibrational energy into channel points, to stimulate the patient's energetic field.

c. The Invisible Needle Palm is used for directing and emitting the most condensed form of concentrated vibrational energy into the channel points, to stimulate the patient's energetic field.

VIBRATING PALM EXERCISE

The training for this kind of vibrational extension usually begins from a static Wuji posture, then gradually progresses into a dynamic state of energy projection.

- From a Wuji posture, press both palms together at the center of the chest forming a "Buddhist greeting" posture (see Chapter 15). Press the Baihui point upward and the Mingmen backward, while slightly drawing in the chest. Keep hips relaxed, knees bent, tongue on palate, and eyes closed.
- Breathe naturally while focusing the mind on the Lower Dantian. When the Heat and Qi begin to circulate, exhale while mentally guiding the Qi up the chest into both of the palms, by sending the energy through the three Yin channels of the hands.

When inhaling, mentally guide the Qi along the three Yang channels of the hands, back down the back into the Lower Dantian. Maintain natural breathing, and continue to focus attention on both the palms and the fingertips. The palms should heat up and the fingertips tingle, as they expand with Qi (Figure 34.15).

Lead the vibrating energy in the Lower Dantian up into the palms and fingertips, feeling the tissues dissolve inch by inch, cell by cell. The Qi is always centered on the inner Lao Gong Pc-8 point, gathering and collecting but not dispersing. Practice this exercise once or twice a day for 3-10 minutes.

Note: It is imperative that the doctor, when using the technique of "stationary energy pro-



Figure 34.15. The Vibrating Palm exercise helps to increase the Qigong doctor's projected vibration.

jection," never hold his or her breath, or purposely make the hand vibrate by forcefully shaking the muscles. To do so causes Qi stagnation which results in pain and stiffness in the chest and sharp pain in the arms that feels similar to having a fractured bone or a laceration of the muscles. To ensure that there are no difficulties, the doctor should first master the Vibrating Qi method, allowing the vibrating energy to extend and project naturally.

GUIDING THE HOT AND COLD FLOW OF ENERGY

This method refers to the doctor's release of energy being emitted into the patient's body to either regulate Hot syndromes with Cold energy, or Cold syndromes with Hot energy. These two Yin and Yang energetic properties are used to develop the emission of both Hot and Cold energetic flows, through breathing, mental concentration and finger placement.

When Yin Qi is applied, the patient will feel "cold as iron," when Yang Qi is applied, the patient will feel "hot as fire." The mind plays an important role in regulating the doctor's and patient's Yin and Yang energy. When the Qigong doctor thinks of fire, the doctor's body will naturally become hot; conversely, when the doctor thinks of water, his or her body will naturally become cold.

HAND MANIPULATION OF YIN AND YANG ENERGY EXTENSION

The Yin (Cold) and Yang (Hot) energy extension utilizes specific palm and finger arrangements. The index and middle fingers together are assigned Yang properties, whereas the ring and little fingers together are assigned Yin properties. The doctor's left thumb connects with the selected two fingers, to determine the release of Yin or Yang energies. This energy is first gathered from the doctor's left hand, through the arm into the Lower Dantian, then emitted out through the right hand. The Qi that is emitted when the doctor's thumb, index and middle fingers connect, for example, releases the Heart's Yang Qi through the right hand. This technique is used to replenish the patient's Yang and regulate the patient's Heart energy.

GATHERING AND ISSUING YANG (HOT) ENERGY

Before emitting Hot energy into the patient, the doctor's Qi is first gathered into his or her left palm by imagining a small "fiery red sun" radiating heat, light, and fire. This small sun is imagined within the circle created between the thumb and first two fingers on the left hand. The hot energy of the sun is then absorbed through the doctor's left arm into the Lower Dantian. The Heat is then blended with the Lower Dantian's Qi and released out the doctor's right arm through either the tips of the index and middle fingers (the Yang Sword Fingers hand technique) for a deeper, concentrated type of penetration, or through the Extended Fan Palm hand technique for a dispersing type of penetration.

To extend Hot energy deeper into the patient, the right hand Yang Sword Finger posture is used. The doctor's index and middle fingers are extended and joined together, the ring and little fingers curl into the center of the palm. The thumb should rest on the nails of the ring and little finger, forming a circle.

The first or "index" finger indicates the Wood Element, i.e., the Liver's energy, and the middle finger indicates the Fire Element or the Heart's Qi. Together, both fingers activate the Qi of Fire and Wood, which catalyze the Yang energy needed for guiding Heat during point concentration.

Guiding Hot Yang Qi Exercise

This particular meditation is used to increase Heat and light in specific areas of the patient's body (usually for chronic, Deficient, or Cold syndromes). The following meditation, for example, can be used to Heat and tonify the Kidneys in chronic fatigue patients.

- Sit on the edge of a chair in front of a table, feet flat, eyes closed, with the left hand resting comfortably on the left thigh. The right palm is extended face down suspended over the table.
- Breathe naturally while concentrating the mind on the Lower Dantian. Imagine the energy in the Lower Dantian is a hot, burning sun expanding out and enveloping the entire body. Gather the energy back into the Lower Dantian, transforming it into heat and light. Draw the heat and light up into the chest, down the arms, and out the right palm. Concentrate and imagine the heat and light burning and extending into the table, penetrating deep into it. After awhile, switch palms. In China, this exercise is practiced while standing or sitting in the sunshine, facing south or east. Practice for 20-40 minutes (Figure 34.16).

GATHERING AND ISSUING YIN (COLD) ENERGY

Before extending Cold energy into the patient, the doctor's Qi is first gathered into his or her left palm by imagining a small, watery blue moon, radiating cool light. This small moon is imagined within the circle created between the thumb and last two fingers. The cool blue energy of the moon is then absorbed through the doctor's left arm, into the Lower Dantian. The cool blue energy is then blended with the Qi of the doctor's Lower Dantian and released out the doctor's right arm through either the tips of the ring and little fingers (the Yin Sword Fingers hand technique) for a deeper, concentrated type of penetration, or through the Extended Fan Palm hand technique for a dispersing type of penetration.



Figure 34.16. Guiding Hot Yang Qi Exercise

In extending cool blue energy into the patient, the right hand Yin Sword Finger posture is generally used. The doctor's ring and little fingers are extended and joined together, and the index and middle fingers curl into the center of the palm. The thumb should rest on the nails of the index and middle finger forming a circle.

The ring finger indicates the Metal Element or the Lungs' energy, and the little finger indicates the Water Element or the Kidneys' energy. Together, both fingers activate the Qi of Metal and Water, which is a catalyst for the Yin energy needed for guiding cool Yin Qi during point concentration.

Guiding Cold Yin Qi Exercise

This meditation is used to cool specific areas in the patient's body in acute, inflamed Excess or Heat syndromes. It can also be used, to cool down and dredge the Liver in cases of chronic depression.

- Sit on the edge of a chair in front of a table, feet flat, eyes closed, with the left hand resting comfortably on the left thigh. The right palm is extended face down suspended over a table.
- Breathe naturally while concentrating the mind on the Lower Dantian. Begin to gather energy from the heels and Bubbling Well (Kd-1) points, directing the energy through the chest (CV-17), out the arms, and into the right palm. Imagine the right palm turning as cold as ice. Focus the mind on the coldness of the right palm and imagine the cold energy penetrating deep into the table. In China, this exercise is practiced at night, facing north or west for 20-40 minutes (Figure 34.17).

Note: While practicing the Cold Yin Guiding exercise, never imagine that the whole body is cold, also do not direct and keep the cold energy into your body (only through it). Otherwise the Cold energy will affect the balance and energetic harmony of the Qi's flow. You can, however, use the image of cool blue water or vapor flowing through your body into the right hand (which is freezing cold), without causing harm to your body's energetic balance.

CLINICAL APPLICATION OF YIN AND YANG ENERGY EXTENSION

Traditionally, the Qigong doctor would emit Hot Yang Qi during the Yang period of the day (from midnight to high noon) to warm the patient's Cold areas. During the Yin periods of the day (from high noon to midnight) the doctor would apply the Cold Yin Qi to cool the Hot areas of the patient's body.

In China today, the clinical application of issuing Hot or Cold energy is no longer limited to the position of the sun and moon, but is applied according to the doctor's ability to regulate the Excess or Deficient condition of the patient's disease.

GUIDING THE ENERGETIC FLOW OF THE FIVE ELEMENTS

This particular Medical Qigong healing system is divided into two popular methods of energy extension: The Five Elemental Organ Energies Method and The Five Elemental Channel Energies Method.



Figure 34.17. Guiding Cold Yin Qi Exercise

Both systems can be used for diagnosing the patient (using palm detection) or for treating Excess or Deficient conditions within the patient's body (using energy extension techniques). Each of these two powerful systems of treatment has its own unique advantage in application. Both systems combine healing sound resonances with energy light extension of various colors, and are used in accordance with the theory of the Five Elements.

THE SIX CHARACTER FORMULA

When utilizing either the Five Elemental Organ, or Five Elemental Channel system of energy projection, the Qigong doctor will guide the energy of the Five Elements in conjunction with the Six Character Formula. The Six Character Formula includes: The Five Elemental Energies, Time of Treatment, Direction of Energy, Position of the Thumb, Guiding Energy, and Emitting Energy and Sound.

1. The Five Elemental Energies of Wood, Fire, Earth, Metal, and Water relate to either the Five Elemental Channel system of energy projection and the Blood / Heat Cycles; or the relate to Five

Elemental Organ system and the energy of the Five Yin Organs. The decision regarding which of the two methods to choose is determined by the patient's condition.

2. The time of treatment is traditionally determined by the doctor in accordance with the patient's Blood/Heat Cycle, the time of day (sunrise, noon, sunset, and midnight) and the season (summer, winter, autumn, or spring).
3. The direction of energy emitted into the patient's body is determined by the doctor in accordance with his or her intention to purge, tonify or regulate the patient's tissues.
4. The position of the thumb is determined in accordance with the type and amount of energy the doctor wishes to absorb into his or her Lower Dantian.
5. Guiding (Pushing, Pulling and Leading) the energy is determined by the doctor in accordance with the Excess or Deficiency of the patient's Five Yin Organs: Liver (Wood), Heart (Fire), Spleen (Earth), Lungs (Metal), and Kidneys (Water).
6. The type of energy (Qi or Shen) and the choice of sound to be emitted are determined by the doctor's intention and the condition of the patient's organs and channels. Qi and sound are emitted like water, Shen is emitted like light.

EMITTING THE ENERGY OF THE FIVE ELEMENTAL ORGANS

The method of projecting the Five Elemental Organ Energies is utilized by blending a specific organ energy together with the Qi stored in the doctor's Lower Dantian. Both of these energies are combined and then issued out the doctor's right palm into the patient. The fusion of the doctor's Lower Dantian Qi with the selected organ Qi is very powerful. This synergized Qi is further combined with sound resonation and colored light to treat patients with extreme conditions of Deficiency.

The left thumb connects with either the tip of the index (Wood), middle (Fire), ring (Metal), little finger (Water) or upper pad of the palm (Neutral) to connect with the selected organ energy (Figure 34.18).



Figure 34.18. Left Palm - The Five Element Organ Energy Pattern: the left hand is used in order to absorb the organ Qi into the doctor's Lower Dantian. This arrangement corresponds to the Five Seasonal Pattern Cycle and the Five Elements.

Five Fingers	**Five Elements**	**Five Viscera**
Thumb	Earth	Spleen
Index	Wood	Liver
Middle	Fire	Heart
Ring	Metal	Lungs
Little	Water	Kidneys

Figure 34.19. Hand Chart of the Five Elements

After choosing the appropriate thumb and finger position on the left hand to tap into the selected organ's energy, the doctor descends this energy into the Lower Dantian. This energy is then blended together with the energy of the Lower Dantian and led out of the doctor's body, to be emitted into the patient using the right hand, along with the sound and specific organ color (Figure 34.19).

EMITTING THE ENERGY OF THE FIVE ELEMENTAL CHANNELS

The method of projecting the Five Elemental Channel Energies is utilized by blending a specific channel energy together with the Qi stored in the doctor's Lower Dantian. To tap into the selected channel's energy, the thumb is positioned on the corresponding finger, or palm segment (Figure 34.20). The selected channel's energy is then blended with the Qi stored in the doctor's Lower Dantian. These combined energies are then issued out the doctor's right palm into the patient. The blending of channel and Lower Dantian Qi is strong but not as powerful as the doctor's organ energy.

The resonant sound and light emitted from the combined channel and Lower Dantian energy is considered appropriate for patients with moderate Deficiency conditions. Healing sounds in combination with specific colors can be emitted by the Qigong doctor to stimulate the internal tissues. When healing sounds are directed into the patients tissues they have a tonifying action, as opposed to the purging affect which happens when the patient's practice healing tones by themselves (see Chapter 40).

The treatment is conducted according to the Five Elemental Creative Cycle. First the energy of the "mother" element is gathered into the doctor's Lower Dantian to be combined with the doctor's Lower Dantian energy. After the doctor collects and mixes the mother's elemental channel energy with the Lower Dantian's energy, the doctor switches the left thumb's position to the mother's corresponding "child" element position. This enables the mother's channel energy to support the strength of the child's channel energy, which is emitted into the patient's body (Figure 34.21).

Note: The doctor first connects to the mother element, then to the child element. Thus the mother's elemental channel energy, Lower Dantian energy and the child's elemental channel Qi are synergized and projected into the patient's corresponding "child" organ. The patient's organ, into which the Qi is emitted, has the same elemental attribute as the doctor's "child" transmitted energy.

1. To Emit Liver Energy and Guide Wood Qi proceed as follows:
   - First, from a Wuji posture, press the left thumb into the channel Water bands (9, 10). Inhale this Water energy into the Lower Dantian, mixing it together with your Lower Dantian energy.
   - Second, extend the right hand facing outward from the chest, facing the patient. Then exhale and press the thumb onto the Wood channel bands (1, 2) while uttering the sound "Shu." Guide the Wood energy out of the right palm into the patient's Liver organ or channel. In this particular technique, the doctor is using Water energy to support the extension of Wood energy.
2. To Emit Heart Energy and Guide Fire Qi proceed as follows:
   - First, from a Wuji posture, press the left thumb into the channel Wood bands (1, 2), while inhaling the Wood energy into the Lower Dantian, mixing it together with your Lower Dantian energy.
   - Second, extend the right hand facing outward in front of the chest, towards the patient. When exhaling, press the thumb onto the Fire channel bands (7, 8) with the thumb while uttering the Heart sound "Haa." Guide the Fire energy out the right palm into the treatment area. In this particular technique, the doctor is using Wood energy to support the extension of Fire energy.
3. To Emit Spleen Energy and Guide Earth Qi proceed as follows:
   - First, from a Wuji posture, press the left thumb into the channel Fire bands (7, 8) gathering this Fire energy into your Lower Dantian.
   - Second, extend the right hand in front of the

Colors		Element	Channel
1.	Green	Wood	Gall Bladder
2.	Green	Wood	Liver
3.	White	Metal	Lungs
4.	White	Metal	Large Intestine
5.	Yellow	Earth	Stomach
6.	Yellow	Earth	Spleen
7.	Red	Fire	Heart
8.	Red	Fire	Small Intestine
9.	Blue	Water	Bladder
10.	Blue	Water	Kidney
11.	Red	Fire	Pericardium
12.	Red	Fire	Triple Burner

Figure 34.20. The Twelve Channels are superimposed onto the Qigong doctor's left palm, arranged according to the progression of the Two Hour Qi and Blood/Heat Cycle.

This Blood/Heat Cycle also corresponds to the Four Principle Time Periods and can be divided into quarters and arranged according to the Midnight, Sunrise, Noon, and Sunset patterns of the Sun.



Figure 34.21. Left Palm - The Five Elemental Channel Pattern:

The left palm is used in gathering and absorbing the channel Qi of the doctor's Five Yin Organs. As the Qigong doctor's thumb touches the specific areas on the fingers, the energy is gathered into the doctor's Lower Dantian and released out from the right palm.

chest, facing outward towards the patient. When exhaling, press the thumb into the Earth's channel bands (5, 6) while uttering the Spleen sound "Who." Guide the Earth energy out of the right palm into the treatment area. In this particular technique the doctor is using Fire energy to support the extension of Earth energy.

4. To Emit Lung Energy and Guide Metal Qi proceed as follows:
   - First, from a Wuji posture, connect the left thumb onto the tip of the left index finger (i.e., the Earth channel bands #5, 6), thus forming a circle. Imagine this circle full of golden light. When inhaling, draw this golden Earth energy into the Lower Dantian, while also inhaling Heavenly Qi into the Yellow Court area (CV-12) below the solar plexus. Mix all three of these energies together.
   - Second, extend the right hand facing outward in front of the chest, towards the patient. When exhaling, press the thumb the Metal channel bands (3, 4) while uttering the Lungs' sound "Sss." Guide the Metal energy out of the body by way of the right palm into the treatment area. In this particular technique, the doctor is using

imagination to draw the Earth's golden light energy into his or her Lower Dantian to support the extension of Metal energy.

5. To Emit Kidney Energy and Guide Water Qi proceed as follows:
   - First, from a Wuji posture, press the left thumb into the Metal channel bands (3, 4). Inhale the Metal energy into the Kidneys, mixing it together in the Lower Dantian.
   - Second, extend the right hand facing outward in front of the chest. As you exhale, press the Water channel bands (9, 10) while uttering the "Chree" sound (in a very low pitch). Guide the Water energy out of the body by way of the right palm. In this particular technique, the doctor is using Metal energy to support the extension of Water Qi.

Once skilled in these five exercises, the Qigong doctor should continue to practice them in combination with the Linear, Circular, or Spiral Energy Guiding Methods, creating an individualized, structured technique.

COMBINING THE ENERGY OF THE FIVE ELEMENTAL TONGUE POSITIONS

The doctor can also use the Five Elemental Tongue Positions to increase the power and energetic potential of the doctor's internal organ. Each tongue position connects with the organ's Orb (the complete organ system), thereby increasing the power of the doctor's Qi projection. These tongue positions are described as follows.

1. To connect with Earth (Spleen) energy—the tongue is placed on the bottom of the jaw at the base of the lower palate, beneath the teeth and gum line.
2. To connect with Metal (Lungs) energy—the tongue is placed between the maxilla and mandible bones, suspended, between the teeth.
3. To connect with Fire (Heart) energy—the tongue is placed on the hard palate, at the front of the upper palate, behind the teeth and gum line.
4. To connect with Wood (Liver) energy—the tongue is placed on the hard palate, at the middle of the upper palate at the center of the roof of the mouth.
5. To connect with Water (Kidneys) energy—the tongue is placed on the soft palate, at the back of the upper palate.

COMBINING THE ENERGY OF THE FIVE ELEMENTAL COLORS

The doctor can also include the Five Elemental Colors to increase the power of his or her internal Qi projections (see Chapter 4). The Five Elemental Colors are described as follows.

- Earth (Spleen)—The organ color bright yellow, the channel color is soft yellow.
- Metal (Lungs)—The organ color bright white, the channel color is soft white.
- Fire (Heart)—The organ color bright red, the channel color is soft red.
- Wood (Liver)—The organ color bright green, the channel color is soft green.
- Water (Kidneys)—The organ color bright blue, the channel color is soft blue.

SUMMARY OF QI EMITTING METHODS

When the Qigong doctor emits Qi into the patient, it effects the quality of light, sound, heat, vibration, and electromagnetic energy stored within the patient's tissues and cells. There are many variations of Qi emission hand postures and techniques used by Qigong doctors in China. Each differs according to the various schools, colleges, and styles of Medical Qigong training. These changeable and diverse hand postures, as well as the various Qi extension, guidance, and regulation techniques can all be combined and grouped together to assist the Qigong doctor in understanding the clinical treatment potentials. The following is an outline of the aforementioned Hand Postures and Extension, Guidance, and Regulation techniques (described in Chapter 33 and 34), along with their applications.

HAND POSTURES USED FOR EMITTING QI

1. The Extended Fan Palm Hand Posture energy emission has the widest beam of Qi extension.
2. The Sword Finger Hand Posture energy emission has the width and beam reduced into a more condensed form of Qi extension.
3. The One Finger Skill Hand Posture energy emission is further reduced into an even more condensed form of Qi extension.

4. The Invisible Needle Hand Posture energy emission is condensed even further into a finely honed needle of light, similar to that of a laser beam.

HAND TECHNIQUES USED FOR BREAKING UP ENERGETIC STAGNATIONS

1. The Thunder Fingers Hand Technique is the strongest, most aggressive hand technique, and is used to break into the energetic boundary of the Qi stagnation. It is used as a preparation technique before purging the stagnation.
2. The Shaking and Trembling Hand Technique is the second most aggressive hand technique, and is used to purge stagnation and toxic Qi from the patient's body.
3. The Vibrating Hand Technique is a powerful, yet subtle hand technique, which can be used to expand, contract, vibrate, and loosen the patient's Stagnant Qi.
4. The Kneading Tiger Hand Technique is used to separate the Toxic Qi, and to dredge and purge it out of the patient's body.

ENERGY EXTENSION AND GUIDANCE TECHNIQUES FOR MOVING QI

1. The Pushing Technique is used to push and move the energy within the body's tissues, channels, and energetic fields.
2. The Pulling Technique is used to pull and move the energy within the body's tissues, channels, and energetic fields.
3. The Leading Technique is used to lead, guide, and move the energy within the body's tissues, channels, and energetic fields.
4. The Circling Technique is used to lead, guide, and move the energy in a circling pattern within the body's tissues, channels, and energetic fields.
5. The Spiraling Technique is used to spiral or drill energy into or out of the body's tissues, channels, and energetic fields.
6. The Energetic Cupping Technique is used to lead, guide, and move the energy within the body's tissues, channels, and energetic fields.

HAND POSTURES USED FOR PURGING, DREDGING, AND REMOVING TOXIC QI

1. The Bellows Palm Hand Posture is used like a vacuum to remove toxic Qi
2. The Dragons Mouth Palm Hand Posture is used to grasp, pull, and lead toxic Qi from the body.
3. The Sword Fingers Hand Posture is used to circle-wrap toxic Qi (like a fork wrapping spaghetti) and remove it from the body.
4. The Kneading Tiger Hand Posture is used to grasp, seize, and pull toxic Qi from the body.
5. The Shaking and Trembling Hand Posture is used in order to grasp, seize, and pull toxic Qi from the body.
6. The Thunder Fingers Hand Posture is used to shake and release toxic Qi from the doctor's body.
7. The Extended Fan Palm Hand Posture is used to dredge, pull, and purge toxic Qi from the body.

TYPES OF ENERGY RELEASED THROUGH QI EMISSION

1. Hot Qi Emission is used to tonify or sedate a specific area, organ, channel, or energetic field.
2. Cold Qi Emission is used to cool down or sedate a specific area, organ, channel, or energetic field.
3. Color Qi Emission is used to tonify or sedate a specific area, organ, channel, or energetic field.
4. Sound Emission is used to tonify or sedate a specific area, organ, channel, or energetic field.
5. Five Elemental Organ Qi Emission is used to tonify or sedate a specific area, organ, channel, or energetic field.
6. Five Elemental Channel Qi Emission is used to tonify or sedate a specific area, organ, channel, or energetic field.

CHAPTER 35
THE INVISIBLE NEEDLE THEORY AND APPLICATION

INTRODUCTION

In China today, the use of Invisible Needles in Medical Qigong therapy is usually reserved for patients who are hypersensitive to energy flow. As the patient's sensitivity increases, the treatments are modified in order to complement their perceptive abilities.

To perform the Invisible Needle technique, the Qigong doctor must first connect with the divine energy. This is performed by drawing energy from the Heavens through the Baihui GV-20 point at the top of the head and extending it out through the hands, enveloping the patient. Some Qigong doctors imagine that needles of light, from the Heavens, descend through their Baihui point. As this light fills their body, they become empowered with a never-ending reserve of Invisible Needles to treat the patient. In order to use these needles, the doctors rotate their wrist clockwise and the Invisible Needle flows out the Pc-8 Point at the center of their palm (Figure 35.1).

Other Qigong doctors use a single needle image. The doctor imagines needles of light coming out of the Heavens, spiraling around the head like a golden halo. This golden halo is positioned above the head, above the Heavenly Transpersonal Point (located about a foot above the head). To use these needles, the doctors reach above their head and pluck the needles from the Heavens. These needles are then inserted into the patient's body (Figure 35.2). When using either visualization, the important factor is to focus on how deep the needles should penetrate. When treating an area deep in the major organs, a clockwise rotation reinforces and tonifies, while a counterclockwise rotation sedates the organ area.

PREPARATION

Before inserting an Invisible Needle into the



Figure 35.1. The Qigong doctor imagines divine healing light descending from the Heavens, filling the doctor's body with the energy to create the Invisible Needle.



Figure 35.2. Another variation is for the Qigong doctor to imagine divine healing light descending from the Heavens and encircling the doctor's head like a golden halo. Contained within this halo are the Invisible Needles.

patient, it is important for the doctor to dredge the diseased area first. This is similar to swabbing an area with alcohol (or disinfectant) before inserting an acupuncture needle. As one hand extends the Invisible Needle, the other is used to reinforce its energy. The doctor works the Invisible Needle into the patient's tissues until he or she feels it inside the patient's body. Sometimes the patient may feel a cold sensation while being treated by the doctor. This is a normal reaction to the Invisible Needle insertion. The longer that the doctor keeps the Invisible Needle inserted inside the patient's body, the better the healing effect.

ANGLE OF INSERTION FOR TONIFICATION OR SEDATION

The skill of using Invisible Needles encompasses a complete system of energetics that utilizes both reinforcing (tonifying) and reducing (sedating) techniques. The polarity of the patient's channel (Yin or Yang) determines the angle at which the Invisible Needle is inserted.

- When performing reducing or sedating techniques, it is important to insert the Invisible Needles perpendicularly into the patient's points or channels, forming an energetic dam to slow the flow of Qi (Figure 35.3). The doctor removes the needle slowly, and leaves the point open (this allows the point to continue to release Qi naturally).
- When performing any reinforcing or tonifying techniques, insert the Invisible Needle at an angle, pointed in the direction of the channel's flow (provided that the channel is flowing towards the direction of the intended organ). Then, when retracting the Invisible Needle, remove it quickly and seal the point. This quick retraction method is done to prevent the Qi from escaping the area once it is stimulated, and is followed by pressing the needle hole to seal the point (Figure 35.4).

One favorite tonification technique used by certain Qigong doctors in Beijing, China is to leave the Invisible Needles inside the patient, while regulating the Conception and Governing Vessels. Once they have strengthened the patient's Microcosmic Orbit (Fire Cycle), they retract the Invisible Needles and disperse them one by one into the Earth. The insertion and manipulation of the Invisible Needles is performed with the Invisible Needle Palm technique.



Figure 35.3. The doctor's right hand extends the Invisible Needle perpendicularly into the patient's point or channel, to reduce or sedate the energy flow. The doctor's left hand is used to reinforce the energetic purging of the patient's toxins.



Figure 35.4. Insert the Invisible Needle at a 45 degree angle with the flow of the patient's channel to reinforce or tonify, provided the channel's flow is towards the organ.

In order to prevent the Qi from escaping, when performing any reinforcing or tonifying techniques, the Qigong doctor presses the patient's channel point after retracting the Invisible Needle.

Another favorite technique used for tonification is for the Qigong doctor to first insert the Invisible Needle deep into the patient's Kd-1 point at the bottom of the feet. Once the needle is inserted, the doctor extends his or her intention, causing the needle to grow and extend up the patient's legs and into the Kidneys. Next, the doctor emits energy up the patient's legs to further tonify the Kidneys and Mingmen area.

The Invisible Needles can also be transformed into the specific colors of the Five Elements to enhance tonification. A blue needle, for example, can be used to intensify Kidney tonification. Each needle can additionally be spiraled in a clockwise or counterclockwise direction to generate an energetic vortex used for either tonification or purgation (Figure 35.5).

THE HAND POSTURES OF THE INVISIBLE NEEDLE

The following is a description of the various hand postures used when treating patients with the Invisible Needle technique.

THE DOCTOR'S RIGHT HAND

The doctor's right hand is generally used for controlling and projecting the energy of the Invisible Needle into the patient. It is not only responsible for the formation but also the insertion of the Invisible Needle. The action and movement of the right palm projecting and stimulating Qi is sometimes referred to as the Chicken Pecking technique. In this hand posture, the thumb connects with the index finger or index and middle finger to form the shape of a bird's beak (Figure 35.6). While these fingers are joined together, the other fingers on the hand relax in an extended, straight position. The doctor's intention is focused on the image of an Invisible Needle which is projected into the patient's body.

The pricking, insertion, and manipulation of the Invisible Needle is only effective when the Qigong doctor connects and roots his or her intention deep within the patient's Jing, Qi, and Shen. This intention connects the doctor with the patient's Qi and Blood, and their animated Spirit.

THE DOCTOR'S LEFT HAND

The doctor's left hand is used to either manipulate the patient's tissues to enhance the Qigong treatment, or to collect Qi into the doctor's Lower Dantian to be projected into the patient. This technique is similar in method to collecting the Yin (Cold) and Yang (Hot) energy before emitting it into the patient. Once the thumb connects with any of the fingers, the released energy bears the nature of the associated element and its Yin and Yang properties (Figure 35.7). The Qi that is collected when the thumb and middle finger connect, for example, is the Yang Qi within the Heart.



The needle can be made to grow and extend deep inside the patient's tissues or channels.

The needle can be made to grow fat inside the patient's tissues or channels to increase Qi projection.



Clockwise spiraling the needle is used to create an energetic vortex for tonification.

Counterclockwise spiraling the needle is used to create an energetic vortex for purgation.

Figure 35.5. The Invisible Needle Techniques



Figure 35.6. The Invisible Needle Palm

This Qi replenishes the Yang Qi and regulates the energy of the Heart (Figure 35.8). If the doctor's hand is positioned over the Pericardium Channel and energy is emitted into the patient, the patient's Shen will become peaceful. When treating with the Five Elemental organ energy, the index and middle finger stand for Fire and Wood; this combination is considered Yang. The ring and little finger stand for Water and Metal; this combination gathers and creates Yin energy.

TIME AND DURATION OF TREATMENT

In general, Medical Qigong Invisible Needle Technique and Point Therapy is applied once a day. A routine therapeutic course includes six to eighteen treatments. Patients with mild diseases may continue the therapy from six to twenty-four treatments. For chronic patients, however, treatment may last as long as one to three months depending on the patient's condition (i.e., for paraplegic patients the treatment is generally from three to six months).

As far as the time sequence of when to treat the patient, or when the patient is to treat themselves, the chronometric rate is based on the high-tide sequence of the patient's channels (i.e., 11 am to 1 pm is the Heart time, which is the best time period to treat patients with Heart disease).

REMOVING THE INVISIBLE NEEDLES AND ENDING THE TREATMENT

During tonifying treatment, the Qigong doctor removes the Invisible Needle quickly from its point of origin while the patient is inhaling. This allows the patient to keep the Qi and Shen within the body's channels and tissues. After extracting the needle, the doctor presses down on the acupuncture point with emitted Qi and lightly rubs it in a clockwise direction until the open point has closed.

During a sedating treatment, the Qigong doctor has the patient exhale to expel the Evil Qi and Heat from the patient's tissues. After extracting the needle slowly, the doctor allows the acupuncture point to naturally drain and eventually close by itself. This aids in draining the Evil Qi and Excess Heat from the patient's body.



Figure 35.7. When treating patient's with the Invisible Needle technique for tonification, the Qigong doctor emits the required amount of energy into the patient, according to the specific Deficient organ and channel's condition.

The thumb, being the Earth Element and neutral, allows the Qigong doctor the ability to connect and combine the energy of the Five Yin Organs into his or her Lower Dantian, before extending the Qi into the patient.

Five Fingers	**Five Elements**	**Five Viscera**
Thumb	Earth	Spleen
Index	Wood	Liver
Middle	Fire	Heart
Ring	Metal	Lungs
Little	Water	Kidneys

Figure 35.8. Hand Chart of the Five Elements

CHAPTER 36
ENERGETIC POINT THERAPY

The importance of Energetic Point therapy as a Medical Qigong modality can best be understood when exploring the amount of information stored within the body's tissues. According to theoretical physicist Michio Kaku, the body's DNA contains over one hundred trillion times the information stored in current computers. There is an even greater amount of information stored within the three subtle energy fields outside of the human body. Most of this information is not readily translatable or decipherable, and is hidden from the conscious mind.

By stimulating certain energy points, for a specific length of time, an energetic trigger mechanism, or response reflex is created. This energetic reaction releases memories and stored information unique to each patient. To facilitate the unlocking of this stored information, the Qigong doctor must maintain a deep state of Alpha consciousness when stimulating the patient's energy points.

Energetic Point therapy involves two distinct modalities of treatment: Channel Point treatments and Channel Point meditations. Either can be used in conjunction with the Invisible Needle therapy. In these particular modalities of treatment, the Qigong doctor can either emit Qi into specific channel points on the patient's body to enhance the Medical Qigong treatment, or have the patient meditate on a specific point while the doctor administers the therapy. Both approaches can be used by the Qigong doctor to gather energy, move Qi, or release trapped energy from the patient's tissues.

CHANNEL POINT TREATMENTS AND PRESCRIPTIONS

The following treatments are generally used in the clinic by the Qigong doctor for Invisible Needle therapy, but are not necessarily limited to that modality of treatment. These Energetic Point treatments are arranged and categorized according to specific diseases. The Energetic Points are located on the patient's front and back as depicted in the anatomical graphs (Figures 36.1 and 36.2). These points are clinically used for the following treatment goals:

POINT THERAPY TO TONIFY YIN ENERGY

1. To Tonify Yin energy and to reduce a Deficient type of Fire, extend Qi into the patient's Kd-3 point.
2. To nourish the Yin energy and to reduce Fire, extend Qi into the patient's Kd-3 and Lu-10 points.
3. To treat a Deficiency of Yin of the Liver and Kidneys and to reduce the causes of Deficient Fire, extend Qi into the patient's Sp-6 and Lv-3 points.
4. To treat a Deficiency of Yin causing a dryness of the Lungs, extend Qi into the patient's Lu-1 and Bl-13 points on the front and back of the body. Regulate the respiratory tract, as well as the patient's Lu-7 and Kd-6 points, thereby tonifying the body's Yin energy and activating the descending function of the Lungs.

POINT THERAPY TO TONIFYING OR DISPERSE YANG ENERGY

1. To strengthen the Yang of the patient's Kidneys, extend energy into the patient's GV-4, Bl-23, and Kd-3 points.
2. To warm, and tonify the Yang of the patient's Spleen and Kidneys, extend energy into the patient's Bl-20 and -23 points. This treatment is ideal for eliminating Damp fluid caused from Deficient types of edema.
3. To fortify the Yang and avert a state of Yang collapse, tonify the patient's Yuan Qi by extending energy into the patient's Lower Dantian, focusing specifically on the patient's CV-4, -6, and -8 points.


Bl-7
Bl-7
CV-22
Pc-3
CV-13
CV-12
Pc-3
Lv-15
CV-8
Pc-5
Pc-5
Lv-15
CV-6
Lu-7
Lv-15
Lu-7
CV-3
St-29
CV-2
St-29
Sp-10
Sp-10
St-36
Sp-9
Sp-9
St-40
Lv-5
Lv-5
Sp-6
Sp-6
Lv-3
Lv-2
Lv-3
Lv-2
Sp-4
Sp-3
Sp-1

Figure 36.1. Chart of Specific Channel Points

4. To treat a condition of Deficiency of Yang of the Spleen, strengthen the patient's Stomach and Spleen to eliminate Damp and Phlegm. This is done by extending energy and tonifying the patient's St-36, CV-12, and Bl-20 points. Then activate and warm the Qi of the patient's Lungs by extending Qi into Bl-13, and -43 points.
5. To strengthen the Yang of the Spleen, promote the Spleen's transporting function by extending energy into the patient's CV-12, Bl-20, Lv-13, and Sp-3 points.
6. To raise the patient's Yang Qi or the Yang Qi flowing within the patient's Governing Vessel, extend energy into the GV-20 point.
7. To reduce hyperactive Yang of the patient's Liver, first dredge and disperse the patient's GB-20, Bl-18, and Lv-2 points to pacify the Yang of the Liver; then tonify by extending energy into the patient's Bl-23 and Kd-3 points to strengthen the Kidneys.
8. To reduce Excess Yang within the patient's Governing Vessel which has caused a hyperactivity of Heat, dredge and sedate the patient's GB-2O point. Then purge the Heat from the patient's GV-14 and LI-4 points.

POINT THERAPY TO TONIFY OR DISPERSE QI

1. To strengthen the patient's Yuan Qi, extend Qi into the patient's Lower Dantian, focusing on CV-4 and -6 points.
2. To fortify the patient's Qi and reestablish their Yang, extend energy into the patient's GV-20, CV-6, and St-36 points.
3. To subdue the patient's ascending Qi, extend Qi into the patient's CV-22 and Bl-17 points.
4. To disperse the patient's stagnant Qi and Phlegm, extend Qi into the patient's Bl-13 point.
5. To tonify the Kidneys' Qi and Jing and to reduce any Kidney Deficiency, extend Qi into the patient's GV-4, Bl-52, and Kd-3 points.
6. To stimulate the circulation of Qi and Blood, extend Qi into the patient's LI-4 and Lv-3 points.

POINT THERAPY TO TONIFY AND NOURISH THE BLOOD

1. To activate the patient's Blood circulation, extend energy into the patient's Sp-10 point.
2. To stimulate the function of conducting Blood, extend energy into the patient's Sp-1 point.
3. To control the production of Blood, extend energy into the patient's Bl-20 point to control the Blood, as well as Bl-15 to increase the production of Blood.
4. To activate Blood circulation and remove stasis, extend energy into the patient's Sp-6 and Bl-17.
5. To strengthen the source of Blood formation, extend energy into the patient's St-36 and Sp-6 points.
6. To remove Blood stasis of the uterus, extend energy into the patient's Bl-32 and St-29 points.

POINT THERAPY TO ELIMINATE COLD AND DAMP

1. To warm the Spleen and Stomach to eliminate Cold, extend energy into the patient's Lower Dantian and CV-12 and -13 area.
2. To disperse Cold, relieve pain, pacify the Stomach and strengthen the Spleen, extend energy into the patient's Sp-4 and Bl-20 points.
3. To strengthen the Spleen to disperse Dampness, extend energy into the patient's Sp-6 and St-36 points.
4. To eliminate edema above the waist, extend energy into the patient's Bl-20 and Lv-13 points.
5. To eliminate edema below the waist, extend energy into the patient's Bl-28, LI-6, and Sp-9 points.

POINT THERAPY TO ELIMINATE HEAT

1. To eliminate Heat from the patient's body, extend energy into the patient's LI-11 points, or dredge and disperse energy from the patient's Shi Xuan points (at the tips of the fingers).
2. To move Heat downwards from the patient's body, dredge and disperse energy from the patient's Kd-1 points.
3. To disperse External Heat, dredge and disperse energy from the patient's SI-3 points.
4. To eliminate Internal Heat, dredge and disperse energy from the patient's Pc-5 points.
5. To eliminate Damp Heat, extend energy into the patient's Bl-20 and Sp-9 points.


GV-20
GV-16
GB-12
GB-12
GB-20
GB-20
GV-14
Bl-43
Bl-12
Bl-13
Bl-43
Bl-15
Bl-17
Bl-18
Bl-52
Bl-19
Bl-20
Bl-52
LI-11
LI-11
Bl-23
Bl-23
LI-6
Bl-32
Bl-32
GV-4
LI-6
TB-5
Bl-28
Bl-28
TB-5
LI-4
LI-4
SI-3
SI-3
Bl-38
Bl-38
Bl-40
Bl-40
GB-34
GB-34
Kd-7
Kd-7
Kd-3
Kd-3
Kd-1

Figure 36.2. Chart of Specific Channel Points

6. To eliminate Damp Heat from the Blood, dredge and disperse energy from the patient's Bl-40 points, then extend energy into the Pc-3 points.
7. To reduce Fire of the Liver, dredge and disperse energy from the patient's CV-3 and Lv-5 points.
8. To reduce Liver and Gall Bladder Upward Fire disturbance, dredge and disperse energy from the patient's GB-12, as well as Bl-19 and -18 areas.

POINT THERAPY TO ELIMINATE WIND

1. To eliminate Wind Cold, dredge and disperse energy from the patient's GV-16, Bl-12, GB-20, Lu-7, LI-4, and Kd-7 points.
2. To eliminate Wind Heat, dredge and disperse energy from the patient's GV-14, LI-4, TB-5, and GB-20 points.
3. To eliminate Wind from the upper portion of the patient's body, dredge and disperse energy from the patients Bl-7, GV-20, and -16 points.
4. To eliminate pathogenic Wind, extend energy into the patient's Lu-7 points to activate the natural dispersing function of the Lungs.
5. To eliminate Wind and reduce Fire, dredge and disperse energy from the patient's GB-20 points.
6. To calm the Wind of the Liver, dredge and disperse energy from the patient's Lv-3 points.

POINT THERAPY TO ELIMINATE PHLEGM

1. To eliminate Damp Phlegm in the Interior, first strengthen the function of the patient's Spleen and Stomach to eliminate the Dampness, by extending energy into the patient's Bl-20 and CV-12 points, then eliminate the Phlegm by dredging both of the St-40 points.
2. To eliminate Phlegm Fire in the patient's Stomach, dredge the patient's GB-34 and St-40 points.

CONTRAINDICATIONS

Never apply Energy Point therapy to patients who are in an acute stage of inflammatory diseases (especially of the abdomen). Also avoid using Energy Point therapy on patients with hypertension, heart diseases, severe cases of pulmonary tuberculosis, hemophilia, purpura hemorrhagic, purpura allergic, and severe skin diseases.

CHANNEL POINT MEDITATION

After applying the Invisible Needle technique or Energetic Point therapy, the Qigong doctor may decide to initiate Channel Point meditation to intensify the treatment. This is achieved by having the patient concentrate on specific points along the channels. This concentration will produce two distinct results. First, it will get rid of any of the patient's distracting thoughts, and second, it will cause different fluctuations of the Qi and Blood circulation through the patient's Yin and Yang organs. This focused concentration will allow the internal organs to supply the patient's body with either: a more concentrated flow of Qi and Blood into the tissue area; or the focused attention will have a stronger dispersing effect on the patient's tissues (depending on the patient's focus).

Each time a patient switches the focus of concentration to a different point in a different area of the body, the circulation and regulation of Qi and Blood will alter to accommodate the mental transitions of intention. In giving the patient a specific point meditation as a prescription, the Qigong doctor should be careful to select the areas and points in accordance with the particular Qigong exercises that will arrest the patient's Yin and Yang organ disease.

Generally speaking, when treating an Excess condition with Channel Point meditation, the Qigong doctor has the patient imagine draining the Excess Qi out through the extremities. In the case of a Deficiency, the doctor has the patient focus on tonifying the Deficient organ(s) by absorbing energy and light into the Deficient area. Below is a list of channel point regulations and their applications.

QIHAI (CV-6) SEA OF QI

The CV-6 point, located in the Lower Dantian, is the most frequently selected point (Figure 36.3). It is chosen for normal conditions to lead the Qi back to its origin. It is this area from which Qi emanates and returns, hence its name, Sea of Qi. Focusing on this point will allow the patient to tonify the Kidneys (Yuan) Qi, and can be used to regulate the Lower Burner, Conception Vessel, and Water pathways. The Qigong doctor may also extend energy into this area to:

- restore collapsed Yin or Yang Qi,
- raise the patient's Middle Burner Qi,
- warm a patient's Yang Qi,
- warm a patient's Cold condition,
- treat mental disorders,
- treat male sexual problems,
- treat urinary problems,
- treat local pain,
- treat fatigue, and
- treat Qi and Blood Deficiency.

MINGMEN (GV-4) GATE OF LIFE

This point is also called the Palace of Essence (Figure 36.4). Located between the two Kidneys, this point is used for patients with a Deficiency of the Kidney Yang and declining Fire of the Mingmen (this condition is manifested as lumbago pain, seminal emissions, and an aversion to cold). Focus the patient's concentration on the navel first, then gradually have the patient focus deeper into the Mingmen area. This area is known as the Sea of Blood and Essence. Focusing on this point will allow the patient to tonify and stabilize the Kidney (Yuan) Qi and Jing. A Qigong doctor extending energy into this area can regulate the patient's water pathways, heat the body's Yang Qi, and lower blood pressure. This point is also used to treat lower back pain, sciatica, as well as sexual/genital problems.

SHAO SHANG (LU-11) LESSER SHANG

This point is also called Ghost Sincerity, and is considered the second of eleven ghost points (Figure 36.5). The sound "shang" is a musical note and corresponds to the Element Metal. This particular point is used for patients with a Deficiency of Lung Qi (this is manifested by asthma and coughing). It reinforces the Qi and regulates the Lungs. A Qigong doctor can pull energy from this area to dredge and clear Lung Fire, Heat, and Summer Heat, as well as dispel Wind Heat from the patient's body.

ZHONG CHONG (PC-9) MIDDLE RUSHING

This point is used for patients with a Deficiency of Heart Qi (which manifests as palpi-



Figure 36.3. Lower Dantian (CV-6)



Figure 36.4. Mingmen (GV-4)



Figure 36.5. Shao Shang (Lu-11)

tations and restlessness). It reinforces the Qi and calms the Heart and mind. This area is good for regulating the Heart's Qi, reviving consciousness, and restoring collapsed Yang. It can be used to dredge and clear the patient's body of Heart Fire, Heat, and Summer Heat conditions (Figure 36.6).

ZU SAN LI (ST-36) FOOT THREE MILES

This point is used for patients with a disorder of transporting and transforming Spleen and Stomach Qi (which manifests as abdominal distention and pain). This point has a strong tonifying effect (especially for the Spleen) and regulates the Stomach. It also tonifies the Ying (Nutritive) Qi, and regulates the Lower and Middle Burners. It can be used by a Qigong doctor to dredge and reduce digestive stagnation, to redirect Rebellious Qi, to drain pathogenic influences from the Stomach, and to soften hard abdominal masses or tumors (Figure 36.7).

DA DUN (LV-1) GREAT PILE

This point is used for patients with hyperactive Liver Yang or overactive Liver and Heart Fire. It calms the Liver to treat diseases of the upper portion of the body (primarily the head). By focusing on this area, the patient can regulate and tonify the Liver Qi and Blood. The Qigong doctor may dredge this area to disperse Liver Qi and transform Damp Heat in the Lower Burner (Figure 36.8).

YONG QUAN (KD-1) GUSHING SPRING

This point is used for patients with Yin Deficiencies of the Liver and Kidney, hyperactivity of Fire due to Yin Deficiencies, or Excess in the upper torso and Deficiency in the lower torso. Concentration on this area will also calm the spirit, clear Fire and Heat from the head area, restore collapsed Yang, and transform Heart Phlegm (Figure 36.9).

BAIHUI (GV-20) HUNDRED MEETINGS

This point is used for patients with a Deficiency of Qi in the Middle Burner (manifested by a shortness of breath, dizziness, intractable diarrhea, and a prolapse of the internal organs). This point is known as the Sea of Marrow. Focusing on this area will clear the brain and calm the spirit. If the Qigong doctor treats this area, the patient's



Figure 36.6. Zhou Chong (Pc-9)



Figure 36.7. Zu San Li (St-36)



Figure 36.8. Da Dun (Lv-1)



Figure 36.9. Yong Quan (Kd-1)

lower orifices can be stabilized, the Qi can be warmed and tonified, and Yang Qi can be warmed and a collapse can be prevented. This point is also used in order to treat hypertension, insomnia, seizures, dizziness, headaches, and the prolapse of internal organs (Figure 36.10).

HUIYIN (CV-1) MEETING OF YIN

This point is used for patients with a Deficiency of Lung Qi and Kidney Yin (manifested by asthma and coughing). Focusing the patient's concentration on this area stabilizes the patient's Jing and lower orifices, as well as calms the spirit and clears the brain. It can be used by the Qigong doctor to tonify and regulate the patient's Qi, to clear Heat from the patient's body, to treat irregular menses, urethritis, prostatitis, and to raise the blood pressure (Figure 36.11).

YIN TANG (EX. HN. 3) SEAL HALL

This point is used for patients to calm the spirit, and can be used by the Qigong doctor to dispel Wind and clear Heat from the patient's body. This point is also used to treat epilepsy, nausea and vomiting, insomnia, sinus headaches, dizziness, and vertigo (Figure 36.12).



Figure 36.10. Baihui (GV-20)



Figure 36.11. Hui Yin (CV-1)



Figure 36.12. Yin Tang (Ex.Pt.)

CHAPTER 37
MEDICAL QIGONG MASSAGE

INTRODUCTION TO TISSUE FUNCTION

To understand the energetic function of surface and deep tissue stimulation through Medical Qigong Massage, it is important to first understand the reflexes and spontaneous energetic reactions within the body's tissues. The tissues of the human body are in a constant state of perpetual change. No matter where illness or damage has occurred, everything in the body is linked to the organs' and bowels' functions of producing and governing energy, and their interaction with the body's surface tissues (Figure 37.1–37.2).

In Traditional Chinese Medicine, the human body is viewed as a conglomeration of Qi, Blood, channels, tendons, fascia, bones, Marrow, bowels (Yang organs), and viscera (Yin organs). Each part is interdependent, each having inseparable Yin and Yang relationships and all of them interacting with each other. The following describes the interaction of: Qi and Blood, Tendons and Fascia, Bones and Marrow and the Bowels and Viscera.

1. Qi is considered the Blood's leader: as the Qi leads, the Blood follows. If the Qi ceases to flow, the Blood stops.
2. The tendons and fascia are used for channel energy movement. As the tendons and fascia stretch, they cause the channel Qi to increase its energetic movement and flow. When the tendons and fascia are calm, the channel Qi slows down.
3. The bones are the Marrow's residence. When the bones are hard, the Marrow is solid; when the bones are soft, the Marrow is hollow.
4. The bowels (Yang organs) are the viscera's (Yin organs') manifestations. If the bowels are strong, the organs become robust; when the bowels become weak, the viscera begin to fail.

Medical Qigong massage takes into consideration the function and flow of the body's tis-



Figure 37.1. The Human Body (Anterior)

sues, in conjunction with the interacting systems of the body's energetic fields, striving to regulate both systems at the same time.

TWO APPROACHES IN TREATMENT

Medical Qigong massage can be divided into two schools of treatment modalities: Surface Tissue Massage Therapy and Visceral Tissue Massage Therapy.

1. Surface Tissue Massage Therapy utilizes the Five Elemental Qi Massage Therapy techniques in conjunction with external tissue stimulation. All external tissue manipulation techniques used in Qigong massage should be light as a feather and should not exceed the pressure one would place on an eyeball. When treating with Surface Tissue Massage, the doctor's focus must be centered on the dispersion of pathogenic Qi and the expansion of the patient's Wei Qi, while softly touching the patient's tissues.
2. Visceral Tissue Massage Therapy utilizes the Five Elemental Qi Massage Therapy techniques in conjunction with deep tissue stimulation. By matching the patient's pulse frequency and respiration with that of the doctor's, a stable, energetic resonance is secured and treatment begins. When treating with Visceral Tissue Massage, the doctor's focus must be centered deep into the patient's internal organs without touching the patient's external tissues.

After external tissue massage is used to treat the patient's tissues, it is important for the doctor to maintain focused intention on the patient's channels while slowly removing his or her hands. If a break in contact with the mind's intention is made, the patient's tissues will return to their pretreatment state. Once the doctor has physically disconnected from the patient in this manner, Distance Qi Emission and Qi manipulation techniques can be applied.

It is believed that the treatment of diseases should be carried out primarily by Qi emission as the main approach, and secondarily through Qigong massage. By combining both external and internal tissue manipulation skills with energy



Figure 37.2. The Human Anatomy (Posterior)


Energetic Tissue Manipulation
Focus on a specific point
health maintenance
therapeutic point regulation
Focus on a specific area
local region treatment
general body treatment
Focus on a specific channel
health maintenance
therapeutic channel regulation

Figure 37.3. Energetic Tissue Manipulation Chart

extension techniques, the Qigong doctor greatly improves the quality of treatments. In the clinical setting, this type of energetic tissue manipulation is utilized before or after energy extension. This facilitates the relaxation of the patient's muscles and joints and the opening or closing of their points. It also aids in dredging the channels, guiding the flow of energy, and in regulating Yin and Yang energy.

TISSUE REGULATION THROUGH MEDICAL QIGONG MASSAGE

The external treatment of the patient's tissues encompasses a wide variety of body manipulation and alignment methods to provide a complete treatment program (Figure 37.3). Used for toning the organs, glands, nervous system, and joints, Qigong massage is applied to treat soft tissue injury. The following are the six treatment goals of Qigong Massage:

- To relax the tendons, activate the channels, promote circulation of Qi and Blood, and relieve pain,
- To disperse Blood stagnation,
- To relieve muscle spasms,
- To expand the tendon sheaths,
- To treat fascia in order to move stagnations and separate adhesions, and
- To correct dislocations.

The following is a list of the five predominant external tissue manipulation techniques used by Qigong doctors in China today.

THE FIVE ELEMENTAL QI MASSAGE THERAPY

Traditionally there are five different techniques for Medical Qigong massage therapy. These five techniques are very important for reestablishing the energetic vitality of the patient's body. Each of these techniques relates to a specific action and organ associated with one of the Five Elements. The objective of these techniques is to influence the muscles, nerve fibers, and deep-lying tissues of the body in order to aid metabolism and stimulate energy flow (Figure 37.4). The applications of these five methods of energy manipulation and their affect on the body's tissues are described as follows.

THE CIRCLE-TWISTING METHOD

This technique relates to the Spleen, which rules and affects the muscles, and is implemented as a quick drilling motion into the body's surface tissues, using the fingers, palms, knuckles, or heel of the palm.

When treating a patient's tissue area, a circle-twisting movement will stimulate the Qi and Blood within the channel points. This will generate a numbing and tingling sensation that will

Circle-Twisting Method	Spleen-Earth Element: affects the muscles, stimulates and improves Blood circulation.
Compression Release Method	Kidneys-Water Element: affects the bones, and regulates the Wei and Ying Qi.
Thrusting Method	Heart-Fire Element: affects the Blood, pulse, and regulates and activates the Qi.
Grasping and Shaking Method	Liver-Wood Element: affects the tendons, ligaments and muscles, promotes, clears, and activates Qi flow, and balances the Yin and Yang energy.
Tapping Method	Lungs-Metal Element: affects the Qi and skin.

Figure 37.4. The Five Elemental Qi Massage Methods

cause the channel points to induce the energy to counterattack the foreign invasion of Turbid Qi and disease. The circle-twisting action will also stimulate and improve Blood circulation and is divided into two modalities of treatment:

- To stimulate, massage the area in a clockwise, spiraling, circular motion from the outside to the center of the point. The purpose of this action is to gather energy from the surrounding areas of the patient's body and collect it into the center point the doctor is treating.
- To sedate, massage the area in a counterclockwise, spiraling circle from the center of the point outward. The purpose of this action is to disperse the energy from the area the doctor is treating. This Excess energy will later be either moved into other organs, or dredged outside the patient's body through an adjacent channel (Figure 37.5).

THE COMPRESSION RELEASE METHOD

This technique relates to the Kidneys, which rule and affect the bones, and is performed by the doctor extending his or her intention into the patient, softly pressing the body's surface tissues, using the whole palm, parts of the fingers, or elbows. The Compression Release method is commonly used to purge or drain the tissues of pathogenic Qi.

The Compression Release techniques are generally used to regulate the Ying and Wei Qi, which travel along the channels and collaterals. Deep pressure reaches the Ying Qi, while shallow pressure stimulates the Wei Qi. Once damage has occurred in the body, the damaged channel points and organ regions cause certain changes in the Wei Qi, Ying, Qi, and Blood areas of the body, resulting in numbness, aches, pain, swelling, etc. Both Circle-Twisting and Compression Release techniques can eliminate these symptoms and create a more stable energy flow.

The Compression Release Technique

Once the proper hand posture and area to be treated has been selected, the doctor guides Qi into his or her palm and fingers using Hot, Cold, vibrating, or spiraling energy. The doctor then initiates a rhythmic compression over the patient's tissues stimulating the patient's energetic field. This action has the function of relieving stagnation or congestion and can be used to dredge the



To sedate, purge, or disperse, move the energy in a counterclockwise direction.

To stimulate, tonify, or gather, move the energy in a clockwise direction.

Figure 37.5. Circle Twisting Method of Energy Therapy

channels and energetic points, as well as to relieve muscle spasms and physical pain.

The doctor must apply the correct amount of pressure for the patient's physical condition:

1. A slow Compression Release method is applied to any kind of hyperactive illness, nervous system disorder, mental disorder, or loss of Blood.
2. A medium Compression Release method is applied to illness for Spleen and Stomach disorders.
3. A fast Compression Release method is applied to hypoactive or Cold illnesses.

It is important to note that when applying the Compression Release method to tonify a specific area, the doctor should energetically press on the channel at a forty-five degree angle, slightly above where the channel flows into the injured area. This augments the flow of energy along the channel.

To disperse or drain a particular area, the doctor should apply slight pressure at an angle past where the channel flows into the injured area. This downward pressure will cause the energy to flow away from the injury. This application is used when treating Excess conditions.

THE THRUSTING METHOD

This technique relates to the Heart, which rules and affects the Blood and Blood pulses. It is utilized to gently push the tissues, extending the Qi and Blood along the patient's surface channels, using the thumb, ball of the thumb, or heel of the palm. The thrusting method can draw energy into a Deficient area or move Qi out of an Excess area.

The Thrusting Technique

Once the proper hand posture and area to be treated has been selected, the doctor guides Qi into his or her palm and fingers using Hot, Cold, vibrating, or spiraling energy. The doctor then rubs lightly or lightly touches above the patient's tissues while simultaneously emitting Qi.

The technique should be synchronized with the frequency of the patient's pulse and respiration. The Thrusting technique has the function of regulating and activating the patient's Qi, alleviating pain, and dredging the channels.

THE GRASPING AND SHAKING METHOD

This technique relates to the Liver, which rules and affects the tendons. It is administered by lightly vibrating the skin (gently at first, then slowly increasing the intensity). The Grasping and Shaking method sends a wave of vibration throughout the patient's body, and is used to increase Qi and Blood flow to the tissue area.

The Grasping and Shaking Technique

Once the proper hand posture and area to be treated has been selected, the doctor guides Qi into his or her palm and fingers using Hot, Cold, vibrating, or spiraling energy.

The doctor then lightly grasps and shakes the energetic field within the patient's tissues, while extending energy. The Grasping and Shaking technique is used for directing Qi to flow with or against the natural currents in the body's channels. It promotes, clears, and activates the channels and flow of Qi, relaxes the muscles and tendons, and balances the Yin and Yang energy.

THE TAPPING METHOD

This technique relates to the Lungs, which rule and affect the Qi and skin. This technique is administered by lightly and rhythmically tapping the patient's skin (with varying degrees of force), using the fingers, palms or fists (Figure 37.6). The Tapping method sends a pulsating ripple throughout the patient's tissues and is used to disperse stagnation from a point, channel, or organ.



Figure 37.6. In the Massage Tapping Method, the Qigong doctor will extend his or her intention deep into the patient's tissues in order to stimulate the channel point.

YIN AND YANG ENERGETIC POINT MANIPULATION

Before treating patients with Five Elemental Regulation therapy, the Qigong doctor should be aware of the principals of Yin and Yang energetic polarity involved within the Energetic Point Manipulation. This method of treatment is used to regulate the patient's Wei Qi, Ying Qi, and Qi and Blood systems (as a whole), in order to form a governed systemic balance. In the Energetic Point Manipulation methods, the treating techniques are directly based on Yin and Yang theory.

THE YIN THEORY OF QI MANIPULATION

This technique is expressed as a passive, quiet, or motionless action (more energy and less physical movement). The energetically passive Yin movements are used to push, fill, or tonify the patient's Righteous Qi, located within the patient's tissues. It is used for treating external tissue conditions and for internal organ conditions.

- If the external tissue area is in an inactive or Yin state, apply a Yin technique. Treat a Cold area with soft, passive manipulations, while extending the mind superficially onto the patient's surface tissues to fill or tonify anti-pathogenic factors, and to revitalize the Deficient area.
- If the internal organ area is either in an active or Yang (Hot or hard) state, the doctor must apply a Yin, passive, or slow action technique, while extending his mind deep into the patient's tissues and organs.

THE YANG THEORY OF QI MANIPULATION

This technique is expressed as an active technique, in motion. The active energy of the Yang movements are generally used to pull or purge pathogenic factors. It is used for treating external tissue conditions and for internal organ conditions.

- If the external tissue area is in an active or Yang state, apply a Yang technique (treating an External Hot or hard area with fast dredging manipulations) while extending the mind superficially onto the patient's surface tissues. This is done to pull or purge pathogenic factors, or break up the stagnation.
- If the internal organ area is either in an inactive or Yin (Cold or flaccid) state, the doctor must apply a Yang, quick, or active technique, while extending his or her mind deep into the patient's tissues and organs.

This combination of movement (Yang) and non-movement (Yin) is embodied in both the Circle-Twisting and Compression Release Methods of the Five Elemental Regulation Techniques.

APPLICATION FOR YIN AND YANG TECHNIQUES

The following text gives examples of specific Yin or Yang hand techniques, and when to apply them:

1. The Qigong doctor uses Yin hand techniques for tonifying, filling and pushing Qi and

Blood through the patient's organs, tissues, and channels. The Yin hand actions are demonstrated through slow or inactive hand movements.
2. The Qigong doctor uses Yang hand techniques for sedating, purging, and pulling Qi and Blood. The Yang hand actions are demonstrated through fast or active hand movements.

YIN AND YANG TREATING METHODS

The following text gives examples of specific Yin or Yang hand treatment methods, and when to apply them:

1. When a patient's tissues are in an Excess Yang state (Hard or Hot), the Qigong doctor sedates the area with counterclockwise rotations, leading the Excess energy from inside the tissue area out of the body.
2. When a patient's tissues are in a Deficient Yin state (Flaccid or Cold), the Qigong doctor tonifies the area with a clockwise rotation, to bring energy into the Deficient tissue area.

TREATING THE TISSUE AREA OR ENERGETIC POINT

In treating the patient's surface tissue area or specific energetic points, some Qigong schools teach that with a male patient, one should begin with points on the left side, then on the right side; whereas for female patients, one begins working on the points on the right side of the body, then on the left.

DEEP AND SHALLOW PRESSURE

Energy compression (deep or shallow) is controlled by the doctor's release. A deep compression relates to the Ying Qi, while a shallow compression pertains to the Wei Qi. This Compression Release technique affects the body's Blood and vital energy harmony. It seeks to balance the body's energy by preventing the Qi from flowing in the wrong direction. This technique also leads the pathogenic Qi outside the patient's body and is commonly called "The Dispersing Evil Qi Technique."

If stagnant energy remains in the center of a channel point, then the doctor must employ a Compression Release method. The compression causes the channel point to contract, leading it toward a calm, stable state. When the doctor releases the compression on the channel point, it expands and becomes stimulated into an active state.

THE GRADUAL ENERGETIC PENETRATION OF TISSUES

When treating a patient with External Tissue Regulation, there should always be a gradual penetration of energy permeating the patient's tissues. The Qigong doctor first sinks his or her focused intention onto the patient's surface tissues. The intention is then slowly sunk deeper, first into the patient's muscles and inner fascia, then into the bones or internal viscera.

At no time should pressure damage the tissues or compound pain. Treatment or pressure time at each area or energetic point should not be excessive. To establish the correct amount of pressure, determine the normal energetic pulsation in accordance with the Five Elemental Qi Massage methods, then decide if the technique is to be light, medium, or heavy.

ADDITIONAL GUIDELINES

The following are specific guidelines of Qigong massage treatment methods, and when to apply them:

1. Before beginning Qigong massage, the patient must be comfortable and relaxed. Otherwise the patient's body will not be receptive to the tissue stimulation or Qi emission.
2. When first touching the patient, the touch should be slow, as if the doctor is dipping his or her hand to test the water. The movements should have an established rhythm.
3. The doctor should never hold his or her arm, or the patient's arm, rigid or fully extended; the elbows should always be bent to some degree.
4. A symptom or damaged area occurring on one area or point at the extremity of a channel may be effectively treated by stimulating the point at the opposite end of the channel (see Magic Square, Chapter 31).
5. Points which are painful with light pressure

are in a state of Yang and need to be purged and sedated.

6. Points which are painful to deep pressure are in a state of Yin and need stimulation.
7. When an organ is functioning normally, it should receive weak, short stimuli that will increase the function, action, and energetic potential of the organ.
8. Cool skin over a point or channel indicates a Deficiency in that channel and should be tonified.
9. Hot skin indicates Excess Qi accumulation. It also indicates a current or pending illness in an organ, or area associated with that channel, and should be purged immediately.

SECTION IX

MEDICAL QIGONG EXERCISES AND PRESCRIPTIONS

CHAPTER 38

INTRODUCTION TO MEDICAL QIGONG PRESCRIPTIONS AND REGULATION EXERCISES

HISTORY OF MEDICAL QIGONG PRESCRIPTIONS

Many of the earliest known Medical Qigong prescriptions were derived from the movements of animals. Dating back to the second century B.C., the Qigong Classic (Dao Yin Tu) illustrates, in manuscripts written on silk, over 45 Qigong postures with descriptions of the movements as well as the names of the diseases which they treat. Over half of these illustrated postures are animal movements.

In the ancient Chinese text called the *Spring and Autumn Annals*, it is written, "Flowing water never stagnates, and the hinges of an active door never rusts. This is due to movement. The same principle applies to the body's Jing and Qi. If the body does not move, Jing does not flow. When Jing does not flow, Qi stagnates." The soft flowing movements in the Medical Qigong prescription exercises enhance and increase the flow of the body's Qi and Blood.

THE FUNCTION OF MEDICAL QIGONG PRESCRIPTIONS

When a disease develops, certain active points of the disease correspond to different organs, muscles and limbs of the body, and a pathological reflex is formed. Trigger and reflex points which are painful to touch are perfect examples of this phenomenon. The cerebral cortex can be inhibited in specific ways by regulating the Mind and entering a state of tranquility through Medical Qigong prescriptions, thus overriding the pathological reflex pattern, allowing the body time to heal.

Although acupuncture and herbs can, in addition to relieving pain, move Qi, Blood, and Phlegm (the roots of the disease), they fail to address the patient's life-style which is often a major contributing factor. Problems such as stagnation, Excess or Deficient conditions are often exacerbated by a patient's sedentary life style. A responsible doctor of Medical Qigong therapy addresses this particular element by prescribing physical therapy, exercise, and meditations as part of the overall treatment strategy.

Tonify	Deficient Conditions	Color Visualizations
Purge	Excess Conditions	Sound Resonations
Regulate	Yin and Yang	Qigong Massage

Figure 38.1. Medical Qigong Treatments

The standing rule for treatment in Medical Qigong prescriptions is to:

- Tonify the Deficient organs and organ systems with color visualization, by using the Mind's intention to focus on moving Qi into a Deficient organ, strengthening, thus illuminating its tissues;
- Purge the Excess organs and organ systems with sound resonation, by using the Mind's intention to focus on moving the Qi out from an Excess organ, resonating, and draining its tissues;
- Regulate the body's Yin and Yang organs and organ systems with Qigong massage, by using the Mind's intention to balance the energetic fields by moving the Qi up and down, right and left, and inside and outside of the tissues (Figure 38.1).

The therapeutic effects of Medical Qigong meditations and prescriptions are designed to move Qi and Blood stagnation, to tonify the internal organs and organ systems, and to enhance the autonomic nervous system. These prescriptions stimulate the patient's body, thereby gradually eliminating fatigue, as the normal body functions are restored. Another important aspect of the Medical Qigong meditations and prescriptions is the enhancement of the body's immune system functions.

MEDICAL QIGONG AND THE IMMUNE SYSTEM

The many health benefits of Medical Qigong include increased white blood cell production, stabilized blood pressure, and an improved immune function. The immune system, unlike the vascular circulation system, defies a clear anatomical description. It can only be understood through its functions and interrelationships with the mind and various other parts and systems of the body, such as the lymph nodes, Spleen, tonsils, appendix, Peyer's patches (in the ilium), thymus gland and the bone marrow.

The lymph nodes contain specialized compartments - some contain B cells (B stands for Blood), some T cells (T stands for Thymus), and some contain macrophages. The tonsils likewise contain B and T cells. The appendix and Peyer's patches are components of the lymphatic drainage system, and serve as locations where the B cells mature and where antibodies are produced by the B cells. The body's T cells mature in the thymus gland.

Both B and T cells begin their life in the Liver, when the fetus is only nine weeks old. They then migrate to the bone marrow where they form precursor cells. Afterwards, the T cells migrate to the thymus and the B cells remain in the bone marrow.

The immune system utilizes two major strategies for protecting the body from an infectious disease: The Humoral Immunity and the Cell Mediated Immunity.

- In humoral immunity the B cells play the primary role, and the T cells as well as other related cells play supporting roles.
- In cell mediated immunity the T cells play the main role, while B cells and other related cells play auxiliary roles.

Both T cells and B cells are called "Lymphocytes." They are two types of white blood cells that originate in the body's bone marrow and travel in the blood and lymph circulatory system (Figure 38.2). Both T cells and B cells are concentrated in the lymph nodes, which are found in clusters near groups of veins, and are heavily concentrated under the arm pits, in the adenoids, the Spleen and in the groin area.

When B cells encounter an antigen or foreign substance, they differentiate into plasma cells. These plasma cells secrete antibodies that fight and neutralize bacteria, or coat the antigen to mark it for destruction by other components of the immune system (such as the T cells).

T cells specialize in destroying cells infected by viruses, in attacking tumors, and in rejecting transplanted organs and tissues. The T cell, after leaving the bone marrow, travels to the thymus gland where it undergoes further development before returning to the lymph and blood circulatory systems. The T cells respond to an antigen by differentiating into several kinds of T cells, three of which are of primary importance: Killer T cells (also called cytotoxic T cells), Helper T cells and Suppressor T cells. Killer T cells bind to viral antigens displayed on the surface of infected cells and destroy them. Helper T cells bind to the antigens on the surface of a B cell that has already bound itself to the antigen. Each Helper T cell then releases Lymphokines (one well know class of lymphokines is interferon), that enhance the maturation of the B cells, or signal them to differentiate and multiply into plasma cells that secrete antibodies. The Suppressor T cells function to dampen the immune response and to signal the "all clear."

A third group of important immune cells are the phagocytes. These cells are the body's natural scavengers. They engulf antigens and destroy them. Those that specialize in cleaning up the debris are called macrophages. The macrophages can also signal B or T cells to the presence of foreign material.

Another important group of cells are called Null cells, among which the N.K. or "natural killer" cells are found. These cells are able to identify tumors and virally infected cells, and kill them without having any prior encounter with such an antigen.



Figure 38.2. The Body's Immune System

A final important group consists of Mast cells. They contain powerful chemicals: heparin - an anticoagulant, serotonin - a neurotransmitter, and histamine - a biochemical released in overabundant quantities in allergic reactions.

These white blood cells live in the blood and lymph fluid, and are commonly known as the leukocytes. There are two main varieties of white corpuscles: The Polymorphonuclear Leucocyte (Polymorphs) and Lymphocyte.

- Polymorphs are found in the bone marrow stem cells; they destroy invading bacteria and remove dead or damaged tissue.
- Lymphocytes are found in the lymph glands, Spleen and thymus gland and circulate in the blood along with the polymorphs. They are the smallest of the leucocytes, and designated the lymphocyte because it is identical with the lymphoid cell derived from the lymphatic glands.

Both the white blood cells called polymorphs and lymphocytes move into the body's surrounding tissues as a part of the immune function. The purpose of these cells is to work together to defend the body from invasion of pathogenic factors. Their function is to identify, ingest, destroy and eliminate disease-causing organisms, as well as to remove any and all dead, damaged, or irregular cells.

Immune cells are produced in the lymphoid tissue and red bone marrow, and are stored in the lymphatic organs and blood. In order to perform their function of protecting and cleaning, these cells must circulate throughout the entire body. The capillaries and lymphatic vessels carry the lymph fluid through the lymph nodes and the lymphatic organs of the thymus gland, spleen, and tonsils, where the lymph fluid is filtered, cleansed of impurities, and infused with new lymph cells.

In order for an external pathogen to affect the body, it must first pass through the protective layers of cells. Generally, the macrophages (specialized white blood cells) present within the tissues ingest the pathogens and dead tissues. This action of the macrophages is reinforced by the action and movement of the Wei Qi. When a pathogenic intruder invades the body, the macrophages are the first to attack the intruder. If the macrophages are not strong enough, more blood and fluid, which contain more immune cells, are brought to the area. The increased fluid engorges the tissue, and brings more cellular activity. The increased


The Body's Immune System
Congenital Immunity Established Through:
1. Antibodies passed from mother to fetus via the placenta
Acquired Immunity Established Through:
1. Antibodies passed to the infant during breast-feeding
2. Infection (contact with pathogen)
3. Injection of immune serum (gamma globulin)
4. Injection of vaccine (dead or attenuated pathogens)

Figure 38.3. Congenital and Acquired Immunity

blood and cellular metabolism increases the local temperature. The immune cells try to break down and ingest the pathogen, creating a process which continues until the disease is eliminated.

Once the battle is won, some of the Killer T cells and Helper T cells will remain circulating in the blood and lymph circulatory system as Memory cells that will be able to deal more efficiently with any future antigen of the same kind. Likewise, some of the mature B cells will also become Memory cells that hover around lymph nodes which they use as a base of operation.

Because Qigong movements generate heat and soften the body's connective tissues, this encourages the flushing of the intercellular fluid throughout the body's tissues and organs. When combined with Breathing, Mental, and Postural Qigong exercises, the entire body is affected. These energetic Qigong actions increase oxygenation of the blood and improve circulation, thereby enhancing lymphocyte production and strengthening the body's immune system.

CONGENITAL AND ACQUIRED IMMUNITY

The body has two ways of establishing or maintaining its immune functions: Congenital Immunity and Acquired Immunity (Figure 38.3).

- Congenital Immunity (Prenatal) is established during gestation, through antibodies that are passed from the mother to the fetus via the placenta.
- Acquired Immunity (Postnatal) is established in the following ways: immediately after birth during breast-feeding (through the colostrum-mother's first milk), through contracting an infection (contact with external pathogens), the injection of an immune serum (gamma globulin), and the injection of vaccines (dead or attenuated pathogens).

Due to the importance of establishing a strong immune system within the body's Prenatal Jing, Traditional Chinese Medicine strongly endorses fetal education, instruction on diet and nutrition, maintaining emotional well-being during pregnancy, and Qigong exercises specifically designed to enhance the child's Prenatal Essence, Energy, and Spirit.

OVERVIEW

One specific goal of Medical Qigong treatments, exercises and meditations is to activate and strengthen the immune function. Qigong therapy can be used to not only strengthen the metabolism of the organs and cells, but also increase cellular energy, thus making the immune system stronger.

In China, even though the lymphatic function itself was unknown and unnamed, its effects were



Medical Qigong Self-Regulation Therapy

1. The patient is taught to increase self-awareness.
2. The patient is taught to cleanse and purify his or her energetic field.
3. The patient is taught to strengthen and recharge his or her body.
4. The patient is taught to circulate the Qi internally and externally throughout the body's entire energetic structure.
5. The patient is taught to dissipate any Excess Qi from the body.

Figure 38.4. The Five Stages of Healing Transitions That Occur Through Self-Regulation Therapy

generally ascribed to the proper action of the Qi and Body Fluids. Therefore, elaborate methods for generating and circulating lymph were developed, and faithfully practiced through Qigong. Breath, movement and postural modification as well as meditations have specific effects on the circulation of the lymph and therefore enhance the overall function of the lymphatic system.

THE FIVE STAGES OF HEALING

When practicing Medical Qigong exercises and meditations, there are five basic stages of healing transitions which occur through self-regulation therapy (Figure 38.4).

1. The patient is taught to increase his or her awareness of the body (physically, mentally, and emotionally) and its current condition.
2. The patient is taught to cleanse and purify the body's energetic fields to rid it of Qi stagnations and toxic pathogenic factors.
3. The patient is taught to strengthen and recharge his or her body to replenish the Qi.
4. The patient is taught to circulate the Qi internally and externally throughout the body's entire energetic structure, thus moving any stagnant Qi and strengthening the body.
5. The patient is taught to dissipate any Excess Qi from the body by way of self-massage (lightly brushing the skin to release stagnant Qi).

THE THREE CATEGORIES OF MEDICAL QIGONG PRESCRIPTIONS

The Medical Qigong prescriptions are divided into the same three categories (or goals) used in Medical Qigong therapy: tonification, purgation and regulation. These three goals are achieved through both Dynamic and Quiescent Qigong exercises, meditations, prayers, and mantras. These prescriptions enable the patient to reinforce the treatments performed by the Qigong doctor, and prevent the patient's energy from reverting back to old destructive patterns.

The Qigong doctor selects the proper Qigong prescription to fit the patient's illness (to Tonify, Purge, or to Regulate) and formulates a rational program that suits the patient's case. The patient should never be allowed to practice at random, otherwise pathological changes or Qi deviations may occur.

The following are but a few examples of Qigong prescriptions, which are interchangeable, as there are certain variations of purging exercises that can be modified and used for tonification and visa versa.

QIGONG PURGING EXERCISES

Qigong Purging exercises are practiced by the patient to detoxify pathogenic Qi. Some examples are already presented in this textbook are:

- Channel Purging exercise (Chapter 15)
- Cleansing the Body meditation (Chapter 12)
- Dry Crying meditation (Chapter 53)
- Energy Melting meditation (Chapter 18)
- Internal Organ Sound Therapy exercises (Chapter 4 and Chapter 40)
- Old Man and Tide Pool meditation (Chapter 40)
- Pulling Out The Pain meditation (Chapter 28)
- Releasing Emotional Blockages and Energetic Armoring meditation (Chapter 18)
- Sun and Moon meditation (Chapter 18)
- Tumor and Cancer Tone Resonating exercises (see Chapter 40)

QIGONG TONIFICATION EXERCISES

Qigong Tonification exercises are practiced by the patient to strengthen and stabilize the internal organs and organ systems. Some examples are already presented in this textbook are:

- Channel Point meditations (Chapter 36)
- Color Visualization meditations (Chapter 4)
- Cultivating Yuan Qi meditation (Chapter 50)
- Daoist Five Yin and Yang Organ exercises (Chapter 42)
- External Qi Cultivation meditations (Chapter 41)
- Gaining Wisdom meditation (Chapter 49)
- Gathering Energy from the Five Planets meditations (Chapter 11)
- Gathering Moon Cream meditation (Chapter 11)
- Gathering Sun's Essence meditation (Chapter 11)
- Gathering Qi from Mountains, Valleys, and Deserts (Chapter 12)
- Gathering Qi from The Four Directions (Chapter 12)
- Gathering Qi from Trees, Bushes, and Flowers (Chapter 12)
- Improving the Intellectual Facilities meditation (Chapter 49)
- Internal Qi Cultivation meditations (Chapter 41)
- Nei Guan - Inner Viewing Meditation (Chapter 25)
- One Through Ten meditation (Chapter 26)
- Opening and Closing the Three Dantians exercise (Chapter 41)
- Organ Massage exercises (Chapter 39)
- Qigong Walking exercises (Chapter 15)
- Seeing Auras meditation (Chapter 25)
- Soul Retrieval meditations (Chapter 19)
- Tian Wu Zang meditation (Chapter 11)

QIGONG REGULATION EXERCISES

Qigong Regulation exercises are practiced by the patient to balance their Yin and Yang, as well as their internal organ energy. Regulation exercises usually follow Tonification or Purgation exercises, because the goal is to reestablish balance. Some examples already presented in this textbook are:

- Exchange of Fire and Water meditation (Chapter 18)
- Gathering Qi in the Upper and Lower Dantians (Chapter 41)
- Microcosmic Orbit meditations Chapter 41)
- Opening and Closing the Three Burners (Chapter 41)
- Opening and Closing the Three Dantians exercise (Chapter 15)
- Pulling Down the Heavens (Chapter 41)
- Qigong Self-Healing massage (Chapter 41)
- Taiji Ruler exercises (Chapter 18)
- Wu Zang meditation (Chapter 28)

CHOOSING PRESCRIPTIONS ACCORDING TO THE PATIENT'S QI CIRCULATION

When prescribing Medical Qigong prescriptions, the priority is to get the patient to move and circulate the Qi and Blood superficially and deeply within the body. According to Chinese physician, Professor Yan De-xin, the motion and quality of Blood flow in young and middle-aged patients is different from that in the elderly, which should be kept in mind when prescribing exercises.

- When prescribing Medical Qigong therapy for young patients, use mostly Dynamic and some Quiescent Qigong regulations.
- When prescribing Medical Qigong exercises for both adolescent and middle aged patients, it is important to increase Yin Qi cultivation while maintaining and storing the patient's Yang Qi.
- When prescribing Medical Qigong for senior citizens, focus is placed on Quiescent Qigong, with a minor emphasis on Dynamic breathing exercises, depending on their age and constitution.
- When prescribing Medical Qigong therapy for patients with very weak health or constitution, the doctor should prescribe mostly Quiescent Qigong regulations to start with.
- When prescribing Medical Qigong therapy for senior citizens with a strong constitution and health, the doctor can prescribe Qigong regulations that increase Yin Qi cultivation while maintaining and storing the patient's Yang Qi.

MEDICAL QIGONG PRESCRIPTIONS FOR GENERAL SYNDROMES

The following are some examples of the proper application of Dynamic and Quiescent Qigong prescriptions as presented by Dr. He Si Hai of the Zhe Jiang Qigong Hospital in China:

1. For Excess and Heat Syndromes it is recommended to prescribe static (quiescent) Medical Qigong exercises. After the gradual decline of the patient's fever or disease, the Qigong exercises are gradually increased in numbers and duration, and the purging training method is added (provided they have not excessively consumed their constitution).
2. For Deficiency and Cold Syndromes it is recommended to prescribe Dynamic Medical Qigong exercises. Gradually increase the exercises to include methods of lifting the limbs. If however, the pathological state is more serious, then static exercises are prescribed first.
3. For Cerebral Hemorrhage, have the patient practice static exercises such as the Hibernation Breathing exercise (quiescent lying posture, see Chapter 15) while combining it with the Yongquan (Kd-1) purging exercise (once the patient has regained consciousness). Dynamic Medical Qigong exercises that use methods of passing, circulating, or distributing Qi through the head are forbidden.
4. For Cerebral Embolism combine the training methods to include exercises that accelerate Blood flow and strengthen the function of the limbs as well as quiescent tonifying methods.
5. For Malignant Tumors (in a state of non-diffusional transference, in situ), combine an effective Dynamic exercise with a Quiescent exercise. Some examples of non-aggressive tumors / cancers are considered energetically warm and in a non-aggressive state of transition are:

- Prostate cancer
- Cervical dysplasia
- Endometrial adenocarcinoma (uterine)
- Basal cell skin cancer
- Squamous cell skin cancer

6. For Malignant Tumors (in a state of diffusion, i.e., metastatic) prescribe Quiescent Medical Qigong exercises which are similar to the Hibernation Breathing exercise, in combination with strengthening exercises for patients with chronic diseases. Dynamic Medical Qigong exercises which accelerate the Blood flow are forbidden. Some examples of tumors that are considered energetically Hot and in an aggressive state of transition are:

- Pancreatic cancer
- Leukemia
- Cervical cancer
- Clear cell carcinoma (uterine)
- Melanoma (skin cancer)

NUMBER OF BREATHS REQUIRED IN MEDICAL QIGONG PRESCRIPTIONS

Each Medical Qigong treatment will generally last up to three days. The Medical Qigong prescriptions that the doctors gives their patients will extend the treatment's effects indefinitely, providing the patients do all their homework.

The number of breaths required to Regulate the patient's Yin and Yang energy in a Medical Qigong prescription is often calculated in respiratory cycles, and on the basis of the number of the Yin and Yang aspects of diseases. This is often determined by the Yin and Yang energy numbers. Yang energy is represented by all the odd numbers (1, 3, 5, 7, 9, etc.). Yin energy is represented by all the even numbers (2, 4, 6, 8, etc.). These numbers are related to the Five Elements (Figure 38.5). For example: 6 is the number of the Kidneys, 7 the Heart, 8 the Liver, 9 the Lungs, and 10 the Spleen (Figure 38.6). The cycles of Yin and Yang numbers can be implemented through the utilization of the Magic Square (see Chapter 31).

The Yang number is used to calculate the respiratory cycles for Tonification and Purgation of the Yang channels; likewise, the Yin number is used for the Yin channels. This calculation should only be used as a general reference guide in treatment. Clinically, respiratory cycles should be determined based on the location and nature of the disease (if it is Yin or Yang, Exterior or Interior, Deficient or Excessive). The primary goal for using respiratory calculations is to ensure that sufficient Qi is administered when applying Medical Qigong treatments and therapeutic prescriptions. A disease due to a Deficiency of Yin, for example, should be treated with a tonification method for 18 or 64 respiratory cycles. To treat a Deficiency of Yang, a tonification method is used by the patient for 24 to 36 breaths.

	General Treatment	Moderate Treatment	Strong Treatment
Yin	6	18 or 36	64
Yang	9	27 or 49	81

Figure 38.5. Number of Yin and Yang Respirations

5 Yin Organs	Kidneys	Heart	Liver	Lungs	Spleen
Number of Respirations	6	7	8	9	10
Element	Water	Fire	Wood	Metal	Earth

Figure 38.6. Yin and Yang Five Element Respiration

CHAPTER 39
SPECIFIC ORGAN SELF-MASSAGE PRESCRIPTIONS

INTRODUCTION

The next few chapters of this book include some of China's most popular clinical therapies. It is the author's sincere desire to educate the reader as to the diversity, yet effectiveness of these prescriptions. It is important to remember that it is not necessarily the exercise or prescription's history that matters, what does matter is the initial goal of the prescription (whether to purge, tonify, or regulate) and the correct posture, breath, and mental focus.

This section begins with energy massage techniques, which are prescriptions that require the patient to regenerate his or her own body energy for self-healing, cultivation, and circulation. These exercises are designed to purge, tonify and regulate the Five Yin Organ System. They are not arranged in any particular order, and can be singled out by the doctor and given to patients for specific ailments. Each massage prescription is named after the organ it stimulates. For clinical therapy, perform these exercises three to five times a day.

HEART MASSAGE

The doctor can chose to give the patient either the One Through Four meditation (1-fun, 2-shoe, 3-tree, 4-core; from Chapter 26), or the Stacking the Bones meditation (described below) to prepare for the following meditations.

1. Begin in a Wuji posture to perform the Stacking of the Bones meditation. Imagine the energy in your body sinking and melting into the ground; the bones vertically stack, one by one, on top of each other. Each of the body's articulations stacks on top of the next section of bone, from the bottom of the feet, ankles, knees, etc., to the top of the head.

   The spine is kept straight but relaxed, the anal sphincter is closed, the tongue is touching the top of the upper palate, the Mingmen is slightly pressing towards the back, and the body is completely relaxed.



Figure 39.1. The patient uses the mind's intent to regulate the Qi of the Heart.

2. Perform the Heart Regulation. When prescribing these exercises for male patients, have them place the left hand over the Heart with the right hand on top of the left hand (for women, the hand positions are opposite, and the beginning placement of the hands is below the left breast). Massage in twelve circular rotations clockwise to the left, then twelve rotations counterclockwise. The hand can either lightly touch the skin (using Qi massage), or be slightly off the skin, up to several inches away from the patient's body (using Qi Distance therapy), depending on the degree of energetic sensitivity and projection skill (Figure 39.1). Focus the mind's intention on the Heart organ, allowing the energy within the Heart area to flow and circulate with the movement of the hands.



Figure 39.2. Pulling Down the Heavens allows the patient to sink the Qi, returning the excess energy back into the Lower Dantian.



Figure 39.3. Exhaling and Opening the Lower Dantian allows the body to expel the Evil Qi from the internal organs. Expand the abdomen.

The purpose of the rotating action of the Heart's Qi is for promoting Blood circulation and dispersing Blood Stasis, while dredging the channels and collaterals.

3. Perform the Point Respiration. This technique focuses breathing and imagination into the channel points for the specific treatment area. For this particular exercise, the patient should leave the hands over the Heart, while concentrating the focused intention and breath deep into the tissue of the organ. The patient should then exhale while lightly squeezing and pressing the area of the Heart, and imagining divine healing light radiating outward from the tissues. While inhaling, the patient should lift the hands away from the body and imagine divine healing light flowing into the Heart organ area. This action is similar to that of a bellows. This exercise should be performed twelve times, then lead the Qi down into the Lower Dantian.
4. Perform the Pulling Down the Heavens method. Inhale, pause, then exhale while slowly bringing the arms down the center line of the torso, while quietly drawing the energy back down into the Lower Dantian. When lowering the arms, imagine the energy of the Heart like water, melting and flowing down the torso.

   Pause for a breath at the Lower Dantian, rooting the energy. Then slowly raise the hands above the head, while inhaling. Exhale slowly and imagine the energy in the arms and head melting down the body, beginning at the top of the head and tips of the fingers, flowing down and into the Lower Dantian.

   This action is important, because if the Qi is not brought back into the Lower Dantian after each exercise, the energy will be easily dispersed (Figure 39.2).
5. Perform the Opening and Closing of the Lower Dantian. Finally exhale and imagine the Evil Qi being expelled through the mouth. As you exhale, separate both of the hands away from the abdomen (as you contract the abdomen). This is called the Opening (Figure 39.3).

   After completing the Opening of the Lower



Figure 39.4. Inhaling and Closing the Lower Dantian allows the body to seal itself from outside pathogenic factors. Contract the abdomen.

Dantian, inhale through the nose while bringing both hands back to face the Lower Dantian (as you expand the abdomen). This action is called the Closing. When Closing, imagine sealing the body in a protective energetic field, so that the pathogenic factors cannot get inside (Figure 39.4). Perform the Opening and Closing method three times.

Note: The techniques 1 through 5 are one complete set. Perform a total of three sets. Three sets are necessary because the body will naturally progress through three stages. The first time the body is introduced to a new pattern it will shock the system. The second time the body begins to understand the pattern. The third and final time the body recognizes and accepts the changes the patient is attempting to reprogram.

LIVER MASSAGE

1. Begin from a Wuji posture and perform either the One Through Four or Stacking the Bones method as described in Heart Massage (1).



Figure 39.5. The patient will focus their mind's intent on the Liver area while massaging, allowing their energy to circulate into the organ's tissues.

2. Perform the Liver Regulation. Place the left hand on the Liver with the right hand on top (opposite for women). Massage in twelve circular rotations to the left in a clockwise direction, then twelve rotations in the opposite direction. When massaging, focus the mind on the Liver. Inhale and imagine divine healing light coming down from the Heavens and filling the Liver. Exhale and purge the Liver of Turbid Qi through the mouth.

   The purpose of this exercise is to smooth and regulate the activities of the vital energy flowing inside the Liver, encouraging the hyperactive and Rebellious Liver Qi to flow downward (Figure 39.5).
3. Perform Point Respiration with both hands still over the Liver, for twelve breaths, as described in the Heart Massage (3).
4. Perform Pulling Down the Heavens by leading Qi down into the Lower Dantian, as described in the Heart Massage (4).
5. End with Opening and Closing method as described in the Heart Massage (5).



Figure 39.6. The patient focuses the mind's intent on the Lung area while massaging, allowing the energy to circulate into the organ's tissues.

Note: The techniques 1 through 5 form one complete set. Perform two more sets for a total of three to complete the prescription.

LUNG MASSAGE

1. Begin from a Wuji Posture and perform either the One Through Four or Stacking the Bones method as described in the Heart Massage (1).
2. Perform the Lung Regulation. Place both palms on the Lungs (specifically on an injured or diseased region, if known). Massage in twelve circular rotations from the bottom, up the center to the top and then to the outside of the chest. Then massage twelve rotations in the opposite direction, from the top, down the center and to the outside. When massaging, concentrate on the Lung region. Inhale and imagine divine healing light coming down from the Heavens and filling the Lungs. Exhale and purge the Lungs of Turbid Qi.

   The purpose of this exercise is to bring Blood and Qi into the Lung area, clean and purify the inhaled breath and support the Lungs' Qi flowing downward (Figure 39.6). TB patients with pulmonary holes should concentrate on abundantly filling and expanding the vital energy in the Lungs while visualizing the Qi activating the body's cells to close the holes. If the patient is unable to visualize this, or the reaction is too uncomfortable, have the patient mentally pull the Qi downward.
3. Perform the Point Respiration with both hands still over the Lungs, for twelve breaths, as described in the Heart Massage (3).
4. Perform Pulling Down the Heavens method, leading the Qi back down into the Lower Dantian as described in the Heart Massage (4).
5. End with Opening and Closing method as described in the Heart Massage (5).

Note: The techniques 1 through 5 are one complete set. Perform two more sets for a total of three to complete the prescription.

SPLEEN & STOMACH MASSAGE

SPLEEN MASSAGE

1. Begin from a Wuji Posture and perform either the One Through Four or Stacking the Bones method as described in the Heart Massage (1).
2. Perform the Spleen Regulation. Place the left hand on the Spleen with the right hand on top (opposite for women). Massage in twelve circular rotations to the left in a clockwise direction, then twelve rotations in the opposite direction. When massaging, concentrate the mind on the energy within the Spleen area, imagining the Spleen Qi movement flowing with the movements of the hands (Figure 39.7). Inhale and imagine divine healing light coming down from the Heavens and filling the Spleen. Exhale and imagine the Spleen absorbing the divine Qi.

   The purpose of this exercise is to strengthen and increase the Spleen's function of transporting and converting Qi. This is an excellent massage for patients with splenomegaly (enlargement of the spleen) and dyspepsia (painful digestion).
3. Perform the Point Respiration with both hands still over the Spleen, for twelve breaths,



Figure 39.7. The patient focuses the mind's intent on the Spleen area while massaging, allowing the energy to circulate into the organ's tissues.



Figure 39.8. The patient will focus their mind's intent on the Stomach area while massaging, allowing their energy to circulate into the organ's tissues.

as described in the Heart Massage (3). Then move both hands to the Stomach area.

STOMACH MASSAGE

4. Perform the Stomach Regulation. Place the left hand on the Zhongwan CV-12 point at the middle of the Stomach with the right hand on top (opposite for women). Massage in twelve circular rotations to the left in a clockwise direction, then twelve rotations in the opposite direction. When massaging, concentrate on warming the Stomach area (Figure 39.8). Inhale and imagine divine healing light coming down from the Heavens and filling the Stomach. Exhale and purge the Stomach of Turbid Qi.

   This is an excellent massage for patients with thoracic depression, abdominal distention, gastritis, and gastric ulcers.
5. Perform the Point Respiration with both hands still over the Stomach, for twelve breaths, as described in the Heart Massage (3).
6. Perform the Pulling Down the Heavens method to draw the Qi down into the Lower Dantian, as described in the Heart Massage (4).
7. End with the Opening and Closing method as described in the Heart Massage (5).

Note: The techniques 1 through 7 are one complete set. Perform two more sets for a total of three to complete the prescription.

KIDNEY MASSAGE

This exercise is excellent for tonifying the Kidneys, as well as healing impotence, premature ejaculation, lumbago, lower back problems, and pelvic inflammatory disease (for PID use reverse breathing with static Qigong training).

This is an extremely important exercise for patients and for Qigong doctors to practice; it enables them to increase their Qi projection when treating patients.

1. Begin from a Wuji Posture and perform either the One Through Four or Stacking the Bones method as described in the Heart Massage (1).
2. Perform the Kidney Regulation. Close the eyes and place both hands on the back (waist



Figure 39.9. The patient will focus the mind's intent on the Kidney area while massaging, allowing the energy to circulate into and warm the organ's tissues.



Figure 39.10. The patient will focus the mind's intent on the bottom of the foot while massaging, allowing the energy to flow through the Kidney Channel into the Lower Dantian.

level), middle fingers touching the Shen Shu Bl-23 points. Focus on the Kidneys. Begin massaging twenty-four times inward, then twenty-four times outward, until the area becomes warm (Figure 39.9).

3. Perform the Point Respiration with both hands still over the Shen Shu Bl-23 points for thirty-six breaths. Exhale as you press the palms into the Kidneys, inhale as you raise the palms from the back. While inhaling, imagine divine healing light coming down from the Heavens and filling the Kidneys completely. While exhaling, imagine the Kidneys absorbing the divine Qi.
4. Perform the Pulling Down the Heavens method, drawing Qi into the Lower Dantian as described in the Heart Massage (4).
5. Perform the Opening and Closing method as described in the Heart Massage (5).

Note: The techniques 1 through 5 are one complete set. Perform two more sets for a total of three to complete the prescription, then proceed to the Closure.

6. Perform the Closure. After completing three sets of the Kidney exercise, place the right hand on the navel and the left hand on the Mingmen. Focus on gathering Heat and Qi in the Lower Dantian. Next, place the right foot on the left knee (opposite for women). With the right hand still on the Lower Dantian, place the left hand at the bottom of the right foot and gently massage the Yongquan Kd-1 point. Massage this area 100 times in a clockwise direction, then 100 times counterclockwise. When massaging the Kd-1 point, work slowly, focusing the mind's intention through the center of the palm into the center of the foot, imagining the Qi flowing up the leg into the Lower Dantian (Figure 39.10).

Note: Some Medical Qigong Clinics in China perform this same exercise while slapping the bottom of the feet (instead of using circular massage). They begin this treatment with 100 strikes on each foot for the first day, increasing an additional 100 strikes each consecutive day (not exceeding 300 strikes) until the desired result is achieved.

7. Perform the Point Respiration for twelve breaths, with the right hand still on the Lower Dantian and the left hand still on the bottom of the right foot, as described in the Heart Massage (3).
8. Switch feet, placing the left hand on the Lower Dantian while the right hand gently massages the Kd-1 at the bottom of the left foot, 100 times clockwise then 100 times counterclockwise.
9. Perform the Point Respiration for twelve breaths, with the left hand still on the Lower Dantian and the right hand still on the bottom of the left foot.
10. End with the Opening and Closing method as described in the Heart Massage (5).

Note: Do not use this ending method (5 and 10) for patients who suffer from insomnia, as it will have an awakening effect as it invigorates the vital energy. When performed at bedtime it can be used for treating insomnia by following the simple prescription below.

TREATMENT FOR INSOMNIA

This is a very famous prescription for insomnia. I have used it in my clinical practise for many years and have found it to be extremely effective. If the insomnia is due to a Deficiency of Kidneys' Yin, or the patient is restless during the night due to the Liver's Heat rising and causing the patient's mind to wander, this prescription will help. After clinically treating patients for insomnia, the Qigong doctor can prescribe the following exercise to be performed by the patient.

This exercise is to be practiced just before the patient is going to sleep. Begin by sitting at the edge of the bed, repeating the previous Kidney exercises 2, 3, and 6.

1. Perform the Kidney Regulation. Close the eyes and place both hands on the back (waist level), middle fingers touching the Shen Shu Bl-23 points. Focus on the Kidneys. Begin massaging twenty-four times inward, then twenty-four times outward, until the area becomes warm (Figure 39.9).
2 Perform the Point Respiration with both hands still over the Shen Shu Bl-23 points for thirty-six breaths. Exhale as you press the palms into the Kidneys, inhale as you raise the palms from the back. While inhaling, imagine divine healing light coming down from the Heavens and filling the Kidneys completely. While exhaling, imagine the Kidneys absorbing the divine Qi.
3. Perform the Closure. After completing three sets of the Kidney exercise, place the right hand on the navel and the left hand on the Mingmen. Focus on gathering Heat and Qi in the Lower Dantian. Next, place the right foot on the left knee (opposite for women). With the right hand still on the Lower Dantian, place the left hand at the bottom of the right foot and gently massage the Yongquan Kd-1 point. Massage this area 100 times in a clockwise direction, then 100 times counterclockwise. When massaging the Kd-1 point, work slowly, focusing the mind's intention from the Lower Dantian through the leg into the center of the foot, imagining the Qi flowing down the leg into the bottom of the foot (Figure 39.10). As the mind begins to relax, close the eyes and fall sleep. If you become fatigued, do not complete the exercise.

An explanation for the reason for this exercises success is as follows:

1. The Kidney exercise 1 and 2 will root the body's Blood, Heat, and Heart Qi back into the Kidneys and Lower Dantian, where they will become stabilized.
2. The Kidney exercise 3 will draw the body's Heat, Blood, and the Heart Qi away from the torso and Lower Dantian into the extremities of the feet, quieting the mind and causing sleep.

CHAPTER 40
HEALING SOUND THERAPY AND PRESCRIPTIONS

INTRODUCTION AND HISTORY

As early as the Qin Dynasty (221-207 BC) healing sounds have been recorded in China. For thousands of years, Qigong masters have studied occurrences in nature and in the physical body to develop a holistic approach to health and longevity. One of the many discoveries made is that all humans produce similar sound patterns in certain situations. For instance, after a tense situation many people utter a sigh of relief. This sigh is the body's way of releasing emotional stress. Specific situations will release different emotional sounds, because emotions are stored as tone resonances in the different chambers of the Five Yin Organs.

During the Sui Dynasty (590-618 AD), ancient Qigong Master Zhi Zhuan pointed out that there are six ways of expelling toxic energy from the internal organs, using the six different sounds formula. The silently spoken six sounds are coordinated with the breathing and the movements of the body's extremities to purge and cleanse the organ cavities and particular channels of stagnant Qi. These exercises are excellent for treating muscular injuries and for the Yin and Yang organs. The impure Qi produced by external pathogenic factors (from food, air, and drink) and internal pathogenic factors (toxic emotions and negative mental attitudes) will be expelled directly from each organ.

The healing sound techniques can either be used by the patient as a form of static Medical Qigong prescription (for purgation), or projected into the patient by the doctor as a clinical form of energetic stimulation (for tonification or purgation). The six words are: Xu (Shu), Ke (Haa), Hu (Who), Si (Sss), Chui (Chree), and Xi (Shee). These sounds are also used in chanting (in spiritual Qigong). Ancient documents state that these six sounds denote the Five Yin Organs as well as the five seasons.

It is important to note that there are several healing sound systems used by different Medical Qigong schools and other cultures. These sound systems all affect the body's sympathetic and parasympathetic nerves to some degree. The main emphasis, when performing any healing sound, should be placed on the connection of the mind, breath, and imagination to the area or internal organ focused on by the patient. This will reduce the potential for causing Qi deviations. The patient must have an internal image and actually hear and feel the resonating sound inside the body. It is also important that the patient feel enveloped in the sound, vibration, energy, and light of the therapeutic tone.

SOUND VOLUME RESONATION

The pronunciations of the sounds must be correct. The resonant effects of the sounds must be brought into full play to be successfully transmitted to the diseased areas of the internal organs. Therefore, it is extremely important that the patient focus the mind and intention on the area being treated. There are three volume resonations commonly used in Medical Qigong sound therapy: soft, moderate, and loud.

1. Soft volume is spiritual in its energetic nature and is related to the projection of Shen. A soft volume is generally used when beginning sound therapy treatments. With soft volume pronunciation, the patient can easily feel where the sound waves reach and acquire resonant effect, but the amplitude of the sound wave is not wide enough to produce the desired healing effects, and its vibrational force is very weak.
2. A moderate volume of sound is emotional and mental in its energetic nature and is related to the projection of Qi. A moderate volume is

considered the standard for all healing sound treatments. Moderate volume is decided by the individual's own voice. It should be limited to the range in which the patient's voice does not strain and in which the voice can be raised or lowered effortlessly.

3. Loud Volume is related to the projection of Jing. A loud volume is used to shock the patient into feeling the diseased tissue area. This is due to the fact that loud volume is more tangible (or physical) in its energetic nature. With loud volume pronunciation, the patient can easily feel the body's internal organs and tissues vibrate; however, this sound is only used to reintroduce a desensitized patient to his or her body. The problem with prolonged use of loud volume is that the increased volume is liable to create tension and cause Qi deviations.

The volume of sound uttered also depends on the patient's current state of health. People who are physically weak can usually practice the breath regulating and Qi reinforcing exercises, but should not practice the sound pronouncing method until they feel appropriately energetic.

To practice the word pronouncing method, the patient should start from the soft volume and increase it gradually. Diseases of different parts of the body require different volumes. For example:

- Patients with Heart or Lung trouble can comfortably take the soft to moderate volume pronunciation;
- Patients with Liver, Spleen, Stomach, Kidney and intestinal diseases can take the moderate to louder volume pronunciation.

HIGH-, MIDDLE-, AND LOW-PITCHED SOUND

The healing sounds have high, middle, and low pitches with different penetrating potentials. When correctly vocalized, they cause resonant vibrations in the body, producing certain states of consciousness that have both a psychological and a physiological effect on the nervous system.

As the tones change from a high to low pitch, they regulate the depth of the tone penetration. Similar to a dimmer switch on a light bulb, the tone adjusts the depth of the vibration resonance in the body.

The three pitch sounds also affect the energy movement of the body's Triple Burners, as well as the internal organs positioned within the thorax.

1. The high-pitched sound is pronounced in a straight tone with the head slightly drooped. The high pitch focuses the energy resonation into the specific organs of the patient's Upper Burner from the sternum to the manubrium. After completing the sound resonation exercise, return back to the Wuji position and relax; regulate the body using natural breathing.
2. The middle-pitched sound is pronounced in either a rising or descending tone, depending on the patient's specific conditions. The rising tone will cause the patient's Qi to ascend, while the descending tone will cause the Qi to drop. The middle pitch focuses the energy resonation into the specific organs of the patient's Middle Burner from the navel to the sternum within patient's body. Middle-pitched sounds are only prescribed for specific conditions (organ prolapse or organ energetic overload).
3. The low-pitched sound is pronounced in a dropping, then rising tone, within one breath. This causes the energetic resonation to saturate the diseased organ from top to bottom, then from bottom to top. This focuses the energy resonation into the specific organs of the patient's Lower Burner from the navel to the perineum. The method of pronouncing the low-pitched sound is usually practiced immediately after sounding the high-pitched tone.

After pronouncing either the high-, middle- or low-pitched sounds, perform the Open and Close the Three Dantians method once, then close with the Pulling Down the Heavens exercise. This completes one set.

BREATH AND MIND CONTROL

Healing sounds produce an aspirating effect analogous to vacuuming a room. This analogy describes to the patient the desired intention needed to successfully utilize this modality of healing. Toning without proper focused intention, breath, and mind control placed on the specific internal organ is like trying to vacuum a room while waving the hose in the air. Although the hose is sucking the air, it is not performing the desired result of purging the room of dust and dirt. To become proficient and establish the desired result, the individual must focus the attention and place the vacuum hose onto the specific area that needs cleaning.

Healing sound and toning therapy work the same way. It is not just sounding the tone which allows the technique to work, but the combination of the breath and mind focused on the intended internal organ. When practicing sound therapy, the patient generally uses the Natural Breathing method, along with focused intention and color visualization.

While inhaling, the patient imagines breathing in divine, white light healing energy through the nose and absorbing this healing Qi into the diseased area, vibrating it.

When exhaling, the patient imagines breathing out the dark, diseased, Turbid Qi through the mouth. It is important for patients to maintain the healing color (i.e.: green, red, golden yellow, white, or blue) vibration inside the diseased organ, even when they exhale.

SEPARATING THE BREATH INTO YIN AND YANG

The breath can be divided into either Yin or Yang qualities. When breathing shallow and focusing the mind on the front of the throat, the breath feels cool and is therefore considered Yin; however, when shifting the mind's attention towards the back of the throat, the breath, when released, feels hot, and is considered Yang. This change in temperature is due to the front of the body being Yin in nature and the back of the body being Yang.

AUDIBLE AND INAUDIBLE SOUND RESONATION

Before projecting sound therapy in a clinical setting, the Qigong doctor must vibrate the three Dantians while focusing on his or her Taiji Pole. Once the sound vibration has filled the doctor's body, the resonate healing sounds can be projected into the patient's tissues and organs.

Another way to produce sound is to imagine that the sound is appearing as a specific color and causing a vibration within the body. Clinical sound therapy is further divided into three distinct levels of emitted energies: Obvious Sound Resonation, Hidden Sound Resonation and Mysterious Sound Resonation.

1. The Obvious (Ming) Sound Resonation is audible sound. This energy sound resonation is considered Yang and is produced through the vocal organs. When toning audibly, the healing sounds fills the Qigong doctor's energetic fields. These fields can then be transferred onto the patient to produce a very strong, physical affect on the patient's tissues and organs. The Qigong doctor connects (through intention) with the patient's internal organ, and imagines his or her voice penetrating the diseased organ's tissues. The doctor then imagines the patient's tissues vibrating like rippling water with the sound exhalation, to purge the pathogenic Qi.
2. The Hidden (An) Sound Resonation is slightly audible sound. This energy sound is considered Yin transitioning into Yang, and is produced by softly exhaling sound energy resonation into the patient's body. This slightly audible energy sound resonation affects the patient's tissues and organs more on an emotional plane, enveloping and penetrating the patient's tissues like a mist.
3. The Mysterious (Hua) Sound Resonation is inaudible sound. This energy sound resonation is considered Yin and is mentally produced inside of the doctor's body. The Qigong doctor first focuses and fills his or her body and energetic field with the vibrant sound. The doctor then focuses the mind on the healing sound like a mantra. This inner sound fills the Qigong doctor's field with resonant vibration which can be transferred into the patient's body. This energy sound resonation affects the patient's tissues and organs on a more spiritual dimension, enveloping and purging like a gentle light.

The Qigong doctor can also coordinate the projection of the healing sounds with the patient's toning to synchronize their energetic fields. All sound techniques have specific postures, breathing, and mind regulations to facilitate whole body integration.

Patients and students are usually encouraged to practice the audible sound vibrations until they can vibrate the tissues of the organs at will, before they proceed to the inaudible sound resonation.

THE SIX HEALING SOUND PRESCRIPTIONS

Before starting any organ sound exercise, there are certain grounding and cleansing techniques that the patient should practice. These preparation exercises are described as follows.

1. Always begin sound resonation from a Wuji standing posture.
2. Breathe naturally from the abdomen, inhaling through the nose and exhaling through the mouth. The body should be relaxed, and respiration should be gentle, thin, even, and extended. The mind should not concentrate on the expansion of the Lungs, but on the Lower Dantian first, and then on the treatment area. Also, breath through every pore of the body into the Lower Dantian.

   Upon exhaling, sound the healing word with a low volume pronunciation, feeling where the sound waves reach. Once the tissue area is stimulated, increase the volume. At the same time draw in the abdomen, draw up the anus, slightly knead the ground with the feet, sink the shoulders, and then shift the body weight to both heels. This will access the Kidneys' Water Qi. When inhaling, close the mouth, raise the tongue against the hard palate, and shift the body weight to the anterior soles of the feet. This will access the body's Fire energy. Exhale the specific sounds through the mouth while imagining the impurities of that specific organ being expelled.
3. Pull Down the Heavens (the ending breath regulation). Inhale and exhale through the nose. When inhaling, slowly raise both arms forward and upward from the sides of the body, with both palms facing downward until reaching shoulder level. Then turn the palms up, and continue to circle the arms over the head. When exhaling, bend the elbows to make a curve in front of the chest, and press the abdomen. Then separate the arms to the sides of the legs, and return to the Wuji posture (Figure 40.1).



Figure 40.1. Pulling Down the Heavens allows the patient to sink the Qi, returning the excess energy back into the Lower Dantian.

Regulate the breath three times in the Wuji posture after completing the exercise. Breathing Regulation (Pulling Down the Heavens) is required after the exercise of each sound is completed and before the next exercise begins.

THE SOUND "XU" (SHU) NOURISHES THE LIVER

This sound relieves Liver stagnation, aids in correcting certain types of visual distortions, and purges the accumulation of Phlegm in the body (e.g., the condition of Lung Hot Phlegm, due to an already existing cold).

Both hands overlap the inner Laogong Pc-8 points, with the left hand on the outside for men (opposite hand position for women). The Shaoshang Lu-11 point of both thumbs presses against the navel, with the Laogong points pointing at the umbilicus.

When inhaling, expand the abdomen and close the eyes, feeling the breath envelop and penetrate the Liver organ. At the same time direct the Qi of the Liver's Channels to flow upward from the Dadun Lv-1 point on the lateral portions of the big toes. Visualize the Qi rising through the lower abdomen, linking the Gall Bladder to the Lungs, traveling to the throat, and eyes, to the forehead, and then to the Baihui GV-20 point.

When exhaling, contract the abdomen and release the pathogenic factors. Focus the attention and imagination on the Qi flowing down the face, to connect with the Lungs' Channels, flowing downward to the Shaoshang Lu-11 points on the medial portions of the thumbs. The Qi is then directed and rooted into the Lower Dantian. Open the eyes wide, and sound the word "Shu" (the lips are slightly brought together, the tongue tip stretches forward with the lateral sides slightly curling toward the middle). Exhale completely.

In this particular exercise, the breath should feel lukewarm as you exhale (Figure 40.2). Perform six times.

THE SOUND "KE" (HA) REPLENISHES THE HEART

This sound relieves Fire from the Heart and expels Heat from the body; it also improves poor circulation and reduces fevers. The respiration patterns are the same as those in the previous (Liver) sound prescription.

When inhaling, raise both hands to shoulder level as if embracing a post. Both palms should face each other with the arms making a curve in front of the chest. Expand the abdomen and close the eyes; feel the breath envelop and penetrate the Heart organ. At the same time direct the Qi of the Spleen's Channels to flow from the Yinbai Sp-1 point on the medial portion of the big toes, along the inner portions of the legs, upward to the abdomen to meet with the Thrusting Channels, and enter into the Heart.



Figure 40.2. The sound "Xu" (Shu) is used to purge Liver stagnation as well as to disperse the accumulation of Phlegm in the body (Lung Hot Phlegm).



Figure 40.3. The sound "Ke" (Ha) is used to purge Heart Fire as well as expel Heat from the body.



Figure 40.4. The sound "Hu" (Who) is used to treat digestive problems, by purging Stomach and Intestinal stagnation.

When exhaling, softly open the eyes and draw the Qi out from the Heart, past the Lungs, through the armpits, along the inner portions of the arms, to the Shaochong Ht-9 point on the medial portion of the little fingers. Point the fingers forward to release the pathogenic Qi, and sound the word "Ha." The mouth is half closed with the tongue placed against the lower mandible. Exhale completely. This breath should feel hot (Figure 40.3).

Return to the beginning position and perform six times.

THE SOUND "HU" (WHO) STRENGTHENS THE SPLEEN

This sound is used to correct digestive problems, especially when the Stomach or intestines feel full or sluggish.

When inhaling, raise both hands upward in front of the abdomen, as if embracing a ball in the Lower Dantian area. Both palms should face each other with the arms making a curve. Expand the abdomen and close the eyes; feel the breath envelop and penetrate the Spleen organ. Direct the Qi of the Spleen's Channels to flow from the Yinbai Sp-1 points on the medial portion of the big toes, up to the abdomen to enter the Spleen, and to link up with the Stomach.

When exhaling, the right palm turns outward, rolling over and pushing above the head, thus forming the posture of Holding the Heavens. At the same time, imagine the Qi ascending up to the throat, to the root of the tongue, and spreading under it. Imagine a secondary river of Qi flowing from the Stomach to the Heart, and ascending along the Heart's Channels to the Shaochong Ht-9 point on the medial portion of the little fingers, and exhale the sound "Who." The lips are brought together as if playing a flute, the tongue is level and stretched forward as much as possible to allow the ascending energy of the Thrusting Channels to rush out. Exhale completely while the left palm turns downward and presses down to the outside of the left hip (Figure 40.4).



Figure 40.5. The sound "Si" (Sss) is used in order to Purge the Lungs.

Next, inhale and turn the right palm over to face the body; slowly descend the right arm in front of the body, while the left arm turns towards the body and ascends. The two hands cross in front of each other (with the ascending arm on the inside, and the descending arm outside). Now the left hand pushes up and the right hand pushes down. At the same time, exhale and repeat the sound "Who." Pressing both left and right hands form one set. Perform six times. At the end, cross both arms in front of the chest and return to the beginning position.

THE SOUND "SI" (SSSS) MOISTENS THE LUNGS

This sound is used to nourish the Lungs, treat problems such as tuberculosis, abscesses, and dermatitis.

From the beginning Wuji posture, inhale and raise both hands as if holding a ball, moving it upwards, until the hands face the Shanzhong CV-17 point at the front of the chest. Direct the Qi of the Liver's Channels to ascend from the Dadun Lv-1 point on the lateral portions of the big toes, along the inner portion of the legs, through the lower abdomen into the Lungs.

When exhaling, turn over both palms to face downward, then separate the palms horizontally to the sides. Guide the Qi along the Lungs' Channels to the Shaoshang Lu-11 points on the inner portion of the thumbs, while exhaling the sound "Sss" The lips are slightly drawn back, the upper and lower teeth are slightly brought together forming a small slit; the tip of the tongue is placed against the slit in-between the teeth to articulate the sound. Exhale completely, then allow both arms to descend to the sides of the body (Figure 40.5). Repeat six times.

THE SOUND "CHUI" (CHREE) STRENGTHENS THE KIDNEYS

This sound is used to regulate the Kidneys, expel chills, and to maintain the Internal Heat of the Lower Dantian and Mingmen Fire.

Inhale and raise both arms to embrace an imaginary ball in front of the chest (Middle Dantian area).



Figure 40.6. The sound "Chui" (Chree) is used to regulate the Kidneys and the Mingmen Fire, as well as to expel chills from the body.



Figure 40.7. Massage the sides of the body.

The joints in between the thumb and index finger of both hands are stretched wide open. Lead the Qi to flow upward from the Yongquan Kd-1 points of the Kidney Channels, through the inner portions of the thighs, along the spinal column, and into the Kidneys.

When exhaling, hold the posture and stretch the fingers, while leading the Qi from the Kidneys into the chest and then to the Lungs. The channel Qi then transfers into the Pericardium Channels and flows down the arms to the Zhongchong Pc-9 points at the tips of the middle fingers. While exhaling, sound the word "Chree." The mouth is nearly closed with the corners slightly drawn back; the tongue moves forward. The breath should feel cold (Figure 40.6).

Slowly straighten the body as the hands circle downward, from the lower back to the thighs. Rub the lower lumbar region (Shenshu Bl-23 points) and the sides of the thighs (Huantiao GB-30 points), moving the hands upward while massaging the buttocks. Return to the holding the ball posture and repeat six times (Figure 40.7).

THE SOUND "XI" (SHE) REGULATES THE TRIPLE BURNERS

This sound is used to eliminate Excess Heat, for treating rheumatism, poor circulation, and problems of the Triple Burners. This exercise helps to recharge the body's Qi metabolism, regulate Internal Qi, and balance the eight systems of the body (respiratory, digestive, reproductive, circulatory, lymphatic, nervous, muscular/skeletal, and excretory systems).

The "She" sound of the Triple Burners is always prescribed for patients undergoing radiation or chemotherapy. This allows the patient to disperse the toxic Heat left within the tissues.

From a beginning Wuji posture, inhale and raise both hands as if holding an imaginary ball up in front of the chest at the Middle Dantian. Direct the channel Qi of the Triple Burner Channels in the arms to flow downward to the Lower Dantian, then down the legs via the Gallbladder Channels to the tips of the fourth toes of the feet at the Qiaoyin points (GB-44).

Exhale the sound "She," at the same time rotating both arms upward to form the Embracing the Heavens posture. The lips are slightly open and drawn back; the tongue suspends behind the teeth. When exhaling, direct the Qi to flow from the Qiaoyin GB-44 points on the outer portion of the fourth toes upward, along the Gall Bladder Channels, through the outer portions of the legs to the head, and transfer the energy flow into the Triple Burner Channels, directing it along the outer portions of the arms to the Guanchong TB-1 points at the ends of the ring fingers. Exhale completely.

Inhale, while turning the palms over to face downward, and begin lowering both arms along the front of the chest. Imagine the Qi flowing down from both arms into the Lower Dantian. Exhale without sounding "She," and press both palms down along the front of the abdomen to the sides of the hips, returning to the Wuji posture (Figure 40.8). Repeat the entire sequence six times.

This exercise is different from the others in that the energy circulates back and forth through the channels but does not disperse outside the body. Meaning you inhale Qi from fingers to toes, exhale Qi from toes to fingers and sound, inhale Qi from fingers to Lower Dantian, exhale Qi from Lower Dantian to toes, without sound, then begin entire sequence again.



Figure 40.8. The sound "Xi" (She) is used to purge Excess Heat from the body.

THE PROPER NUMBER OF BREATHS FOR HEALING SOUND PRACTICE

When practicing all six healing sounds, each sound should be practiced a minimum of three to six times before proceeding on to the next sound. If the patient wishes to practice the six healing sounds daily, the patient should perform each sound no more than twenty-four times. If the patient is practicing one or more healing sounds for a specific therapy, then the number of times for tone resonances should be thirty-six.

Practice the six healing sounds in the sequential order of the Fire Cycle (i.e., Liver, Heart, Spleen, Lungs, Kidneys, and Triple Burners) to enhance the

Yang energetic field. Practice the six healing sounds in the sequential order of the Water Cycle (i.e., Liver, Kidneys, Lungs, Spleen, Heart, and Triple Burners) to enhance the Yin energetic field.

It is advisable to practice the healing sounds at the end of a meditation practice. This is because the free circulation of Qi is already in motion and freely accessible after meditating.

COMBINING MULTIPLE ORGAN SOUNDS

The six healing organ sounds may be performed as in the prescribed series, or as individual therapies ranging from single to multiple organ sounds. Some examples are:

1. Single organ sound regulation, like the "Haa" sound for the Heart, is used followed by swallowing the collected saliva (after Qi purgation) to relieve a fast, irregular heartbeat.
2. Multiple organ sound regulations, like the sounds of "Shu" (Liver), "Haa" (Heart), and "Sss" (Lungs), are used in sequence to quench the pathogenic Fire inside the patient's body (for mild symptoms).
3. All six healing sounds are used for regulation and balance to treat "False Cold" (a feverish sensation followed by a feeling of cold all over the body). This symptom is caused by Excess Fire. The Internal Fire drives the Yin to the body's surface, thus producing the cold sensation. To treat, the Qigong doctor guides the patient's Yin Qi back to its original organs and uses all six sounds to regulate the body.
4. Sounding according to the Five Seasons will also be beneficial to the patient's Qi regulation. The five sounds are divided according to each season, and the vulnerability of each organ. They are categorized as follows:
    a. "Shu" sounding in the springtime will benefit the Liver.
    b. "Ha" sounding in the summer will benefit the Heart.
    c. "Ssss" sounding in the autumn will benefit the Lungs.
    d. "Chree" sounding in the winter, and during all seasons, will vitalize the Kidneys and harmonize Qi and Blood.
    e. "Who" sounding in all seasons helps vitalize the Spleen and regulates the function of Postnatal Qi.
5. Combining healing sounds according to the specific prescriptions is similar to taking combinations of Chinese herbs. The Six Healing Sounds may be combined in order to target specific areas on the body's energetic system. Generally, the doctor gives the patient specific healing sound combinations as prescriptions to purge stagnation, and to increase the energetic movement within the diseased tissues or organs.

    One such combination prescription used to treat overall Shen disturbances due to emotional depression, from suppressed anger, guilt or grief is called, "Old Man Searching for the Reflection of the Moon at the Bottom of the Tide Pool." In Medical Qigong Soul Retrieval, this healing sound prescription is used to bring the patient back in touch with his or her painful emotions.

OLD MAN SEARCHING FOR THE REFLECTION OF THE MOON AT THE BOTTOM OF TIDE POOL

This particular exercise was introduced into the United Stated in the early 70's by Dr. Her Yue Wong. Doctor Wong believed that after the Qigong student has spent a sufficient amount of time practicing the Five Elemental Daoist Qigong tonification exercises, his or her deep seated emotions will begin to surface and must be purged from the body. In order to purge the toxic emotions, this healing sound prescription was given:

1. Begin this exercise prescription from a standing posture. Both feet are facing forward, shoulders width apart. Inhale, and imagine divine healing light filling the Lungs. While inhaling, separate and stretch both arms to the sides of the body, forming the shape of a "T" (Figure 40.9).
2. Lean over and begin to exhale, making the "Sh-h-h-h" sound. While exhaling imagine Toxic Qi from both Lungs flowing down each arm and pouring into the ground. Both arms should swing from one side to the other, crisscrossing



Figure 40. 9. Old Man and Tide Pool (a)



Figure 40. 10. Old Man and Tide Pool (b)



Figure 40. 11. Old Man and Tide Pool (c)



Figure 40. 12. Old Man and Tide Pool (d)

while making the purging sound (Figure 40.10).

3. Return to an upright position, while inhaling and imagining divine healing light filling the chest (especially the Heart, Liver and Spleen areas). When inhaling, look upward and raise the hands over the head (Figure 40.11).
4. When exhaling, both hands should descend to shoulder level, making soft fists (as if embracing two sparrows). Focus the mind's intention on the center of the chest and imagine the Toxic Qi releasing from the Heart while making the "Haa-a-a-a" sound. Exhale only half of your breath. Next, exhale the second half of your breath while imagining Toxic Qi releasing from the Liver and Spleen and making the "Who-o-o-o" sound. While exhaling, move both hands down to the hips while keeping the fists soft (Figure 40.12). Repeat the last two steps (c. and d.) three times. This equals one set. Practice 36 sets to complete the exercise. It should take about 25 minutes.

There is an story associated with this ancient healing sound prescription; it is described as follows.

One night, on a full moon, an old man on the southern coast of China, went looking for sea crustaceans to feed his family. Holding his lamp upward, he gazed down and saw a large beautiful pearl at the bottom of a tide pool. "Oh My!" He exclaimed, as he quickly placed his lamp on a rock. "Look at the size of that pearl! With a pearl that large, I'll be able to retire! Even my family won't have to work, and we'll all live in the lap of luxury for the rest of our lives!"

So the old man stretched his hands wide and began splashing his arms in the tide pool, trying to grasp the large pearl. Sh-h-h-h-h-h-h-h! went the water as the old man frantically grasped at nothing. Perplexed, the old man looked up. Reaching into the night sky, the old man's eyes widened as he saw the full moon. "Ha-a-a-a-a-a!" exclaimed the old man, "It's the moon!" "Whooo-o-o-o-o-o" cried the old man, "There's no money!"

CONTRAINDICATIONS FOR THE SIX HEALING SOUND THERAPY

There are several counter-indications for the use of the Six Healing Sound Therapy:

- The resonating sounds have a strong affect on the tissues, therefore patients who have broken or fractured bones are forbidden to practice sound therapy. Only after the bones tissues have mended are the patients allowed to practice the healing sounds.
- Due to the stimulating effect of the Six Healing Sound Therapy, it is advisable for the Qigong doctor not to prescribe the practice of the six healing tones in a very acute stage of illness. Vibrating the patient's internal organs in the beginning stages of a disease (i.e., a high fever) may stimulate the patient's virus or bacterial growth.
- Women are prohibited from practicing Tone Resonation therapy when pregnant, as the tone resonations have a pattern of dispersing clots and may lead to spontaneous miscarriages.
- Women are prohibited from practicing Tone Resonation therapy when menstruating, as it is important for the woman's body to be allowed to naturally Purge Toxic Blood from the body.

SOUND RESONATION THERAPY FOR TUMOR AND CANCER

Cysts, tumors, and cancer are characteristic of Excess stagnation of Qi and Blood, as well as stagnations of Heat and Cold. Chronic diseases, marked by obstruction of channel Qi, disorders of Qi and Blood, and the breakdown of Yin and Yang balance, are also included as Excess stagnation syndromes. The following sound methods involve a special series of tone resonation exercises (similar to, but stronger then the six healing sounds) which are utilized to disperse stagnations.

In order to find the correct pitch, the patient starts with a soft volume sound to experience the physical characteristics of the internal organ vibrating. While pronouncing the tone with the vocal cords relaxed, the patient gradually increases the sound to a louder volume.

While exhaling the sound, the patient focuses on an internal image of the diseased tumor dissolving. The patient must actually hear and feel the sound resonating the body's tissues, saturating the organ with sound vibration, energy, and light.

The following sounds are prescribed for the treatment of tumor and cancer therapy: the "Guo" sound is used by patients with Liver diseases, the "Zheng" (pronounced as jang) sound is pronounced by patients with Heart trouble, the "Gong" sound by patients with Spleen diseases, the "Shang" sound by patients with Lung trouble, and the "Yu" sound by patients with Kidney diseases. The relationship between the five pronunciations and the five solid organs as well as the number of pronunciations are shown in Figure 40.13.

PREPARATION FOR TUMOR AND CANCER SOUND THERAPY

Have the patient begin this exercise in a Wuji posture, and encourage the patient through the One Through Four meditation (One-Fun, Two-Shoe, Three-Tree, and Four-Core) described in Chapter 26.

Each tumor and cancer healing sound is pronounced in a straight tone, facing the left and exhaling the tone while rotating the body to the right. This allows the patient to purge the specific diseased organ. After completing the required number of straight tone exhalations, the patient faces forward and pauses.

The patient then begins the second half of the

		Elements				
		Wood	Fire	Earth	Metal	Water
Yin organs	solid organs	Liver	Heart	Spleen	Lung	Kidney
Yang organs	hollow organs	Gall Bladder	Small Intestine	Stomach	Large Intestine	Bladder
body turns left to right body turns right to left	high-pitched straight tone low-pitched descending-ascending tone	guo	zheng	gong	shang	yu
number of repetitions		8	7	10	9	6

Figure 40.13. Tumor and Cancer Sound Therapy Chart

prescription by facing the right direction and exhaling a descending tone while rotating the body to the center of the room, then rising tone while rotating the body towards the left side of the room. This application causes the patient to purge the diseased organ's channels of Toxic Qi.

Upon completion the patient performs the Pulling Down the Heavens technique to cleanse the body of any leftover energetic residue.

THE PROPER AMOUNT OF TONE REGULATIONS

The beginning patient should not be too anxious to perform the required number of pronunciations. By gradually reaching the required number, and slowly adapting themselves to the Tone Resonation method, the patients avoid getting tired. The sound "Shang," for example, is pronounced nine times for each exercise in the case of Lung disease. However, a beginner may start by pronouncing the tone three times, and then gradually progress to six times in twenty days. Then, in another thirty days, the patient can reach the required number of times. The number of repetitions is always dependent upon the patient's age, type of constitution and the severity of the disease.

In other words, the amount of times in a day that the patient performs the healing sounds depends upon the patient's general condition. The sounds used in tumor and cancer therapy, for example, will be prescribed more frequently with less volume then that of the regular six healing sound therapies. For Lung cancer, for example, the patient should perform the "Shang" sound eighteen times a day, nine breaths in each direction, right and left; for Lung congestion, perform the "Sss" sound three times a day, 36 breaths for each set.

SPECIALIZED PRESCRIPTIONS FOR TUMORS AND CANCER

The sound therapies used for treating tumors and cancer are quite different and much more powerful then the six healing sounds previously prescribed to purge and regulate the body's internal organs. Because of the dramatic difference in power and energetic potential between these two healing sound systems, the cancer patient will be given a lower number in tone respirations, but an increased number of times of practice per day.

The healing sounds used for treating tumors and cancers are as follows: for Liver/Gall Blad-



Figure 40.14. For Liver diseases the sound is "Guo."



Figure 40.15. For Heart trouble, the sound is "Zheng" (Jang).



Figure 40.16. For Spleen diseases, the sound is "Gong."



Figure 40.17. For Lung trouble, the sound is "Shang."



Figure 40.18. For Kidney diseases, the sound is "Yu."



Figure 40.19. For chemotherapy, the sound is "Xi" (She).

der tumors, use the sound "Guo" (Figure 40.14); for Heart/Small Intestine tumors, use the sound "Zheng" (Jang - Figure 40.15); for Spleen/Stomach tumors, use the sound "Gong" (Figure 40.16); for Lung/Large Intestine tumors, use the sound "Shang" (Figure 40.17); and for Kidney/Bladder tumors, use the sound "Yu" (Figure 40.18). The Triple Burners' sound "Xi" (She) is used to purge Heat from the body after radiation and chemotherapy (Figure 40.19).

The choice of sound resonation must suit the patient's specific disease. Generally, in the beginning, patients with cancer should mainly pronounce the purgation sound "Haa" nine times to purge the Heart of stagnant emotions (Figure 40.20). After pronouncing the sound "Haa" for a certain time period, the patient begins to become emotionally vulnerable. The doctor then adds the specific sounds for the treatment of the diseased internal organs. The "Shang" sound, for example, is prescribed for patients with Lung cancer.

1. The tones for Radiation and Chemotherapy patients should include the Triple Burners' sound "She." This toning should be done when their blood count is low after chemotherapy or radiation therapy and is used to purge Excess Heat from the body. The sound "She" is pronounced six times. Its high-pitched sound is in the straight tone (perform six times), and its low-pitched sound is in the dropping and rising tone (perform six times).

   After the patient has stabilized and the red and white blood count has reached a normal level, the "She" sound is dropped and replace by the sound "Haa." This is done to stabilize the patient's emotions. Instead of "Haa," the doctor can also replaced the healing sound with the specific sound needed to treat the diseased internal organ.
2. The tones for Stomach cancer patients should include the sound "Dong." The Dong sound has a deeper penetrating affect than the "Gong" sound (which is usually prescribed for Stomach diseases). The "Dong" sound should be pronounced ten times (Figure 40.21). Its high-pitched sound is "Dong" in the straight tone (perform ten times), and its low-pitched sound is "Dong" in the dropping and rising tone (perform ten times).
3. The tones for Brain tumor patients (with cerebral carcinoma) should include the sound "Duo." The "Duo" sound should be pronounced ten times (Figure 40.22). Its high-pitched sound is "Duo" in the straight tone (perform ten times), and its low-pitched sound is "Duo" in the dropping and rising



Figure 40.20. For cancer in general, the sound is "Ha."



Figure 40.21. For Stomach cancer, the sound is "Dong."



Figure 40.22. For brain cancer, the sound is "Duo."



Figure 40.23. Back View for the Cancer Prescriptions

tone (perform ten times). In addition the patient should also practice techniques to strengthen the Kidneys and Heart.

4. The tones for Lung tumor patients (with carcinomas of the Lungs) should include the "Shang" sound. The "Shang" sound should be pronounced nine times. The patient should also use the Fast Breathing Method technique (2 inhalations, followed by 1 exhalation of the sound "Shang"), in addition to practicing Lung and Kidney strengthening exercises.
5. The tones for Large Intestine tumor patients (with carcinomas of the Large Intestine) should include the "Shang" sound. The "Shang" sound should be practiced nine times using the Fast Breathing Method technique, in addition to practicing Lung strengthening exercises.
6. The tones for Nasopharyngeal tumor patients should include the "Shang" sound. The "Shang" sound should be practiced nine times using the Fast Breathing Method Walking technique (see Chapter 15), in addition to practicing Lung strengthening exercises.
7. The tones for Small Intestine tumor patients (with carcinomas of the Small Intestine) should include the "Zheng" sound. The "Zheng" sound should be practiced seven times, using the Fast Breathing Method technique, in addition to practicing Heart strengthening exercises.
8. The tones for Liver Cancer and Gall Bladder tumor patients (with carcinomas of the Liver and Gall Bladder) should include the "Guo" sound. The "Gou" sound should be practiced eight times, using the Fast Breathing Method technique, in addition to practicing Lung, Liver, and Spleen strengthening exercises.
9. The tones for the Bladder and uterus tumor patients (with carcinomas of the Urinary Bladder and uterus) should include the "Yu" sound. The "Yu" sound should be practiced six times, using the Fast Breathing technique, in addition to practicing Kidney strengthening exercises.

   While in a Wuji posture, the patient places both hands on the Kidneys and presses the middle fingers at the Shenshu Bl-23 point beside the Mingmen before pronouncing the sounds (Figure 40.23).
10. The tones for Prostate cancer patients should include the "Yu" sound. The "Yu" sound should be practiced six times, using the Fast Breathing Method technique, in addition to practicing Kidney strengthening exercises.
11. The tones for Skin Cancer patients (with dermal carcinomas) should include the "Shang" sound. The "Shang" sound should be practiced nine times, using the Fast Breathing Method technique, in addition to practicing Lung, Liver, and Spleen strengthening exercises.

CONTRAINDICATIONS FOR TUMOR AND CANCER SOUND THERAPY

As previously mentioned, the tumor and cancer healing sounds are only prescribed for purging Excess conditions within the patient's diseased organs, and not for treating Deficient organ conditions. If a specific internal organ is already in a state of Deficiency and the patient is allowed to focus on that organ with one of the tumor and cancer sounds, the patient's condition will worsen. This increases the potential for rapid growth of the disease.

CHAPTER 41
MEDICAL QIGONG REGULATION EXERCISES

INTRODUCTION

The following chapters explore several systems of Medical Qigong exercises used in regulation, purgation, and tonification prescriptions. Conceived in ancient China, these exercises originate from the various medical, martial, and Daoist schools of energy cultivation. It is from these ancient energetic systems that today's modern clinical Qigong prescriptions originate.

Each Qigong system has its own unique approach to circulating, balancing, and storing the body's life-force energy. No one particular style of energetic healing is superior to the next, only different in its approach. The primary goal of each of these systems is removing stagnant pathogenic energy and replenishing and circulating clean life-force energy.

The Xi Yuan Hospital in Beijing, China is famous for its advanced Medical Qigong clinics and Medical Qigong prescriptions. These exercises utilize both Static and Dynamic Postures and are generally taught in both the inpatient and outpatient clinics. The static exercises are used to store the Qi, while Dynamic Qigong exercises are used to open the patient's channels and circulate the Qi.

Each prescription should be practiced for five to ten minutes for each organ or organ system on a daily basis; or if the patient is practicing only one set (e.g., Regulation of Spleen and Stomach Qi), they should practice for thirty minutes. Unless otherwise indicated, all breathing should be "natural."

The goal is for patients to empty their body and mind, so that their emotions can be felt and activated. In the Medical Qigong clinic there is a saying, "The patient can only heal what they feel."

STARTING AND ENDING THE PRESCRIPTIONS

Before starting any Medical Qigong prescription, it is important for the patient to understand that every Qigong exercise must start and end with specific preparations.

- Before starting the Medical Qigong prescription, the patient must always purge his or her body. It does not matter if the exercise they are about to begin is used to purge, tonify, or regulate the internal energy; they must always purge first. This is similar to washing a dirty glass before filling it with clean water.
- After ending the Medical Qigong prescription, the patient must always gather the generated Internal Qi and the return to its origin. The term "Return to its Origin" refers to a three fold process:
  - cultivating, collecting, and accumulating the prenatal energy,
  - developing and transforming it into postnatal Jing, Qi, and Shen, and
  - returning it back to prenatal Jing, Qi, and Shen.

This allows the Post-Heaven Kan and Li (Water and Fire energies) to return to their origin and restores them to Pre-Heaven Qi (Heaven and Earth energies). This fusion into one energy, often called the Hun-Yuan or Blended Originals, requires the patient's original substances to condense into one energetic substance and be merged with the patient's Lower Dantian energy.

In order to collect the energy, the patient is taught to apply the Three Natures Become One technique of focused concentration (all thinking, seeing, and listening is focused into the Lower Dantian). The Three Natures are as follows: the eyes represent the perceptive nature, the ears represent the spiritual nature, and the Heart represents the courageous nature. When all three natures unite into one, the energetic refinement is called "collecting the body's true nature." The patient can then collect the body's power.

MEDICAL QIGONG CULTIVATION EXERCISES

The body is composed of different densities of energy and matter in the form of internal organs, organ systems, channels, and collaterals. When practicing Qi cultivation methods both students and patients are instructed to train in a progressive order of Qi cultivation.

First, the students and patients are taught how to purge, tonify, and regulate their internal and external channels. Once the Yin and Yang energy of the channels are balanced, the practitioners learn how to balance the Yin and Yang energy of the internal organs. This training likewise involves purging, tonifying and cultivating methods. The directed focus of intention on specific points, channels, or areas of the body causes the Qi to gather in those locations and to be absorbed into the body's tissues through the Mind's intention (whole body awareness and consciousness). The final step of training the Yuan (Original) Qi is undertaken only after the first two steps have been accomplished.

All cultivation practices of Medical Qigong therapy can be divided into two main categories of gathering and training Qi: the External Elixir Cultivation (Wai Dan Shu) and the Internal Elixir Cultivation (Nei Dan Shu). These two Qi cultivation training methods are described as follows.

EXTERNAL QI CULTIVATION

The External Elixir Cultivation (Wai Dan Shu) involves several methods of gathering energy from the external environment (Heaven and Earth) to strengthen the body's organs, organ systems, channels, and collaterals.

HERBS AND FOOD

The first method is developed through food and herbal soups, teas, and pills to increase the body's energy. When herbs are prescribed as a tonic, they stimulate the organ's energy by increasing the flow of Qi in the patient's channels. Qigong and herbology go hand-in-hand with respect to the energetic regulation and balance of the body's life-force energy. Herbs can be extremely important for maintaining the physiological balance of the metabolism and restoring any depletion of the body's energetic mechanism. Herbs act as a form of energetic nutrient, allowing the Earth energy to be ingested into the body through a natural substance.

MEDITATION

The second method is developed through meditation. Qi is cultivated through the body's extremities from energy originating outside of the body's torso (i.e., both palms, both soles of the feet, and the top of the head). The External Elixir Cultivation meditation focuses the concentration on either the Heaven or Earth energy fields to draw their energy into the torso for increased Yin or Yang Qi regulation. The Postural Dao Yins in External Elixir Cultivation may be either static or dynamic.

Two examples of External Elixir Cultivations are: the Earth Yin Qi Regulation and the Heaven Yang Qi Regulation. The Earth Yin and Heaven Yang Qi Regulations are used to balance the energy along the body's ascending and descending energetic channels. To balance along the horizontal energetic channel, perform the Turning and Winding the Belt Vessel exercise described later on in this chapter.

- **Earth Yin Qi Regulation**

  The Earth Qi is considered Yin Qi or electronegative energy. Blood also pertains to Yin Qi. Through Earth Regulating Qigong meditations, the body's Blood cells can be replenished with Earth Yin energy.

  Begin the Earth Qi Regulation meditation from a Wuji posture, while using Natural Breathing. In this particular exercise, the practitioner takes advantage of the Kd-1 points at the bottom of the feet, and the Pc-8 points at the center of the palms which are sensitive to the magnetic pull of the Earth.

  After standing in the Wuji posture for several minutes, inhale and begin to absorb the

Earth Qi up from the ground through the centers of the palms and the bottom of the feet (Figure 41.1). After several more minutes of drawing the Earth energy into the Lower Dantian, begin circulating the energy through the Microcosmic Orbit's Fire Cycle. The palms should begin to expand and feel almost swollen; the red and white blotches on the palms and feet indicate that the exercise has been practiced correctly.

- **Heaven Yang Qi Regulation**

Heaven energy pertains to the sun's Yang Qi or electropositive energy, which is used to tonify the body's Yang Qi.

Begin from a Wuji posture, placing both palms above the head, facing upwards, like two antennas collecting the sun or Heaven's Qi into the Middle Dantian. Use Natural Breathing. Imagine the sun's golden light showering the outside of your body. Open your mouth and imagine swallowing the sun's Qi, allowing it to mix with your saliva. As you swallow, feel the energy flow down into your Lower Dantian, and then out of your pores. Once the Dantian is full, the body should feel expansive. Always end the meditation by returning the energy to the Lower Dantian to avoid any Qi deviations (Figure 41.2).



Figure 41.1. Absorb the Earth Qi into the body through both hands and feet, and store the Qi in the Lower Dantian.



Figure 41.2. Absorb the sun's energy into the body through both palms, moving it into the Middle Dantian, and store the Qi in the Lower Dantian.

INTERNAL QI CULTIVATION

The Internal Elixir Cultivation (Nei Dan Shu) method focuses on first training the energetic substances already gathered and existing inside the torso, and then extending this accumulated energy out into the extremities. Since it first appeared in the Han Dynasty, the training and theory of Internal Elixir Cultivation has become the primary focus of many Qigong masters, working with postnatal energy transformations. Internal Elixir Cultivation focuses on transforming the body's Jing, Qi, and Shen. When practicing this exercise, ancient Qigong masters imagined the Lower Dantian as a stove, the Shen as a Fire, and the body's Jing, Qi, and Shen as the internal medicine.

At birth, the energy flows up the front of the body (Conception Vessel) and down the back (Governing Vessel). This is considered the circulation of the Yuan Qi (generated from the prenatal Jing stored in the Kidneys). It is considered the Perceptual Yin or Water Cycle of the Microcosmic Orbit. This Perceptual Yin Cycle allows the newborn child to possess powerful psychic, empathic, and kinetic abilities; it enables the child to energetically connect with the environment in order to ensure survival.

As the child advances in age, he or she begins to encounter and experience some hostile messages in the form of physical or emotional frustration and pain from both parents, siblings, and the environment. For protection, the child armors and creates a denial system, which insulates him or her from the energetic and emotional wounding. The child begins to instinctively stop the energetic flow of the perceptual Yin Water Cycle and begins to activate the acquired rational mind, trying to cope with his or her feelings and the stress of his or her surroundings. Whenever the child begins to experience painful emotions, he or she learns to avoid experiencing these hurtful feelings through certain mental and physical actions by contracting the throat and thorax. These acquired actions further create an energetic restriction and impede the flow of Qi along the Conception and Governing Vessels. This physical activity naturally causes the Yin Water Cycle to stop its perceptual flow of energy, and allows the child's body to deal with the trapped emotional experiences by storing them within the tissues. Although this is not a healthy response, it allows the child to survive and develop in a sometimes difficult environment. In cases of deep traumatic wounding (physical, emotional or sexual), the child becomes void of deep emotional connections, while still allowing for certain perceptual survival instincts.

Also, our culture emphasizes left brain thinking for educational purposes, and later to enable young adults to rival others in the competitive job market. The child thus must forgo most of his or her innate intuitive perceptions to succeed in school and to appropriately integrate society's values and belief structures. Very little encouragement is given to right brain activity; it is in fact discouraged by society at large.

REGULATING THE BODY'S QI

The first stage in circulating and cultivating the Qi is to regulate the Yang or Fire Cycle of the Microcosmic Orbit. This allows the trapped emotions within the tissues to be released. This is initiated through mental concentration, focusing the flow of the Qi up the back and down the front of the body. It is extremely important to allow the trapped energy to release itself naturally from the body through the Fire Cycle of the Microcosmic Orbit. Otherwise, trapped emotions deep within the tissues can cause Qi deviations within the body, which may lead to energetically induced psychosis.

When regulating the Microcosmic Orbit, there are three primary methods of energetic cultivation that harmonize the body's Jing, Qi, and Shen. They relate to the sun (Fire and Heaven), moon (Water and Earth) and stars (Wind and Man).

THE FIRE PATH OF THE MICROCOSMIC ORBIT

The Yang or Fire Path is the most popular method of cultivating energy along the Small Heavenly Cycle or Microcosmic Orbit (Figure 41.3). Because it joins together the body's Yin and Yang rivers of Qi, which regulate the Twelve Primary Channels, it is considered the foundational meditation for the Internal Elixir Cultivation methods. The circulation of Postnatal Qi is generated from the Acquired Essence (food, air, and water). In this cycle, the Qi moves up the Governing Vessel and down the Conception Vessel, and is considered the ascension of Yang or the opening of the Fire Channel. The initial goal is to circulate the Fire energy from Yang to Yin to convert Jing to Qi and then to Shen. The Yang (Fire) Qi supports awareness of the emotional side of consciousness.


Exhale down the Conception Vessel.
Inhale up the Governing Vessel.
Lower Dantian

Figure 41.3. The Fire Path of the Microcosmic Orbit flows up the back and down the front of the body.

The Heart and Middle Dantian are considered the House of Shen; Fire and passion (Qi that manifests as emotions) and are related to the flow of the Conception Vessel. The Kidneys and Lower Dantian are considered the House of Jing, Water and pleasure and are related to the flow of the Governing Vessel. It is important to use Reverse Breathing while uniting the Heart's Fire and Kidneys' Water, to cause the alchemical transformation of Jing into Qi in the lower abdomen.

When moving the Qi along the Governing Vessel, practitioners must move the energy through the Five Gates (see Chapter 30). The energy first gathers at the Lower Dantian, then overflows into the Governing Vessel, collecting, building, and then passing through to the next gate, one gate at a time. As the energy gathers at these gates, the Qi and Blood begins to Heat and vibrate the tissues. This energetic reaction affects the patient's emotions that correspond to or are embedded in each specific gate, causing a powerful emotional release. As the Qi passes through to the next gate, a new set of emotions is experienced, then released.

THE JIAJI POINTS' EFFECT ON THE GOVERNING VESSEL'S ENERGETIC FLOW

Jia translates to mean "besides." Ji translates as "the spinal column." These points are located lateral to the lower border of each spinous process of the cervical, thoracic, and lumbar vertebrae. Each point has its own Luo pathway (energetic channel), which intersects with the spine and connects to the Jiaji point located on the opposite side of the Governing Vessel. It is believed that one pair of the ascending Governing Vessel's Luo Channel intersects and connects to all of the Jiaji points along the spine.

This being the case, when the two energetic flows from the Jiaji points (via the Luo pathways) are superimposed, the reaction causes a crisscrossing and intertwining of Qi flow, which resembles the intertwining energies of the caduceus or double snakes.

THE TWELVE EARTHLY BRANCHES' RELATIONSHIP WITH THE MICROCOSMIC ORBIT

Within the Fire Cycle of the Microcosmic Orbit, there are twelve channel points located along the Governing and Conception Vessels which relate to the Twelve Earthly Branches and the waxing and waning of the Yin and Yang cycles (see Chapter 11). The Fire phase of the Microcosmic Orbit starts at the Zi branch located at the Sheng Si Qiao area at the root of the penis in men and at the vagina in women. Moving up the back of the body, there are four phases of Qi ascent in the Governing Vessel. The four phases are: from Zi to Chou, from Zi to Yin, from Zi to Chen, and from Zi to Si. The Mao point is one of the four cardinal points (along with Zi, Wu, and You) and is a point of purification. The path up the Governing Vessel cleanses the energy through this point of purification.



Figure 41.4. Twelve Earthly Branch Relation with the Microcosmic Orbit: the main channels of the back and front of the body correspond to the ecliptic path of the sun. These twelve special energy points are associated with the Twelve Chakra Gates.

When the energy reaches the Wu point at the top of the head (also known as the Ascending point), it stays there briefly before beginning the descent of Yin in the Conception Vessel. The descent down the Conception Vessel purifies the energy (Figure 41.4).

While at the perineum and Zi point in the orbit, the Yang Qi begins to develop as the Yin Qi reaches its zenith. Once the energy reaches the Mao point at the middle of the back, the Yang energy has developed fully and begins to prosper. At the Wu point at the top of the head, the Yin Qi begins to develop while the Yang Qi reaches its zenith. This point represents the turning point from Yang to Yin.

If the energy is to flow properly down the Conception Vessel, there must be an opening of the energy centers via a connection with the Shen. This purification of energy commences at the Wu point when the Yang Qi turns to Yin Qi. While the Earth's daily orbit around the sun has the same Yin-Yang transitions, the body absorbs the Yang energy during the hours of Zi and Wu, and expels Yin energy during the hours of Mao and You.

At the Zi hour (11 p.m.–1 a.m.), the Jing naturally collects at the Sheng Si Qiao point at the root of the penis (prostate area) in men causes a natural erection while the man is sleeping. This hour also marks the commencement of the Yang half of the day. This period of the day is the best for collecting Jing and, thus, is the best time to perform Wuji standing practice.

CONTRAINDICATIONS

Whenever the practitioners are weak, it is important that they practice Natural Dantian Breathing and avoid practicing the Microcosmic Orbit. If patients attempt to practice Circular Breathing while in a depleted state, the Qi may become trapped in their head causing Qi Deviations, and initiating more problems. Circular Breathing is achieved by guiding the Qi in a circular pattern through even inhalation (e.g., up the spine) and exhalation (e.g., down the front of the body).

THE WATER PATH OF THE MICROCOSMIC ORBIT

The Water Path is trained only after the completion of the Fire Path circulation exercise. After the patient's Prenatal Qi has been cultivated and accumulated to a substantial level, the patient may lead the Qi up the Conception Vessel and down the Governing Vessel (Figure 41.5).

This is opposite the direction of the flow of the Fire Path, and is considered the ascension of Yin or the opening of the Water Channel. The purpose for the Water Path circulation is to change, regulate, and charge the body's Yuan Shen. The Water cycle supports the perceptional side of consciousness, cools down the body's overheated Yang Qi, and regulate the Qi circulation of the Fire Path to rebalance the body.

THE WIND PATH OF THE MICROCOSMIC ORBIT

The Wind Path of the Microcosmic Orbit is the third method of circulation and requires practitioners to lead energy up the center of their body through the Taiji Pole (Figure 41.6). This energy pathway flows up through the Marrow of the spine, through the brain, and washes over the falx cerebri into the pineal and pituitary gland. It then descends down along the Conception Vessel and back into the Lower Dantian.

The purpose of the Wind Path is to increase divine perception (by accessing the energy of the Wu Jing Shen), and to regulate the body's glandular and endocrine systems, to enable the practitioner to slow down the aging process.


Exhale down the Governing Vessel.
Lower Dantian
Inhale up the Conception Vessel.

Figure 41.5. The Water Path of the Microcosmic Orbit travels up the front and down the back of the body, ending at the Lower Dantian.


Exhale down the Conception Vessel.
Inhale up the center of the spine.
Lower Dantian

Figure 41.6. The Wind Path of the Microcosmic Orbit travels up the center of the spine into the brain and third-eye point, down the front of the body, ending at the Lower Dantian.

MEDICAL QIGONG PRESCRIPTIONS

The following exercises are taken from various hospitals, universities, and institutes of Medical Qigong. These regulation prescriptions are used throughout China.

DESCEND THE QI AND CLEANSE THE ORGANS

This exercise was developed to utilize the body's Hun-Yuan Qi (the body's internal combined organ energy) to flush and cleanse the Triple Burners and the Five Yin Organs. This is a purging exercise, used to:

- eliminate the body's Turbid Qi,
- unclog the channels and collaterals,
- wash the bones,
- transform the Marrow, and
- combine the remaining pure energy with the body's Yuan Qi.

It can be prescribed for patients with Excess conditions to descend the Liver's or Heart's Fire.

PULLING DOWN THE HEAVENS

This exercise requires the focus of energy to flow down the body in three directions (front, center, and back) to complete one set.

1. Begin in a Wuji posture, with both feet facing forward, a little wider than shoulders width apart. Both hands are at the sides of the body. The spine is kept straight, with the body relaxed and centered (see Chapter 15 for proper alignment). Stand with the eyes focused on the horizon. Pull the Qi from the horizon into the eyes and down to the Lower Dantian, filling the entire body. Hold this posture for one to three minutes (Figure 41.7).
2. Inhale through the nose. With the palms facing downward, begin to scoop the energy from the Earth into the body, gathering and absorbing the environmental energy. Focus on slowly filling the body with Earth Qi while moving the hands upwards to about waist level (Figure 41.8).
3. Continue inhaling, turning the palms to face the Heavens and drawing both hands upwards at a forty-five degrees angle. As both palms continue to move upwards, begin pulling in and absorbing the Heavenly Qi while guiding the hands above the head. Complete the inhalation with the arms above the head, palms facing the top of the head. Pause when the hands are above the Baihui area (Figure 41.9).
4. Exhale through the nose, and begin descending the palms in front of the body. Allow the palms to face the body and direct the Qi flow through the head and throat area (Figure 41.10).
5. Imagine the energy continuing to pour down through the chest and abdominal areas (Figure 41.11).
6. While exhaling, slowly lower the hands in front of the body in one continuous movement, until they reach just above the knees (Figure 41.12).
7. Inhale and begin the sequence again. Each time the hands pass in front of the body, exhale and imagine the Qi being emitted through the hands into the tissues. Three passes over the front of the body equal one set, practice 36 sets. The energetic pathway of each set is explained as follows:
    a. The first pass begins by leading the Qi down the front of the body from the Baihui area. Each palm facing the body divides the energy into two rivers, which flow from the top of the head, over the ears, and down the throat. Continue guiding the two rivers down the front of the chest, joining again at the navel. From there lead the Qi down into the Huiyin CV-1 point at the perineum, then separate them again into two rivers which continue to flow down the Yin channels on the inside of each leg, ending at the Yongquan Kd-1 point at the bottom of each foot.
    b. Start the next pass at the middle of the head above the Baihui area. Lead the Qi down the center of the body, and absorb the Heavenly Qi as it passes through all the body's internal organs, till it reaches the Lower Dantian area. From the Lower Dantian divide the energy into two rivers and descend the Qi down the center of the legs ending



Figure 41.7. Wuji Posture



Figure 41.8. Pulling Down the Heavens (A)



Figure 41.9. Pulling Down the Heavens (B)



Figure 41.10. Pulling Down the Heavens (C)



Figure 41.11. Pulling Down the Heavens (D)



Figure 41.12. Pulling Down the Heavens (E)

at the Yongquan Kd-1 point at the bottom of each foot.

c. The final pass likewise begins at the top of the head, at the Baihui area. Imagine the energy flowing like a river, down the midline of the back of the head and back, until it reaches the Mingmen GV-4 point. From there it divides into two rivers, descending into the Huantiao GB-30 point at the side of each buttock, and continues to flow down the outside of each leg and ends at the Yongquan Kd-1 point at the bottom of each foot. As the Qi descends (on each pass), it washes the organs from the top of the head (Baihui point) to the bottom of the feet.
d. To end the exercise, relax the whole body and return to the Wuji posture, allowing the Qi to return to its origin. As the Qi descends through the body, imagine the environmental energy fusing with the body's Yuan Qi, forming a mist and dew. Imagine this mist slowly flowing down (from top to bottom) and bathing, cleansing, and purifying the entire body. As the mist descends, if a certain organ is diseased, pause for a while to bathe the area with the vapor before continuing the flow of energy. Consciously disperse the pathogens out the extremities.

GATHERING QI IN THE UPPER AND LOWER DANTIANS

This exercise is designed to strengthen, tonify, and regulate the body's internal organs and energetic fields. It is excellent for promoting and maintaining health, and can be used for tonifying the Kidneys, as well as to treat impotence, premature ejaculation, lumbago, lower back problems, and pelvic inflammatory disease (PID). When treating PID, use reverse breathing with Static Qigong training.

This is a tonification exercise, used to increase the production of Jing (sperm or ovary energy), transforming it into Qi, and to lead the Jing up the spinal cord to support the brain, as well as nurture the bone marrow. This exercise adds Fire to the Mingmen, simmering the condensation of energy within the Kidneys. When the Kidney (Water) and Heart (Fire) energies are sufficient, their energies merge to form the True Qi which cultivates one's nature, spirit, and life. This exercise also assists the Microcosmic Orbit and establishes a base for refining and gathering energy in the Upper and Lower Dantians and Huiyin.

GATHERING QI IN THE UPPER DANTIAN

Begin from a Wuji posture. Inhale, as both hands gather energy while moving up the sides of the body and embrace the Qi into the Upper Dantian. Pause and exhale while separating the hands (Figure 41.13).

Inhale and imagine the middle fingers of each hand gathering the Heaven and Earth Qi into the Upper Dantian. Imagine the body absorbing these energies through the Yin Tang point (Third Eye), into the pineal gland at the center of the brain. Imagine the light of the Upper Dantian getting brighter as the energy begins to increase (Figure 41.14). Repeat this exercise nine times.

Upon completion, focus on the Upper Dantian and begin to gather and fuse the body's Yuan Shen along with the collected Heaven and Earth energies into one energy. As this energy collects, imagine it forming into an energetic ball of white light and allow the hands to guide the light downward into the Lower Dantian.

During the process of descending the Qi from the Upper to Lower Dantian, the focus should be on feeling, guiding, listening, and seeing the energy traveling downward. As the energy of the Shen descends, the Jing energy naturally ascends. This descending and ascending action of Jing and Shen energies cultivates an abundant amount of Qi in the Lower Dantian. After the Qi has been gathered and stored there, pause a moment, allowing the energy to settle. Then proceed to regulate the Lower Dantian.

GATHERING QI IN THE LOWER DANTIAN

Both hands sink down to waist level and form an embracing posture in front of the navel. Inhale while slowly drawing the palms inward towards the navel, gathering the Qi into the center of the Lower Dantian. Pause a moment and relax, allow-



Figure 41.13. Gathering Qi in the Upper Dantian (A)



Figure 41.14. Gathering Qi in the Upper Dantian (B)



Figure 41.15. Gathering Qi in the Lower Dantian (A)



Figure 41.16. Gathering Qi in the Lower Dantian (B)



Figure 41.17. Gathering Qi in the Huiyin Area (A)



Figure 41.18. Gathering Qi in the Huiyin Area (B)



Figure 41.19. Gathering Qi in the Huiyin Area (C)



Figure 41.20. Gathering Qi in the Huiyin Area (D)

ing the energy to settle, then exhale and separate the hands (Figure 41.15).

Inhale and imagine the body absorbing the universal and environmental energies in through the navel and Lower Dantian areas (Figure 41.16). Repeat this exercise nine times.

Imagine the Lower Dantian as a reservoir, storing but never overflowing. The expansion and contraction of the abdominal muscles creates a "beating and drumming" movement which improves the abdominal muscles' elasticity while massaging the digestive system. The "beating and drumming" movement strengthens and increases peristalsis.

GATHERING QI INTO THE HUIYIN AREA

Continuing from the last posture, both hands begin to move downward from the Lower Dantian (Figure 41.17).

As you inhale, bend over and imagine scooping the Earth energy along the inside of the legs, directing the Qi through the three Yin channels into the body's Huiyin, coccyx, and Mingmen areas. While inhaling, it is important to pull up on the anal sphincter and imagine gathering the Earth Qi directly through the lower body's orifices (testicles and penis, or vagina) into the Kidneys and Mingmen area (Figure 41.18).

Move both hands from the insides of the thigh, groin, and lower abdomen backward, along the Belt Vessel, expanding the energy into the Kidneys and Mingmen area. Hold this posture and exhale, imagining the Qi flowing into the Kidneys and Mingmen areas (Figure 41.19).

Next, circle the Qi down to the Lower Dantian and Huiyin area. Pause for a moment to allow the Qi to settle and root (Figure 41,20). Repeat this exercise nine times and end this exercise.

ROLLING THE BALL WITH BOTH PALMS

The purpose of this exercise is to regulate the Yin and Yang balance of energy in the body. This exercise also causes the capillaries along the Microcosmic Orbit to open up, improving the Qi circulation and nerve stimulation in the extremities.

It is excellent for purging and regulating emotions from the Heart and Yellow Court, as well as for descending Rebellious Lung Qi downward and purging Yang Qi Rising.

SHAKING THE SUN AND MOON

Begin from a Wuji posture. Both arms raise up in front of the shoulders, palms and fingertips pointing upward. Imagine the left palm embracing the sun and the right palm embracing the moon. Vigorously shake the palms, focusing the mind's intention on the center of the palms and fingers (Figure 41.21).

Place both palms in front of the chest and Middle Dantian area, and imagine the energy of the sun and moon melting into each other, creating a huge ball of energy. Make sure the eyes focus on the center of the ball (Figure 41.22).

ROLLING THE BALL

Wait until you can feel the sensation of the energy ball before beginning the rotations. Imagine the energy ball in the hands and the energy ball in the Lower Dantian blending naturally into one energy, simultaneously rotating and rolling together both internally and externally.

Begin rolling the ball, keeping the mind's intention focused on the center of each palm. Imagine the ball is slowly growing between the hands. Roll the ball, with the hands opposite each other, (one hand is up while the other is down), eighteen times in a clockwise direction, then reverse the direction and repeat another eighteen times (Figure 41.23). After the last rotation, relax the arms and return to Wuji posture.

OPENING AND CLOSING THE UPPER, MIDDLE, AND LOWER BURNERS

This exercise is used to regulate the body's Yin and Yang energy, tonify the Yin organs, calm and harmonize the Yang organs, Regulate the Triple Burners, and help open the Conception and Governing Vessels. This is an excellent exercise for purging and regulating Excess conditions within the Triple Burners, as well as for purging the patient's Liver Fire.

There is an ancient Chinese saying, "Open, close, and come and go, one hundred illnesses will be healed." When opening, the Qi circulates into the muscles. When closing, the Qi sinks and gathers into the bones. The purpose of this exercise is to train the mind's intention, making it easier to increase the body's external field of Wei Qi.

OPENING AND CLOSING THE UPPER BURNER

Begin from a Wuji posture. Both arms raise up to shoulder level. Vigorously shake the hands, palms facing down. Before opening and closing the Upper, Middle and Lower Burner areas, the awareness must settle in the Laogong area (center of the palms) for a few minutes. Wait until heat



Figure 41.21. Shaking the Sun and Moon (A)



Figure 41.22. Shaking the Sun and Moon (B)



Figure 41.23. Rolling the Ball with Both Palms (A)



Rolling the Ball with Both Palms (Side View)



Figure 41.24. Vigorously Shake the Hands



Figure 41.25. Open and Close the Upper Burner (A)



Figure 41.26. Open and Close the Upper Burner (B)



Figure 41.27. Open and Close the Middle Burner (A)



Figure 41.28. Open and Close the Middle Burner (B)



Figure 41.29. Open and Close the Lower Burner (A)



Figure 41.30. Open and Close the Lower Burner (B)

is felt in the center of the palms before beginning (Figure 41.24).

After a while, bring both hands close to each other in front of the throat and manubrium sterni area (the upper segment of the sternum). Both palms face each other, with the fingers facing upwards. Pause a moment, focusing the mind's attention on the center of the palms, forming an energetic ball (Figure 41.25).

Slowly begin to open by pulling the arms apart, while imagining the energy between the center of the palms stretching like warm taffy. When the hands separate and open, the mind and body (chest and abdomen) also open. Slowly begin to close by bringing both palms together, pushing and condensing the stretched energy to form an energetic ball. When the hands close, the mind and body close by removing the attention away from the outside world (Figure 41.26).

When inhaling, imagine extending the fingers deep into the body and the Qi pouring deep into the tissues. When exhaling, separate the hands while imagining the Excess Heat and toxic energy being purged from the body. Repeat the exercise eighteen times.

OPEN AND CLOSE THE MIDDLE BURNER

Both hands sink down in front of the diaphragm and xiphoid process (just above the navel). Pause a moment, keeping the eyes on the energy ball and an imaginary line which connects the inner Laogong Pc-8 points at the center of the palms (Figure 41.27).

Slowly begin to open by pulling the arms apart, while imagining the energy between the center of the palms stretching like warm taffy. While exhaling, separate the hands while imagining the Excess Heat and toxic energy being purged from the body (Figure 41.28).

Slowly close by bringing both palms together, forming an energetic ball as you push and condense the energy. While inhaling, imagine extending the fingers deep into the body and the Qi pouring deep into the tissues. Repeat the exercise eighteen times.

OPENING AND CLOSING THE LOWER BURNER

Both hands sink down in front of the reproductive organs and perineal area. Pause a moment, keeping the eyes on an imaginary line which connects the inner Laogong Pc-8 points at the center of the palms (Figure 41.29).

Slowly begin to open by pulling the arms apart, imagining the energy between the center of the palms stretching like warm taffy. When exhaling, separate the hands while imagining the Excess Heat and toxic energy being purged from the body (Figure 41.30).

Slowly close by bringing both palms together, forming an energetic ball by pushing and condensing the Qi. While inhaling, imagine extending the fingers deep into the body and the Qi pouring deep into the tissues. Repeat eighteen times.

To end the exercise, draw the Qi back into the Lower Dantian, and return to a Wuji posture.

SUN AND MOON ROTATING TECHNIQUE

This exercise will massage the internal organs of both the Heart and the Lungs. In Medical Qigong, the sun is sometimes referred to as the energy of the Heart, which is the considered the master of the three Yang energies. The moon pertains to the Lungs, which are the masters of the three Yin energies. Through the harmony of these dual powers the body's Yuan (Original) Qi is born. This exercise increases the elasticity of the Heart muscles and arteries and improves Blood circulation. It also flushes the Eight Extraordinary Vessels, increases vitality, and causes the upper half of the body to become lighter while making the lower half more solid.

This exercise can also be used in conjunction with the healing sound "Shang" to treat Lung diseases (i.e., asthma and chronic bronchitis), as well as breast cysts and tumors by purging Toxic Qi from the tissues of the Lung.

ROTATING THE PALMS

Begin from a Wuji posture, start by vigorously shaking the hands and then rubbing the palms together (Figure 41.31).

Place both hands on the chest, and draw the heat from the center of the palms into the chest, inhaling three times. Once the chest has absorbed a certain amount of heat, both palms begin to ro-



Figure 41.31. Vigorously Shake the Hands



Figure 41.32. Sun and Moon Rotating Technique (A)



Figure 41.33. Sun and Moon Rotating Technique (B)



Figure 41.34. Expanding and Contracting the Rings (Forward-A)



Figure 41.35. Expanding and Contracting the Rings (Forward-B)



Figure 41.36. Expanding and Contracting the Rings (Forward-C)

tate up the center line of the chest. The rotation of the arms forms two circles, that circulate the energy from the inside to the outside of the breast. The focus of the intention should be on the "chest opening and the back closing" of the thorax. Repeat this exercise 18 to 36 rotations, depending on the severity of the condition (Figure 41.32).

Next, rotate the circles in the opposite direction, moving from the outside towards the center line of the chest and then down, circulating the energy from the outside to the inside of the breast. Repeat 18 to 36 rotations, depending on the severity of the condition (Figure 41.33).

When the rotations are completed, the middle fingers of both hands slightly press the Conception Vessel downward to descend the Qi into the Lower Dantian. Rub the abdomen three times and resume a Wuji posture.

EXPANDING AND CONTRACTING THE RINGS

Expanding and contracting the rings refers to the expansion and contraction of the spinal vertebra. This exercise reinforces the flow of the Microcosmic Orbit, invigorates and strengthens the Yuan Qi, aids in transforming Jing to Qi, and strengthens the entire spine. The patient's coordination and balance are also positively affected.

While performing this exercise, the body should move like a "dragon playing in the ocean waves" by appearing and disappearing, rising and sinking, and twisting and coiling. The goal is to stretch and loosen the spinal column, rib articulations, and the back. This will cause the body's Fire to descend and Water energy to ascend naturally through the body's center channels.

This exercise can be modified into a stationary position for convalescing patients or patient's confined to a wheelchair. The patient bends forward, allowing the spine to slowly stretch, shifting the body to a forty-five degree angle.

Begin this exercise from a right Bow Stance (weight is shifting 70% to the back, 30% forward) with both hands positioned in front of the Lower Dantian (Figure 41.34).

Both hands raise upward and stretch forward, creating an arc and stretching the spinal column. When extending and stretching the spine forward, imagine the Earth Qi traveling up the back leg, through the spine and Governing Vessel to the top of the head (Baihui point), and extending down to the Yin Tang and both Laogong points at the center of the palms (Figure 41.35).

While extending the energy outward, use intention to connect with the Heavenly Qi, the energy of the horizon, or a tree (Figure 41.36).

As both hands withdraw, shift the weight to the back leg, allowing the spinal column to contract. As you shift your weight back to the starting position, imagine drawing Qi up from the Earth into your body. Repeat nine times. End in the Wuji posture. Then switch directions by switching the position of the feet and repeat the entire sequence while reversing the rotation.

To perform the second half of the exercise, shift the body's weight forward and begin moving the body in the reverse circular direction (Figure 41.37).

Imagine the Heaven Qi traveling from the Baihui point down the Conception Vessel and out the front foot, extending deep into the Earth (Figure 41.38).

As the weight shifts back, imagine drawing Qi from the Heavens back into the body through the head and hands (Figure 41.39).

Sink the Qi deep into the Earth allowing the body to be cleansed and purified (Figure 41.40). Repeat the exercise nine times. End in the Wuji posture. Then switch directions and repeat the entire sequence.

DESCENDING THE YANG AND ASCENDING THE YIN TECHNIQUE

This exercise cultivates Qi in the channels and collaterals of the lower body, aids the free flow of Qi to the Lower Dantian, strengthens the Kidneys, Spleen, Stomach, and the Liver Qi, while regulating the Gall Bladder Qi.

It is an excellent exercise for pulling the Earth Qi (Spleen Qi) up while sinking the Stomach Qi, and is good for treating problems such as irritable bowel syndrome and problems caused from Excess Heat in the Middle and Lower Burners. In order to treat such conditions, the exercise should be performed for twenty minutes, twice a day.



Figure 41.37. Expanding and Contracting the Rings (Reverse-A)



Figure 41.38. Expanding and Contracting the Rings (Reverse-B)



Figure 41.39. Expanding and Contracting the Rings (Reverse-C)



Figure 41.40. Expanding and Contracting the Rings (Reverse-D)

This exercise can furthermore be used in conjunction with the healing sound "Yu" to treat reproductive organ diseases (i.e., uterine and ovarian cysts, tumors, and cancer, as well as prostate cancer). The patient should practice a total of one to four hours each day, depending on the severity of the condition.

Begin from a Wuji posture and embrace the abdomen (Figure 41.41).

Gather Qi into the Lower Dantian and turn towards the left, both hands move into the Huantiao GB-30 point at the side of the hip (Figure 41.42).

Both hands slowly descend the three Yang channels down the outside of the left leg with a "pushing" action, ending on the outside of the left foot at the Bubbling Well point (Kd-1) at the bottom of the foot. As both hands reach downward to the foot, stretch the body and allow the waist to follow the descending Qi with a downward crouching movement (Figure 41.43).

Next, shift the hands around the foot and begin ascending the three Yin channels with the hands inside the left leg. Continue the movement all the way up into the Huiyin point, pubic bone, and Lower Dantian area with a "pulling" and "drawing" action. Pull the anal sphincter upward while drawing the Earth Qi into the body. When both hands raise and gather Qi upward, the body and waist must follow the ascending and rising movements (Figure 41.44).

Pause for a few seconds and let the Qi settle into the Lower Dantian (Figure 41.45).

Shift the body's weight, and repeat the entire sequence on the opposite leg. The turning of the waist should match the movements of the thighs. The toes should naturally grasp the ground and the soles of the feet should feel full of Qi. Repeat nine times on each leg, and end in a Wuji posture.

End the exercise by ascending and descending the Earth Qi through both legs.

From a Wuji posture, both hands embrace the abdomen to gather the Qi of the Lower Dantian and to separate the energy into two balls of energy (Figure 41.46).

Both hands then slowly descend the outside Yang channels of each thigh, all the way to the outside of the feet, ending at the Bubbling Well points (Figure 41.47).

Move the hands along the front of the feet, toward the inside of the foot, slowly ascending the inside Yin channels of each thigh all the way up the body into the Huiyin and Lower Dantian areas (Figure 41.48)

Pause and allow the Qi to settle in the Lower Dantian, then begin again (Figure 41.49). Repeat



Figure 41.41. Descend the Yang and Ascend the Yin Technique (Single-A)



Figure 41.42. Descend the Yang and Ascend the Yin Technique (B)



Figure 41.43. Descend the Yang and Ascend the Yin Technique (C)



Figure 41.44. Descend the Yang and Ascend the Yin Technique (D)



Figure 41.45. Descend the Yang and Ascend the Yin Technique (E)



Figure 41.46. Descend the Yang and Ascend the Yin Technique (Double-A)



Figure 41.47. Descend the Yang and Ascend the Yin Technique (B)



Figure 41.48. Descend the Yang and Ascend the Yin Technique (C)



Figure 41.49. Descend the Yang and Ascend the Yin Technique (D)

this exercise 18 times, then return to the Wuji posture and end the exercise.

TURNING AND WINDING THE BELT VESSEL TECHNIQUE

This tonifying exercise is divided into two methods: the Small Turning and Winding, and the Large Turning and Winding techniques. Each method of exercise causes a different action between the rotation of the energy's circle, the form's circle, and the internal turning action of the Lower Dantian.

Practice the Small Turning and Winding technique first, then proceed to the Large Turning and Winding technique. The small method uses a 180 degree semicircular rotation in addition to the Belt Vessel and Lower Dantian circle rotation.

When practicing the Large Turning and Winding method, the patient's mind must imagine a 360 degree circle rotation of the Belt Vessel. The body moves externally in one direction, while the energy in the Lower Dantian rotates in the reverse direction.



Figure 41.50. Small Turning and Winding (A)



Figure 41.51. Small Turning and Winding (B)



Figure 41.52. Small Turning and Winding (C)



Figure 41.53. Large Turning and Winding (A)



Figure 41.54. Large Turning and Winding (B)



Figure 41.55. Large Turning and Winding (C)



Figure 41.56. Large Turning and Winding (D)

The back and forth, side to side movements of the Turning and Winding action move the body's Qi, and stimulate the energy moving within the Belt Vessel's Qi circle. This energy circle fuses with the external rotation of the hands, allowing the energy from both external and internal Qi circles to be absorbed into the Lower Dantian. Once absorbed into the Lower Dantian, the Qi expands into the body's center core and blends with the Yuan Qi. This strengthens the waist, spine, and enables the Middle Burner's Qi to pervade through the upper and lower parts of the body. This exercise also develops strong and vigorous Kidneys and thus promotes the transportation of the Kidney's Jing and Qi.

SMALL TURNING AND WINDING TECHNIQUE

From a Wuji posture, step forward with the left foot to form a Leaning Horse stance. Raise both palms to waist level, in front of the Lower Dantian, with the palms facing the ground (Figure 41.50).

Inhale and shift the body forward towards the right direction and begin to rotate, turning and twisting the body in a clockwise direction. Imagine gathering the Earth's Qi into the Lower Dantian (Figure 41.51)

Exhale, but allow the mind to focus on absorbing the Earth Qi into the Lower Dantian. Pause for a minute, allowing the Qi to settle after filling the Lower Dantian (Figure 41.52). After nine circle rotations switch directions, moving in the opposite direction nine times.

LARGE TURNING AND WINDING TECHNIQUE

Bring the hands to the right side of the Mingmen and right Kidney area, while placing the mind's intention onto the Lower Dantian and navel area (Figure 41.53).

Inhale, as you extend both hands forward, and begin gathering the Earth's Qi (Figure 41.54).

Begin to circle rotate a 270 degree turn towards the left, while internally the energy of the Lower Dantian circles in the opposite direction to the right (Figure 41.55). Imagine the navel to be the center of the external circle and the Belt Vessel to be the internal circle. The mind's intention leads the energy which guides the hands and moves the body and the waist. The hand movements and center of weight shifting must be synchronized.

Exhale and gather the Earth's Qi into the left Kidney and Mingmen area; repeat nine times. Allow the Qi to fill the Mingmen and Kidneys, then switch directions for nine times (Figure 41.56). End in the Wuji position.

OPENING AND CLOSING THE HEAVEN AND EARTH TECHNIQUE

The purpose of this exercise is to cultivate and strengthen the Lower Dantian energy by blending it together with the Heaven and Earth Qi using the Beating and Drumming the Qi method of Qi cultivation. This cultivation method roots and stabilizes the body, causing the Five Hearts to return to their origin. The Five Hearts (sometimes called the Five Palms) are as follows:

- The Heart of the Baihui area (the Crown Chakra)
- The Hearts of each Laogong area (the palm Chakra)
- The Hearts of each Yongquan area (the bottom of each foot Chakra)

When the energy of the Lower Dantian disperses through the body, as the Mingmen pushes back, the Yuan Qi returns and gathers into the navel. This gathering and extending, back and forth action of energy of the Five Hearts transforms the body's Yuan Qi, strengthens the Yin and Yang energy, opens the body's channels, and encourages the merging of the Heart's Fire and the Kidneys' Water Qi. This method is divided into two techniques: Open the Heaven and Close the Earth, and Open the Earth and Close the Heaven techniques.

OPEN THE HEAVEN AND CLOSE THE EARTH

Begin from a Wuji posture with the left hand on the Lower Dantian and the right hand resting on top of it, both Laogong points face the navel (Figure 41.57).

Keep the mind's intention focused on the navel as the center base. Inhale as both arms raise up the center line of the body (Figure 41.58).

Extend the intention into the Heavens and begin to gather the universal Qi (Figure 41.59). Imagine Heavenly Qi descending and completely



Figure 41.57. Open the Heavens and Close the Earth (A)



Figure 41.58. Open the Heavens and Close the Earth (B)



Figure 41.59. Open the Heavens and Close the Earth (C)



Figure 41.60. Open the Heavens and Close the Earth (D)



Figure 41.61. Open the Heavens and Close the Earth (E)



Figure 41.62. Open the Heavens and Close the Earth (F)



Figure 41.63. Close the Heavens and Open the Earth (A)



Figure 41.64. Close the Heavens and Open the Earth (B)



Figure 41.65. Close the Heavens and Open the Earth (C)



Figure 41.66. Close the Heavens and Open the Earth (D)



Figure 41.67. Close the Heavens and Open the Earth (E)



Figure 41.68. Collect the Qi and Return it to the Lower Dantian (A)



Figure 41.69. Collect the Qi and Return it to the Lower Dantian (B)



Figure 41.70. Collect the Qi and Return it to the Lower Dantian (C)

filling the body (Figure 41.60). Exhale and gather the Heavenly Qi deep into the body's center core (Figure 41.61).

Lead the energy from inside of the body's center core to the outside, imagining Heavenly Qi, like steam, releasing through the pores and filling up the body's external energy bubble like a mist (Figure 41.62). Repeat 18 times.

OPEN THE EARTH AND CLOSE THE HEAVENS

This is the exact reverse action of the Open the Heaven and Close the Earth technique. Begin from a Wuji posture with the left hand on the Lower Dantian and the right hand resting on top of it, both Laogong points face the navel (Figure 41.63).

Inhale and begin to separate the hands, moving them to the outside of the body (Figure 41.64). Imagine gathering the Earth's Qi into the body as the hands raise upwards towards the head (Figure 41.65). Exhale and gather the Earth's Qi deep into the body's center core (Figure 41.66).

Lead the energy from inside of the body's center core to the outside, imagining the Earth's Qi, like steam, releasing through the pores and filling up the body's external energy bubble like a mist (Figure 41.67). Repeat 18 times, then pause and relax, returning to the Wuji posture.

COLLECT THE QI AND RETURN TO THE LOWER DANTIAN TECHNIQUE

The purpose of this exercise is to gather both universal and environmental energy and to store it in the navel. This exercise is used for treating Deficient conditions.

COLLECT AND RETURN

Begin from a Wuji posture and step out to the right, forming a Horse Stance. The left hand swings to embrace the navel and Lower Dantian as the body shifts its weight and twists toward the right (Figure 41.68).

The body slowly begins to shift from side to side while the opposite hand gathers the universal and environmental energy, gathering and packing it into the navel and Lower Dantian area (Figure 41.69).

During the exchange of left and right hands collecting Qi, imagine that the body is swimming in water. Imagine the energetic consistency of the air, like water, following each arm as it moves, flowing into the center of a whirlpool located in the navel and Lower Dantian area (Figure 41.70). Repeat 18 times. End in Wuji posture.

QIGONG SELF-HEALING MASSAGE AND POINT THERAPY

Qigong Massage and Point therapy is usually practiced after the Qigong meditations and exercise prescriptions. It involves having the patient lightly massage or tap the skin, while extending Qi into the various channels, points, and tissues. These self-healing massage techniques are specifically designed to disperse stagnations and Excess conditions, as well as to activate and regulate the energetic flow within the body's external and internal channels, thereby increasing the energy flow.

These massage techniques can be practiced from either a lying, sitting, or standing posture.

WASH THE FACE

This exercise stimulates the skin and facial muscles. Begin from a Wuji posture. Shake the hands vigorously to remove any External pathogenic Qi. Then slap the palms and rub the hands together vigorously until they get hot. Gently place both hands over the eyes and inhale, absorbing the heat into the face and Upper Dantian. While inhaling, allow the Qi to enter the Taiji Pole.

Exhale and imagine the energy gathered in the Upper Dantian descending down the center of the body, flowing into the Lower Dantian. Perform this gathering and descending action three times.

Next, both hands begin to wash the face, in an outward circular motion. Allow the hands to massage the face, up from the nose, eyes, and forehead, down along the temples, cheeks, and across the chin and mouth, returning back to the nose. Perform this face massage technique for 9 breaths.

Shake the hands vigorously to remove any External pathogenic Qi, then proceed to the next exercise.

MASSAGE THE HEAD

Guide all ten fingers over the head and down over the back of the neck (this is called Ten Dragons Run Through the Forest). Repeat nine times. This can be performed either by touching or not touching the head (Figure 41.71).



Figure 41.71. Wash the Face and Massage the Head: After rubbing the hands to heat the palms, place both hands on the face and draw the heat in through the eyes and into the Upper Dantian (1). Next, comb the hair with the fingertips (2), and drain the excess Qi from the head and neck area (3).



Figure 41.72. Beating the Heavenly Drum

BEATING THE HEAVENLY DRUM

This exercise balances the air pressure in the eustachian tubes and ear canals, relieves tinnitus, helps prevent vertigo, relaxes the mind, helps to improve hearing, expels stagnant Qi collected at the back of the head (within the Jade Pillow), and also stimulates the pineal gland and Kidneys' Qi.

Begin by interlacing the fingers and place both hands on the back of the head. The palm of each hand should cover the ears. While compressing the ears, close your eyes and practice the Beating and Drumming thumping method at the back of the head in the rhythmic sequence of a heart beat. This causes relaxation and creates an altered, in-utero state of consciousness. The index fingers of each hand should thump the Jade Pillow (Bl-9) at the back of the occiput pass 36 times (Figure 41.72).

After thumping the back of the head, clench the teeth, close the mouth, and bend the body over. Exhale while bending over and bring the head between the legs. The legs are straight, waist and buttocks are relaxed, and both eyes look towards the back from in-between the legs, while holding the breath (Figure 41.73).



Figure 41.73. Bend the Body Over While Holding the Breath

Next, raise the body up, inhale and again perform the Beating the Heavenly Drum sequence. Practice this exercise 14 times.

PRESSING THE EARS

This exercise is used to enhance hearing, stimulate mental energy and also to stimulate the Kidneys' Qi. Use the Laogong areas at the center of each palm to compress the ears (like a plunger). Repeat this exercise nine times (Figure 41.74).



Figure 41.74. Pressing the Ears

Next, move the right hand behind the head and pull the left ear (at a 45 degree angle) towards the back, with the left hand is placed on the Lower Dantian. Hold this posture for 9 breaths, then reverse for 9 breaths.

RUBBING THE EYES

RUBBING THE EYES (SEQUENCE #1)

This exercise is good for enhancing Qi and Blood circulation to the eyes for improving vision, treating eye diseases (especially glaucoma), relieving fatigue (caused by eye strain), and also for stimulating the Liver Qi.

With both thumbs resting on the cheekbones, form two soft fists and, using the edge of the index knuckles, begin to massage in a circle the top of the eyelids (from the bridge of the nose out along the eyebrows). Next massage just bellow the bottom of the eyelids from the bridge of the nose. Alternate from top to bottom 18 times (Figure 41.75).

RUBBING THE EYES (SEQUENCE #2)

With the thumbs still resting on the cheekbones, use the tip of the index fingers to massage the points around the eyes, from the inner corners of the skin, in a circular motion. Start rotating in a small circle, at the Bl-1 point. Circle nine times towards the inside, then nine times towards the outside, for a total of three breaths.

Next massage the middle of the eyebrows at the Extra Point Yu Yao. Then proceed to the outside of the eyes at the GB-1 point. (3) End at the base of the eyes at the St-1 point. Each area should be massaged 18 times (9 times towards the inside, then 9 times towards the outside) (Figure 41.76).

MASSAGING THE NOSE

This exercise is performed to treat colds, reduce swelling of the sinus tissues, eliminate mucus from the airways, stimulate the sinus nerves, open the nasal passages, and also stimulate the Lungs' Qi.

Begin by making soft fists and use the sides of the thumbs to massage the sides of the nose at the LI-20 points in an up and down motion 9 times pressing inward, and then 9 times pressing outward (Figure 41.77).

Next, use the tips of the index fingers and press deeply at the base of the nose at the LI-20 points, for a period of ten seconds, then circle-massage for 18 rotations. Press deeply midway up the nose, on both sides at the Bitong points for a period of ten seconds, then circle-massage 18 times. Finally, both fingers press deeply at the upper point at the bridge of the nose at the Shangen points for ten seconds, then circle-massage 18 times.

CLICKING THE TEETH

This exercise is good for strengthening the teeth and gums, tonifying the jaw muscles, im-



Figure 41.75. Rubbing the Eyes (Sequence 1)



Figure 41.76. Rubbing the Eyes (Sequence 2)

proving the Qi and Blood circulation to the gum tissues, and also to enhance the Kidneys' Qi. Clamp the jaws shut so that the teeth are pressing together and the jaw muscles flex. Click the teeth 36 times.

WAGGING THE TONGUE

This exercise is good for stimulating the salivary ducts beneath the tongue, and also for stimulating the Heart's Qi. Wag the tongue on the outside gums 18 times in one direction, 18 times in the opposite direction, then 18 times from the lower to upper palate, and finally, 18 times pressing the tip of the tongue against the back of the teeth (Figure 41.78).

SWALLOWING THE SALIVA

Saliva contains many kinds of enzymes which aid in digestion. In ancient China, this practice was sometimes called the Immortal's Water or Juice of Jade, because the saliva is energized during the Qigong meditation and believed to contain special healing properties.

To begin, inhale and swallow the saliva with a big gulp (three times), using the breath as a seal or bubble to enclose the air, then send it down the Conception Vessel to bathe the Five Yin Organs, ending at the Lower Dantian. It is important to tilt the head slightly forward (after inhaling) before swallowing the Immortal's Water.

WHIRLING THE NAPE AND TURNING THE NECK

The purpose of this exercise is to massage the thyroid and larynx as well as to stretch the muscles and tendons throughout the neck and cervical vertebrae.

To begin, place the back of the hands on the Kidneys. While relaxing, allow the head to relax and naturally hang, slowly rotating its motion to the left and right nine times (Figure 41.79).

Next, suspend the head and slowly twist the nape of the neck to the right and left direction nine times. While performing this exercise, focus the mind's intention on the Lower Dantian. When finishing, focus the mind's attention on the Bubbling Well points at the center of the feet.



Figure 41.77. Massaging the Nose



Figure 41.78. Wagging the Tongue

MASSAGING THE CHEST AND ABDOMEN

The purpose of this exercise is to disperse Excess Qi from the chest and abdominal area. This allows the body to balance the energy of the upper torso with that of the lower torso.

Beginning with the mind's attention focused on the Laogong areas at the center of each palm (Pc-8), brush the chest and abdomen downward nine times, starting from the collar bone and ending by the pubic bone (Figure 41.80).

MASSAGE TAPPING THE HANDS (LI-4)

Stimulating the Hegu or Joining of the Valleys points. The purpose of this exercise is to clear and activate the channels and collaterals, regulate, tonify and promote the circulation of Qi, to dispel pathogenic Wind, clear Fire and Heat, and to tranquilize the mind.

Begin by extending both arms in front of the body and allow both hands to collide into each other, thus tapping the Hegu points located between the thumb and first finger. Repeat nine times (Figure 41.81).

MASSAGE TAPPING THE FOREARMS (PC-6)

Stimulating the Neiquan or Inner Border Gate points. The purpose of this exercise is to regulate and tonify the Qi and Blood of the Heart and Stomach, to clear the Heart Fire, transform the Heart Phlegm, and to calm the Heart.

Begin by forming a hollow fist with the right hand and then lightly tap the Neiquan point located three fingers up from the wrist fold, on the lower left forearm area, nine times. Switch arms and repeat (Figure 41.82).

MASSAGE TAPPING THE ELBOWS (LI-11)

This exercise stimulates the Quchi or Crooked Pond points. The purpose of this exercise is to help dispel pathogenic Wind from the body, to regulate the Stomach and intestines, eliminate stasis, relax the muscles and tendons, lubricate the joints, and to cool the Heat in the Blood.

To begin, the right hand forms a hollow fist



Figure 41.79. Whirling the Nape and Turning the Head



Figure 41.80. Massaging the Chest and Abdomen



Figure 41.81. Massage Tapping LI-4

and lightly taps the Quchi point located at the end of the left elbow-fold, nine times. Switch arms and repeat (Figure 41.83).

MASSAGING UNDER THE ARMS (HT-1)

This exercise stimulates the Jiquan or Supreme Spring points. The purpose of this exercise is to regulate the Qi of the Lungs and Heart, promoting the circulation of Qi and Blood, as well as to regulate the blood vessels.

To begin, the right hand reaches under the left arm pit and circle massages nine times. Switch sides and repeat nine times (Figure 41.84).

MASSAGE TAPPING THE UPPER SHOULDERS (GB-21)

This exercise stimulates the Jianjing or Shoulder Well points. The purpose of this exercise is to regulate the body's Qi activities, disperse Liver Qi stagnation, extinguish Liver Wind, dispel Wind and Cold, redirect Rebellious Qi downward, and to dredge Excess Qi from all the Yang channels.

To begin, the right hand forms a hollow fist or soft palm and taps the left Jianjing point located on the upper ridge of the neck, while the left hand alternately taps the right Jianjing point. Both left and right tapping count as one set. Perform nine times (Figure 41.85).

MASSAGING THE ARMS

This exercise stimulates the six channels of the arms (the three Yang channels located on the outside, three Yin channels located on the inside).

Begin by placing the right palm on the inside of the left shoulder. Exhale and rub the entire arm from inside the shoulder and arm to the fingers. Next inhale and rub the entire outside of the arm from the fingers to the outside of the shoulder. Continue this movement for 18 breaths, then repeat on the other side (Figure 41.86).

MASSAGE TAPPING THE LOWER DANTIAN (CV-6)

This exercise stimulates the Qihai or Sea of Qi points. The purpose of this exercise is to energize and tonify the lower abdominal organs, as well as to stimulate the Qi of the Lower Dantian.



Figure 41.82. Massage Tapping Pc-6



Figure 41.83. Massage Tapping LI-11



Figure 41.84. Massaging Under the Arm Ht-1



Figure 41.85. Massage Tapping GB-21

Begin by stroking the chest, gathering the body's Qi down into the Lower Dantian. Using either soft fists, palms, or fingers, both hands lightly tap the Lower Dantian and navel area for three breaths (Figure 41.87).

MASSAGE TAPPING THE BACK OF THE WAIST (GV-4)

This exercise stimulates the Mingmen or Gate of Life point. This exercise stimulates and tonifies the Kidneys, adrenal glands, and the Mingmen. It is used to regulate the Governing Vessel, excite and strengthen Kidneys' Yang Qi, to replenish the Kidneys, as well as to strengthen the lower back and bones.

Begin by slightly leaning the body forward. Using the right and left soft palms or hollow fists, lightly tap the back of the waist, Mingmen and the Kidneys' area for three breaths (Figure 41.88).

MASSAGE TAPPING THE SIDES OF THE HIPS (GB-30)

This exercise stimulates the Huantiao or Jumping Circle points. The purpose of this exercise is to dispel Wind and Cold, reduce pain in the thighs and legs, as well as to strengthen the lower back, and tonify the lower extremities.

Using the right and left hollow fists or soft palms, lightly tap the hip bone Huantiao points nine times (Figure 41.89).

MASSAGE TAPPING THE THIGHS (GB-31)

This exercise stimulates the Fengshi or Wind's Market points. The purpose of this exercise is to dispel Wind and Cold, clear Heat, tonify the legs, reduce flaccidity and numbness of the lower extremities, and to transform Dampness.

Using the right and left hollow fists or soft palms, lightly tap the upper thighs at the Fengshi Points nine times (Figure 41.90).

MASSAGE TAPPING THE OUTSIDE OF THE KNEES (GB-34)

This exercise stimulates the Yanglingquan or Yang Mound Spring points. The purpose of this exercise is to relax the muscles and tendons, acti-



Figure 41.86. Massaging the Arm Channels


Figure 41.87. Massage Tapping the Lower Dantian


Figure 41.88. Massage Tapping the Mingmen GV-4


Figure 41.89. Massage Tapping GB-30

vate the flow of Qi and Blood in the channels and collaterals, relieve spasms and pain, clear away Damp-Heat, and disperse stagnant Liver and Gall Bladder Qi.

Using the right and left hollow fists or soft palms, lightly tap the outside of the knees at the Yanglingquan points nine times (Figure 41.91).

MASSAGE TAPPING THE INSIDE OF THE KNEES (SP-9)

This exercise stimulates the Yinlingquan or Yin Mound Spring points. The purpose of this exercise is to regulate and tonify the Spleen (Yang), Stomach (Yin), and Lower Burner, to resolve Dampness and Damp Heat, as well as to treat knee pain and problems with difficulty in urination.

Using the right and left hollow fists or soft palms, lightly tap the inside of the knees at the Yinlingquan points nine times (Figure 41.92).

MASSAGE TAPPING THE BACK OF THE KNEES (BL-40)

This exercise stimulates the Weizong or Entrusting Middle points. The purpose of this exercise is to relax the muscles and tendons, activate the flow of Qi and Blood in the channels and collaterals, cool the Blood to stop bleeding, transform Damp Heat in the Bladder and intestines and to strengthen the waist and knees.

Using the right and left hollow fists or soft palms, lightly tap the back of the knees at the Weizhong points nine times (Figure 41.93).

MASSAGE TAPPING BELOW THE KNEES (ST-36)

This exercise stimulates the Zusanli or Foot Three Miles points. The purpose of this exercise is to regulate the Stomach and intestines, facilitate the flow of Qi to relieve bloating and distention, to dissipate stagnation and obstructions, to promote the circulation of Ying Qi, to alleviate water retention and subdue swelling, and to activate the flow of Qi and Blood in the channels and collaterals.

Using the right and left hollow fists or soft palms, lightly tap the lower leg Zusanli points nine times (Figure 41.94).



Figure 41.90. Massage Tapping GB-31



Figure 41.91. Massage Tapping GB-34



Figure 41.92. Massage Tapping Sp-9



Figure 41.93. Massage Tapping Bl-40

MASSAGE TAPPING ABOVE THE MEDIAL MALLEOLUS (SP-6)

This exercise stimulates the Sanyinjiao or Three Yin Crossing points. The purpose of this exercise is to tonify and regulate the Qi and Yang of the Spleen, as well as regulate the Qi of the Stomach, Middle and Lower Burners, reduce digestive stagnation, and to facilitate Blood flow.

Using the right and left hollow fists or soft palms, lightly tap the inside of the lower leg at the Sanyinjiao points nine times. (Figure 41.95).

MASSAGE TAPPING THE HEELS (KD-1)

This exercise stimulates the Yongquan or Bubbling Spring points. The purpose of this exercise is to tonify the Kidneys' Yin and Jing, tranquilize the mind, clear away Heat, purge pathogenic Fire, calm the Liver and to stop pathogenic Wind.

To begin this exercise make sure that the knees are slightly bent. Quickly rise and fall on both heels to stimulate the Yongquan points and shake the back nine times (Figure 41.96).

TREMBLING THE KNEES

The purpose of this exercise is to disperse stagnant Qi, as well as to relax the perineum.

To begin this exercise, relax, then bend and straighten the knees quickly for nine times. Next shake them from side to side quickly in order to tremble and shake the entire body. Repeat nine times (Figure 41.97).

CIRCLING THE ABDOMEN

The purpose of this exercise is to balance the Lower Dantian Qi, stimulate the Stomach and bowels, and enhance digestive peristalsis.

To begin, place the center of both palms on the Lower Dantian, embracing the navel (for men, the left palm is on the top, opposite for women). Focus the mind's intention deep into the Lower Dantian. While using the navel as the center, connect the energy of the Lower Dantian with the center of the palms as they rotate.

Begin to circle 36 times counterclockwise for men (from the patient's point of view), whereas the rotation is clockwise for women. Allow the circle to gradually move from a smaller to a larger



Figure 41.94. Massage Tapping St-36



Figure 41.95. Massage Tapping Sp-6



Figure 41.96. Dropping the Heels to Stimulate Kd-1

rotation (as the hands circle, imagine that they are dispersing the Qi). Pause and reverse the circle, rotating 24 times in the opposite direction, gradually reducing the circle's size. This will draw the Qi from the outer portion of the body and collect it into the Lower Dantian. Pause for a moment then return to the Wuji position (Figure 41.98).

COMPLETING THE EXERCISE

Upon completion of the exercise, close the Four Doors (the center of each palm and foot) and cultivate the Qi with stillness, allowing the energy to return to its origin. Hold a quiet Wuji postue for about 15 minutes.

The purpose for the first circle rotation is to release the Yuan Qi which has been collected and gathered in the Lower Dantian. This is to avoid any stagnation which may cause the energy flow to slow down. This also disperses and releases the Yuan Qi, allowing it to blend with the Essential Qi of the Five Yin Organs.

When performing the reverse or second circle rotation, allow all the dispersed energy to gather together and return back to the Lower Dantian. This accumulates and stores the organ energy, blending it together with the Original Qi.



Figure 41.97. Trembling the Knees



Figure 41.98. Circling the Abdomen to Finish

CHAPTER 42
DAOIST QIGONG REGULATION EXERCISES

This particular school of Daoist Medical Qigong Regulation was first introduced in the West by one of my teachers, Dr. Her Yue Wong. These techniques have become increasingly popular, as they are simple, yet extremely effective in tonifying and regulating the body's organ energy.

The interesting thing about Western healing practices is that they focus on the neuromuscular skeletal system to the exclusion of the visceral system, not recognizing that the visceral system is necessary to supply the fuel for the neuromuscular system. These following exercises focus on the visceral system and enhance the quality of life of the viscera.

The system as a whole is divided into two sections. The first section stimulates, energizes, and regulates the body's Yang organs and channels. The second section stimulates, energizes, and regulates the body's Yin organs and channels.

The exercises can be practiced as a complete system, or singled out individually and practiced as tonification prescriptions. As with any Medical Qigong prescription, the patient must purge his or her body of Toxic Qi before starting the tonification exercise and return the Qi back to the Lower Dantian upon completion.

DAOIST FIVE YANG ORGAN REGULATION EXERCISE

This exercise massages the five Yang digestive organs, strengthens the peristaltic action of the body's digestive system, as well as increases the capillary circulation through the stimulation of the autonomic nervous system. The Yang digestive organs (Stomach, Small Intestine, Large Intestine, Urinary Bladder, and Gall Bladder) are used by the body to release waste and Turbid Qi; therefore, it is important to keep the Yang organs strong and functioning smoothly.

The Beating and Drumming the Qi Breath Regulation (which is employed within this exercise) is beneficial for those patients who suffer from digestive problems and irregularity (i.e., spastic colon, chronic diarrhea, irritable bowel syndrome, etc.).

When the patient's arms swing rhythmically throughout the exercise, the nerves and Qi channels of the shoulder joints become stimulated. The swaying action of the arms increases the circulation in the energetic channels which connect the different internal organs and terminate at the hands.

Although this exercise is simple, the result in strengthening the body's peristaltic action and curing digestive illnesses is very effective. The patient is therefore cautioned not to eat prior to practicing this exercise.

SWAYING THE ARMS WHILE BEATING AND DRUMMING THE QI

Assume a wide stance with the arms suspended by the sides of the body. While inhaling, swing the arms up straight out in front of the body and then bring the hands in by the chest (Figure 42.1). Expand the abdomen fully focusing the mind's inten-



Figure 42.1. The Daoist Five Yang Organ exercise. Inhale and draw the Qi into the Lower Dantian while swinging the hands forward.

tion on filling the lower abdomen with Qi.

When exhaling, swing the arms back behind the body while compressing the abdomen down and inward directing the Qi to flow from the lower perineum, circulate back into the sacral area, then to the navel and back down to the perineum (Figure 42.2).

Continue to swing the arms back and forth at a pace that is comfortable using natural breathing. The abdomen should expand and contract without forcing the respiration. The patient must have the anal sphincter closed throughout the entire exercise. Continue this repetition for at least 50 breaths. Try to work up to 250 breaths or more for chronic conditions of abdominal obstruction and Qi stagnation within the digestive system.

The pressing and releasing action of the abdomen stimulates the energetic functions of the autonomic nervous system. The autonomic nervous system has two divisions:

1. The fight or flight mechanism of the sympathetic division -- which shuts down the digestive system due to the production of adrenaline or norepinephrine and redirects Qi and Blood flow to the brain and skeletal muscles, and
2. The vegetative, renewal mechanism of the parasympathetic division -- which draws Qi and Blood from the brain into the digestive system.

The centers for neuronal control of the autonomic nervous system and also control the digestion and tubal contraction are located in the cranium and in the sacrum. The accessory nerve and vagus nerve carries from the brain stem, its nucleus (or center), all of the information to supply the digestive system with impulses to stimulate peristaltic contraction. At the lower end of the digestive system, the sigmoid colon, rectum, Bladder and uterus are controlled by nerve fibers coming from the first, second, and third sacral foramina. The action of the cranial-sacral division of the parasympathetic nervous system is to stimulate peristaltic action (hence the movement of nutrients through the digestive system).

The movement of the abdominal cavity, diaphragm, and thoracic cavity changes the position of each organ and enhances its function. By tightening the anal sphincter and compressing and releasing the urogenital diaphragm, the reproductive organs are also stimulated, including the uterus, prostate, urethra, and testicles. Finally, the Daoist Five Yang Organ Regulation exercise also enhances the peristaltic action of the body's lymphatic system, circulatory system, and tubal systems.



Figure 42.2. Exhale and compress the abdomen, allowing the hands to swing behind the body.

DAOIST FIVE YIN ORGAN TONIFICATION AND REGULATION EXERCISES

Each of the following exercises are designed to stimulate the specific internal Yin organ, as well as the paths of energy that flow from the channels of each organ. Since the Yin organs have the responsibility of storing energy, each exercise is named for the organ it tonifies.

The Yin exercises are performed in the sequence shown below without pausing in-between transitions. Unless specifically prescribed as a therapeutic modality, each exercise should flow directly into the next. The transitions are very important for continuity of energy flow. This particular Five Yin Organ series begins with an opening exercise and ends with a closing exercise.

OPENING, COLLECTING, AND MOVING THE QI

The opening exercise is designed to stretch and loosen the spinal vertebrae and to facilitate the energy flow through the patient's Governing Vessel. The spinal stretch also stimulates the flow of fluids and electrical impulses in the central nervous system (brain and spinal cord), which is nurtured by the cerebral spinal fluid. When the fluid starts to move, it awakens the nervous system causing more nutrients to enter the cellular structure of the nerves. The stretching, compressing, and pumping action of the spinal cord stimulates the movement receptors located in all of the ligaments and fascia energizing the body's entire proprioceptor mechanism.

The opening exercise is also designed to stretch the connective tissue, warm the body's intercellular matrix and tissues, stimulate the somatic system, free adhesions, as well as enhance the elasticity and compressibility of the ligamentous structure.

After finishing the Daoist Five Yang Organ Regulation exercise, return both hands to the Lower Dantian. Next, raise both hands above the head as you inhale (Figure 42.3).

Imagine energy (like a rushing river) flowing up from the feet, filling the legs, hips, waist, chest, arms, and head. Every square inch of the body is absorbing and being saturated with this Earth energy. When the entire body is completely full, the hands should still be positioned above the head (Figure 42.4).

Begin to exhale and feel the hands getting very heavy. The heaviness pulls the hands forward and then slowly starts to pull the body over. Slowly bend the head forward and feel the cervical vertebrae stretch. Let the hands pull the arms, which in turn will pull the shoulders and torso, followed by bending at the waist. The purpose of this movement is to feel each vertebra of the spine stretch sequentially so that a rippling effect descends down the spine. This will facilitate maximum stretch of the spine. While bending over, exhale and imagine the energy melting away from the entire body (like ice melting into water) slowly dissolving and rushing down through the feet and out into the ground (Figure 42.5).

Once completely bent over, imagine picking up a ball. Bend the knees and slowly stand up. While standing up, reverse the rippling of the spine from the coccyx, sacrum, and lower lumbar vertebrae to the base of the skull (Figure 42.6). Repeat these movements five times. Remember to inhale while raising the body, bring both arms over your head, and exhale as the body descends.



Figure 42.3. The Daoist Five Yin Organ Opening exercise. Begin by stretching the arms above the head.



Figure 42.4. Inhale and imagine the Earth Qi like water filling the entire body.



Figure 42.5. Exhale, bend the body and imagine any tension melting out the body into the Earth.



Figure 42.6. For the transition movement to the Lung Tonification exercise: inhale, bend the knees and slowly stand up.

LUNG TONIFICATION AND REGULATION EXERCISE

This exercise is designed to massage the Lungs' tissues and nerves, as well as tonify the entire Lung organs and channels. In the Lung exercise, both the sympathetic and parasympathetic divisions of the autonomic nervous system are stimulated. The compression and release action of the scapulae and thoracic vertebrae stimulate the nerves, arteries, veins and capillary system in the thoracic region.

Compressing and releasing of the muscles and blood vessels in the back and chest areas stimulates the transforming of the Qi and Blood and enhances the health of the individual tissue cells. The compression and release of the thorax also increases the stimulation of the nervous system in the Lung area, as well as stimulates the "release and return" action of the lymphatic system. All the major lymphatic ducts are located in the posterior portion of the thoracic wall.

The compression and release of the second, third, and fourth thoracic vertebrae stimulates the sympathetic preganglionic fibers from the spinal cord, which in turn stimulates the postganglionic fibers and the sympathetic outflow to the Lungs and bronchi. Patients practice this exercise to strengthen their respiratory system as well as increase the production of their Wei Qi to enhance their body's immune system.

Upon completion of the Opening exercise, the patient brings the hands above the head and places them in front of the torso at shoulder level while exhaling. The patient's palms should be facing downward parallel with the floor (Figure 42.7).

Inhale and bring the arms straight out to the sides (both hands should not go any higher than the shoulders) (Figure 42.8).

As the arms reach the sides of the body, rotate the palms until they face upward. Keep the shoulders stable and relaxed (Figure 42.9).

While exhaling, bring the arms straight out in front of the body returning to the beginning posture (Figure 42.10).

Allow the scapulas to gently push the arms forward. The sternum at this point is pushed inward so as to hollow the chest. Once the hands are aligned in the front of the shoulders, rotate the arms and



Figure 42.7. The Lungs Tonification exercise: Inhale as the hands separate.



Figure 42.8. Separate the Hands and turn the palms upward.



Figure 42.9. Exhale as you bring the arms toward each other.



Figure 42.10. Draw the hands toward each other and turn the palms facing the Earth.

inhale to begin again. Repeat 20 times.

Note: Do not let the hands touch when bringing the arms back together towards the center line of the body. The body will short circuit itself, resulting in a mild shock or a sick feeling inside the thorax by the Heart.

KIDNEY TONIFICATION AND REGULATION EXERCISE

This exercise is designed to massage the Kidneys' tissues and nerves, as well as tonify the entire Kidney organs and channels. According to Western physiology, the Kidneys maintain the chemical, pH (potential of hydrogen), and temperature balance of the Blood. The Kidneys function like a rheostat changing the body's ability to absorb, retain, or release water according to the environment (e.g., retaining water in hot climates).

The twisting back and forth, pumping action of the exercise stimulates an opening and closing action within the Kidney organ. The Kidneys receive the major Blood supply from the abdominal aorta. In the Kidney exercise, the action of raising the torso upwards will literally suck Qi and Blood into the Kidney area.

Patients practice this exercise to strengthen their reproductive system, as well as increase the production of their Jing. It also helps balance the body's general energy condition, and can be used to treat sexual disorders and malfunctions.

Upon completing the Lung exercise, both arms are extending straight out in front of the body (Figure 42.11).

Inhale and drop the elbows and bring the hands down in front of the Lower Dantian (Figure 42.12).

Exhale and shift the weight to the left. As the left outer palm wraps around the back, resting itself on the right Kidney, the right palm extends towards the left direction (Figure 42.13).

The right palm, facing outward towards the left direction, begins to circle upwards in front of the face at eye level. As the palm begins to move, the eyes watch the back of the right palm (Figure 42.14).

Shift the weight towards the right side of the body and begin leaning towards the right direction. The eyes continue to follow the right palm as it begins to circle downwards in front of the body. Ex-



Figure 42.11. After completing the Lung exercise, center the body to prepare for the Kidney Tonification exercise.



Figure 42.12. Preparation for the Kidney Tonification Exercise



Figure 42.13. Kidney Tonification Exercise: exhale as the left outer palm wraps around the right kidney, and the right palm extends outward in a left direction.



Figure 42.14. Begin to inhale as the right palm circles upwards and turns outward at eye level and begins to descend.

hale while shifting the weight (Figure 42.15).

Shift the weight, bend the knees and begin to lean over. While continuing to exhale, imagine scooping water with the right palm. Bend at the waist and scoop with the right arm. Keep the back relaxed and straight (Figure 42.16).

Allowing the right arm to follow the motion of the body, begin rising up slightly while turning forming an arc in front of the torso. As the palm raises, imagine the energy (which has been scooped into the arm) draining down the right arm across the shoulders and down the left arm into the right Kidney. Repeat this side for ten breaths (Figure 42.17).

After completing 10 breaths switch directions by shifting the weight onto the right leg (Figure 42.18 and Figure 42.19).

The right hand wraps the torso ending at the left Kidney and Mingmen area while the left palm is positioned in front of the face. Begin to inhale and repeat 10 times on the opposite side.

LIVER TONIFICATION AND REGULATION EXERCISE

This exercise is designed to massage the Liver's tissues and nerves, as well as tonify the entire Liver organ and channels.

According to Western physiology, the Liver is the body's master filter, collecting all of the nutrients that are being absorbed from the digestive system via the hepatic portal vein. The Liver functions like a series of channels. The cells of the channels are considered the processing factory for the entire body. If the body has a need for a particular nutrient, the Liver will create the enzymes for digestion, breaking down into components that which the body needs (or storing the components until needed). The Liver is also responsible for detoxifying, producing antibodies, and creating new cells to handle foreign substances recently absorbed by the body (storing substances of which it has no need).

The compression and release action of the torso causes a physical compression within the Liver organ itself, flushing Qi and Blood from the digestive system through the Liver and into the Gall Bladder where bile is stored.



Figure 42.15. Continue inhaling as you bend over at the waist. Once your head sinks below your hips begin to exhale. Allow your right palm to circle downward to the left.



Figure 42.16. Continue exhaling as your weight shifts to the other foot and imagine the palm scooping up water as the body begins to circle upward.



Figure 42.17. As the torso begins to arch upwards, allow the right arm to follow the body's movement. As the arm reaches the chest level, turn the outer palm towards the face and begin inhaling.



Figure 42.18. Preparation to switch hand positions: Shift the body's weight onto the right leg as the right arm begins to move to the back left Kidney and the left arm leaves the right Kidney to move forward.



Figure 42.19. Kidney Regulation exercise final movement: begin to inhale as the left palm circles upwards and turns outward at eye level and begins to descend to the left.

Patients practice this exercise to strengthen their tendons and ligaments. This exercise helps to regulate the patient's emotional state.

Upon completing the Kidney exercise, begin to unwind the arm from behind the back and rotate the hips so they face forward (Figure 42.20).

Place the right arm straight out in front of the body, shoulder level, palm facing down. Place the left hand by the left hip, palm facing up (Figure 42.21).

Simultaneously draw the right palm back and extend the left palm forward while inhaling. The left hand moves forward passing the right hand which is moving backwards (Figure 42.22).

The hands continue in this motion extending outward from the center line of the body. Use long, slow inhalation and exhalation, inhaling and exhaling every three moves. Relax and continue to repeat this sequence for 20 breaths (Figure 42.23).

HEART TONIFICATION AND REGULATION

This exercise is designed to massage the Heart's tissues and nerves, as well as tonify the entire Heart organ and channels.

The compression and release of the skeletal muscles squeezing and releasing the cardiac muscle energetically stimulates the pericardium surrounding the heart. The twisting movement and compression of the torso also enhances the fluidity of all the connective tissues that are involved with the Heart. Every time the thoracic wall moves, expands, contracts, or twists, the tissues of the Heart are pulled, stretched, and released.

Patients practice this exercise to strengthen their circulatory system. This exercise helps to



Figure 42.20. Preparation for the Liver Tonification Exercise: upon completing the Kidney exercise, begin to unwind the arm from behind the back and rotate the hips so they face forward.



Figure 42.21. Liver Tonification Exercise: place the right arm straight out in front of the body, shoulder level, palm facing down. Place the left hand by the left hip, palm facing up.



Figure 42.22. Simultaneously draw the right palm back and extend the left palm forward while inhaling. The left hand moves forward, passing the right hand which is moving backwards.



Figure 42.23. Use long, slow inhalation and exhalation, inhaling and exhaling every three moves.



Figure 42.24. Preparation for the Heart Regulation Exercise: upon completing the Liver exercise allow both hands to sink down in front of the lower abdomen.



Figure 42.25. Heart Tonification Exercise: imagine the hands embracing a ball, placing the right hand on top, and the left hand on bottom: inhale.

stimulate the patient's intellectual activity and mental acuity or clarity.

Upon completing the Liver exercise allow both hands to sink down in front of the lower abdomen (Figure 42.24).

Imagine the hands embracing a ball, placing the right hand on top, and the left hand on bottom (Figure 42.25).

Exhale and twist the hips to the left, simultaneously raising the left hand up over the head while extending the right hand towards the left (Figure 42.26).

Continue pressing until both hands extend to the furthest point (Figure 42.27).

Inhale and turn the right palm upwards facing the sky as the body twists back to the center allowing the right hand to end up in front of the navel (Figure 42.28).

The left hand simultaneously turns so that the palm faces the center of the right hand following it to the center line of the body (Figure 42.29).

As the body reaches the point where it faces forward, twist to the right side and push in the same manner while exhaling. Repeat 10 times on each side (Figure 42.30).



Figure 42.26. Exhale and twist the hips to the left simultaneously raising the left hand up over the head while extending the right hand towards the left.



Figure 42.27. Continue pressing until both hands extend to the furthest point.



Figure 42.28. Inhale and turn the right palm upwards facing the sky as the body twists back to the center allowing the right hand to end up in front of the navel.



Figure 42.29. The left hand simultaneously turns so that the palm faces the center of the right hand following it to the center line of the body.



Figure 42.30. As the body reaches the point where it faces forward, twist to the right side and push in the same manner while exhaling.

SPLEEN TONIFICATION AND REGULATION EXERCISE

This exercise is designed to massage the Spleen's tissues and nerves, as well as tonify the entire Spleen organ and channels.

Raising the arms above the head stretches all of the suspensory ligaments of the Spleen making the Spleen energetically accessible by the twisting movements of the torso. The compression and release action on the connective tissue and fascia that support the placement of the Spleen allows the internal channels to become dilated facilitating a greater flow of Qi and Blood into the organ.

While looking up and turning to the right, the left brain is stimulated. Consequently, by looking up and turning to the left, the right brain is stimulated. According to Western physiology, light waves come into the eyeballs through the retina stimulating the optic nerve, chiasma, tract, lateral geniculate body (stimulating the thalamus), superior colliculi (in the brain stem where visual reflexes are initiated), optic radiations, cerebral cortex, and occipital (visual) cortex, which integrates both visual and memory impulses responsible for the perception of the image. Half of the information received from the right eye goes to the right side of the brain, while the other half of the information crosses over and stimulates the left brain.

Patients practice this exercise to strengthen their digestive system, as well as to enhance their visual equilibrium.

Upon completion of the Heart exercise, bring both hands down to the waist level, palms facing downward. Circle them above the head and perform the Pulling Down the Heavens exercise. Next, move the palms towards the outside of the knees while twisting the thumbs to point towards the back of the body (this stimulates the Luo points of the arms and squeezes the Wei Qi of the hands and arms deep into the bones) (Figure 42.31).

The thumb and index fingers touch and form a triangle as the hands slowly raise above the head (Figure 42.32).



Figure 42.31. Preparation for the Spleen Regulation Exercise



Figure 42.32. Spleen Regulation Exercise: the thumb and index fingers touch and form a triangle as the hands slowly raise above the head.

The eyes look through the center of the triangle as the upper torso is turned from side to side. It is important that the hips remain stationary and that the upper torso rotate in order to massage the digestive organs. Inhale in the center. Exhale on each side. Repeat 10 times on each side (Figure 42.33).

ENDING, ROOTING, AND STABILIZING THE QI

The purpose of the ending is to gather the Qi back into the patient's Lower Dantian rooting and stabilizing the patient's Qi. This ending exercise is very important as its initial goal is to gather any excess Qi developed from the over stimulation of the Five Yin Organs and to collect the runoff energy into the Lower Dantian (where it can be absorbed and used by the Eight Extraordinary Vessels). Otherwise, if the individual unknowingly has a preexisting Excessive condition in a particular Yin organ, the additional tonification can exasperate the organ's condition. To avoid this Excess condition, certain Medical Qigong schools will use external massage and lightly brush the energetic channels after practicing certain Qigong exercises and meditations to disperse any excess Qi.

The soft compression used during the ending exercise increases the partial pressure of oxygen in the Blood as more oxygen passes into the cells. The action of moving oxygen into the cells creates a movement of carbon dioxide out of the cells increasing the exchange rate and establishing a greater metabolic breakdown.

The breathing initiated for the ending exercise is known as "Turtle Breathing." The Turtle Breathing method requires slow respiration and stimulates the center hub of the Belt Vessel.

Upon completion of the Spleen exercise, exhale and start to separate both hands (as if embracing a ball) (Figure 42.34 and 42.35).

Bring both hands down to waist level and separate the arms, moving the hands away from the center of the body (Figure 42.36). Inhale and raise the arms up over the head. Each hand is placed above the head as if embracing a ball (Figure 42.37).

Exhale and form loose fists with the hands (Figure 42.38).



Figure 42.33. The eyes look through the center of the triangle as the upper torso is turned from side to side. Inhale in the center, exhale on each side.



Figure 42.34. Preparation for Ending the Daoist Five Yin Organ Exercise (a)



Figure 42.35. Preparation for Ending the Daoist Five Yin Organ Exercise (b)



Figure 42.36. Preparation for Ending the Daoist Five Yin Organ Exercise (c)



Figure 42.37. Ending the Daoist Five Yin Organ Exercise: each hand is placed above the head as if embracing a ball.



Figure 42.38. Exhale and form loose fists with the hands.



Figure 42.39. As you bend over, slowly turn the soft fists so that the curled fingers face the body and begin squatting, forming a Turtle Posture.



Figure 42.40. Inhale and slowly begin to raise the body up while opening the fists, and allow the hands to return back to their original position at the sides of the body.

As you bend over, slowly turn the soft fists so that the curled fingers face the body and begin squatting forming a Turtle Posture (Figure 42.39).

Inhale and slowly begin to raise the body up while opening the fists and allow the hands to return back to their original position at the sides of the body (Figure 42.40). Repeat five times and end in the Wuji posture.

When practicing the Turtle Breathing method, the mind's intention and respiration should be focused onto the Lower Dantian, navel, and Mingmen areas of the body.

The Lower Dantian is divided into eight sections (see Figure 42.41). Each section is numbered, beginning with the front of the Lower Dantian at the navel area (1), increasing in number as one continues over the left and right sides of the waist (4), ending at the Mingmen area (8).

Think of the anal sphincter as a great funnel, attached in eight different segments (like canals) which progress up the torso. As you focus your mind on each section (begin with the navel at section 1), allow any excess energy to flow downwards from that particular section to be gathered into the Lower Dantian. With your imagination, direct the breath and Qi from your torso to flow into each of the eight areas.

The breath and Qi should be slowly inhaled and guided into the Lower Dantian via the anal sphincter area for an even three counts. Then, proceed to gather Qi from the next consecutive area of the body. By pulling upwards on the anal sphincter and perineal areas, an energetic vacuum is created within the pelvic diaphragm and urogenital diaphragm. This energetic vacuum is used to gather the internal organ's excessive Qi.

Begin with collecting Qi from the front of the body, to the navel via the anal sphincter. Hold the Qi in the Lower Dantian area for three counts, then proceed to the next areas at the sides of the body absorbing the Qi into the Lower Dantian via the anal sphincter for three counts.

Next, proceed to the sides of the body continuing in progression until you reach the Mingmen area (8). Then, reverse the progression beginning with the Mingmen and working around


Left Ovary,
Left Breast,
Heart,
Conception Vessel,
Reproductive Organs,
Bladder
Right Ovary,
Right Breast,
(1)
Navel
Transverse Colon,
Small Intestines
(2)
(2)
Transverse Colon,
Small Intestines
(3)
(3)
(4)
(4)
Descending
Colon
Ascending
Colon
(5)
Spleen,
Stomach
(5)
Liver,
Gall Bladder
(6)
(6)
Left
Lung
Right
Lung
(7)
Mingmen
(7)
Left
Kidney
(8)
Right
Kidney
Governing Vessel,
Spinal Cord,
Brain

Figure 42.41. When practicing Turtle Breathing, inhale and slowly begin drawing the Qi from the front of the body into the navel area (1), absorbing the energy from the Heart, Conception Vessel, reproductive organs, and Bladder into the Lower Dantian. This absorbing action is created by pulling upwards on the anal sphincter in the direction of the intended energy. Next, proceed to the sides of the body. In women, the next area (2) will include the excess energy gathered from both the left and right ovaries, as well as the left and right breasts. In men, however, this area (2) is considered general and not specific to certain internal organs or tissues. Continue in the progression of circling the waist until you have reached the Mingmen area (8). Then, reverse the order of the tissue areas (8, 7, 6, etc.).

the waist until you reach the navel (8, 7, 6, etc.). Make sure that you push your anal sphincter towards the direction of the area of the body from which you are absorbing Qi.

After perfecting the Turtle Breathing, a practitioner can create the energetic vacuum and initiate the absorption of excess Qi into the Lower Dantian by moving his or her intention from the anal sphincter through the Lower Dantian and torso at an extremely fast speed.

SECTION X

TREATMENT OF INTERNAL DISEASES WITH QI EMISSION THERAPY

INTRODUCTION

Clinical records from China verify that Medical Qigong treatments are most effective on nervous system diseases, migraines, bronchial asthma, nocturnal enuresis, psychosomatic diseases, gastric ulcers, arthritic pains, sterility, and in the elimination of ovarian cysts and benign tumors.

The following chapters are designed to assist the Medical Qigong doctor in his or her professional clinical practice, by explaining the various techniques and prescriptions used in several Medical Qigong Hospitals, Institutes and Colleges throughout China.

These Medical Qigong techniques are presented as basic guidelines for the Qigong doctor to use, and need not be followed exactly to the letter. They are presented as an example to advise Qigong doctors in treatment and prescription protocols.

I have personally found these various approaches of Chinese energetic medicine to be extremely effective in my own clinical practice, and have therefore encouraged the directors of the International Institute of Medical Qigong to instruct their students in the following techniques.

This particular section of the book (Section X) deals with the treatment of Zang (Yin) and Fu (Yang) disharmonies in clinical practice, and discusses general and specific diagnosis, treatments, and prescriptions. I will begin by exploring several examples of the Five Elements' disease patterns and the various techniques used to treat them (Chapter 43-48). Starting with the treatment of Liver diseases, I will progress to the treatment of Heart, Spleen/Stomach, Lung and Kidney Diseases.

In the ending chapter in this section emphasis will be placed on the practical application and theoretical principles of "Miscellaneous" diseases and their treatments.

CHAPTER 43
QI EMISSION THERAPY FOR LIVER DISEASES

INTRODUCTION

The Five Yin Organs' interrelationship with each other, and their complex interrelationship with the energetic ebb and flow of Qi must constantly be regulated to maintain health. The constant flux of energetic flow within the body sometimes causes an Excess or Deficiency of Qi requiring specific organ therapy for restoration and balance. This therapy is designed to bring the specific organ or organ systems back into balance by using various meditations, visualizations and breathing exercises.

This section focuses on specific Liver diseases and how to rectify them. The Liver is responsible for the circulation and smooth movement of the body's internal Qi.

The Liver is a solid (Zang) organ which stores the Blood and is attributed to the element Wood. The Liver is sometimes referred to as the Green Emperor. The Liver is in charge of strategy without hesitation. It is energetically paired with the Gall Bladder (a hollow organ) which carries out the decisions made by the Liver (Figure 43.1).

The Liver houses the Hun. The Liver's association with the environment is through the eyes. Through observation, the Qigong doctor's eyes can receive images that reveal the status or intention of the patient. These images are absorbed into the doctor's Shen via the Hun. There is an old Chinese saying, which goes, "When the Hun swim to the eyes, a person can see."

In the springtime, Liver Qi becomes more active in individuals with strong Liver Qi; whereas, it may become Deficient in those with weak Liver Qi. When Liver Qi is Deficient, the patient becomes fearful; when the Liver Qi is in Excess, the patient becomes consumed by anger. The excessive eating or drinking of sour foods, and overexposure to wind depletes the Liver.



Figure 43.1. The Liver (Lv) Channel

LIVER COMPLICATIONS AND SYMPTOMS

Liver diseases often manifest with the following symptoms which are common to the organ's energetic dysfunction: headaches, dizziness, tiredness, and mental and emotional problems. When Liver disorders occur, the patient may experience Qi movement below the left side of the navel (which feels hard upon pressure), pain and distention in the hypochondria, cramps, drowsiness, blurred vision, etc. A list of Liver syndromes and their symptoms are described as follows.

1. Stagnation of Liver Qi can cause such symptoms as: headaches, mental and emotional problems, hypochondriac pain, abdominal pain and masses, diarrhea, constipation, painful urination, dysmenorrhea, and premenstrual tension.
2. Stagnant Liver Qi Invading the Stomach can result in epigastric pain.
3. Stagnant Liver Qi Invading the Lungs can cause wheezing.
4. Liver Yang Rising can cause such complications as: headaches, dizziness, and tiredness.
5. Liver Fire Blazing can cause such symptoms as: severe headaches, dizziness, breathlessness, wheezing, coughing, mental and emotional problems, insomnia, tiredness, painful or scanty urination, and constipation.
6. Liver Wind can cause headaches, dizziness, seizures, tremors, muscle spasms and tiredness.
7. Liver Blood Deficiency can cause such symptoms as headaches, mental and emotional problems, tiredness, hypochondriac pain, constipation, and premenstrual tension.
8. Liver Yin Deficiency can cause such symptoms as wheezing, mental and emotional problems, insomnia, tiredness, and hypochondria pain.
9. Stagnation of Liver Blood can cause such symptoms as headaches, mental and emotional problems, hypochondriac pain, abdominal pain, and dysmenorrhea.
10. Damp Heat in the Liver and Gall Bladder can cause such symptoms as jaundice, headaches, mental and emotional problems, hypochondriac pain, and abdominal pain.

GENERAL TREATMENT FOR LIVER DISEASES

The following is a description of a general protocol used for treating common Liver diseases. The goal is to introduce the Qigong doctor to the basic hand positions and areas of the patient's body towards which Qi is emitted or Turbid Qi is removed. Once the Qigong doctor becomes proficient at locating these specific points, the treatment flows more smoothly.

The reader will notice that after comparing the various Liver and Gall Bladder therapies, certain patterns repeat themselves.

1. Generally, the Qigong doctor accesses the patient's Liver through either direct energetic insertion into the Liver's anatomical location, or through the patient's channels or external energetic fields.
2. After purging, tonifying, and regulating the patient, the Qigong doctor stimulates the back gates to the patient's Liver and the Yellow Court.
3. Next, the doctor roots the patient's Middle Burner Qi into the Lower Dantian.
4. Finally, the Qigong doctor leads any remaining Turbid Qi down the right Gall Bladder Channel and out of the patient's body (Figure 43.2).

Keep in mind that these areas are general, and that specific treatment patterns must change as they apply to the patient's exact condition (Excess, Deficient, etc.).

MEDICAL QIGONG THERAPY FOR LIVER QI DYSFUNCTION

The primary therapies used to treat Liver diseases include the Windy Breathing Method (see Chapter 16) to strengthen the Liver, Spleen, Lungs, and Kidneys, and Quiescent Qi Regulating meditations (see Chapter 14).

1. Patients with Deficiency of Qi and Cold syndromes of the Liver may feel cold and are li-


Purge Toxic Qi out the patient's Liver organ.
Root Rebellious Liver Qi into the Lower Dantian, then regulate.
Lead and purge the Toxic Qi out of the patient's GB-34 points
Lead and purge the Toxic Liver Qi out of the patient's right Gall Bladder Channel.

Figure 43.2. Basic Treatment for Liver Stagnation


Shu
Heart
Haa
Green
Liver
Spleen
Kidneys
Lungs

Figure 43.3. Purging the Child to Treat the Mother

able to feel frightened. To treat this condition, the patient can practice the meditation of Taking in the Green Qi to nourish the Liver and also Taking in the Blue Qi to nourish the Kidneys (Formula: nourishing the mother to replenish the child).

2. Patients with an Excess of Qi and Heat syndromes of the Liver may have dry eyes, pain in the hypochondria that may radiate down to the lower abdomen, and changing moods accompanied by flushed cheeks. To treat this condition, the patient can practice uttering "Xu" (pronounced Shu) for the Liver, and "Ha" for the Heart (Figure 43.3. Formula: purging the child to treat the mother).

   Note: In treating Liver diseases, exhaling the sound "Shu" purges and sedates, while inhaling "Shu" replenishes and tonifies (see Chapter 40).

3. Stagnation of Liver Qi and Liver Fire Rising (anger or rage impairing the Liver) may cause an abnormal dispersing and impair the Liver's function. The patient may experience headaches, deafness, and swelling cheeks. To stabilize the hyperactive Liver Yang (and guide the flaring up Liver Fire to descend), the Qigong doctor guides the patient's Qi back to its origin with external energy projection. If treatment of Liver stagnation is not undertaken, there may be an organic change in the

Liver, resulting in hardening of the Liver or Liver cancer.

4. Patients with Rebellious Liver Qi resulting in hypochondriac pain and stiffness with spasms, should be treated by guiding their Qi back to the origin of the Liver with external Wei Qi therapy.

LIVER QIGONG PRESCRIPTIONS

The following system of exercises can be used to regulate the Qi and Blood of the Liver Channels, soothe and regulate Qi circulation, and suppress hyperactive Yang. These exercises can also be used to prevent and treat diseases and syndromes such as hypertension, psychoneurosis, chronic hepatitis, and hepatosplenomegaly (the enlargement of both Liver and Spleen), as well as bitter taste in the mouth, dry throat, dizziness, vertigo, and fullness in the chest and hypochondrium.

COLOR VISUALIZATION AND ORGAN CORRESPONDENCE

In China, the clinical use of color therapy is prescribed according to the Five Color Correspondence Theory. Each of the five major colors are assigned to specific organs and their channels (see Chapter 4). If an organ is diseased, it will generally appear in various shades from gray to black. To heal the disease, the patient imagines taking in the organ's clean color, while dispersing the turbid pathogenic color. This visual meditation helps to return the organ's Qi back to its origin, in order to achieve balance and health.

PRESCRIPTIONS FOR TONIFYING THE LIVER

Taking in the Green Qi can be used to tonify the Liver. The properties inherent within the color green have a persistent vibratory rate also used for tonifying the Liver and Gall Bladder.

1. Assume a standing, sitting, or lying posture. Relax the whole body, breathe naturally, and get rid of any stray thoughts. Place the tongue against the soft palate on the roof of the mouth.
2. Visualize green energy in front of you. Draw from a visual/emotional association with green trees, grass, bushes, etc. from your imagination, or if possible, actually look at a green object. Inhale the green light energy in through the nose and down into the Liver organ. As you exhale through the mouth, the dark, pathogenic Qi leaves the Liver; however, the bright, clean color remains in the organ, stimulating and vitalizing it. With each breath the organ retains more clean energy and begins to glow. Repeat for five breaths.

   Next breathe the color green in through the nose, filling the entire mouth. When exhaling, send the Qi slowly to both costal portions at the sides of the Lungs, and then down to the Lower Dantian. Practice eight to sixteen times.

PRESCRIPTIONS FOR PURGING THE LIVER

Purge the Liver by having the patient rub his or her chest while sounding "Shu." Have the patient assume a sitting or standing posture, and place both palms flatly on both sides of the chest and inhale slowly. When exhaling, the patient should sound the word "Shu," while gently rubbing both costal regions in a clockwise circular motion with both palms. Practice for ten to twenty breaths.

PRESCRIPTIONS FOR SOOTHING THE LIVER AND CONDUCTING QI

The following exercise is used to regulate and soothe the Liver Qi; it is used after the purging or tonifying exercises.

1. Stand relaxed with both arms naturally hanging down, palms facing downward, with the five fingers of each hand slightly held up. Press down with slight force and imagine Qi reaching the palms and extending to the fingertips. Press the palms down three times (Figure 43.4).
2. Lift both hands up in front of the chest, with each palm facing forward. Focus the mind on both palms. Push the palms forward three times, first drawing them closer to the body and then pressing them further away from the chest (Figure 43.5).
3. Stretch both hands horizontally out to the sides of the body (as if imitating a bird that is stretching out its wings) with all the fingers pointing upward, and the palms pushing to



Figure 43.4. Press the palms downward three times.



Figure 43.5. Press the palms forward three times.



Figure 43.6. Press the palms to the sides of the body three times.



Figure 43.7. Direct the Qi to flow downward from the Middle to the Lower Dantian three times.

the sides. Focus your attention on extending the Qi out the palms to the fingertips. Press the palms out to the sides three times (Figure 43.6).

4. Draw both palms back to the front of the chest, palms facing upwards, elbows down. Rotate the palms to face downwards, and circle them down to the pubic arch, while focusing the mind on both palms (Figure 43.7). When Qi flows to the Lower Dantian turn the palms to face upward as if embracing a ball at the Lower Dantian.

Perform this exercise three times, then place both hands against the sides of the body. This completes one set. Do three sets.

MEDICAL QIGONG THERAPY FOR SPECIFIC LIVER DISEASES

The following are several Medical Qigong treatments used in China to treat specific Liver diseases.

DISORDERS OF THE BILIARY TRACT

The biliary tract includes the organs and ducts that participate in the secretion, storage, and delivery of bile into the duodenum.

ETIOLOGY

Disorders of the biliary track mainly include cholecystitis (inflammation of the Gall Bladder), cholelithiasis (formation of calcium or bile stones in the Gall Bladder), and ascariasis of the biliary tract (infestation by ascaris lumbricoides parasites). Traditional Chinese Medicine teaches that the first two diseases belong to the category of hypochondriac pain or jaundice, while the last condition is called biliary ascariasis.

Disorders of the biliary track can be caused by mental depression, stagnation of Gall Bladder Qi, the excessive intake of fatty foods, exopathogenic invasion, failure of biliary drainage system resulting from stagnation of Dampness and Heat, or obstruction by ascarid parasites. Although the causes and symptoms of these disorders are different, the Medical Qigong treatments and prescriptions are the same.

SYMPTOMS

The onset of biliary tract disorders are usually acute, and the pain is felt on the right upper abdomen and the right hypochondrium area of the thorax. Other symptoms include nausea, vomiting, rigor, high fever, yellow-colored skin pigmentation (jaundice), yellow sclera of the eyes, and whitish-grey stool.

Patients with biliary ascariasis may experience severe colic or a tearing pain below the xiphoid process. The pain is sometimes so severe that the patient experiences extreme perspiration accompanied by nausea and vomiting. If the ascarid parasites withdraw from the biliary tract, the pain is immediately relieved, but can return intermittently. If the ascarid parasites move completely into the Gall Bladder, the pain will be continuous, causing Gall Bladder distention. Symptoms such as jaundice, rigor, and high fever may appear, and a tenderness on the upper right quadrant of the xiphoid process can be felt with deep pressure.

TREATMENT

Cholelithiasis (gall stones) and cholecystitis (inflammation) are often treated by guiding the Toxic Qi downward and out of the patient's lower extremities along the Liver and Gall Bladder Channels, and by balancing the Qi activities between the upper and lower quadrants of the patient's body, as well as the right and left sides.

1. To begin treating disorders of the biliary tract, place the patient in a sitting position on the table. Stimulate the Bl-18, -19, -20, -21 points beside the patient's lower thoracic vertebrae, paying particular attention to the right side of the patient's body.
2. Next, extend Qi into the Gall Bladder area for 24 breaths (on the front of the patient's body), stimulating this area with the Tiger Kneading Palm technique, using Pushing, Pulling, and Shaking Qi manipulations.
3. To regulate the patient's Qi, and relieve epigastric distension, the doctor purges the patient's Toxic Qi, guiding it to flow out of the body downwards along the patient's Gall Bladder and Stomach Channels and out of the feet.
4. Using the Vibrating Palm technique, stimulate the patient's Bl-18, -19, -20, -21 points on the right side of the body once more, this time for 28 breaths. Then use the same Vibrating Palm technique on the front side of the body while directing the energy towards the Gall Bladder for 28 breaths.
5. Finally extend energy into the patient's Bl-19 point on the right side of the body for 12 breaths, and using the Sword Fingers technique, lead the Qi down the right Bladder Channel to the foot and out the small toe three times.

TREATMENT MODIFICATIONS

When treating the condition of ascariasis of the biliary tract, also include rubbing the abdomen 18 times in a counterclockwise direction.

PRESCRIPTIONS AND HOMEWORK

In prescribing homework, place the patient in a standing Wuji posture, with both palms placed against the hypochondria. Have the patient slowly massage the Gall Bladder area while purging the organ with the sound "Shu" for 24 exhalations.

Next, have the patient sit or lie down in a comfortable setting. As the patient inhales, he or she should meditate on the word peace; as the patient exhales, he or she should focus on relaxation. The patient should focus on releasing all tension in the head, chest, Liver, Gall Bladder, back, abdomen, and waist, for 36 breaths.

GALLSTONES

A gallstone is a Gall Bladder stone formed as a result of an excess of cholesterol in relation to the bile acids. The formation of calculi which results from this skewed relationship of cholesterol and bile is believed in Traditional Chinese Medicine to be dependent on the Liver Qi.

ETIOLOGY

Stagnant Liver Qi is believed to be a prerequisite for the formation of gallstones. If the Liver Qi stagnates, the bile will not secrete properly, leading to an accumulation of Damp Heat in the Gall Bladder. The steaming action of Heat on Dampness over prolonged periods of time, leads to the formation of gallstones.

It is generally believed that gallstones are related to cholestasis, an infection of the biliary tract, and metabolic disturbances of cholesterol. Gallstones form when the bile contains more cholesterol than it can keep in solution. The cholesterol precipitates out to form gallstones. The incidence of gallstones in women is approximately twice that in men. Any factor which increases the patient's cholesterol or decreases bile acids may lead to the formation of gallstones (i.e., obesity, high fat diet, Liver disease, and bile stasis increase the risk of developing gallstones). There are three types of gallstones: Cholesterol Stones, Mixed Stones, and Pigment Stones.

1. Cholesterol stones are usually single stones, which are composed almost entirely of cholesterol, and correspond to the pattern of Damp Heat in the Liver and Gall Bladder.
2. Mixed stones are the most common type of stones, consisting of lamellated layers of cholesterol, bilirubin, and calcium.
3. Pigment stones are less common and are always numerous. They are composed of bile pigment.

Gallstones are clinically manifested as pain in the right upper abdominal quadrant and right costal region, and are classified in Traditional Chinese Medicine as being placed in the categories of either hypochrondriac pain or jaundice.

SYMPTOMS

- Liver Qi stagnation is manifested by pain and distention in the right upper abdominal quadrant and right hypochondriac region. The pain can range from mild to severe. The patient may experience a distention and fullness in the Stomach with no obvious fever or jaundice.
- Damp Heat in the Liver and Gall Bladder is manifested by persistent pain in the right upper abdominal quadrant and right hypochondriac region. The pain manifests proximally or radiates up to the right shoulder. The patient experiences abdominal distention, fever, and jaundice.

TREATMENT

Have the patient sit on the edge of the table. Begin stimulating the patient's middle-back area, focusing on the Bl-21, Bl-20, BL-19, and Bl-18 points, on the right side of the back and drain the Toxic Qi down the torso and out the GB-34 point below the knee.

Use the Vibrating Palm hand technique and emit Qi into the patient's mid-back area for 14 breaths at each point. Then emit Qi into the painful area of the front side of the patient's body for 28 breaths.

Next, applying the Extended Fan Palm hand technique, emit Qi into the patient's Gall Bladder for 24 breaths using the Pulling and Leading manipulation skills to draw the Qi down through the Gall Bladder and Stomach Channels and out the patient's feet.

TREATMENT MODIFICATIONS

When treating a patient with a Liver Qi stagnation, use the Pulling and Leading manipulations to draw Qi down the lower limbs of the patient's body.

When treating patients with Damp Heat in the Liver and Gall Bladder: use the Extended Fan Palm hand technique and emit Qi into the patient's CV-12 and St-21 points, leading the Qi down the right Stomach Channel to the feet.

PRESCRIPTIONS AND HOMEWORK

Have the patient practice Liver Massage described in Chapter 39, while exhaling the sound "Shu" for 36 breaths.

PRESCRIPTION MODIFICATIONS

- For patients with Liver Qi stagnation, have the patient practice rubbing the hypochondrium while imagining the Toxic Qi descending down and out the body. Instruct the patient to practice the Descending the Yang and Ascending the Yin Technique (see Chapter 41).
- For patients with Damp Heat in the Liver and Gall Bladder, have the patient practice rubbing the hypochondrium while imagining the Toxic Qi descending down and out the body as he or she sounds the "Hu" sound to purge and regulate the Spleen.

CIRRHOSIS

Cirrhosis is a generalized disease marked by hepatic lesions. It is a chronic disease of the Liver characterized by the formation of dense lobular connective tissue, degenerative changes in the parenchymal cells, structural alterations in the Liver lobules, and sometimes fatty and cellular infiltration within the Liver.

ETIOLOGY

Cirrhosis refers to a series of pathological changes of degeneration, necrosis and regeneration of Liver cells, as well as the proliferation of fibrous tissue due to prolonged or recurrent damage of the Liver caused by various pathogenic factors. Cirrhosis is clinically manifested as a series of symptoms caused by a hypofunction of the Liver and portal hypertension.

SYNDROMES

1. Liver Qi stagnation and Spleen Deficiency results in lassitude, weakness, fullness in the chest and abdomen, hypochrondriac distension and pain, occasional nausea, belching, and vomiting.
2. Qi and Blood stagnation results in poor appetite, hypochrondriac distention and pain, and enlargement of the Spleen and Liver marked by spider nevus and Liver spots.
3. Water retention results in hardness and fullness of the abdomen with a severe fullness in the Stomach, distention of the abdomen or intestines (by gas), nausea, vomiting, and anorexia. Patients with an insufficiency of Spleen and Kidney Yang suffer from symptoms of cold limbs, pale complexion, and an aversion to cold. Patients with a Deficiency of Liver and Kidney Yin experience sporadic fever, irritability, and a dark complexion.

TREATMENT

Place the patient on the edge of the table and stimulate the Bl-18 and BL-20 points on the mid-back, as well as the Lv-13 and Lv-14 points (at the sides of the body), and the CV-12 point (at the center of the body). Use a Vibrating Palm hand technique to emit Qi into these points for a period of 14 to 18 breaths.

Use the Extended Fan Palm technique and emit Qi into the patient's mid-back at the Bl-18 points, as well as the sides of the torso at the Lv-13 and Lv-14 points. Purge and drain the Toxic Qi down and out the patient's body along the Gall Bladder and Liver Channels.

TREATMENT MODIFICATIONS:

When treating patients with Liver Qi stagnation and Spleen Deficiency, use the Vibrating Palm to emit Qi into the Bl-20 and CV-12 points.

When treating patients with Qi and Blood stagnation, use the Extended Fan Palm technique to emit Qi into the Lv-13 and Lv-14 points, conducting the Qi along the Gall Bladder Channel down the leg to GB-34, and out the body.

When treating patients with water retention, use the Extended Fan Palm technique to emit Qi into the Sp-21 points. Lead the Qi down the Spleen Channels into the lower limbs. For patients with a Spleen and Kidney Yang Defeciency or a Liver and Kidney Yin Deficiency, use a Vibrating Palm technique to emit Qi into the Lower Dantian and Mingmen areas.

PRESCRIPTIONS AND HOMEWORK

Have the patients practice self-regulation exercises to tonify the entire body's energetic system.

PRESCRIPTION MODIFICATIONS

1. For patients with Liver Qi stagnation and Spleen Deficiency, have the patients practice the Old Man Searching for the Reflection of the Moon at the Bottom of the Tide Pool (see Chapter 40).
2. For patients with Qi and Blood stagnation, have the patient perform the Liver Massage while exhaling the sound "Xu."
3. For patients with water retention, have them practice rubbing the Yellow Court area (CV-12) and sounding the word "Hu" to dredge the Spleen and Stomach. For patients with a Spleen and Kidney Yang Deficient, have them practice Gathering the Sun's Essence (see Chapter 11), and for patients with a Kidney and Liver Yin Deficient, have them practice Gathering the Moon Cream. (see Chapter 11).

CHOLECYSTITIS

In Traditional Chinese Medicine, both sides of the hypochondrium are related to the Liver Channels. In Western medicine, however, only the right side reflects a possible Liver pathology. Thus, it is important to have a distinction between left and right hypochondriac pain. Cholecystitis consists of the inflammation of the Gall Bladder with or without gallstones. It is related to hypochondriac pain on the right side of the body. It is created when cholesterol is maintained in the bile solution within the bile acids. Hypochondriac pain on the left side of the body extending to the epigastrium and left scapula is often related to acute pancreatitis.

ETIOLOGY

Cholecystitis is mostly caused by a bacterial infection or an obstruction of the bile duct. Clinically it is characterized by pain in the upper right quadrant of the abdomen and dyspepsia, and may be accompanied by nausea, vomiting, and sweating.

SYNDROMES

- Damp Heat manifestations are alternating attacks of chills and fever. Sometimes there is fever without chills, nausea, vomiting, loss of appetite, and pain in the right hypochondrium region.
- Qi stagnation manifestations are distending or moving pain in the right hypochondrium, belching, acid regurgitation, nausea, and anorexia.

TREATMENTS

1. Have the patient sit at the edge of the table. Stimulate the patient's mid-back, emitting Qi into the Bl-18, Bl-19, and Bl-20 points as well as the GB-34 point below the right knee.
2. Using the Vibrating Palm, first emit Qi into the patient's mid-back for 14 breaths, then directly into the painful area on the front side of the patient's body for 28 breaths.
3. Using the Extended Fan Palm hand technique, emit Qi into the patient's Gall Bladder region for 24 breaths, then purge the Toxic Qi down their right Gall Bladder Channel to the base of the foot and out of the body.

TREATMENT MODIFICATIONS

- For patients with Damp Heat, use the Extended Fan Palm hand technique to emit Qi into the patient's CV-12 area, then purge the Toxic Qi down the Stomach Channels to the base of the feet and out the body.
- For patients with Qi stagnation, use mostly purging and dredging Qi manipulations, focusing on the patient's lower torso.

PRESCRIPTIONS AND HOMEWORK

It is advisable to have the patient perform the Six Healing Sound Regulation exercise (see Chapter 40).

PRESCRIPTION MODIFICATIONS

- For patients with Damp Heat, it is advisable to have them perform the Spleen Massage (see Chapter 39) while exhaling the sound "Hu" to purge the Spleen and Stomach, allowing the Toxic Qi to flow down the Spleen and Stomach Channels into the ground.
- For patients with Qi stagnation, it is advisable to have them perform the Liver Massage (see Chapter 39) while exhaling the sound "Shu."

HYPOCHONDRIAC PAIN

Hypochondriac pain is a syndrome characterized by pain in one or both sides of the hypochondrium. The hypochondrium is located on the part of the abdomen beneath the lower ribs on each side of the epigastrium.

Chronic hepatitis, hepatolithiasis, cholelithiasis, cholecystitis and other diseases related to the Liver and Gall Bladder can be differentiated and treated in accordance with the exercises described in the prescription section.

ETIOLOGY

Hypochondriac pain may be caused by different factors such as trauma, the accumulation or blockage of Qi, stagnation of Phlegm and the Deficiency or Excess of Liver Qi (commonly seen in patients with Excess Liver Fire or Liver Qi stagnation). The symptoms of hypochondriac pain may occur in one or both sides.

SYNDROMES

- An Excess syndrome occurs when a patient suffers from Excess Liver Fire. This condition manifests with symptoms such as severe pain in the hypochondrium area with difficulty in breathing. The pain may radiate from both sides of the body, or from one side only.
- A Deficient syndrome occurs when a patient suffers from a Liver Yin and Kidney Yin Deficiency (often caused by mental depression or hemorrhage). This condition is observed clinically with symptoms such as a dull or sharp pain in the hypochondrium areas.

TREATMENT

1. Begin by stimulating the patient's Middle Dantian and Lv-14 and Lv-13 points at the front of the chest in the hypochondrium area (on both sides or the right side only). Next, stimulate the patient's mid-back around the Bl-17 and Bl-18 points and the base of the outside of the knees around the GB-34 areas.
2. Using the Extended Fan Palm hand technique, emit Qi into the patient's Lv-13 and Lv-14 points and the painful region of the chest and hypochondrium and begin purging the Toxic Qi, dredging it down the body and out of the extremities through the patient's Liver and Gall Bladder Channels.

TREATMENT MODIFICATIONS

- For patients with an Excess syndrome, extend energy into the patient's mid-back at the Bl-18 points. Then grasp and softly rock this tissue area to free the trapped Qi.
- For patients with a Liver and Kidney Yin Deficiency, emit Qi into the patient's Lower Dantian and Mingmen area using the Extended Fan Palm technique for 12 to 24 breaths.

PRESCRIPTIONS AND HOMEWORK

1. Have the patient perform the Liver Massage (see Chapter 39) and sound the healing tone "Shu" for 36 breaths.
2. If the pain is on the left side of the patient's chest, have the patient place his or her palms on the painful area and begin to purge the Toxic Qi from the midline of the thorax, down the left side of the body, following the Gall Bladder Channel to the ground, for nine breaths.
3. Finally, have the patient stand in a Wuji posture and focus the mind's intention on his or her palms. The patient then raises the arms sideways, like a bird stretching its wings (creating a "T" formation). Next, both arms embrace (as if holding an imaginary ball) at the Middle Dantian level. The patient imagines the Qi from the middle chest flowing downward and rooting into the Lower Dantian.

CHAPTER 44
QI EMISSION THERAPY FOR HEART DISEASES

INTRODUCTION

The Heart is a solid (Zang) organ and controls Blood circulation. The Heart corresponds to the element Fire and is sometimes referred to as the Red Emperor. The Heart houses the Shen and is in charge of mental activities and long term memory. It is energetically paired with the Small Intestine (a hollow organ), which is in charge of separating the pure, clean energy from the impure Qi (Figure 44.1).

The Heart's upper external connection with the outside is through the tongue, hence sensations of the tongue (from food, kissing and so on), as well as talking can travel directly into the spirit, mind, and emotion, affecting the Heart's desires and senses.

In the early summer months, the Heart energy becomes more active in individuals who already have strong Heart Qi, but can become Deficient in those who already have weak Heart Qi. Excessive eating and drinking of bitter foods, and overexposure to heat depletes the Heart.



Figure 44.1. The Heart (Ht) Channels

HEART COMPLICATIONS AND SYMPTOMS

The Heart is responsible for governing the flow of Blood through the body's arteries and veins. Coronary artery disease (CAD) is a disease in which the patient's coronary arteries begin to harden, or impede adequate vascular flow to the myocardium, resulting in an insufficient supply of Qi and Blood throughout the body. This causes such diseases as hypertension, vasculitis, myocarditis, congenital Heart disease, rheumatic Heart disease, nervous malfunctioning of the Heart, organic pathological changes of the Heart, and arteriosclerosis of the brain.

In general, patients with Heart disease may have an arterial pulse above the navel which often disappears upon pressing, as well as a hot sensation in the soles of the feet and palms, dry mouth, stiffness of the tongue, and absentmindedness. A list of Heart syndromes and their symptoms are described as follows.

1. Heart Qi Deficiency can cause such symptoms as: physical tiredness, palpitations, sweating, pallor, and shortness of breath when exerting oneself.
2. Heart Yang Deficiency can cause such symptoms as: tiredness, tightening in the chest, and edema.
3. Heart Blood Deficiency can cause such symptoms as: headaches, mental and emotional problems, tinnitus, and tiredness.

4. Heart Blood stagnation can cause such symptoms as: mental and emotional problems, as well as tightness or pain in the chest.
5. Heart Yin Deficiency can cause such symptoms as: tiredness, insomnia, and mental and emotional problems.
6. Heart Fire can cause such symptoms as: insomnia, painful urination, and mental and emotional problems.

GENERAL TREATMENT FOR HEART DISEASES

The following is a description of a general protocol used for treating a patient's Heart. The goal is to introduce the Qigong doctor to the basic hand positions and areas of the patient's body towards which Qi is emitted (or Turbid Qi is removed). Once the Qigong doctor becomes proficient at locating these specific points, the treatment will flow more smoothly.

After comparing the various Heart therapies, the reader will notice that certain patterns repeat themselves.

1. Generally, the Qigong doctor can access the patient's Heart through four methods:
   - direct energetic insertion into the Heart's anatomical location,
   - the patient's channels,
   - the external energetic Wei Qi fields, or
   - the patient's Taiji Pole (Figure 44.2).

   To avoid energetic armoring (while accessing the Qi in the front of the Heart), it is important for the doctor to already be connected to the patient's Shendao point (through the back of the Heart).
2. After treating the patient (purging, tonifying, and regulating), the Qigong doctor stimulates the patient's Heart and Shendao area, and roots the Upper Dantian Qi into the Lower Dantian.
3. Next, the Qigong doctor leads any remaining Turbid Qi down the Pericardium and Heart Channels and out from the patient's hands (Figure 44.3).

Keep in mind that these areas are general and


Stimulate and Root the Heart through the Taiji Pole.
Access the patient's Heart through the Shendao (GV-11) point.
Root the Heart in the Lower Dantian

Figure 44.2. Treating Heart Conditions


Lead Toxic Heat down the Pericardium and Heart Channels.

Figure 44.3. Lead the Toxic Qi out of the body through the patient's Pericardium Channels.

that specific treatment patterns must change as they apply to the patient's exact condition (Excess, Deficient, etc.).

MEDICAL QIGONG THERAPY FOR HEART QI DYSFUNCTION

The primary therapies used to treat cardiovascular diseases include: the Windy Breathing method to strengthen the Heart and Kidneys, Toe-Raised Walking, Heart Massage, and Quiescent meditation (see Chapter 15).

- Patients with an Excessive Qi syndrome of the Heart with extreme Heat may have a flushed complexion, full pulse, and excess sputum; they may feel pain in the chest, hypochondrium, back, shoulders, and arms. This syndrome can be treated by having the patient utter the "Ha" sound while guiding the Kidney Water Qi upwards to suppress the Heart Fire (Figure 44.4). Alternatively, the Qigong doctor may guide the Evil Qi out of the patient's body along the Heart and Small Intestine Channels with Pulling and Leading Qi manipulations.
- Patients with Deficient Heart Qi may dream of flames and red colored objects and have a radiating pain in the abdomen. This condition can be treated by having the patient perform the Taking in Yellow Qi meditation (see Chapter 4) which replenishes the child (Spleen), and Taking in Pink Qi meditation to nourish the mother (Heart); or, by using the Pushing and Guiding Qi manipulations to reinforce the Heart Qi and the Qi in the Lower Dantian.

In this particular case (Deficient Qi syndrome of the Heart), the reason the patient should not take in the energetic color red is because the Heart has already established a draining pattern, and any energy pouring into the Heart will only continue to drain away.

HEART QIGONG PRESCRIPTIONS

To tonify the Heart, tranquilize the mind, promote Blood circulation, and remove obstructions in the channels, prescription exercises can be used. The following exercises can be used to prevent and treat diseases and syndromes such as coronary Heart disease, hypertension, angina, arrhythmia, rheumatic Heart disease, cardiac neurosis as well as palpitations (ranging from mild to severe), pericardial pain, and insomnia.



Figure 44.4. Treating Patients with an Excess Qi Syndrome of the Heart

PRESCRIPTIONS FOR TONIFYING THE HEART

Taking in the Red Qi can be used to tonify the Heart. The properties inherent within the color red have a persistent vibratory rate used for tonifying the Heart and Small Intestine.

1. Assume a standing, sitting, or lying posture. Relax the whole body, breathe naturally, and get rid of any stray thoughts.
2. As you inhale, visualize red energy in front of you. Inhale the red light energy in through the nose and down into the Heart organ. As you exhale through the mouth, the dark, pathogenic Qi leaves the Heart; however, the bright, clean color remains in the organ, stimulating and vitalizing it. With each breath the organ retains more clean energy and begins to glow. Repeat for five breaths.
3. Next breathe the red energy in through the nose and fill the entire mouth with it. When exhaling through the nose, send the Qi slowly to the Heart, then to the Lower Dantian, to connect the energy of the Heart and Kidneys and to remove obstructions in the whole body. Perform this exercise seven or fourteen times. Return to the first step and close the training.



Figure 44.5. Hands rest in front of the Lower Dantian.



Figure 44.6. Both palms simultaneously press forward.

PRESCRIPTIONS FOR PURGING THE HEART

Purge the Heart by having the patient rub his or her chest while sounding "Ha."

1. The preparatory postures are the same as above.
2. Begin by clicking the teeth, stirring the tongue, and swallowing the saliva, then place the palms on the pectoral region of the left side of the chest (left hand on the outside for men, opposite for women). Inhale slowly, then gradually exhale the sound "Ha," focusing the mind on the Heart area. Repeat for six to twelve breaths altogether while rubbing with the palm lightly in a clockwise circle.

PRESCRIPTIONS FOR REGULATING THE HEART AND CONDUCTING QI

The following exercise is used to regulate the Heart after purging or tonifying.

1. Assume a standing or sitting posture. Relax the whole body, breathe naturally, and raise the tongue against the hard palate, just behind the teeth. Bring both palms loosely together (left over right for men, opposite for women) at the Lower Dantian; stand still for several minutes and concentrate the mind on the Lower Dantian (Figure 44.5).
2. Turn both palms outward, and push the arms along the sides of the body towards the back. Hold this posture for several minutes.
3. Turn both palms upward and lift them to the sides of the chest.
4. With both palms facing forward, stretch both hands level and forward. Focus your attention on the ends of the middle finger of each hand, while the thumb and little fingers stretch and separate (Figure 44.6).
5. Clench both hands into fists and pull them along the sides of the body towards the back, as if dragging heavy weights. Perform this movement three times (Figure 44.7).
6. Raise the right palm, as if holding a heavy weight in front of the chest, and push the palm out vertically to the right. Then, draw the right hand back to the side of the body near the hip. Repeat on the left side, and finally return to the starting posture. Perform these movements three times (Figure 44.8). This completes one set. Perform three sets.

SPECIFIC MEDICAL QIGONG THERAPY FOR HEART DISEASES

The following are several Medical Qigong Treatments used in China to treat specific Heart diseases.

HYPERTENSION

Hypertension is considered a condition in which the patient has higher blood pressure then what is determined to be normal for his or her



Figure 44.7. Both hands simultaneously clench into fists and pull to the hips.



Figure 44.8. Alternate each palm as it presses towards the side of the body.

chronological age and physique. Generally, Traditional Chinese Medicine places it in the categories of vertigo and headache.

ETIOLOGY

Hypertension is one of the most common problems impacting the Heart. It is the result of an imbalance of the Yin and Yang functional aspects of Deficient Kidney Yin and Excess Liver Yang, and/or an overabundance of Phlegm and Dampness within the body.

Hypertension can be caused by the patient eating too much food or salt, by too much stress, or not enough exercise. A renin imbalance within the patient's Kidneys, increased cholesterol, a preexisting genetic predisposition, a secondary illness (diabetes, nephritis, or hyperthyroidism), or even pregnancy can also lead to hypertension. These causes of hypertension can result in one of three internal factors: high cardiac output due to stress, reduced elasticity of the vessels, and resistance to Blood flow.

1. When the body experiences emotional tension it releases adrenaline, which speeds up the Heart rate and causes the blood vessels to narrow, increasing the body's blood pressure.
2. A buildup of plaque and normal aging reduces the vessel's elasticity and can lead to hypertension.
3. Old age, certain hormonal imbalances or disorders, or a genetic predisposition can likewise cause high blood pressure.

The overall goals in treating hypertension patients are to:

1. Lower blood pressure,
2. Stabilize blood pressure,
3. Establish a quiescent state of mind (generally, meditating 20 minutes, twice a day provides the patient with a prolonged state of deep relaxation needed to combat stress), and
4. Encourage life-style changes (i.e., monitor potassium intake, decrease sodium intake, weight control, and stress reduction management). Treatment programs are established as described below.

SYNDROMES

As previously stated, there are three underlying causes or syndromes relating to hypertension: Excess Liver Yang, Deficient Yin, Excess Liver Fire, and Kidney Yin and Yang Deficiency.

1. If the body's Kidney Yin is Deficient, it fails to nourish the Liver Yin, which leads to a condition of hyperactivity of Liver Yang. The clinical manifestations are feelings of fullness in the head, daydreaming, headaches, dizziness, tinnitus, insomnia, and dysphoria with feverish sensations in the chest.
2. Excess Liver Fire can cause headaches, dizziness, restlessness, irritability, flushed face, and constipation.
3. If the body's Kidney Yang is Deficient the Yin (Water) accumulates, if the Yang does not move, the blood vessels cannot relax. This results in

obstructed Blood flow. The clinical manifestations are dizziness and tinnitus, daydreaming, palpitations, amnesia, lassitude and weakness in the legs, as well as insomnia.

TREATMENT FOR PATIENTS SENSITIVE TO ENERGY

1. Use Medical Qigong therapy, and have the patient sit in a chair with his or her feet flat on the ground. Begin the treatment by cleaning the patient's Conception and Governing Vessels, using purgation methods. Focus specific attention on clearing the patient's head area (Figure 44.9). Literally sweep with the entire hand, and comb the patient's Wei Qi fields with the fingers.

   By scanning the occipital region of the patient, you can verify that the Excess Qi in the patient's upper extremities has abated. Once these vessels are clean, you can focus on treating the hypertension.
2. Stand behind the patient, using the Extended Fan Palm technique (with both hands) extend energy from the left hand into the top of the patient's head at the Baihui GV-20 area, while your right hand extends energy into the back of the patient's head, beginning at Yuzhen Bl-9. The two streams of Qi flow downward to the Dazhui GV-14 area, where they join into one river, which continues to flow downward through the patient's Taiji Pole. Continue to visualize these two streams joining and filling the Lower Dantian, for a period of 6 to 12 breaths (Figure 44.10).
3. Next, move your left hand and extend energy into the patient's Yellow Court, while your right hand is placed above the patient's Mingmen area. Lead the Qi from the Yellow Court into the patient's Lower Dantian, continuing to root the Qi, for a period of 6 to 12 breaths.

TREATMENT MODIFICATIONS

These modifications are additional formulas which are added onto the previous treatment according to the specific cause and condition of the patient's Heart.

1. When treating patients with Excess Liver Yang and Deficient Yin, use the Extended Fan Palm



Figure 44.9. The Qigong doctor begins by dredging, purging and cleaning the patient's Conception and Governing Vessels.



Figure 44.10. The Qigong doctor emits Qi into the patient's Baihui, Yuzhen and Dazhui points, in order to access the Taiji Pole and fill the patient's Lower Dantian.

hand technique and emit Qi into the patient's mid-back, drawing the energy down and rooting it in the patient's Lower Dantian and Mingmen.

2. When treating patients with Excess Liver Fire, it is important to treat the Lv-13 and -14 points, by dredging and purging the Excess Qi, and leading it down the patient's right Gall Bladder Channel, through the foot and into the Earth.
3. When treating patients with Kidney Yin and Yang Deficiency, use the Extended Fan Palm technique to emit Qi into the patient's mid-back, drawing the energy down and rooting it in the patient's Lower Dantian and Mingmen.

TREATMENT FOR PATIENTS NOT SENSITIVE TO ENERGY

Use Jing Point therapy in conjunction with Medical Qigong therapy (see Chapter 36). Have the patient lie prone. Using the Sword Finger technique, touch the patient's head with the left hand and extend energy into the Baihui GV-20 point. Guide this Qi down to the Lower Dantian through the Taiji Pole, while your right hand embraces and energizes the patients' Mingmen GV-4 point, thereby filling the Lower Dantian and rooting the patient's Heart Qi (Figure 44.11). Next, treat the patient's LI-11, St-36, Lv-2, and Sp-6 points on both sides of the body to lower the patient's blood pressure.

PRESCRIPTIONS AND HOMEWORK

1. A static posture can be given to convalescing patients as part of a meditative homework prescription for treatment of high blood pressure. The prescription is as follows.
    a. Have the patients lie supine (the patients may use a pillow under the head for comfort) and have him or her imagine that they are floating in warm water.
    b. The patients should perform the toning sound "Zheng" (prenounced Jang), and imagine dispersing Qi out of his or her body. The patient should use natural breathing while toning and dispersing the Toxic Qi. There are ten major areas, from the top of the head to the bottom of the feet, from which the patients must discharge the toxins. These areas include: the top of the head, Upper Dantian, throat, Middle Dantian, Yellow Court, Lower Dantian, the center of the thighs, knees, ankles, and bottom of the feet (Figure 44.12).
    c. After several minutes the patients will relax and focus their attention on the Lower Dantian or Bubbling Well points at the bottom of the feet.
2. Another meditation prescription given to patients with hypertension is to have them sit and imagine the feeling of warm water pouring down over the head, torso, extremities, and feet. This meditation should be practiced several times a day, using 36 breaths each time.
3. The patient can also be given the prescription of rubbing the hypochondrium and toning the sound "Shu" to purge Excess Heat from the Liver.



Figure 44.11. If the patient is not sensitive to energy, have them lie prone, and apply Jing Point Therapy in conjunction with Qi emission.



Figure 44.12. In this Static posture used to treat high blood pressure the patient lies supine and performs the toning sound "Zheng" (Jang), for dispersing Qi.

PALPITATION

A palpitation is an abnormally rapid throbbing or fluttering of the Heart. The symptom is characterized by nervous feelings or restlessness due to strong anxitey or fright. Clinically, it mostly attacks paroxysmally and is caused by emotional stress or overexertion. Symptoms such as insomnia, vertigo, tinnitus, etc. often accompany palpitations.

Diseases with palpitation as the main manifestation include arrhythmia, iron-deficiency anemia, aplastic anemia, hyperthyroidism and anxiety disorders. These diseases may all be differentiated and treated in reference to the prescriptions described in this section.

ETIOLOGY

There are several factors which contribute to palpitations. These factors and their symptoms are described as follows.

1. In patients suffering from Deficient Qi and Blood, and Deficient Heart Qi, palpitations may occur following sudden mental irritation. The patient may note unduly rapid heartbeat accompanied, in cases of Deficient Heart Qi, by pallor, restless sleep at night, dizziness and vertigo. This condition may also be caused by Deficient Heart Blood that fails to nourish the Heart.
2. Phlegm Fire disturbing the Heart may also give rise to palpitations. In cases with internal disturbances of Phlegm Fire, symptoms also include fidgeting and disorientation.
3. Another factor causing palpitations is a Deficiency of Heart Yang that leads to fluid retention. In cases of fluid retention with epigastric stiffness symptoms will also include: dizziness, excessive salivation and mental fatigue.

TREATMENT

1. Begin by extending Qi into the patient's Bl-14, Bl-18, CV-15, and CV-17 points. To open up these points, emit Qi into the tissue areas surrounding these points using the Extended Fan Palm technique.
2. Next, use the Sword Fingers hand technique and vibrate Qi into each of these points for the duration of six to twelve breaths at each point. Upon completion, the doctor will then guide the Qi back down the patient's torso and root it into the patient's Lower Dantian.
3. Finally, the doctor emits Qi into the patient's Yellow Court area using the Extended Fan Palm technique and then guide the Heart and Pericardium Channel Qi down the patient's arms using Pushing, Pulling and Leading techniques. This ending is performed to balance the Qi in the upper and lower aspects of the patient's body.
4. As with every treatment, end the procedure by regulating the patient's Microcosmic Orbit (Fire Cycle).

TREATMENT MODIFICATIONS

These modifications are additional formulas which are added onto the previous treatment according to the specific cause and condition of the patient's Heart.

1. In cases of insufficiency of Heart Blood, add Bl-17 and Bl-20 to the treatment points.
2. In cases of internal disturbance of Phlegm Fire, purge from the CV-12 to St-40 points.
3. In cases of Fluid retention, add Bl-21 and Bl-22 to the treatment points, for 14 to 24 breaths. Then, guide the Qi to flow down the patient's Gall Bladder Channels into their Bl-40 points.

PRESCRIPTIONS AND HOMEWORK

1. For treatment of palpitations due to Deficient Heart Blood, have the patient practice the method of Taking in the Red to nourish the Heart (see Chapter 4). Have the patient send the red Qi slowly down into the Heart and then to the Lower Dantian during the exhalation. Practice should be for several minutes, according to the patient's strength and constitution.
2. For treatment of palpitations due to Phlegm Fire, have the patient place both hands on the Heart and slowly inhale. As the patient exhales, he or she should pronounce the sound "Ha." This exercise should continue for several minutes.
3. For Heart regulation, have the patient practice the Heart exercise from the Daoist Five Yin Organ prescriptions (see Chapter 42).

RHEUMATIC HEART DISEASE

Rheumatic valvular Heart disease is a condition where there is chronic damage of the cardiac valve caused by rheumatosis. It clinically manifests with palpitations, dyspnea and edema.

SYNDROMES

1. Heart Blood stagnation is manifested through symptoms such as severe palpitations, bad cough with hemoptysis, lassitude and weakness, purplish-red color of the lips, nails and zygomatic facial regions, pain in the Heart, chest, or both.
2. Deficient Qi and Blood manifests through such symptoms as shortness of breath, palpitations which are aggravated on exertion, perspiration and pale complexion.
3. Heart and Kidney Yang Deficiency manifest through such symptoms as palpitations, pale or darkish complexion, edema, cough, cold hands and feet and dyspnea.

TREATMENT

1. Have the patient sit at the edge of the table, and begin to stimulate the Shendao (GV-11) and Middle Dantian areas.
2. Use the Vibrating Palm hand technique and emit Qi into the patient's Yellow court and Shendao (GV-11) area for 6 to 12 breaths.
3. Use the Extended Fan Palm hand technique and emit Qi into the patient's Heart region, leading Qi down the Heart and Pericardium Channels to the tips of the fingers (on both sides of the body).

TREATMENT MODIFICATIONS

1. When treating patients with Heart Blood stagnation, use the Extended Fan Palm hand technique and emit Qi into the patient's Middle Dantian, leading the stagnant Qi down the Heart and Pericardium Channels and out the hands (on both sides of the body).
2. When treating patients with Deficient Qi and Blood, use the Extended Fan Palm technique and emit Qi into the patient's Middle Dantian (both Shendao GV-11 and CV-17 areas), leading the Qi down the Conception Vessel to the Lower Dantian to root and stabilize the patient's Qi.
3. When treating patients with Heart and Kidney Yang Deficiency, use the Extended Fan Palm technique and emit Qi into the patient's Shendao (GV-11) and Mingmen (GV-4) for 24 breaths.

PRESCRIPTIONS AND HOMEWORK

When prescribing homework for patients with rheumatic Heart disease, have them begin with a quiescent sitting meditation, while focusing on their Lower Dantian.

PRESCRIPTION MODIFICATIONS

1. Have patients with Heart Blood stagnation perform the Heart Massage exercise (see Chapter 39), while toning the sound "Ha."
2. It is advisable for patients with Qi and Blood Deficiency to practice the method of Taking in the Yellow Qi into the Spleen and Red Qi into the Heart from the natural environment.
3. Have patients with Heart and Kidney Yin Deficiency practice Gathering the Moon Cream (see Chapter 11), as well as the method of Taking Yellow Qi into the Spleen and Red Qi into the Heart from the natural environment (see Chapter 4).

CONTRAINDICATIONS

The Heart may either have functional or structural problems. In either condition, Medical Qigong is contraindicated when working directly over a pacemaker.

Also, when treating Heart conditions, make sure the patient is under a Western doctor's care, and inquire as to any medications the patient may be taking.

CHAPTER 45
QI EMISSION THERAPY FOR SPLEEN/STOMACH DISEASES

INTRODUCTION

The Spleen is a solid (Zang) organ and it stores and nourishes Ying (Nourishing) Qi. The Spleen corresponds to the element Earth and is sometimes referred to as the Yellow Emperor. It houses the Yi, which governs the intention, thought, study, concentration, and memorization. It is energetically paired with the Stomach (a hollow organ). The Spleen is in charge of transporting, distributing and transforming nutrients and Qi into Gu Qi, as well as controlling Blood circulation (Figure 45.1).

The Spleen's external connection with the outside world is through the mouth, hence any connection with the mouth can affect the body's acquired constitution, developing a tolerance or intolerance to specific substances (allergies), as well as affect concentration and thought.

In the late summer months, Spleen Qi becomes more active in individuals who already possess strong Spleen Qi, but can become Deficient in those individuals who already have weak Spleen Qi. Excessive eating and drinking of sweet foods, and overexposure to dampness weakens the Spleen.

SPLEEN COMPLICATIONS AND SYMPTOMS

Because of the importance of both the Spleen and Stomach, this chapter is divided into two separate sections. The first section focuses on specific Spleen diseases and how to rectify them. The second section explores the energetic dysfunctions of the Stomach.

The following discussion of treatment begins with an explanation of Spleen complications and symptoms. Spleen syndromes have symptoms which are common to the organ's energetic dysfunction such as: diarrhea, tiredness, and edema. A list of Spleen syndromes and their symptoms are described as follows.



Figure 45.1. The Spleen (Sp) Channels

1. Spleen Qi Deficiency can cause such symptoms as: wheezing, tiredness, abdominal pain, diarrhea, constipation, painful urination, enuresis, bleeding and menorrhagia.
   a. Patients with a failure of normal transporting and transforming Qi activity in the Spleen may have a poor appetite, abdominal distention, loose stools, edema and retention of Phlegm.
   b. Deficient Spleen Qi may cause the Qi in the Middle Burner to sink. This results in shortness of breath, unwillingness to talk, persistent diarrhea, prolapse of the anus or uterus, or gastroptosis (downward displacement of the Stomach).
   c. Spleen Qi Deficiency can result in failure of the Spleen to control the Blood circulation and may be manifested by the following symptoms: bloody stool, bleeding from the uterus, and subcutaneous hemorrhaging.
2. Spleen Yang Deficiency can cause such symptoms as: tiredness and edema.
3. Spleen Blood Deficiency can result in fatigue.
4. Spleen Yin Deficiency can result in tiredness.
5. Damp Heat in the Spleen can cause such symptoms as: sinusitis, edema, common cold, and influenza.
6. Dampness in the Spleen can cause such symptoms as: diarrhea, tiredness, edema, and Wind Stroke.

GENERAL TREATMENT FOR SPLEEN DISEASES

The following is a description of a general protocol used for treating the Spleen. The goal is to introduce the Qigong doctor to the basic hand positions and areas of the patient's body towards which Qi is emitted (or Turbid Qi removed). Once the Qigong doctor becomes proficient at locating these specific points, the treatment will flow more smoothly.

After comparing the various Spleen therapies, the reader will notice that certain patterns repeat


Energize the Deficient Spleen.
Energize the Lower Dantian.
Purge the Toxic Spleen Qi down the Stomach Channel and out the St-36 point.

Figure 45.2. Treating Spleen Conditions

themselves.

1. Generally, the Qigong doctor accesses the patient's Spleen through either direct energetic insertion into the Spleen's anatomical location, or through the patient's channels and external energetic fields.
2. After treating the patient (purging, tonifying, and regulating), the Qigong doctor stimulates the patient's Spleen and Yellow Court areas, and roots the patient's Middle Burner Qi into the Lower Dantian.
3. Next, the Qigong doctor leads any remaining Turbid Qi down the Stomach Channels and out of the patient's St-36 points (Figure 45.2).

Keep in mind that these areas are general and that specific treatment patterns must change as they apply to the patient's exact condition (Excess, Deficient, etc.).

MEDICAL QIGONG THERAPY FOR SPLEEN QI DYSFUNCTION

The primary therapy used to treat the Spleen and gastric diseases include the Windy Breathing method (see Chapter 16) to strengthen the Liver, Spleen, Lungs, and the Kidneys.

1. Spleen diseases should be treated by vocalizing the "Hu" sound, which is effective for removing Turbid Qi accumulated in the Spleen, as well as for aiding digestion (Figure 45.3).
2. To treat insufficiencies of the Middle Burner, the doctor emits Qi into the patient's Zhong Wan CV-12 point and Lower Dantian points to reinforce the patient's Qi in the Middle Burner area.
3. Patients with an Excess Heat syndrome of the Spleen should be treated by guiding the Qi out along the Spleen and Stomach Channels with Pulling and Leading Qi manipulations to expel the Turbid Qi from both the Spleen and Stomach.

SPLEEN QIGONG PRESCRIPTIONS

The following exercise regulates the Qi and Blood of the Spleen Channels, strengthens the Spleen and replenishes Qi. It also regulates the Stomach and promotes digestion. It can be used to prevent and treat diseases and syndromes such as: gastritis, gastric and duodenal ulcers, colitis and gastrointestinal neurosis, abdominal distention, diarrhea and constipation.



Figure 45.3. The "Hu" sound will purge the Spleen.

PRESCRIPTIONS FOR TONIFYING THE SPLEEN

The method of Taking in the Yellow Qi can be used to tonify the Spleen. The properties inherent within the yellow color have a persistent vibratory rate used for tonifying the Spleen and Stomach.

1. Assume a standing or sitting posture. Relax the whole body, breathe naturally, and get rid of any stray thoughts.
2. When inhaling, imagine yellow energy in front of you. Inhale the yellow light energy in through the nose and down into the Spleen organ. As you exhale through the mouth, the dark, pathogenic Qi leaves the Spleen; however, the bright clean color remains in the organ, stimulating and vitalizing it. With each breath the organ retains more clean energy and begins to glow. Repeat for five breaths.
3. Next breathe the color yellow in through the nose, filling the entire mouth. When exhaling through the nose, send the Qi slowly to the Zhongwan CV-12 point, then out to the four limbs, skin, and hair. Repeat five to ten times. Return to the beginning posture and close the training.



Figure 45.4. Twist at the waist, swing the arms, and look towards the opposite direction, focusing the mind's intention on the heel.



Figure 45.5. Turn and look over the shoulder with both eyes wide open.

PRESCRIPTIONS FOR PURGING THE SPLEEN

Purge the Spleen by having the patient rub his or her epigastrium while toning the sound "Hu."

Assume a sitting or standing posture. Gently place both palms (left on the outside for men, opposite for women) flatly on the Zhongwan CV-12 point on the upper abdomen. Exhale, rubbing the palms in a clockwise direction while sounding "Hu". Perform ten to twenty breaths.

Dredging the Spleen and Stomach

The following exercise is used to purge Toxic Qi from the Spleen and Stomach.

1. Assume a standing posture and breathe naturally. While relaxing the whole body, twist at the waist as you swing both arms in front of the body to the left, then to the right. Look in the opposite direction when turning the torso. As you turn your torso, your mind should be focused on your heels. Continue until you feel all tension has left your body (Figure 45.4).
2. Assume a sitting posture. While sitting on a bed, press the palms level on the mattress and meditate until you feel peaceful and relaxed. Turn the head towards the left and look over your left shoulder into the distance. Then turn the head to the right and look back over your right shoulder into the distance. Pause in the center, facing forward (Figure 45.5). When looking over the shoulders, both eyes should be wide open. Repeat five times in each direction.

PRESCRIPTIONS FOR REGULATING THE SPLEEN AND CONDUCTING QI

The following exercise is used to regulate the Spleen after purging or tonifying.

1. In a Wuji posture, begin by placing the hands on the Yellow Court and begin circle rotation in a clockwise direction for 36 rotations, ending at the Lower Dantian. Pause for 18 breaths to root the Spleen Qi in the Lower Dantian.
2. Next, rotate the abdomen in a counterclockwise direction for 36 rotations, ending at the Lower Dantian. Pause for 18 breaths and return to Wuji posture.

SPECIFIC MEDICAL QIGONG THERAPY FOR SPLEEN DISEASES

The following Medical Qigong treatment is used in China to treat specific types of Spleen disease.

DIABETES

Diabetes refers to a syndrome characterized by polydipsia (excessive thirst), polyphagia (excessive eating), and emaciation. It is a general term used to describe diseases characterized by insufficient secretion of insulin and excessive urination.

The prescriptions described in this section can also be used for the treatment of such disorders as: psychogenic polyuria, polyphagia due to hyperthyroidism, hyperhidrosis (excessive sweating), and emaciation.

ETIOLOGY

According to Traditional Chinese Medicine, diabetes is caused by disturbances in the Spleen and Stomach functions of transforming and transporting energy and the accumulation of toxic Heat in the body. These malfunctions can be due to eating too much sweet and greasy food, or drinking too much alcohol.

From the Western medical perspective, there are two types of diabetes, one type can be controlled through diet, the other cannot (usually hereditary). Diabetes is included in metabolic diseases (the Beta cells in the pancreas do not produce enough insulin) and caused by pathogenic factors relating to genetic predispositions, environmental stress, diet, obesity, and alcohol consumption.

In the Medical Qigong clinic there are three main factors that can contribute to the origination of diabetes: improper diet, emotional factors, and congenital predisposition.

1. The first factor is due to improper diet, including the excessive intake of alcohol, acrid, sour, pungent and greasy foods. The excessive intake of these types of foods can cause stagnation at the Middle Burner (which houses the Stomach and Spleen), and failure of the Stomach and Spleen to transport the accumulated Heat inside the body. This in turn can give rise to failure of the body's Yin fluids to nourish the Lungs and Kidneys, resulting in diabetes.
2. The second factor is due to a state of constant emotional upheaval. Emotional upsets can lead to stagnation of Qi which in turn impairs the body's Fluids, causing a Yin Deficiency with a hyperactivity of Evil Fire, resulting in diabetes.
3. The third factor is due to a genetic predisposition that can eventually surface if the patient is negligent with his or her diet and emotional health.

The Qigong doctor focuses on strengthening the patient's Spleen and Stomach, regulating the Liver Qi, and tonifying the Lung, Stomach, and Kidney Yin (which has been consumed by the Toxic Heat). It also is helpful to monitor the patient's eating habits to correct the disturbed metabolic rate and promote the regeneration and secretion by the patient's pancreatic islet cells.

SYMPTOMS

1. Diabetes involving the Upper Burner is characterized by excessive thirst, dry throat, dry tongue, and frequent urination.
2. Diabetes involving the Middle Burner is characterized by consuming abnormally large quantities of food during meals, emaciation, or constipation.
3. Diabetes involving the Lower Burner is characterized by frequent sweet smelling urination, or chyluria (passing of fat globules in the urine), and weakness and softness in the waist and knees.

TREATMENT

1. Begin by stimulating the Bl-23, Bl-20, Bl-13, St-36, and Sp-6 points on both sides of the patient's body.
2. Then purge and dredge the patient's CV-12, CV-4, and St-21 points.
3. Next, use the Extended Fan Palm hand manipulation with the Vibrating Palm technique to emit Qi into the patient's Bl-23, Bl-20, Bl-13, CV-12, and CV-4 for six to twelve breaths.
4. Continue emitting Qi into those points and into the Middle Dantian to regulate the Qi

activities of the Upper, Middle, and Lower Burners.

5. End the treatment by softly holding on to the patient's LI-11, LI-4, and Ht-1 points on both sides of the body, and with a gentle rocking or shaking motion allow the Qi to flow into the patient's body, settling into the patient's Lower Dantian.

PRESCRIPTIONS AND HOMEWORK

The "Inner Health" cultivation meditation is given to patients with diabetes, and is prescribed as follows.

1. Have the patient begin in a sitting posture, eyes closed, body relaxed using natural abdominal breathing.
2. While inhaling, the patient places the tongue against the hard palate, and begins to mentally repeat the mantra "I am quietly sitting."
3. While holding the breath, the patient mentally continues by saying the words "I am healthy."
4. The patient then exhales, releasing the tongue from the palate, while thinking the last phrase.

MEDICAL QIGONG THERAPY AND STOMACH DISEASES

This second section focuses on specific Stomach diseases and how to rectify them (Figure 45.6). The following discussion of treatment begins with an explanation of Stomach syndromes and symptoms. Several Stomach diseases have symptoms which are quite common to the organ's energetic dysfunction, such as epigastric pain.

STOMACH COMPLICATIONS AND SYMPTOMS

A list of Stomach syndromes and their symptoms are described as follows.

1. Stomach Heat can cause headache, epigastric pain, and bleeding.
2. Stomach Damp Heat can cause sinusitis and epigastric pain.
3. Stomach Phlegm Fire can cause epigastric pain and mental and emotional problems.
4. Stomach Deficiency can cause epigastric pain, diarrhea, atrophy syndrome, and bleeding.
5. Stomach Yin Deficiency can cause tiredness, epigastric pain, and bleeding.
6. Cold invading the Stomach can result in epigastric pain.
7. Stagnant Blood in the Stomach can result in epigastric pain.



Figure 45.6. The Stomach (St) Channels

GENERAL TREATMENT FOR STOMACH DISEASES

The following is a description of a general protocol used for treating the patient's Stomach. The goal is to introduce the Qigong doctor to the basic hand positions and areas of the patient's body towards which Qi is emitted (or Turbid Qi removed). Once the Qigong doctor becomes proficient at locating these specific points, the treatment will flow more smoothly.

After comparing the various Stomach therapies, the reader will notice that certain patterns repeat themselves.

1. Generally, the Qigong doctor accesses the patient's Stomach through either direct energetic insertion into the Stomach's anatomical location, or through the patient's channels and external energetic fields.
2. After treating the patient (purging, tonifying, and regulating), the Qigong doctor stimulates the patient's Stomach, Spleen, and Yellow Court areas, and then roots the patient's Middle Burner Qi into the Lower Dantian.
3. Next, the Qigong doctor leads any remaining Turbid Qi down the Stomach Channels and out of the patient's St-36 points (Figure 45.7).

Keep in mind that these areas are general and that specific treatment patterns must change as they apply to the patient's exact condition (Excess, Deficient, etc.).

SPECIFIC MEDICAL QIGONG THERAPY FOR STOMACH DISEASES

The following are several Medical Qigong treatments used in China to treat specific Stomach diseases.

ABDOMINAL PAIN

Abdominal pain is an abnormal condition of the abdomen in which there is a sudden, abrupt onset of severe pain in any part of the abdomen below or just around the umbilicus.

Diseases such as acute pancreatitis, gas-


Stimulate the patient's Stomach and Yellow Court area.
Energize the Lower Dantian.
Purge the Toxic Stomach Qi down the Stomach Channels and out the St-36 points.

Figure 45.7. Treating Stomach Conditions

trointestinal spasm, stress induced abdominal pain, dyspeptic abdominal pain, and peritonitis, etc., in which abdominal pain symptoms appear, should be differentiated. Each differential diagnosis can be treated according to the exercises taught in the prescription section.

ETIOLOGY

The treatment for abdominal pain that is primarily intestinal in origin is different then that of gynecological abdominal pain, which is related to the menstrual cycle (see Chapter 51). There are four main factors which can contribute to the intestinal type of abdominal pain: abdominal pain due to the internal accumulation of Cold in the Lower Burner, abdominal pain due to dysfunction of Spleen Yang, abdominal pain due to food stagnation, and abdominal pain due to emotional stress.

1. Internal Cold in the Lower Burner may accumulate from eating too many cold foods and drinks, or can be due to the invasion of pathogenic Cold caused by exposure to the elements. Women in particular are more prone to Cold invading the abdomen during or immediately after menstruation. When Cold contacts the tissues, it slows down the movement of Qi and Blood, thus causing pain. External Cold may invade the patient's intestines directly without causing exterior symptoms, resulting in a sudden onset of pain and diarrhea.
2. Patients who are usually Deficient in Yang Qi often have a weak digestive system and a dysfunction of the Spleen Yang Qi. In this condition, pain often follows a pathogenic invasion, no matter how mild it may be. The pathogenic invasion may be due to overeating, overexertion, or brought on by eating after fasting and dieting, or simply by an Exterior Cold invasion.
3. Food stagnation is related to food intake or constipation, and is induced by Qi stagnation. The Stomach fails in digesting the food and the Spleen fails in separating and transporting the Clear and Turbid Qi.
4. Emotional stress is related to the circulation of Qi and Blood in the abdomen, and thus affects both the Liver and Spleen. Anger, frustration, and resentment can cause Liver Qi stagnation in the intestines, resulting in abdominal pain. Pensiveness and worry affect the Spleen and Lungs, impairing the transforming ability of the Spleen Qi and the downward descending ability of the Lung Qi, and likewise result in abdominal pain.

SYMPTOMS

1. Abdominal pain due to the internal accumulation of Cold, occurs abruptly, and may be relieved by defecation.
2. Abdominal pain due to Spleen Yang dysfunction, is characterized by continuous recurring pain, which may be relieved by pressure. Symptoms include loose stool, mental fatigue, and aversion to Cold.
3. Abdominal pain due to food stagnation, is characterized by gastric and abdominal distention, severe tenderness in the abdominal area, aversion to food and belching with acid regurgitation.
4. Abdominal pain due to emotional stress, is characterized by crying and vomiting.

TREATMENT

1. Have the patient lay on his or her side and begin stimulating the Bl-21, Bl-20, CV-12, St-36, and St-25 points on both sides of the body.
2. Purge the patient's Bladder Channels from the mid-back and waist area down to the feet three to five times.
3. Using the Vibrating Palm, emit Qi into the patient's CV-12, St-25, Bl-21, and Bl-20 points on both sides of the body. Purge and guide the Toxic Qi through the abdomen and down the lower extremities along the Stomach and Bladder Channels and out the patient's feet.
4. Using the Extended Fan Palm technique, extend Qi into the patient's CV-12 and both St-25 points for 14 breaths. Using Pulling and Leading manipulations, guide the patient's Qi down along the Stomach Channels and out both of the patient's feet.
5. Finally, Circle Rotate the patient's abdomen for 81 breaths in a clockwise direction.



Figure 45.8. To tonify Deficient Stomach Qi, the patient must imagine drawing Qi into the body through the Baihui point at the top of the head, and the Yongquan points at the bottom of the feet. All three rivers of energy must meet to form a pool of energy within the Stomach area, which the body will absorb and store.



Figure 45.9. To treat Excess Stomach Qi, begin from a supine posture. While inhaling, imagine the Qi flowing down the Stomach Channels from the Baihui point ending just below the sternum at the Stomach area. Exhale and imagine the Turbid Qi dissolving and melting into the Lower Dantian, then disperse it from the body, out the pores.

TREATMENT MODIFICATIONS

1. In cases of abdominal pain due to the internal accumulation of Cold, add the method of extending Hot Qi.
2. In cases of pain due to Spleen Yang dysfunction, extend Hot Qi into the patient's Bl-21, Bl-20, and Mingmen area.
3. In cases of pain due to food stagnation, emit Qi using the Extended Fan Palm with clockwise then counterclockwise Spiraling methods into the patient's CV-12, CV-4, and St-25 points.
4. In cases of pain due to emotional stress, emit Qi using the Extended Fan Palm hand technique into the patient's Ht-7 and Pc-6 points on both sides of the body. Purge and Circle Massage the Shendao (GV-11) area in a counterclockwise direction.

PRESCRIPTIONS AND HOMEWORK

1. Have the patient place his or her right palm on the CV-12 area and begin to Circle Massage 36 times in a clockwise and then 36 times in a counterclockwise direction.
2. After completing the circle rotations, the patient pauses for a moment, and then leads the Qi down to the navel and continues the 36 rotations, in both clockwise and counterclockwise directions.
3. Next, the patient inhales and presses the fingers of both hands gently below the xiphoid process. The patient exhales and directs the Qi down along the midline of the body to the pubic symphysis area for 36 times.
4. Finally the patient overlaps his or her hands (right over the left in men and opposite in women) and places them on the midpoint of the lower abdomen to knead the tissue area clockwise and then counterclockwise 36 times.

PRESCRIPTIONS MODIFICATIONS

- In cases of Stomach pain due to Deficient Stomach Qi, have the patient lie supine. The patient must imagine drawing Qi into his or her body through the Baihui point at the top of the head, and the Yongquan points at the bottom of the feet. All three rivers of energy must meet to form a pool of energy within the Stomach area, which the body will absorb and store into the Stomach's spacial cavity (Figure 45.8).

- In cases of Stomach pain due to Excess Stomach Qi and to treat Excess Stomach Qi symptoms, have the patient lie supine. As the patient inhales, he or she is to imagine the Qi flowing down the Stomach Channels (from the Baihui point) ending just below the sternum at the stomach area. As the patient exhales, he or she imagines the Turbid Qi trapped within the Stomach dissolving and melting into the Lower Dantian. Next, the patient disperses the Toxic Qi from the body out through the pores (Figure 45.9).

CHRONIC GASTRITIS

In Traditional Chinese Medicine, this disease belongs to the category of epigastralgia. Gastritis is described as an inflammation of the Stomach. Inflammation of the gastric mucosa is the main clinical manifestation of chronic gastritis, and results in chronic epigastralgia and dyspepsia (air hunger, resulting in difficult breathing, shortness of breath, sometimes accompanied by pain).

ETIOLOGY

Generally, emotional factors such as worry, anxiety, or anger may cause stagnation of Qi. Stagnant Qi, by impeding the function and flow of the body's energy, causes Qi deviations and obstructions that result in a stomach ache.

Gastritis can be superficial (affecting only the superficial layers of the Stomach) or atrophic (causing thinning of the Stomach mucosa). Its main manifestations are epigastric pain, which occurs about one hour after eating, followed by nausea, belching, and vomiting with sour regurgitation.

SYNDROMES

1. Liver and Stomach Qi stagnation, manifests as a distending pain, fullness, and discomfort in the Stomach, which is aggravated after a meal. The pain is not fixed to any specific Stomach location and worsens under emotional stress, causing belching with acid regurgitation and nausea.
2. Stomach Yin Deficiency due to Stomach Heat manifests as a stomach ache accompanied by a scorching sensation. The pain is not fixed to any specific Stomach location and is aggravated when the Stomach is empty, and is alleviated after a meal. The symptoms are expressed as irritability, dysphoria, and excess appetite.
3. Weakness of the Spleen and Stomach manifests as a dull stomachache which is relieved by Heat and pressure. Symptoms are expressed as abdominal distention, dim complexion, lassitude, cold limbs, and anorexia. If the patient has congenital insufficiency of Yang in the Middle Burner (the functional area of the Spleen and Stomach), Cold may originate from the interior of the body.

TREATMENT

1. Have the patient lie supine and relax his or her whole body, focusing especially on the Stomach area. The patient imagines the Toxic Qi dispersing upon exhalation.
2. Begin to purge and dredge the patient's CV-15 point (just below the xiphoid process), leading the Qi down to the Lower Dantian.
3. Next, use a Vibrating Palm hand technique to emit Qi into the patient's CV-12 point and both St-21 points for 14 to 28 breaths.
4. Applying the Extended Fan Palm hand technique to the patient's CV-12 and Middle Dantian, begin drawing Qi downward along the Conception Vessel and Stomach Channels to the bottom of the patient's feet.
5. Finally, have the patient lie prone and stimulate the Bl-20 and Bl-21 points on the lumbar-dorsal region, directing the energy from the upper back down to the Mingmen area.

TREATMENT MODIFICATIONS

1. For Stagnant Liver and Stomach Qi, use the Extended Fan Palm hand technique to emit Qi into the patient's Bl-18 points, pulling and conducting Qi along the Gall Bladder and Liver Channels down the legs and out the feet on both sides.
2. For Stomach Yin Deficiency due to Stomach Heat, use the Vibrating Palm hand technique

to emit Qi into the patient's Bl-20 and Bl-23 points, leading the Qi down the patient's Bladder Channels to the feet.

3. For Spleen and Stomach Deficiency, use the Extended Fan Palm hand technique to emit Qi into the patient's Lower Dantian area.

PRESCRIPTIONS AND HOMEWORK

Have the patient practice the Descending the Yang and Ascending the Yin technique (see Chapter 41).

PRESCRIPTION MODIFICATIONS

1. For patients with Liver and Stomach Qi stagnation, have the patient practice the Spleen and Stomach Massage (see Chapter 39). Then perform the healing sounds "Hu" to regulate the Spleen and "Shu" to regulate the Liver.
2. For treating patients with Stomach Yin Deficiency due to Stomach Heat, have the patient first dredge the Spleen and Stomach and then perform the "Chui" (pronounced Chree) healing sound to regulate the Kidneys. Next, have the patient practice the tonification method of Taking in the Yellow Qi (see Chapter 4).
3. For treating patients Deficient Spleen and Stomach Qi, have the patient first practice the Daoist Five Organ Regulation exercise (see Chapter 42). Next, have the patient practice the tonification method of Taking in the Yellow Qi to strengthen the Spleen and Taking in the Red Qi to strengthen and regulate the Heart.

GASTRIC AND DUODENAL ULCERS

An ulcer is an open sore or lesion of the skin or a mucus membrane, accompanied by sloughing of inflamed, dead, or dying tissue, that causes the Stomach's lining to become more vulnerable to acids. If the sore becomes infected puss is discharged.

ETIOLOGY

A gastric or duodenal ulcer refers to a chronic ulcer seen only in the regions where the gastrointestinal tract contacts the patient's gastric juice. Its formation and development is closely related to the digestive functions of the acidic gastric juices and pepsin. Clinically this type of ulcer is characterized by chronic recurring epigastralgia, lasting for a few weeks, with pain occurring from 30 minutes to two hours after eating.

Currently, Stomach ulcers are also being treated through either herbs or antibiotics (from Western medicine). They are caused by bacterial infections resulting from either Qi and Blood stagnation or a Deficient Cold syndrome of the Spleen and Stomach.

SYNDROMES

- Qi and Blood stagnation results in a distended pain and fullness in the Stomach, tenderness, belching, and acid regurgitation, which becomes aggravated by emotional stress.
- A Deficient Cold syndrome of the Spleen and Stomach results in a dull pain within the Stomach which is relieved by heat and compression and aggravated by cold. There can also be vomiting with watery regurgitation, shallow complexion, cold extremities, lassitude, and weakness.

TREATMENT

1. Have the patient sit at the end of the treatment table, and begin extending energy into the patient's mid-back along their Bl-18, Bl-20, and Bl-21 points using the Extended Fan Palm technique.
2. Next, use the Vibrating Palm to extend energy into the patient's Yellow Court area. When the area has been sufficiently stimulated, purge the Toxic Qi out of the patient's body by leading the Qi down to the Lower Dantian for 14 to 28 breaths.
3. Finally, use the Extended Fan Palm hand technique to emit Qi into the patient's CV-12 and St-34 points for 14 breaths. Then lead the Qi down the Conception Vessel into the Lower Dantian to root and stabilize the patient's energy.

TREATMENT MODIFICATIONS

- When treating patients with Qi and Blood stagnation, use the Extended Fan Palm hand method to emit Qi into the CV-12, CV-13, and St-21 points. Next, direct the Qi along the patient's Conception Vessel and Stomach Channels, leading the Toxic Qi down the patient's legs and out of the body via the St-36 points.

- When treating patients with a Deficient Cold syndrome of the Spleen and Stomach, use the Extended Fan Palm hand method to emit Qi into the patient's Mingmen and Lower Dantian areas.

PRESCRIPTIONS AND HOMEWORK

In treating patients with ulcers, have them practice the Old Man Searching for the Reflection of the Moon at the Bottom of the Tide Pool exercise (see Chapter 53).

PRESCRIPTION MODIFICATIONS

- For patients with Qi and Blood stagnation, have them perform the Spleen and Stomach Massage (see Chapter 39) while sounding "Hu." Next, have the patient dredge the Spleen and Stomach using the sound "Shu" to purge the Liver and regulate Liver Qi.
- For patients with a Deficient Cold syndrome of the Spleen and Stomach, have them practice the method of Taking in the Yellow Qi from the natural environment.

CHRONIC CONSTIPATION

Chronic constipation refers to the prolonged retention of feces in the intestinal tract and difficulty in discharging the fecal matter. This condition is not only painful to the patient, but also increases toxicity in the body. It is clinically characterized by decreased times of fecal discharge or small amounts of feces which are considered either too dry and hard, or too difficult to be discharged.

Generally, the transitional time for food to pass through the digestive tract for humans takes 24 to 40 hours. The postponement of defecation over two days is considered constipation, although some normal patients may have regular defecation every two to three days.

ETIOLOGY

The common causes of constipation are: Diet, Febrile Diseases, Emotional Stress, and A Sedentary Life-style.

1. Diet plays a major role in causing constipation. Constipation can result from the excessive consumption of hot, spicy, or greasy foods. This excess consumption of hot and greasy foods can dry up the fluids of the Stomach and intestines, thereby drying up the stool so that it cannot properly move through the intestinal walls.

   An excess consumption of Cold foods can block the Spleen's function of transporting and thus prevent the stool from moving downwards.

   Finally, a lack of fiber in the food, lack of sufficient fluid intake or excessive alcohol consumption can cause constipation.
2. Febrile diseases can be caused by External Wind Heat invasion, which if not rapidly expelled from the body, can turn into an Interior Heat condition. The Interior Heat usually attacks the Lungs, Stomach, and intestines causing the Body Fluids to dry up. A Deficiency of Body Fluids from the retention of Heat within the intestines (even after the febrile disease has passed) can cause dry stool and constipation.
3. Liver Qi stagnation (due to mental depression, anger, resentment, or frustration) can cause a Qi obstruction in the Lower Burners that affects bowel movements and leads to constipation, abdominal distention, and pain. Excessive studying, worrying, and thinking affects the Spleen, slowing down its transportation of food in the intestines, this in turn can lead to constipation.
4. A sedentary life-style, whether from choice or due to a weak constitution from a chronic or severe illness (or surgery), can cause constipation. Patients in convalescent homes often suffer from constipation due to a lack of exercise and poor diet, which can lead to Spleen Qi and Blood Deficiency. Lack of exercise weakens the Spleen Qi and can cause Liver Qi stagnation. When Spleen Qi becomes Deficient for long periods of time, the Spleen energy fails to provide the Qi to move the stool, resulting in constipation.

SYNDROMES

- Constipation due to an Excess condition is caused by decreased times of fecal discharge (once every three to seven days), and is usually accompanied with fever, thirst, poor appetite, and emotional anxiety.

- Constipation due to a Deficient condition is mostly seen in patients who have just recovered from an illness, or have just given birth and have become Deficient in Qi and Blood. It may also be observed in patients who suffer from a congenital insufficiency of Yang Qi in their Lower Burner and an accumulation of Yin Cold, which makes it difficult for the intestines to perform their normal transporting function. Patients with a Deficient condition may have bowel movements every three to seven days. The stool may be very dry, hard, and difficult to pass. This condition is clinically manifested by a pale and dull complexion, listlessness, and cold pain in the abdomen which is relieved by heat. The patient may also experience emotional fright due to a Kidney Qi Deficiency.

TREATMENT

1. Have the patient sit at the end of the treatment table, and begin to stimulate the patient's mid-back between the Bl-23 and Bl-25 points. Then stimulate the patient's lower lumbar and coccygeal areas, dredging and purging the Toxic Qi down the patient's thighs and the feet, while stimulating the Bl-31 through Bl-34 points.
2. The doctor will then have the patient lie supine and begin to stimulate the patient's Yellow Court and Lower Dantian areas, using the Vibrating Palm hand technique for 14 breaths.
3. Next, apply the Kneading Tiger Palm with the Vibrating and Quivering hand manipulations to emit Qi into the back of the patient's head at the Bl-10 points for 12 breaths, and then onto the patient's Lower Dantian for 14 breaths.
4. After energizing the patient's Lower Dantian, emit Qi, using the Extended Fan Palm technique, into the patient's middle epigastrium and navel area, as well as into the Lower Dantian. Finally, use the Spiraling and Quivering hand manipulation in a clockwise direction to gather the stagnant Qi and to lead it down the patient's Stomach Channels and out the legs.

TREATMENT MODIFICATIONS

- When treating patients with an Excess type of constipation, use the Extended Fan Hand Palm technique to emit Cold Qi into the patient's lower abdomen. Rotate the hand in a counterclockwise direction, while purging the Toxic Qi from the patient's body. Repeat for 14 breaths.
- When treating patients with a Deficient type of constipation, use the Vibrating Palm technique to emit Qi into the patient's Lower Dantian and Mingmen area for 8 to 16 breaths.

PRESCRIPTIONS AND HOMEWORK

To treat chronic constipation, have the patient practice the Daoist Five Yang Organ Regulating exercise (see Chapter 42) for 250 breaths twice a day.

PRESCRIPTION MODIFICATIONS

- For patients with an Excess type of constipation, place them in the Wuji posture with their hands resting on their lower abdomen. Begin with a clockwise rotation, imagining the Toxic Qi draining from the patient's Spleen and Stomach areas, down into their Stomach Channels and out their feet.
- For patients with a Deficient type of constipation, have them practice rubbing their Lower Dantian to strengthen the abdominal Qi, and have them practice the Gathering the Sun's Essence meditation (see Chapter 11).

CHAPTER 46
QI EMISSION THERAPY AND LUNG DISEASES

INTRODUCTION

The Lungs are solid organs that control the cycles of Qi circulation in the body, and are sometimes referred to as the White Emperor. They correspond to the element Metal. The Lungs house the Po (Corporeal Souls) and are in charge of respiration and regulating the metabolism of the Body's Fluids (Figure 46.1). The Lungs are also responsible for keeping Qi pure and extending it downward. The Lungs are energetically paired with the Large Intestine (a hollow organ).

The Lungs' upper external connection with the outside world is through the nose, hence any fragrance or odor inhaled through the nose affects the senses and evokes emotional responses from the Po.

In the fall months, the Lung Qi becomes more active in individuals that already possess strong Lung Qi, but becomes Deficient in those who already have weak Lung Qi. The excessive eating and drinking of pungent foods and the overexposure to dryness drains the Lungs.



Figure 46.1. The Lung (Lu) Channels

LUNG COMPLICATIONS AND SYMPTOMS

This section focuses on specific Lung diseases and how to rectify them. The following discussion of treatment begins with an explanation of Lung syndromes and symptoms. Several Lung diseases have symptoms which are quite common to the organ's energetic dysfunction, such as headaches, cough, the common cold and influenza. A list of Lung syndromes and symptoms are described as follows.

1. Wind Cold invading the Lungs usually enters the patient through the pores of the skin and body hair (which are ruled by the Lungs). If the Lungs' energetic field is invaded by Wind Cold, it may cause the Lung Qi to become impure, ascend, and cause obstructions in the pores, resulting in a Wind Cold syndrome. This can cause the following symptoms: severe aversion to cold, headache, cough, the common cold or influenza, breathlessness, asthma, and allergic rhinitis.
2. Wind Heat Invading the Lungs usually enters the body by way of the mouth and nose; the nose being the orifice to the Lungs. If the Lungs' energetic field is invaded by Wind Heat, it may cause the Lung Qi to become impure, ascend, and impede the ability of the

pores to expel pathogenic Evils, resulting in a Wind Heat syndrome. This can cause the following symptoms: slight aversion to cold, headache, cough, the common cold or influenza, asthma, allergic rhinitis and sinusitis.

3. Wind Dampness is a type of Wind Cold syndrome. It consists of both Wind and Dampness together, invading either the skin (causing itching and rashes) or the channels and joints (causing painful obstruction syndrome). If the Lungs' energetic field is invaded by Wind Dampness, it causes the following symptoms: skin rashes, swollen joints, body aches, headaches, the common cold and influenza.
4. Wind Dryness invading the Lungs causes the following symptoms: dry, itchy sore throat, dry lips, dry mouth, the common cold and influenza, cough and bleeding.
5. Lung Heat causes the following symptoms: restlessness and a feeling of heat, common cold and influenza, cough, sinusitis, breathlessness and atrophy syndrome as the body's functions begin to shut down.
6. Lung Phlegm Heat causes the following symptoms: common cold and influenza, cough with expectoration, breathlessness and a sensation of oppression in the chest.
7. Cold-Damp Phlegm invading the Lungs causes the following symptoms: a feeling of heaviness, cough with profuse expectoration, wheezing, nausea, poor appetite and breathlessness.
8. Lung Qi Deficiency causes the following symptoms: breathlessness, wheezing, slight cough with no phlegm, asthma, allergic rhinitis, tiredness, spontaneous sweating, and enuresis or incontinence.
9. Lung Yin Deficiency causes the following symptoms: night sweating, extreme tiredness, breathlessness, asthma, dry cough in short bursts, and Five Palms Hot (a condition also known as "Five Center Heat," in which the patient feels a hot sensation in the palms and soles of the feet, accompanied by heat and agitation of the chest and/or head area).


Access Lu-1 and 2, to purge the Lungs.
Access GV-14, Bl-12 and 13, to purge the Lungs.

Figure 46.2. Treating Lung Diseases


Purge the Lungs through the Lung and Large Intestine Channels.

Figure 46.3. Drain the Turbid Qi out of the Lungs, down the Lung Channels and out of the hands.



Figure 46.4. Replenish the mother (Spleen) to nourish the child (Lungs).

GENERAL TREATMENT FOR LUNG DISEASES

The following is a description of a general protocol used for treating a patient's Lungs. The goal is to introduce the Qigong doctor to the basic hand positions and areas of the patient's body towards which Qi is emitted (or Turbid Qi removed). Once the Qigong doctor becomes proficient at locating these specific points, the treatment will flow more smoothly.

After comparing the various Lung therapies, the reader will notice that certain patterns repeat themselves.

1. Generally, the Qigong doctor accesses the patient's Lungs through either direct energized insertion into the Lungs' anatomical location, or through the patient's channels and external energetic fields (Figure 46.2).
2. After treating the patient (purging, tonifying, and regulating), the Qigong doctor stimulates the patient's Lungs and Upper Burner areas and roots the patient's Qi into the Lower Dantian.
3. Next, the Qigong doctor leads any remaining Turbid Qi down the Lung Channels and out the patient's hands (Figure 46.3).

Keep in mind that these areas are general and that specific treatment patterns must change as they apply to the patient's exact condition (Excess, Deficient, etc.).

MEDICAL QIGONG THERAPY FOR LUNG QI DYSFUNCTION

Patients with Lung disease may have a pale complexion, dry hair, dyspnea (difficult breathing), hyposmia (a deficient sense of smell), stuffy nose, dryness and itching of the skin, or discomfort and pain in the chest and back. Patients may dream of the sun, moon, clouds, or of having sex. The primary therapies used to treat Lung diseases include the Breath regulation and Qi reinforcing meditations (see Chapter 16).

- Patients with an Excess Heat syndrome of the Lungs may have a flushed right cheek. To treat this type of syndrome, have the patient utter the sounds "Si" (Sss) for the Lungs and "Chui" (Chree) for the Kidneys. Guide the Evil Qi out of the patient's body along the Lung and Large Intestine Channels using the Pushing, Pulling and Guiding Qi manipulations.
- Patients with a Deficient syndrome of the Lungs may have shortness of breath and be unable to regulate their breathing. To treat this type of syndrome, have the patients inhale the sound "Hu," as they visualize absorbing the color yellow to replenish the Spleen (the mother); this will nourish the Lungs (the child). Next, the patient guides the Qi back to the Lungs (Figure 46.4).

LUNG QIGONG PRESCRIPTIONS

These exercises regulate the Qi in the Lung Channels, tonify the Lungs, replenish Qi, ventilate the Lungs, and relieve asthma, coughing, and sputum. These exercises can be used to prevent and treat the following diseases and syndromes: bronchitis, pulmonary emphysema, and bronchial asthma, as well as dyspnea and abundant expectoration.

PRESCRIPTIONS FOR TONIFYING THE LUNGS

The Taking in the White Qi meditation can be used to tonify the Lungs. The properties inherent within the color white have a persistent vibratory rate used for tonifying the Lungs and Large Intestine.

1. Assume a standing, sitting, or lying posture.



Figure 46.5. Inhale



Figure 46.6. Exhale



Figure 46.7. Inhale



Figure 46.8. Exhale

Relax the whole body, breathe naturally, and get rid of any stray thoughts.

2. When inhaling, imagine a white energy in front of you. Inhale the white light energy in through the nose and down into the Lungs. As you exhale through the mouth, the dark, pathogenic Qi leaves the Lungs; however, the bright clean color remains in the Lungs, stimulating and vitalizing them. With each breath the Lungs retain more clean energy and begin to glow. Repeat for five breaths.
3. Next breathe the color white in through the nose, filling the entire mouth. When exhaling through the nose, send the Qi slowly into the Lungs, then down to the Lower Dantian, and then further out into the skin and hair of the whole body. Repeat nine to eighteen times. Return to the beginning posture and close.

PRESCRIPTIONS FOR PURGING THE LUNGS

Purge the Lungs by having the patient rub his or her chest while sounding "Sss."

The patient should assume a sitting or standing posture. Both palms are placed flat on the sides of the chest as the patient inhales slowly. When exhaling, the patient sounds the word "Sss" while rubbing the chest with both palms (circling up and down, from the center outward). This exercise is performed for six to twelve breaths.

PRESCRIPTIONS FOR REGULATING THE LUNGS AND CONDUCTING QI

The following exercise is used to regulate the Lungs after purging or tonifying.

1. Sit with the legs crossed, breathe in with the spine arched backwards and the hands by the sides pressing against the ground; extend the chest, and inhale until the chest is full (Figure 46.5).

   Pause, then push the upper back in a posterior direction and draw in the chest while exhaling through the nose (Figure 46.6). Repeat four to nine times.
2. Next, still sitting with the legs crossed, place the palms on the knees. Inhale with the spine erect and turn the head allowing the torso to turn slightly to the left (Figure 46.7). Then bend forward and exhale while facing the center (Figure 46.8). Next, inhale and turn to the right, then again bend forward and exhale while facing the center. Always inhale when turning to the sides, and exhale while facing the center.

SPECIFIC MEDICAL QIGONG THERAPY FOR LUNG DISEASES

The following are several Medical Qigong treatments used in China to treat specific Lung diseases.

TREATING THE COMMON COLD AND INFLUENZA

Upper respiratory tract infections belong to the category of common colds, while influenza belongs to the category of seasonal epidemic colds. Both conditions may be treated by referring to the prescriptions described within this section.

ETIOLOGY

The common cold is a generic term used to describe an Exterior condition caused from the invasion of pathogenic Wind (Wind Cold, Wind Heat, Wind Damp Heat or Wind Dry Heat). It is generally associated with coryza or inflammation of the respiratory mucous membranes.

Upper respiratory tract infection is caused by viruses or bacteria. Influenza is known as an acute, contagious respiratory infection, characterized by sudden onset. The chief clinical manifestations are stuffy nose, nasal discharge, coughing, sneezing, sore throat, fever, headache, chills, and an aversion to wind.

If the pathogenic Qi is on the Exterior level of the body, the internal organs are not affected, and only the patient's Wei Qi is involved. If the pathogenic factor becomes Interior, the patient's internal organs are affected, especially the Lungs and Spleen. If the pathogen is not cleared and purged from the patient's body, it may either penetrate more deeply into the patient's body and cause serious problems, or give rise to residual Heat which causes chronic post-viral fatigue syndromes.

SYNDROMES

- A Wind Cold syndrome has the following symptoms: chills, headache, aches and painful joints, coughs and sore itchy throat, stuffy nose, low fever, and no sweating with profuse, watery nasal discharge.
- A Wind Heat syndrome has the following symptoms: fever, cough, headache, slight aversion to cold, swollen and sore throat, thick yellow sputum, slight thirst, and perspiration. Once the pathogenic factor penetrates into the patient's interior, the body's Qi begins to fight against it, causing a fever and feeling of heat inside the body, with an aversion to cold, and shivering.

TREATMENT

1. Have the patient sit at the end of the treatment table.
2. Begin by stimulating the energy within the patient's head, purging and leading the Toxic Qi down the patient's arm and out the LI-11 and LI-4 points.
3. Then stimulate the patient's Yintang (Third Eye) and Taiyang (temple) points. Using Pulling and Leading Qi manipulation techniques, purge and guide any remaining Toxic Qi downward, along the Conception Vessel and the Stomach Channels, out the patient's feet, three to seven times.
4. Next, to balance the functional activities of the body's Qi, stimulate the tissue area on the patient's upper back and head (GV-14 and GV-16, Bl-12 and Bl-13) using the Extended Fan Palm technique, and guide the Qi downward along the Bladder Channels to the patient's feet.
5. Finally, softly grasp the patient's LI-4 and LI-11 points and gently shake the arm, stimulating the patient's Lung Qi. This technique is performed on each of the patient's arms.

TREATMENT MODIFICATIONS

1. When treating patients with Wind Cold syndrome, extend Hot Qi into the GV-14 and Bl-12 points, using the Extended Fan Palm technique, and guide the Qi downward along the Bladder Channels to the patient's feet and out the body.
2. When treating patients with Wind Heat syndrome, extend Cold Qi into the GV-14, Bl-13, and GB-20 points, using the Extended Fan Palm technique, and guide the Qi downward along the Stomach Channels to the patients' feet and out the body.
3. When treating patients with nasal obstruction, extend Vibrating Qi, using the Sword Fingers technique, into the Ll-20 points for 9 breaths.
4. When treating patients with cough, chest stuffiness, and Phlegm, extend Vibrating Qi, using the Sword Fingers technique, into the CV-17, Lu-1, and Lu-2 points for 8 breaths.

PRESCRIPTIONS AND HOMEWORK

The patients should be given the Ten Dragons Run Through the Forest exercise (see Chapter 41) to sweep and purge the Gall bBladder

Channels. Most of the attention should be placed on feeling the Qi beneath the hands, with emphasis placed on exhalation to expel the pathogenic Wind from the body. Perform this prescription for 24 to 50 times.

CHRONIC BRONCHITIS

Chronic bronchitis is a condition caused by the chronic inflammation of the mucous membranes of the bronchial tubes.

ETIOLOGY

Chronic inflammation of the bronchial mucosa and peribronchial tissues is mostly due to lingering and recurrent acute bronchitis, or may occur after an infection from other diseases. The chief clinical manifestations are chronic recurring cough, expectoration and dyspnea. Bronchitis can be divided into acute and chronic conditions.

1. Acute bronchitis corresponds to the Qi level of infection within the four level identification patterns. It is the easiest to treat, and normally manifests with Hot Phlegm symptoms.
2. Chronic bronchitis takes a little longer to heal and the doctor should focus treatment on attending to the root and manifestation of the disease simultaneously (purging Phlegm and dispersing the Heat or Cold).

SYNDROMES

- For Phlegm Dampness attacking the Lungs, the main symptoms are abdominal distention, cough with copious white sputum, stuffiness in the chest and loss of appetite.
- For Lung and Spleen Deficiency, the main symptoms are cough with sputum, shortness of breath, spontaneous sweating, loss of appetite and loose stool.

TREATMENT

1. Have the patient sit at the edge of the table. Begin to purge the patient's Lungs, dredging the Toxic Qi down the Lung Channels and out of the hands.
2. Use the Vibrating Palm technique to stimulate the patient's Middle Dantian, Lu-1, -2, Bl-13, GV-16, and St-40 points. Use 8 to 12 breaths for each point.

TREATMENT MODIFICATIONS

- For Phlegm Dampness attacking the Lungs, use the Extended Fan Palm technique to emit Qi into the patient's Lungs; purge the Spleen and Stomach Channels, leading the Toxic Qi down the channels and out of the St-40 and Sp-6 points on each leg.
- For Spleen and Lung Deficiency, emit Qi using the Vibrating Palm technique into the patient's Bl-20, Bl-23, Bl-13 and CV-12 points for 6 to 12 breaths.

PRESCRIPTIONS AND HOMEWORK

Have the patient practice the Lung exercise from Daoist Five Yin Organ Tonification and Regulation exercises (see Chapter 42) to strengthen and balance the Lungs.

PRESCRIPTION MODIFICATIONS

- For patients suffering from Phlegm Dampness attacking the Lungs, have the patient perform the Sun and Moon Rotating technique (see Chapter 41), sounding "Sss" to regulate the Lungs and the sound "Hu" to regulate the Spleen.
- For patients suffering from Lung and Spleen Deficiency, have them perform the Taking in the White Qi to tonify the Lungs, and the Taking in the Yellow Qi to tonify the Spleen.

ASTHMA

Asthma is a chronic disorder of the respiration organs characterized by difficulty in breathing, wheezing, and tightness in the chest. Bronchial asthma, chronic bronchitis and pulmonary emphysema are all included in the category of this disease.

ETIOLOGY

Asthma is an Excess condition which is caused mainly by a retention of Wind, Cold, Heat or Damp Phlegm in the Lungs. When a patient is affected by invasion of pathogenic Dampness, disorders in Qi mobility develop. Phlegm mixes with Qi and obstructs the air passages, causing dyspnea (shortness of breath) and wheezing.

Asthma may also result from an obstruction of the Lungs due to Phlegm retention caused by a failure of the Spleen to transport, or from a Deficient condition of the Kidneys. The diagnosis of this disease can be divided into two types of asthma: early onset asthma and late onset asthma.

1. Early onset asthma (also called extrinsic or atopic asthma), usually starts during childhood and is divided into non-allergenic and allergenic asthma. Allergic asthma is associated with eczema and it tends to be difficult to treat because it stems from a congenital Lung and Kidney Qi Deficiency and is often hereditary. Early onset asthma can be affected by diet (e.g., lactose intolerance), emotional problems, fatigue, chronic illness and invasion by external pathogenic factors. It is related to an allergic hypersensitivity of the immune system.
2. Late onset asthma (also called intrinsic asthma) normally starts later in life and is due to bronchial hyperreactivity. In late onset asthma there is no hereditary basis. It is generally characterized by a Lung, Spleen, or Kidney Deficiency and a retention of Phlegm. In some cases, asthma can be caused by Liver Qi stagnation or Liver Fire obstructing the descending action of Lung Qi. Late onset asthma can be affected by overwork, excessive sexual activity, emotional stress and the excess consumption of sour, greasy or cold foods.

SYNDROMES

1. For Wind Cold asthma due to External Evils, the main symptoms are dyspnea, coughing, abundant, thin expectoration and clear Phlegm accompanied with external Wind Cold syndrome.
2. For asthma due to the accumulation of Phlegm Dampness in the Lungs, the main symptoms are dyspnea, cough, abundant, thin and sticky expectoration, stuffiness in the chest and in the epigastric region.
3. For asthma due to Deficient Lung and Spleen Qi, the main symptoms include dyspnea, spontaneous perspiration, aversion to Wind, an expectoration of clear, thin Phlegm, weak voice, loss of appetite and general lassitude.
4. For asthma due to Deficient Lung and Kidney Yin, the main symptoms are dyspnea, dry throat and mouth, dry cough, inconsistent fever, night sweating, and with some patients there may be hemoptysis (the expectoration of Blood).

TREATMENT

The therapeutic effect of Medical Qigong is better for patients who have had this disease for a short time period. In chronic asthma, improvement usually takes more time.

1. Begin by stimulating the patient's CV-22, CV-17 and CV-4 points along with the Bl-13 points.
2. Using the Vibrating Palm technique and emit Qi with the left palm into the patient's lower neck and upper back area, while simultaneously extending energy into the patient's Lower Dantian with the right hand for 14 to 28 breaths.
3. Purge the Toxic Qi from the patient's CV-22 and Bl-13 areas, then lead and guide the patient's Lung Qi down the Governing Vessel and Bladder Channels into the Mingmen GV-4 and Bl-23 points. Repeat for 3 to 7 respirations.
4. Using the Sword Fingers hand posture, vibrate energy into the patient's CV-22, -17, Lu-1 and Lu-2 points. Then guide the patient's Qi to flow downward from the chest to the Lower Dantian along the Stomach Channels and Conception Vessel to stabilize the patient's Qi.

TREATMENT MODIFICATIONS

1. To treat a case of Wind Cold syndrome due to exogenous Evils, purge and sweep the patient's Gall Bladder Channels, concentrating on the head area. Then extend Qi into the patient's Lu-1 and Lu-2 points. Use Pulling and Leading manipulations to draw the Toxic Qi along the patient's Lung Channels, expelling the pathogenic Qi out of the fingertips on both hands.
2. In treating cases of Deficient Lung and Spleen Qi, use the Extended Fan Palm hand posture and Vibrating Palm technique to emit Qi towards the patient's CV-12, CV-6, Bl-20 and Bl-13 points for 9 to 18 breaths.

3. In treating cases of Deficient Lung and Kidney Yin, use Extended Fan Palm hand posture and Vibrating Palm hand technique to emit Qi towards the patient's Lower Dantian, Mingmen, and Bl-13 points for 6 to 12 breaths.

PRESCRIPTIONS AND HOMEWORK

Patients are encouraged to practice physical exercises to strengthen the body and enhance their resistance to pathogenic invasion. These exercise prescriptions however, must not be too strenuous. Two prescriptions used for relieving asthma and respiratory pain are described as follows.

Exercise to Relieve Asthmatic Pain. For chronic conditions of asthma, patients are given the following prescription:

1. From a sitting or standing posture, slightly close the eyes and relax. Stimulate the energy of the chest by kneading the sternum from the sternal notch to the xiphoid process 36 times.
2. Inhale and place the right palm on the left side of the chest. Exhale, and begin dredging the left Lung Channel using a sweeping motion to purge the Toxic Qi down the arm and out through the hand. Perform this Purging exercise 10 times, then repeat 10 times on the opposite side.
3. Finally, perform the Kidney Rub exercise (see Chapter 39) for 18 breaths.

Exercise to Relieve Asthma Attacks

For acute asthmatic attacks, patients are given the following prescription.

From a sitting or standing posture, slightly close the eyes and relax the muscles of the chest and back. Take a deep breath and say "relax" silently, while simultaneously imagining the Lungs relaxing and descending the body's Qi down to the toes along both lateral sides of the body. As the Qi descends from the Lungs, imagine this energy flowing like water, down your body into the Earth. Repeat this procedure until the asthma attack has receded.

PRESCRIPTION MODIFICATIONS

- Patients with Deficient Lung Qi should practice the previous exercises in combination with Taking in the White Qi.
- Patients with a domination of pathogenic factors should practice the previous exercises in combination with rubbing their chest and uttering the sound "Sss."

BRONCHIECTASIS

Bronchiectasis is the chronic dilation of the bronchi, with a secondary infection that usually involves the lower portion of the Lungs. Dilation may involve an isolated segment or can spread throughout the entire bronchi.

ETIOLOGY

This disease is characterized by hypertrophy of the mucus-secreting glands in the bronchial tree. The dilation and deformation of the bronchi are caused by the damage of the vessel walls due to chronic inflammation of the bronchi and the peribronchial Lung tissue. In advanced cases the bronchi themselves can become inflamed with infection. The clinical manifestation is a chronic cough with an excessive expectoration of sputum. If followed by infection, there may be night sweating, fever and lassitude.

SYNDROMES

1. Liver Fire attacking the Lungs can manifest with pain and distention in the chest and hypochrondium, flushed face, cough, expectoration of yellow, thick sputum and repeated hemoptysis (Blood discharging from the larynx, trachea, bronchi, or Lungs).
2. Dry Heat scorching the Lungs manifests as a dry throat and dry cough with little sputum, which is bright red and bloody.
3. Qi and Yin Deficiency manifests through shortness of breath, lassitude, emaciation, repeated hemoptysis, cough with little sputum, erratic fever and flushed face (especially around the cheeks).

TREATMENT

1. Have the patient sit at the edge of the table, and begin to stimulate the upper chest at the Lu-1 and Lu-2 points and the upper back around the patient's Bl-13 points.
2. Using the Extended Fan Palm hand technique, emit Qi into the patient's Middle Dantian directing the energy to flow into the Lu-1 and Bl-13 points for 6 to 12 breaths.

3. Using the Leading and Guiding hand techniques, purge and dredge the Toxic Qi out the Lung Channels (i.e., down the arms and out of the hands).

TREATMENT MODIFICATIONS

1. When treating patients with Liver Fire attacking the Lungs, include the Vibrating Palm technique, and emit Qi into the patient's Bl-13 and Bl-18 points for 12 breaths. Then purge the Liver Channels down the torso and out of the legs.
2. When treating patients with Dry Heat scorching the Lungs, apply the Vibrating Palm technique to emit Qi into the patient's Bl-23 and Bl-13 points for 24 breaths.
3. When treating patients with Qi and Yin Deficiency, apply the Vibrating Palm technique to emit Qi into the Bl-13, Bl-20, and Bl-23 points for 12 breaths.

PRESCRIPTIONS AND HOMEWORK

It is advisable for patients to practice regulating Lung exercises with Natural Breathing to strengthen the Lungs.

PRESCRIPTION MODIFICATIONS

1. For Liver Fire attacking the Lungs, have the patient perform the Sun and Moon Rotating technique (see Chapter 41), while sounding the word "Sss" for 36 breaths, to purge the Lungs in addition to performing the Lung tonification and regulation exercises (see Chapter 42). Next, have the patient rub the hypochrondrium area and sound the word "Shu" for 36 breaths.
2. For Dry Heat scorching the Lungs, (from a Wuji posture) have the patient bring both hands up to the sternum and begin kneading the sternum down to the xiphoid process 36 times. Next, the patient places both palms on the chest with the fingers touching the sternum to allow the Qi to flow into the Lungs for 10 breaths. Finally, the patient rubs the hypochrondrium and purges the Toxic Qi from the body while exhaling and rubbing the sides of the chest, starting at the armpits, to direct the Qi to flow downward into the Lower Dantian.
3. For Qi and Yin Deficiency, it is advisable for the patient to practice Lung tonifying exercises and the Gathering the Moon Cream exercises (see Chapter 11), as well as the methods of Taking in the White Qi.

SINUSITIS

Sinusitis is described as the inflammation of the sinuses. Infections stemming from the common cold or influenza frequently cause secondary infections in the sinuses, these infections tend to become chronic. The body's frontal and maxillary sinuses are very prone to infection and inflammation.

ETIOLOGY

An invasion of pathogenic Wind Cold into the Lungs through the nose (the orifice of the Lungs) can bring about the accumulation of Heat and cause an obstruction of the Lungs' Qi. This condition further impairs the Lungs' dispersing and descending function, giving rise to sinusitis.

The excessive consumption of greasy, hot foods leads to a buildup of Phlegm and Heat toxins within the body and may predispose the patient to sinusitis. Greasy, hot foods may also lead to the formation of Damp Heat within the Stomach and Spleen, which can be transported upwards into the sinuses by way of the Stomach Channels.

Excess conditions, such as Wind Heat, Lung Heat, Stomach and Spleen Damp Heat, and Liver and Gall Bladder Fire, should all be purged from the patient's body, whereas chronic conditions caused by Spleen Deficiency should be tonified.

SYNDROMES

Sinusitis is characterized by consistent yellowish and foul smelling nasal discharge accompanied by cough, impairment of smell, and dull pain in the upper part of the cranium. The headache caused from sinusitis is located on the face and corresponds with either the frontal ethmoidal or the maxillary sinuses.

TREATMENT

1. Begin by stimulating the patient's frontal sinuses, focusing specific attention on the LI-20, GB-20, and Yintang points.

2. Then emit Qi into both of the patient's hands and wrist areas, focusing specific attention on the LI-4 and Lu-7 points.
3. Next, using either the Sword Fingers or Extended Fan Palm hand posture, emit Qi into the patient's LI-20 points. Begin using the Pushing, Pulling, and Leading manipulations to guide the patient's Toxic Qi down the Stomach Channels, purging it out through the St-36 point on each leg.

PRESCRIPTIONS AND HOMEWORK

The following prescription is used for relieving sinusitis.

The patient, from a seated posture, rubs his or her palms until the dorsal sides of each thumb are very hot. Then the patient places the thumbs on the sides of the nose and begins to gently rub up and down for 10 breaths. This exercise is called Bathing the Nose.

Next, the patient places the tips of the middle fingers on each side of the nose (LI-20), and begins kneading these points. This is followed by using circular rotations from the cheeks to the nose five times during inhalation, and then from the nose to the cheeks five times during exhalation. This part of the exercise is called Kneading the Apex of the Nose. This exercise is performed for 10 breaths.

CHAPTER 47
QI EMISSION THERAPY FOR KIDNEY DISEASES

INTRODUCTION

The Kidneys are solid (Zhong) organs that store the body's Jing. They correspond to the element Water and are sometimes referred to as the Black Emperor. The Kidneys house the Zhi, which is the will power, and they are in charge of life and reproduction. The Kidneys are also responsible for bone, brain and Marrow formation. They govern the Mingmen Fire and are the root of the Yin and Yang energies within all the organs (Figure 47.1). The Kidneys are energetically paired with the Bladder (a hollow organ).

The Kidneys are responsible for inhalation. Upon inhalation the Kidneys grasp the Lungs' Qi and hold it. This "holding" action secures the body's ability to maintain deep, slow inhalation. Therefore, when the Kidneys become weak (due to shock, trauma or disease), one of the clinical manifestations of Deficient Kidneys includes dyspnea (shortness of breath and gasping for air).

The Mingmen, or Gate of Life, is the root of the Yuan Qi, the residence of Water and Fire energy. The Yin Qi of the Five Yin Organs cannot be nourished without it, and the Yang Qi of these organs cannot be lifted without it. Kidney Qi flows to the brain. The ears (Yang orifice), anus and urethra (two Yin orifices) are the orifices of the Kidneys.

The Kidneys' upper external connection with the outside world is through the ears, hence any sound or tone resonation affects the core essence of the individual's spiritual and emotional will power.

In the winter months the Kidneys become more active in individuals who already possess strong Kidney Qi, but becomes Deficient in those with weak Kidney Qi. The excessive eating and drinking of salty foods and overexposure to cold depletes the Kidneys.

Kidney Yin energy flows to the Liver, Heart, and Lungs. It is responsible for the body's Jing



Figure 47.1. The Kidney (Kd) Channels

and produces the birth, growth, maturation, and reproduction cycle. Kidney Yang energy flows to the Spleen, Liver, Heart, and Lungs. It supports the Yang of all the body's organs via the Mingmen (Figure 47.2).

KIDNEY COMPLICATIONS AND SYMPTOMS

This section focuses on specific Kidney diseases and how to rectify them. The following discussion of treatment principles begins with an explanation of Kidney syndromes and symptoms. Several Kidney diseases have symptoms which are common to the organ's energetic dysfunction, such as mental and emotional problems, lower back pain, tiredness, and breathlessness. A list of Kidney syndromes and their symptoms are described as follows.

1. A Kidney Yang Deficiency syndrome manifests through such symptoms as headaches, breathlessness, wheezing, asthma, tiredness, mental and emotional problems, lower back pain, diarrhea, constipation, painful urination, enuresis, edema, menorrhagia and premenstrual tension.
2. A Kidney Yin Deficiency syndrome manifests through such symptoms as tiredness, chest tightness, asthma, breathlessness, mental and emotional problems, constipation, enuresis, lower back pain, bleeding, Parkinson's disease, menorrhagia and premenstrual tension.
3. A Kidney Jing Deficiency syndrome manifests through such symptoms as tinnitus, dizziness, and mental and emotional problems.

GENERAL TREATMENT FOR KIDNEY DISEASES

The following is a description of a general protocol used for treating a patient's Kidneys. The goal is to introduce the Qigong doctor to the basic hand positions and areas of the patient's body through which Qi is emitted (or Turbid Qi removed). Once the Qigong doctor becomes proficient at locating these specific points, the treatment will flow more smoothly.



Figure 47.2. Kidney Yin flows from the Kidneys to the Liver, then to the Heart and Lungs. Kidney Yang flows from the Kidneys to the Spleen, Liver, Heart and the Lungs.

After comparing the various Kidney therapies, the reader will notice that certain patterns repeat themselves.

1. Generally, the Qigong doctor accesses the patient's Kidneys through either direct energetic insertion into the Kidneys' anatomical location on the back, through the naval and Mingmen access gates, or through the patient's channels and external energetic fields (Figure 47.3).
2. After treating the patient (purging, tonifying, and regulating), the Qigong doctor will stimulate the patient's Kidneys, Mingmen, and Lower Burner areas, and roots the patient's Qi into the Lower Dantian.
3. Next, the Qigong doctor stimulates the patient's Kidneys and Lower Dantian through the Taiji Pole and Bubbling Spring (Kd-1) points, regulating the body's Yin and Yang Qi via the Microcosmic Orbit (Fire Cycle).

Keep in mind that these areas are general and that specific treatment patterns must change as they apply to the patient's exact condition (Excess, Deficient, etc.).


Energize the Kidneys through the patient's Taiji Pole.
Energize the Kidneys through the Mingmen (GV-4) point.
Energize the Kidneys through the Shenque (CV-8) point at the navel.
Regulate the Kidneys through the Sanyinjiao (Sp-6) points.
Energize the Kidneys through the Yongquan (Kd-1) points.

Figure 47.3. Treating Kidney Diseases

MEDICAL QIGONG THERAPY FOR KIDNEY QI DYSFUNCTION

Some symptoms of Kidney disease can manifest as dark circles under the eyes, decaying teeth, distended abdomen, dyspnea, and perspiration. The primary therapy used to treat Kidney diseases include: the Windy Breathing method to strengthen the Kidneys, Toe-Raised Walking, and Kidney massage (see Chapter 15).

1. An Excess Heat syndrome of the Kidneys should be treated by purging through uttering the "Chui" (Chree) sound, and reinforcing its effectiveness by focusing intent on the exhalation (Figure 47.4). This gradually relieves sluggishness and stagnation of the Kidney's Qi.
2. A Kidney Deficiency syndrome manifests mid-lower back pain at the waist level, and should be treated by Taking in the Blue Qi (see Chapter 4) into the Kidneys, Mingmen, and Lower Dantian.
3. A Deficiency of Mingmen Fire should be treated by emitting Qi into the patient's Lower Dantian and Mingmen area with the Pushing technique along with clockwise Qi rotation. This manipulation invigorates the Kidneys' Qi and replenishes the Fire of the Mingmen.


Heart
Spleen
Lungs
Kidneys
Liver
Chree

Figure 47.4. The Kidney sound is "Chui" (Chree).

KIDNEY QIGONG PRESCRIPTIONS

These exercises promote the flow of Qi and Blood of the Kidney Channels, nourish the Kidneys, strengthen Yang, and increase the Yuan Qi. These exercises can also be used to prevent and treat the following diseases and syndromes: nephritis, psychoneurosis, lumbago, rachialgia (spinal inflammation), tinnitus, deafness, frequent micturition and aversion to cold due to having a Cold condition.

PRESCRIPTIONS FOR TONIFYING THE KIDNEYS

The Taking in the Blue Qi can be used to tonify the Kidneys. The properties inherent within the color blue have a persistent vibratory rate used for tonifying the Kidneys and Bladder.

1. Assume a standing, sitting, or lying posture. Relax the whole body, place the tongue against the hard palate behind the teeth, and get rid of any stray thoughts.
2. When inhaling, visualize blue energy in front of you. Inhale the blue light energy in through the nose and down into the Kidney organs. As you exhale through the mouth, the dark, pathogenic Qi leaves the Kidneys; however, the bright clean color remains in the organ, stimulating and vitalizing it. With each breath the organ retains more clean energy and begins to glow. Repeat for five breaths.
3. Next breathe the blue color in through the nose, filling the entire mouth. When exhaling through the nose, send the blue Qi slowly down to the Kidneys, then into the Lower Dantian. Perform six to twelve times. Return to the beginning posture and close.

PRESCRIPTIONS FOR REGULATING THE KIDNEYS

Remove stagnation from the Kidneys by having the patient rub the abdomen while sounding "Chree."

Assume a sitting or standing posture. Place both palms flatly on the lower abdomen (left hand on the outside for men, opposite for women), inhale slowly, and exhale the sound "Chree" while rubbing the lower abdomen clockwise, gently with the palms. Perform ten to twenty breaths.



Figure 47.5. Rotate the waist in a clockwise and counterclockwise direction.

PRESCRIPTIONS FOR STRENGTHENING THE KIDNEYS AND CONDUCTING QI

The following exercise is used to tonify the Kidneys.

1. Assume a standing posture. Clench both hands into fists, and place them against the soft tissue on both sides of the Mingmen. Rotate the waist, turning towards the left in a clockwise direction for six rotations. After the six rotations pause in the center, then rotate in the opposite direction for six times (Figure 47.5).
2. Assume a standing or sitting posture. Rub the sides of the Mingmen with both hands, up and down thirty-six times, focusing the mind on the lumbar region (Figure 47.6).
3. Tuck the sacrum under (to stimulate the renal capsule), placing both palms on the groin, under the junction of the pubic bone (left hand on the outside for men, right for women).

Support and gently pull up the area around the perineum with both hands eighty-one times (Figure 47.7). Switch hands and repeat. Note: The Kidneys are injured by irregular



Figure 47.6. Rub the Kidney and Mingmen area.



Figure 47.7. Support the groin and perineal area.

sleep patterns, fear, excessive caffeine, sex, drugs, alcohol, and smoking. Excess saltiness and Cold (climate and food) have a draining effect on the Kidneys.

SPECIFIC MEDICAL QIGONG THERAPY FOR KIDNEY DISEASES

The following are several Medical Qigong treatments used in China to treat specific Kidney diseases.

TINNITUS AND DEAFNESS

Tinnitus is a condition of a high-pitch or rushing-wind sound within one or both ears. The sound may be a consistent pitch or vary in intensity and modulation.

ETIOLOGY

Although the ears are the opening of the Kidneys, there are other influences which must be addressed when dealing with tinnitus. Tinnitus is most commonly caused by stagnation of the Triple Burner and Gall Bladder Channels. These channel stagnations are due to three adverse conditions: the rising of Liver Wind Fire which may be induced by violent rage, the obstruction of the orifices in the head due to External Wind invasion, or by failure of the Kidney Jing to reach the ears due to a Kidney Deficiency.

This disease can be divided into Full and Empty Types of tinnitus:

1. The Full Type of tinnitus is caused by the flaring up of pathogenic Wind, Yang, Fire, Phlegm, or Phlegm Fire. It is most noted in the Excess rising of Liver and Gall Bladder Fire, or Phlegm Fire flaring upwards. This type of tinnitus is experienced as a sudden onset with a loud sound and is aggravated by cupping one's hands over one's ears.
2. The Empty Type of tinnitus is caused by a Deficiency of Kidney Qi, Kidney Jing, Lung Qi, or Heart Blood that is unable to extend to the ears. It is most noted in Kidney Jing Defi-

ciency, Deficient Upper Burner Qi and Heart Blood Deficiency. This type of tinnitus manifests clinically through a gradual onset with a low sound and is improved by cupping one's hands over one's ears.

SYMPTOMS

1. The Excess Type of tinnitus manifests as a sudden deafness or distending pain in the ears accompanied with a loud-pitched ringing noise. The adverse rising of Liver Wind Fire or Gall Bladder Wind Fire causes vexation and irritability, and often manifests as a flushed face and dry mouth.

   The Excess condition caused by an invasion of External Wind also includes symptoms such as chills, fever, and headache.
2. The Deficient Type of tinnitus can either occur constantly or intermittently, and may be aggravated by overstraining and relieved by hand pressure. This condition is often accompanied by dizziness, soreness of the waist, seminal emission, or leukorrhea.

TREATMENT

1. Begin by stimulating the patient's TB-3, TB-17, SI-19, and LI-4 points on both sides of the body.
2. Emit Qi towards the patient's Lower Dantian, using the right Sword Finger hand posture and left Extended Fan Palm hand posture.
3. Next, extend energy into the patient's affected ear and focus the Qi emission around the patient's TB-17 and TB-21 point areas. Next, guide the Qi to flow down the head, neck, shoulders, and arms along the Triple Burner Channels and out of the hand 3 to 7 times.
4. Finally, extend Qi into the patient's affected ear and guide the Qi down and out of the body along the corresponding Gall Bladder Channel ending at the corresponding foot.

MODIFICATIONS

- In cases of adverse rising of Liver Wind Fire, use the Vibrating Palm to emit Qi into the patient's Bl-18 and -19 points for 14 breaths on both sides of the body.
- In cases of Kidney Deficiency, emit Qi into the patient's Bl-23 points for 14 breaths.

PRESCRIPTIONS AND HOMEWORK

In the following three prescriptions make sure the patient heats his or her hands before beginning.

1. Have the patient perform the Beating the Heavenly Drum exercise (see Chapter 16) for 24 breaths.
2. Have the patient press the ears with the palms in a compression-release fashion 10 times each. Be sure to warn the patient to avoid forceful or violent compression. The patient's intention should focus deep within the orifice of the ears.
3. Have the patient pinch the top of the auricles of the ears gently, and massage them from the top downwards 24 times.

LUMBAGO

Lumbago is a general non-specific term for dull aching pain in the lumbar region of the back.

ETIOLOGY

Lumbago is a common symptom observed in many diseases, such as acute and chronic muscular strain of the lower back, subluxation of the discs, prolapse of the lumbar vertebra, etc. Patients may suffer from lumbago with pain radiating down to their lower limbs. Lumbago pain can also be aggravated by weather changes. Traditionally, there are three general causes of lumbago: lumbago due to Wind Cold and Dampness, lumbago due to Kidney Deficiency, and lumbago due to trauma.

1. Lumbago due to Wind Cold and Dampness, is caused by retention of Cold and Damp pathogens in the channels and collaterals. This in turn leads to the obstruction or stagnation of Qi and impairs Blood circulation.
2. Lumbago due to Kidney Deficiency is caused by an over consumption of the Kidney Jing due to an overactive sex life. This results in the failure of the Kidneys to nourish the Triple Burner Channels.
3. Lumbago due to trauma occurs from an injury to the tissues and muscles (e.g., dislocated vertebra, fractures, ruptured spinal disks, etc.), and leads to stagnation of Qi and Blood. Qi and Blood stagnation leads to obstructions in the channels and collaterals.

SYMPTOMS

1. Lumbago, due to Wind Cold and Dampness, is manifested by heaviness and pain at the waist, which may radiate to the hips and down the legs, or may be accompanied by muscular stiffness. In chronic cases, the pain is intermittent with various degrees of severity. On wet and cold days the patient often feels cold at the waist and lumbar area.
2. Lumbago, due to Kidney Deficiency, is manifested by continuous, dull pain, accompanied by soreness and weakness of the waist and knees, cold limbs and nocturnal emission.
3. Lumbago due to trauma is manifested by localized pain along with tenderness and limited mobility.

TREATMENT

1. Place the patient in a sitting position on the table. Begin stimulating the patient's Mingmen area with your left hand while the right hand guides the energy down to the patient's Bl-40 points behind the knees.
2. Using the Extended Fan Palm hand manipulation emit Qi into the patient's Mingmen and Bl-18 areas, guiding the Qi to flow along the Bladder Channels down the legs.
3. Next, place the patient in a supine posture, knees pointing upwards and feet flat on the table. Position yourself over the patient allowing the weight of your chest to support and compress the physical structure of the patient's knees, lower legs and feet. Embrace the patient's hips and imagine separating the inner fascia and tissues. The purpose for this compression is to initiate a strong internal stretching action within the tendons and smaller muscles of the patient's lower back and sacral area. This technique is used to disperse stagnant Qi and Blood within the patient's lumbar vertebra, sacrum and femur articulations. At the same time, direct the Qi upwards along the patient's spine and Governing Vessel. Hold this compression for several minutes.
4. To avoid respiratory congestion (while your weight is stretching the patient's sacrum and lower lumbar), the patient is instructed to raise the arms above the head.
5. As the patient experiences the lower back compression, he or she imagines the stagnant energy (trapped within the lumbar area) melting like ice into water and flowing through the Microcosmic Orbit (Fire Cycle). With each exhalation the patient relaxes to a deeper level, imagining him or herself sinking deeper into the table.

TREATMENT MODIFICATIONS

1. For lumbago due to Wind Cold and Dampness, purge the pathogenic Qi out of the patient's body first, and then emit Heat into the channel points associated with the specific location of the patient's pain.
2. For lumbago due to Kidney Deficiency, use a Vibrating Palm technique to emit Qi towards the patient's Mingmen, Bl-23 and Bl-18 points for 14 breaths each point on both sides of the body.
3. For lumbago due to trauma, extend Qi for 28 breaths into any Ah Shi point (painful tissue area).

INSOMNIA

Insomnia is described as a sleeping disorder that disrupts the patient's normal sleeping pattern. In mild cases, the patient may have difficulty falling asleep or remaining asleep (waking numerous times during the night). In severe cases the patient may be unable to fall asleep at all. Diseases with insomnia as part of their manifestation include anxiety disorders and menopausal syndrome.

ETIOLOGY

The amount and quality of sleep depends on the state of the patient's Shen, which is rooted in the Heart (specifically, the Heart Blood and Heart Yin). If the Heart is agitated or Deficient, the Shen cannot root, and sleep will be affected. Any disharmony of the body's internal organs due to an Excess or Deficient condition affects the patient's Jing and Blood. Since the Jing and Blood root the Shen, the Shen will have no residence and insomnia may result.

Insomnia can be caused by insufficient Blood due to impairment of the Spleen Qi, or from malnourishment of the Heart Qi due to a Deficiency of Heart Blood. This condition can also result from overfatigue, anxiety or irritability. This may be due to a disharmony between the Heart and Kidneys (resulting from Deficient Kidneys), irritability (due to mental depression) or from disharmony between the energetic function of the Stomach and Spleen (resulting from an improper diet).

Since the Hun (rooted in the Liver Blood or Liver Yin) play an important role in the length and quality of sleep, Liver Blood Deficiency can cause the Hun to be deprived of their residence and to wander at night causing restless sleep.

SYMPTOMS

The main symptom is an inability to sleep, which based on the different conditions of this illness can be further classified as:

- An inability to get to sleep,
- Sleepwalking, and an
- inability to fall asleep after waking.

The symptoms vary with the causes of the disease.

1. Insomnia due to a Deficiency of the Heart and Spleen (resulting from severe worry) may cause shallow sleep, or dream disturbed sleep. It is manifested by palpitations, poor memory, vertigo, dizziness and spontaneous sweating.
2. Insomnia due to Kidney Deficiency (resulting from excessive sexual activity) is manifested by dizziness, tinnitus, soreness in the loins and back area, as well as involuntary seminal emission.
3. Insomnia due to upward stirring of Liver Yang is manifested by pain and distention of the chest and epigastrium, belching, and acid regurgitation, as well as mental hyperirritability, dizziness and headaches.

TREATMENT

1. Begin by having the patient sit at the edge of the table. Your right hand emits Qi into the patient's CV-12 point, directing the energy to flow down into the patient's Lower Dantian. The left hand extends energy into the patient's mid-back around the area of the patient's Bl-18, Bl-19, Bl-20 and Bl-21 points, and leads the Qi down the Bladder Channels to the feet on both sides.
2. Next, use the Vibrating Palm technique to extend energy into the patient's Baihui, GV-14, Mingmen, CV-12 and Lower Dantian areas for 9 to 18 breaths each.
3. Emit Qi into the patient's Baihui area and leads the Qi from the top of the patient's head down the Conception Vessel into the Lower Dantian.
4. Finally, emit Qi into the patient's GB-8 point by the top of the ears and guide the Qi down the patient's Stomach Channels to the St-36 points.

TREATMENT MODIFICATIONS

1. For treatment of insomnia due to Deficiency of Heart and Spleen, emit Qi into the patient's Bl-20 and Bl-15 points, guiding the Qi down along the Bladder Channels to the feet.
2. For insomnia due to Kidney Deficiency emit Qi into the patient's Mingmen and Bl-23 points for 18 respirations.
3. For insomnia due to emotional depression, emit Qi towards the patient's Lv-3 and Lv-4 points (on both sides of the body), guiding the Qi down to the patient's lower extremities along the Liver and Gall Bladder Channels.
4. For insomnia due to Spleen and Stomach disharmony, use the Vibrating Palm hand technique to emit Qi into the patient's CV-12, St-36, and St-21 points on both sides of the body.

PRESCRIPTIONS AND HOMEWORK

For the best results, have the patient practice Medical Qigong prescriptions one to two hours before going to bed. For chronically ill patients, the causes of the insomnia should be removed first, followed by Medical Qigong prescriptions and regular physical exercise for lasting therapeutic results.

Have the patient perform the Kidney Massage for treating insomnia prescribed in Chapter 39.

PYELONEPHRITIS

Pyelonephritis is an infectious disease caused by bacteria invading the renal parenchyma and renal pelvis unilaterally or bilaterally. It clinically manifests through the following symptoms: fever, lumbago and abnormal discharge of urine.

SYNDROMES

1. Damp Heat in the Bladder is clinically manifested through symptoms such as frequent and painful urination, fever, distention and pain in the lower abdomen, lumbago and aversion to cold.
2. Stagnation of Liver and Gall Bladder Heat is clinically manifested through symptoms such as fever with or without chills, nausea, loss of appetite, lumbago or pain in the lower abdomen, frequent urination with cloudy urine and feeling agitated.
3. Spleen and Kidney Deficiency with Heat stasis is clinically manifested through such symptoms as edema of the face, swelling of the feet, abdominal distention, thin stools and frequent urination, lassitude and weakness in the entire body (especially the legs), dizziness, tinnitus and anorexia (lack of appetite).

TREATMENT

1. Have the patient sit at the edge of the table and begin stimulating the Mingmen and Lower Dantian areas using a Vibrating Palm technique for 11 to 22 breaths.
2. Next, have the patient lay supine on the table and stimulate the patient's Sp-6 and Kd-3 areas on both sides of the body.
3. Use the Extended Fan Palm hand technique to emit Qi into the patient's Lower Dantian, guiding it down the Kidney Channels to the bottom of the feet.

TREATMENT MODIFICATIONS

1. When treating patients with Damp Heat in the Bladder, use a Sword Fingers hand posture and apply the Vibrating technique, emitting Qi into the patient's Mingmen and Lower Dantian for 14 to 28 breaths.
2. When treating patients with stagnant Heat in the Liver and Gall Bladder, use the Extended Fan Palm hand posture to emit Qi into the patient's mid-back and Liver, purging Toxic Qi down the Liver and Gall Bladder Channels and out of the body via the legs.
3. When treating patients with Deficient Spleen and Kidneys, use the Extended Fan Palm hand posture to emit Qi into the patient's mid-back Bl-20, and Bl-23 points, CV-12 and Lower Dantian areas.

PRESCRIPTIONS AND HOMEWORK

Have the patients practice the Standing Post Posture with arms suspended at the Middle Dantian, and the mind's intention focused on the Lower Dantian. Use natural abdominal breathing (see Chapter 16).

PRESCRIPTION MODIFICATIONS

1. For patients with Damp Heat in the Bladder, have them practice rubbing the costal area and sounding "Who."
2. For patients with stagnant Liver and Gall Bladder Heat, have them practice massaging the costal area and sounding the word "Shu."
3. For patients with Spleen and Kidney Deficiency, have them practice the method of Taking in Yellow Qi, as well as the Gathering the Moon Cream exercise (see Chapter 11).

IMPOTENCE

Impotence is a weakness and inability of the male to achieve or maintain an erection. Symptoms vary from premature ejaculation to partial penile erection (the penis is erect but not hard, resulting in the incapability of sexual intercourse), to a complete failure to achieve any erection at all. Impotence indicates a weakness in all Five Yin Organ energies. The combined energies must be sufficient to culminate an erection, as described below.

1. The Heart energy quality is strongly affected by the nature of the sexual encounter. Casual sex may not involve the highest spiritual energy of the Heart's upper chamber (see Chapter 5), only the basic instincts and drives of the lower chamber. The Heart may also be affected by the individual's moral values and beliefs, as well as the quantity and quality of emotional passion (i.e., with or without guilty feelings) at the time of arousal. Heart energy also pertains to the energy of the Blood.
2. The Spleen energy pertains to what the man

is thinking and his intention at the time of arousal. This also affects the man's muscles.

3. The Liver energy pertains to visual stimulation that affects a man's sexual drive. This affects the man's strength. Many aspects of man's sexuality are relate to the Liver's functions, i.e., visual images evoking emotions, Blood filling the erectile tissue, and the power of desire.
4. The Kidney's Qi pertains to the Jing energy stored within the Marrow, and relates to the man's will power and endurance. It is associated with audible stimulation and affects the man's endurance.
5. The Lung Qi is man's somatic expression of sexual passion and is stimulated through touch and smell. This energy also affects the man's endurance.

ETIOLOGY

There are two main factors ascribed to impotence: psychogenic and organic. In the first case, the patient's physical, mental, emotional, and spiritual energies are out of harmony. This can be caused by fear, excitement, performance anxiety, etc. In the second case, impotence can be caused by medications, drugs, alcohol, etc. In most organic cases, however, impotence is caused by prostate failure, cardiovascular disease or diabetes. If this condition persists long enough the man looses sexual interest and the condition becomes psychosomatic.

SYNDROMES

- Insufficiency of Kidney Yang is clinically manifested through symptoms such as impotence, lumbago, weakness in the knees, dizziness, tinnitus, aversion to cold, cold limbs and a cold sensation in the external genitalia, listlessness and shortness of breath.
- The downward flow of Damp Heat is clinically manifested through such symptoms as impotence, itching and pain around the external genitalia and scanty, dark urine.

TREATMENT

1. Stimulate the patient's Mingmen and Lower Dantian areas using the Vibrating Palm technique for 12 breaths.
2. Next, stimulate the patient's Sp-6 areas on each leg, leading the Qi up into the Lower Dantian for 12 breaths.
3. Finally, return back to the Mingmen and Lower Dantian areas using the Extended Fan Palm hand technique. Emit Qi for 24 breaths, rotating in a clockwise direction to gather the Qi in the Lower Dantian.

TREATMENT MODIFICATIONS

- When treating a patient with an insufficiency of Kidney Yang, vibrate the energy using the Sword Fingers Hand technique, while emitting Qi into the Lower Dantian for 16 to 18 breaths.
- When treating a patient with a condition of Damp Heat flowing downward, purge the Qi along the Kidney Channels down into the Lower Dantian. Use the Extended Fan Palm hand technique and emit Qi into the patient's Lower Dantian, Kd-13 and Kd-14 points on both sides of the body, as well as the navel area, for 24 breaths.

PRESCRIPTIONS AND HOMEWORK

It is advisable to have the patient perform the Deer exercise, prescribed for increasing the body's Jing.

1. Have the patient sit on the edge of the chair, rubbing the palms to create heat. This right hand will cup his testicles so that the palm completely covers them with slight pressure. The left hand is placed on the area of the Lower Dantian just below the navel. The left hand moves in a circular clockwise direction 81 times. Next, the hands are rubbed together again, reversing the hand positions so that the left hand cups the testicles and the right hand is on the Lower Dantian. The circle rubbing is repeated in the opposite direction 81 times. Concentrate on the heat and Qi filling up the Lower Dantian and genital area.
2. The patient should tighten and draw up the anal muscle while inhaling, feeling the Qi being drawn up the rectum and prostate area, filling up the Lower Dantian. He should hold the breath as long as possible, then exhale, release and relax. The anal contraction exer-

cise should be repeated beginning with 25 breaths, and eventually working up to 250 breaths.

PRESCRIPTION MODIFICATIONS

1. When treating patients with Kidney Yang Deficiency, it is advisable to have them practice Beating and Drumming the Qi with lower abdominal breathing (see Chapter 42).
2. When treating patients with a downward flow of Damp Heat, it is advisable to have the patient rub the Lower Dantian and sound the healing tones "Chree" for 36 breaths and "Shu" for 36 breaths.

CHAPTER 48
QI EMISSION THERAPY FOR MISCELLANEOUS DISEASES

INTRODUCTION

This chapter deals with miscellaneous diseases that are classified as either complicated multiple diseases, or energetic conditions which have not yet been classified. This section describes the conditions, symptoms and treatment for these syndromes. The discussion of these various treatments begins with energetic dysfunctions stemming from the Qi of the Three Dantians, and expands further to include other tissues, internal organ and energetic organ system complications.

DEFICIENT DANTIAN QI

One of the most common problems found in the body's energetic system is Deficient Dantian Qi. The symptoms vary according to the location of the Deficiency, as well as the patient's constitution.

1. If the energy is Deficient within the Lower Dantian, the symptoms and syndromes cover a large range that includes: chronic diarrhea, asthma due to Kidney Deficiency, hypertension due to Yin Deficiency, Blood Deficiency, insomnia, spermatorrhea, collapsing syndrome due to Deficiency, abandoned-type Wind Stroke, abandoned-type coma and all types of organ prolapse.
2. If the energy is Deficient within the Middle Dantian, the problems may include shortness of breath, bronchitis, asthma, chest pain, palpitations, intercostal neuralgia, all breast disorders including acute mastitis and breast abscesses.
3. If the energy is Deficient within the Upper Dantian, the problems may include frontal headaches, dizziness, vomiting, fainting due to Blood loss, insomnia, eye soreness, febrile convulsions and insanity.

PRESCRIPTIONS FOR REGULATING THE THREE DANTIANS

The following meditations are prescriptions used to regulate the heat, vibration, and light in the Lower, Middle, and Upper Dantians.

1. The Lower Dantian meditation solidifies the Qi in the Lower Dantian that allows for stable energy transference to take place. The purpose for Heat Regulation in the Lower Dantian is to cause the internal organs to steam; this transfers energy from organ to organ to nurture and regulate the body's Qi.

   Have the patient focus on breathing into the center of the Lower Dantian. Upon inhaling, the patient imagines drawing Qi into the body from the nose, urethra and anus, and directs it into the Lower Dantian. After inhaling, the patient closes the lower orifices and circulates the Qi up through the coccyx and Mingmen area, then down into the navel and into the Lower Dantian. It is important that the patient visualize a ball of energy rotating in the lower abdomen like a spinning wheel. As this Qi begins to collect in the Lower Dantian, heat and vibration begin to resonate in the lower abdominal area.
2. The Middle Dantian meditation expands the patient's Wei Qi, which in turn enhances the body's protection against an attack of Hot or Cold pathogenic factors. The patient should draw the Toxic Qi out of the Yang Channels of the arms, through the center point of the palms. This is an excellent meditation for treating diseases caused from Excess Heat, such as insomnia, headaches, hypertension, and arthritis of the joints:

   To regulate the heat of the Heart Fire and Middle Dantian area, the patient focuses the breath and mind's intention on the center of the chest (CV-17) while placing the right thumb inside the heart of the left palm (Pc-8), while resting both hands on the lap.

3. The Upper Dantian meditation not only expands the patient's Wei Qi, but also fills the body with sound and light vibration. Sound and vibration are used in the Qigong clinic to purge Toxic Qi out of the patient's body. This is an excellent meditation for balancing and energizing all Three Dantians.

   The patient begins in a standing or sitting Wuji posture, with the spine straight, Mingmen pressed back, anal sphincter closed, tongue on upper palate, and breathing naturally. This particular exercise follows the opening and closing pattern of Qi regulation. The focus is placed on each Dantian area for a period of 18 to 24 breaths. Each Dantian area needs a specific sound and light visualization to open, purge, close, and regulate its energy. The sounds and physical actions are as follows.

- To open, energize and regulate the Upper Dantian, use the sound of "Om." The arms separate and come together above the Baihui area (above the head) in order to open and close the Upper Dantian. The focus of the mind's intention is placed on drawing in divine healing light while inhaling, to fill the Taiji Pole. When exhaling, imagine the energy rushing into the Upper Dantian while toning the first vowel sound "O." Then imagine light shinning outside of the body while sounding the consonant sound "m." On the beginning of the vowel sound, the tongue is placed on the lower palate. As the tone and breath reach its midpoint, the tongue rises to connect with the upper palate to finish the sound "Om."
- To open, energize and regulate the Middle Dantian use the sound of "Ha." The arms separate and come together above the chest at the CV-17 point while opening and closing the Middle Dantian. The focus of the mind's intention is placed on drawing in divine healing light while inhaling, to fill the Taiji Pole. When exhaling the tone "Ha", separate the arms and imagine that the Qi rushes into the Middle Dantian and then expands to shine outside of the body. On the beginning of the tone "Ha," the tongue should be placed on the lower palate. As the tone and breath reach its midpoint, the tongue maintains its connection to the lower palate.
- To open, energize and regulate the Lower Dantian use the sound of "Hai-riem." The arms separate and come together above the lower abdomen at the CV-8 point while opening and closing the Lower Dantian. The focus of mind's intention is placed on drawing in divine healing light while inhaling, to fill the Taiji Pole. When exhaling, imagine the Qi rushing into the Lower Dantian with the first syllable "Hai," then shines outside of the body when the syllable "reim" is pronounced. At the beginning, the tongue is placed on the lower palate to pronounce the sound "Hai." As the tone and breath reach its midpoint, the tongue changes its position to behind the teeth to tone the sound "reim."

All three sounds are used to activate and energize the body's Three Dantians by practicing these sounds in the following two step progression:

1. Upon inhalation, focus the mind's intention on drawing divine healing light into the body to fill the Taiji Pole.
2. While exhaling, sound the specific tone of each Dantian, while both hands perform the opening (the expanding movements of the arms and hands) and closing (the contracting movements of the arms and hands) technique at each Dantian. The mind visualizes the light resonating and shining out from the body at each Dantian during the toning.

IMPROPER YIN AND YANG ENERGY BALANCE

Another common problem observed in the clinic is an imbalance of Yin and Yang Qi within the patient's body. Converting and balancing the Yin and Yang energy diverts the Qi before it has a chance to overload the body's system. The Qigong doctor first removes any obstruction in the patient's Governing Vessel and then harmonizes the patient's Yin and Yang energy by extending Qi into the patient's back, on the GV-13 and -14 points.

The following meditations are used as prescriptions to develop a strong electrical charge in the body, that balances the Yin and Yang currents:

Have the patient place the thumb in the heart of his or her palm (Pc-8), fingers touching the back (dorsal) side of the hand, opposite the (Pc-8) point (Figure 45.1). To energize the Lower Dantian the patient concentrates on his or her lower abdominal area. To energize the Middle Dantian the patient should concentrate on the area at center of the chest. The only difference between the Lower Dantian exercise and the meditation used to heat the Middle Dantian is the focal point of the patient's concentration. In these particular exercises, the hand postures are the same, however, the mind is focused on either the hands near the Lower Dantian, or on the middle of the chest.

- For men to develop a stronger electropositive Yang energy field, the right hand should cover the top and center of the left hand. To develop a stronger electronegative Yin energy field, the left hand should cover the top and center of their right hand.
- For women to develop a stronger electropositive Yang energy field, the left hand should cover the top and center of the right hand. To develop a stronger electronegative Yin energy field, the right hand should cover the top and center of the left hand.

Note: In generating energy within each Dantian area it is important to understand basic Yin and Yang polarities and their relationship to male and female. The female chest is considered Yang while the female genital area is considered Yin. The female Middle Dantian (or Heart area) is the focal point of female Yang (positive) energy; the genital area is the focal point of female Yin (negative) energy. Conversely, the male chest is considered Yin while the male genital area is considered Yang. The Middle Dantian (or Heart area) is the focal point of male Yin (negative) energy; the genital area is the focal point of male Yang (positive) energy (see Chapter 5).

DISORDERS OF THE QI

Whenever energy movement is impeded, disorders in Qi functions occur. Generally, these disturbances cause either disorders of Fire, or disorders of Water (see Chapter 22).

The cause and progression to these disorders can be further broken down and classified according to their energetic dysfunction. There are several types of Qi disorders observed in the clinic and they are generally described as follows.

LEAKAGE AND LOSS OF QI

During or after training practice, the patient may feel that Qi is continuously and uncontrollably leaking out of the body from the genitalia and anus or somewhere else on the body. This loss of Qi can lead to Qi Deficiencies and manifest through the following symptoms: emaciation, weakness of the limbs, grayish and dull complexion, nervousness, mental disturbances, distractibility, failing memory, spontaneous sweating, night sweats, seminal emission, insomnia, lassitude and sluggishness.

To treat this condition apply the Extended Fan Palm technique, use the Pushing, Pulling, and Shaking manipulations to emit Qi into the Mingmen; then use Vibrating and Shaking manipulations to emit Qi into the Lower Dantian.

QI STAGNATION DISORDERS

Qi stagnation exists when the Qi becomes sluggish when moving within the body's channels, organs, or tissues. Qi stagnation can be caused by many different factors such as suppressed emotions, trauma, contraction of microorganisms, poor diet, and weak digestion. Qi stagnation, over time, results in localized pain, distention, cysts, tumors, etc. Qi stagnation disorders have two subcategories: Qi and Blood Stasis, and Obstructed Qi (see Chapter 22).

1. Qi and Blood Stasis refers to the sensation of local pain, heaviness, soreness, distention, and compression, which are caused by the stagnant Qi and Blood in certain areas of the body. These sensations do not resolve by themselves. This stasis may occur during or after

Medical Qigong training practice from Qi disorders and visceral malfunctions.
2. Obstructed Qi is also considered a subcategory of Qi stagnation, and exists when the Qi becomes so stagnant that it no longer flows. At this stage the Qi can't move the Blood. This can be caused by trauma, surgery, and acute Qi stagnation.

Reconstructive Qi therapy, for conditions of Qi stagnation use the following two methods:

1. Select corresponding channel points in the region of the Qi and Blood stasis. Knead the selected channel points, then push and rub along the obstructed channel.
2. Finish the treatment by applying the Extended Fan Palm technique; use the Pushing, Pulling and Shaking manipulations to emit and conduct Qi along the channels to open them.

REBELLIOUS QI DISORDERS

Rebellious Qi disorders manifest as Qi flowing in the wrong direction (a direction different from its normal physiological progression); this causes a disturbance within the harmonious flow of energy and affects the organ functions. The symptoms have to be analyzed according to the internal organ which is involved. There are two types of Rebellious Qi, the Excess type and the Deficient type. Rebellious Qi is categorized as follows.

DISORDERS OF EXCESS REBELLIOUS QI

Disorders of Excess Rebellious Qi occur when the vital Qi increases and forces the pathogenic Qi to move. This causes local sensations of pain, soreness, distention, heaviness, coldness or hotness which can develop during Qigong practice. To treat for conditions of Rebellious Qi, use the following two methods:

1. From the head and torso, follow the routes of the channels and collaterals out to the extremities. Pinch and lightly pull on the extremities (fingers and toes). Then press, knead, push and rub the location of the discomfort, guiding and leading the Qi along the channels away from the area of discomfort.
2. Apply the Extended Fan Palm method; use the Pulling and Leading manipulation to pull and guide the Qi, or open up the channel points to disperse the Qi.

DISORDERS OF DEFICIENT REBELLIOUS QI

Disorders of Deficient Rebellious Qi refer to the disorderly flow of Qi and Blood during or after training practice, which can cause dizziness, fright, a heavy feeling in the chest, shortness of breath, shaking limbs, trembling of the hands and feet or fainting. Generally, energy sensitive practitioners know the location and direction of the disorderly flow of Qi in their tissues.

To treat conditions of Deficient Rebellious Qi use the following two methods:

1. Open the appropriate channel points to regulate the functional activities of the Eight Extraordinary Vessels.
2. Select appropriate regions and channel points and apply the Extended Fan Palm or Sword Fingers technique. Use Pushing, Pulling, and Shaking manipulations to activate the channel Qi of that particular channel or region. Then, use the Leading manipulation to direct the Qi into specific channels or return it to the Lower Dantian.

ARTHRITIS

Arthritis is defined as inflammation of the joints, usually accompanied by pain, swelling and frequently changes in structure. This is a chronic, multiple arthropathy and can be divided into the peripheral type (pertaining to the four limbs), and the central type (pertaining to the spinal column, i.e., rheumatoid arthritis or ankylosing spondylitis).

ETIOLOGY

Arthritis is caused by pathogenic Wind, Cold and Dampness attacking the body's channels and hindering the Qi and Blood circulation. This invasion can give rise to pain, soreness, heaviness, and numbness of the tendons and muscles, as well as swelling and difficulty in moving the joints. This condition can be caused from an unstable lifestyle weakening the body's Wei Qi, overexposure to a draft after sweating, wading in water, exposure to cold weather, or laying on a damp ground for long periods of time.

SYMPTOMS

Arthritis is clinically manifested primarily as arthralgia and dysfunction of the joints and can be accompanied by muscle spasm, loss of muscle tone, loss of muscle mass and deformity. Symptoms can be divided into early and late stages.

- In the early stages of arthralgia, the local swelling usually starts from the small joints of the fingers and toes, wrists and ankles, or from the iliosacral joint and spreads upward into the body. Several weeks or months later, the patient may feel local tenderness and inflexibility of the joints with some clicking or cracking sounds. In this stage the pain is worse at night and early in the morning, and may be alleviated with gentle exercise. In the early stages of arthritis, the patient's condition can be controlled and even restored back to normal through Medical Qigong prescriptions.
- In the later stages of arthritis, the articulation of the joint movement is markedly limited, and patients may experience deformity in the joints, as well as stiffness, muscular atrophy and paralysis. The phalangeal and carpal joints of the patient's hands may become rigid and deviate to the ulnar side of the arm. The fingers may also become deformed with restricted mobility, and the elbow and shoulder joints may also be affected. In the late stages of arthritis, the treatment can only control the progression of the disease and alleviate local symptoms. The patient's locomotive function can only be gradually improved.

If the patient's lower limbs are affected, the ankle, knee and hip joints may become rigid, and he or she may experience motor impairment. If arthritis occurs in the patient's spinal column, it may cause kyphotic deformity and dyspnea, as well as restriction in neck movement. At this stage a sudden backward flexing of the neck may cause sudden death in patients with rigid forward bending neck deformity.

When treating an External invasion of pathogenic factors, the Qigong doctor observes three main symptoms of arthritis:

1. Wind or migratory arhtralgia is manifested by pain that has no particular fixed location, but moves throughout the body's extremities and joints, and is sometimes accompanied by chills and fever.
2. Cold arthralgia is manifested by localized pain of the joints, which may be relieved by heat and aggravated by cold.
3. Damp arthralgia is manifested by fixed pain and swelling in the joints and extremities, or by numbness of the skin which may be aggravated in cloudy and rainy weather.

TREATMENTS

1. Place the patient in the standing posture and begin dredging the Governing Vessel, drawing the energy into the ground.
2. Use the Extended Fan Palm hand technique and begin to emit Qi into the patient's GV-14, Mingmen, and Lower Dantian areas.
3. While emitting Qi into the painful joint areas, purge the pathogenic energy out of the patient's body, leading the Toxic Qi along the channels and out of the extremities.

PRESCRIPTIONS AND HOMEWORK

In treating arthritis it is important to prescribe exercises which lubricate the joint articulations to increase the production of Qi and Blood to the extremities. The Daoist Five Yin and Yang Organ exercises will accomplish this goal quite easily.

The patients are required to perform Qigong prescriptions which improve the body's resistance, but do not cause fatigue. Patients should also improve their diet and should be encouraged to consult a nutritionist for natural supplements that can help rebuild healthy cartilage and reduce pain. They should also make every effort to keep their body warm.

For patients with osteoporosis, stretching techniques, as well as sudden forward flexing of the neck are absolutely prohibited.

PRESCRIPTION MODIFICATIONS

1. When treating patients who suffer from arthritic pain in the upper limbs, advise them to practice shoulder and arm Dynamic Medical Qigong, moving at a slow, fluid pace.
2. When treating patients who suffer from ar-

thritic pain in the lower extremities, advise them to practice Dynamic Walking Medical Qigong (see Chapter 15), moving at a slow, fluid pace.
3. When treating patients who suffer from arthritic pain in the waist and lower back, advise them to practice the Expanding and Contracting the Rings exercise (see Chapter 41).
4. When treating patients who suffer from arthritic pain in the neck, advise them to practice slow-moving non-forceful neck rotation exercises in conjunction with stationary neck massage.

VERTIGO

Vertigo is a syndrome manifested mainly by dizziness and dim eyesight. It is defined as a sensation of moving around in space or having objects move about the person as a result of a disturbance of equilibrium. Vertigo is sometimes used as a synonym for dizziness, feeling light headed, or giddy.

Patients with mild vertigo may experience relief from this condition after a short bed rest, with their eyes closed. In severe cases, patients may suffer from a serious rotary vertigo and will not be able to stand or walk straight (e.g., sea and air sickness), sometimes followed by nausea, vomiting, perspiration, or even syncope (fainting).

Diseases that have vertigo as their main manifestation include cerebral arteriosclerosis, auditory vertigo, hypertension, anemia, and psychosomatic illnesses such as hyperventilation (which often accompanies anxiety disorders, especially panic disorders). These diseases may be diagnosed, categorized, and treated with reference to the prescriptions described in this section.

ETIOLOGY

Several factors contribute to the vertigo syndrome. In ancient times, Chinese physicians believed that vertigo was caused by Yin Deficiency and Excess Liver Wind, or by a head trauma. In Excess conditions, vertigo is caused by Phlegm Fire or Wind Phlegm. Currently, the clinical protocol for treating vertigo is divided into three conditions:

1. Hyperactive Liver Yang causing an insufficiency of Kidney Yin,
2. A Deficiency of Qi and Blood in the Heart and Spleen causing a Deficiency in the Marrow reservoir, and
3. Stagnation of Phlegm Dampness caused by a Deficiency of Spleen and Stomach Qi (which fail to transport the Phlegm).

Vertigo may be caused by a variety of factors affecting the ear, the eighth cranial nerve, and the brain stem; including middle ear disease, infectious diseases, trauma, tumors, toxemia due to food poisoning, hypertension, sun stroke, and toxic conditions such as those caused by alcohol and drugs. Over medication and malnutrition (especially in the elderly who suffer from dehydration) also cause vertigo.

SYMPTOMS

1. In cases where the patient has hyperactive Liver Yang, the syndrome of vertigo is characterized by severe dizziness, splitting headache, blurred vision, nausea, soreness and weakness of the waist and legs, mental fatigue (caused by emotional upset and anger), flushed face, constipation and tinnitus.
2. In cases of Qi and Blood Deficiency, the symptoms include rotary vertigo, blurred vision or night blindness, listlessness, disinclination to talk, palpitations, insomnia and anorexia.
3. In cases of stagnation of Phlegm Dampness, the symptoms include chest pain and distress, nausea and vomiting, poor appetite, listlessness of the body and heaviness in the head.

TREATMENT

When treating patients with vertigo, begin with the upper body working downward and from the medial aspect of the body towards the lateral part of the body.

1. Begin with the patient sitting on the edge of the table. Stimulate the patient's Baihui, the sides of the head, (GB-4, GB-8, and Taiyang areas), GV-14, Shendao, Mingmen, and the Lower Dantian.
2. Next, use the Vibrating Palm hand manipulation to emit Qi into the patient's Baihui, GV-14, Yellow Court and Lower Dantian for 12 to 24 breaths.

3. Use the Extended Fan Palm hand technique to emit energy into the patient's St-8, St-21 and St-36 points on both sides of the body.
4. With the left palm, emit Qi into the patient's Baihui point while using the right hand Sword Fingers to guide the patient's Qi from the Yellow Court down the Conception Vessel into the Lower Dantian.
5. Next, direct the Qi from the patient's St-8 points down to the St-36 points via the Stomach Channels.
6. Purge the energy of the upper torso out through the hands via the Large Intestine Channels.
7. Finally, lightly pat and knead the patient's Baihui and GV-14, softly rocking their upper limbs to end the treatment. Softly pressing and kneading the patient's tissues along their channels can push Qi and Blood downward to free the patient's mind from Toxic Qi and can improve the eyesight. The soft grasping can relieve stasis of Qi and Blood in the patient's blood vessels and promote circulation, thus reducing and relieving vertigo.

TREATMENT MODIFICATIONS

1. In cases of hyperactive Liver Yang, use the Extended Fan Palm hand method to emit Qi into the patient's Bl-18, Mingmen, and Lower Dantian. Guide the Qi to flow along the channels (or in a clockwise direction) to nourish the patient's Yin and to suppress the hyperactive Yang.
2. In cases of Deficient Qi and Blood, use the Extended Fan Palm hand method to emit Qi into the patient's mid-back (Bl-17, Bl-18, and Bl-20 points) and Lower Dantian to nourish the patient's Qi and to replenish the Blood.
3. In cases of stagnation of Phlegm Dampness, use the Extended Fan Palm hand method to emit Qi into the patient's Yellow Court. Guide the Toxic Qi down the Stomach Channels and expel the pathogens out from the patient's St-36 points.

PRESCRIPTIONS AND HOMEWORK

To treat vertigo, have the patient practice the Descend the Qi and Cleanse the Organs exercise (see Chapter 41).

PRESCRIPTION MODIFICATIONS

When treating patient's who suffer from a Deficiency of Kidney Yin and a hyperactivity of Liver Yang, prescribe the following meditation. Have the patient take a standing or sitting posture, breathing naturally, and relaxing. While inhaling through the nose, the patient imagines blue energy filling the mouth. When exhaling, the patient imagines this dark blue energy slowly pouring down the throat, like warm water, filling the Kidneys and Lower Dantian area. The patient should practice this meditation for 7 breaths.

HEADACHES

A headache is defined as a diffused pain in different portions of the head which is not confined to any one nerve distribution area. It may be acute, chronic, frontal, temporal, occipital, confined to one side of the head, or affect the region immediately over one or both eyes. The character of the pain may vary from dull and aching, to acute stabbing pain that is almost unbearable. There may be intermittent, intense pain, a throbbing pain, a pressure in the head which feels as if it will burst the head, or a penetrating pain driving through the head.

ETIOLOGY

Transient, acute headaches may vary in their etiology. Disease of the perinasal sinuses, teeth, eyes, ears, nose or throat, acute infections, invasion of Wind Cold pathogens into the channels of the head, or trauma to the head are among the most frequent causes of headaches.

Chronic headaches may also be caused by a variety of conditions including physical, emotional, psychosomatic, or psychogenic factors, including fevers, metabolic conditions (hypertension, etc.), or even exposure to toxic chemicals.

SYNDROMES

Headache syndromes can be divided into five categories which are described as follows.

1. A Shaoyang headache (migraine) is clinically manifested through symptoms such as a severe headache (splitting pain) in the temple region accompanied by Excess Heat in the

head, conjunctive congestion, and sometimes intercostal fullness or pain. Nausea often accompanies a severe migraine attack.

2. A Taiyang headache (occipitocervical headache) is clinically manifested through such symptoms as a headache and pain in the back of the head which can be accompanied by fever, aversion to cold, and rigidity at the back of the neck.
3. A Jueyin headache (vertical ache) is clinically manifested through such symptoms as a vertex headache, vertigo, insomnia, dizziness, and irritability with a flushed face.
4. A Yangming headache (frontal ache) is clinically manifested through such symptoms as a headache in the upper part of the cranium accompanied by dysphoria (depression and anxiety) with a smothering sensation, thirst, bad breath and constipation.
5. A Deficient Qi and Blood headache is clinically manifested through such symptoms as a lingering headache with a heavy sensation in the head, blurred vision, lassitude, and weakness.

TREATMENT

Begin by purging and dredging the patient's Upper Dantian, focusing on the Yintang, Taiyang, Baihui, GV-16, GV-20, and GB-4 points. Purge the pathogenic Qi down the patient's arms and out the LI-11 and LI-4 points, as well as down the Gall Bladder Channel out of the GB-41 points. The point and channel purging is specific to the location (right or left side) of the headache.

Next, using the Extended Fan Palm hand technique, emit Qi into the patient's headache region, purging it down the Conception Vessel to the Lower Dantian.

TREATMENT MODIFICATIONS

1. When treating a patient with a Shaoyang headache, apply the Extended Fan Palm hand technique to emit Qi into the GB-4, GB-8, and TB-20 points, leading the pathogenic Qi out of the Triple Burners and Gall Bladder Channels.
2. When treating a patient with a Taiyang headache, apply the Extended Fan Palm hand technique to emit Qi into the LI-11 and Bl-10 points, Purging pathogenic Qi down the Large Intestine and Bladder Channels and out of the hands and feet.
3. When treating a patient with a Jueyin headache, start at the head using the Circle Spiraling hand technique in a counterclockwise direction, purging the Toxic Qi out the patient's Gall Bladder Channels and out of the legs.
4. When treating a patient with a Yangming headache, use the Extended Fan Palm hand technique to emit Qi into the patient's Taiyang, Yintang, and St-8 points, purging the Toxic Qi down the Stomach Channels and out of the legs.
5. When treating patients with Deficient Qi and Blood, use the Extended Fan Palm hand technique to emit Qi into the patient's mid-back, at the Bl-17 and Bl-20 points, and the chest at the CV-17 point. Then emit Qi into the patient's CV-12 and Lower Dantian areas.

PRESCRIPTIONS AND HOMEWORK

1. It is advisable to have the patient practice the Ten Dragons Run Through the Forest exercise found in the Wash the Face and Massage section of Chapter 39.
2. It is beneficial to prescribe the following meditation to prevent the advancement of an acute attack. The main focus of this meditation is to direct Blood, Heat, and Qi to the body's upper extremities (the arms and hands), away from the original source of pain (i.e., the head).
    a. From a sitting, semi-reclining, or lying posture, the patient begins to relax and quiet the mind, with the eyes closed.
    b. The patient imagines that it is summertime and he or she is at the beach. Next, the patient focuses on both arms and hands, imagining them growing warmer and warmer in the hot sun. The patient imagines feeling massive amounts of heat radiating from the arms and hands, redirecting the Blood flow away from the head.
    c. Then, the patient imagines the face becoming cooler, as the pressure and pain

melts down the neck, shoulders, arms, forearms and out of the hands.

Prescription Modifications

1. For patients with a Shaoyang headache, focus the prescription meditations and exercises on treatments that purge the bilateral sides of the patient's head along the Triple Burners and Gall Bladder Channels, dredging the pathogenic Qi down and out of the patient's arms and legs.
2. For patients with a Taiyang headache, focus the prescription meditations and exercises on treatments that purge the patient's occiput and cranium, the Small Intestine and Bladder Channels, and that dredge the pathogenic Qi down and out of the patient's arms and legs.
3. For patients with a Jueyin headache, focus the meditations and exercises on treatments that purge the patient's vertex cranium, dredging the Toxic Qi down the Liver Channels and out of the legs.
4. For patients with a Yangming headache, focus the prescription meditations and exercises on treatments that purge and dredge the energy from the patient's forehead down the Large Intestine and Stomach Channels and out of the legs.
5. For patients with a Deficient Qi and Blood headache, focus the prescription on Lower Dantian Cultivation exercises and meditations.

MIGRAINE HEADACHES

This type of headache initially consists of a constriction in the head arteries, followed by vasodilation of the extracerebral cranial arteries.

ETIOLOGY

Migraine headaches are usually brought about by stress, and can also be initiated by an allergic reaction to what the patient's body considers to be a toxic invasion (e.g., cheese, chocolate, red wine, contraceptive pills, etc.). These types of stresses on the body's system result in internal organ dysfunction, which is generally caused by one or more of the following three factors.

1. The energy of the Heart and Spleen are not regulated.
2. A rising up of Liver Heat and Fire occurs.
3. A Deficiency of Kidney Yin and rising of Heart Fire occurs simultaneously.

The result of stress-related internal organ dysfunctions causes the initial constriction of the arteries in the head, followed by vasodilatation and distention of the vessels.

SYMPTOMS

The clinical manifestations of migraine headaches are hypersensitivity to light and sound, followed by severe, throbbing pain (most commonly felt on only one side of the head), nausea, dizziness, and sometimes vomiting. Some migraine patients experience seeing an aura or visual disturbances (colors, shapes, lines, flashing spots, or temporary reduction in the field of vision) before the head pain begins.

TREATMENT

For treatment, the Qigong doctor must pull the pathogenic energy out of the patient's head, from the location of the pain; then lead the Excess Toxic Qi out of the patient's extremities, and open up the channels so that Qi can rise and fall to the patient's head unobstructed.

1. In a severe case, combine Medical Qigong therapy with Jing Point therapy.
   a. Begin the treatment by pulling out (with strong intention) the stagnant Qi trapped in the patient's head. First, purge the patient's Wei Qi field, then enter the patient's Jade Pillow at the base of the head. Next, emit Qi along the falx cerebri and circulate it using your intention to create a small Microcosmic Orbit (circling from the back of the head to the nose and back). This encourages the patient's stagnant Qi to move.
   b. Next, dredge around the area of the patient's eye (from the inner corner of the eye to the side of the eye), starting at the Bl-1 point to the Yin Tang point (Third Eye), following the sphenoid arch across to the temple at the Taiyang point, then to the back of the ear at the

TB-17 point. Next, lead the pathogenic Qi down the neck and pull out the stagnant Qi through the extremities (Pc-6 and LI-4 on the hand). If the patient is feeling nausea, purge the Toxic Qi from the Yellow Court and lead the Toxic Qi down and out the body through the St-36 point on the leg and Lv-3 point on the foot.

c. To remove sluggish Qi stagnation, squeeze the patient's trapezius muscles, draining the pathogenic Qi out of the axillary fold of the patient's arm. The patient should breathe into the painful areas, and imagine any remaining Toxic Qi descending down the arm into the fingertips when exhaling. The doctor should squeeze the patient's arm as the patient exhales, to support the descending action of the Toxic Qi.

d. The patient should be given homework, depending on his or her constitution.

2. In treating chronic migraine headaches, combine Medical Qigong therapy with An Mo therapy, working from the branch to the root.

   a. Begin the treatment by pulling out the stagnant Qi trapped in the patient's head. This is done by first purging the patient's Wei Qi field, then entering the patient's Jade Pillow (at the base of the head) to purge and remove Toxic Qi and stagnation. Then emit and guide the Qi with your intention, to flow along the patient's falx cerebri. This forms a small Microcosmic Orbit (circling from the back of the head to the nose and back) and encourages the patient's stagnant Qi to move.

   b. Extend Qi into the patient's Bl-1 point (on the inside of the eye).

   c. Next, focus energy into the patient's Yin Tang point and begin circulating the Qi along the orbicularis oculi muscle of whichever eye is in pain (along the eyebrows to the ear). Work from the inside of the eye, out along the eyebrows (Figure 48.1).

   d. After several rotations, follow the sphenoid arch to the back of the ear at the TB-17 point (if the pain is bilateral, for men treat the left side first; for women treat the right side first).

   e. Next, beginning at the TB-21 point, outline the outside of the ear, then massage the lateral aspect of the ear's ridge (upper auricle) (Figure 48.2).

   f. Hold both of the patient's ears firmly and begin to apply slight pressure at a 45 degree angle towards the sides of the patient's head. This allows the Qi trapped within the patient's head to escape. Using intention, move the Qi from the Jade Pillow (along the tentorium cerebelli) into the patient's pituitary gland. Then divide the energy into two rivers of Qi that circulate through the middle of the cerebrum and end back at the Jade Pillow.



Figure 48.1. For treating chronic migraine conditions (which dominate behind the left eye), begin by extending Qi into the patient's Bl-1 point and start to dredge the Toxic Qi from the patient's Yin Tang area, circulating the orbicularis oculi muscle of the eye in a clockwise direction.



Figure 48.2. Outline the outside of the patient's ear, then massage the lateral aspect of the ear's ridge.

g. From the front of the head, at the edge of the hair, gather the Qi and lightly scratch the patient's head, as you use the Kneading Tiger technique. Visualize pulling the Toxic Qi down the front and sides of the patient's head (down the Gall Bladder Channels) to the base of his or her neck (Figure 48.3).
h. From the base of the neck, pull the Toxic Qi down and out of the arms.
i. The patient should be given seated Quiescent Qigong meditation homework, the length of meditation time will depend on his or her constitution.

Note: When treating migraine headaches, the head should always be treated first before treating the extremities.



Figure 48.3. Using the Kneading Tiger technique, visualize pulling the pathogenic Qi out of the patient's head, down the side of the neck and down along the sides of his or her arm.

SECTION XI

SPECIALIZED QI EMISSION THERAPY FOR PEDIATRICS, GERIATRICS, GYNECOLOGY, NEUROLOGY, PSYCHOLOGY, ONCOLOGY, AND SURGERY

INTRODUCTION

In this section we will explore disease treatment techniques and prescriptions unique to Medical Qigong doctors who specialize in Pediatrics, Geriatrics, Gynecology, Neurology and Oncology.

The last two chapters will address Medical Qigong therapy and the treatment of radiation, chemotherapy, and surgery.

CHAPTER 49
QI EMISSION THERAPY FOR PEDIATRICS

INTRODUCTION

Pediatrics is the branch of medicine which deals with the care of children and the treatment of childhood diseases.

From a traditional Chinese medical perspective, children are different than adults in several important ways. First, the Yin and Yang energy in children is fresh and pure, and their vitality usually flourishes. Second, although the internal organs of children have begun to take shape, the organs are still in the process of developing Qi; the organs are still maturing and are not yet fully developed. Because children are still growing organs and tissues, stimulating the channels and channel points has a different effect on their body than on an adult.

Specifically, the Lungs, Spleen, and Kidneys are especially delicate in children. The Lungs and Spleen are weak, and the Kidneys are particularly vulnerable. The Lungs control the Qi of the whole body. The Spleen is responsible for the transformation of food and the transportation of Gu Qi (food Qi). The Lungs and Spleen are the postnatal foundation of health. The Kidneys are in charge of the bones and Marrow and are the prenatal foundation of health. Children are still full of Prenatal Qi; they are just beginning to use their Lungs and Spleen for the function of acquiring Postnatal Qi. Consequently, their energetic system is vulnerable and unstable.

If children are born without congenital defects or weakness, are nursed properly, and avoid contracting major diseases, the internal organs should develop normally. However, because of inherent weakness or immaturity of the digestive system, almost all pediatric diseases of children under the age of six usually begin with some element of indigestion. A child's tiny digestive system makes him or her prone to the creation of Phlegm. Since the Spleen is the root of Phlegm production, and the Lungs are the storehouse of Phlegm, then a congenitally weak Spleen can lead to the creation of Turbid Dampness within the child's body. This Turbid Dampness can congeal into Phlegm and lodge within the child's Lungs. These symptoms can be observed in young children as runny noses, ear infections, phlegmy coughs, and other respiratory difficulties.

EARLY STAGES OF CHILD GROWTH AND DEVELOPMENT

In childhood, growth and development occur rapidly. In the ancient Chinese medical classic entitled *"Prescriptions Worth a Thousand Gold Ducats"* it states, "A newborn is feeble and tender; two months later, its pupils begin to become well developed, it can smile and distinguish parents from strangers; 150 days later, its sacral bones have been well developed, it can sit independently; 210 days later, its metacarpal bones have been well developed, it can crawl; 300 days later, its patellae have been well developed, it can stand alone; at one full year of life, its shank and occipital bones have been well developed, it can walk and speak."

In the natural course of childhood growth and development, there may be fever, irregular pulse signs, or perspiration due to the imbalances of Yin and Yang. The child usually recovers spontaneously within a day or two. Such episodes are called Changing and Steaming. Changing implies the transformation of the Five Yin Organs, with the accompanying variations of emotions, and the development of the child's intelligence. Steaming implies the vaporous exchanges within the six Yang organs induced by accumulated Heat. The ancient Chinese discovered that there is one Changing every 32 days, and one Steaming every 64 days. Thus, within 320 days, there are 10

Changings, and within 576 days, there are 9 Steamings. Every Changing or Steaming is an ordinary event in the course of growth and development, and should not be mistaken for a condition of childhood disease. However, if children are not cared for properly during Changing and Steaming, they are more apt to fall ill.

PATHOLOGY

In *"Detailed Analysis of Epidemic Febrile Diseases,"* Dr. Wu Tang stated that children's diseases are apt to change because the internal organs are frail and their defense mechanisms are incomplete; children contract infections easily because the skin and muscles are still tender, and the vitality is timid and weak. Propensity to illness, inclination to Excess and Deficiency, and being prone to suffer from Heat and Cold syndromes are common features of pediatric pathology. Since children are full of pure Yang, the course of disease is changeable and unpredictable. Nevertheless, recovery of health is generally easy.

DEFICIENT LUNGS

Children are apt to suffer from internal organ disorders, especially of the Lungs, manifested by symptoms of cough, dyspnea, retention of Phlegm and Dampness in the Lungs, seasonal febrile diseases, allergies, asthma, and other Lung disorders.

The Lung is a delicate organ in charge of the skin and hair. Therefore, particularly in children, junctures between the skin and muscles are not compact enough to resist the invasion of Exogenous Cold, Heat, Dampness, Wind, and other pathogens. Seasonal pathogens may attack the Lungs through these slackened junctures and through the nose, thereby interfering with the descending and dispersing functions of the Lungs. This results in the accumulation of Heat, fullness in the chest, productive cough, or dyspnea.

DEFICIENT SPLEEN

Since the Spleen is not yet matured and thus usually Deficient, it may be harmed or damaged due to improper diet, irregularity of meals, or imbalances caused by excessively Hot or Cold diets. Consequently, Clear Yang fails to rise, Turbid Yin fails to descend, and Stomach Qi becomes disharmonious. Therefore, children frequently suffer from abdominal masses, abdominal pain and distension (stomachache), belching, hiccups, vomiting and diarrhea, infantile malnutrition, and other digestive disorders. These conditions often lead to children becoming hypersensitive to the foods they consume.

According to Five Elements theory, the Spleen (Earth) generates the Lungs (Metal) and the Lungs (Metal) generate the Kidneys (Water). The elements work in coordination and influence each other. In children suffering from Spleen Deficiency, there will also be a Deficiency of Lung Qi; in children suffering from Lung Deficiency, there will also be a Kidney Deficiency.

DEFICIENT KIDNEYS

Kidney problems can manifest in two different ways: Kidney Jing Deficiency, which can cause retardation, or Congenital Qi Deficiency (i.e., Deficiency in the Sea of Marrow), which can lead to Down's Syndrome, Attention Deficit Disorder (ADD) and learning disabilities. Since the Kidneys control the lower orifices, Deficient Kidney Qi can also lead to chronic bed wetting.

If the child was improperly nursed when they were young, the Deficient Kidney Yin not only fails to nourish the bones and Marrow, but also fails to nourish tendons. During depletion of Liver and Kidney Yin, there can be atrophy, weakness of tendons, five types of developmental retardation, as well as five kinds of flaccidity.

LIVER YANG EXCESS

By contrast, Liver Yang is usually Excessive, and Liver Wind may be brought on by Heat or Fire, resulting in infantile convulsions, twisting, and even opisthotonos.

HEART (SHEN) IMBALANCE

The Heart is responsible for the child's mental stability. The Heart Fire and the Kidney Water must constantly be balanced to stabilize the child's Wu Jing Shen. An imbalance of the Heart can lead to Shen disturbances which can result in mental instability or disability.

According to the active energetic balance of the child's Wu Jing Shen, the Hun tend to naturally be overactive, and the Shen of the Heart is generally unstable. The reason for this instability is because the Hun are very active within a child. The Hun are responsible for creativity, enthusiasm, dreaming, going in and out of the body, and seeing into the Spirit world. The Shen, which is responsible for the child's discriminating mind, respect and conveying the appropriate behavior, is not fully developed. Consequently, young children tend to often be wild, hard to control, and get easily bored.

In treating a child's overactive Hun and unstable Shen, the Qigong doctor harmonizes the child's Heart Fire and Kidney Water energy, and opens the Heart's orifices (using Qi massage on the child's eyes, ears, nose, mouth and all upper sensory orifices) to stabilize the Wu Jing Shen.

HOT AND COLD EXOGENOUS FACTORS

Susceptibility to Exogenous Cold and Heat reflects the characteristics of puerile Yin and Yang. When children are invaded by Exogenous Evils, for example, there will be Excess Heat syndromes; when the child's healthy energies are depleted, there will be Deficiency Cold syndromes.

Although various defects and Deficiencies do exist in children, their Yang, Liver, and Heart are in a hyperfunctional state. Therefore, children are full of vitality and their anti-pathogenic responses are sensitive and immediate. The causes of childhood diseases are usually comparatively simple, relative to adults, and their convalescence is easier and quicker provided they receive appropriate treatment and care.

THERAPY

Because the internal organs of children are still forming and are, therefore, still frail and tender, children are much more sensitive than adults, and cannot stand strong energetic stimulation. This is why the primary modality for treating young children is gentle pediatric Tui Na, which is usually on the child's hands, feet or abdomen, or Qigong massage (lightly touching the child's body). Acupuncture is used only infrequently, and when it is, the needles are usually not retained for long - the points are quickly and lightly stimulated and then the needles are removed. Similarly, when using Medical Qigong emission therapy, a milder stimulation is applied than would be used for adults when purging, tonifying, and regulating.

Medical Qigong is useful for treating pediatric neurological disorders, and particularly for such conditions as epilepsy, hyperactivity, attention deficit disorder (ADD), and mental retardation. Effective points for tonification include Tianzhu (Bl-10), Sishencong (four extra points, located around the Baihui area at the top of the head), Baihui (GV-20), Yamen (GV-15) and Fengfu (GV-16).

When children under the age of six practice self-regulation Medical Qigong exercises (such as Qigong to increase intelligence), they frequently develop special abilities. These abilities include ESP (e.g., telepathy and telekinesis), and special Qigong healing abilities.

ENERGETIC MOVEMENT AND FLOW

The child's Microcosmic Orbit naturally flows in the direction of the Water cycle, moving up the front (CV) and down the back (GV) in order to facilitate the child's spiritual, intuitive, and psychic perceptions. This energetic movement continues in this direction until the child reaches puberty, at which time the energy reverses its direction and flows up the back (GV) and down the front (CV), in the direction of the Fire cycle. This energetic switch in direction facilitates the child's cognitive development and the ability to control emotions and impulses. The time of the Microcosmic Orbit's energetic reversal varies depending on the child's physical constitution, state of health, and his or her environment.

MEDICAL QIGONG EXERCISE PRESCRIPTIONS FOR CHILDREN

The following Medical Qigong exercise is considered a basic training method for children. This exercise is specifically developed for children of all ages and physical conditions, and is used to improve a child's physical and mental health, as well as aid in curing some common childhood diseases. This exercise can also help to cure food allergies, loss of appetite, malnourishment, a weak immune system, neurasthenia, insomnia, dreaminess, and disturbances of the Spleen and Stomach. It is believed that this exercise also helps moderate a child's stubbornness and impatience.

IMPROVING INTELLECTUAL FACILITIES QIGONG (DA-ZHI-GONG)

This particular Medical Qigong exercise is excellent for children who range from 3 to 12 years old. The time and frequency of the following Qigong exercise is not fixed. It is important, however, that the child be consistent with the practice, and that the body and mind remain relaxed while training.

It is important that the child practice the entire Qigong sequence in its proper order. The child is not allowed to practice only a part of the exercise.

Prohibited from this particular exercise are children who have weak constitutions (i.e., have difficulty in standing up) or suffer from serious diseases.

1. Begin by having the child assume a standing Wuji posture. Have him or her relax the body, with the eyes either open or closed. The child then raises both hands in front of the Upper Dantian. Boys will place the left hand facing the forehead, about three inches from the Yintang point. Girls will place the right hand facing the forehead, about three inches from the Yintang point. At the same time the opposite hand should be level with the other palm and should be facing outwards (Figure 49.1).
2. Both hands begin to make a clockwise circle rotation (from the child's point of view). The child keeps the Yin Tang point as the center of the circle, for 18 breaths. Next, the child moves both hands to the front of the right eye and continues the same clockwise movement while keeping the right eye at the center of the circle. Rotate for 18 breaths. Then, the child moves both hands to the front of the left eye and continue the clockwise movement for 18 breaths. Finally, the child returns to the front of the forehead and continues the rotation, keeping the Yintang point as the center for 18 breaths, then



Figure 49.1. Improving Intellectual Facilities (1)



Figure 49.2. Improving Intellectual Facilities (2)



Figure 49.3. Improving Intellectual Facilities (3)



Figure 49.4. Improving Intellectual Facilities (4)

ends the meditation (Figure 49.2).

3. The child places both hands in front of the ears, with the center of the palms facing the external opening of the ear canals; breathing naturally, the child moves both hands forward and backwards while emitting Qi into the ears. Make sure the child does not concentrate on any specific thing, but simply relaxes (Figure 49.3).
4. Next, the middle fingers softly touch the navel with the left hand, and the right hand softly touches the Mingmen. Have the child imagine that there is a big red ball of fire in his or her abdomen (where the child's two middle fingers are pointing). The child's fingers should remain is this position until warmth is felt in the abdomen. If the heat becomes too hot, have the child exhale the sound "Ha" three times to release the Excess Heat (Figure 49.4).
5. To end the exercise, have the child cover his or her tailbone with both hands and jump up and down gently for several minutes. Do not allow the child to become tired from jumping. Again, make sure that the child does not concentrate on any specific thing (Figure 49.5).



Figure 49.5. Improving Intellectual Facilities (5)



Figure 49.6. Gathering Wisdom Qigong (1)



Figure 49.7. Gathering Wisdom Qigong (2)

MEDICAL QIGONG FOR GAINING WISDOM QIGONG (TONG-LING-GONG)

This particular Medical Qigong exercise is excellent for children who range from 3 to 16 years of age. The time and frequency of this particular Qigong exercise is not fixed, and may be decided by the child. Also, there are no contraindications for this particular Qigong exercise.

1. The child begins by standing with his or her feet flat, shoulders width apart. The child should place one hand on the Lower Dantian (below the navel) and the other hand at the back, below the Mingmen (opposite the Lower Dantian). Have the child close his or her eyes and relax the body and mind for about three minutes. The child is to imagine that the upper part of the body (above the waist) is extended into the blue sky above, and that below it (around waist level) are clouds (Figure 49.6).
2. Next, the child imagines that he or she has changed into an Immortal (a Super-Hero). Encourage the child's imagination to flow freely with this concept, allowing the child to move about, gently shaking the knees (Figure 49.7). After several minutes end the meditation.

CHAPTER 50
QI EMISSION THERAPY FOR GERIATRICS

Geriatrics is a branch of medicine which deals with the problems of the aging. Geriatric specialists addresses the physiological, pathological, psychological, economic, and sociological problems of the elderly. The importance of geriatrics is emphasized by the fact that the expected life-span of the average person is increasing.

Diseases of the internal organs can spread throughout the body via the channels and collaterals, and vice versa, as channel diseases can be transmitted to the internal organs. If Qi and Blood lose their harmony due to old age, and the patient's internal organs, channels, and collaterals become obstructed, then Phlegm and Stasis will develop internally. The accumulation of Phlegm, Qi and Blood stasis may lead to a chain reaction of pathological transformations, such as Hot, Cold, Excess or Deficiency Syndromes in the patient's internal organs. The following are examples of some of the pathological transformations.

1. If the patient's Qi and Blood in the Liver lose their harmony, the patient may experience fatigue and depression with dry eyes or diminished vision. The patient may also experience numbness in the extremities and muscle spasms due to a weakening of the sinews and blood vessels.
2. If the patient's Qi and Blood in the Heart lose their harmony, the patient may experience poor memory, insomnia, heart palpitations, and shortness of breath (which may be aggravated by movement).
3. If the patient's Qi and Blood in the Spleen lose their harmony, the patient may experience fatigue and general weakness in all four limbs. The patient may also experience loose or bloody stools, and there will be abdominal distention after food consumption.
4. If the patient's Qi and Blood in the Lungs lose their harmony, the patient may experience coughing with Phlegm and panting, as well as spontaneous sweating.
5. If the patient's Qi and Blood in the Kidneys lose their harmony, the patient may experience poor memory, anxiety, tinnitus or deafness, as well as a sore or weak lower back, knees, and teeth.

The Chinese have a saying, "When the Heaven (Heart Qi) connects with the Earth (Kidney Qi), all seven emotions are kept in moderation." When Qi becomes scattered the Heart Fire and the Kidney Water cannot converge. This results in an unbalanced and unstable energy flow.

The Kidneys are extremely important for health maintenance and healing in all patients, and especially in senior citizens. As one gets older, the Kidneys, lower back, and legs are the first things to be affected.

It is important to stabilize the Heart because the Heart is responsible for mental and emotional orientation. Traditional Chinese Medicine holds that, "when the Heart is moved, all the other organs will be shaken."

In teaching Medical Qigong to senior citizens, first quiet the Heart, so that the other organs can begin to relax. When the mind becomes disturbed, the body becomes disturbed. To affect one is to affect the other.

The eyes are considered the seedlings of the Heart as they receive information, gathering it and feeding it to the brain. It is important for the Heart's Qi to descend into the Lower Dantian to calm the mind. When the patient is in a hurry, the Heart is in a hurry, thus inducing the Qi to rise to the head. This results in nervous tension and anxiety. It is only through rest and quiet training that the mind and the Heart can begin to settle.

One method of quieting the mind is through prayer and meditation. This is considered "active rest." Sleep is considered "passive rest." When focusing inward and not using the eyes to see or the ears to hear, the Qi begins to converge in the middle of the body and the energy is drawn back into the organs, settling down into the Lower Dantian. This convergence of Qi nourishes and cultivates the natural energetic structure of the internal organs. Senior citizens are encouraged to sit for longer periods of energy cultivation. If they practice Taijiquan they are to avoid low postures and big motions. The arm movements should be kept small, soft, and slow.

TREATING THE PATIENT'S EMOTIONAL STABILITY

When treating the elderly, the Qigong doctor bases the regulation therapy prescriptions on two major priorities. The first is to achieve emotional stability and the second is to improve the Qi and Blood circulation.

The first priority in working with healing prescriptions is to focus on the patient's psychological profile. When teaching Medical Qigong to senior citizens, first teach them how to quiet the Heart. Once the Heart is calm the other internal organs begin to relax. Always keep in mind that when the mind becomes disturbed, the body becomes disturbed. To affect one is to affect the other.

Depression and sadness can have a profound effect on the patient's healing ability. Medical Qigong regulation can be a strong aid in releasing an elderly patient from a chronic, detrimental attitude that complicates the healing cycle. Take for example the three stages of emotional transition the patient endures before his or her Spirit closes (see Chapter 18).

If anger and grief are not allowed to be expressed by the patient (which is the first stage of energetic expression and release of emotional pain), then anger transforms into depression, and grief transforms into despair. This is the second stage of the energetic/emotional transformation due to emotional pain. If the patient's depression and despair are not alleviated, then indifference, the final stage of energetic/emotional transformation, is developed. The patient becomes withdrawn, apathetic and either antisocial, or obsessive/compulsive in his or her thinking and behavior.

When the patient's Spirit closes, they tend to be extremely difficult to work with, and can easily sabotage their own healing potential. Though the use of Soul Retrieval meditations (see Chapter 19), Medical Qigong prescriptions can be used to reconnect the patient with their disassociated emotions. This allows the patient the ability to feel and regain contact with his or her true feelings.

Pleasant emotions bring about a calm and relaxing physiology, while strong, chronic negative emotions cause Qi and Blood stagnation, as well as Excess conditions within the patient's body, effecting the quality of the body's life force energy.

ENERGIZING THE PATIENT'S QI CIRCULATION

The second priority is to get the patient to move and circulate the Qi and Blood deep and superficially within his or her body. Static Blood is considered the primary mechanism of senility. All growth, development, decline, and debility of the human body, is related to the condition of the patient's Qi and Blood.

Pathophysiologically, both Qi and Blood affect each other; if one becomes diseased, the other is affected. Due to the Kidney's influence, as seniors get older, their hearing, hair, memory, lower back, and legs become adversely affected. Traditionally, all senility-combating formulas of Medical Qigong stress treating the patient's Spleen and Kidney Deficiency by supplementing the patient's Yin and/or Yang. Then, by applying the balancing methods of activating the patient's Blood and rectifying the Qi, the doctor can also combat the patient's senility.

Senility is also frequently caused by dehydration and malnutrition. Both conditions are frequently overlooked by Western medicine. The dehydration is usually due to a breakdown of the body's thirst signal. The patient does not feel thirsty, and thus forgets to drink. Malnutrition may be caused by a lack of enzymes that aid in absorbing nutrition from foods. Overmedication likewise can cause senility. These issues should always be addressed when treating the elderly, along with Medical Qigong exercises and meditations.

One example of a Medical Qigong exercise for aiding Qi and Blood circulation for geriatric patients is the Microcosmic Orbit (Fire Cycle) which can be practiced in a sitting position.

The elderly are more subject to musculoskeletal disorders and visceral diseases, especially in the Kidneys and Liver. As the Kidney Yang rises, it begins to restrict the heat in the upper portion of the body, thereby affecting the Heart. Also, as the patient gets older the Lungs cannot sustain liquid retention; this affects the Wei Qi, and results in a thinner layer of skin covering the body.

The Qigong movements prescribed for the elderly should be kept slow and smooth. Qi regulation can be cultivated safely by focusing the patient's intention on the center of the palms while keeping the mind's intention moving downward. The patient must not exert strain when using the muscles. When the patient turns his or her body, make sure that the center of each palm (Pc-8) faces the other. Slow and even breathing will calm the patient's emotions and sedate the mind.

It is important to begin Medical Qigong regulation training for senior citizens with natural breathing. Natural breathing allows their respiration to become soft, natural, gentle and quiet. The focus of the mind should be on relaxation. In dealing with senior citizens, if the focus of their mind's intention is allowed to become too concentrated, it can cause the Qi in their body to constrict and develop into Qi or Blood stagnation. Redirect their focus of intention on their breathing by practicing the Small Heavenly Cycle meditation. The Small Heavenly Cycle meditation is used to regulate the body's Yin and Yang energy and to strengthen the patient's mind and spirit. The Large Heavenly Cycle meditation can be prescribed to increase the patient's Qi and Blood circulation, to rejuvenate the body and the sense organs, to clear the complexion, and to improve mobility.

TAPPING THE KNEES TO PREVENT SENILITY

One exercise prescription that the doctor can use to assist the patient in combating senility is to have the patient lightly tap above, below, and around his or her knees. This exercise stimulates the Kidneys' energy and can also be used as an important adjunct to maintaining health for senior citizens, especially when combined with the foot tapping (Kd-1) Kidney Tonification exercise (see Chapter 39). Combined, both of these exercises can help to strengthen the patient's Kidneys, lower back, and legs. When combining both exercise prescriptions, the Knee Tapping exercise should follow after the Kidney Tonification exercises.

To begin the Knee Tapping exercise, have the patient sit in a chair, with both knees lower then the thighs. Encourage the patient to direct the focus of his or her attention in and around the knee area. As the patient taps or softly slaps the tissue surrounding the knees, he or she should imagine the energy and vibration flowing into the Lower Dantian. After several minutes (about 36 breaths) the patient can stop.

CULTIVATING THE PATIENT'S YUAN QI BY ABSORBING ENERGY FROM NATURE

Another priority of focus for older patients is the gathering, storing and cultivation of his or her Yuan Qi. In China, in order to tonify the Yuan Qi, elderly patients practice their Qi Tonification and Regulation Exercises facing a cypress tree daily (a cypress tree is considered very powerful and full of energy). If a cypress tree is not available, then the patient can use a pine or oak tree. This exercise prescription is considered a slow and gentle Dynamic cultivation. Any Dynamic exercise for senior citizens should always be practiced slowly, and gently, in order to replenish the Yuan Qi during the Static Qigong posture (in this case, standing).

The flexion and extension of the muscles relates to the interaction of Yin and Yang within the body's energetic tissues and muscles. This flexion and extension of the muscles becomes the foundation of energy balance. Relaxation of the body results in soft, gentle movement, peacefulness and tranquillity. Muscular rigidity, on the other hand, results in hardness, restlessness and disease.

In order to practice Medical Qigong exercises, senior citizens are encouraged to keep their body's energy connected with the energy of the Earth. This connection is obtained via their energetic attachment through the bottom of their feet and the center of their palms. If the patients are confined to wheelchairs, or are bedridden, they can still focus the mind's intention on the Lower Dantian, and then extend their energy deep into the Earth.

As with all Medical Qigong prescriptions, the patients must first purge and cleanse their body before gathering, collecting, tonifying and regulating the body's energy. To purge the body of Toxic Qi, the patients imagine divine healing energy pouring down from the Heavens, filling the entire body, as they inhale. This vibrant healing energy is absorbed into their tissues and the Toxic Qi stored within the patient's body is dispersed into the Earth.

As the patients exhale, they imagine the Toxic Qi melting out their tissues and flowing downward, deep into the ground. The patients perform this purging and dispersing sequence for several breaths until they feel cleansed. Next, the patients begin to fill and regulate their body.

To fill and regulate the body, the patients imagine circulating the energy downward, deep into the Earth, and into the root system of a tree.

Next, the patients imagine the Earth's energy ascending up through the top of the tree, blending with the energy of Heaven, and then descending through their head, filling their entire body from the feet upward like water being poured into a glass and filling it up (Figure 50.1).

The inhalation and exhalation should follow the Natural Abdominal Breathing method, and the mind's intention should be focused on filling, gathering and circulating the universal and environmental Qi.



Figure 50.1. Extend Qi and Intention deep into the root system of the tree and absorb its natural energy through the Baihui point at the top of the head.

FURTHER OBSERVATIONS AND INSIGHTS ON GERIATRIC PATIENTS

According to Mark Johnson (an expert who has been treating "Seniors" with Medical Qigong Therapy and Taijiquan since 1987), any encouragement to undertake new experiences is very cathartic for older patients. Getting involved in anything creative seems to prolong the quality of their life.

Understanding the physical and emotional transitions that geriatric patients undergo in their every day life helps the Qigong doctor establish a better awareness of the patient's energetic dynamics. These physical and emotional transitions can best be understood when realizing the internal and external conflicts senior patients must constantly address.

COMPANIONSHIP

Many people tend to lose meaning in their life when they retire, lose a spouse, witness the death of countless friends, or when their children move away. Patients who lose their life purpose (or their meaning of life) usually do not live long. Elderly patients, who have lost their friends, usually have an extremely strong emotional attachment to any pet they may own. If the pet dies, this is usually as devastating as the loss of a close family member.

According to clinical observation, most older patients who become involved in spirituality, social service or voluntary work tend to be the most fulfilled and therefore most healthy. Humor and laughter as a means of internal emotional medicine for older patients cannot be overemphasized. Socializing with an understanding yet active support group also tends to bring healing to their heart.

In addressing the issue of being lonely, it has been found that the healing quality of having a pet to love can be very helpful for seniors who have become solitary or isolated.

OVERMEDICATING

Too many older patients are overly medicated. Taking up to ten pills a day is not unusual for many seniors. In a book initiated by Ralph Nader, titled "Worst Pills, Best Pills" the author emphasizes the fact that if an older person is taking over three different drugs, they are taking too many and should consult their doctor with the expressed purpose of cutting down to a maximum of only three types of medication.

The drugs given to seniors are usually tested on 30 year old individuals who are generally much stronger than most 70 year olds. Therefore half dosages are usually considered safer. In addition, there is a minimum of thirty-three drugs on the market today that can give the symptoms of Parkinson's disease. Several healers have gotten their patients off Parkinson's medication after demonstrating the fact that one of their other medications initiated the patient's symptoms.

SEDENTARY LIFE-STYLE

Too many older patients are sedentary, especially men. It is generally agreed that people living today move only 35% as much as people living 100 years ago. This has got to have a major impact on one's health, especially on older people whose circulation is not what it once was. Our bodies are designed to move; to become sedentary violates one of our basic needs. The studies conducted at Emory College confirm that the safest and most beneficial exercises for seniors is Medical Qigong, Taijiquan, walking, mild aerobics and light weight training. Seniors are encouraged to stay away from running.

IMPROPER DIET

Because of the patient's age and changing metabolic needs, diet is as equally important for seniors as exercise. Proper nutrition can be used to augment the benefits from the patient's prescriptions, as well as to increase the patient's healing potential. The diet in senior housing communities is usually atrocious. Sugar, canned vegetables and too many heavy meats are the norm. When prescribing Medical Qigong exercises for seniors, the Qigong doctor must also take into consideration the patient's diet and fluid intake, making sure that it is not sabotaging the healing effect of the Qigong prescriptions.

SLEEP DEPRIVATION

As patients gets older, their Kidney Jing becomes weak, their hair begins to turn grey, the hearing and sight becomes affected, the bone structure, mental comprehension and sleeping patterns also undergo changes. These physical transitions can and do affect the patient's emotional outlook on life. This however, is all part of the natural course of ageing.

Due to the weakening of the patient's Kidneys, sleep deprivation is more common in seniors than most people realized. More training in dealing with insomnia and changing sleeping patterns is necessary for Western doctors, as the serious impact on health by sleep deprivation is poorly understood in Western society.

Sleep is needed to invigorate and stabilize the patient's Wu Jing Shen (Five Essence Spirits). Without sleep, the patient's Hun (Spirit Soul), Shen (Spirit), Yi (Intention), Zhi (Willpower) become depleted and they lose control of their Po (Corporeal Soul). This affects the patient's intuitive perceptions, mental comprehension, drive and willpower, and can result in dementia.

UNDERSTANDING DEATH AND DYING

Classes and workshops on death and dying should be more available, and both patients as well as doctors should be encouraged to attend them. The doctor can benefit greatly by learning specific meditations being taught to facilitate this major transition, and also how to relate better to their elderly and young dying patients. The patients can benefit greatly by increasing their awareness and understanding of this process, as well as learning the numerous meditations that help resolve unprocessed emotions. Furthermore, patients can meet others with whom they can share their fears and hopes openly.

Too often the elderly do not wish to share these feelings, even with those closest to them for fear of burdening their family and friends. Patients may also be very reluctant to disclose their personal concerns for fear of being alienated, even with Qigong doctors, especially if the doctor's fear of death becomes evident through too much encouragement to get well and not lose hope.

CHAPTER 51
QI EMISSION THERAPY FOR GYNECOLOGY

INTRODUCTION

Gynecology is the study of diseases of the female reproductive organs. The earliest records of Chinese gynecological medical writings date as far back as the Shang Dynasty (1500–1000 BC). From a Traditional Chinese Medical perspective, a woman's physiology is characterized and diagnosed in accordance with her menstrual flow and vaginal discharge (also included are the energetic formations and transitions during pregnancy and childbirth). A woman's physiology is dominated by, and rooted in Blood. Her Lower Burner houses the uterus, which stores Blood, and corresponds to her Lower Dantian.

MENSTRUAL FLOW

Normally, a woman will follow the cycles of the moon and will menstruate every 28 days. Her cycles can be categorized into either new moon or full moon periods. The length of days between menstruation and the time of duration vary; four days of flow is considered average.

A woman's menstrual cycle can be categorized into four distinct time periods: Irregular Menstruation, Early Menstruation, Late Menstruation, and Prolonged Menstruation.

1. An irregular menstrual cycle is never consistent: sometimes early, sometimes late. The cause of an irregular menstrual cycle can be due to either a stagnation of Liver Qi (from suppressed anger or emotional shock), Liver Qi invading the Spleen (emotions affecting the Liver invades the Spleen), or a constitutional weakness of the Kidneys.
2. The cause of an early menstrual cycle can be due to either Heat in the patient's Blood or Qi Deficiency.
3. The cause of a late menstrual cycle can be due to either Cold stagnation of Blood, Blood Deficiency, stagnation of Qi (caused from emotions), or Deficiency of Qi.
4. The cause of a prolonged menstrual cycle can be due to either Qi Deficiency or Heat in the Blood (this is because Blood that is Hot wanders out of the vessels).

QI AND BLOOD REGULATION

Due to periodical menstruation and the complex changes that occur in the uterus and the organs (ovaries, cervix, and vagina) associated with reproduction, women tend to become especially vulnerable to Blood damage. The formation, circulation, and control of Blood depends upon the transformation, regulation, and production of the woman's Qi. This interdependence of Qi and Blood is regulated through the harmony of the body's Five Yin Organs. For example:

1. The Liver stores the Blood.
2. The Heart controls the Blood.
3. The Spleen contains or keeps the Blood in its vessels. In addition, the body's Spleen and Stomach are also known as the source of reproduction and transformation of Qi and Blood.
4. The Lungs store the Qi, which commands or moves the Blood.
5. The Kidneys store the Jing, which transforms or creates the Blood.

The woman's Sea of Blood can only flow freely when the Qi and Blood of the Five Yin Organs are in harmony. When a woman's Sea of Blood is full and exuberant, then her menstruation will be healthy and normal.

Regarding the Eight Extraordinary Vessels, a woman's Governing, Conception and Thrusting Vessels all originate within her uterus. The Governing Vessel governs the body's Sea of Yang and represents the Yang aspect of a woman's reproductive functions. The Conception Vessel governs the body's Sea of Yin and provides the Yin substances for all physiological and hormonal transitions, including puberty, conception, pregnancy, childbirth, and menopause. The Thrusting Vessels function as the Sea of the Twelve Primary Channels, and influence the supply and proper movement of Blood in the uterus, and control all aspects of menstruation.

The Belt Vessel encircles the Governing, Conception, and Thrusting Vessels, and governs, guides, and supports the energetic flow of Qi and Jing to the uterus.

Regarding the Twelve Primary Channels, their internal network is distributed throughout the uterus and is connected to both the Heart and Kidneys. In addition, the energetic connection with the uterus is further strengthened by the convergence of the Liver, Spleen, and Kidney Channels, along with the Conception Vessel, through the connecting vessels in the genitalia.

ETIOLOGY AND PATHOLOGY OF GYNECOLOGICAL DISEASES

In order for the Qigong doctor to make a correct diagnosis pertaining to a woman's menstrual flow and reproductive organ function, attention must be placed on identifying the primary etiology of the imbalance in the patient's Qi and Blood.

The Governing, Conception, Thrusting, and Belt Vessels are the most important vessels in terms of diagnosing gynecological pathophysiology. Consequently, any damage or disease of the these vessels are believed to be the main causes of gynecological disorders.

Either a direct or indirect attack to the Conception and Thrusting Vessels can cause disharmony of Qi and Blood, resulting in a loss of internal organ regulation.

DIRECT CAUSE

A direct cause of damage to the Conception and Thrusting Vessels can result from either Evil Toxin infections or from hygienically unclean sexual encounters. If the Conception and Thrusting Vessels become damaged, the result can manifest in symptoms such as profuse abnormal vaginal discharge or uterine bleeding.

INDIRECT CAUSE

Indirect causes of damage to the Conception and Thrusting Vessels can result from internal damage due to: The Seven Emotional Factors, Invasion of the Six Exogenous Factors, and An Inconsistent and Undisciplined Diet.

1. The Seven Emotional Factors tend to be the major factors in determining the root causes in most gynecological diseases.

   The suppression of anger, rage, resentment, and jealousy often results in Liver Qi depression, which eventually leads to Blood stagnation. This can result in such symptoms as delayed, painful, or blocked menstruation. If a hyperactive Liver Yang condition occurs, the patient can develop symptoms as serious as pre-eclampsia or eclampsia (coma and convulsive seizures that can occur between the 20th week of pregnancy and first week postpartum; symptoms include edema of the legs and feet, puffiness of the face, hypertension, severe headaches, dizziness, epigastric pain, nausea, sudden convulsive seizures and coma). The Liver's Blood Heat can lead to profuse uterine bleeding, leaking of Blood, hemoptysis (throwing up Blood) or epistaxis (bleeding of the nose).

   The suppression of worry and regret, or obsessiveness, can harm the Heart and Spleen. This can lead to amenorrhea (the absence or suppression of menstruation) or a fetal leakage (after conception, if a small amount of bloody fluid discharges from a woman's vagina, it is known as Tai Lou or fetal leakage).

   The suppression of fright, fear, loneliness, and insecurity can damage the Kidneys and lead to miscarriages.

2. Invasion of the Six Exogenous Factors, in particular, Cold, Heat, and Dampness, are the primary causes for gynecological diseases.

   If the Blood is invaded by Cold, it congeals, causing delayed menstruation, painful menstruation, or severe contractions and thick conglomerations of Blood.

   If the Blood is invaded by Heat, it moves, causing the Blood to flow recklessly. This reckless movement of Blood leads to early menstruation, excessive menstruation, and uterine bleeding.

If the Blood is invaded by Dampness (Damp Evils invading the Spleen), it can lead to abnormal vaginal discharge, uterine bleeding, and irregular menstruation.

3. An Inconsistent and Undisciplined Diet can lead to a Spleen and Stomach disharmony. If the Spleen and Stomach's ability to transform and transport food becomes hindered or weakened, the Sea of Blood becomes Empty. This can lead to delayed menstruation or scanty menstruation.

   If the Spleen loses its ability to restrain and contain the Blood, both Blood and Qi leak out of the vessels. This leaking of Qi and Blood can lead to excessive menstruation and uterine bleeding.

   If the Spleen's Yang does not perform its transporting function, Dampness and Turbidity will descend, resulting in abnormal vaginal discharge.

VAGINAL DISCHARGE

In Traditional Chinese Medicine, abnormal vaginal discharge (Dai Xia) is considered a disease of the Belt Vessel. If the Belt Vessel loses its restraint on the other vessels, then abnormal vaginal discharge is produced. This is usually caused by a Spleen Deficiency, Dampness, and descending Turbid Qi.

CONSISTENCY

The consistency of the patient's vaginal discharge can be divided into three categories: Turbid, Watery, and Clotting (thick and pasty).

1. A Turbid discharge refers to Blood Heat and an infection in the uterus. It also refers to signs of Cold stagnation.
2. A Watery discharge is considered a Cold Damp and / or Deficient condition.
3. Clots (thick and pasty) are considered a Damp Heat and Excess condition.

SMELL

The smell of the patient's vaginal discharge can be divided into conditions of either Damp Heat, indicated by a leathery smell, or Cold Dampness, indicated by a fishy smell. Also, if the patient's menstrual Blood has a strong, foul smell, it usually indicates a Heat condition.

COLOR

Vaginal discharge color is divided into five colors (Wu Se Dai): white, yellow, red, green-blue, and dark brown or black. The pathology of the discharge color is mostly caused from a Deficient Conception Vessel, loss of restraint from the Belt Vessel, Spleen Dampness, or Evil Wind invading the uterine vessels. These conditions create Heat, which descends into the uterine area causing disease.

Only profuse vaginal discharge, which bears an unnatural color and gives off a malignant odor, is considered pathological. The five colors of vaginal discharge are as follows.

1. White vaginal discharge (Bai Dai) is the most commonly seen type of vaginal discharge. It is a Cold condition caused by a Spleen or Kidney Yang Deficiency, or from Exterior Cold Dampness. It manifests as a white, sticky, slimy fluid discharge from inside the patient's vagina with a fishy smell. Symptoms include sore lower back, weakness, and irregular menstruation.
2. Red vaginal discharge (Chi Dai) is caused from Damp Heat in the Lower Burner or Fire Blazing through the Heart and Liver channels. The latter eventually causes a Yin Blood Deficiency. Red vaginal discharge manifests as thick and sticky, white with red mixed together, pale red, or red vaginal discharge with a foul odor. Symptoms include thirst, bitter taste in the mouth, and reddish urine. Continued red vaginal discharge may be a sign of cancer, and the patient should immediately be referred out to an oncologist.
3. Yellow vaginal discharge (Huang Dai) is caused from Heat, usually Damp Heat in the Lower Burner produced from a Deficient Spleen not transporting the Dampness. This condition causes Water Dampness to brew and bind, which then transforms into Damp Heat. The Damp Heat invades the Conception Vessel which causes the Belt Vessel to lose its ability to restrain. It manifests as a yellow, sticky, and

slimy vaginal discharge with a foul odor. A vaginal discharge that has yellow and red with white pus (after menopause) is considered a manifestation of Toxic Damp Heat in the uterus and can indicate endometrium cancer.

4. Green-blue vaginal discharge (Qing Dai) is caused by Damp Heat in the Liver or Gall Bladder Channels. A yellow-green color with pus accompanied by itching and soreness is also a sign of Damp Toxic invasion.
5. Dark brown or black vaginal discharge (Hei Xia) is seen as a form of Blood stagnation.

All gynecological disorders are closely related to the patient's whole constitution, even though the manifestations appear in the reproductive organs. The patient's general constitution, age, dietary habits, home and work environment, should all be taken into account when diagnosing clinical pathophysiologies.

MENSTRUAL COMPLICATIONS

DYSMENORRHEA

Dysmenorrhea is one of the most frequent gynecologic disorders observed in the clinic today. It is described as pain associated with menstruation and refers to cyclic pain (before, during or after menstruation) felt in the lower abdomen or lumbosacral area of the woman's body before, during, or after menstruation. Serious cases of dysmenorrhea can be accompanied by headache, nausea, vomiting, and even syncope.

ETIOLOGY

From a Traditional Chinese Medical perspective, a woman's body is more susceptible to an attack of external pathogens and injury from internal emotional disturbances during her menstrual period. Mental depression may injure the Liver and cause Qi and Blood stagnation.

The invasion of Cold into the Thrusting and Conception Vessels may also cause stagnation and coagulation of Blood, which in turn causes Qi and Blood Deficiency (leading to poor nourishment of the uterus). Excessive exposure to Cold and Dampness can cause Cold to invade a woman's uterus, causing stasis of Blood. A women is prone to Cold invasion when her uterus and Blood are in a weakened state, during and soon after her period.

There are four different phases identified during a woman's menstrual cycle: Before Menstruation, During Menstruation, After Menstruation, and During Mid-cycle.

1. Before menstruation, the woman's Yang rises in preparation to move Blood during her menses; Liver Qi also moves into the lower abdomen in preparation to move the Blood. If a woman's Liver Qi stagnates, it can cause the Blood stagnation in the uterus, leading to pain, especially before her period. This type of stagnation is the most important pathological condition causing dysmenorrhea. Liver Qi stagnation can be caused from emotional strain resulting from suppressed emotions, such as anger, resentment, hatred, and frustration.
2. During menstruation, the woman's Blood is moving. The movement of Blood relies on Liver Qi and Liver Blood. If a woman's Liver Blood stagnates, it will cause pain during her period.
3. After menstruation, the woman's Blood and Yin are Empty.
4. During mid-cycle, the woman's Blood and Yin gradually fill up the Thrusting and Conception Vessels.

According to Western medicine, dysmenorrhea is related to mental stress, emotional instability, mental depression, and fright. Dysmenorrhea can also be due to diseases of the ovaries, uterine, or endocrine glands.

The menstrual pain may appear one to two days before the onset of the menstrual period, and remain until the start of the menstrual flow. It usually lasts from just a few hours to one to two days.

SYMPTOMS

In Traditional Chinese Medicine, dysmenorrhea is classified into two types of syndromes: the Excess type and the Deficient type.

- The Excess type of dysmenorrhea can be caused by either Qi and Blood stagnation, Cold stagnation, or Damp Heat. An Excess condition manifests as distention and pain in a woman's lower abdomen and / or lumbago, occurring before or during menstruation. Symptoms also include obstructed menstruation with pale-purplish color and clots.

- The Deficient type dysmenorrhoea can be caused by either Qi and Blood Deficiency or Kidney and Liver Yin Deficiency. Symptoms of this condition manifest as pain in the lower abdomen, occurring before or during menstruation, which can be relieved by heat and compression. The patient will experience soreness and distention of the waist and legs with pale and scanty menses.

TREATMENT

1. To begin, have the patient sit at the edge of the table and begin stimulating the Yellow Court, Mingmen, and Lower Dantian areas, using the Vibrating Palm technique, for 6 to 8 breaths.
2. Emit Qi, using the Extended Fan Palm technique, into the patient's Lower Dantian, purging the Qi down the Stomach Channels to her feet.

TREATMENT MODIFICATIONS

- When treating patients with the Excess type of dysmenorrhea, emit Qi into the patient's Lower Dantian, St-21, and Lv-14 points, then purge the Stomach and Liver Channels down to and out of the feet.
- When treating patients with the Deficient type of dysmenorrhea, emit Qi into the patient's Lower Dantian, then guide Qi along the Stomach and Spleen Channels to regulate the body.

PRESCRIPTIONS AND HOMEWORK

Have the patient practice the Descending the Yang and Ascending the Yin techniques (see Chapter 41).

PRESCRIPTION MODIFICATIONS

1. For patients with the Excess type of dysmenorrhea:
    a. Have the patient sit at the edge of a chair, relax and breath naturally, with the tongue placed up against the hard palate. The patient's mind should concentrate on her Lower Dantian and navel area.
    b. The patient should imagine the navel as the center of a wheel. When inhaling, she should move the Qi upwards, rotating the energy clockwise, from the lower portion of the right side of the abdomen. The patient silently chants the phrase: "The white tiger hides in the east." Exhaling, she rotates the Qi from above the navel to the left side of the abdomen back to the beginning point, while silently chanting the phrase: "The blue dragon shelters in the west." The patient continues circulating the Qi around the navel, rotating it in a clockwise direction for 36 breaths. In this particular meditation, it is important the patient start with small circles and gradually increase the circumference of the energy circle, in order to disperse the accumulated Heat in the uterus.
2. For patient's with a Deficient type of dysmenorrhea:
    a. Have the patient sit at the edge of a chair, relax and breath naturally, with her tongue placed up against the hard palate. The patient's mind should concentrate on the Lower Dantian and navel area.
    b. Imagine the navel as the center of a wheel. When inhaling, she should move the Qi upwards, rotating the energy counterclockwise, from the lower portion of the left side of the abdomen. The patient silently chants the phrase: "The blue dragon shelters in the west." Exhaling, she rotates the Qi from above the navel to the right side of the abdomen back to the beginning point, silently chanting the phrase: "The white tiger hides in the east." She continues circulating Qi around the navel, rotating from large to small circles in a counterclockwise direction for 36 breaths. In this particular meditation, it is important that the patient start with large circles and gradually decrease the en-

ergy circle's circumference in order to gather energy into the uterus.

MENOXENIA

Menoxenia refers to the pathological changes of menstruation occurring in the cycles, such as the color, quantity, and quality. This includes extended or delayed menstrual cycles, as well as menorrhagia (excess bleeding) and scanty menstruation.

SYMPTOMS

1. Blood Heat symptoms include: prolonged menstrual cycle, profuse menstruation of bright red or purplish color, viscous in quality, and a heavy feeling in the chest.
2. Deficiency of Qi symptoms include: prolonged menstrual cycle, profuse, pale and watery menstruation, listlessness, palpitations, shortness of breath, and an empty or dropping sensation in the lower abdomen.
3. Blood Stasis symptoms include: delayed menstrual cycle, purplish and massed menstruation with pain and distention in the lower abdomen.

TREATMENT

1. Have the patient sit at the edge of the table and begin to stimulate her Yellow Court, Lower Dantian, and Mingmen areas using the Vibrating Palm, for 8 to 16 breaths.
2. Use the Extended Fan Palm hand posture to emit Qi into the patient's Mingmen and Lower Dantian using the Spiral Rotating method of Qi manipulation. Rotate the energy in a counterclockwise direction for conditions of Excess and a clockwise direction for Deficient conditions.

TREATMENT MODIFICATIONS

- When treating a patient with Blood Heat, emit Qi into her Yellow Court and Lv-14 points, drawing the energy down her Liver Channels and out of her feet.
- When treating patients with a Deficiency of Qi, use a Extended Fan Palm hand method while tonifying and filling her Mingmen and Lower Dantian areas.
- When treating a patient with Blood Stasis, use the Extended Fan Palm hand method to emit Qi into her Lower Dantian and rotate the Qi in a clockwise direction.

PRESCRIPTIONS AND HOMEWORK

In order to move the energy and allow Qi and Blood to flow smoothly in the uterus, have the patient practice the Microcosmic Orbit Fire Cycle (see Chapter 41).

PRESCRIPTION MODIFICATIONS

- For patients with Blood Heat, it is advisable to have them practice the Liver Massage method (see Chapter 39) and sound the word "Xu" (Shu).
- For patients with Qi Deficiency, have the patients perform Natural Breathing meditations, as well as the Daoist Five Yin and Yang Organ Exercise (see Chapter 42).
- For patients with Blood Stasis, have the patient practice Circling the Abdomen, for 36 breaths in a clockwise direction (see Chapter 41).

CYSTS AND TUMORS

BREAST CYSTS AND BENIGN TUMORS

A breast cyst or benign tumor is a lump or nodule found within the breast tissue.

ETIOLOGY

The fibrocystic changes that can occur in a woman's breast tissue are commonly divided into three levels of benign breast disorders. Beginning with Level-1 breast cysts (which include the development of benign lumps, nodules or fibroadenoma), progressing onto the development of Level-2 breast cysts (which include the development of mastitis or carbuncles), and ending with Level-3 breast tumors.

The Qigong doctor's treatment will vary according to the type and condition of the lump enclosed within the patient's breast tissue.

DIAGNOSIS ACCORDING TO DIFFERENT TYPES OF BREAST LUMPS

The Qigong doctor differentiates among the types of breast lumps and initiates treatment accordingly. Breast lumps can be divided into three major categories: Phlegm, Blood Stasis, and Toxic Heat.

1. Phlegm lumps are soft with distinct edges, mobile and slippery. They are not swollen, and the skin surface around the area is white.
2. Blood Stasis lumps are hard, immobile nodules. The skin surface around the surrounding area is purple.
3. Toxic Heat lumps are hard, immobile, with indistinct edges. The skin surface of the surrounding area is indented and red.

LEVEL-1 BREAST CYSTS (BENIGN LUMPS, NODULES OR FIBROADENOMA)

These are lumps that feel like hard nodules; they are usually painless, round, flat, and mobile. The lumps do not feel hot or cold to touch, the skin color is unchanged, and the size of the lump may vary depending on the patient's mood changes.

ETIOLOGY

Level-1 cysts are usually caused by the patient's Liver and Spleen being affected by anger, worry, and depression. The Spleen Qi is weakened, thus disrupting the free-flow of the Liver Qi. This leads to conditions of nodules due to both Qi and Phlegm stagnation. Long term Qi stagnation eventually leads to the accumulation of Phlegm and Stasis of Blood.

SYMPTOMS

These type of cysts are characterized by their process of development; they generally start off small and increase in size after several months.

TREATMENT

Eliminate the stagnation and remove the Phlegm using Qi purging and dispersing techniques.

LEVEL-2 BREAST CYSTS (MASTITIS OR CARBUNCLE)

This condition is a painful inflammation of the breast skin and underlying tissue.

ETIOLOGY

Level-2 cysts are usually caused by Qi and Blood stagnation, resulting from the stagnation of the Liver or Gall Bladder Qi, which is accompanied by excessive stagnation of Toxic Heat in the Stomach Channels. Breast cysts can be internally induced by suppressing the emotions, especially grief. Generally mother issues relate to the left breast and Lung area, while father issues relate to the right breast and right Lung area.

TREATMENT

1. After clearing the diseased area of Toxic Qi, the Qigong doctor uses the Sword Fingers technique to stimulate CV-17, St-18, Lu-1, Bl-18, and -21 points, to open the points along the Liver, Lung, and Stomach Channels.
2. Next, the Qigong doctor emits Qi, using the Vibrating and Shaking techniques, to disperse the cyst.
3. The doctor then applies the Dragon Mouth manipulation to dredge the patient's body, by pushing, pulling, and leading the Stagnant and Toxic Qi down the patient's Lung Channels (out the arms), and Stomach Channels (out her legs), via the St-36 points.
4. The patient is given homework, consisting of Jing Point Therapy, and of kneading the surface and surrounding tissue of the cyst at least once a day. This prescription should also include the use of the "Shang" sound tone resonation to further dissolve the cyst, and to dispel the Toxic Qi out of the breasts.

LEVEL-3 BREAST TUMORS

This type of breast cyst corresponds to a severe condition of dysplasia.

ETIOLOGY

Level-3 cysts are usually caused by Liver Fire, accompanied by Heart and Lung Qi stagnation due to the accumulation of grief, sorrow, exasperation, and being upset, or due to the derangement of the patient's Thrusting and Conception Vessels.

TREATMENT

1. After clearing the diseased area of pathogenic Qi, the Qigong doctor uses the Thunder Palm technique to disperse the tumor.
2. After several minutes of blasting the area, the Qigong doctor uses the Spiraling and Circling Energy techniques to circle the tissue areas

surrounding the tumor, drawing the pathogenic Qi down and out of the patient's nearest arm via the Lung Channel (Figure 51.1).

3. The Qigong doctor then uses energetic Pulling and Shaking techniques to release the pathogenic Qi from the patient's body and to draw it out of the arm. The doctor must then pull and snap each of the patient's fingers and thumbs, to release and disperse the Excess Heat and pathogenic Qi.
4. Next, circle rotate the energy within the patient's Lower Dantian, pulling the Qi down the lower legs and out the St-36 points.
5. Finally, fill her Lower Dantian and circle regulate her Governing and Conception Vessels using the Microcosmic Orbit to balance the Yin and Yang energy.
6. Give the patient homework consisting of Jing point therapy that stimulates the GB-21, St-36, CV-17, and Sp-6 points, once a day. If the patient is using magnetic therapy, she should place the magnets on the points for 1 hour. This prescription should also include herbs, and the use of the "Shang" sound tone resonation (straight tone and descending/ascending tone prescriptions) to further dissolve the tumor.

OVERVIEW OF TREATMENT

The general treatment for breast diseases, depending on the severity of the condition, is divided into five main components: Medical Qigong therapy, Medical Qigong massage, prescriptions, Jing point therapy, and herbal teas.

MEDICAL QIGONG THERAPY

The doctor's emitted energy can assist the patient in dispersing stagnations, as well as dissolving breast tumors and cysts. Generally, the doctor's treatment lasts for a period of three days, and can be indefinitely prolonged and increased in effectiveness if the patient is given additional Medical Qigong prescriptions as homework.

MEDICAL QIGONG MASSAGE PRESCRIPTION

This therapy is most important as it allows the patient to reconnect with her tissues and further allows her to feel and release emotions trapped



Figure 51.1. After purging the Toxic Qi from the patient's upper body, the Qigong doctor continues to disperse the patient's Toxic Qi from the lower abdomen, leading it down the patient's leg and out of the St-36 points.

within her body (remember, you can only heal what you feel). This healing process is as follows.

1. The patient begins by rubbing her hands together to get them hot.
2. Placing her hands on her breast, the patient inhales and draws the heat from her hands into the breast tissue, while imagining divine healing light flowing from the Heavens, and pouring into her body to fill up her chest.
3. The patient circle massages her breasts 36 times towards the outside of her body, concentrating on the breast tissue filling up with the divine healing energy that destroys any and all pathogens stored within her breast tissues.
4. After completing 36 times in one direction, the patient reverses directions but maintains the same visualization.
5. Next, the patient exhales the straight healing sound "Shang" for 9 breaths, toning, while turning the body from the left to the right side. The patient focuses on purging the pathogens out of her breast area through her mouth. This purges her Lungs and the surrounding breast tissues.
6. The patient then exhales the descending/ascending healing sound "Shang" for 9 breaths as she turns at the hips, toning from the right to the left side of her body, and focuses on purging the pathogens out of her breast area. This purges her Lung Channels and the surrounding energetic connections to the breast area.
7. The patient then rubs 36 times in a clockwise direction, from her abdomen to her Lower Dantian, leading the Qi downwards. This is performed to root the energy back into her Lower Dantian.
8. The patient ends the prescription in a quiescent state of mind.

MEDICAL QIGONG PRESCRIPTIONS

This therapy allows the patient to purge the organs that are found to be the root cause of the disease. In Medical Qigong, the doctor views the patient's cysts or tumors as a flower. If, through surgery, the top of the flower is plucked from its stem (and the branch, stem, and root cause of the disease is left still intact), the tumor or cyst will return again. In order to heal the patient's condition, the doctor must also address the original cause of the disease and destroy the entire support system. The purpose for these prescriptions is to destroy the disease's entire root system to kill the flower.

1. The Dry Crying prescription is given to purge the emotions of grief and sorrow from the patient's Lungs (see Chapter 53).
2. The "Guo" healing sound is given to purge the patient's Liver Fire.
3. The "Shang" healing sound is given to dissolve the cyst or tumor.
4. Prescribe Jing Point Therapy. Specific points are prescribed for the patient to enhance the doctor's treatments, and increase her own healing potential. The patient is encouraged to stimulate specific areas of her body, by emitting Qi while pressing and focusing her intention into the following points:
    a. The Small Intestine 3 point affects the patient's breast disease caused by Rebellious Qi and Qi depression.
    b. The Stomach 18 point frees Qi flow locally in the patient's breast.
    c. The Stomach Channel transverses the breast, and the Stomach 36 point regulates Qi of the patient's entire body.
    d. The Spleen 6 point is specifically chosen for treating breast cysts.
    e. The Gall Bladder 21 point (Shoulder Tapping) is prescribed to assist the patient in sinking Liver Qi Heat.

HERBAL TEAS

All herbal teas are administered to move the Qi and assist the doctor's treatment. Dandelion tea, for example, is mixed with green tea to clear Heat from the patient's body; or green orange peel is added to help move the Qi.

OVARIAN CYSTS AND UTERINE TUMORS

In an ovarian cyst, there is a closed sack or pouch containing fluid, semifluid, or solid material, usually characterized by Phlegm, Damp Heat, and Stasis of Blood.

ETIOLOGY OF OVARIAN CYSTS

Ovarian cysts can be caused by psychological upheavals which lead to enlarged follicles that fail to rupture, as well as by Liver Fire stagnation. Ovarian cysts are usually related to the anger from the Liver turning inward and attacking the body.

ETIOLOGY OF UTERINE TUMOR

A uterine tumor, or myoma, is a solid benign growth in the myometrium, and is often called a fibroid. It contains muscle tissue. Excessive uterine bleeding is a common effect of myomas. Ovarian cysts and uterine tumors are generally divided into three types of myomas:

1. The subserous type is located on the outside wall of the uterus;
2. The interstitial type is located within the wall of the uterus;
3. The submucous type is located on the inside of the uterus.

TREATMENT

The same treatment is used for both ovarian cysts and uterine tumors. To treat these conditions, the doctor uses Medical Qigong therapy in conjunction with Jing point therapy and herbs.

1. Begin with the patient in a supine position and purge and clean the diseased area of pathogenic Qi, using the Thunder Palm technique in conjunction with the Vibrating Palm, to disperse the stagnation in the ovaries or uterus.
2. Disperse pathogenic Qi out the patient's body via the Gall Bladder Channels.
3. Tonify the patient's Lower Dantian with Qi and circulate the energy through the Microcosmic Orbit.
4. Press and stimulate with Jing point therapy the Sp-6, Sp-9, St-36, GB-34, and GB-38 points (Figure 51.2).

PRESCRIPTIONS AND HOMEWORK

The patient should be given homework, in accordance with her constitution. The prescriptions should include:

1. The "Guo" sound to disperse Liver Fire.
2. The "Yu" sound to disperse ovarian cysts.
3. Prescribe Lower Dantian regulation exercises to access and regulate the ovarian energy.
4. Prescribe herbs for chronic conditions.



Figure 51.2. When treating ovarian cysts, use Jing Point therapy in conjunction with Qi emission, to stimulate Sp-6,-9, St-36, G.B.-34 and 38 points.

UTERINE COMPLICATIONS

MISCARRIAGE

A miscarriage is the termination of a pregnancy, at any time before the fetus has attained extrauterine viability. Miscarriage occur usually between conception and the fourth month of pregnancy.

In Traditional Chinese Medicine, a miscarriage can have several stages and levels of severity, ranging from such conditions as Fetal Leakage, Restless Stirring of the Fetus, Falling Fetus, and Small Birth. Within each of these conditions there are several patterns of disharmony.

ETIOLOGY

There is an ancient Chinese saying which states "A miscarriage is more serious than child birth." According to Traditional Chinese Medicine, there five basic mechanisms associated with the cause of a miscarriage: Empty Conception and Thrusting Vessels, Blood Deficiency, Depressed Liver Fire, Blood Stasis, and External Injuries.

1. An Empty condition of the Conception and Thrusting Vessels causes miscarriages. The mother's Kidney Qi consolidates the fetus and is responsible for constricting the anal and vaginal orifices. If the Conception and Thrust-

ing Vessels become empty, they cannot consolidate and secure the fetus within the womb. If any of the following three conditions occur singly or in concert, both the Conception and Thrusting Vessels may indeed become Empty: (1) the mother's Yin Essence is depleted or consumed; (2) the Mingmen Fire is insufficient, and (3) both the Yin and Yang Qi are Deficient. Any of these three conditions may be due to: congenital weakness and insufficiency, chronic disease, extreme or prolonged stress, unrestrained sex after conception, or the mother's age (over 40).

2. Blood Deficiency from an irregular diet, excessive worry and anxiety may deplete the Spleen and Stomach organs resulting in a miscarriage. Since the Spleen is the postnatal root for Blood generation and transformation, an Empty or Deficient condition of Spleen Qi may cause Blood Deficiency. Furthermore, as the Spleen Qi restrains and supports the mother's abdomen, a Spleen Qi Deficiency, or Empty Spleen Qi, may lead to the prolapse of the Central Qi and produce insufficient Blood to nourish the fetus. Both the Central Qi prolapse and the Blood Deficiency can present the Conception and Thrusting Vessels from consolidating the fetus and securing it in the womb.
3. Depressed Liver Fire due to suppressed emotional frustration (with mental agitation, anger, jealousy, and envy) may cause a miscarriage. The excessive Heat generated by the depressed Liver Fire may in turn attack the mother's Sea of Blood, scorching and injuring the Thrusting (Chong) Vessel. This injury, in turn, may cause the mother's Yin Blood to flow recklessly downward, leaving no place for the fetus to rest.
4. Blood Stasis may be due to three different factors: past internal injuries, iatrogenic disorders, and long term Qi stagnation. The excessive accumulation of Qi and Blood within the mother's womb during conception can sometimes aggravate a preexisting condition, and thereby cause hemorrhaging, as well as initiate energetic patterns which fails to stop her from bleeding.
5. External Injuries from accidents (sustaining a sprain or strain in the abdominal region), or battery (being hit or struck) can lead the body into a state of shock. This shock to the mother's body may damage either the Conception or Thrusting Vessels, preventing them from securing the fetus within the womb.

TREATMENT

In the Medical Qigong clinics in China, doctors are cautioned to be extremely careful when treating pregnant patients. Qi emission can cause a spontaneous miscarriage if done incorrectly. It is therefore recommended that only Medical Qigong doctors, who have specialized in the specific treatment of pregnant women, be allowed to diagnose and treat them. The interdependencies of the mother's and the fetus' energy circulation is too complex and delicate for a generalized practitioner to handle.

Treatments for miscarriage vary, based on pattern discriminations of Kidney Deficiency, Qi and Blood Deficiency, Blood Heat or physical trauma. An example of an ancient Chinese prescription requires the doctor to treat Yingu Kd-10 for miscarriages with vaginal bleeding, dark urine, abdominal distention, and fullness with an inability to lie down.

If the patient has already experienced a miscarriage, and is in the state of recovery, specific treatments vary according to the doctor's diagnosis concerning the etiology and pathology of the patient's condition.

HOMEWORK AND PRESCRIPTIONS

Each consecutive miscarriage causes further injury to the patient's Kidneys, creating or aggravating the stagnant Blood condition in the uterus. Doctors of Traditional Chinese Medicine therefore encourage their patients to take herbal medicines, and to practice Medical Qigong for six months before attempting to conceive again.

When they do become pregnant again, they are encouraged to continue to practice Medical Qigong meditations and exercises for strengthening and balancing their body's energetic fields and internal organs.

A patient recovering from a miscarriage is given specific prescriptions according to her emotional condition, organ dysfunction, and the etiology of the condition.

UTERINE COMPLICATIONS DUE TO ABORTIONS

Another important aspect of Medical Qigong and gynecology is helping a patient face the loss, or termination of a pregnancy. This can occur either intentionally (through an abortion), or unintentionally through a miscarriage, spontaneous abortion, or the death of a fetus by other causes.

When a woman has undergone an elective abortion, the Qigong doctor must not only consider the potential for scar tissue formation and physical complications within her uterus, but also the energetic and emotional complications resulting from the abortion.

While treating the patient, the doctor may discover within the uterus what appears to be the energetic remains of the aborted embryo. These phantom embryos may in fact be thought forms created by the mother's feelings of guilt and shame at having undergone an abortion. These difficult emotions are further compounded by deeper feelings of self-hate, that go unnoticed by others.

Most people feel little compassion for women who suffer a miscarriage, and discourage them from grieving. They are frequently advised by well meaning friends to believe that the miscarriage was all to the good, preventing a possible deformed or sickly baby from being born.

If women who miscarry are discouraged from grieving, those who make the painful decision to abort often face scorn and disbelief when they grieve their loss. Silently they mourn as best they can, haunted by feelings of shame imposed upon them by others and their own conscience.

Most women struggle long and hard before resorting to abortion. Afterwards, they often obsess about the living embryo, and what it felt like to be pregnant, centering all their attention on the uterus. Such intense, emotional concentration creates phantom embryos that, in fact, take on the form of ghostly embryos. These thought forms or energetic imprints are clearly visible to the doctor's inner vision. The energetic imprint contains the location, exact age and size at the time of the embryo's termination. The unprocessed energetic charge of the embryonic ghost's location creates an energetic vortex. This vortex, in turn, draws emotions such as rage, anger, guilt, and shame into itself. If this area is not purged, the resulting accumulation of negative emotions will develop into cysts, tumors, and possibly cancer.

This energetic reaction to surgical abortions has been confirmed by several Western doctors (all wishing to remain anonymous). These doctors observed that after many years of performing abortions, within a very short time period several patients (whose ages ranged from 16 to the mid 30's) developed reoccurring cysts and tumors. The location of the cysts or tumors in the majority of the patients uteri was at the exact tissue area of the embryo.

HEALING THE ENERGETIC TRAUMA

When the patient has decided to heal from her loss, she must not only address her physical condition (scar tissue formation, etc.), but also heal from the spiritual and emotional woundings as well. To assist the patient to heal emotionally and disperse the energetic charges, the doctor must help the patient transform the energy stored within her Wu Jing Shen, which is responsible for maintaining the toxic energetic pattern. Only after experiencing and releasing the emotions stored within the Wu Jing Shen (see Chapter 13) is the patient ready to heal. The healing process is divided into three distinct steps:

1. The patient is encouraged to completely forgive herself for losing the child and to reconnect with her higher power.
2. The patient is encouraged to completely forgive herself for being in the situation, and assume the responsibility of the pregnancy and the loss.
3. The patient is encouraged to completely forgive the person responsible for making her pregnant.

It is important for the patient to completely feel and experience all three stages of forgiveness in order to begin healing these energetic wounds.

Withholding the smallest bit of guilt or anger will seek to sabotage the healing process, and will also allow the toxic energetic charge to remain within the patient's tissues. Even the smallest bit of anger or guilt that remains will continue to recreate a destructive energetic cycle, storing and retaining the patient's toxic emotions.

RELEASING THE EMBRYO'S ETERNAL SOUL

The purpose and goal of releasing the embryonic thought form is to free the patient from the energetic remnants of the phantom embryo. The patient is encouraged to make peace with herself and with the energetic form of her unborn child, as well as the divine (God or higher spiritual force incorporated in the patient's own belief system). The patient does this through deep, meditative prayer, positive affirmation, and an attitude of honor and respect for the relationship between herself and the embryo's energetic remains. Even though the Eternal Soul does not remain present during the abortion, the mother may still need to atone for her decision not to bring the baby to term. This atonement may be necessary to fully release all feelings of guilt in accordance with the patient's religious belief system.

The patient must also make peace with the embryo's Eternal Soul, by enveloping the phantom embryo in a circle of divine healing light and love, to return it back to the divine. In order to achieve this, it is helpful for the patient to visualize creating a small energetic bubble, full of love and healing light, to house the departed embryo's energetic remains before returning it back to the divine. This serves to complete the emotional closure. Once closure is established, the energy of the embryo's energetic remains will leave her body, allowing the patient to feel a fulfilling sense of release, completion, calmness, and inner-peace.

UNDERSTANDING ENERGETIC ABORTIONS

The gift of life is an incredible miracle. If a difficult decision is made to not keep a pregnancy, however, then the patient should consider contacting the embryo's Eternal Soul. Through prayer, meditation, imagination, and visualization, the mother and father can connect to the developing embryo and request that the embryo's Eternal Soul return back to the light of the divine. Sometimes called an energetic abortion, this energetic transformation can take place within the first developing stages of the mother's pregnancy.

Since the Eternal Soul is ageless, it is possible to carry on a mind to mind conversation. When a baby is born, its brain must have time to develop before it can grasp complex information; the mind itself must have time to direct the brain's growth and the body's maturation. Once the Eternal Soul is freed from the body, however, it is not confined by the physical limitations of the infantile brain and should be spoken to as an equal. This method is used by psychotherapists on the leading edge today, using hypnosis to facilitate the patient's connection to the Eternal Soul through visualization.

Patients who have undergone age regression psychotherapy to the state of conception and embryonic state often describe visiting the mother's womb during the time of conception, then leaving and returning at various times during the embryonic stage of development. The Eternal Soul's residence does not appear to be permanent until the end of the first trimester (see Chapter 2). Until then, the Eternal Soul may come and go as it chooses, staying, at times, just long enough to insure the continued growth and development of its physical body.

It may be for this reason, that talking mind to mind with the embryo's Eternal Soul to request its departure, is often successful in precipitating a miscarriage. As the Eternal Soul leaves the embryo's body (sometimes observed as a small ball of white light energy), all that remains in the mother's womb is an empty, lifeless mass of tissue. Usually the mother's body will naturally abort the lifeless tissue mass, either immediately, or by the next morning.

CHAPTER 52

QI EMISSION THERAPY FOR NEUROLOGY (STROKE, COMA, PARALYSIS, AND MULTIPLE SCLEROSIS)

INTRODUCTION

Neurology is a branch of medicine that deals with the nervous system and its diseases, as well as neuropathology. Neuropathology is the study of diseases of the nervous system and the structural and functional changes occurring within them. Neurological diseases are divided into either congenital predispositions that develop over time into full-blown disorders, or those in which acquired destructive pathogenic factors act upon the brain. The latter are usually caused by toxic, traumatic, mechanical, inflammatory factors or neoplastic types of diseases (abnormal tissue formation).

The following is a description of several treatments and prescriptions used in various Qigong clinics and hospitals throughout China. Please be aware that specific treatments will vary according to each patient's constitution and the nature of his or her diseases.

STROKE (WIND-STROKE)

A stroke is a sudden loss of consciousness followed by paralysis, and may be caused by one of several different factors, including a brain hemorrhage, the formation of an embolus or thrombus in an artery, or the rupture of an extracerebral artery causing subarachnoid hemorrhage.

ETIOLOGY

Although a stroke occurs suddenly, in actuality, the causal factors build up for several years. A stroke can be caused from high blood pressure, diabetes, high cholesterol, chronic dehydration, overwork, emotional stress, irregular diet, excessive sexual activity and severe migraines. Strokes usually occur at night, or early in the morning (the same is true regarding heart attacks).

There are four pathogenic factors involved in causing stroke. These factors are: Wind, Phlegm, Fire and Stasis. The Liver is dependent on the Kidney Water (Yin Qi) to moisten and soften it. If, however, the Kidney Yin becomes Deficient, this may cause the Liver Yang energy to grow, and to generate Fire. Excess Liver Fire may stir up Internal Wind which causes the Qi and Blood to rebel upwards. Phlegm is then formed, which obstructs the cavities and vessels, causing the patient to lose consciousness. This can further develop into Penetrating Wind (i.e., stroke). Internal Wind may also develop from Heat and Phlegm caused by the patient eating too many sweet and fatty foods (irregular diet), overwork, emotional stress, excessive sexual activity, and inadequate rest.

In the clinic, conditions referred to as stroke (Wind-Stroke) include cerebral hemorrhage, cerebral thrombosis, cerebral embolism, and cerebrovascular spasm. These four conditions are termed in Western Medicine as "Cerebro-Vascular Accident" (CVA), and include: Cerebral Hemorrhage, Cerebral Thrombosis, Cerebral Embolism, and Cerebrovascular Spasm.

1. Cerebral Hemorrhage consists of bleeding, which is caused from a rupture of a sclerosed, or diseased vessel in the brain;
2. Cerebral Thrombosis is an obstruction of a cerebral artery by a thrombus (blood clot);
3. Cerebral Embolism is a condition which occurs when an embolus (bubble of air, or piece of a thrombus) detaches from a thrombus and obstructs a cerebral artery; and
4. Cerebrovascular Spasm (Ischemia) is a condition which occurs when a cerebral vessel temporarily contracts, or constricts, impeding Blood flow. Hence, the oxygen supply is obstructed sufficiently to cause symptoms. When reversible, or when there is no permanent damage, they are known as Transient Ischemic Attacks, or TIA's. The TIA's are pre-stroke symptoms, commonly known as a mini-stroke.

SYMPTOMS

In dealing with stroke patients, it is important to differentiate between the severe type (which attacks the internal organs and channels), the mild type (which attacks only the channels), and the chronic type.

Stroke manifestations can either arise independently from an attack on the channels, or as a result of an attack on the internal organs. After a severe type of stroke, the patient enters into the next stage, clinically manifesting symptoms similar to that of the mild type. The shorter the time lapse before beginning treatment on a stroke patient, the better the chances are for recovery.

THE SEVERE TYPE OF STROKE

In a severe type of Wind-Stroke, the energy attacks the patient's internal organs and channels. It is characterized by a loss of consciousness, aphasia, numbness, paralysis and/or coma. If the right side of the brain is damaged, there will be paralysis on the left side of the patient's body with accompanying memory defects and language difficulties. If the left side of the brain is damaged, there will be paralysis on the right side of the patient's body, speech and language difficulties, slow, cautious movements, and memory problems.

Clinically, severe stroke patients are further classified into two categories: Tense or Flaccid. The Tense type (also referred to as the Closed type) corresponds to the Collapse of Yin. The Flaccid type (also referred to as the Open type) corresponds to the Collapse of Yang. These conditions and symptoms are further described as follows.

1. The Tense Stroke Symptoms include: clenched hands, open eyes, clenched jaw, red face, coarse breathing, and a forceful pulse.
   - **Treatment for Tense Stroke conditions.** Rescue the patient's Yin by giving herbs, as well as extending Qi into the patient's GV-20, -26, Kd-1, Lv-3, St-40, and the 12 Jing-Well points on both hands (Lu-11, LI-1, Ht-9, SI-1, Pc-9, TB-1). The patient should be given homework upon recovering, depending on his or her constitution.
2. The Flaccid Stroke Symptoms include: limp hands, closed eyes, open mouth, weak breathing, and a weak pulse.
   - **Treatment for Flaccid Stroke conditions.** Rescue the patient's Yang by giving herbs, as well as extending Qi into CV-8, CV-6, and CV-4 points, and GV-20 points (with or without the application of Moxa), to increase the patient's Yang. Patient should be given homework upon recovering, depending on his or her constitution.

THE MILD TYPE OF STROKE

In the Mild Type of Wind-Stroke, the energy attacks only the patient's channels. This is characterized by numbness, slurred speech, and unilateral paralysis. Clinically, mild stroke patients are further classified into two categories that are determined by the type of channels that are attacked.

1. An attack of the main channels causes no loss of consciousness or coma; however, there will be unilateral paralysis (hemiplegia), numbness of the limbs and deviation of the eye and mouth. Clinical manifestations vary according to the location of the channels and collaterals that have been affected.
   a. Symptoms of an attack on the channels include: facial paralysis, hemiplegia, motor impairment and numbness of the limbs.
   b. Symptoms of an attack on the collaterals consists of a unilateral numbness of the face and extremities.
2. An attack of the connecting channels is characterized by numbness.
   - **Treatment for mild stroke conditions.** In order to treat a Mild stroke condition combine Medical Qigong therapy with acupuncture therapy and herbs, to:
     a. Remove obstructions from the patient's channels,
     b. Purge Wind and transform Phlegm,
     c. Invigorate the patient's connecting channels,
     d. Regulate the circulation of Qi and Blood in the patient's channels, and
     e. Prescribe homework in accordance with the patient's constitution and condition.

In the acute stage, stroke patients should immediately be treated in combination with Western medicine, utilizing Qigong, acupuncture and herbal therapy. Treatments should be given everyday (usually every six hours) for the first month, and every other day for the second month. The general treatment is aimed at relieving the patient's spasms, and lowering his or her blood pressure (if the condition is due to hypertension). The primary points treated are determined by the type of stroke, which internal organs were affected, and the extent of damage to the patient.

THE CHRONIC TYPE OF STROKE

This condition is characterized by slurred speech or an inability to talk or eat, and involves either a unilateral (hemiplegia) or bilateral (paraplegia) paralysis.

- **Treatment for Chronic Stroke conditions.** In order to treat a chronic stroke condition the Qigong doctor must invigorate the patient's Blood, tonify the Spleen and open the patient's channels. The specific points will vary according to the area and location where the channels are blocked. The most commonly used points include: St-4, St-6, St-7, TB-17, GB-14, LI-4, SI-18, Tai Yang (Temple), and Yin Tang (Third Eye Point).

  If the body is in a state of unilateral paralysis, the doctor also treats the opposite side of the patient's head using Jing Point Scalp Therapy, in order to move stagnation, purge any Excess, and stimulate and fill any Deficiencies.

COMA

A coma is an abnormal, deep stupor occurring during illness, as a result of the illness, or due to an injury.

ETIOLOGY

From a Traditional Chinese Medical perspective, a coma results from Qi obstruction to the brain. More then 50% of coma cases result from trauma to the head, or circulatory accidents in the brain. A coma can be initiated from several different types of conditions.

1. A trauma induced coma is caused by an injury to the head as a result of accidents and internal hemorrhages. Electrocution can also induce a coma.
2. Insufficient Blood flow to the brain can cause a coma. This can result from circulatory accidents within the brain caused from hypertension, arteriosclerosis, thrombosis, and tumors.
3. An overdose of drugs, alcohol or medications, poisoning, gases or fumes such as carbon dioxide or carbon monoxide can all induce a coma.
4. Temperature abnormalities, such as hypothermia or sunstroke can cause vomiting, diarrhea, shock and then coma.
5. Insulin shock, epilepsy, electrolyte abnormalities, endocrine problems, meningitis, uremia or renal problems, and hyperglycemia can all induce a coma.
6. An infection induced coma is caused by an acute infection and bacterial intoxications as in fevers, botulism, and other infectious diseases; or as a result from abscess formations.
7. Psychogenic comas are also known as a hysterical coma.
8. Windstroke comas are caused by tension, hyperactive Liver Yang and Phlegm Fire overheating the brain. This results in urine and stool incontinence, cerebral hemorrhaging, and thrombosis. This is often located at the union of the anterior and posterior cerebral arteries, called the Circle of Willis.

SYMPTOMS

When a patient is in a coma, the Shen is completely out of its residence and the patient cannot be aroused by external stimuli. The patient's Shen is inactive, yet the Hun and Po are still there. For death to occur, it is not enough for the patient's Shen to leave, but the energy of the Hun and Po must also leave.

TREATMENT

In treating coma patients, it is mandatory to use methods that will activate the patient's Qi, remove the Blood stasis, and return the Shen back into the body. In the acute stages of treatment, use Medical Qigong therapy in addition to the Invisible Needle technique (see Chapter 35). It is most important to treat the coma patient as soon as possible. I have trained with three doctors of Traditional Chinese Medicine who were proficient in coma revival. Below are two accounts of coma revival cases from Dr. Lu Guo Hong's clinic at the Hai Dan Medical Qigong College in Beijing, China.

Case Study #1. Dr. Lu's patient had been in a coma for four hours prior to treatment. The patient regained consciousness within fifteen minutes during the treatment. Dr. Lu treated his patient using the Vibrating Palm technique (on points GV-20, Yin Tang, GV-15, CV-17, Bl-15, Pc- 6, TB- 5, and the extra points Shi Xuan at the tips of the fingers). By squeezing the Shi Xuan points, the Excess Heat was allowed to disperse (Figure 52.1).

Case Study #2. A female patient apparently incurred a series of Transient Ischemic Attacks (TIA) over a period of two years prior to coming to Dr. Lu. As the condition progressed, she developed a thrombosis on the left side of the brain, which paralyzed the right side of her body. The patient then apparently incurred thrombosis of the right side as well.

Because there were thrombosis on both sides of the brain, the patient was expected to die within a month. Dr. Lu, assisted by two other doctors, treated the patient for three days using the Extended Fan Palm technique, Invisible Needles, and Vibrating Palm technique. In this particular case, the doctors used the same points as in the previously mentioned case to cultivate the patient's Yuan Qi, adding points Bl-23, GV-4, CV-4, and CV-8. The patient was treated twice a day for 15 minutes, both morning and evening.

On the fourth day, the patient regained consciousness, and the treatment was continued once a day for a month using the Conception and Governing Vessel circulation points (to move the Qi along the Microcosmic Orbit), in addition to points on the arms including LI-4, LI-11, LI-15, TB-5, and TB-14 points.

When treating the lower limbs, he used GB-30, GB-31, GB-34, Sp-6, Sp-10, and St-41 points. The patient was given prescriptions and homework, specific to her constitution, state of consciousness, and motor control.



Figure 52.1. Common Points used for Coma Revival

The patient gradually regained movement in her limbs. Once the patient could move her limbs, she was given Dynamic Qigong to increase the flow of energy to her extremities. This included meditations and exercises that used guided imagery to regain muscle cellular memory. After two months, the treatment time was changed to every other month until the patient was fully restored.

FACIAL PARALYSIS (BELLS PALSY)

This condition is known as the sudden onset of unilateral facial paralysis.

ETIOLOGY

The patient experiences the swelling of the seventh facial nerve due to the External Wind and Cold invasion.

SYMPTOMS

The disease is characterized by hemiparalysis of the face which manifests as numbness of the affected area, deviation of the eye and mouth, distorted mouth with the corners tilted on the healthy side, and a half closed eye with dacryorrhea (excess tear flow).

TREATMENT

For this type of paralysis, it is important that the Qigong doctor treat the patient as soon as possible. The shorter the duration time from the initial onset and the treatment, the more successful the therapy tends to be.

1. Begin by purging the Toxic Qi out from the patient's face and head area, dredging the Toxic Qi down the arm and out the LI-4 point.
2. Using the Extended Fan Palm hand technique, emit Qi into the affected area, guiding the Qi to circulate in the Microcosmic Orbit from the anterior to the posterior of the patient's head.
3. Finally, initiate the Fire Cycle Microcosmic Orbit to regulate the patient's Qi.

TREATMENT MODIFICATIONS

- For treatment of the first stage of paralysis, the doctor is advised to apply gentle Pressing and Kneading techniques to the patient's face before using the Extended Fan Palm hand technique.
- To treat patients whose paralysis has remained in a chronic state, the doctor is advised to use deep pressing and kneading techniques before using the Vibrating Palm technique.

PRESCRIPTIONS AND HOMEWORK

1. Have the patient massage the affected side of the face from the corner of the mouth to the ear and forehead, down over the side of the ear and down the side of the neck 81 times.
2. The patient then focuses on specific areas on the face, circle massaging with the tips of the thumbs for 24 times.
3. Finally, the patient is given the Wash the Face and Massage the Head exercise to perform for 18 times (see Chapter 39).

MULTIPLE-SCLEROSIS (MS)

In Chinese medicine, multiple sclerosis is considered a type of Atrophy Syndrome. It is an inflammatory disease of the central nervous system in which infiltrating lymphocytes (predominantly T cells and macrophages) deteriorate the myelin sheath of nerves. Its pathology consists in the partial destruction of the myelin sheath around the spinal cord, brain and optic nerves.

ETIOLOGY

Multiple sclerosis is suspected to be an autoimmune disease, somehow linked to a viral infection originating from an invasion of External Dampness (especially in the beginning stages). As the External Dampness invades the body it begins to obstruct the channels, causing heaviness, numbness, and tingling in the limbs.

Diet is another contributing factor. The excessive consumption of greasy fried foods, dairy foods, or Cold foods can impair the Spleen, leading to the formation of Dampness.

In the later stages of MS, excessive sexual activity can also be a contributing factor for weakening the body and escalating the disease's progression. Excessive sexual activity can weaken the patient's Kidneys, contributing to such symptoms as dizziness, blurred vision, urgency or hesitation of urination, and extreme weakness of the legs. If excessive Liver Yang develops, symptoms will also include stiffness of the legs, severe vertigo, and vomiting. In the later stages of development, Liver Wind can cause tremors and severe spasms of the patient's legs.

Clinically MS is categorized as either a passive aggressive type of disease, in which episodes of neurologic dysfunctions are followed by times of remission, or a steady progression of neurologic dysfunction.

SYMPTOMS

The symptoms of MS were once thought to develop gradually; however, this is not necessarily true. In about 40% of clinical cases, the onset may occur in less than a few hours. In about one half of the patients, at onset the symptoms include weakness, or numbness in one or more limbs; later, the tendon reflexes become hyperactive.

In young patients the first obvious symptom is often retrobulbar neuritis (inflammation of the nerves behind the eyeball) causing blurred vision. In older patients the most common symptom is weakness of the legs.

Patients may experience vertigo, retrobulbar or optic neuritis, double vision, unstable walking, vomiting, and difficulty urinating. Also included are numbness or tingling of the extremities, as well as periodical electric shocks radiating through the limbs. These symptoms may be due to optic nerve, brain stem, cerebellar and spinal cord involvement.

Traditional Chinese Medicine divides these symptoms into two categories of clinical manifestations: Damp Phlegm with Spleen Deficiency, and Liver and Kidney Deficiency.

Clinical manifestations in patients with Damp Phlegm and Spleen Deficiency include feeling weak and tired, dizzy, as well as numbness, tingling and feeling of heaviness in the legs.

Clinical manifestations of patients with Liver and Kidney Deficiency include progressive weakness of the back, legs and knees, blurred vision, dizziness, poor memory, and a hesitancy, or an urgency to urinate.

TREATMENT

There are two basic treatment patterns in Medical Qigong for multiple sclerosis. If the treatment is started within its early stages, the symptoms can be completely eliminated, and the progression of the disease indefinitely stopped. This, of course, must be done in conjunction with an alteration in the patient's eating habits (no red meat, processed meat, sugar additives, or high fat diary products). The patient should reduce the amount of sexual activity, get plenty of rest and exercise, and avoid allergy causing agents. Treatments are described as follows.

1. To treat a patient with Damp Phlegm and Spleen Deficiency, first resolve the Dampness by purging the patient's torso and extremities. Next Dredge the Toxic Qi down the legs and out the Sp-9, and Sp-6 points. After purging, emit Qi into the Yellow Court (CV-12) to tonify the Spleen. Finally tonify the patient's Lower Dantian and regulate his or her Microcosmic Orbit (Fire Cycle).
2. To treat a patient with Liver and Kidney Deficiency, first tonify the patient's Kidneys and Liver by emitting Qi into the patient's Mingmen and Lower Dantian. Next emit energy into the patient's Bubbling Spring (Kd-1) points and direct the Qi to flow up the patient's Yin Channels into the patient's Lower Dantian and Kidney area. Finally, regulate the patient's Microcosmic Orbit (Fire Cycle).

PRESCRIPTIONS AND HOMEWORK

Patients often benefit from Medical Qigong exercises such as the Descending the Yang and Ascending the Yin Technique, Walking Therapy, Daoist Five Organ Exercises, as well as Taijiquan (Tai Chi Chuan) practice. One prescription I have found to be very effective in treating MS patients is as follows.

1. Have the patient sit in a chair, feet flat on the ground, hands resting on the knees, anal sphincter closed, tongue touching the upper palate while inhaling and exhaling through the nose.
2. While using natural breathing, the patient focuses on the Lower Dantian to create an energy ball. With each inhalation, divine healing light is absorbed into the body and stored in the Lower Dantian. With each exhalation, this healing light radiates within the Lower Dantian. After several minutes, the patient notices the Lower Dantian becoming full of heat and light.
3. Next, the patient imagines the energy ball in the Lower Dantian leaving the body through the coccyx into the Earth upon exhalation. Upon inhalation, the patient imagines the energy flowing up the center of both legs and filling the Lower Dantian. This meditation should continue for at least 20 to 30 minutes per sitting.

CHAPTER 53
QI EMISSION THERAPY FOR PSYCHOLOGY

INTRODUCTION TO ENERGETIC PSYCHOLOGY

The object of Chinese psychology is to study and understand the interplay of internal and external events on physical, mental, emotional, energetic and spiritual dimensions of human existence. These interactions include the human qualities and characteristics, as well as the fundamental attributes that exist and evolve within the changing environment and evolutionary development of nature. These interactions at the most fundamental level can be viewed as the transformational interactions of Yin into Yang, and Yang into Yin vibrational energy.

All matter vibrates regardless of its form (gaseous, liquid, solid, or in a transitional state such as ice melting into water). The human body receives these vibrations through the skin, eyes, ears, nose, and mouth, and records them in its cells. The mind interprets these incoming vibrations as images, sounds, smells, and sensations, and organizes these into memories. The extent to which the mind interprets the incoming data, depends upon the level of consciousness and awareness of the individual at the time of the recording. In times of danger, alertness normally increases and consciousness either expands or focuses more sharply until the danger is past; or if an injury occurs consciousness and awareness may be lost (e.g., a car crash).

When a Qigong doctor, attunes his or her vibrations to the patient's energetic field and emits Qi, the body's cells responsible for storing the vibrations are stimulated. The doctor's intention to heal the patient by releasing traumatic memories, combined with his or her projected Qi, often causes the patient to relive the original traumatic experience as the recorded vibrations are released. The Qigong doctor (still in tune with the patient's energy) is receptive to the patient's reaction and is able to interpret the released energy in the form of images, sensations, smells, sounds, and emotions while they are being reexperienced by the patient. If the doctor is sufficiently attuned, he or she may even pick up the conscious thoughts of the patient during this process.

As doctors tune in to their patients' cell emissions they are also able to project their own thoughts and interpretations of these memories back to the patients. This creates a positive feedback system, wherein the doctors' thoughts can influence the patients' thoughts and emotional reactions. Through thought transmission, Qigong doctors are often able to break the vicious cycle of negative thinking that so often leads to disease in the body.

In Western psychology, it is believed that a person's tendency to interpret events - even negative imaginary events (e.g., assigning malicious intentions to peoples' actions), can result in a self-fulfilling prophecy. By assuming and expecting the worst behavior in people, such a person always feels on the defensive and provokes others around him or herself to anger or irritation, thus reinforcing the negative viewpoint.

Chinese energetic medicine adds to this simple behavioral understanding of self-fulfilling prophesies, a new level of comprehension based on energetic interchange between people. When someone observes, or imagines, a specific negative thing happening, certain brain cells record this information in the form of vibrations. These vibrations can be received by another person's corresponding brain cells and projected back to the original sender, reinforcing the negative interpretation of the event(s). If this feedback loop continues - an imaginary wrong may become manifest, i.e., the negative event imagined actually occurs.

It is believed that different cells store different types of information, received in the form of vibrations. The silent thought communications between doctors and patients is believed to involve different sets of cells than those used to receive and record emanations of divine energy. These cells interrelate with the patient's emotional changes that are stored and released from the Yin and Yang organs and tissues, and are expressed through the patient's Wu Jing Shen.

The patient's ontology also includes the patient's growth and self-realization in relationship to the Wu Jing Shen (Five Essence Spirits) and the emotions stored within the body's Yin and Yang organs. Each of the Five Yin Organs has a Yin and a Yang aspect within its energetic substance, as well as emotional factors, and dynamic interconnections. The Yin and Yang aspects give rise to the Creative and Controlling Cycles and the Five Yin organs with their associated elements and emotional energies (Figure 53.1 - 53.3).

Summary of the Five Elements		
Wood	Liver	Anger, irritation and rage
Fire	Heart	Joy, happiness, pleasure and excitement
Earth	Spleen	Worry, sympathy, anxiety, contemplation and meditation
Metal	Lungs	Grief, sorrow, anguish, distress and heartache
Water	Kidneys	Fear, terror, panic, horror and fright

Figure 53.1. The Five Elements, Organs and Acquired Emotions

THE EMOTIONAL ENERGY STORED WITHIN THE FIVE YIN ORGANS

Traditional Chinese Medicine classifies the etiology of diseases into Internal and External physical, mental, emotional, energetic, and spiritual influences. In Chinese psychology, the primary focus is placed on the "root" of the energetic/emotional dysfunction. The root of the energetic/emotional dysfunction is often the unprocessed emotions which are stored in their associated organs. Once the patients' mental and emotional symptoms have been alleviated, the energy that was being used to suppress the excessive emotions, is then freed to be focused on their physical healing.

Traditional Chinese Medicine also recognizes the power of thoughts, images (including psychotic delusions and hallucinations), and fantasies to generate and release emotions. Qigong doctors study these images and emotional reactions of attraction or aversion to evaluate their patient's condition. When traumatic memories and emotions are suppressed over a long period of time, or are still fresh in the mind, any minor incident can precipitate a tidal wave of emotions. A rapid influx of thoughts and images sweeps through the mind, too fast for the conscious brain to register. These thoughts and images are of past painful experiences, and are loaded with emotional energy. Getting cut off by someone on the freeway, for example, may cause a momentary reaction of surprise, or an explosive enduring rage, depending upon the condition of the Five Yin Organs. In the latter case, the driver is overwhelmed by the Liver's sudden release of rage, triggered by the traumatic images and emotions from the past.

Clinical pathology is considered an Excess or Deficiency of the emotions at the level of the Five-Elements and their corresponding organs. The Excess or Deficiency of an internal organ can cause a release of thoughts or images that sweep through the patient's mind, bringing a sudden emotional response. In some instances these emotions first affect a specific organ, and then the entire balance of energy, as the first organ's energetic field deteriorates or adversely expands. When emotionally charged Qi is trapped within the tissues of the patient's internal organs, it travels through the channels, affecting the metabolic order of the viscera, glands and nervous system.

Creative Cycle			
Wood	Anger	Creates Joy	Fire
Fire	Joy	Creates Worry	Earth
Earth	Worry	Creates Grief	Metal
Metal	Grief	Creates Fear	Water
Water	Fear	Creates Anger	Wood

Figure 53.2. The Creative Cycle

Controlling Cycle			
Wood	Anger	Controls Worry	Earth
Earth	Worry	Controls Fear	Water
Water	Fear	Controls Joy	Fire
Fire	Joy	Controls Grief	Metal
Metal	Grief	Controls Anger	Wood

Figure 53.3. The Controlling Cycle

Emotions consist of energetic light that is either tempered and softened by the patient's belief structure and energetic fields. When the emotions and life purpose are in harmony, the Wu Jing Shen become focused; the Hun and Po do not disperse, grief and anger do not arise, and the Five Yin Organs effectively combat pathogenic influences. If this energetic light becomes unstable, i.e., too Excessive or Deficient, the patient's inner strength and individual nature begins to undergo dramatic changes.

The body's internal organs and their relationship to the Five Elements are as follows.

EXCESSIVE ANGER INJURES THE LIVER (WOOD)

The Chinese character for anger (Nu) is depicted by the Heart ideograph underneath two characters, a woman (placed on the left) and someone who has the upper hand (placed on the right). It expresses the feeling and frustration of an enslaved woman being dominated by someone.

PATHOLOGICAL MANIFESTATIONS OF ANGER

Pathological anger is considered the perverse movement of the element Wood. Anger is a generated force that has the potential to unleash explosive amounts of Qi, pushing the energetic manifestations to the extreme.

THE YIN AND YANG ASPECTS OF ANGER

The emotion of anger can be divided into Yin and Yang tendencies. The Yang type of anger can burst out due to accumulated pressure, resulting in the upward flow of massive amounts of Blood and Qi. The Yin type of anger implodes, remaining buried or held inside, thereby causing internal agitation and dissatisfaction which generates blockages.

The Liver's negative nature is one of being stubborn and rude; its positive nature is one of being compassionate, unselfish, kind, and merciful. The rising of Heat from the Liver's Qi corresponds to the level of anger; since the Liver stores the Blood and the Blood stores the Hun (Ethereal Soul). When the Hun leaves the body due to anger and rage, the animal nature of the Po take over. As the individual's Liver Fire rises, it causes the eyes and the face to become red. Liver Fire can also injure the Liver as well as the Blood, bile and Body Fluids associated with this organ.

ANGER AFFECTING THE LIVER

When Liver Qi becomes depleted it retracts, causing the emotion of fear to arise. When Liver Qi fills to Excess, the result is progressive restlessness, irritability, anger, and rage. In some instances, these emotions affect the entire balance of energy so that the organ begins to deteriorate.

Anger can cause trembling of the entire body due to the Liver's control of the tendons and ligaments.

When an individual experiences any type of boundary invasion, the Liver Qi triggers the Heart (Shen) to recall from its long term memories past traumas (containing both anger and fear). At the same time, the Liver also drains the Kidney Qi to meet the apparent life-threatening situation; this prepares the body for the flight or fight response. The power of the emotional response causes the Heart to go into shock and prevents the Shen from directing the mind. Thus another trauma is experienced by the patient's interpretation of the event (e.g., getting cut off on the road) and will automatically trigger an exaggerated emotional response in the future.

Given that the Liver is the mother of the Heart (responsible for long term memory) and the child of the Kidneys (responsible for short term memory), the Liver can drain the Kidneys and flood the Heart with anger, causing one's mind to go blank and the face to turn red.

ANGER AFFECTING THE SPLEEN AND STOMACH

Anger can damage the Spleen and Stomach, causing digestive problems, loss of appetite, and a sour taste in the mouth. These symptoms are directly related to the level of anger.

ENERGETIC PATTERN OF ANGER

The Qi pattern of anger has a very hot energy associated with it. When discharged, this hot energy swells up like a tidal wave expanding from behind the person's back over the head (Figure 53.4). It crests over the head and rushes forward like a wild animal attacking. The emotion also travels from the groin up the back of the body and out through the eyes.

Grief controls anger as metal cuts wood. At the root of anger is pain and sorrow. The anger protects the patient from feeling the initial hurt that festers like an infected wound. When the doctor lances the wound, allowing the toxic anger to drain, the uncovered original hurt can heal cleanly. Anger is transformed to sorrow and grief. The compassionate, non-judgmental attitude of the doctor allows the patient to grieve openly. The release of toxic anger and pain enables the patient to listen to the Hun. By focusing on the patient's emotional hurt from past experiences, which are the root of his or her anger, a shift from anger to hurt occurs. This exchange of emotions allows the patient to confront the hurtful past memories and discharge the toxic anger.



Figure 53.4. Anger rushes from the Liver over the back like a tidal wave, causing the Qi to ascend.

EXCESSIVE JOY INJURES THE HEART (FIRE)

The Chinese character for joy (Le) is depicted by the ideograph of a large drum, framed by bells mounted on a wooden stand. It expresses the feeling of rhythmical ceremonies and excitation. The character gives the image of a hand beating a drum during a festival (this same character is used for music).

THE YIN AND YANG ASPECTS OF JOY

When the Heart's emotions are balanced, they can be experienced as love, joy, happiness, excitement, and pleasure. This warmth radiates through the body affecting the expansion of free and easy Qi circulation. Joy is communicated and felt throughout the body, mind and soul.

PATHOLOGICAL MANIFESTATIONS OF JOY

Excessive joy and laughter can injure the Heart and scatter the spirit; the Qi becomes congested and the Heart flutters erratically. When the Heart Qi becomes depleted, it can no longer control the Lungs: the emotion of grief arises, and when the Qi fills to Excess, hysteria results. Water extinguishes Fire, therefore the emotion of fear controls the emotion of joy. By supporting a hysterical patient to become aware of his or her underlying fears, the doctor can startle the patient into a sense of sobriety.

Pathological joy and laughter are considered the perverse movement of the element Fire. If the patient's Fire becomes uncontrollable, the Qi - which expands outward towards the periphery - will cause the patient to become hysterical. After Fire has exhausted the patient's life-force, it leaves the patient exhausted, dazed, and disenchanted. The Heart's negative nature is confused, doubtful, and greedy; the positive nature is open-minded, loving, non-judgemental, and trustful.

ENERGETIC PATTERN OF JOY

Joyful feelings make the body's Qi become soft and relaxed. This energetic pattern is expansive, and causes a slower movement of the Qi. As the Heart controls the blood vessels and stores the Shen, a joyful spirit produces a clear, calm mind and a healthy body. This energy bubbles out from the center core of the body and ripples out in all directions (Figure 53.5). A light energy gently flows from the recipient back to the person expressing the emotion. While in this state, the patient's head is usually held erect, the face is full of color, and the limbs are relaxed.



Figure 53.5. Joy bubbles out from the center core of the body, rippling out in all directions, causing the Qi to slow its flow.

EXCESSIVE WORRY INJURES THE SPLEEN (EARTH)

When the Spleen Qi becomes depleted, all four limbs lose their strength and the Five Yin Organs become unstable. When the Spleen Qi becomes Excessive, the body becomes swollen and the flow of urine and menses loses its smoothness.

THE YIN AND YANG ASPECTS OF WORRY

The emotions associated with the Spleen are relative to the energy expended in contemplation, meditation, anticipation, and worry. Too much worry and thought produces Qi stagnation. A stagnant condition causes Stomach disorders, such as poor appetite, indigestion, ulcers, constipation, or diarrhea. Stagnation can also block the Shen, which is responsible for emotional and mental balance, and thus result in a lack of common sense. The Spleen's negative nature is suspicious and self-centered; the positive nature is truthful, sincere, and compromising.

WORRY AFFECTING THE MEMORY

The Spleen stores the Yi, and the Yi stores ideas. The Spleen transfers short term memory to the Kidneys; the Kidneys later transfers the acquired memory to the Heart, which is responsible for long term memory. In trauma victims, the Kidneys' role in transferring memories, can also account for the loss of memories that are too terrible to accept, since these memories are transferred along with great fear, or fail to get transferred at all.

THE ENERGETIC PATTERN OF WORRY

When one is worried, the energy comes up from the Earth and congests in the Middle Dantian area, thus weakening the Wei Qi (Figure 53.6).

CONTROLLING THE EMOTION OF WORRY

Because the element Wood controls the element Earth, the emotion of anger controls worry. It is very important that any anger uncovered be directed at the root cause, and not at the doctor who is trying to help a patient end a negative pattern. The doctor will gently challenge toxic belief structures held by the patient, until the patient begins to confront whatever issue is at the root of the anger.

When the patient becomes angry with the doctor, it is generally a condition known as "transference." If and when transference arises, the Qigong doctor can ask the patient, "Who do I remind you of right now?" or "When was the last time you felt this way?" Trace the patient's feelings as far back as possible. If the doctor gets mad at the patient, it is called "countertransference." Both transference and countertransference can involve any emotion (e.g., falling in love, feeling afraid, etc.).

EXCESSIVE SADNESS AND GRIEF INJURES THE LUNGS (METAL)

The Chinese character for sadness (Bei) is depicted by the Heart ideograph underneath the character for the back (placed on the top). It portrays a picture of a person who has turned his or her back on the true feelings of the Heart. The Chinese character for grief (Ai) is depicted by the mouth ideograph (wailing, groaning, and lamenting) placed within the center of the character of someone dressed in a special garment for mourning. Pathological grief is considered the perverse movement of the element Metal.

When grief is experienced, its natural movement of condensation begins to compress the Heart, interfering with Blood circulation. This obstruction destroys both the respiratory flow of the Lungs, as well as the body's liquids. The Lungs store the Qi, the Qi stores the Po (Corporeal Soul). When the Lung Qi becomes depleted, shortness of breath develops. When the Lung Qi becomes excessive, the result is a feeling of discomfort in the chest, panting, and difficult breathing.



Figure 53.6. Worry binds the Qi, causing the Qi to stagnate.

THE YIN AND YANG ASPECTS OF GRIEF

The feelings associated with the Lungs are sadness, melancholy, grief, sorrow, and anxiety. The negative nature is cunning, jealousy, and pessimism; the positive nature is generosity and righteousness. In the Five Elemental Controlling Cycle, the Lungs (Metal) affect the Liver (Wood). Excessive sadness from the Lungs can cause the Liver Qi to stagnate the Blood (Metal Overcontrolling Wood), leading to possible intercostal and hypochondriac pain, bloating, and depression.

GRIEF'S AFFECT ON THE INTERNAL ORGANS

Grief disperses the Qi, and thus injures the Lungs. Crying can lead to the release of toxic anger (that suppresses the feelings of sorrow) and grief. Depression and despair may also be manifestations of abnormal Liver Qi stagnation. When grief from the Lungs is excessive, the Spleen may be affected (this almost always happens after a major loss, such as a death in the family).

THE ENERGETIC PATTERN OF GRIEF

The external energetic patterns of grief and sorrow have a heavy, downward moving energy (Figure 53.7). The internal energetic patterns and manifestations of grief have a very thick, sticky energy, and a denseness like gelatin. Long periods of extreme grief also injure the Heart, Pericardium, and the Triple Burner Channels.

CONTROLLING THE EMOTION OF GRIEF

Because Fire melts Metal, the emotion of joy controls grief. The grieving process is a very important part of healing; however, chronic grief can be extremely detrimental, and when it is extreme and prolonged it can lead to spiritual oppression or possession. If the survivor cannot accept the death, he or she may prevent the departure of the loved one's spirit for many years on end. The patient may beg the Eternal Soul not to leave and cling with unrelenting grief to the lost one's energy. This type of dependency deepens, rather than lessens over time, as the patient opens more to receive the loved one's spiritual essence. In so doing, other Gui (spirits) are given power to enter as well.

After a death of someone loved, the patient may consciously suppress any joy or pleasure. The patient may believe that to allow any relief to suffering is tantamount to a betrayal of the deceased. This belief structure must be addressed by the doctor and patient. Establishing a sense of empathy with the patient will provide a safe environment for the patient to release the emotion of grief. The doctor can work towards empowering the patient to begin to recognize times of joy, and learn, or remember, how to count his or her blessings, to let go of sadness and grief, and reclaim lost joy.

Grief may give way to despair and anxiety. Because anxiety suppresses respiration, anxiety lowers the body's resistance to pathogenic factors by weakening the Wei Qi; anxiety also damages the Large Intestine, resulting in symptoms that range from constipation to ulcerative colitis.



Figure 53.7. Grief causes the Qi to become obstructed.

Just as too much grief can cause inappropriate laughter, or gallows humor; too much laughter masks the accumulated and suppressed grief. Gallows humor is a syndrome whereby the patient laughs instead of grieving about hurtful past, or current experiences. Gallows humor is a defence mechanism of the patient's denial. Grief and humor are examples of opposites (Yin and Yang) transforming into each other.

The concern in dealing with many grieving people (pertaining to the death of a patient's mate or close friend, etc.) is that the patient may be using grief to suppress other unresolved emotions, such as: guilt, fear and loneliness.

1. Fear of forgetting the deceased voice, appearance, etc. may be due to feelings of guilt over not having expressed enough love towards the person when it was possible to do so.
2. Guilt over any expressed feelings of joy or happiness, may seem morally wrong because they cannot be shared by the departed.
3. Guilt may arise from too many hurtful things said, or too many things left unsaid to the departed.
4. Guilt over never having had the chance to really say good-bye (as with victims of accidents and sudden death) may become all consuming.
5. Loneliness and isolation may result from the loss of friendships.

6. Worry that loss of income and security may cause financial difficulties and health problems may cause the patient to cling to the past.

To assist the patient to heal from these toxic beliefs, the doctor prescribes creative visualizations, such as the following.

"Imagine, see and feel yourself and your loved one clothed in your astral bodies. Embrace and express your feelings and thoughts, knowing that these will be heard and received. Listen to your loved one's answer.

Ask forgiveness for any cruel remarks or failures to be as loving as you wish you could have been. Visualize your loved one accepting the request for forgiveness; embrace with love, and release him/her to be with God with your blessings."

In cases where the patients could not attend the funeral, have the patient imagine the funeral and perform a ritual closure (e.g., lighting a candle at home and saying a prayer).

Finally, encourage the patient to give him or herself permission to experience some joy in life and to go on living.

EXCESSIVE FEAR INJURES THE KIDNEYS (WATER)

The Chinese character for fear (Kong) is depicted by the Heart ideograph underneath two characters, a structure (placed on the left) and repeated strokes by the small blows of a hammer (placed on the right).

THE AFFECT OF FEAR ON THE INTERNAL ORGANS

The Kidneys store the Jing, the Jing stores the Zhi (actions that the mind expresses). Pathological fear is considered the perverse movement of the element Water. Fear is the unrestrained sinking and uncontrolled descent of Water Qi. When the Shen of the Heart is no longer supported by the Kidneys' Jing, the Shen leaves its residence. This results in the emotional release of panic. If the Heart Fire becomes weak, the Kidney Water rapidly draws downward and freezes. Insecurity, hesitation, immobility, and paralysis ensue. If the Heart Fire become Deficient, it cannot radiate warmth, causing the patient to crouch and hide.



Figure 53.8. Fear causes the Qi to move inward and downward.

If the Kidney Yin is Deficient, the vision deteriorates, there is a ringing in the ears, dizziness, night sweats, and nocturnal emissions. If the Kidney Yang is Deficient, the Mingmen Fire becomes Deficient, and causes a counter-flow of energy affecting the hearing. Kidney Yang Deficiency also results in shortness of breath, cold limbs, and impotency. When the Kidney Qi becomes Excessive, swelling occurs and the Five Yin Organs become unstable. The feelings associated with the Kidneys are fear, paranoia, and panic.

THE YIN AND YANG ASPECTS OF THE KIDNEYS

The Kidneys' negative nature is arrogant, troublesome, and ignorant; the positive nature is peaceful, soft, and tender. Fear can cause loss of Bladder control, weakening of the knees, renal failure, and permanent damage to the Kidneys. It can injure the Heart, affecting the speech, eyes, and the Shen.

When fear injures the Kidneys, this can affect the Liver, causing muscle spasms, trembling, and disruption of the menses cycle. When the Gall Bladder is affected, decision-making becomes more difficult.

THE ENERGETIC PATTERN OF FEAR

The energetic pattern of fear is very cold and implodes into the center of the body, drawing all the energies inward and downward. Fear travels from the eyes down the front of the body into the groin (Figure 53.8).

Because Earth absorbs Water, contemplation controls fear. Therefore, the doctor can help the patient control the fear through visualization and meditation. The purpose of the visualization is to resolve and reprogram the patient's thinking patterns.

THE EMOTION OF FRIGHT

The emotion of fright is distinguishable from fear by the sudden, unexpected shock to the system. The Chinese character for fright (Ju) is depicted by the ideograph of a small bird opening its frightened eyes, in fear, anxiety, and dread. Fright startles the Shen, which then scatters the Qi and injures the Heart. Persistent fright causes damage to the Kidney Qi and results in a negative cycle of chronic fear.

FIVE YIN ORGAN EMOTIONAL RESPONSES

The common ingredient in any emotional dysfunction is the power element maintaining it. Holding on to original traumas, whether consciously or unconsciously, requires a great deal of energy. It is possible to stop this negative pattern by releasing the toxic emotional energy, thereby creating the opportunity for the mind, body, and spirit to heal. A new pattern of harmonious balance can be maintained, however, only after the old dysfunctional patterns are consciously recognized during their occurrence. Old habits die hard; new patterns require time and continuous effort before becoming as automatic as the previous dysfunctional habits. Every emotion is meant to serve a positive function, even anger, fear, and grief. Patients often require reminding of this fact. Every emotion also has its darker side when repressed for too long and when avoided at all costs.

1. Learning how and when to express anger is as important as not holding on to it for extended periods of time. Anger serves as a warning sign that personal boundaries are being violated, threatened, wounded, or that injustices are being committed. Patients must be taught better communication skills so they need not resort to screaming or insulting others to protect themselves. Appropriate assertiveness skills must be learned, and may require either psychotherapy, or classes in assertiveness training. Patients must also learn how to ask for what they need and desire, without expecting those close to them to mind read. Without learning how to set appropriate boundaries, without the ability to say "no" to those who take advantage of them, they will fall into the old habit of accumulating resentments; or they will alienate their employer, friends, and family through unguarded candor when angry.
   - On its negative side, anger can cause rage and destructive patterns (both internally and externally).
   - On its positive side, anger can cause constructive boundary setting and the righting of wrongs.
2. Fear, like anger, serves as a warning sign. Fear informs patients when they are in danger, so that appropriate measures can be taken to insure safety and survival. Some patients do not recognize the danger signals until it is too late to avoid falling victim to unscrupulous people. Some may require counseling and instruction in how to establish healthy relationships, and in how to identify individuals who are potential abusers before it becomes too late to avoid the ensuing violence.
   - On its negative side, fear can cause disabling panic.
   - On its positive side, fear can cause an awareness of the need for self-protection.
3. Joy in excess can lead to disharmony. Nervous laughter, or always playing the clown to gain acceptance, can be extremely difficult to unlearn. Often professional help is needed to increase socialization skills and self-esteem.



Figure 53.9. The Five Element Cycles

- On its negative side, joy can cause hysteria.
- On its positive side, joy can be a source of happiness to the spirit.

4. Sorrow is necessary at times to motivate patients to change. The old self must periodically die to make room for new experiences and learning. Risking sorrow is part of the process of bonding and maturing. Sadness is often a signal of imbalance in the patient's life, indicating insufficient rest or recreation, and far too much work.
   - On its negative side, sorrow can cause self-pity, rather than compassion for oneself.
   - On its positive side, sorrow can release distress.
5. Worry and anxiety are normal reactions to change. When these emotions become pathological in intensity of duration, patients may need professional help in the form of medication (e.g., for obsessive compulsive disorders), and/or psychotherapy (e.g., in the case of generalized anxiety disorder and posttraumatic stress disorder).
   - On its negative side, worry can cause great anxiety.
   - On its positive side, worry can be a motivating source for change.

The healing stages used in Medical Qigong Therapy employ these transitions in order to assist the patient's emotional and spiritual growth.

The picture in Figure 53.9 summarizes the Five Elements, their associated organs, and their associated emotions.

The cycles serve a functional importance for emotional transitions. The elements can be arranged in a number of ways. For clinical purposes, the main emphasis is on the Creative and Controlling Cycles.

EMOTIONAL DISHARMONY

It is becoming more common in the Western belief system that if a patient concentrates his or her mind and emotions on healing the illness, they can accelerate the recovery. Some Western research suggests that when the patient stops thinking and trains the mind to relax (reaching an alpha state), the healing is accelerated.

Emotional disharmony can resonate and penetrate one's entire being, thereby creating a vicious

Major Organ Disharmony	→	Emotional Disharmony
↑		↓
Environmental Disharmony	←	Disturbed Behavior

Figure 53.10. The Cycle of Emotional Disharmony

circle affecting the body, mind, emotion, energy, and spirit. As evidenced by the diagram (Figure 53.10), any disharmony in one of these four factors can trigger the cycle.

This vicious circle can be set in motion by any major disharmony, be it environmental, physical, emotional, or behavioral. Once in motion the disease can feed on itself. The power of emotional energy generated can at times overwhelm the conscious mind. The mind then has three options: to give in to the emotional tidal wave, to become eventually paralyzed through the effort of controlling it, or simply to deny that anything is wrong.

When emotional energy is suppressed it accumulates within the body, causing the Qi to flow incorrectly or to condense. The unresolved emotions cause chronic blocks in the body, particularly in the back, neck, Stomach, and intestinal areas. This toxic energy stored in the muscles and organs leads to tension, stress, and illness. The root cause of chronically tense shoulder muscles, for example, can be traced to: tensing the muscles to suppress the emotion(s), a strong negative belief system, and an accumulation of unresolved past traumatic memories, which continue to resurface.

Unless the initial cause of tension is released, the tissue memory associated with the initial trauma will repeat its programmed pattern, resulting in chronic tension and pain. Painful and negative emotions are not the only emotions suppressed. Many people also suppress feelings of joy and love. Most do so out of fear, guilt, and sense of unworthiness. Some do so out of religious beliefs, believing that suffering is good for the soul, or that the are being punished by God for sins of omission and / or commission to test their faith.

All emotions are triggered by sensory associations with pleasant and unpleasant past memories. In many cases patients are completely unaware of the triggering smell, image, sensation, or sound. To them it seems that the trauma, or memory, resurfaces from nowhere. This inability to pinpoint the trigger mechanism may indicate the progression of the patient's illness. Patients suffering from panic attacks, for example, have no idea what stimulus may have caused the overwhelming terror that they feel. Quite often panic attacks increase in frequency, partly out of the anticipatory fears of having another one, and partly due to their fear spreading and generalizing.

The first panic attack may have taken place in a restaurant, triggered by one of the five senses registering similar data (a smell or image for instance) which occurred during one of their traumatic memories. Henceforth they will avoid this restaurant, or perhaps all restaurants because new data has been added to the original trigger mechanism. New smells and images occurring during the attack may now stimulate the old memory of the trauma. Eventually, such patients may become home bound as they try to limit themselves to only safe places; their panic attacks have generalized to agoraphobia (fear of places or situations from which escape might be difficult or embarrassing). Each panic attack requires more energy to suppress both the original trauma and all of the new traumas added to it from surfacing.

Outgoing, successful people can thus transform themselves into anxiety ridden hermits. They can also develop physical symptoms, or turn to alcohol and drugs in attempts to cope. In less extreme mental / emotional diseases, changes in skin colors, tone of voice, mannerisms, and nervous twitches may manifest. As the mind tries to suppress uncomfortable emotions, these unresolved feelings often manifest as physical symptoms.

At times, however, the symptoms manifest more on the mental level, as in obsessive compulsive disorder. The logical mind, failing to completely suppress the emotion, may develop frantic obsessive thinking patterns, that seem to take on a life of their own. Some patients may obsess about dying, even if they seem by Western medical standards to be physically completely healthy; or they may obsess about killing their own child, or forgetting to lock all the doors when leaving the house and so on. They have no control over their repeating thoughts, and are aware of the unrealistic and unreasonable nature of these obsessions. Nevertheless, they are helpless to stop themselves.

Obsessions often manifest with compulsive addictions such as washing the hands so often during the day that they are raw and bleeding, or pulling out the hair on their head, or folding and unfolding their clothing. Any ordinary daily activity may turn into a compulsion, requiring the patients to continue performing a meaningless action again and again.

Another frequent disease found in traumatized patients goes by the name of posttraumatic stress disorder. Patients suffering from this condition have flash backs, i.e., they can not stop having moments of releasing the original traumas again and again with full intensity.

In posttraumatic stress disorder patients' symptoms are often disabling. Anxiety is chronic, they are in a state of hyper-alertness. They have become good at disassociating from their body, since it has become a very uncomfortable place to be. The Shen wanders and the patients may, or may not, be aware of where their spirit goes or what it experiences at these times. In extreme cases the ego fractures, usually during early childhood, and a full blown identity disorder (previously called multiple personality disorder) ensues.

Patients suffering from obsessive compulsive disorders, posttraumatic stress disorder, agoraphobia and panic attacks, or identity disorders should be referred out for extra help to a mental health professional specializing in these disorders.

Ideally, the doctor can teach and encourage the patient to get in touch with their body, and learn how to achieve and maintain a balance between the physical, mental and emotional planes. The doctor can also teach the patients how to transition detrimental energy into a higher level of consciousness, when the patients become aware of an unpleasant emotion. When patients learn how to channel their own energy in a more healthy way, the cycle of reliving the past can be broken. A negative emotion can be transmuted and expressed as a positive emotion; emotional energy can be converted to positive life-force energy.

EMOTIONAL FREQUENCY RESONATION

When the Qigong doctors are appropriately sensitive to the patients' emotional transitions, they are able to detect, and recognize, recurring energetic patterns. These energetic patterns are in constant resonation throughout the body's tissues. As patients shift their emotional thinking, their energetic frequency resonation (the body's Hz rhythm) shifts. These different emotions establish specific patterns of energy in the body. Each individual has a brain wave pattern that is as unique as their fingerprints. According to Richard Lee, director of the China Healthway's Institute, individuals resonate at different frequencies depending on their state of consciousness. Mr. Lee's research reveals the following.

1. Those motivated by fear and instinct will resonate at the delta wavelength, between 0 and 4 Hz (hertz, i.e., cycles per second). This level of energetic resonation, as measured by an electroencephalograph (EEG), is normal in an awake infant and a sleeping adult. This delta wavelength, however, indicates brain pathology in adults that are awake.
2. Those motivated by attachment and desire will resonate at the theta wavelength, between 4 - 7 Hz. This level of energetic resonation is generally common in children and in adults in the early stages of sleep. This frequency range also occurs when an individual creates mental imagery, and often manifests when a person is involved in deep altered states of consciousness. This level of energetic resonation also occurs in many brain disorders.
3. Those motivated by service and compassion will resonate at the alpha wavelength, between 8 and 13 Hz. These low amplitude alpha waves usually occur when the brain is in a calm, and the mind is relaxed (in a state of wakefulness). It was discovered that Qigong masters emit energy within this frequency range.
4. Those motivated by organization and planning will resonate at the beta wavelength, between 14 and 25 Hz. This level of energetic

resonation usually occurs when the nervous system is active and the body is awake. It manifests during sensory input and mental activity. This frequency range is usually common for those suffering from nervous overload and excessive thinking.

When the patients' vibratory rate shifts towards the alpha rhythm, they begin to experience deep relaxation and clarity of mind. Relief from chronic pain and symptoms associated with low energy is achieved.

According to Richard Lee, the infrasonic sound produced by Qigong masters is effective because it causes decreased resonation in the theta and beta ranges. This simultaneously decreases attachments and desires, calms the emotions, and reduces excess thinking, thereby freeing the patient's vital sources to be redirected towards healing.

DIFFERENTIATION OF PSYCHO-EMOTIONAL DISORDERS

Traditional Chinese Medicine has, for centuries, recognized the fact that psycho-emotional states, energy, and physical health are intertwined. In the Huang Di Nei Jing, the emperor's medical adviser, Qi Po, outlined the Internal Factors (emotions) as primary causes of disease.

Within the context of Traditional Chinese Medicine, Medical Qigong therapy is useful for treating many types of psycho-emotional disorders. Qi emission therapy can be used to calm the patients' Shen, as well as accelerate the patients' recovery time. In China, psycho-emotional problems are commonly called Jing Shen disorders and are differentiated as follows: Obstructed Shen, Unsettled Shen, and Weakened Shen.

1. Obstructed Shen is a condition due to the Shen becoming obstructed with Phlegm, or in mild cases, becoming obstructed by Qi or Blood. Symptoms are characterized by confused thinking, clouding of the mind, and in severe cases, complete loss of touch with reality. Degrees of severity range from very mild disorders to severe schizophrenia or mania.
2. Unsettled Shen is a condition due to the Shen becoming unsettled from Blood or Yin Deficiency (in mild cases), Qi stagnation, Blood Stasis, Fire, Empty Heat, Phlegm Fire, or Internal Wind. Symptoms are characterized by agitation, restlessness, and anxiety.
3. Weakened Shen is a condition due to Deficiency of Qi, Yang, Blood, or Yin. Symptoms are characterized by depression, mental exhaustion, and melancholy (dysthymia).

ETIOLOGY

The cause for psycho-emotional disorders can range from a variety of factors, including prenatal or postnatal constitutional imbalance, diet, unbalanced sexual activity, overwork, alcohol or drug abuse, trauma, stress, emotional immaturity, and instability, as well as a lack of love or spiritual perspective.

TREATMENT PRINCIPLES

There is a considerable degree of overlap among Jing Shen disorder symptoms. Therefore, the treatment principle must be based on a clear distinction between Excess and Deficiency, as well as the cause (root) and manifestation (branch) of the symptoms. The main treatment principles are as follows:

1. Nourish the Heart and calm the Shen to treat Shen weakness due to Qi, Yin, Yang, Blood, or Body Fluids Deficiency.
2. Purge the Excess, move stagnation, and calm the Shen to treat Shen obstruction or Shen agitation (unsettled Shen) due to Excess conditions of Qi, Blood, Phlegm, and/or Fire stagnation.
3. Purge the Excess, nourish the Heart and calm the Shen to treat Shen obstruction due to Yin Deficiency with Empty Heat.
4. Resolve the Phlegm, open the Heart's orifices, and calm the Shen to treat Shen obstruction due to Phlegm or Phlegm Fire.
5. Sink and calm the Shen to treat unsettled Shen due to rising Qi.

The term "calm the Shen" is used to describe the treatment principles in all psycho-emotional disorders. It should be understood to mean not only calming the mind, as in anxiety, but also lifting the patient's mood (as in depression), or clearing the mind (as in schizophrenia or mania).

SELF-TREATMENT PRESCRIPTIONS FOR PSYCHO-EMOTIONAL DISORDERS

Most meditations are difficult for patients with psycho-emotional disorders due to several factors. One factor is the problem of maintaining focused attention, as well as retaining the memory of specific medical Qigong prescriptions. The success, or failure of the treatment will also depend on the severity of the disorder.

POINT MEDITATION FOR EMOTIONAL TRAUMA

In China, Channel Point meditation is used in conjunction with the Massage Tapping method for treating patients with conditions such as anxieties, phobias, and addictions. In acupuncture, 135 of the original 365 acupuncture points are used to treat mental, emotional, energetic, and spiritual disharmonies. In fact, many of the "new" points can be applied for the treatment of Jing Shen disorders.

The cause of fear and anxiety is the disruption to the body's energy system from emotional trauma. When a patient is focusing on a particular anxiety or fear, the Shen becomes disrupted, and the energetic harmony of the body becomes unbalanced. This energetic imbalance causes certain physical reactions within the patient (abnormal breathing, pulse, etc.), and results in pathological behaviors.

TREATING EMOTIONAL ANXIETIES, PHOBIAS, AND ADDICTIONS

To treat anxieties, phobias, and addictions, the doctor encourages the patient to focus attention on the specific fears, or cravings for the particular addiction, to initiate a maximum emotional charge of distress. When the patient reaches maximum emotional distress, the doctor calls out specific channel points for the patient to tap.

The patient is given a specific mantra to repeat while tapping, to discharge the accumulated emotionally charged Qi, such as; "I accept this fear (or other emotion or craving)" or "I am being healed." The treatment continues for five to ten minutes, as the patient focuses on feeling the distress as much as possible, until all the trapped emotion has been discharged. Some energetic points commonly chosen for treating emotional anxieties, phobias, and addictions are GV-26, Ht-7, and Pc-6. These specific points are used to draw the energetic charge away from the Heart and into the extremities; this action facilitates calming the patient's Shen.

The initial tapping method, in conjunction with vivid imagination and positive affirmation, disperses the energy away from the Heart and other organs and calms the Shen. The spontaneous dispersing of the emotional charge, stored within the patient's tissues, releases all feelings of stress and anxiety. This type of guided Tapping Meditation therapy not only reduces and disperses the patient's emotional trauma, but also causes an energetic reprogramming within the patient's psychophysical dynamics.

MEDICAL QIGONG TREATMENT OF THE PHOBIA AND ANXIETY OF DEMON POSSESSION

These specific treatments are used in China to treat specific mental, and emotional disorders, that lead the patient to imagine that they are being haunted by spirit demons. In rectifying this type of psycho-emotional disorder, it is recommended that the Qigong doctor proceed as follows.

1. Perform Channel Point therapy to open the energetic points of the Eight Extraordinary Vessels (Figure 53.11).
2. Press and knead the Baihui GV-20, Dazhui GV-14, Lingtai GV-10, and Feishu Bl-13 points. Then apply the Extended Fan Palm or Sword Fingers method (see Chapter 33), using the Pulling and Shaking manipulations (see Chapter 34) to emit and conduct Qi along the Governing Vessel.
3. Press and knead the following channel points Baihui GV-20, Yintang (Ex.Pt.), Renzhong GV-26, Tinggong SI-19, Jiachè St-6, Quchi LI-11, Hegu LI-4, Weizhong Bl-40, and Chengshan Bl-57 points.
4. Apply the Sword Finger technique, using the Vibrating and Shaking manipulations to emit Qi into the Jiuwei CV-15 and Zhongwan CV-12 points and conduct Qi along the Conception Vessel to return it to the Lower Dantian.

MEDICAL QIGONG TREATMENT FOR SPECIFIC SPIRIT/GHOST HALLUCINATIONS

These specific treatments are also used in


GV-20
Yin Tang
SI-19
St-6
GV-26
SI-19
St-6
CV-15
CV-12
LI-11
LI-11
LI-4
LI-4
GV-20
GV-14
Bl-13
Bl-13
GV-10
Bl-40
Bl-57

Figure 53.11. Medical Qigong Channel Point Therapy for the Treatment of Energetic Delusions

China to treat specific mental and emotional disorders that lead the patient to see spirit/ghost hallucinations. The Qigong doctor may additionally treat the patient according to the following therapeutic point stimulation:

- If the patient is disoriented, sees and hears floating corpse ghosts, or hears crying ghosts, treat the Tianfu Lu-3 points.
- If the patient is manic-depressed, sees and hears ghosts talking, treat the Tianchuang SI-16 points.
- If the patient is having seizures, sees and hears ghosts talking, treat the Tianzhu Bl-10 points.
- If the patient is manic, suicidal with incessant wild talking and actions, treat the Fengfu GV-16 point.
- If the patient experiences chronic nightmares, confused dreaming, and restless sleep, treat the Tianyou TB-16 points.

MEDICAL QIGONG TREATMENT FOR DEMON OR SPIRIT POSSESSION

Since the creation of Traditional Chinese Medicine in the People's Republic of China, the notion of spirits has been down-played. However, within the confines of the Medical Qigong clinics, I have been fortunate enough to be able to discuss with several Qigong doctors the cause, effect, and treatment of demon and spirit possession.

These following Thirteen Ghost Points are listed in the *Thousand Ducat Formulas*, prescribed by the famous physician Dr. Sun Simiao in the 7th century China, and were once used for the treatment of spirit possession (Figure 53.12). Today in China, these points are now used in the TCM clinics for the treatment of manic and depressive mental disorders, as well as for treating epilepsy. In extreme manic cases (with Heat) the doctor bleeds all of these points as well as all twelve Jing-Well points on the patient's hands. Classically, the patient is treated by bleeding each of these points, or by inserting an acupuncture needle into each point and then immediately withdrawing it. These Ghost Points are stimulated in a sequence of progressive point therapy, wrapping and enfolding the patient's body in five consecutive circles.

1. The Guigong (Ghost Palace), also known as the Renzhong GV-26 (Middle of Man) point, is the first point to be stimulated and is treated to calm the Shen and clear the brain.
2. The Guixin (Ghost Faith), also known as the Shaoshang Lu-11 (Lesser Metal's Note) points on both thumbs, are treated to calm the Shen and restore Collapsed Yang.
3. The Gullei (Ghost Fortress), also known as the Yinbai Sp-1 (Hidden Clarity) points on both big toes, are treated to calm the Shen, clear the brain, in order to instill clarity of thought and mind.

These first three points are used to complete the energetic pass of the first circle, covering the head, tips of the thumbs and tips of the big toes. The GV-26 point is considered the meeting point of Yin and Yang in the body, while the Lu-11 points on both hands and the Sp-1 points on both feet are located on the body's Hand and Foot Tai Yin Channels.

Next, the following two points are used to complete the second circle:

4. The Guixin (Ghost Heart), also known as the Daling Pc-7 (Big Mound) points on both wrists, are treated to calm the Shen and clear the brain.
5. The Guilu (Ghost Path), also known as the Shenmai Bl-62 (Extending Vessel) points under both outside ankles, are treated to calm the Shen.

The Ghost Heart and Ghost Path points complete the energetic pass of the second circle, covering and wrapping the patient's wrists and ankles. The Pc-7 points on the wrists are located on the body's Hand Jue Yin, and the Bl-62 points on the outside of the ankles are located on the body's Foot Tai Yang Channel points.

The following set of four points are stimulated to complete the energetic pass of the third circle:

6. The Guizhen (Ghost Pillow), also known as the Fengfu GV-16 (Wind's Palace) point just below the occiput, is treated to clear the brain.
7. The Guichuang (Ghost's Bed), also known as the Jiache St-6 (Jaw Vehicle) points on both sides of the jaw, are treated to dispel Wind and Cold and to clear Heat.
8. The Guishi (Ghost Market), also known as the Chengqiang CV-24 (Receiving Liquid) point under the lower lip, is stimulated to treat mental disorders, dispel Wind and Cold, clear


GV-23
GV-26
St-6
St-6
CV-24
LI-11
Lu-11
Lu-11
Pc-8
Pc-8
Jade Gate
Sp-1
GV-16
Pc-7
CV-1
Bl-62
Bl-62

Figure 53.12. Medical Qigong Treatment for Spirit Possession

Heat, and to transform Dampness and Phlegm.

9. The Guicu (Ghost Cave), also known as the Laogong Pc-8 (Palace of Labor) points at the center of both palms, are stimulated to treat mental disorders and to clear the brain.

These four points complete the energetic pass of the third circle, by covering and wrapping the patient's head, then drawing the energy into the center of the patient's palms. The GV-16 point on the back of the patient's head is located on the back gate of the Upper Dantian, the St-6 points are located on the sides of the mandible, and the CV-24 point is located in the depression in the center of the patient's mentolabial groove (jaw).

The next two points complete the energetic pass of the fourth circle:

10. The Guitang (Ghost Hall), also known as the Shangxing GV-23 (Upper Star) point, is treated to brighten the Shen and clear Heat.
11. The Guicang (Ghost Store), also known as the Yumentou (Jade Gate) in women, and Yinxiafeng (Below the Hidden Seam) in men, is used to treat mental disorders. The Jade Gate is located at the opening of the vagina, the Below the Hidden Seam is located in the Huiyin area in men.

These two points complete the energetic pass of the fourth circle, by covering and wrapping the patient's body from the head to the lower perineum. The GV-23 point is located on the anterior hairline, at the top of the patient's forehead, and the Ghost Store point is located in the lower perineum.

The following two points are stimulated to complete the fifth energetic pass:

12. The Guitui (Ghost Leg), also known as the Quchi LI-11 (Crooked Pool) points, are treated in order to drain the pathogenic influences from the Lungs and to calm the Po (Corporeal Soul).
13. The Guifeng (Ghost Seal), also known as the Haiquan (Sea Spring) and She Xia Zhong Feng (Under Tongue Middle Frenulum) are two Extra points located below the tongue. They are stimulated in order to treat mental disorders.

These final two points complete the energetic pass of the fifth circle, by covering and wrapping the patient's body from the arms to the head. The LI-11 points are located in the depression on the lateral end of the elbow crease, and the Haiquan Sea Spring points are located under the tongue.

TREATING PHOBIAS AND DEPRESSION USING "THE WINDOWS OF THE SKY" POINTS

If we observe the body as a figure 8, with the head being the upper portion and the torso being the lower portion, the neck would represent the area where the two circles meet. The points and orifices of the head, face and neck are like great windows in which Qi moves.

The trunk of the body is considered Earth and the realm of the physical; the head pertains to Heaven and the realm of the spirit. The neck is where all of the classic "window" points are located. The neck is the junction between Heaven and Earth, and is considered the Earth's window to Heaven. With the exception of Lu-3 (upper arm) and Pc-1 (chest), eight of the ten Windows of the Sky points are located on the neck itself, and seven of the ten points have the word Tian (Heaven) as part of their name.

Over the last quarter century, the Chinese have used the Windows of the Sky points in treating such psychological disorders as depression and phobias. In the Qigong clinic, we look for three indications before prescribing the Windows to the Sky points.

1. According to the Nei Jing, the Windows of the Sky points are used when the Yang Qi is unable to ascend to the patient's head. The result is that the patient will have physical symptoms in the head or Heart (i.e., loss of hearing, or pain described as being behind the Heart.
2. The second indication is that there is something missing in the Heavenly aspect of the patient's spiritual life. When the patient becomes stuck in their own negative patterns, these particular points can be used to open a window of hope by bringing into the patient's body the illuminating light from Heaven.

   In these cases, the patient's disconnection from emotions and spiritual insight is due to the chronic negative patterns that block the descent of Heavenly light.

3. The third indication is a constant attitude of despondency by the patient. This behavior is not in accordance with his or her own values and beliefs, but the patient cannot control this pattern. Some patients know that something is amiss but cannot discern the source of the problem.

The Window points induce a hypnagogic state (a transitional state between sleeping and awaking) that allows some patients to experience out-of-body projection and past life regressions.

TREATMENT

When treating patients with the Windows of the Sky points, the Qigong doctor should use slow, gentle pressure on the skin to dip into the tissues, and then proceed with pure intention. The ten Windows of the Sky points are described as follows.

1. The Tian Fu Lu-3 (Heaven's Residence) point is sometimes called the Celestial Palace. The word Heaven represents divinity, clarity of vision, and the sense of the spirit (Figure 53.13). This point has a powerful psychological effect on all emotional problems deriving from Lung Qi disharmonies (e.g., depression, claustrophobia, agoraphobia, mental confusion, and forgetfulness).
2. The Fu Tu LI-18 (Support the Prominence) point is also known as Support and Rush Out. It is used on patients who feel out of touch with their own inner strength (Figure 53.14). This point relieves coughing, resolves Phlegm, and disperses masses (cysts and tumors) in the neck area. It is also used to treat a patient's inability to speak.
3. The Tian You TB-16 (Heaven's Opening) point can be used to calm the patient of anxieties and to soothe Heart palpitations (Figure 53.15). This point is also used for dizziness, sudden deafness, and diminished visual acuity.
4. Tian Zhu Bl-10 (Heaven's Pillar) is a Sea of Qi point. It is used to clear the brain, open the orifices, brighten the patient's eyes, and re-



Figure 53.13. Heaven's Residence



Figure 53.14. Support the Prominence



Figure 53.15. Heaven's Opening

move obstructions from the channels. The energy that moves and is located at these points has to do with the patient's will, ambition, and inner fortitude (Figure 53.16). Energetic dysfunction located at the Heaven's Pillar may manifest as deep sadness or anxiety, and be related to a lack of inner strength, or will. This point is also used when the patient's feet are unable to support the body.

5. Ren Ying St-9 (Man's Welcome) is a Sea of Qi point. The ancient Chinese philosophers associated this area of the body with Man in the triad of Heaven, Man, and Earth. This point is known as a place where energy is being welcomed into the body (Figure 53.17). It is a very sedating point of Blood and Qi, and is used to reduce blood pressure. Opening up this point allows the patient to become receptive to nurturing energy (Ying Qi). The doctor should be gentle and only treat one side at a time. It is also used to disperse Lung Qi and Regulate Qi.
6. The Tian Tu CV-22 (Heaven's Rushing Out) point is also known as the Celestial Chimney, and is an area where the body's internal energy and spirit leaves the body through sound (Figure 53.18). Heaven Rushing Out is related to emotional and spiritual expression, and is relevant when the patient's spiritual self (i.e., the individual's life purpose) is not being supported by physical actions (his or her code of conduct). In other words, the patient's life purpose is not in alignment with the patient's behavior. This point can also be used to regulate the Lungs, stimulate the descending action of the Lung Qi, clear Heat, and resolve Phlegm.
7. Feng Fu GV-16 (Wind's Palace) is a Sea of Marrow point, and is also a very good point for strengthening the body's Wei Qi (Figure 53.19). This point connects directly to the brain, and is used to eliminate Wind, clear the mind, open the sensory orifices, and benefit the energetic function of the brain (used for treating convulsions, epilepsy, or palsy).
8. The Tian Chuang SI-16 (Heaven's Window)



Figure 53.16. Heaven's Pillar



Figure 53.17. Man's Welcome



Figure 53.18. Heaven's Rushing Out



Figure 53.19. Wind's Palace

point is used to open a window to Heaven, especially in patients who need help in perceiving how to change a negative behavior pattern into a productive and harmonious one (Figure 53.20). This point is used for dispersing the Liver's Qi and for eliminating buzzing, pain, or deafness of the ears.

9. The Tian Rong SI-17 (Heaven's Appearance) point is also known as the Celestial Countenance. This point is where the Small Intestine's Channel Qi is received by, and enters into, the Heaven's Body Chamber (the head or skull). It can be used to produce a strong movement of energy from the head downward into the body.

   This point is used in spiritual emergencies, when patients have lost their connection with Earth energy, and remain blissed out, and oblivious of reality. It is often used in cases of addictions, once the patient is conscious of the addiction (Figure 53.21). This point is also used in order to expel Excess Fire and remove obstructions from the patient's channels.

10. The Tian Chi Pc-1 (Heaven's Pond) point is also known as the Celestial Pool. The term pond represents a source, resource, or reservoir of energy for the spirit. This point influences the area where the Shen gathers or pools in the chest region (Figure 53.22). It is capable of enhancing the transition from normal consciousness to feelings of being submerged in a sea of energy.

    It affects the Heart and Pericardium which govern the Shen, and whose symbolic home is Heaven. The doctor uses this point to remove the patient's street armor, and to begin the process of opening the patient's Heart protector at its source. This point is also used to disperse the Lungs' Qi, expand and relax the chest, regulate Qi, and clear Heat.

    Note: Because of the proximity of the breast tissue, the Heavenly Spring points (Pc-2) are sometimes used in women instead of the Heaven's Pond points (Figure 53.23). The Heavenly Spring point is located halfway down the anterior face of the biceps muscle.



Figure 53.20. Heaven's Window



Figure 53.21. Heaven's Appearance



Figure 53.22. Heaven's Pond



Figure 53.23. Heavenly Spring

TREATING PSYCHO-EMOTIONAL DISORDERS RELATED TO STRESS

The following prescriptions are used in order to assist the patient in dealing with suppressed anger and grief, for additional prescriptions used in order to treat emotional problems (see Chapter 19).

TREATING EXCESS LIVER FIRE AND THE REPRESSION OF ANGER

One of the most common problems observed in the clinic is Excess Liver Fire. One of the many causes of Excess Liver Fire is the repression of anger and a suppression of the spiritual components of the Hun. When anger is suppressed, its volatile Heat will sometimes attack and drain the Kidney Yin (Water). Therefore, Excess Liver Fire is generally related to a Deficiency of the Kidney Yin energy. When Qigong doctors reduce the Excess Liver Heat, they must also increase the patient's supply of Kidney Yin (Water) Qi (see note #2).

If the Liver's Yin becomes Deficient, the body's Qi will not be able to keep the patient's Internal Fire from rising. This causes the Yang to rise to the patient's head, and the Blood to become Deficient. The patient becomes irritable as the Liver's Yang begins to rise. This in turn, causes high blood pressure, which is associated with such problems as headaches, dizziness, insomnia, tinnitus, hypertension, and migraine headaches. Deficient Liver Yin, if unchecked, turns into Liver Fire, which causes severe high blood pressure, and heats the patient's Blood. As the Blood heats, it becomes Deficient, and causes Liver Wind. Unchecked Deficient Liver Yin results in shaking and trembling. If the Liver Wind mixes with the patient's Phlegm, it blocks the patient's channels resulting in paralysis, aphasia, memory problems, and eventually stroke.

The method of treatment is chosen according to the patient's syndromes:

1. For patients sensitive to energy, use Medical Qigong therapy while the patient is lying supine.
   - Purge and disperse Qi from the patient's Liver;
   - Pull pathogenic Qi out the patient's Liver Channels;
   - Tonify the patient's Kidneys through the Lower Dantian;
   - Give Liver purging and Kidney tonification prescriptions and homework.
2. For patients not sensitive to energy, use Tui Na and An Mo in conjunction with Medical Qigong therapy while the patient is lying prone.
   - Purge and reduce the Fire in the patient's Governing Vessel and Bladder Channels;
   - Start at the Mingmen and dredge the patient's Liver Fire, ending at the sacrum, using a counterclockwise circle rotation to reduce the Liver's Qi;
   - Give Liver purging and Kidney tonification prescriptions and homework.

Note #1. If the Liver Fire attacks the Stomach, resulting in vomiting and migraine headaches, have the patient lie supine. Because the Liver's Fire can travel transversely along the hypochondrium area, the Qigong doctor rocks and gently shakes the patient from the center of the thorax down to the Kidneys using intention, lead and disperse the Heat out from the patient's torso. Next, pull the Stomach Qi down and out of the patient's feet.

Note #2. Tonify the patient's Kidneys by using Jing Point therapy on the following points: St-36, GB-34, Sp-6, Lv-3, and Kd-1 on both sides of the body.

BEATING THE BAG AND SHOUTING TO DETOXIFY LIVER HEAT AND RELEASE TRAPPED ANGER AND RAGE

Beating the Bag and Shouting is the most common Medical Qigong homework given to patients with Excessive Liver Fire. The concept of Beating the Bag and Shouting is best comprehended when the function and flow of Liver Qi Heat is understood. When striking the bag and shouting, the shaking movements of the body will:

- facilitate an energetic discharge from the Liver organ,
- help alleviate pressure stored within the Liver organ itself (detoxifying suppressed feelings), and
- purge the body of Excess Liver Heat.

It is important for the patients to understand, that when shouting and striking on the surface of the bag (while focusing their intention deep into the bag's center), they are releasing deep seated pathogenic rage. This is why it is prohibited for patients to substitute such things as pillows, bed, etc., for the bag. If a patient takes a pillow and pounds it, for example, screaming and shouting to release the aggression, he or she is releasing and discharging pathogenic Qi into the pillow. If after releasing this Toxic Qi into the pillow, it is returned to the bed for a person to sleep on, the patient will reabsorb the discharged energy. To avoid this occurrence, patients are encouraged to set aside a space where they can safely discharge internal pathogenic Qi (preferably outdoors). This is similar to isolating and storing garbage away from living quarters.

While striking the bag, in addition to feelings of anger and rage, sometimes the patient may start crying or experience overwhelming feelings of grief and despair. This is also a normal reaction to dispersing toxic emotion. It sometimes occurs while discharging Stagnant Liver Qi, because the Lungs, which store the emotion of grief, have the function of keeping the Liver organ in check, in accordance with the Five Elemental Controlling Cycle.

What the patient needs to perform this exercise is two wooden dowels (1–1.5 inches in diameter and three feet long), a large bag of rice from the grocery store, and some duct tape. Completely encase the bag of rice with the duct tape to prevent spilling. Place the bag on a table, or a hard surface, level with the Lower Dantian. Hold a dowel in each hand, strike the bag, and focus on the Liver's Qi traveling up the back, down the arms, and through the wooden dowels.

With each impact, imagine the body releasing Toxic Liver Qi into the bag. It is important for the patient to exhale completely and deeply from the lower abdomen when shouting and striking the bag. Sometimes the patient is encouraged to shout "no" or "stop." These words will help the patient to facilitate complete emotional discharging, while also reestablishing a patient's broken energetic/emotional boundary system.

Bag striking should be performed for 10–15 minutes to achieve maximum benefit. Afterwards patients may feel euphoric and exhausted due to the heightened endorphin activity now occurring within the tissues. If the patient still feels angry, he or she should try writing out the rest of the rage on paper, which is then discarded. In order to end the exercise, patients should sit for five minutes in quiet solitude. It is important for the patient to reflect on any emotional memories which have been released and brought back into consciousness. The patient may then begin sharing these feelings and memories with the doctor, and commence the process work for healing the unexpressed emotions.

Some patients may become absolutely horrified at themselves for getting so angry during bag beating that they feel terrified afterwards; especially if so much rage was built up that is seems there is no end to it. Often patients are forced to stop from overwhelming fatigue, aches, and pain caused by this purging exercise. If the patient allows the rage to build and never completely processes the rage, it may cause the patient to feel that without the anger he or she would literally cease to exist, or that he or she is innately evil. The patient may feel that he or she "is" the anger, and that the exercise is making it worse, and may strive to control the anger even more than before.

Some patients will get so mad, they will walk out on the Qigong doctor without processing anything. This unprocessed rage can be extremely dangerous, especially if the patient is prone to beating his or her mate, kids, or pets. Many people are completely unaware of how much anger they have suppressed. Some patients are like bottomless wells, especially patients with borderline personality disorder. Patients with this disorder should never be given this exercise, as it could lead to self-mutilation. Refer such patients out for psychotherapy.

In our culture, women are not allowed to express anger, much less rage. If the patient has ever been beaten, or witnessed a loved one being abused, he or she may believe that he or she is just like the abuser, and that he or she has been lying to him or herself about not being bad and may become suicidal.

The Qigong doctor should never prescribe this exercise unless he or she fully understands the complexity of the patient's circumstances. Some patients require a period of time, in a safe place, with supervision to help them deal with such intense emotions.

Other possible reactions might be that the patient goes into stronger denial of the rage, blames the doctor for causing him or her to beat their mate or children, or blames the doctor for causing the rage. The Qigong doctor must make sure there is sufficient time for the patient to process all the reactions aroused. The patient must not feel hurried.

ANGER MANAGEMENT

With some patients it is best to start them off journalizing the anger, not in a dairy, but on sheets of paper. They address the letters to the person, or persons, with whom they are angry. They continue writing until all the anger has been discharged. They are not to mail the letters, or give them to the addressee, or show them to anyone including the Qigong doctor. In writing the letter, they allow themselves to fully express the anger without judging themselves. The patient should not be concerned about grammar, foul language, etc. No matter how trivial the upsetting incident was, it should be written down. The flow of consciousness is initiated and continued until the end of the letter. No event (no matter how silly or insignificant) that comes to mind should be left unexpressed.

When finished, the letter is to be torn up, or safely burned in a ritual of healing and letting go (e.g., light some incense or candles, then blow them out after the paper has been incinerated). Symbolically the patient must let go of the anger for good, and that is why the letter is destroyed in a ritualistic act.

Only later, as the patient continues to practice this purging technique, slowly gaining control of the emotions, can the angry letters be kept for a few days and reread. In rereading the letters the patient engages his or her discriminating, judging faculties (i.e., "Was I right to get upset over this incident? Did I over-react? What did this incident remind me of from my childhood?"). This is a safe and very powerful method of discharging anger from the patient's body. The patient is encouraged and allowed to say everything he or she thinks of when writing, holding nothing back. It is nonthreatening, and allows the patient to come to understand him or herself better in time.

TREATING STAGNANT LUNG QI AND THE REPRESSION OF GRIEF

The Lungs dominate the Qi and respiration. A common problem observed in the clinic is stagnant, or obstructed Qi within the Lungs, from the toxic buildup of sorrow, grief, and worry. Sadness and sorrow can cause a Deficiency of Lung Qi, while worry can cause the Qi in the chest to stagnate. Stagnant Qi within the Lungs is usually directly or indirectly related to the suppression of emotional issues.

The right Lung is considered more Yang than the left Lung; it therefore tends to reflect, and sometimes manifests physically, any unresolved, or suppressed emotional conflicts experienced within the father-child relationship (or other main male figures in the patient's childhood). These unresolved emotional issues tend to carry over and help shape the nature of subsequent conflicts experienced in other male relationships. These ongoing emotional reactions provide a further opportunity in life to express, work through, and resolve these emotional issues.

The left Lung is considered more Yin and thus reflects emotional issues stemming from the mother-child relationship (or main female figure in childhood). The left Lung may likewise manifest these issues in subsequent female relationships.

Generally, cysts, tumors, or cancer originating in these corresponding regions reflect the emotional history. Because of these emotional patternings, the method of treatment for Lung diseases (that are Internally induced) is chosen according to the patient's syndromes in relationship to the root of the original trauma. After determining the specific Lung which dominates and manifests the patient's pathogenic condition, the Qigong doctor proceeds as follows.

1. For patients sensitive to energy, use Medical Qigong therapy while the patient is supine.
   - Disperse Qi over the patient's throat and Lungs;
   - Purge pathogenic Qi out the afflicted Lung Channel;
   - Tonify the patient's Spleen and Kidneys;
   - Prescribe Homework.
2. For patient's not sensitive to energy, use Medical Qigong therapy in conjunction with An Mo Qi therapy while the patient is supine.
   - Disperse Qi over the patient's throat and Lung area;
   - Purge pathogenic Qi out the afflicted Lung Channel;
   - Dredge Fire from the patient's Liver;
   - Tonify the patient's Spleen and Kidneys;
   - Prescribe Homework.

DRY CRYING TO DETOXIFY STAGNANT LUNG QI AND RELEASE TRAPPED SORROW AND GRIEF

The most common homework prescription given to patients with stagnant Lung Qi is the Dry Crying exercise. The concept of "dry crying" is best understood if we look back to when we were little children. When little children cry hard, they generally release full body resonances. They shake and undulate from the middle of the body, allowing the pain to resonate outwards. When children reach puberty, they learn (through parental or peer pressure) to suppress their feelings, and to restrain full body resonance, by tensing the muscles in the throat. The constant pressures from society, parents and peers, result in self-conscious feelings and shame regarding the loss of control over the emotions. The following exercise allows the patient to experience full body resonation and to release deeply suppressed emotions.



Figure 53.24. Dry Crying

Begin the exercise from a standing position. Stand with the feet more than shoulders width apart, toes pointing straight and the knees comfortably bent. With each hand, touch the thumb to the index finger to form a circle. Relax the arms letting them hang naturally. Close the anal sphincter, and breath naturally from the abdomen. Tilt the head backwards, opening the mouth wide, and relax the jaw. Allow the upper body to lean and bow backwards (without straining the spine), but stretching the psoas muscles. Hold this posture from 5 to 15 minutes, concentrating on relaxing the body, and allowing it to resonate (Figure 53.24).

The psoas muscles are located in the lower back and Mingmen area. They articulate from the transverse process of the lower lumbar vertebra. These muscles travel near the center of the abdomen down to the inner thigh. These particular muscles are associated with the storing and releasing of powerful emotions. As the psoas muscles stretch, the body begins to resonate and shake from the pelvic cavity upward. This action returns patients back to the preadolescent state of energy release, allowing them to detoxify deep seated grief within the tissues.

In order to complete the exercise, it is extremely important to ground. This prevents the uprooted toxic emotions from causing Qi stagnations in the throat and chest area. After holding the posture for the prescribed amount of time, slowly lean forward and tilt the chin down. Allow the arms to continue to hang naturally. Slowly lean forward until the hands touch the floor. Imagine Qi, flowing like water, from the torso out your arms, cleansing your body, sending the pathogenic Qi deep into the center of the Earth.

CONTRAINDICATIONS

Patients should avoid this particular exercise if they have previously injured their back. For patients who have difficulty with the stretching of the cervical or lumbar vertebrae, it is encouraged that they wear a cervical collar or lumbar support to prevent injury to the spine. Also, the exercise can be modified to allow the patient to sit comfortably on the edge of a chair while stretching the psoas muscles if the standing stretch is too difficult.

CHAPTER 54
QI EMISSION THERAPY FOR ONCOLOGY

HISTORY OF CANCER TREATMENTS

The ancient doctors of Traditional Chinese Medicine understood about the formation of tumors. The earliest records found were inscriptions recorded on "Oracles of Bone," unearthed from the ruins of the Yin Dynasty (16th–11th century B.C.). The word "ai" (cancer) first appeared in the Chinese Medical classic *Wei Ji Bao Shu* during the Song Dynasty, in the year 1171.

In Traditional Chinese Medicine, cysts, tumors, and cancers are considered multifaceted diseases, originating from imbalances in one or more of the five following sources: environmental, chemical, biological, physical, and psychological. According to the *General Treatise on the Etiology and Symptomatology of Diseases,* a tumor is one of the many diseases that responds to Dao Yin (Medical Qigong) exercises and meditations. To prevent the formation of cysts, tumors, or cancer, and to increase the strength of the immune system, Qigong doctors encourage patients to monitor their diet, maintain emotional stability, increase physical exercises through Medical Qigong prescriptions, and avoid exposure to pollutants.

From a Western Medical perspective, tumors and cancer are likewise considered multifaceted diseases. They are generally viewed as being created and formed through a constant bombardment, attack, and weakening of the tissues, caused by the following three factors:

- A congenital tendency towards specific types of tumors and cancers (inherited weakness);
- Exposure to radiation, environmental pollutants, and chemical poisoning, and
- An inability to repair weakened DNA, leading to uncontrolled replication.

In Traditional Chinese Medicine, cancer cells are considered "infant bodies" which absorb nourishment from the host (mother) body for their own growth; thus they are called "pathogenic or evil embryos." Cancer cells are actually components of the "original" or "mother" body.

CATEGORIZATION OF TUMORS

In Chinese Medicine, tumors and cancers are commonly referred to as "a retention of mass." Retention has the meaning of stagnation. Tumors and cancer originate from flowing substances within the body such as Qi, Blood, Phlegm, and food. These substances stagnate when they are attacked by pathogenic factors, and they gradually take on the form of a lump as a result of excessive accumulation. If the lump subsides spontaneously, it is commonly referred to as a cyst, or benign tumor. Many benign cysts and tumors, however, persist indefinitely.

BENIGN TUMORS

A benign tumor grows slowly, and can spontaneously stop growing, or disappear by itself. A benign tumor also grows in expansive ways. Its margin is clearly defined with firm boundaries, and is easily manipulated through palpation. There is no temperature differentiation between the skin surrounding a benign tumor and normal skin tissue.

Often, no symptoms surround the internal location of a benign tumor. As the tumor grows in certain areas of the patient's body, however, it can disrupt the functional activity of an affected organ. Benign tumors have been known to cause bleeding and inflammation. If the tumor is located within the endocrine glands, it can cause an abnormal function within the gland itself. A tumor located within an endocrine gland does not usually endanger the patient's life. Benign tumors can, however, become life threatening if the location compresses specific areas of the patient's brain or vital organs.



Figure 54.1. The Three Formations of Cancer Growth

MALIGNANT TUMORS

A malignant tumors grow very fast (potentially doubling every two months). Degeneration, festering, and hemorrhaging often accompany malignant tumors. A malignant tumor is infiltrative in its growth, with no clearly defined boundary. Its appearance is irregular and fastened (not easy to move through palpation). The skin temperature surrounding the malignant tumor is considered energetically Hot, as it is warmer than the normal surrounding tissue.

Most malignant tumors either metastasize to nearby, or distant areas of the body. The body's symptoms include fever, pain, anemia, fatigue, and general weakness. In many cases, if left untreated, they can cause death. Malignant tumors, and cancers can be divided into two main categories: a Carcinoma, and a Sarcoma.

1. A carcinoma is a malignant growth or tumor that occurs in the epithelial tissue (the outer surface or first layer of tissue that lines the body's cavities, as well as the principal tubes and passageways leading to the exterior of the body). Skin cancer, esophageal squamous cancer, adenocarcinoma of the Stomach, and breast cancer all belong to this type of carcinoma. A carcinoma may affect any organ, or part of the body, and may spread by direct extension, or indirectly through the lymphatic system and bloodstream.
2. A sarcoma is a malignant growth, or tumor, that occurs within the connective or mesenchymal tissue. It may affect the muscles, bones, fat, blood vessels, lymph system, Kidneys, Bladder, Liver, Lungs, Spleen, or parotid glands. Rhabdomyosarcoma (sarcoma of the muscles), osteosarcoma (sarcoma of the bones), and lymphosarcoma (sarcoma of the lymphatic system) all belong to this type of sarcoma.

THREE FORMATIONS OF CANCER GROWTH

According to Dr. Pan Mingji, Director of the Fuzhou Cancer Institute of Integration of Traditional Chinese and Western Medicine, there are three forms of cancer growth: Expansive Growth, Infiltrative Growth and Exophytic Growth (Figure 54.1).

1. Cancers of the Expansive Growth type consist of tumor cells crowded together on certain parts of the body. These cells proliferate, grow constantly, and expand towards the outside. The cells of the surrounding tissue form a wall to resist the tumor's expansion. The wall becomes the external membrane of the tumor, which has an evident boundary separating it from the normal tissue. Tumor growth begins in this way in the early stages of both benign tumors and malignant sarcomas.
2. Cancers of the Infiltrative Growth type consist of cells that not only group together, but, also separately invade the intercellular spaces, and tubular tissue of normal cells. They establish their foundation within the tissues, and proliferate daily, expanding outward with no boundary system between the cancer tumor and the normal tissue. Since there is no surrounding wall of membrane, the growth spreads in mass. Malignant tumors, especially carcinoma growth, infiltrate in this way.
3. Cancers of the Exophytic Growth type consist of cancer cells that occur on the skin, body cavity, or gastrointestinal mucosa; they often form on the surface of the body's tissues through papillary masses, projecting outwards on the skin and mucosa. Polyp, papilla-

shaped tumors, papilloma, gingival cancer, esophagal cancer, Stomach cancer, and intestinal cancer all grow in this way.

Benign tumors do not spread; they only grow in an expansive or exopathic way. The malignant tumor is different, however, as the cancer cells do not remain in their original location but expand from the mass outward. This expansion extends into other organs and tissues by way of the body's lymphatic plexus and blood circulation. This phenomenon is known as metastasizing.

ETIOLOGY, THE SIX PATHOGENIC EVILS THAT CAUSE CANCER

The following is an analysis of the causes of tumor formation. Traditional Chinese Medicine maintains the concept that a tumor is a systemic disease (affecting the whole body). It can be summarized as a disorder of the internal organs caused by emotional strains, and an imbalance of the viscera, that has allowed the pathogenic Evils to enter the body and obstruct the channels and collaterals. These pathogenic Evils cause problems, that may eventually lead to the stagnation of Blood and Qi and develop into tumors. The pathology of cancer is as follows: Qi stagnation, Blood stagnation, Retention of Toxic Dampness, Retention of Phlegm, Toxin Attack, and Weakness or Deficiency of Energy (Figure 54.2).



Figure 54.2. The Six Pathogenic Evils That Cause Cancer

1. Emotional strains, depression of Liver Qi, or External pathogenic Evil factors can lead to a stagnation of Qi. Long term Qi stagnation can cause stagnation of Blood, which eventually causes clots. It is known that pathogenic Cold and Heat, and the prevailing pathogenic Evil factors, inevitably cause Blood clots.
2. Since Blood and Qi flow together, the obstruction of Qi can lead to an interference in Blood circulation. This interference gradually leads to Blood stasis; Blood Stasis is always further complicated by stasis of Qi. Blood stasis is sometimes referred to as "Dead Blood," due to the fact that the Blood is not moving. When Dead Blood accumulates in a certain area of the body, it eventually develops into an immovable mass or lump.
3. A weakness of the Spleen and Stomach, as well as indigestion, can cause retention of fluid in the body. Long term fluid retention will produce toxic materials that can accumulate and form lumps.
4. Functional disorders of the Lungs and Spleen lead to poor digestion of watery food, and poor distribution of Body Fluids. Fluid retention causes Phlegm, especially when it is complicated by Excess Heat. If Phlegm is unable to move upward to be dispersed out of the body, it collects and stagnates. The stagnation of Phlegm in the Lung(s) leads to asthma. The stagnation of Phlegm in the Stomach causes gastric disorder and nausea. If Phlegm goes beneath the skin, it will take the form of a movable mass or lump.
5. Toxic Evils may come from poisonous external environments (exposure to chemicals, asbestos, ultraviolet rays, radiation, etc.) or may be generated by the stagnation of Excess Heat within the body. This Excessive Heat causes abnormal cell fusion and growth within the body, leading to cancer formation, and a systemic breakdown of normal cell growth.
6. Deficiency of both Qi and Blood, as well as a weakness of Yuan Qi, make the body more vulnerable and susceptible to the formation of new growth. When pathogenic Evils enter the body, they damage the Blood and Qi. If the Yuan Qi cannot be restored, the disease will lead to a vicious, destructive cycle, mak-

ing the individual more and more debilitated.

These six pathological changes may occur either alone or in combination: i.e., Qi and Blood stasis, Phlegm stagnation and Toxic Dampness, Phlegm stagnation and Blood stasis, a weakness of the body's Yuan Qi and strong pathogenic Evils.

The choice of which Medical Qigong therapy to use should be based on differentiation of symptoms and signs. Since cancers are primarily caused by emotional strains, strong pathogenic Evils, and a weakness of the patient's Yuan Qi, clinical therapy should be focused on tonifying the patient's Yuan Qi, and purging the Evil pathogenic factors.

EMOTIONAL COMPONENTS OF CANCER FORMATION

From the clinical perspective, if the cancer is internally induced through emotional suppression, there will be a series of emotional transitions the Qigong doctor will observe during its development. When there is an accumulation of negative emotions, for example, the patient's body begins to wall off this type of energy, and creates an energetic cyst, instead of dissipating and disposing of the Toxic Qi. The patient's suppressed internal emotions intensify the production and formation of the cyst, and feed the cancer cells, which result in an uncontrolled, rapid growth rate of these cells.

The body creates potential tumors and cancer cells every day. The macrophages or monocytes (large phagocytes) in the immune system aggressively attack and dissolve the cancer cells once the body becomes aware of them. Areas in the body, however, which are armored in denial, tend to attract and protect these distorted cells, allowing them to cluster and mass together.

Cancer cells can grow and accumulate wherever emotions are being repressed. The patient's denial maintains the constant unconscious flow of energy to these tissue areas. The phagocytes and other components of the immune system do not attack these toxic pockets of emotional energy, because of the patient's continuous denial of their existence. Consciousness and awareness exists even at the cellular level of the body. The continuous emotional energy bombarding the cells and tissues causes these tissues to go into an emotional state of shock. Emotional shock causes a release of endogenous opiates and corticosteroids, that deplete the white blood cells, and prevent the immune system from protecting the body. Because of the immune system's weakened state of resistance, infection and even the formation of cancer cells are now free to enter and coagulate within the tissue areas.

Scientific studies based in China, and the West, have shown that stress can stimulate the neuroendocrine system to the extent that it leads to depression of the immune system. Furthermore, the creation and growth of cancer can be influenced by stress. Removal of psychological stress alone can alter the neuro-immunologic functioning of the body to the extent that it can prevent and even change the course of cancer development.

In a patient with emotional blocks, chronic tension begins to interrupt the flow of Qi. If the emotional block is deep and long standing, this tension becomes constant. The capacity to express or discharge the trapped emotion becomes very difficult.

As the awareness dims, the natural communication between the conscious and subconscious mind breaks down. The original conscious decision to suppress certain emotions becomes a habit; it thus becomes an unconscious aberrant automatic function. When emotions are expressed, the conscious and subconscious mind are in harmony and synergized. When emotions are suppressed, the subconscious mind can no longer perform its job of healing the body; it diverts all its energy to shield the patient's denial system. Thus, the Shen itself, becomes misaligned with the patient's life purpose. The patient's posture, movements and lack of spiritual growth, reflect this misalignment. Changes also occur in skin temperature, body chemistry, and skin tone. The overall level of vital life force visibly drops.

Dr. Xu, at the Xi Yuan Hospital in Beijing, China, often pointed out that emotional upheaval, and the restriction of the breath, could cause the patient's energy to stagnate or deviate from its path. The deviated Qi draws more energy to its pathway, compounding the disease. The unstable emotional and mental focus of the patient further causes adverse effects to the body. Medical Qigong therapy and exercises expose the patient's deepest secrets, and thus reveal the underlying causes of the disease, which can then be treated. The patient's being is energized through his or her personal perceptions and belief structures. Therefore, it is necessary to change the patient's belief structure to increase the level of awareness and perceptual accuracy. The patient must be enabled to let go of suppressed emotions to fully experience deep emotional and spiritual changes. The Qigong doctor initiates the release of Toxic Qi to begin this healing process that can thereafter be maintained through appropriate prescriptions.

When cysts, tumors, or cancer are internally induced, they are formed from long-standing suppressed emotions which have become trapped within the tissue itself. These emotions usually consist of anger, guilt, grief, shame, and disappointment. The energetically formed cyst, or tumors, will remain walled off until the emotional energy is dissipated. Cysts, or tumors, can lodge themselves anywhere, penetrating deep into the major viscera causing visceral dysfunction; or they can superficially lodge themselves beneath the skin.

If the nature of the emotional energetic matrix (i.e., belief structure) is negative, the patient retains the energy of the injury, making it difficult to heal the trauma. If, however, the emotional matrix is positive, then the energy of the injury can be easily dispersed.

Once the Qigong doctor's energy reaches the cyst or tumor, the patient's energetic resonance supporting the tumor formation is interrupted. As the doctor continues to break up the cyst or tumor's physical mass, the frozen energetic pattern begins to unwind. The doctor continues to unravel the energetic mass until all the Heat has been released from the tissues, and the energetic pattern's unwinding is completed.

The underlying pathophysiology of healing can be broken down into four components:

1. The mind affects tissue matter through the emotions.
2. The emotions cause neuropeptides to be released.
3. The emotions (via the neuropeptides) influence the direction and movement of the immune cells (e.g., monocytes), sending them to various parts of the body.
4. The immune system (e.g., monocytes and phagocytes) heal the body.

The neuropeptide receptor sites are located on the immune cells, linking the body's immune system with the functions of the mind, emotions, and spirit. Neuropeptides are produced in response to the individual's state of mind and emotions; they influence the state of health of all the internal organs.

Through Dynamic Medical Qigong training, neuropeptides, in the form of endorphins, are released within the body's system. This release of energy and endorphins helps to facilitate the patient's healing.

Through the use of Medical Qigong therapy, exercises, and meditations, areas of denial and subconscious energetic patterning can be altered. The energetic matrix which supports the tumor(s) or cyst(s) thus dissolves.

When a healing session occurs, the Qigong doctor's external energy field envelops the patient's tissues, thus allowing the patient's cells to receive new information to reprogram the toxic energetic patterns. This reaction occurs providing the patient's tissues are open to receive the informational structures needed to either rebuild them, or disperse the disease's cell formation.

CANCER FORMATION AND THE PATIENT'S MIND, EMOTIONS, AND SPIRIT

Emotions strongly influence the increase or decrease of tumor size; therefore, it is important to regulate the patient's mind, emotions, and spirit. When the patient's mind, emotions and spirit are free from distractions and are in harmony, the patient is able to manage negative emotions. Regulating the Mind (whole body awareness and consciousness) is considered the primary Medical Qigong technique used for teaching patients how to avoid creating the dark abyss of negative emotions.

The patient must learn to let optimism prevail over pessimism. The practice of Medical Qigong not only cultivates vital energy and builds up the patient's health, but promotes the development of optimism through creating a quiescent mind. Tranquility and optimism improve circulation of Qi and Blood (which strengthens the immune system) thereby inhibiting cancer cells until they gradually perish.

While visiting in Maui, Hawaii, I came in contact with four people who had been diagnosed with terminal cancer, and had a life expectancy of two weeks according to their physicians. Each person had their own unique story as to how they had come to the Hawaiian Islands to die. What struck me as fascinating was the fact that each one of these individuals had either left successful but extremely stressful businesses, or long term abusive relationships. Each made amends the best they could with relationships from their past (those who had anger against them or those whom they had hurt). They had come to paradise to live their last weeks in peace. That was several years ago! It seems that upon resolving all personal conflict, and leaving their stressful environment, their cancers went into spontaneous remission. Each individual was now concentrated on enjoying the pleasures of a simpler life, and on focusing on their own spiritual growth.

STRESSFUL LIFE ACTIVITIES AND THE IMMUNE SYSTEM

Stressful life activities create a flood of adrenaline within the body. This occurs not only from the endings of the vertebral lumbar division at the core segment of the major internal organs, but also from the core of the adrenal gland in the medulla (which specifically is a sympathetic ganglion, and responds to stress by releasing adrenaline into the blood stream). Adrenaline spreads throughout the body and activates not only the body's sympathetic nervous system, but also the adrenal glands; the heart rate, respiratory rate, blood pressure, and Blood flow to the muscles are increased in response to the Fight or Flight Syndrome.

When the release of adrenaline causes the mind and body to react, the immune system must then seek to balance the chemical imbalances created within the body, before it can return to its normal job of monitoring cellular activity, and defending against pathogens. If a patient is already vulnerable to a specific disease, added stress causes the patient to get sick quicker. Meditation takes the patient out of the stress mode, deactivates the adrenal glands, and normalizes the function of the immune system.

An unstable life style is very stressful and can lead to depression and Qi deviations. Conflict produces stress which causes anxiety; chronic stress wears down the mind and body, which leads to anxiety, or depression. Stress begins with an overexcitement of the nervous system, slowly working its way deep into the body like wet cement. It causes the shoulders and upper back to become tense and rigid. Stress can result from happy occasions (such as weddings) and other normally pleasant events. When the patient's life style is not properly balanced, over time Qi deviations, and illness can result. The capacity to bear stress is related to the strength of the nerves. When stress levels surpass the nervous system's capacity to handle them, the nerves "break down"; this results in all sorts of physical, mental, and emotional disturbances. These disturbances, if unheeded, can eventually lead to organ malfunctions, cysts, tumors, cancer, and premature death. To avoid such states, a balance between work and rest must be maintained.

At a conference of the International Society for Neuro-immunomodulation (*The Effects of Stress and Depression on Physical Disease*), Dr. Philip Gold, of the National Institute of Mental Health stated that stress and depression send hormones (e.g., cortisol) flowing into the bloodstream. An imbalance of hormones, if unregulated, can:

- destroy the appetite,
- cripple the immune system,
- shut down the processes that repair tissue,
- inhibit sleeping patterns,
- break down bone density,
- aid the onset of infection, and
- instigate the growth of cancer cells.

An individual's emotional past determines his, or her, present state of health, both physical and emotional. Past emotional belief structures are responsible for both creating and healing diseases. Just as thoughts drift through the mind (but do not become active until they reside within a belief structure), so emotional wounding resides within the tissues and cells waiting to be activated by emotional upheavals. Our thoughts become form via choices, and manifest within the body.

In most societies, sharing traumatic wounds is often the first act of intimacy and bonding. Traumas provide a common ground for relationships, and support the pain structure that cements the relationship. People become addicted to empowering wounds, which in turn supports and empowers the disease. The exchange of painful personal traumas is reinforced by receiving sympathy and strong empathy, which binds rather than releases the pain from the tissues. Desire for sharing one's pain in order to receive love can lead to a habitual way of relating to those closest and dearest. When such individuals feel taken for granted, or unappreciated, they may immediately resort to sharing past traumas to illicit the desired response. When such techniques fail to elicit the desired response, a new wounding is experienced. Many of these individuals will continue to unconsciously create new traumas, in the hope that, this time, the desired outcome will be achieved. This in turn can become an addiction, empowering old wounds as it creates new ones, including illness. Thus, the spirit becomes divided to support the new belief structure (i.e., that pain and misery grin love and attention), and the life-force energy deviates from its assigned job of protecting the body, which creates illness. Setting the self up for new wounds is not a conscious process, but an unconscious one, which needs to be brought into the patient's awareness in order to be healed. Then and only then can the mind and spirit act as one unit, directing the body's Qi towards its proper function of healing.

Because energetic healing occurs in the present, not in the past, victims of past traumas will never heal if the energy continuously regresses to the armored traumatic belief structure.

USING MEDICAL QIGONG TO STRENGTHEN THE IMMUNE SYSTEM

Medical Qigong increases leukocyte production, stabilizes the body's blood pressure, and improves the immune function. The immune system is not so much an independent system, but is rather an interactive functional system throughout the body. Immune cells which live in the Blood and lymph fluid are commonly known as leukocytes (white blood cells); lymphocytes are a type of leukocytes that is created in the Spleen. The purpose of these cells is to work together to defend against pathogenic factors. The function of leukocytes and lymphocytes is to identify, ingest, destroy, and eliminate disease-causing organisms, as well as remove all dead, damaged, or irregular cells.

Immune cells are produced in the lymph tissue and red bone marrow, and are stored in the lymphatic organs and the Blood. To perform the function of protecting and cleaning, immune cells must circulate throughout the entire body through the capillaries and vessels that carry Blood and lymph fluid. Immune cells travel from the lymph nodes and the lymphatic organs of the thymus gland, Spleen, and tonsils, which are responsible for filtering the lymph fluid to remove impurities, and produce more lymph cells.

For an External pathogen to affect the body, it must first pass through protective layers of cells. Generally, the macrophages present within the tissues ingest the pathogens and dead tissues. Macrophages are reinforced by the action and movement of the body's Wei Qi. When a pathogenic intruder invades the body, the macrophages are often the first to attack the intruder. If the macrophages are not strong enough, more Blood and fluid are brought to the area, which contain more diverse immune cells. The increased fluid engorges the tissue, which engenders more cellular activity. The increased Blood and cellular metabolism increases the local temperature. The immune cells break down and ingest the pathogens, creating a process which continues until the disease is eliminated.

The dynamic movements of Medical Qigong


Cancer Treating Prescriptions
1.The Fast Walking Method
2.The Deep Breathing Method
3.The Tone Resonating Method

Figure 54.3. Three Prescriptions Used For Treating Cancer

exercises generate Heat, soften the body's connective tissues, and encourage the flushing of the intercellular fluid throughout the body's tissues and organs. Energetic Qigong practices increase oxygenation in the Blood and improve circulation, thereby enhancing leukocyte production, and strengthening the body's immune system.

CANCER TREATMENT METHODS

Tumor and cancer cells make their own room within the body's tissues by crowding the normal tissues. The tumor and cancer cells grab nourishing energy at the expense of the host, thus damaging the patient's body.

Medical Qigong cancer treatment methods are techniques designed to purge the energy that supports the tumor. These techniques are based on the fundamental Qigong patterns mentioned previously. The goal of these patterns focuses on treating the patient's Excess syndrome first, by purgation. Purgation is then followed by tonification, then regulation. The rapid growth of healthy energy, and the fast expulsion of Evil factors, should lead to normal body function restoration, and create more vigorous metabolic activity. More nourishment can be absorbed, delivered and distributed throughout the body, leaving no room to feed the tumor cells.

In Medical Qigong clinics, tumors are viewed as being similar in their expansion and growth to that of the energetic pattern of a plant's Qi flow. When tracing the origin of a tumor, the Qigong doctor begins at the tumor's location (considered the flower or fruit of the disease) and traces its energetic branches to the organ of origin (the actual root of the disease). If the disease is internally induced, the original source, i.e., the dysfunctional internal organ, feeds the tumor through suppressed emotional trauma.

To address this problem, the doctor prescribes the following three cancer treatment methods as homework, in addition to Medical Qigong treatments and herbal therapy: the Fast Walking Method, Deep Breathing Method, and the Tone Resonation Method (Figure 54.3).

1. The Fast Walking Method stimulates the electromagnetic fields within the tissues and reinforces the patient's Yuan Qi. By walking fast and changing the normal breathing patterns, the cancer cells can be destroyed. This is because the dual action of shocking the system with more Qi and Blood flowing through the body tends to stimulate the electromagnetic fields within the tissues, causing the tissue cells to become stimulated and the immune system to be aroused and thus enhanced.
2. The Deep Breathing Method tranquilizes the patient's mind, and enhances their Yuan Qi. The Deep Breathing method is used to treat various cancers due to mental and emotional factors, by changing the patient's normal breathing patterns.

By changing the normal breathing into rapid exhaling, slow deep exhaling, or relaxed toning, Blood clots and tumors can be dissolved. This breathing technique has a special effect on reinforcing the patient's Yuan Qi. When prescribing Medical Qigong therapy, it is important to match the patient's Yin disease with a Yang method of treatment, and a Yang disease with a Yin method of therapy. For example: rapid exhalation (a Yang method) would be used when treating an abdominal mass caused by a Cold (Yin) condition.

3. The Tone Resonating Method is utilized to purge any residual Evil pathogenic factors from the patient's body.

When first starting the Medical Qigong Cancer Tone therapy, a patient's practice time should be short. The performing time can be extended gradually with the increase of the patient's physical strength. To bring the Medical Qigong exercises to peak efficiency, a patient should practice a minimum of four hours (including 15 minute breaks), and up to six hours each day. The patient can take a break after half an hour to avoid fatigue.

Through various kinds of breathing and fast walking therapies, Qi can be energized to flow so vigorously through the Conception Vessel that the patients' Yin and Yang is balanced and their Lung Channels are strengthened. In the course of treating the tumor or cancer, True Qi (Zhen Qi) is fostered and the immunity of the body strengthened. Research from China proves that persistent training, vigorous enough to increase a person's heartbeat up to 70-80% of its maximum rate, helps dissolve Blood clots. Other reports state that long distance running can be effectively used to cure cancers. These reports may help explain why fast walking, and breathing methods, are effective for preventing and treating cancer.

SOCIAL ONCOLOGY—ESTABLISHING A CANCER SUPPORT GROUP

In China, cancer patients join support groups to practice Medical Qigong. This form of treatment is called social oncology; it was created by the Cancer Recovery Society for the purpose of supporting human interaction and the recovery of health by cancer patients.

Cancer recovery groups meet daily in parks throughout China, practicing self-healing (in particular, Guo Lin's Cancer Recovery Qigong and Walking Qigong Therapy). After practice, the groups gather together for about an hour to socialize in a nearby tea house. The patients sing songs, tell jokes, laugh, introduce new members, read poems, and tell stories that highlight the possibilities of recovery from cancer. As part of the social meeting, the group regularly sings "Happy Birthday" to each patient who has an anniversary after his or her cancer diagnosis. Laughter becomes a top priority in social oncology, and is considered the strongest medicine for healing.

According to Dr. Roger Jahnke, O.M.D., the advantages of social oncology are three fold: stress reduction, positive reinforcement of hope, and the establishment of deep interpersonal relationships.

1. Stress is reduced through socializing rather than isolating and fretting. The social healing aspect of the patient's recovery program serves as a constant reminder that the physical healing is enhanced when he or she becomes lighthearted and free of worry.
2. Increased hope and faith is achieved through the power of personal testimony. Each day during the social healing session, patients hear stories of close friends whose recovery process proves the benefits of healing from various forms of Medical Qigong.
3. The value of love and encouragement from friends mitigates depression, fear, and worry. Isolation is like a food to cancer; social oncology provides fun, encouragement and a deep, caring interpersonal connection within the recovery group.

SOCIAL ONCOLOGY WITHIN THE HOSPITALS

In several Medical Qigong hospitals in China, when the patients first check-in, they are assigned a support group. The support group consists of previous and current patients, who have survived the same type of cancer as the entering patients.

To assist patients in healing and to give them every emotional advantage during recovery, visitors, phone calls, letters, TV, and newspapers are forbidden for six weeks; this ensures a controlled environment in which neither family nor friends can adversely affect the healing process (through critical comments or attitudes). Patients are immersed in a support group full of caring, motivated individuals all working towards the same goal. Furthermore, patients who have been there the longest share their success stories, boosting everyone's moral.

The concept of clinical social oncology is based on the belief that the patients' high spirits affect the emotional perspective, and thus mental thinking. These emotional and mental changes alter the physical body. It was recently discovered that the group of breast cancer patients, who participated in the Stanford Hospital Cancer Support Group, lived twice as long as the women who refused to join the group. This difference in longevity was attributed to the love, support, and social aspect of the cancer support group. This recently discovery has given rise to the increase of several support groups in the United States now being established for patients recovering from AIDS, heart attacks, and many other illnesses including several types of cancer.

CANCER RESEARCH

Noted research scientist Feng Lida pioneered cancer research in China by showing that emitted Qi from Qigong masters produced marked changes in cancer cell cultures from mice. Several studies reported the effects of emitted Qi on tumors in animals. The emission of Qi, for example, was reported to inhibit the growth of implanted malignant tumors in mice, but did not destroy the tumors. Encouraged by the results with animals, researchers carried out clinical research on the effects of Medical Qigong on human subjects with cancer.

In one study, 127 patients with medically diagnosed cancer were divided into a Qigong group of 97 patients, and a control group of 30 patients. All patients received drugs, and the Qigong group practiced Medical Qigong for more than two hours a day over a period of 3 to 6 months. Both groups improved, but the Qigong group showed improvements four to nine times greater than the control group for strength, appetite, and weight gain. The Qigong group also did not experience bouts of diarrhea. The phagocytic rate, which is a measure of the immune function, increased in the Medical Qigong group, but decreased in the control group. These cancer treatment results were gathered and compiled from clinical research by Dr. Kenneth M. Sancier, available in the first Appendix of this text.

MEDITATIONS FOR CANCER PATIENTS

The following meditations are frequently used within the Medical Qigong clinic to aid healing. As previously discussed, it takes focused concentration to initiate an energetic transformation. Focused concentration is achieved through proper imagination, visualization and positive affirmation; it is practiced to reprogram the body's energetic cell patterns, and initiate healing.

DIVINE HEALING LIGHT MEDITATION

A very effective Medical Qigong meditation called Divine Healing Light is practiced by cancer and tumor patients throughout China to dissolve and disperse energetic pathogens. This meditation begins as follows:

Begin in a seated posture. Relax, and feel a quiet comfort. Imagine yourself seated on a quiet mountain overlooking the ocean, resting under a clear, dark blue evening sky. At the rim of the ocean, the full moon begins to rise. It continues to ascend until it faces you, suspended in the sky above your head. Slowly the moon begins to shrink, becoming smaller and smaller, yet brighter and brighter until it becomes the size of a small luminous pearl. This brilliant white pearl begins to pulse and expand, as it grows it opens to form a large orb, vibrating with divine power. From the center of the divine power flows unconditional love, healing, and compassion.

Breathe in this vibrant, healing light; allow it to penetrate deep into your body, permeating every cell, illuminating and dispersing all illness. Open fully to the divine healing. Feel the love and compassion enveloping you, and penetrating all the diseased areas of your body. Continue to breathe the healing energy in through your nose and exhale out through your mouth (imagining all the unclean energy descending into the ground). Continue this breathing pattern until all the negative energy has been expelled and replaced with divine love and healing light.

PULLING OUT THE PAIN MEDITATION

This meditation is an effective treatment prescription for treating many illnesses, including cancer and tumors. The goal is to eliminate all toxic belief structures that stand in the way, and sabotage the patient's healing. Gentle acceptance of the illness and emotional pain opens the pathway to understanding and unveiling hidden traumas. Force does not work in trying to change the tumor or cancer energetic patterns. Only honesty, respect, tenderness, and understanding will begin the healing process. As pain and suffering are allowed to surface into consciousness, the immune system is able to recognize diseased cells, and can mobilize an army of immune cells. These are then able to effectively identify, dissolve, and remove any tumors and disease.

The doctor instructs and guides patients through this meditation matching the rhythm of the words, to the patients' exhalations. Patients draw their painful memories and traumas out of their body in the form of dark smoke; they then separate the distilled wisdom and knowledge from this dark cloud, reabsorbing the healing light into every pore and cell in their body. The dark cloud then is released with the help of an angelic being who severs the energetic cord(s) that still attach the patients to their pain and suffering. The doctor assists the complete severance by clapping his or her hands as the patients visualize the "Sword of Truth" (held by this holy being), severing the dark energetic cord(s). The sword of truth represents the patients' intent to regain their power by letting go of their attachment to their illness. This attachment created very real energetic cords that bound the patients to their painful memories and toxic emotions. Severing these cords, or cord, symbolizes the end of the patients' investment in their disease, and the beginning of true healing. All the patients' pain and despair is released, as the black cloud ascends into the Heavens, and into the hands of God (or a higher power, in accordance with the belief structure of the patients). As the cloud reaches the first wave of love and compassion emanating from God (or a higher power), a mighty explosion transmutes the black despair and pain, into divine healing light. The doctor then assists the patients in accepting this healing, loving light back into their body, to experience, perhaps for the first time in their lives, true forgiveness and a state of grace.

1. Begin by sitting comfortably in a chair, with both feet on the floor, hands resting on the thighs, eyes closed, tongue on the upper palette. Breathe naturally through the Lower Dantian.
2. Focus your attention on the Yellow Court area below the diaphragm where you store painful memories and traumas. Imagine opening up this area to release the toxic energy out of your body as a stream of dark steam releasing from a pot.
3. As the dark steam flows out of your body you release feelings and memories of guilt, anger, rage, humiliation, abandonment, degradation, rejection, insecurity, and sorrow. These toxic emotions have, until now, prevented you from healing through creating a deep distrust of yourself and others.
4. Focus your attention on this energetic cloud, and begin separating the pain and hurtful memories from the knowledge and wisdom gathered from these experiences. Visualize this knowledge and wisdom in the form of golden, white, and silver light energy gathering on the right side of the room. Continue to drain the dark cloud of misery and pain, now occupying the left side of the room, until you have extracted all the new insights from it. As you do so, you notice the dark cloud becoming heavier and darker.
5. Focus on the right side of the room. Through you intention, begin to inhale and imagine this bright, illuminating energy flowing back into your body. Absorb this knowledge and wisdom gathered from past experiences, void of any feelings of hurt, pain, or judgement, into every cell of your body. This distilled knowledge and wisdom empowers you to heal from

your wounds on a physical, mental, emotional, and spiritual level.

6. Next focus your attention on the dark black cloud containing all your pain and suffering. Imagine an angelic being, righteous and holy holding a "Sword of Truth" standing by your side, ready to sever the dark energetic cords still connecting your physical body to this dark cloud of despair. The sword descends and severs the cords (the doctor claps his or her hands at this moment).
7. The cloud of darkness begins to float up, through the ceiling, through the sky into space. Far in the distance you begin to perceive God, or a higher power, emanating waves of compassion, love, and mercy descending towards the Earth. One of the waves touches the ascending dark cloud of hurt and pain, exploding it into a brilliant light. The cloud is immediately transmuted into fluorescent crystal blue drops of light. This pure, clean energy descends from the Heavens like a gentle rain. Breathe in this crystal blue healing energy, let it penetrate deeply into every pore, every tissue and cell, saturating your body completely. Feel the light cleansing, healing, and radiating throughout your being.

SUMMARY

Cancer is defined by Traditional Chinese Medicine as, "an obstruction of Qi and Blood circulation resulting in stagnation." The root cause for cancer is the breakdown and stagnation of the patient's Yuan Qi. Once cancer becomes established within the patient's body, or metastasizes, it is difficult to heal.

In order for cancer to form, it must elude the body's immune system, undergo many divisions, and produce countless generations of cells without resistance. By the time the cancer cells have formed into a cluster mass, a fixed energetic pattern has been established to support its existence and survival.

Only when the patient's Yuan Qi is returned to its original state, can the body begin to heal itself. Medical Qigong Cancer treatment methods strengthen the True Qi which in turn strengthens and cultivates the Yuan Qi. In this manner, the body is returned to its natural state of Yin and Yang balance.

It is the author's hope that these effective methods of treating cancer will soon be available to the American public. To this end, I have established a three-year master's and plan to offer a five-year doctorate program in Medical Qigong Science at the Five Branches Institute, College of Traditional Chinese Medicine, in Santa Cruz, California.

TREATING TUMORS AND CANCER WITH MEDICAL QIGONG THERAPY

The following are several Medical Qigong techniques and treatment modalities, currently used in China, to treat different types of energetically induced cysts, tumors, and cancers. It is advisable to accompany the prescriptions with various herbal prescriptions.

BRAIN TUMORS

A brain tumor is a generic term used to describe any intracranial mass, which includes: neoplastic, cystic, inflammatory (abscesses), or syphilitic.

ETIOLOGY

There are many causes for intracranial tumors. The most common cause is Kidney Yin (Water) failing to wash over the brain to disperse the pathogens. This condition can be caused by Excess Liver Fire dissolving the body's Kidney Water.

SYMPTOMS

Intracranial tumors produce symptoms primarily by two mechanisms: the infiltration and destruction of the normal brain tissue; or the tumor mass affecting the surrounding tissue, which causes edema, thus increasing the intracranial pressure.

General symptoms include headache (due to intracranial pressure), changes in the retina, and vomiting (without nausea). Additional symptoms include mental and emotional changes such as dullness, giddiness, or epileptiform convulsions.

TREATMENT

1. The doctors first step is to analyze the syndrome and the patient's emotional outlook.

When treating brain tumors, the growth of the disease must first be stopped. Check the patient's external living conditions, and do a psychological profile to determine any detrimental patterns.

2. Dredge and disperse toxic Heat out of the patient's Yang channels. Remove any Excess Liver Fire by drawing it out the Liver organ; then dredge the patient's Liver Channels, dispersing toxins out through the Lv-3 points.
3. The doctor must reverse the process of tumor development to dissolve the tumor. Instruct the patient to visualize energy from the Lower Dantian rising up to the tumor and transforming the mass back into Qi. The tumor growth must be reversed by first converting the solid tumor into soft tissue, then into fluid Qi that is then dispersed.

   In cases of cranial thrombosis, tumors must be dissolved slowly; otherwise other tumors will be created. The tumors must be softened, then slowly dispersed to avoid any recreation of the energetic channels' dysfunctions.
4. Extend Qi into the patient to reinforce the Kidneys' Qi by extending Qi into the patient's feet via the brain tumor point, Shihmein, at the bottom of the heels (Figure 54.4). Next, lead the patient's Kidney Water up into the brain to rinse over and slowly dissolve the tumor.
5. Finally, regulate and balance the patient's Yin and Yang energy.

PRESCRIPTIONS AND HOMEWORK

1. Have the patient practice the healing sound "Duo" (10 times in a straight and 10 times descending/ascending tone) five times a day.
2. Assign tonifying exercises for the Kidneys and Heart.
3. Prescribe herbal teas to enhance the patient's Kidney Yin.

BREAST CANCER

Mammary cancer is one of the most common types of malignant tumors in women; it is considered a malignant neoplasm of the breast.

ETIOLOGY

There are multiple factors associated with breast cancer. These factors can be categorized under genetic family factors, hormonal factors, dietary factors, environmental factors, and benign breast disease. Heredity can play an important role, especially if the patient's mother (or close relative) had bilateral breast cancer diagnosed prior to menopause. Also, a history of chronic breast disease (especially epithelial hyperplasia), or obesity can predispose the patient to breast cancer.



Figure 54.4. The Qigong doctor will emit Qi into the patient's "Brain Tumor" point (also called the Shimian, meaning insomnia point) located at the bottom of the patient's Heel.

SYMPTOMS

Symptoms consist of hard lumps which lack mobility, and progressively increase in size. The hard lumps may be concave, convex, or protrude; or the nipple may be inverted. Breast cancer is usually related to stagnation of the Liver's Qi, stasis of Blood, Phlegm and Toxic Heat, as well as weak Kidneys. The emotional components which lead to breast cancer are suppressed grief, worry, sorrow, and depression.

TREATMENT

1. Purge and eliminate the stagnation from the breast tissue (Figure 54.5).
2. Subdue the Rebellious Qi.
3. Clear the Liver and tonify the Kidneys. When treating breast cancer, the doctor should use the Vibrating Palm in conjunction with projected Tone Resonation (projecting both vibration and the "Ni" tone resonation into the cancerous area).
4. Tonify the patient's Conception and Thrusting Vessels, and end with the Microcosmic Orbit regulation (Fire Cycle).

UTERINE CANCER

Uterine cancer is considered a malignant neoplasm of the uterus.

ETIOLOGY

The etiology of uterine cancer is unknown. Possible causes of the disease may be:

- chronic stress
- toxins
- suppression of emotions
- pathological changes of the endometrial hyperplasia, or
- cervical carcinoma spreading onto the uterus.

SYMPTOMS

A uterine carcinoma is generally more common in women after menopause, roughly 75% of uterine cancers occur in postmenopausal women, 15% peri-menopausal women and 10% of menstruating women. The main clinical manifestations include pain in the lower abdomen, waist and thighs, abnormal uterine bleeding with a bloody, purulent discharge.

TREATMENT

One Medical Qigong therapeutic technique used in China to treat uterine cancer is as follows.

1. Purge the diseased area of stagnant Qi using the Thunder Palm technique in conjunction with the Vibrating Palm technique.
2. Project the sound "Yu" into the uterus to disperse Heat from the cancer cells.
3. Disperse Excess Heat from the patient's Liver and uterus, leading the Toxic Qi out the patient's body via the right Gall Bladder



Figure 54.5. After Purging the pathogenic Qi from the patient's upper body, the Qigong doctor continues to disperse the patient's Toxic Qi from her lower abdomen, leading it down her legs and out her St-36 points.

Channel.

4. Fill and tonify the patient's Lower Dantian and Kidneys with Qi. Circulate the energy through the Microcosmic Orbit to improve Qi and Blood circulation through the Governing and Conception Vessels.

PRESCRIPTIONS AND HOMEWORK

The Conception Vessel moves Qi in the Lower Burner and uterus; it is the primary Vessel used in treating uterine and cervical cancer. Sexual activities are therefore prohibited from the start of the treatments, until treatment is no longer needed.

1. Have the patient practice the Descending the Yang and Ascending the Yin Technique (see Chapter 41), ending with the healing sound "Yu" for 24 breaths, 9 times a day.
2. Prescribe the Fast Exhaling Breathing Method along with the Cancer Walking methods for treating Kidney disease (see Chapter 15).
3. Have the patient practice the method of Taking in the Blue Qi, three times a day for 15 minutes each session, to strengthen the Kidneys.
4. Have the patient practice the Filth Dispelling meditation, while focusing on her uterus. This meditation is practiced as follows:
   a. From a sitting posture, with the eyes closed, and the body relaxed, place the tongue up against the upper hard palate, behind the teeth.
   b. Breathe naturally and evenly.
   c. Imagine Qi whirling in through the upper portion of the uterus, circulating clockwise, building momentum as the energy flows downward to the base of the uterus.
   d. Once the energy has reached just above the cervix area, imagine the whirling Qi absorbing the noxious Heat and Toxic Qi from the uterus, transforming it into wind, and dispelling it out the vagina. Repeat this sequence 10 times.
   e. Next, gently close the vagina and anal sphincter, then inhale, and imagine the Qi flowing into the body through the vagina. As this energy flows into the uterus and Lower Dantian area, it transforms into wind. This wind circulates in a counterclockwise direction, spiraling up the body, through the Thrusting Vessel and exits the body through the mouth with each exhalation. Repeat this visualization 10 times.
   f. Finally, focus attention on the Lower Dantian, imagine the Qi returning to its origin, and rub the abdomen 36 times in a clockwise direction to end the prescription.

CERVICAL CANCER

Cervical cancer is considered one of the most common malignant tumors in China. It is considered a malignant neoplasm of the cervix of the uterus, and can occur at any age.

ETIOLOGY

Cervical cancer is suspected to be an oncogenic papilloma virus that is transmitted sexually. Risk factors include:

- sexual intercourse at an early age,
- multiple sexual partners and promiscuous male sexual partners (especially those whose previous partner had cervical cancer),
- serious cervical lacerations caused from the penis being too long, or the insertion of foreign objects,
- unsanitary sexual relationships,
- closely spaced births, and
- a family history of cervical cancer.

Excessive sexual activity predisposes young teenage girls to cervical cancer, because, with the onset of ovulation and the changes in vaginal PH, active squamous metaplasia is taking place in the cervix. During this time of cellular immaturity and vulnerability, a carcinogen is most likely to have an influence on the squamous epithelium; this can predispose the teenager girl to cervical cancer later on in life.

THE DEVELOPMENT OF CERVICAL CANCER

There are two main types of cancer of the cervix. The squamous cell carcinomas make up 85-90% of cervical cancer, the rest (a small 10-15%)

are developed from a malignant adenoma arising from a glandular organ known as a adenocarcinoma.

Cervical cancer begins with the growth of abnormal precancerous cells and tissues called dysplasia. Dysplasia is first detectable in the squamous epithelium of the cervix (the muscle lining of the cervix), and spreads to create a tumor called a cervical intraepithelial neoplasm (CIN). The cervical intraepithelial neoplasm progresses through three levels of severity, from mild, to moderate, to severe. At the severe level of CIN, the precancerous growth turns malignant; it becomes a carcinoma in situ (localized). If left untreated, the carcinoma progresses through four more stages of development, each of which is subdivided into two grades of severity. These grades indicate the location and spread of the carcinoma. The four stages and their subdivisions are described as follows:

In the beginning stages of the disease, cervical dysplasia is characterized by three stages of abnormality and severity (CIN-1,-2,-3), which later progress onto four stages of invasive carcinoma (Stages I through IV).

- CIN-1: Corresponds to a mild condition of dysplasia.
- CIN-2: Corresponds to a moderate condition of dysplasia.
- CIN-3: Corresponds to a severe condition of dysplasia, and carcinoma (in situ). The cancer, however, is found only in the layers of the cells lining the cervix, and has not yet extended deeper into the tissue lining.
- Stage I-A: Corresponds to a microinvasive carcinoma. The cancer is beginning to spread from the lining of the cervix into the deeper connective tissue.
- Stage I-B: Corresponds to an invasive carcinoma confined to the cervix. The cancer has now spread from the lining of the cervix into the deeper connective tissues.
- Stage II-A: Corresponds to a tumor extending beyond the cervix, into the upper third of the patient's vagina, but is still inside the pelvic area.
- Stage II-B: Corresponds to a tumor extending beyond the cervix, into the loose connective tissues around the patient's uterus (parametrium), but is still inside the pelvic area.
- Stage III-A: Corresponds to a tumor extending into the lower third of the patient's vagina.
- Stage III-B: Corresponds to a tumor extending into the patient's pelvic wall. At this stage, the cancer may be blocking the ureters (responsible for carrying urine from the Kidneys to the Bladder).
- Stage IV-A: Corresponds to a tumor extending into the patient's Bladder or rectum.
- Stage IV-B: Corresponds to a tumor extending into the patient's Liver or Lungs.

SYMPTOMS

Clinical symptoms include bleeding after sexual intercourse and between periods, abnormal bowel movements, or fatigue. Bleeding may also be noticed after severe exertion or straining during defecation. As the disease develops, the leukorrhea (vaginal discharge) may become filthy and mixed with blood, or foul and mixed with sloughed pieces of Body Fluid or tissue. Additional symptoms include lumbar, sacral and abdominal pain, Bladder irritation, frequent and urgent urination, blood-tinged vaginal discharge, unilateral lymphoedema, and unilateral ureteral obstruction (this indicates a very advanced stage).

TREATMENT

When Righteous Qi is increased through Medical Qigong therapy and prescription homework, the energy feeding the patient's cancer begins to decrease.

One Medical Qigong therapeutic technique used in China to treat cervical cancer is as follows:

1. Purge the diseased uterine area of pathogenic Qi using the Thunder Palm technique in conjunction with the Vibrating Palm to disperse the stagnation.
2. Use the "Yu" sound Qi projection into the uterine and cervix area to disperse Heat from the cancer cells.

3. Disperse the Excess Heat from the patient's Liver and cervix areas, leading the Toxic Qi out the patient's body via the right Gall Bladder Channel.
4. Fill and tonify the patient's Lower Dantian and Kidneys with Qi. Circulate the energy through the Microcosmic Orbit to improve Qi and Blood circulation through the Governing and Conception Vessels.

PRESCRIPTIONS AND HOMEWORK

The Conception Vessel moves Qi in the Lower Burner and uterus, and is the primary vessel used to treat uterine and cervical cancer; therefore, sexual activities are prohibited from the start of the treatments, until treatment is no longer needed.

The prescriptions and homework required for cervical cancer treatment are exactly the same exercises that are used for the treatment of uterine cancer.

PROSTATE CANCER

Prostate cancer is considered a malignant neoplasm, and is usually an adenocarcinoma of the prostate gland. It is the major type of cancer in males. Prostate cancer occurs in less than 1% in men under 50. Men with a family history of prostate cancer are three times more likely to develop it then the general public. Many prostate cancers remain dormant, but once awakened, can become life-threatening.

ETIOLOGY

The etiology of prostate cancer is unknown. Speculations suggest that prostate cancer can be related to an imbalance between male and female hormones. From a Western Medical perspective, the carcinogenesis is a multistep accumulation of genetic lesions. These lesions may result in uncontrolled cellular proliferation, a decrease in cellular death or an apoptosis, invasion, and the metastatic spread of the disease.

From a Traditional Chinese Medical perspective, prostate cancer is due to Excess Liver Fire and Kidney Deficiency. The suppression of anger and fear, as well as a diet consisting of a high alcohol intake, or consumption of too many hot spicy foods, may also cause, or contribute to prostate cancer.

SYMPTOMS

In the early stages there are no symptoms; however, as the disease progresses the inflamed prostate gland impedes urination and results in outflow obstruction, preventing the Bladder from emptying completely. Dull pain is experienced around the external genitals and Bladder. There is frequent burning, unfinished and dripping after urination with white discharge. Also, in some cases, there will be sexual function disorders (an inability to attain erection) as well as sciatica-like symptoms with pain radiating downward to the perineum and anus.

If the prostate is hard and firm, it indicates cancer; if the prostate is large and swollen, it indicates an infection. Inflammation of the prostate can be divided into acute and chronic conditions.

In acute prostatitis caused from Damp Heat in the Lower Burner, symptoms include pain and discomfort in the genital and Bladder areas, fever, and chills.

In chronic prostatitis, symptoms include dull pain in the urogenital area, discharge from the penis, discomfort during sexual intercourse, and frequent urination (especially during the night).

TREATMENT

One of the Medical Qigong therapeutic techniques used in China to treat prostate cancer is as follows.

1. With the patient supine, begin to purge the diseased prostate area of pathogenic Qi using the Thunder Palm technique in conjunction with the Vibrating Palm to disperse the stagnation.
2. Next, use "Yu" sound projection into the prostate area to disperse the Heat from the cancer cells.
3. Disperse Excess Heat from Liver and pathogenic Qi from the prostate, out of the patient's body via the right Gall Bladder Channel.
4. Fill and tonify the patient's Lower Dantian and Kidneys with Qi, and circulate the energy through the patient's Microcosmic Orbit to improve Qi and Blood circulation within the Governing and Conception Vessels.

PRESCRIPTIONS

Depending on the patient's condition, one or more of the following prescriptions may be given:

1. The "Guo" sound resonation is used to disperse the Liver Fire.
2. The Kidneys' "Yu" sound resonation is used to disperse Toxic Qi from the prostate.
3. Tonification and regulation exercises are prescribed for the Lower Dantian, Spleen, and Kidneys.
4. The following three exercises are used to treat prostate cancer, and were made popular in the West by Dr. Hong Liu.
   a. Sit at the edge of the chair with your feet flat on the floor. The right leg crosses over your left leg. With your left hand grasp the bottom of the right foot.

      Then extend your right hand out in front of the body, palm facing upward, while you imagine releasing toxic energy from your body through the mouth as you exhale. As you inhale, twist your hand as far as possible towards the right side keeping your eyes on the palm, while simultaneously pulling your foot towards the body and contracting the anus and perineum. This opens the Liver Channel and directs Qi into the Kidneys and prostate area.

      After completing the movement, hold your breath for a moment. Imagine Blood and Qi flowing into the prostate area and exhale while returning to the starting position. The exercise is repeated for 18 breaths per each side.

   b. The next exercise begins from a Wuji posture. Bend over as you flex your toes upwards. Hold this position as long as you can before standing erect, focusing on breathing naturally from the abdomen. This movement increases the flow of Qi and Blood into the prostate area. It is important to make sure this exercise is performed slowly. The exercise is repeated 9 times.

   c. This last exercise is done sitting on the floor while facing a wall. Place the balls of your feet against the wall while resting your heels on the floor. Wrap your arms around your bent knees, while keeping the back straight and breathing naturally through the Lower Dantian.

      While inhaling, focus on breathing from the lower abdomen instead of the chest. This causes the Qi of the Thrusting Vessel to stimulate the prostate gland, and increases the flow of Qi and Blood into the prostate area. The exercise is repeated for 18 breaths.

5. The "Filth Dispelling Meditation," is also prescribed, with the patient focusing on his prostate area. This meditation is practiced as follows:
   a. From a sitting posture, with the eyes closed, and the body relaxed, place the tongue up against the upper hard palate, behind the teeth.
   b. Breathe naturally and evenly.
   c. Imagine Qi whirling in through the upper area of the Bladder, circulating clockwise, building momentum as the energy flows down to the prostate area.
   d. Once the energy has reached the prostate, the patient will imagine the whirling Qi absorbing the noxious Heat and filthy Qi from the Bladder and prostate areas, transforming it into wind, which is dispelled out through the penis. The exercise is repeated 10 times.
   e. Next, gently close the anal sphincter while inhaling and imagine the Qi flowing into the body through the penis. This energy flows into the Lower Dantian, becoming transformed into wind. This wind begins circulating in a counterclockwise direction, spiraling up the body, through the Thrusting Vessel and exits through the mouth with each exhalation. This is also practiced for 10 repetitions.

f. Finally, focus the attention on the Lower Dantian; imagine the vital Qi returning back to its origin, while rubbing the abdomen in a clockwise direction to end the prescription.

LUNG CANCER (PULMONARY CARCINOMA)

Lung cancer, also called a "Bronchial Carcinoma," is a malignant Lung tumor that originates in the bronchi. It can also spread to the trachea appearing as an ulcer in the windpipe, a small flattened bump or nodule. It can extend into the body's lymphatic system, as well as into the blood vessels.

The most common type of bronchogenic tumor is the squamous cell or epidermoid (on the airway lining). The oat cell and adenocarcinoma are the next most common.

ETIOLOGY

Squamous cell cancer is usually associated with a history of cigarette smoking and secondhand smoke. Statistically it is the most common of all carcinomas and accounts for 40% of all male deaths. Other chemical carcinogens may cause Lung cancer, especially among workers in industrial and mining areas.

SYMPTOMS

The main clinical manifestations include: chest pain, coughing with scanty sputum (sometimes with blood), pectoralgia, fever, loss of appetite, loss of weight, weakness and breathlessness in the later stages due to a Lung Yin Deficiency.

TREATMENT

Purge the Excess Heat from the patient's Lungs and Liver. Tonify and regulate the patient's Kidneys and Mingmen area, then strengthen the patient's Spleen and Lungs.

PRESCRIPTION AND HOMEWORK

1. Have the patient practice the Dry Crying exercise for a period of 15 minutes twice a day (see Chapter 53).
2. Have the patient practice the Sun and Moon Rotation Technique (see Chapter 41), ending with the healing sound "Shang" for 24 breaths, 9 times a day.
3. Prescribe the Fast to Moderate Exhaling Breathing Method along with the Cancer Stepping Method for treating Lung diseases (see Chapter 15).
4. Have the patient practice the method of Taking in the White Qi, three times a day for 15 minutes each time to strengthen the Lungs.
5. Have the patient practice the method of Taking in the Blue Qi, three times a day for 15 minutes each time in order to strengthen the Kidneys.

LIVER CANCER

The Liver is the most usual site for the metastatic spread of tumors that disseminate through the Blood system. Carcinoma of the Liver is quick in development, high in mortality, and is regarded as one of the common malignant tumors.

ETIOLOGY

The etiology of Liver cancer is unknown. There are speculations suggesting that the following list of items may cause, or contribute, to the creation of Liver cancer:

- exposure to chronic stress and the suppression of anger,
- toxic poisoning (Liver cancer is usually associated with a long history of alcohol, drug abuse and chronic hepatitis), and
- a congenital weakness, with heredity being the predisposing factor.

SYMPTOMS

The Liver may have a single nodule, or multiple nodules. The main clinical manifestations include: distension and severe hypochondriac pain, hemorrhage of the digestive tract, and progressive hepatomegaly (enlargement). Its surface feels irregular on palpation (central depression or umbilications can often be detected).

TREATMENT

Purge the Excess Heat from the patient's Liver and Gall Bladder Channels, then tonify and regulate the patient's Kidney and Mingmen areas. Strengthen the patient's Spleen and Lungs, then regulate the patient's Liver.

PRESCRIPTIONS

1. Have the patient practice the Descend the Yang and Ascend the Yin Technique (see

Chapter 41), ending with the healing sound "Guo" for 24 times, 9 times a day.
2. Prescribe the Fast to Moderate Exhaling Breathing Method along with the Cancer Walking Method for treating Liver disease (see Chapter 15).
3. Have the patient face, or embrace, a tree while practicing the method of "Taking in the Wood Element Qi," but only upon inhalation. With each exhalation the patient should purge the toxic Qi, sending it into the ground. This prescription is practiced three times a day for 15 minutes each time.
4. Have the patient practice the method of "Taking in the White Qi," three times a day for 15 minutes for each session to strengthen the Lungs.
5. Have the patient practice the method of "Taking in the Green Qi," three times a day for 15 minutes for each session to strengthen the Liver.
6. Have the patient practice the method of "Taking in the Yellow Qi," three times a day for 15 minutes for each session to strengthen the Spleen.

ESOPHAGEAL CANCER

Carcinoma of the esophagus is one of the common malignant tumors, caused from a carcinoma of the squamous epithelium of the esophagus. This type of carcinoma is called "Ge Shi" or dysphagia in Traditional Chinese Medicine.

ETIOLOGY

The cause of esophageal cancer is unknown. There is speculation that the following list of items may cause or contribute to the creation of esophageal cancer:

- consumption of foods with a high content of nitrates,
- large quantities of spicy, hot foods, or mouldy food,
- chronically eating too fast, thus irritating the throat,
- strong alcoholic drinks,
- smoking,
- poor oral hygiene, resulting in tooth decay, and
- chronic stress and the suppression of emotions.

There are three types of esophageal cancer that invade the wall of the esophagus.

1. An ulcerous carcinoma of the esophagus that grows towards the outside of the esophagus. Dysphagia (difficulty in swallowing) is not evident in this type of cancer.
2. A tumor which grows in a circular formation. In this type of cancer, the lumen is narrow and easily obstructed.
3. The tumor attaches itself to one side of the esophagus, while the other side is still healthy and can still dilate. In this type of cancer, symptoms of obstruction appear slowly.

SYMPTOMS

More common in men over 40, carcinoma of the esophagus causes pain in the epigastric and sternal area. Swallowing aggravates the symptoms. The main clinical manifestations include the following symptoms:

- enlarged lymph nodes in the neck,
- difficulty in swallowing (dysphagia),
- excessive salivation,
- poor digestion,
- vomiting,
- loss of weight,
- pain in the chest and back, and
- emaciation and weakness.

TREATMENT

Purge the Excess Heat from the patient's throat, Lungs and Liver area. Tonify and regulate the patient's Kidney and Mingmen area, then regulate the Qi of the patient's esophagus, rooting it within the Lower Dantian.

PRESCRIPTIONS

1. Have the patient practice the "Dry Crying" exercise for a period of 15 minutes twice a day (see Chapter 53).
2. Have the patient practice the healing sound "Shang" for 24 breaths, 9 times a day (see Chapter 40).
3. Prescribe the Fast to Moderate Exhaling Breathing Method along with the Cancer Walking method for treating Lung disease (see Chapter 15).

4. Have the patient practice the method of "Taking in the White Qi," three times a day for 15 minutes for each session to strengthen the Lungs.

STOMACH CANCER

Carcinoma of the Stomach is regarded as one of the common malignant tumors. It is sometimes categorized as a carcinoma, lymphoma or sarcoma.

ETIOLOGY

The etiology for Stomach cancer is unknown. Speculations suggest exposure to chronic stress, and a suppression of emotions, may cause, or contribute to this disease. There is also an association between the development of gastric cancer and previous partial gastrectomies for benign diseases.

SYMPTOMS

The symptoms of Stomach carcinoma often do not appear until they have developed to the middle and late stages. Most common in men over 40, carcinoma of the Stomach causes a continual pain and burning sensation in the epigastric and sternal area, which is usually aggravated by swallowing. The main clinical manifestations include: shallow complexion, lack of appetite, loss of weight, extreme anemia, blood in the stool, debility, vomiting of partially digested food, and sometimes Blood that looks like coffee-grounds. The Liver may also be enlarged with nodules.

TREATMENT

Purge the Excess Heat from the patient's Stomach, Liver and Gall Bladder Channels, then tonify and regulate the patient's Heart and Spleen. End by regulating the patient's Kidney and Mingmen areas.

PRESCRIPTIONS

1. Have the patient practice the Descend the Yang and Ascend the Yin Technique (see Chapter 41) ending with the healing sound "Dong" for 24 times, 9 times a day (see Chapter 40).
2. Have the patient practice the method of "Taking in the Yellow Qi," three times a day for 15 minutes each time in order to strengthen the Spleen.
3. Have the patient practice the "Taking in the Red Qi," three times a day for 15 minutes each session to strengthen the Heart.

PANCREATIC CANCER

Carcinoma of the pancreas is regarded as one of the common malignant tumors. Statistics state that 22% of deaths from gastrointestinal cancer are due to cancer of the pancreas.

ETIOLOGY

The etiology for pancreatic cancer is unknown. Speculations suggest cigarette smoking and diet (in particular, a high intake of fat and / or meat) may cause, or contribute to the cancer. Recent investigations have identified a number of factors that may also contribute to the cause of pancreatic cancer, including: environmental factors, surgical or associated medical factors, genetic factors, and occupational exposures to toxins.

SYMPTOMS

This type of cancer is more common in men between 50 and 70. A carcinoma of the pancreas causes pain in the epigastric area, which starts as a dull ache and usually becomes aggravated by lying down. The main clinical manifestations include dyspepsia, diarrhea and constipation, loss of weight, nausea, vomiting and fatigue.

The symptoms of pancreatic cancer can sometimes vary in accordance to its exact location. The head of the pancreas is close to the duodenum, while its tail reaches to, and energetically connects with, the Spleen. The middle of the pancreas lies horizontally across the upper aspect of the abdomen.

1. Carcinoma of the Pancreas's head has as for its main symptom jaundice, due to the common bile duct of the Gall Bladder becoming obstructed. This obstruction causes the bile to back flow into the Liver and thus contaminates the Blood. This causes both the Gall Bladder and Liver to swell. As the amount of bile and Blood increases, it causes the skin, mucous membrane and sclera to become yellow, and the urine to turn brown. During the later stages, the skin color changes from a yellowish color to orange or dark yellow.
2. Carcinoma of the Pancrea's body has for its

main symptoms sharp abdominal pain and swelling. The abdominal pain reacts to the compression of the abdominal cavity nerve. This type of pain can occur sporadically, radiating to the patient's shoulder and back. The patient will notice this type of pain becoming aggravated when sitting up or lying down. Bending forward, however, can ease the pressure on the celiac nerve plexus and reduce the pain.

3. Carcinoma of the Pancrea's tail usually does not have detectable, early symptoms. At times, it can only be discovered when the tumor has metastasized to the peritoneum, Lungs, bones or other organs. Once the tumor has developed to sufficient size, the manifestation of symptoms include anorexia, fatigue, and loss of body weight.

TREATMENT

Purge the Excess Heat from the patient's pancreas, then dredge the Stomach, Liver and Gall Bladder Channels. Next, tonify and regulate the patient's Heart and Spleen, then regulate the patient's Kidney and Mingmen areas.

PRESCRIPTIONS

1. Have the patient practice the Descend the Yang and Ascend the Yin Technique (see Chapter 41), ending with the healing sound "Dong" for 24 times, 9 times a day (see Chapter 40).
2. Have the patient practice the method of "Taking in the Yellow Qi," three times a day for 15 minutes each session to strengthen the Spleen.
3. Have the patient practice the "Taking in the Red Qi," three times a day for 15 minutes each time in order to strengthen the Heart.

COLON AND RECTUM CANCER

Carcinoma of the Large Intestine or rectum is regarded as one of the common malignant tumors of the digestive tract.

ETIOLOGY

It has been long accepted that colorectal cancer is caused, or promoted, by environmental factors, especially diet. It is suspected that carcinogens are present in the patient's feces.

Also, chronic ulcerative colitis is considered a predisposing factor for colorectal cancer. The following chronic diseases are believed to be related: benign tumors of the colon and rectum (especially frequently occurring Large Intestine polyps), and chronic colitis (especially chronic amoebic dysentery and chronic ulcerative colitis).

SYMPTOMS

Colorectal cancer is more common in patients over 50 years of age. A carcinoma of the colon causes pain in the lateral abdominal area, which also may be umbilical. The main clinical manifestations include a sudden change of bowel habit (constipation or diarrhea), loss of weight, fatigue and Blood in the stool.

Large Intestine cancer can be divided into two quadrants of right and left intestinal dysfunction.

- Cancer on the right half of the Large Intestine is measured from the cecum to the right half of the transverse colon. The early symptom of this disease is dull pain and discomfort within the right epigastrium, or lower abdominal area. As the disease progresses, the pathological changes of the tumor initiate poisoning symptoms which appear as: weakness of the body, poor appetite, loss of weight, and anemia. In the midterm, or late stages, the patient can sometimes feel the tumor on the right side of their abdomen (located where the right Large Intestine stores food residue from the Small Intestine).
- Cancer on the left half of the Large Intestine is measured from the center of the transverse colon to the junction of the sigmoid colon and rectum. Symptoms of cancer in the left half of the Large Intestine appear earlier because the frequency of defecation increases with mucus and Blood in the stool. Moreover, because the narrow opening of the Large Intestine is now occupied by the tumor, it is difficult for the fecal matter to pass through, causing inflammation, as well as alternating diarrhea and constipation. If the tumor continues to grow, the intestinal cavity can be clogged, causing abdominal distention and toxicosis of the whole body.

TREATMENT

Purge the Excess Heat from the patient's Large Intestine and rectum area, purging and dredging the toxic Qi out the body and down the Stomach, Liver and Gall Bladder Channels. Next, tonify and regulate the patient's Kidney and Mingmen areas, emitting Qi through the soles of the patient's feet. End with regulating the patient's Fire and Water Qi through the Fire Cycle of the Microcosmic Orbit.

PRESCRIPTION AND HOMEWORK

Have the patient practice the "Filth Dispelling Meditation," focusing on the Large Intestine and rectum area. The meditation should be practiced as follows.

1. Begin from a sitting posture, eyes closed, body relaxed, with the tongue placed up against the upper hard palate, behind the teeth.
2. The breathing should be natural and even.
3. Imagine Qi whirling in through the upper orifice of the Stomach, circulating clockwise through the Small Intestine, building momentum as it flows to the Large Intestine.
4. Imagine the whirling Qi driving through the colon. As it moves through the colon, the whirling Qi begins absorbing the noxious Heat and filthy Qi from the Large Intestine, transforming it into wind, and dispelling it out the anus. This is practiced for 10 repetitions.
5. Next, gently close the anal sphincter while inhaling; imagine the Qi in the lower abdomen again becoming transformed into wind. This wind begins circulating in a counterclockwise direction, spiraling up the body, through the Stomach, and is expelled out the mouth. This is also practiced for 10 repetitions.
6. Finally, focus the attention on the Lower Dantian; imagine the vital Qi returning back to its origin, and begin rubbing the abdomen clockwise to end the prescription.

CHAPTER 55
QI EMISSION THERAPY FOR RADIATION AND CHEMOTHERAPY

The purpose of Cytotoxic treatments (radiation and chemotherapy) is to kill the dividing cells responsible for the formation of the tumor mass. The well-known side effects of these types of therapy are loss of hair, loss of appetite, nausea, vomiting and damage to the patient's skin and gastrointestinal tract. When facing radiation and chemotherapy, the damage to the patient's immune system, although less obvious, is the major concern for the Qigong doctor. The cure of the cancer inevitably lies in activating and increasing the function of the immune response, so that it can recognize and eliminate the malignant tissue.

In China, Medical Qigong Therapy is commonly prescribed as an adjunct to both radiation and chemotherapy. The value of Medical Qigong Therapy is that it is very useful in reducing the harmful side effects caused by both radiation and chemotherapies, as well as enhancing the patient's immune system. Both radiation and chemotherapy assist the body in weakening a pathogenic cluster, but do not completely kill all of the tumor or cancer cells. That function is still left to the patient's immune system (which has consequently been weakened by the radiation or chemotherapy). Because Medical Qigong treatments, prescriptions and meditations enhance the body's immune system, its utilization as a adjunctive therapy is paramount.

MEDICAL QIGONG THERAPY AND RADIATION THERAPY

In most cases, radiation is much safer than chemotherapy because it can be directed into one specific area of the patient's body. However, it may also cause scarring that can interfere with the patient's internal organ function. Although radiation therapy is strong, its effect on the patient's body can be corrected by the Qigong doctor with dredging, purging, dispersing and tonifying techniques. The tissue damage left after radiation therapy should be rectified by dredging, purging and dispersing the afflicted area first. Then, after the toxic Heat has been purged, begin to tonify the patient's supporting organs and tissues surrounding the treatment area.

Sometimes the harmful side-effects of radiation therapy can be avoided by giving the patient Resonant Sound Therapy. In order to alleviate the patient's toxic Heat and pain, it is important for them to practice the "She" sound to cool the tissues after radiation treatments. After the organs have been sufficiently cleansed, the doctor may then tonify the patient's tissues, as well as the Wei Qi Fields, which have been damaged by the radiation therapy.

MEDICAL QIGONG THERAPY AND CHEMOTHERAPY

All forms of chemotherapy are cell-killing agents that damage the DNA and injure actively dividing cells, including those of the body's immune system. The tissue damage after chemotherapy is extremely extensive; the white blood cells decrease, causing secondary infections. Unlike radiation therapy, which is generally isolated to specific areas of the patient's body, chemotherapy affects all of the body's internal organs.

When treating patients who have undergone chemotherapy, it is important for the Qigong doctor to dredge, purge and disperse all the patient's Yin and Yang organs. As with radiation therapy, Sound Resonation Therapy is also mandatory in alleviating the patient's pain.

It is important for the patients to practice the "She" sound to cool the tissues after chemotherapy treatments. Specifically, cancer patients should pronounce the "She" Healing Sound therapy several times a day when their blood count is low, after both chemotherapy or radiation therapy. The sound "She" is pronounced six times. Its high pitched sound is in the straight tone, and its low pitched sound is in the dropping and rising tone. This sound is dropped and replaced by the sound "Ha," or the sound for the specific internal organ, as soon as the red and white blood count reaches a normal level.

After pronouncing the sound "Ha" for a certain period of time, add the sounds for the specific internal organs that have been affected (for example, add "Shang" for a patient with Lung cancer, and "Guo" for a patient with Liver cancer, etc.).

When treating the patient, after the diseased organs have been sufficiently cleansed, the doctor may then tonify the patient's Blood, Jing and tissues, as well as their energetic fields, which have been damaged by the chemotherapy.

RELIEVING SYMPTOMS ASSOCIATED WITH RADIATION AND CHEMOTHERAPY

After receiving radiation or chemotherapy, patients may suffer from several internal complications due to the severe organ and tissue trauma caused by these therapies. The following are six common problems resulting from radiation and chemotherapy.

1. A gastrointestinal infection can result from both radiation and chemotherapy, which have a tendency to burn up the body's Yin. This frequently results in causing Rebellious Qi, which is accompanied by such symptoms as nausea, vomiting, and poor appetite. Treat by tonifying the patient's Stomach Yin by prescribing herbs, and use Jing Point Therapy to quiet the digestion by tonifying Pc-6, St-36 points, as well as the Ear Shenmen points.
2. An infection of the Large Intestine can occur from the accumulation of toxins in the Lower Burner creating Damp Heat Symptoms (caused from radiation and chemotherapy). These toxins can cause abdominal pain, constipation or diarrhea with bloody mucous. Treat by tonifying the patient's Yin to prevent loss of Body Fluids (also give astringent herbs), and use Jing Point Therapy to stop any internal bleeding, by tonifying St-25, St-36, St-37, St-38, LI-4 and LI-11 points.
3. A Urinary Bladder infection can be caused by both radiation and chemotherapy that have a tendency to create Damp Heat in the Lower Burner. Damp Heat in the Lower Burner can result in cloudy, bloody and scanty urination, with a feeling of an urgency to urinate but an inability to do so. To treat, use Jing Point Therapy and tonify Sp-6, Sp-9, CV-2, CV-3, Bl-23 and Bl-29 points.
4. Edema in the limbs can occur from both radiation and chemotherapy that have a tendency to create Wind Damp and Deficiency, which leads to an accumulation of Body Fluids in the extremities. Treat by tonifying the Spleen and draining the body of Dampness. Use Jing Point Therapy to tonify Sp-6, Sp-9, Lu-7, LI-4, and Bl-20; also prescribe herbs.
5. A diminished white blood cell count can be caused by radiation and chemotherapy and can lead to secondary infections. Treat by tonifying the patient's Blood and Jing, and prescribe herbs.
6. Pneumonia can be caused by radiation and chemotherapy that have a tendency to cause damage to the Lungs. When both the Lung Qi and Yin Qi are damaged, pneumonia can result. Treat by tonifying the patient's Yin and Lung Qi, and prescribe herbs to enhance the immune system.

CHAPTER 56

QI EMISSION THERAPY FOR SURGERY

Medical Qigong Therapy is useful for treating patients before, during and after surgery. Qi emission can be used to reduce the patient's bleeding, enhance the immune system, minimize the risk of infection, strengthen the body, and to accelerate the recovery rate. Medical Qigong modalities are involved in preoperative therapy, surgery, postoperative therapy, follow-up therapies and remedial prescriptions.

MEDICAL QIGONG AND PREOPERATIVE THERAPY

Although Medical Qigong Therapy has had incredible results in healing and in stopping the progression of certain diseases, it is not a "cure-all." As with other clinical modalities, it has its own limitations. Currently, conventional medicine only utilizes three modalities for treating tumors and cancer; these include surgery, radiation and chemotherapy. In the healing process, undergoing surgery is sometimes unavoidable, and should never be viewed by the patient as a defeat, but only as a necessary step in the healing transition.

Having to face surgery should not be viewed as a negative reflection of a Qigong doctor's healing potential, nor as a patient's inability to heal. Surgery should be viewed as a necessary life saving intervention, that can firmly establish the patient on the road towards health and recovery. It is a positive affirmation of the patient's commitment to getting well and taking responsibility for the healing. Sometimes, surgery is a necessary step towards health and healing.

Before surgery, it is important for the doctor to consider the emotional relationship that the patient has developed with his or her diseased tissues. The mental, emotional, energetic and spiritual aspects of a disease must not be ignored.

The doctor's involvement with the patient and the tissues which are about to be surgically removed is extremely important, since this emotional interaction affects the patient's healing potential. For healing to take place, a trusting relationship with the patient must first be solidly established; this includes a compassionate attitude of the doctor towards the tissues that will be removed. The doctor models the correct attitude to facilitate an accelerated healing for the patient. It is believed that scar tissue formation is in direct proportion to the patient's fears and negative expectations surrounding the surgery. These fears and expectations form energetic and spiritual attachments to the physical body. Often the patient attempts to disconnect these spiritual attachments out of fear and survival instinct.

A patient is spiritually, emotionally and energetically interconnected with his or her body. This energetic attachment includes any and all organs, organ systems, or areas of the body which can be involved in the operation.

A patient may sometimes feel disillusioned about his or her own interpersonal relationship with the body, and try to disconnect all energetic attachments to the body's tissues out of fear and survival instinct. It is important for the Qigong doctor to help the patient get in touch with the suppressed feelings of loss surrounding the tissues which will soon be operated on. This is because surgery represents the death of a relationship with part of the self. Although the relationship that the patient has with the diseased organ is not considered a healthy one, it exists nevertheless. Allowing the patient to deny his or her true feelings related to the surgery interferes with the healing process. Denial may lead to increased scar tissue formation, and can promote the return of certain disease formations.

The Qigong doctor therefore encourages the patient to talk to, and "brief," each organ and tissue area regarding the surgical procedure to prevent further denial, and to promote the release of feelings. Otherwise, the patient may experience feelings of loss, grief and depression; this reaction can of course also be due to the aftereffects of the anesthesia. It is important that these feelings be experienced and expressed before the surgery. After the surgery, the patient may then experience feelings of relief and gratitude about the new changes in his or her body.

To prepare for surgery, the patient is usually given Medical Qigong meditations and prescriptions that strengthen the Lower Dantian, Kidney and Mingmen areas. One, or several sessions may be specifically devoted to allowing the patient to connect with the diseased organ(s), as well as the regions that are to be operated on. A request for divine intervention can facilitate the patient's relinquishing control, and for the removal of any and all energetic armor surrounding the diseased area (and the subsequent release of emotions associated with this armoring). The patient is then encouraged to disconnect any energetic attachments that the diseased tissues have formed with the surrounding cells, facilitating a final closure. This gradual process allows for an easier transition, as the patient's body must completely release any attachment to the diseased tissues during surgery.

Just before surgery, the patient is given a meditation, and encouraged to imagine a divine white light energy submerging and enveloping the regions of the body which are to undergo the operation. The Lower and Middle Dantians, as well as the areas which will soon be operated on, should also be energized. In addition, the Liver should also be energized to make sure that the Blood coagulates properly during the surgery.

USING MEDICAL QIGONG FOR ANESTHESIA

According to research on Western Surgeries (presented at the Second International Symposium on Memory and Awareness in 1992), patients who undergo anesthesia may be aware of both the pain and conversations within the operating room. Many kinds of drugs used to supplement anesthesia, such as neuromuscular blocking agents, paralyze all the muscles in the body but do not affect the central nervous system and consciousness. During surgery, patients have been observed flinching, twitching and making other facial expressions. Many patients later can give an accurate detailed account of the surgical procedure and conversations between the doctors and nurses. Even when unconscious, patients (whether energetically inside or outside of their bodies), can record, see and remember everything.

Qigong energy emitted during surgery, can however, reduce pain and wound shock, as well as calm the patient's Shen. Qi emission also reduces postoperative complications such as respiratory tract infection, functional disorders of the gastrointestinal tract, retention of urine, etc. The energy received by the patient also speeds up the healing process.

Medical Qigong therapy is found to be very useful in relieving pain by affecting the body's neuro-chemicals. The energy stimulates the peripheral and cutaneous nerves that carry sensory information, via the spinal cord, to the brain. This stimulation of the cutaneous nerves activates neurotransmitters which carry pain messages to the brain, and facilitates the closure of the body's pain-relay gates. The brain produces endorphins, or endogenously generated morphine-like chemicals in response to this closure. The body's opiate receptors are then able to dull the pain. This process is the basis for Qigong Anesthesia. Because Medical Qigong therapy safely produces an analgesic affect on the body's cutaneous tissues, its use in hospitals for surgery as well as for pre and postoperative procedures is gradually increasing.

The first operation in which Qigong anesthesia was applied (recorded in modern times), was performed successfully for the removal of a thyroid tumor in the Shanghai #8 People's Hospital, on May 9, 1980. Qigong Master Lin Hou-sheng demonstrated the ability to induce anesthesia during surgery by pointing his fingers at specific acupuncture points, using external Qi projection without the use of any Western anesthetic. The patient's blood pressure, pulse and respiration rate remained stable during the operation, and the patient's physiological function remained normal after the operation. The success of the Qigong anesthesia boosted the resident doctor's confidence and laid a solid foundation for future applications of Qigong anesthesia in surgical operations.

Qigong anesthesia has begun to follow in the wake of the widely accepted acupuncture anesthesia, as a holistic alternative to conventional pharmaceutical methods. The number of cases treated in China with Qigong anesthesia is steadily increasing, primarily for the following six benefits.

1. Arresting the patient's pain,
2. Resisting the pulling reflex action or shock reaction of the body's internal tissues and organs when the scalpel is inserted,
3. Reducing infection,
4. Reducing the body's opposition or contrary action/reaction to operative wounds,
5. Preventing wound shock (response of the body to the tissue trauma), and
6. Promoting the healing of wounded tissues.

Since Qigong analgesia is effective through the stimulation of certain points on the body's surface, both the location of the points, and the type of energetic application are crucial. There are three methods commonly used in selecting points: According to the Channels, According to the Segmental Innervation, and According to the Auricular Points.

1. The analgesic approach used according to the patient's channels includes two main applications:
   - The selection of points according to the course of the channel which traverses the site of the operation, and
   - The selection of points according to the differentiation of symptoms and signs of a disease, as well as the responses that may be elicited from the patient's body during the operative procedure.
2. The analgesic approach used according to the segmental innervation includes three main applications:
   - The selection of points according to the adjacent segment, or an area that is supplied by the same spinal nerve, or an adjacent spinal nerve of the operative site,
   - The selection of points according to the remote segment, in an area not supplied by the same spinal nerve, or an adjacent spinal nerve (on the operative site), and
   - The selection of points according to the stimulation of the nerve trunk within the same segment, stimulating directly the peripheral nerve of the operative site.
3. The analgesic approach used according to the Auricular Points employs the insertion and stimulation of acupuncture needles with Medical Qigong Therapy, and includes three main applications:
   - The selection of points according to the corresponding Auricular areas pertaining to the operative site and its involved internal organs,
   - The selection of points according to the theory of the Yin and Yang Organs pertaining to the operative site and its involved internal organs, and
   - The selection of points according to such things as tenderness, reduction of electro-resistance, the appearance of deformation and/or discoloration when a certain internal organ or area of the body is affected.

It is important preoperatively that the patient have confidence in the doctor's method of Qigong application. Any misgivings should be dispelled by explaining the procedure to gain the patient's full corporation and trust. In order to know the level of response that the patient will experience, it is necessary to test the patient's response to Qigong anesthesia prior to any surgery.

To use external Qi as an anesthetic, the Qigong doctor must first focus Qi into his or her Lower Dantian, increase its charge and density and then extend it out through the palms, or sword fingers, into the patient's body through specific channel points. The goal is to numb a specific area on the patient's body without touching the patient.

When Qigong anesthesia is being administered successfully, 96% of the nerve fibers responsible for pain sensation become anesthetized and the patient loses consciousness within ten minutes. Ten minutes after cessation of the Qigong anesthesia emission, 24% of the anesthesia has disappeared; while 72% of the tissue remains numb. The remaining tissue quickly recovers from the anesthetic effect and the patient quickly returns to consciousness.

Patients suffering from pain caused by such conditions as cancer or dysmenorrhea also respond positively to Qigong anesthesia.

MEDICAL QIGONG THERAPY AND SURGERY

Surgery has been performed in China for thousands of years. In ancient times, the legendary physician Hua Tuo was noted, not only for his expertise in Medical Qigong, acupuncture, massage and herbs, but also for his surgical skills as well. In Western culture, surgical therapies are applied for the removal of tumors, cysts, and abnormal tissue growth, as well as the transplantation of organs (heart, lungs, and kidneys) and the replacement of dysfunctional systems (joint replacement). Surgery, however, having a potential to both hinder and obstruct the body's flow of life force energy, is generally considered a last resort modality.

During surgery, the Qigong doctor assists the surgeon by applying External Qi Emission to the patient's body, energizing and strengthening specific areas. This is done to reduce pain and alleviate or eliminate the pulling reflex action (shock reaction) of the body's internal tissues and organs when the scalpel is inserted, prevent infection, and reduce bleeding.

When assisting surgeons during an operation, I personally have found that it is important to maintain a physical connection with the patient's body before beginning the Qi emission, until the anesthesia has fully taken effect. As the anesthesia relaxes the patient's tissues, the Qigong doctor can feel and see the patient's spirit leave the body.

Just before the scalpel begins its first incision, it is important for the Qigong doctor to physically disconnect from the patient's body. Even though the Qigong doctor has physically disconnected from the patient's tissues, it is extremely important for the Qigong doctor to increase his or her energy extension deeper into the center core of the patient's body. This protects the Qigong doctor from experiencing the shock, and initial trauma from the scalpel's first incision, which resonates throughout the patient's entire body.

It is also important for the Qigong doctor to focus the attention on extending and circulating his or her energy deep into the patient's Taiji Pole while the surgery is being performed. As the patient begins to lose Qi and Blood due to the operation, the Qigong doctor replenishes the patient's lost Qi, as well as energizes the incoming Blood from the transfusion. The Qigong doctor should also slow down the bleeding by slowing the patient's pulse.

During surgery, the surgeon's scalpel will sever several of the patient's channels as the doctor cuts through the surface of the skin and continues into the deeper regions of the patient's body. Each channel that is being disconnected will weaken the patient's energetic field corresponding to that specific organ or organ systems. It is the Qigong doctor's responsibility to maintain connection with the patient's energy field, and also to monitor and maintain the patient's energy level. The Qigong doctor maintains this connection as the surgeons open up the patient's body cavity, move internal organs, remove the diseased tissues (and any associated structures), and then sutures and closes the patient's body cavity.

When the patient is being sutured, the Qigong doctor must facilitate the patient's circulation of Qi through the Microcosmic Orbit; this stimulates the re-connection of any of the patient's internal and external channels which have been severed. The Qigong doctor must also change and rebuild the Energetic Grid formations in the body's internal and external energetic fields. The patient's Energetic Grid is reconstructed to a pre-diseased pattern to prevent the regrowth of the disease.

MEDICAL QIGONG AND POSTOPERATIVE THERAPY

The separation and restructuring of the inner fasciae that occurs during surgery can cause serious postoperative problems by either stopping the Qi from flowing (causing stagnations), or altering the energy's natural course (causing deviations). This is why after the surgery has been completed, it is extremely important for the Qigong doctor to immediately dredge and disperse the Turbid Qi from the patient's body. This is performed by energetically combing over the fresh incisions, to reconnect the patient's energetic preoperative patterns. Energetic combing also promotes the rapid healing of the patient's wounded tissues, reduces the formation of scar tissue, and continues to alleviate the effects of the surgery.

To facilitate an escalated healing, the Qigong doctor must also energize the patient's Kidneys and any energetic field which may have been depleted. Also, to bring the patient's temperature back to normal, and to disperse any feelings of nausea after the anesthesia and shock of surgery wear off, certain Heart, Pericardium and Stomach Channel points require stimulation.

It is important to note that after an operation, the patient's Dantians and all the body's tissues have been depleted, and are in need of revitalization. While the patient is healing, the color of the aura (located in the Wei Qi field surrounding the area of the surgical trauma) is usually dark to light gray. To increase the healing potential, the Qigong doctor gives the patient specific prescriptions in accordance with the internal organ(s) affected, such as white light meditation images. This is prescribed to energize and replenish the patient's damaged tissues and energy fields. The Qigong doctor also continues to work on rebuilding, reconnecting and reinforcing the patient's channels and Energetic Grids which the surgeon has severed during the operation.

MEDICAL QIGONG THERAPY AND RECREATING ORGAN ENERGY

Once an organ has been removed, there remains an energetic "void" within the spatial cavity of the patient's tissues. The energy of the organ, however, still exists within the patient's body as a "Phantom Organ." This energetic phenomena is due to the creative "blue-printing" of the prenatal and postnatal formation of the body's tissues. Because mass and energy are interconnected and interchangeable, it is therefore possible to energetically stabilize, as well as energize, the spatial cavity wherein the surgically removed organ once resided. To assist the patient in recreating active organ energy, the Qigong doctor prescribes the following meditation:

Lungs	Brilliant Pure White
Large Intestines	Abalone-Shell White
Stomach	Deep Yellow
Spleen	Orange Yellow
Heart	Red with Blue Tint
Small Intestine	Pink
Bladder	Deep Blue
Kidneys	Light Pastel Blue
Pericardium	Purple Red
Triple Burners	Orange Red
Gall Bladder	Pale Chartreuse
Liver	Dark Green

Figure 56.1. Organ Color Chart

STAGE 1 - THE HOOKUP

Generally several days after the surgery, while the patient is still recovering, the Qigong doctor has the patient imagine him or herself being connected to the Heavens and rooted to the Earth. Next, the patient uses color visualization.

STAGE 2 - CHOOSING THE APPROPRIATE COLOR

To prescribe the correct color, it is important for the Qigong doctor to know which organ or organ systems have either been removed, or seriously affected by the surgery. The patient is then assigned specific color meditations to tonify and strengthen the energetic fields that support the traumatized tissues. These meditations are also used to reestablish a physical, mental, emotional, energetic and spiritual connection to the area of trauma.

Figure 56.1 categorizes the general colors associated with the body's organs and channels. These colors can be viewed as extensions of energy originating from the original organs.

STAGE 3 - CLEANING AND ENERGIZING THE SPATIAL CAVITY

After the doctor has selected the proper organ color, the patient is given specific images used to cleanse, purify, and energize the tissues. These meditations create a solid energetic transformation that stabilizes the patient's energetic field.

1. The Cleansing and Purifying meditation is as follows. The patient imagines that his or her fingers and toes are straws. As the patient inhales, he or she will imagine divine white light energy flowing from the Heavens and Earth into the fingers and toes, filling the specific area which has been traumatized by the surgery (Figure 56.2). While exhaling, the patient imagines any pathogenic Qi leaving the tissues and body via the fingers and toes. The patient continues to perform this cleansing meditation for several minutes until he or she feels that the specific area has been purified.
2. The Creating and Energizing meditation requires that the patient imagine a clean, vibrant color (the Five Element Color associated with the particular organ), flowing into the spatial cavity, and areas, surrounding the removed organ. As the patient inhales, the organ color fills the vacant cavity, energizing the remaining energetic structure and surrounding tissues. The patient continues with this imagery until the specific organ area is full of heat, light and vibration (Figure 56.3). Because the surgery has permanently removed the organ from the patient's body, it is important for the patient to continue with this meditation every day for the rest of his or her life.



Figure 56.2. As the patient inhales, he or she will imagine the divine white healing light flowing into his or her body through the fingers and toes. This image is used to purge the patient's body and cleanse the tissues.



Figure 56.3. Once the patient is cleansed, in order to energize the tissues, he or she will imagine a clean vibrant energy color flowing into the specific spatial cavity associated with the removed organ.

MEDICAL QIGONG THERAPY AND ORGAN TRANSPLANTATION

Each particular organ in the human body has its own unique history and experience. This emotional memory and experience is active in the donated organ, as well as in the patient's diseased organ. Before the body can, or will receive a foreign organ, there must first be a time of reconciliation between the memories stored within the negative (as well as positive) physical cells of the organ soon to be replaced, and that of the donor's organ. To assist the surgeon in transplanting an organ, the Qigong doctor must perform visceral cleansing, preparation and purification of the transplanted organ. This method is explained in the following three stages:

STAGE 1

The patient must release all attachment to the departing organ. This includes all negative (as well as positive) physical, mental, emotional, energetic and spiritual memories and experiences.

STAGE 2

The history and emotional memory of the transplanted organ must be cleansed. This includes all negative (as well as positive) physical, mental, emotional, energetic and spiritual memories stored within the donor's organs.

STAGE 3

The relationship between the patient's tissues and the spatial cavity wherein the initial diseased organ was, or is located, must be established and harmonized.

The patient's body will either receive or reject the transplanted organ due to unresolved emotional trauma stored within the patient's tissues, or within the transplanted organ itself. Current research reveals that emotions trapped within transplanted organs can surface within the patient's subconscious mind, affecting his or her behavioral patterns. This is manifested through certain unnatural behavioral traits, which are transferred via the donated organ to the patient.

A famous example of a lingering emotional connection between an organ donor, the organ, and the recipient is described in the following true story. A few years ago a young woman (vegetarian) received a heart transplant from a young man who died in a motorcycle accident. Upon being discharged from the hospital, the woman began craving Chicken McNuggets, which was the young man's favorite food. This was in direct opposition to her previous diet and eating habits.

It is important to note here that organ rejection is not always due to the donor or patient's unresolved emotional issues. Organ rejection can also be caused from biological reactions complicating the acceptance of the foreign tissue.

FOLLOW-UP AND REMEDIAL PRESCRIPTIONS

The follow-up and remedial prescriptions will be determined according to the specific type of surgery the patient has undergone. The prescriptions must be designed to purge, strengthen and regulate any organ(s) that have been weakened by the surgery. Follow-up and remedial prescriptions must also circulate the patient's energy to reduce any energetic stagnations which may have been caused by internal organ movement and fascia damage. This will assist the patient in an escalated recovery, as well as reduce postoperative depression, which often follows after major surgery.

Sometimes, when assisting a patient who is healing from a severe disease (i.e., malignant tumors), additional Western therapies such as radiation or chemotherapy are required. The following is a testimonial by a patient of mine, Thea Sagen (female - age 50), illustrating the use of Qigong therapy in combination with radiation therapy.

Here is a summary of events surrounding my pancreatic surgery, June 16, 1997 at Community Hospital of the Monterey Peninsula.

"On June 16, 1997, emergency surgery to remove a fist-sized tumor from the tail of my pancreas, resulted in my former Sifu (Martial Arts Master), Jerry Alan Johnson, changing roles to become an "Energy Therapist." Thanks to my admitting physician, Dr. Stephanie Taylor, who facilitated the arrangement, Dr. Johnson was the first representative of Chinese Medical Qigong therapy allowed to enter surgery at the Community Hospital of the Monterey Peninsula.

As my Energy Therapist, Dr. Johnson conducted a preoperative session during which he facilitated the energetic and emotional release of my tumor. He then accompanied me into the four hour surgery, during which he maintained my energy levels, while reminding my tissues of their preoperative energetic patterns in order to facilitate rapid healing. He continued to work with me through the postoperative healing, and followed up several days after surgery. It was his vital support and insights that helped me to undergo the recommended course of radiation therapy.

The following is a synopsis of the Medical Qigong therapy that I experienced along with the traditional Western modalities used to treat my pancreatic islet-cell tumor.

Phase 1. The Preoperative Stage. Consisted of a Medical Qigong session directed toward putting me in touch with the tumor, my relationship to it, and the emotions associated with it. This was followed with an atonement with the Divine and relinquishment of control, removal of the armoring around my tumor, and subsequent release of emotions with it. I actually "saw" the disconnected energetic attachments of the tumor as they detached from my organs and were blowing like ostrich feather segments in a wind. I also saw a bright neon sign on the tumor that identified its emotional source. This entire process took only an hour, yet it facilitated closure with the tumor in order for me to easily release it during the surgery, which immediately followed the session. It also provided me with insights that helped my emotional healing over the months following surgery.

Phase 2. Surgery. I entered surgery without any sedatives and was filled with a tremendous sense of peace and empowerment in knowing that the hospital was honoring my energetic, as well as my physical needs. The surgery lasted for four hours during which Dr. Johnson connected with my energy fields and monitored, as well as maintained, my energy levels. He continued treating me, and working with my energetic fields, as the anesthesia was administered, and as the two surgeons opened my cavity, moved structures, removed the tumor (along with the tail of my pancreas and the spleen), and then sutured and closed my abdominal cavity.

Throughout the surgery Dr. Johnson stood at my head, where energy enters through the crown, and facilitated the running of energy into my center channel in the core of my body. He described his work as following the actions of the surgeons, and my body's response to these actions: the incision, the movement of internal organs, the resection of the tumor, and the final suturing. He used this opportunity to change the energetic grid formations in the tumor bed to prevent regrowth of the tumor, which was malignant.

Phase 3. The Postoperative Stage. This stage involved a continuation of the mitigation of the effects of surgery. He worked to tonify my Kidneys, to bring my temperature up, and to offset the shock of surgery, as well as used acupressure points to calm my heart and stomach during the nausea. I was reminded upon awakening, to do my Microcosmic Orbit exercise. Dr. Johnson then proceeded to "dredge" or comb over the incision to reconnect my pre-energetic channel and tissue patterns in order to facilitate healing, and to reduce scar tissue. The healing of the incision was fast. My doctors later remarked at how quickly I healed, and how little scar tissue there was compared to similar surgeries.

Phase 4. Follow-Up and Remedial Prescriptions. During the days following surgery, Dr. Johnson taught me several meditations: The "Divine Healing Light Meditation" for healing the tumor bed and incision, and the "Heaven and Earth Spleen Meditation" that fuses a ball of energy where the spleen once was – allowing me to continue to produce the energetic pattern of the spleen within my body. I began doing these meditations the day following surgery for the week of hospitalization, and continued to practice them along with the Microcosmic Orbit exercises throughout my recovery.

Phase 5. Radiation. After several weeks of recuperation, I was scheduled to received radiation treatments daily (Monday through Friday) for six weeks. Each day I would perform the Medical Qigong exercises (vocal and physical prescriptions) outdoors in a field overlooking the ocean.

Then I would drive to the hospital for the 15 minutes of radiation, followed by a session with Dr. Johnson every other day. I understood that the Medical Qigong exercises and sessions would offset the heat in the tissues while protecting the surrounding organs from unwarranted harm. There was concern about the possible loss of function in one kidney, but blood tests during the treatments showed no noticeable effects on them, or on my liver. In addition, unexpected by-products of the Medical Qigong sessions involved the release of emotional memories and an experience of the Divine in my healing process.

On alternate days after radiation, I had acupuncture and pranic healing with Jason Gill L.Ac. who teaches classes in Chinese Herbs and Traditional Chinese Medicine at Dr. Johnson's International Institute of Medical Qigong. Through these treatments, and the use of Chinese herbs, my immune system was strengthened. These complimentary modalities, combined with my body's own healing abilities and visualization practice, enabled me to avoid the typical side-effects of nausea and diarrhea. Aided by the positive energy from these two therapists, I was able to maintain my energy levels in sufficient quantity to continue driving to the radiation treatments on my own.

It is hard for me to imagine what this entire experience might have been like without the support of a doctor of Medical Qigong. I am truly grateful for Dr. Johnson's dedication, discipline and expertise that enabled him to be present for me throughout all aspects of this illness. It was a gift that I would encourage other patients to utilize for themselves in combination with any traditional allopathic program for cancer. I had the best of both worlds working for me in a remarkable manner thanks to all of my doctors."

PHANTOM PAINS OF AMPUTATED ORGANS

Amputation may be necessary as a result of severe injury or massive infection, such as gangrene. During surgical amputation, the soft tissues are cut in such a way that they cover the end of the remaining bone to heal completely. This allows the body's tissues to seal and protect themselves from the external environment. "Ghost" or "phantom" pains are caused by the patient's energetic connection with the amputated tissues, through the internal "energetic spacial cavity," or external "energetic boundary system." The phantom limb (usually one of the body's extremities, e.g., finger, hand, arm, etc.) exists in an energetic state and continues to interact with the patient's external Wei Qi field, as well as with the patient's Shen. Any interaction with the space, or energetic field of the amputated organ, will produce a direct response in the patient, similar to that of contacting the actual physical limb.

Rehabilitation programs generally do not prepare the patient for such reactions as phantom pains, which tend to leave the patient perplexed and frustrated. To alleviate the symptoms of phantom pains, the Qigong doctor sedates the patient's Wei Qi field that surrounds the amputated limb, and assists the patient in re-patterning the old energetic field to fit the postoperative tissue formation. The Qigong doctor can also prescribe Juniper Berries, which will relieve the phantom pain symptoms.

MEDICAL QIGONG THERAPY AND THE TREATMENT OF SCAR TISSUE

Medical Qigong therapy may be effective for treating pathologies caused by scarring due to surgical procedures. The formation of scar tissue often becomes the source of other physical problems by either obstructing, or weakening, the flow of Qi within the body's channels. In most cases of pathological scar tissue, the scar itself transverses several channels within the superficial and deep tissues.

The topological relationships of each scar will vary according to each patient. Therefore, different therapeutic approaches may be required for treatment, depending on the patient's strength, weakness, Elemental Constitution, and the patient's emotional state surrounding the surgery. Manifestations of scar tissue pathology include some of the following symptoms:

- a feeling of discomfort, or unpleasant sensations that originates around the scar area,

- radiating sensations that occur when the scar is being pressed, and
- a sharp, pulling type of pain that originates from the scar.

These conditions can be present, even if it has been several years since the surgery was performed.

TREATMENT

Medical Qigong treatment for scar tissue formation follows the principle of emitting Qi along the pathway of the channels. Before treatment, the doctor should take into consideration the energetic flow and function of the channels that have been affected by the surgery. If, for example, a patient's Yang channel (e.g., Stomach) becomes obstructed due to surgery, it can create an Excess condition within the Stomach Channel, which in turn creates a Deficiency of the Spleen Channel. Therefore, the treatment of both the Stomach and Spleen channels should be addressed.

After surgery, some scar tissue formation is inevitable, since both the body's inner-facia and channels (which are responsible for the lubrication of the tissues) have been severed. To minimize the degree of scar tissue formation, the Qigong doctor uses Qi extension techniques on the sutured area, extending his or her intention deep into the patient's body. The doctor's focuses on dispersing stagnations and regulating the flow of the undercurrent of Qi through the sutured tissues. Emphasis should be placed on reconnecting the patient's channels and collaterals. Next, the doctor focuses on regulating the external and internal flow of energy from within and without the patient's tissue area.

In treating scar tissue formation which has laid dormant for quite some time, tissue regulation through Tui Na therapy is required. After using the proper tissue regulation method (see Chapter 37), the Qigong doctor ends the treatment by using the One Finger Skill technique along the line of the patient's external scar. To perform this method, one thumb is placed on the end of the scar, while the doctor's other thumb presses into tissue, slowly outlining the entire scar (this heats and energizes the patient's tissues). The doctor ends the treatment with both thumbs placed at the beginning and ending of the scar, extending his or her energy through the patient's tissue in a circular pattern. This technique naturally induces an energetic emotional release of the memories trapped within the scar tissue.

SECTION XII

MEDICAL QIGONG APPENDICES

INTRODUCTION TO THE APPENDICES

There are many documents discussing the experimental research of Medical Qigong Therapy written within the past ten years. Among these documents, are listed a collection of abstracts from five national congresses on Medical Qigong researches as well as four World Conferences. The research has covered a variety of topics ranging from Medical Qigong and its relationship with: Physics, Chemistry, Biology, Western and Traditional Chinese Medicine, Optics, Magnetism, Electromagnetism, Acoustics and the Projection of Sound Resonation, Fluid Mechanics, Nuclear Physics, Electro-Chemistry, Organic Chemistry, Inorganic Chemistry, Analytical Chemistry, Physiology, Bio-Chemistry, Molecular Biology, Micro-Biology, Cytology, Genetics, Pathology, Pharmacology, Psychology, and Sports Medicine.

The experimental research of Medical Qigong is actually a study with multiple sciences. Of all the research reported, Biology and Medicine are in the forefront of the material collected.

The following research was conducted by distinguished scholars at various Universities, Scientific Academies, and Institutes through out the world (i.e.: Beijing Medical University, Qinghua Medical University, Nanjing Medical University, Tokyo Medical University, Tokyo Electro-engineering University, Higher Energy Institute, Physics Institute, International Institute of Medical Qigong, China Healthways Institute, etc.).

This research was focused on the Extension of Emitted Qi by various Medical Qigong Masters / Doctors, the result being positive in it's conclusion on the effectiveness of Medical Qigong Therapy as a solid and effective clinical modality.

This section of the text is devoted to the scientific approach of analyzing and scrutinizing the claims made as to the actual effectiveness of Medical Qigong Therapy as a clinical modality.

For this purpose, I have elicited the help of my good friend, the renowned scientist and research investigator, Dr. Kenneth M. Sancier. Dr. Sancier (a Material Scientist) is the president of the Qigong Institute, of San Francisco, California, and an active Council Board Member of the World Academic Society of Medical Qigong (Beijing, China). His many years of extensive research in the field of Energetic Medicine has led him to help organize the first International Congress of Qigong in conjunction with the Fifth International Congress of Chinese Medicine (at the University of California, Berkeley) including maintaining an active annual Qigong Science Forum for scientists. He is also responsible for developing the first computerized Qigong Data Base, which is currently being sold worldwide.

Dr. Sancier has actively collected scientific information on Qigong by attending international conferences, and meeting scientists in China, Japan, Canada and the United States. He has published several reviews of clinical and experimental studies of the medical aspects of Qigong therapy in many scientific journals and magazines. Although the following information in this appendix represents but a fraction of Dr. Sancier's findings, I am confident that the reader will find the data fascinating.

Dr. Jerry Alan Johnson   May 2000

APPENDIX 1A
MEDICAL APPLICATIONS OF QIGONG

Kenneth M. Sancier, Ph.D.
Qigong Institute
Menlo Park, California

ABSTRACT

This article reviews selected scientific studies of medical applications of Chinese Qigong. The intention of the review is to outline research on Qigong and its potential for improving health care in western countries. The review centers on clinical and experimental studies to show that Qigong exercise can beneficially affect many functions of the body and improve health. The studies were selected to illustrate the following points: medical applications of Qigong are diverse, some studies were conducted in depth, and many applications hold promise to improve western health care.

Several specific clinical and experimental studies are outlined. The study using electroacupuncture according to Voll shows that almost all organs and functions of the body can be balanced by Qigong. The research on hypertension serves as a model to illustrate the many ways that the effects of Qigong on the body can be measured. Studies on brain waves are included to show that the mind is involved in Qigong and probably in the healing process. Research on Qigong's role in high altitude adaption suggests some practical applications for treating cardiovascular disease. A combination of Qigong and drug therapies is superior to drug therapy alone, as indicated in the case of two diseases, hypertension and cancer. In conclusion, there is a plea to medical practitioners and scientists to collect existing information on medical Qigong, promote research if needed, and identify applications that hold promise for improving western health care.

INTRODUCTION TO MEDICAL QIGONG

Traditional Chinese Medicine (TCM) is a holistic system for promoting health and for healing that includes several therapies such as acupuncture and moxibustion, herbal medicine, acupressure massage, nutrition, and Medical Qigong. These therapies are often used in combinations. The underlying theory of TCM is based on balancing Qi, the vital energy in the body, according to the theory of "yin-yang" and the Five Elements, that has been used for more than three thousand years. In practice, the flow of Qi is regulated, and "blocks" to the flow of Qi are removed. Energy blocks or Qi in excess or deficiency may result from disease, injury or stress. Qigong (pronounced chee gong) has a history of thousands of years, and it is unique among TCM therapies because almost anyone can learn and practice Qigong. However, it best to study Qigong with a qualified teacher to avoid adverse side effects. It is claimed that 60 million people in China practice Qigong daily, primarily to maintain health and achieve long life.

The word Qigong is a combination of two ideas. Qi is the vital energy of the body, and gong is the skill of working of the Qi. Medical Qigong for health and healing consists primarily of meditation, physical movements, and breathing exercises. Qigong practitioners develop an awareness of Qi sensations in their bodies and use their mind, i.e., intention, to guide the Qi in the body. It is said that the benefits of Qigong extend beyond health and healing to enhance spiritual life and even special abilities, such as psychic powers. Qigong is also used in martial arts to help develop physical and mental powers for self defense and healing.

Medical Qigong is divided into two parts: internal and external. Internal Qi is developed by individual practice of Qigong exercises. When Qigong practitioners become sufficiently skilled, they can use external Qi to "emit" Qi (Wai Qi in Chinese) for the purpose of healing another person. There are many reports of the medical efficacy of emitted Qi. This therapy has limited application on a large scale because there are a limited number of skilled Qigong masters. The present article will focus mainly on internal Qi because almost everyone can learn Qigong exercises for maintaining health and for self-healing.

In the early 1980s, scientists in China began investigating the many medical benefits claimed for Qigong. Since then, research on hundreds of medical applications of Qigong has been reported in the literature, which, unfortunately for the West, is written primarily in Chinese. A wealth of material is published in English in the proceedings of international conferences of Qigong. The proceedings contain abstracts of talks given at the conferences, and since 1986 there are 837 abstracts, more than half in English.

EXAMPLES OF MEDICAL APPLICATIONS OF QIGONG

Some examples of the applications of medical Qigong and emitted Qi on humans, animals, cell cultures, and plants were reviewed. Clinical and experimental evidence showing that Qigong exercise and external Qi affects various functions and organs of the body have been discussed. A short list of some of the functions and organs affected by Qigong, and the measurement techniques employed, include: the brain (EEG and magnetometer); blood flow (thermography, sphygmography, and rheoencephalography); heart functions (blood pressure, EKG, and UCG); kidney (urinary albumin assay); biophysical (enzyme activity, immune function, sex hormone levels); eyesight; and tumor size in mice.

In the following discussion, some clinical and experimental research studies will be discussed to illustrate the scope of research on medical applications of Qigong. The studies have been selected because they contain scientific information on important chronic medical conditions, such as hypertension and aging. Most of these studies on Qigong used controls and statistical analysis. This review focuses on the main accomplishments of selected research studies. Details may be omitted because of space limitations or because relevant information is not available. The critical evaluation of research studies will be left to medical specialists.

THERAPEUTIC BALANCING OF THE CHANNELS AND FUNCTIONS OF THE BODY

Electroacupuncture According to Voll (EAV) can monitor the effects of Qigong practice on therapeutic balancing of the Channel system, the classical TCM organs, and body functions. In EAV the electrical conductance of the skin above individual acupuncture points is measured using a low voltage and low current. Diagnosis depends on measuring the relative electrical conductance and its time dependence. An important diagnostic criterion of degeneration of an organ is an "indicator drop" that may occur during the measurement when the conductance reaches an apparent maximum value but then decreases before leveling off.

Measurements were made at 24 acupuncture points at the ends of the Channels of the fingers and toes of subjects and were made by the same operator and equipment. The subjects were asked to perform a Qigong exercise of their choosing, for example, sitting or standing meditation or moving Qigong. Two series of EAV measurements were made before and after healthy subjects practiced Qigong. In the first series, four subjects were examined by EAV before and after they practiced Qigong for 10 to 15 minutes. Qigong exercise decreased the average of the EAV measured values in the range of -19 to -31% ($p<0.004$) for the four subjects. Qigong essentially eliminated the indicator drops. In the second series, each of seven subjects was examined by EAV three times in a blind protocol so that the operator did not know whether a subject had practiced Qigong before the second or third examination. In the second series, Qigong exercise changed the average EAV measured values in the range of -17% to -35% for four subjects and in the range of 4% to 15% for three subjects. Indicator drops again were decreased.

These preliminary results show that Qigong can make significant changes in the therapeutic balancing of the Channel and organ systems, the goal of TCM.



Figure 1. A 30-year folow-up of the effect of Qigong on mortality and stroke of 242 hypertensive patients. Both groups received drug therapy. (Qang. Xu, et al. ref. 7)

HYPERTENSION

Several groups in China have investigated the effects of Qigong on hypertension (i.e., high blood pressure). Research on the short- and long-term effects of Qigong practice on hypertensive patients has been carried out at the Shanghai Institute of Hypertension by Wang Chongxing, Xu Dinghai and their colleagues. Their research is reviewed extensively because it serves as a model of the effects of Qigong on many functions of the body. For these studies, the patients practiced "Yan Jing Yi Shen Gong" for 30 minutes twice a day. This Qigong is claimed to be especially valuable for therapeutic purposes and delaying senility. The Qigong exercise consists of a combination of sitting meditation and gentle physical movements that emphasizes a calm mind, relaxed body, and regular respiration.

PREVENTION OF STROKE AND MORTALITY

In 1991, the researchers reported a 20-year controlled study of the anti-aging effects of Qigong on 204 hypertensive patients. Recently, the researchers performed a 30-year follow-up on 242 hypertensive patients who were divided randomly into a Qigong group (n = 122) and a control group (n = 120). All patients were given drug therapy to control blood pressure, but only the experimental group practiced Qigong 30 minutes a day, twice a day. The results show that the accumulated mortality was 25.41% in the Qigong group and 40.79% in the control group ($p<0.001$). The incidence of stroke was 20.49% and 40.73% ($p<0.01$), and death rate due to stroke was 15.57% and 32.50% ($p<0.01$), respectively. These results, which are shown graphically in Figure 1, indicate that Qigong has potential for preventing strokes and extending life.



Figure 2. Serum estrdiol levels of hypertensive men (ages 40–69) and women (ages 51–57) who practice Qigong one year compared to healthy controls. (Ankun, Eang, et al. ref. 6)

The researchers also reported that over the 20-year period, blood pressure of the Qigong group stabilized while that of the control group increased. Remarkably, during this period the drug dosage for the Qigong group could be decreased and for 30% of the patients could be eliminated. However, the drug dosage for the control group had to be increased. These results suggest that Qigong activated the natural healing process of the body.

IMPROVEMENTS IN HEART FUNCTION AND MICROCIRCULATION

Aged hypertensive patients usually are found to have a deficiency of Heart-energy, which often leads to a weakened function of the left ventricle and a disturbance of microcirculation. The researchers evaluate the effects of Qigong by using ultrasonic cardiography (UCG) and indices of microcirculation. The 120 male subjects, 55 to 75 years of age, were divided into three groups: 46 cases of hypertensive subjects with Heart-energy deficiency, 34 cases without Heart-energy deficiency, and 40 cases with normal blood pressure. Patients whose blood pressure measured more than 160/95 mm mercury were accepted as subjects after regulation with anti-hypertensive drugs for 4 weeks.

The results showed that subjects with Heart-energy deficiency experienced several improvements: increases in cardiac output, ejection fraction mitral valve diastolic closing velocity, and mean velocity of circumferential fiber shortening, while the total peripheral resistance decreased ($p<0.05$-0.01). Significant changes did not occur in the group without Heart-energy deficiency.

Multiple quantitative evaluation of nailfold disturbance in microcirculation was made on the above three groups by observing 10 indices of abnormal conditions: configuration of micrangium, micrangium tension, condition of blood flow, slowdown of blood flow, thinner afferent limb, efferent limb and afferent limb ratio, color of blood, hemorrhage, and petechia. At the beginning of the study, the incidence of microcirculation obstruction for the above three groups was 73.91%, 26.47% and 17.50%, respectively. After practicing qigong for one year, the group with

Heart-energy deficiency showed a decrease in nailfold microcirculation obstruction from 73.91% to 39.31% ($p<0.05$). Significant changes did not occur in the group without Heart-energy deficiency.

These studies show that proper TCM diagnosis is essential for qigong therapy. The investigators emphasized that the kind of qigong must be selected according to the patient's condition.

IMPROVEMENT IN SEX HORMONE LEVELS

One consequence of aging is that the levels of sex hormones change in unfavorable directions. For example, female hormone (estrogen) levels tend to increase in men and decrease in women. Two studies indicate that this trend can be reversed by qigong exercise. The effect of qigong exercise on plasma sex hormone levels was determine for hypertensive men and women. The sex hormones levels were measured before and after qigong practice for one year.

The 70 male patients with essential hypertension (ages 40 to 69; disease stage II) were divided into two groups. For the qigong group (n = 42), the estradiol level (E2) decreased from 70.12 to 47.71 pg/ml, a decrease of 32% ($p<0.01$), while no significant changes occurred in the control group (n = 20). The testosterone levels (T) of both groups decreased about 7%. The value of E2 for the qigong group (47.71 pg/ml) approached that of healthy men (42.23±5.82 pg/ml) of the same age but without hypertension or cardiovascular, pulmonary, hepatic, renal, or endocrine diseases ($p<0.05$). For women (ages 51 to 67, the number in group not available), the aging process was associated with failure of ovarian function manifested by decreased E2 and increased T levels. Qigong resulted in an increase of E2 from 40.9±.3.5 to 51.6±3.5 pg/ml, a value about equal to that of normal menopausal controls without hypertension or cardiovascular, pulmonary, hepatic, renal, or endocrine diseases. The value of T was also increased by qigong from 25.5±2.2 to 37.2±2.2 ng/dl. These favorable changes in estradiol levels, E2, brought about by qigong are summarized in Figure 2 for both men and women.

In an auxiliary study, the 24-hour urinary estradiol levels were determined in 30 men ages 50 to 69. Qigong for one year resulted in a decrease of 31% in E2 and a decrease of 54% in the estradiol/testosterone ratio (E2/T). These changes were accompanied by improvements in symptoms associated with Kidney deficiency hypertension, such as soreness, dizziness, insomnia, hair loss, impotence, and incontinence. The average score for these symptoms was changed by qigong from 5.53±2.31 to 2.83±1.32 ($p<0.001$).

Ye Ming and co-workers reported similar favorable changes in plasma sex hormone levels E2 in 77 male and female qigong exercisers after 2 months qigong compared with 27 controls. They did not observe significant changes in testosterone.

The above studies show that qigong exercise can help restore the sex hormone levels that had deteriorated because of aging.

INCREASED BONE DENSITY

Aging may result in a decrease in bone density, especially in women. As a consequence, bones become more brittle and subject to fracture.

Bone density of male subjects was found to increase by practicing qigong for one year. For subjects 50 to 59 years of age (18 cases), the bone density increased from 0.627±0.040 to 0.696±0.069 g/cm3 ($p<0.01$). For subjects 60 to 69 years of age (12 cases), the bone density increase was somewhat less, namely, from 0.621±0.039 to 0.672±0.083 g/cm3 ($p<0.05$). For both age groups, the bone density increased to values exceeding those of normal men of the same age, 0.695±0.096 and 0.657±0.102 g/cm3, respectively. The results are shown graphically in Figure 3.

It is likely that qigong therapy also would help restore the bone density of women, especially menopausal women. If so, hormone replacement therapy and its side effects could be reduced.

CHANGES IN BLOOD CHEMISTRY IN HYPERTENSIVE PATIENTS

Auxiliary studies by Wang, Xu and co-workers on the effects of qigong exercise on blood chemistry of hypertensive subjects include improvements in plasma coagulation firbrinolysis indices, blood viscosity, erythrocyte deformation index, levels of plasma tissue-type plasminogen activator (tPA), plasminogen activator inhibitor (PAI), VIII factor related antigen (VIII R:AG), and anti-thrombin (AT-III). In another study, they reported that qigong exercise significantly and beneficially changed the activities of two messenger cyclic nucleotides (cAMP and cGMP).

These results provide further evidence that qigong affects many complex functions of the body.

CANCER

Feng Lida pioneered in research showing that emitted qi from qigong masters produced marked changes in cell cultures of cancer cells from mice. Several studies reported the effects of emitted qi on tumors in animals. For example, emitted qi was reported to inhibit the growth of implanted malignant tumors in mice but did not destroy the tumors. Encouraged by the results with animals, researchers carried out clinical research on the effects of qigong on human subjects with cancer. Detailed results are not available in English for all these clinical studies.

Some results are available for a clinical study of qigong as a therapeutic aid for patients with advanced cancer. In this study, 127 patients with medically diagnosed malignant cancer were divided into a qigong group of 97 patients and a control group of 30 patients. All patients received drugs, and the qigong group practiced qigong for more than 2 hours a day over a period from 3 to 6 months. Both groups improved, but the qigong group showed improvements four to nine times greater than the control group for strength, appetite, diarrhea free, and weight gain of 3 kg. The phagocytic rate, which a measure of the immune



Figure 3. Changes in bone density of hypertensive men who practice Qigong one year compared to healthy males of the same age. (Xu Wang, et al. ref. 9)



Figure 4. Comparison of Qigong, drug and drug-alone terapies for patients with advanced cancer. (ref. 25)

function, increased in the qigong group but decreased in the control group. These results are shown in Figure 4.

REVERSING SENILITY

To study the mechanism of keeping fit by qigong, a controlled study was made of 100 subjects classified either as presenile or with senile impaired cerebral function. The subjects were divided into two groups of 50 people each with a mean age of 62.7 years and with a similar distribution of age and sex. The qigong group practiced a combination of static and moving qigong. The control group exercised by walking, walking fast, or running slow. According to TCM method of classifying the vital energy, more than 80% of the patients in each group were classified as deficient in vital function and vital essence of the Kidney. Criteria for judging outcome were based on measuring clinical signs and symptoms including cerebral function, sexual function, serum lipid levels, and function of endocrine glands.

After six months, 8 of the 14 main clinical signs and symptoms in the qigong group were improved above 80%, whereas none of the symptoms in the control group was improved above 45%. These results suggest that qigong can reverse some symptoms of aging and senility.

MIND-BODY REGULATION

The main function of qigong is to regulate the mind, and according to TCM theory the mind leads the qi. The mind-regulating function of qigong mainly refers to the regulation of the functions of the brain and related body reactions. One tenant of qigong is that "the mind leads the qi, and the qi leads the blood." This somewhat mysterious statement can be interpreted to mean that intention (the mind) can direct the qi within the body. This mechanism is perhaps similar to the role of volition in biofeedback self-regulation.

BRAIN WAVES

The main focus of research has been on the effects of qigong on brain waves as measured by electroencephalography (EEG). During static, e.g., sitting meditation, alpha brain waves dominate over beta waves and spread to the frontal areas of the brain. Kawano and Wang have found differences in the EEG of Zen Buddhist priests and qigong masters. During almost all types of qigong training, the frequency of the alpha waves increased in the range from +0.6 to 1.0 Hz. During deep Zen meditation, the frequency decreased in the range from -1.0 to -1.5 Hz, and sometimes theta waves appeared. Also, frontal and occipital alpha waves tended to synchronize with a phase difference that depended on the type of meditation. This phase difference became smaller with qigong meditation (i.e., better synchronization) and larger for Zen meditation. According to Kawano and Wang these differences in brain function suggest that internal qigong involves a "semi-conscious" process, which involves some awareness and activity, while Zen meditation is a neutral process that releases the meditator from all concerns. This difference may relate to qigong being a healing art, whereas Zen is generally not considered to be one.

As mentioned earlier, a qigong master can emit qi to heal a patient, and the literature contains many references to this subject. The interaction between the qigong master and his subject has been followed in double blind tests. Both qigong master and subject were simultaneously measured by EEG, polygraphs, biochemical blood tests, and psychological tests. The EEG studies showed that brain wave patterns of the subject and qigong master were synchronized in type of brain waves and their location in the brain. Such synchronism may be required for healing by emitted qi.

Machi has studied qigong masters by combining EEG measurements with simultaneous measurements of physiological changes. He found that while the qigong master was emitting qi, the alpha-1 waves showed extremely high potential on the right frontal lobe, and there were increases in blood pressure, heart rate, and skin surface temperature. He also detected a far infrared emission with 1 Hz modulation signal coming from the Laogong point (a major acupuncture point in the palm of the hand.)

BLOOD FLOW TO THE BRAIN

Qigong exercise has been shown by rheoencephalography to increase blood flow to the brain. For 158 subjects with cerebral arteriosclerosis who practiced qigong for 1 to 6 months, improvements were noted in symptoms such as memory, dizziness, insomnia, tinnitus, numbness of limbs, and vertigo headache. During these studies, a decrease in plasma cholesterol was also noted. These results may offer hope to people with cerebral arteriosclerosis.

EFFECT OF RAPID AND LARGE CHANGES IN ALTITUDE

Studies have been made to determine whether qigong exercise would protect pilots from altitude stress when they increased altitude by going rapidly from low altitudes to the Tibetan highlands.

CARDIAC FUNCTION

Before entering the Tibetan highland, 66 persons were divided into two groups: a qigong group of 32 young men who did Qiyuan Qigong exercise for 4 weeks, and a control group of 34 young men who exercised to radio music. The two groups of men suddenly entered the highlands from a lower altitude. Before and after entering the highland, measurements were made of symptoms of altitude sickness and physiological changes. The qigong group suffered less altitude stress than the control group as measured by blood pressure, heart rate, oxygen consumption, microcirculation on epex of tongue and nail fold, and temperature at Laogong point (P8) of the left hand ($p<0.01$). The researchers suggest that qigong can prevent stresses from altitude changes.

These results with healthy subjects suggest that qigong also should be effective in improving the health of people with cardiovascular conditions. In fact several research studies have been reported the beneficial effects of qigong on cardiovascular diseases.

MICROCIRCULATION DISORDERS

Air force pilots were randomly divided into two groups: a qigong group of 22 persons who had practiced Qiyuan Qigong exercise for eight weeks, and a control group of 18 persons who did physical exercise for eight weeks before entering the Tibetan highlands. Microcirculation was measured at tongue apex and the nail fold, and also from the temperature at the Laogong point in palm of the left hand. When the men entered the high altitude, abnormal blood pressure and microcirculation of tongue apex and nail fold occurred in both groups. However, the abnormalities were statistically less in the qigong group than in the control group ($p<0.01$). The temperature at Laogong kept steady in the qigong group, but was reduced in the control group ($p<0.05$).

STUDY OF LUNG FUNCTION

The men were divided into three groups. Forty young males were in the qigong group and practiced Qi Yuan qigong for 4 weeks prior to entering the highlands; 40 young men were in the control group and exercised to radio music for 4 weeks prior to entering the highlands; and 40 young males were residents living at high altitudes. The results show that the integral value of symptoms of acute mountain sickness was lower in the qigong than in control group ($p<0.05$—0.01). Pulmonary ventilation of the qigong group was significantly improved compared with the control group ($p<0.05$—0.01), and nearly equal to the resident group.

The favorable outcome of these studies suggests that qigong may be a valuable therapy for people suffering from cardiac, microcirculation and lung disorders.

SUMMARY AND CONCLUSIONS

This review deals with only a small fraction of a large collection of research already performed on medical applications of qigong, mainly in China. Hopefully, the information presented is sufficient to illustrate the potential of qigong exercise for restoring normal body functions. The main conclusion from many studies is that qigong enables the body to heal itself.

Medical practitioners and scientists are encouraged to evaluate the potential value of medical applications of qigong. They should collect as much information as possible from original sources, develop bibliographies, and then determine whether additional research is required to validate given medical applications. They should then recommend those applications most likely to be suitable for western health care. It is recommended that TCM and qigong be considered to complement western medicine.

There are several issues that should be addressed for the successful introduction of qigong into western health care. It is necessary to win the support of scientists, medical practitioners and the public who know very little about TCM and qigong. A crucial step is to collect scientific evidence from research already performed. Regrettably, there are few research reports in English, and original scientific reports in Chinese are often difficult to obtain and translate. Further, some of the best technical research papers are incomplete scientifically. Recently this has become less of a problem in China. Although some scientific reports have flaws, we must not reject all research on qigong. We must give credit to China for developing the science of qigong and recognize that it is a science in development.

On the positive side, qigong is emerging rapidly among a public interested in improving their health. Qigong is a subject being addressed by the public press and in books and magazines. Increasing numbers of medical practitioners are becoming active in alternative medicine, although few physicians have studied TCM. At least one insurance company has paid for qigong therapy. HMOs and state and federally funded medical programs would benefit from paying for qigong therapy because it is effective and inexpensive. Pharmaceutical companies are already exploring many herbs, and these companies also could benefit from qigong research because of the synergic effect between qigong and drugs mentioned in this review. The Office of Alternative Medicine (OAM) of the National Institutes of Health is working to develop a basis for evaluating the merits of different alternative therapies, and in 1994 it funded one grant involving qigong. Incidentally, the Japanese Ministry of International Trade and Industry (MITI) is reported to be taking a pragmatic approach to alternative therapies by encouraging the development of industrial applications of therapies such as acupuncture and qigong.

There are many medical applications of qigong. Some of the most promising for introducing into western health care are chronic problems such as hypertension, cardiovascular disease, aging, asthma, allergies, neuromuscular problems, and cancer. These areas of public health deserve consideration by the western medical establishments.

*The p-value is the probability that two quantities are not different: the smaller the p-value greater the difference.

REFERENCES

1. Qigong Database™ is available from the Qigong Institute,450 Sutter Street, Suite 2104, San Francisco, CA 94108.
2. Sancier K M, Hu B. Medical Applications of Qigong and Emitted Qi on Humans, Animals, Cell Cultures, and Plants: Review of Selected Scientific Studies. Am J Acupuncture.1991:19 (4) 367-377.
3. Sancier K M. The effect of qigong on human body functions. Proceedings, Fifth International Symposium on Qigong, Shanghai, China.1994:179.
4. Sancier K M. The effect of qigong on therapeutic balancing measured by electroacupuncture according to Voll (EAV): a preliminary study. Acupuncture & Electro-Thera Res Int J. in press.
5. Wang Chongxing, Xu Dinghai, Qian Yuesheng, Medical and health care qigong, J Traditional Chinese Medicine. 1991:11(4) 296-301.
6. Kuang Ankun, Wang Chongxing, Xu Dinghai, Qian Yuesheng. Research on the anti-aging effect of qigong. J. Traditional Chinese Medicine. 1991:11 (2) 153-158.
7. Hong Shunhua, et al. Microcirculation of nail fold and immunogenicity after qigong practice for short periods. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 56-57.
8. Li Ziran, Li Liziang, Zhang Boli. Group observation and experimental research on the prevention and treatment of hypertension by qigong. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 113-114.
9. Jing Guinian. Observations on the curative effects of qigong self adjustment therapy in hypertension Proceedings, Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 115-117.
10. Bian Huangxian. Clinical observation of 204 patients with hypertension treated with qigong. Proceedings, First International Congress of Qigong. Berkeley, Calif., 1990: 101
11. Wang Chongxing, et al. The beneficial effect of qigong on the hypertension incorporated with coronary heart disease. Proceedings, Third International Symposium on Qigong, Shanghai, China. 1990: 40.
12. Wu Renzhao, Liu Zhewei. Study of qigong on hypertension and reduction of hypotensor. Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 125.
13. Bornoroni Corrado, et al. Treatment of 30 cases of primary hypertension by qigong techniques. Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 126.
14. Zhang Guifang. Development and application of a series of qigong feedback tapes Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 125.
15. Wang Chongxing, et al. Effects of qigong on preventing stroke and alleviating the multiple cerebro-cardiovascular risk factors—a follow-up report on 242 hypertensive cases over 30 years. Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 123-124.
16. Wang Chongxing, Xu Dinghai, et al. Beneficial effects of qigong on the ventricular function and microcirculation of deficiency in heart-energy hypertensive patients. Pri-

vate communication.

17. Xu Dinghai, Wang Chongxing, et al. Clinical study of delaying effect on senility by practicing "Yang Jing Yi Shen Gong" in hypertensive patients. Proceedings, Fifth International Symposium on Qigong, Shanghai, China, 1994:109.
18. Ye Ming, et al. Relationship among erythrocyte superoxide dismustase activity, plasma sexual hormones (T, E2), aging and qigong exercise. Proceedings, Third International Symposium on Qigong, Shanghai, China. 1990:28-32 (in English and Chinese).
19. Kuang Ankun, Wang Chongxing, Xu Dinghai, Qian Yueshang. Research on "anti-aging" effect of qigong. J Traditional Chinese Medicine. 1991:11 (3) 224-227.
20. Feng Lida, Effect of emitted qi on human carcinoma cells. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 1-4.
21. Feng Lida, Effect of emitted qi on the L 1210 cells of leukemia in mice. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 4-5.
22. Zhao Shan, et al. Preliminary observation of the inhibitory effect of emitted qi on transplanted tumors in mice. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 46-48.
23. Liu Tehfu,Wan Minsheng,Lu Oulun. Experiment of the emitted qi on animals. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 60-61.
24. Feng Lida,Peng Liaomin. Effect of emitted qi on prevention and treatment of tumors in mice. Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 106-107.
25. Sun Quizhi, Zhao Li. Clinical observation of qigong as a therapeutic aid for advanced cancer patients. Proceeding, First World Conf Academic Exchange of Medical Qigong, Beijing, China. 1988: 97-98.
26. Chen Guoguang. The curative effect observed for 24 (cancer) cases under my emitted qigong treatment. Proceedings, Second International Conference on Qigong, Xi'an, China. 1989: 141-142.
27. Lo Jifeng, et al. Changes of peripheral blood cell population and immune functions in 31 nasopharyngeal carcinoma (NPC) patients treated with radiotherapy and qigong. Proceedings ,Third National Academic Conference on Qigong Science, Guangzhou, China. 1990: 94-95.
28. Yu Yi, et al. Effect of self-controlling qigong therapy on the immune function of cancer patients. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China.1993: 128.
29. Zhao Hongmei, Bian Jingnan. Curative effect of intelligence qigong on 122 tumor patients. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China.1993:130.
30. Wang Ying. Clinical observation on 30 cases of cancer treated by qigong therapy Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China. 1993: 131.
31. Xong Jing, Lu Zhong. Curative effect on 120 cancer cases treated by Chinese-Western medicine and qigong therapy. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China. 1993: 131
32. Fu Jingzhi. Treatment of advanced gastric cancer in the aged by the combination of qigong and medicinal herbs. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China. 1993: 132-133.
33. Zhang Shengbing. Effects of mind-regulation by qigong on the human body. Proceedings, Fifth International Symposium on Qigong, Shanghai, China, September. 1994:68.
34. Kawano Kimiko, Wang Fengfong. Difference between the EEG of Zen priests and internal qigong masters. Society of Mind-Body Science. 1994: 3 (1) 99-104. (in Japanese).
35. Machi Yoshio. Various measurements to qigong masters for analyzing qigong mechanism. Society for Mind-Body Science. 1994:3 (1) 65-87. (in Japanese).
36. Kashiwasake Masaki. Double-blind tests of qi transmission from qigong masters to untrained volunteers. Society for Mind-Body Science. 1993:2 (1) 81-87 (in Japanese).
37. Machi Yoshio. Various measurements of qigong masters for analyzing qigong mechanism Society of Mind-Body Science. 1994:3 (1) 65-87. (In Japanese).
38. Liu Yuanliang, He Shihai, Xie Shanling. Clinical observation on the treatment of 158 cases of cerebral arteriosclerosis by qigong. Proceedings, Second World Conference on Academic Exchange of Medical Qigong, Beijing, China. 1993:125.
39. Liu Yuanliang. Private communication, 1993.
40. Mo Feifan, Xu Yongchun, Lu Yongpin, Xu Guang. Study of prevention of cardiac function disorder due to immediate entry into highlands by qigong exercise. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China. 1993: 78.
41. Chu Weizong, et al. Changes of blood viscosity and RCG in 44 cases with cardiovascular diseases after qigong ex-

ercises. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 57-58.

42. Qin Chao, et al. Bidirectional adjustment of blood pressure and heart rate by daoyin tuina on the arterial blood and heart rate. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 107.
43. Wang Chongxing, et al. Beneficial effect of qigong on improving the heart function and relieving multiple cardiovascular risk factors. Proceedings ,Third International Symposium on Qigong. Shanghai, China. 1990: 42 (in Chinese).
44. Mo Feifan, Wan Lurong, Jia ZiZi, Xu Guang. Study of prevention of microcirculation disorders of pilots in highlands by qigong. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China.1993: 78.
45. Mo Feifan, Lu Yongpin, Zhao Guoliang. Effect of exercise with qigong on lung function of persons entering highland. Proceedings, Fifth International Symposium on Qigong, Shanghai, China.1994:186.
46. Wang Chongxing, Xu Dinghai, et al., private communication.
47. Wang Chongxing, Xu Dinghai, et al. Proceedings, Fifth International Symposium on Qigong, Shanghai, China, September. 1994::22 (Chinese),109.
48. Wen-hsien Wu, Intractable reflex sympathetic dystrophy
49. McGee C T, Chow E P Y. Miracle Healing from China — Qigong. 1st ed. Coeur d'Alene, ID: Medipress; 1994: 8-19.

APPENDIX 1B
ANTI-AGING BENEFITS OF QIGONG

Kenneth M. Sancier, Ph.D.

INTRODUCTION

In the early 1980s, scientists in China began to study the medical benefits claimed for qigong. Since then, research on hundreds of medical applications of qigong have been reported in the Chinese literature. Of special interest for the present article are clinical reports of the medical benefits of qigong that claim to retard or reverse some diseases associated with aging.

Most of the original research was reported in Chinese, but access in English to most of this material is possible by reference to the proceedings of international conferences of qigong. Since 1986, ten such proceedings contain about 840 abstracts of talks given at the conferences, more than half of which are in English. These abstracts, along with about 160 abstracts of articles in the scientific literature, have been organized as a computerized database. The database enables searches and development of bibliographies across this entire body of information by using any key word. The clinical outcomes reported in this article are partly based on material in the database and partly on the author's person contacts with researchers.

The word qigong is a combination of two ideas: qi the vital energy of the body, and gong the skill of working of the qi. Medical qigong for health and healing consists primarily of meditation, physical movements, and breathing exercises. Qigong practitioners develop an awareness of qi sensations in their bodies and use their mind, i.e., intention, to guide the qi in the body. The benefits of qigong are said to extend beyond health and healing to enhance spiritual life and even special abilities, such as psychic powers.

Medical qigong is divided into two parts: internal and external. Internal qi is developed by individual practice of qigong exercises. When qigong practitioners have sufficiently mastered the skill, they can "emit" qi (external qi or waiqi in Chinese) for the purpose of healing another person. There are many scientific reports of the medical existence and efficacy of emitted qi. The present article focuses mainly on internal qi because almost everyone can learn qigong exercises for maintaining health and for self-healing, whereas, there are a limited number of skilled qigong masters available for healing.

There are numerous reports of the effects of emitted qi on living systems and the functions and organs of the human body. The present author reviewed some examples of medical applications of qigong and emitted qi on humans, animals, cell cultures, and plants, and he also published some of his experimental research on physiological effects of qigong. He discussed some clinical and experimental evidence showing that qigong exercise and external qi affects various functions and organs of the body. A short list of some of the functions and organs affected by qigong, and the measurement techniques employed (in parentheses), include: the brain (EEG and magnetometer); blood flow (thermography, sphygmography, and rheoencephalography); heart functions (blood pressure, EKG, and UCG); kidney (urinary albumin assay); biophysical (enzyme activity, immune function, sex hormone levels (laboratory analysis); eyesight (clinical); and tumor size in mice.

CLINICAL STUDIES INDICATING THE ANTI-AGING BENEFITS OF QIGONG

Several clinical studies will be described to illustrate the scope of research on medical applications of qigong to treat chronic medical conditions that may affect the aging process. Some details may be omitted because of space limitations. The critical evaluation of the research studies will be left to medical specialists.

THERAPEUTIC BALANCING OF THE CHANNELS AND FUNCTIONS OF THE BODY BY QIGONG

The profound effect that internal qigong practice may have on balancing the energies of the organs and functions of the body is illustrated by measurements using Electroacupuncture According to Voll (EAV). In EAV the electrical conductance of the skin above individual acupuncture points is measured using low voltage and low current. Diagnosis depends on measuring the relative electrical conductance and its time dependence. An important diagnostic criterion of degeneration of an organ is an "indicator drop" that may occur during the measurement when the conductance reaches an apparent maximum value but then decreases before leveling off.

Measurements were made at 24 acupuncture points at the ends of the 12 Channels in the fingers and toes of subjects and were made by the same operator and equipment. The subjects were asked to perform a qigong exercise of their choosing for 10 to 15 minutes, for example, sitting or standing meditation or moving qigong. Two series of EAV measurements were made before and after healthy subjects practiced qigong.

In the first series, four subjects were examined by EAV before and after they practiced qigong. Qigong exercise decreased the average of the EAV measured values of the four subjects in the range of -19 to -31% ($p<0.004$). Qigong eliminated almost all the indicator drops.

In the second series, each of seven subjects was examined by EAV three times in a blind protocol so that the operator did not know whether a subject had practiced qigong before the second or third examination. The results showed that qigong exercise changed the average EAV measured values in the range of -17 to -35% for four subjects and in the range of 4 to 15% for three subjects. Indicator drops again were markedly decreased.

These preliminary results show that internal qigong practice can make significant changes in the therapeutic balancing of the Channel and organ systems.

In a similar type of study, the electric current at acupuncture points on 14 Channels was measured using a single square wave voltage pulse technique. Both a qigong master, who emitted qi, and a qi-receiver were measured simultaneously and continuously. The results show that internal and external qigong produce different values in some measurement parameters, and also some synchronous behavior was observed between the sender and receiver.

BLOOD PRESSURE

The effect of qigong exercise on blood pressure is shown graphically in Fig. 1. The blood pressure (systolic and diastolic) in millimeters mercury is plotted as a function of time over 20 years for the group consisting of 242 patients, 122 in the qigong group and 120 in the control group. During the first two months, the blood pressure of all patients dropped in response to the hypotensive drug. Subsequently, and over the period of 20 years, the blood pressures of the qigong group stabilized while that of the control group increased. Remarkably, during this period the drug dosage for the qigong group could be decreased, while the dosage for the control group had to be increased.

Fig. 1. Effect of qigong on blood pressure of hypertensive patients over 20 years. Qigong group (n = 104) practiced 30 min/day twice/day, control group (n = 100).

MORTALITY AND STROKE

The incidences of mortality and stroke for the 30-year study are shown in Fig. 2. These results show that qigong exercise decreased by about 50 percent the incidence of total mortality, mortality due to stroke, and morbidity due to stroke. At the end of 30 years, 86 patients survived in the qigong group and 68 in the control group. These results clearly show that qigong has significant potential for preventing strokes and extending life.

Fig. 2. Effect of qigong on mortality and stroke of hypertensive patients over 30 years. Both groups received drug therapy; qigong group (n = 122) practiced qigong 30 min/day twice/day; the control group (n = 120).

IMPROVEMENTS IN HEART FUNCTION AND MIRCROCIRCULATION

Aged hypertensive patients usually are found to have a deficiency of Heart-energy, which often leads to a weakened function of the left ventricle and a disturbance of microcirculation. The researchers evaluated the effects of qigong for120 aged patients by using ultrasonic cardiography (UCG) and indices of microcirculation.

Experiments showed that the left ventricular function (LVF) in the hypertensive aged group (80 cases) was lower than that in the aged normal blood pressure group (40 cases), while the LVF in the deficiency of Heart-energy hypertensive patients (46 cases) was lower than in the non-deficiency Heart-energy hypertensive patients (34 cases).

After practicing qigong for one year, cardiac output was increased, the total peripheral resistance decreased, and the ejection fraction mitral valve diastolic closing velocity and the mean velocity of circumferential fiber shortening tended to be increased. Significant changes did not occur in the group without Heart-energy deficiency.

Quantitative evaluation of nailfold disturbances in microcirculation was made on the above groups by observing 10 indices of abnormal conditions: configuration of micrangium, micrangium tension, condition of blood flow, slowdown of blood flow, thinner afferent limb, efferent limb and afferent limb ratio, color of blood, hemorrhage, and petechia. The results showed that hypertension had an accelerating effect on the disturbance of microcirculation. The incidence of disturbance of microcirculation disturbance was 73.9% in the deficiency of Heart-energy hypertensive patients. After a year of qigong practice, the incident of disturbance was 39.1% ($p<0.01$).

The results suggest that qigong exercise has beneficial effects on Heart-energy and regulation of the blood channel, and qigong seems to have improved abnormal conditions of blood circulation.

ENHANCED ACTIVITY OF ANTI-AGING ENZYME SOD

Superoxide dismutase (SOD) is produced naturally by the body but its activity declines with age. SOD is often called an anti-aging enzyme because it is believed to destroy free radicals that may cause aging. The effects of qigong exercise to treat disorders of retired workers were studied by Xu Hefen and coworkers and included determinations of plasma SOD.

For their study, 200 retired workers,100 males and 100 females, ranging in age from 52 to 76 were divided into 2 groups: the qigong exercise group and the control group, and each group consisted of 50 males and 50 females. The main qigong exercise was Emei Nei Gong (one kind of qigong exercises of the Emei School), and was practiced at least 30 minutes a day.

The result showed that the mean level of SOD was increased by qigong exercise. For example, the SOD level was larger in the qigong group (about 2700 μ / g Hb) and than in the control group (1700 μ / g Hb), and this difference was significant ($p<0.001$). This study shows that qigong exercise can stimulate physical metabolism, promote the circulation of Channels and regulate the flowing of qi and blood, thus preventing and treating disorders of aging and promoting longevity.

CARDIOVASCULAR FUNCTION

Several studies reveal the potential benefits that qigong may have for improving the cardiovascular function of those with heart disease as well as old people. This conclusion is based on three studies reporting that qigong exercise can protect healthy pilots from altitude stress when they flew rapidly from a low altitude to the high altitude of the Tibetan highlands.

Before entering the Tibetan highland, 66 healthy young men were divided into two groups: a qigong group of 32 men who did Qiyuan Qigong exercise for 4 weeks, and a control group of 34 men who exercised to radio music. The two groups of men rapidly entered the highlands from a lower altitude. Before and after entering the highland, measurements were made of symptoms of altitude sickness and physiological changes.

The qigong group suffered less altitude stress than the control group as measured by blood pressure, heart rate, oxygen consumption, microcirculation on the epex of tongue and the nail fold, and the temperature at the Laogong point of the left hand ($p<0.01$). The researchers suggest that qigong can prevent stress from altitude changes.

In another study of changes in altitude, healthy young men were divided into three groups. Forty males were in the qigong group and practiced Qiyuan qigong for 4 weeks prior to entering the highlands; 40 men were in the control group and exercised to radio music for 4 weeks prior to entering the highlands; and 40 males were residents living at high altitudes. The results show that the integral value of symptoms of acute mountain sickness was lower in the qigong than in control group ($p<0.01$ to 0.05). Pulmonary ventilation of the qigong group was significantly improved compared with the control group ($p<0.01$ to 0.05), and nearly equal to the resident group.

In another study, air force pilots were randomly divided into two groups: a qigong group of 22 men who had practiced Qiyuan Qigong exercise for eight weeks, and a control group of 18 men who did physical exercise for eight weeks before entering the Tibetan highlands. Microcirculation was measured at tongue apex and the nail fold, and also from the temperature at the Laogong point in palm of the left hand. When the men entered the high altitude, abnormal blood pressure and microcirculation of tongue apex and nail fold occurred in both groups. The abnormalities were statistically less in the qigong group than in the control group ($p<0.01$). The temperature at Laogong kept steady in the qigong group, but was reduced in the control group ($p<0.05$).

The results of these three studies with healthy subjects lead to the conclusion that qigong also should be effective in improving the health of people with cardiovascular conditions including the aged. In fact several research studies have reported such beneficial effects of qigong on cardiovascular diseases. The three studies also provide evidence that qigong exercise is superior to physical exercise such as calisthenics.

COMBINATION OF MEDICAL QIGONG AND DRUGS THERAPY

There is ample evidence in the literature that therapy by a combination of qigong exercise and drugs is superior to that of drugs alone. The advantages of a combination therapy of qigong and drugs over drugs alone were discussed earlier in this paper for hypertension and cancer.

The mechanism of this apparent synergism is not entirely understood, but undoubtedly relates to the fundamental mechanism of qigong. Qigong is believed to remove blocks to the ready flow of the qi (energy), blood, oxygen and nutrients to all cells of the body as well as to promote removal of waste products from cells of the body. Blocks to energy (qi) flow may result from injury, disease or stress.

Increases in qi flow and blood circulation help nourish diseased or stressed tissue, providing a means for the body to heal itself. This mechanism suggests that qigong also could promote drug uptake to tissue and cells via increased blood circulation. Omura's research shows that drug uptake was increased by using qigongized paper (i.e., paper to which emitted qi was sent) applied to afflicted area of the body.

CONCLUSIONS

This review deals with a small fraction of the large collection of clinical research on medical applications of qigong. The information presented is intended to illustrate the potential of qigong exercise for restoring normal body functions in people with chronic conditions, many of which accelerate the aging process. The main conclusion from many studies is that qigong exercise helps the body to heal itself. In this sense, qigong is a natural anti-aging medicine. Two studies indicate that qigong exercise is superior to some physical exercises.

Qigong can complement Western medicine in many ways to provide better healthcare. For example, qigong has special value for treating chronic conditions and as a preventive medicine, whereas Western medicine has special value for treating acute conditions. There are many medical applications of qigong that can complement Western medicine to improve health care. Some examples include chronic problems such as hypertension, cardiovascular disease, aging, asthma, allergies, neuromuscular problems, and cancer. These areas of public health deserve consideration by the Western medical establishment.

REFERENCES

1. Kenneth M. Sancier, Ph.D., Copresident & Director of Research, 561 Berkeley Avenue, Menlo Park, CA 94025, USA. Phone/Fax +1-415-323-1221.
2. Some of the material in this article was adapted from the article, "Medical Applications of Qigong," by K.M. Sancier, Ph.D., and published in Alternative Therapies in Health and Medicine. 1996;2 (1): 40-46.
3. Qigong Database™ is available from the Qigong Institute, East West Academy of Healing Arts, 450 Sutter Street, Suite 2104, San Francisco, CA 94108, USA.
4. The p-value is the probability that two quantities are not the same: the smaller the p-value smaller the probability and the more significant the result.
5. Wang C, Xu D. Private communication, May 1995.
6. Duration of the study is not available.

ENDNOTES

[1] Sancier K M, Hu B. Medical Applications of Qigong and Emitted Qi on Humans, Animals, Cell Cultures, and Plants: Review of Selected Scientific Studies. Am J Acupuncture.1991:19 (4) 367-377.

[2] Sancier, KM, Medical applications of qigong. Alternative Therapies in Health & Medicine. 1995; 2(1) in press.

[3] Sancier KM, Chow EPY. Healing with qigong and quantitative effects of qigong. J. American College of Trad. Chinese Medicine. 1989: 7(3):13-19.

[4] Sancier KM. The effect of qigong on therapeutic balancing measured by electroacupuncture according to Voll (EAV): a preliminary study. Acupuncture & Electro-Therapy Res Int J.:1995;19:119-127.

[5] Sancier K M. The effect of qigong on human body functions. Proceedings, Fifth International Symposium on Qigong, Shanghai, China.1994:179.

[6] Kido M. Channel measurements of qi-gong operation and synchronous phenomena. J. Mind-Body Science: 1993: 2(1): 19-26.

[7] Wang Chongxing, Xu Dinghai, Qian Yuesheng, Medical and health care qigong, J Traditional Chinese Medicine. 1991:11(4) 296-301.

[8] Kuang Ankun, Wang Chongxing, Xu Dinghai, Qian Yuesheng. Research on the anti-aging effect of qigong. J. Traditional Chinese Medicine. 1991:11 (2) 153-158.

[9] Hong Shunhua, et al. Microcirculation of nail fold and immunogenicity after qigong practice for short periods. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 56-57.

[10] Li Ziran, Li Liziang, Zhang Boli. Group observation and experimental research on the prevention and treatment of hypertension by qigong. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 113-114.

[11] Jing Guinian. Observations on the curative effects of qigong self adjustment therapy in hypertension Proceedings, Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 115-117.

[12] Bian Huangxian. Clinical observation of 204 patients with hypertension treated with qigong. Proceedings, First International Congress of Qigong. Berkeley, Calif., 1990: 101

[13] Wang Chongxing, et al. The beneficial effect of qigong on the hypertension incorporated with coronary heart disease. Proceedings, Third International Symposium on Qigong, Shanghai, China. 1990: 40.

[14] Wu Renzhao, Liu Zhewei. Study of qigong on hypertension and reduction of hypotension. Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 125.

[15] Bornoroni Corrado, et al. Treatment of 30 cases of primary hypertension by qigong techniques. Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 126.

[16] Zhang Guifang. Development and application of a series of qigong feedback tapes Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 125.

[17] Wang Chongxing, et al. Effects of qigong on preventing stroke and alleviating the multiple cerebro-cardiovascular risk factors—a follow-up report on 242 hypertensive cases over 30 years. Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 123-124.

[18] Wang Chongxing, Xu Dinghai, et al. Beneficial effects of qigong on the ventricular function and microcirculation

of deficiency in heart-energy hypertensive patients. Private communication, January 1994.

[19] Xu Dinghai, Wang Chongxing, et al. Clinical study of delaying effect on senility by practicing "Yang Jing Yi Shen Gong" in hypertensive patients. Proceedings, Fifth International Symposium on Qigong, Shanghai, China, 1994:109.

[20] Ye Ming, et al. Relationship among erythrocyte superoxide dismustase activity, plasma sexual hormones (T, E2), aging and qigong exercise. Proceedings, Third International Symposium on Qigong, Shanghai, China. 1990:28-32 (in English and Chinese).

[21] Kuang Ankun, Wang Chongxing, Xu Dinghai, Qian Yueshang. Research on "anti-aging" effect of qigong. J Traditional Chinese Medicine. 1991:11 (3) 224-227.

[22] Xu, Hefen; Xue, Huining; Bian, Meiguang; Zhang, Chengming; Zhou, Shuying. Clinical study of the anti-aging effect of qigong. Proceedings, Second World Conference for Academic Exchange of Medical Qigong. Beijing, China. 1993: 137.

[23] Mo Feifan, Xu Yongchun, Lu Yongpin, Xu Guang. Study of prevention of cardiac function disorder due to immediate entry into highlands by qigong exercise. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China. 1993: 78.

[24] Mo Feifan, Lu Yongpin, Zhao Guoliang. Effect of exercise with qigong on lung function of persons entering highland. Proceedings, Fifth International Symposium on Qigong, Shanghai, China.1994:186.

[25] Mo Feifan, Wan Lurong, Jia ZiZi, Xu Guang. Study of prevention of microcirculation disorders of pilots in highlands by qigong. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China.1993: 78.

[26] Chu Weizong, et al. Changes of blood viscosity and RCG in 44 cases with cardiovascular diseases after qigong exercises. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 57-58.

[27] Qin Chao, et al. Bidirectional adjustment of blood pressure and heart rate by daoyin tuina on the arterial blood and heart rate. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 107.

[28] Wang Chongxing, et al. Beneficial effect of qigong on improving the heart function and relieving multiple cardiovascular risk factors. Proceedings ,Third International Symposium on Qigong. Shanghai, China. 1990: 42 (in Chinese).

[29] Zhang Shengbing. Effects of mind-regulation by qigong on the human body. Proceedings, Fifth International Symposium on Qigong, Shanghai, China, September. 1994:68.

[30] Liu Yuanliang, He Shihai, Xie Shanling. Clinical observation on the treatment of 158 cases of cerebral arteriosclerosis by qigong. Proceedings, Second World Conference on Academic Exchange of Medical Qigong, Beijing, China. 1993:125.

[31] Liu Yuanliang. Private communication, 1993.

[32] Feng Lida, Effect of emitted qi on human carcinoma cells. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 1-4.

[33] Feng Lida, Effect of emitted qi on the L 1210 cells of leukemia in mice. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 4-5.

[34] Zhao Shan, et al. Preliminary observation of the inhibitory effect of emitted qi on transplanted tumors in mice. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 46-48.

[35] Liu Tehfu,Wan Minsheng,Lu Oulun. Experiment of the emitted qi on animals. Proceedings, First World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1988: 60-61.

[36] Feng Lida,Peng Liaomin. Effect of emitted qi on prevention and treatment of tumors in mice. Proceedings, Second World Conference for Academic Exchange of Medical Qigong, Beijing, China. 1993: 106-107.

[37] Sun Quizhi, Zhao Li. Clinical observation of qigong as a therapeutic aid for advanced cancer patients. Proceeding, First World Conf Academic Exchange of Medical Qigong, Beijing, China. 1988: 97-98.

[38] Chen Guoguang. The curative effect observed for 24 (cancer) cases under my emitted qigong treatment. Proceedings, Second International Conference on Qigong, Xi'an, China. 1989: 141-142.

[39] Lo Jifeng, et al. Changes of peripheral blood cell population and immune functions in 31 nasopharyngeal carcinoma (NPC) patients treated with radiotherapy and qigong. Proceedings ,Third National Academic Conference on Qigong Science, Guangzhou, China. 1990: 94-95.

[40] Yu Yi, et al. Effect of self-controlling qigong therapy on the immune function of cancer patients. Proceedings,

Second World Conf on Academic Exchange of Medical Qigong, Beijing, China.1993: 128.

[41] Zhao Hongmei, Bian Jingnan. Curative effect of intelligence qigong on 122 tumor patients. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China.1993:130.

[42] Wang Ying. Clinical observation on 30 cases of cancer treated by qigong therapy Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China. 1993: 131.

[43] Xong Jing, Lu Zhong. Curative effect on 120 cancer cases treated by Chinese-Western medicine and qigong therapy. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China. 1993: 131

[44] Fu Jingzhi. Treatment of advanced gastric cancer in the aged by the combination of qigong and medicinal herbs. Proceedings, Second World Conf on Academic Exchange of Medical Qigong, Beijing, China. 1993: 132-133.

[45] McGee C T, Chow E P Y. Miracle Healing from China—Qigong. 1st ed. Coeur d'Alene, ID: Medipress; 1994: 8-19.

APPENDIX 1C
THE EFFECT OF QIGONG ON THERAPEUTIC BALANCING MEASURED BY ELEXTROACUPUNCTURE ACCORDING TO VOLL (EAV): A PRELIMINARY STUDY

Kenneth M. Sancier, Ph.D.

ABSTRACT

Electroacupuncture According to Voll (EAV) was used to monitor the effects of qigong practice on therapeutic balancing of subjects. In EAV the electrical conductance of the skin above individual acupuncture points is measured using low voltage and current. Diagnosis depends on measuring the relative electrical conductance and its time dependence. An important diagnostic criterion of degeneration of an organ is an indicator drop which occurs during the measurement when the conductance decreases from an apparent maximum value and then levels off. Two series of EAV measurements were made before and after healthy subjects practiced qigong. Measurements were made at 24 acupuncture points at the ends of the Channels of the fingers and toes of a subject and were made by the same operator and equipment. The subjects were asked to perform a qigong exercise of their choosing. In the first series, four subjects were examined by EAV before and after qigong exercise. Qigong exercise decreased the average EAV measured values of the four subjects in the range of -19 to -31%. Qigong eliminated indicator drops for three subjects and reduced the indicator drop by 80% for the fourth subject. In the second series, each of seven subjects was examined by EAV three times in a blind protocol so that the operator did not know whether a subject had practiced qigong before the second or third examination. Qigong exercise changed the average EAV measured values in the range of -17 to -35% for four subjects and 4 to 15% for three subjects. Indicator drops appeared for three subjects, and they were eliminated for two subjects and reduced by 50% for the third subject. These preliminary studies indicate that EAV can monitor the effects of qigong on changes in the therapeutic balancing of the Channel-organ system. Suggestions are made of how EAV can provide basic information about qigong and its applications.

INTRODUCTION

Electroacupuncture According to Voll (EAV) is one of several electroacupuncture techniques for measuring local skin electrical conductance for diagnostic and therapeutic purpose(1). In general, EAV emphasizes preventive medicine by providing the medical practitioner with a diagnosis of a subject's health and its change at every stage of therapy. In the present study, EAV was used to monitor the effects of qigong practice on therapeutic balancing of subjects (2,3). The equipment is basically a D.C. resistance meter that measures relative changes in electrical conductance of the skin above an individual acupuncture point. Diagnosis depends on measuring the relative electrical conductance and its time dependence. The relative conductance is measured by a meter that is calibrated from 0 to 100. The "normal" value of 50 is expected when the acupuncture point and associated organ are in a physiologically balanced condition. Higher values (higher conductance) are associated with inflammation and lower values (lower conductance) with degenerative disturbances. The indicator drop is an important diagnostic criterion in EAV of a functionally disturbed organ. An indicator drop occurs during a measurement when the conductance of a given acupuncture point increases to an apparent maximum value and then decreases to a lower equilibrium value. In the present study, EAV was used to monitor the effects of qigong practice on therapeutic balancing of healthy subjects.

Two series of EAV measurements were made by the same operator and equipment. In both series, the subjects were asked to perform a qigong exercise of their choosing, usually sitting or standing meditation or moving qigong. The first series was performed during an international conference (4) at which qi and the human Channel system were among the main topics. About six months later, the second series was conducted in San Francisco with different subjects (5).

MATERIALS AND METHODS

The EAV instrument, a Computronix Acupro II system (Synergy Health Systems, 1223 Wilshire Boulevard #321, Santa Monica, CA 90403) was designed and operated by Douglas C. Leber. The instrumental test parameters were: 1.25 volts D.C. output voltage, 12.7 microamperes current output at full scale, and 95,000 ohms resistance at midscale of 50. A schematic of the electrical circuit is shown in Fig. 1. The instrument was calibrated from 0 to 100, and the value of 50 indicates that an organ associated with the acupuncture point was free of pathological problems. The tester pressed the brass probe electrode (0.13 cm diameter and connected to the positive side of the circuit) gently onto the acupuncture point as shown in Fig. 2. To minimized variations of skin conductance due to perspiration, tap water was applied to the skin in the region of the acupuncture point before the measurement. The cylindrical brass hand electrode (1-inch diameter and connected to the negative side of the circuit) was held in the subject's free hand, which was also moistened with water. Twenty four acupuncture points at the ends of the Channels of the fingers and toes of a subject were tested in about 5 minutes. The computer was programmed to provide information on the right and left side of the body for twenty organs and physiological functions of the body.

The subjects were 30 to 65 years of age. They were examined by EAV before and after practicing a qigong exercise for 10 to 15 minutes. The subjects went to a secluded spot to practice their own style of qigong, which was sitting or standing meditation or a form of moving qigong. The subjects were asked to balance their energies, and they were examined within 15 minutes after practicing qigong. One subject was examined by EAV before and after receiving qigong therapy from a qigong master and was also examined by EAV three more times within 22 hours.

RESULTS AND DISCUSSION

Series 1: In Series 1, four subjects were examined by EAV before and after qigong. Subjects A, B, and C, who had practiced qigong for more than 10 years, practiced their own style of qigong for 10 to 15 minutes. Subject D, who had studied qigong for about one year, was given a qigong balancing treatment for about 10 minutes by subject A, a qigong master who used a combination of acupressure massage and emitted qi to balance the Channels and organs of subject D. Subject A was not aware of that variations in the polarity of qi may exist in different parts of the his hands and of the body of the subject (6).

Examples of the EAV measurements before and after qigong are shown for subject D in Fig. 3 and for subject C in Fig. 4. The 20 pairs of horizontal bars represent the measured values at the acupuncture points associated with specific organs and functions of the body as described below the pair of bars. For a given pair of bars, the upper bar represents the value on the left side of the body and the lower bar that on the right side of the body. For example, LUCL and LUCR represents the lung Channel on the left and right side of the body, respectively. The scale for the measured values is shown at the bottom of each graph in the figure. A vertical line at the "normal" reading of 50 is a convenient reference for comparing changes that resulted from qigong practice. The two numerical values to the left of each bar are the actual measured values. The maximum value is on the left and the equilibrium value, which may be lower if there is an indicator drop, is on the right. The magnitude of the indicator drop is represented by a "white" bar and its numerical value is the difference between the maximum and the minimum measured values.

Visual inspection of Fig. 3 and Fig. 4 shows that qigong had decreased all measured values and had either eliminated indicator drops or reduced their numbers. However, qigong did not restore balance to some of the Channels and the corresponding organs. For example after the qigong balancing treatment for subject D, the measured values for the spleen, liver and gall bladder Channels on the right side of the body remained elevated with respect to the others at values of 66, 69 and 67, respectively. In the case of subject C, the measured values remained elevated for the stomach at values of 77 and 66 and for the urinary bladder on the right side of the body at a value of 68, and two of the nine indicator drops remained. These observations suggest that EAV can be used to monitor the effects of qigong therapy on individual organs of the body.

The results of the EAV measurements obtained before and after qigong for each of the four subjects are summarized in Table 1. For each subject, average measured values were calculated from the 40 values, 20 on the left and 20 on right side of the body (see Fig. 3). For each subject, a percentage change (change %) was calculated from the average measured values obtained before and after qigong. The results show that qigong had changed the average measured values of each practitioner in the range of -19 to -31%. The sum of all indicator drops (in meter divisions) for a given EAV examination were either eliminated or reduced markedly by qigong. The style of qigong of each subject and the duration of the practice are noted in a separate column in Table 1.

In Table 1, the plus and minus value that follows an average EAV value is an apparent "standard deviation" that indicates that individual Channels or body functions have measured values greater or less than the average value. This standard deviation would be zero if all the Channels and body functions were balanced and had the same measured AEV values. Individual Channels and body functions may not be balanced for many reasons, including chronic, acute, stress, and emotional factors. The magnitude of the apparent standard deviation may be regarded as a semiquantitative indicator of imbalance in the Channel system.

In a preliminary study to determine possible lasting effects of qigong, subject D was examined by EAV a total of four times over a period of 22 hours. The average measured value was 75.1±5.2 before qigong, 51.5±9.9 twenty minutes after qigong balancing, 55.7±10.4 four hours later after lunch, and 59.0±8.1 twenty-two hours later after breakfast. The increases in the standard deviations after the first 20 minutes were mainly due to large elevations in the measured EAV values of the Channels of the liver at a value of 85, spleen at 85, large intestines at 68, and kidney at 65. These changes are probably caused by food eaten at lunch.

Series 2. A blind protocol was used in Series 2 so that the EAV operator did not know when the seven subjects practiced qigong. This was accomplished by measuring the EAV of each subject three times, and in between measurements the subject left the examination room. After the initial EAV examination, the subjects were given a random selected card instructing them to practice qigong after the first or after the second EAV examination. Later the subjects informed the examiners when they practiced qigong. Of the seven subjects, E, F, G, H, I and K were experienced qigong practitioners, while subject J had studied qigong one year. Computer printouts similar to those in Fig. 3 and Fig. 4 were analyzed for each subject. The averages of the 40 measured values and the sum of indicator drops are tabulated in Table 2. The average measured values obtained just after qigong practice are indicated in boldface.

The results show that qigong practice changed the average measured readings of most subjects. The average measured values decreased for four subjects (E, F, G, H) in the range of -17% to -35%, increased for two subjects (J and K) in the range of 12% to 15%, and remained essentially unchanged for subject I. For subject I, a decrease in the average measured values was observed after qigong, that is, from the second to the third examination (82.7±2.7 to 61.2±11.8, respectively). This decrease may be due to a delay in the effects of qigong exercise. Indicator drops were present in the EAV of only three subjects before qigong, and these drops were either eliminated or decreased by qigong.

In series 2, the average measured values for four subjects (E, F, G, H) showed similar decreases in magnitude as those in series 1. However, the average measured values for the other three subjects (I,J, K) increased. This difference in response of individual qigong practitioners can be accounted for in many ways, such as by differences in qigong style, intention of the practitioner, and physical and emotional states. For example, we had asked the subjects to balance their energies, but subject J later told us that she had tried to increase her qi, thus perhaps explaining the increase of 12%.

Because of scheduling problems, we were unable to carry out control experiments. However, the reproducibilities of successive AEV measurements before or after qigong were satisfactory for five of the subjects. This can be seen in Table 2 by comparing the second and third measurements (after qigong) for subjects E, F, H, and J, and by comparing the first and second measurements (before qigong) for subject G. These successive readings changed less than 4%.

CONCLUSIONS

Our preliminary studies suggest that the EAV technique can monitor the effects of qigong on the therapeutic balancing of the Channel-organ system. EAV also should be valuable in other applications of qigong: 1) evaluating the effectiveness of different types of personal qigong exercises for balancing organs of the body, 2) measuring the receptivity of subjects to emitted qi, 3) evaluating the effects of different kinds of emitted qi, for example, positive and negative qi (8), 4) determining the duration of the balancing effects of qigong, 5) determining the relative healing power of qigong masters for certain medical problems, 6) comparing the relative effectiveness of energy balancing by qigong with other therapies, such as acumassage, acupuncture, healing with hands, Reiki, as well as conventional physical exercise, 7) investigating the therapeutic effectiveness of qi energy stored on materials such as paper (7), 8) investigating the therapeutic effectiveness of electrical, mechanical and laser stimulation(8), and 9) investigating the interaction between a qigong master and a subject (9).

ACKNOWLEDGEMENTS

The author acknowledges the cooperation of Douglas C. Leber of the Computronix Electro-Medical Systems, who designed and operated the EAV instrument. He also acknowledges support in arranging the experiments by Jim Jose of Synergy Health Systems, qigong master Gong Xin Xiong, Harry Kung, Linda Kung, and the qigong practitioners.

REFERENCES

1. Fred M. K. Lamb, Jr., M.D., Julia J. Tsuei, M.D., Zixian Zhao, M.D., M.S.: Bioenergetic Regulatory Measurement Instruments and Devices. Am. J. Acupuncture, Vol.16, No. 4: pp. 345-349, Oct.- Dec., 1988.
2. R. Voll: Twenty years of electro-acupuncture diagnosis in Germany: A progress report. Am. J. Acupuncture, Vol. 3, No. 1: pp. 7-17, 1975.
3. See collection of nine articles on Electroacupuncture According to Voll in the Am. J. Acupuncture, Special EAV issue, pp. 5-99, Second printing, 1989.
4. International Conference on Bioenergetic Medicine, Past, Present and Future, University of Hawaii, September 30, 1989.
5. Presented at the Second World Conference on Academic Exchange of Medical Qigong, Beijing, China, September 1993.
6. Omura,Y., Common factors contributing to intractable pain and medical problems with insufficient drug uptake in areas to be treated, and their pathogenesis and treatment: Part I. Combined use of medication with acupuncture, (+) Qigong energy-stored material, soft laser or electrical stimulation, Acupuncture & Electro-Thera. Res. Int. J., Vol. 17: pp. 107-148, 1992.
7. Omura, Y., Storing of Qigong energy in various materials and drugs (Qigongnization): its clinical application for treatment of pain, circulatory disturbance, bacterial or viral infections, heavy metal deposits, and related intractable medical problems by selectively enhancing circulation and drug uptake, Acupuncture & Electro-Thera. Res. Int. J., Vol. 15: pp. 137-157, 1990.

8. Omura, Y., Connections found between each Channel (heart, stomach, triple burner, etc.) & organ representation area of corresponding internal organs in each side of the cerebral cortex; release of common neurotransmitters and hormones unique to each Channel and corresponding acupuncture point & internal organ after acupuncture, electrical stimulation, mechanical stimulation (including Shiatsu), soft laser stimulation or Qigong, Acupuncture & Electro-Thera. Res. Int. J., Vol. 14: pp. 155-186, 1989.
9. Omura, Y., Unique changes found on the Qigong (chi gong) master's and patients's body during Qigong treatment; their relationship to certain Channels and acupuncture points and the re-creation of therapeutic Qigong states by children and adults, Acupuncture & Electro-Thera. Res. Int. J., Vol. 14: pp. 61-89, 1989.

Table 1. The effect of qigong exercise on the average measured EAV values and sum of indicator drops for each of 4 subjects before and after qigong (Series 1).

Each subject was tested before and after practicing qigong. Subject D was given qigong balancing therapy by subject A. The change (%) refers to the difference between the measured values before and after qigong. The indicator drop (ID) divisions are the sum of all such drops for a given subject. The style and duration of qigong practice is shown in the right-hand columns. Average measured values for before and after qigong were calculated from the average of 40 readings, 20 on the left side of the body and 20 on the right side (see Fig. 3).

Average measured values Sum ID Divisions Qigong
Before After Change Before After Time
SubjectQigongQigong(%)QigongQigongStyle(min.)
A69.0±3.351.4±4.4-26200Moving15
B72.0±3.953.3±7.1-26220Standing10
C67.0±6.654.6±5.7-1912928Sitting10
D75.1±5.251.5±9.9-31530Therapy10

Table 2. A blind study of the effect of qigong exercise on the average measured EAV values and sum of indicator drops for each of 7 subjects before and after qigong exercise (Series 2).

Each subject was tested 3 times. The bold faced numbers indicate measured values obtained just after qigong practice. Secret instructions informed the subjects to practice qigong either after the second or third EAV test. The change (%) refers to the difference in measured values before and after qigong practice. Indicator drop (ID) divisions are summed for a given subject. The style and duration of qigong practice are shown in the right-hand columns. The average measured values before or after qigong were calculated from the average of 40 measured values, 20 on the left side of the body and 20 on the right side (see Fig. 4).

Average Measured Values Sum ID Divisions Qigong
Change Before After Time
SubjectFirst testSecond testThird test (%)QigongQigongStyle(min.)
E61.3±15.439.6±11.238.6±9.7-35140Moving 15
F74.8±3.052.0±5.251.7±4.0-3000Sitting10
G76.1±2.6 79.1±4.258.1±8.6-2700Sitting10
H74.4±3.262.1±12.758.9±10.5-1700Sitting10
I79.2±4.182.7±2.761.2±11.8400Sitting10
J67.5±8.974.5±7.071.1±4.2122814Moving15
K67.2±11.5 53.9±13.562.1±14.71580Sitting10

APPENDIX 2

INTRODUCTION

This second Appendix includes research information on Medical Qigong therapy, collected by my good friend Richard H. Lee, Director of China Healthways Institute, San Clemente, California. Mr. Lee, a council board member of the World Academic Society of Medical Qigong, in Beijing, China, is a specialist in Western medical technology. He has worked extensively with the research department of the Beijing College of Traditional Chinese Medicine, studying the relationship of infrasonic waves emitted as Qi.

This research, focused on the Extension of Emitted Qi by various Medical Qigong Masters / Doctors, was motivated by the pioneering research of Professor Lu Yan Fang at the National Institute of Electro-Acoustics in Beijing, China. Professor Lu developed prototype devices which simulated the frequency output of Medical Qigong doctors.

Mr. Lee has spent many years in China and abroad researching and collecting scientific data which led to the development of several Infratonic Medical Qigong Therapeutic Machines (in Chaotic resonances), which are currently being sold worldwide.

This second Appendix is a continuation of the research devoted to the scientific approach of analyzing and scrutinizing the claims made as to the actual effectiveness of Medical Qigong Therapy as a clinical modality. The result on the effectiveness of Medical Qigong Therapy as a solid and effective clinical modality being positive in conclusion.

The following information in this second appendix represents but a fraction of Mr. Lee's findings, however, I am confident that the reader will find the data fascinating.

Dr. Jerry Alan Johnson May 2000

SCIENTIFIC INVESTIGATIONS INTO CHINESE MEDICAL QIGONG THERAPY

Richard H. Lee
Director China Healthways Institute
San Clemente, California

INTRODUCTION

In the years since the first edition of "Scientific Investigations" was published, the debate over the existence of Qi, the legitimacy of healers, and the reality of PSI phenomena has heated up. While most readers embrace energetic concepts like Qi as a useful framework for understanding otherwise unexplainable phenomena, some continue to reject Qi. Even in China, while an estimated 100 million people practice Qigong, many professionals remain skeptical. Scientists who actually investigate Qigong generally conclude that the phenomena really do happen, but still try to maintain an arms-length distance from it. Many doctors are also reluctant to discuss Qi openly even though most of the general public is quick to identify Qi as feelings of abundant vitality, and the absence of Qi as fatigue.

There appear to be three principal barriers to serious consideration of Qi.

1. Inertia: "There is not enough data." "These studies have not been replicated." This seems to stem from an unwillingness to explore the studies that have been done. This book presents enough information to satisfy the open-minded investigator and the Qi explorer, but nothing was added in this edition to satisfy those who demand overwhelming evidence.
2. Hidden Bias: This is probably the biggest resistance that Qigong research faces. Many people simply refuse to consider the possibility of action at a distance, as exhibited in Qigong and PSI research. On the basis of this single assumption, all empirical data which supports such phenomena must be rejected as mistakes, experimenter bias, or falsification. Nothing was added to this edition to try to overcome this hidden bias.
3. Need for a framework: While the information presented in the first edition of this book answered the question, "Is the phenomenon of Qigong scientifically measurable?," It left readers without a framework other than faith by which they can understand these phenomena. Without a framework of understanding, many are reluctant to accept these strange experimental results.

Others are less concerned about physical substance and seek to understand Qi as an aspect of intention or consciousness. This more closely parallels the approach of most Qigong masters who, through years of training, gradually gain mastery over their own mind (through focus of attention), emotions (through calmness and releasing desires), and physical body (through discipline). Interestingly, this second viewpoint is similar to the view of many skeptics who insist that phenomena of Qi are simply "a product of the mind." Combining the idea that Qi is strongly influenced by the mind, with the research in this book which shows that Qi is measurable in the physical world, we get a picture of Qi as a mind / body connection which is appealing to most readers.

The Chinese do not view Qi as a scientific substance, but rather, as the essence of life, the bridge of consciousness between mind and body, and the "eternal now" in which all activity occurs. The physical body supports physical fields (Qi) which support vibrational frequency patterns (Qi) which allow communication (Qi) between some kind of abstract consciousness (mind) and a physical body which is our vehicle.

Richard H. Lee, January, 1999

QIGONG MASTERS AND ENERGETIC MEDICINE

For thousands of years, China has been a major source of the world's technology. We are surrounded by Chinese inventions such as paper, movable type, gun powder, and surgical anesthesia. And while the West has shot past China in many technological areas, there are still areas where China holds an edge. The Chinese investigations into the phenomenon of Qigong over the last ten years have, in some ways, placed Chinese researchers at the forefront of energetic medicine. Many findings of this research are presented on the following pages.

Qigong has been practiced for thousands of years in China. Yet it has never before had the broad acceptance that it has today. This is because the scientific investigations into the nature of Qigong show clearly that something is going on beyond what physics might predict. Measurable energy is emitted from the hands of those who have mastered these Qigong techniques. These masters can influence events from a distance with energy (or signal) emitted from their hands. Further, these energy emissions and Qigong training exercises have scientifically measurable, beneficial effects on health and healing.

Qigong masters have demonstrated many remarkable feats. Some can soften and bend steel. Some can light fluorescent tubes with their bare hands. Others can kill cancer cells in laboratory experiments, and many can, from another room, alter the brain wave patterns of test subjects including test animals.

The energy they emit from their hands is measurable with scientific equipment in the forms of infrared, magnetic, and acoustical energy. In one test, a strong pulse of static electricity was measured at a point 50 mm above the head of a Qigong master. In another, a strong magnetic field was measured just at the instant that a heavy iron bar hit a Qigong master's head. The bar bent as it would against Superman's head. He was unharmed with no sign of a lump or a bruise.

In 1979 and 1980, the leaders of China decided to put Qigong to the test. The Western scientific test. High technology government organizations across the country, many as prestigious as the National Atomic Energy Lab in Shanghai, and the Space Science and National Electro-Acoustics Institutes in Beijing, started testing Qigong masters and promptly discovered that the phenomenon of emitted Qi was measurable. Some of these laboratories went further and actually developed therapy equipment such as the Infratonic QGM which reproduces the infrasonic component of the emitted Qi. This research has led me into Qigong and taught me many things I didn't think I ever wanted to know.

Today's Western scientists know little about Qigong, but it is an important healing technology in the world today. It is the basis of acupuncture and traditional Chinese herbal medicine, yet it presents effective medical intervention when used alone. Americans have been radiating cancer with energy emitted from machines for the last few decades. The Chinese have been using energy emitted from the hands of Qigong doctors to treat cancer for thousands of years, finding that, in many cases, tumors can be shrunk without side effects.

These scientific experiments are repeatable. Scientific laboratories in America will reach the same conclusions as those in China. The evidence is persuasive that systematic Qigong training produces real benefits. And advanced practitioners can emit energy from their hands that is measurable with scientific equipment. Further, therapeutic equipment has successfully reproduced many of the beneficial effects observed. The Chinese scientific investigations into medical Qigong are indeed at the heart of a medical revolution that is improving the science of health and healing around the world.

THE SCIENCE OF CHINA

For thousands of years China has been a center for the advancement of civilization. The science of China has produced a wide variety of technologies. Gunpowder is the central ingredient to modem warfare. Paper and printing with movable type have for centuries been at the center of education, communication, and information storage. Despite the growth of computers, this system will continue to be the world's dominant information storage method.

Many centuries ago, a physician named Hua Tou invented surgical anesthesia and performed many kinds of surgeries like appendectomies and other of today's popular surgeries. While the Chinese contributed to what has today become modem medicine, they also created "Chinese medicine," a system of medicine based on the Chinese science of "Qi" or vital energy. It is this system from which acupuncture and Chinese herbal medicine have evolved. And at the heart of this system lie the science and practice of Qigong.

QIGONG'S LONG HISTORY

Through the millennia Qigong has been an influential force in the molding of China. Until recently it has been hidden from public view. Like many other disciplines, the art of Qigong has been taught from father to son or from master to disciple only after a strict oath of secrecy has been given. Knowing a science that others don't know gives a practitioner a decided advantage in earning a living. Thus, until recently, very few books have been written about Qigong, particularly about the more advanced techniques of study. The exception is the secret books that have been maintained in religious monasteries, being copied and recopied by studious monks through the centuries.

Even this activity in monasteries came to an abrupt halt with the Communist government in China when Mao put an end to most religious activities. Through the Cultural Revolution, monasteries and temples were shut down. Many of the ancient texts and artifacts were destroyed. Others were stored in government libraries. Many of the Qigong masters were killed. A few went into hiding or escaped from the country.

At the end of the Cultural Revolution, Deng Xiao Peng set about rebuilding much of the cultural heritage of China, allowing limited freedom of religious expression. He also promoted the rediscovery and preservation of traditional Chinese science and medicine, which included Qigong.

It is interesting to note that much of the willingness to share the secret teachings of Qigong came from outside countries. Masters who had emigrated to the West had started teaching the techniques openly without the strict code of silence. And some of the secret Qigong texts that had been taken from the temples and monasteries were published for people around the world to read. Qigong was no longer a secret so there was no longer any value to secrecy in China and Qigong masters became much more willing to teach what they knew.

The most influential factor in the Qigong revival was, perhaps, the new policy on the part of the China government to allow freedom of religion, particularly religion that had a basis in China's cultural heritage. Thus, Taoists and Buddhists who had preserved its teachings in secret for centuries were free to share their knowledge. This allowed Qigong practitioners to demonstrate their skills freely in public without fear of being condemned to death as witches or evil beings. Paranormal skills were again publicly accepted as a product of China's cultural heritage.

The big boost to Qigong came in the early 1980's when modern science turned to study the tradition of Qigong. The leaders of China reasoned that, if Qigong is to be accepted, it must pass the rigorous screening of scientific scrutiny. Studies were funded in the prestigious scientific institutes of China to determine whether the special skills of the Qigong masters could be scientifically verified. The results were most impressive. Many forms of energy were measured coming from the hands or bodies of Qigong practitioners in reproducible scientific experiments.

Scientific investigations into the effectiveness of medical Qigong quickly showed that, for many illnesses, medical Qigong was unsurpassed by any other medical system in the world. The discovery that energy emitted from the hands of Qigong doctors under controlled laboratory conditions was highly effective in killing cancer cells, gained extensive press coverage around the world.

Qigong science is a very new field with valuable technologies just beginning to surface. But given the fundamental nature of these discoveries, Qigong science could easily dominate the world of the 21st century.

SIMULATION OF EMITTED QI

Simulation of emitted Qi has been the goal of much of the Chinese Qigong research that has been conducted since about 1980. Many devices have been developed and tested, some of which have considerable potential. The following is a description of the most common forms:

Infrared devices have been developed some of which, through rare-earth emission surfaces, emit characteristic frequency bands, while others modulate the infrared output according to recorded patterns emitted by Qigong masters. These devices tend to have the most effect where coldness in the body is effectively treated with heat.

Electrical devices are often adapted to deliver current through the skin at frequency patterns that follow patterns produced by Qigong masters. These units have been used principally by acupuncturists.

Acoustical devices, which reproduce the subsonic output of the emitted Qi in the form of deep acting massage action, have been shown to be effective in pain management, circulation of Qi, blood, and endocrine fluids, and relaxation. The Infratonic QGM was used in several of the laboratory tests described in this book to simulate the emitted Qi in experiments. Because this device offers many insights into the nature and function of emitted Qi, and because many of the readers of this book use the Infratonic QGM at home or in their medical practices, much of the research around this device is included in this book.

SCIENTIFIC PLAUSIBILITY OF QI, THE HUMAN ENERGY FIELD

Some readers might tend to reject the findings of this study based on their assumption that the existence of human energy fields and the altering of a person's energy field are outside the laws of physics, and therefore impossible. It is therefore appropriate here to briefly review some of the findings of researchers mostly within the last decade to show that these energy fields are quite measurable with existing equipment and that there is strong evidence that known biophysical mechanisms can account for the observed phenomena.

First, the human body clearly has a vibrating electrical field, measurable for decades through such techniques as EMG, EEG, and EKG. How is this possible? The classical view of the human cell as a bag of water with a nucleus has been, for the most part, rejected in favor of models in which a highly structured collection of filaments, tubes and fibers connect the cell's nucleus not only to the surface of the cell but beyond, in a matrix which connects and interrelates the cells of the entire body (Oschman 1994) and (Pinta and Coffee 1991). Second, helical molecules within the body, such as DNA, keratin, collagen, actin, and myosin have piezoelectric qualities. As they elongate and contract they produce voltages. Also, when voltages are applied, they expand or contract producing mechanical activity and acoustical energy.

While it is well established that electrical signals are produced and received by the body, readers are more likely to question whether a magnetic field interpenetrates and surrounds the body. In 1963 researchers at Syracuse University reported the first measurements of the magnetic field of the human heart, just a millionth the strength of the earth's magnetic field, yet highly coherent and measurable throughout the body and beyond. Then in 1971, the SQUID, a highly sensitive superconducting magnetometer, was developed which was used to measure the magnetic field of the brain, 100 times weaker than that of the heart (Cohen 1972).

Many researchers now believe that the magnetic field of the heart, which extends throughout the body plays a role in regulating biological functions. Then, in 1991, Seto and colleagues measured the magnetic field between the hands of healers to be as strong as 1 milligauss. This is less than 1% the strength of Earth's magnetic field, but 1000 times as strong as the magnetic field produced by the heart. If the heart regulates biological functions with it's weak field, it is certainly feasible that a magnetic field from the hands of healers, measured to be many times stronger than the heart field might influence biological functions.

But, how can a magnetic field be produced from the hands? The Josephson junction, a superconducting semiconductor which is the basis of the SQUID's extremely high sensitivity to weak magnetic fields, has been predicted in quantum physics calculations to be present in living tissue. This was verified just ten years ago. (Del Giudice et al 1989). DNA is one of the biochemical structures shown to act as a superconducting magnetic field detector, able, through the Hall effect, not only to detect very weak magnetic signals, but also to produce magnetic signals (McCraty 1993). Thus DNA may act as a signal amplifier, releasing its energy coherently into passing magnetic waves, much as the ruby rod of a laser releases its light energy coherently with a passing photon to produce a laser beam. This provides a mechanism by which healers might produce the observed relatively strong biomagnetic signals, and by which a test subject or patient might be influenced by such signals (Oschman 1993).

Thus, modern advances in science now provide mechanisms by which it is possible for healers to produce magnetic and electric signals of significant magnitude to influence patients. For those who seek a more indepth overview of this rapidly advancing field of knowledge, "The Scientific Basis of Energy Medicine" by James L. Oschman, 1998, is highly recommended.

REFERENCES

Cohen D 1972 Magnetoencephalography: Detection of the brain's electrical activity with a superconducting magnetometer. Science 175: 664-666

Del Guidice ES, Doglia S, Milani M, Smith JM, Vitiello G 1989 Magnetic flux quantisation and Josephson behaviour in living systems, Physica Scripta 40: 786-791

Dumitrescu I, Kenyon JN Electrographic imaging in medicine and biology, Nevil Spearman Limited, Suffolk England, 1983

Konikiewicz L, Griff L Bioelectrography a new method for detecting cancer and monitoring body physiology, Leonard Associates Press, Harrisburg, 1984

Lee R Bioelectric vitality- exploring the science of human energy, China Healthways Institute, 1997

Liu G, Wan P, Peng X, Zhong X The influence of the emitted Qi on the auditory brainstem evoked responses (ABER) and auditory middle latency evoked responses (MLR) in cats, Proceedings of the First World Conference for Academic Exchange of Medical Qigong, Beijing College of Traditional Chinese Medicine, 1988.

McCraty R, Atkinson M, Tiller WA 1993. New electrophysiological correlates associated with intentional heart focus, Subtle Energies 4: 251-268

Niu Xin, Liu G, Yu Z Measurement and Analysis of the Infrasonic Waves from the Emitted Qi, Proceedings of the First World Conference for Academic Exchange of Medical Qigong, Beijing College of Traditional Chinese Medicine, 1988.

Oschman JL 1993 A biophsysical basis for acupuncture. Proceedings of the First Symposium of the Committee for Acupuncture Research, CAR, Boston.

Oschman JL, Oschman NH 1994, Somatic recall, parts I-II Soft tissue memory / Soft tissue holography, Massage Therapy Journal, American Massage Therapy Association, Lake Worth, FL 34: 36-45, 66-67, 101-116

Pinta KJ, Coffee DS 1991 Cellular harmonic information transfer through a tissue tensegrity-matrix system. Medical Hypotheses 34:88-95

Seto A, Kusaka C, Nakacato S et al 1992 Detection of extraordinarily large bio-magnetic field strength from human hand. Acupuncture and Electro-Therapeutics Research International Journal 17:75-94

THE FUTURE OF QIGONG

Chinese research has found that Qigong training increases balance, quickness and endurance in athletes, and that fighter pilots trained in Qigong have quicker reactions and greater tolerance for the G-forces of sudden turns. Qigong has provided revolutionary treatments for hypertension and cancer, and has the potential for much more.

If, as the Chinese claim, Qi is the fundamental substance of the universe making up both matter and energy, and if we can through our bodies and our awareness, control and direct this Qi, not only within our own bodies, but as has been seen, beyond the limits of our bodies, the fantasy of "the Force" in Star Wars comes within the grasp of reality. Psychic phenomena like telekinesis and mental telepathy become minor extensions of the human manipulation of Qi. The Western ideas of positive thinking take on new meaning:

"The mind is the builder" and "Your thoughts create your reality."

The Chinese science of Qigong gives us proven tools to strengthen our ability to structure the world around us by training our minds and bodies to feel and understand Qi.

Remember that Western science and technology gave us electric motors which, when coupled with man-made equipment, can do the work of a thousand men. This came with our understanding of the principles of electricity. Emitted Qi simulation devices such as the Infratonic QGM provide this work-saving feature of machines. As we learn more about Qi, how it functions, and how it is directed by the human body, we will learn how to construct more and more powerful machines. We will see Qigong devices not only in hospitals but also in agriculture, in building air conditioning systems, in chemical processing plants and in space flight. The scientific Qigong research that started just a decade ago will grow and grow, and perhaps dominate our world of the 21st century.

However, the real emphasis of the Qigong movement and the intent of most Qigong teachers is not just to heal patients with illness, but to expand human potential. The research presented in this book shows that Qigong exercises help people to develop, not only the ability to heal themselves and others, but to do things which scientists considered impossible just a few years ago. Through a study of Qigong, there is strong evidence that we can become more than we ever thought possible.

INFRASONIC QIGONG RESEARCH

The discovery that specific bands of very low frequency sound influence healing and vitality was an accident. A "friend of the family" walked in to the National Electroacoustics Laboratory in Beijing and asked Prof. Lu Yan Fang, an acoustics scientist, if she would test his hand to see if any sound was coming out of it when he emitted Qi. She thought he was crazy but went along because she didn't want to dishonor her family by turning out a friend.

Prof. Lu's discovery that he did indeed emit a very strong signal in the infrasonic range was quite a surprise. This signal was 100 times stronger than that of a healthy, normal person. Elderly and sick people had even lower readings.

To verify that this infrasonic sound had a physiological effect, she built a device to simulate this output and tested it in hospitals. It worked to relieve pain and assist recovery in a wide variety of patients.

Prof. Lu's patent for the Infratonic QGM was the first ever filed in China and her device was awarded three awards for outstanding contribution to science and medicine from Chinese national science organizations.

It is clear from the Chinese infrasonic research presented in this chapter that infrasonic sound is an important component of emitted Qi.

INFRASONIC SIMULATION OF EMITTED QI FROM QIGONG MASTERS

by Professor Liu Guo-long, MD, PhD
Beijing College of Traditional Chinese Medicine
with Richard Lee

SUMMAY OF RESEARCH

Emitted Qi from Qigong masters clearly has a strong effect on the central nervous system, not only in humans but also in animal subjects. Qigong meditation and the Infratonic QGM have similar effects. These findings are summarized below:

Repetition of these tests with animals confirmed that these changes are physiological and not psychological phenomena by eliminating placebo effects.

DOUBTS ABOUT EMITTED QI

At the beginning of my research with Qigong, I was confident that a study of neurophysiology would prove that the "Wai-Qi" emitted by Qigong masters was nothing more than a psychological factor induced by the waving of hands and hypnotic suggestion.

Qigong is a system of physical and mental exercises which has been practiced in China for thousands of years. Up until the 1980's, most Chinese considered Qigong masters (those who have mastered this Qigong training) to be mythical story book characters with super-human powers. However, as the Chinese government began to support scientific research into Qigong, the few remaining true Qigong masters began to surface, amazing researchers with feats like killing bacteria in test tubes and causing previously paralyzed people to get up and walk.

I thought that these were all tricks of one sort or another, perhaps magicians' sleight-of-hand, hypnosis, or optical illusion. When I got the chance to work with people claiming to possess these abilities, I was fascinated. This was my chance to test with scientific equipment, whether there was any truth behind the excitement about Qigong masters. I was confident that I could disprove the myths.



Emitted Qi has a pronounced and repeatable effect on EEG. It enhances frontal and occipital EEG power spectra, and often enhances the frontal so much that frontal becomes the dominant EEG activity whereas occipital dominance is more common. Emitted Qi also enhances and synchronizes the Alpha.

BACKGROUND

I was a specialist in Western medical technology assigned to the research department of the Beijing College of Traditional Chinese Medicine. The project was sponsored by the China Government Department of Education and the Department of Natural Sciences. My research group was assigned to study the relationship of infrasonic waves to emitted Qi. These research grants were motivated by the pioneering research of Prof. Lu Yan Fang at the National Institute of Electro-Acoustics in Beijing, who developed prototype devices to simulate the output of Qigong doctors.

Research has confirmed that humans have a very high degree of acoustic activity in the subsonic range below 20 Hertz (infrasonic), similar to the alpha rhythm of EEG. Also, people with chronic illnesses were found to have a much lower level of infrasonic activity, while Qigong masters had a much higher level of infrasonic output when they were emitting Qi.

The implication was that infrasonic sound might be related to human functioning, and further, that it might be in some way involved in the mechanism of brain functioning. We searched the available scientific literature for research papers for relationships between sound waves and brain waves but found none that had been done.

Extensive clinical research, based on infrasonic Qigong simulation, showed it to be effective for a wide variety of hospital problems. These results are what motivated the National Departments of Education and Natural Sciences to look further into the importance of infrasonic sound and what led to the research I am about to describe:

THE BRAIN AS A DETECTOR OF EMITTED QI

I had learned in my many years of research with the Electro-Encephalograph (EEG) that the human brain responds to even the most subtle of stimuli to the body, so I reasoned that, if there were really any scientific basis to emitted Qi, it would show up in the brain waves of test subjects who were placed in the path of these emissions. I expected to see no difference between the resting states and the Qi emission states.

What we saw was extraordinary. Within a few seconds after the Qigong master began to emit Qi, the subject's EEG would begin to shift. The EEG power spectrum was enhanced on all channels while the most pronounced increase was in the frontal lobe. Also, there was an enhancement and synchronization of the Alpha Rhythm in all channels. When the Qigong master stopped emitting Qi the EEG would gradually shift back toward the baseline readings.

To determine whether infrasonic energy was a significant part of the emitted Qi, we used the infrasonic Qigong prototypes in the same experiment. It was located 18 inches away, directly behind the back of the head of the test subject. The EEG electrodes were attached as before. The simulator was activated for short periods of time and the results recorded. We found that the effects on the receiver's EEG were quite similar to those of the emitted Qi.

Our further research involved monitoring the various sensory-cortical evoked potentials during Qigong meditation, emitted Qi, and infrasonic Qigong simulation. We again found very similar results from all three stimuli. We found that a large portion of the cerebral cortex was inhibited while other somatosensory cortex were excited. One of the significant findings of this study is that the inhibition of the cerebral cortex during Qigong meditation is clearly different from the excitation of the cerebral cortex that is measurable during sleep.

Through Acoustical Brainstem Evoked Response (ABER) it was found that the brainstem structures from the medulla to the hypothalamus were significantly facilitated. The brainstem plays an important role in regulating the functions of the inner organs, motor function, and emotion.

The implications of these studies were startling. Qigong masters can, without touch, voice, eye contact or any other traditional communication means, induce a clear, strong, and highly measurable change in a subject's brain functioning. A synchronization of alpha rhythm indicates deep relaxation, and is closely associated with accelerated healing. Enhanced power spectrum in the frontal lobe is especially significant because the association cortex of the frontal lobe is concerned with higher motor action, higher sensory function, emotional and motivational aspects of behavior, and integration of autonomic function. Facilitation of the brain stem, with its regulation of internal organs, may be a mechanism by which physical healing is induced or accelerated.

Despite these highly significant changes in EEG and evoked potentials, the subject had felt nothing and had no idea of the profound changes taking place within them.

The findings of these studies are solid evidence that a Qigong master can induce real physiological changes in a subject from several feet away, and further, may help to explain the high rate of recovery from chronic degenerative diseases in groups of hospital patients under the care of Qigong masters. These studies also show that the infrasonic Qigong simulator can induce similar changes in brain function and that, through Qigong meditation, a Qigong master can induce these same changes in his own brain.

SCIENTIFIC CONTROLS

There is much disagreement on how emitted Qi affects the brain. Many doctors insist that brain changes are psychologically induced, and that verbal suggestion, impressive hand motion, and expectation of the subject account for the observed phenomena.

To test this, we had several Qigong masters and people pretending to be Qigong masters treat the test subjects. The subjects were told that all were Qigong doctors, and all moved their hands in similar ways. We saw no significant changes in brain wave patterns with the fake Qigong masters, but when the real doctors emitted their Qi, or when we used the infrasonic Qigong simulator, we repeatedly got the highly significant changes.

Even this did not satisfy many of the doctors who reviewed our work, so we repeated the study with animals. We monitored EEG in awake rabbits and ABER in anesthetized cats as Qigong masters emitted Qi toward them. Even though there was no voice or eye contact between the Qigong masters and the animals, and the masters emitted Qi from several feet away, we saw shifts in EEG and ABER (Acoustical Brainstem Evoked Response) similar to those observed in the human subjects. This is a highly convincing result because all kinds of placebo effects are eliminated, yet modification of brain function at a distance remains.

INFRASONIC VS. ELECTROMAGNETIC INTERFERENCE

Extremely low frequency (ELF) electromagnetic signals can affect EEG. There is growing concern about the low frequency radiation produced by 60 Hz electrical power lines located close to people's homes and schools because of apparent disruption of brain and cellular function. ELF signals will cause the principal EEG power spectrum to show a spike at the frequency of the ELF signal. This is because the EEG is easily entrained by ELF signals. When the signal is discontinued, the EEG abruptly returns to normal. Electrical power lines operate at 60 Hz, which corresponds to EEG in the high Beta range, associated with mental anxiety and confusion. The entrainment of EEG to 60 Hz around power transmission lines may be why researchers are finding that people who live close to these power lines show a higher incidence of brain tumors.

The results using the infrasonic Qigong simulator were quite different from ELF signal entrainment. The shifts in EEG were gradual rather than abrupt, and while dominant EEG frequency did drift toward the dominant peak infrasonic frequency, it was a broad spectrum of EEG activity rather than a spike. The enhanced power spectrum continued after simulation was stopped, gradually decreasing and returning to the pretest state. From these observations it is clear that the effects of infrasonic are quite different from the entrainment of ELF electromagnetic signals.

SUMMARY

When I started this project in 1976, I had serious doubts about Qigong masters and emitted Qi. Now I am convinced that emitted Qi is very real and that Qigong is a very valuable art. With the support of the China government, an estimated 50 million Chinese are practicing Qigong daily, and many Western hospitals have added Qigong departments for patients with chronic and degenerative diseases. In addition, the China government has funded extensive scientific research into the nature of emitted Qi with the goal of advancing science and medical technology.

The study of emitted Qi and infrasonic sound, as they relate to human health and functioning, is a broad and exciting field. The use of Qigong in treating chronic degenerative diseases such as cancer and hypertension in China has proven very effective. It has been employed to accelerate healing for thousands of patients with a wide variety of diseases in Chinese hospitals. I am confident that emitted Qi, Qigong meditation, and the infrasonic Qigong simulator will play an increasing role in health care around the world.

SECONDARY ACOUSTIC BIOLOGICAL RESPONSE

(The following is from a technical paper presented in Beijing, China by Professor Lu Yan Fang, the inventor of the Infratonic Qigong Machine.)

"People often talk about sound. Common sense suggests that sound is what the ear can hear, the frequencies between 60 Hz. and 20,000 Hz.

Secondary sound is that sound that is outside of the range of the human ear, specifically low frequency sound below 60 Hz. Secondary sounds travel long distance with little attenuation.

In the 20th century, in the 1930's, this secondary sound was discovered, but it wasn't until the 1960's that it started drawing much attention. Since then the study, measurement, and analysis of the physical features of secondary sound have included:

1. Physical Features
2. Secondary Sound Measurement
3. Technology of Analyzing, and
4. Protecting the Body Against Strong Secondary Signals

Initial secondary sound biological response studies emphasized protecting against high level secondary sound which can damage the human body. Laboratory studies showed that strong secondary sounds beyond 150 dB are harmful to biological bodies. The American Environmental Protection Agency sets standards for secondary sound, concluding that secondary sounds below 130 dB are not harmful.

To this date there had been almost no studies investigating how secondary sounds affect biological processes. And never before has there been any thought of testing of the human body as a secondary sound source. Since 1983, we have worked with more than 70 Qigong masters, and have discovered for the first time that the human body actually emits a secondary sound signal. The frequency distribution peak of the signal is located in the secondary sound region of the sound spectrum, at about 10 Hz.

Through more than 100 repeated lab experiments we found almost identical results of frequency distribution. According to the analysis of test results in 1984, the first infrasonic Qigong prototypes were constructed. These machines used electroacoustic technology to simulate the frequency distribution of the Qigong master's low frequency signal, but stronger. This simulation of the human body life signal emission is then fed back to the human body. In the two years that followed, many clinical and animal tests proved that weak secondary sounds benefit the human body. The discovery that infrasonic sound is a basic substance of Qigong emission opens Qigong science's big door, opening an exciting new field for medical science.

Through hospital and clinical use, 1,134 patients were treated by the Infratonic QGM. Animal studies were also performed. Clinical use and animal use prove that this kind of secondary sound signal can strengthen many functions of the human body. The Qigong machine can have significant treatment value to the human body and works by reproducing the acoustic waves produced by the human body. It can promote circulation, regulate Qi and blood, open channels, and relieve pain.

The Qigong master is not alone in this ability to emit the secondary acoustical signal. Most everybody generates a similar signal. Young people with good health can emit the signal to a degree similar to that of a Qigong master. People with a weak body and elderly people have similar signals but much lower in power. People having Qigong training have a signal that is strong all the time, but especially strong during Qi emission. However, in normal people, as age increases or health condition worsens, the signal decreases. This explains why the human body is only sometimes a source of secondary sound. In the meantime, the body is also a receptor of secondary acoustical signals, and can be benefited by receiving the weak secondary acoustic signals.

Very early in the development of traditional Chinese medicine, this effect had been shown to exist. Anmo, and tuina, Chinese therapeutic massage techniques, give the human body this kind of low frequency stimulation. This stimulation through acupuncture points follows the cell as the basic pathway, and then goes to the meridian, and reaches the problem area. Then the problem can improve. Just like an old Chinese saying: "If you can get enough energy into the problem area, you can use that energy to treat the problem."

The human body's secondary acoustical biological effect is a scientific reality. The human body produces, delivers, emits, receives and controls this low frequency energy. This weak secondary acoustic effect has beneficial biological effect on the human body. It and its relationship with traditional Chinese medicine are of great value to the medical world. It is hoped that all scientists do research in this area.

MEASUREMENT AND ANALYSIS OF INFRASONIC WAVES FROM EMITTED QI

Niu Xin, Liu Guolong and Yu Zhiming
Beijing College of Traditional Chinese Medicine, Beijing, China

The theory of traditional Chinese medicine suggests that Qi is one of the fundamental substances in human bodies. Modem scientific research of the essence of the emitted Qi has yielded some positive results. In order to find out the relation between the emitted Qi and infrasonic waves, to explore the mechanism of the emitted Qi, to find out how a person generates and receives the emitted Qi, and to provide a quantitative physical scale for indicating the strength of the emitted Qi for experimental studies of the effect of it, we measured and analyzed the infrasonic waves from the Qi emitted by Qigong masters.

The test, which was done by an infrasonic testing system made in Denmark, was conducted in a noise-proof room in the Institute of Sound and Electronics under the Ministry of Electronic Industry. The background noise in the room was lower than 30 dB (decibel). The microphone was hung in the air over Laogong (P-8, acupuncture designation for a point in the center of the palm), the distance being 2 cm with no contact.

The experiment tested the release of emitted Qi at Laogong (P-8) in the palm, Mingmen (Du-4), Baihui (Du-20), Dantian, and Jianzhi. Special attention was paid to the test of Laogong (P-8).

1. The peak frequency of the infrasonic waves from the tested Qigong and non-Qigong masters ranged from 8 to 12.5 Hz. In one case the frequency reached 16 Hz. In another two, it reached 6 Hz.
2. The infrasonic waves from the Qigong masters ranged from 45 to 76 dB and those from the non-masters, 45-50 dB. Comparison of the intensity of infrasonic waves during the Qigong state and the non-Qigong state before and after the emission of Qi showed a statistically significant increase ($P<0.01$).* The increase of wave intensity of the Qigong masters compared with that of the non-Qigong masters was also obviously significant ($P<0.01$).* **The energy of the Qigong masters was over 100 times higher than that of ordinary persons.**
3. The masters who had practiced Qigong for many years and often emitted Qi to treat patients had a higher intensity of infrasonic waves, reaching over 70 dB. Those who started to practice Qigong a short time before and mainly practiced *Nei Yang Gong* had a lower intensity of the infrasonic waves (lower than 60 dB.)

Infrasonic and ultrasonic waves are all sound waves which cannot be detected by human ears. The frequency of infrasonic waves is below 20 Hz. Many natural phenomena and artificial actions may generate infrasonic waves. Human bodies may act as a source or a receptor of infrasonic waves giving rise to a biological effect. The infrasonic information we acquire a from the measurement of the Qi makes it possible to study the effect of the emitted Qi.

The Valsalva state in which a Qigong master emits his Qi, is the breath regulating state of Qigong and also the state of emitted Qi in the breath holding exercise. Non-Qigong masters who simulate the Valsalva state also send out more intense infrasonic waves. It shows that every person has infrasonic characteristics. A long period of practicing Qigong helps increase the radiative intensity of infrasonic waves. Entering the Valsalva state helps in the emission of Qi. The Qi emitted by masters who adopted Song Jing Gong (relaxed Quiescent pattern) had more intense infrasonic waves (reaching 72 dB). Thus, the mechanism of the emitted Qi released by different exercise patterns is different.

We have found by a series of tests that very able Qigong masters can keep the energy of infrasonic waves at a relatively high level (over 70 dB). So tests on infrasonic waves can be used to screen Qigong masters.

The human body can generate and emit infrasonic waves. As far as acoustics is concerned, the most suitable resonant frequency of human tissues is within the range of infrasonic waves. It shows that the human body easily receives infrasonic waves. Infrasonic waves are a strong, effective part of the emitted Qi because of their quick, long distance transmission, strong penetration, and non-decreasing vibration. It is possible that infrasonic waves themselves transmit the messages between the Qigong masters and the subjects, or serve as a carrier.

[(P<0.01) means that the probability that these test results would occur by chance is less than 1%. This measure of "statistical significance" tells us that the sample size was large enough and causative factors strong enough that the results of this study are reliable.]*

NEURO SCIENCE—NERVE IMPINGEMENT AND EMITTED QI

China Healthways Newsletter's Interview with Liu Guo Long, MD, PhD
Beijing College of Traditional Chinese Medicine
by Richard H. Lee in Palos Verdes, CA, August, 1991

(This interview came about as a result of requests by readers of China Healthways Newsletter for an explanation of neuroscience as it relates to vital energy and healing.)

Dr. Liu provides a fresh view into the role of vital energy in the nervous system and how vertebral nerve impingement affects Qi.]

China Healthways Newsletter: How has your research changed your views on Qi?

Dr. Liu: I started my research with the intention of proving that there was no physiological basis for Qigong, that it was nothing more than a circus trick. As my research progressed, I became more and more convinced that emitted Qi is both measurable and effective for healing. This was not before I eliminated all possible psychological effects by replacing human subjects in my experiments with laboratory animals and got similar results. In my view, emitted Qi is quite real because it is easily measurable using the human brain as a detector.

CHN: How does Qigong affect the function of the nervous system?

Dr. Liu: This is a very complex question because emitted Qi affects different organs quite differently. First, it clearly increases Electro-Encephalograph (EEG) activity throughout the brain and nervous system, principally in the frontal cortex and in the range of alpha, 8 to 14 Hz. This greater mental activity in the alpha range is associated with clear relaxed state of deep thought, which many agree is effective to relieve tensions and clear the mind. The frontal cortex of the cerebrum is at the top of the hierarchy. It is the center of awareness within the body, directing the cerebellum and brain stem. Increased EEG activity in the frontal cortex would indicate expanded awareness.

Secondly, emitted Qi inhibits the sensitivity of the cerebrum to outside stimulation while facilitating the sensitivity of the hypothalamus and medulla of the brainstem. The cerebrum performs high level conscious activities. When inhibited it receives less visual, auditory, and sensory input, and presumably sends fewer and clearer signals to the brain stem, which, in turn, is responsible for automatic functions such as respiration, vasodilation, and the complex functioning of internal organs. Because the brainstem is facilitated, it is more able to "tune-in" to the needs and illnesses of the body and to activate the needed repairs to restore health. I believe that this enhanced awareness of internal stimuli in the brain stem, combined with reduced sensitivity to outside stimuli, is the primary product of emitted Qi that brings about accelerated healing throughout the body.

CHN: Then, would you say that emitted Qi directed only to the central nervous system can enhance healing in all parts of the body?

Dr. Liu: That's right.

CHN: How can Qi applied to the local injury accelerate healing?

Dr. Liu: Neurons in all parts of the body are in constant oscillation, producing measurable output in the range of 8 to 14 Hz, the frequency of the alpha pattern. Neurons can both emit and receive energy in this frequency band. Therefore nerves throughout the body can be facilitated by the emitted Qi. The application of emitted Qi to the site of an injury facilitates the signals to the brain stem. Stronger and more accurate signals to the brain means a more effective healing response directed to the area of injury, including greater vasodilation, increased lymph flow, and an increased supply of nutrients for cell regeneration.

CHN: Is there any direct effect of emitted Qi on the injured tissue.

Dr. Liu: Yes, of course. Qi is the vital energy that drives the regeneration of tissue. Supplementing the available Qi can directly increase the metabolic activity of the injured tissue just as it increases the EEG activity of the brain.

CHN: How can emitted Qi strengthen the immune system against bacteria and viruses?

Dr. Liu: The mechanisms are the same. A facilitated brainstem and nervous system are able to identify the invader more quickly and accurately and to direct the immune system response more precisely to the area of infection. And, as before, the added supply of Qi fuels a more furious response from the immune system. Chinese herbs such as Huang Qi (Astragalus) are also highly effective at enhancing Qi to accelerate the immune response.

CHN: Can mis-position of spinal vertebrae disrupt this healing process?

Dr. Liu: Most definitely. There are basically three types of nerves, the sensory, the motor, and autonomic. Vertebral pressure on any type of nerve cell can inhibit sensitivity or create false signals. If sensory nerves are affected, important information may never reach the brain, or may arrive confused, misdirecting the healing effort. Affected motor nerves can result in spasm or dropsy, and most importantly, impingement of autonomic nerves affects the function of internal organs and if it continues over a long period, can result in serious degeneration or dysfunction.

Often, impingement of motor nerves can perpetuate the problem. As muscles spasm from false motor nerve signals, they may tend to pull the vertebrae further out of alignment, increasing the impingement. In this case, the problem tends to get worse with time as greater impingement further increases the muscle spasm.

The best way to deal with this sort of nerve impingement is through adjusting the position of spinal vertebrae. Often just the vertebral adjustment is sufficient to release pressure on the motor nerve and release the muscle spasm, allowing complete recovery. However, in many cases the impinged nerve is slow to recover, showing some immediate release of spasm but not complete release. The remaining muscle spasm is sufficient to pull the vertebra out of adjustment again and re-establish the motor nerve impingement.

In these cases of muscle spasm aggravating the nerve impingement, better results are achieved if a nerve facilitation technique is used in conjunction with the adjustment. Emitted Qi or the Infratonic QGM applied a few minutes before or after the adjustment facilitates the nerve to provide greater muscle relaxation and quicker regeneration of the nerve. In upper back disturbances the Chinese herbal formula, Hsiao Yao Pien is also excellent to accelerate progress by promoting improved Qi circulation through the motor nerves and through the muscle itself.

INFRASONIC TREATMENT OF ASTHMA

by Su Cheng Wu,
Department of Pediatrics,
The First Affiliated Hospital Guangxi Medical University,
Nanning, Guangxi, China.

(This clinical study finds that infrasonic sound is effective in treating symptoms of childhood bronchial asthma, and in strengthening immune function as measured by T-lymphocyte population.)

Fifty cases of child bronchial asthma were treated with the Infratonic QGM and routine drugs. T lymphocyte subpopulation (CD2 , CD4, CD8, and CD4/CD8) of peripheral blood was measured to evaluate this treatment's clinical effectiveness on raising immunity. The control group of 15 cases was treated with routine drugs only.

TREATMENT METHOD

Based on the features of child bronchial asthma and a dialectical therapeutics of traditional Chinese medicine, the following four points were treated for 5-10 minutes each morning for 5 days:

Dingchuan (located on the back, 0.5 cun lateral to the lower border of the spinous process of the 7th cervical vertebra). Indications: Facilitating the flow of the lung-qi to relieve asthma. Feishu (Located on 1.5 cun lateral to the lower border of the spinous process of the 3rd thoracic vertebra). Indications: Facilitating the flow of the lung-qi to resolve cough. Tiantu (located on the neck, on the anterior midline, in the center of the suprasternal fossa). Indications: Cough, asthma, chest pain and so on. Danzhong (located on the chest, on the anterior midline, on the level of the 4th intercostal space, on the midpoint of the line connecting the two nipples). Indications: Checking upward adverse flow of the lung or the stomach-qi).

OBSERVATION CRITERIA—FOUR GRADES

1. Clinically controlled: Remission from symptoms. Occasional mild asthma attacks are remitted without taking any medicine.
2. Obviously curative effect: Asthma attack is relieved within a short time.
3. Improvement: Some abatement.
4. Inefficacy: Symptoms, signs and reproduction rate of T lymphocyte subpopulation are unimproved or exacerbated.



T- lymphocytes in Control vs Experimental Groups

THERAPEUTIC RESULTS

94% of the experimental group showed improvement (as shown to the right). In the control group 80% showed improvement as follows: Clinically controlled - 6 cases; obviously curative - 3 cases, improvement - 3 cases, inefficacy - 3 cases. X^2 determination indicates that there is a more obvious therapeutic effect in the treatment group than that in the control group (P<0.01).

LABORATORY RESULTS

T Lymphocyte subpopulation showed a significantly greater increase in the experimental group than in the control group treated by routine drugs alone as shown below:



*Notes: Comparison before/after treatment P<0.01 unless noted: * = P>0.05*

In this study, clinical symptoms of wheezing, coughing and asthma caused by infection of the upper respiratory tract are obviously relieved using the Infratonic device. Testing of peripheral blood showed that the reproduction rate of T lymphocytes subpopulation in treatment group is greater than those receiving routine treatment, indicating increased level of immunologic function of human cells. The Infratonic QGM reduces the course of treatment without discomfort or side-effect. Its biological mechanism of action should be explored in the future.

THE INFRASONIC SIGNAL FROM THE QIGONG PERSPECTIVE

Sun Hua Ling, MD, Beijing Military Qigong Research Institute

(Dr. Sun, a physician and gifted Qigong doctor presents her analysis of the mechanism of emitted Qi and infrasonic signal.)

With the development of human society, health care has become an important part of daily life. Qigong training and techniques and devices like the Infratonic QGM can provide valuable influence. This instrument simulates the low frequency sound of Qigong doctors, which penetrates tissues and organs of the human body, influencing the function of cells, providing clinical results. This study reflects clinical treatment with the QGM of more than 1000 patients.

Cells are units of the human body. Biological electric waves transfer information between cells, forming a biological field of consciousness. The aim of Qigong training is the unification of this field, making the human body more in tune with nature and able to affect nature.

Some "hard Qigong" masters can break stones but can't treat disease because their emitted Qi's amplitude and frequency can not be absorbed by the human body. To be effective, emitted Qi or simulated emitted Qi must be close to the biological waveform of the patient. Then it is easily absorbed and treatment is more likely to be successful. Effective treatment protocols for 30 disease conditions were developed.

MECHANISMS OF THE QGM

1. Relieves pain and edema.
2. Strengthens immune function and reduces inflammation.
3. Normalizes autonomic nervous system.
4. Relieves some symptoms of heart disease.

RELIEVES PAIN AND EDEMA

When applied to sprain of joints, fracture, and arthritis, the QGM has the obvious result of reducing pain distention and edema. It also relieves pain due to sciatic neuralgia, cancer, lumbago, periarthritis of shoulder and stiffness of neck and shoulder muscles. Thus the QGM can effectively treat disease caused by disturbance of blood circulation and can improve local blood circulation.

Patients may feel a sensation of heat, relaxation of muscles, and gradual reduction of pain. This phenomenon may be due to excitation of cells, nerves, and blood vessels around the diseased area. This excitation may contribute to the reduction in pain.

STRENGTHENS IMMUNE FUNCTION AND REDUCES INFLAMMATION

The QGM has a function similar to short wave and ultrashort wave diathermy which strengthens immune function and reduces inflammation. It strengthens metabolism of organs and cells, increasing cellular energy, thus making the immune system stronger.

Diseases such as nephritis, inflammation of intestines and gall bladder, pancreatitis, gas, duodenal ulcer, and infantile dyspepsia, all respond favorably to treatment with the QGM, probably because of this factor of increased cellular energy.

NORMALIZES AUTONOMIC NERVOUS SYSTEM

Where the autonomic nervous system is disturbed, the QGM is often useful. This includes neurasthenia, tenseness of the cerebral cortex, and fatigue. Research shows that the low frequency signals emitted by the QGM penetrate the tissues and organs, altering the internal environment of cells, improving cellular metabolism, and relaxing nerves and muscles, thus regulating the balance between internal and external environment of nerve cells.

Some scholars suggest that emitted Qi may increase cerebral bioelectricity, balancing cell environment, resulting in disappearance of disease. In traditional Chinese medicine, this corresponds to "regulating the meridians and collaterals", "improving blood circulation", and "nourishing internal organs".

RELIEVES SOME SYMPTOMS OF HEART DISEASE

The QGM can relieve symptoms such as lack of blood in the heart muscle, arrhythmia, pressure on the chest, palpitation, and shortness of breath for pulmonary heart disease. This result may be due to improved metabolism of cells and improved local blood circulation.

EMITTED QI TRAINING INCREASES INFRASONIC SOUND EMISSION OF HEALERS

Prof. Lu Yan Fang, National Institute of TV and Electroacoustics, Beijing
Richard H. Lee, Director, China Healthways Institute, USA

(This study supports the premise, proposed by researchers earlier in this chapter, that infrasonic sound can be used as a measure of Qigong ability and indicates that Qigong skills, in this case, the ability to emit infrasonic sound from the palms, can be increased through intensive training.)

Can students in an intensive Qigong training increase the output of infrasonic sound from their hands after one week of training?

To answer this question (and others), 29 Americans traveled to China. The strength of their infrasonic emission was measured before and after the training at the Institute of TV and Electroacoustics, a national institute of technology and standards. Prof. Lu Yan Fang, who conducted the seminal research on infrasonic sound emission two decades ago, conducted the testing. In her research she had found that Qigong masters, powerful healers in China, were able to emit high intensity low frequency sound, 100 to 1000 times stronger than average individuals. Before the experiment she expressed strong doubts as to the possibility of increasing energy emission within one week because Qigong masters require many years to cultivate powerful Qi emission.

Prof. Lu had seen that strong young adolescent males could produce sound as high as 60 dB while average individuals emitted in the 40's and 50's. She was not surprised when in the initial testing 21 of 25 produced scores in the 40's. She felt that an improvement to 60 dB (only one participant had scored in the 60's in the pretest) would suggest improvement to supernormal ability, and that scores above 70 dB would be in the range of the powerful and well known Qigong healers.

A powerful Qigong healer who had scored well in this test before was invited to demonstrate. After several tries, the best he could do was 67 dB, which was 100 times what an average adult could produce, and still in the range of powerful healers, but not nearly as good as he had done previously. He was rather embarrassed and the translator explained that he had worked late the night before and had exhausted his Qi. An hour later he returned covered with perspiration. Apparently, in an effort to redeem himself, he had been building up power doing Qigong exercises for the past hour. This time his score was 78 dB, 10 times the power he had generated just an hour earlier. Participants applauded as he came out of the testing chamber. He had redeemed himself. Interestingly, he was massaging his shoulder as if he had strained it during the Qi emission.

This was a most interesting scenario. First the failure of an experienced Qigong doctor to produce high power, then his performing Qigong exercises to build up his Qi, and finally, his powerful sound emission, offered a persuasive picture that some sort of energy can be stored in the body during Qigong exercises and discharged rapidly through the shoulders to the hands to create intense sound, and possibly straining muscles.

Supporting this finding, one participant was experimenting with the equipment afterwards, emitting Qi into the microphone. At first he could produce high levels of infrasonic sound in front of the microphone, but after five minutes of emitting he could produce only 10% of the power he had produced earlier. He did not feel tired, but as he tried to emit sound, he found that his hand would no longer tremble as it had before. He had apparently exhausted his supply of this form of Qi!

Test Scores: The average score for the group before the training was 47 dB with only four participants scoring above 50. Under the guidance of Master Wan Sujian, a well known Qigong teacher and physician, the group began a 10-day intensive which included climbing mountains and the Great Wall, practicing emitted Qi, and receiving extensive emitted Qi. The group also received physical therapy treatments to open meridians and remove potential blockages in the arms and shoulders which would otherwise restrict the flow of Qi to the hands. The results of both tests are shown below.

After the emitted Qi intensive, the number scoring above 50 dB tripled from four to 13. Five scored above 60 and two above 70. An average increase of 7 dB (to 54 dB) means that students were producing five times the infrasonic energy they had produced before the training. (Statistical significance $t < 0.0005$) Professor Lu was quite impressed. She felt that five of the participants had both the amplitude and spectral distribution associated with powerful Qigong healers.

An interesting technique: While four of the five participants who scored above 60 were men with strong musculature, one petite woman scored 64 dB, which is 10 times the power that anyone else of similar build had scored. When asked her secret, she answered, "Well, to be honest, as I was waiting to emit Qi I silently asked our teacher for help. As soon as I did, I felt a surge of energy flowing through my arm and my hand started trembling powerfully. When I was done, my arm was sore clear up to the shoulder." She had massaged her shoulder after emitting her Qi much as the Qigong master who first demonstrated had done.

SCIENTIFIC QIGONG RESEARCH

Measuring the emitted Qi from Qigong masters has been the purpose of scientific research in many major scientific research institutes in China,



Participants were able to emit substantially higher levels of infrasonic sound after a week-long Qigong training. On the average, scores increased from 47 dB to 54 dB, a five-fold increase in infrasonic energy.

including the following:

- China Immunology Research Center, Beijing
- Institute of Space Medico-Engineering, Beijing
- National Research Institute of Sports Science, Beijing
- Institute of Psychology, Academia Sinica, Beijing
- China Academy of Traditional Chinese Medicine, Beijing
- Institute of Traditional Chinese Medicine, Beijing
- Beijing College of Traditional Chinese Medicine, Beijing
- Tangshan Health Institute for Women and Children, Hebei
- Zhejiang Research Institute of Traditional Chinese Medicine, Hangzhou
- Guiyang College of Traditional Chinese Medicine, Guizhou
- Shanghai Academy of Traditional Chinese Medicine, Shanghai
- The Second Military Medical College, Shanghai
- Shanghai Qigong Institute, Shanghai
- Xing Cheng Air Force Sanitarium
- Zhao Baofeng Beidaihe Qigong Rehabilitation Hospital, Hebei
- Shanghai Institute of Hypertension, Shanghai
- Shenyang Institute of Traditional Chinese Medicine, Shenyang
- Institute for Industrial Health, Xian
- Shandong Medical University, Shandong
- Anti Epidemic Centers of Henan Province, Xin Xiang
- Institute of High Energy Physics, Beijing
- Jiangxi Chinese Medicine and Pharmacy Institute, Jiangxi
- Nanjing Aeronautical Institute, Nanjing
- Institute of Space Medical Engineering, Sichuan
- Chinese Academy of Sciences, Chengdu

While thousands of investigations have been done, just a few have been described here, principally those that are reproducible either with Qigong masters or with Qigong simulation equipment. These studies show that emitted Qi is effective in treating digestive problems, infectious diseases, and bone fractures; that measurable changes in blood chemistry occurs a result of Qigong exercises; and that emitted Qi affects electricity and light in physics experiments.

EFFECTS OF THE EMITTED QI ON HEALING OF EXPERIMENTAL FRACTURE

Jia Lin and Jia Jinding
National Research Institute of Sports Science, Beijing, China.

(This study offers laboratory evidence that Qigong masters can accelerate recovery from fractures. From 1988 FWCAEMQG Proceedings)

The emitted Qi has been found to have a good curative effect on soft tissue injuries such as muscle soreness, scleroma in muscles, acute muscle sprain, muscle contusion and pains. Fracture is also a common injury in sports medicine. We have cured some cases of fracture with the emitted Qi. The purpose of this experiment was to investigate the biological effect of the emitted Qi on healing of fracture.

Sixteen healthy male rabbits, weighing between 1.9 and 2.5 kg, were divided into two groups: the control group and the emitted Qi group. A fracture with a gap of 3 mm was made in the left radius. The rabbits in the emitted Qi group were given the emitted Qi treatment for three minutes per day after fracture. X-ray films were taken every week. Each week specimens for light microscopy from two rabbits were cut into slices of 8*u*m thickness along vertical axis of radius, stained with H.E., and studied by a light microscope. The morphological observations are as follows:

1. Based on some radiographic indexes, such as reaction of fracture section, periosteal reaction and amount of callus formation and callus density, we found that the amount and density of callus formation were better in the emitted Qi group than in the control group. The difference was significant in the 2nd week

(n=16. P<0.01) and 3rd week (n=12. P<0.05).

2. Ultrathin sections were produced with LKB-III ultrotome, stained with uranyl acetate and lead citrate, and studied with a DXB electron microscope (EM). The changes in myofibrils were observed and photographed (x13000). Injured myofibril volume density in the pictures were calculated by means of point-count method.

The ultrastructural examination revealed that overstrain caused pathological changes such as muscle fiber edema, shortening or lengthening of sarcomeres, disorganization, breaking and disappearance of myofibrils as well as Z lines, accompanied by edema and damage of mitochondria. These changes could be seen less frequently in the emitted Qi group than in the control group. The result of quantitative analysis showed that the volume density of myofibrils of the injured muscle in the emitted Qi group was 2.47%, and that in the control group, 20.41 %.

MEASURING QI IN THE BLOOD

A Preliminary Study of the Relationship Between Qigong and Energy Metabolism—The Changes of the Blood ATP Content in Qigong Masters in the Qigong State

by Wang Zhenchang, Huang Jian, and Wu Zijuan
Shanghai Qigong Institute, Shanghai, China

[This revealing study quantifies a physiological change in the blood during Qigong exercise and Qi emission. When Qigong masters do Qigong exercises, blood ATP level increases, indicating a storing of energy. When they emit Qi, blood ATP level drops, indicating a depletion of energy. This is measurable evidence that physiological changes are occurring when a healer says he is collecting energy or emitting energy. It is also evidence that healers may be exhausted after treating patients and need rest and energy building activities to remain in good health themselves. From the 1988 FWCAEMQG Proceedings.]

Recently it has been reported that the emitted Qi by Qigong masters may have material foundation and the internal Qi cultivation can promote health. In this paper, the relationship between Qigong and energy metabolism was studied. The ATP content was measured with 20*ul* of blood drawn from the ring finger of the Qigong masters before and after the Qigong exercise, and, at rest, by the method of bioluminescence assay.

The instrument (FG-30 Type Luminescence Meter) and the chief reagent (luciferase-luciferin) were produced by Shanghai Plant Physiology Institute. The experiments were conducted in three groups:

1. The experimental group: The blood was drawn from each Qigong master's ring finger after he had taken a short rest, and before he exercised Qigong and entered the Qigong state. If he could emit Qi, he would do it for 5-10 minutes. If he exercised internal Qi cultivation, he would do it for half an hour. After the Qigong exercise the blood was drawn again. After rest for half an hour the blood was drawn once more.
2. The control group: The above procedure was repeated on the second day but the Qigong masters did not exercise Qigong.
3. The healthy group: Healthy persons did as the Qigong masters did at the same time. The results are as follows:

In 10 healthy persons the blood ATP contents were constant during the experiment. For nine Qigong masters in the control group the blood ATP contents did not change markedly. The blood ATP contents in 11 Qigong masters after emitting



their Qi decreased markedly (the mean decrease was .000131 M compared with that of the healthy group ($P<0.01$). The blood ATP contents in 16 Qigong masters after cultivating the internal Qi increased markedly (the mean increase was .000054 M) compared with that of the healthy and the control group ($P<0.05$). The duration of Qigong practice influenced the changes of the blood ATP content.

The blood ATP contents in both groups of Qigong masters recovered after rest. Qigong masters were observed continually. First they exercised Qigong, cultivating the internal Qi. Then they emitted their Qi. The blood ATP contents changed as above. Conclusions were discussed. The emitted Qi may have a material foundation because the blood ATP contents decreased after the Qi was emitted. The internal Qi cultivation process promotes anabolism and increases CAMP level so that health may be improved.

EFFECTS OF QIGONG ON NEUROTRANSMITTERS

Liu Binghuai, Jiao Jie and Chen Quanzhu
Anhui College of Traditional Chinese Medicine, Anhui Province, China
Li Yefu, Shang Lili (Affiliated Hospital)

[This study shows that you don't need to be a Qigong master to gain healing benefits from Qigong exercises. New Qigong practitioners with chronic illnesses showed significant normalization of neurotransmitter concentration after Qigong practice. From the 1988 First World Conference for Academic Exchange of Medical Qigong (FWCAEMQG)]

It is well accepted that Qigong contributes to preventing and curing of diseases and prolonging life. To study its mechanisms, the authors observed by means of fluorescence spectrophotometry in 68 subjects the variations in blood content of the following monoamine neurotransmitters before and after the Qigong exercises. (5-hydroxytamine: 5-HT, norepinephrine: NE, and dopamine: DA) Forty-four of the subjects were male, 24 females. Their age ranging from 25 to 68 years old, with an average of 48. They all had practiced the Qigong exercise for one month. All were patients of common chronic diseases such as hypertension, coronary heart disease, gastric ulcer, gastritis, pulmonary emphysema, chronic bronchitis, joint system diseases, neurasthenia and neurosis. Results are as follows:

1. A comparison of monoamine neurotransmitter contents in the blood of the subjects pre- and post-exercise showed a general reduction in 5-HT, averaging from 0.42 to 0.21 *ug*/ml, close to the normal value of 0.15 *ug*/ml. The difference was notable ($P<0.001$) Variations in NE and DA tended to go up. The average NE was from 0.27 to 0.35 *ug* /ml, and DA increased from an average of 0.86 to 1.19 *ug* / ml. The above description showed that the effect of the Qigong exercise is closely related to the monoamine neurotransmitters in the body fluid.
2. Effects of the Qigong exercise on the blood monoamine neurotransmitters of patients of different diseases: The subjects were divided into five groups according to the nature of their disease. Subjects in each group showed reduction in blood 5-HT content after they had practiced the Qigong exercise. In all the groups, the content of vasoconstrictor substance 5-HT dropped to the normal concentration level, resulting in sufficient blood supply for the local tissues and organs. It also improved blood flow, promoted metabolism and strengthened the physiological function of the cells in the tissues thus helping to restore health, adding to the efficacy of Qigong.
3. The Qigong exercise helps regulate the neuro-body fluid inner environment. Through regulating the 5-HT blood concentration in the neurotransmitters of parasympathetic nerve, it causes the extra high blood 5-HT of the cardiovascular patients to drop to the normal level. It also dilates the coronary artery and improves the physiological functions, resulting in the relief of symptoms.
4. The Qigong exercise helps build or strengthen

the physiological function of the digestive system. The exercise exerts an influence on the control of nerves that govern the activities of the internal organs. It is shown by variation in the blood content of neurotransmitters NE, DA and 5-HT, with 5-HT getting lower and DA getting higher, facilitating local blood flow and metabolism in the tissues.

5. Through regulating the concentration of pain producer 5-HT in the peripheral blood, the Qigong exercise achieves an analgesic effect. The drop of 5-HT content is relative to the result of analgesia. This fact shows that the drop of 5-HT is good for invigorating blood circulation and reducing extravasation, which is a proof of the TCM principle: "pain is removed when block is eliminated."

The Qigong exercise results in preventing and curing of diseases. It helps regulate the neuro-body fluid inner environment, promotes activities of organs and maintains dynamic equilibrium of the organism through self stabilization.

PHYSICAL CHARACTERISTICS OF EMITTED QI

Gui Yongfan, Chen Qi, Li Yinfa, and Jiang Shen
Nanjing Aeronautical Institute, Nanjing, China

[Emitted Qi can alter the results of common physics experiments shown in this study from 1988 FWCAEMQG Proceedings.]

In this paper, three functions of the emitted Qi which were discovered with the aid of some physical instruments, such as the Van de Graaff generator and light sensitive plate are discussed.

1. The emitted Qi can restrain the discharge process. The discharge between the two balls in the Van de Graaff generator will be stopped or the period of discharge will become longer when the emitted Qi is exerted on the instrument. The Van de Graaff generator was used for testing. The two discharge balls in the generator were pulled apart until the critical state was reached. Then the Qigong master aimed his emitted Qi at the discharge space. The distance between the fingers or palm of the Qigong master and the discharge space was 10 cm to 3 M. We have discovered the following phenomena:
   a. The emitted Qi stopped the discharge or made the period of discharge longer.
   b. The Qigong master had no sensation of getting an electric shock when he emitted his Qi near the discharge space. Nevertheless, when he stopped emitting his Qi, he had the sensation of an electric shock if his hand was still near the discharge space.
   c. In the restraining process, a series of restraint and discharge, such as restraint—intermittent bursts of discharge—restraint, sometimes appeared.
2. The emitted Qi can cause the exposure of light sensitive plates wrapped in a piece of black paper. By false color image processing with a picture processing instrument, we obtained a color photograph, in which the image of fingers and the Laogong (P-8, center of palm) can be seen clearly. The Qigong master emitted his Qi at the emulsion layer of a light sen-



The concentration of the monoamine neurotransmitter 5-hydroxytamine decreased toward the normal value of 0.15 ug/ml in the above groups of patients after one month of Qigong exercises.

sitive plate from about 10 cm away for about 10 minutes.

RESULTS

a) The color of the controls was darker than that of the affected plates. b) After development, white speckles, various patterns or orderly stripes appeared on the affected plates.

SUPERCONDUCTING MAGNETOMETER MEASURES CHANGES DURING QIGONG

Wu Benjie, Dept. of Biophysics, Beijing Medical University
Wang Xiubi, Institute of Somatic Sciences, Beijing,
Wang Zijun, Nanjing University
Liu Jianben, Institute of Geophysics, Beijing

[Here we see that Qigong masters can produce magnetic fields from their palms, and that these fields have characteristic frequency bands. From 1988 FWCAEMQG Proceedings.]

A dynamic study of Qigong (QG) magnetic signals (MS) by a flux-gate magnetometer was conducted in a magnetically shielded room. Under the QG state, MS was <2Hz in frequency and several *n*T (T = Tesla, the unit of magnetic flux density, $1n\mathrm{T} = 10^{-9}$ T) in amplitude. For deeper understanding of the MS dynamic properties, human weak MS were investigated by a superconducting biomagnetometer which is wider in frequency response (DC to 10 kHz instead of DC to 10 Hz) and higher in sensitivity. Through a frequency-power spectrum analysis by a computer, the MS changes under QG state were analyzed quantitatively.

Twenty persons (38 tests) were selected as subjects, and divided into two groups. (1) The control group consisting of three persons did not practise Qigong, 46.3 years old in average; (2) The Qigong group (practising for 1-20 years) consisted of 17 persons (31 tests), 48.3 years old in average.

The subjects took off all magnetic things; then came into a magnetically shielded room, with the acupoint to be measured aiming at the probe. The distance between the probe and Laogong (P 8) was about 6 cm, and that between the probe and head acupoints was about 4.5 cm. The MS dynamic changes were recorded continuously, before, during, and after QG state (3 minutes each).

MS was measured by a superconducting biomagnetometer, Model M-601. The frequency power spectra were analyzed by a signal processor, Model 7T17-S. In this paper the power changes were all of relative values.

The experimental results indicate that under the QG state three kinds of MS (1Hz, 3 Hz and <2 kHz) are measured from different acupoints Laogong (P 8), Baihui (Du 20), Yintang (Extra); there are three kinds of MS changes in intensity: increasing, decreasing and no change; and there is a good repetition of the change patterns and signal frequency of MS. Two novel phenomena were found, i.e. decrease of power and the change of frequency spectrum in MS during QG.

QIGONG AND CANCER

Cancer is one area where western science can use some help. Our government has pumped billions into cancer research, yet the problem continues to grow. Chemotherapy and radiation have such negative side effects that the time has come to look beyond therapies of killing "bad" cells, toward therapies with which the individual patient brings his own body into order.

In China, the obvious answer is Qigong. Cancer occurs when the cells of the body follow the will of an outside influence, perhaps a bacteria or a virus or a genetic predisposition. If Qi is strong and flowing smoothly within the individual, many Chinese believe that the cells will do the will of the organism, not of an outside influence.

A very interesting experiment that illustrates the will of an individual influencing cell growth is presented in a study by Dr. Feng Lida, MD, Ph.D., a famous Beijing researcher. She had Qigong masters treat vials of E-coli bacteria. The first vial was held but not treated. The Qigong master emitted Qi to the second one to try to "kill" the bacteria. He directed "health-promoting" Qi to the third one. Dr. Feng reported that, with over 40 repetitions, the health promoting dose resulted in a seven- to tenfold increase in the number of E. coli. The health destroying dose lowered the number of bacteria by one half or more. This experiment illustrates the power of the Qigong master in influencing cell growth. Every one of us has the latent ability to do the same, directing Qi to control disease within our own bodies. This can be seen from the success of programs emphasizing visualization and meditation.

If Qi is weak in an area of the body, abnormal growth will appear. Qi is weakened by poor nutrition and lack of exercise. It is also weakened by mental and environmental stress. Chemotherapy and radiation put heavy additional loads on the body, draining it of Qi. This is why methods to strengthen Qi are so valuable.

This chapter is devoted to Qigong as it is applied to cancer. It is clear from these studies that Qigong is an option that every person trying to beat cancer should consider, regardless of whether western techniques are also pursued. Chemotherapy and radiation in many cases have been shown to be of little value improving quality or length of life. They are not the only option. The following evidence shows that Qigong is an important therapeutic modality for treatment of cancer.

THE EFFECT OF THE EMITTED QI ON CARCINOMA CELLS

Feng Lida, Qian Ju Qing, Chen SuQing, et.al.
China Immunology Research Center, Beijing, China

[This influential paper is the first presented in the 1998 FWCAEMQG Proceedings, and shows that emitted Qi can kill cancer cells and alter chromosomes in vitro, providing clinical evidence that cancer patients would do well to learn Qigong.]

We used the techniques of tissue culture, cytogenics and electron microscopy to study the Hale cells and SCG-7901 human gastric adenocarcinoma cells, the change of the cellular ultrastructure and abnormal structure of the chromosomes of the cells. The results showed:

1. The effect of the emitted Qigong on the Hale Cells:

We repeated the experiment 20 times under identical conditions. After the Hale cells received the emitted Qi for 20 minutes, the survival rate of the cells in the experimental group was 69.28% of that in the control group, i.e. 30.72% of the cells in the experimental group were killed. At the same time we observed the Hale cells with a translation electron microscope, and found that degeneration and swelling took place in some of the cells which received the emitted Qi. The endoplasmic reticula were dilated obviously, and the nuclei of the cells were destroyed.

THE EFFECT OF EMITTED QI ON THE GASTRIC ADENOCARCINOMA CELLS:

After the gastric adenocarcinoma cells received the emitted Qi for one hour, the survival rate of the cells was 74.98% of that in the control group. i.e. the average destruction rate of the cells was 25.02%. We repeated the experiment 41 times under identical conditions, and through statistical analysis, found a difference between the two groups ($P<0.01$). In the meantime, a scanning electron microscope was used to study the cells. The results showed that the microvilli of the cells which received the emitted Qi had remarkably dwindled or disappeared and tiny holes could be seen on the surface of the cells.

3. The effect of the emitted Qi on the chromosomes of the gastric adenocarcinoma cells: We repeated the experiment 10 times under identical conditions. 1420 tumor cells in the control group and 1,428 tumor cells which received the emitted Qi for 60 minutes were analyzed. The subdiploid in the control group was 2.11%, the superdiploid was 0.14%, whereas the subdiploid in the experimental group was 3.29% and supertriploid was 0.56%. The statistical significance in these findings ($P<0.05$).

The structure of the chromosomes of the gastric adenocarcinoma cells also varied. In the experimental group, the total abnormality rate was

5.39%. The total abnormality rate in the control group was 1.40%. (P<0.01).

SUMMARY:

Tumor is a common disease which endangers man's life and health. The study on the effects of the emitted Qi on carcinoma cells, especially on the study of the structure and the chromosomes of tumor cells, has not been reported in the world before. The human chromosome is a material base of human heredity and a carrier of the genetic material. The results of our studies showed that the abnormality of the chromosomes of the gastric adenocarcinoma cells was significant after they received emitted Qi. The rate of exchange, breaking, and the dicentromere in the structure of the chromosomes of the gastric adenocarcinoma cells is increased. The results suggested that the emitted Qi could kill the chromosomes of the gastric adenocarcinoma cells. The study may start a new way to cure carcinoma.

QIGONG AS A THERAPEUTIC AID FOR ADVANCED CANCER PATIENTS

by Sun Quizhi and Zhao Li, Kuangan Men Hospital China Academy of Traditional Chinese Medicine, Beijing, China

[This article shows that, in clinical trials, cancer patients were far better off when they combined Qigong exercises and chemotherapy as compared to chemotherapy alone.]

One hundred and twenty three cases of advanced cancer treated simultaneously with drugs and Qigong has been reported in this paper. These were inpatients of our department during the past five years. Among them there were 60 males and 63 females. The youngest was 20 years old. The average age was 47 years old. These patients were diagnosed pathologically as malignant cancer, 70 cases were in the III stage, 53 were in the IV stage, of which, cancer of the stomach accounted for 42.23%, cancer of the large intestine 31.70%, mastocarcinoma 11.29%, and cancer of the esophagus and cardinal carcinoma, 8.1% each.

The 123 patients were divided into two groups. The experimental group included 93 cases treated with drugs and Qigong exercises. The control group, which consisted of 30 cases, was treated by drugs alone. Similar drugs were given to the two groups. Each patient who received the therapy of drugs and Qigong did the Qigong exercises for over two hours a day, three months as a course. Symptoms, signs, body weight, and immunological indices, etc. were recorded before and after treatment. The results were as follows:

1. Amelioration of general symptoms: In the experimental group, 81.7% of the patients regained strength, 63% improved appetite, 33.3% were free from diarrhea or irregular defecation in the experimental group, while in the control group the rates of patients were



Cells of lung cancer before irradiation with emitted Qi



Villus exfoliation of lung cancer cells after irradiation with emitted Qi.

10%, 10% and 6%, respectively. The difference between the two groups is significant. (P<0.01)

2. Body weight: In the experimental group, 50.54% of the patients' body weight increased more than 3 kg, and 5.4% of the patients' body weight decreased more than 3 kg. In the control group, the rates were 13.3% and 30.0%, respectively. The difference between the two groups is, again, quite significant.
3. Phagocytosis of macrophages: In the experimental group, the phagocytic rate of macrophages increased by 12.31 % and the index of macrophages increased from 0.45 before the combined therapy to 0.63 after. In the control group, the phagocytic rate did not elevate, but decreased by 7.87% while the phagocytic index also dropped from 0.63 to 0.50.
4. In addition, it has been observed that, in the experimental group, the erythrocyte sedimentation of 23, and hepatic function of 20 of the 93 patients returned to normal, while in the control group, there were only three patients with normalized erythrocytic sedimentation, and two patients with normalized hepatic function, out of the 30 control cases.

To sum up, these studies suggest that the Qigong therapy is helpful to some extent to ameliorating the symptoms, improving appetite, strengthening constitution, and increasing the ability of self-cure. Qigong can regulate the mind, heart, Qi, and blood so as to get rid of pessimism and eliminate evil factors. Therefore, it is really an effective, simple supplementary treatment with no side effects.

THE EFFECT OF EMITTED QI ON LEUKEMIA IN MICE

Feng Lida and Zhao Xiuzhen
China Immunology Research Center, Beijing, China

[This study by Feng Lida, MD, PhD shows that emitted Qi can decrease the reproduction rate of leukemia cells in mice and that infrasonic Qi simulators can play a similar role. From the 1988 FWCAEMQG proceedings.]

With the rapid development of modern science and technology and the enhancement of people's living standard, the constitutive proportion of diseases has changed and most infectious and parasitic diseases have been brought under control or eliminated, whereas, tumors are becoming a common problem and are endangering man's life and health. In our country, the number of patients suffering from tumor diseases is over 1,000,000 a year, and the number of patients who died from tumors has exceeded 800,000. Therefore, it is important for us to explore a new route to cure tumors.

Leukemia is a malignancy, which has a high incidence and is difficult to cure. As there are some similarities between leukemia in mice and human leukemia, we chose DBA mice as a research model to study the effect of the emitted Qi on L_{1210} cells of leukemia in mice.

The experiment chose DBA mice with a weight of 20±2 gm, and both male and female mice were used. In the experiment we killed the mice, which had been injected with the L_{1210} cells 7 to 9 days before we collected the celiac liquid and adjusted the concentration of cells to 4.70-31.00 million/ml (avg. concentration was 1.20 million/ml). 0.2 ml L_{1210} cells was injected i.p. into the abdominal cavity of mice. And after one day we randomly divided the mice into groups.

One Group Treated With Emitted Qi

Among these groups, the mice of the experimental group received the emitted Qi once per day, for between 10 and 40 minutes for 10 days, while in the control group, no treatment was given. After 10 days the mice were killed and the number of L_{1210} cells were counted with a light microscope. The average value in the control group was 200.435x0.5 million per mouse, while in the experimental group 66.458x0.5 million per mouse and there is significant meaning between the two groups. (P<0.01).

Second Group Treated With Infrasonic Qi Simulator

At the same time, we used an infrasonic qi



123 advanced cancer patients were treated for 6 months. The control group with drugs, the experiemental with drugs and Qigong exercises. The results show the value of Qigong exercises in cancer treatment.



Concentration of leukemia cells in mice after 10 days' treatment with emitted Qi and the infratonic Qi stimulators

simulator to stimulate the mice injected with the L_{1210} cells, once per day, two hours at a time for 10 days, after which the number of L_{1210} cells was observed. The number in the control group was 160.826x0.5 million per mouse, while in the experimental group 70.870x0.5 million per mouse. This difference is of statistical significance ($P<0.1$). The results showed that the number of L_{1210} cells which were injected into mice could be remarkably reduced after the mice received emitted Qi, and the fact suggested that the emitted Qi could kill or inhibit the L_{1210} cells in mice.

Qigong is a part of traditional Chinese medicine, which is a therapy with Chinese characteristics. In recent years, Qigong has been used to cure a lot of diseases, especially difficult diseases and tumor diseases. It is an important issue whether Qigong can kill or inhibit malignant tumor cells or not. The result of this experiment shows that the emitted Qi could kill or inhibit the L_{1210} cells of leukemia in mice. After a body received it many times, the emitted Qi could significantly reduce the number of L_{1210} cells in mice. The experimental study laid a theoretical basis for the treatment of tumors with Qigong. Qigong therapy will be a new way to cure carcinoma. However, the mechanism and way that the emitted Qi kills or inhibits L_{1210} cells of malignant tumor cells in mice needs to be further investigated.

EFFECTS OF QIGONG ON MALIGNANT TUMOR

Luo Sen, Tong Tianmin, et al.
Zhejing Institute of Traditional Chinese Medicine
Hangzhou Qigong Hospital, Hangzhou, China.

[This study, also from the 1988 FWCAEMQG proceedings shows the benefits of combining traditional and modern cancer therapies in maintaining healthy blood cells.]

Under observation in this experiment were 80 patients with 17 kinds of malignant tumors including nasopharyngeal carcinoma, breast cancer, lung cancer, and gastric carcinoma. Their diagnosis was confirmed by cytological and radiological examinations. Within this group, 48 were male and 32 female. Most of them had been operated on before hospitalization. They were at their I or II stage of the disease and had received radiation or chemotherapy before. These patients were randomly divided into three groups. 30 of them, as the first group, received Qigong treatment.

The second group, composed of 25 cases, were treated with routine chemotherapy. And the third group, another 25, received chemotherapy combined with Qigong exercises. The parameters adopted included WBC and RBC count, serum hemoglobin and platelet count in blood before and after treatment, T-lymphocyte conversion test (H3TdRLT) and urine excretion of 17-hydroxy steroids within 24 hours before and after the last week of Qigong therapy in some patients. The total period of observation lasted 60 days. Results are reported as follows:

1. Group I, the Qigong group, developed a significant rise in their WBC, RBC count and serum hemoglobin after treatment ($P<0.01$). Group II, treated with chemotherapy, presented a significant lowering in these measures ($P<0.01$). Group III, which both practiced Qigong and received chemotherapy, showed an obvious elevation of serum hemoglobin, RBC and platelet count ($P<0.005$-0.01). Their WBC remained at the same level as before the treatment ($P>0.05$)
2. T-lymphocyte conversion test in Group I also showed a significant rise ($P<0.05$). It was seen to be maintained at the original level in Group III ($P>0.05$).

This experiment proves that this kind of Qigong exercise, by exciting the circulation of Qi along meridians and modulating the functions of blood circulation, immune response and endocrine tissues, can minimize the toxic side-effects of chemotherapy and enhance energy supply to the body. This practice is effective in treatment of cancer and supported by confirmed scientific experiment.

EFFECTS OF PATIENT TUMORS ON KIRLIAN IMAGES OF HEALTHCARE PROVIDERS

Su Cheng Wu, Guangxi Tumor Hospital, Guangxi, China
Richard H. Lee, China Healthways Institute, USA

The process of emitting Qi during a Qigong treatment, while valuable at jump-starting a patient's recovery, is exhausting and requires extensive Qigong exercises to replenish the depleted Qi. However, as Qigong practitioners become more skilled, they can treat more patients with less depletion, probably through a combination of becoming more proficient at collecting Qi and more efficient at utilizing the Qi that they do have. This is an important field of study because of the prevalence of "burnout" which affects many practitioners in all the medical professions. Perhaps doctors and nurses can be taught the principles of efficient use of their Qi. The following is offered to illustrate this point:

The top two Kirlian photographs on this page show images of fingertips of healthy individuals and healers. The light recorded by the photos is created as electrons moving between the fingers and the film ionize air. In the first photo, the balls are created as electrons leaving the finger create pools of light. And the streamers are created as electrons stream back from the film to the finger. A balance between balls and streamers indicates that electrons move both to and from the fingers. The second photo shows that, around the fingers of healers, the electrons travel more as waves than particles, creating a smooth glow instead of balls and streamers.

In cancer patients, research has shown that balls appear around the cancer (not illustrated, reference Dumitrescu and Kenyon in "Electrographic Imaging in Medicine and Biology", 1983) and streamers appear around all other parts of the body, as shown in the fourth picture. (reference "Bioelectrography" by Konikewicz and Griff 1984 and Dumitrescu, 1983). This strongly suggests that the rapid growth of cancer cells is fueled by high electrical vitality at the cancer site, and that the rest of the body is devitalized as the high energy electrons are somehow attracted by the cancer.

The lower three Kirlian photos were taken in a tumor hospital. A typical cancer patient (the third photograph) shows virtually no Kirlian image. This indicates a very low flow of electrons, either in or out of the finger, and thus, low vitality. After increasing the patient's electrical conductivity using an Infratonic QGM on the foot (K-1), the patient's image brightened, but showed only streamers but no balls, as electrons shot to the fingers but did not return from the fingers to the film. Had high energy electrons returned to the film, we would have seen balls in addition to streamers in the photographs. This suggests that the entire patient, not just the photographed finger, is depleted in electrical vitality, and may be drawing electrical vitality from the Kirlian camera as high voltage electrons stream into the patient's body, but do not return to the film. This supports the common belief that cancer draws vitality from everything in the surrounding area while fueling the very rapid growth of the cancer cells.

Several doctors in the tumor hospital were photographed and those with patient contact showed a similar image dominated by streamers with almost no balls. This suggests that the doctors were in some way devitalized by the patients' low energy condition, and were, themselves, drawing electrical vitality from the camera. It appears that cancer drains the vitality of everyone, the patient, health care providers, family, and even those who visit to show their support.

Why does vitality flow to the cancer site? Qigong practitioners believe that intentionality moves Qi, which suggest that intentionality might be acting. We might suspect the intentionality of the patient, the family or the doctor. All seem to be convinced that the cancer will win. It seems that we should also look at the possibility that the cancer, itself, has intentionality, and is causing the patient to give up hope and the doctor to say things like, "You have no more than 3 to 6 months



Kirlian image of typical healthy person shows balance between balls and streamers.



Kirlian image of typical healer

Cancer patient shows low conductivity.



Cancer patient shows increased streamers after QGM treatment.



Doctor with patient contact also shows streamer dominance.



to live." Perhaps the fight against cancer is a battle of wills over the flow of vitality more than simply the biologically understood multiplication of ignorant cancer cells.

Can we reverse this flow of vitality, and will this reverse the growth of cancer? The preceding research in this chapter shows that Qigong practice and emitted Qi can kill and decrease the growth rate of cancer. Perhaps intentionality is a new weapon against cancer. And maybe the Kirlian camera will be the biofeedback technique which shows patients and researchers when their intentionality is properly applied and when they are winning the battle.

As is concluded in most research studies, "More research is necessary."

CHAOS AND CONSCIOUSNESS

The study of Qi as the relationship between the physical world and consciousness is often avoided by scientists because this violates a basic tenet of science, the experimental method, that the experimenter is not to interfere with the experiment. However, this appears to be exactly what Qigong masters are doing. Whereas religious groups have long held that our thoughts, wishes, desires, and prayers can influence our own lives and the lives of those around us, the scientific world has, for the most part, denied this possibility.

If, in our study of Qigong, we discount the conscious intent of the practitioner, we are ignoring what Qigong practitioners claim is the vital ingredient, intentionality. Thus, we are led to study the physics of the phenomenon, the interaction of electric, magnetic, and acoustical fields. However, if we allow intentionality to enter the equation, a very different view of Qigong emerges with enormous implications.

To accept that consciousness can influence the physical world, science needs some sort of field or substance which can be shaped by consciousness such as the rhythmic movement of electrical charges in the body as measured by EEG, which is shown to be influenced by Qigong masters.

From a broader perspective, this field is chaos, which might be described as uncertainty regarding the future, or instability such that subtle influences can guide the field's reorganization. In the case of EEG, the chaos is the available instability of free electrons, molecular ions, and neurochemicals. There are probably many other forms of chaos within the body including magnetic, acoustical, and electromagnetic. It is chaos, or uncertainty in these fields, which allows consciousness to enter and shape reality.

Qigong therapy is often broken into three phases. First, the practitioner "adds Qi" increasing the available energy, or chaos of the patient. Then he "sweeps the bad Qi out the feet" to remove crystallized structures which are interfering with the patient's health. Finally, he "smooths the Qi" to help bring order out of the chaotic state which results from the adding of chaos and removing of "bad Qi."

Thus, a Qigong treatment might be viewed as adding chaos to liquefy a crystallized structure, removing undesired, loosened crystals, then smoothing and harmonizing the field to "bring a higher order out of the chaos." Softening and bending metal, altering EEG in anesthetized animals, and accelerating recovery from cancer might all be explainable by "consciousness creating and guiding chaos."

LOW DIMENSIONAL CHAOS IN PRACTICING QIGONG

Yagu Lin, Jijun Gao, and Huo Lu
Shanghai Qigong Research

[In our research at CHI, we have found that chaos is a key ingredient in the effectiveness of a therapeutic signal, allowing greater penetration into the body. This Chinese chaos research shows that Qigong exercises result in reduced complexity of the EEG in the brain, providing calmness and mental clarity (bringing order out of chaos). From the FWCAEMQ.]

Recently, researchers such as Kaczmark, I.K. (1977), Nicolis, G. (1985), Skarda, C.A. and Freeman, W.J. (1987), and Xu Jinghua and Xu Nan (1987) have reported the systematic complexity and chaos of the brain electroencephalographic techniques (EEG) by the analysis of dimensionality in studies of chaotic dynamics of biological systems. However, there are few reports analyzing the Qigong functional state using this method.

In this paper, we analyze change in attractor dimensionality d values of the occipital EEG before, during, and after Qigong exercises. The results show that before exercises, d=1.8, during exercises d increases to 2.1, and after Qigong exercise, it remains at the increased value of 2.1. These results show that Qigong exercises can lower the complexity under conscious conditions, increase the orderliness, and decrease the randomness. This may explain Qigong's effect of "warding off distraction, thoughts, or evils," and may be a principal mechanism of Qigong's effectiveness.

QIGONG TRAINING AND COHERENCE OF EEG

Yang Sihuan, Yang Qinfei, Shi Jiming, Cao Yi
Institute of Qigong Science,
Beijing College of Traditional Chinese Medicine,
100029, Beijing, China

[This study shows that Qigong training increases coherence between the right and left sides of the brain. From the perspective of chaos theory, this means that Qigong helps to bring "order out of chaos" in the brains of practitioners. From Second World Conference on Academic Exchange of Medical Qigong.]

In this study, we analysed the coherence of EEG to observe the trainees' EEG regularly. The young students, who were 17 to 20 years old, had been practicing "Zhanzhuang Gong" for one year. We try to find out the effects of the Qigong training period on coherence of EEG. Thirty two persons in the Qigong group and 35 persons in the control group were involved in this experiment. During one year period of observation the subjects of the Qigong group practiced Qigong for 40 minutes every day. The EEGs of the Qigong group were analysed every half year in meditation, and the EEGs were also recorded before learning Qigong. The students in the control group did not take part in the Qigong training and their EEGs were investigated at rest twice with an interval of one year. In the test, eight channels of EEGs were simultaneously processed by a computer on line for 20 minutes. The program, "computer evaluation system for the Qigong state" was provided by the "Laboratory of Bio-Control, Department of Electrical Engineering, Zhejiang University".

After one year of Qigong training, total coherence between the left and right frontal regions increased from 0.84±0.07 to 0.87±0.06 ($p<0.05$). Before Qigong training, the total coherence between the left and right occipital areas was 0.68±0.14. After half year's training, it increased to 0.79±0.10, and after a year's training, it was 0.76±0.10. Self comparison showed the probability $p<0.001$. The total coherence between the left and right temporal areas before Qigong training was 0.48±0.17. Half year after Qigong training it was 0.55±0.13, compared with that before Qigong training ($p<0.05$). One year after Qigong training it was 0.64±0.12. Comparing before and a half year after Qigong training $p<0.001$.

Total coherence did not change significantly in the control group

VIBRATIONAL TREMBLING, CHAOS, AND EEG

Dale M. Patterson, MS, CACB, BCIA Certified
Richard H. Lee, China Healthways Institute, USA

[This article, published in China Healthways Newsletter, provides data collected from biofeedback research conducted by Dale Patterson which shows that chaos increases alpha EEG induction.]

Vibrational trembling appears to be a way memory is stored or processed in the physical body. Chaotic sound penetrates this field of vibrational activity, softening this memory and allowing us to more easily let go of fixated thoughts, addictive desires, and compulsive actions.

When someone is full of anger at being blocked from acquiring the object of desire, he may tremble extensively in the theta range of EEG. And when someone is overloaded with the stress of excess thinking (worry) and approaching a nervous breakdown, he will also tremble, but this time in the beta range. This excess vibrational activity consumes the body's Qi and causes the person to become emotionally, mentally, and physically rigid.

Applying chaotic sound breaks up these repeating patterns, often freeing the patient from frustration and worry. As the patient relaxes, capacity to process thoughts and emotions increases, new answers are found, and the increased freedom and flexibility are experienced as increased vitality. Thus, where physical memory inhibits healing, adding a chaotic alpha signal can accelerate recovery.

LABORATORY TESTING

Dale Patterson, a board certified EEG technician trained in biofeedback became intrigued with the QGM when one of his patients brought one in. He recorded EEG brain maps first with an early model of the QGM which produced a clinically significant 18% increase in Alpha. He then used the Q4 with chaos which provided eight times the increase in alpha activity, showing that chaos increases induction of alpha rhythm in the EEG.



CHAOS AND THE COLLEGE ENTRANCE EXAM

Su Cheng Wu, Guangxi Medical Hospital

[From China Healthways Newsletter: A medical researcher applied the Infratonic QGM to high school students preparing for the college entrance examination.]

There was little chance that Li Wen Chao could ever attend college. As a high school senior, he had achieved only moderate grades in his courses and had done poorly on previous national examinations. Without very high scores in the China College Entrance Examination, Li would almost certainly spend his life in a menial factory or farming job. The College Entrance Examination is terrifying, because everyone who faces it knows that only half of high school graduates will enter the nation's college system. *Failure in this examination is a common cause of suicide in China.*

Enter Su Cheng Wu, a medical researcher and Li's uncle. He had just completed a successful study involving infrasonic treatment of bronchial asthma (see page 28) and was searching for other subjects to study. He felt that stress, nervousness, and mental overload were the principal reasons that high school seniors failed the examination, and believed that the Infratonic QGM would induce the deep calmness and mental clarity of Alpha into the students' minds and bodies, helping them to relax and overcome the mental overload that causes brains to lock up during tests.

For three days before the examination, Dr. Su went to visit his nephew's class and treated each patient by holding the machine on the upper back for five minutes and encouraging the student to talk about fears and tensions regarding the upcoming test. For students suffering from symptoms such as headaches, dizziness, poor appetite, insomnia, and menstrual pain, he instead selected and treated an appropriate point, usually along the front midline of the body.

The results of this small test drew much attention. Li's class was average among the seven senior classes, yet performed the best by far. Whereas the average pass rate for the other six senior classes was 50%, 86% of the students in this class passed the examination and were placed in five year colleges! The other 14% got high enough scores that they were accepted to three year trade schools. Thus, 100% made it to some sort of college. Li Wen Chao enrolled the next year at Guangxi Medical University to become a physician.

While it sounds unreasonable that a little chaotic infrasonic sound can cause such a large increase in scores, the opposing view makes more sense. *Stress and worry can shut down the thinking process.*

SEARCHING FOR JING, QI, AND SHEN IN WESTERN SCIENCE

Traditional Chinese medicine (TCM) holds that three "vital treasures", Jing, Qi, and Shen, are real substances which envelop the human body and are essential to life and healing. These are the fields through which Qigong masters work. Jing provides the genetic structure or the physical strength of the body. Qi is the life or vitality of the body, our energy level. And Shen provides the mind, or conscious aspect. TCM goes further, introducing three seeds of consciousness, the lower, middle and upper Dan Tians located in the lower abdomen, chest, and above the head respectively, which are born and mature through cultivation, providing awareness of the physical world through Jing, Qi, and Shen.

This parallels the writings of Alice Bailey which present a three fold personality: the etheric body (Jing) is shaped by the emotional body (Qi) which, in turn, is shaped by the mental body (Shen). The substance of each body is produced by the physical body whereas the function of each body is to support a mode of consciousness.

In "A New Science of Life" by Rupert Sheldrake a "morphogenetic field" is described as a vibrational field which surrounds and shapes living things as they organize. He argues that our genetic structure doesn't contain, but rather tunes into the blueprint of the physical body through this morphogenetic field. He supports this with laboratory findings that as more and more animals and humans are taught a new behavior, others of similar genetic makeup but physically separated from the first, learn the new behavior more and more quickly. Jing appears to be the TCM equivalent to the morphogenetic field of the physical body. Qi and Shen might also support morphogenetic fields of their own. According to Sheldrake, these morphogenetic fields are programmable, obtaining their initial programming from genetic structure, and being reprogrammed through experience and learning.

Jing, from the standpoint of physics, might be a field of electrons in constant flux suspended in salt water throughout our bodies. The rhythmic movement of this electric field is measurable by EEG, EMG, and EKG. Electrostatic forces are very strong and it is conceivable that such a field can shape a physical body by catalyzing certain chemical reactions and moving certain molecules to the right place at the right time, causing, for example, differentiation between liver cells and brain cells in the embryo.

If Jing is to vibrate freely it requires sufficient energy to have free flowing electrical charges both to resonate with the morphogenetic field and to fuel biochemical reactions. Ilya Prigogine, in "Order Out of Chaos", proposes that life requires chaos, that higher forms of organization emerge out of chaos, and that raising the energy of a system allows it to reconfigure into a higher order of organization. From the standpoint of Jing, when biochemical activity exhausts the available electrochemical potential, chaos in the field of electrons has been exhausted. Then the physical body may become unresponsive, and illness may result. Research during long airline flights shows that, where crowding and recirculated cabin air reduce the availability of electrical energy in the air, people become depleted and develop exhaustion and succeptibility to illness and infection. When passengers wear portable air ionizers, which add electrical instability (chaos) to the air by ionizing it, they do not suffer from exhaustion and avoid illnesses from airborne bacteria. From the standpoint of physics, Jing might be the available electrical instability or chaos in the sea of electrons in the body.

Qi might be a field of magnetic substance which can be measured because it makes the body more electrically conductive. Such diagnostic equipment as Ryodoraku and EAV are claimed to measure the Qi by measuring the electrical conductivity of meridians. High and balanced conductivity are associated with good health and vitality, and low or imbalanced conductivity is associated with illness and debility. While the Qi may have little direct influence on the physical body, its ability to increase local electrical conductivity gives it the ability to provide selective pathways of decreased resistance which allows it to influence the flow of electrons, and thus, shape the Jing. Electrically conductive needles may give acupuncturists a similar ability.

Analysis with Kirlian photography shows that washing the hands with tap water causes the electrical conductivity of the hand to decrease considerably. However, when the hands are washed with the same water which is first passed through a strong magnetic field, the electrical conductivity of the hands increases. (ref: Bioelectric Vitality — The Science of Human Energy by Lee) This tells us, first, that water can store and transport some sort of magnetic substance, and second, that this substance can be removed from or added to the human body. To illustrate this, Kirlian research on long jet flights reveals that reduced magnetic fields on airliners often cause those who have a TCM condition called Yin deficiency to have severe exacerbations of symptoms such as anxiety, nausea, headaches, dizziness, and rising heat. Placing a magnet on the body during the flight provides a source for magnetic substance and reduces the symptoms considerably. Qi might be describable by physics as available magnetic activity within the body, though there appears to be much about magnetism that physics doesn't yet know.

Shen is described in traditional literature as mind or awareness, and often as light. If it is light, why can't we see it? Modern physics tells us that an electron is really an electromagnetic wave, an x-ray, high energy light which has been somehow captured by the nucleus of an atom. Thus, it is conceivable that a field of light or electromagnetic energy could resonate around our physical bodies and remain unmeasurable, just as electrons orbit around a nucleus undetected.

Shen may become visible when excited by electricity. Most people have Kirlian images which show small balls of light surrounding the finger during the negative pulse and streamers, lines of light perpendicular to the finger surface, during the positive pulse. However, healers and artists who use their hands with enhanced awareness, often have a smooth glow around their fingers. (Kirlian photos of the balls and streamers and smooth glow are shown on page 58.) Some even have certain fingers with a smooth glow while others show the balls and streamers. It appears that only those fingers used intelligently have the glow. For instance, a person who principally uses three fingers for massage will find that those three will have the glow while the others have the balls and streamers. The fact that electrons act differently around a healer's fingers is a big opportunity for physicists to investigate the nature of Shen, and to give us a better understanding of the special function abilities of Qigong masters and other healers.

CONCLUSION

Jing, Qi, and Shen are measurable with physical equipment, and thus are subject to scientific study. These measurements correlate with states of health and rates of healing. Thus monitoring the strength of these fields in hospitalized patients and supplementing them when low may prove of value in reducing recovery time and saving lives. In addition to studying, monitoring and supplementing these fields, it might also be productive to study how to increase a patient's resonance with his own morphogenetic field while decreasing his resonance with that of a disease process. This may be a principal area where Qigong masters and other healers excel, while western medicine has little knowledge. Jing, Qi, and Shen, long considered nothing more than useful metaphors by western scientists, may be very real substances which unlock the door for western scientists to understand human vitality.

THE ROLE OF CHAOS IN DISEASE AND HEALING

Richard H. Lee, China Healthways Institute

In the book, "Order Out of Chaos," Ilya Prigogine offers that, when a structured system is energized, its chaos increases, allowing it to reconfigure spontaneously into a higher order of organization. This may explain the evolutionary progression on Earth from the simple structures to the highly organized life forms, from the helpless child to the capable adult who chooses to serve a yet higher organization, humanity.

How can chaos be healing? Chaos is often thought of as unpredictable and destabilizing. It is the enemy of structure and overturns the law of the land. How is it possible that chaos can be harnessed to serve us? As an example: When someone's life is not working, when the basic order upon which they depend is failing them, and when they just want to run away, it may be time to "let go of life" in a way that nurtures the creation of a new order within which the world again makes sense.

Chaos is opportunity. Where there is rigid organization, there is little opportunity for restructuring. The best solutions often go ignored because their implementation would require destruction of some of the structure which holds an organization together. An organization which is flexible, receptive to new ideas, and free to adjust to changing circumstances, is willing to break down old structures for the sake of growth and efficiency. Structure provides for certainty. Chaos injects uncertainty. With a high degree of chaos, an organization can quickly adapt to strange and unfamiliar circumstances without being held back by the inertia of structure.

Within the human body, there is a great deal of structure. Physically we can have unnecessary chronic muscle tension, purposeless lumps, and other structures which don't serve us. Emotionally, we can hold onto desires which repeatedly carry us down pathways of misery. Mentally, we can so fill ourselves with conflicting thoughts that we are unable to sleep and on the edge of nervous breakdown. Whenever a structure within us becomes inflexible, we experience pain. Blocked desire provides emotional pain, and conflicting world views cause mental pain. Flexibility allows us to face the unexpected with capability and enthusiasm. We can run from the path of an approaching car, or stop to pick up a dime. We can eat a bowl of bean sprouts and tofu as comfortably as a hamburger, attend a religious service of any denomination without concern for the clothing of our creator, and be comfortable considering philosophies of strict child rearing alongside newsletters promoting chaos.

Random, unexpected events provide the chaos which exposes our rigidity, our unyielding habits, our crystallized beliefs. Sometimes these crystallized structures within us yield to the pressure but often they resist, sustaining the old ways despite conflicting forces and pain. And sometimes the strain even becomes so great that a person's entire world view shatters. This can be a hugely transformative event:

The initial stress is experienced as pain, uncertainty, or fear of the unknown. We become desperate to avoid further stressing of the crystallized structure so we hang on even tighter. Then the order governing our emotions and thoughts snaps, pops, or shatters. We burst into tears and watch as our life falls to shambles before our eyes, with seemingly nothing left for us to hang onto. We may feel an abrupt shift. Perhaps we experience an immediate release or an exhilarating feeling of freedom and relaxation. At other times, we find ourselves drowning in the unknown, trying to hang onto the structure which just crumbled, unwilling to relax and trust that a new better structure will form in its place. Sometimes we spend years trying to hang onto a crumbled, useless, and painful structure.

Chaos is an opportunity to restructure our beliefs, habits, and physical bodies into a more flexible arrangement, more suitable to the unknown but anticipated future. Whenever we face a new situation, we have this opportunity. Every time we make a new choice or break an old habit, we increase our flexibility and expand our opportunities.

How do we nurture chaos? We start by looking for patterns which restrict our choices, consume our resources, and limit our beliefs. Watching TV, smoking, recounting past experiences or gossip, consuming countless grams of animal fats and alcohol, spending endless hours or repetition in a job or relationship. Changing these patterns may be quite painful because of deep and extensive crystallization, but the result will almost certainly be free time, vitality, new experiences, and an opportunity to make less restricted new choices. While choices made in anger are easiest, and often create more chaos, choices made with love usually provide a greater opportunity for growth. If shattering and reorganization occur within the emotion of anger, the new order will embody anger. If we immediately forgive and "love our enemy", the new order within us will embody love and harmony.

THERAPEUTIC CHAOS

Richard H. Lee, China Healthways Institute

[This article describes how chaotic infrasonic sound might work to penetrate the body, break up stagnation and accelerate healing.]

Over the past ten years CHI has been studying the Infratonic QGM, trying to determine why it is effective at accelerating recovery and decreasing pain. Until recently, our focus has been on the broad spectrum frequency band of infrasonic sound produced by the QGM which infuses the local area, facilitating nerves and inducing Alpha brainwave activity, facilitating nerve transmission between the brain and the local site of pain. This is a plausible mechanism, but there appears to be more to it.

As we experimented chaos surfaced as an "active ingredient." We built prototypes with advanced microprocessor technology which produced an almost purely chaotic signal. In testing we found that these new units penetrated more deeply and stimulated resistant areas of the body which other therapies could not penetrate.

It appears that our thoughts and emotions are strongly affected by sound, and that the body defends itself against outside vibrational signals by anticipating and setting up signals which cancel them out. This may be why someone speaks loudly when he wants to persuade us of an idea, and why we may shout back to defend our own position, and why it is difficult to read or think clearly while sitting in a noisy park in a big city, or in a windstorm, or with loud music playing. It seems that it is difficult to sustain one's own complex thoughts when noise is jumbling them.

Many of the emotions and thoughts we hold within us can be the cause of chronic illness, pain, and slow healing. We might even be carrying some of these patterns from childhood, or pick them up from chance encounters or spooky movies. Like a computer virus, they are lurking among thoughts and beliefs which make up our personality. Those emotions and thoughts which are causing health problems are part of what Qigong therapists call "bad Qi."

Our ability to filter out recognizable sounds, while allowing us to maintain our own thoughts and emotions, is a major barrier to the effectiveness of therapy devices like TENS, ultrasound, and massagers. If we receive a therapeutic treatment from such a device, it may provide some relief but will only affect those surface vibrational patterns which are ready to let go. Thus many therapy devices relax muscles to some degree. But as soon as the therapy begins to intrude on dominant beliefs or emotions we automatically identify the invading signal and filter it out. Thus, predictable therapeutic signals can only do so much.

While we can defend against rhythmic signals, our old attitudes and emotions are defenseless against the random sound of a chaos therapy device because it is unpredictable. It simply goes past our vibrational defenses and softens all thoughts and emotions in the target frequency range. This may be why, after a treatment, people feel calm, clear thinking, and liberated from the problems and worries of life. A big part of what they are feeling may be the abundance of energy which is released when old unnecessary thought and emotion patterns dissolve, releasing the Qi, the substance that was vibrating to maintain them.

It is not just "bad Qi" that is softened by chaotic infrasonic sound. All structures, thoughts and emotions, may be softened as acoustical chaos increases in the body. Since accelerated healing of broken bones and sprained tendons is often reported, chaotic sound may soften these solid physical structures as well. This parallels the first step in Qigong therapy, emitting Qi to soften and liquefy the stagnant Qi.

The second step is to sweep "bad Qi" downward and out the feet. This may be a process of removing old vibrational structures which have been freed to move but have not entirely dissolved. Therapists have found that using chaotic infrasonic sound to sweep from the area of pain down the body and out the feet after treating the pain is often more effective than treating the point of pain alone.

The third step in Qigong therapy is to create a nurturing Qi field to allow the remaining Qi to harmonize, nurturing the emergence of a new order out of the chaos. The Infratonic QGM helps to do this by infusing the body with alpha EEG activity. Whereas the theta rhythm is associated with our individual identity and our relationship with the physical world (and our sense of ego and self importance), and the beta rhythm is associated with planning and thinking (stress and worry), alpha is all about relationships, putting the group before the individual. This may be why, after a QGM treatment, patients become more "compliant" in a doctor's office and people find that interpersonal conflicts are easier to resolve. This process may also occur on the cellular level toward healing and disease resolution as "bad Qi" is removed and the body's cells and organs can reorganize along the lines of teamwork and harmony.

Qigong therapy can be understood in terms of chaos theory. As we let go of old structure, we have an increase of chaotic or undefined energy, which then can transform into a higher order of organization which handles all previous requirements in a new way and has left over capacity for new endeavors.

IMPLICATIONS OF SCIENTIFIC QIGONG RESEARCH

The findings of the scientific research into human vitality have implications in broad areas of science and medicine.

1. Emitted Qi has strong measurable effects in health, healing, physiology and mental functioning. The presented research will encourage scientists around the world to seek deeper understanding of this phenomenon.
2. As human vitality becomes better understood, both in terms of measurable fields which surround the body, and chaos and consciousness, it will be integrated into the American health care system. Monitoring and treating patients accordingly will significantly improve recovery rates and shorten hospital stays.
3. Qigong exercises are effective tools for the individual to cultivate rapid healing and vitality. In addition, many who overcome chronic illness through Qigong practice will develop the ability to help treat others through the emitted Qi.
4. For those who are caught in the frenzied thinking of busy city life, practice of Qigong and other forms of concentration and meditation exercises is an answer. Qigong simulators help to get people started in their relax-

ation and Qigong exercises by relieving pain, promoting deep relaxation and mental clarity, and providing evidence that the phenomenon is real.

5. As the principles of human vitality are accepted in families, children will learn that their feelings of energy flowing through their bodies are normal, and that their awareness of these feelings is valuable. Just as children quickly learn the language that their parents speak, these children will learn to understand and use Qi if their parents accept and discuss it.

The Chinese scientific investigations into Qigong establish the phenomenon of emitted Qi as a real and fertile area of scientific study. Qigong teaching centers and Qigong simulation devices are already making a difference. Further studies into the nature of human vitality and inventions coming out of this ongoing research will do much to shape the 21st century.

APPENDIX 3

INTRODUCTION

This third Appendix includes research information on the physiological and energetic mechanisms triggered within the body, when stimulated through Medical Qigong therapy, Taijiquan or Yoga. This information was collected by my good friend Roger Jahnke, OMD, Director of the Qigong Department at the Santa Barbara College of Oriental Medicine, Santa Barbara, California. Mr. Jahnke is a doctor of Acupuncture and Oriental Medicine, and has studied extensively in China and abroad, learning Traditional Chinese Medicine and refining his clinical ability since 1967.

Doctor Jahnke is also the Director of the Health Action Clinic in Santa Barbara, California, and was one of the founding Board members of the National Qigong Association. He has written a Medical Qigong book entitled, "The Healer Within: Using Traditional Chinese Techniques to Release Your Body's Own Medicine."

This third Appendix is a continuation of the research devoted to the scientific approach of analyzing and scrutinizing the claims made as to the actual effectiveness of Medical Qigong Therapy as a clinical modality. The result on the effectiveness of Medical Qigong Therapy as a solid and effective clinical modality being positive in conclusion.

The following information in this third appendix represents but a fraction of Dr. Jahnke's findings, however, I am confident that the reader will find the data fascinating.

Dr. Jerry Alan Johnson May 2000

THE PSYCHOLOGICAL AND ENERGETIC MECHANISMS TRIGGERED IN THE HUMAN SYSTEM BY THE SELF-APPLIED HEALTH ENHANCEMENT METHODS QIGONG, TAIJI, AND YOGA

Roger Jahnke, OMD
Director of the Qigong Department
Santa Barbara College of Oriental Medicine

Western science has very clearly delineated numerous physiological systems: the digestive system, the nervous system, the cardiac system, etc. However, what might be called the "healing system" has not been discussed or clearly defined until recently. Medicine has uncovered many of the pathological processes that occur within the recognized systems and defined clinical strategies for their resolution. Strategies for enhancing the "healing system," however, have not been addressed by conventional science or medicine.

Numerous cultures, typically considered to be scientifically unsophisticated, actually noted and described the "healing system" long ago. The Chinese in traditional Chinese medicine, and the Asian Indians in Ayurvedic medicine, simultaneously developed elaborate theories of the function of the "healing system," and over thousands of years refined strategies for enhancing its function to produce a remarkable endogenous resource for self-repair. This internally generated healing resource is called an "inner elixir," literally a medicine produced within the human system.

In addition to specific clinical methods such as acupuncture, herbal therapies and tissue manipulation (massage and articular adjustment), these ancient cultures also created comprehensive health enhancement and self-healing systems to assist people in improving their own capacity to heal. Collectively such methods have been called the self-applied health enhancement methods (SAHEM). 1 Typically SAHEM includes breath practice, relaxation and regulation of the mind and nervous system through meditation, purposeful adjustment of the body posture with gentle movements and self-applied massage.

Qigong (also Chi Kung) from China and Yoga from India are ancient methodologies developed and refined over thousands of years specifically for sustaining and enhancing the "healing system." Qigong and Yoga, while they are historically based on the cultivation of factors unknown to the West (China—Qi and India—Prana), actually have specific effects on well known physiological mechanisms that are fully understood by Western science.

While there are many subtle aspects of human physiology that are triggered or accelerated by the practice of the SAHEM (including an emerging new understanding of "energetics," "bio-energetics" or "the electro-physiological system) the following three areas of conventional physiology make up a major portion of the physiological function of the "healing system" and are enhanced by the practice of the SAHEM.

1. Oxygen Delivery
2. Lymph Generation and Propulsion
3. Brain and Neurological Activity

The following sections will address each of these aspects. Other important mechanisms effected by the SAHEM including co-enzymes, antioxidants, connective tissue, precursor hierarchies, stem cell morphology , etc. do not fall into the scope of this paper and their discussion must be held for the future. The domain of subtle energy based mechanisms for the SAHEM effect will be explored briefly in conclusion.

OXYGEN

The Chinese knew about the circulation of the blood approximately 2000 years before William

Harvey described it in 1616 (Temple and Needham, 1986; Veith, 1972)). They knew about the energy generating relationship of food and air 2300 years before the elaboration of the oxidation feature of the Krebs cycle. The simplicity of the ancient Chinese formula for metabolic activity, understandable even by children, encourages wise use breath and food as health enhancing factors This is how Chinese grandmothers have passed health wisdom to children. Note that such simple wisdom is uncommon in the grandmothers of scientific cultures today.

It is often asked what difference there is between Qigong, Yoga (or other mild SAHEM) and the more vigorous conventional fitness methods like running, lifting weights, power biking and aerobic exercise. One way to discuss this is to trace the oxidation and energy cycle. In both aggressive, vigorous exercise and mild exercise the body naturally produces a powerful mix of metabolic resources. In vigorous exercise this is typically called a fuel. In the mild fitness systems of ancient cultures this inner resource has historically been called a medicine, or an elixir.

In vigorous exercise this oxygen induced resource is spent as fuel for hungry muscles. In the milder forms of SAHEM this resource is not completely spent, instead it is circulated internally and utilized as an internal reserve of self-repair factors to sustain and heal the tissues, organs and glands. At the advanced levels of Qigong this endogenous medicine is believed to be transformed into an elixir of longevity and wisdom.

Increased oxygen availability from practice of SAHEM has three potential effects, it:

1. supports energy (ATP, AMP, ADP) generation.
2. generates water as a by product of energy metabolism.
3. enhances immune function.

ENERGY GENERATION

The energy necessary for cellular processes and body heat regulation is supplied through the reaction of oxygen and glucose, in the presence of adenosine triphosphate (ATP). The combination of oxygen from air and sugar from food is catalyzed by ATP releasing chemical energy (ergs) which accomplishes all cellular processes. ATP is the basic energy storage and energy transfer molecule in the body.

The oxygen carrying capacity of the blood and the energy catalyzing ability of ATP are critical factors in the ability of the human organism to sustain a high level of vitality. This suggests that oxygen and ATP may be related to what the Chinese call "Qi" and what the Asian Indians call "Prana," the vital force or life energy. Chinese medicine distinguishes several aspects of Qi. Zhen Qi (Genuine, True or Normal Energy) is the basic dynamic force of all vital function. Ying Qi (Nutrient Energy) is the dynamic force which fuels cellular work (Kaptchuk, 1983). The interaction of oxygen, nutrients and ATP is apparently a physiological process that is a direct correlate of one particular aspect (there are many) of the activity of the Qi.

In Chinese research it was observed that blood levels of ATP increase with practices which cultivate Qi (Wang, 1988). When the mysterious practice of Qi emission (projecting Qi) was performed, the practitioner's ATP levels decreased significantly. Emission of Qi results in a decrease in stored ATP (or potential energy) as recognized by Western physiological science.

The SAHEM activate the body's energy metabolism cycle. The Chinese call this the "cycle of the transformation of energy" (Jahnke, 1989). In the West it is called the Krebs cycle, and has been nicknamed the "bioenergetic cycle."

In the West, ancient medicine is generally characterized as unscientific, superstitious or even primitive. Therefore, the Chinese "formula" for the transformation of energy (Qi) seems overly simplified:

Gu Qi + Kong (Qing) Qi = Zhen Qi

or energy of food + energy of air = essential body energy

Gu Qi (grain Qi, or food Qi) is the essence or life force of food. It mixes with Kong Qi (Kaptchuck, 1983) or Qing Qi (Kendall, 1989) (natural air Qi), the essence or life force of air to form Zhen Qi (Genuine, True or Normal Qi)) which is the life force of the body (Veith, 1972;

Kaptchuck, 1983; Kendall, 1989).

However, it is this same basic formula, hidden in the complex vocabulary of Western science, that is used in modern physiology:

$6O_2 + C_6H_{12}O_6 = ATP = ergs + 6CO_2 + 6H_2O$

air + glucose = catalyst = energy + carbon dioxide + water

It seems that the Chinese knew, without a particularly refined scientific method, that only a portion of the air and food, the Qi or essence, was employed in the process. In fact only 21% of air is oxygen and glucose is approximately 60% of food. (Guyton, 1992)

Science has been exploring energies, beyond metabolic energy (ergs), within the human system including the migration of ions, the ionic gates in cell membranes, the ionic discharge along neurological pathways and the electrical discharge that causes the beating of the heart. The overall understanding of body energetics will increase significantly as science explores the extent to which Qi is linked to these known physio-energetic mechanisms. The interaction of oxygen, glucose and ATP is likely only one energetic aspect of the beneficial effects of Qigong and other SAHEM.

WATER PRODUCTION

A second critical benefit of increased oxygen metabolism is linked to the cellular production of water as a by-product of the energy production cycle noted above. (Shields, 1989) This water is incorporated in interstitial fluid, lymph, blood serum, cerebrospinal fluid, synovial fluid, tears, sweat, etc.

Coincidentally, the energy which fuels the work of the cells as well as much of the water which contributes to the lymphatic fluid and other body fluids have the same source: metabolism. Metabolism is gently increased by all of the SAHEM. In addition, while the metabolic production of ergs also produces water, it is also interstitial water that has been found to conduct the physiologic flow of ions internally.

The benefits of the practice of health enhancement and self-healing methods upon the water component of the endogenous self-repair resource will be further explored in the section below on the lymphatic system. The bionic conductance will be explored briefly under energetic mechanisms.

IMMUNE FUNCTION

ATP drives the activity of every cell. Immune function as well as the production of immune resources (white blood cells, lymphocytes, T-cells, killer cells, etc.) are dependent on oxygen availability. It has been shown that exercise can mobilize the effect of natural killer (NK) cells. (Pedersen, 1988) However, in individuals who exercise so vigorously that they exceed the aerobic level and cross the anaerobic threshold, immune function is actually decreased (Brahmi, 1985; Fehr, 1989).

The scientific evidence is strong on two points: 1) oxygen deficiency leads to decreased immune function and 2) moderate amounts of mild exercise increase immune function.

In his research, Nobel Prize recipient Otto Warburg found that oxygen deficiency was typically supportive of cancer cell proliferation (Warburg, 1966). There are numerous studies that associate reduced lung volume and oxygen exchange capacity with increased mortality and reduced resistance to disease (Gordon, 1970; Cullen, 1983). In studies with elders, immunodeficiency was found to be one consequence of reduced oxygen metabolism. (Saltzman, 1987).

Oxygen's effect on immune function was demonstrated in a German study. It was found that in elderly injured, stressed and hospitalized individuals the arterial oxygen content is often reduced from normal levels. Administration of oxygen was found to elevate the arterial oxygen content and increase recovery rates. Interestingly, the experimental addition of germanium to the treatment protocol in the study further accelerated the healing process (Liem, 1985). Germanium is known to accelerate oxygen metabolism.

These mechanisms associated with oxygen's role in the endogenous "healing system," are naturally occurring and optimal in healthy individuals. One or several of these mechanisms may be deficient in individuals who are ill or at risk for disease. These mechanisms are all enhanced by the gentle movement, focused breath practice and relaxation that occur in the practice of Qigong, Yoga and other SAHEM.

LYMPH SYSTEM FUNCTION

The lymphatic system has been largely neglected in the conventional Western scientific tradition. Contrasted with cardiac function, for example, the lymph function is relatively unexplored. Perhaps, because lymph and lymph vessels are generally translucent, they drew little attention in early anatomical study compared to organs, blood vessels, muscles and bones.

Hippocrates and Aristotle referred to "white blood" and "colorless fluid." In the Middle Ages medical knowledge declined and the lymph was temporarily forgotten. Not until 1627 did Asellius, in Milan, recover the knowledge of the lymph (Rusznyak, 1976). The structure and action of the lymph system was still undefined by 1900 (Yoffey, 1970) and both the immunological function of the lymph and the actual lymphogenic process are still not clearly understood even as we enter the 21st century.

However, in Asia, medical practice is based on meticulous observation of whole organisms—the whole person and the totality of integrated functions. Even though the discrete lymphatic function itself was unknown and unnamed, its effects were generally ascribed to the proper action of the Qi and fluids in China or the Prana and fluids in India. Even though the lymph, as such, was unnamed by Asian physicians, elaborate methods for generating and circulating lymph were developed, and faithfully practiced through Qigong, Yoga and other self-care practices.

When these practices are viewed in relation to what is now known about lymphatic function and its healing role, it appears that much of Qigong, Tai Chi, Yoga and Pranayama were developed specifically with the enhancement of lymphatic function in mind. Breath, movement and postural modification as well as meditation have specific effects on the circulation of the lymph and therefore enhance the overall function of the lymphatic system.

In the West science has divided the body fluids into specific categories: blood, lymph, cerebrospinal fluid, synovial fluid, extracellular fluid, intracellular fluid. From the paradigm of the West it seems that the unsophisticated Chinese may have overlooked important information with their broad, non-specific view of "Qi, blood and body fluids." However, the lymph fluid is largely interstitial biological water. This becomes an aspect of blood plasma (Rusznyak, 1976). Plasma and lymph both contribute water to the cerebrospinal fluid, part of which migrates back into the lymphatic system (Bradbury, 1985). This cycling of fluid (essentially water) from one system into another validates the Chinese approach of thinking of the all various fluids in a single continuum: simply as "body fluids."

Recent discoveries have demonstrated that electrical energy in the form of ion streams migrate throughout the body (Nordenstrom, 1983). The conductance medium for this energy flow system (which will be discussed in the energetic section of this article) is biological water in its numerous contexts including lymph, blood serum, interstitial fluid, etc.

The practice of SAHEM activates a number of remarkable self-healing mechanisms associated with the lymphatic system:

1. Lymph generation
2. Lymph propulsion
3. Immune function
4. Cerebrospinal fluid circulation
5. Nutritive function

LYMPH GENERATION

The actual generation of the lymph has long been attributed to the filtration of blood plasma from the capillaries (Adair and Guyton, 1985). As recently as 1985 this was recognized as the primary source of the lymph. This idea overlooks a significant detail that is at the crux of the tremendous health benefits of Qigong and Yoga: a significant portion of the water in the body's fluids is produced by the identical physiological process that generates the body's biological energy as discussed in the previous section on oxygen (Shields, 1989). Just as an individual respires to sustain life, each cell is also respiring. For each gram of glucose metabolized, in excess of a gram of water is produced.

In a moderately active 70 Kg human, between 2100cc and 2800cc of lymph enters the blood stream daily at the sub-clavian vein through the thoracic duct. In a resting individual the calculations of the Krebs cycle show that the cells produce approximately 950cc (Shields, 1989) of this daily water flow. In a person engaging in moderate exercises, such as Qigong or Yoga (or walking), up to 1400cc of aerobically generated water can be produced daily. When an individual is practicing some sort of moderate body activity, as much as one half of the water that is produced and propelled through the lymph system is a by-product of cellular metabolism. Increased lymph flow improves the elimination of the by-products of metabolism and pathogenic factors (both considered toxins) and increases the circulation of immune factors.

LYMPH PROPULSION

The blood's circulatory system has the powerful heart muscle to propel its fluid. The lymph, however has no distinct heart in humans. It was understood that the movement of lymph against gravity is accomplished by the contractions of the skeletal musculature through vessels with one way valves in a uni-directional system. Nothing new emerged until the mid 1900's when studies revealed that birds and reptiles have specific lymph hearts (Shields, 1980). Even as late as 1941 important aspects of lymph propulsion mechanism remained obscure (Drinker and Yoffey, 1941).

By 1949 "spontaneous, intrinsic pulsatory contraction of the peripheral lymphatic vessels" was demonstrated in humans with a rhythm unassociated with either the heart or the breath (Smith, 1949; Olszewski, 1979).

The current literature is crowded with a wide range of questions raised by research specifically on lymph propulsion: What factors might stimulate the intrinsic contractile mechanism? Is it consistent throughout or differentiated, by what regional factors? By what autonomic and neuro-endocrine factors is intrinsic contractility modified? These are just a few of the questions. The study of SAHEM will accelerate our ability to answer these and other more general questions on the lymph system such as: What regulates lymph protein concentration? What effect does passage through the lymph nodes have on the proliferation of immune cells from within the nodes (Olszewski, 1985)? And what is the nutritive role of the lymph (Shields, 1972)?

The breath, through two mechanisms, has a significant effect on the propulsion of the lymph: 1). aerobic production of water and 2). mechanical pumping of the breath apparatus, lungs and diaphragm. Several additional propulsive mechanisms are initiated by body movement and body posture.

Tentative agreement now exists on at least five mechanisms which comprise the "lymph heart" and are activated by the SAHEM, including:

1. aerobic production
2. intrinsic smooth muscle contraction
3. contraction of striated skeletal muscles
4. gravity
5. breath apparatus: lungs, rib cage and diaphragm

Aerobic Propulsion. The aerobic production of water contributes to lymph propulsion mechanically. The cellular production of water, as a by-product of oxygen metabolism, is increased by dynamic Qigong and Yoga practice. The liquid holding capacity of the tissue spaces is naturally limited. As the limit is reached, the presence of additional lymph drives the excess into the terminal lymphatic vessels, the initial vascular openings of the lymphatic system (Yoffey, 1970: Adair, 1985; Shields, 1980, Olszewski, 1985). Like a cup that is running over, the interstitial space fills, building volume and pressure, and then flows over into the lymph vessels.

Intrinsic Smooth Muscle Contraction. The automatic response of the smooth muscle tissue of the lymphatic vessels and the peripheral lymphatic capillaries is to contract when filled and stretched to a certain tolerance (Olszewski, 1985). This contraction moves the lymph forward, with the assistance of the one way valves, in much the same way as the contraction of the heart moves the blood (Bradbury, 1985). In Qigong and Yoga this mechanism is accelerated by the increase in metabolism from gentle movement which contributes to lymph volume.

A number of studies have demonstrated that the intrinsic mechanism is also triggered when the overall sympathetic aspect of the autonomic nervous system is modified by the parasympathetic. Therefore, he intrinsic contractility mechanism is accelerated or enhanced by the shifting into the deeply relaxed state that is a primary feature of SAHEM practice.

Striated Skeletal Muscle Contraction. Even slight contraction of skeletal muscles in mild health enhancement practices propels the lymph in the one way vessels. In the more dynamic practices the pumping of the skeletal muscles and compression of the body parts increases interstitial. The effect of muscle contraction on lymph is one of the classic explanations for lymph motion (Adair, 1985, Bradbury, 1985). In Qigong and Yoga this mechanism is triggered by the mechanical action of the musculature and the action of the skeleton through the relaxation and contraction of the striated muscles in the movement forms of the practice.

Gravitational Propulsion. Because gravity exerts such a substantial force and because lymph has so far to climb to get to the thoracic duct's entry into the sub-clavian vein (at the base of the neck), any inversion of the limbs or even the prone body position allows for a more free flow of lymph. In keeping with this, elevation of the limbs is often prescribed for health problems characterized by a pooling of interstitial fluids, edema.

In SAHEM, many postures and movements create this mechanical dynamic where the lymph is actually propelled by gravity. In certain walking forms, Tai Chi and Guo Lin Qigong are the most renowned, the practitioner is constantly but slowly moving all of the limbs in beautiful circular motions that recurrently activate this mechanism. In Yoga many of the asanas (postures) invert the limbs. In the head and shoulder stands the whole body is inverted.

Breath Apparatus: Mechanical Propulsion. The most powerful of the array of mechanisms that work together to form the "lymph heart" is the mechanical action of the breathing apparatus itself (Sheilds, 1980). The concentration of lymphoid tissue above and below the diaphragm is many times more dense, and contains greater fluid volume, than any of the lymphoid tissue at the periphery, or even in the moderately prolific lymphoid areas of the axilla or groin (Adair, 1985). Lymph that has been carried from all over the body, accumulates centrally and is then propelled by the breath / diaphragm in a final rush through the thoracic lymph duct into the blood at the subclavian vein where it leaves behind its identity as lymph and is transformed into blood serum (Shields, 1981).

Above the diaphragm the thoracic duct of the lymphatic system is a central collecting vessel. Its size is many times that of the peripheral lymph vessels. Below the diaphragm a substantial dilation of the thoracic duct forms a collecting capsule for lymph, called the cisterna chyli. Chyle is a milky fluid of nutrients absorbed from the small intestine, which is passed into the circulating blood through the thoracic duct.

When full inspiration of the breath occurs, the diaphragm drops downward. A tremendous pressure is exerted on the cisterna chyli and a great negative pressure is generated in the thoracic cavity. The compressed cisterna chyli shoots lymph upward through the thoracic cavity. As air rushes in to balance the negative thoracic pressure, the lungs are fully expanded. This creates a powerful positive pressure which compresses the thoracic duct. Due to the one way lymphatic valvular system, lymph is forced upward where it enters into the sub-clavian vein with a rush.

Simultaneously, when the diaphragm drops downward on full inspiration it also compresses the abdominal and pelvic organs. The contents of the lymphoid reservoirs and vessels are forced by the same arrangement of one way valves forward in the system. In research with moving X-ray film, study subjects explored various actions and breath patterns. It was demonstrated that deep inspiration pumps the lymph at a rate that is dramatically greater than resting inspiration and other activities, including massage and walking (Shields, 1981).

It is fascinating to note that in Traditional Chinese Medical theory it has been taught for several millennia that the "lungs regulate the water passages" (Xie Zhu Fan, 1988). To Westerners this seems quite strange. The kidneys are considered to be responsible for water regulation. How could the Chinese have known that the activity of the lungs and diaphragm were linked to moving the body's internal water supply? Even now as we enter the 21st century Western science, and especially average Western citizens, have little idea that the simple act of regulating the breath is such a profound healing tool. However, here we can see that the Chinese somehow arrived at a kind of remarkable wisdom about how the lungs, the breath and the oxygen literally cooperate to produce and circulate the healing resource of water in the body.

IMMUNE FUNCTION

The immunoactive aspect of the lymphatic system is well represented in the conventional literature of Western physiology (Drinker, 1941; Bradbury, 1985; Olszewski, 1985; Van Rooiijen, 1987). The bone marrow, thymus, spleen and lymph nodes participate in the interaction of the lymph and immunity. The composition of the lymph fluid itself includes a number of immune active agents such as lymphocytes and macrophages (Olszewski, 1985).

Lymphocytes that exit with the lymph fluid from the nodes come from three sources: 1) inflowing with lymph from the tissues in the peripheral vessels, 2) exchanged from the blood that enters the node's own vascular system and 3) formed by local proliferation in the node itself (Bradbury, 1985). Lymphocytes naturally collect within the node, especially when lymph flow is sluggish. Greater numbers of cells proliferate when lymph flow is greater and the numbers circulated out of the node increase with flow volume as well (Adair, 1985). Both the numbers immunoactive cells and their circulation rate are increased by the deepening of the breath, relaxation and the alternating contraction and releasing of the musculature in the gentle practices of Qigong and Yoga.

Excellent recent research has clearly delineated, localized and quantified the development of specific antibody forming cells in lymph nodes (Van Rooijen, 1987). In addition, it has been found that there are neurotransmitter receptor sites on lymphocytes where they actually interface with the neuropeptides that drive immune function (Smith, 1985). This is one of the important links between neurochemistry and immunity that is mediated through the lymph system and optimized by the practice of the SAHEM which also increases the numbers of circulating immune cells and accelerates their rate of delivery.

CEREBROSPINAL FLUID (CSF)

The cerebrospinal fluid (CSF) system was classically perceived as a closed system, though another view, unconventional for many years, held that CSF was actually circulating in an open system that allowed the fluid to flow through the aracnoid villi and into the venous blood. By the 1970's it was generally acknowledged that the CSF travels along the cranial and spinal nerves and into the perineural lymphatics (Kimber, 1977).

Research using the microinjection of tracers has suggested several possible pathways for the passage of both the CSF and the cerebral interstitial fluid (CIF) to exit the aracnoid space (Bradbury, 1985). By 1985 the flow of CSF and CIF into the lymphatics was well documented (Bradbury, 1985). Consideration has even been given to the effects of pressure and posture on this flow (Bradbury, 1985), both of which are primary effects that are enhanced in the practice of Qigong, Taiji and Yoga.

The presence of CSF in the lymphatic system and the presence of neurotransmitter receptors on immune cells (Covelli, 1988) suggests a powerful benefit of the SAHEM on the interaction between neurotransmitters and immune function in the reticulo-endothelial system.

NUTRITIVE (TROPHIC) FUNCTION

The importance of a broad availability of nutritional factors to the tissues is fully accepted. However, the role of the lymphatic system in this activity was barely understood before 1972. (Shields, 1972) The original findings of Assellius in dogs revealed the route of absorption of nutrients from the small intestine via the lacteals which are specialized lymphatic ducts. (Adair, 1985) The effect of the breath apparatus through the action of the diaphragm, during deep inspiration, on the cysterna chyli and the small intestine may significantly enhance the rate or effectiveness of nutrient absorption.

The breath gentle body movements are considered especially important in traditional Asian systems of medicine and self-care as techniques for accelerating the circulation and absorption of healing nutritional factors in the diet and in medicinal and tonic herbal formulas. The clarification and understanding of the trophic function of the lymph suggests a simple but profound effect of the SAHEM on both the volume and flow rate of the lymphatic fluid and its nutrifying potential.

These mechanisms associated with lymphatic function play a significant role in the endogenous "healing system." They are naturally occurring and optimally functional in healthy individuals. One or several of these mechanisms may be deficient in individuals who are ill or at risk for disease. Each of these mechanisms are enhanced by the gentle movement, focused breath practice and relaxation that occur in the practice of Qigong, Yoga and other SAHEM.

BRAIN AND NERVOUS SYSTEM FUNCTION

Much of what is described in traditional medical systems as the "balance" of forces or energies, such as yin and yang in the Chinese system, can be associated with the dualistic components of the nervous system. In the central nervous system yin is rest and yang is action. Balance is the state between rest and action called dynamic equilibrium. This is the state that training in Qigong and Yoga seeks to refine. In the autonomic nervous system yin may be associated with the parasympathetic and yang may be associated with the sympathetic. The balance of yin and yang is associated with homeostasis—the state of balanced function and vitality.

Because the Western world view has generally had a difficult time understanding and accepting the concepts of Qi (chi), prana or vital force from the Asian systems, there has been a strong trend toward explaining the effects of Yoga, Qigong, acupuncture, etc. through the mechanisms of the nervous system (Kendall, 1989; Mann, 1973; Melzak and Wall, 1973; NIH, 1997). While these practices do have a definite effect upon neurological function, the neurological mechanism may actually be only an intermediary feature of a more refined and less easily quantified system of dynamic subtle energy interactions. However, much research has been done that reveals the neurological mechanisms activated in Qigong and Yoga, and it is appropriate to explore them here.

Qigong and Yoga and many of the SAHEM enhance several nervous system functions. These include:

1. initiation of the "relaxation response" (RR)
2. shift of the neurotransmitter profile
3. dilation of blood capillaries
4. support of the brain/neurological aspects of immune function
5. balance of right/left brain hemispheres
6. induction of alpha, and sometimes theta waves in EEG.

INITIATION OF THE RELAXATION RESPONSE

When the predominance of autonomic nervous system activity is sympathetic (adrenergic) the human system is working, expending energy and breaking down tissue. This is associated with the action phase of metabolism, and referred to as catabolic. In the extreme, this is the "fight or flight response" with increased heart rate, breath rate and blood pressure. It is also called the stress state and can lead to adrenal exhaustion and collapse (Selye, 1978). This state, when overactive and out of balance causes internal acidosis. Biological stress is conducive to the proliferation of a number of diseases or syndromes including hypertension, pain, depression, immune deficiency and inflammation (Benson, 1975).

The opposite aspect of autonomic activity, parasympathetic (cholinergic), is a phase of rest and tissue regeneration. It is associated with the conservative anabolic phase of metabolism. In its extreme this state is associated with the "relaxation response" (Benson, 1975), characterized by decreased heart and breath rate and a lowering of blood pressure. This is also associated with the resting phase of the basic resting activity cycle (BRAC), (Kleitman, 1967). Conscious deactivation of the sympathetic function with the activation of certain parasympathetic features of autonomic activity can neutralize the negative effects of "fight or flight" overactivity. The primary steps to initiate this state are deep, slow breathing coupled with the intention to relax. (Benson, 1975) These are the identical initiating steps for the practice of Qigong and Yoga. The literature alludes liberally to traditional Asian health maintenance practices as the historic source of techniques for generating the relaxation response (RR) and the typical biofeedback response (Green and Green, 1977).

NEUROTRANSMITTER PROFILE

Much of the new science of psychoneuroimmunology is based upon findings in the area of neurohormones, neuropeptides or neurotransmitters. It has already been mentioned that neurotransmitter receptor sites have been found on lymphocytes. A characteristic profile of neurotransmitters is present in a person who is experiencing pain, anxiety or depression. (Shealy, 1989) Joy, comfort or celebration produce their own neurotransmitter profiles as well. (Ornstein and Sobel, 1987) In patients suffering from pain, increased norepinephrine, reduced cholinesterase and depressed beta endorphin were found to be typical. (Shealy, 1989)

When SAHEM methods are employed that regulate the sympathetic function through the hypothalamus (see below) a neurotransmitter profile emerges which is characterized by decreased norepinephrine, elevated cholinesterase and elevated beta endorphin. (Shealy, 1989) The neurotransmitter profile present in the predominantly parasympathetic and usually more anabolic (alkaline) environment is recognized as able to reduce pain and depression (Shealy, 1989), reduce cravings for addictive substances (Kovacs, 1988) and promote healing.

Chinese research has quantified neurotransmitter activity specific to Qigong exercise. It was found that the Qigong effect, the biological state during Qigong practice, is associated with specific shifts in the monoamine neurotransmitter content of the blood. (Liu, 1988) Serotonin and 5HE generally tend to be decreased by Qigong practice. Noradrenaline and dopamine tend to increase. This demonstrates that the aspects of Qigong and Yoga that quiet the mind and relax the body tend to induce a neurotransmitter profile that is conducive to healing.

INCREASED MICROCIRCULATION

A classic body response in Qigong and Yoga is the elevation of skin temperature. In the fight or flight state, hyper-sympathetic, the arterioles in the skin, muscles and certain organs constrict. During the systematic deactivation of sympathetic function, typical in Qigong and Yoga, vasodilation occurs with the accompanying warmth of the surface of the skin. This is one of the primary goals in biofeedback training and was found as a typical response when the skin temperature of meditators was evaluated in research. (Green, 1977)

A number of studies from China explore the microcirculatory mechanism very thoroughly and conclude that this microcirculatory dilation, increasing blood volume in a particular region, is a major reason for the continued successful application of Qigong and other ancient health maintenance methods (Zhou, 1989; Xiu, 1988; Hong, 1988; Wei, 1988; Zhao, 1988; Chu, 1988).

An ancient saying from traditional Chinese medicine is, "The Qi is the commander (leader) of the blood, and the blood is the mother of the Qi" (Kaptchuk, 1983). It is interesting that the Chinese were aware of a direct relationship between healing energy and blood circulation long ago. They were able, without science as we know it, to develop specific self-healing methods that purposefully increase the circulation of Qi and blood more effectively to the tissues, organs and glands.

BRAIN/NEUROLOGICAL ASPECTS OF IMMUNE FUNCTION

In the classic tradition of Western science, it has been thought that the immune system was an autonomous self-regulating system. A tremendous amount of research now demonstrates that mental and emotional states alter resistance to disease and infection (Ornstein, 1987). Immune organs including the thymus gland, spleen, lymph nodes and bone marrow are invested with nerve tissue (Ornstein, 1987). Lymphocytes and macrophages have receptors for neurochemicals, including catacholamines, prostaglandins, serotonin and endorphin (Roszman, 1985; Ornstein, 1987). Clearly, there is a definite relationship between brain, nervous system function and immune capability—a major interaction of the "healing system."

In the practice of Qigong and Yoga the hypothalamus regulates the autonomic nervous system function to decrease sympathetic activity. (Green, 1977; Benson, 1975) A number of studies have demonstrated that the hypothalamus has an influence over immune function (Ornstein, 1987). The hypothalamus has 40 times more receptor sites than any other part of the brain or nervous system (Pert, 1985 and 1986).

Meditation, progressive relaxation, deep breathing and slow relaxed movement all tend to move the practitioner out of the sympathetic state and induce the relaxation response. Research on the effect of relaxation and visualization sheds some light on the effect that the Qigong and Yoga states may have on immune function. Groups of elders who received relaxation training had significant increases in the activity of "natural killer cells" while control groups did not. Chinese research has corroborated the positive effect of Qigong and other SAHEM on the status of immune function as well (Hong, 1988; Yao, 1989; Xu, 1988; Wang, 1988; Shannahoff-Khalsa, 1988).

BRAIN HEMISPHERE DOMINANCE

Thousands of years ago the Oriental practitioners of self-care disciplines intuitively developed an awareness of an alternating cycle of the predominance of body activity from the right side of the body to the left side. One particular Qigong method, Taiji (Tai Chi), is founded on a constant, flowing of the limbs in circular motions, alternating from right to left. The side of the body that bears the weight is planted, stable, heavy and associated with the Yin. The side that is free to move and kick is active, light, flexible and associated with the Yang. Constant alternation of right and left side activity are thought to balance the forces of yin and yang in the body. Focusing on the right and left sides, alternatively, activates and balances the right and left motor centers in the brain.

In Yogic medicine (Ayurveda), the channels or circuits that conduct the resonating human energy field, are called nadis. Ida nadi and Pingala nadi associate with right and left brain activities (Shannahoff-Khalsa, 1988; Werntz, 1983). This association effects right and left nasal passage activity. These channels alternate dominance in a 2-3 hour cycle, causing the dominant nostril to be clear while the other nostril to swells and becomes congested. (Werntz, 1983) This phenomenon was not noted in the Western world until 1889 when the German physician R. Kayser recorded his observation of the "nasal cycle" (Kayser, 1889). Much of the research on this phenomenon up through the 1980's was motivated by the quest to develop pharmaceuticals for nasal congestion (Shannahoff-Khalsa, 1988).

It has been demonstrated that the nasal cycle is coupled with the alternating lateralization of cerebral hemispheric activity (Werntz, 1983). It was found with research subjects that when a shift occurred in either nasal dominance or brain hemisphere dominance, there was an associated shift, within moments, in the other as well. The right nasal cavity, tends to be more open and the left more congested when the left hemisphere of the brain is more active. This is associated with the active phase of the BRAC and increased general sympathetic tone (Shannahoff-Khalsa, 1988). In contrast the right brain hemisphere is more active when the left nostril is open and dominant and the individual is in the resting phase of the BRAC or the para-sympathetic mode.

A number of different physiological states have been found to be associated with the dominance of one or the other nostril.

- deep sleep is initiated more quickly with left nostril dominance.
- appetite and digestive ability are enhanced during right nostril dominance.
- left nostril, right brain dominance is more conducive to receiving new ideas, while right nostril, left brain dominance is an advantage during discourse.
- it is possible to alter the pattern of "thought waves" by consciously alternating nasal dominance by exercising the congested nostril through forced nostril breathing (Shannahoff-Khalsa, 1989).

A specific Qigong and Yoga breath technique which has been practiced for centuries is the right and left singular nostril breathing. The Salk Institute has done extensive research with this technique, originally prompted by the researcher's work with the Kundalini Yoga tradition. The studies have shown that forcing the breath through the constricted nostril can increase the EEG amplitude of the contralateral hemisphere of the brain (Werntz, 1987). It has been demonstrated that certain diseases and psychopathologies are brain hemisphere specific (Flor-Henry, 1979; McIntyre, 1976). It may be possible, therefore, that the use of alternating single nostril breathing may be applicable as therapy in cases where lateralized dysfunction has been found.

In addition, it was discovered that there is a direct correlation between nasal dominance, brain hemisphere dominance and the lateralized biochemical activity in the peripheral body parts. Recent studies of the nasal cycle comparing plasma catecholamine levels in the venous circulation of the right and left arms found that levels of norepinephrine alternated in direct correlation with the rhythm of sympathetic dominance of the nasal passages (Kennedy, 1986).

INDUCTION OF ALPHA/THETA BRAIN WAVE ACTIVITY

The intention to relax and deepening of the breath are the classic initiating actions that trigger the "relaxation response." Research with practitioners of Yoga (Green, 1977) and Qigong (Collected Proceedings, 1988) has shown that during practice brain wave frequency tends toward the alpha range and in certain cases theta frequency brain activity is achieved.

Alpha level brain function is a result of relaxation and is conducive to healing. The slowing of heart rate, reduction of blood pressure and elevation of skin temperature are common physiological features of the alpha state. Theta is a deeper trance like state that has been found in research with individuals with extraordinary capabilities such as sitting on beds of nails or immediate wound healing without bleeding. (Green, 1977)

In Qigong and Yoga the goal is to bring the lowest achievable frequency of brain wave activity to the practice. In standing Qigong, where there is no body movement, deep states of consciousness with low frequency brain waves are more likely than in moving Qigong. Similarly, in Yoga, there are methods involving movement and methods that primarily involve stillness. The pure meditation state lends more easily to the theta range of brain activity.

Several EEG studies from China have concentrated on the quiescent state—meditation with no movement (Pan, 1988; He, 1988; Wang, 1988). However, the dynamic or moving methods are effective, as well, when the alpha or theta state is achieved with the movement. In both Qigong and Yoga it is a primary focus to "allow the body and energy to sink and relax" and to "relax into the posture."

These neurological mechanisms are associated with the production and circulation of an endogenous healing resource. In healthy individuals they are optimally functional. In those individuals who are ill or at risk for disease, one or several of these functions may be deficient. The gentle movement, focused breath practice and relaxation that occur in the practice of Qigong, Yoga and other SAHEM enhance all of the neurological activities.

ENERGETIC MECHANISMS

As has been shown, the benefits of practicing health enhancement and self-healing methods are significant even though we have little or no understanding of the traditional Asian mechanisms based in Qi and Prana. There is, however, a robust exploration of energetic biophysiology in the Western world that is not new. The biological energy for the work of the cell, called ergs, is fully embraced by conventional science. The electrical discharge in the sinus node of the heart and the ability to track it electrically through EKG has an unquestionable place in science and medicine. It is fully recognized that the movement of the neurological impulse along the nerve pathway includes a discharge of ions. The permeability of the cell membrane is directly linked to the electrical charge associated with the channels of entry and exit In diagnostic medicine the MRI's ability to manipulate the electrons within the cells is clearly based on energetic subtlety that is beyond ionic exchanges.

There is really no question that there has been a profound discussion of energetic physiology that is quite evolved in Western science. As early as 1935 Harold Saxton Burr described a system of electro-dynamic fields (Burr, 1935) from studies using DC current with both salamanders and humans (Burr, 1973). Previous to that numerous European and American scientists and natural philosophers, including Hippocrates, Paracelcus, Van Helmut, Fludd, Stahl, Mesmer, Galvani, Hahnamann discussed a non-chemical basis to life and medicine: pneuma, physis, munia, magnale magnum, magnetic fluid, anima, animal magnetism, life force, odic force, vital force, elan vitale, life field, etheronic force, body electric. This is a much richer history of energetic physiology than most people in the Western world are aware.

Robert Becker confirmed Burr's work and used low frequency DC currents to regenerate salamander tails, and foster healing in wounds and non-healing bone fractures. In his work with the National Institutes of Health (NIH) Becker demonstrated that the perineural (nerve sheath) network is highly conductive. The points of highest conductivity on this network are in the same spot, in many instances, as the major acupuncture points (Becker, 1985). B.E.W. Nordenstrom has delineated the vascular-interstitial closed circuit (VICC) as a system of preferential ion conductance pathways (PICP), comprising a network of biological circuitry (Nordenstrom, 1983) which is nearly identical to the energy channels of traditional Chinese medicine.

It is unlikely that much historic time will pass before the Western scientific community turns full strength on the issues of energetic physiology. Already the notion of inherent electrodynamic fields has gained significant attention. A concept is arising in both China and the west of "bioinformation," which is an intrinsic "informing" capacity across the life continuum, all the way from molecules through mind. (Rubik, 1995) It has been proposed that the energetic mechanism of acupuncture, energy medicine and the inner capacity for self-repair is mediated through an electromagnetic vector field, intrinsic to each living entity. (Liboff, 1997)

Qigong and Yoga with their roots in energy based systems and their obvious benefits in health and healing will only accelerate the movement toward a scientific clarification of the interface between the biochemical and bioenergetic aspects of physiology.

CONCLUSION

Qigong, Taiji, Yoga and various other self-applied health enhancement methods (SAHEM) including Feldenkrais and Alexander methods have demonstrated significant potential for disease resolution, health improvement, health maintenance and performance enhancement. The efficacy of these ancient techniques and the newer innovations can be explained clearly through our conventional scientific understanding of the activation of the body's basic self-regulatory mechanisms. Though the traditional Asian explanations for such efficacy has been based on mysterious and invisible forces, Qi and Prana, the methods are, nonetheless, fully congruent with our prevailing model of physiology.

One or several of the following mechanisms (see chart) are activated during the practice of various forms of SAHEM: enhancement of oxygen availability, cellular water production, lymph propulsion, cerebrospinal fluid motion, acceleration of immune activity, modification of the neu-

Physiological Mechanisms	Structures, Processes, and Substrates	Qigong or Yoga Activity
I. Oxygen		
1. Energy generation	Oxygen uptake	Movement/breath
2. Aerobic water	Oxygen uptake	Movement/breath
3. Immune enhancement	Oxygen uptake	Movement/breath
4. Free radical neutralization	Oxygen uptake	Movement/breath
II. Lymph		
1. Aerobic generation	Oxygen uptake	Movement/breath
2. Propulsion		
a) Aerobic	Oxygen uptake	Movement/breath
b) Intrinsic contraction	Interstitial fluid volume	Breath and relaxation
c) Muscle pump	Muscle contraction	Movement
d) Gravitational	Body position	Postures and movement
e) Breath apparatus	Lungs, diaphragm, cisterna chyli	Breath activity
3. Immune function	Propulsion (2a–e)	Breath, movement, and posture
4. Cerebrospinal fluid flow	Propulsion (2a–e)	Breath, movement, and posture
5. Nutritive function	Propulsion (2a–e)	Breath, movement, and posture
III. Nervous system		
1. Autonomic	Brain, neurochemistry, nervous system	Relaxation and breath
2. Neurotransmitter profile	Hypothalamus	Relax/visualize
3. Microcirculation	Hypothalamus	Relaxation
4. Immunity	Macrophages, lymphocytes, neurotransmitters	Relaxation, meditation
5. Brain hemisphere control	Brain, nervous system	Nostril breath and right/left side movement
6. Brain wave frequency	Brain, nervous system	Meditation
7. Neuroreflex stimulation	Neuroreflex system	Rubbing points

Appendix Figure 3.1. Physiological mechanisms and the activities in Qigong and other self-applied health enhancement methods (SAHEM) which are their triggers:

rotransmitter profile, initiation of the relaxation response, alpha range brain wave frequency, etc. Each of these mechanisms is a component of a powerful internal "healing system." Together they produce and circulate internal healing resources which are historically referred to in Asia as an "inner medicine" or "healer within." In Western terms we might call this an endogenous medicine or a naturally occurring self-repair resource.

It may be that simple SAHEM practices are among the most powerful healing tools ever developed by the human race. It is clear that triggering such an array of self-regulating internal mechanisms has a profound effect on the capability of an individual to maintain health or resolve disease. Given 70% of disease is preventable (DHHS, 1991) and 8 of the 9 major causes of disease are preventable (Fries and Koop, 1993), the SAHEM may be more powerful than post symptomatic medical intervention in reducing disease overall.

Using science to study Qigong, Yoga and acupuncture will very likely help to rewrite the textbooks of medicine and physiology. Direct study of the activity of the physiological states triggered in subjects trained in Qigong or Yoga is an obvious research priority. In light of the crisis in health care costs, it is the mandate of the medical and social sciences to purposefully remove barriers to the implementation of these practices and the study of their benefits.

It was agreed in 1997 that acupuncture had health enhancing potential (NIH, 1997) even though neither its traditional Asian explanation nor its Western scientific explanation were conclusive. Given the conventional scientific understanding of the SAHEM is very much more conclusive than the understanding of acupuncture, it is likely that Qigong and Yoga will be even more easily embraced in the emerging health care delivery paradigm that is based in health improvement. This promises to eventually create a radical transformation in health care and medicine, a major redesign of public health and a significant decrease in the cost of medicine.

For now we have ample evidence to confirm the value of these practices physiologically. Eventually, perhaps, our capacity to explore more subtle realms of human energy will confirm that there is an energetic feature of anatomy and physiology that we do not yet understand. Either way, it is clear that Qigong, Yoga and other SAHEM are practical, timely and inexpensive tools for increasing health and healing disease.

REFERENCES

Adair, T.H., Guyton, A.C., Introduction to the Lymphatic System. Experimental Biology of the Lymphatic Circulation. Johnston (ed), Amsterdam, Elsevier Science Publishers, 1985.

Becker, R. O., The Body Electric: Electromagnetism and the Foundation of Life. New York, William Morrow and Co., 1985.

Benson, H.R., The Relaxation Response, New York, William Morrow and Company, 1975.

Bradbury, M.W.B., Cserr, H.F., Drainage of Cerebral Interstitial Fluid and of Cerebral Spinal Fluid into Lymphatics. Johnston (ed), Biology of the Lymphatic Circulation, Elsevier Science Publishers, 1985.

Brahmi, Z., et al., Effect of Acute Exercise on Natural Killer Cell Activity in Trained and Sedentary Human Subjects, Journal of Clinical Immunology, 5(5):321, 1985.

Burr, H.S., Northrop, F.S.C., The Electro-dynamic Theory of Life. Quarterly Review of Biology, 8: 322-33, 1935.

Burr, H.S., Fields of Life. New York, Ballentine, 1973.

Chu Weizong, et al., Changes of cerebral blood flow and microcirculation under the Qigon state. Proceedings of the First International Conference for the Academic Exchange of Qigong, Beijing, China, 1988.

Collected Proceedings, The First World Conference for the Academic Exchange of Medical Qigong. Beijing, China, 1988.

Covelli, V., Jirillo, E., Neuropeptides with Immunoregulatory Functions: Current Status of Investigation. Functional Neurology. 3(3):253-261, 1988.

Cullen, K., et al., Multiple Regression Analysis of Risk Factors for Cardiovascular Disease and Cancer Mortlality in Busselton, West Austrailia: A 13 Year Study, Journal of Chronic Diseases, 36:371-377, 1983.

DHHS, Healthy People 2000. Department of Health and Human Services, 1991.

Drinker, C.K., Yoffey, J.M., Lymphatics, Lymph and Lymphoid Tissue. Cambridge MA, Harvard University Press, 1941.

Fehr, H.G. Human macrophage function and physical exercise: phagocytic and histochemical studies. European J Applied Physiology 1989;58(6):613-7.

Flor-Henry, P., Shizophrenic-like reactions and affective psychoses associated with temporal lobe epilepsy. American Journal of Psychiatry, 126:400-403, 1979.

Fries, J., and Koop, C.E., Refducing Health Care Costs by Reducing the Nedd and Demand for Medical Services. New England Journal of Medicine,

329: 321- 325, 1993.

Gordon, T., Kannel, W.B., The Framingham Study. An Epidemiological Investigation of Cardiovascular Disease. Sections 1-26, Bethesda MD, National Heart and Lung Institute, 1970.

Green, E., Green, A., Beyond Biofeedback. New York, Delacorte Press, 1977.

Guyton, A.C., Medical Physiology, Phila, Saunders and Co., 1992

Hong Shunhua, et al., A primary observation on microcirculation of nail fold and immunogenicity after Qigong practice for a short period. Proceedings of the First International Conference for the Academic Exchange of Qigong, Beijing, China, 1988.

Jahnke, R., Qi Gong: Awakening and Mastering the Profound Medicine that Lies Within. American Journal of Acupuncture, 17(2):139-151, 1989.

Kaptchuk, T.J., The Web That Has No Weaver. New York, Congdon and Weed, 1983.

Kayser, R., Die Exakte Messung der Lufterchgangigkeit der Nase, Z Ohrenheilk, 20:96-106, 1889.

Kendall, D.E., Understanding Traditional Energetic Concepts. Energy Fields in Medicine, Proceedings of the Fetzer Foundation1989 Conference coordinated by Michael Morton, 10-43, 1989.

Kennedy, B, Ziegler, M.G., Shannahoff-Khalsa, D.S., Alternating Lateralization of Plasma Catecholamines and Nasal Patency in Humans, Life Sciences, 38:1203-1214, 1986.

Kimber, D.C., Kimber, Gray, Stackpole's Anatomy and Physiology, 17th Edition, New York, Macmillan Publishing Co., 1977.

Kleitman, N., Basic Rest Activity Cycle in Relationship to Sleep and Wakefulness. In Kales, A., Sleep: Physiology and Pathology, Philadelphia, Lippincott, 1967.

Kovacs, G.L., Telegdy, G., Hypothalamo-neurohypophyseal Neuropeptides and Experimental Drug Addiction, Brain Research Bulletin, 20(6):893-895, 1988.

Liboff, A., Bioelectromagnetic Fields and Acupuncture. The Journal of Alternative and Complementary Medicine, 3(Supp 1), S-77—S-87, 1997.

Liem, S. H., The Effect of Sanumgerman (Germanium) on the Oxygen Partial Pressure of the Oxygen Multistep Process. paper presented at the International Conference on Organic Germanium. 1985.

Liu Binghuai, et al., Effects of the qigong exercise on the content of the monoamine neurotransmitters in the blood. Proceedings of the First International Conference for the Academic Exchange of Qigong, Beijing, China, 1988.

Mann, F, Acupuncture: The Ancient Chinese Art of Healing and How It Works Scientifically. New York, Random House, 1973.

McIntyre, M., et al., Left and right temporal lobe epileptics: a controlled investigation of some psychological differences. Epilepsia 17:377-86, 1976.

Melzak, R and Wall, The Puzzle of Pain. 1973 Harmondsworth : Penguin Books, 1973.

NIH, National Institutes of Health Consensus Panal on Acupuncture, 1997.

Nordenstrom, B.E.W., Biologically Closed Electrical Circuits: Clinical, experimental and theoretical evidence for an additional circulatory system. Stockholm, Sweden, Nordic Medical Publications, 1983.

Olszewski,W.L., Lymphatic Contractility. New England Journal of Medicine, 300, 316, 1979.

Olszewski, W.L., Peripheral Lymph: Formation and Immune Function. Boca Raton, FL, CRC Press, 1985.

Ornstein, R., Sobel, D., The Healing Brain. New York, Simon and Schuster, 1987.

Pedersen, B.K., et al., Modulation of Natural Killer Cell Activity in the Peripheral Blood by Physical Exercise. Scandanavian Journal of Immunology, 27(6):673-678, 1988.

Pert, C.B., et al., Neuropeptides and their receptors: a psycho somatic network. The Journal of Immunology, 135(2):820-826, 1985.

Pert, C.B., The wisdom of the receptors: neuropeptides, the emotions

and the bodymind. Advances, Institute for the Advancement of Health, 3(3):8-16, 1986.

Rubik, B., The unifying Concept of Information in Acupuncture and Other Energy Medicine Modalities. The Journal of Alternative and Complementary Medicine, 3(Suppl), S-67—76, 1997.

Roszman, T.L., et al., Neuroanatomic and neurotransmitter influences on immune function. The Journal of Immunology, 135(2):769-772, 1985.

Rusznyak, I., Foldi, M., Szabo, G., Lymphatics and Lymph Circulation. London, Pergamon Press, 1976.

Saltzman, R.L., et al., Immunodeficiency of the Elderly. Reviews of Infectious Diseases, 9(6):1127-1139, 1987.

Selye, H., The Stress of Life, New York, McGraw-Hill Book Co., 1978.

Shannahoff-Khalsa, D., A Contemporary View of Life Force Biology: The Merging of Kundalini Yoga and the Neurosciences, in Energy Medidcine Around the World, ed T.M. Srinivasan, Pheonix, AZ, 1988.

Shannahoff-Khalsa, D., Rhythems of the Mind and Breath, Advances, Journal of Mind-Body Health, 6, #2, 51-55, 1989.

Shealy, C.N., et al., Depression: A Diagnostic Neurochemical Profile and Therapy with Cranial Electrical Stimulation, Journal of Neurological and Orthopedic Medicine and Surgery, 10(4):319-321, 1989.

Shields, J.W., The Trophic Function of the Lymphoid Elements. Springfield, Il., International Foundation of Lymphology, 1972.

Shields, J.W., "Central Lymph Propulsion," Journal of the International Society of Lymphology, 13(1):9-17, 1980.

Shields, J.W., Human Central Lymph Propulsion, Journal of the American Medical Association, 246 (18), 1981.

Shields, J.W., The Aerobic Production and Central Propulsion of Lymph. Proceedings of the 12th International Congress of Lymphology, Tokyo, Japan, September, 1989.

Smith, E.M., et al., Lymphocyte production of endorphins and endorphin-mediated immunoregulatory activity. The Journal of Immunology, 135(2):779-782, 1985.

Smith, R.O., Lymphatic Contractility: A Possible Intrinsic Mechanism of the Lymph Vessels for Transport of Lymph. Journal Of Experimental Medicine, 90, 497, 1949.

Temple, R, Needham J, The Genius of China: 3,000 years of science, discovery and invention, New York, Simon and Schuster, 1986.

Van Rooijen, n., The "In Situ" Immune Response in the Lymph Nodes: A Review. The Anatomical Record, 218(4):359-364, 1987.

Veith, I., The Yellow Emperor's Classic of Internal Medicine (Nei Ching). Berkeley, University of California Press, 1972.

Wang, Zhengchang, et al., A preliminary study of the relationship between Qigong and energy metabolism: the changes of blood ATP content in Qigong masters in the Qigong state. Proceedings of the First World Conference for the Academic Exchange of Medical Qigong, Beijing, China, Pg 58, 1988.

Warburg, O., The Prime Cause and Prevention of Cancer, 1966 Lindau Lecture, Wurzburg, Germany, K. Triltsch.

Wei Shouzhang, et al., An experimental research of the changes of blood volume in the brain and the changes of the heart rate in the Qigong and PSI state. Proceedings of the First International Conference for the Academic Exchange of Qigong, Beijing, China, 1988.

Werntz, D., Bickford, R.G., Bloom, F.E., Shannahoff-Khalsa, D.S., Alternating Cerebral Hemispheric Activity and the Lateralization of Autonomic Nervous Function. Human Neurobiology, 2:39-43, 1983.

Werntz, D., Bickford, R.G., Shannahoff-Khalsa, D.S., Selective Hemispheric Stimulation by Unilateral Forced Nostril Breathing. Human Neurobiology, 6:165-171, 1987.

Yoffey, J.M., Courtice, F.C., Lymphatics, Lymph and the Lymphomeyloid Complex. London, Academic Press, 1970.

Xie Zhu Fan, et al., Reference Guide to Acupuncture: Zang Fu Principles and Diagnosis. Wonder Lake, IL, Northern Star Press, 1988.

Xiu Ruijuan, et al., Studies of Qigong effect on the human body by the computerized synchronous system for macro and microcirculatory parameters measurement. Proceedings of the First International Conference for the Academic Exchange of Qigong, Beijing, China, 1988.

Zhao Baofeng, et al., Effects of Qigong on cerebral blood flow (CBF) and extremitic blood flow (EBF). Proceedings of the First International Conference for the Academic Exchange of Qigong, Beijing, China, 1988.

Zhou, M.R., Observation of Qigong treatment in 60 cases of pregnancy induced hypertension. Chung Hsi i Chieh Ho Tsa Chih, 9(1):16-18, 1989.

1Note: Taiji (Tai Chi) is a kind of Qigong. Pranayama is an aspect of Yoga. Feldenkrais Method, Alexander Technique and numerous systems of self-initiated health enhancement including puroseful walking and very low impact aerobics are more recently developed self-applied health enhancement methods (SAHEM).

GLOSSARY OF TERMS

A

Abdominal Breathing - to breathe from the abdomen (expand with inhalation, contract with exhalation).

Acupuncture - one of the Four branches of Traditional Chinese Medicine, which involves treating patients through the use of Needling, Cupping, Bloodletting, Moxa and Magnets in order to stimulate energy flow.

Acupuncturist - a doctor of acupuncture therapy.

Acquired Essence - also called Postnatal Jing, is acquired energetic tissue substance, developed after birth.

Acquired Force - energy pertaining to the Earth and surrounding environment.

Acquired Qi - also called Postnatal Qi, is the body's energy derived from food, air and drink, acquired after birth.

Acquired Rational Mind - also called postnatal mind, are thoughts and feelings derived from the acquired experiences of one's environment.

Acute - a rapid onset and short duration of a particular condition.

Adenoma - a neoplasm (abnormal formation of tissue) of glandular epithelium.

Adenocarcinoma - a malignant tumor arising from a glandular organ.

Affirmation - a word, phrase or sentence that is repeated frequently to influence, or change, a belief held deeply within the unconscious mind.

Agoraphobia - fear of places or situations from which escape might be difficult or embarrassing. Symptoms include panic like symptoms and a precondition towards panic attacks.

Akashic Records - a Sanskrit term used to describe the detailed knowledge of all the historical events of the world recorded within the "all-pervasive space of the universe" or "Wuji," also called the "knowledge of the infinite Void."

Alchemy - internal transformation of body and energy brought about by: 1. Nei Dan (Inner Alchemy) through internal Qigong training, and 2. Wai Dan (External Alchemy) using herbal formulas.

Amenorrhea - the absence or suppression of menstruation.

Ancestral Channel - a term used to describe one of the Eight Extraordinary Vessels.

Ancestral Qi - energy inherited from both parents at the time of conception, responsible for innate talents and skills.

Ancestral Traits - pertaining to the ancestral spiritual influence which affects the patient's body. Ancestral traits are developed according to the geographic location at the time of conception.

Anemia - a reduction in the number of circulating red blood cells.

Angina Pectoris - severe pain and a sensation of constriction about the heart.

An Jing - see Hidden Power.

Ankylosing Spondylitis - inflammation of the vertebrae, giving rise to stiffness of the back.

An Mo Therapy - a tissue manipulation therapy that focuses primarily on the treatment of internal organ disorders.

Anorexia - loss of appetite.

An Sound Resonation - Hidden or inaudible sound resonation.

Antibody - any of the numerous proteins produced by the immune system that defend against antigens.

Anxiety - emotional distress, resulting in Heart palpitations, inability to concentrate, muscle tension causing muscle aches.

Aphasia - the absence or impairment of the ability to communicate through speech, writing, or signs, due to a dysfunction within the brain center.

Aplastic Anemia - anemia caused by deficient red cell production, due to bone marrow disorders.

Apoptosis - the disintegration of cells into membrane-bound particles that are then phagocytosed by other cells.

Archetypes - a term coined by the psychiatrist Carl G. Jung to describe the collective unconscious images and motifs (e.g., warrior, healer, priest, whore, etc.). An inherited idea or mode of thought derived from the experiences of the race which is present in the unconscious of the individual.

Arrhythmia - an irregularity or loss of rhythm pertaining to the Heart.

Arteriosclerosis - term pertaining to a number of pathological conditions in which there is a thickening, hardening, and loss of elasticity of the artery walls.

Arthralgia - pain in the joints.

Arthritis - pain and inflammation of the joints, followed by progressive stiffness.

Arthropathy - pertaining to any joint disease.

Ascariasis - infestation of ascaris lumbicoides parasite (pinworm).

Ascending Qi - the action and flow of energy moving upward.

Ashi Points (also called Trigger Points) - places on the body which are tender spots or painful areas near diseased or injured tissue.

Asthma - a disease caused by increased responsiveness of the tracheobronchial tree within the Lungs, due to various stimuli, causing severe difficulty in breathing.

Astral Body - also called the Soul Body, describes the energetic vehicle in which the Eternal Soul can journey outside of the physical body. The Astral Body is connected to the Middle Dantian by a silver "cord of life."

Astral Matter - the energetic substance located within the second field of the body's external Wei Qi and attributed to the emotional energy body.

Astral Plane - an energetic and spiritual plane of existence parallel to the physical plane.

Astral Travel - also called Soul Travel (or Astral Projection) describes the condition of the Eternal Soul journeying outside of the physical body, connected to the Middle Dantian by a silver "cord of life."

Astringent - any substance or agent that causes tissues to contract or that inhibits secretion of Body Fluids such as mucus or Blood.

Antigens - any substance able to provoke an immune response in the human body.

Atrophic - pertaining to atrophy.

Atrophy Syndrome - a disorder characterized by flaccidity and weakness of the limbs and a progressive loss of strength and muscle tone.

Attention Deficit Disorder - a learning disorder manifesting through the following symptoms: habitual failure to pay attention, very distractible, inability to organize, extreme impulsiveness, difficulty in studying, often accompanied by hyperactivity.

Aura - the energetic field which radiates light and circulates around the second field of the body's external Wei Qi

Aura Colors - the body's energetic luminous colors ranging from red, orange, yellow, green, blue, violet to white.

Auspicious Powers - the energy potential contained within the Five Yin Organs.

B

Ba Gan - eight diagnostic principles used in Traditional Chinese Medicine in order to differentiate symptoms.

Bai Dai - white vaginal discharge.

Baihui Point (One Hundred Meetings) - the Governing Vessel point at the top of the head (GV-20).

Bellows Palm Technique - a palm technique in which the thumb and little finger compress and release like a bellows.

Bells Palsy - unilateral facial paralysis of sudden onset.

Benign - gentle or kindly, not aggressive, the opposite of malignant.

Bile - a secretion stored in the Gall Bladder released into the duodenum as a digestive juice.

Bio-Rhythm - three distinct cycles and energy flow that pertain to the body's physical, emotional and intellectual rhythms.

Bipolar Personality Disorder - formerly known as Manic Depressive Personality Disorder, a state of extreme euphoria or pervasive irritability, with racing thoughts, inability to sleep, and impulsive behavior (that may last for days or months), that alternate with morbid depression with suicidal ideation or attempts at suicide (see Depression). During the manic phase there may be hallucinations.

Bird's Bridge - pertaining to the energetic connection between the tongue and the upper "hard" palate, behind the teeth.

Birth Energetic Patterns - pertaining to the energetic patterns developed according to the influence of the time and geographic location of the patient's birth.

Bladder Fire - also called Common Peoples' Fire, or Perineal Fire, is located in the lower abdomen by the perineum, and is responsible for evaporating water.

Blended Originals (Hun Yuan) - the body's "internal combined energy" fused into the Lower Dantian area.

Bloated and Expanded Stagnation - stagnation with a characteristically expansive or bloated appearance, can be caused from an accumulation of Phlegm and Body Fluids (in addition to Qi and Blood) in the adjacent tissue areas of the body.

Blood (Xue) - the dense fluid which nourishes the body, transmits Qi, and provides the material for the mind and emotions.

Blood Heat - a condition categorized by Heat and Blood signs (retching of Blood, expectoration of Blood, Bloody stool or urine, nosebleeds, and menstrual irregularities).

Bloodletting - a technique used in acupuncture therapy which entails pricking the skin to release and remove Blood Heat and Blood stagnation.

Blood Stagnation - the impairment or cessation of normal Blood flow.

Blood Stasis - the same as Blood stagnation.

Blood Vessels - the body's transportation system for Qi and Blood nutrition and regeneration.

Body Fluids (Ye) - these are clear, light, and watery. They originate from food and drink and are transformed and separated by the Spleen (aided by the Kidneys) and dispersed by the Lungs and Triple Burners. (i.e., sweat, tears, saliva, and mucus.)

Body Liquids (Jin)- these are a heavier denser form of Body Fluids. Their function is to moisten the joints, spine, brain, and bone marrow. They lubricate the orifices of the sensory organs.

Bone - the body's skeletal material related in essence to the Kidneys.

Bone Marrow - sustains and nurtures the bones, composed of Kidney Jing (Essence) and Marrow.

Book of Commentaries - consisting of ten commentaries from Confucius and his disciples, pertaining to the study of the eight trigrams, sixty-four hexagrams, and the Yi-Jing.

Book of Oracles - written by King Wen and the Duke of Zhou, pertaining to the study of the eight trigrams, sixty-four hexagrams, and the Yi-Jing.

Borborygmus - a gurgling, rumbling sound heard over the Large Intestine, caused by the passing of gas through the liquid contents of the intestines.

Borderline Personality Disorder - a psychological disorder characterized by a pervasive pattern of intense, unstable relationships, and an unstable self-image. Such patients suffer from chronic feelings of emptiness stemming from abandonment issues. They exhibit self-destructive behavior and transient paranoia, or dissociative symptoms.

Brain - pertaining to the Sea of Marrow issuing from the Kidneys that collects within the cranium.

Brain Tumor Point - Shihmien Point located on the heel of each foot.

Bronchial Asthma - asthma caused by a hypersensitivity to an allergen.

Bronchiectasis - chronic dilatation of a bronchus or bronchi, with a secondary infection (usually involving the lower portion of the Lungs).

Bronchitis - inflammation of mucous membrane of the bronchial tubes.

C

Caduceus - medical insignia picturing double snakes wrapping a winged staff.

Calculi - the plural of calculus or stones, usually composed of mineral salts.

Cancer - an obstruction of Qi and Blood circulation resulting in stagnation and the formation of a malignant tumor that tends to spread.

Carbuncle - a circumscribed inflammation of the skin and deeper tissues.

Carcinogens - any substance or agent that produces or increases the risk of developing cancer.

Carcinoma - a malignant growth or tumor that occurs in the epithelial tissue (the outer surface or first layer of tissue that lines the body's cavities, as well as the principal tubes and passageways leading to the exterior of the body)

Catatonic - totally withdrawn, almost unconscious, frozen and unable to move.

Celestial Stems - see Ten Celestial Stems.

Center Core - pertaining to either 1. The core of light within the Taiji Pole which joins the body's three Dantians through the center of the body, or 2. The True Self (the essence of a person's spirit).

Cerebral Embolism - a condition which occurs when an embolus (bubble of air, or piece of a thrombus) detaches from a thrombus and obstructs a cerebral artery.

Cerebral Hemorrhage - bleeding caused from a rupture of a sclerosed or diseased vessel in the brain.

Cerebral Thrombosis - an obstruction of a cerebral artery by a thrombus (blood clot).

Cerebro-Vascular Accident (CVA) - in the clinic, conditions referred to as stroke (or Wind-stroke) include cerebral hemorrhage, cerebral thrombosis, cerebral embolism, and cerebrovascular spasm. These four conditions are termed in Western Medicine as "Cerebro-Vascular Accident."

Cervical Spondylosis - a degenerative arthritis (osteoarthritis) of the cervical vertebrae and related tissues.

Chakra - an energetic vortex, spiraling out from the body's Taiji Pole, manifesting in the body and extending through the external field of Wei Qi.

Chakra Gates - the twelve major energy gates located on the center line of the anterior and posterior aspects of the body, as well as at the lower perineum and the top of the head.

Chakra System- the seven major Chakra or energy centers that connect to the Taiji Pole. Five Chakras extend to the front and back of the torso, with an additional one located at the top of the head and on the perineum.

Channels - the body's energetic rivers responsible for transporting Qi, also called "meridians."

Channel Points - areas or points (similar to small pools of Qi) found along the streams of a Channel, through which energy of the Yin and Yang (Zang / Fu) organs and channels are transported internally and externally.

Channel Qi - pertaining to the Qi found within the energetic flow of a channel.

Charts of the Hall of Light - ancient diagram depicting the body's internal organs and channels.

Chemotherapy - the application of chemical agents that have a specific and toxic effect upon the disease-causing microorganism, as well as the patient's tissues, energetic fields and immune system.

Chicken Pecking Palm Technique - a palm technique wherein the doctor's hand resembles the head of a chicken while manipulating the energy flow of the Invisible Needle.

Chi Dai - red vaginal discharge.

Child Element - pertaining to the Five Element Creative Cycle of Traditional Chinese Medical, the primary organ is considered the Mother and its sequential organ is considered the Child.

Chinese Massage and Tissue Regulation - one of the four branches of Traditional Chinese Medicine, which involves treating patients through the use of tissue manipulation, including Jie Gu Therapy for bone disorders, Tui Na Therapy for muscle disorders, Gua Sha Therapy for febrile diseases, An Mo therapy for internal organ disorders, and Jing Point Therapy for channel and internal organ regulation.

Cholecystitis - inflammation of the Gall Bladder.

Cholelithiasis - formation of calcium, i.e., bile stones in the Gall Bladder.

Cholestasis - an infection of the biliary tract.

Chronic - the long duration of a specific disease or condition, showing slow or little improvement.

Chronic Fatigue Syndrome - debilitating fatigue that is not the result of physical or mental exertion, and does not diminish by resting.

Chrono-biology - the science that deals with the study of the body's biological clocks and fluctuations in accordance with the cycles of the sun, moon and nature's rhythms.

Chyluria - the passing of fat globules in the urine.

Circle of Willis - the union of the anterior and posterior cerebral arteries, forming an anastomosis at the base of the brain.

Circulating Energy Technique - this method refers to rotating Qi in a circular pattern (clockwise or counterclockwise) to move Qi and Blood stagnation, or to gather energy for tonification.

Cirrhosis - Cirrhosis is a generalized Liver disease marked by hepatic lesions, characterized by the formation of dense lobular connective tissue, degenerative changes in the parenchymal cells, structural alterations in the Liver lobules, and sometimes fatty and cellular infiltration within the Liver.

Clairaudience - the ability to hear sounds, music, and voices not audible to normal hearing (for example, receiving Messages and / or inspirations from the divine).

Clairasentience - the ability to perceive smells, taste, touch, emotions and physical sensations that contribute to an overall psychic and intuitive impression.

Clairvoyance - the ability to perceive current objects, events and / or people that may not be discerned through the body's normal senses. Both time and space are perceived on a clairvoyant spiritual dimension.

Clean Qi - Energy which has been purified.

Clinical Ethics - the moral principles and standards governing the doctor's conduct with patients in or away from the clinic.

Coccyx Pass (Wei Lu Guan) - is located on the lowest segment of the spine just posterior to the anus, near the Chang Qiang (GV-1) point.

Colitis - the inflammation of the colon.

Cold Constitution - pertaining to a physical body innately prone towards coldness.

Collapsed Qi - this is considered a subcategory of Deficient Qi, and is regarded as the third and most severe type of Deficiency.

Collaterals (Luo) - the body's energetic streams that branch off the Twelve Primary Channels and the Conceptional and Governing Vessels.

Collective Unconsciousness - concept of psychiatrist Carl G. Jung pertaining to the memories of mental patterns that are experienced and shared by all mankind.

Coma - an abnormal deep state of unconsciousness with some possible awareness of surroundings, but a total inability to communicate with the outside environment. Comas result from a Qi obstruction to the brain caused by illness or injury.

Common People's Fire - pertaining to the Bladder Fire, located in the perineal area of the body.

Compressed Stagnation - stagnation caused by the patient's energy pressing downward (externally moving inward), feels armored and hollow.

Concentrative Meditation - keeping the mind focused and under control.

Congealed - when Qi and/or Blood become thick and solid within the body's tissues, energetic fields, or both.

Congenital Qi (Prenatal Qi) - energy existing before the fetus is born, acquired from the mother's, father's energies, as well as from the environmental and universal energies. It is sustained through prayer, meditation and sleep.

Conscious Mind - acquired mental reasoning, created through learning via the five senses and interactions with other people.

Constipation - difficulty or infrequent defecation, with the passage of unduly hard and dry fecal material.

Constitutions - see Five Elemental Constitutions.

Contracted Stagnation - stagnation caused by the patient's energy pulling inward, feels armored and solid.

Contraindications - any symptom or circumstance indicating the inappropriateness of a form of treatment that would be otherwise advisable.

Controlling Cycle - pertaining to the Five Element Cycle, where one organ controls the second elemental organ in the Five Elements' Circle.

Corporeal Soul - see Po.

Coryza - the inflammation of the respiratory mucous membranes.

Cosmology - the study of the universe.

Countertransference - this is the process whereby a doctor loses objectivity and unconsciously projects feelings, thoughts, beliefs and patterns of behavior onto the patient.

Couple Point - the Master Point's secondary point of connection affecting the Eight Extraordinary Vessels.

Cranio-Sacral Rhythm - Western term given to the fluctuating rhythm of the Sea of Marrow flowing from the Kidneys.

Creative Cycle - pertaining to the Five Element Cycle, where one organ creates the energy for the next.

Creative Subconscious Mind - the part of the mind that maintains the patient's reality by making him or her act like the person they believe themselves to be.

Creative Visualization - the process of using visualization as a tool for transforming energy and spirit.

Crown Center - the name given to the Baihui Point (GV-20) and Upper Chakra Gate, at the top of the head.

Crystal Palace - the energetic field of Qi located within the third ventricle of the brain.

Cupping - a technique used in acupuncture therapy in which wooden, clay, or glass cups are adhered to the patient's skin by suction, to drain or remove pathogenic Qi from the body's pores.

Curious Organs - the body's Six Extraordinary Yang Organs which function like Yin Organs as they store Yin Essence (i.e., Blood, Marrow, or Kidney Essence), but look like Yang Organs (because they are hollow). These organs consist of the uterus, brain, Marrow, bones, blood vessels and Gall Bladder.

Cycle of Disharmony - an emotional state which induces a vicious cycle of physical, mental, emotional, energetic and spiritual disharmony.

Cyst - a closed sac that forms in tissue or a body cavity.

Cystitis - inflammation of the Bladder, usually occurring secondary to ascending urinary tract infection.

Cytotoxic Treatments - treatment containing toxins which attack the cells of the body (for example: radiation and chemotherapy).

D

Dacryorrhea - excess tear flow.

Damp - a internal pathogenic condition relating to the storage of Damp or Wet toxins.

Dantians - the body's three main energetic pools, or reservoirs located in the head, chest and lower abdomen.

Dantian Regulation - the principle of balancing the energy governing the body's three main energetic pools (Dantians).

Dao - pertaining to God or divine consciousness.

Daoist - a student of the "Dao" or way of life, pertaining to living in harmony with the universe and environment.

Dao Yin - energy regulation exercises consisting of training the body, mind, and breath.

De - pertaining to an individual's personal Virtue.

Defence Mechanisms - see Ego Defence Mechanisms.

Deficiency - a condition relating to the inadequate degree of a particular substance, e.g., Qi, Blood, Yin, Yang, Heat, etc.

Delusions - refers to the occurrence of a mental derangement in the patient resulting in a false belief based on incorrect inference about external reality. Regardless of the evidence to the contrary, the belief is strongly maintained.

Demon or Spirit Oppression - the condition of having a foreign spirit attach to a patient's external Wei Qi field, resulting in emotional disharmony.

Demon or Spirit Possession - the condition of having a foreign spirit invade and inhabit the patient's body, mind, emotion, and spirit.

Denial - a conscious refusal of an impulse-evoking fact, feeling or memory.

Depersonalization Disorder - persistent, recurring episodes of depersonalization, characterized by a feeling of detachment, or estrangement from one's self.

Depression (Major) - a psychological disorder resulting in major sadness and pessimism, feelings of worthlessness, helplessness and hopelessness. Symptoms include overeating or under-eating, insomnia or hyper-insomnia, difficulty concentrating, and fatigue.

Descending - the action of energy moving downward.

Diabetes - a general term used to describe diseases characterized by excessive urination and a sugar imbalance in the Blood.

Diaphoresis - profuse sweating.

Diathermy - the therapeutic use of a high-frequency current to generate heat within a certain area of the body.

Di Qi - Earth (Environmental) Energy.

Disharmony - pertaining to a lack of adequate balance of energy.

Disorder - an abnormal state of physical, mental, emotional, energetic or spiritual disharmony.

Dispersing- the spreading of Qi to other parts of the body, or purging of pathogenic energy from the body.

Displacement - the shifting of impulses aroused by one person, or situation on to a safe target.

Dissociated Identity Disorder - new terminology used for multiple personality disorder.

Distance Therapy - also called External Qi Therapy, Qi Emission and Outgoing Qi Therapy, is defined as extending or projecting energy into a patient from a distance.

Divergent Channels - twelve secondary channels that parallel the Twelve Primary Channels.

Divine - pertaining to God.

Divine Center - referring to the North Star's stable position in the sky.

Divine Hook-Up - the Qigong doctor's initial preparation for therapy, wherein he or she connects with the divine for guidance.

Divine Therapy - long distance Qigong healing.

D.M.Q. - a licensed Doctor of Medical Qigong Therapy, presently only obtainable in China.

Dong - the Yang method of dynamic Postural Dao Yin training.

Dragon's Mouth Palm Technique - hand technique wherein the thumb touches the other four fingers of the hand, forming an image of the head of a dragon. This hand manipulation is used for leading and pulling the Qi.

Draining Qi - drawing off pathogenic energy from a specific organ area or channel of the patient's body.

Dredging - a type of energetic purging, used to clean the patient's energetic fields and channels.

Drilling Energy Technique - this method refers to rotating Qi in a spiraling pattern (clockwise or counterclockwise) to access the energy deep inside the patient's body.

Dryness - a internal pathogenic condition relating to the storage of Dry toxins.

Dynamic Qigong - energy gathering which utilizes active movements of the body.

Dysmenorrhea - painful menstruation.

Dyspepsia - painful digestion.

Dyspeptic - one afflicted with dyspepsia.

Dysphagia - difficulty in swallowing.

Dysphoria - exaggerated feeling of depression, anxiety and unrest.

Dysplasia - the abnormal development of tissue.

Dyspnea - air hunger, resulting in difficult breathing, shortness of breath, sometimes accompanied by pain.

Dysthymia - a chronic, form of depression (lasting at least two years), for children and adolescents the mood can be irritable rather than sad.

E

Earth Element - one of the Five Elements, pertaining to Spleen and Stomach.

Earth Energy (Qi) - Energy pertaining to the Earth and surrounding environment.

Earth Jing - energy that supervises the maturation phase of the fetus's ability for emotional and spiritual bonding during the seventh month of pregnancy.

Earthly Branches - twelve energies of the Earth represented in the human body as the Twelve Primary Channels.

Earth Transpersonal Point - pertaining to the body's energetic connection to the Earth, located several feet beneath the feet.

ECG (or EKG) Eletrocardiogram - a graphic record made by an instrument that measures the Heart's electrical activity; usually used to confirm a diagnosis of a Heart condition.

Eclampsia - coma and convulsive seizures (between the 20th week of pregnancy and first week postpartum). Symptoms result in edema of the legs and feet, puffiness of the face, hypertension, severe headaches, dizziness, epigastric pain, nausea, sudden convulsive seizures and coma.

Eczema - an acute or chronic inflammation of the skin.

Edema - an acute or chronic cutaneous inflammatory condition.

EEG Electroencephalogram - a graphic record made by an instrument that measures the brain's electrical activity and records it as patterns of fluctuating waves.

Ego - the ego is the mediator between the id and the superego. According to Dr. Sigmund Freud's psychoanalytical theory, the superego combines the critical inner parent aspect with the idealistic aspect of the individual's conscience; the id consists of unconscious drives and instincts. The ego as meditator is responsible for ensuring rational behavior.

Ego Defense Mechanisms - according to Dr. Sigmund Freud's psychoanalytical theory, the ego defence mechanisms include: Repression, Displacement, Projection, Intellectualization, Regression, Fixation, Denial, Reaction-Formation, and Sublimation.

Eight Confluential Points - the areas where the Eight Extraordinary Vessels and Twelve Primary Channels intersect with each other.

Eight Energetic Principles - a system of differential diagnosis using four pairs of opposites (Yin and Yang, Cold and Hot, Deficient and Excess, Internal and External).

Eight Energetic Touches - pertaining to the somatic tissue response to energy stimulation (tingling, sensations of heat, coldness, expansiveness, contracted, heaviness, lightness, and vibration).

Eight Extraordinary Vessels - the primary channels responsible for the formation of the fetus, which after birth, are considered the body's reservoirs for collecting the overflow energy from the Twelve Primary Channels.

Eight Miscellaneous Factors - eight factors that can off set the patient's Yin and Yang balance (diet, overexertion, excessive sex, child bearing, traumatic injuries, exposure to poisons, parasites, and iatrogenic disorders).

Eight Trigrams (Bagua) - eight cosmological patterns of three lines (solid and / or broken), called Yaos, used to diagnose as well as predict future transitions.

Emaciation - the state of being malnourished and extremely lean.

Embolus - the obstruction of a blood vessel by foreign substances or a blood clot.

EMG Electromyogram - a graphic record made by an instrument that measures the muscle's electrical activity and records its function.

Emitting Qi - the Qigong doctor extending energy outside the body for the purpose of treating a patient.

Emotional Energy Body - is the external energy existing in the body's second field of Wei Qi, which is attached to the internal organs.

Emotional Spirit - pertaining to the Emotional Energy Body.

Empathic Communication - the doctor's ability to experience the feelings and thoughts of his / her patients.

Empty Qi - a serious weakness or Deficiency of the body's Qi.

Encephalomyelitis - acute inflammation of the brain and spinal cord.

Endrometrial Hyperplasia - excessive proliferation of the cells within the lining of the uterus.

Energetic Armoring - a condition resulting from the patient protecting specific tissues, organs, or areas of the body. Energetic armoring is initiated when the patient freezes certain emotional feelings to maintain the denial system.

Energetic Barriers (Energetic Boundaries) - the protective barriers existing within and outside of the body's tissues.

Energetic Complications - pertaining to energetic imbalances within the patient's tissues (e.g., compressed energy stagnation, energetic armoring, migrating Qi deviations, etc.)

Energetic Cords - energetic bands of light and vibration which form an emotional attachment, connecting the patient to certain people, places, or things.

Energetic Grids - an energetic net covering the surface of Heaven , Earth or the human body.

Energetic Leakage - a condition resulting from the patient releasing Qi out of the joints, due to an injury or unconscious sabotage.

Energetic Medicine - any and all medicine having to do with the stimulation, cultivation, tonification, purgation, balance and maintenance of the body's Qi.

Energetic Point Therapy - extending energy from a distance into specific channel points, or vessels on the patient's body.

Enteric Nervous System - pertaining to the nervous system of the Small Intestine.

Enuresis - the involuntary discharge of urine.

Environmental Energy (Qi) - Energy pertaining to the Earth and surrounding environment.

Environmental Force - energy pertaining to the Earth and surrounding environment.

Epigastric Pain - pain in the region over the pit of the stomach.

Epileptiform - having the form of epilepsy.

Epistaxis - bleeding of the nose.

Epithelial Hyperplasia - excessive proliferation of the cells within the outer surface of the body, including the secreting portions of the glands and ducts.

Essence (Jing) - referring to either Prenatal and Postnatal energetic tissue mass.

Eternal Soul - the individual's True Self, which is always connected to the divine. It is absorbed into the mother's egg at the time of conception, and is rooted within the body's Taiji Pole.

Ethereal Matter - the body's foundational energetic substance.

Ethereal Souls - see Hun.

Etiology - the causes of a disease.

Eustachian Tubes - the auditory tube, extending from the middle ear to the pharynx.

Evil Embryo - pertaining to a toxic formation in the form of a tumor or cancer mass.

Evil Influences - pathogenic factors that can be either physical, mental, emotional, energetic or spiritual.

Evil Qi (Xie Qi) - also called Pathogenic Qi, Perverse Qi, Toxic Qi, and Heteropathic Qi, is energy that causes disease or harmful effects to the body.

Evil States - a condition wherein the patient experiences mental delusions, obsessions, infatuations with the doctor, spiritual oppression or possession.

Evil Wind - toxic wind that invades the body, tissues or organs.

Excess - a condition relating to the over abundance of a particular substance. (e.g., Heat, Wind, Damp, Cold, etc.).

Exopathogenic - a disease or pathogen originating outside of the body.

Extended Fan Palm Technique - hand technique where the fingers separate like a Chinese fan, used for extending energy through the doctor's palm.

External Pathogenic Factors - an external invasion of Heat, Damp, Cold, Dryness, or Wind, or a combination thereof.

External Qi Therapy - a technique used in Medical Qigong therapy which pertains to Qi being emitted onto a patient.

Extraordinary Organs - also called Curious Organs, these six organs are shaped like Yang (Hollow) organs but store Yin Essence. The brain stores Marrow, the Marrow stores Kidney Jing, the bones store Marrow, the blood vessels store the Blood, the Gall Bladder stores the bile, and the uterus stores Kidney Jing, Blood, and Qi.

Extraordinary Vessels - secondary channels that flow in conjunction with the body's Twelve Primary Channels.

Extra Point - a point with a definite location, but not originating on the fourteen main channels.

F

False Cold - a feverish sensation followed by a feeling of cold all over the body.

False Self - pertaining to the dark emotional side of the self, i.e., the masks and defence mechanisms that serve to protect the individual from dealing with his or her issues.

False Yang - a clinical condition where an overabundance of Cold (Yin) transforms into Heat (Yang).

False Yin - a clinical condition where an overabundance of Heat (Yang) transforms into Cold (Yin).

Fascia - a fibrous membrane covering, supporting, and separating the muscles, as well as uniting the skin with the body's underlying tissues.

Febrile Diseases - any and all diseases which cause the body to produce a fever.

Feng Shui - the study of harmonizing the energetic flow of Wind and Water, and the healing art of adjusting the person's environment to create improvements in the person's health and life.

Fetal Education - regulating the mother's behavior to improve her child's physical, emotional, and mental health is called "fetal education" in Traditional Chinese Medicine, and is important in the development of the child's Prenatal Essence, Energy, and Spirit.

Fetal Leakage - after conception, if a small amount of bloody fluid discharges from a woman's vagina, it is known as Tai Lou or fetal leakage.

Fibroadenoma - a tumor with fibrous tissue, forming a dense covering.

Fire Element - one of the Five Elements, pertaining to the Heart, Small Intestine, Pericardium, and Triple Burners.

Fire Jing - energy that controls the development phase of the fetus's emotional and spiritual well-being during the fifth month of pregnancy.

Five Agents - the five energies that are linked to the moral qualities of a person's inner characteristics (the five virtues stored within the body's Wood, Fire, Earth, Metal and Water elements).

Five Elements - Wood, Fire, Earth, Metal and Water.

Five Element Animals - Green Dragon, Red Phoenix, White Tiger, Dark Blue Turtle, and Yellow Phoenix.

Five Elemental Constitutions - physical constitutions based upon the observation of the Five Elemental formations within the human body.

Five Element Organs - the organs related to the Five Elements, including: Wood - Liver and Gall Bladder, Fire - Heart and Small Intestine (also included are the Pericardium and Triple Burners), Earth - Spleen and Stomach, Metal - Lungs and Large Intestine, Water - Kidneys and Bladder.

Five Energetic Fields - pertaining to the body's five levels of energy, including: 1. External Wei Qi Fields, 2. Internal Ying Qi Field, 3. Sea of

Blood, 4. Sea of Marrow, 5. Center Core of Light (Taiji Pole).

Five Flavors - also called the Five Tastes, are sour, bitter, sweet, pungent, and salty.

Five Major Yang (Fu) Organs - also called the Five Bowels, they are the body's five hollow organs: Gall Bladder, Small Intestine, Stomach, Large Intestine, and Bladder.

Five Major Yin (Zang) Organs - are the body's five solid organs: Liver, Heart, Spleen, Lungs and Kidneys.

Five Orbs - pertaining to the 5 Yin internal organs (Liver, Heart, Spleen, Lungs and Kidneys), their complete organ system, and the surrounding areas that they influence.

Five Palms Hot - a condition in which the patient feels a hot sensation in the palms and soles of the feet, accompanied by heat and agitation of the chest and / or head area.

Five Passes - five important gates on the Governing Vessel located at the coccyx, Mingmen, Shendao, occiput and Baihui, where energy tends to stagnate.

Five Portals of the Earthly Yin Gate - pertaining to the five points at the bottom of the perineum through which the Qi of Earth enters into the body.

Five Portals of the Heavenly Yang Gate - pertaining to the five points at the top of the head through which the Qi of Heaven enters into the body.

Five Sense Organs - eyes, tongue, mouth, nose and ears.

Five Thunder Fingers Technique - hand manipulation technique wherein the fingers and thumb are rapidly extended from a closed soft fist, to strike with Qi for dispersing stagnations.

Five Thrusting Channels - see Thrusting Channels.

Five Tissues - tendons, blood vessels, muscles, skin and bones.

Five Zhi - in connection with the five mental aspects of the Mind, the Hun (Ethereal Soul), Po (Corporeal Soul), the Shen (Spirit), the Yi (Intellect), and the Zhi (willpower) are sometimes referred to as the Five Zhi.

Fixation - has the same result as regression, but the person becomes fixated at a particular stage of mental and emotional development.

Flat Palm Detection - an extended palm technique used for sensing and diagnosing.

Four Bigs - pertaining to severe excess of fever, sweating, thirst, and pulse.

Four Doors - the center of each palm and foot.

Four Winds - pertaining to the Energy of the four compass points. (North - back, South - front, West - right, and East - left.)

Fu Organs - Yang or hollow organs (Gall Bladder, Small Intestine, Stomach, Large Intestine, and Bladder). The Fu Organs operate primarily to relieve the Zang (Yin) Organs of toxic energies and wastes.

G

Gallow's Syndrome - laughing at a very painful experience instead of grieving or crying.

Gastritis - the inflammation of the stomach.

Gastroptosis - the downward displacement of the stomach.

Gate of Access - the passageway between life and death, believed to be related to the stars of the Big Dipper.

Gate of the Moon - the western energetic region, which the sun must pass through in order to create Autumn.

Gathering the Immortal's Water - pertaining to the energetic production of the saliva or Juice of Jade to create the Immortal Pill.

Gathering Qi - also called Respiratory Qi, Collection Qi, Chest Qi, Pectoral Qi, and Big Qi of the Chest. It is derived from the conversion of the purest and most potent forms of the body's Jing (particularly sexual fluids, hormones, and neurochemicals).

Ghosts (Gui) - disembodied spirits.

Ghost Points - points used for the treatment of emotional and spiritual disorders.

Gland - an organ that produces a hormone or other secretion.

Golden Gate in the East - the eastern energetic region, which the sun must pass through in order to create spring.

Gong - meaning skill or study.

Gout - sudden intense pain in a joint, usually the big toe or ankle, followed by swelling, inflammation and heat in the joint (in extreme casts alternating chills and fever are experienced).

Grandmother Element - pertaining to the Five Element Creative Cycle of Traditional Chinese Medical, the primary organ is considered the Mother and its previous organ is considered the Grandmother.

Grain Qi (Gu Qi) - Energy derived from food and drink.

Grounding - see Rooting.

Gua Sha Therapy - an external "surface" tissue scraping technique commonly used to clear Excess Heat from the body.

Guiding Qi - the technique of leading Qi.

Gu Qi - Energy derived from food and drink.

Gui - ghosts or spirits.

H

Hai - means sea.

Healing Tones - resonant sounds used to purge the body of pathogens.

Heart Fire - pertaining to the energy of the Heart, which is responsible for transforming the body's Energy into Spirit. This occurs in the chamber of the Heart's courtyard (the Yellow Court).

Heaven Qi - also known as Heavenly Qi, this energy pertains to the Heavens, the divine and the celestial influences.

Heavenly Stems - the ten energies of Heaven represented in the human body as the Yin and Yang aspects of the Five Elements or ten major internal organs.

Heavenly Transpersonal Point - pertaining to the body's energetic connection to the Heavens, located two to five feet above the head.

Hei Xia - dark brown or black vaginal discharge.

Hemiparalysis - paralysis on one side of the body

Hemiplegia - paralysis on only one side of the body.

Hemoptysis - the expectoration of Blood.

Hepatitis - inflammation of the Liver.

Hepatolithiasis - calculi or concretions in the Liver.

Hepatomegaly - enlargement of the Liver.

Hepatosplenomegaly - the enlargement of both the Spleen and Liver.

Herbal Therapy - one of the four branches of Traditional Chinese Medicine, which involves treating patients through the use of formulas created through teas, soups, tinctures, wines, oils, balms, liniments and pills to stimulate energy flow.

Herbalist - a doctor of Herbal Therapy.

Herpes Simplex I - an infectious disease caused by the herpes simplex virus. This disease is characterized by thin-walled vesicles that occur in the skin, usually at a site where the mucus membranes joins the skin.

Hexagram - a six line symbol representing the function and flow of Yin and Yang energy, formed by stacking two trigrams on top of each other.

Hibernation Breathing - a breathing method which includes inhaling and exhaling through every pore on the body's surface, from the body's Center Core (Taiji Pole).

Hidden Power (An Jing) - techniques that emphasize stretching and twisting the tendons and ligaments (known as Reeling and Pulling the Silk) to cultivate resonant vibration within the body for striking and issuing power.

Hollow Organs - the body's Yang organs, which consist of the Gall Bladder, Small Intestine, Stomach, Large Intestine, Bladder. Also included in this list are the Triple Burners.

Hologram - pertaining to the body's energetic three dimensional image.

Hook-Up - see divine Hook-Up.

Hostile Forces - dark spiritual forces which seek to influence the physical, mental, emotional, energetic and spiritual life of an individual.

Hot Constitution - pertaining to a physical body innately prone towards heat.

Hot Evil - also known as Evil Heat, a pathogenic condition causing Excess patterns that are Hot and Yang in nature.

Hou Tian Zhi Qi (Postnatal Qi) - translates to mean after the baby sees the Heavens.

Hua Jing - see Mysterious Power

Huang - any membranous tissue.

Hua Sound Resonation - Mysterious or Spiritual Sound Resonation.

Huang Dai - yellow vaginal discharge.

Hui Yin Point (CV-1) - Conception Vessel point located between the scrotum and the anal sphincter.

Human Force - the energy or force manifesting from inside of the human body, as well as the within the human energetic field.

Hun (Ethereal Soul) - the Three Ethereal Souls which are the spiritual part of man that ascends to Heaven upon the death of the body.

Hunter Killer Cells - the body's neutrophils and macrophages, as well as the interferons and antibodies.

Hun Yuan - the body's internal energies that has been combined and fused into the Lower Dantian area.

Hyperbilirubinemia - excessive amounts of bilirubin (the orange-colored or yellowish pigment in bile) in the Blood.

Hyperhidrosis - excessive sweating due to an over-activity of the sweat glands.

Hypertension - high blood pressure.

Hyperthyroidism - a condition caused by excessive secretions of the thyroid glands, resulting in an increased metabolic rate and the consumption of food to support this increased metabolic activity.

Hypertrophy - the increase in the size of an organ or structure that does not involve tumor formation.

Hypochondriac Pain - pain in the upper lateral region on each side of the body below the thorax and beneath the ribs.

Hyposmia - a deficient sense to smell.

Hypotension - low blood pressure.

I

I-Ching - see Yi-Jing

Id - Dr. Sigmund Freud's terminology for one of the three divisions of the psyche in Psychoanalytic Theory that is the unconscious source of psychic energy responsible for the body's drives and instincts.

Immortal's Pill - pertaining to the energetic production of Heaven and Earth Qi, in conjunction with the saliva.

Immortal's Water - when meditating, another word for energized saliva.

Incontinence - an inability to control urination, involuntary urination when coughing, laughing, sneezing, running, or performing some other physical activity. This condition can also refer to involuntary defecation.

Infatuations - refers to the patient feeling intensely amorous towards the doctor.

Influenza - an acute contagious respiratory infection, characterized by a sudden onset, with chills, fever and headache.

Inner-vision - the skill of observing images of the internal organs, and energetic fields relating to the body, mind, emotion and spirit, and their transition stages.

Insight Meditation - focusing on sensual stimuli (sounds, smells, colors, etc.) while meditating.

Insomnia - a sleeping disorder.

Insulting Cycle - pertaining to the Five Elemental Cycle, wherein the Child Element counter attacks the Grandmother Element.

Intellectualization - an elaborate rationalization of a naked impulse, to justify it.

Interferons - a group of proteins released by the white blood cells and fibroblasts, responsible for fighting infection.

Interjection - the insertion or interpose the energetic pattern.

Internal Dialogues - internal conversations, which are part of the patient's personal belief structure.

Internal Pathogenic Factors - pertaining to diseases originating from the body's internal organs and emotions (e.g., anger, fear, grief, worry, etc.).

Internal Viewing - technique used by the Qigong doctor to view the patient's internal organs.

Interpersonal Relationships - close personal relationships, relating to self and others.

Invading Cycle - pertaining to the Five Elemental Cycle, wherein the Grandmother Element overcontrols the Child Element.

Invisible Needle Therapy - the insertion of invisible energetic needles into the patient's body to stimulate energy flow.

Invisible Needle Palm Technique - Qi emission in which energy is emitted in a very fine line, to stimulate specific channel points.

J

Jaundice - a condition due to deposition of the bile, characterized by the yellowing of the skin, eyes, mucous membranes and Body Fluids.

Jia Ji Guan (Spinal Pass) - two points located on the lateral sides of the Mingmen (GV-4) where Qi can become stagnant.

Jie Gu Therapy - a tissue manipulation therapy that focuses on the adjustment of bones and ligaments.

Jin - thin Body Fluids.

Jing - the human body's Essence, divided into Prenatal and Postnatal Essence.

Jing Luo - the body's channels and collaterals.

Jing Point Therapy - the original term for Channel Point Therapy or Acupressure.

Jing Shen Bing - pertains to all types of mental illness.

Jiu Wei (Yellow Court) - located in the center of the diaphragm, below the xiphoid process of the sternum. Its function is that of being the access point to release emotional memories from the body's internal organs. Its location is also attributed to the 3rd Chakra.

Jue Yin (Reverting Yin) - associated with the most severe diseases, indicates Yin Qi developing its final stage and then reverting into Yang.

Juice of Jade - Energized saliva produced in meditation practices.

K

Karma - the manifestation of consequences to our actions and beliefs: "As you sew, so shall you reap."

Karmic Related Illness - pertaining to spiritual illnesses, which can be either congenital or acquired.

Ketheric Matter or Substance - pertaining to the spiritual energy located within the third external field of Wei Qi.

Kidney Fire (Mingmen Fire) - the energy that heats the body's Essence (Jing), and dominates all Twelve Primary Channels. It is the motivating force of the body.

Kinetic Communication - the intuition of the physical body, felt by the Qigong doctor as a movement in or of his or her own body.

Kneading Tiger Palm Technique - hand manipulation technique resembling the movement of a tiger kneading the ground, used for dispersing Qi stagnations.

Kyphotic - the exaggeration or angulation of the normal posterior curve of the spine (humpback).

L

Laogong - channel point located at the center of each palm.

Large Heaven Cycle (Macrocosmic Orbit) - Qigong Meditation which connects the Qi of the extremities to the Qi within the Governing and Conception Vessels.

Leading Qi - technique of manipulating the patient's Qi by using a guiding gesture with the hands.

Leukocyte - the body's white blood corpuscles, which included lymphocytes and other immune system cells.

Leukorrhea - an acute or chronic disease caused by the unregulated clonal proliferation of stem cells within the Blood forming tissues.

Ley Lines - the energetic pathways that connect energy spots on the planet.

Life Force Energy - Qi.

Light Energy Therapy - color, light projection and visualization used for healing.

Light of the Dao - divine healing light energy.

Lipid Bilayers - the outer membrane of most cells, includes two layers of lipid molecules.

Lithotripsy - crushing of a calculus in the bladder or urethra.

Liver Wind - terminology used to describe excess Heat generated from a toxic Liver condition which can cause pathogenic symptoms.

Lobular - composed of small lobes.

Lords of the Three Dantians - three spiritual energies used to describe the energetic aspects of the human soul (Tai Yi, Si Ming and Xia Tao Kang).

Lo Scroll (Magic Square) - a tool used for diagnosis and treatment of disorders through number configurations, which correspond to the Late-Heaven sequence of the Trigrams of the Yi-Jing (I-Ching).

Lower Burner - area of the body in the Lower Dantian, responsible for the separation of Clean and Dirty Fluids. It also facilitates the production of urine.

Lower Dantian - area in the center of the lower abdomen, attributed to the body's chamber of heat and physical power. The Lower Dantian is also known as the Sea of Energy, Pill of Immortality, Root of life, Source of Generating Qi, Five Qi Collection Seat, Progenitor of Life, Stove of Spirit, Root of Heaven, and Cinnabar Field.

Lower Unconsciousness - pertaining to the acquired mind which is connected to the primal senses.

Lumbago - dull, aching pain in the lumbar region of the lower back.

Luo - translated to mean a net or web, and in Traditional Chinese Medicine it refers to the Connecting Vessels, i.e., the Fifteen Collaterals. These vessels are the major "passage ways" for the circulation of the body's channel energy, emerging out of the Luo (pathway) points on the Twelve Primary Channels (plus the Governing and Conception Vessels).

Luo Points - are the major intersecting points of the Fifteen Collaterals. The Luo points are located below the elbows and knees and provide an additional energetic barrier to keep Evil Winds from affecting the Twelve Primary Channels, being somewhat deeper then the Muscle/Tendon Channels.

Lymphocytes - immune cells present in the Blood and lymphatic tissue.

Lymphoma - a group of malignant solid tumors of the lymphoid tissue.

Lymphosarcoma - a sarcoma of the lymphatic system.

M

Macrocosmic Orbit - Qigong Meditation which connects the Qi of the Governing and Conception Vessels with the extremities of the body.

Macrophages - the major phagocytic cells of the immune system (also known as Hunter Killer Cells).

Magic Square - also known as the Lo Scroll, a tool used for diagnosis and treatment of disorders through number configurations corresponding to the Late-Heaven sequence of the trigrams of the Yi-Jing (I-Ching).

Magnetic Energy Therapy - magnetic energy affecting the body's channels and points via electromagnetic field stimulation.

Malar Flushes - pertaining to flushed skin along the cheeks.

Malignant - detrimental; growing worse; threatening to produce death.

Man Qi - general term used to describe the energy relating to the body, mind, emotion, energy and spirit of both men and women. In the body, the area between the navel and the lower sternum correspond to "Man."

Manic Depressive Personality Disorder - see Bipolar Personality Disorder

Mantra - a Sanskrit word, meaning a spiritual phase or sound repeated internally or externally, used as a tool in meditation to induce an altered state of consciousness.

Marrow - derived from the Kidneys, nourishes the brain, spinal cord and forms the bone marrow.

Master Point - the main point of energy interaction on a specific channel, used to affect another organ system or channel energy flow.

Mastitis - inflammation of the breast.

Medical Qigong - one of the four branches of Traditional Chinese Medicine.

Menorrhagia - excessive bleeding during the time of menstruation.

Menoxenia - the pathological changes of menstruation occurring in a woman's cycle, affecting the color, quantity and quality of Blood flow.

Mental Delusions - the occurrence of mental derangement in the patient resulting from a false belief based on an incorrect inference regarding external reality. This belief is firmly sustained despite incontrovertible evidence to the contrary.

Meridians - the body's channels or rivers of Energy.

Message (Xin Xi) - knowledge stored within the Wuji or the Void.

Metal Element - one of the Five Elements, relating to the Lungs and Large Intestine.

Metal Jing - Energy that supervises the development phase of the fetus's ability for emotional attachment and bonding during the sixth month of pregnancy.

Metrorrhagia - bleeding from the uterus.

Microcosmic Orbit - energetic orbits that circulate the Qi within the body's energetic channels; divided into Fire, Water and Wind pathways.

Micturition - discharging urine.

Middle Burner - area of the body pertaining to the body's digestive system, responsible for transporting Gu Qi (derived from food and drink).

Middle Dantian - area in the center of the chest, attributed to the body's chamber of emotional and vibrational power. The Qi of the Middle Dantian is called Zong Qi. Zong Qi is translated as Gathering Qi, Ancestral Qi, Genetic Qi, or Essential Qi. The Middle Dantian is also known as Middle Field of Elixir, Scarlet Palace, Central Altar, Middle Sea of Energy, Courtyard of the Heart, Opening of Suspended Gold, and the Seat of Emotion.

Middle Emotional/Mental Barrier - the second and middle energetic barrier of the Wei Qi fields.

Mind Regulation - the principles governing the conduct, action or functions of the mind.

Ming Jing - see Obvious Power.

Mingmen (Gate Of Life) - area responsible for heating the body, in particular the Kidneys and Lower Dantian.

Mingmen Fire (also known as Kidney Fire, Advisor Fire, or Ministerial Fire,) - the Energy that heats the body's Essence (Jing), and dominates all Twelve Primary Channels. It is the motivating force of the body.

Ming Sound Resonation - Obvious or Audible Sound Resonation.

Ministerial Fire - pertaining to the Energy responsible for heating the Middle Burner.

Moon Cream - energy gathered during meditation from the moon's Essence in the form of cool light.

Morphogenic Field - pertaining to the form of the energetic field of Jing.

Mother and Child Therapy - the Traditional Chinese Medical description of the primary organ (Mother) and its sequential organ (Child) in the Five Elemental Creative Cycle.

Mother Element - pertaining to the Five Element Creative Cycle, the primary organ is considered the "mother."

Moxa Therapy - herb heated and applied in a clinical setting for tonification.

Multiple Personality Disorder - also called Identity Disorder, is a mental state in which the patient develops "alter" personalities as a coping mechanism in dealing with severe emotional traumas.

Multiple-Sclerosis (MS) - an inflammatory disease of the central nervous system in which infiltrating lymphocytes degrade the myelin sheath of nerves.

Muscle/Tendon Channels - channel connections to the body's muscles, tendons, ligaments and other connective tissues.

Myalgic Encephalomyelitis - acute inflammation of the brain and spinal cord.

Myocarditis - the inflammation of the cardiac muscle (located in the middle layer of the walls of the heart).

Myoma - a uterine tumor that is a solid benign growth in the myometrium, often called a fibroid, containing muscle tissue.

Myophagism - a condition where the macrophages destroy (eats) muscular tissue.

Mysterious Pass - the space between Yin and Yang where infinite space and time (Wuji) exists.

Mysterious Power (Hua Jing) - techniques which emphasize training and conditioning the mind's imagination and intention, to project and utilize the power of the individual's Shen (Spirit).

N

Necrosis - part of an area of tissues or bone that is dying or dead and may spread to healthy tissues or bones.

Nei Dan Shu - internal elixir cultivation, that focuses on cultivating Qi from within the individual's body.

Nei Gong (Internal Skill) - the training of the body's tendons, bone, breath, mind, emotion, and spirit to facilitate internal power.

Nei Guan (Internal Viewing) - see inner vision.

Nei Jing - the Yellow Emperor's classics on Chinese internal medicine.

Neoplasm - a new or abnormal formation of tissue, as in a tumor growth.

Nephritis - inflammation of the Kidneys.

Neurasthenia - unexplained chronic fatigue and lassitude.

Neutrophils - the most common type of granulocytic white blood cell, responsible for fighting infection.

Nine Dantian Chambers - the nine internal cavities established within the energetic matrix of each Dantian.

Nine Palaces - the Later-Heaven sequence of the Trigrams of the Yi-Jing (I-Ching), represented in the human body as the Eight Extraordinary Vessels and the Taiji Pole.

Nine Star System - pertaining to the total development of the three periods of life and the three star developmental sequence.

Noxious Qi (Turbid Qi) - coarse, Toxic, Evil, unrefined, polluted, or dirty Energy.

O

Objective World - pertaining to the spiritual world existing outside an individual's thoughts or feelings.

Obstructed Qi - Energy that is immobile.

Obstruction - the inhibition of the flow of Qi or Blood, caused by Cold, Damp, Heat and Wind, etc.

Obvious Power (Ming Jing) - techniques that emphasize the training and conditioning of the muscles, strengthening the bone structure, and increasing the individual's overall stamina. This school also includes such techniques as pounding the body (arms, hands, legs, and torso) to strengthen and toughen the tissues.

Occipital Pass (Yu Zhen Guan) - the area located just inferior to the occipital bone where the brain originates (according to energetic embryology), known as a specific point where Qi often stagnates.

Oliguria - diminished amount of urine formation.

Omniscient Sight - the ability to see 360 degrees simultaneously.

One Finger Skill Technique - clinical modality involving Energy extension employed through a single finger.

Ontology - the study of the historical development of an individual.

Opening and Closing - the method of leading Qi into and out of specific internal organs, the Triple Burners areas, or one of the Three Dantians, via the hands.

Opisthotonosis - a form of spasm in which the patient's head and heels are bent backwards, and the body is bowed forward.

Organ Dysfunction - the impaired or abnormal function of an internal organ.

Organ Regulation - technique for balancing the action or functional principles of the internal organs.

Organ Qi - Energy of the body's Yin and Yang organs.

Original Spirit (Yuan Shen)- see Prenatal Spirit

Original Qi (Yuan Qi) - pertaining to the body's Prenatal Qi acquired from both parents at conception, and from the mother during gestation.

Original Force - pertaining to the Heavenly energy, manifesting as the energy of the entire cosmos.

Original Yang - pertaining to the body's Prenatal Kidney Yang.

Original Yin - pertaining to the body's Prenatal Kidney Yin.

Osteoarthritis - a chronic disease involving the joints and the deterioration of the articular cartilage.

Osteoporosis - a general term used for describing any disease process that results in the reduction of bone mass.

Osteosarcoma - a sarcoma of the bones.

Outer Spiritual Barrier - the third and furthermost energetic barrier of the Wei Qi fields.

Overcontrolling Cycle - pertaining to one of the Five Elemental Cycles, where one organ overcontrols the second elemental organ in the Five Elements' Circle.

P

Palace of Eternal Frost - the northern energetic region, which the sun must pass through in order to create winter.

Palace of Universal Yang - the southern energetic region, which the sun must pass through in order to create summer.

Palpitations - an abnormal rapid, throbbing, or fluttering of the Heart.

Pancreatitis - inflammation of the pancreas.

Panic Attack - overwhelming panic and sense of impending doom, resulting in hyperventilation (breathlessness), heart palpitations and visual distortions.

Papillary Masses - small, nipple-like protuberances or elevated tissue masses.

Paraplegia - paralysis on both sides of the body.

Parenchymal Cells - the essential parts of an organ's cells that are concerned with the organ's function.

Parkinson's Disease - a chronic nervous disease characterized by muscular weakness, rigidity and a fine, slow tremor.

Past Life Regression - pertaining to the patient's exploration and experiences of previous lives.

Pathogenic - disease-causing; see Internal Pathogenic Factors and External Pathogenic Factors.

Penetrating Wind - pertaining to the external pathogen of Wind invading the tissues.

Peribronchial - surrounding the windpipe (bronchus).

Perineural Cells - the sheath of cells around a bundle of nerve fibers within the perineurium.

Peristalsis - a progressive wave like movement that occurs involuntarily in the hollow tubes of the body.

Peritonitis - inflammation of the abdominal cavity.

Pernicious Influences - pertaining to the Six External Factors that cause disease.

Personal Subconscious Mind - part of the mind associated with the recording and storing of personal interpretations of reality.

Peyer's Patch - an aggregation of lympth nodes found chiefly in the ilium.

Phagocytes - cells that have the ability to destroy and ingest bacteria, protozoa, unhealthy cells and cell debris.

Phantom Embryo - an energetic thought form in the shape of an embryo created through the woman's feelings of grief, guilt or remorse after a surgical abortion.

Phantom Organ - the energy of a particular organ which still exists, even after surgical removal.

Phantom Pain - the feeling of pain relating to a particular organ which still energetically exists, even after surgical removal.

Phlegm - pathogenic factor responsible for the formation of diseases including tumors.

Physical Barrier - the first level and closest to the body of the three Wei Qi energetic barriers.

Piezoelectric - pertaining to the electricity created from pressure, especially pressure on or within the bones.

Po (Seven Corporeal Souls) - sometimes called the Seven Turbid Demon Natures, this spiritual energy manifests as the physical or material soul of the human body that returns to the Earth at death.

Points - specific areas on the body where energy can intersect to travel externally to internally, or visa versa.

Point Respiration - exercise which requires breathing into a specific channel point, organ, or area of the body.

Polarity - opposite negative and positive qualities of power.

Polergeists - malevolent spiritual entities. Parapsychology research indicates that poltergeist activity is often the manifestation of a psychokinetic ability.

Polydipsia - excessive thirst.

Polyphagia - eating abnormally large amounts of food at a meal.

Polyuria - the excessive secretion and discharge of urine.

Portal Hypertension - the increased pressure in the portal vein resulting from an obstruction of the Blood flow through the Liver.

Postnatal Energy (Postheaven Qi) - sometimes called the Acquired Qi, it is the Energy acquired after birth from food, drink, and air.

Postnatal Essence (Postheaven Jing) - sometimes called the Acquired Essence, it is the Essence acquired after birth from food, air and drink.

Postnatal Spirit (Zhi Shen) - also called the body's Mental Spirit, Acquired Spirit, and Conscious Spirit. This spiritual essence is acquired after birth through the refinement of one's Qi.

Post Traumatic Stress Disorder - characterized by the reexperiencing of an extremely traumatic event or events, accompanied by symptoms of increased arousal, and by avoidance of stimuli associated with the traumas. This includes the general numbing of the patient's emotional responsiveness.

Prenatal Energy (Yuan Qi) - sometimes referred to as Congenital Qi, Pre-Heaven Qi, Inherited Qi, Source Qi, Ancestral Qi, Primordial Qi, Genuine Qi, and Kidney Qi. It is Energy existing before the fetus is born, acquired from the mother's, father's, environmental and universal energies, and sustained through prayer, meditation and sleep.

Prenatal Essence (Yuan Jing)- also called Preheavenly Essence, Original Essence, Inherited Essence, Congenital Essence, Primordial Essence, and Ancestral Essence. It is the Original Essence existing before the fetus is born, acquired from the mother and father.

Prenatal Spirit (Yuan Shen) - also called the Intuitive Spirit, Perceptual Spirit, Primordial Spirit, Congenital Spirit, and the Original Subconscious. It is the Spirit essence existing before the fetus is born, acquired from fusing the mother's, father's, environmental and universal energies. The Prenatal Spirit also relates to the individual's ability to perceive and intuit information.

Prescriptions - directions given to the patient with regard to the manner of Medical Qigong exercises and meditations that must be practise after the initial Medical Qigong treatment.

Primal Senses - pertaining to the gross physical, animalistic survival senses (seeing, hearing, feeling, smelling, etc.).

Primary Channels - the body's twelve main channels, containing six Yin and six Yang rivers of Energy.

Primary Posture - the main posture, in a series of Medical Qigong prescriptions, that the patient focuses on.

Primitive Unconsciousness (Lower Unconsciousness) - pertaining to the acquired mind and related to the primal senses.

Projection - the attribution of unacceptable impulses within oneself to other people.

Proliferative Arthritis - the rapid reproduction and growth of arthritis.

Prostatitis - the inflammation of the prostate.

Protective Qi (Wei Qi) - the body's external field of defensive, protective energy (divided into three external fields of Qi).

Pruritus - severe itching.

Psychogenic - a condition developed from the beliefs originating within the mind.

Psychogenic Polyuria - pertaining to the belief that one must frequently secrete and discharge urine.

Psychometry - the act of sensing the thoughts, images and so on, with which the object has been imprinted.

Psychoneurosis - emotional disfunction caused from unresolved unconscious conflicts.

Psychosexual Qi Deviation - a condition resulting from an immediate energetic tissue overstimulation of the sexual organs. Patients with this condition experience intense sexual undulations and orgasms when being treated in a safe clinical environment.

Psychosomatic - pertaining to the relationship between the physical tissues and the emotions.

Pulling Down the Heavens - an opening and closing meditation used to energize and clear the body from the top of the head to the bottom of the feet, with breath, mind and hand movements.

Pulmonary Emphysema - a chronic disease of the lungs characterized by a destructive increase in the normal size of air spaces distal to the terminal bronchiole.

Purpura - a condition characterized by hemorrhages of the internal organs, skin, mucous membranes and other tissues, with various manifestations and diverse causes.

Purgation (Purging) - technique used in order to reduce Excess and expel pathogenic Evils located within the energetic fields and tissues of the body.

Pyelonephritis - the inflammation of the Kidneys and pelvis.

Q

Qi - is the energetic medium existing between matter and spirit (also known as Life Force Energy, when pertaining to the physical body).

Qi Collapse - pertaining to the complete absence (void) of either Yin or Yang Qi.

Qi Compression - using the Qi to press the tissues.

Qi Deviations - an alteration of energetic patterns and flow of energy that affects the body, mind, emotion and spirit, resulting in disease.

Qi Dysfunction - the impaired or abnormal function of the body's energy.

Qi Extension - the emission of energy from the body.

Qigong - Energy Skill, pertaining to exercises that cultivate Life Force Energy. There are three primary schools of Qigong training - Martial, Medical and Spiritual.

Qigong Clinic - a facility for diagnosis and treatment of outpatients with Medical Qigong therapy.

Qigong Doctor - in China, a person who medically treats patients for mental or physical disorders using Qi.

Qigong Massage - soft tissue regulation wherein the Doctor's hand lightly skims the patient's body. This gentle surface tissue stimulation is used to energize, stimulate or dredge the patient's Wei Qi fields. It is used with purging and tonifying techniques.

Qigong Therapy - one of the four branches of Traditional Chinese Medicine, which involves treating patients through the use of Energetic Point Therapy, Qigong Massage, Distance Therapy, Self-Regulation Therapy, and Invisible Needle Therapy, to stimulate energy flow.

Qigong Therapist - in America, a person who medically treats patients for mental or physical disorders using Qi.

Qi Hai - Sea of Qi point (CV-6).

Qi Manipulations - techniques used to treat or influence the flow of energy in the body.

Qing Dai - green-blue vaginal discharge.

Qi Projection (Qi Extension) - the emission of energy from the body.

Qi Regulation - energetically balancing the action or functions of the body's Yin and Yang energies.

Qi Stasis - the total stagnation of energy.

Quiescent - a meditative state wherein the individual's mind and body becomes quiet and peaceful.

R

Rachialgia - spinal inflammation.

Reaction-Formation - the conversion of one feeling into its opposite, typically seen in love turning into hate.

Rebellious Qi - energy that does not follow the correct flow or current, acting recklessly.

Reconstructive Qi Therapy - pertaining to the reconstruction and energizing of the body's energetic fields and organ systems (especially after surgery).

Reducing Qi - to lessen or decrease an organ or channel's energy.

Reflexology - the skill of pressing specific areas of the body's hands and feet to initiate internal energetic movement.

Regression - the return to an earlier childhood stage of behavior to reduce the demands on the ego.

Regulating - pertaining to the balancing of the body's Yin and Yang Energies.

Reinforcing Qi - to strengthen and support the body's organ or channel Energy.

Repression - the pushing down of unwanted ideas and emotions into the unconscious.

Respiratory Qi - Energy of the chest.

Restrictive Cycle - pertaining to the Five Elemental Controlling Cycle, where one organ restricts the energy of another organ (as depicted in the pentagram drawing).

Retrobulbar Neuritis - inflammation of the nerves behind the eyeball.

Returning To The Origin - see Rooting the Lower Dantian.

Reverse Breathing - opposite of abdominal breathing, wherein the patient will contract the abdomen with the inhalation, and expand the abdomen with the exhalation.

Rhabdomyosarcoma - a sarcoma of the muscles.

Rheumatic - pertaining to an rheumatism (a general term used to describe an acute or chronic condition characterized by inflammation, soreness and stiffness of the muscles, and pain in the joints and associated structures.

Rheumatoid Arthritis - a form of arthritis, characterized by inflammation of the joints, swelling, stiffness, cartilaginous hypertrophy, and pain.

Rheumatoid Spondylitis - a chronic, progressive disease, characterized by inflammation of the joints between the articular processes, costovertebral joints, and sacroiliac joints.

Rheumatosis - an acute or chronic condition characterized by inflammation, soreness and stiffness of the muscles, and pain in the joints.

Rhinitis - the inflammation of the nasal mucosa.

Righteous Qi (Zheng Qi) - is also called Upright Qi and Correct Qi. It is energy that heals the body and fights diseases.

Rigor - a sudden, chill with high temperature, followed by heat and profuse perspiration. Can also be referred to a state of hardness and stiffness, as in the muscles.

Root - the original cause of a disease; or to energetically secure into the Earth by extending the body's Energy deep into the ground, as if growing tree roots.

Rooting - the process of extending the body's Qi into the Earth to either establish a solid energetic foundation, or if need be, disperse Toxic Qi.

Rooting the Lower Dantian (Returning to the Origin) - returning the body's collected Qi back into the Lower Dantian.

S

San Bao (Three Treasures of Man) - pertaining to Jing (Essence), Qi (Energy) and Shen (Spirit).

San Jiao (Triple Burners) - corresponding to three main body cavities, responsible for heating the body and transporting the Body Fluids.

Sarcoma - a malignant growth, or tumor, that occurs within the connective or mesenchymal tissue. It may affect the muscles, bones, fat, blood vessels, lymph system, Kidneys, Bladder, Liver, Lungs, Spleen, and/or parotid glands.

Schizophrenia - a mental disorder, that induces hallucinations - usually auditory - through can also be visual, accompanied by very disordered thinking, delusions, disorganized speech, irrational or catatonic behavior, such as stupor, rigidity, or flaccid movement of the limbs. The ability to interact with others is greatly impaired.

Sclera - a tough white fibrous tissue that covers the white of the eyes.

Sea of Blood (Sea of the Twelve Channels) - pertaining to the Energy located in the Thrusting Vessel.

Sea of Energy - Energy located in the Lower Dantian, or Qi Hai area.

Sea of Grain and Water (Sea of Nourishment) - pertaining to the Energy located in the Stomach.

Sea of Marrow - pertaining to the Energy flowing in the spinal column and brain, originating from the Kidneys.

Sea of Qi - the chest center. Some Medical Qigong schools maintain that there are two reservoirs of Qi: the Middle Dantian, being the Sea of Postnatal Qi, and the Lower Dantian, being the Sea of Prenatal Qi (which is regulated by the Qihai CV-6 point).

Sea of Yang Channels - pertaining to the Governing Vessel.

Sea of Yin Channels - pertaining to the Conception Vessel.

Self Regulation Therapy - pertaining to the patient's Qigong prescriptions (meditations and/or exercises).

Seven Emotions - see Seven Internal Factors.

Seven Essential Stars - the Sun, Moon, Mars, Venus, Mercury, Saturn and Jupiter, associated with the body's seven orifices.

Seven Internal Factors - pertaining to the seven emotional pathogenic factors that cause disease, when in an Excess condition (Joy, Sorrow, Worry, Grief, Fear, Fright, and Anger).

Seven Material Souls - pertaining to the seven Earthly spirits that reside in the body as the Po.

Seven Orifices - ears, eyes, nostrils, mouth, anus and urethra, which are considered the gates and windows of Essence, Energy and Spirit.

Seven Turbid Demon Natures - see Po.

Shaman - an ancient Tungus term meaning "between the worlds." A Shaman is a tribal priest or priestess who heals the physical, mental, emotional, energetic and spiritual aspects of the patient.

Shao Yang - Small Yang, also called Lesser Yang, Minor Yang, or Young Yang, is affiliated with the sunrise and the waxing-moon phase. Modern physicists associate the Lesser Yang with a light force and electromagnetism.

Shao Yin - Small Yin, also called Lesser Yin, Minor Yin, or Young Yin, is affiliated with the sunset and the waning-moon phase. Modern physicists associate the Lesser Yin with a heavy force, and gravity.

Shen - meaning Spirit; when speaking about physical development, it is derived from Qi, and can be divided into both Prenatal and Postnatal Shen.

Shen Deviations - mental and emotional disorders which have caused the Three Ethereal Souls (Hun) to leave the patient's body.

Shengong - training of the spirit through meditation and visualization.

Shening Out - terminology used to describe the Ethereal Soul (Hun) wandering away from the body.

Shi Qi (Turbid Qi) - also known as Evil Qi, Toxic Qi, and Pathogenic Qi, it is coarse, unrefined, polluted or dirty energy.

Sishencong (Four Alert Spirit) Points - four points at the top of the head (that surround the Baihui Point) used to absorb Heavenly Qi into the body.

Shou Zhen (Hand Diagnosis) - a form of diagnosis, wherein, the doctor assess the "energetic blueprint" of the patient's body transformed onto the doctor's left hand.

Shu Points - five specific points below the elbows and knees identified as the Well, Spring, Stream, River and Sea points. Each point has an affect on the quantity of the energy of an organ.

Sishencong (Four Spirit Hearings) Points - a group of four points located at the top of the head (surrounding the Baihui point), used for absorbing Heavenly Qi into the body's Taiji Pole.

Six External Factors - also known as the Six Pernicious Influences, these factors pertain to the six climatic changes (Wind, Summer Heat, Heat, Damp, Dryness, Cold, and Fire).

Six Storage Areas- body's Yang organs constantly fill and empty, and include the Bladder, Gall Bladder, Stomach, Large Intestine, Small Intestine, and Triple Burners.

Skin Zones - twelve dermal-zones, based upon the surface location of the body's Twelve Primary Channels.

Soaring Dragon Technique - hand technique for Qi emission, where the energy is emitted through the middle finger bent and pointing downward, while the other fingers are extended straight outwards.

Solid Organs - the body's Yin organs, which include the Liver, Heart, Spleen, Lungs, and Kidneys (also included in this list is the Pericardium).

Soul - immaterial Spiritual Essence of an individual's life, stored within the Heart and Middle Dantian.

Soul Body- see Astral Body.

Soul Extensions - the Shen develops and contains Twelve Soul Extensions. These Twelve Soul Extensions contain the body's different personality characteristics.

Soul Loss - the loss of parts of the Eternal Soul.

Soul Retrieval - to spiritually search for and bring back one's forgotten memories (soul), which have been isolated from consciousness due to trauma and shock.

Soul Travel - see Astral Travel.

Sound Energy Therapy - sound projected as audible and inaudible tone resonation, used for healing.

Sound Resonation - healing tones used for tonifying or dispersing the patient's Energy.

Spider Nevus - a branched growth of dilated capillaries on the skin, that resemble a spider.

Spinal Pass (Jia Ji Guan) - two points located on the lateral sides of the Mingmen (GV-4), where energy has a potential to stagnate.

Spinous Process - the single midline posterior projection arising at the junction of each vertebra.

Spiraling Energy Technique - hand manipulation, that extends and spirals the doctor's projected energy.

Spirit - the energetic manifestation of the Eternal Soul.

Spirit Body - the energetic vehicle inwhich the body's Shen can travel throughout the Astral Plane. The Spirit Body can manifest through many forms (Body of Light, animal forms, etc.).

Spirit Demons - see Demon Possession and Oppression.

Spirit Soul - the Three Ethereal Souls, accompanied by the individual's consciousness, acting as one unit for spirit travel.

Spirit Travel - the spirit (Hun) journeying outside of the physical body.

Splenomegaly - the enlargement of the Spleen.

Squamous Metaplasia - the conversion of tissue into a form of scalelike cells, that is abnormal for that tissue.

Stacking the Bones - allowing the bones to stack upon each other from the bottom of the feet to the top of the head.

Stagnation - not moving, inactive; pertaining to Qi, Blood, or thought patterns.

Static Qigong - the process of stationary, quiescent Energy gathering.

Stroke (Wind Stroke) - caused by the buildup of Excess Liver Fire creating Internal Wind.

This Internal Wind causes Qi and Blood to rebel upwards causing Phlegm to form and obstruct the cavities and vessels, creating Penetrating Wind or Stroke.

Subarachnoid Hemorrhage - bleeding internally, within the spaces at the base of the brain, between the pia proper and arachnoid contain the cerebrospinal fluid.

Subconscious Mind - part of the mind associated with the recording and storing of personal interpretations of reality (not readily accessible to the conscious mind).

Sublimation - the channeling of unacceptable impulses into acceptable, refined social forms and is the only defence mechanism considered to be a healthy reaction.

Substances - pertaining to the body's essential parts of physical and energetic material.

Sui - Marrow.

Super Ego - Dr. Sigmund Freud's terminology for the division of the psyche in psychoanalytic theory, responsible for the psychic reward and punishment system.

Sun's Essence - energy gathered from the sun, ingested as warm light.

Sword Fingers Technique - hand manipulation that emits Qi through the extended index and middle fingers.

Symptoms - a subjective manifestation of a pathological condition, reported by the patient.

Syndromes - a grouping of signs and symptoms, based on their frequent reoccurrence, that may suggest a common underlying pathogenesis.

Systemic - affecting the entire body.

T

Taiji Pole - the Center Core of light which joins the body's three Dantians and the Eternal Soul together.

Tai Yang - Great Yang, also called Strong Yang, Major Yang, or Old Yang, is affiliated with high noon and the full-moon phase. Modern physicists associate the Strong Yang with a strong nuclear force.

Tai Yi - meaning Great Divinity or God.

Tai Yin - Great Yin, also called Strong Yin, Major Yin, or Old Yin, is affiliated with midnight and the new-moon phase. Modern physicists associate the Great Yin with a weak nuclear force.

Ten Heavenly Stems - the ten energies of Heaven that rule the changes of the Five Elemental seasonal transitions, and are represented in the human body as the Yin and Yang aspect of the Five Elements (represented in the human body as the ten major internal organs).

Ten Thousand Voices - pertaining to the state of open receptivity of the Qigong doctor's Heart, after rooting the mind.

Ten Wings - consisting of ten commentaries from Confucius and his disciples, pertaining to the study of the eight trigrams, sixty-four hexagrams, and the Yi-Jing.

Third Eye Point (Yin Tang) - located in the center of the forehead, responsible for spiritual intuition and communication.

Thought-forms - images of concentrated thought patterns that manifest on the vibrational resonance of the Astral Plane.

Three Ethereal Souls (Hun) - pertaining to the three heavenly spirits that reside in the body.

Three Fires - the heat in the body, generated from the energy radiating from the Heart Fire, Kidney Fire, and Bladder Fire.

Three Outer Forces - pertaining to the three natural powers of Heaven, Earth and Man.

Three Parts Wisdom - knowledge obtained through the doctor's connection and communication with his or her Upper, Middle, and Lower Dantians.

Three Periods of Life - the developmental stages of the patient's Jing, Qi and Shen divided into the womb, childhood and adulthood.

Three Stars - pertaining to the three periods of life, each period is divided into three stages of development, known as the three stars.

Three Treasures of Earth - pertaining to the energy of Soil, Water and Wind, and the study of Feng Shui (Wind and Water).

Three Treasures of Heaven - pertaining to the energy of the sun, moon and stars, and the study of Chinese astrology.

Three Treasures of Man - pertaining to the energetic interaction of the body's Essence, Energy and Spirit, and the study of the Yi-Jing (I-Ching or Book of Changes).

Three Wonders - Clinical manifestations of Qi, categorized as Subtle, Mysterious and Incredible Wonders.

Thrombosis - the formation and development or existence of a Blood clot (thrombus) within the walls of the vascular system.

Thrusting Channels - the Five Energy Channels which surround and penetrate the body's center core via the Taiji Pole.

Thrusting Vessels - also called the Chong Vessels, they are the Five Energy Vessels which originate from the center of the body and internally transverse the legs and torso.

Ti - referred to as the Divine Center.

Tian Qi (Heavenly Energy) - the transformed energy of the Yuan Qi and the divine.

Tian Shen (Heavenly Spirit) - the transformed energy of the Yuan Shen and the divine.

Tie Bi (Iron Wall) - the areas of the body where it is most difficult for the energy to pass through when circulating the Microcosmic Orbit.

Tinnitus - a ringing, tinkling, or buzzing sound in the ear.

Toe Raised Stepping - pertaining to energetic walking therapy, wherein the toes are stretched when stepping in order to facilitate the increase of Qi flowing into the body via the leg channels.

Tonification (Tonify) - to supplement the insufficiency and strengthen the body's resistance.

Traditional Chinese Medicine - Chinese Energetic Medicine, divided into four branches of healing modalities (Acupuncture, Herbal Therapy, Medical Qigong Therapy, and Tissue Regulation Therapy (Chinese Massage).

Transference - the process whereby a patient unconsciously transfers feelings, thoughts, beliefs and patterns of behavior that had been previously experienced with others onto the doctor.

Transient Ischemic Attacks (TIA) - temporary interference with the Blood supply to the brain.

Treatment - the medical care given to a specific condition.

Trigger Points (Ashi Points) - places on the body which are tender spots, or painful areas near diseased or injured tissue.

Trigram - pertains to three Yao lines stacked upon one another forming a specific symbol, which represents certain characteristics.

Triple Burners (San Jiao) - also known as the Triple Heaters and Triple Warmers, they correspond to three main body cavities (perineum to navel, navel to base of solar plexus, solar plexus to throat), and are responsible for heating the body and transporting Body Fluids.

True Fire - the original Heat or Fire Energy that regulates the body's Yin and Yang Qi, created from the radiating energy of the Heart's Fire, Kidneys' Fire and Bladder's Fire.

True Nature - one's innate nature in harmony with life.

True Qi - the energy that circulates in the body's channels and collaterals which nourishes the Yin and Yang organs and fights disease.

True Self - one's true nature, connected to the subconscious mind.

True Spirit - pertains to the spiritual nature of the True Self. The Hun and Po are expressions of the body's True Spirit.

Tsou Hou Ru Mo ("the Spirit leaves and the Demon enters") - describes self induced psychosis, pertaining to improper Qigong training, wherein the patient's Hun leave the body and the Po take over.

Tui Na Therapy - a tissue manipulation therapy that focuses on the adjustment and / or stimulation of the muscles and tendons.

Tumor - an abnormal growth, either benign or malignant, caused by a retention of mass due to the cultivation and stasis of Qi, Blood, Phlegm, etc.

Turbid Qi - also called Evil Qi, is coarse, unrefined, polluted, and dirty energy.

Twelve Pi Hexagrams - the twelve symbols pertaining to the twelve time periods of the day and year.

Twelve Primary Channels - the body's twelve main energetic rivers (Liver, Lungs, Large Intestine, Stomach, Spleen, Heart, Small Intestine, Bladder, Kidneys, Pericardium, Triple Burners, and Gall Bladder).

Twelve Earthly Branches - twelve energies of the Earth that determine the six Qi factors of the seasonal transitions (represented in the human body as the Twelve Primary Channels).

Two Breathings - pertaining to the abdominal breathing method of holding the breath.

U

Umbilications - a depression resembling a navel.

Universal Qi - energy pertaining to the Heavens, the divine and the celestial influences.

Upper Burner - pertaining to the body's complex system of Fluid distribution via the Lungs and located within the upper chest cavity.

Upper Dantian - area within the center of the head, attributed as the body's chamber of light and door to psychic and intuitive powers. The Upper Dantian is also known as Seal Palace, Ancestral Opening, Calm Fountain, Heaven's Valley, Inner Source, and Clay Pill Palace.

V

Vasculitis - the inflammation of a blood or lymph vessel.

Vertigo - the sensation of moving in space, resulting in such symptoms as dizziness and light-headedness.

Virtue (De) - pertaining to the function of the divine in man.

Virtue of Dao - pertaining to the commendable quality of the divine.

Viscera - the body's internal organs.

Void - also called Wuji, it pertains to the infinite space between matter and energy.

W

Wai Dan Shu - external elixir cultivation, that focuses on cultivating Qi from outside the individual's body.

Wai Qi - external, extended energy.

Walking Therapy - Postoral Dao Yin walking exercises and dynamic "moving" meditations used for the treatment of organ Deficiencies.

Wandering Bi - migrating pain within the body's cavities.

Waning - to grow smaller.

Water Element - one of the Five Elements, pertaining to Kidneys and Bladder.

Water Jing - energy that controls the genetic development phase of the fourth fetal month.

Waxing - to grow larger.

Wei Lu Guan (Coccyx Pass) - located on the lowest segment of the spine just posterior to the anus, near the Chang Qiang (GV-1) point.

Wei Qi - the body's external field of Defensive and Protective energy (divided into three fields of Qi).

Wen Huo - pertaining to the gentle breathing method of Respiratory Dao Yin training.

White Blood Cell - any of a group of Blood cells that have no hemoglobin and migrate into tissues to fight infection and digest cell debris.

Wind Bi - pain in the body created by toxic Wind invasion.

Wind Stroke - Stroke caused by the buildup of Excess Liver Fire creating Internal Wind. This Internal Wind causes Qi and Blood to rebel upwards causing Phlegm to form and obstruct the cavities and vessels, thus creating Penetrating Wind or Stroke.

Windy Breathing Method - pertaining to the method of breathing through the nose.

Wood Element - one of the Five Elements, pertaining to the Liver and Gall Bladder.

Wood Jing - energy that controls the development phase of the direction of the fetus's emotional and spiritual aspects during the seventh month of pregnancy.

Wu Guan (Five Passes) - five important gates on the Governing Vessel located at the coccyx, Mingmen, Shendao, occiput, and Baihui areas where energy tends to stagnate.

Wu Huo - pertaining to the vigorous breathing method of Respiratory Dao Yin training.

Wuji - pertaining to infinite space or the formless Void.

Wuji Posture - a quiet standing posture used in meditation to allow the practitioner to return to a state of tranquility.

Wu Jing Shen (Five Essence Spirits) - the spiritual energy radiating from the core of the Five Yin Organs. Combined, these energies create the foundation of the body's Shen (Spirit).

Wu Se Dai - pertaining to the five colors of vaginal discharge - white, yellow, red, green-blue, and dark brown or black.

Wu Wei - a state of "no mind," i.e., no thoughts.

Wu Zang - the Five Yin Organs. Wu translates to mean "five," Zang translates to mean "to store or hold."

X

Xie Qi (Evil Qi) - energy that causes disease or harmful effects to the body.

Xin Xi (The Message) - knowledge stored within the Wuji or the Void.

Xiphoid Process - the lowest part of the sternum bone (sometimes referred to as the Doves Tail).

Xue - Blood.

Y

Yang - the positive charged energetic polarity, opposite of its companion Yin, pertaining to man, hard, light, hot, etc.

Yang Channels - the body's Yang energetic rivers, consisting of the Governing Vessel, Belt Vessel, Yang Linking Vessels, Yang Heel Vessels, Large Intestine Channels, Triple Burner Channels, Small Intestine Channels, Stomach Channels, Gall Bladder Channels, and Bladder Channels.

Yang Fire - also called Emperor's Fire, energy of the Heart Fire.

Yang (Fu) Organs - also known as Hollow Organs, that consist of the Gall Bladder, Small Intestine, Stomach, Large Intestine, Bladder. Also included is this category are the Triple Burners.

Yang Shen Disturbances - an emotional Yang state of energetic dysfunction.

Yang Ming (Yang Brightness) - indicates Yang Qi developing its final stage and then reverting into Yin.

Yao - a solid or broken line which is representative of either Yang or Yin energy, used in combination of three as Trigrams or six as Hexagrams.

Yao Cycles - the progression of twelve hexagrams (six Yang and six Yin) flowing in a waxing and waning cycle.

Ye (humor) - thick, turbid Body Fluids.

Yellow Court - located in the center of the diaphragm, just below the xiphoid process of the sternum. Its function is that of being the access point to releasing the body's internal organ emotional memories. Its location is also attributed to the 3rd Chakra.

Yi - the intention or thought (the cognitive mind).

Yi Jing - Chinese "Book of Changes," pertaining to the natural transitions of life.

Yin - the negative charged energetic polarity, opposite of its companion Yang, pertaining to woman, soft, dark, cold, etc.

Yin Channels - Yin energetic rivers, consisting of the Conception Vessel, Thrusting Vessel, Yin Linking Vessels, Yin Heel Vessels, Lung Channels, Pericardium Channels, Heart Channels, Spleen Channels, Liver Channels, and Kidney Channels.

Yin (Zang) Organs - also known as the Solid Organs, that consist of the Liver, Heart, Spleen, Lungs and Kidneys. Also included in this category is the Pericardium.

Yin Shen Disturbances - an emotional Yin state of energetic dysfunction.

Yin Tang (Third Eye Point) - located in the center of the forehead, responsible for projecting the Spirit for psychic intuition and communication.

Ying Qi (Nutritive Qi) - the body's nourishing energy.

Yu (Surplus) Vessels - secondary vessels that branch away from the energetic flow of the major Linking Vessels (at the chest and back), connecting the Linking Vessels energetic flow to the hands.

Yuan Jing (Original Essence) - the Original Kidney or Prenatal Essence.

Yuan Shen (Original Spirit) - the Original Prenatal Spirit.

Yuan Qi (Original Energy) - the Original Kidney or Prenatal Qi.

Yun - the Yin method of dynamic postural Dao Yin training.

Yu Zhen Guan (Occipital Pass) - the area located just inferior to the occipital bone where the brain originates, known as a specific point where Qi often stagnates.

Z

Zang Organs - Yin or solid organs (Liver, Heart, Spleen, Lungs, Kidneys and Pericardium).

Zang/Fu Organs - the body's Yin and Yang organs.

Zhang Xiang Xue Shou - in Chinese medical science, the study of energetic physiology.

Zhen Qi - see True Qi

Zheng Qi - Righteous Qi, pathogenic fighting Energy.

Zhi - the Will power, mental drive and determination.

Zhong Qi - Center Qi, Energy of the chest.

Zhou Qi - Turbid Qi, Evil Qi, Impure Qi

Zong Qi - Gathering Qi, and / or Respiratory Qi.

Zygomatic Facial Regions - pertaining to the sides of the cheeks below the eyes.

BIBLIOGRAPHY

1. Anodea Judith
   Wheels of Life
   Liewellyn Publications, 1990
   St. Paul, Minnesota 55164-0383
2. *A Barefoot Doctor's Manual*
   A Guide To Traditional Chinese and Modern Medicine
   A Cloudburst Press Book
   Madrona Publishers
   Seattle, Washington 1977
3. Robert O. Becker, M.D.
   Cross Currents
   Jeremy P. Tarcher, Inc., 1990
   Los Angeles, Ca. 90036
4. Harriet Beinfield, L.Ac. and
   Efrem Korngold, L.Ac., O.M.D.
   Between Heaven And Earth
   A Guide To Chinese Medicine
   Ballantine Books, NY 1992
5. Barbara Ann Brennan
   Hands of Light
   A Guide to Healing Through the Human Energy Field
   Bantam Books Publishing 1988
   New York, New York
6. Paul Carus
   Chinese Astrology
   Early Chinese Occultism
   Open Court Publishing 1989
   La Salle, Illinois
7. Dr. Chen Yan-Feng
   Pre-Natal Energy, Mobilizing Qigong
   China Taoist Ancient Qigong
   Chinese Kung Fu Series
   Guandong Xin hua Printing House 1992
8. *Chinese Qigong*
   Publishing House of Shanghai
   College of Traditional Chinese Medicine
   China 1990
9. *Chinese Qigong*
   Outgoing Qi Therapy
   Shandong Science and Technology Press
   China 1992
10. *Chinese Qigong Therapy*
    Shandong Science and Technology Press
    China 1995
11. Dr. Choa Kok Sui
    Pranic Healing
    Samuel Weiser, Inc. 1990
12. Kenneth S. Cohen
    The Way of Qigong
    Ballantine Books 1997
13. Peter Deadman
    Selected Articles from the
    Journal of Chinese Medicine
    England
14. Peter Deadman & Maazin Al-Khafaji
    with Kevin Baker
    A Manual of Acupuncture
    Journal of Chinese Medicine Publications
    England 1998
15. Luc DeSchepper MD, PhD,CA
    Acupuncture for the practitioner
    Asnta Monica, California 91403
16. Vincent T. DeVita, Jr., Samuel Hellman,
    Steven A. Rosenberg
    Cancer Principles and Practice of Oncology
    Fifth Edition - Vol 1
    Lippincott - Raven Publishers
    Philadelphia - New York 1997

17. Vincent T. DeVita, Jr., Samuel Hellman, Steven A. Rosenberg
Cancer Principles and Practice of Oncology
Fifth Edition - Vol 2
Lippincott - Raven Publishers
Philadelphia - New York 1997

18. Paul Dong and Thomas Raffill
Empty Force
Element Books, Inc., 1996
Rockport, Mass. 01966

19. *Essentials of Chinese Acupuncture*
Beijing College of Traditional Chinese Medicine
Foreign Languages Press, 1980
Beijing, China

20. Richard Feit and Paul Zmiewski
Acumoxa Therapy
A Reference and Study Guide
Volume II The Treatment of Diseases
Paradigm Publications
Brookline, Massachusetts 1990

21. Richard Gerber, M.D.
Vibrational Medicine
Bear and Company, 1988
Santa Fe, New Mexico 87504-2860

22. Stanislav Grof,M.D. with Hal Zina Bennett
The Holotropic Mind
Harper Collins Publishers, Inc. 1993
New York City, New York

23. Rosemary Ellen Guiley
Harper's Encyclopedia of
Mystical and Paranormal Experiences
Harper Collins Publishers Inc. 1991
New York City, New York

24. Dr. Guo Liang Cao
Essentials Of Tuinaology
Chinese Medical Massage and Manipulation
Cao's Fire Dragon
Hilo, Hawaii 1983

25. Leon Hammer, M.D.
Dragon Rises and Red Bird Flies
Psychology and Chinese Medicine
Staton Hills Press, Inc.
Barrytown, New York 1990

26. *Illustration of Channels and Points For Acupuncture and Moxibustion and Qigong*
Hunan Science and Technology Press
China 1992

27. Roger Jahnke D.O.M.
The Healer Within
Harper Publishing
San Francisco 1997

28. Dr. Jiao Guo Rui
Qigong Essentials for Health Promotion
China Reconstruction Press 1990

29. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
Chi Kung Correspondence Course, Vol. 1-6
Pacific Grove, CA 1988

30. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
The Essence of Internal Martial Arts, Vol. 1
Esoteric Fighting Techniques and Healing Methods
Pacific Grove, CA 1994

31. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
The Essence of Internal Martial Arts, Vol. 2
Energy Theory and Cultivation
Pacific Grove, CA 1994

32. Ted J. Kaptchuk, O.M.D.
The Web That Has No Weaver
Congdon and Weed, Inc., 1983
New York, New York, 10001

33. Dr. Arnie Lade, DOM
Acupuncture Points
Images & Functions
Eastland Press 1989

34. Claude Larre and Elisabeth Rochat de la Vallee
The Seven Emotions
Psychology and Health in Ancient China
Monkey Press
Cambridge, CB4 3PU 1996

35. Dr. Mariam Lee, D.O.M.
Insights of a Senior Acupuncturist
Blue Poppy Press
Boulder, Colorado 1992

36. Richard H. Lee
Qi and Kirlian Photography
China Healthways Institute, 1996
San Clemente, Ca 92672

37. Master Shou-Yu Liang and Wen-Ching Wu
Qigong Empowerment
A Guide to Medical, Taoist, Buddhist
and Wushu energy Cultivation
The Way of Dragon Publishing, 1997
East Providence, Rhode Island 02914-0561

38. Dr. Lin Huo Sheng & Dr. Luo Pei Yu
Three Hundred Questions on
Qigong Exercises
Guandong Science and Technology Press
China 1994

39. Dr. Hong Liu with Paul Perry
Mastering Miracles
Warner Books Inc., 1997
New York, New York, 10020

40. Liu Zheng-Cai and Hua Ka
A Study of Daoist Acupuncture
Blue Poppy Press
Boulder, Colorado 1999

41. Livia Kohn & Yoshinobu Sakade
Taoist Meditation and
Longevity Techniques
Center for Chinese Studies
University of Michigan 1989

42. Ke Yun Lu
The Essence of Qigong
A Handbook of Qigong Therapy
and Practice
Abode of the Eternal Tao
Eugene, Or. 1998

43. Giovanni Maciocia
Tongue Diagnosis in Chinese Medicine
Eastland Press Inc., 1987
Seattle, Washington 98111

44. Giovanni Maciocia
Obstetrics & Gynecology in
Chinese Medicine
Churchill Livingstone Inc., 1998
New York City, New York, 10011

45. Giovanni Maciocia
The Foundations of Chinese Medicine
Churchill Livingstone Inc., 1989
New York City, New York, 10011

46. Kiiko Matsumoto & Stephen Birch
Extraordinary Vessels
Paradigm Publications
Brookline, Massachusetts 1986

47. Kiiko Matsumoto and Stephen Birch
Hara Diagnosis: Reflections on the Sea
Paradigm Publications, 1988
Brookline, Massachusetts 02146

48. Hugh Milne
The Heart of Listening
A Visionary Approach to Craniosacral Work
North Atlantic Books
Berkeley, California 1995

49. Joseph Needham,F.R.S.,F.B.A.
Science and Civilization in China
Volume 5 Chemistry and
Chemical Technology
Part V: Spagyrical Discovery and Invention:
Physiological Alchemy
Cambridge University Press 1986
Cambridge, London

50. Master Ni Hua Ching
The Book of Changes and
the Unchanging Truth
Malibu, CA 1983

51. John O'Connor and Dan Bensky
Acupuncture, A Comprehensive Text
Shanghai College of Traditional Medicine
Eastland Press
Chicago, Illinois 1981

52. Yoshiaki Omura, Sc.D.,M.D.
Acupuncture Medicine
Japan Publications, Inc. 1982
Tokyo, Japan

53. Pan Mingji
How to Discover Cancer Through Self-Examination
Fujian Science and Technology
Publishing House
Beijing, China 1992

54. *Point Therapy*
A Chinese Traditional Therapeutic Skill
Shandong Science and Technology
Press 1990

55. Daniel Reid
Harnessing the Power of the Universe
A Complete Guide to the Principles and Practice of Chi-Gung
Shambhala Publications, Inc.
Boston, Massachusetts 1998

56. D. Scott Rago
Leaving the Body
A Complete Guide to Astral Projection
Prentice-Hall, Inc., 1983
Englewood Cliffs, New Jersey

57. Elisabeth Kubler-Ross,M.D.
On Death and Dying
Collier Books, 1969
Macmillan Pub. Co., New York

58. Jeremy Ross, C.Ac. (Nanjing), B.Ac. (M.B.Ac.A.), C.Ed.
Zang Fu,The Organ Systems of Traditional Chinese Medicine
Functions, Interrelationships and Patterns of Disharmony in Theory and Practice
Churchill Livingstone
Edinburgh, London, Melbourne
and New York 1985

59. Stephano Sabetti
The Wholeness Principle
Exploring Life Energy Process
Life Energy Media 1986
Sherman Oaks, California

60. Mikio Sankey Ph.D., L.Ac.
Esoteric Acupuncture
Gateway to Expanded Healing Vol.1
Mountain Castle Publishing
Los Angeles, Ca. 1999

61. Jack Schwark
Human Energy Systems
The Aletheia Foundation, 1980

62. Kylea Taylor
The Ethics of Caring
Hanford Mead Publishers 1995
Santa Cruz, California

63. *Textbook of Medical Qigong Therapy*
Haidian Qigong University
Medical Qigomg College
White Cloud Monestry, 1988
Beijing, China

64. Clayton L. Thomas, M.D., M.P.H.
Taber's Cyclopedic Medical Dictionary
F.A. Davis Company, 1993
Philadelphia, Pa., 19103

65. Michael Tierra
East West Master Course In Herbology
Santa Cruz, California 1981

66. Dr. Tzu Kuo Shih
Qigong Therapy
The Chinese Art of Healing With Energy
Station Hill Press 1994

67. Ilza Veith
The Yellow Emperor's Classic of Internal Medicine
University of California Press, 1966
Berkeley and Los Angeles, Ca.

68. Andrew Weil,M.D.
Spontaneous Healing
Fawcett Columbine
Published by Ballantine Books 1995
New York City, New York

69. Nigel Wiseman and Feng Ye
A Practical Dictionary of Chinese Medicine
Second Edition
Paradigm Publications 1998
Brookline, Massachusetts

70. Henry S. Wu, D.C.
    Differentiation of Syndromes
    California Acupuncture College 1982
    Los Angeles, Ca.
71. Yan De-Xin
    Aging & Blood Stasis
    A New TCM Approach to Geriatrics
    translated by Tang Guo-shun & Bob Flaws
    Blue Poppy Press
    Boulder, Co. 1995
72. Dr. Yang Jwing Ming, Ph.D.
    The Root of Chinese Qigong
    The Secrets of Qigong Training
    Yang Martial Arts Association 1989
73. Yin Hui He
    Fundamentals of
    Traditional Chinese Medicine
    Foreign Languages Press, 1995
    Beijing, China
74. Yu Gong Bao
    Chinese Qigong Illustrated
    New World Press 1995

CLINICAL REFERENCES

1. Master John Fey
   Clinical Notes from Lectures
   Medical Qigong Therapy
   Reference: Differential Healing Modalities
   Los Angeles , CA 1984 to 1987
2. Michael Gershon, M.D.
   Professor of Anatomy and Cell Biology
   Columbia Presbyterian Medical Center
   Research presented by Sandra Blakeslee
   New York Times, New York 1996
3. Dr. Jason Gill, L.Ac.
   Lectures on Traditional Chinese Medicine
   Clinical Notes on Differential Diagnosis
   Pacific Grove, CA 1994 to 1997
4. Dr. Jason Gill
   Clinical notes and Lectures
   Reference: Dr. Jeremy Ross Lectures
   on Traditional Chinese Medicine
   Pacific Grove, CA. 1994 to 1997
5. Dr. Jiang Gui Zhong and
   Dr. Cai Chang Rong
   Clinical Notes from Hu Guo Hospital
   Medical Qigong Therapy, An Mo Therapy
   and Differential Healing Modalities
   Beijing, China 1993
6. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
   Clinical notes from the First World
   Conference on Medical Qigong
   Medical Qigong Therapy and Differential
   Healing Modalities
   Reference Conference No. 1, Sept. 1988
7. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
   Clinical notes from the International
   Symposium on Chinese Qigong Health
   Preservation and Qigong Techniques
   Medical Qigong Therapy and Differential
   Healing Modalities
   Reference Symposium, Nov. 1990
8. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
   Clinical notes from the Second World
   Conference on Medical Qigong
   Medical Qigong Therapy and Differential
   Healing Modalities
   Reference Conference No. 2, Sept. 1993
9. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
   Clinical notes from Xi Yuan Hospital
   on Medical Qigong Therapy and
   Differential Healing Modalities
   Internship July 1993 through Sept. 1995
10. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
    Clinical notes from Hai Dian Medical
    University on Medical Qigong Therapy and
    Differential Healing Modalities
    July 1993 through Sept. 1995
11. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
    Clinical notes from the Third World
    Conference on Medical Qigong
    Medical Qigong Therapy and Differential
    Healing Modalities
    Reference Conference No. 3, Sept. 1996

12. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
Clinical notes from the Second World Congress on Medical Qigong
Medical Qigong Therapy and Differential Healing Modalities
San Francisco, California Nov. 1997

13. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
Clinical notes from the Fourth World Conference on Medical Qigong
Medical Qigong Therapy and Differential Healing Modalities
Reference Conference No. 4, Sept. 1998

14. Jerry Alan Johnson, Ph.D., D.T.C.M., D.M.Q. (China)
Clinical Notes from International Institute of Medical Qigong
Medical Qigong Therapy and Differential Healing Modalities
Pacific Grove, CA 1988 - 1999

15. Sifu Mark Johnson
Clinical Notes in Geriatric Medical Qigong Therapy and Esoteric Daoist Studies of the Yi-Jing and Feng Shui
Mill Valley, CA 1998 - 1999

16. Dr. Lu Guo Hong, Dr. Niu Yu Hua, and Dr. Li Fu Dong
Clinical notes from Hai Dian Medical University on Medical Qigong Therapy and Differential Healing Modalities
Beijing, China 1993 - 1996

17. Dr. Lu and Dr. Shu Zong Wei
Clinical Notes from Xi Yuan Hospital
Medical Qigong Therapy and Differential Healing Modalities
Beijing, China 1993

18. Dr. Hugh Milne
Clinical Notes from Cranial-Sacral Therapy Level 1 through 6, 1990-1995
Monterey, Calif.

19. Dr. Ren Shun Tu & Dr. Xu Hong Tao
Clinical Notes from Xi Yuan Hospital
Medical Qigong Therapy and Differential Healing Modalities
Beijing, China 1995

20. Dr. Teng Ying Bo
Clinical Notes from Beijing Medical Qigong Science and Research Institute
Medical Qigong Therapy and Differential Healing Modalities
Beijing, China 1995

21. Dr. Zheng Zhan Ding
Clinical Notes on Medical Qigong Diagnosis, Therapy and Differential Healing Modalities
Beijing, China 1993 - 1996

INDEX

A

Abdominal Breathing, 392-394, 422
Abdominal Pain, 64, 206, 208, 211, 471, 473, 565, 768, 788,793-795, 838, 910, 916, 917, 920
Abortions, 444, 445, 600, 860, 861
Absorbing Qi From Nature, 125, 126, 293, 304, 306, 307
Acquired Cellular Patterns, 115
Acquired Constitution, 787
Acquired Disorders, 461
Acquired Energy, 317
Acquired Essence, 319, 607, 720
Acquired Force, 270
Acquired Mind, 91, 201, 333, 335, 336, 138, 344, 345
Acupressure, 631, 928
Acupuncture, 49, 50, 52, 54, 56, 59, 66, 126, 128, 129, 133, 159, 164, 199, 215, 245-249, 309, 507, 522, 529, 536, 537, 557, 565, 566, 595, 611, 662, 664, 839,683, 864, 865, 882, 884, 922, 923, 924, 929
Adenocarcinoma, 689, 896, 910, 911, 913
Adrenaline, 426, 781, 900
Affirmation, 87, 89, 90, 104, 115, 411, 430, 448, 519, 554, 555, 561, 619, 861, 882, 904, 921
Akashic Records, 516
Alarm Points, 252
Alchemy, 131, 132, 249, 267, 293
Alternating Current, 128
An Jing (Hidden Power), 48
An Mo, 57, 61-65, 566, 631, 832, 890, 893
Anal Sphincter, 149, 154, 200, 342, 363, 365, 366, 393, 422, 451, 691, 728, 734, 752, 824, 868, 893, 909, 912, 917
Ancestral Channel, 197
Ancestral Qi, 137
Ancestral Traits, 274, 510, 517
Anemia, 425, 784, 828, 896, 915, 916
Anesthesia, 129, 438, 442, 447, 922, 923, 924, 925, 928
Anger, 48, 64, 75, 88, 99, 108, 138, 149, 154, 155, 168, 348, 403, 404, 413, 427, 429, 431, 439, 445-447, 452, 460, 466-470, 488, 508, 545, 560, 578, 581, 582, 594, 599, 601, 602, 615, 617, 619, 624, 626, 627, 708, 767, 769, 794, 796, 798, 828, 844, 849, 850, 852, 855, 858, 859, 860, 861, 869, 871, 872, 874, 877, 890, 891, 892, 899, 900, 905, 911, 913
Angina, 384, 394, 602, 779
Anorexia, 774, 775, 796, 819, 828, 916
Antique Shu Points, 249, 250, 251 370
Anxiety, 75, 88, 108, 123, 129, 135, 170, 174, 176, 204, 208, 214, 250, 253, 391, 394, 398, 404, 426, 432, 439, 447, 469-471, 488, 508, 602, 616, 784, 796, 880, 817, 818, 820, 828, 830, 843, 859, 874, 875, 877-882, 888, 900
Aphasia, 202, 212, 219, 220, 492, 505, 864, 890
Aplastic Anemia, 784
Archetypes, 48, 87, 334, 336
Arrhythmia, 779, 784
Arteriosclerosis, 777, 828, 865
Arthritis, 64, 384, 566, 823, 826, 827
Ascariasis, 772, 773
Ascending Qi, 201, 375, 376, 667
Asthma, 172, 174, 198, 204, 251, 360, 382, 443, 447, 464, 466, 492, 495, 497, 544, 670, 672, 731, 766, 801-803, 806-808, 812, 823, 838, 897
Astral Body, 84, 85, 348, 349, 351, 437
Astral Matter, 328
Astral Plane, 344, 348, 350, 351, 444, 516
Astral Travel, 85, 91, 328, 337, 345, 346, 435
Astrology (Chinese), 99, 268, 293, 297
Atman, Adam, 50, 54
Atrophy Syndrome (Disorder), 603, 792, 802, 867
Aura, 137, 143, 147, 155, 328, 525 529, 531, 688, 831, 925
Aura Colors, 525, 528
Auspicious Powers, 280
Autumn Equinox, 280
Awakening, 74, 150, 411, 413, 430, 513, 650

B

Ba Gan, 465
Back Pain, 154, 194, 202, 219, 421, 461, 497, 670, 812, 813
Bai Yuan, 84, 86
Baihui Point, 84, 147, 201, 229, 284, 370, 371, 431, 453, 520, 547, 573, 575, 846
Base Chakra, 151
Becker, Robert O., 128, 129, 141, 245, 246
Beijing Medical University, 274

Bellows Palm Technique, 594, 639, 659
Bells Palsy (Facial Paralysis), 866
Belt Vessel, 70, 71, 185, 197, 198, 200, 206-209, 210, 253, 260, 386, 575, 718, 728, 735, 737, 850, 851
Benign Tumors, 766, 854, 895-897, 916
Big Dipper, 135, 273, 290-294, 575, 612
Biochemical, 128, 138, 515, 685
Biorhythm, 272-276
Bitter Foods, 304, 310, 311, 466, 472, 770, 777, 851
Black, 46, 105, 247, 308, 310, 311, 327, 413, 414, 426, 431, 438, 439, 451, 452, 473, 502, 504, 505, 521, 529, 617, 624, 770, 811, 851, 852, 905, 906
Bladder, 57, 78, 82, 123, 136, 146, 154, 161, 182-185, 193, 312, 324
Bladder Channel, 71, 82, 174, 182 184, 194, 201, 210, 212, 219, 221, 236, 252, 381, 501, 504, 707, 772, 794, 797, 805, 807, 817, 818, 830, 831, 890
Bladder Divergent Channel, 222, 225
Bladder Fire, 127
Bloated Energy Stagnation, 600
Blood Deficiency, 170, 214, 242, 489, 670, 768, 777, 785, 788, 798, 816, 818, 823, 828, 849, 851-853, 858, 859
Blood Heat, 490, 851, 854, 859, 890
Blood Pressure, 64, 274, 362, 377, 379, 391, 394, 398, 406, 426, 670, 672, 684, 780-783, 863, 865, 888, 890, 900, 901, 922
Blood Stasis, 180, 399, 486, 490, 667, 692, 825, 843, 854, 855, 858, 859, 881, 897, 898
Blood Vessels, 73, 76, 128, 138, 163, 170, 176, 178, 180, 189, 198, 217, 241, 243, 257, 262, 263, 322-324, 326, 329, 378, 391, 392, 394, 398, 401, 403, 466, 489, 490, 504, 610, 612, 617, 781, 843, 873
Blue, 74, 91, 101, 121-124, 147, 155, 217, 241, 247, 293, 294, 307, 326, 426, 453, 524, 526, 529, 561, 573, 575, 610, 624, 633, 653, 654, 658, 701, 769, 813, 814, 829, 842, 851, 852, 853, 904, 906, 909, 913, 925
Body Fluids, 73, 74, 92, 119, 159, 163-166, 170, 182, 184, 191, 193, 318, 324, 333, 459, 466, 481, 483, 490-492, 496, 501, 616, 687, 798, 897, 920
Bone, 79, 81, 95, 129, 198, 260-263, 319, 650, 837, 895 896
Bone Marrow, 76, 141, 166, 260, 319, 324, 330, 331, 491, 684, 685, 726, 901
Bones, 257, 260, 261, 263
Book of Commentaries, 271
Borborygmus, 472
Brain, 77, 138, 140, 141, 146, 184, 198, 201, 202, 257-260, 324, 328, 330, 331, 349, 401, 403, 404, 408, 410, 519, 527, 587, 599, 605, 671, 843, 861, 863-870, 880, 888, 895, 906
Brain Tumor, 441, 713, 906, 907
Breast Cancer, 896, 904, 907, 908
Breast Cysts, 108, 731, 601, 854, 855, 857
Breath Regulation, 355, 356, 391, 396,, 397 803
Bridge of Light, 409, 410, 548
Bronchial Asthma, 766, 803, 806
Bronchiectasis, 808
Bronchitis, 360, 382, 731, 803, 806, 823

C

Caduceus, 721
Calculi, 773
Cancer Formation, 898, 897, 899
Cancer Research, 904
Cancer Treatments, 895
Carbuncle, 854, 855
Carcinogens, 913, 916
Carcinoma, 204, 689, 713, 715, 896, 908-916
Categorization of Signs and Symptoms, 462
Categorization of Tumors, 895
Celestial Stems, 296, 300
Center Core, 131, 148, 149, 150, 151, 161, 307, 330-332, 409, 415, 438, 494, 541, 547, 573, 620, 621, 650, 737, 873
Center Qi, 321, 322, 324
Center Thrusting Channels, 120, 293, 295
Centrifugal and Centripetal, 249
Cerebral Embolism, 689, 863
Cerebral Hemorrhage, 689, 863
Cerebral Thrombosis, 863
Cerebro-Vascular Accident (CVA), 863
Cervical Cancer, 601, 689, 909-911
Chakra, 135, 139, 142-144, 151-157, 553, 600, 722, 737
Chakra System, 151, 153, 157
Channel Pathology, 193, 194, 252
Channel Point Meditation, 665, 669, 688, 882
Channel Point Therapy, 883
Channel Points, 59, 66, 126, 128, 159, 228, 246, 249, 250, 644, 651, 665-668, 675, 676, 692, 721
Chao, Yuan Fang, 71, 523
Chemotherapy, 411, 551, 707, 713, 919-921, 927
Cheng, Zhong Ling, 465
Chicken Pecking Technique, 663
Child Element, 656
China Healthways, 47, 119, 125, 129
Chinese Massage, 49, 50, 52, 56, 57, 61, 62, 129, 164, 309, 631, 565, 566
Cholecystitis, 772, 775, 776

Cholelithiasis, 772, 776
Cholestasis, 773
Chronic Bronchitis, 360, 731, 806
Chronic Constipation, 799,798
Chronic Fatigue Syndrome, 360, 598
Chronic Gastritis, 796
Chronobiology, 274
Chyluria, 791
Circle of Willis, 865
Circle Twisting Method, 677
Circular Breathing , 723
Cirrhosis, 774
Clairaudience, 146, 155, 343, 346
Clairsentience, 155
Clairvoyance, 146, 343, 346, 351, 437
Classification of Energetic Points, 249
Clean Qi, 191, 505
Climate, 215, 356, 466, 467, 488, 815
Clinical Ethics, 576, 578
Coccyx Pass (Wei Lu Guan), 605
Cold, 465-467, 470-475, 477, 480, 481, 551, 552, 597, 598
Cold Deficiency, 502
Colitis, 602, 789, 875, 916
Collapsed Qi, 488
Colon and Rectum Cancer, 916
Color Imagery, 123
Color Vibration, 119, 120, 122, 526
Color Visualization, 683, 688, 701, 770, 925
Coma, 64, 146, 444, 466, 823, 850, 864-866
Common Cold and Influenza, 801, 802, 804
Common People's Fire, 127
Compass School (Feng Shui), 270
Compassion, 75, 104, 155, 168, 429, 431, 437, 446-448, 524, 541, 617, 624, 860, 871, 872, 878, 880, 904, 905, 906, 921
Compressed Energy Stagnation, 600
Compression Release Method, 676-679
Concentrative Meditation, 407
Conception; 67-70, 72, 74, 84, 86, 119, 132, 200, 274, 275, 318, 320, 321, 333, 339, 409
Conception Vessel, 151, 157, 198, 200-208, 213, 217, 221, 242, 252, 257, 284, 294, 342, 372, 387, 432, 605, 606, 646, 670, 720-723, 733, 743, 785, 850-852, 855, 856, 882, 903, 909, 911
Congealed Blood, 241
Congenital Cellular Patterns, 115
Congenital Constitution, 99
Congenital Jing, 99, 115
Congenital Qi, 838
Congenital Spirit, 401
Connecting Channels, 208, 239, 864
Conscious Mind, 343, 409, 410, 439, 441, 617, 625, 665, 879
Constipation, 154, 174, 470, 502, 503, 505, 768, 781, 788, 789, 791, 794, 798, 799, 812, 828, 830, 873, 875, 915, 916, 920
Constitution, 61, 68, 99, 100-105, 176, 319, 356, 360, 362, 395, 419, 420, 426, 453, 457-459, 460, 462-465, 475-477, 479, 483, 484, 486, 490, 507, 511, 557, 563, 566, 569, 598, 603, 631, 689, 711, 784, 787, 798, 823, 832, 833, 839, 852, 858, 863, 864, 866, 929
Constitutional Failure, 459
Contracted Energy Stagnation, 600, 601
Contraindications for Medical Qigong, 590
Controlling Cycle, 100, 123, 313, 468, 496, 871, 874, 891
Corporeal Soul, 138, 250, 273, 429, 436, 847, 874, 886
Coryza, 805
Cosmology, 268, 348
Counter-Transference, 579
Creative Cycle, 100, 123, 249, 251, 281, 316, 495, 496, 656, 871
Creative Subconscious, 409, 412, 444, 513, 554, 555, 561, 617, 623
Crown Center, 156
Crown Chakra, 151, 153, 154, 737
Cupping, 57-59, 649, 659, 815, 816
Curious Organs, 257
Cycle of Disharmony, 468
Cycle of the Moon, 276, 284
Cycle of the Sun, 276, 277
Cycles of the Stars, 290
Cysts and Tumors, 64, 601, 731, 854, 860, 887, 895
Cytotoxic Treatments, 919

D

D.M.Q., 50, 54
Damp Heat, 174, 184, 193, 210, 486, 504, 505, 667, 669, 671, 747, 768, 773-776, 788, 792, 805, 809, 819-821, 851, 852, 857, 911, 920
Dantian Breathing, 723
Dao, 47, 84, 102, 132, 141, 142, 144, 148, 149, 199, 267, 268, 271, 317, 318, 323, 326, 333, 407, 416, 514, 515, 541, 587
Daoist, 99, 118, 131-133, 143, 249, 333, 348, 350, 378, 688, 708, 717, 751, 752, 762, 763, 784, 797, 799, 806, 827, 854, 868
Death, 86-89, 92, 93, 95, 132, 134, 135, 142, 144, 268, 270, 276, 292, 334, 339, 344, 411, 426, 436, 437, 442-445, 459, 468, 503, 518, 530, 541, 545,

625, 626, 627, 628, 827, 846, 848, 860, 865, 874, 875, 896, 900, 911, 913, 915, 921
Defense Mechanism, 149, 447, 450, 604, 619, 621, 838
Deficient Dantian Qi, 823
Delusions, 437, 438, 870, 883
Demon Oppression, 437, 438
Demon Possession, 424, 438, 442,
Denial, 142, 326, 438,441, 444, 447, 449, 450, 569, 578, 602, 618-621, 626, 720, 875, 882, 892, 898, 899, 922
Depersonalization Disorder, 446
Depression, 89, 119, 129, 156, 168, 172, 191, 202, 214, 219, 245, 335, 337, 341, 391, 404, 426, 427, 439, 444, 446, 460, 468, 469, 476, 486, 518, 545, 560, 590, 598, 626, 627, 653, 695, 708, 772, 776, 798, 818, 830, 843, 844, 850, 852, 855, 857, 874, 881, 886, 887, 897, 898, 900, 903, 907, 913, 922, 927
Diabetes, 64, 155, 311, 781, 791, 792, 820, 863
Diagnosis According to the Triple Burners, 504
Diagnosis and Treatment of the Patient, 462
Diaphoresis, 501
Diet, 46, 61, 69, 95, 99, 115, 176, 260, 308-310, 313, 421, 426, 458, 460, 467, 472, 473, 475, 484, 486, 489, 490, 509, 510, 570, 686, 773, 791, 798, 807, 818, 838, 847, 850, 851, 859, 863, 867, 881, 895, 911, 915, 916, 927
Different Schools of Qigong, 47
Differentiation of Psycho-Emotional Disorders, 881
Differentiation of Syndromes, 461, 502
Digestion, 111, 168, 174, 176, 178, 182, 189, 191, 260, 309, 310, 312, 333, 360, 361, 372, 409, 460, 486, 505, 509, 616, 694, 743, 789, 897, 914, 920
Direct Current, 128, 246
Disorders of Body Fluids, 491,490
Disorders of Qi, 483
Disorders of the Blood, 489, 490
Disorders of the Body Fluids, 490
Disorders of the Human Body, 459
Disorders of the Qi, 483, 489, 825
Divergent Channels, 160, 161, 222-227
Divine Center, 290, 438
Divine Energy, 46, 48, 91, 132, 147, 161, 260, 317, 323, 407, 515, 531, 570, 576, 587, 661, 870
Divine Guidance, 649
Divine Healing, 407, 440, 452, 453, 533, 542, 544, 546-549, 556, 577, 606, 624, 661 697, 708, 709, 846, 857, 861, 868, 904, 905, 928
Divine Hook-Up, 541, 542, 546-548, 550, 582, 583
Divine Light, 86, 115, 326, 437, 547, 559, 573
Divine Qi, 323, 531, 694, 696, 697
Divine Will, 142, 155, 340, 407, 548, 625, 627
Dossey, Larry, 530
Dragons Mouth Technique, 659
Draining Toxic Qi, 596
Dreams, 335-337, 340, 344, 347 436, 437-439, 448, 449, 627
Dry Crying Prescription, 622, 688, 857, 893, 913, 914
Durville, Hector, 437
Dynamic Qigong, 278, 355, 356, 372, 373, 406, 426, 591, 717, 866
Dysmenorrhea, 206, 471, 768, 852, 853, 924
Dyspepsia, 469, 694, 775, 796, 915
Dyspeptic, 794
Dysphoria, 781, 796
Dyspnea, 172, 198, 214, 251, 253, 360, 464, 467, 785, 803, 806, 807, 811, 813, 838

E

Earth Element, 98, 100, 293, 493, 663, 676
Earth Jing, 80, 81
Earth Qi, 67, 73, 82, 83, 132-134, 301-303, 305, 307, 308, 324, 362, 372, 380, 383, 386, 532, 656, 718, 719, 724, 726, 728, 733, 734, 737, 752
Earth Transpersonal Point, 576
Earthly Branches,156, 157, 161, 268, 269, 270, 281, 290, 291, 296, 297, 299, 721
Eczema, 241, 807
Edema, 96, 172, 242, 382, 422, 492, 496, 498, 602, 665, 667, 777, 785, 787, 788, 812, 819, 850, 906, 920
Ego, 142, 155, 331, 340, 344, 416, 428, 517, 519, 541, 621, 880
Eight Confluent Points, 253, 611
Eight Energetic Principles, 308, 461, 465, 478, 480, 509
Eight Energetic Touches, 359, 408, 588, 589, 598
Eight Extraordinary Vessels, 70, 71, 83, 84, 107, 133, 148, 159, 160, 197, 198, 199, 200, 215, 216, 253, 257, 284, 296, 332, 611, 731, 826, 849, 882
Eight Influential Points, 253
Eight Miscellaneous Causes of Disease, 460
Eight Miscellaneous Factors, 459, 460
Eight Principles of Differential Diagnosis, 465
Eight Trigrams, 270, 271, 286, 610-612
Eighteen Classifications of Qi, 321
Eighth Lunar Month, 80
Electricity, 117, 124, 126, 128, 129, 141, 581, 631
Elemental Constitutions, 83, 95, 99, 100, 106, 107, 114, 115, 320, 462, 612
Elements, 57, 75, 98, 99, 107, 118, 119, 249, 250, 251, 268, 269, 270, 273, 276, 281, 290, 299, 308,

310, 311, 313, 469, 493, 494, 496, 497, 555, 556, 575, 612, 654, 655, 663, 675, 690, 838, 870, 871, 878
Emaciation, 206, 484, 594, 791, 808, 825, 914
Embryological Development, 67, 71, 200, 206
Emotional Components of Cancer, 898
Emotional Disharmony, 468, 878
Emotional Disorder, 882
Empathic Communication, 84, 138, 139, 513, 519
Emperor, 90, 91, 138, 144, 268, 293, 296, 333, 529, 607, 609, 767, 777, 787, 801, 811
Empty Qi, 484, 486, 488
Endocrine System, 392, 394, 403
Endorphins, 129, 635, 899, 922
Energetic Armoring, 431, 600, 602, 606, 688, 778
Energetic Barriers, 327
Energetic Blockages, 598
Energetic Boundary Invasion, 581, 582
Energetic Circle Drawing Pattern, 546, 547, 550, 551
Energetic Complications, 600, 601, 606
Energetic Cords, 552-555, 624, 905, 906
Energetic Cupping, 649, 659
Energetic Depletion, 559, 560, 569, 600-603, 606
Energetic Disharmony, 459
Energetic Disorder, 461
Energetic Grids, 88, 91, 272, 326, 327, 561, 925
Energetic Leakage, 600, 603, 606
Energetic Medicine, 84, 157, 259, 628, 766, 869
Energetic Point Therapy, 57, 64-66, 247, 405, 665, 669
Energy Balancing Procedures, 597
Energy Projection, 118, 120, 155, 247, 326, 343, 348, 349, 351, 561, 631, 633 649, 651, 654, 769
Enuresis, 184, 219, 220, 766, 788, 802, 812
Environmental Energy, 48, 67-69, 88, 125, 149, 161, 199, 268, 274, 302, 307, 327, 517, 547, 553, 560, 724, 726, 739
Environmental Force, 270
Environmental Qi, 86, 144, 152, 286, 302, 306, 307, 324, 351, 587, 391, 572, 846
Epigastric Pain, 471, 496, 768, 792, 796, 850
Esophageal Cancer, 914
Esophagus, 176, 180, 914
Eternal Soul, 48, 74-76, 80, 86, 87, 90, 92, 93, 138, 251, 334-338, 340, 341, 401, 436, 447, 349, 444, 616
Ethics, Clinical, 576, 580, 578
Etiology During Adulthood, 458
Etiology During Childhood, 458
Etiology Within the Womb, 457
Eustachian Tubes, 741
Evil Qi, 290, 322-324, 357, 377, 431, 459, 460, 570, 571, 590, 664, 679, 692, 779, 803
Evil States, 437, 439
Evil Wind, 851
Excess Body Fluids, 492
Excess Heat, 51, 126, 134, 260, 394, 395, 488, 490, 510, 594, 664, 706, 707, 713, 731, 733, 783, 789, 803, 813, 823, 829, 839, 841, 856, 866, 897, 908, 911, 913, 914, 915, 916, 917
Excess Liver Fire, 364, 776, 781, 783, 863, 890, 906, 907, 911
Excess Qi, 58, 59, 61, 107, 108, 129, 140, 197, 243, 310-312, 377, 387, 388, 399, 405, 486, 488, 532, 551, 593, 595, 612, 669, 680, 687, 740, 744, 745, 779, 782, 783
Expanded Energy Stagnation, 600, 602
Extended Fan Palm Technique, 552, 634, 640, 650-653, 658, 659, 773-776, 782-785, 791, 794-799, 805-808, 810, 816, 817, 819, 820, 825 827, 829, 830, 853, 854, 866, 867, 882
External Pathogenic Factors, 48, 64, 239, 251, 312, 322, 323, 327, 328, 465, 466, 471, 503, 613, 699, 807
External Wei Qi Fields, 64, 151, 263
Extra Point, 572, 590, 742
Extraordinary Organs, 141, 197, 198, 257
Extroverted Structure, 114

F

Facial Paralysis (Bells Palsy), 194, 212, 467, 864, 866
Facing the Death of a Patient, 625
Faith Projection, 532
Fall Equinox, 573
False Self, 441
False Yang, 475, 477
False Yin, 478, 477
Fascia, 61, 67, 95, 150, 159, 163, 164, 228, 229, 241, 552, 673, 675, 679, 817, 927
Fear, 64, 75, 76, 89, 99, 104, 106-108, 129, 142, 149, 151, 154, 172, 182, 187, 327, 330, 335, 348, 365, 368, 404, 413, 427, 429, 432, 439, 445, 452, 460, 470, 488, 508, 512, 518
Febrile Diseases, 59, 501, 502, 504, 798, 838
Feng, Lida, 904
Feng Shui, 119, 270
Fetal Toxins, 68, 77, 458
Fetus, 68-77, 80-83, 86, 88, 99, 148, 197, 204, 206, 208, 257, 269, 275, 317, 320, 322, 457, 516, 517, 553, 684, 686, 858, 859, 860
Fibroadenoma, 854, 855
Fifteen Collaterals, 217
Fifth Lunar Month, 77

Fire Cycle, 157, 201, 260, 293, 294, 646, 662, 707, 719-721, 784, 812, 817, 839, 845, 854, 867, 868, 908, 917
Fire Element, 79, 98, 100, 137, 251, 293, 493, 653, 676
Fire Jing, 77
First Lunar Month, 72
Five Agents, 74-78, 86, 87, 99, 118, 137, 292, 333-335, 347
Five Dominions of Energy, 45
Five Element Cycles, 878
Five Element Organs, 296
Five Element Theory, 313, 333, 463
Five Elemental Animals, 270
Five Elemental Constitutions, 83, 95, 99, 100, 106, 107, 114, 115, 320, 462, 612
Five Energetic Fields, 47, 326
Five Essence Spirits, 75, 90, 139, 141, 334, 346, 847, 870
Five Flavors, 310, 311, 313
Five Orbs, 77, 78
Five Palms Hot, 471, 802
Five Passes, 424, 604, 605
Five Portals of the Earthly Gate, 148, 342
Five Portals of the Heavenly Gate, 342
Five Sense Organs, 217, 242
Five Stages of Healing, 687
Five Thunder Fingers, 594, 641, 647
Five Tissues, 242
Five Yang Organs, 82
Five Yin Organs, 75, 77, 78, 80, 82, 84, 90, 137, 141, 204, 292, 295, 329, 333, 339, 341-344, 372, 376, 419, 429, 452, 572, 615, 655, 657, 663, 699, 724, 743, 749, 811, 837, 849, 870, 871, 873, 876
Fixation, 621
Flat Palm Detection, 521, 522, 554
Fluids, 60, 73, 74, 76, 92, 119, 137, 159, 163-166, 170, 174, 182, 184, 189, 191-193, 241, 242, 310, 311, 312, 315, 318, 322-324, 333, 459, 466, 470, 472, 473, 478, 481, 483, 490-492, 495, 496, 498, 501, 504, 537, 602, 616, 687, 752, 791, 798, 801, 871, 881, 897, 920
Food and Color, 123
Food Qi, 137, 321, 324, 837
Form School (Feng Shui), 270
Four Bigs, 501-503, 505
Four Categories of Energetic Points, 246
Four Doors, 749
Four Levels, 57, 462, 502, 510
Four Principle Time Periods, 278, 657
Four Seasonal Peak Transitions, 279
Four Winds, 306
Fourth Lunar Month , 76
Freud, Sigmund, 516, 621

G

Gall Bladder, 160, 166-168, 182, 191, 192, 194, 257, 260
Gall Bladder Channel, 73, 166, 168, 194, 215, 219, 222, 229, 253, 375, 560, 595, 707, 768, 772, 774, 815
Gall Bladder Divergent Channel, 222, 223
Gallstones, 119, 773, 775
Gastric and Duodenal Ulcers, 789, 797
Gastritis, 208, 695, 789, 796
Gastroptosis, 360, 788
Gate of Access, 292
Gate of Life (Mingmen), 135, 154, 670, 746, 811
Gate of the Moon, 279, 280
Gathering Qi, 137, 303, 305, 306, 322, 324, 391, 469, 641, 688, 726-728
Gathering Sun, 688
Generated Heat, 126
Geriatrics, 567, 836, 843
Gershon, Michael, 134, 135
Ghost Points, 254, 670, 884
Ghosts (Gui), 351, 435, 436, 439, 441, 444, 445, 884
Gill, Jason, 929
Gold, 120, 131, 132, 148, 156, 283, 293, 294, 307, 331, 406, 431, 452, 573, 624, 640, 657, 658, 661, 701, 719, 905
Gold, Philip, 426
Governing Vessel, 198, 200-203, 215, 220, 221, 253, 259, 260, 849, 866
Grasping and Shaking Method, 676, 677
Green, 53, 101, 121-123, 155, 293, 296, 307, 308, 310, 425, 433, 439, 492, 496, 508, 574, 575, 658, 701, 770, 851, 852, 857
Grief, 48, 64, 75, 88, 99, 104, 105, 108, 129, 155, 170, 172, 339, 404, 413, 427, 432, 439, 445-447, 460, 488, 508, 559, 581, 594, 599, 600, 602, 616, 617, 619, 708, 844, 855, 857, 871-875, 877, 890-892, 894, 899, 907, 922
Gu Qi (Food Qi), 83, 137, 163, 176, 180, 191, 309, 319, 321, 322, 324, 489, 495, 496, 537, 787, 837
Gua Sha, 57, 61, 62, 63, 565
Gui (Ghosts), 86, 93, 334, 338, 436, 444, 445, 611, 875
Guiding Qi, 779, 803, 368
Gynecology, 567, 836, 849, 860

H

Hai Dian University, Medical Qigong College, 51, 69
Hand Postures for Qi Emission, 634
He, Si Hai, 689
Headaches, 54, 64, 111, 115, 155, 198, 202, 211, 214, 219, 394, 397, 403, 421, 422, 426, 495, 518, 569, 599, 672, 768, 769, 777, 781, 801, 802, 812, 818, 823, 829, 831, 832, 833, 850, 890
Healing Emotional Trauma, 623
Healing Sound Therapy, 118, 699, 710, 919
Heart, 80, 84, 99, 140, 152, 179, 214, 220, 281, 293, 337, 338, 340, 341, 343, 430, 490, 495, 496, 497, 560, 603, 606, 616, 664, 726, 769, 779, 817, 838, 872, 886
Heart Channel, 178, 180, 194, 220, 235, 279, 778
Heart Diseases, 379, 384, 669, 777, 778, 780
Heart Divergent Channel, 222, 226
Heart Fire, 123, 127, 137, 151, 180, 310, 311, 430, 495, 558, 671, 704, 744, 778, 779, 823, 831, 838, 839, 843, 876
Heart Massage, 691, 693, 694, 695, 696, 697, 779, 785
Heat Deficiency, 502
Heaven Qi, 67, 83, 87, 125, 132, 139, 140, 141, 273, 308, 324, 372, 381, 386
Heavenly Stems, 161, 268, 270, 281, 286, 296, 297, 299
Heavenly Transpersonal Point, 576, 661
Hemiplegia, 864, 865
Hemoptysis, 785, 807, 808, 850
Hepatitis, 383, 425, 567, 770, 776, 913
Hepatolithiasis, 776
Hepatomegaly, 913
Hepatosplenomegaly, 770
Herbal Medicine, 49, 50, 60, 164, 336, 565, 566
Herbalist, 60, 61, 566, 569
Herpes Simplex, 472
Hexagram, 109, 111-115, 277, 278, 279, 363
Hibernation Breathing, 399, 689
Hidden Power (An Jing), 48, 260
High Blood Pressure (Hypertension), 64, 379, 406, 443, 781, 783, 863, 890
History of Cancer Treatments, 895
Hollow Organ, 767, 777, 787, 801, 811
Hologram, 325, 326, 404, 516, 581
Hong, Liu , 912
Hostile Forces, 89, 438, 442
Hou Tian Zhi Qi, 321
Housing the Shen, 48, 178, 337, 342, 343
Howell, Madeleine, 53, 56
Hua Jing (Mysterious Power), 48
Hua, Tuo, 924
Huiyin Point, 145, 201, 284, 342, 550, 573
Hun (Ethereal Soul), 48, 74-78, 80, 84, 86, 87, 88, 90-92, 132, 138, 139, 141, 146, 168, 250, 251, 273, 333-341, 344, 347, 371, 401, 409, 420, 424, 429, 435, 436, 438, 441, 442, 444, 446-448, 460, 574, 604, 616, 717, 724, 767, 818, 839, 847, 865, 871, 872, 890
Hyperhidrosis, 791
Hypertension, 51, 54, 99, 180, 211, 214, 360, 375, 391, 394, 403, 425, 565, 566, 669, 672, 770, 774, 777, 779, 780, 781, 782, 783, 823, 828, 829, 850, 865, 890
Hyperthyroidism, 781, 784, 791
Hypochondriac Pain, 215, 498, 768, 770, 772, 775, 776, 874, 913
Hyposmia, 803
Hypotension, 210, 214, 376, 425

I

I Ching, 109
Id, 621
Immortal, 842
Immune System, 47, 115, 137, 154, 198, 241, 260, 274, 322, 341, 385, 400, 403, 426, 430, 470, 552, 598, 620, 684-686, 753, 807, 840, 895, 898-902, 905, 906, 919-921, 929
Impotence, 154, 202, 230, 695, 726, 819, 820
Improper Yin and Yang Energy Balance, 824
Incredible Wonders, 588, 590
Indago, 575
Infatuation, 437, 444
Influenza, 470, 788, 801-805, 809
inner-vision, 85, 259, 325, 346, 371, 405
Insight Meditation, 407
Insomnia, 64, 138, 180, 204, 211-214, 250, 322, 335, 395, 471, 478, 484, 495, 497, 502, 504, 565, 672, 697, 768, 778-782, 784, 817, 818, 823, 825, 828, 830,840, 843, 847, 890
Insulting Cycle, 497
Intent (Yi), 49, 80, 134, 191, 278, 332, 361, 378, 394, 398, 411, 427, 534, 617, 648, 650, 691-696, 813
Internal Dialogues, 86, 87
Internal Organ Disorders, 838
Internal Pathogenic Factors, 64, 323, 467, 699
Internal Viewing (Inner-Vision), 520
Internal Wind, 202, 465, 467, 863, 881

Introverted Structure, 114
Intuition, 101, 102, 134, 140, 143, 144, 146, 154-156, 197, 201, 286, 328, 336, 343, 544, 577, 617, 649
Intuitive and Perceptual Diagnosis, 507, 512, 513, 521
Invading Cycle, 497
Invisible Needle Therapy, 65, 66, 247, 639, 640, 651, 659, 661-665, 669, 865
Iron Wall, 604

J

Jahnke, Roger, 903
Jaundice, 498, 768, 772, 773, 915
Jia Ji Guan, (Spinal Pass) 605
Jie Gu Therapy, 61, 63, 565
Jing Point Therapy, 57, 61-63, 228, 247, 595, 783, 831, 855-858, 890, 920
Jing-Luo, 159, 323
Jing-Shen Bing (Mental Illness), 141
Johnson, Mark, 846
Joy, 75, 99, 129, 178, 189, 193, 404, 428, 429, 431, 460, 469, 488, 508, 615, 619, 872-879
Jue Yin, 57, 160, 222, 501-503, 612, 884
Juice of Jade, 372, 743
Jung, Carl G., 516

K

Kaku, Michio, 665
Karma, 70, 86, 268, 416
Ketheric Matter, 328
Kidney Channel, 81, 107, 154, 184, 187, 194, 206, 208, 210, 219, 237, 706, 814, 819, 820, 850
Kidney Diseases, 426, 710, 713, 766, 811-815
Kidney Divergent Channel, 208, 222, 225
Kidney Fire, 127, 133
Kidney Jing, 133, 137, 170, 184, 260, 319, 320, 812, 815, 816, 838, 847
Kidney Massage, 695, 813, 818
Kidney Qi, 133, 184, 185, 312, 377, 380, 382, 387, 391, 461, 491, 495, 498, 799, 807, 811, 813, 815, 838, 843, 858, 872, 876, 877
Kinetic Communication, 84, 134, 347, 513
Kneading Tiger Palm, 559, 640, 647, 650, 659, 799, 833
Knees, 109, 111, 113, 215, 217, 249, 251, 360-365, 368, 422, 428, 558, 575, 600, 651, 691, 724, 746, 747, 748, 749, 753, 757, 761, 776, 783, 791, 804, 817, 820, 842, 843, 845, 868, 876, 893, 912

L

Lao, Zi, 541
Large Intestine, 71, 78-82, 98, 123, 136, 160, 161, 166, 170, 172-174, 180, 191, 194, 215, 219, 220, 222, 224, 232, 240, 252-254, 257, 276, 281, 182, 312, 339, 366, 378, 382, 387, 501-504, 525, 595, 616, 713, 715, 751, 801-803, 829, 830, 831, 875, 916, 917, 920
Large Intestine Channel, 80, 81, 172, 174, 194, 219, 232, 382, 595, 802, 803, 829
Large Intestine Divergent Channel, 222, 224
Lashley, Karl, 404
Lee, Richard H., 119, 125, 129, 880, 881
Leukocyte, 901, 902
Leukorrhea, 206, 816, 910
Ley lines, 271
Li, Fu Dong, 51
Li, Shi Zhen, 200, 519
Light, 166, 326, 331, 342, 347, 410, 442, 530, 542, 548
Light Meditation, 342, 904, 925, 928
Liu, Bing, 274
Liver, 168, 170, 174, 182, 260, 310, 929
Liver Cancer, 383, 715, 770, 913, 920
Liver Channel, 72, 168-170, 187, 194, 219, 222, 230, 380, 384, 471, 770, 775
Liver Diseases, 710, 712, 766-769, 772
Liver Divergent Channel, 222, 223
Liver Fire, 117, 155, 215, 364, 382, 497, 595, 729, 768, 769, 776, 781, 783, 807-809, 855, 857-859, 863, 871, 890, 906, 907, 911, 912
Liver Massage, 693, 774, 775, 776, 854
Liver Wind, 117, 505, 745, 768, 815, 816, 828, 838, 867, 890
Lo Scroll, 607
Locations of Energetic Blockages, 598
Long Distance Therapy, 530, 532
Lords of the Three Dantians, 84, 85, 86
Lower Burner, 57, 182, 191-193, 204, 211, 322, 387, 504, 505, 510, 598, 610, 670, 671, 700, 729-731, 747, 791, 794, 799, 812, 849, 851, 909, 911, 920
Lower Dantian, 363, 397
Lu, Guo Hong, 51
Lumbago, 362, 421, 670, 726, 814, 816-820, 853
Lung Cancer, 379, 567, 711, 713, 913, 920
Lung Channel, 79, 166, 170, 172, 194, 220, 231, 282, 802, 803, 806-809, 857, 893, 903
Lung Diseases, 155, 172, 360, 492, 731, 801-804, 892, 913

Lung Divergent Channel, 222, 224
Lung Massage, 694
Lungs, 123, 124, 137-139, 155, 161, 166, 168, 170, 172, 174, 178, 184, 191-193, 198
Luo points, 217, 218, 220, 761
Lymphocytes, 684, 685
Lymphocytes, 178, 685, 867, 901
Lymphoma, 915
Lymphosarcoma, 896

M

Maciocia, Giovanni, 194
Macrocosmic Orbit, 189
Macrophages, 684, 685, 867, 898, 901
Magic Square, 200, 270, 607, 608, 610-612, 679, 690
Magnetic Energy, 117, 124, 125, 581
Magnetic Therapy, 57, 58, 126, 856
Malar Flushes, 497
Malignant Tumors, 689, 896, 904, 907, 909, 913-916, 927
Mantra, 89, 406, 424, 701, 792, 882
Marrow, 57, 64, 141, 143, 184, 198, 202, 253, 254, 257, 259, 260, 263, 288, 315, 318, 319, 324, 326, 330, 331, 359, 431, 461, 591, 616, 671, 673, 723, 724, 837, 838, 888
Master and Couple Points, 252
Master Points, 213, 215, 252
Mastitis, 823, 854, 855
Meditation, 282, 288, 294, 307, 332, 376, 407, 426, 430, 431, 448, 520, 527, 532, 546, 547, 572, 573, 574, 591, 622, 623, 669, 688, 718, 882, 900, 904, 905, 912, 917, 928
Meditations for Cancer Patients, 904
Memory, 113, 114, 119, 140, 141, 149, 176, 178, 187, 202, 259, 319, 329, 337, 338, 340, 341, 351, 395, 404, 444, 445, 448, 450, 452, 484, 490, 603, 616-618, 621, 650, 685, 686, 777, 818, 825, 843, 844, 864, 866, 868, 872, 873, 879, 882, 890, 922, 927
Meng, Xian Tong, 548
Menopause, 204, 850, 852, 907, 908
Menoxenia, 854
Menstrual Complications, 852
Menstruation, 204, 206, 257, 274, 363, 590, 591, 794, 849-854
Mental Dao Yin Training, 357, 401, 421, 404, 405, 425
Mental Delusions, 437
Mental Disorder, 438, 508, 677
Mental Restlessness, 214, 250, 471, 504
Meridians, 159
Message (Xin Xi), 80, 134, 139, 142-245, 327, 340, 343, 344, 346, 349, 352, 488, 514-516, 534, 535, 551, 599, 618, 625, 720, 922
Metal Element, 98, 293, 493, 653, 676
Metal Jing, 78
Microcosmic Fire Cycle, 201
Microcosmic Orbit, 120, 157, 189, 199, 242, 260, 293, 294, 304, 365, 366, 424, 432, 547, 558-560, 589, 604, 645-647, 662, 688, 720-723, 726, 728, 733, 784, 812, 817, 831, 832, 839, 845, 854, 856, 858, 866-868, 908, 909, 911, 917, 924, 928
Microcosmic Water Cycle, 201
Middle Burner 57, 87, 139, 170, 191-193, 242, 321, 322, 502-505, 598, 610, 670, 671, 700, 730, 731, 768, 788, 789, 791, 793, 796
Middle Dantian, 131, 132, 137-140, 145-147, 154, 155, 161, 189, 198, 776, 783, 785, 874
Migraine, 54, 64, 394, 599, 829, 830-833, 890
Migrating Qi, 600, 603
Ming Jing (Obvious Power), 48
Ming, Qing Zhu, 50
Mingmen, 560, 590, 605, 670, 785, 812, 813, 842
Mingmen Fire, 127, 133, 368, 705, 706, 811-813, 859, 876
Moon Cream, 288, 688, 775, 785, 809, 819
Morphogenic Field, 315
Mother Element, 309, 401, 495, 496
Moxa Therapy, 57-59, 128, 212, 239, 565, 566, 864
Multiple Personality Disorder, 437, 442, 443, 445, 880
Multiple Sclerosis (MS), 863, 867, 868
Muscle Tendon Channel, 60, 161, 163, 217, 228, 239
Myocarditis, 777
Myss, Caroline, 141
Mysterious Pass, 398
Mysterious Power (Hua Jing), 48
Mysterious Wonders, 588, 589

N

Nader, Ralph, 847
Natural Breathing, 361, 379, 391-393, 397, 651, 700, 701, 718, 719, 752, 783, 809, 845, 854, 868
Necrosis, 774
Nei Dan Shu, 718, 719
Nei Guan, 520, 688
Nei Jing, 355, 611, 881, 886
Neoplasm, 907, 908, 909, 910, 911

Nephritis, 781, 814
Neurology, 50, 567, 836, 863
Neuropeptides, 135, 899
Nine Chambers, 82, 135, 136, 139, 140, 143, 144, 292
Nine Palaces, 296
Nine Stars, 135
Nordenstrom, Bjorn, 128
Ninth Lunar Month, 81
Niu, Yu Hua, 51
Nutritive Qi, 137

O

Objective World, 438
Obstructed Qi, 486, 488, 825, 826, 892
Obvious Power (Ming Jing), 48
Occipital Pass, 605
Old Age, 461, 486, 781, 843
Oncology, 50, 567, 836, 895, 903, 904
One Finger Skill Technique, 637, 638, 639, 658, 930
Opening and Closing the Three Dantians, 152, 170, 239, 322, 359, 377-383, 399, 423, 425, 433, 458, 467, 640,688, 692-697, 729, 731, 737, 824
Opisthotonosis, 424
Orange, 121, 122, 154, 311,526, 857, 915
Organ Dysfunction, 403, 831, 860
Organ Regulation, 62, 63, 751, 752, 797,850
Organ Transplantation, 927
Orifices, 79-81, 92, 159, 187, 292, 378, 491, 672, 728, 811, 815, 823, 838, 839, 858, 881, 886-888
Original Energy (Yuan Qi), 316, 317
Original Essence (Yuan Jing), 316, 317, 318, 331
Original Force, 268, 320
Original Spirit (Yuan Shen), 84, 85, 90, 316-318, 419
Original Yang (Kidney), 321
Original Yin (Kidney), 321
Osteoporosis, 430, 827
Outer Spiritual Barrier, 327
Ovarian Cysts, 64, 601, 734, 766, 857, 858
Ovarian Cysts and Uterine Tumors, 857

P

Palace of Eternal Frost, 279
Palace of Universal Yang, 279
Palpitation, 180, 384, 495, 497, 670, 777, 779, 782, 784, 785, 818, 823, 828, 843, 854, 887
Pancreas, 111, 122, 153, 154, 176, 191, 311, 505, 525 610, 791, 915, 916, 927, 928
Pancreatic Cancer, 689, 915
Pancreatitis, 775, 793
Pang, Dong Hui, 51
Paraplegia, 865
Parenchymal Cells, 774
Parkinson's Disease, 812, 847
Past Life, 344, 516-518, 887
Pediatric, 62, 567, 837-839
Penetrating Wind (Stroke), 863
Perceptual Communication Training, 519
Peribronchial, 806, 808
Pericardium, 71, 74, 79, 122, 140, 160, 161, 166, 178, 187-194, 213, 214, 219,220, 222, 227, 238, 240, 252, 253, 257, 276, 282, 375, 384, 490, 502-505, 664, 706, 778, 784, 785, 875, 889, 925
Pericardium Channel, 74, 187, 189, 194, 213, 220, 238, 375, 384, 504, 706, 778, 784, 785
Pericardium Divergent Channel, 222, 227
Perineum, 83, 109, 110, 111, 125, 127, 132, 133, 135, 145, 147, 148, 149, 151, 154, 191, 200, 201, 205, 206, 221, 284, 294, 295, 331, 332, 342, 363, 365, 393, 422, 575, 700, 722, 724, 748, 752, 814, 886, 911, 912
Peristalsis, 728, 748
Peritonitis, 794
Pernicious Influences, 470
Personal Subconscious Mind, 409, 410, 411,441
Peyer's Patch, 684
Phagocytes, 684, 898, 899
Phantom Embryo, 860, 861
Phantom Organ, 925
Phantom Pain, 929
Phlegm, 473, 492, 495, 504, 505, 602, 667, 669, 671, 683, 702, 703, 744, 781, 788, 802, 805-809, 815, 828, 829
Phlegm Fire, 176, 669, 784, 792, 815, 828, 865, 881
Phobias, 518, 882, 886
Piezoelectric, 129, 263
Pineal Gland, 141, 144, 156, 366, 409, 410, 520, 521, 726, 741
Pink, 426, 779
Pituitary Gland, 155, 366, 392, 394, 440, 520, 521, 635, 723, 832
Po (Corporeal Soul), 74-76, 80, 83-92, 134, 138, 139, 141, 146, 170, 250, 251, 273, 333-335, 338-341, 344, 347, 365, 371, 401, 403, 409, 424, 429, 436, 438, 444, 446, 447, 460, 574, 604, 616, 801, 847, 865, 871, 874, 881, 886
Point Names, 249
Point Respiration, 692, 693, 694, 695, 696, 697
Polarity, 70, 129, 152, 199, 200, 250, 268, 536, 581, 619, 639, 662, 678

Poltergeists, 435,436, 437
Polydipsia, 791
Polyphagia, 791
Polyuria, 791
Portal Hypertension, 774
Postnatal Jing, 137, 316-320, 324, 333, 607, 717
Postnatal Mind, 346, 402, 409
Postnatal Qi, 133, 137, 174, 198, 199, 309, 316, 320, 321, 333, 338, 459, 588, 603, 708, 720, 837
Postnatal Shen, 316, 333-337, 430
Postoperative Therapy, 921, 924
Posttraumatic Stress Disorder, 878, 880
Postural Dao Yin Training, 355, 359, 363
Prayer, 46, 87, 90, 91, 99, 118, 127, 146, 148, 149, 260, 305, 317, 318, 331, 333, 337, 529, 530, 535, 542, 544, 548, 687, 844, 861, 876
Pregnancy, 68, 69, 72-74, 81, 99, 204, 206, 257, 274, 275, 321, 457, 459, 590, 591, 686, 781, 849, 850, 858, 860, 861
Prenatal Jing, 141, 316, 318, 319, 320, 324, 333, 517, 686
Prenatal Jing, 517, 717, 720
Prenatal Qi, 68, 84, 120, 138,198, 199, 260, 279, 316, 317, 320, 321, 333, 723, 837
Prenatal Shen, 316, 333, 335, 337
Preoperative Therapy, 921
Prescriptions, 561, 784, 857, 902
Primary Channels, 71, 83, 84, 127, 133, 148, 159, 160-166, 189, 194-199, 206, 217, 218, 220, 222, 228, 239, 240, 241, 246, 249, 250, 253, 257, 281, 282, 284, 296, 387, 611, 720, 850
Prostate Cancer, 689, 715, 734, 911, 912
Protective Qi (Wei Qi), 132, 191, 215, 322, 323, 324
Psoas Muscles, 893, 894
Psychic Powers, 512
Psychogenic Polyuria, 791
Psychology, 49, 55, 56, 98, 117, 344, 445, 449, 512, 567, 869, 870
Psychometry, 534
Psychoneurosis, 770, 814
Psychosexual Qi Deviations, 438, 600, 603, 606
Psychosomatic, 532, 766, 820, 828, 829
Psychotherapy, 336, 861, 877, 878, 891
Pulling Down The Heavens, 283, 288, 688, 692-696, 700, 702, 711, 724, 725, 761
Pulmonary Emphysema, 803, 806
Pulse, 122, 148, 151, 152, 247, 248, 274, 312, 316, 326, 330, 331, 341, 349, 359, 391, 392, 470-473, 476-481, 494, 501-505, 509, 510, 562, 589, 640, 674, 676, 677, 777, 779, 837, 864, 882, 904, 922, 924
Pungent Foods, 311, 312, 801
Purgation Techniques, 594, 595, 596
Purging, 84, 284, 396, 397, 419, 452, 537, 551-559, 839
Purpura, 669
Pyelonephritis, 818

Q

Qi, Blood and Body Fluid, 463, 511
Qi Compression, 598
Qi Deficiency, 247, 422, 459, 472, 489, 491, 777, 788, 799, 802, 807, 838, 849, 854, 859
Qi Deviation, 419-426, 433, 434, 437, 460, 545, 569, 570, 590, 596, 600, 603, 606, 687, 699, 700, 719, 720, 723, 796, 900
Qi Dysfunction, 768, 779, 789, 803, 813
Qi Extension Techniques, 643, 930
Qi Manipulation, 598, 631, 674, 678, 772, 775, 779, 789, 803, 805, 854
Qi Regulation, 320, 374, 375, 399, 434, 582, 596, 597, 646, 708, 718, 719 824, 845
Qi Reservoirs , 197
Qi Stagnation, 471, 486, 509
Qigong Clinic, 50- 56, 64, 303, 304, 392, 419, 439, 507, 521, 548, 559, 621, 696, 717, 791, 824, 859, 863, 884, 886, 902, 904
Qigong Massage, 65, 543, 622, 623, 643, 673-675, 679, 683, 740, 839, 856
Qihai, 135, 198, 377, 433, 558, 669, 745
Quiescent, 278, 306, 318, 344, 355, 356, 391, 398, 406, 407, 449, 453, 493, 520, 572, 583, 591, 625, 687,689, 768, 781, 785, 779, 833, 857, 900

R

Rachialgia, 814
Radiation, 121, 128, 273, 302, 411, 461, 527, 551, 631, 707, 713, 836, 895, 897, 919-921, 927-929
Rebellious Qi, 208, 325, 432, 483, 487, 488, 594, 671, 745, 826, 857, 908, 920
Reconstructive Qi Therapy, 826
Red 124, 147, 154, 194, 198, 290, 294, 307, 308, 426, 470, 471, 477, 521, 529, 570, 573, 575, 633, 639, 658, 701, 751, 752, 777, 779, 784, 785, 797, 841, 851, 852, 854, 855, 857, 864, 868, 872, 915, 916
Reflexology, 61, 62, 112
Regression, 329, 445, 516-518, 546, 604, 621, 861, 887
Repression, 449, 578, 621, 890
Respiratory Dao Yin Training, 357, 397

Restrictive Cycle, 495, 497
Reverse Breathing, 394, 422, 695, 721, 726
Rhabdomyosarcoma, 896
Rheumatic Heart Disease, 777, 779, 785
Rheumatosis, 785
Rhinitis, 801, 802
Righteous Qi (Zheng Qi), 323, 324, 357, 486, 548, 552, 570, 590, 678, 910
Rigor, 772
Rooting, 380, 430, 432, 546-550, 603, 633, 636, 761
Ross, Elisabeth Kubler, 626

S

Sacred Healing Space, 541, 546, 547, 548, 549
Sadness, 75, 88, 99, 138, 170, 172, 339, 439, 446, 447, 452, 460, 469, 508, 615-617, 844, 874, 875, 878, 888, 892
Sagen, Thea, 927
Saliva, 75, 166, 324, 312, 372, 387, 491, 616, 708, 719, 743, 780
Salty Food, 313
San Bao (Three Treasures), 315
Sancier, Kenneth M., 904
Sarcoma, 896, 915
Sclera, 772, 915
Sea of Blood, 64, 71, 198, 199, 206, 253, 326, 329, 330, 670, 849, 851, 859
Sea of Energy, 326, 889
Sea of Grain and Water, 198
Sea of Marrow, 57, 64, 141, 143, 198, 253, 254, 259, 326, 330, 331, 461, 671, 838, 888
Sea of Qi, 133, 135, 137, 198, 252, 253, 669, 745, 887, 888
Sea of Yang Channels, 201
Sea of Yin Channels, 204
Seat of Emotions, 328
Second Lunar Month, 73
Self-Massage, 377, 386, 387, 388, 596, 687, 691
Self-Regulation Therapy, 57, 64, 65, 687
Seven Corporeal Souls, 75, 80, 83, 86-90, 134, 170, 251, 334, 338, 340, 341, 365, 401, 446, 447, 616
Seven Emotions, 98, 99, 467, 468, 469, 470, 488, 612, 843
Seven Essential Stars, 79, 80
Seven Internal Factors, 460
Seven Orifices, 292
Seventh Lunar Month, 79
Shaman, 529
Shang Ling (Pleasent Soul), 86, 87, 347
Shao Yang, 57, 109, 160, 222, 501-503, 612
Shao Yin, 57, 109, 160, 222, 501-503, 612
Shealy, C. Norman, 141
Shen, Chang, 532
Shengong (Spirit Skill Training), 56, 318, 326, 332, 342, 343, 348, 449, 541, 583
Shening Out, 342, 602, 604
Shimian Point, 907
Shu Point, 193, 249, 250, 251, 370, 611
Si Ming (Administrator of Destiny), 84-86, 90, 92, 347
Silver 84, 85, 151, 288, 307, 337, 348, 349, 431, 451, 452, 624, 905
Sinusitis, 382, 788, 792, 802, 809, 810
Sishencong Points, 149, 342, 548, 839
Sitting Meditation, 242, 337, 360, 785
Six External Factors, 460
Six Functions of Qi, 323
Six Stages, 57, 308, 462, 501, 503, 504, 510
Six Storage Areas, 78, 79
Six Transportations of Shen, 144, 344, 345, 346, 411
Sixth Lunar Month, 78, 79
Skin Zones, 160, 161, 163, 239, 240, 241, 276, 508
Sleep, 89, 91, 99, 166, 178, 210, 211, 212, 254, 274, 317, 323, 333, 335-337, 341, 360, 361, 407, 414, 421, 426, 438, 444, 458, 460, 475, 476, 509, 546, 563, 570, 604, 619, 651, 697, 722, 784, 815, 817, 818, 844, 847, 880, 884, 887, 891, 900
Small Intestine, 79, 98, 122, 136, 146, 160, 168, 172, 174, 178, 180-182, 191, 192, 194, 217, 219, 220, 222, 226, 235, 322
Small Intestine Channel, 180, 182, 194, 215, 219, 235, 779
Small Intestine Divergent Channel, 222, 226
Soaring Dragon Technique, 638
Social Oncology, 903, 904
Solid Organs, 165, 710, 801
Soul Extensions, 85, 90, 347
Soul Loss, 443, 444
Soul Retrieval, 91, 439, 442-450, 453, 577, 602, 606, 623, 633 688, 708, 844
Sound Vibration, 65, 117, 118, 155, 406, 701, 702, 710
Spider Nevus, 774
Spinal Pass, 605
Spiraling Energy, 647-649
Spirit Demon, 438-441, 882
Spirit Oppression, 438, 439
Spirit Possession, 143, 254, 438-440, 884, 885
Spirit Soul, 87, 273, 847
Spiritual Dryness, 582
Spleen, 75, 77-83, 99, 111, 122, 123, 160, 163, 166, 174-178, 184, 191-194, 281, 286, 290, 294, 311,

312, 380, 381, 383, 425, 432, 439, 452, 466, 469, 470, 472-474, 479-498, 503, 505, 509, 522, 525, 615, 616, 656-658, 665, 667, 669, 671, 675, 676, 677, 704, 707, 708, 709, 710, 713, 715, 717, 733, 747, 748, 761
Spleen and Stomach Massage, 797, 798
Spleen Channel, 77, 176-178, 194, 206, 209, 217, 219, 221, 234, 775, 789, 853, 930
Spleen Diseases, 710, 712, 787, 788, 789, 791
Spleen Divergent Channel, 222, 225
Splenomegaly, 694
Spring Equinox, 279, 280, 573
Stacking the Bones, 691, 693-695
Standing Meditation, 360, 399
Static Qigong Training, 355, 356, 695,726
Sternum, 139, 204, 260, 261, 600, 700, 731, 755, 795, 796, 808, 809
Stomach, 78, 79, 82, 83, 174-177, 180, 182, 191-194, 198, 276, 281, 293, 309, 311, 319, 321, 322, 363, 368, 385, 403
Stomach Cancer, 385, 567, 713, 714, 897, 915
Stomach Channel, 78, 108, 174, 176, 194, 217, 219, 233, 325, 504, 522, 776, 788, 793, 795
Stomach Diseases, 425, 713, 787, 792, 793
Stomach Divergent Channel, 222, 225
Stream Points, 251, 253, 370
Stroke, 64, 202, 250, 379, 492, 565, 567, 646, 788, 823, 828,863-865, 890
Subconscious Mind, 118, 134, 336, 344, 345, 403, 407, 409-412, 437-439, 441, 453, 458, 513, 517, 555, 561, 623, 625, 898, 927
Subtle Wonders, 359, 588, 589
Summer Solstice, 279, 280, 573
Sun, Simiao, 143, 309, 884
Super Ego, 621
Surgery, 95, 108, 124, 440, 442, 444, 445, 486, 536, 567, 625, 798, 826, 836, 857, 92-929, 930
Sweet Food, 311, 787
Sword Fingers, 433,636, 637, 652, 653, 659, 772, 784, 805, 807, 810, 819, 820, 826, 829, 855, 882, 923
Symptoms, 457, 461-464, 546, 570, 572, 578, 591, 596, 708
Syndrome, 461-464, 467, 468, 472, 474, 480

T

Tai Guang (Eminent Light), 86, 87
Tai Yang, 57, 109, 160, 222, 378, 501, 503, 612, 865, 884
Tai Yi (Great Divinity), 84-86, 92, 347
Tai Yin 57, 109, 160, 222, 501-503, 612, 884
Taiji Pole, 64, 69-71, 83, 84, 86, 88, 89, 91, 92, 118-120, 122, 125, 131, 132, 135, 144, 145, 147-154, 157, 161, 187, 197, 243, 280, 284, 288-290, 293, 294, 296, 306, 307, 326, 328, 331, 332, 334, 341, 342, 344, 347, 363, 364, 366, 386, 400, 410, 436, 451, 453, 494, 531, 532, 541, 547, 548, 550, 551, 559, 560, 572, 588, 594, 603, 606, 611, 645, 646, 701, 723, 740, 778, 782, 783, 812, 813, 824, 924
Taiji Ruler, 433, 434, 688
Tang, Rongchuan, 111
Tapping Method, 595, 596, 676, 678, 882
Taylor, Kylea, 580
Taylor, Stephanie, 53
Ten Thousand Voices, 408
Ten Wings, 271
Tenth Lunar Month, 82
The Six Stages, 308, 462, 501-504, 510
Third Eye, 92, 120, 142, 144, 332, 350, 410, 451, 520, 521, 531, 558, 576, 632, 726, 805, 831, 865
Third Lunar Month, 74, 86
Three Fires, 127
Three Formations of Cancer Growth, 896
Three Functions of Energetic Points, 247
Three Outer Forces, 132, 267-271
Three Periods of Life 457, 458
Three Treasures of Earth, 301, 313
Three Treasures of Heaven, 273, 297
Three Treasures of Man, 69, 267, 315, 316
Three Wonders, 588
Thrombosis, 863, 865, 866, 907
Thrusting Channels, 120, 148, 293-295, 342, 703, 704
Thrusting Method, 676, 677
Thrusting Vessel, 70, 168, 198, 200, 204, 206,-208, 219, 366, 909, 912
Tinnitus, 202, 215, 235, 254, 260, 741, 777, 781, 782, 784, 812, 814-820, 828, 843, 890
Tongue Positions, 372, 658
Tonification and Purgation Guidelines, 596
Tonification and Purgation Methods, 594
Tonification Techniques, 593
Traditional Chinese Medicine, 45, 47-50, 54, 56-58, 61, 67, 69, 86, 93, 95, 97, 100, 119, 138, 144, 159, 163, 164, 165, 176, 193, 217, 228, 249, 268, 272, 281, 312, 321, 330, 332, 401, 402, 457, 460, 465, 473, 474, 489, 490, 492-497, 509, 537, 548, 603, 673, 686, 772, 773, 775, 781, 791, 796, 843, 851, 852, 858, 859, 866, 867, 870, 881, 884, 895, 897, 906, 914, 929

Transference, 65, 68, 160, 315, 338, 488, 515, 572, 577, 579, 582, 689, 823, 874
Transformation, 48, 56, 91, 92, 95, 98, 99, 117, 119, 128, 132, 133, 137, 145, 172, 176, 182, 191-193, 199, 206, 259, 263, 276, 297, 299, 318, 319, 320-322, 338, 411-413, 415, 416, 419, 445, 453, 454, 457, 486, 489, 490, 491, 494, 496, 498, 502, 505, 513, 530, 532, 534, 554, 561, 580, 627, 721, 837, 844, 849, 859, 861, 904, 926
Transient Ischemic Attacks (TIA), 863
Transpersonal Point, 576, 661
Transportation, 111, 163, 172, 176, 192, 338, 490, 737, 798, 837
Trappier, Arthur, 126
Treating Phobias and Depression, 886
Treating Psycho-Emotional Disorders, 890
Treating Tumors and Cancer, 711, 906, 921
Treatment of Scar Tissue, 929
Trigger Points, 246
Trigrams of the Yi-Jing, 607
Triple Burner Channel, 76, 189, 190, 193, 194, 215, 220, 238, 707
Triple Burners, 57, 76-79, 127, 133, 135, 189-193, 222, 227, 282, 321, 374, 478, 479, 503, 504, 510, 612
Triple Burners Divergent Channel, 222, 227
True Fire 127, 135
True Qi (Zhen Qi), 81, 286, 321-324, 381, 382, 387, 726, 903, 906
True Self, 106, 139, 142, 541, 150, 331, 347, 420, 441, 454, 541, 621
True Spirit, 334
Tui Na, 57, 61-63, 65, 461, 565, 631, 839, 890, 930
Tumor, 53, 55, 327, 381, 395, 421, 440, 532, 688, 710, 711, 715, 855-857, 895-899, 902-907, 910, 913, 914, 916, 919, 922, 927, 928
Turbid Qi (Shi Qi), 191, 282, 288, 303, 391, 397, 419, 487, 488, 505, 536, 552, 569-572, 650, 676, 693-695, 701, 724, 751, 768, 778, 788, 789, 793-796, 802, 803, 812, 851, 925
Twelve Chakra Gates, 151, 152, 156, 157, 722
Twelve Divergent Channels, 222
Twelve Earthly Branches, 156, 157, 268-270, 281, 290, 291, 296, 297, 299, 721
Twelve Entry Points, 252
Twelve Exit Points, 252
Twelve Muscle/Tendon Channel, 163, 228
Twelve Pi Hexagrams, 166, 276, 277
Twelve Primary Channels, 71, 83, 84, 127, 133, 159, 160, 163-166, 189, 194-199, 206, 217, 222, 228, 239-241, 253, 281, 282, 284, 296, 611, 720, 850
Twelve Skin Zones, 163, 239, 240, 241, 276
Twelve Yuan-Source Points, 253
Two Gates of Energetic Points, 246

U

Ulcers, 155, 403, 466, 471, 695, 766, 789, 797, 798, 873
Universal Qi, 321, 380, 587, 737
Upper Burner, 57, 166, 191-193, 321, 322, 425, 491, 504, 505, 610, 651, 700, 729, 730, 791, 803, 816
Upper Dantian, 83, 84, 86, 87, 89, 120, 125, 131, 132, 137, 139-147, 155, 156, 161, 199, 283, 288, 289, 317, 328, 332, 342, 347, 350, 366, 371, 372, 377-379, 387, 388, 433, 451, 453, 513, 518-520, 522, 526, 547, 548, 558-560, 569, 576, 581, 598, 599, 603, 632, 636, 645, 646, 651, 726, 727, 740, 778, 783, 823, 824, 830, 840, 886
Uterine Cancer, 908, 911
Uterine Tumor, 858
Uterus, 69, 72-74, 76-82, 108, 133, 136,146, 366, 459, 471, 486, 505, 591, 667, 715, 908-911

V

Vaginal Discharge, 194, 210, 849-852, 910
Vertigo, 254, 495, 554, 672, 741, 770, 781, 784, 818, 828-830, 867
Violet, 121-123, 128, 155, 156, 526, 527, 633, 897
Virtue, 75, 76, 88, 89, 91, 138, 146, 147, 268, 332-334, 339, 340, 544, 549
Visualization, 49, 65, 87, 89, 243, 336, 343, 348, 356, 371, 403, 411, 443, 448, 449, 519, 545, 547, 554, 555, 561, 625, 683, 688, 701, 767, 770, 824, 861, 876, 877, 904, 929
Vlamynck, Jean Ruth, 50, 53, 54
Void (Wuji), 108, 316, 317, 331, 332, 356, 514-516, 612

W

Walking Therapy, 376, 377, 380-386, 868
Wandering Bi, 603
Water Cycle, 201, 269, 708, 720, 723, 839
Water Element, 98, 133, 251, 268, 293, 493, 653, 676
Weather, 124, 215, 270, 279, 280, 281, 290, 293, 301, 307, 322, 465, 479, 501, 816, 826, 827
Wei Lu Guan (Coccyx Pass), 605
Wei Qi (Protective Qi), 48, 57, 64, 126, 132, 137, 140, 145, 149, 151, 164, 322, 324-329, 549, 551, 552, 554, 559, 572, 575, 612

White, 46, 104, 120, 122-124, 137, 138, 147, 148, 206, 210, 241, 260, 288, 293, 294, 306, 307, 311, 327, 331, 338, 406, 412, 414, 415, 425, 431, 439, 451, 452, 471-473, 476, 492, 497, 501, 505, 508, 520-523, 529, 531-534, 536, 547, 573-576, 589, 617, 624, 639, 658, 684, 685, 701, 713, 719, 726, 803, 804, 806, 851-853, 855, 861, 898, 901, 904, 905, 911, 919, 920, 922, 925, 926
Willpower (Zhi), 151, 338, 340, 341, 348, 574, 847
Wind Bi, 603
Wind Cold, 217, 464, 467, 472, 669, 801, 802, 805, 807, 809, 816, 817, 829
Wind Damp, 464, 802, 805, 920
Wind Heat, 217, 467, 472, 505, 669, 670, 798, 801, 802, 805, 809
Wind Phlegm, 492, 828
Wind Stroke, 202, 492, 788, 823
Window of the Sky Points, 254, 886, 887
Windy Breathing Method, 392, 394, 396, 768, 779, 789, 813
Wong, Her Yue, 708
Wood Element, 98, 100, 293, 493, 556, 653, 676, 914
Wood Jing, 79
Worry, 64, 75, 88, 99, 101, 104, 108, 129, 138, 172, 178, 348, 403, 404, 427, 429, 432, 439, 460, 488, 508, 603, 615, 616, 619, 794, 796, 798, 818, 850, 855, 859, 873, 874, 876, 878, 892, 903, 907
Wu Guan (Five Passes), 604
Wu Huo Breathing Method, 394
Wu Jing Shen (Five Essence Spirits), 80, 84, 90, 141, 409, 443, 57, 847, 860, 870, 871
Wu, Ju-Tong, 504
Wu Ying (Without Essence), 84, 86
Wu Zang (Five Yin Organs), 294, 572, 573, 574, 688
Wuji, 45, 85, 132, 144, 148, 149, 267, 316, 317, 332, 344, 345, 356, 371, 398, 415, 514-516, 520, 633

X

Xi Yuan Hospital of Beijing China, 51, 52, 67, 303, 406, 439, 499, 566, 627, 717, 898
Xia Tao Kang (Below Healthy Peach/Life), 84-86, 92, 347
Xiphoid Process, 109, 111, 154, 600, 772, 808, 809
Xu, Hongtao, 52

Y

Yan, De-xin, 688
Yang Channels, 71, 72, 160, 161,165, 166, 172, 174, 180, 182, 189, 558, 595, 651, 690, 734, 745
Yang Deficiency, 472, 480, 495, 502, 777, 781, 783, 785, 788, 812, 821, 823, 851, 876
Yang Fire, 103, 137, 200, 242
Yang Heel Vessels, 70, 71, 107, 197, 198-200, 210-212, 215, 251, 259, 377, 381
Yang Linking Vessels, 70, 71, 108, 197, 200, 213-215, 251
Yang Ming, 57, 160, 222, 501, 503, 612
Yang Organs, 197, 198, 222, 242, 247, 253, 254, 257, 837, 870
Yang Polarity, 152, 268
Yang Shen Disturbances, 430
Yang Yao, 166, 276-278
Yao Cycles, 166, 276, 278
Yao Lines, 109, 612
Ye, Tian Shi, 502
Yellow, 49, 68, 99, 106, 122-124, 136, 139, 140, 147, 154, 193, 198, 241, 319, 355, 386, 429, 430, 431, 526, 529, 558, 560, 572, 598, 600, 607, 624, 645, 646, 657, 728, 768, 775, 779, 782-785, 787, 789, 790, 793, 797-799, 806, 819, 828, 829, 832, 851, 853, 854, 868, 905, 914-916
Yellow Emperor, 49, 68, 99, 106, 193, 198, 319, 355, 429, 529, 572, 787
Yi (Intent), 75, 80, 84-86, 92, 109, 139, 141, 176, 333-335, 337, 338, 340, 341, 347, 401, 402, 407, 411, 425, 427, 429, 573, 607, 616, 636, 787, 847, 873
Yi-Jing (Book of Changes: I-Ching), 268, 271
Yin Channels, 71, 160, 161, 165, 168, 170, 176, 178, 184, 187, 213, 214, 223, 251, 690, 868, 884
Yin Deficiency, 204, 242, 474, 480, 488, 490, 491, 495, 502, 505, 768, 775, 776, 778, 785, 788, 791, 792, 796, 797, 802, 808, 809, 812, 828, 853, 881, 913
Yin Essence, 200, 257, 278, 285, 321,859
Yin Heel Vessels, 71, 107, 108, 199, 210-212
Yin Linking Vessels, 70, 71, 108, 200, 213, 214
Yin Organs, 250, 253, 257
Yin Shen Disturbances, 430
Yin Tang (Third Eye Point), 120, 131, 143, 144, 332, 350, 451, 520, 521, 531, 632, 636, 672, 726, 733, 831, 832, 833, 840, 865, 866, 883
Yin Yao, 277-279
Ying Qi (Nutritive Qi), 57, 64, 137, 163, 166, 191, 193, 322, 324, 326, 329, 330, 491, 502-504, 676, 678, 679, 747, 888
Yu Jing (Hidden Essence), 86, 87, 347
Yu Vessels, 213, 215

Yu Zhen Guan, 605
Yuan Jing, 133, 316-318, 324, 331, 333, 633
Yuan Qi, 70, 133, 135, 137-139, 191, 197, 199, 201, 204, 252, 253, 279, 316-324, 333, 368, 371, 383, 387, 391, 398, 466, 487, 560, 588, 590, 665, 667, 688, 720, 724, 726, 733, 737, 749, 811, 814, 845, 866, 897, 898, 902, 903, 906
Yuan Shen, 84-86, 90-92, 118, 138, 142, 187, 201, 259, 268, 316-318, 333, 335, 337, 338, 343, 344, 345-347, 371, 401-404, 408-410, 419, 427, 440-451, 514, 528, 633, 723, 726

Z

Zhang, Zhong Jing, 501
Zhao, Joanna, 50, 54
Zhao, Xianke, 127
Zhen Qi (True Qi), 81, 286, 322, 324, 903
Zheng Qi (Righteous Qi), 282, 323, 324
Zheng, Zhan Ding, 404, 518, 524
Zhi (Will), 75, 76, 79, 80, 85, 90, 102, 118, 139, 141, 151, 187, 201, 333-335, 338, 340, 341-347, 811, 847, 876
Zhi Shen (Postnatal Spirit), 85, 90, 201, 333, 335, 343-347, 401-404, 408-412, 427, 446
Zhi, Zhuan, 699
Zhong Qi (Center Qi), 321, 322, 324
Zhou Qi (Turbid Qi), 321, 324
Zhou, Qianchuan, 49, 99
Zong Qi (Gathering Qi), 80, 137, 138, 191, 322, 324

ABOUT THE AUTHOR

- Dean of Medical Qigong Science - Five Branches Institute, College and Clinic of Traditional Chinese Medicine (U.S.A.)
- Director of Medical Qigong Clinic - Five Branches Institute, College and Clinic of Traditional Chinese Medicine (U.S.A.)
- Director and Founder of the International Institute of Medical Qigong - (United States, Canada, South Africa, and Europe).
- Professor of Medical Qigong Science and Philosophy - Licensed by the Beijing Western District Qigong Science and Research Institute (China)
- Physician in Charge of Traditional Chinese Medicine - Licensed by the Beijing Bureau of Scientific Technology (China)
- Doctor of Medical Qigong and Anmo Therapy - Licensed by the Beijing Western District Qigong Science and Research Institute (China)
- Graduate Degree in Medical Qigong Therapy - Medical Qigong College - Hai Dian University of Beijing, (China)
- Council Board Member (United States Representative)- World Academic Society of Medical Qigong, (China)
- Council Board Member (Medical Qigong Committee)- National Qigong Association (U.S.A.)
- Ambassador of Chinese Medical Qigong Therapy to North America - Commissioned by The World Health Organization Collaborating Center for Traditional Chinese Medicine, Beijing, China (sponsored by the United Nations)


Dr. Jerry Alan Johnson

MEDICAL BACKGROUND

Dr. Jerry Alan Johnson is one of the few internationally recognized non-Chinese Grand Masters, practicing doctors and Director/Professors of Medical Qigong Therapy. Having studied for more than twenty-eight years, he is recognized both in China and the West as America's leading authority on Medical Qigong therapy. Dr. Johnson is licensed as a Doctor of Traditional Chinese Medicine (D.T.C.M.) in Beijing, China, and has served with national and international committees to promote and encourage the practice of Medical Qigong.

Dr. Johnson began his initial training in energetic medicine in 1972. He started his formal clinical studies of Traditional Chinese Medicine in Monterey, California in 1974, where he focused his studies on acupuncture, herbology, Medical Qigong therapy, traumatology and Chinese massage. After receiving certification as an Acupuncturist and Herbalist from an 1978-81 internship, Dr. Johnson operated clinics in Colorado Springs, Colorado (1981-84), working as a consultant and associate in Acupuncture and Medical Qigong Therapy to Western Medical Doctors and Chiropractors.

In 1993 Dr. Johnson furthered his clinical studies at the China Beijing International Acupuncture Training Center, and at the Acupuncture Institute of China, Academy of T.C.M. He was the first foreigner from the Acupuncture Institute invited to treat patients in the Medical Qigong Clinic at the Xi Yuan Hospital of T.C.M. (featured in Bill Moyer's special "Healing and the Mind"). There he interned as a Doctor of Medical Qigong Therapy, specializing in the treatment of cysts, tumors, and kidney dysfunctions.

Dr. Johnson also interned as a Doctor of Anmo Therapy at the Orthopedic Traumatology Clinic of the Hu Guo Si Hospital of T.C.M. (in Beijing, China) specializing in Chinese bone-setting, traumatology and tissue manipulation. His training includes Neuro-muscular Therapy, Psychophysical Integrational Therapy, Advanced Visceral Manipulation and Advanced Cranio-Sacral Therapy from the Milne Institute of Healing Arts.

In 1995 Dr. Johnson received his Graduate Degree in Medical Qigong Therapy from the Medical Qigong College - Hai Dian University of Beijing, China, and was licensed as a Doctor of Medicine Qigong. The Beijing Western District Qigong Science and Research Institute awarded Dr. Johnson a license as "Professor of Medical Qigong Science and Philosophy" after his completion of both academic doctoral thesis, and numerous clinical field studies (1995).

In 1997 Dr. Johnson became the first Qigong doctor allowed to assist in surgery at the Community Hospital of the Monterey Peninsula, in Carmel, California, where he continues to work closely with Western Doctors.

In 1997 Dr. Johnson was elected to the Board of Directors of the National Qigong Association-USA. In 1998 he was appointed the Chairman of the Medical Qigong Committee, responsible for establishing the guidelines and national standards for Medical Qigong practitioners working in clinical settings.

In 1998 Dr. Johnson was elected to the Board of Directors of the World Academic Society of Medical Qigong, centered in Beijing, China, and serves as one of four Council Board Members that represent the United States at the World Conferences. Also, in 1998, his clinical status was elevated to the position of "Physician in Charge of Traditional Chinese Medicine" from the Beijing Bureau of Scientific Technology, in China.

In the Spring of 1999 Dr. Johnson accepted the position of Dean of Medical Qigong Science from the Five Branches Institute, College and Clinic of Traditional Chinese Medicine, in Santa Cruz, California. Dr. Johnson developed a Masters Program which includes instruction and training from his textbook entitled: *Chinese Medical Qigong Therapy, A Comprehensive Clinical Text.* The course also includes the specialization of specific Medical Qigong Therapies such as Pediatrics, Geriatrics, Gynecology, Neurology, Psychology, Oncology and Surgery.

In the Spring of 2000 Dr. Johnson established within the Five Branches Institute the first Medical Qigong Clinic at a T.C.M. College in North America, facilitating the combined use of acupuncture, herbs and Medical Qigong therapies to the general public.

Dr. Johnson is also the founder and director of the International Institute of Medical Qigong, in Monterey, California, and has designed a three-year Medical Qigong program which has been implemented by several colleges and Medical Qigong Institutes throughout the United States, Canada, Europe and South Africa.

Dr. Johnson serves as the official representative for North America for The World Health Organization Collaborating Center for Traditional Medicine, sponsored by the United Nations for the promotion and development of Traditional Chinese Medical Qigong Therapy.

An active member of the World Academic Society of Medical Qigong, Dr. Johnson was a key speaker at the 1996 Third World Conference on Medical Qigong, held in Beijing, China, the 1997 Second World Congress on Medical Qigong held in San Francisco, California, the First American Qigong Association Conference, held in San Francisco, California, the 1998 Fourth World Conference on Medical Qigong, held in Beijing, China, and the 1999 National Qigong Gathering held in Baltimore, Maryland. He has lectured and taught many seminars at The American College of Traditional Chinese Medicine in San Francisco, California, The University of California San Francisco, The Qigong Institute of Menlo Park, California, The International Training Center at San Diego State University, The Monterey Institute of International Studies, The Asilomar Conference Center of Pacific Grove, California, as well as several other colleges, institutes and hospitals throughout North America.

MARTIAL ARTS BACKGROUND

Dr. Johnson is also internationally renowned as a Shifu (Master Instructor) of several Chinese Martial Arts Systems, having studied the martial arts for over 34 years.

In Shaolin, he has studied Praying Mantis, Hung Gar, Wing Chung, and Mi Zongquan Shaolin styles of fighting, weapons and Martial Qigong, and is a certified Master Instructor in Mi Zongquan Shaolin, teaching through the authority of the Mi Tsung-I Northern Shaolin Federation of Taiwan.

In Baguazhang he has studied several schools of fighting, including the Yin Fu, Cheng Ting-Hua, Liu De Kuan, Fu Zhen-Song, and the Chang Zhao-Dong Styles of combat, weapons and Martial Qigong. He is a certified Master Instructor in Chang Zhao-Dung Baguazhang, teaching through the authority of the Ching Yi Baguazhang Association, the Hsiao Mien Hu Martial Arts Association, and The Canadian Martial Arts Society.

In Taijiquan, Dr. Johnson has studied several schools of fighting, including the Yang Pan-Hou, Yang Chien-Hou, and Chen Fa Ke styles of combat, weapons and Martial Qigong. He is a certified Master Instructor as well as a "Twentieth Generation Inner-Door Disciple" from Feng Zhi Qiang's Chen Style Taijiquan, teaching through the authority of the Beijing Martial Arts Association and the Beijing Chen Style Taijiquan Association of China. He is also a certified Master Instructor in the Yang Style Taijiquan, teaching through the authority of the Tai Chi Chuan Federation of Taiwan.

Excelling in "Empty Hand," as well as "Weapons Fighting" from both the Shaolin and Wudang Martial Arts Systems, Dr. Johnson competed regularly in the tournament circuit and was titled: 1980 Southbay National Champion, 1982 Tournament of Fighters Champion, 1982 Universal Tae Kwon Do/Tang Soo Do Invitational Grand Champion, 1983 Colorado National Kung Fu Champion, 1983 Tournament of Fighters Grand Champion, 1984 Colorado National Kung Fu Champion, and the Tournament of Fighters Kung Fu Champion in 1984, when he retired from competition.

In addition to his own championships, many of Dr. Johnson's students also went on to compete at the national level, bringing several championship titles to the school. Like their teacher, Dr. Johnson's students excelled in free-form fighting, Taiji Push-hands and Chinese Gongfu forms, as well as weapon competitions.

In 1986, the state of California issued Dr. Johnson teaching credentials, allowing him to teach adult education classes in Taijiquan and Baguazhang. Since then, he has been a council member of the International Baguazhang Research and Teachers Exchange, and served as a judging official and member of the Executive Committee of the U.S. Chinese Kuo Shu Federation, as well as a coaching official, national certifier and council member of the Amateur Athletic Union (affiliated with the U.S. Olympics). Dr. Johnson also participated on the Board of Advisors for the United States of America Wushu-Kung Fu Federation, and is a member of the International Congress of Oriental Medicine and Martial Arts. He was also a standing member of the North American Chinese Martial Arts Federation.

Author and Publisher:

Dr. Johnson was a contributing author, selected to write the Medical Chi Kung section, for the book *The Complete Illustrated Guide to Chi Kung*, a cooperative project between Element Books (UK) and author James MacRitchie. Dr. Johnson was also one of the selected contributing authors for the book *Qigong-Essence of the Healing Dance*, a cooperative project between P.B.S. and Documentary Producer/Director Garri Garripoli.

Dr. Johnson has been interviewed many times on local radio programs, and has been featured in numerous local and international newspapers and magazines, including: *Newsweek Magazine* "The International Addition," *The World Medical Qigong Quarterly*, *Qi-The Journal of Traditional Eastern Health & Fitness*, *The Empty Vessel Magazine*, *Pent-*

house Magazine, Self Magazine, Billboard Magazine, The Mystical World of Chinese Martial Arts, Inside Kung Fu Magazine, Combat Karate Magazine, Internal Arts Magazine, Black Belt Magazine, The Pa Kua Chang Journal, and Inside Karate's Master Series Magazine.

Televised specials include: *NBC News* "Dateline," *CBS/Channel 46* "Eye on America," featured in a documentary on Medical Qigong filmed for the *"Discovery Channel,"* featured in a documentary on Medical Qigong filmed for SBS "Qi-into the world of the unknown," and *K.P.B.S.* "Managing Health and Productivity; New Approaches In Technology," as well as *The David Letterman Show.*

In 1988, Dr. Johnson created and published a six level "Pa Kua Chang Chi Kung Correspondence Course," and in 1989, founded the "Pa Kua Chang News Letter," which later became known as the "Pa Kua Chang Journal," and was distributed worldwide. Dr. Johnson has written and published five books on martial arts entitled:

- The Secrets of the Eight Animals,
- The Masters Manual of Pa Kua Chang,
- Classical Pa Kua Chang Fighting Systems and Weapons,
- The Essence of Internal Martial Arts Volume 1: Esoteric Fighting Techniques and Healing Methods, and
- The Essence of Internal Martial Arts Volume 2: Energy Theory and Cultivation.

From 1984 to 1986, Dr. Johnson produced and directed six Baguazhang instructional videos entitled:

- The Eight Animal School of Pa Kua Chang
- The Original Form of Pa Kua Chang
- The Eight Circular Pa Kua Staff
- The Eight Circular Pa Kua Broadsword
- The Dragon School of Pa Kua Chang, and
- The Fighting Techniques of Pa Kua Chang.

In 1994 he was featured in two videos on Taijiquan, as well as one Qigong video narrated by actor John Saxon, entitled:

- Tai Chi-The Empowering Workout,
- Power Tai Chi- Total Body Workout, and
- Chi Kung-The Healing Workout,

He additionally created two Meditation CD / cassette tapes with composer John Serri entitled:

- Tai Chi Meditation - [1] Life Force Breathing, and
- Tai Chi Meditation - [2] Eight Direction Perception.

Dr. Johnson's latest project includes 10 Medical Qigong videos which contain instructional information and training from his current textbook *Chinese Medical Qigong Therapy, A Comprehensive Clinical Text,* entitled:

- Gathering Energy from Heaven and Earth,
- Stationary and Dynamic Medical Qigong Posture Training,
- Treating Patients with Medical Qigong Therapy (Vol.1),
- Treating Patients with Medical Qigong Therapy (Vol.2),
- Medical Qigong Energy Techniques and Qi Emitting Methods,
- Medical Qigong Invisible Needle Technique, Five Element Qigong Massage, and Energetic Point Therapy,
- Medical Qigong Healing Sound Therapy and Prescriptions,
- Treatment of Internal Organ Diseases with Medical Qigong,
- Treatment of Cysts, Tumors, and Cancer with Medical Qigong Therapy, and
- Soul Retrieval.

Dr Johnson's books, video tapes, meditation C.D.'s and cassette tapes have been translated into other languages and are currently being sold around the world. They have been featured in *Publishers Clearing House, Columbia House, Borders Book and Music Co., The Book of the Month Club, T'ai Chi Magazine, Century Martial Arts, Qi-The Journal of Traditional Eastern Health & Fitness, The Complete Guide to Exercise Videos, the Double Day Book and Music Co, and Direct TV (both in the United States and Japan).*

For more information about the author, the reader can turn to his web page at:

www.qigongmedicine.com

ADDITIONAL BRANCHES OF THE INTERNATIONAL INSTITUTE OF MEDICAL QIGONG

The following is a list of graduating students and instructors, as well as national and international directors of the International Institute of Medical Qigong.

BRANCHES WITHIN THE UNITED STATES

Jerry Alan Johnson, Ph.D.,D.T.C.M.,
D.M.Q. (China)
Director and founder of the International
Institute of Medical Qigong
(Main Branch)
P.O.Box 52144
Pacific Grove, California 93950 USA
Phone: (831) 646-9399
Fax: (831) 646-0535
E-Mail: drjerryalanjohnson@eatrhlink.net
Web Page: www.qigongmedicine.com

Seth Lefkowitz, D.C., D.M.Q. (China)
Director of the International Institute of
Medical Qigong
(South San Francisco Branch)
351 South Baywood Avenue,
San Jose, California 95128 USA
Phone (408) 243-1565
Fax: (408) 243-1568
E-Mail: naturespath4me@yahoo.com

Arnold Tayam, D.M.Q. (China)
Director of the International Institute of
Medical Qigong
(San Jose/Silicon Valley Branch)
c/o The Longevity Center
P.O. Box 26712
San Jose, California 95159-6712 USA
Phone (408) 295-5911
Fax: (408) 971-0136
E-Mail: chi@longevity-center.com
Web Page: www.longevity-center.com

Jean Ruth Vlamynck, L.Ac., Dipl.Ac.,
M.T.C.M., M.Q.T.
Director of the International Institute of
Medical Qigong
(Santa Cruz Branch)
257 B Center Ave.
Aptos, California 95003 USA
Phone: (831) 689-9093
Fax: (831) 689-9094
E-Mail: jeanhere@bigplanet.com
Web Page: www.relaxationresources.com/
assoc/jeanv.html

Dale M. Hopkins, M.Q.P.
Director of the International Institute of
Medical Qigong
(Northern Santa Cruz Branch)
24345 Loma Prieta Ave.
Los Gatos, California 95033
Phone: (408) 353-2566

Wendy Lang, M.Q.P.
Director of the International Institute of
Medical Qigong
(Marin County Branch)
12 Skylark Dr. Apt 33
Larkspur, California 94939
Phone: (415) 924-7883
E-Mail: wendylang@altavista.com

Andy Balestracci, M.Q.P., and
Linda MacElwee, M.Q.P.
Director of the International Institute of
Medical Qigong
(Mendicino Branch)
P.O. Box 43
Philo, California 95466
Phone: (707) 895-9115

Geoffery Greenspahn, M.Q.T.
Director of the International Institute of
Medical Qigong
(Los Angeles Branch)
Los Angeles, California
Phone: 310-775-5022
E-Mail: rumblej@hotmail.com

Todd Gedryn, M.Q.T.
Director of the International Institute of
Medical Qigong
(San Francisco Branch)
c/o Qigong Institute of North America
9 White Tail Lane
Monterey, Ca 93940 USA
Phone (408) 221-0628
Fax: (831) 373-8149
E-Mail: todd@qigonginstitute.net
Web Page: www.qigonginstitute.net

Matthew B. Weston, M.Q.T.
Director of the International Institute of
Medical Qigong
(Big Sur Branch)
c/o South Coast Qigong Center
P.O. Box 223373
Carmel, California 93922 USA
Phone (831) 626-3347
E-Mail: qigongr@mbay.net

Ted Cibik, M.Q.P.
Director of the International Institute of
Medical Qigong
(Pennsylvania Branch)
c/o Inner Strength Inc.
R.D. #4 Box 64
Leechburg, Pa 15656 USA
Phone (724) 274-0586
Fax: (724) 845-7739
E-Mail: ted@inner-strength.com
Web Page: www.inner-strength.com

Judith "Lacy" Storey, L.Ac.
Director of the International Institute of
Medical Qigong
(Colorado Branch)
Breckenridge, Colorado USA
Phone (303) 274-0586
E-Mail: dakini@colorado.net

Ellie Christianson, L.L.C., M.Q.P.
Director of the International Institute of
Medical Qigong
(Arizona Branch)
481 West Greys Road
Tuson Arizona 85718
E-Mail: ellie@MIOBI.com

Donald Mead, M.Q.P.
Director of the International Institute of
Medical Qigong
(Georgia Branch)
1008 Courtenay Drive NE
Atlanta, Georgia 30306-3330
Phone: (404) 873-6557
E-Mail: dmm10@mindspring.com

Connie Comer, M.Q.P.
Director of the International Institute of
Medical Qigong
(Oregon Branch)
1427 N.W. 23rd Ave.
Portland, Oregon 97210
Phone: (503) 226-6822
E-Mail: conniecomer@hotmail.com

INTERNATIONAL BRANCHES

Cynthia McMullen, C.M.T., M.Q.P.
Director of the International Institute of
Medical Qigong
(Alaska Branch)
3713 E. 19th Ave.
Anchorage, Alaska 99508
Phone: (907) 279-0135
E-Mail: touchoftaoCM@netscape.net

Robert C. Bawol, M.Q.P.
Director of the International Institute of
Medical Qigong
(New Mexico Branch)
1145 N. Alameda
Las Cruces, New Mexico 88005
Phone: (505) 647-8827
E-Mail: arrow@HTG.net

Shirley Norway
Director of the International Institute of
Medical Qigong
(Illinois Branch)
P. O. Box 1349
Fairfield, Illinois 52556
Phone: (515) 472-8404

Andy James, M.Q.T.
Director of the International Institute of
Medical Qigong
(Canadian Branch)
c/o Canadian Practitioners' Association
of Asian Medicine
Toronto, Canada M4K IK4
Phone: (416) 463-9360
Fax: (416) 463-0045
E-Mail: emerge@powerofbalance.com

Richard Garnier
Director of the International Institute of
Medical Qigong
(Europe Branch)
c/o Chariot D'or
Villa Samicky 171 che du Suveran
06140 Vence , France
Phone/Fax: 33 493 58 51 20
E-Mail: chardor@club-internet.fr

Susan Vial, M.Q.P.
Director of the International Institute of
Medical Qigong
(South Africa Branch)
P.O. Box 235
Magaliesburg, 2805 Gauteng
South Africa
E-Mail: saspect@iafrica.com

THE 100 DEADLIEST KARATE MOVES



BY DR. TED GAMBORDELLA
5TH DAN

Dedicated to the memory of
DEMETRIUS HAVANUS (The Golden Greek).
I have lost a good friend,
and the arts have
lost a great teacher and fighter.
We will all miss you, very much.

THE 100
DEADLIEST
KARATE MOVES



Introduction

I wrote The 100 Deadliest Karate Moves as a practical text for the serious martial arts student or teacher. It is soley meant to be used as a reference in practice, and I do not condone or suggest that any of the techniques found in this book be used in the street against another man, unless, of course, the defender's life is in immediate danger. The techniques found in this book were not devised by me, and most are common knowledge to the average student.

What I have attempted to do is to compile moves in such a manner that one can study the kicks and blows and then can see the exact technique and target area, with the resulting damage to the attacker. I am assuming that the reader will have an adequate martial arts background so that he knows the basic stances and strikes. Therefore, I am showing only the strike or kick to the target area, without reference to body stances or other basics. All blows and kicks must be delivered with the utmost speed and power in order to be effective.

In a final chapter I show examples of street applications of some of the techniques. This is meant as a training section in order to get the student or teacher to begin to think of how the strikes and blows might be applied in a life-or-death situation.

Basic Strikes

The Front Snap Kick

Lift the knee of the kicking leg as high as possible in front of the body,
be sure to keep the fists tight, and the toes turned upward to prevent damage to the foot.


THE 100
DEADLIEST
KARATE MOVES
BY DR. TED GAMBORDELLA
5TH DAN



Snap the kick out directly in front of the body to the target area, keep the other leg slightly bent for balance, and be sure to thrust with the hips for speed and power.



Kicking Techniques

The Front Heel Thrust

This kick is similar to the front snap, but uses the heel for the striking area, and it has more power and penetration. The kicking technique is the same. However, you thrust more directly forward with this kick, and be sure to lock the leg for the full power to the heel.





The Front Snap-High

This kick requires a lot of flexibility and balance if any power is to be produced. It is extremely effective for areas of the face, throat, and chin.



The Side Kick

This is one of the most powerful kicks and is used for most areas of the body. Lift the kicking leg as high as possible to the front of the body, curling the toes of the foot inward for protection.



Snap, and thrust the kick directly to the side and the target area; be sure to snap the hips into the kick for full power. The heel, or side of the heel, is the striking area. Keep the arm above the leg, down the side of your body to protect your ribs. This is probably the most devastating kick and the hardest to stop when done correctly.



continued…



The Side Kick continued

Bring the leg up about hip high, directly in front of the body. Look behind over your shoulder to the target area.



Thrust directly back with speed and power, snapping the hips for more power, and strike the heel of the foot into the desired area.






THE 100 DEADLIEST KARATE MOVES

The Knee

This kick is used when the attacker is too close to use an extension kick and is quite capable of stopping the largest of men. Raise the knee directly up with power and speed to the striking area.



You get more power by thrusting or snapping up with the hips on this kick.



Vital Points & Kick Attacks

All of the kicks demonstrated in this section will do permanent damage to an attacker's body, if done with appro- priate speed, power, and accuracy. We are shown demonstrating the vital points and the best kick attack for each one. Beneath the illustration, you will find the damage and the results that you can expect from using each kick against a would-be attacker.

One: Front Snap to the Shin



Damage: broken shin, bruised shin.
Result: attacker unable to stand or to continue to fight.

Two: Front Heel Kick to Shin



Damage: severely bruised or broken shin.
Result: attacker will be unable to stand or to continue fight.



THE 100
DEADLIEST
KARATE MOVES

Three: Front Snap to Kneecap



Damage: dislocated knee, broken kneecap, sprained, torn ligaments, tendons.
Result: attacker unable to stand or to continue fight; will require surgery to correct.

Four: Front Heel Kick Across Kneecap



Damage: dislocated knee, broken kneecap, torn tendons and ligaments.
Result: attacker unable to stand or to continue to fight; will require surgery to correct.



Five: Front snap to tailbone



Damage: broken coccyx, extreme pain.
Result: attacker unable to stand or to sit, will require medical attention.

Six: Front Snap to Lower Back



Damage: broken back, bruised kidneys, extreme pain.
Result: attacker may be permanently crippled; requires medical attention immediately.





Seven: Front Snap to Ribs



Damage; loos of breath. broken ribs
Result: attacker will be unable to breathe for several minutes; will fall down.

Eight: Front Snap with Heel to Chin



Damage: broken jaw, crushed jaw, teeth knocked out, loss of consciousness.
Result: attacker will be knocked out for several minutes.



THE 100
DEADLIEST
KARATE MOVES

Nine: Front Snap to Throat



Damage:crushed throat, smashed Adam's apple.
Result:attacker will die, usually, unless given immediate medical attention.

Ten: Front Snap to Solar Plexus



Damage: broken or bruised ribs, loss of breath, extreme pain.
Result: attacker will be unable to breathe for several minutes.



Eleven: Front Snap with Heel to Pelvis



Damage: crushed testicles, broken pelvis, internal damage to groin area.
Result: attacker will be unable to stand and may suffer per- manent, crippling injury.

Twelve: Front Snap with Shin Area to Testicles



Damage: crushed testicles, cracked pelvis.
Result: attacker will be unable to stand; will usually require surgery, and often will be permanently crippled.

Thirteen: Kick to Knee



Damage: dislocated knee, torn ligaments and tendons.
Result: attacker will be unable to stand or to continue to fight; will require surgery to correct knee.

Fourteen: Side Snap Kick to Ribs



Damage: broken ribs, possible internal damage, lung damage
Result: attacker will be unable to stand or breath.



Fifteen: Side Kick to Throat



Damage; crushed throat, broken Adam's apple.
Result: attacker will die unless given immediate medical attention.

Sixteen: Side Kick to Jaw



Damage: broken jaw, loss of consciousness.
Result: attacker will be knocked out for several minutes, require medical attention.



THE 100
DEADLIEST
KARATE MOVES

Seventeen: Side Kick to Face



Damage: broken nose, teeth knocked out, broken jaw, loss of consciousness.
Result: attacker will be knocked out for several minutes.

Eighteen: Side Kick to Chin



Damage: teeth knocked out, brokne jaw, loss of conciousness.
Result: attacker will be knocked out for several minutes.

THE 100
DEADLIEST
KARATE MOVES

Nineteen: Side Kick to Heart



Damage: crushed or cracked chest, broken sternum, possibly stopped heart.
Result: attacker will be unable to breathe for several minutes; may die.

Twenty: Side Kick to Back of Head



Damage: broken neck, loss of consciousness.
Result: attacker will be knocked out, usually permanently crippled; may die.



Twenty-One: Roundhouse Kick to Kidneys



Damage: bruised kidneys, possibly broken back, extreme pain.
Result: attacker will usually fall down, have internal damage, and be in pain for weeks.

Twenty-Two: Roundhouse to Side of Head



Damage: brokenjaw,teethknockedout,eardrumbusted,loss of consciousness.
Result: attacker will pass out, lose balance and ability to fight.



THE 100
DEADLIEST
KARATE MOVES

Twenty-Three: Roundhouse to Temple (toes directly contact temple)



Damage: cracked skull, nerve damage, blood stoppage to brain.
Result: attacker will be knocked out, may go into a fit or delirium.

Twenty-Four: Roundhouse to Side of Neck



Damage: bruised or broken neck, extreme pain, loss of blood to brain.
Result: attacker will pass out for several minutes.



THE 100
DEADLIEST
KARATE MOVES



Twenty-Five: Roundhouse to Solar Plexus



Damage: cracked or broken ribs, loss of breath, possible internal damage.
Result: attacker will be unable to stand or breathe for several minutes.

Twenty-Six: Roundhouse to Knee



Damage: broken knee, torn and sprained ligaments and tendons.
Result: attacker will be unable to stand or to continue to fight.

Twenty-Seven: Roundhouse to Groin



Damage: crushed testicles, broken or cracked pelvis.
Result: attacker will be unable to stand and will be in great pain, maybe crippled.

Twenty-Eight: Knee to Groin



Damage: crushed testicles, cracked pelvis.
Result: attacker will be unable to stand, will be in great pain, and possibly permanently crippled.



Twenty-Nine: Knee to Face



Damage: broken nose, crached teeth, broken jaw
Result: attacker will be knocked out for several minutes.

Thirty: Knee to Throat



Damage: crushed windpipe.
Result: attacker will die unless given immediate medical attention.



Thirty-One: Knee to Coccyx



Damage: broken or cracked coccyx.
Result: attacker will be un- able to stand or to sit, will require medical attention.

Thirty-Two: Knee to Kidney and Lower Back



Damage: broken lower back.
Results: attacker will be in great pain and have internal damage requiring a doctor.



Thirty-Three: Knee Drop to Heart



Damage: heart will be stopped, rib cage crushed, lungs punctured.
Result: attacker will usually die unless given immediate medi- cal help.

Thirty-Four: Stomp to Heart



Damage: stopped heart, cracked or crushed chest, punctured lungs.
Result: attacker will usually die unless given immediate medical attention.



Thirty-Five: Stomp to Groin



Damage: crushed groin, cracked pelvis.
Result: attacker will be unable to stand, may be crippled.

Thirty-Six: Stomp to Throat



Damage: crushed throat.
Result: attacker will usually die unless given immediate medical attention.



Thirty-Seven: Stomp to Face



Damage: crushed nose, broken skull
Result: attacker will usually die unless given immediate medical attention.

Thirty-Eight: Stomp to Back of Head



Damage: teeth knocked out, neck broken, concussion.
Result: permanent crippling, broken neck may cause death.




THE 100
DEADLIEST
KARATE MOVES
BY DR. TED GAMBORDELLA
5TH DAN

Thirty-Nine: Stomp to Lower Back



Damage: broken back and ribs
Result: permanent crippling, broken back may cause death.

Forty: Stomp to Coecyx



Forty-One: Heel Kick to Top of Head



Damage: cracked skull, teeth broken.
Result: loss of consciousness for several minutes.

Forty-Two: Heel Kick to Temple



Damage: crushed temple, cracked skull, blood stoppage to brain.
Result: attacker will pass out for several minutes or go into a fit.



Forty-Three: Heel Kick to Back of Head



Damage: broken neck, loss of consciousness, broken jaw.
Result: attacker will pass out for several minutes; may be permanently crippled.

Forty-Four: Heel Kick to Throat



Damage: crushed throat.
Result: attacker will usually die unless given immediate medical help.



THE 100
DEADLIEST
KARATE MOVES



THE 100
DEADLIEST
KARATE MOVES

Forty-Five: Heel Kick to Face



Damage: broken nose, teeth knocked out, jaw broken.
Result: attacker will be knocked out for several minutes, require medical help.

Forty-Six & Forty-seven: Front Knee Strangle





Damage: loss of breath.
Result: death, unless pressure is released.

Vital Points & Hand Attacks

If the following hand attacks are used in defensive situations, they can inflict serious damage upon an attacker when the hand technique is applied with the necessary speed, power, and accuracy. The vital points and appropriate attacks to each area are illustrated, with a notation on the damage and results of each hand attack.

Forty-Eight: Shuto to the Throat



Damage: crushed throat, broken Adam's apple.
Result: attacker will usually die unless given immediate medical help.

Forty-Nine: Shuto to Teeth



Damage: teeth knocked out, jaw broken.
Result: attacker will usually be knocked out or unwilling to fight



THE 100
DEADLIEST
KARATE MOVES

Fifty: Shuto to Eyes, Bridge of Nose



Damage: broken nose, loss of vision, concussion.
Result: attacker will be knocked out for several minutes.

Fifty-One: Shuto to Top of Skull



Damage: broken or cracked skull, concussion.
Result: attacker will be knocked out for several minutes.

THE 100
DEADLIEST
KARATE MOVES

Fifty-Two: Shuto to Solar Plexus



Damage: breath knocked out, loss of consciousness, extreme pain.
Result: attacker will be unable to move, breathe, and will be unable to finish attack.

Fifty-Three: Shuto to Collarbone



Damage: broken collarbone.
Result: attacker will be unable to pick up arm or to continue to fight.





THE 100
DEADLIEST
KARATE MOVES

Fifty- four: Shuto to side of neck



Damage: broken neck, loss of blood to brain.
Result: attacker will be knocked out for several seconds, or minutes.

Fifty-Five: Shuto to Jaw, Side of Face



Damage: broken jaw, teeth knocked out.
Result: attacker will lose consciousness for several minutes.

Fifty-Six: Shuto to Ribs



Damage: broken ribs, possible lung damage.
Result: attacker will be unable to breathe for several minutes.

Fifty-Seven: Shuto to Groin



Damage: cracked pelvis, crushed groin area.
Result: attacker will be in great pain, unable to stand, may be crippled.



Fifty-Eight: Shuto to Back of Neck



Damage: broken neck.
Result: permanent crippling, possible death.

Fifty-Nine: Shuto to Temple



Damage: cracked skull, loss of consciousness, crushed temple.
Result: attacker will be knocked out, or go into a fit or delirium.



THE 100
DEADLIEST
KARATE MOVES

Sixty: Shuto to Kidneys



Damage: bruised kidneys, cracked or bruised ribs, great pain.
Result: attacker will suffer internal damage and be in great pain.

Sixty-One: Palm Heel to Face



Damage: broken nose, teeth knocked out, broken jaw.
Result: attacker will be knocked out for several minutes.



Sixty-Two: Palm Heel to Chin



Damage: broken jaw, poosble broken neck
Result: attacker will be knocked out for several minutes.

Sixty-Three: Palm Heel to Throat



Damage: crushed throat, broken Adam's apple.
Result: attacker will usually die unless given medical help.





THE 100
DEADLIEST
KARATE MOVES

Sixty-Four: Palm Heel to Heart



Damage: heart stopped, chest broken, sternum cracked, possible lung damage.
Result: attacker will be unable to breathe for several minutes, may die.

Sixty-Five: Palm Heel to Temple



Damage: crushed temple, concussion.
Result: attacker will pass out for several minutes or have a fit.

Sixty-Six: Palm Heel to Back of Head



Damage: broken neck, concussion.
Result: attacker will be knocked out, may have permanent crippling or death.

Sixty-Seven: Palm Heel to Kidneys



Damage: bruised kidney, broken back.
Result: attacker will fall down, have internal damage.



THE 100
DEADLIEST
KARATE MOVES

Sixty-Eight: Elbow to Face



Damage: teeth knocked out, broken jaw, broken nose.
Result: attacker will be knocked out for many minutes; need surgery.

Sixty-Nine: Elbow to Throat



Damage: crushed throat.
Result: death unless given medical attention immediately.



Seventy: Elbow to point of chin



Damage: broken jaw, teeth knocked out, neck snapped back.
Result: attacker will be knocked out, may have broken neck.

Seventy-One: Elbow to Heart-Solar Plexus



Damage: loss of consciousness, broken chest, stopped heart.
Result: attacker will be unable to breathe for several minutes, may die.



Seventy-Two: Elbow to Ribs



Damage: broken ribs, possible lung damage.
Result: attacker will be unable to breathe for several minutes.

Seventy-Three: Elbow to Groin



Damage: cracked pelvis, bruised testicles.
Result: attacker will be unable to stand for several minutes, may be crippled.



Seventy-Four: Elbow to Back of Neck



Damage: broken neck.
Result: attacker will be permanently crippled, knocked out; mav die.

Seventy-Five: Ridge Hand to Solar Plexus



Damage: broken ribs, cracked chest.
Result: attacker will be unable to stand or breathe for several minutes.



THE 100
DEADLIEST
KARATE MOVES

Seventy-Six: Ridge Hand to Temple



Damage: cracked skull, broken jaw.
Result: attacker will be knocked out or go into a fit.

Seventy-Seven: Ridge Hand to Kidneys



Note: *This can be done with the regular ridge hand, or with the bottom fist as shown here, which gives more power, for the ridge hand can be damaging to the thumb if the hand is not trained well.*
Damage: bruised kidneys, cracked spine.
Result: kidney damage, extreme pain, death may result.



Seventy-Eight: Ridge Hand to Back of Head



Damage: broken neck.
Result: attacker will be knocked out; may be permanently crippled, may die.

Seventy-Nine: Ridge Hand to Side of Neck



Damage: broken neck, eardrum , loss of blood to brain.
Result: attacker will be knocked out for a few minutes.


THE 100
DEADLIEST
KARATE MOVES

Eighty: Reidge Hand to Throat



Damage: crushed throat, broken Adam's apple.
Result: attacker will die unless given immediate medical attention.

Eighty-One: Ridge Hand to Bridge of Nose



Damage: broken nose, loss of vision, concussion.
Result: attacker will be knocked out for several minutes.





Eighty-Two: Ridge Hand to Groin



Damage: bruised or crushed testicles, cracked pelvis.
Result: attacker will be unable to stand for several minutes; may be crippled.

Eighty-Three: Punch to Groin



Damage: cracked or broken pelvis, bruised testicles.
Result: attacker will be unable to stand for many minutes; may be crippled.

Eighty-Four: Punch to Heart



Damage: cracked ribs, cracked sternum, loss of breath, stop- page of heart.
Result: attacker will be unable to breathe for many minutes; may die.

Eighty-Five: Punch to Throat



Damage: broken Adam's apple, crushed throat.
Result: attacker will be unable to live unless given medical attention.



THE 100
DEADLIEST
KARATE MOVES

Eighty-Six: Punch to Bridge of Nose



Damage: broken nose, teeth knocked out, eye damage.
Result: attacker will lose consciousness for several minutes or will be unable to see.

Eighty-Seven: Punch to Temple



Damage: broken jaw, teeth knocked out, loss of blood to brain.
Result: attacker will be knocked out for many minutes or go into a fit.



Eighty-Eight: Punch to Chin



Damage: broken jaw, teeth knocked out.
Result: attacker will be knocked out for several minutes.

Eighty-Nine: Punch to Ribs



Damage: broken ribs, pos- sible lung damage.
Result: attacker will be un- able to breathe for several minutes.



THE 100 DEADLIEST KARATE MOVES

Ninety: Punch to Kidneys



Damage:bruised ribs, internal damage, broken back,
Result: attacker will fall down, usually have internal damage requiring medical help.

Ninety-One: Punch to Back of Neck



Damage: broken neck.
Result: attacker will be knocked out, usually crippled; rnay die.



Ninety-Two: Two-Finger Eye Strike



Damage: loss of eyes or scarring of eyes.
Result: attacker will be in great pain, and lose eyesight, perhaps permanently.

Ninety-Three: One-Finger Eye Strike



Damage: loss of eye, permanent eye damage.
Result: attacker will lose eye, or will lose sight for a long time.

THE 100
DEADLIEST
KARATE MOVES



Ninety-Four: Eye Gouge, Thumb



Damage: loss of eye, permanent eye damage.
Result: extreme pain, loss of vision, loss of eye.

Ninety-Five: Double-Eye Gouge



Damage: loss of eyes, loss of vision.
Result: attacker will lose vision, maybe lose eyesight forever.

Ninety-Six: Eardrum Strike



Damage: broken eardrums, cracked jaw.
Result: attacker will be in great pain, lose balance and willingness to fight.

Ninety-Seven: Tiger Claw to Throat



Damage: collapse of larynx.
Result: attacker will die unless pressure is relieved.



Ninety-Eight: Head Butt to the Bridge of Nose



Damage: broken nose, teeth knocked out, cracked skull.
Result: loss of consciousness, internal damage.

Ninety-Nine: Forefinger Strike to Throat



Damage: crushed throat.
Result: attacker will die unless given medical attention.



THE 100
DEADLIEST
KARATE MOVES

One Hundred: Two-Handed Strike to Back of Neck



Damage: broken neck.
Result: attacker will be knocked out for many minutes, usually crippled; may die.



THE 100
DEADLIEST
KARATE MOVES

Street Fighting Applications

The following chapter contains some practical applications for the use of deadly moves in certain situations. I am not showing all of the techniques you have just learned, but rather I am going to illustrate practical applications of some techniques to get your mind working about how to put techniques to use. each situation that you might find yourself involved with in the street requires hundreds of different actions, and all must be done immediately. There is no best technique or action, but you should always try to do what works best for you, after you have practiced all of the techniques.

I do not condone that under any circumstances, short of your imminent death or the impending death of another, that you use these techniques on anyone in the street.

THE 100
DEADLIEST
KARATE MOVES

Situation One: You are standing by your car ready to get in when an attacker with a crowbar tries to kill you.
Response: You have several courses of action. You may turn quickly and snap a FRONT KICK into his throat.



Situation Two: You are getting into your car with your wife when two thugs attack you with a crowbar, trying to kill you.

Response: You both react with kicks; the man with a SIDE KICK to the face; the woman with a BACK KICK to the groin. You then finish them off with STOMPS to the throat and neck.





Situation Three: You are walkingr with your wife when two thugs start to attack you.
Response: The man reacts with a SHUTO to the neck; the woman with a SNAP KICK to the groin. The man finishes them off with a STOMP to the groin and the woman KNNEES the face of her attacker.





Situation Four: A woman is walking down the street when a would-be rapist grabs her.
Response: She reacts with a ROUNDHOUSE to the groin.She continues to turn and thrusts a HEEL KICK to the throat, kicking him down where she finishes him off with a STOMP to the head.



THE 100 DEADLIEST KARATE MOVES

Situation Five: You are at the cash wash when two men attack you.
Response: You react with a SIDE KICK to the throat of one man. A PUNCH to the jaw of the other.Then, back to the fist with an ELBOW SMASH to the jaw. Finishing both of with STOMPS to the groin.





Situation Six: You are at the cash wash when two men jump you and manage to grab you. One gets you into a bear hug.

Response: You react to the one in front of you with a SNAP KICK to the groin.Then you do a REAR LIFT KICK to the groin of the man holding you.The come around with an ELBOW SMASH to his face, knocking him down.You finish him with a STOMP to the face, with the other one you use a SHUTO to the throat.





SECOND EDITION

Strength Training Anatomy



OVER
450,000
COPIES SOLD!

Frédéric Delavier


Sternocleidomastoid
Semispinalis capitis
Splenius capitis
Levator scapula
Scalenes
Omohyoid
Trapezius
Acromion
Clavicle
Deltoid
Pectoralis major, sternocostalis part
Triceps brachii, long head
Triceps brachii, medial head
Triceps brachii, lateral head
Biceps brachii
Brachialis
Brachioradialis (supinator)
Latissimus dorsi
Anconeus
Serratus anterior
Palmaris longus
Flexor digitorum superficialis
Extensor digitorum
Gluteus medius (under gluteal fascia)
Gluteus maximus
Greater trochanter
Tensor fascia lata
Fascia lata, iliotibial band
Biceps femoris, long head
Vastus lateralis
Vastus medialis
Biceps femoris, short head
Vastus intermedius
Plantaris
Femur, lateral condyle
Meniscus
Head of fibula
Gastrocnemius, lateral head
Soleus
Fibularis longus
Extensor digitorum longus
Tibialis anterior
Fibularis brevis
Peroneus
Extensor hallucis longus
Lateral malleolus
Extensor digitorum brevis
Abductor digiti minimi pedis
Abductor hallucis
Sternum
Pectoralis major, abdominal part
External oblique
Rectus abdominis (under aponeurosis)
Anterior superior iliac spine
Pronator teres
Brachioradialis
Extensor carpi radialis longus
Extensor carpi radialis brevis
Flexor carpi radialis
Palmaris longus
Flexor digitorum sublimis
Thenar
Metacarpal bone II
Proximal phalanx
Distal phalanx
Linea alba
Iliopsoas
Cremaster
Pyramidalis (under aponeurosis)
Sartorius
Rectus femoris
Adductor longus
Sartorius
Gracilis
Vastus medialis
Patella
Femur, medial condyle
Meniscus
Gastrocnemius, medial head
Tibia, medial surface
Tibialis anterior
Soleus
Flexor digitorum longus
Flexor hallucis longus
Tendo calcaneus (Achilles)
Medial malleolus
Talus
Navicular bone of foot
Medial cuneiform bone
Metatarsal bone I


Semispinalis capitis
Splenius capitis
Levator scapula
Sternocleidomastoid
7th cervical vertebra, spinous process
Trapezius
Spine of scapula
Acromion
Deltoid
Infraspinatus
Teres minor
Teres major
Rhomboid major
Thoracic vertebra, spinous process
Latissimus dorsi
Thoracolumbar fascia
External oblique
Lumbar trigone
Iliac crest
Sacrum, dorsal surface
Gluteus medius, beneath the gluteal fascia
Tensor fascia lata
Greater trochanter
Gluteus maximus
Gracilis
Semitendinosus
Semimembranosus
Sartorius
Coracobrachialis
Triceps brachii, long head
Biceps brachii
Triceps brachii, medial head
Triceps brachii, lateral head
Triceps brachii, tendon
Brachialis
Biceps brachii, tendon
Pronator teres
Medial epicondyle
Olecranon
Brachioradialis
Flexor carpi radialis
Palmaris longus
Flexor carpi ulnaris
Extensor carpi ulnaris
Flexor digitorum superficialis
Abductor pollicis longus
Flexor pollicis longus
Pisiform
Abductor pollicis brevis
Palmar aponeurosis
Distal phalanges
Extensor digitorum tendon
Adductor magnus
Iliotibial tract (fascia lata)
Vastus lateralis
Biceps femoris, long head
Vastus intermedius
Biceps femoris, short head
Femur, popliteal surface
Plantaris
Gastrocnemius, lateral head
Gastrocnemius, medial head
Peroneus longus
Soleus
Gastrocnemius tendon
Peroneus brevis
Flexor hallucis longus
Flexor digitorum longus
Lateral malleolus
Trochlea of the talus
Extensor digitorum brevis
Abductor digiti minimi
Calcaneal tuberosity
Medial malleolus
Tendo calcaneus (Achilles)


Sternocleidomastoid
Scalenes
Trapezius
Sternohyoid
Sternum
Biceps brachii, long head
Serratus anterior
Latissimus dorsi
Rectus abdominis
Lateral epicondyle
Olecranon
Anconeus
Umbilicus
External oblique
Internal oblique
Pyramidalis
Anterior superior iliac spine
Iliopsoas
Pectineus
Sartorius
Adductor longus
Gracilis
Rectus femoris
Vastus lateralis
Vastus medialis
Patella
Lateral condyle
Meniscus
Patellar ligament
Tibial tuberosity
Gastrocnemius
Tibialis anterior
Soleus
Medial surface of tibia
Flexor digitorum longus
Extensor hallucis longus
Peroneus tertius
Medial malleolus
Extensor hallucis brevis
Extensor digitorum brevis
Abductor hallucis
Omohyoid, inferior belly
Clavicle
Acromion
Pectoralis major
Deltoid
Pectoralis major, abdominal portion
Biceps brachii
Brachialis
Triceps brachii, medial head
Pronator teres
Brachioradialis
Extensor carpi radialis longus
Flexor carpi radialis
Extensor carpi radialis brevis
Extensor digitorum
Abductor pollicis longus
Extensor pollicis brevis
Radius
Gluteus medius
Tensor fascia lata
Fascia lata, iliotibial tract
Iliotibial tract
Head of fibula
Gastrocnemius
Peroneus longus
Extensor digitorum longus
Peroneus brevis

frédéric delavier

STRENGTH TRAINING ANATOMY

SECOND EDITION

HUMAN KINETICS

CONTENTS

1 ARMS 4
2 SHOULDERS 27
3 CHEST 49
4 BACK 66
5 LEGS 93
6 BUTTOCKS 115
7 ABDOMEN 128

1

ARMS

1 CURLS 6
2 CONCENTRATION CURLS 7
3 HAMMER CURLS 8
4 LOW-PULLEY CURLS 9
5 HIGH-PULLEY CURLS 10
6 BARBELL CURLS 11
ELBOW STRUCTURE AND ITS EFFECT ON TRAINING 12
7 MACHINE CURLS 13
8 PREACHER CURLS 14
9 REVERSE CURLS 15
10 REVERSE WRIST CURLS 16
11 WRIST CURLS 17
12 PUSH-DOWNS 18
13 REVERSE PUSH-DOWNS 19
14 ONE-ARM REVERSE PUSH-DOWNS 20
15 TRICEPS EXTENSIONS 21
16 DUMBBELL TRICEPS EXTENSIONS 22
17 ONE-ARM DUMBBELL TRICEPS EXTENSIONS 23
18 SEATED DUMBBELL TRICEPS EXTENSIONS 24
19 SEATED E-Z BAR TRICEPS EXTENSIONS 24
20 TRICEPS KICKBACKS 25
21 TRICEPS DIPS 26


Extensor pollicis longus, tendon
Extensor retinaculum
Extensor pollicis brevis
Abductor pollicis longus
Extensor carpi radialis brevis
Extensor carpi radialis longus
Brachioradialis
Biceps brachii, tendon
Anterior deltoid
Middle deltoid
Biceps brachii
Teres major
Latissimus dorsi
Subscapularis
Pectoralis major
Serratus anterior
Extensor carpi radialis longus, tendon
Extensor carpi radialis brevis, tendon
1st dorsal interosseous muscle
Extensor digitorum, tendon
Flexor digitorum superficialis, tendon
Flexor digitorum profundus, tendon
Adductor pollicis
Opponens pollicis
Abductor pollicis brevis
Flexor pollicis longus
Flexor digitorum superficialis
Flexor carpi radialis
Palmaris longus
Pronator teres
Biceps brachii, aponeurosis
Brachialis
Triceps brachii, medial head
Triceps brachii, long head
Coracobrachialis


Biceps brachii, long head
Biceps brachii, short head
Biceps brachii
Flexor digitorum profundus
Flexor digitorum superficialis, tendon
Lumbrical
Flexor pollicis longus
Flexor digitorum superficialis
Biceps brachii, tendon
Brachialis
Triceps brachii, medial head
Triceps brachii, long head


Brachialis, tendon
Brachialis
Coracobrachialis


Bicipital groove
Greater tubercle
Lesser tubercle
Acromion
Coracoid process
Clavicle
Capitulum
Capitate
Lunate
Trapezoid
Metacarpal
Head of radius
Proximal phalanx
Middle phalanx
Distal phalanx
Trapezium
Scaphoid
Radius
Ulna
Radial tuberosity
Humerus
Trochlea
Deltoid tuberosity

1 CURLS


Pectoralis major (clavicular head)
Anterior deltoid
Middle deltoid
Flexor carpi ulnaris
Posterior deltoid
Triceps brachii, lateral head
Brachialis
Brachioradialis
Flexor carpi radialis
Biceps brachii
Palmaris longus
Pronator teres
Triceps brachii, medial head
Extensor carpi radialis longus
Anconeus
Brachialis
Triceps brachii, long head
Extensor carpi radialis brevis
Extensor digitorum
Extensor carpi ulnaris
Extensor digiti minimi


1
2
Humerus
Ulna
Radius
1
2
1 SUPINATION
2 PRONATION

Sit holding a dumbbell in each hand with arms hanging down and the palms of the hands facing the body:

- Inhale and bend the the elbow, rotating the palm up before the forearm reaches horizontal.
- Continue by raising the elbows at the end of the movement.

This exercise primarily uses the brachioradialis (long supinator), brachialis, biceps brachii, and anterior deltoid and, to a lesser extent, the coracobrachialis and clavicular head of the pectoralis major.

COMMENT: This exercise takes the biceps through its complete range of motion, which includes flexion, protraction, and supination.







THREE WAYS TO EXECUTE CURLS
1 EMPHASIZE BICEPS
2 WORK BRACHIORADIALIS INTENSELY
3 WORK MAINLY BICEPS AND BRACHIALIS

CONCENTRATION CURLS

2


Trapezius
Pectoralis major
Anterior deltoid
Middle deltoid
Coracobrachialis
Biceps brachii
Triceps brachii, long head
Triceps brachii, lateral head
Brachialis
Biceps brachii, tendon
Biceps brachii, aponeurosis
Triceps brachii, medial head
Brachioradialis
Pronator teres
Extensor carpi radialis longus
Flexor carpi radialis
Extensor carpi radialis brevis
Palmaris longus
Flexor carpi ulnaris



FINAL POSITION

Sit holding a dumbbell with the palm facing forward and the elbow positioned against the inner thigh:

- Inhale and lift the forearm by bending the elbow.
- Exhale at the end of the effort.

This isolation exercise allows you to control the range of motion, speed, and form of the movement.

It mainly works the biceps brachii and brachialis.

BRACHIALIS MUSCLE


Clavicle
Acromion
Sternum
Humerus
Brachialis
Costal cartilages
Ulna
Rib
Radius
Metacarpal
Carpal
Proximal phalanx
Distal phalanx
Middle phalanx


Clavicle
Acromion
Humerus
Coracoid process
Coracobrachialis
Scapula
Biceps brachii, short head
Biceps brachii, long head
Radius
Brachialis
Biceps brachii, tendon
Ulna

3 HAMMER CURLS


Trapezius
Infraspinatus
Teres minor
Teres major
Latissimus dorsi
Triceps brachii
Lateral head
Long head
Medial head
Extensor carpi radialis longus
Extensor carpi radialis brevis
Anconeus
Extensor carpi ulnaris
Flexor carpi ulnaris
Posterior deltoid
Middle deltoid
Anterior deltoid
Deltoid
Pectoralis major
Biceps brachii
Brachialis
Brachioradialis
Extensor digitorum
Extensor digiti minimi

BRACHIORADIALIS MUSCLE


Scapula
Clavicle
Costal cartilage
Sternum
Humerus
Brachioradialis
Radius
Ulna
Carpal
Metacarpal
Proximal phalanx
Middle phalanx
Distal phalanx

Stand or sit gripping a dumbbell in each hand with the palms facing each other:

- Inhale and raise the forearms together or alternately.
- Exhale at the end of the movement.

This is the best exercise for developing the brachioradialis.

It also develops the biceps brachii, brachialis, and, to a lesser degree, the extensor carpi radialis brevis and longus.


THE MOVEMENT

LOW-PULLEY CURLS

4


Splenius capitis
Sternocleidomastoid
Levator scapula
Trapezius
Scalenes
Deltoids
Pectoralis major
Biceps brachii
Infraspinatus
Teres minor
Teres major
Triceps brachii
Latissimus dorsi
Brachialis
Extensor carpi radialis longus
Anconeus
Extensor pollicis brevis
Flexor carpi radialis
Abductor pollicis longus
Extensor digitorum
Extensor carpi radialis brevis
Brachioradialis

Stand facing the machine, grasping the handles with an underhand grip (thumbs facing away from each other):

- Inhale and bend the elbows to raise the forearms.
- Exhale at the end of the movement.

This exercise focuses the effort on the biceps brachii and works the muscle intensely.

THE MOVEMENT

VARIATION

Two-handed low-pulley curls

5 HIGH-PULLEY CURLS


Flexor digitorum superficialis
Flexor carpi ulnaris
Palmaris longus
Flexor carpi radialis
Pronator teres
Sternocleidomastoid
Ulna
Radius
Humerus
Brachialis
Aponeurotic expansion of biceps brachii
Triceps brachii, medial head
Biceps brachii
Brachialis
Triceps brachii, long head
Coracobrachialis
Teres major
Latissimus dorsi
Serratus anterior
Long head
Short head
Biceps brachii
Clavicle
Scapula
Sternum
Rib
Pectoralis major





VARIATION
One-handed execution

Stand between the pulleys with the arms outstretched in a "cross" and grasp the handles of the high pulleys with an underhand grip:

- Inhale and bend the elbows to bring the hands toward the body. Exhale at the end of the movement.

This exercise, which is most often performed as a cool-down at the end of an arm session, focuses the work on the short head of the biceps brachii, which has been stretched and put under tension in the "cross" start-up position.

This exercise also contracts the monoarticular brachialis elbow flexor.

Perform this exercise with light weights so that you can concentrate and feel the contraction at the inside of the biceps brachii. Sets of high reps provide the best results.


Phalanx
Metacarpal
Carpal
Radius
Humerus
Ulna
Biceps brachii tendon, partially wrapped around the radius

When the hand is pronated, the distal tendon of the biceps brachii muscle is partially wrapped around the radius.


Phalanx
Metacarpal
Carpal
Humerus
Radius
Ulna
Biceps brachii tendon, partially wrapped around the radius

When the biceps brachii contracts, the force placed on its distal tendon causes the radius to pivot on its axis, bringing the hand into supination.


Extensor carpi ulnaris
Flexor digitorum superficialis
Flexor carpi radialis
Brachioradialis
Palmaris longus
Coracobrachialis
Teres major
Deltoid
Subscapularis
Flexor carpi radialis
Pectoralis major
Aponeurosis of biceps brachii
Latissimus dorsi
Serratus anterior
Pronator teres
External oblique
Triceps brachii, medial head
Biceps brachii
Brachialis
Triceps brachii, long head

Comment: In addition to its role as a forearm flexor, the biceps brachii is the most powerful supinator.

BARBELL CURLS 6


Sternocleidomastoid
Scalenes
Trapezius
Pectoralis major
Deltoid
Biceps brachii
Long head
Short head
Triceps brachii, lateral head
Brachialis
Pronator teres
Brachioradialis
Biceps brachii, aponeurosis
Flexor carpi radialis
Flexor carpi ulnaris
Palmaris longus
Extensor carpi radialis longus
Extensor carpi radialis brevis
Flexor pollicis longus
Flexor digitorum superficialis
Omohyoid
Sternohyoid
1st rib
Clavicle
Acromion
Coracoid process
Scapula
Long head
Short head
Biceps brachii
Sternum
Costal cartilages
Biceps brachii
Brachialis
Biceps brachii, tendon
Floating ribs
Lumbar vertebra
Os coxa
Ulna
Radius





THE MOVEMENT

BRACHIALIS MUSCLE


Clavicle
Coracoid process
Acromion
Head of humerus
Greater tubercle
Lesser tubercle
Bicipital groove
Rib
Brachialis
Brachialis, tendon
Ulna
Radius

Stand with the back straight, grasping the barbell with an underhand grip and hands slightly wider than shoulder-width apart:

- Inhale and raise the barbell by bending the elbows, taking care to stabilize the torso and spine by isometrically contracting the gluteal muscles, abdominal muscles, and spinal muscles.
- Exhale at the end of the movement.

This exercise mainly contracts the biceps brachii, brachialis, and, to a lesser degree, the brachioradialis, pronator teres, and the wrist flexor group.

Variations: Vary the width of the grip to work different parts of the muscle more intensely:

- Placing the hands farther apart isolates the short head of the biceps brachii.
- Placing the hands closer together isolates the long head of the biceps brachii.

Raising both elbows after they are flexed increases the contraction of the biceps brachii and contracts the anterior deltoid.

To make the exercise more difficult, perform the movement with the back against a wall so that the shoulder blades don't move.

You can lift more weight and gain strength by leaning the torso back while lifting the bar; however, to prevent injury, this requires good technique and well-developed abdominal and lumbar muscles.



BARBELL CURLS

1 **Narrow grip**
Mainly works the long head of the biceps brachii.
2 **Wide grip**
Mainly works the short head of the biceps brachii.

ELBOW STRUCTURE AND ITS EFFECT ON TRAINING


Acromion
Clavicle
Head of humerus
Greater tuberosity
Lesser tuberosity
Coracoid process
Bicipital groove
Glenoid cavity
Crest of lesser tubercle
Crest of greater tubercle
Deltoid tuberosity
Radial fossa
Scapula
Lateral epicondyle
Coronoid fossa
Capitulum
Medial epicondyle
Head of radius
Trochlea
Radial tuberosity
Coronoid process
Radius
Ulnar tuberosity
Ulna
Lunate
Styloid process
Head of ulna
Scaphoid
Trapezium
Styloid process
Trapezoid
Capitate
Pisiform
Triquetral
Hamate
Metacarpal
Proximal phalanx
Middle phalanx
Distal phalanx



Biceps training with an E-Z bar eases excessive wrist tension.



1 Upper extremity with a small angle

2 Upper extremity with a significant valgus angle (more common in women)

When training the biceps brachii using a barbell, take into account variations in each person's physical structure.

In the anatomical position (arms hanging alongside the body, palms facing forward, and thumbs pointing laterally), the angle at the elbow between the upper arm and the forearm varies from person to person. Someone whose forearm hangs distinctly away from the body in a valgus position must break excessively at the wrist when performing a curl with a straight bar, which is painful. Therefore, these people should work with an E-Z bar to spare their wrists.

Comment: Valgus of the elbow is usually more pronounced in women.

MACHINE CURLS

7


Trapezius
Triceps brachii, lateral head
Omohyoid
Scalenes
Deltoid
Sternocleidomastoid
Pectoralis major
Biceps brachii
Brachialis



INITIAL POSITION



Performing the curl with an Atlas pulley is a great way to pump up the muscle.

Sit at the machine and grasp the bar with an underhand grip, arms extended, and resting on the support:

- Inhale and raise the forearms.
- Exhale at the end of the movement.

This is one of the best exercises for working the biceps brachii. Fixing the arms against the support makes it impossible to "cheat."

At the beginning, the muscle tension is intense, so be sure to warm up properly using light weights. To avoid the risk of tendonitis, do not completely extend the arm.

This movement also works the brachialis and, to a lesser extent, the brachioradialis and pronator teres.

8

PREACHER CURLS


Sternocleidomastoid
Trapezius
Deltoid
Pectoralis major
Biceps brachii
Brachialis
Brachioradialis
Pronator teres
Flexor carpi radialis
Lateral head
Long head
Medial head
Triceps brachii
Biceps brachii, aponeurotic expansion
Palmaris longus

Sit or stand with the arms resting on the support pad and grasp the bar with an underhand grip:

- Inhale and raise the forearms by bending the elbows. Exhale at the end of the effort.

This is one of the best exercises for isolating the biceps.

Attention: The angle of the support pad places significant tension on the forearms when the arm is completely extended. Therefore, warm up the muscles properly and begin with lighter weights.



THE MOVEMENT


Brachioradialis
Extensor pollicis brevis
Flexor digitorum
Brachialis
Triceps brachii, medial head
Extensor carpi radialis longus
Extensor pollicis longus
Deltoid
Biceps brachii
Pectoralis major
Flexor carpi ulnaris
Abductor pollicis longus
Palmaris longus
Triceps brachii, long head
Extensor carpi radialis brevis
Flexor carpi radialis
Teres major
Pronator teres
Serratus anterior
Latissimus dorsi

REVERSE CURLS 9


Splenius capitis
Thyrohyoid
Levator scapula
Sternocleidomastoid
Scalenes
Infraspinatus
Teres minor
Teres major
Triceps brachii
Long head
Lateral head
Brachioradialis
Extensor carpi radialis longus
Olecranon
Anconeus
Extensor carpi radialis brevis
Extensor digitorum
Extensor digiti minimi
Extensor carpi ulnaris
Flexor carpi ulnaris
Head of ulna
Extensor retinaculum
Omohyoid
Sternohyoid
Trapezius
Deltoids
Pectoralis major
Brachialis
Biceps brachii
Abductor pollicis longus
Extensor pollicis brevis
Triceps brachii, lateral head
Triceps brachii, long head
Triceps brachii, tendon
Lateral epicondyle
Anconeus
Olecranon
Extensor digitorum
Extensor carpi ulnaris
Extensor digiti minimi
Flexor carpi ulnaris
Brachialis
Biceps brachii
Brachioradialis
Extensor carpi radialis longus
Extensor carpi radialis brevis
Abductor pollicis longus
Extensor pollicis brevis
Ulna
Radius
Extensor pollicis longus, tendon

MUSCLES OF THE FOREARM (LATERAL VIEW)

THE MOVEMENT

Stand with the legs slightly apart and arms extended and grasp the bar with an overhand grip (with the thumbs facing each other):

- Inhale and raise the forearms by bending the elbows.
- Exhale at the end of the movement.

This exercise works the extensor muscles of the wrist: extensor carpi radialis longus, extensor carpi radialis brevis, extensor digitorum, extensor digiti minimi, and extensor carpi ulnaris.

It also acts on the brachioradialis, brachialis, and, to a lesser degree, the biceps brachii.

Comment: This is an excellent exercise for strengthening the wrist, which is often weak because of an imbalance caused by using the wrist flexors rather than the wrist extensors. For this reason, many boxers include it in their training. Many bench press champions use it to keep their wrists from trembling under extreme weights.

10 REVERSE WRIST CURLS


Brachioradialis
Flexor carpi radialis
Extensor carpi radialis longus
Extensor carpi radialis brevis
Extensor digitorum
Abductor pollicis longus
Extensor pollicis brevis
Flexor pollicis longus
Flexor digitorum superficialis
Extensor pollicis
Extensor indicis
1st dorsal interosseous
Palmaris longus
Flexor carpi ulnaris
Humerus
Ulna
Radius
Extensor carpi radialis longus
Extensor carpi radialis brevis
Extensor digitorum
Extensor digiti minimi
Extensor carpi ulnaris
Extensor indicis
Phalanx
Metacarpal

Sit with the forearms resting on the thighs or on a bench and grasp the bar with an overhand grip and keep the wrists relaxed:

- Raise the hands by extending at the wrists.

This exercise contracts the extensor carpi radialis longus and brevis, extensor digitorum, extensor digiti minimi, as well as the extensor carpi ulnaris.

Comment: This exercise strengthens the wrists, which are often vulnerable because of weak wrist extensors.

WRIST EXTENSORS


Medial epicondyle
Olecranon
Extensor carpi ulnaris
Ulna
Head of ulna
Metacarpal
Proximal phalanx
Middle phalanx
Distal phalanx
Humerus
Extensor carpi radialis longus
Extensor digitorum
Extensor carpi radialis brevis
Extensor digiti minimi
Radius
Carpal
Extensor indicis



FINAL POSITION

WRIST CURLS 11


Deltoid
Biceps brachii
Triceps brachii, long head
Brachialis
Triceps brachii, medial head
Pronator teres
Brachioradialis
Flexor carpi radialis
Palmaris longus
Flexor digitorum superficialis and profundus
Pisiform
Flexor carpi ulnaris
Pectoralis major
Humerus
Ulna
Radius
Radial tuberosity
Flexor digitorum superficialis covering flexor digitorum profundus
Pisiform
Flexor pollicis longus
Trapezium
Metacarpal


WRIST FLEXORS
Pronator teres
Flexor carpi radialis
Palmaris longus
Flexor carpi ulnaris
Flexor digitorum superficialis
Flexor digitorum profundus
Flexor pollicis longus
Superficial layer
Middle layer
Deep layer

Sit with the forearms resting on the thighs or on a bench and grasp the bar with an underhand grip with wrists relaxed:

- Inhale and raise the hands by flexing at the wrists.

This exercise contracts the flexor carpi radialis, palmaris longus, flexor carpi ulnaris, and the flexors digitorum superficialis and profundus.

The latter two muscles, although located deep in the wrist, make up most of the muscle mass of the wrist flexors.


1 Begin
2 End
THE MOVEMENT

12 PUSH-DOWNS


Splenius
Sternocleidomastoid
Levator scapula
Scalenes
Trapezius
Spine of scapula
Deltoid
Infraspinatus
Teres minor
Teres major
Triceps brachii
Lateral head
Long head
Medial head
Olecranon
External oblique
Anconeus
Flexor carpi ulnaris
Pectoralis major
Biceps brachii
Brachialis
Brachioradialis
Extensor carpi radialis longus
Extensor carpi radialis brevis
Extensor digitorum
Extensor digiti minimi
Extensor carpi ulnaris
Head of ulna
Extensor retinaculum





THE MOVEMENT

Stand with the back to the machine and grasp the handle with an overhand grip, keeping the elbows tucked into the body:

- Inhale and extend the forearms, keeping the elbows tucked into the body.
- Exhale at the end of the movement.

Comment: This exercise isolates the triceps and the anconeus.

The variation using a rope rather than a handle engages the lateral head of the triceps more intensely.

Performing the movement with an underhand grip requires more contribution from the medial head of triceps.

Hold an isometric contraction for one or two seconds at the end of the movement to feel the effort more intensely.

When using heavy weights, lean forward with the torso.

Beginners can use this exercise to develop enough strength to move on to more difficult exercises.


Medial head
Lateral head
Long head
Triceps brachii

VARIATION WITH BACK TO THE MACHINE
To isolate of the long head of the triceps.



VARIATION WITH A ROPE
To isolate the lateral head of the triceps

REVERSE PUSH-DOWNS

13


Splenius capiti
Sternocleidomastoid
Levator scapula
Scalenes
Trapezius
Omohyoid
Deltoid
Infraspinatus
Teres minor
Teres major
Triceps brachii, long head
Latissimus dorsi
Triceps brachii, lateral head
Biceps brachii
Brachialis
Brachioradialis
Triceps brachii, medial head
Lateral epicondyle
Olecranon
Pectoralis major
1st dorsal interosseous
Extensor pollicis longus
Flexor digitorum superficialis
Flexor carpi radialis
Extensor carpi radialis brevis
Extensor digitorum
Flexor carpi ulnaris
Extensor carpi ulnaris
Extensor carpi radialis longus
Anconeus

Stand facing the machine with the arms next the body and elbows bent and grasp the handle with an underhand grip:

- Inhale and extend the forearms by straightening the elbows, keeping them tucked into the body.
- Exhale at the end of the movement.

The underhand grip isolates the medial head of the triceps brachii and precludes working with heavy weights.

When extending the forearms, the anconeus and wrist extensors also contract.

The extensor carpi ulnaris, extensor digitorum, extensor digiti minimi, and extensors carpi radialis longus and brevis keep the wrist straight with isometric contraction during the exercise.


Acromion
Head of humerus
Triceps brachii, long head
Triceps brachii, lateral head
Triceps brachii, medial head
Triceps brachii, tendon
Radius
Ulna
Styloid process
Clavicle
Coracoid process
Spine of scapula
Scapula
Vertebra
Rib
Medial epicondyle
Olecranon
Anconeus
Carpal
Metacarpal
Proximal phalanx
Middle phalanx
Distal phalanx

14 ONE-ARM REVERSE PUSH-DOWNS


Infraspinatus
Teres minor
Teres major
Latissimus dorsi
Triceps brachii, lateral head
Triceps brachii, long head
Triceps brachii, medial head
Flexor carpi ulnaris
Extensor carpi ulnaris
Extensor digiti minimi
Extensor digitorum
Trapezius
Deltoid
Pectoralis major
Biceps brachii
Brachialis
Triceps brachii, tendon
Brachioradialis
Anconeus
Extensor carpi radialis longus
Extensor carpi radialis brevis
INITIAL POSITION

Stand facing the machine and grasp the handle with an underhand grip:

- Inhale and extend the forearm.
- Exhale at the end of the movement.

This exercise mainly works the lateral head of the triceps.


INSERTIONS OF THE ARM
Anterior view
Posterior view
Supraspinatus
Infraspinatus
Triceps brachii, long head
Triceps brachii, lateral head
Deltoid
Brachialis
Triceps brachii, medial head
Medial epicondyle muscles
Triceps brachii, tendon
Anconeus
Brachioradialis
Medial epicondyle muscles
Pectoralis major
Deltoid
Biceps brachii
Supraspinatus
Coracobrachialis
Infraspinatus
Latissimus dorsi
Teres major
Coracobrachialis
Brachialis
Lateral epicondyle muscles
Extensor carpi radialis longus
Brachialis

TRICEPS EXTENSIONS 15


Flexor carpi ulnaris
Palmaris longus
Flexor carpi radialis
Flexor digitorum superficialis
Flexor pollicis longus
Abductor pollicis longus
Extensor pollicis brevis
Biceps brachii, aponeurotic expansion
Olecranon
Pronator teres
Brachialis
Medial head
Lateral head
Long head
Triceps brachii
Biceps brachii
Coracobrachialis
Pectoralis major
Serratus anterior
Subscapularis
Teres major
Posterior deltoid
Latissimus dorsi



1 **Lowering the bar to the forehead**
Focuses the work on the medial and lateral heads of the triceps brachii.



2 **Lowering the bar behind the head**
Focuses the work on the long head of the triceps brachii.



VARIATION ON A MACHINE

Performing this exercise at an Atlas triceps pulley simulates the movement with a barbell, but enables you to isolate the long head of the triceps brachii.

Lie on a horizontal bench and grasp the barbell with an overhand grip and the arms vertical:

- Inhale and lower the barbell to the forehead or behind the head by bending the elbows.
- Return to the initial position.
- Exhale at the end of the effort.

Comments: Because of individual variations in shoulder width, valgus angle at the elbows, and wrist flexibility, the hands can be closer or farther apart on the bar and the elbow angle more or less open during the exercise.
Using an E-Z bar helps prevent excessive strain at the wrists.

16 DUMBBELL TRICEPS EXTENSIONS


Abductor pollicis longus
Extensor pollicis brevis
Extensor pollicis longus
Flexor carpi ulnaris
Extensor carpi ulnaris
Extensor digiti minimi
Extensor digitorum
Anconeus
Extensor carpi radialis brevis
Extensor carpi radialis longus
Brachioradialis
Brachialis
Medial head
Lateral head
Long head
Triceps brachii
Serratus anterior
Latissimus dorsi
Anterior deltoid
Biceps brachii
Middle deltoid
Posterior deltoid
Teres minor
Infraspinatus
Teres major

Lie on a flat bench and grasp a dumbbell in each hand with the arms vertical:

- Inhale and lower the forearms by bending the elbow with a controlled movement.
- Return to the initial position.
- Exhale at the end of the effort.

This exercise works all three heads of the triceps brachii equally.



THE MOVEMENT


Acromion
Head of humerus
Triceps brachii, long head
Triceps brachii, lateral head
Triceps brachii, medial head
Triceps brachii, tendon
Radius
Ulna
Styloid process
Clavicle
Coracoid process
Spine of scapula
Scapula
Vertebra
Rib
Medial epicondyle
Olecranon
Anconeus
Carpal
Metacarpal
Proximal phalanx
Middle phalanx
Distal phalanx

ONE-ARM DUMBBELL TRICEPS EXTENSIONS 17


Phalanx
Metacarpal
Carpal
Ulna
Radius
Sternocleidomastoid
Splenius
Levator scapula
Trapezius
Spine of scapula
Deltoid
Infraspinatus
Teres minor
Anconeus
Olecranon
Tendon
Lateral head
Long head
Triceps brachii
Humerus
Acromion
Clavicle
Scapula
Rhomboid major
Teres major
Rib
Latissimus dorsi
Vertebra
Thoracolumbar fascia
External oblique
Triceps brachii
Lateral head
Long head
Medial head
Biceps brachii
Brachialis
Olecranon
Pronator teres
Biceps brachii, aponeurosis
Brachioradialis
Flexor carpi radialis
Palmaris longus
Flexor digitorum
Flexor carpi ulnaris



THE MOVEMENT

Sit or stand and grip a dumbbell in one hand with the arm vertical:

- Inhale and bend the elbow to lower the dumbbell behind the head to the neck.
- Return to the initial position.
- Exhale at the end of the movement.

The vertical position of the arm stretches the long head of the triceps brachii, emphasizing its contraction while working.

Comment: Contract the abdominal core to prevent arching the low back. If possible use a bench with support for the low back.

18 SEATED DUMBBELL TRICEPS EXTENSIONS


Palmaris longus
Flexor carpi ulnaris
Extensor carpi ulnaris
Anconeus
Triceps brachii, medial head
Pectoralis major
Subscapularis
Teres minor
Teres major
Extensor digiti minimi
Extensor digitorum
Extensor carpi radialis brevis
Extensor carpi radialis longus
Brachioradialis
Lateral head
Long head
Triceps brachii
Deltoid
Infraspinatus
Latissimus dorsi
Serratus anterior

Sit and grasp a dumbbell, holding it behind the neck:

- Inhale, and extend the forearm.
- Exhale at the end of the movement.

The vertical position of the arm strongly stretches the long head of the triceps brachii, emphasizing its contraction while working.

Contract the abdominal core to prevent arching the low back. If possible use a bench with support for the low back.



19 SEATED E-Z BAR TRICEPS EXTENSIONS

Sit or stand and grasp an E-Z bar with an overhand grip and arms vertical:

- Inhale and bend the elbows to lower the bar behind the head.
- Return to the initial position.
- Exhale at the end of the extension.

The vertical position of the arms strongly stretches the long head of the triceps brachii, emphasizing its contraction while working.

An overhand grip isolates the lateral head of the triceps brachii.

Contract the abdominal muscles and avoid arching the low back. If possible use a bench with support for the low back.



THE MOVEMENT


Flexor carpi ulnaris
Palmaris longus
Flexor carpi radialis
Brachioradialis
Biceps brachii, aponeurotic expansion
Pronator teres
Brachialis
Triceps brachii, medial head
Biceps brachii
Triceps brachii, long head
Deltoid
Teres major
Coracobrachialis
Latissimus dorsi
Radius
Ulna
Triceps brachii, tendon
Medial head
Lateral head
Long head
Triceps brachii
Head of humerus
Clavicle
Scapula
Rib

TRICEPS KICKBACKS

20


Flexor carpi ulnaris
Extensor digitorum
Extensor digiti minimi
Extensor carpi ulnaris
Extensor pollicis brevis
Triceps brachii
Lateral head
Long head
Teres major
Brachioradialis
Anconeus
Deltoid
Biceps brachii
Pectoralis major
Brachialis
Extensor carpi radialis longus
Extensor carpi radialis brevis
Abductor pollicis longus

Stand with the knees slightly bent and lean forward at the waist, maintaining a straight back.

Bend the elbow and hold the upper arm horizontally alongside the body:

- Inhale and extend the forearm.
- Exhale at the end of the movement.

This is an excellent exercise for pumping the triceps group.

Perform this exercise until you feel a burn for best results.



INITIAL POSITION

21

TRICEPS DIPS


Trapezius
Teres minor
Infraspinatus
Teres major
Rhomboid
Latissimus dorsi
Flexor carpi radialis
Palmaris longus
Extensor carpi ulnaris
Flexor carpi ulnaris
Deltoid
Pectoralis major
Lateral head
Long head
Medial head
Triceps brachii
Anconeus
Extensor digitorum
Extensor digiti minimi

TRICEPS BRACHII MUSCLE


Scapula
Clavicle
Acromion
Spine of scapula
Head of humerus
Glenoid cavity
Triceps brachii, long head (sectioned)
Triceps brachii, lateral head
Triceps brachii, long head
Triceps brachii, long head (selection)
Vertebra
Rib
Triceps brachii, tendon
Triceps brachii, medial head
Lateral epicondyle
Olecranon
Anconeus
Os coxa
Sacrum
Medial epicondyle
Radius
Ulna



INITIAL POSITION

Suspend the body between two benches by placing the hands on the edge of one bench and the feet on the edge of the other bench:

- Inhale, then dip by bending the elbows and rise by extending the forearms.
- Exhale at the end of the movement.

This exercise works the triceps and pectorals as well as the anterior deltoid.

Resting weights on top of the thighs increases the difficulty and intensity of the dip.

2

SHOULDERS



FRONT

Scalenes
Trapezius
Anterior deltoid
Middle deltoid
Biceps brachii
Brachialis
Triceps brachii, medial head
Triceps brachii, long head
Coracobrachialis
Teres major
Latissimus dorsi
Subscapularis
Pectoralis major
Serratus anterior
1st rib
Clavicle
Deltoid
Humerus
Scapula
Sternum
Rectus abdominis, under the aponeurosis
Umbilicus
Anterior superior iliac spine
Pyramidalis
Pubic symphysis



BACK

Clavicle
Acromion
Deltoid
Humerus
Spine of scapula
Scapula
Vertebra
Rib
Latissimus dorsi
External oblique
Semispinalis capitis
Splenius
Sternocleidomastoid
Trapezius
Anterior deltoid
Middle deltoid
Triceps brachii, lateral head
Triceps brachii, long head
Posterior deltoid
Teres major
Teres minor
Infraspinatus
Rhomboid

1 BACK PRESSES 28
2 SEATED FRONT PRESSES 29
✚ SHOULDER INJURIES / LYING DUMBBELL PRESSES 30
3 SEATED DUMBBELL PRESSES 33
4 FRONT DUMBBELL PRESSES 34
5 BENT-OVER LATERAL RAISES 35
6 LATERAL DUMBBELL RAISES 36
7 ALTERNATE FRONT ARM RAISES 38
8 SIDE-LYING LATERAL RAISES 39
9 LOW-PULLEY LATERAL RAISES 40
10 LOW-PULLEY FRONT RAISES 41
11 HIGH-PULLEY LATERAL EXTENSIONS 42
12 LOW-PULLEY BENT-OVER LATERAL RAISES 43
13 ONE-DUMBBELL FRONT RAISES 44
14 BARBELL FRONT RAISES 45
15 UPRIGHT ROWS 46
16 NAUTILUS LATERAL RAISES 47
17 PEC DECK REAR-DELT LATERALS 48

1 BACK PRESSES


Epicranius, occipital belly
Deltoid
Anterior deltoid
Middle deltoid
Posterior deltoid
Semispinalis capitis
Splenius capitis
Sternocleido-mastoid
Cranium
Mastoid process
Cervical vertebra
Brachioradialis
Extensor digitorum
Extensor carpi radialis brevis
Extensor carpi ulnaris
Extensor carpi radialis longus
Anconeus
Brachialis
Biceps brachii
Trapezius
Clavicle
Supraspinatus
Acromion
Spine of scapula
Radius
Ulna
Humerus
Scapula
9th rib
Thoracic vertebra
Lumbar vertebra
Triceps brachii
Lateral head
Medial head
Long head
Teres minor
Teres major
Infraspinatus
Rhomboid major
Latissimus dorsi
External oblique
Thoracolumbar fascia

Sit with the back straight, holding the bar across the back of the neck with an overhand grip:

- Inhale and extend the bar straight up, keeping the low back as straight as possible.
- Exhale at the end of the effort.

This exercise uses the deltoid, mainly the middle and posterior fibers, as well as the trapezius, triceps brachii, and serratus anterior. Although not worked as intensely, the rhomboids, infraspinatus, teres minor, and, deeper in, the supraspinatus also contract. You can also perform this exercise while standing at a frame that guides the barbell. Various specific machines can help with the performance of this exercise.


THE MOVEMENT

To prevent injury to the shoulder joint, which is vulnerable, lower the bar only as far as your unique shoulder structure and flexibility allow you to do comfortably.

SEATED FRONT PRESSES

2


Splenius
Sternocleidomastoid
Trapezius
Deltoid
Anterior deltoid
Posterior deltoid
Middle deltoid
Spine of scapula
Acromion
Biceps brachii
Brachialis
Brachioradialis
Extensor carpi radialis longus
Anconeus
Triceps brachii
Lateral head
Medial head
Long head
Rhomboid major
Latissimus dorsi
Teres minor
Teres major
Infraspinatus
FINAL POSITION
Pectoralis major clavicular head
Anterior deltoid
Triceps
FRONT VIEW



1 **Narrow grip with the elbows forward**
Isolates the anterior deltoid and the clavicular head of the pectoralis major.



2 **Wide grip with the elbows out to the side**
Isolates the anterior and middle deltoids.

Sit with the back straight and hold the bar with an overhand grip, resting it across the upper chest:

- Inhale and extend the bar vertically.
- Exhale at the end of the movement.

This fundamental exercise mainly uses the anterior and lateral deltoids, clavicular head of the pectoralis major, triceps brachii, serratus anterior, trapezius and, deeper in, the supraspinatus.

You can also perform this exercise standing, as long as you keep the back straight, avoiding excessive curvature of the lumbar spine. Extending the barbell with the elbows forward isolates the anterior deltoid.

Extending the bar with the elbows spread apart isolates the middle deltoid.

You can use various machines for this exercise.

SHOULDER INJURIES



HIP JOINT



SHOULDER JOINT

Compared to the relatively stable coxofemoral joint, the shoulder joint is less encased and is more mobile, which makes it more vulnerable to injury.



ROTATOR CUFF MUSCLES FROM THE FRONT

Shoulder injuries occur frequently in weightlifting and especially in bodybuilding where developing the entire deltoid group requires the athlete to perform a significant number of repetitions and variations in exercises, which multiplies the risk of injury.

Compared to the stability of the hip joint, where the head of the femur sits deep in the glenoid cavity of the pelvis, the shoulder joint, which is very mobile and allows the arm to move through a wide range of motion, is in fact much less contained and protected.

The shoulder is defined as a ball-and-socket joint because the head of the humerus is mainly held within the glenoid cavity of the scapula by a complex musculotendinous group.

Most weightlifting injuries occur when training the deltoids, and they rarely result in muscle pulls or tears. They are usually caused by poor technique or overuse of the tendons reinforcing the articular capsule.

In contrast to contact sports, such as football, where sudden arm movements can create serious injuries involving dislocation or even torn tendons, the most serious injury in weightlifting involves entrapment.

When some people perform exercises in which they raise the arms, such as extensions from the neck or lateral raises, the supraspinatus tendon is rubbed and compressed between the head of the humerus and the osteoligamentous ceiling created by the inferior surface of the acromion and the coracoacromial ligament.

Inflammation follows. This generally begins with the serous bursa, which normally protects the supraspinatus from excessive friction, and extends to the supraspinatus tendon itself, which, without treatment, ends up affecting the adjacent infraspinatus tendon posteriorly and the long head of the biceps brachii anteriorly. Raising the arm becomes extremely painful and eventually can cause irreversible deterioration of the supraspinatus tendon through calcification and even tearing; however, this usually happens to people 40 years of age or older.

The space between the humerus and the osteoligamentous acromiocoracoid ceiling varies from person to person. Some athletes cannot raise their arms laterally without excessive friction. These people should avoid all extensions from the neck, lateral raises that go too high, and back presses.

All barbell extensions for the shoulders must be performed to the front with the elbows slightly forward. When doing lateral dumbbell raises, you'll need to determine the proper height to raise the arms to. The correct movement is the one you can perform without causing pain.

Not everyone responds the same way to the same shoulder injury. Some people may perform all sorts of arm raises that compress the tendon, sometimes even causing tendon degeneration, without initiating a painful inflammatory process. This is how a torn supraspinatus tendon can be discovered during assessment without that person ever having complained of pain.

Another cause of shoulder pain may an imbalance in muscle tension around the articular capsule. Remember that the head of the humerus is solidly fixed against the glenoid fossa of the scapula by a group of muscle tendons adhering to or crossing over the articular capsule: In front, this is the subscapularis; a little more anterior is the long head of the biceps; superiorly, is the supraspinatus; and finally posteriorly, the infraspinatus and teres minor. Spasm, hypertonicity, or hypotonicity in one or more of these muscles can pull the shoulder joint into an incorrect position. This position can cause friction during arm movements, resulting in inflammation.



ROTATOR CUFF MUSCLES, SEEN FROM BEHIND

Supraspinatus
Spine of scapula
Acromion
Supraspinatus tendon
Humerus, greater tubercle
Infraspinatus
Teres minor
Scapula, medial border
Triceps brachii
Long head
Lateral head
Medial head

Example: Shortening or spasm of the teres minor and the infraspinatus will pull the head of the humerus in external rotation, which will cause rubbing at the anterior shoulder joint during arm movement. Over time, this will injure the long head of the biceps brachii.

Balance the training of the shoulder muscles and avoid exercises that feel awkward or painful.



CORONAL SECTION OF THE SHOULDER JOINT DISPLAYING THE SEROUS BURSA

Supraspinatus
Acromion
Clavicle
Capsular ligament
Glenoid labrum
Supraspinatus tendon
Subacromial serous bursa
Head of humerus
Hyaline cartilage of humeral head
Epiphyseal line
Hyaline cartilage of glenoid fossa
Deltoid
Recess
Humerus
Scapula



LATERAL VIEW OF SCAPULA HIGHLIGHTING THE CORACOACROMIAL LIGAMENTOUS CEILING

Acromion
Coracoid process
Spine of scapula
Coracoacromial ligament
Glenoid fossa
Lateral border

Comment:
Massage, either manually or even better with an electric massager, and electrical stimulation are effective for decreasing or eliminating spasms and shortening of the teres minor and infraspinatus.

LYING DUMBBELL PRESSES



This is one of the rare exercises that may be performed by people suffering from the all-too-common entrapment syndrome.

Performing arm extensions with dumbbells while lying on a bench and keeping the elbows next to the body works the anterior deltoid and, to a lesser degree, the middle deltoid intensely while preventing excessive rubbing at the anterior shoulder.

When performed regularly, this maintains size and tone of deltoids despite the existence of injury. You can also use this exercise to reeducate the pectoralis major following tearing. Extending while keeping the elbows against the body reduces its stretch, thus reducing the risk of tearing the scarred area.

Performing the exercise:

Lie on a bench with the chest expanded, back slightly arched, feet flat on the ground, and the elbows bent next to the body, holding a dumbbell in each hand.

- Inhale and extend the arms vertically.
- Exhale at the end of the movement.
- Return to the initial position with a controlled movement.

SEATED DUMBBELL PRESSES

3


Splenius capitis
Sternocleidomastoid
Levator scapula
Trapezius
Semispinalis capitis
Phalanx
Extensor pollicis longus
Extensor digiti minimi
Biceps
Brachioradialis
Extensor digitorum
Flexor carpi ulnaris
Extensor carpi ulnaris
Extensor carpi radialis brevis
Anconeus
Extensor carpi radialis longus
Abductor pollicis longus
Biceps brachii
Acromion
Humerus
Metacarpal
Carpal
Radius
Ulna
Spine of scapula
Clavicle
Scapula
9th rib
Lumbar vertebra
Middle deltoid
Posterior deltoid
Anterior deltoid
Deltoid
Teres minor
Teres major
Infraspinatus
Latissimus dorsi
Triceps brachii
Medial head
Lateral head
Long head

Sit on a bench, keeping the back straight, and hold dumbbells at shoulder level with an overhand grip (thumbs pointing inward):

- Inhale and extend the arms vertically.
- Exhale at the end of the movement.

This exercise contracts the deltoid, mainly the middle deltoid, as well as trapezius, serratus anterior, and triceps brachii.

This movement may also be performed standing or alternating the arms. A backrest helps prevent an excessive arch in the back.



VARIATION
PALMS FACING EACH OTHER



FINAL POSITION

4 FRONT DUMBBELL PRESSES


Pectoralis major, clavicular head
Anterior deltoid
Middle deltoid
Posterior deltoid

VARIATION WITH ALTERNATING EXTENSIONS

Sit on a bench, keeping the back straight. With elbows bent and pointing forward, hold the dumbbells at shoulder level with an underhand grip (thumbs pointing away from each other):

- Inhale and extend the arms vertically while rotating 180 degrees at the wrists, bringing them into an overhand grip (thumbs pointing toward each other).
- Exhale at the end of the movement.

This exercise solicits the deltoid, mainly the anterior deltoid, as well as the clavicular head of the pectoralis major, triceps brachii, trapezius, and serratus anterior.

Variations:
This exercise may be performed seated against a backrest to help prevent an excessive arch in the back, standing, and alternating arms.


Scalenes
Trapezius
Spine of scapula
Pectoralis major, clavicular head
Extensor digitorum
Biceps brachii
Brachioradialis
Extensor carpi radialis brevis
Brachialis
Extensor carpi radialis longus
Anconeus
Triceps brachii
Lateral head
Long head
Medial head
Sternocleidomastoid
Splenius
Levator scapula
Middle deltoid
Posterior deltoid
Anterior deltoid
Deltoid
Infraspinatus
Teres minor
Teres major
Latissimus dorsi
Serratus anterior
External oblique
FINAL POSITION

Comment: Working with the elbows pointing forward prevents excessive friction, which triggers inflammation in the shoulder that can eventually develop into a more serious injury.
This movement is recommended for people with weak shoulders and is meant to replace more intense exercises, such as classic dumbbell extensions with the elbows pointing to the sides or extensions from behind the neck.

BENT-OVER LATERAL RAISES

5


Clavicle
Trapezius
Infraspinatus
Latissimus dorsi
External oblique
Teres minor
Teres major
Acromion
Deltoid
Anterior deltoid
Posterior deltoid
Middle deltoid
Triceps brachii
Brachialis
Biceps brachii
Brachioradialis
Extensor carpi radialis longus
Anconeus
Flexor carpi ulnaris
Extensor carpi radialis brevis
Extensor carpi ulnaris
Extensor digiti minimi
Sternocleidomastoid
Pectoralis major
Biceps brachii
Brachioradialis
Pronator teres
Flexor carpi radialis
Palmaris longus
Flexor digitorum superficialis
Extensor digitorum

DELTOID INSERTIONS


Coracoid process
Scapula
Spine of scapula
Acromion
Clavicle
Humerus
Deltoid

Stand with legs slightly apart and knees slightly bent and lean forward at the waist while keeping the back straight. With arms hanging down, grasp the dumbbells with the elbows slightly bent:

- Inhale and raise the arms to horizontal.
- Exhale at the end of the effort.

This exercise works the shoulder group, accenting the work of the posterior deltoid. Squeeze the shoulder blades together at the end of the movement to contract the middle and lower portions of the trapezius, rhomboids, teres minor, and infraspinatus.

Variation: The exercise may be performed facedown on an incline bench.



FINAL POSITION

6 LATERAL DUMBBELL RAISES


Sternocleidomastoid
Sternohyoid
Trapezius
Pectoralis major
Deltoid
Coracobrachialis
Biceps brachii
Brachialis
Brachioradialis
Pronator teres
Triceps brachii
Medial head
Long head
Teres major
Latissimus dorsi
Serratus anterior
External oblique
Rectus abdominis
Gluteus medius
Iliopsoas
Pectineus
Tensor fascia lata
Adductor longus
Sartorius
1st rib
Clavicle
Posterior deltoid
Anterior deltoid
Middle deltoid
Deltoid
Radius
Ulna
Humerus
Scapula
Sternum
Rib
Pubic symphysis
Os coxa
Sacrum
Pubic symphysis
Femur
Gracilis

SUPRASPINATUS MUSCLE ACTION


Supraspinatus
Acromion
Greater tubercle
Head of humerus
Glenoid cavity
Spine of scapula
Scapula
Humerus

The supraspinatus helps the deltiod raise the arm laterally and helps keep the head of the humerus in the glenoid cavity.



1 Dumbbells to the side
2 Dumbbells behind
3 Dumbbells in front

INITIAL POSITIONS: VARIATIONS

Stand with a straight back, with legs slightly apart, arms hanging next to the body, holding a barbell in each hand:

- Raise the arms to horizontal with the elbows slightly bent.
- Return to the initial position.

This exercise mainly uses the middle deltoid.

The three divisions of the deltoids create a multipennate muscle whose different fiber directions converge on the humerus. Their function is to support relatively heavy weight and to move the arm through its full range of motion with precision. Therefore, it is important to adapt training to the specifics of this muscle by varying the initial position of the movement (hands behind, to the side, or in front). This thoroughly works all the fibers of the middle deltoid. Because everyone's physical structure is different (length of the clavicle, shape of the acromion, and height of the insertion at the humerus), you must find the angle of the initial position that is best for you. Lateral raises contract the supraspinatus, although you can't see this because it is located deep in the supraspinatus fossa of the scapula (shoulder blade), where it attaches to the lesser tubercle of the humerus.

Raising the arm above horizontal contracts the upper part of the trapezius; however, many bodybuilders don't work above horizontal so that they isolate the the lateral deltoid. This exercise should not be performed with heavy weights, but instead in sets of 10 to 25 reps, while varying the working angle without much recuperation time until you feel a burn. To increase the intensity, maintain an isometric contraction for a few seconds with the arm at horizontal between each repetition.


Deltoid
Anterior deltoid
Middle deltoid
Posterior deltoid
Splenius
Levator scapula
Sternocleidomastoid
Extensor carpi radialis brevis
Extensor digitorum
Extensor carpi ulnaris
Anconeus
Brachialis
Biceps brachii
Flexor carpi ulnaris
Triceps brachii
Extensor carpi radialis longus
Brachioradialis
Teres major
Teres minor
Infraspinatus
Rhomboids
Trapezius
Upper portion
Middle portion
Lower portion
Serratus anterior
Latissimus dorsi
External oblique


CONVERGENT MUSCLE
PENNATE MUSCLE
A
CONVERGENT MUSCLE
A1
A
A2
PENNATE MUSCLE

A pennate muscle displaces greater weight than a convergent muscle but over a shorter distance.

During lateral raises, because the pennate fibers of the middle deltoid produce great force but weak contraction, they work synergistically with the anterior and posterior deltoids to bring the arm to horizontal.

The sum of the actin* and myosin* filaments of a fusiform muscle is equal to its transverse section A.

The sum of the actin and myosin filaments of a pennate muscle is equal to the sum A of its oblique sections A1 and A2.

*The motor elements of a muscle whose maximum force of contraction is approximately 5 kg per cm^2 per second.



FINAL POSITION: VARIATIONS

1 Arms raised to horizontal works the deltoid.

2 Arms raised above horizontal isolates the upper and middle portions of the trapezius.

7 ALTERNATE FRONT ARM RAISES


Omohyoid
Sternocleidomastoid
Trapezius
Pectoralis major clavicular head
Deltoid
Anterior deltoid
Middle deltoid
Biceps brachii
Brachialis
Triceps brachii
Brachioradialis
Extensor carpi radialis longus
Anconeus
Extensor digitorum
Extensor carpi radialis brevis
Extensor digiti minimi
Abductor pollicis longus
Extensor carpi ulnaris
Extensor pollicis brevis
Sternohyoid
Palmaris longus
Flexor carpi radialis
Pronator teres
Medial head
Long head
Triceps brachii
Coracobrachialis
Teres major
Latissimus dorsi
Pectoralis major
Serratus anterior





THE MOVEMENT

Stand with the feet slightly apart, holding the barbells with an overhand grip as they rest against the front of the thighs or slightly to the side:

- Inhale and alternate raising the arms to the front to eye level.
- Exhale at the end of the effort.

This exercise uses mainly the anterior deltoid, the clavicular head of the pectoralis major, and, to a lesser degree, the remaining deltoids. All movements that raise the arms contract the muscles that anchor the scapula to the rib cage, such as the serratus anterior and rhomboids, which create a stable support for the humerus to move from.



VARIATION
Lying facedown on an incline bench.



VARIATION
Raising to the front using both hands.

SIDE-LYING LATERAL RAISES

8


Extensor carpi radialis brevis
Extensor digitorum
Extensor carpi radialis longus
Extensor digiti minimi
Triceps brachii
Deltoid
Brachioradialis
Trapezius
Infraspinatus
Rhomboids
Anconeus
Flexor carpi ulnaris
Extensor carpi ulnaris
Flexor carpi ulnaris
Palmaris longus
Teres minor
Teres major
Latissimus dorsi

Lie on one side on the floor or on a bench holding a dumbbell with an overhand grip:

- Inhale and raise the arm to vertical.
- Exhale at the end of the movement.

Unlike standing raises, which progressively work the muscle to maximum intensity at the end of the movement (when the arm reaches horizontal), this exercise works the deltoid differently by focusing the effort at the beginning of the raise. Sets of 10 to 12 repetitions work best.


Clavicle
Deltoid, multipennate middle deltoid
Clavicle
Scapula
Anterior deltoid
Posterior deltoid
Rib
Humerus
Rib
FRONT
BACK

Comment: This movement contracts the supraspinatus, the muscle mainly responsible for initiating abduction. Varying the initial position (dumbbell in front of or behind the thigh) allows you to work all the deltoid fibers.

9 LOW-PULLEY LATERAL RAISES


Brachialis
Middle deltoid
Anterior deltoid
Triceps brachii, medial head
Biceps brachii
Triceps brachii, long head
Coracobrachialis
Teres major
Latissimus dorsi
Sternocleidomastoid
Scalenes
Trapezius
Omohyoid
Deltoid
Anterior deltoid
Middle deltoid
Posterior deltoid
Biceps brachii
Brachialis
Triceps brachii
Long head
Lateral head
Medial head
Brachioradialis
Extensor carpi radialis longus
Anconeus
Extensor carpi ulnaris
Flexor carpi ulnaris
Extensor carpi brevis
Extensor digitorum
Extensor digiti minimi
Abductor pollicis longus
Extensor pollicis brevis
Pectoralis major
Rectus abdominis, under the aponeurosis
External oblique


Posterior deltoid
Anterior deltoid
Middle deltoid
Clavicle
Head of humerus
DELTOID ACTION
Sternum
Scapula
Rib
Glenoid cavity
Humerus

Grasp the handle with the arm next to the body:

- Inhale and raise the arm to horizontal.
- Exhale out at the end of the movement.

This exercise mainly develops the middle deltoid. Because the muscle is multipennate, composed of many fibers in the shape of a feather, it is best to vary the working angles in order to work all the fibers.


FINAL POSITION

LOW-PULLEY FRONT RAISES 10


Trapezius
Deltoid
Middle deltoid
Posterior deltoid
Teres minor
Infraspinatus
Teres major
Pectoralis major
Latissimus dorsi
Serratus anterior
Brachialis
Brachioradialis
Extensor carpi radialis longus
Extensor carpi radialis brevis
Extensor digitorum
Extensor carpi ulnaris
Flexor carpi ulnaris
Anconeus
Triceps brachii, medial head
Triceps brachii, lateral head
Triceps brachii, long head

Stand with the feet slightly apart, arms next to the body. Grasp the handle with an overhand grip with one hand:

- Inhale and raise the arm up to eye level.
- Exhale at the end of the movement.

This exercise contracts the deltoid (mainly the anterior deltoid) as well as the clavicular head of the pectoralis major and, to a lesser degree, the short head of the biceps brachii.


Trapezius
Spine of scapula
Infraspinatus
Posterior deltoid
Teres major
Acromion
Pennate fiber of the middle deltoid
Teres minor
Triceps brachii
Pectoralis major

SHOULDERS (LATERAL VIEW)

11 HIGH-PULLEY LATERAL EXTENSIONS


Trapezius
Deltoid
Anterior deltoid
Middle deltoid
Posterior deltoid
Brachialis
Triceps brachii
Brachioradialis
Acromion
Triceps brachii
Extensor carpi radialis longus
Teres minor
Infraspinatus
Rhomboid
Teres major
Latissimus dorsi
External oblique
Gluteus medius
Gluteus maximus
Anconeus
Extensor carpi ulnaris
Extensor digitorum
Extensor digiti minimi
Flexor carpi ulnaris
Extensor carpi radialis brevis


Cranium
6th cervical vertebra
Rhomboid minor
Clavicle
Spine of scapula
Acromion
Head of humerus
Rhomboid major
4th thoracic vertebra
Scapula
Deltoid tuberosity
Humerus
Rib
1st lumbar vertebra

RHOMBOID MAJOR AND MINOR MUSCLES

Located deep under the trapezius, the rhomboids pull the shoulder blades together toward the spine and press them against the rib cage.

In some people, the major and minor rhomboids are fused, creating one muscle.

Stand facing the pulleys with the arms extended to the front, gripping the right handle with the left hand and the left handle with the right hand:

- Inhale and extend arms to the side and back.
- Exhale at the end of the movement.

Return to the initial position with a controlled movement and begin again.

This exercise mainly contracts the posterior deltoid, infraspinatus, teres minor, and, at the end of the movement as the shoulder blades come together, the trapezius and deeper in, the rhomboids.



INITIAL POSITION

Comment: People who carry their shoulders forward because of chest muscle development can perform this exercise in addition to posterior shoulder work at a machine to help rebalance their posture.

To realign shoulders where they belong, work with moderate weights, and at the end of the movement squeeze the shoulders back.

LOW-PULLEY BENT-OVER LATERAL RAISES

12


Posterior deltoid
Infraspinatus
Middle deltoid
Teres minor
Teres major
Triceps brachii, lateral head
Biceps brachii
Brachialis
Trapezius
Anterior deltoid
Pectoralis major


Trapezius
Deltoid
Teres minor
Infraspinatus
Teres major
Rhomboid
Latissimus dorsi, upper fibers

PARTS WORKED

Stand with the feet apart, legs slightly bent, and lean forward from the waist, keeping a flat back. Grip a handle in each hand with the cables crossed:

- Inhale and raise the arms to the side to horizontal.
- Exhale at the end of the effort.

This exercise mainly works the posterior deltoid. At the end of the movement, as the shoulder blades squeeze together, the trapezius (middle and lower portions) and the rhomboids contract.

13 ONE-DUMBBELL FRONT RAISES


Sternocleidomastoid
Splenius
Levator scapula
Scalenes
Omohyoid
Trapezius
Pectoralis major, clavicular head
Deltoid
Middle deltoid
Posterior deltoid
Anterior deltoid
Triceps brachii, long head
Triceps brachii, lateral head
Brachioradialis
Anconeus
Extensor digitorum
Extensor carpi radialis brevis
Flexor carpi ulnaris
Extensor carpi ulnaris
Extensor digiti minimi
Pectoralis major
Extensor carpi radialis longus
Biceps brachii
Brachialis

Stand with the legs slightly apart, a straight back, and the abdominal muscles contracted. With arms extended, grasp a dumbbell in both hands with fingers crossed over each other as it rests against the thighs:

- Inhale and raise the dumbbell to eye level.
- Lower gently, avoiding abrupt movements.
- Exhale at the end of the movement.

This exercise mainly contracts the anterior deltoid, the clavicular head of the pectoralis major, and the short head of the biceps.

Note that all the fixators of the scapula are used during the isometric contraction, which allows the humerus to move from a stable position.


Rib
Sternal manubrium
Clavicle
Acromion
Pectoralis major, clavicular head
Coracoid process
Body of sternum
Humerus
Costal cartilages
Xiphoid process

CLAVICULAR HEAD OF THE PECTORALIS MAJOR ACTIVELY PARTICIPATES IN RAISING THE ARM ANTERIORLY

BARBELL FRONT RAISES

14


Sternocleidomastoid
Scalenes
Omohyoid
Trapezius
Pectoralis major, clavicular head
Deltoid
Anterior deltoid
Middle deltoid
Posterior deltoid
Teres major
Latissimus dorsi
Triceps brachii
Brachialis
Anconeus
Extensor digitorum
Extensor digiti minimi
Extensor carpi ulnaris
Flexor carpi ulnaris
Pectoralis major
Biceps brachii
Extensor carpi radialis longus
Pronator teres
Extensor carpi radialis brevis
Brachioradialis
Flexor carpi radialis



VARIATION
Front raise at a low pulley.

Stand with the legs slightly apart and the back straight, contracting the abdominal muscles. Hold the barbell with an overhand grip as it rests against the thighs:

- Inhale and raise the barbell with extended arms to eye level.
- Exhale at the end of the movement.

This exercise contracts the anterior deltoid, the clavicular head of the pectoralis major, the infraspinatus, and, to a lesser degree, the trapezius, serratus anterior, and short head of biceps.

If you continue raising the arms, the posterior deltoid contracts, reinforcing the work of the other muscles and allowing you to raise the arms to vertical.

The exercise may also be performed with your back to a low pulley and the cable passing between the legs.


1 Begin
2 End

THE MOVEMENT

Comment: The biceps brachii participates to a lesser degree in all anterior arm raises.

15 UPRIGHT ROWS


Trapezius
Superior portion
Middle portion
Inferior portion
Splenius
Sternocleidomastoid
Middle deltoid
Anterior deltoid
Brachialis
Posterior deltoid
Teres major
Rhomboids
Medial head
Lateral head
Long head
Triceps
Teres minor
Infraspinatus
Latissimus dorsi
External oblique
THE MOVEMENT

Stand with the legs slightly apart and back straight. Grasp the barbell with an overhand grip slightly wider than shoulder width as it rests against the thighs:

- Inhale and pull the barbell up along the body to the chin keeping the elbows as high as possible.
- Lower the bar in a controlled manner without abrupt movements.
- Exhale at the end of the effort.

This exercise mainly uses the deltoid, trapezius, and biceps, and to a lesser degree, the muscles of the forearms, the gluteal muscles, the lumbosacralis group, and the abdominal muscles.

This is a fundamental exercise that is comprehensive and helps develop a "Hercules" physique.



The deltoid raises the arm to horizontal. The trapezius takes over to rotate the scapula (shoulder blade), allowing the arm to continue its upward course.

NAUTILUS LATERAL RAISES 16


Sternohyoid
Pectoralis major, clavicular head
Pectoralis major
Clavicle
Sternum
Deltoid
Biceps brachii
Triceps brachii
Long head
Medial head
Brachialis
Pronator teres
Brachioradialis
Flexor digitorum superficialis
Flexor carpi ulnaris
Extensor carpi radialis longus
Palmaris longus
Flexor carpi radialis
Sternocleidomastoid
Levator scapula
Omohyoid
Trapezius
Scalenes
Middle deltoid
Anterior deltoid
Deltoid
Triceps brachii, lateral head

Sit at a machine, grasping the handles:

- Inhale and raise the elbows to horizontal
- Exhale at the end of the movement.

This exercise uses the deltoid (focusing most of the effort on the middle deltoid) and the supraspinatus, located under the deltoid. If raising the arm above horizontal, the upper portion of the trapezius also becomes involved.

Comment: This is an excellent beginning exercise because you don't have to worry about your form or positioning, and it allows long sets of repetitions.


2 End
1 Begin

THE MOVEMENT

17 PEC DECK REAR-DELT LATERALS


Trapezius, upper portion
Posterior deltoid
Anterior deltoid
Middle deltoid
Triceps brachii, lateral head
Brachialis
Brachioradialis
Trapezius, middle portion
Extensor carpi radialis longus
Extensor carpi radialis brevis
Anconeus
Infraspinatus
Teres minor
Trapezius, lower portion
Rhomboid
Teres major
Triceps brachii, long head
Latissimus dorsi
Serratus anterior
External oblique
Triceps brachii, medial head


Splenius
Sternocleidomastoid
Levator scapula
Trapezius
Infraspinatus
Supraspinatus fossa
Spine of scapula
Infraspinatus
Acromion
Teres minor
Greater tubercle
Scapula
Sulcus for radial nerve
Deltoid tuberosity
Humerus
Olecranon fossa
Capitulum, humerus
Trochlea, humerus
Medial epicondyle
Posterior deltoid
Middle deltoid
Deltoid
Teres minor
Rhomboids
Teres major
Long head
Lateral head
Medial head
Triceps
Lattissimus dorsi
External oblique
Thoracolumbar fascia
Gluteus medius
Gluteus maximus

INFRASPINATUS AND TERES MINOR

Both of these muscles arise from the posterior surface of the scapula (shoulder blade), pass onto the scapulohumeral articulation, adhering to its articular capsule, and insert at the greater tubercle of the humerus.

They play an important role in external rotation of the arm and reinforce the action of the shoulder ligaments by actively reinforcing the attachment of the arm to the chest.

Comment: In some people, the teres minor and infraspinatus are fused, forming one muscle.


THE MOVEMENT

Sit facing the machine, with the torso against the back pad, arms forward, gripping the handles:

- Inhale and separate the arms, squeezing the shoulder blades together at the end of the movement.
- Exhale.

This exercise mainly engages the posterior deltoid, infraspinatus, and teres minor and, at the end of the movement, when the shoulder blades squeeze together, the trapezius and rhomboids.

3
CHEST

1 INCLINE PRESSES 50
✚ PECTORALIS MAJOR TEAR 51
2 BENCH PRESSES 52
3 CLOSE-GRIP BENCH PRESSES 54
✚ BENCH PRESS AND ELBOW PAIN 54
4 DECLINE PRESSES 55
5 PUSH-UPS 56
6 PARALLEL BAR DIPS 57
7 DUMBBELL PRESSES 58
8 DUMBBELL FLYS 59
9 INCLINE DUMBBELL PRESSES 60
10 INCLINE DUMBBELL FLYS 61
11 PEC DECK FLYS 62
12 CABLE CROSSOVER FLYS 63
13 DUMBBELL PULLOVERS 64
14 BARBELL PULLOVERS 65

1 INCLINE PRESSES


Pectoralis major
Brachioradialis
Rectus abdominis, under the aponeurosis
Linea alba
External oblique
Teres major
Latissimus dorsi
Subscapularis
Serratus anterior
Flexor digitorum superficialis
Anterior deltoid
Biceps brachii
Coracobrachialis
Flexor carpi radialis
Palmaris longus
Flexor carpi ulnaris
Extensor carpi ulnaris
Anconeus
Triceps brachii, long head
Brachialis
Triceps brachii, medial head

PART OF THE PECTORALS MAINLY USED

Comment: Contrary to popular lore, the incline press does not tone the breasts and in no way prevents their sagging. Breasts are composed of adipose tissue containing the mammary glands, all of which is contained in a net of connective tissue that rests on top of the pectoralis major.


Clavicle
Trapezius
Deltoid
Infraspinatus
Teres minor
Teres major
Latissimus dorsi
Triceps brachii
Brachialis
Pectoralis major
Body of the breast
Mammary papilla
Serratus anterior
Biceps brachii

Sit on an incline bench angled at 45 to 60 degrees, grasp the barbell with an overhand grip wider than shoulder width:

- Inhale and lower the barbell to the sternal notch.
- Extend the arms.
- Exhale at the end of the movement.

This exercise mainly solicits the clavicular head of the pectoralis major, anterior deltoid, triceps brachii, serratus anterior, and pectoralis minor. This exercise may be done at a frame that guides the bar.

PECTORALIS MAJOR TEAR


7th cervical vertebra
1st rib
Pectoralis major, clavicular head
Clavicle
Acromion
Tear in the tendon of the clavicular head of the pectoralis major
Sternum
Humerus
6th rib
Costal cartilages
Omohyoid
Sternocleidomastoid
Sternohyoid
Trapezius
Clavicular head
Sternocostal head
Abdominal head
Pectoralis major
Anterior deltoid
Middle deltoid
Biceps brachii
Triceps brachii
Latissimus dorsi
Serratus anterior
Brachialis
Rectus abdominis
External oblique
Pronator teres

The pectoralis major originates at the anterior surface of the rib cage and inserts at the anterior surface of the upper end of the humerus.

It is a powerful muscle whose main function is to bring the arms together in front of the rib cage. (It is the hugging muscle.)

Unlike most sports, where pectoralis major injuries are rare, weightlifting, especially the bench press, can lead to small tears and even partial rupture of its tendon.

This ultimate injury is seen only in relatively powerful athletes using abnormally rapid force before the tendon has had time to strengthen. Sometimes it is associated with a low-calorie diet aimed at increased muscle definition. (These diets tend to weaken the muscles, tendons, and joints.)

The injury, which always occurs during heavy bench-pressing, generally affects only the tendon of the clavicular head of the pectoralis major.

A torn tendon is extremely painful, and the athlete may faint. Swelling and bruising often appear on the anterior surface of the arm, and retraction of the clavicular head leads to a hollow that is medial to the anterior deltoid.

The problem with this injury is that doctors often misdiagnose it. This mistake is unfortunately common but is understandable because during the posttraumatic examination the injured party is able to perform all the movements that indicate full motor function of the pectoralis major. Therefore, the injury appears to be a simple muscle tear rather than the more serious tear of the tendinous insertion.

For example, despite a tear of the clavicular head of the pectoralis major, anterior elevation of the arm, which is part of its function, is compensated for by the anterior deltoid. And abduction is performed by the sternal and abdominal heads of the pectoralis major.

If the tendon of the clavicular head of the pectoralis major is torn, it must be surgically reinserted onto the humerus as soon as possible. If this is not done promptly, retraction and fibrosis of the muscle occurs, and the operation will no longer be possible.

Although you can move your arm through its full range of motion without the superior head of the pectoralis major, you will never recover your initial strength and will be at a serious disadvantage if you want to continue heavy weight training.


Head of the humerus
Lesser tubercle
Greater tubercle
Anatomical neck
Bicipital groove
Section of the muscle corresponding to the clavicular head (susceptible to tearing)
Section of the muscle corresponding to the sternal portion
Section of the muscle corresponding to the chondro-abdominal portion
insertion of the pectoralis major

INSERTION OF THE PECTORALIS MAJOR MUSCLE ON THE HUMERUS DISPLAYING HOW THE TENDON TWISTS ON ITSELF CREATING A U-SHAPE

During bench presses or flys, the most lateral part of the pectoralis major tendon, which corresponds to the clavicular head, is put under the most stress.

Therefore, when lifting heavy weights, this is the tendon that tears or pulls away from its insertion.

2 BENCH PRESSES


PART OF THE PECTORALS MAINLY USED
Brachioradialis
Pronator teres
Subscapularis
Serratus anterior
Teres major
Latissimus dorsi
Pectoralis major
Coracobrachialis
Anterior deltoid
Biceps brachii
Flexor digitorum superficialis
Palmaris longus
Flexor carpi ulnaris
Extensor carpi ulnaris
Flexor carpi radialis
Anconeus
Triceps brachii
Medial head
Long head

Lie faceup on a horizontal bench, with buttocks on the bench and feet flat on the ground:

- Grasp the barbell with an overhand grip wider than shoulder width.
- Inhale and lower the bar to the chest with a controlled movement.
- Extend the arms and exhale at the end of the effort.

This exercise engages the complete pectoralis major muscle, pectoralis minor, anterior deltoid, serratus anterior, and coracobrachialis.



THE MOVEMENT

Variations

1. This movement may be performed while arching the back power-lifter style. This position brings the more powerful lower part of the pectoral muscle into play, allowing you to lift heavier weights.
2. Executing the extension with the elbows next to the body concentrates the work onto the anterior deltoid.
3. Varying the width of the hands isolates different parts of the muscle:
   - Hands closer together isolates the central part of the pectorals.
   - Hands wider apart isolates the lateral part of the pectorals.
4. Varying the angle of the barbell isolates different parts of the muscle:
   - Lowering the bar to the chondrocostal border of the rib cage isolates the lower part of the pectorals.
   - Lowering the barbell onto the middle part of the pectorals isolates the midline fibers.
   - Lowering the bar onto the sternal notch isolates the clavicular head of the muscle.
5. If you have back problems or want to isolate the pectorals, perform the extension with the legs raised.
6. Perform the extension at a frame that guides the bar.



CLASSIC POSITION



ARCHED-BACK VARIATION

Executing the bench press with an arched back, power-lifter style, limits the range of the movement and allows you to lift significantly heavier weights because it uses mainly the lower part of the pectorals, which are the strongest. In competition, the feet and the head should not move, and the buttocks should remain in contact with the bench. People with back problems should not perform this variation.



RAISED-LEG VARIATION

Performing the movement with raised legs helps prevent excessive arching, which can cause low back pain.

This variation diminishes the effort of the lower pectorals by working the middle and superior fibers more.


Hands gripping the bar tightly to stabilize the wrists
Chest raised to limit the lowering of the bar
Chin pulled in and head in contact with the bench
Back arched to limit the lowering of the barbell and rib cage positioned to mobilize the lower part of the pectorals, which are by far the most powerful
Buttocks in contact with the bench
Feet fixed and heels on the ground to ensure stabilization during the exercise

POSITIONING FOR A POWER BENCH PRESS



ATTENTION

1 For maximum safety, lock onto the bar with a grip in which the thumb and fingers oppose each other.

2 If the grip on the bar is not locked on in opposition, the bar could slip out of your hands and fall on the jaw or, worse, the neck and cause a serious injury.

3 CLOSE-GRIP BENCH PRESSES


Flexor digitorum superficialis
Flexor carpi ulnaris
Anconeus
Biceps brachii
Triceps brachii
Medial head
Lateral head
Long head
Teres major
Posterior deltoid
Serratus anterior
Latissimus dorsi
Subscapularis
Palmaris longus
Brachioradialis
Flexor carpi radialis
Pronator teres
Brachialis
Pectoralis major





PART OF THE PECTORAL MUSCLES THAT ARE MAINLY USED



EXECUTION WITH ELBOWS OPEN TO THE SIDES TO BETTER ISOLATE THE TRICEPS BRACHII

Lie on a horizontal bench with the buttocks on the bench and the feet on the ground, gripping the barbell with an overhand grip and wrists 4 to 15 inches apart, depending on the flexibility of the wrists: Inhale and lower the bar with a controlled movement to the chest, with the elbows out to the side. Extend and exhale at the end of the effort. This exercise develops the pectoral muscles at the sternal notch and the triceps brachii. (With this in mind, it may be included in a program for the arms.) By extending and keeping the elbows next to the body, a greater part of the work is performed by the anterior deltoid. This movement may be performed at a frame that guides the bar.

Attention: Depending on your physical structure, the narrow grip may cause wrist pain. In this case, use a wider grip.

Bench Presses and Elbow Pain

Elbow pain most often develops after bench pressing. This overuse injury is generally related to excessive training with long sets. In bench pressing, locking the extended arms at the end of the movement subjects the elbow to rubbing and microtrauma, which over time may lead to inflammation.

Comment: Occasionally, this condition can lead to intra-articular calcifications, which are particularly crippling. In this case, surgery is often the only solution for regaining complete arm extension.

At the first sign of elbow pain, avoid for several days exercises that involve arm extension in order to prevent serious injury.

When you resume exercises that include arm extension, avoid completely extending the forearms at the end of the movement until the pain has completely disappeared.

SECTION THROUGH THE ELBOW JOINT


Diaphysis of the humerus
Adipose mass
Adipose mass
Main zone of friction prone to inflammation injuries
Olecranon fossa
Olecranon
Articular cavity
Trochlea, cartilage
Coronoid process
Ulna

With repeated extension of the forearm, the olecranon butts up against the olecranon fossa of the humerus. The articulation then suffers from microtrauma, which over time may generate painful inflammation at the dorsal surface of the elbow.

DECLINE PRESSES 4


Pectoralis major
Brachioradialis
Rectus abdominis
Serratus anterior
Brachialis
Subscapularis
External oblique
Flexor carpi ulnaris
Palmaris longus
Superior finger flexors
Flexor carpi radialis
Triceps brachii
Long head
Short head
Pronator teres
Latissimus dorsi
Teres major

THE MOVEMENT



Lie on a decline bench (between 20 and 40 degrees), with the head angled down and feet fixed to prevent sliding and grasp the barbell with an overhand grip shoulder width or more:

- Inhale and lower the barbell to the lower pectorals with a controlled movement.
- Extend the arms and exhale at the end of the movement.

This exercise contracts the pectoralis major (mainly its inferior fibers), triceps brachii, and the anterior deltoid.

This exercise is useful for outlining the inferior groove of the pectorals. Using light weights and lowering the bar to the neck stretches the pectoralis major correctly. The decline press may be performed at a frame that guides the bar.

PECTORALIS MAJOR


Clavicle
Pectoralis major, clavicular head
Acromion
Pectoralis major, sternocostal head
Bicipital groove
Sternum
Pectoralis major tendon
Humerus
Pectoralis major, abdominal head
Chondrocostal border of rib cage
Rib

PECTORALIS MAJOR MUSCLE INSERTIONS


Sternum
Clavicle
Scapula
Humerus
Rib



PART OF PECTORALIS MUSCLES MAINLY USED

5 PUSH-UPS


Sternocleidomastoid
Trapezius
Scalenes
Anterior deltoid
Middle deltoid, pennate fibers
Posterior deltoid
Triceps brachii
Pectoralis major, clavicular head
Pectoralis major
Biceps brachii
Brachioradialis
Pronator teres
Flexor carpi radialis
Abductor pollicis longus
Extensor pollicis brevis
Extensor carpi radialis longus
Anconeus
Extensor carpi radialis brevis
Extensor digitorum
Extensor digiti minimi
Extensor carpi ulnaris



INITIAL POSITION

Support yourself facedown on the ground, with arms extended, hands shoulder-width (or more) apart, and feet touching or slightly apart:

- Inhale and bend the elbows to bring the rib cage close to the ground without arching the low back excessively.
- Push back up to complete arm extension.
- Exhale at the end of the movement.

This movement is excellent for the pectoralis major and the triceps brachii.



PART OF THE PECTORAL MUSCLES MAINLY USED

Varying the tilt of the chest focuses the work on different parts of the pectorals:

- Feet higher isolates the the clavicular head of the pectoralis major.
- Chest higher isolates the inferior part of the pectoralis major.

Varying the width of the hands focuses the work on different parts of the pectorals:

- Hands wider isolates the lateral part of the pectoralis major.
- Hands closer together isolates the sternal head of the pectoralis major.



While performing push-ups the serratus anterior contracts to maintain the scapula against the rib cage, locking the arms onto the torso.

PARALLEL BAR DIPS

6


Triceps brachii
Long head
Lateral head
Medial head
Brachialis
Olecranon
Anconeus
Extensor carpi radialis longus
Flexor carpi ulnaris
Extensor carpi ulnaris
Extensor digitorum
Middle deltoid
Posterior deltoid
Trapezius
Anterior deltoid
Biceps brachii
Pectoralis major
Serratus anterior
Brachioradialis
Extensor carpi radialis brevis



PART OF THE PECTORAL MUSCLES MAINLY USED

Hang from the parallel bars with arms extended and legs suspended:

- Inhale and bend the elbows to bring the chest level with the bars.
- Return to the extended arm position.
- Exhale at the end of the effort.

The more the chest is angled forward during the exercise, the more the inferior fibers of the pectorals are used. Conversely, the more vertical the chest, the more the triceps brachii will be used.

This exercise is excellent for stretching the pectoralis major and for working on the flexibility of the shoulder girdle. However, it is not recommended for beginners because it requires a certain amount of initial strength.

If you are a beginner, use a dips machine to familiarize yourself with the movement.

Sets of 10 to 20 repetitions provide the best results.

For developing more strength and also more size, athletes used to this movement may use a weight belt, or hang a weight from their legs.



EXECUTING DIPS AT A MACHINE

1 Initial position
2 Final position



THE MOVEMENT

Comment: Execute the dips with caution to prevent shoulder trauma.

7 DUMBBELL PRESSES


Pectoralis major
Extensor digiti minimi
Extensor digitorum
Flexor carpi ulnaris
Extensor carpi ulnaris
Extensor carpi radialis brevis
Anconeus
Extensor carpi radialis longus
Middle deltoid
Anterior deltoid
Trapezius
Biceps brachii
Brachioradialis
Brachialis
Triceps brachii



PART OF THE PECTORAL MUSCLES MAINLY USED

Lie faceup on a horizontal bench, with feet flat on the ground for stability and elbows bent, holding dumbbells with an overhand grip at the chest level:

- Inhale and extend the arms vertically while rotating the forearms so that the palms face each other.
- Once the hands face each other, perform an isometric contraction to focus the effort on the sternal head of the pectoralis major.
- Exhale at the end of the movement.

This exercise is similar to the bench press, but with its greater range of motion, it stretches the pectoralis muscles.

Although not contracted as intensely, the triceps brachii and anterior deltoid are also used.



VARIATION

Executing the exercise without rotating the forearms.

DUMBBELL FLYS 8


Coracobrachialis
Pectoralis major, sternocostal head
Pectoralis major, clavicular head
Anterior deltoid
Sternum
Scalenes
Sternocleidomastoid
Trapezius
Flexor digitorum superficialis
Palmaris longus
Flexor carpi radialis
Pronator teres
Biceps brachii
Brachialis
Triceps brachii, lateral head
Middle deltoid
Subscapularis
Serratus anterior
Latissimus dorsi
Teres major
Abductor pollicis longus
Extensor pollicis brevis
Extensor carpi ulnaris
Flexor carpi ulnaris
Extensor digiti minimi
Extensor digitorum
Extensor carpi radialis brevis
Brachioradialis
Extensor carpi radialis longus
Anconeus

Lie on a narrow bench that won't interfere with the shoulder movement and hold a dumbbell in each hand with arms extended or slightly bent to relieve stress on the joint:

- Inhale and open the arms to horizontal.
- Raise the arms to vertical while exhaling.
- Perform a small isometric contraction at the end of the movement to emphasize the work on the sternal head of the pectoralis major.

This exercise is never performed with heavy weights.

This exercise focuses the work on the pectoralis major. It serves as a basic exercise to increase thoracic expansion, which contributes to increased pulmonary capacity. It also develops muscle flexibility.



THE MOVEMENT



PART OF THE PECTORAL MUSCLES MAINLY USED

Comment: To avoid the risk of tearing the pectoral muscles, perform the exercise with extreme caution when using heavier weights.

9 INCLINE DUMBBELL PRESSES


Pectoralis major, clavicular head
Deltoid
Anterior deltoid
Middle deltoid
Pectoralis major
Biceps brachii
Subscapularis
Teres major
Brachialis
Triceps brachii, medial head
Triceps brachii, long head
Serratus anterior
Latissimus dorsi





PART OF THE PECTORAL MUSCLES MAINLY USED

Sit on a bench with an angle of no more than 60 degrees (to prevent too much work with the deltoid), with elbows bent and grasping the dumbbells with an overhand grip:

- Inhale and extend the arms vertically, bringing the dumbbells together.
- Exhale at the end of the movement.

This exercise, which is midway between an incline press and incline dumbbell fly, works the pectorals (mainly the clavicular head) and increases their flexibility. It also contracts the anterior deltoid, the serratus anterior, and the pectoralis minor (these last two muscles are fixators of the scapula, which stabilize the arm at the torso). It also uses the triceps brachii, but not as intensely as the barbell press does.

Variation: Beginning the press with the hands in an underhand grip and rotating the wrists halfway to an overhand grip so that the dumbbells face each other focuses the effort on the sternal head of the pectoralis major.



FINAL POSITION

INCLINE DUMBBELL FLYS

10


Flexor pollicis longus
Extensor carpi radialis longus
Brachioradialis
Deltoid
Coracobrachialis
Biceps brachii
Flexor digitorum superficialis
Palmaris longus
Flexor carpi ulnaris
Flexor carpi radialis
Biceps brachii, aponeurotic expansion
Medial epicondyle
Pronator teres
Brachialis
Triceps brachii
Medial head
Long head
Teres major
Subscapularis
Latissimus dorsi
Serratus anterior
Pectoralis major

Sit on a bench angled between 45 and 60 degrees, dumbbells in hand and arms extended vertically or slightly bent to ease stress when bringing the arms together:

- Inhale and extend the arms to horizontal.
- Raise the arms to vertical while exhaling.

This movement should not be performed with heavy weights. It focuses the effort mainly on the clavicular head of the pectoralis major. Along with the pullover, it is a fundamental exercise for developing thoracic expansion.



FINAL POSITION



PART OF THE PECTORAL MUSCLES MAINLY USED

11 PEC DECK FLYS


Biceps brachii
Deltoid, anterior division
Triceps brachii, medial head
Brachialis
Triceps brachii, long head
Rectus abdominis
External oblique
Humerus
Pectoralis major
Scapula
Rib
Intercostal muscle

Sit at the machine with the arms open and horizontal, bent at the elbows. Rest the forearms on the pads, with the forearms and wrists relaxed:

- Inhale and squeeze the arms together. Exhale at the end of the movement.

This exercise works the pectoralis major by stretching it. As the elbows come together, focus the effort onto the sternal head of the pectoralis major.

This exercise also develops the coracobrachialis and the short head of the biceps brachii. Long sets allow you to pump the muscles intensely.

This exercise helps beginners develop enough strength to move onto more complex movements.


Biceps brachii
Anterior deltoid
Pectoralis major
Pectoralis major, clavicular head
Triceps brachii, long head
Coracobrachialis
Coracobrachialis
Teres major
Latissimus dorsi
Sternum
Serratus anterior
Subscapularis



FINAL POSITION



VARIATION

At a machine applying force with the hands.

CABLE CROSSOVER FLYS

12


Clavicle
Acromion
Trapezius
Deltoid
Clavicle
1st rib
Acromion
Coracoid process
Humerus
Ulna
Radius
Triceps, lateral head
Brachialis
Biceps brachii
Latissimus dorsi
Sternocleidomastoid
Serratus anterior
Pectoralis major
External oblique
Rectus abdominis, under the aponeurosis
Linea alba
Pectoralis minor
Manubrium sterni
Cartilage
Body of sternum
Intercostal muscles
Vertebre lumbalis
Sacrum
Os coxa

PART OF THE PECTORAL MUSCLES MAINLY USED

Stand with the legs slightly apart and lean the torso forward a bit, with the arms spread apart and elbows slightly bent:

- Inhale and squeeze the arms together until the wrists touch. Exhale at the end of the contraction.

This is an excellent exercise for working the pectoralis major muscles. Sets with a lot of reps allow you to pump the muscle well. You can work all the fibers of the pectoralis major by varying the angle of the chest and the working angle of the arms (squeezing the arms at various heights).

Comment: Cable crossover flys also contract the pectoralis minor, which is located deeper than the pectoralis major. Besides stabilizing the scapula (shoulder blade), this muscle also pulls it forward.



THE MOVEMENT



1 **Crossed arm:**
Increases the focus onto the sternal head of the pectoralis major.

2 Classic execution.


Flexor carpi ulnaris
Palmaris longus
Flexor digitorum superficialis
Flexor carpi radialis
Brachioradialis
Biceps brachii
Deltoid
Pronator teres
Brachialis
Sternocleidomastoid
Triceps brachii, medial head
Trapezius
Pectoralis major
Triceps, long head
Coracobrachialis
Latissimus dorsi
Subscapularis
Teres major
Serratus anterior

INITIAL POSITION

13 DUMBBELL PULLOVERS


Anconeus
Extensor carpi radialis longus
Brachioradialis
Medial head
Lateral head
Long head
Triceps brachii
Latissimus dorsi
Serratus anterior
Pectoralis major
External oblique
Thoracolumbar fascia
Extensor digitorum
Extensor carpi ulnaris
Flexor carpi ulnaris
Brachialis
Biceps brachii
Deltoid
Infraspinatus
Trapezius
Teres major
Teres minor
Abductor pollicis longus
Extensor digiti minimi
Extensor carpi radialis brevis
Extensor pollicis brevis

THE MOVEMENT

Lie on a bench with the feet flat on the ground and hold a dumbbell in the palms of both hands, with the thumbs surrounding the handle and arms extended:

- Inhale and lower the dumbbell behind the head, bending slightly at the elbows.
- Exhale and return to the initial position.

This exercise develops the bulk of the pectoralis major, long head of triceps brachii, teres major, latissimus dorsi, serratus anterior, rhomboids, and pectoralis minor. The last three muscles stabilize the scapula so that the humerus can move from a stable base.

STABILIZERS OF THE SHOULDER BLADES


Cranium
Vertebra
Levator scapula
Spine of scapula
Rhomboid minor
Rhomboid major
Serratus anterior
Levator scapula
Clavicle
Acromion
Pectoralis minor
Sternum
Serratus anterior
Rib
Costal cartilage
BACK
FRONT

If you use this exercise to open the rib cage, you must work with light weights and avoid bending too much at the elbows. If possible, use a convex bench or place yourself across a horizontal bench and position the pelvis lower than the shoulder girdle. Take in a deep breath at the beginning of the movement and breathe out only at the end of the execution.





PERFORMING THE MOVEMENT AT A MACHINE



VARIATION POSITION ACROSS A BENCH

Placing yourself transversely across a bench opens the rib cage.

BARBELL PULLOVERS

14


THE MOVEMENT
Palmaris longus
Flexor carpi radialis
Pronator teres
Brachialis
Triceps brachii, long head
Biceps brachii
Pectoralis major
Brachioradialis
Extensor carpi ulnaris
Flexor carpi ulnaris
Anconeus
Triceps brachii, medial head
Triceps brachii, lateral head
Posterior deltoid
Teres minor
Infraspinatus
Subscapularis
Teres major
Serratus anterior
Latissimus dorsi
INSERTIONS OF THE SERRATUS ANTERIOR
Ribs
Sternum
Serratus anterior
Humerus
Vertebra
Scapula

SERRATUS ANTERIOR MUSCLE


Scapula
Acromion
Coracoid process
Glenoid cavity
Lateral border
Vertebra
Rib
Intercostal muscles
Costal cartilages
Serratus anterior
Spinous process, thoracic vertebra

With arms extended, hold the barbell with an overhand grip and hands shoulder-width apart:

- Inhale and expand the chest as much as possible, lowering the barbell behind the head bending slightly at the elbows.
- Exhale while returning to the initial position.

This exercise develops the pectoralis major, long head of the triceps brachii, teres major, latissimus dorsi, serratus anterior, rhomboids, and pectoralis minor.

This is an excellent movement for developing the flexibility and expansion of the rib cage. It should be performed with light weights using proper form and breathing.

4

BACK


Parietal
Occipital
Semispinalis capitis
Splenius cervicis
Occipitalis
Rhomboid minor
Mastoid
Abductor pollicis longus
Sternocleidomastoid
Splenius capitis
Extensor carpi radialis brevis
Flexor carpi ulnaris
Trapezius
Brachioradialis
Extensor carpi ulnaris
Rhomboid major
Radius
Biceps brachii
Brachialis
Ulna
Extensor digiti minimi
Extensor digitorum
Humerus
Olecranon
Acromion
Anconeus
Clavicle
Extensor carpi radialis longus
Levator scapula
Biceps brachii, tendon
Infraspinatus
Medial head
Teres minor
Triceps brachii
Lateral head
Teres major
Deltoid
Long head
Spine of scapula
Teres major
Supraspinatus
Teres minor
Iliocostalis thoracis
Infraspinatus
Spinalis thoracis
Rhomboid major
Latissimus dorsi
Latissimus dorsi
Floating rib
External oblique
Internal oblique
Thoracolumbar fascia
Iliac crest
Gluteus medius
Os coxa

1 REVERSE CHIN-UPS 67
2 CHIN-UPS 68
3 LAT PULL-DOWNS 70
4 BACK LAT PULL-DOWNS 71
✚ TRICEPS BRACHII TEARS 72
5 CLOSE-GRIP LAT PULL-DOWNS 73
6 STRAIGHT-ARM LAT PULL-DOWNS 74
7 SEATED ROWS 75
8 ONE-ARM DUMBBELL ROWS 76
9 BENT ROWS 77
10 FREESTANDING T-BAR ROWS 78
11 T-BAR ROWS WITH ABDOMINAL SUPPORT 79
12 STIFF-LEGGED DEADLIFTS 80
13 SUMO DEADLIFTS 81
14 DEADLIFTS 82
✚ BICEPS BRACHII TENDON TEAR 84
✚ LOW BACK PAIN ✚ SHOULD YOU ARCH YOUR BACK? 86
15 BACK EXTENSIONS 87
16 TORSO EXTENSIONS AT A MACHINE 88
17 UPRIGHT ROWS 89
18 BARBELL SHRUGS 90
19 DUMBBELL SHRUGS 91
20 MACHINE SHRUGS 92

REVERSE CHIN-UPS

1


Extensor carpi ulnaris
Extensor digiti minimi
Extensor digitorum
Anconeus
Triceps brachii, lateral head
Teres major
Deltoid
Infraspinatus
Teres minor
Teres major
Subscapularis
Latissimus dorsi
Serratus anterior
Flexor carpi ulnaris
Flexor digitorum
Palmaris longus
Flexor carpi radialis
Brachioradialis
Pronator teres
Triceps brachii, medial head
Brachialis
Triceps brachii, long head
Biceps brachii
Coracobrachialis

Hang from a bar with an underhand grip, hands shoulder-width apart:

- Inhale and push out the chest as you raise the chin to the bar.
- Exhale at the end of the movement.

This movement develops the latissimus dorsi and teres major and is associated with the intense work of the biceps brachii and brachialis. Therefore, it could be included in an arm workout program.

This exercise also contracts the middle and lower portions of the trapezius, the rhomboids, and the pectorals.

Performing this exercise takes a certain amount of strength; use a high pulley to make it easier.

MUSCLE INSERTIONS AT THE SHOULDER BLADE


Trapezius
Infraspinatus
Teres minor
Levator scapula
Supraspinatus
Infraspinatus
Serratus anterior
Teres major
Teres minor
Deltoid
Triceps brachii
Biceps brachii
Coracobrachialis
Deltoid
Omohyoid
Supraspinatus
Subscapularis
Serratus anterior
Triceps brachii
Teres major

POSTERIOR VIEW

ANTERIOR VIEW

2 CHIN-UPS


Biceps brachii
Teres minor
Sternocleidomastoid
Cranium
Mastoid process
7th cervical vertebra
Brachioradialis
Trapezius
Splenius capitis
Extensor carpi radialis longus
Brachialis
Deltoid
Clavicle
Abductor pollicis longus
Extensor pollicis brevis
Extensor digiti minimi
Scapula
Humerus
Extensor digitorum
Extensor carpi ulnaris
Extensor carpi radialis brevis
Radius
Ulna
Flexor carpi ulnaris
Brachioradialis
Anconeus
Triceps brachii
Teres major
Teres major
Rhomboid minor
Infraspinatus
Rhomboid
Trapezius, lower portion
Rhomboid major
Latissimus dorsi
Latissimus dorsi
Thoracolumbar fascia
External oblique
Gluteus medius
Greater trochanter
Iliac crest
Gluteus maximus
Os coxa
Tensor fascia lata
Posterior superior iliac spine
Adductor magnus
Greater trochanter
Iliotibial band
Coccyx
Quadriceps, vastus lateralis
Femur
Biceps femoris, long head
Semitendinosus
Biceps femoris, short head
Semimembranosus



VARIATIONS

The chin-up may be performed by bringing the back of the neck almost level with the bar.

ATTENTION

To avoid tendinitis of the distal tendon of the biceps brachii (the biceps tendon that inserts at the radius), keep the elbows slightly bent.

Hang from a fixed bar with a very wide overhand grip:

- Inhale and pull the chest up to the level of the bar.
- Exhale at the end of the movement.

Return to the initial position with a controlled descent and begin again.

This exercise takes a certain amount of strength and is excellent for developing the latissimus dorsi and teres major and, when the shoulder blades come together at the top of the chin-up, the rhomboids and middle and lower portions of the trapezius. It also works the biceps brachii, brachialis, and brachioradialis.

Variations: By sticking out the chest you can raise your chest to chin level. To increase the intensity, wear a weight belt. Keeping the elbows in next to the body during the movement contracts mainly the external fibers of the latissimus dorsi and develops the width of the back.

Bringing the elbows back and the chest out as you raise the chin to the bar mainly solicits the upper and central fibers of the latissimus dorsi and those of the teres major. This exercise develops the bulk of the back when the shoulder blades come together and the rhomboids and the upper and lower portion of the trapezius are used equally.

Comment: Although not as strongly contracted, the pectoralis major works with the latissimus dorsi and teres major to create the angle between the arm and the trunk.

BRINGING THE BAR TO THE NECK WITH ARMS ALONGSIDE THE BODY



Bringing the elbows alongside the body
mainly solicits the lateral fibers of the latissimus dorsi
and develops the width of the back.

BRINGING THE BAR TO THE CHEST WITH ELBOWS BEHIND



Pulling the elbows back to raise the chin to the bar
mainly solicits the upper and central fibers of the latissimus dorsi.
This variation is excellent for developing the bulk of the back.



In both monkeys and humans, the latissimus dorsi
and teres major are particularly well developed.

Originally, the teres major and latissimus dorsi muscles of our far-off ancestors played a role in their getting around on all fours by helping them to push off with the front paws.

As our ancestors became tree climbers, these muscles became powerful, specializing in vertical displacement. Returning to the ground, our more recent ancestors adopted bipedal displacement without losing the possibility of climbing. For this reason we possess powerful back muscles capable of pulling our bodies up, still allowing us to climb trees.

Comment: The main difference between our locomotor mechanism and that of our close simian relatives is the development of lower extremities that allow us to walk on two legs. Our chest and upper extremities have not developed differently and have the same structure and proportions. Contrary to popular opinion, apes do not have relatively big arms; we just have big legs!



3

LAT PULL-DOWNS


Biceps brachii
Brachialis
Sternocleido-mastoid
Splenius
Trapezius
Deltoid
Infraspinatus
Teres minor
Teres major
Latissimus dorsi
Triceps brachii
Aponeurosis for insertion of the latissimus dorsi
External oblique
Extensor carpi radialis brevis
Flexor carpi ulnaris
Extensor digitorum
Extensor carpi ulnaris
Anconeus
Extensor carpi radialis longus
Brachioradialis

Sit facing the machine with the legs positioned under the pads, gripping the bar in with a wide overhand grip: Inhale and pull the bar down to the sternal notch while puffing out the chest and pulling the elbows back. Exhale at the end of the movement.

This exercise develops the bulk of the back. It mainly works the upper and central fibers of the latissimus dorsi. The middle and lower portions of the trapezius, the rhomboids, the biceps brachii, the brachialis, and, to a lesser extent, the pectorals also contract.


12th cervical vertebra
Trapezius
Infraspinatus
Deltoid
Clavicle
Acromion
Spine of scapula
Teres minor
Teres major
Rhomboid major
Triceps brachii, long head
Triceps brachii, lateral head
Thoracolumbar fascia
Scapula
Teres major
12th vertebra
Latissimus dorsi
Trapezius
Floating rib
External oblique
Lumbar triangle
Gluteus medius
Iliac crest
Sacrum
Gluteus maximus
Greater trochanter
Neck of femur
Greater trochanter
Tensor fascia lata
Head of femur
Adductor magnus
Ischial tuberosity
Biceps femoris, long head
Coccyx
Femur
Gracilis
Semitendinosus


Ulna
Radius
Humerus
Spine of scapula
Acromion
Teres major
Scapula

The teres major gets its name from its circular transverse section.



VARIATION WITH A WIDE BAR AND PALMS FACING EACH OTHER

BACK LAT PULL-DOWNS

4


Splenius
Sternocleidomastoid
Trapezius
Spine of scapula
Trapezius, lower portion
Biceps brachii
Brachioradialis
Triceps brachii
Deltoid
Brachialis
Extensor carpi radialis brevis
Extensor carpi ulnaris
Flexor carpi ulnaris
Extensor digitorum
Olecranon
Anconeus
Rhomboid
Extensor carpi radialis longus
Teres minor
Teres major
Aponeurosis of insertion of latissimus dorsi
Infraspinatus
Latissimus dorsi
External oblique
Os coxa


THE MOVEMENT

ACTION OF TERES MAJOR AND LATISSIMUS DORSI


Supraspinatus
Acromion
Clavicle
Humerus
Infraspinatus
Teres minor
Spine of scapula
Teres major
Rib
7th thoracic vertebra
Latissimus dorsi
Iliac crest
Sacrum
Vertebral aponeurosis
Coccyx
Pubic symphysis

Sit facing the machine with the thighs positioned under the pads, grasping the bar with a wide overhand grip:

- Inhale and pull the bar down to the back of the neck, bringing the elbows alongside the body.
- Exhale at the end of the movement.

This exercise develops the width of the back. It works the latissimus dorsi (mainly the lateral and lower fibers), the teres major, the forearm flexors (biceps brachii, brachialis, and brachioradialis), the rhomboids, and the lower portion of the trapezius. The latter two muscles come into play when the shoulder blades are pulled together. Back lat pull-downs help beginners develop enough strength to move on to chin-ups.


VARIATION AT A MACHINE WITH A FIXED AXIS

TRICEPS BRACHII TEARS


Scapula
Brachioradialis
Extensor carpi radialis longus
Extensor carpi radialis brevis
Extensor digitorum longus
Extensor carpi ulnaris
Tear of long head of triceps brachii
Biceps brachii
Deltoid
Metacarpal
Humerus
Brachialis
Carpal
Radius
Ulna
Anconeus
Triceps brachii
Lateral head
Long head
Medial head
Teres minor
Teres major
Infraspinatus
Trapezius
Latissimus dorsi
Lateral head
Long head
Medial head
Triceps brachii

Heavy training of the back and injury to the long head of the triceps brachii

Although it is not the most-used muscle when working the back, the long head of the triceps brachii is the most frequently injured muscle during back lat pull-downs with heavy weights or during chin-ups with added weight.

The latissimus dorsi is a powerful, fan-shaped muscle that attaches the arm to the rib cage, and whose distal tendon is strongly attached to the humerus.

This is the main climbing muscle.

The long head of the triceps brachii, on the other hand, is a smaller muscle whose main function is to extend the forearm and secondarily to bring the arm toward the rib cage. In this way it complements the action of the latissimus dorsi.

Tearing of the long head of the triceps occurs when the muscle is fatigued, most frequently after an improper warm-up.

It only takes a sudden relaxation of the latissimus dorsi during chin-ups with added weight to immediately shift the tension to the long head of the triceps.

This tendon may partially tear, most often close to its insertion on the scapula. (Fortunately complete tears are infrequent.)

Unlike incapacitating shoulder injuries, which may completely halt upper-body training, a tear in the long head of the biceps is less devastating.

You can still perform back exercises such as seated rows or T-bar rows and movements for the triceps such as forearm extensions at a high pulley with the elbows next to the body despite the injury as long as you begin with lighter weights.

However, a brief rest period is recommended before beginning upper-body training.

Comment: Tearing the long head of the triceps may also occur during bench presses. To prevent this triceps tear, warm up with stretching exercises


Extensor carpi radialis longus
Extensor carpi radialis brevis
Ulna
Radius
Humerus
Anconeus
Brachioradialis
Biceps brachii
Triceps brachii
Brachialis
Medial head
Lateral head
Long head
Triceps brachii
Deltoid
Trapezius
Teres minor
Teres major
Infraspinatus
Rhomboid major
Latissimus dorsi
Acromion
Clavicle
Scapula
Rib
Thoracic vertebra
Lumbar vertebra

TRICEPS STRETCH

Stand or sit with your back straight and one arm raised vertically beside your head. Bend the arm at the elbow and touch the top of the back with your hand. With the other hand grasp the elbow and slowly try to pull it behind your head.

This stretches the teres major, the long head of the triceps brachii, and, to a lesser extent, the latissimus dorsi.

Variation: Pull the hand rather than the elbow. For greater intensity, place the raised arm against a wall.

CLOSE-GRIP LAT PULL-DOWNS

5


Flexor digitorum
Palmaris longus
Flexor carpi radialis
Brachioradialis
Pronator teres
Brachialis
Triceps, medial head
Biceps brachii
Flexor carpi ulnaris
Extensor carpi ulnaris
Anconeus
Triceps brachii, lateral head
Triceps brachii, long head
Coracobrachialis
Teres minor
Infraspinatus
Teres major
Latissimus dorsi
Subscapularis
Serratus anterior
Pectoralis major
FINAL POSITION

Sit and face the machine with knees positioned under the pads.

- Inhale and bring the handle to the sternum while expanding the chest and leaning slightly back with the torso.
- Exhale at the end of the movement.

This exercise develops the latissimus dorsi and teres major.

When the shoulder blades come together, the trapezius and the posterior deltoid contract.

As with every pulling exercise, the biceps brachii and brachialis contract, and when the palms face each other, the brachioradialis comes into play.

6 STRAIGHT-ARM LAT PULL-DOWNS


Middle deltoid
Triceps brachii, lateral head
Brachialis
Brachioradialis
Extensor carpi radialis longus
Sternocleidomastoid
Splenius
Trapezius
Posterior deltoid
Teres minor
Infraspinatus
Rhomboid
Extensor carpi radialis brevis
Extensor digitorum
Extensor digiti minimi
Teres major
Latissimus dorsi
External oblique
Aponeurosis for latissimus dorsi
Anconeus
Triceps brachii, long head
Flexor carpi ulnaris
Extensor carpi ulnaris
Triceps brachii, medial head


MUSCLES USED
Scapula
Glenoid cavity
Teres major
Latissimus dorsi
Triceps brachii, lateral head
Triceps brachii, long head
Head of humerus
10th, 11th, 12th ribs
Iliac crest
Sacrum
Os coxa
Pubis

Stand and face the machine with feet slightly apart; grip the bar with an overhand grip, arms extended and shoulder-width apart; fix the back and contract the abdominal core:

- Inhale and bring the bar to the thighs, keeping the arms extended (elbows can be slightly bent).
- Exhale at the end of the movement.

This exercise, which works the latissimus dorsi, strengthens the teres major and the long head of the triceps, which stabilizes the arm–trunk hinge.

Comment: Many swim coaches use this exercise to develop a powerful crawl stroke.


THE MOVEMENT

SEATED ROWS 7




Sternocleidomastoid
Splenius capitis
Levator scapula
Spine of scapula
Trapezius
Rhomboid major
Teres minor
Teres major
Pectoralis major
Latissimus dorsi
Serratus anterior
External oblique
Erector spinae, under the thoracolumbar fascia
Infraspinatus
Posterior deltoid
Medial deltoid
Long head
Lateral head
Medial head
Triceps brachii
Brachioradialis
Extensor carpi radialis longus
Extensor carpi radialis brevis
Extensor digitorum
Abductor pollicis longus
Extensor pollicis brevis
Extensor carpi ulna
Extensor digiti minimi
Anconeus
Flexor carpi ulnaris

Sit facing the machine, feet resting on the foot pad and the torso bent forward. Inhale and bring the handle to the base of the sternum by straightening the back and pulling the elbows back as far as possible. Exhale at the end of the movement and return smoothly to the initial position.

This exercise works the bulk of the back; it focuses the effort on the latissimus dorsi, teres major, posterior deltoid, biceps brachii, and brachioradialis, and at the end of the movement, when the shoulder blades come together, the trapezius and rhomboids.

While raising the chest, the spinal muscles (erector spinae) also contribute.

Allowing the weight to pull you on the return helps develop back flexibility.

Attention: To prevent back injury, never round the back when performing seated rows with heavy weights. ⚠



THE MOVEMENT



Variations with a wide bar:

1. An underhand grip isolates the inferior portion of the trapezius.
2. An overhand grip isolates the posterior deltoid and the middle portion of the trapezius.

8 ONE-ARM DUMBBELL ROWS


Infraspinatus
Rhomboid major
Cervical vertebra
Levator scapula
Splenius
Latissimus dorsi
Trapezius
Scalene
Thoracolumbar fascia
Teres major
Teres minor
External oblique
Serratus anterior
Pectoralis major
Triceps brachii
Long head
Lateral head
Medial head
Sternocleidomastoid
Spine of scapula
Anterior deltoid
Middle deltoid
Posterior deltoid
Deltoid
Biceps brachii
Brachialis
Brachioradialis
Extensor carpi radialis longus
Anconeus
Extensor digitorum
Extensor carpi ulnaris
Flexor carpi ulnaris
Extensor carpi radialis brevis
Extensor digiti minimi
Extensor pollicis brevis
Extensor pollicis longus
Abductor pollicis longus

Grasp a barbell with the palm facing in; use the opposite hand and knee on the bench to support the back:

- Inhale and lift the upper arm and elbow as high as possible next to the body with the elbow bent.
- Exhale at the end of the movement.

To maximize the contraction, rotate the torso slightly toward the working side at the end of the row.

This exercise mainly works the latissimus dorsi, teres major, and posterior deltoid, and, at the end of the contraction, the trapezius and rhomboids. The forearm flexors (biceps brachii, brachialis, and brachioradialis) are also used.


FINAL POSITION

BENT ROWS 9


Splenius
Levator scapula
Sternocleidomastoid
Scalenes
Trapezius
Posterior deltoid
Infraspinatus
Teres minor
Rhomboid major
Teres major
Triceps brachii
Latissimus dorsi
Deltoid
Middle deltoid
Anterior deltoid
Brachialis
Biceps brachii
Brachioradialis
Pectoralis major
Extensor carpi radialis longus
Extensor carpi radialis brevis
Extensor digitorum
Extensor carpi ulnaris
Flexor carpi ulnaris
Palmaris longus
Anconeus
Erector spinae, under the thoracolumbar fascia
External oblique
Iliac crest
Gluteus medius
Tensor fascia lata
Gluteus maximus
Greater trochanter
Rectus femoris
Vastus lateralis
Quadriceps
Adductor magnus
Fascia lata, iliotibial band
Semitendinosus
Long head
Short head
Biceps femoris
Gastrocnemius, medial head
Gastrocnemius, lateral head
Soleus
Peroneus longus
Peroneus brevis
Semimembranosus

THE MOVEMENT



1 **Hands in pronation (overhand grip)**
Emphasizes the rhomboids and lower portion of the trapezius.



2 **Hands in supination (underhand grip)**
Emphasizes the upper portion of the trapezius and the biceps brachii.

Stand with legs slightly bent, grasping the bar with overhand grip and the hands wider than shoulder-width apart. With the back straight, lean forward at the waist 45 degrees, so that the bar is at knee level:

- Inhale and hold the breath during an isometric contraction of the core and pull the barbell up to the chest.
- Return to the initial position and exhale.

This exercise contracts the latissimus dorsi, teres major, posterior deltoid, and the forearm flexors (biceps brachii, brachialis, brachioradialis). When the shoulder blades come together, the rhomboids and trapezius contract.

The forward lean of the torso uses the spinal muscles in an isometric contraction.

Varying the hand position in width and grip (overhand or underhand) along with changing the angle of the torso allows you to work the back from a variety of angles.

Attention: To prevent injury, never round the back during this exercise.

10 FREESTANDING T-BAR ROWS


Sternocleidomastoid
Splenius
Levator scapula
Trapezius
Infraspinatus
Rhomboid
Latissimus dorsi
Serratus anterior
Erector spinae, under the thoracolumbar fascia
Gluteus maximus
Gluteus medius
Iliac crest
Greater trochanter
Tensor fascia lata
Biceps femoris, long head
Fascia lata, iliotibial band
Rectus femoris
Quadriceps
Vastus lateralis
Vastus intermedius
Vastus medialis
Spine of scapula
Posterior deltoid
Acromion
Teres minor
Teres major
Middle deltoid
Pectoralis major
External oblique
Triceps brachii
Brachialis
Brachioradialis
Extensor carpi radialis longus
Anconeus
Extensor digitorum
Extensor carpi radialis brevis
Biceps femoris, long head
Gastrocnemius
Peroneus longus
Extensor digitorum longus
Soleus
Peroneus brevis




Straight back

Never round your back when performing freestanding T-bar rows.

Straddle the bar with the legs slightly bent, leaning forward with a flat back about 45 degrees. Grasp the bar with an overhand grip:

- Inhale and raise the bar to the chest.
- Exhale at the end of the movement.

This exercise is similar to bent rows and allows you to concentrate on working your back because you do not have to focus too much effort on positioning.

This exercise uses mainly the latissimus dorsi, teres major, infraspinatus, rhomboids, trapezius (mainly the middle portion), and the flexors of the forearm.

The forward lean isolates the abdominal and spinal muscles in isometric contraction.

Using a supinated (underhand) grip transfers some of the effort to the triceps brachii and the upper portion of the trapezius at the end of the pull.

Some machines are equipped with parallel handles that allow a grip between pronated and supinated, which contracts the brachioradialis more intensely.


Brachialis
Brachioradialis
Biceps brachii

T-bar rows also work the forearm flexors.

T-BAR ROWS WITH ABDOMINAL SUPPORT 11


Rhomboids
Trapezius
Infraspinatus
Biceps brachii
Brachialis
Splenius
Sternocleidomastoid
Posterior deltoid
Middle deltoid
Deltoid
Latissimus dorsi
Triceps brachii
Brachioradialis
Extensor carpi radialis longus
Anconeus
Pectoralis minor
Pectoralis major
Serratus anterior
External oblique
Aponeurotic insertion of latissimus dorsi

VARIATION AT A MACHINE
REPRODUCING THE MOVEMENT
AS PERFORMED AT A T-BAR

- Inhale and bring the bar to the chest with an overhand grip.
- Exhale at the end of the movement.

This exercise is similar to bent rows and allows you to concentrate on working your back because you do not have to focus too much effort on positioning.

It mainly uses the latissimus dorsi, teres major, posterior deltoid, arm flexors, trapezius, and rhomboids.

Some machines are equipped with an abdominal support, which eliminates the work of the abdominal and spinal muscles. However, when using heavy weights, the rib cage is compressed against the abdominal-support pad, which interferes with breathing and makes the exercise painful to perform.

Comment: A pronated (overhand) hold shifts some of the effort to the biceps brachii and the upper portion of the trapezius at the end of the pull.

12 STIFF-LEGGED DEADLIFTS


Erector spinae, under the aponeurosis
Iliac crest
Latissimus dorsi
Rhomboids
Trapezius
Infraspinatus
Teres minor
Teres major
Deltoid
Acromion
Gluteus medius
Gluteus maximus
Greater trochanter
Tensor fascia lata
Biceps femoris, long head
Adductor magnus
Semitendinosus
Fascia lata iliotibial band
Vastus lateralis
Biceps femoris, short head
Semimembranosus
Sartorius
Serratus anterior
External oblique
Long head
Lateral head
Medial head
Triceps brachii
Quadriceps, vastus intermedius
Patella
Head of fibula
Extensor digitorum longus
Peroneus longus
Soleus
Gastrocnemius, lateral head
Gastrocnemius, medial head
Soleus
Triceps surae
Peroneus brevis



ACTION OF THE HAMSTRINGS AND GLUTEUS MAXIMUS WHEN SHIFTING THE PELVIS TO VERTICAL


🟥 HAMSTRING ACTIONS
🟩 ACTION OF THE GLUTEUS MAXIMUS



DEADLIFT WITH STRAIGHT LEGS

Stand with the feet slightly apart in front of the bar as it rests on the ground:

- Inhale and bend forward at the waist with the chest forward, back arched, and legs as straight as possible.
- Grasp the bar with an overhand grip. Keeping the arms relaxed, stand up straight by rotating the hips. Keep the abdominal muscles tight and a slight arch in the back for support.
- Exhale out at the end of the movement.
- Bend forward and return to the initial position, but without returning the bar to the floor.

To avoid injury, keep the back straight.

This exercise contracts the deep spinal muscles on either side of the spinal column that straighten the spine.

Straightening the torso by tilting the pelvis from front to back contracts the gluteus maximus and hamstrings (except the short head of the biceps femoris).

Deadlifting from the ground with extended knees stretches the back of the thighs.

To increase the intensity, stand on a box so that the feet are higher than the bar on the ground.

Comment: To stretch the hamstrings, perform the stiff-legged deadlift with very light weights. The greater the weight, the more the gluteal muscles take over from the hamstrings to straighten the pelvis to vertical.

HAMSTRING ACTIONS


Rib
Floating ribs
Lumbar vertebra
Sacrum
Os coxa
Head of femur
Ischial tuberosity
Neck of femur
Greater trochanter
Biceps femoris, long head
Semitendinosus
Femur
Semimembranosus
Biceps femoris, short head
Costal cartilage
Patella
Meniscus
Tibial tuberosity
Head of fibula
Tibia
Fibula

The hamstrings, except for the short head of the biceps femoris, actively participate in tilting the pelvis back.

SUMO DEADLIFTS 13



THE MOVEMENT

INITIAL POSITION
FINAL POSITION
Sternocleidomastoid
Scalenes
Sternohyoid
Deltoid
External oblique
Rectus abdominis, under the aponeurosis
Quadriceps
Rectus femoris
Vastus medialis
Vastus lateralis
Patella
Sartorius
Tibialis anterior
Gastrocnemius, medial head
Soleus
Tibia
Biceps femoris
Semimembranosus
Semitendinosus
Trapezius
Omohyoid
Pectoralis major
Biceps brachii
Brachialis
Triceps brachii
Tensor fascia lata
Iliopsoas
Pectineus
Adductor longus
Gracilis
Adductor magnus
Adductor muscles
Gluteus maximus



DEEP MUSCLES OF THE BACK USED DURING THE SUMO DEADLIFT

Mastoid process
Vertebra
Iliocostalis cervicis
Longissimus cervicis
Rib
Iliocostalis thoracis
Longissimus thoracis
Spinalis thoracis
Iliocostalis lumborum
Quadratus lumborum
Insertion of aponeurosis
Semispinalis capitis
Splenius capitis
Splenius cervicis
Serratus posterior superior
Serratus posterior inferior
Os coxa
Sacrum
Coccyx
Femur

Stand facing the bar, with legs wider than shoulder-width apart and toes pointing out in line with the knees:

- Inhale and bend the legs until the thighs are horizontal to the ground; grasp the bar with an overhand grip about shoulder-width apart. If you are lifting very heavy weights, use a reverse grip (grasping the bar with one overhand and one underhand grip) to keep the bar from rolling.
- Hold your breath and contract the core, slightly round the back, and extend the legs, bringing the torso vertical and pulling the shoulders back.
- Exhale at the end of the movement.
- Return the bar to the ground holding your breath and never round your back.

The difference between this and the classic deadlift is that this exercise works the quadriceps and adductor muscles intensely. Because the pelvis is not as tilted, it works the back less.

Comment: When beginning the movement, slide the bar along the shins. High reps (10 maximum) with light weights strengthen the lumbar region and work the thighs and the gluteal muscles.

When using heavy weights, perform this exercise with great caution to prevent injuries to the hip joints, adductor group of the thighs, and the lumbosacral junction. The sumo deadlift is one of the three power-lifting movements.

14 DEADLIFTS


Sternocleidomastoid
Splenius capitis
Levator scapula
Trapezius
Scalenes
Deltoid
Triceps brachii
Trapezius
Brachioradialis
Extensor carpi radialis longus
Extensor carpi radialis brevis
Anconeus
Extensor digitorum
Biceps brachii
Pectoralis major
Serratus anterior
Sternum
Brachialis
External oblique
Rectus abdominis, under the aponeurosis
Linea alba
Iliopsoas
Palmaris longus
Flexor carpi radialis
Flexor digitorum
Pectineus
Adductor longus
Adductor magnus
Gracilis
Sartorius
Patella
Triceps surae
Gastrocnemius, medial head
Gastrocnemius, lateral head
Soleus
Tibia
Flexor digitorum longus
Tibialis anterior
Peroneus longus
Peroneus brevis
Extensor digitorum longus
Extensor digiti minimi
Gluteus maximus
Flexor carpi ulnaris
Extensor carpi ulnaris
Fascia lata, iliotibial band
Rectus femoris
Vastus lateralis
Vastus medialis
Quadriceps
Biceps femoris
50
50
Spinal cord
Spinous process
Articular process
Vertebral canal
Nucleus pulposus
Annulus fibrosus
Vertebral body
Transverse process
Articular process
Intervertebral disc
Spinous process
Vertebral body
Vertebral foramen
(Hole through which a spinal cord nerve runs)

With vertebral flexion, the disc is compressed in front and expanded in back. The fluid of the nucleus pulposus migrates to the back and may compress on the neural elements (which causes sciatic pain).

COMMENT

By limiting the rolling of the bar, the reverse grip allows you to lift much heavier weights.


Reverse power grip
Classic grip

Stand facing the barbell, legs slightly apart with the abdominal muscles contracted and the back slightly arched. Bend the knees until the thighs are horizontal with the floor. This position will vary depending on the flexibility at the ankles and your physical structure. (The thighs will be horizontal for someone with short femurs and arms. The thighs will be above than horizontal for someone with long femurs and arms.) Grasp the barbell with extended arms in an overhand grip a little wider than shoulder-width apart (reversing the grip of one hand—one overhand and one underhand—keeps the bar from rolling, which allows you to use much heavier weights):

- Inhale, hold the breath, and contract the abdominal muscles and low back and raise the bar by straightening the legs and allowing the bar to slide up the shins. When the bar reaches the knees, straighten the torso while straightening the legs.
- Exhale at the end of the effort.

Throughout the exercise, never straighten your back.

This exercise works nearly every muscle in the body and is effective for developing the lumbosacral and trapezius muscles. It also works the gluteal muscles and quadriceps intensely.

The deadlift, along with the bench press and the squat, make up the exercises in power-lifting competitions.


Splenius capitis
Levator scapula
Sternocleidomastoid
Scalene
Deltoid
Infraspinatus
Teres minor
Teres major
Triceps brachii, lateral head
Triceps brachii, long head
Triceps brachii, medial head
External oblique
Gluteus medius
Greater trochanter
Tensor fascia lata
Rectus femoris
Fascia lata, iliotibial band
Biceps femoris, long head
Vastus lateralis
Biceps femoris, short head
Peroneus longus
Extensor digitorum longus
Peroneus brevis
Spine of scapula
Trapezius
Rhomboid major
Latissimus dorsi
Gluteus maximus
Adductor magnus
Gracilis
Semi-tendinosus
Semi-membranosus
Sartorius
Plantaris
Vastus medialis
Gastrocnemius, lateral head
Gastrocnemius, medial head
Soleus
Flexor digitorum longus
Gastrocnemius tendon



THE MOVEMENT



To prevent injury, never round the back during the exercise.


Splenius capitis
Serratus posterior superior
Levator scapula
Supraspinatus
Infraspinatus
Teres minor
Teres major
Spinalis thoracis
Iliocostalis
Longissimus thoracis
Serratus anterior
Serratus posterior inferior
Quadratus lumborum
Piriformis
Superior gemellus
Obturator externus
Inferior gemellus
Quadratus femoris
Biceps femoris, long head
Semitendinosus
Sternocleidomastoid
Rhomboid minor
Trapezius
Rhomboid major
Deltoid
Infraspinatus
Teres minor
Teres major
Latissimus dorsi
External oblique
Gluteus medius
Gluteus maximus
Semitendinosus
Biceps femoris, long head
Vastus lateralis

MUSCLES USED DURING THE DEADLIFT (HIGHLIGHTED)

No matter what the exercise, as soon as heavy weights are involved, it is essential to create a "block."

1. *Expanding the chest and holding a deep breath fills the lungs, which supports the rib cage and prevents the chest from collapsing forward.*
2. *Contracting the abdominal muscle group supports the core and increases the intra-abdominal pressure, which prevents the torso from collapsing forward.*
3. *Finally, arching the low back by contracting the lumbar muscles positions the spinal column in extension.*

These three actions together are referred to as *blocking*, which keeps you from rounding the back (vertebral flexion). A rounded back when lifting heavy weights can cause a herniated disc.

BICEPS BRACHII TENDON TEAR


1st rib
Clavicle
Manubrium of sternum
Coracoid process
Head of humerus
Acromion
Lesser tubercle
Greater tubercle
Biceps brachii
Short head
Long head
Rib
Xiphoid process
Biceps brachii
Costal cartilage
Brachialis
Linea alba
Biceps brachii, distal tendon, sectioned
Os coxa
Anterior superior iliac spine
Ulna
Radius
5th lumbar vertebra
Sacrum
Neck of femur
Greater trochanter
Carpal
2nd metacarpal
Proximal phalanx
Middle phalanx
Distal phalanx
Pubic symphysis
Diaphysis of femur
Zygomaticus minor
Zygomaticus major
Masseter
Orbicularis oris
Depressor labii inferioris
Sternohyoid
Sternocleidomastoid
Trapezius
Omohyoid
Deltoid
Pectoralis major
Serratus anterior
Triceps brachii
Latissimus dorsi
Biceps brachii
External oblique
Brachialis
Medial epicondyle
Biceps brachii, tendon
Pronator teres
Extensor carpi radialis longus
Biceps brachii, aponeurotic expansion
Brachioradialis
Flexor carpi radialis
Palmaris longus
Flexor carpi ulnaris
Flexor digitorum superficialis
Rectus abdominis, under the aponeurosis
Iliopsoas
Tensor fascia lata
Pyramidalis
Sartorius
Pectineus
Gracilis
Adductor longus
Vastus lateralis
Rectus femoris
Vastus medialis
Quadriceps

Tearing the long head of the biceps brachii is by far the most common serious sport-related biceps injury.

Generally, it occurs in a muscle, already weakened by tendinitis, after a sudden backward movement of the arm, e.g., during a throw. This movement is relatively common in baseball, tennis, and any sport involving a throwing action, but it also occurs in the snatch in weightlifting. During this motion, tension is suddenly placed on the long head of the biceps brachii, most often where its tendon passes through the bicipital groove of the humerus.

Weightlifting, specifically the deadlift, with heavy weights can cause another characteristic biceps brachii injury.

A common practice when using heavy weights in the deadlift that prevents the bar from rolling in the hands is to use a reverse grip (one overhand grip and one underhand grip).

This technique, although usually safe, can in rare instances cause the tearing or the pulling away of the inferior tendon of the biceps brachii where the muscle inserts onto the humerus.

During the positive phase of the deadlift, the effort is mainly exerted by the muscles of the legs and gluteal muscles, the back, and the abdominal muscles. The arms hang down, completely extended and relaxed.

Unfortunately, the slight shortening caused by contracting either head of the biceps brings the hand into supination (the biceps being the strongest supinator), which with extra heavy weights may cause complete rupture of the tendon at the radius.

This injury occurs at the distal attachment because as the arms hang next to the body, the proximal tension is divided between the short and long heads of the biceps brachii whereas, distally, only one tendinous insertion supports the tension.

Compared to other tendon tears such as the pectoralis major or the adductors of the thigh in which the pain is unbearable and stops the athlete from continuing, the pain of a biceps tendon tear is relatively mild despite the seriousness of the actual injury.

In competitive power lifting, athletes have continued their lift despite the biceps tendon tear incurred during that lift.

After the accident the diagnosis is obvious: swelling caused by hemorrhaging appears in the forearm. But what is most striking is the appearance of the biceps brachii, which becomes ball shaped at the upper arm close to pectoralis major and the deltoid, revealing the brachialis muscle lower down.

Despite the tear, the brachialis, brachioradialis, extensor carpi radialis longus and brevis, and pronator teres muscles can still flex the arm, just not as strongly. Supination of the forearm becomes much more of a problem because the end range of this movement relies only on the supinator muscle.

If this injury is not immediately treated with surgery to reattach the biceps tendon onto the radius, irreversible retraction of the muscle will occur with fibrous change. And although moving the arm will still be possible, there will be permanent loss of strength in flexion and supination. It is possible to prevent this injury by regularly working the biceps, not to develop the muscle, but to strengthen its tendon. For this reason add forearm flexion isolations using a bar in a series of "cheats" by leaning the chest back to give the bar a boost. If practiced regularly, this technique reinforces the distal tendon of the biceps by the tension it places on it. Nevertheless it must be performed carefully without rounding the back to avoid injury.



BICEPS BRACHII MUSCLE RETRACTED WITH TEARING OF ITS DISTAL TENDON

NORMAL BICEPS BRACHII MUSCLE



TYPICAL APPEARANCE OF AN UNTREATED DISTAL BICEPS TENDON TEAR

If, after tearing the distal tendon of the biceps brachii, surgery to reattach it to the radius is not performed quickly, permanent retraction and atrophy of the muscle will occur.



BICEPS TENDON ON THE ARM OF THE SUPINATED HAND CAN TEAR DURING A HEAVY DEADLIFT

LOW BACK PAIN

Back pain is the most common problem of the lumbar spine region.

Generally, it is not serious and is most often caused by the shortening of the small, deep vertebral muscles that attach to the transverse processes.

If, during a poorly executed rotation or extension of the spine, one of these muscles is overstretched or is torn, it will automatically shorten along with its neighboring muscles and the superficial erector spinae. The back muscles cramp in pain; however, this cramping limits movement that otherwise might tear or increase the tearing of the small deep muscle.

This general shortening of a portion of the back muscles often disappears when the small deep muscle heals. But sometimes the back pain becomes entrenched, and even after the muscles heal, the local shortening can last several weeks and in some people for years.


Levator costarum longus
Levator costarum brevis
Rotatores thoracis
Interspinalis
Intertransversarii lumborum medialis
Intertransversarii lumborum lateralis
Lumbar costoid process
Thoracic vertebra, spinous process
12th rib
Multifidus
Lumbar vertebra, superior articular process
Iliac
Lumbar vertebra, inferior articular process
Sacrum

SMALL DEEP MUSCLES OF THE BACK

Comment: Although not serious in and of itself, lumbago, which is a painful contracture of the back muscles, can be part of more serious vertebral injuries such as herniated discs, tears in the paravertebral muscles and ligaments, and fractures.

SHOULD YOU ARCH YOUR BACK?

SHOULD YOU ARCH YOUR BACK?

For people without vertebral problems, arching the back during an exercise is not risky. In fact, with movements such as the squat (page 46) or the deadlift (page 132), where the back tends to round, arching the back can prevent injury. However, for some people arching the back during an exercise can be very dangerous.

- For people suffering from congenital spondylolysis (incomplete fusing of the vertebral arch), putting the lumbar spine in extension can cause the vertebra to slide (spondylolisthesis), which may cause serious nerve compression and lead to sciatica.
- For people who are not fully grown or people experiencing osteoporosis, extending the lumbar spine may lead to spondylolysis because of fractures in the vertebral arch. This fracture in the posterior anchoring system of the vertebra may allow the vertebra to slide forward and seriously compress the neural elements (which leads to sciatica).


Mamillary process
Spinous process
Lamina of the vertebral arch
Superior articular process
Accessory process
Costoid process
Vertebral foramen
Pedicle of the vertebral arch
Vertebral body intervertebral surface

LUMBAR VERTEBRA FROM ABOVE


Spondylolysis (fracture of the vertebral arch)
Intervertebral disc
Sacrum
Lumbar vertebra
SLIDING OF THE VERTEBRA

With spondylolysis (fracture of the vertebral arch) the vertebra may slide forward (spondylolisthesis) and compress the neural elements, causing sciatica.

BACK EXTENSIONS 15


Biceps femoris, short head
Semitendinosus
Semimembranosus
Gastrocnemius
Gluteus medius
Gluteus maximus
Quadratus lumborum
Fascia lata, iliotibial band
Iliocostalis lumborum
Latissimus dorsi
Rhomboid major
Teres major
Infraspinatus
Trapezius
Quadriceps, vastus lateralis
Biceps femoris, long head
Soleus
Peroneus longus
Extensor digitorum longus
Tibialis anterior
Iliac crest
Spinalis thoracis
Longissimus thoracis
External intercostals
Iliocostalis thoracis
Scapula
Humerus



THE MOVEMENT



VARIATION WITH A BAR ACROSS THE SHOULDERS



VARIATION EXTENDING AT AN INCLINE BENCH

Lie facedown on a Roman chair and place the ankles under the roller pads. Because the axis of flexion passes through the coxofemoral joints, the pubic bone should not rest on the support pad:

- With the torso bent forward, extend the back to horizontal. Raise the head and continue into hyperextension by arching the lumbar spine. This must be performed carefully to protect your low back.

This exercise mainly develops the group of paraspinal erectors of the spine (iliocostales, longissimus thoracis, spinalis thoracis, splenius, and semispinalis capitis) and quadratus lumborum and, to a lesser degree, the gluteus maximus and the hamstrings except for the short head of the biceps femoris. Complete flexion of the torso develops the flexibility of the lumbosacral mass. Supporting the pelvis on the bench, so that the axis is displaced to the back of the body, focuses the movement completely at the lumbosacral level but less intensely given the range of motion and the greater power of the lever arm.

To increase the intensity, sustain the horizontal position of the torso at the end of the extension for a few seconds. Using an incline bench makes this exercise easier for beginners to execute.

Variations

- Performing the torso extension with a bar on the shoulders stabilizes the upper back, which focuses the effort on the lower part of the erector spinae muscles.
- The back extension machine allows you to focus on the lumbosacral mass of the spinal muscles (see page 88, Torso Extensions at a Machine).
- To increase the intensity, perform the exercise while holding a weight to the chest or behind the neck.

16 TORSO EXTENSIONS AT A MACHINE


Thin
Thick
Scapula
Humerus
Radius
Ulna
Femur
Neck of femur
Tibia
Fibula
Spinalis thoracis
Longissimus thoracis
External intercostals
Rib
Iliocostalis lumborum
Quadratus lumborum
Iliac crest
Lumbosacral, under the aponeurosis
Os coxa

ERECTOR MUSCLE OF THE SPINE



THE MOVEMENT

Sit at the machine, leaning the torso forward and the pad of the machine at shoulder-blade (scapula) level:

- Inhale and press back, straightening the torso as much as possible.
- Return slowly to the initial position while exhaling and begin again.

This exercise works the erector muscles of the spine, focusing the effort on the low back, specifically the lumbosacral mass of the spinal muscles.

This exercise is excellent for beginners. Done in sets of 10 to 12 repetitions, it develops the strength to progress to more technically demanding exercises for the back.

To perform this exercise with heavier weights, reduce the number of repetitions in the set.

Because the machine regulates the range of motion and the weight, the number of repetitions may vary during the same session.

Example: Two series of 15 repetitions with moderate weights and complete range of performance followed by two series of 7 repetitions with more weights and reduced range.

UPRIGHT ROWS 17


Sternocleidomastoid
Brachialis
Brachioradialis
Extensor carpi radialis longus
Semispinalis capitis
Splenius
Levator scapula
Triceps brachii
Lateral head
Long head
Medial head
Teres minor
Teres major
Infraspinatus
Rhomboid major
Serratus anterior
Latissimus dorsi
External oblique
Middle deltoid
Posterior deltoid
Anterior deltoid
Deltoid
Upper portion
Middle portion
Lower portion
Trapezius
Aponeurosis insertion of latissimus dorsi


THE MOVEMENT

Stand with the legs slightly apart, keeping the back straight and grasping the barbell with an overhand grip. The grip should be hand width or slightly wider:

- Inhale and pull the barbell up along the front of the body to the chin, raising the elbows as high as possible.
- Exhale and lower the barbell with a controlled movement.

This exercise mainly uses the superior portion of the trapezius as well as the deltoid, levator scapula, biceps brachii, brachialis, muscles of the forearm, abdominal muscles, gluteal muscles, and lumbosacral group.

A wider grip uses the deltoid more than the trapezius.

18 BARBELL SHRUGS


Splenius
7th cervical vertebra
Trapezius, middle portion
Trapezius, lower portion
Sternocleidomastoid
Levator scapula
Trapezius, upper portion
Middle deltoid
Spine of scapula
Posterior deltoid
Teres minor
Infraspinatus
Rhomboid
Teres major
Latissimus dorsi
External oblique
Long head
Lateral head
Medial head
Triceps brachii

FINAL POSITION
TRAPEZIUS CONTRACTED


Cranium
Spine of scapula
Trapezius
Superior nuchal line
Clavicle
Acromion
Scapula
Rib
Thoracic vertebra

TRAPEZIUS

Stand with the legs slightly apart and face the bar that is either on the ground or on a stand:

- Grasp the bar with an overhand grip, with the hands slightly wider than shoulder-width apart, or use a reverse grip if the weight is heavy.
- Shrug the shoulders keeping the arms relaxed, back straight, and abdominal muscles contracted.

This exercise develops the upper portion of the trapezius, mainly its occipital-clavicular fibers, and the levator scapula.

Comment: Use a reverse grip when working with heavy weights. To balance the work on the trapezius, change the hands with each set. For example, perform one set with the right hand overhand and the left hand underhand. Switch on the following set.

DUMBBELL SHRUGS 19




Skull
Splenius
Sternocleidomastoid
Trapezius
Spine of scapula
Deltoid
Infraspinatus
Teres minor
Teres major
Triceps brachii
Rhomboid
Latissimus dorsi
Levator scapula
Clavicle
Acromion
Spine of scapula
Rhomboid
Scapula
Humerus
Vertebra
Rib



INITIAL POSITION

Stand with the legs slightly apart, head upright or slightly flexed forward, and arms relaxed at the sides gripping a dumbbell in each hand:

- Shrug the shoulders with an anterior to posterior rotation.
- Return to the initial position.

This exercise contracts the superior, or clavicular, portion of the trapezius, the levator scapula, and the middle portion of the trapezius and the rhomboids when squeezing the shoulder blades together and rotating the shoulders to the back.

TRAPEZIUS ACTION



1 Upper portion
2 Middle portion
3 Lower portion



EXECUTING THE ROTATION AT THE END OF THE MOVEMENT

Comment: It is impossible to rotate the shoulders when using heavy weights.

20

MACHINE SHRUGS




Splenius
Sternocleidomastoid
Levator scapula
Scalene
Spine of scapula
Infraspinatus
Trapezius, lower portion
Teres major
Latissimus dorsi
Anconeus
Extensor digitorum
Trapezius, upper portion
Deltoid
Teres minor
Triceps brachii
Brachioradialis
Extensor carpi radialis longus
Extensor carpi radialis brevis


FINAL POSITION
TRAPEZIUS CONTRACTED

Stand facing the machine and hold the handles with an overhand grip slightly wider than shoulder width, or if the machine allows, with the palms facing each other:

- Shrug the shoulders, keeping the head and back straight.

This exercise allows you to perform long sets. It is excellent for developing the upper portion of the trapezius and the levator scapula.

5

LEGS


Gluteus minimus
Iliopsoas
Pectineus
Adductor longus
Adductor magnus
Tibialis anterior
Extensor hallucis longus
Gluteus medius
Sartorius
Tensor fascia lata
Adductor longus
Gracilis
Rectus femoris
Vastus medialis
Vastus lateralis
Vastus intermedius
Quadriceps
Gastrocnemius, medial head
Gastrocnemius, lateral head
Peroneus longus
Tibialis anterior
Extensor digitorum longus
Soleus
Peroneus brevis
Extensor hallucis longus


Gluteus minimus
Piriformis
Superior gemellus
Obturator internus
Inferior gemellus
Quadratus femoris
Biceps femoris, long head
Semimembranosus
Biceps femoris, short head
Semimembranosus
Popliteus
Peroneus longus
Flexor digitorum longus
Tibialis posterior
Flexor hallucis longus
Peroneus brevis
Gluteus medius
Gluteus maximus
Greater trochanter
Tensor fascia lata
Adductor magnus
Fascia lata, iliotibial band
Gracilis
Semitendinosus
Biceps femoris, long head
Biceps femoris, short head
Semimembranosus
Sartorius
Plantaris
Gastrocnemius, lateral head
Gastrocnemius, medial head
Soleus
Peroneus longus
Peroneus brevis

1 **DUMBBELL SQUATS** 94
2 **FRONT SQUATS** 95
3 **SQUATS** 96
4 **POWER SQUATS** 98
✚ **DISC HERNIATION** 99
5 **ANGLED LEG PRESSES** 100
6 **HACK SQUATS** 101
7 **LEG EXTENSIONS** 102
8 **LYING LEG CURLS** 103
9 **STANDING LEG CURLS** 104
10 **SEATED LEG CURLS** 105
✚ **HAMSTRING MUSCLE TEARS** 106
11 **GOOD MORNINGS** 107
12 **CABLE ADDUCTIONS** 108
13 **MACHINE ADDUCTIONS** 109
14 **STANDING CALF RAISES** 110
15 **ONE-LEG TOE RAISES** 111
16 **DONKEY CALF RAISES** 112
17 **SEATED CALF RAISES** 113
18 **SEATED BARBELL CALF RAISES** 114

1

DUMBBELL SQUATS




Latissimus dorsi
External oblique
Iliac crest
Tensor fascia lata
Gluteus medius
Greater trochanter
Gluteus maximus
Quadriceps
Rectus femoris
Vastus lateralis
Vastus intermedius
Patella
Fascia lata
Biceps femoris, long head
Biceps femoris, short head
Peroneus longus
Extensor digitorum longus


INITIAL POSITION

Stand with the feet slightly apart, a dumbbell in each hand and the arms relaxed, looking straight ahead:

- Inhale, slightly arch the back, and bend the knees.
- When the thighs reach horizontal, extend the legs to return to the initial position.
- Exhale at the end of the effort.

This exercise mainly works the quadriceps and the gluteal muscles.

Comment: There is no point in working with heavy weights. Working with moderate weights in sets of 10 to 15 repetitions provides the best results.

FRONT SQUATS 2


Rectus abdominis, under the aponeurosis
Pubic symphysis
Iliopsoas
Pectineus
Adductor longus
Gracilis
Sartorius
Patella
Patellar ligament
Gastrocnemius, medial head
Tibia, medial surface
Soleus
Flexor digitorum longus
Latissimus dorsi
External oblique
Anterior superior iliac spine
Gluteus medius
Tensor fascia lata
Gluteus maximus
Greater trochanter
Adductor magnus
Fascia lata
Rectus femoris
Vastus lateralis
Vastus medialis
Vastus intermedius
Quadriceps
Head of fibula
Tibialis anterior
Extensor digitorum longus
Peroneus longus




THE MOVEMENT



Lowering the thighs by bending the knees while the legs are held by equipment focuses a major part of the work on the quadriceps muscles.

Stand with the legs about shoulder-width apart, holding the bar with an overhand grip as it rests on the upper pectoral muscles and the anterior deltoid:

- Inhale deeply to maintain intrathoracic pressure, which prevents the torso from collapsing forward, slightly arch the low back, contract the abdominal core, and bend the knees to lower the thighs horizontal to the floor.
- Return to the initial position and breathe out at the end of the movement.

Stick out the chest and to raise the elbows as high as possible to prevent the barbell from sliding forward.

Even though the barbell is in front, keep the back upright and don't lean the torso forward. To make the exercise easier, place blocks under the heels.

This type of squat focuses a greater part of the effort onto the quadriceps and is performed with lighter weights than the classic squat. This exercise contracts the gluteal muscles, hamstring, abdominal core, and the erector spinae. This is a movement frequently used in weight training because it corresponds perfectly with the work the thighs do at the end of a snatch.



CORRECT POSITION



INCORRECT POSITION

3 SQUATS


Quadriceps
Vastus lateralis
Rectus femoris
Vastus intermedius
Vastus medialis
Sartorius
Patella
Patellar tendon
Gastrocnemius, medial head
Tibia
Soleus
External oblique
Iliac crest
Gluteus medius
Tensor fascia lata
Greater trochanter
Gluteus maximus
Fascia lata
Short head
Long head
Biceps femoris
Gastrocnemius, lateral head
Soleus
Peroneus longus
Peroneus brevis
Extensor digitorum longus
Tibialis anterior
TWO WAYS TO HOLD THE BARBELL
1
2
1 On the trapezius
2 On the deltoid and the trapezius, power-lifter style.

The squat is the number one bodybuilding movement: It uses nearly the entire muscular system, and it also works the cardiovascular system. It helps develop thoracic expansion, and therefore, respiratory capacity:

- With the barbell resting on a stand, slide under the bar and place it on the trapezius a bit higher than the posterior deltoid. Grasp the bar firmly with the hands at a comfortable width and the elbows back.
- Inhale deeply (to maintain the intrathoracic pressure, which will prevent the torso from collapsing forward), slightly arch the back by rotating the pelvis forward, contract the abdominal core, look straight ahead, and remove the barbell from the stand.
- Step back one or two steps and stop with both feet parallel to each other (or toes pointing slightly outward) and about shoulder-width apart. Bend forward from the hips (the axis of flexion should pass through the coxofemoral joints) and avoid rounding the back in order to prevent injury.
- When the thighs are horizontal to the floor, straighten the legs and lift the torso to return to the initial position.
- Exhale at the end of the movement.

The squat mainly works the quadriceps, gluteal muscles, adductor group, erector spinae, abdominal muscles, and the hamstrings.

Comment: The squat is one of the best exercises for developing the shape of the buttocks.


TORSO ANGLE BASED ON PHYSICAL DIFFERENCES

Variations:

- People with rigid ankles or long femurs can place a block under their heels to keep from tilting the torso too much. This variation isolates the quadriceps.
- Lowering the bar onto the posterior deltoid increases the leverage of the back, which helps you lift heavier weights. This technique is essential for power lifters.
- The squat can be performed at a frame, which keeps you from tilting the torso and lets you focus on the quadriceps.

FOOT PLACEMENT IN THE SQUAT

When executing the classic squat, that is, with the feet approximately shoulder-width apart, you must place the feet properly. They should be parallel or slightly pointed to the outside. However, you must take into consideration your unique physical structure and make adjustments as necessary to ensure that the feet are in line with the knees.

For example: If you naturally walk with the feet pointed out, perform the squat with the feet pointed out.



1 CORRECT POSITIONS

When executing squats, hold the back straight.

Given the variations in each person's physical structure (different leg lengths and ankle flexibility) and the variations in technique (width of stance, use of heel blocks, barbell higher or lower), the tilt of the torso will vary; however, the lean should start at the hips.

2 INCORRECT POSITION

Never round the back when executing squats.

This mistake is responsible for most lumbar spine injuries, especially herniated discs.



TRADITIONAL HORIZONTAL SQUAT

COMPLETE SQUAT

To feel the working of the gluteal muscles, lower the thighs to horizontal.

1-2-3 NEGATIVE PHASE
4 COMPLETE SQUAT

To feel the working of the gluteal muscles even more, lower the thighs past horizontal. However, this technique can only be performed by people with flexible ankles or short femurs. Furthermore, you must perform the complete squat carefully and avoid the tendency to round the low back, which can lead to serious injury.

No matter what the exercise, as soon as heavy weights are involved, it is essential to create a "**block**."

1. *Expanding the chest and holding a deep breath fills the lungs, which supports the rib cage and prevents the chest from collapsing forward.*
2. *Contracting the abdominal muscle group supports the core and increases the intra-abdominal pressure, which prevents the torso from collapsing forward.*
3. *Finally, arching the low back by contracting the lumbar muscles positions the spinal column in extension.*

These three actions together are referred to as *blocking*, which keeps you from rounding the back (vertebral flexion). A rounded back when lifting heavy weights can cause a herniated disc.

4 POWER SQUATS


Rectus abdominis, under the aponeurosis
Internal oblique, under the aponeurosis
Iliopsoas
Pubic symphysis
Pectineus
Quadriceps, rectus femoris
Sartorius
Adductor longus
Quadriceps, vastus medialis
Meniscus
Gracilis
Gastrocnemius, medial head
Tibia, medial surface
Soleus
Adductor magnus
Semimembranosus
Semitendinosus
External oblique
Gluteus medius
Anterior superior iliac spine
Tensor fascia lata
Greater trochanter
Gluteus maximus
Pyramidalis, under the aponeurosis
Fascia lata, iliotibial band
Quadriceps, vastus lateralis
Quadriceps, vastus intermedius
Head of fibula
Patella
Patellar ligament
Peroneus longus
Tibialis anterior
Extensor digitorum longus
Peroneus brevis

This movement is performed the same as the classic squat, except that the legs are farther apart and the toes point out, which works the inner thigh intensely.

The working muscles are as follows:

- quadriceps
- adductor muscle group (adductor magnus, adductor longus, adductor brevis, adductor pectineus, and gracilis)
- gluteal muscles
- hamstrings
- abdominal muscles
- lumbosacral muscle group


THREE FEET POSITIONS FOR SQUATS

Muscles used extensively 🟥 Muscles used 🟧

DISC HERNIATION


Greater sciatic notch
Sciatic nerve, L4-L5-S1-S2-S3
Posterior cutaneous nerve of the thigh, S1-S2-S3
Common peroneal segment of sciatic nerve
Biceps femoris, long head, cut
Adductor magnus
Tibial segment of sciatic nerve
Biceps femoris, short head, cut
Biceps femoris, long head, cut
Common peroneal nerve
Articular branch
Tibial nerve
Lateral sural cutaneous nerve
Peroneal communicating branch
Lateral calcaneal branch
Lateral dorsal cutaneous nerve
Perianal branches
Adductor magnus
Semitendinosus
Semimembranosus
Medial sural cutaneous nerve
Gastrocnemius
Sural nerve
Soleus
Tibial nerve
Plantar nerves
Medial calcaneal branches

SCIATIC NERVE
AND POSTERIOR CUTANEOUS NERVE OF THIGH



To prevent injury at the lumbar level, never round the back when executing a deadlift or squat.


DISC HERNIATION
Spinal cord
Nerve root
Annulus fibrosus
Nucleus pulposus
Intervertebral disc
Costoid process
Spinous process
Articular process

Vertebral flexion using weights can cause a herniated disc, usually in the lumbar vertebrae. These herniations occur most frequently with the squat and deadlift, and most often are the result of incorrect back position because of bad technique.

Disc herniation is a relatively frequent injury in weightlifting, most often caused by incorrect back position during the squat, deadlift, or bent row.

When executing these exercises, the main thing to avoid is rounding the back (vertebral flexion), which expands the back of the disc and pinches the front of it.

If the intervertebral disc is cracked or aging, the gelatinous liquid of the nucleus pulposus migrates backward and can compress on the spinal cord or the roots of the spinal nerves. Symptoms depend on the type of lesion, the amount of nucleus pulposus pushed out, and the surface that is compressed. The nucleus pulposus can bulge or, worse, explode through the annulus fibrosus, which surrounds it, and sometimes tear the posterior ligament that connects the vertebrae to each other. Compression of the neural elements caused by the tearing of the annulus fibrosus is particularly painful and incapacitating.

In weight training, herniations usually occur at the lumbar level and most frequently between the third and fourth or between the fourth and fifth lumbar vertebrae. The pain is dull and deep, sometimes accompanied by swelling and tingling. The pain is located in the middle of the back or more often to one side, radiating to the gluteal muscles, pelvis, and pubis and down the leg following the path of the sciatic nerve (hence the name sciatica to define this type of pain). Generally, disc herniations are spontaneously reabsorbed, and the pain eventually disappears. But in some cases, the bulge in the disc does not disappear and continues to press painfully against the nerves, or a detached piece of intervertebral cartilage compresses the neural elements.

In both these cases, a surgeon can remove the part that is pressing against the nerves.

To prevent disc herniation, use proper form when performing risky exercises such as the squat, deadlift, good morning, and bent row.

No matter what the exercise, as soon as heavy weights are involved, it is essential to create a "block."

1. *Expanding the chest and holding a deep breath fills the lungs, which supports the rib cage and prevents the chest from collapsing forward.*
2. *Contracting the abdominal muscle group supports the core and increases the intra-abdominal pressure, which prevents the torso from collapsing forward.*
3. *Finally, arching the low back by contracting the lumbar muscles positions the spinal column in extension.*

These three actions together are referred to as blocking, which keeps you from rounding the back (vertebral flexion). A rounded back when lifting heavy weights can cause a herniated disc.

Comment: After a heavy workout, stretch the back by hanging from a chinning bar and focusing on relaxing the body. This allows the muscles to relax and rebalance the pressures inside the intervertebral discs.

EFFECT OF AGE ON DISC HERNIATION LUMBAR VERTEBRAL SEGMENT (CUT)


Foramen
Cartilaginous covering
Annulus fibrosus
Vertebral body
Superior articular process
Pedicle of the vertebral arch
Spinous process
Inferior articular process

1 **Young vertebral segment**
The intervertebral disc is still healthy.

2 **Older vertebral segment**
With age, the annulus fibrosus begins to develop fissures and the viscous gel of the nucleus pulposus begins to dehydrate. The intervertebral disc collapses and the vertebral segments lose their mobility.

From the age of 30, the intervertebral discs degenerate, and the annulus fibrosus can crack as the nucleus pulposus begins to dehydrate. The discs of older athletes are more rigid and less elastic, and the mobility of the spine is limited. On the other hand, as the viscous gel of the nucleus pulposus gradually dehydrates, it becomes less likely that it will be displaced and compress against the nerve.

In comparison, disc herniation in a young person involves the movement of a greater amount of the gelatinous fluid of the nucleus pulposus, causing more compression, pain, and incapacity of the neural elements. Disc herniation therefore occurs more frequently with young athletes.

5 ANGLED LEG PRESSES


Soleus
Tibialis anterior
Extensor digitorum longus
Peroneus longus
Patella
Gastrocnemius, lateral head
Biceps femoris, short head
Biceps femoris, long head
Vastus medialis
Vastus intermedius
Vastus lateralis
Rectus femoris
Quadriceps
Fascia lata
Gluteus maximus
Greater trochanter
Tensor fascia lata
External oblique



ATTENTION

For some people, using the press with heavy loads can provoke a movement of the sacroiliac hinge. This can induce very painful muscle spasms.



INITIAL POSITION

Position the back properly against the backrest on a machine, with the feet slightly apart:

- Inhale and release the safety bars then bend the knees completely so that the thighs touch or nearly touch the torso.
- Return to the initial position, exhaling at the end of the movement.

Placing the feet low against the foot plate isolates the quadriceps; placing the feet higher on the foot plate calls on the gluteal muscles and the hamstrings. Placing the feet wider apart focuses effort on the adductors.

Comment: People with back pain who are unable to perform squats can do this exercise. However, they must never lift the back off the back pad.

Feet high on the foot plate



Strong use of the gluteal muscles and the hamstrings

Feet low on the foot plate



Strong use of the quadriceps

Feet apart



Strong use of the adductors

Feet close together



Strong use of the quadriceps

HACK SQUATS

6


External oblique
Gluteus medius
Iliopsoas
Tensor fascia lata
Pectineus
Adductor longus
Sartorius
Biceps femoris
Gastrocnemius, medial head
Tibialis anterior
Soleus
Extensor digitorum longus
Peroneus longus
Soleus
Peroneus brevis
Rib
Vertebra
Os coxa
Sacrum
Femur
Vastus lateralis
Rectus femoris
Vastus medialis
Quadriceps
Patella
Patellar ligament
Tibia
Fibula

Stand with the legs straight and feet slightly apart, back against the back pad, and shoulders positioned under the shoulder pads. (Hack refers to a "yoke." The pads are reminiscent of the collar placed around the neck of draft animals.):

- Inhale and release the safety catch. Bend the knees, then return to the initial position.
- Exhale at the end of the exercise.

This movement focuses the effort on the quadriceps. The more the feet are forward, the more the gluteal muscles will be used. To protect the back, contract the abdominal core, which eliminates lateral movement of the pelvis or cervical spine.


HUMAN
CHIMPANZEE

BIPEDAL ADAPTATION

In the chimpanzee, our closest relative, the well-developed torso is paired with an underdeveloped gluteus maximus, which makes raising the trunk and standing erect difficult and causes an awkward two-footed gait.

The human is the only primate who has completely adapted to walking upright on two legs. Besides the well-developed gluteus maximus, the entire human structure has adapted to walking on two legs. For example, the torso is relatively small, which makes holding it erect easier, and, unlike the gorilla or chimpanzee, humans can lock the knee joint when it is extended, which makes standing much less tiring.

7 LEG EXTENSIONS


2 End
1 Begin
THE MOVEMENT
Rectus abdominis, under the aponeurosis
External oblique
Gluteus medius
Tensor fascia lata
Fascia lata
Gluteus maximus
Biceps femoris
Long head
Short head
Head of fibula
Tibia, medial surface
Tibialis anterior
Gastrocnemius, lateral head
Peroneus longus
Extensor digitorum longus
Soleus
Anterior superior iliac spine
Iliopsoas
Pectineus
Adductor longus
Sartorius
Rectus femoris
Vastus lateralis
Vastus medialis
Vastus intermedius
Quadriceps
Patella
Patellar ligament

Sit at the machine and grasp the handles or the seat to hold the torso immobile. Bend the knees and place the ankles under the ankle pads.

- Inhale and raise the legs to horizontal.
- Exhale at the end of the exercise.

This is the best exercise for isolating the quadriceps. The greater the angle of the backrest, the farther toward the back the pelvis rotates. This exercise stretches the rectus femoris, which is the midline biarticular portion of the quadriceps, which makes the work on it more intense while extending the legs.

This movement is recommended for beginners so that they can develop enough strength to move on to more technically demanding exercises.


Anterior view
Posterior view
Vastus lateralis
Vastus medialis
Vastus intermedius
Vastus medialis
Vastus lateralis
Vastus intermedius

INSERTIONS OF THE QUADRICEPS FEMORIS MUSCLE ONTO THE FEMUR


Anterior superior iliac spine
Os coxa
Sacrum
Neck of femur
Coccyx
Greater trochanter
Rectus femoris
Vastus lateralis
Vastus medialis
Patella
Vastus intermedius
Patellar ligament
Meniscus
Fibula
Tibial tuberosity

QUADRICEPS FEMORIS MUSCLE

LYING LEG CURLS

8


VARIATION WITH A DUMBBELL HELD BETWEEN THE ANKLES

Semimembranosus
Biceps femoris, short head
Semitendinosus
Biceps femoris, long head
Fascia lata, iliotibial band
Gluteus maximus
Greater trochanter
Tensor fascia lata
Gluteus medius
External oblique
Latissimus dorsi
Soleus
Peroneus brevis
Peroneus longus
Gastrocnemius
Extensor digitorum longus
Patella
Quadriceps, rectus femoris
Tibialis anterior
Quadriceps
Vastus medialis
Vastus lateralis
Vastus intermedius

Lie facedown on the machine, holding the handles, legs extended, and ankles positioned under the ankle pads:

- Inhale and bend both legs at the same time, trying to touch the gluteal muscles with the heels.
- Exhale at the end of the effort.
- Return to the initial position with a controlled movement.

This exercise works the hamstring group and gastrocnemius and deeper, the popliteus muscle. In theory, during flexion, it is possible to target the semitendinosus and semimembranosus by internally rotating the feet, or to target the long and short heads of the biceps femoris by externally rotating the feet. But in practice, this proves to be difficult, and only emphasis on the hamstrings and the gastrocnemius can be easily achieved:

- Point the toes (plantar flexion) to feel the effort in the hamstrings.
- Flex the feet (dorisflexion) to feel the effort in the gastrocnemius.

Variation: This exercise may be performed by alternating the legs.


2 End
1 Begin

THE MOVEMENT

HAMSTRING MUSCLES


Os coxa
Sacrum
Head of femur
Coccyx
Neck of femur
Pubic symphysis
Greater trochanter
Ischial tuberosity
Lesser trochanter
Semimembranosus
Biceps femoris, long head
Semitendinosus
Biceps femoris, short head
Intercondylar fossa
Tibia
Head of fibula

9 STANDING LEG CURLS


Latissimus dorsi
External oblique
Erector spinae, under the aponeurosis
Iliac crest
Gluteus medius
Sacrum
Greater trochanter
Gluteus maximus
Tensor fascia lata
Adductor magnus
Gracilis
Fascia lata, iliotibial band
Semitendinosus
Biceps femoris, long head
Semimembranosus
Biceps femoris, short head
Hamstrings
Plantaris
Gastrocnemius, medial head
Gastrocnemius, lateral head
Head of fibula
Soleus
Peroneus longus
Rectus femoris
Vastus lateralis




Hamstrings
Femur
Patella
Meniscus
Tibia
Gastrocnemius
Fibula

Contracting the hamstrings and the lateral and medial heads of the gastrocnemius flexes the knee joint.


2 End
1 Begin

THE MOVEMENT

Stand with the torso resting against the pad, thigh positioned against the knee pad, the knee straight, and the back of the ankle resting against the ankle roll:

- Inhale and bend at the knee.
- Exhale at the end of the movement.

This exercise uses the hamstring group (semitendinosus and semimembranosus and the long and short heads of the biceps femoris) and, to a lesser extent, the gastrocnemius. To engage the gastrocnemius more, simply bend at the ankle when bending at the knee. To decrease its participation, which is often the goal, simply point the toes.

SHORT HEAD OF THE BICEPS FEMORIS

Of all the flexor muscles, only the short head of the biceps femoris works across just one joint: It bends the knee.


Os coxa
Head of femur
Pubic tubercle
Greater trochanter
Biceps femoris, long head
Femur
Biceps femoris, short head
Patella
Head of fibula
Tibia

SEATED LEG CURLS 10


Quadriceps, vastus intermedius
Patella
Tibialis anterior
Extensor digitorum longus
Peroneus longus
Quadriceps, rectus femoris
External oblique
Gluteus medius
Tensor fascia lata
Fascia lata, iliotibial band
Greater trochanter
Gluteus maximus
Quadriceps, vastus lateralis
Peroneus tertius
Peroneus brevis
Soleus
Gastrocnemius
Semimembranosus
Semitendinosus
Biceps femoris, short head
Biceps femoris, long head

Sit at the machine, with the legs extended, ankles resting on the ankle pad, thighs positioned between the thigh pad and the seat, holding the handles:

- Inhale and bend the knees.
- Exhale at the end of the movement.

This exercise uses the hamstring muscles and, deeper, the popliteus. To a lesser extent, it works the gastrocnemius.

Variations

- Perform the exercise with the feet in dorsiflexion (feet flexed) to increase the work of the gastrocnemius muscles.
- Perform the exercise with the feet in plantar flexion (toes pointed) to focus the effort on the hamstrings.

POPLITEUS MUSCLE


Femur
Condyles
Popliteus
Fibula
Tibia

The popliteus, located on the posterior side of the leg at the knee joint, works with the hamstrings and gastrocnemius to bend the leg.



END OF MOVEMENT


Biceps femoris, long head
Semitendinosus
Semimembranosus
Biceps femoris, short head
Gastrocnemius, medial head
Gastrocnemius, lateral head

MUSCLES USED

HAMSTRING MUSCLE TEARS

ACTION OF THE HAMSTRING MUSCLES DURING THE SQUAT


2 Straightening the pelvis erects the torso.
1 The hamstrings contract to straighten the pelvis.

While performing the squat, the hamstring muscles contract to straighten the pelvis, which at the same time prevents the torso from tilting too far forward (as long as pelvis is aligned with the torso by contracting the abdominal and lumbar muscles).

HAMSTRING MUSCLES


External oblique
Gluteus medius
Gluteus maximus
Tensor fascia lata
Greater trochanter
Adductor magnus
Fascia lata
Gracilis
Quadriceps, vastus lateralis
Semitendinosus
Biceps femoris
Long head
Short head
Semimembranosus
Plantaris
Gastrocnemius, lateral head
Gastrocnemius, medial head
Iliac crest
Os coxa
Sacrum
Coccyx
Pubic symphysis
Neck of femur
Greater trochanter
Ischial tuberosity
Lesser trochanter
Biceps femoris, long head, sectioned
Semitendinosus, sectioned
Linea aspera
Femur
Short head
Long head, sectioned
Biceps femoris
Semimembranosus
Condyles of femur
Meniscus
Head of fibula
Soleal line

Muscle tearing of the hamstrings

In bodybuilding, hamstring tears occur frequently. This injury occurs most often during the squat when the torso is too far forward. The hamstring muscle group, with the exception of the short head of biceps femoris, is in an extremely stretched position and contracts forcefully to straighten the pelvis. This can lead to tearing, most often at the high or middle portion of the muscle group.

Hamstring tears can also occur when working at a leg curl machine using heavy weights. This most often occurs at the beginning of the movement when the legs are extended and the muscles are stretched.

Although in general, the tears in hamstring muscle fibers are not extensive and not serious (it is rare to see a significant tear in the muscle or its tendinous insertion), they are always painful and prone to complications.

In fact, fibrous scarring frequently occurs after a tear in this muscle group, which creates friction that is especially painful and incapacitating during sport activity. Furthermore, this inelastic scar tissue is liable to tear during intense effort.

Preventing hamstring tearing

To prevent muscle tears, perform either a specific stretching workout or incorporate hamstring stretches during a lifting workout between sets of squats and deadlifts and exercises for the back of the thigh.

Certain weightlifting exercises, such as good mornings or stiff-legged deadlifts, can be considered the best hamstring protectors because of their combined action of muscle strengthening and stretching.

After hamstring tearing

To prevent the formation of fibrous scar tissue in the hamstrings, it is essential to reeducate the muscles as soon as possible. A week after a tear, you must perform gentle stretches for the back of the thighs. The goal is to stretch the injured muscles and especially to soften the scar so that it doesn't tear when you resume training.

RETRACTION OF THE HAMSTRINGS


Loss of lumbar curve
Pelvis in posterior tilt
Hamstring muscles

Retraction of the hamstrings causes the pelvis to tip back (posterior rotation), which reduces the lumbar curve and sets the stage for vertebral injuries.

In today's modern world, sitting for long periods during the day can lead to retraction of the hamstring muscles in certain people.

This retraction of the muscles on the back of the thigh tips the pelvis back and reduces the normal curvature of the spine.

This causes the person to adopt poor posture with the pelvis tucked under and the back rounded, which over time can lead to vertebral injuries. To limit this relatively frequently occurring retraction of the hamstrings, stretching movements such as an easy good morning with straight legs and the stiff-legged deadlift are recommended. Hamstring stretches after a hamstring workout are also recommended.

Comment: A massage therapist can also treat fibrous scars by using massage or mechanical techniques aimed at softening the lesion.

GOOD MORNINGS 11


Trapezius
Teres minor
Spine of scapula
Infraspinatus
Rhomboid
Deltoid
Teres major
Biceps brachii
Brachialis
Triceps brachii
Latissimus dorsi
Erector spinae, under the thoracolumbar fascia
External oblique
Iliac crest
Gluteus medius
Tensor fascia lata
Greater trochanter
Gluteus maximus
Fascia lata, iliotibial band
Adductor magnus
Quadriceps, vastus lateralis
Biceps femoris
Long head
Short head
Quadriceps, vastus intermedius
Semimembranosus
Plantaris
Gastrocnemius, lateral head
Gastrocnemius, medial head
Spinalis thoracis
Longissimus thoracis
Rib
Iliocostalis
Quadratus lumborum
Iliac
Sacrum
Neck of femur
Greater trochanter
Coccyx
Ischial tuberosity
Femur
Head of fibula
Tibia
Gracilis
Semimembranosus
Semitendinosus





TWO WAYS TO PERFORM GOOD MORNINGS

1 Bent knees 2 Straight knees


Latissimus dorsi
Erector spinae, under the aponeurosis
Gluteus medius
Gluteus maximus
External oblique
Tensor fascia lata
Greater trochanter
Quadriceps, rectus femoris
Fascia lata
Semitendinosus
Quadriceps, vastus lateralis
Patella
Tibialis anterior
Biceps femoris, long head
Semimembranosus
Biceps femoris, short head
Extensor digitorum longus
Peroneus longus
Soleus
Peroneus brevis
Gastrocnemius, medial head
Gastrocnemius, lateral head

Straightening the legs while tilting forward lengthens the hamstrings, helping to better feel the contraction while straightening the trunk.

Bending the knees while tilting forward allows the hamstrings to relax, which facilitates hip flexion.



Stand with the feet slightly apart and the bar resting on the trapezius or a little lower on the posterior deltoid:

- Inhale and bend the torso forward, keeping the back straight. The axis of rotation should pass through the coxofemoral joints.
- Return to the initial position and exhale.

To make the exercise easier, bend slightly at the knees.

This movement, which works the gluteus maximus and the spinal group, is especially noteworthy for the action on the hamstrings (except the short head of the biceps femoris, which only flexes the knee). Besides knee flexion, the main function of the hamstrings is to tip the pelvis back (posterior rotation) and straighten the torso when the pelvis is locked to the torso through isometric contraction of the abdominal core and the lumbosacral muscle group.

To better feel the work of the hamstrings, don't work with heavy weights. In the negative phase, the good morning is excellent for stretching the back of the thighs. Worked regularly, it helps prevent injury when executing a heavy squat.

12 CABLE ADDUCTIONS


THE MOVEMENT
Gluteus medius
Tensor fascia lata
Iliopsoas
Pectineus
Adductor longus
Adductor magnus
Fascia lata, iliotibial band
Head of fibula
Patella
Gracilis
Patellar ligament
Tibialis anterior
Extensor digitorum longus
Peroneus longus
Tibia, medial surface
Rectus abdominis, under the aponeurosis
External oblique
Anterior superior iliac spine
Pyramidalis, under the aponeurosis
Pubic symphysis
Sartorius
Rectus femoris
Vastus lateralis
Vastus medialis
Vastus intermedius
Quadriceps
Gastrocnemius
Soleus
Flexor digitorum longus
ADDUCTOR MUSCLES OF THE THIGHS
Os coxa
Sacrum
Obturator internus
Pubis
Pectineus
Adductor longus
Adductor brevis
Femur
Gracilis
Adductor magnus
Patella
Fibula
Common insertion
Tibia

Stand on one leg, with the other leg in the ankle cuff and the hand of the supporting leg holding onto the machine:

- Pull the cable across the support leg.

This exercise works the adductor group (pectineus; adductors brevis, longus, and magnus; and gracilis). To develop definition of the inside of the thighs, perform sets of high repetitions.

MACHINE ADDUCTIONS 13


Anterior superior iliac spine
Anterior inferior iliac spine
Pubic symphysis
Pectineus
Adductor brevis
Adductor longus
Adductor magnus
Femur
Patella
Adductor tubercle
Tibial tuberosity
Medial meniscus
Tibia, subcutaneous medial surface
Metatarsals
Proximal phalanx
Distal phalanx
Sacrum
Head of femur
Ischial tuberosity
Calcaneus
Sustentaculum tali
Cuneiform
Navicular
Talus

Sit at the machine with the legs spread apart:

- Contract the thighs to bring the legs together.
- Return to the initial position with a controlled movement.

This exercise works the adductor muscle group (pectineus; adductors minimus, magnus, brevis and longus; and gracilis) and allows you to use heavier weights than you can with the cable adductions but with a decreased range of motion.

Best results are achieved in long sets until you feel a burn.

Comment: Perform this exercise to strengthen the adductors. This muscle group is often injured during intense exertion.

Therefore, increase the weights gradually and perform adductor muscle stretches at the end of the workout.



THE MOVEMENT

ADDUCTORS MINIMUS AND MAGNUS (POSTERIOR VIEW)


Iliac crest
Sacrum
Coccyx
Symphysis pubis
Ischial tuberosity
Adductor magnus
Popliteal surface
Adductor tubercle
Anterior superior iliac spine
Os coxa
Neck of femur
Greater trochanter
Lesser trochanter
Adductor minimus
Linea aspera
Medial condyle
Lateral condyle

14 STANDING CALF RAISES

GASTROCNEMIUS MUSCLE MEDIAL HEAD



GASTROCNEMIUS MUSCLE LATERAL HEAD




Rib
Lumbar vertebra
Iliac crest
Os coxa
Sacrum
Neck of femur
Greater trochanter
Lesser trochanter
Ischial tuberosity
Diaphysis of femur
Gastrocnemius, lateral head
Triceps surae
Gastrocnemius, medial head
Soleus
Tibia, medial malleolus
Fibula, lateral malleolus
Calcaneal tuberosity
Latissimus dorsi
External oblique
Gluteus medius
Gluteus maximus
Greater trochanter
Tensor fascia lata
Adductor magnus
Fascia lata, iliotibial band
Semitendinosus
Quadriceps, vastus lateralis
Biceps femoris, long head
Gracilis
Semimembranosus
Quadriceps, vastus intermedius
Biceps femoris, short head
Plantaris
Gastrocnemius, lateral head
Gastrocnemius, medial head
Soleus
Peroneus longus
Peroneus brevis
Flexor hallucis longus
Flexor digitorum longus
Achilles tendon




1 Begin
2 End

THE MOVEMENT



Variation: Performing the exercise at an incline machine works the calves without overloading the back.



THE MOVEMENT

Stand at the machine with a straight back, shoulders under the pads, and the balls of the feet on the foot plate, with the calves relaxed and the heels hanging down:

- Rise up by extending (plantar flex) the feet, keeping the knees straight.

This exercise uses the triceps surae (made up of the soleus and the lateral and medial heads of the gastrocnemius). Move the feet through the complete range of flexion with each repetition in order to stretch the muscles properly. In theory, it is possible to isolate the medial gastrocnemius by pointing the toes out and to isolate the lateral gastrocnemius by pointing the toes in. But in practice, this is difficult to achieve. Only separating the work of the soleus and gastrocnemius is easy to achieve. This is done by flexing the knees to relax the gastrocnemius and to put more effort on the soleus.

Variations: Perform the exercise at a frame with a wedge under the feet or with a free bar without the wedge for more balance; however, this reduces the amplitude of movement.

Comment: The triceps surae is an extremely powerful, tough muscle group that alone raises the entire weight of the body thousands of times in a day when we walk. Don't hesitate to work it with heavy weights.


Femur
Femur
Patella
Tibia
Gastrocnemius
Soleus
Tibia
Fibula
Fibula
Talus
Cuneiform
Achilles tendon
Calcaneus
Cuboid
Metatarsal

TRICEPS SURAE ACTION

ONE-LEG TOE RAISES 15


INITIAL POSITION
Biceps femoris, long head
Semitendinosus
Biceps femoris, short head
Semimembranosus
Triceps surae
Gastrocnemius, medial head
Gastrocnemius, lateral head
Soleus
Achilles tendon
Calcaneus
Fascia lata
Quadriceps, vastus externus
Quadriceps, vastus intermedius
Patella
Peroneus longus
Extensor digitorum longus
Tibialis anterior
Peroneus brevis
Extensor hallucis longus
Peroneus tertius



TWO TYPES OF CALVES


Femur
Plantaris
Gastrocnemius, lateral head
Gastrocnemius, medial head
Soleus
Triceps surae
Achilles tendon
Calcaneus
1
2

1 Long calf: Gastrocnemius and soleus are low

2 Short calf: Gastrocnemius and soleus are high with a long tendon.

Comment: Some people have an unusual triceps surae that does not grow larger with training. These people can develop strength only. Long gastrocnemius and soleus muscles develop easily. Conversely, short calves resist developing bulk.

TRICEPS SURAE MUSCLE GROUP


Veterbra
Os coxa
Sacrum
Femur
Gastrocnemius, lateral head
Tibia
Fibula
Soleus
Gastrocnemius, medial head
Achilles tendon
Calcaneus

Stand with the toes of one foot on the foot plate and hold a dumbbell in one hand and use the other hand for support and balance:

- Rise up on the toes (plantar flexion), keeping the knee joint straight or slightly flexed.
- Return to the initial position.

This exercise contracts the triceps surae. Completely flex the foot with each repetition in order to stretch the triceps surae properly. Optimal results are obtained through long sets until you feel a burn.

16 DONKEY CALF RAISES


Fascia lata, iliotibial band
Quadriceps
Vastus lateralis
Vastus medialis
Biceps femoris, short head
Patella
Head of fibula
Triceps surae
Gastrocnemius, lateral head
Gastrocnemius, medial head
Soleus
Peroneus longus
Extensor digitorum longus
Tibialis anterior
Flexor digitorum longus
Extensor hallucis longus
Extensor retinaculum
Lateral malleolus
Gastrocnemius, medial head
Soleus
Triceps surae
Tibia, medial face
Medial malleolus
Peroneal retinaculum



TRICEPS SURAE INSERTION


Gastrocnemius, medial head
Plantaris, inconstant
Gastrocnemius, lateral head
Soleus
Achilles tendon

Stand with the legs relaxed, toes on the foot plate and heels hanging down, legs extended, torso leaning forward, forearms resting on the front support, and the padded plate of the machine resting on the back of the hips:

- Rise up by extending the ankles and pointing the toes (plantar flexion).

This exercise focuses on the triceps surae, especially the gastrocnemius.

Variation: If there's no machine for this exercise, put a block under the feet, bend forward, and rest the forearms on a support, and perform this exercise while someone straddles your hips.

ACTION OF TRICEPS SURAE


Femur
Patella
Gastrocnemius
Soleus
Tibia
Fibula
Achilles tendon
Talus
Navicular
Cuneiform
Calcaneus
Cuboid
Femur
Tibia
Fibula
Metatarsal

SEATED CALF RAISES 17


Vetebra
Sacrum
Os coxa
Femur
Patella
Peroneus longus*
Fibula
Tibia
Tibialis posterior*
Flexor digitorum longus*
Flexor hallucis longus*
Peroneus brevis*

*Although it is not their main function these muscles participate in foot extension.


Quadriceps
Rectus femoris
Vastus lateralis
Vastus intermedius
Tensor fascia lata
Fascia lata, iliotibial band
Gluteus maximus
Biceps femoris
Long head
Short head
Semimembranosus
Achilles tendon
Inferior peroneal retinaculum
Calcaneal tuberosity
Patella
Fascia lata, iliotibial band
Patellar ligament
Head of fibula
Tibialis anterior
Extensor digitorum longus
Peroneus longus
Gastrocnemius
Soleus
Triceps surae
Peroneus brevis
Extensor hallucis longus
Peroneus tertius
Lateral malleolus
Extensor retinaculum
Extensor digitorum brevis

TRICEPS SURAE MUSCLE


Vetebra
Os coxa
Sacrum
Femur
Tibia
Fibula
Soleus
Gastrocnemius, lateral head
Gastrocnemius, medial head
Achilles tendon
Calcaneus

Sit at a machine, with the knees positioned under the pads, the toes on the foot bar, and the ankles relaxed:

- Extend the feet and point the toes.

This exercise isolates the soleus, whose name is derived from its resemblance to the flat fish, the sole. (This muscle inserts at the top at the tibia and fibula under the knee joint and attaches at the bottom to the calcaneus by the Achilles tendon. Its purpose is to extend the feet at the ankles.)

Bending at the knees relaxes the gastrocnemius, which attaches at the top above the knee joint and at the bottom onto the Achilles tendon, and reduces its contribution to ankle extension.

Variation: You can also perform this exercise by sitting on a bench with a wedge under the feet and a barbell resting on the thighs. Wrap the bar for comfort.


1 Begin
2 End

VARIATION WITH A BARBELL RESTING ON THE KNEES

18 SEATED BARBELL CALF RAISES


INITIAL POSITION
Quadriceps, vastus lateralis
Fascia lata, iliotibial band
Biceps femoris
Short head
Long head
Gastrocnemius, lateral head
Tibialis anterior
Soleus
Extensor digitorum longus
Peroneus longus
Peroneus brevis
Sartorius
Vastus medialis
Pectineus
Patella
Adductor longus
Gracilis
Semimembranosus
Semitendinosus
Gastrocnemius, medial head
Soleus
Tibia
Flexor digitorum longus

Sit on a bench with a block under the toes and the barbell resting on the thighs:

- Extend (plantar flex) the ankle.

Attention: Cushion the bar on the thighs with a rubber pad or a folded towel to reduce pain.

This exercise mainly uses the soleus. This muscle, which is part of the triceps surae group, inserts at the top below the knee joint on the tibia and fibula. At the bottom, it attaches to the calcaneus via the Achilles tendon. Its function is to extend the feet at the ankles. Unlike the calf raises, which allow you to work with heavy weights, this exercise does not allow heavy weights because of the awkwardness of the bar position. For best results, work in sets of 15 to 20 repetitions.

Variation: You can also perform this exercise without additional weights while sitting on a chair or bench. In this case, work in very long sets until you feel a burn.


Femur
Patella
Gastrocnemius, relaxed
Tibia
Fibula
Navicular
Cuneiform
Soleus
Achilles tendon
Metatarsal
Calcaneus
Talus
Cuboid

1

When the knees are bent, the gastrocnemius muscle, which attaches above the knee, is relaxed. In this position, it weakly assists ankle extension because most of the work is done by the soleus.


Gastrocnemius, stretched
Navicular
Fibula
Cuneiform
Soleus
Metatarsal
Achilles tendon
Calcaneus
Talus
Cuboid

2

Conversely, when the knee is straight, the gastrocnemius is stretched. In this position, it actively participates in ankle extension and completes the action of the soleus.

6

BUTTOCKS

Gluteal muscles, a human characteristic

Although some of the larger primates occasionally walk, humans are the only primates and one of the few mammals that has completely adapted to two-legged locomotion. One of the structural features directly related to this way of getting around is the significant development of the gluteus maximus muscle, which has become the biggest and most powerful muscle in the human body.

The development of the gluteal muscles is truly a human characteristic. In comparison, the gluteal muscles in quadrupeds are proportionately underdeveloped, and the hindquarters of the horse, which some consider as typical for animals, is in fact made up of the hamstrings (the back of the thigh in humans).

In humans, the gluteus maximus, which extends the hip, does not play an important role in walking. Instead, the hamstrings play the major role in straightening the pelvis (hip extension) with each stride. Just put your hand on the buttocks while walking, and you can feel that they do not contract much.

However, as soon as the effort becomes significant, such as when walking uphill, walking quickly, or running, the gluteal action is called into play to extend the hip and erect the torso.

These biomechanical points help explain why in exercises for the gluteal muscles and the hamstrings, such as good mornings (see page 107) and leg raises, either the gluteal muscles or the hamstrings are isolated depending on the amount of weight involved.



In quadrupeds, such as the horse, the gluteus maximus muscle is proportionally less developed than in the human being.

1 **LUNGES** 116
2 **DUMBBELL LUNGES** 117
KNEE INSTABILITY 118
3 **CABLE BACK KICKS** 119
4 **MACHINE HIP EXTENSIONS** 120
5 **FLOOR HIP EXTENSIONS** 121
6 **BRIDGING** 122
7 **CABLE HIP ABDUCTIONS** 123
INDIVIDUAL VARIATIONS IN HIP MOBILITY 124
8 **STANDING MACHINE HIP ABDUCTIONS** 125
9 **FLOOR HIP ABDUCTIONS** 126
10 **SEATED MACHINE HIP ABDUCTIONS** 127

1 LUNGES


External oblique
Tensor fascia lata
Quadriceps
Rectus femoris
Vastus lateralis
Vastus medialis
Vastus intermedius
Patella
Biceps femoris, short head
Peroneus longus
Extensor digitorum longus
Tibialis anterior
Biceps femoris, long head
Fascia lata, iliotibial band
Gluteus medius
Greater trochanter
Gluteus maximus
Adductor magnus
Semitendinosus
Semimembranosus
Gracilis
Gastrocnemius, lateral head
Soleus
Sartorius
Vastus medialis

Stand with the legs slightly apart and the bar behind the neck resting on the trapezius muscles:

- Inhale and take a big step forward, keeping the trunk as straight as possible.
- Lunge until the front thigh is horizontal to the floor or slightly less.
- Exhale and return to the initial position.

This exercise, which works the gluteus maximus intensely, can be performed two different ways: either by taking a small step (which isolates the quadriceps) or taking a big step (which isolates the hamstrings and gluteus maximus and stretches the rectus femoris and iliopsoas of the back leg).

Comment: Because the front leg must support almost all the weight in the lunge position and the exercise demands a good sense of balance, begin with very light weights.


1 EXECUTION WITH A SMALL STEP: PREDOMINANTLY WORKS THE QUADRICEPS


2 EXECUTION WITH A BIG STEP: PREDOMINANTLY WORKS THE GLUTEUS MAXIMUS

DUMBBELL LUNGES

2




External oblique
Tensor fascia lata
Quadriceps
Rectus femoris
Vastus lateralis
Vastus medialis
Vastus intermedius
Patella
Biceps femoris
Short head
Long head
Semitendinosus
Gastrocnemius
Peroneus longus
Extensor digitorum longus
Tibialis anterior
Soleus
Peroneus brevis
Fascia lata, iliotibial band
Quadriceps, vastus medialis
Gluteus medius
Gluteus maximus
Adductor magnus
Semitendinosus
Semimembranosus
Gracilis
Sartorius
Gastrocnemius
Soleus



INITIAL POSITION

Stand with the legs slightly apart and hold a dumbbell in each hand:

- Inhale and take a big step forward, keeping the torso as straight as possible.
- When the forward thigh reaches horizontal or slightly below, use tonic extension to return to the initial position.
- Exhale at the end of the movement.

This exercise mainly works the gluteus maximus and quadriceps.

Variations: The bigger the step, the more the gluteus maximus of the forward leg is used and the iliopsoas and rectus femoris of the back leg is stretched.

A smaller step isolates the quadriceps of the forward leg.

You can perform a complete set on one side and then the other or work the legs alternately during the same set.

Comment: Because all of the weight is supported by the front leg in the lunge position and the exercise requires a good sense of balance, work with light weights to protect the knee.


Iliac crest
Gluteus medius
Gluteus maximus
Tensor fascia lata
Fascia lata, iliotibial band
Semitendinosus
Semimembranosus
Quadriceps, vastus lateralis
Latissimus dorsi
External oblique
Erector spinae, under the thoracolumbar fascia
Coccyx
Greater trochanter
Adductor magnus
Biceps femoris, long head
Gracilis

ANATOMY OF THE BUTTOCKS

KNEE INSTABILITY

When the knee is extended, the medial and lateral collateral ligaments are stretched and prevent rotation of the joint. When you are standing, the knee locks in extension, and there is no need for muscle tension to stabilize the joint.

When the knee is bent, the medial and lateral collateral ligaments are relaxed. In this position muscle tension provides the stability.

When the knee flexes and rotates, the meniscus travels forward. Then, if extension is not controlled, the meniscus may not return to its normal position fast enough and becomes pinched between the condyles, which can tear the meniscus. If a piece of the meniscus is severed when it is pinched, surgery may be necessary to remove it.

With asymmetrical exercises such as the lunge (see page 116), control the speed and the form of the movement to protect the knee.

1 KNEE IN EXTENSION **2 KNEE IN FLEXION**


Femur
Patella
Meniscus
Medial collateral ligament
Tibia
Fibula

When the knee is flexed, the lateral ligaments are relaxed. Rotation of the joint is possible.

MENISCI


With meniscus
No meniscus

One of the main functions of the meniscus is to disperse pressure in the knee joint by increasing the supporting surface area for the femur on the tibia, avoiding premature wear on the articular surfaces.

MENISCI AND KNEE LIGAMENTS


Femur
Posterior cruciate ligament
Anterior cruciate ligament
Medial collateral ligament
Lateral collateral ligament
Medial meniscus
Lateral meniscus
Head of fibula
Tibia

CABLE BACK KICKS

3


Posterior superior iliac spine
Superficial gluteus maximus
Greater trochanter
Linea aspera of femur
Head of fibula
Patella
Tibia
Lumbar vertebra
Iliac crest
Os coxa
Anterior superior iliac spine
Head of femur
Ischial ramus
Deep gluteus maximus
Diaphysis of femur

The deep gluteus maximus attaches to the linea aspera of the femur


Posterior superior iliac spine
Sacrum
Coccyx
Ischial tuberosity
Linea aspera of femur
Head of fibula
Tibia
Patella
Lumbar vertebra
Iliac crest
Os coxa
Anterior superior iliac spine
Iliofemoral (Bertin's) ligament
Greater trochanter
Ischial ramus
Diaphysis of femur

Hip extension is limited by the iliofemoral (Bertin's) ligament


External oblique
Gluteus medius
Gluteus maximus
Semitendinosus
Biceps femoris, long head
Semimembranosus
Gastrocnemius, lateral head
Peroneus longus
Soleus
Greater trochanter
Tensor fascia lata
Fascia lata, iliotibial band
Vastus lateralis, quadriceps
Biceps femoris, short head
Extensor digitorum longus
Tibialis anterior
Peroneus brevis

Stand on one leg facing the machine, the other leg attached to the ankle strap of the low pulley, and the pelvis tilted forward. Grasp the handle:

- Extend the hip and pull the leg back.
- Hip extension is limited by the tension of the iliofemoral (Bertin's) ligament.

This exercise mainly works the gluteus maximus and, to a lesser extent, the hamstrings (except the short head of biceps femoris).

It helps develop the profile of the hips while firming the gluteal region.

4 MACHINE HIP EXTENSIONS


Sacrum
Os coxa
Iliofemoral ligament
Head of femur
Pubis
Greater trochanter
Ischial tuberosity

Hip extension is limited by the tension of the iliofemoral ligament, also referred to as Bertin's ligament, which is a thickening of the articular capsule.


Latissimus dorsi
External oblique
Gluteus maximus
Gracilis
Biceps femoris, long head
Biceps femoris, short head
Gastrocnemius, lateral head
Gastrocnemius, medial head
Gluteus medius
Coccyx
Adductor magnus
Semitendinosus
Quadriceps, vastus lateralis
Semimembranosus
Soleus


Gluteus medius
Gluteus maximus
Greater trochanter
Adductor magnus
Gracilis
Semitendinosus
Fascia lata
Biceps femoris, long head
Vastus lateralis


Latissimus dorsi
External oblique
Gluteus medius
Greater trochanter
Tensor fascia lata
Fascia lata
Gluteus maximus
Rectus femoris
Vastus lateralis
Quadriceps
Adductor magnus
Semitendinosus
Biceps femoris, long head

Stand on one leg with the other slightly forward and position the roll against the calf halfway between the knee and ankle. Lean the torso forward slightly and grasp the handles:

- Inhale and push the thigh back until the hip is hyperextended.
- Maintain the position with an isometric contraction for a couple of seconds.
- Return to the initial position.
- Exhale at the end of the extension.

This exercise mainly works the gluteus maximus and, to a lesser extent, the semitendinosus, semimembranosus, and the long head of the biceps femoris.

FLOOR HIP EXTENSIONS

5


Soleus
Gastrocnemius, lateral head
Peroneus longus
Biceps femoris, short head
Semimembranosus
Biceps femoris, long head
Semitendinosus
Gluteus maximus
Gluteus medius
Tibialis anterior
Extensor digitorum longus
Fascia lata
Quadriceps
Vastus lateralis
Rectus femoris
Tensor fascia lata
Greater trochanter
External oblique



THE MOVEMENT

Kneel on one leg and bring the other knee to the chest while leaning on the elbows or on the hands with the arms extended:

- Extend the bent leg back with complete hip extension.

With the leg extended, this exercise uses the hamstrings and gluteus maximus. With the knee bent, only the gluteus maximus is used and less intensely.

This exercise can be performed with higher or lower amplitude during the last part of the extension. You can maintain an isometric contraction for a couple of seconds at the end of the movement.

To increase the intensity, use ankle weights.

Its ease of execution and its effectiveness has made this exercise popular, and it is frequently used in group classes.



VARIATION ON A BENCH



VARIATION WITH BENT KNEE

6 BRIDGING


THE MOVEMENT
BEGIN
END
Quadriceps
Vastus intermedius
Vastus medialis
Vastus lateralis
Rectus femoris
Patella
Fascia lata, iliotibial band
Tensor fascia lata
Greater trochanter
Iliac crest
Gluteus medius
Gluteus maximus
External oblique
Short head
Long head
Biceps femoris
Gastrocnemius, lateral head
Peroneus longus
Soleus
Peroneus brevis

Lie on the back, with hands flat on the ground, arms alongside the body, and knees bent:

- Inhale and lift the buttocks off the ground, pushing down through the feet.
- Maintain the position for a couple of seconds and lower the pelvis without touching the buttocks on the ground.
- Exhale and begin again.

This exercise mainly works the hamstrings and gluteus maximus.

Perform this exercise in long sets, making sure to contract the muscles at the top of the lift, when the pelvis is off the ground.

Comment: Because it is easy and effective, bridging has become part of most group exercise classes.


VARIATION AT A BENCH
1 Begin
INITIAL POSITION
2 End

Variation 1:

To perform bridging with the feet raised, lie on the back, with hands flat at the sides, arms alongside the body, thighs vertical, and feet resting on a bench:

- Inhale and raise the pelvis off the ground; maintain the position for two seconds and lower without touching the buttocks to the ground.
- Exhale and begin again.

This exercise works the gluteus maximus and especially the hamstrings. The hamstrings are used more in this exercise than when bridging from the ground. Execute this exercise slowly, and focus on the muscle contraction.

Sets of 10 to 15 repetitions provide the best results. Another variation is to perform bridging with the calves resting on the bench. This isolates the hamstrings even more intensely and also requires strong work from the gastrocnemius.

Variation 2:

Limit the range of the movement by not lowering the pelvis as far and create a burn.

Comment: Bridging is actually extending the hips.

CABLE HIP ABDUCTIONS 7


GLUTEAL INSERTIONS AT THE OS COXA
Gluteus medius
Gluteus maximus
Gluteus minimus




Latissimus dorsi
External oblique
Gluteus medius
Gluteus maximus
Tensor fascia lata
Greater trochanter
Fascia lata
Quadriceps, vastus lateralis
Biceps femoris, long head
Biceps femoris, short head
Gastrocnemius, lateral head
Gastrocnemius, medial head
Soleus
Coccyx
Adductor magnus
Gracilis
Semitendinosus
Semimembranosus
Sartorius
Plantaris


SECTION THROUGH A FEMALE HIP DISPLAYING THE GLUTEUS MEDIUS OVERLYING THE GLUTEUS MINIMUS
External oblique
Internal oblique
Transversus abdominis
Iliac crest
Os coxa, vertical and transverse cut
Gluteus medius
Gluteus minimus
Coxofemoral joint
Head of femur
Neck of femur
Greater trochanter
Lesser trochanter
Femur
Quadriceps, vastus lateralis
Subcutaneous adipose layer
Ischial ramus

Stand on one leg with a pulley attached to the other ankle:

- Raise the leg laterally as high as possible.

This exercise mainly works gluteus medius and the deeper gluteus minimus.

Long sets until you feel a burn are most effective.


GLUTEAL "DELTOID"
Gluteal "deltoid"
Gluteus medius
Tensor fascia lata
Gluteus maximus


GLUTEUS MINIMUS
Os coxa
Gluteus minimus
Greater trochanter
Femur
Patella

Although located deep, the gluteus minimus contributes to the bulk of the upper buttock.

INDIVIDUAL VARIATIONS IN HIP MOBILITY

Regardless of individual muscle elasticity and ligamentous tension, it is mainly the shape of the bones of the coxofemoral joint that is responsible for hip mobility. The configuration of the bone is most important in hip abduction.

Example

- When the neck of the femur is almost horizontal (coxa vara) and associated with a well-developed superior rim of the acetabulum covering the head of the femur, abduction movements are limited.
- When the neck of the femur is close to vertical (coxa valga) and associated with an undeveloped superior acetabular rim, abduction movements are facilitated.

Therefore, it is useless to try to raise the leg high laterally if your hip joint is not made for it.

ATTENTION

If hip abduction is forced, the neck of the femur will butt up against the rim of the acetabulum, and the pelvis will tilt onto the head of the opposite femur to compensate for lateral extension of the leg. When some people perform sets of forced abductions, over time microtrauma may occur, which develops excessive growth of the superior rim of the acetabulum, limiting the mobility of the hip and risking painful inflammation.


1
2
Action of the gluteus medius and minimus

1 Abduction of the hip (limited by the neck of the femur butting against the acetabulum)

2 Forced abduction of the hip (tilting the pelvis onto the head of the opposite femur)

VARIATIONS IN OSSEOUS HIP STRUCTURE


MAXIMUM ABDUCTION
Neck of femur

An almost horizontal neck of the femur is referred to as a **coxa vara**. It limits abduction movements because it butts up against the rim of the acetabulum sooner.


MAXIMUM ABDUCTION
Neck of femur

An almost vertical neck of the femur is referred to as **coxa valga**. It allows greater abduction movements.


Os coxa
Greater trochanter
Ischial spine
Head of femur
Ischion
Lesser trochanter
Acetabulum
Neck of femur

ABDUCTION IS LIMITED BY THE NECK OF THE FEMUR BUTTING UP AGAINST THE RIM OF THE ACETABULUM.

STANDING MACHINE HIP ABDUCTIONS 8


Tensor fascia lata
Biceps femoris, long head
Quadriceps, rectus femoris
Fascia lata
Quadriceps, vastus lateralis
Quadriceps, vastus intermedius
Patella
Tibialis anterior
External oblique
Gluteus medius
Grand trochanter
Gluteus maximus
Adductor magnus
Semitendinosus
Semimembranosus
Gracilis
Sartorius
Quadriceps, vastus medialis
Biceps femoris, short head
Gastrocnemius, medial head
Soleus
Peroneus longus
Extensor digitorum longus



THE MOVEMENT



Stand on one leg at the machine, placing the other leg against the roll below the knee:

- Slowly raise the leg as high as possible.
- Return to the initial position.

Abduction is limited by how soon the neck of the femur butts up against the rim of the acetabulum.

This exercise develops the gluteus medius. It also develops the deeper gluteus minimus, whose function is the same as that of the anterior fibers of the gluteus medius. For best results, use long sets.


Tensor fascia lata
Quadriceps, rectus femoris
Fascia lata, iliotibial band
Quadriceps, vastus lateralis
Quadriceps, vastus intermedius
Peroneus longus
Peroneus brevis
Peroneus tertius
Soleus
Calcaneal tendon
Gluteus medius
Gluteus maximus
Long head
Short head
Biceps femoris
Semitendinosus
Semimembranosus
Gastrocnemius, medial head
Gastrocnemius, lateral head
Iliac crest
Gluteus minimus
Greater trochanter
Diaphysis of femur
Condyle of femur
Sacrum
Coccyx
Ischial tuberosity

GLUTEUS MEDIUS AND MINIMUS RAISE THE LEG LATERALLY

9 FLOOR HIP ABDUCTIONS


Greater trochanter
Femur
Gluteus medius
Coccyx
Lumbar vertebra
Sacrum
Os coxa


THE MOVEMENT

Lie on the side and support the head with the hand:

- Raise the leg laterally no more than 70 degrees, keeping the knee straight.

This exercise works the gluteus medius and minimus. You can vary how high you raise the leg. Hold the leg at the height of the movement for a few seconds with an isometric contraction.

You can raise the leg slightly to the front or the back or raise it vertically.

To increase the intensity, use ankle weights, elastic band, or low pulley.


THREE WAYS TO RAISE THE LEG


ISOLATED ZONES

1 Leg raised vertically
2 Leg raised slightly behind
3 Leg raised slightly in front

SEATED MACHINE HIP ABDUCTIONS

10


END
BEGIN
THE MOVEMENT
External oblique
Rectus abdominis
Gluteus medius
Tensor fascia lata
Greater trochanter
Quadriceps, rectus femoris
Quadriceps, vastus lateralis
Fascia lata, iliotibial band
Gluteus maximus



Sit at the machine:

- Spread the legs as wide as possible.
- Return to the initial position with a controlled movement.

The more angled the backrest, the more the gluteus medius is isolated. The more vertical the backrest, the more the gluteus maximus is worked.

Ideally, lean forward or back to change the angle of the torso during a set.

Example: Perform 10 repetitions with the torso resting against the backrest and 10 repetitions with the torso leaning forward.

This exercise sculpts and firms the top of the hip, which makes the waistline look narrower.



GLUTEAL PORTION ISOLATED
WITH THE TORSO AGAINST THE BACKREST

GLUTEAL PORTION ISOLATED
WITH THE TORSO LEANING FORWARD

7

ABDOMEN


Deltoid
Xiphoid process
Biceps brachii
Brachialis
Latissimus dorsi
Rectus abdominis, aponeurosis
External oblique
Umbilicus
Linea alba
Tensor fascia lata
Iliopsoas
Pectineus
Adductor longus
Gracilis
Pectoralis major
Pectoralis major, abdominal part
Serratus anterior
Intercostal
Rib
Costal cartilage
Rectus abdominis
Internal oblique
Anterior superior iliac spine
Inguinal ligament
Pyramidalis
Cremaster
Suspensory ligament of the penis
Sartorius
Rectus femoris
Vastus medialis
Vastus lateralis
Quadriceps

⚠ ATTENTION ... 129
1 CRUNCHES ... 130
2 SIT-UPS ... 131
3 GYM LADDER SIT-UPS ... 132
4 CALVES OVER BENCH SIT-UPS ... 133
5 INCLINE BENCH SIT-UPS ... 134
6 SUSPENDED BENCH SIT-UPS ... 135
7 HIGH-PULLEY CRUNCHES ... 136
8 MACHINE CRUNCHES ... 137
9 INCLINE LEG RAISES ... 138
10 LEG RAISES ... 139
11 HANGING LEG RAISES ... 140
12 BROOMSTICK TWISTS ... 141
13 DUMBBELL SIDE BENDS ... 142
14 ROMAN CHAIR SIDE BENDS ... 143
15 MACHINE TRUNK ROTATIONS ... 144

ATTENTION!


Costal angle
12th thoracic vertebra
12th rib, floating rib
Lumbar vertebra
Psoas minor
Iliac crest
Psoas major
Anterior superior iliac spine
Sacrum
Head of femur
Pecten pubis
Ischial ramus
Pubic symphysis
ACTION OF PSOAS
Intervertebral disc
Anterior superior iliac spine
Greater trochanter
Lesser trochanter

ACTION OF PSOAS MAJOR ON THE LUMBAR CURVE

Aside from its role as a powerful hip flexor, the psoas muscle pulls the lumbar spine into lordosis, increasing the curve.

When performing exercises for the abdominal muscles, round the back.



CORRECT POSITION, ROUNDED BACK **INCORRECT POSITION, ARCHED BACK**

As with most movements involving the abdominal core, leg raises either on the ground or at an incline bench should never be performed with an arched back.



INCORRECT POSITION, BACK ARCHED

Unlike other weightlifting movements, exercises for the abdominal core and especially those for the rectus abdominis absolutely must be worked with a rounded back (rolling up the spine).

When performing exercises that roll the spine up off the floor, as in crunches, you hold the spine differently than when performing squats, deadlifts, or other standing movements.

If during exercises with additional weights, such as squats, deadlifts, or good mornings, the vertebral column is not arched at the lumbar spine, vertical pressure combined with rounding the back pushes the nucleus pulposus of the intervertebral disc posteriorly, which can compress the nerves and cause sciatica or a herniated disc.

On the other hand, when performing specific exercises for the abdomen, if the back is not rounded with intense contraction of the rectus abdominis and the internal and external obliques, the powerful psoas hip flexors will increase the lumbar curve, forcing the intervertebral discs forward.

This causes increased pressure at the posterior lumbar vertebral articulations, which can cause low back pain or, more seriously, articular compression or shearing.

1 CRUNCHES*


Tibialis anterior
Extensor digitorum longus
Gastrocnemius, lateral head
Quadriceps, vastus intermedius
Patella
Rectus abdominis
Internal oblique
External oblique
Pectoralis major
Peroneus longus
Soleus
Biceps femoris, short head
Quadriceps, vastus lateralis
Biceps femoris, long head
Fascia lata
Quadriceps, rectus femoris
Greater trochanter
Gluteus maximus
Gluteus medius
Tensor fascia lata
Latissimus dorsi
Teres major
Serratus anterior

Lie on the back, with hands behind the head, thighs vertical, and knees bent:

- Inhale and raise the shoulders off the ground, bringing the knees and head toward each other by crunching, which means rounding the back and rolling the spine up.
- Exhale at the end of the movement.

This exercise mainly uses the rectus abdominis.

To work the obliques more intensely, bring the right elbow to the left knee, then the left elbow to the right knee alternately with each crunch.

* Perform a crunch by rounding the back and rolling the spine up, bringing the pubis and sternum toward each through voluntary contraction.


1 Begin
2 End

THE MOVEMENT



VARIATION
SEATED CRUNCH ON A BENCH

SIT-UPS 2


Pectoralis major
Rectus abdominis
Quadriceps, vastus lateralis
Quadriceps, vastus medialis
Patella
Quadriceps, rectus femoris
Biceps femoris, short head
Semimembranosus
Tibialis anterior
Extensor digitorum longus
Peroneus longus
Latissimus dorsi
Serratus anterior
External oblique
Gluteus medius
Tensor fascia lata
Greater trochanter
Gluteus maximus
Soleus
Fascia lata, iliotibial band
Gastrocnemius, lateral head
Biceps femoris, long head
Semitendinosus





PERFORMING THE EXERCISE WITH A PARTNER ANCHORING THE FEET

Lie on the back, with knees bent, feet flat on the ground, and hands behind the head:

- Inhale and raise the torso by rounding the back.
- Exhale at the end of the movement.
- Return to the initial position without touching the ground.

Continue until a burn develops in the abdominal muscles.

This exercise works the hip flexors as well as the obliques, but it mainly acts on the rectus abdominis.

Variations:

1. Having a partner hold the feet makes the exercise easier.
2. Extending the arms forward makes the exercise easier for beginners.
3. Working on an incline bench makes the exercise more intense.



1 The movement.
2 Variation with arms extended to make the movement easier.



VARIATION ON AN INCLINE BENCH
The greater the angle, the greater the effort.

Comment: Because, in general, a woman's torso is not as bulky proportionate to the legs as in men, performing sit-ups without lifting the feet off the ground is easier for women than for men.

3 GYM LADDER SIT-UPS


Tibialis anterior
Extensor digitorum brevis
Peroneus brevis
Peroneus longus
Patella
Vastus lateralis, quadriceps
Soleus
Gastrocnemius, lateral head
Biceps femoris, short head
Quadriceps, rectus femoris
Biceps femoris, long head
Pectoralis major
Teres major
Fascia lata, iliotibial band
Latissimus dorsi
Serratus anterior
Gluteus maximus
External oblique
Gluteus medius
Tensor fascia lata
Rectus abdominis


Pectoralis major
Sternum
Serratus anterior
Rectus abdominis
Linea alba
Area of cross section
Umbilicus
External oblique
Anterior superior iliac spine
Pyramidalis
Pubic symphysis

Lie faceup on the ground and position the feet between two bars in the ladder, with the thighs vertical, and hands behind the head:

- Inhale and raise the torso as high as possible, rounding the spine.
- Exhale at the end of the movement.

This exercise works the rectus abdominis and, to a lesser degree, the external oblique.

Position the feet lower on the ladder so that the pelvis can rock more and better contract the flexor muscles of the hip (iliopsoas, rectus femoris, and tensor fascia lata) when lowering the torso.


CROSS SECTION
Erector spinae
Aponeurosis
Vertebra
Quadratus lumborum
Transversus abdominis
Internal oblique
Aponeurosis
External oblique
Rectus abdominis

CALVES OVER BENCH SIT-UPS

4


Extensor digitorum longus
Tibialis anterior
Tibia
Quadriceps, vastus medialis
Patella
Quadriceps, vastus lateralis
Rectus abdominis
Quadriceps, rectus femoris
Pectoralis major
Teres major
Serratus anterior
Latissimus dorsi
External oblique
Peroneus brevis
Peroneus longus
Gastrocnemius, lateral head
Semi-tendinosus
Gluteus medius
Tensor fascia lata
Biceps femoris, long head
Greater trochanter
Gluteus maximus
Biceps femoris, short head



THE MOVEMENT



Correct position

Incorrect position

PLACEMENT OF THE HANDS AND ELBOWS

To prevent pulling on the neck excessively, place the hands behind the ears rather than behind the head.

The wider the elbows, the more difficult the movement.

Conversely, the closer together and more forward the elbows, the easier the execution.

Lie on your back with your calves laying over a flat exercise bench. Place your hands behind your head:

- Inhale and lift your shoulders off the floor.
- Try to touch your knees with your head.
- Exhale as you complete the movement.

This exercise focuses on the rectus abdominis, particularly above the navel. By placing your torso farther from the bench you increase pelvic mobility, which allows your torso upward by contracting the iliopsoas, tensor fasciae latae, and rectus femoris in order to flex the hips.

5 INCLINE BENCH SIT-UPS


Pectoralis major
Rectus abdominis
Quadriceps, rectus femoris
Patella
Quadriceps, vastus lateralis
Fascia lata
Tibialis anterior
Teres major
Latissimus dorsi
Serratus anterior
External oblique
Gluteus medius
Tensor fascia lata
Greater trochanter
Gluteus maximus
Gastrocnemius, lateral head
Soleus
Extensor digitorum longus

VARIATION WITH TORSO ROTATION

ORIENTATION OF THE ABDOMINAL MUSCLES
THAT SUPPORT AND PROTECT THE INTERNAL ORGANS

In quadrupeds, the muscles of the abdominal core create a hammock-like structure that passively supports the internal organs. These muscles move little during locomotion.

With the shift to bipedal locomotion in humans, the muscles of the abdominal core have grown stronger to align the pelvis with the trunk in a vertical position and to prevent the trunk from swaying too much during walking or running.

The abdominal core has developed into powerful muscles that actively contain the internal organs.


1 Rectus abdominis
2 External oblique
3 Internal oblique
4 Transversus abdominis
1
2
3
4

Sit on a bench with the feet positioned under the rolls, hands behind the ears:

- Inhale and lower the torso less than 20 degrees.
- Raise the torso while slightly rounding the back to better focus on the rectus abdominis.
- Exhale at the end of the movement.

Perform this exercise in long sets. It works the abdominal core as well as the iliopsoas, tensor fascia lata, and rectus femoris of the quadriceps. The latter three muscles tilt the pelvis forward.

Variation: Rotating the torso on the way up focuses some of the effort on the internal and external obliques.

Example: Rotating to the left works the right external oblique, the left internal oblique, and the right rectus abdominis more intensely. Rotations can be performed in sets of alternating sides or sets all on the same side. In either case, concentrate on feeling the muscles contract. There is no point in angling the bench excessively.

SUSPENDED BENCH SIT-UPS 6




Quadriceps, rectus femoris
Tibialis anterior
Peroneus longus
Quadriceps, vastus intermedius
Patella
Rectus abdominis
Peroneus brevis
Soleus
Gastrocnemius, lateral head
Extensor digitorum longus
Quadriceps, vastus lateralis
Fascia lata, iliotibial band
Greater trochanter
Gluteus maximus
External oblique
Tensor fascia lata
Gluteus medius


FLEXOR MUSCLES OF THE HIP
Iliopsoas
Psoas major
Psoas minor
Iliacus
Iliopsoas
Tensor fascia lata
Rectus femoris
Sartorius
Vastus lateralis
Rectus femoris
Vastus medialis
Quadriceps

Position the feet under the pads, with the torso suspended in midair, hands near the ears:

- Inhale and raise the torso, trying to bring the head to the knees while rounding the spine.
- Exhale at the end of the contraction.

This exercise develops the rectus abdominis. It also contracts the obliques, but less intensely.

Because of the forward tilt of the pelvis, the rectus abdominis, iliopsoas, and tensor fascia lata contribute strongly.

Comment: This movement requires a fair amount of strength, which you can build through other easier exercises.


1 The movement


2 Variation with arms extended in front to make the movement easier.

7 HIGH-PULLEY CRUNCHES


Pectoralis major
Serratus anterior
Latissimus dorsi
External oblique
Rectus abdominis
Iliac crest
Gluteus medius
Pyramidalis
Iliopsoas
Tensor fascia lata
Pectineus
Quadriceps, rectus femoris
Sartorius
Greater trochanter
Gluteus maximus
Fascia lata, iliotibial band

ACTION OF THE ABDOMINAL MUSCLES



Kneel in front of the machine, holding the handle behind the neck:

- Inhale.
- Exhale and roll the spine as you lower the sternum toward the pubis.

This movement is never performed with heavy weights. Concentrate on feeling the muscles contract, mainly the rectus abdominis, in order to focus the work on the abdominal core.

MACHINE CRUNCHES

8


Latissimus dorsi
Serratus anterior
External oblique
Rectus abdominis
Quadriceps, vastus lateralis
Gluteus medius
Tensor fascia lata
Fascia lata, iliotibial band
Biceps femoris, short head
Peroneus longus
Extensor digitorum longus
Pectoralis major
Quadriceps, rectus femoris
Quadriceps, vastus medialis
Patella
Sartorius
Tibialis anterior
Gastrocnemius, medial head
Soleus
Tibia

RECTUS ABDOMINIS MUSCLES


Sternum
Costal cartilage
Linea alba
11th rib
12th rib
Iliac fossa
Anterior superior iliac spine
Head of femur
Pubic tubercle
Greater trochanter
5th rib
Rectus abdominis
Tendinous inscription
Umbilicus
Pyramidalis
Inguinal ligament
Neck of femur
Femur
Pubic symphysis

Sit at the machine, grasp the handles, and position the feet under the pad:

- Inhale and roll the spine, trying to bring the sternum to the pubis.
- Exhale at the end of the movement.

This exercise allows you to adjust the weight, or workload, to your ability. To avoid risk, beginners should use light weights. Well-trained athletes can use heavier weights.

9 INCLINE LEG RAISES




Soleus
Gastrocnemius, medial head
Extensor digitorum longus
Biceps femoris, short head
Peroneus longus
Semimembranosus
Tibialis anterior
Biceps femoris, long head
Quadriceps, vastus lateralis
Semitendinosus
Fascia lata, iliotibial band
Quadriceps, rectus femoris
Tensor fascia lata
Adductor magnus
Gluteus maximus
Greater trochanter
Rectus abdominis
External oblique
Gluteus medius
Latissimus dorsi



VARIATION
Performing leg flutters

Lie on an incline bench and grip the bars or handles:

- Inhale and raise the legs to horizontal, then raise the pelvis, rolling the spine up as if trying to bring the knees to the head.

This exercise first works the iliopsoas, tensor fascia lata, and rectus femoris of the quadriceps when raising the legs. Then it works the abdominal core and contracts mainly the infraumbilical portion of the rectus abdominis when raising the pelvis and rolling up the spine.

Comment: This is an excellent exercise if you have trouble feeling the work on the lower abdominal muscles. Given the difficulty of the exercise, beginners should start with the bench only slightly inclined.



1 Pelvis in posterior tilt
2 Pelvis in neutral position
3 Pelvis in anterior tilt

LEG RAISES 10


THE MOVEMENT
Sternum
Serratus anterior
Deltoid
Clavicle
Scapula
Humerus
Rib
Costal cartilages
12th rib
Vertebra
Psoas minor
Iliacus
Psoas major
Iliopsoas
Pubic symphysis
Greater trochanter
Pectineus
Lesser trochanter
Adductor longus
Gracilis
Sartorius
Femur
Patella
Tibial tuberosity
Fibula
Latissimus dorsi
Serratus anterior
Rectus abdominis, under the aponeurosis
External oblique
Anterior superior iliac spine
Gluteus medius
Sacrum
Iliopsoas
Pyramidalis, under the aponeurosis
Tensor fascia lata
Fascia lata, iliotibial band
Quadriceps
Rectus femoris
Vastus medialis
Vastus lateralis
Vastus intermedius
Patellar ligament
Gastrocnemius
Tibialis anterior
Extensor digitorum longus
Peroneus longus
Soleus
Flexor digitorum longus
Peroneus brevis
Extensor hallucis longus
Tibia, medial surface
Talus
Navicular
Cuneiform
Cuboid
Metatarsal
Proximal phalanx
Distal phalanx
ILIOPSOAS ACTION
Iliopsoas
Psoas
Iliacus
Vertebra
Os coxa
Sacrum
Pubic symphysis
Head of femur
Femur

Support the body by resting the elbows on the pads. Position the back against the back support:

- Inhale and raise the knees to the chest, rounding the back in order to contract the abdominal core.
- Exhale at the end of the movement.

This exercise works the hip flexors, mainly the iliopsoas, and the obliques. It intensely works the lower part of the rectus abdominis.

Variations:

1 To target the lower abdominal muscles, perform small flutters with the legs when rolling up the spine.

2 To make the exercise more intense, extend the legs horizontally. However, this requires flexible hamstrings.

3 Hold the knees to the chest for a few seconds with an isometric contraction.

11 HANGING LEG RAISES



VARIATION

Alternately raising the legs to the left and then to the right side uses the internal and external obliques more intensely.


Quadriceps, vastus lateralis
Biceps femoris, short head
Patella
Quadriceps, vastus intermedius
Extensor digitorum longus
Peroneus longus
Tibialis anterior
Tibia
Peroneus brevis
Rectus abdominis
External oblique
Quadriceps, rectus femoris
Gluteus medius
Tensor fascia lata
Fascia lata
Greater trochanter
Gluteus maximus
Biceps femoris, long head
Semitendinosus
Semimembranosus
Gastrocnemius, lateral head
Soleus



Hang from a chin-up bar:

- Inhale and raise the knees as high as possible by rolling up the spine and bringing the pubis toward the sternum.
- Exhale at the end of the movement.

This exercise uses the iliopsoas, rectus femoris, and tensor fascia lata when you raise the legs and the rectus abdominis and, to a lesser degree, the internal and external obliques when you bring the pubis toward the sternum.

Small leg flutters without lowering the knees below horizontal focus the effort on the abdominal core.


Hypertonic spinal erector muscles create an excessive lumbar curve.
Hypotonic abdominal muscles create abdominal ptosis.
Kyphosis (rounding of the upper back)
Hypotonic spinal erector muscles with loss of lumbar curve.
Hyper-tonic abdo-minal muscles.

ABDOMINAL–LUMBAR EQUILIBRIUM

Balance the work between the abdominal muscles and the erector muscles of the spine.

Hypotonicity or hypertonicity of either of these muscle groups can lead to poor posture, which over time can cause injury.

Example

Hypertonicity of the lower part of the erector muscles of the spine (lumbosacral mass) associated with hypotonicity of the abdominal muscles leads to hyperlordosis with abdominal ptosis (sagging).

If addressed in time with exercises to strengthen the abdominal core, this postural fault can sometimes be corrected.

Conversely, hypertonic abdominal muscles associated with slack erector muscles, especially in the upper part (spinalis thoracis, longissimus thoracis, iliocostalis thoracis) leads to kyphosis (rounding of the upper back) with loss of the lumbar curve. This postural fault can be corrected with exercises to strengthen the erector muscles of the spine.

BROOMSTICK TWISTS 12


Deltoid
Biceps brachii
Latissimus dorsi
Serratus anterior
External oblique
Gluteus medius
Tensor fascia lata
Iliopsoas
Pectineus
Fascia lata, iliotibial band
Adductor longus
Quadriceps, rectus femoris
Quadriceps, vastus lateralis
Pectoralis major
Rectus abdominis
Internal oblique, in deep
Pyramidalis
Sartorius
Gracilis
Adductor magnus
Quadriceps, vastus medialis



Stand with the legs apart, holding a stick across the trapezius above the posterior deltoid, hands resting on the stick without pushing:

- Rotate the torso to one side and to the other, keeping the pelvis fixed with isometric contraction of the gluteal muscles.

When the right shoulder is forward, this exercise works the right external oblique and, deep in, the left internal oblique and, to a lesser degree, the rectus abdominis, quadratus lumborum, and the extensor muscles of the spine on the left side.

To increase the intensity, round the back slightly.

You can also perform the movement while seated, which helps to fix the pelvis so that you can focus the effort on the abdominal core.

Best results are obtained with sets lasting several minutes.



VARIATION
Seated on a bench.

13

DUMBBELL SIDE BENDS


Sternum
Rib
Xiphoid process
Lumbar vertebra
Os coxa
Sacrum
Pyramidalis
Pubic symphysis
Costal cartilages
Rectus abdominis
External oblique
Rectus abdominis, under the aponeurosis
Internal oblique, under the aponeurosis
Femur





VARIATION AT A LOW PULLEY


Rib
Vertebra
Os coxa
Intercostal muscles
Quadratus lumborum
Sacrum
Coccyx

QUADRATUS LUMBORUM MUSCLE

Stand with the legs slightly apart, one hand behind the head and holding a dumbbell in the other hand:

- Bend the torso to the side opposite to the dumbbell.
- Return to the initial position or beyond with passive flexion of the torso.
- Alternate sets changing the side of the dumbbell without resting.

This exercise mainly works the obliques on the side the torso bends toward. It works the rectus abdominis, deep muscles of the back, and quadratus lumborum (back muscle that inserts on the 12th rib, the transverse processes of the lumbar vertebrae, and the iliac crest) less intensely

ROMAN CHAIR SIDE BENDS

14



This exercise is performed on a bench originally designed for lumbar extensions.
Lie on your side with the hip on the bench, torso in the air, hands near the ears or on the chest, and feet positioned under the rolls:

- Raise the side of the body toward the ceiling.

This exercise mainly works the obliques and rectus abdominis on the side that is bending, but the opposite obliques and rectus abdominis are also used in isometric contraction to prevent the torso from lowering below horizontal.

Comment: The quadratus lumborum muscle is always used when bending the torso toward the side.


Pectoralis major
Serratus anterior
Rectus abdominis
External oblique
Internal oblique, under the aponeurosis
Tensor fascia lata
Adductor longus
Quadriceps, rectus femoris
Quadriceps, vastus medialis
Patella
Latissimus dorsi
Pyramidalis
Gluteus medius
Quadriceps, vastus lateralis
Iliopsoas
Pubic symphysis
Sartorius
Pectineus


5th rib
Rectus abdominis
12th rib
External oblique
Lumbar vertebra
Iliac crest
Os coxa
Sacrum
Acetabulum
Anterior superior iliac spine
Inguinal ligament
Pubic tubercle

EXTERNAL OBLIQUE MUSCLE OF THE ABDOMEN


Vertebra, spinous process
Erector spinae, under the aponeurosis
Iliac crest
Os coxa
Sacrum
Ischial tuberosity
Sternum
Rib
Rectus abdominis
Costal cartilage
Rectus abdominis, under the aponeurosis
Internal oblique
Anterior superior iliac spine
Inguinal ligament
Pubic tubercle

INTERNAL OBLIQUE MUSCLE OF THE ABDOMEN

15 MACHINE TRUNK ROTATIONS





VARIATION SEATED AT A MACHINE


Rectus abdominis
Gluteus medius
Tensor fascia lata
Pyramidalis
Pubic symphysis
Quadriceps, rectus femoris
Fascia lata, iliotibial band
External oblique
Anterior superior iliac spine
Internal oblique, under the aponeurosis
Iliopsoas
Pectineus
Sartorius
Adductor longus
Gracilis
Quadriceps, vastus medialis
Quadriceps, vastus lateralis


Sternum
5th rib
Rectus abdominis
Costal cartilage
Linea alba
Transversus fascia of the abdomen
Internal oblique
Transversus abdominis
Umbilicus
Rectus abdominis, section
Anterior superior iliac spine
Inguinal ligament
Neck of femur
Femur
Head of femur
Pubic symphysis
Greater trochanter
Pubic tubercle

DEEP MUSCLES OF THE ABDOMEN

Stand on the swivel plate and grasp the handle:

- Rotate the pelvis to one side then to the other, keeping the shoulders fixed. The knees should be slightly bent. Control the rotations.

This exercise mainly works the external and internal obliques and, to a lesser degree, the rectus abdominis.

To feel the effort more intensely on the external and internal obliques, round the back slightly.

Best results are obtained with very long sets.



MAIN MUSCLE GROUPS

- ● Abdominals
- ● Adductors
- ● Dorsal muscles
- ● Shoulders
- ● Arm extensors
- ● Wrist extensors
- ● Gluteals
- ● Arm flexors
- ● Wrist flexors
- ● Scapulae fixers
- ● Thigh flexors
- ● Lumbar muscles
- ● Surae
- ● Pectorals
- ● Quadriceps
- ● Trapezii


Sagittal suture
Parietal foramen
Superior nuchal line
Inferior nuchal line
Mastoid notch
Atlantooccipital membrane
Superior transverse scapular ligament
Acromioclavicular ligament
Coracohumeral ligament
Articular capsule
Supraspinous ligament
External intercostal muscle
Intertransverse ligament
Articular capsule
Lateral intermuscular septum
Medial intermuscular septum
Radial collateral ligament
Ulnar collateral ligament
Radial annular ligament
Interosseous membrane
Ulnar collateral ligament
Dorsal radiocarpal ligament
Radial collateral ligament
Dorsal intercarpal ligament
Dorsal metacarpal ligament
Collateral ligament
Collateral ligament
Articular capsule
Deep transverse metacarpal ligament
Iliofemoral ligament
Ischiofemoral ligament
Posterior sacroiliac ligament
Sacrotuberous ligament
Sacrospinous ligament
Sacrococcygeal ligament
Coccyx
Pubic symphysis
Adductor magnus tendon
Medial head of gastrocnemius
Articular capsule
Gastrocnemius lateral head
Oblique popliteal ligament
Fibular collateral ligament
Arcuate popliteal ligament
Popliteus muscle
Posterior ligament of head of fibula
Semimembranosus tendon
Tibial collateral ligament
Interosseous membrane
Posterior tibiofibular ligament
Deltoid ligament
Lateral talocalcaneal ligament
Medial talocalcaneal ligament
Calcaneofibular ligament
Calcaneal tendon
Parietal bone
Occipital bone
Temporal bone
Lateral occipital protuberance
Mastoid process
Mandible
Atlas, 1st cervical vertebra
Axis, 2nd cervical vertebra
Clavicle
Acromion
Spine of scapula
Head of humerus
Greater tuberosity
Medial border
Lateral border
Scapula
Diaphysis of humerus
Deltoid tuberosity
Groove of radial nerve
Transverse process
10th thoracic vertebra
12th rib (floating rib)
Olecranon fossa
Lateral epicondyle
Medial epicondyle
Olecranon
Head of radius
3rd lumbar vertebra
Spinous process
Costoid process
Iliac crest
Anterior gluteal line
Posterior superior iliac spine
Radius
Anterior superior iliac spine
Ulna
Sacrum
Head of femur
Ischial spine
Head of ulna, styloid process
Styloid process
Scaphoid
Lunate
Pisiform
Trapezium
Triquetral
Greater trochanter
Neck of femur
Lesser trochanter
Gluteal tuberosity
Ischial tuberosity
Diaphysis of femur
Inferior pubic ramus
Trapezoid
Capitate
Hamate
Metacarpal
Proximal phalanx
Middle phalanx
Distal phalanx
Linea aspera
Medial supracondylar line
Lateral supracondylar line
Popliteal surface
Adductor tubercle
Lateral epicondyle
Lateral condyle
Medial condyle
Intercondylar fossa
Meniscus
Medial condyle
Head of fibula
Soleal line
Body of tibia
Body of fibula
Medial malleolus
Lateral malleolus
Navicular
Calcaneus
Cuboid bone
Metatarsal
Proximal phalanx


Frontal bone
Supraorbital foramen
Parietal bone
Sphenoid bone
Infraorbital foramen
Mandible
Mental foramen
Interclavicular ligament
Anterior sternoclavicular ligament
Costoclavicular ligament
Conoid ligament
Trapezoid ligament
Acromioclavicular ligament
Coracoacromial ligament
Supraspinatus tendon
Coracohumeral ligament
Subscapularis muscle
Biceps brachii tendon, long head
Sternocostal ligament
Interchondral ligament
Internal intercostal muscle
External intercostal muscle
Medial intermuscular septum
Lateral intermuscular septum
Radiate ligament of costal head
Anterior longitudinal ligament
Articular capsule
Ulnar collateral ligament
Annular ligament of radius
Radial collateral ligament
Oblique cord
Intertransverse ligament
Interosseous membrane
Palmar radioulnar ligament
Palmar radiocarpal ligament
Palmar ulnocarpal ligament
Radial collateral ligament
Flexor retinaculum
Deep transverse metacarpal ligament
Ulnar collateral ligament
Pisohamate ligament
Palmar ligament
Tooth
Lumbar vertebra
Intervertebral disc
Sacral promontory
Iliac ala
Costoid process
Iliolumbar ligament
Anterior sacroiliac ligament
Sacrum
Iliofemoral ligament
Inguinal ligament
Pubofemoral ligament
Sacrospinous ligament
Sacrotuberous ligament
Obturator membrane
Superior pubic ligament
Coccyx
Arcuate pubic ligament
Pubic symphysis
Adductor magnus tendon
Quadriceps tendon
Suprapatellar bursa
Quadriceps, vastus medialis
Quadriceps, vastus lateralis
Lateral patellar retinaculum
Fibular collateral ligament
Medial patellar retinaculum
Tibial collateral ligament
Interosseous membrane
Anterior tibiofibular ligament
Articular capsule
Deltoid ligament
Anterior talofibular ligament
Deep transverse metatarsal ligament
Nasal bone
Superior orbital fissure
Lacrimal bone
Inferior orbital fissure
Temporal bone
Zygomatic bone
Mastoid process
Mandible
Clavicle
Acromion
Coracoid process
Head of humerus
Greater tuberosity
Lesser tuberosity
Bicipital groove
Glenoid cavity
Scapula
Sternum
5th rib (true rib)
Deltoid tuberosity
12th rib (false rib) costal cartilage
Xiphoid process
12th rib (floating rib)
Medial epicondyle
Trochlea of humerus
Capitulum of humerus
Head of radius
Coronoid process
Ulnar tuberosity
Radial tuberosity
Iliac crest
Anterior superior iliac spine
Anterior inferior iliac spine
Ulna
Radius
Head of ulna
Lunate
Scaphoid
Trapezium
Capitate
Trapezoid
Triquetral
Pisiform
Hamate
Metacarpal
Proximal phalanx
Middle phalanx
Distal phalanx
Greater trochanter
Head of femur
Neck of femur
Lesser trochanter
Superior pubic ramus
Ischial tuberosity
Pubic tubercle
Inferior pubic ramus
Femur
Adductor tubercle
Patella
Medial condyle
Lateral condyle
Meniscus
Head of fibula
Tibial tuberosity
Medial surface of tibia
Tibia
Fibula
Medial malleolus
Talus
Navicular
Lateral malleolus
Cuneiform bone
Cuboid bone
Metatarsal
Proximal phalanx
Middle phalanx
Distal phalanx

Strength Training Anatomy

Discover for yourself the magic of *Strength Training Anatomy*, one of the best-selling strength training books ever published!

Get an inside look at the human form in action with more than 400 full-color illustrations. This detailed artwork showcases the muscles used during each exercise and delineates how these muscles interact with surrounding joints and skeletal structures. Like having an X-ray for each exercise, the information gives you a multifaceted view of strength training not seen in any other resource.

This updated bestseller also contains detailed anatomical analysis of training injuries and preventive measures to help you exercise safely. Chapters are devoted to each major muscle group, with 115 total exercises for arms, shoulders, chest, back, legs, buttocks, and abdomen.

The former editor in chief of *PowerMag* in France, author and illustrator **Frédéric Delavier** is a journalist for *Le Monde du Muscle* and a contributor to *Men's Health Germany* and several other strength publications.

ISBN 0-7360-6368-4
51995
9 780736 063685
$19.95
In Canada $26.95

Human Kinetics

The Ultimate At-Home Guide to Strengthening, Lengthening,
and Toning Your Body—Without Machines



The
Pilates® Body

BROOKE SILER

Owner of `re:AB` *and Certified Instructor in the Pilates® Method*

The Ultimate At-Home Guide to Strengthening, Lengthening, and Toning Your Body—Without Machines



The Pilates® Body

BROOKE SILER

Owner of re:AB and Certified Instructor in the Pilates Method®

Broadway Books
New York

BROADWAY

THE PILATES® BODY. Copyright © 2000 by Brooke Siler.
All rights reserved. Printed in the United States of America.
No part of this book may be reproduced or transmitted in any form or
by any means, electronic or mechanical, including photocopying,
recording, or by any information storage and retrieval system,
without written permission from the publisher. For information,
address Broadway Books, a division of Random House, Inc.,
1540 Broadway, New York, NY 10036.

Broadway Books titles may be purchased for business and
promotional use or for special sales. For information, please write to:
Special Markets Department, Random House, Inc., 1540 Broadway,
New York, NY 10036.

BROADWAY BOOKS and its logo, a letter B bisected on the diagonal,
are trademarks of Broadway Books, a division of Random House, Inc.

Visit our Web site at www.broadwaybooks.com

Library of Congress Cataloging-in-Publication Data

Siler, Brooke, 1968–
The pilates body : the ultimate at-home guide to strengthening,
lengthening, and toning your body—without machines /
by Brooke Siler. — 1st ed.
p. cm.
ISBN 0-7679-0396-X
1. Exercise. 2. Physical fitness. 3. Mind and body. I. Title.
RA781.S5645 2000
613.7'1—dc21 99-36046
CIP

FIRST EDITION

PHOTOGRAPHS BY MARC ROYCE
ILLUSTRATED BY MEREDITH HAMILTON
DESIGNED BY TINA THOMPSON

00 01 02 19 18 17 16 15

Pilates® and the Pilates Studio® are registered trademarks of Pilates, Inc.,
and are used with permission.

I dedicate this book to the everlasting spirit of my father, Bern Siler, who
taught me about the incredible creative power of the mind, the intricacy
of the body, and the overwhelming importance of positive thought.

I would also like to dedicate this book to the tireless effort of
Romana Kryzanowska to keep alive the spirit of Joseph Pilates and
his work. It is through her enthusiasm and integrity for the
Pilates method that we all come to benefit.
She is an inspirational example of the powers of devotion and dedication,
and it is an honor to continue to study under her.
Thank you, Romana!

Acknowledgments

The author would like to thank the following for their participation in the production of this book:

Photographer extraordinaire: Marc Royce.

Hair, make-up, and style guru: Bryan Marryshow.

Model dynamos: Julianna Womble, Caitlin Cook, and Dana Eisenstein.

To Romana Kryzanowska, Sari Pace, Sean Gallagher, Elyssa Rosenberg and The Pilates Studio for their superb training.

For the use of their clothing: Capezio, Baryshnikov, Danskin, and Norma Kamali.

For their professional support and encouragement: Charles Bergau, Michele Hicks, Kevin Jennings, Erika Morrell, Bruce Lederman, Lauren Marino and the Broadway team, and the entire gang at re:AB. Thank you!

A very special thank you to Debra Goldstein for her never-ending support and enthusiasm! You take literary agenting to a new level!

And to Mom . . . for teaching me that I can do whatever I want to do if I put my mind to it! I love you.



From the archives of The Pilates Studio®

Joseph Pilates, the founder of the Pilates Method of Contrology.

Physical fitness can neither be achieved by wishful thinking nor outright purchase.

—JOSEPH PILATES

Contents

What Is Pilates? 1
Philosophies Behind the Pilates Method of Body Conditioning 7
The Matwork Principles 15
Key Elements to Mastering the Mat 19
Frequently Asked Questions 25
The Matwork 33
  Getting Started: Modified Beginner Matwork 35
  The Pilates Mat: Full Program 50
  Advanced Extras 145
  The Standing Arm Series 159
  The Wall (Cooldown) 170
The Next Step 174
Glossary 193

What Is Pilates?

The Pilates® method of body conditioning is a unique system of stretching and strengthening exercises developed over ninety years ago by Joseph H. Pilates. It strengthens and tones muscles, improves posture, provides flexibility and balance, unites body and mind, and creates a more streamlined shape.

At a time when the fitness industry is tripping over itself to create new, innovative trends, the Pilates method, with more than nine decades of success, stands out as a tried-and-true formula of wisdom and unwavering results. Pilates was developed to create a healthy body, a healthy mind, and a healthy life, and people are ready to heed its message of balance.

Whether because of a new consciousness or an intense dissatisfaction with the results of trendy exercise programs, in the past five years there has been a tremendous surge in the mind-body focus movement. People are beginning to realize how inefficient the exercises of the 1980s really were. We may have bought into the no-pain-no-gain mentality, but ultimately that led us to spend too much of our precious spare time chained to the gym. We now realize that while exercise should be an important part of our lives, it should add to and not take away from our enjoyment of a full life. With Pilates, specifically the matwork, we can minimize the amount of time spent in a gym or in front of an exercise video, but maximize the results achieved from a full-body workout. The matwork teaches us that the body is the finest and only tool necessary for achieving physical fitness.

Our old exercise regimes are failing us for another reason: They are based on isolating muscles and working each area of the body individually rather than treating the body as the integrated whole it is. The poor physical condition many of us are in today comes from the imbalance of engaging in complicated, inefficient exercises that isolate certain body parts while neglecting others. If our goal in exercising is to balance our bodies, improve circulation, reduce stress, improve endurance, look better, and feel great, then wouldn't it stand to reason that we should utilize the one method that for over nine decades has proven its ability to achieve all these things?

The Pilates philosophy focuses on training the mind and body to work together toward the goal of overall fitness. Although born in a completely different era, Joseph Pilates understood the physical and mental pressures of a busy schedule. He sought to reeducate us to work our bodies with the efficiency of performing our daily tasks in mind. Pilates believed that his method would propel people to become more productive both mentally and physically. For this reason the Pilates matwork is designed to fit into the physical and time constraints of the individual without diminishing its comprehensive elements.

Pilates began developing his exercise system in Germany in the early 1900s. Plagued by asthma and rickets as a child, Pilates' method sprang from his determination to strengthen his frail and sickly body. He called his method "The Art of Contrology," or muscle control, to highlight his unique approach of using the mind to master the muscles. Interned during the First World War, he taught his method to fellow internees and successfully maintained their health through the deadly influenza epidemic of 1918. During the latter part of the war Pilates served as an orderly in a hospital on the Isle of Man, where he began working with nonambulatory patients. He attached springs to the hospital beds to support the patients' ailing limbs while he worked with them, and he and the doctors noticed that the patients were improving faster.

These spring-based exercises became the basis for the apparatus Pilates would later design to be used in conjunction with the matwork. That is why the Pilates name is often associated with antiquated-looking machines, but the matwork is the original movement system that Joseph Pilates created and is just as effective as the work done on the machines. This book shows the entire matwork sequence and has the advantage of being completely portable. The movements of Pilates matwork need no accoutrements and can be performed anywhere a normal human body can fit comfortably when stretched out at full length.

Joseph set up the first official Pilates Studio® in New York City after immigrating to the United States in 1926. Since its introduction to American culture Pilates has maintained a steady and devout following. It has been the secret of dancers and performers since the late 1920s; Martha Graham and George Balanchine were big fans. In recent years it has been discovered by athletes, models, and actors who say they owe their strong, lithe bodies to the Pilates method.

Joseph Pilates authored a book in 1945 called *Return to Life*. That title epitomizes the very nature of the Pilates method. Through concentrated and creative effort you too will reap the myriad benefits that this unique method of conditioning has to offer, reawakening your body through movement and your mind through conscious thought. The combination results in the extra plus of the Pilates method: a revitalization of spirit that is a crucial factor in maintaining good health and a sound mind and body.

"Ideally, our muscles should obey our will. Reasonably, our will should not be dominated by the reflex actions of our muscles." Joseph Pilates believed in the power of our minds to control our bodies. He proved his theory time and again through years of research and training, and his legacy has been passed down through his students.

I have been involved in health clubs in one form or another since the age of fifteen and have tried all that they have to offer. I spent years as a personal trainer using weights and machines and sincerely believed that I had put all the strength into my body that it might need. I was wrong. What I had done was create a bulky, stiff set of muscles in a young, active body. I spent hours in the gym daily trying to create a feeling of well-being that was eluding me at every turn. I continued to have aches and pains that no amount of training would alleviate, and worst of all . . . I was bored!

And then I discovered the Pilates method of body conditioning. Within a matter of weeks I began to feel the internal strength that I had craved. My movements became more controlled and responsive. I was standing straighter and feeling more energized than ever before. After a few short months my bulky muscles began lengthening and my flexibility increased tenfold. I felt as graceful and lithe as a dancer. Subsequently my aches and pains vanished and I found myself enjoying my activities more. Most important, I felt empowered by my newfound knowledge. I was interested. I was in control. I was hooked.

Two and a half months after discovering Pilates I enrolled in the certification course, and in the years since, I have enveloped myself in the world of Pilates as both student and teacher. I have trained for thousands of hours and

Master Instructor
Romana Kryzanowska

have watched the magic of this method unfold before my eyes both in my own work and in the work of my clients.

I continue to study under the master tutelage of Romana Kryzanowska, who was chosen by Joseph and his wife, Clara Pilates, to carry on his work. I bring you *The Pilates Body* in the effort to further expound upon the brilliance of this method in a clear, concise, and creative way. For each movement I have provided visual and verbal cues that will stimulate your mind to action. With patience and perseverance your body will follow, allowing you to experience the efficiency of the Pilates method.

The beauty of Pilates is that once you understand the core of its philosophy, its movements can be translated into any format. Each exercise is an important movement in and of itself and can be used as a way to stretch and move correctly in the course of one's day, but it is not a limited exercise regimen. Many people use the essence of the exercises to enhance other activities; athletes, for example, employ the movements and philosophy of Pilates in their sports. But whether you're an athlete or a couch potato, young and limber or old and inflexible, the Pilates method can and does change the way you relate to your own body and the way you carry it in the world.

The power each of us holds to take control over our own well-being is startling. It begins by becoming aware of our bodies as an integrated part of our creative minds. We were all born with that power. We were all children with active imaginations that continue to live inside us. Sometimes we only need reminding. This book is that reminder. Instead of giving your power away, you will learn to harness it and use it for your very own. This book



From the archives of The Pilates Studio®

Joseph Pilates and his wife, Clara, on one of the original Pilates apparatus.

will teach you to creatively blend the power of your mind with the movement of your body in a way that is both efficient and extremely enjoyable. It is important that you understand the role you play in all of this. It's all about you. What you put in is what you'll receive, no more and no less.

Remember that with the power of your mind you can bring anything to light, so see your goal and then work to achieve it. This book will serve as a tool to help you along the path, but remember that it is your dedication to yourself that ultimately makes it all possible.

Good luck, and above all else . . . enjoy yourself!



From the archives of The Pilates Studio®

Joseph Pilates demonstrates the "Natural Rejuvination of The Human Body through 'Contrology' Balance of Body and Mind."

Philosophies Behind the Pilates Method of Body Conditioning

"PHYSICAL FITNESS IS THE FIRST REQUISITE OF HAPPINESS"

Joseph Pilates believed that in order to achieve happiness it is imperative to gain mastery of your body. If at the age of thirty you are stiff and out of shape, then you are "old." If at sixty you are supple and strong, then you are "young."

Pilates' development of his method evolved into a vision of an ideal lifestyle, attained only through balance of the physical, mental, and spiritual. Through visualization, physical strengthening and stretching of the body, mental vigor and improved blood flow returns to inactive brain cells. This renewed spirit of thought and movement is the first step toward stress reduction, grace of movement, alacrity, and a greater enjoyment of life.

One of the best examples of this theory is a child at play. The suppleness and vitality of a child are often envied, as if they were traits we no longer possess. Says who? With patience, perseverance, and a strong will all things are possible.

REDUCING STRESS AND FATIGUE

In today's fast-paced life the physical and mental stresses we encounter are dangerous threats to both our health and our happiness. We spend countless hours sitting in front of our computers or bent over our desks, or we're running around, lifting, lugging, and creating havoc in our bodies and minds. Without properly caring for our bodies it is impossible to feel good. Most if not all of our stress and fatigue comes from poor posture, imbalances in the body, and lack of correct breathing. We must first learn to properly strengthen and control our muscles before subjecting them to the rigors of daily living.

These days it seems that only our hobbies and leisure activities keep us relaxed and invigorated, but why should that be so when we can so easily utilize the strength and suppleness inherent in our bodies?

The Pilates method of body conditioning is not an arduous technique that leaves you tired and sore. In fact, quite the opposite is true. By allowing the movements to stretch your body as you simultaneously work on the strengthening elements of the method, you are creating a habit of relaxed effort for your body to follow. We are far too used to straining ourselves in the effort to strengthen our muscles when we should be enjoying the movements themselves.

USING VISUAL IMAGES TO ENGAGE YOUR MIND AND BODY

Most exercise dropouts claim boredom as their number-one excuse—not hard to believe considering that most people work out only because they feel they "should" and not because it feels good or adds to their mental stimulation.

Think about all the hours you have spent exercising and letting your mind drift away from what you are doing. Instead of watching television or thinking about taxes and baby-sitters, remember what it is you are trying to achieve. Essentially, when you work your body without engaging your mind, you are performing only half a workout. It is the least efficient way to achieve the goals you have set for yourself. The opposite is also true in the lifestyle standards we set for ourselves. By engaging our minds at work without considering the physical toll today's jobs take on our bodies, we are setting ourselves up for a fall. "Sound body, sound mind"—sound advice!

Visual imaging is a relatively new concept in the realm of fitness, but it is by far the most effective. Using visual images to engage the mind is the fastest way to gain access to our complex anatomical system. By using visual metaphors you are able to subconsciously call upon the use of your muscles without needing the technical knowledge of muscles and their functions. If I tell you to "sit up tall as if your head were touching the ceiling," not only are you using your mind's eye to visualize that sensation, but you have also employed myriad muscles you probably never knew existed. You are presenting your mind and body with a challenge that unites their efforts to achieve that goal.

When you create a familiar, albeit imagined, situation within your mind, the body is able to instinctively respond. The creation of that situation is what engages the mind and makes the process more enjoyable. Essentially, it is your own creative ability that will control the actions of your body.

TRIGGERING INSTINCTUAL MUSCLE REACTION THROUGH VISUAL IMAGES

Visual imaging creates a frame of reference for your body to follow. By asking your mind to conjure up images, the innate signaling system of your body is triggered. Like a telephone switchboard, images are routed through your brain and transferred into instinctual movements. Imagine how your body would react if you were punched in the gut. Not pleasant, but the thought alone is enough to trigger a physical response. Similarly, expressions such as "walking on air" or "a spring in your step" can be manifested physically.

The movements of the matwork will become as much second nature as skipping, twisting, reaching, or bending over to pick up a dropped pen. The benefit is that you no longer need to think of movement as belonging only in an exercise class. You will begin to trigger the same awareness in the movements of your daily activities that you have while focused in a class.

Pilates believed that proper movements should become as natural to a person as they are to an animal. When an animal raises itself off the ground, it stretches from its head to its claws to its tail. It leaves nothing out. When we humans move, we tend to focus on one area or another and ignore the rest. The irony is that most everything we do, from walking to sitting up, can and should utilize all our muscles.

Subconscious rhythm is inherent in us all. When we walk, run, gesture, and move in general, we do so without thinking. This is the way it should be, and this is the way the Pilates method was designed to work. By flowing from one movement to the next, you will re-create the natural rhythm of the body. I have made sure to include transitional directions in each exercise so that as you progress you will know how to move smoothly from one exercise to the next.

The goal of the matwork sequence, at any level, is to create a natural flow of movement and then to gradually increase the dynamic, or energy, with which you perform the movements without sacrificing control. Eventually the time it takes to complete your mat sequence should decrease to where you can choose some or all of the exercises and not lose the efficiency with which you perform each one.

MAKING THE CONNECTION BETWEEN PILATES AND YOUR DAILY ACTIVITIES

At first the movements of the matwork may seem unconnected to your daily routine. However, with patience and persistence you will begin to understand how the movements are merely tools to understanding your body. Once learned, muscle control can be applied to any function of physical movement, from walking and running to lifting and carrying.

Structured around the stomach, hips, lower back, and buttocks—the center of the body, or its "powerhouse"—the movements of the Pilates method are instrumental in maintaining good posture and alignment. These are key elements in proper muscle use and make even the most difficult daily tasks seem effortless.

"NEVER DO TEN POUNDS OF EXERCISE FOR A FIVE-POUND MOVEMENT"

If there is one true misconception in exercise, it is the belief that more is more. An attitude such as "This feels like it's really working—let's do a few more sets" is pointless. It's like doubling up on your medication to get better faster. You end up doing more harm than good because you are exhausting your muscles. In a sense, the Pilates method is to exercise what interval training became to aerobics: a more comprehensive way to work your body within the limits of muscular endurance.

The concept of working all the muscles simultaneously but continually switching movements is the most efficient way to build stamina. Because all the muscles of the body are being used simultaneously, and during each and every exercise, there is no need to try to load up on one area.

QUALITY VERSUS QUANTITY

Just because it's not burning doesn't mean it's not working! If I had a nickel for every time I've had to prove that exercise can work without pain, I'd be a very rich woman.

I know that quite a number of exercisers have grown accustomed to the soreness associated with working out and find it rather addictive, but such soreness is not an indication that the workout is actually efficient. Muscle soreness is a direct result of lactic acid buildup in the muscle, improper stretching, or the tearing of muscle tissue. The energy your body needs to expend to repair damage or counteract fatigue is precisely what takes away from the efficiency of the workout.

Pilates was designed to work directly with the deepest muscles in the body, creating a strong core without the pain associated with conventional exercises. And because you stretch your muscles as you strengthen them throughout the sequence of a Pilates workout, there is no fear of being improperly warmed up. There is no ripping of muscle tissue, jarring impact on your joints, or exhaustion of your muscles beyond effectiveness. Each movement has a prescribed maximum number of repetitions. The reason for this is, assuming you are doing the exercise correctly, that you are working your muscles so precisely and efficiently that doing any more is completely unnecessary.

Most exercise techniques focus on the superficial muscles in the body and pump them up for effect. This is fine if bulk is your goal; however, thick, stiff muscles are not necessarily an ideal. For example, the hulking muscle of Arnold Schwarzenegger may be considered attractive by some, but sheer mass inhibits a muscle's ability to move freely. In comparison, the lean and lithe muscles of Bruce Lee are testament to the fact that you can heighten a muscle's efficiency by combining grace of movement with strength.

TAKE BACK YOUR POWER BY BELIEVING YOU CAN

The first and biggest hurdle in exercise is combating the mind's self-deprecation. Many people come to my studio and instinctively begin reciting their shortcomings: "I'm weak," "I'm uncoordinated," "I'm lazy." They are looking to me to fix their bodies, but the truth is that becoming dedicated and succeeding in fitness are already within their control. If you have made the effort to get to an exercise studio or to buy and read this book, then there is already something wonderful stirring inside you. Reward your new desire for change with positive thoughts rather than dwelling on the deficiencies that brought you to this point.

Believing in your innate ability to achieve is the key to changing your body. It is as simple and charming as the age-old tale of *The Little Engine That Could*. While the vast majority of Americans have forgotten this concept or think they have outgrown it, I assure you that it still holds true.

I am lucky in that I get to watch small miracles happen every day. I have watched the weary become strong, the stiff become flexible, and those suffering from pain become pain-free. There is only one reason this happens, and it is because they have come to believe that they can. There is nothing that we cannot achieve if we put our minds to it, and this is especially true when we are speaking about our own bodies. We spend the majority of our lives trying to influence external forces over which we have little or no control, when the very thing over which we have complete control is literally beneath our own noses.

The many clients that I train on a daily basis all have one thing in common: my constant positive bombardment. Their success comes when they begin believing the positive feedback themselves. Real strength begins in the mind. Stop giving your power away. There is no one who should care more about your success than you do!

COMMITTING TO PHYSICAL AND MENTAL SELF-IMPROVEMENT

In Pilates, as well as in life, there is nothing that will work for you that you do not *make* work for you. There is no good fairy who will come to you in the night and transform your body for you. The physical and mental commitment you must make to achieve your goal is the most important step in the process of change.

Believing in and following the Pilates philosophy will be the closest you come to making a miraculous change in the way you look and feel. Take the time to understand the essence of each exercise and to enjoy the freedom of movement, and in time you will create the results you are looking for.

BREAKING AWAY FROM THE GYM/TRAINER TRAP

As strange as it may sound coming from a personal trainer, I do my best to promote self-sufficiency when it comes to exercise. The Pilates method is an education in body awareness and is meant to provide you with the necessary tools for taking care of yourself. If your gym closes early or your trainer is not available, it is not an excuse to sit home and do nothing.

Autonomy is a powerful tool against the risk of failure in exercise. For this reason the Pilates matwork is designed with the intent of making you the master of your own fitness destiny. Whether you do five or forty-five minutes a day, committing yourself to your body is the key.


Pilates at 57
Aug 1937

From the archives of The Pilates Studio®

The Matwork Principles

While Pilates draws from many diverse exercise styles running the gamut from Chinese acrobatics to yoga, there are certain inherent ruling principles that bring all these elements together under the Pilates name:

CONCENTRATION

Concentration is the key element to connecting your mind and body. In order to work your body, you must be present with your mind. It is your mind that wills your body into action. Pay attention to the movements you perform and note how your muscles respond to the attention. When you focus on an area, notice how much more you can feel that area working. That's the power of your mind! Use it!

CONTROL

Joseph Pilates built his method on the idea of muscle control. That meant no sloppy, haphazard movements. This is the primary reason injuries occur in other exercise methods. Imagine gymnasts, acrobats, or dancers performing their skills without control. Disastrous! The movements of the matwork are no different. They must be performed with the utmost control to avoid injury and produce positive results. No Pilates exercise is done just for the sake of getting through it. Each movement serves a function, and control is at the core.

CENTER

Think about the muscles you use to go about your daily tasks. For most people it is the arms and legs that get used the most, but what about our center? We have a large group of muscles in our center—encompassing our abdomen, lower back, hips, and buttocks—that are begging for attention. Pilates called this center the "powerhouse." All energy for the Pilates exercises initiates from the powerhouse and flow outward to the extremities. Physical energy is exerted from your center to coordinate your movements. In this way a strong foundation is built upon which we can rely in daily living.

FLUIDITY

Part of the uniqueness of the Pilates method comes from the fluidity with which the exercises are meant to be performed. There are no static, isolated movements because our bodies do not naturally function that way. Dynamic energy replaces the quick, jerky movements of other techniques. A focus on grace of motion is emphasized over speed, and ultimately the movements should feel as fluid as a long stride or a waltz.

PRECISION

Every movement in the Pilates method has a purpose. Every instruction is vitally important to the success of the whole. To leave out any detail is to forsake the intrinsic value of the exercise. Therefore, choose to focus on doing one precise and perfect movement over many halfhearted ones. Eventually, this precision will become second nature to you, and anything less will be just that.

BREATH

Breathing is the first act of life and the last, and so it is imperative to learn to breathe correctly. In order to achieve his ideal of total fitness, Joseph Pilates designed his method to cleanse the bloodstream through oxygenation. By employing full inhalations and full exhalations, you are expelling stale air and noxious gases from the depths of your lungs and replenishing your body with fresh air to energize and revitalize your system. You will find that proper breathing will help to control your movements both during the exercises and in daily life.

Most books on the Pilates method are content to end with the discussion of the previous six principles, which are indeed the foundation of the exercises. However, there are three additional principles that are crucial to the actualization of your exercise goals. Though they are rarely mentioned in today's fitness world, devoted practitioners of the Pilates method and anyone truly dedicated to the pursuit of the mind-body connection understand that employment of these principles is the difference between simply doing the exercises and experiencing them to their fullest.

IMAGINATION

Our minds work in mysterious ways, and one of those ways is our ability to create a visual framework for our bodies to follow. Our minds act as a switchboard through which we can signal instinctive physical response. We can literally spur our bodies to action through an undercurrent of creative thought. In *The Pilates Body* you will use your mind's eye to enhance your physical movement. I have included both visual and verbal metaphors to reinforce the essence of those movements. Be creative!

INTUITION

Listening to our bodies is something we rarely do. We tend to take the power of our natural intuition for granted. Most of us push our bodies through pain, sickness, and exhaustion, often resulting in discomfort and injury. The Pilates method is based upon the ideal of well-being and is not another mind-numbing, quick-fix solution to fitting into a bikini by summer. Do not force what is not natural. If something hurts, stop! As you will be acting as your own guardian and trainer, it is vital that you trust what feels right and what doesn't. In time you will be able to feel the effectiveness of the exercises as you perform them, in turn creating the results you are looking for.

INTEGRATION

Integration is the ability to see your body as a comprehensive whole. Each exercise in the matwork employs every muscle from your fingertips to your toes. In the Pilates method you will never isolate certain muscles and neglect others. The very idea of isolation creates an unbalanced body that impedes flexibility, coordination, and balance. Uniformly developed muscles are the key to good posture, suppleness, and natural grace. Through integration you will learn to use every muscle simultaneously to achieve your goal. Your mind is the coach and the muscles of your body are your team. No one sits on the bench!

Key Elements to Mastering the Mat

In order to gain the most from your mat workouts, it is important to understand the key elements that are in play. There are many concepts within the whole that may require a variation of what you have been taught in the past.

Remember that opening your mind to new information is the first step toward achieving your goals.



Figure 1

1. REDEFINING THE BODY

Classically we have thought of the body as two arms, two legs, a torso, and a head. In the matwork the key to understanding the movements comes from imagining the body in its simplest form: the torso. The torso (see Fig. 1) encompasses the space starting from just beneath the skull and continuing down to the bottom of the buttocks. It contains the vertebral column (spine) and all the major organs. The "powerhouse," from where the exercises initiate, is also contained within the torso. By visualizing the body in this form, it is easier to understand the essence of the exercises. Your arms and legs will certainly be working; however, it is important not to focus on the extraneous parts of the body as much as the muscles radiating from the body's core, or powerhouse.

2. YOUR POWERHOUSE

All Pilates exercises initiate from the muscles of the abdominals, lower back, hips, and buttocks (see Fig. 2). The band of muscles that circles the body just under your belt line is termed the "powerhouse." If you think about how you sit and stand, you will probably find that you sink most of your weight into these areas. This not only causes undue stress on the muscles of the lower back, resulting in soreness and promoting poor posture, but also helps create the "gut" and "love handles" that we all strive so hard to combat.

When performing the mat exercises, remember that you should be constantly working from the powerhouse and lifting up and out of this region. Imagine stretching your upper body away from your hips as if you were being cinched in a corset. This action of pulling up and in simultaneously will automatically engage your powerhouse muscles and help protect your lower back.



Figure 2

3. "SCOOPING YOUR BELLY," OR NAVEL TO SPINE

In many exercise methods we are taught to bear down on the abdominal muscles, pushing them outward into a little hill of sorts. The action of this technique builds the muscles outward and tends to push them away from the spinal column. The result of training your muscles in this way is either to develop a slight sway in the lower back that makes it truly difficult to support the lower lumbar region of the back, or to develop a thick middle whereby your back is supported by the mass of contracted muscles that makes having a waistline virtually impossible. When learning the matwork a very different technique is emphasized. You will learn to "scoop" your belly, or press your navel to your spine, thereby using the abdominal muscles to reinforce the paraspinals (muscles that run alongside your spine). This action not only strengthens and stretches the muscles of the lower back considerably but also allows for the creation of a flat abdominal wall. Pressing the navel to the spine is very often confused with sucking in the stomach, but this is not the case at all. By sucking in your stomach you automatically hold your breath, the very antithesis of the desired effect. Instead think of a weight pressing your belly down to your spine, or an anchor attached to your belly button from the inside and pulling it down through the floor (see Fig. 3). Learn



Figure 3

to maintain this feeling while breathing normally, that is, taking in and expelling air from the lungs and not from the belly, as taught in many other techniques.

4. TUCKING UNDER VERSUS LENGTHENING

In Pilates it is key to keep lengthening your muscles as you strengthen them, therefore, any movement that instructs you to "squeeze your buttocks tightly" is not meant to cause you to tuck your bottom under or contract your muscles so strenuously that your bottom curls up off the mat. Ideally, your pelvis and the base of your spine should stay pressed against the mat or be held firmly in position by the surrounding muscles of the powerhouse.

If you are new to Pilates, it may seem difficult for you to begin some of the movements without a slight tuck, and that's okay. Just be aware that your goal is to gain strength and control to be able to lengthen in opposition to your pelvis; in other words, stretch away from it, and keep it stabilized throughout the exercise movements.

5. INTEGRATED ISOLATION

One very important and unique element of the matwork is learning to rethink the point of focus when you perform the movements. It is commonly thought that the areas of the body that are in motion during an exercise are the areas on which the mind should be focused; this is known as "isolating" a particular group of muscles. The problem with this ideology is that it ignores the other areas of the body that are not in motion, creating an unbalanced body. When performing the matwork, however, it is important that every muscle of the body be working simultaneously, since that is the natural inclination of the body and also maintains the body's sense of balance. In order to achieve this goal during the matwork, it is most effective to think of focusing on stabilizing, or anchoring, the area of the body that is *not* in motion. For example, in the Roll-Up (see Fig. 4), by focusing your mind on stabilizing your lower body while your upper body is in motion, the muscles of your entire body are engaged in a symbiotic and highly effective



Figure 4

manner. Generally, when you attempt this exercise focusing only on the lifting and forward motion of the upper body without first anchoring and focusing on the lower body, you create a very sloppy and ineffective exercise that can lead to injury.

6. STABILIZATION USING THE PILATES STANCE

Very often in the movement descriptions you will come across the expression "Squeeze the backs of the upper inner thighs"; this action is used to engage and stabilize the lower body. The "back of the upper inner thighs" is meant to express a slight turnout of the legs initiating from the hip joint. This slight movement disengages the quadriceps (thigh muscles) and engages instead the target areas of the hips, buttocks, and outer and inner thighs. Think of turning your thighs to face away from each other and holding a tennis ball between them (see Fig. 5). Your feet should remain in a small V position with the heels glued together. Your knees should remain "soft," straight but not locked.

In the beginning you might find that it is not easy to turn out at the thigh without also turning out the feet, but it is important that you master this position so that you may correctly perform the exercises. You will also find that during the progression of movement of the exercise the legs will want to turn back inward; this is precisely the point at which focusing on the stabilization of the leg position is most important. Continue squeezing the buttocks and backs of the upper inner thighs together and feel the effort created throughout the entire torso as you do so.



Figure 5

7. MUSCLE CONTROL WITHOUT TENSION

One of the most difficult concepts of the matwork for most people is the idea of engaging and controlling the muscles without tensing. We have become conditioned to tense up, hold our breath, and push to the point of strain in order to achieve our exercise goals. The matwork will serve to dispel those fallacies and retrain you to see the efforts of the movements in a much more natural way.

Think about a dancer as he/she performs; while you know how much strength and effort it takes to perform the complicated dance moves, it often appears effortless and natural. The same principle is at work while performing the mat exercises. While the movements require strength and concentration, there should always be a natural flow and rhythm that serve to relax the muscles without disengaging them from their task. This relaxation needs to begin in the mind and circulate throughout the muscles of the body. Breath is an effective tool for achieving this state. While the breathing should feel natural, inhaling at the beginning of a movement and exhaling throughout its completion, there are times you will find you are holding your breath because the exertion is too great. This defeats the purpose of the exercise. Make sure that (1) you have made the necessary modifications to ensure that you are working at the proper level for your body and, (2) you are not tensing your muscles as you perform the movements. Remember that there is no one testing you. If you begin gradually, mastering the important elements of the movements first, the rest will undoubtedly follow.

Be patient and enjoy the process!

8. MODIFICATIONS FOR THE MOST COMMON PAINS AND INJURIES

No exercise in the Pilates method should cause pain. Ever!

If you find an exercise putting an uncomfortable strain on an area of your body, stop, review the instructions to make sure you are working from the proper muscles, and try again. If you still experience pain, leave that exercise out for now. As your strength and control increase, you will be able to come back to that exercise in time. Remember too that some exercises may not be suited to your individual body. Use your best judgment and listen to your body!

Lower back pain is most often caused by pushing your abdominal muscles away from your back, leaving little support for the muscles of the spine. To combat this habit, focus on pulling the navel to your spine, as if the actual belly button is, in fact, a button that is fastened to your spine. The deeper the stomach "sinks" into your spine, the safer your back will be. When horizontal, imagine a heavy metal plate anchoring your belly to the mat beneath you. When vertical, imagine a rope through your center pulling your belly back.

Knee pain is most often caused by improper foot and leg positioning, or by gripping or overextending the muscles around the knee joint. Try to maintain a "soft" knee while executing the movements and use the muscles of the inner thighs and buttocks to compensate instead. Throughout most of the exercises, and especially while standing, use the Pilates stance to support your weight. (See Figs. 6 and 7.)

Neck pain is most often due to weak muscles or tightening your shoulders to support that weakness. As you perform the movements of the matwork remember to stay lifted using the muscles of your abdominal region and not the neck itself. Always lower your head and rest when you feel you are exerting too much effort from your neck. If needed, you can place a small pillow under your neck for support.

9. LENGTHENING YOUR NECK

It is a common mistake in Pilates to tense up in the shoulders as you perform some of the movements. In order to avoid this bad habit, it is important that you think of lengthening the vertebrae just below the skull by pressing the back of your neck toward the mat when lying flat or pressing out through the crown of your head when sitting, standing, or stretching forward. This adjustment will release the muscles of the neck and shoulders and allow you to focus on your powerhouse instead. Think of bringing your chin closer to your chest to achieve this sensation.



Figure 6



Figure 7

Frequently Asked Questions

WHY THIS FORM OF PILATES?

Over the years Pilates has taken on many different shapes and forms as it has passed from teacher to teacher. Some styles have taken on a genuinely therapeutic approach and are taught in a slower and more deliberate manner. Others have maintained an athletic and more dynamic approach focusing more on movement and rhythm. In its essence Pilates is meant to stretch and strengthen the body in keeping with balance and alignment. Posture, length, and muscle control is at Pilates' core and many different styles of teaching are employed to reach these goals.

There has been much controversy over what can be deemed true Pilates, and in some cases we must agree to disagree. However, Joseph Pilates, in his own books, made it clear that his method was meant to propel us forward to becoming responsible and in control of our bodies and our health. He sought to enlighten, invigorate, and empower us and to that end you must find what works best for you, your lifestyle, and your goals.

Before going into detail about how to use this book to best advantage, I want to address some of the most common questions about the Pilates method.

What is my goal with the matwork?

You are working to re-create your approach to exercise. By using the matwork movements and philosophy, you will create a system that is the most beneficial to your individual body and lifestyle. You are reteaching your body lessons of correct form and movement that will stay with you for a lifetime. Your overall goal is to break bad habits and to connect to and form an alliance



Joseph H. Pilates
founder of Contrology,
at seventy two years of age,
with several of his inventions
for physical rehabilitation.

From the archives of The Pilates Studio®

with your body. For most this means the enjoyment of moving correctly and reaping the benefits of what that brings: better posture, a strong center, suppleness, alacrity, and a feeling of well-being.

Your exercise goal is individual. In the beginning you should aspire simply to master the beginning exercises of the mat (see "Getting Started" on p. 35) by giving your body the chance to perform them regularly. This takes patience and persistence. Don't give up if you can't get all the movements right away. You are working new muscles, and it will take a little time to accustom your body. Even some of the fittest athletes of our time have had difficulty properly performing these movements!

If you are working to advance to the highest matwork level, then your goal is to hone your routine to where you can add new exercises without sacrificing time. This in no way means that you should speed through what you already have learned to get to something new. You want to move with rhythm and dynamic but without surrendering control. Effort and sweat are sure signs that you are accomplishing your goal, but strain and sloppiness are not!

Each and every exercise lends itself to the importance of the whole. Some of the advanced exercises may not be best suited to your particular body. That's okay. Discover what feels best and perfect what you know. Soon you will find that you don't know how you ever lived without it!

Will I be able to do this if I have not been exercising regularly?

As with any exercise program, it is important to check with a physician before beginning. If you are pregnant, injured, or in any way incapacitated, it is imperative that you get the approval of your doctor first.

However, the Pilates matwork is designed to accommodate any level of fitness. Understanding that the Pilates method is a corrective system of exercise in which you will progress in stages is also key.

You must begin slowly, reading about and visualizing the movements. As you will not have the added benefit of a trainer to correct your form, it is important that you become aware of your body before beginning and throughout your progress. Do not push your body past the point of comfortable movement. These exercises are meant to teach you a new way to *connect* to your body, not to conquer it. Therefore, begin with only a few of the movements; the seven modified beginner exercises are meant to teach you the fundamentals that will apply not only to the rest of the program but also to the way you move in general. Learn them well and you will progress in no time.

What kind of a mat should I use and where?

Any mat or pad that is thick or dense enough to support and protect the delicate vertebrae of your spine will do. A thick carpet or long, folded blanket may also do the trick. As some of the exercises involve rolling back or pressing your spine into the mat, you will want to make sure you are not going to work out on a surface hard enough to bruise or injure your vertebrae. A surface that is too soft is not desirable, either, because it inhibits balance.

The beauty of the Pilates matwork is that it can be done anywhere your body can fit at full length. You need no special accoutrements or equipment to master the principles of this well-designed method.

What should I wear?

Workout clothing (leggings, tank tops, and so on) is the most practical and will allow you to see the muscles you are working, but any comfortable clothing will do. No shoes or sneakers are necessary. Don't wear pants with belt loops or anything that may irritate your back while performing the movements of the matwork.

When is the best time to do the matwork?

Doing the exercises is what's important; it matters less when you do them.

Some people prefer to begin their day with the matwork to wake up, and some use it to relieve stress at the end of their day. Some like it before lunch. And some will do little bits throughout their day. The bottom line is to make sure that you are doing at least some of the movements every day. Try to integrate the principles of the method into your daily schedule and you will find that you increase your strength, awareness, and flexibility faster than you thought imaginable.

It is not recommended that you exercise directly after eating, when you are sick, or if you are overtired. As the movements rely upon the utmost concentration in order to be truly effective, it is important to be clearheaded when doing the exercises. Remember that one well-performed movement is more effective and less destructive than twenty sloppy ones.

How many times a week should I do the matwork and for how long?

Joseph Pilates used to recommend committing to the matwork four times a week for fifteen to thirty minutes at a go. This number will change in stages. Some longtime students of the mat can perform the entire advanced sequence in fifteen minutes and not sacrifice the precision of the movements. The most important element of working with the Pilates method is precision and control; therefore, you must use your common sense to determine your own exercise time frame. In the beginning you may prefer to practice for half an hour. You may be strapped for time and do only five minutes. In either case you must be sure to limit the quantity of exercises to match the quality with which you perform them.

HOW TO USE THIS BOOK

The Pilates Body is laid out in stages so that you can achieve the most possible from an at-home program.

Begin with the basic modified mat (see "Getting Started") and practice until you feel confident in your body's ability to take the next step. From there you can begin building your way up in the full program. Do not try to add too many new exercises at once. Remember, it is the quality with which you perform each exercise that counts!

Remember to read all the instructions thoroughly before beginning. Visualize the movements as you read the descriptions, and then use the photos and visual cues as your reference thereafter. There are always things that get missed the first time around, so periodically come back to the instructions as you progress, and reevaluate your form and knowledge. Have a friend help by checking your positions against the instructions in the book. Or try teaching some of the basic exercises to a friend. Both of these are good ways to stay on top of the learning process. Lastly, try to find a certified Pilates instructor to work with in your area. (A list of certified instructors and studios is provided on p.174.)

Along with step-by-step instructions I have included what I call the "Inside Scoop." The Inside Scoop is essentially a list of tips that I have derived from training hundreds of diverse clients. These tips are meant to aid in the efficiency of understanding the movement as well as being a checkpoint to help you avoid common bad habits. The Inside Scoop is the next best thing to having a trainer on hand, so use its information to become your own personal trainer.

The level of each exercise is clearly indicated, both in the text and in the use of different models.

- Follow Caitlin for all beginner exercises.



- Begin adding exercises with Dana as you progress to the intermediate level.

- And follow Julianna as you progress to the advanced exercises.

Add one new exercise at a time. Do not rush your progress.

As an added benefit, in each step-by-step description I have included instructions for transitioning from one exercise to the next to create the sequential element that makes the matwork fluid and rhythmic.

Remember that variations and tips on progressing are included throughout the text, so be sure to go back and read over the instructions when you feel ready to move on.

Please note: The models used in this book have been training in the Pilates method for years. Although their bodies may seem to represent an unrealistic ideal for many, they have worked hard to achieve their fitness goals. Above all else, they were chosen for their skill in exemplifying the movements during the long and arduous days of shooting. I hope in earnest that they do not intimidate but inspire.



From the archives of The Pilates Studio®

Joseph Pilates demonstrates the "Teaser."

The Matwork

- *Getting Started—Modified Beginner Matwork:* These seven exercises should be your introduction to the mat for the first few weeks, or however long you still feel you are working within your range. Just because they are called beginner exercises does not mean they are easy, so don't be so eager to get on to the advanced stuff. Mastering the beginner matwork is the most challenging part of the program, and once you have done this, you will then be ready to add new exercises.
- *The Pilates Mat—Full Program:* All the exercises, beginner through advanced, are charted with step-by-step instructions, tips for performing the exercises, photos of the exercise movements, and creative visuals illustrating the key focal points of each exercise. Remember to listen to your body when adding a new movement. Nothing should ever hurt when performing the exercises. Take your time, use concentration and control, and enjoy the movements.
- *Advanced Extras:* These six exercises are adapted from the exercises most commonly performed on the apparatus. They are for the advanced student who wishes to add new movements to his/her program. They should be performed with the same caution and control as the rest of the matwork. Just because you are advanced does not mean you are above injuring yourself. Remember to work from your powerhouse and listen to your body.
- *The Standing Arm Series:* This series need not be performed in its entirety. Choose from the variety of exercises in this section to create a balanced addition to your mat workout.
- *The Wall (Cooldown):* The Wall is meant as the cooldown section of the program. Its movements, especially Rolling Down the Wall, can be used throughout the day to stretch and relax the muscles of your back, neck, and shoulders.



From the archives of The Pilates Studio®

Joseph Pilates demonstrates the "Double Leg Stretch."

Getting Started:
Modified Beginner Matwork

The goal of the modified beginning section is to introduce your body to the movements of the matwork in a safe and effective way. The focus of these seven exercises is on finding the muscles of your powerhouse—abdominals, buttocks, lower back, and hips—and strengthening them to support you through the more complicated movements to come.

Make sure to stay attentive to what you are feeling as you introduce your body to the movements and as you discover new muscles. The modified beginning seven will be the foundation upon which your knowledge, understanding, and power builds, so make your best effort to stay consistent and aware.

Remember to come back to the beginning seven every so often to redefine your progress and get back to the core of the technique. These seven exercises are also great to use when you travel and need a quick fitness fix.

MODIFIED BEGINNER

THE HUNDRED

Step by Step

1. Lie on your back with your knees bent in toward your chest. Deeply inhale, and as you exhale feel your chest and belly sinking into the mat beneath you.
2. Keep that *feeling of a weight pressing your torso down into the mat* as you bring your head up to look at your belly button. (Make sure you are folding forward from your upper torso and not your neck.)
3. Lift forward until you feel the bottom of your shoulder blades pressing into the mat beneath you.
4. Stretch your arms out beside you, reaching from deep in the pit of your arm, *as if you were trying to touch the wall across the room with your fingertips.*
5. Begin pumping your arms straight up and down *as if you were slapping water.* (Keep your arms straight and pumping just above the mat.)
6. Inhale for five counts and exhale for five counts, reaching ever forward as you breathe.
7. Maintain this position, pumping your arms and breathing, for as close to one hundred counts as you can manage.
8. End by lowering your head and placing the soles of your feet flat on the mat to prepare for the Roll-Up. . . .



The Hundred is a breathing exercise. It is meant to begin circulating your blood to warm up the body in preparation for the exercises to follow.

The Beginning Scoop

GOAL
- To stay lifted in your head and chest region for all one hundred breaths. You should be able to maintain a flat back and "scooped" belly throughout.

FOCUS
- Make sure you are always focused on the weight of your belly as it sinks into your spine.
- Keep your shoulders pressing away from your ears to stretch the neck muscles and increase the abdominal focus.
- Squeezing the buttocks and knees together will provide stability for your lower back.

NO-NOS
- If your neck hurts, put it down. Do not push to the point of strain.
- Do not push your abdominals out or hold your breath as you go.
- Do not let your thighs rest on your chest as you perform the movements.

BEGINNING MODIFICATIONS
- You can place a small pillow or rolled towel under your head to support your neck if it is too difficult to hold lifted.
- Begin with twenty or thirty breaths and gradually increase to one hundred.

BEGINNING PROGRESSIONS
- As you progress, allow the exhalations to get longer and longer in order to improve your cardiovascular capacity.
- Begin trying to straighten your legs to the ceiling at a ninety-degree angle as you continue pumping your arms.



MODIFIED BEGINNER

THE ROLL-UP

Step by Step

1. Lie on your back with your knees together and bent and the soles of your feet planted firmly on the mat. Your arms are long by your sides.
2. Squeezing your knees together and tightening your buttocks, inhale and roll up by bringing your chin to your chest and continuing forward.
3. Exhale as you straighten your legs and stretch forward. Keep your navel pulling back into your spine. This is opposition at work!
4. In order to feel the articulation of your spine, it is helpful to imagine this rhythm: Lift your chin to your chest, lift your chest over your ribs, lift your ribs over your belly, lift your belly over your hips, and imagine trying to lift up out of your hips and over your thighs as you stretch forward.
5. Initiate rolling back down by squeezing your buttocks and slightly tucking your tailbone underneath you as you bend your knees. Pull your navel deeper into your spine.
6. Reverse the sequence of the exercise and exhale as you feel each vertebra pressing into the mat beneath you. Keep squeezing your knees together for stability.
7. When the backs of your shoulders touch the mat, lower your head and bring your arms down by your sides.
8. Repeat this sequence three to five times and finish by lying flat on the mat with your arms long by your sides to prepare for Single Leg Circles. . . .



The Roll-Up works the powerhouse and stretches the hamstrings.

The Beginning Scoop

GOAL

- To engage the muscles of your powerhouse and flow through the movements.

FOCUS

- The key to this exercise is rhythm. Try to feel the fluidity of the sequence.
- Use your breath to help control your movements.
- Remember to squeeze your legs together to keep your lower body still.
- Keep your chin tucked into your chest as you roll up and back down so that you are not pulling from your neck. Think of curling yourself forward, stretching, and then *slowly* uncurling back down to the mat.
- Remember to use the oppositional force of pulling back in your belly as you stretch forward.

NO-NOS

- Do not allow your feet to lift off the mat as you roll up and lower yourself back down.
- Do not use your shoulders to pull you up.
- Do not allow your body to flop forward as you stretch.

BEGINNING MODIFICATIONS

- If you have trouble rolling up, pull yourself up by placing your hands on the underside of the legs. Remember to still squeeze the legs together for support and pull your navel into your spine. (Make sure your feet are not too close to your buttocks or you will not have the range of motion to be able to come up.)
- Squeeze a ball or small pillow between your ankles to help stabilize your lower body throughout.



MODIFIED BEGINNER

SINGLE LEG CIRCLES

Step by Step

1. Lie on your back with your knees bent, the soles of your feet firmly planted, and your arms long by your sides. Feel your entire spine pressing into the mat beneath you.
2. Straighten one leg up to the ceiling at a ninety-degree angle and turn it out slightly in the hip socket. (This will help you to maintain contact between the back of your hip and the mat.)
3. Begin the circle by moving your leg *across your body first,* then circling it down, around, and back up to its starting position. Do not let your leg swing too far outside your hip joint.
4. *Imagine your leg is a heavy lead pole and you are scratching circles into the ceiling with it.*
5. The accent of this movement is on the "upswing." Press your navel deep into your spine to bring your leg back up, but do not lift your buttocks off the mat.
6. Complete three to five repetitions, inhaling as you begin the motion and exhaling as you complete it. Reverse the direction of the leg, making sure you remain stabilized in your hips at all times—that is, try not to let the hips wobble as you circle the leg.
7. Repeat the sequence with your other leg.
8. End by bending both knees, feet flat on the mat, and rolling up to a sitting position. Lift your bottom forward to your heels to prepare for Rolling Like a Ball. . . .



The Single Leg Circles articulate, stretch, and strengthen your leg in the hip joint.

The Beginning Scoop

GOAL

- To remain perfectly still in your upper body and control the circling movement from your powerhouse.

FOCUS

- The accent for this exercise is on the upswing. Try to hold your leg steady at the end of each circle to feel your abdominals at work.
- Press your palms into the mat for added stability.
- You want to feel this exercise working the inner and outer thighs as well as the powerhouse region.
- In order to stop the quadriceps (thigh) muscle from doing all the work, turn your leg out slightly in the hip and think of engaging your buttock to help perform the movement.

NO-NOS

- Make sure that you do not drop the leg so low as to cause your back to arch off the mat.
- Make sure that your knee does not turn inward as you circle the leg. Think of leading with the *inside* of your knee instead.

BEGINNING PROGRESSIONS

- As you progress, you can gradually increase the size of your circles. Make sure to maintain control in the hips throughout.





MODIFIED BEGINNER

ROLLING LIKE A BALL

Step by Step

1. Sit at the front of your mat with your knees bent toward your chest and open slightly.
2. Place a hand under each thigh (not behind your knees) and lift your feet off the mat until you are balancing on your tailbone. Your chin is tucked into your chest, your elbows are wide, and you should feel you have taken on the roundness of a ball.
3. Initiate the rolling by sinking your navel deep into your spine and falling backward, bringing your legs with you. Do not throw your head back to begin the momentum; work instead from deep within your abdominal muscles.
4. Inhale as you roll back and exhale as you come forward, placing emphasis on keeping a uniform distance between your chest and thighs as you go. Keep your elbows extended so that you work from your abdominals and not your shoulders.
5. *Imagine you are in a rocking chair that is about to tip over, and quickly bring yourself back to a balanced position.*
6. Repeat the Rolling Like a Ball five or six times and end by putting the soles of your feet flat on the mat and lifting your bottom back and away from your heels to prepare for the Single Leg Stretch. . . .



Rolling Like a Ball works on your abdominals, improves balance, and acts as a spinal massage.

The Beginning Scoop

GOAL

- To stay completely rounded throughout the rolling movement.

FOCUS

- Momentum is the key here. The more slowly you roll back, the less chance you have of making it back up.
- Try to allow yourself to feel each vertebra as it presses back into the mat, like running up the scale on a xylophone.
- Remember to pull your abdominals in, and to keep your head and neck supported throughout the rolling movement.
- Each time you come forward, "put on the brakes" and balance on your tailbone. (Do not allow your feet to touch the mat.)

NO-NOS

- Do not roll back onto your neck; think of stopping at the bottom of the shoulder blades instead.
- Make sure you do not allow your head to fly back and forth throughout the movement. Keep it securely tucked toward your knees.
- Do not close your eyes as it inhibits balance.

BEGINNING PROGRESSION

- Test your strength by placing a ball (about the size of a basketball) between your scooped belly and thighs and see if you can still perform the sequence.



SINGLE LEG STRETCH

Step by Step

1. Lie on your back with your knees pulled into your chest.
2. Grab hold of one shin with both hands and extend your other leg to the ceiling at as close to a ninety-degree angle as you can manage. If your right leg is bent, place your right hand on your ankle and your left hand on your knee.
3. With your elbows extended, lift your head and neck and reach your chin toward your belly.
4. Exhale and watch as your navel sinks deep into your spine. Hold it there *as if you were anchored to the mat below.*
5. Inhale and switch legs and hand positions. Stretch your extended leg long out of your hip and in line with the center of your body.
6. Repeat three sets of the Single Leg Stretch and then pull both knees into your chest to prepare for the Double Leg Stretch. . . .



The Single Leg Stretch works your powerhouse and stretches your back and legs.

The Beginning Scoop

GOAL

- To stay completely still in your upper body as you perform the movements of the legs.

FOCUS

- Remember to stay lifted from your abdominals and the back of your chest area. Scoop your belly at all times and press your spine *further* into the mat as you switch legs.
- Keep your elbows extended and your shoulders pressing down and away from your ears in order to best utilize your abdominals.
- Keep your extended leg at a height that enables you to maintain a flat back.
- Squeezing the buttocks as you extend your leg will help ensure the integrity of the position.

NO-NOS

- Do not let your shoulders creep up around your ears.
- Do not lift your head from the neck itself. (If your neck gets tired, rest it back down on the mat and then try again to lift correctly.)
- Do not release your abdominal muscles as you switch legs.



MODIFIED BEGINNER

DOUBLE LEG STRETCH

Step by Step

1. Lie on your back with both knees pulled into your chest.
2. Extend your elbows and bring your head and neck up with your chin reaching for your belly.
3. Exhale and watch as your navel sinks deep into your spine.
4. Inhale deeply and stretch your body long, reaching your arms back by your ears and your legs straight up to the ceiling at a ninety-degree angle *as if you were stretching before getting out of bed in the morning.*
5. *Imagine keeping your torso firmly anchored to the mat, as you did in the Single Leg Stretch, and do not allow your head to move from your chest.*
6. As you exhale, draw your knees back into your chest by circling your arms around to meet them.
7. Pull your knees deeply into your chest to increase the emphasis on the exhalation, as if you were squeezing the air out of your lungs.
8. Repeat the sequence five times, remaining still in your torso as you inhale to stretch and exhale to pull.
9. End by pulling both knees into your chest with a deep exhalation and then roll up to sitting to prepare for the Spine Stretch Forward. . . .



The Double Leg Stretch works the powerhouse and stretches the arms and legs.

The Beginning Scoop

G.O.A.L
- To remain perfectly still in your center, chin into chest, throughout the movements.

F.O.C.U.S
- Keep your neck supported by staying completely still in the upper body as you perform the movement. Squeeze your buttocks and inner thighs together tightly as you extend your legs to support your lower back.
- As you inhale and stretch out, make sure your arms are straight and you are reaching in opposition. (Feel as if you are being pulled in two directions with only your abdominals to hold you down on the mat.)

T.I.P
- If you pull your chest up to your knees very deeply as you exhale and keep your elbows extended, you will feel a nice release stretch in the trapezius region (upper back and neck area). This is generally a very tense spot on most people, so enjoy the release as you exhale.

N.O.-N.O
- Do not let your head fall back as you stretch your arms above your head.



MODIFIED BEGINNER

SPINE STRETCH FORWARD

Step by Step

1. Sit up tall with your legs extended on the mat in front of you and open to slightly wider than your hips' width. Bend your knees slightly to release your hamstrings.
2. Straighten your arms out in front of you at shoulder height and flex your feet. Inhale and sit even taller.
3. Bring your chin to your chest and begin rolling down, pressing your navel deep into your spine as you round. *Imagine you are forming the letter* C *with your body.*
4. Exhale as you stretch your upper body forward, resisting the stretch by pulling back with your abdominals. This is opposition at work again. Your hips should remain still at all times.
5. Inhale as you reverse the motion of the exercise, *rolling up as if constrained by a wall behind you.*
6. Exhale, returning to your tall seated position. Press your shoulders down, and *stretch your back flat up against the imagined wall behind you.*
7. Repeat three times with the goal of increasing the stretch down the spine with each repetition.

Practice these seven modified exercises until you feel ready to move on to the basic exercises of the full mat program. . . .



The Spine Stretch Forward works the deep abdominals, articulates the spine, and enhances good posture.

The Beginning Scoop

GOAL

- To keep your hips stable as you stretch your spine.

FOCUS

- Breathing is the key to a good stretch, so do not hold your breath, as this creates more tension in your body and limits your progress.
- Press your shoulders down and away from your ears as you roll yourself back up to release the muscles in the back of your neck. (The crown of your head should be stretching toward the ceiling.)
- As you stretch up to a tall seated position make sure you are initiating from your powerhouse and not lifting your head to come up. (Your head should be the last part up.)

NO-NOS

- Do not let your knees roll inward as you stretch forward. Think of pulling your baby toes back toward you as you stretch.
- Do not flop forward as you stretch. Think of reaching in opposition instead.
- Roll not back but up as you sit tall.

BEGINNING PROGRESSION

- As you progress, try to increase the stretch in your hamstrings by straightening one leg and then the other as you exhale forward.



The Pilates Mat:
Full Program

THE EXERCISE SEQUENCE OF THE MAT

Remember that these exercises were developed as a sequence to create a flow of movement. Study this chart and try to visualize the transitions from one exercise to the next.



THE HUNDRED



THE ROLL-UP



THE ROLLOVER



LEG CIRCLES



ROLLING LIKE A BALL



SINGLE LEG STRETCH



DOUBLE LEG STRETCH



SINGLE STRAIGHT LEG STRETCH



DOUBLE STRAIGHT LEG STRETCH



CRISSCROSS



SPINE STRETCH FORWARD



OPEN-LEG ROCKER

THE CORKSCREW



13

THE SAW



14

SWAN DIVE



15

SINGLE LEG KICKS



16

DOUBLE LEG KICKS



17

NECK PULL



18

THE SCISSORS



19

THE BICYCLE



20

SHOULDER BRIDGE



21

SPINE TWIST



22

THE JACKKNIFE



23

SIDE KICKS



24

TEASERS



25

HIP CIRCLES



26

SWIMMING



27

THE LEG PULL-DOWN



28

LEG PULL-UP



29

KNEELING SIDE KICKS



30

MERMAID/SIDE BENDS



31

THE BOOMERANG



32

THE SEAL



33

PUSH-UPS



34

BEGINNER

THE HUNDRED

Step by Step

1. Lie on your back and pull your knees into your chest. Inhale deeply, and as you exhale sink your chest and belly into the mat beneath you.
2. Keep that *feeling of a weight pressing your torso down* as you bring your head up to look at your belly. (Make sure you are folding forward from your upper back and not your neck.)
3. Stretch your arms long by your sides and reach forward until you feel the bottom of your shoulder blades sinking into the mat beneath you.
4. Straighten your legs to the ceiling, squeezing the buttocks and backs of the upper inner thighs together until no light comes through them.
5. *Begin pumping your arms straight up and down as if you were slapping water.* (Keep the movement slightly above the mat and your arms straight.)
6. Inhale for five counts and exhale for five counts, reaching ever forward as you breathe.
7. Lower your legs to a forty-five-degree angle, or to the point just before your spine arches off the mat.
8. Maintain this position, pumping your arms and breathing for one hundred counts.
9. End by lowering your head and bringing your knees back into your chest before stretching yourself out to full length to prepare for the Roll-Up. . . .





The Hundred is a breathing exercise meant to circulate your blood to warm up the body in preparation for the exercises to follow.



The Inside Scoop

GOAL

- The goal of the Hundred is to be able to maintain a steady, flat back with your feet held at eye level. This is no easy task in the beginning, so do not push yourself to the point of strain.

KEYS

- Make sure you are always focused on the weight of your belly as it sinks into your spine.
- Keep your shoulders pressing away from your ears to stretch the neck muscles and increase the abdominal focus.
- Squeezing the buttocks and backs of the upper inner thighs will provide stability for your lower back.

NO-NO

- Never drop your legs past the point of comfort for your back. You should be able to maintain a flat back and scooped belly throughout.

MODIFICATIONS

- If your lower back begins to hurt, simply bend your knees in toward your chest.
- If your neck hurts, rest it back down on the mat and then try again, making sure you are lifting from the area around the back of your chest and not from the neck itself.

PROGRESSION

- As you progress, allow your exhalations to get longer and longer in order to improve your cardiovascular capacity.





BEGINNER

THE ROLL-UP

Step by Step

1. Stretch out to your body's full length, *the way you might stretch your waking body as you get up in the morning.*
2. Squeeze your buttocks tightly and press the backs of your upper inner thighs together.
3. Flex your feet into the Pilates stance and bring your straight arms forward over your head.
4. As your arms pass over your chest, lift your head and inhale as you begin to roll up and forward.
5. *Imagine that your lower body is strapped down to the mat, stabilizing you just below the hip bones.*
6. In order to feel the articulation of your spine it is helpful to imagine this rhythm: Lift your chin to your chest, lift your chest up over your ribs, lift your ribs up over your belly, lift your belly up over your hips, and try to lift up out of your hips and over your thighs.
7. Exhale as you stretch forward from your hips while keeping your navel pulled back into your spine. This is opposition at work!
8. Initiate rolling back down by squeezing your buttocks and slightly tucking your tailbone underneath you. Inhale as you begin pulling your navel to your spine.
9. Reversing the sequence of the exercise, exhale as you feel each vertebra pressing into the mat beneath you. Keep squeezing the backs of your upper inner thighs together for stability.
10. When the backs of your shoulders touch the mat, lower your head and bring your arms over into a full-body stretch before beginning the movement again.
11. Complete three to five repetitions and end by lying flat on the mat with your arms long by your sides for the Rollover. . . .

NOTE: If you are a beginner, go on to the Single Leg Circles. . . .

①





②

The Roll-Up stretches and strengthens the spine by articulating the vertebrae.



The Inside Scoop

GOAL

- To remain perfectly still in your lower body as you articulate your spine.

KEYS

- Try to feel the fluidity of the movement as you go.
- Use the oppositional forces of pulling back in your belly as you stretch forward so you do not flop.
- Remember to squeeze the backs of your upper inner thighs together to keep the lower body still. *Imagine you are gripping a small ball tightly between your ankles or the backs of your inner thighs.*
- Keep your chin tucked into your chest as you roll forward and back so that you are not pulling from your neck. Think of curling yourself forward, stretching, and then slowly uncurling back onto the mat, lengthening your spine as you go.

NO-NOS

- Do not roll up using your neck and shoulders. Use the muscles of your powerhouse.
- Do not allow your body to flop forward as you stretch.
- Do not allow your legs to lift off the mat as you roll up.

③



④



ADVANCED

THE ROLLOVER

Step by Step

1. Lie on the mat and extend your arms long by your sides for stability.
2. Initiate the Rollover by squeezing the buttocks and inhaling as you lift your legs off the mat and up over your head. Remember to lift from the back of your hips and control the movement with your powerhouse.
3. Roll over until your legs are parallel with the ceiling and mat. Do not roll onto the back of your neck. Balance on the back of the shoulders instead.
4. Open your legs to hip width and exhale as you roll your spine back down onto the mat, feeling each vertebra pressing into the mat as you go.
5. Control this movement by *imagining that your arms are lead bars pinning you to the mat.* Press weight into your palms to provide a frame in which you can align your body.
6. As you roll down, feel your spine stretching longer and longer by keeping your legs straight and slightly turned out.
7. When your tailbone has touched down, continue lowering the legs to the point just before your lower back arches off the mat. Squeeze your legs together again and repeat the Rollover sequence.
8. Complete three to five repetitions with the legs closed on the way over and open on the way down, and then reverse the leg position, completing three to five repetitions with the legs open on the way over and squeezing together on the way down.
9. Finish the Rollover by lying down with your arms long by your sides for the Single Leg Circles. . . .

①



②



The Rollover stretches and articulates the spine by use of the powerhouse.



The Inside Scoop

If you have a bad neck or lower back, leave this exercise out.

GOAL

- To keep your upper body glued to the mat as you perform the Rollover movements.

KEYS

- Make sure you are suitably warmed up for this exercise.
- Fluidity! Use your powerhouse to keep the momentum steady throughout.
- Make sure you are lifting from the back of your hips and not simply allowing the weight of your legs to pull you over.
- Stabilize your torso by pressing weight into your palms and sliding them forward as you go.
- Keep a slight turnout at the hip and thigh to further increase your control.

NO-NOS

- Never roll onto the back of your neck.
- If you cannot roll over without dropping your feet to the floor or bending your knees, you should not be doing this exercise yet.

MODIFICATION

- In the beginning you may "soften" your knees if the stretch in the back of your legs proves to be too much. (But don't make a habit of this!)

PROGRESSIONS

- For an additional stretch, place your toes on the mat overhead and press back into your heels.
- On the last Rollover you can bring your hands around overhead and grab your feet.

④



③



SINGLE LEG CIRCLES

Step by Step

1. It helps to begin this exercise with a stretch by pulling one knee into your chest, then straightening it to the ceiling while holding your ankle or calf.
2. Bring your arms back down by your sides and leave your leg reaching straight up to the ceiling at as close to a ninety-degree angle as you can manage. Lengthen the back of your neck by pressing it to the mat.
3. Your opposite leg should be centered and reaching long in front of you for stability.
4. Stretch your leg across your body, then circle it down, around, and back up to its starting position. Keep your leg slightly turned out at your hip so that the back of your hip maintains contact with the mat. Do not allow your leg to swing too far to the outside of the hip joint.
5. *Imagine drawing circles on the ceiling with your leg.*
6. Complete three to five repetitions inhaling as you begin the motion and exhaling as you complete it. Then reverse the direction of your leg and complete three to five repetitions, making sure you remain stabilized in your hips at all times.
7. Repeat the stretch and circles with the other leg.
8. End the Single Leg Circles by bending both knees and rolling up to a sitting position. Lift your bottom forward to your heels to prepare for Rolling Like a Ball. . . .



The Single Leg Circles articulate and strengthen the leg in the hip joint, and stretch the iliotibial band (muscle running along the outer part of the thigh).



The Inside Scoop

GOAL

- To remain completely still in your hips and torso as you circle your leg.

KEYS

- The accent for this exercise is on the upswing, where you must utilize your powerhouse to control the movement. Try to hold your leg steady at the end of each circle to feel your abdominals at work.
- Press your palms into the mat for added stability.
- In order to stop the quadriceps from doing all the work, turn your leg out slightly in the hip and think of engaging your buttock to help perform the movement. (If your hip clicks or pops, readjust your leg position and remember to squeeze your buttocks.)

NO-NOS

- Make sure that your knee does not turn inward as you circle the leg. Think of leading with the *inside* of your knee instead.
- Make sure that you do not drop your leg so low as to cause your back to arch off the mat. (If necessary, bend your opposite knee slightly to maintain a flat back.)
- Do not tilt your head back or lift the back of your chest off the mat.

PROGRESSION

- As you progress, you can gradually increase the size of your circles. Make sure to maintain control in the hips throughout!







BEGINNER

ROLLING LIKE A BALL

Step by Step

1. Sit toward the front of your mat with your knees bent into your chest and grab your ankles. Keep your heels glued together and your elbows extended.
2. Open your knees slightly and lift your feet off the mat until you are balancing on your tailbone. Your chin is tucked into your chest and you should feel *you have taken on the roundness of a ball.*
3. Initiate the rolling by sinking your navel deep into your spine and falling backward, bringing your knees with you. Do not throw your head back to begin the movement.
4. Inhale as you roll back and exhale as you come forward, placing emphasis on pulling your heels in tightly to your buttocks as you come up.
5. *Imagine you are in a rocking chair that is about to tip over, and quickly bring yourself back up.*
6. Each time you come forward, "put on the brakes" and balance on your tailbone. Do not allow your feet to touch the mat.
7. Repeat the Rolling Like a Ball five or six times and prepare for the Stomach Series by sitting back on your mat and pulling one knee into your chest. . . .





Rolling Like a Ball is an abdominal exercise that improves balance and massages the spine.



The Inside Scoop

GOAL

- To stay as tightly tucked as possible throughout the entire movement.

KEYS

- Momentum is the key here. (The more slowly you roll back, the less chance you have of making it back up!)
- Try to feel each vertebra as it presses back into the mat, *like running up the scale of a xylophone.*
- Remember to pull your abdominals in and keep your head and neck supported throughout the rolling movement.
- Keep your elbows extended.

NO-NOS

- Do not allow your head to fly back and forth throughout the movement. Keep it securely tucked into your knees.
- Do not roll back onto your neck; think of stopping at the bottom of the shoulder blades instead.
- Do not allow your shoulders to creep up around your ears.

PROGRESSION

- For an added challenge, try placing your head between your knees and wrapping your arms around your legs instead of holding at the ankles.

As you progress be sure that your heels stay glued to your bottom throughout the rolling movement.



BEGINNER

SINGLE LEG STRETCH

Step by Step

1. Sit in the center of your mat with your knees bent. Take hold of your right leg and pull it into your chest with your inside hand on the knee and your outside hand on the ankle. (This will keep your leg in proper alignment with your hip.)
2. Roll your back down to the mat, bringing your bent leg with you.
3. Extend your opposite leg out in front of you and hold it above the mat at an angle that allows your back to remain flat on the mat.
4. With your elbows extended and your chin lifted onto your chest, inhale and watch as your navel sinks deep into your spine.
5. *Imagine you are anchored into the floor below.*
6. Exhale and switch legs, bringing the outside hand to the ankle and the inside hand to the knee. Stretch your extended leg long out of your hip and in line with the center of your body.
7. Repeat five to ten sets of the Single Leg Stretch and then pull both knees into your chest and go on to the Double Leg Stretch. . . .





This is the first of five exercises termed the "Stomach Series." They are meant to flow from one to the next without changing the initial body position.



The Inside Scoop

GOAL

- To stay lifted and perfectly still in your torso as you perform the sequence.

KEYS

- Stay lifting forward from the abdominals and the back of your chest. (Keep your eyes on your belly.)
- Scoop your belly in at all times and press your spine *further* into the mat as you switch legs.
- Keep your elbows extended and your shoulders pressing down and away from your ears in order to best utilize your abdominals.
- Squeezing the buttocks as you extend your leg will help ensure the integrity of your leg position.

NO-NOS

- Do not lift forward from the neck itself.
- Make sure you are not lowering your extended leg below hip level. Keep it at a height that enables you to maintain a flat back.

MODIFICATIONS

- If you have a bad knee, hold the underside of the thigh instead of the top of the knee.
- For a bad back, extend the straight leg to the ceiling only. As your lower abdominal strength improves, you will be able to begin lowering it to a more challenging angle.



DOUBLE LEG STRETCH

Step by Step

1. Lie on your back and pull both knees into your chest, elbows extended and head lifted.
2. Inhale deeply and stretch your body long, reaching your arms back by your ears and with your legs long out in front of you and raised off the mat at about a forty-five-degree angle, *as if you were stretching before getting out of bed in the morning.*
3. *Imagine your torso firmly anchored to the mat,* as you did in the Single Leg Stretch, and do not allow your head to move off your chest.
4. As you exhale, draw your knees back into your chest by circling your arms around to meet them.
5. Sink your belly further from your knees to increase the emphasis on the exhalation, as if you were compressing air out of your lungs.
6. Repeat the sequence five to ten times, remaining still in your torso as you inhale to stretch and exhale to pull.
7. End by pulling both knees into your chest with a deep exhalation and go on to the Single Straight Leg Stretch. . . .

NOTE: Beginners go to the Spine Stretch Forward. . . .



Second of the Stomach Series. Works the powerhouse and stretches the body.



The Inside Scoop

GOAL

- To remain perfectly still in your torso as you perform the movements.

KEYS

- Support your neck by keeping your chin toward your chest as you stretch long.
- Squeeze your buttocks and upper inner thighs together tightly as you extend your legs to support your lower back.
- As you inhale and stretch out, make sure your arms are straight and feel as if you are being pulled in two directions with only your abdominals to hold you down on the mat.

TIP

- If you press your knees up against your hands and increase the distance between your knees and chest as you exhale, keeping your elbows extended, you will feel a nice release in your upper back and neck area.

NO-NO

- Do not let your head fall back as you stretch your arms above your head.

MODIFICATION

- For a sensitive lower back, straighten your legs to the ceiling instead of to a forty-five-degree angle. As your lower abdominal strength increases, you will be able to begin lowering your legs to a more challenging angle.





INTERMEDIATE

SINGLE STRAIGHT LEG STRETCH

Step by Step

1. Lie on your back and pull both knees into your chest, elbows extended and head lifted.
2. Extend your right leg straight up to the ceiling and grab your ankle with both hands as you stretch your left leg long in front of you, keeping it hovering slightly above the mat.
3. *Imagine anchoring your torso firmly to the mat* and keep your head lifted onto your chest.
4. Exhale and press your spine deeper into the mat beneath you.
5. Inhale and pull your raised leg in toward your head (keeping it straight) with a double bounce.
6. Exhale and quickly switch the straight legs by scissoring them past each other.
7. Grab the ankle of your left leg and repeat the motion, inhaling for one set and then exhaling for one set. *Imagine the rhythm of windshield wipers beating.*
8. Complete five to ten sets and end by bringing both legs together at a ninety-degree angle in the Pilates stance, and place your hands behind your lifted head to prepare for the Double Straight Leg Stretch. . . .





Third of the Stomach Series. Provides for an additional stretch in the back of the legs while still working the abdominal region.



The Inside Scoop

GOAL

- To remain perfectly still in your torso as you stretch and scissor your legs.

KEYS

- Use your sense of rhythm to control the dynamic of this exercise, with small pulses on each stretch.
- Keep your eyes focused on your belly and make sure that it is scooping at all times.

NO-NOS

- Make sure you are not sinking or hunching your shoulders with each beat. Keep lifted from the back of the chest area instead.
- Do not rely on your shoulders to hold the weight of your leg overhead. Use that powerhouse!

BEGINNING

- If this stretch proves too difficult in the beginning, hold lower down on your leg. Try your calf first, and if it is still too difficult, move your hands to the back of your thigh. Do not hold behind your knee.

PROGRESSION

- For a more advanced version, try the exercise with your arms reaching long by your sides. Use control and common sense. If it hurts your neck or lower back, stop.



INTERMEDIATE

DOUBLE STRAIGHT LEG STRETCH

Step by Step

1. Lie on your back with your hands, one on top of the other (*not* interlaced), behind your lifted head.
2. Extend your legs straight to the ceiling in the Pilates stance. Squeeze your inner thighs together until no light comes through them.
3. Anchor your center firmly to the mat and lift your head onto your chest. Remember you are lifting from the back of the shoulders and the abdominal muscles, not from the neck, so do not allow your hands to pull the weight of your head forward.
4. Squeeze your buttocks, for stability in your lower back, and lower your straight legs down toward the mat as you inhale. Stop when you feel your lower back begin to arch off the mat.
5. Squeeze your buttocks tighter and exhale as you raise your straight legs toward the ceiling again. You should feel your chest pressing slightly toward the legs as they return to their upright position.
6. *Imagine your legs are attached to springs above your head and you must stretch the springs on the way down and resist their pull on the way back up.*
7. Repeat five to ten times and end by bringing both knees into the chest to prepare for the Crisscross. . . .





Fourth in the Stomach Series. Targets the powerhouse to the extreme. Upper and lower abdominals help power the stretch up the backs of the legs.



The Inside Scoop

GOAL

- To remain perfectly still in your torso, with a flat back, as you lower your legs to the floor.

KEYS

- Keep your elbows extended and press your shoulders down and away from your ears to stretch the muscles of your neck and further increase the focus on the abdominals.
- To accentuate the control element of this movement, keep a slight turnout in the hip and thigh and squeeze extra tight as you bring the legs back up, pressing your chest toward your thighs as you do.
- Make sure you maintain a scooped belly throughout the movement and press your back into the mat beneath you. Feel as though your belly button is lifting and lowering the legs.

NO-NOS

- Do not allow your back to arch off the mat as you lower your legs.
- Do not allow your legs or feet to pass your belt line. Stop when they are directly perpendicular to the ceiling.

MODIFICATION

- In the beginning, and for as long as it serves you, place your hands in a V position just below your tailbone (palms down). This position will help support your lower back.

PROGRESSION

- For an added challenge, try changing the dynamic of the exercise by switching the accent from the lifting up to the lowering down. (Change the breathing accordingly.)





INTERMEDIATE

CRISSCROSS

Step by Step

1. Lie on your back with your hands behind your lifted head and your knees bent into your chest.
2. Extend your right leg out long and above the mat in front of you and twist your upper body until your right elbow touches the left knee. Inhale as you lift to twist.
3. Make sure you are *lifting from below your shoulder* to reach the knee and not simply twisting from the shoulder socket.
4. Look back to your left elbow to increase the stretch and hold the position as you exhale. Make sure your upper back and shoulders do not touch the mat as you twist and hold the stretch.
5. Switch the position by inhaling and bringing your left elbow to your right knee while extending the opposite leg out in front of you. *Hold* the stretch as you exhale completely.
6. *Imagine your center anchored to the mat so that you don't rock from hip to hip.*
7. Complete five to ten sets and then pull your knees tightly into your chest.
8. Roll up to sitting and straighten your legs out in front of you to prepare for the Spine Stretch Forward. . . .





The last of the Stomach Series, the Crisscross works the external obliques, waistline, and powerhouse.



The Inside Scoop

There are many *ways of cheating during this exercise! Here are the major ones.*

NO-NOS

- Make sure you are lifting and twisting from your waist and not from your neck and shoulders.
- Keep your elbows extended as much as possible throughout the movements and do not allow them to fold in or to touch the mat as you twist.
- Be sure to actually look back to your elbow as you twist so you can work deeper into your obliques (and even strengthen your ocular muscles).
- Do not rush through this exercise. Really feel the twist and hold the position as you exhale completely.
- Do not allow your outstretched leg to drop too low in front of you. Maintain control by squeezing your buttocks.
- Do not rock your body from side to side as you go. The steadier you remain, the more efficiently you are working.



BEGINNER

SPINE STRETCH FORWARD

Step by Step

1. Sit tall with your legs extended straight out on the mat in front of you and open to slightly wider than your hips' width.
2. Straighten your arms out in front of you and flex your feet *as if you were pressing your heels into the wall across the room.*
3. Inhale and sit up even taller as if the crown of your head were pressing up and through the ceiling above.
4. Bring your chin to your chest and begin to round down toward your belly, forcing the air out of your lungs. *Imagine you are forming the letter C with your body.*
5. Exhale as you stretch forward, simultaneously pulling in your abdominals. *Imagine you are stretching over a beach ball held between your legs. Squeeze the imaginary ball with your upper inner thighs* as you lift your chest up over the top.
6. Inhale and reverse the motion of the exercise, *rolling up as if constrained by a wall behind you.*
7. Exhale as you return to your tall seated position, pressing your shoulders down and stretching your arms long in front of you. *Really feel your back stretching flat up against the imagined wall behind you.*
8. Repeat three times with the goal of increasing the stretch down the spine with each repetition. End by sitting tall and bending your knees in toward your chest to prepare for the Open-Leg Rocker. . . .





The Spine Stretch Forward articulates the spine and enhances good posture. It also stretches your hamstrings and empties stale air from your lungs.



The Inside Scoop

GOAL

- To keep your hips stable and your belly pulling back as you round and stretch forward.

KEYS

- As you roll up to sitting make sure you are lifting from your powerhouse and not initiating from your head. (Your head should be the last part up.)
- Press your shoulders down and away from your ears as you roll yourself up to release the muscles in the back of your neck. Keep the crown of your head stretching toward the ceiling.
- Think of pulling your baby toes back toward you as you stretch forward.
- Breathe through the stretch to control the movement.
- Try to feel as if you are creating space between each vertebra as you roll up.

NO-NOS

- Do not let your knees roll inward as you stretch forward.
- Roll not back but *up* as you return to your tall seated position.
- Do not hold your breath, as this creates more tension in your body and limits your progress.

PROGRESSION

- As you progress try to increase the stretch by pulling deeper into your spine with each repetition.





INTERMEDIATE

OPEN-LEG ROCKER

Step by Step

1. Sit toward the front end of your mat with your knees bent in toward your chest. Open your knees to shoulder width and take hold of your ankles.
2. Pull your navel deep into your spine and lean back until you are balancing on your tailbone with your feet off the floor.
3. Straighten both legs toward the ceiling in an open V position and balance. Your arms are straight.
4. To initiate the rocking, inhale, pressing your navel down into your spine, and bring your chin to your chest. Do not initiate the movement by throwing your head back.
5. Roll back just as far as the bottom of your shoulder blades, remaining in your V position, and then exhale to come back up (chin on chest).
6. *Imagine you are sitting in a high-backed rocking chair that is about to tip over, and quickly bring yourself up to a balanced position.*
7. Repeat six times and end by coming up and balancing. Bring your legs together and, leaving them in the air, lay your upper body down onto the mat to prepare for the Corkscrew. . . .







The Open-Leg Rocker massages the spine, stretches your back, works the powerhouse, and is just plain fun!



The Inside Scoop

GOAL

- To be able to hold at your ankles, with straight legs and straight arms, using your powerhouse.

KEYS

- The trick to this exercise is making sure that you are really working from your abdominals and not straining to come up each time. Dynamic is the key.
- Pull in your abdominals to initiate the rocking back, and also to come back up.

NO-NOS

- Do not throw your head back and forth to initiate the movements of this exercise.
- Do not roll onto the back of your neck.

BEGINNING

- Simply try straightening your legs and balancing without rocking. Then try to rock back and up with straight legs, holding behind your calves. (Do not hold behind your knees.)

PROGRESSION

- For an advanced challenge, try placing your hands alongside your ankles (or shins) *without* holding on and rock back and up this way. Do not allow your hands to move from their position. (Remember to initiate from the powerhouse!) Balance at the top of each rocking motion.





INTERMEDIATE

THE CORKSCREW

Step by Step

1. Lie down on the mat with your legs, in the Pilates stance, extended straight up to the ceiling. Arms are long and heavy by your sides.
2. Inhale and sink your navel to your spine as you circle your legs to the left, down, and around, and then exhale as you bring them back up to their starting position. Do not allow your hips to rock off the mat as you circle your legs. *Imagine your torso is strapped to the mat, leaving only your legs free to move.*
3. Reverse the direction of the circle each time, inhaling as you begin and exhaling as you complete the circle. Your back remains flat against the mat at all times.
4. Make sure to squeeze the buttocks and the upper inner thighs together so that there is no light coming through the legs.
5. Complete three to five sets of the Corkscrew and end by bending your knees into your chest to release your lower back.
6. Roll up to a sitting position with your legs extended on the mat and open slightly wider than your hips' width to prepare for the Saw. . . .





The Corkscrew is meant to target the muscles of the powerhouse, stretch your back, and improve balance.



The Inside Scoop

GOAL

- To keep your neck, back, and shoulders perfectly still and relaxed throughout the movements.

BEGINNING

- Keep the circles very small and tuck your hands in a triangle just below your tailbone to maintain a slight tilt in the hips back toward your center. As your strength and control increase, begin making the circles larger.

KEYS

- Focus on your upper back and shoulders remaining pressed into the mat beneath you.
- Press your palms down into the mat by your sides to stabilize the upper body.
- Scoop your navel down into your spine for support.
- Make sure to squeeze up the back of the inner thighs and buttocks to support your lower back.
- *Imagine your legs have fused together into one.*

NO-NOS

- Do not roll back onto your neck.
- Do not allow your back to arch off the mat.

PROGRESSION

- For the advanced version of this exercise, allow your hips to lift off the mat as you bring your legs back up and over your head, *as if you were drawing a big circle around your entire body in each direction using your feet as your guides.*





INTERMEDIATE

THE SAW

Step by Step

1. Sit up as tall as possible, with your legs extended and open slightly wider than your hips' width. Flex your feet and push your heels out from under you.
2. Stretch your arms out to your sides as if you were reaching out to touch both sides of the room at once.
3. Inhale and pull your navel up and into your spine, imagining you are stretching the crown of your head up and through the ceiling above.
4. Twist from your waist to the left. Make sure your opposite hip remains pressing down into the mat beneath you. *Imagine you are sitting in a block of cement and are able to move only from just above your hips.*
5. Bring your head and chest toward your right leg, stretching your left arm forward and just past your baby toe. Allow your pinkie finger to brush by the baby toe as if it were a saw.
6. Continue to stretch your chest to the thigh as you deepen the exhalation. Feel your opposite hip deeply imbedded in the cement and unable to move. Stretch the crown of your head toward the baby toe and lift your back arm in opposition.
7. Inhale and draw your body up, initiating from the navel, into the starting position.
8. Repeat the sequence to the right, exhaling deeply as you stretch your head and chest toward the left leg.
9. Complete four sets and then flip onto your stomach to prepare for the Swan Dive. . . .

①



②



The Saw is a breathing exercise that wrings the stale air from the bottom of your lungs. It works the waistline and stretches the hamstrings.



The Inside Scoop

GOAL

- To keep your hips absolutely still as you stretch past your baby toe, with straight legs and back arm lifted.

KEYS

- Stabilize your hips as you stretch in each direction. Think of pressing your opposite heel forward and sitting on the opposite buttock as you stretch.
- Roll up to a tall seated position and inhale before twisting to the other side. Think of filling your lungs with air and then wringing them out as you twist on the exhalation.
- Once again, initiate coming up from the powerhouse (abdominals and buttocks). Your head should be the last part to come up. (Remember to sit up, not back.)

NO-NOS

- Do not scrunch up in your neck as you reach past your baby toe. Lengthen from the crown of the head instead.
- Do not allow your knees to roll in as you stretch forward.

MODIFICATION

- If this stretch proves too difficult, simply soften the opposite knee, or both knees if necessary. As your flexibility increases, begin keeping both legs absolutely straight throughout.



ADVANCED

SWAN DIVE

Step by Step

PREPARATION

1. Lie on your stomach with your palms pressing into the mat directly beneath your shoulders. Squeeze your legs together tightly and allow the tops of your feet to press into the mat behind you.
2. As you inhale, draw your navel up into your spine and begin straightening your arms. Keep your chest lifting and your neck long. (Do not drop your head back.)
3. Exhale and bend your arms, lowering yourself back down to the mat. Keep squeezing the buttocks and upper inner thighs together to support your lower back.
4. Do this stretch two or three times to warm up your back muscles for the Swan Dive. . . .

NOTE: If you are at an intermediate level, go on to the Single Leg Kicks. . . .

SWAN DIVE

5. On the last stretch upward, with your chest reaching for the ceiling, release your hands and inhale, rocking forward onto your breastbone with your arms extended in front of you, palms up, and your straight legs lifted behind you. *Imagine that you are diving forward to catch a beach ball.*
6. With the same momentum, exhale and rock back, lifting in your chest, and *imagine throwing the ball back over your head.* (Keep arms and legs straight throughout the rocking motion.)
7. Keep rocking back and forth, inhaling forward and exhaling back.
8. Rock for a maximum of five Swan Dives and then sit onto your heels with your forehead on the mat to release your lower back.
9. Hold this rest position for one or two breaths and then lie on your stomach, propped up on your elbows, to go on to the Single Leg Kicks. . . .



①



②

The Swan Dive stretches and strengthens all the muscles of the back, neck, and shoulders.



The Inside Scoop

If you have a bad back leave this exercise out. Make your goal slowly building up to the preparation stretch only.

G.O.A.L

- To maintain a rigid body as you rock with your legs glued together and arms straight.

K.E.Y.S

- Breathing and dynamic are the keys to this exercise. Keep the momentum going and focus on your breath throughout.
- Remember to engage the muscles of your powerhouse throughout the Swan Dive to protect the sensitive muscles that run along the spine. It does not take very much to strain these muscles, and once you do, the ache is hard to overcome. Listen to your body. If it hurts, stop.
- Keep your heels together for the entire Swan Dive. If this proves too difficult, allow them to separate slightly, but do not release the muscles of the buttocks.

N.O.–N.O.

- Do not throw your head back and forth as you go. Lift from your chest and lengthen the back of your neck to secure the weight of your head.



③



④

INTERMEDIATE

SINGLE LEG KICKS

Step by Step

1. Lie on your stomach, propped up on your elbows, with your navel pulled up into your spine and your pubic bone pressing firmly down into the mat.
2. Squeeze your buttocks and the backs of your upper inner thighs together to support your lower back. Make sure that your elbows are *directly* beneath your shoulders and your chest is lifted so that you do not sink into your shoulders and back of the neck.
3. Your hands can be made into fists and positioned directly in front of your elbows. (If fists are uncomfortable, place your palms facedown on the mat.) Think of lifting your upper body away from the mat by pressing away from the elbows.
4. *Imagine you are being suspended from the ceiling from your belly and must continue to press your elbows and pelvic bone into the mat to stay grounded.*
5. Lengthen your spine and kick your left heel into your left buttock with a double beat.
6. Switch and kick the right heel to the right buttock with a double beat. Straighten the opposite leg when it is not kicking. Do not let it touch the mat in between kicks.
7. Remember to stay lifted in the abdominals by pressing up and away from your elbows.
8. Complete five sets and end by sitting back on your heels to release your lower back. Lie onto your stomach with your face to one side and your hands behind your back to prepare for the Double Leg Kicks. . . .



The Single Leg Kicks work your hamstrings, biceps, and triceps while stretching your thighs, knees, and abdominal muscles.



The Inside Scoop

If you have bad knees, leave this exercise out, or simply use the motion of slowly bringing your heel toward your buttock as a stretch over the knee. If you experience pain, stop.

GOAL

- To remain lifted and perfectly still in your torso as you kick your heels into your bottom.

KEYS

- The key to this exercise is maintaining a lifted upper body throughout the kicking movement. This is best achieved by lifting your chest up and away from your elbows while still pressing your pubic bone into the mat.
- Make sure to lengthen from the crown of your head to maintain a long neck and to support the weight of your head.
- Keep your upper thighs and knees glued together as you kick to engage the hamstring and buttock muscles.

NO-NOS

- Do not sink into your shoulders or lower back.
- If your lower back hurts, stop. Sit back on your heels and release your back.



DOUBLE LEG KICKS

Step by Step

1. Lie on your stomach with your face resting on one side. Clasp your hands behind you and place them as high up on your back as is comfortable while still being able to touch the fronts of your shoulders and elbows down to the mat.
2. Squeeze your buttocks and upper inner thighs together and inhale as you kick both heels, *like a fish's tail,* to your bottom three times.
3. As you extend your legs back down to the mat, exhale and stretch your arms back to follow them, bringing your upper back up off the mat in an arched position.
4. Continue to reach your clasped hands long and low behind you, squeezing your shoulder blades together and lengthening your spine. Keep your legs and the tops of your feet pressing down into the mat beneath you as you stretch back.
5. Exhale as you return your upper body to the mat, turning your face to the other side and bringing your hands and heels back to the initial kicking position.
6. *Imagine your hands and feet are connected by a band that is pulled back and forth between them.*
7. Complete three sets of the Double Leg Kicks and then sit back onto your heels to release the lower back. Flip onto your back and lie with your hands behind your head and your legs outstretched on the mat to prepare for the Neck Pull. . . .



The Double Leg Kicks work the back of the legs and buttocks and stretch the shoulders and midback.



The Inside Scoop

If you have a bad back or shoulders, leave this exercise out.

GOAL

- To be able to touch your heels to your buttocks during the kicks. To press your elbows into the mat with your hands high on your back. To keep your legs together and your feet down when stretching your back.

KEYS

- Make sure to keep your arms reaching long and low behind you. Think of trying to get your hands down past your buttocks.
- Keep the tops of your feet pressing into the mat as you stretch back, engaging the muscles of the buttocks and thighs throughout.
- Make sure you are pulling your navel up into your spine throughout to support your lower back.
- If you feel pain in your back, stop! Sit back onto your heels with your arms outstretched and release your upper and lower back.

NO-NOS

- Do not allow your head to sink back into your shoulders. Lengthen the back of your neck by pressing forward and up from the crown of the head, keeping your chest lifted.
- Do not allow your buttocks to lift up as you kick your heels into them.



INTERMEDIATE

NECK PULL

Step by Step

1. Lie on your back with your hands, one on top of the other, behind the base of your head.
2. Extend your legs straight out on the mat and open them to your hips' width. Flex your feet and glue your heels to the mat. Make sure your back is flat and your navel is pressing down into your spine.
3. Inhale and begin rolling up and forward, squeezing your buttocks to initiate the movement. Remember the sequence to rolling up: Lift your chin to your chest, lift your chest up over your ribs, lift your ribs up over your belly, then try to lift your belly up and over your hips. Think of peeling yourself up off the mat and curling forward.
4. *Imagine your legs are strapped to the mat just below your hips.*
5. Exhale as you round your back over your thighs as if taking a bow. Keep your elbows wide and your legs firmly anchored to the mat.
6. Inhale and draw yourself up to a tall seated position *as if pressing up against an imaginary wall behind you*. Remember to lift up and not back.
7. Exhale as you slightly tuck your tailbone underneath you and begin slowly rolling your spine back down to the mat. Try to feel each vertebra stretching down to the mat, as if you were putting a space between each one.
8. Repeat the Neck Pull five times and end by lying on your back with your knees bent in toward your chest to prepare for the Scissors. . . .

NOTE: If you are not advanced, or if you have any sign of a weak back, do not perform the next five exercises. End the Neck Pull instead by lying on your side, and go on to the Side Kick Series (p. 98). . . .



The Neck Pull strengthens your powerhouse, stretches your hamstrings, articulates your spine, and improves posture.



The Inside Scoop

GOAL

- To keep your legs glued to the mat at all times, not letting them slide forward or back.

KEYS

- The key to the Neck Pull is remaining fixed in the lower body as you perform the sequence. *Imagine your feet are two lead weights that cannot be budged. Your legs are the rods that hold them in place.*
- Keep your elbows outstretched throughout the movements.
- Initiate the movements from deep within the abdominals and engage your powerhouse throughout.
- Articulate your spine as you peel yourself off the mat and press each vertebra into the mat on the way down.

NO-NO

- Do not pull forward so hard on your head as to strain the muscles in the back of your neck.

MODIFICATION

- If you are unable to come up with straight legs, bend your knees and use your hands to "walk" up the underside of your thighs. Stretch forward, straightening your legs and placing your hands behind your head. Roll up to a tall seated position and then, bending your knees and replacing your hands on the underside of your thighs, lower yourself back down, pressing each vertebra into the mat as you go.

PROGRESSION

- For an advanced variation, try to keep your upper body more rigid, lengthening as you roll back. Still touch each vertebra down to the mat as you go.





VERY ADVANCED

THE SCISSORS

Step by Step

1. Lie flat on your mat with your legs straight and feet long.
2. Bring your legs straight up to a ninety-degree angle, and continue lifting by pressing your hips and legs up to the ceiling.
3. Place your hands on your back, just above your hips, so that you are stabilized in a lifted position.
4. Pull your navel deep into your spine and squeeze your buttocks tightly to secure your position.
5. Inhale and reach one leg long toward the mat while the other reaches over your head in a splitlike movement.
6. Allow your legs to pulse slightly without wobbling in your base.
7. Switch legs by scissoring them past each other and exhale as your opposite leg now pulses overhead.
8. Complete three sets of Scissors and remain in a lifted position to prepare for the Bicycle. . . .





The Scissors stretch your hip flexors, quads, and hamstrings while building strength in the powerhouse and increasing the flexibility of your spine.



The Inside Scoop

Do not perform the Scissors and the Bicycle if you have a bad neck, shoulder, or wrist.

GOAL

- To remain stable and controlled in your hips while allowing your legs to scissor into alternating straight-legged splits.

KEYS

- Keep lifting in your hips.
- Use your buttocks and abdominals to provide the strength necessary for this movement.
- To increase the stretch, think of reaching your ankles as far away from each other as possible as you pulse.
- Focus on the forward leg reaching away from you so that you do not sink into your neck and shoulders.
- Breathe!

NO-NOS

- Do not allow the weight of your body to rest solely on your neck and/or hands.
- Do not allow your knees to bend as you go. Stretch only as far as is possible with straight legs.



VERY ADVANCED

THE BICYCLE

Step by Step

1. Remain in the lifted position from the Scissors and adjust your hands so you are holding your hips steady.
2. Reach your left leg to the ceiling as you stretch your right leg down toward the mat in front of you.
3. Bend your right knee and draw your heel in toward your bottom.
4. As you bring your right knee in toward your chest, allow your left leg to stretch down toward the mat in front of you.
5. Repeat the sequence with your left leg and then continue "pedaling" for three sets.
6. *Imagine you are trying to keep your feet on the pedals of a big bicycle as you go.*
7. After three sets forward, reverse the pedaling movement and complete three sets in reverse.
8. End by allowing your back to roll down to the mat and place the soles of your feet flat on the floor to prepare for the Shoulder Bridge. . . .

NOTE: For an advanced transition to the Shoulder Bridge, finish the Bicycle by lowering the soles of your feet slowly down to the mat with your back still propped up on your hands. Change your support position by turning your hands to the outside and grasping the undersides of your hip bones.





The Bicycle works the backs of your legs while simultaneously stretching your hips and thighs.



The Inside Scoop

If you have a bad back, neck, wrist, or shoulder, leave this exercise out.

GOALS

- To remain perfectly still and lifted in your hips as you perform the cycling movements.
- The accent is on reaching each leg forward and trying to touch your toe to the floor as you "pedal."

KEYS

- Keep your navel pressed to your spine throughout.
- *Imagine you are glued to your hands.*
- Use your powerhouse to control the movements.

NO-NOS

- Do not sink into your wrists.
- Do not arch your lower back to the point where your belly sticks out.





VERY ADVANCED

SHOULDER BRIDGE

Step by Step

1. If you have not made the advanced transition from The Bicycle then lie on your back with your knees bent, hips' width apart, and the soles of your feet planted firmly on the mat.
2. Squeeze your buttocks up off the mat and raise your hips until you are able to place a hand under the back of each hip. Your elbows are directly under each hand and your fingers face outward. *Imagine you are suspended from the ceiling by a sling around your hips.*
3. Pull your navel deep into your spine and secure the muscles of your powerhouse.
4. Stretch one leg out long in front of you and kick it up to the ceiling, inhaling as you go.
5. Flex your foot at the highest point and, exhaling, lower your leg, stretching it long out of your hip as it goes.
6. Perform three to five kicks and return your foot to its original position on the mat.
7. Repeat the sequence with your other leg and then remove your hands, slowly rolling your back down onto the mat. Pull your knees into your chest to release the muscles of your lower back and then sit tall with your legs outstretched to prepare for the Spine Twist. . . .



The Shoulder Bridge works the powerhouse, the thighs, and the backs of the legs.

The Inside Scoop

If you have a bad back, wrist, knee, or elbow, leave this exercise out.



GOAL
- To remain perfectly still and lifted in your hips as you perform the leg sequence.

KEYS
- Keep your navel pressed to your spine and squeeze your buttocks throughout.
- Kick only to the highest point you can manage without dropping in your back.
- Keep stretching long out of your hips as you lower and lift your leg (without arching or sinking in your back).
- Stay lifted in your hips by pressing into the standing leg to maintain balance and control.
- Keep your leg aligned with your hip throughout the kicking sequence.

NO-NOS
- Do not sink your weight into your hands or neck.
- Do not allow your leg to drop to the mat as you lower it.

PROGRESSION
- You can add a double kick at the top before slowly lowering your leg.



SPINE TWIST

Step by Step

1. Sit up very tall with your arms stretched to either side of the room, and press the crown of your head up to the ceiling.
2. Straighten your legs out in front of you and glue them together in the Pilates stance with your feet flexed and your heels pressing out from under you.
3. Inhale and press your navel up and into your spine, as if you were being cinched at the waist.
4. Exhale and twist your torso to the right, staying perched on top of your hips and squeezing your buttocks and legs together tightly.
5. *Imagine you are a twisting vine growing taller from your roots.*
6. Increase the stretch by lifting up in the chest as you increase the exhalation.
7. Inhale deeply as you return to your starting position. Keep your shoulders pressing down and your arms outstretched.
8. Repeat the movement to the left and try to *imagine you are wringing the air out of your body as you would the water from a wet towel.*
9. Complete three sets and end by lying on your back with your arms by your sides to prepare for the Jackknife. . . .





The Spine Twist is a breathing exercise used to wring the stale air from your lungs as you stretch the muscles of your back.



The Inside Scoop

GOAL

- To "wring" the stale air from your lungs as you twist without allowing your hips or heels to shift position.

KEYS

- Keep your feet flexing, and keep energy pressing out from your heels. Keep your legs straight throughout.
- Use your breath to increase the stretch, and focus as much on sitting tall in between the twists as while twisting.
- To ensure that you are twisting from your waist and not your shoulders, try placing your hands behind your head, one on top of the other, and repeating the movements. Remember to stay lifted in your chest.
- Squeeze your buttocks and upper inner thighs tightly together as you perform the sequence.
- Make sure to fill your lungs back up with new air as you return to center.
- Lengthen your neck and spine by pressing up from the crown of your head.

NO-NOS

- Do not sink into your back as you twist. Lift tall out of your waist and lift your chest as you go.
- Allow your head to follow the natural twist of the spine. Do not force your head to turn past the point of comfort.

VARIATION

- Add a slight pulse to each side to release the air from your lungs or sustain one long exhalation as you go.





THE JACKKNIFE

Step by Step

1. Lie on your back with your arms long and heavy by your sides and your legs straight out on the mat in the Pilates stance.
2. Inhale and press your navel deep down into your spine to initiate the movement of the Jackknife.
3. Squeezing your buttocks and the backs of the upper inner thighs together, lift your legs off the mat and bring them over your head by lifting from the back of the hips and engaging the powerhouse. Stop when you reach the back of your shoulders. Do not roll onto your neck.
4. From this position press the backs of your arms firmly into the mat, squeeze your buttocks tighter, and push your hips upward, raising your straight legs to the ceiling *as if opening a Swiss Army knife and snapping it into place.*
5. Keep your weight resting on the backs of your shoulders, and keep your feet in line with your nose.
6. Slowly begin rolling your spine back down to the mat vertebra by vertebra, exhaling as you go. Try to keep your hips and feet suspended in the air for as long as possible as you roll down, resisting gravity.
7. *Imagine your feet are supported by springs overhead.*
8. When your back is flat, stretch your legs toward the floor and then repeat the sequence. Inhale as you lift your legs and hips up, and exhale as you lower them back down to the mat.
9. Repeat three times and end by bringing your knees into your chest. Stretch yourself out and roll onto your side to prepare for the Side Kick Series. . . .



The Jackknife builds strength in your powerhouse and arms while stretching the muscles of your back, neck, and shoulders.



The Inside Scoop

If you have a bad neck, shoulder, or back, leave this exercise out.

GOAL
- To use the muscles of your powerhouse to keep your feet directly over your nose as you roll down.

KEYS
- Keep pressing your palms and the backs of your arms down into the mat as you lift your hips.
- Sliding your palms forward as you return your back down to the mat will help to stabilize your torso and release the muscles in your neck and shoulders.
- Pull your navel deep into your spine and use your exhalation to press deeper into the mat.
- Keep a slight turnout in your legs throughout the sequence to fully engage your hips and buttocks.

NO-NOS
- Do not roll onto your neck. Rest the weight of your body on the backs of your shoulders instead.
- Do not allow your legs to separate. Keep squeezing up the backs of the upper inner thighs and buttocks to support your lower back.

PROGRESSION
- As you progress you do not need to bring your legs all the way overhead before snapping up into your lifted position. Try to refine the angles of the movements to create a fluid motion of lifting and lowering.





THE SIDE KICK SERIES

1. Front/Back
2. Up/Down
3. Small Circles
4. Side Passé
5. Inner-Thigh Lifts
6. Bicycle
7. Grande Ronde de Jambe
8. Transition: Heel Beats

The body position for the Side Kick Series remains the same throughout each exercise. With the exception of the inner-thigh lifts (p. 108) you should remain in one of the two upper-body positions shown at right. (If your neck or shoulder bothers you in these positions, see the modification.)

BODY POSITION
Step by Step

1. Lie on your side with your elbow, shoulder, midback, and buttocks aligned with the back edge of your mat.
2. Position your legs at a forty-five-degree angle in front of your body. (Adjust this position accordingly in the beginning until you feel you are able to maintain stability in this position. Think shoulder over shoulder, hip over hip.)
3. Keep your weight pressing into the palm of your forward hand and *imagine you are balancing a hot cup of coffee on your shoulder throughout the entire series.* (If you are in the advanced position, *imagine your top elbow is stuck to the ceiling.*)
4. Lengthen the back of your neck by pressing the crown of your head away from your shoulders.
5. Keep your feet in the Pilates stance with a *slight* turnout in the hip and thigh. (This will release your quadriceps and allow you to work from your hips and buttocks more efficiently.)
6. Your foot should be held long and aligned with your hip. (For variation, try pointing or flexing your foot to accentuate the movements. Remember, though, the exercises initiate from your hips and powerhouse, so do not focus too much on your lower leg.)

BODY POSITION
The Inside Scoop

The Side Kick Series works your inner and outer thighs and increases strength and mobility in the hip joint.

GOAL

- The goal of this series is to gradually increase your range of motion, so do not attempt big movements at the expense of control. If you are rocking unsteadily just to achieve big kicks, you will sacrifice the integrity and efficiency of the movements.

KEYS

- The most important part of the Side Kick Series is holding the upper-body position still as you perform the movements.
- Remember to use your powerhouse to stabilize your torso.
- In the beginning it is best to keep your forward hand pressing down into the mat in front of you (see beginner position below).
- Keep your weight pressing onto your bottom hip and make sure you are not rocking back and forth on your hip as you go.
- If your hip pops as you perform some of the movements, readjust your leg position and make sure you are squeezing your buttocks for control.

NO-NO

- Remember not to sink into your shoulders as you perform the series.

MODIFICATION

- If your neck gets tired or hurts during the series, simply lay your head down on your arm. (You can place a rolled-up towel or small pillow between your neck and your bottom arm to maintain the alignment of the spine in this position.)

Beginner



Advanced



INTERMEDIATE

FRONT/BACK

Step by Step

1. Take the Side Kick position (described on p. 98) that best suits your ability.
2. Lift your top leg to hip height and turn it out ever so slightly from the the hip to disengage the thigh.
3. Inhale, pressing your navel deep into your spine.
4. Swing your leg to the front and pulse it twice (like two small kicks) as far forward as it will go without rocking forward in your hips or scrunching in your waist.
5. Exhale as you swing your leg back, reaching for the back corner of the room.
6. *Imagine balancing cups of hot coffee on your shoulder and do not rattle the cups as you go.*
7. Repeat no more than ten times and bring your heels back together to prepare for Up/Down Kicks. . . .





Front/Back Kicks work the back of your hips and buttocks, stretch your hamstrings, and improve balance.



The Inside Scoop

GOAL

- To maintain a long, perfectly stable torso as you swing your leg front and back.

KEYS

- Make sure your legs are long and straight without gripping your muscles.
- Use your powerhouse to stabilize your torso.

NO-NOS

- Do not allow your hips or shoulders to rock back and forth as you go.
- Do not allow your leg to bend completely or you will lose the stability in your hips.
- Do not let your foot or leg drop below the height of your hip as you perform the sequence.

PROGRESSION

- Begin with small kicks front and back and gradually increase your range of motion without wobbling.



UP/DOWN

Step by Step

1. Take the Side Kick position that best suits your ability. Keep your leg slightly turned out to disengage the quadriceps.
2. Inhale and lift your top leg straight up to the ceiling.
3. Exhale as you resist gravity on the way back down, stretching your leg long out of your hip as you go.
4. *Imagine your ankle is attached to a spring overhead* and use your powerhouse to control the movements.
5. Complete five sets and rest your heels together in the Pilates stance to prepare for the Small Circles. . . .





Up/Down Kicks work the hips, buttocks, and outer thighs and stretch your inner thigh muscles.



The Inside Scoop

GOAL
- To remain long and lifted in your torso as you kick your leg up and lengthen it back down.

KEYS
- Your leg will be tempted to roll inward during this movement, so be sure to keep a slight turnout in the hip and thigh throughout.
- Lift your leg only as high as you can manage with it remaining straight.
- Remember to lengthen your leg from the hip on the way back down, as if you are pressing away from your torso.
- *Imagine sliding a penny up the wall with your foot and pressing it into the wall on the way back down.*
- Stay lifted in your upper body by pressing the crown of your head away from your hips.

NO-NO
- Do not sink into your waist or shoulders as you lift your leg to the ceiling.



BEGINNER

SMALL CIRCLES

Step by Step

1. Take the Side Kick position that best suits your ability.
2. Lift your top heel just above your bottom heel and begin circling the leg from the hip in a small but vigorous forward motion.
3. *Imagine you are circling your leg inside a small hoop.*
4. Complete five circles forward and then reverse for five circles. End by resting the heels together in the Pilates stance.





The Small Circles work the back of the hips, the buttocks, and the thighs.



The Inside Scoop

GOAL

- To maintain perfectly still and lifted in your torso as you circle your leg.

KEYS

- Work the circles from the top of the leg and hip joint, keeping your leg straight as you do so.
- Lengthen your leg from the hip *as if pressing a penny into the wall with your foot.*
- Squeeze your buttocks for support.
- Use your powerhouse to maintain stability in your torso so you do not rock back and forth.

NO-NOS

- Do not allow your knee, thigh, or foot to roll inward as you go.
- Do not bend your knee or circle from your lower leg; work from the hip down.



INTERMEDIATE

SIDE PASSÉ

Step by Step

1. Take the Side Kick position that best suits your ability.
2. Lift your top leg straight up to the ceiling. Bend your knee and bring your foot down to the inside of the opposite thigh or just in front of it. Slide your foot down the length of the leg until it is straight, and then lift it up to the ceiling again. Maintain a long leg and foot.
3. Repeat three to five times and then reverse the motion, drawing the foot into the body, lifting it straight to the ceiling, and then resisting gravity as you lower it down to the stationary leg.
4. *Imagine your leg resisting the pull of a spring attached overhead.*
5. Repeat three to five times in each direction. On the last repetition draw the foot in toward the body and place it on the floor just in front of your bottom thigh to prepare for the Inner-Thigh Lifts. . . .

①



②



This exercise is adapted from the spring work usually performed on the apparatus. It works the hips and inner and outer thighs.



The Inside Scoop

GOAL

- To maintain a long and perfectly stable torso as you perform the sequence.

KEYS

- Rhythm! Allow the fluidity and feeling of the movements to enrich the exercise.
- The more still you remain in your torso, the more efficient the exercise will be.
- Stay lengthened in your waistline throughout.
- Reach your leg long out of your hip *as if you were pressing a penny into the wall with your foot.*

NO-NOS

- Do not sink into your shoulder or waist as you straighten your leg to the ceiling.
- Do not allow your knee, thigh, or foot to roll inward as you go.

④



③



INTERMEDIATE

INNER-THIGH LIFTS

Step by Step

1. Lie on your right side with your left foot crossed in front of your right leg, foot flat on the floor, and kneecap facing the ceiling.
2. Rest your head on your arm and with the other hand take hold of your ankle to hold it in place, or press your palm down into the mat in front of you.
3. Extend your straight leg long out of your hip and raise it off the floor, turning your heel slightly toward the ceiling.
4. *Imagine you have a stack of books balanced on the inside of your knee as you go.*
5. Lift and lower your leg without letting it touch the mat. Emphasis is on the lifting.
6. Lower and lift five to ten times and then hold the leg in the lifted position, pulsing it upward for ten small pulses. *Do not drop the books!* You can also try five circles forward and five circles back in this lifted position. End by sliding your bent leg down the other and into the Pilates stance to prepare for the Bicycle. . . .



The Inner-Thigh Lifts work your inner and outer thighs and stretch the back of the hip.



The Inside Scoop

GOAL

- To maintain an actively outstretched body as you perform the lifting movements.

MODIFICATION

- If it is too difficult to keep your upright leg bent in this position, simply rest your knee on the mat in front of you.

KEYS

- Lift as much of your thigh off the mat as you can, maintaining a slight outward rotation of the leg.
- Maintain your long, steady upper body by stretching your outreached arm in opposition to your leg.

NO-NOS

- Do not bend your outstretched leg as you go.
- Do not grip in your quadriceps.



BICYCLE

Step by Step

1. Take the Advanced Side Kick position.
2. Swing your top leg back *as if pushing on the pedal of a very large bicycle,* bending your knee behind you and bringing your heel to your buttock for a stretch in the hip and knee. Bring your bent knee past your outstretched knee and toward your shoulder, not dropping forward in your hips. Extend your leg out in front of you *as if pushing forward on the pedal* and "cycle" by swinging your straight leg back to repeat the motion.
3. *Try to envision the bicycle as being very large and hard to pedal so that you can control the movement and get the most from the stretch.*
4. Pedal forward three times and then reverse the sequence, pedaling backward three times. End by bringing your heels back together into the Pilates stance to prepare for the Grande Ronde de Jambe. . . .



①



②



The Bicycle stretches and strengthens the hips, buttocks, and hamstrings.



The Inside Scoop

GOAL

- To maintain a long, perfectly stable torso as you cycle forward and back.

KEYS

- Stay long in your waistline throughout the movements, especially when holding your leg straight out in front of you.

Cycling Backward (kick forward, bend knee, knee back, straighten leg)

- Press your knee as far back as possible before straightening your leg behind you.
- Lengthen your back as you stretch your leg.

Cycling Forward (leg back, bend knee, knee forward, straighten leg)

- Bring your heel to your buttock *before* bringing your knee forward.

NO-NOS

- Do not allow your knee, thigh, or foot to roll inward as you stretch.
- Do not bring your hip forward as your leg swings to the front.
- Do not drop your leg below hip level.



④



③

ADVANCED

GRANDE RONDE DE JAMBE

Step by Step

1. Take the Advanced Side Kick position.
2. Lift your top leg to hip height, keeping it slightly turned out.
3. Inhale and swing your leg to the front. Slide your foot up the wall in front of you, rotate the leg in your hip socket and reach back to the corner of the wall behind you. (Remember to press your top hip forward and stretch your upper back longer to create a counterbalance for the weight of the leg stretching back.)
4. Swing your leg to the front and repeat the sequence two or three times: swing forward, lift, rotate, and stretch back. *Imagine stirring the inside of a large cauldron.*
5. Reverse the sequence by swinging your leg back and long out of your hip. Lift your foot to the ceiling, rotating your leg outward in the hip socket. Lower your leg and hold it at hip height before repeating the sequence. Swing back, lift, rotate, and slowly lower to hip height. Remember to maintain a long, strong torso for stability as you perform these movements.
6. Repeat two or three times in each direction and end by bringing your heels together in the Pilates stance and rolling onto your stomach to prepare for Transition: Heel Beats. . . .


①


②

The Grande Ronde de Jambe articulates the leg within the hip joint, stretches the hamstrings and hip flexors, and works the powerhouse.



The Inside Scoop

GOAL

- To maintain a long, stable torso as you circle your leg.

KEYS

- Remember to counterbalance the weight of your leg by pressing your top hip in opposition to your foot.
- Keep energy pressing out the crown of your head, and keep pressing your shoulders down away from your ears.

NO-NOS

- Do not sink into your waist or shoulders as you go.
- Do not allow yourself to rock in the hips.



④



③

INTERMEDIATE

Transition: HEEL BEATS

Step by Step

1. Lie on your stomach, squeezing the backs of your legs together, and rest your forehead on the back of your hands (one on top of the other).
2. Squeeze your buttocks tight, inhale, and lift both thighs off the mat behind you, keeping your legs straight and heels together.
3. Hold your legs in the air and beat your heels together lightly.
4. *Imagine your upper body is strapped to the mat, unable to move, and your legs are suspended by springs behind you.*
5. Inhale for five beats and exhale for five beats.
6. End by sitting back onto your heels to release your lower back, and then lie on your other side in the Side Kick position.

   NOTE: For an advanced variation, try bringing your heels into your buttocks and then straightening your legs with your thighs still lifted. Repeat three times. (See variation photo.)

7. Repeat the Side Kick Series exercises with the opposite leg and end by lying on your back with your knees pulled into your chest to prepare for the Teasers. . . .

①



②



The Heel Beats work your powerhouse and the backs of your legs.



The Inside Scoop

GOAL

- To remain perfectly still in your torso with your legs raised and beating, or bending and straightening.

KEYS

- Keep your navel pulled up into your spine to protect your lower back.
- Keep your upper back and shoulders relaxed during the beats. If you need to, reach your arms out long in front of you.
- Squeeze your buttocks tight to protect your lower back and stabilize your torso.
- Keep your legs as straight as possible throughout the beats.
- Keep your knees as lifted as possible throughout the Advanced Variation.

NO-NOS

- Do not beat your heels so vigorously as to bruise them. Work from the whole leg.
- Make sure your thighs are not touching the mat as you go.

Advanced Variation

①



②



TEASER (Preparation I)

Step by Step

1. Lie on your back and place the soles of your feet flat on the mat with your knees and thighs squeezing together. (Your feet should be at a forty-five-degree angle from your knees.)
2. Reach your arms back overhead and stretch your fingertips to the back wall. Maintain a flat back by engaging your powerhouse.
3. Bring your arms forward and allow your head and upper body to begin following them forward and up. *Imagine you are being lifted by a balloon attached to your chest.*
4. Inhaling, roll up to where your abdominals are still engaged and hold yourself there for a count of three.
5. As you exhale, begin rolling your spine back down, pressing each vertebra into the mat as you go.
6. When the back of your head has touched down, begin reaching your arms back over your head and stretch your fingertips to the wall behind you. Maintain a long neck as you do so.
7. Repeat this sequence three times and then go on to Teaser Preparation II. . . .



①



②



This variation is meant to test the strength of your powerhouse before moving on to the full Teasers.



The Inside Scoop

GOAL

- To remain perfectly still in your lower body while rolling up and lowering yourself back down.

KEYS

- Try to focus on lifting up more than forward to keep your powerhouse engaged.
- Keep squeezing your buttocks, inner thighs, and knees together throughout.
- Lengthen as you roll down, keeping your sacrum pressed flat to the mat.

NO-NOS

- Do not allow your feet to move as you roll up.
- Do not rock forward onto your tailbone.

④





③

TEASER (Preparation II)

Step by Step

1. Lie on your back, remaining in the position of the Teaser (Preparation I).
2. Straighten one leg up to a forty-five-degree angle from the floor and glue it to the inside of your opposite knee. Turn out slightly in the hip and thigh and squeeze your buttocks and inner thighs together tightly.
3. Repeat the same sequence as in Preparation I without allowing your knees to come apart as you go.
4. Reach for your outstretched foot, staying lifted in your chest. Lift tall out of your waist as you inhale. *Imagine being pulled up by the force of a magnet.*
5. As you exhale, begin rolling your spine down to the mat and stretch your arms back overhead.

   NOTE: For an abdominal challenge, when you reach the top, exhale and twist your upper body to the right. Inhale and return to center, then exhale and twist to the left. Inhale and return to center. Exhaling, lower yourself slowly back down to the mat.

6. Repeat either variation two or three times with each leg and end by pulling your knees into your chest and releasing your back before going on to the full Teasers. . . .

①



②



This variation works your powerhouse and stabilizes your lower body in preparation for the full Teaser.



The Inside Scoop

GOAL

- To keep your knees glued together and your leg straight throughout the sequence.

KEYS

- Work from the deep muscles of your powerhouse to control the movement.
- The key to getting up to the top is to feel yourself "floating" slowly upward with control.
- Think of lifting from your chest and pressing your shoulders down and away from your ears.
- Remember to articulate your spine as you roll up and down, creating space between each vertebra.

NO-NOS

- Make sure your knees do not come unglued as you perform these movements. (And no cheating by resting one knee on top of the other!)
- Do not allow your shoulders to creep up around your ears as you lift upward. Do not hold your breath or throw your body weight upward.

④



③



INTERMEDIATE

TEASER I

Step by Step

1. Lie on your back with both legs straight to the ceiling and in the Pilates stance.
2. Stretch your arms long overhead while maintaining a flat back.
3. Lower your legs to a forty-five-degree angle from the floor, pressing your navel deeper into your spine.
4. Inhale and bring your arms from over your head to reach toward your toes.
5. Allow your body to "float" up to your feet by bringing your chin to your chest and "peeling" your upper body off the mat.
6. *Imagine you have a spring attached from your ankles to your chest that pulls you up toward your feet.*
7. Hold that V position, balancing on your tailbone, and then exhale as you begin rolling your spine back down to the mat. *Feel the pull of the spring as you descend in opposition.* Squeeze your buttocks tightly to make sure that your legs remain stationary.
8. When your head has touched down on the mat, stretch your arms out long overhead and repeat the sequence, inhaling as you float up and exhaling as you press each vertebra back into the mat beneath you.
9. Repeat the sequence three times and end by sitting up and placing the soles of your feet on the mat to prepare for the Seal. . . . (p. 140)

NOTE: For the advanced level, end in the lifted V position to prepare for Teaser II. . . .



The Teaser I is one of the all-time favorites of the Pilates method. It tests your powerhouse control to the fullest and is a great way to chart your progress.



The Inside Scoop

If your back hurts, stop. Lie back with your knees into your chest to release your lower back.

GOAL

- To remain perfectly still in your lower body as you perform the movements of the Teaser.

KEYS

- The key to the Teaser series is to relax your mind and find your rhythm as you go.
- You must *breathe* during this sequence. If you hold your breath, you will not be using your muscles efficiently.
- Make sure to press your navel down deep into your spine and squeeze your buttocks and backs of the inner thighs to engage your powerhouse.

NO-NOS

- Do not lower your legs past the point of control. If you feel your back beginning to arch off the mat, raise your legs back up toward the ceiling.
- The Teasers consist of very controlled movements. Do not allow yourself to "throw" your body up or drop it back down.

ADVANCED PROGRESSION

- Hold your arms straight to the ceiling, alongside your ears, as you roll down. Try to stretch away from your legs as you go.

③



④



ADVANCED

TEASER II

Step by Step

1. You are in the lifted V position of Teaser I, balancing on your tailbone and pressing your navel deep into your spine.
2. Hold your upper body absolutely still as you lower your legs toward the mat.
3. Lower and lift your legs three times, making sure you are working from your powerhouse by keeping your navel pressed to your spine and squeezing your buttocks and inner thighs together tightly.
4. *Imagine your legs are pointed arrows hinged at your hips or suspended by springs, attached to your ankles, and are supported as you pull down on the springs and resist their pull on the way up.*
5. Inhale as you lower your legs and exhale as you return to your V position.
6. End in the lifted V position to prepare for Teaser III. . . .







The Teaser II improves balance and coordination and works the powerhouse.

The Inside Scoop

If your back hurts, stop. Lie down and pull your knees to your chest to release your lower back.

GOAL
- To maintain a rigid, lifted upper body as you lower and lift your legs with control.

KEYS
- Make sure you are slightly turned out at the hip and thigh, Pilates stance, to engage the muscles of the inner thighs, hips, and buttocks.
- Keep lifted in your chest as if you were suspended from the ceiling. Think of lifting your legs to your chest as you bring them up each time.
- Press your shoulders down and away from your ears to release the neck and shoulder muscles.
- Total control is key, so make your movements slow and deliberate until you have it mastered.

NO-NOS
- Do not allow yourself to rock forward and back on your tailbone.
- Do not allow your back to arch or sink as you lower your legs. Keep squeezing the backs of your legs and do not lower them past the point of control.
- Do not drop your legs.





TEASER III

Step by Step

1. You are in the lifted V position of Teaser II, balancing on your tailbone and pressing your navel deep into your spine.
2. Lift your arms to the ceiling alongside your ears and slowly roll your entire body back down to the mat. Initiate the roll down by pressing your navel deep into your spine and stretch in opposition as you go, reaching your upper back away from your ankles and allowing every vertebra to press down in between. Stretch your fingertips to the wall behind you.
3. Use the combined movements of Teasers I and II to begin folding back up into your V position, lifting the upper body and ankles off the mat simultaneously until your fingers touch your toes.
4. *Imagine resisting the pull of a heavy spring that is attached between your breastbone and your ankles or that you are two distinct arrows hinged at your hips.*
5. Stretch your arms up and back alongside your ears and exhale as you slowly begin stretching the spring back out, reaching your upper back away from your ankles, until you have pressed each vertebra back down into the mat beneath you.
6. Initiate the roll back down by pressing your navel deeper into your spine and squeezing up the back of the inner thighs and buttocks to support your lower back.
7. Repeat three times and end by holding yourself in the lifted V position. Bring your arms behind you and place them, palms down and fingers facing away from you, onto the mat to prepare for Hip Circles. . . .

①



②



The Teaser III is the combination of Teasers I and II and utilizes all the muscles of the body with an accent on the powerhouse.



The Inside Scoop

If your back hurts, stop. Lie down and pull your knees into your chest to release your lower back.

GOAL

- To stretch as long as possible and fold up as fully as possible using the control of your powerhouse.

KEYS

- Make sure that you initiate the movement of Teaser III from your powerhouse.
- Think of folding up around your center by pressing your navel firmly to your spine and squeezing your buttocks to begin.
- Use the sensation of "floating" as you lift your body up into the V position.
- If you have trouble coming up, try reversing the breathing sequence.
- Keep your shoulders pressing down and away from your ears to release the muscles in your neck and shoulders.

NO-NO

- Do not hold your breath or you will impede your progress.



④

③

ADVANCED

HIP CIRCLES

Step by Step

1. Balance on your tailbone with your legs held in the V position of the Teasers, stretch your arms behind you, and place the palms of your hands on the mat behind you.
2. Inhale and move your legs, still held in the Pilates stance, down and around to the right.
3. Exhale and complete the circle, bringing the legs to the left and back up to the starting V position.
4. *Imagine your hands are stuck in cement and you are unable to move your torso except to keep it lifting to the ceiling.*
5. Remember that your upper body is providing the counterbalance as the weight of your legs circles down and around, so you must *press your hands deeper into the cement as your weight shifts.*
6. Switch directions with each circle, inhaling as you begin the circle and exhaling as you complete it. Try to make your legs feel very light as they circle so that you can engage the hip and abdominal muscles and not the muscles of the thigh.
7. Complete three sets of Hip Circles and end by bringing your legs down to the mat and rolling onto your stomach with your arms outstretched in front of you to prepare for Swimming. . . .





The Hip Circles focus on the muscles of the powerhouse and stretch the front of the shoulders, across the chest, and down the arms.



The Inside Scoop

Do not perform this exercise if you have a shoulder injury or a weak back.
If your back hurts, stop. Lie down and pull your knees into your chest to release your lower back.

GOAL

- To maintain a rigid, lifted chest and straight arms as your legs circle.

KEYS

- Think of pressing your chest up and away from the heels of your hands so as not to sink into your neck and back.
- The accent of the circles is on the upswing, so use all the power in your powerhouse to bring your legs back up to the center. Think of trying to bring your straight legs up to your nose.
- Press your shoulders down and away from your ears.
- Maintain a straight back with your ribs pulled in throughout.

NO-NOS

- Do not allow your upper torso to move, or your neck to crane forward.
- Do not drop your legs below your point of control.

MODIFICATION

- Prop yourself up on your elbows if maintaining straight arms is too difficult.





SWIMMING

Step by Step

1. Lie on your stomach, completely outstretched on the mat, with your legs squeezing together behind you in the Pilates stance. Reach your fingertips for the wall in front of you.
2. Inhale, pulling your navel up into your spine as you bring your right arm and your left leg up into the air simultaneously. Hold them there as you lift your head and chest off the mat as well.
3. Switch the arms and legs by lifting your left arm and right leg above the mat.
4. Continue switching pairs until you have a swimming or light splashing motion in effect, inhaling for five counts and exhaling for five counts.
5. *Imagine you are balancing on a rock in the water and need to keep the movements controlled so you don't slip off.*
6. Complete two or three sets of five inhalations/exhalations each, and then sit back on your heels to release your lower back.
7. End by lying on your stomach with your hands placed palms down beneath your shoulders and your legs pressed together to go on to the Leg Pull-Down. . . .





Swimming stretches and strengthens the muscles along your spine.



The Inside Scoop

GOAL

- To maintain a firm, lifted center throughout the swimming motion.

KEYS

- The key to the Swimming movement is to keep control from your center.
- Use your powerhouse to stay lifted, keeping your line of vision *above the surface of the water.*
- Remember to keep squeezing your buttocks together tightly to protect your lower back and to work the backs of your legs.
- Feel that you are stretching in opposition, fingers and toes reaching for the opposing walls of the room.
- Lengthen the back of your neck by pressing energy out of the crown of your head.
- Keep your arms and legs as straight as possible throughout the exercise without allowing them to touch the mat in between lifts.
- Make sure that your chest and thighs are lifted off the mat throughout.

NO-NOS

- Do not allow your limbs to drop as you perform the swimming motion.
- Do not allow your belly to drop or you will immediately feel this in your lower back!
- Do not allow your neck to crane backward.



ADVANCED

THE LEG PULL-DOWN

Step by Step

1. Place your hands, palms down, onto the mat underneath your shoulders and pull your navel up into your spine as you press yourself up into a push-up position.
2. Squeeze up the back of your legs and make sure your body is held in a straight line, as if there were a steel rod from your head to your heel.
3. Shift your body weight backward, pressing your heels toward the mat, then rock forward onto the balls of your feet. *Imagine you are suspended by a cord leading from your belly button to the ceiling.*
4. Do this two or three times to warm up the tendons, then inhale as you lift one leg straight off the mat behind you and hold it there as you exhale and repeat the rocking movement.
5. Switch legs with each breath sequence.
6. Complete three sets and then flip onto your backside to perform the Leg Pull-Up. . . .

①



②



The Leg Pull-Down stretches the Achilles tendon (back of the ankle) and your calves, and stabilizes the powerhouse.



The Inside Scoop

GOAL

- To maintain a rigid center throughout the movement. (The movement is *like that of a battering ram being pulled back and rocked forward.* Think of the crown of your head as the contact point.)

KEYS

- Keep your arms and legs completely straight throughout the movement and think of pushing up and away from the heels of your hands so you do not sink into your wrists.
- Make sure you keep your navel firmly pulled up into your spine.
- Keep your neck long and your head aligned with your spine.

NO-NOS

- Do not allow your head to hang down.
- Do not allow your belly to hang out as gravity will want it to do.
- Do not twist in your hips as you lift your leg.

④



③



ADVANCED

LEG PULL-UP

Step by Step

1. Sit tall with your palms on the mat by your sides.
2. Lift your hips off the mat and firm your center with your legs long and squeezing together.
3. With straight arms and toes pointing to the mat, inhale and kick one leg straight up as high as possible without breaking at the waist.
4. Flex your foot at the height of the kick and exhale as you slowly lower your leg, pressing out of your heel.
5. As your heel nears the mat, point your toe and kick the leg up again, inhaling as you go.
6. *Imagine you are suspended by a sling around your hips that keeps your center lifted and still.*
7. Repeat the motion three times and then repeat with your other leg.
8. End by lowering your buttocks to the mat. Take a kneeling position with your knees aligned with the front edge of your mat and go on to the Kneeling Side Kicks. . . .





The Leg Pull-Up focuses on your powerhouse with emphasis on the buttocks. It also works the arms and shoulders and provides a stretch in the hamstrings.



The Inside Scoop

If you have a bad wrist or shoulder, leave this exercise out.

GOAL

- To maintain a rigid, lifted center throughout the movements.

KEYS

- Make sure your arms remain straight and you are pushing up off the heels of your hands so as not to sink into your wrists and shoulders.
- Keep your hips lifted at all times *as if there were a large, sharp pin beneath your buttocks.*
- Remember to keep your navel pulled firmly into your spine so that your belly does not push outward as you kick.

NO-NOS

- Do not sink into your neck and shoulders.
- Your legs must remain straight at all times during this exercise. Do not bend at the knee or you will not be working from the hip and buttock as intended.

MODIFICATION

- Let your chin rest forward on your chest. As you progress, try to keep your head and neck aligned with your spine.



ADVANCED

KNEELING SIDE KICKS

Step by Step

1. Kneeling on the front edge of your mat, place one palm down on the mat directly under your shoulder and in alignment with your hips, fingers parallel to the mat.
2. Place your other hand behind your head with your elbow to the ceiling.
3. Straighten your top leg out along the mat in line with your body, making sure that your torso is grounded and your center is firm.
4. Lift your outstretched leg up off the mat as close to hip height as you can manage and balance. *Imagine you are suspended from the ceiling by a sling around your waist.*
5. Inhale as you kick your leg to the front wall, making sure you are not breaking in the waist as you go. *Imagine kicking a ball suspended before you.*
6. Exhale and swing your leg back, stretching it as far as you can without rocking in your hips or pushing your belly forward.
7. *Imagine the crown of your head is pressed into a wall and cannot move as you perform the kicking motions.*
8. Complete four sets of kicks on one side and then repeat the sequence balancing on your opposite side.

   NOTE: For an even more advanced challenge, try performing some of the other Side Kick variations from pages 98–115 while balanced in the kneeling position.

9. End by lowering your hip down to the mat and bringing your heels in toward your buttocks. Remain resting on one hand and go on to the Mermaid. . . .



The Kneeling Side Kicks concentrate on the waistline and hips. Emphasis is also on balance and coordination.



The Inside Scoop

If you have a bad knee, leave this exercise out.
The Kneeling Side Kicks are essentially the Side Kicks (pages 98–115) performed balancing on one knee. Use similar images, where helpful, to master the movements.

GOAL

- To remain perfectly still and rigid in your upper body as you perform the kicks.

KEYS

- Keep your elbow to the ceiling so that your shoulder and chest remain open throughout the exercise.
- Keep your navel pulled firmly to your spine and your hips still as you go.
- Keep your head lifted and aligned with your spine.

NO-NOS

- Do not sink into your neck or shoulders.

PROGRESSION

- Start with small kicks front and back and concentrate instead on your balance and control before engaging in big movements. Once you are able to remain still in your torso as you kick your leg, begin making the kicks stronger to challenge yourself.



ADVANCED

MERMAID/SIDE BENDS

Step by Step

1. Sit on one side with your knees slightly bent and together, your top foot on the mat just in front of the other.
2. Place your hand, palm down and parallel to the mat, directly beneath your shoulder. Allow your top hand to rest on your shin.
3. Press up onto a straight arm and bring your upper foot to rest on top of the other. You should be balanced on your hand and the side of your foot with your body lifted and straight, aligned from head to toe. *Imagine you are suspended at your hips by a sling attached to the ceiling.*
4. Turn your head toward the ceiling and try to bring your chin down to your top shoulder. Stretching your arm and fingertips down toward your feet, exhale slowly and allow for a slight dip in your hips. You should feel a stretch up the underside of your body.
5. Inhale deeply and lift your arm up and straight overhead alongside your ear, reaching as far away from your feet as possible. Allow for a lift in your hips and return your head to a position in line with your spine. You should now feel a stretch along the top side of your body.
6. Repeat the movements three times and then lower your hip to the mat, take hold of your ankles with your top hand, and bring your supporting arm overhead, bending toward your legs to stretch your side in a mermaid pose. Switch to the other side.
7. End by lowering your hips to the mat and then sitting tall with your legs extended out in front of you and your palms resting on the mat by your sides to prepare for the Boomerang. . . .





The Mermaid concentrates on the muscles of the arms, shoulders, and wrists. It also stretches the hips and waistline and helps to develop balance.



The Inside Scoop

If you have a bad wrist or shoulder, leave this exercise out.

GOAL

- To maintain a rigid body and perfect balance throughout.

KEYS

- The key to this exercise is remaining lifted out of your shoulder throughout the movement.
- Stay firm in your center and lifted in your hips.
- Keep the movements slow and controlled to facilitate balance.

NO-NOS

- Do not allow your body weight to sink into your wrist and shoulder.
- Keep your arm directly alongside your ear as you stretch overhead. Do not pitch your body forward as you go.

PROGRESSION

- As this is a difficult postion to maintain, try to map out the motion before pressing up onto your arm. Practice stretching your arm and turning your head while your hips are still resting on the mat. When you feel confident, try just holding the lifted position and balancing there for a breath. Finally, put the movements together to perform the full exercise.



ADVANCED

THE BOOMERANG

Step by Step

1. Sit tall with straight legs and cross your right ankle over your left. Press your hands into the mat on either side of your body to help you lift up out of your hips.
2. Inhale and roll back until your legs are overhead. Do not roll onto your neck.
3. Hold this position steady, exhaling as you open and close your legs in a snapping motion, recrossing your ankles, now with the left over right.
4. Inhale and roll up into your V position, bringing your arms forward to your toes.
5. Balancing in this position, bring your arms down and around the sides of your body, clasping them together behind your back and stretching them away from your torso.
6. Slowly, and with great control, exhale and begin leaning forward until your legs touch the mat and your nose is on your knees in a deep bow.
7. Keeping your arms lifted behind you, gently unclasp your hands and circle them forward to your toes.
8. Complete two sets (or four Boomerangs), switching ankles each time. End by sitting up and lifting your bottom forward to your heels to prepare for the Seal.

①



②



③





The Boomerang is one of the most comprehensive exercises of the matwork. It stretches and strengthens almost all the muscles of your body.

The Inside Scoop

This exercise can seem intimidating at first, but if you use the imagery from the Rollover and Teasers to help find your focus, you'll get it in no time.

KEYS

- Initiate from your powerhouse, keeping your body stiff so your movements do not get sloppy.
- Keep your arms as straight as possible and push off your palms as you lift your legs.
- Balance your weight on the back of your shoulders as you recross your ankles.
- If you are very flexible in your shoulders, do not lift your arms so high behind you that your shoulders pop. Keep the movements controlled at all times.
- Let your neck relax as you stretch forward over your legs but do not relax so long as to interrupt the dynamic flow of the exercise sequence.

NO-NOS

- Do not roll onto your neck.
- Do not allow your legs to drop down to the mat after balancing in the Teaser position. Think of "floating" forward as you slowly lower your legs and torso with control.

⑥



④



⑤



BEGINNER

THE SEAL

Step by Step

1. Sit at the front of your mat with your knees bent to your chest and heels together. Open your knees to shoulder width and slide a hand under and around each ankle. Pull your feet up off the mat until you are balancing on your tailbone.
2. Inhale and press your navel deeper into your spine.
3. Roll back, pulling your feet with you. Do not roll too far onto the back of your neck. Balance on the back of the shoulders instead, allowing your legs to extend slightly until your feet are over your head.
4. Balancing in the backward position, clap your heels together three times *like a seal clapping its flippers.*
5. Exhale as you roll forward, tucking your chin into your chest. Pull on your ankles to come up.
6. Balance in the forward position and clap your heels together three times.
7. *Imagine you are on rockers, balancing on the edges both front and back and trying not to tip over in either direction.*
8. Repeat the sequence six times, allowing yourself to feel the massage up and down the muscles of your back.
9. For an advanced transitional challenge: Begin building momentum as you are nearing completion of your sixth repetition. Cross your ankles while in the backward position, release your hands, and roll up and forward into a standing position. Use your powerhouse and the dynamic of your arms reaching out in front of you to bring you up.





The Seal massages the spinal muscles, works the powerhouse, and tests balance and coordination.



The Inside Scoop

If you have a bad neck, leave this exercise out.

GOAL

- To be able to balance, both back and forward, with your feet only a few inches from the mat in both positions.

KEYS

- The key to the Seal is remembering to relax and enjoy the movement. This exercise is playfully called the "dessert" exercise of the matwork because it feels so good after all the hard work you have done.
- Use the control of your powerhouse and breath to bring you forward and back.
- Allow your legs to straighten slightly as you bring them overhead, but leave your hips down.

NO-NOS

- Do not throw your head back and forth to accomplish the rocking motion of this exercise. Initiate the movements from your powerhouse and use the pulling on your ankles to help build momentum as you begin.
- Do not roll too far onto your neck. You should remain with your weight resting on the back of your shoulders instead.
- This should be a relaxing motion, so do not tense your shoulders or legs as you roll.

MODIFICATION

- If it is too difficult to master the clapping movement of the feet in the backward position, simply leave it out and clap the feet only on the forward balance portion.





ADVANCED

PUSH-UPS

Step by Step

1. Stand at the back of your mat with your feet and legs in the Pilates stance.
2. Inhale deeply and pull your navel into your spine.
3. Exhale and walk your hands down the front of your legs until your palms are pressing into the mat. Allow for the stretch up the backs of your legs.
4. Inhale and walk your hands out on the mat until your palms are directly beneath your shoulders.
5. Exhale and lower your hips until they are in line with the rest of your body. *Imagine you are suspended by a heavy spring attached to your belt loops and up to the ceiling.*
6. Perform three Push-Ups by bending and straightening your arms with your elbows held tightly to your sides. (Breathe normally.)
7. On your last Push-Up, fold up in your center, bringing your chest toward your legs. Exhale as you press your palms and heels firmly into the mat and pull your navel up deeper into your spine for a complete stretch. *Imagine being pulled up in your center by the spring.*
8. Inhale and walk your hands back toward your feet. Keep your legs as straight as possible as you go.
9. Exhale and roll your body back up to a standing position.
10. Repeat the sequence no more than three times.

    NOTE: For an advanced challenge, try performing the entire Push-Up sequence while balancing on one leg. The same steps apply for the single-leg Push-Up, but remember to keep your back leg *lifted* throughout the entire exercise. Remember to repeat the sequence on the other leg for uniformity.

11. End by standing tall and proud. You have just finished the full Pilates Matwork sequence!

①



②



Push-Ups concentrate on the shoulders, chest, arms, and upper back. Pilates' Push-Ups also stretch your shoulders and hamstrings.



The Inside Scoop

If you have a bad wrist or shoulder, leave this exercise out.

GOAL

- To keep your body rigid and elbows pinned to your sides as you perform the Push-Ups.

KEYS

- The key to the Pilates Push-Up is maintaining a firm center, with navel to spine and your buttocks and legs squeezing firmly together behind you. Powerhouse!
- Maintain a straight line with your body and head. Think of trying to touch your chin to the mat as you lower your body, and push off the heels of your hands as you lift up.
- The more rigid you are able to keep your body, the less chance of collapsing in your center. Keep your movements small and progress slowly.

NO-NOS

- Do not allow your middle to drop, as that places the majority of your body's weight onto your shoulders.
- Do not allow your head to hang as you perform the Push-Ups.

MODIFICATION

- If you find it too difficult to keep your elbows pinned into your sides, you may allow them to remain slightly open. Do not make a habit of this!

ADVANCED PROGRESSION

- As you walk your hands back toward your leg after the single leg push-up, lift your back leg higher and maintain that height as you try to lift both hands off the floor simultaneously. Rise, stretching your arms out long in front of you and your leg out long behind you, as in an arabesque. Bring your feet togther and stand tall before repeating the sequence with your other leg.

④



③





From the archives of The Pilates Studio®

Joseph Pilates demonstrates "Rocking."

Advanced Extras

These exercises are mostly adapted from the apparatus and are for the advanced student only.

1. Rowing III
2. Rowing IV
3. Rowing I
4. Twist I
5. Twist II
6. Rocking

ADVANCED EXTRA

ROWING III

Step by Step

1. Sit tall with your legs extended in front of you and squeeze them together. Feet are relaxed or softly pointed.
2. Bring your elbows into your sides and sit taller off the mat by squeezing your buttocks.
3. Inhale and reach your arms forward on an upward diagonal, lifting in your back but not in your shoulders.
4. Exhale and press your palms in a downward motion toward the floor *as if pressing down on a heavy lever.* Feel your shoulders also pressing down and away from your ears. Keep your chest lifted.
5. Inhale and bring your arms up above your head, just in front of your ears, without sinking into your back or shoulders.
6. Exhale and open your arms to the sides, pressing your palms downward *as if pushing down on two benches* by your sides. Make sure that your hands are still within your peripheral vision and that you are lifting in your back and chest.
7. Fold your elbows tightly back into your sides and repeat the sequence three to five times.
8. End by bringing your palms down to the mat alongside your hips and go on to Rowing IV. . . .


①


②


③

The Rowing exercises concentrate on posture and abdominal control. Their main focus is on the movements of the upper body, but stability in the lower body is essential to mastering the exercise.

The Extra Scoop

Although this exercise may feel like a simple circling of the arms, it is the way you perform the movement that counts!

GOAL

- The challenge of this exercise is to remain completely still while lifting tall in your torso and cinching in your waist throughout the sequence.

KEYS

- Squeeze your buttocks and legs together tightly in the Pilates stance throughout the movement.
- Keep your chest lifted and slightly in front of your hips so that you can stretch up and forward and not sink back into your tail.
- Make sure the back of your neck remains long and lifted from the crown of your head.
- Keep your shoulders pressing down and away from your ears to allow for a stretch in your neck.

NO-NO

- Do not allow your shoulders to creep up around your ears.



⑥



④



⑤

ADVANCED EXTRA

ROWING IV

Step by Step

1. Start by sitting tall with your legs extended in front of you, feet flexed (from your ankles, not your toes) and palms pressing into the mat by your sides.
2. Inhale, pulling your navel deep into your spine, and exhale as you fold your body in half, bringing your head and chest down to your legs.
3. Inhale and slide your hands along the mat past your heels. Keep pressing energy out of the heels.
4. Exhale as you slowly roll up to a sitting position, making sure you are lifting out of your back and waist and not from your shoulders. *Imagine pressing each vertebra into a wall* as you roll up to sitting. Your arms should now be held in midair parallel to your legs.
5. Inhale as you lift your arms up overhead. Stop just before your ears and stretch taller, keeping your feet flexed and pressing long out of your heels.
6. Exhale and open your arms to the sides, pressing your palms downward *as if pressing down on two benches* by your sides. Remember to keep your hands within your peripheral vision as you bring them down to the mat.
7. Inhale and then fold in half, repeating the sequence three to five times.
8. End by sitting tall with your hands drawn into your breastbone to prepare for Rowing I. . . .



①



②



③

This exercise works your powerhouse, stretches your back and hamstrings, and improves posture.

The Extra Scoop

GOAL

- To stay lifted and long in your waist and lower back throughout the arm movements.

KEYS

- Fluidity! Allow yourself to feel the fluid movements as you perform them.
- Press your palms down into the mat as you slide them past your heels to engage your abdominals.
- Keep stretching forward as you roll up. *Imagine you are inflating with air.*
- Stay pitched slightly forward in your hips to keep your powerhouse engaged. Navel to spine!
- Squeeze your buttocks and legs tightly together in the Pilates stance throughout the movements.
- Push your heels away from you as you roll up.

NO-NOS

- Do not roll up from your head or shoulders.
- Do not sit back on your tail as you roll up to a tall seated position.
- Do not lift in your shoulders as you circle your arms overhead.

④



⑤



⑥



ADVANCED EXTRA

ROWING I

Step by Step

1. Sit tall with your legs extended in front of you, feet flexed and your hands, made into fists, pulled into your breastbone. Extend your elbows without raising your shoulders.
2. Inhale as you roll your upper body backward, scooping your belly down toward the mat and squeezing your buttocks and the backs of your inner thighs together tightly for stability.
4. Holding yourself steady with your powerhouse, open your arms out wide to your sides with your palms facing back behind you.
5. Exhale and bring your upper body through your arms. *Imagine you are pressing your palms back into a wall,* and stretch down toward your legs. Allow your hands to clasp at your tailbone as you stretch forward.
6. Inhale and slowly lift your joined hands upward, stretching your arms toward the ceiling. Do not allow your shoulders to over rotate or dislocate (pop out of the joint) as you go.
7. Slowly unclasp your hands and exhale as you circle your arms around to your feet in a controlled sweeping motion. Visualize the arm movement of the butterfly stroke in swimming as you perform this motion.
8. Roll up to a straight-backed sitting position, drawing your hands back into your breastbone, and repeat the sequence three to five times.



①



②



③

This exercise works your powerhouse while stretching your arms, back, shoulders, and hamstrings. It improves balance and tests your muscle control.

The Extra Scoop

GOAL

- To stay lengthened out of your lower back throughout the movements of the rowing.

KEYS

- *Imagine you are pulling on springs attached to the wall in front of you.*
- Keep your buttocks and legs squeezing together tightly in the Pilates stance throughout.
- Keep your heels firmly planted on the mat in front of you.
- Navel to spine!
- Create resistance as you press your arms back and stretch forward.

NO-NOS

- Do not roll so far back as to lose control of your powerhouse, or tip backward.
- Do not let your shoulders creep up around your ears.
- Do not flop forward over your legs. Pull back in your powerhouse to enhance the stretch.
- Do not allow your shoulders to overrotate in the socket.



⑥



④



⑤

ADVANCED EXTRA

TWIST I

Step by Step

1. Sit on the side of one hip, propped up on a straight arm, fingers facing away from you.
2. Bend your knees and cross your top foot over your bottom foot. Hold your ankles in close to your bottom with your top hand and lean slightly into your supporting hand.
3. In one motion pull your navel up into your spine, inhaling, and lift your bottom hip to the ceiling by straightening your legs. *Imagine you are being pulled by a sling around your center.*
4. As your bottom hip lifts behind you, bring your top arm up and overhead. *Imagine drawing a sweeping arc up and over your body.*
5. Keep your eyes focused on your supporting hand throughout and lengthen your neck by stretching from the crown of your head. Reach your top arm long out of your side.
6. Reverse the motion of the twist, returning your bottom hip to the mat in a slow, controlled movement. Focus on stretching your arm up and away from your body as you lower yourself down.
7. Complete three controlled twists and then switch sides, working your opposite hip for three more.



This extra works your abdominals, arms, and waistline; stretches the side of your body; and improves balance and coordination.

The Extra Scoop

GOAL

- To keep your body perfectly steady throughout the twisting movement.

KEYS

- Keep lifting your bottom hip to the ceiling and reaching your top arm away to increase the stretch up the side of your body.
- Lift your belly up and away from your supporting arm to relieve the pressure on your wrist.
- Actively stretch the crown of your head away from your body to support your neck.

NO-NO

- Do not sink into your shoulders or wrists at any time during the sequence.

PROGRESSION

- The closer you bring your supporting arm to your body, the harder the exercise will become.



ADVANCED EXTRA

TWIST II

Step by Step

1. Sit on one side with your knees slightly bent and together, your top foot on the mat just in front of the other.
2. Place your hand, palm down and fingers facing away from you, almost directly beneath your shoulder. Allow your top hand to rest on your knee.
3. In one movement press up onto a straight arm and straighten your legs, bringing your top arm up and overhead until it is alongside your ear. Look toward your outstretched hand.
4. You should be balanced on your hand and the sides of your feet with your body lifted and straight, aligned from head to toe. *Imagine you are suspended by a strong spring attached through your belt loops and up to the ceiling.*
5. Maintaining your balance, bring your top arm down and thread it through the space between your lifted body and the floor. Allow your head and upper body to slowly follow, twisting to face the mat without allowing your hips to move.
6. Now take your arm out and reach it back, allowing your upper body to twist toward the ceiling.
7. Return to your long, aligned position of Step 4. Then, bringing your arm around and down, slowly lower your hip back to the mat.
8. Inhale as you lift up, exhale as you twist to face the mat, inhale as you face the ceiling, and exhale as you lower yourself back down.
9. Do two or three Twists on each side.



This extra puts your balance and control to the test. It works the major muscles of the abdominals, including your obliques, and stretches your hips and waistline.

The Extra Scoop

GOAL

- To maintain perfect balance and control in your hips while lengthening and twisting your upper body.

KEYS

- Stay reaching as long in your body as possible.
- Keep your hips still as you twist.
- Think of your feet being firmly planted as you perform the movements.

NO-NOS

- Do not let your hips or legs twist as you go.
- Do not sink into your shoulders or hips.
- Do not lean all your weight into your wrists or knees.



ADVANCED EXTRA

ROCKING

Step by Step

1. Lie on your stomach and bend your knees bringing your heels toward your bottom.
2. Reach behind you and grab your ankles (one at a time if necessary).
3. Inhaling, slowly stretch your body upward, lifting your chest and knees off the mat. Reach the soles of your feet to the back of your head. *Imagine you are being lifted to the ceiling by your hands and feet.*
4. Rock forward by pulling your ankles up toward your head and simultaneously pushing your chest to the mat. Exhale as you rock forward.
5. Inhale and rock back by lifting your chest and pulling back from your ankles. Keep your navel pressed to your spine. *Imagine yourself as a rocking horse.*
6. Rock back and forth five times. End by releasing your ankles and sitting back to your heels with your arms stretched long in front of you and your forehead on the mat. This will release the muscles of your lower back.



Rocking stretches your shoulders, back, quadriceps, and knees. It requires a strong back and a lot of abdominal control.

The Extra Scoop

GOAL

- To create a comfortable rhythm of breath and motion as you rock.

KEYS

- Use your breathing to provide the dynamic for the rocking.
- Keep your arms straight and your legs taut throughout.
- Constantly pull up in your chest and knees as you rock.
- Keep your head still and stretch your neck long to support the weight of your head.

NO-NOS

- Do not throw your head forward and back to initiate the rocking movements
- Do not allow your heels or hands to drop toward your bottom as you go.







From the archives of The Pilates Studio®

Joseph Pilates shows the results of his method.

The Standing Arm Series

1. Zip Up
2. Chest Expansion
3. Shaving the Head
4. Arm Circles
5. Biceps Curl I
6. Biceps Curl II
7. Triceps Extension
8. The Bug
9. Boxing
10. Lunges

These exercises can be performed with or without hand weights. (No more than two pounds is recommended.)

It is not necessary to perform all of the Standing Arm Series exercises each time. Choose the ones you feel best complement your workout level.

BEGINNER

ZIP UP

Step by Step

1. Stand in the Pilates stance with your arms hanging long in front of you.
2. Inhale and begin pulling your hands up the center line of your body, bending your elbows out to the sides as you go.
3. *Imagine you are pulling a tight zipper up your center line.*
4. Exhale and lower the hands and arms slowly, resisting gravity as you go.
5. *Imagine you are pressing down the heavy plunger on a box of dynamite.*
6. Do three to five sets, moving slowly and deliberately to create resistance.

PROGRESSIONS

- Rise up onto your toes as you "zip up" and lower your heels slowly as you press down.
- Do not allow your heels to come apart as you go.





BEGINNER

CHEST EXPANSION

Step by Step

1. Stand in the Pilates stance with your arms long by your sides.
2. Inhale and press your palms back, lifting your chest open as you do.
3. Hold your breath as you turn your head slowly to the left and then to the right, stretching your neck and shoulder muscles. *Imagine pulling back on heavy springs attached to the wall in front of you.*
4. Return your head to center and exhale as you release your arms back down to your sides.
5. Repeat four sets, alternating the initial direction you turn your head each time.

PROGRESSION

- Rise onto your toes as you press your arms back and balance there as you turn your head from side to side. Lower your heels as you exhale and return to the starting position.



BEGINNER

SHAVING THE HEAD

Step by Step

1. Stand in the Pilates stance with your hands held in a triangle behind your head. Do not lift your shoulders as you perform the movements of this exercise.
2. Inhale and press your hands upward on a slight diagonal forward. *Imagine you are rolling a large boulder up a steep mountain with your hands.*
3. Exhale and slowly bring your hands back behind your head, *imagining the weight of the boulder hovering above your head as you do.*
4. Use your powerhouse to control your movements.
5. Repeat the sequence five times.

PROGRESSIONS

- Rise onto your toes as you stretch your arms up, and lower your heels as you exhale and return to your original position.
- Do not allow your heels to come apart as you go.





BEGINNER

ARM CIRCLES

Step by Step

1. Stand in the Pilates stance with your arms hanging long in front of you.
2. Begin making small, controlled circles with your arms as you raise them in front of you.
3. Make sure you are circling your entire arm from your shoulder and not from your wrist or forearm. *Imagine you are holding a heavy bucket in each hand.*
4. Continue circling until your arms are above your shoulders and then reverse the circles as you lower them back to your sides.
5. Make sure that your shoulders are pressing down and away from your ears as you perform the lifting and lowering motions.
6. Complete three to five sets of lifting and lowering your circling arms.

PROGRESSIONS

- Rise onto your toes as you circle your arms upward and then lower your heels back to the mat as you lower your arms.
- If you are performing the movements correctly, you should be able to feel your powerhouse working throughout the exercise. Remember to keep your body weight shifted slightly forward and over your toes.





BEGINNER

BICEPS CURL I

Step by Step

1. Stand in the Pilates stance with your arms extended straight out in front of you, your hands made into fists with your palms facing the ceiling.
2. Inhale and slowly curl your wrists and forearms in toward your shoulders, *as if you were pulling on two heavy springs attached to the wall in front of you.*
3. Exhale and slowly uncurl your arms to their starting position, *trying to resist the pull of the imagined springs.*
4. Do not allow your elbows to drop as you perform the curling and uncurling movements.
5. Keep your shoulders pressing down and away from your ears.
6. Complete three to five repetitions.







BEGINNER

BICEPS CURL II

Step by Step

1. Stand in the Pilates stance with your arms held out to your sides, hands made into fists with your palms facing the ceiling.
2. Make sure that your arms are slightly in front of your shoulders so that your hands are still within your peripheral vision.
3. Inhale, curling your wrists and forearms in toward your shoulders in a slow and controlled motion, *as if you were pulling on heavy pulleys attached to the walls.*
4. Exhale and *resist their pull* as you slowly uncurl your arms back to their starting position.
5. Do not allow your shoulders to lift as you curl your arms in.
6. Make sure that your elbows are aligned with your shoulders throughout the entire movement.
7. Complete three to five repetitions.



INTERMEDIATE

TRICEPS EXTENSION

Step by Step

1. Stand with your feet parallel and aligned directly beneath your hips.
2. Bend your knees deeply until your kneecaps are over your toes.
3. Fold your upper body forward until your back *is as straight as a tabletop,* and make sure that your head is aligned with your spine.
4. With your hands made into fists, palms facing each other, bend your elbows tightly into your sides and bring your fists to your shoulders.
5. Inhale and slowly extend your arms out straight behind you, *as if pulling on two springs attached to the wall in front of you.*
6. Make sure that you allow your arms to straighten fully without moving your elbows from their position tight against your sides.
7. Exhale and *resist the pull of the imagined springs* as you slowly bring your hands back into your shoulders.
8. Keep your knees bent and use your powerhouse to control your movements.
9. Complete three to five repetitions.





INTERMEDIATE

THE BUG

Step by Step

1. Stand with your feet parallel and aligned directly beneath your hips. *(Try to draw an imaginary line from your hip bones to the center of your heels.)*
2. Bend your knees deeply until your kneecaps are over your toes.
3. Fold your upper body forward until your back is straight and allow your arms to hang straight down toward the mat.
4. With your hands in fists and your knuckles facing each other, open your elbows out to either side.
5. In a slow and controlled motion, inhale and begin lifting your elbows up until they are aligned with your shoulders. *Imagine you are trying to open heavy trap doors.*
6. Exhale and *resist the pull of the doors* as you slowly bring your fists back togther.
7. Make sure that your head remains aligned with your spine and does not hang forward or lift back. *Imagine pressing the crown of your head into the wall in front of you.*
8. If your back hurts during this sequence, stop. Round forward and *roll* yourself back up to a standing position.
9. Remember to keep your knees bent and in alignment with your hips, and use your powerhouse to control the movements.
10. Complete three to five repetitions.





ADVANCED

BOXING

Step by Step

1. Take the starting position of the Triceps Extension (p. 166).
2. Inhale and simultaneously extend one arm straight out in front of you and one arm straight behind you. Turn your wrists as you perform this motion so that your front palm is facing down and your back palm is facing up.
3. Exhale and return your fists into your sides.
4. Inhale as you repeat the sequence with the opposite arm leading. Make sure that your extended arms are aligned with your body, neither lifted above nor dropping below.
5. Complete three to five sets.

- Do not throw your arms forward or back.
- This movement is slow and controlled, aligned from your powerhouse.



①



②



③



④

ADVANCED

LUNGES

Step by Step

1. Stand in a modified Pilates stance with the heel of your left foot against the arch of your right (third position in dance).
2. Twist your upper body to face left with your arms long by your sides.
3. In one swift and controlled motion, step your left foot out on a diagonal lunge and lean your upper body toward it, bringing your arms up alongside your ears. Inhale as you lunge. *Imagine holding back a crowd.*
4. Exhaling, push off your left foot and come back to your starting position.
5. Complete three lunges to each side.

PROGRESSIONS

- In the outstretched lunge position, lower and lift your straight arms without moving your torso. Keep the back of your neck long and the crown of your head stretching to the wall for stability. Exhale as you lower your arms, inhale as you lift them. Do no more than three repetitions.
- Do not lower your hips below your knee as you lunge.
- Keep your knee directly over your lunging foot for proper alignment.
- Do not rest your torso on your thigh when you lunge.
- Press back into your straight leg to evenly distribute your weight.
- Keep your navel pressed deeply into your spine throughout the movements.





The Wall
(Cooldown)

1. Circles
2. Sliding Down
3. Rolling Down

CIRCLES ON THE WALL

Step by Step

1. Stand with your back against a wall and your feet about six to ten inches away from the base and in the Pilates stance.
2. Press your back flat so that all your vertebrae are touching the wall behind you.
3. Begin circling your arms in front of you, making sure not to lift them above shoulder height or to allow your hands out of your peripheral vision. *Imagine you are holding a heavy can of paint in each hand.*
4. Inhale as you begin the circle and exhale as you complete it.
5. Complete five circles in each direction.

The Inside Scoop

- Make sure that you do not arch your lower back away from the wall as you go.
- Keep your shoulders pressing down and away from your ears so that you are using the muscles of your powerhouse and not your shoulders to perform the circling motion.
- You may find it difficult in the beginning to get your entire spine flat, so make sure that at least your mid- and lower back make contact with the wall.
- Keep lifting taller as you go. Do not allow yourself to sink into your lower back or shoulders.







SLIDING DOWN THE WALL

Step by Step

1. Standing with your back pressed up against the wall, position your feet so that they are hip's width apart and about six to eight inches out from the wall. (This will vary depending on your height.)
2. Begin sliding your back down the wall by bending your knees. Keep your knees aligned with your hips and do not allow yourself to slide down so far that your bottom is below the height of your knees. Stop when you feel you can comfortably maintain a seated position.
3. Make sure that your entire spine maintains contact with the wall behind you by continuing to work from your powerhouse. *Imagine you are being pulled back by a powerful magnet behind the wall.*
4. Inhale as you slide down and then hold your breath as long as possible.
5. Exhale and slide yourself back up the wall by pressing into the soles of your feet.
6. Repeat the sequence three times, holding the down position as long as possible.

PROGRESSION

- In the seated position you can add the arm circles from page 163, or simply raise your arms to shoulder height as you slide down and lower your arms as you slide up as in the photos below. Hold your arms at shoulder height as you hold your breath. Exhale as you lower them.



ROLLING DOWN THE WALL

Do this exercise whenever you need to relax, or at the end of a workout to stretch your muscles.

Step by Step

1. Stand with your back pressed flat against a wall and your feet in the Pilates stance about eight to ten inches from the base of the wall.
2. Inhale and begin rolling down by bringing your chin to your chest and then "peeling" each vertebra from the wall. Imagine rubber cement sticking you to the wall as you roll down.
3. Roll down only to the point where your tailbone still maintains contact with the wall behind you, and allow your arms to hang loosely as you go.
4. Pull your navel deeply into your spine to increase the stretch. Engage all the muscles of your powerhouse to maintain control in this position. Imagine you are leaning over a railing.
5. Allow your arms to circle freely and relax your head and neck. Breathe naturally.
6. After five circles in each direction inhale and roll back up the wall, replacing each vertebra as you go.

The Inside Scoop

- Use your powerhouse and not your head to come up. (Your head should be the last part to lift up.)
- You may find that you need to soften your knees or slightly tuck your pelvis to begin rolling up.
- Make sure that you end by pressing your entire spine back into the wall, opening your chest and exhaling.







The Next Step

If you are looking to work with a certified Pilates instructor, here is a list of teachers around the world.

The Pilates Studio® Certifying Centers
© Copyright 1999 Pilates Inc., Pilates® and the Pilates Studio®
are registered trademarks of Pilates Inc. www.pilates-studio.com

NEW YORK CITY

(West Side) The Pilates Studio®, Sean P. Gallagher, PT, Director, 2121 Broadway, Suite 201, New York, NY 10023 (between 74th and 75th Sts.), (212) 875-0189, Fax: (212) 769-2368, Purchase Products: (888) 278-7227 x23

(Midtown) Drago's Gym, Romana Kryzanowska, Sari Pace, Master Teacher, 50 West 57th St., 6th Fl., New York, NY 10019, (212) 757-0724

FLORIDA

Fort Myers The Pilates Studio® of Fort Myers, Hope Petrine, Director/Certified Instructor, 11751 Cleveland Ave., Suites 21 and 22, Fort Myers, FL 33907, (941) 274-5711, Fax: (941) 274-6622

ILLINOIS

Evanston The Pilates Studio® of the Midwest, Fatima Bruhns, Director/Instructor, 820 Davis St., Suite 202, Evanston, IL 60201, (847) 492-0464, Fax: (847) 492-0210

WASHINGTON

Seattle The Pilates Studio® of Seattle & Capitol Hill Physical Therapy, Lauren Stephen, Lori Coleman Brown, PT, Directors/Instructors, 413 Fairview Ave. North, Seattle, WA 98109, (206) 405-3560, Fax: (206) 405-3938

PENNSYLVANIA

Philadelphia The Pilates Studio® @ the P.A. Ballet, June Hines, Megan Egan, Instructors, 1101 South Broad St., Philadelphia, PA 19147, (215) 551-7000, Fax: (215) 551-7224

GEORGIA

Atlanta The Pilates Studio® @ the Atlanta Ballet, Denise Reeves, Director/Instructor, 4279 Roswell Rd., #703, Atlanta, GA 30342, (404) 459-9555, Fax: (404) 459-9455

BRAZIL

São Paulo The Pilates Studio®, Inelia Garcia, Director/Instructor: R. Estevan, Cecilia Delgado. R. Cincinato Braga, Instructors, 520 Bela Vista, São Paulo, Brazil, Tel./Fax: 011-55112848905

AUSTRALIA

Surry Hills The New York Studio of Pilates® of Australia, Cynthia Lochard, Director/ Instructor, Roula Karitarzoglou, Edwina Ward, Instructors, Suite 12, Level 4146-56 Holt St., Surry Hills, 2010 Australia, Tel./Fax: 011-61296984689

Instructors Certified by the Pilates Studio®

ALABAMA	
Gulf Shores	Misti McKee, Instructor, Gulf Shores, AL 36542, (334) 955-6466
ALASKA	
Fairbanks	Ann Turner, Instructor, 621 Gingko Rd., Fairbanks, AK 99709, (907) 479-2360
ARIZONA	
Phoenix	Fitness Solutions, Inc., Lauren Tomasulo, Owner/Instructor, 4515 North 16th St., Suite 113, Phoenix, AZ 85016, (602) 631-9698
Phoenix	Pamela More, Instructor, Tel./Fax: (602) 569-1612
Phoenix	Pamela LaPierre, Phoenix, AZ 85008, (602) 817-4402
Scottsdale	Studio Joe, Joey Greco, Sherry Brady Greco, Janice Wessman, Pratibha Noggle, Instructors, 7170 East McDonald, #5, Scottsdale, AZ 85253, (602) 367-8501
Scottsdale	Harry Zabrocki, Alicia Elliott, Instructors, (602) 538-3046
Scottsdale	Janice Wessman, Instructor, Tel./Fax: (602) 675-8501, wessmanj@aol.com
Tucson	John White, Instructor, 2025 North Nancy Rose Blvd., Tucson, AZ 85712, (520) 319-8242
Tucson	Jennifer Pollack, Instructor, Tucson, AZ 85719, (520) 320-7844
Tucson	Suzanne Rosin, Jerome Weinberg, Instructors, 7001 Eagle Point Pl., Tucson, AZ 85750, (520) 299-0544
Tucson	Debi Crawford, Instructor, 5451 North Via Del Arbolito, Tucson, AZ 85750, (520) 577-1597, dlcrawf@aol.com
CALIFORNIA	
Alhambra	Powerhouse, Sasha Koziak, Instructor, 1003 Bushnell St., Alhambra, CA 91801, (526) 458-5600, jkoziak@earthlink.net
Berkeley	Minoo Hamzavi, Instructor, 1525 Spruce St., #36, Berkeley, CA 94709-1561, (510) 848-4133
Berkeley	Mirta Lee Ribas, Instructor, 1315 Stannage Ave., Berkeley, CA 94702, (510) 558-9010, birthrites@igc.org
Brentwood	Above and Beyond Fitness, Sara Carone, Instructor, 11601 Wilshire Blvd., Brentwood, CA 90049, (310) 966-1999
Burbank	Regina Fox Dawson, Instructor, (818) 559-3509, regdawson@yahoo.com
Burbank	Merilee Blaisdell, Instructor, (818) 504-9630, MerileeMB@aol.com
Calabasas Hills	Jacqueline Berns, Instructor, (310) 317-0990
Encino	Michael Levy Workout, Michael Levy, Linda Luber, Karen Biancardi, Sarah Lovatt Carone, Instructors, 17200 Ventura Blvd., #310, Encino, CA 91316, (818) 783-0097
Glendale	The Gold Touch, Darien Gold, Owner/Instructor, 610 North Jackson St., Glendale, CA 91206, (888) 908-4778

Hollywood	Bill and Jacqui Landrum, Instructors, 6315 Ivarene Ave., Hollywood, CA 90068, (323) 469-2012
Irvine	Audrey Wilson, Instructor, 30 Seton Rd., Irvine, CA 92715, (949) 551-3443, audreydancin@earthlink.net
Lomita/Torrance	Joellyn Musser, Instructor, 24725 Pennsylvania Ave., C-19, Lomita, CA 90717, (310) 530-7881, clbr8lkif@earthlink.net
Los Angeles	Licia Perea, Instructor, 2159 Lyric Ave., Los Angeles, CA 90027, (323) 669-3303
Los Angeles	Jennifer Palmer, Instructor, (323) 394-5469
Los Angeles	Niedra Gabriel (known formerly as Mickey Terra), Karen Biancardi, Instructors, 616 North Spaulding Ave., Los Angeles, CA 90036, (323) 651-1796
Los Angeles	Charlene Hanson, Instructor, 1745 Beloit Ave., #117, Los Angeles, CA 90025, (310) 312-8942
Los Angeles	Renda Mishalany, Instructor, 332½ North Orange Grove Ave., Los Angeles, CA 90036, (213) 525-0293
Los Angeles	Laurel Canyon Studio, Heidi Kling, Instructor, 8549 Walnut Dr., Los Angeles, CA 90046, (323) 654-4347, Fax: (323) 654-2396
Los Angeles	Karen Biancardi, 571 N. Gower, Los Angeles, CA 90004, (213) 957-2035
Los Angeles	Geoffrey Rhue, Instructor, 2127 Yosemite Dr., Los Angeles, CA 90041, (213) 254-8490
Los Angeles	Nonna Glazer, Instructor, 310 South Hamel, #103, Los Angeles, CA 90048, (310) 385-9485
Malibu	Survival of the Fittest, Jacqueline Berns, Instructor, 3806-J Cross Creek Rd., Malibu, CA 90265, (310) 317-0990
Malibu	Phyllis Reffo, Instructor, 30125 Harvester Rd., Malibu, CA 90265, (310) 457-8751
Newport Beach	Body Fit, Sheena Jongeneel, Instructor, 3422 Via Lido, Newport Beach, CA 92663, (949) 675-2639
North Hills	Sarah Lovatt-Carone, Instructor, 9219 Hagvenhurst Ave., North Hills, CA 91344, (818) 893-5387
North Hollywood	Trish Garland Studio, Trish Garland, Instructor, 12223 Califa St., North Hollywood, CA 91607, (818) 985-8222
Oakland	Katherine Davis, Instructor, Oakland, CA 94610, (510) 832-0653, KDavis5267@aol.com
Oceanside (San Diego Area)	Julia Hilleary, Instructor, Oceanside, CA 92056, (760) 431-7988
Ojai	Mary Jo Healy, Jinny Feiss, Instructors, 218 North Padre Juan Ave., Ojai, CA 93023, (805) 646-3797, Fax: (805) 640-8930, healy@ojai.net
Pasadena	ZOE, Zoe Hagler, Owner/Instructor/Teacher/Trainer, Geoffrey Rhue, Merilee Blaisdell, Jennifer Palmer, Instructors, 21 South El Molino, Pasadena, CA 91101, (626) 585-8853

Redondo Beach	Arlene Renay Reese, Instructor, 313 Avenue G, Redondo Beach, CA 90277, (310) 540-5539
San Diego	Studio Mo, Moses Urbano, Instructor, (619) 295-1850, Fax: (619) 295-1023, studiomo@home.com
San Francisco	Catherine Kirsch, Instructor, (415) 288-1001 x7064, Cherrie_34@hotmail.com
San Francisco	Kerri Palmer Gonon, Instructor, San Francisco, CA 94131, (415) 441-6985, twoinsf@flash.net or kp_trainer@yahoo.com
San Francisco	Nancy Rosellini, Instructor, 387 Staples Ave., San Francisco, CA 94112, (415) 441-6985
Santa Monica	Nela Fry, Instructor, 1008 Euclid St., Santa Monica, CA 90403, Tel./Fax: (310) 394-2805, nela@csi.com
Santa Monica	Heather Leon, Instructor, 508A Santa Monica Blvd, Santa Monica, CA 90401, (310) 394-9780
Santa Monica	Jennifer Bocian, Instructor, (310) 260-9736
Santa Monica	Unda Joy Luber, 932 17th Pl., Santa Monica, CA 90403, (310) 588-7376
Sherman Oaks	The Body Coach, Susan Lonergan, Instructor, (818) 905-6856
Sherman Oaks	Courtney, Instructor, (818) 986-8361
West Hollywood	Winsor Fitness, Mari Winsor, Instructor, 945 North LaCienega, West Hollywood, CA 90069, (310) 289-8766, Fax: (310) 289-0812
Westlake Village	Deborah Mandis Cozen, RPT, Instructor, 3034 Winding Lane, Westlake Village, CA 91361, (805) 373-1030
Westwood	Adylia Roman, Instructor, Westwood, CA 90024, (310) 446-6100
COLORADO	
Boulder	Flatiron Athletic Club, Deidre Szarabajka, Michelle Perkins, Instructors, 505 Thunderbird Dr., Boulder, CO 80301, (303) 499-6590, www.FACBoulder.com
Breckenridge	Jessica Paffrath, Instructor, Breckenridge, CO 80424, (970) 453-2139
Denver	Amy Halaby, Instructor (Denver Athletic Club), 1325 Glenarm Pl., Denver, CO 80204, (303) 534-7331 x1502
CONNECTICUT	
Bridgeport	Monica Mauri, Instructor, Bridgeport, CT 06605, (203) 333-8926
Cos Cob	Terese Garsson, Instructor, 14 Pond Pl., Cos Cob, CT 06807 (near Greenwich and Stamford), (203) 629-5543, Tgarsson@aol.com
Greenwich	The Fitness Edge, Mejo Wiggin, Saro Vanasup, Caroline Benton, Instructors, (203) 629-3743
Greenwich	Patricia Erickson, Instructor, P.O. Box 7737, Greenwich, CT 06836, Tel./Fax: (203) 661-1848, pattyerick@aol.com
New Canaan	Holly Mensching, Instructor, 11 Burtis Ave., New Canaan, CT 06840, (203) 972-3438

New Haven	Lenore Frost, CHT, OTR/L, Instructor, 61 Amity Rd., Suite B, New Haven, CT 06515, (203) 389-8177
Norfolk	Sarah Smolen, Instructor, (860) 542-0081
Norwalk	Oleg Belousou, Instructor, (203) 847-0591
Ridgefield	Simone Wunderli-Rucolas, Instructor, 124 Tanton Hill Rd., Ridgefield, CT 06877, (203) 438-7984, Swisssimi@aol.com
South Norwalk	Amy Matton, Instructor, South Norwalk, CT 06854, (203) 831-8701
Thomaston	Jeffrey Smolen, Instructor, (860) 283-6428
West Hartford	Elizabeth Flores, Instructor, 41 South Main St., West Hartford, CT 06107, (860) 233-5232
Westport	Bodywork Studio, Cristina Bruno, Lynn Bartner, Ossi Rauch, Jeanne Turkel, Instructors, 645 Post Rd. East, Westport, CT 06880, (203) 226-8550, Fax: (203) 222-0731
Westport	Lynn Bartner, Instructor, LMB21665@aol.com
FLORIDA	
Boca Raton	The Balanced Body Inc., Cecil S. Y. Ybanez, PT, Instructor, 5580 North Federal Hwy., Boca Raton, FL 33487, (561) 994-8848
Boca Raton	Boca Body Works, Cindy Maybruck, Instructor, 7088 Beracasa Way, Boca Raton, FL 33433, (561) 347-1110, Fax: (561) 395-7544, cmaybruck@aol.com
Burnell	Robin Campbell, Instructor, (904) 437-6022
Delray Beach	John Mahoney, Instructor, 39 Gleason St., Delray Beach, FL 33483, (561) 703-5646
Fort Lauderdale	Martha (Marty) Hammerstein, 516 Southwest 12th Ct., Fort Lauderdale, FL 33315, (954) 525-8565
Fort Myers	The Pilates Studio® of Fort Myers, Hope Petrine, Director/Certified Instructor, 11751 Cleveland Ave., Suites 21 and 22, Fort Myers, FL 33907, (941) 274-5711, Fax: (941) 2746622
Miami	Progressive Bodyworks of Miami, Anna Caban, Instructor, 3622 Northeast 2nd Ave., Miami, FL 33137, (305) 438-0555, Fax: (305) 438-0545, www.pro-body.com
Miami Beach	Alba Calzada Carter, Instructor, 1674 Meridian Ave., #506, Miami Beach, FL 33139, (305) 695-8084
Orlando	Mod Bod 2000, Jacki Garland, Jessica Gazzola, Samantha Gazzda, Instructors, (407) 903-0641
St. Petersburg	Linda McNamar, Instructor, 1045 9th Ave. North, St. Petersburg, FL 33705, (727) 822-4722
Sarasota	Dynamic Fitness Inc., Sherry Resh, Instructor, 4141 South Tamiami Trail, Suite 11, Sarasota, FL 34231, (941) 379-8811, S.Resh@aol.com
Winter Park	Michelle Hartog, Instructor, 4355 Bear Gully Rd., Winter Park, FL 32792, (407) 678-3116, mglowhart@aol.com

Winter Park	MatWorkz, Debra Watson, Instructor, 558 West New England Ave., #200, Winter Park, FL 32789, (407) 628-4888
GEORGIA	
Atlanta	The Pilates Studio® @ the Atlanta Ballet, Denise Reeves, Director/Instructor, Robin Warden, Deidra Simon, Emily Bradley, Cristina Williams, Instructors, 4279 Roswell Rd., #703, Atlanta, GA 30342, (404) 459-9555, Fax: (404) 459-9455
Atlanta	Studio Lotus, Misti McKee, Flo Fitzgerald, Instructors, 1123 Zonolite Rd., Suite 19, Atlanta, GA 30306, (404) 817-0900, www.studiolotus.com
Atlanta	Lisa Browning, Instructor, 3200 Cobb-Galeria Pkwy., #215, Atlanta, GA 30339, (770) 984-8889, LBSMT@aol.com
Duluth	Elizabeth Elliott, Instructor, (770) 623-3119, Lelliott2@aol.com
Norcross	The Work, Edgar Tirado, Instructor, 5952 Peachtree Ind. Blvd., #16, Norcross, GA, (770) 518-9610
HAWAII	
Pukalani	Belkis Lodzada, Instructor, Pukalani, HI 96788, (808) 572-7683
IDAHO	
Boise	Carrie Shanafelt, Instructor, (208) 345-6526
ILLINOIS	
Antioch	Patricia Kendziora, Instructor, (847) 395-2686
Barrington	Welcome to Your Body, Inc., Maryanne Radzis, Susan Hacker, Instructors, 220 South Cook St., Barrington, IL 60010, (847) 304-4900
Barrington	Susan Hacker, Instructor, (773) 489-9844
Chicago	Stacy Weitzner, Instructor, (773) 529-7104
Chicago	Juanita Lopez, Instructor/Teacher/Trainer, (312) 878-3639
Chicago	Julie Schiller, Instructor, 1016 North Dearborn, Chicago, IL 60610, (773) 871-2385
Chicago	Integrations, Inc., Kevin Bradley, Instructor, 1122 North Clark St., Chicago, IL 60610, (312) 280-7950
Chicago	David Englund, Instructor, 1912 Lincoln Park West, Chicago, IL 60714, (312) 932-0991, Mrerolfu@aol.com
Chicago	Chiropractic Health Resources, Corrine Stamslaw, Ceci Fano-Bryan, Jacqueline Brenner, Instructors, 2105 North Southport, #208, Chicago, IL 60614, (773) 472-0560
Chicago	Body Endeavors-Performance Gym, Liv Berger, Instructor, 1000 West North Ave., 3rd Fl., Chicago, IL 60622, (312) 202-0028, Fax: (312) 751-8122
Chicago	Gail Tangeros, Instructor, 1720 West Leland, #2, Chicago, IL 60640, (773) 561-2854
Chicago	Krista Merrill, Instructor, 5030 North Parkside Ave., Chicago, IL 60630, (773) 545-6165
Chicago	Susan Hacker, Instructor, (773) 489-9844

Chicago	Fitness Foundations Chicago, Linda Tremain, PT, Krista Merrill, Juliet Cella, Instructors, 213 West Institute Pl., #303, Chicago, IL 60610, (312) 642-5633, Fax: (312) 642-5733, ltremain@sprynet.com
Chicago	Erin Harper, Instructor, 5313 North Ravenswood, #301, Chicago, IL 60640, (773) 989-9979
Chicago	The Pilates Studio® of the Midwest at Hubbard Dance Complex, Dana Santi, Manager, 1151 West Jackson Ave., Chicago, IL 60607, (312) 492-8835, Fax: (312) 492-8875
Chicago	The Pilates Studio® of the Midwest at Ballet Chicago, 185 North Wabash, Chicago, IL 60601
Chicago	Joe Palla, Instructor, 5828 North Paulina, Chicago, IL 60660, (773) 344-6491
Evanston	The Pilates Studio® of the Midwest, Fatima Bruhns, Director/Instructor, Juanita Lopez, Teacher of Teachers and Training Director, Loribeth Cohen, PT (Dir. of P.T.), Dorota Gottfried, Jenna Sisk, Rhonda Celenza, Dana Santi, Joe Palla, Ellen Krafft, Randi Neebe, Mary Nardi, Gail Tangeros, Gail Diehl, Instructors, 820 Davis St., Suite 202, Evanston, IL 60201, (847) 492-0464, Fax: (847) 492-0210
Glen Carbon	The Integrated Body, Pam Moody, Instructor, 23-C Kettle River Dr., Glen Carbon, IL 62034 (St. Louis Area), (618) 656-3890
Glenview	Loribeth Cohen, Instructor, 3122 Crestwood Lane, Glenview, IL 60025, (847) 998-5859 or (847) 624-7455
Highland Park	In Synch Fitness Corp., Fatima Bruhns, Director/Instructor, Debbie LaMantia, Randi Neebe, Joe Palla, Patty Kendziora, Instructors, 1898 First St., Highland Park, IL 60035, (847) 266-1512
Lake Villa	Cathie Deref-McCue, Instructor, 38569 Route 59, Lake Villa, IL 60046 (near border of WI), (847) 356-0180, CDM_HEALTHY_BODY@Juno.com
North Shore	Cheryl Ivey, Instructor, (847) 651-5413
Oakbrook	Fitness Foundations, Inc., Linda Tremain, PT, Jill Popovich, Amy McDowell, Krista Merrill, Erin Harper, Instructors, 1111 West 22nd St., #610, Oakbrook, IL 60523, (630) 573-5877, Fax: (630) 573-5875, Itremain@sprynet.com
Oak Park	Alternative Fitness Studio, Andrea Andrade, Instructor, 126 North Oak Park Ave., Oak Park, IL 60302, (708) 386-4930
Skokie	Barbara Stoltz, Instructor, 8700 Ridge Way, Skokie, IL 60076, (847) 677-3194
Willowbrook	Dana Santi, Instructor, 6141 Knoll Wood Rd., Willowbrook, IL 60514, (630) 654-9834, DanaST919@aol.com
IOWA	
Bettendorf	Gail Diehl, Instructor, 4640 Crow Creek Ct., Bettendorf, IA 52722-6925, (319) 332-8625
KANSAS	
Overland Park	Modern Body Contrology, David Mooney, Instructor, 9308 Dearborn, Overland Park, KS 66207, Tel./Fax: (913) 649-1479

LOUISIANA	
New Orleans	Larry Gibas. Instructor, 1702 Fern St., New Orleans, LA 70118, (504) 862-6210
New Orleans	Monica Wilson, Instructor, (504) 894-1665, bwilson@mailhost.tes.tulane.edu
New Orleans	Caroline Probst, Instructor, (504) 527-6374, cnolan1@bellsouth.com
MAINE	
Belfast	Sustainable Fitness, Beth Tracy, Instructor, 92 Main St., Belfast, ME 04915, (207) 338-2977
Camden	Maureen (Mo) Freeman, Instructor, 133 Washington St., Camden, ME 04843, (207) 230-0073
Cape Elizabeth	Nancy Eitner, Instructor, 10 Olde Fort Rd., Cape Elizabeth, ME 04107, (207) 799-4139
Rockland	Ily Shofestall, Brigitte Ziebell, Instructors, The Thorndike, 385 Main St., Rockland, ME 04841, (207) 596-6177
MASSACHUSETTS	
Boston	Boston Bodyworks Studio, Kathryn Van Patten, Instructor, 12 Joy St., Boston, MA 02114, (617) 723-8090
Boston	Sarah Faller, Instructor, (617) 269-4300 x187
Boston	Progressive Bodyworks, Clare Dunphy-Foster, Cheryl Boyle Lathum, Vania Sacramento, Sarah Faller, Instructors, 441 Stuart St., Boston, MA 02116 (Back Bay), (617) 247-8090, strongbody@aol.com
Cambridge	Green Street Studios, Martha Mason, Lisa Silveria, Instructors, 185 Green St., Cambridge, MA 02139, (617) 491-2940
Gloucester	Joe Porcaro, Instructor, (978) 283-4531
Lenox	Uli Magel, Instructor, (888) 969-6668
Salem	Jimmy Raye, Instructor, 21 Salem St., Salem, MA 01970, (978) 741-1540
Stockbridge	Mathilde M. Klein, PT, Instructor, 21 South St., Box 1219, Stockbridge, MA 01262, (413) 298-3896
Wakefield	Flexfit Mind & Body Training Center, Carla Dunlap-Kann, Instructor, 607 North Ave., Soor 14, Wakefield, MA 01880, (781) 245-9143, coccobuns@carladunlap.com
Waltham	Fitness Finesse, Inc., Cheryl Lathum, Kathy Van Patten, Instructors, 411 Waverly Oaks Rd., #200, Waltham, MA 02452, (781) 736-0000
MARYLAND	
Baltimore	Goucher College, Elizabeth Lowe Ahearn, Lynne Balliette, Linda Moxley, Instructors, 1021 Dulaney Valley Rd., Baltimore, MD 21204-2794, (410) 337-6399, Fax: (410) 337-6433, eahearn@goucher.edu
Frederick	Linda Rinier Moxley, Instructor, (301) 694-3015
Mount Rainier	Michael Rooks, Instructor, (301) 927-2134, rookery@worldnet.att.net

MICHIGAN	
Detroit	Wayne State University, Theatre Dept., Nira Pullin, Instructor, 4841 Cass Ave., Suite 3225, Detroit, MI 48202, (313) 577-3508, (612) 672-6697 (for Univ. Theatre students only)
MISSOURI	
Columbia	In Line Studio, Janice Dulak, Instructor, Stevens College, 1815 University Ave., Columbia, MO, (573) 442-2211 x4715
Kirkwood	Susan Bronstein, Instructor, 11830 Big Bend Rd., St. Louis, MO 63122, (314) 965-5672
St. Louis	Body and Mind Awareness, Caryle Flom, Instructor, (314) 721-8148, caryle_flom@email.com
(St. Louis Area)	Pam Moody, Instructor, 340 South Fillmore, Edwardsville, IL 62025, (618) 692-9763
NEW JERSEY	
Absecon	Holly's Dance & Body Arts, Holly Bozzelli, Instructor, 119 Marin Dr., Absecon, NJ 08201, (609) 383-8822
Clifton	Karen Schoenberger, Instructor, (973) 779-7116, karsch@ix.netcom.com
Haledon	Julie LaRusso, Instructor, (973) 790-4243, gary-julie@worldnet.att.net
Hohokus	Body Tech, Kathryn Ross-Nash, Julie LaRusso, Instructors, 500 Barnett Pl., Hohokus, NJ 07423, (201) 444-6200, bodytech@pipeline.com
Kingston	Integrated Fitness, Donna C. Longo, Instructor, 4595 Route 27, Kingston, NJ 08528, POB 44, (609) 252-9229 and (609) 252-0997
Princeton	Anthony Rabara, Instructor, 377 Wall St., Princeton, NJ 08540, (609) 921-7990
Ridgewood	Arlene Dodd, Instructor, 75 Wilson St., Ridgewood, NJ 07450, (201) 455-3102
Tenafly	Jeannie Lee, Instructor, Tenafly, NJ 07670, (201) 568-0425
Titusville	Zane Rankin, Instructor, 50A River Dr., Titusville, NJ 08560, (609) 730-9544
Upper Montclair	The Movement Place, Holly Mensching, Karen Cooper, Sarah Ainsworth, Instructors, 48 Northview Ave., Upper Montclair, NJ 07043, (973) 746-2577
Waldwick	Pamela DeJohn, Instructor, 51 Waldwick Ave., Waldwick, NJ 07463, (201) 652-5986, pamdej@wordnet.att.net
Westmont	Donna M. Tambussi, Instructor, 20 Haddon Ave., Westmont, NJ 08108, (609) 869-3569
NEW MEXICO	
Santa Fe	Kathleen Loeks, Instructor, 615 Calle de Leon, Santa Fe, NM 87505, (505) 984-2909, Fax: (505) 982-7411
Sante Fe	Stacy Weitzner, Instructor, (505) 988-4489, awgalt@worldnet.att.net
NEW YORK STATE	
Albany	Body Wisdom, Ellen A. Weinstein, Owner/Instructor, 344 Fuller Rd., Albany, NY 12203, (518) 435-1064

Bedford	Vandy Lipman, Instructor, 66 Millbrook Rd., Bedford, NY 10506, (914) 234-6079
Briarcliff Manor	Saro Vanasup, Instructor, (914) 762-0040 (Westchester County)
Brooklyn	Jessica Fadem, Instructor, (718) 469-2265 (Park Slope)
Brooklyn	Body Tonic, Jennifer DeLuca, Instructor, 150 5th Ave., Brooklyn, NY 11215, (718) 622-2755
Brooklyn	Metta Coleman, PT, Instructor (Mount Sinai Hospital, NYC), Metira@aol.com
Brooklyn	Kara Springer, Instructor, 50 Clark St., Apt. 2C, Brooklyn, NY 11201, Kspringer@erols.com
Brooklyn	Rosanna Barberio, Instructor, (718) 246-2447
Cold Spring Harbor	Amy Wilson, Instructor, (516) 815-5505
Fishers Island	Susan Connelly, Instructor, P.O. Box 648, Fishers Island, NY 06390, (516) 788-7750
Glen Cove	Charmian's Center, Charmian Surface, Instructor, 13 Harbor Hill Rd., Glen Cove, NY 11542, (516) 671-0242
Great Neck	Fitness Studio at Marathon P. T., Doug Pollack, PT, Instructor/Owner, Ali Daniels, Ann Turner, Linda Figlia, Instructors, 330 Great Neck Rd., Great Neck, NY 11021 (Long Island), (516) 829-2938
Great Neck	Total Body Dynamics, Patricia O'Donnell, Instructor, (516) 944-0670
Greenlawn	Mary Lundo Studio, Mary Lundy, Instructor, 46 Fenwick St., Greenlawn, NY 11740, (516) 757-9050
Hastings-on-Hudson	Bodyscape, Kerry Donegan, Instructor, 5 Boulanger Plaza, (914) 478-2639
Huntington	Maggie Amrhein, Owner/Instructor, Teri Safaii, Amy Wilson, Instructors, 318 Main St., Huntington, NY 11743 (Long Island), (516) 421-1866
Irvington	Bella Flex Studio, Nancy Adler, Instructor, (914) 591-5690, adlern@email.msn.com
Katonah	Equipoise, Carol Dodge Baker, Vandy Lipman, Instructors, 113 Todd Rd., Katonah, NY 10536, (914) 232-3689, Fax: (914) 234-9289
Kingston	The Movement Center, Leah Chaback Feldman, Owner/Instructor/Teacher/Trainer, Elise Bacon, Beth Sullivan, Debra Noble, Instructors, 39 Broadway, Kingston, NY 12401, (914) 331-0986
Locust Valley	Fitness Studio at Marathon P. T., Doug Pollack, PT, Patricia O'Donnell, Ann Turner, Amy Wilson, Linda Figlia, Instructors, 22 Forest Ave., Locust Valley, NY 11560 (Long Island), (516) 671-8631
Locust Valley	Linda Figlia, Instructor, (718) 224-1695, Fra6301in@aol.com
Mount Kisco	The Art of Control, Simona Cipriani, Instructor/Owner, Tiziana Trovati, Megan Bridge, Instructors, 37 West Main St., Mount Kisco, NY 10569, (914) 242-0234
New Paltz	Elise Bacon, Instructor, 12 North Chestnut St., New Paltz, NY 12561, (914) 255-0559

Port Washington	Susan Brilliant, Instructor, (516) 883-8298
Rhinebeck	Deni Bank, Instructor, Astor Square Mail, 88 Rt. 9N, Suite 20, Rhinebeck, NY 12572, (914) 876-5114
Riverdale	Kerry Donegan, Instructor, (718) 548-1175
Rye	Amy Aronson Studio, Instructor, 560 Polly Park Rd., Rye, NY 10580 (Westchester County), (914) 921-0522
St. Albans	Miyuki Kato, Instructor, 194-09 109th Ave., #1F, St. Albans, NY 11412, (718) 217-9814, miyuki.mclaurine@cwix.com
Saratoga Springs	Lisa Hoffmaster, PT, Instructor, 376 Broadway, Suite 5, Saratoga Springs, NY 02866, (518) 677-2557
Scarsdale	Center for Movement, Eleanor Jardim, Jean McCabe, Kathy Wolfe, Donna Krystofiak, Instructors, 846 Scarsdale Ave., Scarsdale, NY 10543, (914) 722-7646
Sleepy Hollow	Saro Vanasup, Instructor (Westchester County), (914) 524-9655
Southampton	Jeanette Davis, Instructor, 395 County Rd., #39A, Southampton, NY 11968, (516) 204-0122
Westhampton	Mary McGuire Wein, Instructor, (516) 325-3491
Woodbury	Tracy Greenfield, Instructor, (516) 319-4915
NEW YORK CITY:	
(West Side)	The Pilates Studio®, Sean P. Gallagher, PT, Director, Bob Liekens, Supervising Instructor/Teacher/Trainer, Sharon Henry, Kelly Hogan, Saro Vanasup, Stephanie Beatty, Ton Voogt, Michael Fritzke, Peter Fiasca, Sandra Zevner, Instructors, 2121 Broadway, Suite 201, New York, NY 10023 (between 74th and 75th Sts.), (212) 875-0189, Fax: (212) 769-2368
(West Side)	Cynthia Khoury, Instructor, 2130 Broadway, #1002, New York, NY 10023, (212) 787-0746
(West Side)	Mathilde M. Klein, PT, Instructor, 210 West 78th St., #3A, New York, NY 10023, (212) 595-3863
(West Side)	Reebok Sports Club, Monique Rhodriquez, Sharon Korty, Holly Cosner, Instructors, 160 Columbus Ave., New York, NY 10023, (212) 501-3685
(West Side)	Alicia Principe, Instructor, 210 West 101st St., New York, NY 10025, (212) 662-6025
(West Side)	Suzanne Jordan, Instructor, 55 West 111th St., New York, NY 10026, (212) 427-5238, szanjord@usa.com
(West Side)	Christina Richards, Instructor, (212) 362-8939
(West Side)	Kim Reis, Instructor, (212) 353-6813, Kikireis@aol.com
(West Side)	Monique Rhodriguez, Instructor, (212) 665-0575
(West Side)	Simone Cardoso, Instructor, (212) 582-9567
(West Side)	Junghee Kallander, Instructor, (212) 665-0575

(Midtown)	Drago's Gym, Romana Kryzanowska, Sari Pace, Master Teachers, Lori Oshansky, Jeanne Gross, Claude Assante, Instructors, 50 West 57th St., 6th Fl., New York, NY 10019, (212) 757-0724
(East Side)	The Pilates Studio® & Pilates®, Inc., Elyssa Rosenberg, Associate Director, Suzanne Jordan, Junghee Kallander, Stephanie Beatty, Instructors, 890 Broadway, 6th Fl., New York, NY 10003, (212) 358-7676, Fax: (212) 358-7678, (800) 474-5283 or (888) 474-5283
(East Side)	Makiko Oka, Instructor, East 60th St., (212) 308-0786, MakikoOka@aol.net
(East Side)	JRW Physical Therapy, Roberta Wein, PT, Instructor, Yohanna Ragins, Bernadette Ceravolo, Instructors, 60 East 56th St., 5th Fl., New York, NY 10022, (212) 688-6089
(East Side)	Cristina Gregon, Instructor, (212) 477-6288, cristi1009@aol.com
(East Side)	Pamela Pardi, Instructor, (212) 420-5925, ppardi5700@aol.com
(East Side, UN)	Christy Ann Brown, Instructor, (212) 973-0273
(Gramercy Park)	Susan Connelly, Instructor, (212) 228-1984
(Greenwich Village)	Diane Lam, Instructor, 526 Hudson St., #2F, New York, NY 10014, (212) 627-8605
(Greenwich Village)	Village Body Mechanics, Clain Dipalma, Instructor, New York, NY 10011, (212) 229-9369
(Greenwich Village)	Hanna Koren, Instructor, 46 Downing St., #5A, New York, NY 10014, (212) 645-0157
(NoHo)	re:AB, Brooke Siler, Owner/Instructor, Maria Hassabi, Daniela Ubide, Karin Weidner, Amy Wilson, Kara Springer, Elizabeth Stile, Instructors, 33 Bleecker St. at Mott St., Suite 2C, New York, NY 10012, (212) 420-9111, Fax: (212) 475-4103, reABNYC@aol.com, www.reabnyc.com
(SoHo)	Halle Markle, Instructor, 594 Broadway, #904, New York, NY 10012 (near Houston Street), (212) 431-8377
(SoHo)	Frances Craig, Instructor, (212) 925-4629, Fcraig@aol.com
(TriBeCa)	TriBeCa Bodyworks, Alycea Baylis, Instructor/Owner, Elizabeth Knock, Gina Papalia, Diane Lam, Angeline Shaka, Alison Thiern, Tizonia Trovati, Kathy Buccellato, Gabrielle Gregory, Rosanna Barberio, Instructors, 177 Duane St., New York, NY 10013, (212) 625-0777, Fax: (212) 625-0030, PilatesNYC@aol.com
(West Village)	James Duus, Instructor, 245 West 14th St., (212) 229-7674
NORTH CAROLINA	
Boone	Marianne Adams, Instructor, 665 Tarleton Circle, Boone, NC 28607, (828) 262-3028, Adamsm@appstate.edu
Chapel Hill	Celeste Neal Huntington, Instructor, 251 South Elliot Rd., Chapel Hill, NC 27514, (919) 929-1536
Swannanoa	Kathie Campbell, Instructor, 123 Long Beach Rd., Swannanoa, NC 28778, (828) 298-3623

Wilmington	The Studio, Ben Harris, Instructor, 7210 Wrightville Ave., Wilmington, NC 28403, (910) 509-1414, Fax: (910) 509-0116

OHIO

Athens	The Body in Mind Studio, Marina Walchli, Leah Jean Rutkowski, Instructors, 9 Factory St., Athens, OH 45701, (740) 592-6090, Mwalchli:l@ohiou.edu
Athens	Leah Jean Rutkowski, Instructor, 11 Hocking St., Athens, OH 45701, (740) 589-6514, LR202595@oak.cats.ohiou.edu
Athens	Kris Kumfer, Instructor, Athens, OH 45701, (740) 597-6311
Cincinnati	BodyMind Balance, Inc., Jill Dema, Instructor, 3440 Edwards Rd., Cincinnati, OH 45208, (513) 871-6463
Ottawa	Jill Kuhlman, Instructor, (419) 532-3969, jk549196@oak.cat.ohiou.edu

OKLAHOMA

Norman	Laura Wren, Instructor, 4017 Oxford Way Norman, OK, (405) 321-6171

OREGON

Clackamas	Diane Caldwell, Instructor, (503) 698-4613, dcaldwell@imagina.com
Eugene	Susan Tate, Instructor, (541) 484-4011
Portland	Studio Adrienne, Adrienne Silveria, Instructor, Roxane Murata, Teacher/Trainer, 614 Southwest 11th Ave., Portland, OR 97205, (503) 227-1470, ELN/ro22@earthlink.net
Portland	Anne Egan, Instructor, 3424 Northeast 24th Ave., Portland, OR 97212, (503) 249-0823, Anne_Egan@Juno.com

PENNSYLVANIA

Ambler	Peter Fiasca, Instructor, 208 Brookwood Dr., Ambler, PA 19002, (215) 205-8004, p.fiasca@worldnet.att.net
Chalfont	Zahra Nasser, Instructor, Chalfont, PA 18914, (215) 997-5640
Doylestown	Caroline Nolan Probst, Instructor, (215) 340-2222
Honesdale	Stone Gate Studios, Robin Dodson, Instructor, (570) 251-9408
Philadelphia	The Pilates Studio® @ the P.A. Ballet, June Hines, Megan Egan, Instructors, 1101 South Broad St., Philadelphia, PA 19147, (215) 551-7000, Fax: (215) 551-7224
Philadelphia	Alternative Health and Fitness Concepts, Janine Galati, Instructor, 2016 Walnut St., 2nd Fl., Philadelphia, PA 19103, (215) 567-4969
Philadelphia	Megan Bridge, Instructor, (215) 925-0244, meganbridge@falshcom.net
Pittsburgh	Dilla Mastrangelo, J. Christopher Potts, Instructors, 820 Maryland Ave., Pittsburgh, PA 15232, (412) 363-3426
Rydal	June Hines, Instructor, 1132 Dixon Lane, Rydal, PA 19046, (215) 576-8261
Titusville	The Rankin Studio, Sane Rankin, Instructor, 50A River Dr., Titusville, PA, (609) 730-9544
Wilkes Barre	Rosa Anne Serpico, Instructor, (570) 824-4391, rserp@prodigy.net

RHODE ISLAND

Barrington	Cassy DaSilva, Instructor, Barrington, RI 02806, (401) 247-2700, C1Angels@aol.com
East Greenwich	Body Mind Fitness, Inc., Deborah Montaquila, Instructor, 5 Division Street East, East Greenwich, RI 02818, (401) 885-2102
Johnston	Balanced Fitness, Linda Chavaree, Pam Turner, Instructors, 1665 Hartford Ave., #36, Johnston, RI 02919, (401) 528-1166
Providence	Body by Design, Inc., Catherine Cuzzone, Instructor, 126 Bayard St., Providence, RI 02906, (401) 421-7408
Warwick	P. Turner Studio at R.G.E., Pamela Turner, Instructor, 1775 Bald Hill Rd., Warwick, RI 02886, (401) 738-4401

SOUTH CAROLINA

Anderson	Edgar Tirado, Instructor, Camp Lou Ann, (864) 226-5439
Columbia	Ann Lore, Instructor, 128 Woodshore Ct., Columbia, SC 29223, (803) 788-7764, angelannsc@webtv.net

TENNESSEE

Franklin	Carrie Chrestman Leal, Instructor, (615) 579-6688
Memphis	Bodies in Motion, Sway Hodges, Instructor, 5111 Sanderlin Ave., Memphis, TN 38117, (901) 452-4976
Nashville	Greta Gryzwana Teague, Instructor, (615) 321-5100, epiphanydance@mindspring.com
Nashville	Willow Studio, Bambi Watt, Instructor, 5133 Harding Rd., Nashville, TN 37205, (615) 354-1955
Nashville	Spring Studio, Julie Kraft, Instructor, 2021 21st Ave. South, Suite 100 (old St. Bemards convent bldg.), Nashville, TN 37212, (615) 292-1930
Nashville	Bodies in Balance, Sylvia Gamonet, Greta Teague, Elizabeth McCoyd, Instructors, 1907-B Division St., 2nd Fl., Nashville, TN 37203, (615) 321-5100, Fax: (615) 321-5107

TEXAS

Austin	The Hills Fitness Center, Tracy Anderson, Instructor, 4615 Beecaves Rd., Austin, TX 78746, (512) 327-4881
Austin	Rachel Bhagat, Instructor, Rbhagat@hotmail.com
Austin	Vicki Hickerson, Instructor, Austin, TX 78731, (512) 452-0115, Fax: (512) 453-8619
Dallas	Body Proof Inc., Read Gendler, Instructor, 6706 Northaven Rd., Dallas, TX 75230, (214) 369-7273, Fax: (214) 369-7990
Galveston	Studio 424, Vicki Bolen. Instructor, 424 22nd St., Galveston, TX 77550, (409) 762-1399

UTAH

Salt Lake City	Katie Howard, Instructor, 2396 East Logan Way, Salt Lake City, UT 84108, (801) 582-4848

Salt Lake City	Body and Mind Studio, Claudia Flores, Instructor, 3300 South East, Suite 201, Salt Lake City, UT 84106, (801) 486-2660
VIRGINIA	
Arlington	Body Logic, Karen Garcia, Instructor, 3017 B Clarendon Blvd., Arlington, VA 22201, (703) 527-9626
Norfolk	Power House, Camilo Rodriguez, Todd Rosenlieb, Instructors, 134 West Olney Rd., Norfolk, VA 23510, (757) 622-4822
Richmond	4S Fitness, Inc., Jerry Weiss, Instructor, 2927A West Cary St., Richmond, VA 23221, (804) 355-5010
Virginia Beach	Studio P, Leslie Vise-Clark, Reid Strasma, Instructors, 4020 Bonney Rd., Suite 104, Virginia Beach, VA 23452, (757) 306-7077, Fax: (757) 306-7009
Virginia Beach	Axiom, Elyse Tapper Cardon, Instructor, 332 North, Great Neck Rd., Suite 105, Virginia Beach, VA, (757) 486-8665, Fax: (757) 486-8663, davelyse@aol.com
WASHINGTON, D.C.	Excel Movement Studio, Lesa McLaughlin, Theran MacNeil, Kerry Devivo, Christine Abbott, Instructors, 3407 8th St. NE, 2nd Fl., Washington, D.C. 20017, (202) 269-3020
	Fitness for Life, Brigitte Ziebell, Instructor, 1417 27th St. NW, Washington, D.C. 20007, (202) 338-6765
WASHINGTON	
Everett	Intrinsic Energy Studio, Bernadette Wilson, Instructor, 3426 Broadway, Suite 301A, Everett, WA 98201, (425) 252-8240
Kirkland	Atasha Avery, Instructor, 429 8th Ave., Kirkland, WA 98033, (206) 822-2448, atasha_a@hotmail.com
Seattle	The Pilates Studio® of Seattle & Capitol Hill Physical Therapy, Lauren Stephen, Director/Instructor, Lori Coleman Brown, PT, Director/Instructor, Dorothee Vandewalle, Teacher/Trainer, Chacha Guerrero, Bernadette Wilson, Danielle Stanley, Sachiko Glass, PT, Theresa Shape, Instructors, 413 Fairview Ave. North, Seattle, WA 98109, (206) 405-3560, Fax: (206) 405-3938
Seattle	Robert Leonard Spa, Chris Siris, Dorothee Vandewalle, Instructors, 2033 6th Ave., Seattle, WA 98121, (206) 441-9900, Agish@aol.com
Seattle	Jennifer Saltzman, Instructor, 915 East Pine St., #408, Seattle, WA 98112, (206) 726-1903
Seattle	Molly Ashenfelter, Instructor, 5747 37th Ave. NE, Seattle, WA 98105, (206) 522-6620
Shoreline	Peggy Z. Protz, Instructor, 102 North 171st St., Shoreline, WA 98133, (206) 533-0820, pez009@sttl.uswest.net
WISCONSIN	
Milwaukee	Body Mechanics Studio, Jennifer Goldbeck, Instructor, 807 North Jefferson, Milwaukee, WI 53202, (414) 224-8219

WYOMING	
Jackson	Sally Lynne Baker, Instructor, POB 10609, Jackson, WY 83002, (307) 734-8940, DLCrawf@aol.com
Teton Village	Interhealth Studio, Sally Baker, Instructor, P.O.B 10609, Jackson, WY 83002

International Certified Instructors

AUSTRALIA	
Surry Hills	The New York Studio of Pilates® of Australia, Cynthia Lochard, Director/Instructor, Roula Karitarzoglou, Edwina Ward, Instructors, Suite 12, Level 4146-56 Holt St., Surry Hills, 2010 Australia, Tel./Fax: 011-61296984689
Sydney	Powerhouse Personal Training, Gina Richter, Chris Lavelle, Instructors, Suite 2, 44 Smith St., Balmain (Sydney) NSW 2041, Tel.: 011-61298186234, Fax: 011-61298186235
Sydney	Paulina Quinteros, Instructor, Tel.: 011-61293577448, Pquinteros@hotmail.com
AUSTRIA	
Vienna	Performing Arts Studios Vienna, Gabriella Cimino, Instructor, Zieglergasse 7, 1070 Vienna, Austria, Tel./Fax: 011-4315235656
BERMUDA	
Warwick	Contrology! Bermuda Ltd., Sophia Cannonier, Instructor, 82 Southshore Rd., Nautilus House, Upper Level, Warwick, Bermuda, WK09, (441) 236-0336, Fax: (441) 236-7998
BRAZIL	
Puerto Allegre	Studio Balance, Allesandra Tegoni, Instructor, Av. Encantado, 410, Puerto Allegre-RS 90470-420, Tel.: 011-55513306346
São Paulo	The Pilates Studio®, Inelia Garcia, Director/Instructor, R. Estevan, Cecilia Delgado, R. Cincinato Braga, Instructors, 520, Bela Vista, São Paulo, Brazil, Tel./Fax: 011-55112848905
São Paulo	Bergson Queiroz, Instructor, Rua Herculano de Freitas, 237-Ap 187, São Paulo, SP Brazil 01308-020, Tel.: 011-55112345106
CANADA	
Calgary	Lynne Smith, Instructor, 924 17th Ave. SW, Calgary, Alberta, Canada T2TOA2, (403) 244-4448
London/Ontario	Michaela Sirbu, Instructor, London, Ontario, (519) 457-1371, mcs@lon.ionline.net
Montreal	Deja Griffith, Instructor, #414, 3025 Sherbrook Street West, Montreal, Quebec H3Z- I A I, (514) 989-8299
Winnipeg/Manitoba	Therese Desrosiers, Instructor, (204) 943-3614
CHILE	
Santiago	Marcela Ortiz De Zarate Broughton, Instructor, El Buen Camino 96808-B Penalolen, Santiago, Chile, Tel./Fax: 011-5622927485

Santiago Fransisca Molina, Instructor, Nueva Costanera 4076, Santiago, Chile, Tel./Fax: 011-5622287133

ENGLAND

Cornwall Gayla Zukevich Stulce, Instructor, 6 Meadow Rise St., Columbus Major, Cornwall, UK TR96BL, Tel.: 011-441637881972, meadownse@aol.com

FRANCE

Marseille Monica Germani, Instructor, 23 Rue de la Guadelupe, 13006 Marseille, France, Tel.: 011-91710303

Paris Phillipe Taupin, Instructor, Le Centre du Marais, 39 Rue du Temple, 75006 Paris, France, Tel.: 011-33142729174, Fax: 011-33142729187

GERMANY

Berlin Galina Rohleder, Instructor, Schluterstranbe 13, 10625 Berlin, Germany, Tel.: 011-49308231124

Frankfurt Leigh Matthews, Mayra Rodriguez Matthews, Instructors, Hans-Thoma-Strasse 7 (H.h), 60596 Frankfurt, Tel.: 011-49696032156

Munich Karin Weidner-Mubanda, Instructor, Tel.: 011-49899576841

Stuttgart Davorka Kulenovic, Instructor, Sickstr. 32/70190, Stuttgart, Germany, Tel.: 011-497119239026

GREECE

Athens Eugenia Papadopolou, Instructor, Corpus Ray, 4 Doxapatri St., 114 71 Athens, Greece, Tel.: 011-3013617290

Cyprus Emily Papaloizou, Instructor, Tel.: 011-3575342582

ICELAND

Reykjavik National School of Ballet in Iceland, Lisa S. T. Johannsson, Instructor, Engjateig 1, Reykjavik 105, Iceland, Tel.: 011-3545530660, Fax: 011-3545572948

JAPAN

Tokyo University of the Sacred Heart, Yumi Takada, Instructor, Hiroo 4, Chome 3-1, Shibuya-Ku, Tokyo, Japan, Tel.: 011-81354853884

Tokyo Makiko Oka, Instructor, 2-59-6 Ikebukuro, Toshima-Ku, Tokyo, Japan 171, Tel.: 011-8139846546

LATVIA

Riga Studija Sports Pluss, Aija Peagle, Instructor, Blaumanu iela 5A, Riga, Latvia

NETHERLANDS

The Hague Marjorie Oron, Jane Poerwoatmodjo, Instructors, Keizerstraat 167, 2584 BE The Hague, Netherlands, Tel.: 011-31703508684, Fax: 011-31703228285

Rosmalen Manon Van Grunsven, Instructor, Jan Heymanslaan 1395246 BK Rosmalen, Tel.: 011-31736418956

PHILIPPINES

Manila Cecile Sicangco Ibarrola, Instructor, 227 Reposo St., Bel Air II, Makati, Manila, Philippines 1209, Tel.: 011-6328954465

PORTUGAL

Lisbon
Maria dos Anjos Machado, Rua de Angola, blc-6, 3-A, Encosta Da Carreira, 2750 Cas Cais, Portugal, Tel.: 011-35114865652

SPAIN

Barcelona
Estudio El Arte Del Control, Javier Perez Pont, Esperanza Aparicio Romero, Instructors, mazucase@teleline.es

Madrid
Estudio Lara, Lara Fermin, Instructor, C/Magallanes 28, 1 A, 28015 Madrid, Spain, Tel./Fax: 011-34915943863



Pilates at 82

From the archives of The Pilates Studio®

Glossary

This is a very basic reference for the terms and names of muscles that are commonly used throughout this book. For more detailed information on the muscles, please consult an anatomical reference book.

MUSCLES

Hamstrings: The muscles/tendons that run up the back of the leg from your knee to your buttocks.

Quadriceps: A large group of muscles that run up the front of the thigh from the knee to the hip.

Obliques: The side muscles of the abdominals.

Triceps: The muscles that run up the back of the arm from the elbow to the shoulder.

Biceps: The muscles that run up the inside of the arm from the inside of the elbow to the armpit.

TERMS

Range of Motion: The scope of movement within which a muscle can comfortably be exercised.

Dynamic: The energetic output with which you perform the movements. In the matwork, dynamic is emphasized over speed. Your energy should match your level of control.

Momentum: The force with which you exert your movements. No exercises of the matwork should be performed by "throwing" your body around. The momentum for each movement should initiate in your center, or powerhouse, and remain controlled.

Articulation: In essence this is the act of segmenting, or putting space between the vertebrae, for example, as you roll up or down.

"Softening": The point at which your legs or arms can be straightened without locking your joint. (For example, "soft" knees are not locked or pushed into a hyperextended position.)

Hyperextension: The extension, or straightening, of body parts beyond their normal limits. (For example, when a leg "bows" backward at the knee joint, it is considered hyperextened.)

"Lengthening": The act of stretching or straightening without strain or tension in the muscle.

Pilates stance: The V position of the feet, heels together and toes a few inches apart, legs squeezing tightly together from the heels to the back of the upper inner thighs.

Powerhouse: The band of muscles that circle the body just under the beltline.

"Navel to Spine": The physical and mental act of connecting your abdominals to your spine to protect and engage the muscles of the powerhouse region.

Scoop: The act of pulling your navel down into your spine by contracting your abdominal muscles to create a concave, or "scooped," feeling in the belly.

About the Author

Brooke Siler is the owner of re:AB, the renowned studio for Pilates in NoHo, New York. Hailed as "trainer to the stars" by *Entertainment Tonight* and named as one of the top personal trainers in the country by *Vogue* magazine, Brooke is fast becoming one of the leading fitness gurus today.

Brooke was trained in the Pilates method of body conditioning by Romana Kryzanowska, the leading authority in the Pilates method alive today. Romana's thirty years studying and teaching directly under Joseph Pilates, plus an additional thirty years since, have earned her the title of the grand dame of Pilates. Brooke spent over six hundred hours under Romana's master tutelage and has since gained her own reputation as a highly respected teacher among those in her field.

After being certified by The Pilates Studio® in New York City, Brooke began privately training clients out of her apartment in Greenwich Village. Her reputation began to grow through word of mouth among her celebrity clientele, and it wasn't long before the press caught on. In 1997 Brooke accepted a partnership offer from her friend Michele Hicks, a top model and actress. Together they opened re:AB, a stylish, personable studio for one-on-one and group Pilates training sessions. Since re:AB's opening in June 1997, the studio has appeared on NBC News, NY1 News, E!, and VH-1, and has been featured in publications as diverse as *Elle, The New York Observer, Vogue, People, Harper's Bazaar,* and *Cosmopolitan*.



HEALTH • FITNESS

> *"In ten sessions you will feel the difference, in twenty you will see the difference, and in thirty you'll have a whole new body."*
>
> *—Joseph H. Pilates*

The Pilates® method may be today's hottest exercise, but it has been endorsed by physicians for almost a century. Originally developed by Joseph H. Pilates to help strengthen and condition muscles, Pilates is the ultimate mind-body exercise for anyone who wants to tone, streamline, and realign their body without the bulked-up results of more conventional workout methods. Now, in *The Pilates® Body*, author Brooke Siler—one of the most sought-after personal trainers in the country and owner of New York's top studio for Pilates training, **re:AB**—provides a complete, easy-to follow program of Pilates exercises that can be done anywhere, anytime, and without machines. With step-by-step instructions, Siler guides the reader through the complete circuit of mat exercises, each of which is clearly illustrated by photographs, line drawings, and unique visualization exercises. With Pilates you will not only streamline your figure—you will dramatically improve your posture, flexibility, and balance, and enhance your physical and emotional well-being. *The Pilates Body* shows you how.

"Brooke is extremely knowledgeable about using Pilates as a tool to increase muscle strength and improve life energy and vitality. I love Brooke!"
—Amber Valletta

"All trainers feel committed to their clients. However, few give the dedication of a coach. Brooke is a trainer who is a coach. She pushes me to realize my potential and believes in my ability more than I do."
—Trudi Tapscott, Model Editor, *Vogue* magazine

Brooke Siler is the co-owner of **re:AB**, the renowned studio for Pilates® training in New York City, where her clients include Amber Valletta, Shalom Harlow, and Liv Tyler. Hailed as the "trainer to the stars," she trained under Joseph Pilates' protégé, Romana Kryzanowska, and has been recognized by *Vogue*, *Cosmopolitan*, *Harper's Bazaar*, and the *New York Observer* as one of the country's leading fitness gurus. She lives in New York City.

US $18.00 / $28.00 CAN

BROADWAY

Visit our website at www.broadwaybooks.com • Design by Umi Kenyon • Photography by Marc Royce

HUMAN
ANATOMY

J.A. Gosling MD, MB ChB, FRCS, FAS
Professor of Anatomy
Stanford University
USA

P.F. Harris MD, MB ChB, MSc, FAS
Emeritus Professor of Anatomy
University of Manchester
UK

J.R. Humpherson MB ChB
Formerly Senior Lecturer in Anatomy
Faculty of Life Sciences
University of Manchester
UK

I. Whitmore MD, MB BS, LRCP MRCS, FAS
Professor of Anatomy
Stanford University
USA

P.L.T. Willan MB ChB, FRCS
Formerly Professor of Anatomy
University of UAE
Al-Ain
United Arab Emirates

Contributors to previous editions
Photography by:

A.L. Bentley ABIPP, AIMBI, MBKS
Formerly Medical Photographer
Faculty of Life Sciences
University of Manchester
UK

J.L. Hargreaves BA(hons)
Formerly Medical Photographer
Faculty of Life Sciences
University of Manchester
UK

Embalming and section cutting by:

J.T. Davies LIAS
Formerly Senior Anatomical Technician
Faculty of Life Sciences
University of Manchester
UK

HUMAN ANATOMY

SIXTH EDITION

Color Atlas and Textbook

ELSEVIER

Edinburgh London New York Oxford Philadelphia St Louis Sydney Toronto 2017

ELSEVIER

First edition 1985
Second edition 1990
Third edition 1996
Fourth edition 2002
Fifth edition 2008
Sixth edition 2017

© 2017 Elsevier Ltd. All rights reserved.

The right of J.A. Gosling, P.F. Harris, J.R. Humpherson, I. Whitmore and P.L.T. Willan to be identified as author/s of this work has been asserted by them in accordance with the Copyright, Designs and Patents Act 1988.

No part of this publication may be reproduced or transmitted in any form or by any means, electronic or mechanical, including photocopying, recording, or any information storage and retrieval system, without permission in writing from the publisher. Details on how to seek permission, further information about the Publisher's permissions policies and our arrangements with organizations such as the Copyright Clearance Center and the Copyright Licensing Agency, can be found at our website: www.elsevier.com/permissions.

This book and the individual contributions contained in it are protected under copyright by the Publisher (other than as may be noted herein).

ISBN 978-0-7234-3827-4
eISBN 978-0-7234-3828-1

Notices
Knowledge and best practice in this field are constantly changing. As new research and experience broaden our understanding, changes in research methods, professional practices, or medical treatment may become necessary.

Practitioners and researchers must always rely on their own experience and knowledge in evaluating and using any information, methods, compounds, or experiments described herein. In using such information or methods they should be mindful of their own safety and the safety of others, including parties for whom they have a professional responsibility.

With respect to any drug or pharmaceutical products identified, readers are advised to check the most current information provided (i) on procedures featured or (ii) by the manufacturer of each product to be administered, to verify the recommended dose or formula, the method and duration of administration, and contraindications. It is the responsibility of practitioners, relying on their own experience and knowledge of their patients, to make diagnoses, to determine dosages and the best treatment for each individual patient, and to take all appropriate safety precautions.

To the fullest extent of the law, neither the Publisher nor the authors, contributors, or editors, assume any liability for any injury and/or damage to persons or property as a matter of products liability, negligence or otherwise, or from any use or operation of any methods, products, instructions, or ideas contained in the material herein.

ELSEVIER your source for books, journals and multimedia in the health sciences
www.elsevierhealth.com

ELSEVIER Book Aid International Working together to grow libraries in developing countries
www.elsevier.com • www.bookaid.org

The publisher's policy is to use **paper manufactured from sustainable forests**

Printed in China

For Elsevier:
Senior Content Strategist: Jeremy Bowes
Content Development Specialist: Nani Clansey
Project Manager: Andrew Riley
Designer/Design Direction: Miles Hitchen
Illustration Manager: Amy Faith Naylor

Preface to the Sixth Edition

The prime purpose of the first edition of *Human Anatomy* was to present topographical anatomy as it is seen in the dissecting room. The unique combination of photographs with accompanying labelled diagrams and concise text is preserved in this edition. However, the book has evolved to accommodate modern trends in the teaching of anatomy to emphasise clinical applications and problem solving.

Changes have included the addition of introductory sections for each chapter to provide an overview of each region; the incorporation of selected radiographs and CT scans and MR images; and the use of cross sections of all regions of the body to provide a basis for interpreting body scans.

Self-assessment exercises have included clinical case histories and multiple choice questions, as well as radiographs and scans, together with anatomical sections.

In previous editions the terminology was updated to conform to *Terminologia Anatomica* and a list of alternative terms is included. On occasions fonts have changed to improve readability.

In this edition we have continued to improve the text and the diagrams by remedying omissions and removing errors and ambiguities. In addition, we have added new radiographs and scans. The numerous examples of clinical and applied anatomy in each chapter are now clearly identified. After discussions with the publisher, we elected to indicate clinical comments by highlighting in blue and to employ enclosing arrows in some electronic media.

Whilst the book was initially written for medical and dental students, the content will now also be useful to candidates preparing for higher qualifications in surgical specialties and radiology. It will also be relevant to students in other professions where anatomy is a significant component of the course.

It is with sadness that we report the death of John Davies whose skills as an embalmer enabled the authors to prepare the many dissections presented in this atlas.

J.A.G., P.F.H., J.R.H., I.W., P.L.T.W.
2016

Preface to the First Edition

Despite the many anatomical atlases and textbooks currently available, there appeared to be a need for a book which combined the advantages of each of these forms of presentation. This book was conceived with the intention of filling that need. With a unique combination of photographs of dissections, accompanying diagrams and concise text, this volume aims to provide the student with a better understanding of human anatomy.

The basis of this work is the cadaver as seen in the dissecting room; therefore, reference to surface and radiological anatomy is minimal. Likewise, comments on the clinical and functional significance of selected anatomical structures are brief. However, comparison is made where appropriate between the anatomy of the living and that of the cadaver.

Each dissection was specially prepared and photographed to display only a few important features. However, since photographs of dissections are inherently difficult to interpret, each is accompanied by a guide in the form of a drawing. Each drawing is coloured and labelled to highlight the salient features of the dissection and is accompanied by axes to indicate the orientation of the specimen. Adjacent photographs often depict different stages of the same dissection to help the student construct a three dimensional image.

The first chapter introduces anatomical terminology, provides general information about the basic tissues of the body, and includes overall views of selected systems. Because the six subsequent chapters describe anatomy primarily through dissection, a regional approach has been employed. Features of bones are described only when considering their related structures, especially muscles and joints; osteology is not considered in its own right. The internal structure of the ear and eye are beyond the scope of this book since the study of these topics requires microscopy; the anatomy of the brain and spinal cord are also excluded as they are usually taught in special courses.

The level of detail contained in this book is appropriate for current courses in topographical anatomy for medical and dental undergraduates. In addition, it will be of value to postgraduates and to students entering those professions allied to medicine in which anatomy is part of the curriculum.

The terminology employed is that which is most frequently used in clinical practice. Where appropriate, alternatives (such as those recommended in *Nomina Anatomica*) are appended in brackets.

Preparation of the dissections and the text has occupied the authors for nearly five years. Our objective was to create a high quality and visually attractive anatomical work and we hope that the time and effort spent in its preparation is reflected in the finished product.

J.A.G., P.F.H., J.R.H., I.W., P.L.T.W.
Manchester, 1985

Acknowledgements for All Editions

The authors are indebted to Drs Victoria Clague, Gulraiz Ahmad and Peter Mullaney, Professors Waqar Bhatti, R.S. Harris and A.R. Moody, and to the Departments of Radiology at Kaiser Permanente, San Rafael CA and Manchester University for the provision of radiographs, CT scans and MR images.

Our families deserve special mention, as without their untiring support and patience these editions would certainly not have come to publication.

We thank them all.

J.A.G., P.F.H., J.R.H., I.W., P.L.T.W.

Human Anatomy User Guide

Organization

This book begins with a chapter on basic anatomical concepts. This is following seven chapters, each with its own introduction, on the different regions of the body. Information is usually presented in dissection order, progressing from the surface to deeper structures. The limbs are described from proximal to distal with the joints considered last.

Text and Photographs

Where possible the text and photographs are arranged on self-contained two-page spreads, so that the reader can locate relevant illustrations without turning a page. Clinical content is highlighted in blue in the print edition or indicated by enclosing arrows in eBook versions (➲).

Accompanying Diagrams

Adjacent to each photograph is a line diagram in which colour is used to focus attention on particular structures in the dissection. The colours usually conform to the following code:

■ Artery

■ Bone

■ Capsule/Fascia

■ Duct

■ Fat

■ Fibrocartilage

■ Gland

■ Hyaline cartilage

■ Ligament/Tendon

■ Mesentery/Peritoneum

■ Muscle

■ Nerve

■ Organ

■ Space

■ Vein

■ Mucous membrane

In diagrams showing muscle attachments on bone, the areas are shown using the muscle colour enclosed by different coloured lines. In other diagrams colour indicates the extent of a compartment or space.



Labels and Leader Lines

The structures of particular interest in each diagram are labelled. A single structure is named in a label either with a single leader line or by a leader line which branches to show different parts of the same structure. However, if two or more structures are named, the first has the main leader line terminating on it while the subsequent structures are indicated by side branches given off at progressively shorter distances from the label. A leader line ending in an arrow indicates a space or cavity.



Orientation Guides

Next to the diagrams are orientation guides in which the following abbreviations are used:

L left
R right
S superior
I inferior
P posterior
A anterior
la lateral
m medial
pr proximal
d distal

Orientation guides in oblique views employ large and small arrow heads and long and short arrow shafts. Here are four examples:

from in front;





from behind;





from the left side and slightly in front;





from the left side, slightly above and in front.





Terminology

The book conforms to *Terminologia Anatomica,* using the English terms. The list of alternative terms relates older non-official terms to their modern equivalent.

Self-assessment

The photographs in the main body of each chapter are unfettered by labels, leader lines or other superimposed markings; thus, readers can readily test their knowledge by either masking the whole of the accompanying diagram and studying the photograph alone, or covering only the labels.

Exams Skills, Clinical Case Skills & Observations Skills are provided after each chapter to allow readers to further self-test. Answers to Exam Skills and Clinical Case Skills are at the end of the book; those for Observation Skills are at the bottom of the same page as the picture.

Chapter 1

BASIC ANATOMICAL CONCEPTS

Terms of Position and Movement 2
Basic Tissues and Structures 5
  Skin 5
  Subcutaneous tissue (superficial fascia) 5
  Deep fascia 5
  Muscle 7
  Cartilage 9
  Bone 10
  Skeleton 11
  Joints 12
  Serous membranes and cavities 15
  Blood vessels 16
  Lymphatic vessels and nodes 19
  Nervous tissue 20

Terms of Position and Movement

To avoid ambiguity and confusion, anatomical terms of position and movement are defined according to an internationally accepted convention. This convention defines the anatomical position as one in which the human body stands erect with the feet together and the face, eyes and palms of the hands directed forwards (Fig. 1.1).

With the subject in the anatomical position, three sets of planes, mutually at right angles, can be defined.

Vertical (or longitudinal) planes are termed either coronal or sagittal. Coronal (or frontal) planes (Fig. 1.2) pass from one side to the other, while sagittal planes (Fig. 1.3) pass from front to back.


Superior
Lateral
Medial
Medial
Lateral
Median sagittal plane
Coronal plane
Horizontal plane
Proximal
Distal
Right
Posterior
Anterior
Left
Inferior
Fig. 1.2
Fig. 1.4
Fig. 1.3
Fig. 1.5

Fig. 1.1 Anatomical position and the terms used in anatomical description.


S
R
L
I
Brain
Mandible
Oral cavity

Fig. 1.2 Coronal section through the head.


S
A
P
I
Heart
Lung
Diaphragm
Stomach
Liver

Fig. 1.3 Sagittal section through the trunk. This section lies to the left of the median sagittal plane.

One particular sagittal plane, the median sagittal (midsagittal) plane, lies in the midline and divides the body into right and left halves (Fig. 1.4).

Horizontal (or transverse) planes (Fig. 1.5) transect the body from side to side and front to back.

Sections cut at right angles to the long axis of an organ or parts of the body are also known as transverse. Similarly, longitudinal sections are cut parallel to the long axis.

The terms medial and lateral are used to indicate the position of structures relative to the median sagittal plane. For example, the ring finger lies lateral to the little finger but medial to the thumb. The front and back of the body are usually termed the anterior (or ventral) and posterior (or dorsal) surfaces, respectively (Fig. 1.1). Thus one structure is described as anterior to another because it is placed farther forwards.

Superior and inferior are terms used to indicate the relative head/foot positions of structures (Fig. 1.1). Those lying towards the head (or cranial) end of the body are described as superior to others, which are inferior (or caudal). Thus the heart lies superior to the diaphragm; the diaphragm is inferior to the heart. In the limbs, the terms proximal and distal have comparable meanings. For example, the elbow joint is proximal to the wrist but distal to the shoulder. These terms are also used to indicate the physiological direction of flow in tubes, such as the oesophagus is proximal to the stomach.

The terms superficial and deep indicate the location of structures in relation to the body surface. Thus the ribs lie superficial to the lungs but deep to the skin of the chest wall (Fig. 1.5).



Fig. 1.4 Median sagittal section through the trunk.



Fig. 1.5 Transverse section through the thorax at the level of the intervertebral disc between the sixth and seventh thoracic vertebrae. Inferior aspect. (Compare Fig. 2.71.)

Movements at joints are also described by specific terms. From the anatomical position, forward movement of one part in relation to the rest of the body is called flexion. Extension carries the same part posteriorly (Fig. 1.6). However, because in the fetus the developing upper and lower limbs rotate in different directions, the movements of flexion and extension in all joints from the knee downwards occur in opposite directions to the equivalent joints in the upper limb. In abduction, the structure moves away from the median sagittal plane in a lateral direction, whereas adduction moves it towards the midline (Fig. 1.7). For the fingers and toes, the terms abduction and adduction are used in reference to a longitudinal plane passing along the middle finger or the second toe, respectively. Movement around the longitudinal axis of part of the body is called rotation. In medial (or internal) rotation, the anterior surface of a limb rotates medially, while lateral (or external) rotation turns the anterior surface laterally (Fig. 1.8). Movements that combine flexion, extension, abduction, adduction and medial and lateral rotation (for instance, the 'windmilling' action seen at the shoulder joint) are known as circumduction.



Fig. 1.7 Movements of abduction and adduction. In adduction, flexion of the shoulder joint allows the limb to be carried anterior to the trunk.



Fig. 1.6 Movements of flexion and extension of the shoulder joint.



Fig. 1.8 Movement of the forearm indicates medial and lateral rotation at the shoulder joint. The elbow is flexed.

Basic Tissues and Structures

Skin

Skin (Fig. 1.9) is a protective covering for the surface of the body and comprises a superficial layer, called the epidermis, and a deeper layer, the dermis. The epidermis is an epithelium consisting of a surface layer of dead cells, which are continually shed and replaced by cells from its deeper germinal layer. The dermis is a layer of connective tissue containing blood vessels, lymphatics and nerves. In most areas of the body, the skin is thin and mobile over the underlying structures. Specializations of the skin include fingernails and toenails, hair follicles and sweat glands. On the palms of the hands and soles of the feet (and corresponding surfaces of the digits), hair follicles are absent and the epidermis is relatively thick. The skin in these regions is also firmly anchored to the underlying structures, reducing its mobility during gripping and standing. Lines of tension (Langer's lines) occur within skin and are of importance to surgeons. Scars following surgical incisions made along these lines tend to be narrower than those made across the lines of tension.

Skin is usually well vascularized and receives blood from numerous subcutaneous vessels. Knowledge of this vascular supply is important when operations that involve the use of skin flaps are undertaken. Skin has a rich nerve supply, responding to touch, pressure, heat, cold, vibration and pain. In certain areas, such as the fingertips, the skin is especially sensitive to touch and pressure. Skin is innervated by superficial (cutaneous) branches of spinal or cranial nerves. The area of skin supplied by each cranial or spinal nerve is known as a dermatome (Figs 1.37 & 1.38).

Subcutaneous tissue (superficial fascia)

Immediately deep to the skin is a layer of loose connective tissue, the subcutaneous tissue (Fig. 1.9), which contains networks of superficial veins and lymphatics and is traversed by cutaneous nerves and arteries. It also contains fat, which varies considerably in thickness from region to region and between individuals. For example, over the buttock the fat is particularly thick, while on the back of the hand it is relatively thin. Over the lower abdomen this tissue is subdivided into two layers, a superficial fatty layer and a deeper membranous layer.

Deep fascia

The deep fascia (Fig. 1.9) consists of a layer of dense connective tissue immediately beneath the subcutaneous tissue. Although thin over the thorax and abdomen, it forms a substantial layer in the limbs (e.g. fascia lata; p. 260) and neck (e.g. investing fascia; p. 324). Near the wrist and ankle joints, the deep fascia is thickened to form retinacula, which maintain the tendons in position as they cross the joints. Deep fascia also provides attachment for muscles and gives anchorage to intermuscular septa, which separate the muscles into compartments. Bleeding and swelling within muscle compartments due to crushing injuries or fractures may raise the pressure so much that it compresses blood vessels and reduces blood flow. The resulting ischaemia may be followed by scarring and deformity with contracture of muscles.



Fig. 1.9 Multilevel 'step' dissection through the right midcalf to show layers of skin, fascia and intermuscular septa.


External
oblique
Apo-
neurosis
S
R
L
I

Fig. 1.10 External oblique is a flat muscle with an extensive aponeurosis.


External
oblique
(cut)
Costal
cartilages
S
R
L
I

Fig. 1.11 External oblique cut to show its thickness.

Muscle

Muscle is a tissue in which active contraction shortens its component cells and/or generates tension along their length. There are three basic types: smooth muscle, cardiac striated muscle, voluntary striated muscle. Striated and smooth describe the microscopic appearance of the muscle.

Smooth muscle is present in the organs of the alimentary, genitourinary and respiratory systems and in the walls of blood vessels. Capable of slow, sustained contraction, smooth muscle is usually controlled by the autonomic nervous system (p. 22) and by endocrine secretions (hormones).

Cardiac striated muscle (myocardium) is confined to the wall of the heart and is able to contract spontaneously and rhythmically. Its cyclical activity is coordinated by the specialized conducting tissue of the heart and can be modified by the autonomic nervous system.

Skeletal muscle (voluntary striated muscle) is the basic component of those muscles that produce movements at joints. These actions are controlled by the somatic nervous system (p. 20) and may be voluntary or reflex. Each muscle cell (fibre) has its own motor nerve ending, which initiates contraction of the fibre. Muscles may be attached to the periosteum of bones either directly or by fibrous connective tissue in the form of deep fascia, intermuscular septa or tendons. Direct fleshy attachment can be extensive but tendons are usually attached to small areas of bone. Muscles with similar actions tend to be grouped together, and in limbs these groups occur in compartments (e.g. extensor compartment of the forearm).

Usually, each end of a muscle has an attachment to bone. The attachment that remains relatively fixed when the muscle performs its prime action is known as the origin, whereas the insertion is the more mobile attachment. However, in some movements, the origin moves more than the insertion; therefore, these terms are of only limited significance.

The muscle fibres within voluntary muscle are arranged in differing patterns, which reflect the function of the muscle. Sometimes they are found as thin flat sheets (as in external oblique; Figs 1.10 & 1.11). Strap muscles (such as sartorius; Fig. 1.12) have long fibres that reach without interruption from one end of the muscle to the other.



Fig. 1.12 Sartorius is a strap muscle.



Fig. 1.13 Flexor pollicis longus is a unipennate muscle.



Fig. 1.14 Dorsal interossei are bipennate muscles.



Fig. 1.15 Subscapularis is a multipennate muscle.

Pennate muscles are characterized by fibres that run obliquely. Unipennate muscles (e.g. flexor pollicis longus; Fig. 1.13) have fibres running from their origin to attach along only one side of the tendon of insertion. In bipennate muscles (such as dorsal interossei; Fig. 1.14) the fibres are anchored to both sides of the tendon of insertion.

Multipennate muscles (e.g. subscapularis; Fig. 1.15) have several tendons of origin and insertion with muscle fibres passing obliquely between them. Some muscles, for instance digastric, have two fleshy parts (bellies) connected by an intermediate tendon (p. 348).

Most tendons are thick and round or flattened in cross-section, although some form thin sheets called aponeuroses (Fig. 1.10). When tendons cross projections or traverse confined spaces, they are often enveloped in a double layer of synovial membrane to minimize friction. Where they cross joints, tendons are often held in place by bands of thick fibrous tissue, which prevent 'bowstringing' when the joints are moved. Examples include the retinacula at the wrist and ankle joints, and tendon sheaths in the fingers and toes (Figs 1.16 & 1.17).

The nerve supply to a skeletal muscle contains both motor and sensory fibres, which usually enter the fleshy part of the muscle. Groups of muscles with similar actions tend to be supplied by nerve fibres derived from the same spinal cord segments.

As very metabolically active tissue, muscle has a rich arterial blood supply, usually carried by several separate vessels. The contraction and relaxation of muscles in the limbs compresses the veins in each compartment. As the veins contain unidirectional valves, this muscle pump action assists the return of venous blood from the limbs to the trunk.



Fig. 1.16 Anterior view of the left hand, dissected to reveal its fibrous sheaths and tendons.



Fig. 1.17 Posterior view of the left hand, dissected to show the extensor retinaculum at the wrist.

Cartilage

Cartilage is a variety of hard connective tissue, which gains its nutrition by diffusion from blood vessels in the surrounding tissues. It is classified by its histological structure into hyaline cartilage, fibrocartilage and elastic cartilage.

Hyaline cartilage occurs in costal cartilages (Fig. 1.11), the cartilages of the larynx and trachea, and in developing bones. In synovial joints (Fig. 1.23) it forms the glassy, smooth articular surfaces, which reduce friction during movement. Articular cartilage is partly nourished by diffusion from the synovial fluid in the joint cavity.

The inclusion of tough inelastic collagen fibres in the matrix constitutes fibrocartilage, which is stronger and more flexible than the hyaline type. Fibrocartilage is found in intervertebral discs (Fig. 1.22), the pubic symphysis, the manubriosternal joint, and as articular discs in some synovial joints (e.g. knee and temporomandibular).

Elastic cartilage, which occurs in the external ear and epiglottis, is the most flexible form of cartilage. It contains predominantly elastic fibres and has a yellowish appearance.

Cartilage may become calcified in old age, becoming harder and more rigid. Brittle costal cartilages may be subject to fracture during chest compressions of cardiopulmonary resuscitation, particularly in older people.



Fig. 1.18 Longitudinal section of an adult tibia.



Fig. 1.19 Anterior view of a child's tibia.

Bone

Bone forms the basis of the skeleton and is characterized by a hard, calcified matrix, which gives rigidity. In most bones two zones are visible. Near the surface the outer cortical layer of bone appears solid and is called compact bone, whereas centrally the bone is known as spongy (cancellous) bone. Many bones contain a cavity (medulla) occupied by the bone marrow, a potential site of blood cell production (Fig. 1.18).

The numerous bones comprising the human skeleton vary considerably in shape and size, and are classified into long bones (e.g. femur); short bones (bones of the carpus); flat bones (parietal bone of skull); irregular bones (maxilla of skull); and sesamoid bones (patella). Sesamoid bones develop in tendons, generally where the tendon passes over a joint or bony projection. Some bones are described as pneumatized because of their air-filled cavities (for instance, ethmoid).

Bone is enveloped by a thin layer of fibrous tissue called periosteum (Fig. 1.9), which provides anchorage for muscles, tendons and ligaments. Periosteum is a source of cells for bone growth and repair and is richly innervated and exquisitely sensitive to pain. The pain of fractures or tumours in bone is often due to disturbance of the periosteum.

Bone has a profuse blood supply provided partly via the periosteal vessels and partly by nutrient arteries, which enter bones via nutrient foramina and also supply the marrow. Fractured bones often bleed profusely from damaged medullary and periosteal vessels.

Several names are given to the different parts of a long bone in relation to its development (Fig. 1.19). The shaft (or diaphysis) ossifies first and is separated by growth plates from the secondary centres of ossification (or epiphyses), which usually lie at the extremities of the bone. The part of a diaphysis next to a growth plate is called a metaphysis and has a particularly rich blood supply. When increase in bone length ceases, the growth plates disappear and the epiphyses fuse with the diaphysis. Fractures involving epiphyses and metaphyses often disrupt bone growth.


Frontal
Temporal
Zygomatic
Maxilla
Mandible
First rib
Manubrium
Body of sternum
Seventh cervical vertebra
First thoracic vertebra
Parietal
Occipital
Pectoral girdle
Clavicle
Scapula
Humerus
Twelfth rib
Radius
Ulna
Lumbar vertebra
Hip bone
Ilium
Ischium
Pubis
Femur
Phalanges
Metacarpals
Carpals
Sacrum
Coccyx
Patella
Tibia
Fibula
Tarsals
Metatarsals
Phalanges
S
R
L
I
S
L
R
I

Fig. 1.20 Anterior and posterior views of the skeleton.

Skeleton

The skeleton (Fig. 1.20) is composed of bones and cartilages held together by joints, and gives rigidity and support to the body. It has axial and appendicular components. The axial component includes the skull, vertebral column, ribs, costal cartilages and sternum. The appendicular skeleton comprises the bones of the upper and lower limbs and their associated girdles. In this book, individual bones are described in the appropriate regions.

Joints

Joints are classified according to their structure into fibrous, cartilaginous and synovial types. In fibrous joints (Fig. 1.21), which are relatively immobile, the two bones are joined by fibrous tissue (e.g. sutures seen between the bones of the skull).

Cartilage is interposed between bone ends in cartilaginous joints. Primary cartilaginous joints contain hyaline cartilage, are usually capable of only limited movement, and are described between the ribs and sternum. In secondary cartilaginous joints (Fig. 1.22), fibrocartilage unites the bone ends. These joints, which generally allow more movement than those of the primary type, all lie in the midline. Examples include the intervertebral discs, the manubriosternal joint and the pubic symphysis.

Synovial joints

The most common type of joint is the synovial joint, which is complex and usually highly mobile. They are classified according


Fibula
Tibia
Anterior tibiofibular ligament
Medial malleolus
Lateral malleolus
S
la
m
I

Fig. 1.21 The inferior tibiofibular joint is an example of a fibrous joint.


S
P
A
I
Lumbar vertebra
Spinal nerve
Intervertebral foramen
Intervertebral disc
Pedicle
Anterior longitudinal ligament

Fig. 1.22 Sagittal section to show an intervertebral disc, a secondary cartilaginous joint.

to the shape of the joint surfaces (such as plane, saddle, ball-and-socket) or by the type of movement they permit (such as sliding, pivot, hinge). In a typical synovial joint (Fig. 1.23) the articulating surfaces are coated with hyaline cartilage and the bones are joined by a fibrous capsule, a tubular sleeve, which is attached around the periphery of the areas of articular cartilage. In every synovial joint, all of the interior (except for intra-articular cartilage) is lined with synovial membrane. This thin vascular membrane secretes synovial fluid into the joint space, providing nutrition for the cartilage and lubrication for the joint.

The capsule is usually thickened to form strengthening bands known as capsular ligaments (e.g. the pubofemoral ligament). In addition, fibrous bands, discrete from the capsule, may form extracapsular ligaments (such as the costoclavicular ligament). In some joints, there are intracapsular ligaments (for instance, the ligament of the head of the femur), which are covered by synovial membrane. Tendons sometimes fuse with the capsule (as in the rotator cuff) or they may run within the joint, covered by synovial membrane, before reaching their bony attachment (e.g. biceps brachii at the shoulder joint; Fig. 1.24).


d
m
la
pr
Articular cartilage
Synovial cavity
Collateral ligaments

Fig. 1.23 Coronal section through a metacarpophalangeal joint, a synovial joint. The collateral ligaments are thickenings of the joint capsule.


Scapular spine (cut)
Coracoid process
Joint capsule
s
m
la
i
Tendon of long head of biceps brachii
Head of humerus

Fig. 1.24 Removal of part of the shoulder joint capsule reveals the intracapsular but extrasynovial tendon of the long head of biceps brachii.

Fluid-containing sacs of synovial membrane called bursae (Fig. 1.25) separate some tendons and muscles from other structures. Bursae, which lie close to joints, may communicate with the cavity of the joint through a small opening in the capsule (as does the subscapularis bursa).

In some joints (e.g. knee) a disc of cartilage is interposed between the articular cartilage covering the bone ends (Fig. 1.26). This provides a matched shape for each bone end, thus allowing freer movement without compromising stability. In addition, different types of movement are permitted in each half of the joint.

Stability varies considerably from one synovial joint to another, as several factors limit excessive movement and contribute to the stability of the joint. These include the shape of the articulating surfaces, the strength of the capsule and associated ligaments, the tone of the surrounding muscles and, where present, intra-articular discs and ligaments. At the hip joint, the ligaments and the shape of the bones provide the main stability, whereas the tone of the surrounding muscles is more important in stabilizing the shoulder joint. Lack of stability associated with muscle weakness or trauma may result in dislocation, so that the cartilage-covered surfaces may no longer make contact. Dislocation may damage adjacent blood vessels and nerves.

Joints, particularly their capsules, receive a rich sensory innervation derived from the nerves supplying the muscles that act on the joint. For instance, the axillary nerve supplies the shoulder joint and deltoid.



Fig. 1.25 Sagittal section through the elbow joint. The olecranon bursa does not communicate with the joint cavity.



Fig. 1.26 Disarticulated knee joint to show the menisci.

Blood vessels around joints frequently take part in rich anastomoses, which allow alternative pathways for blood flow when the joint has moved to a different position and ensure an adequate supply to the synovial membrane (such as in the knee joint; Fig. 1.27).

Serous membranes and cavities

Pericardium, pleura and peritoneum comprise the serous membranes lining the cavities that separate the heart, lungs and abdominal viscera, respectively, from their surrounding structures. Where the membrane lines the outer wall of the cavity it is called parietal and has somatic sensory innervation, and where it covers the appropriate organ it is called visceral with no somatic innervation. The spread of disease to involve parietal membranes usually provokes pain felt at a site which the patient can identify precisely. The parietal and visceral parts are in continuity around the root of the viscus and are separated from each other by a cavity, which normally contains only a thin film of serous fluid. The membranes are in close contact but are lubricated by the intervening fluid, which permits movement between the viscus and its surroundings (Fig. 1.28).



Fig. 1.27 Branches of the popliteal artery anastomose around the knee joint.



Fig. 1.28 Transverse section through the thorax at the level of T5 showing the right pleural cavity. Superior aspect.

Blood vessels

Blood vessels convey blood around the body and are classified into three main types: arteries, capillaries and veins.

Arteries are relatively thick-walled vessels, which convey blood in a branching system of decreasing calibre away from the heart (Fig. 1.31). Some arteries are named after the region through which they pass (such as the femoral artery), while others are named according to the structures they supply (for instance, the renal artery). The largest vessels, such as the aorta, have elastic walls and therefore are called elastic arteries. They give rise to arteries whose walls are more muscular (muscular arteries), such as the radial artery in the forearm. A particularly thick smooth muscle coat is also a feature of the walls of the microscopic arterioles. The tone of arteriolar smooth muscle is under the control of the autonomic nervous system and hormones and is an important factor in the maintenance of pressure in the arterial system. In general, there are few alternative pathways for arterial blood to reach its destination. However, in some regions (e.g. joints and at the base of the brain), arterial supply is provided by more than one vessel (Fig. 1.27). Such arteries may communicate directly with each other at sites known as arterial anastomoses. Arterial pulses may be felt easily in superficial arteries, such as the radial artery at the wrist. Identifying pulses in deeply located arteries, such as the abdominal aorta, may require firm pressure.

Capillaries link the smallest arteries (arterioles) and the smallest veins (venules) and convey blood at low pressure through the tissues. Collectively, these thin-walled microscopic vessels have a very extensive surface area, facilitating gaseous and metabolic exchange between the blood and tissues.

Veins carry blood at low pressure from the capillary bed back to the heart (Fig. 1.32). They may be deep (accompanying arteries) or superficial (lying in the superficial fascia) (Fig. 1.29) and are usually linked by venous anastomoses. Veins accompanying arteries are often arranged as several interconnecting vessels called venae comitantes. In the limbs, the deep veins can be compressed by local muscular action, thus assisting venous return. Many veins (excluding the venae cavae, those draining viscera and those within the cranium) contain unidirectional valves, which direct the flow of blood towards the heart (Fig. 1.30). Damage to these valves can lead to dilated veins known as varicose. The venous pattern is often variable, and numerous anastomotic connections provide alternative pathways for venous return. In some regions, numerous intercommunicating veins form meshworks called plexuses (such as the pelvic venous plexus). In the cranial cavity, venous blood is carried in special vessels formed by the dura mater lining the interior of the skull. These dural sinuses receive blood from the brain.



Fig. 1.29 Multilevel ‘step’ dissection through the right leg showing the blood vessels.



Fig. 1.30 Portion of saphenous vein opened longitudinally and in cross-section.


S
R
L
I
Superficial temporal
Maxillary
Facial
Lingual
Superior thyroid
Right common carotid
Right vertebral
Right subclavian
Axillary
Profunda brachii
Brachial
Radial
Gonadal
Interosseous
Ulnar
Superficial palmar arch
Femoral
Popliteal
Posterior tibial
Anterior tibial
Medial plantar
Plantar arch
Posterior auricular
Occipital
External carotid
Internal carotid
Left common carotid
Left subclavian
Brachiocephalic
Right coronary
Thoracic aorta
Coeliac
Renal
Superior mesenteric
Abdominal aorta
Inferior mesenteric
Common iliac
Internal iliac
External iliac
Profunda femoris
Fibular
Lateral plantar
Dorsalis pedis

Fig. 1.31 Principal systemic arteries.


S
R
L
I
Superficial temporal
Facial
Left external jugular
Right internal jugular
Left internal jugular
Right vertebral
Subclavian
Left brachiocephalic
Axillary
Right brachiocephalic
Cephalic
Superior vena cava
Hepatic
Inferior vena cava
Basilic
Renal
Gonadal
Venae comitantes
Common iliac
Internal iliac
External iliac
Dorsal arch
Femoral
Great saphenous
Popliteal
Small saphenous
Venae comitantes
Dorsal arch
Deep veins
Superficial veins

Fig. 1.32 Principal systemic veins.


Lymph node
Efferent and afferent lymphatics
S
la
m
I

Fig. 1.33 Inguinal lymph node.

Lymphatic vessels and nodes

Tissue fluid is collected by microscopic open-ended channels called lymphatics. From a particular region or organ, these valved lymphatic vessels drain into aggregations of lymphoid tissue (called lymph nodes; Fig. 1.33), which filter lymph. Groups of lymph nodes are often found close to an organ (e.g. hilar nodes) or at the root of a limb (e.g. axillary lymph nodes). Ultimately, lymph drains into the venous system in the root of the neck through larger lymph channels called the thoracic duct and the right lymphatic trunk (Fig. 1.34).

Because they filter the fluid passing through them, lymph nodes may become involved in the spread of infection or malignancy (e.g. cancer). Thus the surgeon removing a cancerous organ may also excise the lymph nodes draining that organ.


Right lymphatic trunk & tributaries
Thoracic duct & tributaries
S
R
L
I
Cervical nodes
Subclavian trunk
Jugular trunk
Axillary nodes
Right lymphatic trunk
Thoracic duct
Cisterna chyli
Aortic nodes
Iliac nodes
Inguinal nodes

Fig. 1.34 The main lymphatic nodes and vessels.

Nervous tissue

Nervous tissue contains two types of cell: neurones and neuroglia. The neurone is the functional unit responsible for the conduction of nerve impulses. It consists of a cell body and its associated processes. One type of process, of which there is only one per neurone, is the axon. This may be relatively short but sometimes is very long, as in peripheral nerves, where axons comprise the individual nerve fibres. The neuroglia undertake supporting roles and include Schwann cells, which provide the myelin sheaths around axons. These sheaths insulate the axons, increasing their speeds of conduction.

The nervous system consists of central and peripheral parts. The brain and spinal cord comprise the central nervous system.

The peripheral nervous system consists of spinal, cranial and autonomic nerves, and their associated ganglia. Bundles of nerve cell processes and their supporting Schwann cells form peripheral nerves. Several nerve processes, bound together by connective tissue, form a nerve bundle; numerous bundles, surrounded by a fibrous sheath (epineurium), constitute the complete peripheral nerve. Nerve cell bodies also form part of the peripheral nervous system and are usually grouped together into ganglia. The peripheral nervous system is divided into somatic and autonomic parts.

Somatic nerves

In general, the somatic nerves innervate skeletal muscle and transmit sensation from all parts of the body except the viscera. A total of 12 pairs of cranial nerves are attached to the brain and are named: olfactory (I); optic (II); oculomotor (III); trochlear (IV); trigeminal (V); abducens (VI); facial (VII); vestibulocochlear (VIII); glossopharyngeal (IX); vagus (X); accessory (XI); hypoglossal (XII). Most of these nerves supply structures in the head and neck, but the vagus nerve also supplies thoracic and abdominal viscera.

Spinal nerves are also in pairs and each is attached to a specific segment of the spinal cord by anterior and posterior roots. There are eight cervical (C1–C8); 12 thoracic (T1–T12); five lumbar (L1–L5); five sacral (S1–S5); and one or two coccygeal (Co) spinal nerves (Fig. 1.35).


S
A
P
I
First cervical
Cervical plexus (C2–C4)
Brachial plexus (C5–T1)
Median
Ulnar
Radial
Musculocutaneous
T2–T12
Lumbar plexus (L1–L4)
First lumbar
Sacral plexus (L4–S4)
Fifth sacral and first coccygeal
Femoral
Obturator
Sciatic
Common fibular
Tibial
Saphenous
Deep fibular
Superficial fibular
Medial plantar
Lateral plantar

Fig. 1.35 Lateral view of the distribution of the anterior rami of the spinal nerves.

Thoracic spinal nerves illustrate the typical segmental pattern of distribution to the body wall (Fig. 1.36). The area of skin supplied by one spinal (or cranial) nerve is called a dermatome (Figs 1.37 & 1.38). In the trunk the dermatome pattern involves substantial overlap between adjacent areas. Similarly, all the muscles supplied by a single spinal (or cranial) nerve comprise a myotome.


A
R
L
P
Cutaneous branches
Muscle branch
Anterior root
Sympathetic trunk
Anterior ramus
Posterior ramus
Spinal cord
Posterior root
Rami communicantes

Fig. 1.36 Course and distribution of a typical thoracic spinal nerve. Inferior aspect.


S
R
L
I
C4
T2
T3
T4
T5
T6
T7
T8
T9
T10
T11
T12
L1
Cervical
Thoracic
Lumbar

Fig. 1.37 Dermatomes of the trunk.


S
R
L
I
S
L
R
I
Cervical
Thoracic
Lumbar
Sacral

Fig. 1.38 Dermatomes of the limbs.

The regular pattern of innervation in the trunk is modified in the limbs, each being supplied by several spinal nerves through a complex network, a plexus (such as the brachial plexus of the upper limb; Fig. 1.39). Plexus formation modifies the pattern of myotomes so that spinal cord segments innervate muscles according to their prime actions. For example, flexors of the elbow joint are supplied by the spinal cord segments C5 and C6. Sensory cell bodies are located in ganglia on peripheral nerves near the central nervous system (for instance, trigeminal ganglion, posterior root ganglia). However, the cell bodies of somatic motor nerves are located in the central nervous system.

Autonomic nerves

The autonomic nervous system innervates smooth and cardiac muscle and glands. It is divided into two parts: sympathetic and parasympathetic, whose effects for the most part are antagonistic (e.g. sympathetic stimulation increases while parasympathetic stimulation reduces heart rate). In both sympathetic and parasympathetic components, preganglionic myelinated axons leave the central nervous system and synapse on neurones in peripheral ganglia distributed throughout the body. The postganglionic axons that pass to the effector organs are nonmyelinated. Autonomic sensory fibres accompany autonomic efferent fibres in peripheral nerves, but their cell bodies are located in the posterior root ganglia in company with somatic sensory neurones. Pain from diseased organs, called visceral pain, which is usually poorly localized, is transmitted by autonomic sensory nerves.

The parts of the central nervous system from which the autonomic nerves emerge differ for the sympathetic and parasympathetic components (Fig. 1.40).

Sympathetic nerves Preganglionic sympathetic fibres leave the central nervous system in the spinal nerves of all the thoracic and the upper two lumbar segments (thoracolumbar outflow) and enter the ganglionated sympathetic trunks via white rami communicantes. The two sympathetic trunks lie on either side of the vertebral column and extend throughout most of its length. Each trunk consists of sympathetic ganglia and interconnecting nerve trunks.

Unmyelinated postganglionic axons destined for the blood vessels and sweat glands of the body wall, including the limbs, leave the ganglia by grey rami communicantes and are distributed by the spinal nerves. Special visceral branches pass directly from the trunks to reach the appropriate organ.

Postganglionic sympathetic nerve fibres are often conveyed to their destinations as plexuses intimately related to the walls of arteries.



Fig. 1.39 The axilla has been dissected to show the brachial plexus.

Parasympathetic nerves In the parasympathetic system, myelinated preganglionic fibres leave the central nervous system as part of cranial nerves III, VII, IX and X and as part of sacral spinal nerves S2, S3 and S4, to form the craniosacral autonomic outflow. These preganglionic fibres synapse in ganglia lying close to or in the wall of the target organ. Relatively short nonmyelinated postganglionic axons emerge from these ganglia to innervate the appropriate tissue. In the head there are four paired ganglia (ciliary, pterygopalatine, submandibular and otic) that receive preganglionic parasympathetic fibres from cranial nerves III, VII and IX. The postganglionic fibres from these ganglia supply the eye, and lacrimal, nasal and salivary glands. Preganglionic fibres from the vagus (X) nerve synapse with postganglionic neurones that innervate cervical, thoracic and abdominal viscera. Preganglionic fibres from the sacral nerves (pelvic splanchnic nerves or nervi erigentes) supply the pelvic organs. The parasympathetic ganglia associated with the vagus and sacral nerves usually comprise small clusters of cells in the walls of the innervated organs (Fig. 1.40).


Outflow from CNS
Intermediate ganglion or plexus
Target sites
III
Ciliary ganglion
Sphincter pupillae and ciliary muscle of eye
VII
Pterygopalatine ganglion
Lacrimal and nasal glands
Submandibular ganglion
Submandibular and sublingual glands
IX
Otic ganglion
Parotid gland
X
Pulmonary plexus
Lungs
Cardiac plexus
Heart
Plexus in gut wall as far as splenic flexure
Gut as far as splenic flexure
T1
L2
Sympathetic trunk
Arteries
Head and neck
Cardiac and pulmonary branches
Heart and lungs
Spinal nerves
Body wall and limbs
Thoracic splanchnic nerves
Coeliac and mesenteric plexuses
Gut wall as far as splenic flexure
Hypogastric nerves
Gut wall beyond splenic flexure and pelvic viscera
S2
S3
S4
Plexus in gut wall beyond splenic flexure and pelvic viscera
Gut wall beyond splenic flexure
Pelvic and perineal viscera
Parasympathetic nerves (craniosacral outflow)
Sympathetic nerves (thoracolumbar outflow)

Fig. 1.40 Pattern of innervation in the parasympathetic and sympathetic autonomic nervous systems.

Chapter 2

THORAX

Introduction 26
Skeleton of the Thorax 28
  Ribs 28
  Sternum 29
Thoracic Wall 30
  Skin 30
  Breast 30
  Muscles 31
  Intercostal spaces 32
  Intercostal muscles 33
  Intercostal vessels and nerves 34
Pleura 36
  Parietal pleura 36
  Visceral pleura 37
Lungs 38
  Fissures 39
  Surfaces, borders and relations 39
Bronchi 42
  Pulmonary vessels 42
  Autonomic nerves 42
Mediastinum 43
Pericardium 44
  Fibrous pericardium 44
  Serous pericardium 44
Heart 45
  External features 45
  Chambers and valves 47
  Blood vessels 53
  Conducting system 56
Mediastinal Structures 58
  Brachiocephalic veins 58
  Superior vena cava 58
  Arch of aorta and branches 58
  Phrenic nerves 60
  Trachea 60
  Oesophagus 62
  Vagus (X) nerves 62
  Descending thoracic aorta and branches 62
  Thoracic duct 63
  Azygos venous system 63
  Thoracic sympathetic trunk 64
Exam Skills 65
Clinical Case Skills 66
Observation Skills 67

Introduction

The thorax is the region of the trunk that includes the sternum, costal cartilages, ribs and thoracic vertebrae, together with the structures they enclose. Superiorly, the thorax is limited by the upper surfaces of the first ribs and their costal cartilages, the manubrium of the sternum and the first thoracic vertebra. The space bounded by these structures is the superior thoracic aperture (thoracic inlet) (Fig. 2.1), which allows structures to pass between the root of the neck and the thorax. Space-occupying tumours in this location may compress adjacent structures, leading to the clinical condition called, confusingly, thoracic outlet syndrome. Inferiorly, the cavity of the thorax is separated from the abdominal contents by a fibromuscular sheet called the diaphragm. The oesophagus and other intrathoracic structures pass through the diaphragm to gain or leave the abdomen. Since the diaphragm is convex superiorly, some of the organs within the abdomen are covered by the lower ribs and costal cartilages.

The ribs, costal cartilages and sternum form a semi-rigid framework that provides attachment for several muscles; some connect adjacent ribs and costal cartilages, others attach to the pectoral


First rib
First and second costal cartilages
First thoracic vertebra
Superior thoracic aperture
Manubrium
Manubriosternal joint
P
R
L
A

Fig. 2.1 The boundaries of the superior thoracic aperture (pink line).


Trachea
Right main bronchus
Left main bronchus
Lobes of left lung
Lobes of right lung
Xiphoid process
Costal margin
S
R
L
I

Fig. 2.2 The trachea, bronchi and lungs.

girdle or humerus or descend from the thorax to contribute to the musculature of the abdominal wall. The medial ends of the clavicles articulate with the upper border of the manubrium and flank the jugular (suprasternal) notch. The manubrium articulates with the body of the sternum at the manubriosternal joint (sternal angle, angle of Louis), which usually forms a horizontal ridge. This is a useful landmark during clinical examination because the second costal cartilages meet the sternum at this level. It is normal practice to count ribs starting at the second costal cartilages, as the first ribs are obscured by the clavicles. Inferiorly, the thoracic wall is limited by the costal margin, which is formed by the costal cartilages of the lower ribs. The costal margin extends upwards and medially as far as the lower end of the sternum and forms the upper boundary of the abdominal wall. The inferior portion of the sternum, the xiphoid process, can usually be identified in the midline between the costal margins (subcostal angle). The space between adjacent ribs and costal cartilages is occupied by intercostal muscles, which are active during respiratory movements of the thoracic wall. Intercostal vessels and nerves run between these muscles in each space and give branches to adjacent tissues and the overlying skin. In both sexes, the nipples are surface features, the anatomical locations of which vary depending upon the build of the individual. The glandular components of the breast lie deep to the nipple, embedded in the fat of the subcutaneous tissues that cover the muscles of the chest wall. Posteriorly, the upper ribs are covered by the scapulae and their muscles.

The space contained within the thoracic wall is occupied by several important organs. Some of these are confined to the thorax (e.g. heart), while others traverse the region, passing from the neck into the abdomen (e.g. oesophagus). On each side, the lung occupies a large proportion of the thoracic cavity (Fig. 2.2) and is surrounded by a serous sac called the pleura. The pleura encloses a cavity (pleural cavity), which usually contains a thin film of serous fluid enabling the lungs and thoracic wall to move freely over one another. Each pleural cavity is separated from its neighbour by a midline partition called the mediastinum. The mediastinum is the term used to describe all the structures that occupy this central portion, including the heart and its great vessels (Figs 2.3 & 2.4) and the intrathoracic parts of the trachea and oesophagus.


Right common carotid
Right subclavian
Brachiocephalic trunk
Right pulmonary
Ascending aorta
Diaphragm
Left common carotid
Left subclavian
Arch of aorta
Left pulmonary
Descending thoracic aorta
Pulmonary trunk
Heart
S
R
L
I

Fig. 2.3 The heart and great arteries.


Right internal jugular
Right subclavian
Right brachiocephalic
Superior vena cava
Right pulmonary
Left internal jugular
Left subclavian
Left brachiocephalic
Left pulmonary
Inferior vena cava
S
R
L
I

Fig. 2.4 The heart and great veins.

Skeleton of the Thorax

The skeleton of the thorax consists of 12 thoracic vertebrae, the 12 pairs of ribs and their costal cartilages, and the sternum (Fig. 2.5). Structures in continuity between the root of the neck and the upper part of the thoracic cavity pass through the superior thoracic aperture (thoracic inlet), which is bounded by the first thoracic vertebral body, the first pair of ribs and costal cartilages and the upper border of the sternum. The inferior thoracic aperture (thoracic outlet), through which structures pass between the thoracic and abdominal cavities, is formed by the twelfth thoracic vertebral body, the twelfth and eleventh ribs and the costal margin (the fused costal cartilages of the seventh to the tenth ribs inclusive).

Ribs

Although the ribs differ in size and shape, most (2–9 inclusive) have features in common and are described as typical ribs (Fig. 2.6). Each typical rib consists of a head, neck, tubercle, shaft, upper and lower borders and inner and outer surfaces. The heads of the ribs are those parts that articulate with the thoracic vertebral bodies. The lower part of the head forms a synovial joint with its own vertebral body, while the upper part articulates with the vertebra above. The intermediate part of the head lies against the intervertebral disc. The neck of the rib connects the head and the tubercle and lies in front of the transverse process. The tubercle of the rib faces posteriorly and the medial part of its surface forms a synovial joint with the articular facet on the transverse process of the corresponding vertebra. The shaft forms the remainder of the rib and ends anteriorly at a shallow depression, which receives the costal cartilage. Passing laterally from the tubercle, the shaft slopes downwards and backwards before turning forwards and outwards to form the angle. Lateral to the angle, the shaft possesses a sharp lower border, which bounds the costal groove.

The first rib is atypical. Its head possesses an articular facet solely for its own vertebral body. The shaft is short and broad and has superior and inferior surfaces. In addition, its superior surface carries a ridge that forms a projection on the inner border of the rib, the scalene tubercle, to which is attached the scalenus anterior. Two grooves lie across the shaft, one in front of the ridge (for the subclavian vein) and the other behind (for the subclavian artery and lowest trunk of the brachial plexus). The tenth, eleventh and twelfth ribs are also atypical, in that each head possesses a single facet and the rib is usually devoid of a tubercle or an angle.

Costal cartilages

All ribs possess costal cartilages, and those of the upper seven pairs (true ribs) articulate with the sides of the sternum. Pairs 8–12 (false ribs) fall short of the sternum. These articulate with the



Fig. 2.5 Articulated bones of the thorax showing the relationships between the vertebral column, ribs, costal cartilages and sternum.

cartilage immediately above, while 11 and 12 (floating ribs) are pointed and end freely in the muscle of the abdominal wall.

Sternum

The sternum is a flat bone and consists of the manubrium, the body (Fig. 2.7) and the xiphoid process. The manubrium articulates with the medial end of each clavicle at the sternoclavicular joint and with the first costal cartilage. Its upper margin includes the jugular notch, which forms part of the superior thoracic aperture. A palpable secondary cartilaginous joint (the manubriosternal joint) unites the manubrium and body and forms a useful guide to the second costal cartilage, which abuts the sternum at the lateral margin of the joint. The lateral margins of the body of the sternum are indented by the medial ends of the second to the seventh costal cartilages. The xiphoid process lies in the subcostal angle and projects downwards and backwards from the body of the sternum.


Neck
Head
Tubercle
Scalene tubercle
Angle
Shaft
Shaft

Fig. 2.6 Superior view of the right first, seventh and twelfth ribs showing their surface features and relative sizes.


Manubrium
Suprasternal notch
S
R
L
I
Articular surface for sternoclavicular joint
Manubriosternal joint
Body of sternum
Indentations for costal cartilages

Fig. 2.7 The manubrium and the body of the sternum. The xiphoid process is absent.

Thoracic Wall

Skin

The skin covering the thorax receives its nerve supply from lower cervical and upper thoracic spinal nerves. Above the level of the manubriosternal joint, C4 gives cutaneous innervation, while thoracic nerves T2–T11 provide the dermatomes for the remainder of the thoracic wall. The first thoracic nerve does not contribute to the cutaneous nerve supply of the thorax but innervates some of the skin of the upper limb (Figs 1.35 & 3.6).

Breast

The breast (Fig. 2.8) consists of glandular tissue and a quantity of fat embedded in the subcutaneous tissue of the anterior chest wall. In the male and immature female, the gland is rudimentary. Although the size and shape of the breast in the adult female vary, the base (the part lying on the deep fascia covering pectoralis major, serratus anterior and rectus abdominis) is constant in position. In the adult female, the base is roughly circular and extends between the second and sixth ribs. Medially, the gland overlies the lateral border of the sternum. Part of the breast extends upwards and laterally and reaches the anterior fold of the axilla. This is the axillary tail (process) and is the only part of the breast to penetrate beneath the deep fascia. During clinical palpation of the breast it is essential that the axillary tail is included as part of the physical examination.

The glandular elements consist of 15–20 lobes arranged radially, each draining into a lactiferous duct. These ducts open independently onto the surface of the nipple. The nipple is surrounded by an area of pink skin, the areola, which may develop brown pigmentation during pregnancy.

The gland is traversed by fibrous septa (ligaments of Astley Cooper) (Fig. 2.8), which subdivide the lobes and loosely attach the skin of the breast to the deep fascia covering the chest wall. In certain types of breast carcinoma, these fibrous septa may produce characteristic dimpling of the skin over the lesion. Normally, the breast is freely mobile over the underlying muscles. However, lack of mobility when pectoralis major is contracted indicates that breast pathology has fixed the gland to the underlying chest wall muscles.

Blood supply

The fat and glandular elements of the breast receive blood from arteries that also supply the deeper structures of the chest wall. These vessels include perforating branches from the internal thoracic artery (internal mammary artery) and the second, third and fourth intercostal arteries. The lateral thoracic and thoracoacromial arteries arising from the axillary artery also supply the breast. The gland is drained by veins that accompany the arteries.

Lymph drainage

Within the substance of the breast, the lymphatic vessels form a system of interconnecting channels that collect lymph from all parts of the organ. The superior and lateral aspects of the breast usually drain into central and apical axillary nodes via infraclavicular and pectoral nodes. It is therefore important to palpate axillary lymph nodes in suspected cases of malignant breast disease. The medial and inferior parts of the breast drain deeply into glands along the internal thoracic vessels and thence via the bronchomediastinal lymph trunk into the confluence of lymphatic



Fig. 2.8 Sagittal section through the right breast and underlying chest wall. In this dissection, the glandular structure of the breast cannot be distinguished.

vessels in the root of the neck (p. 330). Lymphatics may also cross the midline to communicate with vessels in the opposite breast.

Muscles

The outer surfaces of the ribs, costal cartilages and sternum give attachment to muscles involved in movements of the upper limb and the scapula, namely pectoralis major, pectoralis minor and serratus anterior. In addition, the external surfaces of the lower ribs provide attachment for rectus abdominis and the external oblique muscles of the anterior abdominal wall (pp 143, 144).

Pectoralis major

This large fan-shaped muscle (Fig. 2.9) attaches to the clavicle, sternum and upper costal cartilages and forms the bulk of the anterior wall of the axilla. The clavicular head is attached to the anterior surface of the medial half of the clavicle. The sternocostal head is anchored to the manubrium and body of the sternum, and to the upper six costal cartilages. Laterally, both parts of the muscle attach to the humerus along the lateral lip of the intertubercular sulcus (p. 77).

Pectoralis major is supplied by the medial and lateral pectoral nerves from the brachial plexus. Functionally, it is a powerful adductor and flexor of the arm at the shoulder joint and also produces medial rotation of the humerus. When the upper limb is fixed, the sternocostal part may act as an accessory muscle of inspiration by elevating the ribs.

Pectoralis minor

This small muscle (Fig. 2.10) lies deep to pectoralis major and is usually attached to the third, fourth and fifth ribs. The muscle converges on the medial border of the coracoid process of the scapula. Pectoralis minor is supplied by the medial and lateral pectoral nerves and assists in movements of protraction and rotation of the scapula.


Sterno-
cleidomastoid
Deltoid
Clavicle
Clavicular
head
Cephalic
vein
Sterno-
costal
head of
pectoralis
major
Serratus
anterior
S
la
m
I

Fig. 2.9 Pectoralis major, revealed by removal of the skin, the subcutaneous tissue and deep fascia.


Pectoralis
major
(cut)
Axillary
vein
Cephalic
vein
Thoraco-
acromial
artery
Pectoralis
major
(cut)
Pectoralis
minor
Serratus
anterior
S
la
m
I

Fig. 2.10 Pectoralis minor, exposed by removal of pectoralis major.

Serratus anterior

This large muscle lies between the scapula and chest wall and attaches to the lateral aspects of the upper eight ribs (Fig. 2.11), forming part of the medial wall of the axilla. The muscle fibres from the upper four ribs attach to the superior angle and to the costal surface of the medial border of the scapula. The fibres from ribs 5–8 converge on the costal surface of the inferior angle of the scapula.

Innervation is provided by the long thoracic nerve arising in the neck from the upper three roots (C5, C6 & C7) of the brachial plexus. The muscle is a powerful protractor of the scapula and assists trapezius in producing scapular rotation during abduction of the upper limb. In addition, the muscle helps to stabilize the scapula during movements of the upper limb.

Intercostal spaces

The interval between two adjacent ribs is called an intercostal space. On each side of the thorax there are 11 such spaces, numbered from above and occupied by muscles, membranes, nerves and vessels. The number given to each intercostal space and its neurovascular structures corresponds to that of the rib which limits the space superiorly. The nerves and vessels immediately inferior to the twelfth ribs are termed the subcostal nerves and vessels. The intercostal nerves and vessels supply the intercostal


Brachial plexus (cut)
Subclavian vein and artery (cut)
Long thoracic nerve
Clavicle
Second rib
Serratus anterior
Costal margin
S
P
A
I

Fig. 2.11 Serratus anterior seen after removal of the pectoral muscles and displacement of the scapula backwards.


Second rib
External intercostal muscles
Clavicle
External intercostal membranes
Internal intercostal muscles
Costal margin
S
P
A
I

Fig. 2.12 External intercostal muscles, exposed by removal of the upper limb and serratus anterior.

muscles and the parietal pleura deep to each space. Branches from these vessels also supply the overlying muscles of the body wall, the superficial fascia and skin. Most intercostal nerves have cutaneous branches that supply the skin covering the chest and abdominal walls.

Intercostal muscles

There are three layers of intercostal muscles, which lie superficial, intermediate and deep. These are named the external, the internal and the innermost intercostal muscles.

External intercostal muscles

The fibres of the external intercostal muscles slope downwards and forwards from the lower border of one rib to the upper border of the subjacent rib (Fig. 2.12). The muscle extends from the tubercle of the rib posteriorly to the junction of the rib and its costal cartilage anteriorly. Between costal cartilages the muscle fibres are replaced by a thin fascial sheet, the external intercostal membrane, which reaches the lateral border of the sternum (Fig. 2.13).

Internal intercostal muscles

The internal intercostal muscles (Fig. 2.14) lie immediately deep to the external intercostal muscles. The fibres of the two muscles are mutually at right angles, those of the internal intercostal muscles running downwards and backwards from the lower border of one rib to the upper border of the subjacent rib. Anteriorly, each muscle continues between the costal cartilages to reach the lateral border of the sternum (Fig. 2.13). Posteriorly, each


Sternocleido-
mastoid
Perforating branches of internal thoracic arteries
Body of sternum
External intercostal membranes
Subclavian vein
External intercostal muscle
Second rib
Internal intercostal muscles
Xiphoid process
S
R
L
I

Fig. 2.13 External intercostal membranes and the anterior fibres of the internal intercostal muscles.


Clavicle
Second rib
External intercostal muscles (cut)
Internal intercostal muscles
S
A
P
I

Fig. 2.14 Internal intercostal muscles, exposed by removal of the anterior parts of the external intercostal muscles.

muscle extends only to the angles of the ribs, where it is replaced by the internal intercostal membrane, which continues as far as the tubercles of the ribs.

Innermost intercostal muscles

These muscles lie on a plane deep to that of the internal intercostal muscles (Fig. 2.15). They form the lateral part of an incomplete layer of muscle which includes the transversus thoracis (sternocostalis) anteriorly (Fig. 2.16) and subcostalis posteriorly. The innermost intercostal muscles connect the inner surface of each rib to that of its neighbours.

Nerve supply

All the intercostal muscles in a particular intercostal space are supplied by the corresponding intercostal nerve.

Actions

Although the main role of the intercostal muscles is in ventilation of the lungs, it must be emphasized that during normal, quiet breathing, the muscles of the thoracic wall make only a small contribution. Inspiration is usually brought about mainly by the diaphragm, whose descent increases the vertical diameter of the thorax. The transverse and anteroposterior diameters of the thorax are increased, especially in deep inspiration, by the external intercostal muscles, which incline the ribs outwards, upwards and forwards, so that the intercostal spaces are widened. During quiet breathing, expiration is largely due to the ‘elastic’ recoil of the lungs and thoracic wall and involves minimal activity by the intercostal muscles. Even when expiration is ‘forced’, for example during vigorous physical exertion or when coughing, the main muscular effort is provided by the muscles of the abdominal wall rather than the chest wall. However, the internal intercostal muscles contribute to forced expiration by drawing the ribs downwards and inwards, thereby narrowing the intercostal spaces.

Intercostal vessels and nerves

Each intercostal space has a principal artery, vein and nerve, which collectively form the neurovascular bundle (Fig. 2.15). This bundle lies in the neurovascular plane between the internal and innermost intercostal muscles and runs along the upper part of the intercostal space, occupying the costal groove of the rib. Usually, the vein lies superiorly and the nerve inferiorly in the bundle. A collateral nerve and collateral vessels arise posteriorly from the neurovascular bundle and run forwards along the lower border of the intercostal space to supply the intercostal muscles.

Intercostal arteries

Intercostal arteries enter from both anterior and posterior ends of the intercostal space. Anteriorly, the internal thoracic arteries (internal mammary arteries) (Fig. 2.16) arising from the subclavian arteries in the root of the neck (p. 330) provide branches that run laterally to supply the upper six pairs of intercostal spaces. On each side, the lower five spaces receive anterior intercostal arteries from the musculophrenic artery, one of the terminal branches of the internal thoracic artery. These anterior arteries anastomose end-to-end with the posterior intercostal arteries.


External intercostal muscle
Parietal pleura
Internal intercostal muscles (cut)
Innermost intercostal muscles
Intercostal artery
Internal intercostal muscle
Internal intercostal muscle (cut)
External intercostal muscles (cut)
Intercostal nerve
S
A
P
I

Fig. 2.15 Innermost intercostal muscles and intercostal nerves exposed after removing parts of the internal intercostal muscles. In the third intercostal space the innermost intercostal muscle has been removed to expose the parietal pleura.

Posterior intercostal arteries to the lower nine intercostal spaces arise as direct branches from the descending thoracic aorta (Fig. 2.64). For the first and second spaces, the posterior intercostal arteries are derived from the intercostal branch of the costocervical trunk. This trunk arises from the subclavian artery (p. 331) and its intercostal branch enters the thorax by crossing the neck of the first rib. The anastomoses between anterior and posterior intercostal arteries in the lower nine intercostal spaces and between the scapular arteries and posterior intercostals are important because they enable blood to reach the descending aorta when the aortic arch is abnormally narrowed (coarctation of the aorta).

Intercostal veins

Anteriorly, the intercostal veins from the lower five intercostal spaces drain into the musculophrenic veins. The upper six intercostal veins and the musculophrenic veins drain into the internal thoracic veins, which themselves are tributaries of the brachiocephalic veins in the root of the neck. Posteriorly, the intercostal veins drain into the azygos venous system. On the right, those in the lower eight spaces terminate directly in the azygos vein (Fig. 2.64). The veins from the second and third spaces combine into a single vessel, the right superior intercostal vein, which drains into the arch of the azygos vein. The first posterior intercostal vein (supreme intercostal vein) leaves the thorax to terminate in the root of the neck, usually in the right vertebral vein.

On the left, the lower eight posterior intercostal veins enter either the hemiazygos or accessory hemiazygos veins (Fig. 2.65). The left superior intercostal vein drains the second and third spaces and crosses the left side of the arch of the aorta to terminate in the left brachiocephalic vein (Fig. 2.57). As on the right the first posterior intercostal vein (supreme intercostal vein) leaves the thorax to terminate usually in the vertebral, but occasionally in the brachiocephalic, vein.

Intercostal nerves

The intercostal nerves comprise the anterior rami of the upper 11 thoracic spinal nerves. Each intercostal nerve enters the neurovascular plane posteriorly (Fig. 2.65) and gives a collateral branch that supplies the intercostal muscles of the space. Except for the first, each intercostal nerve gives off a lateral cutaneous branch near the midaxillary line, which pierces the overlying muscle (Fig. 1.36). This cutaneous nerve divides into anterior and posterior branches, which supply the adjacent skin. The intercostal nerves of the second to the sixth spaces enter the superficial fascia near the lateral border of the sternum and divide into medial and lateral cutaneous branches.

Most of the fibres of the anterior ramus of the first thoracic spinal nerve join the brachial plexus for distribution to the upper limb (p. 80). The small first intercostal nerve is the collateral branch and supplies only the muscles of the intercostal space, not the overlying skin.

The intercostal nerves of the lower five spaces continue in the neurovascular plane beyond the costal margin to supply the muscles and skin of the abdominal wall (p. 145).





Fig. 2.16 Internal thoracic vessels, revealed by removal of the anterior parts of the intercostal muscles.


Right and left brachiocephalic veins
Internal thoracic vessels
Mediastinum
Musculophrenic vessels
S
R
L
I
Left subclavian artery
Second rib (cut)
Third intercostal nerve
Parietal pleura
Inferior border of left lung
Costodiaphragmatic recess
Costal margin

Fig. 2.17 Removal of the anterior chest wall has exposed the internal thoracic vessels and costal part of the parietal pleura, through which the lungs are visible.

Pleura

The thoracic cavity lies within the walls of the thorax and is separated from the abdominal cavity by the diaphragm. The cavity contains the right and left lungs, each surrounded by a serous membrane called the pleura. Between the lungs is a central partition, the mediastinum, which includes the heart and great vessels, the trachea and the oesophagus. Superiorly, numerous mediastinal structures enter or leave the root of the neck through the superior thoracic aperture (p. 322). Inferiorly, important structures including the aorta, inferior vena cava and oesophagus pass between the mediastinum and the abdomen through openings in the diaphragm (p. 203).

The pleura surrounds the lungs and lines the walls of the thoracic cavity and is subdivided into visceral and parietal parts. The visceral layer covers the surface of the lung and is continuous with the parietal layer around the mediastinal attachment of the lung at the lung root. The parietal layer covers the lateral aspect of the mediastinum, the upper surface of the diaphragm and the inner aspect of the chest wall (Fig. 2.17). Although the parietal and visceral layers are normally in contact, a space, the pleural cavity (Fig. 2.18), exists between them and contains a thin film of serous fluid. The fluid ensures close apposition of the two pleural surfaces and reduces friction during respiratory movements. Injury or disease may produce an accumulation of air (pneumothorax) or fluid (pleural effusion) within the pleural cavity, causing the lung to collapse.

Parietal pleura

The parietal pleura is named according to the surfaces it covers. Thus, the mediastinal pleura conforms to the contours of the structures forming the lateral surface of the mediastinum and is innervated by sensory branches of the phrenic nerve. Inferiorly, the diaphragmatic pleura clothes the upper surface of the diaphragm. The central portion receives sensory branches from each phrenic nerve, while the periphery is innervated by lower intercostal nerves. The pleura covering the inner surface of the thoracic wall is called the costal pleura and is innervated segmentally by the intercostal nerves (Fig. 2.17).

The periphery of the diaphragm slopes steeply downwards towards its attachment to the thoracic wall, creating a narrow gutter, the costodiaphragmatic recess. Within this recess, which is particularly deep laterally and posteriorly, the costal and diaphragmatic parts of the parietal pleura lie in mutual contact.

The parietal pleura extending into the root of the neck is called the cervical pleura and is innervated by the first intercostal nerve. It is applied to the undersurface of a firm fascial layer, the suprapleural membrane, which prevents upward movement of the apex of the lung and pleura during ventilation (Fig. 7.15).

Surface markings of the parietal pleura

Because the parietal pleura is reflected from the thoracic wall onto both the mediastinum and the diaphragm, a line of pleural reflection can be mapped out on the body surface. Traced from its upper limit, approximately 2.5 cm above the medial third of the clavicle, this line descends behind the sternoclavicular joint. This cervical pleura may be accidentally perforated when a central venous line is being placed in the subclavian vein. The pleural reflection line approaches the midline at the level of the manubriosternal joint. On the right, the pleural reflection descends vertically to the level of the sixth costal cartilage, while on the left, the heart displaces the pleura laterally (Fig. 2.17) so that from the fourth to the sixth costal cartilages, the line of reflection lies just lateral to the edge of the sternum. This displacement exposes part of the pericardium underlying the medial ends of the fourth and fifth intercostal spaces. Traced laterally from the sixth costal cartilage, the surface marking is the same on each side, crossing the eighth rib in the midclavicular line and the tenth rib in the midaxillary line.

Posteriorly, the parietal pleura continues horizontally, crosses the twelfth rib 5 cm from the midline and continues medially for a further 2.5 cm. Thus, a small area of parietal pleura lies below the level of the twelfth rib.

Visceral pleura

The visceral pleura (Fig. 2.18) is continuous with the mediastinal parietal pleura around the root of the lung. Structures entering or leaving the hilum of the lung occupy the upper part of this pleural sleeve, the lower part consisting of an empty fold of pleura, the pulmonary ligament (Fig. 2.25). The visceral pleura firmly adheres to the surface of the lung and extends into the depths of the fissures. Unlike the parietal layer, the visceral pleura does not have a somatic innervation.

Surface markings of the visceral pleura

Since the visceral pleura covers the surface of the lung, its surface markings coincide with those of the lung (p. 41).



Fig. 2.18 Transverse section at the level of the fourth thoracic vertebra showing the arch of the aorta and the bifurcation of the trachea. Inferior aspect. (Compare Fig. 2.68.)

Lungs

The two lungs lie in the thoracic cavity and are separated by the structures in the mediastinum (Fig. 2.19). Although the lungs of infants are pink, those of older individuals may have a mottled appearance due to deposits of inhaled carbon. Living lungs are elastic, enabling their volumes to change during ventilation, in contrast to embalmed lungs, which are rigid and often bear the imprints of adjacent structures. Each lung is covered in visceral pleura and is cone-shaped, with the base or diaphragmatic surface directed downwards and the apex upwards. The costal surface is smoothly convex, while the mediastinal surface is irregular and bears the hilum of the organ. Fissures are usually present, and divide each lung into lobes (usually three lobes on the right and two on the left). Most of the lung consists of the peripheral part of the respiratory tract and the associated pulmonary vascular system. Having entered the lung, the bronchi and pulmonary vessels subdivide extensively (Fig. 2.26).


Brachiocephalic trunk
Left common carotid artery
Right brachiocephalic vein
Left brachiocephalic vein
Horizontal fissure (incomplete)
Fibrous pericardium
Lingula
Diaphragm
S
R
L
I

Fig. 2.19 Lungs, after removal of the anterolateral thoracic wall and parietal pleura. In this specimen the lungs overlie more of the mediastinum than is usual.


Lower lobe
Oblique fissure
Upper lobe
S
P
A
I
Apex
Anterior border
Horizontal fissure (incomplete)
Middle lobe
Inferior border
Diaphragmatic surface

Fig. 2.20 Costal surface of the right lung, showing oblique and horizontal fissures and the upper, middle and lower lobes.

Fissures

Although variations occur, each lung is usually divided into upper and lower lobes by an oblique fissure. On the right, the upper lobe is further subdivided by the horizontal fissure (Fig. 2.20), which runs from the anterior border of the lung into the oblique fissure and demarcates the middle lobe. On the left, the horizontal fissure is usually absent and the middle lobe is represented by the lingula (Fig. 2.21).

Surfaces, borders and relations

The costal surface is convex and extends upwards into the cervical part of the pleura to form the apex of the lung, which is closely related to the corresponding subclavian artery and vein. The inferior surface (base) is markedly concave (Figs 2.22 & 2.23), conforming to the upward convexity of the dome of the diaphragm. The costal and diaphragmatic surfaces meet at the sharp inferior border. The anterior border is also sharp and is formed where the costal and mediastinal surfaces are in continuity. In contrast, the posterior border is rounded and rather indistinct.


Anterior border
Upper lobe
S
A
P
I
Apex
Oblique fissure
Lower lobe
Lingula
Diaphragmatic surface

Fig. 2.21 Costal surface of the left lung showing the oblique fissure and upper and lower lobes.


Horizontal fissure (incomplete)
S
la
m
I
Apex
Upper lobe
Anterior border
Middle lobe
Diaphragmatic surface
Inferior border

Fig. 2.22 Right lung, showing its concave inferior surface and sharp anterior and inferior borders.


Anterior border
Apex
S
m
la
I
Costal impression
Costal surface of upper lobe
Cardiac impression
Cardiac notch
Lingula
Diaphragmatic surface

Fig. 2.23 Left lung, showing the cardiac notch and lingula, both of which are particularly obvious in this specimen.

Each lung is attached to the mediastinum by the lung root, the principal components of which are the pulmonary vessels and the bronchi. These structures, accompanied by bronchial vessels, lymphatics and autonomic nerves, enter or leave the lung through the hilum. Usually, two pulmonary veins emerge from each lung, the inferior vein being the lowest structure in the hilum (Figs 2.24 & 2.25). The bronchi and pulmonary arteries are adjacent as they pass through the hilum, and on the left, the main bronchus lies posteroinferior to the pulmonary artery. However, on the right, the main bronchus frequently divides into two branches, the upper and lower lobe bronchi, before reaching the lung, and each bronchus is accompanied by a branch of the pulmonary artery. The hila of both lungs often contain lymph nodes, which are recognizable by their acquired dark coloration (Fig. 2.27).


S
A
P
I
Impression of superior vena cava
Right pulmonary arteries
Anterior border
Oblique fissure
Diaphragmatic surface
Impression of azygos vein
Right main bronchus
Right pulmonary veins
Posterior border
Pulmonary ligament (cut)

Fig. 2.24 Mediastinal surface of the right lung.


S
P
A
I
Impression of aortic arch
Oblique fissure
Left main bronchus
Left pulmonary veins
Pulmonary ligament (cut)
Diaphragmatic surface
Left pumonary artery
Anterior border
Costal surface
Cardiac impression
Lingula

Fig. 2.25 Mediastinal surface of the left lung.

The two lungs have different medial relations. On the right, the anterior part of the mediastinal surface of the lung is related to the right brachiocephalic vein, the superior vena cava and the pericardium covering the right atrium of the heart. Intervening between these structures and the mediastinal pleura is the right phrenic nerve, which descends in front of the hilum to reach the diaphragm. The upper part of the hilum is related to the azygos vein (Fig. 2.24), which arches forwards to terminate in the superior vena cava. The trachea and accompanying right vagus nerve are related to the right upper lobe.

On the left, the mediastinal surface of the lung bears distinct impressions produced by the fibrous pericardium and the heart (Fig. 2.25). The left phrenic nerve is related to the mediastinal pleura and passes in front of the hilum as it descends across the pericardium. The aorta creates an obvious groove (Fig. 2.25) where it arches over the lung root and descends behind the hilum as the descending thoracic aorta.

Surface markings

The apex of each lung rises above the medial third of the clavicle. From here the anterior border of the lung follows the reflection of the parietal pleura, passing behind the sternoclavicular and manubriosternal joints. On the right, the border descends vertically, close to the midline from the level of the second to the sixth costal cartilages (Fig. 2.2). On the left, the heart displaces the lung and parietal pleura so that the pericardium is exposed behind the medial ends of the fourth and fifth intercostal spaces. This location is sometimes used to insert a needle into the pericardial cavity or heart. On both sides, the inferior border of the lung crosses the sixth rib in the midclavicular line, the eighth rib in the midaxillary line and the tenth rib 5 cm from the midline posteriorly. The lower border of the lung lies at a higher level than the line of pleural reflection; this part of the pleural cavity not occupied by lung is called the costodiaphragmatic recess (Fig. 4.105) and may be fluid filled in pleural effusion.



Fig. 2.26 Resin corrosion cast of the lower trachea and the bronchial tree. The amber portions of the specimen relate to the trachea, the main (primary) bronchi and the lobar (secondary) bronchi, while the coloured portions are the segmental (tertiary) bronchi and their branches.

Bronchi

The bifurcation of the trachea in the mediastinum gives rise to the right and left main (principal) bronchi (Fig. 2.26).

The right main bronchus is wider and more steeply inclined than the left (Fig. 2.27). As a consequence, inhaled foreign bodies are more commonly found in the right main bronchus. The main bronchi give rise to lobar (secondary) bronchi, which are confined to their respective lobes. On the right, the upper lobe bronchus arises outside the hilum in the lung root, whereas on the left, the lobar bronchi arise entirely within the lung. In each lobe, further subdivision occurs into segmental (tertiary) bronchi, which are constant in position and supply specific portions of lung called bronchopulmonary segments. Each lobe consists of a definite number of these segments. Within individual segments, the bronchi further subdivide into bronchioles, then respiratory bronchioles, which in turn lead into the alveolar ducts and alveoli. Bronchial arteries derived from the descending thoracic aorta accompany and supply the major bronchi. Venous return from the bronchi is through bronchial veins that terminate in the azygos venous system (p. 63).

Pulmonary vessels

The right and left pulmonary arteries divide into branches that correspond to and accompany the subdivisions of the bronchi within the lungs. The bronchi and pulmonary arteries lie centrally in the bronchopulmonary segments. The arteries ultimately give rise to pulmonary capillaries in the alveolar walls. Oxygenated blood drains from these capillaries into tributaries of the pulmonary veins that occupy intersegmental positions. These vessels empty into two pulmonary veins, which usually emerge separately through each hilum (Figs 2.24 & 2.25) and drain into the left atrium.

Autonomic nerves

The pulmonary plexus, most of which lies behind the lung root, contains both sympathetic and parasympathetic fibres, which accompany the bronchi into the lung. Sympathetic nerves originate in the upper thoracic ganglia of the sympathetic trunk and supply smooth muscle in the walls of the bronchi and pulmonary blood vessels. The parasympathetic fibres are derived from the vagus nerves and supply bronchial smooth muscle and mucous glands.


Superior vena cava
Right lung
Sternum
Ascending aorta
Costal cartilage
Left lung
Pleural cavity
Pericardial cavity
Left main bronchus
Left pulmonary vein
Descending aorta
Azygos vein
A
R
L
P
Right main bronchus
Bifurcation of pulmonary trunk
Lymph node
Oesophagus

Fig. 2.27 Transverse section at the level of the fifth thoracic vertebra showing the bifurcation of the pulmonary trunk. Inferior aspect. (Compare Fig. 2.69.)

Mediastinum

The central part of the thorax between the two pleural cavities contains a group of structures collectively termed the mediastinum. These include the heart and great vessels, the trachea and the oesophagus. The mediastinum extends from the superior thoracic aperture above to the diaphragm below and from the sternum in front to the thoracic vertebral bodies behind (Fig. 2.28). By convention, the mediastinum is divided into superior and inferior parts by an imaginary horizontal plane passing through the manubriosternal joint and the lower part of the fourth thoracic vertebra. The superior mediastinum lies between this plane and the superior thoracic aperture and contains the superior vena cava and its tributaries, the arch of the aorta and its branches and the trachea. Also passing through this region are the oesophagus, the thoracic duct and the right and left vagus and phrenic nerves.

The inferior mediastinum lies between the imaginary plane and the diaphragm and consists of three compartments. The largest of these is the middle mediastinum, containing the heart and its covering of fibrous pericardium. In front of the middle mediastinum lies the anterior mediastinum, consisting of a small amount of fat and the remnants of the thymus gland. Behind the fibrous pericardium lies the posterior mediastinum, traversed by the descending thoracic aorta, the oesophagus, the thoracic duct and the azygos venous system. The sympathetic trunks run alongside the thoracic vertebral bodies.


S
P
A
I
Azygos vein
Oesophagus
Trachea
Brachiocephalic artery
Left brachiocephalic vein
Right pulmonary artery
Lung
Aorta and aortic valve
Sternum
Blood clots in left atrium and right ventricle
Diaphragm

Fig. 2.28 Near-midline sagittal section through the thorax showing some mediastinal structures.

Pericardium

Fibrous pericardium

The fibrous pericardium is a sac of dense connective tissue surrounding the heart. In addition to the heart, it encloses the roots of the great arteries and veins and is covered on its inner surface by serous pericardium (see below). The broad base of the fibrous pericardium is attached to the central tendon of the diaphragm (Fig. 2.29) and is pierced by the inferior vena cava.

Superiorly, the sac fuses with the adventitial layers of the aorta, pulmonary trunk and superior vena cava. On each side, the posterior part of the sac blends with the walls of the pulmonary veins.

The anterior aspect of the fibrous pericardium is related to the anterior parts of the two lungs and the anterior reflections of the pleura. Between the pleural reflections, the pericardium lies close to the body of the sternum and to the medial ends of the adjacent fourth and fifth left costal cartilages and associated intercostal structures.



Fig. 2.29 The fibrous pericardium and phrenic nerves revealed after removal of the lungs.



Fig. 2.30 The fibrous pericardium has been opened to expose the visceral pericardium covering the anterior surface of the heart.

During infancy and childhood, the thymus (most of which lies in the superior mediastinum) is related to the anterior surface of the pericardium, but after puberty, the thymus regresses and is gradually replaced by fat.

Laterally, the pericardium is covered by mediastinal pleura and is crossed by the right and left phrenic nerves as they descend to the diaphragm. These nerves supply sensory fibres to the fibrous pericardium, the parietal serous pericardium and the mediastinal pleura. Most of the blood supply to the fibrous pericardium is provided by the internal thoracic arteries and veins via pericardiacophrenic vessels that accompany the phrenic nerves.

Behind the fibrous pericardium lie the oesophagus, the descending thoracic aorta and the thoracic duct (pp 62, 63).

Serous pericardium

Deep to the fibrous pericardium lies the serous pericardium, consisting of parietal and visceral layers. Between the two layers is the pericardial cavity, a narrow space containing a thin film of serous fluid. The parietal layer lines the inner surface of the fibrous pericardium, to which it is firmly attached. The visceral layer covers the outer surface of the heart and the roots of the great vessels (Fig. 2.30).

These two layers slide freely against each other and are in continuity where the great vessels pierce the fibrous pericardium. The reflections between the parietal and visceral layers form two sleeves. One sleeve surrounds the ascending aorta and pulmonary trunk; the second is more extensive and surrounds the superior and inferior venae cavae and pulmonary veins. The two pericardial sleeves lie adjacent to each other and the narrow intervening channel is called the transverse pericardial sinus (Fig. 2.40). A second sinus lies behind the left atrium of the heart. This is the oblique pericardial sinus, which is limited superiorly by the pericardial reflection around the pulmonary veins and superior vena cava (Fig. 2.35). An accumulation of fluid (e.g. blood) within the pericardial cavity may compromise venous return to the heart and therefore reduce cardiac output (cardiac tamponade).

Heart

External features

The heart, enclosed in pericardium, occupies the middle mediastinum. It is roughly cone-shaped and lies behind the sternum with its base facing posteriorly and its apex projecting inferiorly, anteriorly and to the left, producing the cardiac impression in the left lung.

The heart consists of four chambers, namely the right and left atria and the right and left ventricles (Fig. 2.31). A fat-filled groove, the coronary or atrioventricular sulcus, separates the surfaces of the atria from the ventricles and carries the right and left coronary arteries and the coronary sinus. The right atrium receives the superior and inferior venae cavae and the coronary sinus. The right and left pulmonary veins drain into the left atrium. The right ventricle is continuous with the pulmonary trunk while the left ventricle opens into the ascending aorta.

Borders

It is useful to represent the outline of the heart as a projection onto the anterior chest wall. When represented in this way, the heart has right, inferior and left borders (Fig. 2.32). The right border is formed by the right atrium and runs between the third and sixth right costal cartilages approximately 3 cm from the midline. The inferior border is formed mainly by the right atrium and right ventricle. At its left extremity, the border is completed by that part of the left ventricle which forms the apex of the heart. The inferior border runs from the sixth right costal cartilage approximately 3 cm from the midline to the apex, which usually lies behind the fifth left intercostal space, 6 cm from the midline. In the living, the apex usually produces an impulse (apex beat) palpable on the anterior chest wall. The left ventricle together with the left auricle (left atrial appendage) form the left border of the heart, which slopes upwards and medially from the apex to the second left intercostal space, approximately 3 cm from the midline.



Fig. 2.31 Transverse CT image at the level of the eighth thoracic vertebra. (Compare Fig. 2.72.)



Fig. 2.32 Borders and valves of the heart and their relationships to the anterior chest wall.

Surfaces

Most of the anterior surface of the heart consists of the right atrium and right ventricle (Fig. 2.33). The left ventricle contributes a narrow strip adjacent to the left border of the heart. The anterior surface is completed by the right and left auricles. The coronary sulcus descends more or less vertically on the anterior surface and contains the right coronary artery embedded in fat. The anterior surfaces of the right and left ventricles are separated by the anterior interventricular artery (left anterior descending artery).

Most of the inferior (diaphragmatic) surface of the heart (Fig. 2.34) consists of the two ventricles, the left usually contributing the greater area. The posterior interventricular vessels mark the boundary between these two chambers. The surface is completed by a small portion of the right atrium adjacent to the termination of the inferior vena cava.

The posterior surface or base of the heart (Fig. 2.35) consists mostly of the left atrium together with a small part of the right atrium.


S
R
L
I
Superior vena cava
Fibrous pericardium (cut)
Right atrium and auricle
Right ventricle
Left vagus nerve
Ligamentum arteriosum
Left auricle
Pulmonary trunk
Left ventricle

Fig. 2.33 Anterior surface of the heart.


A
R
L
P
Right ventricle
Posterior inter-ventricular artery and vein
Right atrium
Inferior vena cava
Fibrous pericardium (cut)
Left ventricle
Coronary sulcus
Oesophagus

Fig. 2.34 Inferior surface of the heart. The inferior part of the fibrous pericardium has been removed with the diaphragm.


S
L
R
I
Left pulmonary artery
Left auricle
Oblique pericardial sinus
Left atrium
Coronary sinus
Left ventricle
Superior vena cava
Right pulmonary artery
Right pulmonary veins
Reflection of serous pericardium
Right atrium
Inferior vena cava

Fig. 2.35 The posterior surface of the heart showing the reflection of the serous pericardium and the site of the oblique pericardial sinus.

Chambers and valves

The cavities of the right and left atria are continuous with those of their respective ventricles through the atrioventricular orifices. Each orifice possesses an atrioventricular valve, which prevents backflow of blood from the ventricle into the atrium. The myocardium of the atria is separated from that of the ventricles by connective tissue, which forms a complete fibrous ring around each atrioventricular orifice. Interatrial and interventricular septa separate the cavities of the atria and ventricles. Valves, each with three semilunar cusps, guard the orifices between the right ventricle and pulmonary trunk (pulmonary valve) and the left ventricle and ascending aorta (aortic valve). All these valves close passively in response to differential pressure gradients.

Right atrium

The right atrium receives blood from the superior and inferior venae cavae and from the coronary sinus and cardiac veins, which drain the myocardium. The superior vena cava enters the upper part of the chamber. Adjacent to its termination is a broad triangular prolongation of the atrium, the auricle (atrial appendage), which overlaps the ascending aorta (Fig. 2.36).

Internally, the anterior wall of the right atrium possesses a vertical ridge, the crista terminalis (Fig. 2.36). From the crista, muscular ridges (musculi pectinati) run to the left and extend into the auricle. The posterior (septal) wall is relatively smooth but possesses a well-defined ridge surrounding a shallow depression named the fossa ovalis. This fossa is the site of the foramen ovale, which, in the fetus, allows blood to pass directly from the right to the left atrium. The coronary sinus empties into the chamber close to the atrioventricular orifice. Inferiorly, the right atrium receives the inferior vena cava immediately after the vessel has pierced the central tendon of the diaphragm. A fold called the valve of the inferior vena cava (Fig. 2.36) projects into the chamber and is the remnant of a fetal structure that directed the flow of blood across the right atrium towards the foramen ovale.


Right pulmonary artery
Superior vena cava
S
R
L
I
Aortic sinuses
Pulmonary veins
Right auricle
Crista terminalis (cut)
Musculi pectinati
Fossa ovalis
Inferior vena cava and valve
Orifice of coronary sinus

Fig. 2.36 Interior of the right atrium and auricle, exposed by reflection and excision of part of the anterior atrial wall.

Tricuspid valve

From the right atrium, blood flows into the right ventricle through the right atrioventricular orifice, which is guarded by the tricuspid valve (Fig. 2.37). The valve possesses three cusps, the bases of which attach to the margins of the atrioventricular orifice, while their free borders project into the cavity of the right ventricle (Fig. 2.38), where they are anchored by fibrous strands (chordae tendineae) to the papillary muscles of the ventricle. During ventricular contraction (systole), the papillary muscles pull on the chordae, preventing eversion of the valve cusps and reflux of blood into the atrium. The valve lies in the midline behind the lower part of the body of the sternum (Fig. 2.32) and its sounds are heard best by auscultation over the xiphisternum.

Right ventricle

The right ventricle has the right atrium on its right and the left ventricle both behind and to its left. The chamber forms parts of the anterior and inferior surfaces of the heart and narrows superiorly at the infundibulum, which leads into the pulmonary trunk (Fig. 2.38). The walls of the right ventricle are thicker than those


Ascending aorta
Right auricle
Superior vena cava (opened)
Right ventricular cavity
Cusps of tricuspid valve
Orifice of coronary sinus
S
P
A
I

Fig. 2.37 Tricuspid valve, revealed after removal of the lateral wall of the right atrium.


Ascending aorta
Pulmonary trunk and valve
Right auricle
Infundibulum of right ventricle
Right coronary artery
Cusps of tricuspid valve
Chordae tendineae
Papillary muscle
Ventricular wall (cut)
S
R
L
I

Fig. 2.38 Interior of the right ventricle seen after removal of its anterior wall.

of the right atrium and internally possess numerous muscular ridges called trabeculae carneae (Fig. 2.43). One of these, the moderator band (Fig. 2.54), often bridges the cavity of the chamber, connecting the interventricular septum to the anterior ventricular wall. When present, it carries the right branch of the atrioventricular bundle of conducting tissue (p. 56). Projecting from the ventricular walls into the interior of the chamber are processes of myocardium, the papillary muscles, each attached at its apex to several chordae tendineae. The right ventricle is separated from the left ventricle by the interventricular septum, which is muscular inferiorly and membranous superiorly (Figs 2.43 & 2.46).

Pulmonary valve

The pulmonary orifice lies between the infundibulum and the pulmonary trunk and is guarded by the pulmonary valve (Figs 2.39 & 2.40), which consists of three semilunar cusps. The valve closes during ventricular relaxation (diastole), preventing backflow of blood from the pulmonary trunk into the right ventricle. The valve lies behind the left border of the sternum at the level of the third costal cartilage (Fig. 2.32). Sounds generated by this valve are loudest over the anterior end of the second left intercostal space.


Pulmonary trunk (cut) and sinuses
Cusps of pulmonary valve
Anterior interventricular artery
Interventricular septum
Cusp of tricuspid valve
Inferior surface
S
R
L
I

Fig. 2.39 Ventricular surfaces of the cusps of the pulmonary valve seen after removal of part of the anterior wall of the right ventricle.


Anterior interventricular artery
Pulmonary sinus and valve
Right coronary artery
Right ventricle
A
L
R
P
Left coronary artery
Pulmonary vein
Left atrium
Aortic valve
Superior vena cava
Position of transverse pericardial sinus

Fig. 2.40 Pulmonary and aortic valves seen from above.

Left atrium

The left atrium lies behind the right atrium and forms the base of the heart. It possesses a hook-like auricle (left atrial appendage), which projects forwards to the left of the pulmonary trunk and infundibulum. The chamber receives superior and inferior pulmonary veins from each lung (Fig. 2.35). The four pulmonary veins, together with the two venae cavae, are all enclosed in a sleeve of serous pericardium, forming the superior limit of the oblique pericardial sinus. The left atrium forms the anterior wall of this sinus, which separates the chamber from the fibrous pericardium and oesophagus. Most of the inner surface of the left atrium is smooth (Fig. 2.41), although musculi pectinati are present in the auricle.

Mitral (bicuspid) valve

The left atrium communicates anteroinferiorly with the left ventricle through the left atrioventricular orifice, which is guarded by the mitral valve. This valve possesses two cusps, whose bases attach to the margins of the atrioventricular orifice (Fig. 2.41), while their free borders and cusps are anchored by chordae tendineae to the papillary muscles within the left ventricle (Fig. 2.42). The valve prevents reflux during ventricular contraction. Although it lies in the midline at the level of the fourth costal cartilages (Fig. 2.32), the sounds of the mitral valve are best heard over the apex of the heart.


Ascending aorta
Left auricle (displaced)
Superior vena cava
Cusps of mitral valve
Position of fossa ovalis
Left ventricular cavity
S
L
R
I

Fig. 2.41 Mitral valve and interior of the left atrium and auricle seen after removal of the posterior wall of the chamber.


Anterior interventricular artery
Pulmonary sinus
Ascending aorta
S
A
P
I
Trabeculae carneae
Papillary muscle (cut)
Mitral valve and chordae tendineae
Circumflex artery
Coronary sinus (cut)

Fig. 2.42 Interior of the left ventricle seen after removal of part of its wall.

Left ventricle

From the left atrioventricular orifice, the left ventricle extends forwards and to the left as far as the apex. The thickness of the wall of the chamber is normally three times that of the right ventricle (Fig. 2.43). Internally, there are prominent trabeculae carneae and papillary muscles (Fig. 2.46). The chamber narrows as it passes upwards and to the right behind the infundibulum to form the aortic vestibule (Fig. 2.44), the part of the ventricle that communicates with the ascending aorta through the aortic orifice.

Aortic valve

The aortic valve consists of three semilunar cusps (Fig. 2.45), which prevent backflow of blood from the ascending aorta during ventricular diastole. The valve lies behind the sternum to the left of the midline at the level of the anterior end of the third left intercostal space (Fig. 2.32). However, its sounds are best heard over the medial ends of the first and second right intercostal spaces.


Anterior interventricular artery
Right ventricular wall
S
L
R
I
Left ventricular wall
Papillary muscle
Inter-ventricular septum
Trabeculae carneae
Marginal artery

Fig. 2.43 Section through the heart showing the apical portions of the left and right ventricles.


Anterior interventricular artery
Pulmonary trunk
Superior vena cava
Left auricle
Circumflex artery
S
A
P
I
Inter-ventricular septum
Aortic vestibule
Cusp of mitral valve
Coronary sinus (cut)

Fig. 2.44 Mitral valve and aortic vestibule, exposed by removal of part of the left ventricular wall.

Pulmonary trunk and ascending aorta

The pulmonary trunk and the ascending aorta lie within the fibrous pericardium, enclosed together in a sleeve of serous pericardium anterior to the transverse pericardial sinus (Fig. 2.40). The pulmonary trunk extends upwards and backwards, while the ascending aorta initially lies behind it and passes upwards and forwards, overlapped by the right auricle. At the origin of each vessel are three dilatations or sinuses (Figs 2.39 & 2.45), one immediately above each of the cusps of the pulmonary and aortic valves. When ventricular contraction ceases, blood flows into the sinuses, thus pushing against the cusps and closing the valves. Two of the aortic sinuses give rise to the right and left coronary arteries.

The pulmonary trunk emerges from the pericardium and divides into right and left pulmonary arteries in the concavity of the aortic arch, anterior to the bifurcation of the trachea at the level of the fourth thoracic vertebra. As the ascending aorta pierces the fibrous pericardium, it turns backwards and to the left, becoming the arch of the aorta.

Connecting the aortic arch to the pulmonary trunk (or to the commencement of the left pulmonary artery) is the ligamentum arteriosum (Fig. 2.46), the remnant of the fetal ductus arteriosus which conveyed blood from the pulmonary trunk to the aorta, bypassing the pulmonary circulation. Occasionally, the ductus remains patent after birth, giving rise to serious circulatory abnormalities.




Pulmonary valve and sinus
Left coronary artery
Aortic valve and sinus
Superior vena cava
A
L
R
P
Right coronary artery and its opening
Right auricle

Fig. 2.45 Aortic and pulmonary valves viewed obliquely from above.




Arch of aorta
Left pulmonary artery
Pulmonary trunk
Infundibulum of right ventricle
Mitral valve
Membranous and muscular parts of interventricular septum (cut)
Tricuspid valve
Right ventricle
Left vagus nerve
Left recurrent laryngeal nerve
Ligamentum arteriosum
Anterior interventricular artery (cut)
Papillary muscles
Left ventricular wall
S
R
L
I

Fig. 2.46 Anterior view of the aorta, pulmonary trunk and ligamentum arteriosum. Most of the muscular part of the interventricular septum has been removed to show the interior of the left ventricle.

Blood vessels

The arterial supply to the heart is provided by the right and left coronary arteries, which arise from the ascending aorta just above the aortic valve (Fig. 2.47). They supply the myocardium, including the papillary muscles and conducting tissue. The principal venous return is via the coronary sinus and the cardiac veins.


Pulmonary valve
Left coronary artery
Anterior inter-ventricular artery
Circumflex artery
Left auricle (displaced)
Left superior pulmonary vein
Marginal artery
Right auricle
Right coronary artery
Aortic valve
Superior vena cava
Left atrium
A
L
R
P

Fig. 2.47 Origins of the right and left coronary arteries from the root of the ascending aorta seen from above.

Right coronary artery

This vessel arises from the anterior aspect of the root of the aorta and descends in the anterior coronary sulcus (Figs 2.47 & 2.48). At the inferior border, it gives off a marginal branch, which runs to the left towards the apex of the heart. The right coronary artery continues on the inferior surface in the coronary sulcus (Fig. 2.49) and terminates by anastomosing with the circumflex branch of the left coronary artery. On the inferior surface, the posterior (inferior) interventricular artery arises from the right coronary artery (occasionally the left coronary artery) and runs in the posterior interventricular groove towards the apex. When the posterior interventricular artery arises from the right coronary artery, the heart is described as right dominant. The right coronary artery and its branches supply the anterior surface of the right atrium, the lower part of the left atrium, most of the right ventricle and parts of the left ventricle and interventricular septum (Fig. 2.51B). In addition, branches from this artery usually supply most of the conducting tissue of the heart (p. 56).


Ascending aorta
Pulmonary trunk
Anterior cardiac veins
Right coronary artery
Anterior coronary sulcus
Marginal artery
Great cardiac vein
Fibrous pericardium (cut)
Ventricular branch of coronary artery
Anterior inter-ventricular artery
S
R
L
I

Fig. 2.48 Right and left coronary arteries and their branches on the anterior surface of the heart.

Left coronary artery

This artery takes origin from the posterior aspect of the root of the ascending aorta and runs to the left behind the pulmonary trunk where its major branch, the anterior interventricular artery, arises (Figs 2.47 & 2.50). The latter vessel descends in the anterior interventricular groove towards the apex of the heart. The left coronary artery continues as the circumflex artery in the posterior part of the coronary sulcus and terminates by anastomosing with the right coronary artery. The vessel supplies the posterior wall of the left atrium and auricle, most of the left ventricle and parts of the right ventricle and interventricular septum (Fig. 2.51A).


Marginal artery
Right ventricle
Posterior inter-ventricular artery
A
R
L
P
Right coronary artery
Ventricular branch of left coronary artery
Coronary sulcus
Right atrium
Coronary sinus
Inferior vena cava

Fig. 2.49 Right and left coronary arteries and their branches on the inferior surface of the heart. The posterior interventricular artery is duplicated in this specimen.


Pulmonary trunk
Anterior inter-ventricular artery
Ascending aorta
Superior vena cava
P
L
R
A
Left coronary artery
Left auricle (displaced)
Circumflex artery
Coronary sinus (cut)
Ventricular branches of left coronary artery

Fig. 2.50 Left coronary artery and its branches, viewed from the left.

Coronary sinus and cardiac veins

Most of the venous return from the heart is carried by the coronary sinus, which runs along the posterior part of the coronary sulcus and terminates in the right atrium. The coronary sinus is formed near the left border of the heart by the union of the posterior vein of the left ventricle and the great cardiac vein (Fig. 2.52), which accompanies the anterior interventricular artery. Other veins enter the coronary sinus, including the middle cardiac



Fig. 2.51 (A) Left coronary arteriogram. (B) Right coronary arteriogram. *(From Weir J, Abrahams PH, Spratt JD, Salkowski LR. Imaging Atlas of Human Anatomy. 4th edn. 2011:89–122. ©Elsevier.)*


Posterior vein of left ventricle
Great cardiac vein
Left auricle
Left pulmonary veins
S
A
P
I
Ventricular branch of left coronary artery
Oblique vein of left atrium
Coronary sulcus
Coronary sinus

Fig. 2.52 Oblique view of the coronary sinus lying in the coronary sulcus.

vein (Fig. 2.53), which accompanies the posterior interventricular artery. Some cardiac veins enter the right atrium independently (Fig. 2.48).

Conducting system

Coordinated contraction of the myocardium is controlled by specialized conducting tissues, consisting of the sinuatrial (SA) node, the atrioventricular (AV) node, the atrioventricular bundle (of His) and its right and left branches (Fig. 2.54).

The SA node lies in the anterior wall of the right atrium close to the termination of the superior vena cava. It occupies part of the root of the auricle and the upper end of the sulcus terminalis. Numerous autonomic nerves supply the node and modify its rate of discharge. The SA node usually receives blood from an atrial branch of either the right or left coronary artery. From the SA node the cardiac excitation wave passes through the atrial myocardium to reach the AV node.

The AV node lies in the interatrial septum anterosuperior to the termination of the coronary sinus. It is continuous with the atrioventricular bundle, which passes through the fibrous ring separating the atria and ventricles. The bundle gains the upper part of the interventricular septum and promptly divides into right and


Oblique vein of left atrium
Right pulmonary artery and vein
P
L
R
A
Coronary sulcus
Inferior vena cava
Coronary sinus and termination
Right atrium
Right coronary artery
Left ventricle
Middle cardiac veins

Fig. 2.53 Posteroinferior view of the termination of the coronary sinus in the right atrium.

left branches. The AV node and bundle are supplied by branches of the posterior interventricular artery. Interruption of the arterial supply to the conducting tissues may result in cardiac arrhythmias.

Lying beneath the endocardium, the right branch of the atrioventricular bundle descends in the interventricular septum and often passes in the moderator band (Fig. 2.55) to ramify within the anterior wall of the right ventricle. The left branch runs on the left side of the interventricular septum. Both branches divide repeatedly at the ventricular apices and spread out into the myocardium of the respective ventricles.


S
R
L
I
Superior vena cava
Sinuatrial node
Fossa ovalis
Orifice of coronary sinus
Atrioventricular node and bundle
Tricuspid valve
Right bundle branch
Moderator band
Interventricular septum
Left bundle branch

Fig. 2.54 Location of the conducting tissues.


Ascending aorta and right coronary artery
Cusp of tricuspid valve
Chordae tendineae
S
R
L
I
Infundi-bulum
Right ventricular wall (cut)
Inter-ventricular septum
Moderator band

Fig. 2.55 Moderator band, seen through a window cut in the anterior wall of the right ventricle.

Mediastinal Structures

Brachiocephalic veins

On each side, the brachiocephalic vein is formed in the root of the neck by the union of the internal jugular and subclavian veins. At its origin, the vein lies behind the sternoclavicular joint and in front of the first part of the subclavian artery.

The right brachiocephalic vein runs a short vertical course in the superior mediastinum to unite with the left brachiocephalic vein (Fig. 2.56) behind the medial end of the first right costal cartilage. It receives the right vertebral and internal thoracic veins, together with the right jugular and subclavian lymph trunks and the right lymph duct. The vessel is accompanied by the right phrenic nerve.

The left brachiocephalic vein enters the thorax and runs obliquely to the right, passing behind the manubrium. The vessel lies in front of the origin from the arch of the aorta of the left common carotid artery and the brachiocephalic trunk. At its commencement, the vein is joined by the termination of the thoracic duct and, along its course, receives the left vertebral, internal thoracic and superior intercostal veins and, usually, the inferior thyroid veins.

Superior vena cava

Formed by the union of the two brachiocephalic veins, this large vessel descends vertically (Fig. 2.56) and terminates in the right atrium of the heart. It lies to the right of the ascending aorta and to the left of the right phrenic nerve and receives the azygos vein before piercing the fibrous pericardium.

Arch of aorta and branches

The arch of the aorta lies within the superior mediastinum, in continuity with the ascending aorta. The vessel curves backwards and to the left to reach the left side of the fourth thoracic vertebral body, where it becomes the descending aorta. The arch possesses a concavity inferiorly, left and right sides and a superior convexity.

The concavity is related to the bifurcation of the pulmonary trunk and the left main bronchus. The ligamentum arteriosum attaches the pulmonary trunk (or left pulmonary artery) to the concavity of the aortic arch and is closely related to the left recurrent laryngeal nerve (Figs 2.46 & 2.57).

The left side of the aortic arch is crossed by the left phrenic and vagus nerves (Fig. 2.57) and covered by mediastinal pleura. The phrenic nerve lies in front of the vagus and passes onto the fibrous pericardium in front of the lung root. The vagus nerve inclines backwards to pass behind the lung root, having given off the left recurrent laryngeal nerve. The left superior intercostal vein passes forwards across the arch and usually terminates in the left brachiocephalic vein (Fig. 2.57).

The right side of the arch is related, from in front backwards, to the superior vena cava, trachea, left recurrent laryngeal nerve, oesophagus and thoracic duct. These structures lie between the aorta and the right mediastinal pleura.

The convexity of the arch gives rise to the brachiocephalic trunk, left common carotid and left subclavian arteries (Fig. 2.58), which ascend into the root of the neck. The brachiocephalic trunk is the first branch of the arch of the aorta and arises behind the left brachiocephalic vein. The trunk slopes upwards and to the right across the anterior surface of the trachea, leaving the thorax to the right of the trachea to divide in the root of the neck into the right subclavian and right common carotid arteries.


Right internal jugular vein
Right and left brachio-cephalic veins
Brachio-cephalic trunk
Inferior thyroid veins
Left common carotid artery
Left internal jugular vein
S
R
L
I
Trachea
Left subclavian vein
Arch of aorta
Left vagus and phrenic nerves
Fibrous pericardium (cut)
Right phrenic nerve
Pulmonary trunk
Superior vena cava

Fig. 2.56 Relationships of the brachiocephalic veins to the great arteries arising from the aortic arch.

The left common carotid artery arises behind the brachiocephalic trunk and ascends, in company with the left phrenic and vagus nerves, through the superior mediastinum on the left of the trachea into the root of the neck (Fig. 2.58).

The left subclavian artery is the most posterior artery arising from the aortic arch and lies immediately behind the left common carotid artery. It runs upwards and laterally, closely related to the pleura covering the apex of the left lung, entering the root of the neck behind the sternoclavicular joint.


Left and right brachiocephalic veins
Vagal and sympathetic cardiac nerves
Left phrenic nerve
Fibrous pericardium
Inferior thyroid vein
Left superior intercostal vein
Aortic arch
Left vagus nerve
Ligamentum arteriosum
Left pulmonary artery (cut)
Left bronchus (cut)
Pulmonary veins (cut)
S
A
P
I

Fig. 2.57 Oblique view of the arch of the aorta showing the courses of the left vagus and phrenic nerves.


Right common carotid artery
Right subclavian artery
Brachiocephalic trunk
Right vagus nerve
Arch of azygos vein (cut)
Arch of aorta (cut)
Descending aorta
Trachea
Left common carotid artery
Left subclavian artery
Left recurrent laryngeal nerve
Left vagus nerve
Left main bronchus (cut)
Oesophagus
S
R
L
I

Fig. 2.58 Arch of the aorta and its branches viewed anteriorly.

Phrenic nerves

The right and left phrenic nerves (C3, C4 & C5) pass through the superior thoracic aperture behind the respective subclavian veins. Owing to the asymmetry of the mediastinal organs, the intrathoracic courses of the two nerves differ. The right phrenic nerve, covered by mediastinal pleura, accompanies the right brachiocephalic vein and the superior vena cava in front of the root of the right lung (Fig. 2.59). It descends vertically across the fibrous pericardium covering the right atrium and pierces the diaphragm alongside the inferior vena cava.

The left phrenic nerve, also covered by mediastinal pleura, lies lateral to the left common carotid artery and crosses the left side of the aortic arch to gain the fibrous pericardium in front of the left lung root (Fig. 2.57). The nerve then descends across the pericardium as far as the apex of the heart, where it pierces the diaphragm (Fig. 2.60).

The phrenic nerves supply the muscle of the diaphragm, excluding the crura. They give sensory fibres to the fibrous and parietal serous pericardium and the mediastinal and diaphragmatic pleura, and sensory branches to the peritoneum covering the inferior surface of the diaphragm (pp 36, 205).

Trachea

The trachea descends through the neck, where normally it is palpable above the jugular notch, and enters the thorax in the midline, immediately behind the upper border of the manubrium. It runs vertically through the superior mediastinum and, at the level of the aortic arch, divides into right and left main bronchi (Fig. 2.61).

The right main bronchus is wider than the left and inclines steeply downwards to enter the right lung root. The right upper lobar bronchus often arises outside the hilum of the lung. The left main bronchus runs obliquely to the left within the concavity of the arch of the aorta, passing behind the left pulmonary artery to gain the left lung root.

The thoracic part of the trachea is crossed anteriorly by the brachiocephalic trunk and the left brachiocephalic vein (Fig. 2.59). In addition, the trachea is overlapped by the anterior margins of the pleura and lungs and the thymus (or its remnants). The trachea is related on the left to the arch of the aorta and left common carotid and subclavian arteries, on the right to the superior vena cava, the termination of the azygos vein, the right vagus nerve and the mediastinal pleura, and posteriorly to the oesophagus and the left recurrent laryngeal nerve. (The right recurrent laryngeal nerve does not enter the thorax but passes around the right subclavian artery in the root of the neck; p. 331.)

The vascular supply of the trachea is from the inferior thyroid arteries and veins. The recurrent laryngeal nerves supply sensory and parasympathetic secretomotor fibres to the mucous membrane and motor fibres to the smooth muscle (trachealis).


Right internal thoracic artery (cut)
Right brachiocephalic vein
Brachiocephalic trunk
Left common carotid artery
S
R
L
I
Trachea
Left brachiocephalic vein
Fibrous pericardium (cut)
Left lung root
Right phrenic nerve
Superior vena cava
Right lung root
Right atrium

Fig. 2.59 Oblique view showing the course of the right phrenic nerve.


S
R
L
I
Left common carotid artery
Left subclavian artery
Left vagus nerve
Left phrenic nerve
Left lung root
Left auricle
Pulmonary trunk
Fibrous pericardium (cut)
Diaphragm

Fig. 2.60 Oblique view of the intrathoracic course of the left phrenic nerve.


Right vagus nerve
Right common carotid artery
Trachea
S
R
L
I
Arch of azygos vein (cut)
Arch of aorta (cut)
Left vagus and recurrent laryngeal nerves
Right main bronchus (cut)
Left main bronchus (cut)
Oesophagus

Fig. 2.61 Trachea and left and right main bronchi, exposed after removal of the anterior part of the aortic arch.

Oesophagus

The oesophagus descends through the root of the neck and traverses the superior thoracic aperture behind the trachea. In the superior mediastinum the oesophagus lies in front of the upper four thoracic vertebral bodies and behind the trachea, the left main bronchus and left recurrent laryngeal nerve. The aortic arch and the thoracic duct are on its left while the azygos vein arches forwards on its right (Fig. 2.62).

The oesophagus continues into the posterior mediastinum in front of the fifth thoracic vertebra accompanied by the right and left vagus nerves. It descends behind the fibrous pericardium and inclines to the left to cross in front of the descending aorta. On its right side, the oesophagus is covered by mediastinal pleura. On the left, once anterior to the descending aorta, it is related to pleura as far as the diaphragm. Accompanied by branches of the vagus nerves (see below), the oesophagus passes through the diaphragm at the level of the tenth thoracic vertebra.

The oesophagus is supplied by branches from the inferior thyroid arteries and from the descending thoracic aorta. Its lower part receives branches from the left gastric artery that ascends through the oesophageal opening in the diaphragm. Radicles of the left gastric vein (a tributary of the portal vein) anastomose with veins that drain venous blood from the oesophagus into the azygos system (see Portacaval anastomoses, p. 185). The upper part of the oesophagus is drained by the brachiocephalic veins. Sensory and parasympathetic motor fibres to the oesophagus are provided by the vagi and their recurrent laryngeal branches.

Vagus (X) nerves

In the superior mediastinum, the relationships of the right and left vagi differ. The right vagus nerve (Fig. 2.62) enters the thorax behind the bifurcation of the brachiocephalic trunk and on the right of the trachea. The nerve, covered by mediastinal pleura, inclines backwards and passes behind the right lung root to gain the oesophagus. The left vagus nerve descends behind the left common carotid artery to cross the left side of the aortic arch, gives off the left recurrent laryngeal nerve and continues behind the left lung root to reach the oesophagus.

The left recurrent laryngeal nerve (Fig. 2.62) passes around the arch of the aorta adjacent to the ligamentum arteriosum and ascends in the interval between the trachea and oesophagus. In the posterior mediastinum, the right and left vagus nerves divide on the surface of the oesophagus to form a network, the oesophageal plexus. The terminal branches of the plexus (the anterior and posterior vagal trunks) enter the abdomen with the oesophagus (p. 197).



Fig. 2.62 Intrathoracic part of the oesophagus and accompanying vagus nerves after removal of the main bronchi and the lower part of the trachea.

Descending thoracic aorta and branches

The descending aorta (Fig. 2.63) is continuous with the aortic arch and initially lies to the left of the fifth thoracic vertebral body. As it traverses the posterior mediastinum, it inclines forwards and to the right, gaining the midline anterior to the twelfth thoracic vertebra. On the right, the upper part of the descending aorta is related to the thoracic vertebral bodies and the oesophagus. The lower part and all of its left side are covered by mediastinal pleura. The thoracic duct and the azygos vein lie to the right of the aorta, and anteriorly it is crossed by the oesophagus sloping obliquely from the midline to the left. The descending aorta leaves the thorax in front of the twelfth thoracic vertebra and behind the median arcuate ligament of the diaphragm with the thoracic duct and azygos vein (Figs 2.64 & 4.104).

Posterior intercostal arteries from the descending aorta supply the third to the eleventh intercostal spaces on both sides. They anastomose with the anterior intercostal arteries derived from either the internal thoracic or the musculophrenic arteries. Other branches from the aorta supply the right and left bronchi and the oesophagus.

Thoracic duct

Arising from the upper part of the cisterna chyli (p. 196), the thoracic duct passes into the thorax, lying between the azygos vein and descending aorta, and with these structures (Figs 2.62 & 2.63) ascends through the posterior mediastinum to gain the superior mediastinum on the left of the oesophagus. The duct then curves forwards and to the left, crossing the apex of the left lung to enter the root of the neck where it terminates in the confluence of the left internal jugular and subclavian veins.

Azygos venous system

This system of veins drains blood from most of the posterior thoracic wall and from the bronchi, the pericardium and part of the intrathoracic oesophagus. The azygos vein enters the thorax through the aortic opening and receives posterior intercostal veins from the lower eight spaces on the right (Fig. 2.64). Veins from the second and third spaces drain into the right superior intercostal vein, which terminates in the azygos vein as it arches over the right lung root to join the superior vena cava. The venous return


Left subclavian artery (cut)
Right superior intercostal vein
Thoracic duct
Azygos vein
Left internal jugular vein (cut)
Left subclavian vein
Descending aorta
Oesophagus (cut)
S
R
L
I

Fig. 2.63 Descending aorta and thoracic duct, exposed after removal of the thoracic part of the oesophagus.


Right superior intercostal vein
Right sympathetic trunk
Innermost intercostal muscles
Posterior intercostal vein and artery
Intercostal nerve
Thoracic duct
Azygos vein
Descending aorta
S
R
L
I

Fig. 2.64 Azygos vein, right intercostal nerves and posterior intercostal vessels, exposed after removal of the parietal pleura.

from the first space drains into the right brachiocephalic vein. The azygos vein also receives the hemiazygos veins.

The hemiazygos and accessory hemiazygos veins drain the lower eight posterior intercostal spaces on the left side. The lowermost four spaces usually empty into the hemiazygos vein, which crosses the midline to terminate in the azygos vein (Fig. 2.65). Veins from the next four intercostal spaces usually join to form the accessory hemiazygos vein, which also crosses the midline to end in the azygos. Sometimes, the hemiazygos and accessory hemiazygos veins drain into the azygos vein by a single vessel. The second and third spaces on the left are drained by the left superior intercostal vein (Fig. 2.57), which crosses the aortic arch to end in the left brachiocephalic vein. The first left intercostal space drains into the corresponding brachiocephalic vein.

Thoracic sympathetic trunk

The thoracic part of the sympathetic trunk (chain) runs along the lateral aspects of the thoracic vertebral bodies (Figs 2.65 & 2.66). In continuity with the cervical and abdominal parts, the thoracic sympathetic trunk consists of a series of interconnected enlargements (ganglia) occurring at intervals along its length. Usually, each thoracic spinal nerve is connected to its own ganglion by two branches, a white (preganglionic) and a grey (postganglionic) ramus communicans. Not infrequently, adjacent ganglia fuse together and, most often, the inferior cervical and first thoracic ganglia fuse to form the stellate ganglion.

Branches

Fine nerve filaments running from the sympathetic trunk contribute to the autonomic prevertebral plexuses supplying the thoracic organs, including the heart (cardiac plexuses), lungs (pulmonary plexuses) and the oesophagus (oesophageal plexus). The lower thoracic ganglia give rise to a collection of autonomic fibres that form the greater (Fig. 2.66), lesser and least splanchnic nerves, destined to supply intra-abdominal structures, which are gained by piercing the crura of the diaphragm. All thoracic spinal nerves receive from the grey rami communicantes, sympathetic postganglionic fibres, which are distributed to various structures of the body wall (e.g. blood vessels, hair follicles and sweat glands) by the segmental spinal nerves.


Thoracic duct
Azygos vein
Accessory hemiazygos vein
Ramus communicans
Posterior intercostal arteries (cut)
Hemiazygos vein
Left sympathetic trunk
Posterior intercostal vein and artery
Intercostal nerve
Greater splanchnic nerve
Descending aorta (cut)
S
R
L
I

Fig. 2.65 Oblique view of left sympathetic trunk, hemiazygos vein, intercostal nerves and posterior intercostal vessels after removal of the descending aorta and parietal pleura on the left side of the midline.


Right superior intercostal vein
Rami communicantes
Posterior intercostal vein and artery
Intercostal nerve
Thoracic duct
Right sympathetic trunk and ganglion
Azygos vein
Greater splanchnic nerve
Descending aorta
S
R
L
I

Fig. 2.66 Oblique view of right sympathetic trunk and posterior intercostal vessels and intercostal nerves after removal of the parietal pleura.

Exam Skills

Each of the incomplete statements below is followed by five suggested answers or completions. Decide which are true and which are false. The answers are supplied on p. 417.

1. In the right atrium features visible on the interatrial septum include:

a) the orifice of the coronary sinus.
b) the valve of the inferior vena cava.
c) the fossa ovalis.
d) the crista terminalis.
e) musculi pectinati.

2. In the mediastinum:

a) the left brachiocephalic vein passes behind the left common carotid artery.
b) the brachiocephalic trunk arises from the aortic arch.
c) the left vagus nerve crosses the aortic arch.
d) the ligamentum arteriosum connects the aortic arch to the left pulmonary artery.
e) the oesophagus lies anterior to the descending thoracic aorta.

3. The right lung:

a) possesses a transverse fissure.
b) is in contact with the pericardium overlying the right ventricle.
c) possesses an oblique fissure separating the lower from the middle lobe.
d) has an impression of the azygos arch on its medial surface.
e) receives a rich somatic sensory innervation.

4. A typical rib:

a) articulates with the transverse process of the thoracic vertebra of the same number.
b) possesses a head, which articulates with the body of the same numbered vertebra.
c) is attached by a costal cartilage to the sternum.
d) is attached to the rib below by fibres of external intercostal muscle.
e) has parietal pleura in contact with its deep surface.

5. The oesophagus:

a) passes through the right crus of the diaphragm.
b) receives innervation from the phrenic nerve.
c) is indented by the arch of the aorta.
d) is closely related to the right recurrent laryngeal nerve in the thorax.
e) has veins draining into the hepatic portal vein.

6. The trachea:

a) has the right brachiocephalic vein anteriorly.
b) divides at the level of the fourth thoracic vertebra.
c) has the aortic arch on its left.
d) has a sensory supply from the phrenic nerves.
e) is closely related to the recurrent laryngeal nerves.

7. The right coronary artery:

a) lies in the coronary sulcus.
b) anastomoses directly with the anterior interventricular artery.
c) supplies the SA node.
d) has a right marginal branch.
e) supplies most of the left ventricle.

8. In the thorax, the right vagus:

a) is closely related to the trachea.
b) gives rise to the right recurrent laryngeal nerve.
c) is crossed by the azygos arch.
d) lies anterior to the root of the right lung.
e) contributes to the formation of the oesophageal plexus.

9. The arch of the aorta:

a) is crossed by the left recurrent laryngeal nerve.
b) is crossed by the left vagus.
c) is covered by parietal pleura of the left lung.
d) is crossed by the left phrenic nerve.
e) is located within the superior mediastinum.

10. In the thorax, the sympathetic chains:

a) connect with the intercostal nerves.
b) give rise to splanchnic nerves.
c) leave in company with the descending thoracic aorta.
d) are covered by parietal pleura.
e) are closely related to the oesophagus.

11. The left brachiocephalic vein:

a) lies partly within the middle mediastinum.
b) lies anterior to the brachiocephalic trunk.
c) usually receives the thoracic duct.
d) terminates in the superior vena cava.
e) receives inferior thyroid veins.

12. The fibrous pericardium:

a) is innervated by intercostal nerves.
b) is firmly attached to the diaphragm.
c) is closely related to the phrenic nerves.
d) is closely related to the oesophagus.
e) is lined by parietal serous pericardium.

13. The left main bronchus:

a) lies within the concavity of the arch of the aorta.
b) is closely related to the oesophagus.
c) is usually wider than the right main bronchus.
d) lies posterior to the left vagus nerve.
e) receives branches from the internal thoracic artery.

14. Concerning respiratory movements:

a) the diaphragm descends during expiration.
b) the lung extends into the costodiaphragmatic recess during inspiration.
c) intercostal muscles contract during inspiration.
d) expiration is assisted by contraction of pectoralis major.
e) elasticity of the lungs contributes to expiration.

15. The thoracic duct:

a) enters the thorax in company with the oesophagus.
b) lies in the posterior mediastinum.
c) arches across the apex of the left lung.
d) lies anterior to the trachea in the superior mediastinum.
e) lies to the left of the azygos vein as it enters the thorax.

16. Concerning the cardiac conducting system:

a) the SA node lies in the interatrial septum.
b) specialized conducting tissue connects the SA and AV nodes.
c) the AV node lies close to the termination of the coronary sinus.
d) the AV bundle lies in the interventricular septum.
e) the left coronary artery is commonly the main arterial supply.

Clinical Case Skills

The answers are supplied on p. 418.

Case Study 1

A 51-year-old woman complained to her family practitioner that she had felt very fatigued for several weeks. She had lost 7–10 pounds in weight over the previous month. On physical examination the physician discovered a firm nodular swelling, about 3–4 cm in diameter, in the left breast that was anchored in tissue several centimetres beneath the skin.

Questions:

1. To which additional areas of this woman's body should the physician direct special attention during the physical examination and why?
2. Which muscle should be caused to contract in order to demonstrate the fixation of the swelling?
3. Following surgical removal of the swelling and exploration of the axilla, the patient is found to have a winged scapula. How has this occurred?
4. Following surgery, she noted a swollen left arm. Why?

Case Study 2

A 67-year-old man developed a worsening cough over several months and, when the sputum began to show streaks of blood, he consulted a physician. The patient gave a history of smoking cigarettes for 40 years and recently had noted that his voice had become hoarse. An X-ray of the chest revealed an irregularly-shaped density in the hilar region of the left lung.

Questions:

1. How might the hoarseness relate to the location of the density?
2. Which other structures are situated in the vicinity of the hilar region of the lung?
3. What is the nerve supply of the mediastinal pleura against which the density lies?
4. If the density obstructed the left upper lobe bronchus, what would the effect be?

Case Study 3

While playing golf, a 74-year-old man felt tingling down the medial side of his left arm. He continued to play but 10 minutes later began to have difficulty breathing and became dizzy. He sat down on a nearby bench but soon complained of severe chest pain and then lapsed into unconsciousness.

He was rushed to hospital where an electrocardiogram showed irregularities in the heart's electrical activity. Some minutes later, he deteriorated markedly, and his blood pressure dropped dramatically. He lapsed into a deep coma and died several minutes later. A post-mortem showed total obstruction of the left coronary artery and near-complete obstruction of the right coronary artery.

Questions:

1. What is the cause of the tingling sensation in the left arm?
2. How does coronary artery disease cause irregularities in the cardiac cycle?
3. Which coronary artery is more likely to cause irregularities in rhythm if obstructed?
4. Where do anastomoses occur between the coronary arteries?

Case Study 4

An 8-year-old boy was found to have high blood pressure during a school physical examination. He was referred to his physician, who verified the high blood pressure and noted that his femoral pulses were weak in comparison to the radial and carotid pulses. His feet seemed cool to the touch and the patient said he always had to wear warm socks even in summer. A chest radiograph was remarkable for irregular notches along the lower borders of several of the ribs on both sides of his chest.

Questions:

1. How can unequal pulses in the upper and lower limbs be explained?
2. Which vessels caused the notching along the ribs, and in which direction was blood flowing through them?
3. Rib notching was absent from the upper two ribs. Why?
4. Would auscultation of the thorax reveal any abnormal sounds?

Observation Skills

Identify the structures indicated. The answers are supplied at the foot of the page.



Fig. 2.67 Transverse CT image at the level of the second thoracic vertebra. (Compare Fig. 2.71.)



Fig. 2.68 Transverse CT image at the level of the fourth thoracic vertebra. (Compare Fig. 2.18.)

Answers:

Fig. 2.67 1 = right internal jugular vein; 2 = infrahyoid strap muscle; 3 = trachea; 4 = medial end of left clavicle; 5 = left internal jugular vein; 6 = left common carotid artery; 7 = left subclavian vein; 8 = left subclavian artery; 9 = oesophagus; 10 = right common carotid artery; 11 = right subclavian artery.

Fig. 2.68 1 = left brachiocephalic vein; 2 = brachiocephalic trunk arising from arch of aorta; 3 = aortic arch; 4 = oesophagus; 5 = trachea; 6 = termination of right brachiocephalic vein.



Fig. 2.69 Transverse CT image at the level of the fifth thoracic vertebra. (Compare Fig. 2.27.)



Fig. 2.70 Transverse CT image at the level of the seventh thoracic vertebra. (Compare Fig. 1.5.)

Answers:

Fig. 2.69 1 = superior vena cava; 2 = ascending aorta; 3 = bifurcation of pulmonary trunk into right and left pulmonary arteries; 4 = descending aorta; 5 = pulmonary veins.

Fig. 2.70 1 = right pulmonary vein entering left atrium; 2 = right atrium; 3 = right ventricle; 4 = infundibulum of left ventricle; 5 = left lung; 6 = descending aorta; 7 = oesophagus; 8 = azygos vein.



Fig. 2.71 Transverse section at the level of the third thoracic vertebra. Inferior aspect. (Compare Fig. 2.67.)



Fig. 2.72 Transverse section at the level of the sixth thoracic vertebra. Inferior aspect. (Compare Fig. 2.31.)

Answers:

Fig. 2.71 1 = pectoralis major; 2 = pectoralis minor; 3 = right brachiocephalic vein; 4 = left brachiocephalic vein; 5 = brachiocephalic trunk; 6 = left common carotid artery; 7 = left lung; 8 = left axillary vein; 9 = left subclavian artery; 10 = oesophagus; 11 = thoracic spinal cord; 12 = trachea; 13 = lymph nodes.

Fig. 2.72 1 = right atrium; 2 = fibrous pericardium; 3 = internal thoracic vessels; 4 = sternum; 5 = right ventricle; 6 = aortic valve; 7 = anterior interventricular artery; 8 = left ventricle; 9 = descending aorta; 10 = azygos vein; 11 = oesophagus; 12 = pericardial cavity; 13 = pleural cavity; 14 = oblique fissure; 15 = lower lobe of right lung.



Fig. 2.73 Posteroanterior chest radiograph.



Fig. 2.74 Posteroanterior chest radiograph.

Answers:

Fig. 2.73 1 = coracoid process; 2 = first rib; 3 = trachea; 4 = blade of scapula; 5 = diaphragm; 6 = breast.

Fig. 2.74 1 = clavicle; 2 = arch of aorta; 3 = pulmonary trunk; 4 = left ventricle; 5 = apex; 6 = right atrium; 7 = hilar markings.

Chapter 3

UPPER LIMB

Introduction 72
Deltoid 76
  Axillary nerve 76
Axilla 77
  Walls 77
  Contents 78
Anterior Compartment of the Arm 82
  Muscles 82
  Vessels 83
  Nerves 83
Cubital Fossa 85
Anterior Compartment of the Forearm 86
  Superficial muscles 86
  Deep muscles 87
  Vessels 88
  Nerves 89
Palm and Digits 90
  Deep fascia of the palm 90
  Flexor tendons in the hand 93
  Thenar muscles 94
  Hypothenar muscles 95
  Deep muscles 95
  Digital extensor expansions 98
  Blood vessels 98
  Nerves 99
Muscles Attaching the Upper Limb to the Trunk 100
  Trapezius 100
  Levator scapulae and rhomboids 101
  Latissimus dorsi 102
Short Scapular Muscles 103
  Rotator cuff muscles 103
  Teres major 105
Posterior Compartment of the Arm 106
  Triceps brachii 106
  Vessels and nerves 106
Posterior Compartment of the Forearm 108
  Superficial muscles 109
  Deep muscles 110
  Vessels 113
  Nerves 113
Dorsum of the Hand 114
Clavicular and Shoulder Joints 115
  Clavicular joints 115
  Shoulder joint 116
Elbow Joint 119
Radioulnar Joints 121
Wrist Joint 122
  Radiocarpal joint 122
Joints of Carpus 123
  Intercarpal joints 123
  Movements 123
  Carpal tunnel 123
Joints of the Hand 125
  Carpometacarpal joints 125
  Metacarpophalangeal joints 125
  Interphalangeal joints 125
Exam Skills 127
Clinical Case Skills 128
Observation Skills 130

Introduction

The upper limb (extremity) comprises several bones and their joints (Fig. 3.1), clothed by soft tissues. For descriptive purposes, the limb is divided into regions (Fig. 3.2), each enveloped by fascia and containing muscles with nerve and vascular supplies. The scapula with its associated muscles and soft tissues comprise the scapular region, the muscles attaching between the front of the chest wall and the upper limb (together with the overlying fascia, breast and skin) constitute the pectoral region. The scapula and the clavicle, which together form the pectoral girdle, articulate at the acromioclavicular joint. The clavicle articulates with the trunk at the sternoclavicular joint and the scapula with the humerus at the glenohumeral (shoulder) joint.

Between the proximal part of the limb and the chest wall is the axilla, a region traversed by the principal nerves and vessels passing between the upper limb and the root of the neck.

The arm is that part of the upper limb between the shoulder and the elbow. The muscles of the arm are disposed in anterior (flexor) and posterior (extensor) compartments, separated by the humerus and the medial and lateral intermuscular septa (Fig. 3.3). In front of the elbow joint (at which the humerus, radius and ulna articulate) lies the cubital fossa, a region traversed by vessels and nerves passing between the arm and the forearm.

The forearm lies between the elbow and the wrist, and its muscles are arranged in anterior (flexor) and posterior (extensor) compartments, separated by the radius, ulna, and interosseous membrane (Fig. 3.4). Rotation at the proximal and distal radioulnar joints permits the hand to function in any position between the extremes of supination (palm facing up) and pronation (palm facing down).

The forearm articulates with the carpus at the wrist (radiocarpal) joint. Together with the flexor retinaculum, the bones of the carpus form the carpal tunnel, which links the anterior compartment of the forearm and the palm of the hand. The structures of the palm lie anterior to the metacarpals, while posteriorly is the dorsum of the hand. The digits are named, from lateral to medial, the thumb and the index, middle, ring and little fingers.

The skin and subcutaneous tissue of the shoulder region are supplied by supraclavicular nerves, whereas the cutaneous supply of the remainder of the upper limb is derived from the brachial plexus (Fig. 3.5). Each of the anterior (ventral) rami contributing to this plexus supplies a specific area of skin (dermatome; Fig. 3.6).


Bones
Pectoral girdle:
Clavicle
Scapula
Humerus
Joints
Elbow
Radius
Proximal radioulnar
Ulna
Carpal bones
Metacarpals
Distal radioulnar
Wrist
Carpometacarpal
Metacarpophalangeal
Interphalangeal
Phalanges
S
la
m
I

Fig. 3.1 Bones and joints of the upper limb.


Scapular region
Axilla
Compartments of arm:
Posterior
Anterior
Cubital fossa
Compartments of forearm:
Posterior
Anterior
Carpal region
Dorsum of hand
Palm of hand
S
la
m
I

Fig. 3.2 Parts of the upper limb.


Level of medial epicondyle
Little finger
Thumb
A
m
la
P
Neurovascular structures
Humerus
Lateral inter-muscular septum
Deep fascia
Anterior compartment
Posterior compartment

Fig. 3.3 Transverse section midway between glenohumeral and elbow joints to show the compartments of the arm.


Superficial vein
Little finger
Inter-osseous membrane
A
m
la
P
Thumb
Deep fascia
Radius
Intermuscular septa
Ulna
Anterior compartment
Posterior compartment

Fig. 3.4 Transverse section midway between elbow and wrist joints to show the compartments of the forearm.

Each dermatome and the area supplied by each individual superficial nerve may vary somewhat from one person to another. There is overlapping of innervation by adjacent superficial nerves. Damage to a single nerve produces anaesthesia over an area smaller than that supplied by the nerve so that identification of nerve injury requires careful testing. The ventral rami also supply specific muscles (myotomes) that can be tested clinically by assessing movements at joints (Table 3.1).



Fig. 3.5 Typical distribution of cutaneous nerves in the upper limb.



Fig. 3.6 Typical arrangement of dermatomes of upper limb. There may be considerable overlap of areas supplied.

The courses of the principal arteries are shown in Figure 3.7. In the root of the neck, the axillary artery is continuous with the subclavian artery, which derives from the brachiocephalic trunk on the right, but directly from the arch of the aorta on the left side. In the axilla and arm, there is a single main arterial channel, which terminates in the forearm by dividing into radial and ulnar arteries.

There are deep and superficial veins in the upper limb (Fig. 3.8). Deep veins accompany the arteries in the forearm and hand and consist of interconnecting networks of venae comitantes. The brachial artery may be accompanied by either one or two veins, but there is usually a single axillary vein, which drains via the subclavian into the brachiocephalic vein. The superficial veins, lying outside the muscle compartments, are often visible through the skin and those on the forearm and back of the hand are often used for venepuncture. The veins contain valves which prevent backflow of blood. The smaller superficial veins, and on occasion the main veins of the limb, are subject to considerable variation, even between the right and left sides of the same individual.

Most superficial lymphatics of the upper limb drain to the axillary nodes (p. 81), although lymph from the medial aspect of the forearm first traverses a small group of nodes near the medial aspect of the cubital fossa. In the shoulder region, some lymph may pass through supra- or infraclavicular nodes. The deep lymphatics of the limb also drain to the axillary lymph nodes. From here, lymph passes into the

Table 3.1 Segmental innervation for upper limb movements

Shoulder (glenohumeral joint)		
Action	Abduction	Adduction
Spinal segments	C5	C6
Elbow (cubital joint)		
Action	Flexion	Extension
Spinal segments	C5 and C6	C7 and C8
Reflex	Biceps jerk	Triceps jerk
Wrist (radiocarpal joint)		
Action	Flexion	Extension
Spinal segments	C6 and C7	C6 and C7
Knuckles (metacarpophalangeal joints)		
Action	Abduction and adduction of fingers	
Spinal segments	T1	

C, cervical myotomes; T, thoracic myotomes.

subclavian trunk and then into either the right lymphatic duct or, on the left, the thoracic duct (Fig. 1.34).

Figure 3.9 illustrates the important sites at which the principal nerves of the limb are closely related to bone: axillary nerve to the neck of the humerus; radial nerve to the midshaft of the humerus; ulnar nerve to the medial epicondyle; posterior interosseous nerve to the neck of the radius. Injury to one of these bones may damage the adjacent nerve. The main parts of the brachial plexus in the axilla, the cords, are continuous via the divisions and trunks in the lower part of the neck with the anterior (ventral) rami of spinal nerves C5, C6, C7, C8 and T1, which form the roots of the plexus.


Subclavian
Thoraco-acromial
Axillary
Subscapular
Profunda brachii
Collateral
Brachial
Ulnar
Interosseous
Radial
Deep palmar arch
Superficial palmar arch
S
la
m
I

Fig. 3.7 Principal arteries of the upper limb. No muscular branches are shown.


Subclavian
Cephalic
Axillary
Venae comitantes of brachial artery
Venae comitantes
Basilic
Dorsal venous arch
Superficial
Deep
S
la
m
I

Fig. 3.8 Typical arrangement of the principal veins of the upper limb. For clarity, venae comitantes are illustrated as single channels.


Lateral cord
Medial cord
Median nerve
Anterior interosseous nerve
Recurrent branch
Digital branches
of median nerve
Lateral cord of brachial plexus
Medial cord of brachial plexus
Musculocutaneous nerve
Ulnar nerve
Lateral cutaneous nerve of forearm
Dorsal branch
Palmar branch
Deep branch
Digital branches
of ulnar nerve
Posterior cord of brachial plexus
Axillary nerve
Radial nerve
Posterior interosseous nerve
Superficial branch of radial nerve
Digital branches of radial nerve
S
la
m
I

Fig. 3.9 Courses of the principal nerves of the upper limb. From left to right: median nerve, musculocutaneous and ulnar nerves, radial and axillary nerves.

Deltoid

Deltoid is a large multipennate muscle responsible for the rounded contour of the shoulder region (Fig. 3.10). The muscle overlies the shoulder joint and the attachments of the short scapular muscles to the upper end of the humerus (Fig. 3.11). Proximally, it has a continuous attachment to the lateral third of the clavicle and to the acromion and spine of the scapula. The distal attachment is to a roughened area, the deltoid tuberosity, midway down the lateral surface of the shaft of the humerus (Fig. 3.23). Deltoid acts only on the shoulder joint, where it is the main abductor. During this movement, produced by the acromial fibres, the joint is stabilized by the clavicular fibres and those from the scapular spine. Acting alone, the anterior fibres produce flexion, whereas the posterior fibres extend the shoulder joint. Deltoid is supplied by the axillary nerve, a terminal branch of the posterior cord of the brachial plexus.

Axillary nerve

The axillary nerve leaves the axilla through the quadrangular space (Fig. 3.64) accompanied by the posterior circumflex humeral artery. In its course, the nerve is closely related to the surgical neck of the humerus and to the capsule of the shoulder joint. It supplies deltoid and teres minor, the shoulder joint and skin overlying the lower part of deltoid. Damage to the nerve may occur during dislocation of the shoulder joint, resulting in weakness of abduction, impaired sensation and, subsequently, in loss of the normal contour of the shoulder as the deltoid muscle becomes wasted.


Acromion
Deltoid
Cephalic vein
Deep fascia of anterior compartment of arm
Clavicle
Delto-pectoral triangle
Branches of thoraco-acromial artery
Pectoralis major
S
la
m
I

Fig. 3.10 Anterior view of deltoid. The cephalic vein lies in the deltopectoral groove. Deformity of the clavicle is due to a healed fracture.


Trapezius
Spine of scapula
Acromion of scapula
Teres major
Latissimus dorsi
Fascia of posterior compartment of arm
Clavicle
Deltoid
Pectoralis major
Cephalic vein
S
P
A
I

Fig. 3.11 Lateral view. Deltoid has a continuous proximal attachment to the spine and acromion of the scapula and the lateral part of the clavicle.

Axilla

The axilla is the space between the root of the upper limb and the chest wall. It is traversed by the principal vessels and nerves that pass between the upper limb and the root of the neck. The shape and size of the axilla vary according to the position of the shoulder joint but when the limb is in the anatomical position the axilla is shaped as a truncated pyramid with a narrow apex (inlet) superiorly, a broad base and three walls (Fig. 3.12).


S
la
m
I
Apex (inlet)
Lateral edge
Medial wall
Anterior wall
Posterior wall
Base

Fig. 3.12 Shape of the axilla.


P
la
m
A
Apex (inlet) of axilla
Transverse process of T1
Superior border of scapula
Spine of scapula
Clavicle
Acromion
Coracoid process
First rib
Costal cartilage
Manubrium

Fig. 3.13 Axilla from above, showing the boundaries of its apex.

Walls

The upper ribs and intercostal spaces, covered by serratus anterior, form the medial wall (Fig. 3.15), which is convex laterally. The anterior wall consists of pectoralis major overlying pectoralis minor and subclavius (Figs 3.14 & 3.16), while the posterior wall is formed by subscapularis, teres major and latissimus dorsi. The muscles of the anterior and posterior walls converge on the humerus (Fig. 3.15) so that the axilla is limited laterally by the narrow intertubercular sulcus of the humerus. The base of the axilla, convex upwards, is formed by fascia passing between the inferior margins of the anterior and posterior walls. The triangular apex of the axilla provides continuity between the root of the neck and the upper limb and is bounded by the clavicle, the superior border of the scapula and the first rib (Fig. 3.13).




Clavicle
Deltoid
Axillary fat
Pectoralis major (cut)
Cephalic vein
S
la
m
I
Sternomastoid
External jugular vein
Calvicular head of pectoralis major (cut)
Axillary vein
Branches of thoraco-acromial artery
Pectoralis minor
Serratus anterior

Fig. 3.14 Structures that pass above pectoralis minor in the anterior wall of the axilla. Pectoralis major and fascia around pectoralis minor have been removed.

Contents

The axilla contains the axillary artery and its branches, the axillary vein and its tributaries, parts of the brachial plexus and the axillary lymph nodes.

Coracobrachialis and the short and long heads of biceps brachii traverse the axilla. In addition, the tail of the breast usually enters the axilla. All these structures are embedded in loose fatty connective tissue (Fig. 3.15).


Scapula
Teres minor
Deltoid
Tendon of triceps long head
Shaft of humerus
Cephalic vein
Infra-spinatus
Sub-scapularis
Intercostal muscle
Rib
Serratus anterior
Pectoralis minor
Pectoralis major
Axillary artery
Coraco-brachialis and biceps short head (fused)
Tendon of biceps long head
Axillary fat
Axillary vein
Thoracic cavity
Parts of brachial plexus
P
la
m
A

Fig. 3.15 Transverse section showing (left) the walls and (right) the contents of the axilla. Superior aspect. The lung has been removed.

Axillary artery

The subclavian artery continues as the axillary artery beyond the lateral edge of the first rib. Near the inlet, the axillary artery lies posterior to the axillary vein (Figs 3.16 & 3.17) but more distally, the artery lies lateral to the vein close to the humerus. The axillary artery and parts of the brachial plexus that surround it are bound together by a fibrous layer called the axillary sheath. Local anaesthetic injected inside the sheath will spread to produce a brachial plexus nerve block. Coracobrachialis and the short head of biceps brachii lie lateral to the artery, while pectoralis minor crosses it anteriorly. By convention, the axillary artery is described in parts which lie above, behind and below pectoralis minor. Distal to the lower border of teres major, the vessel continues into the arm as the brachial artery (Fig. 3.18).

Branches of the axillary artery supply the walls of the axilla and adjacent structures. The thoracoacromial artery (Fig. 3.14) supplies the anterior wall, while the superior thoracic and lateral thoracic arteries supply the medial and anterior walls. The


Pectoralis minor (cut)
Deltoid (cut)
Biceps long head
Musculo-cutaneous nerve
Biceps short head (cut)
Latissimus dorsi
External jugular vein
Clavicle
Subclavius
Cephalic vein (stump)
Median nerve
Axillary vein
Long thoracic nerve
Thoraco-dorsal artery and nerve
S
la
m
I

Fig. 3.16 Axillary neurovascular bundle, exposed by removal of the pectoral muscles and axillary fat.


S
la
m
I
Superior trunk
Lateral cord
Musculo-cutaneous nerve
Coraco-brachialis
Axillary artery
Median nerve
Radial nerve
Ulnar nerve
Scalenus anterior
Subclavian artery
Inferior trunk
Medial cord
Posterior cord
Sub-scapularis
Sub-scapular artery
Thoraco-dorsal nerve

Fig. 3.17 Components of the brachial plexus. The clavicle and the veins and most of the axillary artery have been removed.

thoracoacromial and lateral thoracic arteries also supply part of the breast. The posterior wall is supplied by the subscapular artery. The anterior and posterior circumflex humeral arteries (Fig. 3.18) pass laterally and encircle the surgical neck of the humerus, supplying the shoulder joint and the upper part of the arm. An important collateral circulation, the scapular anastomosis is formed by communication between the circumflex scapular branch of the subscapular artery and the suprascapular branch from the thyrocervical trunk, a branch of the subclavian artery. These, and anastomoses involving transverse cervical and posterior intercostal arteries, may enable blood to bypass blockages in the subclavian and axillary arteries.

Axillary vein

The venae comitantes of the brachial artery unite with the basilic vein in the upper part of the arm and continue as the axillary vein above the inferior border of teres major. The vein ascends medial to the axillary artery (Fig. 3.16), passing behind pectoralis minor, and crosses the lateral edge of the first rib to continue as the subclavian vein, lying anterior to its companion artery. A major tributary of the axillary vein is the cephalic vein, which ascends in the groove between deltoid and pectoralis major. Just below the clavicle, it enters the axilla by piercing the fascia above pectoralis minor (Fig. 3.14). The progress of a catheter inserted proximally along the cephalic vein may be impeded by the acute angulations often present near its termination in the axillary vein above pectoralis minor. The axillary vein receives other tributaries, which in general correspond to the branches of the axillary artery.

Brachial plexus

The whole plexus is described here, although only the divisions, cords and certain branches lie within the axilla. The brachial plexus supplies the upper limb and consists of a branching network of nerves derived from the anterior rami of the lower four cervical and the first thoracic spinal nerves. Occasionally, the plexus receives a major contribution from cervical nerve four (said to be a pre-fixed plexus) or from the second thoracic nerve (post-fixed plexus). The plexus enables nerve fibres originating in several spinal cord segments to be distributed to each peripheral branch. Knowledge of the segmental arrangement and distribution is necessary for accurate diagnosis in diseases or injuries involving the spinal cord or the brachial plexus. The parts of the plexus are named, from proximal to distal: roots, trunks, divisions and cords (Fig. 3.19). The five roots (anterior rami) give rise to three trunks (superior, middle and inferior), which emerge between scalenus medius and scalenus anterior to lie in the floor of the posterior triangle of the neck (p. 326). The roots of the plexus lie deep to the prevertebral fascia, while the trunks are covered by its lateral extension, the axillary sheath. Each trunk divides into an anterior and a posterior division behind the clavicle, at the apex of the axilla. Within the axilla, the divisions combine to produce the three cords, which are named lateral, medial and posterior, according to their relationships to the axillary artery. Each cord ends near the lower border of pectoralis minor by dividing into two terminal branches. Other branches of the plexus arise in the neck and axilla directly from the roots,



Fig. 3.18 Some posterior branches of the brachial plexus seen after removal of the more anterior parts of the plexus. Biceps brachii and coracobrachialis have been excised.

trunks and cords (Fig. 3.20). The anterior divisions form the lateral and medial cords (Fig. 3.17), whose branches supply the flexor muscles of the arm, forearm and hand, and the skin overlying the flexor compartments. The three posterior divisions unite to form the posterior cord (Fig. 3.18), the branches of which supply the extensor musculature of the shoulder, arm and forearm and the skin of the posterior surface of the limb.

Axillary lymph nodes

The axillary lymph nodes receive lymph not only from the upper limb but also from the superficial tissues of the trunk above the level of the umbilicus, including the breast.

The nodes are described in groups according to their positions in the axilla. Anteriorly lies the pectoral group, which drains the lateral and anterior aspects of the body wall including the breast. Laterally, along the axillary vessels, is the humeral (lateral) group of nodes, which receives most of the lymph from the upper limb. Posteriorly the subscapular nodes receive lymph from the dorsal aspect of the body wall. Within the axilla, efferent lymph channels drain centrally and then proximally to apical nodes from which a subclavian lymph trunk arises; this terminates in the root of the neck by joining, on the right, the right lymphatic duct or, on the left, the thoracic duct. Sometimes the lymph trunks join the subclavian vein directly (p. 330). Clinical examination often includes palpation of the axillary lymph nodes, for example in breast disease. When malignant disease is present, the axilla may be explored surgically to identify sentinel lymph nodes.

The principal vessels and nerves entering or leaving the axilla are listed in Table 3.2.


Roots
Trunks
Anterior
Posterior
Divisions
Cords
Terminal branches
C5
C6
C7
C8
T1
Superior
Middle
Inferior
Lateral
Posterior
Medial

Fig. 3.19 Main components of the brachial plexus in their usual arrangement.


Roots
Trunks
Anterior
Posterior
Divisions
Cords
Terminal branches
Suprascapular
Dorsal scapular
C5
C6
C7
C8
T1
Subclavian
Upper subscapular
Thoracodorsal
Lower subscapular
Long thoracic
Lateral pectoral
Lateral head of median
Axillary
Musculocutaneous
Median
Radial
Medial head of median
Medial pectoral
Medial cutaneous of arm (brachial)
Medial cutaneous of forearm (antebrachial)
Ulnar

Fig. 3.20 Branches of the brachial plexus. The arrangement of these nerves may vary considerably.

Table 3.2 Principal vessels and nerves entering or leaving the axilla

Between axilla and root of neck (via inlet of axilla)	Between axilla and arm (lateral to fascia of axillary floor)	Through anterior wall (via interval between clavicle and pectoralis minor)	Through posterior wall (via triangular and quadrangular intermuscular spaces)
Subclavian/axillary artery Axillary/subclavian vein Trunks/divisions of brachial plexus Subclavian lymph trunk	Axillary/brachial artery Brachial/axillary vein Median nerve C6, C7, C8, T1 Musculocutaneous nerve C5, C6, C7 Ulnar nerve C8, T1 Radial nerve C5, C6, C7, C8 Brachial lymphatics	Thoracoacromial artery Cephalic vein Pectoral nerves C5, C6, C7, C8, T1 Deltopectoral lymphatics	Circumflex branch of subscapular artery Axillary nerve C5, C6 with posterior circumflex humeral artery

Anterior Compartment of the Arm

The anterior compartment of the arm contains three muscles (biceps brachii, coracobrachialis and brachialis), the brachial artery with its venae comitantes and three nerves (the median, ulnar and musculocutaneous nerves).

Muscles

The three muscles of the compartment are supplied by the musculocutaneous nerve. The two heads of biceps separate proximally (Fig. 3.21) and have tendinous attachments to the scapula. The short head lies medially and attaches to the tip of the coracoid process. The tendon of the long head attaches to the supraglenoid tubercle, leaves the shoulder joint deep to the transverse humeral ligament and continues distally in the intertubercular sulcus deep to the tendon of pectoralis major. The muscle bellies fuse and are attached by a tendon (Fig. 3.27) to the tuberosity of the radius and by the bicipital aponeurosis, which fuses with deep fascia on the medial side of the forearm. Biceps is a strong flexor of the elbow and supinator of the forearm at the radioulnar joints, and a weak flexor of the shoulder joint.


Coracoid process
Axillary vein
Pectoralis minor (cut)
Median nerve
Latissimus dorsi
Medial cutaneous nerve of forearm
Deltoid (cut)
Tendons of short and long heads
Biceps brachii
Aponeurosis of biceps
Brachio-radialis
Lateral cutaneous nerve of forearm
S
la
m
I

Fig. 3.21 Anterior view of biceps brachii after removal of deep fascia and anterior fibres of deltoid.

Coracobrachialis attaches to the coracoid process with the short head of biceps. The muscle attaches distally to the medial side of the shaft of the humerus near its midpoint (Fig. 3.23). Coracobrachialis is pierced by the musculocutaneous nerve (Fig. 3.22) and functions as a weak flexor and adductor of the shoulder joint.

Brachialis lies deeply and has an extensive attachment to the anterior surface of the distal half of the shaft of the humerus


Capsule of glenohumeral joint
Short head of biceps brachii (cut)
Musculo-cutaneous nerve
Brachialis
Lateral cutaneous nerve of forearm
Axillary artery
Axillary vein
Median nerve
Coraco-brachialis
S
la
m
I

Fig. 3.22 The musculocutaneous nerve piercing coracobrachialis. The short head of biceps brachii has been divided and the muscle reflected laterally.


Anatomical neck
Head
S
la
m
I
Greater tubercle
Lesser tubercle
Surgical neck
Deltoid tuberosity
Coracobrachialis
Brachialis
Pectoralis major
Deltoid
Lateral supracondylar ridge
Medial supracondylar ridge
Medial epicondyle
Lateral epicondyle
Capitulum
Trochlea

Fig. 3.23 Anterior aspect of humerus.

(Fig. 3.23) and adjacent intermuscular septa. The muscle passes to the coronoid process of the ulna (Fig. 3.34) and acts as a powerful flexor of the elbow joint.

Vessels

The brachial artery is the continuation of the axillary artery distal to teres major. In the upper part of the arm, the brachial artery with its venae comitantes is accompanied by the median and ulnar nerves (Fig. 3.24) and the medial cutaneous nerve of the forearm. The artery passes distally and laterally, lying medial to biceps and anterior to coracobrachialis and brachialis. An important branch, the profunda brachii artery (p. 107), supplies the posterior compartment of the arm. Division of the brachial artery into its terminal radial and ulnar branches usually occurs in the cubital fossa but may occur more proximally. The brachial artery is vulnerable to injury in fractures just proximal to the humeral epicondyles, with risk of subsequent fibrosis in forearm muscles (Volkmann's ischaemic contracture).

Venae comitantes, ascending from the cubital fossa, accompany the brachial artery and are joined by the basilic vein after it has pierced the deep fascia at about midarm level. At the lower border of the axilla the venous channels usually combine to form a single axillary vein.

Nerves

The musculocutaneous nerve (Fig. 3.22) is a terminal branch of the lateral cord. It pierces coracobrachialis and lies between


Musculo-cutaneous nerve
Brachialis
Brachial artery
Lateral cutaneous nerve of forearm
Vena comitans (cut)
Lateral and medial heads of median nerve (displaced)
Axillary artery
Sub-scapular artery
Ulnar nerve
Median nerve
S
la
m
I

Fig. 3.24 Brachialis, the brachial artery and the nerves of the compartment. Biceps brachii and most veins have been excised.

biceps and brachialis, supplying each of these muscles. The nerve continues distally as the lateral cutaneous nerve of the forearm, which pierces the deep fascia between biceps and brachioradialis to lie superficially over the cubital fossa (Fig. 3.26).

The median and ulnar nerves traverse the entire length of the arm, but neither gives any branches above the elbow joint. The median nerve arises by lateral and medial heads, which are terminal branches of the lateral and medial cords. In the upper part of the arm the nerve lies lateral to the brachial artery but at midarm level it crosses anterior to the vessels and finally lies medial to the artery (Fig. 3.24), a position retained in the cubital fossa. The ulnar nerve is a terminal branch of the medial cord and, together with the medial cutaneous nerve of forearm, initially lies medial to the brachial artery but leaves the artery at midarm level (Fig. 3.24). It then pierces the medial intermuscular septum and enters the posterior compartment to lie between the septum and the medial head of triceps.


Medial cutaneous nerve of arm
Cephalic vein
Medial cutaneous nerve of forearm
Biceps brachii
Subcutaneous tissue
Median cubital vein
Lateral cutaneous nerve of forearm
Perforating vein
S
la
m
I

Fig. 3.25 Cutaneous nerves and superficial veins overlying the right cubital fossa. Subcutaneous tissue has been retained medial to the basilic vein.


S
la
m
I
Biceps brachii
Basilic vein
Branch of posterior cutaneous nerve of forearm
Tendon and aponeurosis of biceps brachii
Perforating vein
Deep fascia of forearm
Brachio-radialis
Lateral cutaneous nerve of forearm

Fig. 3.26 Roof of the cubital fossa after removal of subcutaneous tissue, veins and nerves. A perforating vein communicates with deep veins by passing through the deep fascia.


S
la
m
I
Medial head of triceps
Brachial artery and venae comitantes
Aponeurosis of biceps brachii (cut)
Tendon of biceps brachii
Median nerve
Pronator teres
Radial artery and vena comitans

Fig. 3.27 Contents of the cubital fossa. The aponeurosis of biceps brachii and deep fascia have been removed.

Cubital Fossa

The cubital fossa is a triangular space in front of the elbow joint, bounded laterally by brachioradialis and medially by pronator teres (Fig. 3.28). By convention, the fossa is limited proximally by an imaginary line drawn between the two humeral epicondyles. The roof is formed by deep fascia, reinforced by the aponeurosis of biceps (Fig. 3.26). The subcutaneous tissue overlying the roof contains branches of the lateral and medial cutaneous nerves of forearm and superficial veins such as the median cubital vein, which links the cephalic and basilic veins (Fig. 3.25). The arrangement of these superficial veins, which are often punctured to obtain samples of blood for laboratory analysis, may vary considerably between individuals.

The fossa is traversed by nerves and vessels passing between the arm and the forearm. Its contents (Figs 3.27 & 3.29), embedded in fatty connective tissue, are, from medial to lateral, the median nerve, the brachial artery and its venae comitantes, the tendon of biceps and the radial nerve. Distally, the terminal branches of the radial nerve, the superficial and deep radial (posterior interosseous) nerves, and the terminal branches of the brachial artery (namely the radial and ulnar arteries) also lie within the fossa. The floor of the cubital fossa (Fig. 3.29) is formed by supinator and brachialis overlying the capsule of the elbow joint.


Brachialis
Proximal limit of cubital fossa
Brachio-radialis
Tendon of biceps brachii (cut)
S
la
m
I
Common flexor origin
Pronator teres
Flexor carpi radialis

Fig. 3.28 Boundaries of the cubital fossa after removal of the roof and contents.


Tendon of brachialis
Posterior interosseous nerve
Superficial branch of radial nerve
Brachio-radialis
S
la
m
I
Medial epicondyle
Pronator teres
Tendon of biceps brachii (cut)
Supinator
Flexor carpi radialis

Fig. 3.29 Brachioradialis and pronator teres have been retracted to reveal the floor of the cubital fossa and expose the radial nerve.

Anterior Compartment of the Forearm

The anterior compartment of the forearm (Fig. 3.4) contains a superficial and a deep group of muscles, which include flexors of the wrist, fingers and thumb and two muscles that act as pronators. The compartment is traversed by the median and ulnar nerves and by the radial and ulnar arteries with their venae comitantes. A layer of deep fascia continuous with a similar layer on the posterior aspect of the limb encloses the compartment and provides additional attachment for the superficial muscles. In front of the carpus, deep fascia forms the flexor retinaculum (Fig. 3.30), which lies anterior to tendons in the carpal tunnel (p. 124). Subcutaneous tissue overlying the compartment contains cutaneous nerves and tributaries of the cephalic and basilic veins. Branches of the medial and lateral cutaneous nerves of the forearm may continue distal to the wrist over the carpal region of the hand.

Superficial muscles

The superficial muscles are, from lateral to medial, pronator teres, flexor carpi radialis, palmaris longus and flexor carpi ulnaris (Fig. 3.31). Flexor digitorum superficialis is also included in this group but is partly covered by the other muscles.

All the superficial muscles attach proximally to the common flexor origin on the front of the medial epicondyle of the humerus (Fig. 3.34). In addition, pronator teres attaches to the medial side of the coronoid process of the ulna, and flexor carpi ulnaris attaches to the medial border of the olecranon and the adjacent part of the subcutaneous border of the ulna. Flexor digitorum superficialis has an additional attachment to the ulnar collateral ligament of the elbow, the coronoid process and the anterior oblique line of the radius.

Distally, pronator teres attaches halfway along the lateral aspect of the shaft of the radius and forms the medial border of the cubital fossa. The muscle pronates the forearm. Flexor carpi radialis attaches to the bases of the second and third metacarpal bones (Fig. 3.37). It is a flexor and abductor of the wrist joint. Palmaris longus, a vestigial muscle that may be absent, has a long thin tendon, which attaches to the


S
la
m
I
Radial artery
Flexor digitorum superficialis
Median nerve
Ulnar nerve
Flexor retinaculum
Flexor digitorum superficialis tendons
Fibrous flexor sheath

Fig. 3.30 Flexor retinaculum revealed by removal of subcutaneous tissue and most of the deep fascia. The retinaculum is partly obscured by some of the intrinsic muscles of the hand.


S
la
m
I
Pronator teres
Flexor carpi radialis
Brachioradialis
Flexor carpi ulnaris
Extensor carpi radialis longus
Radial artery
Flexor digitorum superficialis
Abductor pollicis longus (cut)
Ulnar nerve
Median nerve

Fig. 3.31 Flexor carpi radialis and flexor carpi ulnaris seen after removal of deep fascia and the flexor retinaculum. This specimen lacks palmaris longus.

palmar aponeurosis. The muscle is a weak flexor of the wrist joint. Flexor carpi ulnaris attaches distally to the pisiform and, via ligaments from the pisiform, to the hook of the hamate and the base of the fifth metacarpal (Fig. 3.47). It is the most medial of the superficial muscles and is a flexor and adductor of the wrist.

Flexor digitorum superficialis (Fig. 3.32) is relatively large and is the deepest of this group of muscles. Distally, it gives rise to four tendons, one for each finger, which pass into the hand deep to the flexor retinaculum. In the carpal tunnel the tendons have a characteristic grouping (Fig. 3.32). Within each finger, the tendon forms two slips, which pass around the profundus tendon and then partly reunite before attaching to the sides of the middle phalanx (Fig. 3.37). The muscle flexes the wrist and the metacarpophalangeal and proximal interphalangeal joints of the fingers.

The superficial muscles all pass anterior to the elbow and therefore act as weak flexors of that joint in addition to their roles in the movements of the wrist and hand. Collectively, the carpal flexors and extensors stabilize the wrist joint during movements of the fingers and thumb. Inflammation at the common flexor origin (medial epicondylitis or Golfer's elbow) may follow unaccustomed use of the superficial forearm muscles and cause pain on flexion of the wrist joint.

All the superficial muscles are innervated by the median nerve, except flexor carpi ulnaris, which is supplied by the ulnar nerve.

Deep muscles

The deep muscles are flexor pollicis longus, flexor digitorum profundus and pronator quadratus. Their attachments to the radius and ulna are illustrated in Figure 3.34. Distally the flexor pollicis longus tendon (Fig. 3.35) passes through the carpal tunnel and attaches to the base of the distal phalanx of the thumb. The muscle flexes the interphalangeal and metacarpophalangeal joints of the thumb. Flexor digitorum profundus (Fig. 3.35) gives rise to four tendons, which traverse the carpal tunnel deep to the tendons of flexor digitorum superficialis (Fig. 3.40). In the palm, the tendons diverge, one entering each finger. Each tendon passes between the slips of


S
la
m
I
Brachio-radialis (cut)
Extensors carpi radialis longus and brevis (cut)
Flexor carpi radialis and ulnaris (cut)
Supinator
Pronator teres
Flexor digitorum super-ficialis
Flexor digitorum profundus
Flexor pollicis longus
Brachio-radialis tendon (cut)
Tendon of flexor carpi ulnaris (cut)
Tendon of flexor carpi radialis (cut)
Tendon of flexor digitorum profundus

Fig. 3.32 Flexor digitorum superficialis and pronator teres, revealed by division of flexors carpi ulnaris and radialis, and of brachioradialis. The vessels and nerves in the forearm have been removed.

the corresponding superficialis tendon, continuing distally to attach to the base of the terminal phalanx. The muscle is a flexor of the fingers and of the wrist joint. Pronator quadratus, a small rectangular muscle lying transversely between the anterior surfaces of the shafts of the radius and ulna (Fig. 3.33), pronates the forearm.

The deep muscles are innervated by the anterior interosseous nerve, except for the medial part of flexor digitorum profundus, which is supplied by the ulnar nerve.

Vessels

The brachial artery usually divides into the radial and ulnar arteries in the cubital fossa (Fig. 3.36). The radial artery passes distally, under brachioradialis, lying on the flexor muscles. In the lower forearm, the vessel is accompanied by the superficial branch of the radial nerve and, near the wrist, is subcutaneous and palpable against the anterior surface of the radius. The artery winds round the lateral aspect of the wrist, traverses the 'anatomical snuff box' and


Flexor pollicis longus
Anterior interosseous nerve and vessels
Flexor digitorum profundus
Interosseous membrane
S
la
m
I
Pronator quadratus
Flexor carpi ulnaris (cut)
Flexor carpi radialis (cut)
Abductor pollicis longus (cut)

Fig. 3.33 Pronator quadratus exposed by division of flexor pollicis longus and flexor digitorum profundus.


Medial supracondylar ridge
Coronoid process of ulna
Head
Neck
Tuberosity of radius
S
la
m
I
Head
Styloid process
Biceps brachii
Brachioradialis
Supinator
Flexor digitorum profundus
Pronator teres
Brachialis
Flexor pollicis longus
Common flexor origin
Pronator quadratus

Fig. 3.34 Anterior aspects of radius, ulna and distal end of humerus. The bones have been separated slightly.

subsequently enters the palm to form the deep palmar arch (Fig. 3.54). In the forearm, the artery gives branches to muscles and contributes to anastomoses around the elbow and wrist joints. Near the wrist, the radial artery is close to the cephalic vein. These vessels may be joined surgically to form an arteriovenous fistula for easy vascular access in patients undergoing renal dialysis.




Fused tendons of superficial flexors (cut)
Brachioradialis (cut)
Tendon of biceps brachii (cut)
Supinator
Flexor pollicis longus
Flexor digitorum profundus
Tendon of brachioradialis (cut)
Tendon of flexor carpi ulnaris (cut)
Tendon of flexor carpi radialis (cut)
Lumbricals
Tendons of flexor digitorum superficialis (cut)
S
la
m
I

Fig. 3.35 Flexor digitorum profundus and flexor pollicis longus exposed by removal of the superficial flexors. As in this specimen, the index component of flexor digitorum profundus is often separate from the rest of the muscle.

The ulnar artery passes deep to the arch formed by the radial and ulnar attachments of flexor digitorum superficialis and continues between the superficial and deep flexor muscles. In the distal part of the forearm, the artery is accompanied on its medial side by the ulnar nerve. It lies beneath flexor carpi ulnaris but at the wrist emerges to lie lateral to the tendon of this muscle, where its pulse can be palpated. The ulnar artery crosses superficial to the flexor retinaculum and, as it enters the hand, divides into superficial and deep palmar branches. The ulnar artery gives branches to the muscles of the anterior compartment and to the anastomoses around the elbow and wrist joints. Its largest branch, the common interosseous artery (Fig. 3.36), arises near the origin of the ulnar artery and promptly divides into posterior and anterior interosseous branches. The posterior interosseous artery enters the posterior interosseous compartment of the forearm (Fig. 3.77). The larger anterior interosseous artery passes distally in the anterior compartment, lying on the interosseous membrane, accompanied by the anterior nerve. The vessel supplies the deep flexor muscles and gives nutrient branches to the radius and ulna. Distally, it penetrates the interosseous membrane to assist in the anastomoses around the wrist. The patency of the ulnar and radial arteries and of the palmar arches can be assessed using Allen's test. After compression of both arteries, release of one artery should be followed within a few seconds by flushing of the whole hand. The compression is then repeated and followed by release of the other artery. Incomplete or slow flushing suggests poor blood flow through one of the arteries or its branches.

Venae comitantes accompany the arteries of the anterior compartment and drain proximally into veins around the brachial artery.

Nerves

The median nerve enters the forearm from the cubital fossa between the two heads of pronator teres. It crosses anterior to the ulnar artery (Fig. 3.36) and descends between the superficial and deep flexors. At the wrist, the median nerve is remarkably superficial, lying medial to the tendon of flexor carpi radialis and just deep to the palmaris longus tendon. The median nerve passes through the carpal tunnel into the hand, where it divides into terminal branches (Fig. 3.52). The nerve supplies all the superficial muscles of the anterior compartment except flexor carpi ulnaris. The anterior interosseous branch of the median nerve (Fig. 3.36) supplies all the deep muscles of the compartment except the medial part of flexor digitorum profundus. This branch lies between flexor digitorum profundus and flexor pollicis longus and passes behind pronator quadratus to supply the wrist (Fig. 3.33). In the forearm, the median nerve also gives a palmar cutaneous branch, which crosses superficial to the flexor retinaculum and supplies skin of the lateral part of the palm. Superficial lacerations near the wrist may damage the palmar cutaneous branches but leave the median and ulnar nerves intact. Testing digital sensation alone will miss injuries to these nerves supplying the palm.

The ulnar nerve passes behind the medial epicondyle where it can be palpated. Pressure here produces pain or tingling felt in the cutaneous distribution of the nerve along the medial side of the hand. Fractures involving the medial epicondyle may damage the ulnar nerve. The nerve enters the forearm between the two heads of flexor carpi ulnaris. Lying on flexor digitorum profundus and covered by flexor carpi ulnaris, it traverses the medial side of the anterior compartment, accompanied in the lower part of the forearm by the ulnar artery. Near the wrist, the ulnar nerve emerges lateral to the flexor carpi ulnaris tendon and crosses superficial to the flexor retinaculum with the ulnar artery on its lateral side. The nerve terminates in the hand by dividing into superficial and deep branches (p. 95). The ulnar nerve supplies the elbow joint and gives branches to flexor carpi ulnaris and the medial part of flexor digitorum profundus. It also provides a palmar cutaneous nerve supplying skin on the medial aspect of the palm, and dorsal cutaneous branches that innervate the medial part of the dorsum of the hand (Fig. 3.78).




Brachial artery and vena comitans
Radial nerve
Median nerve
Deep head of pronator teres
Common interosseous artery
Posterior interosseous artery
Anterior interosseous nerve
Anterior interosseous artery
Ulnar nerve
Ulnar artery
Radial artery
Median nerve
Superficial radial nerve
Flexor digitorum superficialis tendons (cut)
Flexor carpi radialis tendon (cut)
Flexor retinaculum
S
la
m
I

Fig. 3.36 Vessels and nerves of the anterior compartment of the forearm. The superficial flexor muscles and brachioradialis have been divided and most of the venae comitantes have been removed.

Palm and Digits

The hand comprises the wrist (carpus), the palm (metacarpus) and the digits (Figs 3.37 & 3.38). The palm of the hand (Fig. 3.39) contains the palmar aponeurosis, intrinsic muscles, tendons originating from muscles in the anterior compartment of the forearm, and palmar vessels and nerves. The intrinsic muscles comprise the thenar and hypothenar groups, the lumbricals and interossei, and adductor pollicis. The tendons enter the palm through the carpal tunnel (Fig. 3.98) deep to the flexor retinaculum. The skin of the anterior surface of the hand is thick, devoid of hair and contains many sweat glands. It is firmly bound to the underlying deep fascia, producing characteristic creases. Skin over the palmar surface of each distal phalanx is firmly tethered to the periosteum by fibrous septa, which enclose fat-filled spaces. Infection causing increased pressure in the pulp space may result in thrombosis of vessels supplying the distal phalanx causing bone necrosis.

Deep fascia of the palm

The deep fascia of the palm is thickened centrally to form the triangular palmar aponeurosis (Fig. 3.39) and is thinner at each side where it covers the thenar and hypothenar muscles. Proximally, the palmar aponeurosis attaches to the flexor retinaculum and is continuous with the tendon of palmaris longus. Distally, the aponeurosis gives rise to four pairs of digital slips, which cross the metacarpophalangeal joints and attach to the proximal phalanges of the fingers via the fibrous flexor sheaths. The aponeurosis covers the


d
m
la
pr
Distal phalanx
Middle phalanx
Proximal phalanx
Second metacarpal
Hamate
Triquetral
Pisiform
Lunate
Trapezoid
Capitate
Trapezium
Scaphoid
Flexor digitorum profundus
Flexor digitorum superficialis
Adductor pollicis
Opponens digiti minimi
Flexor pollicis longus
Abductor pollicis brevis
Opponens pollicis
Abductor digiti minimi
Abductor pollicis longus
Flexor carpi radialis
Flexor carpi ulnaris

Fig. 3.37 Bones of the hand. The distal attachments of the forearm flexor muscles and of the thenar and hypothenar muscles and the attachments of adductor pollicis are indicated.


d
m
la
pr
Distal phalanx
Middle phalanx
Proximal phalanx
Second metacarpal
Sesamoid bones
Capitate
Hamate and hook
Triquetral
Pisiform
Styloid process of ulna
Trapezoid
Trapezium
Scaphoid
Lunate
Radius

Fig. 3.38 Radiograph of an adult hand. (Compare Fig. 3.97.)

superficial palmar arch, the median nerve and the tendons of the long flexors of the digits. Thickening and shortening of the aponeurosis in Dupuytren's contracture produces fixed flexion of the metacarpophalangeal and proximal interphalangeal joints.

Lateral and medial septa pass from the edges of the palmar aponeurosis to the first and fifth metacarpal bones, respectively. These septa separate the thenar and hypothenar muscles from a central palmar space, which is traversed by the palmar digital vessels and nerves and by the tendons of the long flexor muscles of the fingers.

The subcutaneous tissue of the medial side of the palm usually contains palmaris brevis (Fig. 3.39), a small muscle attaching to the overlying skin and to the palmar aponeurosis.


Digital nerves
Fibrous flexor sheaths
Hypothenar muscles
Palmaris brevis
Flexor retinaculum
Ulnar nerve and artery
d
m
la
pr
Palmar aponeurosis
Thenar muscles
Abductor pollicis longus
Median nerve
Tendon of palmaris longus

Fig. 3.39 Palmar aponeurosis exposed by removal of skin and subcutaneous tissue.


Fibrous flexor sheaths
Tendons of flexor digitorum superficialis
Tendon of flexor digitorum profundus
Attachments of flexor retinaculum
Flexor carpi ulnaris
d
m
la
pr
First lumbrical muscle
Tendon of flexor pollicis longus
Thenar muscles (cut)
Flexor carpi radialis

Fig. 3.40 Tendons of flexor digitorum superficialis in the palm. The palmar aponeurosis, flexor retinaculum and palmar vessels and nerves have been removed.

Flexor tendons in the hand

The tendons of flexor pollicis longus, flexor digitorum profundus and flexor digitorum superficialis enter the hand deep to the flexor retinaculum (Fig. 3.99). On reaching the appropriate digit, each tendon traverses a tunnel formed by the fibrous flexor sheath and the phalanges (Fig. 3.40). The fibrous sheath is attached to the edges of the anterior surfaces of the phalanges (Fig. 3.41) and continues as far as the distal phalanx (Fig. 3.42). The sheath is thinner and more flexible in front of the interphalangeal joints, allowing flexion of the digit without 'bowstringing' of the tendons and thus facilitating gripping. Within the flexor sheaths the tendons are invested by synovial membrane and receive vincula tendinum, small folds of synovium that convey blood vessels to the tendons.


A
m
la
P
Tendon of flexor digitorum superficialis
Digital artery
Tendon of flexor digitorum profundus
Digital vein
Skin crease
Digital nerve
Fibrous flexor sheath
Proximal phalanx
Extensor expansion

Fig. 3.41 Transverse section through the index finger at the level of the proximal phalanx.


d
m
la
pr
Tendons of flexor digitorum profundus
Tendons of flexor digitorum superficialis (cut)
Lumbrical muscles
Tendon of flexor digitorum superficialis
Fibrous flexor sheath (cut)
Adductor pollicis
Flexor pollicis longus

Fig. 3.42 Digital fibrous flexor sheaths. The partially cut away sheath of the middle finger exposes the tendons of flexor digitorum superficialis and profundus, whose phalangeal attachments are revealed on the ring and little fingers.

Thenar muscles

Abductor pollicis brevis, flexor pollicis brevis and opponens pollicis form the thenar eminence on the lateral side of the palm. They attach proximally to the trapezium and scaphoid and to the lateral part of the flexor retinaculum (Fig. 3.37).

Abductor pollicis brevis (Fig. 3.43) lies superficial to the other thenar muscles and passes from the scaphoid to the base of the proximal phalanx of the thumb. The muscle abducts the thumb, moving the digit anteriorly at right angles to the plane of the palm.

Flexor pollicis brevis, lying deep and medial to the abductor, passes from the trapezium to the proximal phalanx of the thumb. The muscle flexes the carpometacarpal and metacarpophalangeal joints, drawing the thumb across the palm (maintaining the thumbnail at right angles to the palmar plane).

Opponens pollicis (Fig. 3.44), the deepest of the thenar muscles, attaches proximally to the trapezium and distally to the shaft of the first metacarpal. The muscle produces opposition of the thumb, allowing pulp-to-pulp contact with the fingers. This movement combines flexion, adduction and rotation of the first metacarpal at its carpometacarpal joint.

The thenar muscles are supplied by the recurrent branch of the median nerve (Figs 3.43 & 3.44). Injury to this nerve may be assessed by palpating the thenar muscles while the subject attempts abduction of the thumb.


Digital branches of median nerve
Recurrent branch of median nerve
d
m
la
pr
Flexor pollicis brevis
Abductor pollicis brevis
Opponens pollicis
Tendon of abductor pollicis longus

Fig. 3.43 Muscles of the thenar eminence exposed by removal of deep fascia. Abductor pollicis brevis is superficial to flexor pollicis brevis and opponens pollicis.


Adductor pollicis
Flexor pollicis brevis
Recurrent branch of median nerve
Opponens pollicis
Flexor retinaculum
d
m
la
pr

Fig. 3.44 Opponens pollicis and flexor pollicis brevis exposed by removal of abductor pollicis brevis.

Hypothenar muscles

Abductor digiti minimi, flexor digiti minimi brevis and opponens digiti minimi (Fig. 3.45) form the hypothenar eminence and attach proximally to the pisiform, the hook of the hamate and the adjacent part of the flexor retinaculum. Abductor digiti minimi passes from the pisiform to the base of the proximal phalanx of the little finger and abducts the digit, moving it medially in the plane of the palm. Flexor digiti minimi brevis attaches between the hamate and base of the proximal phalanx of the little finger and flexes the metacarpal and proximal phalanx of the little finger. Opponens digiti minimi passes from the hamate to the shaft of the fifth metacarpal and on contraction deepens the hollow of the palm.

The hypothenar muscles are supplied by the deep branch of the ulnar nerve (Fig. 3.45).

Deep muscles

The deep muscles of the hand consist of adductor pollicis, the palmar and dorsal interossei and the lumbricals.

Adductor pollicis (Fig. 3.46) has transverse and oblique heads. The transverse


Digital branches of ulnar nerve
d
m
la
pr
Abductor digiti minimi
Opponens digiti minimi
Flexor retinaculum
Flexor digiti minimi brevis
Deep branch of ulnar nerve

Fig. 3.45 Hypothenar muscles exposed by removal of the deep fascia.


Flexor sheaths
Deep transverse metacarpal ligament
Transverse head of adductor pollicis
Oblique head of adductor pollicis
Flexor retinaculum (cut)
First lumbrical muscle (cut)
Sheath of flexor pollicis longus
Flexor pollicis brevis (cut)
Opponens pollicis (cut)
d
m
la
pr

Fig. 3.46 Adductor pollicis. The muscles of the thenar eminence, long flexor tendons, and palmar and digital vessels and nerves have been removed.

head attaches to the shaft of the third metacarpal bone, and the oblique head to the trapezoid, capitate and bases of the second and third metacarpals. Both heads pass laterally to attach to the base of the proximal phalanx of the thumb by a common tendon which usually contains a sesamoid bone (Fig. 3.38). The muscle adducts and flexes the thumb at its carpometacarpal and metacarpophalangeal joints and is supplied by the deep branch of the ulnar nerve (Fig. 3.54).

The interossei consist of three palmar and four dorsal muscles (Fig. 3.47). Each palmar interosseous muscle (Fig. 3.48) arises by a single head from the anterior border of the shaft of the second, fourth or fifth metacarpal. Each dorsal interosseous


d
m
la
pr
Dorsal interossei
Second lumbrical muscle (cut)
Deep transverse metacarpal ligament
Pisohamate ligament
Palmar interossei

Fig. 3.47 Palmar and dorsal interossei exposed by removal of the long flexor tendons and adductor pollicis. The dorsal interossei have much more bulk than the palmar interossei.


d
m
la
pr
Palmar interossei
First dorsal interosseous muscle (cut)
Flexor retinaculum (cut)
Flexor carpi radialis tendon
Tendon of abductor pollicis longus (cut)

Fig. 3.48 Palmar interossei. The dorsal interossei and deep transverse metacarpal ligaments have been excised.

muscle (Fig. 3.49) arises by two heads from the contiguous sides of the shafts of the adjacent metacarpals. Distally the tendon of each interosseous muscle attaches to the base of the proximal phalanx and to the extensor expansion of the appropriate digit (Fig. 3.51). The interossei move the fingers in the plane of the palm (coronal plane); movement of a finger away from the long axis of the middle finger is called abduction while movement towards the middle finger is adduction. The palmar interossei adduct and the dorsal interossei abduct the fingers. In addition, the interossei flex the metacarpophalangeal joints and extend the interphalangeal joints. All the interossei are supplied by the deep branch of the ulnar nerve (Fig. 3.54). The integrity of the nerve and the adducting function of the palmar interossei can be tested by gripping a sheet of paper between the sides of two adjacent fingers.

The lumbricals are four small muscles attaching proximally to the tendons of flexor digitorum profundus (Fig. 3.50). Distally, each lumbrical attaches to the radial side of the extensor expansion of the appropriate finger. The muscles extend the interphalangeal joints and flex the metacarpophalangeal joints. The first and second lumbricals usually have only one head each and are supplied by the median nerve, whereas the third and fourth (medial) usually have two heads and are supplied by the ulnar nerve.




Extensor expansions
Tendons of extensor digitorum (cut)
d
la
m
pr
Dorsal interossei
Extensor carpi radialis brevis
Radial artery
Extensor carpi radialis longus
Extensor carpi ulnaris

Fig. 3.49 Dorsal interossei exposed by removal of deep fascia and tendons of extensor digitorum.




Flexor digitorum superficialis (cut)
Adductor pollicis
d
m
la
pr
Bipennate lumbricals
Tendons of flexor digitorum profundus
Unipennate lumbricals
Tendon of flexor pollicis longus

Fig. 3.50 Removal of the tendons of flexor digitorum superficialis has revealed the attachments of the lumbrical muscles to the tendons of flexor digitorum profundus.

Digital extensor expansions

Each finger possesses an extensor expansion or hood (Fig. 3.51), which receives the tendons of the appropriate long extensor muscle(s), interossei and lumbricals. The broad proximal part of the expansion overlies the metacarpophalangeal joint. Distally, the expansion tapers and attaches by a central slip to the base of the middle phalanx and by two marginal slips to the base of the distal phalanx.

Blood vessels

The arterial supply to the hand is derived from branches of the ulnar and radial arteries, which form superficial and deep palmar arches linking the two main arteries and ensuring a rich blood supply to the palm and fingers.

The ulnar artery enters the hand superficial to the flexor retinaculum and gives a deep branch that accompanies the deep branch of the ulnar nerve. The main artery continues as the superficial palmar arch (Fig. 3.52), which passes distally to the level of the thumb web, lying deep to the palmar aponeurosis but anterior to the digital nerves and flexor tendons. The superficial palmar arch gives four palmar digital branches, which supply the adjacent sides of the fingers (Fig. 3.53) and medial side of the little finger, and is completed laterally by a branch of the radial artery.

The radial artery enters the palm from the dorsum of the hand between the two heads of the first dorsal interosseous muscle (Fig. 3.49). The artery gives branches to the thumb and index finger and continues as the deep palmar arch (Fig. 3.54), which lies over the bases of the metacarpal bones, deep to the flexor tendons, and is about 1 cm proximal to the superficial arch. The deep arch provides perforating branches, which anastomose with dorsal metacarpal arteries, and three palmar metacarpal arteries, which anastomose with the palmar digital arteries of the superficial arch. The deep arch is completed medially by the deep branch of the ulnar artery. Other vessels such as dorsal metacarpal arteries from the dorsal carpal arch may provide an important supply of blood to the hand. The anastomoses between branches of arteries supplying the hand usually provide an adequate blood supply even if one artery is blocked.




Distal phalanx
Attachment to distal phalanx
Capsules of interphalangeal joints
Attachment to middle phalanx
Second dorsal interosseous muscle (cut)
Tendon of extensor digitorum
Third dorsal interosseous muscle (cut)
Second lumbrical muscle (cut)
d
la
m
pr

Fig. 3.51 Dorsal view of the digital expansion of the middle finger. The expansion has been flattened proximally to show the attachments of lumbrical and interosseous muscles.




d
m
la
pr
Digital arteries
Digital branches of ulnar nerve
Superficial palmar arch
Ulnar nerve and artery
Median nerve
Digital branches of median nerve
Recurrent branch of median nerve
Flexor retinaculum
Radial artery and vena comitans
Tendon of flexor carpi radialis

Fig. 3.52 Superficial vessels and nerves of the palm. Skin, subcutaneous tissue and the palmar aponeurosis have been removed.

Most venous blood from the fingers and palm drains into superficial veins on the dorsum of the hand to enter the cephalic or basilic veins.

Nerves

Innervation of the anterior aspect of the hand is shared by the ulnar and median nerves. The ulnar nerve supplies more intrinsic muscles than the median nerve, which supplies a larger area of skin.

The ulnar nerve (Fig. 3.52) enters the palm superficial to the flexor retinaculum and terminates as superficial and deep branches. The superficial branch supplies digital branches to the skin of the medial one and one-half digits. A corresponding area of the palm is supplied by palmar branches that arise from the ulnar nerve in the forearm. The deep branch of the ulnar nerve (Fig. 3.54) accompanies the deep palmar arch and supplies the three hypothenar muscles, the medial two lumbricals, all the interossei and adductor pollicis. The ulnar nerve also supplies palmaris brevis. Injury to the ulnar nerve produces marked wasting (atrophy) of the muscles between the first and second metacarpal bones.

The median nerve traverses the carpal tunnel and terminates as digital and recurrent branches. The digital branches (Fig. 3.52) supply skin of the lateral three-and-one-half digits and usually the lateral two lumbricals. A corresponding area of the palm is supplied by palmar branches arising from the median nerve in the forearm. The recurrent branch of the median nerve (Fig. 3.43) supplies the three thenar muscles.

In the palm, the digital branches of the ulnar and median nerves lie deep to the superficial palmar arch (Fig. 3.52), but in the fingers they lie anterior to the digital arteries arising from the superficial arch (Fig. 3.53). Although there may be variability of innervation of the ring and middle fingers, the skin on the anterior surface of the thumb is always supplied by the median nerve and that of the little finger by the ulnar nerve. The palmar digital branches of the median and ulnar nerves also supply the nail beds of their respective digits.


d
m
la
pr
Connective tissue of pulp space
Digital arteries
Digital branches of median nerve
Fibrous flexor sheath
Lumbrical muscle
Tendon of flexor digitorum superficialis
Superficial palmar arch

Fig. 3.53 Palmar digital arteries and nerves of the fingers.


d
m
la
pr
Metacarpal arteries
Deep branch of ulnar nerve
Flexor retinaculum (cut)
Ulnar nerve (cut)
First dorsal interosseous muscle
Adductor pollicis (cut)
Deep palmar arch
Radial artery

Fig. 3.54 Deep palmar arch and deep branch of ulnar nerve. The long flexor tendons and muscles of the thenar eminence have been removed, and adductor pollicis and the hypothenar muscles divided.

Muscles Attaching the Upper Limb to the Trunk

Three muscles connect the root of the upper limb to the chest wall and are usually dissected with the thorax. For this reason, pectoralis major and minor and serratus anterior are described with the thoracic wall (p. 31). Only the posterior group of muscles attaching the limb and its girdle to the vertebral column are described here: trapezius, latissimus dorsi, levator scapulae and the rhomboids (Fig. 3.55).

Trapezius

Trapezius (Fig. 3.56) is a large superficial muscle overlying the dorsum of the neck and thorax. Its upper fibres attach to the ligamentum nuchae, the external occipital protuberance and the superior nuchal line and pass downwards and laterally to the acromion of the scapula and the lateral part of the clavicle. These fibres produce elevation of the scapula as in shrugging the shoulder. When the scapula is fixed, they produce lateral flexion of the neck. The middle fibres of trapezius run horizontally from the ligamentum nuchae and upper thoracic spinous processes to the acromion and spine of the scapula and retract the scapula. Fibres of the lower part of the muscle attach to the lower thoracic spinous processes superficial to latissimus dorsi (Fig. 3.56) and pass upwards and laterally to the spine of the scapula. These fibres depress the scapula. Acting together, the upper and lower parts of trapezius produce rotation of the scapula, turning the glenoid fossa superiorly to permit full abduction of the limb (p. 117). In the neck, the anterior edge of the muscle forms the posterior boundary of the posterior triangle. The accessory nerve crosses the triangle (Fig. 7.9) and supplies the trapezius from its deep surface.



Fig. 3.55 Attachments of trapezius, rhomboid major and minor, levator scapulae and latissimus dorsi.


Left trapezius
Splenius capitis
Right trapezius
S
L
R
I
Fascia overlying deltoid
Fascia overlying infraspinatus
Teres major
Rhomboid major
Latissimus dorsi
Spinous processes

Fig. 3.56 The trapezius muscles have fascial attachments to the cervical and thoracic spinous processes and, in this dissection, are asymmetric inferiorly.


Splenius capitis
Levator scapulae
S
L
R
I
Rhomboid minor
Trapezius (cut)
Fascia overlying infraspinatus
Rhomboid major

Fig. 3.57 Levator scapulae and rhomboids exposed by removal of trapezius.

Levator scapulae and rhomboids

These three muscles are covered by the trapezius. Levator scapulae (Fig. 3.57) ascends from the medial border of the scapula above the root of the spine to the transverse processes of the upper four cervical vertebrae. The fibres of the rhomboids incline upwards and medially (Fig. 3.57). Rhomboid minor attaches to the medial border of the scapula at the root of its spine and to the spinous processes of the seventh cervical and first thoracic vertebrae. Rhomboid major passes between the remainder of the medial border of the scapula and the spines of the second to fifth thoracic vertebrae.

All three muscles elevate the scapula and assist in scapular rotation during adduction of the upper limb. The dorsal scapular nerve from the brachial plexus (C5) supplies the rhomboids and may innervate levator scapulae, which is also supplied by branches from the cervical plexus (C3 & C4).

Latissimus dorsi

Latissimus dorsi (Fig. 3.58) is a large triangular muscle overlying much of the dorsal aspect of the trunk. The muscle attaches to the spinous processes of the lower six thoracic vertebrae and through the lumbar fascia to the spines of the lumbar vertebrae and the sacrum. The most inferior fibres attach to the posterior part of the iliac crest. Fibres also attach to the lower four ribs and to the inferior angle of the scapula. All the fibres converge on a narrow tendon in the posterior fold of the axilla. The tendon winds round the lower border of teres major to attach to the intertubercular sulcus of the humerus.

The muscle is a powerful adductor and extensor of the humerus at the shoulder joint, particularly when the upper limb is abducted and flexed. Latissimus dorsi is also a medial rotator at the shoulder joint and assists with rotation and retraction of the scapula. In movements such as rising from an armchair, if the humerus is fixed, both muscles contract to raise the trunk. This action is particularly important in patients with paralysed lower limbs. Latissimus dorsi is supplied by a single neurovascular bundle which contains the thoracodorsal nerve (a branch of the posterior cord of the brachial plexus; Fig. 3.18) and the thoracodorsal vessels, which are branches of the subscapular vessels. In reconstructive surgery, the muscle and its overlying skin may be mobilized on this neurovascular pedicle to provide a large myocutaneous flap.



Fig. 3.58 Latissimus dorsi. The anterior border lies parallel to the cut skin edge, and the thoracic attachment has been exposed by removal of trapezius.

Short Scapular Muscles

These short muscles, the four rotator cuff muscles and teres major, span the shoulder (glenohumeral) joint, attaching to the scapula and to the proximal part of the humerus (Figs 3.59 & 3.62).

Rotator cuff muscles

This important group of muscles, namely subscapularis, supraspinatus, infraspinatus and teres minor, is intimately related to the shoulder joint. By attaching not only to the tubercles of the humerus but also to the capsule of the joint, they hold the humeral head firmly in the glenoid fossa and help stabilize the joint.

Subscapularis

Subscapularis (Fig. 3.60) attaches proximally to the medial part of the costal surface of the scapula. Its tendon, separated from the neck of the scapula by the subscapular bursa, is attached to the lesser tubercle of the humerus. The muscle is supplied by the subscapular nerves from the posterior cord of the brachial plexus. Subscapularis produces medial rotation of the arm at the shoulder joint.


Superior angle
Acromion
Suprascapular notch
Coracoid process
Medial border
Inferior angle
S
la
m
I
Subscapularis
Serratus anterior
Pectoralis minor
Biceps brachii and coracobrachialis
Latissimus dorsi
Teres major

Fig. 3.59 Anterior aspects of scapula and proximal end of humerus. The head of the humerus is partly obscured by the overlying coracoid process of the scapula.


Supra-spinatus
Coracoid process
Tendon of biceps brachii (cut)
Lesser tubercle of humerus
Tendon of long head of biceps brachii (cut)
Tendon of latissimus dorsi (cut)
Tendon of teres major (cut)
Superior angle of scapula
Supra-scapular ligament
Medial border of scapula
Sub-scapularis
S
la
m
I

Fig. 3.60 Anterior view of subscapularis. The attachment of serratus anterior to the medial border of the scapula has been excised.


Superior angle of scapula
Attachment of coraco-clavicular ligament
Supra-spinatus
Spine of scapula (cut)
A
m
la
P
Coraco-acromial ligament (cut)
Tendon fused with capsule of shoulder joint
Infra-spinatus

Fig. 3.61 Superior view of supraspinatus after removal of the acromion of the scapula.

Supraspinatus

Supraspinatus (Fig. 3.61) attaches to the supraspinous fossa of the scapula and to the superior facet of the greater tubercle of the humerus (Fig. 3.62). The subacromial bursa lies above the tendon of supraspinatus, separating the tendon and the capsule of the shoulder joint from the coracoacromial arch. The muscle initiates abduction of the shoulder joint. Tendinitis results in an arc of painful movement from about 60° to 120° of abduction. Complete rupture may lead the patient to develop a trick movement in which the body is tilted so that the limb abducts passively until deltoid can abduct the joint actively.

Infraspinatus

Infraspinatus (Fig. 3.63) arises from the infraspinous fossa, and its tendon inserts into the middle facet of the greater tubercle of the humerus. The muscle is covered by a strong fascial membrane. A bursa sometimes separates the tendon from the neck of the scapula.

Supraspinatus and infraspinatus are supplied by the suprascapular nerve, which arises from the upper trunk of the brachial plexus and passes beneath the suprascapular ligament (Fig. 3.59).


Superior border
Coracoid process
Spine of scapula
Greater tubercle
Acromion
Lateral border
S
m
la
I
Supraspinatus
Infraspinatus
Teres major
Teres minor
Triceps long head
Deltoid

Fig. 3.62 Posterior aspects of scapula and proximal end of humerus. The head of the humerus is partly obscured by the overlying acromion of the scapula.


Spine of scapula (cut)
Infra-spinatus
Medial border of scapula
Sub-scapularis
Attachment of teres major
Inferior angle of scapula
Supraspinatus
Tendons fused with capsule of shoulder joint
Teres minor
Surgical neck of humerus
Lateral head of triceps
Long head of triceps
S
m
la
I

Fig. 3.63 Posterior view of infraspinatus and teres minor. Teres major has been removed.

Teres minor

Teres minor (Fig. 3.63) attaches to the posterior surface of the scapula along the upper part of the lateral edge and to the inferior facet of the greater tubercle of the humerus. It is supplied by the axillary nerve.

Both infraspinatus and teres minor laterally rotate the humerus at the shoulder joint. Fractures of the greater tubercle of the humerus may detach infraspinatus and teres minor from the humerus, allowing muscle spasm to produce medial rotation at the shoulder joint.

Teres major

Teres major (Fig. 3.64) is a short bulky muscle, which attaches to the lower part of the posterior surface of the scapula. Laterally, the muscle attaches below the lesser tubercle of the humerus to the medial lip of the intertubercular sulcus (Fig. 3.59). Teres major is supplied by the lower subscapular nerve and adducts and medially rotates the humerus at the shoulder joint.

The axillary nerve and posterior circumflex humeral vessels pass between the teres minor and major muscles, lateral to the long head of triceps, through the quadrangular space (Fig. 3.64). Near the space, the axillary nerve and the posterior circumflex humeral artery are closely related to the surgical neck of the humerus, and fracture of the neck may damage both structures.


Quadrangular space
Infraspinatus
Teres minor
Axillary nerve
Teres major
Long head of triceps
Radial nerve
Lateral head of triceps
S
m
la
I

Fig. 3.64 Teres major and minor. The axillary nerve passes above teres major while the radial nerve lies below the muscle. Both nerves pass lateral to the long head of triceps.


Infra-
spinatus
Teres minor
Deltoid
(cut)
Teres
major
(cut)
Lateral head
of triceps
Long head
of triceps
Tendon of
triceps
Medial
epicondyle
S
m
la
I

Fig. 3.65 Posterior aspect of triceps. Teres major and the posterior fibres of deltoid have been excised.


Teres minor
Long head
of triceps
Inter-
muscular
space
Lateral
head of
triceps
(cut and
retracted)
Medial
head of
triceps
Olecranon
S
m
la
I

Fig. 3.66 The medial head of triceps has been exposed by removal of deltoid and division and retraction of the lateral head.

Posterior Compartment of the Arm

The posterior compartment of the arm contains triceps brachii, the radial nerve accompanied by the profunda brachii artery with its venae comitantes, and the ulnar nerve.

Triceps brachii

Proximally, this muscle attaches to the scapula and the humerus by three heads. The tendon of the long head (Fig. 3.65) attaches to the infraglenoid tubercle of the scapula, and the lateral head attaches to the posterior aspect of the shaft of the humerus above the radial groove (spiral groove, sulcus of the radial nerve) (Fig. 3.67). Both the long and lateral heads lie superficial to the medial head (Fig. 3.66), which has an extensive origin from the lateral and medial intermuscular septa and from the shaft of the humerus below the radial groove. Distally, the three heads fuse, and triceps attaches by a single tendon to the olecranon process of the ulna. Frequently, a bursa lies deep to the tendon, separating it from the capsule of the elbow joint. The three heads are supplied separately by branches of the radial nerve. Triceps is a powerful extensor of the elbow joint. The long head alone spans the shoulder joint and may assist in stabilizing that joint, particularly in full abduction.

Vessels and nerves

Radial nerve

The radial nerve, a terminal branch of the posterior cord, leaves the axilla by passing below teres major and between the humerus and the long head of triceps (Fig. 3.64). In the posterior compartment, the nerve passes between the medial and lateral heads of triceps and in the radial groove is intimately related to the shaft of the humerus (Fig. 3.68). It then leaves the posterior compartment by piercing the lateral intermuscular septum to reach the lateral part of the cubital fossa in front of the elbow joint (Fig. 3.29). In the arm, the radial nerve gives muscular branches to the medial and lateral heads of triceps and to brachioradialis and extensor carpi radialis longus, and cutaneous branches to the lateral aspect of the arm and the posterior aspect of the forearm. The branch to the


Head
Greater tubercle
Surgical neck
Sulcus for radial nerve
S
m
la
I
Attachment of capsule
Triceps lateral head
Triceps medial head
Teres minor
Medial epicondyle
Olecranon fossa
Trochlea

Fig. 3.67 Posterior aspect of humerus.

long head of triceps usually arises in the axilla. The radial nerve may be damaged in the radial groove by fracture of the shaft of the humerus (p. 113), but the branches to triceps, which arise more proximally, are usually spared.

Profunda brachii artery

The profunda brachii artery, a proximal branch of the brachial artery (Fig. 3.18), supplies the posterior compartment and accompanies the radial nerve in the radial groove of the humerus (Fig. 3.68). It gives muscular branches and contributes to the anastomosis around the elbow joint. The venae comitantes of the profunda brachii artery drain into the axillary vein.

Ulnar nerve

The ulnar nerve passes from the anterior to the posterior compartment by piercing the medial intermuscular septum at about midarm level (Fig. 3.24) and descends between the septum and the medial head of triceps. At the elbow it passes posterior to the medial epicondyle of the humerus, medial to the joint, and enters the forearm between the humeral and ulnar heads of flexor carpi ulnaris. The nerve gives no branches in the arm.


Teres major
Tendon of latissimus dorsi
Radial nerve
Medial head of triceps
Nerve to lateral head of triceps
Profunda brachii artery
Nerve to medial head of triceps
Shaft of humerus
Radial nerve
Venae comitantes
S
m
la
I

Fig. 3.68 The radial nerve and profunda brachii artery in the radial groove, seen after retraction of the cut lateral head of triceps. The long head has been excised.

Posterior Compartment of the Forearm

The posterior compartment of the forearm lies behind the radius and ulna and the intervening interosseous membrane. It contains the extensor muscles of the wrist and fingers, the extensors and long abductor of the thumb, and also brachioradialis, supinator and anconeus. The muscles are supplied by the posterior interosseous artery and nerve (deep branch of the radial nerve), assisted by the radial nerve itself. The compartment is enclosed by a layer of deep fascia, which attaches to the posterior


Extensor digitorum
Extensor carpi ulnaris
Abductor pollicis longus
Extensor retinaculum
Extensor pollicis longus
Extensor digitorum
Extensor indicis
S
m
la
I

Fig. 3.69 Extensor retinaculum exposed by removal of subcutaneous tissue and deep fascia. The fibres of the retinaculum run obliquely, passing medially and inferiorly from the radius towards the hamate and pisiform bones.


Common extensor origin
Anconeus
Extensor digitorum
Flexor carpi ulnaris
Extensor carpi radialis longus
Extensor carpi ulnaris
Abductor pollicis longus
Radius
Ulna
Extensor carpi radialis longus and brevis
Extensor pollicis longus
Extensor digiti minimi
Extensor digitorum
Extensor indicis
S
m
la
I

Fig. 3.70 Superficial muscles of the posterior compartment exposed by removal of deep fascia and the extensor retinaculum. Flexor and extensor carpi ulnaris lie edge to edge along the subcutaneous border of the ulna.

(subcutaneous) border of the ulna. In the region of the wrist the fascia is thickened to form the extensor retinaculum (Fig. 3.69). The extensor tendons, invested by synovial sheaths, pass deep to the retinaculum and enter the hand.

Superficial muscles

Four superficial extensors attach proximally to the anterior surface of the lateral humeral epicondyle at the common extensor origin (Fig. 3.70). Extensor carpi radialis brevis (Fig. 3.71) passes distally to the base of the third metacarpal and is an extensor and abductor of the wrist. Extensor digitorum (Figs 3.69 & 3.70) has four tendons which pass to the fingers and form the dorsal expansions or extensor hoods (Fig. 3.51). On the dorsum of the hand these tendons are interconnected by fibrous bands. The muscle is an extensor of the fingers and the wrist joint. Extensor digiti minimi (Fig. 3.70) attaches via two tendons to the dorsal expansion of the little finger and assists extension of this finger. Extensor carpi ulnaris (Fig. 3.70) attaches proximally to both the common extensor origin and the posterior surface of the ulna. Distally, it attaches to the base of the fifth metacarpal bone. The muscle is an extensor and adductor of the wrist. These four superficial extensors span the elbow but, since their attachments are close to the axis of movement, do not act effectively on that joint. They are innervated by the posterior interosseous (deep branch of the radial) nerve.

Two other superficial muscles, brachioradialis and extensor carpi radialis longus, arise from the lateral supracondylar ridge of the humerus and are innervated directly from the main trunk of the radial nerve. Brachioradialis (Figs 3.71 & 3.72) arises from the upper two-thirds of the ridge and attaches distally to the radial styloid process. The muscle is a flexor of the elbow joint


Brachialis
Triceps
Brachio-radialis
Extensor carpi radialis longus
Extensor carpi radialis brevis
Shaft of ulna
Tendon of abductor pollicis longus (cut)
Radial artery
S
P
A
I

Fig. 3.71 Extensors carpi radialis longus and brevis, and brachioradialis after removal of abductor pollicis longus and extensors pollicis longus and brevis.


Brachialis
Radial nerve
Biceps brachii tendon (cut)
Brachio-radialis
Flexor carpi radialis
Extensor carpi radialis longus tendon
Radial artery
Abductor pollicis longus tendon (cut)
Thenar muscles
Hypo-thenar muscles
S
la
m
I

Fig. 3.72 Brachioradialis (anterior aspect). The muscle forms the lateral boundary of the cubital fossa and covers the radial artery and the superficial branch of the radial nerve in the forearm.

and rotates the forearm from full pronation or supination into an intermediate position. Extensor carpi radialis longus (Figs 3.70 & 3.71) arises from the lower third of the supracondylar ridge and attaches distally to the base of the second metacarpal bone. The muscle is an extensor and abductor of the wrist joint.

In addition to their primary roles, the three carpal extensors provide an essential contribution to the power grip by fixing the wrist in an optimum position while the long flexors act on the fingers. Overuse of the muscles attaching to the lateral epicondyle may produce inflammation near the attachment with pain during extension of the wrist and fingers (lateral epicondylitis or 'tennis elbow').

Deep muscles

The proximal attachments of four of the deep muscles are illustrated in Figure 3.73. The tendon of extensor indicis (Fig. 3.74) passes distally, medial to that of extensor digitorum, and attaches to the extensor expansion of the index finger. The extensor pollicis longus tendon passes distally around the ulnar (medial) side of


Olecranon fossa
Medial epicondyle of humerus
Olecranon of ulna
Head of radius
Dorsal tubercle of radius
S
m
la
I
Supinator
Triceps brachii
Anconeus
Abductor pollicis longus
Extensor pollicis longus
Extensor indicis
Extensor pollicis brevis
Pronator teres

Fig. 3.73 Posterior aspects of radius, ulna and distal end of humerus.

the dorsal tubercle of the radius (Fig. 3.74), then crosses the radial extensors of the carpus to attach to the base of the distal phalanx of the thumb (Fig. 3.75). The muscle extends the thumb and its carpometacarpal joint. The tendons of extensor pollicis brevis and abductor pollicis longus (Fig. 3.75) lie together as they cross the radial carpal extensors and brachioradialis. Extensor pollicis brevis attaches to the base of the proximal phalanx of the thumb, which it extends. Abductor pollicis longus attaches to the base of the first metacarpal bone, which it extends and abducts.

Although these four deep muscles act primarily on the joints of the hand, they also span the wrist joint; but their actions here are weak. They are all innervated by the posterior interosseous (deep branch of the radial) nerve.

Extension of the thumb creates a hollow on the posterolateral aspect of the wrist called the anatomical snuff box (Fig. 3.75). It is limited anteriorly by the tendons of abductor pollicis longus and extensor pollicis brevis and posteriorly by extensor pollicis longus. Superficial to the snuff box lie the origin of the cephalic vein and branches of the superficial radial nerve supplying the dorsum of the hand. The branches can be palpated where they cross superficial to the tendon of extensor pollicis longus. The tendons of the two radial carpal extensors and the radial artery pass through the snuff box. The bony floor comprises the radial styloid process, scaphoid, trapezium and base of the first metacarpal bone. Fracture of the scaphoid bone often produces pain, swelling and tenderness in the snuff box (p. 122).




Supinator
Flexor carpi ulnaris
Abductor pollicis longus
Subcutaneous border of ulna
Extensor pollicis longus
Extensor indicis
Extensor pollicis brevis
Dorsal tubercle of radius
Tendon of extensor carpi ulnaris (cut)
Extensor carpi radialis brevis and longus
Extensor digitorum (cut)
S
m
la
I

Fig. 3.74 Extensor indicis and extensors pollicis longus and brevis, after division of extensor digitorum. The tendon of extensor indicis lies on the ulnar (medial) side of the index tendon of extensor digitorum.


Supinator
Brachio-radialis
Extensor carpi radialis brevis
Subcutaneous border of ulna
Abductor pollicis longus and tendon
Extensor pollicis brevis and tendon
Extensor indicis
Extensor carpi radialis longus
Radial artery
Extensor pollicis longus
S
P
A
I

Fig. 3.75 Abductor pollicis longus and extensors pollicis longus and brevis. At the wrist, the radial carpal extensors are crossed by the tendons of these three muscles passing to the thumb.


Triceps
Lateral epicondyle of humerus
Anconeus
Oblique head of supinator
Transverse head of supinator
Shaft of ulna
Interosseous membrane
Brachialis
Radial nerve
Posterior inter-osseous nerve
Superficial branch of radial nerve
Posterior inter-osseous nerve
Shaft of radius
S
P
A
I

Fig. 3.76 Supinator, revealed by removal of the other muscles of the posterior compartment. The posterior interosseous nerve passes between the transverse and oblique heads of the muscle.

Supinator, also a deep muscle, consists of oblique and transverse heads (Fig. 3.76). The oblique head attaches to the lateral epicondyle and collateral ligament, while the transverse head is attached to the supinator crest of the ulna. Both heads wind laterally around the proximal part of the radius and attach to its anterior surface (Fig. 3.73). The muscle supinates the forearm and is supplied by the deep branch of the radial nerve (posterior interosseous nerve), which passes between the two heads of the muscle (Fig. 3.77).

Vessels

In the cubital fossa, the common interosseous branch of the ulnar artery divides into larger anterior and smaller posterior interosseous arteries, which pass distally into their respective compartments of the forearm. The posterior interosseous artery (Fig. 3.77) lies between and supplies the superficial and deep groups of muscles. Near the wrist, a branch of the anterior interosseous artery penetrates the interosseous membrane to assist in the supply of the distal part of the posterior compartment. In addition, muscles on the lateral aspect of the compartment may receive blood from branches of the radial artery. The arteries of the compartment are accompanied by venae comitantes that drain into veins accompanying the brachial artery.

On the dorsum of the wrist, the radial artery enters the anatomical snuff box from the anterior compartment of the forearm deep to the tendons of abductor pollicis longus and extensor pollicis brevis. The artery crosses the floor of the snuff box and leaves the dorsum of the hand by penetrating the first dorsal interosseous muscle to enter the palm.

Nerves

The posterior compartment of the forearm is supplied by the radial nerve, which leaves the arm by penetrating the lateral intermuscular septum. Anterior to the elbow, the nerve lies between brachialis and brachioradialis and divides into superficial and deep branches (Fig. 3.76). The superficial branch continues distally through the forearm covered by brachioradialis, leaving its posterior border near the wrist and crossing the snuff box to terminate as cutaneous branches on the dorsum of the hand (Fig. 3.78). The deep branch, the posterior interosseous nerve, arises from the radial nerve at the level of the neck of the radius and enters the posterior compartment by passing between the two heads of supinator (Fig. 3.77). Initially, it accompanies the posterior interosseous artery but distally lies more deeply on the interosseous membrane. The posterior interosseous nerve gives branches to the elbow, radioulnar and wrist joints, and supplies most of the posterior compartment muscles. Brachioradialis and extensor carpi radialis longus are supplied directly by the radial nerve from branches arising in the arm, and anconeus is supplied by the branch of the radial nerve to the medial head of triceps. Damage to the radial nerve or to its posterior interosseous branch may weaken the extensor muscles of the wrist and fingers, so that they are unable to overcome gravity, causing 'wrist drop'.


Anconeus
Common extensor attachment (cut)
Oblique head of supinator (cut)
Extensor carpi radialis brevis
Posterior interosseous nerve
Posterior interosseous artery
Transverse head of supinator
Extensor carpi ulnaris
Abductor pollicis longus
S
m
la
I

Fig. 3.77 Posterior interosseous artery and nerve, exposed by division of extensor digitorum. The specimen is partly pronated, so the radial border of the forearm faces anteriorly.

Dorsum of the Hand

The dorsum of the hand is innervated by branches of the radial and ulnar nerves (Fig. 3.78). The superficial branch of the radial nerve usually supplies the skin of the lateral three and one-half digits (excluding the nail beds) and a corresponding part of the dorsum of the hand. Skin of the dorsal aspect of the first web space is usually supplied exclusively by the radial nerve and is tested when radial nerve injury is suspected. The skin over the remainder of the posterior aspect of the hand and the medial one and one-half fingers (excluding the nail beds) is supplied by dorsal branches of the ulnar nerve that arise in the anterior compartment and pass around the medial aspect of the wrist.

Much of the venous blood from the digits and the palm drains into a network of vessels that often forms a superficial venous arch on the dorsum of the hand.

At the wrist, the tendons of extensor digitorum lie deep to the extensor retinaculum (Fig. 3.79), invested by a single synovial sheath. On the dorsum of the hand, the tendons diverge to reach the fingers.

Skin on the dorsum of the hand is elastic and freely mobile on the underlying loose connective tissue: infection or injury of the hand frequently results in swelling (oedema) of these lax tissues.




d
la
m
pr
Dorsal digital nerves
Extensor tendons beneath fascia
Superficial branch of radial nerve
Communication between ulnar and radial nerves
Dorsal branch of ulnar nerve

Fig. 3.78 Cutaneous branches of the radial and ulnar nerves on the dorsum of the hand after removal of the superficial veins.




d
la
m
pr
Extensor hoods
Inter-tendinous connection
First dorsal interosseous muscle
Abductor digiti minimi
Extensor indicis
Extensor digitorum
Extensor digiti minimi
Extensor pollicis brevis
Extensor retinaculum
Extensor pollicis longus
Extensor carpi ulnaris

Fig. 3.79 Extensor retinaculum and extensor tendons, exposed by removal of subcutaneous tissue. The tendons pass through fibro-osseous tunnels deep to the retinaculum and are enveloped by synovial sheaths (here removed), which continue beyond the edges of the retinaculum.

Clavicular and Shoulder Joints

Three joints contribute to the considerable mobility of the arm; movement occurs between the humerus and the scapula at the shoulder (glenohumeral) joint, and the scapula moves on the chest wall through the joints at each end of the clavicle. Although few muscles attach to the clavicle, the numerous muscles attached to the scapula and upper humerus all contribute to movement at the clavicular joints. Indeed, movement at the shoulder joint is almost always associated with movement at the sternoclavicular and acromioclavicular joints.


Sterno-hyoid
Sternothyroid
Subclavian vein
Subclavius
Joint capsule
Interclavicular ligament
Manubrium
Clavicle
First rib
Costoclavicular ligament
Articular disc
First costal cartilage
Parietal pleura
S
R
L
I

Fig. 3.80 Sternoclavicular joints. On the left, the joint capsule and subclavius have been excised to reveal the cartilaginous disc and costoclavicular ligament. Pleura is exposed in the first left intercostal space.

Clavicular joints

The sternoclavicular and acromioclavicular joints are subcutaneous and easily palpable in the living subject. Each has a tubular capsule lined by synovial membrane.

At the sternoclavicular joint (Fig. 3.80), the medial end of the clavicle articulates with the notch on the upper border of the manubrium and with the first costal cartilage. The joint is partitioned by an intracapsular disc of fibrocartilage that attaches superiorly to the clavicle, inferiorly to the first costal cartilage and around its periphery to the capsule. There are two accessory ligaments. Above the capsule is the interclavicular ligament, which joins the medial ends of the clavicles. Just lateral to the joint is the costoclavicular (rhomboid) ligament, which attaches the clavicle firmly to the first costal cartilage. Stability depends on the disc and accessory ligaments, which limit both medial displacement and elevation of the medial end of the clavicle. The sternoclavicular joints are separated from the origins of the brachiocephalic veins and other structures in the root of the neck by the sternohyoid and sternothyroid muscles.

At the acromioclavicular joint (Fig. 3.81) the lateral end of the clavicle articulates with the medial aspect of the acromion of the scapula. The joint capsule attaches to the edges of the articular surfaces that lie


Facet for acromion
Facet for clavicle
Acromion
Coracoid process
Glenoid fossa
Attachment of capsule
Attachment of triceps long head
Groove for subclavius
Attachments of coraco-clavicular ligament
Supra-scapular notch
S
la
m
I

Fig. 3.81 Oblique anterior view of scapula and lateral part of clavicle. The bones have been separated to show the articular surfaces of the acromioclavicular joint and the sites of attachment of the coracoclavicular ligament.

obliquely, the clavicular facet facing laterally and inferiorly. Stability of the joint is provided mostly by the strong coracoclavicular ligament linking the coracoid process and the undersurface of the clavicle near its lateral end. This ligament consists of conoid and trapezoid parts.

Both the sternoclavicular and acromioclavicular joints are supplied by branches of the supraclavicular nerves (C3 & C4).

The lateral end of the clavicle may be elevated or depressed and drawn forwards or backwards. The axes of these movements occur at the costoclavicular and coracoclavicular ligaments, rather than through the clavicular joints. Thus, the medial end of the clavicle is elevated during depression of the scapula and moves posteriorly when the scapula is protracted. Full abduction of the upper limb requires rotation of the scapula so that the glenoid fossa tilts upwards. Rotation of the clavicle through 40° at the sternoclavicular joint supplements the 20° of movement available at the acromioclavicular joint, permitting the scapula to rotate through about 60°. The principal muscles of scapular rotation are trapezius and serratus anterior. Protraction is produced by pectoralis minor and serratus anterior and retraction by trapezius and the rhomboids.

The clavicle forms a strut that supports the scapula against the medial pull of muscles such as pectoralis major and latissimus dorsi. The clavicular joints are stabilized by their accessory ligaments, which are so strong that trauma, such as falling onto the outstretched limb, is more likely to fracture the clavicle than rupture the ligaments. The lateral part of a fractured clavicle tends to be displaced inferiorly by the weight of the limb and medially by spasm of pectoralis major and latissimus dorsi muscles, whereas the medial fragment may be elevated by the action of sternocleidomastoid muscle.

Shoulder joint

The shoulder (glenohumeral) joint is synovial, of the ball-and-socket type, and is capable of a wide range of movement. The hemispherical head of the humerus is directed medially and backwards and articulates with the much smaller glenoid fossa of the scapula (Fig. 3.82). The fossa faces anterolaterally and is slightly deepened by the glenoid labrum, a cartilaginous lip round its edge.

The joint capsule (Fig. 3.83) forms a loose sleeve attaching medially to the glenoid labrum. Its humeral attachment is around


Pectoralis major
Clavicle
Subclavius
Axillary artery
Axillary fat
Blade of scapula
Serratus anterior
Subscapularis
A
m
la
P
Head of humerus
Glenoid surface
Glenoid labrum
Deltoid
Infraspinatus

Fig. 3.82 Transverse section at the level of the humeral head showing the relations of the shoulder joint. Superior aspect.


Supraspinatus (cut)
Scapular spine (cut)
Infraspinatus (cut)
Long head of triceps (cut)
S
m
la
I
Coracoid process
Joint capsule
Rotator cuff
Teres minor (cut)
Surgical neck of humerus

Fig. 3.83 Posterior aspect of the shoulder joint. The acromion and parts of the rotator cuff muscles have been excised to reveal the joint capsule.

the anatomical neck except inferiorly on the medial side, where it descends to the level of the surgical neck.

Synovial membrane lines the fibrous capsule and covers the intracapsular part of the humeral shaft (Fig. 3.84). The cavity of the joint usually communicates with the subscapular bursa through a deficiency in the anterior part of the capsule. Indistinct thickenings in the capsule form the glenohumeral ligaments. Between the greater and lesser tubercles (Fig. 3.85), the capsule forms the transverse humeral ligament beneath which the tendon of the long head of biceps enters the joint from the intertubercular groove. The tendon is surrounded by a tubular sheath of synovial membrane as it passes over the humeral head to attach to the supraglenoid tubercle (Fig. 3.86).

The joint is intimately related to subscapularis, supraspinatus, infraspinatus and teres minor (Figs 3.86 & 3.87) whose tendons fuse with the capsule to form the rotator cuff (Fig. 3.83). Above the joint is the coracoacromial arch formed by the coracoid process, the acromion and the intervening coracoacromial ligament. The arch is separated from supraspinatus by the subacromial bursa.

Articular nerves are derived from the suprascapular and subscapular nerves and also from the axillary nerve which passes very close to the joint. As this nerve leaves the axilla through the quadrangular space (Fig. 3.64), it lies immediately inferior to the capsule. The vascular supply is provided by branches of the circumflex humeral and suprascapular arteries.

Flexion of the shoulder joint (up to 180°) is produced mainly by the clavicular fibres of pectoralis major and the anterior fibres of deltoid. Extension (limited to about 45°) is produced by latissimus dorsi and the posterior fibres of deltoid. At the shoulder joint itself, about 120° of abduction is possible, produced by supraspinatus and deltoid; simultaneous rotation of the scapula through 60° permits full elevation of the arm above the head.




Humeral head
Clavicular facet of acromion
Glenoid fossa
Attachment of coracoclavicular ligament
Vascular foramina
Attachments of capsule
S
la
m
I

Fig. 3.84 The bones that form the shoulder joint have been separated to reveal their articular surfaces.


Greater tubercle
Anatomical neck
Attachment of capsule
Clavicular facet of acromion
Attachment of coracoclavicular ligament
P
la
m
A
Intertubercular sulcus
Lesser tubercle
Coracoid process
Attachment of coracoacromial ligament
Humeral head

Fig. 3.85 Superior view of scapula and upper end of humerus. The acromion and coracoacromial ligament prevent upward displacement of the humeral head.

Adduction, produced by teres major, latissimus dorsi and pectoralis major, is limited by the area of the articular surface of the humerus. Medial rotation is produced by pectoralis major, subscapularis, teres major and the anterior fibres of deltoid, and lateral rotation by infraspinatus, teres minor and the posterior fibres of deltoid.

Although the coracoacromial arch prevents upward displacement of the humerus, stability of the shoulder joint relies principally on the rotator cuff muscles that hold the humeral head firmly in the glenoid fossa. Despite the labrum, the glenoid fossa is a shallow socket. The capsular ligaments are lax in most positions and tighten only near the extremes of movement. Dislocation of the joint, usually with anterior and inferior displacement of the head of the humerus, associated with trauma or weakness of the rotator cuff muscles, is relatively common and may result in damage to the axillary nerve.


Acromion
Scapular spine
Glenoid fossa
Infraglenoid tubercle
Supra-glenoid tubercle
Attachment of biceps brachii short head and coraco-brachialis
Coracoid process
Scapular blade
S
P
A
I

Fig. 3.86 Lateral aspect of scapula showing the pear-shaped glenoid fossa. The positions of supraspinous, infraspinous and subscapular fossae can be appreciated.


Supra-spinatus tendon (cut)
Infra-spinatus tendon (cut)
Joint capsule
Glenoid labrum
Teres minor (cut)
Long head of triceps (cut)
Coraco-acromial ligament
Tendon of biceps brachii long head (cut)
Deficiency for subscapularis bursa
Glenohumeral ligaments (cut)
Sub-scapularis (cut)
S
P
A
I

Fig. 3.87 The scapular component of a disarticulated shoulder joint showing the relations and internal features of the joint.

Elbow Joint

The elbow is a synovial hinge joint between the distal end of the humerus and the proximal ends of the radius and ulna (Fig. 3.88). Laterally, the capitulum of the humerus articulates with the slightly concave upper surface of the head of the radius. Medially, the trochlea of the humerus articulates with the deep trochlear notch of the ulna. In the anatomical position (in which the elbow is extended and the forearm is supinated) the orientation of the joint surfaces produces a carrying angle, which displaces the hand somewhat laterally. This angle between the long axes of the arm and the forearm disappears when the forearm is pronated.

The joint capsule (Figs 3.89 & 3.90) attaches proximally to the shaft of the humerus above the radial and coronoid fossae anteriorly and to the margins of the olecranon fossa posteriorly. Distally, it attaches to the anular ligament of the proximal radioulnar joint and to the margins of the trochlear notch of the ulna. Synovial membrane lines the capsule and clothes the underlying pads of fat that project into the radial, coronoid and olecranon fossae of the humerus. The cavity of the elbow joint is continuous with that of the proximal radioulnar joint.

There are two collateral ligaments (Figs 3.89 & 3.90). The radial (lateral) collateral ligament passes between the lateral epicondyle and the anular ligament. The ulnar (medial) collateral ligament attaches proximally to the medial epicondyle, while distally its fibres diverge and attach to the medial aspects of the coronoid and olecranon processes of the ulna. Stability of the joint depends on the integrity of these collateral ligaments, which hold the trochlea of the humerus firmly in the trochlear notch.

Rotation of the ulna is prevented by the shape of the articular surfaces of the


S
la
m
I
Lateral supracondylar ridge
Radial fossa
Capitulum
Coronoid fossa
Medial epicondyle
Trochlea
Trochlear notch
Head and neck of radius
Radial notch
Coronoid process
Radial tuberosity
Interosseous borders

Fig. 3.88 The bones that form the elbow and proximal radioulnar joints have been separated to reveal their articular surfaces.




Capsule (opened)
Radial fossa
Radial collateral ligament
Anular ligament
Ulna
S
la
m
I
Coronoid fossa
Non-articular part of trochlea
Articular cartilage
Ulnar collateral ligament

Fig. 3.89 Anterior aspect of elbow joint. The capsule has been opened to expose the interior of the joint.

trochlea. Dislocation of the joint is usually associated with ligamentous or bony injury.

Only flexion and extension occur at the elbow joint. Flexion (about 150°) is produced mainly by biceps and brachialis with a contribution from brachioradialis when the elbow is partially flexed. Flexion is limited by contact between the anterior surfaces of the arm and the forearm. Extension is often assisted by gravity. Active extension is produced by triceps assisted by anconeus. In full extension the olecranon engages in the olecranon fossa of the humerus, limiting the movement and increasing joint stability. The flexors and extensors of the wrist and hand arising from the humerus close to the joint do not contribute significantly to elbow movements.

Behind the elbow joint lies the tendon of triceps (Fig. 3.91). Immediately anterior to the capsule are brachialis and the tendon of biceps in the cubital fossa (Fig. 3.29). The brachial artery and median nerve are separated from the capsule by brachialis. The ulnar nerve lies behind the medial epicondyle in contact with the ulnar collateral ligament. The vessels and nerves are vulnerable to injury in traumatic dislocation of the joint.

The elbow receives blood from the anastomosis around the joint formed by branches of the brachial, radial and ulnar arteries. The vessels supplying the joint are accompanied by articular nerves derived from branches of the musculocutaneous, radial, ulnar (and sometimes the median) nerves.


S
m
la
I
Olecranon fossa
Trochlea
Ulnar collateral ligament
Olecranon
Capsule (opened)
Capitulum
Radial collateral ligament

Fig. 3.90 Posterior aspect of flexed elbow joint. The capsule has been opened to reveal the olecranon fossa.


S
P
A
I
Fat pad in olecranon fossa
Brachialis
Biceps brachii
Triceps brachii
Humerus
Olecranon and bursa
Head of radius
Capsule of elbow joint
Brachio-radialis
Anular ligament
Radial nerve
Supinator

Fig. 3.91 Oblique longitudinal section of elbow (extended) and proximal radioulnar joints showing the articular surfaces and relations of the joints.

Radioulnar Joints

The radius and ulna articulate at the proximal and distal radioulnar joints, which are synovial. At the proximal joint, the head of the radius articulates with the radial notch of the ulna (Fig. 3.88). The head and neck are encircled by the anular ligament, which attaches to the anterior and posterior margins of the notch on the ulna (Fig. 3.92) and blends with the capsule and radial collateral ligament of the elbow. Thus the cavity of the proximal joint is continuous with that of the elbow.

The distal radioulnar joint occurs between the head of the ulna and the ulnar notch of the radius (Fig. 3.93). An articular disc (a triangular cartilage) attaches the ulnar styloid process to the distal end of the radius and separates the cavity of the distal joint from that of the wrist.

The anular ligament of the proximal joint and the articular disc of the distal joint prevent separation of the radius and ulna, yet allow the radius to rotate freely. In addition, the shafts of the bones are joined by the interosseous membrane, whose fibres incline downwards and medially from the interosseous border of the radius to that of the ulna. The membrane may be regarded as a fibrous radioulnar joint.

The movements of supination and pronation occur through approximately 180° at the radioulnar joints. During pronation the radius rotates across the ulna and twists the forearm and hand so that the palm faces posteriorly. Supination returns the limb to the anatomical position. The axis of the movement passes through the head of the radius and the styloid process of the ulna. Supination is the more powerful movement and is produced by biceps and supinator, although biceps is ineffective when the elbow is fully extended. Pronation is produced by pronator teres and pronator quadratus. Also, when the elbow is flexed, brachioradialis rotates the forearm and returns the limb to the midposition from the extremes of supination or pronation. The head of the radius can be felt rotating about 2 cm distal to the lateral epicondyle during these movements.

In a fall onto the hand, the interosseous membrane may transmit force from the radius to the ulna, protecting the radial head from compression against the capitulum of the humerus. However, since the membrane does not oppose distraction, a sudden tug on the hand may dislocate the radial head downwards from within the anular ligament of the proximal radioulnar joint.




Olecranon
Capsule of elbow joint (cut)
Articular surfaces of trochlear notch
Ulnar collateral ligament
S
la
m
I
Anular ligament
Radial notch
Coronoid process

Fig. 3.92 Anterior view of proximal end of ulna with attached anular ligament, showing articular surfaces of trochlear and radial notches.




Attachment of capsule
Interosseous border of radius
S
la
m
I
Head of ulna
Styloid process
Styloid process
Facet for scaphoid
Facet for lunate
Ulnar notch

Fig. 3.93 Anterior view of distal ends of radius and ulna. The bones have been separated to reveal the ulnar notch.

Wrist Joint

Mobility of the hand on the forearm is provided by a series of synovial joints. Most of the movement occurs at the radiocarpal (wrist) joint, supplemented by movement between the carpal bones themselves. However, minimal rotation occurs here but is achieved for the hand by pronation and supination.

Radiocarpal joint

At the radiocarpal joint, the distal end of the radius and the attached articular disc articulate with the proximal row of carpal bones including, from lateral to medial, the scaphoid, lunate and triquetral (Fig. 3.94). Pisiform does not take part in the wrist joint. The articular disc attaches to the radius and the root of the ulnar styloid process and separates the cavity of the radiocarpal joint from that of the inferior radioulnar joint (Fig. 3.95). The capsule, lined by synovial membrane, attaches to the edges of the articular surfaces and is strengthened by collateral ligaments that pass from the styloid processes of the ulna and radius to the adjacent carpal bones. The movements of this joint are considered on p. 123. Function at the wrist may be severely compromised by fracture of the scaphoid across its narrow 'waist'. This injury may deprive part of the bone of its blood supply, resulting in ischaemic necrosis.




Radius
Joint capsule (cut)
Interosseous membrane
A
la
m
P
Ulna
Head of ulna
Styloid process of ulna
Styloid process of radius
Facet for scaphoid
Facet for lunate
Articular disc

Fig. 3.94 Articular surface of the distal end of the radius and adjacent articular disc.




Ulnar collateral ligament
Triquetral
Lunate
Base of second meta-carpal
Inter-osseous ligament
Scaphoid
Radius
Head of ulna
Articular disc
Distal radioulnar joint
d
m
la
pr

Fig. 3.95 Coronal section of the wrist joint showing articular surfaces and articular disc.

Joints of Carpus

The carpal bones are arranged in two rows: a proximal row, consisting of, from lateral to medial, scaphoid, lunate, triquetral and pisiform; and a distal row consisting of trapezium, trapezoid, capitate and hamate bones (Fig. 3.96).

Intercarpal joints

The joints between the carpal bones are supported by anterior, posterior and interosseous ligaments. The cavities of these joints usually communicate (Fig. 3.96) and function as a single unit called the midcarpal joint (Fig. 3.97). The joints are most stable in full extension when the anterior ligaments are taut.

The pisiform, a sesamoid bone in the tendon of flexor carpi ulnaris, has a separate joint with the triquetral (Fig. 3.98) and is firmly anchored distally to the hook of the hamate and base of the fifth metacarpal bone by pisohamate and pisometacarpal ligaments (Fig. 3.47). The relations of the intercarpal joints are illustrated in Figure 3.98.

Movements

Movements at the radiocarpal and intercarpal joints are complementary, allowing flexion, extension, adduction and abduction of the hand on the forearm. Although the long flexors and extensors of the digits act on the radiocarpal and intercarpal joints, flexion is due principally to the two carpal flexors, and extension to the three carpal extensors. Adduction is produced mainly by the simultaneous contraction of the flexors and extensors on the ulnar side of the forearm and abduction by contraction of the muscles on the radial side.

The radiocarpal and intercarpal joints are stabilized by the extensors and flexors of the wrist during action of the long flexors and/or extensors of the digits. In many activities, movement between the hand and forearm combines extension and abduction, achieved by the two radial carpal extensors.

Carpal tunnel

The carpal tunnel (canal) is a fibro-osseous passage linking the anterior compartment of the forearm with the palm of the hand. The walls of the tunnel consist anteriorly of the flexor retinaculum and posteriorly of the two rows of carpal bones which form a deep groove on their flexor surfaces. The retinaculum (Fig. 3.99) lies transversely across the anterior aspect of the wrist, attaching to the trapezium and scaphoid laterally and to the pisiform and hook of the hamate medially. The retinaculum lies in the hand, its proximal border level with the distal skin crease. The tendon of palmaris longus gains partial attachment to the retinaculum and enters the hand in front of the carpal tunnel (Fig. 3.39). The tendon is accompanied on its medial side by the ulnar artery and nerve, which pass lateral to the pisiform and the flexor carpi ulnaris tendon, but medial to the hook of the hamate. However, the median nerve and the other tendons entering the palm pass deep to the flexor retinaculum and traverse the carpal tunnel.

Within the tunnel (Fig. 3.98) the tendons of flexor digitorum superficialis lie anterior to those of flexor digitorum profundus. These tendons all possess a common synovial sheath, which is usually in continuity with the digital synovial sheath of the little finger but not with those of the other fingers. The tendon of flexor pollicis longus also traverses the tunnel, invested by a separate synovial sheath which continues into the thumb. The tendon of flexor carpi radialis lies laterally in a groove on the trapezium, isolated from the main part of the carpal tunnel.

The median nerve traverses the tunnel immediately deep to the flexor retinaculum, lying approximately at the midpoint of the wrist close to the tendon of palmaris longus, anterior to the tendon of flexor pollicis longus and medial to the flexor carpi radialis tendon. Compression of the median nerve may occur within the carpal tunnel, giving rise to a condition called the carpal tunnel syndrome, which may result in weakness of the thenar muscles and altered sensation (paresthesiae or 'pins and needles') felt in the thumb, index and middle fingers. Since skin on the lateral side of the palm is supplied by a branch of the median nerve which crosses superficial to the retinaculum, sensation in this area usually remains intact (p. 99). The syndrome may be treated operatively by dividing the flexor retinaculum to decompress the tunnel.





Fig. 3.96 Coronal section of the hand showing the joints of the carpal region. The thumb and little finger lay anterior to the plane of section.


Epiphyses of proximal phalanges
Epiphyses of heads of metacarpals
Sesamoid bone
d
m
la
pr
Epiphysis of first metacarpal
Epiphysis of distal end of radius
Epiphysis of distal end of ulna

Fig. 3.97 Radiograph of the hand of an adolescent showing metacarpal and carpal bones. Epiphyseal plates are present. (Compare Fig. 3.38.)


Ulnar nerve and artery
Hypothenar muscles
Flexor retinaculum
Pisiform
Digital flexor tendons
Digital extensor tendons
Thenar muscles
Median nerve
Flexor carpi radialis
Trapezium
Flexor pollicis longus
Radial artery
A
m
la
P

Fig. 3.98 Transverse section through the carpus showing the carpal tunnel and its contents.


Thenar muscles
Flexor retinaculum
Ulnar artery
Flexor carpi ulnaris (cut)
Flexor carpi radialis (cut)
Flexor digitorum superficialis
Ulnar nerve
Median nerve
Flexor pollicis longus
Flexor digitorum profundus
Radial artery and nerve
d
m
la
pr

Fig. 3.99 Flexor retinaculum and the superficial relations and structures entering the carpal tunnel.

Joints of the Hand

The carpometacarpal, metacarpophalangeal and interphalangeal joints are synovial and allow the hand to perform its various functions, including the intricate movements involved in gripping objects. The intrinsic muscles perform delicate movements of the fingers; power is provided by contraction of the muscles in the compartments of the forearm.

Carpometacarpal joints

There are three separate carpometacarpal joints, one for the thumb and two for the fingers. The joint between the first metacarpal and trapezium (Fig. 3.100) possesses saddle-shaped articular surfaces and a lax capsule. This joint permits flexion and extension in a plane parallel to that of the palm, and adduction and abduction in a plane at right angles to that of the palm (and in the plane of the thumbnail). During opposition (the combined movements of medial rotation, adduction and flexion), the thumb rotates so that it may touch any of the fingers pulp-to-pulp. Median nerve injury results in significant disability because opposition is essential in everyday manipulative movements.

The remaining two carpometacarpal joints, those for the fingers, are plane joints and less mobile than the first. Laterally, a joint cavity lies between the second and third metacarpals and the trapezoid and capitate, while medially the fourth and fifth metacarpals articulate with the hamate (Fig. 3.97). These carpometacarpal joints communicate with the three plane (intermetacarpal) joints that lie between the bases of the medial four metacarpals.

Metacarpophalangeal joints

These joints occur between the rounded heads of the metacarpals and concave bases of the proximal phalanges (Fig. 3.38). Each joint capsule is reinforced at the sides by collateral ligaments and is thickened anteriorly to form a fibrocartilaginous plate. The plates of the medial four digits are interconnected by the deep transverse metacarpal ligament. The joints permit flexion, extension, adduction and abduction. Because the collateral ligaments tighten during flexion, adduction and abduction are possible only in the extended position.

Interphalangeal joints

Each of these joints possesses a capsule reinforced by collateral ligaments (Fig. 3.101). However, posteriorly, the capsule is deficient and is replaced by the extensor expansion (Fig. 3.102). These are hinge joints that allow only flexion and extension.

The carpometacarpal, metacarpophalangeal and interphalangeal joints are supplied by branches of adjacent vessels and nerves traversing the palm and digits.



Fig. 3.100 Trapezium and metacarpal of thumb, separated to show the saddle-shaped articular surfaces of the carpometacarpal joint.


Distal phalanx
Articular cartilage
d
m
la
pr
Middle phalanx
Collateral ligament
Proximal phalanx
Extensor expansion
Metacarpo-phalangeal joint space
Head of metacarpal

Fig. 3.101 Coronal section of a finger. The joint spaces have been exaggerated by hyperextension of the specimen.


Nail plate
Distal phalanx
Articular cartilage
d
P
A
pr
Articular cartilage
Tendon of flexor digitorum profundus
Tendon of flexor digitorum superficialis
Proximal phalanx
Extensor expansion
Head of metacarpal

Fig. 3.102 Sagittal section of a finger to show the capsules and relations of the joints.

Exam Skills

Each of the incomplete statements below is followed by five suggested answers or completions.
Decide which are true and which are false. The answers are supplied on p. 417.

1. The flexor retinaculum:

a) forms part of the carpal tunnel.
b) is crossed superficially by the median nerve.
c) is crossed superficially by the ulnar artery.
d) gives attachment to the thenar muscles.
e) attaches to the trapezium.

2. The following muscles act on the metacarpophalangeal joint of the thumb:

a) opponens pollicis.
b) abductor pollicis brevis.
c) extensor pollicis brevis.
d) the first dorsal interosseous.
e) flexor pollicis brevis.

3. Deltoid:

a) is innervated by the axillary nerve.
b) is usually active against gravity during abduction of the shoulder joint.
c) acts to initiate abduction of the shoulder joint.
d) may suffer damage to its nerve supply during dislocation of the glenohumeral joint.
e) attaches to the lateral surface of the shaft of the humerus.

4. The following lie within the axilla:

a) the cords of the brachial plexus.
b) the tendon of the long head of biceps.
c) coracobrachialis.
d) branches of the axillary artery.
e) lymph nodes.

5. These muscles act as follows:

a) pectoralis major causes flexion at the shoulder.
b) brachialis causes flexion at the elbow.
c) biceps brachii causes supination.
d) pronator teres causes pronation.
e) trapezius causes abduction at the glenohumeral joint.

6. Medial rotation of the humerus at the shoulder joint is produced by:

a) teres minor.
b) supraspinatus.
c) subscapularis.
d) latissimus dorsi.
e) pectoralis major.

7. The following enter and/or leave the cubital fossa:

a) the tendon of biceps brachii.
b) the radial nerve.
c) the cephalic vein.
d) the ulnar nerve.
e) the brachial artery.

8. For part of its course, the brachial artery accompanies the:

a) axillary nerve.
b) median nerve.
c) radial nerve.
d) ulnar nerve.
e) musculocutaneous nerve.

9. The following usually receive fibres from the lateral cord of the brachial plexus:

a) the median nerve.
b) the axillary nerve.
c) the musculocutaneous nerve.
d) the lateral cutaneous nerve of the forearm.
e) the ulnar nerve.

10. Branches of the radial nerve supply:

a) skin of the thumb.
b) skin of the forearm.
c) skin of the hypothenar eminence.
d) no muscle that has flexor actions.
e) no muscle(s) located in the hand.

11. Supination:

a) occurs at the radioulnar joints.
b) causes the ulna to move around the radius.
c) is produced mainly by biceps brachii when the elbow joint is fully extended.
d) is opposed by contraction of brachialis.
e) involves active movement of the elbow joint.

12. Complete division of the ulnar nerve at the elbow will:

a) paralyse flexor digitorum superficialis.
b) paralyse flexor carpi ulnaris.
c) prevent abduction and adduction of the fingers.
d) cause anaesthesia of skin on the palmar surface of the fifth digit.
e) cause wasting of the adductor pollicis.

13. Skin of the dorsum of the hand is innervated by the:

a) lateral cutaneous nerve of the forearm.
b) superficial branch of the radial nerve.
c) ulnar nerve.
d) median nerve.
e) posterior cutaneous nerve of the forearm.

14. Flexor digitorum superficialis:

a) flexes the distal interphalangeal joints.
b) receives innervation from the ulnar nerve.
c) attaches to the medial epicondyle of the humerus.
d) lies superficial to the median nerve through most of the forearm.
e) gives attachment for the lumbricals.

15. The interossei:

a) flex the interphalangeal joints.
b) abduct and adduct the fingers.
c) are innervated by the ulnar nerve.
d) flex the metacarpophalangeal joints of the fingers.
e) attach to the extensor expansions.

16. The radial nerve:

a) is a branch of the posterior cord of the brachial plexus.
b) lies in the radial (spiral) groove of the humerus.
c) enters the forearm anterior to the elbow joint.
d) has a branch that passes through supinator.
e) innervates flexor carpi radialis.

Clinical Case Skills

The answers are supplied on p. 418.

Case Study 1

A frail 90-year-old woman was admitted to sheltered accommodation and soon after arrival complained of pain in her right hand, which was ignored by a care assistant, who gave her sleeping tablets. The visiting physician found the woman had a painful blue right hand. The whole limb was cold, especially below the elbow, and cutaneous sensation was absent in the hand. She could not move her hand or fingers. The doctor could not identify pulses in the right upper limb but palpated a strong, though irregular, left radial pulse. The physician explained that a fragment of blood clot had probably escaped from the heart and been carried in the blood to the right arm, where it had blocked the brachial artery as an embolus. Admission to the nearby hospital was organized but unfortunately the elderly patient suffered a major stroke, from which she died 12 hours later.

Questions:

1. Assuming that the clot was atrial in origin, name the pathway it took from the left atrium to reach the brachial artery.
2. What determines the level of an initial arterial blockage?
3. Although the whole limb was poorly perfused (ischaemic), what was a good guide to the severity of the ischaemia?
4. What arterial anastomoses exist between the subclavian and axillary arteries?

Case Study 2

A 50-year-old grandmother with rheumatoid arthritis found that her wrists and the joints in her fingers had become more stiff and painful. She complained of having more difficulty than usual with her right hand and she had dropped several treasured cups. On one occasion while tidying away the broken fragments, she cut her thumb but had not noticed until she saw blood on her clothes. She was having difficulty sleeping as she was being woken by pain in her hand and arm, and she volunteered that something similar happened during her pregnancies but resolved spontaneously after the birth of her children. The physician examined her hands and in addition to her usual joint features noticed flattening of her right thenar eminence compared with the left and some loss of cutaneous sensation. After discussing nerve conduction studies, her physician explained that an operation on the front of her wrist with the scar running near the crease lines would probably be needed to help relieve her problems.

Questions:

1. What is the significance of flattening of the thenar muscles? Which nerve supplies these muscles and where is it particularly vulnerable to compression?
2. What had alerted the physician to sensory deficit, and what was found on examination?
3. Why is the skin incision orientated transversely at the wrist?
4. Which nerve(s) may be vulnerable at operations to divide the flexor retinaculum?

Case Study 3

A fit college student fell heavily and injured his right shoulder while playing football. He had dislocated the same shoulder about a year earlier and had injured it again several times since. His shoulder felt very painful and he was unable to move his right arm. The hospital doctor noticed that his shoulders were not symmetrical, since there was a hollow below the right acromion, and ordered radiographs of the shoulder region to exclude fractures. The radiographs confirmed the suspicion of dislocation of the right shoulder joint: there were no fractures. The dislocation was reduced easily during a short general anaesthetic and the student was allowed home wearing a collar and cuff support and bandaging that held his right elbow against his chest wall. Subsequently, an orthopaedic specialist noticed that the right deltoid was less well developed than the left. Surgical exploration of the joint revealed a capsular tear, which was repaired. Postoperatively, intensive physiotherapy was instituted to strengthen all the muscles acting at the shoulders and the student has now resumed playing football.

Questions:

1. What anatomical features render the shoulder joint particularly prone to dislocation?
2. Which nerve closely related to the joint is liable to injury by dislocation of the shoulder and how should the doctor have examined for this injury?
3. Why was the upper limb bandaged against the chest wall?
4. What is the probable significance of previous injuries?
5. What is the most important stabilizing influence on the glenohumeral joint?

Case Study 4

A 30-year-old, right-handed teacher decided to repair his wooden garden shed. He purchased new roofing, removed the partly rotten wood without difficulty and began to nail the new timbers in place. As the day progressed, the hammer he was using seemed to feel heavier and heavier until just picking it up was an effort and he eventually completed the job using his left hand. That evening the whole of his arm, but especially his elbow, was uncomfortable and even picking up a glass of lager made his elbow sore. He found that squeezing water out of the sponge after taking a shower hurt his elbow. His physician demonstrated exquisite tenderness over the lateral epicondyle of the right humerus and pronounced, 'You've got tennis elbow!' After following his usual activities at work, the teacher found that his pain gradually eased and that he could use his arm completely normally after approximately 1 week.

Questions:

1. Which muscles attach near the lateral epicondyle?
2. Which unaccustomed repetitive action provoked the inflammatory response (give precise movements at the joint)?
3. Which two muscles were likely to be particularly involved?
4. Why did squeezing water from the sponge produce pain?

Observation Skills

Identify the structures indicated. The answers are supplied at the foot of the page.



Fig. 3.103 Cross-section through the arm.



Fig. 3.104 Cross-section through the forearm.

Answers:

Fig. 3.103 1 = cephalic vein; 2 = brachialis; 3 = humerus; 4 = radial nerve; 5 = deep branchial artery; 6 = medial head of triceps; 7 = triceps long head; 8 = ulnar nerve; 9 = median nerve; 10 = brachial artery; 11 = musculocutaneous nerve; 12 = biceps brachii.

Fig. 3.104 1 = palmaris longus tendon; 2 = flexor carpi radialis; 3 = median nerve; 4 = radial artery; 5 = radial nerve; 6 = flexor pollicis longus; 7 = interosseous membrane; 8 = radius; 9 = extensor carpi radialis; 10 = cephalic vein; 11 = abductor pollicis longus; 12 = extensor digitorum; 13 = extensor digiti minimi; 14 = extensor pollicis longus; 15 = extensor carpi ulnaris; 16 = ulna; 17 = basilic vein; 18 = flexor digitorum profundus; 19 = ulnar nerve; 20 = ulnar artery; 21 = flexor carpi ulnaris; 22 = flexor digitorum superficialis.



Fig. 3.105 Sagittal section through the elbow and proximal end of ulna.



Fig. 3.106 Sagittal section through the elbow and proximal end of radius.

Answers:

Fig. 3.105 1 = brachial vein; 2 = humerus; 3 = brachial artery; 4 = brachialis; 5 = fused flexor muscles; 6 = ulna; 7 = trochlea of humerus; 8 = fat pad; 9 = triceps and tendon.

Fig. 3.106 1 = triceps brachii; 2 = capitulum of humerus; 3 = fat pad; 4 = head of radius; 5 = brachial artery; 6 = supinator; 7 = brachialis; 8 = biceps brachii and tendon.



Fig. 3.107 Anteroposterior radiograph of shoulder region.



Fig. 3.108 Lateral radiograph of juvenile elbow.

Answers:

Fig. 3.107 1 = first rib; 2 = clavicle; 3 = acromioclavicular joint; 4 = coracoid process; 5 = acromion; 6 = head of humerus; 7 = articular surface of glenoid fossa; 8 = greater tubercle; 9 = anatomical neck; 10 = intertubercular groove; 11 = soft tissue shadow of deltoid; 12 = surgical neck; 13 = lateral border of scapula; 14 = soft tissue shadow of muscles of axillary folds.

Fig. 3.108 1 = shaft of humerus; 2 = olecranon fossa; 3 = epiphysis of medial epicondyle; 4 = olecranon process; 5 = coronoid process; 6 = shaft of ulna; 7 = shaft of radius; 8 = epiphyseal cartilage plate; 9 = proximal epiphysis of radius; 10 = radiohumeral joint; 11 = epiphysis of capitulum.



Fig. 3.109 Lateral radiograph of juvenile elbow.

Answers:

Fig. 3.109 1 = soft tissue shadow of biceps brachii and brachialis; 2 = shaft of humerus; 3 = neck of radius; 4 = radial tuberosity; 5 = olecranon process; 6 = humero-ulnar joint; 7 = proximal epiphysis of radius; 8 = epiphysis of capitulum; 9 = epiphyseal cartilage plate; 10 = supracondylar ridge; 11 = soft tissue shadow of triceps brachii.

Chapter 4

ABDOMEN

Introduction 136
Anterior Abdominal Wall 140
  Skin and subcutaneous tissue 140
  Muscles 140
  Actions of abdominal muscles 145
  Structures deep to muscles 145
  Nerves and vessels 145
Inguinal Canal 146
  Boundaries 147
  Contents 148
  Inguinal hernias 149
Scrotum 149
  Skin and subcutaneous tissue 149
  Spermatic fasciae 150
  Spermatic cord 150
  Tunica vaginalis 151
  Testis 151
  Epididymis 151
  Ductus (vas) deferens 151
Peritoneum 152
  Parietal peritoneum 152
  Visceral peritoneum and mesenteries 154
  Infracolic compartment of the greater sac 154
  Supracolic compartment of the greater sac 157
  Omental bursa (lesser sac) 157
Stomach 158
  Relations 159
  Arterial supply 160
  Venous drainage 161
  Nerve supply 161
Spleen 162
  Surface features 162
  Relations 163
  Blood supply 163
Duodenum 164
  Parts and structure 164
  Relations 165
  Blood supply 166
Pancreas 167
  Relations 168
  Pancreatic ducts 169
  Blood supply 169
Liver 170
  Surface features and relations 170
  Subphrenic and subhepatic spaces 172
  Biliary apparatus 172
  Hepatic blood vessels 173
Jejunum and Ileum 175
  Ileal diverticulum 175
  Mesentery 176
  Location and relations 176
  Superior mesenteric vessels 177
Caecum, Appendix and Colon 179
  Caecum 180
  Appendix 181
  Colon 181
  Blood supply 182
Portal Venous System 184
  Tributaries 184
  Portal vein 185
  Portacaval anastomoses 185
Kidneys and Suprarenal Glands 186
  Kidneys 186
  Suprarenal glands 189
  Abdominal parts of ureters 189
Abdominal Aorta 190
  Visceral branches 190
  Parietal branches 191
Iliac Vessels 192
  Common and external iliac vessels 192
Inferior Vena Cava 193
  Tributaries 194
Lymphatics of the Abdomen 195
  Iliac lymph nodes 196
  Aortic nodes 196
  Cisterna chyli 196
Autonomic Nerves of the Abdomen 197
  Parasympathetic nerves 197
  Sympathetic nerves 198
  Aortic plexuses 199
Posterior Abdominal Wall 200
  Muscles 200
  Fasciae 201
  Nerves 201
Diaphragm 203
  Musculature 203
  Central tendon 203
  Structures passing between the thorax and abdomen 203
  Movements 204
  Nerve supply 205
  Blood supply 205
  Relations 205
Exam Skills 207
Clinical Case Skills 208
Observation Skills 210

Introduction

The abdomen is separated from the thorax above by the diaphragm, and below is continuous with the pelvis at the pelvic inlet. Passing through the diaphragm are the aorta, oesophagus and inferior vena cava. Because the diaphragm is strongly convex upwards, the upper abdominal organs lie deep to the lower ribs and costal cartilages. The pelvic inlet is an arbitrary plane sloping downwards and forwards, through which run the small and large intestines, the ureters and several vessels and nerves.

The posterior abdominal wall includes muscles that attach to the last rib, the hip bone and the lumbar vertebrae. Laterally, their fasciae merge with the anterolateral abdominal wall, the three layers of muscle of which broaden out and become aponeurotic before meeting in the midline anteriorly. Close to this median raphe is a vertical strap-like muscle, rectus abdominis, running from the pubis to the anterior chest wall.

The inguinal canal, an oblique passage through the anterolateral abdominal wall, conveys the spermatic cord in the male and the round ligament of the uterus in the female (Figs 4.1 & 4.2).

The nerves and vessels of the abdominal wall run between the muscles and supply all layers from skin to parietal peritoneum. Most of the arteries, and their accompanying veins and lymphatics, arise from the thoracic wall or the inguinal region, while the


S
R
L
I
Pectoralis major
Xiphoid process
Costal margin
Linea semilunaris (lateral border of rectus abdominis)
Tendinous intersection
Umbilicus
Inguinal ligament
Abdominal aorta (pulsations may be felt on deep palpation)
Iliac crest
Anterior superior iliac spine
Inguinal crease
Femoral artery
Spermatic cord
Pubic crest

Fig. 4.1 Structures often visible or palpable in the living.


S
R
L
I
Diaphragm
Inferior border of liver
Fundus of gall bladder
Inguinal ligament
Mid-point of inguinal ligament
Pubic tubercle
Anterior superior iliac spine
Inguinal canal
Pubic symphysis
● Base of appendix
● Deep inguinal ring
● Superficial inguinal ring

Fig. 4.2 Clinically important structures not usually visible or palpable in the living.


T4
T5
T6
T7
T8
T9
T10
T11
T12
L1
S
R
L
I

Fig. 4.3 Dermatomes of abdominal wall, showing how they overlap.


Epigastrium
Hypochondrium
Flank or lateral region or loin or lumbar
Inguinal region or groin or iliac fossa
Umbilical region
(Supra) pubic region or hypogastrium
S
R
L
I
Right upper
Left upper
Right lower
Left lower

Fig. 4.4 Subdivisions of the abdomen used in clinical practice. (Left) Nine regions. (Right) Four quadrants.


A
R
L
P
Anterior abdominal wall
Inferior vena cava
Aorta
Liver
Kidney
Posterior abdominal wall
Second lumbar vertebra

Fig. 4.5 Transverse section through the abdomen to demonstrate the shape of the cavity.

innervation is provided by spinal nerves. The cutaneous distribution of these nerves displays considerable overlap, as shown in Figure 4.3.

The abdominal wall muscles accommodate to volume changes of the abdominal and pelvic hollow organs, increase intra-abdominal pressure during forced expiration and straining, and produce movements of the lumbar spine.

The shape of the abdominal cavity is shown in Figures 4.4–4.6. Projecting into the abdomen, the lumbar vertebrae form a substantial midline ridge anterior to which run the aorta and inferior


S
A
P
I
Diaphragm
Lumbar vertebra
Abdominal cavity
Anterior abdominal wall
Sacrum
Pelvic inlet
Symphysis pubis
Pelvic cavity
Pelvic floor

Fig. 4.6 Longitudinal section through the abdomen to show its shape and superior and inferior boundaries.

vena cava. On each side of the lumbar vertebrae are deep paravertebral gutters. The liver lies predominantly to the right of the midline while the spleen and most of the stomach lie to the left (Fig. 4.7). The digestive organs, including the duodenum, jejunum, ileum and colon, lie anterior to the suprarenal glands, kidneys and ureters (Fig. 4.8). The abdominal organs vary considerably in their size, shape and relative position, with the stomach and intestines expanding and contracting as they accommodate their contents. The upper abdominal organs move with the diaphragm and in response to changes in body position, for example from upright to lying down.



Fig. 4.7 The digestive organs within the abdomen.



Fig. 4.8 The kidneys and related organs.

The peritoneum is a serous sac with parietal and visceral layers that are normally in close apposition. The parietal peritoneum lines the abdominal wall and the undersurface of the diaphragm, while the visceral layer coats many of the abdominal organs. Some organs have an almost complete covering and are termed intraperitoneal, for example the stomach, jejunum, ileum and liver. They are relatively mobile and attached by double layers of peritoneum between which run vessels and nerves. Such folds form mesenteries, for example the mesentery of the small intestine, or ligaments such as the falciform ligament of the liver, or omenta such as the greater omentum that hangs like an apron from the stomach. Other organs are retroperitoneal, such as the pancreas and kidneys. They have no mesenteries and only partial coverings of peritoneum, usually on the anterior surface.

The aorta descends in the midline and bifurcates to form the common iliac arteries (Fig. 4.9). From its anterior surface spring three branches to the digestive organs. The coeliac trunk supplies the derivatives of the embryonic foregut: stomach and proximal duodenum, liver, gall bladder, spleen and part of the pancreas. The superior mesenteric artery supplies the derivatives of the midgut: the remainder of the pancreas and small intestine and the large intestine as far as the transverse colon. The inferior mesenteric artery supplies the hindgut: descending and sigmoid colon and rectum. Paired branches arise from the aorta to the suprarenal glands, kidneys, gonads and abdominal wall.

On the right, the renal vein and the suprarenal and gonadal veins join the inferior vena cava directly (Fig. 4.10). On the left, the renal vein is longer and receives the suprarenal and gonadal veins. Blood from the spleen, stomach and intestines drains via the portal venous system to the liver, thence to the inferior vena cava by way of the hepatic veins (Fig. 4.11).

Lymph from the abdominal organs drains by vessels and nodes that accompany the arterial supply. There are nodes within mesenteries and around the aorta, from which vessels drain upwards to enter the cisterna chyli. The latter gives rise to the thoracic duct carrying lymph upwards through the thorax (Fig. 1.34).

Most viscera receive autonomic innervation via both sympathetic and parasympathetic plexuses around the blood vessels, particularly the aorta and its branches. The thoracic splanchnic nerves, branches of the thoracic portion of the sympathetic trunk, pierce the diaphragm close to its aortic opening. Parasympathetic fibres travel in the vagus nerve, which supplies the stomach, liver and biliary system, the small intestine and the proximal part of the large intestine. The distal portion of the colon is supplied by parasympathetic nerves from sacral segments of the spinal cord.


Diaphragm
Coeliac
Renal
Superior mesenteric
Gonadal
Abdominal aorta
Inferior mesenteric
Common iliac
External iliac
Internal iliac
Femoral
S
R
L
I

Fig. 4.9 Principal arteries of the abdomen.


Hepatic
Renal
Gonadal
Inferior vena cava
Common iliac
External iliac
Internal iliac
Femoral
S
R
L
I

Fig. 4.10 Principal systemic veins of abdomen.


Liver
Spleen
Portal
Splenic
Inferior mesenteric
Superior mesenteric
S
R
L
I

Fig. 4.11 Principal components of the portal venous system.

Anterior Abdominal Wall

The skin and subcutaneous tissue of the anterior abdominal wall overlie four muscles that move the trunk, control intra-abdominal pressure and support the abdominal contents. The main nerves and blood vessels lie in the neurovascular plane, deep to all but one of the muscles. Deep to the muscles are the transversalis fascia, extraperitoneal fat and the parietal peritoneum.

Skin and subcutaneous tissue

The midline umbilicus marks the site of former attachment of the umbilical cord. In a lean person, it usually lies midway between the xiphisternum and the symphysis pubis, at the level of the fourth lumbar vertebra, but its position is variable.

The subcutaneous tissue has an outer fatty layer, which is particularly thick in obese individuals, and a deeper membranous layer, which lies on the external oblique muscle (Fig. 4.12). Although thin over most of the abdominal wall, the membranous layer becomes substantial inferiorly. Laterally, it descends into the thigh and attaches to the fascia lata, while medially it continues around the external genitalia into the perineum (p. 244). In the event of a rupture of the male urethra, urine can escape not only into the subcutaneous tissues of the perineum but may track into the abdominal wall deep to the membranous layer, but not into the thigh (p. 227).

The subcutaneous tissue receives its blood from small branches of the arteries that supply the abdominal muscles. The superficial veins drain either upwards towards the axilla or downwards to the groin. In portal hypertension, the superficial veins may dilate and become visible, radiating from the umbilicus (caput medusae; p. 185). The nerve supply to the skin is segmental and is provided by cutaneous branches of the lower thoracic spinal nerves and the first lumbar nerve (Figs 4.2 & 4.3).

Muscles

On each side of the midline, there are four principal muscles. Three of these are flat muscles, arranged in layers in the lateral part of the abdominal wall. External oblique is the most superficial, internal oblique lies deep to it and the deepest layer is transversus abdominis. As each of these muscles is traced anteriorly and medially, its fleshy part gives way to an aponeurosis (Fig. 4.12). The aponeuroses of the flat muscles form a sheath around the fourth muscle, rectus abdominis. In the midline, the aponeuroses from both sides interdigitate to form the linea alba, which bares an obvious scar, the umbilicus. All three aponeuroses attach inferiorly to the pubic crest. These muscles are innervated by the lower six thoracic nerves and the first lumbar nerve (p. 145).

Immediately above the groin, the inguinal canal traverses the lowest part of the abdominal wall and transmits the spermatic cord in the male and the round ligament of the uterus in the female (p. 146). The umbilicus and linea alba are potential sites for hernias. Umbilical hernias are common in infants, due to weakness of the umbilical scar. In later life, weakening of the linea alba near the umbilicus can result in a paraumbilical hernia.


Pectoralis major
Anterior cutaneous nerves
Membranous layer of subcutaneous tissue (cut)
Fatty layer of subcutaneous tissue
Superficial epigastric vein
Superficial circumflex iliac vein
S
R
L
I
External oblique & aponeurosis
Linea alba
Umbilicus
Inguinal ligament
Fascia lata
Spermatic cord

Fig. 4.12 External oblique muscles and aponeuroses. Some subcutaneous tissue, veins and cutaneous nerves have been preserved on one side.

External oblique

The muscle fibres of external oblique slope downwards and forwards (Fig. 4.13). Superiorly, a series of fleshy slips attaches to the outer surfaces of the lower eight ribs, the upper slips interdigitating with serratus anterior, the lower ones with latissimus dorsi. The most posterior fibres attach inferiorly to the iliac crest; elsewhere, the fibres give way to the aponeurosis, which passes medially in front of rectus abdominis to reach the linea alba. The aponeurosis possesses a free lower border that extends from the anterior superior iliac spine to the pubic tubercle and forms the inguinal ligament (Figs 4.1 & 4.12), which marks the boundary between the abdominal wall and the anterior aspect of the thigh.

Immediately above the medial end of the inguinal ligament, the external oblique aponeurosis presents an aperture, the superficial inguinal ring, which is the medial opening of the inguinal canal (p. 146).

Internal oblique

Internal oblique attaches to the lateral two-thirds of the inguinal ligament, to the anterior part of the iliac crest and to the thoracolumbar fascia (Fig. 4.15), through which it is anchored to the lumbar vertebrae. Most of its fibres slope forwards and upwards. The uppermost fibres attach to the costal margin between the ninth and twelfth ribs, while the remainder give way to the aponeurosis of the muscle (Fig. 4.14).

Some aponeurotic fibres reach the linea alba by passing anterior to rectus abdominis, while others pass behind the rectus (p. 143). The lowest fibres arch medially and downwards, contributing to the roof of the inguinal canal. They unite with the underlying fibres of transversus to form the inguinal falx (conjoint tendon), which descends to the pecten pubis (pectineal line) on the pubic bone.



Fig. 4.13 The left external oblique showing its attachments to the lower ribs and the iliac crest.


Site of umbilicus
External and internal oblique aponeurosis
S
R
L
I
Costal cartilages
Internal oblique and aponeurosis
Iliohypogastric nerve (cut)
Inguinal ligament
Ilioinguinal nerve (cut)
Spermatic cords

Fig. 4.14 Most of the left external oblique has been excised to reveal the underlying internal oblique muscle.


Ribs (numbered)
Internal oblique and aponeurosis
S
A
P
I
7
8
9
10
11
12
Thoracolumbar fascia
Iliohypogastric nerve (cut)
Iliac crest
Ilioinguinal nerve

Fig. 4.15 Left internal oblique and attachments, revealed by removal of the external oblique. In this specimen, the costal attachments of serratus anterior include the ninth rib.

Transversus abdominis

The upper part of this muscle arises from the inner aspects of the lower six costal cartilages (Fig. 4.17) by fleshy slips, which interdigitate with the costal attachments of the diaphragm. The middle part of the muscle fuses with the thoracolumbar fascia while the lowest fibres attach to the iliac crest and the lateral half of the inguinal ligament. Most of the fibres run horizontally forwards and are replaced, near the lateral border of rectus, with an aponeurosis (Figs 4.16 & 4.18). The upper part of the aponeurosis reaches the linea alba by passing posterior to rectus abdominis while the inferior part passes anterior to it (see below).

The lowest fibres of transversus abdominis attach to the lateral part of the inguinal ligament and arch over the inguinal canal and, fusing with those of the overlying internal oblique, contribute to the inguinal falx.

Rectus abdominis

Rectus abdominis runs vertically on each side of the linea alba, from the pubis to the front of the chest wall (Fig. 4.16). The inferior attachment is to the anterior aspect of the pubic symphysis and to the pubic crest. The muscle widens superiorly and attaches to the anterior surfaces of the fifth, sixth and seventh costal cartilages. Its gently convex lateral border forms a surface feature called the linea semilunaris. Rectus abdominis is characterized by transverse tendinous intersections, usually at the levels of the xiphisternum, the umbilicus and midway between the two.

Rectus sheath

Rectus abdominis is enclosed in a sheath formed by the aponeuroses of the flat abdominal muscles. The anterior wall of the sheath, which is anchored to the tendinous intersections, covers the entire length of the muscle (Fig. 4.14). By contrast, the posterior wall is not attached to the muscle and falls short of its superior and inferior extremities. Superiorly, the posterior wall of the sheath terminates at the costal margin, above which rectus is in direct contact with the costal cartilages. Inferiorly, the posterior wall continues only a short distance below the umbilicus, where it thins out or ends abruptly. In the latter case, the posterior wall has a recognizable inferior margin, the arcuate line (Fig. 4.18), below which the posterior surface of rectus is in direct contact with the transversalis fascia.

In addition to rectus abdominis, the rectus sheath contains the small triangular pyramidalis muscle, the superior and inferior epigastric vessels (Figs 4.16 & 4.18) and the terminal parts of the lower six intercostal nerves that supply rectus and the overlying skin.


External oblique (cut)
Rectus abdominis and tendinous intersection
Intercostal nerves
S
R
L
I
Transversus abdominis and aponeurosis
Inferior epigastric vessels
Ilioinguinal nerve (cut)
Pyramidalis

Fig. 4.16 Rectus abdominis muscles and neurovascular plane. The anterior walls of both rectus sheaths, the left oblique muscles and part of the left rectus abdominis have been removed.




Ribs (numbered)
6
7
8
9
10
11
12
S
A
P
I
Branches of ninth intercostal nerve
Branches of tenth intercostal nerve
Eleventh intercostal nerve
Subcostal nerve
Transversus abdominis and aponeurosis
Iliohypogastric nerve
Thoracolumbar fascia

Fig. 4.17 Removal of the external and internal oblique muscles has revealed the transversus abdominis muscle and aponeurosis. Running across its surface are the lower intercostal, subcostal and iliohypogastric nerves.




S
R
L
I
Position of lateral edge of rectus abdominis
Transversus abdominis
External and internal oblique (cut)
Arcuate line
Inferior epigastric vessels
Pubic crests
Superior epigastric vessels
Linea alba
Parietal peritoneum
Bladder and median umbilical ligament
Occluded part of umbilical artery
Spermatic cord

Fig. 4.18 On the right, most of the oblique muscles and all of rectus abdominis have been excised to reveal the posterior wall of the rectus sheath. On the left, all the muscles have been removed to show the parietal peritoneum. The bladder is enlarged.

Actions of abdominal muscles

The abdominal muscles flex the lumbar spine, rectus abdominis being particularly powerful in this action. Lateral flexion and rotation of the trunk are produced by coordinated contraction of the oblique muscles on both sides of the midline. Acting collectively, the abdominal muscles increase intra-abdominal pressure and, if the respiratory passages are open, the diaphragm is pushed upwards as in forced expiration, sneezing and coughing. Increased abdominal pressure with the airway closed (straining) occurs when lifting heavy objects and during defecation, childbirth and vomiting.

Structures deep to muscles

The deep surfaces of transversus and rectus abdominis are covered by the transversalis fascia, which forms part of a complete fascial sheet lying deep to the muscles surrounding the peritoneal cavity. Several names are given to this continuous fascial sheet and are derived from the muscles to which the fascia relates. For example, the iliac fascia and psoas fascia cover the iliacus and psoas muscles, respectively. Above the midpoint of the inguinal ligament, an aperture in the transversalis fascia (the deep inguinal ring) forms the lateral opening of the inguinal canal.

Deep to the transversalis fascia is the extraperitoneal fat, which contains four vestigial structures converging on the umbilicus. Descending from the liver is the round ligament of the liver (ligamentum teres hepatis; Figs 4.30 & 4.59), the remnant of the left umbilical vein. Ascending in the midline from the urinary bladder is the median umbilical ligament or urachus (Fig. 4.18). Inclining upwards from each side of the pelvis is the occluded part of the umbilical artery.

The deepest layer of the abdominal wall is the parietal peritoneum (Fig. 4.18). Although the peritoneum and the abdominal musculature are adherent in most areas, they are only loosely attached between the pubis and umbilicus. The distended bladder intervenes between the parietal peritoneum and the abdominal wall (Fig. 4.30) and can be accessed through a lower abdominal incision without opening the peritoneum.

Nerves and vessels

The skin, muscles and parietal peritoneum of the anterior abdominal wall are innervated by the lower six thoracic nerves and the first lumbar nerve.

Lower thoracic nerves

At the costal margin, thoracic nerves 7–11 leave their intercostal spaces and enter the neurovascular plane of the abdominal wall between transversus abdominis and internal oblique (Fig. 4.17). The seventh and eighth nerves slope upwards, the ninth runs horizontally and the tenth and eleventh incline downwards. The nerves pierce rectus abdominis and the anterior layer of the rectus sheath to emerge as anterior cutaneous branches that supply the overlying skin (Fig. 4.12).

The subcostal nerve (T12) takes the line of the twelfth rib across the posterior abdominal wall (p. 201). It continues around the flank in the neurovascular plane and terminates in a similar manner to the lower intercostal nerves.

The seventh to twelfth thoracic nerves give off lateral cutaneous nerves, which further divide into anterior and posterior branches. The anterior branches supply skin as far forwards as the lateral edge of rectus abdominis while the posterior branches supply skin overlying latissimus dorsi. The lateral cutaneous branch of the subcostal nerve is distributed to the skin on the side of the buttock.

First lumbar nerve

The first lumbar nerve divides into upper and lower branches, the iliohypogastric and ilioinguinal nerves (Figs 4.102 & 4.103). The iliohypogastric nerve reaches the neurovascular plane in the loin and divides just above the iliac crest into two terminal branches. The lateral cutaneous branch supplies the side of the buttock and the anterior cutaneous branch supplies the suprapubic region.

The ilioinguinal nerve leaves the neurovascular plane by piercing internal oblique above the iliac crest (Fig. 4.14). It continues between the two oblique muscles and accompanies the spermatic cord or round ligament of the uterus in the inguinal canal (Figs 4.21 & 4.24). Emerging from the superficial inguinal ring (Fig. 4.20), it gives cutaneous branches to skin on the medial side of the root of the thigh, the proximal part of the penis and front of the scrotum or the mons pubis and the anterior part of the labium majus.

Blood vessels

The blood supply to the abdominal wall is provided by the superior and inferior epigastric arteries, supplemented by the musculophrenic artery and the lower posterior intercostal arteries. The superior epigastric artery descends behind rectus abdominis and may anastomose with the inferior epigastric artery (Fig. 4.18). The latter vessel arises from the external iliac artery immediately above the inguinal ligament and inclines upwards and medially, passing just medial to the deep inguinal ring (Figs 4.18 & 4.23). The inferior epigastric artery enters the rectus sheath by passing in front of its posterior wall at the arcuate line. From the anterior ends of the lower two or three intercostal spaces, posterior intercostal arteries continue forwards in the neurovascular plane.

Venous drainage of the deeper layers of the abdominal wall is via venae comitantes of the respective arteries. Blood from the superficial tissues drains into veins, lying in the subcutaneous tissue, which run towards the axilla and groin. Dilatation of the subcutaneous veins is an important clinical sign in patients with obstruction of venous flow within the abdomen, for example, within the inferior vena cava or the liver. Dilatation of the superficial veins is an important clinical sign in patients with portal vein obstruction (p. 185).

Lymphatics

Lymph from the abdominal wall above the level of the umbilicus drains upwards. Lymphatics from the skin and subcutaneous tissue accompany the subcutaneous veins and drain into the axillary nodes, while those from the deeper tissues follow the course of the superior epigastric artery to the internal thoracic nodes. The superficial lymphatics of the lower half of the abdominal wall pass to the superficial inguinal nodes, while the deeper lymph vessels follow the course of the inferior epigastric artery to reach the external iliac nodes.


Pubic symphysis and crest
Superficial inguinal ring
Deep inguinal ring
Inguinal ligament
Anterior superior iliac spine
Penis
Spermatic cord
Pubic tubercle
Femoral artery
S
R
L
I

Fig. 4.19 Position of the inguinal canal and its superficial and deep rings in relation to the inguinal ligament.

Inguinal Canal

The inguinal canal is about 4 cm long and passes obliquely through the flat muscles of the abdominal wall just above the medial half of the inguinal ligament (Fig. 4.19). In the male, the canal conveys the spermatic cord (comprising the ductus [vas] deferens and the vessels and nerves of the testis). In the female, the canal is narrower and contains the round ligament of the uterus.

The lateral end of the canal opens into the abdominal cavity at the midinguinal point, defined as midway between the pubic symphysis and the anterior superior iliac spine. In clinical practice, the midinguinal point serves as a guide to the deep inguinal ring and the femoral artery (Fig. 4.2). There may be individual variation in the relative positions of the deep inguinal ring, the femoral artery, and the bony landmarks, and some authors refer to the midinguinal point or the midpoint of the inguinal ligament as appropriate surface markings. The medial end of the canal opens into the subcutaneous tissues at the superficial inguinal ring, an aperture in the external oblique aponeurosis immediately superior to the pubic tubercle (Fig. 4.20). Continuous with the margins of the superficial ring is a thin sleeve surrounding the spermatic cord, the external spermatic fascia (Fig. 4.21).


Superficial inguinal ring
External oblique aponeurosis
Inguinal ligament
Fascia lata
Ilioinguinal nerve (cut)
Cremasteric fascia
External spermatic fascia
Great saphenous vein
S
R
L
I

Fig. 4.20 Removal of the skin and subcutaneous tissue reveals both superficial inguinal rings (male specimen). On one side the external spermatic fascia has been removed to show the margins of the superficial ring.

Boundaries

The canal comprises a floor, a roof, and an anterior and a posterior wall. The gutter-shaped floor is formed by the inguinal ligament (Fig. 4.22), the in-turned lower edge of the external oblique aponeurosis. The ligament attaches laterally to the anterior superior iliac spine and medially to the pubic tubercle and the pectineal line of the pubis. The expanded medial end of the inguinal ligament, the lacunar ligament, lies in the floor of the medial end of the canal, and its concave lateral edge forms the medial boundary of the femoral ring (Fig. 4.23 and p. 262).

The roof is formed by the lowest fibres of internal oblique and transversus abdominis (Fig. 4.22). These fibres arch over the canal and pass medially and downwards to form the inguinal falx (conjoint tendon), which attaches to the crest and pectineal line of the pubis. The anterior wall of the canal is formed by the external oblique aponeurosis, supplemented laterally by fibres of internal oblique. These fibres arise from the lateral part of the inguinal ligament and cover the anterior aspect of the deep ring (Fig. 4.21). The posterior wall is formed by the transversalis fascia, reinforced medially by the conjoint tendon. Deep to the transversalis fascia are the inferior epigastric vessels, which lie just medial to the deep


Cremasteric fascia
External oblique aponeurosis (cut)
Fibres of internal oblique
S
R
L
I
External spermatic fascia (cut)
Ilioinguinal nerve (cut)

Fig. 4.21 External spermatic fascia and a strip of the external oblique aponeurosis have been removed to show the spermatic cord and ilioinguinal nerve within the canal.


S
R
L
I
External oblique aponeurosis (cut)
Internal oblique (cut)
Inguinal falx
Transversus abdominis
Transversalis fascia
Lacunar ligament
Pubic tubercle
Testicular artery
Pampiniform plexus
Ductus deferens
Testicular veins and artery
Internal spermatic fascia

Fig. 4.22 Lower fibres of internal oblique and part of the spermatic cord have been excised to reveal the posterior wall and floor of the canal.

ring (Fig. 4.23). The inferior epigastric artery may be at risk during operations to repair inguinal hernias.

The inguinal canal is a site of potential weakness in the abdominal wall through which intra-abdominal structures may pass, producing an inguinal hernia (see below). However, several features of the canal's anatomy minimize this weakness. The obliquity of the canal ensures that the superficial and deep inguinal rings do not overlie one another (Fig. 4.19). Furthermore, the strongest part of the anterior wall lies in front of the deep ring and the strongest part of the posterior wall lies behind the superficial ring. Hence, when pressure within the abdomen rises, the anterior and posterior walls of the canal are firmly opposed. In addition, when the abdominal muscles contract, the canal is compressed by the descent of fibres of internal oblique and transversus abdominis in its roof.

Contents

In the male, the canal contains the spermatic cord (Fig. 4.21). In the female, it transmits the round ligament of the uterus (Fig. 4.24), a fibromuscular cord running from the body of the uterus to the subcutaneous tissues of the labium majus. Lymphatics from part of the body of the uterus accompany the round ligament and terminate in the superficial inguinal nodes (Fig. 6.11).

In both sexes, the ilioinguinal nerve (Fig. 4.14) lies deep to the external oblique aponeurosis close to the inguinal ligament. The nerve runs medially in the anterior wall of the canal and emerges through the superficial ring (Figs 4.20 & 4.24).


Testicular artery entering deep inguinal ring
Inferior epigastric artery (cut)
Lacunar ligament
L
A
P
R
Femoral and genitofemoral nerves
External iliac artery and vein
Ureters
Femoral ring
Ductus deferens emerging from deep inguinal ring

Fig. 4.23 Superior view of the male pelvis to show structures near the deep inguinal ring.


Superficial inguinal ring
External oblique aponeurosis (cut)
Fibres of internal oblique
Inguinal ligament
S
R
L
I
Inguinal falx
Round ligament of uterus
Ilioinguinal nerve

Fig. 4.24 Superficial ring and inguinal canal in the female showing the round ligaments of the uterus.

Inguinal hernias

The inguinal canal is the most common site for an abdominal hernia. Two types of inguinal hernia are recognized. The direct type pushes through the inguinal falx into the medial part of the canal. By contrast, the indirect (oblique) type traverses the deep ring and turns medially along the canal. Hernias of both types may emerge through the superficial ring and descend into the scrotum or labium majus. Direct and indirect hernias are distinguished by their relationships to the inferior epigastric vessels. A direct hernia lies on the medial side of these vessels, while the indirect type enters the inguinal canal lateral to them.

The processus vaginalis normally closes but may remain patent in infancy, leaving a tubular channel connecting with the peritoneal cavity. Herniation along the patent processus, called an infantile inguinal hernia, is more common in the male child and may extend into the tunica vaginalis around the testis (p. 151).

Scrotum

The scrotum is a pouch of skin and fascia derived from the anterior abdominal wall and contains the testes, epididymides and the lower parts of the spermatic cords (Fig. 4.25).

Skin and subcutaneous tissue

The skin of the scrotum is supplied anteriorly by the external pudendal vessels and innervated by the ilioinguinal nerve. The remainder of the scrotal skin is supplied by branches of the internal pudendal vessels and branches of the pudendal nerve and posterior cutaneous nerve of thigh. Lymph drains to the superficial inguinal nodes.

Deep to the skin lies the subcutaneous tissue, continuous superiorly with the subcutaneous tissue of the abdominal wall. The scrotal subcutaneous tissue, which contains smooth muscle called dartos, but little fat, forms a median septum, dividing the pouch into right and left sides.



Fig. 4.25 Transverse section through scrotum. The spermatic fasciae are trimmed flush with the subcutaneous tissue.

Ductus deferens
Epididymis
R
P
L
A
Testis and tunica albuginea
Parietal layer of tunica vaginalis
Visceral layer of tunica vaginalis
External spermatic fascia

Spermatic fasciae

Deep to the subcutaneous tissue of each side of the scrotum lie three layers of spermatic fascia (Fig. 4.26). Each layer takes the form of a sleeve derived from one of the layers of the abdominal wall.

The outermost sleeve, the external spermatic fascia, begins at the superficial inguinal ring and is continuous with the external oblique aponeurosis (Fig. 4.20). The intermediate sleeve is the cremasteric fascia and muscle, continuous within the inguinal canal with the internal oblique muscle (Fig. 4.21). The transversalis fascia of the abdominal wall (Fig. 4.22) provides the deepest sleeve, the internal spermatic fascia, which commences at the deep inguinal ring. These three fascial layers surround the components of the spermatic cord and continue downwards to enclose the testis and epididymis.

Spermatic cord

The spermatic cord runs from the deep inguinal ring into the scrotum, terminating posterior to the testis. The cord comprises the ductus (vas) deferens and the vessels and nerves of the testis and epididymis (Fig. 4.27) surrounded by the layers of spermatic fascia (Fig. 4.26).

The principal artery of the spermatic cord is the testicular artery, a branch of the abdominal aorta (Figs 4.88 & 4.89). Also present is the artery to the ductus deferens (Fig. 4.28), usually arising from the superior vesical artery within the pelvic cavity. The veins draining the testis and


Ductus deferens
Testicular artery
Pampiniform plexus
Internal spermatic fascia
Cremasteric fascia
External spermatic fascia
S
A
P
I

Fig. 4.26 Left testis and spermatic cord within their fascial sleeves.


Ductus deferens
Testicular artery
Pampiniform plexus
Fat
Parietal layer of tunica vaginalis (cut)
Head of epididymis
Testis and its appendix
S
A
P
I

Fig. 4.27 Anterolateral part of the parietal layer of the tunica vaginalis has been removed to reveal the testis and head of the epididymis. This testis bears a vestigial tag, the appendix of the testis.


Testicular artery
Ductus deferens and artery
Head and body of epididymis
Efferent ductules
Superior pole of testis
Inferior pole of testis
Tail of epididymis
S
A
P
I

Fig. 4.28 Lateral aspect of testis and epididymis after removal of the tunica vaginalis and pampiniform plexus. The head of the epididymis has been lifted to display the efferent ducts.

epididymis form a network, the pampiniform plexus. Occasionally, these veins become dilated (varicocele; p. 188). From this plexus, one or two veins continue through the deep inguinal ring and ascend the posterior abdominal wall with the testicular artery (Fig. 4.88). The testicular vessels are accompanied by a plexus of autonomic nerves and by lymph vessels which terminate in the aortic lymph nodes.

Tunica vaginalis

The tunica vaginalis is a closed serous sac, which covers the medial, anterior and lateral surfaces of the testis and the lateral aspect of the epididymis (Figs 4.25 & 4.27). Like the peritoneum from which it is derived, the tunica vaginalis has parietal and visceral layers separated by a small quantity of serous fluid. An excessive accumulation of fluid in the sac produces a swelling (hydrocele) anterior to the testis.

In the fetus, the processus vaginalis links the tunica vaginalis with the peritoneal cavity. Usually, the processus closes before birth, but occasionally it remains patent and is associated with infantile hernia.

Testis

The testis is an ovoid organ approximately 5 cm long in the adult, suspended by the spermatic cord in the lower part of the scrotum with its superior pole tilted slightly forwards (Fig. 4.28). The testis has a thick fibrous capsule, the tunica albuginea, which is covered laterally, anteriorly and medially by the visceral layer of the tunica vaginalis (Fig. 4.25). The posterior surface of the organ, devoid of a covering of tunica vaginalis, is pierced by the efferent ductules, branches of the testicular artery and numerous small veins that form the pampiniform plexus (Figs 4.28 & 4.29).

Although the testis usually completes its descent into the scrotum by the time of birth, it may remain in the abdomen or the inguinal canal. In this case, surgical intervention is usually advised.

The testis may rotate, twisting the spermatic cord (torsion). The arterial supply is threatened and urgent surgical correction is needed to prevent necrosis of the testis. Tumours of the testis are common in young adults and may metastasize to the para-aortic nodes. Treatment involves removal of the organ (orchidectomy).

Epididymis

The epididymis consists of a narrow, highly convoluted duct applied to the posterior surface of the testis (Fig. 4.29). Its broad superior part, the head, overhangs the upper pole of the testis, from which it receives several efferent ductules (Fig. 4.28). The body of the epididymis tapers into the tail, which is continuous with the ductus deferens. The epididymis is supplied by branches of the testicular artery and drained by the pampiniform plexus.

Ductus (vas) deferens

The ductus deferens is approximately 25 cm long and connects the tail of the epididymis with the ejaculatory duct in the prostate gland. The ductus ascends behind the testis on the medial side of the epididymis and continues upwards in the cord. When the upper part of the scrotum is palpated, the ductus can be distinguished from the accompanying testicular vessels by its firmness.

After traversing the inguinal canal, the ductus runs backwards across the pelvic brim and along the lateral wall of the pelvis (Fig. 4.23) before terminating in the ejaculatory duct (Fig. 5.24).



Fig. 4.29 Posterior view of testis, epididymis and ductus deferens.

Peritoneum

The peritoneum is a serous membrane with parietal and visceral layers, which encloses a space, the peritoneal cavity. The parietal peritoneum lines the walls of the abdomen and pelvis, while the visceral layer covers many of the abdominal and pelvic organs. In the male, the peritoneal cavity is a closed sac, but in the female, it communicates with the interior of the uterus and vagina via a microscopic channel through each uterine tube. Normally, the peritoneal cavity contains only a few millilitres (mL) of serous fluid, but in certain diseases, serous fluid can accumulate (ascites), sometimes up to several litres.

The peritoneal cavity comprises the greater and lesser sacs. The greater sac is very extensive and can be traced from the diaphragm above into the pelvic cavity below. The omental bursa (lesser sac) is located in the upper part of the abdomen behind the stomach and communicates with the greater sac through a narrow opening, the omental (epiploic) foramen.

Parietal peritoneum

The parietal peritoneum is applied to the inner aspect of the abdominal and pelvic walls (Fig. 4.30) and continues superiorly across most of the undersurface of the diaphragm. The peritoneum lining the anterior abdominal wall is raised into several folds or ridges. Below the umbilicus, the median umbilical ligament often raises a midline ridge (median umbilical fold), on each side of which the occluded part of the umbilical artery (medial umbilical ligament) may produce a further peritoneal fold (medial umbilical fold) (Fig. 4.31). Above the umbilicus, the round ligament of the liver (Fig. 4.30) is contained in a large fold of peritoneum, the falciform ligament, which attaches the liver to the anterior abdominal wall and the diaphragm (Fig. 4.57).

Posteriorly, the peritoneum covers several organs that lie on the muscles of the posterior abdominal wall (Fig. 4.32). These retroperitoneal organs include the ascending and descending parts of the colon, the kidneys, ureters and suprarenal glands, and most of the pancreas and duodenum. Also lying behind the peritoneum are the aorta and its branches and the inferior vena cava and its tributaries.

Nerve supply

The parietal peritoneum of the abdominal wall is innervated by the lower thoracic and first lumbar nerves. Inflammation spreading from an organ such as the appendix to this peritoneum causes well-localized pain and tenderness and rigidity of the abdominal muscles. The lower thoracic nerves also innervate the peritoneum covering the periphery of the diaphragm. Inflammation of this peritoneum consequently gives rise to pain in the lower thoracic wall and abdominal wall. By contrast, the peritoneum on the central part of the diaphragm receives sensory branches from the phrenic nerves (C3, C4 & C5) and irritation here may produce pain referred to the region of the shoulder (the fourth cervical dermatome; Fig. 3.6).



Fig. 4.30 Removal of muscles and fascia of the anterior abdominal wall reveals the parietal peritoneum and extraperitoneal structures.


S
L
R
I
Gluteal muscles
Iliopsoas
Position of umbilicus
Iliac crest
Common iliac vessels
Bladder
Medial umbilical fold
Pelvic peritoneum

Fig. 4.31 Removal of the abdominal organs from a coronal section shows the parietal peritoneum from within.


Inferior vena cava
Peritoneum covering retroperitoneal structures
Ascending colon
Parietal peritoneum
Aorta
Descending colon
A
R
L
P

Fig. 4.32 Transverse section at the level of the third lumbar vertebra showing parietal peritoneum and some retroperitoneal structures. Inferior aspect.

Visceral peritoneum and mesenteries

Most of the abdominal organs have a covering of visceral peritoneum and are suspended within the abdominopelvic cavity by mesenteries. Although organs possessing mesenteries are often termed intraperitoneal, they do not lie within the peritoneal cavity but merely project into it. Mesenteries consist of double layers of peritoneum containing the vessels and nerves of the intraperitoneal organs. Typically, a mesentery attaches to the posterior abdominal wall, where its peritoneal layers are continuous with the parietal peritoneum. Examples include the mesentery of the small intestine (Fig. 4.35) and the transverse mesocolon.

The mesenteries of the stomach (the omenta) do not attach to the abdominal wall but to other organs. The lesser curvature of the stomach is connected to the liver by the lesser omentum, while the upper part of the greater curvature is attached to the spleen by the gastrosplenic ligament (Figs 4.37 & 4.38). The major portion of the greater curvature gives attachment to the greater omentum.

The greater omentum is an apron-like fold of peritoneum with a free lower border (Fig. 4.33). Hanging behind the anterior abdominal wall and in front of most of the small intestine, this omentum is usually a conspicuous feature when the peritoneal cavity is opened. Superiorly, it attaches to both the transverse colon (Fig. 4.34) and the greater curvature of the stomach, enclosing the inferior part of the omental bursa (see below). The free inferior border of the omentum ascends on the right as far as the first part of the duodenum, while on the left it merges with the gastrosplenic ligament. The position of the greater omentum is influenced by previous episodes of intra-abdominal disease because it tends to adhere to sites of inflammation such as the appendix or gall bladder.

The transverse mesocolon (Fig. 4.35) has a long horizontal root, attached across the posterior aspect of the abdomen, principally to the pancreas. This mesocolon slopes downwards and forwards into the greater sac, dividing it into supracolic and infracolic compartments. Along its lower margin, close to the anterior abdominal wall, runs the transverse colon.

Infracolic compartment of the greater sac

This compartment lies below and behind the transverse mesocolon and is usually covered anteriorly by the greater omentum. The infracolic compartment consists of right and left spaces separated by the mesentery of the small intestine (Fig. 4.35). The root of this mesentery begins to the left of the midline near the transverse mesocolon and slopes downwards into the right iliac fossa. The mesentery is extensively folded and is attached to the jejunum and ileum. The left infracolic space communicates directly with the cavity of the pelvis. By contrast, the right infracolic space is confined inferiorly by the attachment of the lower part of the mesentery.

Behind the peritoneum on either side of the infracolic compartment lie the ascending and descending parts of the colon. Lateral to these are grooves lined by peritoneum, the right and left paracolic gutters (Fig. 4.68).



Fig. 4.33 Greater sac after removal of most of the parietal peritoneum. In this specimen the greater omentum is adherent to the right side of the diaphragm, concealing the right lobe of the liver and the gall bladder.


Greater omentum (displaced)
Caecum
S
R
L
I
Transverse colon
Jejunum
Ileum
Sigmoid colon

Fig. 4.34 Greater omentum has been turned upwards to display the contents of the infracolic compartment of the greater sac.


Mesentery of small intestine (cut)
Terminal ileum (cut)
Vermiform appendix
Transverse colon and mesocolon
Jejunal vessels (cut)
Descending colon
Sigmoid colon and mesocolon
S
R
L
I

Fig. 4.35 Infracolic compartment of the greater sac. Removal of the jejunum and ileum has revealed their mesenteries. The descending colon is more medially placed than usual.


Diaphragm (cut)
Right and left lobes of liver
Subphrenic spaces
Fibrous pericardium
S
R
L
I
Falciform and round ligaments of liver (cut)
Transverse mesocolon and colon
Greater omentum (cut)
Anterior and posterior surfaces of stomach

Fig. 4.36 Supracolic compartment of the greater sac. After removal of most of the greater omentum, the greater curvature of the stomach has been displaced upwards to show the position of the omental bursa (pink).


Left lobe of liver (cut)
Lesser curve of stomach and lesser omentum
S
R
L
I
Omental foramen
Superior duodenum
Anterior surface of stomach
Greater curve of stomach and greater omentum (cut)

Fig. 4.37 Lesser omentum exposed by removal of part of the left lobe of the liver. The pink arrow (right) traverses the omental foramen into the omental bursa, which lies behind the lesser omentum.

Another mesentery, the sigmoid mesocolon, lies in the left lower part of the infracolic compartment. Its root is shaped like an inverted 'V', with its apex overlying the bifurcation of the left common iliac vessels and the left ureter. Behind the sigmoid mesocolon lies the intersigmoid recess, which ends blindly at the apex of the 'V' but is continuous inferiorly with the pelvic cavity.

Small folds of peritoneum may produce additional peritoneal recesses (or fossae) near the ascending duodenum (paraduodenal recesses) and the caecum (retrocaecal and ileocaecal recesses). A loop of bowel can become trapped in a peritoneal recess, producing an internal hernia, which may lead to intestinal obstruction.

Nerve supply

The autonomic nerves that supply the abdominal organs also innervate the visceral peritoneum surrounding the organs. Pain conveyed by these nerves tends to be deeply felt and poorly localized.

Supracolic compartment of the greater sac

The supracolic compartment lies above and in front of the transverse mesocolon (Fig. 4.36). Its superior part intervenes between the diaphragm and the liver and is divided by the falciform ligament into two subphrenic spaces. The compartment includes the deep recess between the right lobe of the liver and the right kidney (the hepatorenal recess) and extends across the midline below the left lobe of the liver and in front of the stomach. Infection within the abdomen or pelvis can spread through the peritoneal cavity and may accumulate near the liver, producing an abscess. Abscesses between the diaphragm and the liver are termed subphrenic and those below the liver subhepatic.

Omental bursa (lesser sac)

The omental bursa is the small part of the peritoneal cavity behind the stomach (Figs 4.36 & 4.38). It communicates with the greater sac through a narrow opening, known as the omental or epiploic foramen, which lies between the first part of the duodenum and the visceral surface of the liver (Fig. 4.37).

The omental bursa is isolated from the greater sac by the stomach and several peritoneal folds. One of these folds, the lesser omentum, connects the lesser curvature of the stomach to the posterior surface of the liver (Fig. 4.37). Two further folds, the gastrosplenic and splenorenal (lienorenal) ligaments, attach the spleen to the greater curvature of the stomach and the left kidney, respectively (Fig. 4.38).

The omental bursa extends upwards behind the stomach and the caudate lobe of the liver as far as the diaphragm. On the left, it continues to the hilum of the spleen, terminating between the gastrosplenic and splenorenal ligaments. Inferiorly, the omental bursa usually extends a short distance below the greater curvature of the stomach between the gastric and colic attachments of the greater omentum. To the right, it communicates through the epiploic foramen with the hepatorenal recess of the greater sac.





Fig. 4.38 Transverse section at the level of the disc between the twelfth thoracic and first lumbar vertebrae. The pink arrow (lower) traverses the omental foramen into the omental bursa (pink area). In this specimen the left kidney lies lower than usual. Superior aspect.


Inferior vena cava (cut)
Oesophagus
Liver (cut)
Lesser omentum
Anterior surface of stomach
Aorta
Left dome of diaphragm (cut)
Gastrosplenic ligament
Spleen
Right gastro-omental artery
Transverse mesocolon
S
R
L
I

Fig. 4.39 Stomach and some of its relations, seen after removal of the anterior half of the diaphragm and left lobe of the liver and dissection of the greater omentum.


Pylorus
Cardiac orifice
Cardiac notch
S
R
L
I
Greater curvature
Lesser curvature
Rugae
Incisura angularis
Pyloric canal
Pyloric antrum
Fundus
Body
Pyloric part

Fig. 4.40 Longitudinal section through the stomach.

Stomach

The stomach is the dilated portion of the gut, in which the early stages of digestion take place. It lies in the upper part of the abdomen beneath the left dome of the diaphragm (Fig. 4.39). Proximally, the stomach joins the oesophagus at the cardiac orifice and distally, it is continuous with the duodenum at the pylorus. Between these two relatively fixed points, the organ varies considerably in size, shape and location in response to its muscle tone, the quantity and nature of its contents and the position of the individual (Figs 4.41 & 4.42). Usually, the loaded stomach is J-shaped and lies in the left hypochondrium, the epigastrium and umbilical region of the abdomen.

The oesophagus pierces the diaphragm and has a short intra-abdominal course before joining the stomach at the cardiac orifice. This lies a little to the left of the midline at about the level of the eleventh thoracic vertebra (Fig. 4.42). Anatomical and physiological factors produce a sphincteric effect at the gastro-oesophageal junction. If this mechanism fails, gastric contents can regurgitate into the oesophagus (gastro-oesophageal reflux), causing inflammation of the oesophageal mucosa.

The stomach has two surfaces, anterior and posterior, which meet at two curved borders, the curvatures (Fig. 4.40). The lesser curvature extends from the cardiac orifice downwards and to the right, to reach the upper border of the pylorus. A notch, the incisura angularis, is usually present on the lesser curvature towards its pyloric end. The greater curvature is longer and begins at the cardiac notch on the left side of the cardiac orifice. It arches upwards and to the left before descending along the left and inferior aspects of the organ to reach the inferior border of the pylorus.

The pylorus is normally situated just to the right of the midline at the level of the first lumbar vertebra, on the transpyloric plane.

By convention, the stomach is described as having three parts, the fundus, the body and the pyloric part (Fig. 4.40). The fundus lies above an imaginary horizontal plane passing through the cardiac orifice, while the antrum lies to the right of the incisura angularis. The body lies between the fundus and the pyloric part and is the largest part of the stomach. In the pyloric part, the cavity of the pyloric antrum tapers to the right into a narrow passage, the pyloric canal.

The mucosal lining presents numerous longitudinal folds or rugae, which are most prominent when the stomach is empty (Fig. 4.40). There is a well-developed smooth muscle coat, which is thickened around the pyloric canal and pylorus to form the pyloric sphincter.

Relations

The anterior surface of the stomach lies in contact with the diaphragm, the anterior abdominal wall and the left and quadrate lobes of the liver. Posterolateral to the fundus lies the gastric surface of the spleen (Fig. 4.39). The remainder of the stomach's relations are situated posteriorly and collectively form the stomach bed. This includes the diaphragm, left suprarenal gland, upper part of the left kidney, the splenic artery, pancreas, transverse mesocolon and sometimes, the transverse colon (Fig. 4.43). However, these structures are separated from the stomach by the omental bursa (p. 157). Gastric ulcers can perforate into either the greater sac or the omental bursa. Sometimes, ulceration may involve the pancreas or the splenic artery.



Fig. 4.41 Anteroposterior radiograph after a barium meal and follow through.



Fig. 4.42 Barium meal radiograph with patient tilted head down.


Liver (cut)
Anterior surface of stomach
Posterior surface of stomach
Pancreas (deep to peritoneum)
Right gastro-omental vessels
Transverse mesocolon and colon
A short gastric artery
Gastrosplenic ligament
Left gastro-omental artery
Spleen
A
R
L
P

Fig. 4.43 Omental bursa (pink) and stomach bed, seen after removal of the greater omentum and lifting the greater curvature upwards.

Omenta

Attached to each curvature of the stomach is an omentum, a double layer of peritoneum. The lesser omentum extends from the liver (Fig. 4.37) to the lesser curvature and also attaches to the abdominal oesophagus and the commencement of the duodenum (Fig. 4.39). Near the lesser curvature, this omentum contains the left and right gastric vessels (Fig. 4.44), accompanied by lymphatics and autonomic nerves, while its free border encloses the portal vein, the bile duct and the proper hepatic artery.

The greater omentum hangs from the distal part of the greater curvature and from the superior duodenum. Near the greater curvature, it contains the left and right gastro-omental (gastroepiploic) vessels (Fig. 4.43). To the left, the greater omentum is continuous with the gastrosplenic ligament, which connects the proximal part of the greater curvature to the hilum of the spleen.

Arterial supply

The stomach is supplied by several arteries, which are all derived from branches of the coeliac trunk and which anastomose


Caudate lobe of liver
Right crus of diaphragm
Anterior vagal trunk
Oesophageal artery and vein
Bile duct, proper hepatic artery and portal vein
Right gastric artery
Pancreas
Left gastric artery and vein
S
R
L
I

Fig. 4.44 Dissection of the lesser omentum showing structures along the lesser curvature of the stomach.

extensively with each other. The coeliac trunk (Fig. 4.45) is a short, wide vessel arising from the anterior aspect of the aorta just below the diaphragm. It divides into three branches: the left gastric, the common hepatic and the splenic arteries.

The left gastric artery is the smallest branch, passing upwards and to the left behind the omental bursa to reach the oesophagus, then descending along the lesser curvature within the lesser omentum (Fig. 4.44). Its branches include two or three to the lower oesophagus, which ascend through the oesophageal opening of the diaphragm. Other branches supply the cardia and lesser curvature of the stomach.

The common hepatic artery gives rise to the right gastric and gastroduodenal arteries. The right gastric artery (Fig. 4.44) arises above the superior duodenum and runs to the left within the lesser omentum, supplying the lesser curvature and anastomosing with the left gastric artery. One of the branches of the gastroduodenal artery is the right gastro-omental (gastroepiploic) artery (Fig. 4.43). This vessel runs to the left within the greater omentum, parallel to the greater curvature, giving numerous branches to the pyloric part and body of the stomach.

The splenic artery is the largest branch of the coeliac trunk (Fig. 4.45). It runs a tortuous course to the left along the superior border of the pancreas, initially behind the omental bursa and then within the splenorenal ligament, and terminates near the hilum of the spleen. It provides collateral branches to the pancreas and terminal branches to the spleen and stomach. There are several gastric branches, which pass to the greater curvature by way of the gastrosplenic ligament. Most of these vessels supply the fundus of the stomach and are called short gastric arteries (Fig. 4.43). However, one branch, the left gastro-omental (gastroepiploic) artery, continues downwards and to the right within the greater omentum. It follows the greater curvature, supplies the body of the stomach and may anastomose with the right gastro-omental (gastroepiploic) artery.

Venous drainage

The veins of the stomach accompany the gastric arteries and drain into the portal venous system, the portal vein itself receiving the right and left gastric veins. The splenic vein receives the short gastric and left gastro-omental (gastroepiploic) veins, while the right gastro-omental vein usually enters the superior mesenteric vein. The oesophageal tributaries of the left gastric vein (Fig. 4.44) take part in an important portacaval anastomosis (p. 185) with tributaries of the azygos venous system within the thorax.

Nerve supply

In the thorax, the vagus nerves form a plexus on the surface of the oesophagus. From this plexus emerge two principal nerves, the anterior and posterior vagal trunks, which enter the abdomen on the respective surfaces of the oesophagus. The anterior vagal trunk (Fig. 4.44), derived mostly from the left vagus nerve, gives branches to the anterior surface of the stomach, including the pyloric region. Branches from the posterior trunk, whose origin is mainly from the right vagus nerve, pass to the posterior surface of the stomach and also to the coeliac plexus (pp 197, 199). The parasympathetic innervation of the stomach by the vagus nerves is important in relation to both secretion and motility of the organ.



Fig. 4.45 Stomach and most of the pancreas have been removed to reveal the coeliac trunk and its branches.

Spleen

The spleen is a lymphoid organ lying in the left hypochondrium posterior to the stomach. The fresh spleen is purple in colour and variable in size and shape. Since it lies entirely behind the midaxillary line and under cover of the left lower ribs, the normal spleen cannot be palpated in the living subject, even during full inspiration. The spleen is soft and very vascular and can be damaged by blunt or penetrating injuries resulting in life-threatening intraperitoneal haemorrhage. The blood may irritate the peritoneum lining the abdominal surface of the diaphragm, producing pain referred to the left shoulder region (p. 205).

Surface features

The spleen is oval in shape when viewed from its anterior aspect (Fig. 4.46) and its long axis lies parallel to the left tenth rib. The two extremities of the organ are connected by superior and inferior borders. The superior border often possesses one or more notches near its anterior end, while the inferior border is usually smooth. The organ has two easily distinguishable surfaces. The diaphragmatic surface faces backwards and laterally and is smoothly convex (Fig. 4.47). The visceral surface faces anteromedially and is characterized by ridges and depressions. The centrally placed hilum is perforated by numerous blood vessels together with lymphatics and nerves. The depressions around the hilum accommodate adjacent organs.



Fig. 4.46 Visceral surface of the spleen.



Fig. 4.47 Diaphragmatic surface of the spleen. This specimen has several well-defined notches on its superior border and a single notch on the inferior border.

Relations

The spleen is an intraperitoneal organ and most of its capsule is covered by peritoneum of the greater sac. However, there is a small bare area near the hilum, which gives attachment to two peritoneal folds or ligaments. The splenorenal (lienorenal) ligament runs medially to reach the left kidney, while the gastrosplenic ligament connects the spleen to the greater curvature of the stomach. Part of the omental bursa lies between these two ligaments and extends to the left as far as the splenic hilum (Fig. 4.38).

Arching above the spleen and descending posterior and lateral to it, the left dome of the diaphragm is responsible for movements of the organ during ventilation (Fig. 4.48). The diaphragm separates the spleen from the left lung and pleura, and from the ninth, tenth and eleventh ribs.

On the visceral surface of the spleen, above the hilum, is the gastric impression, which accommodates part of the posterior surface of the stomach. Below the medial half of the hilum is the renal impression, which abuts the superior pole of the left kidney.

Near the lateral extremity of its visceral surface, the spleen may possess a small colic impression, which lies against the left colic flexure. The tail of the pancreas extends laterally into the splenorenal ligament and its tip may reach the splenic hilum (Fig. 4.48).

Blood supply

The splenic artery is a direct branch of the coeliac trunk (p. 161). It follows a tortuous course along the upper border of the pancreas, giving off several pancreatic branches. The artery traverses the splenorenal ligament and divides into its terminal branches near the hilum of the spleen. Several splenic branches enter the hilum, while the short gastric arteries and the left gastro-omental artery enter the gastrosplenic ligament to supply the fundus and greater curvature of the stomach, respectively. Additional clumps of splenic tissue (splenunculi) may be present along the course of the artery.

Veins accompany the terminal branches of the splenic artery and unite adjacent to the hilum of the spleen to form the splenic vein. Running to the right, this vein lies posterior to the tail of the pancreas within the splenorenal ligament and continues retroperitoneally posterior to the body of the gland and inferior to the splenic artery. It then crosses the anterior aspects of the left kidney and renal vessels and receives several small tributaries from the pancreas. Posterior to the neck of the pancreas, the splenic vein unites with the superior mesenteric vein to form the portal vein and, close to its termination, is usually joined from below by the inferior mesenteric vein. If the pressure rises abnormally in the portal venous system (portal hypertension), the spleen may become enlarged (splenomegaly).



Fig. 4.48 Spleen and its vessels and relationship to the diaphragm, pancreas and left kidney. The stomach and part of the colon and peritoneum have been removed.

Duodenum

The duodenum, the proximal portion of the small intestine, begins at the pylorus and terminates at the duodenojejunal flexure. Deeply placed in the epigastric and umbilical regions of the abdomen, it curves round the head of the pancreas and is shaped like the letter 'C' (Fig. 4.49). Unlike the remainder of the small intestine, the duodenum is mostly retroperitoneal and therefore relatively immobile. The duodenal lumen receives bile and pancreatic secretions via the bile duct and the pancreatic ducts.

Parts and structure

The duodenum is conventionally described as consisting of four parts (Fig. 4.49). The superior (first part) begins slightly to the right of the midline at the level of the first lumbar vertebra (on the transpyloric plane) and passes upwards, backwards and to the right. In clinical practice, its initial portion is sometimes termed the duodenal bulb or cap. The descending duodenum (second part) runs vertically to the level of the third lumbar vertebra (Fig. 4.41). The inferior or horizontal duodenum (third part) runs to the left across the midline, arching forwards across the inferior vena cava and aorta. The ascending duodenum (fourth part) slopes upwards and to the left and terminates at the level of the second lumbar vertebra by turning sharply forwards at the duodenojejunal flexure. Close to the pylorus the duodenal mucosa is smooth but in the second and subsequent parts of the organ, it is raised to form numerous circular folds, the plicae circulares (Fig. 4.50). The commonest site for duodenal ulcers is in the first part.

The bile duct and main pancreatic duct approach the descending duodenum near its midpoint from the posteromedial aspect


Liver
Lesser omentum
Pylorus
Pancreas
Inferior mesenteric vein
S
R
L
I
Superior duodenum
Gall bladder
Descending duodenum
Transverse mesocolon and colon (cut)
Inferior vena cava
Duodenojejunal flexure
Ascending duodenum
Jejunal arteries (cut)
Superior mesenteric vein and artery (cut)
Horizontal duodenum

Fig. 4.49 Duodenum and some related structures. The liver and gall bladder have been slightly displaced.

(Fig. 4.51). They usually pierce the duodenal wall in proximity and commonly open into a single chamber, the hepatopancreatic ampulla (of Vater). The ampulla raises a projection, the major duodenal papilla, on the internal aspect of the duodenum. Bile and pancreatic secretions enter the duodenal lumen through the tip of this papilla via a minute opening controlled by a ring of smooth muscle, the ampullary sphincter (of Oddi). Immediately above the major duodenal papilla, there is often a prominent mucosal fold forming a hood (Fig. 4.50), which may serve as a guide to the location of the papilla, particularly during endoscopic examinations. The pancreas usually possesses a second and smaller duct, the accessory pancreatic duct, which enters the descending duodenum at the minor duodenal papilla, about 2 cm proximal to the major papilla.

Relations

Most of the duodenum is retroperitoneal. However, the initial 2 cm have peritoneal relationships similar to the stomach in that the lesser and greater omenta attach, respectively, to the superior and inferior borders. This short segment is relatively mobile and lies immediately inferior to the omental foramen (Fig. 4.49). Posterior duodenal ulcers may erode the pancreas or gastroduodenal artery (Fig. 4.52).

Anterior relations of the proximal portion of the duodenum include the liver and gall bladder. Crossing in front of the descending duodenum are the transverse colon and mesocolon (Fig. 4.49), below which lie coils of jejunum and ileum. Running obliquely across the inferior duodenum are the superior mesenteric vessels (Fig. 4.49), contained in the root of the mesentery of the small intestine. Adjacent to the ascending duodenum are often folds of peritoneum forming paraduodenal recesses.

Posteriorly, the superior duodenum is related to the portal vein, the bile duct and the gastroduodenal artery (Fig. 4.52). The descending duodenum lies in front of the hilum of the right kidney and the right renal vessels while the inferior duodenum crosses the right ureter and gonadal vessels, the inferior vena



Fig. 4.50 First and second parts of the duodenum opened to show the plicae circulares and the major duodenal papilla.



Fig. 4.51 Terminal portions of the bile and main pancreatic ducts and the hepatopancreatic ampulla have been opened.

cava, aorta and origin of the inferior mesenteric artery (Fig. 4.52). The ascending duodenum ascends in front of the left psoas muscle, the left gonadal and renal vessels and the inferior mesenteric vein.

Within the concavity of its C-shaped curve, all parts of the duodenum are related to the pancreas (Figs 4.49 & 4.52).

Blood supply

The gastroduodenal branch of the common hepatic artery descends behind the superior duodenum and divides into right gastro-omental and superior pancreaticoduodenal branches (Fig. 4.52). The latter vessel, which is often duplicated, runs in the interval between the duodenum and head of the pancreas and supplies the portion of the duodenum proximal to the major papilla.

The remainder of the duodenum is supplied by the inferior pancreaticoduodenal branch of the superior mesenteric artery (Fig. 4.52), given off as the superior mesenteric artery emerges from between the neck and uncinate process of the pancreas. The inferior pancreaticoduodenal artery runs to the right between the duodenum and pancreas, supplying both structures and anastomosing with the superior pancreaticoduodenal artery. The veins draining the duodenum follow the arterial supply and terminate in the portal venous system.


Common hepatic artery
Portal vein
Branch to pylorus
Pylorus (cut)
Gastroduodenal artery
Superior pancreatico-duodenal arteries
Right kidney
Right gastro-omental artery (cut)
Inferior vena cava
S
R
L
I
Superior mesenteric vein and artery (cut)
Inferior pancreatico-duodenal arteries
Inferior mesenteric artery and vein
Aorta

Fig. 4.52 Arterial supply and some relations of the duodenum. The superior duodenum has been displaced laterally to reveal the gastroduodenal artery, bile duct and portal vein.

Pancreas

The pancreas is both an exocrine and an endocrine gland. Most of its substance is involved in producing pancreatic juice, which is conveyed by a duct system into the descending duodenum. In addition, microscopic clumps of endocrine tissue, the pancreatic islets (islets of Langerhans), are dispersed throughout the gland.

The pancreas is a long and narrow, lobulated organ, deeply located on the posterior abdominal wall. It lies approximately on the transpyloric plane (L1 vertebral level) and slopes slightly upwards from right to left. Its extremities lie in the right and left paravertebral gutters, while the intermediate portion is thrust forwards in the midline by the prominence of the vertebral column and aorta.

The gland is divided into four parts, from right to left: the head, neck, body and tail (Fig. 4.53). The head is the broadest part and is surrounded by the loop of the duodenum. Projecting to the left from its lower portion is the uncinate process. The neck is indented posteriorly by the portal and superior mesenteric veins. The body, of fairly uniform width, extends to the left and is continuous with the tail, which tapers as it approaches the hilum of the spleen. The tail is contained within the splenorenal ligament but all other parts are retroperitoneal. The pancreas develops from two embryonic structures that fuse. This process may lead to constriction of the duodenum (annular pancreas), causing obstruction of the duodenum.


S
R
L
I
Neck of pancreas
Proper hepatic artery
Gastroduodenal artery
Decending duodenum
Superior mesenteric artery and vein (cut)
Head of pancreas
Body of pancreas
Spleen
Tail of pancreas
Splenic vein
Left kidney
Uncinate process
Horizontal duodenum

Fig. 4.53 Principal relations and parts of the pancreas.

In cross-section, the pancreas is triangular. It has well-defined superior and inferior borders and a blunt anterior border, to which is attached the transverse mesocolon. The inferior half of the gland is related to the infracolic compartment of the peritoneal cavity, while the upper half lies in the floor of the omental bursa and contributes to the stomach bed.

Relations

Surrounded by the loop of the duodenum, the head of the pancreas lies anterior to the inferior vena cava, the right renal vessels and the terminal portion of the bile duct, which is sometimes embedded within the substance of this part of the gland (Fig. 4.54). A tumour in the head of the pancreas can obstruct the bile duct, leading to jaundice. The anterior surface of the head is related to the first part of the duodenum, the transverse colon and the gastroduodenal artery (Fig. 4.53). The uncinate process lies immediately superior to the horizontal duodenum. The superior mesenteric vessels cross the anterior surface of the uncinate process and separate it from the neck of the gland, which lies in front of the superior mesenteric vein and the commencement of the portal vein. The anterior surface of the neck is separated from the pylorus by the omental bursa.

The body of the pancreas crosses the aorta and usually covers the origins of its ventral branches, the coeliac trunk, the common hepatic and splenic branches of which are related to the superior border of the gland (Fig. 4.55), and the superior mesenteric artery, which emerges at the lower border (Fig. 4.53). Further to the left, the gland covers the left renal vessels and suprarenal gland, and the hilum of the left kidney. Immediately posterior to the body, the splenic vein receives a major tributary, the inferior mesenteric vein (Figs 4.54 & 4.55). The inferior border of the body is related to the duodenojejunal flexure, coils of jejunum and the left colic flexure. Overlying the anterior surface of the body are the transverse mesocolon, the stomach and omental bursa, and part of the lesser omentum.

The tail of the gland lies within the splenorenal ligament and is accompanied posteriorly by the splenic vessels (Fig. 4.55). It lies anterior to the visceral surface and hilum of the spleen and posterior to the stomach and omental bursa.



Fig. 4.54 Dissection of the pancreas to expose the terminal portions of the bile and main pancreatic ducts.

Pancreatic ducts

The main pancreatic duct arises in the tail of the gland and traverses the body and neck to reach the head where it curves downwards and to the right, to reach the medial wall of the descending duodenum (Fig. 4.54). The duct receives numerous tributaries and gradually increases in calibre from left to right. It pierces the intestinal wall at the greater duodenal papilla (Fig. 4.51).

The main pancreatic duct and the bile duct usually enter the duodenal wall together and unite to form a common chamber, the hepatopancreatic ampulla (of Vater), in which pancreatic juice and bile may mix before entering the duodenal lumen. There is usually a second and smaller duct, the accessory pancreatic duct, which opens into the duodenum about 2 cm above the main duct, at the minor duodenal papilla. Reflux of bile into the pancreatic duct, due for example to impaction of a gallstone in the hepatopancreatic ampulla, can lead to pancreatitis.

Blood supply

This is derived from branches of the coeliac and superior mesenteric arteries. The head and uncinate process receive superior pancreaticoduodenal branches from the gastroduodenal artery (a branch of the hepatic artery; Fig. 4.53) and inferior pancreaticoduodenal branches from the superior mesenteric artery (Fig. 4.52). The remainder of the gland is supplied by branches from the splenic artery (Fig. 4.55). The venous drainage of the pancreas passes into the portal system. Superior and inferior pancreaticoduodenal veins from the head of the gland pass, respectively, into the portal vein and the superior mesenteric vein. Veins from the remainder of the gland terminate in the splenic vein.



Fig. 4.55 Principal vascular relations of the body and tail of the pancreas.

Liver

The liver is the largest organ in the body and lies in the upper part of the abdominal cavity just beneath the diaphragm and mostly under cover of the ribs. It fills the right hypochondrium and extends across the epigastrium into the left hypochondrium. The living organ is reddish-brown and very soft and delicate.

The surface marking of the inferior margin of the liver coincides with the right costal margin as far anteriorly as the ninth costal cartilage and inclines across the abdomen to the eighth left costal cartilage. The healthy liver is not often palpable in the living subject, even during deep inspiration when contraction of the diaphragm pushes the liver inferiorly.

The liver has the shape of a wedge, tapering towards the left (Fig. 4.56). Of its five surfaces, the superior, the anterior and the right lateral merge with no distinct borders intervening. However, a sharp inferior margin separates the anterior from the inferior or visceral surface. The latter faces obliquely downwards, backwards and to the left. The posterior surface blends with the visceral and superior surfaces at indistinct borders. Most of the surface of the liver is clothed in peritoneum.

Surface features and relations

Anterior and lateral surfaces

The anterior and lateral surfaces of the liver are smoothly convex to conform to the diaphragm and the anterior abdominal wall (Fig. 4.57). A two-layered fold of peritoneum, the falciform ligament, connects the anterior surface to the abdominal wall and demarcates the right and left lobes of the organ. In the free lower border of this ligament runs the fibrous remnant of the umbilical vein, the round ligament (ligamentum teres) of the liver, passing from the umbilicus to the visceral surface of the liver.

Superior surface

This surface is gently convex on each side of a shallow depression related to the central tendon of the diaphragm. Above the liver, the two layers of the falciform ligament diverge. One layer passes to the right and continues as the superior layer of the coronary ligament (Fig. 4.58); the other extends to the tip of the left lobe where it forms the left triangular ligament. The posterior layer of this ligament, when traced to the right, is continuous with the lesser omentum.

Visceral surface

This surface (Fig. 4.59) is divided into three areas by two vertical features, the gall bladder and the fissure for the round ligament, the upper ends of which are linked by a horizontal cleft. This cleft is the porta hepatis through which pass the branches of the proper hepatic artery and portal vein and the hepatic ducts. The round ligament (ligamentum teres hepatis) ascends along its fissure to reach the portal vein. To the left of the fissure the left lobe of the liver overlies the body of the stomach and lesser omentum. To the right of the fissure is the small rectangular quadrate lobe, which is related to the anterior aspects of the pyloric region of the



Fig. 4.56 Anterior view of the liver.


Right lobe of liver
Diaphragm (cut)
Falciform ligament and edge cut from anterior abdominal wall
Left lobe of liver
Subphrenic space
Gall bladder
Greater omentum
Stomach
Transverse colon
S
R
L
I

Fig. 4.57 Liver and some of its relations. In this specimen the greater omentum is adherent to the liver and stomach.


S
L
R
I
Left triangular ligament
Openings of hepatic veins
Inferior vena cava (partially removed)
Bare area
Left lobe
Fissure for ligamentum venosum
Caudate lobe
Superior and inferior layers of coronary ligament
Right triangular ligament

Fig. 4.58 Posterior view of the liver.



Fig. 4.59 Exposure of the porta hepatis reveals the hepatic and cystic ducts and related blood vessels.

stomach and the first part of the duodenum. To the right of the quadrate lobe is the gall bladder, embedded in its fossa. An impression to the right of the gall bladder accommodates the upper pole of the right kidney. This surface of the right lobe is also related to the right colic flexure and the descending duodenum.

Posterior surface

This surface is also divided into three areas (Fig. 4.58). Extending upwards from the left end of the porta hepatis is the fissure in which lies the ligamentum venosum, the fibrous remnant of the fetal ductus venosus. The lesser omentum attaches to the liver in the depths of this fissure and around the margins of the porta hepatis (Fig. 4.60). The portion of the liver to the left of the fissure covers the front of the abdominal oesophagus and the fundus of the stomach.

To the right of the fissure lies the caudate lobe, facing into the superior recess of the omental bursa. To the right of this lobe lies the inferior vena cava, which usually grooves the liver deeply. Further to the right is the bare area (Fig. 4.58), where the right lobe of the liver is in direct contact with the diaphragm and the right suprarenal gland with no intervening peritoneum. The bare area is bounded above and below by the two layers of the coronary ligament, which converge laterally to form the right triangular ligament.

Subphrenic and subhepatic spaces

The arrangement of the various peritoneal ligaments around the liver produces several spaces in which fluids may accumulate. Between the liver and the diaphragm are left and right subphrenic spaces (Fig. 4.57), separated from each other by the falciform ligament and the superior layer of the coronary ligament. The subhepatic spaces lie below and behind the liver, adjacent to either the stomach or the right kidney. Abscesses may occur in these spaces following infections elsewhere in the peritoneal cavity.

Biliary apparatus

Ducts

Bile produced by the liver is collected by a system of canaliculi that drain into the right and left hepatic ducts. The two hepatic ducts emerge through the porta hepatis and soon unite to form the common hepatic duct. As this duct descends in the free border of the lesser omentum, it is joined from the right by the cystic duct to form the bile duct (Fig. 4.59).

Initially, the bile duct lies in the free edge of the lesser omentum, to the right of the hepatic artery and in front of the portal vein. It then passes behind the first part of the duodenum with the gastroduodenal artery and curves to the right behind the head of the pancreas, sometimes grooving the gland (Fig. 4.54). The bile duct pierces the wall of the descending duodenum in company with the main pancreatic duct (Fig. 4.51). Impaction of stones within the bile duct can give rise to jaundice and to biliary colic, a severe intermittent pain in the epigastrium.

Gall bladder

This is a hollow, pear-shaped organ in which bile from the liver is concentrated and stored (Fig. 4.61). It lies against the visceral surface of the liver, often partially buried in its substance, and usually projects beyond the inferior margin to end blindly in a rounded fundus. The fundus normally makes contact with the anterior abdominal wall where the lateral edge (linea semilunaris) of the right rectus abdominis muscle crosses the costal margin (Fig. 4.2). The body of the gall bladder is its widest part and tapers superiorly into the neck, which continues as the cystic duct. This duct, through which bile enters and leaves, runs upwards towards


Posterior surface of stomach
Coeliac trunk (cut)
Lesser omentum
Caudate lobe
Inferior vena cava (cut)
Bare area of liver
S
L
R
I
Splenc artery (cut)
Body of pancreas (cut)
Splenic vein (cut)
Inferior mesenteric vein
Aorta (cut)
Common hepatic artery and portal vein
Bile duct
Superior mesenteric artery (cut) and vein
Duodenum

Fig. 4.60 Posterior view of liver, stomach and lesser omentum. The spleen, left kidney, parts of the pancreas, aorta and inferior vena cava have been removed.

the porta hepatis and then turns downwards to join the common hepatic duct. The undersurface of the gall bladder is covered by peritoneum continuous with that surrounding the liver. The body is usually related to the proximal part of the duodenum and the fundus often makes contact with the transverse colon. Inflammation associated with gallstones can progress to ulceration, allowing stones to pass from the gall bladder into the duodenum or colon.

The arterial supply to the gall bladder is provided by the cystic artery, which usually springs from the right branch of the proper hepatic artery (Fig. 4.59), though its origin is variable. The cystic vein normally drains into the portal vein or its right branch.

Hepatic blood vessels

Blood is conveyed to the liver by the proper hepatic artery and the portal vein, both of which enter via the porta hepatis. Blood is drained by the hepatic veins embedded in the organ, which enter the anterior aspect of the inferior vena cava immediately below the diaphragm (Fig. 4.58). The common hepatic artery, a branch of the coeliac trunk (Fig. 4.62), runs retroperitoneally downwards and to the right to the superior border of the first part of the duodenum (Fig. 4.59). Here, the common hepatic artery gives off the right gastric and gastroduodenal arteries and continues as the proper hepatic artery. The right gastric artery arises


S
L
R
I
Portal vein
Caudate lobe
Bare area
Hepatic ducts
Impression for right kidney
Proper hepatic artery
Round ligament and fissure
Quadrate lobe
Gall bladder

Fig. 4.61 Inferior view of liver and gall bladder showing porta hepatis and visceral surface.


Bile duct
Right and left branches of proper hepatic artery
Portal vein
Left gastric artery and vein
S
R
L
I
Cystic duct
Right gastric artery
Gastro-duodenal artery
Pancreas
Stomach

Fig. 4.62 Course and branches of the common hepatic artery. The lesser omentum has been removed.

above the first part of the duodenum and runs to the left within the lesser omentum, supplying the lesser curvature of the stomach. The larger gastroduodenal artery descends behind the first part of the duodenum alongside the bile duct. Its terminal branches are the superior pancreaticoduodenal artery (Fig. 4.52) and the right gastro-omental artery (Fig. 4.43). The proper hepatic artery ascends in the free border of the lesser omentum on the left of the bile duct and anterior to the portal vein. Near the porta hepatis, it divides into right and left branches to enter the liver with corresponding branches of the portal vein. The left branches of the artery and vein are distributed to the left quadrate and most of the caudate lobes. The right branches supply the remainder of the liver. The proper hepatic artery also supplies the gall bladder via the cystic artery (Fig. 4.59). Within the liver are several segments each with its own arterial supply. During liver and gall bladder surgery, the proper hepatic artery can be compressed, within the free border of the lesser omentum, to stem arterial bleeding.

Jejunum and Ileum

The jejunum and ileum constitute the major part of the small intestine. The jejunum commences at the duodenojejunal flexure and the ileum terminates at the ileocaecal junction. Between these two sites, the small intestine is about 5 or 6 m long and forms numerous loops that fill most of the infracolic compartment of the abdomen (Figs 4.41 & 4.63). By convention, the proximal two-fifths are called the jejunum and the remainder the ileum. However, no precise anatomical feature marks the junction between the two, there being a gradual morphological transition along the whole length of the small intestine.

As the small intestine is traced distally, there is a gradual reduction in the size of the lumen. The terminal ileum is the narrowest region and it is here that gallstones and foreign bodies may lodge. Mucosal folds (plicae circulares) are numerous in the proximal jejunum (Fig. 4.64) but diminish in both size and number so that in the distal ileum they are often absent. This difference in mucosal structure can be detected by palpation and may also be apparent on radiographs. The distribution of lymphoid tissue in the jejunum is diffuse, whereas in the mucosa of the ileum it is arranged in discrete clumps (Peyer's patches).

Ileal diverticulum

Within a metre of the ileocaecal junction, the ileum occasionally possesses a diverticulum on its antimesenteric border. This diverticulum (Meckel's diverticulum) is the embryological remnant of the vitellointestinal duct and may be connected to the umbilicus. Inflammation of the diverticulum can give rise to clinical features similar to those of appendicitis. Sometimes the tip of the diverticulum remains connected to the umbilicus by a fibrous cord around which loops of intestine may become twisted giving rise to intestinal obstruction.



Fig. 4.63 Jejunum and ileum. The greater omentum has been reflected upwards.

Mesentery

The jejunum and ileum are contained within the free border of the mesentery of the small intestine. This fan-shaped structure has a root about 15 cm long attached to the posterior abdominal wall between the duodenojejunal flexure and the ileocaecal junction (Fig. 4.65). The mesentery divides the infracolic compartment of the peritoneal cavity into right and left infracolic spaces. Between its two peritoneal layers, the mesentery contains a quantity of fat, which is particularly abundant in the ileal portion. Embedded in this fat are numerous jejunal and ileal blood vessels (see below), lymphatic vessels and nodes, and autonomic nerves.

Location and relations

Because they are suspended from the mesentery, the jejunum and ileum possess considerable mobility and their coils can change position relative to adjacent organs. The jejunum usually occupies the central part of the abdomen, especially the umbilical region, while the ileum lies at a lower level, mostly in the hypogastrium and the pelvic cavity (Fig. 4.63). The terminal ileum usually ascends from the pelvis into the right iliac fossa to reach the medial aspect of the caecum (Fig. 4.69). The principal anterior relations of the jejunum and ileum are the greater omentum, the transverse colon and its mesocolon, and the anterior abdominal


Peritoneum of mesentery (cut)
Jejunal arteries and veins
Plicae circulares
Ileal arteries and veins
Mucosal folds
Peritoneum of mesentery (cut)

Fig. 4.64 Segments of jejunum (upper) and ileum (lower) opened to show their mucosae. Their mesenteries have been dissected to reveal the blood vessels.

wall. Posteriorly, the coils of small intestine overlie retroperitoneal structures on the posterior wall of the abdomen and pelvis and may also overlap the ascending, descending and sigmoid parts of the colon. Within the pelvis, loops of ileum may lie in contact with pelvic organs, such as the rectum and urinary bladder and, in the female, with the uterus and its appendages.

Superior mesenteric vessels

The superior mesenteric artery supplies the intestine from the descending duodenum to the splenic flexure of the colon. The artery is an anterior branch of the abdominal aorta (Fig. 4.89) at the level of the first lumbar vertebra, just below the coeliac trunk. It descends in front of the left renal vein (Fig. 4.91) and behind the neck of the pancreas. Inclining to the right, the artery continues downwards in front of the uncinate process of the pancreas and across the horizontal duodenum to enter the root of the mesentery (Fig. 4.66).

The superior mesenteric artery gives rise to middle colic and inferior pancreaticoduodenal branches before gaining the mesentery. As it descends in the root of the mesentery, it furnishes the right colic artery, which passes behind the peritoneum to supply the ascending colon. A further branch, also retroperitoneal, is the ileocolic artery, which inclines downwards and to the right towards the caecum. The superior mesenteric artery also gives numerous branches to the jejunum and ileum. Within the mesentery these jejunal and ileal arteries anastomose, producing a series



Fig. 4.65 Mesentery of small intestine. All of the jejunum and most of the ileum have been excised and the cut edge of mesentery trimmed to reveal the jejunal and ileal vessels.


Transverse colon (displaced)
Middle colic artery
Right colic artery
Pancreas
Marginal artery
Ileocolic artery
Ascending colon
Caecal arteries
Ileum (cut)
Caecum
S
R
L
I
Transverse mesocolon (cut and displaced)
Superior mesenteric vein
Jejunal arteries (cut)
Mesentery of small intestine (cut)
Ileal arteries (cut)
Meso-appendix and appendix
Sigmoid colon

Fig. 4.66 Superior mesenteric artery and its branches. The jejunal and ileal veins have been removed.


Lymph node
Arterial arcades
Peritoneum of mesentery (cut)
Ileum

Fig. 4.67 Ileal arteries and their arcades in the mesentery of the ileum.

of arterial arcades which are more profuse in the ileal part of the mesentery (Fig. 4.67). The superior mesenteric artery terminates at the upper border of the terminal ileum, where it anastomoses with the lower branch of the ileocolic artery and the distal ileal arteries. If the superior mesenteric artery becomes narrowed by disease, most of the small intestine and part of the large intestine may become ischaemic or necrotic.

The superior mesenteric vein begins above the terminal ileum and ascends in the root of the mesentery. It lies on the right of the superior mesenteric artery and its tributaries correspond to the branches of the artery. The vein terminates behind the neck of the pancreas by joining the splenic vein to form the portal vein. Close to its termination, it may be joined by the inferior mesenteric vein (Fig. 4.78), but this more commonly enters the splenic vein.

Caecum, Appendix and Colon

The large intestine is approximately 1.5 m long and comprises the caecum, appendix, colon, rectum and anal canal. The caecum and appendix lie in the right iliac fossa, while the colon runs a circuitous course (Figs 4.68–4.70) before descending into the pelvic cavity to become continuous with the rectum. Descriptions of the rectum and anal canal are given in Chapter 5.

The lumen of the intestine is relatively wide in the caecum and ascending colon but narrows gradually as the colon is traced towards the rectum.

The outer longitudinal muscle coat of the caecum and colon is thickened to form three longitudinal bands, the taeniae coli


S
R
L
I
Right colic flexure
Ascending colon
Ileum (cut)
Appendix
Caecum
Transverse colon (elevated)
Descending colon
Paracolic gutter
Sigmoid colon

Fig. 4.68 Caecum, appendix and colon after removal of the greater omentum and most of the small intestine. The transverse colon has been raised.


Right colic flexure
Left colic flexure
S
R
L
I
Descending colon
Caecum
Ileum
Transverse colon
Descending colon
Sigmoid colon

Fig. 4.69 Barium enema radiograph. Most of the colon is gas filled, but barium coats its mucosa and has passed proximally into the ileum.

(Fig. 4.71). Bulges (haustrations) of the gut wall between the taeniae correspond with sacculations on the mucosal surface. The peritoneal surface of the colon (but not of the appendix or caecum) is characterized by numerous fat-filled tags, the omental appendices (appendices epiploicae).

Caecum

The ileum terminates by opening into the large intestine at a slit-like or oval aperture, the ileal orifice (ileocaecal valve) (Fig. 4.72). The caecum is the blind-ending portion of the large intestine below the level of this orifice. The caecum and ascending colon are in direct continuity and the three taeniae coli descend along the outer surface of the caecum and converge on its posteromedial aspect at the root of the appendix.

The caecum usually lies in the right iliac fossa above the lateral half of the inguinal ligament (Fig. 4.73). Anteriorly, it is related to the abdominal wall, the greater omentum and coils of ileum; the iliacus and psoas muscles lie posteriorly. The caecum may lie free


S
R
L
I
Descending colon
Transverse colon
Ileum
Caecum

Fig. 4.70 Barium enema radiograph of a different subject, to show variation in bowel anatomy. The transverse colon is more dependent and coils of sigmoid colon overlap each other.


S
la
m
I
Caecum (displaced)
Taeniae coli
Terminal ileum (cut)
Mesoappendix
Sigmoid colon
Retrocaecal recesses
Peritoneal folds
Root of appendix
Omental appendices

Fig. 4.71 Base of the appendix and retrocaecal folds and recesses revealed by pulling the caecum forwards.

in the iliac fossa, completely surrounded by peritoneum. Alternatively, it may be attached to the iliac fossa by peritoneal folds forming a retrocaecal fossa (Fig. 4.71). Rarely, the caecum is entirely retroperitoneal. On the medial side of the caecum, adjacent to the terminal ileum, small peritoneal folds may enclose one or more ileocaecal recesses.

Appendix

The worm-like appendix is attached to the posteromedial wall of the caecum, where the taeniae coli converge (Fig. 4.71). It is a thick-walled tube with a narrow lumen and, although variable in length, usually measures approximately 10 cm. The surface marking of the root of the appendix is relatively constant, lying one-third of the distance from the anterior superior iliac spine to the umbilicus (Fig. 4.2).

The appendix usually possesses a mesentery, the mesoappendix (Fig. 4.72), which is attached to the mesentery of the ileum and confers upon the appendix a degree of mobility. Although it frequently lies behind the caecum (Fig. 4.74), in front of the iliacus or psoas muscles, it occasionally descends into the pelvis where its tip may lie adjacent to the bladder, the right ureter and, in the female, the ovary or uterine tube (Fig. 4.73). Rarely, the appendix lies anterior or posterior to the terminal ileum. It is a common site of infection (appendicitis), which may spread to adjacent structures. Usually, the pain of appendicitis arises initially from the gut wall and is periumbilical. When the inflammation spreads to the parietal peritoneum the pain becomes localized to the right iliac region.

Colon

The colon consists of ascending, transverse, descending and sigmoid parts (Fig. 4.68). The ascending and descending parts are usually retroperitoneal, while the transverse and sigmoid parts are suspended by mesenteries. The colon possesses two acute


S
la
m
I
Ascending colon
Caecal artery
Ileocolic artery
Mesoappendix
Ileal orifice
Appendicular artery
Appendix
Sigmoid colon

Fig. 4.72 Ileal orifice revealed by removal of the anterior wall of the caecum. The mesoappendix has been dissected to show the appendicular artery.


S
la
m
I
Caecum
Appendix and mesoappendix
Inguinal ligament
Mesentery of small intestine (cut)
Terminal ileum (cut)
Sigmoid colon
Right uterine tube

Fig. 4.73 After removal of most of the small intestine, this appendix can be seen descending over the pelvic brim.

angulations, the right (hepatic) and left (splenic) flexures (Fig. 4.69).

The ascending colon begins at the level of the ileal orifice and runs vertically upwards. At the right colic flexure under the right lobe of the liver, it becomes continuous with the transverse colon. Anterior to the ascending colon lie the abdominal wall, loops of ileum and often the greater omentum. Its posterior relations include the iliacus, transversus abdominis, quadratus lumborum and the right kidney.

The transverse colon extends from the right to the left colic flexure and is suspended by the transverse mesocolon. Typically, its middle portion hangs downwards and crosses the umbilical region (Figs 4.69 & 4.70). At the left colic flexure just below the splenic hilum, it turns inferiorly to become the descending colon. From right to left, the superior relations of the transverse colon include the liver and gall bladder and the greater curvature of the stomach. Posteriorly lie the descending duodenum, the pancreas, loops of small intestine and the spleen. Anteriorly lie the greater omentum and the abdominal wall. The greater omentum attaches to both the transverse colon and the greater curvature of the stomach (p. 160).

The descending colon runs from the left flexure to the left iliac fossa and turns medially at the pelvic brim to continue as the sigmoid colon (Figs 4.68 & 4.76). The upper part of the descending colon is covered anteriorly by coils of jejunum, while the lower part usually makes contact with the abdominal wall, through which it is often palpable. Its posterior relations include the left kidney and the psoas, quadratus lumborum and iliacus muscles.

The sigmoid (pelvic) colon begins at the pelvic brim and terminates in front of the third sacral vertebra by joining the rectum. The sigmoid colon varies in length and is mobile on its mesentery, the sigmoid mesocolon. Its proximal portion usually runs to the right across the lower abdomen (Fig. 4.68) and is related superiorly to loops of small intestine. The remainder of the sigmoid colon lies in the pelvic cavity in contact with the upper surfaces of the pelvic organs. A long pelvic mesocolon can provide mobility so that the colon may twist (volvulus), causing ischaemia or colonic obstruction. Pockets of evaginated colonic mucosa are common and may become infected (diverticulitis).

Blood supply

The blood supply of the caecum, appendix, ascending colon and most of the transverse colon is provided by the superior mesenteric vessels. The remainder of the colon is supplied by the inferior mesenteric vessels.

Branches of superior mesenteric vessels

The origin and course of the superior mesenteric artery are described on p. 177. Its branches to the large intestine vary considerably but usually include the middle colic, right colic and ileocolic arteries (Fig. 4.75).

The middle colic artery enters the transverse mesocolon and divides into right and left branches, which supply the proximal two-thirds of the transverse colon. The right colic artery reaches the ascending colon and divides into ascending and descending branches, which supply the organ. The ileocolic artery has anterior and posterior caecal branches and also supplies the ascending colon and terminal ileum. The appendicular branch (Fig. 4.72) descends behind the terminal ileum, enters the mesoappendix and runs near its free border to the tip of the appendix. The arteries supplying the caecum and colon anastomose, often forming a continuous marginal artery (Fig. 4.75).

Veins corresponding to the branches of the superior mesenteric artery drain into the superior mesenteric vein (Figs 4.75 & 4.78).

Inferior mesenteric vessels

The inferior mesenteric artery arises from the anterior aspect of the abdominal aorta 3 cm or 4 cm above the bifurcation, often overlapped by the horizontal duodenum (Fig. 4.76). The artery runs retroperitoneally downwards and to the left to reach the pelvic brim. Here it crosses the common iliac vessels and continues into the pelvis as the superior rectal artery (p. 218).

The first branch of the inferior mesenteric artery, the left colic artery, runs to the left and gives rise to ascending and descending branches. The former supplies the distal third of the transverse colon and the left colic flexure. The descending branch supplies the descending colon and the commencement of the sigmoid colon. The inferior mesenteric artery gives rise to several sigmoid arteries which reach the sigmoid colon via the mesocolon.

The branches of the inferior mesenteric artery are accompanied by tributaries of the inferior mesenteric vein (Fig. 4.76). The course and termination of this vessel are described with the portal venous system.



Fig. 4.74 Posterior aspect of the caecum to show a retrocaecal appendix.




Transverse colon (displaced)
Right colic artery and vein
Marginal artery
Ascending colon
Terminal ileum (cut)
Caecum
Transverse mesocolon (cut)
Middle colic artery and vein
Mesentery of small intestine (cut)
Superior mesenteric artery and vein
Duodenum
Ileocolic artery and vein
S
R
L
I

Fig. 4.75 Blood supply to the caecum, ascending and transverse colon. The transverse mesocolon and the mesentery of the small intestine have been dissected to reveal the ileocolic, right colic and middle colic vessels.




Superior mesenteric vessels (cut)
Inferior mesenteric vein and artery
S
R
L
I
Left ureter
Sigmoid vessels
Mesocolon (cut)
Spleen
Left colic flexure (cut)
Inferior pole of left kidney
Ascending and descending branches of left colic artery
Descending colon
Left gonadal vessels

Fig. 4.76 Blood supply to the left colic flexure, descending colon and sigmoid colon. Removal of peritoneum from the posterior abdominal wall to the left of the aorta displays the inferior mesenteric vessels.

Portal Venous System

The hepatic portal venous system drains blood from most of the alimentary tract (including the abdominal oesophagus, stomach, small and large intestines), pancreas and spleen. Blood from these organs is drained by the superior mesenteric and splenic veins which unite to form the portal vein (Fig. 4.77). This large vein approaches the porta hepatis with the proper hepatic artery, and branches of both vessels enter the liver and further subdivide. The liver is a common site of secondary infection or cancer because blood is conveyed to it from so many other organs. After traversing the liver, blood from both sources is drained by the hepatic veins, which enter the inferior vena cava (Fig. 4.92).

Tributaries

The superior mesenteric vein (Fig. 4.78) receives blood from most of the small intestine and the proximal half of the large intestine. It drains the duodenum distal to the major papilla, the jejunum and ileum, the caecum and appendix, and the ascending and most of the transverse colon. The vein accompanies the superior mesenteric artery within the root of the mesentery and its tributaries generally correspond to the branches of the artery.

The splenic vein (Fig. 4.78) drains the spleen and parts of the pancreas and stomach. It arises at the hilum of the spleen and runs to the right in the splenorenal ligament behind the tail of the pancreas. The vein continues behind the body of the pancreas and


Liver (cut)
Hepatic artery
Portal vein
Bile duct
Duodenum (cut)
Spleen
Gastroduodenal artery (cut)
Superior mesenteric vein and artery (cut)
Splenic vein
Inferior mesenteric vein
S
R
L
I

Fig. 4.77 Portal and splenic veins. Most of the pancreas has been removed and the superior duodenum turned aside.

usually receives the inferior mesenteric vein and other tributaries corresponding to the branches of the splenic artery.

The inferior mesenteric vein drains the upper part of the anal canal, the rectum, the sigmoid and descending parts of the colon and the distal part of the transverse colon. The vein initially accompanies the corresponding artery but in the latter part of its course, it ascends the posterior abdominal wall independently, passing to the left of the duodenojejunal junction. The vessel usually terminates by joining the splenic vein behind the body of the pancreas (Fig. 4.77), but it may enter the superior mesenteric vein (Fig. 4.78).

Portal vein

The portal vein is formed behind the neck of the pancreas by the union of the superior mesenteric and splenic veins (Fig. 4.77). It runs upwards and to the right behind the gastroduodenal artery and the first part of the duodenum. The vein then enters the free border of the lesser omentum accompanied anteriorly by the bile duct and the proper hepatic artery (Fig. 4.44). Near the porta hepatis, the vein divides into left and right branches, which enter the liver. Several small veins enter the portal vein directly, including the left and right gastric veins and the cystic vein.

Portacaval anastomoses

There are numerous anastomoses between the tributaries of the portal venous system and those of the systemic venous system. In health, these portacaval anastomoses are microscopic; but if there is obstruction of blood flow through the portal vein or liver, they may dilate and give rise to characteristic clinical features. For example, in the wall of the lowest part of the oesophagus, veins draining into the left gastric vein communicate with tributaries of the azygos venous system. Portal vein obstruction can cause gross swelling of these oesophageal veins (oesophageal varices), which may bleed profusely.

Similarly, paraumbilical veins accompanying the round ligament of the liver communicate with the portal vein at the porta hepatis and with veins of the anterior abdominal wall around the umbilicus. Portal vein obstruction may result in dilatation of the subcutaneous veins of the abdominal wall. Other sites of portacaval anastomoses include the anal canal and retroperitoneal parts of the intestines.



Fig. 4.78 Tributaries of the portal vein. In this specimen the inferior mesenteric vein joins the superior mesenteric vein.

Kidneys and Suprarenal Glands

Kidneys

The two kidneys lie behind the peritoneum on either side of the upper lumbar vertebrae (Fig. 4.79). They are embedded in fat in the paravertebral gutters of the posterior abdominal wall and are placed obliquely, with their anterior surfaces directed slightly laterally (Fig. 4.80). The left kidney usually lies at a higher level than the right.

Each kidney is bean-shaped, flattened anteroposteriorly and approximately 11 cm long. The anterior and posterior surfaces are gently convex and the superior and inferior poles are rounded. The lateral border is convex, while the indented medial border bears an aperture, the hilum (Figs 4.81 & 4.82), which is traversed by the renal pelvis or ureter, the renal vessels, lymphatics and


S
R
L
I
Right renal vein
Supra-renal
Superior mesentreic artery (cut)
Left renal vein
Kidney
Psoas major
Inferior vena cava
Left gonadal vein
Ureter
First lumbar nerve
Quadratus lumborum

Fig. 4.79 Kidneys, suprarenal glands and some of the vessels associated with them.


A
R
L
P
Liver
Descending duodenum
Inferior vena cava
Aorta
Left renal vein
Right kidney
Psoas major
Quadratus lumborum
Left kidney

Fig. 4.80 Transverse section at the level of the first lumbar vertebra showing some relations of the kidneys. The spleen is not evident in this specimen. Inferior aspect. (Compare Fig. 4.109.)

autonomic nerves. The hilum leads into a cavity within the kidney, the renal sinus, which is occupied by the calices and renal pelvis (Fig. 4.83), the renal blood vessels and a quantity of fat.

Covered by a thin capsule, the kidney comprises an outer cortex and an inner medulla. The medulla contains numerous pyramids, the apices of which project into the renal sinus as the renal papillae. Urine discharged from the papillae is collected by about 10 trumpet-shaped chambers, the minor calices (Fig. 4.83), which unite to form two or three major calices. These fuse into the single, funnel-shaped renal pelvis, which lies posterior to most of the vessels and is continuous with the ureter. Either of the kidneys and ureters may be duplicated and the two embryonic organs may fuse resulting in a 'horseshoe kidney'.

Perirenal tissues

Each kidney is surrounded by a layer of perinephric (perirenal) fat enveloped in a thin sheet of connective tissue, the renal fascia (Fig. 4.84). This fascia also encloses the suprarenal gland and the proximal part of the ureter. From the inferior pole of the kidney, the renal fascia tapers downwards into the iliac fossa. Around the fascia is a further layer of fat (paranephric or pararenal fat) lying against the posterior abdominal muscles and covered anteriorly by the peritoneum. The perirenal fascia can impede the spread of infection or cancer.

Relations of kidneys

The right and left kidneys have similar posterior relations (Fig. 4.80). The superior poles lie against the diaphragm and the


Superior pole
Polar artery (cut)
Renal artery (cut)
Renal vein (cut)
Ureter
Inferior pole
S
A
P
I

Fig. 4.81 Medial aspect of the right kidney showing the renal vessels passing through the hilum.


NSPIRATION
Minor calix
Major calix
Renal pelvis
Ureter
S
R
L
I

Fig. 4.82 Intravenous urogram showing detail of the pelvicaliceal system.


Minor calix
Major calix
Cortex
Medulla
Renal pelvis
Pelviureteric region
Ureter (cut)
S
m
la
I

Fig. 4.83 Right kidney dissected from behind to show the renal pelvis and calices.

twelfth ribs, below which run the subcostal nerves and vessels. On the left the upper pole is also related, through the diaphragm, to the pleura and eleventh rib. The medial border of each kidney overlaps psoas major (Fig. 4.79), while the inferolateral portion is related to quadratus lumborum and transversus abdominis and to the first lumbar nerve.

The anterior relations of the kidneys are asymmetric. On the right, from above downwards, they include the bare area of the liver, the second part of the duodenum (Fig. 4.80), the right flexure of the colon and coils of jejunum. The medial border of the right kidney is related to the inferior vena cava, the renal vessels and the upper part of the ureter (Fig. 4.84).


Hepatic veins (cut)
Suprarenal gland
Renal fascia (cut)
Ureter
Perinephric fat (cut)
S
R
L
I
Inferior vena cava
Hepatic artery (cut)
Renal vein
Branches of renal artery
Psoas major
Right gonadal vein

Fig. 4.84 Right kidney and suprarenal gland seen within the renal fascia and perinephric fat, part of which has been removed.

On the left, from above downwards, the anterior relations include the stomach and spleen, the splenic vessels, the tail of the pancreas, the left colic flexure and coils of jejunum. The medial border relates to the suprarenal gland, the renal and suprarenal vessels, the left gonadal vein and the proximal part of the ureter (Fig. 4.87).

Renal vessels

At the level of the first lumbar vertebra the aorta usually supplies one renal artery to each kidney (Fig. 4.85). Each artery lies behind the corresponding vein, and the artery on the right crosses behind the inferior vena cava. However, there are often supernumerary (anomalous, aberrant or accessory) renal arteries arising from the aorta above or below the typical vessel. Regardless of its origin, each renal artery divides as it approaches the kidney and all the branches usually traverse the hilum. However, a polar artery may occasionally be found entering the medial border of the organ above or below the hilum (Figs 4.81 & 4.87). Stenosis of a renal artery can lead to systemic arterial hypertension.

Several veins unite near the renal hilum, anterior to the arteries, forming the renal vein. On the right, the vein runs a short course to terminate in the inferior vena cava. The left renal vein is longer and usually receives the suprarenal and gonadal veins before passing in front of the aorta to reach the inferior vena cava (Fig. 4.79). Because of its termination, the left gonadal vein may become dilated if the renal vein is obstructed. In the male, this can lead to swelling of the pampiniform plexus within the scrotum (varicocele; p. 150).


Right suprarenal artery
Renal vein (cut)
Inferior vena cava (cut)
S
R
L
I
Superior mesenteric artery (cut)
Left suprarenal vein (cut)
Left renal artery and vein (cut)
Gonadal arteries

Fig. 4.85 Renal arteries exposed by removal of the renal veins and a portion of the inferior vena cava.


Hepatic veins (cut)
Inferior vena cava (cut)
Right inferior phrenic artery
Suprarenal gland
Suprarenal arteries
Right crus of diaphragm
Coeliac trunk (cut)
Superior mesenteric artery (cut)
Renal artery
Inferior vena cava (cut)
S
R
L
I

Fig. 4.86 Right suprarenal gland and its arteries exposed by removal of the renal vein and a portion of the inferior vena cava.


Inferior phrenic vein (cut)
S
R
L
I
Suprarenal vein
Suprarenal gland
Polar artery
Suprarenal arteries (from aorta)
Left crus of diaphragm
Psoas major
Sympathetic trunk

Fig. 4.87 Left suprarenal gland and its vessels. The renal vein and inferior tip of the gland have been excised to reveal the suprarenal arteries.

Suprarenal glands

The suprarenal glands lie adjacent to the superior poles of the kidneys, embedded in the perinephric fat. On the right, the gland is tetrahedral and occupies the angle between the superior pole of the kidney and the inferior vena cava (Fig. 4.86). The left gland is crescentic and is applied to the medial border of the kidney above the hilum (Fig. 4.87).

The blood supply to the suprarenal glands is provided by branches of the renal and inferior phrenic arteries and the aorta. The right suprarenal vein is very short and enters the inferior vena cava directly while that on the left descends to enter the left renal vein.

The medulla of each suprarenal gland is richly innervated by preganglionic sympathetic nerves from the adjacent part of the sympathetic trunk.

Abdominal parts of ureters

From the pelviureteric region, each ureter descends through the retroperitoneal tissues of the posterior abdominal wall as far as the pelvic brim. Here it crosses in front of the external iliac vessels and continues down the lateral wall of the pelvis (p. 222). Within the abdomen, the ureter lies on psoas major (Fig. 4.84), behind which are the lumbar transverse processes (Fig. 4.82).

The right ureter commences behind the descending duodenum and is crossed by the root of the mesentery, the gonadal vessels and branches of the superior mesenteric artery and accompanying veins. This ureter is also related to coils of small intestine, and sometimes to the caecum and appendix. The left ureter is covered initially by the pancreas and is subsequently crossed by the gonadal vessels, branches of the inferior mesenteric artery and vein (Fig. 4.76) and coils of small intestine and sigmoid colon. At the pelvic brim, it passes behind the root of the sigmoid mesocolon.

Renal calculi may impact where the ureters narrow at the pelviureteric junction, near the pelvic brim and at the entrance to the bladder.

The blood supply to the abdominal part of the ureter is derived from branches of the renal artery, supplemented by minute peritoneal vessels.

Abdominal Aorta

The aorta enters the abdomen behind the median arcuate ligament of the diaphragm at the level of the twelfth thoracic vertebra. It descends behind the peritoneum, inclining slightly to the left of the midline to its bifurcation in front of the fourth lumbar vertebra (Fig. 4.89). Throughout its course, the abdominal aorta is accompanied by lymph vessels and nodes and is surrounded by a plexus of autonomic nerves (pp 196–199).

Posterior to the aorta lie the left lumbar veins, the anterior longitudinal ligament and the lumbar vertebral bodies. Anterior relations, from above downwards, include the body of the pancreas, the splenic and left renal veins, the horizontal duodenum, the root of the mesentery and coils of small intestine.

To the right of the aorta lie the right crus of the diaphragm and the inferior vena cava (Fig. 4.89). On the left are the left diaphragmatic crus, suprarenal gland and kidney.

Degenerative arterial disease often affects the abdominal aorta, which may become narrowed or may dilate (abdominal aortic aneurysm) and rupture causing fatal internal haemorrhage.

Visceral branches

Three arteries arise from the anterior aspect of the aorta to supply the alimentary organs, while three pairs of lateral branches pass to the suprarenals, kidneys and gonads, respectively.

The coeliac and superior mesenteric arteries arise at the levels of the twelfth thoracic and first lumbar vertebrae, respectively, while the smaller inferior mesenteric artery takes origin at the level of the third lumbar vertebra (Fig. 4.89).

Details of the course and distribution of each of these arteries are given on pp 161, 177, 182.



Fig. 4.88 Right gonadal vessels within the abdomen. Several lumbar vessels are also seen.

The suprarenal branches of the aorta (Fig. 4.89) are small and variable and are often supplemented by branches from the inferior phrenic and renal arteries (Figs 4.86 & 4.92). The renal arteries usually arise at the level of the first lumbar vertebra but variations are common (p. 189).

The long and slender gonadal (testicular or ovarian) arteries usually arise from the aorta just below the renal arteries (Fig. 4.89). The gonadal artery on the right crosses in front of the inferior vena cava, and the arteries of both sides incline downwards and laterally through the retroperitoneal tissues on the psoas major muscles (Fig. 4.88). Each artery is accompanied by one or more gonadal veins and crosses anterior to the ureters but posterior to blood vessels supplying the intestines. Inferiorly, the testicular artery follows the psoas major round the pelvic brim and enters the deep inguinal ring (Fig. 4.23). The ovarian artery crosses the external iliac vessels and pelvic brim to reach the ovary within the pelvis (p. 221).

Parietal branches

These vessels supply the diaphragm and the posterior walls of the abdomen and pelvis. The paired inferior phrenic arteries are the first branches of the aorta within the abdomen (Figs 4.86, 4.89 & 4.92) and often furnish small branches to the suprarenal glands before arching upwards and laterally on the abdominal surface of the diaphragm.

Four pairs of lumbar arteries usually arise from the posterolateral aspect of the aorta and supply the posterior abdominal wall (Figs 4.88, 4.90 & 4.103). The arteries on the right cross behind the inferior vena cava to curve round the side of the corresponding vertebral body deep to psoas major.

A single small vessel, the median sacral artery, arises from the back of the aortic bifurcation and descends behind the left common iliac vein to reach the anterior surface of the sacrum (Fig. 4.90).


Renal vein (cut)
Median arcuate ligament
Right suprarenal artery
Coeliac trunk (cut)
Inferior phrenic artery
S
R
L
I
Superior mesenteric artery (cut)
Renal artery and suprarenal branch
Psoas major
Testicular arteries
Lumbar artery
Inferior mesenteric artery
Inferior vena cava and lumbar vein
Bifurcation of aorta
Right and left common iliac veins
Right common iliac artery

Fig. 4.89 Abdominal aorta and its branches, seen after removal of the renal veins and part of the inferior vena cava.

Iliac Vessels

Common and external iliac vessels

The aortic bifurcation gives rise to the two common iliac arteries, which incline downwards and laterally on the medial aspects of psoas major (Fig. 4.90). The vessels terminate in front of the sacroiliac joints by dividing into internal and external iliac arteries. The right common iliac artery crosses in front of the left common iliac vein, while that on the left is crossed by the inferior mesenteric vessels. The ureter crosses either the lower end of the common iliac artery or the commencement of its external branch (Fig. 4.90). The internal iliac artery begins at the bifurcation of the common iliac artery and descends on the lateral wall of the pelvis (p. 238).

The external iliac artery curves round the pelvic brim (Fig. 4.90) and, passing behind the inguinal ligament, enters the thigh as the femoral artery (Fig. 6.19). The external iliac artery is accompanied on its medial side by the corresponding vein and posterolaterally by psoas major. The external iliac vessels are crossed by the ovarian vessels in the female and by the ductus deferens in the male. Near the inguinal ligament the artery gives off the inferior epigastric artery, which runs upwards and medially, medial to the deep inguinal ring (Figs 4.18 & 4.23).

Each external iliac vein begins behind the inguinal ligament as the continuation of the femoral vein (Fig. 4.90). It receives the inferior epigastric vein, ascends on the medial side of the corresponding artery and joins the internal iliac vein (p. 145) to form the common iliac vein. The two common iliac veins continue upwards and medially, passing behind the right common iliac artery, by which they may be compressed, before uniting to form the inferior vena cava.


Inferior vena cava
Lumbar artery
Common iliac artery
Ureter
Median sacral vessels
Tendon of psoas minor
External iliac artery and vein
Vas deferens
S
R
L
I
Inferior mesenteric artery
Sympathetic trunk
Left common iliac vein
Psoas major
Genitofemoral nerve
Testicular vessels
Internal iliac artery
Ureter

Fig. 4.90 Male pelvis and lower abdomen showing the common and external iliac vessels and some of their relations.

Inferior Vena Cava

The inferior vena cava is formed at the level of the fifth lumbar vertebra, a little to the right of the midline (Fig. 4.91). It ascends the posterior abdominal wall and pierces the central tendon of the diaphragm to enter the thorax at the level of the eighth thoracic vertebra (Fig. 4.92).

Behind the inferior vena cava lie the lumbar vertebral bodies, the anterior longitudinal ligament, the right sympathetic chain and right psoas major muscle. In addition, the right renal and right lumbar arteries cross behind the vena cava (Figs 4.88 & 4.89) and most of the right suprarenal gland lies posterior to the vessel (Fig. 4.92).

Near its commencement, the inferior vena cava is covered anteriorly by peritoneum and coils of small intestine. Superiorly, it is crossed by the root of the mesentery, the right gonadal artery (Fig. 4.88) and the third part of the duodenum (Fig. 4.52). It continues behind the omental foramen (Fig. 4.38) and then grooves the posterior surface of the liver (Fig. 4.58) before piercing the diaphragm.


Hepatic veins (cut)
Hepatic artery (cut)
Superior mesenteric artery (cut)
Right renal vein
Right gonadal vein
Ureter
Psoas major
Left common iliac vein
Right crus of diaphragm
Left renal and suprarenal veins
Lymph nodes
Left gonadal vein
Left gonadal arteries
S
R
L
I

Fig. 4.91 Course and principal tributaries of the inferior vena cava.

To the right of the vena cava lie the gonadal vessels, the ureter, the kidney and renal vessels (Fig. 4.91) and the right lobe of the liver. To the left lie the aorta with its associated lymph nodes, the right crus of the diaphragm and the caudate lobe of the liver.

Tributaries

The venous drainage of the suprarenal glands, the kidneys and the gonads is asymmetric. On the right, each of these organs is drained by a vein that passes directly into the inferior vena cava (Figs 4.91 & 4.92) but on the left, the renal vein receives the suprarenal and gonadal veins before crossing in front of the aorta to reach the vena cava. Immediately before its passage through the diaphragm the inferior vena cava receives several large hepatic veins (Fig. 4.92).

The parietal tributaries of the inferior vena cava drain the diaphragm and the posterior pelvic and abdominal walls. The lumbar and median sacral veins (Figs 4.88 & 4.90) accompany the corresponding arteries, the upper lumbar veins often communicating with the renal, suprarenal, azygos and hemiazygos veins. Two or more inferior phrenic veins drain the undersurface of the diaphragm (Fig. 4.92).


Right inferior phrenic veins
Hepatic veins (cut)
Inferior vena cava (cut)
Left inferior phrenic vein and artery
S
R
L
I
Left gastric artery
Right inferior phrenic artery
Right suprarenal vein

Fig. 4.92 Upper part of inferior vena cava showing its tributaries. In this specimen, the left inferior phrenic artery arises from the left gastric artery.

Lymphatics of the Abdomen

The lymphatic vessels and nodes of the abdomen drain the abdominal and pelvic organs as well as the pelvic walls and the lower part of the abdominal wall. (The upper part of the abdominal wall is drained by the internal thoracic and axillary nodes; p. 145.) In addition, the abdominal lymphatics receive lymph from the lower limb, the gonads and the perineum.




Ureter
Testicular vein
External iliac lymph nodes and lymphatic vessel
External iliac artery and vein
Common iliac node(s)
Right and left common iliac arteries
Peritoneum (cut)
S
R
L
I

Fig. 4.93 The common and external iliac arteries are accompanied by a chain of lymphatic vessels and nodes.




Aortic lymph nodes
Inferior vena cava
Testicular vein
Common iliac nodes
Left gastric artery
Hepatic and splenic arteries (cut)
Superior mesenteric artery (cut)
Right testicular artery (cut)
Aorta
Inferior mesenteric artery
S
R
L
I

Fig. 4.94 Removal of the autonomic nerves and retroperitoneal connective tissues reveals the lymphatic vessels and nodes lying on the right side of the aorta.

Some lymph nodes are situated adjacent to the organs they drain and include those of the liver and spleen and in the hila of the kidneys. The lymphatic vessels draining most of the abdominal organs accompany blood vessels and pass to nodes grouped around the aorta. Often, lymph passes through intermediate nodes situated along the courses of the arteries. Most of the lymph from the abdominal walls and viscera eventually drains into the thoracic duct.

Because of their deep position, most intra-abdominal lymph nodes are not palpable in the living subject, even when enlarged.

Iliac lymph nodes

The external iliac nodes (Fig. 4.93) receive lymph from the lower limb and perineum via the deep inguinal nodes. In addition, the iliac nodes drain the deeper layers of the abdominal wall below the level of the umbilicus via lymphatic vessels accompanying the inferior epigastric vessels. Lymph from the superficial tissues of the lower abdominal wall reaches the external iliac nodes, having passed first to superficial and then to deep inguinal nodes.

The internal iliac nodes drain the pelvic walls and floor and some of the pelvic organs, including the bladder, lower part of the rectum, prostate and uterus. However, lymph from most of the rectum, sigmoid colon and ovaries drains to the aortic nodes. From the external and internal iliac nodes lymph passes to nodes alongside the common iliac artery (Fig. 4.93) and subsequently to the aortic nodes.

Aortic nodes

The major abdominal lymphatic vessels and their associated nodes are arranged alongside the aorta (Fig. 4.94). The nodes on each side of the aorta receive lymph from the common iliac nodes, posterior abdominal wall, gonads, kidneys and suprarenal glands, while nodes lying immediately anterior to the aorta drain the digestive organs.

Nodes around the origin of the inferior mesenteric artery drain lymph from most of the rectum and the sigmoid and descending parts of the colon. Nodes lying adjacent to the origins of the superior mesenteric and coeliac arteries drain the spleen, pancreas, liver, stomach, small intestine and the large intestine as far as the splenic flexure.

Cisterna chyli

Efferent lymphatics from the aortic nodes drain into the cisterna chyli (Fig. 4.95). This fusiform sac lies at the level of the upper two lumbar vertebrae, adjacent to the right crus of the diaphragm. It lies behind the right border of the aorta and opens superiorly into the thoracic duct. The duct ascends through the aortic opening of the diaphragm and continues through the thorax to drain into the great veins in the root of the neck (p. 62).




S
R
L
I
Posterior intercostal vessels
Azygos vein (cut)
Thoracic duct
Descending thoracic aorta (cut)
T12/L1 inter-vertebral disc
Left crus of diaphragm (cut)
Duplication of thoracic duct
Cisterna chyli
Afferent lymphatic vessels
Lumbar arteries
Right crus of diaphragm (cut)
Abdominal aorta (cut)
Inferior mesenteric artery

Fig. 4.95 Cisterna chyli, revealed by removal of parts of the crura of the diaphragm and a segment of aorta.

Autonomic Nerves of the Abdomen

The autonomic innervation to the abdominal viscera is provided by perivascular plexuses of nerves accompanying the arterial supply to each organ. The plexuses comprise sympathetic and parasympathetic fibres of both motor and sensory type. The autonomic nerves control glandular secretion, smooth muscle activity and vasomotor tone; they are also sensory, mediating the distension of hollow organs and the tension on mesenteries.

Parasympathetic nerves

Most of the parasympathetic supply is provided by the vagus (X cranial) nerves, but there are small contributions to the distal part of the colon from branches of the pelvic splanchnic nerves that arise from the sacral spinal nerves. The vagi and the pelvic splanchnic nerves carry preganglionic parasympathetic fibres, which synapse with postganglionic fibres in the walls of the relevant organs.

From the oesophageal plexus (p. 62) two or more vagal trunks (gastric nerves) emerge and accompany the oesophagus through the diaphragm. The anterior trunk, derived mostly from the left vagus nerve (Fig. 4.96), enters the abdomen in front of the oesophagus and gives branches to the anterior surface of the stomach and to the liver. The posterior trunk, derived mostly from the right vagus, descends behind the oesophagus and supplies the posterior surface of the stomach and the coeliac plexus. From this plexus, some vagal fibres pass inferiorly to the root of the superior mesenteric artery. The perivascular plexuses that accompany branches of the coeliac and superior mesenteric arteries convey these vagal fibres to all parts of the digestive system as far distally as the splenic flexure of the colon.

The remainder of the large intestine receives its parasympathetic supply from branches of the pelvic splanchnic nerves (nervi erigentes). These ascend through plexuses in the pelvis (p. 236) and cross the left common iliac vessels in the root of the sigmoid mesocolon to reach the root of the inferior mesenteric artery. By accompanying branches of this artery, parasympathetic fibres from the sacral segments of the spinal cord supply the descending and sigmoid parts of the colon and the rectum.



Fig. 4.96 Anterior vagal trunk, revealed by removal of part of the diaphragm and exposure of the lower oesophagus.

Sympathetic nerves

The sympathetic system in the abdomen comprises two gangliated trunks and a network of nerves (the aortic or prevertebral plexuses) covering the surface of the aorta.

Each sympathetic trunk enters the abdomen behind the medial arcuate ligament of the diaphragm (Fig. 4.97) and descends along the medial border of psoas major, the trunk on the right lying posterior to the inferior vena cava. Each trunk passes behind the common iliac vessels and crosses the pelvic inlet at the ala of the sacrum.

Within the abdomen, each trunk bears five lumbar ganglia. Only the upper two ganglia receive fibres from the central nervous system. These preganglionic sympathetic fibres are conveyed in white rami communicantes arising from the first and second lumbar spinal nerves. Some preganglionic fibres synapse in the sympathetic trunk, while others pass into branches of the trunk and synapse nearer the target organs.

Each ganglion of the trunk gives a branch, a grey ramus communicans, to the corresponding spinal nerve. The postganglionic sympathetic fibres in the grey rami are distributed to the body wall and the lower limb. In addition, the ganglia supply branches (containing both pre- and postganglionic fibres) to the abdominal and pelvic organs. Branches from the upper ganglia reinforce the aortic plexuses, while the lumbar splanchnic nerves descend from the lower ganglia and cross anterior to the common iliac vessels (Fig. 4.98). The lumbar splanchnic nerves from the right and left trunks unite below the bifurcation of the aorta to form the hypogastric plexus from which branches descend to reach the pelvic autonomic plexuses (p. 236).



Fig. 4.97 Lumbar portion of the left sympathetic trunk after removal of the aortic plexuses of nerves.

Aortic plexuses

The dense network of autonomic nerves (both parasympathetic and sympathetic) that invests the abdominal aorta (Fig. 4.98) has several component plexuses, which are named according to the larger branches of the aorta. These are the coeliac, aorticorenal, renal, superior mesenteric, intermesenteric and inferior mesenteric plexuses. From these perivascular plexuses, nerves are distributed to the abdominal organs.

The parasympathetic fibres in the aortic plexuses are derived mainly from the posterior vagal trunk, which enters the abdomen on the wall of the oesophagus, while the sympathetic fibres are provided principally by the thoracic splanchnic nerves (p. 64). These branches of the thoracic portions of the sympathetic trunks pierce the crura of the diaphragm to reach the coeliac plexus. Additional sympathetic fibres are provided by the upper ganglia of the lumbar sympathetic chain. Within the aortic plexuses are numerous small ganglia in which the pre- and postganglionic sympathetic fibres synapse.


Splenic and hepatic arteries (cut)
Superior mesenteric artery (cut) and plexus
Inferior mesenteric artery and plexus
Lumbar splanchnic nerves
Left kidney and suprarenal gland
Coeliac plexus
Renal plexus
Intermesenteric plexus
Psoas fascia
S
R
L
I

Fig. 4.98 Aortic plexuses of autonomic nerves after removal of aortic nodes and lymph vessels.

Posterior Abdominal Wall

Posterior to the abdominal cavity lie the lumbar spine, the psoas, iliacus and quadratus lumborum muscles, and associated fasciae and nerves (Fig. 4.99). The posterior abdominal wall extends inferiorly to the pelvic brim and superiorly to the attachment of the diaphragm (p. 203), while laterally it merges with the anterolateral abdominal wall. The lumbar spine and the postvertebral muscles (erector spinae) are considered in Chapter 8.

Muscles

Psoas major

This long fusiform muscle (Fig. 4.99) attaches to the sides of the last thoracic and all five lumbar vertebral bodies, to the intervening discs and to the fronts of the lumbar transverse processes. At the side of each lumbar vertebral body, psoas major attaches to a fascial tunnel conveying a lumbar artery and vein (Fig. 4.103).

The muscle inclines downwards, passing behind the inguinal ligament to enter the anterior compartment of the thigh (Fig. 4.100). The psoas major tendon, which also receives most of the fibres of iliacus, passes in front of the hip joint capsule, from which it is separated by a bursa (Fig. 6.68), and attaches to the lesser trochanter of the femur.

Psoas major is innervated by the anterior rami of the upper lumbar nerves and its principal actions are flexion and medial rotation of the hip joint. In addition, the muscle flexes the lumbar spine both anteriorly and laterally. Within the substance of psoas major the anterior rami of the lumbar nerves form the lumbar plexus, whose branches emerge from the lateral, anterior and medial surfaces of the muscle.

Psoas minor

When present, this small muscle lies on the anterior surface of psoas major and gives way to a long narrow tendon (Fig. 4.99), which attaches to the iliopubic eminence of the hip bone.

Iliacus

This fan-shaped muscle attaches to the upper portion of the abdominal surface of the ilium and adjacent part of the sacrum (Fig. 4.100). Most of its fibres attach to the tendon of psoas major although some reach the femur below the lesser trochanter. The muscle is innervated by the femoral nerve (Fig. 4.103) and assists psoas major in flexing the hip joint.


Transversus abdominis
Iliac crest
Psoas major and psoas minor tendon
Quadratus lumborum
Iliacus
Lumbosacral trunk
Femoral nerve
Obturator nerve
Diaphragm
Subcostal nerve
Iliohypogastric nerve
Ilioinguinal nerve
Sympathetic trunk
Iliac and psoas fasciae
Genitofemoral nerve
S
R
L
I

Fig. 4.99 Removal of the abdominal contents reveals the muscles and nerves of the posterior abdominal wall. On one side, some iliac and psoas fasciae have been preserved.

Quadratus lumborum

Quadratus lumborum (Fig. 4.99) is anchored inferiorly to the iliolumbar ligament and adjacent part of the iliac crest. Superiorly, it reaches the medial part of the lower border of the twelfth rib. There are intermediate attachments to the transverse processes of the upper four lumbar vertebrae. This muscle is innervated by the subcostal nerve and anterior rami of the upper three lumbar nerves and is a lateral flexor of the lumbar spine. When the diaphragm contracts during inspiration, quadratus lumborum stabilizes the twelfth rib.


Genitofemoral nerve (cut)
Psoas major
Iliacus
External iliac vessels (cut)
Femoral nerve (cut)
Tendon of psoas minor
Anterior superior iliac spine
Sartorius (cut)
S
la
m
I

Fig. 4.100 Iliacus and psoas major, seen after removal of the inguinal ligament and part of sartorius. The psoas minor tendon descends to the iliopubic eminence of the hip bone.

Fasciae

The psoas and iliac fasciae form a continuous layer covering the anterior surfaces of their respective muscles (Fig. 4.99). The psoas fascia fuses superiorly with the diaphragmatic fascia and laterally and inferiorly with the transversalis fascia. Fascial thickenings over the upper parts of psoas major and quadratus lumborum form the medial and lateral arcuate ligaments (lumbocostal arches), which provide attachment for the diaphragm (Fig. 4.103). Fascial layers covering the anterior and posterior surfaces of quadratus lumborum fuse to form the thoracolumbar fascia which gives attachment to transversus abdominis. The psoas fascia can direct the spread of tuberculosis from the lumbar vertebrae into the anterior triangle of the thigh, producing a psoas abscess.

Nerves

On each side of the midline the sympathetic trunk enters the abdomen behind the medial arcuate ligament of the diaphragm and descends on the medial border of psoas major (Fig. 4.97). The anterior rami of the subcostal and lumbar nerves emerge through their respective intervertebral foramina and enter the substance of psoas major. All spinal nerves within psoas receive grey rami communicantes from the sympathetic trunk, but only the last thoracic and upper two lumbar nerves supply white rami to the trunk.

Subcostal (T12) nerve

This nerve follows the lower border of the twelfth rib and enters the abdomen behind the lateral arcuate ligament of the diaphragm (Fig. 4.103). It crosses the anterior surface of quadratus lumborum and continues on the deep surface of transversus abdominis. The nerve pierces transversus to enter the neurovascular plane of the abdominal wall, and its subsequent course is similar to that of the lower intercostal nerves (p. 145).


L1
L2
L3
L4
L5
Iliohypogastric nerve
Ilioinguinal nerve
Genitofemoral nerve
Lateral cutaneous nerve of thigh
Femoral nerve
Obturator nerve
Lumbosacral trunk

Fig. 4.101 Diagrammatic representation of the lumbar plexus to show the origins of each of its branches.


First lumbar nerve
S
la
m
I
Psoas major
Lateral cutaneous nerve of thigh
Anterior ramus of L5
Genital and femoral branches of genitofemoral nerve
Obturator nerve
Femoral nerve

Fig. 4.102 Branches of the lumbar plexus emerge from the substance of psoas major.


Psoas major (cut)
Medial arcuate ligament
Lateral cutaneous nerve of thigh (displaced)
Lateral arcuate ligament
Subcostal nerve
Quadratus lumborum
First lumbar nerve
Iliolumbar ligament
Femoral nerve and branch to iliacus
Psoas major (cut)
Median arcuate ligament
Lumbar arteries
Anterior rami of L4 and L5
Sympathetic trunk
Lumbo-sacral trunk
Obturator nerve
S
R
L
I

Fig. 4.103 Removal of most of psoas major and the genitofemoral nerve exposes the lumbar plexus.

Lumbar plexus

Within psoas major the anterior rami of the upper four lumbar nerves form the lumbar plexus, whose branches are distributed to the lower part of the abdominal wall, the lower limb and the sacral plexus in the pelvic cavity (Figs 4.101 & 4.104).

First lumbar nerve

Although a few first lumbar (L1) fibres contribute to the genitofemoral nerve (Fig. 4.101), most form a nerve that emerges from the lateral border of psoas major and crosses the anterior surface of quadratus lumborum (Fig. 4.103).

After a variable distance, this nerve divides into iliohypogastric and ilioinguinal branches, which continue into the anterolateral abdominal wall. Their paths and distribution are considered on p. 145.

Genitofemoral (L1, L2) nerve

This nerve emerges through the anterior surface of psoas major on which it descends, dividing into two branches (Fig. 4.101). The genital branch enters the deep inguinal ring and innervates the cremaster muscle, while the femoral branch passes behind the inguinal ligament to reach the subcutaneous tissue covering the femoral triangle (Fig. 6.9).

Lateral cutaneous (L2, L3) nerve of thigh

Emerging from the lateral side of psoas major, this nerve inclines across the anterior surface of iliacus (Fig. 4.102). It passes behind or through the inguinal ligament close to the anterior superior iliac spine (a site of possible entrapment) and supplies skin on the anterolateral aspect of the thigh (Figs 6.9 & 6.21).

Femoral (L2, L3, L4) nerve

This large nerve appears at the lateral border of psoas major and descends in the gutter between this muscle and iliacus (Fig. 4.102). It innervates iliacus (Fig. 4.103), passes behind the inguinal ligament lateral to the femoral artery and enters the anterior compartment of the thigh (Figs 6.8 & 6.18, p. 262).

Obturator (L2, L3, L4) nerve

Descending vertically within psoas major, this nerve emerges from the medial border of the muscle near the pelvic brim (Figs 4.102 & 4.103). It passes behind the common iliac vessels and runs downwards and forwards on the lateral pelvic wall, as far as the obturator canal (p. 237). Within the canal it divides into anterior and posterior branches, which enter the medial compartment of the thigh (p. 266).

Lumbosacral trunk

Fibres from the fourth lumbar anterior ramus join those of the fifth to form the lumbosacral trunk (Fig. 4.103). The trunk emerges from the medial side of psoas major and crosses the sacroiliac joint to enter the pelvis, where it contributes to the formation of the sacral plexus (p. 237).

Diaphragm

The diaphragm is a musculotendinous partition separating the thoracic and abdominal cavities. Its periphery consists of skeletal muscle fibres, which merge centrally with an aponeurotic tendon (Fig. 4.104). The diaphragm has a pronounced convexity towards the thorax and has two domes or cupolas, the right usually lying at a higher level than the left (Figs 4.105 & 4.106).

Musculature

Peripherally, the diaphragmatic muscle is attached to the sternum, the costal margin and the vertebral column. The sternal attachment is by two small slips to the posterior surface of the xiphisternum. The costal attachment is to the inner surfaces of the lower ribs (usually 7–12) and costal cartilages (Fig. 4.105) by slips that interdigitate with those of transversus abdominis.

The diaphragm attaches to the vertebral column by two crura (pillars), one on each side of the abdominal aorta (Fig. 4.104). Both crura are anchored to the sides of the upper two lumbar vertebral bodies while the longer right crus is also attached to the third lumbar vertebra. The crura are linked in front of the aorta by the median arcuate ligament (Fig. 4.104), the fibres interdigitating as they ascend towards the central tendon. Lateral to each crus the diaphragm attaches to the transverse process of the first lumbar vertebra by the medial arcuate ligament (lumbocostal arch) and to the twelfth rib by the lateral arcuate ligament.

A triangular gap, the lumbocostal triangle (Fig. 4.104), often exists between the fibres attaching to the last rib and those arising from the vertebral column. This is a site where abdominal organs may herniate into the thorax.

Central tendon

The muscle fibres of the diaphragm converge on the margins of the central tendon, a V-shaped area of dense fibrous tissue with its apex directed towards the xiphisternum and its lateral parts running backwards into the domes (Fig. 4.104). The central tendon gives attachment to the fibrous pericardium and is pierced by the inferior vena cava (Figs 4.104 & 4.106).

Structures passing between the thorax and abdomen

Apertures in the diaphragm transmit the inferior vena cava and the oesophagus. The opening for the inferior vena cava (caval opening) lies to the right of the midline, and the oesophageal opening (hiatus) is slightly to the left (Fig. 4.104). During quiet breathing these openings lie at the levels of the eighth and tenth thoracic vertebrae, respectively. The caval opening pierces the central tendon and transmits the right phrenic nerve as well as the vena cava. The oesophageal opening, which also transmits the vagal trunks and branches of the left gastric vessels, is surrounded by muscle fibres of the right crus, which can constrict the oesophagus (Fig. 4.104). Weakness of this musculature may permit regurgitation of gastric contents or herniation of part of the stomach into the thorax (hiatus hernia). Patients may have difficulty with swallowing (dysphagia). The left phrenic nerve pierces the left dome adjacent to the apex of the heart, while on each side the thoracic splanchnic nerves pass through the crura to reach the coeliac plexus. The left crus may also be pierced by the hemiazygos vein.

The aorta enters the abdomen by descending behind rather than through the diaphragm and is accompanied by the thoracic duct and azygos vein (Fig. 4.107). The three vessels pass behind the median arcuate ligament and in front of the twelfth thoracic vertebral body. The subcostal nerves and vessels enter the abdomen behind the lateral arcuate ligaments anterior to quadratus lumborum, while the sympathetic trunks descend behind the medial arcuate ligaments anterior to psoas major (Fig. 4.104). Close to the xiphisternum, the superior epigastric vessels (branches of the internal thoracic vessels) pass between the sternal and costal slips of the diaphragm to enter the rectus sheath. Around the periphery of the diaphragm, intercostal nerves and vessels pass between the muscular slips to leave the lower intercostal spaces and reach the abdominal wall.

Movements

The diaphragm is an important muscle of inspiration and also assists the muscles of the abdominal walls and pelvic floor in raising the pressure within the abdomen and pelvis. Thus, the diaphragm contracts during acts of lifting and straining (e.g. defecation and childbirth).

Its shape and position vary with body position and the phase of ventilation. During full inspiration, the central tendon descends to approximately the level of the tenth thoracic vertebra. This descent, which is enhanced by an upright body posture, enlarges the thoracic cavity. When the diaphragm relaxes during expiration, its central tendon is pushed superiorly by intra-abdominal pressure, compressing the thoracic contents. With the body recumbent or head downwards, this upwards displacement is accentuated by the weight of the abdominal organs.


Central tendon
Inferior vena cava (cut)
Inferior phrenic arteries
Right crus
Medial arcuate ligament
Sympathetic trunk
Oesophagus (cut)
Median arcuate ligament
Abdominal aorta (cut)
Lumbocostal triangle
Subcostal nerve
S
R
L
I

Fig. 4.104 Abdominal surface of the diaphragm after removal of peritoneum. The xiphisternum and anterior costal margin have been excised, including part of the anterior periphery of the diaphragm.

Nerve supply

The right and left phrenic nerves provide the motor and main sensory supply to the diaphragm. The phrenic nerves arise in the neck, from the third, fourth and fifth cervical nerves (p. 236). Each nerve descends through the thorax (p. 60) and divides into terminal branches that pierce the diaphragm and innervate it from the abdominal surface.

Each phrenic nerve provides the motor supply to its own half of the diaphragm. In addition, each phrenic nerve carries sensory fibres from the pericardium and from pleura and peritoneum covering the central portion of the diaphragm. Stimulation of these fibres, for example by blood from a ruptured spleen, may produce pain referred to the shoulder region because the skin over the shoulder is also supplied by the fourth cervical segment of the spinal cord. By contrast, the pleura and peritoneum clothing the peripheral parts of the diaphragm are innervated by sensory branches of the lower intercostal nerves.

Blood supply

The major blood supply is provided by the inferior phrenic arteries (Fig. 4.104), which are usually direct branches of the aorta (Fig. 4.92). The corresponding veins drain into the inferior vena cava. Also, the musculophrenic vessels (terminal branches of the internal thoracic vessels; Fig. 2.17) supply the periphery of the diaphragm.

Relations

The inferior surface of the diaphragm is in contact with abdominal organs including the liver, kidneys, spleen and stomach. Its thoracic surface is related to the heart and lungs and their associated pericardium and pleura (Figs 4.105 & 4.106). Upward and downward excursions of the diaphragm cause corresponding movements of all the organs related to it. During the later stages of expiration, the periphery of the diaphragm comes into contact with the chest wall as the costodiaphragmatic recesses deepen (Fig. 4.105).



Fig. 4.105 The anterior chest and abdominal walls have been removed (except for the costal margins) to reveal the diaphragm. The abdominal organs are undisturbed but both lungs and the diaphragmatic pleura have been removed.


A
L
R
P
Oesophagus
Inferior vena cava
Pericardium
Right dome
Left dome
Descending thoracic aorta
Body of T7 vertebra
Costo-diaphragmatic recess

Fig. 4.106 Thoracic surface of the diaphragm. The parietal pleura remains in situ and the base of the fibrous pericardium has been retained.


Pleura (cut)
Posterior intercostal vein and artery
Azygos vein
Thoracic duct
Descending thoracic aorta
Coeliac trunk (cut)
Cisterna chyli
Superior mesenteric artery
Abdominal aorta
S
R
L
I

Fig. 4.107 The aortic opening of the diaphragm has been opened by division of the median arcuate ligament and removal of parts of both crura. The aorta is accompanied by the azygos vein and thoracic duct.

Exam Skills

Each of the incomplete statements below is followed by five suggested answers or completions.
Decide which are true and which are false. The answers are supplied on p. 417.

1. The rectus abdominis muscle:

a) is a powerful flexor of the lumbar spine.
b) is attached to the costal margin.
c) has a lateral border that crosses the ninth costal cartilage.
d) has the inferior epigastric artery as an anterior relation.
e) lies anterior to the inguinal canal.

2. The superior mesenteric artery:

a) arises from the abdominal aorta at the level of the third lumbar vertebra.
b) passes anterior to the horizontal (third part of) duodenum.
c) supplies branches to the head of the pancreas.
d) gives a middle colic branch.
e) supplies branches to the sigmoid colon.

3. The omental bursa (lesser sac):

a) extends superiorly behind the quadrate lobe of the liver.
b) extends to the left as far as the hilum of the spleen.
c) communicates with the greater peritoneal sac via an opening that lies posterior to the portal vein.
d) is closely related to the pancreas.
e) has the gastrosplenic ligament forming part of its posterior wall.

4. The spleen:

a) develops in the dorsal mesogastrium.
b) lies deep to ribs 9, 10 and 11.
c) may be related at its hilum to the tail of the pancreas.
d) is retroperitoneal.
e) receives its arterial supply from a branch of the superior mesenteric artery.

5. The inferior vena cava:

a) lies anterior to the right sympathetic trunk (chain).
b) passes anterior to the omental foramen.
c) has the right gonadal vein as a direct tributary.
d) pierces the diaphragm at the level of the tenth thoracic vertebra.
e) usually passes anterior to the right renal artery.

6. The diaphragm:

a) contracts during forced expiration.
b) derives part of its motor nerve supply from intercostal nerves.
c) is in direct contact with the liver.
d) derives some arterial supply from the internal thoracic arteries.
e) has an oesophageal opening (hiatus) through which passes the left phrenic nerve.

7. The right kidney:

a) is related posteriorly to the twelfth rib.
b) has a hilum that is directed medially and forwards.
c) is related anteriorly to the head of the pancreas.
d) moves downwards during expiration.
e) is embedded in perirenal fat.

8. Regarding the scrotum:

a) the tunica vaginalis lies posterior to the testis.
b) the epididymis lies medial to the ductus (vas) deferens.
c) the dartos muscle is striated.
d) the ilioinguinal nerve supplies some of the skin.
e) lymph from the subcutaneous tissues drains to inguinal nodes.

9. The body of the pancreas:

a) lies anterior to the splenic vein.
b) has the root of the transverse mesocolon attached to its anterior border.
c) is intraperitoneal.
d) lies at the level of the first lumbar vertebra.
e) receives branches from the splenic artery.

10. The right ureter:

a) lies anterior to the internal iliac artery.
b) is closely related at its commencement to the descending (second part of) duodenum.
c) receives some of its arterial supply from the right renal artery.
d) crosses anterior to the right gonadal vessels.
e) may pass close to the vermiform appendix.

11. The caecum:

a) possesses taeniae coli.
b) usually lies in the right iliac fossa.
c) receives its blood supply from the superior mesenteric artery.
d) usually has the vermiform appendix attached to its lateral side.
e) receives the terminal ileum.

12. Direct relations of the abdominal aorta include:

a) the left renal vein.
b) the descending (second part of) duodenum.
c) the anterior longitudinal ligament.
d) left lumbar veins.
e) the head of the pancreas.

13. Peritoneum related to the liver includes:

a) the falciform ligament, which attaches to the anterior abdominal wall.
b) the left triangular ligament, which attaches to the diaphragm.
c) the lesser omentum, within which lie the gastric vessels.
d) the hepatorenal recess (or pouch) between the liver and the right kidney.
e) the right triangular ligament, which is continuous with the coronary ligaments.

14. The psoas major muscle:

a) attaches to the bodies of all the lumbar vertebrae.
b) laterally flexes the lumbar spine.
c) is innervated by the femoral nerve.
d) has the obturator nerve emerging from its medial surface.
e) extends the hip joint.

15. The liver:

a) usually extends below the costal margin.
b) lies partly in the left hypochondrium.
c) is in direct contact with the left dome of the diaphragm.
d) receives blood from the spleen.
e) has a quadrate lobe which is superior to the porta hepatis.

16. The inguinal canal:

a) has a roof formed by the lowest fibres of the internal oblique and transversus abdominis muscles.
b) has a deep ring that lies lateral to the inferior epigastric vessels.
c) transmits the broad ligament of the uterus.
d) has a superficial ring through which the ilioinguinal nerve emerges.
e) transmits testicular lymphatic vessels to the deep inguinal nodes.

Clinical Case Skills

The answers are supplied on p. 418.

Case Study 1

In the space of 2 months, a 2-year-old boy was taken three times to the family doctor because his mother had noticed a swelling in his scrotum. On the first two occasions, the doctor had found nothing abnormal but the third time he found a mass and sent the boy into hospital for observation. On arrival in the ward, no lump could be found but while having a drink of water the boy spluttered, coughed and began to scream. Now a cylindrical mass was apparent in the lower half of his right groin and extended into the scrotum anterior to the right testis. By the time a surgeon arrived, the boy had begun to vomit. The surgeon said an operation was needed.

Questions:

1. What is the diagnosis?
2. Explain how a structure can move from the abdomen into the scrotum.
3. Why did the lump come and go?
4. What anatomical structure does the mass comprise?
5. Why did the boy vomit during the episode in hospital?
6. What will the surgeon do?

Case Study 2

A 20-year-old woman had an accident in her car. While not wearing a seatbelt, she collided with a tree. The paramedics found her trapped in the driving seat, partially conscious, pale and sweaty, with a weak and rapid pulse. They set up an intravenous drip and took her promptly to hospital. On arrival she was able to tell the doctors about pains in both her abdomen and her left shoulder. The pulse was still rapid and the blood pressure low. Her abdomen was tender, especially on the left side. Preparations were made for a blood transfusion and an abdominal operation. When she recovered from the anaesthetic, she was informed her spleen had been removed.

Questions:

1. The doctors suspected their patient had intra-abdominal bleeding. What was the evidence?
2. The spleen is commonly damaged in victims of blunt trauma to the abdomen. Why is this?
3. Into which part of the peritoneal cavity did the bleeding occur?

Case Study 3

A man in his 50s, who had always been fond of alcohol, especially spirits, visited his family physician with a 6-month history of vague ill-health. He had been prompted to seek advice because a few days earlier, he had noticed his skin looked yellow.

The physician was confronted by a pale and poorly man with mild jaundice. Examining his patient's abdomen, the physician found a tender mass, dull to percussion, in the right hypochondrium, which projected 2 cm below the costal margin and descended when a deep breath was taken. The physician gave his patient some stern advice about his diet, which included a ban on any further alcohol intake. He took a blood sample and asked the man to return in a few days.

Questions:

1. What diagnosis did the doctor make?
2. What features led him to this diagnosis?
3. Why did the mass move during inspiration?

The laboratory reported a raised serum bilirubin concentration and other results consistent with liver failure, but the man did not return and failed to respond to the physician's attempts to get in touch. More than a year later, the patient was found dead on the floor of his home in a pool of blood. The post-mortem report mentioned jaundice, ascites, nodularity and hardness of the liver. Varices had been found in the lower oesophagus, one of which had burst. A lot of clotted blood and partially digested food were found in the lungs, pharynx and mouth. The causes of death were asphyxia and shock.

4. How can liver disease produce varices in the oesophagus?
5. Where else might varicose veins be expected in such a patient?

Case Study 4

A 45-year-old man arrived at the Emergency Department complaining of agonizing pain in the abdomen that had lasted 4 hours. He had tried unsuccessfully to gain relief by defecating and emptying his bladder. He was pale, unable to keep still and begging for pain relief. He indicated the current site of the pain in the right iliac fossa but it had started in the small of the back on the right side and radiated into his groin. The physician found mild tenderness in the right iliac fossa, normal bowel sounds and no fever.

A rectal examination was normal. A sample of urine looked rather dark to the naked eye, and tested positive for blood.

Questions:

1. What is the anatomical origin of the pain?
2. Why was a rectal examination performed?

The patient was given an injection of a powerful analgesic and was admitted to a surgical ward. There he was encouraged to drink as much water as possible and all his urine was collected. A plain radiograph was taken of the abdomen and the doctors carefully examined this, along the line of the right ureter, for the shadow of a calculus in the ureter.

3. What is the course of the ureter, as seen on a radiograph?

An intravenous urogram was performed.

4. What anatomical structures should this investigation depict?

The patient passed his stone the following day. The pain subsided once the calculus entered the bladder and it travelled easily along the urethra into the collecting vessel.

Observation Skills

Identify the structures indicated. The answers are supplied at the foot of the page.



Fig. 4.108 Transverse CT image at the level of the twelfth thoracic vertebra.



Fig. 4.109 Transverse CT image at the level of the second lumbar vertebra.

Answers:

Fig. 4.108 1 = portal vein; 2 = common hepatic artery; 3 = stomach; 4 = coeliac trunk; 5 = body of pancreas; 6 = left suprarenal gland; 7 = splenic vein; 8 = spleen; 9 = left crus of diaphragm; 10 = superior pole of right kidney; 11 = inferior vena cava.

Fig. 4.109 1 = liver; 2 = gall bladder; 3 = inferior vena cava; 4 = transverse colon; 5 = small intestine; 6 = left renal vein; 7 = intercostal muscles; 8 = branches of left renal artery; 9 = erector spinae muscle; 10 = right kidney.



Fig. 4.110 Transverse CT image at the level of the fourth lumbar vertebra. (Compare Fig. 4.112.)



Fig. 4.111 Transverse section at the level of the twelfth thoracic vertebra. Inferior aspect.

Answers:

Fig. 4.110 1 = external oblique; 2 = transverse colon; 3 = rectus abdominis; 4 = descending colon; 5 = psoas major; 6 = ilium (not to be confused with ileum).
Fig. 4.111 1 = intercostal muscles; 2 = fundus of gall bladder; 3 = descending duodenum; 4 = left lobe of liver; 5 = superior mesenteric artery; 6 = stomach; 7 = pancreas; 8 = descending colon; 9 = left crus of diaphragm; 10 = abdominal aorta; 11 = inferior vena cava; 12 = right kidney; 13 = right lobe of liver; 14 = costodiaphragmatic recess.



Fig. 4.112 Transverse section at the level of the intervertebral disc between the third and fourth lumbar vertebrae. Inferior aspect. (Compare Fig. 4.110.)

Answers:

Fig. 4.112 1 = external abdominal oblique; 2 = ascending colon; 3 = peritoneal cavity; 4 = transverse colon; 5 = linea alba; 6 = rectus abdominis; 7 = greater omentum; 8 = small intestine; 9 = retroperitoneal fat; 10 = descending colon; 11 = quadratus lumborum; 12 = mesentery of small intestine; 13 = abdominal aorta; 14 = inferior vena cava; 15 = psoas major.

Chapter 5

PELVIS AND PERINEUM

Introduction 214
  Pelvis 214
  Perineum 215
Pelvic Cavity 216
  Peritoneum 216
Rectum 218
  Relations 218
  Blood supply 218
Female Internal Reproductive Organs 219
  Uterus 219
  Uterine tubes 220
  Ovaries 221
  Vagina 221
Pelvic Ureters 222
Bladder 223
  Relations 224
  Blood supply 224
  Nerve supply 224
Female Urethra 225
Male Urethra 226
  Prostatic urethra 226
  Intermediate (membranous) urethra 227
  Spongy (penile) urethra 227
  Blood supply 227
  Nerve supply 227
Male Internal Organs of Reproduction 228
  Prostate 228
  Seminal vesicle 229
  Ductus (vas) deferens 229
  Bulbourethral gland 229
  Ejaculatory duct 230
  Blood supply 231
  Ejaculation 231
Pelvic Wall and Floor 232
  Hip bone 232
  Pelvic floor 233
  Joints 234
  Muscles 235
  Pelvic fascia 235
Pelvic Nerves 236
  Autonomic nerves 236
  Spinal nerves 237
Pelvic Blood Vessels and Lymphatics 238
  Internal iliac artery and branches 238
  Internal iliac vein and tributaries 239
  Pelvic lymphatics 239
Perineum 240
  Anal canal 240
  Ischioanal (ischiorectal) fossa 241
  Internal pudendal artery 241
  Pudendal nerve 243
Male External Genitalia 244
  Perineal membrane and pouches 244
  Penis 245
  Cutaneous innervation 245
  Lymphatic drainage 245
Female External Genitalia 246
  Clitoris and bulbs of vestibule 246
  Labia 246
  Vestibule 246
  Cutaneous innervation and blood supply 246
Exam Skills 248
Clinical Case Skills 249
Observation Skills 250

Introduction

The pelvic cavity is in direct continuity with the abdominal cavity. It extends downwards and backwards within the confines of the bony pelvis as far as the pelvic floor (pelvic diaphragm), inferior to which lies the perineum. Some anatomists and surgeons refer to the false pelvis or greater pelvis (below the iliac crests but above the pelvic inlet) and the true pelvis or lesser pelvis (below the inlet). This chapter deals only with the true pelvis and these other expressions will not be used again.

Pelvis

The pelvic cavity is a basin-shaped region below and behind the pelvic inlet (Fig. 5.1). It is surrounded by the bones of the pelvic girdle supplemented by muscles, ligaments and fascia. The anterior wall, near the pubic symphysis, is shallow while the posterior wall, the sacrum, is deep and concave. Each lateral wall is lined by the obturator internus, a broad muscle covered on its medial surface by fascia. Above this muscle are two apertures providing access for nerves and vessels entering the lower limb. The greater sciatic foramen leads into the gluteal region, the obturator canal into the thigh.

The organs in the pelvis include the bladder and lower ureters, the rectum and possibly coils of small intestine and the sigmoid colon. The male pelvis also contains the prostate (inferior to the bladder) and seminal vesicles (posterior to the bladder) and parts of the ductus deferentes (Fig. 5.5). In the female, the reproductive organs are interposed between the bladder and rectum and include the vagina, the uterus, uterine tubes and ovaries (Fig. 5.6). In the infant, the pelvic cavity is comparatively shallow and therefore parts of the bladder and uterus may lie above the pelvic brim. In the adult, however, the bladder and uterus often lie below the pelvic inlet (brim), though they rise into the abdomen when distended with urine or enlarged by pregnancy.

The peritoneum of the greater sac covers the superior parts of the pelvic organs. In the male it dips into a single pouch between the bladder and rectum while in the female it forms two deeper pouches, anterior and posterior to the uterus. The peritoneum that drapes over each uterine tube is called the broad ligament and the ovary attaches to its posterior aspect (Fig. 5.8).

The arterial supply to most of the pelvic organs is provided by the internal iliac artery (Fig. 5.2), but the rectum and ovaries are supplied by the inferior mesenteric artery and the ovarian arteries, respectively, from the abdominal aorta. Similarly, most venous blood passes to the internal iliac veins but the rectum drains to the portal venous system via the inferior mesenteric vein, while the ovarian veins enter the inferior vena cava and left renal vein. Much of the lymph from the pelvic organs passes to the internal iliac nodes, but the rectum and ovaries drain to aortic nodes in the abdomen.

Many of the nerves in the pelvis, including the sacral plexuses, are applied to the pelvic walls and are merely in transit to the lower limb. The pelvic organs themselves receive autonomic innervation via the left and right pelvic plexuses, which surround the branches of the internal iliac arteries. The parasympathetic contribution to these plexuses comes from the pelvic splanchnic nerves, branches of the second, third and fourth sacral spinal nerves, while the sympathetic innervation is provided by the hypogastric plexus, which descends from around the aortic bifurcation.

The gutter-shaped pelvic floor is formed largely by the left and right levator ani muscles. They arise from the pelvic wall, chiefly from the fascia covering the obturator internus muscles, slope downwards and fuse in the midline. There is a narrow midline gap near the pubic symphysis traversed by the urethra and vagina. The central part of the pelvic floor is pierced by the rectum, turning downwards and backwards to become the anal canal.



Fig. 5.1 Oblique anterosuperior view of pelvis to show pelvic inlet (pink line) and floor.

Perineum

The perineum is the shallow region that includes the anal canal and the external genitalia. It is bounded by the pelvic outlet: the inferior margins of the bones of the pelvis and their associated ligaments (Fig. 5.3). The region extends forwards to the pubic symphysis, backwards to the coccyx and laterally to the ischial tuberosities. The roof of the perineum is formed by the two levator ani muscles, the floor is the skin and each lateral wall is similar to that of the pelvis: the pubis and ischium are covered by the obturator internus muscle.

The posterior half of the perineum, the anal triangle, contains the anal canal, its sphincters and a fat-filled space on each side, the ischioanal (ischiorectal) fossa. Each fossa communicates with the gluteal region via a small aperture, the lesser sciatic foramen. The anterior half of the perineum, the urogenital triangle, includes the external genitalia. In the female, the lower parts of the vagina and urethra are surrounded by the vulva (labia majora and minora and the clitoris), while in the male the distal part of the urethra is enclosed by the penis. Below the root of the penis is the scrotum. Although the scrotum is part of the perineum it is described with the testis and inguinal canal in Chapter 4 (p. 149).

Most structures in the perineum, including the scrotum but excluding the testes, are supplied by the pudendal nerve and the internal pudendal vessels (Fig. 5.2). The neurovascular bundle arises in the pelvis but does not pierce the levator ani to reach the perineum. Instead, it traverses the greater sciatic foramen, the gluteal region and the lesser sciatic foramen. The nerve and vessels then run forward through the perineum, giving branches to the anal canal, the scrotum or labia and the penis or clitoris. Most of the lymph from these structures passes to the inguinal nodes, which are also the main site of drainage for the lower parts of the vagina and anal canal, but the testes drain to aortic lymph nodes in the abdomen.

The pudendal nerve gives motor branches to many striated muscles in the perineum, including the external anal and urethral sphincters. In addition, it supplies sensory branches to the anal canal, vagina, urethra and most of the perineal skin.


Common iliac artery
External iliac artery
Obturator artery traversing obturator canal
Sacrospinous ligament
Pubic symphysis
Lumbosacral disc
Internal iliac artery
Arteries to pelvic organs
Artery to gluteal region traversing greater sciatic foramen
Internal pudendal artery
S
A
P
I

Fig. 5.2 The internal iliac artery and some of its branches to the pelvis, perineum and lower limb.


Pubic symphysis
Aperture for anal canal
Ischial tuberosity
Urogenital hiatus
Sacrotuberous ligament
Sacrum and coccyx
A
R
L
P

Fig. 5.3 Inferior view of pelvic outlet (pink line) and boundaries of perineum.

Pelvic Cavity

Although the pelvic cavity is in direct continuity with the abdominal cavity, the two regions are delineated by the pelvic inlet (pelvic brim). This lies at approximately 45° to the horizontal and comprises the sacral promontory posteriorly, the arcuate and pectineal lines laterally and the pubic crests and upper border of pubic symphysis anteriorly (Figs 5.1 & 5.26).

The bony walls of the pelvis give attachment to two pairs of muscles. The obturator internus and piriformis muscles arise within the pelvis but their tendons pass out into the gluteal region to reach the femur. The fascia covering the medial surface of obturator internus is dense and provides attachment for the pelvic floor. The piriformis muscles spring from the anterior surface of the sacrum and are partially covered by the large nerves comprising the sacral plexuses (Fig. 5.4).

In both sexes, the pelvic cavity contains the rectum and bladder along with the lower parts of the ureters and loops of small or large intestine. The remaining organs differ between the sexes. The male reproductive organs found within the pelvis (Fig. 5.5) are the prostate, seminal vesicles and ductus deferentes. Those of the female (Fig. 5.6) are the ovaries, uterine tubes, uterus and upper part of vagina.

Peritoneum

Peritoneum lines the lateral and posterior pelvic walls and covers most of the pelvic organs (Figs 5.5 & 5.6). In both sexes peritoneum passes from the anterior abdominal wall onto the upper surface of the bladder. In the male, it descends on the posterior surface of the bladder and then passes onto the rectum, forming a recess, the rectovesical pouch (Fig. 5.14). In the female, peritoneum is reflected from the bladder onto the anterior surface of the body of the uterus, forming the vesicouterine pouch (Fig. 5.6). It covers the fundus of the uterus and on each side passes over the uterine tube, forming the broad ligament. From the posterior surface of the uterus, peritoneum passes over the vault of the vagina onto the anterior wall of the rectum, forming the rectouterine pouch (of Douglas). Fluid may collect in the rectovesical pouch of the male or the rectouterine pouch of the female and, if infected, may form a pelvic abscess.

Between the peritoneum and the pelvic organs, and intervening between the organs, lies the extraperitoneal fat or pelvic fascia (Fig. 5.7 and p. 235). This tissue is important in the spread of infection.



Fig. 5.4 Pelvis and lower abdomen after removal of all the organs and most of the vessels to demonstrate the pelvic inlet (pink line) and cavity.


S
A
P
I
Pubic symphysis
Bladder
Peritoneum
Sigmoid colon
Prostate
Rectovesical septum
Rectum
Anal canal

Fig. 5.5 Median sagittal section through the male pelvis to show the peritoneum and the principal pelvic viscera.


P
R
L
A
Ovary
Uterine tube
Rectouterine pouch
Vesicouterine pouch
Fundus of uterus
Bladder
Sigmoid colon (cut)
Broad ligament

Fig. 5.6 Superior view of peritoneum and organs within the female pelvis. The small intestine and most of the sigmoid colon have been removed.

Rectum

The rectum is the distal portion of the large intestine and lies in the posterior part of the pelvic cavity. It is continuous with the sigmoid colon at the rectosigmoid junction in front of the third piece of the sacrum (Fig. 5.7), where there is often an acute angulation. The rectum curves downwards and forwards, lying first on the anterior surface of the sacrum and then on the upper surface of the pelvic floor. It deviates to either side of the midline and these lateral flexures become pronounced when the organ is distended. The lowest part of the rectum, the ampulla, is its most dilatable portion. Turning abruptly downwards and backwards, the rectum pierces the pelvic floor and terminates at the anorectal junction, where it is continuous with the anal canal (Fig. 5.5). The sharp angulations at the anorectal and rectosigmoid junctions must be navigated with care during endoscopy.

Unlike the colon, the rectum is devoid of appendices epiploicae and has no taeniae, the longitudinal muscle being distributed uniformly around its circumference. The mucous membrane projects into the rectal lumen as three shelves, which form the horizontal folds.

Relations

The upper two-thirds of the rectum are related to the most inferior portion of the peritoneal cavity. The upper third of the organ is covered anteriorly and on both sides by peritoneum, while the middle third, lying behind the rectouterine or rectovesical pouch, has peritoneum only on its anterior surface.

Posterior to the upper part of the rectum are the sacrum, coccyx and the piriformis muscles, while its lower part rests on the levator ani muscles. Descending behind the organ are the superior rectal vessels (Fig. 5.7), the hypogastric plexus of autonomic nerves and, on each side of the midline, the sympathetic trunk and sacral plexus. Lateral to the rectum lie the pelvic plexuses of autonomic nerves and the ureters.

Anterior to the upper portion of the rectum lie those parts of the sigmoid colon and ileum that descend into the pelvic cavity. The anterior relations of the rectal ampulla are of clinical interest because they may be palpated on rectal examination. In the male, these are the prostate (Fig. 5.5), the base of the bladder, the seminal vesicles and ampullae of the ductus. These structures are separated from the rectum by the rectovesical septum. In the female, the rectal ampulla lies adjacent to the vagina. Therefore, rectal examination permits palpation of the cervix of the uterus.

Blood supply

The arterial supply to the rectum is derived principally from the superior rectal artery (Fig. 5.7), the continuation of the inferior mesenteric artery (p. 182). This supply may be supplemented by middle rectal branches from the internal iliac arteries. Venous blood drains into the portal venous system via the superior rectal vein and its continuation, the inferior mesenteric vein. In addition, middle rectal veins drain into the internal iliac veins. As the superior and middle rectal veins interconnect, the wall of the rectum is a site of portacaval anastomosis (p. 185).



Fig. 5.7 Anterior aspect of rectum seen in a male pelvis sectioned coronally. All peritoneum has been removed.

Female Internal Reproductive Organs

The female internal organs of reproduction include the uterus and vagina and the paired ovaries and uterine (fallopian) tubes. The uterus and ovaries are particularly affected by atrophy (shrinkage) after the menopause.

Uterus

The uterus is a pear-shaped organ approximately 8 cm in length. Its major component is the body (or corpus), which remains somewhat enlarged after pregnancy. Inferiorly, the uterus tapers into the cylindrical neck or cervix, which protrudes into the upper part of the vagina (Fig. 5.9).

The uterus is most commonly positioned with its body lying on the superior surface of the bladder (Fig. 5.8). As the bladder fills and empties, the uterine body moves on the relatively immobile cervix. Thus, when the bladder is empty the uterine body is anteflexed (bent forwards on the cervix), but when the bladder is distended the uterus may become retroflexed.

Body

The uterine body possesses anteroinferior and posterosuperior surfaces. The right and left borders give attachment to the broad ligaments and superiorly give origin to the uterine tubes (Figs 5.8 & 5.11). The rounded upper end of the organ between the attachments of the tubes is called the fundus.

On the posterosuperior surface of the uterus lie the sigmoid colon or coils of ileum. Both surfaces are covered with peritoneum, which continues laterally as the broad ligament (Fig. 5.11). Adjacent to the uterus within each broad ligament is the uterine artery and its associated plexus of veins. On each side, the ligament of the ovary and the round ligament of the uterus attach to the uterine body close to the origin of the uterine tube. These ligaments, remnants of the fetal gubernaculum, run laterally within the broad ligament, often raising ridges in the peritoneum. The ligament of the ovary attaches to the medial pole of the ovary, while the round ligament of the uterus runs to the lateral pelvic wall and turns forwards in the extraperitoneal tissues. Crossing the external iliac vessels, the round ligament of the uterus enters the deep inguinal ring (Fig. 5.8), traverses the inguinal canal and terminates in the subcutaneous tissues of the labium majus (Fig. 4.24).

The wall of the uterine body comprises a thick layer of smooth muscle (myometrium) lined by a vascular mucosa (endometrium), the thickness of which varies with the phases of the menstrual cycle. The uterine cavity is narrow in sagittal section but triangular in coronal section, being widest where the uterine tubes enter (Figs 5.10 & 5.11). Tapering inferiorly, the cavity communicates via the internal os with the cervical canal.



Fig. 5.8 Right ovary and broad ligament.

Cervix

The uterine cervix is thick-walled and has a narrow lumen, the cervical canal (Figs 5.9 & 5.11). The canal communicates superiorly with the uterine cavity via the internal os and opens inferiorly into the vagina at the external os. The external os is circular before the first vaginal delivery but thereafter presents an oval aperture. Although approximately in line with the body of the uterus, the cervix lies roughly at right angles to the long axis of the vagina (a position called anteversion). Structures close to the cervix are vulnerable to the local spread of cervical carcinoma. Approximately half of the cervix lies above the vagina (the supravaginal part) and is covered posteriorly by peritoneum passing from the uterine body onto the vault of the vagina. The root of the broad ligament is attached to this part of the cervix and contains the uterine artery (Fig. 5.13). The vessel runs medially above the ureter then turns upwards at the side of the cervix near the lateral fornix of the vagina. Anteriorly, the supravaginal part of the cervix is related to the posterior surface of the bladder. The lower half of the cervix protrudes through the anterior wall of the vagina, making it available for clinical examination including cervical smear testing. Structures close to the cervix, including both ureters, are vulnerable to the local spread of cervical carcinoma.

The uterine body and cervix are supplied by branches of the uterine artery, a branch of the internal iliac artery. Venous blood passes into the uterine venous plexus, which drains into the internal iliac vein (Fig. 5.13).

Uterine tubes

The paired uterine tubes, each approximately 10 cm long, run in the free upper borders of the broad ligaments (Figs 5.8, 5.10 & 5.11) and convey ova from the ovaries to the uterine cavity. Near the ovary, the lumen of each tube communicates with the peritoneal cavity via its pelvic aperture. This opening leads into the funnel-shaped infundibulum, which bears a series of finger-like processes, the fimbriae, one of which attaches to the ovary. The infundibulum leads into the ampulla, which forms the comparatively wide lateral part of the uterine tube. The medial part of the tube, the isthmus, is narrower and continues through the uterine wall as the intramural part of the tube.

The blood supply to the medial part of the uterine tube is provided by terminal branches of the uterine artery. This vessel runs laterally in the upper part of the broad ligament and anastomoses with the ovarian artery, which supplies the lateral portion of the tube. Venous blood drains into veins that accompany the arteries.

Fertilization of ova normally occurs in the uterine tube, usually within its ampulla.



Fig. 5.9 Uterus and vagina in sagittal section.



Fig. 5.10 Hysterosalpingogram. Radio-opaque medium has been injected, via a cannula in the vagina, into the uterus and along the uterine tubes.

Damage to the tubes, often as a result of inflammation (salpingitis), is a common cause of infertility. Sometimes an ectopic pregnancy occurs: a developing blastocyst may fail to reach the uterine cavity but implants and grows within the uterine tube. Rupture of the tube then leads to internal haemorrhage.

Ovaries

The ovaries lie close to the lateral pelvic walls, suspended from the posterior surfaces of the broad ligaments (Fig. 5.8). Each ovary is ovoid, approximately 4 cm long and 2 cm broad, with one pole directed medially towards the uterus and the other laterally towards the fimbriated end of the uterine tube. Each ovary is attached to the broad ligament by a sleeve of peritoneum, the mesovarium, which conveys the ovarian vessels. However, most of the ovarian surface is devoid of peritoneum. The ligament of the ovary attaches to the medial pole of the organ and runs within the broad ligament to reach the side of the uterine body. The ovary may lie in a shallow depression, the ovarian fossa, on the lateral pelvic wall between the external and internal iliac vessels. The ureter and the obturator nerve and vessels descend close to the ovary (Figs 5.13 & 5.16). Ovarian disease that spreads to involve the parietal peritoneum at this site, or the obturator nerve itself, may produce pain referred to the medial side of the thigh.

The ovary is supplied by the ovarian artery (Fig. 5.13), a direct branch of the abdominal aorta (p. 190). After crossing the pelvic brim, this vessel traverses the suspensory ligament of the ovary (infundibulopelvic ligament) to enter the broad ligament and divides into terminal branches within the mesovarium. The ovary is drained by numerous veins (the pampiniform plexus), which unite to form the ovarian vein. On the right, the ovarian vein terminates in the inferior vena cava, while the left ovarian vein usually joins the left renal vein (p. 194).

Vagina

The vagina is a midline tubular organ approximately 8–10 cm long, which slopes downwards and forwards (Figs 5.8 & 5.9). Its upper two-thirds, including the blind-ending vault, lie in the pelvic cavity. The vagina pierces the pelvic floor and terminates inferiorly by opening into the vestibule between the labia minora (p. 246). The anterior and posterior vaginal walls lie in mutual contact so that the lumen forms a transverse cleft. The lining possesses numerous transverse ridges (rugae; Fig. 5.12).

The uterine cervix pierces the upper part of the anterior vaginal wall and an anular groove surrounds the intravaginal part of the cervix. This groove is deepest superiorly where it is termed the posterior fornix (Fig. 5.9). On either side are the lateral fornices, while below the cervix is the comparatively shallow anterior fornix (Fig. 5.12).

Anteriorly, the vagina is closely applied to the posterior wall of the bladder and urethra. Posteriorly lie the rectouterine pouch of peritoneum and the ampulla of the rectum (Fig. 5.13). Lateral to its inferior third are the medial borders of the levator ani muscles, which provide important support to the vagina and uterus. Weakness of the pelvic floor musculature may lead to prolapse (descent of the uterus into the vagina).

The blood supply to the vagina is provided by branches of the uterine arteries and occasionally by vessels arising directly from the internal iliac arteries (Fig. 5.32). Venous blood passes into an extensive venous plexus surrounding the upper vagina and eventually reaches the internal iliac veins.



Fig. 5.11 Posterior aspect of uterus and broad ligaments. The uterine cavity, cervical canal and vagina have been exposed by removal of parts of their posterior walls.


Posterosuperior surface of uterus
External os
Anterior fornix
Lateral fornix
Vaginal wall (cut)
Rugae
S
L
R
I

Fig. 5.12 Intravaginal part of the cervix revealed by removal of the posterior wall of the vagina.

Pelvic Ureters

Each ureter enters the pelvis by crossing in front of the common iliac vessels or the commencement of the external iliac vessels (Fig. 5.14). The ureter passes downwards and backwards before curving forwards to reach the posterior surface of the bladder. The ureter crosses the medial aspect of the obturator nerve and vessels and the superior vesical vessels before running forwards along the levator ani muscle. The pelvic peritoneum covers the medial aspect of the ureter and separates it from the rectum, sigmoid colon or coils of ileum.

In the male, the ureter passes under the ductus deferens and terminates near the seminal vesicle (Fig. 5.15). In the female, the ureter descends on the lateral pelvic wall, outside the peritoneum but close to the ovary as far as the ischial spine, where it turns medially across the pelvic floor to reach the base (root) of the broad ligament. Here it crosses under the uterine artery and passes close to the uterine cervix (Fig. 5.13). The ureter is vulnerable to damage during hysterectomy.


Uterine tube
Ovarian vessels
Ureter
Internal iliac artery and vein
Superior rectal vessels (cut)
Obturator artery
Ovary
Obturator nerve
Round ligament of uterus
Uterine artery and vein
Rectouterine pouch
Rectum
S
A
P
I

Fig. 5.13 Uterine vessels and the ureter after removal of peritoneum from the lateral pelvic wall.

Bladder

The urinary bladder lies in the anterior part of the pelvic cavity. When distended, the organ has an approximately spherical shape, but when empty, it assumes the form of a tetrahedron with four angles and four surfaces. The two posterolateral angles receive the ureters while the inferior angle, the bladder neck, is continuous with the urethra. The anterior angle gives attachment to a fibrous cord, the median umbilical ligament (Fig. 5.17). This remnant of the fetal allantois ascends in the extraperitoneal tissues of the anterior abdominal wall to the umbilicus. If it remains patent, urine may leak from the umbilicus.

The superior surface and the two inferolateral surfaces expand considerably as urine accumulates but the comparatively small posterior surface or base remains relatively fixed. This surface lies between the entrances of the ureters and the bladder neck.

The wall of the bladder consists of smooth muscle (detrusor) whose thickness gradually decreases as the organ fills. Although the interior of the distended bladder is smooth, the mucosa becomes rugose when the organ empties (Fig. 5.17), except in the region of the trigone. This is the triangular area between the ureteric orifices and the internal urethral meatus (Fig. 5.14). The ureters pierce the musculature of the bladder wall obliquely and open at slit-like orifices.


Right ureter
External iliac vessels
Ductus deferens
Ureteric orifice
Trigone
S
R
L
I
Rectovesical pouch
External iliac vessels
Internal urethral meatus

Fig. 5.14 Coronal section through the male pelvis to show the interior of the bladder and some of its relations.


Bladder
Pubic bone (cut)
S
A
P
I
Left ureter
Left ductus deferens
Left seminal vesicle
Prostate
Levator ani (cut)

Fig. 5.15 Lateral view of the male bladder after removal of the left pelvic wall.

Relations

The superior surface of the bladder is covered with peritoneum (Fig. 5.17) on which rest coils of ileum and sigmoid colon. In both sexes, the inferolateral surfaces lie against the obturator internus and levator ani muscles and their associated fascial coverings. Between the bladder and these muscles run the obturator nerve and vessels and the superior vesical vessels (Fig. 5.16). Anterior to the bladder is the retropubic space, filled with adipose tissue and veins (Fig. 5.17). The empty bladder lies behind the pubic bones but as it fills, it rises above the level of the pubic crests and comes into contact with the lower part of the anterior abdominal wall. The distended bladder intervenes between the parietal peritoneum and the abdominal wall (Fig. 4.30) and can be accessed through a lower abdominal incision without opening the peritoneum.

In the male, the seminal vesicle and the ampulla of the ductus deferens are applied to each side of the posterior surface. Peritoneum descends a short distance on this surface before being reflected onto the anterior surface of the rectum to form the rectovesical pouch (Fig. 5.14). Below the level of this pouch, the bladder is related to the rectovesical septum and the ampulla of the rectum. Inferior to the male bladder lie the prostate and the prostatic plexus of veins.

In the female, the posterior part of the superior surface of the bladder is related to the body of the uterus (Fig. 5.17). Peritoneum passes from the superior surface of the bladder onto the uterine body, forming the vesicouterine pouch. Against the posterior surface of the female bladder lie the cervix of the uterus and the anterior wall of the vagina. The inferior angle of the bladder in the female lies at a lower level than in the male and is closely related to the two levator ani muscles.


Internal iliac artery
Ureter
Occluded part of umbilical artery
Superior vesical arteries
Bladder
Uterine artery
Obturator artery and nerve
S
A
P
I

Fig. 5.16 Arterial supply and relations of the bladder in a female pelvis.

Blood supply

The bladder is supplied by branches of the internal iliac arteries. On each side, the patent part of the umbilical artery gives off one or more superior vesical arteries (Fig. 5.16). The bladder receives additional supply from the inferior vesical and obturator arteries. In the female, the uterine and vaginal arteries also contribute to the vascular supply of the bladder.

Venous blood passes into an extensive network of veins, the vesical plexus, which communicates with the prostatic or vaginal plexus and drains into the internal iliac veins.

Nerve supply

The motor innervation to the detrusor muscle is by parasympathetic nerves conveyed in the pelvic splanchnic nerves and the pelvic plexus of autonomic nerves (Fig. 5.30). In the male, the smooth muscle surrounding the bladder neck (preprostatic sphincter) is innervated by sympathetic nerves derived from the hypogastric plexus. The parasympathetic motor innervation stimulates contraction of the bladder at the time of micturition, while the sympathetic supply to the male bladder neck prevents reflux during ejaculation.

Female Urethra

The female urethra is a fibromuscular tube 3–4 cm long and begins at the internal urethral meatus of the bladder. Embedded in the anterior wall of the vagina, it inclines downwards and forwards through the pelvic floor (Fig. 5.18) and terminates in the vestibule at the external meatus between the clitoris and the vaginal opening.

The urethra passes close to the posterior aspect of the pubic symphysis (Fig. 5.17), to which it is attached by the pubourethral ligaments. The middle third of the urethra is encircled by striated muscle fibres of the external urethral sphincter, whose tone is the principal factor in maintaining continence of urine. Occlusive force on the urethra is also provided by contractions of the levator ani muscles (Fig. 5.18). Micturition occurs when bladder pressure is higher than urethral pressure and is produced by contraction of the detrusor muscle of the bladder wall accompanied by relaxation of the external urethral sphincter. Stress incontinence (leakage of urine during everyday activities that raise intra-abdominal pressure) may occur following vaginal delivery due to weakening of pelvic floor muscles.

The arterial supply to the urethra is provided by the inferior vesical arteries, and venous drainage is to the vesical plexus of veins. The mucosa receives its sensory nerve supply from the pudendal nerve, derived from the second, third and fourth sacral segments, which also innervate the external urethral sphincter.


Median umbilical ligament
Sigmoid colon
Vesico-uterine pouch
Retropubic space
Pubic bone (cut)
Body and cervix of uterus
Bladder
Anterior vaginal wall
Urethra
S
A
P
I

Fig. 5.17 Median sagittal section through the female pelvis to show the bladder and some of its relations.


Internal urethral meatus
Urethra
Pubic symphysis
Rectum (cut)
Vagina (cut)
Levator ani
S
R
L
I

Fig. 5.18 Female urethra and its relation to the vagina and the levator ani muscles.

Male Urethra

The male urethra is a fibromuscular tube approximately 20 cm long. Beginning at the internal urethral meatus of the bladder, it descends through the prostate and the pelvic floor and enters the bulb of the penis (Fig. 5.19). It then traverses the corpus spongiosum and glans of the penis and terminates at the external urethral meatus. In the male the urethra not only drains urine from the bladder but also receives secretions from the prostatic ducts, the ejaculatory ducts and the ducts of the bulbourethral glands.

The male urethra is described in three parts: prostatic, intermediate (membranous) and spongy. The prostatic and intermediate parts pass downwards, while the spongy part turns forwards in the bulb of the penis (Fig. 5.19). A catheter or cystoscope must be manoeuvred carefully at this angulation to avoid urethral damage. Although the spongy and prostatic parts can be readily dilated, the external meatus and the intermediate urethra are comparatively narrow.

Prostatic urethra

Passing downwards through the prostate, the prostatic urethra is approximately 3 cm long. A midline ridge, the urethral crest, projects from the posterior wall, producing bilateral grooves, the prostatic sinuses (Fig. 5.20). Opening into each sinus are numerous prostatic ducts. The urethral crest is most prominent near its midpoint, where it presents a rounded elevation, the seminal colliculus. A midline orifice on the colliculus leads into a blind-ending sac, the prostatic utricle, which is a remnant of the ducts that give rise to the uterus in the female embryo. On each side of the utricle is the opening of the ejaculatory duct. Prostatic surgery, which disrupts the bladder neck and weakens the urethral sphincters, may impair urinary continence.


Bladder
Puboprostatic ligaments
Intrabulbar fossa
Corpus spongiosum
Spongy urethra
Glans penis
Navicular fossa
Prostate gland
Prostatic urethra
Intermediate urethra
Bulb of penis
S
A
P
I
External urethral meatus

Fig. 5.19 Male urethra in sagittal section.

Intermediate (membranous) urethra

Emerging from the anterior aspect of the apex of the prostate, the intermediate urethra descends through the pelvic floor and pierces the perineal membrane. It is approximately 2 cm long and its mucosa is folded, giving the lumen a stellate appearance on cross-section. Encircling the intermediate urethra is the striated muscle of the external urethral sphincter (Fig. 5.21), the main structure responsible for urinary continence. Lateral to the sphincter are the medial borders of the levatores ani.

Posterolateral to the intermediate urethra are the paired bulbourethral glands, each about 1 cm in diameter (Fig. 5.21). Their ducts pierce the perineal membrane and open into the spongy urethra. An additional posterior relation of the intermediate urethra is the ampulla of the rectum, while anteriorly lies the lower border of the pubic symphysis, to which the urethra is anchored by the pubourethral ligaments.

Spongy (penile) urethra

The spongy urethra is approximately 15 cm in length, commencing in the bulb of the penis and traversing the erectile tissue of the corpus spongiosum and glans (Fig. 5.19). The mucosa presents numerous small recesses or lacunae and most of its lumen forms a transverse slit. Within the bulb, the urethra is wider, forming the intrabulbar fossa. The lumen is also expanded within the glans to form the navicular fossa, which opens at the surface as a vertical slit, the external meatus. Urine may leak (extravasation) into the superficial perineal pouch if the spongy urethra is torn by perineal trauma or pelvic fracture (p. 244).

Blood supply

The prostatic and intermediate parts of the urethra receive blood from the inferior vesical arteries. The spongy part is supplied by the internal pudendal artery via the dorsal arteries of the penis and the arteries to the bulb. Venous blood passes into the prostatic venous plexus and the internal pudendal veins.

Nerve supply

The principal sensory innervation of the mucosa is provided by the pudendal (S2, S3 & S4) nerve, a branch of the sacral plexus. The same spinal cord segments innervate the external sphincter.

Male Internal Organs of Reproduction

The organs of reproduction in the male comprise the paired testes, epididymides, ductus (vasa) deferentia, seminal vesicles, ejaculatory ducts and bulbourethral glands, as well as the prostate and penis. The superficial organs (the external genitalia) include the penis (p. 245) and the testes and epididymides within the scrotum (pp 149–151).

The reproductive organs described here are those that lie within the pelvis, namely the prostate, the seminal vesicles, the intrapelvic parts of the ductus deferentia (Fig. 5.22) and the ejaculatory ducts.

Prostate

The prostate is an approximately spherical organ lying immediately below the bladder (Fig. 5.23). The flattened superior surface (base) is applied to the neck of the bladder and is pierced by the urethra, which descends through the gland and emerges near the blunt apex. The part of the prostate behind the urethra and above and between the ejaculatory ducts (see below) is sometimes described as the median lobe (Fig. 5.24).

Anteriorly, the prostate is anchored by the puboprostatic ligaments (Fig. 5.19) to the inferior border of the pubic symphysis. Inferior to the organ lies the intermediate urethra (Fig. 5.23) surrounded by the external urethral sphincter, and posteriorly are the rectovesical septum and the ampulla of the rectum. On each side of the prostate is the medial border of levator ani.

The gland often enlarges with advancing age (benign prostatic hypertrophy) and is a site of malignant change (prostatic carcinoma), which may metastasize to the vertebral column (p. 397). Both conditions may obstruct the prostatic part of the urethra. The gland is palpable on rectal examination and may be biopsied through the rectal wall.


Urethral crest
Prostatic sinuses
Prostate (cut)
Seminal colliculus
Opening of prostatic utricle
Openings of ejaculatory ducts
S
R
L
I

Fig. 5.20 Prostatic urethra opened through its anterior wall to show the urethral crest and seminal colliculus.




Pubic symphysis
Bladder
Prostatic venous plexus
Prostate
S
A
P
I
Course of urethra
Deep dorsal vein of penis
External urethral sphincter
Left bulbourethral gland
Bulb of penis

Fig. 5.21 The left pelvic wall and levator ani have been removed to show the prostate gland, external urethral sphincter, left bulbourethral gland and bulb of the penis.

Seminal vesicle

Each seminal vesicle is a sacculated gland approximately 3 cm long, lying lateral to the ampulla of the ductus deferens (Figs 5.24 & 5.25). The seminal vesicles lie in front of the rectum and rectovesical pouch of peritoneum (Fig. 5.23) and extend up the posterior wall of the bladder as far as the terminal parts of the ureters (Fig. 5.25).



Fig. 5.22 Lateral view of the prostate, left seminal vesicle and both ductus deferentes.

Ductus (vas) deferens

Each ductus (vas) deferens begins at the tail of the epididymis in the scrotum, ascends within the spermatic cord and traverses the inguinal canal (pp 146–148). After emerging from the deep inguinal ring, the ductus runs along the lateral pelvic wall, covered by peritoneum, and passes medial to the superior vesical vessels and obturator nerve and vessels. The ductus then crosses above the ureter (Figs 5.22 & 5.23) and turns downwards and medially, posterior to the bladder (Fig. 5.23). The terminal part of the ductus is dilated to form the ampulla, which lies medial to the seminal vesicle. The ampulla is related posteriorly to the peritoneum of the rectovesical pouch and to the rectovesical septum and rectum.

Bulbourethral gland

The bulbourethral glands (Fig. 5.21) lie adjacent to the intermediate urethra and are described on p. 227.


Peritoneum (cut) of rectovesical pouch
Seminal vesicle
Internal urethral meatus
Levator ani (cut)
Intermediate urethra
Ductus deferens and ampulla
Neck of bladder
Base and apex of prostate
S
R
L
I

Fig. 5.23 Coronal section of the pelvic walls and floor. Most of the bladder has been removed to reveal the prostate, the seminal vesicles and both ductus deferentes.

Ejaculatory duct

The duct of each seminal vesicle joins the ampulla of the corresponding ductus deferens to form the ejaculatory duct (Fig. 5.24). The right and left ducts pierce the prostate and run downwards, forwards and medially through its substance to open into the prostatic urethra at slit-like orifices on the summit of the seminal colliculus.

Blood supply

The artery to the ductus deferens is usually a small vessel that arises from the superior vesical artery and accompanies the ductus as far as the epididymis. The ampulla of the ductus, the seminal vesicle and prostate are supplied by the inferior vesical artery. From the internal reproductive organs, blood passes into the venous plexus (Fig. 5.21) surrounding the prostate to drain into the internal iliac veins.

Ejaculation

Semen contains spermatozoa from the testes and secretions from the ampullae of the ductus, the seminal vesicles and prostate. Under the control of the sympathetic nervous system, contraction of smooth muscle in the ductus, seminal vesicles and prostate propels secretions into the prostatic urethra. Semen is then expelled from the urethra by contractions of the bulbospongiosus muscles, which compress the bulb of the penis (p. 245). Reflux of semen into the bladder is prevented by contraction of the smooth muscle in the wall of the bladder neck, the preprostatic sphincter.


S
A
P
I
Ureter
Ampulla of ductus deferens
Bladder (opened)
Seminal vesicle
Prostatic urethra
Median lobe
Urethral crest
Ejaculatory duct
Seminal colliculus

Fig. 5.24 Dissection of prostate and left seminal vesicle.


Posterior surface of bladder
Ureter
Ductus deferens and ampulla
Ischial spine
Left seminal vesicle
Obturator internus
Prostate
S
L
R
I

Fig. 5.25 Removal of the rectum and the posterior wall of the pelvis exposes the bladder, prostate, seminal vesicles and ductus deferentes.

Pelvic Wall and Floor

The pelvic wall is formed by the bones of the pelvic girdle and their associated ligaments, muscles and fascia. The bony component comprises the right and left hip bones anterolaterally and the sacrum and coccyx posteriorly. The pelvic cavity is usually wider and shallower in females because of the differences in the shapes of the surrounding bones.

Hip bone

Only the medial or pelvic surface of the hip bone is considered here; the external surface is described on p. 269. Each hip bone is formed by the fusion of three components: ilium, ischium and pubis (Figs 5.26 & 5.27). The anterosuperior part of the ilium contributes to the abdominal wall and gives attachment to iliacus. The lower portion of the ilium extends below the pelvic inlet and contributes to the lateral wall of the pelvis. On the posterior part of the bone is the auricular surface, which articulates with the corresponding surface of the sacrum at the sacroiliac joint.

The ischium has a rounded tuberosity inferiorly, which bears body weight in the sitting position. Posteriorly is the pointed spine, which separates the greater and lesser sciatic notches, while anteriorly the ramus of the ischium ascends to fuse with the inferior pubic ramus.

The pubic bone has an iliopubic ramus that merges with the ilium near the iliopubic eminence, and an inferior ramus, which is continuous below the obturator foramen with the ramus of the ischium. The bodies of the right and left pubic bones articulate at the pubic symphysis.

The obturator foramen is a large aperture, which is almost completely occluded by the obturator membrane (Fig. 5.27). Superiorly, the membrane leaves a small gap, the obturator canal, which provides access between the pelvis and the medial compartment of the thigh.


S
A
P
I
Iliac crest
Anterior superior and anterior inferior iliac spines
Arcuate and pectineal lines
Superior ramus of pubis
Pubic crest
Symphysial surface
Inferior ramus of pubis
Auricular surface
Greater sciatic notch
Ischial spine
Lesser sciatic notch
Obturator foramen
Ischial tuberosity
Ramus of ischium

Fig. 5.26 Medial surface of right hip bone.

Pelvic floor

The pelvic floor (or diaphragm) is a muscular partition separating the cavity of the pelvis above from the perineum below. It slopes downwards towards the midline, forming a trough that inclines downwards and forwards (Figs 5.28 & 5.29). In the midline anteriorly, a narrow triangular gap, the urogenital hiatus, between the muscle fibres transmits the urethra in both sexes and the vagina in the female (Figs 5.1 & 5.18). Posteriorly, the pelvic floor is pierced by the anal canal.

The pelvic floor is formed principally by the right and left levator ani muscles, which are supplemented posteriorly by the coccygeus muscles (Fig. 5.29). The coccygeus muscle is applied to the medial surface of the sacrospinous ligament. Medially, it attaches to the lateral border of the sacrum and coccyx, and laterally to the ischial spine.

Each levator ani muscle has a linear attachment to the pelvic wall. The attachment commences anteriorly on the pelvic surface of the body of the pubis and continues backwards as the tendinous arch along the obturator fascia as far as the ischial spine (Fig. 5.29). The levator ani muscle has two parts: the anterior part comprises pubococcygeus and the posterior part is iliococcygeus.

Pubococcygeus runs backwards and downwards. Its most anterior fibres lie near the midline and pass close to the urethra. In the male, they support the prostate (Fig. 5.23); in the female, they attach to the vagina (Fig. 5.18). The intermediate fibres of pubococcygeus, puborectalis, reach the anal canal and either attach to its wall or loop behind the anorectal junction. The posterior fibres attach to the coccyx or fuse in the midline with fibres from the other side at the anococcygeal raphe.

The fibres of iliococcygeus pass downwards and medially below those of pubococcygeus and attach to the coccyx and to the anococcygeal raphe.

The levator ani muscles support the pelvic contents, actively maintaining the positions of the pelvic viscera. In particular, the pubococcygeus muscles compress the urethra and vagina and provide support for the bladder and uterus. The levator ani fibres that loop behind the anal canal help to maintain the angulation of the anorectal junction and play an important role in the continence of faeces. During defecation, the fibres attaching to the wall of the anal canal pull the organ upwards. Levator ani and coccygeus are innervated from above by the fourth sacral nerve and from below by branches of the pudendal nerve. The levator ani may be weakened by multiple vaginal deliveries, predisposing to stress incontinence (of urine) and uterine prolapse.


Pubic symphysis
Obturator nerve and vessels (cut) entering obturator canal
Sacroiliac joint
Superior gluteal artery (cut)
S
A
P
I
Piriformis
Greater sciatic foramen
Sacrospinous ligament
Ischial spine
Lesser sciatic foramen
Ligaments of pubic symphysis (cut)
Obturator membrane
Sacrotuberous ligament and ischial tuberosity
Obturator internus (cut)

Fig. 5.27 Right hemipelvis showing the pubic symphysis, the obturator membrane, the ligaments and the foramina.

Joints

The pelvic girdle forms a stable ring because its constituent bones are bound together at the two sacroiliac joints and the pubic symphysis.

The symphysis is a secondary cartilaginous joint containing a pad of fibrocartilage, the interpubic disc (Fig. 5.28), that separates the bodies of the right and left pubic bones. The joint is stabilized by ligaments attached around the articular margins.

The sacroiliac joints allow very little movement because the articulating surfaces of their synovial cavities are irregular and behind each cavity is the thick posterior interosseous ligament. Each joint is further supported by the anterior and posterior sacroiliac ligaments and iliolumbar, sacrospinous and sacrotuberous ligaments. Body weight acting downwards through the lumbosacral disc tends to rotate the sacrum, tipping its lower part backwards, a movement prevented by the sacrospinous and sacrotuberous ligaments (Fig. 5.27).

The iliolumbar ligament attaches medially to the transverse process of the fifth lumbar vertebra and laterally to the iliac crest and front of the sacroiliac joint. The sacrospinous ligament passes from the lateral margins of the sacrum and coccyx to the ischial spine. The larger sacrotuberous ligament passes from the side and dorsum of the sacrum and the posterior surface of the ilium to the ischial tuberosity. These two ligaments convert the greater and lesser sciatic notches into the greater and lesser sciatic foramina (Fig. 5.27). Pregnancy-related hormones may produce ligamentous laxity, especially at the joints of the pelvic girdle, reducing joint support and contributing to lumbar and pelvic pain during pregnancy.


Lumbosacral trunk
Obturator nerve and vessels (cut)
Interpubic disc
S
A
P
I
Sympathetic trunk
Anterior ramus of S3
Piriformis
Sacral plexus
Pudendal nerve and vessels (cut)
Obturator internus and its nerve

Fig. 5.28 Right hemipelvis showing the pelvic attachment of obturator internus.


S
A
P
I
Obturator fascia
Tendinous arch
Levator ani: pubococcygeus and iliococcygeus
Coccygeus
Anococcygeal raphe
External anal sphincter
Lower part of anal canal

Fig. 5.29 Right levator ani and part of the anal canal, seen in a median sagittal section of the pelvis.

Muscles

Piriformis is a flat muscle attached to the pelvic surfaces of the second, third and fourth pieces of the sacrum (Fig. 5.27). Running laterally through the greater sciatic foramen, it enters the buttock and attaches to the upper part of the greater trochanter of the femur (p. 271). Piriformis rotates the hip joint laterally and is innervated by the first and second sacral nerves. Numerous vessels and nerves accompany the muscle through the greater sciatic foramen (Fig. 5.28).

Obturator internus is a fan-shaped muscle with an extensive attachment to the margins of the obturator foramen and the pelvic surface of the obturator membrane (Fig. 5.28). The muscle fibres converge on the lesser sciatic foramen to form a tendon, which turns laterally to enter the gluteal region. The tendon is attached to the medial aspect of the greater trochanter (p. 271). The muscle laterally rotates the hip joint. The nerve to obturator internus (L5, S1 & S2) enters the muscle within the perineum, having traversed the greater and lesser sciatic foramina.

Pelvic fascia

This term includes the fascial lining of the pelvic walls and the extraperitoneal connective tissue surrounding the pelvic viscera (Fig. 5.7). The pelvic surfaces of obturator internus (Fig. 5.29), piriformis and levator ani are covered by fascia that is continuous superiorly with the transversalis and iliac fasciae. Between the pelvic organs, the pelvic fascia mostly comprises a loose meshwork of connective tissue. Pelvic infections can spread widely through these looser tissues. The fascia is condensed anterior to the rectum to form the rectovesical septum; and some of the arteries to the pelvic organs, notably the uterine and vaginal vessels, are accompanied by thickened bands of fascia termed ligaments. Radiating from the uterine cervix to the pelvic walls are the transverse cervical (lateral sacral), uterosacral ligaments and pubocervical ligaments, the latter passing below the bladder neck to reach the cervix.



Fig. 5.30 Right pelvic plexus of autonomic nerves. In this specimen the obturator artery is a branch of the inferior epigastric artery rather than the internal iliac artery.

Pelvic Nerves

Autonomic nerves

The pelvic organs receive their autonomic innervation via the right and left pelvic plexuses, which lie adjacent to the internal iliac arteries and their branches (Fig. 5.30). Nerves pass from the plexuses to the bladder, reproductive organs and the rectum by accompanying the arteries to these organs. The plexuses and their branches contain efferent fibres from both the parasympathetic and sympathetic systems, which reach the pelvis from different parts of the spinal cord.

Parasympathetic nerves

The parasympathetic component of the pelvic plexuses is provided by the pelvic splanchnic nerves (nervi erigentes), which leave the spinal cord in the second, third and fourth sacral nerves. The parasympathetic fibres control micturition, dilation of the erectile tissues in both sexes, and defecation. The pelvic plexuses also provide the parasympathetic innervation of the descending and sigmoid parts of the colon. These fibres ascend into the abdomen in the hypogastric plexus and are distributed with the branches of the inferior mesenteric artery. Extensive dissections during surgical excision of the prostate gland or the rectum may damage the parasympathetic innervation (cavernous nerves) to the erectile tissues, resulting in erectile dysfunction (impotence).


Lumbosacral trunk
Anterior rami of S2, S3 and S4
Obturator nerve (cut)
Obturator internus and nerve
S
A
P
I
Anterior ramus of S1
Superior gluteal artery (cut)
Piriformis
Sacral plexus
Sympathetic trunk
Lateral sacral artery
Pudendal nerve and vessels (cut)

Fig. 5.31 Sacral plexus and pelvic portion of the sympathetic trunk.

Sympathetic nerves

The sympathetic fibres destined for the pelvic autonomic plexuses arise from the lower thoracic and upper lumbar segments of the spinal cord and pass through the lumbar portions of the sympathetic trunks on the posterior abdominal wall. From here, they descend in the hypogastric plexus to reach the pelvis. Sympathetic fibres innervate the smooth muscle of the reproductive organs in both sexes, and in the male are responsible for coordinating ejaculation (p. 231).

The two sympathetic trunks pass from the posterior abdominal wall (p. 198) into the pelvis by crossing behind the common iliac vessels. Descending in front of the sacrum and piriformis muscles (Fig. 5.31), they incline towards the midline and fuse on the anterior surface of the coccyx. Each trunk bears three or four ganglia and provides grey rami communicantes, consisting of postganglionic fibres, to the sacral nerves. These fibres supply blood vessels and sweat glands in the areas innervated by the appropriate sacral nerves.

Spinal nerves

The lower lumbar and upper sacral spinal nerves are predominantly concerned with the innervation of the lower limb. However, a few fibres derived from these spinal nerves are distributed to the pelvic walls and floor and to the perineum.

Obturator nerve

This branch of the lumbar plexus (Fig. 4.101) emerges from the medial border of psoas major and enters the pelvis by crossing in front of the ala of the sacrum. It descends lateral to the common and internal iliac vessels and the ureter (Fig. 5.30) and reaches the medial surface of obturator internus. The nerve approaches the obturator vessels from above and continues with them through the obturator canal (Fig. 5.31) into the medial compartment of the thigh (p. 266). On the lateral pelvic wall, the obturator nerve may be closely related to the ovary (p. 221 and Fig. 5.13). Here, ovarian disease may spread to involve the pelvic peritoneum or the nerve itself, producing pain referred to the medial side of the thigh.

Sacral and coccygeal nerves

The anterior rami of the first four sacral nerves emerge through the anterior sacral foramina and merge to form the sacral plexus (Fig. 5.31). The fifth sacral nerve and the coccygeal nerves are small and do not contribute to the plexus. All the sacral and coccygeal nerves receive grey rami communicantes from the sympathetic trunk.

Sacral plexus

This plexus lies on the posterior pelvic wall in front of piriformis (Fig. 5.31), covered anteriorly by the pelvic fascia. The plexus is formed by the anterior rami of the upper four sacral nerves and is supplemented by the lumbosacral trunk, which carries fibres from the fourth and fifth lumbar nerves (p. 203). The branches of the sacral plexus are distributed to the lower limb, pelvic walls and floor, and perineum.

Those branches that leave the pelvis accompany piriformis through the greater sciatic foramen to enter the buttock (pp 270, 271). The nerve to obturator internus and the pudendal nerve then pass forwards through the lesser sciatic foramen to gain the perineum (Fig. 5.28).

Pelvic Blood Vessels and Lymphatics

The pelvic walls and floor and the pelvic organs receive most of their arterial supply from branches of the internal iliac artery, which also provides branches to the perineum and lower limb. The rectum, however, receives its principal supply from the superior rectal artery (pp 182, 218 & 238), while the posterior wall of the pelvis is supplied by the median sacral artery (Fig. 5.31). The ovaries are supplied by the ovarian branches of the abdominal aorta (p. 190).

Internal iliac artery and branches

The internal iliac artery arises in front of the sacroiliac joint as one of the terminal branches of the common iliac artery (Fig. 5.32). The internal iliac artery runs downwards and backwards on the lateral pelvic wall, giving rise to visceral and parietal branches.

Visceral branches

Before birth, the largest branch of the internal iliac artery is the umbilical artery, which conveys blood to the placenta. In the adult, only its proximal part is patent. It runs forwards, adjacent to the bladder, giving one or more superior vesical branches (Fig. 5.32) and a slender branch to the ductus deferens. Distally, the vessel becomes a fibrous cord, the occluded part of the umbilical artery or medial umbilical ligament, which continues through the extraperitoneal tissues of the anterior abdominal wall to the umbilicus (Fig. 4.30). The inferior vesical artery occurs only in the male and supplies the lower part of the bladder, the prostate, the seminal vesicle and the pelvic ureter. The uterine artery runs medially in the root of the broad ligament, crosses above the ureter (Fig. 5.13) and supplies the vagina and the uterine cervix, body and tube. The artery follows the lateral border of the body of the uterus, then runs laterally in the broad ligament, close to the uterine tube, and terminates by anastomosing with the ovarian artery.

The vagina is supplied by branches of the uterine artery together with one or two small vaginal arteries from the internal iliac artery.

The middle rectal artery (Fig. 5.32) supplies the muscle coat of the rectum and in the male, may give additional branches to the prostate and seminal vesicles.


Left common iliac vein (cut)
Right common iliac artery
Internal iliac artery
External iliac artery
Ureter
Occluded part of umbilical artery
Superior vesical arteries
S
A
P
I
Right internal iliac vein (cut)
Inferior gluteal artery
Internal pudendal artery
Middle rectal artery
Uterine and vaginal arteries
Obturator artery

Fig. 5.32 Right internal iliac artery and some of its branches.

Parietal branches

The obturator artery runs downwards and forwards, with the corresponding vein and nerve, to enter the obturator canal. It supplies the proximal part of the medial compartment of the thigh and the hip joint (Figs 5.28 & 5.32). Occasionally, the obturator artery takes origin from the inferior epigastric artery and descends into the pelvis to reach the obturator canal. Such a vessel, an accessory or abnormal obturator artery (Fig. 5.30), passes close to the femoral ring. In the latter case, it may be damaged during femoral hernia operations (Figs 4.23 & 5.30, femoral ring).

The superior and inferior gluteal arteries pass through the greater sciatic foramen into the buttock, the superior artery running above piriformis (Fig. 5.31) and the inferior below (p. 271).

The internal pudendal artery provides the principal arterial supply to the perineum. The artery passes through the greater sciatic foramen into the gluteal region, curves round the ischial spine and then passes forwards through the lesser sciatic foramen into the perineum (p. 241).

The iliolumbar artery ascends the posterior abdominal wall to anastomose with the lower lumbar arteries.

The lateral sacral artery (Fig. 5.31) supplies the posterior wall of the pelvis and anastomoses with the median sacral artery.

Internal iliac vein and tributaries

The branches of the internal iliac artery are accompanied by veins that drain the buttock and perineum, the pelvic walls and most of the pelvic organs. These veins unite to form the internal iliac vein (Fig. 5.33), which ascends on the lateral pelvic wall posterior to the artery. The vein terminates by joining the external iliac vein to form the common iliac vein.

Most of the veins emerging from the pelvic organs anastomose freely, forming extensive venous plexuses (the vesical, prostatic, uterine and vaginal plexuses). While most blood from these plexuses passes into the internal iliac vein, some enters either the superior rectal vein via portacaval anastomoses or the vertebral venous plexus via the anterior sacral foramina. Prostatic carcinoma can spread via these venous plexuses to the sacral and lumbar vertebrae.

Pelvic lymphatics

Lymph from the pelvis is drained by lymphatic vessels that accompany the arteries. Most of the lymph drains into nodes adjacent to the internal iliac artery and then into efferent vessels that pass to the common iliac nodes (p. 196). However, lymphatic vessels from the ovaries and the rectum pass directly to the aortic nodes, and some vessels from the body of the uterus accompany the round ligament through the inguinal canal to terminate in the superficial inguinal nodes.



Fig. 5.33 Right internal iliac vein and tributaries.

Perineum

Below the pelvic floor lies the perineum, a superficial region traversed by the anal canal and the lower parts of the genital and urinary tracts. The perineum is diamond-shaped, extending anteriorly to the pubic symphysis, posteriorly to the coccyx and laterally to the ischial tuberosities (Figs 5.34 & 5.3). On each side, the region is bounded by the conjoined rami of the ischium and pubis and by the sacrotuberous ligament, which is overlapped by the inferior border of gluteus maximus. Inferiorly, the perineum is bounded by skin. By convention, the perineum is divided into two triangular areas by a line joining the ischial tuberosities. Posteriorly is the anal triangle, containing the anal canal and the ischioanal (ischiorectal) fossae, and anteriorly lies the urogenital triangle, containing the external genitalia.

Anal canal

The anal canal is the terminal part of the intestine and is approximately 4 cm long. Beginning at the anorectal junction, it passes downwards and backwards as far as the anus (Fig. 5.5). Its upper part is lined by mucous membrane bearing several longitudinal ridges, the anal columns; the lower part is lined by skin. The smooth muscle coat of the rectum continues into the wall of the anal canal and thickens to form the internal anal sphincter. Striated fibres from the levator ani muscles (Fig. 5.35) blend with the outer layers of the wall and continue as far as the perianal skin.

In addition, the lower two-thirds of the anal canal are encircled by the external anal sphincter (Fig. 5.36), composed of striated muscle fibres. This sphincter comprises three parts, of which the uppermost, the deep part, blends with the levator ani muscles. Inferior to this lies the superficial part, attached posteriorly to the coccyx and anococcygeal raphe and anteriorly to the posterior border of the perineal membrane. The most inferior component of the sphincter, the subcutaneous part, encircles the anal opening. Continence of faeces is not dependent on the external sphincter alone; the fibres of the levator ani muscles that maintain the anorectal angulation play a major role.

The anal canal is supplied by inferior rectal branches (Fig. 5.36) from the pudendal nerve, which innervate the external sphincter and the cutaneous lining (p. 243). The internal sphincter and the mucous membrane lining the upper part are innervated, like the rectum, by autonomic nerves. The blood supply is provided by inferior rectal branches of the internal pudendal artery. The anal canal is a site of portacaval anastomosis because venous blood passes not only via inferior rectal veins to the internal iliac veins but also into the superior rectal vein (p. 185). These anastomoses dilate in the presence of portal hypertension. The lining of the lower part of the anal canal has a rich nerve supply. Tears of the mucosa of the lower part of the anal canal may result in painful fissures. Lymph drains from the upper part of the canal to the internal iliac nodes, but from the lower part, it passes to the superficial inguinal nodes. Therefore, a patient with an anal tumour may present with inguinal lymphadenopathy. Lymph drains from the upper part of the canal to the internal iliac nodes, but from the lower part, it passes to the superficial inguinal nodes.



Fig. 5.34 Deep dissection of male perineum. The bulb of the penis has been removed to expose the perineal membrane. Gluteus maximus has been resected on one side to reveal the sacrotuberous ligament.

Ischioanal (ischiorectal) fossa

On each side of the anal canal is a fat-filled space extending laterally as far as obturator internus, upwards to the levator ani muscle and downwards to the perianal skin (Fig. 5.35). The fossae communicate behind the anal canal. Anteriorly, each fossa tapers and continues above the perineal membrane and external urethral sphincter almost to the pubic symphysis. Entering each fossa from the gluteal region via the lesser sciatic foramen are the nerve to obturator internus, the pudendal nerve (Fig. 5.37) and the internal pudendal artery with its venae comitantes. Although infection in this fossa (ischiorectal abscess) often requires surgical incision, the vessels and nerves supplying the anal canal are protected by their superior location within the fossa and are rarely damaged.

The nerve to obturator internus arises from the sacral plexus and supplies the muscle from within the ischioanal fossa (Fig. 5.28).

The pudendal nerve and the internal pudendal vessels pass along the lateral wall of the fossa in a fascial tunnel, the pudendal canal. Branches from the nerve and artery traverse the upper part of the fossa to supply the anal canal and the posterior part of the scrotum or labium majus (Fig. 5.36).

Internal pudendal artery

This vessel provides most of the arterial blood to the perineum. Arising from the internal iliac artery within the pelvis (Fig. 5.32), it enters the buttock through the greater sciatic foramen and then traverses the lesser sciatic foramen to enter the ischioanal fossa. The artery runs forwards along the lateral wall of the fossa in the pudendal canal and gives off inferior rectal branches and posterior scrotal or labial branches. The artery continues above the perineal membrane, where it provides branches to the bulb of the penis or vestibule and crus of the penis or clitoris, and terminates by dividing into deep and dorsal arteries of the penis or clitoris. In the male, the dorsal artery passes below the pubic symphysis and continues along the dorsum of the penile shaft (Fig. 5.37), lateral to the deep dorsal vein, and gives branches to the erectile tissue of the corpus cavernosum. The deep artery pierces the perineal membrane and supplies the erectile tissue of the corpus cavernosum. In the female, there are comparable but smaller branches to the clitoris. The internal pudendal artery and its branches are accompanied by venae comitantes, which drain into the internal iliac vein.



Fig. 5.35 Coronal section through anal canal and ischioanal fossae. Anterior aspect.


Anal opening
Scrotum
Bulb of penis
Posterior scrotal nerve
Hamstring muscles
A
R
L
P
Ischial tuberosity
Inferior rectal nerve and artery
Deep, superficial and subcutaneous parts of external anal sphincter
Levator ani
Gluteus maximus
Anococcygeal raphe

Fig. 5.36 Oblique view of the anal triangle to show the parts of the external anal sphincter and the inferior rectal nerve and artery.


Dorsal nerve of penis
Levator ani (cut)
Internal pudendal artery
S
A
P
I
Pudendal nerve
Perineal nerve
Inferior rectal nerves
Suspensory ligament of penis
Deep dorsal vein
Dorsal artery
Superficial vein (cut)
Deep fascia of penis (cut)
Glans

Fig. 5.37 Left pudendal nerve, exposed by removal of the lateral wall of the pelvis.

Pudendal nerve

The pudendal nerve provides the principal innervation to the perineum. It arises from the sacral plexus (S2, S3 & S4) and accompanies the internal pudendal artery into the perineum. In the ischioanal fossa, the nerve divides into the dorsal nerve of the penis (or clitoris) and the perineal nerve (Fig. 5.37).

The perineal nerve supplies an inferior rectal branch to the anal canal and posterior scrotal or labial branches to the skin of the genitalia (Fig. 5.36). On reaching the anterior part of the perineum, the perineal nerve gives branches to all muscles in the superficial perineal pouch, as well as sensory branches to the urethra.

The dorsal nerve of the penis continues forwards with the internal pudendal artery above the perineal membrane and below the pubic symphysis. It runs along the dorsum of the penis, lateral to the dorsal artery (Fig. 5.39), and innervates the skin of the distal two-thirds of the organ. The dorsal nerve of the clitoris has a similar course and distribution.


Corpus cavernosum
Corpus spongiosum
Spermatic cord (cut)
Bulbo-spongiosus (cut)
Bulb
Ischio-cavernosus
Crus
Perineal membrane
Superficial transverse perineal muscle (cut)
A
R
L
P
Ischial ramus
External anal sphincter

Fig. 5.38 Root of penis. The right ischiocavernosus and bulbospongiosus muscles have been removed to expose the crus and the bulb of the penis.

Male External Genitalia

The male external genitalia comprise the scrotum and the penis. An account of the scrotum and its contents is given on pp 149–151. The penis consists of a shaft, which is free, and a root, which lies in the superficial perineal pouch, attached to the inferior surface of the perineal membrane.

Perineal membrane and pouches

The perineal membrane is a shelf of dense fascia spanning the triangular interval between the right and left ischial rami and inferior pubic rami (Fig. 5.34). The membrane has a long free posterior margin and a short anterior margin that is separated from the pubic symphysis by a small gap transmitting the deep dorsal vein of the penis. The central part of the membrane is pierced by the urethra and bulbourethral ducts.

At the root of the penis and around the neck of the scrotum, the membranous layer of perineal subcutaneous tissue attaches laterally to the ischial and pubic rami. Posteriorly, the fascia is anchored to the free edge of the perineal membrane. The space contained by the membranous layer of the penis and the scrotum is called the superficial perineal pouch. This pouch communicates with the subcutaneous tissues of the anterior abdominal wall but not with the ischioanal fossae, the thighs or pelvic cavity. If the spongy part of the urethra is ruptured, urine may escape into the superficial pouch (superficial extravasation of urine, p. 140).

On the pelvic aspect of the perineal membrane lie the external urethral sphincter and bulbourethral glands in a space often called the deep perineal pouch. The term urogenital diaphragm is a misnomer sometimes applied to the deep perineal pouch and its boundaries.



Fig. 5.39 'Step' dissection of the shaft of the penis to show the three corpora and the dorsal vessels.

Penis

The erectile tissue of the shaft of the penis consists of the paired corpora cavernosa, lying in apposition, and the midline corpus spongiosum.

The corpus spongiosum is uniform in diameter except at its extremity, where it expands into the glans (Fig. 5.19), whose prominent margin forms the corona of the penis. Proximally, the corpus spongiosum continues into the root of the penis to form the bulb, which is attached to the inferior surface of the perineal membrane (Fig. 5.38). The urethra pierces the perineal membrane, enters the bulb from above and curves downwards and forwards. It traverses the corpus spongiosum and glans (Fig. 5.19) and terminates at the external urethral meatus near the apex of the glans.

Dorsal to the corpus spongiosum are the paired corpora cavernosa (Fig. 5.39), which extend distally as far as the concave proximal surface of the glans. Proximally, the corpora cavernosa continue inferior to the pubic symphysis and diverge as the crura. Each crus tapers posteriorly and is attached to the inferior surface of the perineal membrane and the adjacent rami of the pubis and ischium (Figs 5.34 & 5.38).

Fascial layers and skin

The three corpora of the penis are enveloped by a sleeve of deep fascia, which also covers the dorsal vessels and nerves of the organ (Fig. 5.39). Proximally, the deep fascia is anchored to the front of the pubic symphysis by the suspensory ligament of the penis (Fig. 5.37), while distally it terminates at the corona by fusing with the corpora. Covering the deep fascia is the superficial fascia.

The subcutaneous tissue of the penis is membranous, devoid of fat and traversed by superficial nerves and vessels (Fig. 5.39). Proximally, it is continuous with the subcutaneous tissue of the anterior abdominal wall and can be traced around the scrotum, where it contains smooth muscle, the dartos.

The cutaneous covering of the penis is freely mobile except over the glans to which it is adherent. The skin is reflected distally beyond the corona over the glans to form the hood-like prepuce or foreskin. This is attached to the undersurface of the glans by a vascular fold, the frenulum. Removal of the foreskin (circumcision) is commonly performed for both medical and religious reasons.

Muscles

Surrounding the bulb of the penis are the paired bulbospongiosus muscles (Fig. 5.38). Their fibres attach to the perineal membrane and pass downwards and backwards to meet at a midline raphe and blend posteriorly with the external anal sphincter. The bulbospongiosus muscles contract during ejaculation and the terminal stages of micturition to compress the urethra and expel its contents.

Covering each crus is the ischiocavernosus muscle (Fig. 5.38). From the posterior end of each crus, a small superficial transverse perineal muscle runs medially to the penile bulb. All the penile muscles are innervated by the perineal branch of the pudendal nerve.

Vessels

The erectile tissues of the penis have a rich blood supply. Each internal pudendal artery (p. 241) provides branches to the bulb and to the corresponding crus before terminating as the dorsal and deep arteries. The deep artery traverses the length of the corpus cavernosum, while the artery to the bulb continues along the corpus spongiosum to reach the glans. Diseases affecting these arteries or their autonomic supply may lead to erectile dysfunction (impotence). The principal venous drainage is via the midline deep dorsal vein, which runs beneath the deep fascia (Fig. 5.39). This vein is accompanied by the dorsal arteries and passes inferior to the pubic symphysis into the pelvic cavity, where it terminates in the prostatic venous plexus (Fig. 5.21). From this plexus, blood drains into either the internal iliac veins or the internal pudendal veins.

Erection of the penis is controlled by parasympathetic nerves (the pelvic splanchnic nerves or nervi erigentes) from the sacral segments of the spinal cord. Stimulation of these nerves causes arterial dilatation and simultaneous venous constriction. This results in engorgement of the erectile tissues leading to enlargement and stiffening of the penis. Diseases affecting these arteries or their autonomic supply may lead to erectile dysfunction.

The skin of the penis and the front of the scrotum are supplied by the external pudendal branches of the femoral arteries. The superficial veins of the penis and the anterior part of the scrotum drain via the external pudendal veins, which are tributaries of the great saphenous vein (Fig. 6.11). The posterior part of the scrotum is supplied by posterior scrotal branches from the internal pudendal artery, and venous blood passes into the internal pudendal veins.

Cutaneous innervation

The pudendal nerve supplies most of the penis and scrotum via its dorsal and posterior scrotal branches. However, the anterior part of the scrotum and the proximal part of the shaft of the penis are innervated by the ilioinguinal nerve, which descends from the superficial inguinal ring (Fig. 4.21).

Lymphatic drainage

Lymph from the superficial tissues of the penis and scrotum passes to the superficial inguinal nodes, while that from the deeper tissues is conveyed via lymphatic vessels accompanying the internal pudendal artery and passes to the internal iliac nodes.

Female External Genitalia

Clitoris and bulbs of vestibule

The perineal membrane is thinner in the female than in the male and is pierced by both the vagina and the urethra. Attached to the inferior surface of the membrane is erectile tissue similar to that in the male, namely the crura of the clitoris and the bulbs of the vestibule covered by the thin ischiocavernosus and bulbospongiosus muscles, respectively (Figs 5.40 & 5.41). The right and left crura attach to the medial margins of the ischial and pubic rami. Passing forwards and medially they merge beneath the pubic symphysis to form the shaft of the clitoris. This turns downwards and backwards towards the urethral opening, and its tip is capped by the glans of the clitoris.

The paired bulbs of the vestibule surround the urethral and vaginal openings (Fig. 5.41). Anteriorly, they taper and fuse into a midline structure that terminates as the glans of the clitoris. The posterior end of each bulb is expanded and covers the greater vestibular (Bartholin's) gland. This gland is approximately 1 cm in diameter and drains into a minute duct, which opens into the vestibule lateral to the vaginal opening. The gland may be the site of cyst formation (Bartholin's cyst) or may become infected (Bartholin's abscess) requiring surgical intervention. Superficial transverse perineal muscles pass laterally from the bulbs of the vestibule to the ischial tuberosities.

Labia

The most superficial parts of the female external genitalia are the skin folds, the labia majora (Fig. 5.40). These meet anteriorly at the mons pubis. The mons is a pad of fat overlying the pubic symphysis and covering most of the clitoris. Between the labia majora lie the two labia minora, which become more prominent anteriorly. The labia minora fuse in the midline, forming two folds of skin around the glans of the clitoris. The hood-like anterior fold comprises the prepuce of the clitoris and the smaller posterior fold forms the frenulum. Posteriorly, the labia minora are united by a delicate fold, the fourchette, which is usually torn during vaginal delivery.

Vestibule

The labia minora enclose a cleft, the vestibule, into which the vagina and urethra open (Fig. 5.41). The vaginal opening (introitus) is an anteroposterior slit, usually surrounded by a fringe of skin, the hymen. The external urethral meatus lies approximately 1 cm anterior to the vaginal opening.

The term vulva is used to describe the mons pubis, the labia majora and minora, the clitoris and vestibule.

Cutaneous innervation and blood supply

The mons pubis and the anterior parts of the labia are innervated by the ilioinguinal nerves (Fig. 4.24). The posterior part of the vulva receives cutaneous innervation from the labial branches of the pudendal nerves, supplemented by branches of the posterior cutaneous nerves of the thighs and the perineal branches of the fourth sacral nerves. Anaesthetic injected near the ischial spines will produce pudendal nerve block, which is sometimes used during childbirth.

The skin and subcutaneous tissues are supplied by the internal pudendal artery and the superficial and deep external pudendal branches of the femoral artery. Most of the venous blood passes into the venae comitantes of the internal pudendal artery, but anteriorly some blood drains by external pudendal veins into the great saphenous vein. Lymph from the skin and superficial tissues, including the vestibule and lower vagina, passes to the superficial inguinal nodes (Fig. 6.11), while lymphatics from deeper structures follow the course of the arteries to reach the internal iliac nodes.


Mons pubis
Labia minora
Labium majus
Perineal membrane
Posterior labial nerve
Anus
A
R
L
P
Body, tubercle and inferior ramus of pubis
Ischio-cavernosus
Bulbo-spongiosus
Ischial tuberosity and ramus
Levator ani
Inferior rectal nerve and vessels

Fig. 5.40 Superficial dissection of one side of the female perineum, showing the muscles and cutaneous nerves.


Ischio-cavernosus
Prepuce (cut)
Glans and shaft of clitoris
A
R
L
P
Body and inferior ramus of pubis
Crus
External urethral meatus
Bulb of vestibule (cut)
Perineal membrane
Greater vestibular gland
Vaginal opening
Bulbo-spongiosus

Fig. 5.41 Deeper dissection of the female perineum. The glans, shaft and left crus of the clitoris have been exposed. The left bulb of the vestibule has been cut to reveal the greater vestibular gland.

Exam Skills

Each of the incomplete statements below is followed by five suggested answers or completions. Decide which are true and which are false. The answers are supplied on p. 417.

1. The ovary:

a) receives its principal arterial supply from the internal iliac artery.
b) lies in the angle between the internal and external iliac vessels.
c) is attached by the mesovarium to the anterior surface of the broad ligament.
d) may lie in close proximity to the obturator nerve.
e) has a surface which is devoid of peritoneal covering.

2. Peritoneum in the female pelvis:

a) forms the round ligament of the uterus.
b) forms the mesovarium.
c) covers the posterior fornix of the vagina.
d) covers the anterior and lateral surfaces of the whole length of the rectum.
e) is in direct contact with the ureters.

3. The piriformis muscle:

a) attaches to the pelvic surface of the sacrum.
b) passes through the lesser sciatic foramen.
c) attaches to the greater trochanter of the femur.
d) has the pelvic plexus on its anterior surface.
e) is a medial rotator of the hip joint.

4. Concerning the lumbar and sacral plexus:

a) the obturator nerve carries fibres from spinal segments L2, L3 and L4.
b) the femoral nerve emerges from the anterior surface of the psoas major muscle.
c) the pudendal nerve provides the motor supply to the external anal sphincter.
d) sympathetic fibres leave the spinal cord in spinal nerves S2, S3 and S4.
e) the lumbosacral trunk carries fibres from spinal segments L4 and L5.

5. The uterus:

a) is supplied with blood by branches of the internal iliac artery.
b) is supported by the broad ligaments.
c) has most of its lymphatics draining into inguinal nodes.
d) is closely related to the ureters.
e) pierces the anterior wall of the vagina.

6. The obturator internus muscle:

a) attaches to the medial surface of the obturator membrane.
b) has a tendon that enters the gluteal region inferior to the ischial spine.
c) is innervated by the first and second lumbar nerves.
d) contributes to the lateral wall of the ischioanal (ischiorectal) fossa.
e) attaches to the lesser trochanter of the femur.

7. Branches of the internal iliac artery in the female include:

a) the superior gluteal artery.
b) the ovarian artery.
c) the uterine artery.
d) the superior vesical artery.
e) the superior rectal artery.

8. The prostate:

a) is surrounded by a plexus of veins.
b) lies within the deep perineal pouch (space).
c) is pierced by the ejaculatory ducts.
d) lies posteroinferior to the base of the bladder.
e) is innervated by branches from the pudendal nerves.

9. The urinary bladder in the female:

a) has peritoneum on its anterior surface.
b) has the urachus attached to its apex.
c) has a rich parasympathetic nerve supply.
d) is drained by internal iliac lymph nodes.
e) is closely related to the body of the uterus.

10. The bulb of the penis:

a) is attached to the superior surface of the perineal membrane.
b) contains the penile urethra.
c) is compressed by the bulbospongiosus muscle.
d) receives blood from the deep artery of the penis.
e) continues as the corpus cavernosus.

11. The ductus (vas) deferens:

a) begins at the tail of the epididymis.
b) ascends within the spermatic cord.
c) passes above the ureter to reach the posterior aspect of the bladder.
d) terminates as an ampulla, which lies lateral to the seminal vesicle.
e) is innervated by the obturator nerve.

12. Regarding the hip bone:

a) the ischial spine gives attachment to the sacrospinous ligament.
b) the anterior superior iliac spine gives attachment to the inguinal ligament.
c) the obturator foramen is traversed by the nerve to obturator internus.
d) articulates with the sacrum by means of a synovial joint.
e) the lacunar ligament is attached to the pectineal line.

13. The uterine (fallopian) tube:

a) runs within the free border of the broad ligament of the uterus.
b) receives some of its arterial supply from the ovarian artery.
c) has a lumen which is narrowest where it pierces the uterine wall.
d) is closely related to the ureter.
e) opens directly into the peritoneal cavity.

14. The parasympathetic nerves of the pelvis:

a) arise from S2, S3 and S4 spinal cord segments.
b) ascend through the hypogastric plexus to supply the sigmoid colon.
c) are involved in the micturition reflex.
d) carry the nervous impulse responsible for ejaculation.
e) innervate the rectum.

15. The greater vestibular gland:

a) lies in the deep perineal pouch.
b) has a duct which opens into the vestibule of the vagina.
c) is closely related to the bulb of the vestibule.
d) is covered by bulbospongiosus.
e) lies in the labium majus.

16. Rupture of the penile bulbar urethra gives rise to extravasation of urine into:

a) the subcutaneous tissue of the scrotum.
b) the subcutaneous tissue of the penis.
c) the subcutaneous tissue of the thigh.
d) the subcutaneous tissue of the lower anterior abdominal wall.
e) the ischioanal (ischiorectal) fossa.

Clinical Case Skills

The answers are supplied on p. 419.

Case Study 1

A 30-year-old woman went into labour at the end of her first pregnancy and was admitted to an obstetric unit. For the first few hours, she was provided with pain relief by injections of analgesic and the inhalation of an oxygen/nitrous oxide mixture. But after 10 hours of uterine contraction it was decided she was making insufficient progress and the baby should be delivered by forceps. The obstetrician told her he was going to anaesthetize her birth canal by means of two injections and he proceeded to carry out bilateral pudendal blocks. Using a special needle, he palpated for features of the patient's bony pelvis from within the vagina in order to place the anaesthetic fluid near the pudendal nerves.

Questions:

1. What cutaneous structures does the pudendal nerve innervate?
2. What bony features did the obstetrician palpate?

Case Study 2

A 25-year-old woman was brought to her family doctor one morning because she had woken up feeling weak and had fainted soon after getting up. She had had a poor night's sleep because of vague lower abdominal pains. The doctor could find very little when he examined her abdomen apart from suprapubic tenderness on the right side. However, he was worried about her and arranged for admission into hospital. There she was given an intravenous drip and closely observed. A gynaecologist examined her and performed a vaginal examination. He asked her whether she had any pain in her neck or shoulders. Three hours after admission she had an emergency operation. The right uterine tube was found to contain a pregnancy which had ruptured. This was removed, as was a large volume of blood and clot in the peritoneal cavity. A blood transfusion was given.

Questions:

1. Explain the abdominal tenderness noted by the family doctor.
2. What might the gynaecologist have noted during the vaginal examination?
3. Why did the gynaecologist ask about pain in the neck and shoulders?

Case Study 3

A 30-year-old woman with three children, aged 6 years, 3 years and 4 months, complained of incontinence of urine when she laughed. Only a small amount of urine escaped on each occasion but it was distressing to her. Questioning revealed that she also passed urine involuntarily when coughing or when lifting the baby. She was worried she might need an operation. After excluding an infection in the bladder, her doctor referred her to a nurse who specialized in incontinence, to see whether nonoperative treatment might be successful. The nurse told the patient that exercises may help solve the problem. She explained how to do the exercises and encouraged her to perform them several times a day.

Questions:

1. In terms of physics and anatomy what makes any person of either sex continent of urine?
2. What are the most important structures contributing to urinary continence in women?
3. Why are women rather prone to this complaint?
4. Which nerves stimulate contraction of the smooth muscle of the bladder wall?

Case Study 4

A 60-year-old man consulted his doctor because he had noticed blood in his stools. The doctor suspected cancer of the colon or rectum and proceeded to examine his neck, chest and abdomen. He did a rectal examination and referred the man to a surgeon for a further opinion. The specialist did a similar examination, carefully percussed the abdomen and ordered a number of investigations, including a chest radiograph, blood tests for liver function, sigmoidoscopy and barium enema.

Questions:

1. Why did the doctor examine the man's neck?
2. Why did the surgeon percuss the abdomen?
3. Rectal cancer can invade any structure directly related to the rectum in both sexes. Which structures could become involved in this way?

Observation Skills

Identify the structures indicated. The answers are supplied at the foot of the page.



Fig. 5.42 Transverse CT image at the level of the pubic symphysis. (Compare Fig. 5.44.)



Fig. 5.43 Transverse CT image at the level of the pubic symphysis. (Compare Fig. 5.46.)

Answers:

Fig. 5.42 1 = femoral artery; 2 = femoral vein; 3 = pubic symphysis; 4 = pectineus; 5 = urinary bladder (distended); 6 = obturator externus; 7 = obturator internus; 8 = uterine tube; 9 = rectum (distended); 10 = coccyx; 11 = gluteus maximus; 12 = fundus of uterus.

Answers:

Fig. 5.43 1 = obturator internus; 2 = pubic symphysis; 3 = pectineus; 4 = femoral vein; 5 = femoral artery; 6 = acetabular fossa; 7 = prostate (enlarged); 8 = anal canal; 9 = coccyx; 10 = gluteus maximus.



Fig. 5.44 Transverse section just superior to the level of the pubic symphysis. Inferior aspect. (Compare Fig. 5.42.)



Fig. 5.45 Transverse section at the level of the ischiopubic rami. Inferior aspect.

Answers:

Fig. 5.44 1 = femoral nerve; 2 = femoral artery; 3 = femoral vein; 4 = vagina; 5 = neck of bladder; 6 = levator ani; 7 = pectineus; 8 = gluteus maximus; 9 = ischioanal fossa; 10 = anal canal; 11 = coccyx; 12 = obturator internus.

Answers:

Fig. 5.45 1 = tensor fasciae latae; 2 = rectus femoris; 3 = sartorius; 4 = ischiopubic ramus; 5 = crus of clitoris; 6 = adductor muscles; 7 = shaft of femur; 8 = gluteus maximus; 9 = tendons of hamstring muscles; 10 = urethra; 11 = vagina; 12 = sciatic nerve; 13 = vastus lateralis.



Fig. 5.46 Transverse section at the level of the pubic symphysis. Inferior aspect. (Compare Fig. 5.43.)



Fig. 5.47 Transverse section at the level of the ischiopubic rami. Inferior aspect.

Answers:

Fig. 5.46 1 = obturator internus; 2 = femoral vein; 3 = spermatic cord; 4 = neck of bladder; 5 = pubis; 6 = pectineus; 7 = head of femur; 8 = greater trochanter; 9 = ischial tuberosity; 10 = levator ani; 11 = rectum (distended); 12 = ischioanal fossa; 13 = gluteus maximus.

Answers:

Fig. 5.47 1 = tensor fasciae latae; 2 = femur; 3 = adductor muscles; 4 = crus of penis; 5 = corpora cavernosa; 6 = spermatic cord; 7 = sciatic nerve; 8 = bulb of penis; 9 = levator ani; 10 = anal canal; 11 = ischiopubic ramus; 12 = gluteus maximus; 13 = tendons of hamstring muscles.

Chapter 6

LOWER LIMB

Introduction 254
Anterior Compartment of the Thigh 259
  Subcutaneous tissue (superficial fascia) 259
  Fascia lata 260
  Muscles 260
  Femoral triangle 262
  Adductor (subsartorial) canal 262
  Femoral vessels 262
  Femoral nerve 262
  Deep inguinal lymph nodes 263
Medial Compartment of the Thigh 264
  Muscles 264
  Obturator nerve 266
  Vessels 266
Gluteal Compartment 267
  Gluteus maximus 267
  Tensor fasciae latae 269
  Structures deep to gluteus maximus 269
  Short muscles of the buttock 271
  Cruciate arterial anastomosis 271
Posterior Compartment of the Thigh 272
  Hamstring muscles 272
  Sciatic nerve 273
  Posterior cutaneous nerve of thigh 273
  Profunda femoris artery 274
Popliteal Fossa 274
  Roof 274
  Walls 274
  Contents 274
  Floor 275
  Popliteus 275
Posterior Compartment of the Leg 276
  Superficial structures and deep fascia 276
  Superficial muscles 277
  Neurovascular structures 278
  Deep muscles 279
Sole of the Foot 280
  Plantar aponeurosis 280
  Muscles and tendons 281
  Blood supply 285
  Nerve supply 285
Anterior and Lateral Compartments of the Leg and Dorsum of the Foot 286
  Anterior compartment of leg and dorsum of foot 286
  Lateral compartment of leg 290
Hip Joint 292
  Articular surfaces 292
  Capsule 292
  Ligaments 293
  Synovial membrane and bursae 294
  Movements 295
  Stability 295
  Relations 295
  Blood supply 295
  Nerve supply 295
Knee Joint 296
  Articular surfaces 296
  Capsule 297
  Collateral ligaments 298
  Intracapsular ligaments 298
  Menisci 299
  Infrapatellar fat pad 299
  Synovial membrane and bursae 299
  Popliteus 299
  Movements 300
  Stability 300
  Innervation 300
  Blood supply 300
Tibiofibular Joints 301
Ankle Joint 302
  Capsule and synovial membrane 302
  Ligaments 302
  Movements 304
  Stability 304
  Blood and nerve supply 305
  Relations 305
Joints of the Foot 306
  Tarsal joints 306
  Tarsometatarsal and intermetatarsal joints 307
  Metatarsophalangeal and interphalangeal joints 308
Arches of the Foot 309
  Stability 310
Exam Skills 312
Clinical Case Skills 313
Observation Skills 315

Introduction

The lower limb supports the body during standing and locomotion. The hip (coxal) bone (Fig. 6.1) provides attachment for muscles of the buttock and thigh, which link the limb to the trunk. The hip joint, between the acetabulum of the hip bone and the head of the femur, is multiaxial and provides versatility of movement.

The femur (Fig. 6.1) is surrounded by the muscles of the thigh and buttock. Its lower end with the patella and upper end of the tibia form the knee joint, a hinge joint. The tibia and fibula, surrounded by the leg muscles, form at their lower ends a socket, which articulates with the talus at the ankle joint, also a hinge.

The foot contains three groups of bones: the tarsals posteriorly, the metatarsals more anteriorly and the phalanges within the toes. The skeleton of the foot is adapted for bipedal standing and walking.

The limb is covered by skin, subcutaneous tissue containing vessels and nerves and by deep fascia. Intermuscular septa separate the muscles into different compartments (Figs 6.2 & 6.3). Each compartment contains muscles with common actions and is supplied by a neurovascular bundle. The thigh has anterior, posterior and medial compartments, whereas the leg has anterior, posterior and lateral compartments. The foot has only two: the dorsum and the sole.

The principal vessels and nerves enter the limb from the abdomen or pelvis by three different routes (Fig. 6.4): posterior to the inguinal ligament from the abdomen to the anterior compartment of the thigh; through the obturator canal between the pelvis and the medial compartment of the thigh; via the greater sciatic foramen, where the pelvis communicates with the gluteal region.



Fig. 6.1 The skeleton of the lower limb.


la P
A m
Profunda femoris vessels
Femur
Deep fascia (fascia lata)
Superficial fascia
Sciatic nerve and accompanying artery
Great saphenous vein
Femoral vein and artery
Anterior compartment
Posterior compartment
Medial compartment

Fig. 6.2 'Step' dissection through the midthigh, showing the relation of the compartments.


A
m la
P
Interosseous membrane
Peroneal intermuscular septa
Fibula
Deep fascia
Superficial fascia
Tibia
Neuro-vascular bundle
Short saphenous vein
Lateral compart-ment
Posterior compart-ment
Anterior compart-ment

Fig. 6.3 'Step' dissection through the midcalf, showing the relationships of the compartments.


S
P A
I
Iliac crest
Inguinal ligament
Aceta-bulum
Pubic tubercle
Ischial tuberosity
Femoral nerve and vessels via subinguinal space
Sciatic and gluteal nerves and vessels via greater sciatic foramen
Obturator nerve and vessels via obturator canal
Sacrotuberous ligament
Sacrospinous ligament
Obturator membrane

Fig. 6.4 Sites of access of the principal nerves and vessels from the abdomen and pelvis into the root of the lower limb.

Superior and inferior gluteal arteries from the internal iliac artery supply the gluteal region. However, the main supply to the limb is provided by the continuation of the external iliac artery, the femoral artery (Fig. 6.5). This traverses the anterior compartment of the thigh and passes behind the knee to become the popliteal artery, which divides into anterior and posterior tibial branches. The anterior tibial artery passes into the anterior compartment of the leg and continues onto the dorsum of the foot as the dorsalis pedis artery. The posterior tibial artery traverses the posterior compartment of the leg and divides into medial and lateral plantar arteries which supply the sole (plantar compartment) of the foot. Anastomoses occur between arteries in the sole and on the dorsum of the foot.

The superficial and deep veins are linked by communicating (perforating) veins. The superficial veins arise in the foot from the dorsal venous arch (Fig. 6.6). Medially, the great saphenous vein ascends the leg and thigh and drains into the femoral vein just below the inguinal ligament. From the lateral side of the foot the short saphenous vein passes behind the ankle and across the calf to enter the popliteal vein. Deep veins begin distally as venae comitantes, which unite to form the popliteal vein (Fig. 6.6). This becomes the femoral vein in the thigh and continues deep to the


Aorta
Common iliac
Superior and inferior gluteal
External iliac
Inguinal ligament
Lateral and medial circumflex femoral
Profunda femoris with perforating branches
Internal iliac
Obturator
Femoral
Popliteal
Posterior tibial
Anterior tibial
Fibular
Arteries passing behind skeletal structures
Lateral plantar
Plantar arch
Dorsalis pedis
Medial plantar
S
la
m
I

Fig. 6.5 Principal arteries of the lower limb.


Inferior vena cava
Common iliac
External iliac
Femoral
Profunda femoris
Internal iliac
Great saphenous
Popliteal
Venae comitantes of posterior and anterior tibial arteries
Small saphenous
Superficial
Deep
Veins passing behind skeletal structures
Dorsal venous arch
S
la
m
I

Fig. 6.6 Veins of the lower limb.

inguinal ligament as the external iliac vein. Gluteal veins accompany the corresponding arteries and drain into the internal iliac vein.

There are both superficial and deep lymphatics. The superficial lymphatics accompany the superficial veins. Those with the great saphenous vein terminate in superficial inguinal nodes (Fig. 6.7), which drain into deep inguinal nodes. Lymphatics following the short saphenous vein drain into nodes in the popliteal fossa. The deep lymphatics accompany arteries in the muscle compartments. Those from the leg and foot drain into the popliteal nodes whence lymphatics ascend with the femoral artery to the deep inguinal nodes whose efferents pass to the external iliac group.

The nerves of the lower limb are derived from the lumbar and sacral plexuses. The femoral nerve supplies the anterior compartment of the thigh, while the obturator nerve innervates the medial compartment (Fig. 6.8). The sciatic nerve and its branches supply the posterior compartment of the thigh and all compartments of the leg and foot.


External iliac nodes
Superficial inguinal nodes
Deep inguinal nodes
Popliteal nodes
Direction of lymph flow
Superficial lymphatics
Deep lymphatics
S
la
m
I

Fig. 6.7 Lymphatics and lymph nodes of the lower limb.


Femoral
Sciatic
Obturator
Tibial
Common fibular
Deep and superficial fibular
Nerves passing behind skeletal structures
Lateral and medial plantar
S
la
m
I

Fig. 6.8 Principal nerves of the lower limb.

Cutaneous nerves (Fig. 6.9) supply areas of skin which vary between individuals. The territories supplied by adjacent nerves overlap and therefore damage to a single nerve usually produces anaesthesia confined to the central part of the area supplied. The dermatome distribution is shown in Figure 6.10. There is some overlap of dermatomes except along the axial lines. Table 6.1 shows lower limb myotomes and reflexes. There is a regular pattern. One pair of spinal nerves control a particular movement and the subsequent pair the opposite movement. Control of movements changes by one segment progressively down the limb.


S
la
m
I
L1, L2 and L3
T12 and L1
S1, S2 and S3
Femoral branch of genitofemoral nerve
Ilioinguinal nerve
Obturator nerve
Posterior cutaneous nerve of thigh (sacral plexus)
Cutaneous nerves of thigh:
Lateral
Intermediate
Medial
Lateral cutaneous nerve of calf
Saphenous nerve
Sural nerve
Superficial and deep fibular nerves
Lateral and medial plantar nerves
Branches of posterior rami
Lateral cutaneous branches of spinal nerves
Branches of sciatic nerve
Branches of femoral nerve
Other branches from lumbar plexus

Fig. 6.9 Areas of distribution of cutaneous nerves in the lower limb.


S
la
m
I
S4
S3
L1
L2
S2
L3
L4
L5
S1

Fig. 6.10 The dermatomes of the lower limb.

Table 6.1 Segmental innervation for lower limb movements

Hip (coxal joint)		
Action	Flexion	Extension
Spinal segments	L2, L3	L4, L5
Knee (genu)		
Action	Extension	Flexion
Spinal segments	L3, L4	L5, S1
Reflex	Quadriceps (knee) jerk	–
Ankle (talocrural joint)		
Action	Dorsiflexion	Plantarflexion
Spinal segments	L4, L5	S1, S2
Reflex	–	Gastrocnemius (ankle) jerk
Subtalar joint (talocalcaneonavicular joint)		
Action	Inversion	Eversion
Spinal segments	L4	L5 and S1

L, lumbar; S, sacral.

Anterior Compartment of the Thigh

The anterior compartment is the largest in the thigh, occupying the region between the inguinal ligament and the knee. Lateral and anteromedial intermuscular septa separate the contents from the posterior (hamstring) and medial (adductor) compartments, respectively (Fig. 6.2). The anterior compartment (Fig. 6.12) contains quadriceps femoris, sartorius and the tendon of iliopsoas, and is innervated by the femoral nerve. The femoral artery and vein, the principal vessels of the lower limb, traverse the compartment and leave via the opening in adductor magnus to gain the popliteal fossa.

Subcutaneous tissue (superficial fascia)

The subcutaneous tissue contains the great (long) saphenous vein and its tributaries with their accompanying arteries, superficial inguinal lymph nodes and cutaneous nerves. The great saphenous vein ascends on the medial side of the thigh (Fig. 6.11) and passes through the saphenous opening in the fascia lata to empty into the femoral vein. The great saphenous vein drains the superficial tissues of the entire limb except the lateral side of the leg and foot. Near its termination, the vein receives tributaries, which drain the buttock, the perineum and the abdominal wall below the umbilicus. These tributaries are accompanied by corresponding branches of the femoral artery.

The superficial inguinal lymph nodes, often palpable in the living, lie just distal and parallel to the inguinal ligament and adjacent to the termination of the great saphenous vein (Fig. 6.11). These nodes receive lymph from the same superficial tissues as those drained by the great saphenous vein and its tributaries. Efferent lymphatics from the superficial nodes pass through the fascia lata and drain into the


S
la
m
I
Superficial circumflex iliac vein
Superficial epigastric vein
Superficial inguinal lymph nodes
Great saphenous vein
Femoral vein
Superficial external pudendal vein

Fig. 6.11 Great saphenous vein, its tributaries and the superficial inguinal lymph nodes lying in subcutaneous tissue.


S
la
m
I
Iliopsoas
Tensor fasciae latae
Pectineus
Sartorius
Adductor longus
Rectus femoris
Gracilis
Vastus lateralis and medialis
Iliotibial tract

Fig. 6.12 Muscles of the anterior compartment of thigh after removal of the skin and fascia lata.

deep inguinal nodes within the femoral triangle and femoral canal, where nodes are a focal point in lymphatic drainage of the lower limb (p. 257).

The lateral cutaneous nerve of the thigh (L2 & L3) (Fig. 6.17) pierces the inguinal ligament close to the anterior superior iliac spine, where it may become entrapped, causing pain in the thigh (meralgia paraesthetica). It supplies skin as far as the knee. The intermediate and medial cutaneous nerves of the thigh arise from the femoral nerve and supply the anterior and medial surfaces of the thigh. Usually, the obturator nerve gives a cutaneous supply to the medial side of the thigh. The femoral branch of the genitofemoral nerve (L1 & L2) passes beneath the inguinal ligament to supply skin over the femoral triangle, and the ilioinguinal nerve emerges through the superficial inguinal ring to supply the adjacent medial aspect of the thigh.

Fascia lata

The fascia lata (deep fascia) completely invests the thigh, providing attachment for muscles and associated intermuscular septa in the anterior compartment. It attaches superiorly to the inguinal ligament and iliac crest, and inferiorly is continuous with the deep fascia of the leg. Below and lateral to the pubic tubercle is the saphenous opening, which transmits the terminal part of the long saphenous vein.

Over the lateral aspect of the thigh, the fascia lata is particularly thick, forming the iliotibial tract. Gluteus maximus and tensor fasciae latae are attached to its upper part (Fig. 6.30).

Muscles

Quadriceps femoris

The four parts of quadriceps femoris, namely rectus femoris, vastus lateralis, vastus intermedius and vastus medialis, cover the front and sides of the femur (Figs 6.12, 6.13 & 6.14). Rectus femoris is attached by a straight head to the anterior inferior iliac spine and by a reflected head to the ilium above the acetabulum.

Vastus lateralis attaches to the intertrochanteric line, the lateral lip of the linea aspera and the lateral supracondylar ridge of the femur (Figs 6.15 & 6.16). Vastus intermedius attaches to the upper two-thirds of the anterior and lateral surfaces of the femoral shaft, while vastus medialis anchors to the spiral line and medial lip of the linea aspera. Distally, these four muscles form a common tendon, which attaches to the upper border (base) of the patella. From the lower border (apex) of the patella, the tendon continues as the patellar ligament (Fig. 6.75) to attach to the tibial tubercle.

Quadriceps femoris is a powerful antigravity muscle, extending the knee joint during standing, walking and running. In addition, rectus femoris flexes the hip. The lower fibres of vastus medialis stabilize the position of the patella (p. 300). Quadriceps femoris is supplied by branches of the femoral nerve.

Sartorius

This strap-like muscle is attached proximally to the anterior superior iliac spine and descends obliquely across the thigh (Fig. 6.12), crosses the posteromedial side of the knee and, with gracilis and semitendinosus, attaches to the upper end of the subcutaneous surface of the tibia (Fig. 6.79). Sartorius flexes and laterally rotates the hip and flexes the knee. It is supplied by the femoral nerve.



Fig. 6.13 Quadriceps femoris. Vastus intermedius is partially revealed by removal of rectus femoris. Pectineus and adductors longus and brevis have been excised.


Rectus femoris
Vastus intermedius
Femur
Vastus lateralis
Perforating branches of profunda femoris artery and vein
Common fibular and tibial branches of sciatic nerve
Semitendinosus and biceps
A
la
m
P
Vastus medialis
Sartorius
Femoral artery with venae comitantes
Great saphenous vein
Adductor longus
Gracilis
Adductor magnus
Semimembranosus

Fig. 6.14 Transverse section through the thigh to show the adductor canal (pink) and components of quadriceps femoris. Inferior aspect.


Quadrate tubercle
Lesser trochanter
Gluteal tuberosity
Nutrient foramen
Lateral and medial lips of linea aspera
Lateral and medial supra-condylar line
Inter-condylar notch
Lateral and medial condyles
S
m
la
I
Vastus medialis
Vastus intermedius
Vastus lateralis

Fig. 6.15 Femoral attachments (posterior view) of the vasti muscles.


Greater trochanter
Fovea capitis
Head and neck of femur
Inter-trochanteric line
Lesser trochanter
Shaft
Adductor tubercle
S
la
m
I
Patellar surface
Vastus medialis
Vastus intermedius
Vastus lateralis

Fig. 6.16 Femoral attachments (anterior view) of the vasti muscles.

Femoral triangle

The femoral triangle occupies the upper medial part of the anterior compartment of the thigh. Its upper boundary is the inguinal ligament; its lateral limit is the medial border of sartorius and its medial boundary is the medial border of adductor longus (some authors use the lateral border in their definition). The roof is fascia lata and the floor comprises iliopsoas, pectineus and adductor longus (Fig. 6.17). The triangle contains the femoral vessels and nerve, and the deep inguinal lymph nodes.

Adductor (subsartorial) canal

This canal is an intermuscular space linking the femoral triangle with the popliteal fossa. Triangular in cross-section, it lies beneath sartorius, occupying the groove between vastus medialis and adductor longus, and at its lower end adductor magnus (Fig. 6.14). Through the canal run the femoral artery and vein and nerve to vastus medialis and the saphenous nerve (Fig. 6.18).

Femoral vessels

The femoral artery, a continuation of the external iliac, is the main artery of the lower limb. It enters the anterior compartment behind the midpoint of the inguinal ligament where it is relatively superficial, easily palpable and accessible for catheterization to perform arteriograms. It is also vulnerable to penetrating or stab wounds. It descends through the femoral triangle (Fig. 6.19) and the adductor canal and continues through the opening in adductor magnus as the popliteal artery (p. 274).

The femoral artery or its main branches supplies all three compartments of the thigh. Subcutaneous branches of the artery traverse the saphenous opening or pierce the fascia lata to accompany the superficial veins in the groin (Fig. 6.11). The largest deep branch is the profunda femoris artery (Fig. 6.20), which arises from the posterolateral aspect of the femoral artery about 4 cm below the inguinal ligament and runs distally behind the femoral artery, leaving the triangle by passing between pectineus and adductor longus. The profunda femoris and its perforating branches pass through the adductor muscles and contribute to the anastomosis in the posterior compartment of the thigh. One of the perforating arteries gives a large nutrient branch to the femur.





Fig. 6.17 Boundaries and floor of the femoral triangle.

Close to its origin, the profunda femoris artery usually gives medial and lateral circumflex femoral branches (Fig. 6.20). The medial circumflex artery winds round the medial aspect of the femur between iliopsoas and pectineus to join the cruciate anastomosis (p. 271), and the lateral circumflex artery encircles the femur, passing laterally deep to sartorius and rectus femoris.

The femoral vein is the continuation of the popliteal vein at the opening in adductor magnus. In the adductor canal, it lies behind the femoral artery and continues through the femoral triangle, lying medial to the artery (Fig. 6.19). Passing deep to the inguinal ligament the femoral vein becomes the external iliac vein. Tributaries of the femoral vein, except the great saphenous vein, correspond to the branches of the femoral artery.

Femoral sheath

The femoral artery and vein are invested in a thick fascial sleeve, the femoral sheath, derived from the transversalis and iliac fasciae. The sheath passes deep to the inguinal ligament and tapers inferiorly, blending with the adventitia of the vessels about 2.5 cm distal to the ligament.

Two vertical septa divide the sheath into three compartments. The femoral artery lies laterally, while the femoral vein occupies the intermediate compartment. The medial compartment is called the femoral canal (Fig. 6.20) and contains fat and lymph nodes. The upper limit of the femoral canal is the femoral ring (Fig. 4.23), an aperture bounded in front by the inguinal ligament and behind by the superior ramus of the pubis, while laterally lies the femoral vein and medially the lacunar ligament. A femoral hernia descends through the femoral ring to enter the femoral canal.

Femoral nerve

The femoral nerve (L2, L3 & L4) enters the thigh beneath the inguinal ligament, lying on iliopsoas lateral to the femoral sheath (Fig. 6.19). After a brief course in the femoral triangle, it divides into several superficial and deep branches. The superficial branches are the intermediate and medial cutaneous nerves of the thigh and the nerves to sartorius and pectineus. The deep branches include the nerves supplying rectus femoris and the vasti, and the saphenous nerve, which enters the adductor canal.

Deep inguinal lymph nodes

The deep inguinal lymph nodes lie in the femoral triangle medial to the femoral vein. They receive lymph from the superficial inguinal nodes and from all parts of the limb deep to the investing fascia. They also drain the glans of the penis or clitoris. Efferent vessels pass proximally through the femoral canal to reach the external iliac nodes.


Superficial inguinal ring
Femoral nerve
Lateral circumflex femoral artery
Sartorius
Nerve to vastus medialis
Adductor longus
Femoral vein
Vastus medialis
Saphenous nerve
Adductor magnus
S
la
m
I

Fig. 6.18 Contents and boundaries of the adductor canal, exposed by displacement of sartorius laterally.


Inguinal ligament
Deep circumflex iliac artery
Femoral nerve and cutaneous branch
Femoral canal
Femoral vein and artery
Pectineus
Branch to vasti
Great saphenous vein (cut)
Branches to sartorius
Nerve to vastus medialis
Saphenous nerve
Lateral cutaneous nerve of thigh
Medial cutaneous nerve of thigh
S
la
m
I

Fig. 6.19 Contents of the femoral triangle exposed by removal of its roof (fascia lata). The deep inguinal lymph nodes lie within the femoral canal.


Femoral canal
Femoral nerve (cut)
Lateral and medial circumflex femoral arteries
Femoral artery and vein (cut)
Profunda femoris artery and vein
Vastus medialis
Adductor longus
Femoral vein and artery (cut)
Saphenous nerve (cut)
S
la
m
I

Fig. 6.20 Profunda femoris vessels seen after removal of segments of the femoral artery and vein.

Medial Compartment of the Thigh

The medial compartment of the thigh is wedge-shaped and lies between the anterior and posterior compartments. It contains pectineus, adductors longus, brevis and magnus, gracilis and obturator externus. The obturator nerve and vessels and the profunda femoris vessels, together with their perforating branches, supply the compartment.

Muscles

The muscles are arranged in three layers. The anterior layer consists of pectineus, adductor longus and gracilis, from lateral to medial (Fig. 6.21). Deep to these, forming the intermediate layer, is adductor brevis (Figs 6.22 & 6.23). The posterior layer consists of obturator externus and adductor magnus (Figs 6.24 & 6.25). The proximal attachments of these muscles are to the outer surface of the bony pelvis between the superior pubic and ischial rami. In


Lateral cutaneous nerve of thigh
Iliopsoas
Pectineus
Sartorius
Adductor longus
Fascia lata
Gracilis
Adductor magnus
S
la
m
I

Fig. 6.21 Anterior layer of muscles of the medial compartment of thigh.


Pectineus
Adductor longus (cut)
Branches of anterior division of obturator nerve
Adductor brevis
Gracilis
Adductor longus (cut)
Adductor magnus
S
la
m
I

Fig. 6.22 Adductor brevis and branches of the anterior division of the obturator nerve, revealed by removal of part of adductor longus.

addition, obturator externus is attached to the obturator membrane.

The more anterior muscles have higher attachments than those of the deeper layers (Fig. 6.26). Distally, the muscles attach to the femur, except for gracilis (Fig. 6.79), which descends below the knee to gain the proximal end of the subcutaneous surface of the tibia in company with sartorius and semitendinosus. Obturator externus passes laterally below and behind the capsule of the hip joint (Figs 6.25 & 6.70) to the trochanteric fossa on the medial aspect of the greater trochanter. Pectineus and adductors longus, brevis and magnus slope downwards and laterally to attach in the region of the linea aspera, the sequence being related to the layer in which the muscle lies (Fig. 6.27). Adductor magnus has the longest attachment, extending from the gluteal tuberosity above to the adductor tubercle below.


Pectineus
Superior public ramus
Obturator externus
Posterior and anterior divisions of obturator nerve
Adductor brevis
Pectineus (cut)
Adductor magnus
Quadriceps femoris
Gracilis
S
la
m
I

Fig. 6.23 Division of the obturator nerve, revealed by removal of adductor longus and part of pectineus. In this specimen the posterior division lies in front of obturator externus but it usually lies behind or may fan through it.


Anterior division (cut)
Posterior division of obturator nerve
Obturator externus
Adductor magnus
Pectineus (cut)
Adductors longus and brevis (cut)
Femoral vein and artery (cut) traversing adductor opening
S
la
m
I

Fig. 6.24 Adductor magnus and the posterior division of the obturator nerve. Adductor brevis has been removed.


Iliopsoas (cut)
Psoas bursa
Capsule of hip joint
Anterior and posterior divisions of obturator nerve (cut)
Obturator externus
Adductor magnus (cut)
Iliopsoas (cut)
Sciatic nerve
Hamstring
Adductor magnus (cut)
S
la
m
I

Fig. 6.25 Obturator externus, completely revealed by removal of parts of iliopsoas and adductor magnus.

All the muscles in the compartment, except obturator externus, adduct the hip joint. During walking they stabilize the femur, while the abductors of the hip prevent tilting of the pelvis (p. 270). In addition, pectineus and adductor longus are medial rotators and obturator externus a lateral rotator. Pectineus assists flexion at the hip joint and gracilis flexes and medially rotates the knee joint.

All the muscles in the medial compartment except pectineus are innervated by the obturator nerve. Pectineus usually has a supply from the femoral nerve but may also be supplied by the obturator nerve, and the ischial part of adductor magnus receives fibres from the tibial part of the sciatic nerve.

Obturator nerve

The obturator nerve gains the compartment through the obturator canal and promptly divides into anterior and posterior divisions (Fig. 6.23). The former passes anterior to obturator externus, while the posterior division usually pierces and supplies the muscle before emerging onto its surface. The two divisions then descend, respectively, anterior and posterior to adductor brevis. The anterior division supplies adductors longus and brevis and gracilis (Fig. 6.22), and gives sensory branches to the hip joint and to skin on the medial side of the thigh. The posterior division lies on and supplies adductor magnus (Fig. 6.24) and gives sensory branches, which accompany the femoral artery through the opening in adductor magnus to supply the knee joint. Since the obturator nerve innervates the hip and knee joints, disease in one joint may cause referred pain in the other. Pelvic pathology, including tumours pressing on the obturator nerve (pp 222, 234, 235) may also cause referred pain in the hip, knee and medial side of the thigh.

Vessels

The blood supply is derived from the profunda femoris artery and its perforating branches, supplemented by the obturator artery and other branches of the femoral artery. The obturator artery is small and forms an arterial circle around the margins of the obturator membrane, supplying the proximal parts of the muscles. An acetabular branch passes beneath the transverse acetabular ligament and accompanies the round ligament to the head of the femur. Venae comitantes accompanying the arteries in the compartment drain into the profunda femoris or internal iliac veins.


S
la
m
I
Iliopubic eminence
Superior pubic ramus
Anterior superior and anterior inferior iliac spines
Acetabulum
Acetabular notch
Ischial tuberosity
Pubic tubercle
Body of pubis
Obturator foramen
Inferior pubic ramus
Ischial ramus
Pectineus
Obturator externus
Gracilis
Adductor longus
Adductor brevis
Adductor magnus

Fig. 6.26 Attachments of the muscles of the medial compartment of the thigh to the hip bone.


Head and neck of femur
Trochanteric crest
Spiral line
Linea aspera
Popliteal surface
S
m
la
I
Pectineus
Adductor brevis
Adductor magnus
Adductor longus

Fig. 6.27 Femoral attachments of the muscles of the medial compartment of the thigh.

Gluteal Compartment

The gluteal region or buttock forms part of the root of the limb. It overlies the dorsum of the ilium, ischium and sacrum and is continuous proximally with the lower trunk and distally with the posterior compartment of the thigh. Three substantial muscles (gluteus maximus, medius and minimus), covered by deep fascia and a thick layer of subcutaneous fat, form the bulk of the buttock and account for its surface contour. The gluteal fold, a prominent surface feature, lies at the junction of the buttock and thigh.

Gluteus maximus

This very large trapezoidal muscle is the most superficial in the buttock. Its fibres slope downwards and laterally (Fig. 6.28) and its lower edge passes obliquely across the gluteal fold. Some of


Thoracolumbar fascia covering erector spinae
Iliotibial tract
Gluteus maximus
S
m
la
I
Attachment to gluteal tuberosity of femur
Iliotibial tract

Fig. 6.28 The attachments of gluteus maximus include the thoracolumbar fascia and the iliotibial tract.


S
P
A
I
Iliac crest
Gluteus maximus (reflected)
Gluteus medius
Superior gluteal artery
Inferior gluteal artery
Piriformis
Greater trochanter
Inferior gluteal nerve
Fascia lata (cut)
Sciatic nerve
Attachment of gluteus maximus to gluteal tuberosity
Posterior cutaneous nerve of thigh

Fig. 6.29 Reflection of gluteus maximus exposes gluteus medius and neurovascular structures.

the sensory nerves to the skin of the buttock penetrate the medial part of the muscle, while others emerge around its upper and lower borders. Proximally, the muscle has an extensive attachment: to the ilium behind the posterior gluteal line, to the lower part of the sacrum, to the coccyx, to the sacrotuberous ligament and to the thoracolumbar (lumbar) and gluteal fasciae. A synovial bursa is usually present where it crosses the ischial tuberosity. Distally, some of the deeper fibres are attached to the gluteal tuberosity of the femur (Fig. 6.29), but most of the muscle is attached through the iliotibial tract (Fig. 6.30) to the anterior surface of the lateral tibial condyle. The nerve supply is from the inferior gluteal nerve (L5, S1 & S2).


Tubercle of iliac crest
Fascia lata
Gluteus maximus
Tensor fasciae latae
Posterior cutaneous nerve of thigh
Iliotibial tract
S
P
A
I

Fig. 6.30 Attachment of gluteus maximus and tensor fasciae latae to the iliotibial tract.

Gluteus maximus is a strong extensor of the thigh, especially during running and climbing, and also produces abduction at the hip joint. As an antigravity muscle, it extends the trunk on the hip, and through the iliotibial tract, it extends and stabilizes the knee joint and the supporting limb during walking and standing.

Tensor fasciae latae

This small muscle is attached proximally to the ilium between the anterior superior iliac spine and iliac tubercle (Fig. 6.31) and distally to the anterior border of the iliotibial tract (Fig. 6.30), which it tenses. It is supplied by the superior gluteal nerve.

Structures deep to gluteus maximus

The arrangement of these structures is clarified by noting whether they enter the buttock above or below the piriformis muscle (Fig. 6.29), which itself enters via the greater sciatic foramen (Fig. 6.36).


Iliac crest
Posterior superior iliac spine
Inferior, anterior and posterior gluteal lines
Greater and lesser sciatic notches
Iliac tubercle
Anterior superior iliac spine
Acetabulum
Head and neck of femur
Greater trochanter
Ischial spine and tuberosity
S
P
A
I
Gluteus maximus
Gluteus medius
Gluteus minimus
Tensor fasciae latae

Fig. 6.31 Attachments of the gluteal muscles to the ilium and the greater trochanter.

Structures entering above piriformis

The superior gluteal nerve (L4, L5 & S1) arises within the pelvis from the lumbosacral plexus and enters the buttock through the greater sciatic foramen (Fig. 6.36), running laterally between gluteus medius and gluteus minimus (Fig. 6.32). It supplies both muscles and terminates in tensor fasciae latae.

The superior gluteal artery arises from the posterior aspect of the internal iliac artery. It enters the buttock accompanying the corresponding nerve and divides into a superficial branch, which supplies the overlying gluteus maximus (Fig. 6.29) and two deep branches, an upper and lower, which supply gluteus medius and minimus (Fig. 6.32). The deep branches also contribute to anastomoses around the greater trochanter and anterior superior iliac spine. The accompanying veins form an extensive plexus between the muscles and drain into the internal iliac vein.

Gluteus medius and minimus

These fan-shaped muscles lie superior to piriformis. Gluteus medius (Fig. 6.29) is attached proximally to the dorsum of the ilium between the posterior and anterior (middle) gluteal lines and to the gluteal fascia, which separates it from gluteus maximus. Distally, it is attached to the lateral surface of the greater trochanter. Gluteus minimus lies immediately deep to gluteus medius and attaches proximally to the dorsum of the ilium between the anterior and inferior gluteal lines (Fig. 6.31) and distally to the anterior surface of the greater trochanter (Fig. 6.32). Both are supplied by the superior gluteal nerve.

Although both gluteus medius and minimus medially rotate the femur at the hip joint, their importance is in abduction. During walking, gluteus medius and minimus of the supporting limb contract, pulling on the pelvis from their femoral attachments to prevent tilting of the pelvis towards the unsupported side. Failure of this mechanism is the basis of Trendelenburg's sign of hip instability with a dipping gait. It may result from a defective acetabulum (usually congenital) or loss of function in these muscles.

Structures entering below piriformis

These are: three nerves laterally, the sciatic nerve, nerve to quadratus femoris and posterior cutaneous nerve of thigh; medially the internal pudendal artery, pudendal nerve and nerve to obturator internus; and in intermediate position, the inferior gluteal nerve and vessels.

The sciatic nerve (Fig. 6.33), the largest nerve in the lower limb, arises from the spinal nerves L4, L5, S1, S2 and S3 and supplies the entire limb, except for the gluteal structures and the medial and anterior compartments of the thigh. It leaves the greater sciatic foramen about halfway between the posterior superior iliac spine and ischial tuberosity and curves laterally and downwards, crossing the midpoint between the ischial tuberosity and greater trochanter. Its location must be remembered to avoid damaging the nerve when making intramuscular injections into the buttock. The nerve is separated from the capsule of the hip joint by obturator internus and the gemelli, quadratus femoris and the upper border of adductor magnus (Fig. 6.33). A branch of the inferior gluteal artery accompanies the nerve.



Fig. 6.32 Reflection of gluteus medius reveals gluteus minimus and the superior gluteal artery and nerve entering the buttock above piriformis.

The nerve to quadratus femoris (L4, L5 & S1) lies deep to the sciatic nerve, obturator internus and the gemelli and supplies the inferior gemellus, quadratus femoris and the hip joint.

Superficial and medial to the sciatic nerve is the posterior cutaneous nerve of the thigh (Fig. 6.33), which arises from spinal nerves S1, S2 and S3. Within the buttock, its perineal branch runs forwards to supply the skin on the posterior part of the scrotum or labium majus. Other branches curl round the lower border of gluteus maximus to supply the skin over the buttock.

The inferior gluteal nerve and vessels occupy an intermediate position. The nerve turns immediately posteriorly to supply gluteus maximus.

The inferior gluteal artery, a branch of the internal iliac artery, accompanies the nerve and supplies gluteus maximus (Fig. 6.29) and the short lateral rotators of the hip joint and contributes to the trochanteric and cruciate anastomoses. Venae comitantes accompany the artery and drain into the internal iliac system.

The pudendal nerve (S2, S3 & S4), internal pudendal vessels, and nerve to obturator internus (L5, S1 & S2), also supplying the superior gemellus, enter beneath the medial part of piriformis (Fig. 6.33). Their course in the buttock is brief before turning forwards into the lesser sciatic foramen, crossing the sacrospinous ligament or ischial spine to enter the pudendal canal (Fig. 6.36 and p. 243).

Short muscles of the buttock

The short muscles of the buttock are, from above downwards, piriformis, obturator internus with the gemelli, and quadratus femoris (Fig. 6.33). Piriformis arises from the ventral surface of the sacrum (p. 235) and runs laterally through the greater sciatic foramen to converge on the medial border of the greater trochanter. It is innervated within the pelvis by spinal nerves L5, S1 and S2. Obturator internus attaches to the lateral wall of the pelvic cavity (Fig. 6.72), including the obturator membrane, and runs backwards towards the lesser sciatic foramen, where its tendon makes a right-angled turn to run laterally across the buttock to the medial aspect of the greater trochanter above the trochanteric fossa. The superior and inferior gemelli are small muscles arising from the upper and lower margins of the lesser sciatic notch to fuse with the obturator internus tendon.

Quadratus femoris attaches to the lateral margin of the ischial tuberosity and to the quadrate tubercle of the femur and the subjacent shaft. Being behind the hip joint, all the short muscles laterally rotate the hip.

Cruciate arterial anastomosis

The cruciate anastomosis lies at the lower border of quadratus femoris and receives contributions from above, the inferior gluteal artery; below, the first perforating artery; and on each side, the medial and lateral circumflex femoral arteries.


Inferior gluteal vessels and nerves
Nerve to quadratus femoris
Piriformis
Pudendal nerve
Nerve to obturator internus
Sacro-tuberous ligament
Internal pudendal artery
S
m
la
I
Obturator internus tendon and gemelli
Quadratus femoris
Adductor magnus
Posterior cutaneous nerve of thigh and perineal branches
Sciatic nerve

Fig. 6.33 Structures emerging below piriformis and the course and relations of the sciatic nerve.

Posterior Compartment of the Thigh

The posterior compartment is enclosed by the fascia lata (Fig. 6.34) and extends from the gluteal region above to the popliteal fossa below. It contains the posterior cutaneous nerve of thigh, hamstring muscles, sciatic nerve and terminal branches of the profunda femoris artery.

Hamstring muscles

These three muscles, semimembranosus, semitendinosus and biceps femoris (long head) (Fig. 6.35), attach proximally to the ischial tuberosity (Fig. 6.36) and distally to the upper end of the tibia or fibula and are innervated by the sciatic nerve. They span the entire length of the femur and act on two joints, the hip for extension and the knee for flexion. After flexion of the trunk, the hamstrings act as antigravity muscles by pulling on the ischial tuberosities, thus extending the trunk into an upright position at the hip. Tears of the hamstrings occur in sports involving jumping, running and kicking.

Semimembranosus

This muscle is attached to the upper and lateral parts of the ischial tuberosity by a wide, flat tendon, which is overlapped by the tendons of biceps and semitendinosus close to the tuberosity, and descends on the medial side of the popliteal fossa to its


S
m
la
I
Posterior cutaneous nerve of thigh
Perforating vein
'Window' cut in fascia lata
Anomalous small saphenous vein
Great saphenous vein

Fig. 6.34 Nerves and veins of the posterior compartment of thigh, seen through a 'window' cut in the fascia lata. This small saphenous vein continues proximally to terminate in the great saphenous vein.




Sciatic nerve
Attachment of gluteus maximus to gluteal tuberosity
Ischial tuberosity
Branches to hamstrings
Long head of biceps femoris
Semimembranosus
Branch to short head
Short head of biceps femoris
Semitendinosus
S
m
la
I

Fig. 6.35 Principal contents of the posterior compartment of thigh, seen after removal of deep fascia.

main attachment into a horizontal groove on the posteromedial aspect of the medial tibial condyle. Some of its fibres pass upwards and laterally behind the knee joint to form the oblique posterior ligament; others descend to reinforce the fascia over popliteus (Fig. 6.39).


Dorsum of ilium
Iliac crest
Greater trochanter
Intertrochanteric crest
Greater and lesser sciatic foramina
S
m
la
I
Dorsum of sacrum
Sacrotuberous and sacrospinous ligaments
Lesser trochanter
Gluteal tuberosity
Gluteus maximus
Biceps and semitendinosus
Semimembranosus
Quadratus femoris

Fig. 6.36 Posterior view of sacrum and bony pelvis showing sacrotuberous and sacrospinous ligaments with the greater and lesser sciatic foramina.

Semitendinosus

Proximally, semitendinosus is attached to the medial part of the ischial tuberosity. It descends on the medial side of the popliteal fossa, forming a narrow tendon, which overlies semimembranosus, and attaches to the medial surface of the upper end of the tibial shaft close to the attachments of sartorius and gracilis (Fig. 6.79). Besides contributing to the common actions of the hamstring group, semitendinosus and semimembranosus produce medial rotation of the leg at the knee.

Biceps femoris

This muscle has two heads. Proximally, the long head is attached to the medial part of the ischial tuberosity close to the semitendinosus and descends to the lateral side of the popliteal fossa, where it fuses with the short head, which originates from the lateral lip of the linea aspera and lateral supracondylar ridge of femur (Fig. 6.35). Inferiorly, the tendon of biceps is attached to the head of the fibula. In addition to the general actions of the hamstrings, biceps produce lateral rotation of the leg at the knee.

Sciatic nerve

The sciatic nerve emerges at the lower border of gluteus maximus lying just beneath the deep fascia, passes deep to the long head of biceps and descends in the midline of the limb. In the distal third of the thigh, it usually divides into two terminal branches, the tibial and common fibular (common peroneal) nerves, which continue into the popliteal fossa (Fig. 6.40). Division may occur more proximally in the thigh, within the buttock or even the pelvis. In the latter case, the common fibular nerve may pass through the piriformis where it may be compressed. Proximally, fibres from the medial (tibial) part of the sciatic nerve supply the hamstrings (Fig. 6.35) and the ischial head of adductor magnus. More distally, a branch from the lateral (common fibular) part of the nerve supplies the short head of biceps.

Posterior cutaneous nerve of thigh

The nerve enters the thigh superficial and slightly medial to the sciatic nerve and descends beneath the fascia lata to the upper part of the popliteal fossa (Fig. 6.37). Apart from branches arising near the lower border of gluteus maximus, the nerve gives sensory fibres to the skin on the back of the thigh, popliteal fossa and proximal part of leg.


Branches of posterior cutaneous nerve of thigh
S
m
la
I
Great saphenous vein
Deep fascia forming roof of fossa
Posterior cutaneous nerve of thigh
Small saphenous vein

Fig. 6.37 Removal of skin and subcutaneous tissue reveals the cutaneous nerves. The small saphenous vein and accompanying nerve pierce the roof of the popliteal fossa.


Semi-tendinosus
Sciatic nerve (cut)
S
m
la
I
Popliteal artery and vein (cut)
Semimembranosus
Biceps
Plantaris
Lateral and medial heads of gastrocnemius
Common fibular nerve (cut)

Fig. 6.38 Muscles forming the walls of the popliteal fossa.

Profunda femoris artery

Perforating branches of the profunda femoris artery penetrate adductor magnus and terminate in the posterior compartment. They anastomose with branches from the inferior gluteal artery above and the popliteal artery below.

Popliteal Fossa

The popliteal fossa is a diamond-shaped space behind the knee joint. It contains the principal blood vessels and nerves passing between the thigh and the leg. It has a roof, four walls and a floor.

Roof

The roof is formed by the investing layer of deep fascia. In the subcutaneous tissue overlying the roof are the posterior cutaneous nerve of the thigh, which continues into the proximal part of the leg, and the small saphenous vein (Fig. 6.37). The vein usually penetrates the roof to drain into the popliteal vein but may drain more proximally into the great saphenous vein (Fig. 6.34).

Walls

The walls overhang the fossa. Superiorly, they are formed by the diverging tendons of the hamstrings, namely semitendinosus and semimembranosus lying medially and biceps laterally. Inferiorly are the medial and lateral heads of gastrocnemius, which converge at the inferior angle (Fig. 6.38). Adjacent to the lateral head of gastrocnemius is the small plantaris muscle. On each side of the popliteal fossa the hamstring tendons overlap the heads of gastrocnemius, and between the medial head of gastrocnemius and semimembranosus there is frequently a bursa (Fig. 6.39).

Contents

The principal contents of the fossa are embedded in fat and comprise the popliteal artery and vein together with the two terminal branches of the sciatic nerve, the common fibular and tibial nerves (Fig. 6.40). These vessels and nerves are responsible for the blood and nerve supply of most of the leg and foot.

The popliteal artery lies deepest and is the continuation of the femoral artery from the thigh. It enters through the opening in adductor magnus and descends vertically on the floor of the fossa to the inferior angle, where it leaves beneath the fused heads of gastrocnemius. The artery is so deep that it is difficult to palpate unless the knee is flexed to relax the boundaries and roof of the fossa. The artery supplies the surrounding muscles and also forms a substantial plexus of articular branches anastomosing symmetrically around the knee joint (Fig. 1.27).

The popliteal vein lies superficial to the artery and is formed at the inferior angle of the fossa by the union of the venae comitantes that accompany the tibial arteries in the leg. It continues proximally with the artery through the opening in adductor magnus to enter the adductor canal and become the femoral vein.

The tibial and common fibular nerves (Fig. 6.40), entering the fossa from the posterior compartment of the thigh, lie just beneath the roof, superficial to the popliteal vessels. The tibial nerve enters from beneath the hamstrings and descends vertically, bisecting the fossa, and leaves beneath the gastrocnemius at the inferior angle of the fossa, where it enters the posterior compartment of the leg. The tibial nerve is mainly motor in its distribution, supplying gastrocnemius, plantaris, popliteus and soleus. All these branches arise within the fossa. The nerve also gives sensory branches to the knee joint and a large cutaneous branch, which passes into the calf to form the sural nerve. The common fibular nerve descends under cover of the tendon of biceps to reach the lateral angle of the fossa, where it enters the lateral (fibular or peroneal) compartment of the leg. Here it winds around the neck of the fibula where it is vulnerable to damage and compression, resulting in foot-drop. It supplies sensory branches to the knee joint and two cutaneous nerves, one to the lateral side of the calf and the other, the lateral sural cutaneous nerve, joining the sural nerve in the calf.

The remaining contents of the popliteal fossa are the deeply placed popliteal lymph nodes, which lie close to the popliteal artery. They drain the deep structures of the leg and foot and the knee joint and receive superficial lymphatics, which accompany the short saphenous vein from the lateral side of the foot and leg.

Floor

The floor of the fossa is formed, from above downwards, by the popliteal surface of the femur, the capsule of the knee joint reinforced by the oblique popliteal ligament and popliteus (Fig. 6.39).

Popliteus

This muscle is attached to a triangular area on the posterior surface of the proximal end of the tibia above the soleal line. The tendon passes upwards and laterally, penetrating the capsule of the knee joint (Fig. 6.77) to become attached to a pit below the lateral epicondyle of the femur. Its action is to 'unlock' the knee joint by producing lateral rotation of the femur on the tibia during flexion of the joint from the fully extended position. Popliteus is supplied by the tibial nerve.


Popliteal surface of femur
Middle genicular artery and nerve
S
m
la
I
Capsule of knee joint
Semimembranosus (cut)
Oblique popliteal ligament
Bursa
Popliteus
Semitendinosus (cut)
Popliteal artery and venae comitantes (cut)
Tibial nerve (cut)

Fig. 6.39 Floor of popliteal fossa, seen after removal of walls and contents of the fossa.


Popliteal artery and vein traversing opening in adductor magnus
S
m
la
I
Popliteal artery
Tibial nerve
Common fibular nerve
Muscular branches
Lateral head of gastrocnemius
Medial head of gastrocnemius

Fig. 6.40 Principal vessels and nerves of the popliteal fossa, revealed by removal of fat.

Posterior Compartment of the Leg

The compartment extends from the popliteal fossa above to the ankle below. Gastrocnemius and soleus account for its bulk (Fig. 6.41) and the characteristic contour of the calf. Their common tendon is conspicuous as it passes towards the ankle. Deeper are tibialis posterior and the two long flexors of the toes, flexor hallucis longus and flexor digitorum longus, whose tendons all pass distally into the foot. The posterior tibial artery and its venae comitantes and the tibial nerve pass distally between soleus and the long flexors to enter the foot, where they supply structures in the sole.

Superficial structures and deep fascia

The small (short) saphenous vein begins on the lateral side of the foot as a continuation of the dorsal venous arch. Passing behind the lateral malleolus (Fig. 6.42) it ascends in the midline of the calf and usually terminates by piercing the fascial roof of the popliteal fossa (Fig. 6.37). The vein has frequent communication with the great saphenous vein and important communicating (perforating) veins, which pierce the investing deep fascia to link up with the deep veins of the calf, particularly just above the ankle.

The sural nerve is formed principally from the cutaneous branch of the tibial nerve and descends from the popliteal fossa to pierce the deep fascia in the proximal part of the calf. Here it is joined by the sural communicating branch of the common fibular nerve and continues distally with the small saphenous vein postero-inferior to the lateral malleolus to reach the foot (Fig. 6.42). The nerve supplies skin over the lower two-thirds of the calf and on the lateral side of the ankle and foot.

The deep fascia is continuous proximally with the popliteal fascia, and distally near the heel is thickened in two places. The first forms a thick band stretching between the tibia and fibula over which the tendo calcaneus passes, separated by a bursa. The second thickening, the flexor retinaculum, bridges the gap between the medial malleolus and the medial surface of


Tibia
Tibialis posterior
Great saphenous vein
Posterior tibial artery and vena comitans
Deep vein and branch of tibial artery
Gastrocnemius
Short saphenous vein
Tibial nerve
Interosseous membrane
Peroneal intermuscular septa
Fibula
Peroneal artery
Soleus
Deep fascia
m
A
P
la

Fig. 6.41 'Step' dissection showing the muscle layers in the upper third of the leg and the location of principal nerves and vessels.


S
P
A
I
Lateral head of gastrocnemius
Cutaneous nerve of calf
Sural nerve
Small saphenous vein (duplicated)
Perforating veins
Fibular muscles
Deep fascia
Lateral malleolus

Fig. 6.42 Small saphenous vein and sural nerve. Perforating veins pierce the deep fascia to connect with deep veins in the calf muscles.

the calcaneus, completing a fibro-osseous tunnel similar to the carpal tunnel of the wrist. It is the gateway into the sole of the foot for the tendons of the deep muscles of the compartment and the neurovascular bundle. The tibial nerve may be compressed in the tunnel, causing pain in the heel and foot.


S
m
la
I
Tibial nerve
Common fibular nerve
Lateral and medial heads of gastrocnemius
Soleus
Aponeurosis
Tendo calcaneus
Lateral malleolus
Calcaneus

Fig. 6.43 Removal of the deep fascia reveals the superficial flexor muscles, gastrocnemius and soleus.

Superficial muscles

Gastrocnemius

The muscle has medial and lateral heads attached to the respective femoral condyles. The medial head is the larger and its fibres extend more distally. The two heads share a common aponeurosis, which overlies that of the subjacent soleus (Fig. 6.43). The long parallel fibres of gastrocnemius provide a large range of movement and are used especially during walking and running. Because of its femoral attachments, it is a weak flexor of the knee joint.

Soleus

This muscle attaches to the soleal line on the posterior border of the tibia, from where it arches across to the posterior aspect of the head and upper shaft of the fibula (Figs 6.44 & 6.45). Its short multipennate fibres are continually in action during standing.

The aponeuroses of gastrocnemius and soleus form the tendo calcaneus (Achilles), which attaches to the middle third of the posterior surface of the calcaneus, and via this tendon the two muscles are the principal flexors of the foot at the ankle joint. The tendon, separated from the upper part of the calcaneus, is easily palpable and is used clinically to obtain the stretch reflex or ankle jerk (S1 & S2).

Plantaris

This muscle attaches to the lower end of the femur close to the lateral head of gastrocnemius. Its long thin tendon passes deep to the medial head of gastrocnemius (Fig. 6.45) between the aponeuroses of gastrocnemius and soleus to insert into the posterior surface of the calcaneus


Intercondylar eminence
Tibial condyles
Head and neck of fibula
Soleal line
Line of attachment of intermuscular septum
Nutrient foramen
Posterior surface of fibula
Medial malleolus
Groove for tendon of flexor hallucis longus
Lateral malleolus
Head of talus
Tuberosity of navicular
Calcaneus
Soleus
Flexor digitorum longus
Flexor hallucis longus
Tibialis posterior
S
m
la
I

Fig. 6.44 Posterior view of bones of leg and foot. The diagram shows attachments of muscles of posterior compartment.



Fig. 6.45 Partial removal of the two heads of gastrocnemius reveals soleus and the neurovascular bundle passing beneath the soleal arch to enter the calf.

medial to the tendo calcaneus. It is a weak flexor of the knee and ankle joints.

Gastrocnemius, soleus and plantaris are supplied by the tibial nerve in the popliteal fossa (Fig. 6.40). Soleus is further supplied by the tibial nerve as it passes beneath the soleal arch.

Neurovascular structures

Posterior tibial artery

At the lower border of popliteus, the popliteal artery divides into two terminal branches, the anterior tibial artery (p. 290) and the larger posterior tibial artery. The latter, accompanied by its venae comitantes, passes deep to the soleal arch and descends on the fascia of tibialis posterior (Fig. 6.41) between flexor digitorum longus and flexor hallucis longus. Near the ankle, the artery lies on the distal end of the tibia and the capsule of the ankle joint, where its pulsations are easily felt. Passing beneath the flexor retinaculum, it gives calcaneal branches to the superficial tissues of the heel and then divides into medial and lateral plantar arteries. It provides branches to the muscles in the calf and also a large nutrient artery to the tibial shaft.

The most conspicuous branch, the fibular (peroneal) artery, arises just beyond the soleal arch (Fig. 6.46) and passes distally and laterally deep to flexor hallucis longus and upon the fascia of tibialis posterior. It gives muscular branches and a nutrient branch to the fibula. The fibular artery terminates behind the lateral malleolus as lateral calcaneal branches supplying the tissues of the heel. In the lower part of the leg, a communicating artery links the fibular and posterior tibial arteries.

A perforating branch of the fibular artery passes forwards through the interosseous membrane into the anterior compartment of the leg. When the anterior tibial artery is small, this perforating artery may substitute for it distally, continuing into the foot as the dorsalis pedis artery.

Tibial nerve

The tibial nerve enters the compartment from the popliteal fossa by passing beneath the soleal arch. Usually, the posterior tibial artery lies medially as it descends through the calf on the fascia of tibialis posterior and on the distal end of the tibia (Fig. 6.46). Similar to the artery, as it enters the foot it often terminates beneath the flexor retinaculum as two branches, the medial and lateral plantar nerves. It supplies soleus and the deep leg muscles and gives sensory branches to skin over the ball of the heel.

Deep muscles

Lying deep to soleus are flexor digitorum longus, flexor hallucis longus and tibialis posterior (Figs 6.41 & 6.46). Proximally, their attachments are limited by the origin of soleus from the tibia and fibula. Their tendons enter the foot beneath the flexor retinaculum.

Flexor digitorum longus arises from the posterior surface of the tibia (Fig. 6.44) and from the fascia covering tibialis posterior. In the foot, the tendon divides into four slips, which are attached to the bases of the terminal phalanges of the lateral toes. The muscle flexes the toes and assists in plantar flexion of the ankle joint.

Flexor hallucis longus is larger than flexor digitorum longus (Fig. 6.46) and has extensive attachments to the posterior surface of the shaft of the fibula (Fig. 6.44), the posterior intermuscular septum and the fascia covering tibialis posterior. Its muscle fibres characteristically extend almost as far as the ankle (Fig. 6.46) and give way to a tendon, which passes beneath the flexor retinaculum to insert into the base of the distal phalanx of the great toe. It is a powerful flexor of the hallux, especially in forward propulsion of the foot at the take-off point during walking. Plantar flexion at the ankle joint is also assisted.

Tibialis posterior is the deepest muscle in the compartment and attaches to the posterior surface of the tibia (Fig. 6.44), to the medial surface of the fibula and to the upper two-thirds of the interosseous membrane. Passing under the flexor retinaculum, where it is the most medial structure, the tendon enters the foot to attach principally to the tuberosity of the navicular and by small slips to the other tarsal bones. Together with tibialis anterior its action is to invert the foot. It is also a weak plantar flexor of the ankle joint.

All three deep muscles of the calf are supplied by the tibial nerve. Further details of the tendons in the sole of the foot are given on p. 282.



Fig. 6.46 Removal of the superficial flexor group shows the deep muscles of the compartment and the main neurovascular bundle.

Sole of the Foot

The sole of the foot contains the plantar aponeurosis, intrinsic muscles, tendons originating from muscles in the leg, and plantar vessels and nerves. The tendons, accompanied by the vessels and nerves, enter the sole deep to the flexor retinaculum (Fig. 6.48) in the tarsal tunnel, between the medial aspect of the calcaneus and the medial malleolus. The skin of the sole is thick and heavily keratinized and is firmly attached to the deep fascia by fibrous septa which traverse and loculate the subcutaneous fat. In the heel, it forms a weight-bearing fat pad.

Plantar aponeurosis

The plantar aponeurosis, the deep fascia of the sole covering the superficial layer of muscles, is especially thick in its central portion. Posteriorly, the aponeurosis is attached to the medial and lateral calcaneal tubercles. Anteriorly, it widens and diverges into five digital slips (Fig. 6.47), which attach to the fibrous flexor sheaths and plantar metatarsal plates (Fig. 6.96). These plates give the aponeurosis indirect attachment to the bases of all the proximal phalanges, providing an important support for the longitudinal arches of the foot (Figs 6.98–6.102). Inflammation of the aponeurosis (plantar fasciitis) is a cause of pain in the foot.


Digital slips
Digital branch of medial plantar nerve
A
la
m
P
Digital branch of lateral plantar nerve
Cutaneous branches of lateral plantar nerve (cut)
Cutaneous branch of medial plantar nerve (cut)
Plantar aponeurosis
Deep fascia covering abductor hallucis
Deep fascia covering abductor digiti minimi

Fig. 6.47 Plantar aponeurosis, deep fascia and cutaneous nerves, revealed by removal of the skin of the sole.


Tendon of tibialis posterior and attachment
Tendon of flexor digitorum longus
Posterior tibial artery
Tibial nerve
Tendon of flexor hallucis longus
Tendo calcaneus (cut)
Flexor retinaculum
Medial plantar artery and nerve
Tendon of flexor hallucis longus
Tendon of flexor digitorum longus
Lateral plantar nerve (cut) and artery
S
A
P
I

Fig. 6.48 Long tendons and the principal vessels and nerves from the posterior compartment of the leg pass deep to the flexor retinaculum to enter the sole of the foot.

Muscles and tendons

The muscles and tendons in the sole of the foot are arranged in four layers.

Superficial intrinsic muscles

This layer comprises three muscles, which span the length of most of the foot and attach to the deep surface of the plantar aponeurosis. Abductor hallucis (Fig. 6.49) lies on the medial side of the foot and arises from the medial calcaneal tubercle and the adjacent flexor retinaculum. Its tendon passes to the great toe with the medial tendon of flexor hallucis brevis and attaches to the medial side of the base of the proximal phalanx. It is supplied by the medial plantar nerve.

Flexor digitorum brevis lies centrally (Fig. 6.49) and attaches to the medial calcaneal tubercle (Fig. 6.50). It has four tendons, which pass forwards to enter the fibrous flexor sheaths of the lateral four toes. Each tendon splits to allow the passage of the long flexor tendon (Figs 6.49 & 6.51), then reunites to attach to the flexor surface of the middle phalanx. Flexor digitorum brevis aids flexion of the proximal parts of the toes and is supplied by the medial plantar nerve.

Abductor digiti minimi traverses the lateral border of the sole (Fig. 6.49) and is attached posteriorly to the medial and lateral calcaneal tubercles. Entering the little toe, its tendon attaches to the lateral side of the proximal phalanx. The muscle is supplied by the lateral plantar nerve.


Fibrous flexor sheaths
Tendon of flexor digitorum brevis
Tendon of flexor digitorum longus
Branches of lateral plantar nerve
Branches of medial plantar nerve
Abductor digiti minimi
Flexor digitorum brevis
Abductor hallucis
A
la
m
P
Edges of intermuscular septa
Plantar aponeurosis (cut)

Fig. 6.49 Superficial intrinsic muscles and plantar nerves after removal of deep fascia, part of the plantar aponeurosis and second fibrous tendon sheath. In this specimen, flexor digitorum brevis has only three tendons.


Styloid process at base of fifth metatarsal
Groove on cuboid for fibularis longus tendon
Tuberosity of navicular
Head of talus
Sustentaculum tali
Groove for flexor hallucis longus tendon
Lateral and medial calcaneal tubercles
A
la
m
P
Tibialis anterior
Fibularis brevis
Flexor hallucis longus
Tibialis posterior
Fibularis longus
Flexor digitorum longus

Fig. 6.50 Plantar view of bones of foot showing attachments of some long tendons.

Long flexor tendons and associated intrinsic muscles

This layer includes the tendons of two long flexor muscles, which arise in the leg, namely flexor hallucis longus and flexor digitorum longus. Attached to the tendon of flexor digitorum longus (Fig. 6.52) are quadratus plantae (flexor accessorius) and the four lumbricals.

The tendon of flexor hallucis longus grooves the posterior surface of the talus and curves forwards inferior to the sustentaculum tali and the spring (plantar calcaneonavicular) ligament. It passes deep to the tendon of flexor digitorum longus, to which it is usually attached. The tendon of flexor hallucis longus continues forwards inferior to the head of the first metatarsal, where it passes between the sesamoid bones in the two tendons of the flexor hallucis brevis (see below) and enters the fibrous flexor sheath of the great toe to reach its attachment to the base of the distal phalanx (Fig. 6.52). The actions and innervation of flexor hallucis longus are described on p. 279.

The tendon of flexor digitorum longus passes forwards medial to the sustentaculum tali and divides into four tendons, one for each of the lateral four toes (Figs 6.51 & 6.52). Each tendon enters its fibrous flexor sheath and passes through the flexor digitorum brevis tendon before attaching to the base of the terminal phalanx. The actions and innervations of flexor digitorum longus are considered on p. 279.

Quadratus plantae (flexor accessorius) (Figs 6.51 & 6.52) is quadrangular and is anchored posteriorly to the medial and lateral tubercles of the calcaneus. Anteriorly, the muscle attaches to the tendons of flexor digitorum longus. By pulling on these tendons, it can flex the toes irrespective of the position of the ankle. Its nerve supply is from the lateral plantar nerve.

The lumbricals are four small muscles attached proximally to the tendons of flexor digitorum longus (Fig. 6.52). Distally, each slender tendon winds around the medial side of the appropriate digit to attach to the extensor expansion and base of the proximal phalanx. The lumbricals extend the lateral four toes but flex the metatarsophalangeal joints. The first lumbrical is supplied by the medial plantar nerve and the remainder by the lateral plantar nerve.

Deep intrinsic muscles

The three muscles in this layer are located in the anterior part of the foot (Fig. 6.53), adjacent to the metatarsals. Flexor hallucis brevis and adductor hallucis lie medially and are attached to the great toe, while flexor digiti minimi brevis lies laterally and acts on the little toe.

Flexor hallucis brevis lies along the medial side of the foot and is attached posteriorly to the cuboid and the three cuneiforms. Passing forwards on either side of the flexor hallucis longus tendon (Fig. 6.52), the muscle gives rise to two short tendons, which lie inferior to the first metatarsophalangeal joint. Each tendon contains a sesamoid bone (Figs 6.101 & 6.102) and enters the great toe to attach to the appropriate side of the base of the proximal phalanx. Flexor hallucis brevis flexes the proximal phalanx and is innervated by the medial plantar nerve.

Adductor hallucis (Fig. 6.53) consists of an oblique head which is attached to the bases of the second, third and fourth metatarsals, and a transverse head which lies across the anterior part of the sole, attached to the deep transverse metatarsal ligaments and the lateral three metatarsophalangeal joints. The two heads converge and attach to the lateral tendon and sesamoid of flexor hallucis





Fibrous flexor sheath
Lumbricals
Abductor digiti minimi
Lateral plantar nerve and artery
Flexor digitorum brevis (cut)
A
la
m
P
Digital branches of medial plantar nerve
Tendon of flexor hallucis longus
Tendon of flexor digitorum brevis (cut)
Flexor digitorum longus
Medial plantar artery
Flexor accessorius
Medial plantar nerve
Abductor hallucis

Fig. 6.51 Removal of flexor digitorum brevis has revealed the plantar nerves and arteries, which enter the sole deep to abductor hallucis.

brevis. Adductor hallucis assists flexor hallucis brevis and may help to support the transverse arch of the foot. It is supplied by the lateral plantar nerve.

Flexor digiti minimi brevis lies along the plantar surface of the fifth metatarsal (Fig. 6.53), attaching posteriorly to the base of the bone and anteriorly to the lateral side of the base of the proximal


Tendons of flexor digitorum longus
Lumbricals
Quadratus plantae
Lateral plantar artery
Tendon of flexor hallucis longus
Plantar metatarsal artery
Heads of flexor hallucis brevis
Medial and lateral plantar nerves (cut)
Flexor digitorum brevis (cut)
A
la
m
P

Fig. 6.52 Tendons of flexor digitorum longus, flexor hallucis longus, quadratus plantae and the lumbricals, after removal of medial and lateral plantar nerves and the tendons of flexor digitorum brevis.


Fibrous flexor sheaths (opened)
Transverse and oblique heads of adductor hallucis
Abductor digiti minimi (cut)
Flexor digiti minimi brevis
Lateral and medial plantar arteries
Abductor digiti minimi (cut)
Tendon of flexor hallucis longus (cut)
Plantar metatarsal artery
Abductor hallucis (cut)
Flexor hallucis brevis
Tendons of flexors digitorum longus and hallucis longus (cut)
Abductor hallucis (cut)
Flexor digitorum brevis (cut)
A
la
m
P

Fig. 6.53 Deep intrinsic muscles, revealed by removal of long flexor tendons and abductors of the great and little toes.

phalanx of the little toe. The muscle flexes the proximal phalanx and is innervated by the lateral plantar nerve.

Interossei and tendons of fibularis (peroneus) longus and tibialis posterior

Lying deeply in the sole, attached to the metatarsals, the three plantar interosseous muscles (Fig. 6.54) attach by single heads to the plantar borders of the third, fourth and fifth metatarsals. The four dorsal interossei (Fig. 6.55) are bicipital and attach to contiguous surfaces of the shafts of the metatarsals. The tendons pass forwards dorsal to the deep transverse metatarsal ligaments and attach to the bases of the proximal phalanges and dorsal extensor expansions. These muscles are supplied by the lateral plantar nerve. They assist extension of the phalanges and flexion of the


A
la
m
P
Plantar metatarsal arteries
Deep transverse metatarsal ligament
Plantar inter-osseous muscles
Dorsal inter-osseous muscles
Plantar arch
Adductor hallucis (cut)
Lateral and medial plantar arteries

Fig. 6.54 Interosseous muscles and the plantar arterial arch, exposed by removing adductor hallucis.


A
m
la
P
Capsules of inter-phalangeal joints
Capsules of metatarso-phalangeal joints
Shafts of metatarsals
Plantar metatarsal artery
Dorsalis pedis artery (cut)
Dorsal interosseous muscles
Extensor digitorum and hallucis brevis (cut)

Fig. 6.55 Dorsal aspect of the foot showing the dorsal interosseous muscles after partial removal of extensor digitorum brevis. Extensor expansions have been removed to show joint capsules.

metatarsophalangeal joints. Their attachments indicate that plantar interossei should adduct and dorsal interossei should abduct the toes, but these movements are often poorly developed, especially in the shod foot.

The tendons of fibularis (peroneus) longus and tibialis posterior (Fig. 6.56) pass deeply into the sole to reach their attachments on tarsal and metatarsal bones. The fibularis longus tendon enters the lateral side of the sole and is retained in a groove inferior to the cuboid by the long plantar ligament. The tendon passes forwards and medially to reach the lateral aspect of the base of the first metatarsal and adjacent medial cuneiform (compare with tibialis anterior, p. 288). The tendon of tibialis posterior enters the medial aspect of the foot deep to the flexor retinaculum (Figs 6.48 & 6.56), attaches to the tuberosity of the navicular and sends additional slips to other tarsal bones and the metatarsal bases. These two tendons may help to support the medial longitudinal arch. The other actions of fibularis longus and tibialis posterior and their innervation are considered on pp 279, 290.

Blood supply

Deep to the flexor retinaculum, the tibial artery divides into medial and lateral plantar branches (Fig. 6.51). Passing forwards, the medial plantar artery runs deep to the superficial intrinsic muscles, gives off plantar cutaneous branches, which pass between abductor hallucis and flexor digitorum brevis, and terminates by supplying digital branches to the medial (and occasionally lateral) side of the great toe. The larger lateral plantar artery passes forwards and laterally (Fig. 6.54) deep to the superficial intrinsic muscles towards the base of the fifth metatarsal. Here the artery inclines medially and deeply to form the plantar arch, lying on the interossei and bases of the metatarsals. A perforating branch between the first and second metatarsals usually links the arch with the dorsalis pedis artery (p. 290). From the arch, plantar metatarsal arteries (Fig. 6.54) pass distally to the webs of the toes where they divide into digital branches. Venae comitantes accompany medial and lateral plantar arteries and their branches.

Nerve supply

Cutaneous branches of the tibial nerve supply the skin over the heel. Deep to the flexor retinaculum the tibial nerve divides into medial and lateral branches, which supply their respective sides of the sole (Figs 6.48 & 6.51). The larger medial plantar nerve accompanies the corresponding artery and gives cutaneous branches to the medial three and one-half digits, including the nail beds. The nerve also supplies abductor hallucis, flexor hallucis brevis, flexor digitorum brevis and the first lumbrical.

The lateral plantar nerve accompanies the corresponding artery (Fig. 6.51), supplying quadratus plantae and abductor digiti minimi and giving cutaneous branches to the sole. Near the base of the fifth metatarsal it divides into superficial and deep branches, which supply the remaining muscles of the sole. The deep branch accompanies the plantar arch and terminates in adductor hallucis. In addition to muscular branches, the superficial branch also gives cutaneous branches to the lateral one and one-half toes.





A
la
m
P
Base of first metatarsal
Tendon of tibialis anterior
Tendon of tibialis posterior and slips
Flexor retinaculum
Tendon of flexor digitorum longus (cut)
Posterior tibial artery (cut)
Base of fifth metatarsal
Tendon of fibularis brevis
Tendon of fibularis longus
Long plantar ligament
Tibial nerve (cut)
Flexor hallucis longus (cut)

Fig. 6.56 Deep dissection of sole to show long plantar ligament and tendons of fibularis longus and tibialis posterior.


Anterior intermuscular septum
Fibularis brevis and longus
Anterior tibial artery and venae comitantes
Posterior intermuscular septum
Deep fibular nerve
Fibula
Fibular artery
Soleus
Medial and lateral heads of gastrocnemius
Deep fascia
Tibialis anterior
Extensor digitorum longus
Interosseous membrane
Tibia
Tibialis posterior
Posterior tibial artery
Tibial nerve
Vena comitans
A
la
m
P

Fig. 6.57 Transverse section through the leg showing anterior and lateral compartments and their contents. Inferior aspect.

Anterior and Lateral Compartments of the Leg and Dorsum of the Foot

Anterior compartment of leg and dorsum of foot

The anterior compartment of the leg contains muscles that extend the ankle joint and toes and evert and invert the foot. Its neurovascular bundle comprises the anterior tibial artery and its venae comitantes and the deep fibular nerve (Fig. 6.57). The cutaneous branches of the superficial fibular nerve are also present.

On the dorsum of the foot are the long extensor tendons, the dorsalis pedis artery, the dorsal venous arch and, more laterally, the bellies of extensor digitorum brevis and extensor hallucis brevis. The medial and lateral malleoli lie on each side of the ankle.

Superficial structures

The dorsal venous arch (Fig. 6.58) drains blood from the toes and sole of the foot. From its medial end the great (long) saphenous vein passes in front of the medial malleolus where it is palpable and accessible, and then ascends to the posteromedial aspect of the knee. From the lateral side of the arch, the small saphenous vein passes behind the lateral malleolus and ascends to the popliteal fossa (p. 274). The saphenous nerve accompanies the great saphenous vein (Fig. 6.59), supplying skin on the medial side of the leg and medial border of the foot as far as the ball (metatarsophalangeal joint) of the great toe. The sural nerve accompanies the small saphenous vein (Fig. 6.58) and supplies skin along the lateral border of the foot and little toe.

The superficial fibular (superficial peroneal) nerve enters the anterior compartment of the leg from the lateral (fibular or peroneal) compartment at the anterior border of fibularis longus (Fig. 6.60). Shortly after piercing the deep fascia it divides into medial and lateral branches, which supply the skin of the leg and dorsum of the foot (Fig. 6.58). On reaching the toes, the medial branch supplies the medial side of the great toe and the contiguous aspects of the second and third toes, while the lateral branch innervates the adjacent sides of the third, fourth and fifth toes. Thus, all of the digital skin is innervated by the superficial fibular nerve, except for the cleft between the great and second toes (supplied by the deep fibular [peroneal] nerve; Fig. 6.58) and the lateral aspect of the little toe (supplied by the sural nerve).

The skin and subcutaneous tissues over the anteromedial surface of the tibia are comparatively thin and have a sparse blood supply. As a consequence, lacerations in this region may heal relatively slowly. The subcutaneous tissues of the ankle are a common site for accumulation of tissue fluid (oedema).

Deep fascia

In the region of the ankle and foot there are thickenings of the investing deep fascia forming retinacula (Fig. 6.60), which prevent bowstringing of the long extensor tendons during muscular contraction. As the tendons pass beneath the retinacula to reach the foot they are enveloped in synovial membrane. By convention, superior and inferior extensor retinacula are described (Fig. 6.64). The superior retinaculum forms a broad band passing between the anterior borders of the tibia and fibula. The inferior retinaculum is Y-shaped, with its stem attached to the upper surface of the calcaneus.


Superficial fibular nerve
Saphenous nerve
Lateral malleolus
Medial malleolus
Origin of great saphenous vein
Origin of small saphenous vein
Sural nerve
Perforating vein
Dorsal venous arch
Terminal branch of deep fibular nerve
Digital veins
S
la
m
I

Fig. 6.58 Superficial nerves and veins on the dorsum of the ankle and foot.


Saphenous nerve
Great saphenous vein
S
A
P
I
Superficial fibular nerve
Medial malleolus
Saphenous nerve

Fig. 6.59 Superficial veins and nerves on the medial surface of the leg and foot.


S
la
m
I
Fibularis longus
Tibialis anterior
Sub-cutaneous surface of tibia
Extensor digitorum longus
Fibularis brevis
Superficial fibular nerve (cut)
Fibularis tertius
Extensor retinaculum
Tendons of extensor digitorum longus
Tendon of extensor hallucis longus
Tendon of tibialis anterior
Extensor digitorum brevis
Tendon of fibularis tertius
Sural nerve
Tendons of extensor digitorum brevis

Fig. 6.60 Muscles of the anterior compartment of the leg and tendons on the dorsum of the foot, seen after removal of deep fascia. The extensor retinaculum has been retained.

Muscles

The muscles in the anterior compartment are tibialis anterior, extensor hallucis longus, extensor digitorum longus and fibularis (peroneus) tertius. All are supplied by the deep fibular nerve. Tibialis anterior is the most medial (Figs 6.57 & 6.60), attaching to the lateral condyle and anterolateral surface of the shaft of the tibia, the adjacent interosseous membrane and the deep fascia overlying the muscle. Distally, its tendon crosses the anterior border of the lower end of the tibia and attaches to the base of the first metatarsal and adjacent part of the first cuneiform bone (Fig. 6.61). The muscle inverts the foot and dorsiflexes the ankle joint.

The other three muscles all attach to the narrow anterior surface of the fibula and adjacent interosseous membrane. Extensor digitorum longus (Fig. 6.57) is attached to the proximal three-quarters of the bone, fibularis tertius (when present) to the distal quarter, and extensor hallucis longus is overlapped by them medially at midshaft level. In addition, extensor digitorum longus attaches to the anterior intermuscular septum and overlying deep fascia.

The proximal part of extensor hallucis longus is overlapped by adjacent muscles, but in the lower part of the leg, its tendon emerges lateral to that of tibialis anterior. As it descends towards the ankle, the tendon crosses from the lateral to the medial side of the neurovascular bundle.

In the foot, the tendon of extensor hallucis longus runs forwards to the great toe (Fig. 6.62), where it attaches to the base of the distal phalanx. It is a powerful extensor of the toe, dorsiflexor (extensor) of the foot and assists inversion. Lateral to extensor hallucis longus, the muscle belly of extensor digitorum longus gives way distally to four tendons, which pass to the dorsal aspects of the lateral four toes. Each tendon forms an extensor expansion that divides into three slips. The central slip attaches to the base of the middle phalanx, while the two lateral slips combine to insert into the base of the distal phalanx (Fig. 6.62). Extensor digitorum longus extends the lateral four toes and dorsiflexes the foot. Fibularis tertius is a continuation of the belly of extensor digitorum longus. It attaches to the lateral border of the fifth metatarsal (Fig. 6.62) and everts the foot and dorsiflexes the ankle.

The muscles of the anterior compartment of the leg are active during walking in both the supporting and swing phases. In the weight-bearing limb they help to incline the leg forwards, while the foot remains stationary on the ground. In the swinging limb, the muscles maintain the ankle in dorsiflexion, thereby preventing the foot from dropping.

On the dorsum of the foot, extensor digitorum brevis and extensor hallucis brevis (Fig. 6.62) are attached to the upper surface of the calcaneus and overlying stem of the inferior extensor retinaculum. Extensor digitorum brevis gives rise to three short tendons, which pass deep to the long extensor tendons of the lateral three toes (Fig. 6.62) and attach to the dorsal extensor expansions of the second, third and fourth toes. The tendon of extensor hallucis brevis attaches to the base of the proximal phalanx of the great toe. The muscles assist extension of the toes, particularly when the long extensors are flexing the leg forwards on the foot just before it is lifted from the ground during walking. The nerve supply is the deep fibular nerve.


Tibial tubercle
Head and neck of fibula
Anteromedial (subcutaneous) surface of tibia
Anterior border of tibia
Anterior surface of fibula
Medial malleolus
Lateral malleolus
Head of talus
S
la
m
I
Tibialis anterior
Extensor digitorum longus
Extensor hallucis longus
Fibularis tertius
Patellar ligament

Fig. 6.61 Anterior view of bones of leg and foot showing attachments of muscles of anterior compartment.


Anterior tibial artery and venae comitantes
Great saphenous vein
Medial malleolus
Tibialis anterior
Extensor hallucis longus
Extensor digitorum brevis
Tendons of extensor digitorum longus
Deep fibular nerve
Tendon of fibularis tertius
Tendon of extensor hallucis brevis
Dorsalis pedis artery
S
la
m
I
Tendons of extensor digitorum brevis
Extensor expansion
Digital cutaneous branch of deep fibular nerve

Fig. 6.62 Principal structures on the dorsum of the ankle and foot seen after removal of the extensor retinaculum.

Neurovascular bundle

This comprises the deep fibular nerve and the anterior tibial artery, with its venae comitantes (Fig. 6.57). The artery, a terminal branch of the popliteal artery (p. 278), reaches the anterior compartment after passing through the interosseous membrane (Figs 6.76 & 6.83). It then descends on the anterior surface of the membrane (Fig. 6.63) and at the ankle lies midway between the two malleoli. It continues distally as the dorsalis pedis artery on the lateral side of the extensor hallucis longus tendon (Fig. 6.62), where its pulsations are palpable in the living foot.

At the proximal end of the first intermetatarsal space, the dorsalis pedis artery gives a deep branch that passes between the two heads of the first dorsal interosseous muscle to join the plantar arch (p. 285). This arrangement provides an anastomosis between the anterior and posterior tibial arteries. The dorsalis pedis artery terminates as the first dorsal metatarsal artery, supplying the great toe and adjacent border of the second toe and the arcuate artery. It turns laterally beneath the extensor tendons across the bases of the metatarsals and gives metatarsal arteries, which divide to supply adjacent borders of the remaining three digits.




Common fibular nerve
Neck of fibula
Fibularis longus (reflected)
S
la
m
I
Anterior tibial artery
Extensor digitorum longus (cut)
Interosseous membrane
Deep fibular nerve
Fibularis longus (cut)
Extensor digitorum longus (cut)
Tibialis anterior
Superficial fibular nerve (cut)
Fibularis brevis
Extensor hallucis longus
Anterior tibial artery
Lateral malleolus
Deep fibular nerve

Fig. 6.63 The common fibular nerve and its branches and the anterior tibial artery, seen after deep dissection of both compartments.

The deep fibular (peroneal) nerve, a terminal branch of the common fibular nerve, winds around the neck of the fibula deep to fibularis (peroneus) longus (Fig. 6.63). The nerve accompanies the anterior tibial vessels into the foot and supplies all muscles in the anterior compartment. In the foot, the nerve is close to the dorsalis pedis artery, usually lying lateral to the artery but sometimes medial to it (Fig. 6.62). It gives a branch to extensors digitorum and hallucis brevis and the tarsal joints and terminates by supplying the skin between the great and second toes (Fig. 6.62).

Lateral compartment of leg

The lateral (fibular or peroneal) compartment of the leg extends from the head of the fibula above to the lateral malleolus below. Its principal contents are the fibularis longus and brevis muscles (Fig. 6.64). Fibularis (peroneus) longus is attached to the upper two-thirds of the lateral surface of the fibula and fibularis (peroneus) brevis to the lower two-thirds, with brevis being the more anterior. Both muscles are attached to the two crural intermuscular septa and the overlying deep fascia (Fig. 6.57). On reaching the ankle the tendons pass behind and then below the lateral malleolus, restrained by the superior and inferior fibular retinacula and surrounded by synovial membrane (Fig. 6.64). The tendon of fibularis brevis passes forwards above the fibular trochlea of the calcaneus to attach to the base of the fifth metatarsal. The fibularis longus tendon passes forwards below the fibular trochlea and turns medially into the sole of the foot where it lies in a groove on the cuboid bone (Fig. 6.65). It attaches to the lateral side of the base of the first metatarsal and the adjacent first cuneiform.

Fibularis longus and brevis are evertors of the foot and weak plantar flexors of the ankle joint. Their nerve supply is the superficial fibular nerve, a terminal branch of the common fibular nerve, which enters the lateral compartment by winding around the neck of the fibula. Here it is palpable and may sometimes be compressed.

Branches of the fibular artery, which arises from the posterior tibial artery (p. 278), pierce the posterior intermuscular septum to supply fibularis longus and brevis.


S
P
A
I
Gastrocnemius
Fibularis longus
Soleus
Fibularis brevis
Tendo calcaneus
Superior and inferior extensor retinacula
Extensor digitorum brevis
Tendon of fibularis longus
Tendon of fibularis brevis

Fig. 6.64 Lateral aspect of the leg and foot showing fibularis longus and brevis.


Fibularis longus
Fibularis brevis
S
P
A
I
Tibial tubercle
Lateral surface of fibula
Location of tendons of fibularis longus and brevis
Fibular trochlea of calcaneus
Groove beneath cuboid for fibularis longus tendon
Styloid process of fifth metatarsal

Fig. 6.65 Lateral view of bones of leg and foot showing attachment of muscles of lateral compartment.

Hip Joint

The hip joint is a synovial ball-and-socket joint between the head of the femur and the acetabulum of the hip bone (Fig. 6.66).

Articular surfaces

The femoral head, covered by hyaline cartilage, forms two-thirds of a sphere and has a central pit (fovea; Fig. 6.66) giving attachment to the round ligament (ligamentum teres). The head surmounts the femoral neck, whose base abuts the medial side of the greater trochanter. The acetabulum is a deep socket with a C-shaped articular area covered with hyaline cartilage and a fat-filled nonarticular area (acetabular fossa), the margins of which give attachment to the base of the ligamentum teres (Fig. 6.67). The acetabulum is deficient inferiorly at the acetabular notch (Fig. 6.66), where blood vessels, bridged by the transverse acetabular ligament, enter the joint. A fibrocartilaginous labrum, attached to the margins of the acetabulum and the transverse ligament, helps to deepen the socket.

Capsule

Medially, the fibrous capsule is attached to the outer margin of the labrum; laterally the capsule attaches to the intertrochanteric




S
la
m
I
S
P
A
I
Articular area of acetabulum
Acetabular fossa
Superior ramus of pubis
Acetabular notch
Neck of femur
Lesser trochanter
Fovea
Head of femur
Greater trochanter
Inter-trochanteric line

Fig. 6.66 Articular surfaces of the hip joint comprise the acetabulum of the hip bone and the head of the femur.




S
la
m
I
S
P
A
I
Capsule
Acetabular labrum
Obturator nerve
Obturator artery (cut)
Obturator externus (cut)
Articular cartilage
Ligamentum teres (cut)
Retinacular fibres
Attachment of capsule (cut)
Femoral neck and head
Iliopsoas tendon (cut)

Fig. 6.67 Internal features, revealed by disarticulation of the joint after cutting the ligaments and joint capsule.

line (Figs 6.66 & 6.68) at the root of the femoral neck and to the femoral shaft just above the lesser trochanter. From the femoral attachment of the capsule, retinacular fibres derived from the deep part of the capsule (Fig. 6.67) are reflected medially over the neck to the margins of the head. Posteriorly, the line of attachment of the capsule is such that only the upper (medial) half of the femoral neck lies within the joint.

Ligaments

The iliofemoral, pubofemoral and ischiofemoral ligaments are capsular thickenings that spiral downwards and laterally from the hip bone to the femur. The strong iliofemoral ligament (Fig. 6.68) is an inverted Y-shape, the stem attaching to the anterior inferior iliac spine and the limbs to the upper and lower ends of the intertrochanteric line.

The pubofemoral ligament (Fig. 6.68) passes from the iliopubic eminence to the femoral neck just above the lesser trochanter. The ischiofemoral ligament lies posteriorly (Fig. 6.70) and reaches the root of the greater trochanter.

Within the joint is the ligament of the head of the femur (ligamentum teres femoris) (Figs 6.67 & 6.69), which has the form of a flattened cone, the base attaching to the margins of the acetabular fossa and transverse acetabular ligament and the apex to the fovea on the femoral head.




S
la
m
I
Rectus femoris
Gluteus maximus
Iliopsoas (cut)
Iliofemoral ligament
Pubofemoral ligament
Psoas tendon (cut)
Adductor magnus
Inguinal ligament
Femoral nerve and vessels (cut)
Femoral canal
Superior pubic ramus
Psoas bursa (opened)
Obturator nerve (cut)
Obturator externus

Fig. 6.68 Anterior surface of the joint capsule, its associated ligaments and immediate relations.




S
la
m
I
Acetabular labrum
Femoral head
Ligamentum teres
Capsule
Iliopsoas tendon (cut)
Obturator canal
Division of obturator nerve (cut)
Obturator artery (cut)
Obturator externus

Fig. 6.69 Joint capsule opened anteriorly to show the interior of the joint. The femur has been abducted and externally rotated.

Synovial membrane and bursae

Synovial membrane lines the interior of the capsule and the non-articular surfaces of the joint, clothes the ligament of the head of the femur and is reflected over the retinacular fibres and the femoral neck as far as the head. The iliopsoas tendon and anterior aspect of the capsule are separated by a large bursa (Fig. 6.68), which often is in communication with the joint cavity.

The tendon of obturator externus is separated from the capsule by a smaller bursa, which may also communicate with the joint.


Capsule
Sciatic nerve (cut)
Internal pudendal artery
Pudendal nerve
Sacro-tuberous ligament
Obturator internus and gemelli (cut)
Gluteus minimus (cut)
Nerve to quadratus femoris
Greater trochanter
Arteries of trochanteric anastomosis
Obturator externus
Ischio-femoral ligament
Quadratus femoris (cut)
S
m
la
I

Fig. 6.70 Posterior surface of the joint capsule, the ischiofemoral ligament and close relations.


Pectineus
Femoral vein artery and nerve
Iliopsoas
Sartorius
Tensor fasciae latae
A
m
la
P
Gluteus maximus
Obturator internus
Sciatic nerve
Labrum
Gluteus medius

Fig. 6.71 Transverse section through the hip joint showing its relations. Superior aspect. (Compare Fig. 5.42.)

Movements

The hip joint is multiaxial and permits flexion, extension, abduction, adduction, medial and lateral rotation and circumduction.

Flexion is produced by iliopsoas, assisted by sartorius, rectus femoris and pectineus. Gluteus maximus and the hamstrings are extensors. Abductors of the hip include gluteus medius and minimus, while adduction is produced by adductors longus, brevis and magnus, pectineus and gracilis. Medial rotation is produced by iliopsoas, tensor fasciae latae and the anterior fibres of gluteus minimus and medius. Lateral rotation is produced by piriformis, quadratus femoris, obturator externus and internus and the gemelli.

Stability

The hip joint is very stable, largely because of its bony morphology and the deep fit of the femoral head into the acetabulum. Other important factors include the ligaments and the tone of the muscles crossing the joint. The ilio-, pubo- and ischiofemoral ligaments all limit extension and medial rotation. The iliofemoral ligament, in particular, prevents hyperextension, especially in the upright posture when body weight acts behind the transverse axis of the hip joint and tilts the pelvis backwards. The ligament of the head of the femur limits adduction of the hip.

Relations

The joint is deeply placed behind the midpoint of the inguinal ligament. Laterally, the greater trochanter covers the neck of the femur and is palpable on the lateral side of the thigh. Medially, only the thin bone of the acetabular fossa (Figs 6.71 & 6.72) separates the head of the femur from structures within the pelvis that are vulnerable following acetabular fracture accompanied by medial displacement of the femoral head. Posteriorly lie structures of the gluteal region (Fig. 6.70), including the sciatic nerve, which may be damaged in posterior dislocation. Anteriorly, the joint is covered by the iliopsoas and the femoral vessels and nerve. Obturator externus and the adductor muscles lie inferiorly (Fig. 6.72), while superiorly are gluteus medius and minimus.



Blood supply

The arterial supply of the hip joint, especially that of the head and neck of the femur, is of particular clinical importance. The joint receives branches from the obturator artery, superior and inferior gluteal arteries, and medial and lateral circumflex femoral arteries, either directly or from the trochanteric anastomosis they form. From this anastomosis (Fig. 6.70), nutrient arteries travel in the retinacular fibres to enter foramina on the upper part of the femoral neck and terminate in the head. As only the upper half of the neck is covered posteriorly by the joint capsule, fractures at this site may be classified as either intra- or extracapsular. Intracapsular fractures that tear the retinacular fibres may deprive the head of the femur of much of its blood supply, resulting in avascular necrosis. Additional blood supply comes from a branch of the obturator artery conveyed in the ligament of the head of the femur to the femoral head, and from one of the perforating branches of the profunda femoris artery via a nutrient artery that enters the shaft to supply the femoral neck and head.

Nerve supply

Nerves to the joint include the nerve to rectus femoris from the femoral nerve, branches from the anterior division of the obturator nerve, and the nerve to quadratus femoris from the sacral plexus.



Fig. 6.72 Coronal section through the hip joint showing its relations.

Knee Joint

The knee joint is a synovial joint between the distal end of the femur, proximal end of the tibia and posterior aspect of the patella (Fig. 6.73). It is a hinge joint with a wide range of flexion and extension and limited lateral and medial rotation. The joint is relatively superficial anteriorly, medially and laterally where some of its bony features are palpable. Posteriorly, the joint is inaccessible, being deeply placed in the floor of the popliteal fossa (Fig. 6.74).

Anteriorly, the patellar ligament (Fig. 6.75) passes from the apex of the patella to the tibial tubercle. It is easily palpable and is used clinically for the stretch reflex (knee jerk, L3 & L4).

Articular surfaces

The medial and lateral condyles of the femur have articular surfaces, covered by hyaline cartilage, which extend over their inferior and posterior aspects and articulate with the respective condyles on the tibia (Fig. 6.73). On the front of the femur lies the patellar articular surface, while posteriorly a deep intercondylar fossa separates the two condyles. The articular areas on the tibial condyles are separated by the intercondylar eminence, the lateral articular area being flatter and smaller than the medial area (Fig. 6.73).


la
m
I
S
Apex of patella
Medial and lateral articular areas
Patellar surface
Condyles of femur
Intercondylar fossa
A
la
m
P
Condyles of tibia
Intercondylar eminence
Tibial tubercle
P
la
m
A

Fig. 6.73 Articular surfaces of the patella, femur and tibia.


'Hamstring' muscles
Popliteal vein and artery
Quadriceps tendon
Fat
Suprapatellar bursa
Gastrocnemius
Capsule
Meniscus
Patella
Popliteus
Infrapatellar fat pad
Patellar ligament
S
A
P
I

Fig. 6.74 Sagittal section through the knee joint showing the articular surfaces and relations.


S
la
m
I
Vastus medialis
Patella
Capsule
Tibial collateral ligament
Capsule covering meniscus
Fibular collateral ligament
Tibial condyles
Sartorius (cut)
Semitendinosus
Tibial tubercle and attaching patellar ligament

Fig. 6.75 Superficial dissection from the anterior aspect to show patellar ligament, capsule, and collateral ligaments.

Capsule

The capsule is thin anteriorly and posteriorly but is reinforced on each side by strong collateral ligaments. On the sides of the femur, the capsule attachment extends up to the epicondyles. Posteriorly, it attaches along the superior margins of the condyles (Figs 6.76 & 6.78) and the intercondylar line, while anteriorly it extends proximally (Figs 6.75, 6.79 & 6.81) to accommodate the synovial membrane that forms the suprapatellar bursa (pouch).

On the sides of the tibia, the capsule attaches close to the articular margins. Those parts of the capsule on each side of the joint that loosely anchor the outer borders of the menisci to the tibia are called the coronary ligaments. Posteriorly, the capsular attachment inclines downwards to include the posterior part of the intercondylar area, while anteriorly the attachment deviates inferiorly as far as the tibial tubercle. On the patella, the capsule is attached close to the articular margins.

Posteriorly, part of the insertion of semimembranosus forms the oblique popliteal ligament, which passes upwards and laterally (Figs 6.76 & 6.77), reinforcing the capsule. Where the posterior part of the capsule is pierced by popliteus, it thickens to form the arcuate ligament (Fig. 6.76).


Line of attachment of capsule
Oblique popliteal ligament
Semimembranosus tendon (cut)
Foramen for middle genicular vessels and nerve
Arcuate ligament
Popliteus
Fibular collateral ligament
Soleus (cut)
Anterior tibial artery piercing interosseous membrane
S
m
la
I

Fig. 6.76 Posterior aspect of joint showing capsule, popliteus and semimembranosus insertion.


Capsule
Oblique popliteal ligament
Tendon of semimembranosus (cut)
Posterior cruciate ligament
Lateral femoral condyle
Fibular collateral ligament
Popliteus tendon
Meniscus
Meniscofemoral ligament
Head of fibula
S
m
la
I

Fig. 6.77 Partial removal of capsule to reveal the meniscofemoral and posterior cruciate ligaments and the tendon of popliteus.

Collateral ligaments

On the medial side of the joint, the thick tibial collateral ligament (Fig. 6.79) broadens as it descends from the medial femoral epicondyle to the upper part of the subcutaneous surface of the tibia. Its deep aspect is attached to the outer margin of the medial meniscus (Fig. 6.78), which diminishes mobility of the meniscus, making it more susceptible to tears. On the lateral side the cord-like fibular collateral ligament (Fig. 6.80) descends from the lateral epicondyle of the femur to the styloid process and head of the fibula, separated from the lateral meniscus by the popliteus tendon (Fig. 6.78).

Intracapsular ligaments

The intracapsular ligaments comprise the anterior and posterior cruciate ligaments and the meniscofemoral ligament.

The cruciate ligaments (Fig. 6.78) are named according to their attachment to the intercondylar eminence of the tibia (Fig. 6.82). The anterior ligament passes upwards, backwards and laterally to attach to the medial surface of the lateral condyle of the femur.


Medial femoral condyle
Medial collateral ligament
Posterior cruciate ligament
Medial meniscus
Lateral and medial tibial condyles
Popliteus (cut)
S
m
la
I
Line of attachment of capsule
Lateral femoral condyle
Lateral collateral ligament
Anterior cruciate ligament
Popliteus tendon (cut)
Lateral meniscus
Proximal tibiofibular joint (opened)

Fig. 6.78 The posterior part of the capsule has been removed to show the cruciate ligaments and menisci.


S
A
P
I
Patella
Capsule extending to supra-patellar bursa
Ligamentum patellae
Capsule overlying meniscus
Tibial tubercle
Vastus medialis
Tibial collateral ligament
Gracilis tendon
Sartorius tendon (cut)
Semi-tendinosus tendon

Fig. 6.79 Superficial dissection from the medial aspect showing the tibial collateral ligament, capsule and insertions of sartorius, gracilis and semitendinosus.

The posterior ligament passes upwards, forwards and medially (Fig. 6.78) to attach to the lateral surface of the medial femoral condyle. The meniscofemoral ligament is adjacent to the posterior cruciate ligament (Fig. 6.77) and attaches the posterior border of the lateral meniscus close to the femoral attachment of the posterior cruciate ligament. It stabilizes the meniscus during rotation of the femur on the tibia. Although within the capsule, the cruciate and meniscofemoral ligaments are covered by reflections of synovial membrane and are therefore not within the synovial cavity.

Menisci

The medial and lateral menisci are C-shaped (Fig. 6.82) with their anterior and posterior horns attached to the intercondylar eminence of the tibia and their outer borders to the joint capsule (coronary ligaments). The menisci differ in size and shape, the medial being narrower though slightly larger, so that its horns embrace those of the lateral meniscus. Also, the medial is attached to the medial collateral ligament and in cross-section is deeper than the lateral meniscus. A transverse ligament (Fig. 6.82) connects the anterior horn of the medial meniscus with the anterior aspect of the lateral meniscus.



Fig. 6.80 Lateral aspect of joint showing the collateral ligament and the meniscus, revealed by removing part of the capsule.


S
la
m
I
Capsule (cut)
Suprapatellar bursa (opened)
Patellar surface
Lateral meniscus
Alar fold
Infrapatellar fat pad
Tibial collateral ligament
Fibular collateral ligament
Patella (reflected downwards)

Fig. 6.81 Interior of joint, revealed by opening the capsule anteriorly and reflecting the patella downwards.

Infrapatellar fat pad

Deep to the patellar ligament is a quantity of fat (Fig. 6.74), which bulges the synovial membrane into the interior of the joint. Folds of synovial membrane, the alar folds (Fig. 6.81), extend on either side from the main pad. Another fold, the ligamentum mucosum, lies in the midline between the anterior part of the intercondylar notch and the lower margin of the patella.

Synovial membrane and bursae

Synovial membrane lines the interior of the capsule but does not cover the menisci. On the femur, it is attached to the margins of the intercondylar notch and covers the front and sides of the cruciate ligaments. Synovial membrane also covers the infrapatellar fat pad and the tendon of popliteus.

The suprapatellar bursa (Fig. 6.81; Fig. 6.74) is a large pouch of synovial membrane, passing a hand's breadth proximal to the upper border of the patella, deep to quadriceps. Part of vastus intermedius attaches to it. Since the bursa is continuous with the synovial cavity of the joint, it provides a route for injecting fluid into or withdrawing fluid from the joint. After injuries to the joint, fluid accumulates (effusion) in the suprapatellar bursa, causing typical fullness around the knee and the basis for the patellar-tap test. Several other bursae lie near the knee joint and may enlarge, causing swelling. Bursae between the capsule and the two heads of gastrocnemius often communicate with the knee joint, while that beneath the medial head may also communicate with the overlying semimembranosus bursa. Other bursae, which do not communicate with the joint, are the pre- and infrapatellar bursae beneath the skin covering the patella and patellar ligament, respectively. These may also enlarge.

Popliteus

From its tibial attachment, the popliteus passes upwards and laterally (Fig. 6.76), penetrating the posterior aspect of the capsule of the knee joint deep to the arcuate ligament. Within the joint, its tendon, covered by synovial membrane, attaches to the posterior border of the lateral meniscus and to the femur (Fig. 6.77) immediately below the lateral epicondyle. Popliteus is supplied by the tibial nerve and its actions are considered below.

Movements

The principal movements of the knee joint are flexion and extension. Flexion is produced mainly by the hamstrings (semimembranosus, semitendinosus and biceps) assisted by the two heads of gastrocnemius. Extension is produced by quadriceps femoris acting through the patellar ligament. Gluteus maximus, acting through the iliotibial tract, maintains stability of the knee in the extended position.

Because of the shape of the articular surfaces, the femur rotates medially during the later stages of extension. The lateral condyle and meniscus (moving in unison because of the meniscofemoral ligament) glide forwards on the lateral tibial condyle, while the medial condyle completes its movement of extension on the medial meniscus. Full extension is achieved with completion of medial rotation and further movement is prevented by tension in the collateral and oblique posterior ligaments. During the early stages of flexion, lateral rotation of the femur on the tibia is produced by popliteus, which also pulls the lateral meniscus posteriorly. During flexion and extension the patella glides over the patellar surface of the femur.

Slight active rotation of the tibia on the femur can occur when the knee is in a flexed but non-weight-bearing position. Sartorius, gracilis and semitendinosus rotate medially, while biceps femoris rotates laterally.

Stability

The knee joint is very stable. The most important factors are muscle tone, especially in quadriceps and the ligaments. The cruciate ligaments stabilize the femur on the tibia, preventing excessive anteroposterior movement. The collateral ligaments assist medial and lateral stability, while the iliotibial tract stabilizes the knee during extension. All of these ligaments, together with the oblique posterior ligament, prevent hyperextension. Cruciate and collateral ligament injuries together with meniscal tears commonly occur in sports, particularly following twisting movements, during which the foot is anchored to the ground.

Owing to angulation of the femur relative to the tibia, contraction of quadriceps femoris tends to displace the patella laterally. This displacement is prevented, first by the lowest fibres of vastus medialis, which insert into the medial patellar border and whose active contraction resists lateral movement of the patella, and second by the large size and prominence of the lateral femoral condyle, making lateral patellar movement mechanically difficult. Occasionally, the lateral femoral condyle fails to develop normally, resulting in patellar instability.

Innervation

Branches from the femoral, obturator and sciatic nerves supply the joint, sensory fibres from the femoral nerve travelling with the branches to the vasti and sartorius. Genicular branches from the tibial and common fibular divisions of the sciatic nerve, together with fibres from the posterior division of the obturator nerve, also supply the joint.

Blood supply

The knee joint receives its blood supply from the extensive genicular anastomosis derived mainly from branches of the


Popliteus tendon (cut)
Anterior cruciate ligament (cut)
Patellar surface of femur
Posterior cruciate ligament (cut)
A
la
m
P
Tibial collateral ligament (cut)
Horns of medial meniscus
Capsule (cut)
P
la
m
A
Fibular collateral ligament (cut)
Horns of lateral meniscus
Transverse ligament
Ligamentum patellae (cut)

Fig. 6.82 Disarticulation of joint reveals menisci and attachments of cruciate ligaments.

popliteal, anterior and posterior tibial arteries (Fig. 1.27). Dislocation of the knee may damage the popliteal artery and seriously compromise the blood supply to the leg and foot. It may also damage the tibial and common peroneal (fibular) nerves causing loss of sensation and movement below the level of the knee.

Tibiofibular Joints

The tibia and fibula articulate at proximal and distal tibiofibular joints and are also connected by an interosseous membrane (Fig. 6.83), which unites the interosseous borders of the bones and separates the flexor and extensor compartments of the leg.

The proximal tibiofibular joint is a plane synovial articulation between the lateral condyle of the tibia and head of the fibula, and is supplied by the common fibular nerve. The capsule is reinforced by anterior and posterior ligaments, and the synovial cavity does not communicate with the knee joint.

The opposed triangular surfaces at the lower ends of the tibia and fibula are bound together by an interosseous ligament, forming the fibrous distal tibiofibular joint, which is strengthened by anterior and posterior tibiofibular ligaments. The transverse ligament, an inferior extension of the posterior ligament, contributes to the articular socket of the ankle joint (Fig. 6.85), whose cavity frequently extends for a short distance between the tibia and fibula. The ankle is stabilized by the ligaments of the distal tibiofibular joint, which prevent separation of the malleoli. Innervation is by the deep fibular and tibial nerves.

Very little movement occurs at the tibiofibular joints, but slight rotation of the fibula may accompany flexion and extension of the ankle.


Fibular collateral ligament
Proximal tibiofibular joint (opened)
Capsule (cut)
Posterior cruciate ligament (cut)
Anterior tibial artery
Tibial collateral ligament (cut)
Posterior surface of tibia
Interosseous membrane
Posterior tibiofibular ligament
S
m
la
I

Fig. 6.83 Posterior view of tibia and fibula to show tibiofibular joints and interosseous membrane. The lower part of the tibiofibular ligament has been removed.

Ankle Joint

The ankle joint is a synovial hinge joint between the lower ends of the tibia and fibula and the upper part of the talus (Fig. 6.84), and all the articular surfaces are covered by hyaline cartilage. The proximal articular surface comprises the distal end of the tibia and the medial and lateral malleoli, which together form a deep socket (Fig. 6.85), completed posteriorly by the posterior tibiofibular ligament (see below). The socket is wider anteriorly than posteriorly and is completely congruous with the upper part of the talus, which is reciprocally wedge-shaped (Figs 6.84 & 6.86). The articular surface on the lateral side of the talus is more extensive than that on the medial side.




S
la
m
I
Fibula
Inferior surface of tibia
Lateral and medial malleolus
Superior surface of trochlea
Body of talus
Lateral and medial surfaces
Neck
Head
P
la
m
A

Fig. 6.84 Bones of the ankle joint showing their articular surfaces.

Capsule and synovial membrane

The fibrous capsule attaches to the margins of the articular surfaces, but anteriorly extends forwards onto the neck of the talus (Fig. 6.86). The capsule is thin anteriorly and posteriorly, but is reinforced on each side by ligaments. Synovial membrane lines the capsule internally and covers the intracapsular part of the neck of the talus.

Ligaments

The posterior tibiofibular ligament spans the gap between the distal ends of the tibia and fibula, contributing to the articular socket posteriorly (Fig. 6.85). There are two collateral ligaments. The medial (deltoid)




S
m
la
I
Medial malleous
Tibia
Fibula
Joint capsule (cut)
Inferior surface of tibia
Posterior tibiofibular ligament
Lateral malleolus

Fig. 6.85 Oblique inferior view of the wedge-shaped articular socket of the ankle joint.

ligament (Fig. 6.89) is attached by its apex to the tip of the medial malleolus. Its deeper fibres descend to the margin of the articular surface on the medial side of the talus and its longer superficial fibres attach to the tuberosity of the navicular, the medial border of the spring (plantar calcaneonavicular) ligament and the sustentaculum tali.

The lateral ligament has three components: the anterior and posterior talofibular and the calcaneofibular ligaments (Figs 6.87 & 6.88). All attach to the lateral malleolus. The anterior talofibular ligament passes forwards to the lateral side of the neck of the talus, the posterior talofibular ligament medially to the posterior tubercle of the talus, and the calcaneofibular downwards and backwards to the side of the calcaneus. Tearing of the medial and/or lateral collateral ligaments occurs with fractures of one or both malleoli. They are known by the clinical eponym of Pott's fracture.




Lateral malleolus
Fibula
Superior surface of trochlea
S
la
m
I
Medial malleolus
Anterior talofibular ligament
Neck of talus
Medial ligament
Capsule (cut)

Fig. 6.86 Anterior view of the ankle joint showing articular surfaces, revealed by removal of the capsule.




Tendo calcaneus (cut)
Joint capsule
Posterior talofibular ligament
Lateral malleolus
Talus
Anterior talofibular ligament
Capsule (cut)
Calcaneo-fibular ligament
Calcaneus
S
P
A
I

Fig. 6.87 Lateral aspect of joint to show lateral collateral ligament.


Medial malleolus
Medial ligament
Tibia
Trochlea
Fibula
Posterior tibiofibular ligament
Lateral malleolus
Posterior talofibular ligament
Calcaneo-fibular ligament
Calcaneus
Tendo calcaneus (cut)
S
m
la
I

Fig. 6.88 Posterior view of the ankle joint showing the articular surface of talus after removal of the capsule.

Movements

Only extension (dorsiflexion) and flexion (plantar flexion) occur at the ankle joint, around a transverse axis between the malleoli. Plantar flexion is produced by soleus and gastrocnemius, assisted by tibialis posterior, flexors hallucis longus and digitorum longus, and fibularis longus and brevis. Extension (dorsiflexion) is produced by tibialis anterior, extensors hallucis longus and digitorum longus, and fibularis tertius.

Stability

The joint is very stable due to the wedge shape of the articulating surfaces and the strong collateral ligaments. During standing and walking, body weight tends to displace the tibiofibular socket forwards so that it becomes closely packed against the wider anterior part of the talus, which further enhances stability during dorsiflexion. Excessive forward displacement of the tibia and fibula on the talus is prevented by the posterior fibres of the medial (deltoid) ligament and by the calcaneofibular and posterior talofibular ligaments. However, in plantar flexion the narrow part of the talus articulates with the wider anterior part of the socket, allowing some side-to-side movement. In this position, forced inversion of the foot may damage the anterior talofibular ligament, one form of sprained ankle.




Tendon of tibialis anterior (cut)
Sus-tentaculum tali
Trochlea
Tendo calcaneus (cut)
Long plantar ligament
Attachment of tibialis posterior to tuberosity of navicular
Plantar calcaneo-navicular ligament
Medial (deltoid) ligament (superficial part)
Calcaneus
S
A
P
I

Fig. 6.89 Medial (deltoid) ligament (superficial part) of the ankle joint.


Lateral malleolus
Talus
Medial malleolus
Medial ligament (deep part)
Tendons of tibialis posterior and flexor digitorum longus
Sustentaculum tali
Tendon of flexor hallucis longus
Abductor hallucis
Flexor accessorius
S
la
m
I
Abductor digiti minimi
Tendons of peroneus brevis and longus
Flexor digitorum brevis
Heel fat pad

Fig. 6.90 Coronal section through ankle and talocalcaneal joints showing their relations.

Blood and nerve supply

Branches of the anterior and posterior tibial arteries, including the fibular, anastomose at the level of the malleoli and supply the joint. Innervation is from the deep fibular and tibial nerves.

Relations

The sides of the joint, the bony malleoli, are superficial (Fig. 6.90) and easily palpable. Passing subcutaneously in front of the joint are branches of the superficial fibular nerve and, just anterior to the medial malleolus, the saphenous nerve and great saphenous vein. On a deeper plane are the tendons of tibialis anterior and extensor hallucis longus, the dorsalis pedis artery, the deep fibular nerve, and the tendons of extensor digitorum longus and fibularis tertius (Fig. 6.91).

Posteriorly, the tendo calcaneus (Achilles) lies separated from the joint capsule by a bursa and pad of fat. Behind the medial malleolus are the tendons of tibialis posterior, flexor digitorum longus and flexor hallucis longus (Fig. 6.90), accompanied by the tibial nerve and posterior tibial artery (Fig. 6.91). Passing below the medial malleolus, they enter the foot beneath the flexor retinaculum. Passing superficially behind the lateral malleolus are the small saphenous vein and sural nerve and, more deeply, the tendons of fibularis longus and brevis (Fig. 6.91).


Tendon of tibialis anterior
Tendon of extensor hallucis longus
Great saphenous vein
Tibia
Tendons of tibialis posterior and flexor digitorum longus
Posterior tibial artery and tibial nerve
Tendon of flexor hallucis longus
Tendo calcaneus
Deep peroneal nerve
Tendon of extensor digitorum longus
Anterior tibial artery with venae comitantes
Lateral malleolus
Tendons of fibularis longus and brevis
Sural nerve
Short saphenous vein
A
m
la
P

Fig. 6.91 Transverse section immediately above the ankle joint cavity showing relations.

Joints of the Foot

These joints include those between the tarsal bones, the metatarsals and the phalanges. They are all synovial and have shapes related to their movements.

Tarsal joints

Although the tarsal joints are articulations between individual bones, they are usually classified into groups according to their locations (Fig. 6.92). The posterior tarsal group involves the talus and calcaneus; the midtarsals are between the talus and navicular on the medial side of the foot and between the calcaneus and cuboid on the lateral side; the anterior tarsals include the navicular, three cuneiforms and cuboid. All these joints are extremely stable.

Talocalcaneal joint

There are two articulations between the talus and calcaneus, each with a separate synovial cavity. Posteriorly is a saddle joint between the convex surface on the middle third of the calcaneus and the reciprocally concave surface on the body of the talus (Fig. 6.93). Anteriorly, two small flat facets on the anterior part of the calcaneus, including the sustentaculum tali, articulate with corresponding facets beneath the head of the talus (Fig. 6.93).


S
la
m
I
Medial malleolus
Medial collateral (deltoid) ligament
Trochlea and head of talus
Calcaneus
Navicular
Cuboid
Interosseous ligaments

Fig. 6.92 Sections in two different planes through the ankle and foot to show ankle and tarsal joints.


Attachment of tibialis anterior (cut)
Anterior articular facets
Head of talus
Facet for sustentaculum tali
Interosseous ligament (cut)
A
la
m
P
Dorsal ligaments
Navicular
Bifurcated ligament
Plantar calcaneonavicular ligament
Posterior articular surfaces
A
m
la
P
Tendo calcaneus (cut)

Fig. 6.93 Talocalcaneal and talonavicular joints. The talus has been disarticulated and turned over.

Talonavicular joint

The head of the talus forms a ball-and-socket joint with the posterior surface of the navicular. This joint shares a common synovial cavity with the anterior part of the talocalcaneal articulation. The combined joint, which involves the head of the talus, is termed the talocalcaneonavicular joint. The posterior talocalcaneal and talocalcaneonavicular joints form the subtalar joint.

Calcaneocuboid joint

At this plane joint, the flat anterior surface of the calcaneus articulates with the posterior surface of the cuboid (Fig. 6.92).



Fig. 6.94 Radiograph of juvenile foot showing tarsal bones and joints.

Other tarsal joints

Plane joints occur between the opposing surfaces of the navicular, the three cuneiforms and the cuboid (Fig. 6.92) and their synovial cavities freely communicate.

Capsules and ligaments

The fibrous capsules are attached around the margins of the articular surfaces. Short ligaments on the dorsum of the joints (Fig. 6.93) reinforce the capsules and, with the interosseous ligaments (Fig. 6.92), keep the articulating surfaces closely opposed. The strong interosseous talocalcaneal ligament (Fig. 6.93) in the sinus tarsi holds the talus and calcaneus together. The stem of the bifurcated ligament attaches to the anterior part of the calcaneus and its limbs to the navicular and cuboid. Beneath the tarsals, the long and short plantar ligaments (Fig. 6.56) unite the plantar surfaces of the calcaneus and cuboid. The plantar calcaneonavicular (spring) ligament (Fig. 6.93) unites the navicular and sustentaculum tali, supporting the head of the talus and completing the socket by which the head articulates with the navicular and calcaneus.

Movements

The most mobile of the tarsal joints is the talocalcaneonavicular joint. Its ball-and-socket shape permits rotation around an oblique axis, which passes upwards, forwards and medially through the neck and head of the talus. This rotation, together with gliding movements at the other tarsal joints, enables the anterior part of the foot to twist in respect to the more posterior part. These twisting movements involve raising either the medial or lateral border of the foot. Raising the medial border is called inversion and is produced by tibialis anterior and posterior, assisted by extensor hallucis longus. Raising the lateral border is called eversion and is brought about by fibularis longus, brevis and tertius.

Because of the oblique axis of the talocalcaneonavicular joint, inversion is always accompanied by plantar flexion and adduction of the foot, while eversion is accompanied by dorsiflexion and abduction. These additional movements can be compensated by simultaneous movements at other joints. Thus, the plantar flexion accompanying inversion can be offset by slight dorsiflexion at the ankle joint, while adduction can be offset by lateral rotation of the leg at the knee and hip joints.

Innervation

The tarsal joints are innervated by branches of the medial and lateral plantar nerves and the deep fibular nerve.

Tarsometatarsal and intermetatarsal joints

These are plane joints in which the bases of the fourth and fifth metatarsals articulate with the cuboid, while the bases of the first, second and third metatarsals articulate with the respective cuneiforms (Fig. 6.94). Dorsal, plantar and interosseous ligaments reinforce the joint capsules. These joints allow gliding movements during alterations in the height of the arches. Innervation is by plantar and deep fibular nerves.

Metatarsophalangeal and interphalangeal joints

In each of the ball-and-socket metatarsophalangeal joints, the metatarsal head articulates with the base of the proximal phalanx and the associated fibrocartilaginous plantar plate (Figs 6.95 & 6.96). A capsule enclosing the articular surfaces is reinforced on each side by a collateral ligament and dorsally by the extensor expansion. The principal movements are flexion and extension with only minimal abduction or adduction. The first metatarsophalangeal joint is especially important, bearing body weight during walking. Two sesamoid bones (Figs 6.101 & 6.102) are usually present in the plantar plate of this joint, closely associated with the insertions of the intrinsic muscles of the great toe (p. 282).

The interphalangeal joints (Figs 6.95 & 6.97) are hinge joints, allowing flexion and extension. The muscles moving these joints are described on p. 282. The joints of the toes are innervated by digital branches of the medial and lateral plantar nerves.


Distal interphalangeal joint
Tendon of flexor digitorum longus (displaced from sheath)
S
A
P
I
Metatarso-phalangeal joint
Tendon sheath
Plantar plate

Fig. 6.95 Sagittal section through the third toe showing the metatarsophalangeal and interphalangeal joints.


Head of first metatarsal (bisected)
Articular cartilage on base of proximal phalanx
Plantar plate
S
A
P
I
Joint capsule (cut)
Tendon of flexor hallucis longus
Fibrous slip of plantar aponeurosis

Fig. 6.96 Internal features of the first metatarsophalangeal joint. Part of the capsule and the distal part of the metatarsal bone have been removed.


A
m
la
P
Proximal phalanx
Joint capsule
Head of metatarsal

Fig. 6.97 Longitudinal section through the great toe showing its joints.

Arches of the Foot

The tarsal and metatarsal bones form two longitudinal arches, medial and lateral. The medial arch is higher, forming the instep of the foot, and consists of the calcaneus, talus, navicular, three cuneiforms, and medial three metatarsals (Figs 6.98, 6.99 & 6.100). The lateral arch comprises the calcaneus, cuboid and lateral two metatarsals (Fig. 6.98). Each arch has an anterior and a posterior pillar, which together transmit body weight to the ground. The posterior pillar of each arch is the same, namely the tubercles on the inferior surface of the calcaneus. However, the anterior pillars are separate, being formed by the heads of the appropriate metatarsals. The arches are important in relation to human bipedalism, as they enhance forward propulsion.


Medial intermediate and lateral cuneiforms
Base and head of metatarsal
Proximal, middle and distal phalanges
A
m
la
P
Navicular
Talus
Calcaneus
Cuboid
Styloid process
Medial longitudinal arch
Lateral longitudinal arch

Fig. 6.98 Dorsal aspect of the bones of the foot showing the medial and lateral longitudinal arches.


Medial cuneiform
Navicular
Medial longitudinal arch
S
A
P
I
Proximal and distal phalanges
Head of first metatarsal
Head of talus
Sustentaculum tali
Tubercle on calcaneus

Fig. 6.99 Medial aspect of the bones of the foot to show the medial longitudinal arch.


Head of first metatarsal
Cuneiform
Navicular
Head of talus
Dome of talus
Sesamoid bone
Bases of first and fifth metatarsals
Cuboid
Sustentaculum tali
Tubercle on calcaneus

Fig. 6.100 Radiograph of foot showing longitudinal arches.

Stability

Factors in maintaining the arches include skeletal structure, ligaments, the plantar aponeurosis, and tendons and muscles. Skeletal structure is important in the medial arch, where at its highest point the head of the talus articulates in a wedge-like manner with the navicular anteriorly and the sustentaculum tali posteriorly (Figs 6.101 & 6.102). The head of the talus is supported inferiorly by the plantar calcaneonavicular (spring) ligament (Figs 6.93, 6.101), lying immediately above the tendon of flexor hallucis longus and a slip from the tendon of tibialis posterior, which passes backwards to the sustentaculum tali (Fig. 6.56). Tibialis anterior, through the attachment of its tendon to the first cuneiform and first metatarsal, may also support the medial arch, which it raises during inversion.

The lateral arch is supported by the long and short plantar ligaments and the tendon of fibularis longus. Both longitudinal arches derive support from the long flexor tendons of the toes and from the plantar aponeurosis, whose digital slips gain indirect attachment to the proximal phalanges (Fig. 6.96). When the heel rises from the ground the aponeurosis is passively tightened by extension of the toes at the metatarsophalangeal joints, thereby raising the longitudinal arches.


Navicular
Head of talus
Tibia
S
A
P
I
Medial cuneiform
Head of first metatarsal
Sesamoid bone
Tendon of extensor hallucis longus
Tendon of flexor hallucis longus
Inter-osseous talo-calcaneal ligament
Sustentaculum tali
Calcaneus
Plantar calcaneo-navicular ligament
Intrinsic muscles
Heel fat pad
Plantar aponeurosis

Fig. 6.101 Sagittal section of foot showing the medial longitudinal arch.


Head of first metatarsal
Medial cuneiform
Navicular
Head of talus
Sustentaculum tali
Tendon of flexor hallucis longus
Sesamoid bone
Plantar calcaneonavicular ligament
Plantar aponeurosis
Heel fat pad
Calcaneus

Fig. 6.102 MRI sagittal scan of foot and ankle.

Exam Skills

Each of the incomplete statements below is followed by five suggested answers or completions. Decide which are true and which are false. The answers are supplied on p. 417.

1. The gluteus maximus muscle:

a) has distal attachment principally to the iliotibial tract.
b) has a bursa separating it from the ischial tuberosity.
c) extends the hip and flexes the knee.
d) is supplied by the inferior gluteal nerve.
e) is attached to the sacrotuberous ligament.

2. Gluteus minimus muscle:

a) attaches to the anterior surface of the greater trochanter.
b) is supplied by the superior gluteal nerve.
c) is covered by the gluteus medius.
d) laterally rotates the hip.
e) during walking contracts in the weight-bearing limb.

3. Concerning nerves in the lower limb:

a) the sciatic nerve passes through the greater sciatic foramen.
b) the obturator nerve innervates the obturator internus.
c) the femoral nerve lies in the femoral sheath.
d) the lateral cutaneous nerve of the thigh passes through the inguinal ligament.
e) the genitofemoral nerve innervates skin on the anterior surface of the thigh.

4. Dermatomes in the lower limbs are located:

a) over the femoral triangle for L1.
b) along the medial border of the foot for L5.
c) over the gluteal region for S3.
d) over the footprint on the sole of the foot for S1.
e) on the lateral side of the leg for L4.

5. Concerning muscles in the thigh:

a) adductor longus separates the femoral from the profunda vessels.
b) vastus medialis forms the lateral wall of the adductor canal.
c) vastus intermedius attaches to the capsule of the knee joint.
d) iliopsoas forms the medial part of floor of the femoral triangle.
e) obturator externus lies below the capsule of the hip joint.

6. The femoral nerve:

a) has root origins from L2, L3 and L4 spinal cord segments.
b) lies lateral to the femoral artery.
c) gives cutaneous branches to the lateral side of the thigh.
d) supplies the sartorius muscle.
e) has a branch passing distally to supply the medial side of the foot.

7. The obturator nerve:

a) supplies obturator externus.
b) innervates the gracilis muscle.
c) has two divisions separated by adductor brevis.
d) supplies skin on the medial side of the thigh.
e) gives branches to the knee and hip joints.

8. Concerning the hip joint:

a) iliopsoas is a powerful flexor and medial rotator.
b) posterior dislocation endangers the sciatic nerve.
c) the surface marking lies just below the midinguinal point.
d) the iliofemoral ligament prevents backward tilting of the pelvis.
e) the neck of the femur lies intracapsular.

9. Concerning the patella:

a) the medial femoral condyle provides stability.
b) when dislocated it displaces laterally.
c) dislocation is more common in the female.
d) vastus medialis is attached to its medial border.
e) the prepatellar bursa is subcutaneous.

10. Concerning arteries in the lower limb:

a) the femoral artery is palpable at the midpoint of the inguinal ligament.
b) the popliteal artery lies close to the capsule of the knee joint.
c) the anterior tibial artery arises in the posterior compartment of the leg.
d) the posterior tibial artery passes behind the lateral malleolus.
e) the dorsalis pedis artery anastomoses with the plantar arch.

11. Concerning venous drainage of the lower limb:

a) communicating (perforating) veins direct blood from superficial to deep veins.
b) the great saphenous vein lies anterior to the medial malleolus.
c) the deep veins below the level of the knee comprise venae comitantes.
d) the small saphenous vein is accompanied by the sural nerve.
e) the superficial epigastric vein drains directly into the femoral vein.

12. Regarding the femoral sheath and its contents:

a) fascia iliaca forms the posterior part of the sheath.
b) the femoral vein lies in the lateral compartment.
c) branches of the ilioinguinal nerve pass anteriorly.
d) the femoral canal and ring are in the medial compartment.
e) pectineus muscle lies posteriorly.

13. Concerning the lymphatic system of the lower limb:

a) the main drainage is to inguinal lymph nodes.
b) skin on the lateral side of the foot drains into popliteal nodes.
c) superficial inguinal nodes drain the lower part of the anal canal.
d) lymph from the lower limb will reach the lumbar lymph trunk.
e) deep parts of the buttock drain into the deep inguinal nodes.

14. Concerning inversion and eversion of the foot:

a) inversion is produced by tibialis anterior.
b) inversion is produced by tibialis posterior.
c) inversion and eversion involve the subtalar joints.
d) inversion is produced by fibularis (peroneus) tertius.
e) eversion is produced by fibularis (peroneus) longus.

15. Concerning the knee joint:

a) the suprapatellar bursa reaches a hand's breadth above the patella.
b) the popliteus muscle attaches to the medial meniscus.
c) the tibial collateral ligament attaches to the medial meniscus.
d) the oblique popliteal ligament is derived from semimembranosus tendon.
e) the collateral ligaments limit extension.

16. Concerning the ankle joint:

a) forced eversion may tear the anterior talofibular ligament.
b) the calcaneofibular ligament prevents forward displacement.
c) the capsule extends onto the neck of the talus.
d) part of the innervation is from the deep fibular (peroneal) nerve.
e) it is less stable when plantar flexed.

Clinical Case Skills

The answers are supplied on p. 419.

Case Study 1

A 24-year-old athletic male soccer player was brought to the Emergency Department with a history of having fallen hard during a game and twisting his knee after being tripped.

On examination, he was lying with his left knee partially flexed. It was beginning to swell with fullness visible at the sides and above the patella, together with a slight patellar tap. All passive movements were painful. There was localized pain on deep pressure just medial to the patellar ligament over the joint line, and also severe pain over the joint line on the medial border of the knee. It became excruciating with firm medial-ward pressure applied over the lateral side of the joint at the same time as attempted abduction of the leg at the knee.

A plain frontal radiograph, including a film taken while manoeuvring the joint as described with attempted abduction of the leg at the knee, showed inequality of the femur/tibia joint line with widening on the medial side.

Questions:

1. What is the anatomical basis for patellar tap?
2. What structure was injured to be the cause of pain on deep pressure medial to the patellar ligament?
3. What structure was injured to explain pain on the medial border of the knee, accentuated by pressure over the lateral side with concomitant abduction of the leg?
4. Which ligaments are extracapsular and which are intracapsular? What are their roles in stabilizing the joint?

Case Study 2

A 45-year-old female shop assistant complained of pain and aching in her right leg over a period of several years. The symptoms were particularly bad at the end of the day. Recently, a lump had appeared in the left groin, which disappeared when she lay down on her bed, but reappeared on rising in the morning, and it became bigger when she coughed.

The patient was tall and not overweight. On standing, a large tortuous vein appeared beneath the skin, extending from the foot up the medial side of the limb into the groin. There was also a swelling, the size of an egg, just below the medial part of the crease in the groin. It disappeared when the patient was recumbent and especially if the limb was elevated.

The swelling, lying below and lateral to the pubic tubercle, had a smooth surface, was soft and uniform, and could be easily compressed. A direct impulse and thrill could be felt when the patient coughed. A large varicose vein was present along the whole length of the medial side of the limb. Trendelenburg's test was positive.

Questions:

1. Which vein was varicose?
2. What structure was giving rise to the swelling in the groin, and why was there a thrill over it when the patient coughed?
3. What mechanism is important in venous return from the lower limb and at what levels in the limb does it operate?
4. Swellings in the groin are common. What other structures may cause swellings here?

Case Study 3

The patient was a 60-year-old man with diabetes. For more than a year he had experienced increasing difficulty in walking due to cramps and pain in the calves of his legs. Although the pain was easier when he rested, it was becoming severe even at rest and interfered with his sleep at night. In the past 2 months he had noticed a black area at the end of his right big toe, which was getting worse.

The skin of both lower limbs, especially below the knee, was shiny, thin and hairless. No arterial pulses could be felt in the limb on the right side. The skin over the distal half of the right hallux was shrunken and black, being gangrenous with a sharp line of demarcation separating it from the more proximal part of the toe.

An arteriogram showed severe and widespread narrowing with irregularity of the walls and occlusion of the main artery just above the adductor tubercle. Extensive collaterals were present above and around the knee.

Questions:

1. Where is an arteriogram performed in the lower limb and why?
2. Where are the locations for detecting arterial pulsation in the lower limb?
3. What comprises the genicular anastomosis and which arteries contribute?

Case Study 4

A 20-year-old man presented to the neurology clinic with a 5-month history of weakness in the left leg and numbness in the left foot. There was a 6-month previous history of a chest infection during an overseas holiday, for which he was given two intramuscular injections in the left gluteal region.

The patient walked without any obvious limp although slight foot-drop was evident on the left side. There was weakness of plantar flexion, and further weakness on flexing the hallux. Midcalf wasting was evident on the left side. Diminished pain and touch sensation was noted over the left sole of the foot and the ankle-jerk reflex was absent.

Motor nerve conduction studies showed slowing of conduction in the left common fibular (peroneal) nerve compared with the right side, and sensory nerve conduction studies showed slowing in the left sural nerve compared with the right side.

Questions:

1. What nerve supplies the posterior compartments in the lower limb, and which of its branches supplies the muscles of the posterior compartment of the leg?
2. What does wasting of the calf muscles indicate about the level of the lesion?

Observation Skills

Identify the structures indicated. The answers are supplied at the foot of the page.



Fig. 6.103 Sagittal section of knee.

Answers:

Fig. 6.103 1 = vastus intermedius; 2 = quadriceps tendon; 3 = suprapatellar bursa; 4 = patella; 5 = infrapatellar fatpad; 6 = prepatellar bursa; 7 = patellar ligament; 8 = infra patellar bursae superficial and deep; 9 = popliteus; 10 = popliteal artery and vein; 11 = soleus; 12 = gastrocnemius; 13 = anterior and posterior cruciate ligaments; 14 = popliteal artery and vein; 15 = hamstring.



Fig. 6.104 Sagittal MRI section of knee.

Answers:

Fig. 6.104 1 = posterior cruciate ligament; 2 = gastrocnemius; 3 = popliteus; 4 = patella; 5 = patellar ligament; 6 = infrapatellar fatpad; 7 = anteriour cruciate ligament.



Fig. 6.105 Transverse section of leg.



Fig. 6.106 Transverse section of thigh.

Answers:

Fig. 6.105 1 = interosseous membrane; 2 = tibialis anterior; 3 = tibia; 4 = tibialis posterior; 5 = saphenous nerve; 6 = great saphenous vein; 7 = flexor digitorum longus; 8 = soleus; 9 = medial head of gastrocnemius; 10 = sural nerve; 11 = small saphenous vein; 12 = lateral head of gastrocnemius; 13 = deep veins; 14 = posterior tibial artery; 15 = fibula; 16 = peroneal muscles; 17 = anterior tibial artery; 18 = extensor digitorum longus.

Fig. 6.106 1 = rectus femoris; 2 = vastus intermedius; 3 = vastus medialis; 4 = sartorius; 5 = femoral artery and vein; 6 = great saphenous vein; 7 = adductor longus; 8 = adductor magnus; 9 = gracilis; 10 = semimembranosus; 11 = semitendinosus; 12 = long head of biceps femoris; 13 = sciatic nerve; 14 = short head of biceps femoris; 15 = profunda femoris vessels; 16 = vastus lateralis.



Fig. 6.107 Coronal section of ankle.

Answers:

Fig. 6.107 1 = peroneal muscles; 2 = lateral malleolus; 3 = body of talus; 4 = interosseous talocalcaneal ligament; 5 = fibularis brevis tendon; 6 = calcaneum; 7 = fibularis longus tendon; 8 = abductor digiti minimi; 9 = flexor digitorum brevis; 10 = quadratus plantae; 11 = abductor hallucis; 12 = flexor hallucis longus tendon; 13 = flexor digitorum longus tendon; 14 = tibialis posterior tendon; 15 = medial ligament; 16 = medial malleolus.



Fig. 6.108 Oblique radiograph of ankle and anteroposterior radiograph of foot.



Fig. 6.109 Lateral radiograph of juvenile ankle.

Answers:

Fig. 6.108 1 = head of talus; 2 = navicular; 3 = base of fifth metatarsal; 4 = cuboid; 5 = calcaneocuboid joint; 6 = calcaneum; 7 = tubercle for tendo calcaneus.

Fig. 6.109 1 = epiphysis on distal end of tibia; 2 = dome of talus; 3 = subtalar joint; 4 = posterior traction epiphysis on calcaneum; 5 = medial cuneiform; 6 = navicular; 7 = talonavicular joint; 8 = head of talus; 9 = ankle joint.

Chapter 7

HEAD AND NECK

Introduction 322
Neck 324
  Fascial layers 324
  Sternocleidomastoid (sternomastoid) 325
  Posterior triangle of neck 326
  Cervical plexus 326
  Anterior triangle of neck 327
  Ansa cervicalis 329
  Thyroid gland 329
  Root of neck 330
Contents of the Carotid Sheath 332
  Carotid arteries 332
  Internal jugular vein 333
  Nerves 333
  Lymphatics 334
Superficial Structures of the Face and Scalp 335
  Muscles of facial expression 335
  Facial nerve 336
  Blood supply of face 337
  Sensory supply 337
Parotid Gland 339
  Structures traversing parotid gland 340
  Neurovascular supply 341
Masseter, Temporalis and Infratemporal Fossa 342
  Masseter 342
  Temporalis 342
  Infratemporal fossa 342
Digastric and Styloid Muscles 347
  Digastric 348
  Muscles of styloid process 348
Mylohyoid and Related Structures 349
  Mylohyoid 350
  Geniohyoid 350
  Tongue 350
  Submandibular and sublingual glands 352
  Hypoglossal (XII) nerve 352
  Glossopharyngeal (IX) nerve 352
Pterygopalatine Fossa 353
  Maxillary (V_2) division of the trigeminal nerve 353
  Pterygopalatine ganglion 354
  Vessels 355
Nasal Cavities and Paranasal Air Sinuses 356
  Nasal cavities 356
  Paranasal air sinuses 358
Palate 361
  Hard palate 361
  Soft palate 361
Pharynx 363
  Muscles 363
  Nerve supply 364
  Pharyngobasilar fascia and auditory tube 364
  Lymphoid tissue 365
  Blood supply 365
Larynx 366
  Skeleton 366
  Membranes and ligaments 368
  Intrinsic muscles 368
  Nerve supply 370
  Blood supply 371
Cranium and Contents 372
  Bony features 372
  Meninges 374
  Arterial supply to the brain 376
  Cranial nerves 378
Orbit 379
  Bony walls 379
  Fascial layers 380
  Eyelids, conjunctiva and lacrimal apparatus 380
  Extraocular muscles 380
  Movements of the eyeball and eyelid 382
  Nerves 382
  Vessels 384
Exam Skills 385
Clinical Case Skills 386
Observation Skills 387

Introduction

The bones of the head and neck include the skull, the mandible and the cervical vertebrae (Fig. 7.1). The skull (cranium) comprises the neurocranium, which contains the brain and meninges, and the bones of the face (viscerocranium), attached to the anterior aspect of the neurocranium and clothed by soft tissues. The facial bones enclose the orbits, the nose and paranasal air sinuses, and the mouth and pharynx. The mandible articulates with the neurocranium at the temporomandibular joints.

The neck is the junctional region between the head and the thorax and the upper limbs, and is bounded above by the mandible and the base of the skull and below by the superior thoracic aperture (thoracic inlet) and pectoral girdle. The neck contains the seven cervical vertebrae and associated muscles, parts of the alimentary and respiratory tracts and the thyroid gland. In the midline immediately anterior to the vertebrae is the pharynx, which continues as the cervical oesophagus. Anterior to these are the larynx and upper trachea with the thyroid gland. On each side of the organs, major vessels pass between the thorax and the head, accompanied by nerves and lymphatics. The cervical vertebrae support the skull, allowing it to be moved in relation to the trunk. Within the cervical vertebral column lies the vertebral canal, containing the spinal cord enclosed by meninges. The neck is enclosed by investing fascia, subcutaneous tissue and skin.

Arising from the brainstem are 12 pairs of cranial nerves (Fig. 7.2), which provide innervation for structures in the head and neck. One cranial nerve, the vagus (X), is distributed not only to the head and neck but also to structures in the thorax and abdomen. Eight pairs of segmental spinal nerves arise from the cervical part of the spinal cord. The upper cervical spinal nerves are distributed to the head and neck, whereas the lower ones descend into the upper limbs and thorax. Dermatomes of the head and neck are derived from the trigeminal (V) nerve and from cervical spinal nerves (Fig. 7.3).



Fig. 7.1 Skeleton of head and neck. Boundary of neck (pink line).



Fig. 7.2 Extracranial parts of cranial nerves III–VII and IX–XII.


S
A
P
I
V_1 ophthalmic
V_2 maxillary
V_3 mandibular
C2
C3
C4

Fig. 7.3 The dermatomes of the head and neck. Cutaneous nerves are shown in yellow.

The arterial supply to the head and neck (Fig. 7.4) is derived from the paired common carotid and vertebral arteries. Each common carotid artery divides to form an internal carotid artery, supplying the contents of the neurocranium and the orbit, and an external carotid artery which supplies the face, most of the scalp and the upper part of the neck. Branches from the subclavian arteries supply structures in the root of the neck. Each vertebral artery ascends through foramina in the transverse processes of the cervical vertebrae and enters the skull via the foramen magnum to assist in the supply to intracranial structures.

Venous drainage (Fig. 7.4) occurs through superficial and deep systems, which communicate in several places. Superficial veins of the face, scalp and neck drain via the external jugular veins into the subclavian veins. Blood from deeper structures of the face and from within the neurocranium drains through the internal jugular veins into the brachiocephalic veins.

Lymph drains through a chain of lymph vessels and nodes lying along the internal jugular vein and is returned to the venous system, usually at the junction of internal jugular and subclavian veins.


S
A
P
I
Internal carotid artery
External carotid artery
Vertebral artery
Common carotid artery
S
A
P
I
Retromandibular vein
External jugular vein
Anterior jugular vein
Vertebral vein
Internal jugular vein
Deep veins
Superficial veins

Fig. 7.4 The main arteries and veins of the head and neck.

Neck

Fascial layers

These are complex and are divided into four components: investing fascia, prevertebral fascia, pretracheal fascia and carotid sheaths (Fig. 7.5). The investing fascia is analogous to deep fascia in the limbs. Deep to the skin and superficial tissues, it surrounds the neck, extending from the pectoral girdle below to the base of the skull and mandible above, and splits to enclose trapezius and sternocleidomastoid. Superiorly, the investing fascia is attached to the superior nuchal lines and to the mastoid processes. Between the mastoid process and the angle of the mandible the fascia encloses the parotid gland. Its superficial layer passes superiorly over the surface of the gland to attach to the zygomatic arch; on its deep surface the fascia is thickened to form the stylomandibular ligament. Inferiorly, the investing fascia is attached to the spine of the scapula, the acromion, the superior border of the clavicle, and the manubrium.




A
L
R
P
Investing fascia
Pretracheal fascia
Prevertebral fascia
External jugular vein

Fig. 7.5 Transverse section at the level of the fourth cervical vertebra showing the layers of cervical fascia (green lines). Superior aspect. (Compare Fig 7.95.) The layers are shown separately in the diagrams below.


Sternocleidomastoid
Submandibular gland
Trapezius
Prevertebral muscles
Vertebral artery
Postvertebral muscles
Spinal cord
Vagus nerve
Larynx and pharynx
Carotid sheath
External carotid artery
Internal carotid artery
Internal jugular vein

The investing fascia and its enclosures.

The prevertebral fascia and its enclosures.

The pretracheal fascia and carotid sheaths and their enclosures.

The prevertebral fascia encloses the vertebral column, pre- and postvertebral muscles and origins of the cervical and brachial plexuses. Superiorly, it attaches to the base of the skull and inferiorly, it extends into the superior mediastinum.

The pretracheal fascia covers the anterior and lateral aspects of the trachea and larynx, limited superiorly by the hyoid bone and by the oblique lines on the thyroid cartilage. It splits to enclose the thyroid gland and inferiorly fuses with the adventitia of the aortic arch in the superior mediastinum. Posterolaterally on each side, the pretracheal fascia blends with the carotid sheath.

Each of the two carotid sheaths contains a common, an internal and part of an external carotid artery, a vagus nerve and an internal jugular vein. The sheaths are attached to the base of the skull around the jugular and carotid foramina and pass inferiorly to the aortic arch and brachiocephalic veins to fuse with the adventitia covering these vessels.

Infection can track superiorly and inferiorly between these fascial layers.

For purposes of anatomical description, the superficial part of each side of the neck is divided into anterior and posterior triangles separated by sternocleidomastoid.

Sternocleidomastoid (sternomastoid)

This muscle passes obliquely upwards and backwards from the manubrium and the medial end of the clavicle to the mastoid process and superior nuchal line of the skull (Fig. 7.6). One sternocleidomastoid acting alone turns the head towards the opposite shoulder, whereas acting together both muscles protrude the head forwards. Sternocleidomastoid is innervated by the spinal part of the accessory nerve (XI).



Fig. 7.6 Oblique view of the neck showing sternocleidomastoid after removal of the investing fascia covering sternocleidomastoid and trapezius.

Posterior triangle of neck

This triangle is bounded anteriorly by sternocleidomastoid and posteriorly by trapezius. Inferiorly, the upper border of the clavicle forms the base, while superiorly, the attachments of sternocleidomastoid and trapezius converge onto the superior nuchal line to form the apex of the triangle. The posterior triangle does not lie in a flat plane but spirals so that the inferior portion is directed anteriorly, while the apex faces posterolaterally.

Roof

The roof of the triangle is formed by the investing fascia, which spans the interval between trapezius and sternocleidomastoid. The external jugular vein initially lies vertically over the sternocleidomastoid just beneath the skin and then passes onto the roof of the lower part of the triangle. The vein pierces the roof just above the clavicle to enter the triangle and drain into the subclavian vein. Cutaneous branches of the cervical plexus also lie superficial to the roof of the triangle (Fig. 7.7).

Floor

The floor of the posterior triangle is formed by the prevertebral fascia covering the paravertebral muscles, which are, from above downwards, splenius capitis, levator scapulae and scalenus posterior, medius and anterior (Fig. 7.8). Deep to the prevertebral fascia are the subclavian artery, the three trunks of the brachial plexus and the cervical plexus. Continuing laterally to reach the axilla, the brachial plexus and the subclavian artery are enclosed in a prolongation of the prevertebral fascia, the axillary sheath. Injection of local anaesthetic inside the axillary sheath blocks sensation from the upper limb. Deep to the scalene muscles, subclavian vessels and brachial plexus are the pleura and apex of the lung. These are vulnerable to accidental penetration during cannulation of the subclavian vessels.

Contents

Between the floor and the roof of the triangle lie the contents (Fig. 7.9), which include a number of vascular structures, the spinal part of the accessory (XI) nerve, components of the cervical plexus and supraclavicular and occipital lymph nodes. The spinal part of the accessory nerve passes obliquely across the triangle from beneath the posterior border of sternocleidomastoid to leave deep to the anterior border of trapezius. It supplies both of these muscles. In the lower part of the triangle the inferior belly of omohyoid passes towards its scapular attachment. Two branches of the thyrocervical trunk, namely the transverse cervical and suprascapular arteries, also pass laterally across the triangle to the scapula. At the apex of the triangle the occipital artery emerges to supply part of the scalp. The subclavian vein is sometimes visible just above the clavicle.

Cervical plexus

The cervical plexus is formed from the anterior rami of the first four cervical spinal nerves and supplies the paravertebral muscles with segmental branches. It provides a branch from C1 to the hypoglossal nerve and branches from C2 and C3, which all contribute to the ansa cervicalis. The phrenic nerve, the principal innervation of the diaphragm, is formed from C3, C4 and C5 and runs vertically downwards on the anterior surface of scalenus anterior, behind the prevertebral fascia.

Sensory branches from the cervical plexus (Fig. 7.7) pass through the triangle and emerge by piercing the roof near the



Fig. 7.7 Boundaries and roof of the posterior triangle of the neck. The external jugular vein and cutaneous branches of the cervical plexus, lying superficial to the roof, are also present.

midpoint of the posterior border of sternocleidomastoid. These convey sensation from the neck, the lower part of the face and pinna, the side of the scalp and the upper part of the thoracic wall. The lesser occipital nerve (C2) ascends along the posterior border of sternocleidomastoid and supplies the side of the occipital region of the scalp. The great auricular nerve (C2 & C3) runs vertically upwards across sternocleidomastoid and conveys sensation from the lower part of the pinna and the skin over the parotid gland. The transverse cervical nerve (C2 & C3) passes horizontally, supplying the skin over sternocleidomastoid and the anterior triangle. Finally, the supraclavicular nerves (C3 & C4) radiate downwards to convey sensation from skin over the upper part of the anterior thoracic wall and the shoulder region.

Anterior triangle of neck

By convention, the two anterior triangles of the neck extend medially to the midline. Posterolaterally, each triangle is bounded by the anterior border of sternocleidomastoid and superiorly by the inferior border of the mandible. That part of the triangle above the hyoid bone will be described with the mylohyoid and related structures.


S
A
P
I
Splenius capitis
Levator scapulae
Dorsal scapular nerve
Scalenus posterior
Long thoracic nerve
Parts of brachial plexus
Supra-scapular nerve
Scalenus medius
Inferior belly of omohyoid
Scalenus anterior
Nerve to subclavius

Fig. 7.8 Floor of the posterior triangle from which the prevertebral fascia has been removed. The inferior belly of the omohyoid muscle, one of the contents of the triangle, is still present.


S
A
P
I
External jugular vein
Lesser occipital nerve
Spinal accessory nerve
Proprioceptive fibres for trapezius
Supra-clavicular nerves
Transverse cervical artery
Inferior belly of omohyoid
Great auricular nerve
Transverse cervical nerve
Anterior jugular vein
Supra-scapular artery
Subclavian vein

Fig. 7.9 Contents of the posterior triangle. The external jugular vein is in continuity with the anterior jugular system.

Roof

The roof of the anterior triangle (Fig. 7.10) is formed by the investing fascia of the neck. Superficial to the fascia are platysma (p. 336) and the anterior jugular vein. This vessel pierces the roof and passes deep to sternocleidomastoid to drain into the external jugular vein just before its termination in the subclavian vein. The cutaneous innervation of the skin over the triangle has already been described (p. 326).

Floor

The floor of the anterior triangle is composed of the pretracheal fascia and posterolaterally, the carotid sheath. The thyroid gland (Fig. 7.13) is enclosed by the pretracheal fascia, while the larynx and trachea lie deep to it. Laterally, the carotid arteries, internal jugular vein and vagus (X) nerve all lie within the carotid sheath.

Contents

The contents of the anterior triangle (Fig. 7.11) comprise infrahyoid or strap muscles (sternohyoid, sternothyroid, thyrohyoid and omohyoid) and their immediate nerve supply. The most superficial muscle, sternohyoid, is attached inferiorly to the deep surface of the manubrium and superiorly to the lower border of the body of the hyoid bone. Deep to sternohyoid are both sternothyroid and thyrohyoid. Sternothyroid extends from the manubrium to the oblique line on the lamina of the thyroid cartilage. In the same plane, thyrohyoid runs from the thyroid cartilage to the inferior edge of the body of the hyoid bone. Omohyoid consists of two bellies linked by an intermediate tendon. The inferior belly is attached to the suprascapular ligament and the adjacent part of the scapula. It crosses the posterior triangle and ends deep to sternocleidomastoid in the intermediate tendon, which is anchored to the clavicle by a loop of investing fascia. The superior belly continues upwards to its attachment on the lower border of the hyoid bone lateral to the other muscles.

All four muscles are supplied segmentally by branches from the first three cervical spinal nerves. Thyrohyoid is supplied by fibres from C1 that have travelled with the hypoglossal (XII) nerve; the remaining muscles are supplied via the ansa cervicalis. The infrahyoid muscles depress the hyoid bone and the larynx.



Fig. 7.10 Boundaries and roofs of both anterior triangles of the neck. The midline is the division between the two triangles.


S
R
L
I
Omohyoid and sternohyoid (cut)
Thyrohyoid
Sternothyroid
Hyoid bone
Superior belly of omohyoid
Inferior belly of omohyoid
Sternohyoid

Fig. 7.11 Contents of the anterior triangle. The right omohyoid and sternohyoid muscles have been removed to show the deeper thyrohyoid and sternothyroid muscles.

Ansa cervicalis

Under cover of sternocleidomastoid two nerves, the roots of the ansa, unite to form a loop, the ansa cervicalis (Fig. 7.12), which provides the motor supply to the strap muscles. The superior root (descending limb) from the hypoglossal nerve consists solely of C1 fibres and descends to join the inferior root, C2 and C3 fibres from the cervical plexus, to form the ansa.

Thyroid gland

The thyroid gland (Fig. 7.13) is a vascular endocrine gland enclosed by the pretracheal fascia and closely applied to the anterior and lateral surfaces of the trachea. The fascia links the gland to the larynx, so that during swallowing both structures are elevated simultaneously. The two lateral lobes of the gland are joined across the midline by a narrow isthmus at the level of the third tracheal ring. A single pyramidal lobe is often present and projects upwards from the isthmus. Each lateral lobe is pear-shaped with its superior extremity reaching the oblique line on the thyroid cartilage, while its lower pole lies at the level of the fifth tracheal ring.

Lying anterior to the isthmus of the gland are the sternothyroid muscles and the anterior jugular veins. The lateral lobes are covered anterolaterally by the other infrahyoid muscles and the anterior borders of the sternocleidomastoid muscles. Posterolaterally lie the carotid sheaths, while posteromedially are the trachea, larynx and oesophagus. In the interval between the oesophagus and trachea the recurrent laryngeal nerves course upwards towards the larynx where they are vulnerable during thyroid or parathyroid surgery. A superior and an inferior parathyroid gland are embedded in the posterior surface of each lateral lobe.

The thyroid gland is a highly vascular organ and is supplied on each side by superior and inferior thyroid arteries. The superior thyroid artery, from the external carotid artery, descends to the upper pole of the gland. The inferior thyroid artery, from the thyrocervical trunk of the subclavian artery, ascends to enter the posterolateral aspect of the gland from behind the carotid sheath. A venous plexus on the surface of the gland drains via superior and middle thyroid veins into the internal jugular veins and via inferior thyroid veins to the left brachiocephalic vein. Lymph drains from the gland into the jugular chain of nodes.


Thyrohyoid
Superior belly of omohyoid (cut)
Sternothyroid
Sternohyoid
S
A
P
I
Superior root from hypoglossal nerve
Internal jugular vein
Inferior root of ansa cervicalis
Inferior belly of omohyoid (cut)
Thoracic duct

Fig. 7.12 Ansa cervicalis, lying on the internal jugular vein, and its branches to the strap muscles.


S
R
L
I
Pyramidal lobe
Cricothyroid
Middle thyroid vein
Inferior thyroid veins
Superior thyroid artery
Superior thyroid vein
Internal jugular vein
Left lateral lobe of thyroid gland
Isthmus
Common carotid artery

Fig. 7.13 Thyroid gland and its immediate blood supply, revealed by removal of the pretracheal fascia.





Fig. 7.14 Root of the neck after removal of the clavicles, pretracheal fascia, thyroid gland, carotid sheaths and left internal jugular vein.

Root of neck

The root of the neck is the region immediately above the superior thoracic aperture (p. 322). In the midline are the trachea and oesophagus, descending into the superior mediastinum (Fig. 7.14) between the apices of the lungs, which are each covered with pleura and a suprapleural membrane (Fig. 7.15). The other major structures in the root of the neck are vessels and nerves, which will be described in relation to scalenus anterior and its attachment to the scalene tubercle of the first rib (p. 28).

Veins

Each subclavian vein (Fig. 7.14) begins at the outer border of the first rib as the continuation of the axillary vein (p. 80). The vessel passes over the rib in front of the attachment of scalenus anterior and receives the external jugular vein from above. The subclavian and internal jugular veins unite at the medial border of scalenus anterior to form the brachiocephalic vein, which enters the thorax anteriorly alongside the trachea. On each side of the neck a major lymphatic trunk terminates by drainage into the angle where the subclavian and internal jugular veins unite. On the left, this lymphatic vessel is the thoracic duct, which arches laterally over the apex of the lung from its position alongside the oesophagus. The duct passes between the carotid sheath and the vertebral vessels, crossing in front of the phrenic nerve and the subclavian artery. The thoracic duct is the ultimate drainage channel for lymph from the lower limbs, pelvis, abdomen, left upper limb and the left side of the thorax, head and neck. On the right side of the neck, the smaller right lymphatic trunk terminates similarly, draining lymph only from the right upper limb and the right side of the thorax, head and neck. Cannulating the thoracic duct allows collection of lymphocytes for immunological investigation and treatment.

Arteries

The left common carotid and left subclavian arteries emerge from the thorax on the left of the trachea and oesophagus (Fig. 7.14). On the right, the brachiocephalic trunk divides at the level of the superior thoracic aperture to form the right common carotid and right subclavian arteries (Fig. 7.14). Each common carotid artery ascends into the neck within its sheath and gives no branches before its termination. Each subclavian artery passes laterally over the upper surface of the first rib posterior to scalenus anterior and continues into the axilla as the axillary artery (p. 79).

Three branches of the subclavian artery, internal thoracic, thyrocervical and vertebral arteries (Figs 7.14 & 7.15), arise medial to scalenus anterior. The internal thoracic artery (p. 34) descends into the thorax to supply the anterior thoracic and abdominal walls. The thyrocervical trunk is short and divides into three branches, the inferior thyroid (p. 329), suprascapular and transverse cervical arteries. The latter two vessels cross the posterior triangle of the neck. The suprascapular artery supplies the scapula and related structures and the transverse cervical artery supplies superficial structures in the posterior part of the neck. The vertebral artery (Fig. 7.15) inclines upwards and backwards medial to scalenus anterior and crosses in front of the transverse process of the seventh cervical vertebra, before continuing superiorly



through the foramina transversaria of the upper six cervical vertebrae, to enter the skull through the foramen magnum (p. 376).

The costocervical trunk (Fig. 7.15) arises from the subclavian artery behind scalenus anterior and arches backwards over the suprapleural membrane as far as the neck of the first rib, where it divides to form the superior intercostal artery supplying the upper two intercostal spaces (p. 35) and the deep cervical artery, which supplies the muscles of the back of the neck.

Nerves

The vagus (X) and phrenic nerves, both sympathetic chains and parts of both brachial plexuses all traverse the root of the neck. Each vagus nerve (Fig. 7.14) descends within the carotid sheath and enters the superior mediastinum between the main arterial and venous structures medial to the phrenic nerve. On the right side of the neck, the recurrent laryngeal nerve arises from the vagus, hooking under the subclavian artery to ascend in the groove formed by the lateral surfaces of the trachea and oesophagus. On the left, the recurrent laryngeal nerve follows a similar course but arises from the vagus in the thorax (p. 62).

The phrenic nerve (Fig. 7.15), formed from the anterior rami of the third, fourth and fifth cervical spinal nerves, passes inferiorly on the anterior surface of scalenus anterior beneath the prevertebral fascia. It leaves the medial side of the muscle near its lower end and enters the thorax between the main arterial and venous structures lateral to the vagus nerve.

The sympathetic trunks (Fig. 7.15), covered by the prevertebral fascia, lie alongside the bodies of the cervical vertebrae. In the neck each trunk bears only three sympathetic ganglia, the superior, middle and inferior. The lowest ganglion fuses frequently with the first thoracic ganglion to form the stellate (cervicothoracic) ganglion. The trunk continues into the thorax in front of the neck of the first rib. The middle and inferior cervical sympathetic ganglia are often linked by a nerve, the ansa subclavia, which curves around the subclavian artery.



Fig. 7.15 Deeper structures of the root of neck, revealed by removal of most of the left vagus and phrenic nerves, the left scalenus anterior, both common carotid arteries and the large veins.

The brachial plexus (Fig. 7.14) originates from the anterior rami of the lowest four cervical and first thoracic spinal nerves which, partly covered by scalenus anterior, constitute the roots of the plexus. They combine to form the trunks of the plexus, which emerge from behind the lateral border of the muscle. The plexus continues into the upper limb enclosed with the axillary artery in a prolongation of the prevertebral fascia called the axillary sheath. (A detailed account of the brachial plexus is given on p. 180.)

Scalene muscles

Scalenus anterior (Fig. 7.15) is attached superiorly to the transverse processes of the third, fourth, fifth and sixth cervical vertebrae. Inferiorly, it attaches to the scalene tubercle on the first rib (p. 28). Behind it lie scalenus medius (Fig. 7.15) and scalenus posterior, which arise from the transverse processes of the lower six cervical vertebrae and attach inferiorly to the upper surfaces of the first and second ribs, respectively. These muscles are supplied segmentally by cervical spinal nerves. They elevate the first and second ribs and laterally flex the neck.

Contents of the Carotid Sheath

The carotid sheaths form part of the fascial layers of the neck (pp 324, 325) and extend from the base of the skull into the superior mediastinum. Each sheath contains the common, the internal and part of the external carotid arteries, the internal jugular vein and parts of the glossopharyngeal (IX), vagus (X) and accessory (XI) nerves.

Carotid arteries

The common carotid artery arises on the left from the aortic arch and on the right from the brachiocephalic artery, then ascends within its sheath into the neck. At the upper border of the thyroid cartilage it divides into internal and external carotid arteries (Fig. 7.17). At its origin the internal carotid artery is dilated to form the carotid sinus. The vessel ascends within the carotid sheath without branching and, in company with its sympathetic nerve plexus, enters the carotid canal. In the cranial cavity the internal carotid artery terminates as the anterior and middle cerebral arteries (p. 377), having given rise to the ophthalmic artery, which supplies the contents of the orbit.

The external carotid artery leaves the carotid sheath, inclines superolaterally and enters the deepest part of the parotid gland, where it divides into terminal branches at the level of the neck of the mandible. Separating the external and internal carotid arteries are the styloid process, stylopharyngeus, the glossopharyngeal (IX) nerve and the pharyngeal branch of the vagus (X) nerve.

The external carotid artery usually has eight branches (Fig. 7.17), supplying much of the extracranial portion of the head and upper part of the neck. The ascending pharyngeal artery arises on the medial aspect of the external carotid artery and ascends on the lateral surface of the pharynx. The next branch, the superior thyroid artery, inclines downwards and forwards from the anterior surface of the external carotid to supply the thyroid gland and the larynx. The lingual artery passes forwards from the anterior surface of the external carotid artery into the base of the tongue (p. 351). The facial artery, another anterior branch, supplies the tonsil and descends under the body of the mandible, grooving the


Parotid gland (cut)
Posterior belly of digastric
Submandibular nodes
Anterior belly of digastric
Submandibular gland
S
A
P
I
Mastoid node
Sternocleido-mastoid
Jugulodigastric node
Deep cervical nodes
Internal jugular vein
Omohyoid
Supraclavicular nodes

Fig. 7.16 Internal jugular vein and some cervical lymph nodes, revealed after removal of sternocleidomastoid and part of the parotid gland.

submandibular gland and emerging from beneath the mandible at the anterior border of masseter to supply the face (Fig. 7.35).

Arising from the posterior surface of the external carotid artery, the occipital artery passes upwards and backwards deep to sternocleidomastoid (Figs 7.17 & 7.24). The vessel crosses the apex of the posterior triangle of the neck to supply the posterior part of the scalp. The posterior auricular artery arises below the pinna and passes upwards and backwards to supply the pinna and the scalp.

The terminal branches of the external carotid artery, the superficial temporal and maxillary arteries, arise within the parotid gland. The former supplies the lateral part of the scalp, while the maxillary artery supplies the infratemporal fossa, pterygopalatine fossa and lateral wall of the nose. Postganglionic sympathetic nerve fibres accompany the external carotid artery and its branches.

Internal jugular vein

The internal jugular vein (Figs 7.16 & 7.17) is formed below the jugular foramen after the union of the sigmoid and inferior petrosal dural venous sinuses. The vein descends through the neck within the carotid sheath and receives the facial, lingual, pharyngeal, and superior and middle thyroid veins. The internal jugular vein also communicates with the external jugular system via the anterior branch of the retromandibular vein. It terminates by uniting with the subclavian vein to form the brachiocephalic vein.

Nerves

Within the carotid sheath lie the glossopharyngeal (IX), vagus (X) and accessory (XI) nerves, which leave the skull via the jugular foramen. The glossopharyngeal nerve passes inferiorly, leaves the sheath and winds around the posterolateral surface of stylopharyngeus to enter the posterior third of the tongue. The nerve supplies stylopharyngeus and gives a sensory branch, which innervates the carotid sinus (p. 352).

The vagus (X) nerve (Fig. 7.17) bears two sensory ganglia, one in the jugular foramen and one below the base of the skull, between which the nerve receives the


Transverse facial artery
Maxillary artery
External carotid artery
Stylohyoid
Facial artery
Lingual artery
External carotid artery
Superior thyroid artery
S
A
P
I
Superficial temporal artery
Internal jugular vein (cut)
Sternocleido-mastoid (cut)
Posterior auricular artery (cut)
Accessory nerve
Occipital artery
Hypoglossal nerve
Carotid sinus and internal carotid artery
Vagus nerve

Fig. 7.17 Branches of the external carotid artery and the vagus, accessory and hypoglossal nerves, after removal of part of the internal jugular vein, carotid sheath and posterior belly of digastric.

cranial part of the accessory nerve. The vagus nerve descends in the posterior part of the carotid sheath between the carotid artery and internal jugular vein and gives rise to pharyngeal, superior laryngeal and cardiac branches before traversing the superior thoracic aperture. The pharyngeal branch passes forwards between the internal and external carotid arteries to the outer surface of the pharynx, contributing to the pharyngeal plexus. The superior laryngeal nerve accompanies the superior thyroid artery and vein supplying the larynx. The cardiac branches of the vagus join those from the sympathetic trunk and descend into the thorax. The right vagus gives a recurrent laryngeal branch in the neck which curves around the right subclavian artery and passes superiorly to reach the larynx (p. 331). The left recurrent laryngeal nerve arises from the left vagus nerve in the thorax and passes around the aortic arch before ascending into the neck.

The accessory (XI) nerve (Fig. 7.17) is formed by the fusion of cranial and spinal roots in the posterior cranial fossa. In the jugular foramen the nerve divides into a cranial part joining the vagus nerve and a spinal part which supplies sternocleidomastoid and trapezius.

Lymphatics

Lymphatic vessels from structures in the head and neck accompany the vascular supply and drain into superficial or deep groups of lymph nodes.

Superficial lymph nodes

Several groups of superficial nodes form an incomplete ring around the lower part of the head. The submental nodes lie between the anterior bellies of the two digastric muscles, draining lymph from the tip of the tongue and the mental region. The submandibular group (Fig. 7.16) lies on the superficial surface of the submandibular gland and receives lymph from the submental nodes, from the remainder of the anterior two-thirds of the tongue, from the floor of the mouth (including the gums and teeth), and from the nose, face and anterior part of the scalp. The parotid nodes lie on or within the parotid gland, the mastoid group (Fig. 7.16) on the lateral surface of the mastoid process, and the occipital lymph nodes at the apex of the posterior triangle of the neck. These three groups drain the remainder of the face and scalp, including the external ear. Lymph from all the superficial nodes drains into the deep cervical nodes.

Deep cervical lymph nodes

The deep cervical or jugular lymph nodes (Fig. 7.16) form a chain in and around the carotid sheath. Two of the deep cervical nodes are of particular clinical significance. The jugulodigastric node receives lymph mainly from the tongue and tonsil and the jugulo-omohyoid node drains the tongue. From the deep cervical nodes lymph drains inferiorly, via the jugular lymphatic trunk, usually into the thoracic duct on the left and into the right lymphatic duct on the right. Removal of these nodes by careful surgical dissection can successfully treat locally metastatic cancer.

Superficial Structures of the Face and Scalp

The subcutaneous tissue of the face and scalp is highly vascular and is traversed by several nerves. Most of the nerves are sensory to skin and include branches of the trigeminal (V) and upper cervical spinal nerves. In addition, there are branches that are motor from the facial (VII) nerve to a group of muscles in the subcutaneous tissues of the face, scalp and front of the neck, known as the muscles of facial expression.


Frontalis
Orbital and palpebral parts of orbicularis oculi
Levator labii superioris alaeque nasi
Levator anguli oris
Orbicularis oris
Depressor labii inferioris
Mentalis
Epicranial aponeurosis
Transverse part of nasalis
Levator labii superioris
Zygomaticus major and minor
Buccinator
Risorius
Depressor anguli oris
S
A
P
I

Fig. 7.18 Muscles of facial expression. The skin and subcutaneous fat have been removed.

Muscles of facial expression

In general, these muscles are arranged as sphincters or dilators around the orifices of the face (Fig. 7.18). Most are anchored to bone at one end and attached to skin at the other.

Palpebral fissure

The sphincter of the palpebral fissure (the gap between the eyelids) is orbicularis oculi, which is divided into inner palpebral and outer orbital parts. The palpebral part lies within the eyelids and is attached to the medial and lateral palpebral ligaments. The orbital portion is attached only to the medial palpebral ligament, and its fibres lie around the orbital margin. Both parts close the palpebral fissure, the palpebral part gently and the orbital part forcefully as when ‘screwing up the eyes’. The palpebral part also helps sweep tears medially across the cornea from lacrimal gland to lacrimal canaliculi. The dilator components are provided by levator palpebrae superioris within the orbit (p. 380), and by occipitofrontalis in the scalp. The latter muscle has two bellies, occipital and frontal, linked by an extensive intermediate tendon, the epicranial aponeurosis, which forms a mobile layer over the vault of the skull. From its posterior extremity the occipital belly (occipitalis) descends to its attachment on the highest nuchal line of the occipital bone (Fig. 7.19); from its anterior end the frontal belly (frontalis) descends in the forehead and its fibres interdigitate with those of orbicularis oculi and attach to skin near the


Epicranial apo-neurosis
Occipitalis
Sternocleido-mastoid
Highest nuchal line
Trapezius
S
A
P
I

Fig. 7.19 Posterior view to show occipitalis and part of the epicranial aponeurosis.

eyebrow. Occipitalis fixes the epicranial aponeurosis allowing frontalis to raise the eyebrows.

Nostril

Around each nostril is nasalis with two feeble parts, alar and transverse, which dilate and compress the nostrils, respectively.

Mouth

Orbicularis oris, the sphincter of the mouth, is embedded in the lips and attaches near the midline to the mandible and maxilla. In addition, there are dilators around the mouth whose fibres continue into orbicularis oris. The most medial dilator of the upper lip is levator labii superioris alaeque nasi. This muscle attaches near the medial margin of the orbit and runs to the alar cartilage of the nose and to the upper lip. Levator labii superioris is attached to bone beneath the orbital margin, whereas levator anguli oris lies slightly deeper and its fibres incline towards the angle of the mouth. Two of the dilator muscles take attachment from the zygoma: zygomaticus major and minor. Attached to the mandible are three muscles, called, from lateral to medial, depressor anguli oris, depressor labii inferioris and mentalis.


Zygomatic arch
Parotid duct (cut)
Buccinator
Facial artery
S
A
P
I
Tendon of temporalis
Lateral pterygoid
Medial pterygoid
Angle of mandible

Fig. 7.20 Buccinator seen after removal of some superficial facial muscles, the parotid gland and most of its duct, and masseter.

The buccinator muscle (Figs 7.18 & 7.20) lies deep to the other dilator muscles in the wall of the cheek. Anteriorly, it blends with the deep surface of orbicularis oris. Posteriorly, it gains attachment to the outer surface of the mandible from the level of the first to the third molar teeth. Passing behind the third molar tooth, buccinator is attached to the pterygomandibular raphe and the pterygoid hamulus. The muscle attachment continues forwards along the outer surface of the maxilla as far as the first upper molar tooth. Buccinator controls the size of the vestibule of the mouth (that part of the buccal cavity lying between the cheek and the teeth).

The platysma (Fig. 7.21), the most extensive muscle of facial expression, descends in the subcutaneous tissue of the neck from the inferior border of the mandible and fades out on the anterior surface of the thorax. A few fibres may run horizontally from the angle of the mouth as risorius. Platysma is most easily seen in action during respiratory distress when the skin of the neck is pulled taut.

Ear

In the human, the auricular muscles are almost vestigial.

Facial nerve

All the muscles of facial expression derive their motor nerve supply from the facial (VII) nerve. Occipitalis and some of the


Risorius
Depressor anguli oris
Cervical branches of facial nerve
Parotid gland
Masseter
Sternocleidomastoid
External jugular vein
Platysma
S
A
P
I

Fig. 7.21 Platysma, the largest muscle of facial expression, and its nerve supply.

auricular muscles are innervated by the posterior auricular branch of the nerve (p. 340); the remaining muscles are supplied by the five sets of branches (Fig. 7.22) that emerge from the anterior border of the parotid gland (p. 339). The temporal branch of the facial nerve ascends to supply the remaining auricular muscles and frontalis. The zygomatic branch is directed towards the eye and supplies muscles above and below the palpebral fissure. The third branch, the buccal, runs horizontally forwards to innervate buccinator and the muscles of the upper lip. The mandibular branch supplies the muscles of the lower lip, dipping below the mandible in its course. The cervical branch descends to supply platysma.

Blood supply of face

Most of the superficial structures of the face obtain their blood supply from the facial artery (Fig. 7.22), a branch of the external carotid artery. The facial artery enters the face by hooking under the inferior border of the mandible, where it is easily palpated. The vessel then pursues a tortuous course across the face towards the inner angle of the orbit. The area of the face in front of the ear is supplied by the transverse facial artery, an anterior branch of the superficial temporal artery. Emerging from the orbit to supply the forehead are the supraorbital and supratrochlear branches of the ophthalmic artery.

Blood from the face drains into the facial vein (Fig. 7.22), which accompanies the facial artery. The vein also receives the supratrochlear and supraorbital veins and thus communicates with ophthalmic veins in the orbit. Blood from the lateral part of the face drains into the superficial temporal vein.

Sensory supply

The sensory nerve supply of the face is conveyed in branches of the three divisions of the trigeminal (V) nerve (Fig. 7.23).

Scalp

The scalp (Fig. 7.24) extends from the superior nuchal line posteriorly to the superior orbital margin anteriorly, and to the external


S
A
P
I
Supra-trochlear branches of V_1
Infra-orbital branches of V_2
Buccal branch of facial nerve
Facial artery and veins
Supra-orbital branches of V_1
Superficial temporal artery
Temporal branches of facial nerve
Zygomatic branches of facial nerve
Parotid gland
Cervical branches of facial nerve
Mandibular branches of facial nerve
External jugular vein

Fig. 7.22 Neurovascular structures of the face. In this specimen the facial vein is duplicated, a common variation.


V_1 ophthalmic
V_2 maxillary
V_3 mandibular
Divisions
Cervical nerves
S
A
P
I

Fig. 7.23 Dermatomes of the face. Areas of the face are supplied with sensory fibres from the different divisions of the trigeminal nerve.




Epicranial aponeurosis
Supra-trochlear artery and nerves
Supra-orbital artery
Superficial temporal artery
Superficial temporal vein
S
A
P
I
Skin
Supra-orbital nerves
Lesser occipital nerve
Greater occipital nerve
Occipital artery

Fig. 7.24 Vessels and nerves of the scalp lying on the epicranial aponeurosis.

acoustic meatus and zygomatic arch laterally. It comprises two functional layers applied to the outer surface of the vault of the skull. Close to the bones lies the pericranium, which forms the periosteum of the skull. This is loosely attached over each constituent bone but is firmly bound to the sutures so that subperiosteal bleeding is limited to the area of the bones involved. Superficial to the pericranium, but separated from it by a layer of loose connective tissue, lie the epicranial aponeurosis (intermediate tendon of occipitofrontalis) and the skin of the scalp, firmly bound to each other so that they move as one over the underlying pericranium and skull.

The arteries and nerves that supply the scalp enter at its circumference and because they accompany each other, they will be described together, starting anteriorly. Near the midline are the supratrochlear and supraorbital nerves, arteries and veins. The nerves are derived from the ophthalmic division of the trigeminal (V) nerve. The vessels communicate with their ophthalmic counterparts within the orbit.

Lateral to the orbit the zygomaticotemporal nerve from the maxillary division of the trigeminal nerve, accompanied by its vessels, ascends a short distance into the scalp. Just in front of the ear, the auriculotemporal nerve from the mandibular division of the fifth cranial nerve passes into the scalp. The superficial temporal artery and vein follow a similar course.

The area of the scalp behind the ear is supplied by the lesser occipital nerve (C2 anterior ramus) accompanied by the posterior auricular artery and vein. Posteriorly near the midline the scalp receives the greater occipital nerve (C2 posterior ramus) and the occipital artery and vein.

In addition, venous blood may drain via the diploic veins of the skull into the intracranial venous sinuses. Scalp wounds bleed profusely, making suturing difficult. To diminish bleeding, circumferential pressure may be temporarily applied with an elastic bandage.

Parotid Gland

The parotid is the largest of the salivary glands and is pyramidal in shape (Fig. 7.25). Its base faces laterally between the anterior border of sternocleidomastoid and the ramus of the mandible, while its apex lies deeply against the styloid process. The gland extends upwards between the external acoustic meatus and the temporomandibular joint, movements of which may be painful when the parotid is inflamed.

The parotid gland is deeply indented in front by the mandible, masseter and medial pterygoid. Deep to the gland are the infratemporal fossa and the styloid apparatus, the latter separating it from the carotid sheath and the pharyngeal wall.

The investing fascia of the neck splits into two layers to enclose the gland (p. 324). The superficial layer attaches above to the zygomatic arch, while anteriorly it merges with the tissues of the cheek. The deep layer is attached to the tympanic part of the temporal bone and is thickened between the styloid process and the angle of the mandible to form the stylomandibular ligament. Swelling in the parotid is particularly painful because of the toughness of the surrounding fascia and its position between the mandible in front and the temporal bone behind.

The parotid duct (Fig. 7.26) passes forwards across the surface of masseter, turns medially and pierces buccinator to open obliquely into the vestibule of the mouth opposite the upper


A
L
R
P
Medial pterygoid
Wall of pharynx
Ramus of mandible
Masseter
Stylo-pharyngeus
Stylohyoid
Stylo-glossus
Retro-mandibular vein
Internal and external carotid arteries
Parotid gland
Occipital artery
Mastoid process
Internal jugular vein
Sternocleido-mastoid
Digastric

Fig. 7.25 Transverse section of the head through the parotid glands. Superior aspect. (Compare Fig. 7.93.)


S
A
P
I
Accessory parotid gland
Zygomatic branches of facial nerve
Temporal branch of facial nerve
Superficial temporal artery
Parotid duct
Parotid gland
Buccal branch of facial nerve
Pinna
Masseter
Mandibular branch of facial nerve
Facial artery
Facial veins
Sternocleido-mastoid
Cervical branches of facial nerve
External jugular vein

Fig. 7.26 Parotid gland and branches of the facial nerve, exposed by the removal of the superficial layer of parotid fascia.

second molar tooth. This oblique passage through the mucosa compresses the duct when intraoral pressure is raised. When masseter contracts, the duct may be palpated over the anterior edge of the muscle. An accessory part of the gland may lie alongside the duct.

Structures traversing parotid gland

Of these, the most superficial are branches of the facial (VII) nerve that run forwards to the face and pass superficial to the retromandibular vein and its tributaries. The deepest is the termination of the external carotid artery.

Facial (VII) nerve

The facial nerve emerges from the skull through the stylomastoid foramen and turns forwards to enter the posterior surface of the parotid gland. Before penetrating the gland, it gives two branches. The posterior auricular branch passes behind the external acoustic meatus to supply occipitalis and the auricular muscles. The other supplies the posterior belly of digastric and stylohyoid. Within the gland, the facial nerve forms a plexus from which five groups of branches (Fig. 7.26) emerge at the periphery of the gland to supply the muscles of facial expression (p. 335). This plexus divides the gland into superficial and deep parts. Tumours confined to one of these parts only can be removed without damage to the facial nerve.

Retromandibular vein

Within the parotid gland, the superficial temporal and maxillary veins unite to form the retromandibular vein (Fig. 7.27). Inferiorly, this short vein terminates as anterior and posterior divisions, which escape from the gland. The anterior division joins the facial vein, which drains into the internal jugular vein. The posterior division unites with the posterior auricular vein to form the external jugular vein (p. 326).

Termination of external carotid artery

Entering the parotid from below, the external carotid artery ascends through the gland and at the level of the neck of the mandible divides into the maxillary and superficial temporal arteries (Fig. 7.28). The former runs anterosuperiorly to leave the


S
A
P
I
Superficial temporal vein
Maxillary vein
Retro-mandibular vein
Masseter
Facial vein
External jugular vein
External acoustic meatus
Deep part of parotid gland
Posterior auricular vein
Posterior and anterior divisions of retromandibular vein
Sternocleido-mastoid

Fig. 7.27 Retromandibular vein and its communications, seen after removal of the superficial portion of the parotid gland.


Transverse facial artery
Ramus of mandible
External carotid artery
Masseter
Facial artery
S
A
P
I
Superficial temporal artery
Maxillary artery
Facial nerve
Posterior belly of digastric
Accessory nerve
Internal jugular vein

Fig. 7.28 External carotid artery and its terminal branches, revealed by complete excision of the parotid gland.

gland and enter the infratemporal fossa. The superficial temporal artery continues upwards between the external acoustic meatus and the temporomandibular joint to supply the temple. Its pulsation can be felt just above the joint.

Several lymph nodes lie just under the fascia covering the parotid gland or within the gland itself.

Neurovascular supply

The gland receives its vascular supply from the vessels traversing it. Parasympathetic secretomotor fibres follow a tortuous route to the gland. The preganglionic fibres arise from the inferior salivatory nucleus in the brainstem and pass in the tympanic branch of the glossopharyngeal (IX) nerve to the tympanic plexus in the middle ear, leaving the skull in the lesser petrosal nerve to synapse in the otic ganglion (p. 345). Postganglionic parasympathetic fibres travel to the gland in the auriculotemporal branch of the mandibular (V_3) division. By contrast, postganglionic sympathetic nerves are conveyed in the plexus accompanying the external carotid artery.

Masseter, Temporalis and Infratemporal Fossa

Masseter

Masseter (Fig. 7.29) attaches along the length of the zygomatic arch and its fibres slope downwards and backwards to the lateral surface of the ramus of the mandible adjacent to the angle (Fig. 7.31). This muscle is a powerful elevator of the mandible and is easily palpated when the teeth are clenched. It is supplied by the masseteric branch of the mandibular (V_3) division of the trigeminal nerve.

Temporalis

Temporalis (Fig. 7.30) is a large fan-shaped muscle occupying the temporal fossa and taking attachment from the area of bone bounded by the inferior temporal line. The more superficial fibres arise from the temporal fascia that covers the muscle and is attached to the superior temporal line. All the fibres descend deep to the zygomatic arch to attach to the coronoid process and anteromedial aspect of the ramus of the mandible (Fig. 7.31). Temporalis elevates the mandible, as in closing the mouth, and its posterior fibres retract the mandible. The deep temporal branches of the mandibular (V_3) division of the trigeminal nerve supply the muscle from its deep surface.



Fig. 7.29 Masseter, showing its attachment to the zygomatic arch and the angle of the mandible, after removal of the parotid gland.

Infratemporal fossa

This fossa lies deep to the ramus of the mandible and is limited on its medial aspect by the lateral wall of the pharynx and the medial pterygoid plate of the sphenoid bone. The fossa is bounded by the posterior surface of the maxilla in front and by the styloid process and its attached muscles behind. The roof is provided by the temporal and sphenoid bones in the base of the skull while inferiorly the fossa is continuous with the neck.

Within the fossa are the two pterygoid muscles, the mandibular (V_3) division of the trigeminal nerve and its branches, and the maxillary vessels and their branches. Adjacent to the fossa is the temporomandibular joint.

Pterygoid muscles

Each of the lateral and medial pterygoid muscles (Figs 7.32–7.34) has two attachments to the skull. The upper head of the lateral pterygoid attaches to the inferior surface of the greater wing of the sphenoid. The lower head attaches to the lateral surface of the lateral pterygoid plate. Both heads converge on the neck of the mandible and the capsule of the temporomandibular joint. The lateral pterygoid pulls forward both the neck of the mandible and the articular disc, thus depressing the mandible and opening the mouth.

The lower head of the lateral pterygoid is clasped by the two heads of the medial pterygoid. The deep head of the latter is larger and attaches to the medial surface of the lateral pterygoid plate. The superficial head is attached to the tuberosity of the maxilla. The fibres of both heads incline obliquely downwards, backwards and laterally to attach to the medial surface of the angle of the mandible. The muscle is a powerful elevator of the mandible.


S
A
P
I
Temporalis
Zygomatic arch (cut)
Capsule of temporo-mandibular joint
Coronoid process
Ramus of mandible
Angle of mandible
External acoustic meatus

Fig. 7.30 Temporalis, seen after removal of masseter, part of the zygomatic arch and the temporal fascia.


Groove for nerve to mylohyoid
Coronoid process
Neck
S
A
P
I
Head
Mandibular canal
Mylohyoid line
Mental foramen
Lingula

Fig. 7.31 Mandible. The right wisdom tooth is partially erupted.


Deep temporal nerves
Upper head of lateral pterygoid
Masseteric nerve
Lower head of lateral pterygoid
Articular surfaces
Intra-articular disc
Head of mandible
S
A
P
I

Fig. 7.32 Temporomandibular joint opened by excision of the lateral part of its capsule.


Deep temporal nerves
Lateral pterygoid
Buccal nerve
Inferior alveolar nerve
Lingual nerve
Nerve to mylohyoid
Inferior alveolar artery
Upper and lower joint cavities
Head of mandible
Superficial temporal artery (cut)
Maxillary artery
External carotid artery
S
A
P
I

Fig. 7.33 Contents of the infratemporal fossa seen after excision of part of the mandible. In this specimen, the maxillary artery passes deep to lateral pterygoid.

Temporomandibular joint

The temporomandibular joint (Fig. 7.32) is a synovial joint. The head of the mandible articulates with the articular fossa and eminence of the temporal bone. Fibrocartilage covers the articular surfaces and also forms an articular disc, which divides the joint into two separate cavities. Within these cavities, the non-cartilaginous surfaces are lined with synovial membrane.

The fibrous capsule surrounding the joint is attached to the margin of the articular cartilage and to the neck of the mandible. Anteriorly, it receives the attachment of the lateral pterygoid while its deep surface is firmly adherent to the periphery of the articular disc.

Laterally, the capsule (Fig. 7.30) is thickened to form the lateral ligament, which inclines posteroinferiorly from the root of the zygomatic arch to the neck of the mandible. Two accessory ligaments lie medial to the joint, although not in contact with the capsule. The sphenomandibular ligament extends from the spine of the sphenoid to the lingula adjacent to the mandibular foramen. The stylomandibular ligament, a thickening of the parotid fascia, passes from the styloid process to the angle of the mandible.

The joint receives its nerve supply from the auriculotemporal and masseteric branches of the mandibular (V_3) division of the trigeminal nerve.

Movements at the joint include elevation, depression, protraction and retraction of the mandible. The head of the mandible does not merely rotate in the articular fossa but also moves forwards onto the articular eminence of the temporal bone, taking the articular disc with it. The alternate protraction and retraction of right and left sides produces the grinding movements used in chewing. The muscles responsible for these movements are known collectively as the muscles of mastication. The mouth is closed by contraction of masseter, temporalis and medial pterygoid. The lateral pterygoid protracts the mandible and, assisted by digastric and mylohyoid (p. 348), also opens the mouth. Retraction is produced by the posterior fibres of temporalis. When the mandible is fully depressed, the joint is relatively unstable and dislocation



Fig. 7.34 Branches of the mandibular division of the trigeminal nerve and the maxillary artery, revealed by removal of the mandibular head and lateral pterygoid.

may occur, the head of the mandible moving in front of the articular eminence and resulting in an inability to close the mouth.

Mandibular (V_3) division of trigeminal nerve

The mandibular division of the trigeminal nerve (Figs 7.33 & 7.34) contains sensory and motor fibres and enters the infratemporal fossa through the foramen ovale in the sphenoid. Two small branches arise from the short main trunk of the nerve. The first branch ascends through the foramen spinosum to receive sensation from the meninges of the middle cranial fossa. The other branch is motor, supplying the medial pterygoid and giving a small branch that passes through the otic ganglion (lying just medial to the main trunk of the mandibular division) to supply tensor tympani and tensor veli palatini.

The main trunk descends between the lateral pterygoid and tensor veli palatini muscles, dividing into anterior and posterior divisions. The anterior division is mainly motor and gives masseteric, deep temporal, lateral pterygoid and buccal branches. The masseteric nerve (Fig. 7.32) curves laterally above the lateral pterygoid to enter the deep surface of masseter. Two or three deep temporal nerves (Fig. 7.33) ascend deep to temporalis, which they supply, and further branches enter the deep surface of the lateral pterygoid. The buccal nerve (Figs 7.33 & 7.34) is a sensory branch that passes forwards between the two heads of the lateral pterygoid to supply the skin over the cheek and the mucosa lining the cheek, which it reaches by piercing, but not supplying, buccinator.

The posterior division of the main trunk is mainly sensory and has three branches, the auriculotemporal, lingual and inferior alveolar nerves. The auriculotemporal nerve (Fig. 7.34) arises by two roots, which clasp the origin of the middle meningeal artery. The nerve passes backwards before turning superiorly behind the temporomandibular joint to ascend in company with the superficial temporal vessels. It gives secretomotor branches to the parotid gland (p. 339) and conveys sensation from the temporal region, the upper half of the pinna and most of the external acoustic meatus.

The lingual nerve (Figs 7.33 & 7.34) inclines downwards and forwards between the pterygoids, deviating medially to pass below the superior constrictor of the pharynx. In the floor of the mouth it runs forwards lateral to the hyoglossus muscle, at whose anterior border it again turns medially to pass inferior to the submandibular duct and enter the base of the tongue. It conveys general sensation from the anterior two-thirds of the tongue. Near the lower border of the lateral pterygoid the lingual nerve is joined by the chorda tympani (a branch of the facial nerve). Arising within the temporal bone, the chorda tympani emerges from the petrotympanic fissure. It carries taste fibres, which have travelled in the lingual nerve from the anterior two-thirds of the tongue and preganglionic parasympathetic fibres destined for the submandibular ganglion (p. 352).

The inferior alveolar nerve (Figs 7.33 & 7.34) descends medial to the lateral pterygoid and gives rise to a motor branch that curves downwards to supply mylohyoid and the anterior belly of digastric. The inferior alveolar nerve then enters the mandibular foramen in the ramus of the mandible and runs forwards in the mandibular canal, supplying the lower teeth and alveolar ridge. Its mental branch emerges from the mental foramen to supply skin overlying the chin. Local anaesthetic injected near the inferior alveolar nerve as it enters the mandibular foramen will block sensation from the lower teeth and gums on that side of the mouth. Often there is loss of sensation in the same side of the tongue because of the proximity of the lingual nerve.

Maxillary artery

This artery (Figs 7.33 & 7.34) arises in the parotid gland (p. 339) as a terminal branch of the external carotid artery, passes anterosuperiorly across the infratemporal fossa, usually lateral to the lateral pterygoid, and traverses the pterygomaxillary fissure to enter the pterygopalatine fossa where terminal branches arise. These correspond to branches of the maxillary nerve (p. 353).

In the infratemporal fossa, the maxillary artery gives branches to supply masseter, temporalis and the pterygoid muscles. In addition, the middle meningeal artery arises deep to the lateral pterygoid, embraced by the two roots of the auriculotemporal nerve. It traverses the foramen spinosum and within the cranium supplies the meninges of the middle cranial fossa and the cranial vault.

The maxillary artery also gives rise to the inferior alveolar artery, which accompanies the nerve into the mandibular canal. Further small branches supply the middle ear and the lining of the external acoustic meatus.

Pterygoid venous plexus

Veins within the pterygopalatine fossa form a plexus that extends through the pterygomaxillary fissure into the infratemporal fossa, where the plexus is related to the pterygoid muscles. This pterygoid plexus has important connections to the cavernous sinus in the skull and infraorbital and ophthalmic veins. The plexus drains by the maxillary vein into the retromandibular vein (p. 340).

Digastric and Styloid Muscles


S
A
P
I
Inferior alveolar nerve
Lingual nerve
Nerve to mylohyoid
Styloglossus
Stylohyoid
Anterior belly of digastric
Nerve to thyrohyoid
Maxillary artery (cut)
Styloid process
Posterior belly of digastric
External carotid artery (cut)
Sternocleido-mastoid
Facial artery
Hypoglossal nerve
Lingual artery

Fig. 7.35 Digastric and stylohyoid seen after removal of part of the mandible. The superficial part of the submandibular gland has also been excised.

Digastric

The digastric muscle (Fig. 7.35) consists of anterior and posterior bellies united by an intermediate tendon. The posterior belly attaches to the medial surface of the mastoid process and inclines forwards and downwards, becoming continuous with the intermediate tendon close to the hyoid bone. This tendon pierces stylohyoid and is anchored by a fascial sling to the hyoid bone. The anterior belly continues forwards from the intermediate tendon to attach to the inferior border of the mandible near the midline. Digastric elevates the hyoid bone during swallowing and assists mylohyoid and the lateral pterygoid in depressing the mandible when opening the mouth. The posterior belly is innervated by the facial (VII) nerve (p. 340). The anterior belly receives its motor supply from the mandibular (V_3) division of the trigeminal nerve via the mylohyoid branch of the inferior alveolar nerve (p. 345).

Muscles of styloid process

Three muscles, stylohyoid, stylopharyngeus and styloglossus, attach to the styloid process but diverge to reach the hyoid bone, the pharynx and the tongue, respectively.

Stylohyoid (Fig. 7.35) inclines downwards and forwards from the posterior surface of the styloid process to attach to the body of the hyoid bone alongside the lesser horn. The muscle or its tendon is pierced by the intermediate tendon of digastric near the hyoid bone. Stylohyoid elevates the hyoid and is innervated by the facial (VII) nerve.

Stylopharyngeus (Fig. 7.36) is attached to the medial side of the root of the styloid process and passes inferomedially on the lateral surface of the superior pharyngeal constrictor. It enters the wall of the pharynx between the superior and middle constrictors and blends with the other longitudinal muscles of the pharynx. The muscle elevates the pharynx and larynx during swallowing and is the only muscle innervated by the glossopharyngeal (IX) nerve.

Styloglossus (Fig. 7.36) inclines anteromedially from the tip of the styloid process and upper end of the stylohyoid ligament and passes between the superior and middle constrictors of the pharynx to enter the tongue. It elevates and retracts the tongue and, in common with other muscles of the tongue, is supplied by the hypoglossal (XII) nerve.



Fig. 7.36 Stylopharyngeus and styloglossus seen after excision of digastric, stylohyoid and the middle portion of the stylohyoid ligament.

Mylohyoid and Related Structures


A
R
L
P
Nerve to anterior belly of digastric (cut)
Nerve to mylohyoid
Mylohyoid and raphe
Mandible
Anterior belly of digastric
Facial artery
Position of hyoid bone
Sub-mandibular gland (superficial part)
Hypoglossal nerve

Fig. 7.37 Mylohyoid, revealed by removal of the right anterior belly of digastric and superficial part of the right submandibular gland.


Lingual nerve
Submandibular duct and gland
Mylohyoid and raphe
Nerve to thyrohyoid
S
A
P
I
Inferior alveolar nerve
Nerve to mylohyoid
Hypoglossal nerve
Lingual artery

Fig. 7.38 The hypoglossal nerve, lingual nerve and submandibular duct passing above mylohyoid.



Fig. 7.39 Structures deep to mylohyoid, seen after partial removal of the mylohyoid and the mandible. The submandibular ganglion is elongated in this specimen.

Suspended from the body of the mandible is a thin sheet of muscle formed by the two mylohyoid muscles. The fibres of each muscle incline downwards and medially, meeting each other in the midline to form a shallow gutter. This gutter slopes downwards and backwards and ends at the free posterior borders of the two muscles on either side of the hyoid bone.

Each mylohyoid separates the superficial tissues in the upper part of the neck from the tongue and related structures within the mouth. Below the muscle lie the anterior belly of digastric (p. 348), part of the platysma (p. 336), the facial artery and vein, and the larger superficial part of the submandibular salivary gland (Fig. 7.37). This gland curves around the posterior border of mylohyoid so that its deep part and the submandibular duct lie above the muscle. Also located on the superior aspect of mylohyoid are the sublingual glands, the tongue with its vessels and nerves and the geniohyoid muscles.

Mylohyoid

This muscle (Figs 7.37 & 7.38) takes attachment from the mylohyoid line on the inner aspect of the body of the mandible. Most of its fibres reach a midline raphe, where they interdigitate with those from the opposite side. However, the posterior fibres descend to the body of the hyoid bone. The mylohyoid muscles raise the hyoid bone and the tongue during swallowing; they also help to depress the mandible when the hyoid bone is fixed from below. The muscle is innervated by the mylohyoid nerve, a branch of the inferior alveolar nerve from the mandibular division of the trigeminal nerve (V_3).

Geniohyoid

Above mylohyoid geniohyoid (Fig. 7.39) lies close to the midline, passing from the inferior mental spine (inferior genial tubercle) on the mandible to the body of the hyoid bone. Innervated by C1 spinal nerve fibres that are conveyed in the hypoglossal nerve, geniohyoid either elevates the hyoid or depresses the mandible.

Tongue

The tongue is a muscular organ and lies mostly within the oral cavity, although its posterior part projects into the oropharynx.

Surface features

The tongue is covered by mucosa, which is reflected anteriorly and laterally onto the inferior surface. Under the tip of the tongue the mucous membrane forms a midline


P
R
L
A
Foramen caecum
Sulcus terminalis
Fungiform papillae
Vallate papillae

Fig. 7.40 Surface features of the tongue.


Lingual nerve
Submandibular duct
Genioglossus
Mandible
Geniohyoid
Hypoglossal nerve (cut)
Hyoglossus (cut)
Stylopharyngeus
Ascending palatine artery
Glossopharyngeal nerve
Tonsillar artery
Facial artery
Lingual artery
S
A
P
I

Fig. 7.41 Deeper structures in the base of the tongue, revealed after removal of the sublingual gland and part of hyoglossus.

fold, the frenulum. The upper surface of the tongue (Fig. 7.40) is divided into anterior two-thirds and posterior one-third by a V-shaped groove, the terminal sulcus. A midline depression, the foramen caecum, lies at the apex of the groove. A row of round elevations, the vallate papillae, lies just in front of the sulcus. From the mucosa of the tongue, somatic sensory and taste fibres pass centrally to reach the brain. From the anterior two-thirds of the tongue (and adjacent oral mucosa), these fibres travel in the lingual nerve (p. 345). Somatic sensory fibres continue to the brain in the mandibular (V_3) division of the trigeminal nerve. However, taste fibres leave the lingual nerve and are conveyed via the chorda tympani nerve to the facial (VII) nerve (p. 345). Both taste and somatic sensory nerve fibres from the posterior third of the tongue (including the vallate papillae) are conveyed in the glossopharyngeal (IX) nerve.

Muscles

The musculature of the tongue, divided into two functional halves by a fibrous septum, consists of both extrinsic and intrinsic muscles. In general, the extrinsic muscles alter the position of the tongue and the intrinsic muscles alter its shape.

The extrinsic muscles comprise styloglossus (p. 348), hyoglossus and genioglossus. Hyoglossus (Fig. 7.39) is attached to the body and greater horn of the hyoid bone and its fibres pass upwards and forwards to reach the side of the tongue. Hyoglossus depresses the tongue, particularly at the sides. Genioglossus (Figs 7.41 & 7.42) forms much of the bulk of the tongue, its fibres radiating from the superior mental spine (superior genial tubercle). The superior fibres reach the tip, while the inferior fibres pass into the posteroinferior part of the organ. Genioglossus draws the tongue forwards and downwards and its anterior fibres retract the tip.

Palatoglossus descends from the soft palate and enters the side of the tongue posteriorly. Although it helps to elevate the tongue, it is usually considered to be a muscle of the palate (p. 362).

The intrinsic muscles comprise interlacing longitudinal, transverse and vertical groups of fibres on either side of the midline fibrous septum. The shape of the tongue is changed by integrated contractions of the various groups.

The hypoglossal (XII) nerve (Fig. 7.39) supplies all the muscles of the tongue, both intrinsic and extrinsic. (The nerve supply to palatoglossus is described with the other muscles of the palate; p. 362.) Damage to the hypoglossal nerve causes the tongue to deviate to the injured side when protruded.

Blood supply

Arising from the front of the external carotid artery, the lingual artery (Fig. 7.41) loops upwards above the greater horn of the hyoid bone and continues forwards into the base of the tongue deep to hyoglossus. Having supplied structures in the tongue, the lingual artery terminates in the tip. Venous drainage follows a reciprocal course into the internal jugular vein.

Submandibular and sublingual glands

The superficial part of the submandibular salivary gland (Fig. 7.37) lies inferior to mylohyoid and extends below the medial surface of the mandible. It is continuous around the posterior border of mylohyoid with the smaller deep part (Fig. 7.38) of the gland that lies above the muscle. The lateral surface of the superficial part of the gland is indented by the facial artery as the vessel arches forwards to reach the inferior border of the mandible (p. 337).

From the deep part of the gland the submandibular duct passes forwards and medially to open close to the midline at the base of the frenulum of the tongue. A number of small sublingual glands (Fig. 7.39) lie beneath the mucosa adjacent to the submandibular duct. These glands are drained by ducts that open either into the submandibular duct or directly into the mouth. Calculi in the submandibular duct can often be palpated through the mucosa of the floor of the mouth. Both the sublingual and submandibular glands receive postganglionic parasympathetic secretomotor fibres from the submandibular ganglion (Fig. 7.39). Preganglionic fibres reach the submandibular ganglion from the facial nerve by way of the chorda tympani and lingual nerves.



Fig. 7.42 Sagittal section through the tongue and surrounding structures.

Hypoglossal (XII) nerve

The twelfth cranial nerve (Fig. 7.38) leaves the skull through the hypoglossal canal and descends between the internal jugular vein and internal carotid artery to turn forwards close to the origin of the occipital artery from the external carotid artery, where the superior root of the ansa cervicalis (p. 329) arises. The hypoglossal nerve then continues forwards across the loop of the lingual artery and passes between mylohyoid and hyoglossus to enter the tongue whose muscles it supplies. The branches given to thyrohyoid and geniohyoid are composed of C1 fibres which are distributed via the hypoglossal nerve.

Glossopharyngeal (IX) nerve

The glossopharyngeal nerve (Fig. 7.41) emerges from the skull through the jugular foramen. Initially contained within the carotid sheath, the nerve curves forwards around the stylopharyngeus muscle (which it also supplies) and passes between the superior and middle constrictors of the pharynx to enter the posterior part of the tongue. The glossopharyngeal nerve conveys both somatic and taste sensation from the posterior third of the tongue, oropharynx and lateral parts of the soft palate. The nerve has an autonomic sensory branch, the carotid sinus nerve, which ascends from the carotid sinus and carotid body. In addition, a tympanic branch passes to the tympanic plexus in the middle ear. The lesser petrosal nerve arises from this plexus.

Pterygopalatine Fossa

The pterygopalatine fossa lies between the pterygoid process of the sphenoid bone posteriorly, the palatine bone medially and the maxilla anteriorly (Fig. 7.43). It is slit-like and opens laterally through the pterygomaxillary fissure into the infratemporal fossa. It contains part of the maxillary (V_2) division of the trigeminal nerve, the pterygopalatine ganglion and its branches and the termination of the maxillary artery, together with accompanying veins and lymphatics. The pterygopalatine fossa communicates with the middle cranial fossa through the foramen rotundum, with the foramen lacerum through the pterygoid canal, with the orbit through the inferior orbital fissure, with the walls of the nasal cavity through the sphenopalatine foramen and with the palate via the greater and lesser palatine canals.

Maxillary (V_2) division of the trigeminal nerve

The maxillary division (Fig. 7.44) leaves the cranial cavity through the foramen rotundum, crosses the pterygopalatine fossa and continues forwards through the inferior orbital fissure into the orbit. It terminates as the infraorbital nerve, which traverses the infraorbital canal to reach the face. The maxillary division has several branches arising in the pterygopalatine fossa and the floor of the orbit. In the pterygopalatine fossa (Fig. 7.45), two branches suspend the pterygopalatine ganglion from the parent nerve. Also arising in the fossa are the posterior superior alveolar nerves (Figs 7.44 & 7.45), which descend in the posterior wall of the maxillary air sinus to reach the upper molar teeth. In the floor of the orbit, the middle and anterior superior alveolar nerves (Fig. 7.44) arise and descend in the lateral and anterior walls of the maxilla. Collectively, the superior alveolar nerves


Foramen for zygomatico-facial nerve
Inferior orbital fissure
Pterygo-palatine fossa
Zygomatic arch
Maxilla
Lateral pterygoid plate
Pterygoid hamulus
Styloid process
Mastoid process
S
A
P
I

Fig. 7.43 The pterygopalatine fossa, bounded by the maxilla and lateral pterygoid plate.


Infraorbital nerve
Fibres to lacrimal gland
Zygomatic nerve
Zygomatico-temporal nerve
Anterior superior alveolar nerve
Maxillary (V_2) division
Maxillary air sinus and its mucosa
Posterior superior alveolar nerve
Maxillary artery
S
A
P
I

Fig. 7.44 The maxillary nerve and artery, seen after excision of part of the lateral walls of the orbit and maxillary air sinus.

supply the maxilla and its air sinus, the alveolar ridge and all the upper teeth. The zygomatic nerve (Fig. 7.44) also arises in the floor of the orbit and ascends on the lateral wall, dividing into zygomaticotemporal and zygomaticofacial nerves. These branches pierce the zygomatic bone to supply the overlying facial skin. A branch from the zygomaticotemporal nerve conveys postganglionic parasympathetic fibres from the pterygopalatine ganglion to the lacrimal gland. The infraorbital nerve (Fig. 7.44) emerges onto the face through the infraorbital foramen and supplies the skin of the cheek, lower eyelid, upper lip and lateral surface of the external nose.




Nerve of pterygoid canal
Maxillary (V$_2$) division
Posterior superior alveolar nerve
S
P
A
I
Maxillary artery (cut)
Pharyngeal branch
Pterygo-palatine ganglion
Lesser and greater palatine nerves
Posterior lateral nasal nerve

Fig. 7.45 Medial view of the contents of the pterygopalatine fossa, revealed by removal of bone from the lateral wall of the nose.

Pterygopalatine ganglion

The pterygopalatine ganglion (Fig. 7.45) is suspended from the maxillary division in the pterygopalatine fossa and transmits sensory, parasympathetic and sympathetic nerve fibres. Sensory fibres originating in the palate, nose and nasopharynx pass through the ganglion without synapsing to enter the maxillary division. Preganglionic parasympathetic fibres destined for the ganglion leave the brain in the facial (VII) nerve and travel via the greater petrosal nerve. These fibres emerge from the petrous temporal bone and pass along the floor of the middle cranial fossa to enter the foramen lacerum, where they accompany postganglionic vasomotor sympathetic fibres from the carotid plexus as the nerve of the pterygoid canal to reach the pterygopalatine ganglion. In the ganglion the parasympathetic fibres synapse, and postganglionic fibres are distributed through the appropriate branches of the ganglion to the mucous glands in the nose and palate. Secretomotor parasympathetic fibres destined for the lacrimal gland enter the maxillary division and travel in its zygomatic branch. The ganglion earns its nickname, the ‘hay fever ganglion’, by virtue of its parasympathetic component. Sympathetic fibres are also distributed in the branches of the ganglion.

There are five groups of branches from the pterygopalatine ganglion (Fig. 7.45): posterior lateral nasal, pharyngeal, nasopalatine, and greater and lesser palatine. Posterior lateral nasal nerves, entering via the sphenopalatine foramen, supply the lateral wall of the nasal cavity. The pharyngeal branch innervates the nasopharynx. The nasopalatine nerve (Fig. 7.46) crosses the anterior surface of the body of the sphenoid bone to enter the nasal


Sphenoid air sinus
Auditory tube
Nasopalatine nerve traversing incisive foramen
S
P
A
I
Soft palate
Hard palate
Upper lip

Fig. 7.46 Sagittal section showing the left nasopalatine nerve in situ after removal of the nasal septum.

septum, then angles anteroinferiorly in a groove on the upper edge of the vomer, eventually passing through the incisive canal onto the lower surface of the anterior part of the hard palate. The nerve conveys sensation from the front of the palate and the inferior part of the nasal septum. The greater and lesser palatine nerves traverse the palatine canal to emerge from the appropriate palatine foramina on the lower surface of the hard palate. The greater palatine nerve supplies the hard palate, while the lesser innervates the soft palate.

Vessels

The maxillary artery (Figs 7.44 & 7.45) enters the pterygopalatine fossa from the infratemporal fossa and divides into its terminal branches which accompany the branches of the ganglion and bear corresponding names. Venous blood drains into the pterygoid plexus, which continues into the infratemporal fossa and communicates with the cavernous sinus via the inferior and superior orbital fissures.

Nasal Cavities and Paranasal Air Sinuses

Nasal cavities

The paired nasal cavities lie centrally within the facial skeleton, medial to the orbits and the maxillary air sinuses (Fig. 7.47). They are separated from the oral cavity by the palate, from the anterior cranial fossa by the cribriform plates and from each other by the midline nasal septum. Anteriorly, the cavities lead into the vestibules, which are surrounded by the cartilaginous external nose and open onto the face at the nostrils. Posteriorly, the nasal cavities are limited by the free edge of the nasal septum at the choanae (posterior nasal apertures), which open into the nasopharynx. Each cavity is partially subdivided by three shelf-like projections from the lateral wall, the superior, middle and inferior conchae (turbinates Fig. 7.48). The parts of the nasal cavity beneath each of these are called correspondingly the superior, middle and inferior meatuses, while above the superior concha is the sphenoethmoidal recess. Into this recess and the meatuses drain the paranasal air sinuses and the nasolacrimal duct. Respiratory epithelium lines the cavity and paranasal air sinuses while the vestibule has a stratified squamous epithelium bearing nasal vibrissae (hairs).

Bony walls

The medial wall is the nasal septum (Fig. 7.49), common to both cavities and formed superiorly by the perpendicular plate of the ethmoid. This plate continues upwards as the crista galli, which projects into the anterior cranial fossa. The bony septum is completed posteroinferiorly by the vomer. Anteriorly, the septum is composed of hyaline cartilage which extends into the external nose.

The roof of each cavity comprises, from in front backwards, the nasal and frontal bones, the cribriform plate of the ethmoid and, finally, the body of the sphenoid bone containing the sphenoidal air sinuses. Olfactory (I) nerves from the olfactory mucosa traverse the many small foramina in the cribriform plate to reach the olfactory bulbs in the anterior cranial fossa (Fig. 7.50). These nerves are vulnerable to damage in head injuries with fracture of the cribriform plates, disrupting the sense of smell. Leakage of cerebrospinal fluid from the nose may also result from these fractures.



Fig. 7.47 Coronal section showing the orbits and nasal cavities. Posterior aspect. (Compare Figs 7.84 & 7.92.)

The floor of each nasal cavity is formed by the hard palate, consisting of the palatine process of the maxilla and the horizontal process of the palatine bone.

Numerous bones contribute to the lateral wall (Figs 7.48, 7.50 & 7.51), including the inferior concha and the maxilla, lacrimal, ethmoid, palatine and sphenoid bones. The maxilla forms the anteroinferior portion of the lateral wall and contains the maxillary air sinus. Between the maxilla and the ethmoid, part of the lacrimal bone covers the nasolacrimal canal, which opens into the inferior meatus. Each labyrinth (lateral mass) of the ethmoid is attached to the lateral part of the cribriform plate and contains numerous air cells. From the medial surface of the labyrinth project the small superior and the larger middle conchae. The ethmoidal air cells bulge into the middle meatus, forming the bulla, beneath which a curved groove, the hiatus semilunaris, separates the ethmoid from the maxilla. Forming the posterior limit of the hiatus semilunaris is the vertical plate of the palatine bone. The most posterior component of the lateral wall is the medial pterygoid plate of the sphenoid. Overlying the maxilla and palatine bones is a separate bone, the inferior concha.

Sensory nerve supply

The somatic sensory nerve supply to the walls of the nasal cavity is derived mainly from the maxillary (V_2) division of the trigeminal nerve. The posterior lateral nasal nerves from the pterygopalatine ganglion (p. 354) supply most of the lateral wall, while the nasopalatine nerve supplies the septum. Lesser and greater palatine nerves supply the posterior part of the lateral wall and the floor. In addition, fibres from the ophthalmic (V_1) division reach the nasal cavity via the anterior ethmoidal nerve. This nerve


Superior concha
Cribriform plate
Crista galli
Middle concha
Medial pterygoid plate
Pterygoid hamulus
Inferior concha
S
P
A
I

Fig. 7.48 Bony lateral wall of nasal cavity after sagittal section and removal of the septum.


Posterior border of septum
Sphenoethmoidal recess
Frontal air sinus
Auditory tube
Nasal septum
Hard palate
S
P
A
I

Fig. 7.49 Sagittal section just to right of midline with intact nasal septum.

supplies the anterosuperior parts of the septum and the lateral wall and continues as the external nasal nerve to supply the midline part of the external nose.

Blood supply

Most of the blood supply to the walls of the nasal cavity is provided by branches of the maxillary artery. These vessels arise in the pterygopalatine fossa and are named according to the branches of the pterygopalatine ganglion they accompany. The anteroinferior part of the nasal septum is highly vascular (Little's area) and commonly gives rise to nasal haemorrhage (epistaxis).

Venous blood passes to the pterygoid plexus, the facial vein and the ophthalmic veins.

Paranasal air sinuses

There are four paired groups of paranasal air sinuses (Figs 7.51–7.54) contained within the frontal, maxillary, ethmoid and sphenoid bones. Each sinus communicates with the nasal cavity, is lined with mucous membrane and normally contains air. The frontal air sinuses are situated in the vertical and horizontal parts of the frontal bone, closely related to the frontal lobes of the brain. They are variable in size and open into the middle meatus at the infundibulum, the most anterior part of the hiatus semilunaris. The frontal air sinus is supplied by the supraorbital branch of the ophthalmic (V_1) division of the trigeminal nerve.

The maxillary air sinus (antrum) occupies the body of the maxilla, lying above the oral cavity and alveolar ridge and below


Olfactory bulb and nerves
Cribriform plate
S
P
A
I
Superior concha
Middle concha
Inferior concha
Sphenoidal air sinus
Auditory tube
Hard palate

Fig. 7.50 Sagittal section with the nasal septum removed to show the lateral wall of the nasal cavity.


Sphenoidal air sinus
Ethmoidal air cells
Frontal air sinus
S
P
A
I
Infundibulum
Hiatus semilunaris
Opening into maxillary air sinus
Attachment for inferior concha
Auditory tube
Opening of naso-lacrimal duct

Fig. 7.51 Sagittal section after removal of the conchae, the ethmoid bulla and the upper part of the lateral nasal wall.


PA
L
S
R
L
I
Frontal air sinus
Orbit
Ethmoid air cells
Maxillary air sinus
Nasal cavity

Fig. 7.52 Skull radiograph showing paranasal air sinuses.


S
L
R
I
Ethmoid air cells
Maxillary sinus
Nasal cavity
S
P
A
I
Frontal sinus
Ethmoid air cells

Fig. 7.53 Coronal and sagittal CT scans showing paranasal air sinuses.

the orbit. Its opening at the posterior end of the hiatus semilunaris lies high on the medial wall of the antrum, permitting limited drainage for contents such as mucus or pus. Sensory innervation is from the superior alveolar nerves.

The ethmoidal air sinuses are subdivided into three groups of air cells, which communicate with the nose through many tiny foramina. The anterior cells open into the floor of the hiatus, while the middle cells open onto the bulla, both groups being supplied by the anterior ethmoidal nerve. The posterior group, innervated by the posterior ethmoidal nerve, drains into the superior meatus under the superior concha.

The sphenoidal air sinuses lie just below the sella turcica in the body of the sphenoid, through the anterior wall of which they open into the sphenoethmoidal recess. The sensory supply is from the pharyngeal branch of the pterygopalatine ganglion. The pituitary gland can be accessed surgically through the sphenoidal air sinus.

Infection of the paranasal air sinuses (sinusitis) causes thickening of the mucosal lining, which may block the openings into the nasal cavities.



Fig. 7.54 Position of the paranasal air sinuses.

Palate

The palate consists of hard and soft parts covered by mucous membrane (Fig. 7.55). The hard palate separates the oral and nasal cavities while posteriorly the soft palate separates the nasopharynx from the oropharynx.

Hard palate

The bones that comprise the hard palate are the palatine processes of the maxillae anteriorly and the horizontal plates of the palatine bones posteriorly (Fig. 7.82). The hard palate is bounded in front and laterally by the superior alveolar ridge. The soft palate is attached to the free posterior border of the hard palate. Sensory fibres reach the palate in branches of the maxillary (V_2) division of the trigeminal nerve. The nasopalatine nerve emerges from the incisive foramen and supplies the anterior part of the hard palate. The greater palatine nerve gains the hard palate via the greater palatine foramen and innervates its posterior portion.

Soft palate

The soft palate projects into the cavity of the pharynx from its attachment to the posterior edge of the hard palate. When elevated, it separates the oropharynx from the nasopharynx. Five paired muscles attach to the soft palate and contribute to its structure. In the midline the uvula projects downwards from its posterior free border.

Muscles

Tensor veli palatini (Fig. 7.57) attaches to the scaphoid fossa and spine of the sphenoid and to the lateral surface of the cartilaginous portion of the auditory (Eustachian) tube. Its fibres descend between the lateral and medial pterygoid plates on the lateral aspect of the pharyngeal wall and give way to a tendon just above




Pharyngeal tonsil
Auditory tube
Naso-pharynx
Soft palate
Palato-pharyngeal ridge
Oro-pharynx
Epiglottis
Laryngo-pharynx
Cricoid cartilage
S
P
A
I
Nasal cavity
Hard palate
Oral cavity
Palato-glossal ridge
Palatine tonsil
Mandible
Tongue
Hyoid bone
Thyroid cartilage
Laryngeal cavity

Fig. 7.55 Sagittal section through palate and pharynx showing communication with the nasal, oral and laryngeal cavities. Red line, boundaries of subdivisions of pharynx.


Auditory tube
Levator veli palatini
Salpingo-pharyngeus
Uvular muscle
Palato-pharyngeus
S
P
A
I
Hard palate
Palato-glossus
Tongue musculature
Mandible

Fig. 7.56 Further dissection of Fig. 7.55 to show some of the muscles of the soft palate.

the pterygoid hamulus. The tendon hooks under the hamulus and turns medially to enter the soft palate, where it forms the palatine aponeurosis by fanning out and attaching to the posterior border of the hard palate. The palatine aponeurosis forms the basic structure of the soft palate to which other muscles gain attachment. Tensor veli palatini is supplied by the mandibular (V_3) division of the trigeminal nerve and tenses the soft palate.

Levator veli palatini (Figs 7.56 & 7.57) attaches to the inferior surface of the petrous temporal bone just medial to the opening of the auditory tube and to the adjacent part of the tube. Its fibres descend medial to the medial pterygoid plate within the pharynx and attach to the upper surface of the palatine aponeurosis. The muscle is innervated by the pharyngeal plexus (p. 364). Levator veli palatini elevates the soft palate during swallowing, preventing regurgitation of food into the nasal cavities.

Palatoglossus (Fig. 7.56) descends from the inferior surface of the palatine aponeurosis and inclines slightly forwards to enter the posterolateral part of the tongue. The position of palatoglossus is evident on the inner surface of the oral cavity as a mucosal elevation, the palatoglossal ridge (anterior pillar of the fauces; Fig. 7.55). The two palatoglossal ridges form the oropharyngeal isthmus, which marks the posterior boundary of the oral cavity. Innervated by fibres from the pharyngeal plexus, palatoglossus lowers the soft palate, raises the posterior part of the tongue and moves the palatoglossal ridge towards the midline, thus narrowing the isthmus.

Palatopharyngeus (Figs 7.56 & 7.57) attaches to the undersurface of the soft palate. Most of its fibres run posteroinferiorly as part of the longitudinal layer of muscle inside the pharynx and form the palatopharyngeal ridge (posterior pillar of the fauces). On contraction, these fibres depress the soft palate. Other fibres pass horizontally backwards, raising the mucosa into a ridge, against which the soft palate is elevated. Palatopharyngeus receives its motor supply from the pharyngeal plexus.

The uvular muscle (Figs 7.56 & 7.57), also supplied by the pharyngeal plexus, lies entirely within the soft palate and elevates the uvula. In cases of unilateral paralysis of the soft palate, the uvula rises asymmetrically, being pulled away from the paralysed side.

Sensory and secretomotor innervation to the soft palate is from the lesser palatine nerves of the maxillary (V_2) division of the trigeminal nerve, supplemented laterally on the undersurface of the palate by the glossopharyngeal (IX) nerve.



Fig. 7.57 Posterior view of soft palate after removal of cervical vertebral column and posterior wall of pharynx. On the left side, the medial pterygoid and the mucosa of the soft palate have been removed to reveal the muscles.

Pharynx

The pharynx is a muscular tube, which is continuous inferiorly with the oesophagus and into which the nasal, oral and laryngeal cavities open (Fig. 7.60). For descriptive purposes, the pharynx is divided into nasopharynx, oropharynx and laryngopharynx (hypopharynx Fig. 7.55). The nasopharynx is attached to the base of the skull and is bounded anteriorly by the choanae. Inferiorly, it is continuous with the oropharynx at the level of the soft palate. The oropharynx begins anteriorly at the palatoglossal ridge and extends inferiorly to the level of the upper border of the epiglottis, where it is in continuity with the laryngopharynx. The laryngopharynx lies behind the laryngeal inlet, the arytenoids and the cricoid lamina, and on either side of the inlet forms recesses, the piriform fossae (Fig. 7.61). In normal deglutition, these fossae are traversed by fluid and food which pass behind the cricoid cartilage in the terminal part of the laryngopharynx. Foreign bodies such as fish bones may lodge in these recesses during swallowing. At the inferior border of the cricoid cartilage, it is continuous with the oesophagus. The musculature of the pharynx consists of incomplete outer circular and inner longitudinal layers. The pharyngobasilar fascia lies internal to the muscle coat and is lined by mucous membrane.

Muscles

The circular layer of muscles comprises three overlapping constrictors, attaching posteriorly to the midline raphe (Figs 7.58 & 7.59), which is suspended from the pharyngeal tubercle of the occipital bone.

The superior constrictor attaches anteriorly to the lower part of the medial pterygoid plate, the pterygomandibular raphe (in company with buccinator; p. 336) and the posterior end of the mylohyoid line on the mandible. Posteriorly, its fibres attach to the pharyngeal tubercle and the pharyngeal raphe.

The middle constrictor attaches to the lower part of the stylohyoid ligament and to the angle between the greater and lesser horns of the hyoid bone. Posteriorly, it attaches to the raphe, the upper fibres overlapping those of the superior constrictor.

The inferior constrictor has an anterior attachment to the oblique line on the thyroid cartilage, the lateral surface of the cricoid cartilage and the intervening fascia covering the cricothyroid muscle. Its superior fibres curve upwards to the pharyngeal raphe, overlapping those of the middle constrictor. The lower fibres, known as cricopharyngeus, pass horizontally around the lumen of the pharynx below the raphe.

The inner longitudinal layer consists of the stylopharyngeus, palatopharyngeus and salpingopharyngeus muscles. Stylopharyngeus (p. 348) attaches to the styloid process and lies lateral to the superior constrictor. Its fibres descend between the superior and middle constrictors (Fig. 7.59) to blend with the other longitudinal muscles on the medial surface of the two lower constrictors. Palatopharyngeus inclines posteroinferiorly from the soft palate, while salpingopharyngeus descends from the auditory tube, both muscles lying on the inner surface of the constrictors (Fig. 7.56). The longitudinal muscles attach inferiorly to the posterior border of the lamina of the thyroid cartilage.

During swallowing, the pharyngeal constrictors contract sequentially from above downwards to propel the bolus of food into the oesophagus. Simultaneously, the longitudinal muscles shorten the pharynx and elevate the larynx, thus closing its inlet against the base of the tongue. Due to the shape of the epiglottis, the bolus tends to traverse the piriform fossae. At the same time, the soft palate is raised to prevent food entering the nasopharynx and the cricopharyngeus relaxes to allow the bolus to enter the oesophagus.


Internal jugular vein
Internal carotid artery
Superior middle and inferior constrictors
Cervical sympathetic trunk
Vagus nerve
Pharyngeal raphe
S
L
R
I
Ascending pharyngeal artery
Vagus nerve and pharyngeal branch
Superior laryngeal nerve
Pharyngeal plexus
Thyroid gland
Carotid and subclavian arteries
Recurrent laryngeal nerve

Fig. 7.58 Posterior view of pharyngeal musculature after removal of cervical vertebral column, posterior part of the skull, right sympathetic trunk and part of the right internal carotid artery.

Nerve supply

The pharyngeal plexus (Fig. 7.58) consists of nerve fibres lying on the outer surface of the pharynx and receives the pharyngeal branches of the glossopharyngeal (IX) and vagus (X) nerves. The motor component of the plexus is derived from the cranial part of the accessory (XI) nerve via the vagus nerve. It supplies the muscles of the pharynx, except for stylopharyngeus (glossopharyngeal nerve; p. 352).

Sensory fibres from the glossopharyngeal nerve traverse the plexus to supply the oropharynx and mediate the gag reflex. The vagal fibres of the plexus, assisted by those travelling in the laryngeal nerves (p. 370), innervate the laryngopharynx. The sensory innervation of the nasopharynx is supplied by the maxillary (V_2) division of the trigeminal nerve via its pharyngeal branch from the pterygopalatine ganglion.

Pharyngobasilar fascia and auditory tube

The inner surface of the pharyngeal musculature is lined by the pharyngobasilar fascia. This fascial sheet completes the wall of the pharynx superiorly and forms a continuous attachment to the base of the skull. Inferiorly, the fascia becomes gradually thinner, blending with the epimysium of the pharyngeal muscles.


Styloid process
Superior constrictor
Stylo-hyoid ligament
Buccinator
Hyoid bone
Internal jugular vein (cut)
Stylo-pharyngeus
Glosso-pharyngeal nerve
Middle constrictor
Internal and external laryngeal branches of superior laryngeal nerve (cut)
Inferior constrictor
S
L
R
I

Fig. 7.59 Oblique posterior view of pharyngeal musculature.


Stylo-pharyngeus
Styloid process
Inferior concha
Stylo-hyoid ligament
Glosso-pharyngeal nerve
Superior laryngeal nerve
Nasal septum and cavity
Superior constrictor (cut)
Oral cavity
Tongue
Middle constrictor (cut)
Laryngeal cavity
Inferior constrictor (cut)
Oesophagus (cut)
S
L
R
I

Fig. 7.60 Interior of the pharynx. This specimen retains medial pterygoid on the right and the styloid apparatus on the left.

The auditory (Eustachian) tube (Figs 7.55–7.57) opens into the nasopharynx above the superior constrictor by piercing the pharyngobasilar fascia. Laterally, the auditory tube leads into the cavity of the middle ear.

Lymphoid tissue

An incomplete ring of lymphoid tissue, the pharyngeal lymphoid ring (Waldeyer's ring) (Fig. 7.55), lies in the wall of the pharynx between the mucosa and the muscles. This tissue is often subject to infection, particularly in children. On each side, a palatine tonsil lies between the palatoglossal and palatopharyngeal ridges and has a rich blood supply, including its own tonsillar branch from the facial artery. The adenoids, or pharyngeal tonsils, are situated near the roof of the nasopharynx, close to the auditory tubes with their tubal tonsils. When enlarged, the adenoids and tubal tonsils may obstruct one or both tubes, giving rise to middle ear disease. The lingual tonsil lies under the mucosa of the posterior third of the tongue and comprises a diffuse collection of small lymphoid follicles.

Blood supply

The arterial supply to the pharynx is derived from branches of the facial, lingual and maxillary arteries (p. 333). The ascending pharyngeal artery (Fig. 7.58) is a direct branch of the external carotid artery and passes upwards medial to the styloid muscles on the lateral surface of the pharynx. Venous blood drains into the pterygoid plexus and the internal jugular vein.

Larynx

The larynx acts as a sphincter guarding the lower respiratory tract and is responsible for phonation. It lies in the neck and its inlet is continuous with the laryngopharynx (Figs 7.61 & 7.62). Inferiorly, the larynx is continuous with the trachea. It consists of a framework of cartilages and bone, which supports the vocal and vestibular folds and the muscles that move them. Anteriorly lie the infrahyoid strap muscles.

Skeleton

The skeleton of the larynx comprises the thyroid, cricoid and arytenoid cartilages, the epiglottis and the hyoid bone.

The thyroid cartilage (Figs 7.67 & 7.68) has two flat laminae joined anteriorly to form the midline laryngeal prominence (Adam's apple). The posterior margin of each lamina is free and bears a superior and an inferior horn. The tips of the inferior horns articulate by tiny synovial joints with the lateral surfaces of the cricoid cartilage.




Soft palate
Uvula
Posterior part of tongue
Vallecula
Epiglottis
Lateral glosso-epiglottic fold
Internal laryngeal nerve (cut)
Piriform fossa
Oesophagus
A
L
R
P

Fig. 7.61 Posterosuperior view of the larynx, seen through the opened laryngopharynx. The lumen of the larynx is visible through the laryngeal inlet (pink line).


A
L
R
P
Position of hyoid bone
Epiglottis
Vestibular fold
Glottis
Vocal fold
Piriform fossa
Internal laryngeal nerve

Fig. 7.62 Superior view into the larynx. The mucosa lining the laryngopharynx has been removed to reveal the internal laryngeal nerve (laryngeal inlet, pink line).

The cricoid cartilage (Figs 7.67 & 7.71) lies below the thyroid cartilage and is signet ring-shaped, with a narrow anterior arch and a wide posterior lamina. Its inferior border lies horizontally, while the superior border slopes upwards posteriorly. Movement at the cricothyroid joints allows the arch of the cricoid to tip upwards, while the lamina tips backwards.

In addition to its articulations with the thyroid cartilage, the upper border of the cricoid lamina bears articular surfaces, one on each side of the midline, for synovial joints with the two arytenoid cartilages. Each arytenoid (Figs 7.64, 7.67 & 7.71) is pyramidal in shape, with its base on the cricoid lamina and its apex superiorly. It has four surfaces (medial, posterior, anterolateral


S
L
R
I
Greater horn of hyoid bone
Aryepiglottic muscle
Cricothyroid articulation
Recurrent laryngeal nerve
Superior horn of thyroid cartilage
Arytenoid muscle
Posterior crico-arytenoid
Cricoid lamina

Fig. 7.63 Some of the intrinsic muscles of the larynx, seen after removal of the mucosa of the laryngopharynx.


S
L
R
I
Epiglottis
Apex
Body of arytenoid cartilage
Muscular process
Inferior horn of thyroid cartilage (cut)
Capsule of cricothyroid articulation
Arytenoid muscle (cut)
Posterior cricoarytenoid
Cricoid lamina

Fig. 7.64 Cricoid and arytenoid cartilages, exposed by removal of most of the soft tissues on the left of the larynx.

and inferior) and two processes. Anteriorly lies the vocal process, to which the vocal fold is attached, while its muscular process projects laterally. Each arytenoid is able to rotate around its own vertical axis. In addition, the arytenoids can slide laterally and downwards away from the midline on the slope of the articular surface on the cricoid.

The epiglottis (Figs 7.64 & 7.67) is attached in the midline to the inner surface of the thyroid cartilage, just below the laryngeal prominence. It extends upwards and backwards behind the tongue to which it is attached in the midline by the median glosso-epiglottic fold. From each side of the epiglottis a lateral glosso-epiglottic fold (Fig. 7.61) extends to the side of the tongue. These folds bound a recess on each side of the midline, the vallecula (Fig. 7.61), which is a site where swallowed foreign bodies may lodge. The epiglottis overlies the laryngeal inlet when the larynx is raised against the tongue when swallowing.

The hyoid bone (Figs 7.62 & 7.67) is the uppermost skeletal element of the larynx. It consists of a midline body bearing greater horns projecting posteriorly. On each side a lesser horn is located on the upper surface where the body and greater horn unite.

Membranes and ligaments

Several membranes are attached to the laryngeal framework and fill the gaps between the skeletal structures. The conus elasticus (cricovocal membrane) (Fig. 7.66) is elastic and attaches inferiorly to the upper border of the cricoid cartilage. In the midline anteriorly, it reaches the inferior border of the thyroid cartilage, forming the inelastic cricothyroid ligament. Posteriorly it is attached to the vocal processes of the arytenoids. The membrane has a free upper border, which runs between the arytenoids and the thyroid cartilage and forms the basis of the vocal folds (true vocal cords).

The inelastic quadrangular (aryepiglottic) membrane (Fig. 7.66) attaches posteriorly to the body and apex of the arytenoid and anteriorly to the lower part of the lateral edge of the epiglottis. It has a lower free border which forms the vestibular fold (false vocal cord), while the upper free edge forms the aryepiglottic fold (part of the laryngeal inlet).

The thyrohyoid membrane (Fig. 7.68) fills the gap between the thyroid cartilage and the hyoid bone. Its posterior free edges are thickened to form the lateral thyrohyoid ligaments, while the midline thickening is the median thyrohyoid ligament.

Mucous membrane (Fig. 7.65) lines the interior of the larynx. The epithelium is of the respiratory type, except over the vocal and aryepiglottic folds where it is stratified and squamous. A pouch of mucous membrane protrudes laterally between the vocal and vestibular folds, forming the saccule. It contains numerous mucous glands, the secretions of which moisten the vocal folds.

Intrinsic muscles

The intrinsic laryngeal muscles control the position and tension of the vocal and aryepiglottic folds, therefore modifying the shape of the airway through the larynx, acting both at the glottis (rima glottidis), the gap between the vocal folds, and at the inlet (Fig. 7.62). During swallowing, both openings narrow, but in coughing and phonation only the glottis narrows. The glottis





Fig. 7.65 Median sagittal section showing the lumen and mucous membrane of the larynx.

widens during inspiration, especially when deep. The muscles are symmetrical in their arrangement.

The cricothyroid muscle (Fig. 7.68) attaches to the anterolateral surface of the cricoid cartilage and to the inferior edge of the thyroid cartilage and adjacent part of the inferior horn. It raises the arch of the cricoid cartilage, tipping the lamina backwards and thereby increasing the tension and length of the vocal folds. This has the effect of raising the pitch of the voice and narrowing the glottis.

The thyroarytenoid muscle (Fig. 7.70) attaches to the posterior surface of the thyroid cartilage adjacent to the conus elasticus. Its fibres pass posteriorly to gain the vocal process and adjacent body of the arytenoid cartilage. The muscle opposes the action of cricothyroid, drawing the arytenoids forwards and relaxing the vocal folds. Part of the muscle (vocalis) lies in the free edge of the vocal fold. The vocalis gives rigidity to the edge of the fold and also modifies tension differentially along its length.


S
P
A
I
Aryepiglottic fold
Thyrohyoid membrane
Apex of left arytenoid cartilage
Vocal process of arytenoid cartilage
Conus elasticus
Quadrangular membrane
Vestibular fold
Vocal fold
Cricothyroid ligament
Cricoid cartilage

Fig. 7.66 Membranes and folds of the larynx, revealed by removal of most of the mucosa.


S
P
A
I
Lateral thyrohyoid ligament
Superior horn of thyroid cartilage
Left arytenoid cartilage
Capsule of cricoarytenoid joint
Cricoid cartilage
Hyoid
Epiglottic cartilage
Thyroid lamina
Conus elasticus (cut)
Cricothyroid ligament

Fig. 7.67 Bisected skeleton of the larynx, revealed by removal of membranes.

Two muscles attach to the muscular process of each arytenoid. The lateral cricoarytenoid (Fig. 7.69) attaches to the lateral surface of the cricoid, its fibres passing posterosuperiorly to reach the muscular process of the arytenoid. The muscle rotates the arytenoid around its vertical axis, adducting the vocal folds and thereby closing the glottis. The posterior cricoarytenoid (Figs 7.63 & 7.69) inclines anterosuperiorly from the lamina of the cricoid to the muscular process of the arytenoid. Its action opposes that of the lateral cricoarytenoid, rotating the arytenoid so that the folds are abducted and the glottis opened. Simultaneous contraction of the lateral and posterior cricoarytenoid muscles separates the arytenoids by sliding them down the cricoid lamina.

The arytenoid muscle (Figs 7.63 & 7.65) spans the gap between the bodies of the arytenoid cartilages and has transverse and oblique parts. The muscle approximates the arytenoids, closing the glottis. The oblique arytenoids continue anterosuperiorly in the aryepiglottic fold as the aryepiglottic muscles (Fig. 7.69). These assist in closing the laryngeal inlet and are important during swallowing.

Nerve supply

The larynx is supplied by the right and left superior and recurrent laryngeal branches of the vagus (X) nerves. Each recurrent laryngeal nerve (Figs 7.68 & 7.69) ascends from the root of the neck


S
A
P
I
Thyrohyoid ligament
Internal laryngeal nerve
Thyrohyoid membrane
Superior horn of thyroid cartilage
Thyroid lamina
Oblique line
External laryngeal nerve
Inferior horn of thyroid cartilage
Cricothyroid ligament
Cricothyroid
Recurrent laryngeal nerve
Trachea
Oesophagus

Fig. 7.68 Anterolateral view of the larynx.


S
A
P
I
Hyoid (cut)
Aryepiglottic muscle
Part of thyroarytenoid
Arytenoid muscle
Lateral cricoarytenoid
Thyroid cartilage (cut)
Posterior cricoarytenoid
Cricoid cartilage
Inferior horn of thyroid cartilage (cut)
Cricothyroid (cut)
Left recurrent laryngeal nerve

Fig. 7.69 Deeper intrinsic muscles seen after removal of half of the thyroid cartilage and the hyoid bone.

(p. 331) in the groove between the trachea and oesophagus. Passing beneath the lower border of the inferior constrictor, the nerve enters the larynx behind the cricothyroid joint.

It supplies motor fibres to all of the intrinsic muscles (except cricothyroid) and carries sensory fibres from all of the structures within the larynx and laryngopharynx below the level of the vocal folds.

The superior laryngeal nerve (Figs 7.58 & 7.68) arises from the vagus nerve just below the skull and descends to the thyrohyoid membrane where it divides, forming a motor external laryngeal branch and a sensory internal laryngeal branch. The external laryngeal nerve (Fig. 7.68) descends on the outer surface of the larynx to supply the cricothyroid muscle. The internal laryngeal branch (Figs 7.62 & 7.68) pierces the thyrohyoid membrane and provides sensory fibres to the larynx and laryngopharynx above the vocal folds. These sensory nerves contribute to the cough reflex.

Blood supply

The laryngeal branches of the superior and inferior thyroid arteries (Figs 7.13 & 7.15) supply the larynx, while venous blood drains via superior and middle thyroid vessels into the internal jugular veins.


S
A
P
I
Left arytenoid cartilage
Muscular process
Thyroarytenoid
Cricothyroid ligament
Posterior cricoarytenoid
Cricoid cartilage

Fig. 7.70 Thyroarytenoid and the arytenoid cartilage after excision of the lateral cricoarytenoid, arytenoid and aryepiglottic muscles.


S
A
P
I
Epiglottis (cut)
Apex of left arytenoid cartilage
Vocal process
Muscular process
Cricothyroid ligament
Cricoid arch

Fig. 7.71 Cartilages of the larynx, revealed by removal of muscles and membranes on the left side.

Cranium and Contents

The part of the skull that contains the brain and its immediate relations is called the neurocranium. Although the detailed anatomy of the central nervous system is outside the scope of this book, there are some important surface features of the brain (Figs 7.73 & 7.74) to which reference should be made when considering the bony features of the interior of the cranium.

Bony features

The vault of the skull consists of four flat bones. Anteriorly is the frontal bone, posteriorly, the occipital bone and on each side is a parietal bone (Fig. 7.72). The frontal and parietal bones meet along the coronal suture, and the two parietal bones meet along the midline sagittal suture. Posteriorly, the parietal bones meet the occipital bone at the lambdoid suture. The undersurface of the vault bears a long shallow midline groove for the superior


Greater wing
Coronal suture
External acoustic meatus
Lambdoid suture
Lateral pterygoid plate
Pterygoid hamulus
Zygomatic process
Styloid process
Mastoid process
S
A
P
I
Parietal
Zygomatic
Nasal
Temporal
Sphenoid
Maxilla
Frontal
Occipital
Ethmoid
Lacrimal

Fig. 7.72 Lateral view of the skull (without the mandible) showing the component bones.


Olfactory bulbs
Pons
Medulla
S
A
P
I
Parietal lobe
Occipital lobe
Temporal lobe
Cerebellum
Frontal lobe
Brainstem

Fig. 7.73 Lateral view of the brain showing the cerebral hemisphere and the hindbrain.

sagittal venous sinus (see below), which terminates at a prominence, the internal occipital protuberance (Fig. 7.75). Below the level of each parietal bone, the greater wing of the sphenoid bone and the squamous part of the temporal bone complete the lateral wall of the vault.

The cranial base is characterized by the anterior, middle and posterior fossae, arranged in step-like sequence (Fig. 7.75), the anterior being superior. The anterior fossa, which accommodates the frontal lobes of the brain, is formed by the frontal bone laterally, the cribriform plates and crista galli of the ethmoid bone medially and is completed posteriorly by the lesser wings of the sphenoid bone. The numerous small foramina in the cribriform plates communicate with the nasal cavity (p. 356).

The middle fossa, occupied by the temporal lobes of the brain, is formed by the greater wings and body of the sphenoid bone. Posteriorly, the fossa is bounded by the petrous part of each temporal bone, while anteriorly the fossa is completed by the lesser wings of the sphenoid. Each of the lesser wings is perforated by the optic canal, which continues forwards into the orbit. Between the lesser and greater wings is the superior orbital fissure, which also provides access to the orbit. The greater wing is traversed by the foramen rotundum (opening into the pterygopalatine fossa; p. 353) and the foramina ovale and spinosum (both opening into the infratemporal fossa; Fig. 7.82). Lying in the angle between the greater wing and body of the sphenoid and the apex of the petrous part of the temporal bone is the foramen lacerum, which forms part of the roof of the infratemporal fossa. In the midline the body of the sphenoid is hollowed, forming the sella turcica. This is limited by the paired anterior and posterior clinoid processes and accommodates the pituitary gland.

The posterior cranial fossa contains the cerebellum, the pons and the medulla oblongata which is in continuity through the foramen magnum with the spinal cord. The floor of this fossa is formed mostly by the occipital bone, supplemented anteriorly by the body of the sphenoid and the posterior surface of the petrous part of each temporal bone. Anterior to the foramen magnum, the occipital and sphenoid bones fuse to form a smooth incline, the clivus, on which the brainstem lies. The internal acoustic meatus opens onto the posterior surface of the petrous part of the temporal bone while in the suture between this bone and the occipital bone is the jugular foramen. Running horizontally from the internal occipital protuberance is a groove for the transverse venous


Oculomotor nerve
Pons
Medulla
Olfactory bulb
Optic nerve
Internal carotid artery
Basilar artery
A
R
L
P
Temporal lobe
Frontal lobe
Occipital
Cerebellum
Brainstem

Fig. 7.74 Inferior surface of the brain.


Crista galli
Cribriform plate
Superior orbital fissure
Foramen rotundum
Foramen ovale
Groove for inferior petrosal sinus
Internal acoustic meatus
Jugular foramen
Foramen magnum
Optic canal
Lesser wing of sphenoid
Anterior clinoid process
Sella turcica
Foramen lacerum
Foramen spinosum
Petrous part of temporal bone
Groove for superior petrosal sinus
Groove for sigmoid sinus
Internal occipital protuberance
A
L
R
P
Anterior cranial fossa
Middle cranial fossae
Posterior cranial fossa

Fig. 7.75 Base of the skull from above showing the cranial fossae.

sinus. An S-shaped groove for the sigmoid sinus (Fig. 7.75) links the groove for the transverse sinus with the jugular foramen. The hypoglossal canal traverses the occipital bone anterolateral to the foramen magnum (Fig. 7.82).

Meninges

Surrounding the brain are three membranes, the meninges, which comprise the dura mater, arachnoid mater and pia mater.

Dura mater

The dura mater consists of outer periosteal and inner meningeal layers. The periosteal dura attaches to and closely follows the bony contours of the cranial cavity and is continuous through the sutures and foramina with the periosteum (pericranium) on the outer surface of the skull. Although generally bound to the periosteal dura, the meningeal dura is raised in places as a double layer, forming the dural folds.

The largest of these folds is the midline falx cerebri (Figs 7.76 & 7.77), which projects downwards between the two cerebral hemispheres.

Anteriorly, the falx cerebri is attached to the crista galli of the ethmoid bone. It arches over the corpus callosum and gains further attachment to the frontal, parietal and occipital bones. Posteriorly, the falx ends by attaching to another dural fold, the tentorium cerebelli (Figs 7.76–7.78). The tentorium forms an incomplete roof over the posterior cranial fossa and separates the occipital lobes of the cerebrum from the cerebellum. Each side of the tentorium slopes upwards towards its midline attachment to the falx cerebri. Anteriorly, there is a large aperture in the tentorium through which the brainstem passes. The thickened free edge of the tentorium surrounding this aperture continues forwards to reach the anterior clinoid process. The attached border of the tentorium runs laterally from the internal occipital protuberance along a horizontal groove on the inner surface of the occipital bone, then continues medially along the superior border of the petrous part of the temporal bone to reach the posterior clinoid process. Posteriorly, the small falx cerebelli descends vertically from the tentorium and partially separates the two cerebellar hemispheres. The sella turcica in the middle fossa has a roof of dura called the diaphragma sellae, which is attached to the four clinoid processes and has a central aperture for the pituitary stalk.

Dural venous sinuses

Lying between the two layers of dura are endothelium-lined venous channels (Fig. 7.77). These dural venous sinuses, which often groove the adjacent bones, collect blood from the brain and meninges. They also drain cerebrospinal fluid that has been secreted into the subarachnoid space by the choroid plexuses of the brain. A characteristic of these sinuses is the absence of valves.

The superior sagittal sinus lies in the attached margin of the falx cerebri (Figs 7.76 & 7.77). The sinus drains posteriorly and has along its length several dilatations called lacunae. These lacunae possess arachnoid granulations through which the reabsorption of cerebrospinal fluid takes place. The sinus also receives numerous cerebral veins. At the internal occipital protuberance the superior sagittal sinus turns laterally, usually to the right, and continues as the transverse sinus in the attached margin of the tentorium cerebelli (Fig. 7.78). Just before reaching the petrous part of the temporal bone, the sinus turns inferiorly to continue as the sigmoid sinus (Fig. 7.79). This follows an S-shaped course to reach the jugular foramen, through which it is continuous with the internal jugular vein.


Position of superior sagittal sinus
Position of inferior sagittal sinus
Middle cranial fossa
Anterior cranial fossa
Midbrain (cut)
S
A
P
I
Falx cerebri
Great cerebral vein
Position of straight sinus
Tentorium cerebelli and free edge

Fig. 7.76 Falx cerebri and tentorium cerebelli, revealed by removal of the vault of the cranium, associated dura and the cerebral hemispheres.

The smaller inferior sagittal sinus lies in the free border of the falx cerebri (Fig. 7.76). The sinus runs posteriorly and at the tentorium cerebelli is joined by the great cerebral vein, which drains the deeper structures of the cerebral hemispheres. The union of these vessels forms the straight sinus (Figs 7.76–7.78), which continues posteriorly in the attachment of the falx cerebri to the tentorium as far as the internal occipital protuberance. Here, the straight sinus usually turns to the left to form the transverse sinus, whose course mirrors that on the opposite side. This region is known as the confluence of sinuses.

The cavernous venous sinuses (Figs 7.79 & 7.80) lie on either side of the pituitary gland and the body of the sphenoid bone. They contain numerous interconnected venous spaces, producing a spongy appearance. The two sinuses communicate with each


Superior sagittal sinus
Dura
S
R
L
I
Falx cerebri
Cerebral hemisphere
Straight sinus
Tentorium cerebelli
Transverse sinus
Cerebellum

Fig. 7.77 Coronal section through the posterior cranial fossa, showing dura and its folds and venous sinuses. Anterior aspect.


Transverse sinus
Optic (II) nerve
Anterior attachment of falx cerebri
Olfactory bulb (I)
A
L
R
P
Anterior cerebral artery
Midbrain
Great cerebral vein (cut)
Straight sinus
Tentorium cerebelli
Posterior attachment of falx cerebri
Superior sagittal sinus

Fig. 7.78 Superior view of the tentorium cerebelli after removal of the falx cerebri and cerebral hemispheres. The venous sinuses have been opened. The straight sinus turns to the right and the superior sagittal sinus to the left in this specimen.

other and receive blood from vessels that pass through the superior and inferior orbital fissures from the ophthalmic veins and pterygoid venous plexuses. Posteriorly each cavernous sinus drains via the superior and inferior petrosal sinuses. The superior petrosal sinus runs along the superior border of the petrous part of the temporal bone to terminate in the junction of the transverse and sigmoid sinuses. The inferior petrosal sinus descends into the posterior cranial fossa and unites with the sigmoid sinus in the jugular foramen to form the internal jugular vein.

Arachnoid mater

The arachnoid mater, the middle of the meningeal layers, is loosely attached to the dura mater, generally following its folds. The arachnoid is separated from the deeper pia mater by the subarachnoid space, which contains cerebrospinal fluid and is traversed by the arteries of the brain and the cranial nerves. Delicate fibres from the arachnoid mater cross the subarachnoid space and attach to the pia mater.

Pia mater

The pia mater is the innermost of the meninges and clings to the surface of the brain, dipping into its numerous grooves or sulci.

Meningeal vessels

Of the many arteries entering the cranium to supply the meninges, one of particular importance is the middle meningeal artery, which arises from the maxillary artery (p. 346) and enters through the foramen spinosum. This vessel runs laterally across the floor of the middle cranial fossa, grooving the bone, and divides on the squamous part of the temporal bone into frontal (anterior) and parietal (posterior) branches (Fig. 7.79). These branches arch superiorly on the inner surface of the lateral part of the skull and supply the meninges lining most of the vault. Meningeal veins follow the arteries and communicate with the dural venous sinuses and with veins lying outside the skull.

Bleeding from veins or arteries between the meningeal layers can raise intracranial pressure. An extradural (epidural) haematoma results from extravasation between the dura and the skull. A subdural haematoma is produced by bleeding between the dura and arachnoid layers, where normally no space exists. Blood leaking from the vessels that cross the subarachnoid space will give rise to a subarachnoid haemorrhage, the blood intermingling with cerebrospinal fluid.

Arterial supply to the brain

The brain receives arterial blood from the vertebral and internal carotid arteries (Fig. 7.80). The vertebral arteries (p. 330) enter the posterior cranial fossa through the foramen magnum. Passing upwards and forwards they unite in the midline on the clivus to form the basilar artery. Branches to the brainstem and cerebellum arise from the vertebral and basilar arteries before the latter divides at the upper border of the pons to form the left and right posterior cerebral arteries. Before supplying the posterior part of the cerebral hemisphere, each of these vessels gives rise to a



Fig. 7.79 Interior of posterior cranial fossa after removal of tentorium cerebelli and cerebellum. The venous sinuses have been further opened.

posterior communicating artery, which passes forwards to form part of the cerebral arterial circle (circle of Willis) by anastomosing with the internal carotid artery.

The internal carotid artery traverses the carotid canal (Fig. 7.82) to enter the middle cranial fossa, emerging from the upper part of the foramen lacerum. The artery turns anteriorly to enter the cavernous sinus, then continues superiorly to leave the sinus through its roof. Here, near the anterior clinoid process, the ophthalmic artery arises and accompanies the optic nerve through the optic canal into the orbit. The internal carotid artery terminates as the anterior and middle cerebral arteries. The middle cerebral artery supplies the lateral portion of the cerebral hemisphere,


Optic nerves
Ophthalmic artery
Internal carotid artery
Anterior communicating artery
Pituitary stalk
Basilar artery
Spinal cord
A
L
R
P
Anterior cerebral artery
Middle cerebral artery
Posterior communicating artery
Position of cavernous sinus
Right posterior cerebral artery
Position of superior petrosal sinus
Vertebral arteries

Fig. 7.80 Arterial circle, exposed by complete removal of the brain. The basilar and vertebral arteries are asymmetrical in this specimen.


A
L
R
P
Internal carotid artery
Oculometer (III) nerve
Trigeminal (V) nerve
Abducens (VI) nerve
Facial (VII) and vestibulo-cochlear (VIII) nerves
Glosso-pharyngeal (IX) vagus (X) and accessory (XI) nerves
Optic chiasma
Ophthalmic (V_1) and maxillary (V_2) divisions
Left posterior cerebral artery
Mandibular (V_3) division
Trigeminal ganglion
Motor root
Trochlear (IV) nerve
Hypoglossal (XII) nerve

Fig. 7.81 Cranial nerves revealed by removal of most of the brain. The dura over the right trigeminal ganglion has been excised.

while the anterior cerebral artery ascends between the frontal lobes to supply the medial surface of the hemisphere.

The cerebral arterial circle is formed between the branches of the internal carotid and vertebral arteries (Fig. 7.80). The two anterior cerebral arteries are joined by the anterior communicating artery. On each side, an anastomosis, via the posterior communicating artery, between the posterior cerebral branch of the basilar artery and the internal carotid artery completes the cerebral arterial circle. Aneurisms of the cerebral arterial circle are subject to rupture and subsequent subarachnoid haemorrhage.

Cranial nerves

The 12 pairs of cranial nerves enter or leave the skull through various foramina (Figs 7.79 & 7.81). The olfactory (I) nerves emerge from the nasal cavity as a number of short branches, which traverse the cribriform plates and terminate in the olfactory bulbs.

The optic (II) nerve leaves the orbit via the optic canal and joins the optic chiasma immediately anterior to the pituitary stalk. From the chiasma the optic tracts pass backwards to enter the brain.

Three cranial nerves enter the orbit through the superior orbital fissure. To reach the fissure the oculomotor (III) and trochlear (IV) nerves run forwards in the lateral wall of the cavernous sinus, while the abducens (VI) nerve passes through the cavity of the sinus. Infection from the face can spread through veins to the cavernous sinus, which may thrombose, causing damage to the abducens nerve and double vision.

The ganglion of the sensory part of the trigeminal (V) nerve lies covered in dura in a small depression on the apex of the petrous part of the temporal bone. The three divisions of the nerve converge on the anterior surface of the ganglion. From the orbit the branches of the ophthalmic (V_1) division traverse the superior orbital fissure, coalesce and continues backwards, embedded in the lateral wall of the cavernous sinus, to reach the ganglion. The maxillary (V_2) division leaves the pterygopalatine fossa via the foramen rotundum and passes backwards along the lower edge of the sinus to the ganglion. The sensory part of the mandibular (V_3) division, accompanied by the motor root of the trigeminal nerve, ascends from the infratemporal fossa through the foramen ovale. The motor root passes beneath and not through the ganglion to traverse the foramen ovale.

The facial (VII) nerve enters, and the vestibulocochlear (VIII) nerve emerges from, the internal acoustic meatus in the petrous part of the temporal bone.

Three nerves leave via the jugular foramen to enter the carotid sheath, namely the glossopharyngeal (IX), vagus (X) and accessory (XI) nerves.

Finally, the hypoglossal (XII) nerve traverses the hypoglossal canal.



Fig. 7.82 Inferior view of the base of the skull showing the principal foramina.

Orbit

The orbit is a pyramidal cavity, the apex of which is directed posteriorly and base anteriorly (Fig. 7.83). Its bony walls separate it from the anterior cranial fossa above, the ethmoidal air cells and nasal cavity medially, the maxillary air sinus inferiorly and the lateral surface of the face and temporal fossa laterally (Fig. 7.84). Anteriorly, the orbit presents a roughly rectangular aperture which is closed by the eyelids. Within the orbit are the eyeball, the extraocular muscles, cranial nerves II, III, IV, V (ophthalmic and maxillary divisions) and VI, and blood vessels, lymphatics and fat.

Bony walls

The roof of the orbit (Fig. 7.85) comprises the frontal bone, which anteriorly contains the frontal air sinuses. The lateral wall is formed anteriorly by the zygomatic bone and posteriorly by the greater wing of the sphenoid bone. The floor consists of the maxilla anteriorly and the greater wing of the sphenoid




S
R
L
I
Frontal bone
Orbit
Zygomatic bone
Inferior concha
Maxilla
Nasal bone
Nasal septum
Mastoid process
Styloid process

Fig. 7.83 Anterior view of the skull without the mandible.




Frontal lobe
Superior oblique
Medial rectus
Lateral rectus
Inferior rectus
Nasal cavity
S
L
R
I
Levator palpebrae superioris
Superior rectus
Lacrimal gland
Ethmoid air cells
Lens
Maxillary air sinus

Fig. 7.84 Coronal section showing the extraocular muscles and the relations of the orbits. The section through the right orbit passes more anteriorly than on the left. Posterior aspect. (Compare Figs 7.47 & 7.92.)

posteriorly. From anterior to posterior the medial wall comprises the maxilla, lacrimal, ethmoid and sphenoid bones. The medial walls of the two orbits lie parallel to the median plane while their lateral walls are directed forwards and laterally so that they lie at right angles to one another.

Several foramina and the superior and inferior orbital fissures (Fig. 7.85) allow various structures to enter and leave the orbit. On the medial wall, close to the orbital margin, is a depression called the lacrimal groove, bounded by the maxilla and the lacrimal bone. The nasolacrimal canal descends from this groove and opens into the inferior meatus of the nasal cavity. Anterior and posterior ethmoidal foramina perforate the medial wall and allow communication with the lateral wall of the nasal cavity. At the apex of the orbit are the optic canal and the superior and inferior orbital fissures, through which the orbit is in continuity with the middle cranial and pterygopalatine fossae.

Fascial layers

Movement of the eyeball is facilitated by its fascial sheath, the vagina bulbi (fascia bulbi) (Fig. 7.90), which invests it but does not adhere to the sclera and is incomplete anteriorly. The vagina bulbi is attached to the eyeball around the margin of the cornea. Thickenings of the inferior part of the fascia (the suspensory ligament) extend laterally and medially to attach to the orbital walls (check ligaments). The fascia is pierced by the six muscles that move the eyeball. Anteriorly the orbit is closed by the orbital septum, which forms the fibrous layer of the eyelids.

Eyelids, conjunctiva and lacrimal apparatus

Within each eyelid, the orbital septum is thickened to form a tarsal plate (Figs 7.86 & 7.87) and is perforated between the eyelids by the palpebral fissure. Anterior to the septum lies orbicularis oculi and skin. Levator palpebrae superioris is attached to the upper edge of the superior tarsal plate while a few fibres of inferior rectus are attached to the lower edge of the inferior tarsal plate. Posteriorly each plate has tarsal (meibomian) glands and is covered by conjunctiva. The conjunctival epithelium is reflected onto the surface of the eyeball, where it blends with the margin of the cornea. Each eyelid carries a double row of eyelashes together with associated sebaceous glands (which when inflamed form a stye). The lashes on each eyelid extend medially as far as a small elevation containing a central aperture, the lacrimal punctum, leading into the lacrimal canaliculus. The canaliculi carry tear fluid to the lacrimal sac in the lacrimal groove, and the sac in turn drains via the nasolacrimal duct, in the nasolacrimal canal, into the nasal cavity beneath the inferior concha (Fig. 7.51).

The lacrimal gland (Figs 7.86, 7.87 & 7.89) lies in the superolateral angle of the orbit behind the upper eyelid and is deeply indented by the lateral border of the tendon of levator palpebrae superioris. Small ducts open from the deep surface of the gland into the conjunctival sac. Fluid produced by the gland passes medially towards the lacrimal puncta across the surface of the cornea, assisted by blinking of the eyelid. Reflex blinking is initiated if the cornea is touched or becomes dry. Evaporation of the fluid is retarded by the oily secretion of the tarsal glands.

Extraocular muscles

Within the orbit most muscles comprise only striated fibres, but those that move the eyelids also contain smooth fibres under sympathetic control. Damage to this supply results in a drooping upper eyelid, ptosis.

The extraocular muscles are the four recti, the two obliques and one muscle which attaches to the upper eyelids, levator palpebrae superioris (Figs 7.86–7.88). This is the uppermost muscle in the orbit, and from its attachment to the lesser wing of the sphenoid it passes forwards to form a wide tendon, which enters the upper eyelid and blends with the superior tarsal plate.

The medial, lateral, superior and inferior recti (Figs 7.87, 7.88, 7.90 & 7.91) attach posteriorly to the common tendinous ring that surrounds the optic canal and part of the superior orbital fissure. Passing forwards, these four muscles attach to the eyeball immediately behind the corneoscleral junction in positions corresponding to their names. Collectively, they form a cone with its apex at



Fig. 7.85 Bony walls, fissures and foramina of the left orbit.

the optic canal and its base around the equator of the eyeball. Nerves and vessels entering the orbit run their course either within or outside this cone of muscle.

Superior oblique (Fig. 7.89) has a posterior attachment to the lesser wing of the sphenoid adjacent to the common tendinous ring. The muscle passes anteriorly along the junction between the medial wall and the roof of the orbit and forms a tendon which traverses a loop of fibrous tissue, the trochlea, which lies at the superomedial angle of the orbital margin and allows the tendon of superior oblique to turn backwards across the upper surface of the eyeball. The tendon lies beneath superior rectus and attaches to the superolateral part of the eyeball behind the equator.

Inferior oblique (Figs 7.86 & 7.87), lying entirely in the anterior part of the orbit, attaches to the floor of the orbit just lateral to the


Supraorbital nerve
Supratrochlear nerve
Superior oblique
Levator palpebrae superioris
Trochlea
Lacrimal gland
Infratrochlear nerve
Superior and inferior tarsal plates
Inferior oblique
Infraorbital nerve
S
m
la
I

Fig. 7.86 Contents of the left orbit, revealed by removal of its lateral wall and floor and parts of the eyelids. The supraorbital nerve lies in a canal in the frontal bone.


Supraorbital nerve
Superior and inferior tarsal plates
Lacrimal nerve
Lacrimal gland
Lateral rectus
Inferior rectus
Inferior oblique
Infraorbital nerve
S
A
P
I

Fig. 7.87 Lateral view of specimen in Fig. 7.86.


A
la
m
P
Supratrochlear nerve
Supraorbital nerve
Trochlea
Superior oblique
Levator palpebrae superioris
Frontal nerve
Superior rectus
Lacrimal nerve
Trochlear (IV) nerve

Fig. 7.88 Contents of the orbit seen from above after removal of the orbital plate of the frontal bone.

nasolacrimal canal. The muscle passes posterolaterally below the inferior rectus to attach to the inferolateral part of the eyeball behind the equator.

Three cranial nerves supply these muscles. The abducens (VI) nerve (Figs 7.90 & 7.91) innervates lateral rectus, while the trochlear (IV) nerve (Fig. 7.88) supplies superior oblique. All the remaining muscles receive motor branches from the oculomotor (III) nerve (Figs 7.89 & 7.91).

Movements of the eyeball and eyelid

In defining the actions of individual extraocular muscles, it is assumed that the eyeball is positioned so that the gaze is directed forwards into the distance. Within its fascial sheath, the eyeball is rotated by the extraocular muscles, which displace the gaze upwards (elevation), downwards (depression), medially (adduction) and laterally (abduction). Rotation about an anteroposterior axis (torsion) may also occur. Collectively, the extraocular muscles also contribute to the stability of the eyeball, the recti tending to pull the globe backwards and the obliques tending to pull it forwards.

The only actions of the medial and lateral recti are adduction and abduction, respectively. Superior rectus elevates and adducts while inferior rectus depresses and adducts. Both oblique muscles produce abduction, the inferior oblique elevating the gaze and the superior oblique depressing it. Eye movements in general involve the coordinated contraction and relaxation of several individual muscles, and elevation and depression are accompanied by movement of the eyelids. Levator palpebrae superioris raises the upper eyelid (opposed by the orbicularis oculi), while inferior rectus depresses the lower eyelid.

Nerves

Several nerves reach the orbit from the middle cranial and pterygopalatine fossae. The optic (II) nerve (Fig. 7.89), which conveys visual sensation, traverses the optic canal with the ophthalmic artery. Enveloped by meninges and cerebrospinal fluid, the nerve passes forwards and laterally within the cone of rectus muscles and enters the eyeball just medial to its posterior pole. Increased intracranial pressure is transmitted through the cerebrospinal fluid to the eye, giving rise to the clinical sign called papilloedema. Other nerves reach the orbit through the orbital fissures.

The oculomotor (III) nerve (Figs 7.89 & 7.91) enters the cone of muscles via the superior orbital fissure. It has superior and inferior divisions, which are often formed before entering the orbit. The superior division supplies the superior rectus and levator palpebrae superioris while the inferior division gives branches to inferior rectus, inferior oblique, medial rectus and the ciliary ganglion. Sympathetic fibres to the smooth muscle in levator palpebrae superioris and inferior rectus enter the oculomotor (III) nerve in the cavernous sinus and travel with its branches to these muscles. Damage to this pathway results in Horner's syndrome, including ptosis.




A
la
m
P
Levator palpebrae superioris (cut)
Superior oblique tendon
Superior rectus (cut)
Lacrimal gland
Long ciliary nerve
Short ciliary nerves
Superior division of oculomotor (III) nerve (cut)
Superior rectus (cut)
Trochlea
Superior oblique
Ophthalmic artery
Optic (II) nerve
Posterior ethmoidal nerve
Nasociliary nerve
Trochlear (IV) nerve
Levator palpebrae superioris (cut)
Optic (II) nerve
Frontal nerve (cut)

Fig. 7.89 Structures of the orbit seen following excision of superior rectus, levator palpebrae superioris and the superior division of the oculomotor nerve along with a quantity of orbital fat.

The trochlear (IV) nerve (Fig. 7.89) enters the orbit via the superior orbital fissure, passing above the muscle cone to supply superior oblique.

The abducens (VI) nerve (Figs 7.90 & 7.91) gains the orbit via the superior orbital fissure and passes forwards on the inner surface of lateral rectus, which it supplies.

The ophthalmic (V_1) division of the trigeminal nerve divides into lacrimal, frontal and nasociliary nerves, each of which enters the orbit through the superior orbital fissure. The lacrimal nerve (Fig. 7.88) passes forwards, outside the muscle cone, along the angle between the roof and lateral wall of the orbit. It is joined by parasympathetic secretomotor fibres from the zygomatic nerve (p. 354), which are destined for the lacrimal gland. In addition, the lacrimal nerve conveys sensation from the lacrimal gland and the lateral part of the upper eyelid.

The frontal nerve (Fig. 7.88) lies on the upper surface of levator palpebrae superioris and divides into supraorbital and supratrochlear nerves. The supraorbital nerve (Figs 7.86 & 7.88) curves around the upper part of the orbital margin, occupying the supraorbital notch, and conveys sensation from the upper eyelid,


A
la
m
P
Vagina bulbi
Optic (II) nerve (cut)
Lateral rectus
Abducens (VI) nerve
Medial rectus
Inferior rectus
Ophthalmic artery (cut)
Nasociliary nerve (cut)

Fig. 7.90 Muscles of the orbit seen after removal of the upper eyelid, part of the optic nerve, and superior oblique.


Oculomotor branch to inferior oblique
Lateral rectus
Abducens (VI) nerve
Oculomotor root of ciliary ganglion
A
la
m
P
Inferior rectus
Branch to medial rectus
Branch to inferior rectus
Inferior division of oculomotor (III) nerve
Ophthalmic artery (cut)

Fig. 7.91 Inferior division of the oculomotor nerve, revealed by excision of the distal part of the ophthalmic artery and the nasociliary nerve.

forehead, scalp and frontal air sinus. The supratrochlear nerve (Figs 7.86 & 7.88) lies more medially, leaving the orbit just above the trochlea to supply sensory fibres to the medial part of the upper eyelid, forehead and scalp.

The nasociliary nerve (Fig. 7.89), lying within the muscle cone, crosses above the optic (II) nerve and continues forwards along the medial wall of the orbit to terminate below the trochlea. Its branches include one to the ciliary ganglion, two long ciliary nerves, posterior and anterior ethmoidal nerves and the infratrochlear nerve. The long ciliary nerves, which carry sympathetic vasoconstrictor fibres that join the nasociliary nerve in the cavernous sinus, pass forwards to supply vessels within the eyeball. The posterior and anterior ethmoidal nerves leave through their respective foramina, supplying ethmoidal air cells. The anterior ethmoidal nerve passes between the frontal and ethmoid bones and emerges on the upper surface of the cribriform plate. Leaving the anterior fossa, the nerve penetrates the plate to run on the inner surface of the nasal bone as the external nasal nerve and eventually reaches the tip of the nose. It conveys sensation from a strip of nasal skin close to the midline and from the nasal septum. The infratrochlear nerve supplies the medial part of the upper eyelid (Fig. 7.86).

Autonomic nerves

The ciliary ganglion lies just behind the eyeball, lateral to the optic (II) nerve. It receives sensory fibres from the nasociliary nerve, sympathetic fibres from the internal carotid plexus in the cavernous sinus and parasympathetic fibres from the oculomotor (III) nerve. Only the last synapse in the ganglion. From the anterior part of the ganglion, short ciliary nerves (Fig. 7.89) pass forwards into the eyeball, conveying general sensory fibres from the eyeball (including the cornea), parasympathetic fibres to the ciliary muscle and sphincter pupillae and sympathetic fibres to dilator pupillae.

Vasoconstrictor sympathetic fibres reach the eyeball in the long ciliary branches of the nasociliary nerve. Other intraorbital sympathetic fibres travel in the oculomotor (III) nerve to the smooth muscle component of levator palpebrae superioris and inferior rectus. Parasympathetic fibres reach the lacrimal gland via the lacrimal nerve, which communicates with the zygomatic branch of the maxillary (V_2) division of the trigeminal nerve. The cell bodies of these fibres lie in the pterygopalatine ganglion (p. 354).

Vessels

The ophthalmic artery (Figs 7.89 & 7.90), a branch of the internal carotid artery in the middle cranial fossa, enters the orbit through the optic canal inferior to the optic (II) nerve. The artery then accompanies the nasociliary nerve, passing above the optic nerve and continuing forwards along the medial wall of the orbit. Its first branch, the central retinal artery, enters the optic nerve and passes into the eyeball to supply the retina. Occlusion of this artery results in blindness. Other branches of the ophthalmic artery accompany those of the ophthalmic (V_1) division of the trigeminal nerve. In addition, there are posterior and anterior ciliary branches to the eyeball and branches to the extraocular muscles.

Venous blood from the eyeball and adjacent structures drains into inferior and superior ophthalmic veins. The superior ophthalmic vein terminates posteriorly in the cavernous venous sinus while the inferior vein passes through the inferior orbital fissure into the pterygoid venous plexus in the pterygopalatine fossa. Both superior and inferior ophthalmic veins communicate with veins on the face.

Exam Skills

Each of the incomplete statements below is followed by five suggested answers or completions. Decide which are true and which are false. The answers are supplied on p. 417.

1. The internal carotid artery:

a) arises from the brachiocephalic artery on the right.
b) traverses the foramina transversaria of cervical vertebrae 1–6.
c) has a branch entering the orbit.
d) forms the basilar artery.
e) gives rise to the anterior cerebral artery.

2. In the larynx:

a) sensation from the vestibular fold travels in the superior laryngeal nerve.
b) contraction of cricothyroid lowers pitch.
c) the cricoid cartilage forms a complete ring.
d) interarytenoid muscle adducts the vocal folds.
e) the vocal fold is covered with respiratory epithelium.

3. The internal jugular vein:

a) is a continuation of the sigmoid sinus.
b) drains into the brachiocephalic vein.
c) receives blood from the lingual vein.
d) communicates with the retromandibular vein.
e) has the ansa cervicalis on its anterolateral surface.

4. The head of the mandible:

a) is moved medially by lateral and medial pterygoid acting together.
b) is separated from the temporal bone by an intra-articular disc.
c) is moved posteriorly by the lateral pterygoid muscle.
d) is moved posteriorly by temporalis.
e) most often dislocates backwards.

5. The intracranial dura mater:

a) is easily separated into endosteal and meningeal layers.
b) forms the tentorium cerebelli.
c) contains the sigmoid sinus in the free edge of the falx cerebri.
d) is separated from the arachnoid mater by cerebrospinal fluid.
e) forms the diaphragma sellae.

6. The thyroid gland:

a) has an isthmus at the level of the second and third tracheal rings.
b) receives blood from a branch of the subclavian artery.
c) is enclosed in prevertebral fascia.
d) is closely related to both recurrent laryngeal nerves.
e) rises on swallowing.

7. The hypoglossal nerve:

a) leaves the skull through the jugular foramen.
b) conveys touch sensation from the anterior two-thirds of the tongue.
c) innervates the genioglossus muscle.
d) carries C1 fibres for the ansa cervicalis.
e) when damaged results in the protruded tongue deviating to the damaged side.

8. Transection of the facial nerve in the internal acoustic meatus gives rise to:

a) paralysis of buccinator.
b) loss of taste in the anterior two-thirds of the tongue.
c) paralysis of masseter.
d) loss of secretion by the parotid gland.
e) paralysis of stapedius.

9. The maxillary air sinus:

a) extends below the level of the hard palate.
b) has a sensory supply from the ophthalmic division of the trigeminal nerve.
c) is indented by the root of the canine tooth.
d) has a roof formed by the floor of the orbit.
e) opens into the inferior meatus.

10. The maxillary division of the trigeminal nerve:

a) is related to the cavernous venous sinus.
b) conveys sensation from the lower eyelid.
c) passes through the foramen rotundum.
d) conveys sensation from part of the nasal septum.
e) conveys sensation from the hard palate.

11. The vagus nerve:

a) passes through the jugular foramen.
b) is contained in the carotid sheath.
c) conveys touch sensation from the laryngopharynx.
d) is motor to the stylopharyngeus muscle.
e) carries fibres destined for the submandibular gland.

12. In the neck:

a) the phrenic nerve crosses posterior to the subclavian artery.
b) the left vagus nerve gives rise to the recurrent laryngeal nerve.
c) the scalenus anterior muscle lies posterior to the subclavian vein.
d) the thoracic duct drains into the junction of the subclavian and internal jugular veins on the left.
e) the sternohyoid muscle is supplied by the ansa cervicalis.

13. The glossopharyngeal nerve:

a) is motor to the pharyngeal constrictor muscles.
b) traverses the parotid gland.
c) conveys touch sensation from the posterior third of the tongue.
d) is motor to stylopharyngeus.
e) carries sensory fibres from the larynx.

14. Concerning the nasal cavity and its walls:

a) the nasolacrimal duct opens in the middle meatus.
b) the inferior concha is part of the ethmoid bone.
c) the septum is supplied by the mandibular division of the trigeminal nerve.
d) the vomer forms the anterior part of the septum.
e) the sphenoidal air sinus opens into the middle meatus.

15. Concerning the cranial cavity:

a) the superior sagittal sinus drains into the transverse sinus.
b) bleeding from the middle meningeal artery gives rise to extradural/epidural haematoma.
c) the trigeminal ganglion is closely related to the apex of the petrous temporal bone.
d) the internal carotid artery gives rise to the posterior cerebral artery.
e) the temporal lobe lies in the anterior cranial fossa.

16. Concerning the orbit:

a) lateral rectus is supplied by the fourth cranial nerve.
b) superior oblique produces adduction of the eye.
c) the oculomotor nerve carries parasympathetic fibres to sphincter pupillae.
d) secretomotor fibres for the lacrimal gland travel in the nasociliary nerve.
e) the ophthalmic artery enters through the superior orbital fissure.

Clinical Case Skills

The answers are supplied on p. 420.

Case Study 1

A 50-year-old woman presented to her doctor with a pain-free swelling in the right side of her face. Examination indicated that this was a benign parotid tumour, and the woman had a partial parotidectomy at a later date. On recovering from the anaesthetic, the patient was observed to dribble from the right side of her mouth and to have difficulty with closing her right eye. Over a period of a few weeks both these signs disappeared, but the patient now noticed that when she ate, she experienced sweating from the skin overlying the area from which the tumour was removed.

Questions:

1. How would you test for normal function in the parotid gland?
2. Why did the patient experience problems with her mouth and eye after surgery?
3. Why did the initial postsurgery symptoms recover?
4. Explain why the patient experienced sweating with eating.

Case Study 2

The morning after a particularly good party, a 20-year-old student awoke and yawned widely. He heard a click and found that he could not close his mouth. He also experienced sharp, severe pain on both sides of his face just in front of the ear. The student was now unable to speak clearly or eat.

Questions:

1. What had happened?
2. What anatomical features are responsible for the condition?
3. On anatomical grounds, what is the treatment?

Case Study 3

A 35-year-old woman visited her doctor with weight loss, anxiety and tremor. The doctor observed that she had exophthalmos (protruding eyes) and correctly made the diagnosis of thyrotoxicosis (overactive thyroid gland). In order to examine the gland, he stood behind the sitting patient and felt her neck just below the laryngeal prominence.

Questions:

1. What would the doctor ask the patient to do in order to make his examination of the gland complete?
   The prescribed treatment in this patient was partial thyroidectomy. Following surgery the patient was noticed to have a husky voice.
2. What is the likely cause of the change in voice?
3. How may the surgeon have avoided the problem?
4. What other nearby structures are particularly liable to damage in this operation?

Case Study 4

A general practitioner referred a 14-year-old boy to hospital for urgent admission. The boy had suffered acne for some months and in the previous few days had experienced an exacerbation of the condition. He admitted to squeezing pustules on his left cheek and 36 hours later noticed double vision on looking to the left. In the previous few hours he had pain in the middle third of his face on the left and then complained of double vision on looking in most directions.

Questions:

1. What was the diagnosis?
2. Why did the boy experience double vision on looking to the left?
3. What is the anatomical explanation for the progression of events?
4. If allowed to progress untreated, what would be the likely next problem?

Observation Skills

Identify the structures indicated. The answers are supplied at the foot of the page.



Fig. 7.92 Coronal MR image showing the orbits and nasal cavities. (Compare Figs 7.47 & 7.98.)



Fig. 7.93 Transverse MR image showing the orbits. (Compare Fig. 7.100.)

Answers:

Fig. 7.92 1 = inferior concha (turbinate); 2 = tongue; 3 = hard palate; 4 = longitudinal cerebral fissure containing falx cerebri; 5 = superior rectus; 6 = superior oblique; 7 = cribriform plate; 8 = ethmoid air cells; 9 = optic nerve; 10 = lateral rectus; 11 = medial rectus; 12 = inferior rectus; 13 = nasal septum; 14 = middle concha (turbinate); 15 = maxillary sinus (antrum); 16 = nasal cavity.

Fig. 7.93 1 = retrobulbar fat; 2 = lens; 3 = medial rectus; 4 = ethmoid air cells; 5 = optic nerve; 6 = lateral rectus; 7 = cerebellum; 8 = posterior cerebellar notch (containing falx cerebelli).



Fig. 7.94 Transverse CT image at the level of the second cervical vertebra. (Compare Figs 7.25 & 7.102.)



Fig. 7.95 Transverse CT image at the level of the fifth cervical vertebra. (Compare Fig. 7.5.)

Answers:

Fig. 7.94 1 = muscles of tongue; 2 = mandible; 3 = masseter; 4 = medial pterygoid muscle; 5 = oropharynx; 6 = styloid process; 7 = internal carotid artery; 8 = parotid gland; 9 = internal jugular vein; 10 = odontoid process (dens) of axis.

Fig. 7.95 1 = hyoid bone; 2 = submandibular salivary gland; 3 = laryngopharynx; 4 = external carotid artery; 5 = internal carotid artery; 6 = internal jugular vein; 7 = vertebral artery; 8 = sternocleidomastoid; 9 = bifid spinous process; 10 = trapezius.



Fig. 7.96 Transverse CT image at the level of the sixth cervical vertebra. (Compare Fig. 7.103.)



Fig. 7.97 Sagittal MR image of the head near the midline.

Answers:

Fig. 7.96 1 = foramen transversarium; 2 = larynx just above trachea; 3 = cricoid cartilage; 4 = thyroid gland; 5 = sternocleidomastoid; 6 = common carotid artery; 7 = internal jugular vein; 8 = anterior tubercle; 9 = vertebral artery; 10 = trapezius.

Fig. 7.97 1 = oral cavity; 2 = muscles of tongue; 3 = epiglottis; 4 = laryngopharynx; 5 = frontal air sinus; 6 = corpus callosum; 7 = pituitary gland; 8 = tentorium cerebelli; 9 = pons; 10 = sphenoid air sinus; 11 = cerebellum; 12 = nasopharynx; 13 = medulla oblongata; 14 = anterior arch of atlas; 15 = odontoid process (dens); 16 = posterior arch of atlas; 17 = posterior lamina of axis; 18 = spinal cord.



Fig. 7.98 Coronal section showing the orbits and nasal cavities. Anterior aspect. (Compare Fig. 7.92.)



Fig. 7.99 Coronal section at the choanae showing the soft palate. Anterior aspect.

Answers:

Fig. 7.98 1 = frontal sinus; 2 = ethmoid air cells; 3 = nasal septum; 4 = maxillary sinus; 5 = inferior concha and meatus; 6 = oral cavity (distended); 7 = tongue; 8 = mandible; 9 = buccinator; 10 = hard palate; 11 = middle concha; 12 = eyeball; 13 = frontal lobe.

Fig. 7.99 1 = superior sagittal sinus; 2 = falx cerebri; 3 = zygomatic arch; 4 = nasopharynx; 5 = soft palate; 6 = oral cavity (distended); 7 = tongue; 8 = mylohyoid; 9 = mandible; 10 = masseter; 11 = nasal septum; 12 = temporal lobe; 13 = temporalis; 14 = apex of orbit; 15 = cerebral hemisphere.



Fig. 7.100 Transverse section showing the orbits and posterior cranial fossa. Inferior aspect.



Fig. 7.101 Transverse section showing the maxillary sinuses and nasal cavities. Inferior aspect.

Answers:

Fig. 7.100 1 = nasal septum; 2 = eyeball; 3 = temporalis; 4 = temporal lobe; 5 = carotid canal; 6 = inner ear; 7 = pons; 8 = fourth ventricle; 9 = falx cerebelli; 10 = cerebellum; 11 = sigmoid sinus; 12 = pinna; 13 = basilar artery; 14 = sphenoid sinus; 15 = ethmoid air cells; 16 = lens.

Fig. 7.101 1 = nasal cavity; 2 = ethmoid air cells; 3 = maxillary sinus; 4 = nasopharynx; 5 = mandible; 6 = internal carotid artery; 7 = parotid gland; 8 = mastoid process; 9 = pinna; 10 = sternocleidomastoid; 11 = trapezius; 12 = cervical spinal cord; 13 = internal jugular vein; 14 = lateral pterygoid; 15 = masseter; 16 = temporalis.



Fig. 7.102 Transverse section at the level of the second cervical vertebra. Inferior aspect.



Fig. 7.103 Transverse section at the level of the sixth cervical vertebra. Inferior aspect. (Compare Fig. 7.95.)

Answers:

Fig. 7.102 1 = hard palate; 2 = soft palate; 3 = oropharynx; 4 = masseter; 5 = medial pterygoid; 6 = internal carotid artery; 7 = cervical spinal cord; 8 = dura mater; 9 = vertebral artery; 10 = sternocleidomastoid; 11 = parotid gland; 12 = mandible; 13 = buccinator; 14 = orbicularis oris in lower lip.

Fig. 7.103 1 = internal jugular vein; 2 = common carotid artery; 3 = thyroid gland; 4 = strap muscle; 5 = laryngopharynx; 6 = cricoid cartilage; 7 = sternocleidomastoid; 8 = clavicle; 9 = subclavius; 10 = scalenus medius; 11 = scalenus anterior; 12 = spinal cord; 13 = vertebral artery; 14 = trapezius.

Chapter 8

BACK

Introduction 394
Vertebrae and Joints 398
  Cervical vertebrae 398
  Thoracic vertebrae 401
  Lumbar vertebrae 402
  Sacral and coccygeal vertebrae 402
  Facet joints 404
  Intervertebral discs 404
  Intervertebral ligaments 405
Muscles 407
  Splenius muscles 407
  Erector spinae 407
  Transversospinalis 408
  Actions 408
Meninges 410
  Dura mater 410
  Arachnoid mater 410
  Pia mater 411
Spinal Cord 411
  Surface features 411
  Spinal nerve roots 411
  Blood supply 412
Exam Skills 413
Clinical Case Skills 414
Observation Skills 415

Introduction

The back consists of the vertebrae, the intervertebral joints and ligaments, and the muscles that clothe their posterior and lateral aspects (Fig. 8.1). The vertebral column encloses the spinal cord and its meninges.

The vertebral column comprises vertebrae, which are classified regionally as: cervical (7); thoracic (12); lumbar (5); sacral (5 vertebrae fused to form the sacrum); and coccygeal (3–5) (Fig. 8.5). Typically, a vertebra consists of a body, two pedicles, two laminae, two transverse processes and a single spinous process (Fig. 8.6). The body and vertebral arch, formed by the pedicles and laminae, surround the vertebral canal which encloses the meninges and spinal cord (Fig. 8.8). Pairs of superior and inferior articular processes form synovial joints with corresponding processes on adjacent vertebrae. The vertebral bodies are united by fibrocartilaginous discs (Fig. 8.5) and anterior and posterior longitudinal ligaments (p. 404). Each vertebra usually possesses features characteristic of its region.

The vertebral column is curved anteroposteriorly. In the adult, the thoracic and sacral/coccygeal vertebrae form curves that are concave anteriorly (primary or kyphotic curves), whereas in the cervical and lumbar regions the curves are concave posteriorly (secondary or lordotic curves) (Fig. 8.5). Usually, a healthy vertebral column has no lateral curves. Scoliosis, which is an abnormal lateral curve of the column that often includes some rotation, may be associated with abnormal development of a vertebra, vertebral fracture or abnormal muscle activity.

The movements between adjacent vertebrae are relatively limited, although summation enables the vertebral column as a whole to achieve a wide range of motion (Figs 8.2–8.4). Both flexion and extension occur throughout the length of the vertebral column, particularly in the cervical region. Lateral flexion is greatest in the cervical and lumbar regions and rotation occurs mainly in the upper thoracic region.

The muscles of the back (Fig. 8.7) may be classified into superficial, intermediate and deep groups. The superficial muscles (trapezius, latissimus dorsi, levator scapulae, rhomboid major and minor) act mainly on the shoulder girdle (pp 100, 102).


S
L
R
I
Occipital bone
Seventh cervical vertebra
Clavicle
Scapula
First thoracic vertebra
Humerus
Twelfth rib
Fourth lumbar vertebra
Hip bone
Sacrum
Coccyx
🟩 Extent of cutaneous innervation by posterior rami of spinal nerves
🟥 Extent of deep back muscles

Fig. 8.1 Posterior aspect of the back.


S
P
A
I
Extension
Flexion

Fig. 8.2 Flexion and extension of the vertebral column from the anatomical position.


A
L
R
P
Rotation to
the right

Fig. 8.4 View from above of a seated person showing rotation of the vertebral column to the right. The head rotates with respect to the shoulders, and the shoulders rotate with respect to the pelvis.


S
A
P
I
Pedicle
Body
Vertebral
foramen
Intervertebral
notches
Transverse
process
Articular
processes
Lamina
Spinous
process

Fig. 8.6 Oblique view of a lumbar vertebra to show its processes, vertebral foramen and intervertebral notches.


S
L
R
I
Lateral flexion
to the right

Fig. 8.3 Lateral flexion of the vertebral column to the right from the anatomical position.


S
A
P
I
Atlas
Axis
Intervertebral
discs
Intervertebral
foramina
Facet of
sacroiliac
joint
Sacrum
Coccyx
▭ Cervical vertebrae (C1–C7)
▭ Thoracic vertebrae (T1–T12)
▭ Lumbar vertebrae (L1–L5)

Fig. 8.5 Lateral view of the vertebral column.

The intermediate group (the two serratus posterior muscles) are respiratory.

The deep muscles (p. 406), including splenius, erector spinae and transversospinalis, interconnect the base of the skull, the sacrum and the intervening vertebrae. Erector spinae is subdivided into named components, including iliocostalis, longissimus and spinalis, which usually span several vertebrae. Deep to erector spinae is the transversospinalis, whose components usually run obliquely, attaching adjacent vertebrae (Fig. 8.7). Transversospinalis comprises semispinalis, multifidus and rotatores. The deep muscles are all supplied by the posterior rami of the spinal nerves (Fig. 8.8). Cutaneous branches of the posterior rami penetrate muscles to reach the skin (Figs 8.1 & 8.9).

Within the vertebral canal, three meningeal layers, the dura mater, the arachnoid mater and the pia mater, invest the spinal cord (Fig. 8.34). The dura mater is the outer layer and attaches to the foramen magnum where it is continuous with the cranial dura. Inferiorly, the dura attaches to the second sacral vertebra. The arachnoid mater is applied to the inner aspect of the dura. The pia is a vascular layer which closely invests the spinal cord and spinal nerve roots. Between the arachnoid and the pia is the subarachnoid space containing cerebrospinal fluid.

The spinal cord, within its meningeal coverings, is continuous above with the medulla oblongata. In the adult, it extends inferiorly to the level of the second lumbar vertebra. The cord gives rise to paired spinal nerves: 8 cervical; 12 thoracic; 5 lumbar; 5 sacral; and 3 coccygeal. The leash of lumbar, sacral and coccygeal nerve roots descends beyond the lower end of the cord and is known as the cauda equina (Fig. 8.35). The spinal nerves emerge from the vertebral canal through the intervertebral foramina (Fig. 8.10), and divide into posterior and anterior rami (Fig. 8.8; Table 8.1). The posterior rami supply the deep muscles of the back and the overlying skin (Figs 8.1 & 1.36). Vertebrae, weakened by bone disease or growth of metastatic tumours, may fracture causing pain and injury to the nerve roots or to the spinal cord itself.

The vertebral arch develops from right and left parts, which normally fuse across the midline posteriorly. Failure of fusion, most commonly in the lumbar region, results in spina bifida. Often the condition affects only the bones (spina bifida occulta) but more severe forms may leave the spinal meninges exposed or involve maldevelopment of the spinal cord, associated with weakness or paralysis of muscles in the lower limbs.

The vertebral column receives arterial blood from anastomosing branches of many arteries including vertebral, posterior intercostal, lumbar and lateral sacral arteries. Venous blood drains by corresponding veins. The venous plexus in the extradural space (the internal vertebral plexus) and that within the back muscles (the external venous vertebral plexus) communicate via veins in the intervertebral foramina. The plexuses and the veins into which they drain possess no valves. These channels provide routes for blood to return to the heart, bypassing blockages of the inferior vena cava. The plexuses also allow diseases of pelvic organs, for example tumours of the prostate gland, to spread to the vertebrae.



Fig. 8.7 A thoracic vertebra with the main groups of back muscles. Inferior aspect.



Fig. 8.8 A cervical vertebra with the spinal cord and a pair of spinal nerves. Inferior aspect.


Fascia overlying infra-spinatus
Rhomboid major
Trapezius
Latissimus dorsi
Cutaneous branches of posterior rami
Thoraco-lumbar fascia
S
m
la
I

Fig. 8.9 Cutaneous branches of the posterior rami supply skin on the dorsum of the trunk. The nerves shown pierce trapezius and latissimus dorsi.


S
P
A
I
Superior articular process
Superior vertebral notch
Costal facets
Transverse process with costal facet
Vertebral body
Intervertebral disc
Pedicle
Inferior vertebral notch
Spinous process
Inferior articular process

Fig. 8.10 Intervertebral foramen (pink) between two typical thoracic vertebrae. The facet joints between the superior and inferior articular processes of adjacent vertebrae lie posterior to the segmental nerve in the foramen.

Table 8.1 Summary of the main areas of distribution of the anterior rami of spinal nerves

Spinal nerves	Principal areas of distribution
Cervical 1–4	Via the cervical plexus (p. 326) to the neck, and via the phrenic nerves (p. 60) to the diaphragm.
Cervical 5–8 and thoracic 1	Via the brachial plexus (p. 80) to the upper limbs.
Thoracic 1–11	Via the intercostal nerves (p. 35) to the thoracic and abdominal walls.
Thoracic 12	Via the subcostal nerves (p. 201) to the lower abdominal wall.
Lumbar 1	Via ilioinguinal and iliohypogastric nerves (p. 145) to the lower abdominal wall.
Lumbar 1–4	Via the lumbar plexus (p. 203) to the lower limbs.
Lumbar 4 and 5	Via the lumbosacral trunk (p. 203) to the sacral plexus.
Sacral 1–4	Via the sacral plexus (p. 237) to the pelvis and lower limbs.
Sacral 5 and coccygeal 1	Via the coccygeal plexus (p. 237) to skin over the coccyx.

Vertebrae and Joints

Cervical vertebrae

The seven cervical vertebrae are relatively small and enclose a wide vertebral canal with adequate space for the cervical part of the spinal cord. Each transverse process is perforated by a foramen transversarium transmitting the vertebral vessels. The spinous processes all give attachment to a strong midline elastic ligament, the ligamentum nuchae.

Four of the cervical vertebrae (numbers 3–6) have a typical appearance whereas the first, second and seventh are modified. The typical vertebrae (Fig. 8.11) possess short bifid spines and their transverse processes have anterior and posterior tubercles. Often the upper and lower surfaces of the vertebral bodies are not flat but curve upwards at their lateral edges. The facets on the superior articular processes face obliquely backwards and upwards and therefore rotation and lateral flexion always occur together.

The first cervical vertebra, the atlas (Fig. 8.12), has anterior and posterior arches, relatively large transverse processes and two lateral masses. The atlas has no body and its spinous process is represented by a tubercle. On the superior surface of each lateral mass is a concave facet, which articulates with the convex occipital condyle of the skull. The atlanto-occipital joints permit flexion and extension (nodding movements).

The second cervical vertebra, the axis (Fig. 8.13), possesses some of the features of a typical cervical vertebra but it has a unique vertical projection, the dens (odontoid process). This projects superiorly from the upper surface of its body and represents the body of the atlas. The dens articulates by a synovial joint with a facet on the posterior surface of the anterior arch of the atlas, where it is retained by the alar, apical and transverse ligaments (Figs 8.15 & 8.16). The planes of the lateral atlantoaxial joints and the pivot joint of the dens (Fig. 8.14) allow rotation of the head as in looking from side to side.


Body
Anterior tubercle
Foramen transversarium
S
A
P
I
Spinous process
Posterior tubercle
Body
Vertebral foramen
Lamina
R
A
P
L
Foramen transversarium
Bifid spinous process
Superior articular facet
Anterior tubercle
Posterior tubercle

Fig. 8.11 Lateral and superior views of a typical (fourth) cervical vertebra.


Anterior arch
Transverse process
Foramen transversarium
S
A
P
I
Posterior arch
Transverse process
Facet for occipital condyle
R
A
P
L
Tubercle for transverse ligament
Anterior arch
Posterior arch
Posterior tubercle
Articular surface for dens of axis
Anterior arch
Foramen transversarium

Fig. 8.12 Lateral and superior views of the first cervical vertebra, the atlas.


Dens
Body
Transverse process
S
A
P
I
Spinous process
Foramen transversarium
Articular facets for atlas
R
A
P
L
Bifid spinous process

Fig. 8.13 Lateral and superior views of the second cervical vertebra, the axis.


S
L
R
I
Atlanto-occipital joint
Lateral atlantoaxial joint
Occipital condyle
Transverse process of atlas
Dens
Spinous process of axis

Fig. 8.14 Base of the skull, atlas and axis, seen in an expanded posterior view.


S
L
R
I
Anterior margin of foramen magnum
Alar ligament
Dens
Atlas
Axis
Superior part of cruciate ligament
Atlanto-occipital joint
Transverse and inferior parts of cruciate ligament
Lateral atlantoaxial joint

Fig. 8.15 Ligaments of the atlantoaxial joint. The posterior longitudinal ligament, spinal cord and meninges, vertebral arches and the posterior part of the skull have been removed. On the left side, part of the cruciate ligament has been excised. The view is oblique.


Anterior arch of atlas
Median atlantoaxial join
Dens of axis
Alar ligament
S
A
P
I
Transverse part of cruciate ligament
Posterior arch of atlas
Extradural space
Dura
Axis
Third cervical vertebra

Fig. 8.16 Near sagittal section through the median atlantoaxial joint.

The seventh cervical vertebra (Fig. 8.17) possesses a long, non-bifid spine, which provides the inferior attachment for the ligamentum nuchae. The spinous process is easily palpable and hence, the vertebra is called the vertebra prominens. The foramina transversaria of this vertebra are traversed by the vertebral veins but not by the arteries. The costal element of the seventh vertebra, represented by the anterior tubercle and the bar of bone in front of the transverse foramen, may form a cervical rib. The subclavian artery and the first thoracic nerve root may be stretched and distorted as they pass over (superior to) a cervical rib, leading to arterial damage and pain referred along the medial side of the upper limb.

The joints of the whole cervical column allow movements of extension, rotation and lateral flexion. These movements are brought about by the prevertebral and postvertebral muscles (Fig. 8.18), assisted by sternocleidomastoid and trapezius. The prevertebral muscles comprise the scalene group (p. 331) and the longus colli group. The latter passes from the base of the skull down the anterior surface of the vertebral column into the thorax. The prevertebral muscles are much smaller than the postvertebral group which has an antigravity action in keeping the head upright.

Arthritis involving joints of the cervical spine is often associated with the formation of bony outgrowths (osteophytes), which may compress the nerve roots that contribute to the brachial plexus (p. 80). Injuries to the cervical column, particularly involving fracture or dislocation of vertebrae, may result in spinal cord injury leading to quadriplegia or death. The atlantoaxial joint is particularly liable to disruption in hyperextension injuries.


Body
Transverse process
S
A
P
I
Spinous process
Body
Superior articular facet
R
A
P
L
Spinous process
Lamina
Pedicle
Transverse process

Fig. 8.17 Lateral and superior views of the seventh cervical vertebra, the vertebra prominens.




A
L
R
P
Sternocleido-mastoid
Levator scapulae
Longus colli
Pharyngeal wall
Scalene muscles
Trapezius
Splenius
Ligamentum nuchae
Transverso-spinalis

Fig. 8.18 Transverse section at the level of the fourth cervical vertebra, showing the muscles of the neck. Superior aspect. (Compare Fig. 7.94.)

Thoracic vertebrae

The bodies of the 12 thoracic vertebrae increase in size from above downwards. The bodies bear characteristic costal facets (Fig. 8.19), which form synovial joints with the heads of the ribs. Typically a vertebral body possesses one pair of facets (superior and inferior costal facets) on each side adjacent to the attachment of the pedicle. The upper facet receives the rib whose number corresponds to the vertebra, while the lower facet articulates with the rib below. However the tenth, eleventh and twelfth vertebrae possess facets on each side, which are for articulation with their own ribs. The vertebral canal is smaller than in any other region.

The transverse processes project laterally and backwards and typically each bears near its tip a facet for the tubercle of the corresponding rib. The spinous processes are long and slope steeply downwards. The plane of the joints between the facets on the articular processes is almost vertical and permits rotation. However, all movements in the thoracic region are restricted by the rib cage.




Body
Costal facets
Spinous process
Superior articular process
Inferior articular process
S
A
P
I
Vertebral foramen
Lamina
Pedicle
Transverse process
R
A
P
L

Fig. 8.19 Lateral and superior views of the second and tenth thoracic vertebrae.

Lumbar vertebrae

The upper four lumbar vertebrae are very similar. The vertebral foramina are moderate in size (Fig. 8.20) but the bodies are comparatively large, with concave sides. The transverse processes taper and are directed laterally and slightly backwards. The spinous processes are deep and rectangular. Facets on the superior articular processes face medially and 'grasp' the laterally directed inferior facets of the vertebra above, permitting wide ranges of flexion, extension and lateral flexion but severely restricting rotation.

The fifth lumbar vertebra has shorter transverse processes and a less angular spinous process. Its inferior articular facets are widely separated and face anteriorly. They articulate with the sacrum (Fig. 8.21) and prevent forward displacement of the vertebra. A fracture or developmental defect between the superior and inferior articular processes of the fifth lumbar vertebra will allow its body to slip anteriorly, a condition called spondylolisthesis, which may stretch or compress the cauda equina (p. 411). One or both transverse processes may be fused with the upper part of the sacrum (sacralization of the fifth lumbar vertebra), which can cause difficulty in the interpretation of radiographs.

Sacral and coccygeal vertebrae

The sacrum is a triangular bone formed by the fusion of five vertebrae (Figs 8.21 & 8.22). The upper surface of the sacrum resembles that of a lumbar vertebra and carries the lumbosacral disc. Below the apex of the sacrum lies the coccyx (Fig. 8.23), which may be a small single bone or up to four rudimentary vertebrae. The coccyx and the sacrum usually articulate via a small intervertebral disc, although they may be fused. The sacrum slopes backwards and downwards and is concave anteriorly. The bone in the female has relatively small joint surfaces and larger alae, while in the male the larger sacral promontory often creates a heart-shaped pelvic inlet (p. 214). The fused pedicles and laminae enclose the sacral canal, triangular in cross-section, which opens posteroinferiorly at the V-shaped sacral hiatus. The canal contains the lower part of the cauda equina, comprising the roots of the sacral and coccygeal nerves. The anterior rami of the upper four sacral nerves pass into the pelvis via the anterior sacral foramina and contribute to the sacral plexus. The posterior rami traverse the posterior sacral foramina (Fig. 8.22). Lateral to the foramina are the lateral masses, each of which bears an auricular surface for articulation with


Body
Pedicle
Superior articular process
S
A
P
I
Transverse process
Spinous process
Inferior articular facet
Body
Vertebral foramen
R
A
P
L
Superior articular facet
Spinous process
Lamina
Pedicle
Transverse process

Fig. 8.20 Lateral and superior views of a typical (third) lumbar vertebra.


Transverse process
Inferior articular facet
Superior articular process
Ala
First piece of sacrum
Anterior sacral foramen
S
R
L
I

Fig. 8.21 Fifth lumbar vertebra and the upper part of the sacrum, seen in an expanded anterior view.

the ilium (Fig. 8.23). Anaesthetic may be injected through the sacral hiatus and the caudal canal into the epidural space to anaesthetize the cauda equina.

The sacroiliac joint is synovial but allows very little movement because of the irregularity of the articulating surfaces and the thick posterior interosseous ligament. Each joint is further supported by the anterior and posterior sacroiliac ligaments and the iliolumbar, sacrospinous and sacrotuberous ligaments. Body weight, acting downwards through the lumbosacral disc, tends to rotate the lower part of the sacrum backwards, a movement prevented by the sacrospinous and sacrotuberous ligaments (Fig. 8.25).


Sacral promontory
S
A
P
I
Median sacral crest
Interosseous ligament
Articular surface
Lateral mass
Sacral canal
Superior articular facet
S
L
R
I
Posterior sacral foramina
Sacral hiatus

Fig. 8.22 Lateral and posterosuperior views of the sacrum.


S
A
P
I
S
A
P
I
Auricular surfaces
Anterior sacral foramina
Lateral mass
Coccyx
Ilium
Ischium
Pubis

Fig. 8.23 Oblique view of the sacrum, coccyx and right hip bone.

Table 8.2 Features of typical vertebrae in the regions of the vertebral column

	Vertebral bodies	Transverse processes	Vertebral foramina	Articular processes	Spinous processes
Cervical vertebrae	Small	**Foramina transversaria present**	Triangular	Joints in coronal plane and oblique, allowing lateral flexion with rotation	**Bifid** Short
Thoracic vertebrae	Heart-shaped **Costal facets present**	**Costal facets present** No foramina transversaria Incline posterolaterally	Circular	Joints in vertical plane and oblique, allowing rotation	Long Sloping
Lumbar vertebrae	Massive Kidney-shaped	**No costal facets** Incline laterally and slightly posteriorly	Triangular	Joints vertical in sagittal plane, preventing rotation	Thick Rectangular
Sacral segments	**Fused**	**Fused**	Canal		Tubercles

In individual subjects, the features of particular vertebrae may vary.

The different features of vertebrae from the regions of the column are summarised in Table 8.2.

Facet joints

The plane synovial joints between the facets of adjacent superior and inferior articular processes are called zygapophysial or facet joints. The joints in the different regions of the vertebral column allow different movements, determined by the orientations of the articular processes.

Intervertebral discs

Intervertebral discs connect adjacent vertebral bodies (Fig. 8.24) and act as fibrocartilaginous joints along the whole length of the vertebral column. Like the vertebral bodies, the discs gradually increase in size from above downwards, the largest being the lumbosacral disc between the fifth lumbar vertebra and the sacrum (Fig. 8.25). The discs contribute about one-fifth of the length of the vertebral column. Each disc consists of a laminated anulus fibrosus surrounding a gelatinous nucleus pulposus (Fig. 8.28). The nucleus pulposus lies closer to the posterior surface of the disc and thus is more liable to posterior herniation when the disc is damaged. This herniation, often called a slipped disc, may occur near the midline and compress the spinal cord or cauda equina. Posterolateral herniation may compress nerves near the intervertebral foramen (p. 396) and cause muscle weakness and referred pain. Usually, the herniation affects nerve roots passing through the intervertebral foramen below the affected disc. In the cervical region, herniation most commonly occurs between vertebrae C6–C7, affecting nerve C7, and between vertebrae C7–T1, affecting nerve C8. Compression of nerve C7 may produce pain in the dermatome C7 (p. 74) and weakness of extension of the elbow and wrist joints. Compression of nerve C8 may produce pain in the dermatome C8 (p. 74) and weakness of finger movements. In the lumbar spine, herniation most commonly occurs between vertebrae L4–L5, affecting nerve L5, and between vertebrae L5–S1, affecting nerve S1. Compression of nerve L5 may produce pain in the L5 dermatome (p. 258) and weakness of ankle dorsiflexion and extension of the great toe. Compression of nerve S1 may produce pain in the S1 dermatome (p. 258) and weakness of plantar flexion. Pain referred from the back into the lower limb is often called sciatica.

Intervertebral ligaments

The intervertebral discs are reinforced by posterior and anterior longitudinal ligaments (Figs 8.26 & 8.27). These ligaments attach to vertebral bodies and intervertebral discs and anchor inferiorly to the sacrum and superiorly to the cervical vertebrae or skull. Whiplash injuries involving excessive extension-flexion are caused by rear-end car crashes. There may be damage to the joints and ligaments of the cervical spine, including the anterior longitudinal ligament, resulting in cervical pain and restricted movement.

Other ligaments interconnect the laminae, spinous processes and transverse processes of adjacent vertebrae. Ligamenta flava interconnect the laminae within the vertebral canal. The high content of elastic tissue gives these ligaments their yellow appearance and they assist return of the vertebral column to the erect position following flexion. Supraspinous and interspinous ligaments connect adjacent spinous processes of thoracic and lumbar vertebrae. It is through these ligaments that a needle is inserted to withdraw cerebrospinal fluid during lumbar puncture.

The supraspinous and interspinous ligaments are replaced in the cervical region by the ligamentum nuchae, which attaches to the skull at the external occipital protuberance and crest and to the spinous processes of all the cervical vertebrae. Intertransverse ligaments connect the transverse processes of adjacent vertebrae. The lumbosacral joint is reinforced by the iliolumbar ligament, which attaches the transverse process of the fifth lumbar vertebra to the iliac crest (Fig. 8.28).


Lumbar vertebral body
Anterior longitudinal ligament
S
A
P
I
Lumbar spinal nerve in intervertebral foramen
Intervertebral disc
Pedicle

Fig. 8.24 Sagittal section of the lumbar vertebral column.


Anterior sacroiliac ligament
Anterior longitudinal ligament
Lumbosacral disc
Erector spinae
S
A
P
I
Anterior rami of S2, S3 and S4 (cut)
Piriformis
Sacrospinous ligament
Sacrotuberous ligament

Fig. 8.25 Right hemipelvis, showing the sacrum and coccyx in sagittal section.


Posterior longitudinal ligament
Pedicles (cut)
Cut edge
S
L
R
I

Fig. 8.26 Posterior longitudinal ligament, exposed by removal of the vertebral arches, meninges and spinal cord.


Anterior longitudinal ligament
S
R
L
I
Intervertebral discs
Fourth lumbar vertebral body
Cut edge

Fig. 8.27 Oblique view of anterior longitudinal ligament of the lumbar spine.


Quadratus lumborum
Psoas major
Transversus abdominis
Iliac crest
Lumbar vessels
Erector spinae
Thoracolumbar fascia
Spinous process of L3 vertebra
Nucleus pulposus
P
R
L
A

Fig. 8.28 Oblique view of a transverse section of the lumbar spine and muscles at the level of the disc between the third and fourth lumbar vertebrae.

Muscles

The muscles of the erector spinae group are covered in the lumbar region by the thoracolumbar fascia, in the lumbar and thoracic regions by the serratus posterior muscles and in the neck by the splenius muscles.

In the lumbar region, the thoracolumbar fascia is trilaminar and encloses erector spinae posteriorly and quadratus lumborum anteriorly (Fig. 8.28). At the lateral margins of both muscles, the laminae of the fascia fuse and give attachment to the transversus abdominis (Fig. 8.28).

Serratus posterior superior and inferior (Figs 8.29 & 8.30) are weak respiratory muscles, which connect lower cervical and upper thoracic spines with upper ribs, and lower thoracic and upper lumbar spines with lower ribs, respectively. They are supplied by branches of anterior rami of thoracic spinal nerves (intercostal nerves).

Splenius muscles

Splenius (Fig. 8.31) attaches medially to the lower part of the ligamentum nuchae and to the upper thoracic spinous processes. The superior part, splenius capitis, attaches laterally to the mastoid process and superior nuchal line. The inferior part, splenius cervicis, attaches laterally to the transverse processes of the upper cervical vertebrae.

Erector spinae

On each side, erector spinae (Fig. 8.33) occupy the groove between the spinous and transverse processes of vertebrae. The muscle attaches inferiorly to the posterior surface of the sacrum and the posterior part of the iliac crest. In the lumbar region it forms a prominent vertical muscle mass (Fig. 8.37) and attaches to the spinous and transverse processes of the lumbar vertebrae. In the upper lumbar region the


Pinna
Splenius
Levator scapulae (cut)
Serratus posterior superior
Erector spinae
S
L
R
I

Fig. 8.29 Serratus posterior superior. The upper limb girdle and its muscles have been removed.


Intercostal muscle
Erector spinae
Serratus posterior inferior
S
m
la
I
Fascial defect
External abdominal oblique

Fig. 8.30 Serratus posterior inferior revealed by removal of latissimus dorsi.

muscle divides into three columns. The lateral column forms iliocostalis, which attaches to the angles of the ribs and transverse processes of the lower cervical vertebrae. The intermediate column forms the longissimus, which attaches to the ribs and the transverse processes of the thoracic and cervical vertebrae. The medial part of the erector spinae forms the spinalis, which attaches to the spinous processes of the upper lumbar, thoracic and lower cervical vertebrae.

Erector spinae is innervated by branches from the posterior rami of spinal nerves.

Transversospinalis

The muscles of this group lie obliquely (Fig. 8.32), covered by erector spinae (Fig. 8.7). They interconnect transverse processes and spinous processes of vertebrae at higher levels. Semispinalis forms the longest and most superficial member of this group and interconnects lower thoracic transverse processes and upper thoracic and cervical spinous processes. Multifidus lies deep to semispinalis. Its fibres attach the transverse process of each vertebra to the spinous processes of one to three vertebrae above. The deepest fibres of transversospinalis form the rotatores, which connect the lamina of one vertebra to the transverse process of the vertebra below. The rotatores are best developed in the thoracic region.

The transversospinalis muscles are supplied by the posterior rami of the spinal nerves.

Actions

Simultaneous contraction of the deep muscles of both sides extends the vertebral column and regulates or prevents flexion. Unilateral contraction produces lateral flexion and rotation, assisted by the abdominal oblique muscles. The deep muscles have a very important role in achieving and maintaining the fully upright posture.


Splenius capitis
Splenius cervicis
Erector spinae
S
L
R
I

Fig. 8.31 Splenius cervicis and capitis after excision of serratus posterior superior.


Joint of head of rib
Intervertebral disc
Oesophagus
Spinal cord
Descending aorta
Lung
Erector spinae
Trapezius
Transverso-spinalis
Dura
Subarachnoid space
Zygapophysial (facet) joint
A
R
L
P

Fig. 8.32 Transverse section at the level of the sixth thoracic vertebra to show the back muscles and the vertebral foramen. Inferior aspect.


Pinna
Splenius
Longissimus
S
L
R
I
Iliocostalis
External intercostal muscles
Ribs
External abdominal oblique
Position of iliac crest

Fig. 8.33 Splenius and erector spinae exposed by removal of overlying muscles and fasciae.

Meninges

The spinal cord is surrounded by three membranes (dura mater, arachnoid mater and pia mater; Fig. 8.34), which are continuous through the foramen magnum with the cranial meninges.

Dura mater

The dura mater surrounding the spinal cord forms a sheath that corresponds to the inner (meningeal) layer of the cranial dura (p. 374). The spinal dura is separated from the periosteum of the vertebral canal by the extradural (epidural) space (Figs 8.16 & 8.32), which contains fat, vessels and loose connective tissue. Anaesthetic agents are instilled into this space to produce epidural anaesthesia. Spinal dura is attached to the margins of the foramen magnum and via fibrous slips to the posterior longitudinal ligament within the vertebral canal. Inferiorly the dura covers the filum terminale (Fig. 8.35). At the level of the second sacral vertebra the dura attaches to the filum terminale and these continue onto the back of the coccyx to fuse with the periosteum.

Each spinal nerve root is surrounded by a sleeve of dura mater which extends through the intervertebral foramen before fusing with the epineurium of the spinal nerve.

Arachnoid mater

The arachnoid mater is a delicate membrane that surrounds the spinal cord and the nerves within the vertebral canal. Above it, is continuous with the cranial arachnoid through the foramen magnum and below it ends at the level of the second


Spinal cord
Subarachnoid space
Pia
Arachnoid
Extradural space
Transverse process
Dura
A
L
R
P

Fig. 8.34 Spinal meninges.


Lumbar enlargement
Spinal dura (cut and reflected)
Conus medullaris
Posterior nerve roots
Cauda equina
Filum terminale
S
L
R
I

Fig. 8.35 Erector spinae and neural arches removed; spinal dura and arachnoid opened posteriorly and reflected laterally, exposing the lumbar enlargement, conus medullaris and cauda equina.

sacral vertebra. The arachnoid is connected to the pia mater by numerous delicate strands that cross the subarachnoid space between the two meninges. This space is filled with cerebrospinal fluid and also contains blood vessels, which supply the spinal cord. The cerebrospinal fluid is produced in the ventricular system of the brain and circulates in the subarachnoid space around the spinal cord and brain (p. 376). Cerebrospinal fluid is usually sampled by inserting a needle between the arches of the third and fourth or fourth and fifth lumbar vertebrae. In this procedure, which is called a spinal tap or lumbar puncture, the needle is carefully orientated to pass between the spinous processes and enter the subarachnoid space below the termination of the spinal cord so that there is no danger of damage to the spinal cord. In spinal anaesthesia, anaesthetic agents may be injected into the subarachnoid space via a lumbar puncture technique. In a midline puncture, the needle would traverse skin, superficial tissues, supraspinous and interspinous ligaments, the epidural space, the dura and arachnoid mater.

Pia mater

The pia mater is a highly vascular layer that closely invests the spinal cord and nerves. On each side, the pia mater is attached to the dura by the ligamentum denticulatum between the anterior and posterior spinal roots. The pia surrounds the termination of the spinal cord (conus medullaris) and continues as the filum terminale as far as the posterior surface of the coccyx.

Spinal Cord

Surface features

At the level of the upper border of the atlas, the spinal cord is directly continuous with the medulla oblongata. Inferiorly, the cord usually extends as far as the first lumbar intervertebral disc, where it terminates as the conus medullaris. In transverse section, the spinal cord is oval, with its smaller diameter anteroposteriorly. The cord is especially wide at the cervical and lumbar enlargements due to increased numbers of nerve cell bodies within the spinal cord, which innervate the upper and lower limbs.

On the anterior aspect of the cord lies the anterior median fissure, whereas posteriorly, there is a relatively shallow posterior median sulcus. On each side, a posterolateral sulcus marks the site of attachment of the posterior nerve roots.

Spinal nerve roots

The spinal nerves are attached to the spinal cord by anterior and posterior nerve roots (Fig. 8.36). The region of the spinal cord to which one pair of anterior and posterior nerve roots attaches is called a spinal segment (Table 8.3).

Each anterior spinal root emerges from the cord as a series of small rootlets, while similar branches from each posterior spinal root sink into the posterolateral sulcus. The anterior and posterior roots cross the subarachnoid space and unite in the appropriate intervertebral foramen to form a spinal nerve. Each posterior root is characterized by a ganglion just proximal to the union of anterior and posterior roots.

Because the spinal cord is shorter than the vertebral column, the lower spinal nerve roots descend within the vertebral canal before leaving through their intervertebral foramina (Table 8.3). These lumbar, sacral and coccygeal nerve roots are clustered around the conus medullaris and filum terminale to form the cauda equina (Figs 8.35 & 8.37). Compression of the cauda equina, for example by a large central prolapse of an intervertebral disc, may disrupt bladder function and sphincter control and also produce bilateral sensory and motor abnormalities in the lower limbs.


Posterior cervical nerve roots
Cervical enlargement
Spinal dura (cut and reflected)
Ligamentum denticulatum
Thoracic spinal cord
Posterior thoracic nerve roots
S
L
R
I

Fig. 8.36 Cervical spinal cord and dorsal nerve roots. Erector spinae and neural arches removed; the spinal dura has been reflected laterally.

Table 8.3 Levels of spinal cord segments and meninges

Spinal cord	Level in vertebral canal	Meninges
C1 segment	Foramen magnum of skull	
Cervical enlargement	C4–T2 bodies	
C8 segment	C7 body	
L3 segment	T12 body	
Lumbosacral enlargement	T12, L1 bodies	
Lowest extent of spinal cord in adults	L2 body	
Lowest extent of spinal cord in infants	L3 body	
	L3-S2 bodies	Subarachnoid space below spinal cord containing cauda equina
	L3/L4 and L4/L5 spaces	Obtain sample of CSF by lumbar puncture
	S3 segment	Lowest extent of subarachnoid space

Blood supply

The spinal cord receives its arterial supply from anterior and posterior spinal arteries that arise from vertebral arteries and are reinforced by branches of the deep cervical, intercostal and lumbar arteries. These vessels form a longitudinal anastomosis that runs the length of the spinal cord. One main branch from an upper lumbar or lower thoracic artery often provides an important supply to the spinal cord. Damage to this vessel, the artery of Adamkiewicz, may threaten the viability of part of the spinal cord. For example, lumbar arteries may become blocked in aortic aneurysm disease, resulting in spinal cord ischaemia leading to paraplegia with paralysis and loss of sensation in both lower limbs. The venous return from the spinal cord drains into a series of longitudinal anastomosing channels, which empty into veins corresponding to the arteries.


A
R
L
P
Liver
Psoas major
Kidney
Quadratus lumborum
Cauda equina
Spinous process
Crus of diaphragm
Descending colon
Transversospinalis
Abdominal wall muscles
Erector spinae
Thoracolumbar fascia

Fig. 8.37 Transverse section at the level of the first lumbar vertebra to show the back muscles and the contents of the vertebral foramen. Inferior aspect.

Exam Skills

Each of the incomplete statements below is followed by five suggested answers or completions. Decide which are true and which are false. The answers are supplied on p. 417.

1. During walking and/or running the following normally occur:

a) lateral flexion at the lumbar intervertebral joints.
b) movement at the hip joints.
c) contraction of the gluteal muscles.
d) movement at the sacroiliac joints.
e) rotation of the thoracic vertebral column.

2. Concerning the joints between the atlas and the axis:

a) they are all synovial.
b) they allow rotation of the head.
c) they are supported by the alar ligaments.
d) dislocation is usually fatal.
e) they are closely related to the first cervical nerves.

3. The sacroiliac joint:

a) is a fibrous joint.
b) allows rotation in which the lower part of the sacrum moves anteriorly.
c) is stabilized by the sacrotuberous ligament.
d) is a posterior relation of the common iliac artery.
e) is stabilized by the iliolumbar ligament.

4. The lumbar region of the vertebral column:

a) is the least mobile region of the spinal column.
b) has vertebrae which possess mamillary processes.
c) is flexed by the rectus abdominis.
d) has a secondary curvature.
e) has spinous processes which overlap the body of the adjacent vertebra below.

5. The spinal cord:

a) gives rise to eight pairs of cervical spinal nerves.
b) is continuous above with the medulla oblongata.
c) is intimately related to the pia mater.
d) extends throughout the length of the vertebral canal.
e) is separated from CSF by the arachnoid mater.

6. The intervertebral disc between vertebrae L3 and L4:

a) is the smallest intervertebral disc.
b) is related anteriorly to the abdominal aorta.
c) provides attachment for psoas major.
d) is related posteriorly to the cauda equina.
e) is closely related to the second lumbar nerves.

7. The atlas vertebra:

a) has no spinous process.
b) possesses no foramina transversaria.
c) has a vertebral body.
d) permits nodding movements at its joints with the cranium.
e) has large transverse processes.

8. Intervertebral discs:

a) occur between the bodies of adjacent vertebrae.
b) are intimately related to the anterior and posterior longitudinal ligaments.
c) are secondary cartilaginous joints.
d) form part of the borders of the intervertebral foramina.
e) contribute to the curvatures of the vertebral column.

9. The sacrum:

a) usually consists of fused components of five vertebrae.
b) is concave anteriorly.
c) is attached by ligaments to the ilium and ischium.
d) forms synovial joints with the articular processes of the fifth lumbar vertebra.
e) possesses on each side an ala which is crossed by the anterior ramus of the fifth lumbar nerve.

10. The thoracic vertebral column:

a) has a primary curvature which is concave anteriorly.
b) includes 12 vertebrae.
c) articulates with the heads of ribs.
d) throughout its length is related anteriorly to the oesophagus.
e) permits lateral flexion which is restricted by the ribs.

11. The thoracolumbar fascia:

a) provides attachment for transversus abdominis.
b) encloses psoas major muscle.
c) has no attachment to bone.
d) provides attachment for external abdominal oblique muscle.
e) provides attachment for latissimus dorsi.

12. The spinal dura mater:

a) is attached to the vertebral periosteum.
b) lies deep to the spinal arteries.
c) lies superficial to the vertebral venous plexus.
d) terminates at the level of vertebra L2.
e) attaches to the margins of the foramen magnum.

13. A typical cervical vertebra possesses:

a) two pairs of synovial joints.
b) a bifid spinous process.
c) a relatively wide vertebral foramen.
d) a relatively small body.
e) foramina transversaria.

14. The vertebral canal:

a) transmits the vertebral artery.
b) contains ligamenta flava.
c) contains a venous plexus.
d) is narrowed by rotation of the head.
e) lies anterolateral to the cervical vertebral discs.

15. The following relate to lumbar puncture at vertebral level L4/L5:

a) the spinal cord terminates at a higher vertebral level.
b) at this level the ligaments are thinner and easier to penetrate.
c) there is no overlap of the spinous processes.
d) the spinal nerves that exit from the vertebral column below this level are of little importance.
e) the subarachnoid space extends inferiorly to below vertebral level L5.

16. The joints between vertebrae C4 and C5 allow:

a) rotation.
b) flexion with rotation.
c) pure extension.
d) lateral flexion.
e) lateral flexion with rotation.

Clinical Case Skills

The answers are supplied on p. 420.

Case Study 1

A 45-year-old man began to experience headaches, which spread over the back of his head. He had no previous medical problems other than a whiplash injury following a car accident several years previously. His physician paid particular attention to the man's neck and found nothing remarkable on examination other than some restriction of neck movement. Cervical spine radiographs were reported to show early degenerative changes with occasional small osteophytes.

A physiotherapist friend visited the man and was disappointed to find him sitting slumped in a low easy chair but straining forwards and upwards to watch television. The friend tactfully suggested that it might be more comfortable if the television were placed at a lower level and how comfortable cushions were when placed in the hollow of the back. When the physiotherapist called again, she was pleased to discover that the television had been repositioned, the cushions were in use and the man had not experienced any more headaches. He later became re-employed as a gardener.

Questions:

1. At which joints do the movements in the cervical spine occur?
2. Which curvatures are present in the normal vertebral column and what are the effects of sitting as described?
3. What was the cause of the pain felt over the back of the head?

Case Study 2

A 40-year-old man had suffered from intermittent low backache, which started soon after he had helped a neighbour move furniture 2 years previously. He had some tingling along the outside of his left leg, which usually lasted for only a few days. He found that lying flat on the carpeted floor of his living room relieved his backache.

A few days later when bending he felt a sudden severe pain in his back, and tingling along the outside and back of his left leg below the knee. His physician found the man's spine was held in a curve convex to the right and noted that any movement of his lumbar spine produced pain and was restricted by muscle spasm. His lower limbs showed no sensory deficit or muscle weakness and his reflexes were normal apart from an absent left ankle jerk. Straight leg raising aggravated the backache and subsequently, radiography of his lumbar spine showed probable disc space narrowing at L5/S1. Magnetic resonance imaging confirmed a small posterolateral disc protrusion at that level.

Questions:

1. Which dermatome is associated with the posterolateral surface of the leg below the knee?
2. Which segmental level is tested by the ankle jerk?
3. Which spinal nerve traverses the intervertebral foramen immediately below L5 vertebra?
4. What are the boundaries of an intervertebral foramen?
5. Why should disc protrusion at L4/L5 involve S1 nerve?

Case Study 3

A 50-year-old man had been unwell for about 3 months and was losing weight. He suddenly developed severe abdominal pain and was admitted to hospital with suspected peritonitis.

The surgeon took a detailed history and discovered that, although abdominal pain was the main feature, the patient had had backache for several weeks and this was now worse. The abdomen revealed no distension or localized signs and normal bowel sounds were heard. Results of blood tests showed that the white cell count was normal but that haemoglobin was low. Chest and abdominal radiographs were accompanied by additional films because the radiologist had noticed spinal disease. Several vertebrae showed areas of increased bone formation (sclerosis), others showed areas of bone destruction (lysis) and T10 and T11 showed collapse of their bodies. Subsequent tests revealed high plasma levels of acid and alkaline phosphatases and the man was referred to a urologist who obtained fragments of prostatic tissue-containing tumour.

Questions:

1. What was the cause of the 'abdominal' pain?
2. What is the route of spread of disease from pelvic organs such as the prostate to the vertebral bodies?
3. Why was the patient anaemic?

Case Study 4

A previously healthy 30-year-old mother collapsed after taking her children to school. In the Emergency Department, she appeared confused and complained bitterly of a severe generalized headache and that the room lights were too bright. Abnormal findings on physical examination were limited to blood pressure 180/110 and apparent restriction of cervical spine movements.

After admission to hospital a neurologist confirmed photophobia, neck stiffness and raised blood pressure. He performed a lumbar puncture and found blood in the cerebrospinal fluid (CSF).

Questions:

1. Where is CSF located?
2. How are samples of CSF usually obtained?
3. What is a safe vertebral level to attempt lumbar puncture and what layers are traversed?
4. Why was the patient's neck stiff even though she had no history of cervical spine disease?

Observation Skills

Identify the structures indicated. The answers are supplied at the foot of the page.



Fig. 8.38 Lateral radiograph of cervical spine.

Answers:

Fig. 8.38 1 = occipital bone; 2 = posterior arch of atlas; 3 = body of axis; 4 = intervertebral foramen; 5 = soft tissue shadow of postvertebral muscles; 6 = spinous process of fifth cervical vertebra; 7 = intervertebral disc; 8 = body of seventh cervical vertebra; 9 = clavicle; 10 = tracheal air shadow; 11 = calcification in laryngeal cartilage; 12 = hyoid bone; 13 = epiglottis; 14 = mandible; 15 = odontoid process; 16 = anterior arch of atlas.



Fig. 8.39 Anteroposterior radiograph of male pelvis and lumbar spine.

Answers:

Fig. 8.39 1 = spinous process; 2 = body of fourth lumbar vertebra; 3 = lamina; 4 = transverse process; 5 = edge of soft tissue shadow of psoas major; 6 = gas in colon; 7 = coxal joint; 8 = head of femur; 9 = phleboliths; 10 = obturator foramen; 11 = inferior ramus of pubis; 12 = ischial tuberosity; 13 = lesser trochanter; 14 = pubic symphysis; 15 = greater trochanter; 16 = neck of femur; 17 = ischial spine; 18 = coccyx; 19 = sacral foramina; 20 = sacroiliac joint; 21 = lateral mass of sacrum; 22 = iliac crest.

Exam and Clinical Case Skills Answers

Thorax

1. a) T; b) T; c) T; d) F; e) F
2. a) F; b) T; c) T: d) T; e) T
3. a) T; b) F; c) T; d) T; e) F
4. a) T; b) T; c) T; d) T; e) T
5. a) T; b) F; c) T; d) F; e) T
6. a) F; b) T; c) T; d) F; e) T
7. a) T; b) F; c) T; d) T; e) F
8. a) T; b) F; c) T; d) F; e) T
9. a) T; b) T; c) T; d) T; e) T
10. a) T; b) T; c) F; d) T; e) F
11. a) F; b) T; c) F; d) T; e) T
12. a) F; b) T; c) T; d) T; e) T
13. a) T; b) T; c) F; d) F; e) F
14. a) F; b) T; c) T; d) F; e) T
15. a) F; b) T; c) T; d) F; e) T
16. a) F; b) F; c) T; d) T; e) F

Upper Limb

1. a) T; b) F; c) T; d) T; e) T
2. a) F; b) T; c) T; d) F; e) T
3. a) T; b) T; c) F; d) T; e) T
4. a) T; b) T; c) T; d) T; e) T
5. a) T; b) T; c) T; d) T; e) F
6. a) F; b) F; c) T; d) T; e) T
7. a) T; b) T; c) F; d) F; e) T
8. a) F; b) T; c) F; d) T; e) F
9. a) T; b) F; c) T; d) T; e) F
10. a) T; b) T; c) F; d) F; e) T
11. a) T; b) F; c) F; d) F; e) F
12. a) F; b) T; c) T; d) T; e) T
13. a) F; b) T; c) T; d) F; e) F
14. a) F; b) F; c) T; d) T; e) F
15. a) F; b) T; c) T; d) T; e) T
16. a) T; b) T; c) T; d) T; e) F

Abdomen

1. a) T; b) T; c) T; d) F; e) F
2. a) F; b) T; c) T; d) T; e) F
3. a) F; b) T; c) T; d) T; e) F
4. a) T; b) T; c) T; d) F; e) F
5. a) T; b) F; c) T; d) F; e) T
6. a) F; b) T; c) T; d) T; e) F
7. a) T; b) T; c) F; d) F; e) T
8. a) F; b) F; c) F; d) T; e) T
9. a) T; b) T; c) F; d) T; e) T
10. a) T; b) T; c) T; d) F; e) T
11. a) T; b) T; c) T; d) F; e) T
12. a) T; b) F; c) T; d) T; e) F
13. a) T; b) T; c) T; d) T; e) T
14. a) T; b) T: c) F; d) T; e) F
15. a) F; b) T; c) T; d) T; e) F
16. a) T; b) T; c) F; d) T; e) F

Pelvis and Perineum

1. a) F; b) T; c) F; d) T; e) T
2. a) F; b) T; c) T; d) F; e) T
3. a) T; b) F; c) T; d) T; e) F
4. a) T; b) F; c) T; d) F; e) T
5. a) T; b) T; c) F; d) T; e) T
6. a) T; b) T; c) F; d) T; e) F
7. a) T; b) F; c) T; d) T; e) F
8. a) T; b) F; c) T; d) T; e) F
9. a) F; b) T; c) T; d) T; e) T
10. a) F; b) T; c) T; d) T; e) F
11. a) T; b) T; c) T; d) F; e) F
12. a) T; b) T; c) F; d) T; e) T
13. a) T; b) T: c) T; d) F; e) T
14. a) T; b) T; c) T; d) F; e) T
15. a) F; b) T; c) T; d) T; e) F
16. a) T; b) T; c) F; d) T; e) F

Lower Limb

1. a) T; b) T; c) F; d) T; e) T
2. a) T; b) T; c) T; d) F; e) T
3. a) T; b) F; c) F; d) T; e) T
4. a) T; b) T; c) T; d) T; e) F
5. a) T; b) T; c) T; d) F; e) T
6. a) T; b) T; c) F; d) T; e) T
7. a) T; b) T; c) T; d) T; e) T
8. a) T; b) T; c) T; d) T; e) F
9. a) F; b) T; c) T; d) T; e) T
10. a) T; b) T; c) T; d) F; e) T
11. a) T; b) T; c) T; d) T; e) F
12. a) T; b) F; c) F; d) T; e) T
13. a) T; b) T; c) T; d) T; e) F
14. a) T; b) T; c) T; d) F; e) T
15. a) T; b) F; c) T; d) T; e) T
16. a) F; b) T; c) T; d) T; e) T

Head and Neck

1. a) F; b) F; c) T; d) F; e) T
2. a) T; b) F; c) T; d) T; e) F
3. a) T; b) T; c) T; d) T; e) T
4. a) T; b) T; c) F; d) T; e) F
5. a) F; b) T; c) F; d) F; e) T
6. a) T; b) T; c) F; d) T; e) T
7. a) F; b) F; c) T; d) T; e) T
8. a) T; b) T; c) F; d) F; e) T
9. a) T; b) F; c) T; d) T; e) F
10. a) T; b) T; c) T; d) T; e) T
11. a) T; b) T; c) T; d) F; e) F
12. a) F; b) F; c) T; d) T; e) T
13. a) F; b) F; c) T; d) T; e) F
14. a) F; b) F; c) F; d) F; e) F
15. a) T; b) T; c) T; d) F; e) F
16. a) F; b) F; c) T; d) F; e) F

Back

1. a) T; b) T; c) T; d) F; e) T
2. a) T; b) T; c) T; d) T; e) F
3. a) F; b) F; c) T; d) T; e) T
4. a) F; b) T; c) T; d) T; e) F
5. a) T; b) T; c) T; d) F; e) F
6. a) F; b) T; c) T; d) T; e) F
7. a) T; b) F; c) F; d) T; e) T
8. a) T; b) T; c) T; d) T; e) T
9. a) T; b) T; c) T; d) T; e) T
10. a) T; b) T; c) T; d) F; e) T
11. a) T; b) F; c) F; d) F; e) T
12. a) F; b) F; c) F; d) F; e) T
13. a) T; b) T; c) T; d) T; e) T
14. a) F; b) T; c) T; d) F; e) F
15. a) T; b) F; c) T; d) F; e) T
16. a) T; b) T; c) T; d) T; e) T

Thorax

Case Study 1

1. The physical examination should be directed at the (i) axilla, (ii) opposite breast, (iii) supra- and infraclavicular regions and (iv) the parasternal region. Malignancies of the breast commonly spread via lymphatics to these areas.
2. Pectoralis major.
3. During surgery the nerve supply to the serratus anterior (long thoracic nerve) must have been damaged.
4. Surgery removes most of the lymphatic drainage of the limb through the axilla.

Case Study 2

1. The left recurrent laryngeal nerve has been damaged by the lesion, thereby affecting the innervation of laryngeal muscles.
2. Left phrenic nerve, aortic arch, left bronchus, left pulmonary artery and vein.
3. Phrenic nerve.
4. The left upper lobe would collapse as air is absorbed from the bronchial tree within the lobe.

Case Study 3

1. Pain referred via autonomic nerves to the eighth cervical and first thoracic spinal cord segments.
2. Reduction in coronary blood flow causes damage to heart muscle and conduction tissue.
3. The right coronary artery usually supplies both SA and AV nodes.
4. Between the right and left coronary arteries in the coronary sulcus and between the anterior and posterior interventricular arteries at the apex of the heart.

Case Study 4

1. Coarctation of the aorta at a site beyond the origin of the left subclavian artery.
2. Intercostal arteries. Blood was flowing from the anterior into the posterior intercostal arteries and then into the descending thoracic aorta.
3. Both anterior and posterior intercostal arteries in the first two intercostal spaces are branches from vessels which arise proximal to the coarctation (internal thoracic artery and costocervical trunk, respectively).
4. Yes. Turbulence caused by the narrowed segment of the aorta particularly during ventricular contraction.

Upper Limb

Case Study 1

1. Mitral valve, left ventricle, aortic valve, ascending aorta, aortic arch, brachiocephalic, right subclavian and axillary arteries.
2. Sudden reduction of arterial lumen at major branches such as profunda brachii.
3. Lack of sensation and movement are obvious: amputation of her hand would probably have been necessary.
4. Anastomoses and collaterals involving branches of the scapular arteries.

Case Study 2

1. Loss of muscle bulk (wasting) in lower motor neurone problems: median nerve in carpal tunnel.
2. Cut thumb without pain: impaired sensation of anterior thumb, index, middle fingers.
3. Incisions parallel to Langer's lines following skin creases produce less obvious scars.
4. Recurrent branch of median nerve, in hand and ulnar nerve.

Case Study 3

1. Shallow glenoid fossa, lax joint capsule.
2. Axillary nerve at surgical neck: cutaneous sensation over insertion of deltoid.
3. To prevent external rotation, which produces instability.
4. Pain promotes disuse atrophy (wasting) resulting in muscle weakness making further injury more likely.
5. Strength of rotator cuff muscles acting as 'adjustable ligaments'.

Case Study 4

1. Superficial extensor muscles of the forearm at common extensor origin and supracondylar ridge.
2. Extension with lateral deviation (abduction) at the wrist joint.
3. Extensors carpi radialis longus and brevis.
4. Any powerful grip requires extension at the wrist produced by three carpal extensor muscles.

Abdomen

Case Study 1

1. Indirect inguinal hernia
2. There must be a persistent processus vaginalis along the inguinal canal into the scrotum: a tubular communication between the general peritoneal cavity and the tunica vaginalis anterior to the testis.
3. The hernia had been present only at times of high intra-abdominal pressure (e.g. during coughing or crying). The intestine can slide to and fro along the processus vaginalis.
4. Most likely a loop of small intestine.
5. The gut loop became trapped in the hernial sac and its lumen became obstructed.
6. He will replace the gut in the abdomen and close off the processus at the deep inguinal ring.

Case Study 2

1. In addition to the general signs of shock there was the tender abdomen and the pain in the left shoulder, the latter very likely a referred pain from irritation (by blood) of the inferior surface of the diaphragm.

2. The organ is readily ruptured because of its delicate consistency. It may be trapped against the left lower ribs that lie posterior to it. It has a rich blood supply and may therefore bleed profusely.
3. Greater sac.

Case Study 3

1. Hepatitis due to alcohol poisoning.
2. In addition to the history, the liver is enlarged and tender.
3. The liver lies immediately inferior to the diaphragm and it therefore descends when the diaphragm contracts.
4. Obstruction to portal blood flow through the liver leads to a rise in pressure in the portal vein and its tributaries. Portacaval anastomoses dilate, providing alternative routes for blood to reach the heart. One site of anastomosis is in the wall of the oesophagus where submucosal veins (oesophageal varices) become dilated.
5. In the wall of the rectum and anal canal; within the falciform ligament and in the abdominal wall radiating from the umbilicus (caput medusae); between the posterior abdominal wall and any retroperitoneal digestive organ, such as the duodenum.

Case Study 4

1. The right ureter: he has ureteric colic: the pain of a kidney stone passing down the ureter.
2. The patient has signs indicating a problem with the genitourinary system. Rectal examination enables the prostate gland, part of that system, to be palpated. In addition, it might help to suggest or eliminate other causes of such pain: an inflamed appendix within the pelvis would produce tenderness to the right of the rectum.
3. A vertical line near the tips of the lumbar vertebral transverse processes, across the sacroiliac joint and then sweeping past the ischial spine to curve medially towards the bladder.
4. The films will show the bladder, and provided the kidney is excreting, the kidney itself, the calices, renal pelvis and ureter on each side.

Pelvis and Perineum

Case Study 1

1. The pudendal nerve supplies most of the perineum. It gives branches to the skin around the anus (inferior rectal branches) and to most of the vulva (posterior labial branches).
2. The ischial spines, around which the pudendal nerves runs to enter the perineum from the gluteal regions.

Case Study 2

1. The pregnancy was in the right uterine tube and the bleeding was irritating the adjacent peritoneum.
2. Tenderness in the right vaginal fornix. The dilated and bleeding uterine tube lay close to the vagina.
3. He suspected bleeding into the peritoneal cavity. If the patient is being nursed lying flat, blood might track from the pelvis to the subphrenic area to give the classic referred pain due to the phrenic nerve's innervation of the inferior surface of the diaphragm.

Case Study 3

1. The maintenance of a higher pressure in the urethra than in the bladder.
2. The external urethral sphincter (sphincter urethrae) and the levator ani (pelvic floor). These muscles compress the urethra and support its upper part within the pelvic cavity where it is subjected to the same increases in pressure, for example during laughing, as the bladder. The planned exercises are intended to strengthen these muscles.
3. The pelvic floor is stretched during childbirth. Thus the gap between the pubococcygeus muscles gets wider and the bladder sinks to a lower level. The prostate contributes to urinary continence in men, unless it is diseased or damaged.
4. Parasympathetic nerves arising from the spinal cord segments S2, 3 and 4.

Case Study 4

1. The cancer may already have spread via the lymphatic vessels accompanying the mesenteric vessels and abdominal aorta, then the thoracic duct, to the root of the neck.
2. He may have been testing for enlargement of the liver, a likely site for blood-borne secondary cancer because of the portal venous system.
3. The sacrum, vagina, prostate and bladder.

Lower Limb

Case Study 1

1. Applying firm downward pressure over the quadriceps just above the patella forces fluid from the suprapatellar pouch behind the patella towards the general synovial cavity. The extra fluid accumulates behind the patella, which 'floats' forwards away from the femur. On displacing the patella backwards it can be felt to tap against the patella surface of the femur.
2. The medial meniscus.
3. The tibial collateral ligament.
4. Extracapsular: ligamentum patellae, tibial and fibular collateral, oblique popliteal ligament. Intracapsular: anterior and posterior cruciate, oblique popliteal. Collaterals provide medial and lateral stability and limit overextension. Cruciates provide anteroposterior stability and resist over-extension, as does the oblique popliteal ligament. The meniscofemoral ligament holds the lateral meniscus onto the lateral femoral condyle as the femur rotates.

Case Study 2

1. Great saphenous vein.
2. The swelling is a ballooning out of the wall of the great saphenous vein just where it goes deeply to drain into the femoral vein. The thrill on coughing results from

transmission of a pressure wave down the venous system as the result of raised intra-abdominal pressure.

3. The 'muscle pump' mechanism operates in the foot, calf and thigh. Muscle contractions squeeze and empty the deep veins, the blood being propelled upwards towards the heart, valves ensuring unidirectional flow.
4. Other causes of lumps in the groin include: inguinal lymph nodes, inguinal and femoral herniae, incomplete or maldescended testis, psoas abscess or bursitis, lipoma.

Case Study 3

1. Femoral artery, which is located superficially just below the mid-point of the inguinal ligament.
2. Femoral in the groin, popliteal behind the knee, posterior tibial behind medial malleolus, dorsalis pedis on dorsum of foot.
3. Superior medial, superior lateral, inferior medial and inferior lateral genicular from popliteal; recurrent genicular from anterior and posterior tibials; descending genicular from femoral.

Case Study 4

1. Sciatic nerve. Tibial nerve.
2. Involvement of anterior horn cell, anterior nerve root, spinal nerve or its anterior ramus. These comprise the lower motor neurone, characterized by muscle wasting and flaccid paralysis.

Head and Neck

Case Study 1

1. Give the patient something acidic to suck, and then observe the opening of the parotid duct (in the cheek, opposite the second upper molar tooth) for the production of secretions.
2. The facial nerve, motor nerve to muscles of facial expression, lies within the parotid gland and is often disturbed during surgery.
3. The nerve was not interrupted, more likely just stretched, so recovery of function occurred.
4. Some parasympathetic nerve fibres to the parotid gland were interrupted during surgery, and during the healing process they were able to innervate sweat glands in the skin. Thus, when they would be expected to stimulate salivation, they gave rise to 'gustatory sweating'.

Case Study 2

1. The student had dislocated his temporomandibular joints on both sides.
2. The head of the mandible has moved farther forwards than usual, and is now in front of the articular prominence of the joint. Contraction of muscles normally associated with closure of the mouth only raises the head more firmly in front of the prominence.
3. Relaxing the closing muscles, and putting downward pressure on the mandible to allow the head to slip back into the fossa of the joint.

Case Study 3

1. He would ask the patient to swallow. Swallowing raises the larynx, and as the thyroid gland is enclosed in the pretracheal fascia which is itself attached to the larynx, the thyroid gland also rises on swallowing.
2. The recurrent laryngeal nerve lies posterior to the thyroid gland and is likely to be damaged during surgery.
3. Good surgical practice is to positively identify a vulnerable structure, so that subsequent manipulation of tissues avoids damage to it.
4. The parathyroid glands also lie embedded in the posterior surface of the lateral lobes of the thyroid gland.

Case Study 4

1. Cavernous venous sinus thrombosis on the left side.
2. The abducent nerve (VI) runs through the body of the cavernous sinus, and supplies the lateral rectus muscle of the orbit which abducts the eye.
3. Infection from the pustules on the surface of the face has been carried by the veins of the face through the ophthalmic veins, or deep facial veins to the cavernous sinus where thrombosis has occurred. Infection enters the veins when pustules are squeezed.
4. The thrombosis has already involved oculomotor, trochlear and maxillary nerves, and will probably begin to affect the arterial supply to the orbit. Ultimately, meningitis and death are the probable outcomes without treatment.

Back

Case Study 1

1. Atlantoaxial, rotation; atlanto-occipital, nodding; other intervertebral joints, flexion, extension, lateral flexion with rotation.
2. Cervical convex anteriorly, thoracic concave anteriorly, lumbar convex anteriorly: loss of normal lumbar and cervical curves, but increased extension of upper cervical joints.
3. Irritation of roots of upper cervical nerves.

Case Study 2

1. Fifth lumbar.
2. First sacral.
3. Fifth lumbar.
4. Upper and lower vertebral notches (pedicles), intervertebral disc, facet joint.
5. First sacral nerve roots lie close to L5 disc as they pass inferolaterally.

Case Study 3

1. Pain referred from lower thoracic spine involving nerves T10, T11, T12.
2. Valveless veins linking pelvic venous plexuses, internal and external vertebral plexus, basivertebral veins.
3. Normal haemopoetic marrow in vertebrae replaced by metastatic tumour.

Case Study 4

1. In the subarachnoid space bathing spinal cord and brain, and in the ventricular system of brain.
2. By lumbar puncture with the vertebral column flexed to open the interval between vertebral arches.
3. Inferior to the conus medullaris between vertebrae L3/L4 or L4/L5. Skin, fascia, supra- and interspinous ligaments or ligamenta flava, extradural space, dura, arachnoid.
4. Neck movements stimulate reflex contraction of muscles because meningeal irritation by the subarachnoid bleeding increases sensitivity of dural receptors.

Alternative Terms

Eponyms

Achilles tendon	Tendo calcaneus
Adam's apple	Laryngeal prominence
Alcock's canal	Pudendal canal
Astley Cooper's ligaments (breast)	Suspensory ligaments of breast
Aschoff–Tawara node	Atrioventricular node
Bartholin's gland	Greater vestibular gland
Bell's nerve	Long thoracic nerve
Bigelow's ligament	Iliofemoral ligament
Buck's fascia	Deep fascia of penis
Camper's fascia	Fatty layer of subcutaneous tissue of abdominal wall
Cloquet's node	Deep inguinal node in femoral canal
Colles' fascia	Membranous layer of subcutaneous tissue of perineum
Cooper's fascia	Cremasteric fascia
Cooper's ligaments (breast)	Suspensory ligaments of breast
Cowper's glands	Bulbourethral glands
Denonvilliers' fascia	Rectovesical septum
Douglas, Line of	Arcuate line of rectus sheath
Douglas, Pouch of	Rectouterine pouch
Drummond, Marginal artery of	Marginal artery of colon
Dupuytren's fascia	Palmar aponeurosis
Eustachian tube	Auditory tube
Fallopian tube	Uterine tube
Galen, Vein of	Great cerebral vein
Gasserian ganglion	Trigeminal ganglion
Gimbernat's ligament	Lacunar ligament
Harvey's ligament	Ligamentum arteriosum
Highmore, Antrum of	Maxillary air sinus
His, Bundle of	Atrioventricular bundle
Houston's valve	Horizontal/transverse rectal fold
Hunter's canal	Adductor canal, subsartorial canal
Jacobson's nerve	Tympanic branch of glossopharyngeal nerve
Keith–Flack, Node of	Sinuatrial node
Koch's node	
Langerhans, islets of	Pancreatic islets
Langer's lines	Cleavage lines of skin
Lisfranc, Tubercle of	Scalene tubercle
Lister's tubercle	Dorsal tubercle of radius
Lockwood, Ligament of	Suspensory ligament part of vagina bulbi (of eyeball)
Louis, Angle of	Sternal angle
Marshall's vein	Oblique vein of left atrium
Meckel's cave	Trigeminal cave
Meckel's diverticulum	Ileal diverticulum
Meibomian glands	Tarsal glands
Morison, Pouch of	Hepatorenal recess
Müller's muscle	Smooth muscle component of levator palpebrae superioris
Nuck, Canal of	Processus vaginalis
Oddi, Sphincter of	Hepatopancreatic ampullary sphincter
Pacchionian bodies	Arachnoid granulations
Peyer's patches	Aggregated lymphoid nodules in ileum
Poupart's ligament	Inguinal ligament
Purkinje fibres	Cardiac conducting tissue
Retzius, Cave of	Retropubic space
Rosenmüller, Fossa of	Pharyngeal recess
Santorini's duct	Accessory pancreatic duct
Scarpa's fascia	Membranous layer of subcutaneous tissue of abdominal wall
Scarpa's triangle	Femoral triangle
Sibson's fascia	Suprapleural membrane
Spence, Tail of	Axillary tail of breast
Stensen's (Stenoni) duct	Parotid duct
Tenon's capsule	Vagina bulbi, Fascia bulbi (of eyeball)
Thebesian veins	Small cardiac veins
Vater, Ampulla of	Hepatopancreatic ampulla
Vidian nerve	Nerve of pterygoid canal
Waldeyer's ring	Pharyngeal lymphoid ring
Wharton's duct	Submandibular duct
Willis, Circle of	Cerebral arterial circle
Winslow, Foramen of	Omental or epiploic foramen
Wirsung, Duct of	Main pancreatic duct
Wrisberg, Ligament of	Meniscofemoral ligament

Older terms still used in clinical practice

Anterior primary ramus	Anterior ramus (of spinal nerve)
Auditory nerve	Vestibulocochlear nerve
Circumflex nerve	Axillary nerve
Common femoral artery	Femoral artery
Common peroneal nerve	Common fibular nerve
Costophrenic recess	Costodiaphragmatic recess
Dental nerves	Alveolar nerves
Descendens cervicalis	Inferior root of ansa cervicalis
Descendens hypoglossi	Superior root of ansa cervicalis

Dorsal nerve	Thoracic nerve
Dorsal vertebra	Thoracic vertebra
Innominate artery/vein	Brachiocephalic artery/vein
Innominate bone	Hip bone
Internal mammary artery	Internal thoracic artery
Ischiorectal fossa	Ischioanal fossa
Left anterior descending artery (LAD)	Anterior interventricular artery
Lesser sac	Omental bursa
Lienogastric ligament	Gastrosplenic ligament
Lienorenal ligament	Splenorenal ligament
Ligamentum teres	Round ligament
Lumbocostal arch	Arcuate ligament
Pelvic colon	Sigmoid colon

Peroneal artery	Fibular artery
Pharyngotympanic tube	Auditory tube
Posterior facial vein	Retromandibular vein
Posterior primary ramus	Posterior ramus (of spinal nerve)
Spiral groove	Radial groove (of humerus)
Sternocostalis	Transversus thoracis
Sternomastoid	Sternocleidomastoid
Subsartorial canal	Adductor canal
Superficial fascia	Subcutaneous tissue
Superficial femoral artery	Femoral artery
Supinator longus	Brachioradialis
Suprasternal notch	Jugular notch
Uterovesical pouch	Vesicouterine pouch

Contents

1 General Anatomy 1

Position of the Inner Organs, Palpable Points, and Regional Lines 2
Planes and Directions of the Body 4
Osteology 6
  Skeleton of the Human Body 6
  Bone Structure 8
  Ossification of the Bones 9
Arthrology 10
  Types of Joints 10
  Architecture of the Joint 12
Myology 13
  Shapes of Muscles 13
  Structure of the Muscular System 14
Comparative Imaging of Skeletal and Muscular Structures in MRI and X-Ray 15
Organization of the Circulatory System 16
Organization of the Lymphatic System 17
Organization of the Nervous System 18

2 Head and Neck 19

2.1 Skull 20

Bones of the Skull 21
Disarticulated Skull I 24
  Sphenoidal and Occipital Bones 24
  Temporal Bone 26
  Frontal Bone 28
Calvaria 29
Base of the Skull 30
Skull of the Newborn 35
Median Sections through the Skull 36
Disarticulated Skull II 38
  Ethmoidal Bone 38
  Ethmoidal and Palatine Bones 39
  Palatine Bone and Maxilla 40
  Sphenoidal, Ethmoidal, and Palatine Bones 43
  Maxilla, Zygomatic Bone, and Bony Palate 45
  Pterygopalatine Fossa and Orbit 46
  Orbit, and Nasal and Lacrimal Bones 47
Bones of the Nasal Cavity 48
Septum and Cartilages of the Nose 49
Maxilla and Mandible with Teeth 50
Deciduous and Permanent Teeth 51
Mandible and Dental Arch 52

2.2 Masticatory Apparatus and Muscles of the Head 53

Temporomandibular Joint 54
Ligaments of the Temporomandibular Joint 55
Temporomandibular Joint and Masticatory Muscles 56
Facial Muscles 60
Supra- and Infrahyoid Muscles 62
Section through the Cavities of the Head 64
Maxillary Artery 65

112897_S_I_XII_Titelei:_ 06.11.2014 9:05 Uhr Seite VIII

2 Head and Neck

2.3 Brain and Regions of the Head 66

Brain and Cranial Nerves 67
- Trochlear (N. IV), Facial (N. VII), Vestibulocochlear (N. VIII), Glossopharyngeal (N. IX), Vagus (N. X), Accessory (N. XI), and Hypoglossal (N. XII) Nerves 69
- Trigeminal Nerve (N. V) 70
- Facial Nerve (N. VII) 72
- Connection with the Brain Stem 73
- Optic (N. II), Oculomotor (N. III), Trochlear (N. IV), Ophthalmic (N. V_1), and Abducent (N. VI) Nerves 74
- Base of the Skull with Cranial Nerves 76

Regions of the Head 78
- Lateral Region 78
- Retromandibular Region 82
- Para- and Retropharyngeal Regions 85

2.4 Brain and Sensory Organs 86

Scalp and Meninges 87

Meninges 88
- Dura Mater and Dural Venous Sinuses 88
- Dura Mater 90
- Pia Mater and Arachnoid 91

Brain 92
- Median Sections 92
- Arteries and Veins 94
- Arteries 95
- Arteries and the Arterial Circle of Willis 100
- Cerebrum 101
- Cerebellum 104
- Dissections 106
- Limbic System 109
- Hypothalamus 110
- Subcortical Nuclei 111
- Ventricular System 114
- Brain Stem 116
- Coronal and Cross Sections 118
- Horizontal Sections 120

Auditory and Vestibular Apparatus 124
- Temporal Bone 127
- Middle Ear 128
- Auditory Ossicles 130
- Internal Ear 131
- Auditory Pathway and Areas 133

Visual Apparatus 134
- Orbit 134
- Lacrimal Apparatus and Lids 135
- Extra-ocular Muscles 136
- Layers of the Orbit 138
- Eye Accommodation 140
- Macula and Vessels of the Eye 141
- Visual Pathway and Areas 142

2.5 Nasal and Oral Cavities 145

Nasal Cavity 146
- Paranasal Sinuses 146
- Nerves and Arteries 148

Sections through the Nasal and Oral Cavities 150

Oral Cavity 152
- Hyoid Bone and Muscles 152
- Submandibular Triangle 154
- Salivary Glands 155

2.6 Neck and Organs of the Neck 156

Median Sections through the Head and Neck 157

Muscles of the Neck 158

Larynx 160
- Cartilages and Hyoid Bone 160
- Muscles 162
- Vocal Folds 163
- Nerves 164

Larynx and Oral Cavity 165

Pharynx 166
- Muscles 168

Vessels of the Head and Neck 170
- Arteries 170
- Arteries and Veins 172
- Veins 173
- Lymph Vessels and Nodes 174

Regions of the Neck 176
- Anterior Region 176
- Lateral Region 180



3 Trunk 189

Skeleton 190
Head and Vertebral Column 193
Joints Connecting to the Head 194
Cervical Vertebral Column 196
Vertebrae 198
Vertebral Joints 200
Thorax and Vertebral Column 201
Costovertebral Joints and Intercostal Muscles 204
Costovertebral Joints 205
Ligaments of the Vertebral Column 206
Surface Anatomy of the Anterior Body 208
Female 208
Male 209
Thoracic Wall 210
Thoracic and Abdominal Walls 212
Vessels and Nerves 218
Inguinal Region 221
Male 221
Female 224
Surface Anatomy of the Back 225
Back 226
Muscles 226
Nerves 230
Spinal Cord 234
Intercostal Nerves 236
Lumbar Plexus 237
Lumbar Part of the Vertebral Column and Spinal Cord 238
Vertebral Canal and Spinal Cord 240
Median Sections 241
Nuchal Region 242



4 Thoracic Organs 251

Position of the Thoracic Organs 252
Respiratory System 254
Bronchial Tree 254
Projections of Lungs and Pleura 256
Lungs 257
Bronchopulmonary Segments 258
Heart 260
Position of Heart and Related Vessels 260
Isolated Heart 262
Function 264
Valves 266
Direction of Blood Flow 268
Conducting System 269
Coronary Arteries 270
Fetal Circulatory System 272
Regional Anatomy of the Thoracic Organs 274
Internal Thoracic Vein and Artery 274
Anterior Mediastinum and Pleura 275
Thymus 276
Heart 278
Pericardium 282
Pericardium and Epicardium 283
Posterior Mediastinum 284
Mediastinal Organs 284
Diaphragm 292
Coronal Sections through the Thorax 294
Horizontal Sections through the Thorax 296
Mammary Gland 298



5 Abdominal Organs 299

- **Position of the Abdominal Organs** 300
- **Anterior Abdominal Wall** 301
- **Stomach** 302
- **Pancreas and Bile Ducts** 304
- **Liver** 307
- **Spleen** 309
- **Vessels of the Abdominal Organs** 310
  - Vessels of Upper Abdominal Organs and Small Intestine 310
  - Portal Circulation 313
  - Mesenteric Artery and Vein 314
  - Vessels of Retroperitoneal Organs 315
- **Dissection of the Abdominal Organs** 316
  - Colon, Cecum, and Vermiform Appendix 317
  - Mesentery, Duodenojejunal Flexure, and Ileocecal Valve 318
  - Upper Abdominal Organs 319
  - Lower Abdominal Organs 324
- **Posterior Abdominal Wall** 326
  - Pancreas and Bile Ducts 326
  - Pancreas, Bile Ducts, Spleen, and Liver 327
  - Root of the Mesentery and Peritoneal Recesses 328
- **Horizontal Sections through the Abdominal Cavity** 330
- **Midsagittal Sections through the Abdominal Cavity** 332



6 Retroperitoneal Organs 333

- **Position of the Urinary Organs** 334
- **Kidney** 336
  - Arteries 338
  - Arteries and Veins 339
- **Retroperitoneal Region** 340
  - Urinary System 340
  - Lymph Vessels and Nodes 342
  - Arteries 344
  - Vessels and Nerves 345
  - Autonomic Nervous System 346
- **Male Urogenital System** 348
- **Male Genital Organs (isolated)** 350
- **Male External Genital Organs** 352
  - Penis 354
- **Male Internal Genital Organs** 355
  - Testis and Epididymis 355
  - Accessory Glands 356
- **Pelvic Cavity in the Male** 357
  - Coronal Sections 357
  - Vessels of the Pelvic Organs 358
  - Vessels and Nerves of the Pelvic Organs 361
- **Urogenital and Anal Regions in the Male** 362
- **Female Urogenital System** 366
- **Female Genital Organs (isolated)** 368
- **Female Internal Genital Organs** 370
  - Uterus and Related Organs 371
  - Arteries and Lymph Vessels 372
- **Female External Genital Organs** 373
- **Inguinal Region and Female External Genital Organs** 374
- **Urogenital and Anal Regions in the Female** 375
- **Pelvic Cavity in the Female** 378
  - Coronal and Horizontal Sections 378

7 Upper Limb 380

Skeleton of the Shoulder Girdle and Thorax 381
Scapula and Clavicle 383
Skeleton of the Shoulder Girdle and Humerus 384
Humerus 385
Skeleton of the Forearm 386
Skeleton of the Forearm and Hand 387
Skeleton of the Hand 388
Joints and Ligaments of the Shoulder 390
Joints and Ligaments of the Elbow 391
Ligaments of the Hand and Wrist 392
Muscles of the Shoulder and Arm 394
  Dorsal Muscles 394
  Pectoral Muscles 396
Muscles of the Arm 398
Muscles of the Forearm and Hand 400
  Flexor Muscles 400
  Extensor Muscles 404
Muscles of the Hand 406
Arteries 408
Veins 410
Nerves 411
Surface Anatomy of the Upper Limb 413
  Posterior and Lateral Aspects 413
  Anterior Aspect 414
Neck and Shoulder 415
Shoulder 416
  Posterior Region 416
  Anterior Region 418
Shoulder and Arm 420
Axillary Region 422
Brachial Plexus 425
Arm 426
Cubital Region 428
Forearm and Hand 432
  Posterior Region 432
  Anterior Region 434
Hand 436
  Posterior Region 436
  Anterior Region 440
Sections through the Upper Limb 444

8 Lower Limb 446

Skeleton of the Pelvic Girdle and Lower Limb 447
Skeleton of the Pelvis 448
Bones of the Pelvis 452
Bones of the Hip Joint 454
Femur 455
Skeleton of the Leg 456
Bones of the Knee Joint 457
Skeleton of the Foot 458
Ligaments of the Pelvis and Hip Joint 460
Knee Joint 462
Ligaments of the Knee Joint 463
Joints of the Ankle 465
Ligaments of the Foot 466
Muscles of the Thigh 468
  Adductor Muscles 468
  Gluteal Muscles 470
  Flexor Muscles 471
Muscles of the Leg 473
  Flexor Muscles 473
Muscles of the Leg and Foot 474
  Deep Flexor Muscles 476
  Extensor Muscles 478
Muscles of the Foot 479
Arteries 482
Veins 484
Nerves 486
  Lumbosacral Plexus 487
Surface Anatomy of the Lower Limb 488
  Posterior Aspect 488
  Anterior Aspect 489
Thigh 490
  Anterior Region 490
Gluteal Region 494
Thigh 496
  Posterior Region 496
Knee and Popliteal Fossa 498
Crural Region 501
Crural Region and Foot 504
Foot 507
  Posterior Region 507
  Anterior Region 510
Sections through the Lower Limb 514

Index 517

1 General Anatomy

Position of the Inner Organs, Palpable Points, and Regional Lines 2
Planes and Directions of the Body 4
Osteology 6
Arthrology 10
Myology 13
Comparative Imaging of Skeletal and Muscular Structures in MRI and X-Ray 15
Organization of the Circulatory System 16
Organization of the Lymphatic System 17
Organization of the Nervous System 18

Position of the Inner Organs, Palpable Points, and Regional Lines



Position of the inner organs of the human body (anterior aspect). The main cavities of the body and their contents.



Regional lines and palpable points at the ventral side of the human body.

Regional lines

A = Parasternal line
B = Midclavicular line
C = Anterior axillary line
D = Umbilical-pelvic line

The bones of the skeletal system are palpable through the skin at different points. This enables physicians to localize the inner organs. On the **ventral side,** the clavicle, sternum, ribs, and intercostal spaces are palpable. Furthermore, the anterior iliac spine and the symphysis can be localized. For better orientation, several **lines of orientation** are used, e.g., the parasternal line, the midclavicular line, the anterior axillary line, the umbilical-pelvic line.

By means of these lines, the heart and the position of the vermiform process can be localized.



Position of the inner organs of the human body (posterior aspect).



Regional lines and palpable points at the dorsal side of the human body.

Regional lines
E = Paravertebral line
F = Scapular line
G = Posterior axillary line
H = Iliac crest

1	Brain
2	Lung
3	Diaphragm
4	Heart
5	Liver
6	Stomach
7	Colon
8	Small intestine
9	Testis
10	Kidney
11	Ureter
12	Anal canal
13	Clavicle
14	Manubrium sterni
15	Costal arch
16	Umbilicus
17	Anterior superior iliac spine
18	Inguinal ligament
19	Scapular spine
20	Spinous processes
21	Iliac crest
22	Coccyx and sacrum

At the **dorsal side** of the body, the posterior spines of the vertebral column, the ribs, the scapula, the sacrum, and the iliac crest are palpable. **Lines of orientation** are the paravertebral line, the scapular line, the posterior axillary line, and the iliac crest.



Planes of the body:
A = Horizontal or axial or transverse plane
B = Sagittal plane (at the level of the knee joint)

Directions:
1 = Cranial
2 = Caudal
3 = Anterior (ventral)
4 = Posterior (dorsal)



Horizontal section through the pelvic cavity and the hip joints.



MRI scan through the pelvic cavity and the hip joints (horizontal or axial or transverse plane).



Sagittal section through the knee joint.



MRI scan through the knee joint (sagittal plane).



Planes of the body:
A = Midsagittal or median plane
B = Frontal or coronal plane (through the pelvic cavity)

Directions:

1 = Posterior (dorsal)
2 = Anterior (ventral)
3 = Lateral
4 = Medial
5 = Cranial
6 = Caudal



MRI scan through the pelvic cavity and the hip joints (frontal or coronal plane).



Median section through the trunk of a female.


1
4
5
7
6
8
19
15
16
17
18
14
22
12
23
13
28
24
30
25
26
31
34
32
33
35
36
37

Skeleton of a female adult (anterior aspect).


3
2
8
9
20
10
16
21
23
11
27
12
22
13
30
29
31
31
33
32
38

Skeleton of a female adult (posterior aspect).



Skeleton of a 5-year-old child (anterior aspect).
The zones of the cartilaginous growth plates are seen (arrows). In contrast to the adult, the ribs show a predominantly horizontal position.

Axial skeleton

Head

1	Frontal bone
2	Occipital bone
3	Parietal bone
4	Orbit
5	Nasal cavity
6	Maxilla
7	Zygomatic bone
8	Mandible

Trunk and thorax

Vertebral column

9	Cervical vertebrae
10	Thoracic vertebrae
11	Lumbar vertebrae
12	Sacrum
13	Coccyx
14	Intervertebral discs

Thorax

15	Sternum
16	Ribs
17	Costal cartilage
18	Infrasternal angle

Appendicular skeleton

Upper limb and shoulder girdle

19	Clavicle
20	Scapula
21	Humerus
22	Radius
23	Ulna
24	Carpal bones
25	Metacarpal bones
26	Phalanges of the hand

Lower limb and pelvis

27	Ilium
28	Pubis
29	Ischium
30	Symphysis pubis
31	Femur
32	Tibia
33	Fibula
34	Patella
35	Tarsal bones
36	Metatarsal bones
37	Phalanges of the foot
38	Calcaneus





MRI scan of the right femur and hip joint (coronal section). (From Heuck et al., MRT-Atlas, 2009.)



X-ray of the right femur and hip joint (a.-p. direction).

◁ **Femur of the adult.** Coronal section of the proximal and distal epiphyses displaying the spongy bone and the medullary cavity.

1 Head of the femur
2 Spongy bone
3 Diaphysis of the femur
4 Compact bone
5 Articular cartilage



Three-dimensional representation on the trajectorial lines of the femoral head.



Coronal section through the proximal end of the adult femur showing the characteristic structure of the spongy bone.

112897_S_001_018_Kap_1:_ 06.11.2014 8:47 Uhr Seite 9

The **ossification of the bones** of the limbs starts within the ossification centers of the primary cartilagenous bones. Here, the medullary cavity develops. The ossification process of limb bones is not finished at birth.



Ossification of the femur (left: coronal section, right: posterior aspect of the femur). Arrows: distal epiphysis.

◁

1	Ossification center in the head of the femur	5	Lateral condyle
2	Greater trochanter	6	Medial condyle
3	Head of the femur	7	Intercondylar notch
4	Neck of the femur	8	Diaphysis



X-ray of the upper and lower limb of a newborn child (left: upper limb, right: lower limb). Arrows: ossification centers.

1	Scapula	6	Radius
2	Shoulder joint	7	Tibia
3	Humerus	8	Fibula
4	Elbow joint	9	Knee joint
5	Ulna	10	Femur



◁

1	Ulna	6	Fibula
2	Radius	7	Talus
3	Metacarpal bones	8	Calcaneus
4	Phalanges	9	Metatarsal bones
5	Tibia	10	Phalanges

X-ray of hand and foot of a newborn.



Skeleton of the arm and shoulder girdle (anterior aspect).



Shoulder joint as an example of a multiaxial ball-and-socket joint (coronal section).



Ball-and-socket joint with its different axes. Arrows: axes of movement.

1 Humerus
2 Radius
3 Ulna
4 Articular cavity (shoulder joint)
5 Metacarpophalangeal joint
6 Joints of fingers



Elbow joint with ligaments as an example of a hinge joint (monaxial humero-ulnar joint) in combination with a pivot joint (monaxial radio-ulnar joint), which allows rotation.



Coronal section through the elbow joint (MRI scan). (Courtesy of Prof. Heuck, Munich, Germany.) The possibilities of movement are shown in the schematic drawings on page 11.



Coronal section through the shoulder joint (MRI scan).
(From Heuck et al., MRT-Atlas, 2009.)



Hinge joint
(e.g., humero-ulnar joint). Left: extension, right: flexion.
Arrows: axes of movement.



Pivot joint
(e.g., radio-ulnar joint).



Saddle joint
(e.g., carpometacarpal joint of the thumb).



Skeleton of right wrist and hand (medial aspect). The metacarpophalangeal joints are biaxial, as is the carpometacarpal joint of the thumb (✻ in the figure). The joints of the fingers, however, are monaxial.

Joints exhibit a variety of functions. In general, mobility becomes reduced in the direction from proximal to distal. The hip joint, e.g., is multiaxial; the knee joint is biaxial, and the joints of toes and fingers are monaxial.



Coronal section through the knee joint (anterior aspect of the right joint in extension).



Coronal section through the knee joint (MRI scan). (From Heuck et al., MRT-Atlas, 2009.)

1 Femur
2 Tibia
3 Fibula
4 Cruciate ligaments
5 Collateral ligaments
6 Meniscus

Joints are places of articulation allowing movements between bones. Synovial joints are characterized by a joint cavity enclosed by a joint capsule containing synovial fluid, which is produced by the articular capsule. The kind of movements depends not only on form and structure of the articulating bones but also on ligaments incorporated into the articular capsule. In some synovial joints, fibrocartilagenous articular discs develop, when the articulating surfaces of the bones are incongruous.



Schematic drawing of the knee joint as an example of a synovial joint, characterized by a joint cavity enclosed by a joint capsule (red) containing synovial fluid. Blue = articular cartilage.



Fusiform
(palmaris longus)

Bicipital
(biceps brachii)

Tricipital (triceps surae,
gastrocnemius, and soleus)

Quadricipital
(quadriceps femoris)



Digastric
(omohyoideus)

Multiventral
(rectus abdominis)

Multicaudal
(flexor digitorum prof.)

Serrated
(serratus anterior)



Bipennate
(tibialis anterior)

Unipennate
(semimembranosus)

Semitendinous
(semitendinosus)

Broad, flat muscle
(latissimus dorsi)

Ring-like
(sphincter ani externus)

The human body possesses **a great variety of muscles.** The architecture of the muscles depends on the functional systems in which they are involved, i.e., the kind of movements, the form of the joints with their specific ligaments, etc. The movements themselves vary to a great extent individually.



Ventral aspect of the right arm. The biceps muscle appears slightly contracted. In the area of the elbow joint, several subcutaneous veins can be recognized.



Diagram illustrating the position of the flexor and extensor muscles of the arm and their effect on the elbow joint.
A: axis of humero-ulnar joint; arrows: direction of movements; red = flexion; black = extension.



Synovial sheaths of flexor tendons (palmar aspect of the right hand). The flexor retinaculum protects the flexor tendons passing through the carpal tunnel (arrow).

1 Deltoid muscle
2 Biceps brachii muscle
3 Brachioradialis muscle
4 Humerus
5 Triceps brachii muscle
6 Elbow joint
7 Brachialis muscle
8 Pectoralis major muscle
9 Radius
10 Ulna

Joints are moved by muscles. The highly differentiated movements are coordinated by special groups of muscles (**synergists**). Their counterparts are called **antagonists**. Movements can only be carried out harmoniously if the contraction of the synergists are supported by a corresponding dilatation of the antagonists. This interaction is controlled by the nervous system. In order to carry out certain directions of movements, often the tendons of muscles have to be directed by ligaments. At those places, the tendons often develop synovial sheaths, e.g., at the wrist joint or at the fingers.



Frontal section through the shoulder joint (MRI scan). (From Heuck et al., MRT-Atlas, 2009.)



Frontal section through the shoulder joint (X-ray, a.-p. direction). (Courtesy of Dr. Holik, Spardorf, Germany.)

1 Trapezius muscle
2 Supraspinatus muscle
3 Scapula
4 Acromion
5 Head of humerus
6 Deltoid muscle
7 Cavity of shoulder joint
8 Articular cartilage
9 Articular cavity
10 Humerus



Frontal section through the shoulder joint (schematic drawing of the MRI scan above).



Frontal section through the shoulder joint (compare with the two pictures above).



Heart and related vessels in situ (anterior aspect). Anterior thoracic wall, pericardium, and epicardium have been removed. The trachea is divided.

1 Aorta
2 Pulmonary artery
3 Right heart
4 Left heart
5 Diaphragm
6 Abdominal aorta



Organization of the circulatory system with the heart in the center (anterior aspect).
Red = arteries; blue = veins.



Organization of the circulatory systems in the human body.
The center of this system represents the heart.
Red = arteries; blue = veins.

A = Pulmonary circulation
B = Systemic circulation
C = Portal circulation
D = Lymphatic circulation

The center of the circulatory system is the heart, which is situated in the thoracic cavity and in contact with the diaphragm. In the right ventricle, the venous blood is collected and pumped through the pulmonary artery and into the lung where the blood is oxygenated. The veins of the lung transport the blood to the left ventricle, where it is pumped through the aorta and its branches (arteries) in the human body. Arteries and veins mostly run parallel. The venous blood from the intestine reaches the liver via the portal vein.



Organization of the lymphatic system (anterior aspect). Course of the main lymphatic vessels and location of the most important lymph nodes in the body. Red line = border between the lymphatic vessels draining to the left and right venous angles.



Major lymph vessels of the trunk (green). Blue = veins, red = arteries, white = nerves.

1	Tonsils and submandibular lymph nodes	8	Spleen
2	Right venous angle	9	Lymph nodes of the intestinal tract
3	Remnants of the thymus gland	10	Inguinal lymph nodes
4	Thoracic duct	11	Bone marrow
5	Cisterna chyli	12	Lymph nodes of the popliteal fossa
6	Left venous angle	13	Aorta
7	Axillary lymph nodes	14	Left kidney

Lymphatic vessels originate in the tissue spaces (lymph capillaries) and unite to form larger vessels (lymphatics). These resemble veins but have a much thinner wall, more valves, and are interrupted by lymph nodes at various intervals. Large groups of lymph nodes are located in the inguinal and axillary regions, deep to the mandible and sternocleidomastoid muscle, and within the root of the mesentery of the intestine. The lymphatic vessels of the right half of the head and neck, the right thorax, and the right upper limb drain toward the right venous angle; those of the rest of the body, toward the left venous angle.



Diagram illustrating the localization of the three functional portions of the nervous system (brain, spinal cord and autonomic nervous system). Yellow = sympathetic system; red = parasympathetic system.



Posterior part of the trunk. The **solar plexus** with its connection to the vagus nerve and the sympathetic trunk has been dissected.

1 Cerebrum
2 Cranial nerves
3 Spinal nerves
4 Sympathetic trunk
5 Solar plexus
6 Nervous plexus of the autonomic system
7 Aorta
8 Vagus nerve and esophagus
9 Bifurcation of trachea

The nervous system can be divided into three functionally distinct parts:

1. The cranial part, which comprises the great sensory organs and the brain.
2. The spinal cord, which shows a segmental structure and serves predominantly as a reflex organ.
3. The autonomic nervous system, which controls the involuntary functions (subconscious control) of organs and tissues. The autonomic part of the nervous system forms many delicate plexuses near or within the organs. At certain places these plexuses contain aggregations of nerve cells (prevertebral and intramural ganglia).

The spinal nerves leave the spinal cord at regular intervals. The ventral rami of the spinal nerves form the cervical and brachial plexus, which innervates the upper extremity, and the ventral rami of the lumbar and sacral spinal nerves form the lumbosacral plexus, which innervates the pelvis and genital organs and the lower extremity.

2 Head and Neck

2.1 Skull 20

Bones of the Skull 21
Disarticulated Skull I 24
Calvaria 29
Base of the Skull 30
Skull of the Newborn 35
Median Sections through the Skull 36
Disarticulated Skull II 38
Bones of the Nasal Cavity 48
Septum and Cartilages of the Nose 49
Maxilla and Mandible with Teeth 50
Deciduous and Permanent Teeth 51
Mandible and Dental Arch 52

2.2 Masticatory Apparatus and Muscles of the Head 53

Temporomandibular Joint 54
Ligaments of the Temporomandibular Joint 55
Temporomandibular Joint
  and Masticatory Muscles 56
Facial Muscles 60
Supra- and Infrahyoid Muscles 62
Section through the Cavities of the Head 64
Maxillary Artery 65

2.3 Brain and Regions of the Head 66

Brain and Cranial Nerves 67
Regions of the Head 78

2.4 Brain and Sensory Organs 86

Scalp and Meninges 87
Meninges 88
Brain 92
Auditory and Vestibular Apparatus 124
Visual Apparatus 134

2.5 Nasal and Oral Cavities 145

Nasal Cavity 146
Sections through the Nasal and Oral Cavities 150
Oral Cavity 152

2.6 Neck and Organs of the Neck 156

Median Sections through the Head and Neck 157
Muscles of the Neck 158
Larynx 160
Larynx and Oral Cavity 165
Pharynx 166
Vessels of the Head and Neck 170
Regions of the Neck 176



2.1 Skull



General architecture of the skull (lateral aspect). The different bones are indicated in color (compare with the table).

1	Coronal suture
2	Frontal bone
3	Sphenoidal bone
4	Sphenofrontal suture
5	Ethmoidal bone
6	Nasal bone
7	Nasomaxillary suture
8	Lacrimal bone
9	Lacrimomaxillary suture
10	Ethmoidolacrimal suture
11	Zygomatic bone
12	Anterior nasal spine
13	Maxilla
14	Mandible
15	Mental foramen
16	Mental protuberance
17	Superior temporal line
18	Inferior temporal line
19	Parietal bone
20	Temporal bone
21	Squamous suture
22	Lambdoid suture
23	Temporal fossa
24	Parietomastoid suture
25	Occipital bone
26	Zygomatic arch
27	Occipitomastoid suture
28	External acoustic meatus
29	Mastoid process
30	Tympanic portion of temporal bone
31	Condylar process of mandible
32	Coronoid process of mandible



Disarticulated skull (lateral aspect). The facial bones are blue colored. Red line = angle of the clivus.

2	Frontal bone (orange)	**Cranial bones**
19	Parietal bone (light yellow)	
3	Greater wing of sphenoidal bone (red)	
25	Squama of occipital bone (blue)	
20	Squama of temporal bone (brown)	
5	Ethmoidal bone (dark green)	**Base of skull**
3	Sphenoidal bone (red)	
	Temporal bone excluding squama (brown)	
30	Tympanic portion of temporal bone (dark brown)	
	Occipital bone excluding squama (blue)	
6	Nasal bone (white)	**Facial bones**
8	Lacrimal bone (light yellow)	
	Inferior nasal concha	
	Vomer	
11	Zygomatic bone (dark yellow)	
	Palatine bone	
13	Maxilla (violet)	
14	Mandible (white)	
	Malleus Incus Stapes } within petrous portion of temporal bone	**Auditory ossicles**
	Hyoid	



Lateral aspect of the skull.

1 Frontal bone
2 Glabella
3 Supraorbital margin
4 Parietal bone
5 Temporal bone (squamous part)
6 Zygomatic process (articular tubercle)
7 Mastoid process
8 Tympanic part (tympanic plate) and external acoustic meatus
9 Occipital bone (squamous part)
10 External occipital protuberance
11 Occipital condyle
12 Sphenoidal bone (greater wing)
13 Infratemporal crest of sphenoid
14 Pterygoid process (lateral pterygoid plate)
15 Nasal bone
16 Ethmoidal bone (orbital part)
17 Lacrimal bone
18 Zygomatic bone
19 Maxilla (body)
20 Alveolar process and teeth
21 Frontal process
22 Anterior nasal spine
23 Mandible (body)
24 Coronoid process
25 Condylar process
26 Mental foramen
27 Mental protuberance
28 Angle of the mandible

Sutures

29 Coronal suture
30 Lambdoid suture
31 Squamous suture
32 Nasomaxillary suture
33 Frontosphenoid suture
34 Sphenosquamosal suture
35 Occipitomastoid suture



Anterior aspect of the skull.

1	Frontal bone
2	Glabella
3	Supra-orbital margin
4	Supra-orbital notch
5	Trochlear spine
6	Parietal bone
7	Temporal bone
8	Nasal bone

Orbit

9	Lacrimal bone
10	Posterior lacrimal crest
11	Ethmoidal bone

Sphenoidal bone

12	Greater wing of sphenoidal bone
13	Lesser wing of sphenoidal bone
14	Superior orbital fissure
15	Inferior orbital fissure
16	Zygomatic bone

Maxilla

17	Frontal process
18	Infra-orbital foramen
19	Zygomatic process
20	Body of maxilla
21	Alveolar process with teeth

Nasal cavity

22	Anterior nasal aperture
23	Middle nasal concha
24	Inferior nasal concha
25	Nasal septum, vomer

Mandible

26	Body of mandible
27	Ramus of mandible
28	Mental foramen
29	Alveolar part with teeth
30	Base of mandible
31	Mental protuberance

Sutures

32	Frontal suture
33	Coronal suture
34	Frontonasal suture
35	Internasal suture
36	Nasomaxillary suture
37	Zygomaticomaxillary suture
38	Intermaxillary suture

The skull comprises a mosaic of numerous complicated bones that form the cranial cavity protecting the brain **(neurocranium)** and several cavities such as the nasal and oral cavities in the facial region. The neurocranium consists of large bony plates that develop directly from the surrounding sheets of connective tissue **(desmocranium).** The bones of the skull base are formed out of cartilaginous tissue **(chondrocranium),** which ossifies secondarily. The **visceral skeleton,** which in fish gives rise to the gills, has in higher vertebrates been transformed into the bones of the masticatory and auditory apparatus (maxilla, mandible, auditory ossicles, and hyoid bone).

112897_S_019_052_Kap_2_1:_ 06.11.2014 8:50 Uhr Seite 23



Anterior aspect of the skull (individual bones indicated by color).

1 Frontal bone
2 Frontonasal suture
3 Frontomaxillary suture
4 Supra-orbital margin
5 Internasal suture
6 Sphenofrontal suture
7 Optic canal in lesser wing of sphenoidal bone
8 Superior orbital fissure
9 Lacrimal bone
10 Sphenoidal bone (greater wing)
11 Inferior orbital fissure
12 Nasomaxillary suture
13 Infra-orbital foramen
14 Maxilla
15 Vomer
16 Body of mandible
17 Parietal bone
18 Temporal bone
19 Sphenozygomatic suture
20 Ethmoidal bone
21 Zygomatic bone
22 Nasal bone
23 Zygomaticomaxillary suture
24 Middle nasal concha
25 Inferior nasal concha
26 Anterior nasal aperture
27 Mental foramen
28 Ramus of mandible
29 Base of mandible
30 Mental protuberance

Bones
Brown = frontal bone
Light green = parietal bone
Dark brown = temporal bone
Red = sphenoidal bone
Yellow = zygomatic bone
Dark green = ethmoidal bone
Yellow = lacrimal bone
Orange = vomer
Violet = maxilla
White = nasal bone
White = mandible

The following series of figures are arranged so that the mosaic-like pattern of the skull becomes understandable. It starts with the bones of the **skull base** (sphenoidal and occipital bones) to which the other bones are added step by step. The facial skeleton is built up by the ethmoidal bone to which the palatine bone and maxilla are attached laterally; the small nasal and lacrimal bones fill the remaining spaces. Cartilages remain only in the external part of the nose.


1
2
3
4
5
6
7
8
27
28
29
30
31
9
10
11
14
12
32
34
35
36
37

Sphenoidal and occipital bones (from above).


8
5
25
11
26
16
22
38
39
40
41
42
43

Sphenoidal and occipital bones in connection with the atlas and axis (first and second cervical vertebrae) (left lateral view).

Sphenoidal bone

1 Greater wing
2 Lesser wing
3 Cerebral or superior surface of greater wing
4 Foramen rotundum
5 Anterior clinoid process
6 Foramen ovale
7 Foramen spinosum
8 Dorsum sellae
9 Optic canal
10 Chiasmatic groove (sulcus chiasmatis)
11 Hypophysial fossa (sella turcica)
12 Lingula
13 Opening of sphenoidal sinus
14 Posterior clinoid process
15 Pterygoid canal
16 Lateral pterygoid plate of pterygoid process
17 Pterygoid notch
18 Pterygoid hamulus
19 Orbital surface of greater wing
20 Sphenoidal crest
21 Sphenoidal rostrum
22 Medial pterygoid plate
23 Superior orbital fissure
24 Spine of sphenoid
25 Temporal surface of greater wing
26 Infratemporal crest

Occipital bone

27 Clivus with basilar part of occipital bone
28 Hypoglossal canal
29 Fossa for cerebellar hemisphere
30 Internal occipital protuberance
31 Fossa for cerebral hemisphere
32 Jugular tubercle
33 Condylar canal
34 Jugular process
35 Foramen magnum
36 Groove for transverse sinus
37 Groove for superior sagittal sinus
38 Squamous part of the occipital bone
39 External occipital protuberance
40 Superior nuchal line
41 Inferior nuchal line
42 Condylar fossa
43 Condyle
44 Pharyngeal tubercle
45 External occipital crest



Sphenoidal bone (anterior aspect).



Sphenoidal bone (posterior aspect).



Occipital bone (from below).


1
25
2
3
4
5
19
18
20
21
6
22
54
57
11
7
8
9
10
48
49
50
24
51
52
56
53
55

Sphenoidal, occipital, and left temporal bones (from above). Internal aspect of the base of the skull. The left temporal bone has been added to the preceding figure.

Sphenoidal bone

1	Greater wing
2	Lesser wing
3	Foramen rotundum
4	Foramen ovale
5	Foramen spinosum
6	Foramen lacerum
7	Anterior clinoid process
8	Hypophysial fossa (sella turcica)
9	Lingula
10	Dorsum sellae and posterior clinoid process
11	Optic canal
12	Sphenoidal rostrum
13	Medial pterygoid plate
14	Lateral pterygoid plate
15	Pterygoid hamulus
16	Infratemporal crest
17	Body of the sphenoidal bone


37
18
36
21
46
47
22
23
39
38
44
42
24
40
41

Left temporal bone (medial aspect).


37
25
18
47
34
36
42
21
24

Left temporal bone (from above).



Sphenoidal, occipital, and left temporal bones. Base of the skull (external aspect).



Left temporal bone (lateral aspect).

Temporal bone

18 Squamous part
19 Carotid canal
20 Hiatus of facial canal (for the greater petrosal nerve)
21 Arcuate eminence
22 Groove for the sigmoid sinus
23 Mastoid foramen
24 Internal acoustic meatus
25 Zygomatic process
26 Mandibular fossa
27 Petrotympanic fissure
28 Canalis musculotubarius (bony part of auditory tube)
29 External acoustic meatus
30 Styloid process (remnant only)
31 Stylomastoid foramen
32 Mastoid canaliculus
33 Jugular fossa
34 Mastoid process
35 Mastoid notch
36 Groove for middle meningeal vessels
37 Parietal margin
38 Sphenoidal margin
39 Occipital margin
40 Cochlear canaliculus
41 Aqueduct of the vestibule
42 Apex of the petrous part
43 Tympanic part
44 Trigeminal impression
45 Articular tubercle
46 Parietal notch
47 Groove for the superior petrosal sinus

Occipital bone

48 Clivus
49 Jugular tubercle
50 Condylar canal
51 Foramen magnum
52 Lower part of squamous occipital bone (cerebellar fossa)
53 Internal occipital protuberance
54 Groove for the transverse sinus
55 Groove for the superior sagittal sinus
56 Internal occipital crest
57 Upper part of squamous occipital bone (cerebral fossa)
58 Condyle
59 Nuchal plane
60 Superior nuchal line
61 External occipital protuberance
62 Jugular foramen
63 Inferior nuchal line
64 Pharyngeal tubercle
65 Spheno-occipital synchondrosis

Disarticulated Skull I: Frontal Bone



Part of a disarticulated skull (right lateral aspect). The frontal bone and the maxilla are connected with the temporal bone by the zygomatic bone (orange). Sphenoidal bone (black), palatine bone (red), lacrimal bone (yellow).



Frontal bone (inferior aspect). The ethmoidal foveolae cover the ethmoidal cavities of the ethmoidal bone.



Frontal bone (posterior aspect).

Frontal bone

1	Nasal margin
2	Trochlear fossa
3	Fossa for lacrimal gland
4	Anterior ethmoidal foramen
5	Posterior ethmoidal foramen
6	Nasal spine
7	Supra-orbital notch
8	Supra-orbital margin
9	Orbital plate
10	Roofs of the ethmoidal air cells
11	Ethmoidal notch
12	Parietal margin
13	Groove for superior sagittal sinus
14	Squamous part of frontal bone
15	Frontal crest
16	Foramen cecum
17	Nasal spine
18	Zygomatic process of frontal bone
19	Juga cerebralia

Facial bones

20	Maxilla
21	Frontal process of maxilla
22	Lacrimal bone (yellow)
23	Zygomatic bone (orange)
24	Zygomaticofacial foramen

Temporal bone

25	Squamous part of temporal bone
26	External acoustic meatus
27	Mastoid process
28	Styloid process
29	Mandibular fossa
30	Articular tubercle
31	Zygomatic process

Occipital bone

32	Squamous part of occipital bone



Calvaria (superior aspect).



Calvaria (posterior aspect).



Left parietal bone (external aspect).



Left parietal bone (internal aspect).

1 Frontal bone
2 Coronal suture
3 Sagittal suture
4 Parietal bone
5 Superior temporal line
6 Parietal foramen
7 Parietal tuber or eminence
8 Sagittal margin
9 Occipital margin
10 Frontal margin
11 Squamous margin
12 Sphenoidal angle
13 Groove for middle meningeal artery
14 Lambdoid suture
15 Occipital bone
16 External occipital protuberance
17 Inferior nuchal line
18 Occipitomastoid suture
19 Temporal bone
20 Mastoid process
21 Mastoid notch

Base of the Skull



Base of the skull, calvaria removed (internal aspect).

1 Frontal crest
2 Foramen cecum
3 Crista galli
4 Cribriform plate of ethmoidal bone
5 Lesser wing of sphenoidal bone
6 Superior orbital fissure
7 Foramen rotundum
8 Carotid sulcus
9 Middle cranial fossa
10 Foramen ovale
11 Foramen spinosum
12 Clivus
13 Groove for superior petrosal sinus
14 Jugular foramen
15 Groove for sigmoid sinus
16 Internal occipital crest
17 Groove for transverse sinus
18 Internal occipital protuberance
19 Digitate impressions
20 Anterior cranial fossa
21 Chiasmatic sulcus
22 Anterior clinoid process
23 Optic canal
24 Sella turcica (hypophysial fossa)
25 Posterior clinoid process
26 Dorsum sellae
27 Foramen lacerum
28 Groove for greater petrosal nerve
29 Internal acoustic meatus
30 Hypoglossal canal
31 Foramen magnum
32 Posterior cranial fossa
33 Diploe



1 Olfactory bulb
2 Optic nerve (n. II)
3 Ophthalmic nerve (n. V_1)
4 Maxillary nerve (n. V_2)
5 Mandibular nerve (n. V_3)
6 Trigeminal nerve (n. V) with trigeminal ganglion
7 Facial nerve (n. VII) and vestibulocochlear nerve (n. VIII)
8 Glossopharyngeal nerve (n. IX), vagus nerve (n. X) and accessory nerve (n. XI)
9 Anterior meningeal artery
10 Internal carotid artery
11 Oculomotor nerve (n. III) and trochlear nerve (n. IV)
12 Abducent nerve (n. VI)
13 Middle meningeal artery and meningeal branch of mandibular nerve
14 Greater and lesser petrosal nerves
15 Basilar artery
16 Vertebral artery
17 Posterior meningeal artery and recurrent meningeal nerve
18 Hypoglossal nerve (n. XII)
19 Medulla oblongata

Base of the skull with cranial nerves and meningeal arteries (internal aspect).

	Cranial nerves and vessels	Related foramina	Related regions
Anterior cranial fossa	Olfactory nerves (n. I), Anterior ethmoidal artery, vein, and nerve, Anterior meningeal artery	Lamina cribrosa	Nasal cavity
Middle cranial fossa	Optic nerve (n. II), Ophthalmic artery	Optic canal	Orbit
	Oculomotor nerve (n. III), Trochlear nerve (n. IV), Abducent nerve (n. VI), Ophthalmic nerve (n. V_1), Superior ophthalmic vein	Superior orbital fissure	Orbit
	Maxillary nerve (n. V_2)	Foramen rotundum	Pterygopalatine fossa
	Mandibular nerve (n. V_3)	Foramen ovale	Infratemporal fossa
	Middle meningeal artery, Meningeal branch of mandibular nerve (n. V_3)	Foramen spinosum	Infratemporal fossa
	Internal carotid artery	Carotid canal	Cavernous sinus, Base of skull
Posterior cranial fossa	Facial nerve (n. VII), Vestibulocochlear nerve (n. VIII), Artery and vein of the labyrinth	Internal acoustic meatus, Stylomastoid foramen, Facial canal	Inner ear, Face
	Glossopharyngeal nerve (n. IX), Vagus nerve (n. X), Accessory nerve (n. XI), Internal jugular vein, Posterior meningeal artery	Jugular foramen	Parapharyngeal region
	Hypoglossal nerve (n. XII)	Hypoglossal canal	Tongue
	Accessory nerve (n. XI, spinal root), Vertebral arteries, Anterior and posterior spinal arteries, Medulla oblongata	Foramen magnum	Base of skull


1
2
3
4
5
6
7
8
10
12
13
14
16
17
18
19
20
21
22
23
25
9
11
24
15
27
29
30
28
26

Base of the skull (inferior aspect).



Base of the skull (from below). The individual bones are indicated by different colors.



Skull of the newborn (inferior aspect).

A = **Pterygoid canal**
B = **Foramen ovale**
C = Internal carotid artery within **carotid canal** and internal jugular vein within the venous part of jugular foramen
D = **Stylomastoid foramen** (facial nerve)
E = **Jugular foramen** (glossopharyngeal, vagus and accessory nerves)
F = **Hypoglossal canal** (hypoglossal nerve)

1 Incisive canal
2 Median palatine suture
3 Palatine process of maxilla
4 Palatomaxillary suture
5 Greater and lesser palatine foramina
6 Inferior orbital fissure
7 Middle concha (process of ethmoidal bone)
8 Vomer
9 Foramen ovale
10 Groove for auditory tube
11 Pterygoid canal
12 Styloid process
13 Carotid canal
14 Stylomastoid foramen
15 Jugular foramen
16 Groove for occipital artery
17 Occipital condyle
18 Condylar canal
19 Nuchal plane
20 External occipital protuberance
21 Zygomatic arch
22 Lateral pterygoid plate
23 Medial pterygoid plate
24 Mandibular fossa
25 Pharyngeal tubercle
26 Superior nuchal line
27 Mastoid process
28 Inferior nuchal line
29 Mastoid notch
30 Foramen magnum
31 Incisive bone or premaxilla (dark violet)
32 Maxilla (violet)
33 Palatine bone (white)
34 Vomer (orange)
35 Sphenoidal bone (red)
36 Zygomatic bone (yellow)
37 Temporal bone (brown)
38 Occipital bone (blue)
39 Palatine process of maxilla
40 Vomer
41 Sphenoidal bone
42 Petrous part of temporal bone
43 Basilar part
44 Lateral part } of occipital bone
45 Squamous part
46 Mandible
47 Zygomatic arch
48 Choana
49 Pterygoid process of sphenoidal bone
50 Carotid canal
51 External acoustic meatus (tympanic anulus)
52 Sphenoidal fontanelle
53 Parietal bone
54 Mastoid fontanelle



Base of the skull (internal aspect, oblique-lateral view from left side).



Canals, fissures, and foramina of the base of the skull

1 Superior orbital fissure
2 Foramen rotundum
3 Optic canal
4 Foramen ovale
5 Foramen spinosum
6 Internal acoustic meatus
7 Jugular foramen
8 Foramen magnum

Bones

9 Frontal bone (orange)
10 Ethmoidal bone (dark green)
11 Sphenoidal bone (red)
12 Temporal bone (brown)
13 Parietal bone (yellow)
14 Occipital bone (blue)

Details of bones

15 Crista galli
16 Cribriform plate
17 Digitate impressions (frontal bone)
18 Lesser wing of sphenoidal bone
19 Foramen lacerum
20 Hypophysial fossa (sella turcica)
21 Anterior clinoid process
22 Trigeminal impression
23 Petrous part of temporal bone
24 Groove for sigmoid sinus
25 Dorsum sellae (posterior clinoid process)
26 Greater wing of sphenoidal bone, groove for middle meningeal artery
27 Hypoglossal canal

Base of the skull (internal aspect, superior view). The individual bones are indicated by different colors.



Skull of the newborn (anterior aspect).



Skull of the newborn (superior aspect). Calvaria.

Cranial skeleton
1 Frontal tuber or eminence
2 Parietal tuber or eminence
3 Occipital tuber or eminence
4 Squamous part of temporal bone
5 Greater wing of sphenoidal bone

Facial skeleton
6 Maxilla
7 Mandible
8 Zygomatic bone
9 Nasal bone

Sutures and fontanelles
10 Frontal suture
11 Coronal suture
12 Sagittal suture
13 Lambdoid suture
14 Anterior fontanelle
15 Posterior fontanelle
16 Sphenoidal (anterolateral) fontanelle
17 Mastoid (posterolateral) fontanelle

Base of the skull
18 Frontal bone
19 Ethmoidal bone
20 Sphenoidal bone
21 Hypophysial fossa (sella turcica)
22 Dorsum sellae
23 Temporal bone
24 Mastoid (posterolateral) fontanelle
25 Occipital bone

In the newborn, the facial skeleton, in contrast to the cranial skeleton, appears relatively small. There are no teeth presenting. The bones of the cranium are separated by wide fontanelles.



Skull of the newborn (lateral aspect).



Base of the skull of the newborn (internal aspect).



Median section through the skull, right half (internal aspect).

1	Hypophysial fossa (sella turcica)	14	Dorsum sellae
2	Anterior clinoid process	15	Internal acoustic meatus
3	Frontal bone	16	Groove for sigmoid sinus
4	Ethmoidal air cells	17	Hypoglossal canal
5	Sphenoidal sinus	18	Occipital condyle
6	Superior concha	19	Condylar process
7	Middle concha	20	Lateral pterygoid plate } of pterygoid process
8	Maxillary hiatus	21	Medial pterygoid plate } of pterygoid process
9	Inferior concha	22	Lingula of mandible
10	Inferior meatus	23	Mandibular foramen
11	Anterior nasal spine and maxilla	24	Mylohyoid groove
12	Mental spine or genial tubercle	25	Mylohyoid line
13	Groove for middle meningeal artery	26	Submandibular fovea



Facial part of the skull (viscerocranium), divided in two halves (lateral and medial aspect). Right inferior concha has been removed to show the maxillary hiatus. Left maxillary sinus opened.

1 Frontal sinus
2 Frontal bone
3 Crista galli
4 Nasal bone
5 Sphenoidal sinus
6 Superior concha } of ethmoidal
7 Middle concha } bone
8 Frontal process of maxilla
9 Ethmoidal bulla
10 Uncinate process
11 Maxillary hiatus
12 Palatine bone
13 Greater palatine foramen
14 Alveolar process of maxilla
15 Central incisor
16 Zygomatic bone
17 Ethmoidal bone
18 Lacrimal bone
19 Pterygopalatine fossa
20 Maxillary sinus
21 Lateral pterygoid plate
22 Medial pterygoid plate
23 Third molar tooth
24 Pterygoid hamulus
25 Two premolar teeth



Median section through the skull. The nasal septum has been removed. The individual bones are indicated by different colors.

Bones (indicated by colors)
1 Frontal bone (yellow)
2 Nasal bone (white)
3 Ethmoidal bone (dark green)
4 Lacrimal bone (yellow)
5 Inferior nasal concha (pink)
6 Palatine bone (white)
7 Maxilla (violet)
8 Mandible (white)
9 Parietal bone (light green)
10 Temporal bone (brown)
11 Sphenoidal bone (red)
12 Petrous part of temporal bone (brown)
13 Occipital bone (blue)
14 Ala of vomer (light brown)

Because of the upright posture that the human developed in the course of evolution, the cranial cavity greatly increased in size, whereas the facial skeleton decreased. As a result, the base of the skull developed an angulation of about 120° between the clivus and the cribriform plate (see drawing on page 20). The hypophysial fossa containing the pituitary gland lies at the angle formed between these two planes.

Disarticulated Skull II: Ethmoidal Bone



Part of a disarticulated base of the skull.
Ethmoidal, sphenoidal, and occipital bones (from above).
Green = sphenoidal bone; yellow = ethmoidal bone.

Ethmoidal bone
1 Crista galli
2 Cribriform plate
3 Ethmoidal air cells
4 Middle concha
5 Perpendicular plate (part of nasal septum)
6 Orbital plate

Sphenoidal bone
7 Lesser wing
8 Greater wing
9 Anterior clinoid process
10 Posterior clinoid process
11 Foramen ovale
12 Foramen spinosum
13 Lingula of the sphenoidal bone
14 Clivus
15 Optic canal
16 Tuberculum sellae
17 Foramen rotundum (right side)
18 Hypophysial fossa (sella turcica)
19 Dorsum sellae
20 Carotid sulcus
21 Spheno-occipital synchondrosis
22 Lateral pterygoid plate
23 Greater wing of sphenoidal bone (orbital surface)
24 Greater wing of sphenoidal bone (maxillary surface)
25 Foramen rotundum (left side)
26 Superior orbital fissure
27 Infratemporal crest of the greater wing



Ethmoidal bone (lateral aspect), posterior portion to the right.



Ethmoidal bone (anterior aspect).



Part of a disarticulated base of the skull (anterior aspect). Green = sphenoidal bone; yellow = ethmoidal bone; red = palatine bone.

Occipital bone

28 Jugular tubercle
29 Jugular process
30 Mastoid margin
31 Posterior cranial fossa
32 Lambdoid margin
33 Intrajugular process
34 Condylar canal
35 Lateral part of occipital bone
36 Hypoglossal canal
37 Foramen magnum
38 Internal occipital crest
39 Squamous part of occipital bone
40 Internal occipital protuberance

Maxilla

41 Orbital surface
42 Infra-orbital groove
43 Maxillary tuberosity with foramina
44 Frontal process
45 Nasolacrimal groove
46 Infra-orbital margin
47 Anterior nasal spine
48 Zygomatic process
49 Alveolar process

Palatine bone

50 Orbital process
51 Sphenopalatine notch
52 Sphenoidal process
53 Perpendicular plate
54 Horizontal plate
55 Pyramidal process



Right maxilla, ethmoidal, and palatine bones (lateral aspect).



Ethmoidal bone (oblique-anterior aspect).

Disarticulated Skull II: Palatine Bone and Maxilla



Part of a disarticulated base of the skull, similar to the preceding figures, but with palatine bone. Green = sphenoidal bone; yellow = ethmoidal bone; red = palatine bone.

Ethmoidal bone
1 Crista galli
2 Orbital plate
3 Middle concha

Palatine bone
4 Horizontal plate of palatine bone
5 Greater palatine canal
6 Pyramidal process
7 Maxillary process
8 Orbital process
9 Sphenopalatine notch
10 Perpendicular plate of palatine bone
11 Conchal crest
12 Nasal crest
13 Sphenoidal process

Sphenoidal bone
14 Greater wing
15 Superior orbital fissure
16 Greater wing (orbital surface)
17 Lesser wing

Occipital bone
18 Squamous part of occipital bone

Maxilla
19 Maxillary tuberosity
20 Frontal process
21 Orbital surface
22 Infra-orbital margin
23 Infra-orbital groove
24 Zygomatic process
25 Alveolar process



Left palatine bone (medial aspect, posterior aspect to the left).



Left palatine bone (anterior aspect).



Right maxilla and palatine bone (lateral aspect).



Part of a disarticulated base of the skull (anterior aspect).
The left **maxilla** is added to the preceding specimen.

Occipital bone
1 Squamous part

Sphenoidal bone
2 Dorsum sellae
3 Superior orbital fissure
4 Lesser wing
5 Greater wing (orbital surface)
6 Lateral pterygoid plate
7 Medial pterygoid plate

Ethmoidal bone
8 Crista galli
9 Ethmoidal air cells
10 Perpendicular plate
11 Orbital plate

Palatine bone
12 Horizontal plate (nasal crest)

Maxilla
13 Frontal process
14 Inferior orbital fissure
15 Infra-orbital groove
16 Orbital surface
17 Infra-orbital foramen
18 Zygomatic process
19 Anterior lacrimal crest
20 Canine fossa
21 Alveolar process with teeth
22 Anterior nasal spine
23 Juga alveolaria (elevations formed by roots of teeth)
24 Lacrimal groove
25 Maxillary tuberosity with alveolar foramina
26 Palatine process of maxilla



Left maxilla (lateral aspect). Probe = infra-orbital canal.



Left maxilla (posterior aspect).

Disarticulated Skull II: Palatine Bone and Maxilla



Part of a disarticulated base of the skull. The mosaic of the facial bones [sphenoidal bone (green), ethmoidal bone (yellow), and palatine bone (red)] is seen from the antero-lateral aspect.



Left maxilla and palatine bone (medial aspect).

Occipital bone

1 Groove for superior sagittal sinus
2 Internal occipital protuberance
3 Groove for transverse sinus
4 Internal occipital crest

Sphenoidal bone

5 Greater wing (temporal surface)
6 Lateral pterygoid plate
7 Dorsum sellae
8 Lesser wing
9 Superior orbital fissure
10 Greater wing (orbital surface)

Ethmoidal bone

11 Ethmoidal air cells
12 Crista galli
13 Orbital plate

Maxilla

14 Frontal process
15 Inferior orbital fissure
16 Alveolar process with teeth
17 Palatine process
18 Anterior nasal spine
19 Infra-orbital groove
20 Zygomatic process
21 Location of infra-orbital foramen
22 Middle nasal meatus
23 Inferior nasal meatus
24 Maxillary hiatus (leading to maxillary sinus)
25 Third molar
26 Lacrimal groove
27 Conchal crest
28 Body of maxilla (nasal surface)
29 Nasal crest
30 Incisive canal

Palatine bone

31 Orbital process
32 Sphenopalatine notch
33 Sphenoidal process
34 Perpendicular plate
35 Conchal crest
36 Horizontal plate
37 Pyramidal process

Frontal bone

38 Squamous part
39 Supra-orbital foramen
40 Frontal notch
41 Frontal spine

Inferior nasal concha

42 Inferior nasal concha with maxillary process


1
7
5
12
13
14
26
27
29
30
17
6
34
25
36
24
28

Part of a disarticulated base of the skull (medial aspect). Green = sphenoidal bone; yellow = ethmoidal bone; red = palatine bone; natural colored = left maxilla.


1
2
4
10
6
36
17
38
39
40
41
11
14
22
42
23

Part of a disarticulated base of the skull (oblique-lateral aspect). The same specimen as shown above but with frontal bone.



Part of a disarticulated skull showing the connection of the palatine bone (red) and the maxilla with ethmoidal bone (yellow) and sphenoidal bone (green) (anterior aspect).

Frontal bone
1 Squamous part
2 Inferior temporal line
3 Temporal surface
4 Supra-orbital foramen
5 Zygomatic process

Occipital bone
6 Squamous part

Sphenoidal bone
7 Greater wing (temporal surface)
8 Optic canal within the lesser wing
9 Lateral pterygoid plate

Palatine bone
10 Orbital process
11 Perpendicular plate
12 Conchal crest
13 Nasal crest
14 Horizontal plate

Ethmoidal bone
15 Orbital plate
16 Ethmoidal air cell
17 Middle concha
18 Perpendicular plate
(part of bony nasal septum)

Maxilla
19 Infra-orbital groove
20 Infra-orbital foramen
21 Zygomatic process
22 Alveolar process with teeth
23 Palatine process

Left inferior nasal concha
24 Anterior part
of inferior concha



Part of a disarticulated skull showing the connection of the maxilla with the frontal and zygomatic bones (anterior aspect).
Yellow = ethmoidal bone; red = palatine bone; green = sphenoidal bone.



Bony palate and teeth of the maxillae (from below).

Frontal bone
1 Squamous part
2 Frontal notch
3 Supra-orbital foramen
4 Supra-orbital margin
5 Zygomatic process
6 Frontal spine

Sphenoidal bone
7 Greater wing (orbital surface)
8 Foramen rotundum
9 Pterygoid or Vidian canal
10 Lateral pterygoid plate
11 Medial pterygoid plate

Ethmoidal bone
12 Orbital plate
13 Ethmoidal air cells
14 Middle concha

Palatine bone
15 Horizontal plate
15a Nasal crest
16 Pyramidal process
17 Lesser palatine foramen
18 Greater palatine foramen

Zygomatic bone
19 Frontal process
20 Orbital surface

Maxilla
21 Canine fossa
22 Frontal process
23 Palatine process
24 Zygomatic process
25 Alveolar process and teeth
26 Juga alveolaria
27 Infra-orbital foramen
28 Infra-orbital groove
29 Anterior nasal aperture
30 Anterior nasal spine

Incisive bone
31 Central incisor and incisive bone or premaxilla
32 Incisive fossa

Vomer
33 Ala of the vomer

Sutures and choanae
34 Median palatine suture
35 Transverse palatine suture
36 Choanae



Anterior view of both maxillae forming the anterior bony aperture of the nose.



Pterygopalatine fossa, maxillary sinus, and orbit. Paramedian section through the skull (right side, lateral aspect). Frontal and maxillary sinuses are opened.



Illustration of canals and foramina connected with the right orbit and pterygopalatine fossa (compare with the figure above). The greater wing of sphenoidal bone (green) is shown as being transparent. Brown = temporal bone; yellow = ethmoidal bone; red = lacrimal bone; light red = inferior nasal concha; violet = maxilla; red = palatine bone.

1 Occipital bone
2 Temporal bone (petrous part)
3 Internal acoustic meatus
4 Carotid canal
5 Hypoglossal canal
6 Occipital condyle
7 Lateral plate of pterygoid process
8 Dorsum of sella turcica
9 Sella turcica
10 Frontal sinus
11 Optic canal
12 Posterior and anterior ethmoidal foramina
13 Orbital plate of ethmoidal bone
14 Nasal bone
15 Nasolacrimal canal
16 Uncinate process
17 Inferior nasal concha (maxillary process)
18 Maxillary sinus
19 Anterior nasal spine
20 Alveolar process of maxilla
21 Foramen rotundum
22 Pterygopalatine fossa
23 Tuberosity of maxilla with alveolar foramina
24 Sphenopalatine foramen
25 Maxillary hiatus
26 Pterygoid or Vidian canal
27 Lesser palatine canal
28 Greater palatine canal
29 Infra-orbital canal



Part of a disarticulated skull (antero-lateral aspect). Orange = zygomatic bone; yellow = ethmoidal bone; dark green = sphenoidal bone. The arrows indicate the locations of the lacrimal bone (11) and the nasal bone (17).

1 Occipital bone
2 Temporal bone
3 Frontal bone
4 Nasal spine of frontal bone
5 Zygomatic bone
6 Maxilla
7 Frontal process of maxilla
8 Ethmoidal bone
9 Orbital plate of ethmoidal bone
10 Perpendicular plate of ethmoidal bone
11 Site of lacrimal bone
12 Lacrimal groove of lacrimal bone
13 Posterior lacrimal crest
14 Fossa for lacrimal sac
15 Lacrimal hamulus
16 Nasolacrimal canal
17 Site of nasal bone
18 Nasal foramina of nasal bone
19 Anterior nasal spine of maxilla
20 Vomer
21 Greater wing of sphenoidal bone
22 Anterior and posterior ethmoidal foramina
23 Optic canal
24 Superior orbital fissure
25 Inferior orbital fissure
26 Infra-orbital groove
27 Infra-orbital foramen



Left lacrimal bone (anterior aspect).



Left orbit (anterior aspect).



Left nasal bone (anterior aspect).



Lateral wall of the nasal cavity. Median section through the skull.

1 Frontal sinus
2 Ethmoidal air cells
3 Sphenoidal sinus
4 Superior nasal concha
5 Middle nasal concha
6 Maxillary hiatus
7 Inferior nasal concha
8 Palatine bone
9 Maxilla
10 Inferior meatus
11 Palatine process of the maxilla

▷
To page 49:

Blue = Occipital bone
Light green = Parietal bone
Yellow = Frontal bone
Dark brown = Temporal bone
Red = Sphenoidal bone
Dark green = Ethmoidal bone
Light blue = Nasal bone
Pink = Inferior concha
Orange = Vomer
Violet = Maxilla
White = Palatine bone
White = Mandible



Right inferior nasal concha (medial aspect). Anterior part to the left.



Right inferior nasal concha (lateral aspect). Anterior part to the right.

Inferior concha and vomer

1 Ethmoidal process
2 Anterior part of concha
3 Inferior border
4 Ala of vomer
5 Posterior border of nasal septum
6 Lacrimal process
7 Posterior part of concha
8 Maxillary process



Vomer (posterior aspect).



Paramedian sagittal section through the skull including the nasal septum.

1 Crista galli
2 Cribriform plate of ethmoidal bone
3 Perpendicular plate of ethmoidal bone
4 Vomer
5 Ala of the vomer
6 Palatine bone (perpendicular process)
7 Palatine bone (horizontal plate)
8 Mandible
9 Nasal bone
10 Sphenoidal sinus
11 Hypophysial fossa (sella turcica)
12 Grooves for the middle meningeal artery

Cartilages of the nose

13 Lateral nasal cartilage
14 Greater alar cartilage
15 Lesser alar cartilages
16 Septal cartilage
17 Location of nasal bone



Cartilages of the nose (right anterior aspect). Arrow: nostril, framed by nasal wing.



Shape of the cartilages of the nose.



Normal position of the teeth. Dentition in centric occlusion (lateral aspect).



Upper teeth of the adult (inferior aspect).



Lower teeth of the adult (superior aspect).

1	Central incisor
2	Lateral incisor
3	Canines
4	First premolars or bicuspids
5	Second premolars or bicuspids
6	First molars
7	Second molars
8	Third molars
9	Articular tubercle
10	Mandibular fossa
11	Head of mandible
12	Condylar process
13	Hard palate and palatine glands
14	Oral cavity
15	Upper molar
16	Oral vestibule
17	Lower molar
18	Platysma muscle
19	Mandible
20	Maxillary sinus
21	Superior longitudinal muscle of tongue
22	Transverse muscle of tongue
23	Buccinator muscle
24	Inferior longitudinal muscle of tongue
25	Sublingual gland
26	Genioglossus muscle



Coronal section through the oral cavity (anterior aspect).



Comparison of the deciduous and permanent teeth. Notice that the breadth of the alveolar arch of the child's mandible and maxilla holding the deciduous teeth is nearly the same as the comparable portion in the jaws of the adult. Note the emergence of the third molars. The numbers of the teeth correspond to the numbers in the figure below.



Deciduous teeth in a child's skull. The developing crowns of the permanent teeth are displayed in their crypts in the maxilla and mandible.

1 Permanent incisors
2 Permanent cuspid (canine)
3 Premolars
4 First permanent molar
5 Second permanent molar
6 Mental foramen



Isolated teeth of the alveolar part of the maxilla (top row) and the mandible (lower row), labial surface of the teeth.



Lateral aspect of the facial bones. Mandible and teeth in the position of occlusion. Upper and lower jaw occluded.



Mandible of the adult (anterior aspect).



Right half of the mandible (medial aspect).



Mandible of the adult (superior aspect).

1 Temporal bone
2 Temporal fossa (greater wing of sphenoidal bone)
3 Infratemporal crest
4 Infratemporal fossa
5 Zygomatic arch
6 Frontal bone
7 Zygomatic bone (frontal process)
8 Lacrimal bone
9 Nasal bone
10 Lacrimal groove
11 Maxilla (canine fossa)
12 Alveolar process of maxilla

Mandible

13 Condylar process
14 Mandibular notch
15 Ramus of the mandible
16 Masseteric tuberosity
17 Angle of the mandible
18 Body of the mandible
19 Coronoid process
20 Alveolar process including teeth
21 Oblique line
22 Mental foramen
23 Mental protuberance
24 Head of the mandible
25 Genial tubercle or mental spine
26 Mandibular foramen (entrance to mandibular canal)
27 Lingula
28 Mylohyoid sulcus
29 Mylohyoid line
30 Submandibular fossa
31 Sublingual fossa

2.2 Masticatory Apparatus and Muscles of the Head



Muscles of mastication and facial muscles (lateral aspect). The auricle has been removed.

1 Temporal muscle
2 Frontal bone
3 Zygomatic arch
4 Temporomandibular joint
5 External acoustic meatus
6 Maxilla
7 Mandible
8 Masseter muscle



Temporomandibular joint and muscles of mastication (lateral aspect). The base of the skull is bent (gray line).

112897_S_053_065_Kap_2_2:_ 28.11.2014 8:45 Uhr Seite 54



Temporomandibular joint (sagittal section).

1 External acoustic meatus
2 Articular cartilage of condylar process
3 Condylar process of mandible
4 Styloid process
5 Stylomandibular ligament
6 Mandibular fossa
7 Articular disc
8 Articular tubercle
9 Zygomatic bone
10 Lateral pterygoid muscle
11 Coronoid process of mandible
12 Posterior belly of digastric muscle
13 Masseter muscle
14 Temporal muscle
15 Medial pterygoid muscle
16 Parotid duct
17 Buccinator muscle
18 Mandible
19 Mandibular foramen



Temporomandibular joint.
Dissection of the articular disc and the related muscles (lateral aspect).



Movements of the temporomandibular joint and the related lateral pterygoid muscles.



Ligaments of temporomandibular joint. Left half of the head (medial aspect).



Temporomandibular joint with ligaments (lateral aspect).



Ligaments of temporomandibular joint (lateral aspect).

1	Groove for sigmoid sinus
2	Mandibular nerve
3	Lateral pterygoid muscle
4	Styloid process
5	Sphenomandibular ligament
6	Stylomandibular ligament
7	Mylohyoid groove
8	Ethmoidal air cells
9	Ethmoidal bulla
10	Hiatus semilunaris
11	Middle meatus
12	Inferior nasal concha
13	Limen nasi
14	Vestibule with hairs
15	Inferior meatus
16	Hard palate
17	Soft palate
18	Vestibule of oral cavity
19	Lower lip
20	Mandible
21	Zygomatic arch
22	External acoustic meatus
23	Articular capsule
24	Lateral ligament
25	Mandibular notch
26	Zygomatic bone
27	Coronoid process
28	Maxilla
29	Mastoid process
30	Mandibular foramen



Temporomandibular joint and masticatory muscles. The masseter and temporal muscles are shown.



1	Galea aponeurotica
2	Frontal belly of occipitofrontalis muscle
3	Temporal muscle
4	Zygomatic arch
5	Temporomandibular joint
6	External acoustic meatus
7	Mandible
8	Masseter muscle
9	Buccinator muscle
10	Platysma muscle
11	Articular disc of temporomandibular joint
12	Coronoid process of mandible
13	Condylar process of mandible
14	Mastoid process

Temporal muscle with insertion at the mandible and the temporomandibular joint. Zygomatic arch and masseter muscle have been partly removed.



Temporomandibular joint and masticatory muscles. The masseter muscle has been partly removed.



1	Galea aponeurotica
2	Temporal muscle
3	Zygomatic arch
4	Temporomandibular joint
5	External acoustic meatus
6	Mandible
7	Buccinator muscle
8	Masseter muscle (cut)
9	Platysma muscle
10	Lateral pterygoid muscle
11	Posterior belly of digastric muscle
12	Stylohyoid muscle
13	Medial pterygoid muscle
14	Anterior belly of digastric muscle
15	Mylohyoid muscle
16	Hyoid bone

Effect of the masticatory muscles on the temporomandibular joint (arrows).



Temporomandibular joint and masticatory muscles. The zygomatic arch and part of the mandible have been removed to reveal the medial and lateral pterygoid muscles.

1 Galea aponeurotica
2 Frontal belly of occipitofrontalis muscle
3 Temporal muscle
4 Zygomatic arch
5 Articular disc of temporomandibular joint
6 Lateral pterygoid muscle
7 Medial pterygoid muscle
8 Buccinator muscle
9 Mandible
10 Masseter muscle
11 Platysma muscle



Medial and lateral pterygoid muscles and their connections with the articular disc of the temporomandibular joint.

1 Lateral pterygoid muscles
2 Medial pterygoid muscle
3 Temporomandibular joint
4 External acoustic meatus
5 Mandible
6 Nasal septum
7 Facial muscle
8 Cerebellum



Temporomandibular joint and masticatory muscles, sagittal section (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Temporomandibular joint and masticatory muscles, axial section (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)


1
2
3
4a
3
5
6
7
8
4b
9
8
10
7
11
12
10
13
21
14
15
16
5
17
6
18
7
19
20
21
12
22

1	Frontal belly of occipitofrontalis muscle
2	Corrugator supercilii muscle
3	Palpebral part of orbicularis oculi muscle
4a	Transverse part of nasalis muscle
4b	Alar part of nasalis muscle
5	Levator labii superioris alaeque nasi muscle
6	Levator labii superioris muscle
7	Zygomaticus major muscle
8	Levator anguli oris muscle
9	Parotid duct
10	Orbicularis oris muscle
11	Masseter muscle
12	Depressor anguli oris muscle
13	Mentalis muscle
14	Sternocleidomastoid muscle
15	Procerus muscle
16	Depressor supercilii muscle
17	Orbital part of orbicularis oculi muscle
18	Zygomaticus minor muscle
19	Buccinator muscle
20	Risorius muscle
21	Depressor labii inferioris muscle
22	Platysma muscle
23	Galea aponeurotica
24	Temporoparietalis muscle
25	Occipital belly of occipitofrontalis muscle
26	Parotid gland with fascia
27	Temporal fascia
28	Orbicularis oculi muscle
29	Parotid duct and masseter muscle

Facial muscles (anterior aspect). Left side: superficial layer, right side: deeper layer.


1
2
3
4a
5
8
19
11
10
22
12
13
24
15
5
6
18
7
20
22
21
22
12

Facial muscles (anterior aspect).
Left side: superficial layer, right side: deeper layer.


1
3
15
28
4a
5
6
18
7
10
12
13
21
22
23
24
25
26
20
14

Facial muscles (lateral aspect). Sphincter-like muscles surround the orifices of the head. Radially arranged muscles work as their antagonists.


1
15
17
4 a
4 b
17
5
6
18
10
7
20
21
12
22
23
24
25
26
14

Facial muscles (lateral aspect).


1
23
2
27
28
6
8
10
7
12
22
29
26
14

Facial muscles and parotid gland (lateral aspect).


17
7
10
21
20
26
22
14

Platysma muscle (oblique-lateral aspect). Superficial lamina of cervical fascia partly removed.



Supra- and infrahyoid muscles and pharynx (lateral aspect). Ramus of mandible, pterygoid muscles, and insertion of temporal muscle removed.



Supra- and infrahyoid muscles (lateral aspect).

1	Galea aponeurotica
2	Temporal fascia
3	Tendon of temporal muscle
4	Zygomatic arch
5	Lateral pterygoid plate
6	Tensor veli palatini muscle (styloid process)
7	Superior constrictor muscle of pharynx
8	Styloglossus muscle
9	Posterior belly of digastric muscle
10	Stylohyoid muscle
11	Longus capitis muscle
12	Sternocleidomastoid muscle (reflected)
13	Inferior constrictor of pharynx
14	Frontal belly of occipitofrontalis muscle
15	Orbital part of orbicularis oculi muscle
16	Buccinator muscle
17	Depressor anguli oris muscle
18	Mylohyoid muscle
19	Anterior belly of digastric muscle
20	Thyrohyoid muscle
21	Sternohyoid muscle
22	Omohyoid muscle
23	Hyoid bone
24	Sternothyroid muscle
25	Scalene muscles



Supra- and infrahyoid muscles and pharynx (lateral aspect). Buccinator muscle removed; oral cavity opened.

1	External acoustic meatus
2	Tensor veli palatini muscle
3	Styloid process
4	Superior constrictor muscle of pharynx
5	Stylopharyngeus muscle (divided)
6	Middle constrictor muscle of pharynx
7	Sternocleidomastoid muscle
8	Greater horn of hyoid bone
9	Longus capitis muscle
10	Inferior constrictor muscle of pharynx
11	Temporal fascia
12	Tendon of temporal muscle
13	Orbicularis oculi muscle
14	Zygomatic arch
15	Lateral pterygoid plate
16	Parotid duct
17	Gingiva of upper jaw (without teeth) and buccinator muscle (divided)
18	Pterygomandibular raphe
19	Hyoglossus muscle
20	Mylohyoid muscle
21	Anterior belly of digastric muscle (hyoid bone)
22	Sternohyoid and thyrohyoid muscles
23	Omohyoid muscle

Section through the Cavities of the Head



Coronal section through cranial, nasal, and oral cavities at the level of sphenoidal sinus.



Pterygoid and palatine muscles (posterior aspect).

1 Temporal muscle
2 Sphenoidal sinus
3 Nasopharynx
4 Masseter muscle
5 Superior longitudinal, transverse and vertical muscles of tongue
6 Hyoglossus muscle
7 Geniohyoid muscle
8 Corpus callosum (caudate nucleus)
9 Optic nerve
10 Cavernous sinus
11 Zygomatic arch
12 Cross section of lateral pterygoid muscle and maxillary artery
13 Section of medial pterygoid muscle
14 Soft palate
15 Mandible and inferior alveolar nerve
16 Septum of the tongue
17 Mylohyoid muscle
18 Submandibular gland
19 Platysma muscle
20 Foramen magnum, vertebral artery and spinal cord
21 Internal carotid artery
22 Head of mandible
23 Styloid process
24 Inferior alveolar nerve
25 Lingual nerve and chorda tympani nerve
26 Medial pterygoid muscle
27 Uvula
28 Anterior belly of digastric muscle (cut)
29 Condyle of occipital bone
30 Mastoid process
31 Lateral pterygoid muscle
32 Auditory tube and levator veli palatini muscle
33 Tensor veli palatini muscle



Dissection of maxillary artery (lateral aspect). The ramus mandibulae has been partly removed and the canalis mandibulae has been opened.

1 Galea aponeurotica
2 Superficial temporal artery and auriculotemporal nerve
3 Occipital artery and greater occipital nerve (C_2)
4 Temporomandibular joint (opened)
5 External carotid artery
6 Mandible and inferior mandibular artery and nerve
7 Accessory nerve (var.)
8 Great auricular nerve
9 Sternocleidomastoideus muscle
10 Punctum nervosum
11 Supraclavicular nerves
12 Supra-orbital nerves
13 Temporal muscle
14 Transverse facial artery
15 Masseteric nerve and deep temporal branch of maxillary artery
16 Maxillary artery
17 Buccal nerve
18 Lingual nerve
19 Buccinator muscle
20 Facial artery
21 External carotid artery and sinus caroticus
22 Hypoglossal nerve
23 Digastric muscle
24 Transverse cervical nerves



Main branches of maxillary artery (lateral aspect).

1 Superficial temporal artery

Branches of the first part

2 Deep auricular artery and anterior tympanic artery
3 Middle meningeal artery
4 Inferior alveolar artery

Branches of the second part

5 Deep temporal branches
6 Pterygoid branches
7 Masseteric artery
8 Buccal artery

Branches of the third part

9 Posterior superior alveolar artery
10 Infra-orbital artery
11 Sphenopalatine artery and branches to the nasal cavity
12 Descending palatine artery
13 Artery of the pterygoid canal

2.3 Brain and Regions of the Head



Cranial nerves

I = Olfactory nerves
II = Optic nerve
III = Oculomotor nerve
IV = Trochlear nerve
V = Trigeminal nerve
V_1 = Ophthalmic nerve
V_2 = Maxillary nerve
V_3 = Mandibular nerve
VI = Abducent nerve
VII = Facial nerve
VIII = Vestibulocochlear nerve
IX = Glossopharyngeal nerve
X = Vagus nerve
XI = Accessory nerve
XII = Hypoglossal nerve

Dissection of the cranial nerves (indicated by I–XII) (lateral aspect). Brain, brain stem, and cerebellum have been partly removed. Arrow: trigeminal ganglion.



Schematic drawing of the cranial nerves (indicated by I–XII) (lateral aspect).



Brain with cranial nerves (inferior aspect). Midbrain divided.

1 Frontal lobe
2 Temporal lobe
3 Pedunculus cerebri
4 Midbrain (divided)
5 Cerebral aqueduct
6 Splenium of corpus callosum
7 Occipital lobe
8 Olfactory bulb
9 Olfactory tract
10 Optic nerve and optic chiasma
11 Infundibulum
12 Oculomotor nerve (n. III)
13 Mamillary body
14 Substantia nigra
15 Trochlear nerve (n. IV)



Brain with cranial nerves (inferior aspect). Meninges removed.

1 Olfactory sulcus (termination)
2 Orbital gyri
3 Temporal lobe
4 Straight gyrus
5 Olfactory trigone and inferior temporal sulcus
6 Medial occipitotemporal gyrus
7 Parahippocampal gyrus, mamillary body, and interpeduncular fossa
8 Pons and cerebral peduncle
9 Abducent nerve (n. VI)
10 Pyramid
11 Inferior olive
12 Cervical spinal nerves
13 Cerebellum
14 Tonsil of cerebellum
15 Occipital lobe (posterior pole)
16 Olfactory bulb
17 Orbital sulci of frontal lobe
18 Olfactory tract
19 Optic nerve (n. II) and anterior perforated substance
20 Optic chiasma
21 Optic tract
22 Oculomotor nerve (n. III)
23 Trochlear nerve (n. IV)
24 Trigeminal nerve (n. V)
25 Facial nerve (n. VII)
26 Vestibulocochlear nerve (n. VIII)
27 Flocculus of cerebellum
28 Glossopharyngeal nerve (n. IX) and vagus nerve (n. X)
29 Hypoglossal nerve (n. XII)
30 Accessory nerve (n. XI)
31 Vermis of cerebellum
32 Longitudinal fissure



Brain stem and pharynx with cranial nerves (posterior aspect). **Dissection of trochlear (n. IV), facial (n. VII), vestibulocochlear (n. VIII), glossopharyngeal (n. IX), vagus (n. X), accessory (n. XI), and hypoglossal (n. XII) nerves.** The cranial cavity has been opened and the cerebellum removed.

1	Falx cerebri	11	Pharynx (middle constrictor muscle)	19	Hypoglossal nerve (n. XII)
2	Occipital lobe	12	Hyoid bone (greater horn)	20	Vagus nerve (n. X) and internal carotid artery
3	Straight sinus	13	Trochlear nerve (n. IV)	21	External carotid artery
4	Cerebellar tentorium	14	Facial nerve (n. VII) and vestibulocochlear nerve (n. VIII)	22	Sympathetic trunk and superior cervical ganglion
5	Transverse sinus	15	Glossopharyngeal nerve (n. IX) and vagus nerve (n. X)	23	Ansa cervicalis (superior root of hypoglossal nerve)
6	Inferior colliculus of midbrain	16	Accessory nerve (intracranial portion) (n. XI)	24	Glossopharyngeal nerve (n. IX) and stylopharyngeus muscle
7	Rhomboid fossa	17	Hypoglossal nerve (intracranial portion) (n. XII)		
8	Medulla oblongata	18	Accessory nerve (n. XI)		
9	Posterior belly of digastric muscle				
10	Internal carotid artery				



Dissection of the trigeminal nerve (n. V) in its entirety. Lateral wall of cranial cavity, lateral wall of orbit, zygomatic arch, and ramus of the mandible have been removed and the mandibular canal opened.

1 Frontal lobe of cerebrum
2 Supra-orbital nerve
3 Lacrimal nerve
4 Lacrimal gland
5 Eyeball
6 Optic nerve and short ciliary nerves
7 External nasal branch of anterior ethmoidal nerve
8 Ciliary ganglion
9 Zygomatic nerve
10 Infra-orbital nerve
11 Infra-orbital foramen and terminal branches of infra-orbital nerve
12 Pterygopalatine ganglion and pterygopalatine nerves
13 Posterior superior alveolar nerves
14 Superior dental plexus
15 Buccinator muscle and buccal nerve
16 Inferior dental plexus
17 Mental foramen and mental nerve
18 Anterior belly of digastric muscle
19 Ophthalmic nerve (n. V_1)
20 Oculomotor nerve (n. III)
21 Trochlear nerve (n. IV)
22 Trigeminal nerve (n. V) and pons
23 Maxillary nerve (n. V_2)
24 Trigeminal ganglion
25 Mandibular nerve (n. V_3)
26 Auriculotemporal nerve
27 External acoustic meatus (divided)
28 Lingual nerve and chorda tympani
29 Mylohyoid nerve
30 Medial pterygoid muscle
31 Inferior alveolar nerve
32 Posterior belly of digastric muscle
33 Stylohyoid muscle
34 Sternocleidomastoid muscle



Cranial nerves in connection with the brain stem. Left side (lateral superior aspect). Left half of brain and head partly removed. Notice the location of the trigeminal ganglion.



Main branches of trigeminal nerve (compare with the dissection on opposite page).

1 Frontal nerve
2 Lacrimal gland and eyeball
3 Lacrimal nerve
4 Lateral rectus muscle
5 Ciliary ganglion lateral to optic nerve
6 Zygomatic nerve
7 Inferior branch of oculomotor nerve
8 Ophthalmic nerve (n. V_1)
9 Maxillary nerve (n. V_2)
10 Trigeminal ganglion
11 Mandibular nerve (n. V_3)
12 Posterior superior alveolar nerves
13 Tympanic cavity, external acoustic meatus, and tympanic membrane
14 Inferior alveolar nerve
15 Lingual nerve
16 Facial nerve (n. VII)
17 Vagus nerve (n. X)
18 Hypoglossal nerve (n. XII) and superior root of ansa cervicalis
19 External carotid artery
20 Olfactory tract (n. I)
21 Optic nerve (n. II) (intracranial part)
22 Oculomotor nerve (n. III)
23 Abducent nerve (n. VI)
24 Trochlear nerve (n. IV)
25 Trigeminal nerve (n. V)
26 Vestibulocochlear nerve (n. VIII) and facial nerve (n. VII)
27 Glossopharyngeal nerve (n. IX) (leaving brain stem)
28 Rhomboid fossa
29 Vagus nerve (n. X) (leaving brain stem)
30 Hypoglossal nerve (n. XII) (leaving medulla oblongata)
31 Accessory nerve (n. XI) (ascending from foramen magnum)
32 Vertebral artery
33 Spinal ganglion and dura mater of spinal cord
34 Accessory nerve (n. XI)
35 Internal carotid artery
36 Lateral and medial branch of supra-orbital nerve
37 Infratrochlear nerve
38 Infra-orbital nerve
39 Pterygopalatine ganglion and pterygopalatine nerves
40 Middle superior alveolar nerves (entering superior dental plexus)
41 Buccal nerve
42 Mental nerve and mental foramen
43 Auriculotemporal nerve
44 Otic ganglion
45 Chorda tympani
46 Mylohyoid nerve
47 Submandibular gland
48 Hyoid bone



Dissection of the facial nerve (n. VII) in its entirety. Cranial cavity fenestrated, temporal lobe partly removed. Facial canal and tympanic cavity opened, posterior wall of external acoustic meatus removed. **Branches of the facial nerve:** a = temporal branch; b = zygomatic branches; c = buccal branches; d = marginal mandibular branch.



Facial nerve (compare with the dissection above).

1 Trochlear nerve (n. IV)
2 Facial nerve (n. VII) with geniculate ganglion
3 Cerebellum (right hemisphere)
4 Occipital belly of occipitofrontalis muscle and greater occipital nerve
5 Facial nerve (n. VII) at stylomastoid foramen
6 Splenius capitis muscle
7 Cervical branch of facial nerve (n. VII)
8 Sternocleidomastoid muscle and retromandibular vein
9 Orbicularis oculi muscle
10 Chorda tympani
11 External acoustic meatus
12 Facial artery
13 Mastoid air cells
14 Posterior auricular nerve
15 Nucleus and genu of facial nerve

Cranial nerves in connection with the brain stem (oblique-lateral aspect). Lateral portion of the skull, brain, neck and facial structures, lateral wall of orbit and oral cavity have been removed. The tympanic cavity has been opened. The mandible has been divided and the muscles of mastication have been removed.

▷



1 Optic tract
2 Oculomotor nerve (n. III)
3 Lateral rectus muscle and inferior branch of oculomotor nerve
4 Malleus and chorda tympani
5 Chorda tympani, facial nerve (n. VII), and vestibulocochlear nerve (n. VIII)
6 Glossopharyngeal nerve (n. XI)
7 Lingual nerve and inferior alveolar nerve
8 Styloid process and stylohyoid muscle
9 Styloglossus muscle
10 Lingual branches of glossopharyngeal nerve
11 Lingual branch of hypoglossal nerve
12 External carotid artery
13 Superior root of ansa cervicalis (branch of hypoglossal nerve, derived from C_1)
14 Lateral ventricle with choroid plexus and cerebral peduncle
15 Trochlear nerve (n. IV)
16 Trigeminal nerve (n. V)
17 Fourth ventricle and rhomboid fossa
18 Vagus nerve (n. X)
19 Accessory nerve (n. XI)
20 Vertebral artery
21 Superior cervical ganglion
22 Hypoglossal nerve (n. XII)
23 Spinal ganglion with dural sheath
24 Dura mater of spinal cord
25 Internal carotid artery and carotid sinus branch of glossopharyngeal nerve
26 Dorsal roots of spinal nerve
27 Sympathetic trunk
28 Branch of cervical plexus (ventral primary ramus of third cervical spinal nerve)
29 Ansa cervicalis



Cranial nerves of the orbit and pterygopalatine fossa (left orbit, lateral aspect). **Dissection of optic (n. II), oculomotor (n. III), trochlear (n. IV), ophthalmic (n. V_1), and abducent (n. VI) nerves.** Note the zygomaticolacrimal anastomosis (arrow).

1 Frontal lobe
2 Supra-orbital nerve
3 Lacrimal gland
4 Lacrimal nerve
5 Lateral rectus muscle (divided)
6 Optic nerve (n. II) and short ciliary nerves
7 Inferior oblique muscle
8 Zygomatic nerve
9 Inferior branch of oculomotor nerve (n. III) and inferior rectus muscle
10 Infra-orbital nerve
11 Posterior superior alveolar nerves
12 Branches of superior alveolar plexus adjacent to mucous membrane of maxillary sinus
13 Central sulcus of insula
14 Superior rectus muscle
15 Periorbita (roof of orbit)
16 Nasociliary nerve
17 Ciliary ganglion
18 Oculomotor nerve (n. III)
19 Trochlear nerve (n. IV)
20 Ophthalmic nerve (n. V_1)
21 Abducent nerve (n. VI) (divided)
22 Trigeminal nerve (n. V)
23 Trigeminal ganglion
24 Maxillary nerve (n. V_2) and foramen rotundum
25 Mandibular nerve (n. V_3)
26 External acoustic meatus
27 Pterygopalatine nerves
28 Deep temporal nerves
29 Buccal nerve
30 Masseteric nerve
31 Auriculotemporal nerve
32 Trochlea and superior oblique muscle



Cranial nerves innervating extra-ocular muscles (lateral aspect).



Cranial nerves of the orbit (superior aspect). Right side: superficial layer, left side: middle layer of the orbit. Superior rectus muscle and frontal nerve divided and reflected. Tentorium and dura mater partly removed.



Cranial nerves within the orbit (superior aspect).

1	Frontal sinus (enlarged)
2	Frontal nerve (divided and reflected)
3	Superior rectus muscle (divided) and eyeball
4	Superior oblique muscle
5	Short ciliary nerves and optic nerve (n. II)
6	Nasociliary nerve
7	Abducent nerve (n. VI) and lateral rectus muscle
8	Ciliary ganglion and superior rectus muscle (reflected)
9	Oculomotor nerve (n. III)
10	Trochlear nerve (n. IV)
11	Crus cerebri and midbrain
12	Inferior wall of the third ventricle connected with cerebral aqueduct
13	Lateral and medial branches of supra-orbital nerve
14	Supratrochlear nerve
15	Superior levator palpebrae muscle
16	Lacrimal nerve
17	Frontal nerve
18	Ophthalmic nerve (n. V_1)
19	Optic chiasma and internal carotid artery
20	Trigeminal ganglion
21	Trigeminal nerve (n. V)
22	Tentorial notch
23	Superior rectus muscle
24	Ophthalmic artery



Base of the skull with cranial nerves. The brain stem was divided and the tentorium fenestrated. Both hemispheres were removed.



1	Infundibulum
2	Optic chiasma and internal carotid artery
3	Olfactory tract
4	Oculomotor nerve (n. III)
5	Ophthalmic nerve (n. V_1)
6	Trigeminal ganglion
7	Falx cerebri
8	Tentorial notch
9	Trochlear nerve (n. IV)
10	Trigeminal nerve (n. V)
11	Cerebellum
12	Eyeball
13	Medial and lateral rectus muscles
14	Internal carotid artery
15	Oculomotor nerve (n. III)
16	Midbrain
17	Cerebral aqueduct
18	Vermis of cerebellum
19	Occipital lobe of the cerebrum

Axial section through the head at the level of the sella turcica demonstrating cranial nerves (MRI scan). (Dept. of Neurosurgery, Univ. Erlangen-Nuremberg, Germany.)

112897_S_066_085_Kap_2_3:_ 06.11.2014 11:33 Uhr Seite 77



Base of the skull with cranial nerves (internal aspect). Both cerebral hemispheres and upper part of the brain stem have been removed. Incision on the right cerebellar tentorium to display the cranial nerves of the infratentorial space.

1 Superior sagittal sinus with falx cerebri
2 Olfactory bulb
3 Olfactory tract
4 Optic nerve and internal carotid artery
5 Anterior clinoid process and anterior attachment of cerebellar tentorium
6 Oculomotor nerve (n. III)
7 Abducent nerve (n. VI)
8 Tentorial notch (incisura tentorii)
9 Trochlear nerve (n. IV)
10 Cerebellar tentorium
11 Falx cerebri and confluence of sinuses
12 Hypophysial fossa, infundibulum, and diaphragma sellae
13 Dorsum sellae
14 Midbrain (divided)
15 Trigeminal nerve (n. V)
16 Facial nerve (n. VII), nervus intermedius, and vestibulocochlear nerve (n. VIII)
17 Cerebral aqueduct
18 Right hemisphere of cerebellum
19 Vermis of cerebellum
20 Straight sinus


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25

Superficial dissection of lateral region of the face. Peripheral distribution of facial nerve (n. VII).


1
2
3
5
4
7
8
9
10
12
27
16
17
18
6
19
21
20
22
23
26
24

Superficial region of the face. Note the facial plexus within the parotid gland (lateral aspect).



Deep dissection of facial nerve. Retromandibular and submandibular regions (lateral aspect). The parotid gland has been removed.

1	Temporoparietalis muscle
2	Superficial temporal artery and vein, and auriculotemporal nerve
3	Occipital belly of occipitofrontalis muscle and greater occipital nerve (C_2)
4	Facial nerve (n. VII)
5	Lesser occipital nerve and occipital artery
6	Transverse facial artery
7	Masseter muscle
8	Parotid gland and great auricular nerve
9	Splenius capitis muscle
10	Trapezius muscle
11	Punctum nervosum, point of distribution of cutaneous nerves of cervical plexus
12	Sternocleidomastoid muscle and external jugular vein
13	Supraclavicular nerves
14	Brachial plexus
15	Supra-orbital nerves
16	Orbicularis oculi muscle
17	Angular artery (terminal branch of facial artery)
18	Nasalis muscle
19	Zygomaticus major muscle
20	Parotid duct
21	Zygomatic and buccal branches of facial nerve
22	Orbicularis oris muscle
23	Depressor anguli oris muscle
24	Platysma muscle
25	Cervical branch of facial nerve (anastomosing with transverse cervical nerve of cervical plexus)
26	Facial artery and vein
27	Temporal branches of facial nerve
28	Submandibular gland
29	Mandible
30	Mylohyoideus muscle and nerve
31	Anterior belly of digastric muscle
32	Omohyoid muscle
33	Greater petrosal nerve
34	Geniculate ganglion
35	Chorda tympani
36	Posterior auricular nerve
37	Stylomastoid foramen
38	Sternocleidomastoid muscle and retromandibular vein



Main branches of facial nerve (lateral aspect).
a = temporal branches; b = zygomatic branches;
c = buccal branches; d = marginal mandibular branch.



Deep dissection of facial nerve. Retromandibular and submandibular regions (lateral aspect).
The parotid gland and the submandibular gland have been removed. The parotid plexus (4) is formed by anastomosis of the temporal, zygomatic, buccal, marginal mandibular, and cervical branches of the facial nerve, arising in the parotid gland.

1	Parotid gland	8	Hypoglossal nerve (n. XII)	15	Depressor anguli oris muscle
2	Facial nerve (n. VII)	9	Stylohyoid muscle	16	Mandible
3	Great auricular nerve	10	Transverse cervical nerve	17	Mylohyoid muscle and nerve
4	Parotid plexus	11	Zygomaticus major muscle	18	Anterior belly of digastric muscle
5	Sternocleidomastoid muscle	12	Parotid duct	19	Omohyoid muscle
6	Retromandibular vein	13	Facial artery	20	Sternohyoid muscle
7	Cervical branch of facial nerve	14	Masseter muscle		



Superficial dissection of lateral region of the face. Masseter muscle and temporal fascia have been partly removed to display the masseteric artery and nerve.

1 Galea aponeurotica
2 Temporal fascia
3 Temporal muscle
4 Parietal branch
of superficial temporal artery
5 Auriculotemporal nerve
6 Frontal branch
of superficial temporal artery
7 Superficial temporal vein
8 Zygomatic arch
9 Articular disc
of temporomandibular joint
10 Head of mandible
11 Masseteric artery and nerve
12 Mandibular notch
13 Masseter muscle (divided)
14 External carotid artery
15 Great auricular nerve
16 Facial nerve (reflected)
17 Frontal belly of occipitofrontalis muscle
18 Medial branch of supra-orbital nerve
19 Angular artery
20 Orbicularis oculi muscle
21 Infra-orbital nerve
22 Zygomaticus major muscle
23 Maxillary artery
24 Coronoid process
25 Parotid duct (divided)
26 Buccal nerve
27 Facial artery and vein
28 Mental nerve
29 Mandibular branch of facial nerve
30 Cervical branch of facial nerve
31 Transverse cervical nerve
(communicating branch with facial nerve)
and sternocleidomastoid muscle



Deep dissection of facial and retromandibular regions. The coronoid process together with the insertions of temporal muscle have been removed to display the maxillary artery. The upper part of the mandibular canal has been opened.

1 Parietal branch of superficial temporal artery
2 Frontal branch of superficial temporal artery
3 Auriculotemporal nerve
4 Maxillary artery
5 Superficial temporal artery
6 Communicating branches between facial and auriculotemporal nerves
7 Facial nerve
8 Posterior auricular artery and anterior auricular branch of superficial temporal artery
9 Internal jugular vein
10 Mylohyoid nerve
11 Posterior belly of digastric muscle
12 Great auricular nerve and sternocleidomastoid muscle
13 External jugular vein
14 Retromandibular vein
15 Submandibular gland
16 Temporal fascia
17 Temporal tendon
18 Deep temporal arteries
19 Posterior superior alveolar nerve
20 Sphenopalatine artery
21 Posterior superior alveolar arteries
22 Masseteric artery and nerve
23 Buccal nerve and artery
24 Lateral pterygoid
25 Transverse facial artery and parotid duct (divided)
26 Medial pterygoid muscle
27 Facial artery
28 Lingual nerve
29 Inferior alveolar artery and nerve (mandibular canal opened)



Dissection of peripharyngeal and retromandibular regions. The mandible has been partly removed (oblique-lateral aspect).

1 Supra-orbital nerve (medial branch)
2 Temporal muscle
3 Superficial temporal artery and auriculotemporal nerve
4 Orbicularis oculi muscle
5 Anterior deep temporal artery
6 Maxillary artery
7 Buccal nerve
8 Lingual nerve
9 Inferior alveolar nerve and artery
10 Submandibular ganglion
11 Facial artery
12 Mylohyoid muscle and nerve
13 Anterior belly of digastric muscle
14 Omohyoid muscle
15 Occipital artery
16 Greater occipital nerve (C_2)
17 Facial nerve (cut) (n. VII)
18 Great auricular nerve
19 Lesser occipital nerve
20 Posterior belly of digastric muscle
21 Accessory nerve (Var.)
22 Sternocleidomastoid muscle
23 Hypoglossus nerve (n. XII)
24 Supraclavicular nerves (lateral and intermedial branches)
25 Internal jugular vein and ansa cervicalis
26 Anterior supraclavicular nerve


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
15

Deep dissection of facial and retromandibular regions. The mandible and pterygoid muscles have been removed, the temporal muscle was fenestrated.


22
23
24
25
3
26
6
17
9
10
27
11
28
29
30
31
32
33
34
35
16
19
15
36

Deep region of the face with arteries and nerves, particularly dissection of maxillary artery and trigeminal nerve.



Dissection of para- and retropharyngeal regions. The mandible and the lateral wall of the orbit have been removed. The main branches of the trigeminal nerve and its ganglion are displayed.

1	Superficial temporal artery and vein and auriculotemporal nerve
2	Tendon of temporal muscle, deep temporal nerves and artery
3	Maxillary artery
4	Middle meningeal artery
5	Occipital artery
6	Inferior alveolar artery and nerve
7	Posterior belly of digastric muscle
8	Great auricular nerve and sternocleidomastoid muscle
9	Hypoglossal nerve and superior root of ansa cervicalis
10	External carotid artery
11	Supratrochlear nerve and medial branch of supra-orbital artery
12	Angular artery
13	Posterior superior alveolar artery
14	Infra-orbital nerve
15	Facial artery
16	Parotid duct (divided) and buccinator muscle
17	Buccal artery and nerve
18	Mylohyoid nerve
19	Lingual nerve and submandibular ganglion
20	Mental nerve and foramen
21	Inferior alveolar nerve
22	Trigeminal nerve and ganglion
23	Mandibular nerve (n. V_3)
24	Auriculotemporal nerve and middle meningeal artery
25	Superficial temporal artery
26	Facial nerve
27	Lateral branch of supra-orbital nerve
28	Lacrimal gland
29	Ciliary ganglion and short ciliary nerves
30	Inferior branch of oculomotor nerve
31	Maxillary nerve (n. V_2)
32	Angular artery
33	Infra-orbital nerve
34	Posterior superior alveolar nerve
35	Anterior superior alveolar nerve
36	Submandibular gland
37	Cerebellar tentorium
38	Masseter muscle
39	Superior root of ansa cervicalis
40	Ophthalmic nerve (n. V_1)

2.4 Brain and Sensory Organs

1	Vertex of the skull and dura mater
2	Frontal lobe
3	Temporal lobe
4	Facial nerve (n. VII)
5	Central sulcus
6	Lateral sulcus
7	Occipital lobe
8	Cerebellum
9	Frontal sinus
10	Eye and optic nerve (n. II)
11	Nasal cavity
12	Oral cavity
13	Tongue
14	Brain stem
15	Base of skull
16	Spinal cord
17	Vertebral column



Dissection of the head to show the brain with pia mater and arachnoid in situ (lateral aspect).



Sagittal section through the head with brain and sensory organs. The eye with the optic nerve is located within the orbit; the labyrinth organ, within the petrous bone.



Lateral aspect of the head. Scalp, vertex of the skull, and meninges are demonstrated by a series of window-like openings.

1 Skin
2 Galea aponeurotica
3 Skull diploe
4 Dura mater
5 Arachnoid and pia mater with cerebral vessels
6 Frontal belly of occipitofrontalis muscle
7 Branch of middle meningeal artery
8 Pericranium (periosteum)
9 Lateral and medial branches of supra-orbital nerve
10 Orbicularis oculi muscle
11 Zygomatico-orbital artery
12 Auriculotemporal nerve and superficial temporal artery and vein
13 Superior auricular muscle
14 Occipital belly of occipitofrontalis muscle
15 Occipital nerve
16 Occipital artery and vein
17 Greater occipital nerve
18 Sternocleidomastoid muscle
19 Frontal lobe
20 Chiasmatic cistern
21 Interpeduncular cistern
22 Arachnoid granulations
23 Subarachnoid space
24 Superior sagittal sinus
25 Inferior sagittal sinus
26 Corpus callosum
27 Straight sinus
28 Confluence of sinuses
29 Cerebellum
30 Cerebellomedullar cistern
31 Cerebral cortex



Subarachnoid cisterns of the brain (midsagittal section).
Green = cisterns; blue = dural sinus and ventricles;
red = choroid plexus of third and fourth ventricles;
arrows: flow of cerebrospinal fluid.



Cross section of the scalp and the meninges.
The subarachnoid space (23) is shown.



Median sagittal section through the head and neck.

1 Falx cerebri
2 Corpus callosum and septum pellucidum
3 Interventricular foramen and fornix
4 Choroid plexus of third ventricle and internal cerebral vein
5 Third ventricle and interthalamic adhesion
6 Pineal body and colliculi of the midbrain
7 Cerebral aqueduct
8 Mamillary body and basilar artery
9 Straight sinus
10 Fourth ventricle and cerebellum
11 Pons and falx cerebelli
12 Medulla oblongata
13 Central canal
14 Cerebellomedullary cistern
15 Dens of the axis (odontoid process)
16 Spinal cord
17 Superior sagittal sinus
18 Anterior cerebral artery
19 Anterior commissure
20 Frontal sinus
21 Crista galli
22 Optic chiasma
23 Pituitary gland (hypophysis)
24 Superior nasal concha
25 Middle nasal concha and sphenoid sinus
26 Inferior nasal concha
27 Pharyngeal opening of auditory tube
28 Superior longitudinal muscle of tongue
29 Vertical muscle of the tongue
30 Uvula
31 Genioglossus muscle
32 Pharynx
33 Epiglottis
34 Geniohyoid muscle
35 Mylohyoid muscle
36 Hyoid bone
37 Vocal fold and sinus of larynx
38 Esophagus



Dura mater and venous sinuses of the dura mater. The brain has been removed (oblique-lateral aspect).

1 Falx cerebri
2 Position of middle meningeal artery and vein
3 Internal carotid artery
4 Optic nerve (n. II)
5 Frontal sinus
6 Oculomotor nerve (n. III)
7 Diploe
8 Dura mater
9 Superior sagittal sinus
10 Straight sinus
11 Trigeminal nerve (n. V)
12 Facial and vestibulocochlear nerve (n. VII and n. VIII)
13 Cerebellar tentorium
14 Pituitary gland (hypophysis)
15 Inferior sagittal sinus
16 Sigmoid sinus
17 Confluence of sinuses
18 Inferior petrosal sinus
19 Transverse sinus
20 Superior petrosal sinus
21 Cavernous and intercavernous sinuses
22 Sphenoparietal sinus



Dura mater and venous sinuses of the dura mater (left lateral aspect).

Meninges: Dura Mater



Median section through the head. Demonstration of dura mater covering the cranial cavity. Brain and spinal cord are removed (right half of the head, as seen from medial).

1 Cranial cavity with dura mater (right cerebral hemisphere has been removed)
2 Frontal sinus
3 Hypophysial fossa with pituitary gland
4 Sphenoidal sinus
5 Nasal cavity
6 Soft palate (uvula)
7 Oral cavity
8 Tongue
9 Skin
10 Calvaria
11 Dura mater
12 Cerebellar tentorium
13 Confluence of sinuses
14 Infratentorial space (cerebellum and part of the brain stem have been removed)
15 Vertebral canal
16 Frontal branch of middle meningeal artery and veins
17 Middle meningeal artery
18 Diploe
19 Parietal branch of middle meningeal artery and vein
20 Occipital pole of left hemisphere covered with dura mater



Dissection of dura mater and meningeal vessels. Left half of calvaria removed.



Dissection of the brain with pia mater and arachnoid in situ. The head is cut in half except for the brain, which is shown in its entirety.

1 Calvaria and skin of the scalp
2 Dura mater (divided)
3 Position of lateral sulcus
4 Frontal lobe covered by arachnoid and pia mater
5 Frontal sinus
6 Olfactory bulb
7 Sphenoidal sinus
8 Dura mater on clivus and basilar artery
9 Atlas (anterior arch, divided)
10 Soft palate
11 Tongue
12 Epiglottis
13 Vocal fold
14 Position of central sulcus
15 Superior cerebral veins
16 Tentorium (divided)
17 Cerebellum
18 Cerebellomedullary cistern
19 Position of foramen magnum and spinal cord
20 Dens of axis
21 Intervertebral disc



Brain with pia mater and arachnoid. Frontal pole to the left (lateral aspect).

1 Superior cerebral veins
2 Position of central sulcus
3 Position of lateral sulcus and cistern of lateral cerebral fossa
4 Frontal pole
5 Lateral sulcus (arrow)
6 Temporal pole
7 Pons and basilar artery
8 Vertebral arteries
9 Superior anastomotic vein
10 Occipital pole
11 Inferior cerebral veins
12 Hemisphere of cerebellum
13 Medulla oblongata



Median section through brain and brain stem. Frontal pole to the right.

1 Parietal lobe
2 Thalamus, third ventricle, and intermediate mass
3 Great cerebral vein
4 Occipital lobe
5 Colliculi of the midbrain and cerebral aqueduct
6 Cerebellum
7 Medulla oblongata
8 Central sulcus
9 Corpus callosum
10 Frontal lobe
11 Fornix and anterior commissure
12 Hypothalamus
13 Optic chiasma
14 Midbrain
15 Temporal lobe
16 Pons
17 Fourth ventricle
18 Spinal cord
19 Cerebellomedullar cistern
20 Olfactory bulb
21 Hypophysial fossa (sella turcica) with pituitary gland
22 Sphenoid sinus
23 Basilar artery
24 Ligaments to the dens of axis
25 Tongue



Median section through the head (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Median section through the head. Regions of the brain. Falx cerebri removed.

1 Frontal lobe of cerebrum
2 Occipital lobe of cerebrum
3 Corpus callosum
4 Anterior commissure
5 Lamina terminalis
6 Optic chiasma
7 Hypothalamus
8 Thalamus and third ventricle
9 Colliculi of the midbrain
10 Midbrain (inferior portion)
11 Cerebellum
12 Pons
13 Fourth ventricle
14 Medulla oblongata
15 Central canal
16 Spinal cord



Median section through the head with colored highlighting of the brain divisions.

1 Telencephalon (yellow) with lateral ventricles
2 Diencephalon (orange) with third ventricle, optic nerve, and retina
3 Mesencephalon (blue) with cerebral aqueduct
4 Metencephalon (green) with fourth ventricle
5 Myelencephalon (yellow-green)



1 Superior cerebral veins and parietal lobe
2 Frontal lobe
3 Superficial middle cerebral vein and cistern of lateral cerebral fossa
4 Temporal lobe
5 Occipital lobe
6 Inferior cerebral veins and transverse occipital sulcus
7 Inferior anastomotic vein
8 Cerebellum
9 Medulla oblongata

Brain with pia mater and arachnoid (lateral aspect). **Cerebral veins** (bluish). In the lateral sulcus the cistern of the lateral fossa is recognizable. Frontal lobe to the left.





Arteries of the brain (coronal section). Areas supplied by cortical and central arteries. Dotted lines indicate boundaries of arterial supply areas. Arrows: direction of blood flow.

◁ **Coronal section through the right hemisphere,** showing arachnoid, pia mater, and the arterial blood supply (anterior aspect).

1 Arachnoid
2 Cortex
3 Frontal lobe (white matter)
4 Caudate nucleus
5 Internal capsule
6 Insular lobe
7 Claustrum
8 Putamen
9 Middle cerebral arteries
10 Anterior cerebral artery
11 Corpus callosum
12 Septum pellucidum
13 Lateral ventricle
14 Globus pallidus and pallidostriate artery
15 Thalamic artery
16 Optic chiasma
17 Internal carotid artery
18 Posterior cerebral artery
19 Posterior striate branch
20 Insular artery



Arteries of the brain (inferior aspect, frontal pole above). Right temporal lobe and cerebellum partly removed.

1 Olfactory tract
2 Anterior cerebral artery
3 Optic nerve (n. II)
4 Middle cerebral artery
5 Infundibulum
6 Oculomotor nerve (n. III) and posterior communicating artery
7 Posterior cerebral artery
8 Basilar artery and abducent nerve (n. VI)
9 Anterior spinal artery
10 Vertebral artery
11 Cerebellum
12 Anterior communicating artery
13 Internal carotid artery
14 Superior cerebellar artery and pons
15 Labyrinthine arteries
16 Inferior anterior cerebellar artery
17 Inferior posterior cerebellar artery
18 Medulla oblongata
19 Supratrochlear artery
20 Anterior ciliary arteries
21 Lacrimal artery
22 Posterior ciliary arteries
23 Ophthalmic artery with central retinal artery
24 Trigeminal nerve (n. V)
25 Facial nerve (n. VII) and vestibulocochlear nerve (n. VIII)
26 Glossopharyngeal nerve (n. IX), vagus nerve (n. X), and accessory nerve (n. XI)
27 Olfactory bulb
28 Posterior spinal artery



Arteries of the brain (inferior aspect). Right temporal lobe and cerebellum partly removed. Note the arterial circle of Willis around the infundibulum.



1 Insula
2 Middle cerebral artery with two branches:
  a Parietal branches b Temporal branches
3 Basilar artery
4 Vertebral artery
5 Central sulcus
6 Occipital lobe
7 Superior cerebellar artery
8 Cerebellum
9 Anterior cerebral artery
10 Ethmoidal arteries
11 Ophthalmic artery
12 Internal carotid artery
13 Posterior communicating artery
14 Posterior cerebral artery
15 Anterior inferior cerebellar artery
16 Posterior inferior cerebellar artery

Arteries of the brain (lateral aspect of the left hemisphere). The upper part of the temporal lobe has been removed to display the insula and cerebral arteries (injected with red resin).



◁ **Arteries of the brain** (lateral aspect).



1 Interventricular foramen
2 Septum pellucidum
3 Frontal lobe
4 Anterior cerebral artery
5 Anterior commissure
6 Optic chiasma and infundibulum
7 Mamillary body
8 Oculomotor nerve (n. III)
9 Pons
10 Basilar artery
11 Corpus callosum
12 Fornix
13 Choroid plexus
14 Third ventricle
15 Pineal body
16 Tectum and cerebral aqueduct
17 Fourth ventricle
18 Cerebellum (arbor vitae, vermis)
19 Median aperture of Magendie
20 Medulla oblongata

Median section through the brain and brain stem. Cerebral arteries injected with red resin.

1	Skull diploe
2	Middle cerebral artery
3	Internal carotid artery
4	Anterior cerebral artery
5	Nasal cavity
6	Arterial circle of Willis
7	Vertebral artery
8	Common carotid artery
9	Subclavian artery
10	Posterior communicating artery
11	Posterior cerebral artery
12	Basilar artery
13	Aortic arch



Arteriogram of the internal carotid artery (anterior aspect, right side). (Dr. Wieners, Dept. of Radiology, Univ. Berlin, Germany.)



Arteries of the brain. Left hemisphere and brain stem have been removed. Note the arterial circle of Willis around the sella turcica.



Main arteries for brain supply (anterior aspect; MRI angiograph). (Prof. Bautz, Univ. Erlangen-Nuremberg, Germany.)



Arteriogram of the internal carotid artery (lateral aspect).
(Prof. Huck, Dept. of Neuroradiology, Univ. Erlangen-Nuremberg, Germany.)

1 Anterior cerebral artery
2 Loop of the internal carotid artery
3 Middle cerebral artery
4 Posterior cerebral artery
5 Internal carotid artery
6 Superior cerebellar artery
7 Anterior inferior cerebellar artery
8 Posterior inferior cerebellar artery
9 Vertebral artery
10 Ophthalmic artery



Arteries of the brain (lateral aspect). The areas supplied by the main arteries are indicated by different colors.



Arteriogram of the internal carotid artery. Arrow: aneurysm located in the region of the sella turcica.

Areas of blood supply of the brain
(cerebellum = light blue).
A = Anterior cerebral artery (upper and medial parts of the cortex) (orange)
B = Middle cerebral artery (lateral areas of the frontal, parietal, and temporal lobes) (white)
C = Posterior cerebral artery (occipital lobe and inferior parts of the temporal lobe) (blue)



Dissection of the arteries of the brain and head (lateral aspect). Superficial layers of facial region and left hemisphere and cerebellum partly removed.

1	Falx cerebri
2	Anterior cerebral artery
3	Frontal lobe
4	Oculomotor nerve (n. III)
5	Abducent nerve (n. VI)
6	Posterior cerebral artery
7	Internal carotid artery, entering sinus cavernosus
8	Hypoglossus nerve (n. XII)
9	Maxillary artery
10	Facial artery
11	Mandible
12	External carotid artery
13	Submandibular gland
14	Common carotid artery
15	Sternohyoid muscle
16	Calvaria
17	Dura mater
18	Subarachnoidal space
19	Occipital lobe
20	Tentorium of cerebellum
21	Cerebellum
22	Base of skull
23	Vertebral artery (on the posterior arch of the atlas)
24	Cervical plexus
25	Vertebral artery (removed from the cervical vertebrae)
26	Brachial plexus
27	Vertebral artery (branching from the subclavian artery)
28	Subclavian artery



1 Anterior cerebral artery
2 Anterior communicating artery
3 Internal carotid artery
4 Medial cerebral artery
5 Posterior communicating artery
6 Posterior cerebral artery
7 Superior cerebellar artery
8 Basilar artery
9 Anterior inferior cerebellar artery with artery of the labyrinth
10 Vertebral artery
11 Posterior inferior cerebellar artery
12 Anterior spinal artery
13 Pia mater of spinal cord
14 Cerebellar tentorium
15 Dura mater of the cranial cavity
16 Spinal cord
17 Spinal ganglion
18 Spinal nerves (C_3, C_4)
19 Posterior root filaments (fila radicularia post.)
20 Ophthalmic artery (within the orbit)
21 Internal carotid artery (within carotid canal)

I = Olfactory tract
II = Optic nerve
III = Oculomotor nerve
IV = Trochlear nerve
V = Trigeminal nerve
VI = Abducent nerve
VII = Facial nerve
VIII = Vestibulocochlear nerve
IX = Glossopharyngeal nerve
X = Vagus nerve
XI = Accessory nerve
XII = Hypoglossus nerve

Dissection of the arterial circle of Willis at the base of the skull (superior aspect). Calvaria and brain have been removed. Red = arteries; yellow = cranial nerves (n. I–n. XII).



Arterial circle of Willis at the base of the skull (superior aspect). Red = arteries; yellow = cranial nerves (n. I–n. XII).



Brain, right hemisphere (medial aspect). Midbrain divided, cerebellum and inferior part of brain stem removed. Frontal pole to the left.

Red = Frontal lobe
Blue = Parietal lobe
Green = Occipital lobe
Yellow = Temporal lobe
Dark red = Precentral lobe

Dark blue = Postcentral lobe
Dark green = Calcarine sulcus
Dark yellow = Limbic cortex (cingulate and parahippocampal gyri)



Brain (inferior aspect). Midbrain divided, cerebellum and inferior part of brain stem removed. Frontal pole at the top.

1	Precentral gyrus
2	Precentral sulcus
3	Cingulate sulcus
4	Cingulate gyrus
5	Sulcus of corpus callosum
6	Fornix
7	Genu of corpus callosum
8	Interventricular foramen
9	Intermediate mass
10	Anterior commissure
11	Optic chiasma
12	Infundibulum
13	Uncus hippocampi
14	Postcentral gyrus
15	Body of corpus callosum
16	Third ventricle and thalamus
17	Stria medullaris
18	Parieto-occipital sulcus
19	Splenium of corpus callosum
20	Communication of calcarine and parieto-occipital sulcus
21	Calcarine sulcus
22	Pineal body
23	Mamillary body
24	Parahippocampal gyrus
25	Olfactory bulb
26	Olfactory tract
27	Gyrus rectus
28	Optic nerve
29	Infundibulum and optic chiasma
30	Optic tract
31	Oculomotor nerve
32	Pedunculus cerebri
33	Red nucleus
34	Cerebral aqueduct
35	Corpus callosum
36	Longitudinal fissure
37	Orbital gyri
38	Lateral root of olfactory tract
39	Medial root of olfactory tract
40	Olfactory tubercle and anterior perforated substance
41	Tuber cinereum
42	Interpeduncular fossa
43	Substantia nigra
44	Colliculi of the midbrain
45	Lateral occipitotemporal gyrus
46	Medial occipitotemporal gyrus



Brain, left hemisphere (lateral aspect). Frontal pole to the left.

1	Central sulcus
2	Precentral gyrus
3	Precentral sulcus
4	Frontal lobe
5	Anterior ascending ramus of lateral sulcus
6	Anterior horizontal ramus of lateral sulcus
7	Lateral sulcus
8	Temporal lobe
9	Parietal lobe
10	Postcentral gyrus
11	Postcentral sulcus
12	Occipital lobe
13	Cerebellum
14	Superior frontal sulcus
15	Middle frontal gyrus
16	Lunate sulcus
17	Longitudinal fissure
18	Arachnoid granulations



Brain (superior aspect). Right hemisphere with arachnoid and pia mater.

Pink = Frontal lobe
Blue = Parietal lobe
Green = Occipital lobe
Yellow = Temporal lobe
Dark red = Precentral gyrus
Dark blue = Postcentral gyrus



Brain (superior aspect). Lobes of the left hemisphere indicated by color; right hemisphere is covered with arachnoid and pia mater.



1 Premotor area
2 Somatomotor area
3 Motor speech area of Broca
4 Acoustic area
(red: high tone, dark green: low tone)
5 Somatosensory area
6 Sensory speech area of Wernicke
7 Reading comprehension area
8 Visuosensory area

Brain, left hemisphere (lateral aspect). **Main cortical areas** are colored. The lateral sulcus has been opened to display the insula and the inner surface of the temporal lobe.



1 Precentral gyrus
2 Precentral sulcus
3 Superior frontal gyrus
4 Central sulcus
5 Middle frontal gyrus
6 Inferior frontal gyrus
7 Ascending ramus
8 Horizontal ramus } of lateral sulcus
9 Posterior ramus
10 Superior temporal gyrus
11 Middle temporal gyrus
12 Inferior temporal gyrus
13 Parietal lobe
14 Postcentral sulcus
15 Postcentral gyrus
16 Supramarginal gyrus
17 Angular gyrus
18 Occipital lobe
19 Cerebellum
20 Horizontal fissure of cerebellum
21 Medulla oblongata

Brain, left hemisphere (lateral aspect). Frontal pole to the left.



Cerebellum (infero-anterior aspect). The cerebellar peduncles have been severed.



Cerebellum (infero-posterior aspect).



Median section through the cerebellum. Right cerebellar hemisphere and right half of vermis.

1	Superior cerebellar peduncle
2	Middle cerebellar peduncle
3	Cerebellar tonsil
4	Inferior semilunar lobule
5	Vermis
6	Central lobule of vermis
7	Inferior cerebellar peduncle
8	Superior medullary velum
9	Nodule of vermis
10	Flocculus of cerebellum
11	Biventral lobule
12	Left cerebellar hemisphere
13	Inferior semilunar lobule
14	Biventral lobule
15	Vermis of cerebellum
16	Tuber of vermis
17	Pyramid of vermis
18	Uvula of vermis
19	Tonsil of cerebellum
20	Flocculus of cerebellum
21	Right cerebellar hemisphere
22	Vermis (central lobule)
23	Cerebellar lingula
24	Ala of central lobule
25	Superior cerebellar peduncle
26	Fastigium
27	Fourth ventricle
28	Middle cerebellar peduncle
29	Nodule of vermis
30	Flocculus of cerebellum
31	Cerebellar tonsil
32	Culmen of vermis
33	Declive of vermis
34	Tuber of vermis
35	Inferior semilunar lobule
36	Pyramid of vermis (cut)
37	Uvula of vermis



Brain and cerebellum (inferior aspect). Parts of the cerebellum have been removed to display the dentate nucleus and the main pathway to the midbrain (cerebellorubral tract).



Dissection of the cerebellar peduncles and their connection with midbrain and diencephalon. A small part of pulvinar thalami (✻) has been cut to show inferior brachium.

1 Olfactory bulb
2 Olfactory tract
3 Lateral olfactory stria
4 Anterior perforated substance
5 Infundibulum (divided)
6 Mamillary body
7 Substantia nigra
8 Cerebral peduncle (cut)
9 Red nucleus
10 Decussation of superior cerebellar peduncle
11 Cerebellar hemisphere
12 Medial olfactory stria
13 Optic nerve
14 Optic chiasma
15 Optic tract
16 Posterior perforated substance
17 Interpeduncular fossa
18 Superior cerebellar peduncle and cerebellorubral tract
19 Dentate nucleus
20 Vermis of cerebellum
21 Cingulate gyrus
22 Corpus callosum
23 Stria terminalis
24 Septum pellucidum
25 Columna fornicis
26 Cerebral peduncle at midbrain level
27 Pons
28 Inferior olive
29 Medulla oblongata with lateral pyramidal tract
30 Occipital lobe
31 Calcarine sulcus
32 Thalamus
33 Inferior colliculus with brachium
34 Medial lemniscus
35 Superior cerebellar peduncle
36 Inferior cerebellar peduncle
37 Middle cerebellar peduncle
38 Cerebellar hemisphere



1 Lateral longitudinal stria of indusium griseum
2 Medial longitudinal stria of indusium griseum
3 Cerebellum
4 Radiating fibers of the corpus callosum
5 Forceps minor of corpus callosum
6 Forceps major of corpus callosum
7 Splenium of corpus callosum

Dissection of the brain I. The fiber system of the corpus callosum has been displayed by removing the cortex lying above it. Frontal pole at the top.



1 Longitudinal cerebral fissure
2 Genu of corpus callosum
3 Head of caudate nucleus and anterior horn of lateral ventricle
4 Cavum of septum pellucidum
5 Septum pellucidum
6 Stria terminalis
7 Choroid plexus of lateral ventricle
8 Splenium of corpus callosum
9 Calcar avis
10 Posterior horn of lateral ventricle
11 Thalamus (lamina affixa)
12 Commissure of fornix
13 Vermis of cerebellum

Dissection of the brain II. The lateral ventricles and subcortical nuclei of the brain are dissected. The corpus callosum has been partly removed. Frontal pole at the top.



Dissection of the brain III (superior aspect of lateral ventricle and subcortical nuclei of the brain). Corpus callosum partly removed. At right, the entire lateral ventricle has been opened, the insula with claustrum and the extreme and external capsules have been removed, exposing the lentiform nucleus and the internal capsule.

1 Lateral longitudinal stria
2 Medial longitudinal stria
3 Genu of corpus callosum
4 Head of caudate nucleus
5 Septum pellucidum
6 Stria terminalis
7 Thalamus (lamina affixa)
8 Choroid plexus of third ventricle
9 Choroid plexus of lateral ventricle
10 Splenium of corpus callosum
11 Posterior horn of lateral ventricle
12 Anterior horn of lateral ventricle (head of caudate nucleus)
13 Putamen of lentiform nucleus
14 Internal capsule
15 Inferior horn of lateral ventricle
16 Pes hippocampi
17 Crus of fornix
18 Vermis of cerebellum with arachnoid and pia mater
19 Interventricular foramen
20 Right column of fornix
21 Collateral eminence



1 Lateral longitudinal stria
2 Medial longitudinal stria
3 Corpus callosum
4 Septum pellucidum
5 Insular gyri
6 Thalamostriate vein
7 Anterior tubercle of thalamus
8 Thalamus
9 Stria medullaris of thalamus
10 Habenular trigone
11 Habenular commissure
12 Vermis of cerebellum
13 Left hemisphere of cerebellum
14 Head of caudate nucleus
15 Columns of fornix
16 Putamen of lentiform nucleus
17 Internal capsule
18 Taenia of choroid plexus
19 Stria terminalis and thalamostriate vein
20 Lamina affixa
21 Third ventricle
22 Pineal body
23 Superior and inferior colliculus of midbrain

Dissection of the brain IVa. Temporal lobe, fornix, and the posterior corpus callosum have been removed (this part of the specimen is depicted below). Frontal pole at the top (superior aspect).



1 Inferior horn of lateral ventricle
2 Hippocampal digitations
3 Collateral eminence
4 Splenium of corpus callosum
5 Calcar avis
6 Posterior horn of lateral ventricle
7 Uncus of parahippocampal gyrus
8 Body and crus of fornix
9 Parahippocampal gyrus
10 Pes hippocampi
11 Dentate gyrus
12 Hippocampal fimbria
13 Lateral ventricle

Dissection of the brain IVb. Depicted is the portion of the brain removed from the specimen above: temporal lobe and limbic system. Columns of fornix are cut (superior aspect).



Dissection of the limbic system (left side, lateral aspect). Corpus callosum has been cut in the median plane. The left thalamus and the left hemisphere have been partly removed.



Main pathways of limbic and olfactory system. Blue = afferent pathways; red = efferent pathways.

1 Body of fornix
2 Septum pellucidum
3 Lateral longitudinal stria
4 Genu of corpus callosum
5 Column of fornix
6 Medial olfactory stria
7 Olfactory bulb and olfactory tract
8 Optic nerve
9 Anterior commissure (left half)
10 Right temporal lobe
11 Lateral olfactory stria
12 Amygdala
13 Body of corpus callosum
14 Interthalamic adhesion
15 Third ventricle and right thalamus
16 Mamillothalamic fasciculus
17 Part of the thalamus
18 Habenular commissure
19 Pineal body
20 Splenium of corpus callosum
21 Colliculi of midbrain
22 Vermis of cerebellum
23 Stria terminalis
24 Mamillary body
25 Fimbria of hippocampus and pes hippocampi
26 Left optic tract and lateral geniculate body
27 Lateral ventricle and parahippocampal gyrus
28 Collateral eminence
29 Hippocampal digitations
30 Supracallosal gyrus (longitudinal stria)
31 Stria medullaris of thalamus
32 Dorsomedial nucleus of thalamus
33 Mamillotegmental fasciculus
34 Dorsal longitudinal fasciculus (Schütz)



Median section through the diencephalon. Medial part of the thalamus and septum pellucidum have been removed to show the fornix and mamillothalamic fasciculus.

1	Paraventricular nucleus	Hypothalamic nuclei
2	Pre-optic nucleus	
3	Ventromedial nucleus	
4	Supra-optic nucleus	
5	Posterior nucleus	
6	Dorsomedial nucleus	
7	Mamillary body	
8	Corpus callosum	
9	Lateral ventricle (showing caudate nucleus)	
10	Anterior commissure	
11	Column of fornix	
12	Optic chiasma	
13	Crus of fornix	
14	Stria medullaris of thalamus	
15	Thalamus and interthalamic adhesion	
16	Mamillothalamic fasciculus of Vicq d'Azyr	
17	Cerebral peduncle	
18	Pineal body	
19	Tectum of midbrain	



Median section through diencephalon and midbrain. Location of the hypothalamic nuclei.



Location of the main hypothalamic nuclei.

1 Circular sulcus of insula
2 Long gyrus of insula
3 Short gyri of insula
4 Limen insulae
5 Opercula (cut)
  a Frontal operculum
  b Frontoparietal operculum
  c Temporal operculum
6 Corona radiata
7 Lentiform nucleus
8 Anterior commissure
9 Olfactory tract
10 Cerebral arcuate fibers
11 Optic radiation
12 Cerebral peduncle
13 Trigeminal nerve (n. V)
14 Flocculus of cerebellum
15 Pyramidal tract
16 Decussation of pyramidal tract
17 Internal capsule
18 Optic tract
19 Optic nerve (n. II)
20 Infundibulum
21 Temporal lobe (right side)
22 Mamillary bodies
23 Oculomotor nerve (n. III)
24 Transverse fibers of pons



Insula (Reili), left hemisphere. The opercula of the frontal, parietal, and temporal lobes have been removed to display the insular gyri.



Corona radiata, left hemisphere. Frontal pole to the left.



◁ **Corona radiata and internal capsule,** left hemisphere. Lentiform nucleus removed. Frontal pole to the left.



Dissection of the subcortical nuclei and internal capsule, left hemisphere (lateral aspect). The lateral ventricle has been opened, and the insular gyri and claustrum have been removed, revealing the lentiform nucleus and the internal capsule. Frontal pole to the left.

1 Corona radiata
2 Anterior horn of lateral ventricle
3 Head of caudate nucleus
4 Putamen
5 Anterior commissure
6 Olfactory tract
7 Amygdala
8 Hippocampal digitations
9 Internal capsule
10 Calcar avis
11 Posterior horn of lateral ventricle
12 Choroid plexus of lateral ventricle
13 Caudal extremity of caudate nucleus
14 Pulvinar of thalamus
15 Mamillary body
16 Optic tract
17 Anterior commissure
18 Fornix
19 Longitudinal stria
20 Dentate gyrus
21 Hippocampal fimbria
22 Pes hippocampi



Dissection of the limbic system and fornix, left hemisphere (lateral aspect). Frontal pole to the left.



Dissection of the brain stem and cerebellum (lateral aspect). The connections of the brain stem with the cerebellum are dissected. The amygdala of the left hemisphere is shown. The corpus callosum has been partly removed. Frontal pole to the left.

1 Anterior cerebral artery
2 Frontal lobe
3 Amygdala (amygdaloid body)
4 Olfactory tract
5 Internal carotid artery
6 Oculomotor nerve (n. III)
7 Basilar artery
8 Trigeminal nerve (n. V)
9 Hypoglossal nerve (n. XII)
10 Caudate nucleus
11 Internal capsule
12 Lentiform nucleus
13 Caudal extremity of caudate nucleus
14 Inferior colliculus of midbrain
15 Trochlear nerve (n. IV)
16 Superior cerebellar peduncle
17 Middle cerebellar peduncle
18 Cerebellum
19 Facial nerve (n. VII) and vestibulocochlear nerve (n. VIII)
20 Abducent nerve (n. VI)
21 Glossopharyngeal nerve (n. IX), vagus nerve (n. X), and accessory nerve (n. XI)
22 Inferior olive



Schematic drawing of the dissected brain stem and cerebellum shown above (lateral aspect). The course of the pyramidal tracts is indicated in red. Yellow = cranial nerves.



Cast of ventricular cavities of the brain (lateral aspect). Frontal pole to the left.

1 Central part of the lateral ventricle
2 Interventricular foramen of Monro
3 Anterior horn of the lateral ventricle
4 Site of interthalamic adhesion
5 Notch for anterior commissure
6 Third ventricle
7 Optic recess
8 Notch for optic chiasma
9 Infundibular recess
10 Inferior horn of lateral ventricle with indentation of amygdaloid body
11 Lateral recess and lateral aperture of Luschka
12 Suprapineal recess
13 Pineal recess
14 Notch for posterior commissure
15 Posterior horn of lateral ventricle
16 Cerebral aqueduct
17 Fourth ventricle
18 Median aperture of Magendie



Position of ventricular cavities.



Cast of ventricular cavities of the brain (superior aspect). Frontal pole at the top.



Cast of ventricular cavities of the brain and cerebral aqueduct (posterior aspect). Posterior horns of the lateral ventricles (15) are shown. Fourth ventricle (17) from below.



Dissection of the brain (superior aspect of the lateral ventricle and of the subcortical nuclei of the brain). Corpus callosum partly removed. Fornix and choroid plexus of the left lateral ventricle are shown.

1	Frontal lobe of brain	7	Choroid plexus of third ventricle
2	Corpus callosum	8	Body of fornix
3	Caudate nucleus (head)	9	Thalamus
4	Insular cortex	10	Choroid plexus
5	Interventricular foramen	11	Lateral ventricle (occipital horn)
6	Internal capsule	12	Occipital lobe of brain



Brain stem (anterior aspect). Cerebrum removed.



Brain stem (posterior aspect). Cerebellum removed.

1	Caudate nucleus
2	Lentiform nucleus
3	Caudal extremity of caudate nucleus
4	Amygdaloid body
5	Cerebral peduncle
6	Infundibulum
7	Pons
8	Facial and vestibulocochlear nerves (n. VII, n. VIII)
9	Cerebellar flocculus
10	Medulla oblongata
11	Accessory nerve (n. XI)
12	Fornix and column of fornix
13	Olfactory tract
14	Optic nerve (n. II)
15	Oculomotor nerve (n. III)
16	Trigeminal nerve (n. V)
17	Abducent nerve (n. VI)
18	Glossopharyngeal and vagus nerves (n. IX, n. X)
19	Inferior olive
20	Hypoglossal nerve (n. XII)
21	Decussation of the pyramids
22	Thalamus
23	Epiphysis
24	Tectum of midbrain (superior and inferior colliculus)
25	Motor nucleus of trigeminal nerve (n. V)
26	Facial nucleus (n. VII)
27	Middle cerebellar peduncle
28	Visceral nucleus of glossopharyngeal and vagus nerves (n. IX and n. X), salivatory nucleus
29	Vestibular nucleus (n. VIII)
30	Ambiguus nucleus (n. IX, n. X, n. XI)
31	Spinal nucleus of accessory nerve (n. XI)
32	Motor nucleus of oculomotor nerve (n. III)
33	Trochlear nucleus and nerve (n. IV)
34	Sensory nucleus of trigeminal nerve (n. V)
35	Abducent nucleus (n. VI)
36	Hypoglossal nucleus (n. XII)
37	Internal capsule
38	Lamina affixa
39	Third ventricle
40	Brachium of inferior colliculus
41	Superior medullary velum
42	Habenular trigone
43	Medial geniculate body
44	Superior cerebellar peduncle
45	Inferior cerebellar peduncle
46	Choroid plexus of fourth ventricle



Brain stem (posterior aspect). Location of cranial nerve nuclei.


1
2
3
4
5
6
7
8
9
10
11
13
14
15
16
17
18
19
20
21
22
23
12
24
12
25

Brain stem (left lateral aspect). Cerebellar peduncles have been severed, cerebellum and cerebral cortex have been removed.


III
IV
V
VII, VIII
VI
IX, X, XI
XII
28
19
20
24
27
29

Brain stem (lateral aspect). Note the location of the cranial nerves. III–XII = cranial nerves.


1
16
18
26
19
20
9
10
11
24
22
27

Brain stem (dorso-lateral aspect). Cerebellum removed.

1	Internal capsule
2	Head of the caudate nucleus
3	Olfactory trigone
4	Olfactory tracts
5	Optic nerves (n. II)
6	Infundibulum
7	Oculomotor nerve (n. III)
8	Amygdaloid body
9	Pons
10	Trigeminal nerve (n. V)
11	Facial and vestibulocochlear nerves (n. VII, n. VIII)
12	Hypoglossal nerve (n. XII)
13	Glossopharyngeal and vagus nerves (n. IX, n. X)
14	Inferior olive
15	Medulla oblongata
16	Lentiform nucleus
17	Anterior commissure
18	Tail of caudate nucleus
19	Superior colliculus
20	Inferior colliculus
21	Trochlear nerve (n. IV)
22	Superior cerebellar peduncle
23	Inferior cerebellar peduncle
24	Middle cerebellar peduncle
25	Accessory nerve (n. XI)
26	Pulvinar of thalamus
27	Striae medullares and rhomboid fossa
28	Pineal body
29	Clava



Coronal section through the brain at the level of the anterior commissure. Section 1.



Coronal section through the brain at the level of the third ventricle and the interthalamic adhesion. Section 2.

1	Corpus callosum
2	Head of caudate nucleus
3	Internal capsule
4	Putamen
5	Globus pallidus
6	Anterior commissure
7	Optic tract
8	Amygdaloid body
9	Inferior horn of lateral ventricle
10	Lateral ventricle
11	Septum pellucidum
12	Lobus insularis (insula)
13	External capsule
14	Column of fornix
15	Optic recess
16	Infundibulum
17	Thalamus
18	Claustrum
19	Lenticular ansa
20	Third ventricle and hypothalamus
21	Basilar artery and pons
22	Cortex of temporal lobe
23	Inferior colliculus
24	Superior colliculus
25	Cerebral aqueduct
26	Red nucleus
27	Substantia nigra
28	Cerebral peduncle
29	Trochlear nerve (n. IV)
30	Gray matter
31	Nucleus of oculomotor nerve
32	Fibers of oculomotor nerve (n. III)
33	Vermis of cerebellum
34	Fourth ventricle
35	Reticular formation
36	Pons and transverse pontine fibers
37	Emboliform nucleus
38	Dentate nucleus
39	Middle cerebellar peduncle
40	Choroid plexus
41	Hypoglossal nucleus at rhomboid fossa
42	Medial longitudinal fasciculus
43	Trigeminal nerve (n. V.)
44	Inferior olivary nucleus
45	Corticospinal fibers and arcuate fibers
46	Fourth ventricle with choroid plexus
47	Vestibular nuclei
48	Nucleus and tractus solitarius
49	Inferior cerebellar peduncle (restiform body)
50	Reticular formation
51	Medial lemniscus
52	Cuneate nucleus of Burdach
53	Central canal
54	Pyramidal tract
55	Flocculus of cerebellum
56	Cerebellar hemisphere with pia mater
57	"Arbor vitae" of cerebellum
58	Nucleus gracilis of Goll
59	Lateral recess of choroid plexus of fourth ventricle
60	Posterior inferior cerebellar artery
61	Choroid plexus of lateral ventricle


1
61
10
61
25
36

Coronal section through the brain at the level of the inferior colliculus (posterior aspect). Section 3.


23
24
25
26
27
28
29
30
31
32

Cross section through the midbrain (mesencephalon) at the level of the superior colliculus (superior aspect). Section 4.


33
34
35
36
37
38
39

Cross section through the rhombencephalon at the level of the pons (inferior aspect). Section 5.


40
41
42
43
44
45
46
47
48
49
50
51

Cross section through the rhombencephalon at the level of the olive (inferior aspect). Section 6.


33
52
53
54
55
56
57
58
44
59
60
21

Cross section through medulla oblongata and cerebellum (inferior aspect). Section 7.



Right half of the brain. Levels of the sections are indicated.



Horizontal section through the head and brain.
Section 1.



Horizontal section through the head and brain.
Section 2.

1 Skin of scalp
2 Calvaria (diploe of the skull)
3 Falx cerebri
4 Gray matter of brain (cortex)
5 Dura mater
6 White matter of brain

7 Arachnoid and pia mater with vessles
8 Subdural space (slightly expanded due to shrinkage of the brain)
9 Superior sagittal sinus
10 Anterior horn of lateral ventricle

11 Septum pellucidum
12 Choroid plexus
13 Thalamus
14 Splenium of corpus callosum
15 Parietal lobe
16 Frontal lobe

17 Anterior cerebral artery
18 Genu of corpus callosum
19 Caudate nucleus
20 Central part of lateral ventricle
21 Stria terminalis
22 Occipital lobe



Horizontal section through the head and brain at the level of section 1 (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Horizontal section through the head and brain at the level of section 2 (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)

1 Caudate nucleus
2 Lobus insularis (insula)
3 Putamen
4 Claustrum
5 External capsule
6 Internal capsule
7 Thalamus
8 Inferior sagittal sinus
9 Superior sagittal sinus
10 Skin of scalp
11 Falx cerebri
12 Calvaria (diploe of the skull)
13 Genu of corpus callosum
14 Anterior horn of lateral ventricle
15 Septum pellucidum
16 Column of fornix
17 Choroid plexus of third ventricle
18 Splenium of corpus callosum
19 Entrance to inferior horn of lateral ventricle with choroid plexus
20 Optic radiation
21 Third ventricle



Horizontal section through the head and brain at the level of third ventricle of internal capsule and neighboring nuclei. Section 3.



Horizontal section through the head and brain at the level of section 3 (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Sagittal section through the head and brain. Levels of the sections are indicated.

Brain: Horizontal Sections



Horizontal section through the brain, showing the subcortical nuclei and internal capsule. Section 1.

1	Genu of corpus callosum
2	Head of caudate nucleus
3	Putamen
4	Claustrum
5	Globus pallidus
6	Third ventricle
7	Thalamus
8	Pineal body
9	Splenium of corpus callosum
10	Choroid plexus of the lateral ventricle
11	Anterior horn of lateral ventricle
12	Cavity of septum pellucidum
13	Septum pellucidum
14	Anterior limb of internal capsule
15	Column of fornix
16	External capsule
17	Lobus insularis (insula)
18	Genu of internal capsule
19	Posterior limb of internal capsule
20	Posterior horn of lateral ventricle
21	Anterior commissure
22	Optic radiation
23	Falx cerebri
24	Maxillary sinus
25	Position of auditory tube
26	Tympanic cavity
27	External acoustic meatus
28	Medulla oblongata
29	Fourth ventricle
30	Cerebellum (left hemisphere)
31	Temporomandibular joint
32	Tympanic membrane
33	Base of cochlea
34	Mastoid air cells
35	Sigmoid sinus
36	Vermis of cerebellum
37	Intermediate mass



Horizontal section through the head and brain. Section 2.



Horizontal section through the head and brain. Section 4.



Horizontal section through the head and brain. Section 3.

1 Upper lid (tarsal plate)
2 Lens
3 Ethmoidal sinus
4 Optic nerve (n. II)
5 Internal carotid artery
6 Infundibulum and pituitary gland
7 Temporal lobe
8 Basilar artery
9 Pons (cross section of brain stem)
10 Cerebral aqueduct (beginning of fourth ventricle)
11 Vermis of cerebellum
12 Straight sinus
13 Transverse sinus
14 Nasal septum
15 Eyeball (sclera)
16 Nasal cavity
17 Lateral rectus muscle
18 Sphenoidal sinus
19 Oculomotor nerve (n. III)
20 Cerebellar tentorium
21 Skin of scalp
22 Calvaria (diploe of the skull)
23 Occipital lobe
24 Striate cortex (visual cortex)



Horizontal section through the head and brain at the level of section 3 (CT scan).



Sagittal section through the head and brain. Levels of the sections are indicated.



Longitudinal section through the right outer, middle, and inner ear (anterior aspect). The cochlea and semicircular canals have been further dissected.

1 Roof of tympanic cavity
2 Lateral osseous semicircular canal
3 Facial nerve
4 Incus
5 Malleus
6 External acoustic meatus
7 Tympanic cavity and tympanic membrane
8 Vestibulocochlear nerve
9 Anterior osseous semicircular canal
10 Geniculate ganglion and greater petrosal nerve
11 Cochlea
12 Stapes
13 Tensor tympani muscle
14 Auditory tube
15 Levator veli palatini muscle



Right auricle (lateral aspect).

◁
1 Helix
2 Scaphoid fossa
3 Triangular fossa
4 Concha
5 Antihelix
6 Tragus
7 Antitragus
8 Intertragic notch
9 Lobule



Longitudinal section through the right outer, middle, and inner ear (anterior aspect).



Right auditory and vestibular apparatus (anterior aspect).

Outer ear

1 Auricle
2 Lobule of auricle
3 Helix
4 Tragus
5 External acoustic meatus

Middle ear

6 Tympanic membrane
7 Malleus
8 Incus
9 Stapes
10 Tympanic cavity
11 Mastoid process
12 Auditory tube
13 Tensor tympani muscle

Inner ear

14 Anterior semicircular duct
15 Posterior semicircular duct
16 Lateral semicircular duct
17 Cochlea
18 Vestibulocochlear nerve (n. VIII)
19 Petrous part of the temporal bone

Additional structures

20 Superior ligament of malleus
21 Arcuate eminence
22 Internal carotid artery
23 Anterior surface of pyramid with dura mater
24 Stapes
25 Levator veli palatini muscle



Longitudinal section through the outer, middle, and inner ear (anterior aspect). Deeper dissection to display facial nerve and lesser and greater petrosal nerves.



Internal acoustic meatus, left side. The bone was partly removed to show the bottom of the meatus.

1	Anterior osseous semicircular canal (opened)
2	Posterior osseous semicircular canal
3	Lateral osseous semicircular canal (opened)
4	Facial nerve and chorda tympani
5	External acoustic meatus
6	Auricle
7	Facial nerve
8	Trigeminal nerve
9	Bony base of internal acoustic meatus
10	Internal carotid artery within cavernous sinus
11	Cochlea
12	Facial nerve with geniculate ganglion
13	Greater petrosal nerve
14	Lesser petrosal nerve
15	Tympanic cavity
16	Auditory tube
17	Levator veli palatini muscle
18	Internal carotid artery and internal jugular vein
19	Styloid process
20	Area of facial nerve
21	Superior vestibular area
22	Transverse crest
23	Foramen singulare
24	Foraminous spiral tract (outlet of cochlear part of vestibulocochlear nerve)
25	Base of cochlea



Right temporal bone (lateral aspect). Petrosquamous portion has been partly removed to display the semicircular canals.

1 Anterior semicircular canal (red)
2 Posterior semicircular canal (yellow)
3 Lateral or horizontal semicircular canal (green)
4 Fenestra vestibuli
5 Fenestra cochleae
6 Tympanic cavity
7 Mastoid process
8 Petrotympanic fissure (red probe: chorda tympani)
9 Lateral pterygoid plate
10 Mastoid air cells
11 Facial canal (blue)
12 Foramen ovale
13 Carotid canal (red)
14 Tympanic ring
15 Petromastoid part of temporal bone
16 Squamous part of temporal bone
17 Squamomastoid suture
18 Zygomatic process of temporal bone
19 Incisure of tympanic ring
20 Promontory
21 Apex of cochlea (cupula)
22 Spiral canal of cochlea at base of cochlea
23 Epitympanic recess
24 Auditory ossicles and tympanic cavity
25 Hypotympanic recess
26 Canaliculus chordae tympani (green probe)
27 Mastoid process
28 Canaliculus for stapedius nerve (red)
29 Cochlea
30 Canaliculus mastoideus (red probe)



Right temporal bone (lateral aspect). Mastoid air cells and facial canal had been opened. The three semicircular canals were dissected.



Right temporal bone of the newborn (lateral aspect).



Frontal section through the petrous part of temporal bone (CT scan).



Frontal section through the petrous part of the left temporal bone at the level of the cochlea (posterior aspect). The position of the tympanic membrane is indicated by a dotted line.



Medial wall of the tympanic cavity and its relation to neighboring structures of the inner ear, facial nerve, and blood vessels. Frontal section through the right temporal bone (anterior aspect).

1 Anterior surface of the pyramid
2 Mastoid antrum
3 Lateral semicircular canal
4 Cochleariform process
5 External acoustic meatus
6 Jugular fossa
7 Foramen lacerum
8 Apex of petrous part
9 Position of cochlea (modiolus with crista spiralis ossea)
10 Carotid canal
11 Pterygoid process
12 Anterior semicircular duct
13 Facial nerve
14 Geniculate ganglion
15 Greater petrosal nerve
16 Lesser petrosal nerve
17 Internal carotid artery
18 Mastoid air cells
19 Lateral semicircular duct
20 Posterior semicircular duct
21 Stapes with stapedius muscle
22 Stylomastoid foramen
23 Inferior recess of tympanic cavity (hypotympanon)
24 Internal jugular vein
25 Promontory with tympanic plexus (position of cochlea)
26 Tensor muscle of tympanum
27 Auditory tube



1 Head of malleus
2 Anterior ligament of malleus
3 Tendon of tensor tympani muscle
4 Handle of malleus
5 Short crus of incus
6 Long crus of incus
7 Chorda tympani
8 Lenticular process
9 Tympanic membrane

Tympanic membrane with malleus and incus (internal aspect, right side).



1 Tympanic antrum
2 Lateral semicircular canal (opened)
3 Facial canal
4 Stapes with tendon of stapedius
5 Mastoid air cells
6 Chorda tympani (intracranial part)
7 Greater petrosal nerve
8 Tensor tympani muscle (processus cochleariformis)
9 Lesser petrosal nerve
10 Anterior tympanic artery
11 Middle meningeal artery
12 Auditory tube
13 Promontory with tympanic plexus
14 Fenestra cochleae

Tympanic cavity, medial wall (left side). External acoustic meatus and lateral wall of tympanic cavity together with incus. Malleus and tympanic membrane have been removed; mastoid air cells are opened.



1 Tympanic membrane
2 Chorda tympani (intracranial part)
3 Floor of the external acoustic meatus
4 Facial nerve and facial canal
5 Incus
6 Head of malleus
7 Mandibular fossa
8 Spine of sphenoid
9 Chorda tympani (extracranial part)
10 Styloid process

Tympanic membrane (lateral aspect, left side). External acoustic meatus and facial canal have been opened to expose the chorda tympani (magn. ~1.5×).



Tympanic cavity with malleus, incus, and stapes (lateral aspect, left side). Tympanic membrane removed, mastoid antrum opened.



Chain of auditory ossicles in connection with the inner ear (antero-lateral aspect, left side).



Auditory ossicles (isolated).



Position and movements of the auditory ossicles.

Malleus
1 Head
2 Neck
3 Lateral process
4 Handle

Incus
5 Articular facet for malleus
6 Long crus
7 Short crus
8 Body
9 Lenticular process

Stapes
10 Head
11 Neck
12 Anterior and posterior crura
13 Base

Walls of tympanic cavity
14 Tympanic membrane
15 Promontory
16 Hypotympanic recess of tympanic cavity

Internal ear (labyrinth)
17 Lateral semicircular duct
18 Anterior semicircular duct
19 Posterior semicircular duct
20 Common crus
21 Ampulla
22 Beginning of endolymphatic duct
23 Utricular prominence
24 Saccular prominence
25 Incus
26 Malleus
27 Stapes
28 Cochlea

Tympanic cavity
29 Epitympanic recess
30 Mastoid antrum
31 Chorda tympani
32 Tendon of stapedius muscle
33 Round window (fenestra cochleae)



Cast of the right labyrinth (postero-medial aspect).

1	Ampulla (anterior semicircular canal)
2	Elliptical recess
3	Aqueduct of the vestibule
4	Spherical recess
5	Cochlea
6	Base of cochlea
7	Anterior semicircular canal
8	Crus commune or common limb
9	Lateral semicircular canal
10	Posterior bony ampulla
11	Posterior semicircular canal (posterior canal)
12	Fenestra cochleae
13	Bony ampulla
14	Fenestra vestibuli
15	Cupula of cochlea
16	External acoustic meatus
17	Mastoid air cells
18	Tympanic cavity and fenestra cochleae (probe)
19	External acoustic meatus
20	Facial canal
21	Base of cochlea and musculotubal canal
22	Malleus and incus
23	Stapes
24	Tympanic membrane
25	Tympanic cavity
26	Aqueduct of cochlea
27	Endolymphatic sac
28	Endolymphatic duct
29	Macula of utricle
30	Macula of saccule



Cast of the right labyrinth (lateral aspect).



Cast of the labyrinth and mastoid cells (posterior aspect). Life size.



Dissection of bony labyrinth in situ. Semicircular canals and cochlear duct opened.



Auditory and vestibular apparatus. Arrows: direction of sound waves; blue = perilymphatic ducts.



Bony labyrinth, petrous part of the temporal bone (from above). Left: semicircular canals opened; right: semicircular canals closed. Arrows: internal acoustic meatus.

1 Facial canal and semicanal of auditory tube
2 Superior vestibular area
3 Foramen ovale
4 Foramen lacerum
5 Cochlea
6 Vestibule
7 Anterior semicircular canal
8 Lateral semicircular canal
9 Posterior semicircular canal
10 Groove for sigmoid sinus
11 Sigmoid sinus
12 Tympanic cavity
13 Auditory tube
14 Mastoid air cells
15 Facial, vestibulocochlear, and intermediate nerves
16 Temporal fossa
17 Fenestra vestibuli
18 Promontory
19 Zygomatic process
20 Fenestra cochleae
21 Mastoid process



Bony labyrinth (left lateral aspect). Temporal and tympanic bone partly removed, semicircular canals opened.



Internal ear (from above). Diagram showing the position of the membranous labyrinth and the tympanic cavity.



Dissection of the brain stem showing the auditory pathway (posterior aspect). Cerebellum and posterior part of the two hemispheres have been removed.

1 Left lateral ventricle and corpus callosum
2 Thalamus
3 Pineal gland (epiphysis)
4 Superior colliculus
5 Superior medullary velum and superior cerebellar peduncle
6 Rhomboid fossa
7 Vestibulocochlear nerve (n. VIII)
8 Dorsal acoustic striae and inferior cerebellar peduncle
9 Insular lobe
10 Caudate nucleus and thalamus
11 Temporal lobe (superior temporal gyrus) (area of acoustic centers)
12 Transverse temporal gyri of Heschl (area of primary acoustic centers)
13 Acoustic radiation of internal capsule
14 Lateral geniculate body and optic radiation (cut)
15 Medial geniculate body and brachium of inferior colliculus
16 Inferior colliculus
17 Cerebral peduncle
18 Lateral lemniscus
19 Middle cerebellar peduncle
20 Dorsal (posterior) cochlear nucleus
21 Ventral (anterior) cochlear nucleus
22 Inferior olive with olivocochlear tract of Rasmussen (red)
23 Ganglion spirale
24 Obex
25 Frontal lobe
26 Temporal lobe
27 Middle temporal gyrus (area of tertiary acoustic centers)
28 Trapezoid body



Auditory pathway (compare with the dissection above).
Red = descending (efferent) pathway (olivocochlear tract of Rasmussen);
green and blue = ascending (afferent) pathways.



Auditory areas in the left hemisphere (superolateral aspect). Parts of the frontal and parietal lobes have been removed.



Bones of the left orbit (indicated by different colors).



Frontal section through the posterior part of the orbit.



Sagittal section through the orbit and eyeball.

1 Frontal bone
2 Nasal bone
3 Lacrimal bone
4 Maxilla (frontal process)
5 Ethmoidal foramina
6 Lesser wing of sphenoid bone and optic canal
7 Superior orbital fissure
8 Greater wing of sphenoid bone
9 Orbital process of palatine bone
10 Orbital plate of ethmoid bone
11 Inferior orbital fissure
12 Infra-orbital sulcus
13 Nasolacrimal canal
14 Zygomatic bone
15 Levator palpebrae superioris muscle
16 Superior rectus muscle
17 Superior oblique muscle
18 Lateral rectus muscle
19 Medial rectus muscle
20 Inferior rectus muscle
21 Optic nerve (n. II)
22 Nasal septum
23 Middle nasal concha
24 Maxillary sinus
25 Inferior nasal concha
26 Sclera
27 Ophthalmic artery
28 Orbital fatty tissue
29 Tenon's space
30 Periorbita and maxilla
31 Frontal sinus
32 Superior conjunctival fornix
33 Cornea
34 Superior tarsal plate
35 Lens
36 Inferior tarsal plate
37 Inferior conjunctival fornix
38 Inferior oblique muscle



Lids and lacrimal apparatus of the left eye (anterior aspect). Parts of the eyelids have been removed to reveal the underlying eyeball. The maxillary sinus has been opened.



Facial muscles of the left eye (anterior aspect). The orbicularis oculi muscle and its connection to the superior labial muscles are shown. Note the medial palpebral ligament (probe).

1	Orbicularis oculi muscle
2	Superior lacrimal canaliculus
3	Lacrimal sac
4	Inferior lacrimal canaliculus
5	Nasolacrimal duct
6	Inferior nasal concha
7	Upper eyelid
8	Eyeball
9	Lateral palpebral ligament
10	Infra-orbital artery and nerve
11	Maxillary sinus
12	Medial palpebral ligament
13	Levator labii superioris muscle
14	Frontal belly of occipitofrontalis muscle
15	Aponeurosis of levator palpebrae superioris muscle
16	Lacrimal gland
17	Palpebral portion of orbicularis oculi muscle
18	Infra-orbital foramen



Lacrimal apparatus of the left eye (anterior aspect).
Red = Palpebral portion of the orbicularis oculi muscle.



Right orbit with eyeball and extra-ocular muscles (from above). Levator palpebrae superioris muscle has been severed.



Action of the extra-ocular muscles (anterior aspect).

A = Superior rectus muscle
B = Inferior oblique muscle
C = Medial rectus muscle
D = Lateral rectus muscle
E = Inferior rectus muscle
F = Superior oblique muscle



Right orbit with eyeball and extra-ocular muscles (from above). The roof of the orbit has been removed, the superior rectus muscle and the levator palpebrae superioris muscle have been severed.



Left orbit with eyeball and extra-ocular muscles (anterior aspect). Lids, conjunctiva, and lacrimal apparatus have been removed.

1 Inferior oblique muscle
2 Trochlea
3 Tendon of superior oblique muscle
4 Superior oblique muscle and ethmoid air cells
5 Medial rectus muscle
6 Inferior rectus muscle
7 Optic nerve (extracranial part)
8 Optic nerve (intracranial part)
9 Cornea
10 Superior rectus muscle
11 Lateral rectus muscle
12 Levator palpebrae superioris muscle
13 Common annular tendon
14 Internal carotid artery
15 Optic chiasma
16 Sclera
17 Nasal bone
18 Nasolacrimal duct
19 Zygomatic bone
20 Infra-orbital nerves
21 Maxilla



Extra-ocular muscles and their nerves (lateral aspect of the left eye). Lateral rectus muscle divided and reflected.



Left orbit with extra-ocular muscles (anterior aspect). Eyeball removed.



Extra-ocular muscles (antero-lateral aspect).

1	Supra-orbital nerve
2	Cornea
3	Insertion of lateral rectus muscle
4	Eyeball (sclera)
5	Inferior oblique muscle
6	Inferior rectus muscle and inferior branch of oculomotor nerve
7	Infra-orbital nerve
8	Superior rectus muscle and lacrimal nerve
9	Optic nerve (n. II)
10	Lateral rectus muscle
11	Ciliary ganglion and abducens nerve (n. VI)
12	Oculomotor nerve (n. III)
13	Trochlear nerve (n. IV)
14	Ophthalmic nerve (n. V_1) and maxillary nerve (n. V_2)
15	Trochlea and tendon of superior oblique muscle
16	Superior oblique muscle
17	Medial rectus muscle
18	Levator palpebrae superioris muscle
19	Superior rectus muscle
20	Inferior rectus muscle
21	Greater alar cartilage
22	Supra-orbital nerve and levator palpebrae superioris muscle
23	Levator labii superioris muscle

112897_S_107_144_Kap_2_4:_ 06.11.2014 9:09 Uhr Seite 138



Superficial layer of the left orbit (superior aspect). The roof of the orbit and a portion of the left tentorium have been removed.



Middle layer of the left orbit (superior aspect). The roof of the orbit has been removed and the superior extra-ocular muscles have been divided and reflected.

1 Lateral branch of frontal nerve
2 Lacrimal gland
3 Lacrimal vein
4 Lacrimal nerve
5 Frontal nerve
6 Superior rectus
7 Middle cranial fossa
8 Abducent nerve (n. VI)
9 Trigeminal nerve (n. V)
10 Trochlear nerve (intracranial part)
11 Frontal sinus
12 Levator palpebrae superioris muscle
13 Branches of supratrochlear nerve
14 Olfactory bulb
15 Superior oblique muscle
16 Trochlear nerve (intra-orbital part)
17 Optic nerve (intracranial part)
18 Pituitary gland and infundibulum
19 Dorsum sellae
20 Oculomotor nerve (n. III)
21 Midbrain
22 Tendon of superior oblique muscle
23 Eyeball
24 Vena vorticosa
25 Short ciliary nerves
26 Optic nerve (extracranial part)
27 Trigeminal ganglion


33
12
2
6
23
24
25
34
35
36
30
5
7
27
8
10
9
37
38
15
28
39
40
41
28
42
43
44
17
18
20
45

Middle layer of the left orbit (superior aspect). The roof of the orbit and the superior extra-ocular muscles have been removed.


38
33
24
2
46
25
35
47
7
8
48
27
8
9
11
15
23
39
40
30
49
50
44
28
51
18
20
10
45

Deeper layer of the left orbit (superior aspect). The optic nerve has now been removed.

28 Ophthalmic artery
29 Superior ophthalmic vein
30 Nasociliary nerve
31 Levator palpebrae superioris muscle (reflected)
32 Superior rectus muscle (reflected)
33 Lateral branch of supra-orbital nerve
34 Lacrimal nerve and artery
35 Lateral rectus muscle
36 Meningolacrimal artery (anastomosing with middle meningeal artery)
37 Trochlea
38 Medial branch of supra-orbital nerve
39 Medial rectus muscle
40 Anterior ethmoidal artery and nerve
41 Long ciliary nerve
42 Superior oblique muscle and trochlear nerve
43 Common tendinous ring
44 Olfactory tract
45 Basilar artery and pons
46 Optic nerve (external sheath of optic nerve, divided)
47 Ciliary ganglion
48 Ophthalmic nerve (divided, reflected)
49 Inferior branch of oculomotor nerve and inferior rectus muscle
50 Superior branch of oculomotor nerve
51 Internal carotid artery



Anterior segment of the human eye. Note the colored iris and the location of the lens behind the iris.



Anterior segment of the eyeball (posterior aspect). The opacity of the lens is an artifact.



Organization of the eyeball (sagittal section).
Red lines = projection of the light on the fovea centralis.



Sagittal section through the orbit and eyeball (MRI scan).
(Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)

1 Fold of iris
2 Pupillary margin of iris
3 Anterior surface of the lens
4 Inner border of iris
5 Outer border of iris
6 Corneal limbus
7 Sclera
8 Zonular fibers
9 Ciliary body
  a Ciliary processes (pars plicata)
  b Ciliary ring (pars plana)
10 Ora serrata
11 Retina
12 Choroid
13 Posterior surface of the lens
14 Optic nerve (n. II)
15 Central retinal artery and vein
16 Ciliary muscle
17 Cornea
18 Iris
19 Orbital bone
20 Superior rectus muscle
21 Vitreous body
22 Lens
23 Inferior rectus muscle
24 Maxillary sinus

112897_S_107_144_Kap_2_4:_ 06.11.2014 9:09 Uhr Seite 141



Fundus of a normal right eye. Notice, the arteries are smaller and lighter than the veins. (Courtesy of Prof. Okamura, Eye Dept., Univ. Kumamoto, Japan.)

1 Superior macular artery
2 Superior temporal artery and vein of retina
3 Medial artery and vein of retina
4 Fovea centralis and macula lutea
5 Inferior macular artery
6 Inferior temporal artery and vein of retina
7 Optic disc
8 Superior temporal artery of retina
9 Superior nasal artery of retina
10 Inferior temporal artery of retina
11 Inferior nasal artery of retina
12 Posterior and anterior ethmoidal arteries
13 Long and short posterior ciliary arteries
14 Optic nerve (n. II) and ophthalmic artery
15 Central retinal artery
16 Retinal arteries
17 Supratrochlear artery
18 Supra-orbital artery
19 Anterior ciliary artery
20 Dorsal nasal artery
21 Iridial arteries
22 Lens



Fluorescent angiography of the right eye (the same eye as above). The retinal vessels are shown. (Courtesy of Prof. Okamura, Eye Dept., Univ. Kumamoto, Japan.)



Orbit with eyeball, optic nerve, and vessels of the eye. The ophthalmic artery and its branches are shown.



1	Upper lid
2	Cornea
3	Eyeball (sclera, retina)
4	Head of optic nerve
5	Optic nerve
6	Optic chiasma
7	Infundibular recess of hypothalamus
8	Amygdaloid body
9	Substantia nigra and crus cerebri
10	Cerebral aqueduct
11	Vermis of cerebellum
12	Falx cerebri
13	Lateral rectus muscle
14	Optic canal
15	Internal carotid artery
16	Optic tract
17	Hippocampus
18	Inferior horn of lateral ventricle
19	Cerebellar tentorium
20	Optic radiation of Gratiolet
21	Visual cortex (area calcarina, striate cortex)
22	Lens
23	Eyeball
24	Medial rectus muscle
25	Cerebral peduncle
26	Ethmoidal cells
27	Optic nerve (n. II) with dura sheath
28	Temporal muscle
29	Oculomotor nerve (n. III) and pituitary gland (hypophysis)

Horizontal section through the head at the level of optic chiasma and striate cortex (superior aspect). Note the relationship of hypothalamic infundibulum to optic chiasma.



Horizontal section through the head at the level of sella turcica (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Diagram of the visual pathway and path of the light reflex.



30	Midbrain
31	Occipital lobe
32	Long and short ciliary nerves
33	Ciliary ganglion
34	Oculomotor nerve (n. III) within the cavernous sinus
35	Accessory oculomotor nuclei
36	Colliculi of midbrain
37	Corpus callosum
38	Visual field
39	Retina
40	Lateral geniculate body
41	Frontal lobe
42	Caudate nucleus
43	Skin of scalp
44	Diploe of the skull
45	Dura mater
46	Thalamus
47	Anterior cerebral artery
48	Frontal sinus
49	Internal capsule
50	Lentiform nucleus (putamen)
51	Hippocampus
52	Temporal lobe of the left hemisphere

3-D reconstruction of the human visual pathway (MRI scan). (Prof. Huk, Univ. Erlangen-Nuremberg, Germany.)



Dissection of brain stem in situ. Left hemisphere has been partly removed (compare with the MRI scan above).

In **binocular vision** the visual field (38) is projected upon portions of both retinae (blue and red in the drawing). In the chiasma the fibers from the two retinal portions are combined to form the left optic tract. The fibers of the two eyes remain separated from each other throughout the entire visual pathway up to their final termination in the visual cortex (21). **Injuries on the optic pathway** produce visual defects whose nature depends on the location of the injury. Destruction of one optic nerve (A) produces **blindness in the corresponding eye** with loss of pupillary light reflex. If **lesions of the chiasma** destroy the crossing fibers of the nasal portions of the retina (B), both temporal fields of vision are lost **(bitemporal hemianopsia)**. If both lateral angles of the chiasma are compressed (C), the nondecussating fibers from the temporal retinae are affected, resulting in loss of nasal visual fields **(binasal hemianopsia)**. Lesions posterior to the chiasma (D) (i.e., optic tract, lateral geniculate body, optic radiation, or visual cortex) result in a loss of the entire opposite field of vision **(homonymous hemianopsia)**.



Dissection of the visual pathway (inferior aspect). The midbrain is divided. Frontal pole at the top.

1 Medial olfactory stria
2 Olfactory trigone
3 Lateral olfactory stria
4 Anterior perforated substance
5 Oculomotor nerve (n. III)
6 Mamillary body
7 Cerebral peduncle
8 Lateral geniculate body
9 Medial geniculate body
10 Pulvinar of thalamus
11 Optic radiation
12 Splenium of the corpus callosum (commissural fibers)
13 Cuneus
14 Olfactory bulb
15 Olfactory tract
16 Optic nerve (n. II)
17 Infundibulum
18 Anterior commissure
19 Genu of optic radiation
20 Optic tract
21 Interpeduncular fossa and posterior perforated substance
22 Trochlear nerve (n. IV)
23 Substantia nigra
24 Cerebral aqueduct
25 Visual cortex
26 Line of Gennari
27 Gyrus of striate cortex
28 Calcarine sulcus



Frontal section of the striate cortex at the level of the striate area in the occipital lobe.

2.5 Nasal and Oral Cavities



Median sagittal section through the head. The palate separates nasal and oral cavities. The base of the skull forms an angle of about 150° at the sella turcica (dotted line).



Median sagittal section through the head. The tongue has been disposed to show the connection of the oral cavity with the pharynx and the position of the palatine tonsil.

1	Hypophysis within hypophysial fossa
2	Frontal sinus
3	Middle nasal concha
4	Inferior nasal concha
5	Hard palate
6	Soft palate
7	Pharynx with auditory tube
8	Tongue
9	Pharynx with palatine tonsil
10	Mandible
11	Larynx



Lateral wall of the nasal cavity. Septum removed.

1	Sphenoidal sinus
2	Superior meatus
3	Middle meatus
4	Tubal elevation
5	Pharyngeal tonsil
6	Pharyngeal orifice of auditory tube
7	Salpingopharyngeal fold
8	Pharyngeal recess
9	Soft palate
10	Uvula
11	Frontal sinus
12	Spheno-ethmoidal recess
13	Superior nasal concha
14	Middle nasal concha
15	Inferior nasal concha
16	Vestibule
17	Inferior meatus
18	Hard palate
19	Grooves for the middle meningeal artery and parietal bone (yellow)
20	Maxillary hiatus
21	Perpendicular process of palatine bone
22	Openings of ethmoidal air cells
23	Nasofrontal duct
24	Medial pterygoid plate (red)
25	Horizontal plate of palatine process
26	Ethmoidal air cells
27	Maxillary sinus
28	Nasal septum
29	Pterygoid hamulus
30	Nasal bone (white)
31	Frontal process of maxilla (violet)
32	Palatine process of maxilla (violet)
33	Nasal atrium



Bones of the left nasal cavity (medial aspect).



Paranasal sinuses and their connections with the nasal cavity. Openings indicated by arrows.



Median section through the head with nasal and oral cavities. The middle and inferior nasal conchae have been partly removed to show the openings of paranasal sinuses.

1 Great cerebral vein (Galen's vein)
2 Tectum of midbrain
3 Straight sinus
4 Sphenoidal sinus



Lateral wall of the nasal cavity. Openings indicated by arrows.

5 Cerebellum
6 Pharyngeal tonsil
7 Cerebellomedullary cistern
8 Median atlanto-axial joint
9 Spinal cord
10 Oral part of pharynx
11 Falx cerebri
12 Corpus callosum and anterior cerebral artery
13 Frontal sinus
14 Optic chiasm and pituitary gland
15 Superior nasal concha and ethmoidal bulla
16 Semilunar hiatus
17 Accessory openings to maxillary sinus and cut edge of middle nasal concha
18 Vestibule
19 Opening of nasolacrimal duct
20 Inferior nasal concha (cut)
21 Opening of auditory tube
22 Incisive canal
23 Levator veli palatini muscle
24 Salpingopharyngeal fold
25 Lingual nerve and submandibular ganglion
26 Submandibular duct
27 Spheno-ethmoidal recess
28 Superior nasal meatus
29 Salpingopalatine fold
30 Nasofrontal duct
31 Nasolacrimal duct

Nasal Cavity: Nerves and Arteries



Nerves of the lateral wall of nasal cavity (sagittal section through the head). Mucous membranes partly removed, pterygoid canal opened.



Nasal septum. Dissection of nerves and vessels.

1	Facial nerve
2	Internal carotid artery and internal carotid plexus
3	Superior cervical ganglion
4	Vagus nerve (n. X)
5	Sympathetic trunk
6	Optic nerve (n. II) and ophthalmic artery
7	Oculomotor nerve (n. III)
8	Internal carotid artery and cavernous sinus
9	Sphenoidal sinus
10	Nerve of the pterygoid canal
11	Pterygopalatine ganglion
12	Descending palatine artery
13	Lateral inferior posterior nasal branches and lateral posterior nasal and septal arteries
14	Greater palatine nerves and artery
15	Lesser palatine nerves and arteries
16	Branches of ascending pharyngeal artery
17	Lingual artery
18	Epiglottis
19	Anterior ethmoidal artery
20	Olfactory bulb
21	Olfactory tract
22	Nasopalatine nerve
23	Choanae
24	Frontal sinus
25	Crista galli
26	Anterior ethmoidal artery and nerve, and nasal branch of anterior ethmoidal artery
27	Nasal septum
28	Septal artery
29	Crest of nasal septum
30	Hard palate
31	Cerebellar tentorium
32	Trochlear nerve (n. IV)
33	Trigeminal nerve (n. V) with motor root
34	Internal carotid plexus
35	Lingual nerve with chorda tympani
36	Medial pterygoid muscle and medial pterygoid plate
37	Inferior alveolar nerve
38	Sympathetic trunk
39	Greater petrosal nerve
40	Palatine nerves
41	Tongue
42	Olfactory bulb
43	Ophthalmic nerve (n. V_1)
44	Trigeminal ganglion


31
32
33
2
10
34
35
36
15
37
3
17
38
4
39
24
9
11
40
12
14
41

Nerves of the lateral wall of nasal cavity (sagittal section through the head). Carotid canal opened, mucous membranes of pharynx and nasal cavity partly removed.

45 Maxillary nerve (n. V_2)
46 Mandibular nerve (n. V_3)
47 Deep petrosal nerve
48 Medial pterygoid muscle
49 Tensor veli palatine muscle
50 Greater palatine nerve
51 Olfactory nerves
52 Internal and medial nasal branches of anterior ethmoidal nerve
53 Lateral superior posterior nasal branches
54 Lateral inferior posterior nasal branches
55 Incisive canal with nasopalatine nerve
56 Uvula


42
2
43
44
33
45
46
39
47
11
48
49
40
50
51
52
53
54
55

Nerves of the lateral wall of nasal cavity (sagittal section).

112897_S_145_155_Kap_2_5:_ 06.11.2014 9:15 Uhr Seite 150



Horizontal section through the nasal cavity, the orbits, and temporal lobes of the brain at the level of pituitary gland.



Horizontal section through the nasal cavity, the orbits, and temporal lobes of the brain (CT scan). Bar = 2 cm. Arrow: fracture.

1	Cornea
2	Lens
3	Vitreous body (eyeball)
4	Head of optic nerve
5	Medial rectus muscle
6	Lateral rectus muscle
7	Optic nerve with dural sheath
8	Internal carotid artery
9	Pituitary gland and infundibulum
10	Oculomotor nerve
11	Superior tarsal plate of eyelid
12	Fornix of conjunctiva
13	Nasal cavity
14	Sclera
15	Ethmoidal sinus
16	Nasal septum
17	Sphenoidal sinus
18	Temporal lobe
19	Clivus
20	Middle cranial fossa
21	External acoustic meatus
22	Superior sagittal sinus
23	Falx cerebri
24	Superior rectus and levator palpebrae superioris muscles
25	Eyeball and lacrimal gland
26	Inferior rectus and inferior oblique muscles
27	Zygomatic bone
28	Maxillary sinus
29	Inferior nasal concha
30	Hard palate


22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
16
28
39
40
41
42
43

Coronal section through the head at the level of the second premolar of the mandible.


36
37
24
44
38
15
26
28
16
29
30
32
39
42
34
35

Coronal section through the head (MRI scan).
(Prof. Heuck, Munich, Germany.) Note the situation of the head cavities.


36
37
25
15
38
16
29
28
30
31
32
33
34
42
35
43
46
45
47

31	Superior longitudinal muscle of tongue
32	Lingual septum
33	Inferior longitudinal muscle of tongue
34	Sublingual gland
35	Mandible
36	Calvaria
37	Frontal lobe of brain and crista galli
38	Lateral and medial rectus muscles
39	Buccinator muscle
40	Vertical and transverse muscles of tongue
41	Second premolar of the mandible
42	Genioglossus muscle
43	Platysma muscle
44	Orbit and optic nerve (n. II)
45	Hyoid bone
46	Mylohyoid muscle
47	Submandibular gland

◁ **Coronal section through the head** at the level of the second premolar of the mandible.

Oral Cavity: Hyoid Bone and Muscles



1 Nasal cavity
2 Hard palate
3 Upper lip and orbicularis oris muscle
4 Vestibule of oral cavity
5 First incisor
6 Lower lip and orbicularis oris muscle
7 Mandible
8 Genioglossus muscle
9 Geniohyoid muscle
10 Anterior belly of diagastric muscle
11 Mylohyoid muscle
12 Hyoid bone
13 Nasopharynx
14 Soft palate and uvula
15 Oropharynx
16 Root of tongue and lingual tonsil
17 Laryngopharynx
18 Epiglottis
19 Ary-epiglottic fold
20 Laryngopharynx continuous with esophagus
21 Larynx

Median sagittal section through the oral cavity and pharynx.



Hyoid bone (oblique-lateral aspect).



Hyoid bone (anterior aspect).

1 Greater cornu
2 Lesser cornu } of hyoid bone
3 Body



Muscles of the floor of the oral cavity (superior aspect).

1 Lesser cornu and body of hyoid bone
2 Hyoglossus muscle (divided)
3 Ramus of mandible and inferior alveolar nerve
4 Geniohyoid muscle
5 Genioglossus muscle (divided)
6 Stylohyoid muscle (divided)



Muscles of the floor of the oral cavity (inferior aspect). Cut on the base.

7 Mylohyoid muscle
8 Anterior belly of digastric muscle
9 Hyoid bone
10 Mandible
11 Intermediate tendon of digastric muscle



Parapharyngeal and sublingual regions. Innervation of the tongue. Lateral part of face and mandible removed, oral cavity opened. Arrow: submandibular duct.



Supra- and infrahyoid muscles and pharynx.

1 Styloid process
2 Styloglossus muscle
3 Posterior belly of digastric muscle
4 Vagus nerve (n. X)
5 Lingual nerve (n. V_3)
6 Glossopharyngeal nerve (n. IX)
7 Submandibular ganglion
8 Hyoglossus muscle
9 Hypoglossal nerve (n. XII)
10 Stylohyoid muscle
11 Internal branch of superior laryngeal nerve (branch of vagus nerve, not visible)
12 Middle constrictor muscle of pharynx
13 Omohyoid muscle (divided)
14 Thyrohyoid muscle
15 Sternothyroid muscle
16 Esophagus
17 Parotid duct (divided)
18 Buccinator muscle
19 Superior constrictor muscle of pharynx
20 Tongue
21 Terminal branches of lingual nerve
22 Mandible (divided)
23 Genioglossus and geniohyoid muscles
24 Mylohyoid muscle (divided and reflected)
25 Sternohyoid muscle (divided)
26 Thyroid cartilage
27 Hyoid bone
28 Trachea



Submandibular triangle, superficial dissection. Right side (inferior aspect). Submandibular gland has been reflected.



Submandibular triangle, deep dissection. Right side (inferior aspect). Mylohyoid muscle has been severed and reflected to display the lingual and hypoglossal nerves.

1 Parotid gland and retromandibular vein
2 Sternocleidomastoid muscle
3 Retromandibular vein, submandibular gland, and stylohyoid muscle
4 Hypoglossal nerve and lingual artery
5 Vagus nerve and internal jugular vein
6 Superior laryngeal artery
7 External carotid artery, thyrohyoid muscle, and superior thyroid artery
8 Common carotid artery and superior root of ansa cervicalis
9 Omohyoid and sternohyoid muscles
10 Masseter muscle and marginal mandibular branch of facial nerve
11 Facial artery and vein
12 Mandible and submental artery and vein
13 Mylohyoid nerve
14 Submandibular duct, sublingual gland, and anterior belly of digastric muscle
15 Mylohyoid muscle
16 Mylohyoid muscle and anterior belly of left digastric muscle
17 Hyoglossus muscle and lingual artery
18 Lingual nerve
19 Hypoglossal nerve
20 Geniohyoid muscle
21 Anterior belly of right digastric muscle
22 Submandibular gland and duct



Oral cavity (internal aspect). Tongue and pharyngeal wall removed.

1	Medial pterygoid muscle
2	Sublingual papilla
3	Submandibular duct
4	Sublingual gland
5	Lingual nerve
6	Hypoglossal nerve
7	Mylohyoid muscle
8	Geniohyoid muscle
9	Anterior belly of digastric muscle
10	Inferior alveolar nerve
11	Chorda tympani
12	Internal carotid artery
13	Parotid gland
14	Sphenomandibular ligament
15	Vagus nerve
16	Glossopharyngeal nerve
17	Superficial temporal artery and ascending pharyngeal artery
18	Styloglossus muscle
19	Posterior belly of digastric muscle
20	Facial artery
21	Submandibular gland
22	External carotid artery
23	Lingual artery
24	Middle pharyngeal constrictor muscle
25	Stylohyoid ligament
26	Hyoglossus muscle
27	Deep lingual artery
28	Epiglottis
29	Hyoid bone
30	Buccinator muscle
31	Tongue
32	Mandible (divided)
33	Parotid duct
34	Masseter muscle
35	Right and left sublingual caruncle
36	Left sublingual caruncle



Dissection of the major salivary glands (infero-lateral aspect). Left mandible and buccinator muscle partly removed to view the oral cavity.



Location of the major salivary glands (lateral aspect) in relation to the oral cavity.

2.6 Neck and Organs of the Neck



Regional anatomy of the neck (anterior aspect). The anteriorly located muscles and the thoracic wall have been removed.



1 Submandibular gland
2 Hyoid bone
3 Larynx (thyroid cartilage)
4 Nerves and vessels of the neck
(carotid artery, internal jugular vein, and vagus nerve)
5 Thyroid gland
6 Trachea
7 Aortic arch

Organs of the neck (anterior aspect). The main arterial trunks are indicated in red.

1 Nasal septum
2 Uvula
3 Genioglossus muscle
4 Mandible
5 Geniohyoid muscle
6 Mylohyoid muscle
7 Hyoid bone
8 Thyroid cartilage
9 Manubrium sterni
10 Sphenoidal sinus
11 Nasopharynx
12 Oropharynx
13 Epiglottis
14 Laryngopharynx
15 Arytenoid muscle
16 Vocal fold
17 Cricoid cartilage
18 Trachea
19 Left brachiocephalic vein
20 Thymus
21 Esophagus



Regions and triangles of the neck (oblique-lateral aspect).

1 Submental triangle
2 Submandibular triangle
3 Carotid triangle
4 Muscular triangle
Anterior cervical region
5 Jugular fossa
6 Sternocleidomastoid region
7 Posterior cervical region
8 Lateral cervical region
9 Greater supraclavicular fossa (supraclavicular triangle)
10 Lesser supraclavicular fossa



Median section through adult head and neck. Note the low position of the adult larynx when compared with that of the neonate (compare with the dissection below).



Median section through neonate head and neck. Note the high position of the larynx permitting the epiglottis to nearly reach the uvula (compare with the dissection above).



Muscles of the neck (anterior aspect). Sternocleidomastoid and sternohyoid muscles on the right have been divided and reflected.

1	Mandible
2	Hyoid bone
3	Thyrohyoid muscle
4	Sternothyroid muscle
5	Thyroid gland
6	Second rib
7	Anterior belly of digastric muscle
8	Mylohyoid muscle (and mylohyoid raphe)
9	Omohyoid muscle
10	Thyroid cartilage
11	Sternocleidomastoid muscle
12	Sternohyoid muscle
13	Clavicle
14	Subclavius muscle
15	Posterior belly of digastric muscle
16	Stylohyoid muscle
17	Scalene muscles
18	Trapezius muscle
19	First rib
20	Scapula
21	Trachea
22	Manubrium sterni



Muscles of the neck (anterior aspect).

The muscles of the neck are complex and highly sophisticated. There are two major groups of muscles to be distinguished according to their functional aspects. One group is constituted by muscles connecting head to the hyoid bone and the larynx. The second category of muscles links the head and the ribcage.

The sternocleidomastoid muscle represents the border between the anterior and posterior cervical triangle.

112897_S_156_178_Kap_2_6:_ 06.11.2014 9:18 Uhr Seite 159

1	Sternohyoid and thyrohyoid muscles
2	Larynx
3	Cricoid cartilage
4	Internal jugular vein, common carotid artery, and vagus nerve
5	Esophagus
6	Body of cervical vertebra
7	Vertebral artery
8	Spinal cord
9	Posterior scalene muscle
10	Deep muscles of the neck
11	Trapezius muscle
12	Omohyoid muscle
13	Thyroid gland
14	Sternocleidomastoid muscle
15	Sympathetic trunk
16	Longus colli muscle
17	Anterior scalene muscle
18	Longissimus capitis muscle
19	Middle scalene muscle
20	Ventral and dorsal root of cervical spinal nerve
21	Trachea
22	Vertebral artery and vein, and foramen transversarium
23	Cervical spinal nerve
24	Superior facet of articular process
25	Spinous process
26	Sternohyoid and sternothyroid muscles



Axial section through the neck at the level of the intervertebral disc between the fifth and sixth cervical vertebrae (inferior aspect).



Organization of the neck (axial section at the level of the thyroid gland).



Axial section through the neck at the level of the fourth cervical vertebra (MRI scan). (From Heuck et al., MRT-Atlas, 2009.)



Cartilages of the larynx and the hyoid bone (anterior aspect).



Cartilages of the larynx and the hyoid bone (posterior aspect).

1 Epiglottis
2 Lesser cornu of hyoid bone
3 Greater cornu of hyoid bone
4 Lateral thyrohyoid ligament
5 Body of hyoid bone
6 Superior cornu of thyroid cartilage
7 Thyro-epiglottic ligament
8 Conus elasticus
9 Cricothyroid ligament
10 Thyroid cartilage
11 Cricoid cartilage
12 Trachea
13 Corniculate cartilage
14 Arytenoid cartilage
15 Posterior crico-arytenoid ligament
16 Cricothyroid joint
17 Crico-arytenoid joint



Cartilages of the larynx (anterior aspect). Thyroid cartilage is indicated by the outline.



Cartilages and ligaments of the larynx (lateral aspect).

1 Hyoid bone
2 Epiglottis
3 Thyrohyoid membrane
4 Thyroid cartilage
5 Vocal ligament
6 Conus elasticus
7 Arytenoid cartilage
8 Cricoid cartilage
9 Crico-arytenoid joint
10 Cricothyroid joint
11 Tracheal cartilages
12 Corniculate cartilage
13 Muscular process of arytenoid cartilage
14 Vocal process of arytenoid cartilage
15 Lamina of cricoid cartilage
16 Arch of cricoid cartilage



Cartilages of the larynx (oblique-posterior aspect).



Cartilages of the larynx (oblique-posterior aspect).

1 Vocal ligament
2 Lateral thyrohyoid ligament
3 Greater cornu of hyoid bone
4 Epiglottis
5 Thyroid cartilage
6 Corniculate cartilage
7 Arytenoid cartilage
8 Crico-arytenoid joint
9 Cricothyroid joint
10 Cricoid cartilage
11 Trachea



Thyroid cartilage (lateral aspect).



Thyroid cartilage (anterior aspect).

1 Superior cornu
2 Superior thyroid tubercle
3 Lamina of thyroid cartilage
4 Inferior thyroid tubercle
5 Inferior cornu
6 Superior thyroid notch



1 Atlas
2 Axis
3 Cervical vertebrae II–VII
4 Mandible
5 Stylohyoid ligament
6 Hyoid bone
7 Epiglottis
8 Thyroid cartilage
9 Arytenoid cartilage
10 Cricoid cartilage
11 Tracheal cartilages
12 First rib
13 Manubrium of sternum

Position of the larynx and hyoid bone in the neck (oblique-lateral aspect).


1
2
3
4
5
6
7
8
9
2
6
10
11
12
13
14
15
16
17

Laryngeal muscles (lateral aspect).
Thyroid cartilage and thyro-arytenoid muscle have been partly removed.


2
3
4
5
6
18
7
8
1
2
12
19
20
13
14
16
17

Laryngeal muscles (lateral aspect).
Half of the thyroid cartilage has been removed. Dissection of the vocal ligament.

1	Hyoglossus muscle
2	Hyoid bone
3	Epiglottis
4	Thyrohyoid membrane
5	Superior cornu of thyroid cartilage
6	Superior laryngeal nerve
7	Transverse arytenoid muscle
8	Posterior crico-arytenoid muscle
9	Transverse muscle of trachea
10	Ary-epiglottic fold
11	Thyro-epiglottic muscle
12	Thyroid cartilage
13	Lateral crico-arytenoid muscle
14	Cricoid cartilage
15	Articular facet for thyroid cartilage
16	Inferior laryngeal nerve (branch of recurrent nerve)
17	Trachea
18	Arytenoid cartilage
19	Vocal ligament
20	Vocalis muscle (part of thyro-arytenoid muscle)
21	Thyrohyoideus muscle
22	Cricothyroideus muscle
23	Root of tongue
24	Cuneiform tubercle
25	Corniculate tubercle
26	Ary-epiglottic muscle


1
2
4
21
12
22
14
17

Laryngeal muscles and larynx
(anterior aspect).


23
2
24
25
6
3
10
5
26
12
7
8
16
9

Laryngeal muscles and larynx
(posterior aspect).


2
3
4
5
18
7
8
9
19
20
13
14
15
17

Action of internal muscles of the larynx.

1 Hyoid bone
2 Epiglottis
3 Thyroid cartilage
4 Cricoid cartilage
5 Vocal ligament
6 Thyrohyoid ligament
7 Arytenoid cartilage
8 Corniculate cartilage
9 Vocal fold
10 Vestibular fold
11 Ary-epiglottic fold
12 Interarytenoid notch
13 Mandible
14 Anterior belly of digastric muscle
15 Mylohyoid muscle
16 Pyramidal lobe of thyroid gland
17 Sternohyoid and sternothyroid muscles
18 Common carotid artery
19 Internal jugular vein
20 Rima glottidis
21 Sternocleidomastoid muscle
22 Transverse arytenoid muscle
23 Pharynx and inferior constrictor muscle
24 Ventricle of larynx
25 Vocalis muscle
26 Trachea
27 Superior cornu of thyroid cartilage
28 Root of tongue (lingual tonsil)
29 Piriform recess
30 Vocalis muscle
31 Lateral crico-arytenoid muscle
32 Thyroid gland



Laryngeal cartilages (superior aspect).



Glottis in vivo (superior aspect).



Horizontal section through the larynx at the level of the vocal folds (superior aspect).



Sagittal section through larynx and trachea.



Coronal section through larynx and trachea.



Innervation of the larynx (posterior aspect).
Dissection of superior and inferior laryngeal nerves.
Pharynx has been opened.



Innervation of the larynx (anterior aspect).



Larynx and thoracic organs (anterior aspect). Dissection of vagus and recurrent laryngeal nerves.

1 Tongue
2 Superior cervical ganglion
3 Vagus nerve (n. X)
4 Sympathetic trunk
5 Inferior constrictor muscle of pharynx
6 Left common carotid artery
7 Inferior thyroid artery
8 Glossopharyngeal nerve (n. IX)
9 Superior laryngeal nerve
10 Internal branch of superior laryngeal nerve
11 Epiglottis
12 Posterior crico-arytenoid muscle and cricoid cartilage
13 Recurrent laryngeal nerve
14 Thyroid gland
15 Anterior scalene muscle
16 Cricothyroid muscle
17 Middle and posterior scalene muscles
18 Trachea
19 Longus capitis muscle
20 Right recurrent laryngeal nerve
21 Right subclavian artery
22 Brachiocephalic trunk
23 Hyoid bone
24 Thyrohyoid membrane
25 External branch of superior laryngeal nerve
26 Thyroid cartilage
27 Middle cervical ganglion
28 Left recurrent laryngeal nerve
29 Left subclavian artery
30 Phrenic nerve
31 Second rib
32 Superior thyroid artery
33 Thyrocervical trunk
34 Internal thoracic artery
35 Aortic arch
36 Hypoglossal nerve (n. XII)
37 Transverse cervical artery
38 Inferior cervical cardiac nerves (branches of sympathetic trunk)
39 Ligamentum arteriosum



Larynx and oral cavity (posterior aspect). Mucous membrane on the right half of pharynx has been removed.

1 Midbrain (inferior colliculus)
2 Rhomboid fossa and medulla oblongata
3 Vestibulocochlear and facial nerve
4 Glossopharyngeal, vagus, and accessory nerves
5 Occipital artery and posterior belly of digastric muscle
6 Superior cervical ganglion
7 Internal carotid artery
8 Oral cavity (tongue)
9 Ary-epiglottic fold
10 Vagus nerve
11 Piriform recess
12 Thyroid gland and common carotid artery
13 Esophagus
14 Trochlear nerve
15 Occipital condyle
16 Nasal cavity (choana)
17 Accessory nerve
18 Uvula and soft palate
19 Palatopharyngeus muscle
20 External carotid artery
21 Epiglottis
22 Internal branch of superior laryngeal nerve
23 Inferior laryngeal nerve
24 Ansa cervicalis



Pharynx and parapharyngeal nerves in connection with the brain stem (posterior aspect).

1 Inferior colliculus of midbrain
2 Facial colliculus in floor of rhomboid fossa
3 Vestibulocochlear and facial nerves
4 Glossopharyngeal nerve
5 Vagus nerve
6 Accessory nerve
7 Hypoglossal nerve
8 Pharyngobasilar fascia
9 Superior constrictor muscle of pharynx
10 Sympathetic trunk and superior cervical ganglion (medially displaced)
11 Middle constrictor muscle of pharynx
12 Greater cornu of hyoid bone
13 Inferior constrictor muscle of pharynx
14 Trochlear nerve
15 Internal acoustic meatus with facial and vestibulocochlear nerves
16 Jugular foramen with glossopharyngeal, vagus, and assessory nerves
17 Occipital condyle
18 Occipital artery
19 Posterior belly of digastric muscle
20 Accessory nerve (extracranial part)
21 Hypoglossal nerve (extracranial part)
22 External carotid artery
23 Carotid sinus nerve
24 Internal carotid artery
25 Carotid sinus and carotid body
26 Vagus nerve
27 Thyroid gland
28 Esophagus
29 Choanae
30 Medial pterygoid plate
31 Foramen lacerum
32 Pharyngeal tubercle
33 Hard palate
34 Greater and lesser palatine foramen
35 Pterygoid hamulus
36 Lateral pterygoid plate
37 Foramen ovale
38 Mandibular fossa
39 Carotid canal
40 Styloid process and stylomastoid foramen
41 Jugular foramen



Base of the skull (inferior aspect).
Red line = outline of superior constrictor muscle in continuation with buccinator and orbicularis oris muscles.



Pharynx with parapharyngeal nerves and vessels (posterior aspect).



Cross section through head and neck at the level of the atlas (inferior aspect).

1 Ascending pharyngeal artery
2 Pharyngeal plexus
3 Accessory nerve
4 Superior cervical ganglion of sympathetic trunk
5 Superior laryngeal nerve
6 Carotid body and carotid sinus nerve
7 Left vagus nerve
8 Common carotid artery and cardiac branch of vagus nerve
9 Glossopharyngeal nerve
10 Hypoglossal nerve
11 Facial nerve
12 Posterior belly of digastric muscle
13 Middle constrictor muscle of pharynx
14 Right vagus nerve
15 Sympathetic trunk
16 Internal jugular vein
17 Inferior constrictor muscle of pharynx
18 Larynx
19 Buccinator muscle
20 Soft palate and palatine glands
21 Palatine tonsil
22 Uvula of palate
23 Pharynx (oral part)
24 Parotid gland
25 Longus capitis muscle
26 Median atlanto-axial joint and anterior arch of atlas
27 Dens of axis
28 Spinal cord
29 Dura mater
30 Incisive papilla
31 Oral vestibule
32 Masseter muscle
33 Mandible
34 Mandibular canal with vessels and nerve
35 Medial pterygoid muscle
36 External carotid artery
37 Internal carotid artery
38 Atlas
39 Vertebral artery
40 Splenius capitis muscle
41 Semispinalis capitis muscle



Dissection of pharynx, supra-, and infrahyoid muscles (lateral aspect). Mandible partly removed.



Dissection of pharynx, supra-, and infrahyoid muscles (lateral aspect). Oral cavity opened.

1 Maxilla
2 Pterygomandibular raphe
3 Buccinator muscle
4 Mandible (divided)
5 Depressor anguli oris muscle
6 Mylohyoid muscle
7 Anterior belly of digastric muscle
8 Hyoid bone
9 Thyroid cartilage
10 Cricothyroid muscle
11 Styloid process
12 Medial pterygoid muscle (divided)
13 Posterior belly of digastric muscle
14 Styloglossus muscle
15 Stylohyoid muscle
16 Thyropharyngeal part of inferior constrictor muscle of pharynx
17 Thyrohyoid muscle
18 Cricopharyngeal part of inferior constrictor muscle of pharynx
19 Esophagus
20 Trachea
21 First molar of maxilla
22 Tongue
23 Inferior longitudinal muscle of tongue
24 Genioglossus muscle
25 Superior constrictor muscle of pharynx
26 Hypoglossal nerve
27 Hyoglossus muscle
28 Superior laryngeal nerve and superior laryngeal artery



Muscles of the pharynx (posterior aspect).

1	Sella turcica
2	Internal acoustic meatus and petrous part of temporal bone
3	Pharyngobasilar fascia
4	Fibrous raphe of pharynx
5	Stylopharyngeal muscle
6	Superior constrictor muscle of pharynx
7	Posterior belly of digastric muscle
8	Stylohyoid muscle
9	Middle constrictor muscle of pharynx
10	Inferior constrictor muscle of pharynx
11	Muscle-free area (Killian's triangle)
12	Esophagus
13	Trachea
14	Thyroid and parathyroid glands
15	Medial pterygoid muscle
16	Greater horn of hyoid bone
17	Internal jugular vein
18	Parotid gland
19	Accessory nerve
20	Superior cervical ganglion of sympathetic trunk
21	Vagus nerve
22	Laimer's triangle (area prone to developing diverticula)
23	Orbicularis oculi muscle
24	Nasalis muscle
25	Levator labii superioris and levator labii alaeque nasi muscles
26	Levator anguli oris muscle
27	Orbicularis oris muscle
28	Buccinator muscle
29	Depressor labii inferioris muscle
30	Hyoglossus muscle
31	Thyrohyoid muscle
32	Thyroid cartilage
33	Cricothyroid muscle
34	Pterygomandibular raphe
35	Tensor veli palatini muscle
36	Levator veli palatini muscle
37	Depressor anguli oris muscle
38	Mentalis muscle
39	Styloglossus muscle



Muscles of the pharynx (posterior aspect).



Muscles of the pharynx (lateral aspect).



Arteries of head and neck (lateral aspect). Diagram of the main branches of external carotid and subclavian arteries.

1 Frontal and parietal branches
of superficial temporal artery
2 Superficial temporal artery
3 Occipital artery
4 Maxillary artery
5 Vertebral artery
6 External carotid artery
7 Internal carotid artery
8 Common carotid artery (divided)
9 Ascending cervical artery
10 Inferior thyroid artery
11 Transverse cervical artery with two branches
(superficial cervical artery and
descending scapular artery)
12 Suprascapular artery
13 Thyrocervical trunk
14 Costocervical trunk with two branches
(deep cervical artery and supreme intercostal artery)
15 Internal thoracic artery
16 Axillary artery
17 Supra-orbital and supratrochlear arteries
18 Angular artery
19 Dorsal nasal artery
20 Transverse facial artery
21 Facial artery
22 Superior labial artery
23 Inferior labial artery
24 Submental artery
25 Lingual artery
26 Superior thyroid artery
27 Brachiocephalic trunk

▷ **To page 171:**

1 Galea aponeurotica
2 Frontal branch ⎫ of superficial
3 Parietal branch ⎭ temporal artery
4 Superior auricular muscle
5 Superficial temporal artery and vein
6 Middle temporal artery
7 Auriculotemporal nerve
8 Branches of facial nerve
9 Facial nerve
10 External carotid artery
within the retromandibular fossa
11 Posterior belly of digastric muscle
12 Sternocleidomastoid artery
13 Sympathetic trunk and superior cervical ganglion
14 Sternocleidomastoid muscle (divided and reflected)
15 Clavicle (divided)
16 Transverse cervical artery
17 Ascending cervical artery and phrenic nerve
18 Anterior scalene muscle
19 Suprascapular artery
20 Dorsal scapular artery
21 Brachial plexus and axillary artery
22 Thoraco-acromial artery
23 Lateral thoracic artery
24 Median nerve (displaced) and
pectoralis minor muscle (reflected)
25 Frontal belly of occipitofrontalis muscle
26 Orbital part of orbicularis oculi muscle
27 Angular artery and vein
28 Facial artery
29 Superior labial artery
30 Zygomaticus major muscle
31 Inferior labial artery
32 Parotid duct
33 Buccal fat pad
34 Maxillary artery
35 Masseter muscle
36 Facial artery and mandible
37 Submental artery
38 Anterior belly of digastric muscle


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53

Main branches of head and neck arteries (lateral aspect). Anterior thoracic wall and clavicle partly removed; pectoralis muscles have been reflected to display the subclavian and axillary arteries.

39	Hyoid bone
40	Internal carotid artery
41	External carotid artery
42	Superior laryngeal artery
43	Superior thyroid artery
44	Common carotid artery
45	Thyroid ansa of sympathetic trunk and inferior thyroid artery
46	Thyroid gland (right lobe)
47	Vertebral artery
48	Thyrocervical trunk
49	Vagus nerve
50	Ansa subclavia of sympathetic trunk
51	Brachiocephalic trunk
52	Superior vena cava (divided)
53	Aortic arch



Arteries of head and neck (antero-lateral aspect). Clavicle, sternocleidomastoid muscle, and veins have been partly removed. Arteries have been colored red.



Veins of head, neck, and shoulder (anterior aspect). Sternocleidomastoid muscle and anterior thoracic wall partly removed. Note the venous connection with the superior vena cava.

1	Occipital branch of occipital artery
2	Internal carotid artery
3	Cervical plexus
4	Supraclavicular nerve
5	Phrenic nerve and ascending cervical artery on anterior scalene muscle
6	Transverse cervical artery
7	Superficial cervical artery
8	Suprascapular artery and nerve
9	Brachial plexus and transverse cervical artery
10	Lateral cord of brachial plexus
11	Thoraco-acromial artery
12	Lateral thoracic artery
13	Superficial temporal artery
14	Transverse facial artery
15	Facial artery
16	External carotid artery
17	Superior thyroid artery
18	Common carotid artery, vagus nerve, and thyroid gland
19	Thyrocervical trunk
20	Subclavian artery and anterior scalene muscle
21	Occipital vein
22	Superficial temporal vein
23	Sternocleidomastoid muscle
24	Trapezius muscle
25	Internal jugular vein
26	External jugular vein
27	Subclavian vein
28	Cephalic vein
29	Axillary vein and artery
30	Supra-orbital veins
31	Angular vein
32	Superior labial vein
33	Inferior labial vein
34	Facial vein
35	Submental vein
36	Superior thyroid vein
37	Anterior jugular vein
38	Thoracic duct
39	Inferior thyroid vein
40	Superior vena cava
41	Parotid gland and facial nerve
42	Great auricular nerve
43	External jugular vein
44	Brachial plexus
45	Cephalic vein within the deltopectoral triangle
46	Right brachiocephalic vein
47	Superior vena cava
48	Right lung (reflected)
49	Superficial temporal artery and vein
50	Facial artery and vein
51	Cervical branch of facial nerve and submandibular gland
52	Internal jugular vein, common carotid artery, and omohyoid muscle
53	Anterior jugular vein and thyroid gland
54	Jugular venous arch
55	Left brachiocephalic vein
56	Pericardium of heart (location of right atrium)



Veins of head, neck, and shoulder (anterior aspect). Part of the thoracic wall, clavicle, and sternocleidomastoid muscle have been removed. Veins have been colored blue; arteries have been colored red.

The **internal jugular vein** is the continuation of the sigmoid sinus, which drains most of the venous blood from the brain together with the external cerebrospinal fluid. By joining the subclavian vein, it forms the right brachiocephalic vein, which continues on the right side directly into the superior vena cava. The common way to introduce the lead from a pacemaker device into the heart is by way of the cephalic vein. On the left side, the thoracic duct joins the internal jugular vein at the point where the subclavian vein and the internal jugular vein form the left brachiocephalic vein. Note that the subclavian vein lies in front of the anterior scalene muscle, whereas the subclavian artery and the brachial plexus lie posterior to that muscle. The **cephalic vein** joins the axillary vein by passing into the deltopectoral triangle. **The subclavian vein** is strongly fixed to the first rib, so it can be punctured with a needle at that point (underneath the sternal end of the clavicle) to introduce a catheter (subclavian line).



Lymph nodes and lymph vessels of the neck, left side (oblique-lateral aspect). The sternocleidomastoid muscle and the left half of the thoracic wall have been removed. Lower part of the internal jugular vein has been cut and laterally displaced to show the thoracic duct.

1 Superficial parotid lymph node
2 Parotid gland
3 Great auricular nerve
4 Mandible
5 Facial vein
6 Anterior belly of digastric muscle
7 Submandibular gland
8 Submental lymph nodes
9 Superior thyroid artery
10 Thyroid cartilage
11 Omohyoid muscle
12 Sternohyoid muscle

13 Common carotid artery
14 Supraclavicular lymph nodes
15 Anterior jugular vein
16 Thoracic duct and internal jugular vein
17 Jugular venous arch
18 Left brachiocephalic vein
19 Superior mediastinal lymph nodes
20 Retro-auricular lymph nodes
21 Submandibular nodes
22 Superficial cervical lymph nodes
23 Jugulodigastric lymph nodes and jugular trunk

24 Internal jugular vein
25 External jugular vein
26 Jugulo-omohyoid lymph nodes
27 Brachial plexus
28 Cephalic vein
29 Subclavian trunk
30 Infraclavicular lymph nodes
31 Subclavian vein
32 Lung
33 Internal thoracic artery and vein

112897_S_156_178_Kap_2_6:_ 06.11.2014 9:19 Uhr Seite 175



Carotid triangle, left side (lateral aspect). Sternocleidomastoid muscle reflected.

1 Mylohyoid muscle and facial artery
2 Anterior belly of digastric muscle
3 Thyrohyoid muscle
4 External carotid artery, superior thyroid artery, and vein
5 Omohyoid muscle
6 Thyroid cartilage
7 Ansa cervicalis
8 Sternohyoid muscle and superior thyroid artery
9 Stylohyoid muscle
10 Posterior belly of digastric muscle
11 Sternocleidomastoid muscle (reflected)
12 Superior cervical lymph nodes and sternocleidomastoid artery
13 Hyoid bone and hypoglossal nerve (n. XII)
14 Splenius capitis and levator scapulae muscles
15 Superior laryngeal artery and internal branch of superior laryngeal nerve
16 Accessory nerve
17 Cervical plexus
18 Internal jugular vein
19 Facial vein
20 Submandibular lymph nodes
21 Submental lymph nodes
22 Thoracic duct
23 Retro-auricular lymph nodes
24 Occipital lymph nodes
25 Parotid lymph nodes
26 Jugulodigastric lymph node
27 Deep cervical lymph nodes
28 External jugular vein
29 Jugulo-omohyoid lymph node
30 Jugular trunk
31 Subclavian trunk
32 Infraclavicular lymph nodes



Lymph nodes and veins of head and neck (oblique-lateral aspect). Dotted lines = border between irrigation areas; arrows: direction of lymph flow.



Anterior region of the neck (superficial layer). The superficial fascia has been removed.

1 Submandibular gland
2 Cervical branch of facial nerve
3 Transverse cervical nerve
4 Lateral supraclavicular nerves
5 Middle supraclavicular nerves
6 Medial supraclavicular nerves
7 Great auricular nerve

} Cutaneous branches of cervical plexus (3–7)

8 Mandible
9 Facial artery and vein
10 Anterior belly of digastric muscle
11 Mylohyoid muscle
12 Infrahyoid muscles (sternohyoid, sternothyroid, and omohyoid muscles)
13 Anterior jugular veins
14 External jugular vein
15 Pretracheal lamina of cervical fascia
16 Thyroid gland
17 Clavicle
18 Superficial lamina of cervical fascia
19 Carotid sheath with common carotid artery, internal jugular vein, and vagus nerve
20 Carotid sheath
21 Cervical part of sympathetic trunk
22 Prevertebral lamina of cervical fascia
23 Platysma muscle
24 Sternocleidomastoid muscle
25 Vertebral artery and vein
26 Scalene muscles
27 Trapezius muscle



◁ **Cross section through the neck** at the level of the thyroid gland. Notice the position of the three laminae of cervical fascia (blue colored).



Anterior region of the neck with anterior triangle (right side: superficial layer, left side: deeper layer). The pretracheal lamina of cervical fascia and left sternocleidomastoid muscle have been removed.



Supra- and infrahyoid muscles (anterior aspect).

1	Mylohyoid muscle
2	Anterior belly of digastric muscle
3	Facial artery
4	Submandibular gland
5	Great auricular nerve
6	Internal jugular vein and common carotid artery
7	Transverse cervical nerve and omohyoid muscle
8	Sternohyoid muscle and superior thyroid artery
9	Sternocleidomastoid muscle (sternal head)
10	Left sternocleidomastoid muscle (reflected)
11	Sternocleidomastoid muscle (clavicular head) and lateral supraclavicular nerves
12	Middle supraclavicular nerves
13	Medial supraclavicular nerves
14	Mandible
15	Hyoid bone
16	Superficial cervical lymph nodes
17	Left superior thyroid artery and external carotid artery
18	Thyroid cartilage
19	Superior belly of omohyoid muscle
20	Internal jugular vein and branches of ansa cervicalis
21	Thyroid gland and unpaired inferior thyroid vein
22	Posterior belly of digastric muscle
23	Stylohyoid muscle
24	Sternohyoid muscle
25	Sternothyroid muscle
26	Thyrohyoid muscle


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23

Anterior region of the neck (deep layer). Sternocleidomastoid muscles and left clavicle have been removed. Thyroid gland in relation to trachea, larynx, and vessels of the neck is shown.


17
20
24
25
26
7
10
27
28
29
30
31

Cross section through the neck at the level of the thyroid gland (MRI scan). (Courtesy of Prof. Heuck, Munich, Germany.)



Anterior region of the neck and thoracic cavity (deeper layer). Both clavicles, sternum, and ribs have been removed. Main veins have been colored blue.



Anterior region of the neck. Regional anatomy of the thyroid gland with related blood vessels.

1	Submandibular gland
2	Cervical branch of facial nerve (n. VII)
3	Cervical plexus
4	Middle supraclavicular nerves
5	Ansa cervicalis
6	Brachial plexus
7	Internal jugular vein
8	Phrenic nerve
9	Clavicle
10	Common carotid artery
11	Sternoclavicular joint with articular disc
12	Manubrium of sternum
13	Hyoid bone
14	External jugular vein
15	Thyroid cartilage
16	Cricothyroid muscle
17	Thyroid gland
18	Subclavius muscle
19	Recurrent laryngeal nerve
20	Trachea
21	Vagus nerve (n. X)
22	Subclavian vein
23	Middle pectoral nerve
24	Esophagus
25	Body of cervical vertebra
26	Spinal cord
27	Sternocleidomastoid muscle
28	Vertebral artery
29	Transverse process of cervical vertebra
30	Spinous process of cervical vertebra
31	Trapezius muscle
32	Inferior thyroid vein
33	Left brachiocephalic vein
34	Superior lobe of left lung
35	Internal thoracic artery
36	Superior vena cava
37	Superior thyroid artery
38	Inferior thyroid artery
39	Thyrocervical trunk
40	Subclavian artery
41	Aortic arch

112897_S_179_188_Kap_2_6:_ 06.11.2014 9:22 Uhr Seite 180



Lateral region of the neck with posterior and carotid triangles (superficial layer).

1 Parotid gland and great auricular nerve
2 Lesser occipital nerve
3 Internal and external jugular veins
4 Retromandibular vein and external carotid artery
5 Transverse cervical nerve with communicating branch to cervical branch of facial nerve
6 Trapezius muscle and superficial lamina of cervical fascia
7 Lateral supraclavicular nerves
8 Middle supraclavicular nerves
9 Pectoralis major muscle
10 Buccal branch of facial nerve and masseter muscle
11 Facial artery and vein and mandibular branch of facial nerve
12 Cervical branch of facial nerve and submandibular gland (only in the dissection)
13 Thyroid cartilage
14 Omohyoid muscle
15 Sternohyoid muscle
16 Sternocleidomastoid muscle
17 Medial supraclavicular nerves
18 Mandibular branch of facial nerve



Cutaneous branches of cervical plexus (lateral region). Erb's point is indicated by an arrowhead.



Lateral region of the neck with posterior and carotid triangles (superficial layer). The superficial lamina of cervical fascia has been removed to display the cutaneous branches of the cervical plexus and subcutaneous veins.

1	Lesser occipital nerve	15	Parotid gland
2	Internal jugular vein	16	Mandible
3	Splenius capitis muscle	17	Cervical branch of facial nerve
4	Great auricular nerve	18	Submandibular gland
5	Submandibular nodes	19	External carotid artery
6	Internal carotid artery and vagus nerve	20	Superior thyroid artery
7	Accessory nerve	21	Transverse cervical nerve
8	Muscular branches of cervical plexus	22	Superior root of ansa cervicalis
9	External jugular vein	23	Anterior jugular vein
10	Posterior supraclavicular nerves	24	Omohyoid muscle
11	Middle supraclavicular nerves	25	Sternohyoid muscle
12	Suprascapular artery	26	Sternocleidomastoid muscle
13	Pretracheal lamina of fascia of neck	27	Intermediate tendon of omohyoid muscle
14	Clavicle		



Lateral region of the neck (deep layer). Sternocleidomastoid muscle has been cut and reflected to display the pretracheal lamina of the cervical fascia.

1	Sternocleidomastoid muscle (reflected) and branch of accessory nerve	9	Great auricular nerve
2	Facial artery	10	Lesser occipital nerve
3	External carotid artery and superior thyroid artery	11	Splenius capitis and levator scapulae muscles
4	Internal jugular vein	12	Trapezius muscle
5	Deep cervical lymph nodes and external jugular vein	13	Middle scalene muscle and brachial plexus
6	Omohyoid muscle and pretracheal lamina of cervical fascia	14	Posterior supraclavicular nerves
7	Anterior jugular vein	15	Middle supraclavicular nerve
8	Pectoralis major muscle	16	Clavicle and anterior supraclavicular nerves
		17	Sternocleidomastoid muscle (reflected)



Lateral region of the neck (deep layer). The internal jugular vein has been reflected to expose the carotid artery and vagus nerve.

1 Stylohyoid muscle
2 Facial artery and mylohyoid muscle
3 Anterior belly of digastric muscle
4 Internal jugular vein, hypoglossal nerve, and superficial cervical lymph nodes
5 Superior thyroid artery and vein and inferior pharyngeal constrictor muscle
6 Thyroid cartilage and vagus nerve
7 Ansa cervicalis, omohyoid muscle, and common carotid artery
8 Right superior thyroid artery
9 Anterior scalene muscle
10 Sternothyroid muscle and inferior thyroid artery
11 Muscular branches of ansa cervicalis to the infrahyoid muscles
12 Inferior thyroid vein
13 Posterior belly of digastric muscle
14 Sternocleidomastoid muscle and lesser occipital nerve
15 Accessory nerve
16 Splenius capitis muscle
17 Cervical plexus
18 Posterior scalene muscle
19 Levator scapulae muscle
20 Posterior supraclavicular nerves
21 Phrenic nerve
22 Middle supraclavicular nerve
23 Brachial plexus
24 Anterior supraclavicular nerves
25 Sternocleidomastoid muscle



Lateral region of the neck with ansa cervicalis (deeper layer). The cervical fascia and the clavicle are partly removed. Ansa cervicalis and infrahyoid muscles are displayed.

1 Masseter muscle
2 Mylohyoid muscle and facial artery
3 External carotid artery and anterior belly of digastric muscle
4 Hypoglossal nerve
5 Thyrohyoid muscle
6 Superior thyroid artery and vein and inferior pharyngeal constrictor muscle
7 Superior belly of omohyoid muscle
8 Ansa cervicalis, thyroid gland, and internal jugular vein
9 Sternothyroid muscle
10 Sternohyoid muscle
11 Thoracic duct
12 Pectoralis minor muscle
13 Pectoralis major muscle
14 Posterior belly of digastric muscle
15 Sternocleidomastoid muscle and lesser occipital nerve
16 Splenius capitis muscle
17 Superficial cervical lymph nodes and accessory nerve
18 Cervical plexus
19 Middle scalene muscle
20 Levator scapulae muscle
21 Posterior scalene muscle
22 Brachial plexus
23 Transverse cervical artery and clavicle
24 Subclavius muscle
25 Subclavian artery and vein
26 Thoraco-acromial artery
27 Cephalic vein



Lateral region of the neck and submandibular region with hypoglossal nerve (n. XII). Mandible slightly elevated. Arrow: superior cervical ganglion.

1 Facial artery and mandible
2 Submental artery
3 Mylohyoid muscle and nerve
4 Hypoglossal nerve (lingual branches)
5 Thyrohyoid branch of hypoglossal nerve (n. XII)
6 Anterior belly of digastric muscle
7 Hyoid bone
8 Omohyoid branch of hypoglossal nerve (n. XII)
9 Omohyoid muscle and superior thyroid artery
10 Ansa cervicalis
11 Posterior belly of digastric muscle
12 Hypoglossal nerve (n. XII)
13 Vagus nerve (n. X)
14 Internal carotid artery
15 Superior root of ansa cervicalis
16 External carotid artery
17 Cervical plexus
18 Common carotid artery
19 Facial artery and vein
20 Omohyoid muscle
21 Internal jugular vein
22 Sternohyoid and sternothyroid muscles
23 Clavicle
24 Superficial temporal artery and vein
25 Occipital artery
26 Spinal nerves (C_3 and C_4)
27 Spinal processes of cervical vertebrae (C_4 and C_5)
28 Scapula



Nerves and vessels of the neck (lateral aspect). The ansa cervicalis with its connection to the spinal nerves is depicted.



Lateral region of the neck (deeper layer). Clavicle partly removed to show the slit between the scalene muscles. Internal jugular vein removed.

1 Masseter muscle
2 Mylohyoid muscle and facial artery
3 Anterior belly of digastric muscle
4 Hypoglossal nerve
5 Sternohyoid muscle
6 Omohyoid muscle, superior thyroid artery and vein
7 Sternothyroid muscle, thyroid cartilage, and pyramidal lobe of thyroid gland
8 Common carotid artery and sympathetic trunk
9 Ansa cervicalis
10 Phrenic nerve, ascending cervical artery, and anterior scalene muscle
11 Inferior thyroid artery, vagus nerve, and internal jugular vein (cut)
12 Thyroid gland and unpaired inferior thyroid venous plexus
13 Thoracic duct and left subclavian trunk
14 Subclavius muscle (reflected)
15 Sternocleidomastoid muscle (reflected)
16 Posterior belly of digastric muscle
17 Superior cervical ganglion and splenius muscle
18 Lesser occipital nerve
19 Internal carotid artery and branch of the glossopharyngeal nerve to the carotid body
20 External carotid artery
21 Cervical plexus and accessory nerve
22 Inferior root of ansa cervicalis
23 Supraclavicular nerve
24 Levator scapulae muscle
25 Middle scalene muscle and clavicle
26 Transverse cervical artery, brachial plexus, and posterior scalene muscle
27 Subclavian artery and vein
28 Thoraco-acromial artery and pectoralis minor muscle
29 Pectoralis major muscle



Lateral region of the neck (deepest layer). Thyroid gland reflected to expose the esophagus and the recurrent laryngeal nerve.

1	Superior cervical ganglion of sympathetic trunk and posterior belly of digastric muscle
1a	Anterior belly of digastric muscle
2	Facial artery and common carotid artery (reflected anteriorly)
3	Ascending cervical artery and longus colli muscle
4	Omohyoid muscle and superior thyroid artery
5	Sympathetic trunk and sternohyoid muscle
6	Middle cervical ganglion and inferior pharyngeal constrictor muscle
7	Anterior scalene muscle and phrenic nerve
8	Thyroid gland and inferior thyroid artery
9	Vagus nerve and esophagus
10	Stellate ganglion
11	Recurrent laryngeal nerve and trachea
12	Common carotid artery and cervical cardiac branch of vagus nerve
13	Sternocleidomastoid muscle and accessory nerve
14	Splenius capitis muscle
15	Lesser occipital nerve, longus capitis muscle, and cervical plexus
16	Phrenic nerve, posterior scalene muscle, and levator scapulae muscle
17	Supraclavicular nerves and middle scalene muscle
18	Brachial plexus and pectoralis major muscle (clavicular head)
19	Transverse cervical artery and clavicle
20	Subclavian artery
21	Thoraco-acromial artery and pectoralis minor muscle
22	First rib, accessory phrenic nerve, and subclavian vein
23	Internal jugular vein, thoracic duct, and subclavius muscle



Lateral region of the neck and shoulder (deepest layer). Cervical and brachial plexuses and their relation to the blood vessels are shown. Note the location and content of scalene triangle. Sternocleidomastoid muscle and clavicle have been removed; the internal jugular vein was divided to display the roots of cervical and brachial plexuses.

1 Lesser occipital nerve
2 Great auricular nerve
3 Cutaneous branches of cervical plexus
4 Supraclavicular nerve
5 Suprascapular nerve and artery
6 Brachial plexus
7 Median nerve (with two roots) and musculocutaneous nerve
8 Axillary artery
9 Axillary vein
10 Medial brachial cutaneous nerve
11 Ulnar nerve
12 Thoracodorsal nerve
13 Parotid gland and facial nerve (cervical branch)
14 Cervical plexus
15 Submandibular gland
16 Superior thyroid artery
17 Common carotid artery dividing in internal and external carotid artery and superior root of ansa cervicalis
18 Omohyoid muscle and cervical branch of facial nerve joining the transverse cervical nerve (C_2, C_3)
19 Sternohyoid muscle
20 Transverse cervical nerve and sternothyroid muscle
21 Common carotid artery and vagus nerve
22 Phrenic nerve and anterior scalene muscle
23 Internal jugular vein
24 Intercostobrachial nerves
25 Long thoracic nerve

3 Trunk

Skeleton 190
Head and Vertebral Column 193
Vertebrae 198
Thorax and Vertebral Column 201
Ligaments of the Vertebral Column 206
Surface Anatomy of the Anterior Body 208
Thoracic Wall 210
Thoracic and Abdominal Walls 212
Inguinal Region 221
Surface Anatomy of the Back 225
Back 226
Spinal Cord 234
Lumbar Part of the Vertebral Column and Spinal Cord 238
Vertebral Canal and Spinal Cord 240
Nuchal Region 242



1	Frontal bone
2	Maxilla
3	Mandible
4	Cervical vertebrae
5	Clavicle
6	Scapula
7	Humerus
8	Sternum
9	Ribs
10	Costal cartilage
11	Lumbar vertebrae
12	Lumbar vertebra (L_5) and promontory
13	Sacrum
14	Hip bone
15	Radius and ulna
16	Coccyx
17	Head of femur
18	Pubic symphysis
19	Carpal bones
20	Metacarpal bones
21	Femur
22	Phalanges

Skeleton of the trunk with head, vertebral column, thorax, pelvis, and upper limb (anterior aspect).



Skeleton of the trunk with head, vertebral column, thorax, pelvis, and shoulder girdle (oblique-posterior aspect).

1	Occipital bone
2	Atlas
3	Axis
4	Cervical vertebrae
5	Vertebra prominens (C_7)
6	Scapula
7	Thoracic vertebrae
8	Lumbar vertebrae
9	Hip bone
10	Sacrum

112897_S_189_214_Kap_3:_ 06.11.2014 9:24 Uhr Seite 192



Skeleton of the trunk with head, vertebral column, thorax, pelvis, and shoulder girdle (posterior aspect).

1 Occipital bone
2 Atlas
3 Axis
4 Cervical vertebrae
5 Vertebra prominens (C_7)
6 Thoracic vertebrae
7 Scapula
8 Ribs
9 Lumbar vertebrae
10 Hip bone
11 Sacrum
12 Coccyx



Cervical vertebral column in relation to the head (midsagittal section, medial aspect).



Atlas and axis in relation to the head (lateral aspect).

1 External occipital protuberance
2 Foramen magnum
3 Atlanto-occipital joint
4 Transverse process of atlas
5 Median atlanto-axial joint
6 Vertebral canal
7 Spinous process of third cervical vertebra
8 Occipital condyle
9 Lateral atlanto-axial joint
10 Occipital bone
11 Atlas
12 Axis
13 Dens of axis
14 Hypoglossal canal
15 Spinous process of axis



Occipital bone, atlas, and axis (anterior aspect).



Occipital bone, atlas, and axis (left lateral aspect).



Atlas and axis (from above).



Median atlanto-axial joint and transverse ligament of atlas (from above). Dens of axis partly severed.

1 Superior articular facet of atlas
2 Spinous process
3 Anterior arch of atlas with anterior tubercle
4 Dens of axis
5 Transverse foramen and process
6 Posterior tubercle of atlas
7 Posterior arch of atlas and vertebral artery
8 Dura mater
9 Spinous process of axis
10 Median atlanto-axial joint (anterior part)
11 Articular capsule of atlanto-occipital joint
12 Transverse ligament of atlas
13 Superior articular facet of axis
14 Inferior articular process
15 Body of axis
16 Pedicle and lamina of axis
17 Superior longitudinal band of cruciform ligament
18 Alar ligaments
19 Transverse ligament of atlas
20 Inferior longitudinal band of cruciform ligament
21 Occipital bone
22 Atlanto-occipital joint
23 Lateral atlanto-axial joint
24 Third cervical vertebra (C_3)



Atlas and axis (left oblique postero-lateral aspect, demonstrating the articulation of the dens of axis with the atlas [arrows]).



Atlanto-occipital and atlanto-axial joints (posterior aspect). Posterior part of occipital bone, posterior arch of atlas, and axis have been removed to show the cruciform ligament.



Cervical vertebral column and skull (posterior aspect). Note the location of the atlanto-occipital and atlanto-axial joints.

1 Superior articular facet
2 Posterior tubercle of atlas
3 Pedicle and lamina of axis
4 Spinous process of cervical vertebra
5 Occipital bone
6 Dens of axis
7 Atlanto-occipital joint
8 Lateral atlanto-axial joint
9 Spinous process of axis
10 External occipital protuberance
11 Foramen magnum
12 Transverse process of atlas
13 Posterior longitudinal ligament
14 Occipital condyle
15 Tectorial membrane
16 Dorsum sellae
17 Clivus
18 Axis
19 Sella turcica
20 Superior orbital fissure
21 Internal acoustic meatus
22 Jugular foramen
23 Hypoglossal canal
24 Superior longitudinal band of cruciform ligament
25 Alar ligaments
26 Transverse ligament of atlas



Cervical vertebral column and skull with ligaments (posterior aspect). Posterior arches of atlas and axis have been removed to show the tectorial membrane.



Atlanto-occipital and atlanto-axial joints with ligaments (posterior aspect). Posterior part of occipital bone and posterior arch of atlas have been removed to show the cruciform ligament.



1 Atlas
2 Dens of axis
3 Axis
4 Body of cervical vertebra (C_3)
5 Intervertebral discs
6 Sternocleidomastoid muscle
7 Scalene muscles

Coronal section through the cervical vertebral column at the level of the vertical bodies (MRI scan). (Courtesy of Prof. Heuck, Munich, Germany.)



1 Cerebellum
2 Occipital condyle
3 Atlanto-occipital joint
4 Atlas
5 Lateral atlanto-axial joint
6 Intervertebral disc
7 Cistern of pons
8 Head of mandible
9 Dens of axis
10 Axis
11 Body of cervical vertebra (C_3)

Coronal section through the cervical vertebral column at the level of the dens of axis (MRI scan). (Courtesy of Prof. Heuck, Munich, Germany.)

1 Pons
2 Base of skull (clivus)
3 Medulla oblongata
4 Atlas (anterior arch)
5 Dens of axis
6 Intervertebral disc
7 Body of cervical vertebra (C_4)
8 Site of larynx
9 Trachea
10 Cerebellum
11 Cerebellomedullary cistern
12 Spinal cord
13 Trapezius muscle
14 Muscles of the neck
15 Spinous process of cervical vertebra (C_7)
16 Internal jugular vein
17 Common carotid artery
18 Vagus nerve (n. X)
19 Larynx
20 Body of cervical vertebra
21 Vertebral artery
22 Spinal nerve with spinal ganglion
23 Transverse process of cervical vertebra
24 Spinous process of cervical vertebra



Midsagittal section through the cervical vertebral column showing the spinal cord in connection with the medulla oblongata (MRI scan). (Courtesy of Prof. Heuck, Munich, Germany.) ◁





Horizontal section through the neck at the level of the larynx (MRI scan). (Courtesy of Prof. Heuck, Munich, Germany.) Compare with the schematic drawing. ◁


1
2
2
3
1
4
2
2
3
5
6
7
8
C1
9
10
11
12
C2
13
14
15
C
16
17
Th
18
19
20
16
L
2
21
19
16
22
S
23
24
25
26

Representative vertebrae from each region of the vertebral column (superior aspect). From top to bottom: atlas (C_1), axis (C_2), cervical vertebra (C), thoracic vertebra (Th), lumbar vertebra (L), and sacrum (S).


3
29
2
19
16
18
37
17
20

General organization of ribs and vertebrae.


9
8
16
7
6
10
11
12

Atlas and axis.


4
16
19
20
16
3
27
28
3
29
30
27

Typical cervical and thoracic vertebrae.


19
21
16
38
19
26
24
33
31
3
30
5
22
32

Typical lumbar vertebra and sacrum.

△

Representative vertebrae from each region of the vertebral column (lateral aspect, ventral surface on the right).



General characteristics of the vertebrae. Typical cervical, thoracic, and lumbar vertebrae and sacrum.



General characteristics of lumbar vertebrae and sacrum (posterior aspect).

Green = Ribs or homologous processes
Red = Muscular processes (transverse and spinous processes)
Orange = Laminae and articular processes
Yellow and blue = Articular facets

1 Foramen transversarium
2 Vertebral foramen
3 Body of vertebra
4 Superior articular facet
5 Base of sacrum
6 Anterior tubercle of atlas
7 Superior articular facet of atlas
8 Transverse process
9 Posterior tubercle of atlas
10 Dens of axis
11 Superior articular surface
12 Transverse process
13 Arch of vertebra
14 Anterior tubercle of transverse process
15 Posterior tubercle of transverse process
16 Spinous process
17 Shaft of rib
18 Body of vertebra and head of rib articulating with each other (costovertebral joint)
19 Superior articular process
20 Transverse process and tubercle of rib articulating with each other (costotransverse joint)
21 Costal process
22 Auricular surface
23 Lateral part of sacrum
24 Lateral sacral crest
25 Intermediate sacral crest
26 Median sacral crest
27 Inferior articular facet
28 Superior demifacet for head of rib
29 Inferior demifacet for head of rib
30 Inferior vertebral notch
31 Superior vertebral notch
32 Apex of the sacrum
33 Sacral cornu
34 Coccyx
35 Dorsal sacral foramina
36 Mamillary process
37 Pedicle
38 Inferior articular process



Cervical vertebrae (lateral aspect, blue = articular facets).



Thoracic vertebrae (lateral aspect, blue = articular facets).



Lumbar vertebrae with sacrum and coccyx (posterior aspect, blue = articular facets).



Paramedian section through the vertebral column with pelvic cavity (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)

1	Body of vertebra
2	Superior articular facet
3	Vertebral arch
4	Transverse process of vertebra
5	Zygapophysial joint
6	Spinous process
7	Superior articular facet of articulation with head of ribs
8	Transverse process with articular facet of costotransverse joint
9	Costal process of lumbar vertebra
10	Sacrum
11	Median sacral crest
12	Dorsal sacral foramina
13	Coccyx
14	Anterior longitudinal ligament
15	Intervertebral disc
16	Vertebral canal



Skeleton of the thorax (anterior aspect).



Skeleton of the thorax (posterior aspect).

1 Atlas
2 Axis
3 Cervical vertebrae
4 First thoracic vertebra
5 First rib
6 Facet for clavicle and clavicular notch
7 Manubrium sterni
8 Sternal angle
9 Body of sternum
10 Xiphoid process
11 Twelfth thoracic vertebra and rib
12 Jugular notch
13 Second rib
14 Costal cartilages
15 Infrasternal angle
16 Costal arch
17 Costotransverse joints between the transverse processes of thoracic vertebrae and the tubercles of the ribs
18 Spinous processes
19 Costal angle
20 Costal processes of lumbar vertebrae



Disarticulated skeleton of the thorax. The twelve ribs (I–XII) are arranged in a craniocaudal direction.



Skeleton of the thorax (right lateral aspect).

1 Atlas
2 Axis
3 Cervical vertebrae
4 Vertebra prominens (C_7)
5 First rib
6 Facet for clavicle
7 Manubrium sterni
8 Sternal angle
9 Body of sternum
10 Costal arch
11 Tenth rib
12 Eleventh rib
13 Twelfth rib
14 Spinous processes of cervical vertebrae
15 Spinous processes of thoracic vertebrae
16 Spinous processes of lumbar vertebrae
17 Costal angle
18 Intervertebral foramina
19 Intervertebral discs
20 Cervical curvature
21 Thoracic curvature
22 Lumbar curvature
23 Sacrum
24 Coccyx



Vertebral column (right lateral aspect).



Vertebral column and thorax in connection with head and pelvis (lateral aspect).

1	Frontal bone
2	Maxilla
3	Mandible
4	Bodies of cervical vertebrae
5	First rib
6	Manubrium of sternum
7	Sternum (corpus sterni)
8	Seventh rib (last of the true ribs)
9	Costal arch
10	Floating ribs (costae fluctuantes)
11	Body of fourth lumbar vertebra
12	Pelvis
13	Occipital bone
14	Atlanto-occipital joint
15	Atlas
16	Axis
17	Spinous processes of cervical vertebrae (C_4, C_5)
18	Costotransverse joint of first rib
19	Head of second rib
20	Third rib
21	Spinous processes of lumbar vertebrae (L_2, L_3)
22	Sacrum



1	Axillary vein
2	Intercostobrachial nerves
3	Subscapularis muscle and thoracodorsal nerve
4	Long thoracic nerve, lateral thoracic artery and vein
5	Latissimus dorsi muscle
6	External intercostal muscles
7	Serratus anterior muscle
8	Lateral cutaneous branches of intercostal nerves
9	External abdominal oblique muscle
10	Clavicle (divided)
11	Second rib (costochondral junction)
12	Internal intercostal muscles
13	External intercostal membrane
14	Position of xiphoid process
15	Costal arch or margin
16	Anterior layer of rectus sheath

Muscles of the thorax, superficial layer (lateral aspect). Upper limb elevated. Pectoralis major and minor muscles have been removed.



Effect of intercostal muscles on the costovertebral and costotransverse joints. Axes of movement indicated by red lines; direction of movements indicated by red arrows.
A = Action of internal intercostal muscles (expiration);
B = Action of external intercostal muscles (inspiration).



Two thoracic vertebrae (left lateral aspect).



Ligaments of thoracic vertebrae and costovertebral joints (left antero-lateral aspect).

1 Superior demifacet for head of rib
2 Body of vertebra
3 Inferior demifacet for head of rib
4 Intervertebral disc
5 Inferior vertebral notch
6 Superior articular facet and superior articular process
7 Pedicle
8 Transverse process and facet for tubercle of rib
9 Inferior articular process
10 Intervertebral foramen
11 Spinous process
12 Anterior longitudinal ligament
13 Intra-articular ligament
14 Radiate ligament
15 Superior costotransverse ligament
16 Body of rib
17 Intertransverse ligament
18 Articulation of head of rib with two vertebrae
19 Angle of costotransverse joint (articular facet)
20 Costotransverse joint
21 Tubercle of rib
22 Costal angle of rib
23 Vertebral canal
24 Inferior facet of articulation with head of rib
25 Head of rib
26 Superior articular process
27 Facets of articulation with costotransverse joint



Costovertebral joints (lateral aspect).



Costovertebral joints (lateral aspect). Two thoracic vertebrae with an articulating rib (separated). Axis of movement indicated by dashed line. Blue = articular facets.



Median sagittal section through the bodies of lumbar vertebrae, showing the intervertebral discs, each of which consists of an outer laminated portion and an inner core.



Ligaments of the thoracic vertebrae (posterior aspect).

1 Posterior longitudinal ligament and spinal dura mater
2 Body of vertebra
3 Intervertebral disc
  a Inner core (nucleus pulposus)
  b Outer portion (anulus fibrosus)
4 Anterior longitudinal ligament
5 Ligamentum flavum
6 Intertransverse ligament
7 Supraspinous ligament
8 Superior costotransverse ligament
9 Rib
10 Spinous process
11 Costal process of lumbar vertebra
12 Sacrum
13 Intervertebral foramen
14 Interspinous ligament
15 Transverse process of thoracic vertebra



Two caudal lumbar vertebrae and sacrum with their intervertebral discs (anterior aspect). Anterior longitudinal ligament removed.



Ligaments of the thoracic vertebrae (left lateral aspect).



Ligaments of the thoracic vertebrae (oblique-lateral aspect, blue = articular facets).



Ligaments of the lumbar vertebrae (median sagittal section, blue = articular facets).



Vertebral column and ribs (posterior aspect). Muscles of the back has been widely removed to display the ligaments.

1 Anterior longitudinal ligament
2 Body of vertebra
3 Intervertebral disc
4 Intra-articular ligament
5 Radiate ligament
6 Posterior longitudinal ligament
7 Superior articular facet
8 Articular facets of joint of head of rib and costotransverse joint
9 Superior costotransverse ligament
10 Joint of head of rib
11 Rib
12 Interspinal ligament
13 Costotransverse joint
14 Lateral costotransverse ligament
15 Spinous process
16 Supraspinal ligament
17 Nucleus pulposus
18 Costal process
19 Vertebral arch
20 Intervertebral foramen
21 Intertransverse ligament
22 Semispinalis cervicis muscle
23 Levatores costarum muscles
24 Bodies of lumbar vertebrae
25 Spinous processes of lumbar vertebrae and supraspinal ligaments
26 Intertransversarii muscles

Surface Anatomy of the Anterior Body in the Female



Surface anatomy of the anterior body wall in the female.
Note the differences of hairiness between the regions.

1 Clavicle
2 Pectoralis major muscle
3 Areola and nipple
4 Infrasternal angle
5 Costal arch
6 Rectus abdominis muscle
7 Anterior superior iliac spine
8 Inguinal ligament
9 Mons pubis
10 External abdominal oblique muscle
11 Spermatic cord
12 Deltoid muscle
13 External intercostal muscle
14 Internal abdominal oblique muscle
15 Transverse abdominal muscle
16 Rectus sheath
17 Pectoralis minor muscle
18 Anterior serratus muscle
19 Linea alba



Regions and regional lines of the anterior body wall in the female.

1 Anterior cervical region
2 Sternocleidomastoid region
3 Omoclavicular triangle
4 Lateral cervical region
5 Infraclavicular fossa
6 Axillary region
7 Clavipectoral triangle
8 Deltoid region
9 Presternal region
10 Inframammary region
11 Mammary region
12 Pectoral region
13 Epigastric region
14 Hypochondriac region
15 Umbilical region
16 Lateral abdominal region
17 Inguinal region
18 Pubic region
19 Urogenital region
20 Femoral triangle
21 Anterior median line
22 Sternal line
23 Parasternal line
24 Mammillary line (medioclavicular line)
25 Axillary line
26 Horizontal plane at the level of the inferior thoracic aperture
27 Horizontal plane at the level of the anterior superior iliac spine


1
2
4
3
6
10
8
11

Surface anatomy of the anterior body wall in the male. Localization and structure of the muscles can be identified.


12
2
13
6
10
14
15
16
11
17
18
19
10
14
7
8

Muscles of the anterior body wall.


F
A
C_3
G
B
C_4
H
Th_2
C
I
Th_5
Th_1
C_5
Th_7
K
L
D
M
Th_{10}
C_6
E
N
Th_{12}
L_1
O
L_2

Head's zones

A = Duodenum
B = Gallbladder, liver (C_3–C_4)
C = Esophagus (Th_4, Th_5)
D = Liver, gallbladder (Th_6–Th_{11})
E = Colon, vermiform appendix (Th_{11}–T_{12}, L_1)
F = Heart
G = Pancreas
H = Stomach (C_3, C_4)
I = Heart (Th_3, Th_4)
K = Pancreas (Th_8)
L = Stomach (Th_6–Th_9)
M = Small intestine (Th_{10}–L_1)
N = Kidney, ureter, testis (Th_{10}–L_1)
O = Urinary bladder (Th_{11}–L_1)

◁ **Segments of the anterior body wall.** Head's zones are indicated.



Anterior thoracic wall (posterior aspect). Diaphragm partly removed, posterior layer of rectus sheath fenestrated on both sides.

1 Sternocleidomastoid muscle (divided)
2 Clavicle
3 Sternothyroid muscle
4 Internal intercostal muscle
5 Transversus thoracis muscle
6 Intercostal arteries and nerves
7 Musculophrenic artery
8 Superior epigastric artery and vein
9 Diaphragm (divided)
10 Rectus abdominis muscle

11 Subclavian artery and brachial plexus
12 First rib
13 Internal thoracic artery and vein
14 Sternum
15 Innermost intercostal muscle
16 Intercostal artery and vein
17 Xiphoid process
18 Linea alba and
posterior layer of rectus sheath
19 Transverse abdominal muscle



Thoracic wall (anterior aspect). Left pectoralis major muscle has been divided and reflected. Note the connection of the cephalic vein with the subclavian vein.
Arrow: medial pectoral nerve.



Thoracic wall (lateral aspect). Pectoralis major and minor muscles have been removed. A section of the fourth rib has been cut and removed to display the intercostal vessels and nerve.

1	Mandible
2	Facial artery
3	Submandibular gland
4	Hyoid bone
5	Thyroid cartilage and sternohyoid muscle
6	Clavicle
7	Subclavius muscle
8	Second rib
9	Anterior cutaneous branches of intercostal nerves
10	External intercostal membrane
11	Parotid gland
12	External carotid artery
13	Sternocleidomastoid muscle and cutaneous branches of cervical plexus
14	Supraclavicular nerves
15	Pectoralis major muscle and lateral pectoral nerves
16	Thoraco-acromial artery and subclavian vein
17	Pectoralis minor muscle
18	Median and ulnar nerve
19	Thoraco-epigastric vein
20	Cephalic vein and long head of biceps brachii muscle
21	Lateral thoracic artery and long thoracic nerve
22	Lateral cutaneous branches of intercostal nerve
23	Latissimus dorsi muscle
24	Median nerve
25	Axillary artery
26	Intercostobrachial nerves
27	Thoracodorsal nerve
28	Long thoracic nerve
29	Latissimus dorsi muscle
30	Serratus anterior muscle
31	Thoraco-acromial artery
32	Clavicle
33	External intercostal muscle
34	Third rib
35	Internal intercostal muscle
36	Anterior intercostal artery and vein, and intercostal nerve
37	Costal arch or margin

112897_S_189_214_Kap_3:_ 06.11.2014 9:24 Uhr Seite 212



Thoracic and abdominal walls (anterior aspect). Dissection of the internal thoracic artery and vein. Left pectoralis major muscle partly removed. Anterior lamina of the rectus sheath on the left side has been removed.

1 Anterior perforating branches of intercostal nerve
2 Mammary gland
3 External abdominal oblique muscle
4 Rectus sheath (anterior layer)
5 Sternocleidomastoid muscle
6 Clavicle
7 Lateral thoracic artery and vein
8 Pectoralis major muscle
9 Internal thoracic artery and vein
10 Serratus anterior muscle
11 Superior epigastric artery and vein
12 Costal margin
13 Rectus abdominis muscle
14 Cut edge of the anterior layer of the rectus sheath
15 Subclavian artery
16 Highest intercostal artery
17 Internal thoracic artery
18 Musculophrenic artery
19 Superficial epigastric artery
20 Deep circumflex iliac artery
21 Superior epigastric artery
22 Inferior epigastric artery
23 Superficial circumflex iliac artery



Main arteries of thoracic and abdominal walls (anterior aspect).



Thoracic and abdominal walls with superficial muscles (anterior aspect). The fascia of pectoralis major muscle and the abdominal wall have been removed; the anterior layer of the sheath of the rectus abdominis muscle is displayed.

1 Sternohyoid muscle
2 Sternocleidomastoid muscle
3 Supraclavicular nerves (branches of cervical plexus)
4 Deltoid muscle
5 Pectoralis major muscle
6 Anterior cutaneous branches of intercostal nerves
7 External abdominal oblique muscle
8 Lateral cutaneous branches of intercostal nerves
9 Umbilicus and umbilical ring
10 Clavicle
11 Cephalic vein
12 Serratus anterior muscle
13 Linea alba
14 Sheath of rectus abdominis muscle (anterior layer)
15 Inguinal ligament



1 Deltoid muscle
2 Cephalic vein
3 Pectoralis major muscle (divided)
4 Internal intercostal muscle
5 Intercostal artery and vein
(intercostal space, fenestrated)
6 Serratus anterior muscle
7 External abdominal oblique muscle
8 Anterior layer of rectus sheath
9 Iliac crest
10 Superficial epigastric vein
11 Superficial circumflex iliac vein
12 Saphenous opening
13 Superficial inguinal lymph nodes
14 Superficial external pudendal veins
15 Great saphenous vein
16 Nipple
17 Costal margin
18 Subcutaneous fatty tissue
19 Umbilicus
20 Anterior layer of rectus sheath
21 Rectus abdominis muscle
22 Posterior layer of rectus sheath
23 Internal abdominal oblique muscle
24 External abdominal oblique muscle (cut)
25 Transverse abdominal muscle
26 Transversalis fascia and peritoneum
27 Psoas major muscle
28 Body of lumbar vertebra (L_4)
29 Quadratus lumborum muscle
30 Medial tract of erector spinae muscle
31 Lateral tract of erector spinae muscle
(longissimus and iliocostalis muscles)
32 Small intestine
33 Left ureter
34 Abdominal aorta
35 Inferior vena cava
36 Descending colon
37 Spinous process

Thoracic and abdominal walls (anterior aspect). Right pectoralis major and minor muscles are divided. Muscles of thoracic and abdominal walls on the right side are displayed.



Horizontal section through the trunk at the level of the umbilicus, superior to arcuate line (inferior aspect).



1 Deltoid muscle
2 Pectoralis major muscle (divided)
3 Internal intercostal muscle
4 Intercostal artery and vein
5 Rectus abdominis muscle
6 Tendinous intersections
7 External abdominal oblique muscle
8 Anterior superior iliac spine
9 Superficial circumflex iliac vein
10 Superficial epigastric vein
11 Great saphenous vein
12 Cephalic vein
13 Pectoralis major muscle
14 Anterior cutaneous branches of intercostal nerves
15 Nipple
16 Linea alba
17 Anterior layer of rectus sheath
18 Umbilicus
19 Inguinal ligament
20 Pyramidal muscle
21 Superficial inguinal ring and spermatic cord
22 Fundiform ligament of penis
23 Common iliac arteries
24 Small intestine
25 Inferior vena cava
26 Body of lumbar vertebra (L_4)
27 Psoas major muscle
28 Spinous process
29 Internal abdominal oblique muscle
30 Transverse abdominal muscle
31 Descending colon
32 Ilium
33 Multifidus muscle
34 Longissimus and iliocostalis muscles

Thoracic and abdominal walls (anterior aspect). Right pectoralis major and minor muscles and anterior layer of rectus sheath have been removed on the right side.



Horizontal section through the trunk at the level of fourth lumbar vertebra (inferior aspect, CT scan).



1 Costal margin
2 Rectus abdominis muscle
3 External abdominal oblique muscle (reflected)
4 Thoraco-abdominal (intercostal) nerves with accompanying vessels
5 Internal abdominal oblique muscle
6 Arcuate line (arrow)
7 Inferior epigastric artery and vein
8 Ilio-inguinal nerve
9 Position of deep inguinal ring
10 Superficial inguinal lymph nodes
11 Great saphenous vein
12 Linea alba
13 Iliohypogastric nerve
14 Pyramidal muscle
15 Spermatic cord
16 Fundiform ligament of penis

Thoracic and abdominal walls (anterior aspect). External abdominal oblique muscle has been divided and reflected on both sides. The right rectus muscle has been reflected medially to display the posterior layer of rectus sheath. Arrow: location of arcuate line.



1 Anterior layer of rectus sheath
2 Rectus abdominis muscle
3 Posterior layer of rectus sheath
4 Transversalis fascia
5 Transverse abdominal muscle
6 Internal abdominal oblique muscle
7 External abdominal oblique muscle
8 Thoracolumbar fascia with superficial and deep layer
9 Lateral column of erector spinae muscle
10 Medial column of erector spinae muscle

Horizontal section through the trunk, superior to arcuate line (inferior aspect).



1 Rectus abdominis muscle (reflected)
2 External abdominal oblique muscle (divided)
3 Posterior layer of rectus sheath
4 Umbilical ring
5 Internal abdominal oblique muscle
6 Arcuate line (arrow)
7 Inguinal ligament
8 Inferior epigastric artery and vein and rectus abdominis muscle (divided and reflected)
9 Costal margin
10 Linea alba
11 Tendinous intersection
12 Iliohypogastric nerve
13 Ilio-inguinal nerve
14 Pyramidal muscle
15 Spermatic cord

Thoracic and abdominal walls (anterior aspect). External abdominal oblique muscle has been divided and reflected on both sides. The right rectus muscle has been cut and reflected to display the posterior layer of rectus sheath. Arrow: location of arcuate line.



1 Linea alba
2 Rectus abdominis muscle
3 Epidermis
4 Fascia of external abdominal oblique muscle (green)
5 External abdominal oblique muscle
6 Internal abdominal oblique muscle
7 Transverse abdominal muscle
8 Transversalis fascia (green)
9 Peritoneum

Transverse sections through the abdominal wall
a) superior and
b) inferior
to arcuate line.

112897_S_215_250_Kap_3:_ 06.11.2014 9:34 Uhr Seite 218



Thoracic and abdominal walls with vessels and nerves (anterior aspect). Right side: superficial layers; left side: deeper layers. Pectoralis major and minor muscles and the external and internal intercostal muscles on the left side have been removed to display the intercostal nerves. The anterior layer of rectus sheath, the left rectus abdominis muscle, and the external and internal abdominal oblique muscles have been removed to show the thoraco-abdominal nerves within the abdominal wall.



Thoracic and abdominal walls with vessels and nerves (anterior aspect). Right side: superficial layers; left side: deeper layers. Note the segmental organization of the blood vessels and nerves.

1 Sternocleidomastoid muscle
2 Deltoid muscle
3 Pectoralis major muscle
4 Anterior cutaneous branches of intercostal nerves
5 Cut edge of anterior layer of rectus sheath
6 Rectus abdominis muscle
7 Tendinous intersection
8 External abdominal oblique muscle
9 Lateral femoral cutaneous nerve
10 Femoral vein
11 Great saphenous vein
12 Medial supraclavicular nerves
13 Pectoralis minor muscle (reflected) and medial pectoral nerves
14 Axillary vein
15 Long thoracic nerve and lateral thoracic artery
16 Internal thoracic artery
17 Intercostal nerves
18 Lateral cutaneous branches of intercostal nerves
19 Superior epigastric artery
20 Thoraco-abdominal (intercostal) nerves
21 Transverse abdominal muscle
22 Posterior layer of rectus sheath
23 Inferior epigastric artery
24 Lateral femoral cutaneous nerve
25 Inguinal ligament and ilio-inguinal nerve
26 Femoral nerve
27 Femoral artery
28 Spermatic cord
29 Testis
30 Posterior intercostal arteries
31 Internal abdominal oblique muscle
32 Lateral cutaneous branch of intercostal nerve
33 Dorsal branch of spinal nerve
34 Latissimus dorsi muscle
35 Deep muscles of the back (medial and lateral tract)
36 Anterior layer of rectus sheath
37 Posterior layer of rectus sheath
38 Thoracolumbar fascia
39 Spinal cord
40 Aorta
41 Ventral root } of spinal
42 Dorsal root } nerve



Horizontal section through the abdominal wall (inferior aspect) showing the location of the intercostal arteries (left side) and nerves (right side).



1 Rectus abdominis muscle
2 Tendinous intersection
3 Internal abdominal oblique muscle
4 External abdominal oblique muscle (reflected)
5 Anterior superior iliac spine
6 Ilio-inguinal nerve
7 Spermatic cord
8 Costal margin
9 Superior epigastric artery
10 Thoraco-abdominal (intercostal) nerves
11 Posterior layer of rectus sheath
12 Transverse abdominal muscle
13 Semilunar line
14 Arcuate line
15 Inferior epigastric artery
16 Inguinal ligament

Abdominal wall with vessels and nerves (anterior aspect). The left rectus abdominis muscle has been divided and reflected to display the inferior epigastric vessels. The left internal abdominal oblique muscle has been removed to show the thoraco-abdominal nerves.



1 Internal thoracic artery
2 Intercostal artery
3 Musculophrenic artery
4 Rectus abdominis muscle
5 Internal abdominal oblique muscle
6 External abdominal oblique muscle
7 Inferior epigastric artery
8 Deep circumflex iliac artery
9 Superficial circumflex iliac artery
10 Femoral artery
11 Intercostal nerve
12 Superior epigastric artery
13 Intercostal nerve
14 Iliohypogastric nerve (L$_1$)
15 Spermatic cord
16 Femoral branch of genitofemoral nerve
17 Genital branch of genitofemoral nerve

Thoracic and abdominal walls with arteries and nerves (anterior aspect).



Inguinal canal in the male, right side (superficial layer, anterior aspect). There is a small inguinal hernia (arrow).



Inguinal canal in the male, right side (superficial layer, anterior aspect). The external abdominal oblique muscle has been divided to display the inguinal canal.

1 Aponeurosis of external abdominal oblique muscle
2 Superficial circumflex iliac vein
3 Inguinal ligament
4 Lateral crus of inguinal ring
5 Superficial epigastric vein
6 Saphenous opening
7 Femoral artery and vein
8 Great saphenous vein
9 Anterior cutaneous branches of femoral nerve
10 Anterior layer of rectus sheath
11 Intercrural fibers
12 Superficial inguinal ring
13 Spermatic cord and genital branch of genitofemoral nerve
14 Penis with dorsal nerves and deep dorsal vein of penis
15 Aponeurosis of external abdominal oblique muscle (divided and reflected)
16 Internal abdominal oblique muscle
17 Ilio-inguinal nerve
18 Anterior cutaneous branches of iliohypogastric nerve
19 Superficial external pudendal veins

112897_S_215_250_Kap_3:_ 06.11.2014 9:35 Uhr Seite 222



Inguinal canal in the male, right side (deep layer, anterior aspect). Spermatic cord with exception of ductus deferens (probe) has been divided and reflected.



General characteristics of lower part of anterior abdominal wall and inguinal canal.

1 Internal abdominal oblique muscle (reflected)
2 Transverse abdominal muscle
3 Inguinal ligament
4 Spermatic cord with the exception of the ductus deferens (divided and reflected)
5 Ductus deferens and interfoveolar ligament
6 Superficial circumflex iliac artery
7 Femoral artery and vein
8 Superficial inguinal lymph nodes and inguinal lymph vessel
9 Inferior epigastric artery and vein
10 Falx inguinalis or conjoint tendon (cut)
11 Pubic branch of inferior epigastric artery
12 Iliacus muscle
13 Ureter
14 Ductus deferens (in situ)
15 Femoral nerve
16 Spermatic cord with ductus deferens and external spermatic fascia
17 Cremaster muscle
18 Internal spermatic fascia
19 Tunica vaginalis testis
20 Testis and epididymis
21 Rectum
22 Anterior layer of rectus sheath
23 Intercrural fibrae
24 Urinary bladder
25 Superficial inguinal ring
26 Saphenous opening with great saphenous vein
27 Deep dorsal vein of penis
28 Penis
29 Glans of penis
30 Rectus abdominis muscle
31 Deep inguinal ring
32 Pampiniform venous plexus and testicular artery
33 Fascia lata and sartorius muscle
34 Anterior superior iliac spine
35 Inferior epigastric artery
36 Lateral femoral cutaneous nerve
37 Ilioinguinal nerve
38 Suspensory ligament of penis
39 Sartorius muscle
40 External abdominal oblique muscle
41 Dartos fascia and scrotal skin
42 Ductus deferens
43 Vaginal process
44 Peritoneum


1
2
30
3
31
14
32
8
33
26
28
34
35
36
3
37
15
25
7
38
37
16
39
27
20

Inguinal and femoral regions in the male (anterior aspect). On the right, the spermatic cord was dissected to display the ductus deferens and the accompanying vessels and nerves. The fascia lata on the left side has been removed.


2
1
40
31
9
44
30
22
41
28
17
18
16
42
43
19
20
A
B
III
II
I
C
III
II
I

Layers of spermatic cord and types of hernias. Left: normal situation. Middle: location of acquired inguinal hernias: A = indirect inguinal hernia; B = direct inguinal hernia. Right: congenital indirect inguinal hernia (C); the vaginal process remained open.

I = Median umbilical fold containing urachus chord.
II = Medial umbilical fold with remnants of umbilical artery.
III = Lateral umbilical fold with inferior epigastric artery and vein.



Inguinal region in the female (anterior aspect). Left side: superficial layer; right side: external and internal abdominal oblique muscles divided and reflected.

1 Aponeurosis of external abdominal oblique muscle
2 Internal abdominal oblique muscle (divided and reflected)
3 Transverse abdominal muscle
4 Superficial circumflex iliac artery and vein
5 Superficial inguinal ring with fat pad
6 Medial and lateral crural fibers
7 Round ligament (ligamentum teres uteri)
8 Labium majus pudendi
9 Anterior layer of rectus sheath
10 Superficial epigastric artery and vein
11 Inguinal ligament
12 Cutaneous branch of ilio-inguinal nerve
13 Superficial inguinal lymph nodes
14 Entrance of round ligament into the labium majus
15 External pudendal artery and vein
16 Position of deep inguinal ring
17 Ilio-inguinal nerve
18 Internal abdominal oblique muscle
19 Pubic branch of inferior epigastric artery
20 Genital branch of genitofemoral nerve
21 Fat pad of inguinal canal
22 Ilio-inguinal nerve
23 Sheath of round ligament (inguinal canal)
24 Transversalis fascia



Inguinal canal in the female, right side (anterior aspect). The external abdominal oblique muscle has been divided and reflected to display the ilio-inguinal nerve and the round ligament.



Inguinal canal in the female, right side (anterior aspect). The external and internal abdominal oblique muscles have been divided and reflected to show the content of the inguinal canal.



Back of a strong man. Borderlines indicate the scapula and the trapezius muscle.



Regions of the back in the female.

1 Suprascapular region
2 Deltoid region
3 Scapular region
4 Infrascapular region
5 Vertebral region
6 Posterior cubital region
7 Lumbar region
8 Sacral region
9 Gluteal region



Innervation of the back. The dorsal branches of the spinal nerves display a segmental arrangement. The segmental innervation regions of the back are indicated.


C_5
C_6
C_7
C_8
Th_1
Th_2
Th_3
Th_4
Th_5
Th_6
Th_7
Th_8
Th_9
Th_{10}
Th_{11}
Th_{12}
L_1
L_2
L_3
L_4
L_5
S_1
S_2
S_3
S_4
S_5

Segmental arrangement of the back. Cervical (C_1–C_8; only shown are C_5–C_8), thoracal (Th_1–Th_{12}), lumbar (L_1–L_5), and sacral (S_1–S_5) segments are colored different.



Muscles of the back. Dissection of the erector spinae muscle (lateral column of the intrinsic back muscles).



Origin and insertion of erector spinae muscle (sacrospinal system).

1 Rectus capitis posterior minor muscle
2 Rectus capitis posterior major muscle
3 Obliquus capitis inferior muscle
4 Spinous process of axis
5 Semispinalis cervicis muscle
6 Spinous process of seventh cervical vertebra
7 Iliocostalis cervicis muscle
8 External intercostal muscles
9 Iliocostalis thoracis muscle
10 Longissimus thoracis muscle
11 Iliocostalis lumborum muscle
12 Internal abdominal oblique muscle
13 Semispinalis capitis muscle (divided)
14 Longissimus capitis muscle
15 Levator scapulae muscle
16 Longissimus cervicis muscle
17 Rhomboid major muscle
18 Spinalis thoracis muscle
19 Serratus posterior inferior muscle (reflected)
20 Spinous process of second lumbar vertebra
21 Iliac crest
22 Mastoid process



Muscles of the back. Dissection of the deeper layer of the intrinsic back muscles. Longissimus and iliocostalis muscles are cut.

1 Rectus capitis posterior minor muscle
2 Rectus capitis posterior major muscle
3 Obliquus capitis superior muscle
4 Obliquus capitis inferior muscle
5 Semispinalis cervicis muscle
6 Levator scapulae muscle
7 Rhomboideus major muscle
8 Scapula with infraspinatus muscle
9 Teres major muscle
10 Spinalis muscle
11 Latissimus dorsi muscle
12 Levatores costarum muscles
13 Spinous processes of lumbar vertebrae
14 Ribs (Th_{11}, Th_{12})
15 Multifidus muscle
16 Longissimus and iliocostalis muscles (cut)
17 Iliac crest (lumbar triangle)
18 Thoracolumbar fascia
19 Gluteus maximus muscle
20 External occipital protuberance
21 Occipital artery and greater occipital nerve (C_2)
22 Posterior tubercle of atlas
23 Spinous process of axis
24 Spinous process of seventh cervical vertebra (vertebra prominens)
25 Medial branches of dorsal branches of spinal nerves
26 External intercostal muscles
27 Lateral branches of dorsal branches of spinal nerves
28 Superior cluneal nerves



Muscles of the back (deepest layer).



Muscles of the back (deepest layer). Lumbar region (higher magnification).

1 Semispinalis cervicis muscle
2 Levator scapulae muscle
3 Levatores costarum muscles
4 Vertebral arches of lumbar vertebrae
5 Supraspinal ligaments
6 Intertransverse lumbar muscles
7 Lumbar rotator muscles
8 Cutaneous branches of spinal nerves
9 Lumbar interspinal muscles
10 Longissimus and iliocostalis muscles (cut)
11 Spinal muscle of the back
12 Multifidus muscle
13 Tenth rib (T_{10})



Muscles of the back. Transversospinal muscles, deepest layer on the right, where all parts of semispinalis and multifidus muscles have been removed.



Origin and insertion of erector spinae muscle, medial column (transversospinal and intertransversal system).

1	Rectus capitis posterior minor muscle
2	Obliquus capitis superior muscle
3	Rectus capitis posterior major muscle
4	Obliquus capitis inferior muscle
5	Spinous process of axis
6	Longissimus capitis muscle
7	Trapezius muscle (reflected) and accessory nerve (n. XI)
8	Spinous processes
9	Rhomboid major muscle
10	Transverse processes of thoracic vertebrae
11	Teres major muscle
12	Intertransverse ligaments
13	Levatores costarum muscles
14	Rotatores muscles
15	Tendons of iliocostalis muscle
16	Intertransversarii laterales lumborum muscles
17	Iliac crest
18	Gluteus maximus muscle
19	Semispinalis capitis muscle
20	Semispinalis cervicis muscle
21	Semispinalis thoracis muscle
22	External intercostal muscles
23	Multifidus muscle
24	Posterior cervical intertransversarii muscles
25	Spinalis thoracis muscle



Innervation of the back (superficial [left] and deeper [right] layers). Right trapezius and latissimus dorsi muscles have been removed.

1 Occipital belly of occipitofrontalis muscle
2 Splenius capitis muscle
3 Trapezius muscle
4 Medial cutaneous branches of dorsal rami of spinal nerves
5 Medial margin of scapula
6 Rhomboid major muscle
7 Latissimus dorsi muscle
8 Lateral cutaneous branches of dorsal rami of spinal nerves
9 Thoracolumbar fascia
10 External abdominal oblique muscle
11 Iliac crest
12 Last coccygeal vertebra
13 Anus
14 Greater occipital nerve
15 Third occipital nerve
16 Lesser occipital nerve
17 Cutaneous branches of cervical plexus
18 Levator scapulae muscle
19 Deltoid muscle
20 Rhomboid major and minor muscles
21 Upper lateral cutaneous nerve of arm (branch of axillary nerve)
22 Teres major muscle
23 Iliocostalis thoracis muscle
24 Serratus posterior inferior muscle
25 Superior cluneal nerves
26 Middle cluneal nerves
27 Inferior cluneal nerves
28 Posterior femoral cutaneous nerve

▷ **To page 231:**

1 Trapezius muscle
2 Infraspinatus muscle
3 Left latissimus dorsi muscle
4 Thoracolumbar fascia
5 Splenius cervicis muscle
6 Serratus posterior superior muscle
7 Medial branches of dorsal rami of thoracic spinal nerves
8 Lateral branches of dorsal rami of thoracic spinal nerves
9 Iliocostalis muscle
10 Serratus posterior inferior muscle
11 Latissimus dorsi muscle (reflected)



Innervation of the back. Dissection of the dorsal branches of the spinal nerves. On the right, longissimus thoracis muscle has been removed and iliocostalis muscle laterally reflected.



Innervation of the back (deeper layer).

1 Semispinalis capitis muscle
2 Left splenius capitis muscle (cut and reflected)
3 Left splenius cervicis muscle (cut and reflected)
4 Semispinalis thoracis muscle
5 Spinalis thoracis muscle
6 Latissimus dorsi muscle (reflected)
7 Iliac crest
8 Lesser occipital nerve
9 Splenius capitis muscle
10 Levator scapulae muscle
11 Splenius cervicis muscle
12 Serratus posterior superior muscle
13 Scapula
14 Medial branches of dorsal rami of spinal nerves
15 Rib and external intercostal muscle
16 Iliocostalis thoracis muscle
17 Lateral branches of dorsal rami of spinal nerves
18 Multifidus muscle
19 Superior cluneal nerves

1 Greater occipital nerve (C_2)
2 Suboccipital nerve (C_1)
3 Medial branches of dorsal rami of spinal nerves
4 Lateral branches of dorsal rami of spinal nerves
5 Superior cluneal nerves (L_1–L_3)
6 Middle cluneal nerves (S_1–S_3)
7 Inferior cluneal nerves
(derived from branches of the sacral plexus, ventral rami)
8 Lesser occipital nerve
9 Great auricular nerve
10 Trapezius muscle
11 Deltoid muscle
12 Latissimus dorsi muscle
13 Gluteus maximus muscle
14 External intercostal muscle
15 Internal intercostal muscle
16 Innermost intercostal muscle
17 Dorsal ramus of spinal nerve
18 Spinal nerve and spinal ganglion
19 Sympathetic trunk with ganglion
20 Intercostal nerve
21 Lateral cutaneous branch } of intercostal nerve
22 Anterior cutaneous branch } of intercostal nerve
23 Longissimus thoracis muscle
24 Spinal cord
25 Aorta
26 Esophagus
27 Body of rib
28 Thoracic rib
29 Thoracic duct
30 Azygos vein



General characteristics of the innervation of the back. Distribution of dorsal branches of spinal nerves. Note the segmental arrangement of the innervation of the dorsal part of the trunk.



Horizontal section through the posterior part of the thoracic wall (MRI scan). (From Heuck et al., MRT-Atlas, 2009.)



Horizontal section through the anterior and posterior parts of the thoracic wall. Position and branches of spinal nerves and vessels in one thoracic segment are shown.



Lumbar part of spinal cord (posterior aspect). Note the relation between the nervous and muscular segments.



Terminal part of spinal cord (posterior aspect). The dura mater has been removed.



Spinal cord with spinal nerves and meningeal coverings. The vertebral canal has been opened. Longissimus dorsi and iliocostal muscles have been removed.

1 Cerebellomedullary cistern
2 Medulla oblongata
3 Third cervical nerve (C_3)
4 Greater occipital nerve (C_2)
5 Dorsal primary ramus
6 Dorsal roots
7 Spinal ganglion
8 Spinal dura mater
9 Spinal arachnoid mater
10 Filum terminale
11 Conus medullaris
12 Cauda equina
13 Lateral branch of dorsal ramus of spinal nerve
14 Ventral ramus of spinal nerve (intercostal nerve)
15 Iliocostalis muscle



Thoracic part of spinal cord (posterior aspect). Vertebral canal and dura mater have been opened.

1 Arch of vertebra (divided)
2 Spinal nerve with meningeal coverings
3 Dorsal roots of thoracic spinal nerves
4 Spinal cord (thoracic portion)
5 Spinal ganglia with meningeal coverings
6 Pia mater with blood vessels
7 Dura mater (opened)
8 Denticulate ligament
9 Lateral branch of dorsal ramus of spinal nerve
10 Dorsal ramus of spinal nerve (dividing into a medial and lateral branch)
11 Medial branch of dorsal ramus of spinal nerve
12 Spinal dura mater
13 Spinal nerves of sacral segments
14 Filum terminale



Terminal part of spinal cord with dura mater (posterior aspect). Dorsal part of sacrum has been removed.



Spinal cord with intercostal nerves. Inferior thoracic region (anterior aspect). Anterior portion of thoracic vertebrae removed, dural sheath opened, and spinal cord slightly reflected to the right to display the dorsal and ventral roots.

1 Dura mater
2 Spinal cord
3 Costotransverse ligament
4 Innermost intercostal muscle
5 Vertebral arches (cut surfaces)
6 Eleventh rib
7 Intercostal nerve
8 Collateral branch of intercostal nerve
9 Intercostal nerve (entering the intermuscular interval)
10 Anterior root filaments
11 Spinal (dorsal root) ganglion
12 Posterior root filaments
13 Arachnoid mater and denticulate ligament
14 Anterior spinal artery


1
2
3
4
5
6
7
6
8
9

Spinal cord and lumbar plexus in situ (anterior aspect).


C_1
1
2
C_4
4
C_8
7
1
Th_2
Th_4
5
Th_7
7
Th_{10}
10
L_1
L_4
12
S_2
1
4
C_1–C_8
Th_1–Th_{12}
L_1–L_5
S_1–S_5
Co

Organization of spinal cord segments in relation to the vertebral column (anterior aspect).
C = cervical; Th = thoracic; L = lumbar;
S = sacral segments; Co = coccygeal bone.
Numbers indicate the related vertebrae.

1 Conus medullaris
2 Filum terminale
3 Subcostal nerve
4 Iliohypogastric nerve
5 Ilio-inguinal nerve
6 Genitofemoral nerve
7 Lateral femoral cutaneous nerve
8 Femoral nerve
9 Obturator nerve



Lumbar part of vertebral column with pelvis and lower thoracic part (sagittal section, medial aspect).

1 Eleventh rib
2 Body of third lumbar vertebra
3 Intervertebral disc
4 Body of fifth lumbar vertebra
5 Anterior superior iliac spine
6 Symphysial surface
7 Body of twelfth thoracic vertebra
8 Intervertebral foramen
9 Body of first lumbar vertebra
10 Vertebral canal
11 Spinous process of fifth lumbar vertebra
12 Sacrum (median sacral crest)
13 Promontory (promontorium)
14 Sacrum
15 Arcuate line
16 Coccyx
17 Ischial tuberosity
18 Sympathetic trunk with ganglia
19 Ureter
20 Iliohypogastric nerve (Th_{12}, L_1)
21 Ilio-inguinal nerve (L_1)
22 Femoral nerve (L_1–L_4)
23 Genitofemoral nerve (L_1, L_2)
24 Inferior hypogastric plexus
25 Ductus deferens
26 Urinary bladder
27 Medullary cone of spinal cord
28 Root filaments of spinal nerves
29 Subarachnoid space
(filled with cerebrospinal fluid) (blue)
30 Terminal filament of spinal cord
31 Sacral plexus
32 Pelvic splanchnic nerves (nervi erigentes)
33 Rectum



Lumbar part of vertebral column with spinal cord and root filaments (sagittal section). Note the high location of the medullary cone. Sacral plexus and inferior hypogastric plexus are schematically shown.



Paramedian section through the lumbar part of vertebral column with vertebral canal and spinal cord (dashed line in the schematic drawing; MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Median section through the lumbar part of vertebral column with vertebral canal and spinal cord (continuous line in the schematic drawing; MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)

1 First lumbar vertebra (L_1)
2 Root filaments of spinal nerves
3 Sacrum
4 Uterus
5 Spinal cord
6 Dura mater of spinal cord
7 Anterior longitudinal ligament
8 Medullary cone of spinal cord
9 Intervertebral disc of lumbar vertebra



Localization of the sections (red lines).



Horizontal section through the neck. Dissection of the second cervical spinal nerve. Posterior surface at top of figure.



Spinal cord with meningeal coverings (anterior aspect).

1 Trapezius muscle
2 Semispinalis capitis muscle
3 Dorsal ramus of spinal nerve
4 Sternocleidomastoid muscle
5 Platysma muscle
6 Dorsal and ventral roots of spinal nerves
7 Spinal ganglion
8 Posterior belly of digastric muscle
9 Ventral ramus of spinal nerve
10 Vertebral artery
11 Great auricular nerve
12 Superficial temporal artery
13 Styloid process
14 Internal jugular vein and internal carotid artery
15 Rectus capitis posterior major muscle
16 Dura mater and subarachnoid space
17 Denticulate ligament
18 Vertebral artery
19 Parotid gland
20 Dens of axis (divided) and inferior articular facet of atlas
21 Longus capitis muscle
22 Pharyngeal cavity
23 Medial pterygoid muscle
24 Periosteum of vertebral canal
25 Posterior spinal arteries
26 Anterior spinal artery

Meningeal coverings
27 Dura mater
28 Subdural space
29 Extradural or epidural space with venous plexus and fatty tissue
30 Arachnoid
31 Subarachnoid space
32 Pia mater
33 Nucleus pulposus
34 Crus of diaphragm
35 Intervertebral disc
36 Body of first lumbar vertebra
37 Spinal cord
38 Conus medullaris
39 Cauda equina
40 Filum terminale
41 Spinous process



Sagittal section through the vertebral canal (Th_9–L_2). (MRI scan).



Sagittal section through the vertebral canal (Th_{12}–L_2). Note the red bone marrow (unfixed).


1
2
3
4
5
6
7
9
12
10
11
13
14
15
16
17
18
19
20
8
21
22
23
24
25

Median section through the head and trunk in the adult (female). The conus medullaris of the spinal cord is located at the level of L_1.


2
18
3
19
20
21
22
15
23
24
4
8
29
6
7
26
9
27
28
14
16
17

Median section through the head and trunk in the neonate. Note that in the neonate the conus medullaris of the spinal cord extends far more caudally than in the adult.

1	Cerebrum
2	Corpus callosum
3	Pons
4	Larynx
5	Trachea
6	Left atrium
7	Right ventricle
8	Esophagus
9	Liver
10	Stomach
11	Pancreas
12	Transverse colon
13	Umbilicus
14	Small intestine
15	Uterus
16	Urinary bladder
17	Pubic symphysis
18	Cerebellum
19	Medulla oblongata
20	Spinal cord
21	Conus medullaris
22	Cauda equina
23	Rectum
24	Vagina
25	Anus
26	Inferior vena cava
27	Aorta
28	Umbilical cord
29	Thymus



Posterior aspect of the neck (superficial layer). Dissection of the trapezius muscle and the cutaneous branches of the dorsal branches of spinal nerves.

1	Sternocleidomastoid muscle
2	Lesser occipital nerve
3	Descending fibers of trapezius muscle
4	Spine of scapula
5	Medial cutaneous branches of dorsal rami of spinal nerves
6	Medial margin of scapula
7	Rhomboid major muscle
8	Latissimus dorsi muscle
9	Galea aponeurotica
10	Occipital belly of occipitofrontalis muscle
11	Greater occipital nerve
12	Third occipital nerve
13	Splenius capitis muscle
14	Great auricular nerve
15	Cutaneous nerves of cervical plexus
16	Transverse fibers of trapezius muscle
17	Ascending fibers of trapezius muscle
18	Teres major muscle



Posterior aspect of the neck (deeper layer). The left trapezius muscle has been divided and reflected. On the right, trapezius, rhomboid, and splenius muscles have been divided. The right levator scapulae muscle has been slightly reflected.

1	Galea aponeurotica	11	Left trapezius muscle and accessory nerve	20	Splenius cervicis muscle
2	Occipital belly of occipitofrontalis muscle	12	Levator scapulae muscle	21	Right accessory nerve and superficial branch of transverse cervical artery
3	Occipital artery	13	Superficial branch of transverse cervical artery	22	Right levator scapulae muscle
4	Greater occipital nerve (C_2)	14	Rhomboid minor muscle	23	Dorsal scapular nerve and deep branch of transverse cervical artery
5	Semispinalis capitis muscle	15	Rhomboid major muscle	24	Serratus posterior superior muscle
6	Sternocleidomastoid muscle	16	Medial margin of scapula	25	Right trapezius muscle (divided and reflected)
7	Lesser occipital nerve	17	Medial branches of dorsal rami of spinal nerves	26	Right rhomboid major muscle (divided and reflected)
8	Left splenius capitis muscle	18	Ligamentum nuchae		
9	Third occipital nerve (C_3)	19	Splenius capitis muscle (divided)		
10	Spinous process of vertebra prominens (C_7)				



Posterior aspect of the neck (deepest layer). Trapezius, splenius capitis, and cervicis muscles have been divided and partly removed or reflected.

1 Skin of scalp
2 Galea aponeurotica
3 Occipital belly of occipitofrontalis muscle
4 Occipital artery
5 Greater occipital nerve
6 Third occipital nerve
7 Semispinalis capitis muscle
8 Levator scapulae muscle
9 Accessory nerve (n. XI)
10 Superficial cervical artery
11 Trapezius muscle (reflected)
12 Longissimus cervicis muscle
13 Medial cutaneous branches of dorsal rami of spinal nerves
14 Medial margin of scapula
15 Splenius capitis muscle (divided)
16 Sternocleidomastoid muscle
17 Lesser occipital nerve
18 Great auricular nerve
19 Splenius cervicis muscle
20 Longissimus cervicis muscle
21 Spinous process of vertebra prominens (C_7)
22 Rhomboid muscles (divided)
23 Iliocostalis thoracis muscle
24 Longissimus thoracis muscle



Posterior aspect of the neck (deepest layer). Dissection of suboccipital triangle. The right semispinalis capitis muscle has been divided and reflected.



Suboccipital triangle and position of the vertebral artery.

1	Greater occipital nerve
2	Occipital artery
3	Rectus capitis posterior minor muscle
4	Spinous process of axis
5	Left splenius capitis muscle (cut)
6	Lesser occipital nerve
7	Left sternocleidomastoid muscle
8	Third occipital nerve (C_3)
9	Great auricular nerve
10	Left semispinalis capitis muscle
11	Left semispinalis cervicis muscle (cut)
12	Levator scapulae muscle
13	Left longissimus cervicis muscle
14	Medial branches of dorsal rami of spinal nerves
15	Occipital belly of occipitofrontalis muscle
16	Semispinalis capitis muscle (cut)
17	Obliquus capitis superior muscle
18	Rectus capitis posterior major muscle
19	Vertebral artery
20	Suboccipital nerve (C_1)
21	Muscular branch of vertebral artery
22	Obliquus capitis inferior muscle
23	Right semispinalis cervicis muscle
24	Deep cervical artery
25	Dorsal scapular nerve
26	External occipital protuberance
27	Trapezius muscle (cut)
28	Cervical vertebra (C_3)
29	Mastoid process and splenius capitis muscle
30	Atlas
31	Axis
32	Spinous process of third cervical vertebra



Posterior aspect of the neck (deepest layer). Dissection of suboccipital triangle on both sides.

1 Occipital belly of occipitofrontalis muscle
2 Occipital artery
3 Insertion of semispinalis capitis muscle (divided)
4 Lesser occipital nerve (from cervical plexus)
5 Suboccipital nerve (C_1)
6 Greater occipital nerve (C_2)
7 Splenius capitis muscle (reflected)
8 Splenius cervicis muscle
9 Levator scapulae muscle
10 Accessory nerve (n. XI) and trapezius muscle
11 Longissimus cervicis muscle
12 Iliocostalis cervicis muscle
13 Medial cutaneus branches of dorsal rami of spinal nerves (C_7, C_8)
14 Longissimus thoracis muscle
15 Medial margin of scapula
16 Rectus capitis posterior minor muscle
17 Obliquus capitis superior muscle
18 Rectus capitis posterior major muscle
19 Obliquus capitis inferior muscle
20 Spinous process of axis
21 Semispinalis cervicis muscle
22 Semispinalis capitis muscle (divided and reflected)
23 Transverse cervical artery (superficial branch)
24 Serratus posterior superior muscle (divided and reflected)
25 Rhomboid minor muscle (divided and reflected)
26 Rhomboid major muscle (divided and reflected)



Posterior aspect of the neck (deepest layer). The vertebral canal caudally of the atlas and axis has been opened to show the spinal cord. The dura mater has been partly removed.

1	External occipital protuberance
2	Greater occipital nerve (C_2) and occipital artery
3	Atlas (posterior arch)
4	Axis (posterior arch)
5	Spinal dura mater
6	Spinal cord
7	Spinal ganglion
8	Posterior root filaments (fila radicularia posterior)
9	Occipital belly of occipitofrontalis muscle
10	Splenius capitis muscle (cut and reflected)
11	Sternocleidomastoid muscle
12	Levator scapulae muscle
13	Posterior branches of spinal nerves
14	Arches of cervical vertebrae (cut)



Posterior aspect of the neck (deepest layer). Dissection of medulla oblongata and spinal cord. The cranial cavity has been opened.

1 Vermis of the cerebellum
2 Medulla oblongata and posterior spinal artery
3 Vertebral artery
4 Spinal ganglion
5 Occipital artery
6 Cerebellum
7 Cerebellomedullary cistern
8 Posterior arch of atlas
9 Greater occipital nerve (C_2)
10 Levator scapulae muscle and intertransverse ligament
11 Dorsal roots of spinal nerves
12 Vertebral arch
13 Denticulate ligament and arachnoid mater
14 Area where pia mater has been removed
15 Spinal dura mater
16 Dorsal rami of spinal nerves



Posterior aspect of the neck (deepest layer). Dissection of medulla oblongata and spinal cord in relation to the brain.

1 Calvaria
2 Left hemisphere of the brain
3 Cerebellomedullary cistern
4 Spinal cord
5 Scapula with infraspinous muscle
6 Posterior root filaments (fila radicularia posterior)
7 Levatores costarum muscles
8 Falx cerebri with sinus sagittalis superior
9 Subarachnoidal space
10 Confluens sinuum
11 Transverse sinus

12 Cerebellum
13 Occipital artery
14 Suboccipital nerve (C_1)
15 Greater occipital nerve (C_2)
16 Posterior branches of spinal nerves
17 Levator scapulae muscle
18 Deltoid muscle
19 Rhomboid muscles
20 Vertebral arches (cut)
21 External intercostal muscles
22 Spinal dura mater



Oblique-lateral aspect of the neck (deeper layer). The trapezius muscle has been removed.

1 External occipital protuberance
2 Semispinalis capitis muscle
3 Splenius capitis muscle
4 Scapula
5 Splenius cervicis muscle
6 Posterior branches of spinal nerves
7 Longissimus muscle
8 Spinous processes of thoracic vertebrae
9 Iliocostalis muscle
10 Latissimus dorsi muscle
11 Epidermis of the head (scalp)
12 Galea aponeurotica
13 Occipital belly of occipitofrontalis muscle
14 Occipital artery
15 Greater occipital nerve (C_2)
16 Lesser occipital nerve
17 Sternocleidomastoid muscle
18 Great auricular nerve
19 Punctum nervosum
20 Transverse cervical nerve
21 Supraclavicular nerves
22 Accessory nerve (n. XI)
23 Trapezius muscle (cut edge)
24 Medial margin of scapula
25 Rhomboid major muscle
26 Infraspinous muscle
27 Teres major muscle

4 Thoracic Organs

Position of the Thoracic Organs 252
Respiratory System 254
Heart 260
Regional Anatomy of the Thoracic Organs 274
Posterior Mediastinum 284
Diaphragm 292
Coronal Sections through the Thorax 294
Horizontal Sections through the Thorax 296
Mammary Gland 298





Thoracic organs in situ (anterior aspect). The anterior thoracic wall has been removed.

1 Trachea
2 Ascending aorta
3 Upper lobe of left lung
4 Right coronary artery
5 Right ventricle of the heart
6 Costal margin
7 Liver
8 Sternum
9 Right auricle of the heart
10 Middle lobe of right lung
11 Right atrium of the heart
12 Main bronchus
13 Azygos vein
14 Left ventricle of the heart and bulb of aorta
15 Esophagus
16 Descending aorta
17 Spinal cord



Horizontal section through the thorax at the level of the seventh thoracic vertebra (from below).



Sagittal section through the thoracic and abdominal cavities.



Sagittal section through the thoracic and abdominal cavities (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg.)

1 Aortic arch
2 Left atrium of the heart
3 Esophagus
4 Right atrium of the heart
5 Liver
6 Stomach
7 Abdominal aorta
8 Transverse colon (dilated)
9 Body of lumbar vertebra
10 Pulmonary trunk
11 Right ventricle of the heart
12 Superior mesenteric artery
13 Trachea
14 Remaining parts of thymus gland
15 Ascending aorta
16 Pericardium



Sagittal section through the thoracic cavity. The parts of the mediastinum are indicated by colors (compare with the table).

Parts of mediastinum	Content
Superior mediastinum (yellow)	Trachea, brachiocephalic veins, thymus, aortic arch, esophagus, thoracic duct
Middle mediastinum (blue)	Heart, ascending aorta, pulmonary trunk, pulmonary veins, phrenic nerves
Posterior mediastinum (orange)	Esophagus with vagus nerves, descending aorta, thoracic duct, sympathetic trunks
Anterior mediastinum (pink)	Smaller vessels and nerves, fat and connective tissue, thymus (only in the child)



Respiratory system. The lungs have been fixed in expiration and turned laterally. Head bisected and turned laterally.



Bronchial tree (anterior aspect). The lung tissue has been removed. The bronchopulmonary segments are numbered 1–10.

1 Sphenoid sinus
2 Pharyngeal opening of auditory tube
3 Spinal cord
4 Dens of axis
5 Oropharynx (oropharyngeal isthmus)
6 Epiglottis
7 Entrance of larynx
8 Esophagus
9 Upper lobe of right lung
10 Azygos vein
11 Branches of pulmonary artery
12 Right main bronchus
13 Bifurcation of trachea
14 Tributaries of right pulmonary veins
15 Middle lobe of right lung
16 Lower lobe of right lung
17 Frontal sinus
18 Superior nasal concha
19 Middle nasal concha
20 Inferior nasal concha
21 Hard palate
22 Soft palate with uvula
23 Tongue
24 Vocal fold
25 Larynx
26 Trachea
27 Upper lobe of left lung
28 Left pulmonary artery
29 Left main bronchus
30 Left pulmonary veins
31 Lower lobe of left lung

▷ **To page 255:**

1 Nasal cavity
2 Pharynx
3 Larynx (thyroid cartilage)
4 Trachea
5 Upper lobe of right lung
6 Bifurcation of trachea
7 Right main bronchus
8 Horizontal fissure of right lung
9 Middle lobe of right lung
10 Oblique fissures of lungs
11 Lower lobe of right lung
12 Clavicle
13 Upper lobe of left lung
14 Left main bronchus
15 Bronchi supplying bronchopulmonary segments
16 Lower lobe of left lung
17 Costal margin
18 Hyoid bone
19 Right superior lobe bronchus
20 Right middle lobe bronchus
21 Right inferior lobe bronchus
22 Left superior lobe bronchus
23 Left inferior lobe bronchus
24 Segmental bronchi
25 Branches of pulmonary arteries
26 Branches of pulmonary veins


1
2
3
4
5
6
7
8
9
10
11
17
12
13
14
15
10
16
17

Organization and positions of the respiratory organs (anterior aspect).


18
7
19
20
21
24
3
4
6
14
22
23
24

Larynx, trachea, and bronchial tree (anterior aspect).


5
19
25
26
20
21
10
11
1
2
3
4
5
6
7
9
10
13
26
25
22
23
25
26
10
16
1-2
3
4
5
6
8
9
10

Mediastinal dissection of the bronchial tree, pulmonary veins, and pulmonary arteries of right lung (left) and left lung (right) (medial aspect). The bronchopulmonary segments are numbered 1–10.


1
1
2
7
3
4
5
6
8
5
9
10
1
2
3
4
5
6
7
8
9
10
5
6
1
2
3
4
11
1
2
3
4
5
6
7
8
9
10
11

Surface projections of lungs and pleura on the thoracic wall. Left: anterior aspect; right: right-lateral aspect. Red = margins of the lung; blue = margins of pleura. The numbers indicate the ribs.


7
12
5
6
9
13
2
3
4
5
6
7
8
9
10
11
12
7
9
14
1
2
3
4
5
6
7
8
9
10
11

Surface projections of lungs and pleura on the thoracic wall. Left: posterior aspect; right: left-lateral aspect. Red = margins of lung; blue = margins of pleura. The numbers indicate the ribs.

1 Apex of lung
2 Upper lobe of right lung
3 Horizontal fissure of right lung
4 Middle lobe of right lung
5 Oblique fissures of lungs
6 Lower lobe of right lung
7 Upper lobe of left lung
8 Cardiac notch of left lung
9 Lower lobe of left lung
10 Infrasternal angle
11 Costal margin
12 Spine of scapula
13 First lumbar vertebra
14 Space between border of lung and pleura (costodiaphragmatic recess)



Right lung (lateral aspect).



Left lung (lateral aspect).



Right lung (medial aspect).



Left lung (medial aspect).

1 Apex of lung
2 Upper lobe of right lung
3 Horizontal fissure of right lung
4 Oblique fissure of right lung
5 Middle lobe of right lung
6 Lower lobe of right lung
7 Inferior border
8 Upper lobe of left lung
9 Impressions of ribs
10 Oblique fissure of left lung
11 Lower lobe of left lung
12 Groove of subclavian artery
13 Groove of azygos arch
14 Branches of right pulmonary artery
15 Bronchi
16 Right pulmonary veins
17 Pulmonary ligament
18 Diaphragmatic surface
19 Groove of aortic arch
20 Left pulmonary artery
21 Branches of left pulmonary veins
22 Left secondary bronchi
23 Groove of thoracic aorta
24 Groove of esophagus
25 Cardiac impression
26 Lingula



Right lung (medial aspect).



Left lung (medial aspect).



Right lung (lateral aspect).



Left lung (lateral aspect).

The bronchopulmonary segments of the lungs are differentiated by the various colors. Notice that there is no segment in the left lung that corresponds to the seventh segment of the right lung. Compare with the schematic drawing on the facing page.



Distribution of bronchopulmonary segments of the lungs and their relation to the bronchial tree. (After J. F. Huber.)

The bronchopulmonary segments are morphologically and functionally separate, independent respiratory units of the lung tissue. Each segment is surrounded by connective tissue that is continuous with the visceral pleura. The segmental bronchi are centrally located in each segment and are closely accompanied by branches of the pulmonary arteries, whereas the tributaries of the pulmonary veins run **between** the segments. Thus, the veins serve two adjacent segments that drain for the most part into more than one vein. A bronchopulmonary segment is therefore not a complete vascular unit, but segmentation is the result of a specific architecture of the lung vasculature.

Right lung			**Left lung**			
1	Apical segment	Upper lobe bronchus	1+2	Apicoposterior segment	Superior division	Upper lobe bronchus
2	Posterior segment					
3	Anterior segment		3	Anterior segment		
4	Lateral segment	Middle lobe bronchus	4	Superior lingular segment	Inferior division	
5	Medial segment		5	Inferior lingular segment		
6	Superior (apical) segment	Lower lobe bronchus	6	Superior (apical) segment		Lower lobe bronchus
7	Medial basal segment		7	Absent		
8	Anterior basal segment		8	Anteromedial basal segment		
9	Lateral basal segment		9	Lateral basal segment		
10	Posterior basal segment		10	Posterior basal segment		





Heart and related vessels in situ (anterior aspect). Myocardium and coronary arteries have been displayed.

1 Internal jugular vein
2 Common carotid artery
3 Brachiocephalic trunk
4 Ascending aorta
5 Right lung
6 Right auricle
7 Right coronary artery
8 Myocardium of right ventricle
9 Diaphragm
10 Costal margin
11 Thyroid gland and internal jugular vein
12 Trachea and left common carotid artery
13 Left brachiocephalic vein
14 Left lung
15 Pericardium (cut edge)
16 Pulmonary trunk
17 Anterior interventricular artery
18 Myocardium of left ventricle
19 Apex of the heart



1 Right brachiocephalic vein
2 Superior vena cava
3 Right pulmonary artery
4 Right pulmonary veins
5 Ascending aorta
6 Right atrium
7 Right ventricle
8 Inferior vena cava
9 Left internal jugular vein
10 Left common carotid artery
11 Left axillary artery and vein
12 Left brachiocephalic vein
13 Pulmonary trunk
14 Left atrium
15 Left ventricle
16 Descending aorta

Position of heart and related vessels in the thoracic cavity (anterior aspect). Blue = regions of heart and vessels with venous blood flow; red = regions of heart and vessels with arterial blood flow; blue arrows: veins; red arrows: arteries.



Heart and related vessels in situ (anterior aspect). Anterior thoracic wall, pericardium, and epicardium have been removed, the trachea has been divided.

1 Larynx (thyroid cartilage)
2 Sternocleidomastoid muscle (divided)
3 Trachea (divided) and right internal jugular vein
4 Vagus nerve
5 Right common carotid artery and cephalic vein
6 Esophagus
7 Right axillary vein
8 Right and left brachiocephalic veins
9 Superior vena cava
10 Right auricle
11 Right coronary artery
12 Right atrium
13 Diaphragm
14 Pericardium (cut edges)
15 Costal margin
16 Omohyoid muscle
17 Left common carotid artery
18 Left internal jugular vein
19 Clavicle (divided)
20 Left recurrent laryngeal nerve
21 Subclavian vein
22 Pericardial reflection
23 Pulmonary trunk
24 Ascending aorta
25 Anterior interventricular sulcus and anterior interventricular branch of left coronary artery
26 Right ventricle
27 Left ventricle
28 Aortic valve
29 Tricuspid or right atrioventricular valve
30 Inferior vena cava
31 Pulmonary veins
32 Pulmonary valve
33 Left atrioventricular (bicuspid or mitral) valve



Heart and related vessels in situ (anterior aspect). Position of the valves.


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19

Heart of 30-year-old woman (anterior aspect).


11
13
20
21
18
22
19
3
23
24
4
8
25
9
10

Heart of 30-year-old woman (oblique-posterior aspect).

1 Left subclavian artery
2 Left common carotid artery
3 Brachiocephalic trunk
4 Superior vena cava
5 Ascending aorta
6 Bulb of the aorta
7 Right auricle
8 Right atrium
9 Coronary sulcus
10 Right ventricle
11 Aortic arch
12 Ligamentum arteriosum
13 Left pulmonary veins
14 Left auricle
15 Pulmonary trunk
16 Sinus of pulmonary trunk
17 Anterior interventricular sulcus
18 Left ventricle
19 Apex of the heart
20 Left atrium
21 Epicardial fat overlying coronary sinus
22 Posterior interventricular sulcus
23 Pulmonary artery
24 Right pulmonary veins
25 Inferior vena cava
26 Pulmonary veins


11
23
20
26
21
18
4
26
8
25
9
10
22

Heart (posterior aspect). The myocardium of the left ventricle has been fenestrated to show the muscle fiber bundles of the deeper layer with their more circular course.


19
18
15
17
19
26

Vortex of cardiac muscle fibers (inferior aspect).



Heart with coronary arteries (anterior aspect, systolic phase of heart action).

1	Brachiocephalic trunk
2	Right pulmonary artery
3	Superior vena cava
4	Right pulmonary veins
5	Ascending aorta
6	Right atrium
7	Right coronary artery
8	Right ventricle
9	Left common carotid artery and left subclavian artery
10	Descending aorta (thoracic part)
11	Ligamentum arteriosum (remnant of ductus arteriosus Botalli)
12	Left pulmonary artery
13	Aortic arch
14	Left pulmonary veins
15	Pulmonary trunk
16	Left atrium
17	Left coronary artery
18	Diagonal branch of anterior interventricular vein
19	Interventricular branch of left coronary artery
20	Left ventricle
21	Left brachiocephalic vein
22	Thoracic wall
23	Liver
24	Aortic valve
25	Chordae tendineae
26	Papillary muscles
27	Stomach



Coronal section through the thorax at the level of the ascending aorta (MRI scan).
(Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Heart, fixed in diastole (anterior aspect). The ventricles are relaxed, atria contracted.



Heart, fixed in systole (antero-lateral aspect). The ventricles are contracted, atria dilated.

1	Ascending aorta
2	Superior vena cava
3	Right auricle
4	Right atrium
5	Coronary sulcus
6	Right ventricle
7	Pulmonary trunk
8	Left auricle
9	Anterior interventricular sulcus
10	Left ventricle
11	Right pulmonary artery
12	Sulcus terminalis with sinu-atrial node
13	Line indicating plane of position of valves
14	Myocardium of right atrium
15	Inferior vena cava
16	Valve of pulmonary trunk
17	Right tricuspid valve
18	Myocardium of right ventricle



Morphological changes during heart movements. Note the changes in position of the valves (red arrows). Contracted portions of heart are indicated in dark gray.
A = **Diastole:** muscles of the ventricles relaxed, atrioventricular valves open, semilunar valves closed.
B = **Systole:** muscles of ventricles contracted, atrioventricular valves closed, semilunar valves open.



Coronal section through the thorax at the level of the left ventricle in dilation (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Coronal section through the thorax at the level of the left ventricle in contraction (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Coronal section through the human heart in the process of dilation (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Coronal section through the human heart in the process of contraction (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)

1 Pulmonary artery
2 Left atrium
3 Coronary sinus
4 Inferior vena cava
5 Left ventricle (dilated)
6 Left atrioventricular (mitral) valve
7 Left ventricle (contracted)
8 Great cardiac vein (left coronary vein)
9 Right atrium
10 Right ventricle
11 Septomarginal trabecula
12 Papillary muscle
13 Right atrioventricular (tricuspid) valve



Right heart (anterior aspect). Anterior wall of right atrium and ventricle removed.

1	Superior vena cava
2	Crista terminalis
3	Fossa ovalis
4	Opening of inferior vena cava
5	Opening of coronary sinus
6	Right auricle
7	Right coronary artery and coronary sulcus
8	Anterior cusp of tricuspid valve
9	Chordae tendineae
10	Anterior papillary muscle
11	Myocardium
12	Pulmonary trunk
13	Ascending aorta
14	Pulmonic valve
15	Conus arteriosus (interventricular septum)
16	Septal papillary muscles
17	Septomarginal trabecula or moderator band
18	Apex of heart
19	Left auricle
20	Aortic valve
21	Left ventricle
22	Pulmonary veins
23	Position of fossa ovalis
24	Left atrium
25	Left atrioventricular (bicuspid or mitral) valve
26	Right atrium
27	Pericardium
28	Posterior papillary muscle
29	Right ventricle
30	Interventricular septum



Heart, left ventricle with mitral valve, papillary muscles, and aortic valve. Anterior portion of the heart removed.



Heart, left ventricle with posterior part of mitral valve and papillary muscles. Atrium opened.



Valves of the heart (superior aspect). Left and right atria removed. Dissection of coronary arteries. Anterior wall of the heart at the top.

1 Pulmonic valve
2 Sinus of pulmonary trunk
3 Left coronary artery
4 Great cardiac vein
5 Left atrioventricular (mitral) valve
6 Coronary sinus
7 Aortic valve
8 Right coronary artery
9 Right atrioventricular (tricuspid) valve
10 Bulb of aorta
11 Anterior semilunar cusp of pulmonic valve
12 Left semilunar cusp of pulmonic valve
13 Right semilunar cusp of pulmonic valve
14 Left semilunar cusp of aortic valve
15 Right semilunar cusp of aortic valve
16 Posterior semilunar cusp of aortic valve
17 Pulmonary artery
18 Right atrium
19 Left atrium with pulmonary veins
20 Ascending aorta with aortic valve



Pulmonic and aortic valves (superior aspect). Both valves are closed. Anterior wall of the heart at the top.



Horizontal section through the heart at the level of the aortic valve (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)

Heart: Direction of Blood Flow





Heart (anterior aspect). Dissection of the four valves.

1	Brachiocephalic trunk
2	Superior vena cava
3	Sulcus terminalis
4	Right auricle
5	Right atrium
6	Aortic valve
7	Conus arteriosus (interventricular septum)
8	Right atrioventricular (tricuspid) valve
9	Anterior papillary muscle
10	Myocardium of right ventricle
11	Left common carotid artery
12	Left subclavian artery
13	Aortic arch
14	Ligamentum arteriosum (remnant of ductus arteriosus)
15	Thoracic aorta (descending aorta)
16	Ascending aorta
17	Left pulmonary vein
18	Pulmonary trunk
19	Left auricle
20	Pulmonic valve
21	Anterior papillary muscle with chordae tendineae
22	Myocardium of left ventricle
23	Posterior papillary muscle
24	Interventricular septum
25	Brachiocephalic veins
26	Chordae tendineae
27	Papillary muscles of right ventricle
28	Left atrium
29	Left atrioventricular (bicuspid or mitral) valve and chordae tendineae
30	Apex of the heart
31	Left coronary artery
32	Left ventricle



Circulation within the heart (anterior aspect). Arrows: direction of blood flow.



Frontal section through the heart at the level of left ventricle and ascending aorta (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.) Note the aortic valve.



Right ventricle. Dissection of atrioventricular node, atrioventricular bundle (bundle of His), and right limb or bundle branch of conducting system (probes).



Left ventricle. Dissection of left limb or bundle branch of conducting system (probes).

1	Ascending aorta
2	Superior vena cava
3	Right atrium
4	Opening of coronary sinus
5	Atrioventricular node
6	Right atrioventricular valve
7	Pulmonary trunk
8	Atrioventricular bundle (bundle of His)
9	Bifurcation of atrioventricular bundle
10	Right bundle branch
11	Interventricular septum
12	Aortic sinus
13	Entrance of left coronary artery
14	Aortic valve
15	Branches of left bundle branch
16	Purkinje fibers
17	Left auricle
18	Anterior papillary muscles
19	Sulcus terminalis
20	Bulb of aorta
21	Sinu-atrial node (arrows)
22	Muscle fiber bundles of right atrium
23	Coronary sulcus (with right coronary artery)
24	Bundles of conducting system
25	Inferior vena cava
26	Papillary muscles with Purkinje fibers
27	Left atrium
28	Left bundle branch



Right atrium. Anterior wall, showing the location of the sinu-atrial node (arrows).



Conducting system (yellow) **of the heart.**





Coronary arteries (anterior aspect). The epicardium and subepicardial fatty tissue have been removed. The arteries have been injected with red resin from the aorta.

Right coronary artery and veins of the heart (posterior aspect). The epicardium and subepicardial fatty tissue have been removed. The arteries have been injected with red resin.

1 Ascending aorta
2 Aortic bulb and sinu-atrial branch of right coronary artery (in the dissection above)
3 Right auricle
4 Right coronary artery
5 Right atrium
6 Coronary sulcus
7 Right ventricle
8 Left auricle
9 Pulmonary trunk
10 Circumflex branch of left coronary artery
11 Left coronary artery
12 Diagonal branch of left coronary artery
13 Anterior interventricular vein
14 Anterior interventricular artery
15 Anterior interventricular sulcus
16 Left ventricle
17 Apex of the heart
18 Right pulmonary vein
19 Left atrium
20 Left pulmonary veins
21 Oblique vein of left atrium (Marshall's vein)
22 Coronary sinus
23 Great cardiac vein
24 Coronary sulcus (posterior part)
25 Posterior vein of left ventricle
26 Middle cardiac vein
27 Left pulmonary artery
28 Inferior vena cava
29 Right atrium
30 Posterior interventricular branch of right coronary artery
31 Posterior interventricular sulcus
32 Superior vena cava
33 Right marginal branch of right coronary artery
34 Branch of sinu-atrial node
35 Minimal cardiac veins
36 Small cardiac veins
37 Sternum
38 Left atrium with pulmonary veins
39 Right marginal vein



Coronary arteries and veins of the heart (anterior aspect).



Horizontal section through heart and thoracic wall at the level of the aortic bulb (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Human heart (3-D reconstruction of electron beam CT scans as “Shaded Surface Display”).

1	Ascending aorta
2	Right coronary artery
3	Right ventricle
4	Left atrium
5	Pulmonary trunk
6	Septal branch of left coronary artery
7	Diagonal branch of left coronary artery
8	Anterior interventricular branch of left coronary artery
9	Left ventricle
10	Aortic root
11	Right marginal branch of right coronary artery
12	Circumflex branch of left coronary artery
13	Apex of the heart
14	Superior vena cava
15	Right atrium



Coronary arteries (anterior aspect; stereoscopic MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Coronary arteries (posterior aspect; stereoscopic MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Heart and right lung of the fetus (viewed from left side). The left lung has been removed. Note the ductus arteriosus (Botalli).



Heart of the fetus (anterior aspect). Right atrium and ventricle have been opened.

Shunts in the fetal circulation system		
1. Ductus venosus (of Arantius)	between umbilical vein and inferior vena cava	bypass of liver circulation
2. Foramen ovale	between right and left atrium	bypass of pulmonary circulation
3. Ductus arteriosus (Botalli)	between pulmonary trunk and aorta	

1 Right common carotid artery
2 Right brachiocephalic vein
3 Left brachiocephalic vein
4 Superior vena cava
5 Ascending aorta
6 Right auricle
7 Pulmonary trunk
8 Left primary bronchus
9 Left auricle
10 Right ventricle
11 Left ventricle
12 Left common carotid artery
13 Trachea
14 Superior lobe of right lung
15 Left subclavian artery
16 Aortic arch
17 Ductus arteriosus (Botalli)
18 Inferior lobe of right lung
19 Left pulmonary artery with branches to the left lung
20 Descending aorta
21 Left pulmonary veins
22 Inferior vena cava
23 Foramen ovale
24 Right atrium
25 Opening of inferior vena cava
26 Valve of inferior vena cava (Eustachian valve)
27 Opening of coronary sinus
28 Anterior papillary muscle of right ventricle



◁ **Heart and right lung of the fetus** (compare with the dissection above). Direction of blood flow indicated by arrows. Note the change in oxygenation of blood after ductus arteriosus entry into the aorta.



Thoracic and abdominal organs in the newborn (anterior aspect). The right atrium has been opened to show the foramen ovale. The left lobe of the liver has been removed.

1 Internal jugular vein and right common carotid artery
2 Right and left brachiocephalic vein
3 Aortic arch
4 Superior vena cava
5 Foramen ovale
6 Inferior vena cava
7 Ductus venosus
8 Liver
9 Umbilical vein
10 Small intestine
11 Umbilical artery
12 Urachus
13 Trachea and left internal jugular vein
14 Left pulmonary artery
15 Ductus arteriosus (Botalli)
16 Right ventricle
17 Hepatic arteries (red) and portal vein (blue)
18 Stomach
19 Urinary bladder
20 Portal vein
21 Pulmonary veins
22 Descending aorta
23 Placenta



◁ **Fetal circulatory system.**
The oxygen gradient is indicated by color.



Thoracic organs (anterior aspect). The left clavicle and ribs have been partially removed, and the right intercostal spaces have been opened to show the internal thoracic vein and artery.

1 Right internal jugular vein
2 Omohyoid muscle
3 Sternohyoid muscle and external jugular vein
4 Clavicle
5 Thoraco-acromial artery
6 Right subclavian vein
7 Pectoralis major muscle
8 External intercostal muscle
9 Pectoralis minor muscle
10 Body of sternum
11 Right internal thoracic artery and vein
12 Fascicles of transversus thoracis muscle
13 Internal intercostal muscles
14 Serratus anterior muscle
15 Costal margin
16 External abdominal oblique muscle
17 Anterior sheath of rectus abdominis muscle
18 Sternocleidomastoid muscle
19 Left internal jugular vein
20 Transverse cervical artery
21 Brachial plexus
22 Vagus nerve
23 Left axillary vein
24 Left internal thoracic artery and vein
25 Ribs and thoracic wall (cut)
26 Costal pleura
27 Xiphoid process
28 Superior epigastric artery
29 Diaphragm
30 Rectus abdominis muscle



Thoracic organs (anterior aspect). Ribs, clavicle, and sternum have been partly removed to show anterior mediastinum and pleura. Red = arteries; blue = veins; green = lymph vessels and nodes.

1 Sternothyroid muscle and its nerve (a branch of the ansa cervicalis)
2 Right internal jugular vein
3 Right common carotid artery
4 Cephalic vein
5 Right subclavian vein
6 Right brachiocephalic vein
7 Pectoralis major muscle (divided)
8 Pectoralis minor muscle (divided)
9 Parasternal lymph nodes
10 Internal thoracic artery and vein
11 Anterior margin of costal pleura
12 Pericardium
13 Fifth and sixth ribs (divided) and serratus anterior muscle
14 Costodiaphragmatic recess
15 External abdominal oblique muscle
16 Rectus abdominis muscle
17 Larynx (thyroid cartilage)
18 Thyroid gland
19 Trachea
20 Left vagus nerve
21 Left brachiocephalic vein
22 Left internal thoracic artery and vein
23 Thymus
24 Costal pleura
25 Costal margin
26 Superior epigastric artery
27 Margin of costal pleura
28 Diaphragm
29 Linea alba
30 Cut edge of anterior sheath of rectus abdominis muscle



Thoracic organs (anterior aspect). The internal thoracic vessels have been removed, and the anterior margins of the pleura and lungs have been slightly reflected to display the anterior and middle mediastinum, including the heart and great vessels. Red = arteries; blue = veins; green = lymph vessels and nodes.

1	Larynx (thyroid cartilage)
2	Thyroid gland
3	Trachea
4	Internal jugular vein
5	Brachial plexus
6	Right brachiocephalic vein and common carotid artery
7	Right phrenic nerve
8	Ascending aorta
9	Pectoralis minor muscle (divided)
10	Pulmonary trunk (covered by pericardium)
11	Costal pleura
12	Pericardium and heart
13	Serratus anterior muscle
14	Xiphoid process
15	Costal margin
16	External abdominal oblique muscle
17	Sternothyroid muscle (divided and reflected)
18	Vagus nerve
19	Left common carotid artery
20	Left sympathetic trunk
21	Left recurrent laryngeal nerve
22	Left internal thoracic artery and vein (divided)
23	Margin of costal pleura
24	Intercostal nerves and vessels
25	Superior epigastric artery
26	Rectus abdominis muscle
27	Diaphragm
28	Ansa cervicalis
29	Phrenic nerve and anterior scalene muscle
30	External jugular vein (divided)
31	Right subclavian vein
32	Right brachiocephalic vein
33	Internal thoracic artery (divided)
34	Internal thoracic vein (divided)
35	Right lung
36	Cricothyroid muscle
37	Omohyoid muscle
38	Thymus
39	Left lung



Thoracic organs (anterior aspect, enlarged details). The position (above the heart) and size of the thymus are shown.

112897_S_273_298_Kap_4:_ 06.11.2014 9:50 Uhr Seite 277



Thoracic organs (anterior aspect). The pleura has been opened and the lungs exposed. Remnants of the thymus and pericardium are seen.

1 Right internal jugular vein
2 Phrenic nerve and anterior scalene muscle
3 Clavicle (divided)
4 Right subclavian artery and vein
5 Internal thoracic artery
6 Right brachiocephalic vein
7 Brachiocephalic trunk
8 Thymus (atrophic)
9 Upper lobe of right lung
10 Horizontal fissure of right lung (incomplete)
11 Middle lobe of right lung
12 Oblique fissure of right lung
13 Lower lobe of right lung
14 Xiphoid process
15 Diaphragm
16 Thyroid gland
17 Left internal jugular vein
18 Brachial plexus
19 Left cephalic vein
20 Left common carotid artery and vagus nerve
21 Left brachiocephalic vein
22 Internal thoracic artery and vein (divided)
23 Ascending aorta and aortic arch
24 Upper lobe of left lung
25 Pericardium
26 Oblique fissure of left lung
27 Lower lobe of left lung
28 Costal margin



Thoracic organs (anterior aspect). The thoracic wall, costal pleura, pericardium, and diaphragm have been partly removed. Red = arteries; blue = veins.

1	Internal jugular vein
2	External jugular vein (displaced medially)
3	Brachial plexus
4	Trachea
5	Right common carotid artery
6	Clavicle (divided)
7	Right brachiocephalic vein
8	Upper lobe of right lung
9	Thymus (atrophic)
10	Horizontal fissure of right lung
11	Middle lobe of right lung
12	Pericardium (cut edges)
13	Oblique fissure of lung
14	Lower lobe of right lung
15	Diaphragm
16	Falciform ligament
17	Liver
18	Location of larynx
19	Left internal jugular vein
20	Thyroid gland
21	Omohyoid muscle (divided)
22	Vagus nerve
23	Left subclavian vein
24	First rib (divided)
25	Internal thoracic artery and vein
26	Pectoralis major and pectoralis minor muscles (cut edges)
27	Upper lobe of left lung
28	Right ventricle
29	Cardiac notch of left lung
30	Interventricular sulcus of heart
31	Left ventricle
32	Lingula
33	Lower lobe of left lung



Thoracic organs (anterior aspect). Position of the heart and middle mediastinum. The anterior wall of the thorax, the costal pleura, and the pericardium have been removed and the lungs slightly reflected.

1 Thyroid gland
2 Phrenic nerve and anterior scalene muscle
3 Vagus nerve and internal jugular vein
4 Clavicle (divided)
5 Brachial plexus and subclavian artery
6 Subclavian vein
7 Internal thoracic artery
8 Brachiocephalic trunk and right brachiocephalic vein
9 Superior vena cava and thymic vein
10 Right phrenic nerve
11 Transverse pericardial sinus (probe)
12 Right auricle
13 Middle lobe of right lung
14 Right ventricle
15 Cut edge of pericardium
16 Diaphragm
17 Internal jugular vein
18 Trachea
19 Left recurrent laryngeal nerve
20 Left common carotid artery and vagus nerve
21 Left brachiocephalic vein and inferior thyroid vein
22 Left internal thoracic artery and vein (divided)
23 Upper margin of pericardial sac
24 Ascending aorta
25 Pulmonary trunk
26 Left phrenic nerve and left pericardiacophrenic artery and vein
27 Upper lobe of left lung
28 Left ventricle



Thoracic organs (anterior aspect). Position of heart, dissection of coronary vessels in situ. The anterior wall of thorax, costal pleura, and pericardium have been removed.

1 Intermediate supraclavicular nerve
2 Internal jugular vein
3 Right phrenic nerve
4 Right vagus nerve
5 Right common carotid artery
6 Right subclavian vein
7 Right brachiocephalic vein
8 Right internal thoracic artery
9 Superior vena cava
10 Ascending aorta
11 Right lung
12 Right atrium
13 Right coronary artery and small cardiac vein
14 Right ventricle
15 Cut edge of pericardium
16 Diaphragm
17 Costal margin
18 Larynx (cricothyroid muscle and thyroid cartilage)
19 Thyroid gland
20 Left common carotid artery and left vagus nerve
21 Left recurrent laryngeal nerve
22 Trachea
23 Left internal thoracic artery and vein (divided)
24 Thymic veins
25 Margin of pericardial sac
26 Pulmonary trunk
27 Left lung
28 Left ventricle
29 Anterior interventricular artery and vein
30 Lingula
31 Liver



Thoracic organs (anterior aspect). Heart with valves in situ. Anterior wall of thorax, pleura, and anterior portion of pericardium have been removed. The right atrium and ventricle have been opened to show the right atrioventricular and pulmonary valves.

1	Omohyoid muscle
2	Pyramidal lobe of thyroid gland
3	Internal jugular vein
4	Thyroid gland
5	Right subclavian vein
6	Brachiocephalic trunk
7	Right brachiocephalic vein
8	Right internal thoracic artery
9	Right phrenic nerve
10	Superior vena cava
11	Pulmonary vein
12	Branches of pulmonary artery
13	Right auricle
14	Right atrium
15	Right atrioventricular (tricuspid) valve
16	Right lung
17	Posterior papillary muscle
18	Diaphragm
19	Left vagus nerve
20	Left phrenic nerve
21	Anterior scalene muscle
22	Brachial plexus
23	Thyrocervical trunk
24	Left common carotid artery
25	Left subclavian artery
26	Left internal thoracic artery
27	Apex of left lung
28	Left recurrent laryngeal nerve
29	Cut edge of pericardium
30	Pulmonary trunk (fenestrated)
31	Pulmonic valve
32	Supraventricular crest
33	Anterior papillary muscle
34	Left ventricle



Thoracic organs (anterior aspect). Pericardium and mediastinum. Anterior wall of thorax and heart have been removed and the lungs slightly reflected. Note the probe within transverse pericardial sinus.

1 Right internal jugular vein and right vagus nerve
2 Right phrenic nerve and anterior scalene muscle
3 Right common carotid artery
4 Brachial plexus
5 Right subclavian artery and vein
6 Right brachiocephalic vein
7 Right internal thoracic artery (divided)
8 Brachiocephalic trunk
9 Upper lobe of right lung
10 Superior vena cava
11 Transverse pericardial sinus (probe)
12 Right phrenic nerve and right pericardiacophrenic artery and vein
13 Right pulmonary veins
14 Oblique sinus of pericardium
15 Inferior vena cava
16 Diaphragmatic part of pericardium
17 Diaphragm
18 Costal margin
19 Thyroid gland
20 Trachea
21 Left recurrent laryngeal nerve and inferior thyroid vein
22 Left common carotid artery and left vagus nerve
23 Left internal thoracic artery and vein (divided)
24 Vagus nerve at aortic arch
25 Cut edge of pericardium
26 Ascending aorta
27 Pulmonary trunk (divided)
28 Left pulmonary veins
29 Left phrenic nerve and left pericardiacophrenic artery and vein
30 Contour of esophagus beneath pericardium
31 Contour of aorta beneath pericardium
32 Pericardium (cut edge)



Pericardial sac (anterior aspect). The heart has been removed, and the posterior wall of the pericardium has been opened to show the adjacent esophagus and aorta.

1	Internal thoracic vein
2	Superior vena cava
3	Oblique sinus of pericardium
4	Right pulmonary veins
5	Esophagus
6	Branches of right vagus nerve
7	Mesocardium
8	Inferior vena cava
9	Middle lobe of right lung
10	Diaphragm
11	Upper lobe of left lung
12	Ascending aorta
13	Pulmonary trunk
14	Transverse pericardial sinus
15	Left pulmonary veins
16	Descending aorta and left vagus nerve
17	Left lung (adjacent to pericardium)
18	Pericardium
19	Left subclavian artery
20	Vagus nerve
21	Left recurrent laryngeal nerve
22	Descending aorta
23	Pulmonary artery
24	Left atrium
25	Left ventricle
26	Coronary sinus
27	Left common carotid artery
28	Brachiocephalic trunk
29	Azygos arch
30	Right atrium
31	Right ventricle
32	Aortic arch



Heart with epicardium (posterior aspect). Arrows: oblique sinus.



Heart with epicardium (anterior aspect).
Arrow: pericardial reflection.



Mediastinal organs (anterior aspect). Heart and pericardium have been removed. Both lungs have been slightly reflected.

1 Supraclavicular nerves
2 Internal jugular vein
3 Omohyoid muscle
4 Right vagus nerve
5 Right common carotid artery
6 Right subclavian artery
7 Brachiocephalic trunk
8 Right brachiocephalic vein
9 Superior cervical cardiac branch of vagus nerve
10 Inferior cervical cardiac branches of vagus nerve
11 Azygos arch (divided)
12 Bifurcation of trachea
13 Right pulmonary artery
14 Right pulmonary veins
15 Right lung
16 Esophagus and branches of right vagus nerve
17 Inferior vena cava
18 Pericardium
19 Larynx (thyroid cartilage, cricothyroid muscle)
20 Thyroid gland
21 Internal jugular vein
22 Esophagus and left recurrent laryngeal nerve
23 Trachea
24 Left vagus nerve
25 Left common carotid artery
26 Aortic arch
27 Left recurrent laryngeal nerve branching off from vagus nerve
28 Left pulmonary veins
29 Thoracic aorta and left vagus nerve
30 Left lung
31 Left phrenic nerve (divided)

1 Internal jugular vein
2 Right vagus nerve
3 Thyroid gland
4 Right recurrent laryngeal nerve
5 Brachiocephalic trunk
6 Trachea
7 Bifurcation of trachea
8 Right phrenic nerve
9 Inferior vena cava
10 Diaphragm
11 Left subclavian artery
12 Left common carotid artery
13 Left vagus nerve
14 Aortic arch
15 Esophagus
16 Esophageal plexus
17 Thoracic aorta
18 Left phrenic nerve
19 Pericardium
at the central tendon of diaphragm
20 Superior vena cava
21 Pulmonary veins and left atrium



Bronchial tree in situ (anterior aspect). Heart and pericardium have been removed. The bronchi of the bronchopulmonary segments are dissected.
1–10 = numbers of segments (compare with pages 254, 255, and 259).



Frontal section through the thoracic cavity showing the mediastinal vessels (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Mediastinal organs (anterior aspect). The heart with the pericardium has been removed, and the lungs and aortic arch have been slightly reflected to show the vagus nerves and their branches.

1 Supraclavicular nerves
2 Right internal jugular vein with ansa cervicalis
3 Omohyoid muscle
4 Right vagus nerve
5 Clavicle
6 Right subclavian artery and recurrent laryngeal nerve
7 Right subclavian vein
8 Superior cervical cardiac branch of vagus nerve
9 Inferior cervical cardiac branch of vagus nerve
10 Azygos arch (divided)
11 Right lung
12 Right pulmonary artery
13 Right pulmonary veins
14 Esophagus
15 Esophageal plexus
16 Right phrenic nerve (divided)
17 Inferior vena cava
18 Pericardium covering the diaphragm
19 Larynx (thyroid cartilage and cricothyroid muscle)
20 Thyroid gland
21 Left internal jugular vein
22 Esophagus and left recurrent laryngeal nerve
23 Trachea
24 Left vagus nerve
25 Left common carotid artery
26 Aortic arch
27 Left recurrent laryngeal nerve
28 Bifurcation of trachea
29 Left pulmonary artery
30 Left primary bronchus
31 Descending aorta
32 Left pulmonary veins
33 Branch of left vagus nerve
34 Left lung
35 Left phrenic nerve (divided)



Mediastinal organs (anterior aspect). Heart and distal part of esophagus have been removed to display the vessels and nerves of the posterior mediastinum.

1 Thyroid gland
2 Right internal jugular vein
3 Right vagus nerve
4 Point where right recurrent laryngeal nerve is branching off the vagus nerve
5 Right brachiocephalic vein
6 Trachea
7 Left brachiocephalic vein (reflected)
8 Esophagus
9 Right bronchial artery
10 Posterior intercostal artery
11 Azygos vein
12 Thoracic duct
13 Posterior intercostal artery and vein (in front of the vertebral column)
14 Right phrenic nerve
15 Inferior vena cava
16 Diaphragm
17 Left vagus nerve
18 Thyrocervical trunk
19 Left subclavian artery
20 Left common carotid artery
21 Brachiocephalic trunk
22 Left vagus nerve
23 Aortic arch
24 Left recurrent laryngeal nerve
25 Left bronchial artery
26 Lymph node
27 Thoracic aorta
28 Esophageal plexus
29 Left phrenic nerve





Posterior mediastinal organs with diaphragm (anterior aspect). Heart and lungs have been removed, the costal margin remains in place. Note the different courses of left and right vagus.



Posterior mediastinal organs with diaphragm (anterior aspect). Three regions in which the esophagus is narrowed are shown:

A = termed upper sphincter (at the level of the cricoid cartilage);

B = termed middle sphincter (at the level of the aortic arch);

C = termed lower sphincter (at the level of the diaphragm).

1	Right subclavian artery
2	Right recurrent laryngeal nerve
3	Right brachiocephalic vein
4	Superior cervical cardiac nerve
5	Inferior cervical cardiac nerves and pulmonary branches
6	Bifurcation of trachea
7	Esophagus (thoracic part)
8	Bronchi of lateral and medial segments of middle lobe
9	Esophageal plexus and branches of right vagus nerve
10	Inferior vena cava and right phrenic nerve (cut)
11	Sternal part of diaphragm
12	Costal part of diaphragm
13	Falciform ligament of liver
14	Liver (quadrate lobe)
15	Left common carotid artery
16	Left recurrent laryngeal nerve
17	Esophageal branches of left vagus nerve and esophagus
18	Trachea
19	Aortic arch
20	Left vagus nerve
21	Left recurrent laryngeal nerve with inferior cardiac nerve
22	Left primary bronchus
23	Superior and inferior lingular bronchi
24	Esophageal plexus of left vagus nerve
25	Descending aorta
26	Central tendon of diaphragm covered with pericardium
27	Left phrenic nerve (divided)
28	Costal margin
29	Liver (left lobe)
30	Pharynx
31	Secondary bronchi
32	Esophagus (abdominal part)
33	Diaphragm
34	Abdominal aorta



Posterior mediastinal organs (anterior aspect).



Inferior segment of posterior mediastinum (anterior aspect).



Veins of the posterior wall of thoracic and abdominal cavities (anterior aspect).

1 Right vagus nerve
2 Thyroid gland and trachea
3 Intercostal nerve
4 Aortic arch
5 Azygos vein
6 Posterior intercostal artery
7 Greater splanchnic nerve
8 Diaphragm
9 Liver
10 Proper hepatic artery and hepatic plexus
11 Left recurrent laryngeal nerve
12 Inferior cervical cardiac nerves
13 Left vagus nerve and left recurrent laryngeal nerve
14 Left primary bronchus
15 Thoracic aorta and left vagus nerve
16 Esophagus and esophageal plexus
17 Thoracic duct
18 Spleen
19 Anterior gastric plexus and stomach (divided)
20 Splenic artery and splenic plexus
21 Celiac trunk and celiac plexus
22 Pancreas
23 Ramus communicans
24 Sympathetic trunk and sympathetic ganglion
25 Posterior intercostal vein and artery and intercostal nerve
26 Right brachiocephalic vein
27 Superior vena cava
28 Ascending lumbar vein
29 Lumbar veins
30 Right external iliac vein
31 Trachea
32 Accessory hemiazygos vein
33 Posterior intercostal veins
34 Hemiazygos vein
35 Inferior vena cava
36 Median sacral vein
37 Internal iliac vein



Mediastinal organs (right lateral aspect). Right lung and pleura of right half of the thorax have been removed.

1 Posterior intercostal arteries
2 Ganglion of sympathetic trunk
3 Sympathetic trunk
4 Vessels and nerves of the intercostal space (from above: posterior intercostal vein and artery and intercostal nerve)
5 Right primary bronchus
6 Ramus communicans of sympathetic trunk
7 Esophageal plexus (branches of right vagus nerve)
8 Pulmonary veins
9 Posterior intercostal vein
10 Azygos vein
11 Esophagus
12 Greater splanchnic nerve
13 Right vagus nerve
14 Right phrenic nerve
15 Inferior cervical cardiac branches of vagus nerve
16 Aortic arch
17 Superior vena cava
18 Right pulmonary artery
19 Heart with pericardium
20 Diaphragm

112897_S_273_298_Kap_4:_ 06.11.2014 9:50 Uhr Seite 291



Mediastinal organs (left lateral aspect). Posterior and superior mediastinum. The heart with the pericardium is located in situ. Within the posterior mediastinum the descending thoracic aorta and the sympathetic trunk are shown.



Main branches of descending aorta (anterior aspect).

1 Subclavian artery
2 Subclavian vein
3 Clavicle (divided)
4 Left vagus nerve
5 First rib (divided)
6 Left superior intercostal vein
7 Left atrium with pericardium
8 Left phrenic nerve and pericardiacophrenic artery and vein
9 Esophageal plexus (branches derived from left vagus nerve)
10 Apex of the heart with pericardium
11 Brachial plexus
12 Scapula (divided)
13 Posterior intercostal arteries
14 White ramus communicans of sympathetic trunk
15 Sympathetic trunk
16 Aortic arch
17 Left vagus nerve and left recurrent laryngeal nerve
18 Left pulmonary artery
19 Left primary bronchus
20 Thoracic aorta
21 Pulmonary vein
22 Esophagus (thoracic part)
23 Posterior intercostal artery and vein and intercostal nerve
24 Diaphragm
25 Common carotid artery
26 Subclavian artery
27 Highest intercostal artery
28 Bifurcation of trachea
29 Celiac trunk
30 Renal artery
31 Superior mesenteric artery
32 Inferior mesenteric artery
33 Common iliac artery



1 Superior vena cava
2 Right atrium
3 Right ventricle
4 Costal part of diaphragm
5 Costal margin
6 Position of costodiaphragmatic recess
7 Lateral arcuate ligament
8 Medial arcuate ligament
9 Right crus of lumbar part of diaphragm
10 Quadratus lumborum muscle
11 Ascending aorta
12 Pulmonary trunk
13 Left ventricle
14 Pericardium and diaphragm
15 Esophageal hiatus and abdominal part of esophagus (cut)
16 Lumbar part of diaphragm
17 Aortic hiatus
18 Psoas major muscle
19 Lumbar vertebrae

Diaphragm in situ (anterior aspect). Anterior walls of thoracic and abdominal cavities have been removed. Natural position of the heart above the central tendon on the diaphragm is shown.



Changes in the position of the diaphragm and thoracic cage during respiration. Left: lateral aspect; right: anterior aspect. During inspiration the diaphragm moves downward and the lower part of the thoracic cage expands forward and laterally, causing the costodiaphragmatic recess (R) to enlarge (cf. dotted arrows).



1 Azygos venous arch
2 Right pulmonary artery
3 Superior vena cava
4 Right pulmonary vein
5 Fossa ovalis
6 Hepatic veins
7 Inferior vena cava
8 Right crus of lumbar part of diaphragm
9 Medial arcuate ligament
10 Psoas major muscle
11 Left brachiocephalic vein
12 Terminal crista
13 Right atrium
14 Right auricle
15 Central tendon of diaphragm
16 Esophagus
17 Celiac trunk and superior mesenteric artery
18 Aorta
19 Costal part of diaphragm
20 Costal margin
21 Transverse abdominal muscle

Diaphragm and thoracic organs. Paramedian section to the right of the median plane through thoracic and upper abdominal cavities. The plane passes through the superior and inferior vena cava just to the right of the vertebral bodies. Most of the heart remains in situ to the left of this plane (viewed from the right side).



Diaphragm and thoracic organs (paramedian section). The heart is partly dissected.

1 First rib
2 Esophagus
3 Intercostal artery, vein, and nerve
4 Azygos venous arch
5 Pulmonal artery
6 Right bronchi
7 Pulmonary veins
8 Internal intercostal muscle
9 Sympathetic trunk
10 Diaphragm
11 Abdominal aorta
12 Anterior scalene muscle
13 Internal jugular vein
14 Subclavius muscle
15 Clavicle
16 Trachea
17 Junction between superior vena cava and left brachiocephalic vein
18 Aorta
19 Remnants of thymus gland
20 Entrance of superior vena cava into the right atrium
21 Right coronary artery and vein
22 Fossa ovalis
23 Right atrioventricular valve and anterior papillary muscle
24 Right ventricle with pericardium
25 Inferior vena cava



Coronal section through the thorax at the level of the ascending aorta (anterior aspect).



Coronal section through the thorax at the level of the ascending aorta (MRI scan).

1 Clavicle
2 Left brachiocephalic vein
3 Upper lobe of right lung
4 Aortic arch
5 Superior vena cava
6 Right atrium (entrance of inferior vena cava)
7 Coronary sinus
8 Liver
9 Second rib
10 Upper lobe of left lung
11 Pulmonary trunk
12 Ascending aorta and left coronary artery
13 Aortic valve
14 Pericardium
15 Myocardium of left ventricle
16 Lower lobe of left lung
17 Diaphragm
18 Colic flexures
19 Stomach
20 Brachiocephalic trunk





Coronal section through the thorax at the level of superior and inferior vena cava (anterior aspect).



Coronal section through the thorax at the level of the superior vena cava (MRI scan). Arrows: metastases of tumor.

1 Trachea
2 Upper lobe of right lung
3 Superior vena cava
4 Right pulmonary veins
5 Inferior vena cava and right atrium
6 Liver
7 Left common carotid artery
8 Left subclavian vein
9 Upper lobe of left lung
10 Aortic arch
11 Left pulmonary artery
12 Left auricle
13 Left atrium with orifices of pulmonary veins
14 Left ventricle (myocardium)
15 Pericardium
16 Diaphragm
17 Left colic flexure
18 Stomach
19 Left subclavian artery





Horizontal section through the thorax. Section 1 (from below).



Horizontal section through the thorax at the level of section 1 (MRI scan).
(Prof. Bautz and Dr. Janka, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)

1	Internal thoracic artery and vein
2	Right atrium
3	Lung
4	Pulmonary artery
5	Pulmonary vein
6	Primary bronchus
7	Esophagus
8	Serratus anterior muscle
9	Scapula
10	Longissimus thoracis muscle
11	Sternum
12	Pectoralis major and minor muscles
13	Conus arteriosus (right ventricle) and pulmonic valve
14	Ascending aorta and left coronary artery (only in the upper figure)
15	Left atrium
16	Descending aorta
17	Thoracic vertebra
18	Spinal cord
19	Latissimus dorsi muscle
20	Trapezius muscle

112897_S_273_298_Kap_4:_ 06.11.2014 9:50 Uhr Seite 297



Horizontal section through the thorax. Section 2 (from below).



Horizontal section through the thorax at the level of section 2 (MRI scan). (Prof. Bautz and Dr. Janka, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Horizontal section through the thorax. Levels of the sections are indicated.

21	Right ventricle
22	Right coronary artery
23	Right atrioventricular valve
24	Lung (upper lobe)
25	Left atrium
26	Pulmonary veins
27	Lung (lower lobe)
28	Erector muscle of spine
29	Third costal cartilage
30	Nipple
31	Left ventricle
32	Pericardium
33	Left atrioventricular valve
34	Left coronary artery and coronary sinus
35	Accessory hemiazygos vein
36	Serratus anterior muscle
37	Pulmonary trunk



Dissection of mammary gland (anterior aspect).



Dissection of mammary gland and axillary lymph nodes.

1 Platysma muscle
2 Clavicle
3 Deltoid muscle
4 Pectoralis major muscle
5 Deltopectoral groove and cephalic vein
6 Latissimus dorsi muscle
7 Medial mammarian branches of intercostal nerves

8 Breast tissue
9 Areola
10 Nipple (papilla)
11 Costal margin
12 Pectoral fascia
13 Mammary gland
14 Serratus anterior muscle (insertion)
15 Lactiferous sinus

16 Apical lymph nodes
17 Axillary lymph nodes
18 Intercostobrachial nerve
19 Lateral thoracic vein
20 Lymph vessels
21 Serratus anterior muscle
22 Medial branches of intercostal arteries
23 Pectoralis minor muscle



Mammary gland (sagittal section) of a pregnant female.



Lymphatics of the mammary gland. Most lymph vessels drain into the axillary lymph nodes.

5 Abdominal Organs

Position of the Abdominal Organs 300
Anterior Abdominal Wall 301
Stomach 302
Pancreas and Bile Ducts 304
Liver 307
Spleen 309
Vessels of the Abdominal Organs 310
Dissection of the Abdominal Organs 316
Posterior Abdominal Wall 326
Horizontal Sections through the Abdominal Cavity 330
Midsagittal Sections through the Abdominal Cavity 332





Abdominal organs in situ (anterior aspect). The greater omentum has been partly removed or reflected.

1	Liver (left lobe)
2	Stomach
3	Transverse colon
4	Small intestine
5	Cecum with vermiform appendix
6	Rectus abdominis muscle
7	Small intestine and peritoneum
8	Rib (cut)
9	Bile duct, duodenum, and pancreas
10	Inferior vena cava
11	Body of second lumbar vertebra (L_2)
12	Right kidney
13	Cauda equina and dura mater
14	Linea alba
15	Falciform ligament
16	Stomach and pylorus
17	Superior mesenteric artery and vein
18	Abdominal aorta
19	Pancreas adjacent to lesser sac (omental bursa)
20	Left renal artery and vein
21	Left kidney
22	Psoas major muscle
23	Deep muscles of the back



Horizontal section through the abdominal cavity at the level of the second lumbar vertebra (from below).



Anterior abdominal wall of the male. Frontal section through pelvic cavity and hip joints (internal aspect).



1 Left ventricle with pericardium
2 Diaphragm
3 Remnant of liver
4 Ligamentum teres (free margin of falciform ligament)
5 Site of umbilicus
6 Medial umbilical fold (containing the obliterated umbilical artery)
7 Lateral umbilical fold (containing inferior epigastric artery and vein)
8 Median umbilical fold (containing remnant of urachus)
9 Head of femur and pelvic bone
10 Urinary bladder
11 Root of penis
12 Falciform ligament of liver
13 Rib (divided)
14 Iliac crest (divided)
15 Site of deep inguinal ring and lateral inguinal fossa
16 Iliopsoas muscle (divided)
17 Medial inguinal fossa
18 Supravesical fossa
19 Posterior layer of rectus sheath
20 Transverse abdominal muscle
21 Umbilicus and arcuate line
22 Inferior epigastric artery
23 Femoral nerve
24 Iliopsoas muscle
25 Remnant of umbilical artery
26 Femoral artery and vein
27 Tendinous intersection of rectus abdominis muscle
28 Rectus abdominis muscle
29 Interfoveolar ligament
30 Pubic symphysis (divided)
31 External iliac artery and vein

Anterior abdominal wall of the male (internal aspect). The peritoneum and parts of the posterior layer of rectus sheath have been removed. Dissection of inferior epigastric arteries and veins.



Stomach (anterior aspect).



Mucosa of posterior wall of stomach (anterior aspect).



Position of the stomach (parasagittal section through upper part of left abdominal cavity 3.5 cm lateral to median plane).

1	Esophagus
2	Cardial notch
3	Cardial part of stomach
4	Lesser curvature of stomach
5	Pyloric sphincter
6	Angular notch (incisura angularis)
7	Pyloric canal
8	Pyloric antrum
9	Fundus of stomach
10	Greater curvature of stomach
11	Body of stomach
12	Folds of mucous membrane (gastric rugae)
13	Gastric canal
14	Right ventricle of heart
15	Diaphragm (cut edge)
16	Abdominal part of esophagus
17	Liver
18	Cardial part of stomach (cut edge)
19	Position of pyloric canal
20	Body of stomach
21	Transverse colon
22	Small intestine
23	Lung (cut edge)
24	Fundus of stomach (section)
25	Lumbar part of diaphragm (cut edge)
26	Suprarenal gland
27	Splenic vein
28	Pancreas
29	Superior mesenteric artery and vein
30	Intervertebral disc



Muscular coat of stomach, outer layer (anterior aspect).



Muscular coat of stomach, middle layer (anterior aspect).

1	Esophagus (abdominal part)
2	Cardial notch
3	Cardial part of stomach
4	Longitudinal muscle layer at lesser curvature of stomach
5	Lesser curvature
6	Incisura angularis
7	Circular muscle layer of pyloric part of stomach
8	Pyloric sphincter muscle
9	Fundus of stomach
10	Circular muscle layer of fundus of stomach
11	Longitudinal muscle layer of greater curvature of stomach
12	Greater curvature of stomach
13	Longitudinal muscle layer (transition from body to pyloric part of stomach)
14	Pyloric part of stomach
15	Oblique muscle fibers



Muscular coat of stomach, inner layer (anterior aspect).



Upper abdominal region with pancreas, duodenum, spleen, and left kidney (anterior aspect). Stomach and transverse colon have been removed and the liver elevated; the superior mesenteric vein is slightly enlarged.



Pancreas, duodenum, liver, and extrahepatic bile ducts (anterior aspect).

1 Liver
2 Hepatic artery proper
3 Hepatic duct
4 Cystic duct
5 Pylorus
6 Gastroduodenal artery
7 Gallbladder
8 Duodenum
9 Right colic flexure
10 Ascending colon
11 Spleen
12 Stomach
13 Splenic artery
14 Common hepatic artery
15 Portal vein
16 Pancreas
17 Duodenojejunal flexure
18 Kidney (with capsula adiposa)
19 Ureter
20 Superior mesenteric artery and vein
21 Common bile duct
22 Minor duodenal papilla
23 Major duodenal papilla
24 Pancreatic duct



Upper abdominal region with pancreas, duodenum, spleen, and left kidney (anterior aspect). Stomach and transverse colon have been removed and the duodenum fenestrated. The liver has been elevated to show the extrahepatic bile ducts. In this case the accessory pancreatic duct represents the main excretory duct of the pancreas.



Upper abdominal organs (anterior aspect). The schematic drawing shows the most common situation of the pancreatic ducts.

1	Liver
2	Hepatic artery proper
3	Cystic duct
4	Gallbladder
5	Minor duodenal papilla and accessory pancreatic duct
6	Major duodenal papilla and pancreatic duct
7	Duodenum
8	Spleen
9	Stomach
10	Splenic artery
11	Tail of pancreas
12	Pancreas (pancreatic duct and body of pancreas)
13	Kidney (with capsula adiposa in the dissection above)
14	Common bile duct
15	Superior mesenteric artery and vein
16	Ureter
17	Suprarenal gland
18	Aorta with celiac trunk
19	Inferior mesenteric vein



Bile ducts, gallbladder, and pancreatic duct (X-ray, a.-p. direction).



Isolated gallbladder and cystic duct (anterior aspect).
The gallbladder has been opened to display the mucous membrane.

1	Left hepatic duct
2	Right hepatic duct
3	Cystic duct
4	Neck of gallbladder
5	Body of gallbladder
6	Fundus of gallbladder
7	Common hepatic duct
8	Common bile duct
9	Pancreatic duct
10	Major duodenal papilla
11	Second lumbar vertebra
12	Folds of mucous membrane of gallbladder
13	Muscular coat of gallbladder
14	Neck of gallbladder (opened)
15	Cystic duct with spiral fold
16	Minor duodenal papilla
17	Accessory pancreatic duct
18	Uncinate process
19	Plica circularis of duodenum (Kerckring's fold)
20	Head of pancreas
21	Body of pancreas
22	Tail of pancreas
23	Descending part of duodenum
24	Incisure of pancreas



Pancreas with descending part of duodenum (posterior aspect). The duodenum was opened to display the duodenal papillae. Pancreatic duct has been dissected, the common bile duct has been divided. The sphincter of Oddi is shown.



Liver in situ (anterior aspect). Part of the diaphragm has been removed.



Liver in situ (parasagittal section through the left side of the abdomen 2 cm lateral to median plane).

1 Ribs (cut edges)
2 Diaphragm
3 Diaphragmatic surface of liver
4 Falciform ligament of liver
5 Right lobe of liver
6 Fundus of gallbladder
7 Gastrocolic ligament
8 Greater omentum
9 Aorta
10 Esophagus
11 Left lobe of liver
12 Stomach
13 Ligamentum teres
14 Transverse colon
15 Right atrium of heart
16 Central tendon and sternal portion of diaphragm
17 Liver (cut edge)
18 Entrance to duodenum (pylorus)
19 Stomach
20 Duodenum
21 Transverse colon (divided, dilated)
22 Small intestine
23 Thoracic aorta (longitudinally divided)
24 Esophagus (longitudinally divided)
25 Esophageal hiatus of diaphragm
26 Omental bursa (lesser sac)
27 Splenic artery
28 Pancreas
29 Left renal vein
30 Intervertebral disc
31 Abdominal aorta (longitudinally divided)


8
1
10
9
11
2
3
4
5
12
13
2
14
15
6
16
17
7
18
19
20

Liver (inferior aspect). Dissection of porta hepatis. Gallbladder partly collapsed. Ventral margin of liver above.

1 Fundus of gallbladder
2 Peritoneum (cut edges)
3 Cystic artery
4 Cystic duct
5 Right lobe of liver
6 Inferior vena cava
7 Bare area of liver
8 Notch for ligamentum teres and falciform ligament
9 Ligamentum teres
10 Falciform ligament of liver
11 Quadrate lobe of liver
12 Common hepatic duct
13 Left lobe of liver
14 Hepatic artery proper
15 Common bile duct } Portal triad
16 Portal vein
17 Caudate lobe of liver
18 Ligamentum venosum
19 Ligament of inferior vena cava
20 Appendix fibrosa (left triangular ligament)
21 Coronary ligament of liver
22 Hepatic veins
23 Porta hepatis


6
22
VIII
VII
IVa
I
II
III
VI
V
IVb
10
9
14
16
15
1

Segmentation of the liver (anterior aspect). Liver segments indicated by Roman numerals.


VI
V
IV
III
I
II
VII
VII
VIII
IVa
II
III
IVb
V
VI

Liver segments I–VIII. The three main hepatic veins (blue within both schematic drawings shown on the left) drain the eight segments of the liver that have no visible external markings.
Upper drawing = inferior aspect; lower drawing = superior aspect.


6
2
20
21
22
17
5
13
23
3
10
11
1
9
14
16
15

Liver and margins of peritoneal folds (anterior aspect).



Spleen in situ (left lateral aspect). Intercostal spaces and diaphragm have been fenestrated.

1	Serratus anterior muscle
2	Left lung
3	Diaphragm
4	Spleen
5	External abdominal oblique muscle
6	Gastrosplenic ligament
7	Splenic artery
8	Tail of pancreas
9	Superior border of spleen
10	Anterior border of spleen
11	Border of lung
12	Area of liver
13	Area of stomach
14	Tenth rib
15	Eleventh rib
16	Twelfth rib



Spleen (visceral surface). Hilum of spleen with vessels, nerves, and ligaments.



Location of the spleen (left lateral aspect).

1	Greater omentum
2	Middle colic artery
3	Right colic artery
4	Duodenum
5	Ascending colon
6	Ileum
7	Transverse colon
8	Celiac plexus
9	Duodenojejunal flexure
10	Superior mesenteric vein
11	Superior mesenteric artery
12	Jejunum
13	Jejunal arteries
14	Ileal arteries
15	Liver
16	Celiac trunk and abdominal aorta
17	Gallbladder
18	Pancreas
19	Ileocolic artery
20	Stomach
21	Spleen
22	Left colic flexure
23	Appendicular artery
24	Vermiform appendix



Vessels of upper abdominal organs and small intestine (anterior aspect). Dissection of superior mesenteric artery and vein. Greater omentum and transverse colon are reflected.



Arteries of upper abdominal organs and small intestine (anterior aspect). Main branches of superior mesenteric artery.



Vessels of upper abdominal organs and small intestine (anterior aspect). Dissection of superior mesenteric vein. The liver is dissected and elevated.



1	Liver
2	Hepatic artery proper
3	Hepatic duct
4	Gallbladder
5	Major duodenal papilla
6	Apex of the heart
7	Diaphragm
8	Common hepatic artery
9	Inferior vena cava
10	Pancreas
11	Stomach
12	Gastro-omental (gastro-epiploic) artery
13	Superior mesenteric vein
14	Small intestine
15	Jejunal vein
16	Superior mesenteric artery
17	Intestinal lymphatic vessels
18	Superior mesenteric plexus
19	Branches of superior mesenteric artery

Blood and lymphatic vessels of the small intestine (anterior aspect). Note the arterial arch of the mesenteric artery adjacent the small intestine.



Vessels of upper abdominal organs and small intestine (anterior aspect). Stomach and omentum majus have been removed. The liver is elevated.

1	Diaphragm	7	Superior mesenteric vein	13	Pancreas
2	Liver	8	Apex of the heart	14	Superior mesenteric artery
3	Proper hepatic artery	9	Esophagus (abdominal part)	15	Small intestine
4	Duodenum	10	Spleen	16	Inguinal ligament and femoral artery
5	Gallbladder	11	Splenic artery		
6	Inferior duodenal flexure	12	Tail of pancreas		



Dissection of portal venous system (anterior aspect). Blue = tributaries of portal vein; red = branches of superior mesenteric artery.



Main tributaries of portal vein (anterior aspect). Blue = tributaries of portal vein; violet = inferior vena cava; X = sites of portocaval anastomoses.

1	Portal vein
2	Superior mesenteric vein
3	Superior mesenteric artery
4	Right colic vein
5	Ileocolic vein
6	Ileocolic artery
7	Duodenojejunal flexure
8	Middle colic artery
9	Jejunum
10	Jejunal arteries and veins
11	Ileal arteries and veins
12	Inferior vena cava
13	Hepatic veins
14	Liver
15	Para-umbilical veins (located within the ligamentum teres)
16	Spleen
17	Left gastric vein with esophageal branches
18	Splenic vein
19	Inferior mesenteric vein
20	Gastro-omental veins
21	Ileal veins
22	Sigmoid veins
23	Superior rectal vein



Superior mesenteric artery and vein in relation to pancreas and duodenum (anterior aspect). Stomach and transverse colon have been removed and the liver elevated. Note the location of the spleen. A yellow probe is inserted through the omental foramen.

1 Ligamentum teres
2 Liver
3 Gallbladder and common bile duct
4 Hepatic artery proper and portal vein
5 Right gastric artery and pylorus
6 Gastroduodenal artery
7 Superior mesenteric artery
8 Superior mesenteric vein
9 Ascending colon
10 Duodenum
11 Ileocolic artery
12 Lymph nodes
13 Ileum
14 Cecum
15 Left lobe of liver
16 Caudate lobe of liver
17 Spleen
18 Left gastric artery
19 Splenic artery
20 Pancreas
21 Left colic flexure (cut)
22 Jejunal arteries
23 Ileal arteries
24 Jejunum
25 Middle colic artery
26 Right colic artery
27 Appendicular artery
28 Transverse mesocolon
29 Duodenojejunal flexure
30 Inferior mesenteric artery
31 Left colic artery
32 Sigmoid arteries
33 Superior rectal arteries
34 Inferior vena cava
35 Abdominal aorta
36 Descending colon
37 Ileum
38 Sigmoid colon
39 Vermiform appendix
40 Cecum



Main branches of superior and inferior mesenteric arteries (anterior aspect). Arrow: Riolan's anastomosis.



Vessels of the retroperitoneal organs (anterior aspect). Dissection of the inferior mesenteric artery and its anastomosis with the middle colic artery (arrow: Riolan's anastomosis). Greater omentum and transverse colon have been reflected and the intestine partly removed. The normally retrocecally located vermiform appendix has been replaced anteriorly. The right common iliac artery is partly obstructed by a blood thrombus.



1	Middle lobe of right lung
2	Xiphoid process
3	Costal margin
4	Falciform ligament of liver
5	Quadrate lobe of liver
6	Greater omentum
7	Upper lobe of left lung
8	Heart
9	Diaphragm
10	Left lobe of liver
11	Ligamentum teres
12	Stomach
13	Gastrocolic ligament
14	Transverse colon
15	Taenia coli
16	Appendices epiploicae
17	Cecum
18	Taenia coli
19	Ileum
20	Transverse mesocolon
21	Jejunum
22	Sigmoid colon
23	Position of root of mesentery
24	Vermiform appendix
25	Duodenojejunal flexure
26	Mesentery

Abdominal organs (anterior aspect). The anterior thoracic and abdominal walls have been removed.



Abdominal organs (anterior aspect). The greater omentum, which is fixed to the transverse colon, has been raised.



Abdominal organs (anterior aspect). The transverse colon has been reflected.



Abdominal organs (anterior aspect). The greater omentum has been removed.

1 Diaphragm
2 Costal margin
3 Transverse colon
4 Ascending colon with haustra
5 Free taenia of cecum
6 Ileum
7 Cecum
8 Falciform ligament of liver
9 Liver
10 Stomach
11 Gastrocolic ligament
12 Jejunum
13 Sigmoid colon
14 Ileocecal valve
15 Ileal ostium
16 Frenulum of ileal opening
17 Ostium of vermiforme appendix (probe in the dissection)
18 Ileocolic artery
19 Terminal ileum
20 Appendicular artery
21 Vermiform appendix
22 Meso-appendix
23 Mesentery



Ascending colon, cecum, and vermiform appendix. The cecum has been opened. Note the probe in the entrance of the vermiform appendix.



Variations in the position of the vermiform appendix. The cecum has been opened to show the ileal opening. a = retrocecal; b = paracolic; c = retro-ileal; d = pre-ileal; e = subcecal.

Dissection of the Abdominal Organs: Mesentery, Duodenojejunal Flexure, and Ileocecal Valve



1	Lung
2	Diaphragm
3	Falciform ligament of liver
4	Jejunum
5	Ileocecal fold
6	Meso-appendix
7	Vermiform appendix
8	Terminal ileum
9	Cecum
10	Pericardial sac
11	Xiphoid process
12	Costal margin
13	Liver
14	Stomach
15	Transverse colon
16	Duodenojejunal flexure
17	Inferior duodenal fold
18	Mesentery
19	Position of left kidney
20	Descending colon
21	Position of left common iliac artery
22	Sacral promontory
23	Sigmoid mesocolon
24	Sigmoid colon
25	Rectum
26	Beginning of jejunum
27	Peritoneum of posterior abdominal wall
28	Transverse mesocolon
29	Superior duodenal fold
30	Superior duodenal recess
31	Retroduodenal recess
32	Free taenia of ascending colon
33	Ileocecal valve
34	Frenulum of ileocecal valve
35	Orifice of vermiform appendix (probe)
36	Ileocolic artery
37	Vermiform appendix with appendicular artery
38	Ascending colon

Abdominal organs with mesenteries (anterior aspect). The small intestine has been reflected laterally to demonstrate the mesentery.



Duodenojejunal flexure (enlargement of preceding figure).



Ileocecal valve (anterior aspect). Cecum and terminal part of the ileum have been opened.



Upper abdominal organs (anterior aspect). Thorax and anterior part of diaphragm have been removed and the liver raised to display the **lesser omentum.** A probe has been inserted into the epiploic foramen and lesser sac.

1 Falciform ligament and ligamentum teres
2 Liver
3 Gallbladder (fundus)
4 Hepatoduodenal ligament
5 Epiploic foramen (probe)
6 Pylorus
7 Descending part of duodenum
8 Right colic flexure
9 Gastrocolic ligament
10 Caudate lobe of liver (behind lesser omentum)
11 Lesser omentum
12 Stomach
13 Lesser curvature of stomach
14 Superior part of duodenum
15 Diaphragm
16 Greater curvature of stomach with gastro-omental vessels
17 Twelfth thoracic vertebra
18 Right kidney
19 Right suprarenal gland
20 Inferior vena cava
21 Falciform ligament of liver
22 Abdominal aorta
23 Spleen
24 Lienorenal ligament
25 Gastrosplenic ligament
26 Pancreas
27 Lesser sac (omental bursa)



Horizontal section through the lesser sac above the level of epiploic foramen (superior aspect).



Upper abdominal organs (anterior aspect). **Lesser sac.** The lesser omentum has been partly removed and the liver and stomach have been slightly reflected.

1 Falciform ligament and ligamentum teres
2 Liver
3 Hepatoduodenal ligament
4 Gallbladder
5 Probe within the epiploic foramen
6 Superior part of duodenum
7 Pylorus
8 Descending part of duodenum
9 Right colic flexure
10 Gastrocolic ligament
11 Greater omentum
12 Caudate lobe of liver
13 Fundus of stomach
14 Probe at the level of the vestibule of lesser sac (through epiploic foramen)
15 Head of pancreas
16 Lesser curvature of stomach
17 Body of stomach
18 Diaphragm
19 Greater curvature with gastro-omental vessels
20 Head of pancreas and gastropancreatic fold
21 Spleen
22 Tail of pancreas
23 Left colic flexure
24 Root of transverse mesocolon
25 Transverse mesocolon
26 Gastrocolic ligament (cut edge)
27 Transverse colon
28 Umbilicus
29 Small intestine
30 Lesser omentum
31 Lesser sac (omental bursa)
32 Duodenum
33 Mesentery
34 Sigmoid colon


1
2
10
4
5
8
9
11
17
14
20
21
22
23
18
24
25
26
27

Upper abdominal organs (anterior aspect). **Lesser sac.** The gastrocolic ligament has been divided and the whole stomach raised to display the posterior wall of the lesser sac.


2
17
25
27
11
28
29
30
31
15
32
33
34

Midsagittal section through the abdominal cavity, demonstrating the site of lesser sac.
Blue = lesser sac (omental bursa); green = peritoneum; arrow: entrance to the lesser sac (epiploic foramen).


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
1
7
21
20
21
22
23
24
25
26
27
28
29
30
31
32
33

Upper abdominal organs (anterior aspect). **Celiac trunk.** The lesser omentum has been removed and the lesser curvature of the stomach reflected to display the branches of the celiac trunk. The probe is situated within the epiploic foramen.


2
5
10
9
6
14
30
15
34
18
28
36
25
37
35
24
26
29

Arteries of upper abdominal organs and branches of celiac trunk.



Upper abdominal organs (anterior aspect). **Branches of celiac trunk; blood supply of liver, pancreas, and spleen.** The stomach, superior part of duodenum, and celiac ganglion have been removed to reveal the anterior aspect of the posterior wall of the lesser sac (omental bursa) and the vessels and ducts of the hepatoduodenal ligament. The pancreas has been slightly reflected anteriorly.

1 Lung
2 Liver (visceral surface)
3 Lymph node
4 Inferior vena cava
5 Ligamentum teres (reflected)
6 Right branch of hepatic artery proper
7 Diaphragm
8 Common hepatic duct (dilated)
9 Cystic duct and artery
10 Gallbladder
11 Probe within the epiploic foramen
12 Right lobe of liver
13 Portal vein
14 Right gastric artery
15 Duodenum
16 Pylorus
17 Right colic flexure
18 Right gastro-omental (gastro-epiploic) artery
19 Transverse colon
20 Abdominal part of esophagus (cardiac part of stomach)
21 Fundus of stomach
22 Esophageal branches of left gastric artery
23 Lumbar part of diaphragm
24 Left gastric artery
25 Celiac trunk
26 Splenic artery
27 Pancreas
28 Common hepatic artery
29 Left gastro-omental (gastro-epiploic) artery
30 Gastroduodenal artery
31 Pyloric part of stomach
32 Greater curvature of stomach
33 Gastrocolic ligament
34 Supraduodenal artery
35 Short gastric arteries
36 Aorta
37 Spleen
38 Caudate lobe of liver
39 Left branch of hepatic artery proper
40 Descending part of duodenum (cut)
41 Left inferior phrenic artery
42 Suprarenal gland
43 Kidney
44 Transverse mesocolon



Lower abdominal organs (anterior aspect). **Inferior mesenteric artery and autonomic plexus.** The transverse colon with the mesocolon has been raised and the small intestine reflected.

1 Liver
2 Gallbladder
3 Middle colic artery
4 Jejunal artery
5 Inferior mesenteric artery
6 Sympathetic nerves and ganglia
7 Right common iliac artery
8 Small intestine (ileum)
9 Transverse colon (reflected)
10 Transverse mesocolon
11 Anastomosis between middle and left colic artery
12 Spleen
13 Abdominal aorta
14 Left colic artery
15 Duodenojejunal flexure
16 Descending colon (free taenia of colon)
17 Inferior mesenteric vein
18 Superior hypogastric plexus
19 Superior rectal artery
20 Sigmoid arteries
21 Peritoneum (cut edge)
22 Sigmoid mesocolon
23 Sigmoid colon



1	Liver
2	Middle colic artery
3	Horizontal part of duodenum (extended)
4	Superior mesenteric artery and vein
5	Right colic artery
6	Ileocolic artery
7	Ascending colon
8	Cecum
9	Greater omentum (reflected)
10	Transverse colon
11	Transverse mesocolon
12	Duodenojejunal flexure
13	Jejunal arteries
14	Jejunum
15	Ileal arteries
16	Mesenteric lymph nodes and lymph vessels
17	Ileum
18	Abdominal aorta
19	Inferior vena cava
20	Stomach
21	Spleen
22	Splenic artery
23	Head of pancreas
24	Superior mesenteric artery

Lower abdominal organs (anterior aspect). **Superior mesenteric artery and mesenteric lymph nodes.** The transverse colon has been reflected.



Frontal section through the abdominal cavity. The intestinal tract and vessels are filled with a paramagnetic substance (Gadolinium; MRI scan). (Prof. Rödl, Univ. Erlangen-Nuremberg, Germany.)



Posterior abdominal wall with pancreas and extrahepatic bile ducts in situ (anterior aspect). The gastrocolic ligament has been divided and the transverse colon and the stomach replaced to display the pancreas and superior mesenteric vessels.



Blood supply of upper abdominal organs (compare with dissection depicted on following page). Note the branching of the celiac trunk not visible behind the body of pancreas, the main arterial supply of liver, spleen, pancreas, stomach, and duodenum.

1 Stomach (pyloric part) and pylorus
2 Right gastro-omental (gastro-epiploic) artery
3 Fundus of gallbladder
4 Liver (right lobe)
5 Head of pancreas
6 Superior mesenteric artery and vein
7 Duodenum
8 Middle colic artery
9 Transverse colon
10 Greater curvature of stomach (remnants of gastrocolic ligament)
11 Body of stomach
12 Body of pancreas
13 Left gastro-omental (gastro-epiploic) artery
14 Splenic artery
15 Spleen
16 Tail of pancreas
17 Left colic flexure
18 Jejunum
19 Cystic artery
20 Hepatic artery proper
21 Celiac trunk
22 Right gastric artery
23 Common hepatic artery
24 Gastroduodenal artery
25 Superior mesenteric artery
26 Superior posterior pancreaticoduodenal artery
27 Superior anterior pancreaticoduodenal artery
28 Short gastric arteries
29 Left gastric artery
30 Posterior pancreatic branch of splenic artery
31 Inferior pancreaticoduodenal artery
32 Jejunal arteries



Posterior abdominal wall with pancreas, extrahepatic bile ducts, spleen, and liver with their vessels in situ (anterior aspect). The stomach has been removed, the liver elevated, and the descending part of duodenum fenestrated to display the openings of the pancreatic ducts. The pancreatic ducts were dissected. Note the location of superior mesenteric artery and vein between duodenum and pancreas.

1 Ligamentum teres
2 Gallbladder and cystic artery
3 Common hepatic duct and portal vein
4 Cystic duct
5 Right gastric artery (pylorus with superior part of duodenum, cut and reflected)
6 Gastroduodenal artery
7 Common bile duct
8 Probe within the minor duodenal papilla
9 Accessory pancreatic duct
10 Probe within the major duodenal papilla
11 Descending part of duodenum (opened)
12 Middle colic artery and inferior pancreaticoduodenal artery
13 Horizontal part of duodenum (distended)
14 Superior mesenteric artery
15 Liver (left lobe)
16 Caudate lobe of liver and hepatic artery proper
17 Abdominal part of esophagus (cut)
18 Probe in epiploic foramen and lymph node
19 Left gastric artery
20 Spleen
21 Splenic vein and branches of splenic artery
22 Main pancreatic duct and head of pancreas
23 Left colic flexure and tail of pancreas
24 Duodenojejunal flexure

Posterior Abdominal Wall: Root of the Mesentery and Peritoneal Recesses



Abdominal cavity after removal of stomach, jejunum, ileum, and part of the transverse colon. The liver has been slightly raised.



Peritoneal reflections from organs and the position of root of mesentery and peritoneal recesses on the posterior abdominal wall.
Arrows: position of peritoneal recesses.

1 Liver
2 Falciform ligament
3 Hepatoduodenal ligament
4 Pylorus (divided)
5 Gallbladder
6 Probe within the epiploic foramen
7 Duodenojejunal flexure (divided)
8 Greater omentum
9 Root of mesentery
10 Ascending colon
11 Free colic taenia
12 End of ileum (divided)
13 Vermiform appendix with meso-appendix
14 Cecum
15 Pancreas and site of lesser sac
16 Diaphragm
17 Spleen
18 Cardia (part of stomach, divided)
19 Head of pancreas
20 Body and tail of pancreas
21 Transverse mesocolon
22 Transverse colon (divided)
23 Descending colon
24 Cut edge of mesentery
25 Sigmoid colon
26 Rectum
27 Attachment of bare area of liver
28 Inferior vena cava
29 Kidney
30 Attachment of right colic flexure
31 Root of transverse mesocolon
32 Junction between descending and horizontal parts of duodenum
33 Bare surface for ascending colon
34 Ileocecal recess
35 Retrocecal recess
36 Root of meso-appendix
37 Superior recess
38 Isthmus (opening) } of lesser sac (omental bursa)
39 Splenic recess
40 Superior duodenal recess
41 Inferior duodenal recess
42 Bare surface for descending colon
43 Paracolic recesses
44 Root of mesentery
45 Root of mesosigmoid
46 Intersigmoid recess
47 Hepatic veins
48 Duodenojejunal flexure
49 Attachment of left colic flexure
50 Esophagus
51 Entrance to lesser sac through the epiploic foramen (arrow)


16
47
28
27
6
4
29
32
31
33
34
36
18
37
17
38
39
20
31
48
29
49
44
42
45
46
26

Peritoneal recesses on the posterior abdominal wall. The liver, stomach, jejunum, ileum, and colon have been removed. The duodenum, pancreas, and spleen have been left in place. Arrows: position of peritoneal recesses.



Horizontal section through the abdominal cavity. Section 1 (from below).

1 Rectus abdominis muscle
2 Falciform ligament
3 Liver (right lobe)
4 Inferior vena cava
5 Diaphragm
6 Intervertebral disc
7 Liver (left lobe)
8 Rib
9 Liver (caudate lobe)
10 Abdominal (descending) aorta
11 Stomach
12 Spleen
13 Spinal cord
14 Longissimus thoracis and iliocostalis muscles
15 Rectus abdominis muscle
16 External abdominal oblique muscle
17 Transverse colon
18 Head of pancreas
19 Major duodenal papilla
20 Duodenum
21 Suprarenal gland and ureter
22 Kidney
23 Body of vertebra
24 Round ligament of liver
25 Small intestine
26 Superior mesenteric artery and vein
27 Psoas major muscle
28 Descending colon
29 Quadratus lumborum muscle
30 Cauda equina



Horizontal section through the abdominal cavity at the level of major duodenal papilla. Section 2 (from below).



Horizontal section through the abdominal cavity. Section 3 (from below).

112897_S_318_332_Kap_5:_ 06.11.2014 9:58 Uhr Seite 331

31 Ileocecal valve
32 Cecum
33 Common iliac artery and vein
34 Gluteus medius muscle
35 Vertebral canal and dura mater
36 Iliacus muscle
37 Ilium
38 Right renal vein
39 Common iliac arteries
40 Spinous process
41 Internal abdominal oblique muscle
42 Transverse abdominal muscle
43 Longissimus muscle



Horizontal section through the abdominal cavity at the level of section 1 (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Horizontal section through the abdominal cavity at the level of section 2 (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Horizontal section through the abdominal cavity. Levels of the sections are indicated.



Horizontal section through the abdominal cavity at the level of section 3 (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Midsagittal section through the female trunk.



Midsagittal section through the female trunk.
Blue = lesser sac (omental bursa); green = peritoneum.

1 Sternum
2 Right ventricle of heart
3 Diaphragm
4 Liver
5 Stomach
6 Transverse mesocolon
7 Transverse colon
8 Umbilicus
9 Mesentery
10 Small intestine
11 Uterus
12 Urinary bladder
13 Pubic symphysis
14 Left atrium of heart
15 Caudate lobe of liver
16 Lesser sac (omental bursa)
17 Conus medullaris
18 Pancreas
19 Cauda equina
20 Intervertebral discs (lumbar vertebral column)
21 Sacral promontory
22 Sigmoid colon
23 Anal canal
24 Anus
25 Lesser omentum
26 Greater omentum
27 Vesico-uterine pouch
28 Urethra
29 Epiploic (omental) foramen
30 Duodenum
31 Rectum
32 Recto-uterine pouch
33 Vaginal part of cervix of uterus
34 Vagina

6 Retroperitoneal Organs

Position of the Urinary Organs 334
Kidney 336
Retroperitoneal Region 340
Male Urogenital System 348
Male Genital Organs (isolated) 350
Male External Genital Organs 352
Male Internal Genital Organs 355
Pelvic Cavity in the Male 357
Urogenital and Anal Regions in the Male 362
Female Urogenital System 366
Female Genital Organs (isolated) 368
Female Internal Genital Organs 370
Female External Genital Organs 373
Inguinal Region and Female External Genital Organs 374
Urogenital and Anal Regions in the Female 375
Pelvic Cavity in the Female 378





1 Kidney
2 Ureter
3 Inferior vena cava
4 Abdominal aorta
5 Ovary
6 Uterine tube
7 Uterus
8 Round ligament of uterus and inguinal canal
9 Urinary bladder

Retroperitoneal organs of the female in situ (anterior aspect). View of the female pelvis showing uterus with uterine ligaments, ovary, and urinary bladder.



1 Pyloric antrum
2 Gastroduodenal artery
3 Descending part of duodenum
4 Vestibule of lesser sac
5 Inferior vena cava and liver
6 Body of first lumbar vertebra
7 Cauda equina
8 Right kidney
9 Latissimus dorsi muscle
10 Iliocostalis muscle
11 Rectus abdominis muscle
12 Stomach
13 Lesser sac
14 Splenic vein
15 Superior mesenteric artery
16 Pancreas
17 Aorta and left renal artery
18 Transverse colon
19 Renal artery and vein
20 Spleen
21 Left kidney
22 Psoas major muscle
23 Multifidus muscle

Horizontal section through the abdominal cavity at the level of the first lumbar vertebra (from below).



Parasagittal section through thoracic and abdominal cavities at the level of the left kidney 5.5 cm left to median plane.



Positions of urinary organs (posterior aspect). Notice that the upper part of the kidney reaches the level of the margin of pleura and lung.

1 Anterior, middle, and posterior scalene muscles
2 Left subclavian artery
3 Left subclavian vein
4 Pulmonic valve
5 Arterial cone
6 Right ventricle of heart
7 Liver
8 Stomach
9 Transverse colon
10 Small intestine
11 Left lung
12 Left main bronchus
13 Branches of pulmonary vein
14 Left ventricle of heart
15 Spleen
16 Splenic artery and vein, and pancreas
17 Left kidney
18 Psoas major muscle
19 Margin of lung
20 Margin of pleura
21 Renal pelvis
22 Left ureter
23 Descending colon
24 Rectum
25 Suprarenal gland
26 Twelfth rib
27 Pancreas
28 Right kidney
29 Ascending colon
30 Right ureter
31 Cecum
32 Vermiform appendix
33 Urinary bladder
34 Inferior vena cava
35 Body of lumbal vertebra (L_1)
36 Iliocostal muscle
37 Superior mesenteric artery
38 Abdominal aorta



Horizontal section through the abdominal cavity (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Coronal section through right kidney and suprarenal gland (posterior aspect). The renal pelvis has been opened and the fatty tissue removed to display the renal vessels.

1	Renal vein
2	Renal artery
3	Renal pelvis
4	Abdominal part of ureter
5	Major renal calyx
6	Cribriform area of renal papilla
7	Cortex of suprarenal gland
8	Medulla of suprarenal gland
9	Cortex of kidney
10	Medulla of kidney
11	Renal papilla
12	Minor renal calyx
13	Renal sinus
14	Renal columns
15	Fibrous capsule of kidney

Each kidney can be divided into five segments supplied by individual interlobar arteries known as end arteries. Thus, obstruction leads to infarcts marking the trace of segment borders. The anterior kidney surface reveals four segments; the posterior, only three (1, 4, and 5).



Right kidney (posterior aspect). Partial coronal section to expose internal aspect of the kidney.



Cast of renal pelvis and calices.
1–4 = Renal segments on anterior surface.

1	Hepatic vein
2	Anterior and posterior vagal trunk
3	Inferior vena cava
4	Lumbar part of diaphragm
5	Right greater and lesser splanchnic nerves
6	Celiac trunk
7	Celiac ganglion and plexus
8	Superior mesenteric artery
9	Left renal vein
10	Right sympathetic trunk and ganglion
11	Abdominal aorta
12	Left sympathetic trunk
13	Esophagus (cut) and left greater splanchnic nerve
14	Left suprarenal gland
15	Left renal artery
16	Renal pelvis
17	Renal papilla with minor calyx
18	Left testicular vein
19	Ureter
20	Psoas major muscle
21	Quadratus lumborum muscle
22	Lumbar vertebra (L_2)
23	Renal calyx
24	Catheter



Left kidney and suprarenal gland in situ. The anterior cortical layer of the kidney has been removed to display the renal pelvis and papillae.



Renal pelvis with calices and ureter (X-ray, retrograde injection). (Courtesy of Prof. Herrlinger, Fürth, Germany.)



Right kidney (ultrasound image). (Courtesy of Prof. Herrlinger, Fürth, Germany.)



Subtraction angiography of the abdominal aorta with renal artery and renal vessels.

1 Celiac trunk
2 Superior mesenteric artery
3 Middle colic artery
4 Abdominal aorta (with catheter in the figure below)
5 Splenic artery
6 Upper pole of kidney
7 Anterior branch of renal artery
8 Interlobular arteries
9 Renal artery
10 Lower pole of kidney
11 Common iliac artery
12 Posterior branch of renal artery
13 Anterior superior segmental artery of renal artery
14 Superior suprarenal artery
15 Upper capsular artery
16 Perforating artery
17 Lower capsular artery
18 Ureter
19 Right inferior phrenic artery
20 Left inferior phrenic artery
21 Middle suprarenal artery
22 Inferior suprarenal artery
23 Anterior segmental artery of renal artery
24 Left testicular (or ovarian) artery
25 Inferior mesenteric artery



Arteriography of the abdominal aorta with renal arteries and renal vessels. (Courtesy of Dr. Wieners, Dept. of Radiology, Berlin, Germany.)



Arteries of kidney and suprarenal gland.

1 Diaphragm
2 Hepatic veins
3 Inferior vena cava
4 Common hepatic artery
5 Suprarenal gland
6 Celiac trunk
7 Right renal vein
8 Kidney
9 Abdominal aorta
10 Subcostal nerve
11 Iliohypogastric nerve
12 Central tendon of diaphragm
13 Inferior phrenic artery
14 Cardic part of stomach
15 Spleen
16 Splenic artery
17 Superior renal artery
18 Superior mesenteric artery
19 Psoas major muscle
20 Inferior mesenteric artery
21 Ureter
22 Glomerulus
23 Afferent arteriole of glomerulus
24 Glomeruli
25 Radiating cortical artery
26 Subcortical or arcuate artery
27 Subcortical or arcuate vein
28 Interlobular vein
29 Interlobular artery
30 Interlobar artery and vein
31 Vessels of renal capsule
32 Efferent arteriole of glomerulus
33 Vasa recta of renal medulla
34 Spiral arteries of renal pelvis



Retroperitoneal organs, kidneys, and suprarenal glands in situ (anterior aspect). Red = arteries; blue = veins.



Scanning electron micrograph showing glomeruli and associated arteries (magn. 210 ×).



Architecture of the vascular system of the kidney.



Retroperitoneal organs, urinary system in the male (anterior aspect). The peritoneum has been removed.

1	Costal arch
2	Right renal vein
3	Right kidney
4	Inferior vena cava
5	Iliohypogastric nerve and quadratus lumborum muscle
6	Ureter (abdominal part)
7	Psoas major muscle and genitofemoral nerve
8	Iliacus muscle
9	External iliac artery
10	Ureter (pelvic part)
11	Ductus deferens
12	Testis and epididymis
13	Celiac trunk
14	Superior mesenteric artery
15	Left kidney
16	Abdominal aorta
17	Inferior mesenteric artery
18	Common iliac artery
19	Iliac crest
20	Sacral promontory
21	Rectum (cut)
22	Medial umbilical ligament
23	Urinary bladder
24	Penis



Retroperitoneal organs, urinary system in the male (anterior aspect). The peritoneum has been removed. Note the autonomic plexus and ganglia at the abdominal aorta.

1	Diaphragm
2	Inferior vena cava
3	Suprarenal gland
4	Kidney
5	Superior mesenteric artery
6	Ureter
7	Right spermatic vein
8	Psoas major muscle
9	Spleen
10	Cardiac part of stomach
11	Abdominal aorta
12	Splenic artery
13	Celiac trunk and celiac ganglion
14	Renal artery and vein
15	Left spermatic vein
16	Ilio-inguinal nerve
17	Superior hypogastric plexus and ganglion
18	Left common iliac artery
19	Sigmoid colon

112897_S_333_361_Kap_6:_ 06.11.2014 10:35 Uhr Seite 342



Lymph vessels and lymph nodes of the posterior wall of thoracic and abdominal cavities (anterior aspect). Green = lymph vessels and nodes; blue = veins; red = arteries; white = nerves.

1	Internal jugular vein
2	Right common carotid artery and right vagus nerve
3	Jugulo-omohyoid lymph node
4	Right lymphatic duct
5	Subclavian trunk
6	Right subclavian vein
7	Bronchomediastinal trunk
8	Azygos vein
9	Diaphragm
10	Right kidney
11	Right lumbar trunk
12	Right ureter
13	Common iliac lymph nodes
14	Right internal iliac artery
15	External iliac lymph nodes
16	Right external iliac artery
17	Left common carotid artery and left vagus nerve
18	Internal jugular vein
19	Deep cervical lymph nodes
20	Thoracic duct entering left jugular angle
21	Left subclavian vein
22	Left brachiocephalic vein
23	Thoracic duct
24	Mediastinal lymph nodes
25	Thoracic aorta
26	Left suprarenal gland
27	Left renal artery
28	Left kidney
29	Cisterna chyli
30	Lumbar lymph nodes
31	Abdominal aorta
32	Left ureter
33	Sacral lymph nodes
34	Rectum (cut edge)
35	Aortic arch
36	Superior vena cava
37	Intercostal vein
38	Left jugular trunk
39	Left subclavian artery
40	Quadratus lumborum muscle
41	Psoas major muscle
42	Parotid lymph nodes
43	Axillary lymph nodes


42
38
20
4
21
22
36
43
23

Lymph vessels and lymph nodes of the upper part of the body. Dotted red line = border between irrigation areas of the right and left part of the body.


1
2
4
18
38
20
21
39
35
22
36
8
23
37
9
9
29
30
40
41
33
14
34

Lymph vessels and lymph nodes of the posterior wall of thoracic and abdominal cavities (anterior aspect). Note the course of the thoracic duct from the cisterna chyli to the left venous angle. The lymph vessels of the intercostal spaces communicate mainly with the thoracic duct.



Arteriography of the abdominal aorta. The distal portion of the aorta reveals sclerotic changes. (Courtesy of Dr. Wieners, Dept. of Radiology, Berlin, Germany.)

1 Abdominal aorta (containing partly the catheter)
2 Superior suprarenal artery
3 Hepatic artery
4 Superior mesenteric artery
5 Lumbal arteries
6 Common iliac artery (with catheter)
7 Splenic artery
8 Abdominal aorta (partly sclerotized)
9 Left colic artery
10 Inferior mesenteric artery
11 Inferior phrenic arteries
12 Middle suprarenal artery
13 Right colic artery
14 Ileocolic artery
15 Sigmoid arteries
16 Superior rectal artery



Course of the superior and inferior mesenteric arteries within the retroperitoneal space supplying the ascending and descending parts of the colon (anterior aspect).



Vessels and nerves within the retroperitoneal space (anterior aspect). Part of the left psoas major muscle has been removed to display the lumbar plexus. Red = arteries; blue = veins.

1 Diaphragm
2 Hepatic veins
3 Inferior vena cava
4 Inferior phrenic artery
5 Right renal vein
6 Iliohypogastric nerve
7 Quadratus lumborum muscle
8 Subcostal nerve
9 Inferior mesenteric artery
10 Right genitofemoral nerve and psoas major muscle
11 Common iliac artery
12 Iliacus muscle
13 Right ureter (divided)
14 Lateral femoral cutaneous nerve
15 Internal iliac artery
16 Femoral nerve
17 External iliac artery
18 Inferior epigastric artery
19 Cardiac part of stomach and esophageal branches of left gastric artery
20 Splenic artery
21 Celiac trunk
22 Superior mesenteric artery
23 Left renal artery
24 Ilio-inguinal nerve
25 Sympathetic trunk
26 Transverse abdominal muscle
27 Iliac crest
28 Left genitofemoral nerve
29 Left obturator nerve
30 Median sacral artery
31 Psoas major muscle (divided) with supplying artery
32 Rectum (cut)
33 Urinary bladder


1
2
3
4
5
7
6
8
9
6
10
5
11
12
13
14
15
16
17
18
17
19
20
21
22
23
24
25
26

Posterior wall of thoracic and abdominal cavities with sympathetic trunk, vagus nerve, and autonomic ganglia (anterior aspect). Thoracic and abdominal organs removed, except for the esophagus and aorta.


1
27
28
29
30
31
5
7
6
32
33
34
35
14
36
4
17
19
5
14
9
37
10
25
13
35
38

Organization of autonomic nervous system.
Yellow = parasympathetic nerves;
green = sympathetic nerves.



Ganglia and plexus of the autonomic nervous system within the retroperitoneal space (anterior aspect). The kidneys and the inferior vena cava with its tributaries have been removed.

1 Right vagus nerve
2 Right subclavian artery
3 Esophagus
4 Aortic arch
5 Sympathetic trunk
6 Greater splanchnic nerve
7 Intercostal nerve
8 Abdominal part of esophagus and vagal trunk
9 Celiac trunk with celiac ganglion
10 Superior mesenteric artery and ganglion
11 Psoas major muscle and genitofemoral nerve
12 Common iliac artery
13 Superior hypogastric plexus and ganglion
14 Left vagus nerve
15 Brachial plexus
16 Left subclavian artery
17 Left recurrent laryngeal nerve
18 Inferior cervical cardiac nerve
19 Thoracic aorta
20 Esophageal plexus
21 Azygos vein
22 Diaphragm
23 Splenic artery
24 Left renal artery and plexus
25 Inferior mesenteric ganglion and artery
26 Left external iliac artery
27 Superior cervical ganglion of sympathetic trunk
28 Superior cardiac branch of sympathetic trunk
29 Middle cervical ganglion of sympathetic trunk
30 Inferior cervical ganglion of sympathetic trunk
31 Right recurrent laryngeal nerve
32 Lesser splanchnic nerve
33 Lumbar splanchnic nerves
34 Sacral splanchnic nerves
35 Inferior hypogastric ganglion and plexus
36 Left recurrent laryngeal nerve
37 Aorticorenal plexus and renal artery
38 Ganglion impar
39 Esophagus with branches of vagus nerve
40 Hepatic veins
41 Right crus of diaphragm
42 Inferior phrenic artery
43 Right vagus nerve entering the celiac ganglion
44 Right lumbar lymph trunk
45 Lumbar part of right sympathetic trunk
46 Lumbar artery and vein
47 Psoas major muscle
48 Iliac crest
49 Inferior vena cava
50 Iliacus muscle
51 Ureter
52 Left vagus nerve forming the esophageal plexus
53 Left vagus nerve forming the gastric plexus
54 Esophagus continuing into the cardiac part of stomach
55 Lumbocostal triangle
56 Position of twelfth rib
57 Left lumbar lymph trunk
58 Ganglion of sympathetic trunk
59 Quadratus lumborum muscle
60 Lumbar part of left sympathetic trunk
61 Iliac lymph vessels



Male urogenital system (midsagittal section through the pelvic cavity).

1	Sigmoid colon
2	Ampulla of rectum
3	Ampulla of ductus deferens
4	External anal sphincter muscle
5	Internal anal sphincter muscle
6	Anal canal
7	Bulb of penis
8	Testis (cut surface)
9	Median umbilical ligament
10	Urinary bladder
11	Internal urethral orifice and sphincter
12	Pubic symphysis
13	Prostatic part of urethra
14	Prostate gland
15	Membranous part of urethra and external urethral sphincter
16	Corpus cavernosum of penis
17	Spongy urethra
18	Corpus spongiosum of penis
19	Foreskin or prepuce
20	Glans penis
21	Kidney
22	Renal pelvis
23	Abdominal part of ureter
24	Pelvic part of ureter
25	Seminal vesicle
26	Ejaculatory duct
27	Bulbo-urethral gland (Cowper's gland)
28	Ductus deferens
29	Epididymis
30	Umbilicus
31	Trigone of urinary bladder and ureteric orifice
32	Navicular fossa of urethra
33	External urethral orifice
34	Testis
35	Sacrum



Male urogenital system (lateral aspect).



Midsagittal section through the pelvic cavity in the male (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15

Male genital organs, isolated (right lateral aspect).


1
2
16
3
17
18
6
10
12
19
13
14
8
9
15

Male genital organs in situ (right lateral aspect).


20
21
22
16
12
1
23
2
24
3
4
17
5
6
8
9
25
26
27
11
10
28
29
13
14
12
30
15

Positions of male genital organs (right lateral aspect).

1	Ureter
2	Seminal vesicle
3	Prostate gland
4	Urogenital diaphragm and membranous part of urethra
5	Bulbo-urethral gland (Cowper's gland)
6	Bulb of penis
7	Left and right crus penis
8	Epididymis
9	Testis
10	Urinary bladder
11	Apex of urinary bladder
12	Ductus deferens
13	Corpus cavernosum of penis
14	Corpus spongiosum of penis
15	Glans penis
16	Ampulla of rectum
17	Levator ani muscle
18	Anal canal and external anal sphincter muscle
19	Spermatic cord (cut)
20	Sacral promontory
21	Sigmoid colon
22	Peritoneum (cut edge)
23	Rectovesical pouch
24	Ejaculatory duct
25	Lateral umbilical fold
26	Medial umbilical fold
27	Deep inguinal ring and ductus deferens
28	Pubic symphysis
29	Prostatic part of urethra
30	Spongy urethra



Male genital organs and urinary bladder, isolated (anterior aspect). Urinary bladder, prostate, and urethra have been opened. The urinary bladder is contracted.

1 Ureter
2 Ductus deferens
3 Interureteric fold
4 Ureteric orifice
5 Seminal vesicle
6 Trigone of urinary bladder
7 Prostatic urethra with seminal colliculus and urethral crest
8 Deep transverse perineal muscle
9 Membranous urethra
10 Spongy urethra
11 Mucous membrane of urinary bladder
12 Internal urethral orifice and uvula of urinary bladder
13 Prostate
14 Prostatic utricle
15 Right and left corpus cavernosum of penis
16 Ejaculatory duct
17 Sphincter urethrae muscle
18 Sphincter muscle of urinary bladder
19 Bulbo-urethral gland (Cowper's gland)
20 Crus penis
21 Orifices of bulbo-urethral glands
22 Glans penis
23 Ureteric orifices



Posterior half of male urethra and prostate in continuity with the neck of urinary bladder (anterior aspect).



Male genital organs and urinary bladder (anterior aspect). Urinary bladder, urethra, and penis have been dissected.



Male genital organs and urinary bladder, isolated (posterior aspect).

1 Apex of urinary bladder with urachus
2 Urinary bladder
3 Ureter
4 Ductus deferens
5 Ampulla of ductus deferens
6 Seminal vesicle
7 Prostate
8 Bulbo-urethral gland (Cowper's gland)
9 Bulb of penis
10 Crus penis
11 Corpus spongiosum of penis
12 Corpus cavernosum of penis
13 Testis and epididymis with coverings
14 Glans penis
15 Fundus of urinary bladder
16 Head of epididymis
17 Testis
18 Mucous membrane of bladder
19 Trigone of bladder
20 Ureteric orifice
21 Internal urethral orifice
22 Seminal colliculus
23 Prostate
24 Prostatic urethra
25 Membranous urethra
26 Spongy (penile) urethra
27 Skin of penis
28 Deep dorsal vein of penis (unpaired)
29 Dorsal artery of penis (paired)
30 Tunica albuginea of corpora cavernosa
31 Septum of penis
32 Deep artery of penis
33 Tunica albuginea of corpus spongiosum
34 Deep fascia of penis



Urinary bladder, urethra, and penis (anterior aspect, opened longitudinally).



Cross section through the penis (inferior aspect).


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16

Male external genital organs with penis, testis, and spermatic cord, superficial layer (anterior aspect).


17
18
19
20
13
21
22
16
23
A
24
25
26
27
28
29
30
31
32
33
34
15
19
20
34
30
35
B

Vessels of male genital organs.
A = lateral aspect; B = cross section through the penis.

1	Femoral nerve
2	Femoral artery and vein
3	Femoral branch of genitofemoral nerve
4	Spermatic cord with genital branch of genitofemoral nerve
5	Penis with deep fascia
6	Great saphenous vein
7	Cremaster muscle
8	Testis with cremaster muscle
9	Superficial inguinal ring
10	Internal spermatic fascia (cut edge)
11	Ilio-inguinal nerve
12	Left spermatic cord
13	Pampiniform venous plexus
14	External spermatic fascia
15	Superficial dorsal vein of penis



Male external genital organs with penis, testis, and spermatic cord, deeper layer (anterior aspect). The deep fascia of the penis has been opened to display the dorsal nerves and vessels.

16	Glans penis
17	Testicular vein
18	Testicular artery
19	Deep dorsal vein of penis
20	Dorsal artery of penis
21	Helicine arteries
22	Prepuce
23	Testis with tunica albuginea
24	Ductus deferens
25	Ureter
26	Urinary bladder
27	Seminal vesicle
28	Prostate
29	Vesicoprostatic venous plexus
30	Deep artery of penis
31	Artery of bulb of penis
32	Internal pudendal artery
33	Corpus spongiosum of penis
34	Corpus cavernosum of penis
35	Urethra
36	Cremasteric fascia with cremaster muscle
37	Dorsal nerve of penis
38	Epididymis
39	Tunica vaginalis (visceral layer)
40	Tunica vaginalis (parietal layer)
41	Inguinal ligament
42	Femoral cutaneous nerve
43	Deep inguinal ring
44	Ductus deferens and testicular artery
45	Hiatus saphenous
46	Epididymis



Male external genital organs and inguinal region (anterior aspect). Dissection of the inguinal channel.



Male external genital organs (oblique-lateral aspect). The corpus spongiosum of the penis with the glans penis has been isolated and reflected.



Sagittal section through the pelvic cavity with the male genital organs (MRI scan). (From Heuck et al., MRT-Atlas, 2009.)



Resin cast of an erected penis.



Male external genital organs and accessory glands.

1	Corpus cavernosum of penis
2	Corpus spongiosum of penis
3	Corona of glans penis
4	Glans penis
5	Suspensory ligament of penis
6	Pubis (inferior pubic ramus, dissected)
7	Crus penis
8	Bulb of penis
9	Dorsal vein of penis
10	Septum pectiniforme
11	Dorsal artery of penis
12	Bulbo-urethral gland (Cowper's gland)
13	Urinary bladder
14	Seminal vesicle
15	Ampulla of ductus deferens
16	Ductus deferens
17	Membranous urethra
18	Prostate
19	Ureter
20	Common iliac artery and vein
21	Fifth lumbar vertebral body
22	Intestinal loops
23	Rectus abdominis muscle
24	Pubic symphysis
25	Root of penis
26	Sacrum
27	Ampulla of rectum
28	Anal canal
29	External anal sphincter muscle



Testis and epididymis with investing layers (lateral aspect).



Testis and epididymis (lateral aspect). The tunica vaginalis has been opened.



Testis, epididymis, and spermatic cord (left side, postero-lateral aspect)**.** Dissection of spermatic cord and ductus deferens.

1 Spermatic cord
covered with cremasteric fascia
2 Cremaster muscle
3 Position of epididymis
4 Internal spermatic fascia
5 Position of testis
6 Internal spermatic fascia
with adjacent investing layers of testis
(cut surface)
7 Head of epididymis
8 Testis with tunica vaginalis (visceral layer)
9 Body of epididymis
10 Pampiniform venous plexus
(anterior veins)
11 Testicular artery
12 Tunica vaginalis (parietal layer, cut edge)
13 Skin and dartos muscle (reflected)
14 Ductus deferens
15 Artery of ductus deferens
16 Posterior veins of pampiniform plexus
17 Tail of epididymis
18 Transition of epididymal duct
to ductus deferens and venous plexus
19 Parietal layer of tunica vaginalis
20 Appendix of epididymis
21 Appendix of testis
22 Gubernaculum testis



Longitudinal section through testis and epididymis. The left figure shows the testicular septa after removal of the seminiferous tubules.

1 Spermatic cord (cut surface)
2 Head of epididymis (cut surface)
3 Septa of testis
4 Mediastinum testis
5 Tunica albuginea
6 Superior pole of testis
7 Convoluted seminiferous tubules
8 Inferior pole of testis



Accessory glands of male genital organs. Coronal section through the pelvic cavity. Posterior aspect of urinary bladder, prostate, and seminal vesicles.

1	Ureter
2	Ductus deferens
3	Seminal vesicle
4	Ampulla of ductus deferens
5	Ejaculatory duct (proximal portion)
6	Prostate
7	Membranous urethra
8	Bulbo-urethral gland (Cowper's gland)
9	Bulb of penis
10	Penis
11	Glans penis
12	Urinary bladder
13	Levator ani muscle
14	Obturator internus muscle
15	Pelvic bone (cut edge)
16	Puboprostatic ligament
17	Corpus spongiosum of penis
18	Head of epididymis
19	Beginning of ductus deferens
20	Testis
21	Tail of epididymis
22	Corpus cavernosum of penis
23	Spermatic cord
24	Pectineus and adductor muscles
25	Pubis
26	Prostatic part of urethra (seminal colliculus)
27	Rectum
28	Sciatic nerve
29	Great saphenous vein
30	Sartorius muscle
31	Femoral artery and vein
32	Rectus femoris muscle
33	Tensor fasciae latae muscle
34	Pectineus muscle
35	Iliopsoas muscle
36	Vastus lateralis muscle
37	Obturator externus muscle
38	Femur
39	Ischial tuberosity
40	Gluteus maximus muscle



Horizontal section through the pelvic cavity in the male at the level of prostate.



Coronal section through the pelvic cavity in the male at the level of prostate and hip joint (anterior aspect).

1 Acetabulum of hip joint
2 Urinary bladder
3 Head of femur
4 Internal urethral orifice
5 Prostate
6 Seminal colliculus
7 Obturator internus muscle
8 Ischiorectal fossa
9 Membranous urethra
10 Deep transverse perineal muscle
11 Crus penis and ischiocavernosus muscle
12 Prostatic part of urethra
13 Prostatic plexus
14 Levator ani muscle
15 Obturator externus muscle
16 Bulb of penis
17 Median umbilical fold with remnant of urachus
18 Rectovesical pouch
19 Rectum
20 Sacrum
21 Inferior epigastric artery
22 Medial umbilical fold with remnant of umbilical artery
23 Deep inguinal ring and ductus deferens
24 Deep iliac circumflex artery
25 External iliac artery and vein
26 Femoral nerve
27 Iliopsoas muscle
28 Ureter
29 Obturator nerve and internal iliac artery
30 Ilium and sacrum



Coronal section through the pelvic cavity in the male (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Pelvic cavity in the male (from above).

112897_S_333_361_Kap_6:_ 06.11.2014 10:36 Uhr Seite 358



Vessels of the pelvic cavity in the male (right half, parasagittal section). The arteries have been injected with red resin. The parietal layer of peritoneum has been removed. The urinary bladder is filled to a great extent.

1 Left common iliac artery
2 Right common iliac artery
3 Right ureter
4 Right internal iliac artery
5 Right external iliac artery and vein
6 Right obturator artery and nerve
7 Umbilical artery
8 Sigmoid and superior vesical artery
9 Left ductus deferens
10 Urinary bladder
11 Pubis (cut)
12 Prostate
13 Vesicoprostatic venous plexus
14 Deep dorsal vein of penis and dorsal artery of penis
15 Penis and superficial dorsal vein
16 Spermatic cord and testicular artery
17 Bulb of penis and deep artery of penis
18 Cauda equina and dura mater (divided)
19 Intervertebral disc between fifth lumbar vertebra and sacrum
20 Sacral promontory
21 Mesosigmoid
22 Left ureter
23 Left internal pudendal artery
24 Ischial spine (cut), sacrospinal ligament, and inferior gluteal artery
25 Left inferior vesical artery
26 Seminal vesicle
27 Levator ani muscle
28 Branches of inferior rectal artery
29 Perineal artery
30 Anus
31 Posterior scrotal branches
32 Pudendal nerve and sacrotuberal ligament



Vessels of the pelvic cavity in the male (medial aspect, midsagittal section). The gluteus maximus muscle has been removed.

1	Internal iliac artery
2	External iliac artery
3	Ureter
4	Obturator nerve
5	Umbilical artery
6	Deep inguinal ring
7	Urinary bladder (vesica urinaria)
8	Symphysis
9	Prostatic part of urethra
10	Sphincter muscle of urethra
11	Urethra (spongy part)
12	Cavernous body of penis
13	Glans penis
14	Sacrum
15	Promontory
16	Lateral sacral artery
17	Plexus sacralis
18	Inferior gluteal artery
19	Internal pudendal artery
20	Obturator artery
21	Inferior hypogastric plexus
22	Ductus deferens
23	Seminal vesicle (vesicula seminalis)
24	Rectum
25	Prostatic venous plexus
26	Prostate
27	Anal canal
28	Spongy part of penis
29	Pampiniform plexus
30	Testis and epididymis
31	Common iliac artery
32	Umbilical artery
33	Medial umbilical ligament
34	Branches of superior vesical artery
35	Urogenital diaphragm
36	Deep artery of penis
37	Dorsal artery of penis
38	Penis
39	Iliolumbar artery
40	Superior gluteal artery
41	Middle rectal artery
42	Levator ani muscle
43	Inferior rectal artery
44	Inferior vesical artery
45	Testicular artery
46	Artery of bulb of penis
47	Septum of penis



Main branches of internal iliac artery in the male (lateral aspect).



Arteriography of male genital organs (lateral aspect). Arrow: helicine artery.



1 Twelfth thoracic vertebra (Th_{12})
2 Twelfth rib (rib XII)
3 Inferior mesenteric artery
4 Fourth lumbar vertebra (L_4)
5 Sacrum
6 Sacro-iliac articulation
7 Aorta (abdominal part)
8 Left common iliac artery (included into the aneurysm)
9 Aorta with aneurysm
10 Body of lumbar vertebra
11 Intrinsic muscles of the back
12 Thrombotic part of the aneurysm (green)
13 Inferior vena cava (compressed, blue)
14 Iliopsoas muscle
15 Vertebral canal
16 Aneurysm of the aorta (red)

Abdominal part of the aorta showing an infrarenal aneurysm with involvement of both iliac arteries (arrows; 3-D reconstruction). (Courtesy of Prof. Rupprecht and Dr. Rexer, Klinikum Fürth, Germany.)



Abdominal part of the aorta with an aneurysm, after injection of contrast medium. Above = horizontal sections through the abdominal cavity, showing different contrast medium concentrations within the aorta and the aneurysm; below = 3-D reconstruction of the aneurysm; red = aorta; green = thrombotic areas; blue = inferior vena cava (partly compressed).



Vessels and nerves of the pelvic cavity in the male (medial aspect, midsagittal section). The rectum was reflected to display the inferior hypogastric plexus.

1 External iliac artery
2 Right hypogastric nerve
3 Ureter
4 Internal iliac artery
5 Inferior gluteal artery and internal pudendal artery
6 Obturator artery
7 Urinary bladder
8 Ductus deferens
9 Symphysis pubica
10 Prostatic part of urethra
11 Prostatic venous plexus
12 Sphincter urethrae muscle
13 Spongy part of urethra
14 Corpus spongiosum penis
15 Corpus cavernosum penis
16 Glans penis
17 Sacrum
18 Lateral sacral artery
19 Sacral plexus
20 Pelvic splanchnic nerves (nervi erigentes)
21 Levator ani muscle
22 Inferior hypogastric plexus (pelvic plexus)
23 Prostate
24 Rectum (reflected)
25 Anal canal and external anal sphincter muscle
26 Pampiniform plexus continuous with testicular vein
27 Testis and epididymis



Urogenital diaphragm and external genital organs in the male with muscles of the pelvic floor (from below).

1 Glans penis
2 Corpus spongiosum of penis
3 Corpus cavernosum of penis
4 Gracilis muscle
5 Adductor muscles
6 Ischiocavernosus muscle overlying crus of penis
7 Perineal body
8 Gluteus maximus muscle
9 Coccyx
10 Bulbospongiosus muscle
11 Deep transverse perineus muscle covered by inferior fascia of urogenital diaphragm
12 Superficial transverse perineus muscle
13 Anus
14 External anal sphincter muscle
15 Levator ani muscle
16 Anococcygeal ligament
17 Testis
18 Urethra
19 Deep dorsal vein of penis
20 Dorsal artery of penis
21 Deep transverse perineal muscle
22 Obturator internus muscle
23 Sacrotuberal ligament



Urogenital and anal regions in the male (from below). Muscles of urogenital and pelvic diaphragms.



Urogenital diaphragm and external genital organs in the male with vessels and nerves (from below). The testes have been reflected laterally.

1 Right testis (reflected laterally and upward)
2 Bulbospongiosus muscle
3 Ischiocavernosus muscle
4 Adductor magnus muscle
5 Posterior scrotal nerves and superficial perineal arteries
6 Posterior scrotal artery and vein
7 Right artery of bulb of penis
8 Perineal body
9 Perineal branches of pudendal nerve
10 Pudendal nerve and internal pudendal artery
11 Inferior rectal arteries and nerves
12 Inferior cluneal nerves
13 Coccyx (location)
14 Penis
15 Left testis (reflected laterally)
16 Left posterior scrotal artery
17 Deep transverse perineal muscle
18 Left artery of bulb of penis
19 Branch of posterior femoral cutaneous nerve
20 External anal sphincter muscle
21 Anus
22 Gluteus maximus muscle
23 Anococcygeal nerves
24 Acetabulum (femur removed)
25 Ligament of femoral head
26 Body of ischium (cut)
27 Sciatic nerve
28 Coccygeus muscle
29 Levator ani muscle
  a Iliococcygeus muscle
  b Pubococcygeus muscle
  c Puborectalis muscle
30 Prostatic venous plexus
31 Pubis
32 Testis



Pelvic diaphragm and external genital organs in the male (lateral aspect). The right half of the pelvis including the obturator internus muscle and femur have been removed to display the right half of the levator ani muscle.



Urogenital diaphragm and external genital organs in the male (from below). The left crus penis has been isolated and reflected laterally together with the bulb of the penis. The urethra has been cut.

1 Right testis (reflected)
2 Posterior scrotal nerves
3 Left crus penis with ischiocavernosus muscle
4 Anus
5 Inferior cluneal nerves
6 Penis
7 Left testis (reflected)
8 Dorsal artery and nerve of penis
9 Urethra
10 Deep transverse perineus muscle
11 Perineal branches of pudendal nerve
12 Artery of bulb of penis (reflected)
13 Branch of posterior femoral cutaneous nerve
14 Internal pudendal artery and pudendal nerve
15 Inferior rectal arteries and nerves
16 Gluteus maximus muscle
17 Dorsal nerve of penis
18 Posterior femoral cutaneous nerve
19 Perineal and anal branches of pudendal nerve
20 Pudendal nerve
21 Inferior rectal nerves
22 Bulbospongiosus muscle
23 Ischiocavernosus muscle
24 Dorsal artery of penis
25 Perineal artery
26 External anal sphincter muscle
27 Internal pudendal artery and vein
28 Inferior rectal arteries



Urogenital and anal regions in the male (from below). Right side: nerves; left side: arteries and veins.

1 Right testis (reflected)
2 Corpus spongiosum of penis
3 Corpus cavernosum of penis
4 Perineal branch of posterior femoral cutaneous nerve
5 Posterior scrotal arteries and nerves
6 Deep artery of penis
7 Deep transverse perineal muscle
8 Right perineal nerves
9 Inferior rectal nerves
10 Inferior cluneal nerve
11 Anococcygeal nerves
12 Left spermatic cord
13 Left testis (cut surface)
14 Dorsal artery and nerve of penis
15 Deep dorsal vein of penis
16 Urethra (cut)
17 Artery of bulb of penis
18 Superficial transverse perineus muscle
19 Left artery of bulb of penis
20 Perineal branch of pudendal nerve
21 Anus
22 External anal sphincter muscle
23 Gluteus maximus muscle
24 Obturator fascia with Alcock's canal for pudendal nerve, and internal pudendal artery and vein
25 Sacrotuberous ligament
26 Coccyx
27 Urogenital diaphragm with superficial investing fascia of perineum (perineal fascia)



Urogenital diaphragm and external genital organs in the male (from below). The root of the penis has been cut. Dissection of the urogenital diaphragm.



Urogenital and anal regions in the male (from below). Muscles of urogenital and pelvic diaphragms. Light blue = perineal fascia.



Female urogenital system (midsagittal section through the pelvic cavity). The urinary bladder is empty; the position and shape of the uterus are normal.

1 Umbilicus
2 Duodenum
3 Ascending part of duodenum
4 Root of mesentery
5 Small intestine
6 Mesentery
7 Rectus abdominis muscle
8 Uterus
9 Vesico-uterine pouch
10 Urinary bladder (collapsed)
11 Pubic symphysis
12 Anterior fornix of vagina
13 Urethra
14 Clitoris
15 Labium minus
16 Labium majus
17 Vertebral canal with cauda equina
18 Intervertebral disc
19 Body of fifth lumbar vertebra (L_5)
20 Sacral promontory
21 Mesosigmoid
22 Sigmoid colon
23 Recto-uterine pouch (of Douglas)
24 Ampulla of rectum
25 Posterior fornix of vagina
26 Cervix of uterus
27 External anal sphincter muscle
28 Anal canal
29 Vagina
30 Internal anal sphincter muscle
31 Anus
32 Hymen
33 Abdominal aorta
34 Discus intervertebralis, promontory
35 Sacrum
36 Rectum



Sagittal section through the pelvic cavity of a young female. The uterus reveals an extreme anteflexion (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Coronal section through the urinary bladder and urethra in the female (anterior aspect).



Position of female genital organs (medial aspect).



Position of kidneys, urinary, and genital organs in the female (anterior aspect). The excursions of the kidneys are indicated.

1	Muscular coat of urinary bladder
2	Folds of mucous membrane of urinary bladder
3	Right ureteric orifice
4	Interureteric fold
5	Internal urethral orifice
6	Vesico-uterine venous plexus
7	Urethra
8	Pubis (cut edge)
9	External urethral orifice
10	Vestibule of vagina
11	Left ureteric orifice
12	Trigone of bladder
13	Obturator internus muscle
14	Levator ani muscle
15	Bulb of vestibule
16	Left labium minus
17	Umbilicus
18	Sigmoid colon
19	Median umbilical fold with urachus
20	Infundibulum of uterine tube
21	Fimbriae of uterine tube
22	Ovary
23	Uterine tube (isthmus)
24	Uterus
25	Round ligament of uterus
26	Vesico-uterine pouch
27	Urinary bladder
28	Vagina
29	Pubic symphysis
30	Clitoris
31	Body of fifth lumbar vertebra (L_5)
32	Sacral promontory
33	Right ureter
34	Peritoneum (cut edge)
35	Left ureter
36	Recto-uterine pouch (of Douglas)
37	Rectal ampulla
38	Kidney

Female Genital Organs (isolated)





Female genital organs, isolated (anterior aspect). The anterior wall of the vagina has been opened to display the vaginal portion of the cervix.



Position of female internal genital organs (oblique-anterior aspect).

1	Ovary
2	Mesovarium
3	Fundus of uterus
4	Vesico-uterine pouch
5	Cervix of uterus
6	Vaginal portion of cervix
7	Vagina
8	Crus of clitoris
9	Labium minus
10	Fimbriae of uterine tube
11	Infundibulum of uterine tube
12	Ligament of the ovary
13	Mesosalpinx
14	Uterine tube
15	Suspensory ligament of ovary (caudally displaced)
16	Broad ligament of uterus
17	Round ligament of uterus
18	Corpus cavernosum of clitoris
19	Glans of clitoris
20	Hymen and vaginal orifice
21	Linea terminalis
22	Urinary bladder
23	Medial umbilical ligament
24	Pubic symphysis
25	Urethra
26	Ureter
27	Promontory

1 Fundus of uterus
2 Uterine tube
3 Ligament of the ovary
4 Ovary
5 Infundibulum of uterine tube
6 Fimbriae of uterine tube
7 Ureter
8 Rectum
9 Apex of urinary bladder and median umbilical ligament
10 Urinary bladder (fenestrated in the dissection in the middle)
11 Round ligament of uterus
12 Mesosalpinx
13 Mesovarium
14 Recto-uterine pouch (of Douglas)
15 Vesico-uterine pouch
16 Body of uterus
17 Cervix of uterus
18 Vaginal portion of cervix of uterus
19 Vagina
20 Mucous membrane of uterus congestion
21 Anterior fornix of vagina



Female genital organs, isolated (supero-posterior aspect).



Uterus and related organs, isolated (superior aspect). The left ovary is enlarged.



Uterus and related organs, isolated (posterior aspect). The posterior wall of the uterus has been opened.



Female internal genital organs. View of the pelvic cavity (superior aspect). The uterus has been reflected to the right.



Pelvic cavity in the female showing uterus and related organs (antero-superior aspect). The peritoneal cover removed on the right side. Arrows: vesico-uterine and recto-uterine pouches.

1	Median umbilical fold with urachus
2	Urinary bladder
3	Insertion of uterine tube at fundus of uterus
4	Round ligament of uterus
5	Ligament of ovary
6	Uterine tube (isthmus)
7	Ovary
8	Ampulla of uterine tube
9	Rectum
10	Uterus
11	Vagina
12	Recto-uterine pouch (of Douglas)
13	Fimbriae of uterine tube
14	Suspensory ligament of ovary
15	Right common iliac artery (covered by peritoneum)
16	Common iliac vein
17	Common iliac artery
18	Ovarian artery and vein
19	Umbilical fold
20	Obturator artery
21	Inferior vena cava
22	Abdominal aorta
23	Superior hypogastric plexus
24	Recto-uterine fold
25	Broad ligament of uterus
26	Vesico-uterine pouch



Pelvic cavity in the female showing uterus and related organs (superior aspect). The peritoneum has been mostly removed.

1	Ilio-inguinal nerve
2	Ureter
3	Psoas major muscle
4	Genitofemoral nerve
5	Common iliac vein
6	Common iliac artery
7	Ovary
8	Uterine tube
9	Peritoneum
10	Round ligament of uterus
11	Inferior vena cava
12	Abdominal aorta
13	Superior hypogastric plexus
14	Rectum
15	Recto-uterine pouch (of Douglas)
16	Uterus
17	Vesico-uterine pouch
18	Urinary bladder
19	Iliac crest
20	Pubic symphysis
21	Rectal ampulla
22	Obturator internus muscle
23	Promontorium
24	Sigmoid colon
25	Head of femur
26	Urethra
27	Vagina
28	Labium minus



Horizontal section through the pelvic cavity in the female (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)

Female Internal Genital Organs: Arteries and Lymph Vessels



Arteries of female genital organs.



Main drainage routes of lymph vessels of uterus and related organs (indicated by arrows).

1	Uterus
2	Ovary
3	Uterine tube
4	Round ligament of uterus
5	Vaginal portion of cervix of uterus
6	Vagina
7	Clitoris
8	Corpus cavernosum of clitoris
9	Vaginal orifice
10	Bulb of vestibule
11	Greater vestibular gland
12	Ovarian artery
13	Suspensory ligament of ovary
14	Internal iliac artery
15	Tubal branch of ovarian artery
16	Ovarian branch of ovarian artery
17	Uterine artery
18	Ovarian branch of uterine artery
19	Artery of round ligament
20	Internal pudendal artery
21	Vaginal artery
22	Lumbar lymph nodes
23	External iliac lymph nodes
24	Inguinal lymph nodes
25	Abdominal aorta
26	External iliac artery
27	Sacral lymph nodes
28	Internal iliac lymph nodes
29	Superior gluteal artery
30	Obturator artery
31	Inferior gluteal artery
32	Middle sacral artery
33	Femoral artery
34	Vessels of labium majus
35	Femur



Arteriography of the pelvic vessels in the female (a.-p. direction).



1	Glans of clitoris
2	Labium majus
3	Vestibule of vagina
4	Hymen
5	Posterior labial commissure
6	Prepuce of clitoris
7	Labium minus
8	External urethral orifice
9	Vaginal orifice
10	Body of clitoris
11	Crus of clitoris
12	Bulb of vestibule with bulbospongiosus muscle
13	Frenulum of clitoris
14	Greater vestibular gland
15	Ureter
16	Adnexa of uterus
17	Cavernous body of clitoris
18	Anus and internal anal sphincter
19	Urachus
20	Urinary bladder
21	Infundibulum of uterine tube
22	Ovary
23	Uterine tube
24	Suspensory ligament of ovary
25	Perineal body
26	External anal sphincter

Female external genital organs in situ (anterior aspect). Labia reflected.



Cavernous tissue of female external genital organs, isolated (anterior aspect).



Female external genital organs in relation to internal genital organs and urinary system, isolated (anterior aspect).



1	Medial crus of superficial inguinal ring
2	Lateral crus of superficial inguinal ring
3	Superficial inguinal ring
4	Round ligament of uterus
5	Outer labia (labium majus)
6	Rectus abdominis muscle and inferior epigastric artery
7	Deep inguinal ring with ilio-inguinal nerve
8	Inguinal ligament
9	Femoral nerve
10	Femoral artery

Inguinal region and external genital organs in the female (anterior aspect). Dissection of the inguinal canal and round ligament of uterus of a child.



Inguinal region and external genital organs in the female (anterior aspect). The inguinal canal has been opened. The round ligament of uterus and the ilio-inguinal nerve have been dissected.



External genital organs and urogenital diaphragm in the female, superficial layer (inferior aspect).

1 Fatty tissue
encasing round ligament of uterus
2 Position of pubic symphysis
3 Clitoris
4 Labium minus
5 Bulb of vestibule
6 Ischiocavernosus muscle
7 Greater vestibular gland
8 Perineal branches of pudendal nerve
9 Levator ani muscle
10 Inferior rectal nerves
11 External anal sphincter muscle
12 Gluteus maximus muscle
13 Coccyx
14 Fatty tissue of mons pubis
15 External orifice of urethra
16 Urogenital diaphragm with fascia
of deep transverse perineal muscle
17 Vaginal orifice
18 Superficial transverse perineal muscle
19 Obturator internus muscle
20 Anus
21 Suspensory ligament of clitoris
22 Glans of clitoris
23 Crus of clitoris
24 Perineal body
25 Prepuce of clitoris
26 Frenulum of clitoris
27 Posterior commissure of labia



External genital organs with cavernous tissue in the female (inferior aspect). Blue = cavernous tissue of clitoris and bulb of vestibule.



1	Prepuce of clitoris
2	Labium minus
3	Vaginal orifice
4	Deep transverse perineal muscle
5	Dorsal nerve of clitoris
6	Posterior labial nerves
7	Great adductor muscle
8	Perineal branch of pudendal nerve
9	Anus and external anal sphincter muscle
10	Inferior cluneal nerves
11	Mons pubis
12	Crus of clitoris with ischiocavernosus muscle
13	Bulb of vestibule
14	Superficial transverse perineal muscle
15	Pudendal nerve and internal pudendal artery
16	Inferior rectal nerves
17	Levator ani muscle
18	Gluteus maximus muscle
19	Anococcygeal ligament
20	External urethral orifice

External genital organs and urogenital diaphragm in the female, superficial layer (inferior aspect). On the right side the bulb of vestibule has been removed.



Urogenital and pelvic diaphragms in the female (inferior aspect). Muscles, nerves, and arteries have been displayed. The bulb of vestibule has been partly removed.



External genital organs in the female (anterior aspect). The clitoris has been dissected and slightly reflected to the right. The prepuce of clitoris has been divided to display the glans.

1 Position of pubic symphysis
2 Body of clitoris
3 Prepuce of clitoris
4 Adductor longus and gracilis muscles
5 External orifice of vagina and labium minus
6 Posterior labial nerve
7 Perineal body
8 Deep artery of clitoris and dorsal nerve of clitoris
9 Adductor brevis muscle
10 Glans of clitoris
11 Crus of clitoris and ischiocavernosus muscle
12 Bulb of vestibule and bulbospongiosus muscle
13 Anterior branch of obturator nerve



1 Clitoris
2 Labium minus
3 Vaginal orifice
4 Posterior labial nerves
5 Perineal branches of pudendal nerve
6 External anal sphincter muscle
7 Anus
8 Crus of clitoris and ischiocavernosus muscle
9 Bulb of vestibule
10 Dorsal artery of clitoris
11 Superficial transverse perineal muscle
12 Perineal branch of posterior femoral cutaneous nerve
13 Levator ani muscle
14 Internal pudendal artery
15 Inferior rectal nerves
16 Gluteus maximus muscle
17 Anococcygeal ligament

External genital organs and urogenital diaphragm in the female (latero-inferior aspect). The bulb of vestibule has been partly removed. The left labium minus was cut away.

Pelvic Cavity in the Female: Coronal and Horizontal Sections




1
2
3
4
5
6
7
8
9
10
11
12
13
14

Coronal section through the pelvic cavity of the female at the level of the hip joints.

1 Ilium
2 Rectum
3 Recto-uterine fold
4 Ovary
5 Uterine tube
6 Urinary bladder
7 Urethra
8 Labium minus
9 Recto-uterine pouch
10 Uterus and vesico-uterine pouch
11 Ligament of the head of femur
12 Head of femur
13 Vestibule of vagina
14 Labium majus
15 Pyramidalis muscle
16 Femoral nerve
17 Femoral artery and vein
18 Small intestine
19 Broad ligament of uterus


15
16
17
18
12
19
20
9
21
22
23
11
24
25
26
27
28
29

Horizontal section through the pelvic cavity of the female at the level of the uterus (inferior aspect). The uterus is retroverted to the left.


30
31
16
17
32
24
33
21
22
34
23
35
7
32
36
37
29

Horizontal section through the pelvic cavity of the female at the level of the urethral sphincter muscle and vagina (inferior aspect).



Coronal section through the pelvic cavity of the female at the level of the hip joints (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Horizontal section through the pelvic cavity of the female at the level of the uterus (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



Horizontal section through the pelvic cavity of the female at the level of urethral sphincter muscle and vagina (MRI scan). (Prof. Uder, Dept. of Radiology, Univ. Erlangen-Nuremberg, Germany.)



20	Uterine venous plexus
21	Sciatic nerve and gluteus maximus muscle
22	Sartorius muscle
23	Iliopsoas muscle
24	Obturator internus muscle
25	Endometrium
26	Myometrium
27	Rectal ampulla
28	Coccyx
29	Anal cleft
30	Mons pubis
31	Pectineus muscle
32	Obturator externus muscle
33	Levator ani muscle
34	Pubic symphysis
35	Urethral sphincter muscle (base of urinary bladder)
36	Vagina
37	Rectum (anal canal)

7 Upper Limb

Skeleton of the Shoulder Girdle and Thorax 381
Scapula and Clavicle 383
Skeleton of the Shoulder Girdle and Humerus 384
Humerus 385
Skeleton of the Forearm 386
Skeleton of the Forearm and Hand 387
Skeleton of the Hand 388
Joints and Ligaments of the Shoulder 390
Joints and Ligaments of the Elbow 391
Ligaments of the Hand and Wrist 392
Muscles of the Shoulder and Arm 394
Muscles of the Arm 398
Muscles of the Forearm and Hand 400
Muscles of the Hand 406
Arteries 408
Veins 410
Nerves 411
Surface Anatomy of the Upper Limb 413
Neck and Shoulder 415
Shoulder 416
Shoulder and Arm 420
Axillary Region 422
Brachial Plexus 425
Arm 426
Cubital Region 428
Forearm and Hand 432
Hand 436
Sections through the Upper Limb 444





Skeleton of shoulder girdle and thorax (anterior aspect).
The cartilaginous parts of the ribs appear dark brown.

Vertebral column
1 Atlas (C_1)
2 Axis (C_2)
3 Third to seventh cervical vertebrae (C_3–C_7)
4 First thoracic vertebra (Th_1)
5 Twelfth thoracic vertebra (Th_{12})
6 First lumbar vertebra (L_1)

Ribs
7 First to third ribs } True ribs
8 Fourth to seventh ribs }
9 Eighth to tenth ribs } False ribs
10 Eleventh and twelfth ribs (floating ribs) }

Clavicle (A)
11 Sternal end
12 Sternoclavicular joint
13 Acromial end
14 Acromioclavicular joint

Scapula (B)
15 Acromion
16 Coracoid process
17 Glenoid cavity
18 Costal surface

Sternum (C)
19 Manubrium
20 Body
21 Xiphoid process



Skeleton of shoulder girdle and thorax (superior aspect).



Skeleton of shoulder girdle and thorax (posterior aspect).



Skeleton of shoulder girdle and thorax (lateral aspect).

Vertebral column

1	Atlas
2	Axis
3	Third to sixth cervical vertebrae
4	Seventh vertebra (vertebra prominens)
5	First thoracic vertebra
6	Sixth thoracic vertebra
7	Twelfth thoracic vertebra
8	First lumbar vertebra

Clavicle

9	Sternal end
10	Acromial end
11	Acromioclavicular joint

Scapula

12	Acromion
13	Spine of scapula
14	Lateral angle
15	Posterior surface
16	Inferior angle
17	Coracoid process
18	Supraglenoid tubercle
19	Glenoid cavity
20	Infraglenoid tubercle
21	Lateral margin

Thorax

22	Body of sternum
23	Subcostal angle
24	Angle of rib
25	Floating ribs



Right scapula (posterior aspect).



Right scapula (anterior aspect, costal surface).



Right scapula (lateral aspect).



Right clavicle (superior aspect).



Right clavicle (inferior aspect).

Scapula
A = Superior border
B = Medial border
C = Lateral border
D = Superior angle
E = Inferior angle
F = Lateral angle

1 Acromion
2 Coracoid process
3 Scapular notch
4 Glenoid cavity
5 Infraglenoid tubercle
6 Supraspinous fossa
7 Spine
8 Infraspinous fossa
9 Articular facet for the acromion
10 Neck
11 Supraglenoid tubercle
12 Costal (anterior) surface
13 Base of coracoid process

Clavicle
1 Acromial end
2 Articular facet for the acromion
3 Articular facet for the sternum
4 Sternal end
5 Trapezoid line
6 Conoid tubercle
7 Impression of costoclavicular ligament



Bones of **shoulder joint** (posterior aspect).

1	First rib
2	Position of costotransverse joints
3	Fourth to seventh ribs
4	Clavicle
5	Position of acromioclavicular joint
6	Acromion
7	Scapular notch
8	Spine of scapula
9	Head of humerus
10	Glenoid cavity
11	Surgical neck of humerus
12	Posterior surface of scapula
13	Coracoid process
14	Infraglenoid tubercle
15	Greater tubercle of humerus
16	Anatomical neck of humerus



Bones of shoulder joint (anterior aspect).



Right humerus (anterior aspect).



Right humerus (medial aspect).



Right humerus (posterior aspect).

Humerus

1 Greater tubercle
2 Lesser tubercle
3 Crest of lesser tubercle
4 Crest of greater tubercle
5 Intertubercular sulcus
6 Surgical neck
7 Deltoid tuberosity
8 Antero-lateral surface
9 Lateral supracondylar ridge
10 Radial fossa
11 Lateral epicondyle
12 Capitulum
13 Head
14 Anatomical neck
15 Antero-medial surface
16 Medial supracondylar ridge
17 Coronoid fossa
18 Medial epicondyle
19 Trochlea
20 Posterior surface
21 Groove for ulnar nerve
22 Groove for radial nerve
23 Olecranon fossa



Bones of right forearm, radius, and ulna (anterior aspect).



Bones of right forearm, radius, and ulna (posterior aspect).

Radius
1 Head
2 Articular circumference
3 Neck
4 Radial tuberosity
5 Shaft
6 Anterior surface
7 Styloid process
8 Articular surface
9 Posterior surface
10 Ulnar notch

Ulna
11 Trochlear notch
12 Coronoid process
13 Radial notch
14 Ulnar tuberosity
15 Head
16 Articular circumference
17 Styloid process
18 Posterior surface
19 Olecranon



Bones of the right elbow joint (lateral aspect).

Articulations at the right elbow
20 Site of humero-ulnar joint
21 Site of humeroradial joint
22 Site of proximal radio-ulnar joint

A = Humerus
B = Radius
C = Ulna


1
2
3
4
5
6
7
9
10
11
12
13
14
17
18
19
20
21
22
23
15
24
16
25
26

Skeleton of right forearm and hand in pronation.


1
2
3
4
5
7
6
8
10
23
15
11
16
12
13
14
17
18
19
21
22
24
25
26

Skeleton of right forearm and hand in supination.

1 Humerus
2 Trochlea of humerus
3 Capitulum of humerus
4 Articular circumference of radius
5 Radial tuberosity
6 Anterior surface of ulna
7 Posterior surface of radius
8 Anterior surface of radius

9 Articular circumference of ulna
10 Carpal bones
11 Metacarpal bones
12 Proximal phalanges
13 Middle phalanges
14 Distal phalanges
15 Metacarpal bone of thumb
16 Proximal phalanx of thumb

Sites of joints
17 Humeroradial joint
18 Humero-ulnar joint
19 Proximal radio-ulnar joint
20 Distal radio-ulnar joint
21 Wrist joint
22 Midcarpal joint
23 Carpometacarpal joint of thumb
24 Carpometacarpal joints
25 Metacarpophalangeal joints
26 Interphalangeal joints of the hand



Skeleton of right wrist and hand (dorsal aspect).



Skeleton of right wrist and hand (medial aspect).

1	Radius	
2	Ulna	
3	Styloid process of ulna	
4	Lunate bone	Carpal bones
5	Triquetral bone	
6	Capitate bone	
7	Hamate bone	
8	Base of third metacarpal bone	
9	Metacarpal bones	
10	Head of metacarpal bone	
11	Proximal phalanges of the hand	
12	Middle phalanges of the hand	
13	Distal phalanges of the hand	
14	Styloid process of radius	
15	Scaphoid bone	Carpal bones
16	Trapezium bone	
17	Trapezoid bone	
18	Metacarpal bone of thumb	
19	Proximal phalanx of thumb	
20	Distal phalanx of thumb	
21	Base of second proximal phalanx	
22	Head of second proximal phalanx	
23	Tuberosity of distal phalanx	
24	Body of third metacarpal bone	



1	Radius	
2	Styloid process of radius	
3	Scaphoid bone	Carpal bones
4	Capitate bone	
5	Trapezium	
6	Trapezoid bone	
7	First metacarpal bone	
8	Second to fourth metacarpal bones	
9	Proximal phalanx of thumb	
10	Distal phalanx of thumb	
11	Base of second proximal phalanx	
12	Proximal phalanges	
13	Head of second proximal phalanx	
14	Middle phalanges	
15	Distal phalanx	
16	Ulna	
17	Styloid process of ulna	
18	Lunate bone	Carpal bones
19	Pisiform bone	
20	Triquetral bone	
21	Hamate bone	
22	Hamulus or hook of hamate bone	
23	Base of third metacarpal bone	
24	Head of metacarpal bone	
25	Tuberosity of distal phalanx	

Skeleton of right wrist and hand (palmar aspect).

The human hand is one of the most admirable structures of the human body. The carpometacarpal joint of the thumb, a saddle joint, enjoys wide mobility so that the thumb can come into contact with all other fingers, thus enabling the hand to become an instrument for grasping and psychologic expression. During evolution, these newly developed functions appeared after the erect posture of the human body was achieved. An inevitable prerequisite for the development of human cultures is not only the differentiation of the brain but also the development of an organ capable of realizing its ideas: the human hand.



Right shoulder joint. The anterior part of the articular capsule has been removed and the head of the humerus has been slightly rotated outward to show the cavity of the joint.



Coronal section through the right shoulder joint (anterior aspect).



Coronal section through the right shoulder joint (MRI scan).
(Courtesy of Prof. Heuck, Munich, Germany.)

1 Acromial end of clavicle
2 Acromioclavicular joint
3 Acromion
4 Tendon of supraspinatus muscle (attached to the articular capsule)
5 Coraco-acromial ligament
6 Tendon of long head of biceps brachii muscle
7 Tendon of subscapularis muscle (attached to the articular capsule)
8 Intertubercular sulcus
9 Articular capsule of shoulder joint
10 Humerus
11 Trapezoid ligament
12 Coracoid process
13 Glenoid labrum
14 Shoulder joint (joint cavity)
15 Scapula
16 Head of humerus
17 Epiphysial line
18 Supraspinatus muscle
19 Glenoid cavity
20 Trapezius muscle
21 Suprascapular artery, vein, and nerve
22 Teres major muscle
23 Circumflexa scapular artery and vein
24 Latissimus dorsi muscle
25 Deltoid muscle
26 Tendon of long head of triceps brachii muscle



Ligaments of the elbow joint (anterior aspect).



Ligaments of the elbow joint (medial aspect).

1 Humerus
2 Lateral epicondyle of humerus
3 Articular capsule
4 Anular ligament of proximal radio-ulnar joint
5 Radius
6 Tendon of biceps brachii muscle
7 Medial epicondyle of humerus
8 Ulnar collateral ligament
9 Oblique chord
10 Ulna
11 Interosseous membrane
12 Radial fossa
13 Capitulum of humerus
14 Head of radius
15 Radial collateral ligament
16 Coronoid fossa
17 Trochlea of humerus
18 Coronoid process of ulna
19 Olecranon
20 Radial tuberosity



Elbow joint with ligaments (anterior aspect). Articular capsule has been removed to show the anular ligament.



Coronal section through the elbow joint (MRI scan). (Courtesy of Prof. Heuck, Munich, Germany.)



Ligaments of hand and wrist (dorsal aspect).

1	Ulna
2	Exostosis (pathological)
3	Head of ulna
4	Ulnar carpal collateral ligament
5	Deep intercarpal ligaments
6	Dorsal carpometacarpal ligaments
7	Dorsal metacarpal ligaments
8	Interosseous membrane
9	Radius
10	Styloid process of radius
11	Dorsal radiocarpal ligament
12	Radial collateral ligament
13	Articular capsule and dorsal intercarpal ligaments
14	Palmar radiocarpal ligament
15	Tendon of flexor carpi radialis muscle (cut)
16	Radiating carpal ligament
17	Palmar carpometacarpal ligaments
18	First metacarpal bone
19	Palmar ulnocarpal ligament
20	Tendon of flexor carpi ulnaris muscle (cut)
21	Pisohamate ligament
22	Pisometacarpal ligament
23	Palmar metacarpal ligaments
24	Fifth metacarpal bone
25	Articular disc (ulnocarpal)
26	Lunate bone
27	Triquetral bone
28	Hamate bone
29	Scaphoid (navicular) bone
30	Capitate bone
31	Trapezoid bone
32	Second and third metacarpal bones
33	Dorsal interossei muscles



Ligaments of hand and wrist (palmar aspect).



Coronal section through the hand and wrist (MRI scan). (Courtesy of Prof. Heuck, Munich, Germany.) Note the location of the wrist joint.

1 Radius
2 Styloid process of radius
3 Palmar radiocarpal ligament
4 Tendon of flexor carpi radialis muscle (cut)
5 Radiating carpal ligament
6 Articular capsule of carpometacarpal joint of thumb
7 Articular capsule of metacarpophalangeal joint of thumb
8 Palmar ligaments and articular capsule of metacarpophalangeal joints
9 Palmar ligaments and articular capsule of interphalangeal joints
10 Articular capsule
11 Interosseous membrane
12 Ulna
13 Distal radio-ulnar joint
14 Styloid process of ulna
15 Palmar ulnocarpal ligament
16 Pisiform bone with tendon of flexor carpi ulnaris muscle
17 Pisometacarpal ligament
18 Pisohamate ligament
19 Metacarpal bones
20 Deep transverse metacarpal ligaments
21 Tendons of extensor muscles and articular capsule
22 Collateral ligament of interphalangeal joint
23 Collateral ligaments of metacarpophalangeal joints
24 Second metacarpal bone



Ligaments of forearm, hand, and fingers (palmar aspect). The arrow indicates the location of the carpal tunnel.



Ligaments of fingers (lateral aspect).



1 Descending fibers of trapezius muscle
2 Spinous processes of thoracic vertebrae
3 Ascending fibers of trapezius muscle
4 Rhomboid major muscle
5 Inferior angle of scapula
6 Latissimus dorsi muscle
7 Transverse fibers of trapezius muscle
8 Spine of scapula
9 Posterior fibers of deltoid muscle
10 Infraspinatus muscle and infraspinous fascia
11 Teres minor muscle and fascia
12 Long head of triceps brachii muscle
13 Teres major muscle
14 Lateral head of triceps brachii muscle
15 Tendon of triceps brachii muscle
16 Medial intermuscular septum
17 Ulnar nerve
18 Olecranon

Muscles of shoulder and arm, superficial layer (right side, posterior aspect).



1 Trapezius muscle (reflected)
2 Levator scapulae muscle
3 Supraspinatus muscle
4 Rhomboid minor muscle
5 Medial border of scapula
6 Rhomboid major muscle
7 Infraspinatus muscle
8 Teres major muscle
9 Inferior angle of scapula
10 Cut edge of trapezius muscle
11 Intrinsic muscles of back with fascia
12 Latissimus dorsi muscle
13 Acromion
14 Spine of scapula
15 Deltoid muscle
16 Teres minor muscle
17 Long head of triceps brachii muscle
18 Lateral head of triceps brachii muscle
19 Medial head of triceps brachii muscle
20 Medial intermuscular septum
21 Tendon of triceps brachii muscle

Muscles of shoulder and arm, deeper layer (right side, posterior aspect). The trapezius muscle has been cut near its origin at the vertebral column and reflected upward.



1 Splenius capitis muscle
2 Sternocleidomastoid muscle
3 Trapezius muscle (reflected)
4 Lateral supraclavicular nerves
5 Clavicle
6 Levator scapulae muscle
7 Supraspinatus muscle
8 Spine of scapula
9 Deltoid muscle (reflected)
10 Rhomboid minor muscle
11 Rhomboid major muscle
12 Axillary nerve and posterior circumflex humeral artery
13 Infraspinatus muscle
14 Teres minor muscle
15 Long head of triceps brachii muscle
16 Teres major muscle
17 Inferior angle of scapula
18 Triceps brachii muscle
19 Latissimus dorsi muscle

Muscles of shoulder and arm, deeper layer (right side, posterior aspect). The trapezius and deltoid muscles have been divided and reflected.



Position and course of the main shoulder muscles (posterior aspect).

◁

1 Rhomboid minor muscle (red)
2 Rhomboid major muscle (red)
3 Levator scapulae muscle (red)
4 Supraspinatus muscle (blue)
5 Deltoid muscle (red)
6 Infraspinatus muscle (blue)
7 Teres minor muscle (red)
8 Teres major muscle (red)

112897_S_380_408_Kap_7:_ 06.11.2014 10:50 Uhr Seite 396



Shoulder, arm, and pectoral muscles, superficial layer (right side, anterior aspect).

1 Trapezius muscle
2 Acromion
3 Deltopectoral triangle
4 Clavicular part of deltoid muscle (anterior fibers)
5 Acromial part of deltoid muscle (central fibers)
6 Clavicular part of pectoralis major muscle
7 Sternocostal part of pectoralis major muscle
8 Short head of biceps brachii muscle
9 Long head of biceps brachii muscle
10 Abdominal part of pectoralis major muscle
11 Brachialis muscle
12 Serratus anterior muscle
13 External abdominal oblique muscle
14 Sternocleidomastoid muscle
15 Infrahyoid muscles
16 Clavicle
17 Manubrium sterni
18 Body of sternum
19 Xiphoid process
20 Anterior layer of sheath of rectus abdominis muscle



Position and course of pectoral and shoulder muscles (anterior aspect).

1 Subclavius muscle (blue)
2 Pectoralis minor muscle (blue)
3 Pectoralis major muscle (red)
4 Subscapularis muscle (red)
5 Coracobrachialis muscle (red)
6 Serratus anterior muscle (green)



Shoulder, arm, and pectoral muscles, deep layer (right side, anterior aspect).



1	Acromion
2	Clavicular part of deltoid muscle
3	Pectoralis major muscle (reflected)
4	Coracobrachialis muscle
5	Short head of biceps brachii muscle
6	Deltoid muscle (insertion on humerus)
7	Long head of biceps brachii muscle
8	Brachialis muscle
9	Sternocleidomastoid muscle
10	Clavicle
11	Subclavius muscle
12	Pectoralis minor muscle
13	Sternum
14	Third rib
15	Pectoralis major muscle (cut)
16	Platysma muscle
17	Pectoralis major muscle forming the anterior axillary fold
18	Anterior cutaneous branches of intercostal nerves
19	Lateral cutaneous branches of intercostal nerves
20	Rectus abdominis muscle
21	Subscapularis muscle
22	Latissimus dorsi muscle forming the posterior axillary fold
23	Serratus anterior muscle forming the medial wall of the axilla
24	External abdominal oblique muscle

Axillary fossa and serratus anterior muscle (left side, lateral aspect).


1
2
3
4
5
6
7
8
9
10
11

Muscles of the arm (right side, lateral aspect).


33
1
6
34
29
8
3
35
9
36
37
32

Sagittal section through the arm (right side; MRI scan). (From Heuck et al., MRT-Atlas, 2009.)



Position and course of flexors of the arm (anterior aspect).

1 Subscapularis muscle (red)
2 Coracobrachialis muscle (blue)
3 Biceps brachii muscle (red)
4 Brachialis muscle (blue)



Muscles of the arm (right side, anterior aspect). The arm with the scapula and attached muscles has been removed from the trunk.



Muscles of the arm (right side, anterior aspect). Part of the biceps brachii muscle has been removed.
Arrow: tendon of long head of biceps brachii muscle.

1 Acromial part of deltoid muscle (central fibers)
2 Scapular part of deltoid muscle (posterior fibers)
3 Triceps brachii muscle
4 Tendon of triceps brachii muscle
5 Olecranon
6 Clavicular part of deltoid muscle (anterior fibers)
7 Deltopectoral groove
8 Biceps brachii muscle
9 Brachialis muscle
10 Brachioradialis muscle
11 Extensor carpi radialis longus muscle
12 Clavicle (divided)
13 Pectoralis major muscle
14 Medial intermuscular septum with vessels and nerves
15 Lateral intermuscular septum
16 Tendon of biceps brachii muscle
17 Bicipital aponeurosis
18 Axillary artery
19 Rhomboid major muscle
20 Subscapularis muscle
21 Latissimus dorsi muscle (divided)
22 Medial intermuscular septum
23 Medial epicondyle of humerus
24 Brachial artery and median nerve
25 Pronator teres muscle
26 Tendon of short head of biceps brachii muscle
27 Coracobrachialis muscle
28 Distal part of biceps brachii muscle
29 Teres major muscle
30 Long head of triceps brachii muscle
31 Medial head of triceps brachii muscle
32 Radius
33 Head of humerus
34 Axillary nerve
35 Humerus
36 Trochlea
37 Ulna



Flexor muscles of forearm and hand, superficial layer (right side, anterior aspect).



Flexor muscles of forearm and hand, superficial layer (right side, anterior aspect). The palmaris longus and flexor carpi ulnaris muscles have been removed.

1 Biceps brachii muscle
2 Bicipital aponeurosis
3 Brachioradialis muscle
4 Flexor carpi radialis muscle
5 Radial artery
6 Flexor digitorum superficialis muscle
7 Median nerve
8 Antebrachial fascia and tendon of palmaris longus muscle
9 Tendon of abductor pollicis longus muscle
10 Tendon of extensor pollicis brevis muscle
11 Abductor pollicis brevis muscle
12 Palmar aponeurosis
13 Superficial head of flexor pollicis brevis muscle
14 Tendon of flexor pollicis longus muscle
15 Medial intermuscular septum
16 Medial epicondyle of humerus
17 Humeral head of pronator teres muscle
18 Palmaris longus muscle
19 Flexor carpi ulnaris muscle
20 Ulnar artery
21 Tendon of flexor carpi ulnaris muscle
22 Palmaris brevis muscle



Flexor muscles of forearm and hand, middle layer (right side, anterior aspect). The palmaris longus, flexor carpi radialis, and ulnaris muscles have been removed. The flexor retinaculum has been divided.



Position and course of flexors of forearm and hand (anterior aspect).

A Deep flexors

1 Flexor pollicis longus muscle (blue)
2 Flexor digitorum profundus muscle (red)

B Superficial flexors

3 Pronator teres muscle (red)
4 Flexor carpi radialis muscle (red)
5 Flexor carpi ulnaris muscle (red)
6 Flexor digitorum superficialis muscle (blue)

23 Abductor digiti minimi muscle
24 Transverse fasciculi of palmar aponeurosis
25 Digital fibrous sheaths of tendons of flexor digitorum muscle
26 Brachialis muscle
27 Flexor pollicis longus muscle
28 Carpal tunnel (canalis carpi, probe)
29 Triceps brachii muscle
30 Flexor digitorum superficialis muscle
31 Pisiform bone
32 Opponens digiti minimi muscle
33 Flexor digiti minimi brevis muscle
34 Tendons of flexor digitorum superficialis muscle
35 Supinator muscle
36 Radius and extensor carpi radialis brevis muscle
37 Flexor pollicis longus muscle
38 Tendon of flexor carpi radialis muscle
39 Pronator teres muscle (insertion of radius)
40 Flexor digitorum profundus muscle
41 Lumbrical muscles
42 Tendons of flexor digitorum profundus muscle
43 Tendons of flexor digitorum profundus muscle having passed through the divided tendons of the flexor digitorum superficialis muscle
44 Flexor retinaculum



Flexor muscles of forearm and hand, deep layer (right side, anterior aspect). All flexors have been removed to display the pronator quadratus and pronator teres muscles together with the interosseous membrane. Forearm in supination.

1 Biceps brachii muscle
2 Brachialis muscle
3 Pronator teres muscle
4 Brachioradialis muscle
5 Radius
6 Tendon of flexor carpi radialis muscle
7 Tendon of abductor pollicis longus muscle
8 Opponens pollicis muscle
9 Adductor pollicis muscle
10 Tendon of flexor pollicis longus muscle
11 Triceps brachii muscle
12 Medial intermuscular septum
13 Medial epicondyle of humerus
14 Common flexor mass (divided)
15 Ulna
16 Interosseous membrane
17 Pronator quadratus muscle
18 Tendon of flexor carpi ulnaris muscle
19 Pisiform bone
20 Abductor digiti minimi muscle
21 Flexor digiti minimi brevis muscle
22 Tendons of flexor digitorum profundus muscle
23 Tendons of flexor digitorum superficialis muscle
24 Flexor retinaculum
25 Hypothenar muscles
26 Thenar muscles
27 Common synovial sheath of flexor tendons
28 Synovial sheath of tendon of flexor pollicis longus muscle
29 Digital synovial sheaths of flexor tendons



Synovial sheaths of flexor tendons, indicated in blue (palmar aspect of right hand).



Right supinator muscle and elbow joint (anterior aspect). Forearm in pronation.

1	Humerus
2	Lateral epicondyle of humerus
3	Articular capsule
4	Position of capitulum of humerus
5	Deep branch of radial nerve
6	Supinator muscle
7	Entrance of deep branch of radial nerve to extensor muscles
8	Radius and insertion of pronator teres muscle
9	Interosseous membrane
10	Median nerve
11	Triceps brachii muscle
12	Trochlea of humerus
13	Tendon of biceps brachii muscle
14	Brachial artery
15	Pronator teres muscle
16	Tendon of pronator teres muscle
17	Ulna
18	Pronator quadratus muscle
19	Tendon of flexor carpi radialis muscle
20	Thenar muscles
21	Synovial sheath of tendon of flexor pollicis longus muscle
22	Fibrous sheath of flexor tendons
23	Digital synovial sheath of flexor tendons
24	Flexor digitorum superficialis muscle
25	Tendon of flexor carpi ulnaris muscle
26	Common synovial sheath of flexor tendons
27	Position of pisiform bone
28	Flexor retinaculum
29	Hypothenar muscles



Synovial sheaths of flexor tendons (palmar aspect of right hand). The sheaths have been injected with blue gelatin.



A = Axis of flexion and extension
B = Axis of rotation

Arrows:
S = Supination
P = Pronation

Diagram illustrating the two axes of the elbow joint.



Extensor muscles of forearm and hand, superficial layer (right side, posterior aspect). Tunnels for extensor tendons indicated by probes.

1 Lateral intermuscular septum
2 Tendon of triceps brachii muscle
3 Lateral epicondyle of humerus
4 Olecranon
5 Anconeus muscle
6 Extensor carpi ulnaris muscle
7 Extensor digitorum muscle
8 Extensor digiti minimi muscle
9 Extensor retinaculum
10 Tendons of extensor digiti minimi muscle
11 Tendons of extensor digitorum muscle
12 Intertendinous connections
13 Brachioradialis muscle
14 Extensor carpi radialis longus muscle
15 Extensor carpi radialis brevis muscle
16 Abductor pollicis longus muscle
17 Extensor pollicis brevis muscle
18 Tendon of extensor pollicis longus muscle
19 Tendons of both extensor carpi radialis longus and extensor carpi radialis brevis muscles
20 Tendon of extensor indicis muscle
21 First tunnel: Abductor pollicis longus muscle, extensor pollicis brevis muscle
22 Second tunnel: Extensor carpi radialis longus and brevis muscles
23 Third tunnel: Extensor pollicis longus muscle
24 Fourth tunnel: Extensor digitorum muscle, extensor indicis muscle
25 Fifth tunnel: Extensor digiti minimi muscle
26 Sixth tunnel: Extensor carpi ulnaris muscle



Synovial sheaths of extensor tendons, indicated in blue (dorsal aspect of right hand). Notice the six tunnels for the passage of the extensor tendons beneath the extensor retinaculum.



Synovial sheaths of extensor tendons (dorsal aspect of right hand). The sheaths have been injected with blue gelatin.



Extensor muscles of forearm and hand, deep layer (right side, posterior aspect).

1 Triceps brachii muscle
2 Lateral intermuscular septum
3 Lateral epicondyle of humerus
4 Anconeus muscle
5 Extensor digitorum and extensor digiti minimi muscles (cut)
6 Supinator muscle
7 Extensor carpi ulnaris muscle
8 Extensor retinaculum
9 Third and fourth dorsal interossei muscles
10 Tendons of extensor digitorum muscle (cut)
11 Biceps brachii muscle
12 Brachialis muscle
13 Brachioradialis muscle
14 Extensor carpi radialis longus muscle
15 Extensor carpi radialis brevis muscle
16 Abductor pollicis longus muscle
17 Extensor pollicis longus muscle
18 Extensor pollicis brevis muscle
19 Extensor indicis muscle
20 Tendons of extensor carpi radialis longus and extensor carpi radialis brevis muscles
21 First dorsal interosseous muscle



Position and course of extensors of forearm and hand (posterior aspect).

A Extensors of thumb

1 Abductor pollicis longus muscle (red)
2 Extensor pollicis brevis muscle (blue)
3 Extensor pollicis longus muscle (red)
4 Extensor indicis muscle (blue)

B Extensors of fingers and hand

5 Extensor carpi ulnaris muscle (blue)
6 Extensor digitorum muscle (red)
7 Extensor carpi radialis brevis muscle (blue)
8 Extensor carpi radialis longus muscle (blue)



Muscles of thumb and index finger (medial aspect). The tendons of the extensor muscles of the thumb and the insertion of the flexor tendons of the index finger are displayed.



Muscles of the hand (right side, palmar aspect). The tendons of the flexor muscles and parts of the thumb muscles have been removed. The carpal tunnel has been opened.

1 Tendons of extensor pollicis brevis and abductor pollicis longus muscles
2 Extensor retinaculum
3 Tendon of extensor pollicis longus muscle
4 Tendons of extensor carpi radialis longus and brevis muscles
5 First dorsal interosseous muscle
6 Tendon of extensor digitorum muscle for index finger
7 Location of metacarpophalangeal joint
8 Tendon of lumbrical muscle
9 Extensor expansion of index finger
10 Tendon of flexor carpi radialis muscle (cut)
11 Anatomical snuffbox
12 Tendon of abductor pollicis longus muscle
13 Tendon of extensor pollicis brevis muscle
14 Tendon of abductor pollicis brevis muscle
15 Extensor expansion of extensor of thumb
16 Vinculum longum
17 Tendons of flexor digitorum superficialis muscle dividing to allow passage of deep tendons
18 Vincula of flexor tendons
19 Tendon of flexor digitorum profundus muscle
20 Vinculum breve
21 Radial carpal eminence (cut edge of flexor retinaculum)
22 Opponens pollicis muscle
23 Deep head of flexor pollicis brevis muscle
24 Abductor pollicis brevis muscle (cut)
25 Superficial head of flexor pollicis brevis muscle (cut)
26 Oblique head of adductor pollicis muscle
27 Transverse head of adductor pollicis muscle
28 Tendon of flexor pollicis longus muscle (cut)
29 Lumbrical muscles (cut)
30 First dorsal interosseous muscle
31 Position of carpal tunnel
32 Tendon of flexor carpi ulnaris muscle
33 Location of pisiform bone
34 Hook of hamate bone
35 Abductor digiti minimi muscle
36 Flexor digiti minimi brevis muscle
37 Opponens digiti minimi muscle
38 Second palmar interosseous muscle
39 Third palmar interosseous muscle
40 Fourth dorsal interosseous muscle
41 Third dorsal interosseous muscle
42 Tendon of flexor digitorum profundus muscle (cut)
43 Tendons of flexor digitorum superficialis muscle (cut)
44 Fibrous flexor sheaths



Muscles of the hand, deep layer (right side, palmar aspect). The thenar and hypothenar muscles have been removed to display the interossei muscles.



Actions of interossei muscles in abduction and adduction of fingers (palmar aspect of right hand).
Arrow: carpal tunnel.
Red = abduction (dorsal interossei, abductor digiti minimi, and abductor pollicis brevis muscles)
Blue = adduction (palmar interossei muscles, adductor pollicis muscle)



Longitudinal section through the third finger (MRI scan).
(Prof. Heuck, Munich, Germany.) Compare with the correspondent drawing.

1 Pronator quadratus muscle
2 Tendon of flexor carpi radialis muscle
3 Abductor pollicis brevis muscle (divided)
4 Adductor pollicis muscle (divided)
5 Tendon of flexor pollicis longus muscle
6 Lumbrical muscles (cut)
7 Tendon of flexor carpi ulnaris muscle
8 Pisiform bone
9 Abductor digiti minimi muscle (divided)
10 Dorsal interossei muscles
11 Palmar interossei muscles
12 Radius
13 Ulna
14 Flexor retinaculum
15 Tendons of flexor digitorum profundus muscle
16 Tendons of flexor digitorum superficialis muscle
17 Palmar aponeurosis
18 Carpometacarpal joint
19 Third metacarpal bone
20 Metacarpophalangeal joint
21 Head of third proximal phalanx
22 Proximal interphalangeal joint
23 Middle phalanx
24 Distal phalanx



Main branches of subclavian and axillary arteries (right side, anterior aspect). Pectoralis muscles have been reflected, clavicle and anterior wall of thorax removed, and right lung divided. Left lung with pleura and thyroid gland have been reflected laterally to display aortic arch and common carotid artery with their branches.

1 Pectoralis minor muscle (reflected)
2 Anterior circumflex humeral artery
3 Musculocutaneous nerve (divided)
4 Axillary artery
5 Posterior circumflex humeral artery
6 Profunda brachii artery
7 Median nerve (var.)
8 Brachial artery
9 Biceps brachii muscle
10 Thoraco-acromial artery
11 Suprascapular artery
12 Descending scapular artery
13 Brachial plexus (middle trunk)
14 Transverse cervical artery
15 Anterior scalene muscle and phrenic nerve
16 Right internal carotid artery
17 Right external carotid artery
18 Carotid sinus
19 Superior thyroid artery
20 Right common carotid artery
21 Ascending cervical artery
22 Thyroid gland
23 Inferior thyroid artery
24 Internal thoracic artery
25 Right subclavian artery
26 Brachiocephalic trunk
27 Left brachiocephalic vein (divided)
28 Left vagus nerve
29 Superior vena cava (divided)
30 Ascending aorta
31 Median nerve (divided)
32 Phrenic nerve
33 Right lung (divided) and pulmonary pleura
34 Thoracodorsal artery
35 Subscapular artery
36 Lateral mammary branches (var.)
37 Lateral thoracic artery
38 Thyrocervical trunk
39 Supreme intercostal artery
40 Superior ulnar collateral artery
41 Inferior ulnar collateral artery
42 Middle collateral artery
43 Radial collateral artery
44 Radial recurrent artery
45 Radial artery
46 Anterior and posterior interosseous arteries
47 Princeps pollicis artery
48 Deep palmar arch
49 Common palmar digital arteries
50 Ulnar recurrent artery
51 Recurrent interosseous artery
52 Common interosseous artery
53 Ulnar artery
54 Superficial palmar arch
55 Median nerve and brachial artery
56 Biceps brachii muscle
57 Ulnar nerve
58 Flexor pollicis longus muscle
59 Proper palmar digital arteries
60 Anterior interosseous artery
61 Flexor carpi ulnaris muscle
62 Superficial palmar branch of radial artery


56
45
58
45
7
62
55
41
53
50
57
53
60
61
53
54
49
59

Main arteries of forearm and hand (right side, anterior aspect). The superficial flexor muscles have been removed, the carpal tunnel opened, and the flexor retinaculum cut. The arteries have been filled with colored resin.


12
10
4
5
2
35
6
8
42
43
44
45
46
62
47
49
38
25
39
24
37
40
41
50
51
52
53
48
54

Main arteries of the upper limb (right side).



Veins of head, neck, and upper limb and their connection with the heart (oblique-anterior aspect). The anterior thoracic wall has been opened.



Main truncal veins of the upper limb (right side).

1	Superficial temporal artery and vein
2	Occipital vein
3	Parotid gland
4	Great auricular nerve and sternocleidomastoid muscle
5	External jugular vein
6	Internal jugular vein and common carotid artery
7	Deltoid muscle
8	Axillary vein
9	Right cephalic vein within the deltopectoral groove
10	Right lung (middle lobe)
11	Serratus anterior muscle and lateral thoracic vein
12	Cephalic vein on forearm
13	Venous network on dorsum of hand
14	Dorsal metacarpal veins
15	Facial artery and vein
16	Submandibular gland
17	Anterior jugular vein, hyoid bone, and omohyoid muscle
18	Jugular venous arch and thyroid gland
19	Right and left brachiocephalic veins
20	Retrosternal body (remnant of thymus gland)
21	Internal thoracic artery and vein
22	Heart with pericardium
23	Right venous angle
24	Brachial vein
25	Basilic vein
26	Median cubital vein
27	Digital veins



Main branches of radial and axillary nerves (right side). The posterior trunk of brachial plexus is indicated in orange.



Main branches of musculocutaneous, median, and ulnar nerves (right side). The posterior trunk of brachial plexus is indicated in orange.

1 Brachial plexus
2 Lateral cord of brachial plexus
3 Posterior cord of brachial plexus
4 Medial cord of brachial plexus
5 Axillary nerve
6 Radial nerve
7 Posterior cutaneous nerve of arm
8 Lower lateral cutaneous nerve of arm
9 Posterior cutaneous nerve of forearm
10 Superficial branch of radial nerve
11 Deep branch of radial nerve
12 Dorsal digital nerves

13 Roots of median nerve
14 Musculocutaneous nerve
15 Median nerve
16 Ulnar nerve
17 Medial cutaneous nerves of arm and forearm
18 Lateral cutaneous nerve of forearm
19 Anterior interosseous nerve
20 Palmar branch of median nerve
21 Dorsal branch of ulnar nerve
22 Deep branch of ulnar nerve
23 Common palmar digital nerves of median nerve
24 Superficial branch of ulnar nerve


1
2
C4
3
C5
Th1
10
Th2
Th3
4
Th4
Th5
11
C6
OTT 82
5
6
12
Th1
7
13
C6
14
C8
8
15
C7
9

Cutaneous nerves of the upper limb
(right side, anterior aspect).


19
C6
C7
3
C8
16
Th1
Th2
11
Th3
20
Th4
OTT 82
4
12
21
C8
C6
C7
17
22
18
23

Cutaneous nerves of the upper limb
(right side, posterior aspect).

1 Medial supraclavicular nerve
2 Intermediate supraclavicular nerve
3 Upper lateral cutaneous nerve of arm
4 Terminal branches of intercostobrachial nerves
5 Lower lateral cutaneous nerve of arm
6 Lateral cutaneous nerve of forearm
7 Terminal branch of superficial branch of radial nerve
8 Palmar digital nerve of thumb (branch of median nerve)
9 Palmar digital branches of median nerve
10 Anterior cutaneous branches of intercostal nerves
11 Lateral cutaneous branches of intercostal nerves
12 Medial cutaneous nerve of forearm
13 Palmar cutaneous branch of ulnar nerve
14 Palmar branch of median nerve
15 Palmar digital branches of ulnar nerve
16 Cutaneous branches of dorsal rami of spinal nerves
17 Dorsal branch of ulnar nerve
18 Dorsal digital nerves
19 Posterior supraclavicular nerve
20 Posterior cutaneous nerve of arm
21 Posterior cutaneous nerve of forearm
22 Superficial branch
23 Dorsal digital branches
} from radial nerve



Surface anatomy of the upper limb (right side, posterior aspect).



Surface anatomy of the arm (right side, lateral aspect). The triceps brachii muscle is strongly contracted.

1	Olecranon
2	Extensor muscles of forearm
3	Accessory cephalic vein
4	Tendons of extensor digitorum muscle
5	Dorsal venous network of hand
6	Deltoid muscle
7	Triceps brachii muscle
8	Lateral epicondyle of humerus
9	Brachioradialis muscle
10	Cephalic vein
11	Tendon of abductor pollicis longus muscle
12	Tendon of extensor indicis muscle
13	Sternocleidomastoid muscle
14	Clavicle
15	Lateral head of triceps brachii muscle
16	Medial head of triceps brachii muscle
17	Tendon of triceps brachii muscle



Surface anatomy of the upper limb (right side, anterior aspect).



Superficial veins of the arm (right side, anterior aspect). The veins have been injected with blue gelatin.

1 Trapezius muscle
2 Clavicle
3 Deltopectoral triangle
4 Pectoralis major muscle
5 Deltoid muscle
6 Brachial vein
7 Biceps brachii muscle
8 Median cubital vein
9 Cephalic vein
10 Median vein of forearm
11 Tendon of flexor carpi radialis
12 Tendon of palmaris longus muscle
13 Location of adductor pollicis muscle
14 Accessory cephalic vein
15 Basilic vein



Posterior regions of neck and shoulder (left side: superficial layer; right side: trapezius and latissimus dorsi muscles have been removed). Dissection of dorsal branches of spinal nerves.

1	Greater occipital nerve
2	Ligamentum nuchae
3	Splenius capitis muscle
4	Sternocleidomastoid muscle
5	Lesser occipital nerve
6	Splenius cervicis muscle
7	Descending and transverse fibers of trapezius muscle
8	Medial cutaneous branches of dorsal rami of spinal nerves
9	Ascending fibers of trapezius muscle
10	Latissimus dorsi muscle
11	Cutaneous branch of third occipital nerve
12	Great auricular nerve
13	Accessory nerve (n. XI)
14	Posterior supraclavicular nerve and levator scapulae muscle
15	Branches of suprascapular artery
16	Deltoid muscle
17	Rhomboid major muscle
18	Infraspinatus muscle
19	Teres minor muscle
20	Upper lateral cutaneous nerve of arm (branch of axillary nerve)
21	Teres major muscle
22	Medial margin of scapula
23	Long head of triceps muscle
24	Posterior cutaneous nerve of arm (branch of radial nerve)
25	Latissimus dorsi muscle (divided)
26	Ulnar nerve and brachial artery
27	Lateral cutaneous branches of dorsal rami of spinal nerves and iliocostalis thoracis muscle
28	External intercostal muscle and seventh rib
29	Serratus posterior inferior muscle



Posterior region of the shoulder, deepest layer. Rhomboid and scapular muscles have been fenestrated, the posterior part of deltoid muscle has been reflected.

1	Clavicle
2	Deltoid muscle
3	Suprascapular artery
4	Suprascapular nerve
5	Superior transverse scapular ligament
6	Teres minor muscle
7	Axillary nerve and posterior circumflex humeral artery
8	Long head of triceps muscle
9	Circumflex scapular artery
10	Teres major muscle
11	Greater occipital nerve
12	Lesser occipital nerve
13	Great auricular nerve
14	Splenius capitis muscle
15	Accessory nerve (n. XI)
16	Third occipital nerve and levator scapulae muscle
17	Serratus posterior superior muscle
18	Spine of scapula
19	Descending scapular artery and dorsal scapular nerve
20	Rhomboid major muscle
21	Infraspinatus muscle and medial margin of scapula
22	Axillary artery
23	Radial nerve and brachial artery
24	Thoracodorsal artery
25	Thyrocervical trunk
26	Brachial plexus



Collateral circulation of the shoulder (posterior aspect). Anastomosis of suprascapular and circumflex scapular arteries.



Posterior region of the shoulder, deep layer. The arteries of the scapular region have been injected with red gelatin. Trapezius, deltoid, and infraspinatus muscles have been partially removed or reflected.

1 Sternocleidomastoid muscle
2 Lesser occipital nerve
3 Splenius capitis muscle and third occipital nerve
4 Accessory nerve (n. XI)
5 Splenius cervicis muscle and transverse cervical artery (deep branch)
6 Levator scapulae muscle
7 Transverse cervical artery (superficial branch)
8 Spine of scapula and serratus posterior superior muscle
9 Rhomboid major muscle
10 Trapezius muscle
11 Latissimus dorsi muscle
12 Facial artery
13 Acromion
14 Deltoid muscle
15 Suprascapular artery and supraspinatus muscle (reflected)
16 Axillary nerve, posterior circumflex humeral artery, and lateral head of triceps brachii muscle
17 Teres minor muscle
18 Long head of triceps brachii muscle
19 Circumflex scapular artery and teres major muscle
20 Infraspinatus muscle



Anterior regions of shoulder and thoracic wall, superficial layer. Dissection of the cutaneous nerves and veins.

1 Trapezius muscle
2 Posterior supraclavicular nerve
3 Middle supraclavicular nerve
4 Deltopectoral triangle
5 Deltoid muscle
6 Cephalic vein within the deltopectoral groove
7 Upper lateral cutaneous nerve of arm (branch of axillary nerve)
8 Latissimus dorsi muscle
9 Cephalic vein
10 Biceps brachii muscle
11 Triceps brachii muscle
12 Lateral cutaneous branches of intercostal nerves
13 Transverse cervical nerve and external jugular vein
14 Sternocleidomastoid muscle
15 Anterior jugular vein
16 Anterior supraclavicular nerve
17 Clavicle
18 Clavicular part of pectoralis major muscle
19 Sternocostal part of pectoralis major muscle
20 Perforating branch of internal thoracic artery
21 Anterior cutaneous branches of intercostal nerves
22 Abdominal part of pectoralis major muscle
23 Sternocleidomastoid muscle, cervical branch of facial nerve, and anterior jugular vein
24 External jugular vein and transverse cervical nerve (inferior branch)
25 Sternoclavicular joint (opened) with articular disc
26 Pectoralis major muscle
27 Omohyoid muscle and external jugular vein
28 Jugular venous arch and sternohyoid muscle
29 Sternoclavicular joint (not opened)



Anterior regions of thoracic wall and neck. The sternoclavicular joint is depicted. On the right side the joint has been opened by a coronal section. Note the articular disc.



Deltopectoral triangle and infraclavicular region (anterior aspect). The pectoralis major muscle has been cut and reflected.



Anterior regions of shoulder and thoracic wall with axillary region, deep layer. The pectoralis major muscle has been cut and partly removed.

1 Accessory nerve
2 Trapezius muscle
3 Pectoralis major muscle (clavicular part)
4 Acromial branch of thoraco-acromial artery
5 Pectoralis major muscle
6 Lateral pectoral nerves
7 Abdominal part of pectoralis major muscle
8 External jugular vein
9 Cutaneous branches of cervical plexus
10 Sternocleidomastoid muscle
11 Clavicle
12 Clavipectoral fascia
13 Cephalic vein
14 Subclavius muscle
15 Clavicular branch of thoraco-acromial artery
16 Subclavian vein
17 Thoraco-acromial artery
18 Pectoral branch of thoraco-acromial artery
19 Medial pectoral nerve
20 Second rib
21 Pectoralis minor muscle
22 Third rib
23 Deltoid muscle
24 Pectoralis major muscle (reflected), brachial artery, and median nerve
25 Short head of biceps brachii muscle
26 Thoracodorsal artery and nerve
27 Medial cutaneous nerve of arm
28 Intercostobrachial nerve (Th$_2$)
29 Long head of biceps brachii muscle
30 Medial cutaneous nerve of forearm
31 Latissimus dorsi muscle
32 Lateral cutaneous branches of intercostal nerves (posterior branches)
33 Serratus anterior muscle
34 Medial pectoral nerve
35 Long thoracic nerve and lateral thoracic artery
36 Intercostobrachial nerve (Th$_3$)
37 Lateral cutaneous branches of intercostal nerves (anterior branches)



Shoulder and arm (posterior aspect). Dissection of the quadrangular and triangular spaces of the axillary region.



Shoulder region and arm, superficial layer (posterior aspect). Note the segmental arrangement of the cutaneous nerves of the back.



Course of vessels and nerves at the shoulder region and arm (posterior aspect).

1 Trapezius muscle
2 Dorsal branches of posterior intercostal artery and vein (medial cutaneous branches)
3 Medial branches of dorsal rami of spinal nerves
4 Rhomboid major muscle
5 Lateral branches of dorsal rami of spinal nerves
6 Latissimus dorsi muscle
7 Posterior supraclavicular nerves
8 Spine of scapula
9 Deltoid muscle
10 Infraspinatus muscle
11 Teres minor muscle
12 Triangular space with circumflex scapular artery and vein
13 Upper lateral cutaneous nerve of arm with artery
14 Teres major muscle
15 Terminal branches of intercostobrachial nerve
16 Medial cutaneous nerve of arm
17 Tendon of triceps brachii muscle
18 Lateral cutaneous branches of intercostal nerves
19 Medial cutaneous nerve of forearm
20 Long head of triceps brachii muscle
21 Quadrangular space with axillary nerve and posterior humeral circumflex artery
22 Anastomosis between profunda brachii artery and posterior humeral circumflex artery
23 Course of radial nerve and profunda brachii artery
24 Lateral head of triceps brachii muscle
25 Medial collateral artery
26 Radial collateral artery
27 Radial nerve



Shoulder region and arm, deep layer (posterior aspect). Part of deltoid muscle has been cut and reflected to display the quadrangular and triangular spaces of the axillary region.



Shoulder region and arm, deep layer (posterior aspect). The lateral head of the triceps brachii muscle has been cut to display the radial nerve and accompanying vessels.

1 Trapezius muscle
2 Spine of scapula
3 Infraspinatus muscle
4 Teres minor muscle
5 Triangular space containing circumflex scapular artery and vein
6 Teres major muscle
7 Latissimus dorsi muscle
8 Deltoid muscle (cut and reflected)
9 Quadrangular space containing axillary nerve and posterior circumflex humeral artery and vein
10 Long head of triceps brachii muscle
11 Cutaneous branch of axillary nerve
12 Lateral head of triceps brachii muscle
13 Terminal branches of intercostobrachial nerve
14 Lateral cutaneous branches of intercostal nerves
15 Medial cutaneous nerve of arm
16 Medial cutaneous nerve of forearm
17 Upper lateral cutaneous nerve of arm
18 Anastomosis between profunda brachii artery and posterior humeral circumflex artery
19 Humerus
20 Profunda brachii artery
21 Radial nerve
22 Radial collateral artery
23 Middle collateral artery
24 Lower lateral cutaneous nerve of arm
25 Posterior cutaneous nerve of forearm
26 Tendon of triceps brachii muscle



Axillary region (right side, inferior aspect). Dissection of superficial axillary lymph nodes and lymphatic vessels. The pectoralis major muscle has been slightly elevated.

1 Deltoid muscle
2 Cephalic vein
3 Median nerve
4 Brachial artery
5 Medial cutaneous nerves of arm and forearm
6 Ulnar nerve
7 Basilic vein
8 Intercostobrachial nerves
9 Circumflex scapular artery
10 Superficial axillary lymph nodes
11 Lateral thoracic artery
12 Thoracodorsal artery
13 Lateral cutaneous branch of intercostal nerve
14 Latissimus dorsi muscle
15 Thoraco-epigastric vein
16 Serratus anterior muscle
17 Musculocutaneous nerve
18 Radial nerve
19 Pectoralis major muscle
20 Nipple



Axillary region (right side, anterior aspect). Dissection of deep axillary lymph nodes. Pectoralis major and minor muscles have been divided and reflected. Shoulder girdle and arm have been elevated and reflected.

1	Deltoid muscle
2	Insertion of pectoralis major muscle
3	Coracobrachialis muscle
4	Roots of median nerve and axillary artery
5	Short head of biceps brachii muscle
6	Ulnar nerve and medial cutaneous nerve of forearm
7	Thoraco-epigastric vein
8	Deep axillary lymph nodes
9	Latissimus dorsi muscle
10	Serratus anterior muscle
11	Cephalic vein
12	Insertion of pectoralis minor muscle (coracoid process)
13	Musculocutaneous nerve
14	Subclavius muscle
15	Thoraco-acromial artery
16	Axillary vein
17	Clavicle
18	Pectoralis major and minor muscles (reflected)
19	Nipple
20	Anterior cutaneous branches of intercostal nerves
21	Anterior layer of rectus sheath

112897_S_409_445_Kap_7:_ 06.11.2014 10:55 Uhr Seite 424



Axillary region (right side, anterior aspect). Pectoralis major and minor muscles have been cut and reflected to display the vessels and nerves of the axilla.

1 Sternocleidomastoid muscle (cut and reflected)
2 Cervical plexus
3 Trapezius muscle
4 Pectoralis minor muscle and medial pectoral nerve
5 Deltoid muscle
6 Pectoralis major muscle and lateral pectoral nerve
7 Median nerve and brachial artery
8 Circumflex scapular artery
9 Short head of biceps brachii muscle
10 Thoracodorsal artery and nerve
11 Long head of biceps brachii muscle
12 Latissimus dorsi muscle
13 Serratus anterior muscle
14 Internal jugular vein
15 Anterior scalene muscle
16 Phrenic nerve and ascending cervical artery
17 Brachial plexus (at the levels of the trunks)
18 Clavicle
19 Subclavius muscle
20 Thoraco-acromial artery
21 Subclavian vein (cut)
22 Axillary artery
23 Subscapular artery
24 Superior thoracic artery
25 Lateral thoracic artery and long thoracic nerve
26 External intercostal muscle
27 Insertion of pectoralis minor muscle
28 Intercostobrachial nerves
29 Lateral cutaneous branches of intercostal nerves
30 Insertion of pectoralis major muscle



Brachial plexus (anterior aspect). The clavicle and the two pectoralis muscles have been partly removed.



Main branches of brachial plexus. Posterior cord in orange, lateral cord in ocher, and medial cord in light yellow.

1	Accessory nerve
2	Dorsal scapular artery
3	Suprascapular nerve
4	Clavicle and pectoralis minor muscle
5	Lateral cord of brachial plexus
6	Musculocutaneous nerve
7	Axillary nerve
8	Median nerve
9	Brachial artery
10	Radial nerve
11	Cervical plexus
12	Common carotid artery
13	Roots of brachial plexus (C_5–Th_1)
14	Phrenic nerve
15	Transverse cervical artery
16	Subclavian artery
17	Posterior cord of brachial plexus
18	Medial cord of brachial plexus
19	Subscapular artery
20	Long thoracic nerve
21	Ulnar nerve
22	Medial cutaneous nerve of forearm
23	Thoracodorsal nerve
24	Intercostobrachial nerves
25	Medial cutaneous nerves of arm and forearm
26	Anterior scalene muscle
27	Middle scalene muscle
28	Intercostal nerve (Th_3)
29	Axillary artery
30	Suprascapular artery



1	Ascending cervical artery	13	Deep branch of radialis nerve
2	Vertebral artery	14	Superficial branch of radialis nerve
3	Transverse cervical artery	15	Flexor carpi radialis muscle
4	Suprascapular artery and nerve	16	Radial artery
5	Deltoid muscle	17	Common carotid artery
6	Musculocutaneous nerve	18	Brachiocephalic trunk
7	Axillary nerve	19	Subclavian artery
8	Radial nerve	20	Brachial plexus
9	Ulnar nerve	21	Axillary artery
10	Median nerve	22	Intercostobrachial nerve
11	Biceps brachii muscle	23	Brachial artery
12	Brachioradialis muscle	24	Latissimus dorsi muscle

Neck and arm with dissection of nerves and arteries (right side, anterior aspect). The arteries have been colored in red. The course of the radial nerve has been indicated by a wire probe (arrow).



Arm with dissection of nerves and vessels (right side, anterior aspect). The shoulder girdle has been reflected slightly.



Arm with dissection of nerves and vessels, deeper layer (right side, antero-inferior aspect). The biceps brachii muscle has been reflected.

1 Radial artery and superficial branch of radial nerve
2 Lateral cutaneous nerve of forearm
3 Brachioradialis muscle
4 Ulnar artery
5 Tendon of biceps brachii muscle
6 Brachialis muscle
7 Pronator teres muscle
8 Median nerve
9 Medial epicondyle of humerus
10 Inferior ulnar collateral artery
11 Ulnar nerve
12 Medial cutaneous nerve of forearm
13 Brachial artery
14 Biceps brachii muscle
15 Intercostobrachial nerve (Th_3)
16 Latissimus dorsi muscle
17 Thoracodorsal nerve and artery
18 Serratus anterior muscle
19 Subscapular artery
20 Pectoralis major muscle (reflected) and lateral pectoral nerve
21 Radial nerve and profunda brachii artery
22 Axillary nerve
23 Roots of the median nerve with axillary artery
24 Musculocutaneous nerve
25 Pectoralis minor muscle (reflected) and medial pectoral nerve
26 Posterior cord of brachial plexus
27 Clavicle (cut)
28 Lateral cord of brachial plexus
29 Medial cord of brachial plexus
30 Subclavian artery
31 Brachial vein



Cubital region (anterior aspect). Dissection of cutaneous nerves and veins.



Cubital region, superficial layer (anterior aspect). The fasciae of the muscles have been removed.

1 Biceps brachii muscle with fascia
2 Cephalic vein
3 Median cubital vein
4 Lateral cutaneous nerve of forearm
5 Tendon and aponeurosis of biceps brachii muscle (covered by the antebrachial fascia)
6 Brachioradialis muscle with fascia
7 Accessory cephalic vein
8 Median vein of forearm
9 Branches of lateral cutaneous nerve of forearm
10 Terminal branches of medial cutaneous nerve of arm
11 Medial cutaneous nerve of forearm
12 Basilic vein
13 Medial epicondyle of humerus
14 Terminal branches of medial cutaneous nerve of forearm
15 Biceps brachii muscle

16 Tendon of biceps brachii muscle
17 Radial nerve
18 Brachioradialis muscle
19 Radial recurrent artery
20 Radial artery
21 Ulnar nerve
22 Superior ulnar collateral artery
23 Medial intermuscular septum
24 Brachial artery
25 Median nerve
26 Pronator teres muscle
27 Bicipital aponeurosis
28 Ulnar artery
29 Palmaris longus muscle
30 Flexor carpi radialis muscle
31 Flexor digitorum superficialis muscle
32 Flexor carpi ulnaris muscle



Cubital region, middle layer (anterior aspect). The bicipital aponeurosis has been removed.



Cubital region, middle layer (anterior aspect). Pronator teres and brachioradialis muscles have been slightly reflected.

1 Median nerve
2 Biceps brachii muscle
3 Brachial artery
4 Lateral cutaneous nerve of forearm (terminal branch of musculocutaneous nerve)
5 Brachialis muscle
6 Tendon of biceps brachii muscle
7 Brachioradialis muscle
8 Radial artery
9 Ulnar artery
10 Superficial branch of radial nerve
11 Lateral cutaneous nerve of forearm
12 Medial cutaneous nerve of forearm
13 Triceps brachii muscle
14 Ulnar nerve
15 Inferior ulnar collateral artery
16 Anterior branch of medial cutaneous nerve of forearm
17 Medial epicondyle of humerus
18 Median nerve with branches to pronator teres muscle
19 Pronator teres muscle
20 Flexor carpi radialis muscle
21 Deep branch of radial nerve
22 Radial recurrent artery
23 Supinator muscle
24 Medial intermuscular septum of arm



Cubital region, deep layer (anterior aspect). Pronator teres and flexor carpi ulnaris muscles have been cut and reflected.



Cubital region, deepest layer (anterior aspect). Flexor digitorum superficialis muscle and the ulnar head of the pronator teres muscle have been cut and reflected.

1 Biceps brachii muscle
2 Brachialis muscle
3 Brachioradialis muscle
4 Superficial branch of radial nerve
5 Deep branch of radial nerve
6 Tendon of biceps brachii muscle
7 Radial recurrent artery
8 Supinator muscle
9 Insertion of pronator teres muscle
10 Radial artery
11 Ulnar nerve
12 Medial intermuscular septum of arm and superior ulnar collateral artery
13 Brachial artery
14 Median nerve
15 Medial epicondyle of humerus
16 Humeral head of pronator teres muscle
17 Ulnar artery
18 Ulnar head of pronator teres muscle
19 Ulnar recurrent artery
20 Anterior interosseous nerve
21 Common interosseous artery
22 Tendinous arch of flexor digitorum superficialis muscle
23 Anterior interosseous artery
24 Flexor digitorum superficialis muscle
25 Flexor digitorum profundus muscle
26 Flexor pollicis longus muscle



1 Radial artery
2 Basilic vein
3 Pronator teres muscle
4 Flexor carpi radialis muscle
5 Ulnar artery
6 Palmaris longus muscle
7 Median nerve
8 Tendon of biceps brachii muscle
9 Flexor digitorum superficialis muscle
10 Ulnar nerve
11 Tendon of brachialis muscle
12 Flexor carpi ulnaris muscle
13 Flexor digitorum profundus muscle
14 Ulna
15 Median cubital vein
16 Cephalic antebrachii vein
17 Radial vein
18 Brachioradialis muscle
19 Superficial branch of radial nerve, radial artery and vein
20 Extensor carpi radialis longus muscle
21 Extensor carpi radialis brevis muscle
22 Supinator muscle
23 Deep branch of radial nerve
24 Radius
25 Extensor digitorum muscle
26 Extensor carpi ulnaris muscle
27 Anconeus muscle

Axial section through the forearm distally of the elbow joint revealing the arrangement of muscles, nerves, and vessels (compare with the MRI scan below).



Axial section through the forearm distally of the elbow joint (MRI scan). (From Heuck et al., MRT-Atlas, 2009.) For details see schematic drawing above.



Posterior regions of forearm and hand with superficial veins and cutaneous nerves (right side).



Course of the nerves to forearm and hand (posterior aspect). Yellow = radial and ulnar nerves.

1	Cephalic vein
2	Brachioradialis muscle covered by its fascia
3	Posterior cutaneous nerve of forearm (branch of radial nerve)
4	Cephalic vein of forearm
5	Extensor pollicis longus and brevis muscles covered by their fascia
6	Median cubital vein
7	Lateral cutaneous nerves of forearm (branch of musculocutaneous nerve)
8	Intermedian vein of forearm
9	Superficial branch of radial nerve
10	Dorsal digital branches of radial nerve
11	Triceps brachii muscle
12	Dorsal venous network of hand
13	Olecranon
14	Anconeus muscle
15	Extensor digitorum and extensor digiti minimi muscles
16	Supinator muscle
17	Flexor carpi ulnaris muscle
18	Extensor carpi ulnaris muscle
19	Extensor indicis muscle
20	Biceps brachii muscle
21	Brachialis muscle
22	Brachioradialis muscle
23	Supinator channel
24	Deep branch of radial nerve
25	Extensor carpi radialis brevis muscle
26	Extensor carpi radialis longus muscle
27	Abductor pollicis longus muscle
28	Extensor pollicis longus muscle
29	Extensor pollicis brevis muscle
30	Posterior interosseus nerve
31	Ulnar nerve
32	Extensor retinaculum



Posterior region of the forearm with vessels and nerves, superficial layer (right side).



Posterior region of the forearm with vessels and nerves, deep layer (right side).

1 Tendon of triceps brachii muscle
2 Olecranon
3 Anconeus muscle
4 Extensor digitorum muscle
5 Extensor carpi ulnaris muscle
6 Deep branch of radial nerve
7 Posterior interosseous artery
8 Extensor pollicis longus muscle
9 Extensor indicis muscle
10 Tendon of extensor carpi ulnaris muscle
11 Extensor retinaculum
12 Dorsal branch of ulnar nerve
13 Biceps brachii muscle
14 Brachialis muscle
15 Brachioradialis muscle
16 Lateral epicondyle of humerus
17 Extensor carpi radialis longus muscle
18 Extensor carpi radialis brevis muscle
19 Abductor pollicis longus muscle
20 Tendons of extensor digitorum muscle
21 Extensor pollicis brevis muscle
22 Superficial branch of radial nerve
23 Radial artery
24 Posterior interosseous nerve
25 Posterior interosseous branch of radial nerve
26 Posterior branch of anterior interosseous artery
27 Supinator muscle


1
2
3
5
3
6
6
7
6
9
11
12
13
14
15
16
7
17
18
19
20
21
22
23
24
25
20
26
27
28
29
32
34

Anterior regions of forearm and hand with vessels and nerves, superficial layer (right side).


1
2
3
4
5
6
7
6
8
9
10
11
12
13
14
15
16
7
17
18
20
22
23
13
24
25
13
20
26
27
30
31
33
34

Anterior regions of forearm and hand with vessels and nerves, superficial layer (right side). The palmar aponeurosis of the hand and the bicipital aponeurosis have been removed.



Anterior regions of forearm and hand with vessels and nerves, deep layer (right side). The superficial layer of the flexor muscles has been removed.

1 Biceps brachii muscle
2 Brachialis muscle
3 Brachioradialis muscle
4 Deep branch of radial nerve
5 Superficial branch of radial nerve
6 Radial artery
7 Median nerve
8 Flexor retinaculum
9 Thenar muscles
10 Common palmar digital nerves of median nerve
11 Common palmar digital arteries
12 Proper palmar digital nerves of median nerve
13 Ulnar nerve
14 Medial intermuscular septum of arm
15 Superior ulnar collateral artery
16 Brachial artery
17 Medial epicondyle of humerus
18 Pronator teres muscle
19 Bicipital aponeurosis
20 Ulnar artery
21 Palmaris longus muscle
22 Flexor carpi radialis muscle
23 Flexor digitorum superficialis muscle
24 Flexor carpi ulnaris muscle
25 Tendon of palmaris longus muscle
26 Remnant of antebrachial fascia
27 Superficial branch of ulnar nerve
28 Palmaris brevis muscle
29 Palmar aponeurosis
30 Hypothenar muscles
31 Superficial palmar arch
32 Superficial transverse metacarpal ligament
33 Common palmar digital branch of ulnar nerve
34 Proper palmar digital branches of ulnar nerve
35 Anterior interosseous artery and nerve
36 Flexor digitorum profundus muscle
37 Common palmar digital arteries
38 Palmar branch of median nerve
39 Flexor pollicis longus muscle
40 Palmar cutaneous branch of ulnar nerve



Innervation pattern of the hand (palmar aspect). 3½ digits by median nerve, 1½ digits by ulnar nerve.



Dorsum of the right hand, superficial layer. Cutaneous nerves and veins are depicted.



Dorsum of the right hand, deeper layer. Extensor digitorum muscle has been partly removed.



Innervation pattern of the hand (dorsal aspect). 2½ digits by radial nerve, 2½ digits by ulnar nerve. Note that the terminal branches to the dorsal surfaces of the distal phalanges are derived from the palmar digital nerves. The cutaneous distribution varies; often 3½ digits are innervated by the radial and 1½ digits by the ulnar nerve.

1 Posterior cutaneous nerve of forearm (branch of radial nerve)
2 Extensor digitorum muscle
3 Tendon of extensor carpi ulnaris muscle
4 Extensor retinaculum
5 Ulnar nerve
6 Dorsal venous network of hand
7 Abductor pollicis brevis muscle
8 Cephalic vein
9 Extensor pollicis brevis muscle
10 Superficial branch of radial nerve
11 Radial artery
12 Tendon of extensor pollicis longus muscle
13 Dorsal digital branches of radial nerve
14 Tendons of extensor digitorum muscle with intertendinous connections
15 Posterior interosseus nerve (branch of the deep radial nerve)
16 Posterior interosseous artery
17 Styloid process of ulna
18 Dorsal interosseus muscle
19 Dorsal carpal branch of radial artery
20 Lateral cutaneous nerve of forearm (branch of musculocutaneous nerve)
21 Dorsal metacarpal artery
22 Dorsal digital branches of ulnar nerve
23 Regions supplied by palmar digital nerves (ulnar nerve)
24 Regions supplied by palmar digital nerves (median nerve)
25 Communicating branch with ulnar nerve



1	Extensor digiti minimi muscle
2	Extensor carpi ulnaris muscle
3	Extensor retinaculum
4	Basilic vein
5	Dorsal branch of ulnar nerve
6	Dorsal carpal branch of ulnar artery
7	Dorsal venous network of hand
8	Dorsal metacarpal arteries
9	Dorsal metacarpal veins
10	Dorsal digital veins
11	Lateral cutaneous nerve of forearm
12	Posterior cutaneous nerve of forearm
13	Abductor pollicis longus muscle
14	Abductor pollicis brevis muscle
15	Cephalic vein
16	Superficial branch of radial nerve
17	Radial artery
18	Dorsal digital branches of radial nerve
19	Dorsal digital nerves for the fingers
20	Hamate bone
21	Capitate bone
22	Dorsal interossei muscles
23	Collateral ligament
24	Proximal phalanges II–V
25	Middle phalanges II–V
26	Distal phalanges IV and V
27	Os trapezoideum
28	Metacarpal bones II–IV
29	Opponens pollicis muscle
30	Second metacarpophalangeal joint
31	Proper palmar digital artery

Dorsum of the right hand, superficial layer. Cutaneous veins, nerves, and arteries are depicted. The dorsal fascia of the hand has been removed.



Coronal section through the right hand (dorsal aspect). (From Heuck et al., MRT-Atlas, 2009.) For details see the schematic drawing alongside.



Coronal section through the left hand at the level of the interossei muscles (dorsal aspect).



Coronal section through the left hand at the level of the interossei muscles (dorsal aspect; MRI scan). (Courtesy of Prof. Heuck, Munich, Germany.)

1 Radius
2 Radiocarpal joint
3 Scaphoid (navicular) bone
4 Radial artery
5 Trapezoid bone
6 Trapezium bone
7 First metacarpal bone
8 Metacarpophalangeal joint of thumb
9 Interossei muscles
10 Proximal phalanx of thumb
11 Proximal phalanx of fingers
12 Interphalangeal joints
13 Middle phalanx
14 Distal phalanx
15 Ulna
16 Distal radio-ulnar joint
17 Articular disc
18 Lunate bone
19 Triquetral bone
20 Capitate bone
21 Hamate bone
22 Carpometacarpal joints
23 Abductor digiti minimi muscle
24 Fifth metacarpal bone
25 Metacarpophalangeal joint
26 Adductor pollicis muscle
27 Proper palmar digital arteries



Coronal section through the left hand at the level of the interossei muscles (dorsal aspect).



Axial section through the right hand at the level of the carpal tunnel (proximal aspect).



Axial section through the right hand at the level of the carpal tunnel (proximal aspect; MRI scan). (Courtesy of Prof. Heuck, Munich, Germany.)

1 Radius
2 Radiocarpal joint
3 Scaphoid (navicular) bone
4 Metacarpal joint
5 Trapezium bone
6 Trapezoid bone
7 Opponens pollicis muscle
8 First metacarpal bone
9 First metacarpophalangeal joint
10 Interossei muscles
11 Proximal phalanx of thumb
12 Proximal phalanx of fingers
13 Interphalangeal joints
14 Middle phalanx
15 Distal phalanx
16 Ulna
17 Distal radio-ulnar joint
18 Articular disc
19 Ulnar collateral ligament
20 Lunate bone
21 Pisiforme bone
22 Triquetral bone
23 Capitate bone
24 Hamate bone
25 Carpometacarpal joints
26 Abductor digiti minimi muscle
27 Fifth metacarpal bone
28 Metacarpophalangeal joints
29 Trapezium and trapezoid bones
30 Radial artery
31 Tendons of flexor digitorum superficialis and profundus muscles
32 First metacarpal bone
33 Median nerve
34 Flexor retinaculum
35 Thenar muscles
36 Hypothenar muscles
37 Ulnar artery and nerve
38 Carpal tunnel
39 Second and third metacarpal bones
40 Adductor pollicis muscle


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27


1
4
3
32
19
8
31
12
14
34
16
43
18
30
23
25
27
35

Palm of the right hand with arteries and nerves.

◁

Anterior region of wrist and palm of the right hand, superficial layer.


38
39
44
40
41
42

Longitudinal section through the hand at the level of the third finger.


36
37
38
39
24
40
41
42

Longitudinal section through the hand at the level of the third finger (MRI scan). (Courtesy of Prof. Heuck, Munich, Germany.)



Palm of the right hand, middle layer. The flexor retinaculum has been removed.



Arteriogram of the right hand (palmar aspect).

1 Superficial branch of radial nerve
2 Tendon of flexor carpi radialis muscle
3 Radial artery
4 Median nerve
5 Tendon of flexor digitorum superficialis muscle
6 Tendon of abductor pollicis longus muscle
7 Tendon of extensor pollicis brevis muscle
8 Superficial palmar branch of radial artery
9 Abductor pollicis brevis muscle
10 Superficial head of flexor pollicis brevis muscle
11 Terminal branches of superficial branch of radial nerve
12 Common palmar digital nerves (median nerve)
13 Proper palmar digital arteries of thumb
14 Proper palmar digital nerves (median nerve)
15 Tendon of flexor carpi ulnaris muscle
16 Ulnar artery
17 Position of pisiform bone
18 Superficial branch of ulnar nerve
19 Flexor retinaculum
20 Deep branch of ulnar nerve
21 Abductor digiti minimi muscle
22 Common palmar digital nerve (ulnar nerve)
23 Superficial palmar arch
24 Tendons of flexor digitorum muscles
25 Common palmar digital arteries
26 Palmar digital nerves (ulnar nerve)
27 Proper palmar digital arteries
28 Carpal tunnel
29 Fibrous sheaths for the tendons of flexor digitorum muscles
30 Deep palmar arch
31 Princeps pollicis artery
32 Palmar branch of median nerve
33 Common digital palmar artery
34 Ulnar nerve
35 Capillary network of fingers
36 Radius
37 Carpal bones
38 Metacarpal bone
39 Interossei muscles
40 Proximal phalanx
41 Middle phalanx
42 Distal phalanx
43 Dorsal branch of ulnar nerve
44 Tendons of flexor digitorum profundus (upper) and superficialis (lower) muscles



Palm of the right hand, superficial layer. Dissection of vessels and nerves.



Palm of the right hand, superficial layer. Dissection of vessels and nerves. The palmar aponeurosis has been removed to display the superficial palmar arch.

1 Tendon of palmaris longus muscle
2 Radial artery
3 Tendon of flexor carpi radialis muscle and median nerve
4 Distal part of antebrachial fascia
5 Radial artery passing into the anatomical snuffbox
6 Abductor pollicis brevis muscle
7 Superficial head of flexor pollicis brevis muscle
8 Palmar digital artery of thumb
9 Common palmar digital arteries
10 Proper palmar digital nerves (median nerve)
11 Ulnar nerve
12 Tendon of flexor carpi ulnaris muscle
13 Ulnar artery
14 Superficial branch of ulnar nerve
15 Palmaris brevis muscle
16 Palmar aponeurosis
17 Palmar digital nerves (ulnar nerve)
18 Superficial transverse metacarpal ligament
19 Proper palmar digital arteries
20 Superficial palmar branch of radial artery (contributing to the superficial palmar arch)
21 Flexor retinaculum
22 Median nerve
23 Abductor digiti minimi muscle
24 Flexor digiti minimi brevis muscle
25 Opponens digiti minimi muscle
26 Superficial palmar arch
27 Tendons of flexor digitorum superficialis muscle
28 Common palmar digital branch of ulnar nerve
29 Common palmar digital branches of median nerve
30 Fibrous sheaths of tendons of flexor muscles



Anterior region of wrist and palm of the right hand, deep layer. The carpal tunnel has been opened, the tendons of the flexor muscles have been removed, and the superficial palmar arch has been cut.



Anterior region of wrist and palm of the right hand, deep layer. Dissection of the deep palmar arch.

1 Tendon of flexor carpi radialis muscle
2 Radial artery
3 Tendon of abductor pollicis longus muscle
4 Abductor pollicis brevis muscle
5 Superficial and deep heads of flexor pollicis brevis muscle
6 Oblique and transverse heads of adductor pollicis muscle
7 Median nerve
8 Tendons of flexor digitorum superficialis and profundus muscles
9 Tendon of flexor pollicis longus muscle
10 Pronator quadratus muscle
11 Tendon of flexor carpi ulnaris muscle
12 Ulnar artery
13 Superficial branch of ulnar nerve
14 Deep branch of ulnar nerve
15 Abductor digiti minimi muscle
16 Superficial palmar arch (cut end)
17 Common palmar digital nerve (ulnar nerve)
18 Palmar metacarpal arteries of deep palmar arch
19 Palmar digital artery of the fifth finger
20 Fibrous sheaths of tendons of flexor muscles
21 Palmar interossei muscles
22 Opponens pollicis muscle (cut)
23 Deep palmar arch
24 First dorsal interosseous muscle
25 First lumbrical muscle



Horizontal section through the right shoulder joint. Section 1 (MRI scan, inferior aspect).



Upper limb, location of sections 1–5 (MRI scans, p. 444: courtesy of Prof. Heuck, Munich, Germany; MRI scans, p. 445: courtesy of Prof. Bautz and Dr. Janka, Univ. Erlangen-Nuremberg, Germany).



Horizontal section through the right shoulder joint. Section 1 (inferior aspect). * = Upper lobe of lung.

1 Pectoralis major muscle
2 Greater tubercle and tendon of biceps muscle
3 Lesser tubercle
4 Head of humerus and articular cavity of shoulder joint
5 Deltoid muscle
6 Scapula
7 Infraspinatus muscle
8 Serratus anterior muscle
9 Sternum
10 Infrahyoid muscles
11 Trachea
12 Body of thoracic vertebra
13 Vertebral canal and spinal cord
14 Deep muscles of the back
15 Trapezius muscle
16 Brachialis muscle
17 Radial nerve and profunda brachii artery



Axial section through the middle of the right arm. Section 2 (MRI scan, inferior aspect).



Axial section through the middle of the right arm. Section 2 (inferior aspect).



Axial section through the right elbow joint. Section 3 (MRI scan, inferior aspect).



Axial section through the right elbow joint. Section 3 (inferior aspect).



Axial section through the middle of the right forearm. Section 4 (MRI scan, inferior aspect).



Axial section through the middle of the right forearm. Section 4 (inferior aspect).



Axial section through the right hand at the level of the metacarpus. Section 5 (MRI scan, inferior aspect).



Axial section through the right hand at the level of the metacarpus. Section 5 (inferior aspect).

18	Triceps brachii muscle
19	Cephalic vein
20	Biceps brachii muscle
21	Musculocutaneous nerve
22	Ulnar nerve
23	Median nerve
24	Brachial artery and vein
25	Shaft of humerus
26	Brachioradialis muscle
27	Radial nerve
28	Olecranon and articular cavity of elbow joint
29	Basilic vein
30	Humerus
31	Pronator teres muscle
32	Extensor muscles of forearm
33	Deep branch of radial nerve
34	Anterior interosseus artery and nerve
35	Interosseous membrane
36	Ulna
37	Radius
38	Superficial branch of radial artery
39	Flexor pollicis longus muscle
40	Flexor digitorum superficialis and profundus muscles
41	Ulnar nerve, artery, and vein
42	Flexor carpi ulnaris muscle
43	Radial artery
44	Third and fourth metacarpal bones
45	Carpal tunnel with tendons of flexor digitorum muscles
46	Hypothenar muscles
47	Median nerve
48	Interossei muscles
49	First metacarpal bone
50	Thenar muscles
51	Articular cavity of humeroradial joint

8 Lower Limb

Skeleton of the Pelvic Girdle and Lower Limb 447
Skeleton of the Pelvis 448
Bones of the Pelvis 452
Bones of the Hip Joint 454
Femur 455
Skeleton of the Leg 456
Bones of the Knee Joint 457
Skeleton of the Foot 458
Ligaments of the Pelvis and Hip Joint 460
Knee Joint 462
Ligaments of the Knee Joint 463
Joints of the Ankle 465
Ligaments of the Foot 466
Muscles of the Thigh 468
Muscles of the Leg 473
Muscles of the Leg and Foot 474
Muscles of the Foot 479
Arteries 482
Veins 484
Nerves 486
Surface Anatomy of the Lower Limb 488
Thigh: Anterior Region 490
Gluteal Region 494
Thigh: Posterior Region 496
Knee and Popliteal Fossa 498
Crural Region 501
Crural Region and Foot 504
Foot 507
Sections through the Lower Limb 514



112897_S_446_482_Kap_8:_ 06.11.2014 10:58 Uhr Seite 447


13
1
14
15
2
3
4
16
5
17
18
6
7
8
19
9
10
20
11
12
21

Skeleton of pelvic girdle and lower limb (posterior aspect).


15
14
3
4
6
22
19
9
10
20
21
21

Skeleton of pelvic girdle and lower limb (anterior aspect).

1 Ilium
2 Ischial spine
3 Hip joint
4 Greater trochanter
5 Ischial tuberosity
6 Femur
7 Lateral condyle of femur
8 Lateral condyle of tibia
9 Tibia
10 Fibula
11 Talus
12 Calcaneus
13 Lumbar vertebrae
14 Sacro-iliac joint
15 Sacrum
16 Coccyx
17 Pubic symphysis
18 Ischial tuberosity
19 Knee joint
20 Ankle joint
21 Metatarsal bones
22 Patella



Lumbar vertebrae and skeleton of pelvic girdle with both femurs (anterior aspect).

1 Second and third lumbar vertebrae
2 Intervertebral disc
3 Fifth lumbar vertebra
4 Intervertebral disc between fifth lumbar vertebra and sacrum
5 Sacro-iliac joint
6 Sacrum
7 Anterior superior iliac spine
8 Linea terminalis
9 Coccyx
10 Pubis
11 Neck of femur
12 Pubic symphysis
13 Ischial tuberosity
14 Femur
15 Iliac fossa
16 Ischial spine
17 Head of femur (and localization of hip joint)
18 Greater trochanter
19 Lesser trochanter



Female pelvis (superior aspect). Note the differences between the male and female pelvis, predominantly in the form and dimensions of the sacrum, the superior and inferior apertures, and the alae of the ilium.



Male pelvis (superior aspect). Compare with the female pelvis (depicted above).

1 Superior articular process of sacrum
2 Posterior superior iliac spine
3 Base of sacrum
4 Sacral promontory
5 Coccyx
6 Ischial spine
7 External lip
8 Intermediate line } of iliac crest
9 Internal lip
10 Arcuate line
11 Anterior superior iliac spine

12 Anterior inferior iliac spine
13 Iliopubic eminence
14 Pecten pubis
15 Pubic tubercle
16 Pubic symphysis
17 Sacral canal
18 Ala of sacrum
19 Position of sacro-iliac joint
20 Iliac fossa
21 Linea terminalis
22 Iliac crest



Female pelvis (anterior aspect). Note the differences between the form and dimensions of the male and female pelvis. The female pubic arch is wider than the male. The obturator foramen in the female pelvis is triangular, while that in the male pelvis is ovoid.



Male pelvis (anterior aspect). Compare with the female pelvis (depicted above).

1	Anterior superior iliac spine
2	Iliac fossa
3	Position of sacro-iliac joint
4	Iliopubic eminence
5	Lunate surface of acetabulum
6	Acetabular notch
7	Obturator foramen
8	Ischial tuberosity
9	Pubic arch
10	Anterior inferior iliac spine
11	Sacrum
12	Linea terminalis (at margin of superior aperture)
13	Pubic symphysis
14	Ischial spine
15	Coccyx



Female pelvis (posterior aspect). Note the differences between the female and male pelvis, especially with respect to the inferior aperture, the shape of the sacrum, the two sciatic notches, and the pubic arch.



Male pelvis (posterior aspect). Compare with the female pelvis (depicted above).

1 Iliac crest
2 Sacral canal
3 Posterior gluteal line
4 Posterior superior iliac spine
5 Position of sacro-iliac joint
6 Dorsal sacral foramina
7 Sacral hiatus
8 Obturator foramen
9 Ramus of ischium
10 Coccyx
11 Superior articular process of sacrum
12 Gluteal surface of ilium
13 Median sacral crest
14 Greater sciatic notch
15 Position of acetabulum
16 Ischial spine
17 Lesser sciatic notch
18 Ischial tuberosity



Sacrum (posterior aspect).



Sacrum (anterior aspect).



Sacrum (superior aspect).



Diameters of pelvis (oblique-superior aspect).

1 Superior articular process of sacrum
2 Posterior sacral foramina
3 Sacral hiatus
4 Median sacral crest
5 Lateral sacral crest
6 Sacral tuberosity
7 Intermediate sacral crest
8 Coccyx
9 Base of sacrum
10 Sacral promontory
11 Anterior sacral foramina
12 Lateral part of sacrum (ala)
13 Transverse line of sacrum
14 Sacral canal
15 Linea terminalis
16 True conjugate
17 Diagonal conjugate
18 Transverse diameter
19 Oblique diameter
20 Inferior pelvic aperture or outlet

The pelvic girdle is firmly connected to the vertebral column at the sacro-iliac joint. Therefore, the body can be kept upright more easily even if only one limb is used for support (as in walking). The mobility of the lower limb is more limited than that of the upper limb.



Right hip bone (lateral aspect).



Right hip bone (medial aspect).



Sacrum and coccyx (lateral aspect).

A = Ilium
B = Ischium
C = Pubis

1	Posterior superior iliac spine
2	Posterior gluteal line
3	Posterior inferior iliac spine
4	Greater sciatic notch
5	Ischial spine
6	Lesser sciatic notch
7	Body of ischium
8	Ischial tuberosity
9	Obturator foramen
10	Iliac crest
11	Anterior gluteal line
12	Internal lip of iliac crest
13	External lip of iliac crest
14	Anterior superior iliac spine
15	Inferior gluteal line
16	Anterior inferior iliac spine
17	Lunate surface of acetabulum
18	Acetabular fossa
19	Acetabular notch
20	Pecten pubis
21	Pubic tubercle
22	Body of pubis
23	Iliac fossa
24	Arcuate line
25	Iliopubic eminence
26	Symphysial surface of pubis
27	Auricular surface
28	Pelvic surface of sacrum
29	Superior articular process of sacrum
30	Dorsal sacral foramina
31	Sacral tuberosity
32	Lateral sacral crest
33	Median sacral crest
34	Obturator groove
35	Coccyx



Bones of the right hip joint (anterior aspect).

1 Iliac crest
2 Lateral part of sacrum (ala)
3 Position of sacro-iliac joint
4 Anterior superior iliac spine
5 Linea terminalis
6 Iliopubic eminence
7 Bony margin of acetabulum
8 Head of femur
9 Greater trochanter
10 Neck of femur
11 Intertrochanteric line
12 Shaft of femur
13 Fifth lumbar vertebra
14 Intervertebral disc between fifth lumbar vertebra and sacrum (imitation)
15 Sacral promontory
16 Anterior sacral foramina
17 Pubic tubercle
18 Obturator foramen
19 Ramus of ischium
20 Lesser trochanter
21 Posterior sacral foramina
22 Greater sciatic notch
23 Ischial spine
24 Pubic symphysis
25 Pubis
26 Ischial tuberosity
27 Intertrochanteric crest
28 Symphysial surface

Diameters of the pelvis

A = True conjugate (11–11.5 cm) (conjugata vera)
B = Diagonal conjugate (12.5–13 cm)
C = Largest diameter of pelvis
D = Inferior pelvic aperture
E = Pelvic inclination (60°)



Bones of the right hip joint (posterior aspect).



Inclination and diameters of the female pelvis, right half (medial aspect).

112897_S_446_482_Kap_8:_ 06.11.2014 10:58 Uhr Seite 455


1
2
3
4
5
6
7
8
9
10
11

Right femur (anterior aspect).


7
8
9
10
4
6
11
1
12
13
14
15
16

Right femur (medial aspect).


7
9
12
14
11
16
1
17
18
19
20
5
15
21

Right femur (posterior aspect).

1 Greater trochanter
2 Intertrochanteric line
3 Nutrient foramina
4 Shaft of femur (diaphysis)
5 Lateral epicondyle
6 Patellar surface
7 Head
8 Fovea of head
9 Neck
10 Lesser trochanter
11 Medial epicondyle
12 Pectineal line
13 Linea aspera
14 Popliteal surface
15 Lateral condyle
16 Medial condyle
17 Intertrochanteric crest
18 Third trochanter
19 Medial lip of linea aspera
20 Lateral lip of linea aspera
21 Intercondylar fossa



Bones of the leg. Right tibia and fibula (anterior aspect).



Bones of the leg. Right tibia and fibula (posterior aspect).

1 Lateral condyle of tibia
2 Position of tibiofibular joint
3 Head of fibula
4 Interosseous border of tibia
5 Shaft of fibula
6 Interosseous border of fibula
7 Lateral surface of fibula
8 Position of tibiofibular syndesmosis
9 Lateral malleolus
10 Medial condyle of tibia
11 Tuberosity of tibia
12 Shaft of tibia (diaphysis)
13 Anterior margin of tibia
14 Medial malleolus
15 Inferior articular surface of tibia
16 Intercondylar eminence
17 Soleal line
18 Medial border of tibia
19 Posterior surface of tibia
20 Malleolar sulcus of tibia
21 Malleolar articular surface of fibula
22 Apex of head of fibula
23 Posterior surface of fibula
24 Posterior border of fibula
25 Medial intercondylar tubercle
26 Posterior intercondylar area
27 Anterior intercondylar area
28 Lateral intercondylar tubercle



Upper end of the right tibia with fibula (from above), anterior margin of tibia above. Superior articular surface of tibia.



Bones of the right knee joint
(anterior aspect).



Bones of the right knee joint
(posterior aspect).



Bones of the right knee joint
(lateral aspect).



Right patella (anterior aspect).



Right patella (posterior aspect).

1	Femur
2	Patellar surface of femur
3	Lateral epicondyle of femur
4	Intercondylar eminence of tibia
5	Lateral condyle of tibia
6	Position of tibiofibular joint
7	Head of fibula
8	Tuberosity of tibia
9	Fibula
10	Shaft of tibia
11	Popliteal surface of femur
12	Intercondylar fossa of femur
13	Lateral condyle of femur
14	Patella
15	Base of patella
16	Anterior surface of patella
17	Apex of patella
18	Articular surface of patella


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
27
32

Bones of the right foot (dorsal aspect).


16
17
18
19
20
21
22
23
24
31
25
27
32
1
2
3
4
5
6
7
8
9
10
11
12
33

Bones of the right foot (plantar aspect).


34
35
14
15
12
33
10
32
4
36
37
38
39
40
25
24
21

Bones of the right foot together with tibia and fibula (posterior aspect).

1	Tuberosity of distal phalanx of great toe
2	Distal phalanx of great toe
3	Proximal phalanx of great toe
4	Head of first metatarsal bone
5	First metatarsal bone
6	Base of first metatarsal bone
7	Medial cuneiform bone
8	Intermediate cuneiform bone
9	Position of cuneonavicular joint
10	Navicular bone



Bones of the right foot, tibia, and fibula (lateral aspect).



Bones of the right foot, tibia, and fibula (medial aspect).

11 Position of talocalcaneonavicular joint
12 Head of talus
13 Neck of talus
14 Trochlea of talus
15 Posterior talar process
16 Distal phalanges
17 Middle phalanx
18 Position of interphalangeal joints
19 Proximal phalanges
20 Position of metatarsophalangeal joints
21 Metatarsal bones
22 Position of tarsometatarsal joints
23 Lateral cuneiform bone
24 Tuberosity of fifth metatarsal bone
25 Cuboid bone
26 Position of calcaneocuboid joint
27 Calcaneus
28 Tarsal sinus
29 Lateral malleolar surface of talus
30 Peroneal trochlea of calcaneus
31 Groove for the tendon of peroneus longus muscle
32 Calcaneal tuberosity
33 Sustentaculum tali
34 Tibia
35 Medial malleolus
36 Fibula
37 Position of tibiofibular syndesmosis
38 Position of ankle joint
39 Lateral malleolus
40 Position of subtalar joint



Ligaments of pelvis and hip joint (anterior aspect).

1 Iliolumbar ligament
2 Iliac crest
3 Fifth lumbar vertebra
4 Sacral promontory
5 Anterior superior iliac spine
6 Inguinal ligament
7 Sacrospinous ligament
8 Greater trochanter
9 Iliofemoral ligament (vertical band)
10 Lesser trochanter
11 Fourth lumbar vertebra
12 Iliolumbar and ventral sacro-iliac ligaments
13 Sacrum
14 Iliopectineal arch
15 Iliofemoral ligament (horizontal band)
16 Obturator canal
17 Obturator membrane
18 Greater sciatic foramen
19 Sacrospinous ligament
20 Sacrotuberous ligament
21 Lesser sciatic foramen
22 Ischial tuberosity
23 Ischiofemoral ligament
24 Intertrochanteric crest
25 Femur
26 Articular capsule of hip joint
27 Dorsal sacro-iliac ligaments
28 Coccyx with superficial dorsal sacrococcygeal ligament
29 Head of femur
30 Articular cartilage of head of femur
31 Articular cavity of hip joint
32 Acetabular lip
33 Spongy bone
34 Ligament of head of femur
35 Pubofemoral ligament
36 Zona orbicularis



Ligaments of pelvis and hip joint (right posterior aspect).



Coronal section through the right hip joint (anterior aspect).



Right hip joint, opened (latero-anterior aspect). The ligament of the head of the femur has been divided, and the femur has been posteriorly reflected.

1 Femur
2 Lesser trochanter
3 Neck of femur
4 Head of femur
5 Fovea of head with cut edge of ligament of head
6 Lunate surface of acetabulum
7 Acetabular lip
8 Acetabular fossa
9 Transverse acetabular ligament
10 Inguinal ligament
11 Iliopectineal arch
12 Pubic symphysis
13 Pubis
14 Obturator canal
15 Ligament of head of femur
16 Obturator membrane
17 Ischium
18 Anterior longitudinal ligament (level of fifth lumbar vertebra)
19 Sacral promontory
20 Iliolumbar ligament
21 Iliac crest
22 Anterior superior iliac spine
23 Iliofemoral ligament (horizontal band)
24 Iliofemoral ligament (vertical band)
25 Greater trochanter
26 Pubofemoral ligament
27 Anterior inferior iliac spine
28 Ventral sacro-iliac ligaments
29 Sacrospinous ligament
30 Sacrotuberous ligament
31 Intertrochanteric line
32 Ischiofemoral ligament
33 Zona orbicularis



◁ **Ligaments of pelvis and hip joint** (antero-lateral aspect).



Ligaments of pelvis and hip joint (anterior aspect).



Ligaments of pelvis and hip joint (posterior aspect).



Sagittal section through the knee joint (lateral aspect). Anterior surface to the left.



Sagittal section through the knee joint (MRI scan). (From Heuck et al., MRT-Atlas, 2009.)



Right knee joint and tibiofibular joint with ligaments (lateral aspect). Note the position of the lateral meniscus.



Left knee joint with anterior cruciate ligament (lateral aspect).

1 Femur
2 Quadriceps femoris muscle
3 Suprapatellar bursa and articular cavity
4 Patella
5 Articular cartilage of femur
6 Infrapatellar fat pad
7 Patellar ligament
8 Tibia
9 Tibial nerve
10 Adductor magnus muscle
11 Popliteal vein
12 Semitendinosus muscle
13 Semimembranosus muscle
14 Popliteal artery
15 Gastrocnemius muscle
16 Anterior cruciate ligament
17 Posterior cruciate ligament
18 Popliteus muscle
19 Soleus muscle
20 Lateral epicondyle of femur
21 Fibular collateral ligament
22 Head of fibula
23 Fibula
24 Articular cavity of knee joint
25 Lateral meniscus of knee joint
26 Lateral condyle of tibia
27 Tibiofibular joint



Right knee joint with ligaments (anterior aspect). The patella and articular capsule have been removed and the femur slightly flexed.



Right knee joint with ligaments (posterior aspect). The joint is extended and the articular capsule has been removed.



Articular surface of right tibia, menisci, and cruciate ligaments (superior aspect). Anterior margin of tibia above.

1 Femur
2 Articular capsule with suprapatellar bursa
3 Patellar surface
4 Lateral condyle of femur
5 Lateral meniscus of knee joint
6 Fibular collateral ligament
7 Lateral condyle of tibia (superior articular surface)
8 Fibula
9 Medial condyle of femur
10 Tibial collateral ligament
11 Anterior cruciate ligament
12 Medial meniscus of knee joint
13 Transverse ligament of knee
14 Patellar ligament
15 Common tendon of sartorius, semitendinosus, and gracilis muscles
16 Tibia
17 Posterior cruciate ligament
18 Medial condyle of tibia (superior articular surface)
19 Posterior meniscofemoral ligament
20 Head of fibula
21 Tendon of semimembranosus muscle
22 Posterior attachment of articular capsule of knee joint
23 Lateral epicondyle of femur



Right knee joint, opened (anterior aspect). The patellar ligament with the patella have been reflected.



Coronal section through the knee joint (MRI scan). (From Heuck et al., MRT-Atlas, 2009.)



Ligaments of the right knee joint (anterior aspect).



Ligaments of the right knee joint (posterior aspect).

1	Iliotibial tract
2	Articular muscle of knee
3	Patellar surface
4	Lateral condyle of femur
5	Articular capsule
6	Infrapatellar fat pad
7	Patella (articular surface)
8	Suprapatellar bursa
9	Quadriceps femoris muscle
10	Anterior cruciate ligament
11	Medial condyle of femur
12	Tibial collateral ligament
13	Posterior cruciate ligament
14	Medial epicondyle of femur
15	Intercondylar fossa of femur
16	Fibular collateral ligament
17	Medial meniscus of knee joint
18	Medial intercondylar tubercle
19	Femur
20	Lateral epicondyle of femur
21	Lateral meniscus of knee joint
22	Epiphysial line of tibia
23	Tibia
24	Vastus medialis muscle
25	Vastus lateralis muscle
26	Great saphenous vein
27	Fibula



Sagittal section through the foot at the level of the first phalanx.



Sagittal section through the foot and leg (MRI scan).
(From Heuck et al., MRT-Atlas, 2009.)



Skeleton of the left foot. Joints are indicated in blue.
Red lines = axis of joints.

A = Talocrural joint
B = Talocalcaneonavicular joint
C = Transverse tarsal joint (Chopart joint line)
D = Tarsometatarsal joints (Lisfranc joint line)

1 Tibia
2 Deep flexor muscles of leg
3 Superficial flexor muscles of leg
4 Ankle joint
5 Interosseous talocalcaneal ligament
6 Subtalar joint
7 Calcaneal or Achilles tendon and bursa
8 Calcaneus
9 Vessels and nerves of foot
10 Talus
11 Talocalcaneonavicular joint
12 Navicular bone
13 Cuneonavicular joint
14 Intermediate cuneiform bone
15 First tarsometatarsal joint
16 Metatarsal bones
17 Metatarsophalangeal and interphalangeal joints
18 Quadratus plantae muscle with flexor tendons
19 Flexor digitorum brevis muscle
20 Plantar aponeurosis
21 Tendon of tibialis posterior muscle
22 Tendon of flexor hallucis longus muscle
23 Flexor hallucis brevis muscle
24 Sesamoid bone
25 Cuboid bone
26 Fibula
27 Medial cuneiform bone
28 Lateral cuneiform bone
29 Phalanges



Ligaments of the ankle joint of the right foot (dorsal aspect).



Deep ligaments of the right foot (plantar aspect). The toes have been removed.



Ligaments of the foot. Top view of the talocalcaneonavicular joint. The talus has been rotated to show the articular surfaces of the joint.

1	Tibia
2	Trochlea of talus
3	Medial or deltoid ligament of ankle (posterior tibiotalar part)
4	Talus
5	Sustentaculum tali
6	Navicular bone
7	First metatarsal bone
8	Fibula
9	Posterior tibiofibular ligament
10	Lateral malleolus
11	Posterior talofibular ligament
12	Calcaneofibular ligament
13	Calcaneal tuberosity
14	Plantar tarsometatarsal ligaments
15	Long plantar ligament
16	Plantar cuneonavicular ligaments
17	Plantar calcaneonavicular ligament
18	Articular capsules of interphalangeal joints
19	Articular capsules of metatarsophalangeal joints
20	Second metatarsal bone
21	Axis for inversion and eversion of foot
22	Navicular articular surface of talus
23	Anterior and middle calcaneal surfaces of talus
24	Posterior calcaneal surface of talus
25	Talocalcaneal interosseous ligament
26	Middle talar articular surface of calcaneus
27	Dorsal tarsometatarsal ligaments
28	Talonavicular ligament
29	Articular surface of navicular bone
30	Bifurcate ligament
31	Anterior talar articular surface of calcaneus
32	Posterior talar articular surface of calcaneus
33	Calcaneus
34	Calcaneal or Achilles tendon and bursa



Ligaments of the right foot (lateral aspect).



Ligaments of the right foot (medial aspect).

1 Fibula
2 Tibia
3 Trochlea of talus and ankle joint
4 Anterior tibiofibular ligament
5 Anterior talofibular ligament
6 Lateral malleolus
7 Calcaneofibular ligament
8 Lateral talocalcaneal ligament
9 Subtalar joint
10 Calcaneal tuberosity
11 Interosseous talocalcaneal ligament
12 Bifurcate ligament
13 Long plantar ligament
14 Calcaneocuboid joint
15 Tuberosity of fifth metatarsal bone
16 Dorsal tarsometatarsal ligaments
17 Metatarsal bones
18 Head of talus and talocalcaneonavicular joint
19 Navicular bone
20 Dorsal cuneonavicular ligaments
21 Heads of metatarsal bones
22 Medial or deltoid ligament of ankle (tibionavicular part)
23 Medial or deltoid ligament of ankle (tibiocalcaneal part)
24 Dorsal cuneonavicular ligaments
25 Navicular bone
26 Plantar cuneonavicular ligament
27 First metatarsal bone
28 Head of first metatarsal bone
29 Plantar tarsometatarsal ligaments
30 Plantar calcaneonavicular ligament
31 Sustentaculum tali
32 Calcaneus
33 Medial malleolus
34 Medial or deltoid ligament of ankle (posterior tibiotalar part)
35 Talus



Extensor and adductor muscles of the thigh (right side, anterior aspect).



Quadriceps muscle and superficial layer of adductor muscles of the thigh (right side, anterior aspect). The sartorius muscle has been divided.



Course of the extensor muscles of the thigh and muscles inserting with common tendon on the tibia (anterior aspect).

1 Anterior superior iliac spine
2 Inguinal ligament
3 Iliopsoas muscle
4 Femoral artery
5 Tensor fasciae latae muscle
6 Sartorius muscle
7 Rectus femoris muscle
8 Iliotibial tract
9 Vastus lateralis muscle
10 Patella
11 Patellar ligament

12 Aponeurosis of external abdominal oblique muscle
13 Spermatic cord
14 Femoral vein
15 Pectineus muscle
16 Adductor longus muscle
17 Gracilis muscle
18 Vastus medialis muscle
19 Common tendon of sartorius, gracilis, and semitendinosus muscles (pes anserinus)

20 Adductor brevis muscle
21 Femoral artery } entering the adductor canal
22 Femoral vein }
23 Saphenous nerve }
24 Vasto-adductor membrane
25 Vastus intermedius muscle
26 Articularis genus muscle
27 Semitendinosus muscle



Course of the adductor muscles of the thigh (anterior aspect).

1 Pectineus muscle (blue)
2 Adductor minimus muscle (red)
3 Adductor brevis muscle (blue)
4 Adductor longus muscle (blue)
5 Adductor magnus and minimus muscles (red)
6 Gracilis muscle (blue)
7 Iliopsoas muscle (blue and red)



Adductor magnus muscle and deep layer of adductor muscles of the thigh (right side, anterior aspect). Pectineus, adductor longus, and brevis muscles have been divided.

1 Anterior superior iliac spine
2 Inguinal ligament
3 Iliopsoas muscle
4 Sartorius muscle
5 Obturator externus muscle
6 Tensor fasciae latae muscle
7 Rectus femoris muscle
8 Iliotibial tract
9 Adductor longus muscle (divided)
10 Vastus lateralis muscle
11 Vastus medialis muscle
12 Pectineus muscle (divided)
13 Adductor minimus muscle
14 Adductor brevis muscle (cut)
15 Adductor magnus muscle
16 Gracilis muscle
17 Adductor canal
18 Vasto-adductor membrane
19 Diaphragm
20 Quadratus lumborum muscle
21 Iliacus muscle
22 Vastus intermedius muscle



Iliopsoas muscle and deepest layer of adductor muscles of the thigh (right side, anterior aspect). Pectineus, adductor longus and brevis, and rectus femoris muscles have been divided.

23 Aortic hiatus
24 Twelfth rib
25 Psoas minor muscle
26 Psoas major muscle
27 Iliopectineal arch


1
2
3
4
5
6
7
8
9
10
11

Gluteal muscles, superficial layer (right side, posterior aspect).


7
8
18
12
10
13
14
15
16
10
19
6
17
10

Gluteal muscles, deeper layer (right side, posterior aspect).


12
13
14
15
19
21
6
40
22
17
23



Course of the gluteal muscles (posterior aspect).

◁

Course of gluteal (deeper layer) **and ischiocrural muscles** (posterior aspect). The sartorius muscle is indicated by a dotted line.

112897_S_446_482_Kap_8:_ 06.11.2014 10:59 Uhr Seite 471



Flexor muscles of the thigh, superficial layer (right side, posterior aspect).

1 Thoracolumbar fascia
2 Spinous processes of lumbar vertebrae
3 Coccyx
4 Anus
5 Adductor magnus muscle
6 Semitendinosus muscle
7 Iliac crest
8 Gluteus medius muscle
9 Greater trochanter
10 Gluteus maximus muscle
11 Iliotibial tract
12 Piriformis muscle
13 Superior gemellus muscle
14 Obturator internus muscle
15 Inferior gemellus muscle
16 Ischial tuberosity
17 Biceps femoris muscle
18 Tensor fasciae latae muscle
19 Quadratus femoris muscle
20 Gluteus minimus muscle
21 Sartorius muscle
22 Semimembranosus muscle
23 Tendon of gracilis muscle
24 Tibial nerve
25 Medial head of gastrocnemius muscle
26 Common fibular nerve
27 Tendon of biceps femoris muscle
28 Lateral head of gastrocnemius muscle
29 Rectus femoris muscle
30 Vastus medialis muscle
31 Vastus intermedius muscle
32 Vastus lateralis muscle
33 Sciatic nerve
34 Gluteus maximus muscle (insertion)
35 Great saphenous vein
36 Femoral artery
37 Femoral vein
38 Adductor longus muscle
39 Femur
40 Gracilis muscle
41 Septum between semitendinosus and semimembranosus muscles



Cross section through the right thigh (inferior aspect). Anterior side on top.



Flexor muscles of the thigh (right side, posterior aspect). The gluteus maximus muscle has been cut and reflected.



Flexor muscles of the thigh (right side, posterior aspect). The gluteus maximus muscle and the long head of biceps femoris muscle have been divided and displaced.

1 Gluteus maximus muscle (divided)
2 Position of coccyx
3 Piriformis muscle
4 Superior gemellus muscle
5 Obturator internus muscle
6 Inferior gemellus muscle
7 Ischial tuberosity
8 Quadratus femoris muscle
9 Semitendinosus muscle with intermediate tendon
10 Semimembranosus muscle
11 Medial head of gastrocnemius muscle
12 Gluteus medius muscle
13 Adductor minimus muscle
14 Adductor magnus muscle
15 Long head of biceps femoris muscle
16 Iliotibial tract
17 Short head of biceps femoris muscle
18 Popliteal surface of femur
19 Plantaris muscle
20 Tendon of biceps femoris muscle
21 Lateral head of gastrocnemius muscle
22 Tendon of semimembranosus muscle



Flexor muscles of the leg (right side, posterior aspect).



Flexor muscles of the leg (right side, posterior aspect). Both heads of the gastrocnemius muscle have been cut and reflected.



Course of the flexor muscles of the leg (posterior aspect).

1 Semitendinosus muscle
2 Semimembranosus muscle
3 Sartorius muscle
4 Tendon of gracilis muscle
5 Medial head of gastrocnemius muscle
6 Common tendon of gracilis, sartorius, and semitendinosus muscles (pes anserinus)
7 Calcaneal or Achilles tendon
8 Medial malleolus
9 Calcaneal tuberosity
10 Tibial nerve
11 Biceps femoris muscle
12 Plantaris muscle
13 Common fibular nerve
14 Lateral head of gastrocnemius muscle
15 Soleus muscle
16 Peroneus longus and brevis muscles
17 Lateral malleolus
18 Popliteal fossa
19 Tibial nerve and posterior tibial artery
20 Popliteus muscle
21 Tendinous arch of soleus muscle
22 Femur
23 Fibula
24 Tibia



Muscles of leg and foot (right side, medial aspect).



Popliteal region with plantaris and soleus muscles (right side, posterior aspect). Notice the insertion of the tendon of semimembranosus muscle.

1 Vastus medialis muscle
2 Patella
3 Patellar ligament
4 Tibial tuberosity
5 Tibia
6 Tendons of deep flexor muscles (from anterior to posterior: 1. tibialis posterior; 2. flexor digitorum longus; 3. flexor hallucis longus muscles)
7 Flexor retinaculum
8 Tendon of tibialis anterior muscle
9 Tendon of extensor hallucis longus muscle
10 Abductor hallucis muscle
11 Tendon of semimembranosus muscle
12 Sartorius muscle
13 Tendon of gracilis muscle
14 Tendon of semitendinosus muscle
15 Common tendon of gracilis, semitendinosus, and sartorius muscles (pes anserinus)
16 Medial head of gastrocnemius muscle
17 Soleus muscle
18 Calcaneal or Achilles tendon
19 Calcaneus muscle
20 Tendon of flexor hallucis longus muscle
21 Quadriceps femoris muscle (divided)
22 Tendon of adductor magnus muscle (divided)
23 Medial condyle of femur
24 Popliteal artery and vein, and tibial nerve
25 Tibia
26 Femur
27 Lateral epicondyle of femur
28 Oblique popliteal ligament
29 Lateral (fibular) collateral ligament
30 Plantaris muscle
31 Tendon of biceps femoris muscle (divided)
32 Tendinous arch of soleus muscle



Muscles of leg and foot (right side, lateral aspect).



Axial section through the right leg distally of the knee joint (MRI scan). (From Heuck et al., MRT-Atlas, 2009.)



Axial section through the right leg cranially of the ankle joint (MRI scan). (From Heuck et al., MRT-Atlas, 2009.)

1 Common fibular nerve
2 Head of fibula
3 Lateral head of gastrocnemius muscle
4 Soleus muscle
5 Peroneus longus muscle
6 Peroneus brevis muscle
7 Calcaneal or Achilles tendon
8 Lateral malleolus muscle
9 Tendon of peroneus longus muscle
10 Extensor digitorum brevis muscle
11 Tendon of peroneus brevis muscle
12 Patella
13 Patellar ligament
14 Tuberosity of tibia
15 Tibialis anterior muscle
16 Extensor digitorum longus muscle
17 Superior extensor retinaculum
18 Inferior extensor retinaculum
19 Tendon of extensor hallucis longus muscle
20 Tendons of extensor digitorum longus muscle
21 Great saphenous vein
22 Medial head of gastrocnemius muscle
23 Tibia
24 Popliteus muscle
25 Tibial nerve, popliteal artery, and veins
26 Flexor hallucis longus muscle

Muscles of the Leg and Foot: Deep Flexor Muscles



1 Medial condyle of femur
2 Popliteus muscle
3 Flexor digitorum longus muscle
4 Crossing of tendons in the leg
5 Tendon of tibialis posterior muscle
6 Tendon of flexor digitorum longus muscle
7 Medial malleolus
8 Lateral condyle of femur
9 Head of fibula
10 Tibialis posterior muscle
11 Flexor hallucis longus muscle
12 Peroneus longus muscle
13 Peroneus brevis muscle
14 Tendon of flexor hallucis longus muscle
15 Calcaneal or Achilles tendon (divided)
16 Lateral malleolus

Deep flexor muscles of leg and foot (right side, posterior aspect).



1 Popliteus muscle (blue)
2 Flexor digitorum longus muscle (blue)
3 Tibialis posterior muscle (red)
4 Crossing of tendons in the leg
5 Flexor hallucis longus muscle (blue)
6 Crossing of tendons in the sole

Course of the deep flexor muscles of the leg (posterior aspect).



Deep flexor muscles of leg and foot (right side, posterior oblique-medial aspect). Flexor digitorum brevis and flexor hallucis longus muscles have been removed.



Coronal section through the leg (MRI scan). (From Heuck et al., MRT-Atlas, 2009.)

1 Medial condyle of femur
2 Tibia
3 Flexor digitorum longus muscle
4 Crossing of tendons in the leg
5 Tendon of tibialis posterior muscle
6 Abductor hallucis muscle
7 Tendon of flexor hallucis longus muscle
8 Lateral condyle of femur
9 Head of fibula
10 Tibialis posterior muscle
11 Tendon of flexor digitorum longus muscle
12 Flexor retinaculum
13 Calcaneal or Achilles tendon
14 Calcaneal tuberosity
15 Crossing of tendons in the sole
16 Quadratus plantae muscle
17 Tendons of flexor digitorum longus muscle
18 Tendon of tibialis anterior muscle
19 Area of insertion of tibialis posterior muscle
20 Lumbrical muscles
21 Flexor hallucis longus muscle
22 Tibialis anterior muscle
23 Extensor hallucis longus muscle
24 Lateral malleolus of fibula
25 Trochlea of talus



Sole of the right foot with tendons of long flexor muscles (oblique-medial and inferior aspect).



Extensor muscles of leg and foot (right side, oblique antero-lateral aspect).



Extensor muscles of leg and foot (right side, anterior aspect). Part of the tibialis anterior muscle has been removed.

1 Patella
2 Patellar ligament
3 Anterior margin of tibia
4 Tibialis anterior muscle
5 Extensor digitorum longus muscle
6 Superior extensor retinaculum
7 Inferior extensor retinaculum
8 Tendon of peroneus tertius muscle
9 Extensor digitorum brevis muscle
10 Tendons of extensor digitorum longus muscle
11 Soleus muscle
12 Extensor hallucis longus muscle
13 Medial malleolus
14 Tendon of tibialis anterior muscle
15 Extensor hallucis brevis muscle
16 Tendon of extensor hallucis longus muscle
17 Common tendon of gracilis, semitendinosus, and sartorius muscles (pes anserinus)
18 Tibia



Course of the extensor muscles of the leg (anterior aspect).



Muscles of the sole of foot, superficial layer. The plantar aponeurosis and the fasciae of the superficial muscles have been removed.



Sole of the foot with the plantar aponeurosis.



Course of abductor and adductor muscles of the foot (plantar aspect).
Red arrows: abduction;
blue arrows: adduction.

1 Longitudinal bands of plantar aponeurosis
2 Plantar aponeurosis
3 Position of tuberosity of fifth metatarsal bone
4 Muscles of fifth toe with fascia
5 Calcaneal tuberosity
6 Muscles of great toe with fascia
7 Tendons of flexor digitorum longus muscle
8 Tendons of flexor digitorum brevis muscle
9 Lumbrical muscle
10 Flexor digiti minimi brevis muscle
11 Flexor digitorum brevis muscle
12 Tendon of peroneus longus muscle
13 Abductor digiti minimi muscle
14 Tendon of flexor hallucis longus muscle
15 Flexor hallucis brevis muscle
16 Abductor hallucis muscle
17 Plantar aponeurosis (cut)
18 Peroneus longus muscle
19 Peroneus brevis muscle
20 Tibialis anterior muscle
21 Extensor hallucis longus muscle
22 Extensor digitorum longus muscle

1 Plantar interossei muscles (blue)
2 Abductor digiti minimi muscle (red)
3 Dorsal interossei muscles (red)
4 Transverse head of adductor hallucis muscle (blue)
5 Oblique head of adductor hallucis muscle (blue)
6 Abductor hallucis muscle (red)



Muscles of the sole of foot, middle layer. The flexor digitorum brevis muscle has been divided.



Muscles of the sole of foot, middle layer. The tendons of the flexor muscles and the crossing of tendons are displayed. The flexor digitorum brevis muscle has been divided and reflected.

1 Tendons of flexor digitorum brevis muscle
2 Tendons of flexor digitorum longus muscle
3 Lumbrical muscles
4 Interossei muscles
5 Flexor digiti minimi brevis muscle
6 Abductor digiti minimi muscle
7 Quadratus plantae muscle
8 Calcaneal tuberosity
9 Tendon of flexor hallucis longus muscle
10 Flexor hallucis brevis muscle
11 Abductor hallucis muscle
12 Flexor digitorum brevis muscle (divided)
13 Tuberosity of fifth metatarsal bone
14 Tendon of peroneus longus muscle
15 Transverse head of adductor hallucis muscle
16 Crossing of tendons in the sole of foot
17 Medial malleolus
18 Plantar aponeurosis (divided)



Muscles of the sole of foot, deep layer. The flexor digitorum brevis muscle has been removed, and the quadratus plantae, abductor hallucis, and digiti minimi muscles have been divided.



Muscles of the sole of foot, deepest layer. The interossei muscles and the canal for the tendon of peroneus longus muscle are shown.

1 Tendons of flexor digitorum brevis muscle
2 Transverse head of adductor hallucis muscle
3 Abductor digiti minimi muscle
4 Interossei muscles
5 Flexor digiti minimi brevis muscle
6 Opponens digiti minimi muscle
7 Tendon of peroneus longus muscle
8 Quadratus plantae muscle with tendon of flexor digitorum longus muscle
9 Calcaneal tuberosity
10 Tendon of flexor hallucis longus muscle (divided)
11 Tendons of flexor digitorum longus muscle
12 Flexor hallucis brevis muscle
13 Oblique head of adductor hallucis muscle
14 Abductor hallucis muscle (cut)
15 Tendon of tibialis posterior muscle
16 Dorsal interossei muscles
17 Plantar interossei muscles
18 Tuberosity of fifth metatarsal bone
19 Tendon of flexor digitorum longus muscle (crossing of plantar tendons)
20 Long plantar ligament

112897_S_446_482_Kap_8:_ 06.11.2014 10:59 Uhr Seite 482


22
1
23
2
24
25
26
27
28
48
29
30
13
14
31
32
33
34
35
36
25
37
38

Main arteries and nerves of the thigh (right side, anterior aspect). The sartorius muscle has been divided and reflected. The femoral vein has been partly removed to show the deep femoral artery. Note that the vessels enter the adductor canal to reach the popliteal fossa.


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21

Main arteries of the lower limb (anterior aspect).



Arteries of the leg (right side, posterior aspect).

1 Femoral artery
2 Deep artery of thigh
3 Ascending branch of lateral circumflex femoral artery
4 Descending branch of lateral circumflex femoral artery
5 Lateral superior genicular artery
6 Popliteal artery
7 Lateral inferior genicular artery
8 Anterior tibial artery
9 Peroneal artery
10 Lateral plantar artery
11 Arcuate artery with dorsal metatarsal arteries
12 Plantar arch with plantar metatarsal arteries
13 Medial circumflex femoral artery
14 Deep artery of thigh with perforating arteries
15 Descending genicular artery
16 Medial superior genicular artery
17 Middle genicular artery
18 Medial inferior genicular artery
19 Posterior tibial artery
20 Dorsalis pedis artery
21 Medial plantar artery
22 Superficial and deep circumflex iliac arteries
23 Femoral nerve
24 Lateral circumflex femoral artery
25 Sartorius muscle (cut and reflected)
26 Rectus femoris muscle
27 Vastus medialis muscle
28 Inguinal ligament
29 Femoral vein (cut)
30 External pudendal artery and vein
31 Adductor longus muscle
32 Great saphenous vein
33 Obturator artery and nerve
34 Gracilis muscle
35 Saphenous nerve
36 Vasto-adductor membrane
37 Anterior cutaneous branch of femoral nerve
38 Infrapatellar branch of saphenous nerve
39 Popliteal vein
40 Tibial nerve
41 Medial head of gastrocnemius muscle
42 Biceps femoris muscle
43 Common fibular nerve
44 Lateral head of gastrocnemius muscle
45 Plantaris muscle
46 Soleus muscle
47 Flexor hallucis longus muscle
48 Spermatic cord



Superficial veins of the lower limb (right side, medio-anterior aspect). The veins have been injected with red solution.



1 Superficial epigastric vein
2 Superficial circumflex iliac vein
3 Femoral vein
4 Small saphenous vein
5 External iliac vein
6 External pudendal vein
7 Great saphenous vein
8 Dorsal venous arch of foot
9 Saphenous opening with femoral vein
10 Patella
11 Penis
12 Anastomoses between great and small saphenous veins
13 Medial malleolus
14 Saphenous nerve
15 Posterior tibial artery and veins
16 Tibial nerve
17 Medial dorsal cutaneous nerve
18 Posterior tibial vein
19 Popliteal fossa
20 Perforating veins
21 Lateral malleolus
22 Superficial layer of crural fascia
23 Perforating veins I–III (of Cockett)
24 Tibia
25 Dorsal digital veins of foot
26 Dorsal venous arch of foot
27 Dorsal metatarsal veins
28 Anterior tibial artery and vein
29 Fibula
30 Peroneal artery and vein
31 Deep layer of crural fascia

Main trunkal veins of the lower limb (anterior aspect).



Medial malleolar region of the right foot. ▷ Dissection of tibial nerve, posterior tibial vessels, and great saphenous vein. The veins have been injected with blue resin.



Superficial veins of the leg (right side, posterior aspect). The veins have been injected with blue resin.


7
14
10
20
4
20
7
22
20

Superficial veins of the leg (left side, medial aspect). The perforating veins of Cockett have been dissected.


14
7
4
23
24
15
7
23
15

Veins of the leg (left side, medial aspect). The anastomoses between superficial and deeper veins are dissected.


7
21
13
26
27
25

◁ **Superficial veins of the dorsum of the right foot.** The veins have been injected with blue resin.


29
22
28
30
24
31
16
7
4
15
14
20

Anastomoses between superficial and deep veins of the leg. ▷
Arrows: directions of blood flow.



Nerves of the lower limb (lateral aspect).

1	Subcostal nerve	
2	Iliohypogastric nerve	
3	Ilio-inguinal nerve	
4	Lateral femoral cutaneous nerve	
5	Genitofemoral nerve	
6	Pudendal nerve	
7	Femoral nerve	
8	Obturator nerve	
9	Sciatic nerve	
10	Lumbar plexus (L_1–L_4)	lumbosacral plexus
11	Sacral plexus (L_4–S_4)	
12	"Pudendal" plexus (S_2–S_4)	
13	Inferior cluneal nerves	
14	Posterior femoral cutaneous nerve	
15	Common fibular nerve	
16	Tibial nerve	
17	Lateral sural cutaneous nerve	
18	Medial and lateral plantar nerves	
19	Saphenous nerve	
20	Infrapatellar branch of saphenous nerve	
21	Deep fibular nerve	
22	Superficial fibular nerve	
23	Anterior cutaneous branch of iliohypogastric nerve	
24	Lateral cutaneous branch of iliohypogastric nerve	
25	Femoral branch of genitofemoral nerve	
26	Lateral cutaneous branches of intercostal nerves	
27	Anterior cutaneous branches of intercostal nerves	
28	Genital branch of genitofemoral nerve	
29	Anterior scrotal nerves	



Main branches of the lumbosacral plexus (anterior aspect).



1	Transverse abdominal muscle
2	Iliohypogastric nerve
3	Ilio-inguinal nerve
4	Femoral nerve
5	Lateral femoral cutaneous nerve
6	Obturator nerve
7	Obturator internus muscle
8	Pubis (cut edge)
9	Levator ani muscle (remnant)
10	Dorsal nerve of penis
11	Posterior scrotal nerves of pudendal nerve
12	Adductor longus muscle
13	Gracilis muscle
14	Body of fourth lumbar vertebra
15	Cauda equina
16	Intervertebral disc
17	Sacral promontory
18	Sympathetic trunk
19	Sacrum
20	Lumbosacral trunk
21	Sacral plexus
22	Coccyx
23	Sacrospinous ligament
24	Pudendal nerve
25	Inferior rectal nerves
26	Perineal nerves of pudendal nerve
27	Subcutaneous fat tissue of gluteal region

Lumbosacral plexus in situ (right side, medial aspect). The pelvic organs with the peritoneum and part of the levator ani muscle have been removed.



Surface anatomy of the lower limb (right side, posterior aspect). The gluteal muscles are contracted.



Cutaneous nerves of the lower limb (posterior aspect). Dotted lines = border of segments.

1 Iliac crest
2 Sacrum
3 Coccyx
4 Gluteus maximus muscle
5 Ischiocrural muscles
6 Iliotibial tract
7 Tendon of semimembranosus muscle
8 Tendon of biceps femoris muscle
9 Popliteal fossa
10 Triceps surae muscle
11 Calcaneal or Achilles tendon
12 Lateral malleolus
13 Superior cluneal nerves
14 Middle cluneal nerves
15 Inferior cluneal nerves
16 Posterior femoral cutaneous nerve
17 Obturator nerve
18 Saphenous nerve
19 Iliohypogastric nerve
20 Lateral femoral cutaneous nerves
21 Common fibular nerve
22 Sural nerve



Surface anatomy of the lower limb (right side, anterior aspect).



Cutaneous nerves of the lower limb (anterior aspect).
Dotted lines = border of segments.

1 Iliac crest
2 Anterior superior iliac spine
3 Tensor fasciae latae muscle
4 Quadriceps femoris muscle
5 Iliotibial tract
6 Tendon of biceps femoris muscle
7 Patella
8 Patellar ligament
9 Tibia
10 Tendon of tibialis anterior muscle
11 Lateral malleolus
12 Dorsal venous arch of foot
13 Iliohypogastric nerve
14 Lateral femoral cutaneous nerve
15 Femoral nerve
16 Common fibular nerve
17 Superficial fibular nerve
18 Ilio-inguinal nerve
19 Obturator nerve
20 Saphenous nerve
21 Deep fibular nerve


1
2
3
4
5
6
4
7
8
9
10
11
12
13
14
15
16
17
18

Anterior region of the thigh with cutaneous nerves and veins (right side).


11
2
3
5
6
8
19
20
25
13
14
7
21
22
17
18

Anterior region of the thigh with cutaneous nerves and veins (right side; compare with the dissection alongside).

1 Inguinal ligament
2 Superficial circumflex iliac vein
3 Femoral branch of genitofemoral nerve
4 Superficial inguinal lymph nodes
5 Saphenous opening with femoral artery and vein
6 Lateral femoral cutaneous nerve
7 Great saphenous vein
8 Anterior cutaneous branches of femoral nerve
9 Patella
10 Terminal branches of subcostal nerve
11 Terminal branches of iliohypogastric nerve
12 Superficial inguinal ring
13 External pudendal vein
14 Spermatic cord with genital branch of genitofemoral nerve
15 Penis with superficial dorsal vein of penis
16 Testis and its coverings
17 Saphenous nerve
18 Infrapatellar branch of saphenous nerve
19 Lateral sural cutaneous nerve
20 Superficial epigastric vein
21 Accessory saphenous vein
22 Cutaneous branch of obturator nerve
23 Femoral nerve
24 Femoral artery
25 Femoral vein
26 Superficial and inferior inguinal lymph nodes (enlarged)
27 Lymphatic vessels
28 Sartorius muscle
29 Iliohypogastric nerve



Anterior region of the thigh with cutaneous nerves and veins (right side). The fascia lata and the fasciae of the thigh muscles have been removed.



Inguinal nodes with lymphatic vessels (anterior aspect).



Anterior region of the thigh (right side, anterior aspect). The fascia lata has been removed and the sartorius muscle has been slightly reflected.



Anterior region of the thigh (right side, anterior aspect). The fascia lata has been removed and the sartorius muscle has been divided.

1 Anterior superior iliac spine
2 Inguinal ligament
3 Deep circumflex iliac artery
4 Iliopsoas muscle
5 Tensor fasciae latae muscle
6 Femoral nerve
7 Lateral circumflex femoral artery
8 Sartorius muscle
9 Rectus femoris muscle
10 Iliotibial tract
11 Vastus lateralis muscle
12 Anterior sheath of rectus abdominis muscle
13 Inferior epigastric artery
14 Spermatic cord
15 Femoral artery
16 Pectineus muscle
17 Femoral vein
18 Great saphenous vein (divided)
19 Adductor longus muscle
20 Saphenous nerve
21 Muscular branch of femoral nerve
22 Gracilis muscle
23 Vastus medialis muscle
24 Ascending branch of lateral circumflex femoral artery
25 Descending branch of lateral circumflex femoral artery
26 Medial circumflex femoral artery
27 Adductor longus muscle
28 Penis
29 Entrance to adductor canal
30 Vasto-adductor membrane of fascia beneath sartorius muscle



Anterior region of the thigh (right side, anterior aspect). The fascia lata has been removed. Sartorius and pectineus muscles, and the femoral artery have been cut to display the deep femoral artery with its branches. The rectus femoris muscle has been slightly reflected.



Anterior region of the thigh (right side, anterior aspect). The sartorius, pectineus, adductor longus, and rectus femoris muscles have been divided and reflected. The greater part of the femoral artery has been removed.

1 Anterior superior iliac spine
2 Inguinal ligament
3 Tensor fasciae latae muscle
4 Deep circumflex iliac artery
5 Iliopsoas muscle
6 Sartorius muscle (cut)
7 Femoral nerve
8 Lateral circumflex femoral artery
9 Ascending branch of lateral circumflex femoral artery
10 Descending branch of lateral circumflex femoral artery
11 Rectus femoris muscle
12 Vastus medialis muscle
13 Vastus lateralis muscle
14 Femoral vein
15 Pectineus muscle (cut)
16 Femoral artery (cut)
17 Obturator nerve
18 Deep artery of thigh
19 Ascending branch of medial circumflex femoral artery
20 Medial circumflex femoral artery
21 Adductor longus muscle
22 Gracilis muscle
23 Saphenous nerve
24 Distal part of vasto-adductor membrane
25 Rectus femoris muscle
with muscular branches of femoral nerve
26 Adductor longus muscle (divided)
27 Posterior branch of obturator nerve
28 Anterior branch of obturator nerve
29 Point at which perforating artery branches off
from deep artery of thigh
30 Muscular branch of femoral nerve to vastus medialis muscle



Gluteal region (right side). Dissection of the cutaneous nerves.

1	Iliac crest
2	Gluteus maximus muscle
3	Middle cluneal nerves
4	Anococcygeal nerves
5	Perineal branch of posterior femoral cutaneous nerve
6	Adductor magnus muscle
7	Superior cluneal nerves
8	Position of greater trochanter
9	Inferior cluneal nerves
10	Semitendinosus muscle
11	Posterior femoral cutaneous nerve
12	Long head of biceps femoris muscle

A Suprapiriform foramen (of greater sciatic foramen)

Superior gluteal artery, vein, and nerve

B Infrapiriform foramen (of greater sciatic foramen)

Sciatic nerve
Inferior gluteal artery, vein, and nerve
Posterior femoral cutaneous nerve
Internal pudendal artery and vein
Pudendal nerve
Internal obturator nerve
Nerve to quadratus femoris muscle

C Lesser sciatic foramen

Pudendal nerve
Internal pudendal artery and vein
Internal obturator nerve



Location of the sciatic foramina in relation to the bones at the gluteal region (postero-lateral aspect).

Red lines

1 **Spine-tuber line**
(the infrapiriform foramen is situated in the middle of this line)
2 **Spine-trochanter line**
(the suprapiriform foramen is located in the upper third)
3 **Tuber-trochanter line**
(the ischiadic nerve can be found between the middle and posterior third)

Other structures

4	Posterior superior iliac spine
5	Iliac crest
6	Greater trochanter
7	Ischial tuberosity
8	Sacrum



Gluteal region (right side). Gluteus maximus and gluteus medius muscles have been divided and reflected. Notice the position of the foramina above and below the piriformis muscle and the lesser sciatic foramen.

1	Iliac crest	12	Long head of biceps femoris muscle
2	Gluteus maximus muscle (cut)	13	Gluteus medius muscle (cut)
3	Inferior gluteal nerve	14	Deep branch of superior gluteal artery
4	Piriformis muscle	15	Gluteus minimus muscle
5	Muscular branches of inferior gluteal artery	16	Superior gluteal nerve
6	Pudendal nerve and internal pudendal artery within the lesser sciatic foramen (entrance to the pudendal canal)	17	Suprapiriform foramen } greater sciatic foramen
		18	Infrapiriform foramen } greater sciatic foramen
7	Sacrotuberous ligament	19	Obturator internus and superior gemellus muscles
8	Inferior cluneal nerve	20	Posterior femoral cutaneous nerve
9	Inferior rectal nerves	21	Inferior gemellus muscle
10	Inferior rectal arteries	22	Sciatic nerve
11	Perforating cutaneous nerve of posterior femoral cutaneous nerve	23	Quadratus femoris muscle
		24	Tensor fasciae latae muscle



Gluteal and posterior regions of the thigh with cutaneous nerves (right side). The fascia lata and the fasciae of the muscles have been removed.

1 Middle cluneal nerves
2 Perineal branch of posterior femoral cutaneous nerve
3 Posterior femoral cutaneous nerve
4 Semimembranosus muscle
5 Semitendinosus muscle
6 Tibial nerve
7 Medial sural cutaneous nerve
8 Small saphenous vein
9 Medial head of gastrocnemius muscle
10 Gluteus maximus muscle
11 Inferior cluneal nerves
12 Cutaneous veins
13 Long head of biceps femoris muscle
14 Iliotibial tract
15 Short head of biceps femoris muscle
16 Popliteal fossa
17 Lateral sural cutaneous nerve
18 Lateral head of gastrocnemius muscle
19 Common fibular nerve
20 Tendon of biceps femoris muscle
21 Inferior gluteal nerve
22 Sacrotuberous ligament
23 Inferior rectal branches of pudendal nerve
24 Anus
25 Gluteus medius muscle
26 Piriformis muscle
27 Sciatic nerve
28 Inferior gluteal artery
29 Gluteus maximus muscle (cut)
30 Quadratus femoris muscle
31 Sciatic nerve dividing into its two branches (the common fibular nerve and the tibial nerve)
32 Muscular branches of sciatic nerve to the ischiocrural muscles
33 Popliteal artery
34 Popliteal vein
35 Small saphenous vein (cut)
36 Long head of biceps femoris muscle (cut)
37 Superficial fibular nerve


21
22
23
2
24
5
4
6
9
7
25
26
27
28
29
30
3
13
14
31
19
18
17

Gluteal and posterior regions of the thigh (right side). The gluteus maximus muscle has been divided and reflected.


21
22
23
3
32
5
33
4
34
6
35
9
7
25
26
27
28
30
29
14
36
31
19
37
17

Gluteal and posterior regions of the thigh (right side). The gluteus maximus muscle and the long head of the biceps femoris muscle have been divided and reflected.



Posterior region of the knee with cutaneous nerves and veins (right side).



Anterior region of the knee with cutaneous nerves and veins (right side).

1	Cutaneous veins (tributaries of great saphenous vein)
2	Great saphenous vein
3	Cutaneous branches of femoral nerve
4	Position of medial condyle of femur
5	Position of small saphenous vein
6	Fascia lata
7	Terminal branches of posterior femoral cutaneous nerve
8	Cutaneous veins of popliteal fossa
9	Position of head of fibula
10	Superficial layer of fascia cruris
11	Lateral sural cutaneous nerve
12	Venous network around knee
13	Patella
14	Saphenous nerve
15	Infrapatellar branch of saphenous nerve
16	Patellar ligament
17	Position of tibial tuberosity
18	Sartorius muscle
19	Semimembranosus muscle
20	Gastrocnemius muscle
21	Popliteal vein
22	Tibial nerve
23	Biceps femoris muscle
24	Popliteal artery
25	Lateral inferior genicular artery
26	Fibula



Coronal section through the popliteal fossa (MRI scan).
(From Heuck et al., MRT-Atlas, 2009.)



Popliteal fossa, middle layer (right side). The gastrocnemius muscle has been divided and reflected.



Popliteal fossa, deep layer (right side). Gastrocnemius and soleus muscles have been divided and reflected.

1 Semitendinosus muscle
2 Gracilis muscle
3 Semimembranosus muscle
4 Sartorius muscle
5 Tendon of semitendinosus muscle
6 Position of medial condyle of femur
7 Muscular branches of tibial nerve
8 Sural arteries and veins
9 Tendon of semimembranosus muscle
10 Common tendon of gracilis, semitendinosus, and sartorius muscles (pes anserinus)
11 Medial head of gastrocnemius muscle
12 Biceps femoris muscle
13 Muscular branch of popliteal artery
14 Popliteal artery
15 Popliteal vein
16 Tibial nerve
17 Common fibular nerve
18 Lateral head of gastrocnemius muscle
19 Medial sural cutaneous nerve
20 Medial superior genicular artery
21 Medial head of gastrocnemius muscle (cut and reflected)
22 Medial inferior genicular artery
23 Soleus muscle
24 Tendon of plantaris muscle
25 Lateral superior genicular artery
26 Lateral inferior genicular artery
27 Plantaris muscle



Popliteal fossa, deep layer (right side). The muscles have been reflected to display the genicular arteries.



Popliteal fossa, deepest layer (right side). Tibial nerve and popliteal vein have been partly removed and a portion of the soleus muscle was cut away to display the anterior tibial artery.

1 Semitendinosus muscle
2 Semimembranosus muscle
3 Medial superior genicular artery
4 Popliteal artery
5 Medial head of gastrocnemius muscle
6 Middle genicular artery
7 Muscular branches of popliteal artery
8 Medial inferior genicular artery
9 Tendon of plantaris muscle
10 Tibial nerve (cut)
11 Biceps femoris muscle
12 Popliteal vein (cut)
13 Lateral superior genicular artery
14 Lateral inferior genicular artery
15 Lateral head of gastrocnemius muscle
16 Common fibular nerve
17 Head of fibula
18 Lateral sural cutaneous nerves
19 Soleus muscle
20 Medial sural cutaneous nerve
21 Anterior tibial artery
22 Posterior tibial artery
23 Lateral sural cutaneous nerve



Posterior crural region and popliteal fossa with cutaneous veins and nerves (right side).



Posterior crural region and popliteal fossa with cutaneous veins and nerves (right side). The superficial layer of the crural fascia has been removed.



Antero-medial crural region with cutaneous veins and nerves (right side).

1 Great saphenous vein
2 Anastomosis between small and great saphenous veins
3 Medial malleolus
4 Popliteal fossa
5 Position of head of fibula
6 Lateral sural cutaneous nerve
7 Small saphenous vein
8 Sural nerve
9 Calcaneal or Achilles tendon
10 Lateral malleolus
11 Semitendinosus muscle
12 Medial head of gastrocnemius muscle
13 Saphenous nerve
14 Common fibular nerve
15 Medial sural cutaneous nerve
16 Perforating veins
17 Superficial fibular nerve
18 Dorsal venous arch of foot
19 Intermediate dorsal cutaneous nerve
20 Infrapatellar branches of saphenous nerve
21 Terminal branches of saphenous nerve
22 Medial dorsal cutaneous nerve


1
2
3
4
5
6
7
5
8
9
5
10
11
12
13
7
14
15
16
17
18
19
20

Posterior crural region and popliteal fossa, superficial layer (right side). The cutaneous veins and nerves have been removed.


2
1
21
5
6
7
8
22
23
24
5
10
25
11
12
13
7
14
5
26
27
28
18
20

Posterior crural region and popliteal fossa, middle layer (right side). The medial head of gastrocnemius muscle has been divided and reflected.



Posterior crural region and popliteal fossa, deep layer (right side). Triceps surae (gastrocnemius and soleus) and flexor hallucis longus muscles have been cut and reflected.

1 Semimembranosus muscle
2 Semitendinosus muscle
3 Popliteal vein
4 Popliteal artery
5 Tibial nerve
6 Small saphenous vein (cut)
7 Muscular branch of tibial nerve
8 Medial head of gastrocnemius muscle
9 Tendon of plantaris muscle
10 Posterior tibial artery
11 Medial malleolus
12 Biceps femoris muscle
13 Common fibular nerve
14 Sural arteries
15 Plantaris muscle
16 Lateral head of gastrocnemius muscle
17 Soleus muscle
18 Calcaneal or Achilles tendon
19 Lateral malleolus
20 Calcaneal tuberosity
21 Sartorius muscle
22 Popliteal artery
23 Tendinous arch of soleus muscle
24 Flexor digitorum longus muscle
25 Flexor retinaculum
26 Peroneal artery
27 Triceps surae muscle (cut)
28 Flexor hallucis longus muscle
29 Anterior tibial artery
30 Muscular branches of tibial nerve
31 Tibialis posterior muscle
32 Communicating branch of peroneal artery
33 Tendon of tibialis anterior muscle
34 Tibia
35 Tendon of extensor hallucis longus muscle
36 Tendons of extensor digitorum longus muscle
37 Anterior tibial artery
38 Fibula
39 Tendons of peroneus longus and brevis muscles



Cross section through the leg, superior to the malleoli (inferior aspect).



Anterior crural region and dorsum of the foot with cutaneous nerves and veins (right side).



Medial crural region and foot with cutaneous nerves and veins (right side).

1 Superficial crural fascia
2 Medial dorsal cutaneous branch of superficial fibular nerve
3 Lateral malleolus
4 Intermediate dorsal cutaneous branch of superficial fibular nerve
5 Lateral dorsal cutaneous branch of sural nerve
6 Position of tibial tuberosity
7 Anterior margin of tibia
8 Great saphenous vein
9 Medial malleolus
10 Deep fibular nerve
11 Dorsal venous arch of foot
12 Position of patella
13 Infrapatellar branches of saphenous nerve
14 Saphenous nerve
15 Small saphenous vein
16 Perforating vein
17 Calcaneal or Achilles tendon



Lateral crural region and foot with cutaneous nerves and veins (right side).



Anterior crural region and dorsum of the foot with cutaneous nerves and veins.

1 Position of fibula
2 Sural nerve
3 Small saphenous vein
4 Calcaneal or Achilles tendon
5 Lateral calcaneal branches of sural nerve
6 Venous plexus of lateral malleolus
7 Lateral dorsal cutaneous branch of sural nerve
8 Tendon of peroneus brevis muscle
9 Tendons of extensor digitorum longus muscle
10 Crural fascia
11 Superficial fibular nerve
12 Position of tibia
13 Intermediate dorsal cutaneous branch of superficial fibular nerve
14 Medial dorsal cutaneous branch of superficial fibular nerve
15 Lateral malleolus
16 Dorsal digital nerves
17 Dorsal venous arch of foot
18 Deep fibular nerve
19 Dorsal metatarsal veins
20 Saphenous nerve
21 Great saphenous vein


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23

Anterior crural region and dorsum of the foot, middle layer (right side, antero-lateral aspect). The extensor digitorum longus muscle has been divided and reflected laterally.


1
2
3
24
25
26
4
27
7
28
8
9
10
11
12
13
14
5
16
18
17
19
20
22
21
23

Anterior crural region and dorsum of the foot, deep layer (right side, antero-lateral aspect). Extensor digitorum longus and peroneus longus muscles have been divided or removed. The common fibular nerve has been elevated to show its course around the head of fibula.



Coronal section through the right foot and ankle joint (dorsal aspect).



Coronal section through the right foot and ankle joint (MRI scan). (From Heuck et al., MRT-Atlas, 2009.)



Synovial sheaths of extensor tendons (dorsal aspect). The sheaths have been injected with blue gelatin.

1 Iliotibial tract
2 Common fibular nerve
3 Position of head of fibula
4 Extensor digitorum longus muscle
5 Muscular branches of deep fibular nerve
6 Superficial fibular nerve
7 Tendon of extensor digitorum longus muscle
8 Lateral malleolus
9 Extensor digitorum brevis muscle with tendons
10 Tendons of extensor digitorum longus muscle
11 Patella
12 Patellar ligament
13 Anterior margin of tibia
14 Anterior tibial artery
15 Tibialis anterior muscle
16 Deep fibular nerve
17 Extensor hallucis longus muscle
18 Tendon of tibialis anterior muscle
19 Inferior extensor retinaculum
20 Dorsalis pedis artery
21 Extensor hallucis brevis muscle
22 Deep fibular nerve (on dorsum of foot)
23 Terminal branches of deep fibular nerve
24 Deep fibular nerve
25 Peroneus longus muscle (cut)
26 Superficial fibular nerve (with peroneal muscles laterally reflected)
27 Peroneus brevis muscle
28 Lateral anterior malleolar artery
29 Fibula
30 Distal tibiofibular joint (syndesmosis)
31 Talocalcaneal interosseous ligament
32 Calcaneus
33 Tendon of peroneus brevis muscle
34 Cuboid bone
35 Lateral cuneiform bone
36 Metatarsal bones
37 Dorsal interossei muscles
38 Tibia
39 Ankle joint
40 Medial malleolus
41 Talus
42 Talocalcaneonavicular joint
43 Navicular bone
44 Medial cuneiform bone
45 Intermediate cuneiform bone
46 First metatarsal bone
47 Metatarsophalangeal joint of great toe
48 Proximal phalanx of great toe
49 Distal phalanx of great toe
50 Heads of the second and third metatarsal bones
51 Synovial sheath of tendons of extensor digitorum longus muscle
52 Synovial sheath of tendon of tibialis anterior muscle
53 Synovial sheath of tendon of extensor hallucis longus muscle



Dorsum of the right foot, superficial layer.



Dorsum of the right foot, superficial layer. The fascia of the dorsum has been removed.

1 Superficial fibular nerve
2 Superior extensor retinaculum
3 Lateral malleolus
4 Venous network of lateral malleolus and tributaries of small saphenous vein
5 Lateral dorsal cutaneous branch of sural nerve
6 Intermediate dorsal cutaneous nerve
7 Tendons of extensor digitorum longus muscle
8 Dorsal digital nerves
9 Tendon of tibialis anterior muscle
10 Saphenous nerve
11 Venous network of medial malleolus and tributaries of great saphenous vein
12 Medial malleolus
13 Medial dorsal cutaneous nerves
14 Dorsal venous arch of foot
15 Dorsal digital nerve (of deep fibular nerve)
16 Tendon of extensor hallucis longus muscle
17 Dorsal digital arteries
18 Peroneal muscles
19 Deep plantar branch of dorsalis pedis artery anastomosing with plantar arch
20 Extensor digitorum longus muscle
21 Extensor hallucis longus muscle
22 Inferior extensor retinaculum
23 Extensor hallucis brevis muscle



1 Inferior extensor retinaculum
2 Lateral malleolus
3 Lateral anterior malleolar artery
4 Tendons of peroneal muscles
5 Tendon of peroneus tertius muscle
6 Extensor digitorum brevis muscle
7 Tendons of extensor digitorum longus muscle
8 Dorsal metatarsal arteries
9 Medial malleolus
10 Tendon of tibialis anterior muscle
11 Dorsalis pedis artery
12 Deep fibular nerve (on dorsum of foot)
13 Extensor hallucis brevis muscle
14 Tendon of extensor hallucis longus muscle
15 Dorsalis pedis artery with deep plantar branch to the plantar arch
16 Terminal branches of deep fibular nerve
17 Lateral tarsal artery
18 Extensor digitorum brevis muscle (divided)
19 Arcuate artery
20 Dorsal interossei muscles
21 Deep fibular nerve

Dorsum of the right foot, middle layer. The cutaneous nerves have been removed.



Dorsum of the right foot, deep layer. Extensor digitorum and hallucis brevis muscles have been removed.


1
2
3
4
5
6
7
8
9
10

Sole of the right foot, superficial layer. Dissection of cutaneous nerves and vessels.


1
7
1
8
2
11
6
5
4
12
13
14
6
15
7
1
16
8
17
19
18
9
20
21
22
23

Sole of the right foot, middle layer. The plantar aponeurosis has been removed.

112897_S_483_515_Kap_8:_ 06.11.2014 11:03 Uhr Seite 511



Sole of the right foot, middle layer. Dissection of vessels and nerves. The flexor digitorum brevis muscle has been divided and anteriorly reflected.

1 Proper plantar digital nerves
2 Common plantar digital nerves
3 Plantar aponeurosis
4 Superficial branch of lateral plantar nerve
5 Superficial branch of lateral plantar artery
6 Abductor digiti minimi muscle
7 Proper plantar digital arteries
8 Common plantar digital arteries
9 Digital branch of medial plantar nerve to great toe
10 Medial calcaneal branches
11 Tendons of flexor digitorum brevis muscle
12 Flexor digitorum brevis muscle
13 Superficial branch of lateral plantar nerve
14 Lateral plantar artery
15 Plantar aponeurosis (remnant)
16 Fibrous sheath of toe
17 Lumbrical muscles
18 Tendon of flexor hallucis longus muscle
19 Flexor hallucis brevis muscle
20 Medial plantar artery
21 Medial plantar nerve
22 Abductor hallucis muscle
23 Calcaneal tuberosity
24 Tendons of flexor digitorum longus muscle
25 Quadratus plantae muscle
26 Lateral plantar nerve
27 Flexor digitorum brevis muscle (cut)
28 Synovial sheaths of tendons of flexor digitorum longus and brevis muscles
29 Plantar arch
30 Deep branch of lateral plantar nerve



Sole of the right foot with vessels and nerves. The flexor digitorum brevis muscle has been removed. Light blue = synovial sheaths of flexor tendons.



Sole of the right foot, deep layer. Dissection of vessels and nerves. The flexor digitorum brevis muscle, the quadratus plantae muscle with the tendons of the flexor digitorum longus muscle, and some branches of the medial plantar nerve have been removed. The flexor hallucis brevis and adductor hallucis muscles have been cut and portions removed to show the somewhat atypical course of the medial plantar artery and deep muscles of the foot.

1 Proper plantar digital arteries
2 Proper plantar digital nerves
3 Tendons of flexor digitorum brevis muscle
4 Tendons of flexor digitorum longus muscle
5 Superficial branch of lateral plantar artery
6 Deep branch of lateral plantar nerve
7 Superficial branch of lateral plantar nerve
8 Lateral plantar nerve
9 Lateral plantar artery
10 Abductor digiti minimi muscle
11 Calcaneal tuberosity
12 Common plantar digital arteries
13 Tendon of flexor hallucis longus muscle
14 Insertion of both heads of adductor hallucis muscle
15 Plantar metatarsal arteries
16 Medial proper plantar digital nerve
17 Deep plantar branch of dorsal metatarsal artery (perforating branch)
18 Plantar arch
19 Oblique head of adductor hallucis muscle (cut)
20 Medial plantar artery
21 Medial plantar nerve
22 Crossing of tendons in the sole of foot (flexor hallucis longus and flexor digitorum longus muscles)
23 Abductor hallucis muscle
24 Origin of flexor hallucis brevis muscle
25 Medial cuneiform and first metatarsal bones
26 Tendon of peroneus longus muscle
27 Abductor hallucis and flexor hallucis brevis muscles
28 Medial plantar artery, vein, and nerve
29 Fourth and fifth metatarsal bones
30 Lateral plantar artery, vein, and nerve
31 Flexor digitorum brevis muscle
32 Plantar aponeurosis



Cross section through the right foot at the level of the metatarsal bones (posterior aspect).



Sole of the right foot (MRI scan). (From Heuck et al., MRT-Atlas, 2009.) For details see schematic drawing alongside.



Cross section through the right foot at the level of the metatarsal bones (posterior aspect; compare with the dissection on the previous page).



1	Lumbrical muscles
2	Plantar interossei muscles
3	Abductor digiti minimi muscle
4	Tuberosity of fifth metatarsal bone
5	Cuboid bone
6	Tendon of peroneus longus muscle
7	Calcaneus
8	Calcaneal or Achilles tendon
9	First metatarsal bone
10	Flexor hallucis brevis muscle
11	Tendons of flexor digitorum longus and brevis muscles
12	Tendon of flexor hallucis longus muscle
13	Abductor hallucis muscle
14	Medial plantar artery, vein, and nerve
15	Quadratus plantae muscle
16	Lateral plantar artery, vein, and nerve
17	Dorsal venous network of foot
18	Superficial and deep dorsal fascia of foot
19	Tendons of extensor digitorum longus and brevis muscles
20	Tendons of extensor hallucis longus and brevis muscles
21	Adductor hallucis muscle
22	Plantar aponeurosis



Axial section through the pelvis at the level of the hip joints. Section 1 (MRI scan, inferior aspect).



Lower limb,
location of sections 1–5
(MRI scans courtesy of
Prof. Heuck, Munich, Germany).



Axial section through the pelvis at the level of the hip joints in a female. Section 1 (inferior aspect). Arrows: uterus (myometrium with myoma).

1	Sartorius muscle
2	Femoral artery and vein
3	Iliopsoas muscle
4	Pubis
5	Head of femur with ligament of head of femur
6	Articular cavity
7	Rectum
8	Sciatic nerve and accompanying artery
9	Gluteus maximus muscle
10	Obturator artery, vein, and nerve
11	Rectus abdominis muscle
12	Pyramidalis muscle
13	Urinary bladder
14	Obturator internus muscle
15	Rectus femoris muscle
16	Vastus intermedius and vastus lateralis muscles of quadriceps femoris muscle



Axial section through the middle of the right thigh. Section 2 (MRI scan, inferior aspect).



Axial section through the middle of the right thigh. Section 2 (inferior aspect).



Axial section through the right knee joint. Section 3 (MRI scan, inferior aspect).



Axial section through the right knee joint. Section 3 (inferior aspect).



Axial section through the middle of the right leg. Section 4 (MRI scan, inferior aspect).



Axial section through the middle of the right leg. Section 4 (inferior aspect).



Axial section through the end of the right leg. Section 5 (MRI scan, inferior aspect).



Axial section through the end of the right leg. Section 5 (inferior aspect).

17	Femur
18	Perforating artery
19	Sciatic nerve
20	Gluteus maximus muscle (insertion)
21	Vastus medialis muscle
22	Sartorius muscle
23	Femoral artery and vein
24	Great saphenous vein
25	Gracilis muscle
26	Adductor muscles
27	Biceps femoris muscle
28	Patellar ligament
29	Lateral condyle of femur
30	Posterior cruciate ligament
31	Tibial nerve
32	Popliteal artery and vein
33	Lateral head of gastrocnemius muscle
34	Medial condyle of femur
35	Medial head of gastrocnemius muscle
36	Tibialis anterior muscle
37	Tibia
38	Deep fibular nerve, anterior tibial artery, and vein
39	Patellar surface
40	Peroneus longus and brevis muscles
41	Fibula
42	Soleus muscle
43	Flexor digitorum longus muscle
44	Tibialis posterior muscle
45	Posterior tibial artery and vein, and tibial nerve
46	Peroneal artery
47	Small saphenous vein and sural nerve
48	Extensor hallucis longus muscle
49	Extensor digitorum longus muscle
50	Tendon of peroneus longus muscle
51	Lateral malleolus of fibula
52	Peroneus brevis muscle
53	Tendon of tibialis anterior muscle
54	Dorsalis pedis artery
55	Medial malleolus of tibia
56	Tendon of tibialis posterior muscle
57	Tendon of flexor digitorum longus muscle with synovial sheath
58	Flexor hallucis longus muscle
59	Posterior tibial artery and vein
60	Lateral and medial plantar nerves
61	Calcaneal or Achilles tendon
62	Semitendinosus muscle
63	Semimembranosus muscle
64	Anterior cruciate ligament
65	Plantaris muscle
66	Small intestine

Index

Page numbers in **bold** indicate main discussions.

A

Abdomen, parasagittal section 307
Abdominal organs 299 ff
– lower 324 f
– in newborn 273
– peritoneal reflections 328
– position 300, 316
– upper 305, 319 ff
– – blood supply 326
– vessels 310 ff, **322 f**
Accommodation 140
Acetabulum
– bony margin 454
– lunate surface 450, **453**, 461
Achilles tendon 465 f, **473 ff**, 501, 503 ff
– surface anatomy 488
Acromion 15, **381 ff**, 390, 394, 396 f
Adductor hiatus 469
Adhesion, interthalamic 88, **109**, 114, 118
Adnexa of uterus 373
Air cells
– ethmoidal 28, 36, **38**, 41 f, 44 f, **48**, 55, 136, 142
– – openings 146
– mastoid 72, 127 ff
Ala see also Wing
– of central lobule of vermis 104
– of ilium 449
– of sacrum 449, 452, 454
– of vomer 37, 45, **48**, 49
Alcock's canal 365
Ampulla 130 f
– bony 131
– of ductus deferens **348 ff**, 354, 356
– rectal 348, **354**, 371, 378
– of uterine tube 370
Amygdala see Body, amygdaloid
Anastomoses, portocaval 313
Aneurysm, infrarenal, of aorta 360
Angiography, fluorescent, of eye 141
Angle
– of clivus 20
– costal 201, 205
– of costotransverse joint 205
– inferior, of scapula 382 f, 394 f
– infrasternal 7, **201**, 256
– – surface anatomy 208
– lateral, of scapula 382 f
– of mandible 21, **52**
– of rib 382
– sphenoidal, of parietal bone 29
– sternal 201
– subcostal 382
– superior, of scapula 383
– venous
– – left 17
– – right 17, 410
Ankle joint 447, **459**, **465**
– coronal section 507
Ansa
– cervicalis 69, 73, **165**, 175, 179, **183 f**, 276
– – muscular branches 183, 275
– – root
– – – inferior 186
– – – superior 71, 73, **85**, 154, 181
– lenticular 118
– subclavia of sympathetic trunk 171
– thyroid, of sympathetic trunk 171
Anterior 4
Anthelix 124
Antitragus 124
Antrum
– mastoid 128
– pyloric 302, 334
– tympanic 129
Anulus
– fibrosus 206
– inguinalis see Ring, inguinal
– tympanic, of newborn 33
Anus 362 ff
Aorta 16 f
– abdominal 16, 214, **253**, 268, 288, 304, 310, 330, 334, **339 ff**
– – aneurysma, infrarenal 360
– – arteriography 338, 344
– – horizontal section 300
– – sclerotic changes 344
– ascending **253**, 264, 276, 282, 294, 408
– – of fetus 272
– – horizontal section 296
– descending 252, 286
– – of fetus 272 f
– – horizontal section 296, **330**
– – main branches 291
– thoracic 263, 284 f, 291
Aperture
– of Luschka 114
– of Magendie 96, **114**
– median, of fourth ventricle 96
– nasal, anterior 22 f, 45
– pelvic, inferior 452, **454**
– thoracic, inferior, horizontal plane 208
Apex
– of cochlea 127
– of head of fibula 456
– of heart 260, **262**
– of left lung 281
– of lung 256 f
– of patella 457
– of petrous part of temporal bone 27, 128
– of sacrum 199
– of urinary bladder 349, 351
Aponeurosis
– bicipital **399 f**, 428, 435
– of external abdominal oblique muscle 221, **224**
– of levator palpebrae superioris muscle 135
– palmar 400, 407, **435**, 442
– – transverse fasciculi 401
– plantar 479, **511 f**
– – longitudinal bands 479
Apparatus
– auditory 22, **124 ff**, 131
– lacrimal 135
– masticatory 22, **53 ff**
– vestibular **124 ff**, 131
– visual 134 ff
Appendix(-ces)
– of epididymis 355
– epiploicae 316
– fibrosa 308
– of testis 355
– vermiform 310, **314 ff**, 318, 328
– – Head's zone 209
– – ostium 317 f
– – position 300, 317
Aqueduct
– cerebral 67, 75 ff, **88**, 92, 96, 101, **114**, 118, 123, 144
– of cochleae 131
– posterior 114
– of vestibule 27, **131**
Arachnoid mater **91**, 94, 102, 120
– spinal 234, 236, **240**, 248
Arbor vitae of cerebellum 96, 118
Arch
– anterior, of atlas 167, **194**, 197
– aortic 97, 156, 171, 179, 253, **262 ff**, 268 f, 283 f, 289, 294, 342
– – of fetus 272 f
– arterial, of mesenteric artery 311
– azygos **283 f**, 286, 293
– costal 3 f, **201**, 204, 216 f, 220, 252, 274 f, 317
– – surface anatomy 208
– of cricoid cartilage 160
– dental 52
– iliopectineal 460 f, **469**
– palmar
– – deep 441, **443**
– – superficial 408, 435, 442
– plantar 483, **511**
– posterior, of atlas 194, 247 f
– pubic 450 f
– tendinous
– – of flexor digitorum superficialis muscle 430
– – of soleus muscle 473, 474, 503
– venous
– – dorsal, of foot 484, 489, 501, **504 f**, 508
– – jugular 172, 174, 410, 418
– vertebral **199 f**, 207, 235 f, 248
– – cervical 247
– zygomatic 20, **33**, 52 f, 62 f, 81
– – coronal section 64
– – of newborn 33

Page numbers in **bold** indicate main discussions.

Arcus costalis 203
Area
– of acoustic centers 133
– auditory 133
– bare, of liver 308, 328
– calcarina 142
– cortical
– – acoustic 103
– – premotor 103
– – reading comprehension 103
– – sensory speech 103
– – somatomotor 103
– – somatosensory 103
– – visuosensory 103
– – of Wernicke 103
– cribriform, of renal papilla 336
– intercondylar, anterior, of tibia 456
– of liver 309
– muscle-free, of pharynx 169
– of stomach 309
– vestibular, superior 132
– visual 142 ff
Areola **208**, 298
Arm (see also Limb, upper) 426 ff
– arteries 408 f
– axial section 444
– extensor muscles, position 14
– flexor muscles 398
– – position 14
– MRI scan 386, 444
– muscles 394 ff, **398 f**
– – deep layer 421
– – position 14
– – superficial layer 420
– nerves 411 f, 420, **426 ff**
– – cutaneous 412
– sagittal section 386
– skeleton 10
– surface anatomy 413 f
– veins 410
– vessels 420
Arteriole
– afferent, of glomerulus 339
– efferent, of glomerulus 339
Artery(-ies) **16**, 100
– alveolar
– – inferior 65, 82, **83 ff**
– – superior, posterior 65, 85
– angular 79, 81, 85, **170**
– appendicular 310, 314, **317 f**
– arcuate
– – of foot 483, 509
– – of kidney 339
– auricular
– – deep 65
– – posterior 82
– axillary **170**, 172, **188**, 211, 399, **408**, 423 f, 426 f
– – main branches 408
– basilar 31, 88, 91, **95 ff**, **100**, 118, 123
– brachial 399, 408, 415, 422, 424, 426 ff, 430, 435
– – profunda 408, 416
– buccal 65, **82**
– of bulb of penis 353, 359, 363
– capsular, lower, of kidney 338
– carotid 156, 183
– – common 97, 99, 154, **165**, 167, **170 ff**, 261, 276, **291**, 408, 426
– – – of fetus 272
– – external 65, 69, 71, 81, 99, **154**, **165 f**, **170 ff**, 408
– – internal 31, 64, 69, 71, **75 f**, 89, 94 ff, 99 f, 126, 148, **170 f**, 172, 408
– – – arteriogram 98
– – – loop 98
– cerebellar
– – inferior
– – – anterior **95 f**, 98, 100
– – – posterior **95 f**, 98, 100, 118
– – superior **95 f**, 98
– cerebral 94 ff
– – anterior 88, 94 f, **97 f**, 99 f, 113
– – circle of Willis 95, **100**
– – middle 94 f, 97 f, **100**
– – – parietal branch 96
– – – temporal branch 96
– – posterior 94, **97 ff**
– cervical
– – ascending **170**, 172, 187, 408, 426
– – deep 170
– – superficial **170**, 172, 244
– – transverse **170**, 172, 184, 274, 408, 426
– – – deep branch 243
– – – superficial branch 243
– ciliary
– – anterior **95**, 141
– – posterior 95
– – – long 141
– – – short 141
– colic
– – left 314, 324
– – – anastomosis with middle colic artery 324
– – – arteriogram 344
– – middle **310 ff**, 324 ff, 338
– – right **310**, 313 f, **325**, 344
– collateral
– – medial 420
– – middle 408, 421
– – radial 408, 420 f
– – ulnar
– – – inferior 408, 427
– – – superior 408, 428, 435
– communicating
– – anterior 95, 100
– – posterior 97, **100**
– coraco-acromial 423
– coronary 263, **270 f**
– – left 263, **266 ff**, 294, 296 f
– – – circumflex branch 271
– – – interventricular branch 263
– – MRI scan, stereoscopic 271
– – right 252, **263 ff**, **270 f**, 280, 297
– – – sinu-atrial branch 270
– cortical, radiating 339
– cystic 308, 326 f
– deep
– – of clitoris 377
– – of penis 351, 353, **358**, 359
– digital
– – dorsal, of foot 508
– – palmar 408, **442**
– – – common 408, 435, **441 f**
– – – proper 437 f, **441 f**
– – – – of thumb 441
– – – of thumb 442
– dorsal
– – of clitoris 377
– – of penis 353 f, **358 f**, 362, 364
– dorsalis pedis 483
– – deep plantar branch 508 f
– of ductus deferens 355
– epigastric 275
– – inferior 212, 216, 219 f, 223, 301, 345, **374**, 492
– – – pubic branch 224
– – superficial 212
– – superior 210, 212, 219 f, **274 ff**
– ethmoidal 96
– – anterior 31, 139, 141, 148
– – posterior 141
– facial 65, 79, **81**, 83, 99, 154, **170**, 172, 175, 410
– – transverse 65, **79**, 82, **170**, 172
– femoral 219 f, 301, 352, 372, 374, 378, 468, **491 f**, 514
– – circumflex
– – – lateral 483, **492 f**
– – – – ascending branch 492 f
– – – – descending branch 483, 492 f
– – – medial 483, **492 f**
– – – – ascending branch 493
– – entering the adductor canal 468
– gastric
– – left 323 ff
– – – esophageal branches 323, 345
– – right 314, **323 ff**
– – short 323 f, 326
– gastroduodenal 304, **323 ff**, 334
– gastro-epiploic 311, **323 f**
– gastro-omental 311, **323 f**
– genicular
– – descending 483
– – inferior
– – – lateral 483, 499 f
– – – medial 483, 499 f
– – middle 483

Page numbers in **bold** indicate main discussions.

– – superior
– – – lateral 483, 499 f
– – – medial 483, 499
– gluteal
– – inferior 358 f, **372**, 496
– – superior 359, **372**
– – – deep branch 495
– hepatic
– – arteriogram 344
– – common 304, 311, 323 f, 326
– – of fetus 273
– – proper 289, 304 f, 308 f, 311 f, **314**, 326 f
– – – left branch 323
– – – right branch 323
– humeral, circumflex
– – anterior 408
– – posterior 395, 408, 416 f, **420 f**
– ileal 313 ff, **325**
– ileocolic 310 ff, 317 f, **325**, 344
– iliac
– – circumflex
– – – deep 212, 220, 357, **483**, 492
– – – superficial 212, 220, **483**
– – common **291**, 324, 331, 340 f, **345**, 358 f
– – – with catheter 344
– – external 301, 340, 342, **345**, **357 ff**
– – internal 342, **345**, **357 ff**, 372
– – – main branches 359
– iliolumbar 359
– infra-orbital 65, 135
– insular 94
– intercostal 210, **214 f**
– – anterior 211
– – highest 212, **291**
– – medial branches 298
– – posterior 219, 286, **289 ff**
– – – dorsal branches 420
– – superior 170
– interlobar, of kidney 339
– interlobular, of kidney 338 f
– interosseous
– – anterior 408, 430, 435
– – – posterior branch 433
– – posterior 408, 433, **436**
– interventricular, anterior 260, 270, 280
– iridial 141
– jejunal 310 ff, **324 ff**
– of kidney 338 f
– labial
– – inferior 170
– – superior 170
– of labyrinth 31, **95**, 100
– lacrimal **95**, 139
– laryngeal, superior 154, 168, 171
– lingual 148, **154**, **170**
– – deep 155
– lumbar 347
– macular
– – inferior 141
– – superior 141
– mandibular, inferior 65
– masseteric 65, **81**
– maxillary **64 f**, 81 f, **83 ff**, 99, **170**
– – branches 65
– – – deep temporal 65
– – – pterygoid 65
– medial, of retina 141
– meningeal
– – anterior 31
– – base of skull 31
– – middle 31, 65, 85, 87, **89 f**, 129, 139
– – – parietal branch 90
– – posterior 31
– meningolacrimal 139
– – anastomosis with middle meningeal artery 139
– mesenteric 324 f
– – arterial arch 311
– – inferior **291**, 314 f, **324**, 339, 345
– – – anastomosis with middle colic artery 314 f
– – – course 344
– – – main branches 314
– – superior 253, **291**, 300, 304 f, **310 ff**, **325 ff**, 338 f
– – – arteriogram 344
– – – course 344
– – – main branches 310, **314**
– metacarpal, dorsal 436 f
– metatarsal
– – dorsal 483
– – plantar 483
– musculophrenic 210, 212, 220
– nasal
– – dorsal 170
– – inferior, of retina 141
– – posterior, lateral 148
– – superior, of retina 141
– obturator **358 f**, 370, 372, 483
– occipital 65, **83 f**, **87**, **170**, 227, 243, 247 ff
– – occipital branch 172
– ophthalmic **75**, **95 f**, 98, 100, 134, 139, **141**, 148
– ovarian 338, 370, 372
– – ovarian branch 372
– – tubal branch 372
– palatine
– – descending 65, 148
– – greater 148
– – lesser 148
– pallidostriate 94
– pancreaticoduodenal
– – inferior 326 f
– – superior 323
– – – anterior 326
– – – posterior 326
– perforating 483
– pericardiacophrenic 282, 291
– perineal 358
– – superficial 363
– peroneal 483 f, 503
– pharyngeal, ascending 148, 167
– phrenic, inferior 323, 338, 345
– plantar
– – lateral 483, **511 f**
– – – superficial branch 511
– – medial 483, **511 f**
– pollicis, princeps 408, 441
– popliteal 462, **483**, 496, **498 ff**, 503
– profunda
– – brachii 421, 427
– – – anastomosis with posterior humeral circumflex artery 420 f
– – femoris 483, 493
– of pterygoid canal 65
– pudendal
– – external 224, 483
– – internal 353, **358**, 359, 363 f, 372, 376, 495
– pulmonary 16, 264, **283 ff**, 291, 293
– – branches 254
– – of fetus 272 f
– – mediastinal dissection 255
– radial 400, **408**, **426 ff**, 431, 433, 435 f, 438, 442
– – dorsal carpal branch 436
– – superficial branch 445
– – superficial palmar branch 408
– rectal
– – inferior 358 f, **363 f**, 495
– – middle 359
– – superior 314, 324, **344**
– recurrent
– – radial 408, **428 ff**
– – ulnar 430
– renal **291**, 300, 334, **336**, 341, 345, 347
– – anterior branch 338
– – posterior branch 338
– – superior 339
– retinal 141
– – central **95**, 140 f
– of round ligament 372
– sacral
– – lateral 359
– – median 345
– – middle 372
– scapular
– – circumflex 390, 416 f, **420 ff**, 424
– – descending **170**, 408, 416
– – dorsal 170
– scrotal, posterior 363, 365
– segmental, inferior, anterior, of kidney 338
– septal 148
– sigmoid 314, **324**, 344, 358
– sphenopalatine 65
– spinal
– – anterior 31, 95, **100**, 236, 240
– – posterior 31, 95, **100**, 240, 248
– spiral, of renal pelvis 339

Page numbers in **bold** indicate main discussions.

Artery(-ies)
– splenic 289, **304 f**, 309, **323 ff**, 338 f, 345
– – arteriogram 344
– – posterior pancreatic branch 326
– subclavian 97, 99, 172, **179**, 186, 210, 212, 281, 283 ff, **291**, 342, 408, 426
– – of fetus 272
– – main branches 408
– subcortical, of kidney 339
– submental 154, **170**
– subscapular 408, 424, 427
– supra-orbital 141, **170**
– – medial branch 85
– suprarenal
– – inferior 338 f
– – middle 338
– – superior 338
– – – arteriogram 344
– suprascapular 170, 172, 390, **408**, 416 f, 426
– – anastomosis with circumflex scapular artery 416
– supratrochlear **95**, 141, **170**
– sural 499, 503
– temporal
– – deep 82, **85**
– – – anterior 83
– – inferior, of retina 141
– – middle 170
– – superficial 65, **79**, **83 ff**, 87, **170**, 172, 185
– – – anterior articular branch 82
– – – frontal branch 81, **82**, **170**
– – – parietal branch 81, **82**, **170**
– – superior, of retina 141
– testicular 222, 338, 353, **355**, 358 f
– thalamic 94
– of thigh 482 f
– thoracic
– – internal **170**, 179, 210, **212**, 219 f, **274 ff**, 282, 408, 410
– – lateral 170, 172, 204, **211 f**, 219, 408, 422, 424
– – superior 408, 424
– thoraco-acromial 170, 172, 184, **186 f**, 211, 274, 408, 419
– – acromial branch 419
– – pectoral branch 419
– thoracodorsal 408, 416, **419**, 422, 424, 427
– thyroid
– – inferior **170**, 171, 179, 187, 408
– – superior 154, **170**, 171 f, 175, 179, 187 f, 408
– tibial
– – anterior **483 f**, 500, 503
– – posterior 473, **483 f**, 500, 503
– tympanic, anterior 129
– ulnar 400, 408, **427 ff**, 431, 435, 442
– umbilical 273, **358 f**
– – obliterated 301
– – remnant **223**, 357
– uterine 372
– – ovarian branch 372
– vaginal 372
– vertebral 31, 64, 71, 73, 91, **95 ff**, 99 f, 167, **170 f**, 176, 179, 194, **245**, 248, 426
– – posterior arch of atlas 99
– vesical
– – inferior 359
– – superior 358 f
– zygomatico-orbital 87
Arthrology 10 ff
Articulation see Joint
Atlas 24, 161, 167, 191, **193 ff**, 198, 247, **381 f**
Atrium
– left, of heart 253, 265, 268 ff, 283, 291, 295
– – midsagittal section 332
– – orifices of pulmonary veins 295
– nasal 146
– right, of heart 252 f, **261 ff**, 265, 267, 280 f, 283, 293
– – of fetus 272
Auditory apparatus 22, **124 ff**, 131
Auditory pathway 133
Auricle 124 ff, **262**
– of atrium
– – left 264 ff
– – – of fetus 272
– – right 252, 261 f, **264 ff**, 268, 279, 281, 293
– – – of fetus 272
Axilla
– lymphatics 298
– medial wall 397
Axis 24, 161, 191, **193 ff**, 198, **381 f**

B

Back
– innervation 225, 230 ff
– – characteristics 233
– muscles 226 ff
– – deepest layer 228
– regions 225
– segmental arrangement 225, 233
– surface anatomy 225
Ball-and-socket joint 10
Base
– of cochlea 126 f, **131**
– of coracoid process 383
– of mandible 22 f
– of metacarpal bone 388 f
– of metatarsal bone 458
– of patella 457
– of proximal phalanx 388 f
– of sacrum **199**, 452 f
– of skull 20, **30 ff**, 86, 99
– – angle at the sella turcica 145
– – angulation 37
– – arterial circle of Willis 100
– – bones 23, **34**
– – canals 34
– – cranial nerves **31**, **76 f**, 100
– – fissures 34
– – foramina 34
– – inferior aspect 32 f
– – internal aspect **30 f**, 34
– – of newborn **33**, 35
– of stapes 130
Belly
– frontal, of occipitofrontal muscle 56
– posterior, of digastric muscle 54, 70
Bicuspid
– first 50
– second 50
Bifurcation
– of atrioventricular bundle 269
– of trachea 18, **254**, **284 ff**, 291
Bile duct(s) 304 f
– common **304 ff**, 308, 327
– extrahepatic 304 f, **326**
Bladder, urinary see Urinary bladder
Blood
– oxygenated 16
– venous 16
Body
– amygdaloid **109 f**, 112 f, **116 ff**, 142
– anterior
– – regions 208
– – surface anatomy
– – – in the female 208
– – – in the male 209
– of axis 194
– carotid 166 f
– cavernous see Corpus cavernosum
– of cervical vertebra 179, **203 f**
– ciliary 140
– – pars
– – – plana 140
– – – plicata 140
– of clitoris 373, 377
– of corpus callosum 101, **109**
– of epididymis 355
– of fornix 108 f, 115
– of gallbladder 306
– geniculate 109
– – lateral 133, **143 f**
– – medial 116, 133, 144
– of hyoid bone **152**, 160
– of incus 130
– of ischium 453
– mamillary 67 f, 88, 96, 101, 105, **112**, **144**
– of mandible 21 ff, **52**
– of maxilla 21 f
– – nasal surface 42
– of metacarpal bone 388
– of pancreas 304 ff, 326
– perineal 362 f, **373**, 375
– pineal 88, 101, 109, **117**, **122**

Page numbers in **bold** indicate main discussions.

– of pubis 453
– restiform 118
– retrosternal 410
– of rib 205
– of sphenoidal bone 26
– of sternum 201, 274, 381 f
– of stomach 302, 326
– trapezoid 133
– of uterus 369
– of vertebra 199 f
– vitreous 140, 150
Body wall
– abdominal
– – anterior 301
– – – arteries 212
– – – muscles, superficial 213
– – – segments 219
– – horizontal section 219
– – nerves 218 ff
– – posterior 326 ff
– – – lymph nodes 342 f
– – – lymph vessels 342 f
– – – peritoneal recesses 328 f
– – – veins 289
– – transverse section 217
– – vessels 218 ff
– anterior
– – muscles 209, 214 f
– – segments 209
– lower part 222
– surface anatomy 208 f
– thoracic 210 ff
– – anterior 210 ff
– – – arteries 212
– – – muscles, superficial 213
– – – segments 219
– – anterior region 418 f
– – horizontal section 233
– – nerves 218 ff
– – position of spinal nerves 233
– – posterior 342 f
– – – MRI scan 233
– – – veins 289
– – vessels 218 ff
Bone(s) 42, 157
– capitate **388 f**, 392, 438 f
– carpal 7, 190, **387 ff**, 441
– compact, of femur 8
– cranial 20, 37
– – of newborn 35
– cuboid 459
– cuneiform
– – intermediate **458**, 465
– – lateral 459, 465
– – medial 465
– ethmoidal 20 ff, 23, 34, 37, **38**, **40 ff**, 44 f, 47
– – of newborn 35
– – orbital part 21
– facial 20, **28**
– – lateral aspect 52
– frontal 7, 20 ff, 23, **28 f**, 34, 36 f, **42 ff**, 47, 52, 190
– – of newborn 35
– – orbit 134
– – squamous part 28, 42, **44 f**
– – temporal surface 44
– hamate **388 f**, 392, 438 f
– hyoid 22, **62 f**, 69, 71, 88, **151 ff**, 155 ff, **158**, **160 ff**, 163, **168**, 171, 177
– – position 161
– incisive **33**, 45
– lacrimal **20 ff**, 28, 37, 47, 52
– – orbit 134
– lunate **388 f**, 392, 438
– metacarpal 7, 190, **387 ff**, 441
– – axial section 445
– – first 392, 438 f
– – of thumb 387 ff
– metatarsal 7, 447, **458 f**
– nasal 20 ff, 37, **47 f**, 52, **146**
– – orbit 134
– of nasal cavity 48
– navicular **458**, 465 f
– – articular surface 466
– occipital 7, 20 f, **24 ff**, **27 ff**, 33 f, **37 ff**, 42, 46 f, 191 ff, 203
– – basilar part 25, 33
– – lateral part 33, 39
– – of newborn 33, **35**
– – squamous part 20 f, 25, **28**, 33, 39 ff, 44
– – – lower part 27
– – – upper part 27
– palatine 20, **33**, 37, **39 ff**, 42, **44 f**, 48 f
– parietal 7, 20 ff, 23, **29**, 34, 37
– – of newborn 33
– petrous 86
– pisiforme 389, 393, 401 f, 406
– pubic 358
– scaphoid **388 f**, 392, 438 f
– of skull 20 ff
– sphenoidal 20 ff, **23 ff**, 28, 33 f, **37 ff**, **41 f**, 44 f
– – greater wing see Wing, greater, of sphenoidal bone
– – lesser wing 22 f, **25 f**, **30**, 34, **38**, 40 ff, 44, 134
– – of newborn 35
– spongy, proximal end of femur 8
– tarsal 7
– temporal 20 ff, 23, **26 ff**, 33 f, 37, 46 f, 52, **127**
– – of newborn 35, 127
– – petromastoid part 127
– – petrous part 20, **33 f**, 37, 86, 125, 127 f, 132
– – – frontal section 128
– – squamous part 20 f, **27 f**, 127
– – – of newborn 35
– – tympanic part 20 f, 27
– trapezium 388 f, 438 f
– trapezoid **388 f**, 392, 438 f
– triquetral **388 f**, 392, 438 f
– zygomatic 7, 23, 28, 33, 37, 45, **47**, 52, 54, 134
– – orbital surface 45
Bone marrow 17
Border
– anterior, of spleen 309
– inferior, of lung 257
– interosseous
– – of fibula 456
– – of tibia 456
– lateral, of scapula 383 f
– medial
– – of scapula 383, 394
– – of tibia 456
– posterior, of fibula 456
– superior
– – of scapula 383
– – of spleen 309
Brachium of inferior colliculus 116, 133
Brain 3, **66 ff**, **86 ff**, **101 ff**
– arterial supply areas 94, 98
– arteries 94 ff
– blood flow 94
– coronal section 118 f
– cross section 118 f
– dissections 106 ff
– horizontal section 120 ff
– inferior aspect 67, **101**
– median section 92 f, 96
Brain stem **69**, **71 ff**, 86, 113, **116 f**
– auditory pathway 133
– cranial nerve nuclei 116
– median section 92 f
Breast, lymphatics 298
Breast tissue 298
Bronchial tree **254 f**, 259, 285
– mediastinal dissection 255
Bronchus(-i) 254, 257
– primary
– – left 286, **288 f**, 291
– – – of fetus 272
– – right 290
– secondary 288
– segmental 254
Bulb
– of aorta 252, **262**, 267
– olfactory 31, **67 f**, **77**, 91, 101, 105, 109, 148
– of penis **348 f**, 351, **354**, 357
– of vestibule 367, **372 ff**, 376
Bulla, ethmoidal 37, 55, 147
Bundle
– atrioventricular 269
– – bifurcation 269
– of His 269
Bursa
– calcaneal 465
– omental see Sac, lesser
– suprapatellar 462 ff

Page numbers in **bold** indicate main discussions.

C

Calcaneus 7, 447, **459**, 465 ff
– articular surface, talar
– – anterior 466
– – posterior 466
– of newborn 9
Calcar avis 106, 108, **110**, **112**
Calvaria **29**, 89 ff, 99
Calyx, renal 337
– major 336
– minor 336
Canal
– adductor 468
– – entrance 492
– anal 3, **348 f**, 378
– – midsagittal section 332
– carotid 27, 31, **33**, 46, 100, 127 f, **166**
– central 88, 93, 118
– condylar 25, 27, **33**, 39
– facial 31, 127 f, 131 f
– gastric 302
– for greater petrosal nerve, hiatus 27
– hypoglossal 25, **30 f**, **33**, 36, 39, 46, 193, 195
– incisive **33**, 42, 147
– infraorbital 46
– inguinal **221 f**, 374
– – in the female 224, 334
– – in the male 221 ff, 353
– mandibular 82, 167
– – entrance 52
– musculotubal 131
– nasolacrimal **46 f**, 134
– obturator 460 f
– optic 23, 25 f, **30 f**, 34, 38, 44, 46 f, 134, 142
– osseus, semicircular
– – anterior **124 ff**, 131 f
– – lateral **124 ff**, 128, 131 f
– – posterior 131 f
– palatine
– – greater 40, 46
– – lesser 46
– pterygoid 25, **33**, 45 f, 148
– pudendal, entrance 495
– pyloric 302
– sacral 451 ff
– spiral, of cochlea 127
– vertebral 90, 193, 200, **205**, **234 ff**, 239
– – sagittal section 240
Canaliculus
– chordae tympani 127
– cochlear 27
– lacrimal, inferior 135
– mastoid 27, 127
Canalis
– carpi 14, **401**, 406 f, 439, 441, 443, 445
– musculotubarius 27
Canine 50 f
– permanent 51
Capitulum of humerus **385**, 387, 391, 403
Capsula adiposa perirenalis 304 f
Capsule
– articular 12
– – of atlanto-occipital joint 194
– – of carpometacarpal joint of thumb 393
– – of elbow joint 391, **403**
– – of hip joint 460
– – of interphalangeal joint
– – – of fingers 393
– – – of foot 466
– – knee joint 12, **463 f**
– – of metacarpophalangeal joint 393
– – – of thumb 393
– – of shoulder joint 390
– – of temporomandibular joint 55
– – of wrist joint 392
– external 118, 122
– fibrous, of kidney 336
– – vessels 339
– internal 94, **107**, 111 f, **113**, 115 ff
– – anterior limb 122
– – posterior limb 122
Cardia 304
Carotid sheath 176
Carotid sinus nerve 166 f
Carpal tunnel 14, **401**, 406 f, 439, 441, 443, 445
Cartilage(s)
– alar
– – greater 49
– – lesser 49
– articular 8
– – of condylar process 54
– – of femur 462
– – of knee joint 12
– – of shoulder joint 15
– arytenoid 160 f
– corniculate 160
– costal 7, 190, **201**
– cricoid 157, **160 f**
– of larynx 160
– nasal 49
– – lateral 49
– septal 49
– thyroid 153, 156, **160 ff**, 175, 261
– tracheal 160 f
Cartilaginous growth plates 7
Caruncle, sublingual 155
Cauda equina 234, 240, 300, **487**
– horizontal section 330, 334
Caudal 4
Cavity(-ies)
– abdominal
– – frontal section 325
– – horizontal section 330 f
– – midsagittal section 321
– – MRI scan 253, 325, **331**
– – parasagittal section 302, 335
– – posterior 342 f
– – sagittal section 253
– – veins of posterior wall 289
– articular 12
– – elbow joint 445
– – hip joint 514
– – humeroradial joint 445
– – knee joint 462
– – shoulder joint 10, **15**
– cranial, coronal section 64
– glenoid **381 ff**, 384, 390
– nasal 7, 22, 31, 86, **90**, 92, **145 ff**
– – arteries 148 f
– – bones 48
– – coronal section 64
– – horizontal section 150
– – lateral wall 147 ff
– – – nerves 149
– – median section 147
– – nerves 148 f
– oral **50**, 86, 145, 152 f, 155, 165
– – coronal section 50, 64
– – floor 152 f
– – median section **90**, 147
– – muscles 152 f
– – – of the floor 152 f
– – posterior aspect 165
– – vestibule 55
– pelvic
– – female 370
– – – horizontal section 371
– – – midsagittal section 366
– – – MRI scan 366
– – – sagittal section 366
– – horizontal section 4
– – male
– – – coronal section 357, **378 f**
– – – horizontal section 356, **378 f**
– – – midsagittal section 348
– – – MRI scan 348, 354
– – – nerves 361
– – – parasagittal section 358
– – – sagittal section 354
– – – vessels 358 f
– – MRI scan 4 f
– of septum pellucidum 106, 122
– of shoulder joint 390
– thoracic
– – frontal section 285
– – MRI scan 253, 285
– – parasagittal section 335
– – sagittal section 253
– – veins of posterior wall 289
– tympanic 71, 122, 125 f, **130 ff**
– – medial wall 128 ff
– – roof 124
– – walls 130
– ventricular of brain (see also Ventricle) 114 f
Cecum 314, 317, 328

Page numbers in **bold** indicate main discussions.

– horizontal section 331
– position 300
Center acoustic 133
– primary 133
– tertiary 133
Cerebellum 68, 76 f, 86, 88, 92 f, 96, **104 f**, 113, 248
– median section 92 f, 104
Cerebrum 18, **101 ff**, 241
– in neonate 241
Cervix of uterus 369
– vaginal portion 332, **368 f**, 372
Channel, supinator 432
Chiasma, optic 67 f, **75 f**, 88, 92 ff, 101, 105, 136, 142
– lesion 143
Choana 45, 148, 165, **166**
– of newborn 33
Chondrocranium 22
Chord, oblique 391
Chorda(-ae)
– tendineae 263, **266**, 268
– tympani 64, 70 ff, 79, 126, **129**, 130, 148
– – extracranial part 129
– – intracranial part 129
Choroid 140
Circle, arterial, of Willis **95**, **97**, 100
Circulation
– collateral, of shoulder 416
– lymphatic 16 f
– portal 16
– pulmonary 16
– systemic 16
Circulatory system 16
– fetal 272 f
– portal 313
– shunts 272
Circumference, articular
– of radius 386 ff
– of ulna 386 ff
Cistern
– cerebellomedullar 87 f, 91, **147**, 197, 234, 248 f
– chiasmatic 87
– interpeduncular 87
– of lateral cerebral fossa 91, **94**
– of pons 196
– subarachnoid 87
Cisterna chyli 17, 342 f
Claustrum 94, 118, 122
Clava 117
Clavicle 3, 7, 170, 176, 179, 190, **210 ff**, 274, 294, **381 ff**
– articular facet
– – for the acromion 383
– – for the sternum 383
– end
– – acromial **383**, 390
– – sternal 383
– impression of costoclavicular ligament 383
– surface anatomy **208**, 413 f
Clitoris 366, **372 ff**
Clivus 25, 27, **30**, 38, 195
– Dura mater 91
Coccyx 3, 7, 190, 192, **199 f**, 202, 447 ff, 451, **453 ff**
– surface anatomy 488
Cochlea **124 ff**, 128, 131
– base 126
Colliculus(-i)
– inferior, of midbrain 69, 105, 113, 133, **116 ff**
– of midbrain 88, 92 f, 101, 109, **116 ff**, 143
– seminal 350 f, 356 f
– superior, of midbrain 108, **116 ff**
Colon
– ascending 310, 314, 317
– – blood supply 344
– descending 214, 314, 318
– – blood supply 344
– Head's zone 209
– position 3
– sigmoid **314**, 316 ff, 332
– transverse 253, 300, 310, **316 ff**
– – midsagittal section 332
Column
– of fornix 105, 107, 109, **116 ff**, 121 f
– lateral, of erector spinae muscle 214, 216
– medial, of erector spinae muscle 214, 216, **229**
– renal 336
– vertebral see Vertebral column
Commissure
– anterior 88, 92 f, 96, **101**, 109 f, 112, 114, 117 f
– of fornix 106
– habenular 109
– labial, posterior **373**, 375
Concha 124
– nasal
– – inferior 20, 22 f, 36 f, 42, 44, **48**, 55, **88**, 92, 134 f, **145 ff**
– – – inferior border 48
– – – maxillary process 46, **48**
– – middle 22 f, 33, **36 ff**, 40, 44 f, **48**, **88**, 134, **145 ff**
– – superior 36 f, **48**, **88**, 146 f
Condyle
– lateral
– – of femur 9, 447, 455, 457, **463**
– – of tibia 447, 456, **462 f**
– medial
– – of femur 9, 455, **463**
– – of tibia 456
– occipital 21, 25, 27, **33**, 36, 46, 64, 193, 195
Cone
– arterial 335
– medullary, of spinal cord 238 f
Confluence of sinuses 77, **87**, **89 f**, 249
Conjugate
– diagonal 452, **454**
– true 452, **454**
Conjunctiva, palpebral, of lower lid 135
Connection, intertendinous 404
Conus
– arteriosus 266, 268
– – horizontal section 296
– elasticus 160
– medullaris 234, **237**, 240 f
– – midsagittal section 332
– – in neonate 241
Coper's gland 351
Cord
– spermatic 216 ff, 220 ff, **223**, 349, 352, **355**, 358, 491
– – surface anatomy 208
– spinal see Spinal cord
– umbilical 241
– urachus 223
Cornea 134, 136, **140**
Cornu see also Horn
– greater, of hyoid bone 63, 69, **152**, 160, 169
– inferior, of thyroid cartilage 161
– lesser, of hyoid bone **152**, 160
– sacral 199
– superior, of thyroid cartilage 160 ff
Corona
– of glans penis 354
– radiata 111 f
Corpus
– callosum 64, 87 f, 94, 109, 241
– – coronal section 118
– – fiber system 106
– – median section 92 f, 241
– – in neonate 241
– cavernosum
– – of clitoris 368, 372 f
– – of penis **348 ff**, 351 ff, 359, 362
– spongiosum of penis 348 f, **351 ff**, 362
– sterni 203
Cortex
– cerebral 87, 94, **120 ff**
– insular 115
– of kidney 336
– limbic 101
– striate 123, **142**
– – frontal section 144
– of suprarenal gland 336
– of temporal lobe 118
– visual 123, **142**, 144
Costae fluctuantes 203
Cowper's gland 348 ff, 354, **356**
Cranial 4
Crest
– conchal 40, 42, 44
– frontal 28, **30**
– of greater tubercle of humerus 385
– iliac 3, 340, 449, 453, 494 f
– – surface anatomy 488 f
– infratemporal 52
– – of sphenoid 21, 25 f, 38
– intertrochanteric 454 f

Page numbers in **bold** indicate main discussions.

Crest
– lacrimal
– – anterior 41
– – posterior 22
– of lesser tubercle of humerus 385
– nasal 40, 42, 44 f
– of nasal septum 148
– occipital
– – external 25
– – internal 27, **30**, 39, 42
– sacral
– – intermediate 199, 452
– – lateral 199, **453 f**
– – median 199 f, 238, **451**, 453 f
– sphenoidal 25
– supraventricular 281
– transverse, of internal acoustic meatus 126
– urethral 350
Crista
– galli **30**, 34, **37 f**, 40 f, 49, 88, 148, **151**
– spiralis ossea 128
– terminal 266, 293
Crossing of tendons
– in leg 476 f
– in sole 476 f, **480 f**
Crus 350
– anterior, of stapes 130
– cerebri 75
– of clitoris 368, **373**, 375 ff
– commune 131
– of fornix **107**, 108
– lateral, of superficial inguinal ring 221, 374
– long, of incus 129 f
– medial, of superficial inguinal ring 374
– penis 349 ff, **354**, 357, 362, 364
– posterior, of stapes 130
– right
– – of diaphragm 347
– – of lumbar part of diaphragm 292 f
– short, of incus 129 f
Culmen of vermis 104
Cuneus 144
Cupula 127, **131**
Curvature
– cervical 202
– greater, of stomach 302 f, **319 f**, 326
– – longitudinal muscle layer 303
– lesser, of stomach 302 f, 319 f, **322**
– – longitudinal muscle layer 303
– lumbar 202
– thoracic 202
Cusp
– anterior, of tricuspid valve 266
– semilunar
– – anterior, of pulmonic valve 267
– – left
– – – of aortic valve 267
– – – of pulmonic valve 267
– – posterior, of aortic valve 267
– – right
– – – of aortic valve 267
– – – of pulmonic valve 267
Cuspid (canine) 50 f
– permanent 51

D

Declive of vermis 104
Decussation
– of pyramidal tracts 111, **116**
– of superior cerebellar peduncle 105
Demifacet
– inferior, for head of rib 199
– superior, for head of rib 199
Dens of axis 88, 91 f, 167, 193 ff, **199**
Dentition 50
Desmocranium 22
Diameter
– largest, of pelvis 454
– oblique 452
– transverse 452
Diaphragm 16, 210, 261, **274 ff**, 279 ff, 283, 286, **289 ff**, 294 f
– central tendon 285, **288**, 293, 307, 339
– changes of position during respiration 292
– costal part 288, 292 f
– lumbar part **292**, 323, 337
– – right crus 292 f
– midsagittal section 332
– oral 152
– pelvic
– – in the female 376
– – in the male 362 ff
– – muscles 362, 365
– position 3
– sternal part 288
– urogenital
– – in the female 375 f
– – inferior fascia 362
– – in the male 349, 359, 362
– – muscles 362, 365
Diaphragma sellae 77
Diaphysis see Shaft
Diastole 264
Diencephalon 93
Digitations, hippocampal 109, **110**, **112**
Diploe **30**, 87, 89, **97**
Directions of the body 4 f
Disc
– articular
– – fibrocartilagenous 12
– – of sternoclavicular joint 179
– – of temporomandibular joint 54, 56, 81
– – of wrist joint 392, 438
– intervertebral 7, 91, 200, 202
– – cervical 196
– – – MRI scan 197
– – inner core 206
– – lumbar 206 f, 238 f, 332, **448**
– – lumbosacral 206
– – midsagittal section 332
– – MRI scan 240
– – outer portion 206
– optic 141
Dorsal 4
Dorsum
– of foot 504 ff, **508 f**
– – deep layer 509
– – middle layer 509
– – superficial layer 508
– of hand 436 ff
– sellae 25 f, **30**, 34, **36**, 38, 41, 46, 77, 195
– – of newborn 35
Douglas' pouch 332, **366 f**, 370 f
Duct
– cystic **304 f**, 308 f, 327
– ejaculatory 348 ff, **356**
– endolymphatic 130 f
– epididymal 355
– hepatic **304 f**, 310
– – common 306, 308, 327
– lymphatic, right 342
– nasofrontal 146 f
– nasolacrimal **135 f**, 147
– – opening 147
– pancreatic **304 ff**, 327
– – accessory **305 f**, 327
– parotid 54, 60, 63, **79**, 85, 153, **155**, 170
– perilymphatic 131
– semicircular
– – anterior 125, 128 f
– – lateral 125, 128 f
– – posterior 125, 128 f
– submandibular 154 f
– thoracic 17, 172, **174 f**, 186 f, 286, 289, 342
– – course 343
Ductus
– arteriosus Botalli 272 f
– – remnant 263, 268
– deferens 222 f, 238, 340, **348 ff**, 353, 356 f
– venosus of Arantius 272 f
Duodenum 304 ff, 310, 326
– ascending part 366
– descending part 306, **319 f**, 334
– Head's zone 209
– horizontal part 325, 327
– superior part 320
Dura mater **90 f**, 99, 120, 236, 300
– cranial 86 ff, 89 f
– spinal 71, 73, 234 f, **239 f**, 247 ff

E

Ear
– internal 31, **124 ff**, **130 ff**

Page numbers in **bold** indicate main discussions.

– longitudinal section 124 ff
– middle 124 ff, **128 ff**
– outer 124 f
Elbow joint 10, **386 ff**, **391**
– axial section 445
– axis
– – of extension 403
– – of flexion 403
– – of rotation 403
– coronal section 10, 391
– effect
– – of the extensor muscles 14
– – of the flexor muscles 14
– ligaments 10, **391**
– MRI scan 10, 391
– of newborn 9
Eminence
– arcuate 27, **125**
– carpal, radial 406
– collateral 109
– frontal 35
– iliopubic 449, 453 f
– intercondylar 456 f
– parietal 29, **35**
Endometrium 378
Epicardium 283
Epicondyle
– lateral
– – of femur 455, 457, **462 ff**
– – of humerus **385**, 391, 403 f
– medial
– – of femur 455, 464
– – of humerus **385**, 391, 399 f, 427
Epididymis 340, **348 f**, 351, 353, 355
– longitudinal section 355
Epiglottis 88, 91 f, 148, 157, **160**, 163, 165
– of newborn 157
Epiphysis 116
– distal, of femur 9
Esophagus 88, 283 ff, 289
– abdominal part 288, **292**
– Head's zone 209
– horizontal section 296
– thoracic part 288, 291
Eustachian Valve (Valve of inferior vena cava) 272
Eversion of foot, axis 466
Exostosis 392
Expiration
– action of internal intercostal muscles 204
– change in the position of diaphragm 292
Extensor retinaculum **404 ff**, 432, **436 f**
– inferior, of leg 475, 478, 508 ff
– superior, of leg 475, 478, 508
– tunnels 404
Extremity see also Limb
– caudal, of caudate nucleus **110 ff**, 116
Eye
– accommodation 140
– corresponding, blindness 143
– fluorescent angiography 141
– fundus 141
Eyeball 70 f, 135 f
– anterior segment 140
– organization 140
– sagittal section 134, 140
– vessels 141
Eyelid 135
– upper 135

F

Facet
– articular 199
– – inferior
– – – of articulation with head of rib 205
– – – of vertebra 199
– – superior
– – – of atlas 194, 199
– – – of axis 194
– – – of vertebra **199**, 205
– – of vertebra **199**, 200, **205**
– for tubercle of rib 205
Falx
– cerebelli 88
– cerebri 69, **76 f**, **88 f**, 99, 122, 142, 249
– inguinalis 222
Fascia
– antebrachial 400, 435
– – distal part 442
– cervical, lamina
– – pretracheal 176, 181 f
– – prevertebral 176
– – superficial 176, 180
– cremasteric 353
– crural 505
– – deep layer 484
– – superficial 484, 498, **504**
– dartos 222
– deep, of penis 351
– of external abdominal oblique muscle 217
– inferior, of urogenital diaphragm 362
– investing, superficial, of perineum 365
– lata 498
– obturator 365
– pectoral 298
– perineal 365
– pharyngobasilar 166, 169
– spermatic
– – external 222, 352
– – internal 222, 352, **355**
– temporal **60 ff**, 81
– thoracolumbar 216, 219, 227, **471**
– transversal 214, 216 f, 224
Fasciculus
– longitudinal
– – dorsal 109
– – medial 118
– mamillotegmental 109
– mamillothalamic 109 f
– of Schütz 109
– of Vicq d'Azyr 109 f
Fastigium 104
Fat pad
– buccal 170
– infrapatellar 462, 464
– of inguinal canal 224
Fatty tissue
– epicardial 262
– of mons pubis 375
– orbital 134
– subcutaneous 214
Femur 7, 12, 190, 447 f, **454 f**, 457, 462 ff
– coronal section 8 f
– diaphysis 8, 455
– MRI scan 8
– of newborn 9
– ossification 9
– proximal end 8, 455
– X-ray 8
Fenestra
– cochleae **127 ff**, 130
– vestibuli **127**, 131
Fiber(s)
– arcuate, cerebral 111, 118
– commissural 144
– corticospinal 118
– intercrural 221 f, 224
– pontine, transverse 111, 118
– radiating, of corpus callosum 106
– zonular 140
Fibula 7, 12, **447**, **456 ff**, 462 ff
– of newborn 9
– upper end 456
Field, visual 143
Filum(-a)
– radicularia posterior 100, 247, 249
– terminale 234 ff, **237 f**
Fimbria(-ae)
– hippocampal 108 f, 112
– of uterine tube 368 ff
Finger
– abduction 407
– adduction 407
– joints 393
– ligaments 393
– longitudinal section 407
– MRI scan 407
Fissure 23
– cerebral, longitudinal 68, **101 f**, **106**
– horizontal
– – of cerebellum 103
– – of right lung **254**, 256 f, 277 f
– oblique
– – of left lung **254**, 256 f
– – of right lung **254**, 256 f, 277

Page numbers in **bold** indicate main discussions.

Fissure
– orbital
– – inferior 22 f, 33, 41, **47**, **134**
– – superior 22 f, 25, **30 f**, 34, 38, 40 f, **47**, **134**, 195
– petrotympanic 27, 127
Flexor retinaculum
– of forearm **400 ff**, 407, 435, 439, **441 f**
– of hand 14
– of leg **474 f**, 477, 503
Flexure
– colic
– – left 294 f, **310**, 314, 320, 326
– – right 319 f
– duodenal, inferior 312
– duodenojejunal 304, 310 ff, 316, 318, **325 ff**
Flocculus of cerebellum 68, **104**, **116**
Floor
– of the oral cavity 152 f
– pelvic, muscles 362
Fluid
– cerebrospinal 238
– – flow 87
– synovial 12
Fold(s)
– ary-epiglottic **152**, 162 f, 165
– axillary
– – anterior 397
– – posterior 397
– duodenal
– – inferior 318
– – superior 318
– gastropancreatic 320
– ileocecal 318
– interureteric 350
– of iris 140
– of mucous membrane
– – of gallbladder 306
– – of stomach 302
– recto-uterine 370, **378**
– salpingopalatine 147
– salpingopharyngeal 146 f
– umbilical 370
– – content 301
– – lateral **223**, 349
– – medial **223**, 349 f, 357
– – median **223**, 301, 357, 370
– vestibular 163
– vocal 88, 91, **157**, 163
Fontanelle
– anterior 35
– anterolateral 33, **35**
– mastoid 33, **35**
– posterior 35
– posterolateral 33, **35**
– sphenoidal 33, **35**
Foot **458 f**, 504 ff
– axis
– – for eversion 466
– – for inversion 466
– coronal section 507
– cross section 512 f
– ligaments 466 f
– MRI scan 507
– muscles 478 ff
– – extensor 478
– – flexor 471 ff
– – – deep 476 f
– of newborn, X-ray 9
– region, posterior 507 ff
– sagittal section 465
– skeleton **458 f**, 465
Foramen(-ina)
– alveolaria 41, 46
– cecum 28, **30**
– epiploic **319 ff**, 323, 327 f
– – midsagittal section 332
– ethmoidal 134
– – anterior 28, 46 f
– – posterior 46 f
– infra-orbital 22 f, 41 f, 44 f, **47**, 70, **135**
– infrapiriform 494 f
– interventricular, of Monro 88, **96**, 101, **107**, **114**
– intervertebral 202, **205 f**, 238
– jugular **30 f**, **33 f**, 195
– lacerum 26, **30**, 128, 166
– magnum 25, **27**, **30 f**, **33 f**, 39, 64, 91, 193, 195
– mandibular 36, **52**, 54 f
– mastoid 27
– mental 20 ff, 23, **51 f**, 70 f, 85
– nasal 47
– nutrient 455
– obturator 450, 453
– ovale 25 f, **30 f**, **33 f**, 38, 127, 166, **272 f**
– palatine
– – greater 33, 37, 45, 166
– – lesser 33, 45, 166
– parietal 29
– rotundum 25 f, **30 f**, 34, 38, 45 f, 74
– sacral
– – anterior 452, 454
– – posterior **199**, 200, 451, **453 f**
– sciatic
– – greater 460, **494 f**
– – lesser 460, **494 f**
– singulare 126
– sphenopalatine 46
– spinosum 25 f, **30 f**, 34, 38
– stylomastoid 27, 31, **33**, 72, 79, 128, 166
– supra-orbital 42, **44 f**
– suprapiriform 494 f
– transversarium 199
– vertebral 199
– zygomaticofacial 28
Forceps
– major of corpus callosum 106
– minor of corpus callosum 106
Forearm
– arteries 408 f, 433
– axial section 431, 445
– blood vessels 431, 433
– bones 386 ff
– extensor muscles 404 f
– flexor muscles 400 ff
– MRI scan 431
– muscles 400 ff, 431
– nerves 431 ff
– – course 432
– region
– – anterior 434 f
– – posterior 432 f
Foreskin 348
Formation, reticular 118
Fornix 92, **101**, 112, **116**
– anterior, of vagina 366, 369
– conjunctival 150
– – inferior 134
– – superior 134
Fossa
– acetabular 453, 461
– axillary 397
– canine 41, 45, 52
– cerebellar 27
– for cerebellar hemisphere 25
– cerebral 27
– for cerebral hemisphere 25
– condylar 25
– coronoid 385, 391
– cranial
– – anterior 30 f
– – middle 30 f
– – posterior **30 f**, 39
– hypophysial 25 f, **30**, 34, 36 ff, 49, 77, 90
– – of newborn 35
– iliac **448 f**, 453
– incisive 45
– infraclavicular 208
– infratemporal 31, 52
– inguinal, lateral 301
– intercondylar 455, 457, 464
– interpeduncular 68, 101, **105**, 144
– ischiorectal 357
– jugular 27, 128, 157
– for lacrimal gland 28
– mandibular 27 f, **33**, **50**, 54, 129, 166
– navicular, of urethra 348
– ovalis 266, 293
– popliteal **473**, 484, 496, **498 ff**, 501
– – coronal section 498
– – deep layer 499 f
– – deepest layer 500
– – lymph nodes 17
– – middle layer 499
– – MRI scan 498
– – surface anatomy 488
– pterygopalatine 31, 37, **46**, **74 f**
– radial 385, 391

Page numbers in **bold** indicate main discussions.

– retromandibular 170
– rhomboid 69, 71, 73, 117 f, 165
– scaphoid 124
– sublingual 52
– submandibular 52
– supraclavicular
– – greater 157
– – lesser 157
– supraspinous 383
– supravesical 301
– temporal 20, 52
– triangular 124
– trochlear 28
Fovea
– centralis 141
– – projection of light 140
– of head of femur 455, 461
– submandibular 36
Frenulum
– of clitoris 373, 375
– of ileocecal valve 318
Fundus
– of eye 141
– of gallbladder 306 ff, 319, 326
– of stomach **302 f**, 320
– of urinary bladder 351
– of uterus 369
– – insertion of uterine tube 370

G

Galea aponeurotica **56 ff**, 62, 65, 81, 87, 242 ff
Galen's vein 147
Gallbladder **304 ff**, 308 ff, **319 f**, 327 f
– Head's zone 209
Ganglion(-ia) 166
– autonomic 346
– celiac 310, 337, 341, 347
– cervical 73
– – inferior, of sympathetic trunk 347
– – middle 164, 187, **347**
– – superior 148, 164
– – – of sympathetic trunk 167, 170, 185 f, **347**
– ciliary 70 f, 74 f, 85, 137, 139, **143**
– geniculate 72, 79, 124, 126, 128
– hypogastric, inferior 347
– impar 347
– intramural 18
– mesenteric, inferior 347
– otic 71
– prevertebral 18
– pterygopalatine 70 f, 148
– spinal 71, **100**, 233 f, 236, 247 f
– – dural sheath 73
– – meningeal covering 235
– spirale 133
– stellate 187
– submandibular 83, 85, 153
– sympathetic 167, 170, 185 f, 289 f, 337, **347**
– of sympathetic trunk 347
– trigeminal 31, **70 f**, 74 ff, 85, 138, 148
Genital organs
– female 367 ff
– – external 373 f
– – – cavernous tissue 373, **375**
– – internal 368 ff
– – – arteries 372
– – – lymph vessels 372
– – position 367
– male 348 ff
– – arteriography 359
– – external 352 ff, 362
– – internal 355 f
– – nerves 361
– – position 349
– – vessels 352, **358 f**, 363
Gennari, line of 144
Genu
– of corpus callosum **101**, 106 f, 109, 120, 122
– of facial nerve 72
– of internal capsule 122
– of optic radiation 144
Gingiva of upper jaw 63
Glabella 21 f
Gland(s) 350
– accessory, of male genital organs 356
– bulbo-urethral 348 ff, 351, 354, **356**
– – orifices 350
– of Cowper 348 f, 351, 354, **356**
– lacrimal 71, 74, 85, 135, 138
– mammary 212, 298
– – lymphatics 298
– palatine **50**, 167
– parathyroid 169
– parotid 60, **79 f**, **154 f**, 180, 188
– pituitary 37, 88 ff, 123, 142, **150**
– salivary 155
– sublingual 50, **151**, **154 f**
– submandibular 64, 71, **79**, 85, 151, **154 ff**, 176 f, 179
– suprarenal 305, 319, **335 ff**, 341
– – arteries 338
– thymus see Thymus
– thyroid 156, 163 f, 169, 171, 176, 178, **276 ff**, 285
– – pyramidal lobe 186
– – regional anatomy 179
– vestibular, greater 372 f, 375
Glans
– clitoridis 368, **373**, 375
– penis 348, **351 ff**, 354
Globus pallidus 94, 118, 122
Glomerulus 339
Glottis 163
Granulations, arachnoid **87**, 102
Gray matter 118, **120 f**
Groove
– of aortic arch 257
– for auditory tube 33
– of azygos arch 257
– chiasmatic 25
– deltopectoral 298, 399, 410, **418**
– of esophagus 257
– for greater petrosal nerve **30**
– infra-orbital 39 ff, 42, 44 f, 47
– lacrimal 41 f, 52
– for middle meningeal artery 27, 29, 34, **36**, 49, 146
– mylohyoid 36, 55
– nasolacrimal 39
– obturator 453
– for occipital artery 33
– for radial nerve 385
– for sigmoid sinus 27, **30**, 34, 36
– of subclavian artery 257
– for superior petrosal sinus 27, **30**
– for superior sagittal sinus 25, 27 f, 42
– for tendon of peroneus longus muscle 459
– of thoracic aorta 257
– for transverse sinus 25, 27, **30**, 42
– for ulnar nerve 385
Gubernaculum testis 355
Gyrus(-i)
– angular 103
– cingulate **101**, 105
– dentate 108, 112
– frontal
– – inferior 103
– – middle 102 f
– – superior 103
– of Heschl 133
– long, of insula 111
– occipitotemporal
– – lateral 101
– – medial 68, 101
– orbital 68, 101
– parahippocampal 68, **101**, 108
– postcentral 101 f
– precentral 101 ff
– rectus 101
– short, of insula 111
– straight 68
– of striate cortex 144
– supracallosal 109
– supramarginal 103
– temporal
– – inferior 103
– – middle 103, 133
– – superior 103, 133
– – transverse 133

H

Hamulus
– of hamate bone 389, 406

Page numbers in **bold** indicate main discussions.

Hamulus
– pterygoid 25 f, 37, 146, 166
Hand
– arteries 408 f
– arteriogram 441
– axial section 439, 445
– coronal section 392, 437 ff
– differentiation 389
– extensor muscles 404 f
– flexor muscles 400 ff
– innervation 435 f
– ligaments 392 f
– longitudinal section 440
– MRI scan 392, 437 ff
– muscles 400 ff, **406 f**
– – action 407
– – deep layer 407
– nerves 411 f, 435 f
– – course 432
– – nasal 412
– of newborn, X-ray 9
– region
– – anterior 434 f, 440 ff
– – posterior 432 f, **436 ff**
– skeleton 11, 387 ff
– surface anatomy 413 f
– synovial sheaths
– – of extensor tendons 404
– – of flexor tendons 14, 402
– veins 410
Handle of malleus 129 f
Head 7, **147 ff**, 193 f, 474
– arteries 170 ff
– of caudate nucleus **106 ff**, 110, 112, 115, 117, 122
– cavities 151
– connection with the vertebral column 194 f, **203**
– coronal section 64, 151
– CT scan 123
– deep, of flexor pollicis brevis muscle 406
– of epididymis 351, **355**
– of femur 190, 378, 448, **454 f**, 461, 514
– – coronal section 357
– – frontal section 301
– – ossification center 9
– – trajectorial lines 8
– of fibula 456, 462
– horizontal section **120 ff**, 142, 150
– humeral, of pronator teres muscle 430
– of humerus 15, **384 f**, 390, 444
– lateral
– – of gastrocnemius muscle 471 ff, 496, **499 f**, 503
– – of triceps brachii muscle 394, 413, 420 f
– lateral region 78 ff
– long
– – of biceps brachii muscle 211, **396 f**, 419, 424
– – – tendon 399
– – of biceps femoris muscle 472, 494 ff
– – of triceps brachii muscle **394 f**, 399, 415 ff, 420 f
– lymph flow 175
– lymph nodes 174 f
– lymph vessels 174 f
– of malleus 129, **130**
– of mandible 50, **52**, 64, 81, 196
– medial
– – of gastrocnemius muscle 471 ff, 474, **499 f**, 503
– – of triceps brachii muscle 394, 399, 413
– median sagittal section 145
– median section 90, 92 f, 147, 157, 241
– – in neonate 241
– of metacarpal bone 388 f
– of metatarsal bone 458, 467
– midsagittal section 87 f
– MRI scan 92, **120 f**, 151
– of newborn, median section 157
– oblique
– – of adductor hallucis muscle 479
– – of adductor pollicis longus muscle 406
– – of adductor pollicis muscle 443
– of optic nerve 142, **150**
– of pancreas 306, 320, **326 f**
– of proximal phalanx 388 f
– of radius **386 f**, 391
– of rib 199, **205**
– – articulation with vertebrae 205
– sagittal section 86 ff
– short
– – of biceps brachii muscle 396 f, 419, 423 f
– – – tendon 399
– – of biceps femoris muscle 472, 496
– of stapes 130
– superficial, of flexor pollicis brevis muscle 400, 406
– of talus 459, 467
– transverse
– – of adductor hallucis muscle 479 f
– – of adductor pollicis longus muscle 406
– – of adductor pollicis muscle 443
– of ulna **386 f**, 392
– ulnar, of pronator teres muscle 430
– veins 172 f, 410
Head's zones 209
Heart **16**, **260 ff**, **278 ff**, 316
– blood flow 268
– – arterial 260
– – fetal circulatory system 272
– – venous 260
– conducting system 269
– 3-D reconstruction 271
– of fetus 272
– frontal section 268
– function 264
– Head's zone 209
– horizontal section 267, 270
– left 16, 291
– movements 264
– MRI scan 268
– position 3
– in process
– – of contraction 265
– – of dilatation 265
– related vessels 260
– right 16, 290
– valves 261 ff, **266 f**
Helix 124 f
Hemianopsia
– binasal 143
– bitemporal 143
– homonymous 143
Hemisphere
– cerebellar 91, **104 f**, 118
– cerebral
– – auditory areas 132
– – coronal section 94
– – frontal pole 91
– – lateral aspect 102
– – median aspect 101
– – occipital pole 90 f
– – temporal pole 91
Hernia
– femoral 223
– inguinal 221 ff
– – direct 223
– – indirect 223
Hiatus
– adductor 469
– aortic **292**, 469
– esophageal **292**, 307
– maxillary 36 f, 42, 46, **48**, **146**
– sacral 451 f
– saphenous 353
– semilunar 55, 147
Hinge joint 10 f
– axes of movement 11
Hip bone 190 ff
Hip joint 447
– axial section 514
– bones 454
– coronal section 460
– ligaments 460 f
– MRI scan
– – coronar 8
– – frontal 5
– – horizontal 4
– X-ray 8
Hippocampus 142 f
Hook of hamate bone 389, 406
Horn see also Cornu
– anterior, of lateral ventricle **106 f**, 110, 112, 114, **120 ff**
– inferior, of lateral ventricle **107 f**, **114**, 118, 142

Page numbers in **bold** indicate main discussions.

– – entrance 121
– occipital, of lateral ventricle 115
– posterior, of lateral ventricle **106 ff**, 110, 112, 114, 122
Humerus 7, 10, 15, 190, **384 f**, 390, 444
– anterolateral surface 385
– anteromedial surface 385
– of newborn 9
– posterior surface 385
Hymen 366, 368, **373**
Hyoid 20
Hypophysis 37, 88 ff, 123, 142, **150**
Hypothalamus 92 f, **110**, 118
Hypothenar muscles **402 f**, 435
– axial section 445
Hypotympanon 128

I

Ileum 310, 314, 316
– terminal 317 f
Ilium 7, **447**, 453
– gluteal surface 451
Impression(s)
– cardiac, of lung 257
– digitate **30**, 34
– trigeminal 27, 34
Incisor
– central 37, 45, **50**
– lateral 50
– permanent 51
Incisura
– angularis 302 f
– tentorii 77
Incisure
– of pancreas 306
– of tympanic ring 127
Inclination, pelvic 454
Incus 20, 124 f, **129 ff**
Indusium griseum 106
Infundibulum
– of hypophysis 67, 76 f, 93 f, 101, **116**, 118, 150
– hypothalamic, relationship to optic chiasma 142
– of right ventricle 268
– of uterine tube 367 ff, 373
Inspiration
– action of external intercostal muscles 204
– change in the position of diaphragm 292
Insula (Reili) 96, **111**, **118**, 121 f
Intersections, tendinous, of rectus abdominis muscle 217, 220, 301
Intestine, small see Small intestine
Inversion of foot, axis 466
Iris 140
– border
– – inner 140
– – outer 140
– fold 140
Ischium 7, 453
Isthmus
– of lesser sac 328
– oropharyngeal 254
– of uterine tube 367, 370

J

Jejunum 310 ff, 316 f
Joint(-s) 10 ff
– acromioclavicular 381 f, 384, 390
– of ankle 447, **459**, **465**
– atlanto-axial 193 ff
– – lateral 193 f, 196
– – median 147, 167, **193 f**
– – – anterior part 194
– atlanto-occipital 193 ff, 203
– – articular capsule 194
– biaxial 11
– calcaneocuboid 459, 467
– carpometacarpal 387, 407, 438 f
– – of thumb 11, **387**, 389
– – – articular capsule 393
– connecting to the head 194 f
– costotransverse 199, **200 f**, 205, 384
– – effect of intercostal muscles 204
– – of first rib 203
– costovertebral 199, **204 f**
– – axis of movement 205
– – effect of intercostal muscles 204
– crico-arytenoid 160
– cricothyroid 160
– cuneonavicular 458, **465**
– of fingers 10
– of hip see Hip joint
– humeroradial **386 ff**, 445
– humero-ulnar 10, **386 ff**
– interphalangeal
– – of fingers 393, 407, 438 f
– – of hand 387
– – of toes 459
– of knee see Knee joint
– metacarpal 439
– metacarpophalangeal 10 f, **387**, 393, 406 f, 438 f
– – articular capsule 393
– – of thumb 393, 438
– metatarsophalangeal 459
– – of great toe 507
– midcarpal 387
– monaxial 10 f
– multiaxial 10 f
– radiocarpal 438 f
– radio-ulnar 10
– – distal 387, 393, **438 f**
– – proximal **386 ff**, 391
– sacro-iliac 360, 447 f, **451 ff**
– of shoulder 390
– sternoclavicular 179, 381, 418
– subtalar 459, **465**, 467
– synovial 12
– talocalcaneonavicular 459, **465 ff**, 507
– – articular surfaces 466
– talocrural 465
– tarsal, transverse 465
– tarsometatarsal 459, **465**
– temporomandibular **53 ff**, 65, 122
– – articular disc 54, 56
– – capsule 55
– – effect of masticatory muscles 57
– – ligaments 55
– – movements 54
– – MRI scan 59
– tibiofibular 462
– – distal 456, **459**, 507
– – proximal 456 f
– two-axial 11
– vertebral 200
– zygapophysial 200
Joint capsule see Capsule, articular
Joint cavity see Cavity, articular
Juga
– alveolaria 41, 45
– cerebralia 28
Junction, costochondral 204

K

Kerckring's fold 306
Kidney 304, **336 ff**
– arteries 338 f
– arteriography 338
– coronal section 336
– Head's zone 209
– horizontal section 330, 334
– left 17, 305, **340 ff**
– position 3, 300, 334 f
– right 319, **340 ff**
– segments 336
– ultrasound image 337
– upper pole 338
– vascular system 339
– veins 339
Killian's triangle 169
Knee 498 ff
Knee joint 12, 447, 462 ff
– articular capsule 12, **463 f**
– axial section 515
– bones 457
– coronal section 12
– ligaments 463 f
– MRI scan 12, 462
– – sagittal 4
– of newborn 9
– sagittal section 4, 462

Page numbers in **bold** indicate main discussions.

L

Labium
– majus pudeni 224, **366**, 373 f
– minus pudendi 366 f, **373**, 376
Labrum, glenoid 390
Labyrinth 86, **130 ff**
– bony 131 f
– membranous 132
Lacrimal apparatus 135
Laimer’s triangle 169
Lamina
– affixa 106 ff, 116
– of axis 194 f
– cribrosa **30 f**, 34, **38**, 49
– of cricoid cartilage 160
– pretracheal, of cervical fascia 176, 181 f
– prevertebral, of cervical fascia 176
– superficial, of cervical fascia 176, 180
– terminalis 93
– of thyroid cartilage 161
– of vertebra 199
Laryngopharynx **152**, 157
Larynx 145, 156, **160 ff**, 167, 241, 255, 261
– cartilages 160 f
– coronal section 163
– entrance 254
– horizontal section 163
– innervation 164
– ligaments 160
– muscles 162
– – internal, action 162
– of newborn 157
– position 161
– sagittal section 163
Leg
– axial section 475, **515**
– bones 456 f
– coronal section 477
– cross section 503
– muscles 471 ff
– – extensor 478 f
– – – course 479
– – flexor 471 ff
– – – deep 476 f
– – – tendons 474
– surface anatomy
– – anterior aspect 489
– – posterior aspect 488
Lemniscus
– lateral 133
– medial 105, 118
Lens 123, 134, **140 f**
– anterior surface 140
– posterior surface 140
Ligament(s) 496
– acetabular, transverse 461
– alar 194 f
– anococcygeal 362, 376 f
– anterior, of malleus 129
– anular, of proximal radio-ulnar joint 391
– arcuate, medial 292 f
– arteriosum 164
– bifurcate 466
– broad, of uterus 368, 370
– calcaneofibular 466
– calcaneonavicular, plantar 466
– carpal radiating 392 f
– carpometacarpal
– – dorsal 392
– – palmar 392
– collateral
– – carpal, ulnar 392
– – of elbow joint 391
– – fibular 462 ff
– – of interphalangeal joint 393
– – of knee joint 12
– – of metacarpophalangeal joint 393
– – radial 391, 392
– – tibial 463 f
– – ulnar 391, 439
– coraco-acromial 390
– coronary, of liver 308
– costoclavicular, impressions of clavicle 383
– costotransverse 236
– – superior 205 f
– crico-arytenoid, posterior 160
– cricothyroid 160
– cruciate 12
– – anterior **462 ff**, 515
– – posterior 462 ff
– cruciform
– – inferior longitudinal band 194
– – superior longitudinal band 194 f
– cuneonavicular
– – dorsal 467
– – plantar 466
– deltoid 466 f
– – posterior part 467
– – tibiocalcaneal part 467
– – tibionavicular part 467
– denticulate 235, 248
– of elbow joint 10, **391**
– falciform, of liver 278, 288, 300 f, **307 f**, 316 f, 319 f, 328
– – free margin 301
– of foot 466 f
– fundiform, of penis 215 f
– gastrocolic 307, 316 f, **319 ff**, 323
– gastrosplenic 309, 319
– of hand 392 f
– of head of femur 363, 378, **460 f**, 514
– hepatoduodenal **319 f**, 328
– – ducts 323
– – vessels 323
– of hip joint 460 f
– iliofemoral 460 f
– iliolumbar 460 f
– of inferior vena cava 308
– inguinal 3, 213, 217 ff, 224, 353, **460 f**, 468 f, 491
– – surface anatomy 208
– intercarpal
– – deep 392
– – dorsal 392
– interfoveolar 301
– interspinous 206 f
– intertransverse 205 f, 229, 248
– intra-articular 205, 207
– ischiofemoral 460 f
– of knee joint 463 f
– of larynx 160
– lateral, of temporomandibular joint 55
– lienorenal 319
– longitudinal
– – anterior 200, 205, **206 f**
– – posterior 195, **206 f**
– of lumbar vertebra 207
– medial, of ankle see Ligament, deltoid
– meniscofemoral, posterior 463
– metacarpal
– – dorsal 392
– – palmar 392
– – transverse
– – – deep 393
– – – superficial 435, 442
– of ovary 368 ff
– palmar
– – of interphalangeal joint 393
– – of metacarpophalangeal joint 393
– palpebral
– – lateral 135
– – medial 135
– patellar **462 f**, 468, 474 f, 478, 498
– – surface anatomy 489
– of pelvis 460 f
– pisohamate 392 f
– pisometacarpal 392 f
– plantar, long 466, **481**
– popliteal, oblique 474
– pubofemoral 460 f
– puboprostatic 356
– pulmonary 257
– radiate 205, 207
– radiocarpal
– – dorsal 392
– – palmar 392 f
– round 224
– – fatty tissue 375
– – of liver 307, 313 f, 316, **327**, 330
– – of uterus 224, 334, **367 ff**, 370, 374
– sacro-iliac
– – dorsal 460
– – ventral 461
– sacrospinal 358
– sacrospinous 460 f, 487
– sacrotuberous 358, 362, 365, 460 f, **495 f**
– scapular, transverse, superior 416

Page numbers in **bold** indicate main discussions.

– of shoulder 390
– sphenomandibular **55**, 155
– stylohyoid 155, **161**
– stylomandibular 54 f
– superior, of malleus 125
– supraspinous 228
– suspensory
– – of clitoris 375
– – of ovary **368**, 370, 372 f
– – of penis 222, **354**
– talocalcaneal
– – interosseous 465, 467
– – lateral 467
– talocalcaneonavicular, interosseous 466
– talofibular
– – anterior 467
– – posterior 466
– talonavicular 466
– tarsometatarsal
– – dorsal 466 f
– – plantar 466 f
– of thoracic vertebra 205
– thyro-epiglottic 160
– thyrohyoid 163
– – lateral 160
– tibiofibular
– – anterior 467
– – posterior 466
– transverse
– – of atlas 194 f
– – of knee 463
– trapezoid 390
– triangular, left 308
– ulnocarpal, palmar 392 f
– umbilical 340
– – medial 340, 359, 368
– – median 348, 369
– vocal 160, 163
– of wrist of hand 392 f
Ligamentum
– arteriosum 263, 268
– flavum 206
– nuchae **243**, 415
– supraspinous 206
– teres
– – hepatis 307, 313 f, 316, **327**, 330
– – uteri 224, **367 ff**, 370, 374
– – – fatty tissue 375
Light reflex 142
Limb 489
– anterior, of internal capsule 122
– lower 7, 446 ff
– – main arteries 482
– – main trunkal veins 484
– – nerves 486 f
– – – cutaneous 488 f
– – of newborn, X-ray 9
– – segments 488 f
– – skeleton 447 f
– – surface anatomy 488 f
– – – anterior aspect 489
– – – posterior aspect 488
– – veins 484 f, 490 f
– – – superficial 484
– ossification 9
– posterior, of internal capsule 122
– upper 7, 380 ff
– – arteries 408 f
– – axial section 444 f
– – horizontal section 444
– – muscle(s) 14
– – – extensor 14
– – – flexor 14
– – nerves 411 ff
– – – cutaneous 412
– – of newborn, X-ray 9
– – regional anatomy 420
– – skeleton 10
– – surface anatomy 413 f
– – veins 410
– – – superficial 410
Limbic system **109**, 112
– main pathways 109
Limbus, corneal 140
Limen
– insulae 111
– nasi 55
Line(s)
– arcuate 216 f, 220, **238**, 301
– – of ilium 449, 453
– axillary 208
– – anterior 2
– – posterior 3
– epiphysial
– – of humerus 390
– – of tibia 464
– of Gennari 144
– gluteal
– – anterior 453
– – inferior 453
– – posterior 451
– intertrochanteric **454 f**, 461
– mammillary 208
– median, anterior 208
– medioclavicular 208
– midclavicular 2
– mylohyoid 36, **52**
– nuchal
– – inferior 25, **27**, 29, **33**
– – superior 25, 27, **33**
– oblique, of mandible 52
– of orientation
– – dorsal 3
– – ventral 2
– parasternal 2, 208
– paravertebral 3
– pectinal 455
– regional
– – anterior body wall 208
– – dorsal 3
– – ventral 2
– scapular 3
– semilunar 220
– soleal 456
– sternal 208
– temporal
– – inferior 20, 44
– – superior 20, 29
– trajectorial, of femoral head 8
– transverse, of sacrum 452
– trapezoid 383
– umbilical-pelvic 2
Linea
– alba 213, **216 f**, 275, 300
– – surface anatomy 208
– aspera 455
– terminalis 368, **448 ff**, **452 ff**
Lingula
– cerebellar 104
– of lung 257, 278, 280
– of mandible 36, **52**
– sphenoidal 25 f, 38
Lip
– external, of iliac crest 449, 453
– intermediate, of iliac crest 449
– internal, of iliac crest 449, 453
– lateral, of linea aspera 455
– medial, of linea aspera 455
Liver 288 f, 304 f, **307 ff**
– bare area 308, 328
– blood supply 323
– coronal section 294
– of fetus 273
– Head's zone 209
– midsagittal section 332
– peritoneal folds 308
– position 3, 252, 300
– sagittal section 253
– segmentation 308
Lobe
– caudate, of liver 308, 314, **319 f**, 327
– – midsagittal section 332
– frontal 67, 70, 74, **86 f**, 91, 94, 99, **101 f**
– – coronal section 151
– – horizontal section 150
– – median section 92 f
– inferior, of right lung, of fetus 272
– insular 94, 96, 118, **121 f**
– left, of liver 288, 300, **307 f**, 314, 316, 327
– lower
– – of left lung **254**, 256, **277 ff**, 294
– – – bronchopulmonary segments **259**
– – of right lung 254, **256 ff**
– – – bronchopulmonary segments 259
– middle, of right lung 252, **254**, **256 ff**, **277 ff**, 283, 316
– – bronchopulmonary segments 259

Page numbers in **bold** indicate main discussions.

Lobe
– occipital 67 ff, 76, **86**, **101 f**, 103, 115
– – median section 92 f
– parietal 92, **101 ff**
– postcentral 101 f
– precentral 101 f
– pyramidal, of thyroid gland 186
– quadrate, of liver 288, 308, 316
– right, of liver 307 f, 323, 326
– superior, of right lung 294
– – of newborn 272
– temporal 67 f, **86**, **101 f**, 109, 150
– – area of acoustic centers 133
– upper
– – of left lung 252, **254**, **256 ff**, 283, 294 f, 316
– – – bronchopulmonary segments 259
– – of right lung **254**, **256 ff**, **277 ff**, 282, 295
– – – bronchopulmonary segments 259
– – – of fetus 272
Lobe bronchus
– inferior
– – left 254
– – right 254
– lower
– – of left lung 259
– – of right lung 259
– middle, of right lung 254, **259**
– superior
– – left 254
– – right 254
– upper
– – of left lung 259
– – of right lung 259
Lobule
– of auricle 124 f
– biventral, of cerebellum 104
– central, of vermis 104
– semilunar, inferior, of cerebellum 104
Lobus insularis 94, 96, 118, **121 f**
Lung 3, 179, 252 ff, **257 ff**
– bronchopulmonary segments **258 f**, 285
– cardiac impression 257
– groove
– – of aortic arch 257
– – of azygos arch 257
– – of esophagus 257
– – of subclavian artery 257
– – of thoracic aorta 257
– horizontal section 296 f
– impressions of rib 257
– left 252, 254 f, **257 ff**, **277 ff**, 284
– – bronchopulmonary segments 259
– position 256
– right 252, 254 f, **257 ff**, **277 ff**, 284
– – bronchopulmonary segments 259
– surface projection of the thorax wall 256
Luschka, lateral aperture of 114
Lymph capillaries 17
Lymph node(s) 17
– axillary 17, 298, 342, **422 f**
– – deep 423
– – superficial 422
– cervical 174 f
– – deep 175, **182**, 342
– – superficial 174, 177, **184**
– – superior 175
– iliac
– – common 342
– – external 342, **372**
– – internal 372
– infraclavicular 174 f
– inguinal 17, **372**, 491
– – inferior 491
– – superficial 214, 216, 224, **491**
– of intestinal tract 17
– jugulodigastric 174 f
– jugulo-omohyoid **174 f**, 342
– lumbar 342, **372**
– mediastinal 342
– – superior 174
– mesenteric 325
– occipital 175
– parasternal 275
– parotid 175, 342
– – superficial 174
– of popliteal fossa 17
– retro-auricular 174 f
– retroperitoneal 342 f
– sacral 342, **372**
– submandibular 17, 174 f, 181
– submental 174 f
– supraclavicular 174
– of upper body 343
Lymph trunk, lumbar 347
Lymph vessels 17, 298
– iliac 347
– inguinal 491
– of internal female genital organs 372
– of neck 174
– retroperitoneal 342 f
– of trunk 17
Lymphatic system 17
Lymphatics 17

M

Macula
– lutea 141
– of saccule 131
– of utricle 131
Magendie, median aperture of 96, **114**
Main bronchus 252
– left 254
– right 254
Malleolus
– lateral 456, **459**, 466 f, 473
– – surface anatomy 488 f
– – venous plexus 505
– medial 456, **459**, 467, 473
Malleus 20, 73, 124 f, 129, **130 f**
Mandible 7, 20, **22**, 33, 37, 49, **50 ff**, 65, 161, 176, 190, 203
– coronal section 64
Manubrium of sternum 3, 161, 179, 201, **381**
Margin 39, **275 f**
– anterior, of tibia 456, 478, 504
– bony, of acetabulum 454
– costal 3 f, **201**, 204, 216 f, 220, 252, 274 f, 317
– – surface anatomy 208
– frontal, of parietal bone 29
– infra-orbital, of maxilla 39 f
– lambdoid, of occipital bone 39
– lateral, of scapula 382
– of lung 335
– mastoid, of occipital bone 39
– medial, of scapula 242 ff, 394, 415
– nasal, of frontal bone 28
– occipital
– – of parietal bone 29
– – of temporal bone 27
– parietal
– – of frontal bone 28
– – of temporal bone 27
– of pleura 335
– pupillary 140
– sagittal, of parietal bone 29
– sphenoidal, of temporal bone 27
– squamous, of parietal bone 29
– supra-orbital **21 ff**, 28, 45
Marshall's vein 270
Mass, intermediate 92, **101**
Masticatory apparatus 22
Maxilla 7, 20, **22 f**, 28, **33**, 36 f, **39 ff**, 42 ff, 45, 47, 52, 134, 190
– orbital surface 39 ff
Meatus
– acoustic
– – external 27 f, 53 ff, 56, 70 f, 74, 122, **124 ff**, 129
– – – of newborn 33
– – internal 27, **30 f**, 34, 36, 46, **126**, 166, 195
– – – bony base 126
– nasal
– – inferior 36, 42, 48, 55, **146**
– – middle 42, 55, **146**
– – superior 146
Mediastinum
– anterior 253, 275 f
– content 253
– middle 253, 276, 279
– posterior 253, **284 ff**, **288 f**, 291
– – inferior segment 289
– superior 253, **291**
– testis 355
Medulla

Page numbers in **bold** indicate main discussions.

– of kidney 336
– oblongata 31, 69, 88, 93, 103, **116 f**, 248
– – cross section 119
– – median section 92 f
– – MRI scan 197
– of suprarenal gland 336
Membrane
– intercostal, external 204, 211
– interosseous, of forearm 391 ff, **402 f**
– mucous
– – of urinary bladder 350
– – of uterus congestion 369
– obturator 460 f
– tectorial 195
– thyrohyoid **160**, 162, 164
– tympanic 71, 122, 124 f, **129 ff**
– vasto-adductor 468 f, 483, **492**
– – distal part 493
Meninges 87 ff
Meniscus 12
– lateral, of knee joint 462 ff
– medial, of knee joint 463 f
Mesencephalon 67, 75 f, 93, 143
– cross section 119
– median section 92 f
Mesentery 316 ff
– midsagittal section 332
– root 316, 328 f
Meso-appendix **317 f**, 328
– root 328
Mesocolon, transverse 314, 316, **325 f**
– midsagittal section 332
– root 320, 328
Mesosalpinx 368 f
Mesosigmoid 318
– root 328
Mesovarium 368 f
Metacarpals of newborn 9
Metacarpus, axial section 445
Metatarsals of newborn 9
Metencephalon 93
Midbrain 67, 75 f, 93, 143
– cross section 119
– median section 92 f
Moderator band 266
Modiolus 128
Molar 50 f
– permanent 51
Monro, interventricular foramen of 88, **96**, 101, **107**, **114**
Mons pubis 208, 376
MRI scan, structures
– muscular 15
– skeletal 15
Mucosa of wall of stomach 302
Muscle(s) **13 f**, 64, 229, 479, 508
– abductor
– – digiti minimi 401 f, 438 f
– – – of foot 479 f
– – – of hand 406 f, **441 f**
– – of foot 479 ff
– – – course 479
– – hallucis 479 f, **511**
– – pollicis
– – – brevis 400, 406 f, 432, **437**, **441 ff**
– – – longus 404 f, 432, **436 f**
– – – – tendon 441
– adductor 362
– – brevis 377, **469**
– – – of thigh 468 f
– – of foot 479
– – – course 479
– – great 376
– – hallucis
– – – oblique head 479
– – – transverse head 479 f
– – longus, of thigh 377, **468 f**, 471, 492
– – magnus 363, 462, **469**, 471 f, 494
– – minimus **469**, 472
– – pollicis 402, 407, 414, 438
– – – longus 406
– – – oblique head 443
– – – transverse head 443
– – of thigh 377, **468 f**, 471, 492
– – – deep layer 469
– – – deepest layer 469
– – – superficial layer 468
– anconeus 404 f, 431 f
– of arm 394 ff, **398 f**
– articular, of knee 464, 468
– ary-epiglottic 162
– arytenoid 157
– – transverse 162 f
– auricular, superior 87, 170
– of back 226 ff
– – deep layer 300
– – deeper layer 227
– – deepest layer 228 f
– – intertransversal system 229
– – sacrospinal system 226
– – superficial layer 230
– – transversospinal system 229
– biceps 428
– – brachii 14, **396 ff**, 399, 405, **428 ff**, 432, 445
– – – fascia 428
– – – long head 211, **396 f**, 419, 424
– – – – tendon 390, **399**, 427 f, 431
– – – short head 396 f, 419, 423 f
– – – – tendon 399
– – – surface anatomy 414
– – femoris **471 ff**, 503
– – – long head 472, 494 ff
– – – short head 472, 496
– – – tendon 471 f, 496
– bicipital 13
– bipennate 13
– brachialis 14, **396 ff**, 399, 401, 405, 427, 432
– brachioradialis 14, **399**, 402, 404 f, 428, 432
– broad 13
– buccinator 50, **54**, 56, 60, 62 f, 65, 70, 85, **153**, 169
– bulbospongiosus 362, **364**, 373
– calcaneal 474
– ciliary 140
– coccygeus 363
– colli longus 159
– constrictor
– – inferior, of pharynx 62 f, 163, **166 f**, **169**, 184
– – – cricopharyngeal part 168
– – – thyropharyngeal part 168
– – middle, of pharynx 63, 69, **153**, **166 f**, **169**
– – superior, of pharynx 62 f, **153**, 166, 168, **169**
– coracobrachialis **396 ff**, 399, 423
– corrugator supercilii 60
– cremaster 222, 352 f, **355**
– crico-arytenoid
– – lateral 162 f
– – posterior 162
– cricothyroid 162, **168 f**, 276
– dartos 355
– deep, of back 219
– deltoid 14 f, **213 ff**, 298, 390, **397**, **415 ff**, 420 f, 444
– – acromial part 396, 399
– – clavicular part 396 f, 399
– – posterior fibers 394
– – scapular part 399
– – surface anatomy 208
– depressor
– – anguli oris 60, 62, **79 f**, 169
– – labii inferioris 60, 169
– – supercilii 60
– digastric **13**, 65
– – anterior belly 62 ff, 70, **79 f**, 152, 154, **156**, **168**, 170, 175, 177, 183
– – intermediate tendon 152
– – posterior belly 54, 62, 69 f, **82 ff**, 153, 158, 165, **167 ff**, 170, 175, 177, 183
– dorsal
– – of leg, surface anatomy 488
– – of shoulder 394 f
– erector spinae 226
– – insertion 229
– – lateral column 214, 216
– – medial column 214, 216, **229**
– – origin 229
– extensor 14
– – brevis, tendon 441
– – carpi
– – – radialis
– – – – brevis 401, **404 f**, 431
– – – – longus 399, **404 f**, 431
– – – ulnaris 404 f, 431 f, 437
– – – – tendon 436

Page numbers in **bold** indicate main discussions.

Muscle(s)
– extensor
– – digiti minimi, of hand 404 ff, 432, 437
– – digitorum
– – – brevis, of leg 475, 478
– – – of hand 404 ff, 431 f, **436**
– – – longus
– – – – of leg 475, **478 f**, 508
– – – – – tendon 508
– – – – synovial sheath of tendon 507
– – of fingers 405
– – of foot 478
– – of forearm 404 f
– – – surface anatomy 413
– – hallucis
– – – brevis 478, 508 f
– – – longus **478 f**, 508
– – – – synovial sheath of tendon 507
– – – – tendon 474 f, **508**
– – of hand 404 f
– – indicis 405, 432
– – – tendon 404
– – of leg 478 f
– – – course 479
– – pollicis 405 f
– – – brevis 404 f, 432, **436**
– – – – tendon 400
– – – longus 405, 432
– – – – tendon 436
– – of thigh 468
– extra-ocular 136 f
– – action 136
– – innervation 74
– – nerves 137
– facial **53 ff**, 60 f
– of fifth toe 479
– flexor(s) 14
– – of arm 397
– – carpi
– – – radialis **400 f**, 428 f, 431, **435**
– – – – brevis 432
– – – – longus 432
– – – – tendon 392, 407, **441 f**
– – – ulnaris **400 f**, 428, 431 f, **435**
– – – – tendon 392, 406 f, **441 f**
– – deep
– – – of foot 476 f
– – – of leg 465, **476 f**
– – digiti minimi brevis
– – – of foot 479 f
– – – of hand 401 f, 406, **442**
– – digitorum
– – – brevis, of foot 479 f
– – – of hand 401, 441
– – – longus, of foot 476 f, 480, 503
– – – profundus, of hand 401, 430 f, 435, 441
– – – – tendon 407
– – – superficialis, of hand **400 f**, 403, 428, 430 f, **435**, **441 f**
– – – – tendon 407
– – – tendon 401
– – of fingers 401
– – of forearm 400 ff
– – – deep 401
– – – middle layer 401
– – – position 401
– – – superficial layer 400 f
– – hallucis
– – – brevis 480
– – – – origin 512
– – – longus 475 ff, 503
– – – – tendon **476 f**, 479
– – of hand 400 ff
– – – deep 401
– – – middle layer 401
– – – position 401
– – – superficial layer 400 f
– – of leg 471 ff
– – – course 476
– – – crossing 476
– – – tendons 474
– – pollicis
– – – brevis
– – – – deep head 443
– – – – superficial head 400, **441 ff**
– – – longus **400 f**, 430, 435
– – – – tendon 406 f
– – superficial, of leg 465
– – of thigh 471 f
– – – superficial layer 471
– of foot 473 ff, **479 ff**
– of forearm 400 ff, 431
– fusiform 13
– gastrocnemius 462, **471 f**
– – lateral head 471 ff, 496, **499 f**, 503
– – medial head 471 ff, 474, **499 f**, 503, 515
– gemellus
– – inferior 471 f, 495
– – superior 471 f
– genioglossus 50, 88, **151 f**, 157, 168
– geniohyoid 64, 88, **152 ff**, 157
– gluteal
– – deeper layer 470
– – superficial layer 470
– gluteus
– – maximus 229, **471 f**, **494 ff**
– – – surface anatomy 488
– – medius 331, **471 f**, 495 f
– – minimus **471**, 495
– gracilis 362, 377, **468 f**, 471, 492, 499
– – tendon 463, 468, **471**, 473
– of great toe 479
– hamstring 496
– of hand 400 ff, **406 f**
– hyoglossus 63 f, **152 ff**, 162
– hypoglossus 168 f
– iliacus 340, 345, 469
– – horizontal section 331
– iliococcygeus 363
– iliocostalis 214 f
– – cervicis 226
– – insertion 226
– – lumborum 226
– – origin 226
– – tendons 229
– – thoracis 226, 244
– iliopsoas 301, 378, **468 f**, 492, 514
– of index finger 406
– infrahyoid **62 f**, **153**, 176 f, 184
– infraspinatus **250**, **394 f**, 415 f, 420 f, 444
– infraspinous 227, 249
– intercostal
– – effect
– – – on costotransverse joint 204
– – – on costovertebral joint 204
– – external **204**, 211, 226, 415, 424
– – innermost 210, 236
– – internal **204**, 210 f, 214 f, 274
– internal, of larynx, action 162
– interosseus(-i) 438
– – dorsal
– – – of foot 479
– – – of hand 392, 405 ff, **436**
– – of foot 480
– – of hand 441
– – – actions 407
– – palmar 406 f, **443**
– – plantar 479, **481**
– interspinal, lumbar 228
– intertransversal 207, **229**
– – cervical, posterior 229
– – lumborum 228 f
– intrinsic, of back, medial column 216, **229**
– ischiocavernous 357, **361 f**, 375 f
– ischiocrural 470
– latissimus dorsi 204, 211, 227, 232, 242, **394 f**, 397, **415**, 420 f
– of leg 473 ff
– levator(es) 363
– – anguli oris 60, 169
– – ani 349, 356 f, **362 f**, 376
– – costarum 207, **227 f**, 229, 249
– – labii superioris 60, 137, 169
– – – alaeque nasi 60, 169
– – palpebrae superioris **75**, 134, 136 ff
– – – aponeurosis 135
– – scapulae 183, 186, 226 ff, **243 ff**, 247, **394 f**, 415 ff
– – veli palatini 64, **124 ff**, 169
– longissimus 214 f
– – capitis **226**, 229
– – cervicis 226, 244
– – horizontal section 331
– – insertion 226
– – origin 226
– – thoracis 226, 244
– longitudinal

Page numbers in **bold** indicate main discussions.

– – inferior, of tongue 50, **151**, 168
– – superior, of tongue 50, 64, **88**, **151**
– longus
– – capitis 62 f, 167
– – colli 187
– lumbrical
– – of foot 477, **479 f**, 511
– – of hand 401, 406 f, **443**
– masseter **53 f**, 56 ff, 60, 64, **79 ff**, 85, 170
– masticatory **53 ff**, 58
– – effect on the temporomandibular joint 57
– – MRI scan 59
– mentalis 60, 169
– multicaudal 13
– multifidus 227 ff
– multiventral 13
– mylohyoid 62 ff, **79 f**, 88, **152 ff**, 157 f, **168**, 175 ff
– nasal **79**, 169
– – alar part 60
– – transverse part 60
– of neck 158 f
– oblique
– – abdominal
– – – external 204, **212 ff**, 216 f, 220, 274, 309
– – – – surface anatomy 208
– – – internal 214 ff, 217, 220
– – – – horizontal section 331
– – – – surface anatomy 208
– – inferior **74**, 134, **136**
– – superior **72 f**, 134, **136**, 138
– – – tendon 136 f
– obliquus capitis
– – inferior 226 f, 229, **245 f**
– – superior 227, **245**
– obturator
– – externus 356 f, 378, 469
– – internus 356 f, **362 f**, 375, 378, 471 f, 514
– occipitofrontal
– – frontal belly 56, 62, **81**, 87, 170
– – occipital belly 60, 72, **79**, 87, 242 ff, 247
– omohyoid 62 f, **79 f**, 83, 153, 158 f, 175, 274, 276
– – intermediate tendon 181
– – superior belly 177
– opponens
– – digiti minimi 406, **442**
– – – of foot 481
– – – of hand 401
– – pollicis 402, 406, 437, 439
– orbicularis
– – oculi **60 ff**, 63, 72, 79, 81, 87, **135**, 169
– – – connection to superior labial muscles 135
– – – orbital part 60, 62, 170
– – – palpebral part 60, **135**
– – oris 60, 79, 169
– palatine 64
– palatopharyngeus 165
– palmaris
– – brevis 400, **435**
– – longus 400, 428, 431, 435
– – – tendon 400, 435, **442**
– papillary 263, **265 f**
– – anterior 266 f, 268, 281, 293
– – – of right ventricle of fetus 272
– – posterior 266, 281
– – septal 266
– pectineus 356, 378, **468 f**, 492 f
– pectoral 396 f
– – deep layer 397
– – position 396
– – superficial layer 396
– pectoralis
– – major 14, **211 ff**, 274 f, 298, **396 f**, 399, 422, 424
– – – abdominal part 396
– – – clavicular head 187, 396
– – – insertion 423
– – – sternocostal part 396
– – – surface anatomy **208**, 414
– – minor 170, 211, **274 ff**, **396 f**
– – – insertion 423
– – – surface anatomy 208
– perineal, transverse
– – deep 350, 357, **362 ff**, 365, 376
– – – fascia 375
– – superficial 362, **365**, 375 f
– peroneal 508
– – brevis **473**, 476
– – longus **473**, 476
– – – tendon 478
– – tertius, tendon 478
– of pharynx 169
– piriform 471 f, **495**
– plantaris 472 ff, **499**, 503, 515
– popliteus 462, 473, **476**
– procerus 60
– pronator
– – quadratus **402 f**, 407
– – teres 399, **401**, **403**, 428, 431
– – – humeral head 430
– – – ulnar head 430
– psoas
– – major 214 f, 292 f, 300, **340 ff**, 345, 347, **469**
– – – horizontal section 330, 334
– – minor 469
– pterygoid
– – lateral **54 f**, 57 ff, 64, 82
– – medial **54**, 57 ff, 64, 70, 82, 148, 167, 168 f
– pubococcygeus 363
– puborectalis 363
– pyloric sphincter 303
– pyramidal 215, 378, 514
– quadratus
– – femoris **471 f**, 495 f
– – lumborum 214 f, 292, 340, **342**, 469
– – – horizontal section 330
– – plantae **480 f**, 511
– quadriceps femoris 462, 464, **468**, 474, 514
– – surface anatomy 489
– quadricipital 13
– rectus
– – abdominis 210, 212, 214, 216 f, 220, **274 ff**, 300 f, 397
– – – surface anatomy 208
– – capitis posterior
– – – major 226 f, 229
– – – minor 226 f, 229, **245 f**
– – femoris **468 f**, 471, **492 f**
– – inferior **74**, 134, **136 f**
– – lateral 71, **73 ff**, 76, 123, 134, **136**, 142, 150
– – medial 76, 134, **136 f**, 142, 150
– – superior **74 f**, 134, **136 f**, 138
– rhomboid 243
– – major **226 f**, 229, 242 f, 246, **394 f**, 399, 415 ff, 420
– – minor **243**, 245 f, **394 f**
– ring-like 13
– risorius 60
– rotator 229
– – lumbar 228
– sartorius 356, 378, **468 ff**, 471, 473, 491, 499, 514
– – tendon 463, 468
– scalene 62, 158, 176, 196
– – anterior 159, 170, **183**, **186 f**, 276, 279, 281, 335
– – middle 182, **186 f**, 335
– – posterior 159, **183 f**, **186 f**, 335
– semimembranosus 462, **471 ff**, 496, 499
– – tendon 463, 472
– semispinalis
– – capitis 167, **226**, 229, **232**, 243, 246
– – cervicis 207, **226 ff**, 229, 246
– – thoracis 229, 232
– semitendinosus **13**, 462, 468, **471 ff**, 494, 496, 499
– – tendon 463, 468, 499
– – – intermediate 472
– serrated 13
– serratus
– – anterior **204**, **211 ff**, 274, 298, 309, **396 f**, 422
– – – surface anatomy 208
– – posterior
– – – inferior 226, 415
– – – superior 232, **243**, 246, 416 f
– of shoulder 394 ff
– of sole 479 ff
– – deep layer 481
– – middle layer 480
– – superficial layer 479
– soleus 462, **473 f**, 478, 499, 503
– – tendinous arch 473, 503

Page numbers in **bold** indicate main discussions.

Muscle(s)
– sphincter
– – anal
– – – external 348 f, 354, **361 ff**, **375 ff**
– – – internal 348
– – pyloric 302 f
– – urethral **348**, 361, 378
– – – external 348
– – – internal 348
– sphincter-like, of head 60
– spinalis 227 f
– – thoracis 226, 229
– splenius
– – capitis 72, 79, 181 f, 187, 232, 242 ff, 246 f, 395, **415 ff**
– – cervicis 232, 243 f, 246, **415**, 417
– stapedius 128
– sternocleidomastoid 60, 62 f, 65, 70, **79 ff**, 83 f, 87, 154, **158 f**, 176, 180, 210, 213, 242 ff, 274, 396 f, 415, 417 ff
– – clavicular head 177
– – sternal head 177
– – surface anatomy 413
– sternohyoid 62 f, **80**, 99, **153**, **158 f**, 175, 177, 213, 274
– sternothyroid 62, 153, 158 f, 177, 210, 275
– styloglossus 73, **153**, **168**, 169
– stylohyoid 62, 70, 73, **80**, **152 ff**, 158, **168 f**, 177
– stylopharyngeus 63, 69, **169**
– subclavius 158, 211, 396 f
– subscapularis 204, **396**, **398 f**
– supinator 401, **403**, 405, 432
– suprahyoid 62 f, **153**, 177
– supraspinatus 15, **394 f**
– – tendon 390
– temporal **53 f**, 64 f, 81
– – insertion 56
– – tendon 62 f, **82**, 85
– temporoparietalis 60, **79**
– tensor
– – fasciae latae 468 f, **471**, 492, 495
– – – surface anatomy 489
– – tympani 124 f, 128 f
– – – tendon 129
– – veli palatini **62 ff**, 169
– teres
– – major **227**, 229, 242, **250**, 390, **394 f**, 399, 415 ff, 420 f
– – minor **394 f**, 415 ff, 420 f
– of thigh 468 ff
– thyro-arytenoid 162
– thyro-epiglottic 162
– thyrohyoid 62 f, **153 f**, **158 f**, 162, **168 f**, 175, 177
– tibialis
– – anterior 475
– – – course 479
– – – synovial sheath of tendon 507
– – – tendon 474, **477 f**, **503**, **508**
– – posterior 476 f, **503**
– – – tendon 476
– transverse
– – abdominal 210, **214 ff**, 219, 301
– – thoracal 210, 274
– – of tongue 50, 64, 151
– – of trachea 162
– transversospinal system 229
– trapezius 15, 79, 158, 176, 229, 243 f, 390, **394 f**, 420
– – ascending fibers 242, **394**, 415
– – descending fibers 242, **394**, 415
– – surface anatomy 414
– – transverse fibers 242, **394**, 415
– triceps
– – brachii 14, 399, 401
– – – lateral head 394, 413, 420 f
– – – long head **394 f**, 399, 415, 420 f
– – – – tendon 390 f
– – – medial head 394, 399, 413
– – – surface anatomy 413
– – – tendon 399
– – surae, surface anatomy 488
– tricipital 13
– unipennate 13
– vastus
– – intermedius **468 f**, 471, 514
– – lateralis 356, 464, **468 f**, 471, 492 f, 514
– – medialis 464, **468 f**, 471, 474, 492 f
– vertical, of tongue 64, **88**, 151
– vocalis 162 f
– zygomatic
– – major 60, **79 ff**, 170
– – minor 60
Muscle fibers, oblique, of stomach 303
Muscular coat
– of gallbladder 306
– of stomach 303
Myelencephalon 93
Myocardium **262**, 268 ff, 294
Myology 13 f
Myometrium 378

N

Nasopharynx 64, **152**, 157
Neck 156 ff, 415 ff
– anatomical, of humerus 384 f
– anterior aspect 418
– arteries 170 ff
– axial section 159
– cross section 176, 178
– dorsal
– – deeper layer 243
– – deepest layer 244 ff
– – superficial layer 242
– of femur 9, 448, **454 f**
– of gallbladder 306
– horizontal section 197, 240
– lateral region 180 ff
– lymph flow 175
– lymph nodes 174 f
– lymph vessels 174 f
– of malleus 130
– median sagittal section 88
– median section 157
– MRI scan 178, 197
– muscles 158 f
– – deep 159
– nerves 185, 426
– organization 159
– organs 156 ff
– of radius 386 f
– posterior region 415
– regional anatomy 156
– of stapes 130
– surgical, of humerus 384 f
– of talus 459
– of urinary bladder 350
– veins 172 f, 410
– vessels 185
Nerve(s) 248, 412, 427, 435
– abducent 31, 66, 68, 71, **74 f**, 77, 95, 99 f, 113, 116, 137 f
– accessory 31, 65 f, **68 f**, 71, 73, **83**, 100, 113, **116 f**, 165 ff, 186, 229, 243 f, 250, 415 ff, 419
– – intracranial portion 69
– alveolar
– – inferior 64, 70 f, 73, **82 ff**, 148, 152
– – superior
– – – anterior 85
– – – middle 71
– – – posterior 70 f, 74, **82**, 85
– anococcygeal 363, **365**, 494
– of arm 426 ff
– auricular
– – great 65, **79 ff**, 82 f, 176, 180 f, 233, 242, 244, 415 f
– – posterior 72, **79**
– auriculotemporal 65, 70 f, 74, **79**, **81 ff**, 85, 87, 170
– – communicating branches to facial nerve 82
– axillary 395, **411**, 416, 420 f, **425 f**
– – cutaneous branch of arm 230, 421
– – main branches 411
– of back **230 ff**, 233
– buccal 65, 70 f, 74, **81 f**, 83 f
– cardiac, cervical
– – inferior 164, 288 f, **347**
– – superior 288
– carotid sinus 167
– cervical, transverse 65, **80 f**, **176**, 180, 188, 250
– chorda tympani 64
– ciliary
– – long 139, 143
– – short 70, **74 f**, 85, 138, 143
– cluneal

Page numbers in **bold** indicate main discussions.

– – inferior **230**, 233, 363 f, **486**, 488, 494 ff
– – middle **230**, 233, 488, 494, 496
– – superior 227, **230 f**, 233, 488, 494
– cranial 18, **66 ff**, 100, **116 f**
– – base of skull 31
– – nuclei 116
– – – brain stem 116
– – related foramina 31
– – related regions 31
– cutaneous 428
– – of back 420
– – brachial, medial 188
– – dorsal
– – – intermediate, of foot 501, 508
– – – lateral, of foot 508
– – – medial 484
– – – – of foot 501, 508
– – femoral 353
– – – lateral 219, 237, 345, **486 f**
– – – posterior 230, 363 f, **486**, 488, 494, 496
– – – – perineal branch 494, 496
– – of foot 504 f
– – lateral 437
– – – of forearm 411 f, 427 ff, 432, 436 f
– – – lower, of arm 411 f, 421
– – – upper, of arm 230, **412**, 415, **420 f**
– – medial
– – – of arm 411, 421 f
– – – of forearm 411 f, **420 ff**, 425, 427 ff
– – perforating 495
– – posterior
– – – of arm **411 f**, 415
– – – of forearm 411 f, 421, 432, 436 f
– – of region of knee 498
– – sural
– – – lateral 486, 496, 498, 500 f
– – – medial 496, 499, 500 f
– – of thigh 489 f
– digital
– – dorsal
– – – of foot 508
– – – of hand 411 f
– – palmar 441
– – – common 411, 435, 441
– – – proper 435, **442**
– – – supplied regions 436
– – – of thumb 412
– – plantar
– – – common 511
– – – proper 511 f
– dorsal
– – of clitoris 376
– – of penis 221, 353, 364, 487
– erigentes 361
– ethmoidal
– – anterior 31, 139, 148
– – – external nasal branch 70
– facial 31, 66, **68 f**, 71 f, **79 ff**, 83, 85 f, 89, 100, 113, 116 f, 167, 170
– – buccal branches 72, **79**, 180
– – cervical branch 72, **79 ff**, 176, 179 ff, 188
– – communicating branches to auriculotemporal nerve 82
– – deep dissection 79
– – mandibular branch 180
– – marginal mandibular branch 72, **79**, 81, 154, 180
– – ramus colli 176
– – temporal branch 72, **79**
– – zygomatic branch 72, **79**
– femoral 219, 237 f, 301, 345, 352, 357, 374, 378, 460 f, 483, **486 ff**, 489, 491
– – cutaneous branch 498
– – – anterior 483
– – muscular branch 492 f
– fibular
– – common 471, 473, **483**, 486, 488 f, 496, 500, **506**
– – deep 486, 489, **505**, 508
– – superficial 486, 489, 496, **505**, 508
– – – intermediate dorsal cutaneous branch 505
– – – medial dorsal cutaneous branch 505
– of forearm 431 ff
– frontal 71, 75
– – lateral branch 138
– genitofemoral 237 f, 340, 345, **486**
– – femoral branch 220, **352**, 486, 491
– – genital branch 220, 224, **352**, 486, 491
– glossopharyngeal 31, 66, **68 f**, 71, 73, 100, 113, **116 f**, 153, **164 ff**, 167
– – carotid sinus branches 73
– – lingual branches 73
– gluteal
– – inferior 495 f
– – superior 495
– hypogastric 361
– hypoglossal 31, 33, 65 f, **68 f**, 71, **80**, 83, 99 f, **116 f**, 153 f, 164, 166 ff, 185
– – intracranial portion 69
– – lingual branch 73, 185
– – omohyoid branch 185
– – superior root 69
– – thyrohyoid branch 185
– iliocostalis 234
– iliohypogastric 216 f, 220, 237 f, 339 f, 345, 460 f, **486 ff**, 491
– – cutaneous branch
– – – anterior 486
– – – lateral 486
– ilio-inguinal 216, 219 f, 237 f, 341, 345, **352**, 374, **486 ff**
– infra-orbital 70 f, **74**, 81, 85, 135 ff
– – terminal branches 70
– infratrochlear 71
– intercostal 210 f, 219 f, **236**, 289
– – collateral branch 236
– – cutaneous branches
– – – anterior 211, 213, 219, 233, 397, 412, 423, **486**
– – – lateral **204**, 211, 213, 219, 233, 397, 420 ff, 424, **486**
– – mammarian branches, medial 298
– – perforating branches, anterior 212
– intercostobrachial 188, 204, 211, 298, 422, 424, 426 f
– – terminal branches 412
– interosseous
– – anterior, of forearm 411
– – posterior, of forearm 432 f, 436
– labial, posterior 376 f
– lacrimal 70 f, **74 f**, 137 ff
– laryngeal
– – inferior 162, 164 f
– – recurrent 164, 179, **187**
– – – left 164, 261, 276, **279 ff**, 282 ff, 286 f, 289, **347**
– – – right 164, 285 ff, **347**
– – superior 164, 167 f
– – – external branch 164
– – – internal branch 153, 164 f
– lingual 64 f, 70 f, 73, 83, 85, 148, **153 ff**
– mandibular 31, 55, 66, 70 f, 74, 85, 148
– – inferior 65
– – meningeal branch 31
– masseteric 65, 74, **81 f**
– maxillary 31, 66, 70 f, 74, 85, 137
– medial 429
– median 170, **188**, 211, 399 f, 403, 408, 411, **425 ff**, 431, 435
– – axillary region 422, 424
– – cubital region 428 ff
– – main branches 411
– – palmar branch 411 f, 435, 441
– – palmar digital branch 412
– – – common 435, **442**
– – roots 411, **423**, 427
– meningeal, recurrent 31
– mental 70 f, **81**, 85
– musculocutaneous 188, 411, 422, **425 f**
– – main branches 411
– mylohyoid 70 f, **79 f**, 82, 85, 154
– nasociliary 74 f, 139
– nasopalatine 148
– obturator 237, 345, **357 ff**, 483, **486 f**, 493
– – anterior branch 493
– – posterior branch 493
– occipital 87
– – greater 65, 72, **79**, **83**, 87, 227, 230, 233 f, **242 ff**, 245 ff, 415 f
– – lesser **79**, 83, 180 f, 186 f, 230, 233, 242 ff, 415 ff
– – third 230, 242 ff, 245, 416 f
– – – cutaneous branch 415
– oculomotor 31, 66 ff, 70 f, **74 ff**, 99 f, **116 ff**, 137 f, **142 ff**, 148, **150**
– – inferior branch 71, **73 f**, 85, 137

Page numbers in **bold** indicate main discussions.

Nerve(s)
– oculomotor
– – superior branch 139
– olfactory 31, 66
– ophthalmic 31, 66, 70 f, **74 ff**, 85, 137, 148
– optic 31, 64, 66 ff, 70 f, **74 f**, 77, 86, 100, 116 f, 123, 134, **140 f**, 150
– – destruction, blindness in the corresponding eye 143
– – dural sheath 142, 150
– – extracranial part 136, 138
– – intracranial part 136, 138
– of the orbit 74 f
– palatine
– – greater 148
– – lesser 148
– parapharyngeal 166 ff
– parasympathetic 346
– pectoral
– – lateral 211, 419, **424**, 427
– – medial 179, 211, 219, 419, 427
– perineal 487
– peroneal
– – common 501, 503
– – deep 504 f
– – superficial 501
– – – lateral dorsal cutaneous branch 504 f
– – – medial dorsal cutaneous branch 504 f
– petrosal
– – deep 148
– – greater 31, 79, 124, 126, 128, 148
– – lesser 31, 126, 128
– phrenic 164, 179, 183, 187 f, 276 f, **279 ff**, 284 ff, **290 f**, 408, 425
– – accessory 187
– – left 279, 281
– plantar
– – lateral 486, **511 f**
– – – deep branch 511
– – – superficial branch 511
– – medial 486, **511 f**
– of pterygoid canal 148
– pterygopalatine 70, 74
– pudendal 358, **363 f**, 376, **486 f**, 495
– – anal branch 364
– – inferior rectal branches 496
– – perineal branch 364, 375, 377
– radial **411**, 416, 420, **425 ff**
– – axillary region 422
– – course 426
– – cubital region 428
– – deep branch 403, **411**, **417 ff**, 426, 432, 437
– – dorsal digital branch 412, 432, 436
– – innervation of hand 436
– – main branches 411
– – posterior interosseous branch 433
– – superficial branch 411 f, **426 f**, 430 ff, 436 f, 441
– – superficial palmar branch 441
– rectal, inferior 363 f, 376 f, **487**, 495
– recurrent 162
– saphenous 483 f, **486**, 488 f, 491, 498, 504, 508
– – entering the adductor canal 468
– – infrapatellar branch 483, **486**, 491, 498, 504
– scapular, dorsal 243, 416
– sciatic 356, 363, 378, 460 f, 471, **486**, **495 f**, 514
– – branches 496
– – muscular branch 496
– scrotal
– – anterior 486
– – posterior 363 ff, **487**
– spinal 18, **100**, **230 ff**, 233, 242
– – branch
– – – cutaneous 228
– – – – lateral 230
– – – – medial 230, 242
– – – dorsal 233
– – cervical 68, 159, 185
– – – dorsal root 159
– – – ventral rami 18
– – – ventral root 159
– – dorsal branches 415
– – lateral branches of dorsal rami 227, 230, 232 ff
– – lumbar, ventral rami 18
– – medial branches of dorsal rami 227, 230, 232 f
– – meningeal covering 235
– – ramus
– – – dorsal 219, 235, 248
– – – – cutaneous branch 412
– – – – lateral branches 420
– – – – medial branches 420
– – – ventral 234
– – root
– – – dorsal 73, 219, 234, 248
– – – ventral 219
– – sacral 235
– – – ventral rami 18
– – thoracic 233
– – – dorsal root 235
– splanchnic
– – greater 289 f, 337, 347
– – lesser 337, **347**
– – lumbar 347
– – pelvic 238, 361
– – sacral 347
– subcostal 237, 339, **486**
– suboccipital 233, 246, 249
– supraclavicular 65, **79**, 83, 211, 213, 250, 284
– – anterior 83, **182**
– – intermedial branches 83
– – intermediate 280, 412
– – lateral 83, 176, 180, **395**
– – medial 176 f, 180, 219, 412
– – middle 176 f, 180 ff, 418
– – posterior 412, **415**, 420
– supra-orbital 65, 70, 74, **79**, 83, 137
– – lateral branch 71, **75**, 85, 87, 139
– – medial branch 71, **75**, 81, 87, 139
– suprascapular **188**, 390, 416, **426**
– supratrochlear **75**, 85
– sural 488, 501, 505
– – cutaneous branch 504
– – lateral calcaneal branches 505
– sympathetic 346
– temporal, deep 74, **85**
– of thigh 482 f
– thoracic, long 188, 204, **211**, 219, 419, 424 f
– thoraco-abdominal 216, 219 f
– thoracodorsal 188, 204, 211, 419, 424, 427
– tibial 462 f, **471**, 473, 483 f, **486**, 496, 503
– – malleolar region 484
– trigeminal 31, 66, 68, **70 f**, 73 ff, 85, 100, **116 ff**, 148
– – main branches 71
– – motor root 148
– trochlear 31, 66 ff, **69 ff**, **73 ff**, 100, 116 f, 137, 144, 148
– – intracranial part 138
– – intra-orbital part 138
– ulnar **188**, 211, 408, 411, 415, **425 ff**, 431 f, 435 f, 441
– – axillary region 422 f
– – carpal branch 437
– – cubital region 428 ff
– – deep branch 411, 441
– – dorsal branch 411 f, 433, 437, 441
– – innervation of hand 436
– – main branches 411
– – palmar branch 435
– – palmar cutaneous branch 412
– – palmar digital branch 412
– – – common 435, **442**
– – – proper 435 f
– – superficial branch 411, 435, 441
– vagus 18, 31, 66, **68 f**, 71, 73, 100, 113, **116 f**, 148, 156, 164, 167, 171, 183, 261, 274, 276, 284 f, 288, 290, **346 f**
– – cardiac branch 167, 187
– – – cervical
– – – – inferior 284, 286, 290
– – – – superior 284, 286
– – esophageal branches 288, 347
– vestibulocochlear 31, 66, **68 f**, 71, 89, 100, 113, 116 f, 124 f, 133
– – cochlear part 126
– zygomatic 70 f, **74**
Nervous system 18
– autonomic 18, **346 f**
– – ganglia 347
– – plexus 347
– cranial part 18
– parasympathetic 18
– sympathetic 18

Page numbers in **bold** indicate main discussions.

Network
– capillary, of finger 441
– venous
– – around knee 498
– – dorsal
– – – of foot 513
– – – of hand 410, **432**, 437
– – of lateral malleolus 508
– – of medial malleolus 508
Nipple 208, 298, 422 f
Node
– atrioventricular 269
– sinu-atrial 264 f, **269**
Nodule of vermis 104
Nose
– aperture, bony, anterior 45
– cartilages 49
Nostril 49
Notch
– acetabular 450, 453
– angular, of stomach 302 f
– antitragic 124
– cardiac, of left lung 256, **278**
– cardial, of stomach 302 f
– clavicular 201
– ethmoidal, of frontal bone 28
– frontal 42, 45
– interarytenoid 163
– intercondylar 9
– jugular 201
– mandibular **52**, **55**, 81
– mastoid 27, 29, **33**
– parietal, of temporal bone 27
– pterygoid 25
– radial, of ulna 386 f
– scapular 384
– sciatic
– – greater 451, 453 f
– – lesser 451, 453
– sphenopalatine 39 f, 42
– supra-orbital 22, 28
– tentorial 75 ff
– thyroid, superior 161
– trochlear, of ulna 386 f
– vertebral
– – inferior 199
– – superior 199
Nucleus(-i)
– abducent 116
– ambiguus 116
– of Burdach 118
– caudate 64, 94, 106 ff, **113**, **116**, 120 f
– cochlear
– – dorsal 133
– – ventral 133
– of cranial nerve 116
– cuneate 118
– dentate 105, 118
– dorsomedial, of hypothalamus 110
– emboliform 118
– facial 72, **116**
– of Goll 118
– gracilis 118
– hypoglossal **116**, 118
– hypothalamic 110
– lentiform **111**, **113**, **116 f**, 121, 143
– motor
– – of oculomotor nerve 116
– – of trigeminal nerve 116
– oculomotor 118
– – accessory 143
– olivary, inferior 118
– paraventricular 110
– posterior, of hypothalamus 110
– pre-optic 110
– pulposus **206 f**, 240
– red 101, **105**, 109, 118
– salivatory 116
– sensory, of trigeminal nerve 116
– solitarius 118
– spinal, of accessory nerve 116
– subcortical 106 f, **111 ff**
– supra-optic 110
– trochlear 116
– ventromedial, of hypothalmus 110
– vestibular **116**, 118
– visceral
– – of glossopharyngeal nerve 116
– – of vagus nerve 116

O

Obex 133
Occlusion, centric 50
Oesophagus, sphincter 288
Olecranon 386 f, 391, 399, 404
– surface anatomy 413
Olecranon fossa 385
Olfactory system 109
– main pathways 109
Olive, inferior 68, 105, **111**, 113, 116 f, 133
Omentum
– greater 307, **310**, 316, 320, 328
– – midsagittal section 332
– lesser 319 f
– – midsagittal section 332
Opening
– pharyngeal, of auditory tube 88, 254
– saphenous 214, 221 f, **484**, **491**
Operculum
– frontal 111
– frontoparietal 111
– temporal 111
Ora serrata 140
Orbit 7, 31, **46 f**, 136
– bones 134
– horizontal section 150
– layer
– – deeper 139
– – middle 138 f
– – superficial 138
– nerves 74 f
– posterior part, frontal section 134
– sagittal section 134, 140
Organs
– abdominal see Abdominal organs
– genital see Genital organs
– inner, position 2
– mediastinal 284 ff
– of neck 156 ff
– pelvic
– – nerves 361
– – vessels 358 ff
– of posterior mediastinum 288 f
– respiratory
– – organization 255
– – position 255
– retroperitoneal 333 ff
– – in the female 334
– – in the male 340 f
– – vessels 315
– sensory 86 ff
– thoracic see Thoracic organs
– urinary 334 f
Orifice
– ureteric 348 ff, 367
– urethral
– – external 348, **367**, 373
– – internal 348, 350, 357, **367**
– vaginal 368, 372 f, 376
Oropharynx **152**, 157, 254
Ossicles, auditory 20, 22, 127, **130**
– movements 130
Ossification 9
– bones of limb 9
Ossification center 9
Osteology 6 ff
Outlet, pelvic 452
Ovary 368 ff
– position 334

P

Palate
– hard **50**, 55, 145 f, 150, **152**, 166
– soft 55, 64, **90 f**, 145 f, 152, 165, 167
Palm
– arteries 440
– deep layer 443
– middle layer 441
– nerves 440
– superficial layer 440, 442
Pancreas 289, 300, 302, **304 ff**, 310, 314, **326 f**
– blood supply 323
– Head's zone 209

Page numbers in **bold** indicate main discussions.

Papilla
– duodenal
– – greater **304 f**, 311, 327
– – lesser **304 ff**, 327
– renal 336
– – cribriform area 336
– sublingual 155
Papillary muscles 263
Patella 7, 447, 457, 462, 468, 498, 504
– articular surface 464
– surface anatomy 489
Pecten pubis 449, 453
Pedicle 199, 205
– of axis 194 f
Peduncle
– cerebellar
– – inferior **104 f**, 116 f
– – middle **104 f**, 113, **116 f**, 133
– – superior **104 f**, 113, 116 f
– cerebral 67, 73, **105**, 110, 116 ff, 133, 142, 144
Pelvic girdle 452
Pelvis 7, 203 f
– aperture, inferior 451
– axial section 514
– bones 452 ff
– connection with the vertebral column 203
– female 334, **449 ff**
– – diameters 452, **454**
– – inclination 454
– ligaments 460 f
– male 356 ff, **449 ff**
– margin of superior aperture 450
– renal 335 f, 348
– skeleton 448 ff
Penis 348 ff
– cross section 351
Perforated substance, anterior 68
Pericardium 172, 253, 261, 275, **276 ff**, 279 f, **282 f**, 290 f
– diaphragmatic part 282
– reflection 261
Pericranium 87
Perineum, investing superficial fascia 365
Periorbita **74**, 134
Periosteum
– of skull 87
– of vertebral canal 240
Peritoneum 214, 217, 300
– of posterior abdominal wall 318
– reflections from organs 328
Pes
– anserinus 468
– hippocampi **107 f**, 112
Phalanx(-ges) 190
– distal
– – of fingers **387 ff**, 438 f, 441
– – of thumb **388 f**, 458, 507
– – of toe 459
– of foot 7, **388 f**, 458 f, 507
– of hand 7, **387 ff**, 438 f, 441
– middle
– – of fingers 387 ff, 438 f, 441
– – of toe 459
– of newborn 9
– proximal
– – of fingers **387 ff**, 438 f, 441
– – of thumb **387 ff**, 438 f, 458, 507
– – of toe 459
Pharynx 69, 88, 145, 163, **166 ff**
– muscles 168 f
– oral part 92, 167
Pia mater **91**, 94, 102, 120
– spinal 100, 235, **240**
Pivot joint 10 f
Placenta 273
Plane
– axial 4
– of the body 4 f
– coronal 5
– frontal 5
– horizontal 4
– – at the level of the anterior superior iliac spine 208
– – at the level of the inferior thoracic aperture 208
– median 5
– midsaggital 5
– nuchal 27, **33**
– sagittal 4
– transverse 4
Plate
– cribriform, of ethmoidal bone **30 f**, 34, **38**, 49
– horizontal
– – of palatine bone **39 ff**, 42, 44 f, 49
– – of palatine process 146
– orbital
– – of ethmoidal bone **38**, 40 ff, 44 ff, 47, 134
– – of frontal bone 28
– perpendicular **38 ff**, 41 f, 44, 47, 49
– pterygoid
– – lateral 21, 25 f, **33**, 36 ff, 41, 44 f, 62 f, 127, 166
– – medial 25 f, **33**, 36 f, 41, 45, 146, 148, 166
– tarsal
– – inferior 134
– – superior 134, 150
– tympanic 21
Platysma muscle 50, 56, **60 f**, 64, **79**, 151, 176, 298, 397
Pleura 275 f
– costal 274 ff
– position 256
– surface projection of the thorax wall 256
Plexus
– alveolar, superior 74
– aorticorenal 347
– autonomic 324
– brachial 79, 99, 170, 179, **188**, 210, 274, 279, 291, 347, 408, **411**, **424 ff**
– – lateral cord 172, **411**, **425**, 427
– – main branches 425
– – medial cord **411**, **425**, 427
– – middle trunk 408
– – posterior cord **411**, **425**, 427
– – roots 416, **425**
– – ventral rami 18
– celiac 289, 337
– cervical 99, 172, 179, 183, 186, **188**, **425**
– – cutaneous branches 176, **180**, **188**, 211, 230, 242
– – ventral rami 18
– choroid 73, 87
– – of fourth ventricle 116
– – of lateral ventricle **106 f**, 112, 115
– – of third ventricle 88, 107
– dental
– – inferior 70
– – superior 70
– esophageal 285, **287 ff**, 347
– gastric 347
– – anterior 289
– hepatic 289
– hypogastric
– – inferior **238**, 347, **359**
– – superior 324, 341, 347, 371
– lumbar **237**, 486
– lumbosacral 18, **486 f**
– – main branches 486
– mesenteric, superior 311
– nervous, of autonomic system 18
– parotid, anastomoses of the branches of the facial nerve 80
– pelvic 361
– pharyngeal 167
– prostatic 357
– pudendal 486
– renal 347
– sacral 238, 361, **486 ff**
– solar 18
– splenic 289
– tympanic 128 f
– venous
– – extradural 240
– – of lateral malleolus 505
– – pampiniform 222, 352, **355**, 359 f
– – – anterior veins 355
– – – posterior veins 355
– – prostatic 359, 361, 363
– – thyroid, inferior 186
– – uterine 378
– – vesicoprostatic 353, 358
Plica circularis of duodenum 306
Points, palpable
– dorsal 3
– ventral 2
Pons 68, 70, 88, 93, 105, **116 f**

Page numbers in **bold** indicate main discussions.

– cross section 123
– median section 92 f, 241
– in neonate 241
– transverse fibers 111
Porta hepatis 308
Portal venous system 313
Posterior 4
Pouch
– recto-uterine 332, **366 f**, 369 ff, 378
– rectovesical 349 f, 357
– vesico-uterine 332, **366 f**, 369 f, 378
Premaxilla 33
Premolar
– first 50
– second 50
Prepuce
– of clitoris 373, **375 ff**
– of penis 348, **353**
Process(us) 201
– alveolar
– – of mandible 22, **52**, 92
– – of maxilla 22, 37, 39 ff, 42, 44 ff, **52**, 92
– articular
– – inferior
– – – of axis 194
– – – of vertebra 199, **205**
– – superior
– – – of sacrum 451, 453 ff
– – – of vertebra 199, **205**
– – of vertebra 199, **205**
– ciliary 140
– clinoid
– – anterior 25 f, **30**, 34, 36, **38**, 77
– – posterior 25 f, **30**, 34, **38**
– cochleariform 129 f
– condylar, of mandible 20 f, 36, **50**, **52**, 56
– – articular cartilage 54
– coracoid **381 ff**, 384, 390, 423
– coronoid 54
– – of mandible 20 f, **52**, **54 ff**, 81
– – of ulna **386 f**, 391
– costal 199 ff, **206**
– ethmoidal, of inferior nasal concha 48
– frontal
– – of maxilla 22, 28, 37, **39 ff**, 42, 45, 47, 134, **146**
– – of zygomatic bone 45, 52
– intrajugular 39
– jugular 25, 39
– lacrimal, of inferior nasal concha 48
– lateral, of malleus 130
– lenticular 129 f
– mamillary, of vertebra 199
– mastoid 20 f, 27 ff, **33**, **55**, 125
– maxillary
– – of inferior nasal concha 42, 46, **48**
– – of palatine bone 40
– muscular 199
– – of arytenoid cartilage 160
– – of vertebra 199
– odontoid, of axis 88
– orbital, of palatine bone 39 f, 42, 44, 134
– palatine, of maxilla 33, 41 f, 44 f, **48**, **146**
– perpendicular of palatine bone 49, **146**
– pterygoid 21, 36, 128
– – of newborn 33
– pyramidal, of palatine bone 39 f, 42, 45
– sphenoidal, of palatine bone 39 f, 42
– spinous 3, 199 f, 203
– – of axis 193 ff, 226 f, 229
– – of cervical vertebra 179, 195, **199**, 202 f
– – of lumbar vertebra **199**, 202 f, 207
– – of seventh cervical vertebra 226 f, 243 f
– – of thoracic vertebra **199**, 202, 205
– styloid
– – of radius 386 ff, 392 f
– – of temporal bone 27 f, 33, 54 f, 62 ff, 73, 126, 129, **153**, 166, 168
– – of ulna 386 ff, 393
– talar, posterior 459
– transverse
– – of atlas 193 f
– – of cervical vertebra 179
– – of thoracic vertebra 229
– – of vertebra 179, 199 f, **205**, 229
– uncinate
– – of ethmoidal bone 37, 46
– – of pancreas 306
– vaginal 222, **223**
– vocal, of arytenoid cartilage 160
– xiphoid **201**, 204, 210, 274, 316, 381
– zygomatic
– – of frontal bone 28, **44 f**
– – of maxilla 22, 39 ff, 42, 44 f
– – of temporal bone 21, 27 f, 127
Prominence
– saccular 130
– utricular 130
Promontory
– sacral 190, **238**, 318, 340, 349, **358 f**, 368, **452 ff**, 487
– – midsagittal section 332
– of tympanic cavity 127 ff
Pronation 387, **403**
Prostate 348 ff, **356**
– coronal section 357
Protuberance
– mental 22 f, **52**
– occipital
– – external 21, 25, 27, 29, **33**, 193, 195, 227, 247
– – internal 25, 27, **30**, 39, 42
Pubis 7, **448 ff**, 453 f, 514
– symphysial surface 453 f
Pulvinar of thalamus 110, 112, **117**, 144
Punctum nervosum 65, **79**, 250
Purkinje fibers 269
Putamen 94, 107 f, **110**, **112**, 118, 122
Pylorus **303 f**, 307, 319, 328
– muscle layer, circular 303
– position 300
Pyramid 68, 128
– anterior surface 125
– of vermis 104

R

Radiation 122
– acoustic 133
– of Gratiolet see Radiation, optic
– optic **111**, 121 f, **142**, 144
Radius 7, 10, 190, **386 ff**, 391 ff, 438 f, 441
– anterior surface 386 ff
– articular surface 386 f
– axial section 431, 445
– of newborn 9
– posterior surface 386 ff
Ramus
– communicans, of sympathetic trunk 289 f
– of ischium 451 f
– of mandible 22 f, **52**, 152
– pubic, inferior 354
Raphe
– fibrous, of pharynx 169
– mylohyoid 158
– pterygomandibular 63, **168 f**
Recess
– costodiaphragmatic 256, **275**, 292
– duodenal
– – inferior 328
– – superior 318, 328
– elliptical 131
– epitympanic 127, 130
– hypotympanic 127, 130
– ileocecal 328
– inferior, of tympanic cavity 128
– infundibular 114, 142
– intersigmoid 328
– lateral, of fourth ventricle 118
– optic 114, 118
– paracolic 328
– peritoneal 328 f
– pharyngeal 146
– pineal 114
– piriform 163, 165
– retrocecal 328
– of Rosenmüller 147
– spheno-ethmoidal 146 f
– spherical 131
– splenic, of lesser sac 328
– superior, of lesser sac 328
– suprapineal 114
Rectum 318
Region(s)
– abdominal
– – lateral 208
– – upper 305

Page numbers in **bold** indicate main discussions.

Region(s)
– anal
– – in the female 375 ff
– – in the male 362 ff
– axillary 208, 419 f, **422 ff**
– – lymph nodes 17, 298, 342, 422
– – lymphatic vessels 422
– – quadrangular spaces 420 f
– – triangular spaces 420 f
– cervical 157
– – anterior 157, **176 ff**, 208
– – – deep layer 178
– – – deeper layer 177, 179
– – – superficial layer 176 f
– – lateral 157, **180 ff**, 208
– – – deep layer 182 f
– – – deeper layer 186
– – – deepest layer 187 f
– – – superficial layer 180 f
– – posterior 157
– crural 501 ff
– – anterior 504
– – – deep layer 506
– – – middle layer 506
– – antero-medial 501
– – lateral 505
– – medial 504
– – posterior 501 ff
– cubital 428 ff
– – deep layer 430
– – middle layer 429
– – posterior 225
– – superficial layer 428
– deltoid 208, 225
– epigastric 208
– facial, deep dissection 82 ff
– femoral, in the male 223
– gluteal 225, 494 ff
– hypochondriac 208
– infraclavicular 419
– inframammary 208
– infrascapular 225
– inguinal 208
– – in the female **224**, 374
– – in the male 223, 353
– of knee 498 f
– lateral
– – of head 78 ff
– – of neck 181
– lumbar 225
– malleolar 484
– mammary 208
– nuchal 242 ff
– – deeper layer 243
– – deepest layer 244 ff
– – superficial layer 242
– parapharyngeal 31, **153**
– pectoral 208
– peripharyngeal 83
– popliteal 474
– presternal 208
– pubic 208
– retromandibular 80, **82 ff**
– – deep dissection 82 ff
– retroperitoneal 340 ff
– – lymph nodes 342
– – lymph vessels 342
– – nerves 345 f
– – vessels 345
– sacral 225
– scapular 225, 421
– sternocleidomastoid 157, 208
– sublingual 153
– submandibular 80, 185
– superficial, of face 78
– suprascapular 225
– umbilical 208
– urogenital 208
– – in the female 375 ff
– – in the male 362 ff
– vertebral 225
Reil, island of 96, **111**, **118**, 121 f
Respiration, changes of the position of diaphragm 292
Respiratory system 254 ff
Retina 140, 143
Retinaculum see Extensor retinaculum, see also Flexor retinaculum
Rhombencephalon, cross section 119
Rib(s) 7, 190, 192, **198**, **381 ff**
– cartilaginous parts 381
– of child, position 7
– false 381
– first 161, 187, 201, 210, 384
– floating 203, 382
– second 201
– true 203, 381
– twelfth 201 f, 309, 469
Ridge, supracondylar
– lateral 385
– medial 385
Rima glottidis 163
Ring
– ciliary 140
– inguinal
– – crus, lateral 221
– – deep 216, 222, 301, 349, 353, 357, **359**, **374**
– – superficial 221 f, 224, **352**, 374
– – – crus
– – – – lateral 221, 374
– – – – medial 374
– tendinous, common 139
– tympanic 127
– umbilical 213, 217
Riolan's anastomosis 314 f
Roof of orbit 74
Root(s)
– of brachial plexus 416, **425**
– inferior, of ansa cervicalis 186
– of median nerve 411, 423, 427
– of mesentery 316, 328
– of meso-appendix 328
– of mesosigmoid 328
– of penis 301, 354
– posterior, filaments 100, 247
– superior, of ansa cervicalis 71, 73, **85**, 154, 181
– of tongue 163
– of transverse mesocolon 320, 328
Rostrum, sphenoidal 25 f

S

Sac
– endolymphatic 131
– lacrimal 135
– lesser 300, **319 ff**
– – horizontal section 319
– – isthmus 328
– – midsagittal section 332
– – posterior wall 321
– – splenic recess 328
– – superior recess 328
– – vestibule 334
– pericardial 283
– – upper margin 279
Sacrum 3, 7, 190 ff, **198 ff**, 202, 238, 447 f, 494
– lateral part 199, **454**
– pelvic surface 453
– shape 451
– surface anatomy 488
Saddle joint **11**, 389
Scalp 87
Scapula 7, 15, 190 ff, 227, **381 ff**, 390
– articular facet for the acromion 383
– costal surface 381, 383
– of newborn 9
– posterior surface 382, 384
Sclera 134, **140**
Segment(s)
– bronchopulmonary 254, **258 f**, 285
– of kidney 336
– of liver 308
Sella turcica 25 f, **30**, 34, 36, 38, 46, 49
– of newborn 35
Semicanal of auditory tube 132
Septum(-a)
– intermuscular
– – lateral, of arm **399**, 404
– – medial, of arm **399 f**, **417 f**, 428, 435
– – of thigh 471
– interventricular 266 ff
– lingual 151
– nasal 22, **49**, 134, **146**, **148**
– – posterior border **48**
– pectiniforme 354
– pellucidum 88, 94, **96**, 105 ff, 108, 118, **120 ff**

Page numbers in **bold** indicate main discussions.

– of penis 351, 359
– of testis 355
– of tongue 64
Shaft
– of femur 9, **454 f**
– of fibula 456
– of radius 386 f
– of rib 199 f
– of tibia 456
Sheath(s)
– carotid 176
– fibrous
– – digital, of tendons of flexor digitorum muscle 401
– – of flexor tendons of hand 403, 406, **441 f**
– of rectus abdominis muscle
– – anterior layer 204, **212 ff**, 216, 219, **274 f**, 492
– – posterior layer 210, **216 ff**, 219 f, 301
– – surface anatomy 208
– of round ligament 224
– synovial see Synovial sheath
Shoulder 415 ff
– collateral circulation 416
– horizontal section 444
– joints 390
– ligaments 390
– muscles 394 ff
– – course 395
– – deep layer 397, 421
– – position 395
– – superficial layer 396, 420
– nerves 420
– region
– – anterior 418 f
– – posterior 415 ff
– vessels 420
Shoulder girdle 7
– skeleton 10, 192, 381 ff
Shoulder joint **15**, **390**, 394 ff
– articular cavity 10, 15
– bones 384
– coronal section 11, 390
– frontal section 15
– ligaments 390
– MRI scan 11, 15, 390, 444
– of newborn 9
– schematic drawing 15
– X-ray 15
Shunt in fetal circulatory system 272
Sinus(es)
– aortic 269
– carotid 65, **408**
– cavernous 31, 64, **89**, 99, 126, 143, 148
– coronary 265, 283, 294
– – opening 266, 269
– dural 87
– ethmoidal 123, **150**
– frontal 37, **46**, **48**, 75, 86, 88, 90 f, **145 ff**
– – opening 146
– intercavernous 89
– lactiferous 298
– of larynx 88
– maxillary 37, 46, 134, **146**
– – innervation of mucous membrane 74
– oblique, of pericardium 282 f
– paranasal 146 f
– – connection with nasal cavity 146
– pericardial, transverse 279, 282 f
– petrosal, superior 89
– of pulmonary trunk 267
– renal 336
– sagittal
– – inferior 87, 89
– – superior 77, **87 ff**, 249
– sigmoid 89
– sphenoidal 36 f, **48 f**, 64, **88**, 90 f, 123, 146, 148, **150**
– – opening 25
– sphenoparietal 89
– straight 69, 77, **87 ff**, 123
– tarsal 459
– transverse 69, 123, 249
– venous, dural 88 f
Skeleton 6 ff, 190 ff
– appendicular 7
– of arm 10
– axial 7
– of a child 7
– cranial, of newborn 35
– facial 23
– – of newborn 35
– of female adult 6
– of foot **458 f**, 465
– of forearm 387
– of hand 11, 387 ff
– of leg 456
– of lower limb 447 f
– of pelvic girdle 447 f
– of pelvis 448 ff
– of shoulder girdle 10, 381 ff
– of thorax 201 ff, 381 f
– of trunk 190 ff
– visceral 22
– of wrist 11, **388 f**
Skin of scalp **91**, 244
Skull
– anterior aspect 22 f
– base see Base of skull
– bones 20 ff
– disarticulated 20, 24 ff
– lateral aspect 20 f
– median section 36 f
– of newborn 33, **35**
– paramedian section 46
– periosteum 87
Skull diploe **30**, 87, 89, **97**
Small intestine 3, 214
– of fetus 273
– Head's zone 209
– position 300
– vessels 310 ff
– – lymphatic 311
Snuffbox, anatomical 406, 442
Sole 510 ff
– aponeurosis 479
– crossing of tendons 511 f
– deep layer 512
– middle layer 510 f
– MRI scan 513
– muscles
– – deep layer 481
– – deepest layer 481
– – middle layer 480
– – superficial layer 479
– nerves 511
– superficial layer 510
– synovial sheaths of flexor tendons 511
– tendons of long flexor muscles 477
– vessels 511
Space
– epidural, spinal 240
– extradural, spinal 240
– infratentorial 90
– intercostal
– – nerve see Nerve, intercostal
– – vessels see Artery, intercostal, see Vein, intercostal
– quadrangular, of axillary region 420 f
– subarachnoid **87**, 99, 238, 249
– – spinal 240
– subdural 120
– – spinal 240
– triangular, of axillary region 420 f
Sphincter
– lower, of esophagus 288
– middle, of esophagus 288
– of Oddi 306
– upper, of esophagus 288
Sphincter muscle
– anal
– – external 348 f, 354, **361 ff**, **375 ff**
– – internal 348
– pyloric 302 f
– urethral 350, 361, 378
– – external 348
– – internal 348
– of urinary bladder 350
Spinal cord **18**, 64, 86, 88, 91, 93, 179, 219, **234 ff**, 239, 247
– lumbar part 234
– meningeal coverings 240
– organization of segments in relation to the vertebral column 237
– roots filaments 238, 247
– segments
– – cervical 237

Page numbers in **bold** indicate main discussions.

Spinal cord
– segments
– – lumbar 237
– – sacral 237
– – thoracic 237
– terminal part 234 ff
– thoracic part 235
Spine 383, 449
– frontal 42
– iliac
– – inferior
– – – anterior **449 f**, 453
– – – posterior 453
– – superior
– – – anterior 3, 220, 238, **448 ff**, 453 f, 468 f, 492
– – – – horizontal plane 208
– – – – surface anatomy **208**, 489
– – – posterior 449, 451, 453, 494
– ischial **447 ff**, 453 f
– mental 36, **52**
– nasal 28
– – anterior 20, 36, 39, **45 ff**
– – of frontal bone 47
– of scapula 3, 242, **382 f**, 394 f, 420 f
– of sphenoid 25, 129
– trochlear 22
Spine-trochanter line 494
Spine-tuber line 494
Spleen 17, 289, 304 f, **309**, 313 f, 319, 326 f, 339
– blood supply 323
– border
– – anterior 309
– – superior 309
– horizontal section 334
– location 309
– visceral surface 309
Splenium of corpus callosum 67, 101, **106 ff**, 121 f, 144
Squama
– of occipital bone 20 f
– of temporal bone 20 f
Stapes 20, 124 f, 128, **130 f**
Sternum 7, 190, 203, 210, 274, 381
Stomach 289, 294, 300, **302 f**, 305, 313, 316, 319
– cardial part 302 f, 339
– circular muscle layer 303
– of fetus 273
– Head's zone 209
– longitudinal muscle layer 303
– midsagittal section 332
– muscular coat 303
– position 3, 302
– pyloric part 303, 326
– sagittal section 253
Stria
– acoustic, dorsal 133
– longitudinal 112
– – lateral **106 ff**, 115
– – medial 106 ff
– medullaris 101, 117
– – of thalamus 109
– olfactory
– – lateral 105, **109**, **144**
– – medial 105, 109, **144**
– terminalis 105 ff, **109**, 120
Substance, perforated
– anterior 68, 101, 105, **144**
– posterior 105, 144
Substantia nigra 67, 101, **105**, 118, 142, 144
Sulcus
– calcarine **101**, 105, 144
– – communication with parieto-occipital sulcus 101
– carotid **30**, 38
– central 86, 91 f, 96, 102 f
– – of insula 74
– chiasmatic 25, **30**
– cingulate 101
– circular, of insula 111
– coronary 262, 264 ff, 269 f
– of corpus callosum 101
– frontal, superior 102
– infra-orbital 134
– intertubercular 385, 390
– interventricular 278
– – anterior 261 f, **264**
– – posterior 262, **270**
– lateral 86, 91, 102
– – ascending ramus, anterior 102 f
– – horizontal ramus, anterior 102 f
– – posterior ramus 103
– lunate 102
– malleolar, of tibia 456
– mylohyoid 52
– olfactory 68
– orbital, of frontal lobe 68
– parieto-occipital 101
– postcentral 102 f
– precentral 101 ff
– temporal, inferior 68
– terminalis 268 f
– – cordis 264 f, 268
Supination 387, **403**
Surface
– articular
– – inferior, of tibia 456
– – malleolar, of fibula 456
– – of navicular bone 466
– – navicular, of talus 466
– – of patella 457, 464
– – superior, of tibia **456**, 463
– – talar
– – – anterior, of calcaneus 466
– – – posterior, of calcaneus 466
– auricular, of sacrum 199, 453
– bare
– – of ascending colon 328
– – of descending colon 328
– calcaneal
– – anterior, of talus 466
– – middle, of talus 466
– – posterior, of talus 466
– diaphragmatic
– – of liver 307
– – of lung 257
– gluteal, of ilium 451
– lateral, of tibia 456
– lunate, of acetabulum 450, **453**, 461
– malleolar, lateral, of talus 459
– patellar, of femur 455, 457, 463
– pelvic, of sacrum 453
– popliteal, of femur 455, 457
– posterior
– – of fibula 456
– – of tibia 456
– symphysial, of pubis 453 f
Surface anatomy 208 f
Sustentaculum tali **459**, 466
Suture
– coronal 20 ff, **29**, **35**
– ethmoidolacrimal 20
– frontal 22 f, **35**
– frontomaxillary 23
– frontonasal 22
– frontosphenoid 21
– intermaxillary 22
– internasal 22 f
– lacrimomaxillary 20
– lambdoid 20 f, **29**, **35**
– nasomaxillary 20 ff, 23
– of newborn 35
– occipitomastoid 20 f, **29**
– palatine
– – median 33, 45
– – transverse 45
– palatomaxillary 33
– parietomastoid 20
– sagittal 29, 35
– sphenofrontal 20, 23
– sphenosquamosal 21
– sphenozygomatic 23
– squamomastoid 127
– squamous 20 f
– zygomaticomaxillary 22 f
Symphysis, pubic 7, 190, 301, 378, **447 ff**
– midsagittal section 332
Synchondrosis, spheno-occipital 27, **38**
Syndesmosis, tibiofibular 456, **459**, 507
Synovial fluid 12
Synovial sheath
– common, of flexor tendons of hand 402 f
– digital, of flexor tendons of hand 402 f
– of extensor tendons of hand 404
– of flexor tendons of hand 402 f
– of hand 14, **402 ff**
– of tendon of extensor muscles of foot 507

Page numbers in **bold** indicate main discussions.

– of tendon of flexor pollicis longus muscle 402 f
Systole 264

T

Taenia
– of choroid plexus 108
– coli 316
– free, of colon 318, 328
Tail
– of caudate nucleus 117
– of epididymis 355 f
– of pancreas 305 f, 309, 326
Talus 447, **459**, 465 f
– of newborn 9
– surface
– – articular, navicular 466
– – calcaneal
– – – anterior 466
– – – middle 466
– – – posterior 466
Tectum of midbrain 96, **110**, **116**
Telencephalon 93
Tendon 427
– of abductor pollicis longus muscle 400, **402**, 404, 406, 413, 441
– annular, common 139
– of biceps femoris muscle 471 f, 496
– – surface anatomy 488 f
– calcaneal 465 f, **473 ff**, 501, 503 ff
– – surface anatomy 488
– central, of diaphragm 285, **288**, 293, 307, 339
– common annular 136
– conjoint 222
– of deep flexors muscles 474
– of extensor carpi radialis brevis muscle 404 ff
– of extensor carpi radialis longus muscle 404 ff
– of extensor carpi ulnaris muscle 404, **436**
– of extensor digiti minimi muscle 404
– of extensor digitorum longus muscle of foot 475, 478, 503, 508 f
– of extensor digitorum muscle of hand 404 ff, 413, **436**
– of extensor hallucis longus muscle **474 f**, 503, **508 f**
– of extensor indicis muscle 404, 406, 413
– of extensor muscles of foot 507
– – synovial sheaths 507
– of extensor muscles of hand 393
– of extensor pollicis brevis muscle 400, 404, 406, 441
– of extensor pollicis longus muscle 404, 406, **436**
– of flexor carpi radialis muscle 392 f, **401 f**, 406 f, **441 f**
– – surface anatomy 414
– of flexor carpi ulnaris muscle 392 f, 400, **402 f**, 406 f, **441 f**
– of flexor digitorum brevis muscle of leg 479 ff
– of flexor digitorum longus muscle of leg 476, 479 ff
– of flexor digitorum profundus muscle of hand **401 f**, 406 f, 441
– of flexor digitorum superficialis muscle of hand **401 f**, 406 f, **441 f**
– of flexor hallucis longus muscle **476 f**, 479, 481
– of flexor pollicis longus muscle 400, **402**, 406 f
– of gracilis muscle 463, 468, **471**, 473
– of iliocostalis muscle 229
– intermediate
– – of digastric muscle 152
– – of omohyoid muscle 181
– – of semitendinosus muscle 472
– of long head
– – of biceps brachii muscle 390, **399**, 427 f, 431
– – of triceps brachii muscle 390 f, 404
– of lumbrical muscle of hand 406
– of palmaris longus muscle 400, 414, 435, **442**
– of peroneus brevis muscle 503
– of peroneus longus muscle 478, **480 f**, 503
– of peroneus tertius muscle 478
– plantar, crossing 481
– of plantaris muscle 500
– of sartorius muscle 468
– of semimembranosus muscle 463
– – surface anatomy 488
– of semitendinosus muscle 463, 468, 499
– of short head of biceps brachii muscle 399
– of stapedius muscle 130
– of superior oblique muscle 136 ff
– of supraspinatus muscle 390
– of temporal muscle 62 f, 82, 85
– of tensor tympani muscle 129
– of tensor veli palatini muscle 129
– of tibialis anterior muscle 474, 477, **508 f**
– of tibialis posterior muscle 476 f
– of triceps brachii muscle 421
Tenon's space 134
Tensor veli palatini muscle 62, 148
Tentorium, cerebellar 69, 77, 85, **89 ff**, 99, 123, 142
Testis 3, 340, **348 f**, 351, 353, 355, 363
– Head's zone 209
– longitudinal section 355
Thalamus 92 f, 101, **105 ff**, 109, 115, 118, 122
Thenar muscles **402 f**, 435
– axial section 445
Thigh
– anterior region 490 ff
– arteries 482 f
– axial section 514
– cross section 471
– muscles 468 ff
– nerves 482 f
– – cutaneous 490 f, 496
– posterior region 496 f
– veins 490 f
Thoracic cage, changes of position during respiration 292
Thoracic organs 252 ff
– in newborn 273
– position 252 ff
– regional anatomy **274 ff**, 278 ff
Thorax 7, **201 ff**
– coronal section 263, **294 f**
– horizontal section 296 f
– MRI scan 263, **294 ff**
– paramedian section 293
– skeleton 201 ff, 381 f
Thymus 157, 241, **275 ff**
– remnants 17, 253, 293
Tibia 7, 12, **447**, **456 ff**, 462
– articular surface
– – inferior 456
– – superior **456**, 463
– of newborn 9
– ossification center 9
– upper end 456
Tissue, adipose, encasing round ligament 375
Tongue 86, 145
– innervation 31, **153**
Tonsil 17
– cerebellar 68, **104**
– lingual 163
– palatine 145, 155, 167
– pharyngeal 146
Tooth (teeth) 50 ff
– deciduous 51
– lower 22, **50 ff**
– molar 42, **50 f**
– – permanent 51
– – third 37
– permanent 50 f
– premolar 37, **50 f**
– upper 22, 41 f, 44 f, **50 ff**
Trabecula, septomarginal 265 f
Trachea 156, **252 ff**, 255, 261, 284 ff, 295
Tract 489
– cerebellorubral 105
– iliotibial 464, **468 f**, 471, **492**
– – surface anatomy 488 f
– olfactory **67 f**, 71, **76 f**, 100 f, 105, 109, **116 f**, 148
– – lateral root 101
– – medial root 101
– olivocochlear 133
– optic 68, 73, 109, **142**, 144
– pyramidal 111, 118
– – course 111
– – lateral 105
– of Rasmussen 133
– spiral, foraminous 126
Tractus solitarius 118
Tragus 124 f

Page numbers in **bold** indicate main discussions.

Triad, portal 308
Triangle(s)
– anterior, of neck 177
– carotid 157, **175**, **180 f**
– clavipectoral 208
– deltopectoral 172, 396, 419
– – surface anatomy 414
– femoral 208
– lumbar 227
– lumbocostal 347
– muscular, of neck 157
– of neck 157
– omoclavicular 208
– submandibular **154**, 157
– – dissection
– – – deep 154
– – – superficial 154
– submental 157
– suboccipital 245
– supraclavicular 157
Trigone
– habenular 116
– olfactory 68, 117, **144**
– of urinary bladder 348, **350**
Trochanter
– greater 9, 447 f, **454 f**, 494
– lesser 448, **454 f**
– third 455
Trochlea 74, **136 f**, 139
– of humerus 385, 391
– peroneal, of calcaneus 459
– of talus 459, 466
Trunk 7
– brachiocephalic 164, **170 f**, 260, 263, 268 f, 277 f, 284 f, **408**, **426**
– bronchomediastinal 342
– celiac 289, 293, 305, 310, 326, **337 ff**, 340 f, 345, 347
– – branches 319, **322 f**
– costocervical 170
– female
– – midsagittal section 332
– – sagittal section 5
– horizontal section 214 f
– jugular 174 f
– – left 342
– lumbar 342
– lumbosacral 487
– lymph vessels 17
– median section 4, 241
– – in neonate 241
– midsagittal section 332
– posterior part 18
– pulmonary 253, 260, **264 ff**, 270, 276, 279, 281
– – of fetus 272
– sagittal section 5
– skeleton 190 ff
– subclavian 175, 186, 342
– sympathetic 18, 69, 148, 164, 166 f, 170, 187, **238**, 276, **289 ff**, 337, **345 ff**, 487 f
– – cervical part 176
– – lumbar part 347
– – Ramus communicans 290
– – – white 291
– – superior cardiac branch 347
– thyrocervical 164, **170 ff**, **179**, 281, 408, 416
– vagal 347
– – anterior 337
– – posterior 337
Tube
– auditory 122, **124 ff**, 128 f, 145
– – bony part 27
– – opening 147
– – pharyngeal opening 88, 146, 254
– uterine 367 ff, 370, **373**
– – insertion of fundus of uterus 370
– – position 334
Tuber
– calcanei 467
– cinereum 101
– frontal 35
– parietal 29, **35**
– of vermis 104
Tuber-trochanter line 494
Tubercle
– anterior
– – of atlas 194, **199**
– – of transverse process 199
– articular 21, 27 f, **50**, 54
– corniculate 162
– coronoid 383
– cuneiform 162
– dorsal, of atlas 227
– genial 36, **52**
– greater, of humerus 384 f, 444
– infraglenoid 382
– intercondylar
– – lateral, of tibia 456
– – medial, of tibia 464
– – posterior, of tibia 456
– jugular 25, 27, 39
– lesser, of humerus 385, 444
– olfactory 101
– pharyngeal 25, 27, **33**, 166
– posterior
– – of atlas 194 f, **199**
– – of transverse process 199
– pubic **449**, 453
– of rib 199 f, 205
– supraglenoid 383
– thyroid
– – inferior 161
– – superior 161
Tuberculum sellae 38
Tuberosity
– calcaneal 459, 466, 473, 479, **481**, 503
– deltoid 385
– of distal phalanx 388 f
– – of great toe 458
– of fifth metatarsal bone 459
– ischial 238, 356, 447 f, **450 f**, 453, 471 f, 494
– masseteric 52
– maxillary 39 ff, 46
– radial 386 ff, 391
– sacral 453
– tibial **456 f**, 474 f
– ulnar 386 f
Tubules, seminiferous, convoluted 355
Tunica
– albuginea
– – of corpora cavernosa 351
– – of corpus spongiosum 351
– – of testis 353
– vaginalis
– – parietal layer 353, **355**
– – testis 222, **355**
– – visceral layer 353, **355**

U

Ulna 7, 10, 190, **386 ff**, 389, 391 ff, 438 f
– anterior surface 387
– axial section 431, 445
– of newborn 9
– posterior surface 386 f
Umbilicus 3, 213
Uncus
– hippocampi 101
– of parahippocampal gyrus 108
Urachus 273, 351, 370
– remnant 357
Ureter 214, 304, 338, **340 ff**, **348 ff**
– abdominal part 336, 340, 348
– Head's zone 209
– pelvic part 340, 348
– position 3, 334 f
Urethra
– female 367
– male 348 f
– membranous part 348 ff, 354, 356
– prostatic part 348 ff, 356 f
– spongy 348 ff
Urinary bladder 334 f
– base 378
– coronal section 367
– of fetus 273
– frontal section 301
– Head's zone 209
– male 348 ff
– midsagittal section 332
– MRI scan 348
– muscular coat 367
Urinary organs, position 334 f
Urinary system 340 f
Urogenital system

Page numbers in **bold** indicate main discussions.

– of the female 366 f
– of the male 348 ff
Uterus 334, **367 ff**, 370
– midsagittal section 332
– position 366
Utricle, prostatic 350
Uvula 64, **88 f**, 146, 165, 167
– of newborn 157
– of urinary bladder 350
– of vermis 104

V

Vagina 332, **367 ff**, 370, 372
Valve(s)
– aortic **261 ff**, 266 f, 294
– atrioventricular
– – left **261 f**, 265 ff
– – right **261 f**, 265 ff, 293, 297
– bicuspid **261 f**, 265 ff
– of heart **261 ff**, 293, 297
– – position 261, **264**
– ileocecal 317f
– – horizontal section 331
– of inferior vena cava 272
– mitral **261 f**, 265 ff
– pulmonary 281, 296
– pulmonic **261 f**, 267
– tricuspid **261 f**, 265 ff, 293, 297
Vasa recta of renal medulla 339
Vein(s) 16
– anastomotic, superior 91
– angular 172
– arcuate 339
– axillary 172, **188**, 204, 219, 274, 410, 423
– azygos 252, 254, 286, **289 f**, 342
– basilic 410, 414, 422, 431, 437
– brachial 410, 427
– – surface anatomy 414
– brachiocephalic 157, 172, **179**, 261, 275, 277, 281, 284, **408**, 410
– – of fetus 272 f
– cardiac
– – great 265 f, 270
– – middle 270
– – minimal 270
– – small 270, 280
– cephalic 172 f, 184, 211, 213, 275, 298, 410, **418**, 428, 432
– – accessory 413 f
– – on forearm 410, **413 f**, 431
– – surface anatomy 414
– cerebral 94
– – great 92, 147
– – inferior 91
– – internal 88
– – superior 91
– cubital, median 410, **414**, 428, 431 f
– – surface anatomy 414
– cutaneous
– – of leg 501
– – of popliteal fossa 498
– – of region of knee 498
– – of thigh 496
– deep, of leg 485
– digital
– – dorsal
– – – of foot 484
– – – of hand 437
– – of hand 410
– dorsal
– – deep, of penis 221 f, **351 ff**, 354, 358, 362
– – superficial, of penis 358, 491
– epigastric
– – inferior 216, 223
– – superficial 214 f, 221, 484
– – superior 210, 212
– ethmoidal, anterior 31
– facial 79, **81**, 154, 172, 410
– femoral 219, 301, 352, 378, 468, **483 f**, **491 f**, 514
– – entering the adductor canal 468
– gastric, left 313
– gastro-omental 313
– of heart 270
– hemiazygos 289
– – accessory 289, 297
– hepatic 308, 313, 345
– ileal 313
– ileocolic 313
– iliac
– – circumflex, superficial 214 f, 221, **484**, 491
– – common 331
– – external 301, **357 f**, **484**
– – internal 289
– intercostal 210, **214 f**, 342
– – anterior 211
– – posterior 286, 289 ff
– – – dorsal branches 420
– – superior 291
– interlobar, of kidney 339
– interlobular, of kidney 339
– intermedian, of forearm 432
– interventricular, anterior 270, 280
– jejunal 311, 313
– jugular
– – anterior 172, 176, 410
– – external **79**, 82, 172, 176, **274 f**, 410
– – internal 82, 126, 128, 154, 156, 167, 172 f, 179, 181, **274 f**, 284 f, 410
– – – of fetus 273
– labial
– – inferior 172
– – superior 172
– of labyrinth 31
– lacrimal 138
– of leg, anastomoses 485
– lumbar 347
– – ascending 289
– marginal, right 270
– medial, of retina 141
– median, of forearm 414
– meningeal, middle 89 f
– mesenteric
– – inferior 305, 313, 324
– – superior 300, 304 f, **310 ff**, **325 f**
– metacarpal, dorsal 410, 437
– metatarsal, dorsal 484
– oblique, of left atrium 270
– occipital **87**, 172, 410
– ophthalmic, superior 31
– ovarian 370
– paraumbilical 313
– perforating 484, 504
– pericardiacophrenic 282, 291
– peroneal 484
– plantar
– – lateral 512
– – medial 512
– popliteal 462, **483**, 496, 498 ff
– portal 16, 304, 308, **313 f**, 323, 327
– – of fetus 273
– – main tributaries 313
– of posterior abdominal wall 289
– posterior, of left ventricle 270
– of posterior thoracic wall 289
– pudendal, external 483 f, **491**
– – superficial 214, 221
– pulmonary 16, 281, 293
– – branches 254
– – of fetus 272 f
– – left 257, 282 ff, 286, 291
– – mediastinal dissection 255
– – right 257, 282 f, **284**, 286, 293
– radial 431
– rectal, superior 313
– renal 300, **336**, 341
– – left 337
– – right 339 f
– retinal, central 140
– retromandibular 79 f, 154
– sacral, median 289
– saphenous
– – accessory 491
– – anastomoses 484, 501
– – great 214 ff, 219, 221 f, 352, 356, **483 f**, 492, 498, 501, 504
– – small **484**, 496, 501, 504 f
– – – anastomoses with great saphenous vein 484, 501
– scapular, circumflex 390, **420 f**
– scrotal, posterior 363
– sigmoid 313
– spermatic 341
– splenic 302, 313, 327
– subclavian 172 f, 186, 211, 261
– – right 274 ff, 280

Page numbers in **bold** indicate main discussions.

Vein(s)
– subcortical, of kidney 339
– submental 154, 172
– superficial
– – of dorsum of the foot 485
– – of leg 485
– supra-orbital 172
– suprascapular 390
– sural 499
– temporal
– – inferior, of retina 141
– – superficial **79**, 81, 87, **170**, 172, 185, **410**
– – superior, of retina 141
– testicular 353, 361
– thoracic
– – internal **212**, **274 ff**, 410
– – lateral 204, 212, 298, 410
– thoraco-epigastric 211, 422 f
– thymic 280
– thyroid
– – inferior 172, 183, 279, 282
– – superior 172, 175
– tibial
– – anterior 484
– – posterior 484
– umbilical 273
– vertebral 176
– vorticose 138
Velum, medullary, superior 104, 116
Vena
– cava
– – inferior 214, 282, **287**, 295, 313 f, 319, 334, 337, **339 ff**
– – – of fetus 272 f
– – – opening 266, 272
– – – valve 272
– – superior 171 f, 179, 261, 264 ff, 280 f, 290, **292**, 294 f, 342, 408
– – – entrance into the right atrium 293
– – – of fetus 272 f
– – – junction with left brachiocephalic vein 293
– vorticosa 138
Venous system, portal 313
Ventral 4
Ventricle 279
– of brain 114 f
– fourth 73, 87 f, 93, 96, 104, **114**, 118
– of larynx 163
– lateral 73, 93 f, **106 f**, 112, 118
– – central part 114, 120
– left 16, 252, 261, 265 f, 268, **278 ff**, 281, 283, 295
– – in contraction 265
– – in dilatation 265
– – of fetus 272
– right 16, 252 f, 261, **278 ff**, 283
– – of fetus 272 f
– – horizontal section 297
– – midsagittal section 332
– third 87 f, 92 f, 101, 107, 109, **114**, 116, 121 f
– – inferior wall 75
Vermis of cerebellum 68, 76 f, 96, **104 ff**, **107**, 109, 118, 142, 248
Vertebra(e) 198 ff
– cervical 7, 161, 190 ff, **198**
– – articular facets 200
– – seventh 191, 202, 226 f, 243, **381 f**
– characteristics 199
– lumbar 7, 190 ff, **198**, 447 f
– – articular facets 200
– – fifth 238, **448**, 454
– – first 238
– – ligaments 207
– prominens 191, 202, 226 f, 243, **381 f**
– thoracic 7, 191, **198**, **205 f**
– – articular facets 200
– – demifacet for head of rib
– – – inferior 205
– – – superior 205
– – first 201
– – ligaments 205 ff
– – twelfth 201, 238, **381 f**
Vertebral column 7, 86, **193 ff**, **201 ff**, 381 f
– cervical 193, **195 ff**
– – coronal section 196
– – ligaments 195
– – midsagittal section 197
– – MRI scan 196 f
– connection
– – with the head 194 f, **203**
– – with the pelvis 203
– ligaments 206 f
– lumbar 238 f
– – first 381 f
– – median section 239
– – paramedian section 239
– midsagittal section 332
– organization of spinal cord segments 237
Vertex of the skull 86
Vesicle, seminal 348 ff, 353 f, 356
Vessels see also Artery, see also Vein
– of arm 427 ff
– cranial
– – related foramina 31
– – related regions 31
– gastro-omental 319 f
– lymphatic see Lymph vessels
– meningeal 90
– tibial, posterior 484
Vestibular apparatus 131
Vestibule
– of lesser sac 334
– nasal 55, **146 f**
– of oral cavity 50, 55, **152**
– of vagina 367, **373**
Vicq d'Azyr, fasciculus of 110
Vidian canal 25, **33**, 45 f, 148
Vinculum
– breve 406
– of flexor tendon 406
Vision, binocular 143
Visual apparatus 134 ff
Visual pathway 142 ff
– 3-D reconstruction 143
– injuries 143
Vomer 20, 22 f, 33, 45, **47 ff**
Vortex of cardiac muscle fibers 262

W

White matter 120
– frontal lobe 94
Willis, arterial circle of **95**, **97**, 100
Window, round 127 f, 130
Wing see also Ala
– greater, of sphenoidal bone 20, 22 f, **25 f**, 34, **38**, 40 f, 47, 134
– – cerebral surface **25**, 52
– – maxillary surface 38
– – of newborn 35
– – orbital surface 25, **38**, 40 ff, 45
– – temporal surface 25, 42, 44
– lesser, of sphenoidal bone 22 f, **25 f**, **30**, 34, **38**, 40 ff, 44, 134
Wrist of hand
– anterior region 440, **443**
– coronal section 392
– ligaments 392 f
– MRI scan 392
– skeleton 11, 388 f
Wrist joint 387

X

X-ray, structures
– muscular 15
– skeletal 15

Z

Zona, orbicularis 460 f

Human Anatomy

FIFTH EDITION

Saladin

Mc
Graw
Hill
Education

Human Anatomy

FIFTH EDITION

Kenneth S. Saladin
Georgia College & State University



Digital Authors

Stephen J. Sullivan
Bucks County Community College
Christina A. Gan
Highline College

Mc Graw Hill Education

HUMAN ANATOMY, FIFTH EDITION

Published by McGraw-Hill Education, 2 Penn Plaza, New York, NY 10121. Copyright © 2017 by McGraw-Hill Education. All rights reserved. Printed in the United States of America. Previous editions © 2014, 2011, and 2008. No part of this publication may be reproduced or distributed in any form or by any means, or stored in a database or retrieval system, without the prior written consent of McGraw-Hill Education, including, but not limited to, in any network or other electronic storage or transmission, or broadcast for distance learning.

Some ancillaries, including electronic and print components, may not be available to customers outside the United States.

This book is printed on acid-free paper.

1 2 3 4 5 6 7 8 9 0 DOW/DOW 1 0 9 8 7 6

ISBN 978-0-07-340370-0
MHID 0-07-340370-9

Senior Vice President, Products & Markets: *Kurt L. Strand*
Vice President, General Manager, Products & Markets: *Marty Lange*
Vice President, Content Design & Delivery: *Kimberly Meriwether David*
Managing Director: *Michael S. Hackett*
Brand Manager: *Chloe Bouxsein*
Director, Product Development: *Rose Koos*
Product Developer: *Donna Nemmers*
Marketing Managers: *Jessica Cannavo / James F. Connely*
Director of Digital Content: *Michael G. Koot, PhD*
Director, Content Design & Delivery: *Linda Avenarius*
Program Manager: *Angela R. FitzPatrick*
Content Project Managers: *Vicki Krug / Brent dela Cruz*
Buyer: *Laura M. Fuller*
Design: *David Hash*
Content Licensing Specialists: *Lori Hancock/Lorraine Buczek*
Cover Image: *Human head, x-ray, © Pasieka/Science Photo Library/Getty Images RF; White matter fibers of the human brain, © Pasieka/Science Photo Library/Getty Images; Pyramidal neurons of the cerebral cortex impregnated with the Golgi method, © Jose Luis Calvo/Shutterstock.*
Compositor: *MPS Limited*
Printer: *R. R. Donnelley*

All credits appearing on page or at the end of the book are considered to be an extension of the copyright page.

Library of Congress Cataloging-in-Publication Data

Saladin, Kenneth S., author. | Sullivan, Stephen J., author. | Gan, Christina A., author.
Human anatomy / Kenneth S. Saladin, Georgia College and State University; digital authors, Stephen J. Sullivan, Bucks County Community College, Christina A. Gan, Highline College.
Fifth edition. | New York, NY : MHE, [2017] | Includes index.
LCCN 2015042424 | ISBN 9780073403700 (alk. paper)
LCSH: Human anatomy—Textbooks.
LCC QM23.2 .S25 2017 | DDC 612—dc23 LC record available at http://lccn.loc.gov/2015042424

The Internet addresses listed in the text were accurate at the time of publication. The inclusion of a website does not indicate an endorsement by the authors or McGraw-Hill Education, and McGraw-Hill Education does not guarantee the accuracy of the information presented at these sites.

mheducation.com/highered

BRIEF CONTENTS

Preface viii

PART ONE

Organization of the Body

1 The Study of Human Anatomy 1
2 Cytology—The Study of Cells 25
3 Histology—The Study of Tissues 53
4 Human Development 84

PART TWO

Support and Movement

5 The Integumentary System 108
6 The Skeletal System I: Bone Tissue 131
7 The Skeletal System II: Axial Skeleton 151
8 The Skeletal System III: Appendicular Skeleton 184
9 The Skeletal System IV: Joints 205
10 The Muscular System I: Introduction 235
11 The Muscular System II: Axial Musculature 263
12 The Muscular System III: Appendicular Musculature 293
Atlas of Regional and Surface Anatomy 329

PART THREE

Integration and Control

13 The Nervous System I: Nervous Tissue 351
14 The Nervous System II: Spinal Cord and Spinal Nerves 371
15 The Nervous System III: Brain and Cranial Nerves 398
16 The Nervous System IV: Autonomic Nervous System and Visceral Reflexes 442
17 The Nervous System V: Sense Organs 460
18 The Endocrine System 497

PART FOUR

Maintenance

19 The Circulatory System I: Blood 519
20 The Circulatory System II: The Heart 539
21 The Circulatory System III: Blood Vessels 563
22 The Lymphatic System and Immunity 609
23 The Respiratory System 631
24 The Digestive System 653
25 The Urinary System 684

PART FIVE

Reproduction

26 The Reproductive System 703

Appendix A: Answers to Study Guide Questions A-1
Appendix B: Lexicon of Biomedical Word Elements B-1
Glossary G-1
Index I-1

ABOUT THE AUTHORS



© Tim Vacula

KENNETH SALADIN is Distinguished Professor of Biology at Georgia College & State University, where he has taught since 1977. He received his B.S. in zoology at Michigan State University and his Ph.D. in parasitology at Florida State University. Ken teaches human anatomy and physiology, introduction to medical physiology, histology, premedical seminar, and animal behavior, among other courses. He is a member of the Human Anatomy and Physiology Society, American Association of Anatomists, American Physiological Society, Society for Integrative and Comparative Biology, and American Association for the Advancement of Science. He is the author of the best-selling textbook *Anatomy & Physiology: The Unity of Form and Function* and coauthor, with Robin McFarland, of *Essentials of Anatomy & Physiology.* Ken has used the earnings from his textbooks to fund ecosystem conservation and restoration in the Galápagos Islands, to support the Charles Darwin Research Station in the Galápagos, to remodel and equip a Georgia College anatomy laboratory, and to establish multiple student scholarships and an endowed chair in biomedical science and premedical mentoring. Ken and his wife Diane live in Milledgeville, Georgia, and have two adult children in North Carolina.

Courtesy of Tabitha Dell'Angelo

STEPHEN J. SULLIVAN, digital author for the Connect question bank, has been teaching anatomy and physiology at Bucks County Community College in Pennsylvania since 2002. Steve started consulting with McGraw-Hill on the development of digital tools in 2009. His goal for Connect is to create digital assessments that directly reflect the content and style of Ken Saladin's text, provide student access, and foster student success. Steve is a member of the Human Anatomy and Physiology Society and the American Association of Anatomists, and is a 2013 recipient of the Lindback Award for Distinguished Teaching.

© Chris Gan/Yuen Lui Studios

CHRISTINA A. GAN, digital author for the Connect testbank, has been teaching anatomy and physiology, microbiology, and general biology at Highline College in Des Moines, Washington, since 2004. Before that she taught at Rogue Community College in Medford, Oregon, for six years. Christina earned her M.A. in biology from Humboldt State University, researching the genetic variation of mitochondrial DNA in various salmonid species, and is a member of the Human Anatomy and Physiology Society. When she is not in the classroom or developing digital media, she is climbing, mountaineering, skiing, kayaking, sailing, cycling, and mountain biking throughout the Pacific Northwest.

TABLE OF CONTENTS

Preface viii

PART ONE

Organization of the Body

© Dr. Yorgos Nikas/Science Source

CHAPTER 1

The Study of Human Anatomy **1**
The Scope of Human Anatomy 2
The Human Body Plan 8
The Language of Anatomy 19

CHAPTER 2

Cytology—The Study of Cells **25**
The Study of Cells 26
The Cell Surface 30
The Cell Interior 40
The Cell Life Cycle 47

CHAPTER 3

Histology—The Study of Tissues **53**
The Study of Tissues 54
Epithelial Tissue 56
Connective Tissue 63
Nervous and Muscular Tissue—Excitable Tissues 72
Glands and Membranes 75
Tissue Growth, Development, Repair, and Death 79

CHAPTER 4

Human Development **84**
Gametogenesis and Fertilization 85
Stages of Prenatal Development 87
Clinical Perspectives 100

PART TWO

Support and Movement



© SPL/Science Source

CHAPTER 5

The Integumentary System **108**
The Skin and Subcutaneous Tissue 109
Hair and Nails 116
Cutaneous Glands 120
Developmental and Clinical Perspectives 123

CHAPTER 6

The Skeletal System I: Bone Tissue **131**
Tissues and Organs of the Skeletal System 132
Histology of Osseous Tissue 134
Bone Development 139
Structural Disorders of Bone 145

CHAPTER 7

The Skeletal System II: Axial Skeleton **151**
Overview of the Skeleton 152
The Skull 155
The Vertebral Column and Thoracic Cage 167
Developmental and Clinical Perspectives 176

CHAPTER 8

The Skeletal System III: Appendicular Skeleton **184**
The Pectoral Girdle and Upper Limb 185
The Pelvic Girdle and Lower Limb 190
Developmental and Clinical Perspectives 200

CHAPTER 9

The Skeletal System IV: Joints **205**
Joints and Their Classification 206
Synovial Joints 209
Anatomy of Selected Synovial Joints 220
Clinical Perspectives 230

CHAPTER 10

The Muscular System I: Introduction **235**
Muscle Types and Functions 236
General Anatomy of Muscles 237
Microscopic Anatomy of Skeletal Muscle 244
Relating Structure to Function 250
Cardiac and Smooth Muscle 254
Developmental and Clinical Perspectives 257

CHAPTER 11

The Muscular System II: Axial Musculature **263**
Learning Approaches 264
Muscles of the Head and Neck 268
Muscles of the Trunk 279

CHAPTER 12

The Muscular System III: Appendicular Musculature 293

Muscles Acting on the Shoulder and Upper Limb 294

Muscles Acting on the Hip and Lower Limb 310

Muscle Injuries 324

ATLAS A

Atlas of Regional and Surface Anatomy 329

Introduction 330

The Head and Neck 331

The Trunk 333

The Upper Limb 344

The Lower Limb 346

Test of Muscle Recognition 350

PART THREE

Integration and Control



© David Becker/Science Source

CHAPTER 13

The Nervous System I: Nervous Tissue 351

Overview of the Nervous System 352

Nerve Cells (Neurons) 353

Supportive Cells (Neuroglia) 357

Synapses and Neural Circuits 361

Developmental and Clinical Perspectives 365

CHAPTER 14

The Nervous System II: Spinal Cord and Spinal Nerves 371

The Spinal Cord 372

The Spinal Nerves 379

Somatic Reflexes 391

Clinical Perspectives 393

CHAPTER 15

The Nervous System III: Brain and Cranial Nerves 398

Overview of the Brain 399

The Hindbrain and Midbrain 406

The Forebrain 413

The Cranial Nerves 427

Developmental and Clinical Perspectives 437

CHAPTER 16

The Nervous System IV: Autonomic Nervous System and Visceral Reflexes 442

General Properties of the Autonomic Nervous System 443

Anatomy of the Autonomic Nervous System 446

Autonomic Effects 453

Developmental and Clinical Perspectives 456

CHAPTER 17

The Nervous System V: Sense Organs 460

Receptor Types and the General Senses 461

The Chemical Senses 466

The Ear 470

The Eye 480

Developmental and Clinical Perspectives 491

CHAPTER 18

The Endocrine System 497

Overview of the Endocrine System 498

The Hypothalamus and Pituitary Gland 500

Other Endocrine Glands 504

Developmental and Clinical Perspectives 512

PART FOUR

Maintenance



© Dr. Yorgos Nikas/Science Source

CHAPTER 19

The Circulatory System I: Blood 519

Introduction 520

Erythrocytes 523

Leukocytes 527

Platelets 532

Clinical Perspectives 534

CHAPTER 20

The Circulatory System II: The Heart 539

Overview of the Cardiovascular System 540

Gross Anatomy of the Heart 543

Coronary Circulation 549

The Cardiac Conduction System and Cardiac Muscle 552

Developmental and Clinical Perspectives 557

CHAPTER 21

The Circulatory System III: Blood Vessels 563

General Anatomy of the Blood Vessels 564

The Pulmonary Circuit 572

Systemic Vessels of the Axial Region 573

Systemic Vessels of the Appendicular Region 590

Developmental and Clinical Perspectives 601

CHAPTER 22

The Lymphatic System and Immunity **609**
Lymph and Lymphatic Vessels 610
Lymphatic Cells, Tissues, and Organs 615
The Lymphatic System in Relation to Immunity 623
Developmental and Clinical Perspectives 626

CHAPTER 23

The Respiratory system **631**
Overview of the Respiratory System 632
The Upper Respiratory Tract 633
The Lower Respiratory Tract 637
Neuromuscular Aspects of Respiration 643
Developmental and Clinical Perspectives 647

CHAPTER 24

The Digestive System **653**
Digestive Processes and General Anatomy 654
The Mouth Through Esophagus 658
The Stomach 664
The Small Intestine 667
The Large Intestine 671
Accessory Glands of Digestion 673
Developmental and Clinical Perspectives 678

CHAPTER 25

The Urinary System **684**
Functions of the Urinary System 685
The Kidney 686
The Ureters, Urinary Bladder, and Urethra 695
Developmental and Clinical Perspectives 697

PART FIVE

Reproduction

© Simon Fraser/Science Source

CHAPTER 26

The Reproductive System **703**
Sexual Reproduction 704
The Male Reproductive System 705
The Female Reproductive System 715
Developmental and Clinical Perspectives 727

Appendix A: Answers to Study Guide Questions A-1
Appendix B: Lexicon of Biomedical Word Elements B-1
Glossary G-1
Index I-1

PREFACE

Saladin's *Human Anatomy* goes beyond descriptions of body structure to read as a story that weaves together basic science, clinical applications, the history of medicine, and the evolutionary basis of human structure. Saladin combines this humanistic perspective with vibrant photos and art to convey the beauty and excitement of the subject to beginning students.

New to the Fifth Edition

New Scientific Information

This fifth edition features new and updated scientific content on the limitations and applications of MRI and PET scans (chapter 1); pseudopods and ciliopathies (chapter 2); the pathogenesis of pressure sores (chapter 3); causes of spontaneous abortion (chapter 4); skin grafting with atomized spray-on stem cells (chapter 5); the reemergence of polio due to anti-vaccination politics (chapter 14); and the newly recognized pancreatic hormone amylin (chapter 18).

This edition also offers new functional perspectives on biomechanics of the fingernails (chapter 5) and patella (chapter 8); myoglobin (chapter 10); serratus posterior muscles (chapter 11); linguistic functions of the right cerebral hemisphere (chapter 15); lamellar corpuscles (chapter 17); the trabeculae carneae and papillary muscles of the heart (chapter 20); the spleen (chapter 22); the shape and interfaces between pulmonary alveoli (chapter 23); and oogenesis and folliculogenesis (chapter 26). Chapter 21 offers new Deeper Insight essays on air embolism and central venous catheters.

New Perspectives

This edition follows *Gray's Anatomy* and other leading authorities in dispensing with *origin* and *insertion* terminology for muscle attachments (for reasons explained on page 241). The muscle tables in chapters 11 and 12 now list muscle attachments without calling them by these increasingly obsolete terms. Muscle innervations are also simplified in these tables by citing the major cranial and spinal nerves rather than their finer branches.

This edition updates many other anatomical terms and deletes most eponyms in keeping with the *Terminologia Anatomica.* It deletes or de-emphasizes other commonly held but erroneous beliefs such as lactic acid as a cause of muscle fatigue (chapter 10), discredited stories such as Phineas Gage's brain trauma effects (chapter 15), the long-believed absence of lymphatic vessels from the CNS (chapter 22), and obsolete practices such as gallstone lithotripsy (chapter 24).

New Art and Photography

This edition has more than 90 changes in the art program ranging from fine adjustments in art and labeling to entirely new figures of pseudopods (fig. 2.14), structure of the nucleus (fig. 2.18), and proteasomes (fig. 2.19c). Improvements have been made in depictions of the optic radiation of the brain (fig. 17.30) and intercalated discs of cardiac muscle (fig. 20.14). Color keys to the bones have been added to all of the skull art in chapter 7.

New and better photography will be found in these pages for the cerebral angiogram (fig. 1.3b); fluorescent-stained cytoskeleton (fig. 2.16b); the 20-week fetus in utero (fig. 4.11f); basal cell carcinoma (fig. 5.13a); persons exhibiting spinal osteoporosis (fig. 6.16c), peripheral edema (fig. 22.2); the developmental effect of thalidomide (fig. 4.15); X-ray anatomy of the hand (fig. 8.5c); dissection of the ankle (fig. 9.26b); vascular casts of skeletal muscle and the thyroid gland (figs. 10.13 and 21.2); histology of lymphatic nodules (fig. 22.8); the lung (fig. 23.10); the pituitary and adrenal glands (figs. 18.3 and 18.8); and new electron micrographs of erythrocytes in a capillary (fig. 19.3c), an eosinophil (fig. 19.7), macrophage action (fig. 22.7), gastric pits (fig. 24.12), the renal glomerulus (fig. 25.9), and seminiferous tubules (fig. 26.4).

What Else Is New?

Saladin has added two full-page illustrated summaries of the levels of skeletal muscle structure (table 10.1) and cranial nerve pathways (fig. 15.24), enabling students to step back from the details and see the big picture. Expected Learning Outcomes for each chapter section are now listed by letter (in place of bullet points) for easier reference or assignment by instructors, and are reinforced with Assess Your Learning Outcomes in the Study Guide at the end of each chapter. Feedback from students in his own classroom and e-mails from students worldwide have led Ken to rewrite several passages for economy of words and greater conceptual clarity.

A Storytelling Writing Style

Students and instructors alike cite Saladin's prose style as the number one attraction of this book. Students doing blind comparisons of Ken Saladin's chapters and those of other anatomy books routinely find Saladin clearly written, easy to understand, and a stimulating, interesting read. Saladin's analogy-rich writing enables students to easily visualize abstract concepts in terms of everyday experience.

Such dimensions are more impressive when we scale them up to the size of familiar objects. If the soma of a spinal motor neuron was the size of a tennis ball, its dendrites would form a huge bushy mass that could fill a 30-seat classroom from floor to ceiling. Its axon would be up to a mile long but a little narrower than a garden hose. This is quite a point to ponder. The neuron must assemble molecules and organelles in its "tennis ball" soma and deliver them through its "mile-long garden hose" to the end of the axon.

EVOLUTION OF A STORYTELLER

Ken Saladin's penchant for writing began early. For his 10th-grade biology class, he wrote a 318-page monograph on hydras with 53 original India ink drawings and 10 original photomicrographs. We at McGraw-Hill think of this as Ken's "first book." At a young age, Ken already was developing his technical writing style, research habits, and illustration skills.



Courtesy of Ken Saladin

Ken Saladin's "first book," *Hydra Ecology* (1965)



Courtesy of Ken Saladin

Some of Ken's first pen-and-ink artwork (1965)

Ken in 1964

Ken served as an A&P textbook reviewer and testbank writer for several years and then embarked on his first book for McGraw-Hill in 1993. He published the first edition of *Anatomy & Physiology: The Unity of Form and Function* in 1997 and his first edition of *Human Anatomy* in 2004. The story continues with *Human Anatomy,* fifth edition.


Anatomy & Physiology
THE UNITY OF FORM AND FUNCTION
Kenneth S. Saladin

Ken's first textbook published in 1997


Human Anatomy
FIFTH EDITION
Saladin
Mc Graw Hill Education

The story continues in 2016


Essentials of Anatomy & Physiology
Kenneth S. Saladin
Robin K. McFarland

Essentials book published in 2013

GUIDED TOUR

Instructive Artwork for Visual Learners

Saladin's stunning illustrations and photos entice students who regard themselves as "visual learners."

Vivid Illustrations with rich textures and shading and bold, bright colors bring anatomy to life.


Stroma:
Capsule
Reticular tissue
Trabecula
Cortex
Subcapsular sinus
Lymphatic nodule
Germinal center
Cortical sinuses
Medulla
Medullary sinus
Medullary cord
Afferent lymphatic vessels
Artery and vein
Efferent lymphatic vessel
(a)
Medullary cords
Medullary sinus
Macrophage
Trabecula
Lymphocytes
Reticular fibers
Venule
(b)
Lymphocytes
Reticular fibers
(c)
10 µm

© Francis Leroy, Biocosmos/Science Source

Figure 22.11 **Anatomy of a Lymph Node.** (a) Partially bisected lymph node showing pathway of lymph flow. (b) Detail of the boxed region in part (a). (c) Reticular fiber stroma and immune cells in a medullary sinus (SEM). APR


Lumen of stomach
Epithelium
Gastric pit
Gastric gland
Lamina propria
Lymphatic nodule
Muscularis mucosae
Artery
Vein
Oblique layer of muscle
Circular layer of muscle
Longitudinal layer of muscle
Mucosa
Submucosa
Muscularis externa
Serosa
(a) Stomach wall
Mucous neck cell
Parietal cell
Mucous cell
Chief cell
G cell
(b) Pyloric gland
(c) Gastric gland
(d) Gastric pits

© Steve Gschmeissner/Science Source

Figure 24.12 **Microscopic Anatomy of the Stomach Wall.** (a) A block of tissue showing all layers from the mucosa (top) to the serosa (bottom). (b) A pyloric gland from the inferior end of the stomach. Note the absence of chief cells and relatively few parietal cells. (c) A gastric gland, the most widespread type in the stomach. (d) The opening of several gastric pits into the stomach, surrounded by the rounded apical surfaces of the columnar epithelial cells of the mucosa (SEM). APR

Process Figures relate numbered steps in the art with corresponding numbered text descriptions.


Arachnoid granulation
Superior sagittal sinus
Arachnoid mater
Subarachnoid space
Dura mater
Choroid plexus
Third ventricle
Cerebral aqueduct
Lateral aperture
Fourth ventricle
Median aperture
Central canal of spinal cord
Subarachnoid space of spinal cord
①
②
③
④
⑤
⑥
⑦
⑧

① CSF is secreted by choroid plexus in each lateral ventricle.

② CSF flows through interventricular foramina into third ventricle.

③ Choroid plexus in third ventricle adds more CSF.

④ CSF flows down cerebral aqueduct to fourth ventricle.

⑤ Choroid plexus in fourth ventricle adds more CSF.

⑥ CSF flows out two lateral apertures and one median aperture.

⑦ CSF fills subarachnoid space and bathes external surfaces of brain and spinal cord.

⑧ At arachnoid granulations, CSF is reabsorbed into venous blood of dural venous sinuses.

Figure 15.5 The Flow of Cerebrospinal Fluid.

Orientation Tools, like dissection planes and a compass on the anatomical art, clarify the perspective from which a structure is viewed.


Posterior
Anterior
Muscles:
External abdominal oblique
Internal abdominal oblique
Transverse abdominal
Rectus abdominis
Peritoneum
Rectus sheath
Subcutaneous fat
Linea alba
Skin
Aponeurosis of
Transverse abdominal
Internal abdominal oblique
External abdominal oblique

Figure 11.10 Cross Section of the Anterior Abdominal Wall.

The Psychology of Learning

Having taught human anatomy for 38 years, Saladin knows what works in the classroom and incorporates those approaches into the pedagogy of *Human Anatomy.*

Chapters Organized for Preview and Review

Chapter Outline provides a content preview and facilitates review and study.

Deeper Insights pique the interest of health-science students by showing the clinical relevance of the core science.

Brushing Up reminds students of the relevance of earlier chapters to the one on which they are currently embarking.

Anatomy & Physiology REVEALED® icons indicate which area of this interactive cadaver dissection program corresponds to the chapter topic.



PART FOUR

Red and white blood cells, platelets, and sticky threads of fibrin (SEM)

© Dr. Yorgos Nikas/Science Source

CHAPTER

19

THE CIRCULATORY SYSTEM I

BLOOD

CHAPTER OUTLINE

19.1 Introduction 520
- Functions of the Circulatory System 520
- Components and General Properties of Blood 520
- Blood Plasma 522

19.2 Erythrocytes 523
- Form and Function 523
- Quantity of Erythrocytes 524
- Hemoglobin 524
- The Erythrocyte Life Cycle 524
- Blood Types 525

19.3 Leukocytes 527
- Form and Function 527
- Types of Leukocytes 527
- The Leukocyte Life Cycle 530

19.4 Platelets 532
- Form and Function 532
- Platelet Production 533
- Hemostasis 533

19.5 Clinical Perspectives 534
- Hematology in Old Age 534
- Disorders of the Blood 534

Study Guide 536

DEEPER INSIGHTS

19.1 Bone Marrow and Cord Blood Transplants 526
19.2 The Complete Blood Count 532
19.3 Sickle-Cell Disease 536

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:
- Osmosis (p. 34)
- Red bone marrow (p. 138)
- Erythropoietin (p. 510)

Anatomy & Physiology REVEALED® aprevealed.com

Module 9: Cardiovascular System

Reinforced Learning

Each section is a conceptually unified topic, framed between a pair of learning "bookends"—a set of learning objectives at the beginning and a set of review and self-testing questions at the end. Each section is numbered for easy reference in lecture, assignments, and ancillary materials.

Expected Learning Outcomes give the student a preview of key points to be learned within the next few pages.

Before You Go On prompts the student to pause and spot-check his or her mastery of the previous few pages before progressing to new material.



7.1 Overview of the Skeleton

Expected Learning Outcomes

When you have completed this section, you should be able to

a. define the two subdivisions of the skeleton;
b. state the approximate number of bones in the adult body;
c. explain why this number varies with age and from one person to another; and
d. define several terms that denote surface features of bones.



Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. Name the major components of the axial skeleton. Name those of the appendicular skeleton.
2. Explain why an adult does not have as many bones as a child does. Explain why one adult may have more bones than another adult of the same age.
3. Briefly describe each of the following bone features: condyle, epicondyle, process, tubercle, fossa, sulcus, and foramen.

Vocabulary Building

Several features help build a student's level of comfort with medical vocabulary.

Pronunciation Guides Knowing proper pronunciation is key to remembering and spelling terms. Saladin gives simple, intuitive "pro-NUN-see-AY-shun" guides to help students over this hurdle and widen the student's comfort zone for medical vocabulary.

Word Origins Accurate spelling and insight into medical terms are greatly enhanced by a familiarity with commonly used word roots, prefixes, and suffixes.

Footnotes throughout the chapters help build the student's working lexicon of word elements. An end-of-book Glossary provides clear definitions of the most important or frequently used terms.

Building Your Medical Vocabulary An exercise at the end of each chapter helps students creatively use their knowledge of new medical word elements.



Types of Neuroglia

There are six major categories of neuroglia, each with a unique function (table 13.1). Four types occur only in the central nervous system (fig. 13.6):

1. **Oligodendrocytes**[15] (OL-ih-go-DEN-dro-sites) somewhat resemble an octopus; they have a bulbous body with as many as 15 armlike processes. Each process reaches out to a nerve fiber and spirals around it like electrical tape wrapped repeatedly around a wire. This wrapping, called the *myelin sheath,* insulates the nerve fiber from the extracellular fluid and speeds up signal conduction in the nerve fiber.

[15] *oligo* = few; *dendro* = branches; *cyte* = cell



Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. -ic
2. somato-
3. neuro-
4. lipo-
5. dendro-
6. -ite
7. pseudo-
8. oligo-
9. fer-
10. sclero-

Answers in appendix A

Self-Assessment Tools

Saladin provides students with abundant opportunities to evaluate their comprehension of concepts. A wide variety of questions from simple recall to analytical evaluation cover all six cognitive levels of Bloom's Taxonomy of Educational Objectives.

Before You Go On questions test simple recall and lower-level interpretation of information read in the previous few pages.

Apply What You Know tests a student's ability to think of the deeper implications or clinical applications of a point he or she just read.

Figure Legend Questions posed in many of the figure legends prompt the student to interpret the art and apply it to the reading.



Figure 10.1 **Skeletal Muscle Fibers.**
- *What tissue characteristics evident in this photo distinguish this from cardiac and smooth muscle?* APR



- **The placenta.** This organ performs many functions in pregnancy, including fetal nutrition and waste removal. But it also secretes estrogen, progesterone, and other hormones that regulate pregnancy and stimulate development of the fetus and the mother's mammary glands.

Apply What You Know

Often, two hormones have opposite *(antagonistic)* effects on the same target organs. For example, oxytocin stimulates labor contractions, and progesterone inhibits premature labor. Name some other examples of antagonistic effects among the hormones in this chapter.

You can see that the endocrine system is extensive. It includes numerous discrete glands as well as individual cells in the tissues of other organs. The endocrine organs and tissues other than the hypothalamus and pituitary are reviewed in table 18.3.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

9. Name two endocrine glands that are larger in children than in adults. What are their functions?
10. What hormone increases the body's heat production in cold weather? What other functions does this hormone have?
11. Name the main hormone secreted by each layer of the adrenal cortex and one secreted by the adrenal medulla, and state the function of each.
12. What is the difference between a gonadal hormone and a gonadotropin?
13. What hormones are most important in regulating blood glucose concentration? What cells produce them? Where are these cells found?
14. Name one hormone produced by each of the following organs—the heart, liver, and placenta—and state the function of each hormone.

Testing Your Recall sections at the end of each chapter offer 20 simple recall questions to test retention of terminology and basic ideas.

True or False statements require students not merely to evaluate their truth, but also to concisely explain why the false statements are untrue, or rephrase them in a way that makes them true.

Testing Your Comprehension questions are clinical application and other interpretive essay questions that require the student to apply the chapter's basic science to clinical or other scenarios.



Testing Your Recall

1. The hip bone is attached to the axial skeleton through its
   a. auricular surface.
   b. articular cartilage.
   c. pubic symphysis.
   d. conoid tubercle.
   e. coronoid process.
2. Which of these bones supports the most body weight?
   a. ilium
   b. pubis
   c. femur
   d. tibia
   e. talus
3. Which of these structures can be most easily palpated on a living person?
   a. the deltoid tuberosity
   b. the greater sciatic notch
   c. the medial malleolus
   d. the coracoid process of the scapula
   e. the glenoid cavity
4. Compared to the male pelvis, the pelvis of a female
   a. has a less movable coccyx.
   b. has a rounder pelvic inlet.
   c. is narrower between the iliac crests.
   d. has a narrower pubic arch.
   e. has a narrower sacrum.
5. The lateral and medial malleoli are most similar to
   a. the radial and ulnar styloid processes.
   b. the humeral capitulum and trochlea.
   c. the acromion and coracoid process.
   d. the base and head of a metacarpal bone.
   e. the anterior and posterior superior iliac spines.
6. When you rest your hands on your hips, you are resting them on
   a. the pelvic inlet.
   b. the pelvic outlet.
   c. the pelvic brim.
   d. the iliac crests.
   e. the auricular surfaces.
7. The disc-shaped head of the radius articulates with the _____ of the humerus.
   a. radial tuberosity
   b. trochlea
   c. capitulum
   d. olecranon process
   e. glenoid cavity
8. All of the following are carpal bones *except* the _____, which is a tarsal bone.
   a. trapezium
   b. cuboid
   c. trapezoid
   d. triquetrum
   e. pisiform
9. The bone that supports your body weight when you are sitting down is
   a. the acetabulum.
   b. the pubis.
   c. the ilium.
   d. the coccyx.
   e. the ischium.
10. Which of these is the bone of the heel?
    a. cuboid
    b. calcaneus
    c. navicular
    d. trochlear
    e. talus



True or False

Determine which five of the following statements are false, and briefly explain why.

1. There are more carpal bones than tarsal bones.
2. The hands have more phalanges than the feet.
3. The upper limb is attached to the axial skeleton at only one point, the acromioclavicular joint.
4. On a living person, it would be possible to palpate the muscles in the infraspinous fossa but not those of the subscapular fossa.
5. In strict anatomical terminology, the words *arm* and *leg* both refer to regions with only one bone.
6. If you rest your chin on your hands with your elbows on a table, the olecranon of the ulna rests on the table.
7. The most frequently broken bone in humans is the humerus.
8. The proximal end of the radius articulates with both the humerus and ulna.
9. The pisiform bone and patella are both sesamoid bones.
10. The pelvic outlet is the opening in the floor of the greater pelvis leading into the lesser pelvis.

Answers in appendix A

Testing Your Comprehension

1. In adolescents, trauma sometimes separates the head of the femur from the neck. Why do you think this is more common in adolescents than in adults?
2. By palpating the hind leg of a cat or dog or examining a laboratory skeleton, you can see that cats and dogs stand on the heads of their metatarsal bones; the calcaneus does not touch the ground. How is this similar to the stance of a woman wearing high-heeled shoes? How is it different?
3. A deer hunter discovers a human skeleton in the woods and notifies authorities. A news report on the finding describes it as the body of an unidentified male between 17 and 20 years of age. What skeletal features would have been most useful for determining the sex and approximate age of the individual?
4. A surgeon has removed 8 cm of Joan's radius because of osteosarcoma, a bone cancer, and replaced it with a graft taken from one of the bones of Joan's lower limb. What bone do you think would most likely be used as the source of the graft? Explain your answer.
5. Andy, a 55-year-old, 75 kg (165-pound) roofer, is shingling the steeply pitched roof of a new house when he loses his footing and slides down the roof and over the edge, feet first. He braces himself for the fall, and when he hits the ground, he cries out and doubles up in excruciating pain. Emergency medical technicians called to the scene tell him he has broken his hips. Describe, more specifically, where his fractures most likely occurred. On the way to the hospital, Andy says, "You know it's funny, when I was a kid, I used to jump off roofs that high, and I never got hurt." Why do you think Andy was more at risk of a fracture as an adult than he was as a boy?

DEEPER INSIGHT 7.3

Abnormal Spinal Curvatures

Abnormal spinal curvatures (fig. 7.21) can result from abdominal weight gain in obesity or pregnancy; poor posture; weakness or paralysis of the trunk muscles; some diseases; or congenital defects in vertebral anatomy. The most common deformity is an abnormal lateral curvature called *scoliosis*. It occurs most often in the thoracic region, particularly among adolescent girls. It sometimes results from a developmental abnormality in which the body and arch of a vertebra fail to develop on one side. If the person's skeletal growth is not yet complete, scoliosis can be corrected with a back brace.

An exaggerated thoracic curvature is called *kyphosis* (hunchback, in lay language). It is usually a result of osteoporosis, but it also occurs in people with osteomalacia or spinal tuberculosis and in adolescents who engage heavily in such sports as wrestling and weight lifting. An exaggerated lumbar curvature is called *lordosis* (swayback). It can have the same causes as kyphosis, or it can result from added abdominal weight in pregnancy or obesity.



(a) Scoliosis

(b) Kyphosis ("hunchback")

(c) Lordosis ("swayback")

Figure 7.21 **Abnormal Spinal Curvatures.** (a) Scoliosis, an abnormal lateral deviation. (b) Kyphosis, an exaggerated thoracic curvature common in old age. (c) Lordosis, an exaggerated lumbar curvature common in pregnancy and obesity.

Making it Relevant

Deeper Insight essays cover the clinical application of basic science. Some Deeper Insight boxes highlight medical history and evolutionary interpretations of human structure and function.

McGRAW-HILL EDUCATION TEACHING AND LEARNING TOOLS

McGraw-Hill Education A&P: We Have Learning Down to a Science!

At McGraw-Hill Education, we work every day to unlock the full potential of each learner. Our mission is to accelerate learning through intuitive, engaging, efficient and effective experiences—grounded in research. MHE Anatomy & Physiology is your trusted, data-driven partner in A&P education. Since 2009, our adaptive programs in A&P have hosted 600,000 unique users who have answered more than 600 million probes, giving us the only data-driven solutions to help your students get from their first college-level course to program readiness.

LearnSmart® Prep is an adaptive learning tool that prepares students for college-level work in Anatomy & Physiology. **Prep for Anatomy & Physiology now comes standard to students with Connect.** The tool individually identifies concepts the student does not fully understand and provides learning resources to teach essential concepts so students enter the classroom prepared. Data-driven reports highlight areas where students are struggling, helping to accurately identify weak areas.

Anatomy & Physiology| REVEALED® is now mobile! Also, available in Cat and Fetal Pig versions.


Anatomy & Physiology | REVEALED® 3.0

An Interactive Cadaver Dissection Experience

This unique multimedia tool is designed to help you master human anatomy and physiology with:
- Content customized to your course
- Stunning cadaver specimens
- Vivid animations
- Lab practical quizzing

my Course Content
- Maximize efficiency by studying exactly what's required.
- Your instructor selects the content that's relevant to your course.

Dissection
- Peel layers of the body to reveal structures beneath the surface.

Animation
- Over 150 animations make anatomy and physiology easier to visualize and understand.

Histology
- Study interactive slides that simulate what you see in lab.

Imaging
- Correlate dissected anatomy with X-ray, MRI, and CT scans.

Quiz
- Gauge proficiency with customized quizzes and lab practicals that cover only what you need for your course.

WWW.APREVEALED.COM

Concept Overview Interactives combine multiple concepts into one big-picture summary. These striking, visually dynamic presentations offer a review of previously covered material in a creatively designed environment to emphasize how individual parts fit together in the understanding of a larger mechanism or concept. Concept Overview Interactive modules have assessable, auto-graded learning activities in Connect®, can be used as a self-study tool for students, and are also provided separately to instructors as classroom presentation tools.

SELECT:
SET UP:
SELECT:
SET UP:

Mc Graw Hill Education

connect®

Required=Results



McGraw-Hill Connect® Learn Without Limits

Connect is a teaching and learning platform that is proven to deliver better results for students and instructors.

Connect empowers students by continually adapting to deliver precisely what they need, when they need it, and how they need it, so your class time is more engaging and effective.



Using **Connect** improves passing rates by **10.8%** and retention by **16.4%.**

88% of instructors who use **Connect** require it; instructor satisfaction **increases** by 38% when **Connect** is required.

Analytics



Based on McGraw-Hill Education Connect Effectiveness Study 2013

Connect Insight®

Connect Insight is Connect's new one-of-a-kind visual analytics dashboard—now available for both instructors and students—that provides at-a-glance information regarding student performance, which is immediately actionable. By presenting assignment, assessment, and topical performance results together with a time metric that is easily visible for aggregate or individual results, Connect Insight gives the user the ability to take a just-in-time approach to teaching and learning, which was never before available. Connect Insight presents data that empowers students and helps instructors improve class performance in a way that is efficient and effective.

Students can view their results for any **Connect** course.

Mobile

Connect's new, intuitive mobile interface gives students and instructors flexible and convenient, anytime–anywhere access to all components of the Connect platform.



Adaptive

THE FIRST AND ONLY **ADAPTIVE READING EXPERIENCE** DESIGNED TO TRANSFORM THE WAY STUDENTS READ

More students earn **A's** and **B's** when they use McGraw-Hill Education **Adaptive** products.

SmartBook®

Proven to help students improve grades and study more efficiently, SmartBook contains the same content within the print book, but actively tailors that content to the needs of the individual. SmartBook's adaptive technology provides precise, personalized instruction on what the student should do next, guiding the student to master and remember key concepts, targeting gaps in knowledge and offering customized feedback, driving the student toward comprehension and retention of the subject matter. Available on smartphones and tablets, SmartBook puts learning at the student's fingertips—anywhere, anytime.

Over **4 billion questions** have been answered, making McGraw-Hill Education products more intelligent, reliable, and precise.



95% of students reported **SmartBook** to be a more effective way of reading material

100% of students want to use the Practice Quiz feature available within **SmartBook** to help them study

100% of students reported having reliable access to off-campus wifi

90% of students say they would purchase **SmartBook** over print alone

95% reported that **SmartBook** would impact their study skills in a positive way

*Findings based on a 2015 focus group survey at Pellissippi State Community College administered by McGraw-Hill Education

ACKNOWLEDGMENTS

I wish to thank the hundreds of colleagues who have reviewed my writing over the years and tremendously contributed to the factual accuracy, scientific currency, and presentation style of the book before you. Much of this has come about through revising my flagship book, *Anatomy & Physiology: The Unity of Form and Function,* through seven editions. *Human Anatomy* and my book coauthored with Robin McFarland, *Essentials of Anatomy & Physiology,* have derived their own content improvements as they follow in the wake of the heavily reviewed two-semester textbook.

In addition to commissioned reviews of my chapters, spontaneous feedback from other instructors and from students all over the world has been enormously stimulating and helpful in the incessant effort to approach that elusive asymptote called textbook perfection. I'm deeply appreciative of all the encouragement, information, corrections, and suggestions these readers have sent, and I look forward to many more years of such productive correspondence.

My digital team—Steve Sullivan and Chris Gan—have greatly increased the educational value of these books through their work to create self-assessment tools and align McGraw-Hill's Connect resources with the textbook. This has contributed greatly to student and instructor satisfaction with our overall package of learning media, and to the students' success as they master A&P en route to their career aspirations. I am delighted to have them on my team—all for one, and one for all! Thank you so much for what you do to adapt my product to the needs of our students.

I would also like to extend appreciation to members of the Life Sciences Book Team at McGraw-Hill Education who have worked with me on this project, including Amy Reed, Senior Brand Manager; Chloe Bouxsein, Brand Manager; Donna Nemmers, Senior Product Developer; Vicki Krug, Senior Content Project Manager; Lori Hancock, Senior Content Licensing Specialist; Brent dela Cruz, Senior Content Project Manager; David Hash, Senior Designer Jeanne Patterson, freelance Copyeditor; and Julie De Adder, Photo Researcher. Their efforts have yielded another great edition of the text and its companion media suite of Connect products.

Ken Saladin
Georgia College & State University

LETTER TO STUDENTS

Dear Students,

When I was a young boy, I became interested in what I then called "nature study" for two reasons. One was the sheer beauty of nature. I reveled in children's books with abundant, colorful drawings and photographs of animals, plants, minerals, and gems. It was this esthetic appreciation of nature that made me want to learn more about it and made me happily surprised to discover I could make a career of it. At a slightly later age, another thing that drew me still deeper into biology was to discover writers who had a way with words—who could captivate my imagination and curiosity with their elegant prose. Once I was old enough to hold part-time jobs, I began buying zoology and anatomy books that mesmerized me with their gracefulness of writing and fascinating art and photography. I wanted to write and draw like that myself, and I began learning from "the masters." I spent many late nights in my room peering into my microscope and jars of pond water, typing page after page of manuscript, and trying pen and India ink as an art medium. My "first book" was a 318-page paper on some little pond animals called hydras, with 53 illustrations, that I wrote for my tenth-grade biology class when I was 16 (see p. ix).

Fast forward about 30 years to when I became a textbook writer, and I found myself bringing that same enjoyment of writing and illustrating to my own anatomy and physiology textbooks. Why? Not only for its intrinsic creative satisfaction, but because I'm guessing that you're like I was—you can appreciate a book that does more than simply give you the information you need. You appreciate, I trust, a writer who makes it *enjoyable* for you through scientific, storytelling prose and a conceptualized way of illustrating things to spark interest and facilitate understanding. Some of you probably think of yourselves as "visual learners" and others as "verbal learners." Either way, I hope this book will serve your learning style.

I know from my own students, however, that you need more than captivating illustrations and enjoyable reading. Let's face it—A&P is a complex subject and it may seem a formidable task to acquire even a basic knowledge of the human body. It was difficult even for me to learn (and the learning never ends). So in addition to simply writing this book, I've given a lot of thought to what we call pedagogy—the art of teaching. I've designed my chapters to make them easier for you to study and to give you abundant opportunity to check whether you've understood what you read—to test yourself (as I advise my own students) before the instructor tests you. In later editions, we brought on a team of digital authors to produce online learning aids that students have commended as extremely helpful to them in learning human anatomy.

Each chapter is broken down into short, digestible bits with a set of learning goals (Expected Learning Outcomes) at the beginning of each section, and self-testing questions (Before You Go On) just a few pages later. Even if you have just 30 minutes to read during a lunch break or a bus ride, you can easily read or review one of these brief sections. There are also numerous self-testing questions at the end of each chapter, in some of the figure legends, and the occasional Apply What You Know questions dispersed through each chapter. The questions cover a broad range of cognitive skills, from simple recall of a term to your ability to evaluate, analyze, and apply what you've learned to new clinical situations or other problems.

The Guided Tour on page xii takes you through the learning aids we've created for you within the book itself and additional study aids available within Connect. I hope you will take a little time to look at the Guided Tour to see what we have to offer you. The Preface on page x goes a little deeper into my thinking behind the book's design and content and will also help you get more out of your experience.

I hope you enjoy your study of this book, but I know there are always ways to make it even better. Indeed, what quality you may find in this edition owes a great deal to feedback I've received from students all over the world. If you find any typos or other errors, if you have any suggestions for improvement, if I can clarify a concept for you, or even if you just want to comment on something you really like about the book, I hope you'll feel free to write to me. I correspond quite often with students and would enjoy hearing from you.

DEDICATION

This book is
dedicated to
my son Emory.

Ken Saladin
Georgia College & State University
Milledgeville, GA 31061 (USA)
ken.saladin@gcsu.edu

A new life begins—a human embryo on the point of a pin (scanning electron micrograph)

© Dr. Yorgos Nikas/Science Source

PART ONE

CHAPTER 1

THE STUDY OF HUMAN ANATOMY

CHAPTER OUTLINE

1.1 The Scope of Human Anatomy 2
- The Anatomical Sciences 2
- Methods of Study 3
- Variation in Human Structure 6

1.2 The Human Body Plan 8
- Levels of Human Structure 8
- The Human Organ Systems 9
- The Terminology of Body Orientation 9
- Major Body Regions 13
- Body Cavities and Membranes 16

1.3 The Language of Anatomy 19
- The Origins of Medical Terms 20
- Analyzing Medical Terms 20
- Variant Forms of Medical Terms 21
- The Importance of Precision 22

Study Guide 22

DEEPER INSIGHTS

1.1 Situs Inversus and Other Unusual Anatomy 6
1.2 Cardiac Tamponade 17
1.3 Obscure Word Origins 21

Anatomy & Physiology REVEALED®
aprevealed.com

Module 1: Body Orientation

This book is an introduction to the structure of the human body. It is meant primarily to provide a foundation for advanced study in fields related to health and fitness. Beyond that purpose, however, the study of anatomy can also provide a satisfying sense of self-understanding. Even as children, we are curious about what's inside the body. Dried skeletons, museum exhibits, and beautifully illustrated atlases of the body have long elicited widespread public fascination.

This chapter lays a foundation for our study of anatomy by considering some broad themes. We will consider what this science encompasses and what methods are used for the study of anatomy. We will lay out a general "road map" of the human body to provide a context for the chapters that follow. We will also get some insights into how a beginning anatomy student can become comfortable with medical terminology.

1.1 The Scope of Human Anatomy

Expected Learning Outcomes

When you have completed this section, you should be able to

a. define *anatomy* and some of its subdisciplines;
b. name and describe some approaches to studying anatomy;
c. describe some methods of medical imaging; and
d. discuss the variability of human anatomy.

Human anatomy is the study of the structural basis of body function. It provides an essential foundation for understanding **physiology,** the study of the functional relevance of that structure; anatomy and physiology together are the bedrock of the health sciences. You can study human anatomy from an atlas; yet as beautiful, fascinating, and valuable as atlases are, they teach almost nothing but the locations, shapes, and names of things. This book is different; it deals with what biologists call **functional morphology**[1]—not just the structure of organs, but the functional reasons behind it.

Anatomy and physiology complement each other; each makes sense of the other, and each molds the other in the course of human development and evolution. We cannot delve into the details of physiology in this book, but enough will be said of function to help you make sense of human structure and to more deeply appreciate the beauty of human form.

The Anatomical Sciences

Anatomy is an ancient human interest, undoubtedly older than any written language we know. We can only guess when people began deliberately cutting into human bodies out of curiosity, simply to know what was inside. Some of the earliest and most influential books of anatomy were written by the Greek philosopher Aristotle (384–322 BCE), the Greek physician Galen (129–c. 199 CE), and the Persian physician Avicenna (Ibn Sina, 980–1037 CE). For nearly 1,500 years, medical professors in Europe idolized these "ancient masters" and considered their works above reproach. Modern human anatomy, however, dates to the sixteenth century, when Flemish physician and professor Andreas Vesalius (1514–64) questioned the accuracy of the earlier authorities and commissioned the first accurate anatomical illustrations for his book, *De Humani Corporis Fabrica* (*On the Structure of the Human Body,* 1543) (fig. 1.1). The tradition begun by Vesalius has been handed down to us through such famous contemporary works as *Gray's Anatomy,* Frank Netter's *Atlas of Human Anatomy,* and many others, to the richly illustrated textbooks used by college students today.

For all its attention to the deceased body, or **cadaver,**[2] human anatomy is hardly a "dead science." New techniques of study continually produce exciting new insights into human structure and its functional relevance; anatomists have discovered far more about the human body in the last century than in the 2,500 years before. Anatomy now embraces several subdisciplines that study human structure from different perspectives. **Gross anatomy** is the study of structure visible to the naked eye, using methods such as surface observation, dissection, X-rays, and MRI scans. **Surface anatomy** is the external structure of the body, and is especially important in conducting a physical examination of a patient. **Radiologic anatomy** is the study of internal structure, using X-rays and other medical imaging techniques described in the next section.

Systemic anatomy is the study of one organ system at a time and is the approach taken by most introductory textbooks such as this one. **Regional anatomy** is the study of multiple organ systems at once in a given region of the body, such as the head or chest. (See the Atlas of Regional and Surface Anatomy on p. 329.) Medical schools and anatomy atlases typically teach anatomy from a regional perspective, because it is more practical to dissect all structures of the head and neck, the chest, or a limb, than it would be to try to dissect the entire digestive system, then the cardiovascular system, and so forth. Dissecting one system almost invariably destroys organs of other systems that stand in the way. Furthermore, as surgeons operate on a particular area of the body, they must think from a regional perspective and attend to the interrelationships of all structures in that area.

Ultimately, the structure and function of the body result from its individual cells. To see those, we usually take tissue specimens, thinly slice and stain them, and observe them under the microscope. This approach is called **histology (microscopic anatomy). Histopathology**[3] is the microscopic examination of tissues for signs of disease. **Cytology**[4] is the study of the structure and function of individual cells.

Anatomy, of course, is not limited to the study of humans, but extends to all living organisms. Even students of human structure

---

[1] *morpho* = form, structure; *logy* = study of

[2] from *cadere* = to fall down or die

[3] *histo* = *tissue*; *patho* = disease; *logy* = study of

[4] *cyto* = cell; *logy* = study of



Wellcome Library, London

© SPL/Science Source

Figure 1.1 **Evolution of Medical Art.** Two illustrations of the skeletal system made about 500 years apart. (a) From an eleventh-century work attributed to Persian physician Avicenna. (b) From *De Humani Corporis Fabrica* (1543) by Andreas Vesalius.

benefit from **comparative anatomy**—the study of more than one species in order to examine structural similarities and differences and analyze evolutionary trends. Anatomy students often begin by dissecting other animals with which we share a common ancestry and many structural similarities. Indeed, many of the reasons for human structure become apparent only when we look at the structure of other animals. In chapter 25, for example, you will see that physiologists had little idea of the purpose of certain tubular loops in the kidney *(nephron loops)* until they compared human kidneys with those of desert and aquatic animals, which have greater and lesser needs to conserve water. The greater an animal's need to conserve water (the drier its habitat), the longer these loops are. Thus, comparative anatomy hinted at the function of the nephron loop, which could then be confirmed through experimental physiology. Such are the insights that can be gained by comparing different species with each other.

Methods of Study

There are several ways to examine the structure of the human body. The simplest is **inspection**—simply looking at the body's appearance in careful detail, as in performing a physical examination or making a clinical diagnosis from surface appearance. Observations of the skin and nails, for example, can provide clues to such underlying problems as vitamin deficiencies, anemia, heart disease, and liver disease. Physical examinations involve not only looking at the body for signs of normalcy or disease, but also touching and listening to it. **Palpation**[5] means feeling a structure with the hands, such as palpating a swollen lymph node or taking a pulse. **Auscultation**[6] (AWS-cul-TAY-shun) is listening to the natural sounds made by the

---

[5] *palp* = touch, feel; *ation* = process

[6] *auscult* = listen; *ation* = process

National Library of Medicine

Figure 1.2 Early Medical Students in the Gross Anatomy Laboratory with Three Cadavers.

body, such as heart and lung sounds. In **percussion,** the examiner taps on the body, feels for abnormal resistance, and listens to the emitted sound for signs of abnormalities such as pockets of fluid, air, or scar tissue.

A deeper understanding of the body depends on **dissection** (dis-SEC-shun)—the careful cutting and separation of tissues to reveal their relationships. The very words *anatomy*[7] and *dissection*[8] both mean "cutting apart"; until the nineteenth century, dissection was called "anatomizing." In many schools of health science, cadaver dissection is one of the first steps in the training of students (fig. 1.2).

Dissection, of course, is not the method of choice when studying a living person! Not long ago, it was common to diagnose disorders through **exploratory surgery**—opening the body and taking a look inside to see what was wrong and what could be done about it. Any breach of the body cavities is risky, however, and most exploratory surgery has now been replaced by **medical imaging** techniques—methods of viewing the inside of the body without surgery (fig. 1.3). The branch of medicine concerned with imaging is called **radiology.** Anatomy learned in this way is called **radiologic anatomy,** and those who use radiologic methods for clinical purposes include **radiologists** and **radiologic technicians.**

Some radiologic methods involve high-energy **ionizing radiation** such as X-rays or particles called positrons. These penetrate the tissues and can be used to produce images on X-ray film or through electronic detectors. The benefits of ionizing radiation must always be weighed against its risks. It is called *ionizing* because it ejects electrons from the atoms and molecules it strikes. This effect can cause mutation and trigger cancer. Thus, ionizing radiation cannot be used indiscriminately. Used judiciously, however, the benefits of a mammogram or dental X-ray substantially outweigh the small risk.

Some of the imaging methods to follow are considered *noninvasive* because they do not involve any penetration of the skin or body orifices. *Invasive* imaging techniques may entail inserting ultrasound probes into the esophagus, vagina, or rectum to get closer to the organ to be imaged, or injecting substances into the bloodstream or body passages to enhance image formation.

Any anatomy student today must be acquainted with the basic techniques of radiology and their respective advantages and limitations. Many of the images printed in this book have been produced by the following techniques.

Radiography

Radiography, first performed in 1895, is the process of photographing internal structures with X-rays. Until the 1960s, this was the only widely available imaging method; even today, it accounts for more than 50% of all clinical imaging. X-rays pass through the soft tissues of the body to a photographic film or detector on the other side, where they produce relatively dark images. They are absorbed, however, by dense tissues such as bones, teeth, tumors, and tuberculosis nodules, which leave the image lighter in these areas (fig. 1.3a). The term *X-ray* also applies to a photograph *(radiograph)* made by this method. Radiography is commonly used in dentistry, mammography, diagnosis of fractures, and examination of the chest. Hollow organs can be visualized by filling them with a *radiopaque* substance that absorbs X-rays. Barium sulfate, for example, is given orally for examination of the esophagus, stomach, and small intestine, or by enema for examination of the large intestine. Other substances are given by injection for *angiography,* the examination of blood vessels (fig. 1.3b). Some disadvantages of radiography are that images of overlapping organs can be confusing and slight differences in tissue density are not easily detected. In addition, X-rays present the aforementioned risks of ionizing radiation.

Computed Tomography

Computed tomography (a **CT scan**) is a more sophisticated application of X-rays. The patient is moved through a ring-shaped machine that emits low-intensity X-rays on one side and receives them with a detector on the opposite side. A computer analyzes signals from the detector and produces an image of a "slice" of the body about as thin as a coin (fig. 1.3c). The computer can "stack" a series of these images to construct a three-dimensional image of the body. CT scanning has the advantage of imaging thin sections of the body, so there is little organ overlap and the image is much sharper than a conventional X-ray. It requires extensive knowledge of cross-sectional anatomy to interpret the images. CT scanning is useful for identifying tumors, aneurysms, cerebral hemorrhages, kidney stones, and other abnormalities.

Magnetic Resonance Imaging

Magnetic resonance imaging (MRI) was conceived as a technique superior to CT for visualizing soft tissues (fig. 1.3d). The patient lies in a chamber surrounded by a large electromagnet that creates a very strong magnetic field. Hydrogen atoms in the tissues align themselves with the field. The technologist then activates a

---

[7] *ana* = apart; *tom* = cut
[8] *dis* = apart; *sect* = cut



© UHB Trust/Getty Images

© Zephyr/Science Source

© Miriam Maslo/Science Source

(a) X-ray (radiograph)

(b) Cerebral angiogram

(c) Computed tomographic (CT) scan



© UHB Trust/Getty Images

© ISM/Phototake

(d) Magnetic resonance image (MRI)

(e) Positron emission tomographic (PET) scan

Figure 1.3 Radiologic Images of the Head. (a) X-ray (radiograph) showing the bones and teeth. (b) An angiogram of the cerebral blood vessels. (c) A CT scan at the level of the eyes. (d) An MRI scan at the level of the eyes. The optic nerves appear in red and the muscles that move the eyes appear in green. (e) A PET scan of the brain of an unmedicated schizophrenic patient. Red areas indicate regions of high metabolic rate. In this patient, the visual center of the brain at the rear of the head (bottom of photo) was especially active during the scan.

- *What structures are seen better by MRI than by X-ray? What structures are seen better by X-ray than by PET?*

radio wave emitter, causing the hydrogen atoms to absorb additional energy and align in a different direction. When the radio waves are turned off, the hydrogen atoms abruptly realign to the magnetic field, giving off their excess energy at rates that depend on the type of tissue. A computer analyzes the emitted energy to produce an image of the body. MRI can "see" clearly through the skull and vertebral column to produce images of the nervous tissue. Moreover, it is better than CT for distinguishing between soft tissues such as the white and gray matter of the brain. It also avoids the harmful effects of X-rays. A disadvantage of MRI is that the patient must lie completely still in the enclosed space for about 45 minutes to scan one region of the body, and a complete procedure may entail 90 minutes to scan multiple regions such as the abdominal and pelvic cavities. Some patients find they cannot do this. MRI is also not very suitable for gastrointestinal imaging because it requires long exposures and the stomach and intestines move too much to create a sharp image. *Functional MRI (fMRI)* is a form of MRI that visualizes moment-to-moment changes in tissue function; fMRI scans of the brain, for example, show shifting patterns of activity as the brain applies itself to a specific sensory, mental, or motor task.

Apply What You Know

The concept of MRI was conceived in 1948 but could not be put into clinical practice until the 1970s. Speculate on a possible reason for this delay.

Positron Emission Tomography

Positron emission tomography (the **PET scan**) is used to assess the metabolic state of a tissue and to distinguish which tissues are most active at a given moment (fig. 1.3e). The procedure begins with an injection of radioactively labeled glucose, which emits positrons (electron-like particles with a positive charge). When a positron and electron meet, they annihilate each other and give off gamma rays that can be detected by sensors and processed by computer. The result is a color image that shows which tissues were using the most glucose. In cardiology, PET scans can show the extent of tissue death from a heart attack. Since damaged tissue consumes little or no glucose, it appears dark. In neuroscience, PET scans can similarly reveal the extent of brain damage from stroke or trauma. PET scans are also widely used to diagnose cancer and evaluate tumor status. The PET scan is an example of **nuclear medicine**—the use of radioisotopes to treat disease or to form diagnostic images of the body.

Sonography

Sonography[9] is the second oldest and second most widely used method of imaging. A handheld device pressed against the skin emits high-frequency ultrasound waves and receives the signals reflected back from internal organs. Sonography avoids the harmful effects of X-rays, and the equipment is relatively inexpensive and portable. Its primary disadvantage is that it does not produce a very sharp image. Although sonography was first used medically in the 1950s, images of significant clinical value had to wait until computer technology had developed enough to analyze differences in the way tissues reflect ultrasound. Sonography is not very useful for examining bones or lungs, but it is the method of choice in obstetrics, where the image *(sonogram)* can be used to locate the placenta and evaluate fetal age, position, and development (fig. 1.4). Sonography can also be used to view tissues in motion, such as fetal movements, a beating heart, and blood ejection from the heart. Sonographic imaging of the beating heart is called *echocardiography.*

Variation in Human Structure

A quick look around any classroom is enough to show that no two humans look exactly alike; on close inspection, even identical twins exhibit differences. Anatomy atlases and textbooks can easily give you the impression that everyone's internal anatomy is the same, but this simply is not true. Books such as this one can teach you only the most common structure—the anatomy seen in approximately 70% or more of people. Someone who thinks that all human bodies are the same internally would make a very confused medical student or an incompetent surgeon.

Some people completely lack certain organs. For example, most of us have a *palmaris longus* muscle in the forearm and a *plantaris* muscle in the leg, but not everyone. Most of us have five lumbar vertebrae (bones of the lower spine), but some have four and some have six. Most of us have one spleen, but some people have two. Most have two kidneys, but some have only one. Most kidneys are supplied by a single *renal artery* and drained by one *ureter,* but in some people, a single kidney has two renal arteries or ureters. Figure 1.5 shows some common variations in human anatomy, and Deeper Insight 1.1 describes a particularly dramatic variation.



© Alexander Tsiaras/Science Source

© Ken Saladin

Figure 1.4 Fetal Sonography. This three-dimensional fetal image was made at 32 weeks of gestation.
• *Why is sonography safer for the fetus than radiography or computed tomography?*

DEEPER INSIGHT 1.1

Situs Inversus and Other Unusual Anatomy

In most people, the heart tilts toward the left, the spleen and sigmoid colon are on the left, the liver and gallbladder lie mainly on the right, the appendix is on the right, and so forth. This normal arrangement of the viscera is called *situs* (SITE-us) *solitus*. About 1 in 8,000 people is born, however, with a striking developmental abnormality called *situs inversus*—the organs of the thoracic and abdominal cavities are reversed between right and left. A selective left–right reversal of the heart is called *dextrocardia*. In *situs perversus*, a single organ occupies an atypical position, not necessarily a left–right reversal—for example, a kidney located low in the pelvic cavity instead of high in the abdominal cavity.

Some conditions, such as dextrocardia in the absence of complete situs inversus, can cause serious medical problems. Complete situs inversus, however, usually causes no functional problems because all of the viscera, though reversed, maintain their normal relationships to each other. Situs inversus is often diagnosed prenatally by sonography, but many people remain unaware of their condition for several decades until it is discovered by medical imaging, on physical examination, or in surgery. However, you can easily imagine the importance of such conditions in diagnosing appendicitis, performing gallbladder surgery, interpreting an X-ray, auscultating the heart valves, or recording an electrocardiogram.

---

[9] *sono* = sound; *graphy* = recording process



Pelvic kidney

Horseshoe kidney



Variations in branches of the aorta

Figure 1.5 Variations in Anatomy of the Kidneys and Major Arteries near the Heart.

Apply What You Know

People who are allergic to penicillin or aspirin often wear Medic Alert bracelets or necklaces that note this fact in case they need emergency medical treatment and are unable to communicate. Why would it be important for a person with situs inversus to have this noted on a Medic Alert bracelet?

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. How does functional morphology differ from the sort of anatomy taught by a photographic atlas of the body?
2. Why would regional anatomy be a better learning approach than systemic anatomy for a cadaver dissection course?
3. What is the difference between radiology and radiography?
4. What are some reasons that sonography would be unsuitable for examining the size and location of a brain tumor?

1.2 The Human Body Plan

Expected Learning Outcomes

When you have completed this section, you should be able to

a. list in proper order the levels of structural complexity of the body, from organism to atoms;
b. name the human organ systems and state the basic functions and components of each;
c. describe anatomical position and explain why it is important in medical language;
d. identify the three fundamental anatomical planes of the body;
e. define several terms that describe the locations of structures relative to each other;
f. identify the major body regions and their subdivisions;
g. name and describe the body cavities and the membranes that line them; and
h. explain what a potential space is, and give some examples.

The chapters that follow assume a certain core, common language of human structure. You will need to know what we mean by the names for the major body cavities and regions, know the difference between a tissue and an organ, and know where to look if you read that structure X is distal or medial to structure Y, for example. This section introduces this core terminology.

Levels of Human Structure

Although this book is concerned mainly with gross anatomy, the study of human structure spans all levels from the whole organism down to the atomic level. Consider for a moment an analogy to human structure: The English language, like the human body, is very complex, yet an endless array of ideas can be conveyed with a limited number of words. All words in the English language are, in turn, composed of various combinations of just 26 letters. Between the alphabet and a book are successively more complex levels of organization: syllables, words, sentences, paragraphs, and chapters. Humans have an analogous hierarchy of complexity (fig. 1.6), as follows:

The organism is composed of organ systems,
organ systems are composed of organs,
organs are composed of tissues,
tissues are composed of cells,
cells are composed (in part) of organelles,
organelles are composed of molecules, and
molecules are composed of atoms.

The **organism** is a single, complete individual, capable of acting separately from other individuals.



Figure 1.6 **The Body's Structural Hierarchy from the Level of Organism to Atom.** Each level depends on the structure and function of the level below it.

An **organ system** is a group of organs that carries out a basic function of the organism such as circulation, respiration, or digestion. The human body has 11 organ systems, defined and illustrated in the next section. Usually, the organs of a system are physically interconnected, such as the kidneys, ureters, urinary bladder, and urethra that compose the urinary system. The endocrine system, however, is a group of hormone-secreting glands and tissues that, for the most part, have no physical connection to each other.

An **organ** is any structure that has definite anatomical boundaries, is visually distinguishable from adjacent organs, and is composed of two or more tissue types working together to carry out a particular function. Most organs and higher levels of structure are within the domain of gross anatomy. However, there are organs within organs—the large organs visible to the naked eye contain smaller organs, some of which are visible only with the microscope. The skin, for example, is the body's largest organ. Included within it are thousands of smaller organs: Each hair follicle, nail, sweat gland, nerve, and blood vessel of the skin is an organ in itself.

A **tissue** is a mass of similar cells and cell products that forms a discrete region of an organ and performs a specific function. The body is composed of only four primary classes of tissue—epithelial, connective, nervous, and muscular tissue. *Histology,* the study of tissues, is the subject of chapter 3.

Cells are the smallest units of an organism considered to be alive. A cell is enclosed in a *plasma membrane* composed of lipids and protein, and it usually has one nucleus, an organelle that contains most of its DNA. *Cytology,* the study of cells and organelles, is the subject of chapter 2.

Organelles[10] are microscopic structures in a cell that carry out its individual functions, much like organs such as the heart, liver, and kidneys carry out individual functions of the whole body. Organelles include the nucleus, mitochondria, lysosomes, centrioles, and others.

Organelles and other cellular components are composed of **molecules**—particles of at least two **atoms** joined by chemical bonds. The largest molecules, such as proteins, fats, and DNA, are called *macromolecules.*

The Human Organ Systems

As remarked earlier, human structure can be learned from the perspective of regional anatomy or systemic anatomy. This book takes the systemic approach, in which we will fully examine one organ system at a time. There are 11 organ systems in the human body, as well as an *immune system,* which is better described as a population of cells that inhabit multiple organs rather than as an organ system. The organ systems are illustrated and summarized in figure 1.7 in the order that they are covered by this book. They are classified in the following list by their principal functions, although this is an unavoidably flawed classification. Some organs belong to two or more systems—for example, the male urethra is part of both the urinary and reproductive systems; the pharynx is part of the digestive and respiratory systems; and the mammary glands belong to both the integumentary and female reproductive systems.

Systems of Protection, Support, and Movement

- Integumentary system
- Skeletal system
- Muscular system

Systems of Internal Communication and Integration

- Nervous system
- Endocrine system

Systems of Fluid Transport

- Circulatory system
- Lymphatic system

Systems of Intake and Output

- Respiratory system
- Digestive system
- Urinary system

Systems of Reproduction

- Male reproductive system
- Female reproductive system

Some medical terms combine the names of two functionally related systems—for example, the *musculoskeletal system, cardiopulmonary system,* and *urogenital (genitourinary) system.* Such terms serve to call attention to the close anatomical or physiological relationship between two systems, but these are not literally individual organ systems.

The Terminology of Body Orientation

When anatomists describe the body, they must indicate where one structure is relative to another, the direction in which a nerve or blood vessel travels, the directions in which body parts move, and so forth. Clear communication on such points requires a universal terminology and frame of reference.

Anatomical Position

In describing the human body, anatomists assume that it is in **anatomical position**—that of a person standing upright with the feet flat on the floor and close together, arms at the sides, and the palms and face directed forward (fig. 1.8). Without such a frame of reference, to say that a structure such as the sternum, thymus, or aorta is "above the heart" would be vague, since it would depend on whether the subject was standing, lying face down, or lying face up. From the perspective of anatomical position, however, we can describe the thyroid gland as *superior* to the heart, the sternum as *anterior (ventral)* to it, and the aorta as *posterior (dorsal)* to it. These descriptions remain valid regardless of the subject's position. Even if the body is lying down, such as a cadaver on the medical student's dissection table, to say that the sternum is anterior to the heart invites the viewer to imagine the body standing in anatomical position and not to call it "above the heart" simply because that is the way the body happens to be lying.

Unless stated otherwise, assume that all anatomical descriptions refer to anatomical position. Bear in mind that if a subject is facing you in anatomical position, the subject's left will be on your right and vice versa. In most anatomical illustrations, for example, the left atrium of the heart appears toward the right side of the page, and although the appendix is located in the right lower quadrant of the abdomen, it appears on the left side of most illustrations.

The forearm is said to be **supinated** when the palms face up or anteriorly and **pronated** when they face down or posteriorly (see fig. 9.13, p. 217); in anatomical position, the forearm is supinated. The words *prone* and *supine* seem similar to these but have an entirely different meaning. A person is **prone** if lying face down, and **supine** if lying face up.

---

[10] *elle* = little



Principal organs:
Skin, hair, nails, cutaneous glands

Principal functions:
Protection, water retention, thermoregulation, vitamin D synthesis, cutaneous sensation, nonverbal communication

Integumentary system

Principal organs:
Bones, cartilages, ligaments

Principal functions:
Support, movement, protective enclosure of viscera, blood formation, mineral storage, electrolyte and acid–base balance

Skeletal system

Principal organs:
Skeletal muscles

Principal functions:
Movement, stability, communication, control of body openings, heat production

Muscular system

Principal organs:
Lymph nodes, lymphatic vessels, thymus, spleen, tonsils

Principal functions:
Recovery of excess tissue fluid, detection of pathogens, production of immune cells, defense against disease

(a) **Lymphatic system**

Principal organs:
Nose, pharynx, larynx, trachea, bronchi, lungs

Principal functions:
Absorption of oxygen, discharge of carbon dioxide, acid–base balance, speech

Respiratory system

Principal organs:
Kidneys, ureters, urinary bladder, urethra

Principal functions:
Elimination of wastes; regulation of blood volume and pressure; stimulation of red blood cell formation; control of fluid, electrolyte, and acid–base balance; detoxification

Urinary system

Figure 1.7 The 11 Human Organ Systems.



Principal organs:
Brain, spinal cord, nerves, ganglia

Principal functions:
Rapid internal communication, coordination, motor control and sensation

Nervous system

Principal organs:
Pituitary gland, pineal gland, thyroid gland, parathyroid glands, thymus, adrenal glands, pancreas, testes, ovaries

Principal functions:
Hormone production; internal chemical communication and coordination

Endocrine system

Principal organs:
Heart, blood vessels

Principal functions:
Distribution of nutrients, oxygen, wastes, hormones, electrolytes, heat, immune cells, and antibodies; fluid, electrolyte, and acid–base balance

Circulatory system

Principal organs:
Teeth, tongue, salivary glands, esophagus, stomach, small and large intestines, liver, gallbladder, pancreas

Principal functions:
Nutrient breakdown and absorption. Liver functions include metabolism of carbohydrates, lipids, proteins, vitamins, and minerals; synthesis of plasma proteins; disposal of drugs, toxins, and hormones; and cleansing of blood.

(b) Digestive system

Principal organs:
Testes, epididymides, spermatic ducts, seminal vesicles, prostate gland, bulbourethral glands, penis

Principal functions:
Production and delivery of sperm; secretion of sex hormones

Male reproductive system

Principal organs:
Ovaries, uterine tubes, uterus, vagina, mammary glands

Principal functions:
Production of eggs; site of fertilization and fetal development; fetal nourishment; birth; lactation; secretion of sex hormones

Female reproductive system



© McGraw-Hill Education/Joe De Grandis, photographer

Figure 1.8 **A Person Standing in Anatomical Position and Bisected Along the Three Principal Planes of Reference.**
- *What is another name for the specific sagittal plane shown here?*

Anatomical Planes

Many views of the body are based on real or imaginary "slices" called sections or planes. *Section* implies an actual cut or slice to reveal internal anatomy, whereas *plane* implies an imaginary flat surface passing through the body. The three major anatomical planes are *sagittal, frontal,* and *transverse* (fig. 1.8).

A **sagittal**[11] (SADJ-ih-tul) **plane** extends vertically and divides the body or an organ into right and left portions. The **median (midsagittal) plane** passes through the midline of the body and divides it into *equal* right and left halves. Other sagittal planes parallel to this (off center), called **parasagittal**[12] **planes,** divide the body into unequal right and left portions. The head and pelvic organs are commonly illustrated on the median plane (fig. 1.9a).

A **frontal (coronal**[13]**) plane** also extends vertically, but it is perpendicular to the sagittal plane and divides the body into anterior (front) and posterior (back) portions. A frontal section of the head, for example, would divide it into one portion bearing the face and another bearing the back of the head. Contents of the thoracic and abdominal cavities are commonly shown in frontal section (fig. 1.9b).

A **transverse (horizontal) plane** passes across the body or an organ perpendicular to its long axis (fig. 1.9c); it divides the body into superior (upper) and inferior (lower) portions. CT scans are typically transverse sections (see fig. 1.3c), but not always.

Directional Terms

In "navigating" the human body and describing the locations of structures, anatomists use a set of standard **directional terms** (table 1.1). You will need to be very familiar with these in order to understand anatomical descriptions later in this book. The terms assume that the body is in anatomical position.

Most of these terms exist in pairs with opposite meanings: *anterior* versus *posterior, superior* versus *inferior, medial* versus *lateral, proximal* versus *distal,* and *superficial* versus *deep.* Intermediate directions are often indicated by combinations of these terms. For example, one structure may be described as *anterolateral* to another (toward the front and side).

The terms *proximal* and *distal* are used especially in the anatomy of the limbs, with *proximal* used to denote something relatively close to the limb's point of attachment (the shoulder or hip joint) and *distal* to denote something farther away. These terms do have some

---

[11] *sagitta* = arrow
[12] *para* = next to
[13] *corona* = crown; *al* = like



(a) Sagittal section **(b) Frontal section** **(c) Transverse section**

Figure 1.9 **Sections of the Body in the Three Primary Anatomical Planes.** (a) Sagittal section of the pelvic region. (b) Frontal section of the thoracic region. (c) Transverse section of the head at the level of the eyes.

TABLE 1.1 Directional Terms in Human Anatomy

Term	Meaning	Examples of Usage
Anterior	Toward the front of the body	The sternum is *anterior* to the heart.
Posterior	Toward the back of the body	The esophagus is *posterior* to the trachea.
Ventral	Toward the anterior side*	The abdomen is the *ventral* side of the body.
Dorsal	Toward the posterior side*	The scapulae are *dorsal* to the rib cage.
Superior	Above	The heart is *superior* to the diaphragm.
Inferior	Below	The liver is *inferior* to the diaphragm.
Cephalic	Toward the head or superior end	The *cephalic* end of the embryonic neural tube develops into the brain.
Rostral	Toward the forehead or nose	The forebrain is *rostral* to the brainstem.
Caudal	Toward the tail or inferior end	The spinal cord is *caudal* to the brain.
Medial	Toward the midline of the body	The heart is *medial* to the lungs.
Lateral	Away from the midline of the body	The eyes are *lateral* to the nose.
Proximal	Closer to the point of attachment or origin	The elbow is *proximal* to the wrist.
Distal	Farther from the point of attachment or origin	The fingernails are at the *distal* ends of the fingers.
Ipsilateral	On the same side of the body (right or left)	The liver is *ipsilateral* to the appendix.
Contralateral	On opposite sides of the body (right and left)	The spleen is *contralateral* to the liver.
Superficial	Closer to the body surface	The skin is *superficial* to the muscles.
Deep	Farther from the body surface	The bones are *deep* to the muscles.

*In humans only; definition differs for other animals. In human anatomy, *anterior* and *posterior* are usually used in place of *ventral* and *dorsal*.

applications to anatomy of the trunk of the body—for example, in referring to certain aspects of the intestines and the microscopic structure of the kidneys. But when describing the trunk and referring to a structure that lies above or below another in anatomical position, *superior* and *inferior* are the preferred terms. These terms are not usually used for the limbs. Although it may be technically correct, one would not generally say the elbow is superior to the wrist. Rather, it is proximal to the wrist.

Because of the bipedal, upright stance of humans, some directional terms have different meanings for humans than they do for other animals. *Anterior,* for example, denotes the region of the body that leads the way in normal locomotion. For a four-legged animal such as a cat, this is the head end of the body; for a human, however, it is the front of the chest and abdomen. What we call *anterior* in a human would be called *ventral* in a cat. *Posterior* denotes the region that comes last in normal locomotion—the tail end of a cat but the back of a human. In the anatomy of most other animals, *ventral* denotes the surface of the body closest to the ground and *dorsal* denotes the surface farthest away from the ground. These two words are too entrenched in human anatomy to completely ignore them, but we will minimize their use in this book to avoid confusion. You must keep such differences in mind, however, when dissecting other animals for comparison to human anatomy.

One vestige of the term *dorsal* is **dorsum,** used to denote the upper surface of the foot and the back of the hand. If you consider how a quadrupedal animal stands, the corresponding surfaces of its paws are both uppermost, facing the same direction as the dorsal side of its trunk. Although these surfaces of the human hand and foot face entirely different directions in anatomical position, the term *dorsum* is still used.

Major Body Regions

Knowledge of the external anatomy and landmarks of the body is important in performing a physical examination and many other clinical procedures. For purposes of study, the body is divided into two major regions called the *axial* and *appendicular regions.* Smaller areas within the major regions are described in the following paragraphs and illustrated in figure 1.10.

Axial Region

The **axial region** consists of the **head, neck (cervical**[14] **region),** and **trunk.** The trunk is further divided into the **thoracic region** above the diaphragm and the **abdominal region** below it.

---

[14] *cervic* = neck


Upper limb:
Acromial r. (shoulder)
Axillary r. (armpit)
Brachial r. (arm)
Cubital r. (elbow)
Antebrachial r. (forearm)
Carpal r. (wrist)
Palmar r. (palm)
Lower limb:
Coxal r. (hip)
Patellar r. (knee)
Cephalic r. (head)
Facial r. (face)
Cervical r. (neck)
Thoracic r. (chest):
Sternal r.
Pectoral r.
Umbilical r.
Abdominal r.
Inguinal r. (groin)
Pubic r.:
Mons pubis
External genitalia:
Penis
Scrotum
Testes
Lower limb:
Femoral r. (thigh)
Crural r. (leg)
Tarsal r. (ankle)
Pedal r. (foot):
Dorsum
Plantar surface (sole)

© McGraw-Hill Education/Joe De Grandis, photographer

© McGraw-Hill Education/Joe De Grandis, photographer

(a) Anterior (ventral) **(b) Anterior (ventral)**


Cranial r.
Nuchal r. (back of neck)
Interscapular r.
Scapular r.
Vertebral r.
Lumbar r.
Sacral r.
Gluteal r. (buttock)
Dorsum of hand
Perineal r.
Femoral r.
Popliteal r.
Crural r.
Tarsal r.
Calcaneal r. (heel)

© McGraw-Hill Education/Joe De Grandis, photographer

© McGraw-Hill Education/Joe De Grandis, photographer

(c) Posterior (dorsal) **(d) Posterior (dorsal)**

Figure 1.10 **The Adult Female and Male Body Regions.** (r. = region)

One way of referring to the locations of abdominal structures is to divide the region into quadrants. Two perpendicular lines intersecting at the umbilicus (navel) divide the abdomen into a **right upper quadrant (RUQ), right lower quadrant (RLQ), left upper quadrant (LUQ),** and **left lower quadrant (LLQ)** (fig. 1.11a, b). The quadrant scheme is often used to describe the site of an abdominal pain or abnormality.

The abdomen also can be divided into nine regions defined by four lines that intersect like a tic-tac-toe grid (fig. 1.11c, d). Each vertical line is called a *midclavicular line* because it passes through the midpoint of the clavicle (collarbone). The superior horizontal line is called the *subcostal*[15] *line* because it connects the inferior borders of the lowest costal cartilages (cartilages connecting the tenth rib on each side to the inferior end of the sternum). The inferior horizontal line is called the *intertubercular*[16] *line* because it passes from left to right between the tubercles *(anterior superior spines)* of the hip bones—two points of bone

---

[15] *sub* = below; *cost* = rib

[16] *inter* = between; *tubercul* = little swelling


Quadrants
Right upper quadrant
Left upper quadrant
Right lower quadrant
Left lower quadrant
Stomach
10th rib
Anterior superior spine
(a)
(b)
Regions
Midclavicular line
Hypochondriac region
Subcostal line
Lumbar region
Intertubercular line
Inguinal region
Epigastric region
Umbilical region
Hypogastric region
Liver
Gallbladder
10th rib
Large intestine
Small intestine
Urinary bladder
Urethra
(c)
(d)

Figure 1.11 **The Four Quadrants and Nine Regions of the Abdomen.** (a) External division into four quadrants. (b) Internal anatomy correlated with the quadrants. (c) External division into nine regions. (d) Internal anatomy correlated with the nine regions.

located about where the front pockets open on most pants. The three lateral regions of this grid, from upper to lower, are the left and right **hypochondriac,**[17] **lumbar,** and **inguinal**[18] **regions.** The three medial regions from upper to lower are the **epigastric,**[19] **umbilical,** and **hypogastric (pubic)** regions.

Appendicular Region

The **appendicular** (AP-en-DIC-you-lur) **region** of the body consists of the **upper limbs** and **lower limbs** (also called *appendages* or *extremities*). The upper limb includes the **arm** (**brachial region,** BRAY-kee-ul), **forearm** (**antebrachial**[20] **region,** AN-teh-BRAY-kee-ul), **wrist (carpal region), hand (manual region),** and **fingers (digits).** The lower limb includes the **thigh (femoral region), leg** (**crural region,** CROO-rul), **ankle (tarsal region), foot** (**pedal region,** PEE-dul), and **toes (digits).** In strict anatomical terms, *arm* refers only to that part of the upper limb between the shoulder and elbow. *Leg* refers only to that part of the lower limb between the knee and ankle.

A **segment** of a limb is a region between one joint and the next. The arm, for example, is the segment between the shoulder and elbow joints, and the forearm is the segment between the elbow and wrist joints. Slightly flexing your fingers, you can easily see that your thumb has two segments (proximal and distal), whereas the other four digits have three segments (proximal, middle, and distal). The segment concept is especially useful in describing the locations of bones and muscles and the movements of the joints.

Body Cavities and Membranes

The body wall encloses several **body cavities,** each lined by a membrane and containing internal organs called the **viscera** (VISS-er-uh) (singular, *viscus*[21]) (fig. 1.12, table 1.2).

TABLE 1.2 Body Cavities and Membranes

Name of Cavity	Associated Viscera	Membranous Lining
Cranial cavity	Brain	Meninges
Vertebral canal	Spinal cord	Meninges
Thoracic cavity		
Pleural cavities (2)	Lungs	Pleura
Pericardial cavity	Heart	Pericardium
Abdominopelvic cavity		
Abdominal cavity	Digestive organs, spleen, kidneys, ureters	Peritoneum
Pelvic cavity	Bladder, rectum, reproductive organs	Peritoneum



(a) Left lateral view (b) Anterior view

Figure 1.12 The Major Body Cavities.

---

[17] *hypo* = below; *chondr* = cartilage
[18] *inguin* = groin
[19] *epi* = above, over; *gastr* = stomach
[20] *ante* = fore, before; *brachi* = arm
[21] *viscus* = body organ

The Cranial Cavity and Vertebral Canal

The **cranial** (CRAY-nee-ul) **cavity** is enclosed by the cranial bones (braincase) of the skull and contains the brain. The **vertebral canal** is enclosed by the vertebral column (spine, backbone) and contains the spinal cord. The two are continuous with each other and lined by three membrane layers called the **meninges** (meh-NIN-jeez). Among other functions, the meninges protect the delicate nervous tissue from the hard protective bone that encloses it, and anchor the spinal cord to the vertebral column and limit its movement.

The Thoracic Cavity

During embryonic development, a space called the **coelom** (SEE-loam) forms within the trunk (see fig. 4.5c, p. 91). It subsequently becomes partitioned by a muscular sheet, the **diaphragm,** into a superior **thoracic cavity** and an inferior **abdominopelvic cavity.** Both cavities are lined with thin **serous membranes,** which secrete a lubricating film of moisture similar to blood serum (hence their name).

The thoracic cavity is divided by a thick partition called the **mediastinum**[22] (ME-dee-ah-STY-num) (fig. 1.12b). This is the region between the lungs, extending from the base of the neck to the diaphragm, occupied by the heart, the major blood vessels connected to it, the esophagus, the trachea and bronchi, and a gland called the *thymus*.

A two-layered serous membrane called the **pericardium**[23] wraps around the heart. The inner layer of the pericardium forms the surface of the heart itself and is called the **visceral** (VISS-er-ul) **pericardium (epicardium).** The outer layer is called the **parietal**[24] (pa-RY-eh-tul) **pericardium (pericardial sac).** It is separated from the visceral pericardium by a space called the **pericardial cavity** (fig. 1.13a) (see Deeper Insight 1.2). This space is lubricated by a thin film of **pericardial fluid.**

DEEPER INSIGHT 1.2

Cardiac Tamponade

Being confined by the pericardium can cause a problem for the heart under some circumstances. If a heart wall weakened by disease should rupture, blood spurts from the heart chamber into the pericardial cavity, filling the cavity more and more with each heartbeat. Diseased hearts also sometimes seep serous fluid into the pericardial sac. Either way, the effect is the same: The pericardial sac has little room to expand, so the accumulating fluid puts pressure on the heart, squeezing it and preventing it from refilling between beats. This condition is called *cardiac tamponade*. If the heart chambers cannot refill, then cardiac output declines and a person may die of catastrophic circulatory failure. A similar situation occurs if serous fluid or air accumulates in the pleural cavity, causing collapse of a lung.

The right and left sides of the thoracic cavity contain the lungs. A serous membrane called the **pleura**[25] (PLOOR-uh) wraps around each lung (fig. 1.13b). Like the pericardium, the pleura has visceral (inner) and parietal (outer) layers. The **visceral pleura** forms the external surface of the lung, and the **parietal pleura** lines the inside of the rib cage. The narrow space between them is called the **pleural cavity** (see fig. A.11, p. 340). It is lubricated by slippery **pleural fluid.**

Note that in both the pericardium and pleura, the visceral layer of the membrane *covers* the surface of an organ and the parietal layer *lines* the inside of a body cavity. We will see this pattern repeated elsewhere, including the abdominopelvic cavity.

---

[22] *mediastinum* = in the middle
[23] *peri* = around; *cardi* = heart
[24] *pariet* = wall
[25] *pleur* = rib, side



(a) Pericardium (b) Pleurae

Figure 1.13 Parietal and Visceral Layers of the Pericardial and Pleural Membranes of the Thoracic Cavity.

The Abdominopelvic Cavity

The abdominopelvic cavity consists of the **abdominal cavity** superiorly and the **pelvic cavity** inferiorly. The abdominal cavity contains most of the digestive organs as well as the spleen, kidneys, and ureters. It extends inferiorly to the level of a bony landmark called the *brim* of the pelvis (see fig. 8.6, p. 191, and fig. A.7, p. 337). The pelvic cavity, below the brim, is continuous with the abdominal cavity (no wall separates them), but it is markedly narrower and tilts posteriorly (see fig. 1.12a). It contains the rectum, urinary bladder, urethra, and reproductive organs.

The abdominopelvic cavity contains a two-layered serous membrane called the **peritoneum**[26] (PERR-ih-toe-NEE-um). The **parietal peritoneum** lines the cavity wall. The **visceral peritoneum** turns inward from the body wall, wraps around the abdominal viscera, binds them to the body wall or suspends them from it, and holds them in their proper place. The **peritoneal cavity** is the space between the parietal and visceral layers. It is lubricated by **peritoneal fluid.**

Some organs of the abdominal cavity lie against the posterior body wall and are covered by peritoneum only on the side facing the peritoneal cavity. They are said to have a **retroperitoneal**[27] position (fig. 1.14). These include the kidneys; ureters; adrenal glands; most of the pancreas; and abdominal portions of two major blood vessels, the aorta and inferior vena cava (see fig. A.6, p. 336). Organs that are encircled by peritoneum and connected to the posterior body wall by peritoneal sheets are described as **intraperitoneal.**[28]

The intestines are suspended from the posterior abdominal wall by a translucent membrane called the **posterior mesentery**[29] (MESS-en-tare-ee), an infolding of the peritoneum (fig. 1.15). The posterior mesentery of the large intestine is called the **mesocolon.** In some places, after wrapping around the intestines or other viscera, the mesentery continues toward the anterior body wall as the **anterior mesentery.** The most prominent example of this is a fatty membrane called the **greater omentum,**[30] which hangs like an apron from the inferolateral margin of the stomach and overlies the intestines (see fig. A.4, p. 334). It is unattached at its inferior border and can be lifted to reveal the intestines. A smaller **lesser omentum** extends from the superomedial margin of the stomach to the liver.

Where the visceral peritoneum meets an organ such as the stomach or small intestine, it divides and wraps around it, forming an outer layer of the organ called the **serosa** (seer-OH-sa) (fig. 1.14). The visceral peritoneum thus consists of the mesenteries and serosae.

Potential Spaces

Some of the spaces between body membranes are considered to be **potential spaces,** so named because under normal conditions, the membranes are pressed firmly together and there is no actual space between them. The membranes are not physically attached, however, and under unusual conditions, they may separate and create a space filled with fluid or other matter. Thus, there is only a potential for the membranes to separate and create a space.

The pleural cavity is one example. Normally, the parietal and visceral pleurae are pressed together without a gap between them, but under pathological conditions, air or serous fluid can accumulate between the membranes and open up a space. Another example is the internal cavity *(lumen)* of the uterus. In a nonpregnant uterus, the mucous membranes of the opposite walls are pressed together, so there is little or no open space in the organ. In pregnancy, of course, a growing fetus occupies this space and pushes the mucous membranes apart.

---

[26] *peri* = around; *tone* = stretched
[27] *retro* = behind
[28] *intra* = within
[29] *mes* = in the middle; *enter* = intestine
[30] *omentum* = covering



Figure 1.14 **Transverse Section Through the Abdomen.** Shows the peritoneum (thin blue line), peritoneal cavity (with most viscera omitted), and some retroperitoneal organs (between peritoneum and posterior body wall).



© MedicImage/Getty Images

Figure 1.15 **Serous Membranes of the Abdominal Cavity.** (a) Diagram of the abdomen in sagittal section, left lateral view. (b) Surgical photograph of an intestinal mesentery.

- *Is the urinary bladder in the peritoneal cavity?*

Before You Go On

Answer the following questions to test your understanding of the preceding section:

5. Put the following list in order from the largest and most complex to the smallest and least complex components of the human body: cells, molecules, organelles, organs, organ systems, tissues.
6. Name the organ system responsible for each of the following functions: (a) movement and distribution of blood; (b) water retention, sensation, and protection from infection; (c) hormone secretion; (d) nutrient breakdown and absorption; and (e) recovery of excess tissue fluid and detection of pathogens in the tissues.
7. State the directional term that describes the position of (a) the spinal cord relative to the heart; (b) the eyes relative to the nose; (c) the urinary bladder relative to the intestines; (d) the diaphragm relative to the liver; and (e) skin relative to the muscles.
8. State the alternative anatomical terms for the regions commonly known as the neck, the sole of the foot, the lower back, the buttocks, and the calf.
9. Name the membranes that enclose the brain, the heart, the lungs, and the abdominal cavity.

1.3 The Language of Anatomy

Expected Learning Outcomes

When you have completed this section, you should be able to

a. explain why modern anatomical terminology is so heavily based on Greek and Latin;
b. recognize eponyms when you see them;
c. describe the efforts to achieve an internationally uniform anatomical terminology;
d. discuss the Greek, Latin, or other derivations of medical terms;
e. state some reasons why the literal meaning of a word may not lend insight into its definition;
f. relate singular noun forms to their plural forms; and
g. discuss why precise spelling is important in medical communication.

One of the greatest challenges faced by anatomy students is the vocabulary. In this book, you will encounter such Latin terms as *corpus callosum* (a brain structure), *ligamentum arteriosum* (a small fibrous band near the heart), and *extensor carpi radialis longus* (a forearm muscle). You may wonder why structures aren't named in "just plain English," and how you will ever remember such formidable names. This section will give you some answers to these questions and some useful tips on mastering anatomical terminology.

The Origins of Medical Terms

The major features of human gross anatomy have standard international names prescribed by a book titled *Terminologia Anatomica (TA).* The TA system was codified in 1998 by an international body of anatomists and approved by professional associations of anatomists in more than 50 countries.

About 90% of today's medical terms are formed from about 1,200 Greek and Latin roots. Scientific investigation began in ancient Greece and soon spread to Rome. The Greeks and Romans coined many of the words still used in human anatomy today: *duodenum, uterus, prostate, cerebellum, diaphragm, sacrum, amnion,* and others. In the Renaissance, the fast pace of anatomical discovery required a profusion of new terms to describe things. Anatomists in different countries began giving different names to the same structures. Adding to the confusion, they often named new structures and diseases in honor of their esteemed teachers and predecessors, giving us such nondescriptive terms as the *fallopian tube* and *canal of Schlemm.* Terms coined from the names of people, called **eponyms,**[31] afford little clue as to what a structure or medical condition is.

In hopes of resolving this growing confusion, anatomists began meeting as early as 1895 to try to devise a uniform international terminology. After several false starts, they agreed on a list of terms titled *Nomina Anatomica (NA). NA* rejected all eponyms as unofficial and gave each structure a unique Latin name to be used worldwide. Even if you were to look at an anatomy atlas in Korean or Arabic, the illustrations might be labeled with the same Latin terms as in an English-language atlas. *NA* served for many decades until replaced by *TA,* which prescribes both Latin names and accepted English equivalents. The terminology in this book conforms to *TA* except where undue confusion would result from abandoning widely used, yet unofficial terms.

Analyzing Medical Terms

The task of learning anatomical terminology seems overwhelming at first, but as you study this book, there is a simple habit that can quickly make you more comfortable with the technical language of medicine—read the footnotes, which explain the roots and origins of the words. Students who find scientific terms confusing and difficult to pronounce, spell, and remember usually feel more confident once they realize the logic of how terms are composed. A term such as *hyponatremia* is less forbidding once we recognize that it is composed of three common word elements: *hypo-* (below normal), *natr-* (sodium), and *-emia* (blood condition). Thus, hyponatremia is a deficiency of sodium in the blood. Those three word elements appear over and over in many other medical terms: *hypothermia, natriuretic, anemia,* and so on. Once you learn the meanings of *hypo-, natri-,* and *-emia,* you already have the tools to at least partially understand hundreds of other biomedical terms. Inside the back cover, you will find a lexicon of the 400 word elements most commonly footnoted in this book.

Scientific terms are typically composed of one or more of the following elements:

- At least one *root (stem)* that bears the core meaning of the word. In *cardiology,* for example, the root is *cardi* (heart). Many words have two or more roots. In *adipocyte,* the roots are *adip* (fat) and *cyte* (cell).
- *Combining vowels,* which are often inserted to join roots and make the word easier to pronounce. The letter *o* is the most common combining vowel (as in *adipocyte*), but all vowels are used in this way, such as *a* in *ligament, e* in *vitreous, i* in *fusiform, u* in *ovulation,* and *y* in *tachycardia.* Some words have no combining vowels. A combination of a root and combining vowel is called a *combining form:* for example, *odont* (tooth) + *o* (the combining vowel) make the combining form *odonto,* as in *odontoblast* (a cell that produces the dentin of a tooth).
- A *prefix* may be present to modify the core meaning of the word. For example, *gastric* (pertaining to the stomach or to the belly of a muscle) takes on a wide variety of new meanings when prefixes are added: *epigastric* (above the stomach), *hypogastric* (below the stomach), *endogastric* (within the stomach), and *digastric* (a muscle with two bellies).
- A *suffix* may be added to the end of a word to modify its core meaning. For example, *microscope, microscopy, microscopic,* and *microscopist* have different meanings because of their suffixes alone. Often two or more suffixes, or a root and suffix, occur together so often that they are treated jointly as a *compound suffix;* for example, *log* (study) + *y* (process) form the compound suffix *-logy* (the study of).

To summarize these basic principles, consider the word *gastroenterology,* denoting a branch of medicine dealing with the stomach and small intestine. It breaks down into

gastro/entero/logy
gastro = a combining form meaning "stomach"
entero = a combining form meaning "small intestine"
logy = a compound suffix meaning "the study of"

"Dissecting" words in this way and paying attention to the word-origin footnotes throughout this book will help make you more comfortable with the language of anatomy. Knowing how a word breaks down and knowing the meaning of its elements make it easier to pronounce a word, spell it, and remember its definition.

There are a few unfortunate exceptions, however. The path from original meaning to current usage has often become obscured by history (see Deeper Insight 1.3). The foregoing approach also

---

[31] *epo* = after, related to; *nym* = name

DEEPER INSIGHT 1.3

Obscure Word Origins

The literal translation of a word doesn't always provide great insight into its modern meaning. The history of language is full of twists and turns that are fascinating in their own right and say much about the history of the whole of human culture, but they can create confusion for students.

For example, the *amnion* is a transparent sac that forms around the developing fetus. The word is derived from *amnos*, from the Greek for "lamb." From this origin, *amnos* came to mean a bowl for catching the blood of sacrificial lambs, and from there the word found its way into biomedical usage for the membrane that emerges (quite bloody) as part of the afterbirth. The *acetabulum*, the socket of the hip joint, literally means "vinegar cup." The hip socket reminded Pliny the Elder (23–79 CE) of the little cups used to serve vinegar as a condiment on dining tables in ancient Rome. The word *testicles* literally means "little witnesses." The history of medical language has some amusing conjectures as to why this word was chosen to name the male gonads.

is no help with eponyms or with **acronyms**—words composed of the first letter, or first few letters, of a series of words. *PET,* for example, is an acronym for *positron emission tomography.* Note that *PET* is a pronounceable word, hence a true acronym. Acronyms are not to be confused with simple abbreviations such as DNA or MRI, in which each letter must be pronounced separately; these are properly called *initialisms.*

Variant Forms of Medical Terms

A point of confusion for many beginning students is how to recognize the plural forms of medical terms. Few people would fail to recognize that *ovaries* is the plural of *ovary,* but the connection is harder to make in other cases: For example, the plural of *cortex* is *cortices* (COR-ti-sees), the plural of *corpus* is *corpora,* and the plural of *ganglion* is *ganglia*. Table 1.3 will help you make the connection between common singular and plural noun terminals.

In some cases, what appears to the beginner to be two completely different words may be only the noun and adjective forms of the same word. For example, *brachium* denotes the arm, and *brachii* (as in the muscle name *biceps brachii*) means "of the arm." *Carpus* denotes the wrist, and *carpi,* a word used in several muscle names, means "of the wrist." Adjectives can also take different forms for the singular and plural and for different degrees of comparison. The *digits* are the fingers and toes. The word *digiti* in a muscle name means "of a single finger (or toe)," whereas *digitorum* is the plural, meaning "of multiple fingers (or toes)." Thus the *extensor digiti minimi* muscle extends only the little finger, whereas the *extensor digitorum* muscle extends all fingers except the thumb.

TABLE 1.3 Singular and Plural Forms of Some Noun Terminals

Singular Ending	Plural Ending	Examples
-a	-ae	axilla, axillae
-ax	-aces	thorax, thoraces
-en	-ina	lumen, lumina
-ex	-ices	cortex, cortices
-is	-es	diagnosis, diagnoses
-is	-ides	epididymis, epididymides
-ix	-ices	appendix, appendices
-ma	-mata	carcinoma, carcinomata
-on	-a	ganglion, ganglia
-um	-a	septum, septa
-us	-era	viscus, viscera
-us	-i	villus, villi
-us	-ora	corpus, corpora
-x	-ges	phalanx, phalanges
-y	-ies	ovary, ovaries
-yx	-yces	calyx, calyces

The English words *large, larger,* and *largest* are examples of the positive, comparative, and superlative degrees of comparison. In Latin, these are *magnus, major* (from *maior*), and *maximus.* We find these in the muscle names *adductor magnus* (a *large* muscle of the thigh), the *pectoralis major* (the *larger* of two *pectoralis* muscles of the chest), and *gluteus maximus* (the *largest* of the three gluteal muscles of the buttock).

Some noun variations indicate the possessive, such as the *rectus abdominis,* a straight *(rectus)* muscle of the abdomen (*abdominis,* "of the abdomen"), and the *erector spinae,* a muscle that straightens *(erector)* the spinal column (*spinae,* "of the spine").

Anatomical terminology also follows the Greek and Latin practice of placing the adjective after the noun. Thus, we have such names as the *stratum lucidum* for a clear *(lucidum)* layer *(stratum)* of the epidermis, the *foramen magnum* for a large *(magnum)* hole *(foramen)* in the skull, and the aforementioned *pectoralis major* muscle of the chest.

This is not to say that you must be conversant in Latin or Greek grammar to proceed with your study of anatomy. These few examples, however, may alert you to some patterns to watch for in the terminology you study and, ideally, will make your encounters with anatomical terminology less confusing.

The Importance of Precision

A final word of advice for your study of anatomy: Be precise in your use of anatomical terms. It may seem trivial if you misspell *trapezius* as *trapezium,* but in doing so, you would be changing the name of a back muscle to the name of a wrist bone. Similarly, changing *occipitalis* to *occipital* or *zygomaticus* to *zygomatic* changes other muscle names to bone names. Changing *malleolus* to *malleus,* omitting a small and perhaps trivial-seeming syllable, changes the name of the bony protuberance of your ankle to the name of a tiny middle-ear bone. A "little" error such as misspelling *ileum* as *ilium* changes the name of part of the small intestine to the name of a hip bone. Again, a "mere" one-letter difference distinguishes gustation (the sense of taste) from gestation (pregnancy).

The health professions demand the utmost attention to detail and precision—people's lives may one day be in your hands. The habit of carefulness must extend to your use of language as well. Many patients die because of tragic miscommunication in the hospital. Compared to this, it is hardly tragic if an instructor deducts a point or two for a small error in spelling. It should be considered a lesson learned about the importance of accuracy.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

10. Explain why modern anatomical terminology is so heavily based on Greek and Latin.
11. Distinguish between an eponym and an acronym, and explain why both of these present difficulties for interpreting anatomical terms.
12. Break the following words down into their roots, prefixes, and suffixes and state their meanings, following the example of *gastroenterology* analyzed earlier: *pericardium, appendectomy, subcutaneous, arteriosclerosis, hypercalcemia*. Consult the list of word elements inside the back cover of the book for help.
13. Write the singular form of each of the following words: *pleurae, gyri, lumina, ganglia, fissures*. Write the plural form of each of the following: *villus, tibia, encephalitis, cervix, stoma.*

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

1.1 The Scope of Human Anatomy (p. 2)

1. The distinction between the sciences of anatomy and physiology, and the way functional morphology unites the two
2. The distinctions between gross, microscopic, surface, radiologic, systemic, regional, and comparative anatomy
3. Examples of what a physician might be looking for when he or she employs simple inspection, palpation, auscultation, and percussion with a patient
4. Ways in which dissection differs from exploratory surgery, and why exploratory surgery is far less common now than it was in the 1950s
5. The principles behind radiography, computed tomography (CT), magnetic resonance imaging (MRI), positron emission tomography (PET), and sonography
6. Differences between invasive and noninvasive methods of medical imaging
7. Reasons why the anatomy presented in this book may not apply to every human being

1.2 The Human Body Plan (p. 8)

1. The successive levels of human structural complexity from atom to organism
2. Correlation between the levels of human structure and the sciences of gross anatomy, histology, cytology, and ultrastructure
3. The 11 human organ systems, including the basic functions and major organs of each
4. Anatomical position and why it is important in anatomical communication
5. What it means to say the forearm is pronated or supinated, and how this differs from the meanings of *prone* and *supine*
6. The three primary anatomical planes, and what a given region of the body (such as midthoracic) would look like in each of these planes
7. The distinctions between *anterior* and *posterior; cephalic, rostral,* and *caudal; superior* and *inferior; medial* and *lateral; proximal* and *distal; ipsilateral* and *contralateral;* and *superficial* and *deep;* and the ability to use these terms correctly in descriptive anatomical sentences
8. Why the words *anterior* and *posterior* are preferable to *ventral* and *dorsal* for most purposes in human anatomy, and why *ventral* and *dorsal* would be more relevant to dissection of a cat than to dissection of the human cadaver
9. The principal body parts of the axial region and the appendicular region
10. The landmarks used to divide the abdomen into four quadrants, and the name of each quadrant
11. The landmarks used to divide the abdomen into a 3 × 3 grid, and the names of each of the 9 resulting regions
12. Names of the cavities that house the brain and spinal cord, and of the membranes that line these cavities
13. Landmarks that divide the thoracic, abdominal, and pelvic cavities from each other
14. The names of the cavities that enfold the heart and lungs; names of the membranes that line these cavities; names of the relatively superficial and deep layers of each of these two-layered membranes; and names of the fluids that lubricate these membranes and allow for painless heart and lung movements
15. The name of the membrane that lines the abdominal cavity; the name of its lubricating fluid; and the term for organs that lie between this membrane and the body wall
16. The name of the serous membranes that suspend and bind the abdominal organs, and the name for the outer surface of an organ formed by this membrane passing around it
17. The meaning of *potential spaces,* and some examples

1.3 The Language of Anatomy (p. 19)

1. The reason so many medical terms are based on Latin and Greek
2. The role of *Terminologia Anatomica (TA)* in modern medical terminology, and the problems that it is meant to solve
3. How to divide medical terms such as *histology, cardiovascular, anatomy, endometrium, pseudostratified, subcutaneous, corticospinal,* and *hypodermic* into their prefixes, roots, combining forms, and suffixes, and how to recognize combining vowels where they exist
4. The differences between an eponym and an acronym, and between an acronym and an abbreviation, with medical examples of each
5. Recognition of the singular and plural forms of the same term, as in *extensor digiti* and *extensor digitorum*
6. Recognition of the positive, comparative, and superlative forms of the same term, as in the second word of *adductor magnus, pectoralis major,* and *gluteus maximus*
7. The importance of accurate spelling; why even one-letter or other trivial-seeming errors may be very significant in clinical practice; and examples of where this may apply

Testing Your Recall

1. Structure that can be observed with the naked eye is called
   a. gross anatomy.
   b. ultrastructure.
   c. microscopic anatomy.
   d. macroscopic anatomy.
   e. cytology.
2. Which of the following techniques requires an injection of radioisotopes into a patient's bloodstream?
   a. sonography
   b. a PET scan
   c. radiography
   d. a CT scan
   e. an MRI scan
3. The simplest structures considered to be alive are
   a. organs.
   b. tissues.
   c. cells.
   d. organelles.
   e. proteins.
4. The tarsal region is _____ to the popliteal region.
   a. medial
   b. superficial
   c. superior
   d. dorsal
   e. distal
5. The _____ region is immediately medial to the coxal region.
   a. inguinal
   b. hypochondriac
   c. umbilical
   d. popliteal
   e. cubital
6. Which of these regions is *not* part of the upper limb?
   a. plantar
   b. carpal
   c. cubital
   d. brachial
   e. palmar
7. Which of these organs is intraperitoneal?
   a. urinary bladder
   b. kidney
   c. heart
   d. small intestine
   e. brain
8. Which of these is *not* an organ system?
   a. muscular system
   b. integumentary system
   c. endocrine system
   d. lymphatic system
   e. immune system
9. The term *histology* is most nearly equivalent to
   a. histopathology.
   b. microscopic anatomy.
   c. cytology.
   d. ultrastructure.
   e. systemic anatomy.
10. An imaging technique that exposes the patient to no harmful radiation is
    a. radiography.
    b. positron emission tomography (PET).
    c. computed tomography (CT).
    d. magnetic resonance imaging (MRI).
    e. angiography.
11. Cutting and separating tissues to reveal their structural relationships is called _____.
12. The forearm is said to be _____ when the palms are facing forward.
13. The relatively superficial layer of the pleura is called the _____ pleura.
14. Abdominal organs that lie against the posterior abdominal wall and are covered with peritoneum only on the anterior side are said to have a/an _____ position.
15. _____ is a science that doesn't merely describe bodily structure but interprets structure in terms of its function.
16. When a doctor presses on the upper abdomen to feel the size and texture of the liver, he or she is using a technique of physical examination called _____.
17. _____ is a method of medical imaging that uses X-rays and a computer to generate images of thin slices of the body.
18. A/An _____ is the simplest body structure to be composed of two or more types of tissue.
19. The left hand and left foot are _____ to each other, whereas the left hand and right hand are _____ to each other.
20. The anterior pit of the elbow is called the _____ region, whereas the corresponding (but posterior) pit of the knee is called the _____ region.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. ana-
2. -graphy
3. morpho-
4. hypo-
5. -ation
6. -elle
7. palp-
8. ante-
9. intra-
10. auscult-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. Regional anatomy is a variation of gross anatomy.
2. A single sagittal section through the body could show one lung but not both.
3. Abnormal skin color or dryness could be one piece of diagnostic information gained by auscultation.
4. Radiology refers only to those medical imaging methods that use radioisotopes.
5. It is more harmful to have only the heart reversed from left to right than to have all of the thoracic and abdominal organs reversed.
6. There are more cells than organelles in the body.
7. The diaphragm is ventral to the lungs.
8. It would be possible to see both eyes in a single frontal section of the head.
9. Each lung is enclosed in a space between the parietal and visceral pleura.
10. The word *scuba*, derived from the words *self-contained underwater breathing apparatus*, is an acronym.

Answers in appendix A

Testing Your Comprehension

1. Classify each of the following radiologic techniques as invasive or noninvasive and explain your reasoning for each: angiography, sonography, CT, MRI, and PET.
2. Beginning medical students are always told to examine multiple cadavers and not confine their study to just one. Other than the obvious purpose of studying both male and female anatomy, why is this instruction so important in medical education?
3. Identify which anatomical plane—sagittal, frontal, or transverse—is the only one that could *not* show (a) both the brain and tongue; (b) both eyes; (c) both the heart and uterus; (d) both the hypogastric and gluteal regions; (e) both kidneys; and (f) both the sternum and vertebral column.
4. Lay people often misunderstand medical terminology. What do you think people really mean when they say they have "planter's warts"?
5. Why do you think the writers of *Terminologia Anatomica* decided to reject eponyms? Do you agree with that decision? Why do you think they decided to name structures in Latin? Do you agree with that decision? Explain your reasons for agreeing or disagreeing with each.

The inner lining of the trachea photographed with a scanning electron microscope (SEM)

© NIBSC/Science Source

CHAPTER

2

CYTOLOGY— THE STUDY OF CELLS

CHAPTER OUTLINE

2.1 The Study of Cells 26
- Microscopy 26
- Cell Shapes and Sizes 27
- Basic Components of a Cell 29

2.2 The Cell Surface 30
- The Plasma Membrane 30
- Membrane Transport 33
- Extensions of the Cell Surface 36
- The Glycocalyx 38
- Cell Junctions 38

2.3 The Cell Interior 40
- The Cytoskeleton 40
- Organelles 42
- Inclusions 46

2.4 The Cell Life Cycle 47
- The Cell Cycle 47
- Cell Division 47
- Stem Cells 50

Study Guide 51

DEEPER INSIGHTS

2.1 When Desmosomes Fail 39
2.2 The Origin of Mitochondria 46
2.3 Cancer 48

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concept:

- Levels of human structure (p. 8)

Anatomy & Physiology REVEALED®
aprevealed.com

Module 2: Cells and Chemistry
Module 3: Tissues

The most important revolution in the history of medicine was the realization that all bodily functions result from cellular activity. By extension, nearly every dysfunction of the body is now recognized as stemming from a dysfunction at the cellular level. Numerous new medical research articles published every week are on cellular function, and all drug development is based on an intimate knowledge of how cells work. The cellular perspective has thus become indispensable to any true understanding of the structure and function of the human body, the mechanisms of disease, and the rationale of therapy.

This chapter therefore begins our study of anatomy at the cellular level. We will see how continued developments in microscopy have deepened our insight into cell structure, examine the structural components of cells, and briefly survey two aspects of cellular function—transport through the plasma membrane and the cell life cycle. It is the derangement of that life cycle that gives rise to one of the most dreaded of human diseases, cancer.

2.1 The Study of Cells

Expected Learning Outcomes

When you have completed this section, you should be able to

a. state some tenets of the cell theory;
b. discuss the way that developments in microscopy have changed our view of cell structure;
c. outline the major structural components of a cell;
d. identify cell shapes from their descriptive terms; and
e. state the size range of human cells and explain why cell size is limited.

The scientific study of cellular structure and function is called **cytology.**[1] Some historians date the birth of this science to April 15, 1663, when English inventor Robert Hooke employed his newly created microscope to observe the little boxes formed by the cell walls of cork. He named them *cellulae.* Cytology was greatly advanced by refinements in microscope technology and techniques of histology (tissue preparation) in the nineteenth century. By 1900, it was established beyond reasonable doubt that every living organism is made of cells; that cells now arise only through the division of preexisting cells rather than springing spontaneously from nonliving matter; and that all cells have the same basic chemical components, such as carbohydrates, lipids, proteins, and nucleic acids. Cells are the simplest entities considered to be alive; no one molecule such as DNA or an enzyme is alive in itself. These and other principles have been codified as the **cell theory.**

Microscopy

Cytology would not exist without the microscope. Throughout this book, you will find many **photomicrographs**—photos of tissues and cells taken through the microscope. The microscopes used to produce them fall into three basic categories: the light microscope, transmission electron microscope, and scanning electron microscope.

The **light microscope (LM)** uses visible light to produce its images. It is the least expensive type of microscope, the easiest to use, and the most often used, but it is also the most limited in the amount of useful magnification it can produce. Light microscopes today magnify up to 1,200 times. There are several varieties of light microscopes, including the fluorescence microscope used to produce figure 2.16b.

Most of the structure we study in this chapter is invisible to the LM, not because the LM cannot magnify enough but because it cannot reveal enough detail. The most important thing about a good microscope is not magnification but **resolution**—the ability to reveal detail. Any image can be photographed and enlarged as much as we wish, but if enlargement fails to reveal greater detail, it is *empty magnification.* A large blurry image is not nearly as informative as one that is small and sharp. For reasons of physics beyond the scope of this chapter, it is the wavelength of light that places a limit on resolution. At the wavelengths of visible light (about 400 to 700 nanometers, or nm), the LM cannot distinguish between two objects any closer together than 200 nm (0.2 micrometers, or µm).

Resolution improves when objects are viewed with radiation of shorter wavelengths. *Electron microscopes* achieve higher resolution by using not visible light but beams of electrons with very short wavelength (0.005 nm). The **transmission electron microscope (TEM),** invented in the mid-twentieth century, is usually used to study specimens that have been sliced ultrathin with diamond knives and stained with heavy metals such as osmium, which absorbs electrons. The TEM resolves details as small as 0.5 nm and attains useful magnifications of biological material up to 600,000 times. This is good enough to see even things as small as proteins, nucleic acids, and other large molecules. Such fine detail is called cell *ultrastructure.* Even at the same magnifications as the LM, the TEM reveals far more detail (fig. 2.1). It usually produces two-dimensional black-and-white images, but electron photomicrographs are often colorized for instructional purposes.

The **scanning electron microscope (SEM)** uses a specimen coated with vaporized metal (usually gold). The electron beam strikes the specimen and discharges secondary electrons from the metal coating. These electrons then strike a fluorescent screen and produce an image. The SEM yields less resolution than the TEM and is used at lower magnification, but it produces dramatic three-dimensional images that are sometimes more informative than TEM images, and it does not require that the specimen be cut into thin slices. The SEM can view only the surfaces of specimens; it does not see through an object as the LM or TEM does. Cell interiors can be viewed, however, by a *freeze-fracture* method in which a cell is frozen, cracked open, coated with gold vapor, and then viewed by either TEM or SEM. Figure 2.2 compares red blood cells photographed with the LM, TEM, and SEM.

Apply What You Know

Beyond figure 2.2, list all of the photomicrographs in this chapter that you believe were made with the LM, with the TEM, and with the SEM.

---

[1] *cyto* = cell; *logy* = study of


© Doug Bray, Biological Science, Univ. of Lethbridge

(a) Light microscope (LM)


2.0 µm
© Doug Bray, Biological Science, Univ. of Lethbridge

(b) Transmission electron microscope (TEM)

Figure 2.1 **Magnification Versus Resolution.** These cell nuclei were photographed at the same magnification (about × 750) through (a) a light microscope (LM) and (b) a transmission electron microscope (TEM). Note the finer detail visible with the TEM.

Cell Shapes and Sizes

We will shortly examine the structure of a generic cell, but the generalizations we draw should not blind you to the diversity of cellular form and function in humans. There are about 200 kinds of cells in the human body, with a variety of shapes, sizes, and functions.

Descriptions of organ and tissue structure often refer to the shapes of cells by the following terms (fig. 2.3):

- *Squamous*[2] (SQUAY-mus)—a thin, flat, scaly shape, often with a bulge where the nucleus is—much like the shape of a fried egg "sunny side up." Squamous cells line the esophagus and form the surface layer (epidermis) of the skin.
- *Cuboidal*[3] (cue-BOY-dul)—squarish-looking in frontal tissue sections and about equal in height and width; liver cells are a good example.


Red blood cells
10.0 µm
© Ed Reschke/Getty Images

(a) Light microscope (LM)


Red blood cells
Blood vessel
10.0 µm
© David Phillips/Science Source

(b) Transmission electron microscope (TEM)


10.0 µm
© David Phillips/Science Source

(c) Scanning electron microscope (SEM)

Figure 2.2 **Images of Red Blood Cells Produced by Three Kinds of Microscopes.**

• *Based on the SEM image (c), can you explain why the cells in part (a) have such pale centers?*

- *Columnar*—distinctly taller than wide, such as the inner lining cells of the stomach and intestines.
- *Polygonal*[4]—having irregularly angular shapes with four, five, or more sides. Cells that look cuboidal or columnar in frontal view are commonly polygonal in an end view, like a quartz crystal.
- *Stellate*[5]—having multiple pointed processes projecting from the body of a cell, giving it a somewhat starlike shape. The cell bodies of many nerve cells are stellate.
- *Spheroidal* to *ovoid*—round to oval, as in egg cells and white blood cells.

---

[2] *squam* = scale; *ous* = characterized by
[3] *cub* = cube-shaped; *oidal* = like, resembling
[4] *poly* = many; *gon* = angles
[5] *stell* = star; *ate* = characterized by



Figure 2.3 Common Cell Shapes.

- *Discoid*—disc-shaped, as in red blood cells.
- *Fusiform*[6] (FEW-zih-form)—spindle- or toothpick-shaped; elongated, with a thick middle and tapered ends, as in smooth muscle cells.
- *Fibrous*—long, slender, and threadlike, as in skeletal muscle cells and the axons (nerve fibers) of nerve cells.

In some cells, it is important to distinguish one surface from another, because cell surfaces may differ in function and membrane composition. This is especially true in *epithelia,* cell layers that cover organ surfaces. An epithelial cell rests on a lower **basal surface** often attached to an extracellular *basement membrane* (see chapter 3). The upper surface of the cell is called the **apical surface.** Its sides are **lateral surfaces.** You could compare these to the floor, roof, and walls of a house, respectively.

The most useful unit of measurement for designating cell sizes is the **micrometer (µm),** formerly called the *micron*—one-millionth (10^{-6}) of a meter, one-thousandth (10^{-3}) of a millimeter. The smallest objects most people can see with the naked eye are about 100 µm, which is about one-quarter the size of the period at the end of this sentence. A few human cells fall within this range, such as the egg cell and some fat cells, but most human cells are about 10 to 15 µm wide. The longest human cells are nerve cells (sometimes over a meter long) and muscle cells (up to 30 cm long), but both are usually too slender to be seen with the naked eye.

There are several factors that limit the size of cells. If a cell swells to excessive size, it ruptures like an overfilled water balloon. In addition, cell size is limited by the relationship between its volume and surface area. The surface area of a cell is proportional to the square of its diameter, while volume is proportional to the cube of diameter. Thus, for a given increase in diameter, cell



Large cell
Diameter = 20 µm
Surface area = 20 µm × 20 µm × 6 = 2,400 µm²
Volume = 20 µm × 20 µm × 20 µm = 8,000 µm³

Small cell
Diameter = 10 µm
Surface area = 10 µm × 10 µm × 6 = 600 µm²
Volume = 10 µm × 10 µm × 10 µm = 1,000 µm³

Effect of cell growth:
Diameter *(D)* increased by a factor of 2
Surface area increased by a factor of 4 (= D^2)
Volume increased by a factor of 8 (= D^3)

Figure 2.4 **The Relationship Between Cell Surface Area and Volume.** As a cell doubles in width, its volume increases eightfold, but its surface area increases only fourfold. A cell that is too large may have too little plasma membrane to support the metabolic needs of its volume of cytoplasm.

---

[6] *fusi* = spindle; *form* = shape

volume increases much faster than surface area. Picture a cuboidal cell 10 μm on each side (fig. 2.4). It would have a surface area of 600 μm^2 (10 μm × 10 μm × 6 sides) and a volume of 1,000 μm^3 (10 × 10 × 10 μm). Now, suppose it grew by another 10 μm on each side. Its new surface area would be 20 μm × 20 μm × 6 = 2,400 μm^2, and its volume would be 20 × 20 × 20 μm = 8,000 μm^3. The 20 μm cell has eight times as much cytoplasm needing nourishment and waste removal, but only four times as much membrane surface through which wastes and nutrients can be exchanged. In short, a cell that is too big cannot support itself.

Also, if a cell were too large, molecules could not diffuse from place to place fast enough to support its metabolism. The time required for diffusion is proportional to the square of distance, so if cell diameter doubled, the travel time for molecules within the cell would increase fourfold. For example, if it took 10 seconds for a molecule to diffuse from the surface to the center of a cell with a 10 μm radius, then we increased this cell to a radius of 1 mm, it would take 278 hours to reach the center—far too slow to support the cell's life activities.

Having organs composed of many small cells instead of fewer large ones has another advantage: The death of one or a few cells is of less consequence to the structure and function of the whole organ.

Basic Components of a Cell

Before electron microscopy, little was known about structural cytology except that cells were enclosed in a membrane and contained a nucleus. The material between the nucleus and surface membrane was thought to be little more than a gelatinous mixture of chemicals and vaguely defined particles. But the electron microscope revealed that the cytoplasm is crowded with a maze of passages, compartments, and filaments (fig. 2.5). Earlier microscopists were


Apical cell surface
Microvillus
Desmosome
Fat droplet
Secretory vesicle
Intercellular space
Centrosome
Centrioles
Free ribosomes
Nucleus
Nucleolus
Nuclear envelope
Mitochondrion
Hemidesmosome
Basal cell surface
Microfilaments
Terminal web
Secretory vesicle undergoing exocytosis
Golgi vesicles
Golgi complex
Lateral cell surface
Intermediate filament
Lysosome
Microtubule
Rough endoplasmic reticulum
Smooth endoplasmic reticulum
Plasma membranes
Basement membrane

Figure 2.5 **Structure of a Generalized Cell.** The organelles are not all drawn to the same scale. Cytoplasm is more densely crowded with organelles than shown here.

TABLE 2.1 **Sizes of Biological Structures in Relation to the Resolution of the Eye, Light Microscope, and Transmission Electron Microscope**

Object	Size
Visible with the Eye (Resolution 70–100 µm)	
Human egg, diameter	100 µm
Visible with the Light Microscope (Resolution 200 nm)	
Most human cells, diameter	10–15 µm
Cilia, length	7–10 µm
Mitochondria, width × length	0.2 × 4 µm
Bacteria *(Escherichia coli),* length	1–3 µm
Microvilli, length	1–2 µm
Visible with the Transmission Electron Microscope (Resolution 0.5 nm)	
Nuclear pores, diameter	30–100 nm
Ribosomes, diameter	15 nm
Globular proteins, diameter	5–10 nm
Plasma membrane, thickness	7.5 nm
DNA molecule, diameter	2.0 nm
Plasma membrane channels, diameter	0.8 nm

little aware of this detail simply because most of these structures are too small to be resolved by the light microscope (table 2.1).

We now regard cells as having the following major components:

- Plasma membrane
- Cytoplasm
  - Cytoskeleton
  - Organelles (including the nucleus)
  - Inclusions
  - Cytosol

The **plasma membrane (cell membrane)** forms the cell's surface boundary. The material enclosed by the plasma membrane is the **cytoplasm,**[7] and the material within the nucleus (usually the cell's largest organelle) is the **nucleoplasm.** The cytoplasm contains the *cytoskeleton,* a supportive framework of protein filaments and tubules; an abundance of *organelles,* diverse structures that perform various metabolic tasks for the cell; and *inclusions,* which are foreign matter or stored cell products. The cytoskeleton, organelles, and inclusions are embedded in a clear gel called the **cytosol.**

The cytosol is also called the **intracellular fluid (ICF).** All body fluids not contained in the cells are collectively called the **extracellular fluid (ECF).** The ECF located between the cells is also called **tissue (interstitial) fluid.** Some other extracellular fluids include blood plasma, lymph, and cerebrospinal fluid.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. State some tenets of the cell theory.
2. What is the main advantage of an electron microscope over a light microscope?
3. Explain why cells cannot grow to unlimited size.
4. Define *cytoplasm, cytosol,* and *organelle.*

2.2 The Cell Surface

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the structure of the plasma membrane;
b. explain the functions of the lipid, protein, and carbohydrate components of the plasma membrane;
c. describe the processes for moving material into and out of a cell; and
d. describe the structure and function of microvilli, cilia, flagella, pseudopods, and cell junctions.

A great deal of human physiology takes place at the cell surface—for example, the binding of signaling molecules such as hormones, the stimulation of cellular activity, the attachment of cells to each other, and the transport of materials into and out of cells. This, then, is where we begin our study of cellular structure and function. Like explorers of a new continent, we will examine the interior only after we have investigated its coastline.

The Plasma Membrane

The plasma membrane defines the boundaries of the cell, governs its interactions with other cells, and controls the passage of materials into and out of the cell. The side that faces the cytoplasm is the **intracellular face** of the membane, and the side that faces outward is the **extracellular face.**

Membrane Lipids

The plasma membrane is an oily, two-layered lipid film with proteins embedded in it (fig. 2.6b). By weight, it is about half lipid and half protein. Since the lipid molecules are smaller and lighter, however, they constitute about 90% to 99% of the molecules in the membrane.

About 75% of the membrane lipid molecules are phospholipids. A **phospholipid** (fig. 2.7) consists of a three-carbon backbone called glycerol, with fatty acid tails attached to two of the carbons and a phosphate-containing head attached to the third. The two fatty acid tails are *hydrophobic*[8] (water-repellent) and the head is *hydrophilic*[9] (attracted to water). The heads of the phospholipids face the ECF and ICF, whereas the tails form the middle of the "sandwich," as far away from the surrounding water as possible. The phospholipids are not stationary but highly fluid—drifting laterally from place to place, spinning on their axes, and flexing their tails.

---

[7] *cyto* = cell; *plasm* = formed, molded

[8] *hydro* = water; *phobic* = fearing, repelled by

[9] *hydro* = water; *philic* = loving, attracted to

About 20% of the lipid molecules are **cholesterol.** Cholesterol has an important impact on the fluidity of the membrane. If there is too little cholesterol, plasma membranes become excessively fragile. People with abnormally low cholesterol levels suffer an increased incidence of strokes because of the rupture of fragile blood vessels. On the other hand, excessively high concentrations of cholesterol in the membrane can inhibit the action of its enzymes and other proteins.

The remaining 5% of the lipids are **glycolipids**—phospholipids with short carbohydrate chains bound to them. Glycolipids occur only on the extracellular face of the membrane. They contribute to the **glycocalyx,** a sugary cell coating discussed later.

An important quality of the plasma membrane is its capacity for self-repair. When a physiologist inserts a probe into a cell, it doesn't pop the cell like a balloon. The probe slips through the oily film and the membrane seals itself around it. When cells take in matter by endocytosis (described later), they pinch off bits of their own membrane, which form bubblelike vesicles in the cytoplasm. As these vesicles pull away from the membrane, they do not leave gaping holes; the lipids immediately flow together to seal the break.


Plasma membrane of upper cell
Intercellular space
Plasma membrane of lower cell
Nuclear envelope
Nucleus
(a)
100 nm
Extracellular fluid
Peripheral protein
Glycolipid
Glycoprotein
Carbohydrate chains
Extracellular face of membrane
Phospholipid bilayer
Channel
Peripheral protein
Transmembrane protein
Cholesterol
Proteins of cytoskeleton
Intracellular face of membrane
Intracellular fluid
(b)

© Dr. Donald Fawcett/Science Source

Figure 2.6 **The Plasma Membrane.** (a) Plasma membranes of two adjacent cells (TEM). Note also that the nuclear envelope is composed of a double membrane, each layer of which is similar to a plasma membrane. (b) Molecular organization of the plasma membrane.



Figure 2.7 **Phospholipid Structure and Symbol.** (a) Molecular model of a phospholipid. (b) Common symbol used to represent phospholipids in diagrams of cell membranes.

Membrane Proteins

Proteins constitute from 1% to 10% of the membrane molecules. They fall into two broad classes called *integral* and *peripheral proteins.* **Integral proteins** penetrate at least partially into the phospholipid bilayer, and if they pass all the way through, they are also called **transmembrane proteins.** They have hydrophilic regions in contact with the cytoplasm and extracellular fluid, and hydrophobic regions that pass back and forth through the membrane lipid like a thread through fabric (fig. 2.8). Most of the transmembrane proteins are **glycoproteins,** which, like glycolipids, have carbohydrate chains linked to them and help form the glycocalyx. **Peripheral proteins** are those that do not protrude into the phospholipid layer but adhere to either face of the membrane, usually the intracellular face. Some transmembrane proteins drift about freely in the plasma membrane, while others are anchored to the cytoskeleton and thus held in one place. Most peripheral proteins are anchored to the cytoskeleton and associated with transmembrane proteins.

The functions of membrane proteins are very diverse and are among the most interesting aspects of cell physiology. These proteins serve in the following roles:

- **Receptors** (fig. 2.9a). Cells communicate with each other by chemical signals such as hormones and neurotransmitters. Some of these messengers (epinephrine, for example) cannot enter their target cells but can only "knock on the door" with their message. They bind to a membrane protein called a **receptor,** and the receptor triggers physiological changes inside the cell. Some of these have a dual function as receptor and transport proteins—they bind chemicals from the extracellular fluid and transport them into the cell. Others function as both receptors and gated channels, binding a chemical messenger and opening to allow ions into or out of the cell through the receptor protein itself. This is the mechanism by which nerve cells stimulate muscle fibers to contract.
- **Enzymes** (fig. 2.9b). Some membrane proteins are enzymes that carry out chemical reactions at the cell surface. Some of these break down chemical messengers after the message has been received. Enzymes in the plasma membranes of intestinal cells carry out the final stages of starch and protein digestion.
- **Channel proteins** (fig. 2.9c). Some membrane proteins have tunnels through them that allow water and hydrophilic solutes



Figure 2.8 **Transmembrane Proteins.** A transmembrane protein has hydrophobic regions embedded in the phospholipid bilayer and hydrophilic regions projecting into the extracellular and intracellular fluids. The protein may cross the membrane once (left) or multiple times (right). The intracellular "domain" of the protein is often anchored to the cytoskeleton by peripheral proteins.

• *What other regions of the protein on the right would be hydrophilic in addition to the one labeled?*



(a) Receptor A receptor that binds to chemical messengers such as hormones sent by other cells

(b) Enzyme An enzyme that breaks down a chemical messenger and terminates its effect

(c) Channel A channel protein that is constantly open and allows solutes to pass into and out of the cell

(d) Gated channel A gate that opens and closes to allow solutes through only at certain times

(e) Cell-identity marker A glycoprotein acting as a cell-identity marker distinguishing the body's own cells from foreign cells

(f) Cell-adhesion molecule (CAM) A cell-adhesion molecule (CAM) that binds one cell to another

Figure 2.9 Some Functions of Plasma Membrane Proteins.

to enter or leave a cell. These are called **channel proteins.** Some channels are always open, whereas others, called **gates** or **gated channels** (fig. 2.9d), open or close when they are stimulated and thus allow things to enter or leave the cell only at appropriate times. Membrane gates are responsible for firing of the heart's pacemaker, muscle contraction, and most of our sensory processes, among other functions.

- **Transport proteins** (see fig. 2.10c, d). Some membrane proteins, called **transport proteins (carriers),** don't merely open to allow substances through—they actively bind to a substance on one side of the membrane and release it on the other side. Carriers are responsible for transporting glucose, amino acids, sodium, potassium, calcium, and many other substances into and out of cells.
- **Cell-identity markers** (fig. 2.9e). The glycoproteins and glycolipids of the membrane are like genetic identification tags, unique to an individual (or to identical twins). They enable the body to distinguish what belongs to it from what does not—especially from foreign invaders such as bacteria and parasites.
- **Cell-adhesion molecules** (fig. 2.9f). Cells adhere to each other and to extracellular material through membrane proteins called **cell-adhesion molecules (CAMs).** With few exceptions (such as blood cells and metastasizing cancer cells), cells do not grow or survive normally unless they are mechanically linked to the extracellular material. Special events such as sperm–egg binding and the binding of an immune cell to a cancer cell also require CAMs.

Membrane Transport

One of the most important functions of the plasma membrane is to control the passage of materials into and out of the cell. Figure 2.10 illustrates three methods of movement through plasma membranes, as well as filtration, an important mode of transport across the walls of certain blood vessels.

Filtration

Filtration (fig. 2.10a) is a process in which a physical pressure forces fluid through a membrane, like the weight of water forcing it through the paper filter in a drip coffeemaker. In the body, the prime example of filtration is blood pressure forcing fluid to seep through the walls of the blood capillaries into the tissue fluid. This is how water, salts, organic nutrients, and other solutes pass from the bloodstream to the tissue fluid, where they can get to the cells surrounding a blood vessel. This is also how the kidneys filter wastes from the blood. Capillaries hold back large particles such as blood cells and proteins. In most cases, water and solutes filter through narrow gaps between the capillary cells. In some cases, however, the cells have large **filtration pores** through them, like the holes in a slice of Swiss cheese, allowing for more rapid filtration of large solutes such as protein hormones.

Simple Diffusion

Simple diffusion (fig. 2.10b) is the net movement of particles from a place of high concentration to a place of lower concentration—in other words, *down a concentration gradient.* Diffusion is how oxygen and steroid hormones enter cells and potassium ions leave, for example. The cell does not have to expend any energy to achieve this; all molecules are in spontaneous random motion, and this alone provides the energy for their diffusion through space. Molecules diffuse through air, liquids, and solids. They can penetrate both living membranes (the plasma membrane) and nonliving ones (such as dialysis tubing and cellophane) if the membrane has large enough gaps or pores. We say that the plasma membrane is *selectively permeable* because it lets some particles through but holds back larger ones. Nonpolar solutes such as oxygen and carbon dioxide, and hydrophobic substances such


Capillary blood pressure forces water and small solutes through clefts between cells.
Solute
Water
Capillary wall
Red blood cell
Clefts hold back blood cells and other large particles.
High concentration
Solute moves down its concentration gradient
Low concentration
Lipid-soluble solutes diffuse through membrane phospholipid.
Water-soluble solutes diffuse through channel proteins.

(a) Filtration **(b) Simple diffusion**


Solute binds to receptor site on transport protein.
Protein changes shape.
Protein releases solute on other side of membrane.
High concentration
Solute moves down its concentration gradient.
Low concentration
Receptor site
Solute binds to receptor site on transport protein.
Protein breaks down ATP. P_i binds to protein and induces shape change.
Protein releases solute to other side of membrane and releases P_i.
High concentration
Solute moves up its concentration gradient.
Low concentration
P_i
ATP
ADP
P_i

(c) Facilitated diffusion **(d) Active transport**

Figure 2.10 Modes of Membrane Transport.

as steroids, diffuse through the lipid regions of the plasma membrane; hydrophilic solutes such as salts, however, can diffuse only through the water-filled protein channels of the membrane.

Osmosis

Osmosis[10] (oz-MO-sis) is the net flow of water through a selectively permeable membrane from the "more watery" side (the one with less dissolved matter) to the "less watery" side (with more dissolved matter). Water molecules tend to cling to particles of dissolved matter and resist going back through the membrane in the opposite direction—hence the net accumulation of water on the side with more solute. An exception to this is **reverse osmosis,** in which a physical force drives water back to the more dilute side of the membrane. This principle is used to desalinate seawater, converting it to drinkable freshwater, in arid regions and ships at sea. In the human body, the force generated by the heartbeat causes reverse osmosis at the blood capillaries, driving water out of the blood and into the tissue fluid; but where the blood pressure is lower, capillaries absorb tissue fluid by osmosis. Many cells have membrane channel proteins called **aquaporins** that allow water to pass easily through the membrane. Imbalances in osmosis underlie such problems as diarrhea, constipation, and edema. Osmosis is also a vital consideration in intravenous fluid therapy and kidney dialysis.

Facilitated Diffusion

The next two processes, facilitated diffusion and active transport, are called *carrier-mediated transport* because they employ transport proteins in the plasma membrane. **Facilitated**[11] **diffusion** (fig. 2.10c) can be defined as the movement of a solute through a membrane, down its concentration gradient, with the aid of a carrier. The carrier transports solutes such as glucose that cannot pass through the membrane unaided. It binds to a particle on one side of a membrane, where the solute is more concentrated, and releases it on the other side, where it is less concentrated. The process requires no expenditure of metabolic energy by the cell. One use of facilitated diffusion is to absorb the sugars and amino acids from digested food.

---

[10] *osm* = push, thrust; *osis* = process

[11] *facil* = easy

Active Transport

Active transport (fig. 2.10d) is the carrier-mediated transport of a solute through a unit membrane *up its concentration gradient,* with the expenditure of energy provided by adenosine triphosphate (ATP). ATP is essential to this process because moving particles up a gradient requires an energy input, like getting a wagon to roll uphill. If a cell dies and stops producing ATP, active transport ceases immediately. One use of active transport is to pump calcium out of cells. Calcium is already more concentrated in the ECF than in the ICF, so pumping even more calcium into the ECF is an "uphill" movement.

An especially well-known active transport process is the **sodium–potassium (Na^+–K^+) pump,** which binds three sodium ions from the ICF and ejects them from the cell, then binds two potassium ions from the ECF and releases these into the cell. The Na^+–K^+ pump plays roles in controlling cell volume; generating body heat; maintaining the electrical excitability of your nerves, muscles, and heart; and providing energy for other transport pumps to draw upon in moving such solutes as glucose through the plasma membrane. About half of the calories that you "burn" every day are used just to operate your Na^+–K^+ pumps.

Vesicular Transport

All of the processes discussed up to this point move molecules or ions individually through the plasma membrane. In **vesicular transport,** however, cells move much larger particles or droplets of fluid through the membrane in bubblelike *vesicles.* Vesicular processes that bring matter into a cell are called **endocytosis**[12] (EN-doe-sy-TOE-sis), and those that release material from a cell are called **exocytosis**[13] (EC-so-sy-TOE-sis). Like active transport, all forms of vesicular transport require ATP. There are three forms of endocytosis: *phagocytosis, pinocytosis,* and *receptor-mediated endocytosis* (fig. 2.11).

Pinocytosis[14] (PIN-oh-sy-TOE-sis), or "cell drinking," occurs in all human cells. In this process, dimples form in the plasma membrane and progressively sink in until they pinch off as *pinocytotic vesicles* containing droplets of ECF (fig. 2.11a). Kidney tubule cells use this method to reclaim the small amount of protein that filters out of the blood, thus preventing the protein from being lost in the urine.

Receptor-mediated endocytosis (fig. 2.11b) is more selective. It enables a cell to take in specific molecules from the ECF with a minimum of unnecessary fluid. Molecules in the ECF bind to specific receptor proteins on the plasma membrane. The receptors then cluster together and the membrane sinks in at this point, creating a pit. The pit soon pinches off to form a vesicle in the cytoplasm. Cells use receptor-mediated endocytosis to absorb cholesterol and insulin from the blood. Hepatitis, polio, and AIDS viruses trick our cells into admitting them by receptor-mediated endocytosis.

In **phagocytosis**[15] (FAG-oh-sy-TOE-sis), or "cell eating," a cell reaches out with footlike extensions called *pseudopods* (see fig. 2.14), surrounds a particle such as a bacterium or a bit of cell debris, and engulfs it, taking it into a cytoplasmic vesicle called a *phagosome* to be digested. Phagocytosis is carried out especially by white blood cells and macrophages, which are described in chapter 3.



(a) Pinocytosis



(b) Receptor-mediated endocytosis



(c) Exocytosis

Figure 2.11 Modes of Vesicular Transport. (a) Pinocytosis. A cell imbibing droplets of extracellular fluid. (b) Receptor-mediated endocytosis. The Ys in the plasma membrane are membrane receptors that bind a solute in the extracellular fluid, then cluster together. The membrane sinks in at that point until a vesicle pinches off into the cytoplasm bearing the receptors and bound solute. (c) Exocytosis. A cell releasing a secretion or waste product. See also phagocytosis in figure 2.14 for a fourth mode of vesicular transport.

Exocytosis (fig. 2.11c) is the process of discharging material from a cell. It is used, for example, by digestive glands to secrete enzymes, by breast cells to secrete milk, and by sperm cells to release enzymes for penetrating an egg. It resembles endocytosis in reverse. A *secretory vesicle* in the cell migrates to the surface and fuses with the plasma membrane. A pore opens up that releases the products from the cell, and the empty vesicle usually becomes part of the plasma membrane. In addition to releasing cell products, exocytosis is the cell's way of replacing the bits of membrane removed by endocytosis.

---

[12] *endo* = into; *cyt* = cell; *osis* = process
[13] *exo* = out of; *cyt* = cell; *osis* = process
[14] *pino* = drinking; *cyt* = cell; *osis* = process
[15] *phago* = eating; *cyt* = cell; *osis* = process

Extensions of the Cell Surface

Most cells have surface extensions of one or more types called *microvilli, cilia, flagella,* and *pseudopods.* These aid in absorption, movement, and sensory processes.

Microvilli

Microvilli[16] (MY-cro-VIL-eye; singular, *microvillus*) are extensions of the plasma membrane that serve primarily to increase its surface area (fig. 2.12). They are best developed in cells specialized for absorption, such as the epithelial cells of the intestines and kidney tubules. The small intestine has about 200 million microvilli per square millimeter, with about 3,000 on the surface of each absorptive cell. They give such cells far more absorptive surface area than they would have if their apical surfaces were flat. On many cells, microvilli are little more than tiny bumps on the plasma membrane. On cells of the taste buds and inner ear, they are well developed but serve sensory rather than absorptive functions.

Individual microvilli cannot be distinguished very well with the light microscope because they are only 1 to 2 µm long. On some cells, they are very dense and appear as a fringe called the **brush border.** With the scanning electron microscope, they resemble a deep-pile carpet. With the transmission electron microscope, microvilli typically look like finger-shaped projections of the cell surface. They show little internal structure, but often have a bundle of stiff supportive filaments of a protein called *actin.* Actin filaments attach to the inside of the plasma membrane at the tip of the microvillus; at its base, they extend a little way into the cell and anchor the microvillus to a protein mesh called the *terminal web.* When tugged by another protein in the cytoplasm, actin can shorten a microvillus to milk its absorbed contents downward into the cell.

Cilia

Cilia (SIL-ee-uh; singular, *cilium*[17]) are hairlike processes about 7 to 10 µm long. Nearly every cell has a solitary, nonmotile *primary cilium* a few micrometers long. Its function in some cases is still a mystery, but apparently many of them are sensory, serving as the cell's "antenna" for monitoring nearby conditions. The light-absorbing parts of the retinal cells in the eye are modified primary cilia; in the inner ear, they play a role in the senses of motion and balance; and in kidney tubules, they are thought to monitor fluid flow. Odor molecules bind to nonmotile cilia on the sensory cells of the nose. Defects in the development, structure, or function of cilia—especially the nonmotile primary cilia—are responsible for several hereditary diseases called *ciliopathies*.

---

[16] *micro* = small; *villi* = hairs

[17] *cilium* = eyelash



© Don W. Fawcett/Science Source

© Biophoto Associates/Science Source

Figure 2.12 Microvilli and the Glycocalyx. The microvilli are anchored by bundles of actin microfilaments, which occupy the core of each microvillus and project into the cytoplasm. (a) Longitudinal sections, perpendicular to cell surface. (b) Cross sections.



© SPL/Science Source

© Biophoto Associates/Science Source

Figure 2.13 **The Structure of Cilia.** (a) Epithelium of the uterine (fallopian) tube (SEM). The shorter, mucus-secreting cells between the ciliated cells show bumpy microvilli on their surfaces. (b) Three-dimensional structure of a cilium and its basal body. (c) Cross section of cilia and microvilli (TEM). (d) Cross-sectional structure of a cilium. The two central microtubules of the ciliary shaft stop at the cell surface and do not extend into the basal body.

- *Describe as many structural differences between cilia and microvilli as you can.*

Motile cilia occur in only a few organs, mainly in the respiratory tract, uterine (fallopian) tubes, internal cavities of the brain and spinal cord, and some male reproductive ducts. However, they are very abundant where they do occur; ciliated cells typically have 50 to 200 cilia each (fig. 2.13a). These cilia beat in synchronized waves that sweep across the surface of an epithelium, always in the same direction, moving substances such as fluid, mucus, and egg cells.

Cilia possess a central core called the **axoneme**[18] (ACK-so-neem), an orderly array of thin protein cylinders called *microtubules.* In motile cilia, there are two central microtubules surrounded by a ring of nine microtubule pairs arranged like a Ferris wheel (fig. 2.13b–d). The central microtubules stop at the cell surface, but the peripheral microtubules continue a short distance into the cell as part of a **basal body** that anchors the cilium. In each pair of peripheral microtubules, one tubule has paired *dynein* (DINE-een) *arms* along its length. **Dynein,**[19] a *motor protein,* uses energy from ATP to "crawl" up the adjacent pair of microtubules. When microtubules on the front of the cilium crawl up the microtubules behind them, the cilium bends toward the front. Nonmotile primary cilia lack the two central microtubules and the dynein arms.

---

[18] *axo* = axis; *neme* = thread

[19] *dyn* = power, energy; *in* = protein

Flagella

There is only one functional **flagellum**[20] (fla-JEL-um) in humans—the whiplike tail of a sperm. It is much longer than a cilium and has an identical axoneme, but between the axoneme and plasma membrane it also has a complex sheath of coarse cytoskeletal filaments that stiffen the tail and give it more propulsive power.

Apply What You Know

Kartagener syndrome is a hereditary disease in which dynein is lacking from cilia and flagella. How do you think Kartagener syndrome will affect a man's ability to father a child? How might it affect his respiratory health? Explain your answers.

Pseudopods

Pseudopods[21] (SOO-do-pods) are cytoplasm-filled extensions of the cell varying in shape from fine, filamentous to blunt, fingerlike processes (fig. 2.14). Unlike the other three kinds of surface extensions, they change continually. Some form anew as the cell surface bubbles outward and cytoplasm flows into a lengthening pseudopod, while others are retracted into the cell and disappear.

The freshwater organism *Amoeba* furnishes a familiar example of pseudopods, which it uses for locomotion and food capture. White blood cells called *neutrophils* crawl about like amebae by means of fingerlike pseudopods, and when they encounter a bacterium or other foreign particle, they reach out with their pseudopods to surround and engulf it. Macrophages—tissue cells derived from certain white blood cells—reach out with thin filamentous pseudopods to snare bacteria and "reel them in" to be digested by the cell. Like little janitors, macrophages therefore keep our tissues cleaned up. Blood platelets reach out with pseudopods to adhere to each other and to the walls of damaged blood vessels, forming plugs that temporarily halt bleeding.



Figure 2.14 **Pseudopods.** (a) *Amoeba*, a freshwater organism that crawls and captures food by means of pseudopods. (b) A neutrophil (white blood cell) that similarly uses pseudopods for locomotion and capturing bacteria. The three bacteria in red are being surrounded by pseudopods as part of the process of engulfing them by phagocytosis. (c) A macrophage extending filamentous pseudopods to snare and "reel in" bacteria.

The Glycocalyx

All of our cells are essentially sugar-coated. They have a fuzzy surface coat called the **glycocalyx**[22] (GLY-co-CAY-licks), composed of short chains of sugars belonging to the membrane glycolipids and glycoproteins. The glycocalyx has multiple functions. It cushions the plasma membrane and protects it from physical and chemical injury, somewhat like the Styrofoam "peanuts" in a shipping carton. It functions in cell identity and thus in the body's ability to distinguish its own healthy cells from diseased cells, invading organisms, and transplanted tissues. Human blood types and transfusion compatibility are determined by the glycocalyx. The glycocalyx also includes the cell-adhesion molecules described earlier and, thus, helps to bind tissues together and enables a sperm to bind to an egg and fertilize it.

Cell Junctions

Also at the cell surface are certain **cell junctions** that link cells together and attach them to the extracellular material. Such attachments enable cells to grow and divide normally, resist stress, communicate with each other, and control the movement of substances through the gaps between cells. Without them, cardiac muscle cells would pull apart when they contracted, and every swallow of food would scrape away the lining of the esophagus. We will examine three types of junctions—*tight junctions, desmosomes,* and *gap junctions* (fig. 2.15). Each type serves a different purpose, and two or more types often occur in a single cell.

Tight Junctions

A **tight junction** completely encircles an epithelial cell near its apical surface and joins it tightly to the neighboring cells like the plastic harness on a six-pack of soda cans. At a tight junction, the plasma membranes of two adjacent cells come very close together and are linked by transmembrane cell adhesion proteins. These proteins seal off the intercellular space and make it difficult for substances to pass between the cells. In the stomach and intestines, for example, tight junctions prevent digestive juices from seeping between epithelial cells and digesting the underlying connective tissue. They also help to prevent intestinal bacteria from invading the tissues, and they ensure that most digested nutrients pass *through* the epithelial cells and not *between* them.

Desmosomes

A **desmosome**[23] (DEZ-mo-some) is a protein patch that holds cells tightly together at a specific point. We can compare a tight junction and a desmosome, respectively, to a zipper and a snap on a pair of jeans. Desmosomes are not continuous and therefore cannot prevent substances from passing around them and going between cells. They

---

[20] *flagellum* = whip
[21] *pseudo* = false; *pod* = foot
[22] *glyco* = sugar; *calyx* = cup, vessel
[23] *desmo* = band, bond, ligament; *som* = body


Intercellular space
Plasma membrane
Cell-adhesion proteins
(a) Tight junction
Intercellular space
Cell-adhesion proteins
Plaque
Intermediate filaments of cytoskeleton
(b) Desmosome
Proteins
Connexon
Pore
(c) Gap junction
Basement membrane
(d) Hemidesmosome

Figure 2.15 **Types of Cell Junctions.**
- *Which of these junctions allows material to pass from one cell directly into the next?*

serve to keep cells from pulling apart and thus enable a tissue to resist mechanical stress. Desmosomes are common in the epidermis, the epithelium of the uterine cervix, other epithelia, and cardiac muscle. Hooklike J-shaped proteins approach the cell surface from within and penetrate into a thick protein plaque on the inner face of the plasma membrane, and then the short arm of the J turns back into the cell—thus anchoring the plaque to the cytoskeleton. Proteins of the plaque are linked to transmembrane proteins which, in turn, are linked to transmembrane proteins of the next cell, forming a zone of strong cell adhesion. Each cell mirrors the other and contributes half of the desmosome. Such connections among neighboring cells create a strong structural network that binds cells together throughout the tissue (see Deeper Insight 2.1). The basal cells of an epithelium are similarly linked to the underlying basement membrane by half desmosomes called *hemidesmosomes,* so an epithelium cannot easily peel away from the underlying tissue.

DEEPER INSIGHT 2.1

When Desmosomes Fail

We often get our best insights into the importance of a structure from the dysfunctions that occur when it breaks down. Desmosomes are destroyed in a disease called *pemphigus vulgaris*[24] (PEM-fih-gus vul-GAIR-iss), in which misguided antibodies (defensive proteins) called *autoantibodies* attack the desmosome proteins, especially in the skin. The resulting breakdown of desmosomes between the epidermal cells leads to widespread blistering of the skin and oral mucosa, loss of tissue fluid, and sometimes death. The condition can be controlled with drugs that suppress the immune system, but such drugs compromise the body's ability to fight off infections.

Apply What You Know

Why would desmosomes not be suitable as the sole type of cell junction between epithelial cells of the stomach?

---

[24] *pemphigus* = blistering; *vulgaris* = common

Gap Junctions

A **gap (communicating) junction** is formed by a *connexon,* which consists of six transmembrane proteins arranged in a ring, somewhat like the segments of an orange, surrounding a central water-filled channel. Ions, glucose, amino acids, and other small solutes can diffuse through the channel directly from the cytoplasm of one cell into the next. In the human embryo, nutrients pass from cell to cell through gap junctions until the circulatory system forms and takes over the role of nutrient distribution. In cardiac muscle, gap junctions allow electrical excitation to pass directly from cell to cell so that the cells contract in near unison.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

5. Generally speaking, what sort of substances can enter a cell by diffusing through its phospholipid membrane? What sort of substances must enter primarily through the channel proteins?
6. Compare the structure and function of transmembrane proteins with peripheral proteins.
7. What membrane transport processes get all the necessary energy from the spontaneous movement of molecules? What ones require ATP as a source of energy? What membrane transport processes are carrier mediated? What ones are not?
8. Identify several reasons why the glycocalyx is important to human survival.
9. How do microvilli and cilia differ in structure and function?
10. What are the functional differences between tight junctions, gap junctions, and desmosomes?

2.3 The Cell Interior

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the cytoskeleton and its functions;
b. list the main organelles of a cell and explain their functions; and
c. give some examples of cell inclusions and explain how inclusions differ from organelles.

We now probe more deeply into the cell to study its internal structures. These are classified into three groups—cytoskeleton, organelles, and inclusions—all embedded in the clear, gelatinous cytosol. If we think of a cell as being like an office building, the cytoskeleton would be like the steel beams and girders that hold it up and define its shape and size; the plasma membrane and its channels would be the building's exterior walls and doors; and organelles would be the interior rooms that divide the building into compartments with different functions.

The Cytoskeleton

The **cytoskeleton** is a network of protein filaments and tubules that structurally support a cell, determine its shape, organize its contents, direct the movement of substances within the cell, and contribute to movements of the cell as a whole. It can form a very dense supportive web in the cytoplasm (fig. 2.16). It is connected to transmembrane proteins of the plasma membrane and they, in turn, are connected to proteins external to the cell, so there is a strong structural continuity from extracellular material to the cytoplasm. Cytoskeletal elements may even connect to chromosomes in the nucleus, enabling physical tension on a cell to move nuclear contents and mechanically stimulate genetic function.

The cytoskeleton is composed of *microfilaments, intermediate filaments,* and *microtubules.* **Microfilaments (thin filaments)** are about 6 nm thick and are made of the protein actin. They form a fibrous **terminal web (membrane skeleton)** on the cytoplasmic side of the plasma membrane. The lipids of the plasma membrane are spread out over the terminal web like butter on a slice of bread. The web, like the bread, provides physical support, whereas the lipids, like butter, provide a permeability barrier. It is thought that, without this support by the terminal web, the lipids would break up into little droplets and the plasma membrane would not be able to hold together. As described earlier, actin microfilaments also form the supportive cores of the microvilli and play a role in cell movement. Muscle cells especially are packed with actin, which is pulled upon by the motor protein myosin to make muscles contract.

Intermediate filaments (8–10 nm in diameter) are thicker and stiffer than microfilaments. They give a cell its shape, resist stress, and participate in the junctions that attach cells to their neighbors. In epidermal cells, they are made of the tough protein *keratin* and occupy most of the cytoplasm. They are responsible for the strength of hair and fingernails.

A **microtubule** (25 nm in diameter) is a hollow cylinder made of 13 parallel strands called *protofilaments.* Each protofilament is a long chain of globular proteins called *tubulin* (fig. 2.17). Microtubules radiate from the centrosome (see p. 46) and hold organelles in place, form bundles that maintain cell shape and rigidity, and act somewhat like railroad tracks to guide organelles and molecules to specific destinations in a cell. They form the ciliary and flagellar basal bodies and axonemes described earlier, and as discussed later in relation to organelles and mitosis, they form the centrioles and mitotic spindle involved in cell division. Microtubules are not permanent structures. They appear and disappear moment by moment as tubulin molecules assemble into a tubule and then suddenly break apart again to be used somewhere else in the cell (fig. 2.16a). The double and triple sets of microtubules in cilia, flagella, basal bodies, and centrioles, however, are more stable.


Microvilli
Microfilaments
Terminal web
Lysosome
Kinesin
Microtubule
Intermediate filaments
Microtubule in the process of assembly
Nucleus
Secretory vesicle in transport
Desmosome
Intermediate filaments
Centrosome
Microtubule undergoing disassembly
Mitochondrion
(a)
Basement membrane
Hemidesmosome
(b)
15 µm

Figure 2.16 The Cytoskeleton. (a) Components of the cytoskeleton. Few organelles are shown in order to emphasize the cytoskeleton. Note that all microtubules radiate from the centrosome; they often serve as tracks for motor proteins transporting organelles. (b) Cells with their cytoskeletons labeled with fluorescent antibodies, photographed through a fluorescence microscope. The density of a typical cytoskeleton far exceeds even that shown in part (a).

- *What cytoskeletal structures shown here also play structural roles in microvilli, cilia, and flagella?*

© Dr. Torsten Wittmann/Science Source



Figure 2.17 **Microtubules.** (a) A single microtubule is composed of 13 protofilaments. Each protofilament is a helical chain of globular proteins called tubulin. (b) One of the nine microtubule pairs of a cilium. (c) One of the nine microtubule triplets of a centriole.

Organelles

The minute, metabolically active structures within a cell are called **organelles** (literally, "little organs") because they are to the cell what organs are to the body—structures that play individual physiological roles in the survival of the whole (see fig. 2.5). A cell may have 10 billion protein molecules, some of which are powerful enzymes with the potential to destroy the cell if they are not contained and isolated from other cellular components. You can imagine the enormous problem of keeping track of all this material, directing molecules to the correct destinations, and maintaining order against the incessant tug of disorder. Cells maintain order partly by compartmentalizing their contents in organelles. Figures 2.18 and 2.19 show the major organelles.

The Nucleus

The **nucleus** (fig. 2.18) is the largest organelle and usually the only one clearly visible with the light microscope. It contains the cell's chromosomes and is therefore the genetic control center of cellular activity. Granular organelles called *ribosomes* are produced here, and the early steps in protein synthesis occur here under the direction of the genes. Most cells have only one nucleus,



Figure 2.18 **The Nucleus.** (a) Cutaway view to show surface features and contents of nucleoplasm. (b) Detail of a nuclear pore complex, formed by a ring of eight proteins connected by spokes to a central plug.

but there are exceptions. Mature red blood cells have none; they are *anuclear.*[25] A few cell types are *multinucleate*—having 2 to 50 nuclei—including some liver cells, skeletal muscle cells, and certain bone-dissolving cells.

The nucleus is usually spheroidal to elliptical in shape and averages about 5 μm in diameter. It is surrounded by a **nuclear envelope** consisting of two parallel membranes. The envelope is perforated with **nuclear pores,** about 30 to 100 nm in diameter, formed by a ring-shaped *nuclear pore complex* of eight proteins. These proteins regulate molecular traffic into and out of the nucleus and bind the two membranes together. The inside of the nuclear envelope is lined by a web of intermediate filaments, called the **nuclear lamina,** like a cage enclosing the DNA.

The material within the nucleus is called the *nucleoplasm.* Most of it consists of finely dispersed, granular filaments called **chromatin** (CRO-muh-tin), visible only with the TEM. Chromatin is composed of a complex of proteins and DNA, the latter constituting the cell's genes. When cells prepare to divide, the chromatin coils and condenses into short thick rods visible with the LM, and we can see that it consists of (usually) 46 separate bodies, the **chromosomes**[26] (see fig. 2.24). The nuclei of nondividing cells also usually exhibit one or more dense masses called **nucleoli** (singular, *nucleolus*), where subunits of the ribosomes are made before they are transported out to the cytoplasm.

Endoplasmic Reticulum

The term *endoplasmic reticulum (ER)* literally means "little network within the cytoplasm." It is a system of interconnected channels called **cisternae**[27] (sis-TUR-nee) enclosed by a membrane (fig. 2.19a). In areas called **rough endoplasmic reticulum,** the network consists of parallel, flattened cisternae covered with ribosomes, which give it its rough or granular appearance. The rough ER is continuous with the outer membrane of the nuclear envelope (see fig. 2.18), and adjacent cisternae are connected by perpendicular bridges. In areas called **smooth endoplasmic reticulum,** the membrane lacks ribosomes, the cisternae are more tubular in shape, and they branch more extensively. The cisternae of the smooth ER are continuous with those of the rough ER, so the two are different parts of the same cytoplasmic network.

The endoplasmic reticulum synthesizes steroids and other lipids, detoxifies alcohol and other drugs, and manufactures all of the membranes of the cell. Rough ER produces the phospholipids and proteins of the plasma membrane. It also synthesizes proteins that are either secreted from the cell or packaged in organelles called *lysosomes.* Rough ER is most abundant in cells that synthesize large amounts of protein, such as antibody-producing cells and cells of the digestive glands.

Most cells have only a scanty smooth ER, but it is relatively abundant in cells that engage extensively in detoxification, such as liver and kidney cells. Long-term abuse of alcohol, barbiturates, and other drugs leads to tolerance partly because the smooth ER proliferates and detoxifies the drugs more quickly. Smooth ER is also abundant in cells that synthesize steroid hormones, for example in the testes and ovaries. Skeletal and cardiac muscle contain extensive networks of modified smooth ER called *sarcoplasmic reticulum,* which releases calcium to trigger muscle contraction and stores the calcium between contractions.

Ribosomes

Ribosomes are small granules of protein and ribonucleic acid (RNA) found in the cytosol, on the outer surfaces of the rough ER and nuclear envelope, in the nucleoli, and in mitochondria. Ribosomes "read" coded genetic messages (messenger RNA) from the nucleus and assemble amino acids into proteins specified by the code. The unattached ribosomes found scattered throughout the cytoplasm make enzymes and other proteins for use within the cell. The ribosomes attached to the rough ER make proteins that will either be packaged in lysosomes or, in cases such as digestive enzymes, secreted from the cell.

Golgi Complex

The **Golgi**[28] (GOAL-jee) **complex** is a small system of cisternae that synthesizes carbohydrates and certain lipids and puts the finishing touches on protein and glycoprotein synthesis (fig. 2.19b). The complex resembles a stack of pita bread. Typically, it consists of about six cisternae, slightly separated from each other, each of them a flattened, slightly curved sac with a swollen rim.

Figure 2.20 shows the functional interaction between the ribosomes, endoplasmic reticulum, and Golgi complex. Ribosomes link amino acids together in a genetically specified order to make a particular protein. This new protein threads its way into the cisterna of the rough ER, where enzymes trim and modify it. The altered protein is then shuffled into a little **transport vesicle,** a spheroidal organelle that buds from the ER and carries the protein to the nearest cisterna of the Golgi complex. The Golgi complex sorts these proteins, passes them along from one cisterna to the next, cuts and splices some of them, adds carbohydrates to some of them, and finally packages the proteins in membrane-bounded **Golgi vesicles.** These vesicles bud off the rim of the cisterna farthest from the ER, like the warm wax globules of a lava lamp. They are seen in abundance in the neighborhood of the Golgi complex.

Some Golgi vesicles become lysosomes, discussed shortly; some migrate to the plasma membrane and fuse with it, contributing fresh protein and phospholipid to the membrane; and some become **secretory vesicles** that store a cell product, such as breast milk protein, mucus, or digestive enzymes, for later release by exocytosis.

Proteasomes

Ribosomes manufacture numerous proteins for intracellular use, but these proteins cannot linger in the cell forever. When

---

[25] *a* = without; *nucle* = nucleus

[26] *chromo* = color; *some* = body

[27] *cistern* = reservoir

[28] Camillo Golgi (1843–1926), Italian histologist


Rough endoplasmic reticulum
Ribosomes
Cisternae
Smooth endoplasmic reticulum
Cisterna
Golgi vesicle

(a) Endoplasmic reticulum

(b) Golgi complex


Tag
Protein to be degraded
Unfolded protein
Proteasome
Degraded protein
Protein crystal

(c) Proteasome

(d) Lysosomes


Cristae
Matrix
Protein link
Longitudinal view
Microtubules
Cross section

(e) Mitochondrion

(f) Centrioles

Figure 2.19 **Major Cytoplasmic Organelles.** (a) Endoplasmic reticulum, showing rough and smooth regions. (b) Golgi complex and Golgi vesicles. (c) Proteasome degrading a protein. (d) Lysosomes. (e) Mitochondrion. (f) Centrioles. Centrioles are typically seen in pairs, perpendicular to each other; thus, electron micrographs often show one in longitudinal section and the other in cross section, as depicted here.


① Protein formed by ribosomes on rough ER.
② Protein packaged into transport vesicle, which buds from ER.
③ Transport vesicles fuse into clusters that unload protein into Golgi complex.
④ Golgi complex modifies protein structure.
⑤ Golgi vesicle containing finished protein is formed.
⑥ Secretory vesicle releases protein by exocytosis.
Nucleus
Ribosomes
Rough ER
Golgi complex
Lysosome

Figure 2.20 **Organelle Collaboration in Protein Production.** The steps in protein synthesis and secretion are numbered 1 through 6. (1) Acting on instructions from the nucleus, each ribosome assembles amino acids in the correct sequence to make a particular protein. The protein is threaded into the cisterna of the rough ER as it is synthesized. The rough ER cuts and splices proteins and may make other modifications. (2) The rough ER packages the modified protein into transport vesicles that carry it to the Golgi complex. (3) The transport vesicle fuses with a cisterna of the Golgi complex and unloads its protein. (4) The Golgi complex may further modify the protein. (5) The Golgi complex buds off Golgi vesicles containing the finished protein. (6) Some Golgi vesicles become secretory vesicles, which travel to the plasma membrane and release the product by exocytosis. AP|R

their job is done, they must be disposed of. Cells also need to rid themselves of damaged and nonfunctional proteins and foreign proteins introduced by such means as viral infections. The job of protein disposal is handled by organelles called **proteasomes,** which are themselves composed of hollow cylindrical complexes of protein (fig. 2.19c). The cell tags undesirable proteins for destruction and transports them to a proteasome; enzymes of the proteasome unwind them and break them down into amino acids. Proteasomes degrade more than 80% of a cell's proteins.

Lysosomes

Another organelle designed for destroying things is the **lysosome**[29] (LY-so-some) (fig. 2.19d), a package of enzymes enclosed in a membrane. Although often round or oval, lysosomes are extremely variable in shape. When viewed with the TEM, they often exhibit dark gray contents devoid of structure, but sometimes show crystals or parallel layers of protein. At least 50 lysosomal enzymes have been identified. They break down proteins, nucleic acids, carbohydrates, phospholipids, and other substances. White blood cells called *neutrophils* phagocytize bacteria and digest them with the enzymes of their lysosomes. Lysosomes also digest and dispose of surplus, nonvital, and worn-out organelles; this process is called *autophagy*[30] (aw-TOFF-uh-jee). They also aid in a process of "cell suicide" called *apoptosis* (AP-op-TOE-sis), or *programmed cell death,* in which cells that are no longer needed undergo a prearranged death. The uterus, for example, weighs about 900 g at full-term pregnancy and, through apoptosis, shrinks to 60 g within 5 or 6 weeks after birth.

---

[29] *lyso* = loosen, dissolve; *some* = body

Peroxisomes

Peroxisomes (not illustrated) resemble lysosomes but contain different enzymes and are not produced by the Golgi complex. Their general function is to use molecular oxygen (O_2) to oxidize organic molecules, especially to break down fatty acids into two-carbon molecules that can be used as an energy source for ATP synthesis. Such reactions produce hydrogen peroxide (H_2O_2), hence the name of the organelle. H_2O_2 is then used to oxidize other molecules, and the excess is broken down to water and oxygen by an enzyme called *catalase.* Peroxisomes also neutralize free radicals and detoxify alcohol, other drugs, and a variety of blood-borne toxins. Peroxisomes occur in nearly all cells but are especially abundant in the liver and kidneys.

Mitochondria

Mitochondria[31] (MY-toe-CON-dree-uh) (singular, *mitochondrion*) are organelles specialized for a process called *aerobic respiration,* which synthesizes most of the body's ATP. They have a variety of shapes: spheroidal, rod-shaped, bean-shaped, or threadlike (fig. 2.19e), and they constantly move, squirm, and change shape. Like the nucleus, a mitochondrion is surrounded by a double membrane. The inner membrane usually has folds called **cristae**[32] (CRIS-tee), which project like shelves across the organelle and bear the enzymes that produce most of the ATP. The space between the cristae is called the **mitochondrial matrix.** It contains enzymes, ribosomes, and a small, circular DNA molecule called *mitochondrial DNA (mtDNA),* which is genetically different from the DNA in the cell's nucleus (see Deeper Insight 2.2). Mutations in mtDNA are responsible for some muscle, heart, and eye diseases.

Centrioles

A **centriole** (SEN-tree-ole) is a short cylindrical assembly of microtubules arranged in nine groups of three microtubules each (fig. 2.19f). Near the nucleus, most cells have a small, clear patch of cytoplasm called the **centrosome**[33] containing a pair of mutually perpendicular centrioles (see fig. 2.5). These centrioles play a role in cell division described later. In ciliated cells, each cilium also has a **basal body** composed of a single centriole perpendicular to the plasma membrane. Two microtubules of each triplet form the peripheral microtubules of the axoneme of the cilium.

DEEPER INSIGHT 2.2

The Origin of Mitochondria

There is compelling evidence that mitochondria evolved from bacteria that either invaded or were engulfed by other ancient cells, then evolved a mutually beneficial metabolic relationship with them. In size and physiology, mitochondria resemble certain bacteria that live within other cells in a state of symbiosis. Mitochondrial DNA (mtDNA) resembles bacterial DNA more than it does nuclear DNA, and it is replicated independently of nuclear DNA. Mitochondrial DNA is inherited primarily from the individual's mother, because it is passed to the developing embryo mainly from the cytoplasm of the egg cell with little contribution from sperm mitochondria.

Although nuclear DNA is reshuffled in each generation by the process of sexual reproduction, mtDNA remains unchanged from generation to generation except by the slow pace of random mutation. It has therefore been useful as a "molecular clock" for biologists and anthropologists interested in tracing evolutionary lineages in humans and other species. The differences in mtDNA between one individual and another, or between one species and another, can be combined with the rate of mutation to estimate how long ago two individuals or species arose from the same ancestor. Geneticists have gained evidence, although still controversial, that of all females who lived in Africa about 200,000 years ago, only one left any descendants still living today—everyone now on earth is descended from this "mitochondrial Eve," a woman of unparalleled genetic success.

Inclusions

Inclusions are of two kinds: accumulated cell products such as pigments, fat droplets, and granules of glycogen (a starchlike carbohydrate); and internalized foreign matter such as dust, viruses, and bacteria. Inclusions are never enclosed in a membrane, and unlike the organelles and cytoskeleton, they are not essential to cell survival.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

11. Describe at least three functions of the cytoskeleton.
12. Briefly state how each of the following cell components can be recognized in electron micrographs: the nucleus, a mitochondrion, a lysosome, and a centriole. What is the primary function of each?
13. Distinguish between organelles and inclusions. State two examples of each.
14. What three organelles are involved in protein synthesis? Name two organelles involved in protein destruction.
15. Define *centriole, microtubule, cytoskeleton,* and *axoneme.* How are these structures related to each other?

---

[30] *auto* = self; *phagy* = eating
[31] *mito* = thread; *chondr* = grain
[32] *crista* = crest
[33] *centro* = central; *some* = body

2.4 The Cell Life Cycle

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the life cycle of a cell;
b. name the stages of mitosis and describe the events that occur in each one; and
c. discuss the types and clinical uses of stem cells.

This chapter concludes with an examination of the typical life cycle of human cells, including the process of cell division. Finally, we examine an issue of current controversy, the therapeutic use of embryonic stem cells.

The Cell Cycle

Most cells periodically divide into two daughter cells, so a cell has a life cycle extending from one division to the next. This **cell cycle** is divided into four main phases: G_1, S, G_2, and M (fig. 2.21).

The **first gap (G_1) phase** is an interval between cell division and DNA replication. During this time, a cell synthesizes proteins, grows, and carries out its predestined tasks for the body. Most human physiology pertains to what cells do in the G_1 phase. Cells in G_1 also accumulate the materials needed in the next phase to replicate their DNA.

The **synthesis (S) phase** is the period in which a cell makes duplicate copies of its centrioles and all of its nuclear DNA. Each of its DNA molecules uncoils into two separate strands, and each strand acts as a template for the synthesis of the missing strand. A cell begins the S phase with 46 molecules of DNA and ends it with 92. The cell then has two identical sets of DNA molecules, which are available to be divided up between daughter cells at the next cell division.

The **second gap (G_2) phase** is a relatively brief interval between DNA replication and cell division. In G_2, a cell finishes replicating its centrioles and synthesizes enzymes that control cell division. It also checks the accuracy of its DNA replication and usually repairs any errors that are detected.

The **mitotic (M) phase** is the period in which a cell replicates its nucleus, divides its DNA into two identical sets (one per nucleus), and pinches in two to form two genetically identical daughter cells. The details of this phase are considered in the next section. Phases G_1, S, and G_2 are collectively called **interphase**—the time between M phases.

The length of the cell cycle varies greatly from one cell type to another. Cultured connective tissue cells called fibroblasts divide about once a day and spend 8 to 10 hours in G_1, 6 to 8 hours in S, 4 to 6 hours in G_2, and 1 to 2 hours in M. Stomach and skin cells divide rapidly, bone and cartilage cells slowly, and skeletal muscle and nerve cells not at all. Some cells leave the cell cycle for a "rest" and cease to divide for days, years, or the rest of one's life. Such cells are said to be in the **G_0 (G-zero) phase.** The balance between cells that are actively cycling and those standing by in G_0 is an important factor in determining the number of cells in the body. An inability to stop cycling and enter G_0 is characteristic of cancer cells (see Deeper Insight 2.3).

Cell Division

Cells divide by two mechanisms called mitosis and meiosis. Meiosis, however, is restricted to one purpose, the production of eggs and sperm, and is therefore treated in chapter 26 on reproduction. **Mitosis** serves all the other functions of cell division: the development of an individual, composed of some 40 trillion cells, from a one-celled fertilized egg; continued growth of all the organs after birth; the replacement of cells that die; and the repair of damaged tissues. Four phases of



Figure 2.21 The Cell Cycle.

DEEPER INSIGHT 2.3

Cancer

A *tumor (neoplasm*[34]) is a mass of tissue produced when the rate of cell division exceeds the rate of cell death. A *malignant*[35] tumor, or *cancer* (fig. 2.22), is especially fast-growing, lacks a confining fibrous capsule, and has cells that are capable of breaking free and spreading to other organs (*metastasizing*[36]). Cancer was named by Hippocrates, who compared the distended veins in some breast tumors to the outstretched legs of a crab.[37]

All cancer is caused by mutations (changes in DNA or chromosome structure), which can be induced by chemicals, viruses, or radiation or simply occur through errors in DNA replication in the cell cycle. Agents that cause mutation are called *mutagens*,[38] and those that induce cancer are also called *carcinogens*.[39] Many forms of cancer stem from mutations in two gene families, the oncogenes and tumor-suppressor genes. *Oncogenes*[40] are mutated genes that promote the synthesis of excessive amounts of growth factors (chemicals that stimulate cell division) or excessive sensitivity of target cells to growth factors. *Tumor-suppressor (TS)* genes inhibit the development of cancer by opposing oncogenes, promoting DNA repair, and other means. Cancer occurs when TS genes are unable to perform this function. Oncogenes are like an accelerator to the cell cycle, and TS genes are like a brake.

Untreated cancer is almost always fatal. Tumors destroy healthy tissue; they can grow to block major blood vessels or respiratory airways; they can damage blood vessels and cause hemorrhaging; they can compress and kill brain tissue; and they tend to drain the body of nutrients and energy as they "hungrily" consume a disproportionate share of the body's oxygen and nutrients.



From the University of Alabama at Birmingham, Department of Pathology PEIR Digital Library © http://peir.net

Figure 2.22 **Wilms Tumor.** This is a malignant tumor of the kidney occurring especially in children.

mitosis are recognizable—*prophase, metaphase, anaphase,* and *telophase* (fig. 2.23).

In **prophase,**[41] at the outset of mitosis, the chromosomes coil into short, compact rods that are easier to distribute to daughter cells than the long, delicate chromatin of interphase. At this stage, a chromosome consists of two genetically identical bodies called **chromatids,** joined together at a pinched spot called the **centromere** (fig. 2.24). There are 46 chromosomes, two chromatids per chromosome, and one molecule of DNA in each chromatid. The nuclear envelope disintegrates during prophase and releases the chromosomes into the cytosol. The centrioles begin to sprout elongated microtubules called **spindle fibers,** which push the centrioles apart as they grow. Eventually, a pair of centrioles comes to lie at each pole of the cell. Spindle fibers grow toward the chromosomes, where some of them become attached to a platelike protein complex called the **kinetochore**[42] (kih-NEE-toe-core) on each side of the centromere. The spindle fibers then tug the chromosomes back and forth until they line up along the midline of the cell.

In **metaphase,**[43] the chromosomes are aligned on the cell equator, oscillating slightly and awaiting a signal that stimulates each chromosome to split in two at the centromere. The spindle fibers now form a lemon-shaped array called the **mitotic spindle.** Long microtubules reach out from each centriole to the chromosomes, and shorter microtubules form a starlike *aster*[44] that anchors the assembly to the inside of the plasma membrane at each end of the cell.

Anaphase[45] begins with activation of an enzyme that cleaves the two sister chromatids from each other at the centromere. Each chromatid is now regarded as a separate, single-stranded *daughter chromosome.* One daughter chromosome migrates to each pole of the cell, with its centromere leading the way and the arms trailing behind. Migration is achieved by means of motor proteins in the kinetochore crawling along the spindle fiber as the fiber itself is "chewed up" and disassembled at the chromosomal end. Since sister chromatids are genetically identical and since each daughter cell receives one chromatid

---

[34] *neo* = new; *plasm* = growth, formation
[35] *mal* = bad, evil
[36] *meta* = beyond; *stas* = being stationary
[37] *cancer* = crab
[38] *muta* = change; *gen* = to produce
[39] *carcino* = cancer; *gen* = to produce
[40] *onco* = tumor
[41] *pro* = first
[42] *kineto* = motion; *chore* = place
[43] *meta* = next in a series
[44] *aster* = star
[45] *ana* = apart


Aster
Spindle fibers
Centriole
Chromatids
Kinetochore
Cleavage furrow
Nuclear envelope re-forming
Daughter cells in interphase
Chromatin
Nucleolus
1
2
3
4

① **Prophase**
Chromosomes condense and nuclear envelope breaks down. Spindle fibers grow from centrioles. Centrioles migrate to opposite poles of cell.

② **Metaphase**
Chromosomes lie along midline of cell. Some spindle fibers attach to kinetochores. Fibers of aster attach to plasma membrane.

③ **Anaphase**
Centromeres divide in two. Spindle fibers pull sister chromatids to opposite poles of cell. Each pole (future daughter cell) now has an identical set of genes.

④ **Telophase**
Chromosomes gather at each pole of cell. Chromatin decondenses. New nuclear envelope appears at each pole. New nucleoli appear in each nucleus. Mitotic spindle vanishes.

© Ed Reschke

© Ed Reschke

© Ed Reschke/Getty Images

© Ed Reschke/Getty Images

Figure 2.23 **Mitosis.** The photographs show mitosis in whitefish eggs, where chromosomes are relatively easy to observe. The drawings show a hypothetical cell with only two chromosome pairs. In humans, there are 23 pairs.



© Biophoto Associates/Science Source

Figure 2.24 **Chromosomes.** (a) Diagram of a chromosome in metaphase. From the end of the S phase of the cell cycle to the beginning of anaphase in mitosis, a chromosome consists of two genetically identical chromatids. (b) SEM of a metaphase chromosome.

from each chromosome, the daughter cells of mitosis are genetically identical.

In **telophase,**[46] the chromatids cluster on each side of the cell. The rough ER produces a new nuclear envelope around each cluster, and the chromatids begin to uncoil and return to the thinly dispersed chromatin form. The mitotic spindle breaks up and vanishes. Each new nucleus forms nucleoli, indicating it has already begun making RNA and preparing for protein synthesis.

Telophase is the end of nuclear division but overlaps with **cytokinesis**[47] (SY-toe-kih-NEE-sis), division of the cytoplasm into two cells. Early traces of cytokinesis appear even in anaphase. It is achieved by the motor protein myosin pulling on microfilaments of actin in the terminal web. This creates a crease called the *cleavage furrow* around the equator of the cell, and the cell eventually pinches in two. Interphase has now begun for these new cells.

Stem Cells

One of the most controversial scientific issues in the last several years has been stem-cell research. **Stem cells** are immature cells with the ability to develop into one or more types of mature, specialized cells. Their ability to give rise to a diversity of mature cell types is called **developmental plasticity. Adult stem (AS) cells** exist in most of the body's organs. Despite the name, they are not limited to adults, but are found also in fetuses, infants, and children. They multiply and replace older cells that are lost to damage or normal cellular turnover. Some AS cells are **unipotent,** able to develop into only one mature cell type, such as the cells that develop into sperm or epidermal squamous cells. Some are **multipotent,** able to differentiate into multiple mature cell types, such as certain bone marrow cells that give rise to multiple types of white blood cells.

Embryonic stem (ES) cells comprise human embryos (technically, preembryos; see chapter 4) of up to 150 cells. They are **pluripotent,** able to develop into any type of embryonic or adult cell. ES cells are easily obtained from the excess embryos created in fertility clinics when a couple attempts to conceive a child by *in vitro fertilization* (IVF). In IVF, eggs are fertilized in glassware and allowed to develop to about 8 to 16 cells. Some of these are then transplanted into the mother's uterus. Excess embryos are created to compensate for the low probability of success. Those that are not transplanted to the uterus are usually destroyed, but they present a potential source of stem cells for research and therapy.

Skin and bone marrow adult stem cells have been used in therapy for many years. There is hope that stem cells can be manipulated to replace a broader range of tissues, such as injured spinal cords, cardiac muscle damaged by a heart attack, brain tissue lost in Parkinson and Alzheimer diseases, or the insulin-secreting cells needed by people with diabetes mellitus. Adult stem cells, however, seem to have limited developmental potential and to be unable to produce all cell types needed to treat a broad range of diseases. In addition, they are present in very small numbers and are difficult to isolate and culture in the quantities needed for therapy. Embryonic stem cells are easier to obtain and culture and have more developmental flexibility, but their use remains embroiled in political, religious, and ethical debate. Some would argue that if the excess embryos from IVF are destined to be destroyed, it would seem sensible to use them for beneficial purposes. Others argue, however, that potential medical benefits cannot justify the destruction of a human embryo or even a preembryo of scarcely more than 100 cells.

Further scientific advances, however, are beginning to defuse the controversy to some degree. Cell biologists have developed methods to make adult stem cells reverse course on their developmental paths, going back to a pluripotent state that would enable them to go down new roads. In principle, an AS cell that was originally destined to become smooth muscle, for example, might be made to revert to a pluripotent state, then chemically guided down a path leading to nervous tissue for Alzheimer patients or persons paralyzed by spinal cord injury. Such modified adult cells, now called *induced pluripotent stem (iPS) cells,* have begun to show great promise for both medical benefit and reduced controversy.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

16. State what occurs in each of the four phases of the cell cycle.
17. State what occurs in each of the four phases of mitosis.
18. Explain how a cell ensures that each of its daughter cells gets an identical set of genes.
19. Define *unipotent, multipotent,* and *pluripotent stem cells.* Give an example of each.
20. Discuss the advantages and disadvantages of adult and embryonic stem cells for therapy.

---

[46] *telo* = end, final
[47] *cyto* = cell; *kinesis* = action, motion

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

2.1 The Study of Cells (p. 26)

1. The meaning of *cytology* and why it is important in medical anatomy and physiology
2. How the light microscope, transmission electron microscope, and scanning electron microscope differ, and the relative importance of magnification and resolution
3. The cell shapes denoted by the terms *squamous, cuboidal, columnar, polygonal, stellate, spheroidal, ovoid, discoid, fusiform,* and *fibrous*
4. The distinction between the basal, apical, and lateral surfaces of an epithelial cell, and why it is important to differentiate them
5. The size of a micrometer and some common and extreme human cell sizes in terms of micrometers
6. Reasons why cells cannot grow indefinitely large; limitations on cell size
7. The meanings of *plasma membrane, cytoplasm, nucleoplasm, cytoskeleton, organelles, inclusions,* and *cytosol*
8. Terminology of the fluids on the inside and outside of a cell

2.2 The Cell Surface (p. 30)

1. Why the cell surface is so important for an understanding of human function
2. The molecular composition and organization of the plasma membrane
3. The general functions of membrane phospholipids, cholesterol, proteins, glycoproteins, and glycolipids
4. How integral proteins differ from the peripheral proteins of a plasma membrane
5. The diverse physiological roles of membrane proteins, and terms for the proteins that play each role
6. The importance of filtration through biological membranes, and the principal place in the body where this is relevant
7. The processes of simple diffusion, osmosis, reverse osmosis, facilitated diffusion, and active transport in relation to the plasma membrane; the relationship of each process to concentration gradients, the involvement of membrane proteins, and the necessity for ATP
8. The methods of vesicular transport through the plasma membrane: endocytosis (by phagocytosis, pinocytosis, and receptor-mediated endocytosis) and exocytosis; how each process is carried out; and the purposes for which each process may be used
9. The structural and functional differences between microvilli, cilia, flagella, and pseudopods
10. The composition, location, and functions of a cell's glycocalyx
11. The cell junctions that bind cells to each other and to extracellular material—tight junctions, desmosomes, hemidesmosomes, and gap junctions—and the structural and functional differences between them

2.3 The Cell Interior (p. 40)

1. The three components of the cytoskeleton, and how they differ in composition and function
2. Structure and function of a cell's nucleus, rough and smooth endoplasmic reticulum, ribosomes, the Golgi complex, proteasomes, lysosomes, peroxisomes, mitochondria, and centrioles
3. The two types of cellular inclusions, where they come from, and how they differ from organelles

2.4 The Cell Life Cycle (p. 47)

1. The four stages of the cell cycle and what events occur in each one
2. The four stages of mitosis, what events occur in each one, and how the chromosomes behave in such a way as to produce two genetically identical daughter cells
3. The process of cytokinesis and how it overlaps with mitosis
4. The structure of a chromosome as seen from prophase to metaphase
5. The meaning of *stem cells;* their usefulness in medicine; the distinction between adult and embryonic stem cells; and the various degrees of developmental plasticity seen in stem cells

Testing Your Recall

1. The clear, structureless gel in a cell is its
   - a. nucleoplasm.
   - b. endoplasm.
   - c. cytoplasm.
   - d. neoplasm.
   - e. cytosol.
2. New nuclei form and a cell pinches in two during
   - a. prophase.
   - b. metaphase.
   - c. interphase.
   - d. telophase.
   - e. anaphase.
3. The amount of _____ in a plasma membrane affects its stiffness versus fluidity.
   - a. phospholipid
   - b. cholesterol
   - c. glycolipid
   - d. glycoprotein
   - e. transmembrane protein
4. Cells specialized for absorption of matter from the ECF are likely to show an abundance of
   - a. lysosomes.
   - b. microvilli.
   - c. mitochondria.
   - d. secretory vesicles.
   - e. ribosomes.
5. Osmosis is a special case of
   - a. pinocytosis.
   - b. carrier-mediated transport.
   - c. active transport.
   - d. facilitated diffusion.
   - e. simple diffusion.
6. Embryonic stem cells are best described as
   - a. pluripotent.
   - b. multipotent.
   - c. unipotent.
   - d. more developmentally limited than adult stem cells.
   - e. more difficult to culture and harvest than adult stem cells.
7. The amount of DNA in a cell doubles during
   - a. prophase.
   - b. metaphase.
   - c. anaphase.
   - d. the S phase.
   - e. the G_2 phase.
8. Fusion of a secretory vesicle with the plasma membrane followed by release of the vesicle's contents is
   - a. exocytosis.
   - b. receptor-mediated endocytosis.

   c. active transport.
   d. pinocytosis.
   e. phagocytosis.

9. Most cellular membranes are made by
   a. the nucleus.
   b. the cytoskeleton.
   c. enzymes in the peroxisomes.
   d. the endoplasmic reticulum.
   e. replication of existing membranes.

10. Matter can leave a cell by any of the following means *except*
    a. active transport.
    b. simple diffusion.
    c. facilitated diffusion.
    d. pinocytosis.
    e. exocytosis.

11. Most human cells are 10 to 15 _____ wide.

12. When a hormone cannot enter a cell, it binds to a _____ at the cell surface.

13. _____ are channels in the plasma membrane that open or close in response to various stimuli.

14. Most ATP is produced by organelles called _____.

15. Leakage between cells is restricted by cell junctions called _____.

16. Thin scaly cells are described by the term _____.

17. Two human organelles that are surrounded by a double unit membrane are the _____ and _____.

18. Liver cells can detoxify alcohol with two organelles, the _____ and _____.

19. Cells adhere to each other and to extracellular material by means of membrane proteins called _____.

20. A macrophage would use the process of _____ to engulf a dying tissue cell.

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. The shape of a cell is determined mainly by its cytoskeleton.
2. The plasma membrane is composed mostly of protein.
3. A plasma membrane is too thin to be seen with the light microscope.
4. The hydrophilic heads of membrane phospholipids are in contact with both the ECF and ICF.
5. Water-soluble substances usually must pass through channel proteins to enter a cell.
6. Cells must use ATP to move substances down a concentration gradient.
7. Osmosis is a type of active transport involving water.
8. Cilia and flagella have an axoneme, but microvilli do not.
9. Desmosomes enable substances to pass from cell to cell.
10. A nucleolus is an organelle within the nucleoplasm.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. cyto-
2. squam-
3. -form
4. poly-
5. -philic
6. phago-
7. endo-
8. glyco-
9. chromo-
10. meta-

Answers in appendix A

Testing Your Comprehension

1. What would probably happen to the plasma membrane of a cell if it were composed of hydrophilic molecules such as carbohydrates?
2. Since electron microscopes are capable of much more resolution than light microscopes, why do you think biologists go on using light microscopes? Why are students in introductory biology courses not provided with electron microscopes?
3. This chapter mentions that the polio virus enters cells by means of receptor-mediated endocytosis. Why do you think the viruses don't simply enter through the channels in the plasma membrane? Cite some specific facts from this chapter to support your conjecture.
4. A major tenet of the cell theory is that all bodily structure and function result from the function of cells. Yet the structural properties of bone are due more to its extracellular material than to its cells. Is this an exception to the cell theory? Why or why not?
5. If a cell were poisoned so its mitochondria ceased to function, what membrane transport processes would immediately stop? What ones could continue?



A cancer cell (pink) undergoing apoptosis (cell suicide) under attack by an immune cell (orange) (SEM)

© Dr. Andrejs Liepins/Science Source

CHAPTER 3

HISTOLOGY— THE STUDY OF TISSUES

CHAPTER OUTLINE

3.1 The Study of Tissues 54
- The Primary Tissue Classes 54
- Interpreting Tissue Sections 54

3.2 Epithelial Tissue 56
- Simple Epithelia 57
- Stratified Epithelia 57

3.3 Connective Tissue 63
- Overview 63
- Fibrous Connective Tissue 63
- Adipose Tissue 67
- Cartilage 68
- Bone 70
- Blood 71

3.4 Nervous and Muscular Tissue—Excitable Tissues 72
- Nervous Tissue 72
- Muscular Tissue 73

3.5 Glands and Membranes 75
- Glands 75
- Membranes 78

3.6 Tissue Growth, Development, Repair, and Death 79
- Tissue Growth 79
- Changes in Tissue Type 79
- Tissue Repair 79
- Tissue Shrinkage and Death 80

Study Guide 81

DEEPER INSIGHTS

3.1 Collagen Diseases 64
3.2 The Consequences of Defective Elastin 67
3.3 Brittle Bone Disease 71
3.4 Tissue Engineering 80

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:
- Levels of human structure (p. 8)
- Membranes of the body cavities (pp. 16–19)
- Microscopy (p. 26)
- Cell shapes (p. 27)

Anatomy & Physiology REVEALED aprevealed.com

Module 3: Tissues

With its 50 trillion cells and thousands of organs, the human body may seem to be a structure of forbidding complexity. Fortunately for our health, longevity, and self-understanding, the biologists of past generations were not discouraged by this complexity, but discovered patterns that made it more understandable. One pattern is the fact that these trillions of cells belong to only 200 different types or so, and these cells are organized into tissues that fall into just 4 broad categories—*epithelial, connective, nervous,* and *muscular tissue.*

Here we study the four tissue classes; variations within each class; how to recognize tissue types microscopically and relate their microscopic anatomy to their function; how tissues are arranged to form an organ; and how tissues change as they grow, shrink, or change from one type to another over the life of the individual. This chapter describes only mature tissue types. Embryonic tissues are discussed in chapter 4.

3.1 The Study of Tissues

Expected Learning Outcomes

When you have completed this section, you should be able to

a. name the four primary classes into which all adult tissues are classified; and
b. visualize the three-dimensional shape of a structure from a two-dimensional tissue section.

Histology[1] **(microscopic anatomy)** is the study of tissues and how they are arranged into organs. Histology bridges the gap between the *cytology* of the preceding chapter and the *organ system* approach of the chapters that follow.

The Primary Tissue Classes

A **tissue** is a mass of similar cells and cell products that forms a discrete region of an organ and performs a specific function. The four **primary tissues** are epithelial, connective, nervous, and muscular tissue (table 3.1). These differ from each other in the types and functions of their cells, the characteristics of the **matrix (extracellular material)** that surrounds them, and the relative amount of space occupied by cells versus matrix.

In epithelial and muscular tissue, the cells are so close together that the matrix is barely visible, whereas in connective tissue, the matrix usually occupies more space than the cells do. The matrix is composed of fibrous proteins and **ground substance.** The latter is often called **extracellular fluid (ECF), interstitial**[2] **fluid,** or **tissue fluid,** although in cartilage and bone, the matrix is rubbery or stony in consistency.

In summary, a tissue is composed of cells and matrix, and the matrix is composed of fibers and ground substance.

Interpreting Tissue Sections

In your study of histology, you may be presented with various tissue preparations mounted on microscope slides. Most such preparations are thin slices called **histological sections,** and are artificially colored to bring out detail. The best anatomical insight depends on your ability to deduce the three-dimensional structure of an organ from these two-dimensional sections. This ability, in turn, depends on an awareness of how tissues are prepared for study.

Histologists use a variety of techniques to preserve, section (slice), and stain tissues to show their structural details as clearly as possible. Tissue specimens are preserved in a **fixative**—a chemical such as formalin that prevents decay and makes the tissue more firm. After fixation, most tissues are sectioned with a machine called a *microtome,* which makes slices that are typically only one or two cells thick. This is necessary so the light of a microscope

---

[1] *histo* = tissue; *logy* = study of

[2] *inter* = between; *stit* = to stand

TABLE 3.1 The Four Primary Tissue Classes

Type	Definition	Representative Locations
Epithelial	Tissue composed of layers of closely spaced cells that cover organ surfaces or form glands; serves for protection, secretion, and absorption	Epidermis Inner lining of digestive tract Liver and other glands
Connective	Tissue with usually more matrix than cell volume; often specialized to support, bind, and protect organs	Tendons and ligaments Cartilage and bone Blood and lymph
Nervous	Tissue containing excitable cells specialized for rapid transmission of information to other cells	Brain Spinal cord Nerves
Muscular	Tissue composed of elongated, excitable cells specialized for contraction	Skeletal muscles Heart (cardiac muscle) Walls of viscera (smooth muscle)

can pass through and so the image is not confused by too many superimposed layers of cells. The sections are then mounted on slides and colored with histological **stains** to enhance detail. If they were not stained, most tissues would appear pale gray. With stains that bind to different components of a tissue, however, you may see pink cytoplasm; violet nuclei; and pink, blue, green, or golden brown protein fibers, depending on the stain used.

When viewing such sections, you must try to translate the microscopic image into a mental image of the whole structure. Like the boiled egg and elbow macaroni in figure 3.1, an object may look quite different when it is cut at various levels, or *planes of section.* A coiled tube, such as a gland of the uterus (fig. 3.1c), is often broken up into multiple portions since it meanders in and out of the plane of section. An experienced viewer, however, would recognize that the separated pieces are parts of a single tube winding its way to the organ surface. Note that a grazing slice through a boiled egg may miss the yolk (fig. 3.1a). Similarly, a grazing slice through a cell may miss the nucleus and give the false impression that the cell does not have one. In some tissue sections, you are likely to see many cells with nuclei and many others in which the nucleus did not fall in the plane of section and is therefore absent.

Many anatomical structures are significantly longer in one direction than another—the humerus and esophagus, for example. A tissue cut in the long direction is called a **longitudinal section (l.s.),** and one cut perpendicular to this is a **cross section (c.s.),** or **transverse section (t.s.).** A section cut on a slant between a longitudinal and cross section is an **oblique section.** Figure 3.2 shows how certain organs look when sectioned on each of these planes.

Not all histological preparations are sections. Liquid tissues such as blood and soft tissues such as spinal cord may be prepared as **smears,** in which the tissue is rubbed or spread across the slide rather than sliced. Some membranes and cobwebby tissues like the *areolar tissue* described later in this chapter are sometimes mounted as **spreads,** in which the tissue is laid out on the slide, like placing a small square of tissue paper or a tuft of lint on a sheet of glass.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. Define *tissue* and distinguish a tissue from a cell and an organ.
2. Classify each of the following into one of the four primary tissue classes: the skin surface, fat, the spinal cord, most heart tissue, bones, tendons, blood, and the inner lining of the stomach.
3. What are tissues composed of in addition to cells?
4. What is the term for a thin, stained slice of tissue mounted on a microscope slide?
5. Sketch what a pencil would look like in a longitudinal section, cross section, and oblique section.



Figure 3.1 **Three-Dimensional Interpretation of Two-Dimensional Images.** (a) A boiled egg. Note that the grazing sections (upper left and right) miss the yolk, just as a tissue section may miss a nucleus or other structure. (b) Elbow macaroni, which resembles many curved ducts and tubules. A section far from the bend would give the impression of two separate tubules; a section near the bend would show two interconnected lumina (internal spaces); and a section still farther down could miss the lumen completely. (c) A coiled gland in three dimensions and as it would look in a vertical tissue section.

- *Consider the microtubule in figure 2.17a (p. 42). Sketch what you think it would look like in a median longitudinal section.*



Figure 3.2 **Longitudinal, Cross, and Oblique Sections.** Note the effect of the plane of section on the two-dimensional appearance of elongated structures such as bones and blood vessels.

3.2 Epithelial Tissue

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the properties that distinguish epithelium from other tissue classes;
b. list and classify eight types of epithelium, distinguish them from each other, and state where each type can be found in the body;
c. explain how the structural differences between epithelia relate to their functional differences; and
d. visually recognize each epithelial type from specimens or photographs.

Epithelium[3] is a sheet of tissue composed of one or more layers of closely adhering cells, usually serving as the internal lining of a hollow organ or body cavity or the external surface of an organ. Thus, we find epithelia lining the pleural, pericardial, and peritoneal cavities; lining the inner passages of the respiratory, digestive, urinary, and reproductive tracts; and covering the outer surfaces of the stomach and intestines. Epithelia also constitute the secretory tissue and ducts of the glands; most tissue of the liver, pancreas, and kidneys is epithelium. The body's most extensive epithelium is the epidermis of the skin. Epithelia typically serve for protection, secretion of products such as mucus and digestive enzymes, excretion of wastes, and absorption of materials such as oxygen and nutrients.

The cells and extracellular material of an epithelium can be loosely compared to the bricks and mortar of a wall. The extracellular material ("mortar") of an epithelium is so thin, however, that it is barely visible with a light microscope, and the cells appear pressed very closely together. Epithelia are *avascular*[4]—there is no room between the cells for blood vessels. Other avascular tissues, such as cartilages and tendons, have low metabolic rates and are slow to heal when injured. Epithelia, however, almost always lie on a vessel-rich layer of loose connective tissue, which furnishes them with nutrients and waste removal. Epithelial cells closest to the connective tissue layer typically exhibit a high rate of mitosis. This allows epithelia to repair themselves very quickly—an ability of special importance in protective epithelia that are highly vulnerable to such injuries as skin abrasions and erosion by digestive enzymes and acid.

Between an epithelium and the underlying connective tissue is a layer called the **basement membrane.** It contains collagen, glycoproteins, and other protein–carbohydrate complexes, and gradually blends with other proteins in the underlying connective tissue. The basement membrane serves to anchor an epithelium to the connective tissue below it; it regulates the exchange of materials between the epithelium and the tissues below; and it binds growth factors from below that regulate epithelial development. The surface of an epithelial cell that faces the basement membrane is its *basal surface,* and the one that faces away from the basement membrane toward the internal cavity (lumen) of an organ is the *apical surface.*

Epithelia are classified into two broad categories, simple and stratified, with four types in each category:

- Simple epithelia
  - Simple squamous epithelium
  - Simple cuboidal epithelium
  - Simple columnar epithelium
  - Pseudostratified columnar epithelium

- Stratified epithelia
  - Stratified squamous epithelium
  - Stratified cuboidal epithelium
  - Stratified columnar epithelium
  - Transitional epithelium

---

[3] *epi* = upon; *thel* = nipple, female
[4] *a* = without; *vas* = vessels



Figure 3.3 **Cell Shapes and Epithelial Types.** Pseudostratified columnar epithelium is a special type of simple epithelium that gives a false appearance of multiple cell layers.

In a *simple epithelium,* every cell rests on the basement membrane, whereas in a *stratified epithelium,* some cells rest on top of others and do not touch it (fig. 3.3a). The *pseudostratified columnar* type is included among simple epithelia, although it presents a false appearance of stratification for reasons explained shortly. Individual characteristics of all eight epithelia follow (tables 3.2 and 3.3).

Simple Epithelia

Generally, a simple epithelium has only one layer of cells, although this is a somewhat debatable point in the pseudostratified columnar type. Three types of simple epithelia are named for their cell shapes: **simple squamous** (thin scaly cells), **simple cuboidal** (squarish or round cells), and **simple columnar** (tall narrow cells). In **pseudostratified columnar epithelium,** not all cells reach the free surface; the taller cells cover the shorter ones. This epithelium looks stratified in most tissue sections, but careful examination, especially with the electron microscope, shows that every cell reaches the basement membrane—like trees in a forest, where some grow taller than others but all are anchored in the soil below.

Simple columnar and pseudostratified columnar epithelia often have wineglass-shaped **goblet cells** that produce protective mucus over the epithelial surface. These cells have an expanded apical end filled with secretory vesicles; their product becomes mucus when it is secreted and absorbs water. The basal part of the cell is a narrow stem, like that of a wineglass, that reaches to the basement membrane.

Table 3.2 illustrates and summarizes the structural and functional differences among the four simple epithelia. In this and the subsequent tables, each tissue is represented by a photograph and a corresponding line drawing with labels. The drawings help to clarify cell boundaries and other relevant features that may otherwise be difficult to see or identify in photographs or through the microscope. Each figure indicates the approximate magnification at which the original photograph was made. Each is enlarged much more than this when printed in the book, but selecting the closest magnifications on a microscope should enable you to see a comparable level of detail (resolution).

Stratified Epithelia

Stratified epithelia range from 2 to 20 or more layers of cells, with some cells resting directly on others (like a multistory apartment building) and only the deepest layer resting on the basement membrane. Three of the stratified epithelia are named for the shapes of their surface cells: **stratified squamous, stratified cuboidal,** and **stratified columnar.** The deeper cells, however, may be of a different shape than the surface cells. The fourth type, **transitional epithelium,** was named when it was thought to represent a transitional stage between stratified squamous and stratified columnar epithelium. This is now known to be untrue, but the name has persisted.

Stratified columnar epithelium is rare and of relatively minor importance—seen only in short stretches where two other epithelial types meet, as in limited regions of the pharynx, larynx, anal canal, and male urethra. We will not consider this type any further. The other three types are illustrated and summarized in table 3.3.

TABLE 3.2 Simple Epithelia

Simple Squamous Epithelium



© McGraw-Hill Education/Dennis Strete, photographer

Figure 3.4 Simple Squamous Epithelium in the Serosa of the Small Intestine (×400). APR

Microscopic appearance: Single layer of thin cells, shaped like fried eggs with bulge where nucleus is located; nucleus flattened in the plane of the cell, like an egg yolk; cytoplasm may be so thin it is hard to see in tissue sections; in surface view, cells have angular contours and nuclei appear round

Representative locations: Air sacs (alveoli) of lungs; glomerular capsules of kidneys; some kidney tubules; inner lining (endothelium) of heart and blood vessels; serous membranes of stomach, intestines, and some other viscera; surface mesothelium of pleurae, pericardium, peritoneum, and mesenteries

Functions: Allows rapid diffusion or transport of substances through membranes; secretes lubricating serous fluid

Simple Cuboidal Epithelium



© McGraw-Hill Education/Dennis Strete, photographer

Figure 3.5 Simple Cuboidal Epithelium in Kidney Tubules (×400). APR

Microscopic appearance: Single layer of square or round cells; in glands, cells often pyramidal and arranged like segments of an orange around a central space; spherical, centrally placed nuclei; often with a brush border of microvilli in some kidney tubules; ciliated in bronchioles of lung

Representative locations: Liver; thyroid, mammary, salivary, and other glands; most kidney tubules; bronchioles

Functions: Absorption and secretion; production and movement of respiratory mucus

TABLE 3.2 Simple Epithelia (continued)

Simple Columnar Epithelium


(a)
Brush border (microvilli)
Connective tissue
Basement membrane
Nuclei
Goblet cell
Columnar cells
(b)

© Ed Reschke/Getty Images

Figure 3.6 Simple Columnar Epithelium in the Mucosa of the Small Intestine (×400). APR

Microscopic appearance: Single layer of tall, narrow cells; oval or sausage-shaped nuclei, vertically oriented, usually in basal half of cell; apical portion of cell often shows secretory vesicles visible with the transmission electron microscope (TEM); often shows a brush border of microvilli; ciliated in some organs; may possess goblet cells
Representative locations: Inner lining of stomach, intestines, gallbladder, uterus, and uterine tubes; some kidney tubules
Functions: Absorption; secretion of mucus and other products; movement of egg and embryo in uterine tube

Pseudostratified Columnar Epithelium


(a)
Cilia
Basement membrane
Basal cells
Goblet cell
(b)

© McGraw-Hill Education/Dennis Strete, photographer

Figure 3.7 Ciliated Pseudostratified Columnar Epithelium in the Mucosa of the Trachea (×400). APR

Microscopic appearance: Looks multilayered; some cells do not reach free surface but all cells reach basement membrane; nuclei at several levels in deeper half of epithelium; often with goblet cells; often ciliated
Representative locations: Respiratory tract from nasal cavity to bronchi; portions of male urethra
Functions: Secretes and propels mucus

TABLE 3.3 Stratified Epithelia

Stratified Squamous Epithelium—Keratinized


(a)
Dead squamous cells
Living epithelial cells
Dense irregular connective tissue
Areolar tissue
(b)

© Ed Reschke

Figure 3.8 Keratinized Stratified Squamous Epithelium in the Sole of the Foot (×400). APR

Microscopic appearance: Multiple cell layers with cells becoming increasingly flat and scaly toward surface; surface covered with a layer of compact dead cells without nuclei; basal cells may be cuboidal to columnar

Representative locations: Epidermis; palms and soles are especially heavily keratinized

Functions: Resists abrasion; retards water loss through skin; resists penetration by pathogenic organisms

Stratified Squamous Epithelium—Nonkeratinized


(a)
Living epithelial cells
Connective tissue
(b)

© Ed Reschke/Getty Images

Figure 3.9 Nonkeratinized Stratified Squamous Epithelium in the Mucosa of the Vagina (×400). APR

Microscopic appearance: Same as keratinized epithelium but without the surface layer of dead cells

Representative locations: Tongue, esophagus, anal canal, vagina

Functions: Resists abrasion and penetration by pathogenic organisms

TABLE 3.3 Stratified Epithelia (continued)

Stratified Cuboidal Epithelium


© Lester V. Bergman/Corbis
(a)
Cuboidal cells
Epithelium
Connective tissue
(b)

Figure 3.10 Stratified Cuboidal Epithelium in the Duct of a Sweat Gland (×400). APR

Microscopic appearance: Two or more layers of cells; surface cells roughly square or round

Representative locations: Sweat gland ducts; egg-producing vesicles (follicles) of ovaries; sperm-producing ducts (seminiferous tubules) of testes

Functions: Contributes to sweat secretion; secretes ovarian hormones; produces sperm

Transitional Epithelium


© Johnny R. Howze
(a)
Basement membrane
Connective tissue
Binucleate epithelial cell
(b)

Figure 3.11 Transitional Epithelium in the Kidney (×400). APR

Microscopic appearance: Somewhat resembles stratified squamous epithelium, but surface cells are rounded, not flattened, and often bulge above surface; typically five or six cells thick when relaxed, two or three cells thick when stretched; cells may be flatter and thinner when epithelium is stretched (as in a distended bladder); some cells have two nuclei

Representative locations: Urinary tract—part of kidney, ureter, bladder, part of urethra; allantoic duct of umbilical cord

Function: Stretches to allow filling of urinary tract



© David M. Phillips/Science Source

Figure 3.12 Exfoliation of Squamous Cells from the Vaginal Mucosa (SEM).

The most widespread epithelium in the body is stratified squamous, which warrants further discussion. In the deepest layer, the cells are cuboidal to columnar and undergo continual mitosis. Their daughter cells push toward the surface and become flatter (more squamous) as they migrate farther upward, until they die and flake off. Their separation from the surface is called **exfoliation (desquamation)** (fig. 3.12); the study of exfoliated cells is called *exfoliate cytology.* You can easily study exfoliated cells by scraping your gums with a toothpick, smearing this material on a slide, and staining it. A similar procedure is used in the *Pap smear,* an examination of exfoliated cells from the cervix for signs of uterine cancer (see fig. 26.25, p. 733).

Stratified squamous epithelia are of two kinds—keratinized and nonkeratinized. A **keratinized (cornified)** epithelium, found on the skin surface (epidermis), is covered with a layer of compact, dead squamous cells (see fig. 3.8). These cells are packed with the durable protein **keratin** and coated with a water-repellent glycolipid. The skin surface is therefore relatively dry; it retards water loss from the body; and it resists penetration by disease organisms. (Keratin is also the protein of which animal horns are made, hence its name.[5]) The tongue, esophagus, vagina, and a few other internal surfaces are covered with the **nonkeratinized** type, which lacks the layer of dead cells (see fig. 3.9). This type provides a surface that is, again, abrasion-resistant, but also moist and slippery. These characteristics are well suited to resist stress produced by the chewing and swallowing of food and by sexual intercourse and childbirth.

Transitional epithelium is another particularly interesting type of stratified epithelium. Why is it limited to the urinary tract? The answer relates to the fact that urine is usually acidic and hypertonic to the intracellular fluids. It would tend to draw water out of cells by osmosis and kill them if there were nothing to protect the cells. The domed surface cells of transitional epithelium, however, have a unique protective property. They are called *umbrella cells.* On the upper surface of an umbrella cell, the outer phospholipid layer of the plasma membrane is thicker than usual and has dense patches called *lipid rafts* with embedded proteins called *uroplakins.* Uroplakins are impermeable to urine and protect the epithelium, including the cytoplasm of the umbrella cell itself. The lipid rafts are connected to each other by hinges of ordinary plasma membrane. When the bladder is empty and relaxed, these plaques fold at the hinges, drop into the cell interior for storage (like folding a laptop computer and putting it away), and the cells bulge upward as seen in figure 3.11. As the bladder fills with urine, the hinges open (like opening the computer), the plaques spread out over the surface to protect the cell, and the umbrella cells become thinner and flatter. Not surprisingly, this type of epithelium is best developed in the bladder, where it is subject to the most prolonged contact with urine.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

6. Distinguish between simple and stratified epithelia, and explain why pseudostratified columnar epithelium belongs in the former category.
7. Explain how to distinguish a stratified squamous epithelium from a transitional epithelium.
8. What function do keratinized and nonkeratinized stratified squamous epithelia have in common? What is the structural difference between these two? How is this structural difference related to a functional difference between them?
9. How do the epithelia of the esophagus and stomach differ? How does this relate to their respective functions?
10. Explain why epithelial tissue is able to repair itself quickly even though it is avascular.
11. Explain why transitional epithelium is specifically adapted to the urinary tract.

---

[5] *kerat* = horn

3.3 Connective Tissue

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the properties that most connective tissues have in common;
b. discuss the types of cells found in connective tissue;
c. explain what the matrix of a connective tissue is and describe its components;
d. name 10 types of connective tissue and identify their functional specializations;
e. describe the cellular components and matrix of each type, and explain what structurally distinguishes them from each other; and
f. visually recognize each connective tissue type from specimens or photographs.

Overview

Connective tissue is a type of tissue in which cells usually occupy less space than the extracellular material, and that serves in most cases to support and protect organs or bind organs to each other. Most cells of a connective tissue are not in direct contact with each other, but are well separated by extracellular material. Most kinds of connective tissue are highly vascular—richly supplied with blood vessels. Connective tissue is the most abundant, widely distributed, and histologically variable of the primary tissues. Mature connective tissues fall into four broad categories: *fibrous connective tissue, adipose tissue, supportive connective tissue* (cartilage and bone), and *fluid connective tissue* (blood).

The functions of connective tissue include the following:

- **Binding of organs.** Tendons bind muscle to bone, ligaments bind one bone to another, fat holds the kidneys and eyes in place, and fibrous tissue binds the skin to underlying muscle.
- **Support.** Bones support the body, and cartilage supports the ears, nose, trachea, and bronchi.
- **Physical protection.** The cranium, ribs, and sternum protect delicate organs such as the brain, lungs, and heart; fatty cushions around the kidneys and eyes protect these organs.
- **Immune protection.** Connective tissue cells attack foreign invaders, and connective tissue fiber forms a "battlefield" under the skin and mucous membranes where immune cells can be quickly mobilized against disease agents.
- **Movement.** Bones provide the lever system for body movement, cartilages are involved in movement of the vocal cords, and cartilages on bone surfaces ease joint movements.
- **Storage.** Fat is the body's major energy reserve; bone is a reservoir of calcium and phosphorus.
- **Heat production.** Metabolism of brown fat generates heat in infants and children.
- **Transport.** Blood transports gases, nutrients, wastes, hormones, and blood cells.

Fibrous Connective Tissue

Fibrous connective tissue is the most diverse type of connective tissue. It is also called *fibroconnective tissue* or *connective tissue proper*. Nearly all connective tissues contain fibers, but the tissues considered here are classified together because the fibers are so conspicuous. The tissue, of course, also includes cells and ground substance. Before examining specific types of fibrous connective tissue, we will examine these components.

Components of Fibrous Connective Tissue

Cells The cells of fibrous connective tissue include the following types:

- **Fibroblasts.**[6] These are large, fusiform cells that often show slender, wispy branches. They produce the fibers and ground substance that form the matrix of the tissue.
- **Macrophages.**[7] These are large phagocytic cells that wander through the connective tissues. They phagocytize and destroy bacteria, other foreign matter, and dead or dying cells of our own body. They also activate the immune system when they sense foreign matter called *antigens.* They arise from certain white blood cells called *monocytes* or from the stem cells that produce monocytes.
- **Leukocytes,**[8] or **white blood cells (WBCs).** WBCs travel briefly in the bloodstream, then crawl out through the capillary walls and spend most of their time in the connective tissues. The two most common types are *neutrophils,* which wander about in search of bacteria, and *lymphocytes,* which react against bacteria, toxins, and other foreign agents. Lymphocytes often form dense patches in the mucous membranes.
- **Plasma cells.** Certain lymphocytes turn into plasma cells when they detect foreign agents. The plasma cells then synthesize disease-fighting proteins called *antibodies.* Plasma cells are rarely seen except in inflamed tissue and the walls of the intestines.
- **Mast cells.** These cells, found especially alongside blood vessels, secrete a chemical called *heparin* that inhibits blood clotting, and one called *histamine* that increases blood flow by dilating blood vessels.
- **Adipocytes** (AD-ih-po-sites), or **fat cells.** These appear in small clusters in some fibrous connective tissues. When they dominate an area, the tissue is called *adipose tissue.*

Fibers Three types of protein fibers are found in fibrous connective tissues:

- **Collagenous** (col-LADJ-eh-nus) **fibers.** These fibers, made of collagen, are tough and flexible and resist stretching. Collagen is the body's most abundant protein, constituting about 25% of the total. It is the base of such animal products as

---

[6] *fibro* = fiber; *blast* = producing
[7] *macro* = big; *phage* = eater
[8] *leuko* = white; *cyte* = cell



© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Figure 3.13 **Tendons of the Hand.** The white glistening appearance results from the collagen of which tendons are composed. The braceletlike extensor retinaculum across the wrist is also composed of collagen.

- *Which category of connective tissue composes these tendons?*

gelatin, leather, and glue.[9] In fresh tissue, collagenous fibers have a glistening white appearance, as seen in tendons and some cuts of meat (fig. 3.13); thus, they are often called *white fibers.* In tissue sections, collagen forms coarse, wavy bundles, often dyed pink, blue, or green by the most common histological stains. Tendons, ligaments, and the deep layer of the skin (the dermis) are made mainly of collagen. Less visibly, collagen pervades the matrix of cartilage and bone.

- **Reticular**[10] **fibers.** These are thin collagen fibers coated with glycoprotein. They form a spongelike framework for such organs as the spleen and lymph nodes.
- **Elastic fibers.** These are thinner than collagenous fibers, and they branch and rejoin each other along their course. They are made of a protein called **elastin,** whose coiled structure allows it to stretch and recoil like a rubber band. Elastic fibers account for the ability of the skin, lungs, and arteries to spring back after they are stretched. (Elasticity is not the ability to stretch, but the tendency to recoil when tension is released.)

DEEPER INSIGHT 3.1

Collagen Diseases

The gene for collagen is especially subject to mutation, and there are consequently several diseases that stem from hereditary defects in collagen synthesis. Since collagen is such a widespread protein in the body, the effects are very diverse. People with *Ehlers–Danlos*[11] syndrome have abnormally long, loose collagen fibers, which show their effects in unusually stretchy skin; loose joints; slow wound healing; and abnormalities in the blood vessels, intestines, and urinary bladder. Infants with this syndrome are often born with dislocated hips. *Osteogenesis imperfecta* is a hereditary collagen disease that affects bone development (see Deeper Insight 3.3).

Not all collagen diseases are hereditary, however. *Scurvy*, for example, results from a dietary deficiency of vitamin C (ascorbic acid). Ascorbic acid is a cofactor needed for the metabolism of proline and lysine, two amino acids that are especially abundant in collagen. The signs of scurvy include bleeding gums, loose teeth, subcutaneous and intramuscular hemorrhages, and poor wound healing.

Ground Substance Amid the cells and fibers in some connective tissue sections, there appears to be a lot of empty space. In living tissue, this space is occupied by the featureless ground substance. Ground substance usually has a gelatinous consistency resulting from three classes of large molecules composed of protein and carbohydrate: *glycosaminoglycans (GAGs), proteoglycans,* and *adhesive glycoproteins.* Some of these molecules are up to 20 μm long—larger than some cells. The ground substance absorbs compressive forces and, like the Styrofoam packing in a shipping carton, it protects the more delicate cells from mechanical injury. GAGs also form a very slippery lubricant in the joints and constitute much of the jellylike *vitreous body* of the eyeball. In connective tissue, such molecules form a gel that slows down the spread of bacteria and other pathogens (disease-causing agents). Adhesive glycoproteins bind plasma membrane proteins to collagen and proteoglycans outside the cell. They bind all the components of a tissue together and mark pathways that guide migrating embryonic cells to their destinations in a tissue.

Types of Fibrous Connective Tissue

Fibrous connective tissue is divided into two broad categories according to the relative abundance of fiber: *loose* and *dense connective tissue.* In **loose connective tissue,** much of the space is occupied by ground substance, which is dissolved out of the tissue during histological fixation and leaves empty space in prepared tissue sections. The loose connective tissues we will discuss are *areolar tissue* and *reticular tissue* (table 3.4). In **dense connective tissue,** fiber occupies more space than the cells and ground substance, and appears closely packed in tissue sections. The two dense connective tissues we will discuss are *dense regular* and *dense irregular connective tissue* (table 3.5).

---

[9] *colla* = glue; *gen* = producing

[10] *ret* = network; *icul* = little

[11] Edward L. Ehlers (1863–1937), Danish dermatologist; Henri A. Danlos (1844–1912), French dermatologist

TABLE 3.4 Loose Connective Tissues

Areolar Tissue



© McGraw-Hill Education/Dennis Strete, photographer

Figure 3.14 Areolar Tissue in a Spread of the Mesentery (×400). AP|R

Microscopic appearance: Loose arrangement of collagenous and elastic fibers; scattered cells of various types; abundant ground substance; numerous blood vessels
Representative locations: Underlying nearly all epithelia; surrounding blood vessels, nerves, esophagus, and trachea; fasciae between muscles; mesenteries; visceral layers of pericardium and pleura
Functions: Loosely binds epithelia to deeper tissues; allows passage of nerves and blood vessels through other tissues; provides an arena for immune defense; provides nutrients and waste removal for overlying epithelia

Reticular Tissue



© McGraw-Hill Education/Al Telser, photographer

Figure 3.15 Reticular Tissue in the Spleen (×400). AP|R

Microscopic appearance: Loose network of reticular fibers and cells, infiltrated with numerous lymphocytes and other blood cells
Representative locations: Lymph nodes, spleen, thymus, bone marrow
Functions: Supportive stroma (framework) for lymphatic organs

TABLE 3.5 Dense Connective Tissues

Dense Regular Connective Tissue



© McGraw-Hill Education/Dennis Strete, photographer

Figure 3.16 Dense Regular Connective Tissue in a Tendon (×400). APR

Microscopic appearance: Densely packed, parallel, often wavy collagen fibers; slender fibroblast nuclei compressed between collagen bundles; scanty open space (ground substance); scarcity of blood vessels
Representative locations: Tendons and ligaments
Functions: Ligaments tightly bind bones together and resist stress; tendons attach muscle to bone and move the bones when the muscles contract

Dense Irregular Connective Tissue



© McGraw-Hill Education/Dennis Strete, photographer

Figure 3.17 Dense Irregular Connective Tissue in the Dermis of the Skin (×400). APR

Microscopic appearance: Densely packed collagen fibers running in random directions; scanty open space (ground substance); few visible cells; long fibers in the tissue appear as short, chopped-up pieces in thin histological sections, as in photo
Representative locations: Deeper portion of dermis of skin; capsules around viscera such as liver, kidney, spleen; fibrous sheaths around muscles, nerves, cartilages, and bones
Functions: Durable, hard to tear; variable orientation of fibers withstands stresses applied in unpredictable directions

Areolar[12] (AIR-ee-OH-lur) **tissue** exhibits loosely organized fibers, abundant blood vessels, and a lot of seemingly empty space. It possesses all six of the aforementioned cell types. Its fibers run in random directions and are mostly collagenous, but elastic and reticular fibers are also present. Areolar tissue is highly variable in appearance. In many serous membranes, it looks like figure 3.14, but in the skin and mucous membranes, it is more compact (see fig. 3.8b) and is sometimes difficult to distinguish from dense irregular connective tissue. Some advice on how to tell them apart is given after the discussion of dense irregular connective tissue.

Areolar tissue is found in histological sections from almost every part of the body. It surrounds blood vessels and nerves and penetrates with them even into the small spaces of muscles, tendons, and other organs. Nearly every epithelium rests on a layer of areolar tissue, whose blood vessels provide the epithelium with nutrition, waste removal, and a ready supply of infection-fighting leukocytes in times of need. Because of the abundance of open, fluid-filled space, leukocytes can move about freely in areolar tissue and can easily find and destroy pathogens.

Reticular tissue (fig. 3.15) is a mesh of reticular fibers and fibroblasts. It forms the structural framework (stroma) of such organs as the lymph nodes, spleen, thymus, and bone marrow. The space amid the fibers is filled with blood cells. Imagine a kitchen sponge soaked with blood; the sponge fibers are analogous to the reticular tissue stroma.

Dense regular connective tissue is named for two properties: (1) The collagen fibers are closely packed and leave relatively little open space, and (2) the fibers are parallel to each other. It is found especially in tendons and ligaments. The parallel arrangement of fibers is an adaptation to the fact that tendons and ligaments are pulled in predictable directions. With some minor exceptions such as blood vessels and sensory nerve fibers, the only cells in this tissue are fibroblasts, visible by their slender, violet-staining nuclei squeezed between bundles of collagen. This type of tissue has few blood vessels and receives a meager supply of oxygen and nutrients, so injured tendons and ligaments are slow to heal.

The vocal cords and some ligaments of the vertebral column are made of a type of dense regular connective tissue called **elastic tissue.** In addition to the densely packed collagen fibers, it exhibits branching elastic fibers and more fibroblasts. The fibroblasts have larger, more conspicuous nuclei than seen in most dense regular connective tissue.

Elastic tissue takes the form of wavy sheets in the walls of large arteries. When the heart pumps blood into the arteries, these sheets enable them to expand and relieve some of the pressure on smaller vessels downstream. When the heart relaxes, the arterial wall springs back and keeps the blood pressure from dropping too low between heartbeats. The importance of this elastic tissue becomes especially clear in diseases such as atherosclerosis, in which the tissue is stiffened by lipid and calcium deposits, and Marfan syndrome, a genetic defect in elastin synthesis (see Deeper Insight 3.2).

Dense irregular connective tissue also has thick bundles of collagen and relatively little room for cells and ground substance, but the collagen bundles run in seemingly random directions. This arrangement enables the tissue to resist unpredictable stresses. Dense irregular connective tissue constitutes most of the dermis, where it binds the skin to the underlying muscle and connective tissue. It forms a protective capsule around organs such as the kidneys, testes, and spleen and a tough fibrous sheet around the bones, nerves, and most cartilages.

It is sometimes difficult to judge whether a tissue is areolar or dense irregular. In the dermis, for example, these tissues occur side by side, and the transition from one to the other is not at all obvious (see fig. 3.8b). A relatively large amount of clear space suggests areolar tissue, and thicker bundles of collagen with relatively little clear space suggest dense irregular tissue.

DEEPER INSIGHT 3.2

The Consequences of Defective Elastin

Marfan[13] *syndrome* is a hereditary defect in elastin fibers, usually resulting from a mutation in the gene for *fibrillin*, a glycoprotein that forms the structural scaffold for elastin. Clinical signs of Marfan syndrome include hyperextensible joints, hernias of the groin, and vision problems resulting from abnormally elongated eyes and deformed lenses. People with Marfan syndrome typically show unusually tall stature, long limbs, spidery fingers, abnormal spinal curvature, and a protruding "pigeon breast." More serious problems are weakened heart valves and arterial walls. The aorta, where blood pressure is highest, is sometimes enormously dilated close to the heart and may rupture. Marfan syndrome is present in about 1 out of 20,000 live births, and most victims die by their mid-30s. A number of star athletes have died at a young age of Marfan syndrome, including Olympic volleyball champion Flo Hyman, who died of a ruptured aorta during a game in Japan in 1986, at the age of 31.

Adipose Tissue

Adipose tissue, or **fat,** is tissue in which adipocytes are the dominant cell type (table 3.6). Adipocytes may also occur singly or in small clusters in areolar tissue. The space between adipocytes is occupied by areolar tissue, reticular tissue, and blood capillaries.

Fat is the body's primary energy reservoir. The quantity of stored fat and the number of adipocytes are quite stable in a person, but this does not mean stored fat is stagnant. New fat molecules are constantly synthesized and stored as others are broken down and released into circulation. Thus, there is a constant turnover of stored fat, with an equilibrium between synthesis and breakdown, energy storage and energy use.

There are two kinds of fat in humans—white (or yellow) fat and brown fat. **White fat** is the more abundant and significant type in the adult body. Its adipocytes usually range from 70 to 120 µm in diameter, but they may be five times as large in obese people. They have a single large, central globule of fat (fig. 3.18). This is an inclusion, not an organelle; it is not contained in a membrane. It has a solid, greasy consistency (think of bacon fat). Adipocyte

---

[12] *areola* = little space

[13] Antoine Bernard-Jean Marfan (1858–1942), French physician

TABLE 3.6 Adipose Tissue



© McGraw-Hill Education/Dennis Strete, photographer

Figure 3.18 Adipose Tissue in the Breast (×100). APR

Microscopic appearance: Dominated by adipocytes—large, empty-looking cells with thin margins and nucleus pressed against inside of plasma membrane; cells usually shriveled by histological fixative; tissue sections often pale because of scarcity of stained cytoplasm; blood vessels often visible

Representative locations: Subcutaneous fat beneath skin; breast; heart surface; mesenteries; surrounding such organs as kidneys and eyes

Functions: Energy storage; thermal insulation; heat production by brown fat; protective cushion for some organs; filling space, shaping body

cytoplasm is restricted to a thin layer immediately beneath the plasma membrane, and the nucleus is pushed against the edge of the cell. Since the fat globule is dissolved by most histological fixatives, fat cells in most tissue specimens look empty and somewhat collapsed, with some resemblance to chicken wire.

White fat provides thermal insulation, anchors and cushions such organs as the eyeballs and kidneys, and contributes to sex-specific body contours such as the female breasts and hips. On average, women have more fat relative to body weight than men do. Female body fat helps to meet the caloric needs of pregnancy and nursing an infant, and having too little fat reduces female fertility.

Brown fat is found primarily in fetuses, infants, and children; it accounts for up to 6% of an infant's weight, and is concentrated especially in fat pads in the shoulders, upper back, and around the kidneys. Brown fat gets its color from an unusual abundance of blood vessels and certain enzymes in its mitochondria. It stores lipid in the form of multiple droplets rather than one large one. Brown fat is a heat-generating tissue. It has numerous mitochondria, but their metabolism is not linked to ATP synthesis. Therefore, when these cells oxidize fats, they release all of the energy as heat. Hibernating animals accumulate brown fat in preparation for winter and oxidize it solely to generate a little heat during the hibernation period. It is especially significant in human infants and children because they have a larger body surface area, relative to volume, than adults do, and they are more vulnerable than adults to heat loss.

Cartilage

Cartilage (table 3.7) is a relatively stiff connective tissue with a flexible rubbery matrix; you can feel its texture by folding and releasing your external ear or palpating the tip of your nose or your "Adam's apple" (*thyroid cartilage* of the larynx). It is also easily seen in many grocery items—it is the milky-colored gristle at the end of pork ribs and on chicken thigh and breast bones, for example. Among other functions, cartilages shape and support the nose and ears and partially enclose the larynx (voice box), trachea (windpipe), and thoracic cavity.

Cartilage is produced by stem cells called **chondroblasts**[14] (CON-dro-blasts), which secrete the matrix and surround themselves with it until they become trapped in little cavities called **lacunae**[15] (la-CUE-nee). Once enclosed in lacunae, they are called **chondrocytes** (CON-dro-sites). Cartilage only rarely exhibits blood vessels, and even when it does, these vessels are just passing through without giving off capillaries to nourish the tissue. Therefore, nutrition and waste removal depend on solute diffusion through the stiff matrix. Because this is a slow process, chondrocytes have low rates of metabolism and cell division, and injured cartilage heals slowly.

The matrix is rich in glycosaminoglycans and contains collagen fibers that range from invisibly fine to conspicuously coarse. Differences in the fibers provide a basis for classifying cartilage into three types: *hyaline cartilage, elastic cartilage,* and *fibrocartilage.*

Apply What You Know

When the following tissues are injured, which do you think is the fastest to heal, and which do you think is the slowest—cartilages, adipose tissue, or tendons? Explain your reasoning.

---

[14] *chondro* = cartilage, gristle; *blast* = forming

[15] *lacuna* = lake, cavity, pit

TABLE 3.7 Types of Cartilage

Hyaline Cartilage



© Ed Reschke/Getty Images

Figure 3.19 **Hyaline Cartilage in a Bronchus (×400).** AP|R

Microscopic appearance: Clear, glassy matrix, often stained light blue, violet, or pink in tissue sections; fine, dispersed collagen fibers, not usually visible; chondrocytes often in small clusters of three or four cells (*cell nests*), enclosed in lacunae; usually covered by perichondrium

Representative locations: Forms a thin *articular cartilage,* lacking perichondrium, over the ends of bones at movable joints; forms supportive rings and plates around trachea and bronchi; forms a boxlike enclosure around the larynx; a *costal cartilage* attaches the end of a rib to the breastbone; forms much of the fetal skeleton

Functions: Eases joint movements; holds airway open during respiration; moves vocal cords during speech; a precursor of bone in the fetal skeleton and forms the growth zones of long bones of children

Elastic Cartilage



© Ed Reschke/Getty Images

Figure 3.20 **Elastic Cartilage in the External Ear (×1,000).** AP|R

Microscopic appearance: Elastic fibers form weblike mesh amid lacunae; always covered by perichondrium

Representative locations: External ear; epiglottis

Functions: Provides flexible, elastic support

Fibrocartilage



© McGraw-Hill Education/Al Telser, photographer

Figure 3.21 **Fibrocartilage in an Intervertebral Disc (×400).** AP|R

Microscopic appearance: Parallel collagen fibers similar to those of tendon; rows of chondrocytes in lacunae between collagen fibers; never has a perichondrium

Representative locations: Pubic symphysis (anterior joint between two halves of pelvic girdle); intervertebral discs that separate bones of spinal column; menisci, or pads of shock-absorbing cartilage, in knee joint; at points where tendons insert on bones near articular hyaline cartilage

Functions: Resists compression and absorbs shock in some joints; often a transitional tissue between dense connective tissue and hyaline cartilage (for example, at some tendon–bone junctions)

Hyaline[16] (HY-uh-lin) **cartilage** is named for its clear, glassy, microscopic appearance, which stems from the usually invisible fineness of its collagen fibers. **Elastic cartilage** is named for its conspicuous elastic fibers, and **fibrocartilage** for its coarse, readily visible bundles of collagen. Elastic cartilage and most hyaline cartilage are surrounded by a sheath of dense irregular connective tissue called the **perichondrium**[17] (PAIR-ih-CON-dree-um). A reserve population of chondroblasts between the perichondrium and cartilage contributes to cartilage growth throughout life. Perichondrium is lacking from fibrocartilage and from some hyaline cartilage, such as the cartilage caps at the ends of the long bones.

Bone

Bone, or **osseous tissue,** is a hard, calcified connective tissue that composes the skeleton. The term *bone* has two meanings in anatomy—an entire organ such as the femur or mandible, or just the osseous tissue. The bones of the skeleton are composed of not only osseous tissue but also cartilage, bone marrow, dense irregular connective tissue, and other tissue types. Bones support the body as a whole and give protective enclosure for the brain, spinal cord, heart, lungs, and pelvic organs.

There are two forms of osseous tissue: (1) **Spongy bone** fills the heads of the long bones (see fig. 6.5, p. 138) and forms the middle layer of flat bones such as the sternum and cranial bones. Although it is calcified and hard, its delicate slivers and plates give it a spongy appearance. (2) **Compact (dense) bone** is a denser calcified tissue with no spaces visible to the naked eye. It forms the external surfaces of all bones, so spongy bone, when present, is always covered by a shell of compact bone.

Further differences between compact and spongy bone are described in chapter 6. Here, we examine only compact bone (table 3.8). Most specimens you study will probably be chips of dried compact bone ground to microscopic thinness. Most compact bone is arranged as cylinders of tissue that surround **central (haversian**[18]**) canals,** which run longitudinally through the shafts of long bones such as the femur. The bone matrix is deposited in concentric **lamellae**[19]—onionlike layers around each central canal. A central canal and its surrounding lamellae are called an **osteon.** Tiny lacunae between the lamellae are occupied by mature bone cells, or **osteocytes.**[20] Delicate canals called **canaliculi**[21] radiate from each lacuna to its neighbors and allow the osteocytes to contact each other. The bone as a whole is covered with a tough fibrous **periosteum**[22] (PERR-ee-OSS-tee-um) similar to the perichondrium of cartilage.

In the living state, blood vessels and nerves run through the central canals and osteocytes occupy the lacunae and canaliculi. The osseous tissue most commonly presented for introductory laboratory study, however, is dead and dried—devoid of cells, blood vessels, and nerves. For contrast, these bone chips are often saturated with India ink to blacken the central canals, lacunae, and canaliculi (as in fig. 3.22).

About one-third of the dry weight of bone is composed of collagen fibers and glycosaminoglycans, which enable bone to bend slightly under stress (see Deeper Insight 3.3). Two-thirds consists of minerals (mainly calcium and phosphate salts) that enable bones to withstand compression by the weight of the body.

TABLE 3.8 Bone



© McGraw-Hill Education/Dennis Strete, photographer

Figure 3.22 Compact Bone (×100).

Microscopic appearance (compact bone, c.s.): Calcified matrix arranged in concentric lamellae around central canals; osteocytes occupy lacunae between adjacent lamellae; lacunae interconnected by delicate canaliculi
Representative location: Skeleton
Functions: Physical support of body; leverage for muscle action; protective enclosure of viscera; reservoir of calcium and phosphorus

---

[16] *hyal* = glass
[17] *peri* = around; *chondri* = cartilage
[18] Clopton Havers (1650–1702), English anatomist
[19] *lam* = plate; *ella* = little
[20] *osteo* = bone; *cyte* = cell
[21] *canal* = canal, channel; *icul* = little
[22] *peri* = around; *oste* = bone

DEEPER INSIGHT 3.3

Brittle Bone Disease

Osteogenesis[23] *imperfecta* (OI) is a hereditary defect of collagen deposition in the bones. Collagen-deficient bones are exceptionally brittle, and so this disorder is also called *brittle bone disease*. Children with OI often exhibit bone fractures even at birth, and they suffer frequent spontaneous fractures throughout childhood. They may have deformed teeth as well as hearing impairments resulting from deformity of the middle-ear bones. Children with OI are sometimes mistaken for battered children, and their parents falsely accused, before the disease is diagnosed. In severe cases, the child is stillborn or dies soon after birth, whereas other persons live with OI into adulthood. Little can be done for children with this disease except for very careful handling, prompt treatment of fractures, and orthopedic braces to minimize skeletal deformity.

Blood

Blood (table 3.9) is a fluid connective tissue that travels through tubular blood vessels. Its primary function is to transport cells and dissolved matter from place to place. It may seem odd that a tissue as fluid as blood and another as rock hard as bone are both considered connective tissues, but they have more in common than first meets the eye. Like other connective tissues, blood is composed of more ground substance than cells. Its ground substance is the **blood plasma** and its cellular components are collectively called the **formed elements.** Unlike other connective tissues, blood does not usually exhibit fibers, yet protein fibers do appear when the blood clots. Yet another factor placing blood in the connective tissue category is that it is produced by the connective tissues of the bone marrow and lymphatic organs.

The formed elements are of three kinds—erythrocytes, leukocytes, and platelets. **Erythrocytes**[24] (eh-RITH-ro-sites), or **red blood cells (RBCs),** are the most abundant. In stained blood smears, they look like pink discs with thin, pale centers and no nuclei. Erythrocytes transport oxygen and carbon dioxide. **Leukocytes,** or **white blood cells (WBCs),** serve various roles in defense against infection and other diseases. They travel from one organ to another in the bloodstream and lymph but spend most of their lives in the connective tissues. Leukocytes are somewhat larger than erythrocytes and have conspicuous nuclei that usually appear violet in stained preparations. There are five kinds, distinguished partly by variations in nuclear shape: *neutrophils, eosinophils, basophils, lymphocytes,* and *monocytes.* Their individual characteristics are considered in detail in chapter 19. **Platelets** are small cell fragments scattered amid the blood cells. They are involved in clotting and other mechanisms for minimizing blood loss, and they secrete growth factors that promote blood vessel growth and maintenance.

TABLE 3.9 Blood



© Ed Reschke/Getty Images

Figure 3.23 Blood Smear (×1,000).

Microscopic appearance: RBCs appear as pale pink discs with light centers and no nuclei; WBCs are slightly larger, are much fewer, and have variously shaped nuclei, which usually stain violet; platelets are cell fragments with no nuclei, about one-quarter the diameter of erythrocytes

Representative locations: Contained in heart and blood vessels

Functions: Transports gases, nutrients, wastes, chemical signals, and heat throughout body; provides defensive WBCs; contains clotting agents to minimize bleeding; platelets secrete growth factors that promote tissue maintenance and repair

---

[23] *osteo* = bone; *genesis* = formation

[24] *erythro* = red; *cyte* = cell

Before You Go On

Answer the following questions to test your understanding of the preceding section:

12. What features do most or all connective tissues have in common to set this class apart from nervous, muscular, and epithelial tissue?
13. List the cell and fiber types found in fibrous connective tissues and state their functional differences.
14. What substances account for the gelatinous consistency of the ground substance of fibrous connective tissue?
15. What is areolar tissue? How can it be distinguished from any other kind of connective tissue?
16. Discuss the difference between dense regular and dense irregular connective tissue as an example of the relationship between form and function.
17. Describe some similarities, differences, and functional relationships between hyaline cartilage and bone.
18. What are the three basic kinds of formed elements in blood, and what are their respective functions?

3.4 Nervous and Muscular Tissue—Excitable Tissues

Expected Learning Outcomes

When you have completed this section, you should be able to

a. explain what distinguishes excitable tissues from other tissues;
b. name the cell types that compose nervous tissue;
c. identify the major parts of a nerve cell;
d. name the three kinds of muscular tissue and describe the differences between them; and
e. visually identify nervous and muscular tissues from specimens or photographs.

Excitability is a characteristic of all living cells, but it is developed to its highest degree in nervous and muscular tissues, which are therefore described as **excitable tissues.** The basis for their excitation is an electrical charge difference (voltage) called the *membrane potential,* which occurs across the plasma membranes of all cells. Nervous and muscular tissues respond quickly to outside stimuli by means of changes in membrane potential. In nerve cells, these changes result in the rapid transmission of signals to other cells. In muscle cells, they result in contraction, or shortening of the cell.

Nervous Tissue

Nervous tissue is specialized for communication by means of electrical and chemical signals. It consists of **neurons** (NOOR-ons), or nerve cells, and a much greater number of supportive **neuroglia** (noo-ROG-lee-uh), or **glial** (GLEE-ul) **cells,** which protect and assist the neurons (table 3.10). Neurons detect stimuli, respond quickly, and transmit information to other cells. Each neuron has a prominent **neurosoma,** or cell body, that houses the nucleus and

TABLE 3.10 **Nervous Tissue**



© Ed Reschke/Getty Images

Figure 3.24 A Neuron and Glial Cells of a Spinal Cord Smear (×400). AP|R

Microscopic appearance: Most sections show a few large neurons, usually with rounded or stellate cell bodies (neurosomas) and fibrous processes (axon and dendrites) extending from the neurosomas; neurons are surrounded by a greater number of much smaller glial cells, which lack dendrites and axons

Representative locations: Brain, spinal cord, nerves, ganglia

Function: Internal communication

most other organelles. This is the cell's center of genetic control and protein synthesis. Neurosomas are usually round, ovoid, or stellate in shape. Extending from the neurosoma, there are usually multiple short, branched processes called **dendrites,**[25] which receive signals from other cells and conduct messages to the neurosoma, and a single, much longer **axon (nerve fiber),** which sends outgoing signals to other cells. Some axons are more than a meter long and extend from the brainstem to the foot.

Glial cells constitute most of the volume of the nervous tissue. They are usually much smaller than neurons. There are six types of glial cells, described in chapter 13, which provide a variety of supportive, protective, and "housekeeping" functions for the nervous system. Although they communicate with neurons and each other, they do not transmit long-distance signals.

Nervous tissue is found in the brain, spinal cord, nerves, and ganglia (aggregations of neurosomas forming knotlike swellings in nerves). Local variations in the structure of nervous tissue are described in chapters 13 to 16.

Muscular Tissue

Muscular tissue is specialized to contract when it is stimulated, and thus to exert a physical force on other tissues, organs, or fluids; for example, a skeletal muscle pulls on a bone, the heart contracts and pumps blood, and the bladder contracts and expels urine. Not only do movements of the body and its limbs depend on muscular tissue, but so do such processes as digestion, waste elimination, breathing, speech, and blood circulation. The muscles are also an important source of body heat.

There are three types of muscular tissue—*skeletal, cardiac,* and *smooth*—which differ in appearance, physiology, and function (table 3.11). **Skeletal muscle** consists of long, threadlike cells called **muscle fibers.** Most of it is attached to bones, but there are exceptions in the tongue, upper esophagus, some facial muscles, and some **sphincter**[26] (SFINK-tur) muscles (ringlike or cufflike muscles that open and close body passages). Each cell contains multiple nuclei adjacent to the plasma membrane. Skeletal muscle is described as *striated* and *voluntary.* The first term refers to alternating light and dark bands, or **striations** (stry-AY-shuns), created by the overlapping pattern of cytoplasmic protein filaments that cause muscle contraction. The second term, **voluntary,** refers to the fact that we usually have conscious control over skeletal muscles.

Apply What You Know

Although the nuclei of a muscle fiber are pressed against the inside of the plasma membrane, several of those in figure 3.25 appear to be in the middle of the cell. What can account for this appearance? Think in terms of three-dimensional interpretation of two-dimensional histological images.

Cardiac muscle is limited to the heart. It, too, is striated, but it differs from skeletal muscle in its other features. Cardiac muscle is considered **involuntary** because it is not usually under conscious control; it contracts even if all nerve connections to it are severed. Its cells are much shorter, so they are commonly called **myocytes**[27] or **cardiocytes** rather than fibers. The myocytes are branched or notched at the ends. They contain only one nucleus, which is located near the center and is often surrounded by a light-staining region of glycogen, a starchlike energy source. Cardiac myocytes are joined end to end by junctions called **intercalated**[28] (in-TUR-ku-LAY-ted) **discs,** which appear as dark transverse lines separating each myocyte from the next. They may be only faintly visible, however, unless the tissue has been specially stained for them. Gap junctions in the discs enable a wave of excitation to travel rapidly from cell to cell so that all the myocytes of a heart chamber are stimulated and contract almost simultaneously.

Smooth muscle lacks striations and is involuntary. Smooth muscle cells, also called myocytes, are tapered at the ends (fusiform) and relatively short. They have a single centrally placed nucleus. Small amounts of smooth muscle are found in the iris of the eye and in the skin, but most of it, called **visceral muscle,** forms layers in the walls of the digestive, respiratory, and urinary tracts; the uterus; blood vessels; and other organs. In locations such as the esophagus and small intestine, smooth muscle forms adjacent layers, with the cells of one layer encircling the organ and the cells of the other layer running longitudinally. When the circular smooth muscle contracts, it may propel contents such as food through the organ. When the longitudinal layer contracts, it makes the organ shorter and thicker. By regulating the diameter of blood vessels, smooth muscle is very important in controlling blood pressure and flow. Both smooth and skeletal muscle form sphincters that control the emptying of the bladder and rectum.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

19. What do nervous and muscular tissue have in common? What is the primary function of each?
20. What are the two basic types of cells in nervous tissue, and how can they be distinguished from each other?
21. Name the three kinds of muscular tissue, describe how to distinguish them from each other in microscopic appearance, and state a location and function for each one.

---

[25] *dendr* = tree; *ite* = little
[26] *sphinc* = squeeze, bind tightly
[27] *myo* = muscle; *cyte* = cell
[28] *inter* = between; *calated* = inserted

TABLE 3.11 Muscular Tissue

Skeletal Muscle



© Ed Reschke/Getty Images

Figure 3.25 Skeletal Muscle (×400). APR

Microscopic appearance: Long, threadlike, unbranched cells (fibers), relatively parallel in longitudinal tissue sections; striations; multiple nuclei per cell, near plasma membrane

Representative locations: Skeletal muscles, mostly attached to bones but also including voluntary sphincters of the eyelids, urethra, and anus; diaphragm; tongue; some muscles of esophagus

Functions: Body movements, facial expression, posture, breathing, speech, swallowing, control of urination and defecation, and childbirth; under voluntary control

Cardiac Muscle



© Ed Reschke/Getty Images

Figure 3.26 Cardiac Muscle (×400). APR

Microscopic appearance: Short branched cells (myocytes); less parallel appearance than other muscle types in tissue sections; striations; intercalated discs; one nucleus per cell, centrally located and often surrounded by a light zone

Representative location: Heart

Functions: Pumping of blood; under involuntary control

Smooth Muscle



© McGraw-Hill Education/Dennis Strete, photographer

Figure 3.27 Smooth Muscle in the Intestinal Wall (×1,000). APR

Microscopic appearance: Short fusiform cells overlapping each other; nonstriated; one nucleus per cell, centrally located

Representative locations: Usually found as sheets of tissue in walls of viscera and blood vessels; also in iris and associated with hair follicles; involuntary sphincters of urethra and anus

Functions: Swallowing; contractions of stomach and intestines; expulsion of feces and urine; labor contractions; control of blood pressure and flow; control of respiratory airflow; control of pupillary diameter; erection of hairs; under involuntary control

3.5 Glands and Membranes

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe or define different types of glands;
b. describe the typical anatomy of a gland;
c. name and compare different modes of glandular secretion;
d. describe the way tissues are organized to form the body's membranes; and
e. name and describe the major types of membranes in the body.

We have surveyed all of the fundamental categories of human tissue, and we will now look at the way in which multiple tissue types are assembled to form the body's glands and membranes.

Glands

A **gland** is a cell or organ that secretes substances for use elsewhere in the body or for elimination as waste. The gland product may be something synthesized by the gland cells (such as digestive enzymes) or something removed from the tissues and modified by the gland (such as urine and sweat). Its product is called a **secretion** if it is useful to the body (such as a digestive enzyme or hormone) and an **excretion** if it is a waste product (such as urine). Glands are composed predominantly of epithelial tissue, but usually have a supporting connective tissue framework and capsule.

Endocrine and Exocrine Glands

Glands are broadly classified as endocrine or exocrine. Both types originate as invaginations of a surface epithelium (fig. 3.28). Multicellular **exocrine**[29] (EC-so-crin) **glands** maintain their contact with the surface by way of a **duct,** an epithelial tube that conveys their secretion to the surface. The secretion may be released to the body surface, as in the case of sweat, mammary, and tear glands, but more often it is released into the lumen (cavity) of another organ such as the mouth or intestine. **Endocrine**[30] (EN-do-crin) **glands** lose their contact with the surface and have no ducts. They do, however, have a high density of blood capillaries and secrete their products directly into the blood (fig. 3.29a). The secretions of endocrine glands, called **hormones,** function as chemical messengers to stimulate cells elsewhere in the body. Endocrine glands are the subject of chapter 18.

The exocrine–endocrine distinction is not always clear. The liver is mainly an exocrine gland that secretes one of its products, bile,

---

[29] *exo* = out; *crin* = to separate, secrete
[30] *endo* = in, into; *crin* = to separate, secrete



Figure 3.28 **Development of Exocrine and Endocrine Glands.** (a) An exocrine gland begins with epithelial cells proliferating into the connective tissue below. Apoptosis of the cells in the core hollows out a duct. The gland remains connected to the surface for life by way of this duct and releases its secretions onto the epithelial surface. (b) An endocrine gland begins similarly, but the cells connecting it to the surface degenerate while the secretory tissue becomes infiltrated with blood capillaries. The secretory cells will secrete their products (hormones) into the blood.

through a system of ducts, but secretes hormones, albumin, and other products directly into the bloodstream. Several glands, such as the pancreas, testis, ovary, and kidney, have both exocrine and endocrine components. Nearly all of the viscera have at least some cells that secrete hormones, even though most of these organs are not usually thought of as glands (for example, the brain and heart).

Unicellular glands are secretory cells found in an epithelium that is predominantly nonsecretory. They can be endocrine or exocrine. For example, the respiratory tract, which is lined mainly by ciliated cells, also has a liberal scattering of nonciliated, mucus-secreting goblet cells, which are exocrine (see fig. 3.7). The digestive tract has many scattered endocrine cells, which secrete hormones that coordinate digestive processes.

Exocrine Gland Structure

Figure 3.29b and c show a generalized multicellular exocrine gland—a structural arrangement found in such organs as the mammary gland, pancreas, and salivary glands. Most glands are enclosed in a fibrous **capsule.** The capsule often gives off extensions called **septa**[31] (singular, *septum*), or **trabeculae**[32] (trah-BEC-you-lee), that divide the interior of the gland into compartments called **lobes,** which are visible to the naked eye. Finer connective tissue septa may further subdivide each lobe into microscopic **lobules** (LOB-yools). Blood vessels, nerves, and the gland's ducts generally travel through these septa. The connective tissue framework of the gland, called its **stroma,** supports and organizes the glandular tissue. The cells that perform the tasks of synthesis and secretion are collectively called the **parenchyma**[33] (pa-REN-kih-muh). This is typically simple cuboidal or simple columnar epithelium.

Exocrine glands are classified as **simple** if they have a single unbranched duct and **compound** if they have a branched duct (fig. 3.30). If the duct and secretory portion are of uniform diameter, the gland is called **tubular.** If the secretory cells form a dilated sac, the gland is called **acinar** and the sac is an **acinus**[34] (ASS-ih-nus), or **alveolus**[35] (AL-vee-OH-lus). A gland in which both the acini and tubules secrete a product is called a **tubuloacinar gland.**

Types of Exocrine Secretions

Exocrine glands are classified not only by their structure but also by the nature of their secretions. **Serous** (SEER-us) **glands** produce relatively thin, watery fluids such as perspiration, milk, tears, and digestive juices. **Mucous glands,** found in the tongue and roof of the mouth among other places, secrete a glycoprotein called *mucin* (MEW-sin). After it is secreted, mucin absorbs water and forms the sticky product *mucus.* (Note that *mucus,* the secretion, is spelled differently from *mucous,* the adjective form of the word.) **Mixed glands,** such as the two pairs of salivary glands in the floor of the mouth, contain both serous and mucous cells and produce a mixture of the two types of secretions. **Cytogenic**[36] **glands** release whole cells. The only examples of these are the testes and ovaries, which produce sperm and egg cells.



Figure 3.29 **General Structure of Endocrine and Exocrine Glands.** (a) Endocrine glands have no ducts but have a high density of blood capillaries and secrete their products (hormones) directly into the bloodstream. (b) Exocrine glands usually have a system of ducts, which often follow the connective tissue septa, until their finest divisions end in saccular acini of secretory cells. (c) Detail of an acinus and the beginning of a duct.
- *What membrane transport process (review pp. 33–36) are the cells of this acinus carrying out?*

Methods of Exocrine Secretion

Exocrine glands are classified into merocrine, apocrine, and holocrine types according to how they release their secretions. **Merocrine**[37] (MERR-oh-crin) **glands,** also called **eccrine**[38] (EC-rin) **glands,** release their products by means of exocytosis (fig. 3.31a).

---

[31] *septum* = wall
[32] *trab* = plate; *cula* = little
[33] *par* = beside; *enchym* = pour in
[34] *acinus* = berry
[35] *alveol* = cavity, pit
[36] *cyto* = cell; *genic* = producing
[37] *mero* = part; *crin* = to separate, secrete
[38] *ec* = *ex* = out; *crin* = to separate, secrete


Simple coiled tubular
Compound acinar
Compound tubuloacinar
Example: Sweat gland
Example: Mammary gland
Example: Pancreas
Key
Duct
Secretory portion

Figure 3.30 **Some Types of Exocrine Glands.** Glands are classified according to the branching of their ducts and the appearance and extent of the secretory portions.


Milk sugar and protein
Exocytosis
Secretory vesicle
Golgi complex
Milk fat
Plasma membrane
Cytoplasm
Secretion (sebum)
Gland capsule
Disintegrating cells
Mitosis in basal cells replaces cells that disintegrate and die
Intact basal cells
(a) Merocrine
(b) Apocrine
(c) Holocrine

Figure 3.31 **The Three Modes of Exocrine Secretion.** (a) Merocrine secretion in a cell of the mammary gland, secreting milk sugar (lactose) and proteins (casein, lactalbumin) by exocytosis. (b) Apocrine secretion of fat by a cell of the mammary gland. Fat droplets coalesce in the cytosol, then bud from the cell surface with a thin coating of cytoplasm and plasma membrane. (c) Holocrine secretion by a sebaceous (oil) gland of the scalp. In this method, entire gland cells break down and become the secretion (sebum).

- *Which of these three glands would require the highest rate of mitosis? Why?*

These include the tear glands, salivary glands, and most others. Mammary glands secrete the sugar and protein of milk by this method, but secrete the milk fat by another method called **apocrine**[39] secretion (fig. 3.31b). Lipids coalesce from the cytosol into a single droplet that buds from the cell surface, covered by a layer of plasma membrane and a very thin film of cell cytoplasm. Sweat glands of the axillary (armpit) region were once thought to use the apocrine method as well. Closer study showed this to be untrue; they are merocrine, but they are nevertheless different from other merocrine glands in function and histological appearance and are still referred to as apocrine sweat glands.

In **holocrine**[40] **glands** (fig. 3.31c), cells accumulate a product and then the entire cell disintegrates, producing a particularly thick, oily secretion composed of cell fragments and the substance the cell had synthesized prior to its disintegration. Only a few glands use this mode of secretion, such as the oil-producing glands of the scalp and certain glands of the eyelid.

Membranes

Chapter 1 describes the major body cavities and the membranes that line them and cover their viscera. We now consider some histological aspects of these membranes. Membranes may be composed of epithelium only, connective tissue only, or both.

The largest membrane of the body is the **cutaneous** (cue-TAY-nee-us) **membrane**—or more simply, the skin (detailed in chapter 5). It consists of a stratified squamous epithelium (epidermis) resting on a layer of connective tissue (dermis).

The two principal kinds of internal membranes are mucous and serous membranes. A **mucous membrane (mucosa)** (mew-CO-sa) lines passageways that open to the exterior: the digestive, respiratory, urinary, and reproductive tracts (fig. 3.32a). A mucosa consists of two to three layers: (1) an epithelium; (2) an areolar connective tissue layer called the **lamina propria**[41] (LAM-ih-nuh PRO-pree-uh); and sometimes (3) a layer of smooth muscle called the **muscularis mucosae** (MUSK-you-LAIR-iss mew-CO-see). Mucous membranes have absorptive, secretory, and protective functions. They are often covered with mucus secreted by goblet cells, multicellular

---

[39] *apo* = from, off, away; *crin* = to separate, secrete

[40] *holo* = whole, entire; *crin* = to separate, secrete

[41] *lamina* = layer; *propria* = of one's own


Mucous coat
Cilia
Mucin in goblet cell
Ciliated cells of pseudostratified epithelium
Epithelium
Basement membrane
Mucous membrane (mucosa)
Blood vessel
Collagen fibers
Fibroblast
Elastic fibers
Lamina propria
Muscularis mucosae
(a)
Serous fluid
Squamous cells
Areolar tissue
Smooth muscle
Serous membrane (serosa)
(b)

Figure 3.32 Mucous and Serous Membranes. (a) Histology of a mucous membrane such as the inner lining of the trachea. (b) Histology of a serous membrane such as the outer surface of the small intestine.

- *Identify another specific place in the body where you could find a membrane of each type.*

mucous glands, or both. The mucus traps bacteria and foreign particles, which keeps them from invading the tissues and aids in their removal from the body. The epithelium of a mucous membrane may also include absorptive, ciliated, and other types of cells.

A **serous membrane (serosa)** is composed of a simple squamous epithelium resting on a thin layer of areolar connective tissue (fig. 3.32b). In the linings of the pleural, pericardial, and peritoneal cavities, the epithelial component is called **mesothelium.** Serous membranes produce watery **serous** (SEER-us) **fluid,** which arises from the blood and derives its name from the fact that it is similar to blood serum in composition. Serous membranes line the insides of some body cavities and form a smooth surface on the outer surfaces of some of the viscera, such as the digestive tract. The pleurae, pericardium, and peritoneum, described in chapter 1, are serous membranes.

The circulatory system is lined with a simple squamous epithelium called **endothelium.** The endothelium rests on a thin layer of areolar tissue, which often rests in turn on an elastic sheet. Collectively, these tissues make up a membrane called the *tunica interna* of the blood vessels and *endocardium* of the heart.

Some joints of the skeletal system are enclosed by fibrous **synovial** (sih-NO-vee-ul) **membranes,** made only of connective tissue. These membranes span the gap from one bone to the next and secrete slippery *synovial fluid* into the joint.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

22. Distinguish between a simple gland and a compound gland, and give an example of each. Distinguish between a tubular gland and an acinar gland, and give an example of each.
23. Contrast the merocrine, apocrine, and holocrine methods of secretion, and name a gland product produced by each method.
24. Describe the differences between a mucous and a serous membrane.
25. Name the layers of a mucous membrane, and state which of the four primary tissue classes composes each layer.

3.6 Tissue Growth, Development, Repair, and Death

Expected Learning Outcomes

When you have completed this section, you should be able to

a. name and describe the modes of tissue growth;
b. name and describe the ways that a tissue can change from one type to another;
c. name and describe the ways the body repairs damaged tissues; and
d. name and describe the modes and causes of tissue shrinkage and death.

Tissue Growth

Tissues grow because their cells increase in number or size. Most embryonic and childhood growth occurs by **hyperplasia**[42] (HY-pur-PLAY-zhyuh), tissue growth through cell multiplication. Skeletal muscle and adipose tissue grow, however, through **hypertrophy**[43] (hy-PUR-truh-fee), the enlargement of preexisting cells. Even a very muscular or obese adult has essentially the same number of muscle fibers or adipocytes as he or she had in late childhood, but the cells may be substantially larger. **Neoplasia**[44] (NEE-oh-PLAY-zhyuh) is the development of a tumor (neoplasm)—whether benign or malignant—composed of abnormal, nonfunctional tissue.

Changes in Tissue Type

You have studied the form and function of more than two dozen types of human tissue in this chapter. You should not leave this subject, however, with the impression that once these tissue types are established, they never change. Tissues are, in fact, capable of changing from one type to another within certain limits. Most obviously, unspecialized tissues of the embryo develop into more diverse and specialized types of mature tissue—embryonic *mesenchyme* to muscle, for example. This development of a more specialized form and function is called **differentiation.**

Epithelia sometimes exhibit **metaplasia,**[45] a change from one type of mature tissue to another. For example, the vagina of a young girl is lined with a simple cuboidal epithelium. At puberty, it changes to a stratified squamous epithelium, better adapted to the future demands of intercourse and childbirth. In the limb bones, most of the red bone marrow of children changes to adipose tissue by adulthood. The nasal cavity is lined with ciliated pseudostratified columnar epithelium. However, if we block one nostril and breathe through the other one for several days, the epithelium in the unblocked passage changes to stratified squamous. In smokers, the ciliated pseudostratified columnar epithelium of the bronchi may transform into a stratified squamous epithelium.

Apply What You Know

What functions of a ciliated pseudostratified columnar epithelium could not be served by a stratified squamous epithelium? In light of this, what might be some consequences of bronchial metaplasia in heavy smokers?

Tissue Repair

Damaged tissues can be repaired in two ways: regeneration or fibrosis. **Regeneration** is the replacement of dead or damaged cells by the same type of cells as before. Regeneration restores normal function to the organ. Most skin injuries (cuts, scrapes, and minor burns) heal by regeneration. The liver also regenerates remarkably well. **Fibrosis** is the replacement of damaged tissue with scar tissue, composed mainly of collagen produced by fibroblasts. Scar tissue helps to hold an organ together, but it does not restore normal function. Examples include the healing of severe cuts and burns, the healing of muscle injuries, and scarring of the lungs in tuberculosis.

---

[42] *hyper* = excessive; *plas* = growth
[43] *hyper* = excessive; *trophy* = nourishment
[44] *neo* = new; *plas* = form, growth
[45] *meta* = change; *plas* = form, growth

Tissue Shrinkage and Death

Atrophy[46] (AT-ruh-fee) is the shrinkage of a tissue through a loss in cell size or number. It results from both normal aging *(senile atrophy)* and lack of use of an organ *(disuse atrophy).* Muscles that are not exercised exhibit disuse atrophy as their cells become smaller. This was a serious problem for the first astronauts who participated in prolonged microgravity space flights. Upon return to normal gravity, they were sometimes too weak from muscular atrophy to walk. Space stations and shuttles now include exercise equipment to maintain the crew's muscular condition. Disuse atrophy also occurs when a limb is immobilized in a cast or by paralysis.

Necrosis[47] (neh-CRO-sis) is the premature, pathological death of tissue due to trauma, toxins, infection, and so forth. **Infarction** is the sudden death of tissue, such as cardiac muscle *(myocardial infarction)* or brain tissue *(cerebral infarction),* that occurs when its blood supply is cut off. **Gangrene** is any tissue necrosis resulting from an insufficient blood supply, often due to arterial blockage. *Dry gangrene,* commonly seen in the feet of diabetics, is characterized by dry, shrunken, dark brown or black skin. **Decubitus ulcers** (**bed sores** or **pressure sores**) are a form of dry gangrene that occurs when immobilized persons, such as those confined to a hospital bed or wheelchair, are unable to move, and continual pressure on the skin cuts off blood flow to an area. Pressure sores occur especially where a bone comes close to the body surface, such as the hips, sacral region, and ankles. Here, the thin layer of skin and connective tissue is especially subject to compression between the bone and a bed or wheelchair. *Wet gangrene* typically occurs in internal organs and involves neutrophil invasion, liquefaction of the tissue, pus, and a foul odor. It can result from appendicitis or an obstructed colon, for example. *Gas gangrene* is necrosis of a wound resulting from infection with certain bacteria of the genus *Clostridium,* usually introduced when a wound is contaminated with soil. The disorder is named for bubbles of gas (mainly hydrogen) that accumulate in the tissue. This is a deadly condition that requires immediate intervention, often including amputation.

Cells dying by necrosis usually swell, exhibit *blebbing* (bubbling) of their plasma membranes, and then rupture. The cell contents released into the tissues trigger an inflammatory response in which macrophages phagocytize the cellular debris.

Apoptosis[48] (AP-op-TOE-sis), or **programmed cell death,** is the normal death of cells that have completed their function and best serve the body by dying and getting out of the way. Cells undergoing apoptosis shrink and are quickly phagocytized by macrophages and other cells. The cell contents never escape, so there is no inflammatory response. Although billions of cells die every hour by apoptosis, they are engulfed so quickly that they are almost never seen except within macrophages.

DEEPER INSIGHT 3.4

Tissue Engineering

Tissue repair is not only a natural process but also a lively area of research in biotechnology. *Tissue engineering* is the artificial production of tissues and organs in the laboratory for implantation in the human body. The process commonly begins with a synthetic scaffold of collagen or polyester, sometimes in the shape of a desired organ such as a blood vessel or ear. The scaffold is then seeded with human cells and allowed to grow until it reaches a point suitable for implantation. Tissue-engineered skin grafts have been on the market for several years. Scientists have also grown liver, bone, tendon, breast, and other tissues in the laboratory. Researchers have grown "human" ears by seeding polymer scaffolds with human cartilage cells and growing them on the backs of immunodeficient mice unable to reject the human tissue (fig. 3.33). It is hoped that ears and noses grown in this way may be used for the cosmetic treatment of children with birth defects or people who have suffered injuries from accidents or animal bites. In recent years, tissue engineering has been used to construct a new bronchus and new urinary bladders in several patients, seeding a nonliving protein scaffold with cells taken from elsewhere in the patients' bodies.



Figure 3.33 **Tissue Engineering.** Scientists have grown an external ear from human tissue on the back of an immunodeficient mouse. The ear can be removed without killing the mouse and used for implantation into a human patient. In the future, such artificial organs might be used to improve the appearance of patients with facial deformities or injuries.

---

[46] *a* = without; *trophy* = nourishment

[47] *necr* = death; *osis* = process

[48] *apo* = away; *ptosis* = falling

One example of apoptosis is that in embryonic development, we produce about twice as many neurons as we need. Those that make connections with target cells survive, while the excess 50% die. Apoptosis also dissolves the webbing between the fingers and toes during embryonic development, it frees the earlobe from the side of the head in people with detached (pendulous) earlobes, and it causes shrinkage of the uterus after pregnancy ends. Immune cells can stimulate cancer cells to "commit suicide" by apoptosis (see photo on p. 53).

Before You Go On

Answer the following questions to test your understanding of the preceding section:

26. Tissues can grow through an increase in cell size or cell number. What are the respective terms for these two kinds of growth?
27. Distinguish between differentiation and metaplasia. Give an example of a developmental process involving each of these.
28. Distinguish between regeneration and fibrosis. Which process restores normal cellular function? What good is the other process if it does not restore function?
29. Distinguish between atrophy, necrosis, and apoptosis, and describe a circumstance under which each of these forms of tissue loss may occur.

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

3.1 The Study of Tissues (p. 54)

1. The scope of histology and how it relates to cytology and gross anatomy
2. The definition of *tissue*
3. The four primary tissue types, the ways in which they differ from each other, and some places where each type can be found
4. The definitions of *matrix* and *ground substance* and their place in tissue structure
5. The preparation of tissues as stained histological sections
6. The common planes of section in histology and their relevance to three-dimensional interpretation of two-dimensional histological images
7. Methods of histological tissue preparation other than sectioning, and the kinds of tissue for which these other methods are commonly applied

3.2 Epithelial Tissue (p. 56)

1. The defining characteristics of epithelial tissue as a class, and general locations in which epithelia are found
2. The location, composition, and functions of a basement membrane
3. The defining characteristics of the two major classes of epithelium and of the four types in each class
4. The appearance and function of goblet cells
5. The appearance, representative locations, and functions of the four types of simple epithelium: simple squamous, simple cuboidal, simple columnar, and pseudostratified columnar
6. The appearance, representative locations, and functions of the four types of stratified epithelium: stratified squamous, stratified cuboidal, stratified columnar, and transitional
7. Differences in structure, location, and function between the nonkeratinized and keratinized forms of stratified squamous epithelium; and the functions of keratin
8. The process of exfoliation and a clinical application of exfoliate cytology

3.3 Connective Tissue (p. 63)

1. The defining characteristics of connective tissue as a class, and general locations in which connective tissues are found
2. The diverse functions of connective tissues and the types of connective tissue that perform such roles
3. The types of connective tissue classified as fibrous connective tissues; the types of cells that are common in fibrous connective tissue, and their functions; and the three types of protein fibers common in fibrous connective tissue and their functional differences
4. The meaning of *ground substance* and its chemical makeup in connective tissue
5. The distinction between loose and dense fibrous connective tissue
6. The appearance, representative locations, and functions of two types of loose fibrous connective tissue: areolar and reticular tissue
7. The appearance, representative locations, and functions of two types of dense fibrous connective tissue: dense regular and dense irregular connective tissue
8. The defining characteristics, microscopic appearance, representative locations, and functions of adipose tissue, and the distinctions between white fat and brown fat
9. The defining characteristics of cartilage as a class, and the composition and organization of its cells and matrix
10. The relationship of the perichondrium to cartilage, and places where the perichondrium is absent
11. The appearance, representative locations, and functions of the three types of cartilage: hyaline cartilage, elastic cartilage, and fibrocartilage
12. The defining characteristics of bone as a class, and the composition and organization of its cells and matrix
13. The relationship of the periosteum to bone
14. The spongy and compact types of bone and how they differ in appearance and location
15. The microscopic appearance, location, and functions of compact bone
16. Why blood is considered a connective tissue

17. The two principal constituents of blood, and its three types of formed elements and how they can be microscopically distinguished from each other
18. The functions of blood

3.4 Nervous and Muscular Tissue—Excitable Tissues (p. 72)

1. The meaning of cell *excitability*, and why nervous and muscular tissue are called excitable tissues in view of the fact that all living cells are excitable
2. The general function of nervous tissue, its two basic cell types, and the functional distinction between the two cell types
3. The parts of a neuron and the function of each part
4. The microscopic appearance and locations of nervous tissue
5. The defining characteristics of muscular tissue as a class, and the diverse functions of muscular tissue
6. The difference between striated and nonstriated muscle, and between voluntary and involuntary muscle
7. The meanings of *sphincter, cardiocyte, myocyte, intercalated disc,* and *visceral muscle*
8. The microscopic appearance, representative locations, and functions of skeletal, cardiac, and smooth muscle

3.5 Glands and Membranes (p. 75)

1. The definition and general composition of a *gland*
2. The distinction between exocrine and endocrine glands and why it is not always easy to make a clear distinction between them
3. Examples and locations of unicellular glands
4. The generalized structure of a multicellular exocrine gland, including structural and functional interpretations of its lobes and lobules, capsule and septa, stroma and parenchyma
5. The system of classifying exocrine glands according to whether their ducts are branched or unbranched and whether or not their secretory cells are aggregated into dilated sacs at the ends of the ducts
6. The distinctions between serous, mucous, mixed, and cytogenic glands, and examples of each
7. The distinctions between merocrine, apocrine, and holocrine glands, and examples of each; the basis for referring to some glands as apocrine
8. The distinctions between cutaneous, mucous, and serous membranes, and locations and functions of each
9. The tissue layers of a mucous membrane and of a serous membrane
10. The nature and locations of endothelium, mesothelium, and synovial membranes

3.6 Tissue Growth, Development, Repair, and Death (p. 79)

1. Three types of tissue growth—hyperplasia, hypertrophy, and neoplasia—including examples of each, how they differ from each other, and whether each is normal or pathological
2. The difference between differentiation and metaplasia, and examples of each
3. Two ways in which the body repairs damaged tissues, and how they differ
4. The meaning of tissue *atrophy,* its causes, and examples
5. Some forms of tissue necrosis, and examples
6. The process of apoptosis, how it differs from necrosis, and examples of situations in which apoptosis occurs

Testing Your Recall

1. Transitional epithelium is found in
    a. the urinary system.
    b. the respiratory system.
    c. the digestive system.
    d. the reproductive system.
    e. all of the above.
2. The external surface of the stomach is covered by
    a. a mucosa.
    b. a serosa.
    c. the parietal peritoneum.
    d. a lamina propria.
    e. a basement membrane.
3. The interior of the respiratory tract is lined with
    a. a serosa.
    b. mesothelium.
    c. a mucosa.
    d. endothelium.
    e. peritoneum.
4. A seminiferous tubule of the testis is lined with _____ epithelium.
    a. simple cuboidal
    b. pseudostratified columnar ciliated
    c. stratified squamous
    d. transitional
    e. stratified cuboidal
5. When the blood supply to a tissue is cut off, the tissue is most likely to undergo
    a. metaplasia.
    b. hyperplasia.
    c. apoptosis.
    d. necrosis.
    e. hypertrophy.
6. A fixative serves to
    a. stop tissue decay.
    b. improve contrast.
    c. repair a damaged tissue.
    d. bind epithelial cells together.
    e. bind cardiac myocytes together.
7. The collagen of areolar tissue is produced by
    a. macrophages.
    b. fibroblasts.
    c. mast cells.
    d. leukocytes.
    e. chondrocytes.
8. Tendons are composed of _____ connective tissue.
    a. skeletal
    b. areolar
    c. dense irregular
    d. yellow elastic
    e. dense regular
9. The shape of the external ear is due to
    a. skeletal muscle.
    b. elastic cartilage.
    c. fibrocartilage.
    d. articular cartilage.
    e. hyaline cartilage.
10. The most abundant formed element(s) of blood is/are
    a. plasma.
    b. erythrocytes.
    c. platelets.
    d. leukocytes.
    e. proteins.
11. The prearranged death of a cell that has completed its task is called _____.
12. The simple squamous epithelium that lines the peritoneal cavity is called _____.
13. Osteocytes and chondrocytes occupy little cavities called _____.
14. Muscle cells and axons are often called _____ because of their shape.
15. Tendons and ligaments are made mainly of the protein _____.
16. _____ is a type of tissue necrosis associated with poor circulation, often combined with infection.

17. An epithelium rests on a layer called the _____ between its deepest cells and the underlying connective tissue.
18. Fibers and ground substance make up the _____ of a connective tissue.
19. In _____ glands, the secretion is formed by the complete disintegration of the gland cells.
20. Any epithelium in which every cell touches the basement membrane is called a _____ epithelium.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. histo-
2. inter-
3. lam-
4. -blast
5. reticul-
6. chondro-
7. peri-
8. thel-
9. exo-
10. necro-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. If we assume that the aorta is cylindrical, an oblique section of it would have an oval shape.
2. Everything in a tissue that is not a cell is classified as ground substance.
3. The colors seen in prepared histology slides are not the natural colors of those tissues.
4. The parenchyma of the liver is a simple cuboidal epithelium.
5. The tongue is covered with keratinized stratified squamous epithelium.
6. Macrophages are large phagocytic cells that develop from lymphocytes.
7. Most of the body’s protein is collagen.
8. Brown fat produces more ATP than white fat.
9. After tissue differentiation is complete, a tissue cannot change type.
10. Erythrocytes have no nuclei.

Answers in appendix A

Testing Your Comprehension

1. A woman in labor is often told to push. In doing so, is she consciously contracting her uterus to expel the baby? Justify your answer based on the muscular composition of the uterus.
2. The Deeper Insights in this chapter describe some hereditary defects in collagen and elastin. Predict some pathological consequences that might result from a hereditary defect in keratin.
3. When cartilage is compressed, water is squeezed out of it, and when pressure is taken off, water flows back into the matrix. This being the case, why do you think cartilage at weight-bearing joints such as the knees can degenerate from lack of exercise?
4. The epithelium of the respiratory tract is mostly of the pseudostratified ciliated type, but in the alveoli—the tiny air sacs where oxygen and carbon dioxide are exchanged between the blood and inhaled air—the epithelium is simple squamous. Explain the functional significance of this histological difference. That is, why don’t the alveoli have the same kind of epithelium as the rest of the respiratory tract?
5. Some human cells are incapable of mitosis (amitotic), including skeletal muscle fibers, neurons, and adipocytes. Considering the mechanics of mitosis (p. 49) and the structure of these cell types, explain why mitosis would be difficult or impossible for them even if they had all the necessary organelles to carry it out.



A 56-day fetus enclosed in the amniotic sac.

© Claude Edelmann/Science Source

CHAPTER

4

HUMAN DEVELOPMENT

CHAPTER OUTLINE

4.1 Gametogenesis and Fertilization 85
- Gametogenesis 85
- Sperm Migration and Capacitation 85
- Fertilization 86

4.2 Stages of Prenatal Development 87
- Preembryonic Stage 88
- Embryonic Stage 90
- Fetal Stage 96

4.3 Clinical Perspectives 100
- Spontaneous Abortion 100
- Birth Defects 100

Study Guide 105

DEEPER INSIGHTS

4.1 Ectopic Pregnancy 89
4.2 Morning Sickness 93
4.3 Placental Disorders 95
4.4 Cerebral Palsy 104

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:

- Fetal sonography (p. 6)
- Cell division (p. 47)

Anatomy & Physiology REVEALED®
aprevealed.com

Module 14: Reproductive System

Perhaps the most dramatic, seemingly miraculous aspect of human life is the transformation of a one-celled fertilized egg into an independent, fully developed individual. From the beginning of recorded thought, people have pondered how a baby forms in the mother's body and how two parents can produce another human being who, although unique, possesses characteristics of each. Aristotle, in his quest to understand prenatal development, dissected bird embryos and established the sequence in which their organs develop. He also speculated that the hereditary traits of a child resulted from the mixing of the male's semen with the female's menstrual blood. Such misconceptions about human development persisted for many centuries. Scientists of the seventeenth century thought that all the features of the infant existed in a preformed state in the egg or the sperm and that they simply unfolded and expanded as the embryo developed. Some thought that the head of the sperm had a miniature human curled up in it, while others thought the miniature person existed in the egg, and the sperm were merely parasites in the semen. Modern developmental biology was not born until the nineteenth century, largely because darwinism at last gave biologists a systematic framework for asking the right questions and discovering unifying themes in the development of diverse species of animals, including humans. It was in that era, too, that the human egg was first observed. Recent decades have brought dramatic leaps in understanding as geneticists have discovered how genes direct the intricate patterns and processes of human development.

This chapter describes only a few of the earliest and most general developments of the human embryo and fetus. Later chapters in the book describe some major features in the specialized development of each organ system. Knowledge of each system's prenatal development provides a deeper understanding of its mature anatomy.

4.1 Gametogenesis and Fertilization

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the major features of sperm and egg production;
b. explain how sperm migrate to the egg and acquire the capacity to fertilize it; and
c. describe the fertilization process and how an egg prevents fertilization by more than one sperm.

Embryology, the study of prenatal development, embraces processes extending from the production of sperm and eggs (**gametogenesis**[1]) to fertilization, embryonic and fetal development, and birth. In this section, we will deal with gametogenesis and fertilization.

Gametogenesis

Sexual reproduction has a great advantage over asexual reproduction in that it produces genetically varied offspring, a crucial key to species survival in a challenging and ever-changing environment. Yet sexual reproduction also presents a problem. If offspring are to be produced by the union of cells from two parents, and if human cells normally have 46 chromosomes each, it might seem that the union of sperm and egg would produce a fertilized egg **(zygote)** with 92 chromosomes. All cells descended from the zygote by mitosis would also have 92. Then in that generation, a sperm with 92 chromosomes would fertilize an egg with 92, and the next generation would have 184 chromosomes in each cell, and so on. Obviously, if sexual reproduction is to combine cells from two parents in each generation, there must be a mechanism for maintaining the normal chromosome number. The solution is to reduce the chromosome number by half as the sex cells **(gametes)** are formed; this function is achieved by a special form of cell division called **meiosis**[2] **(reduction division).**

Gametogenesis and meiosis are detailed in chapter 26 because they are best understood in relation to the structure of the testes and ovaries. However, a few basic facts are needed here in order to best understand fertilization and the beginning of human development. One of the most important properties of the gametes is that they have only 23 chromosomes—half as many as other cells of the body. They are called **haploid**[3] for this reason, whereas the other cells of the body are **diploid.**[4] Diploid cells have two complete sets of 23 chromosomes (46 in all), one set from the mother and one from the father.

Gametogenesis begins with diploid stem cells that sustain their numbers through mitosis. Some of these cells then set off on a path that leads to egg or sperm cells through meiosis. Meiosis consists of two cell divisions (meiosis I and II) that have the effects of creating new genetic variety in the chromosomes and halving the chromosome number (see p. 709 for details).

In sperm production *(spermatogenesis),* meiosis I and II result in four equal-sized cells called spermatids, which then grow tails and develop into sperm without further division. In egg production *(oogenesis),* however, each meiotic division produces one large cell and one much smaller cell. The small cell, called a *polar body,* is merely a way of disposing of the excess chromosomes, and it soon dies. The large cell goes on to become the egg. This uneven division produces an egg with as much cytoplasm as possible—the raw material for early development. In oogenesis, an unfertilized egg dies after meiosis I. Meiosis II never occurs unless the egg is fertilized.

Sperm Migration and Capacitation

The human ovary usually releases one egg (oocyte) per month, around day 14 of a typical 28-day ovarian cycle. This egg is swept into the *uterine (fallopian) tube* by the beating of cilia on the tube's epithelial cells and begins a 3-day trip down the tube toward the uterus. If the egg is not fertilized, it dies within 24 hours and gets no more than one-third of the way to the uterus. Therefore, if a sperm is to fertilize an egg, it must migrate up the tube to meet it. The vast majority of sperm never make it. Although a typical ejaculation may contain 200 million sperm, many of these are destroyed by vaginal acid or drain out of the vagina; others fail to get through the cervical canal into the uterus; still more are destroyed by leukocytes in the uterus; and half of the survivors of all these ordeals are likely to go up the wrong uterine tube. Only about 200 (1 in a million) reach the general vicinity of the egg.

---

[1] *gameto* = marriage, union; *genesis* = production

[2] *meio* = less, fewer

[3] *haplo* = half

[4] *diplo* = double, paired

Freshly ejaculated sperm cannot immediately fertilize an egg. They must undergo a process called **capacitation,** which takes about 10 hours and occurs during their migration in the female reproductive tract. In fresh sperm, the plasma membrane is toughened by cholesterol. During capacitation, fluids of the female reproductive tract dilute inhibitory factors in the semen and leach cholesterol from the membrane of the sperm head. The membrane becomes more fragile so it breaks open more easily upon contact with the egg. It also becomes more permeable to calcium ions, which diffuse into the sperm and stimulate more powerful lashing of the tail.

The anterior tip of the sperm contains a specialized lysosome called the **acrosome,** a packet of enzymes used to penetrate the egg and certain barriers around it (see fig. 26.8, p. 712). When the sperm contacts an egg, the acrosome undergoes exocytosis—the *acrosomal reaction*—releasing these enzymes (fig. 4.1). But the first sperm to reach an egg is not the one to fertilize it. The egg is surrounded by a gelatinous membrane called the *zona pellucida* and, outside this, a layer of small *granulosa cells.* It requires numerous sperm to clear a path through these barriers before one of them can penetrate into the egg itself.

Fertilization

When a sperm contacts the egg's plasma membrane, it digests a hole into the membrane, the sperm and egg membranes fuse, and the sperm nucleus and midpiece enter the egg (fig. 4.1). The *midpiece,* a short segment of the tail behind the head, contains sperm mitochondria, the "powerhouses" that synthesize ATP for sperm motility. The egg, however, usually destroys all sperm mitochondria, so only the mother's mitochondria (and her mitochondrial DNA) pass to the offspring.

It is important that only one sperm be permitted to fertilize an egg. If two or more sperm did so—an event called **polyspermy**—the fertilized egg would have 69 or more chromosomes and would die of a "gene overdose." The egg has two mechanisms for preventing such a wasteful fate: (1) In the *fast block to polyspermy,* binding of the sperm to the egg opens pores called sodium channels in the


Sperm
First polar body
Egg
Corona radiata
Zona pellucida
④ Rejected sperm
③ Fertilization membrane
② Cortical reaction
① Acrosomal reaction
Nucleus
Acrosome
Sperm nucleus fertilizing egg
Fusion of egg and sperm plasma membranes
Cortical granules
Egg membrane
Zona pellucida
Extracellular space
Granulosa cells

Figure 4.1 Fertilization and the Slow Block to Polyspermy.

egg membrane. Sodium ions flow rapidly into the egg and cause a change in the electrical charge on the membrane, which inhibits the binding of any more sperm. (2) This is followed by a *slow block to polyspermy,* in which sperm penetration triggers an inflow of calcium ions. Calcium stimulates a *cortical reaction*—the exocytosis of secretory vesicles called **cortical granules** just beneath the egg membrane. The secretion from these granules swells with water, pushes all remaining sperm away from the egg, and creates an impenetrable **fertilization membrane** between the egg and zona pellucida (fig. 4.1, steps 2–4).

Upon fertilization, the egg completes meiosis II and discards a second polar body. The sperm and egg nuclei swell and become **pronuclei.** A mitotic spindle forms between them, each pronucleus ruptures, and the chromosomes of the two gametes mix into a single diploid set. This mingling of the maternal and paternal chromosomes is called **amphimixis.**[5] The cell, now called a **zygote,**[6] is ready for its first mitotic division.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. Why is it necessary for gametogenesis to reduce the chromosome number of the sex cells by one-half?
2. Explain why sperm cannot fertilize an egg immediately after ejaculation.
3. Explain why nearly all of an individual's mitochondria originate from the mother.
4. Describe two ways a fertilized egg prevents the entry of excess sperm.

4.2 Stages of Prenatal Development

Expected Learning Outcomes

When you have completed this section, you should be able to

a. name and define the three basic stages of prenatal development;
b. describe the implantation of a conceptus in the uterine wall;
c. describe the major events that transform a fertilized egg into an embryo;
d. define and describe the membranes associated with the embryo;
e. describe three ways in which the conceptus is nourished during its development;
f. describe the formation and functions of the placenta; and
g. describe some major developments in the fetal stage.

Human **gestation** (pregnancy) begins with **conception** (fertilization) and ends with **parturition** (childbirth). It lasts an average of 266 days (38 weeks). Since the date of conception is seldom known with certainty, the gestational calendar is usually measured from the day a woman's last menstrual period (LMP) began, and birth is predicted to occur about 280 days (40 weeks) thereafter. Time periods in this chapter, however, are measured from the date of conception.

All the products of conception are collectively called the **conceptus.** This includes all developmental stages from zygote through fetus, and the associated structures such as the umbilical cord, placenta, and amniotic sac.

Clinically, the course of a pregnancy is divided into 3-month intervals called **trimesters:**

1. The **first trimester** (first 12 weeks) extends from fertilization through the first month of fetal life. This is the most precarious stage of development; more than half of all embryos die in the first trimester. Stress, drugs, and nutritional deficiencies are most threatening to the conceptus during this time.
2. The **second trimester** (weeks 13 through 24) is a period in which the organs complete most of their development. It becomes possible with sonography to see good anatomical detail in the fetus. By the end of this trimester, the fetus looks distinctly human, and with intensive care, infants born at the end of the second trimester have a chance of survival.
3. In the **third trimester** (week 25 to birth), the fetus grows rapidly and the organs achieve enough cellular differentiation to support life outside the womb. Some organs, such as the brain, liver, and kidneys, however, require further differentiation after birth to become fully functional. At 35 weeks from fertilization, the fetus typically weighs about 2.5 kg (5.5 pounds). It is considered mature at this weight, and usually survives if born early. Most twins are born at about 35 weeks' gestation and solitary infants at 40 weeks.

From a more biological than clinical standpoint, human development is divided into three stages called the preembryonic, embryonic, and fetal stages (table 4.1).

1. The **preembryonic stage** begins with the zygote and lasts about 16 days. It involves three main processes: (1) *cleavage,* or cell division; (2) *implantation,* in which the conceptus becomes embedded in the mucosal lining *(endometrium)* of the uterus; and (3) *embryogenesis,* in which the embryonic cells migrate and differentiate into three tissue layers called the *ectoderm, mesoderm,* and *endoderm*—collectively known as the **primary germ layers.** Once these layers exist, the individual is called an *embryo.*
2. The **embryonic stage** extends from day 17 until the end of week 8. It is a stage in which the primary germ layers develop into the rudiments of all the organ systems. When all organ systems are represented (even though not yet functional), the individual is considered a *fetus.*
3. The **fetal stage** of development extends from the beginning of week 9 until birth. This is a stage in which the organs grow, differentiate, and become capable of functioning outside the mother's body.

---

[5] *amphi* = both; *mixis* = mingling
[6] *zygo* = union

TABLE 4.1 **The Stages of Prenatal Development**

Stage	Age*	Major Developments and Defining Characteristics
Preembryonic stage		
Zygote	0–30 hours	A single diploid cell formed by the union of egg and sperm
Cleavage	30–72 hours	Mitotic division of the zygote into smaller, identical blastomeres
Morula	3–4 days	A spherical stage consisting of 16 or more blastomeres
Blastocyst	4–16 days	A fluid-filled, spherical stage with an outer mass of trophoblast cells and inner mass of embryoblast cells; becomes implanted in the endometrium; inner mass forms an embryonic disc and differentiates into the three primary germ layers
Embryonic stage	16 days–8 weeks	A stage in which the primary germ layers differentiate into organs and organ systems; ends when all organ systems are present
Fetal stage	8–38 weeks	A stage in which organs grow and mature at a cellular level to the point of being capable of supporting life outside of the mother's body

*From the time of fertilization

Preembryonic Stage

The three major events of the preembryonic stage are cleavage, implantation, and embryogenesis.

Cleavage

Cleavage consists of mitotic divisions that occur in the first 3 days after fertilization, dividing the zygote into smaller and smaller cells called **blastomeres.**[7] It begins as the conceptus migrates down the uterine tube (fig. 4.2). The first cleavage occurs in about 30 hours. Blastomeres divide again at shorter and shorter time intervals, doubling the number of cells each time. In the early divisions, the blastomeres divide simultaneously, but as cleavage progresses, they become less synchronized.

By the time the conceptus arrives in the uterus about 72 hours after ovulation, it consists of 16 or more cells and has a bumpy surface similar to a mulberry—hence it is called a **morula.**[8] The morula is no larger than the zygote; cleavage merely produces smaller and smaller cells. This increases the ratio of cell surface area to volume, which favors efficient nutrient uptake and waste removal, and it produces a larger number of cells from which to form different embryonic tissues.

The morula lies free in the uterine cavity for 4 or 5 days and divides into 100 cells or so. It becomes a hollow sphere called the **blastocyst,** with an internal cavity called the **blastocoel** (BLAST-oh-seal) (fig. 4.3a). The wall of the blastocyst is a layer of squamous cells called the **trophoblast,**[9] which is destined to form part of the placenta and plays an important role in nourishing the embryo. On one side of the blastocoel, adhering to the inside of the trophoblast, is an inner cell mass called the **embryoblast,** which is destined to become the embryo itself.

Implantation

About a week after ovulation, the blastocyst attaches to the endometrium, usually on the "ceiling" or on the posterior wall of the uterus. The process of attachment, called **implantation,** begins when the blastocyst adheres to the endometrium. The trophoblast cells on this side separate into two layers (fig. 4.3b). In the superficial layer, in contact with the endometrium, the plasma membranes break down and the trophoblast cells fuse into a multinucleate mass called the **syncytiotrophoblast**[10] (sin-SISH-ee-oh-TRO-foe-blast). (A *syncytium* is any body of cytoplasm containing multiple nuclei.) The deep layer, close to the embryoblast, is called the **cytotrophoblast**[11] because it retains individual cells divided by membranes.

The syncytiotrophoblast grows into the uterus like little roots, digesting endometrial cells along the way. The endometrium reacts to this injury by growing over the trophoblast and eventually covering it, so the conceptus becomes completely buried in endometrial tissue. Implantation takes about a week and is completed about the time the next menstrual period would have occurred if the woman had not become pregnant.

Embryogenesis

During implantation, the embryoblast undergoes **embryogenesis**—culminating with arrangement of the blastomeres into the three primary germ layers. At the beginning of this phase, the embryoblast separates slightly from the trophoblast, creating a narrow space between them called the **amniotic cavity.** The embryoblast flattens into an **embryonic disc (blastodisc)** composed of two cell layers: the **epiblast** facing the amniotic cavity and the **hypoblast** facing away. Some hypoblast cells multiply and form a membrane called the *yolk sac,* enclosing the blastocoel. Now the embryonic disc is flanked by two spaces: the amniotic cavity on one side and the yolk sac on the other (fig. 4.3c).

---

[7] *blast* = bud, precursor; *mer* = segment, part
[8] *mor* = mulberry; *ula* = little
[9] *troph* = food, nourishment; *blast* = to produce
[10] *syn* = together; *cyt* = cell
[11] *cyto* = cell


Cleavage
Blastomeres
2-celled stage (30 hours)
4-celled stage
8-celled stage
Morula (72 hours)
Zygote
Second polar body
Egg pronucleus
Sperm pronucleus
Zona pellucida
Fertilization (0 hours)
Sperm cell
First polar body
Secondary oocyte
Ovary
Maturing follicle
Corpus luteum
Ovulation
Blastocyst
Implanted blastocyst (6 days)

Figure 4.2 **Migration of the Conceptus.** The egg is fertilized in the distal end of the uterine tube, and the preembryo begins cleavage as it migrates to the uterus.

- *Why can't the egg be fertilized in the uterus?*

Meanwhile, the disc elongates and, around day 15, a groove called the **primitive streak** forms along the midline of the epiblast. These events make the embryo bilaterally symmetric and define its future right and left sides, dorsal and ventral surfaces, and **cephalic**[12] and **caudal**[13] ends.

The next step is **gastrulation**—multiplying epiblast cells migrate medially toward the primitive streak and down into it (fig. 4.4). These cells replace the original hypoblast with a layer now called the **endoderm,** which will become the inner lining of the digestive tract, among other things. A day later, migrating epiblast cells form a third layer between the first two, called the **mesoderm.** Once this is formed, the epiblast is called **ectoderm.** Thus, all three primary germ layers arise from the original epiblast. Some mesoderm overflows the embryonic disc and becomes an extensive *extraembryonic mesoderm,* which contributes to formation of the placenta (fig. 4.3c).

The ectoderm and endoderm are epithelia composed of tightly joined cells, but the mesoderm is a more loosely organized tissue. It later differentiates into a loose fetal connective tissue called **mesenchyme,**[14] which gives rise to such tissues as cardiac and smooth muscle, cartilage, bone, and blood. Mesenchyme is composed of a loose network of wispy *mesenchymal cells* embedded in a gelatinous ground substance.

DEEPER INSIGHT 4.1

Ectopic Pregnancy

In about 1 out of 300 pregnancies, the blastocyst implants somewhere other than the uterus, producing an *ectopic*[15] *pregnancy.* Most cases are *tubal pregnancies,* implantation in the uterine tube. This usually occurs because the conceptus encounters an obstruction such as a constriction resulting from earlier pelvic inflammatory disease, tubal surgery, previous ectopic pregnancies, or repeated miscarriages. The uterine tube cannot expand enough to accommodate the growing conceptus for long; if the situation is not detected and treated early, the tube usually ruptures within 12 weeks, potentially killing the mother. Occasionally, a conceptus implants in the abdominopelvic cavity, producing an *abdominal pregnancy.* It can grow anywhere it finds an adequate blood supply, such as on the outside of the uterus, colon, or bladder. About 1 pregnancy in 7,000 is abdominal. Abdominal pregnancy is a serious threat to the mother's life and usually requires abortion, but about 9% of abdominal pregnancies end in live birth by cesarean section.

---

[12] *cephal* = head
[13] *caud* = tail
[14] *mes* = middle; *enchym* = poured into
[15] *ec* = outside; *top* = place


Lumen of uterus
Blastocyst:
Blastocoel
Trophoblast
Embryoblast
Endometrium:
Epithelium
Endometrial gland
(a) 6–7 days
Embryonic hypoblast
Cytotrophoblast
Syncytiotrophoblast
(b) 8 days
Germ layers:
Ectoderm
Mesoderm
Endoderm
Amnion
Amniotic cavity
Embryonic stalk
Allantois
Yolk sac
Lacuna
Extraembryonic mesoderm
Chorionic villi
(c) 16 days

Figure 4.3 **Implantation.** (a) Structure of the blastocyst 6 to 7 days after ovulation, when it first adheres to the uterine wall. (b) The progress of implantation about 1 day later. The syncytiotrophoblast has begun growing rootlets, which penetrate the endometrium. (c) By 16 days, the conceptus is completely covered by endometrial tissue. The embryo is now flanked by a yolk sac and amnion and is composed of three primary germ layers.


Amnion
Primitive streak
Primitive groove
Epiblast (soon to become ectoderm)
Mesoderm
Hypoblast (undergoing replacement)
Endoderm (replacing hypoblast)
Yolk sac

Figure 4.4 **Formation of the Primary Germ Layers (Gastrulation).** Composite view of the embryonic disc at 15 to 16 days. Epiblast cells migrate over the surface and down into the primitive groove, first replacing the hypoblast cells with endoderm, then filling the space with mesoderm. Upon completion of this process, the uppermost layer is considered ectoderm.

Once the three primary germ layers are formed, embryogenesis is complete and the individual is considered an **embryo.** It is about 2 mm long and 16 days old at this point.

Embryonic Stage

The embryonic stage of development begins around day 16 and extends to the end of week 8. During this time, the placenta and other accessory structures develop, the embryo begins receiving nutrition primarily from the placenta, and the germ layers differentiate into organs and organ systems. Although these organs are still far from functional, it is their presence at 8 weeks that marks the transition from the embryonic stage to the fetal stage.

Embryonic Folding and Organogenesis

In weeks 3 to 4, the embryo grows rapidly and folds around the yolk sac, converting the flat embryonic disc into a somewhat cylindrical form. As the cephalic and caudal ends curve around the ends of the yolk sac, the embryo becomes C-shaped, with the head and tail almost touching (fig. 4.5). The lateral margins of the disc fold


Age
Longitudinal sections
Cross sections
(a) 20–21 days
Amniotic cavity
Amnion
Endoderm
Foregut
Ectoderm
Hindgut
Embryonic stalk
Heart tube
Allantois
Yolk sac
Amniotic cavity
Amnion
Ectoderm
Neural groove
Mesoderm
Yolk sac
(b) 22–24 days
Caudal
Cephalic
Neural tube
Primitive gut
Coelom (body cavity)
(c) 28 days
Liver bud
Lung bud
Primitive gut
Allantois
Vitelline duct
Yolk sac
Amnion
Neural tube
Ectoderm
Mesoderm
Dorsal mesentery
Primitive gut
Endoderm
Coelom (body cavity)

Figure 4.5 **Embryonic Folding.** The left-hand figures are longitudinal sections with the cephalic (head) end facing right. The right-hand figures are cross sections cut about midway along the figures on the left. Part (a) corresponds to figure 4.3c at a slightly later stage of development. Note the general trend for the cephalic and caudal ends of the embryo to curl toward each other (left-hand figures) until the embryo assumes a C shape, and for the flanks of the embryo to fold laterally (right-hand figures), converting the flat embryonic disc into a more cylindrical body and eventually enclosing a body cavity (c).

around the sides of the yolk sac to form the ventral surface of the embryo. This lateral folding encloses a longitudinal channel, the *primitive gut,* which later becomes the digestive tract.

As a result of embryonic folding, the entire surface is covered with ectoderm, which later produces the epidermis of the skin. In the meantime, the mesoderm splits into two layers. One adheres to the ectoderm and the other to the endoderm, thus opening a space called the **coelom** (SEE-loam) between them (fig. 4.5b, c). The coelom becomes divided into the thoracic cavity and peritoneal cavity by a wall, the diaphragm. By the end of week 5, the thoracic cavity further subdivides into pleural and pericardial cavities.

The formation of organs and organ systems during this time is called **organogenesis.** Table 4.2 lists the major tissues and organs that arise from each primary germ layer.

Apply What You Know

List the four primary tissue types of the adult body (see chapter 3), and identify which of the three primary germ layers of the embryo predominantly gives rise to each.

Three major events of organogenesis are especially important for understanding organ development in later chapters: development of the *neural tube,* outpocketing of the throat region to form *pharyngeal pouches,* and the appearance of body segments called *somites.*

The formation of the **neural tube** is called **neurulation.** This process is detailed in chapter 13, but a few essential points are needed here. By week 3, a thick ridge of ectoderm called the

TABLE 4.2 **Derivatives of the Three Primary Germ Layers**

Germ Layer	Major Derivatives
Ectoderm	Epidermis; hair follicles and piloerector muscles; cutaneous glands; nervous system; adrenal medulla; pineal and pituitary glands; lens, cornea, and intrinsic muscles of the eye; internal and external ear; salivary glands; epithelia of the nasal cavity, oral cavity, and anal canal
Mesoderm	Dermis; skeleton; skeletal, cardiac, and most smooth muscle; cartilage; adrenal cortex; middle ear; blood and lymphatic vessels; blood; bone marrow; lymphoid tissue; epithelium of kidneys, ureters, gonads, and genital ducts; mesothelium of abdominal and thoracic cavities
Endoderm	Most of the mucosal epithelium of the digestive and respiratory tracts; mucosal epithelium of urinary bladder and parts of urethra; epithelial components of accessory reproductive and digestive glands (except salivary glands); thyroid and parathyroid glands; thymus

neural plate appears along the midline of the embryonic disc. This is the source of the entire nervous system. As development progresses, the neural plate sinks and becomes a *neural groove,* with a raised edge called the *neural fold* on each side (fig. 4.6a). Cells along the margins of the fold become specialized *neural crest* tissue. Next, the edges of the fold meet and close, somewhat like a zipper, beginning in the middle of the embryo and progressing toward both ends. By 4 weeks, this process creates an enclosed channel, the neural tube (fig. 4.6b).

Neural crest cells separate from the overlying ectoderm and sink a little more deeply into the embryo to flank the neural tube. As described in chapter 13, neural crest cells later migrate to various positions in the embryo and give rise to several other components of the nervous system and to other tissues. By week 4, the cephalic end of the neural tube develops bulges or *vesicles* that develop into different regions of the brain, and the more caudal part becomes the spinal cord. Neurulation is one of the most sensitive periods of prenatal development. Abnormal developments called *neural tube defects* are among the most common and devastating birth defects (see p. 367).

Pharyngeal (branchial) pouches are five pairs of pockets that form in the walls of the future throat of the embryo at around 4 to 5 weeks' gestation (fig. 4.7). They are separated by **pharyngeal arches,** which appear as external bulges in the neck region (see fig. 4.11b). Pharyngeal pouches are among the basic defining characteristics of all vertebrates from fish to mammals. In humans, they give rise to the tympanic (middle-ear) cavity, palatine tonsil, thymus, parathyroid glands, and part of the thyroid gland.



Figure 4.6 **Neurulation.** (a) The neural groove at 20 days. (b) The neural tube at 26 days.

Somites are bilaterally paired blocks of mesoderm that give the embryo a segmented appearance (see fig. 4.11a, b). They represent a primitive vertebrate segmentation that is more distinctly visible in fish, snakes, and other lower vertebrates than in mammals. Humans, however, show traces of this segmentation in the linear series of vertebrae, ribs, spinal nerves, and trunk muscles. Somites begin to appear by day 20 and number 42 to 44 pairs by day 35. Beginning in week 4, each somite subdivides into three tissue masses: a **sclerotome,**[16] which surrounds the neural tube and gives rise to bone tissue of the vertebral column; a **myotome,**[17] which gives rise to muscles of the trunk; and a **dermatome,**[18] which gives rise to the dermis of the skin and to its associated subcutaneous tissue.

At 5 weeks, the embryo exhibits a prominent **head bulge** at the cephalic end and a pair of **optic vesicles** destined to become the eyes. A large **heart bulge** contains a heart, which has been beating since day 22. The **arm buds** and **leg buds,** the future limbs, are present at 24 and 28 days, respectively. Figure 4.11 a–c shows the external appearance of embryos from 3 to 7 weeks.

Extraembryonic Membranes

The conceptus develops a number of accessory organs external to the embryo itself. These include the placenta, umbilical cord, and four **extraembryonic membranes**—the *amnion, yolk sac, allantois,*

---

[16] *sclero* = hard; *tom* = segment
[17] *myo* = muscle; *tom* = segment
[18] *derma* = skin; *tom* = segment



Figure 4.7 **The Pharyngeal Pouches.** (a) Level at which the section in part (b) is taken. (b) Superior view of the pharyngeal region showing the five pairs of pharyngeal pouches (I–V) and their developmental fates. Compare figure 4.11b.

DEEPER INSIGHT 4.2

Morning Sickness

A woman's earliest sign of pregnancy is often *morning sickness,* a nausea that sometimes progresses to vomiting. Severe and prolonged vomiting, called *hyperemesis gravidarum,*[19] can necessitate hospitalization for fluid therapy to restore electrolyte and acid–base balance. The physiological cause of morning sickness is unknown; it may result from the steroids of pregnancy inhibiting intestinal motility. It is also uncertain whether it is merely an undesirable effect of pregnancy or whether it has a biological purpose. An evolutionary hypothesis is that morning sickness is an adaptation to protect the embryo from toxins. The embryo is most vulnerable to toxins at the same time that morning sickness peaks, and women with morning sickness tend to prefer bland foods and avoid spicy and pungent foods, which are highest in toxic compounds. Pregnant women tend also to be especially sensitive to flavors and odors that suggest spoiled food. Women who do not experience morning sickness more often miscarry or bear children with birth defects than do women who experience it.

and *chorion* (fig. 4.8). To understand these membranes, it helps to realize that all mammals evolved from egg-laying reptiles. Within the shelled, self-contained egg of a reptile, the embryo rests atop a yolk, which is enclosed in the yolk sac; it is suspended in a pool of liquid contained in the amnion; it stores toxic wastes in another sac, the allantois; and to breathe, it has a chorion permeable to gases. All of these membranes persist in mammals, including humans, but are modified in their functions.

The **amnion** is a transparent sac that develops from the epiblast of the embryonic disc. It grows to completely enclose the embryo and is penetrated only by the umbilical cord (fig. 4.8a, b; see also fig. 4.11d, f). The amnion fills with **amniotic fluid,** which serves several functions: It enables the embryo to develop symmetrically; keeps its surface tissues from adhering to each other; protects it from trauma, infection, and temperature fluctuations; allows the freedom of movement important to muscle development; and plays a role in lung development as the fetus "breathes" the fluid. At first, the fluid forms by filtration of the mother's blood plasma, but beginning at 8 to 9 weeks, the fetus urinates into the amniotic cavity about once an hour and contributes substantially to the fluid. The volume changes slowly, however, because the fetus swallows fluid at a comparable rate. By the end of gestation, the amnion contains 700 to 1,000 mL of fluid.

Apply What You Know

Oligohydramnios[20] is an abnormally low volume of amniotic fluid. Renal agenesis[21] is a failure of the fetal kidneys to develop. Which of these do you think is most likely to cause the other one? Explain why. What could be some consequences of oligohydramnios to fetal development?

The **yolk sac,** as we have already seen, arises from cells of the embryonic hypoblast opposite the amnion. Initially, it is larger than the embryo and is broadly connected to almost the entire length of the primitive gut. During embryonic folding, however, its connection to the gut becomes constricted and reduced to a narrow

---

[19] *hyper* = excessive; *emesis* = vomiting; *gravida* = pregnant woman; *arum* = of

[20] *oligo* = few, little; *hydr* = water, fluid; *amnios* = amniotic

[21] *a* = without; *genesis* = formation, development


Maternal blood in placental sinus
Uterus
Chorionic villus
Developing placenta
Umbilical blood vessels
Yolk sac
Amnion
Chorion
Amniotic cavity
(a)
Maternal vein
Maternal artery
Myometrium of uterus
Chorionic villus
Placental sinus
Maternal blood
Umbilical cord
Umbilical arteries
Umbilical vein
(c)
Placenta
Yolk sac
Allantois
Umbilical cord
Amniotic fluid in amniotic cavity
Amnion
Chorion
Lumen of uterus
(b)

Figure 4.8 **The Placenta and Extraembryonic Membranes.** (a) Embryo at 4 weeks, enclosed in the amnion and chorion and surrounded by a developing placenta. (b) Fetus at 12 weeks. The placenta is now complete and lies on only one side of the fetus. (c) A portion of the mature placenta and umbilical cord, showing the relationship between fetal and maternal circulation.

passage called the **vitelline**[22] **duct.** Since the embryo continues growing long after the yolk sac stops, the yolk sac becomes a relatively small pouch suspended from the ventral side of the embryo (see figs. 4.5; 4.8a, b). It produces the first blood cells and the stem cells of gametogenesis. These cells migrate by ameboid movement into the embryo, where the blood cells colonize the bone marrow and other tissues, and the gametogenic cells colonize the future gonads. Eventually, the vitelline duct pinches off and disintegrates.

The **allantois** (ah-LON-toe-iss) is initially an outpocketing of the yolk sac; eventually, as the embryo grows, it becomes an outgrowth of the caudal end of the gut connected to it by the **allantoic duct** (see figs. 4.5; 4.8c). It forms a foundation for growth of the umbilical cord and becomes part of the urinary bladder. The allantoic duct can be seen in histological cross sections of the umbilical cord if they are cut close enough to the fetal end.

---

[22] *vitell* = yolk

The **chorion** (CORE-ee-on) is the outermost membrane, enclosing all the rest of the membranes and the embryo. Initially, it has shaggy processes called **chorionic villi** around its entire surface (fig. 4.8a). As the pregnancy advances, the villi on the placental side grow and branch, and this surface is then called the *villous chorion.* The villous chorion forms the fetal portion of the placenta. The villi degenerate over the rest of the surface, which is then called the *smooth chorion.*

Prenatal Nutrition

Over the course of gestation, the conceptus is nourished in three different, overlapping ways. As it travels down the uterine tube and lies free in the uterine cavity before implantation, it absorbs a glycogen-rich secretion of the uterine glands called **uterine milk.** It is the accumulation of this fluid that forms the blastocoel in figure 4.3a.

As it implants, the conceptus makes a transition to **trophoblastic (deciduous) nutrition,** in which the trophoblast digests cells of the endometrium called **decidual**[23] **cells.** Under the influence of progesterone, these cells proliferate and accumulate a rich store of glycogen, proteins, and lipids. As the conceptus burrows into the endometrium, the syncytiotrophoblast digests them and supplies the nutrients to the embryoblast. Trophoblastic nutrition is the only mode of nutrition for the first week after implantation. It remains the dominant source of nutrients through the end of week 8; the period from implantation through week 8 is therefore called the **trophoblastic phase** of the pregnancy. Trophoblastic nutrition wanes as placental nutrition takes over, and ceases entirely by the end of week 12 (fig. 4.9).

In **placental nutrition,** nutrients from the mother's blood diffuse through the placenta into the fetal blood. The **placenta**[24] is a vascular organ attached to the uterine wall on one side and, on the other side, connected to the fetus by way of the **umbilical cord.** It begins to develop about 11 days after conception, becomes the dominant mode of nutrition at the beginning of week 9, and is the sole mode of nutrition from the end of week 12 until birth. The period from week 9 until birth is called the **placental phase** of the pregnancy.

Placental development begins when extensions of the syncytiotrophoblast, the first chorionic villi, penetrate more and more deeply into the endometrium, like the roots of a tree penetrating into the nourishing "soil" of the uterus (fig. 4.8a, c). As they digest their way through uterine blood vessels, the villi become surrounded by pools of free blood. These pools eventually merge to form a single blood-filled cavity, the **placental sinus.** Exposure to maternal blood stimulates increasingly rapid development of the villi, which branch and grow into shapes like little sprigs of cauliflower. Extraembryonic mesenchyme grows into the villi and gives rise to the blood vessels that connect to the embryo by way of the umbilical cord.

DEEPER INSIGHT 4.3

Placental Disorders

The two primary causes of third-trimester bleeding are placental disorders called *placenta previa* and *abruptio placentae.* These are similar and easily mistaken for each other. A suspicion of either condition calls for a sonogram to differentiate the two and decide on a course of action.

The conceptus usually implants high on the body of the uterus or on its ceiling. In about 0.5% of births, however, the placenta is so low on the uterine wall that it partially or completely blocks the cervical canal. This condition, called *placenta previa,* makes it impossible for the infant to be born without the placenta separating from the uterine wall first. Thus, there is a possibility of life-threatening hemorrhaging during pregnancy or birth. If placenta previa is detected by sonography, the infant is delivered by cesarean (C) section.

Abruptio placentae (ah-BRUP-she-oh pla-SEN-tee) is the premature partial or total separation of the placenta from the uterine wall. It occurs in 0.4% to 3.5% of pregnancies. Slight separations may require no more than bed rest and observation, but more severe cases can threaten the life of the mother, fetus, or both. Such cases require early delivery, usually by C-section.



Figure 4.9 **The Timetable of Trophoblastic and Placental Nutrition.** Trophoblastic nutrition peaks at 2 weeks and ends by 12 weeks. Placental nutrition begins at 2 weeks and becomes increasingly important until birth, 39 weeks after implantation. The two modes of nutrition overlap up to the twelfth week, but the *trophoblast phase* is the period in which most nutrients are supplied by trophoblastic nutrition, and the *placental phase* is the period in which most (eventually all) nutrition comes from the placenta.

- *At what point do the two modes contribute equally to prenatal nutrition?*

The fully developed placenta is a disc of tissue about 20 cm in diameter and 3 cm thick (fig. 4.10). At birth, it weighs about one-sixth as much as the baby. The surface facing the fetus is smooth and gives rise to the umbilical cord. The surface facing the uterine wall is rougher. It consists of the chorionic villi, which are contributed by the fetus, and a region of the mother's endometrium called the *decidua basalis.*

---

[23] *decid* = falling off

[24] *placenta* = flat cake



© Dr. Kurt Benirschke

(a) Fetal side



© Dr. Kurt Benirschke

(b) Maternal (uterine) side

Figure 4.10 The Placenta and Umbilical Cord. (a) The fetal side, showing blood vessels, the umbilical cord, and some of the amniotic sac attached to the lower left margin. (b) The maternal (uterine) side, where chorionic villi give the placenta a rougher texture.

- *How many arteries and how many veins are found in the umbilical cord? Which vessels carry blood with the higher level of oxygen?*

The umbilical cord contains two **umbilical arteries** and one **umbilical vein.** Pumped by the fetal heart, blood flows to the placenta by way of the umbilical arteries and then returns to the fetus by way of the umbilical vein. The chorionic villi are *filled with* fetal blood and *surrounded by* maternal blood; the two bloodstreams do not mix unless there is damage to the placental barrier. The barrier, however, is only 3.5 µm thick—half the diameter of a red blood cell. Early in development, the chorionic villi have thick membranes that are not very permeable to nutrients and wastes, and their total surface area is relatively small. As the villi grow and branch, their surface area increases and the membranes become thinner and more permeable. Thus there is a dramatic increase in *placental conductivity,* the rate at which substances diffuse through the membrane. Oxygen and nutrients pass from the maternal blood to the fetal blood, while fetal wastes pass the other way to be eliminated by the mother. Unfortunately, the placenta is also permeable to nicotine, alcohol, and most other drugs in the maternal bloodstream. Nutrition, excretion, and other functions of the placenta are summarized in table 4.3.

Fetal Stage

At the end of 8 weeks, all of the organ systems are present, the individual is about 3 cm long, and it is now considered a **fetus** (fig. 4.11e–f). Its bones have just begun to calcify and the skeletal muscles exhibit spontaneous contractions, although these are too weak to be felt by the mother. The heart, which has been beating since the fourth week, now circulates blood. The heart and liver are very large and form the prominent ventral bulges seen in figure 4.11b, c. The head is nearly half the body length.

The primary changes in the fetal period are that the organ systems become functional and the fetus rapidly gains weight and becomes more human looking. Full-term fetuses average about 36 cm from the crown of the head to the curve of the buttock in a sitting position *(crown-to-rump length, CRL).* Most neonates (newborn infants) weigh between 3.0 and 3.4 kg (6.6–7.5 pounds). About 50% of this weight is gained in the last 10 weeks. Most neonates weighing 1.5 to 2.5 kg are viable, but with difficulty. Neonates weighing under 500 g rarely survive.

The face acquires a more distinctly human appearance during the last trimester. The head grows more slowly than the rest of the body, so its relative length drops from one-half of the CRL at 8 weeks to one-fourth at birth. The skull has the largest circumference of any body region at term (about 10 cm), and passage of the head is therefore the most difficult part of labor.

TABLE 4.3	Functions of the Placenta
Nutritional roles	Transports nutrients such as glucose, amino acids, fatty acids, minerals, and vitamins from the maternal blood to the fetal blood; stores nutrients such as carbohydrates, protein, iron, and calcium in early pregnancy and releases them to the fetus later, when fetal demand is greater than the mother can absorb from the diet
Excretory roles	Transports nitrogenous wastes such as ammonia, urea, uric acid, and creatinine from the fetal blood to the maternal blood
Respiratory roles	Transports O_2 from mother to fetus, and CO_2 from fetus to mother
Endocrine roles	Secretes hormones (estrogen, progesterone, relaxin, human chorionic gonadotropin, and human chorionic somatomammotropin); allows other hormones synthesized by the conceptus to pass into the mother's blood and maternal hormones to pass into the fetal blood
Immune role	Transports maternal antibodies into fetal blood to confer immunity on fetus


Neural plate
Neural groove
Somites
Amnion (cut edge)
Primitive streak
0.1 cm

(a) 3 weeks

Courtesy of the Human Developmental Anatomy Center, National Museum of Health and Medicine, Silver Spring, MD, USA


Future lens
Pharyngeal arches
Heart bulge
Arm bud
Tail
Leg bud
Somites
0.3 cm

(b) 4 weeks

© Anatomical Travelogue/Science Source


Ear
Eye
Digital rays
Liver bulge
Umbilical cord
Foot plate
Tail
1.0 cm

(c) 7 weeks

© Anatomical Travelogue/Science Source

Figure 4.11 The Developing Human. Parts (a) through (d) show development through the end of the embryonic stage. Parts (e) and (f) show the fetal stage of development.


Yolk sac
Amnion
Umbilical cord
2.0 cm

© Dr G. Moscoso/Science Source

(d) 8 weeks



© John Watney/Science Source

(e) 12 weeks


Amnion
Chorion
Uterus
5.0 cm

© Biophoto Associates/Science Source

(f) 20 weeks

The limbs grow more rapidly than the trunk during the fetal stage, and achieve their final relative proportions to the trunk by 20 weeks (fig. 4.11f). Other highlights of fetal development are described in table 4.4, and the development of individual organ systems is detailed in the chapters that follow (table 4.5).

TABLE 4.4 Major Events of Prenatal Development, with Emphasis on the Fetal Stage

End of Week	Crown-to-Rump Length; Weight	Developmental Events
4	0.6 cm; <1 g	Vertebral column and central nervous system begin to form; limbs represented by small limb buds; heart begins beating around day 22; no visible eyes, nose, or ears
8	3 cm; 1 g	Eyes form, eyelids fused shut; nose flat, nostrils evident but plugged with mucus; head nearly as large as the rest of the body; brain waves detectable; bone calcification begins; limb buds form paddlelike hands and feet with ridges called *digital rays,* which then separate into distinct fingers and toes; blood cells and major blood vessels form; genitals present but sexes not yet distinguishable
12	9 cm; 45 g	Eyes well developed, facing laterally; eyelids still fused; nose develops bridge; external ears present; limbs well formed, digits exhibit nails; fetus swallows amniotic fluid and produces urine; fetus moves, but too weakly for mother to feel it; liver is prominent and produces bile; palate is fusing; sexes can be distinguished
16	14 cm; 200 g	Eyes face anteriorly, external ears stand out from head, face looks more distinctly human; body larger in proportion to head; skin is bright pink, scalp has hair; joints forming; lips exhibit sucking movements; kidneys well formed; digestive glands forming and *meconium*[25] (fetal feces) accumulating in intestine; heartbeat can be heard with a stethoscope
20	19 cm; 460 g	Body covered with fine hair called *lanugo*[26] and cheeselike sebaceous secretion called *vernix caseosa,*[27] which protects it from amniotic fluid; skin bright pink; brown fat forms and will be used for postpartum heat production; fetus is now bent forward into “fetal position” because of crowding; *quickening* occurs—mother can feel fetal movements
24	23 cm; 820 g	Eyes partially open; skin wrinkled, pink, and translucent; lungs begin producing *surfactant,* a fluid that aids postpartum respiration; rapid weight gain
28	27 cm; 1,300 g	Eyes fully open; skin wrinkled and red; full head of hair present; eyelashes formed; fetus turns to upside-down *vertex position;* testes begin to descend into scrotum; may survive if born at 28 weeks
32	30 cm; 2,100 g	Subcutaneous fat deposition gives fetus a more plump, babyish appearance, with lighter, less wrinkled skin; testes descending
36	34 cm; 2,900 g	More subcutaneous fat deposited, body plump; lanugo is shed; nails extend to fingertips; limbs flexed; firm hand grip
38	36 cm; 3,400 g	Prominent chest, protruding breasts; testes in inguinal canal or scrotum; fingernails extend beyond fingertips

TABLE 4.5 Information on Further Development of the Organ Systems

Integumentary system	p. 123	Endocrine system	p. 512
Bone tissue	p. 139	Circulatory system, the heart	p. 557
Skeletal system, axial	p. 176	Circulatory system, blood vessels	p. 601
Skeletal system, appendicular	p. 200	Lymphatic system	p. 626
Muscular system	p. 257	Respiratory system	p. 647
Central nervous system	p. 365	Digestive system	p. 678
Autonomic nervous system	p. 456	Urinary system	p. 697
Sense organs	p. 491	Reproductive system	p. 727

---

[25] *mecon* = poppy juice, opium
[26] *lan* = down, wool
[27] *vernix* = varnish; *caseo* = cheese

Before You Go On

Answer the following questions to test your understanding of the preceding section:

5. What is the criterion for classifying a developing individual as an embryo? What is the criterion for classifying it as a fetus? At what gestational ages are these stages reached?
6. In the blastocyst, what are the cells called that eventually give rise to the embryo? What are the cells that carry out implantation?
7. Name and define the three principal processes that occur in the preembryonic stage.
8. Name the three primary germ layers and explain how they develop in the embryonic disc.
9. Distinguish between trophoblastic and placental nutrition.
10. State the functions of the placenta, amnion, chorion, yolk sac, and allantois.
11. Define and describe the *neural tube, primitive gut, somites,* and *pharyngeal pouches.*

4.3 Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. discuss the frequency and some causes of early spontaneous abortion;
b. discuss some types of birth defects and major categories of their causes;
c. describe some syndromes that result from chromosomal nondisjunction; and
d. explain what teratogens are and describe some of their effects.

Expectant parents worry a great deal about the possibilities of miscarriage or birth defects. It is estimated that, indeed, more than half of all pregnancies end in miscarriage, often without the parents realizing that a pregnancy had even begun, and 2% to 3% of infants born in the United States have clinically significant birth defects.

Spontaneous Abortion

Most miscarriages are *early spontaneous abortions,* occurring within 3 weeks of fertilization. Such abortions are easily mistaken for a late and unusually heavy menstrual period. One investigator estimated that 25% to 30% of blastocysts fail to implant; 42% of implanted blastocysts die by the end of the second week; and 16% of those that make it through 2 weeks are seriously abnormal and abort within the next week. Another study found that 61% of early spontaneous abortions were due to chromosomal abnormalities.

Even fetuses that spontaneously abort later in development show a significantly higher incidence of neural tube defects, cleft lip, cleft palate, and chromosomal abnormalities such as Down syndrome and Turner syndrome (described shortly), by comparison to newborns or fetuses of induced abortions. Spontaneous abortion may in fact be a natural mechanism for preventing the development of nonviable fetuses or the birth of severely deformed infants.

Birth Defects

A birth defect, or **congenital**[28] **anomaly,** is the abnormal structure or position of an organ at birth, resulting from a defect in prenatal development. The study of birth defects is called **teratology.**[29] Birth defects are the single most common cause of infant mortality in North America. Not all of them are noticeable at birth; some are detected months to years later. Thus, by the age of 2 years, 6% of children are diagnosed with congenital anomalies, and by age 5, the incidence is 8%. The following sections discuss some known causes of congenital anomalies, but in 50% to 60% of cases, the cause is unknown.

Mutagens and Genetic Anomalies

Genetic anomalies are the most common known cause of birth defects, accounting for an estimated one-third of all cases and 85% of those with an identifiable cause. One cause of genetic defects is **mutations,** or changes in DNA structure. Among other disorders, mutations cause achondroplastic dwarfism (see Deeper Insight 6.3, p. 143), microcephaly (abnormal smallness of the head), stillbirth, and childhood cancer. Mutations can occur through errors in DNA replication during the cell cycle or under the influence of environmental agents called **mutagens,** including some chemicals, viruses, and radiation.

Some of the most common genetic disorders result not from mutagens, however, but from **aneuploidy**[30] (AN-you-ploy-dee), an abnormal number of chromosomes in the zygote. Aneuploidy results from **nondisjunction,** a failure of one of the 23 pairs of chromosomes to separate during meiosis, so that both members of the pair go to the same daughter cell. For example, suppose nondisjunction resulted in an egg with 24 chromosomes instead of the normal 23. If this egg were fertilized by a normal sperm, the zygote would have 47 chromosomes instead of the usual 46.

Figure 4.12 compares normal disjunction of the X chromosomes with some effects of nondisjunction. In nondisjunction, an egg cell may receive both X chromosomes. If it is fertilized by an X-bearing sperm, the result is an XXX zygote and a suite of defects called the **triplo-X syndrome.** Triplo-X females are sometimes infertile and may have mild intellectual impairments. If an XX egg is fertilized by a Y-bearing sperm, the result is an XXY combination, causing **Klinefelter**[31] **syndrome.** People with Klinefelter syndrome are sterile males, usually of average intelligence, but with undeveloped testes, sparse body hair, unusually long arms and legs, and enlarged breasts *(gynecomastia*[32]*).*

---

[28] *con* = with; *gen* = born
[29] *terato* = monster; *logy* = study of
[30] *an* = not; *eu* = good, normal; *ploid* = form
[31] Harry F. Klinefelter, Jr. (1912–90), American physician
[32] *gyneco* = female; *mast* = breast; *ia* = condition


XX
Parent cell with two X chromosomes
Disjunction
X
X
Each daughter cell receives one X chromosome
X
X
X
Y
Sperm adds an X or Y chromosome
XX
XY
XX zygote
XY zygote
Normal female
Normal male
XX
Parent cell with two X chromosomes
Nondisjunction
XX
One daughter cell gets both X chromosomes
One daughter cell gets no X chromosome
XX
X
X
Sperm adds an X chromosome
XXX
X
XXX zygote
XO zygote
Triplo-X syndrome
Turner syndrome

(a) Normal disjunction of X chromosomes **(b) Nondisjunction of X chromosomes**

Figure 4.12 **Disjunction and Nondisjunction.** (a) The outcome of normal disjunction and fertilization by X- or Y-bearing sperm. (b) Two of the possible outcomes of nondisjunction followed by fertilization with an X-bearing sperm.

- *In the right half of the figure, what would be the two outcomes if the sperm carried a Y chromosome instead of an X?*

This syndrome often goes undetected until puberty, when failure to develop secondary sex characteristics may prompt genetic testing.

The other possible outcome of X chromosome nondisjunction is that an egg cell may receive no X chromosome (both X chromosomes are discarded in the first polar body). If fertilized by a Y-bearing sperm, such an egg dies for lack of the indispensable genes on the X chromosome. If it is fertilized by an X-bearing sperm, however, the result is a female with **Turner**[33] **syndrome,** with an XO combination (*O* represents the absence of one sex chromosome). Only 3% of fetuses with Turner syndrome survive to birth. Girls who survive show no serious impairments as children, but tend to have a webbed neck and widely spaced nipples. At puberty, the secondary sex characteristics fail to develop. The ovaries are nearly absent, the girl remains sterile, and she usually has a short stature.

The other 22 pairs of chromosomes (the *autosomes*) are also subject to nondisjunction. Nondisjunction of chromosomes 13 and 18 results in **Patau syndrome (trisomy-13)** and **Edward syndrome (trisomy-18),** respectively. Affected individuals have three copies of the respective chromosome. Nearly all fetuses with these trisomies die before birth. Live-born infants with these syndromes are severely deformed, and fewer than 5% survive for one year. The most common autosomal anomaly is **Down**[34] **syndrome (trisomy-21).** Its signs (fig. 4.13) include retarded

---

[33] Henry H. Turner (1892–1970), American endocrinologist

[34] John Langdon H. Down (1828–96), British physician



© Petit Format/Science Source

© Courtesy Mihaly Bartalos, from Bartalos 1967: *Medical Cytogenetics*, fig. 10.2 p. 154, Waverly, a division of Williams & Wilkins

Figure 4.13 **Down Syndrome.** (a) A child with Down syndrome (right) and her sister. (b) The karyotype (chart of the chromosomes arranged in pairs) seen in Down syndrome, showing the trisomy of chromosome 21. (c) Characteristics of the hand seen in Down syndrome. (d) The epicanthal fold over the medial commissure (canthus) of the left eye.

- *What was the sex of the person from whom the karyotype in part (b) was obtained?*

physical development; short stature; a relatively flat face with a flat nasal bridge; low-set ears; *epicanthal folds* at the median corners of the eyes; an enlarged, protruding tongue; stubby fingers; and a short broad hand with only one palmar crease. People with Down syndrome tend to have outgoing, affectionate personalities. Mental retardation is common and sometimes severe, but is not inevitable. Down syndrome occurs in about 1 out of 700 to 800 live births in the United States and increases in proportion to the age of the mother. The chance of having a child with Down syndrome is about 1 in 3,000 for a woman under 30, 1 in 365 by age 35, and 1 in 9 by age 48.

About 75% of the victims of trisomy-21 die before birth, and about 20% die before the age of 10 years. Typical causes of death include immune deficiency and abnormalities of the heart or kidneys. For those who survive beyond 10 years, modern medical care has extended life expectancy to about 60. After the age of 40, however, many of these people develop early-onset Alzheimer disease, linked to a gene on chromosome 21.

Teratogens

Teratogens[35] are agents that cause anatomical deformities in the fetus. They fall into three major classes: drugs and other chemicals, radiation, and infectious diseases. The effect of a teratogen depends on the genetic susceptibility of the embryo, the dosage of the teratogen, and the time of exposure. Teratogen exposure during the first 2 weeks usually does not cause birth defects, but may cause spontaneous abortion. Teratogens can exert destructive effects at any stage of development, but the period of greatest vulnerability is weeks 3 through 8. Different organs have different critical periods. For example, limb abnormalities are most likely to result from teratogen exposure at 24 to 36 days, and brain abnormalities from exposure at 3 to 16 weeks.

---

[35] *terato* = monster; *gen* = producing

The most notorious teratogenic drug is thalidomide, a sedative first marketed in West Germany in 1957. Thalidomide was taken by women in early pregnancy, often before they knew they were pregnant. By the time it was removed from the world market in 1961, it had affected an estimated 10,000 to 20,000 babies worldwide, many of them born with unformed arms or legs (fig. 4.14) and often with defects of the ears, heart, and intestines. In some Third World countries, people today take thalidomide in a misguided attempt to treat AIDS, resulting in an upswing in severe birth defects. Thalidomide has recently been reintroduced, however, for legitimate but more limited applications under strictly controlled conditions, such as for the treatment of leprosy. Many teratogens produce less obvious effects, including physical or mental retardation, hyperirritability, inattention, strokes, seizures, respiratory arrest, crib death, and cancer. A general lesson to be learned from the thalidomide tragedy and other cases is that pregnant women should avoid all sedatives, barbiturates, and opiates. Even the acne medicine isotretinoin (Accutane) has caused severe birth defects.



© Time & Life Pictures/Getty Images

Figure 4.14 **Schoolboy Showing the Effect of Thalidomide on Limb Development.**

Alcohol causes more birth defects than any other teratogen. Even one drink a day can have adverse effects on fetal and childhood development, some of which are not noticed until a child begins school. Alcohol abuse during pregnancy can cause **fetal alcohol syndrome (FAS),** characterized by a small head, malformed facial features, cardiac and central nervous system defects, stunted growth, and behavioral symptoms such as hyperactivity, nervousness, and a poor attention span. Cigarette smoking also contributes to fetal and infant mortality, ectopic pregnancy, anencephaly (failure of the cerebrum to develop), cleft lip and palate, and cardiac abnormalities.

The effects of ionizing radiation on an embryo were tragically demonstrated by the many grotesque birth defects caused by the 1986 accident at the nuclear power plant at Chernobyl in the Ukraine. Even diagnostic medical X-rays, however, can be teratogenic and should be minimized or avoided during pregnancy.

Apply What You Know

Martha is showing a sonogram of her unborn baby to her coworkers. Her friend Betty tells her she shouldn't have sonograms made because X-rays can cause birth defects. Is Betty's concern well founded? Explain.

Infectious diseases are largely beyond the scope of this book, but it must be noted at least briefly that several microorganisms can cross the placenta and cause serious congenital anomalies, stillbirth, or neonatal death. Common viral infections of the fetus and newborn include herpes simplex, rubella, cytomegalovirus, and human immunodeficiency virus (HIV). Congenital bacterial infections include gonorrhea and syphilis. *Toxoplasma,* a protozoan contracted from meat, unpasteurized milk, and house cats, is another common cause of fetal deformity. Some of these pathogens have relatively mild effects on adults, but because of its immature immune system, the fetus is vulnerable to devastating effects such as blindness, hydrocephalus, cerebral palsy, seizures, and profound physical and mental retardation. Infections of the fetus and newborn are treated in greater detail in microbiology textbooks.

Some congenital anomalies and other developmental disorders are described in table 4.6 and Deeper Insight 4.4.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

12. In what sense can spontaneous abortion be considered a protective mechanism?
13. What is the difference between mutation and nondisjunction?
14. Name and describe two birth defects resulting from nondisjunction of autosomes and two from nondisjunction of sex chromosomes.
15. Name three distinctly different classes of teratogens and give one example from each class.

TABLE 4.6 Some Disorders of Human Development

Anencephaly	Lack of a forebrain due to failure of the cranial roof to form, leaving the forebrain exposed. The exposed tissue dies, and the fetus is born (or stillborn) with only a brainstem. Live-born anencephalic infants are very short-lived.
Cleft lip and palate	Failure of the right and left sides of the lip or palate to fuse medially, resulting in a fissure connecting the oral and nasal cavities, abnormal facial appearance, defective speech, and difficulty suckling. Can be surgically corrected with good cosmetic results.
Clubfoot (talipes)	Deformity of the foot involving an ankle bone, the talus. The sole of the foot is commonly turned medially, and as a child grows, he or she may walk on the ankles rather than on the soles. Can be corrected to some extent with casts, braces, orthopedic shoes, surgery, and other methods to give near-normal appearance and walking.
Cri du chat[36]	A congenital anomaly due to deletion of a portion of chromosome 5. Infants with cri du chat have microcephaly, congenital heart disease, profound mental retardation, and a weak catlike cry.
Hydrocephalus	Abnormal accumulation of cerebrospinal fluid in the brain. When it occurs in the fetus, the cranial bones separate, the head becomes abnormally large, and the face looks disproportionately small. May reduce the cerebrum to a thin shell of nervous tissue. Fatal for about half of patients but can be treated by inserting a shunt that drains fluid from the brain to a vein in the neck.
Meromelia	Partial absence of limbs (as in fig. 4.14), such as the lack of some digits, a hand, or a forearm. Complete absence of a limb is *amelia*.

Disorders Described Elsewhere

Abruptio placentae 95
Achondroplastic dwarfism 143
Birthmarks 116
Cerebral palsy 104
Congenital defects of the kidney 698
Cryptorchidism 715, 732
Dextrocardia 6
Down syndrome 101
Ectopic pregnancy 89
Edward syndrome 101
Fetal alcohol syndrome 103
Hypospadias 715, 732
Klinefelter syndrome 100
Osteogenesis imperfecta 64
Patau syndrome 101
Patent ductus arteriosus 559
Placenta previa 95
Premature birth 648
Respiratory distress syndrome 648
Situs inversus 6
Situs perversus 6
Spina bifida 367
Spontaneous abortion 100, 734
Triplo-X syndrome 100
Turner syndrome 101

DEEPER INSIGHT 4.4

Cerebral Palsy

Cerebral palsy[37] (CP) is a collective term for a group of movement disorders that are present from infancy and result from brain damage occurring before, during, or shortly after birth. It affects about 500,000 children in the United States alone, with about 10,000 new cases per year.

Its causes include fetal infections or radiation exposure, umbilical or placental blood clots, birth trauma, maternal anesthesia during birth, and oxygen deprivation of the brain before or during birth. CP can also result from incidents in infancy and early childhood, up to about age 3: lead poisoning and other environmental toxins, infections such as encephalitis and meningitis, asphyxia from near-drowning or choking on foreign objects, or physical abuse (shaken baby syndrome). It is more common in multiple and premature births and babies of low birth weight than in full-term, solitary infants of normal weight.

CP may involve damage to the motor control centers of the cerebrum or to various pathways that connect the cerebrum to the cerebellum, basal nuclei, and other brain regions involved in motor control (described in chapter 15). It is often associated with other neurological dysfunctions including epilepsy and blindness. CP has no specific relationship to intelligence; although about 31% of CP victims exhibit intellectual disadvantages, this may stem not just from brain injury but from the way these children are treated by people who underestimate their abilities or openly mock them.

Of the various forms of CP, the most common (65% to 75%) is *spastic cerebral palsy*, characterized by tense, rigid muscles and uncontrollable contractures. The victim has difficulty initiating desired muscle movements as well as suppressing unwanted ones. These make movement and speech slow and difficult, and the speech difficulties can adversely affect childhood intellectual and social development.

Cerebral palsy is incurable but nonprogressive—that is, there is no worsening of brain damage over time. Its signs and symptoms can change, however, as a child matures. It is managed by a very multifaceted approach aimed at minimizing the person's limitations, learning to compensate for them, and achieving the fullest possible independent life. Management may include braces or walkers to aid in locomotion; medical control of seizures and muscle spasms; musculoskeletal surgery; physical, occupational, and speech therapy; and psychological support for childhood social development.

---

[36] *cri du chat* = cry of the cat (French)
[37] *palsy* = paralysis

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

4.1 Gametogenesis and Fertilization (p. 85)

1. The meaning of *gametes* and *gametogenesis*
2. How gametes differ from the body's other cells in chromosome number, why this is a necessity of sexual reproduction, and what type of cell division produces this change in chromosome number
3. How the products of spermatogenesis differ from the products of oogenesis
4. The time required for an egg to travel to the uterus, the time limit on fertilization, and what this implies for sperm migration
5. The purpose and process of sperm capacitation
6. The fertilization process, and the reason that many sperm must collaborate so that one of them can fertilize the egg
7. The egg's mechanisms for preventing polyspermy, and why this is important
8. Events involving the sperm and egg nuclei and chromosomes immediately after sperm penetration

4.2 Stages of Prenatal Development (p. 87)

1. The duration of pregnancy and how the date of childbirth is predicted
2. The components of the conceptus
3. The three trimesters of pregnancy and the developmental milestones of each
4. The preembryonic, embryonic, and fetal stages of development; the developmental milestones that define them; and the timetable of these transitions
5. The three major events of the preembryonic stage; the developmental age (in days) at which this stage is concluded; and the product of this stage
6. The process of cleavage; the appearance of the morula and blastocyst; and the two cell masses of the blastocyst and their respective fates
7. The process of implantation, and the origins and respective roles of the syncytiotrophoblast and cytotrophoblast
8. The process of embryogenesis, and the names of the cell layers and extraembryonic membranes that result from it
9. The age at which the developing individual is considered an embryo; its size at that time; and what anatomical feature defines it as an embryo
10. The major changes that occur during the embryonic stage of development
11. How embryonic folding converts the flat embryonic disc into a cylindrical and C-shaped form, and how it gives rise to the primitive gut
12. How the coelom forms, how it divides into the peritoneal and thoracic cavities, and what cavities arise by further division of the thoracic cavity
13. The meaning of *organogenesis,* and some tissues and organs that arise from each of the three primary germ layers of the embryo
14. The process of neurulation, including the progression from neural plate, to neural groove and folds, to neural tube
15. The origin, location, and fate of the neural crests
16. The location and fate of the pharyngeal pouches
17. The location, three subdivisions, and fate of the myotomes
18. The early appearances of the head, heart, and limbs
19. The appearances, relative locations, and functions of the four extraembryonic membranes—amnion, yolk sac, allantois, and chorion—and functions of the amniotic fluid
20. The three modes in which the conceptus is nourished from the time of its migration down the uterine tube to the time of birth; the timetable and overlap between trophoblastic and placental nutrition
21. The development and mature structure of the placenta; the fetal and maternal components of the placenta; and how nutrients, wastes, hormones, and other materials are exchanged through the placenta while preventing the mixing of maternal and fetal blood
22. The relationship of the placenta to the umbilical cord and its three blood vessels
23. The various functions of the placenta, including but not limited to fetal nutrition and waste removal
24. The time at which the individual is considered to be a fetus, and what distinguishes a fetus from an embryo
25. Major events that occur from the beginning of the fetal stage to the time of birth

4.3 Clinical Perspectives (p. 100)

1. The incidence and common causes of early spontaneous abortion
2. The definitions of *teratology* and *congenital anomaly,* and examples of congenital anomalies that are not evident until months to years after birth
3. The distinction between mutation and aneuploidy as genetic causes of birth defects, and examples of birth defects resulting from each of these
4. The meaning of *nondisjunction,* and some types of aneuploidy that result from it
5. The cause and characteristics of Down syndrome (trisomy-21)
6. The meaning of *teratogens;* the three common categories of teratogens; and examples of teratogenic effects in each category
7. The cause and characteristics of fetal alcohol syndrome

Testing Your Recall

1. When a conceptus arrives in the uterus, it is at what stage of development?
   a. zygote
   b. morula
   c. blastomere
   d. blastocyst
   e. embryo

2. The entry of a sperm nucleus into an egg must be preceded by
   a. the cortical reaction.
   b. the acrosomal reaction.
   c. the fast block.
   d. implantation.
   e. cleavage.

3. The primitive gut develops as a result of
   a. gastrulation.
   b. cleavage.
   c. embryogenesis.
   d. embryonic folding.
   e. aneuploidy.

4. Chorionic villi develop from
   a. the zona pellucida.
   b. the endometrium.
   c. the syncytiotrophoblast.
   d. the embryoblast.
   e. the epiblast.
5. Which of these results from aneuploidy?
   a. Turner syndrome
   b. fetal alcohol syndrome
   c. nondisjunction
   d. mutation
   e. rubella
6. Fetal urine accumulates in the _____ and contributes to the fluid there.
   a. placental sinus
   b. yolk sac
   c. allantois
   d. chorion
   e. amnion
7. A preembryo has
   a. a neural tube.
   b. a heart bulge.
   c. a cytotrophoblast.
   d. a coelom.
   e. decidual cells.
8. The feature that distinguishes a fetus from an embryo is that the fetus has
   a. all of the organ systems.
   b. three germ layers.
   c. a placenta.
   d. an amnion.
   e. arm and leg buds.
9. The first blood and future egg and sperm cells come from
   a. the mesoderm.
   b. the hypoblast.
   c. the syncytiotrophoblast.
   d. the placenta.
   e. the yolk sac.
10. For the first 8 weeks of gestation, a conceptus is nourished mainly by
    a. the placenta.
    b. amniotic fluid.
    c. colostrum.
    d. decidual cells.
    e. yolk cytoplasm.
11. Viruses and chemicals that cause congenital anatomical deformities are called _____.
12. Aneuploidy is caused by _____, the failure of a pair of chromosomes to separate in meiosis.
13. The brain and spinal cord develop from a longitudinal ectodermal channel called the _____.
14. Attachment of the conceptus to the uterine wall is called _____.
15. Fetal blood flows through growths called _____, which project into the placental sinus.
16. The enzymes with which a sperm penetrates an egg are contained in an organelle called the _____.
17. Fertilization occurs in a part of the female reproductive tract called the _____.
18. Bone, muscle, and dermis arise from segments of mesoderm called _____.
19. The egg cell has fast and slow blocks to _____, or fertilization by more than one sperm.
20. A developing individual is first classified as a/an _____ when the three primary germ layers have formed.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. haplo-
2. gameto-
3. zygo-
4. tropho-
5. cephalo-
6. gyneco-
7. -genesis
8. syn-
9. meso-
10. terato-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. Freshly ejaculated sperm are more capable of fertilizing an egg than are sperm several hours old.
2. Fertilization normally occurs in the uterus.
3. An egg is usually fertilized by the first sperm that contacts it.
4. By the time a conceptus reaches the uterus, it has already undergone several cell divisions and consists of 16 cells or more.
5. The individual is first considered a fetus when all of the organ systems are present.
6. The placenta becomes increasingly permeable as it develops.
7. During cleavage, the preembryo acquires a greater number of cells but does not increase in size.
8. In oogenesis, a germ cell divides into four equal-sized egg cells.
9. The stage of the conceptus that implants in the uterine wall is the blastocyst.
10. The energy for sperm motility comes from its acrosome.

Answers in appendix A

Testing Your Comprehension

1. Only one sperm is needed to fertilize an egg, yet a man who ejaculates fewer than 10 million sperm is usually infertile. Explain this apparent contradiction. Supposing 10 million sperm were ejaculated, predict how many would come within close range of the egg. How likely is it that any one of these sperm would fertilize it?
2. What is the difference between embryology and teratology?
3. At what point in the time line of table 4.4 do you think thalidomide exerts its teratogenic effect? Explain your reasoning.
4. A teratologist is studying the cytology of a fetus that aborted spontaneously at 12 weeks. She concludes that the fetus was triploid. What do you think this term means? How many chromosomes do you think she found in each of the fetus's cells? To produce this state, what normal process of human development apparently failed?
5. A young woman finds out she is about 4 weeks pregnant. She tells her doctor that she drank heavily at a party 3 weeks earlier, and she is worried about the possible effects of this on her baby. If you were the doctor, would you tell her that there is serious cause for concern? Why or why not?



A human hair emerging from its follicle (SEM)

© SPL/Science Source

PART TWO

CHAPTER 5

THE INTEGUMENTARY SYSTEM

CHAPTER OUTLINE

5.1 The Skin and Subcutaneous Tissue 109
- Functions of the Skin 109
- The Epidermis 110
- The Dermis 112
- The Hypodermis 113
- Skin Color 114
- Skin Markings 116

5.2 Hair and Nails 116
- Hair 116
- Nails 119

5.3 Cutaneous Glands 120
- Sweat Glands 120
- Sebaceous Glands 122
- Ceruminous Glands 122
- Mammary Glands 122

5.4 Developmental and Clinical Perspectives 123
- Prenatal Development of the Integumentary System 123
- The Aging Integumentary System 125
- Skin Disorders 125

Study Guide 128

DEEPER INSIGHTS

5.1 Tension Lines and Surgery 113
5.2 The Evolution of Skin Color 115
5.3 Extra Nipples—An Evolutionary Throwback 122
5.4 Skin Grafts and Artificial Skin 128

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:

- Cell junctions (p. 38)
- Keratinized stratified squamous epithelium (p. 60)
- Areolar and dense irregular connective tissues (pp. 65, 66)
- Merocrine, holocrine, and apocrine gland types (pp. 76–78)

Anatomy & Physiology REVEALED®
aprevealed.com

Module 4: Integumentary System

The first organ system we deal with in this book is also the most visible one—the *integumentary system,* composed of the skin and its glands, hair, and nails. People pay more attention to this organ system than to any other. Being so visible, its appearance strongly affects our social interactions. Few people venture out of the house without first looking in a mirror to see if their skin and hair are presentable. In the United States alone, we spend billions of dollars annually on skin- and hair-care products and cosmetics. A health-care practitioner must not dismiss this as mere vanity, for a positive self-image is important to the attitudes that promote overall health. Care of the integumentary system must be considered as an important part of total patient care.

The appearance of the skin, hair, and nails is a matter of more than esthetics—their inspection is a significant part of a physical examination. They can provide clues not only to their own health, but also to deeper disorders such as liver cancer, anemia, kidney disease, and heart failure. The skin also is the most vulnerable of our organs, exposed to radiation, trauma, infection, and injurious chemicals. Consequently, it needs and receives more medical attention than any other organ system.

5.1 The Skin and Subcutaneous Tissue

Expected Learning Outcomes

When you have completed this section, you should be able to

a. list the functions of the skin and relate them to its structure;
b. describe the histological structure of the epidermis, dermis, and subcutaneous tissue;
c. describe the normal and pathological colors that the skin can have and explain their causes; and
d. describe the common markings of the skin.

The skin, hair, nails, and cutaneous glands (sweat glands and others) constitute the **integumentary**[1] **system;** the skin alone is called the **integument.** The treatment of this system is a branch of medicine called **dermatology.**[2]

The skin is the body's largest and heaviest organ. In adults, it covers an area of 1.5 to 2.0 m^2 and accounts for about 15% of the body weight. It consists of two layers: a stratified squamous epithelium called the *epidermis* and a deeper connective tissue layer called the *dermis* (fig. 5.1). Below the dermis is another connective tissue layer, the *hypodermis,* which is not part of the skin but is customarily studied in conjunction with it.

Most of the skin is 1 to 2 mm thick, but it ranges from less than 0.5 mm on the eyelids to 6 mm between the shoulder blades. The difference is due mainly to variation in the thickness of the dermis, although skin is classified as thick or thin based on the relative thickness of the epidermis alone. **Thick skin** covers the palms, soles, and corresponding surfaces of the fingers and toes. Its epidermis alone is about 0.5 mm thick, due to a very thick surface layer of dead cells called the *stratum corneum.* This layer serves to resist the pressure and friction to which the palms and soles are especially subjected. Thick skin has sweat glands but no hair follicles or sebaceous (oil) glands. The rest of the body is covered with **thin skin,** which has an epidermis about 0.1 mm thick, with a thin stratum corneum. It possesses hair, sebaceous glands, and sweat glands.

Functions of the Skin

The skin is much more than a container for the body. It has a variety of important functions that go well beyond appearance, as we will see here.

1. **Resistance to trauma and infection.** The skin bears the brunt of most physical injuries to the body, but it resists and recovers from trauma better than other organs do. The epidermal cells are packed with the tough protein **keratin** and linked by strong desmosomes that give the epithelium its durability. Few infectious organisms can penetrate the intact skin. Bacteria and fungi colonize the surface, but their numbers are kept in check by its relative dryness and slight acidity (pH 4–6). Its protective acidic film, called the *acid mantle*, also contains antimicrobial chemicals called *dermcidin* and *defensins.* Immune cells called *dendritic cells* in the epidermis stand guard against pathogens that do breach the surface.
2. **Water retention.** The skin is a barrier to water. It prevents the body from absorbing excess water when you are swimming or bathing, but even more importantly, it prevents the body from losing excess water.
3. **Vitamin D synthesis.** The skin carries out the first step in the synthesis of vitamin D, which is needed for bone development and maintenance. The liver and kidneys complete the process.
4. **Sensation.** The skin is our most extensive sense organ. It is equipped with a variety of nerve endings that react to heat, cold, touch, texture, pressure, vibration, and tissue injury (see chapter 17). These sensory receptors are especially abundant on the face, palms, fingers, soles, nipples, and genitals. There are relatively few on the back and in skin overlying joints such as the knees and elbows.
5. **Thermoregulation.** Cutaneous nerve endings called **thermoreceptors** monitor the body surface temperature. In response to chilling, we can better retain body heat by constricting blood vessels of the dermis *(cutaneous vasoconstriction),* keeping warm blood deeper in the body, not so close to the skin surface. In response to overheating, we can lose excess heat by dilating the dermal blood vessels *(cutaneous vasodilation),* allowing more blood to flow close to the surface and lose heat through the skin. If this is insufficient to restore normal temperature, the sweat glands secrete perspiration. The evaporation of sweat can have a

---

[1] *integument* = covering
[2] *dermat* = skin; *logy* = study of


Hairs
Sweat pores
Epidermis
Dermis
Hypodermis
(subcutaneous fat)
Merocrine sweat
gland
Cutaneous blood
vessels
Motor nerve fibers
Dermal papilla
Tactile corpuscle
(touch receptor)
Blood capillaries
Hair follicle
Sebaceous gland
Hair receptor
Apocrine sweat gland
Hair bulb
Sensory
nerve fibers
Piloerector muscle
Lamellated (pacinian)
corpuscle (pressure receptor)

Figure 5.1 **Structure of the Skin and Subcutaneous Tissue.**
The epidermis is peeled up at the upper left corner to show the dermal–epidermal boundary.

powerful cooling effect. Thus, the skin plays key roles in both warming and cooling the body.

6. **Nonverbal communication.** The skin is an important means of communication. Humans, like other primates, have much more expressive faces than most mammals. Complex skeletal muscles insert on dermal collagen fibers and move the skin to create subtle and varied facial expressions (fig. 5.2).



© DLILLC/Corbis

© McGraw-Hill Education/Joe De Grandis, photographer

(a) **(b)**

Figure 5.2 **Importance of the Skin in Nonverbal Expression.**
Primates differ from other mammals in having very expressive faces due to facial muscles that insert on collagen fibers of the dermis and move the skin.

The Epidermis

The **epidermis**[3] is a keratinized stratified squamous epithelium, as discussed in chapter 3. That is, its surface consists of dead cells packed with keratin. Like other epithelia, it lacks blood vessels and depends on the diffusion of nutrients from the underlying connective tissue. It has sparse nerve endings for touch and pain, but most sensations of the skin are due to nerve endings in the dermis.

Cells of the Epidermis

The epidermis is composed of five types of cells (fig. 5.3):

1. **Stem cells** are undifferentiated cells that divide and produce the keratinocytes described next. They are found only in the deepest layer of the epidermis, called the *stratum basale.*
2. **Keratinocytes** (keh-RAT-ih-no-sites) are the great majority of epidermal cells. They are named for their role in synthesizing keratin. In ordinary histological specimens, nearly all visible epidermal cells are keratinocytes.
3. **Melanocytes** also occur only in the stratum basale, amid the stem cells and deepest keratinocytes. They synthesize the brown to black pigment *melanin.* They have long branching processes that spread among the keratinocytes and continually shed melanin-containing fragments from their tips. The keratinocytes phagocytize these fragments and accumulate melanin granules on the "sunny side" of the nucleus. Like a parasol, the pigment

---

[3] *epi* = above, upon; *derm* = skin



Figure 5.3 Strata and Cell Types of the Epidermis. APR

shields the DNA from ultraviolet radiation. Melanocytes are discussed later in relation to ethnic differences in skin color.

4. **Tactile (Merkel[4]) cells,** relatively few in number, are receptors for touch. They, too, are found in the basal layer of the epidermis and are associated with an underlying dermal nerve fiber. The tactile cell and its nerve fiber are collectively called a *tactile (Merkel) disc.*
5. **Dendritic[5] (Langerhans[6]) cells** are found in two layers of the epidermis called the *stratum spinosum* and *stratum granulosum* (described in the next section). They are immune cells that originate in the bone marrow and migrate to the epidermis and epithelia of the oral cavity, esophagus, and vagina. The epidermis has as many as 800 dendritic cells per square millimeter. They stand guard against toxins, microbes, and other pathogens that penetrate into the skin. When they detect such invaders, they carry fragments of the foreign matter to the lymph nodes and alert the immune system so the body can defend itself.

Layers of the Epidermis

Cells of the epidermis are usually arranged in four to five zones, or strata (five in thick skin), shown in figure 5.3. The following description progresses from deep to superficial, and from the youngest to the oldest keratinocytes.

1. The **stratum basale** (bah-SAY-lee) consists mainly of a single layer of cuboidal to low columnar stem cells and keratinocytes resting on the basement membrane. Scattered among these are the melanocytes, tactile cells, and stem cells. As the stem cells divide, they give rise to keratinocytes that migrate toward the skin surface and replace lost epidermal cells. The life history of these cells is described in the next section.
2. The **stratum spinosum** (spy-NO-sum) consists of several layers of keratinocytes; in most places, this is the thickest stratum, but on the palms and soles it is usually exceeded by the stratum corneum. The deepest cells of the stratum spinosum remain capable of mitosis, but as they are pushed farther upward, they cease dividing. Instead, they produce more and more keratin filaments, which cause the cells to flatten. Therefore, the higher up you look in the stratum spinosum, the flatter the cells appear. Dendritic cells are also found throughout the stratum spinosum, but are not usually visible in tissue sections.

   The stratum spinosum is named for an artificial appearance *(artifact)* created by the histological fixation of tissue specimens. Keratinocytes are firmly attached to each other by numerous desmosomes, which partly account for the toughness of the epidermis. Histological fixatives shrink the keratinocytes, so they pull away from each other; however, they remain attached by the desmosomes—like two people holding hands while they step farther apart. The desmosomes thus create bridges from cell to cell, giving each cell a spiny appearance from which we derive the word *spinosum.*
3. The **stratum granulosum** consists of three to five layers of flat keratinocytes—more in thick skin than in thin skin—and some dendritic cells. The keratinocytes of this layer contain coarse, dark-staining *keratohyalin granules* that give the layer

---

[4] F. S. Merkel (1845–1919), German anatomist
[5] *dendr* = tree, branch
[6] Paul Langerhans (1847–88), German anatomist

its name. The functional significance of these granules will be explained shortly.

4. The **stratum lucidum**[7] (LOO-sih-dum) is a thin translucent zone seen only in thick skin. Here, the keratinocytes are densely packed with a clear protein named *eleidin* (ee-LEE-ih-din). The cells have no nuclei or other organelles. Because organelles are absent and eleidin does not stain well, this zone has a pale, featureless appearance with indistinct cell boundaries.
5. The **stratum corneum** consists of up to 30 layers of dead, scaly, keratinized cells that form a durable surface layer. It is especially resistant to abrasion, penetration, and water loss.

The Life History of a Keratinocyte

Dead cells constantly flake off the skin surface. They float around as tiny white specks in the air, settling on household surfaces and forming much of the dust that accumulates there. Because we constantly lose these epidermal cells, they must be continually replaced.

Keratinocytes are produced deep in the epidermis by the mitosis of stem cells in the stratum basale. Some of the deepest keratinocytes in the stratum spinosum also remain mitotic and thus increase their number. Mitosis requires an abundant supply of oxygen and nutrients, which these deep cells acquire from the blood vessels in the nearby dermis. Once the epidermal cells migrate more than two or three cells away from the dermis, their mitosis ceases. Mitosis is seldom seen in prepared slides of the skin, because it occurs mainly at night whereas most histological specimens are taken during the day.

As new keratinocytes are formed, they push the older ones upward. In 30 to 40 days, a keratinocyte makes its way to the skin surface and flakes off. This migration is slower in old age and faster in skin that has been injured or stressed. Injured epidermis regenerates more rapidly than any other tissue in the body. Mechanical stress from manual labor or tight shoes accelerates keratinocyte multiplication and results in *calluses* or *corns,* thick accumulations of dead keratinocytes on the hands or feet.

As keratinocytes are shoved upward by the dividing cells below, they flatten and produce more keratin filaments and lipid-filled **membrane-coating vesicles.** In the stratum granulosum, four important developments occur: (1) The keratohyalin granules release a protein called *filaggrin*, which binds the cytoskeletal keratin filaments together into coarse, tough bundles. (2) The cells produce a tough layer of *envelope proteins* just beneath the plasma membrane, resulting in a nearly indestructible protein sac around the keratin bundles. (3) The membrane-coating vesicles release a lipid mixture that spreads out over the cell surface and waterproofs it. (4) Finally, as these barriers cut the keratinocytes off from the supply of nutrients from below, their nuclei and other organelles degenerate and the cells die, leaving just the tough waterproof sac of keratin.

The foregoing processes result in an **epidermal water barrier** between the stratum granulosum and the stratum spinosum. This barrier is crucial to retaining water in the body and preventing dehydration. Cells above the barrier quickly die, creating a stratum corneum composed of compact layers of dead keratinocytes and cell fragments. Dead keratinocytes exfoliate (flake off) from the epidermal surface as tiny specks called **dander.** *Dandruff* is composed of clumps of dander stuck together by sebum (oil).

A curious effect of the epidermal water barrier is the way our skin wrinkles when we linger in the bath or a lake. The keratin of the stratum corneum absorbs water and swells, but the deeper layers of the skin do not. The thickening of the stratum corneum forces it to wrinkle. This is especially conspicuous on the tips of the fingers and toes ("prune fingers") because they have such a thick stratum corneum and they lack the sebaceous glands that produce water-resistant oil elsewhere on the body. There may be more to the story than this, however, because the wrinkles do not form when the nerves to the fingers are severed, indicating some role for the nervous system. It has recently been hypothesized that this buckling of the skin may serve a function similar to the tread on a car tire, improving our grip by channeling water away when we press our fingertips to wet surfaces.

The Dermis

Beneath the epidermis is a connective tissue layer, the **dermis.** It ranges from 0.2 mm thick in the eyelids to about 4 mm thick in the palms and soles. It is composed mainly of collagen, but also contains elastic and reticular fibers, fibroblasts, and the other cells typical of fibrous connective tissue (described in chapter 3). It is well supplied with blood vessels, cutaneous glands, and nerve endings. The hair follicles and nail roots are embedded in the dermis. The dermis contains smooth muscles in association with the hair follicles, as described later. In the face, skeletal muscles attach to dermal collagen fibers and produce such expressions as a smile, a wrinkle of the forehead, or the lifting of an eyebrow.

The boundary between the epidermis and dermis is histologically conspicuous and usually wavy (see fig. 5.1). The upward waves are fingerlike extensions of the dermis called **dermal papillae,**[8] and the downward waves are extensions of the epidermis called **epidermal ridges.** The dermal and epidermal boundaries thus interlock like corrugated cardboard, an arrangement that resists slippage of the epidermis across the dermis. If you look closely at your hand and wrist, you will see delicate furrows that divide the skin into tiny rectangular to rhomboidal areas. The dermal papillae produce the raised areas between the furrows. On the fingertips, this wavy boundary forms the *friction ridges* discussed on page 116. In highly sensitive areas such as the lips and genitals, exceptionally tall dermal papillae allow nerve fibers and blood capillaries to come closer to the skin surface. This imparts a redder color and more sensitivity to touch in such areas.

Apply What You Know

Dermal papillae are relatively high and numerous in palmar and plantar skin but low and few in number in the face and abdomen. What do you think is the functional significance of this difference?

---

[7] *lucid* = light, clear

[8] *pap* = nipple; *illa* = little

DEEPER INSIGHT 5.1

Tension Lines and Surgery

The collagen bundles in the dermis are arranged mostly in parallel rows that run longitudinally to obliquely in the limbs, but encircle the neck, trunk, wrists, and a few other areas. They keep the skin under constant tension and are thus called *tension lines (Langer*[9] *lines).* If an incision is made in the skin, especially if it is perpendicular to the tension lines, the wound gapes because the collagen bundles pull the edges of the incision apart. Even if the skin is punctured with a circular object such as an ice pick, the wound gapes with a lemon-shaped opening, the direction of the wound axis being perpendicular to the tension lines. Such gaping wounds are relatively difficult to close and tend to heal with excessive scarring. Surgeons make incisions parallel to the tension lines—for example, making a transverse incision when delivering a baby by cesarean section—so that the incisions will gape less and heal with less scarring.

There are two zones of dermis called the papillary and reticular layers (fig. 5.4). The **papillary** (PAP-ih-lerr-ee) **layer** is a thin zone of areolar tissue in and near the dermal papillae. It is especially rich in small blood vessels. The loosely organized tissue of the papillary layer allows for mobility of leukocytes and other defenses against organisms introduced through breaks in the epidermis.

The **reticular**[10] **layer** of the dermis is deeper and much thicker. It consists of dense irregular connective tissue. Leather is composed of the reticular layer of animal skin, attesting to the toughness of this tissue. The boundary between the papillary and reticular layers is often vague. In the reticular layer, the collagen forms thicker bundles with less room for ground substance, and there are often small clusters of adipocytes. Stretching of the skin in obesity and pregnancy can tear the collagen fibers and produce *striae* (STRY-ee), or stretch marks. These occur especially in areas most stretched by weight gain: the thighs, buttocks, abdomen, and breasts.

The Hypodermis

Beneath the skin is a layer called the **hypodermis**[11] **(subcutaneous tissue).** The boundary between the dermis and hypodermis is indistinct, but the hypodermis generally has more areolar and adipose tissue. It pads the body and binds the skin to the underlying tissues. Drugs are introduced here by hypodermic injection because the subcutaneous tissue is highly vascular and absorbs them quickly.

Subcutaneous fat is hypodermis composed predominantly of adipose tissue. It serves as an energy reservoir and thermal

---

[9] Karl Langer (1819–87), Austrian physician

[10] *reti* = network; *cul* = little

[11] *hypo* = below; *derm* = skin



(a)

(b) Papillary layer of dermis

(c) Reticular layer of dermis

© McGraw-Hill Education/Dennis Strete, photographer

© Hossler, Ph.D. Custom Medical Stock Photo/Newscom

© Susumu Nishinaga/Science Source

Figure 5.4 **The Dermis.** (a) Light micrograph of axillary skin, with the collagen stained blue. (b) The papillary layer, made of loose (areolar) tissue, forms the dermal papillae. (c) The reticular layer, made of dense irregular connective tissue, forms the deeper four-fifths of the dermis. APR

insulation. It is not uniformly distributed; for example, it is virtually absent from the scalp but relatively abundant in the breasts, abdomen, hips, and thighs. The subcutaneous fat is usually about 50% of one's total body fat. It averages about 8% thicker in women than in men, and varies with age. Infants and elderly people have less subcutaneous fat than other people and are therefore more sensitive to cold.

Table 5.1 summarizes the layers of the skin and hypodermis.

Skin Color

The most significant factor in skin color is **melanin,** which is produced by melanocytes but accumulates in the keratinocytes of the stratum basale and the stratum spinosum (fig. 5.5). There are two forms of melanin—a brownish black **eumelanin**[12] and a reddish yellow sulfur-containing pigment, **pheomelanin.**[13] People of different skin colors have essentially the same number of melanocytes, but in dark-skinned people, the melanocytes produce greater quantities of melanin, the melanin granules are more spread out than tightly clumped, and the melanin breaks down more slowly. Thus, melanized cells may be seen throughout the epidermis, from stratum basale to stratum corneum. In light-skinned people, the melanin is clumped near the keratinocyte nucleus, so it imparts less color to the cells. It also breaks down more rapidly, so little of it is seen beyond the stratum basale, if even there.

Skin color also varies with exposure to the ultraviolet (UV) rays of sunlight, which stimulate melanin synthesis and darken the skin. A suntan fades as melanin is degraded in older keratinocytes

TABLE 5.1 Stratification of the Skin and Hypodermis

Layer	Description
Epidermis	Keratinized stratified squamous epithelium
Stratum corneum	Dead, keratinized cells of the skin surface
Stratum lucidum	Clear, featureless, narrow zone seen only in thick skin
Stratum granulosum	Two to five layers of cells with dark-staining keratohyalin granules; scanty in thin skin
Stratum spinosum	Many layers of keratinocytes, typically shrunken in fixed tissues but attached to each other by desmosomes, which give them a spiny look; progressively flattened the farther they are from the dermis. Dendritic cells are abundant here but are not distinguishable in routinely stained preparations.
Stratum basale	Single layer of cuboidal to columnar cells resting on basement membrane; site of most mitosis; consists of stem cells, keratinocytes, melanocytes, and tactile cells, but these are not all distinguishable with routine stains. Melanin is conspicuous in keratinocytes of this layer in black to brown skin.
Dermis	Fibrous connective tissue, richly endowed with blood vessels and nerve endings. Sweat glands and hair follicles originate here and in hypodermis.
Papillary layer	Superficial one-fifth of dermis; composed of areolar tissue; often extends upward as dermal papillae
Reticular layer	Deeper four-fifths of dermis; dense irregular connective tissue
Hypodermis	Areolar or adipose tissue between skin and muscle



© Tom & Dee Ann McCarthy/Corbis

© McGraw-Hill Education/Dennis Strete, photographer

© Creatas/PunchStock RF

© McGraw-Hill Education/Dennis Strete, photographer

(a) Dark skin

(b) Light skin

Figure 5.5 **Variation in Skin Pigmentation.** (a) The stratum basale shows heavy deposits of melanin in dark skin. (b) Light skin shows little or no visible melanin.

- *Which of the five types of epidermal cells are the melanized cells in part (a)?*

---

[12] *eu* = true; *melan* = black
[13] *pheo* = dusky; *melan* = black

and the keratinocytes migrate to the surface and exfoliate. The amount of melanin also varies substantially from place to place on the body. It is relatively concentrated in freckles and moles; on the dorsal surfaces of the hands and feet as compared with the palms and soles; in the nipple and areola of the breast; around the anus; on the scrotum and penis; and on the lateral surfaces of the female genital folds *(labia majora).* The contrast between heavily melanized and lightly melanized regions of the skin is more pronounced in some people than in others, but it exists to some extent in nearly everyone. Variation in ancestral exposure to UV radiation is the primary reason for the geographic and ethnic variation in skin color seen today (see Deeper Insight 5.2).

Other factors in skin color are hemoglobin and carotene. **Hemoglobin,** the red pigment of blood, imparts reddish to pinkish hues to the skin. Its color is lightened by the white of the dermal collagen. The skin is redder in places such as the lips, where blood capillaries come closer to the surface and the hemoglobin shows through more vividly. Depending on diet, the stratum corneum and subcutaneous fat may take on a yellowish tint by accumulating compounds related to vitamin A and **carotene,**[14] a yellow pigment acquired from egg yolks and yellow and orange vegetables. This color is often most conspicuous where the stratum corneum is thickest—on the heel and in calluses of the feet.

The skin may also exhibit abnormal colors of diagnostic value:

- **Cyanosis**[15] is blueness of the skin resulting from a deficiency of oxygen in the circulating blood. Oxygen deficiency turns the hemoglobin a reddish violet color, which is lightened to blue-violet as it shows through the white dermal collagen. Oxygen deficiency can result from conditions that prevent the blood from picking up a normal load of oxygen in the lungs, such as airway obstructions in drowning and choking, lung diseases such as emphysema, and respiratory arrest. Cyanosis also occurs in situations such as cold weather and cardiac arrest, when blood flows so slowly through the skin that the tissues consume oxygen faster than freshly oxygenated blood arrives.
- **Erythema**[16] (ERR-ih-THEE-muh) is abnormal redness of the skin. It occurs in such situations as exercise, hot weather, sunburns, anger, and embarrassment. Erythema is caused by increased blood flow in dilated cutaneous blood vessels or by dermal pooling of red blood cells that have escaped from abnormally permeable capillaries, as in sunburn.
- **Pallor** is a pale or ashen color that occurs when there is so little blood flow through the skin that the white color of the dermal collagen shows through. It can result from emotional stress, low blood pressure, cold temperatures, severe anemia, or circulatory shock.
- **Albinism**[17] is a genetic lack of melanin that usually results in milky white hair and skin, and blue-gray eyes. Melanin is synthesized from the amino acid tyrosine by the enzyme tyrosinase. People with albinism have inherited a recessive, nonfunctional tyrosinase gene from both parents.
- **Jaundice**[18] is a yellowing of the skin and whites of the eyes resulting from high levels of bilirubin in the blood. Bilirubin is a hemoglobin breakdown product. When erythrocytes get old, they disintegrate and release their hemoglobin. The liver and spleen convert hemoglobin to bilirubin and other pigments, which the liver excretes in the bile. Bilirubin can accumulate enough to discolor the skin, however, in such situations as a rapid rate of erythrocyte destruction; when diseases such as cancer, hepatitis, and cirrhosis compromise liver function; and in premature infants, whose liver is not well enough developed to dispose of bilirubin efficiently.
- A **hematoma,**[19] or bruise, is a mass of clotted blood showing through the skin. It is usually due to accidental trauma (blows to the skin), but it may indicate hemophilia, other metabolic or nutritional disorders, or physical abuse.

DEEPER INSIGHT 5.2

The Evolution of Skin Color

One of the most conspicuous signs of human variation is skin color, which can range from the color of espresso or milk chocolate to cafe au lait or light peach. Such variation results from a combination of evolutionary selection pressures, especially differences in exposure to ultraviolet radiation (UVR). This accounts for up to 77% of the variation in human skin color.

UVR can have two adverse effects: It causes skin cancer and it breaks down folic acid, a B vitamin needed for normal cell division, fertility, and fetal development. It also has a desirable effect: It stimulates keratinocytes to synthesize vitamin D, which is needed for the absorption of dietary calcium and thus for healthy bone development. Too much UVR and one is at risk of infertility and fetal deformities such as spina bifida; too little and one is at risk of bone deformities such as rickets. Consequently, populations native to the tropics and people descended from them tend to have well-melanized skin to screen out excessive UVR. Populations native to far northern and southern latitudes, where the sunlight is weak, tend to have light skin to allow for adequate UVR penetration. Ancestral skin color is thus partly a compromise between vitamin D and folic acid requirements. Worldwide, women have skin averaging about 4% lighter than men do, perhaps because of their greater need for vitamin D and calcium to support pregnancy and lactation.

But for multiple reasons, there are exceptions. UVR exposure is determined by more than latitude. It increases at higher elevations and in dry air, because the thinner, drier atmosphere filters out less UVR. This helps to explain the dark skin of natives in such localities as the Andes and the high plateaus of Tibet and Ethiopia. Some other exceptions may be the result of human migrations from one latitude to another occurring too recently for their skin color to have adapted to the new level of UVR exposure. Variation may also result from cultural differences in clothing and shelter, intermarriage among people of different geographic ancestries, and darwinian sexual selection—a preference in mate choice for partners of light or dark complexion.

---

[14] *carot* = carrot
[15] *cyan* = blue; *osis* = condition
[16] *eryth* = red; *em* = blood
[17] *alb* = white; *ism* = state, condition
[18] *jaun* = yellow
[19] *hemat* = blood; *oma* = mass

Apply What You Know

An infant brought to a clinic shows abnormally yellow skin. What sign could you look for to help decide whether this was due to jaundice or to a large amount of carotene from strained vegetables in the diet?

Skin Markings

The skin is marked by many lines, creases, ridges, and patches of accentuated pigmentation. **Friction ridges** are the markings on the fingertips that leave distinctive oily fingerprints on surfaces we touch. They are characteristic of most primates, though their function has long been obscure. They enhance one's sensitivity to texture by vibrating when one strokes an uneven surface, thus stimulating sense organs called lamellar corpuscles (see p. 463) deeper in the skin. They are also thought to improve one's grasp and aid in the manipulation of small and rough-surfaced objects. Friction ridges form during fetal development and remain essentially unchanged for life. Everyone has a unique pattern of friction ridges; not even identical twins have identical fingerprints.

Flexion lines (flexion creases) are lines on the flexor surfaces of the digits, palms, wrists, elbows, and other places (see fig. A.19, p. 345). They mark sites where the skin folds during flexion of the joints. The skin is tightly bound to the deeper connective tissue along these lines.

Freckles and moles are tan to black aggregations of melanocytes. **Freckles** are flat, melanized patches that vary with heredity and exposure to the sun. A **mole (nevus)** is an elevated patch of melanized skin, often with hair. Moles are harmless and sometimes even regarded as "beauty marks," but they should be watched for changes in color, diameter, or contour that may suggest malignancy (skin cancer).

Birthmarks, or **hemangiomas,**[20] are patches of discolored skin caused by benign tumors of the blood capillaries. *Capillary hemangiomas* (strawberry birthmarks) usually develop about a month after birth. They become bright red to deep purple and develop small capillary-dense elevations that give them a strawberry-like appearance. About 90% of capillary hemangiomas disappear by the age of 5 or 6 years. *Cavernous hemangiomas* are flatter and duller in color. They are present at birth, enlarge up to 1 year of age, and then regress. About 90% disappear by the age of 9 years. A *port-wine stain* is flat and pinkish to dark purple in color. It can be quite large and remains for life.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. What is the major histological difference between thick and thin skin? Where on the body is each type of skin found?
2. How does the skin help to adjust body temperature?
3. List the five cell types of the epidermis. Describe their locations and functions.
4. List the five layers of epidermis from deep to superficial. What are the distinctive features of each layer?
5. What are the two layers of the dermis? What type of tissue composes each layer?
6. Name the pigments responsible for normal skin colors, and explain how certain conditions can produce discolorations of the skin.

5.2 Hair and Nails

Expected Learning Outcomes

When you have completed this section, you should be able to

a. distinguish between three types of hair;
b. describe the histology of a hair and its follicle;
c. discuss some theories of the purposes served by various kinds of hair;
d. describe the life cycle of a hair; and
e. describe the structure and function of nails.

The hair, nails, and cutaneous glands are the **accessory organs (appendages)** of the skin. Hair and nails consist mainly of dead, keratinized cells. The stratum corneum of the skin is made of pliable *soft keratin,* but the hair and nails are composed mostly of *hard keratin.* Hard keratin is more compact and is toughened by numerous cross-linkages between the keratin molecules.

Hair

A hair is also known as a **pilus** (PY-lus)—in the plural, *pili* (PY-lye). It is a slender filament of keratinized cells that grows from an oblique tube in the skin called a **hair follicle** (fig. 5.6).

Distribution and Types

Hair occurs almost everywhere on the body except the lips, nipples, parts of the genitals, palms and soles, ventral and lateral surfaces of the fingers and toes, and distal segment of the fingers. The trunk and limbs have about 55 to 70 hairs per square centimeter, and the face has about 10 times as many. There are about 30,000 hairs in a man's beard and about 100,000 in the average person's scalp. The density of hair does not differ much from one person to another or even between the sexes; indeed, it is virtually the same in humans, chimpanzees, and gorillas. Differences in apparent hairiness are due mainly to differences in texture and pigmentation.

Not all hair is alike, even on one person. Over the course of our lives, we grow three kinds of hair: lanugo, vellus, and terminal hair. **Lanugo**[21] is fine, downy, unpigmented hair of the fetus. By the time of birth, most of it is replaced by **vellus,**[22] a similarly fine, pale hair. Vellus constitutes about two-thirds of the hair of women, one-tenth of

---

[20] *hem* = blood; *angi* = vessel; *oma* = tumor, mass

[21] *lan* = down, wool

[22] *vellus* = fleece



© Ed Reschke/Getty Images

Figure 5.6 **Structure of a Hair and Follicle.** (a) Anatomy of the follicle and associated structures. (b) Light micrograph of the base of a hair follicle.

the hair of men, and all of the hair of children except for the eyebrows, eyelashes, and hair of the scalp. **Terminal hair** is longer, coarser, and usually more heavily pigmented. It forms the eyebrows and eyelashes; covers the scalp; and after puberty, it forms the axillary and pubic hair, male facial hair, and some of the hair on the trunk and limbs.

Functions of Hair

In most mammals, hair serves to retain body heat when it is cold, but also to shade the skin from excess solar radiation. Humans have too little hair to serve this purpose except on the scalp, where there is no insulating fat. Hair elsewhere on the body plays a variety of roles that are somewhat speculative, but probably best inferred by comparison to the specialized types and patches of hair in other mammals (table 5.2).

Structure of the Hair and Follicle

A hair is divisible into three zones along its length: (1) the **bulb,** a swelling at the base where the hair originates in the dermis or hypodermis; (2) the **root,** which is the remainder of the hair within the follicle; and (3) the **shaft,** which is the portion above the skin surface. The only living cells of a hair are in and near the bulb. The bulb grows around a bud of vascular connective tissue called the **dermal papilla,** which provides the hair with its sole source of nutrition. Immediately above the papilla is a region of mitotically active cells, the **hair matrix,** which is the hair's growth center. All cells higher up are dead.

In cross section, a hair reveals up to three layers. From the inside out, these are the medulla, cortex, and cuticle. The **medulla** is a core of loosely arranged cells and air spaces. It is most prominent in thick hairs such as those of the eyebrows, but narrower in hairs of medium thickness and absent from the thinnest hairs of the scalp and elsewhere. The **cortex** constitutes most of the bulk of a hair. It consists of several layers of elongated keratinized cells that appear cuboidal to flattened in cross sections. The **cuticle** is composed of multiple layers of very thin, scaly, surface cells that overlap each other like roof shingles, with their free edges directed upward (see photo on p. 108). Cells lining the follicle are like shingles facing in the opposite direction. They interlock with the scales

TABLE 5.2	**Functions of Hair**
Hair of the torso and limbs	Vestigial, but serves a sensory purpose as in detection of small insects crawling on the skin
Scalp hair	Heat retention, protection from sun
Beard, pubic, and axillary (armpit) hair	Advertises sexual maturity; associated with apocrine scent glands in these areas and modulates the dispersal of sexual scents (pheromones) from these glands
Guard hairs (vibrissae)	Help keep foreign objects out of nostrils and auditory canal; eyelashes help keep debris from eyes
Eyebrows	Enhance facial expression, may reduce glare of sun and help keep forehead perspiration from eyes



(a-d): © McGraw-Hill Education/Joe De Grandis, photographer

Figure 5.7 **The Basis of Hair Color and Texture.** Straight hair (a and b) is round in cross section whereas curly hair (c and d) is flatter. Blonde hair (a) has scanty eumelanin and a moderate amount of pheomelanin. Eumelanin predominates in black and brown hair (b). Red hair (c) derives its color predominantly from pheomelanin. Gray and white hair (d) lack pigment and have air in the medulla.

• *Which of the hair layers illustrated here corresponds to the scales seen on the hair shafts in the photo on page 108?*

of the hair cuticle and resist pulling on the hair. When a hair is pulled out, this layer of follicle cells comes with it.

The follicle is a diagonal tube that dips deeply into the dermis and sometimes extends as far as the hypodermis. It has two principal layers: an **epithelial root sheath** and a **connective tissue root sheath** (fig. 5.6a, b). The epithelial root sheath, which is an extension of the epidermis, lies immediately adjacent to the hair root. Toward the deep end of the follicle, it widens to form a **bulge,** a source of stem cells for follicle growth. The connective tissue root sheath, derived from the dermis, surrounds the epithelial sheath and is somewhat denser than the adjacent dermal connective tissue.

Associated with the follicle are nerve and muscle fibers. Nerve fibers called **hair receptors** entwine each follicle and respond to hair movements. You can feel their effect by carefully moving a single hair with a pin or by lightly running your finger over the hairs of your arm without touching the skin. Associated with each hair is a **piloerector muscle**—also known as a **pilomotor muscle** or **arrector pili**[23]—a bundle of smooth muscle cells extending from dermal collagen fibers to the connective tissue root sheath of the follicle (see figs. 5.1 and 5.6). In response to cold, fear, touch, or other stimuli, the sympathetic nervous system stimulates the piloerector to contract and thereby makes the hair stand on end. In other mammals, this traps an insulating layer of warm air next to the skin or makes the animal appear larger and less vulnerable to a potential enemy. In humans, it pulls the follicles into a vertical position and causes "goose bumps," but serves no useful purpose.

Hair Texture and Color

The texture of hair is related to differences in cross-sectional shape (fig. 5.7)—straight hair is round, wavy hair is oval, and tightly curly hair is relatively flat. Hair color is due to pigment granules in the cells of the cortex. Brown and black hair are rich in eumelanin. Red hair has less eumelanin but a high concentration of pheomelanin. Blond hair has an intermediate amount of pheomelanin but very little eumelanin. Gray and white hair result from a scarcity or absence of melanins in the cortex and the presence of air in the medulla.

---

[23] *arrect* = erect; *pili* = of a hair



① **Anagen (early)** **Anagen (mature)**
(Growing phase, 6–8 years)
Stem cells multiply and follicle grows deeper into dermis; hair matrix cells multiply and keratinize, causing hair to grow upward; old club hair may persist temporarily alongside newly growing hair.

② **Catagen**
(Degenerative phase, 2–3 weeks)
Hair growth ceases; hair bulb keratinizes and forms club hair; lower follicle degenerates.

③ **Telogen**
(Resting phase, 1–3 months)
Dermal papilla has ascended to level of bulge; club hair falls out, usually in telogen or next anagen.

Figure 5.8 The Hair Cycle.

Hair Growth and Loss

A given hair goes through a **hair cycle** consisting of three developmental stages: anagen, catagen, and telogen (fig. 5.8). At any given time, about 90% of scalp follicles are in the **anagen**[24] phase. In this phase, stem cells from the bulge in the follicle multiply and travel downward, pushing the dermal papilla deeper into the skin and forming the epithelial root sheath. Root sheath cells directly above the papilla form the hair matrix. Here, sheath cells transform into hair cells, which synthesize keratin and then die as they are pushed upward away from the papilla. The new hair grows up the follicle, often alongside an old *club hair* left from the previous cycle.

In the **catagen**[25] phase, mitosis in the hair matrix ceases and sheath cells below the bulge die. The follicle shrinks and the dermal papilla draws up toward the bulge. The base of the hair keratinizes into a hard club and the hair, now known as a **club hair,** loses its anchorage. Club hairs are easily pulled out by brushing the hair, and the hard club can be felt at the hair's end. When the papilla reaches the bulge, the hair goes into a resting period called the **telogen**[26] **phase.** Eventually, anagen begins anew and the cycle repeats itself. A club hair may fall out during catagen, telogen, or as it is pushed out by the new hair in the next anagen phase. We lose about 50 to 100 scalp hairs daily.

In a young adult, scalp follicles typically spend 6 to 8 years in anagen, 2 to 3 weeks in catagen, and 1 to 3 months in telogen. Scalp hairs grow at a rate of about 1 mm per 3 days (10–18 cm/yr) in the anagen phase. Hair grows fastest from adolescence until the 40s. After that, an increasing percentage of follicles are in catagen and telogen rather than the growing anagen phase. Follicles also shrink and begin producing wispy vellus hairs instead of thicker terminal hairs.

Thinning of the hair, or baldness, is called **alopecia**[27] (AL-oh-PEE-she-uh). It occurs to some degree in both sexes and may be worsened by disease, poor nutrition, fever, emotional stress, radiation, or chemotherapy. In the great majority of cases, however, it is simply a matter of aging. **Pattern baldness** is the condition in which hair is lost from select regions of the scalp rather than thinning uniformly across the entire scalp. It results from a combination of genetic and hormonal influences.

Contrary to popular misconceptions, hair and nails do not continue to grow after a person dies, cutting hair does not make it grow faster or thicker, and emotional stress cannot turn the hair white overnight.

Nails

Fingernails and toenails are clear, hard derivatives of the stratum corneum. They are composed of very thin, dead, scaly cells, densely packed together and filled with parallel fibers of hard keratin. Most mammals have claws, whereas flat nails are one of the distinguishing characteristics of humans and other primates. Flat nails serve as strong keratinized "tools" that can be used for grooming, picking apart food, and other manipulations. In addition, they allow for more fleshy and sensitive fingertips. Imagine touching a few grains of salt on a table. The nail, by providing a counterforce or resistance from the other side of the finger, enhances one's sensitivity to such tiny objects.

The hard part of the nail is the **nail plate,** which includes the **free edge** overhanging the tip of the finger or toe; the **nail body,** which is the visible attached part of the nail; and the **nail root,**

---

[24] *ana* = up; *gen* = build, produce
[25] *cata* = down
[26] *telo* = end
[27] *alopecia* = fox mange



Figure 5.9 Anatomy of a Fingernail. APR

which extends proximally under the skin (fig. 5.9). The surrounding skin rises a bit above the nail as a **nail fold,** separated from the margin of the nail plate by a **nail groove.** The groove and the space under the free edge accumulate dirt and bacteria and require special attention when scrubbing for duty in an operating room or nursery.

The skin underlying the nail plate is the **nail bed;** its epidermis is called the **hyponychium**[28] (HIPE-o-NICK-ee-um). At the proximal end of the nail, the stratum basale thickens into a growth zone called the **nail matrix.** Mitosis here in the matrix accounts for the growth of the nail—about 1 mm per week in the fingernails and slightly slower in the toenails. The thickness of the matrix obscures the underlying dermal blood vessels and is the reason why an opaque white crescent, the **lunule**[29] (LOON-yule), often appears at the proximal end of a nail. A narrow zone of dead skin, the **cuticle** or **eponychium**[30] (EP-o-NICK-ee-um), commonly overhangs this end of the nail.

The appearance of the fingertips and nails can be valuable in medical diagnosis. The fingertips become swollen or *clubbed* in response to long-term hypoxemia—a deficiency of oxygen in the blood stemming from conditions such as congenital heart defects and emphysema. Dietary deficiencies may be reflected in the appearance of the nails. An iron deficiency, for example, may cause them to become flat or concave (spoonlike) rather than convex. Contrary to popular belief, adding gelatin to the diet has no effect on the growth or hardness of the nails.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

7. What is the difference between vellus and terminal hair?
8. Describe the three regions of a hair from its base to its tip, and the three layers of a hair seen in cross section.
9. State the function of the dermal papilla, hair receptor, and piloerector muscle associated with a hair follicle.
10. State a reasonable theory for the different functions of hair of the eyebrows, eyelashes, scalp, nostrils, and axilla.
11. Describe some similarities between a nail and a hair.

5.3 Cutaneous Glands

Expected Learning Outcomes

When you have completed this section, you should be able to

a. name two types of sweat glands and describe the structure and function of each;
b. describe the location, structure, and function of sebaceous and ceruminous glands; and
c. discuss the distinction between breasts and mammary glands, and explain their respective functions.

The skin has five types of glands: *apocrine sweat glands, merocrine sweat glands, sebaceous glands, ceruminous glands,* and *mammary glands.*

Sweat Glands

Sweat glands, or **sudoriferous**[31] (soo-dor-IF-er-us) **glands,** are of two kinds, apocrine and merocrine. **Apocrine glands** (fig. 5.10a) occur in the groin, anal region, axilla, and areola, and in mature males, in the beard area. They are absent from the axillary region of Koreans and sparse in the Japanese. Their ducts lead into nearby hair follicles rather than directly to the skin surface. Both apocrine and merocrine sweat glands produce their secretion by exocytosis. Apocrine sweat glands do not secrete their product by the apocrine method shown in figure 3.31 (p. 77); they were named *apocrine* through a misunderstanding, and the name has unfortunately stuck. The secretory part of the gland, however, has a much larger lumen than that of a merocrine gland, so these glands continue to be called apocrine glands to distinguish them functionally and histologically from the merocrine type. Apocrine sweat is thicker and more milky than merocrine sweat because it has more fatty acids in it.

---

[28] *hypo* = below; *onych* = nail
[29] *lun* = moon; *ule* = little
[30] *ep* = above; *onych* = nail
[31] *sudor* = sweat; *fer* = carry, bear



© McGraw-Hill Education/Dennis Strete, photographer

(a) Apocrine gland

© McGraw-Hill Education/Dennis Strete, photographer

(b) Merocrine gland

© McGraw-Hill Education/Dennis Strete, photographer

(c) Sebaceous gland

Figure 5.10 **Cutaneous Glands.** (a) Apocrine sweat glands have a large lumen and a duct that conveys their aromatic secretion into a hair follicle. (b) Merocrine sweat glands have a narrower lumen and a duct that opens by way of a pore on the skin surface. (c) Sebaceous glands have cells that break down in entirety to form an oily secretion (sebum) that is released into the hair follicle.

- *Are apocrine sweat glands associated with vellus or terminal hair? Explain.*

Apocrine sweat glands are scent glands that respond especially to stress and sexual stimulation. They are not activated until puberty, and in women, they enlarge and shrink in phase with the menstrual cycle. These facts, as well as experimental evidence, suggest that their function is to secrete *sex pheromones*—chemicals that exert subtle effects on the sexual behavior and physiology of other people. They apparently correspond to the scent glands that develop in other mammals on attainment of sexual maturity. The scent of apocrine sweat is considered attractive or arousing in some cultures. Stale apocrine sweat acquires a rancid odor from the action of bacteria on the lipids in the perspiration. Disagreeable body odor is called *bromhidrosis.*[32] It occasionally indicates a metabolic disorder, but more often reflects inadequate hygiene.

Many mammals have apocrine scent glands associated with specialized tufts of hair. In humans, they occur almost exclusively in regions covered by the pubic hair, axillary hair, and beard, suggesting that they are similar to other mammalian scent glands in function. The hair serves to retain the aromatic secretion and regulate its rate of evaporation from the skin. Thus, it seems no mere coincidence that women's faces lack both apocrine scent glands and a beard.

Merocrine[33] **(eccrine**[34]**) glands** (fig. 5.10b) are widely distributed over the entire body, but are especially abundant on the palms, soles, and forehead. Each is a simple tubular gland with a twisted coil in the dermis or hypodermis and an undulating or coiled duct leading to a sweat pore on the skin surface. This duct is lined by a stratified cuboidal epithelium in the dermis and by keratinocytes in the epidermis. Merocrine perspiration functions to cool the body. It contains sodium chloride, ammonia, urea, and uric acid—wastes that are present also in the urine. There are 3 to 4 million merocrine sweat glands in the skin, with a total mass about equal to that of one kidney.

Amid the secretory cells of merocrine and apocrine glands, there are specialized **myoepithelial**[35] **cells** with properties similar to those of smooth muscle. They contract in response to the sympathetic nervous system and squeeze perspiration up the duct.

---

[32] *brom* = stench; *hidros* = sweat

[33] *mero* = part; *crin* = to separate, secrete

[34] *ec* = out; *crin* = to separate, secrete

[35] *myo* = muscle

Sebaceous Glands

Sebaceous[36] (seh-BAY-shus) **glands** (fig. 5.10c) produce an oily secretion called **sebum** (SEE-bum). They occur everywhere except in thick skin, but are most abundant on the scalp and face. They are flask-shaped and usually clustered around a hair follicle, with short ducts that open into the follicle. Some, however, open directly onto the skin surface. They are holocrine glands with little visible lumen. Their secretion consists of broken-down cells that are replaced by mitosis around the perimeter of the gland. Sebum keeps the skin and hair from becoming dry, brittle, and cracked. The sheen of well-brushed hair is due to sebum distributed by the hairbrush.

Ceruminous Glands

Ceruminous (seh-ROO-mih-nus) **glands** are found only in the auditory (external ear) canal, where their secretion combines with sebum and dead epidermal cells to form earwax, or **cerumen.**[37] They are simple, coiled, tubular glands with ducts leading to the skin surface. Cerumen keeps the eardrum pliable, waterproofs the canal, kills bacteria, and coats the guard hairs of the ear, making them sticky and more effective in blocking foreign particles from entering the canal.

Mammary Glands

Mammary glands are milk-producing glands that develop within the breasts *(mammae)* under conditions of pregnancy and lactation. They are not synonymous with the breasts, which are present in both sexes and which, even in females, usually contain only small traces of mammary gland. Mammary glands are modified apocrine sweat glands that produce a richer secretion than other apocrine glands and channel it through ducts to a nipple for more efficient conveyance to the offspring. The mammary glands are discussed in more detail in chapter 26. Table 5.3 summarizes the cutaneous glands.

TABLE 5.3 Cutaneous Glands

Gland Type	Definition
Sudoriferous glands	Sweat glands
Apocrine	Sweat glands that function as scent glands; found in the regions covered by the pubic, axillary, and male facial hair; open by ducts into hair follicles
Merocrine	Sweat glands that function in evaporative cooling; widely distributed over the body surface; open by ducts onto the skin surface
Sebaceous glands	Oil-producing glands associated with hair follicles
Ceruminous glands	Glands of the ear canal that produce cerumen (earwax)
Mammary glands	Milk-producing glands located in the breasts

DEEPER INSIGHT 5.3

Extra Nipples—An Evolutionary Throwback

Humans normally have only one pair of nipples. This is a trait that we share with other primates, related to the fact that most primates have only one infant at a time rather than having to nurse a whole litter. Some women and men, however, develop one or more additional nipples, either on the same breast or slightly superior or inferior to it. This condition is called *polythelia.*[38] The extra nipple often is so little developed that it is mistaken for a mole. In a few cases, fully formed additional breasts develop inferior to the primary ones—a condition called *polymastia*.[39] In medieval Europe and colonial America, polythelia was sometimes used to incriminate women as supposed witches and used as a pretext to put innocent women to death.

Why would such a thing as polythelia occur? It is an example of what evolutionary biologists call an *atavism,* a "throwback" to an ancestral condition. Most mammals develop two rows of mammary glands along lines called the *milk lines* or *mammary ridges,* which extend from the axillary to the inguinal region. This enables a female to nurse a litter of young. Primates have dispensed with all but the most anterior pair, but still possess the genes for development of more. These genes are normally inactive in humans, but when activated, additional nipples or breasts appear along the milk line. Polythelia is a further testimony to our ancestry and kinship with other mammals.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

12. How do merocrine and apocrine sweat glands differ in structure and function?
13. What types of hair are associated with apocrine glands? Why?
14. What other type of gland is associated with hair follicles? How does its mode of secretion differ from that of sweat glands?
15. What is the difference between a breast and mammary gland? What other type of cutaneous gland is most closely related to mammary glands?

---

[36] *seb* = fat, tallow; *aceous* = possessing
[37] *cer* = wax
[38] *poly* = many, multiple; *thel* = nipples; *ia* = condition
[39] *poly* = many, multiple; *mast* = breasts; *ia* = condition

5.4 Developmental and Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the prenatal development of the skin, hair, and nails;
b. describe the three most common forms of skin cancer; and
c. discuss the three classes of burns and the priorities in burn treatment.

Prenatal Development of the Integumentary System

Skin

The epidermis develops from the embryonic ectoderm, and the dermis from the mesoderm. In week 4 of embryonic development, ectodermal cells multiply and organize into two layers—a superficial *periderm* of squamous cells and a deeper *basal layer* (fig. 5.11). In week 11, the basal layer gives rise to a new *intermediate layer* of cells between these two. From then until birth, the basal layer is known as the *germinative layer.* Its cells remain for life as the stem cells of the stratum basale. Cells of the intermediate layer synthesize keratin and become the first keratinocytes. These cells organize into three layers—the stratum spinosum, granulosum, and corneum—as the periderm is sloughed off into the amniotic fluid. By week 21, the periderm is gone and the stratum corneum is the outermost layer of the fetal integument.

Beneath the developing epidermis, the mesoderm differentiates into a gelatinous connective tissue called mesenchyme. Mesenchymal cells begin producing collagenous and elastic fibers by week 11, and the mesenchyme takes on the characteristics of typical fibrous connective tissue. Dermal papillae appear along the dermal–epidermal boundary in the third month. Blood vessels appear in the dermis late in week 6. At birth, the skin has 20 times as many blood vessels as it needs to support its metabolism. The excess may help to regulate the body temperature of the newborn.

Hair and Nails

The first hair follicles appear around the end of the second month on the eyebrows, eyelids, upper lip, and chin; follicles do not appear elsewhere until the fourth month. At birth, there are about 5 million hair follicles in both sexes; no additional follicles form after birth.

A hair follicle begins as a cluster of ectodermal cells called a *hair bud,* which pushes down into the dermis and elongates into a rodlike *hair peg* (fig. 5.12). The lower end of the peg expands into a *hair bulb.* The dermal papilla first appears as a small mound of tissue just below the bulb, then expands into the bulb itself. Ectodermal cells overlying the papilla form the *germinal matrix,* a mass of mitotically active cells that produce the hair root. The first hair to develop in the fetus is lanugo, which appears in week 12 and is abundant by week 20. By the time of birth, most lanugo is replaced by vellus.

The first indications of nail development are epidermal thickenings that appear on the ventral surfaces of the fingers around 10 weeks and on the toes around 14 weeks. They soon migrate to the dorsal surfaces of the digits, where they form a shallow depression



Figure 5.11 Prenatal Development of the Epidermis and Dermis.

called the *primary nail field.* The margins of the nail field are the nail folds. In the proximal nail fold of each digit, the germinal layer of epidermis develops into the nail root. Mitosis in the root produces the keratinocytes that become compressed into the hard nail plate. The nail plate reaches the fingertips by 8 months and the toe tips by birth.

Glands

Sebaceous glands begin to bud from the sides of a hair follicle about 4 weeks after the hair bulb begins to elongate (fig. 5.12). Mature sebaceous glands are present on the face by 6 months and secrete very actively before birth. Their sebum mixes with epidermal and peridermal cells to form a white, greasy skin coating called the *vernix caseosa.*[40] The vernix protects the skin from abrasions and from the amniotic fluid, which can otherwise cause the fetal skin to chap and harden. Its slipperiness also aids in the birth passage through the vagina. The vernix is anchored to the skin by the lanugo and later by the vellus. Sebaceous glands become largely dormant by the time of birth, and are reactivated at puberty under the influence of the sex hormones.

Apocrine sweat glands also develop as outgrowths from the hair follicles. They appear over most of the body at first, but then degenerate except in the limited areas described earlier—especially in the axillary and genital regions. Like the sebaceous glands, they become active at puberty.

Merocrine sweat glands develop as buds of the embryonic germinative layer that grow and push their way down into the dermis (fig. 5.12). These buds develop at first into solid cords of epithelial tissue, but cells in the center of the cord later degenerate to form the lumen of the sweat duct, while cells at the lower end differentiate into secretory and myoepithelial cells.


Week 4
Week 5
Week 12
Week 14
Week 16
Week 20
Weeks 23–28
Epidermis
Hair bud
Hair peg
Hair shaft
Hair bulb
Dermal papilla
Bud of sweat gland
Primordium of sebaceous gland
Developing sweat gland
Epithelial root sheath
Dermal root sheath
Hair bulb
Sebaceous gland
Sweat duct
Secretory cell of merocrine sweat gland
Piloerector muscle
Blood vessels

Figure 5.12 Prenatal Development of a Hair Follicle and Cutaneous Glands.

---

[40] *vernix* = varnish; *case* = cheese; *osa* = having the qualities of

The Aging Integumentary System

Senescence (age-related degeneration) of the integumentary system often becomes noticeable by the late 40s. The hair turns grayer and thinner as melanocyte stem cells die out, mitosis slows down, and dead hairs are not replaced. Atrophy of the sebaceous glands leaves the skin and hair drier. As epidermal mitosis declines and collagen is lost from the dermis, the skin becomes almost paper-thin and translucent. It becomes looser because of a loss of elastic fibers and flattening of the dermal papillae. If you pinch a fold of skin on the back of a child's hand, it quickly springs back when you let go; do the same on an elderly person, and the skin fold remains longer. Because of its loss of elasticity, aged skin sags to various degrees and may hang loosely from the arms and other places.

Cutaneous blood vessels become fewer and more fragile in old age. The skin may redden as broken vessels leak into the connective tissue, and aged skin bruises more easily. Many older people exhibit *rosacea*—patchy networks of tiny, dilated blood vessels visible especially on the nose and cheeks. Injured skin heals slowly in old age because of diminished circulation and a relative scarcity of immune cells and fibroblasts. Dendritic cells decline by as much as 40% in the aged epidermis, leaving the skin more susceptible to recurring infections.

Thermoregulation can be a problem in old age because of the atrophy of cutaneous blood vessels, sweat glands, and subcutaneous fat. Older people are more vulnerable to hypothermia in cold weather and heatstroke in hot weather. Heat waves and cold spells take an especially heavy toll among elderly poor people who suffer from a combination of reduced homeostasis and inadequate housing.

Degeneration of the skin is accelerated by excessive exposure to the ultraviolet radiation of sunlight. This *photoaging* accounts for more than 90% of the changes that people find medically troubling or cosmetically disagreeable: skin cancer; yellowing and mottling of the skin; age spots, which resemble enlarged freckles on the back of the hand and other sun-exposed areas; and wrinkling, which especially affects the most exposed areas of skin (face, hands, and arms). Sun-damaged skin shows many malignant and premalignant cells, extensive damage to the dermal blood vessels, and dense masses of coarse, frayed elastic fibers underlying the surface wrinkles and creases.

Skin Disorders

Because it is the most exposed of all our organs, skin is not only the most vulnerable to injury and disease, but is also the one place where we are most likely to notice anything out of the ordinary. We focus here on two particularly common and serious disorders, skin cancer and burns. Other skin diseases are briefly summarized in table 5.4.

Skin Cancer

Skin cancer is induced by the ultraviolet rays of the sun. It occurs most often on the head and neck, where exposure is greatest. It is

TABLE 5.4	**Some Disorders of the Integumentary System**
Acne	Inflammation of the sebaceous glands, especially beginning at puberty; follicle becomes blocked with keratinocytes and sebum and develops into a blackhead *(comedo)* composed of these and bacteria; continued inflammation of follicle results in pus production and pimples
Dermatitis	Any inflammation of the skin, typically marked by itching and redness; often *contact dermatitis,* caused by exposure to toxins such as poison ivy
Eczema (ECK-zeh-mah)	Itchy, red, "weeping" skin lesions caused by an allergy, usually beginning before age 5; may progress to thickened, leathery, darkly pigmented patches of skin
Psoriasis (so-RY-ah-sis)	Recurring, reddened plaques covered with silvery scale; sometimes disfiguring; possibly caused by an autoimmune response; runs in families
Ringworm	A fungal infection of the skin (not a worm) that sometimes grows in a circular pattern; common in moist areas such as the axilla, groin, and foot *(athlete's foot)*
Rosacea (ro-ZAY-she-ah)	A red rashlike area, often in the area of the nose and cheeks, marked by fine networks of dilated blood vessels; worsened by hot drinks, alcohol, and spicy food
Warts	Benign, elevated, rough lesions caused by human papillomaviruses (HPV). *Common warts* appear most frequently in late childhood on the fingers, elbows, and other areas of skin subject to stress. *Plantar warts* occur on the soles and *venereal warts* on the genitals. Warts can be treated by freezing with liquid nitrogen, electric cauterization (burning), laser vaporization, surgical excision, and some medicines such as salicylic acid.
Disorders Described Elsewhere	
Abnormal skin coloration 115 Birthmarks 116 Burns 126	Pemphigus vulgaris 39 Polythelia and polymastia 122 Skin cancer 125

most common in fair-skinned people and the elderly, who have had the longest lifetime UV exposure and have less melanin to shield the keratinocyte DNA from radiation. The popularity of sun tanning, however, has caused an alarming increase in skin cancer among younger people. While sunscreens protect against sunburn, there is no evidence that they afford protection from skin cancer. Skin cancer is one of the most common cancers, but it is also one of the easiest to treat and has one of the highest survival rates when it is detected and treated early.

There are three types of skin cancer named for the epidermal cells in which they originate: basal cell carcinoma, squamous cell carcinoma, and melanoma. The three types are also distinguished from each other by the appearance of their **lesions**[41] (zones of tissue injury).

Basal cell carcinoma[42] is the most common type. It is the least deadly because it seldom metastasizes, but if neglected, it can cause severe facial disfigurement. It arises from cells of the stratum basale and eventually invades the dermis. On the surface, the lesion first appears as a small, shiny bump. As the bump enlarges, it often develops a central depression and a beaded "pearly" edge (fig. 5.13a).

Squamous cell carcinoma arises from keratinocytes of the stratum spinosum. The lesion has a raised, reddened, scaly appearance and later forms a concave ulcer with raised edges (fig. 5.13b). The chance of recovery is good with early detection and surgical removal, but if it goes unnoticed or is neglected, this cancer tends to metastasize to the lymph nodes and can be lethal.

Melanoma is a skin cancer that arises from the melanocytes, often in a preexisting mole. It accounts for no more than 5% of skin cancers, but it is the most deadly form. It can be treated surgically if it is caught early, but if it metastasizes—which it does quickly—it is unresponsive to chemotherapy and usually fatal. The average person with metastatic melanoma lives only 6 months from diagnosis, and only 5% to 14% of patients survive with it for 5 years. The greatest risk factor for melanoma next to UV exposure is a family history of the disease. It has a relatively high incidence in men, in redheads, and in people who experienced severe sunburns in childhood.

It is important to distinguish a mole from melanoma. A mole usually has a uniform color and even contour, and it is no larger in diameter than the end of a pencil eraser (about 6 mm). If it becomes malignant, however, it forms a large, flat, spreading lesion with a scalloped border (fig. 5.13c). The American Cancer Society suggests an "ABCD rule" for recognizing melanoma: *A* for asymmetry (one side of the lesion looks different from the other); *B* for border irregularity (the contour is not uniform but wavy or scalloped); *C* for color (often a mixture of brown, black, tan, and sometimes red and blue); and *D* for diameter (greater than 6 mm).

Skin cancer is treated by surgical excision, radiation therapy, or destruction of the lesion by heat (electrodesiccation) or cold (cryosurgery).


© NAS Medical/Alamy

(a) Basal cell carcinoma


© Biophoto Associates/Science Source

(b) Squamous cell carcinoma


© James Stevenson/SPL/Science Source

(c) Melanoma

Figure 5.13 Typical Lesions of the Three Forms of Skin Cancer.
• *Which of the ABCD rules can you identify in part (c)?*

Burns

Burns are the leading cause of accidental death. They are usually caused by UV radiation, fires, kitchen spills, or excessively hot bath water, but they also can be caused by other forms of radiation, strong acids and bases, or electrical shock. Burn deaths result primarily from fluid loss, infection, and the toxic effects of **eschar**[43] (ESS-car)—the burned, dead tissue.

---

[41] *lesio* = injure
[42] *carcin* = cancer; *oma* = tumor

Burns are classified according to the depth of tissue involvement (fig. 5.14). **First-degree burns** involve only the epidermis and are marked by redness, slight edema, and pain. They heal in a few days and seldom leave scars. Most sunburns are first-degree burns.

Second-degree burns involve the epidermis and part of the dermis but leave at least some of the dermis intact. First- and second-degree burns are therefore also known as **partial-thickness burns.** A second-degree burn may be red, tan, or white and is blistered and very painful. It may take from 2 weeks to several months to heal and may leave scars. The epidermis regenerates by division of epithelial cells in the hair follicles and sweat glands and those around the edges of the lesion. Severe sunburns and many scalds are second-degree burns.

Third-degree burns are also called **full-thickness burns** because the epidermis and dermis are completely destroyed. Sometimes even deeper tissue is damaged (hypodermis, muscle, and bone). (Some authorities call burns that extend to the bone *fourth-degree burns*.) Since no dermis remains, the skin can regenerate only from the edges of the wound. Third-degree burns often require skin grafts (see Deeper Insight 5.4). If a third-degree burn is left to itself to heal, contracture (abnormal connective tissue fibrosis) and severe disfigurement may result.

Apply What You Know

A third-degree burn may be surrounded by painful areas of first- and second-degree burns, but the region of the third-degree burn is painless. Explain the reason for this lack of pain.

---

[43] *eschar* = scab



© Sonda Dawes/The Image Works

© John Radcliffe/Science Source

© John Radcliffe/Science Source

(a) First degree **(b) Second degree** **(c) Third degree**

Figure 5.14 Three Degrees of Burns. (a) First-degree burn, involving only the epidermis. (b) Second-degree burn, involving the epidermis and part of the dermis. (c) Third-degree burn, extending through the entire dermis and often involving even deeper tissue.

DEEPER INSIGHT 5.4

Skin Grafts and Artificial Skin

Third-degree burns leave no dermis to regenerate what was lost and, therefore, require skin grafts. Ideally, these should come from elsewhere on the same patient's body *(autografts*[44]*)* so there is no problem with immune rejection, but this may not be feasible in patients with extensive burns. A skin graft from another person (called an *allograft*[45] or *homograft*[46]) or even skin from another species (called a *heterograft*[47] or *xenograft*[48]), such as pig skin, may be used, but they present problems with immune rejection.

At least two bioengineering companies produce artificial skin as a temporary burn covering. One such product is made by culturing fibroblasts on a collagen gel to produce a dermis, then culturing keratinocytes on this substrate to produce an epidermis. This is used to treat not only burn patients but also patients with leg and foot ulcers caused by diabetes mellitus. Another new technology available in some countries is a spray-on skin graft. A bit of epidermis the size of a postage stamp is taken from a burn patient and enzymatically broken up into separate cells. The cell suspension is then sprayed onto areas of second-degree burns or other skin lesions. Within a week, this can grow into an area of healthy skin the size of a book page.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

16. What adult skin layer arises from the germinative layer of the fetus?
17. What is the vernix caseosa of the fetus? What purpose does it serve?
18. What types of cells are involved in each type of skin cancer?
19. Which type of skin cancer is most dangerous? What are its early warning signs?
20. What is the difference between a first-, second-, and third-degree burn?
21. What are the two most urgent priorities in treating a burn victim? How are these needs dealt with?

---

[44] *auto* = self
[45] *allo* = different, other
[46] *homo* = same
[47] *hetero* = different
[48] *xeno* = strange, alien

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

5.1 The Skin and Subcutaneous Tissue (p. 109)

1. The difference between the integumentary system and integument, and the branch of medicine that deals with this system
2. The two principal layers of the skin and alternative terms for the connective tissue beneath the skin
3. The range of thicknesses of the skin, the basis for distinguishing thick skin from thin skin, and where those two types of skin are located
4. The multiple functions of the skin and what aspects of skin structure contribute to these functions
5. The five epidermal cell types and their respective functions
6. The four to five strata seen in thin and thick skin, their order of occurrence, and the distinguishing histological features of each stratum
7. The histological distinctions between thin and thick skin
8. The life history of a keratinocyte from the time of its mitotic birth to the time it dies and flakes off the skin surface, and how the stages of its development correlate with the histological appearance of the epidermal strata
9. The significance of the epidermal water barrier, what it is composed of, and how keratinocytes produce it
10. The composition of the dermis, including its fiber and cell types and the diverse small organs that it contains
11. The structure of the dermal–epidermal boundary, the names of its interlocking troughs and ridges, and how and why the appearance of this boundary differs from one region of the body to another
12. The difference between the papillary and reticular layers of the dermis—where they are seen, their tissue composition, and their functional difference
13. The histological composition of the hypodermis and how it differs from the dermis
14. The pigments responsible for normal skin colors, the two types of melanin, and reasons for the differences between light and dark skin
15. A variety of pathological skin colors and what causes such variations
16. The various kinds of lines, creases, and other markings of the skin

5.2 Hair and Nails (p. 116)

1. The protein composition of hair and nails and how this compares to the dominant epidermal protein

2. The distinction between a hair and its follicle, and their general structural relationship
3. The three types of human hair and their differences in appearance, bodily location, and occurrence over the human life span
4. The functions of human hair of various types and bodily locations
5. The three regions of a hair from its base to the portion above the skin; where it gets its nourishment; and which region serves as the hair's growth zone
6. The three zones of a hair seen in cross section, from its core to its surface, including the differences between these zones in cell morphology
7. The layers of a hair follicle and the functional significance of its bulge
8. Nerves and muscles associated with a hair, and their functions
9. Factors that account for differences in hair color and texture (straight, wavy, or curly)
10. Stages in the life cycle of a hair, the principal processes that occur in each stage, and approximately how long each stage lasts
11. Types of hair thinning and factors that contribute to it
12. The morphology of the nails, and how variations in appearance can be of diagnostic value in certain diseases and disorders

5.3 Cutaneous Glands (p. 120)

1. The two types of sweat glands and how they differ in histological appearance, bodily distribution, function, and development over the human life span
2. The function and locations of sebaceous glands, and how they differ from sweat glands in their method of secretion
3. The location of the ceruminous glands, how cerumen differs from the product secreted by these glands, and what functions are served by cerumen
4. Why the terms *mammary gland* and *breast* are not synonymous, and how mammary glands compare and contrast with apocrine sweat glands

5.4 Developmental and Clinical Perspectives (p. 123)

1. Stages in the embryonic development of the epidermis from the ectoderm, and how the dermis differs from the epidermis in its origin and mode of development
2. How the hair and nails develop from the embryonic epidermis
3. Where and how sebaceous glands arise in the embryo; the nature of the vernix caseosa; and how the vernix caseosa, along with the fetal lanugo and vellus, protect the fetus
4. How the two types of sweat glands differ in their prenatal development and how they differ in childhood versus in and beyond puberty
5. Ways in which the adult skin changes with age, especially in the elderly, and how this is influenced by one's lifetime history of UV exposure
6. The three types of skin cancer and how they differ in the cells of origin, relative frequency in the population, and relative risk of metastasis and mortality
7. Distinguishing characteristics of the three degrees of burns

Testing Your Recall

1. Cells of the _____ are keratinized and dead.
   a. papillary layer
   b. stratum spinosum
   c. stratum basale
   d. stratum corneum
   e. stratum granulosum
2. The epidermal water barrier forms at the point where epidermal cells
   a. enter the telogen stage.
   b. pass from stratum basale to stratum spinosum.
   c. pass from stratum spinosum to stratum granulosum.
   d. form the epidermal ridges.
   e. exfoliate.
3. Which of the following skin conditions or appearances would most likely result from liver failure?
   a. pallor
   b. erythema
   c. pemphigus vulgaris
   d. jaundice
   e. melanization
4. All of the following interfere with microbial invasion of the skin *except*
   a. the acid mantle.
   b. melanin.
   c. cerumen.
   d. keratin.
   e. sebum.
5. The hair on a 6-year-old's arms is
   a. vellus.
   b. lanugo.
   c. pilorum.
   d. terminal hair.
   e. rosacea.
6. Which of the following terms is *least* related to the rest?
   a. lunule
   b. nail plate
   c. hyponychium
   d. free edge
   e. cortex
7. Which of the following is a scent gland?
   a. an eccrine gland
   b. a sebaceous gland
   c. an apocrine gland
   d. a ceruminous gland
   e. a merocrine gland
8. _____ are skin cells with a sensory role.
   a. Tactile cells
   b. Dendritic cells
   c. Langerhans cells
   d. Melanocytes
   e. Keratinocytes
9. The embryonic periderm becomes part of
   a. the vernix caseosa.
   b. the lanugo.
   c. the stratum corneum.
   d. the stratum basale.
   e. the dermis.
10. Which of the following skin cells alert the immune system to pathogens?
    a. fibroblasts
    b. melanocytes
    c. keratinocytes
    d. dendritic cells
    e. tactile cells
11. Two common word roots that refer to the skin in medical terminology are _____ and _____.
12. A muscle that causes a hair to stand on end is called a/an _____.
13. The most abundant protein of the epidermis is _____, while the most abundant protein of the dermis is _____.
14. Blueness of the skin due to low oxygen concentration in the blood is called _____.
15. Projections of the dermis toward the epidermis are called _____.

16. Cerumen is more commonly known as _____.
17. The holocrine glands that secrete into a hair follicle are called _____.
18. The scaly outermost layer of a hair is called the _____.
19. A hair is nourished by blood vessels in a connective tissue projection called the _____.
20. A _____ burn destroys part of the dermis, but not all of it.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. dermato-
2. epi-
3. sub-
4. pap-
5. melano-
6. cyano-
7. lucid-
8. -illa
9. pilo-
10. carcino-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. Dander consists of dead keratinocytes.
2. The term *integument* means only the skin, but *integumentary system* refers also to the hair, nails, and cutaneous glands.
3. The dermis is composed mainly of keratin.
4. Vitamin D is synthesized by certain cutaneous glands.
5. Cells of the stratum granulosum cannot undergo mitosis.
6. Dermal papillae are better developed in skin that is subject to a lot of mechanical stress than in skin that is subject to less stress.
7. The three layers of the skin are the epidermis, dermis, and hypodermis.
8. People of African descent have a much higher density of epidermal melanocytes than do people of northern European descent.
9. Melanoma is the most common and deadly form of skin cancer.
10. Apocrine scent glands are activated at the same time in life as the pubic and axillary hair begins to grow.

Answers in appendix A

Testing Your Comprehension

1. Many organs of the body contain numerous smaller organs, perhaps even thousands. Describe an example of this in the integumentary system.
2. Certain aspects of human form and function are easier to understand when viewed from the perspective of comparative anatomy and evolution. Discuss examples of this in the integumentary system.
3. Explain how the complementarity of form and function is reflected in the fact that the dermis has two histological layers and not just one.
4. Cold weather does not normally interfere with oxygen uptake by the blood, but it can cause cyanosis anyway. Why?
5. Why is it important for the epidermis to be effective, but not *too* effective, in screening out UV radiation?



Spongy bone, scanning electron micrograph

© Science Photo Library/Getty Images RF

CHAPTER 6

THE SKELETAL SYSTEM I
BONE TISSUE

CHAPTER OUTLINE

6.1 Tissues and Organs of the Skeletal System 132
- Functions of the Skeleton 132
- Bones and Osseous Tissue 132
- General Features of Bones 133

6.2 Histology of Osseous Tissue 134
- Bone Cells 134
- Matrix 135
- Compact Bone 136
- Spongy Bone 136
- Bone Marrow 138

6.3 Bone Development 139
- Intramembranous Ossification 139
- Endochondral Ossification 139
- Bone Growth 140
- Bone Remodeling 143
- Nutritional and Hormonal Factors 144
- The Aging Skeletal System 144

6.4 Structural Disorders of Bone 145
- Fractures 145
- Osteoporosis 147
- Other Structural Disorders 148

Study Guide 148

DEEPER INSIGHTS

6.1 Radioactivity and Bone Cancer 132
6.2 Polymers, Ceramics, and Bones 136
6.3 Achondroplastic Dwarfism 143
6.4 When *Not* to Eat Your Spinach 145

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:
- Stem cells (p. 50)
- General properties of connective tissues (p. 63)
- Hyaline cartilage (p. 69)
- Introduction to bone histology (p. 70)
- Mesenchyme (p. 89)

Anatomy & Physiology REVEALED
aprevealed.com

Module 5: Skeletal System

In art and history, nothing has symbolized death so much as a skull or skeleton.[1] Bones and teeth are the most durable remains of a once-living body and the most vivid reminder of the impermanence of life.

The dry bones presented for laboratory study may wrongly suggest that the skeleton is a nonliving scaffold for the body, like the steel girders of a building. Seeing it in such a sanitized form makes it easy to forget that the living skeleton is made of dynamic tissues, full of cells—that it continually remodels itself and interacts physiologically with all of the other organ systems. The skeleton is permeated with nerves and blood vessels, evidence of its sensitivity and metabolic activity.

Bone is the subject of chapters 6 through 8. In this chapter, we study bone as a tissue—its composition, development, and growth. This will provide a basis for understanding the skeleton, joints, and muscles in the chapters that follow.

6.1 Tissues and Organs of the Skeletal System

Expected Learning Outcomes

When you have completed this section, you should be able to

a. name the tissues and organs that compose the skeletal system;
b. state several functions of the skeletal system;
c. distinguish between bone as a tissue and as an organ; and
d. describe the general features of a long bone.

The **skeletal system** consists of bones, cartilages, and ligaments tightly joined to form a strong, flexible framework for the body. Cartilage, the embryonic forerunner of most bones, covers many joint surfaces in the mature skeleton. Ligaments hold bones together at the joints and are discussed in chapter 9. Tendons are structurally similar to ligaments but attach muscles to bones; they are discussed with the muscular system in chapters 11 and 12.

Functions of the Skeleton

The skeleton obviously provides the body with physical support, but it plays many other roles that go unnoticed by most people. Its functions include the following.

- **Support.** Bones of the legs, pelvis, and vertebral column hold up the body; the jaw bones support the teeth; and nearly all bones provide support for muscles.
- **Movement.** Skeletal muscles would serve little purpose if not for their attachment to the bones and ability to move them.
- **Protection.** Bones enclose and protect such delicate organs and tissues as the brain, spinal cord, lungs, heart, pelvic viscera, and bone marrow.
- **Blood formation.** Red bone marrow is the major producer of blood cells, including most cells of the immune system.
- **Electrolyte balance.** The skeleton is the body's main reservoir of calcium and phosphate. It stores these minerals and releases them when needed for other purposes.
- **Acid–base balance.** Bone buffers the blood against excessive pH changes by absorbing or releasing alkaline salts such as calcium phosphate.
- **Detoxification.** Bone tissue absorbs heavy metals and other foreign elements from the blood and thus mitigates their toxic effects on other tissues. It can later release these contaminants more slowly for excretion. The tendency of bone to absorb foreign elements can, however, have terrible consequences (see Deeper Insight 6.1).

DEEPER INSIGHT 6.1

Radioactivity and Bone Cancer

Radioactivity captured the public imagination when Marie and Pierre Curie and Henri Becquerel shared the 1903 Nobel Prize for its discovery. Not for several decades, however, did anyone realize its dangers. Factories employed women to paint luminous numbers on watch and clock dials with radium paint. As they moistened the paint brushes with their tongues to keep them finely pointed, the women ingested radium. Their bones readily absorbed it and many of the women developed *osteosarcoma,* the most common and deadly form of bone cancer.

Even more horrific, in the wisdom of hindsight, was a deadly health fad in which people drank "tonics" made of radium-enriched water. One famous enthusiast was the champion golfer and millionaire playboy Eben Byers (1880–1932), who drank several bottles of radium tonic each day and praised its virtues as a wonder drug and aphrodisiac. Like the factory women, Byers contracted osteosarcoma. By the time of his death, holes had formed in his skull and doctors had removed his entire upper jaw and most of his mandible in an effort to halt the spreading cancer. Byers's bones and teeth were so radioactive they could expose photographic film in complete darkness. Brain damage left him unable to speak, but he remained mentally alert to the bitter end. His tragic decline and death shocked the world and put an end to the radium tonic fad.

Bones and Osseous Tissue

The study of **bone,** or **osseous**[2] **tissue,** is called **osteology.**[3] Bone is a connective tissue in which the matrix is hardened by the deposition of calcium phosphate and other minerals. The hardening process is called **mineralization** or **calcification.** Osseous tissue, however, is only one of the components of a bone. Also present are blood, bone marrow, cartilage, adipose tissue, nervous tissue, and fibrous connective tissue. The word *bone* can denote an organ composed of all these components, or it can denote just the osseous tissue.

---

[1] *skelet* = dried up

[2] *os, osse, oste* = bone

[3] *osteo* = bone; *logy* = study of

General Features of Bones

Bones have a wide variety of shapes correlated with their varied protective and locomotor functions. Most of the cranial bones are in the form of thin curved plates called **flat bones,** such as the paired parietal bones that form the dome of the top of the head. The sternum (breastbone), scapula (shoulder blade), ribs, and hip bones are also flat bones. The most important bones in body movement are the **long bones** of the limbs—the humerus, radius, and ulna of the arm and forearm; the femur, tibia, and fibula of the thigh and leg; and the metacarpals, metatarsals, and phalanges of the hands and feet. Like crowbars, long bones serve as rigid levers that are acted upon by skeletal muscles to produce the major body movements. The wrists and ankles have a total of 30 **short bones** (carpal and tarsal bones), which are approximately equal in length and width and which produce relatively limited gliding movements. The patella is also a short bone. Many bones, however, do not fit any of these categories; these are collectively considered **irregular bones**—the vertebrae and the sphenoid and ethmoid bones of the skull, for example.

Figure 6.1 shows longitudinal sections of a long bone. Much of it is composed of an outer shell of dense white osseous tissue called **compact (dense) bone**. The shell encloses a space called the **marrow cavity** or **medullary**[4] (MED-you-lerr-ee) **cavity,** which contains bone marrow. At the ends of the bone is a more loosely organized form of osseous tissue called **spongy (cancellous) bone** (see fig. 6.4). The skeleton is about three-quarters compact bone and one-quarter spongy bone by weight. Compact and spongy bone are described later in more detail.

The principal features of a long bone are its shaft, called the **diaphysis**[5] (dy-AF-ih-sis), and an expanded head at each end, called the **epiphysis**[6] (eh-PIF-ih-sis). The diaphysis of a long bone provides leverage, whereas the epiphysis is enlarged to strengthen the joint and provide added surface area for the attachment of tendons and ligaments. In children and adolescents, an **epiphyseal** (EP-ih-FIZZ-ee-ul) **plate** of hyaline cartilage separates the marrow cavities of the epiphysis and diaphysis. On X-rays, it appears as a transparent line at the end of a long bone (see fig. 6.10). The epiphyseal plate is a zone where the bones grow in length. It is not present in adults (see p. 143).

Externally, most of the bone is covered with a sheath called the **periosteum.**[7] This has a tough, outer *fibrous layer* of collagen and an inner *osteogenic layer* of bone-forming cells. Some collagen fibers of the outer layer are continuous with the tendons that bind muscle to bone, and some penetrate into the bone matrix as **perforating fibers.** The periosteum thus provides strong attachment and continuity from muscle to tendon to bone. The osteogenic layer is important to the growth of bone and healing of fractures. Blood vessels of the periosteum penetrate into the bone through minute holes called **nutrient foramina** (for-AM-ih-nuh); we will trace where they go when we consider bone histology. The internal surface of a bone is lined with **endosteum,**[8] a thin layer of reticular connective tissue with cells that deposit osseous tissue and others that dissolve it.



(a) Living **(b) Dried**

Figure 6.1 Anatomy of a Long Bone. (a) The femur, with its soft tissues including bone marrow, articular cartilage, blood vessels, and periosteum. (b) A dried femur in longitudinal section.

• *What is the functional significance of a long bone being wider at the epiphyses than at the diaphysis?*

---

[4] *medulla* = marrow; *ary* = pertaining to

[5] *dia* = across; *physis* = growth; originally named for a ridge on the shaft of the tibia

[6] *epi* = upon, above; *physis* = growth

[7] *peri* = around; *oste* = bone

[8] *endo* = within; *oste* = bone



Figure 6.2 Anatomy of a Flat Bone.

At most joints, the ends of the adjoining bones have no periosteum but rather a thin layer of hyaline cartilage, the **articular**[9] **cartilage.** Together with a lubricating fluid secreted between the bones, this cartilage enables a joint to move far more easily than it would if one bone rubbed directly against the other.

Flat bones have a sandwichlike construction, with two layers of compact bone enclosing a middle layer of spongy bone (fig. 6.2). In the skull, the spongy layer is called the **diploe**[10] (DIP-lo-ee). A moderate blow to the skull can fracture the outer layer of compact bone, but the diploe sometimes absorbs the impact and leaves the inner layer of compact bone unharmed.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. Name five tissues found in a bone.
2. List three or more functions of the skeletal system other than supporting the body and protecting some of the internal organs.
3. Explain why X-rays of a child's limbs exhibit a clear line between the epiphysis and diaphysis of a long bone.
4. Explain the difference between compact and spongy bone, and describe their spatial relationship to each other in a long bone and a flat bone.
5. State the anatomical terms for the shaft, head, growth zone, and fibrous covering of a long bone.

6.2 Histology of Osseous Tissue

Expected Learning Outcomes

When you have completed this section, you should be able to

a. list and describe the cells, fibers, and ground substance of bone tissue;
b. state the functional importance of each constituent of bone tissue;
c. compare the histology of the two types of bone tissue; and
d. distinguish between two types of bone marrow.

Bone Cells

Like any other connective tissue, bone consists of cells, fibers, and ground substance. There are four types of bone cells (fig. 6.3):

1. **Osteogenic**[11] **(osteoprogenitor) cells** are stem cells found in the endosteum, the inner layer of the periosteum, and within the *central canals,* to be described shortly. They arise from embryonic mesenchyme. Osteogenic cells multiply continually and give rise to the *osteoblasts* described next.
2. **Osteoblasts**[12] are bone-forming cells that synthesize the organic matter of the matrix and help to mineralize the bone. They line up in rows in the endosteum and inner layer of periosteum and resemble a cuboidal epithelium on the bone surface (see fig. 6.8). Osteoblasts are nonmitotic, so the only source of new osteoblasts is the osteogenic cells. Stress and fractures stimulate accelerated mitosis of those cells and therefore a rapid rise in the number of osteoblasts, which then reinforce or rebuild the bone.
3. **Osteocytes** are former osteoblasts that have become trapped in the matrix they deposited. They live in tiny cavities called **lacunae,**[13] which are connected to each other by slender channels called **canaliculi**[14] (CAN-uh-LIC-you-lye). Each osteocyte has delicate cytoplasmic processes that reach into the canaliculi to meet the processes of neighboring osteocytes. Adjacent osteocytes are joined by gap junctions at the tip of these processes. These junctions allow osteocytes to pass nutrients and chemical signals to each other and to transfer wastes to the nearest blood vessels for disposal. Osteocytes also communicate by gap junctions with the osteoblasts on the bone surface.

   Osteocytes have multiple functions. Some resorb bone matrix and others deposit it, so they contribute to the

---

[9] *artic* = joint
[10] *diplo* = double
[11] *osteo* = bone; *genic* = producing
[12] *osteo* = bone; *blast* = form, produce
[13] *lac* = lake, hollow; *una* = little
[14] *canal* = canal, channel; *icul* = little


Osteogenic cell
Osteoblast
Osteocyte
Rough endoplasmic reticulum
Nucleus
Secretory vesicles
Mitochondrion
(a) Osteocyte development
Osteocyte
Osteoclast
Osseous tissue
Stem cells
Periosteum
Resorption bay
Nuclei
Fusion
Osteoclast
Lysosomes
Ruffled border
(b) Osteoclast development

Figure 6.3 **Bone Cells and Their Development.** (a) Osteogenic cells give rise to osteoblasts, which deposit matrix around themselves and transform into osteocytes. (b) Bone marrow stem cells fuse to form osteoclasts.

homeostatic maintenance of both bone density and blood concentrations of calcium and phosphate ions. Perhaps even more importantly, they are strain sensors. When a load is applied to a bone, it produces a flow in the extracellular fluid of the lacunae and canaliculi. Osteocytes have a little antenna—a solitary cilium—that senses this fluid flow. This stimulates the osteocytes to secrete biochemical signals that may regulate bone remodeling—adjustments in bone shape and density to adapt to stress.

4. **Osteoclasts**[15] are bone-dissolving macrophages found on bone surfaces. They develop from the same bone marrow stem cells that give rise to blood cells. Several stem cells fuse with each other to form an osteoclast; thus, osteoclasts are unusually large (up to 150 μm in diameter) and typically have 3 or 4 nuclei, but sometimes up to 50. The side of the osteoclast facing the bone has a *ruffled border* with many deep infoldings of the plasma membrane, increasing its surface area. Hydrogen pumps in the ruffled border secrete hydrogen ions (H^+) into the extracellular fluid, and chloride ions (Cl^-) follow by electrical attraction; thus, the space between the osteoclast and the bone becomes filled with hydrochloric acid (HCl). The HCl, with a pH of about 4, dissolves the minerals of the adjacent bone. Lysosomes of the osteoclast then release enzymes that digest the organic component. Osteoclasts often reside in little pits called *resorption bays* that they have etched into the bone surface.

Apply What You Know

Considering the function of osteoblasts, what organelles do you think are especially abundant in their cytoplasm?

Matrix

The matrix of osseous tissue is, by dry weight, about one-third organic and two-thirds inorganic matter. The organic matter includes collagen and various large protein–carbohydrate complexes called glycosaminoglycans, proteoglycans, and glycoproteins. The inorganic matter is about 85% **hydroxyapatite,** a crystallized calcium phosphate salt [$Ca_{10}(PO_4)_6(OH)_2$]; 10% calcium carbonate ($CaCO_3$); and lesser amounts of magnesium, sodium, potassium, fluoride, sulfate, carbonate, and hydroxide ions.

---

[15] *osteo* = bone; *clast* = destroy, break down

DEEPER INSIGHT 6.2

Polymers, Ceramics, and Bones

The physical properties of bone can be understood by analogy to some principles of engineering. Engineers use four kinds of construction materials: metals, ceramics (stone, glass, cement), polymers (rubber, plastic, cellulose), and composites (mixtures of two or more of the other classes). Bone is a composite of polymer (protein) and ceramic (mineral). The protein gives it flexibility and resistance to tension, while the mineral gives it resistance to compression. Owing to the mineral component, a bone can support the weight of the body without sagging, and owing to the protein component, it can bend a little when subjected to stress.

Bone is somewhat like a fiberglass fishing rod, which is made of a ceramic (glass fibers) embedded in a polymer (resin). The fibers alone would be too flexible and limp to serve the purpose of a fishing rod, while the resin alone would be too brittle and would easily break. The combination of the two, however, gives the rod strength and flexibility. Unlike fiberglass, however, the ratio of ceramic to polymer in a bone varies from one location to another, adapting osseous tissue to different amounts of tension and compression exerted on different parts of the skeleton.

The minerals and collagen form a composite that gives bones a combination of flexibility and strength similar to fiberglass (see Deeper Insight 6.2). The minerals resist compression (crumbling or sagging when weight is applied). When bones are deficient in calcium salts, they soften and bend easily. Soft bones are characteristic of a childhood disease called **rickets,** which occurs when a child is deficient in vitamin D and therefore cannot absorb enough dietary calcium to adequately harden the bones. The legs bow outward under the weight of the body.

The collagen fibers of bone give it the ability to resist tension, so the bone can bend slightly without snapping. When you run, for example, each time your body weight comes down on one leg, the long bones in that leg bend slightly. Without collagen, they would be so brittle they would crack or shatter. Brittle bone disease dramatically demonstrates the importance of collagen to bone strength (see Deeper Insight 3.3, p. 71).

Compact Bone

The histological study of compact bone usually uses slices that have been dried, cut with a saw, and ground to translucent thinness. This procedure destroys the cells and much of the other organic content but reveals fine details of the inorganic matrix (fig. 6.4d). Cross sections of compact bone show onionlike **concentric lamellae**—layers of matrix concentrically arranged around a **central (haversian**[16] or **osteonic) canal.** A central canal and its lamellae constitute an **osteon (haversian system)**—the basic structural unit of compact bone. In longitudinal sections and three-dimensional reconstructions, we find that an osteon is a cylinder of tissue surrounding a central canal. Along their length, central canals are joined by transverse or diagonal passages called **perforating canals.** The central and perforating canals contain blood vessels and nerves. Lacunae lie between adjacent layers of matrix and are connected with each other by canaliculi. Canaliculi of the innermost lacunae open into the central canal.

In each lamella, the collagen fibers "corkscrew" down the matrix in a helical pattern like the threads of a screw. The helices coil in one direction in one lamella and in the opposite direction in the next lamella. Like alternating layers of a sheet of plywood, this makes the bone stronger and enables it to resist tension in multiple directions. In areas where the bone must resist tension (bending), the helix is loosely coiled like the threads on a wood screw and the fibers are more stretched out on the longitudinal axis of the bone. In weight-bearing areas, where the bone must resist compression, the helix is more tightly coiled like the closely spaced threads on a bolt, and the fibers are more nearly transverse.

The skeleton receives about half a liter of blood per minute. Blood vessels, along with nerves, enter the bone tissue through nutrient foramina on the surface. These open into perforating canals that cross the matrix and lead to the central canals. The wall of a central canal looks as if it was pierced with innumerable pinholes. These are the openings from the canaliculi of the innermost lacunae. The osteocytes closest to the central canal receive nutrients from the blood and pass them along through their gap junctions to neighboring osteocytes. They also receive wastes from their neighbors and convey them to the central canal for removal by the bloodstream. Thus, the cytoplasmic processes of the osteocytes maintain a two-way flow of nutrients and wastes between the central canal and the outermost cells of the osteon.

Not all of the matrix is organized into osteons. The inner and outer boundaries of dense bone are arranged in *circumferential lamellae* that run parallel to the bone surface. Between osteons, we can find irregular patches of *interstitial lamellae,* the remains of old osteons that broke down as the bone grew and remodeled itself.

Spongy Bone

Spongy bone consists of a lattice of delicate-looking slivers of bone called **spicules**[17] (rods or spines, as in the photo on p. 131) and **trabeculae**[18] (thin plates as in fig. 6.4c). Although calcified and hard, spongy bone is named for its porous appearance; it is permeated by spaces filled with bone marrow. The matrix is arranged in lamellae like those of compact bone, but they are not arranged in concentric layers, and there are few osteons. Central canals are not needed here because no osteocyte is very far from the blood supply in the marrow. Spongy bone is well designed to impart strength to a bone without adding

---

[16] Clopton Havers (1650–1702), English anatomist

[17] *spicul* = dart, little point

[18] *trabe* = plate; *cul* = little


Compact bone
Spongy bone
(a)
Bone marrow
Trabecula
(c)
Nerve
Blood vessel
Spicules
Trabeculae
Spongy bone
Endosteum
Periosteum
Perforating fibers
Perforating canal
Central canal
Lacuna
Collagen fibers
Concentric lamellae
Circumferential lamellae
Osteon
(b)
Lacunae
Canaliculi
Central canal
Lamella
(d)
20 µm

© B Christopher/Alamy

© Biophoto Associates/Science Source

© Custom Medical Stock Photo/Newscom

Figure 6.4 **The Histology of Osseous Tissue.** (a) Compact and spongy bone in a frontal section of the femur. (b) The three-dimensional structure of compact bone. Lamellae of one osteon are telescoped to show their alternating arrangement of collagen fibers. (c) Microscopic appearance of spongy bone and bone marrow. (d) Microscopic appearance of a cross section of compact bone. AP|R

- *Which type of osseous tissue has more surface area exposed to osteoclast action?*



© Biophoto Associates/Science Source

Figure 6.5 **Spongy Bone Structure in Relation to Mechanical Stress.** In this frontal section of the femur, the trabeculae of spongy bone can be seen oriented along lines of mechanical stress applied by the weight of the body.

unnecessary weight. Its trabeculae are not randomly arranged, as they might seem at a glance, but develop along the bone's lines of stress (fig. 6.5).

Bone Marrow

Bone marrow is a general term for the soft material that occupies the marrow cavity of a long bone, the spaces amid the trabeculae of spongy bone, and the largest of the central canals. In a child, the medullary cavity of nearly every bone is filled with **red bone marrow,** which gets its color from an abundance of red blood cells. Although it is called *myeloid tissue,* red bone marrow is best regarded as an organ. Chapter 22 (p. 617) describes the microscopic structure that justifies that assessment. Red bone marrow is also described as *hemopoietic*[19] (HE-mo-poy-ET-ic), or blood-forming, tissue. All types of blood cells are produced here, although some types are also produced in hemopoietic tissues elsewhere, such as the lymph nodes and thymus.

With age, the red bone marrow is gradually replaced by fatty **yellow bone marrow,** like the fat seen at the center of a ham bone. By early adulthood, red bone marrow is limited to the skull, vertebrae, sternum, ribs, part of the pelvic (hip) girdle, and the proximal heads of the humerus and femur; the rest of the skeleton contains yellow marrow (fig. 6.6). Yellow bone marrow no longer produces blood, although in the event of severe or chronic anemia, it can transform back into red marrow and resume that role.



Figure 6.6 **Distribution of Red and Yellow Bone Marrow.** In an adult, red bone marrow occupies the medullary cavities in the regions colored red. Yellow bone marrow occurs in the long bones of the limbs.
• *Suppose red bone marrow was needed for transfusion to a patient. On the basis of this illustration, suggest one or more optimal anatomical sites for drawing red bone marrow from a donor.*

Before You Go On

Answer the following questions to test your understanding of the preceding section:

6. Suppose you had unlabeled electron micrographs of the four kinds of bone cells and their neighboring tissues. Name each of the four cells and explain how you could visually distinguish each one from the other three.
7. Name three organic components of the bone matrix.
8. What are the mineral crystals of bone called, and what are they made of?
9. Sketch a cross section of an osteon and label its major parts.
10. What are the two kinds of bone marrow? What does *hemopoietic tissue* mean? Which type of bone marrow fits this description?

---

[19] *hemo* = blood; *poietic* = forming

6.3 Bone Development

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe two mechanisms of bone formation;
b. explain how a child grows in height; and
c. explain how mature bone continues to grow and remodel itself.

The formation of bone is called **ossification** (OSS-ih-fih-CAY-shun), or **osteogenesis.** There are two methods of ossification—*intramembranous* and *endochondral.* Both begin with the soft embryonic connective tissue called *mesenchyme* (MEZ-en-kime).

Intramembranous Ossification

Intramembranous[20] (IN-tra-MEM-bruh-nus) **ossification** produces the flat bones of the skull and most of the clavicle (collarbone). Such bones develop within a fibrous sheet similar to the dermis of the skin, so they are sometimes called *dermal bones.* Figure 6.7 shows the stages of the process.

① Mesenchyme first condenses into a soft sheet of tissue permeated with blood vessels—the *membrane* to which *intramembranous* refers. Mesenchymal cells line up along the blood vessels, become osteoblasts, and secrete a soft collagenous *osteoid tissue* in the direction away from the vessel. Osteoid tissue resembles bone but is not yet hardened by minerals (fig. 6.8).

② Calcium phosphate and other minerals crystallize on the collagen fibers of the osteoid tissue and harden the matrix. Continued osteoid deposition and mineralization squeeze the blood vessels and future bone marrow into narrower and narrower spaces. As osteoblasts become trapped in their own hardening matrix, they become osteocytes.

③ While the foregoing processes are going on, more of the mesenchyme adjacent to the developing bone condenses and forms a fibrous periosteum on each surface. The spongy bone becomes a honeycomb of slender calcified trabeculae.

④ At the surfaces, osteoblasts beneath the periosteum deposit layers of bone, fill in the spaces between trabeculae, and create a zone of compact bone on each side, as well as thickening the bone overall. This process gives rise to the sandwichlike structure typical of a flat cranial bone—a layer of spongy bone between two surface layers of compact bone.

Intramembranous ossification also plays an important role in the lifelong thickening, strengthening, and remodeling of the long bones discussed next. Throughout the skeleton, it is the method of depositing new tissue on the bone surface even past the age where our bones can no longer grow in length.

Endochondral Ossification

Endochondral[21] (EN-doe-CON-drul) **ossification** produces most other bones, including the vertebrae, ribs, scapulae, pelvic bones, bones of the limbs, and some parts of the skull. It begins around the sixth week of fetal development and continues into a person's 20s. It is a process in which mesenchyme first differentiates into a hyaline cartilage model in the approximate shape of the bone to come. The cartilage is then broken down and replaced by osseous tissue. Many bones have complex shapes with several centers of endochondral ossification, so we will study this with one of the anatomically simplest bones, a metacarpal bone from the palm of the fetal hand (fig. 6.9). Correlate the following steps with the figure as you read.

① Mesenchyme develops into a body of hyaline cartilage, covered with a fibrous perichondrium, in the location of a future bone. For a time, the perichondrium produces chondrocytes and the cartilage model grows in thickness.

② In a **primary ossification center** near the middle of this cartilage, chondrocytes begin to inflate and die, while the thin walls between them calcify. The perichondrium stops producing chondrocytes and begins producing osteoblasts. These deposit a thin collar of bone around the middle of the cartilage model, encircling it like a napkin ring and providing physical reinforcement. The former perichondrium is now considered to be a periosteum.

③ Blood vessels grow inward from the periosteum and invade the ossification center. Osteoclasts arrive in the blood and digest calcified tissue in the shaft, hollowing it out and creating the **primary marrow cavity.** Osteoblasts also arrive and deposit layers of bone lining the cavity, thickening the shaft. As the bony collar under the periosteum thickens and elongates, a wave of cartilage death progresses toward the ends of the bone. Osteoclasts in the marrow cavity follow this wave, dissolving calcified cartilage remnants and enlarging the marrow cavity of the diaphysis. The region of transition from cartilage to bone at each end of the primary marrow cavity is called a **metaphysis** (meh-TAF-ih-sis). Soon, chondrocyte enlargement and death occur in the epiphysis of the model as well, creating a **secondary ossification center.**

---

[20] *intra* = within; *membran* = membrane

[21] *endo* = within; *chondr* = cartilage


Blood vessel
Osteoid tissue
Osteoblasts
Mesenchyme
Mesenchymal cell
Osteoid tissue
Bone trabecula
Marrow spaces
Osteocyte
Osteoblast

① Deposition of osteoid tissue into embryonic mesenchyme

② Calcification of osteoid tissue and entrapment of osteocytes


Mesenchyme
Periosteum
Spongy bone
Periosteum
Bone trabeculae
Periosteum
Compact bone
Spongy bone
Compact bone
Periosteum

③ Honeycomb of spongy bone with developing periosteum

④ Filling of space to form compact bone at surfaces, leaving spongy bone in middle

Figure 6.7 **Intramembranous Ossification.** The figures are drawn to different scales, with the highest magnification and detail at the beginning and backing off for a broader overview at the end of the process.

- *With the aid of chapter 7, name at least two specific bones that form by this process.*


Periosteum:
Fibrous layer
Osteogenic layer
Osteoid tissue
Osseous tissue (bone)
Osteoblasts
Osteocytes
© Ken Saladin

Figure 6.8 **Intramembranous Ossification of a Cranial Bone of the Human Fetus.** Note the layers of osteoid tissue, osteoblasts, and fibrous periosteum on both sides of the bone.

4 The secondary ossification center hollows out by the same process as the diaphysis, generating a **secondary marrow cavity** at the end of the bone. This cavity expands outward from the center, in all directions. At the time of birth, the bone typically looks like step 4 in figure 6.9. In bones with two secondary ossification centers, one center lags behind the other in development, so at birth there is a secondary marrow cavity at one end, but chondrocyte growth has just begun at the other. The joints of the limbs are still cartilaginous at birth, much as they are in the 12-week fetus in figure 7.30, p. 176.

5 During infancy and childhood, the epiphyses fill with spongy bone. Cartilage is then limited to the articular cartilage covering each joint surface, and to the **epiphyseal plate** of cartilage separating the primary and secondary marrow cavities at one or both ends of the bone. The plate persists through childhood and adolescence and serves as a growth zone for bone elongation. This growth process is described in the next section.

6 By the late teens to early twenties, all remaining cartilage in the epiphyseal plate is generally consumed, and the gap between the epiphysis and diaphysis closes. The primary and secondary marrow cavities then unite into a single cavity. The bones can grow no longer, and one attains his or her maximum adult height. The only remnants of the original cartilage model are the articular cartilages that cover the joint surfaces of the bone.

Bone Growth

Ossification does not end at birth, but continues throughout life with the growth and remodeling of bones. Bones grow in two directions: length and width.


Perichondrium
Hyaline cartilage
① Early cartilage model
Enlarging chondrocytes
Bony collar
Primary ossification center
Periosteum
Secondary ossification center
Blood vessel
Primary marrow cavity
Secondary marrow cavity
Epiphysis
Metaphysis
Diaphysis
Secondary ossification center
Epiphyseal plate
Nutrient foramen
Compact bone
Metaphysis
Cartilage
Articular cartilage
Spongy bone
Epiphyseal line
Periosteum
Marrow cavity

② Formation of primary ossification center, bony collar, and periosteum

③ Vascular invasion, formation of primary marrow cavity, and appearance of secondary ossification center

④ Bone at birth, with enlarged primary marrow cavity and appearance of secondary marrow cavity in one epiphysis

⑤ Bone of child, with epiphyseal plate at distal end

⑥ Adult bone with a single marrow cavity and closed epiphyseal plate

Figure 6.9 **Stages of Endochondral Ossification.** A metacarpal bone of the hand.
• *With the aid of chapter 8, name at least two specific bones that would have two epiphyseal plates (proximal and distal) at stage 5.*

Bone Elongation

To understand growth in length, we must return to the epiphyseal plates mentioned earlier. On an X-ray, the plate appears as a translucent line across the end of a bone, since it is not yet ossified (fig. 6.10). It consists of a band of typical hyaline cartilage in the middle and a metaphysis on each side. In figure 6.9, steps 4 and 5, the cartilage is the blue region and each metaphysis is violet. Even if one end of a bone lacks an epiphyseal plate, it has a metaphysis—the transitional zone between the epiphyseal cartilage and diaphyseal osseous tissue.

At the metaphysis, the cartilage thickens by cell division and enlargement and then undergoes replacement by bone. Figure 6.11 shows the histological structure of the metaphysis and the following steps in this process.

① **Zone of reserve cartilage.** This region, farthest from the marrow cavity, consists of typical resting hyaline cartilage.

② **Zone of cell proliferation.** A little closer to the marrow cavity, chondrocytes multiply and arrange themselves into longitudinal columns of flattened lacunae.

③ **Zone of cell hypertrophy.** Next, the chondrocytes cease to multiply and begin to hypertrophy (enlarge), much like they do in the primary ossification center of the fetus. The walls of matrix between lacunae become very thin.


Diaphysis
Epiphysis
Epiphyseal plate
Metacarpal bone
Epiphyseal plate
Epiphyseal plate

© Jim Wehtje/Getty Images RF

Figure 6.10 **X-ray of a Child's Hand.** The cartilaginous epiphyseal plates are evident at the ends of the long bones. These will disappear and the epiphyses will fuse with the diaphyses by adulthood. Long bones of the hand and fingers develop only one epiphyseal plate.


Zone ①
Zone ⑤
Multiplying chondrocytes
Enlarging chondrocytes
Breakdown of lacunae
Calcifying cartilage
Bone marrow
Osteoblasts
Osteocytes
Trabeculae of spongy bone
① Zone of reserve cartilage
Typical histology of resting hyaline cartilage
② Zone of cell proliferation
Chondrocytes multiplying and lining up in rows of small flattened lacunae
③ Zone of cell hypertrophy
Cessation of mitosis; enlargement of chondrocytes and thinning of lacuna walls
④ Zone of calcification
Temporary calcification of cartilage matrix between columns of lacunae
⑤ Zone of bone deposition
Breakdown of lacuna walls, leaving open channels; death of chondrocytes; bone deposition by osteoblasts, forming trabeculae of spongy bone

© Victor Eroschenko

Figure 6.11 **Zones of the Metaphysis.** This micrograph shows the replacement of cartilage with bone in the growth zone of a long bone.
- *Which two zones in this figure account for the growth of a child in height?*

④ **Zone of calcification.** Minerals are deposited in the matrix between the columns of lacunae and calcify the cartilage. These are not the permanent mineral deposits of bone, but only a temporary support for the cartilage that would otherwise soon be weakened by the breakdown of the enlarged lacunae.

⑤ **Zone of bone deposition.** Within each column, the walls between the lacunae break down and the chondrocytes die. This converts each column into a longitudinal channel (white spaces in the figure), which is immediately invaded by blood vessels and marrow from the marrow cavity. Osteoblasts line up along the walls of these channels and begin depositing concentric lamellae of matrix, while osteoclasts dissolve the temporarily calcified cartilage.

The process of bone deposition in zone 5 creates a region of spongy bone at the end of the marrow cavity facing the metaphysis. This spongy bone remains for life, although with extensive lifelong remodeling. But around the perimeter of the marrow cavity, continuing ossification converts this spongy bone to compact bone. Osteoblasts lining the aforementioned channels deposit layer after layer of bone matrix, so the channel grows narrower and narrower. These layers become the concentric lamellae of an osteon. Finally only a slender channel persists, the central canal of a new osteon. As usual, osteoblasts trapped in the matrix become osteocytes.

Apply What You Know

In a given osteon, which lamellae are the oldest—those immediately adjacent to the central canal or those around the perimeter of the osteon? Explain your answer.

How does a child or adolescent grow in height? Chondrocyte multiplication in zone 2 and hypertrophy in zone 3 continually push the zone of reserve cartilage (1) toward the ends of the bone, so the bone elongates. In the lower limbs, this process causes a person to grow in height, while bones of the upper limbs grow proportionately.

Thus, bone elongation is really a result of cartilage growth. Cartilage growth from within, by the multiplication of chondrocytes and deposition of new matrix in the interior, is called **interstitial growth.**[22] The most common form of dwarfism results from a failure of cartilage growth in the long bones (see Deeper Insight 6.3).

When the epiphyseal plate is depleted in the late teens to early twenties, it leaves a line of relatively dense spongy bone called the **epiphyseal line,** marking the former location of the plate (see figs. 6.1 and 6.9, step 6). Often a delicate ridge on the bone surface also marks this location. When the epiphyseal plate is depleted, we say that the epiphyses have "closed" because no gap between the epiphysis and diaphysis is visible on an X-ray. Once the epiphyses have all closed in the lower limbs, a person can grow no taller. The epiphyseal plates close at different ages in different bones and in different regions of the same bone. The state of closure in various bones is often used in forensic science to estimate the age at death of a subadult skeleton.

Bone Widening and Thickening

Bones also grow throughout life in diameter and thickness. This involves a process called **appositional growth,**[23] the deposition of new tissue at the surface. Cartilages can enlarge by both interstitial and appositional growth, but osseous tissue is limited to the appositional method. Embedded in a calcified matrix, the osteocytes have no room to spare for the deposition of more matrix internally.

Appositional growth occurs by intramembranous ossification at the bone surface. Osteoblasts in the inner layer of periosteum deposit osteoid tissue on the bone surface, calcify it, and become trapped in it as osteocytes—much like the process in figure 6.8. They lay down matrix in layers parallel to the surface, not in cylindrical osteons like those deeper in the bone. This process produces the surface layers of bone called *circumferential lamellae,* described earlier. As a bone increases in diameter, its marrow cavity also widens. This is achieved by osteoclasts of the endosteum dissolving tissue on the inner bone surface. Therefore, we see that flat bones develop by intramembranous ossification alone, whereas long bones develop by a combination of endochondral and intramembranous ossification.

Bone Remodeling

In addition to their growth, bones are continually remodeled throughout life by the absorption of old bone and deposition of new. This process replaces about 10% of the skeletal tissue per year. It repairs microfractures, releases minerals into the blood, and reshapes bones in response to use and disuse. **Wolff's**[24] **law of bone** states that the architecture of a bone is determined by the mechanical stresses placed upon it, and the bone thereby adapts to withstand those stresses. Wolff's law is a fine example of the complementarity of form and function, showing that the form of a bone is shaped by its functional experience. The effect of stress on bone development is quite evident in tennis players, for example, in whom the bones of the racket arm and the

DEEPER INSIGHT 6.3

Achondroplastic Dwarfism

Achondroplastic[25] (ah-con-dro-PLAS-tic) *dwarfism* is a condition in which the long bones of the limbs stop growing in childhood, while the growth of other bones is unaffected. As a result, a person has a short stature but a normal-sized head and trunk (fig. 6.12). As its name implies, achondroplastic dwarfism results from a failure of cartilage growth—specifically, failure of the chondrocytes in zones 2 and 3 of the metaphysis to multiply and enlarge. This is different from *pituitary dwarfism,* in which a deficiency of growth hormone stunts the growth of all of the bones and a person has short stature but normal proportions throughout the skeletal system.

Achondroplastic dwarfism results from a spontaneous mutation that can arise any time DNA is replicated. Two people of normal height with no family history of dwarfism can therefore have a child with achondroplastic dwarfism. The mutant allele is dominant, so the children of a heterozygous achondroplastic dwarf have at least a 50% chance of exhibiting dwarfism, depending on the genotype of the other parent.



© Ken Saladin

Figure 6.12 **Achondroplastic Dwarfism.** The student on the right, pictured with her roommate of normal height, is an achondroplastic dwarf with a height of about 122 cm (48 in.). Her parents were of normal height. Note the normal proportion of head to trunk but shortening of the limbs.

---

[22] *inter* = between; *stit* = to place, stand
[23] *ap* = *ad* = to, near; *posit* = to place
[24] Julius Wolff (1836–1902), German anatomist and surgeon
[25] *a* = without; *chondro* = cartilage; *plast* = growth

clavicle on that side are more robust than those of the other side. Wolff's law is admirably demonstrated by figure 6.5, in which we see that the trabeculae of spongy bone have developed along the lines of stress placed on the femur. Wolff observed that these stress lines were very similar to the ones that engineers already knew of in mechanical cranes.

Bone remodeling comes about through the collaborative action of osteoblasts and osteoclasts. If a bone is little used, osteoclasts remove matrix and get rid of unnecessary mass. If a bone is heavily used or a stress is consistently applied to a particular region of a bone, osteoblasts deposit new osseous tissue and thicken the bone. Consequently, the comparatively smooth bones of an infant or toddler develop a variety of surface bumps, ridges, and spines (described in chapter 7) as the child begins to walk. The greater trochanter of the femur, for example (see fig. 6.5, p. 138; and fig. 8.10, p. 195), is a massive outgrowth of bone stimulated by the pull of tendons from several powerful hip muscles employed in walking.

On average, bones have greater density and mass in athletes and people engaged in heavy manual labor than they do in sedentary people. Anthropologists who study ancient skeletal remains use evidence of this sort to help distinguish between members of different social classes, such as distinguishing aristocrats from laborers. Even in studying modern skeletal remains, as in investigating a suspicious death, Wolff's law comes into play as the bones give evidence of a person's sex, race, height, weight, work or exercise habits, nutritional status, and medical history.

The orderly remodeling of bone depends on a precise balance between deposition and resorption, between osteoblasts and osteoclasts. If one process outpaces the other, or both processes occur too rapidly, various bone deformities, developmental abnormalities, and other disorders occur, such as *osteitis deformans* (Paget disease) and *osteoporosis* (see table 6.2, p. 148; and Deeper Insight 3.3, p. 71).

Nutritional and Hormonal Factors

The balance between bone deposition and resorption is influenced by nearly two dozen nutrients, hormones, and growth factors. The most important factors that promote bone deposition are as follows.

- **Calcium** and **phosphate** are needed as raw materials for the calcified ground substance of bone.
- **Vitamin A** promotes synthesis of the glycosaminoglycans (GAGs) of the bone matrix.
- **Vitamin C (ascorbic acid)** promotes the cross-linking of collagen molecules in bone and other connective tissues.
- **Vitamin D (calcitriol)** is necessary for calcium absorption by the small intestine, and it reduces the urinary loss of calcium and phosphate. Vitamin D is synthesized by one's own body. The process begins when the ultraviolet radiation in sunlight acts on a cholesterol derivative (7-dehydrocholesterol) in the keratinocytes of the epidermis. The product is picked up by the bloodstream, and the liver and kidneys complete its conversion to vitamin D.
- **Calcitonin,** a hormone secreted by the thyroid gland, stimulates osteoblast activity. It functions chiefly in children and pregnant women; it seems to be of little significance in nonpregnant adults.
- **Growth hormone** promotes intestinal absorption of calcium, the proliferation of cartilage at the epiphyseal plates, and the elongation of bones.
- **Sex steroids** (estrogen and testosterone) stimulate osteoblasts and promote the growth of long bones, especially in adolescence.

Bone deposition is also promoted by thyroid hormone, insulin, and local *growth factors* produced within the bone itself. Bone resorption is stimulated mainly by one hormone:

- **Parathyroid hormone (PTH)** is produced by four small *parathyroid glands,* which adhere to the back of the thyroid gland in the neck. The parathyroid glands secrete PTH in response to a drop in blood calcium level. PTH stimulates osteoblasts, which then secrete an *osteoclast-stimulating factor* that promotes bone resorption by the osteoclasts. The principal purpose of this response is not to maintain bone composition but to maintain an appropriate level of blood calcium, without which a person can suffer fatal muscle spasms. PTH also reduces urinary calcium losses and promotes calcitriol synthesis.

The Aging Skeletal System

The predominant effect of aging on the skeleton is a loss of bone mass and strength. After age 35 or 40, osteoblasts become less active than osteoclasts. The imbalance between deposition and resorption leads to **osteopenia,**[26] the loss of bone; when the loss is severe enough to compromise physical activity and health, it is called *osteoporosis* (discussed in the next section). After age 40, women lose about 8% of their bone mass per decade, and men lose about 3%. Bone loss from the jaws is a contributing factor in tooth loss. Not only does bone density decline with age, but the bones become more brittle as the osteoblasts synthesize less protein. Fractures occur more easily and heal more slowly. Arthritis, a family of joint disorders associated with aging, is discussed in chapter 9.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

11. Describe the stages of intramembranous ossification. Name a bone that is formed in this way.
12. Describe the five zones of a metaphysis and the major distinctions between them.
13. How does Wolff's law explain some of the structural differences between the bones of a young child and the bones of a young adult?
14. Identify the nutrients most important to bone growth.
15. Identify the principal hormones that stimulate bone growth.

---

[26] *osteo* = bone; *penia* = lack, deficiency

6.4 Structural Disorders of Bone

Expected Learning Outcomes

When you have completed this section, you should be able to

a. name and describe the types of fractures;
b. explain how a fracture is repaired;
c. discuss the causes and effects of osteoporosis; and
d. briefly describe a few other structural defects of the skeleton.

Most people probably give little thought to their skeletal systems unless they break a bone, although many women know to be more concerned about a far more common bone disorder, osteoporosis. We end this chapter with a consideration of these two pathologies.

Fractures

There are multiple ways of classifying bone fractures. A **stress fracture** is a break caused by abnormal trauma to a bone, such as fractures incurred in falls, athletics, vehicular accidents, and military combat. A **pathological fracture** is a break resulting from a stress that would not normally fracture a bone, but that occurs in bones weakened by some other disease such as bone cancer or osteoporosis. Fractures are also classified according to the direction of the fracture line, whether or not the skin is broken, and whether a bone is merely cracked or is broken into separate pieces (table 6.1; fig. 6.13).

Most fractures are set by *closed reduction,* a procedure in which the bone fragments are manipulated into their normal positions without surgery. *Open reduction* involves the surgical exposure of the bone and the use of plates, screws, or pins to realign the fragments (fig. 6.14). To stabilize the bone during healing,

DEEPER INSIGHT 6.4

When *Not* to Eat Your Spinach

Many a child has been exhorted, “Eat your spinach! It’s good for you.” Popeye the Sailor assured cartoon fans that it made him strong to the finish. There is one time, however, when eating spinach isn’t such a good idea. People with healing bone fractures are advised to avoid it. Why? Spinach is rich in oxalate, an organic compound that binds calcium and magnesium in the digestive tract and interferes with their absorption. Consequently, oxalate can deprive a fractured bone of the free calcium that it needs in order to heal. There are about 571 milligrams of oxalate per 100 grams of spinach. Some other foods high in oxalate are cocoa (623 mg), rhubarb (447 mg), and beets (109 mg).

TABLE 6.1 Classification of Fractures

Type	Description
Closed	Skin is not broken (formerly called a *simple* fracture)
Open	Skin is broken; bone protrudes through skin or wound extends to fractured bone (formerly called a *compound* fracture)
Complete	Bone is broken into two or more pieces
Incomplete	Partial fracture that extends only partway across bone; pieces remain joined
Nondisplaced	The portions of bone are still in correct anatomical alignment (fig. 6.13a)
Displaced	The portions of bone are out of anatomical alignment (fig. 6.13b)
Comminuted	Bone is broken into three or more pieces (fig. 6.13c)
Greenstick	Bone is bent toward one side and has incomplete fracture on opposite side (fig. 6.13d)
Hairline	Fine crack in which sections of bone remain aligned; common in skull
Impacted	One bone fragment is driven into the marrow cavity or spongy bone of the other
Depressed	Broken portion of bone forms a concavity, as in skull fractures
Linear	Fracture parallel to long axis of bone
Transverse	Fracture perpendicular to long axis of bone
Oblique	Diagonal fracture, between linear and transverse
Spiral	Fracture spirals around axis of long bone as the result of a twisting stress such as a skiing accident



© Custom Medical Stock Photo/Newscom

© Howard Kingsnorth/Getty Images

(a) Nondisplaced **(b) Displaced**



© Lester V. Bergman/Corbis

© Custom Medical Stock Photo/Newscom

(c) Comminuted **(d) Greenstick**

Figure 6.13 **X-rays of Representative Fracture Types.** (a) Nondisplaced fracture of the distal humerus in a 3-year-old. (b) Displaced fracture of the tibia and fibula. (c) Comminuted fracture of the tibia and fibula. (d) Greenstick fracture of the radius and ulna.



© Southern Illinois University/Science Source

Figure 6.14 **Open Reduction of Ankle Fractures.** Fractures of the tibia and fibula have been set by surgically exposing the bone and realigning the fragments with plates and screws.

fractures are often set in fiberglass casts. *Traction* is used to treat fractures of the femur in children. It aids in the alignment of the bone fragments by overriding the force of the strong thigh muscles. Traction is rarely used for elderly patients, however, because the risks from long-term confinement to bed outweigh the benefits. Hip fractures are usually pinned, and early ambulation (walking) is encouraged because it promotes blood circulation and healing.

An uncomplicated fracture heals in 8 to 12 weeks, but complex fractures take longer, and all fractures heal more slowly in older people. Figure 6.15 shows the healing process. Usually, a healed fracture leaves a slight thickening of the bone visible by X-ray, but in some cases, healing is so complete that no trace of the fracture can be found.



① **Hematoma formation**
The hematoma is converted to granulation tissue by invasion of cells and blood capillaries.

② **Soft callus formation**
Deposition of collagen and fibrocartilage converts granulation tissue to a soft callus.

③ **Hard callus formation**
Osteoblasts deposit a temporary bony collar around the fracture to unite the broken pieces while ossification occurs.

④ **Bone remodeling**
Small bone fragments are removed by osteoclasts, while osteoblasts deposit spongy bone and then convert it to compact bone.

Figure 6.15 Stages in the Healing of a Bone Fracture.

Osteoporosis

Osteoporosis[27] (OSS-tee-oh-pore-OH-sis) is a disease in which bone density declines to the extent that the bones become brittle and subject to pathological fractures. It involves the loss of proportionate amounts of organic matrix and minerals, especially from the spongy bone, since this is the most metabolically active osseous tissue and has the greatest surface area exposed to osteoclast action. The bone that remains is histologically normal, but insufficient in quantity to support the body's weight and withstand normal stresses (fig. 6.16a).

People with osteoporosis are especially subject to fractures of the hip, wrist, and vertebral column. Their bones may break under stresses as slight as sitting down too quickly. Among the elderly, slowly healing hip fractures can impose prolonged immobility, which, in turn, may lead to fatal complications such as pneumonia. Those who survive often face a long, costly recovery. Spinal deformity is also a common consequence of osteoporosis. As the bodies of the vertebrae lose spongy bone, they become compressed by body weight (fig. 6.16b). People commonly lose height after middle age because of this, but those with osteoporosis often develop a more noticeable spinal deformity called **kyphosis,**[28] an exaggerated thoracic curvature ("widow's hump" or "dowager's hump") (fig. 6.16c).

Those at greatest risk for osteoporosis are postmenopausal white women, especially those of light body build. Compared to men, they have less initial bone mass and begin to lose it at an earlier age. Bone loss accelerates after menopause, when the estrogen level declines sharply. Estrogen supports bone mass by inhibiting osteoclast activity (bone resorption), but the ovaries no longer secrete it after menopause and the rate of bone resorption rises. By age 70, the average white woman has lost 30% of her bone mass, and some as much as 50%. Osteoporosis is less common among black women. Young black women have denser bone on average, and even though they too lose bone density after menopause, the loss usually doesn't reach the threshold for osteoporosis and pathological fractures. About 20% of osteoporosis sufferers are men. Men produce estrogen in both the adrenal glands and testes. By age 70, 50% of men have estrogen levels below the threshold needed to maintain bone density. Osteoporosis also occurs among young female runners, dancers, and gymnasts in spite of their vigorous exercise. Their percentage of body fat is so low that they may stop ovulating, and their ovaries secrete unusually low levels of estrogen. Other risk factors for osteoporosis include dietary deficiencies of calcium, vitamin D, and protein; inadequate exercise; smoking; and diabetes mellitus.

Osteoporosis is now diagnosed with *dual-energy X-ray absorptiometry (DEXA),* which uses low-dose X-rays to measure bone density. DEXA has allowed for earlier diagnosis and more effective drug treatment. However, the severity of osteoporosis depends not on bone density alone, but also on the degree of connectivity between the spongy bone trabeculae, which is lost as trabeculae deteriorate. Neither DEXA nor any other diagnostic method yet available can detect this.

Treatment of osteoporosis is aimed at slowing the rate of bone resorption. Estrogen-replacement therapy has fallen out of favor because it raises the risk of breast cancer, stroke, and coronary artery disease. One of the current preferred treatments is a family of osteoclast-destroying drugs called *bis-phosphonates* (trade names Fosamax, Actonel). They can increase bone mass and cut the risk of fractures in half, but their safety is still being evaluated. Pulsed doses of parathyroid hormone or derivatives such as teriparatide (trade name Forteo) can also increase bone mass by stimulating osteoblasts, but cannot be used for longer than 2 years because of a risk of bone cancer.


(a) © Michael Klein/Getty Images

(b) © Dr. P. Marazzi/Science Source

(c) © Phanie/Alamy

Figure 6.16 **Spinal Osteoporosis.** (a) Spongy bone in the body of a vertebra in good health (left) and with osteoporosis (right). (b) Colorized X-ray of lumbar vertebrae severely damaged by osteoporosis. (c) Abnormal thoracic spinal curvature (kyphosis) due to compression of thoracic vertebrae with osteoporosis.

---

[27] *osteo* = bone; *por* = porous; *osis* = condition

[28] *kypho* = bent, humpbacked; *osis* = condition

TABLE 6.2	Structural Disorders of Bone
Acromegaly[29]	A result of adult growth hormone hypersecretion, resulting in thickening of the bones and soft tissues, especially noticeable in the face, hands, and feet.
Osteitis deformans (Paget[30] disease)	Excessive osteoclast proliferation and bone resorption, with osteoblasts attempting to compensate by depositing extra bone. This results in rapid, disorderly bone remodeling and weak, deformed bones. Osteitis deformans usually passes unnoticed, but in some cases it causes pain, disfiguration, and fractures. It is most common in males over the age of 50.
Osteomalacia	Adult form of rickets, most common in poorly nourished women who have had multiple pregnancies. Bones become softened, deformed, and more susceptible to fractures.
Rickets	Defective mineralization of bone in children, usually as a result of insufficient sunlight or vitamin D, sometimes due to a dietary deficiency of calcium or phosphate or to liver or kidney diseases that interfere with calcitriol synthesis. Causes bone softening and deformity, especially in the weight-bearing bones of the lower limbs.
Disorders Described Elsewhere	
Achondroplastic dwarfism 143 Brittle bone disease 71 Fractures 145	Osteopenia 144 Osteoporosis 147

The risk of osteoporosis is best minimized by weight-bearing exercise and ample calcium and protein intake early in life, especially in the 20s and 30s when the skeleton is building to its maximum mass.

Other Structural Disorders

Several additional bone disorders are summarized in table 6.2. **Orthopedics**[31] is the branch of medicine that deals with the prevention and correction of injuries and disorders of the bones, joints, and muscles. As the word suggests, this field originated as the treatment of skeletal deformities in children, but it is now much more extensive. It includes the design of artificial joints and limbs and the treatment of athletic injuries.

---

[29] *acro* = extremity; *megaly* = abnormal enlargement
[30] Sir James Paget (1814–99), English surgeon
[31] *ortho* = straight; *ped* = child, foot

Before You Go On

Answer the following questions to test your understanding of the preceding section:

16. Name and describe any five types of bone fractures.
17. What is a callus? How does it contribute to fracture repair?
18. List the major risk factors for osteoporosis and describe some ways of preventing it.

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

6.1 Tissues and Organs of the Skeletal System (p. 132)

1. Components of the skeletal system, including but not limited to the bones
2. Seven functions of the skeletal system
3. The constituents of a bone, including but not limited to osseous tissue
4. How bones are classified by shape
5. The spatial relationship between compact and spongy bone
6. The parts of a typical long bone
7. The structure of a typical flat bone

6.2 Histology of Osseous Tissue (p. 134)

1. The four kinds of cells found in a bone, and their respective origins and functions
2. The specialized structure of an osteocyte and how this relates to the microscopic appearance of the bone matrix
3. The specialized structure of an osteoclast and how this relates to its function
4. The composition of the bone matrix and the complementary functional importance of its organic and inorganic components
5. The structural organization of the matrix of compact bone, including the names of the features seen with the microscope
6. The organization of spongy bone and how it combines strength with lightness
7. The two kinds of bone marrow, their locations in the adult skeleton, and their functional differences

6.3 Bone Development (p. 139)

1. The two modes of bone development (ossification) and some bones that develop by each method
2. The stages of intramembranous ossification, converting a soft mesenchymal sheet into a mature (usually flat) bone
3. The stages of endochondral ossification, replacing a hyaline cartilage model with a mature bone
4. Structural differences between the endochondral bones of adults and children, especially with regard to the epiphyseal plates
5. The zones of tissue found in the metaphysis of a child or adolescent; how they relate to the replacement of cartilage by bone; how they relate to the person's growth in height; and why a person cannot grow any taller after the end of adolescence
6. How the endochondral development of compact bone results in osteons with concentric lamellae arranged around the central canal
7. How bones grow in thickness and change shape even after they can no longer grow in length
8. What Wolff's law implies about the ability of bone to adapt to changes in stress
9. The nutrients needed for bone growth and maintenance
10. Hormones that regulate bone growth and remodeling
11. The effects of aging on the skeleton

6.4 Structural Disorders of Bone (p. 145)

1. The difference between stress fractures and pathological fractures
2. Terms for various types of fractures
3. The two basic approaches to clinical treatment of a fracture
4. The definition of *osteoporosis* and why this disease can be such a serious concern for the elderly
5. Osteoporosis risk factors, prevention, diagnosis, and treatment

Testing Your Recall

1. Which cells have a ruffled border and secrete hydrochloric acid?
   a. chondrocytes
   b. osteocytes
   c. osteogenic cells
   d. osteoblasts
   e. osteoclasts
2. The medullary cavity of a child's bone may contain
   a. red bone marrow.
   b. hyaline cartilage.
   c. periosteum.
   d. osteocytes.
   e. articular cartilages.
3. The long bones of the limbs grow in length by cell proliferation and hypertrophy in
   a. the epiphysis.
   b. the epiphyseal line.
   c. the dense bone.
   d. the metaphysis.
   e. the spongy bone.
4. Osteoclasts are most closely related by common descent to
   a. osteocytes.
   b. osteogenic cells.
   c. monocytes.
   d. fibroblasts.
   e. osteoblasts.
5. The walls between cartilage lacunae break down in the zone of
   a. cell proliferation.
   b. calcification.
   c. reserve cartilage.
   d. bone deposition.
   e. cell hypertrophy.
6. Which of these does *not* promote bone deposition?
   a. dietary calcium
   b. vitamin D
   c. parathyroid hormone
   d. calcitonin
   e. testosterone
7. A child jumps to the ground from the top of a playground "jungle gym." His leg bones do not shatter mainly because they contain
   a. an abundance of glycosaminoglycans.
   b. young, resilient osteocytes.
   c. an abundance of calcium phosphate.
   d. collagen fibers.
   e. hydroxyapatite crystals.
8. One long bone meets another at its
   a. diaphysis.
   b. epiphyseal plate.
   c. periosteum.
   d. metaphysis.
   e. epiphysis.
9. Calcitriol is made from
   a. calcitonin.
   b. 7-dehydrocholesterol.
   c. hydroxyapatite.
   d. estrogen.
   e. PTH.
10. One sign of osteoporosis is
    a. osteitis deformans.
    b. osteomalacia.
    c. a stress fracture.
    d. kyphosis.
    e. a calcium deficiency.
11. Calcium phosphate crystallizes in bone as a mineral called _____.
12. Osteocytes contact each other through channels called _____ in the bone matrix.
13. A bone increases in diameter only by _____ growth, the addition of new surface lamellae.
14. Most compact bone is organized in cylindrical units called _____, composed of lamellae encircling a central canal.
15. The _____ glands secrete a hormone that stimulates cells to resorb bone and return its minerals to the blood.
16. The ends of a bone are covered with a layer of hyaline cartilage called the _____.
17. The cells that deposit new bone matrix are called _____.
18. The most common bone disease is _____.
19. The transitional region between epiphyseal cartilage and the primary marrow cavity of a young bone is called the _____.
20. The cranial bones develop from a flat sheet of condensed mesenchyme in a process called _____.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give an example of a term in which it is used.

1. osteo-
2. diplo-
3. lac-
4. -clast
5. -osis
6. dia-
7. -logy
8. artic-
9. -icul
10. -oid

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. Spongy bone is normally covered by compact bone.
2. Most bones develop from hyaline cartilage.
3. Fractures are the most common bone disorder.
4. The growth zone of the long bones of adolescents is the articular cartilage.
5. Osteoclasts develop from osteoblasts.
6. Osteocytes develop from osteoblasts.
7. The protein of the bone matrix is called hydroxyapatite.
8. Blood vessels travel through the central canals of compact bone.
9. Yellow bone marrow has a hemopoietic function.
10. Parathyroid hormone promotes bone resorption and raises blood calcium concentration.

Answers in appendix A

Testing Your Comprehension

1. Most osteocytes of an osteon are far removed from blood vessels, but still receive blood-borne oxygen and nutrients. Explain how this is possible.
2. Predict what symptoms a person might experience if he or she suffered a degenerative disease in which the articular cartilages were worn away and the fluid between the bones dried up.
3. One of the more common fractures in children and adolescents is an *epiphyseal fracture,* in which the epiphysis of a long bone separates from the diaphysis. Explain why this would be more common in children than in adults.
4. Describe how the arrangement of trabeculae in spongy bone demonstrates the complementarity of form and function.
5. Identify two bone diseases you would expect to see if the epidermis was a completely effective barrier to UV radiation and a person took no dietary supplements to compensate for this. Explain your answer.



Anterosuperior view of the thoracic cage and pectoral girdle (colorized CT scan)

© Mehau Kulyk/Science Source

CHAPTER 7

THE SKELETAL SYSTEM II
AXIAL SKELETON

CHAPTER OUTLINE

7.1 Overview of the Skeleton 152
- Bones of the Skeletal System 153
- Anatomical Features of Bones 153

7.2 The Skull 155
- Cranial Bones 155
- Facial Bones 164
- Bones Associated with the Skull 166
- Adaptations of the Skull for Bipedalism 166

7.3 The Vertebral Column and Thoracic Cage 167
- General Features of the Vertebral Column 167
- General Structure of a Vertebra 169
- Intervertebral Discs 169
- Regional Characteristics of Vertebrae 169
- The Thoracic Cage 173

7.4 Developmental and Clinical Perspectives 176
- Development of the Axial Skeleton 176
- Pathology of the Axial Skeleton 179

Study Guide 181

DEEPER INSIGHTS

7.1 Injury to the Ethmoid Bone 164
7.2 Evolutionary Significance of the Palate 165
7.3 Abnormal Spinal Curvatures 168

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:
- Directional terms (p. 12)
- The axial and appendicular body regions (p. 13)
- The neural tube, somites, and pharyngeal arches of the embryo (pp. 91–92)
- General features of bones (p. 133)
- Intramembranous and endochondral ossification (p. 139)

Anatomy & Physiology REVEALED®
aprevealed.com

Module 5: Skeletal System

A knowledge of skeletal anatomy will be useful as you study later chapters. It provides a point of reference for studying the gross anatomy of other organ systems because many organs are named for their relationships to nearby bones. The subclavian artery and vein, for example, are adjacent to the clavicle; the temporalis muscle is attached to the temporal bone; the ulnar nerve and radial artery travel beside the ulna and radius of the forearm; and the frontal, parietal, temporal, and occipital lobes of the brain are named for adjacent bones of the cranium. An understanding of how the muscles produce body movements also depends on knowledge of skeletal anatomy. In addition, the positions, shapes, and processes of bones can serve as landmarks for a clinician in determining where to give an injection or record a pulse, what to look for in an X-ray, or how to perform physical therapy and other medical procedures.

7.1 Overview of the Skeleton

Expected Learning Outcomes

When you have completed this section, you should be able to

a. define the two subdivisions of the skeleton;
b. state the approximate number of bones in the adult body;
c. explain why this number varies with age and from one person to another; and
d. define several terms that denote surface features of bones.

The skeleton (fig. 7.1) is divided into two regions: axial and appendicular. The **axial skeleton,** studied in this chapter, forms the central supporting axis of the body and includes the skull, vertebral


Skull
Frontal bone
Maxilla
Mandible
Pectoral girdle
Clavicle
Scapula
Thoracic cage
Sternum
Ribs
Costal cartilages
Vertebral column
Pelvis
Hip bone
Sacrum
Coccyx
Carpus
Metacarpal bones
Phalanges
Patella
Tarsus
Parietal bone
Occipital bone
Mandible
Clavicle
Scapula
Humerus
Ulna
Radius
Femur
Fibula
Tibia
Metatarsal bones
Phalanges
(a) Anterior view
(b) Posterior view

Figure 7.1 **The Adult Skeleton.** The appendicular skeleton is colored green, and the rest is axial skeleton. APR

TABLE 7.1 Bones of the Adult Skeletal System

Axial Skeleton		Appendicular Skeleton
Skull (22 Bones)		**Pectoral Girdle (4 Bones)**
Cranial bones	Facial bones	Scapula (2)
Frontal bone (1)	Maxilla (2)	Clavicle (2)
Parietal bone (2)	Palatine bone (2)	**Upper Limbs (60 Bones)**
Occipital bone (1)	Zygomatic bone (2)	Humerus (2)
Temporal bone (2)	Lacrimal bone (2)	Radius (2)
Sphenoid bone (1)	Nasal bone (2)	Ulna (2)
Ethmoid bone (1)	Vomer (1)	Carpals (16)
	Inferior nasal concha (2)	Metacarpals (10)
	Mandible (1)	Phalanges (28)
Auditory Ossicles (6 Bones)		**Hip Bone (2 Bones)**
Malleus (2)		**Lower Limbs (60 Bones)**
Incus (2)		Femur (2)
Stapes (2)		Patella (2)
Hyoid Bone (1 Bone)		Tibia (2)
Vertebral Column (26 Bones)		Fibula (2)
Cervical vertebrae (7)	Sacrum (1)	Tarsals (14)
Thoracic vertebrae (12)	Coccyx (1)	Metatarsals (10)
Lumbar vertebrae (5)		Phalanges (28)
Thoracic Cage (25 Bones Plus Thoracic Vertebrae)		
Ribs (24)		
Sternum (1)		Grand Total: 206 Bones

column, ribs, and sternum. The **appendicular skeleton,** studied in chapter 8, includes the bones of the upper limb and pectoral girdle, and bones of the lower limb and pelvic girdle.

Bones of the Skeletal System

It is often stated that there are 206 bones in the skeleton, but this is only a typical adult count, not an invariable number. At birth, there are about 270, and even more bones form during childhood. With age, however, the number decreases as separate bones fuse. For example, each side of a child's pelvic girdle has three bones—the *ilium, ischium,* and *pubis*—but in adults, these are fused into a single *hip (coxal) bone* on each side. The fusion of several bones, completed by late adolescence to the mid-20s, brings about the average adult number of 206. These bones are listed in table 7.1.

The number varies even among adults. One reason is the development of **sesamoid**[1] **bones**—bones that form within certain tendons in response to stress. The patella (kneecap) is the largest of these; most of the others are small, rounded bones in such locations as the hands and feet (see fig. 8.14c, p. 198). Another reason for adult variation is that some people have extra bones in the skull called **sutural** (SOO-chure-ul), or **wormian,**[2] **bones** (see fig. 7.6).

Anatomical Features of Bones

Bones exhibit a variety of ridges, spines, bumps, depressions, canals, pores, slits, cavities, and articular surfaces, often called *bone markings.* It is important to know the names of these features because later descriptions of joints, muscle attachments, and the routes traveled by nerves and blood vessels are based on this terminology. The terms for the most common of these features are listed in table 7.2, and several of them are illustrated in figure 7.2.

As you study the skeleton, use yourself as a model. You can easily palpate (feel) many of the bones and some of their details through the skin. Rotate your forearm, cross your legs, palpate your skull and wrist, and think about what is happening beneath the surface or what you can feel through the skin. You will gain the most from this chapter (and indeed, the entire book) if you are conscious of your own body in relation to what you are studying.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. Name the major components of the axial skeleton. Name those of the appendicular skeleton.
2. Explain why an adult does not have as many bones as a child does. Explain why one adult may have more bones than another adult of the same age.
3. Briefly describe each of the following bone features: condyle, epicondyle, process, tubercle, fossa, sulcus, and foramen.

---

[1] *sesam* = sesame seed; *oid* = resembling
[2] Ole Worm (1588–1654), Danish physician

TABLE 7.2 Surface Features (Markings) of Bones

Term	Description and Example
Canal	A tubular passage or tunnel in a bone (auditory canal of the skull)
Condyle	A rounded knob (occipital condyles of the skull)
Crest	A narrow ridge (iliac crest of the pelvis)
Epicondyle	A flare superior to a condyle (medial epicondyle of the femur)
Facet	A smooth joint surface that is flat or only slightly concave or convex (articular facets of the vertebrae)
Fissure	A slit through a bone (orbital fissures behind the eye)
Foramen	A hole through a bone, usually round (foramen magnum of the skull)
Fossa	A shallow, broad, or elongated basin (infraspinous fossa of the scapula)
Line (linea)	A raised, elongated ridge (nuchal lines of the skull)
Meatus	A canal (external acoustic meatus of the temporal bone)
Process	Any bony prominence (mastoid process of the skull)
Protuberance	A bony outgrowth or protruding part (mental protuberance of the chin)
Sinus	A cavity within a bone (frontal sinus of the skull)
Spine	A sharp, slender, or narrow process (spine of the scapula)
Sulcus	A groove for a tendon, nerve, or blood vessel (intertubercular sulcus of the humerus)
Tubercle	A small, rounded process (greater tubercle of the humerus)
Tuberosity	A rough surface (tibial tuberosity)


Lines
Crest
Sinuses
Foramen
Meatus
Process
Condyle
Spine
Alveolus
Foramen
Process
Spine
Fossae
Fovea
Head
Trochanters
Crest
Line
Epicondyles
Condyles
Head
Tubercle
Tuberosity
Fossae

(a) Skull (lateral view)

(b) Scapula (posterior view)

(c) Femur (posterior view)

(d) Humerus (anterior view)

Figure 7.2 **Anatomical Features of Bones.** Most of these also occur on many other bones of the body.

7.2 The Skull

Expected Learning Outcomes

When you have completed this section, you should be able to

a. distinguish between cranial bones and facial bones;
b. name the bones of the skull and identify the anatomical features of each;
c. identify the cavities within the skull and in some of its individual bones;
d. name the principal sutures that join bones of the skull;
e. describe some bones that are closely associated with the skull; and
f. describe some adaptations of the skull for upright locomotion.

The skull is the most complex part of the skeleton. Figures 7.3 through 7.6 present an overview of its general anatomy. Although the skull may seem to consist of only the mandible (lower jaw) and "the rest," it is composed of 22 bones and sometimes more. Most of them are rigidly joined by **sutures** (SOO-chures), joints that appear as seams on the cranial surface (fig. 7.4). These are important landmarks in the descriptions that follow.

The skull contains several prominent cavities (fig. 7.7). The largest, with an adult volume of about 1,300 mL, is the **cranial cavity,** which encloses the brain. Other cavities include the **orbits** (eye sockets), **nasal cavity, paranasal sinuses, oral cavity** (mouth or buccal cavity), and **middle-** and **inner-ear cavities.** The paranasal sinuses are named for the bones in which they occur (fig. 7.8)—the **frontal, ethmoid, sphenoid,** and **maxillary sinuses.** These sinuses are connected with the nasal cavity, lined by a mucous membrane, and filled with air. They lighten the anterior portion of the skull and act as chambers that add resonance to the voice.

Bones of the skull have especially conspicuous **foramina**—singular, *foramen* (fo-RAY-men)—holes that allow passage for nerves and blood vessels. The major foramina are summarized in table 7.3. The details of this table will mean more to you when you study cranial nerves and blood vessels in later chapters.

Cranial Bones

Cranial bones are those that enclose the brain; collectively, they compose the **cranium**[3] (braincase). The delicate brain tissue does not come directly into contact with the cranial bones, but is separated from them by three membranes called the *meninges* (meh-NIN-jeez) (see chapter 15). The thickest and toughest of these, the *dura mater*[4] (DUE-rah MAH-tur), lies loosely against the inside of the cranium in most places but is firmly attached to it at a few points.

The cranium is a rigid structure with an opening, the *foramen magnum* (literally "big hole"), where the spinal cord meets the brain. The cranium consists of two major parts—the calvaria and the base. The **calvaria**[5] (skullcap) is not a specific bone but simply the dome of the top of the head, composed of parts of multiple bones (see fig. 7.6).

---

[3] *crani* = helmet
[4] *dura* = tough, strong; *mater* = mother
[5] *calvar* = bald, skull

(Text continues on p. 159)


Key
Ethmoid b.
Frontal b.
Mandible
Maxilla
Nasal b.
Parietal b.
Sphenoid b.
Temporal b.
Vomer
Zygomatic b.
Frontal bone
Glabella
Coronal suture
Squamous suture
Sphenoid bone
Lacrimal bone
Nasal bone
Middle nasal concha
Inferior nasal concha
Vomer
Mandible
Mental protuberance
Supraorbital foramen
Parietal bone
Supraorbital margin
Temporal bone
Ethmoid bone
Zygomatic bone
Infraorbital foramen
Intermaxillary suture
Maxilla
Mental foramen

Figure 7.3 The Skull (Anterior View). APR


Parietal bone
Lambdoid suture
Sphenoid bone
Occipital bone
Squamous suture
Temporal bone
Zygomatic process
External acoustic meatus
Mastoid process
Styloid process
Mandibular condyle
Coronal suture
Frontal bone
Temporal lines
Ethmoid bone
Nasal bone
Lacrimal bone
Zygomaticofacial foramen
Infraorbital foramen
Zygomatic bone
Maxilla
Temporal process
Mandible
Mental foramen

(a) Right lateral view


Parietal bone
Squamous suture
Occipital bone
Temporal bone
Sella turcica
Lambdoid suture
Internal acoustic meatus
Jugular foramen
Hypoglossal canal
Coronal suture
Frontal bone
Sphenoid sinus
Frontal sinus
Crista galli
Cribriform plate of ethmoid bone
Perpendicular plate of ethmoid bone
Nasal bone
Vomer
Palatine process of maxilla
Maxilla
Palatine bone
Mandible
Mental spines
Key
Ethmoid b.
Maxilla
Sphenoid b.
Frontal b.
Nasal b.
Temporal b.
Lacrimal b.
Occipital b.
Vomer
Mandible
Parietal b.
Zygomatic b.

(b) Median section

Figure 7.4 The Skull (Lateral Surface and Median Section). AP|R


Incisive foramen
Zygomatic bone
Zygomatic arch
Posterior nasal aperture
Vomer
Sphenoid bone
Mandibular fossa
Styloid process
External acoustic meatus
Occipital condyle
Mastoid process
Mastoid notch
Temporal bone
Condylar canal
Parietal bone
Inferior nuchal line
Superior nuchal line
Occipital bone
Palatine process of maxilla
Intermaxillary suture
Palatine bone
Greater palatine foramen
Medial pterygoid plate
Lateral pterygoid plate
Foramen ovale
Foramen spinosum
Foramen lacerum
Basilar part of occipital bone
Carotid canal
Stylomastoid foramen
Jugular foramen
Foramen magnum
Mastoid foramen
Lambdoid suture
External occipital protuberance

(a) Inferior view


Diploe (spongy bone)
Crista galli
Cribriform foramina
Optic canal
Foramen rotundum
Foramen ovale
Foramen spinosum
Internal acoustic meatus
Jugular foramen
Groove for venous sinus
Hypoglossal canal
Occipital bone
Frontal bone
Cribriform plate of ethmoid bone
Sphenoid bone
Sella turcica
Temporal bone
Petrous part of temporal bone
Parietal bone
Key
Ethmoid b.
Parietal b.
Frontal b.
Sphenoid b.
Maxilla
Temporal b.
Occipital b.
Vomer
Palatine b.
Zygomatic b.

(b) Superior view of cranial floor

Figure 7.5 The Base of the Skull. AP|R


Anterior
Frontal bone
Coronal suture
Parietal bone
Sagittal suture
Sutural bone
Parietal foramen
Lambdoid suture
Occipital bone
Posterior

Figure 7.6 The Calvaria, Superior View. AP|R


Cranial cavity
Frontal bone
Ethmoid bone
Nasal conchae
Superior
Middle
Inferior
Vomer
Mandible
Ethmoid air cells
Orbit
Zygomatic bone
Maxilla
Maxillary sinus
Nasal cavity
Oral cavity

Figure 7.7 Major Cavities of the Skull, Frontal Section.

- *What is the function of the nasal conchae?*


Sphenoid sinus
Frontal sinus
Ethmoid sinus
Maxillary sinus

Figure 7.8 The Paranasal Sinuses.

- *If these sinuses did not exist, it would require significantly more effort to hold the head erect. Explain.*

TABLE 7.3 Foramina of the Skull and the Nerves and Blood Vessels Transmitted Through Them

Bones	Foramina*	Structures Transmitted
Frontal bone	Supraorbital foramen or notch	Supraorbital nerve, artery, and vein; ophthalmic nerve
Parietal bone	Parietal foramen	Emissary vein of superior sagittal sinus
Temporal bone	Carotid canal	Internal carotid artery
	External acoustic meatus	Sound waves to eardrum
	Internal acoustic meatus	Vestibulocochlear and facial nerves; internal auditory vessels
	Stylomastoid foramen	Facial nerve
	Mastoid foramen	Meningeal artery; vein from sigmoid sinus
Temporal–occipital region	Jugular foramen	Internal jugular vein; glossopharyngeal, vagus, and accessory nerves
Temporal–occipital–sphenoid region	Foramen lacerum	No major nerves or vessels; closed by cartilage
Occipital bone	Foramen magnum	Spinal cord; accessory nerve; vertebral arteries
	Hypoglossal canal	Hypoglossal nerve to muscles of tongue
	Condylar canal	Vein from transverse sinus
Sphenoid bone	Foramen ovale	Mandibular division of trigeminal nerve; accessory meningeal artery
	Foramen rotundum	Maxillary division of trigeminal nerve
	Foramen spinosum	Middle meningeal artery; spinosal nerve; part of trigeminal nerve
	Optic canal	Optic nerve; ophthalmic artery
	Superior orbital fissure	Oculomotor, trochlear, and abducens nerves; ophthalmic division of trigeminal nerve; ophthalmic veins
Ethmoid bone	Olfactory foramina	Olfactory nerves
Maxilla	Infraorbital foramen	Infraorbital nerve and vessels
	Incisive foramen	Nasopalatine nerves
Maxilla–sphenoid region	Inferior orbital fissure	Infraorbital nerve; zygomatic nerve; infraorbital vessels
Lacrimal bone	Lacrimal foramen	Tear duct leading to nasal cavity
Palatine bone	Greater palatine foramen	Palatine nerves
Zygomatic bone	Zygomaticofacial foramen	Zygomaticofacial nerve
	Zygomaticotemporal foramen	Zygomaticotemporal nerve
Mandible	Mental foramen	Mental nerve and vessels
	Mandibular foramen	Inferior alveolar nerves and vessels to the lower teeth

*When two or more bones are listed together (for example, temporal–occipital), it indicates that the foramen passes between them.

In study skulls, it is often sawed so that the top can be lifted off for examination of the interior. This reveals the **base** (floor) of the cranial cavity (see fig. 7.5b), which exhibits three depressions called **cranial fossae.** These correspond to the contour of the inferior surface of the brain (fig. 7.9). The relatively shallow **anterior cranial fossa** is crescent-shaped and accommodates the frontal lobes of the brain. The **middle cranial fossa,** which drops abruptly deeper, is shaped like a pair of outstretched bird wings and accommodates the temporal lobes. The **posterior cranial fossa** is deepest and houses a large posterior division of the brain called the cerebellum.

There are eight cranial bones:

1 frontal bone	1 occipital bone
2 parietal bones	1 sphenoid bone
2 temporal bones	1 ethmoid bone

Frontal Bone

The **frontal bone** extends from the forehead back to a prominent *coronal suture,* which crosses the crown of the head from right to left and joins the frontal bone to the parietal bones (see figs. 7.3 and 7.4). The frontal bone forms the anterior wall and about one-third of the roof of



(a) Superior view **(b) Lateral view**

Figure 7.9 **Cranial Fossae.** The three fossae conform to the contours of the base of the brain.

the cranial cavity, and it turns inward to form nearly all of the anterior cranial fossa and the roof of the orbit. Deep to the eyebrows it has a ridge called the **supraorbital margin.** The center of each margin is perforated by a single **supraorbital foramen** (see figs. 7.3 and 7.14), which provides passage for a nerve, artery, and vein. In some people, the edge of this foramen breaks through the margin of the orbit and forms a *supraorbital notch.* The smooth area of the frontal bone just above the root of the nose is called the **glabella.**[6] The frontal bone also contains the frontal sinus, but you may not see this on all study skulls. On some skulls, the calvaria is cut too high to show it, and some people simply do not have one. Along the cut edge of the calvaria, you can also see the *diploe* (DIP-lo-ee)—the layer of spongy bone in the middle of the cranial bones (see fig. 7.5b).

Parietal Bones

The right and left **parietal** (pa-RYE-eh-tul) **bones** form most of the cranial roof and part of its walls (see figs. 7.4 and 7.6). Each is bordered by four sutures that join it to the neighboring bones: (1) the **sagittal suture** between the parietal bones; (2) the **coronal**[7] **suture** at the anterior margin; (3) the **lambdoid**[8] (LAM-doyd) **suture** at the posterior margin; and (4) the **squamous suture** laterally. Small sutural (wormian) bones are often seen along the sagittal and lambdoid sutures, like little islands of bone with the suture lines passing around them. Internally, the parietal and frontal bones have markings that look a bit like aerial photographs of river tributaries (see fig. 7.4b). These represent places where the bone has been molded around blood vessels of the meninges.

Externally, the parietal bones have few features. A **parietal foramen** sometimes occurs near the corner of the lambdoid and sagittal sutures (see fig. 7.6). A pair of slight thickenings, the superior and inferior **temporal lines,** forms an arc across the parietal and frontal bones (see fig. 7.4a). The temporal lines mark the attachment of the large, fan-shaped *temporalis muscle,* a chewing muscle that inserts on the mandible (see fig. 11.6a, p. 274).

Temporal Bones

If you palpate your skull just above and anterior to the ear—that is, the temporal region—you can feel the **temporal bone,** which forms the lower wall and part of the floor of the cranial cavity (fig. 7.10). The temporal bone derives its name from the fact that people often develop their first gray hairs on the temples with the passage of time.[9] The relatively complex shape of the temporal bone is best understood by dividing it into four parts:

1. The **squamous**[10] **part** (which you just palpated) is relatively flat and vertical. It is encircled by the squamous suture. It bears two prominent features: (a) the **zygomatic process,** which extends anteriorly to form part of the **zygomatic arch** (cheekbone); and (b) the **mandibular fossa,** a depression where the mandible articulates with the cranium.
2. The **tympanic**[11] **part** is a small plate of bone that borders the opening of the **external acoustic meatus** (me-AY-tus), the ear canal. It has a pointed spine on its inferior surface, the **styloid process**, named for its resemblance to the stylus used by ancient Greeks and Romans to write on wax tablets. The styloid process provides attachment for muscles of the tongue, pharynx, and hyoid bone.

---

[6] *glab* = smooth
[7] *corona* = crown
[8] *lambd* = the Greek letter lambda (λ); *oid* = resembling
[9] *tempor* = time
[10] *squam* = flat; *ous* = characterized by
[11] *tympan* = drum (eardrum); *ic* = pertaining to



(a) Lateral surface



(b) Medial surface

Figure 7.10 **The Right Temporal Bone.** The lateral surface faces the scalp and external ear; the medial surface faces the brain. AP|R

3. The **mastoid**[12] **part** lies posterior to the tympanic part. It bears a heavy **mastoid process,** which you can palpate as a prominent lump behind the earlobe. It is filled with small air sinuses that communicate with the middle-ear cavity. These sinuses are subject to infection and inflammation (mastoiditis), which can erode the bone and spread to the brain. Inferiorly, there is a groove called the **mastoid notch** medial to the mastoid process (see fig. 7.5a). It is the origin of the *digastric muscle,* a muscle that opens the mouth. The notch is perforated by the **stylomastoid foramen** at its anterior end and the **mastoid foramen** at its posterior end.
4. The **petrous**[13] **part** can be seen in the cranial floor, where it resembles a little mountain range separating the middle cranial fossa from the posterior fossa (see figs. 7.5b and 7.10b). It houses the middle- and inner-ear cavities. The **internal acoustic meatus** opens on its posteromedial surface; this canal is the passage for the *vestibulocochlear* (vess-TIB-you-lo-COC-lee-ur) *nerve,* which carries sensations of hearing and balance from the inner ear to the brain. On the inferior surface of the petrous part are two prominent foramina named for the major blood vessels that pass through them (see fig. 7.5a): (1) The **carotid canal** is a passage for the internal carotid artery, a major blood supply to the brain. This artery is so close to the inner ear that you may be able to hear the pulsing of its blood when your ear is resting on a pillow or your heart is beating hard. (2) The **jugular foramen** is a large, irregular opening just medial to the styloid process, between the temporal and occipital bones. Blood from the brain drains through this foramen into the internal jugular vein of the neck. Three cranial nerves also pass through this foramen.

Occipital Bone

The **occipital** (oc-SIP-ih-tul) **bone** forms the rear of the skull *(occiput)* and much of its base (see fig. 7.5). Its most conspicuous feature is the **foramen magnum,** where the spinal cord meets the brainstem. An important consideration in head injuries is swelling of the brain. Since the cranium cannot enlarge, swelling puts pressure on the brain and results in even more tissue damage. Severe swelling may force the brainstem out through the foramen magnum, usually with fatal consequences.

The occipital bone continues anterior to this as a thick median plate, the **basilar part.** On each side of the foramen magnum is a smooth knob called the **occipital condyle** (CON-dile), where the skull rests on the vertebral column. Passing like a tunnel beneath each condyle is a **hypoglossal**[14] **canal,** named for the *hypoglossal nerve* that passes through it to innervate the muscles of the tongue. In some people, a **condylar** (CON-dih-lur) **canal** occurs posterior to each occipital condyle.

Internally, the occipital bone displays impressions left by large venous sinuses that drain blood from the brain (see fig. 7.5b). One of these grooves travels along the midsagittal line. Just before reaching the foramen magnum, it branches into right and left grooves that wrap around the occipital bone like outstretched arms, approaching each ear before terminating at the jugular foramina. The sinuses that occupy these grooves are described in table 21.3 (p. 579).

Other features of the occipital bone can be palpated on the back of your head. One is a prominent median bump called the **external occipital protuberance**—the attachment for the **nuchal**[15] (NEW-kul) **ligament,** which binds the skull to the vertebral column. A ridge, the **superior nuchal line,** can be traced horizontally from this protuberance toward the mastoid process (see fig. 7.5a). It defines the superior limit of the neck and provides attachment for several neck and back muscles to the skull. It forms the boundary where, in palpating the upper neck, you feel the transition from muscle to bone. By pulling down on the occipital bone, some of these muscles help to keep the head erect. The deeper **inferior nuchal line** provides attachment for some of the deep neck muscles. This inconspicuous ridge cannot be palpated on the living body but is visible on an isolated skull.

---

[12] *mast* = breast; *oid* = resembling
[13] *petr* = stone, rock; *ous* = like
[14] *hypo* = below; *gloss* = tongue
[15] *nucha* = back of the neck

Sphenoid Bone

The **sphenoid**[16] (SFEE-noyd) **bone** has a complex shape with a thick median **body** and outstretched **greater** and **lesser wings,** which give the bone as a whole a ragged mothlike shape. Most of it is best seen from the superior perspective (fig. 7.11a). In this view, the lesser wings form the posterior margin of the anterior cranial fossa and end at a sharp bony crest, where the sphenoid drops abruptly to the greater wings. The greater wings form about half of the middle cranial fossa (the temporal bone forming the rest) and are perforated by several foramina, to be discussed shortly.

The greater wing forms part of the lateral surface of the cranium just anterior to the temporal bone (see fig. 7.4a). The lesser wing forms the posterior wall of the orbit and contains the **optic canal,** which permits passage of the optic nerve and ophthalmic artery (see fig. 7.14). Superiorly, a pair of bony spines of the lesser wing called the **anterior clinoid processes** appears to guard the optic foramina. A gash in the posterior wall of the orbit, the **superior orbital fissure,** angles upward lateral to the optic canal. It serves as a passage for three nerves that supply the muscles of eye movement.

The body of the sphenoid bone contains a pair of sphenoid sinuses and has a saddlelike surface feature named the **sella turcica**[17] (SEL-la TUR-sih-ca). The sella turcica consists of a deep pit called the *hypophyseal fossa,* which houses the pituitary gland (hypophysis); a raised anterior margin called the *tuberculum sellae* (too-BUR-cu-lum SEL-lee); and a posterior margin called the *dorsum sellae.* In life, the dura mater stretches over the sella turcica and attaches to the anterior clinoid processes. A stalk penetrates the dura to connect the pituitary gland to the floor of the brain.

Lateral to the sella turcica, the sphenoid is perforated by several foramina (see fig. 7.5). The **foramen rotundum** and **foramen ovale** (oh-VAY-lee) are passages for two branches of the trigeminal nerve. The **foramen spinosum,** about the diameter of a pencil lead, provides passage for an artery of the meninges. An irregular gash called the **foramen lacerum**[18] (LASS-eh-rum) occurs at the junction of the sphenoid, temporal, and occipital bones. It is filled with cartilage in life and transmits no major vessels or nerves.

In an inferior view of the skull, the sphenoid can be seen just anterior to the basilar part of the occipital bone (see fig. 7.5a). The internal openings of the nasal cavity seen here are called the **posterior nasal apertures,** or **choanae**[19] (co-AH-nee). Lateral to each aperture, the sphenoid bone exhibits a pair of parallel plates—the **medial** and **lateral pterygoid**[20] (TERR-ih-goyd) **plates.** Each plate has a narrow inferior extension called the *pterygoid process* (see fig. 7.5a). The plates provide attachment for some of the chewing muscles.

Ethmoid Bone

The **ethmoid**[21] (ETH-moyd) bone is an anterior cranial bone located between the eyes (fig. 7.12). It contributes to the medial wall of the orbit, the roof and walls of the nasal cavity, and the

---

[16] *sphen* = wedge; *oid* = resembling
[17] *sella* = saddle; *turcica* = Turkish
[18] *lacerum* = torn, lacerated
[19] *choana* = funnel
[20] *pterygo* = wing
[21] *ethmo* = sieve, strainer; *oid* = resembling



(a) Superior view



(b) Posterior view

Figure 7.11 The Sphenoid Bone. APR


Cribriform plate
Cribriform foramina
Orbital plate
Ethmoid air cells
Perpendicular plate
Crista galli
Superior nasal concha
Middle nasal concha

Figure 7.12 The Ethmoid Bone, Anterior View. AP|R

nasal septum. It is a very porous and delicate bone, with three major portions:

1. The vertical **perpendicular plate,** a thin median plate that forms the superior two-thirds of the nasal septum (see fig. 7.4b). (The lower part is formed by cartilages and the vomer, discussed later.) The septum divides the nasal cavity into right and left air spaces called the **nasal fossae** (FOSS-ee). The septum is often curved, or deviated, toward one nasal fossa or the other.
2. A horizontal **cribriform**[22] (CRIB-rih-form) **plate,** which forms the roof of the nasal cavity. This plate has a median crest called the **crista galli**[23] (GAL-eye), an attachment point for the dura mater. On each side of the crista is an elongated depressed area perforated with numerous holes, the **cribriform (olfactory) foramina.** A pair of *olfactory bulbs* of the brain, concerned with the sense of smell, rests in these depressions, and the foramina allow passage for olfactory nerves from the nasal cavity to the bulbs (see Deeper Insight 7.1).
3. The **labyrinth,** a large mass on each side of the perpendicular plate. The labyrinth is named for the fact that internally, it has a maze of air spaces called the **ethmoidal cells.** Collectively, these constitute the *ethmoid sinus* discussed earlier. The lateral surface of the labyrinth is a smooth, slightly concave **orbital plate** seen on the medial wall of the orbit (see fig. 7.14). The medial surface of the labyrinth gives rise to two curled, scroll-like plates of bone called the **superior** and **middle nasal conchae**[24] (CON-kee), or **turbinates.** These project into the nasal fossa from its lateral wall toward the septum (see figs. 7.7 and 7.13). There is also a separate *inferior nasal concha,* discussed later. The three conchae occupy most of the space in the nasal cavity.

---

[22] *cribri* = sieve; *form* = in the shape of
[23] *crista* = crest; *galli* = of a rooster
[24] *conchae* = conchs (large marine snails)


Ethmoid bone:
Crista galli
Cribriform plate
Cribriform foramina
Sella turcica
Sphenoid sinus
Occipital bone
Sphenoid bone
Palatine bone
Lacrimal bone
Maxilla
Frontal bone
Frontal sinus
Nasal bone
Nasal conchae:
Superior
Middle
Inferior
Nasal cartilages
Anterior nasal spine
Incisive foramen
Lip
Incisor
Key
Cartilage
Ethmoid b.
Frontal b.
Inferior nasal concha
Maxilla
Nasal b.
Occipital b.
Sphenoid b.

Figure 7.13 The Left Nasal Fossa (Sagittal Section with Nasal Septum Removed). AP|R

DEEPER INSIGHT 7.1

Injury to the Ethmoid Bone

The ethmoid bone is very delicate and easily injured by a sharp upward blow to the nose, such as a person might suffer by striking an automobile dashboard in a collision. The force of a blow can drive bone fragments through the cribriform plate into the meninges or brain tissue. Such injuries are often evidenced by leakage of cerebrospinal fluid into the nasal cavity, and may be followed by the spread of infection from the nasal cavity to the brain. Blows to the head can also shear off the olfactory nerves that pass through the ethmoid bone and cause *anosmia*, an irreversible loss of the sense of smell and a great reduction in the sense of taste (most of which depends on smell). This not only deprives life of some of its pleasures, but can also be dangerous, as when a person fails to smell smoke, gas, or spoiled food.

> By filling space and creating turbulence in the flow of inhaled air, they ensure that the air contacts the mucous membranes that cover these bones, which cleanses, humidifies, and warms the inhaled air before it reaches the lungs. The superior concha and adjacent part of the nasal septum also bear the sensory cells of smell.

Usually, all that can be seen of the ethmoid is the perpendicular plate, by looking into the nasal cavity (see fig. 7.3); the orbital plate, by looking at the medial wall of the orbit (fig. 7.14); and the crista galli and cribriform plate, viewed from within the cranial cavity (see fig. 7.5b).

Facial Bones

Facial bones do not enclose the brain but lie anterior to the cranial cavity. They support the orbital, nasal, and oral cavities; give shape to the face; and provide attachment for the muscles of facial expression and mastication. There are 14 facial bones:

2 maxillae
2 palatine bones
2 zygomatic bones
2 lacrimal bones
2 nasal bones
2 inferior nasal conchae
1 vomer
1 mandible

Maxillae

The **maxillae** (mac-SILL-ee) are the largest facial bones. They form the upper jaw and meet each other at a median **intermaxillary suture** (see figs. 7.3, 7.4a, and 7.5a). Small points of maxillary bone called **alveolar processes** grow into the spaces between the bases of the teeth. The root of each tooth is inserted into a deep socket, or **alveolus.** Even though the teeth are preserved with the skull, they are not bones. They are discussed in detail in chapter 24.

Each maxilla extends from the teeth upward to the inferomedial wall of the orbit. Just below the orbit, it exhibits an **infraorbital foramen,** which provides passage for a blood vessel to the face and a nerve that receives sensations from the nasal region and cheek. This nerve emerges through the foramen rotundum into the cranial cavity. The maxilla forms part of the floor of the orbit, where it exhibits a gash called the **inferior orbital fissure** that angles downward and medially (fig. 7.14). The inferior and superior orbital fissures form a sideways V whose apex lies near the optic canal. The inferior orbital fissure is a passage for blood vessels and sensory nerves from the face.

The **palate** forms the roof of the mouth and floor of the nasal cavity. It consists of a bony **hard palate** in front and a fleshy **soft palate** in the rear. Most of the hard palate is formed by horizontal extensions of the maxillae called **palatine** (PAL-uh-tine) **processes** (see fig. 7.5a). Just behind the incisors (front teeth) is a pair of **incisive foramina.** The palatine processes normally meet at the intermaxillary suture at about 12 weeks of fetal development. Failure to join causes cleft palate (see table 7.5, p. 179).


Supraorbital foramen
Roof of orbit
Orbital plate of frontal bone
Lesser wing of sphenoid bone
Optic canal
Medial wall
Orbital plate of ethmoid bone
Lacrimal bone
Frontal process of maxilla
Floor of orbit
Orbital process of palatine bone
Orbital surface of maxilla
Temporal bone
Zygomatic process of frontal bone
Greater wing of sphenoid bone
Orbital surface of zygomatic bone
Lateral wall of orbit
Superior orbital fissure
Inferior orbital fissure
Infraorbital foramen
Key
Ethmoid b.
Lacrimal b.
Sphenoid b.
Zygomatic b.
Frontal b.
Maxilla
Temporal b.

Figure 7.14 The Left Orbit (Anterior View). APR

DEEPER INSIGHT 7.2

Evolutionary Significance of the Palate

In most vertebrates, the nasal passages open into the oral cavity. Mammals, by contrast, have a palate that separates the nasal and oral cavities. In order to maintain our high metabolic rate, we must digest our food rapidly; in order to do this, we chew it thoroughly to break it up into small, easily digested particles before swallowing it. We would be unable to breathe freely during this prolonged chewing if we lacked a palate to separate the airflow from the oral cavity.

Palatine Bones

The **palatine bones** are located in the posterior nasal cavity (fig. 7.13). Each one has an L shape formed by a *horizontal plate* and a *perpendicular plate.* The horizontal plates form the posterior one-third of the bony palate (see fig. 7.5a). Each is marked by a large **greater palatine foramen,** a nerve passage to the palate. The perpendicular plate is a thin, delicate, irregularly shaped plate that forms part of the wall between the nasal cavity and the orbit (see fig. 7.12).

Zygomatic Bones

The **zygomatic**[25] **bones**, colloquially called the cheekbones, form the angles of the cheeks inferolateral to the eyes and part of the lateral wall of each orbit; they extend about halfway to the ear (see figs. 7.4a and 7.5a). Each zygomatic bone has an inverted T shape and usually a small **zygomaticofacial** (ZY-go-MAT-ih-co-FAY-shul) **foramen** near the intersection of the stem and crossbar of the T. The prominent zygomatic arch that flares from each side of the skull is formed by the union of the zygomatic bone, temporal bone, and maxilla.

Lacrimal Bones

The **lacrimal**[26] (LACK-rih-mul) **bones** form part of the medial wall of each orbit (fig. 7.14). These are the smallest bones of the skull, about the size of a small fingernail. A depression called the **lacrimal fossa** houses a membranous *lacrimal sac* in life. Tears from the eye collect in this sac and drain into the nasal cavity.

Nasal Bones

Two small rectangular **nasal bones** form the bridge of the nose (see fig. 7.3) and support cartilages that shape the lower portion of the nose. They are only slightly larger than the lacrimal bones. If you palpate the bridge, you can easily feel where the nasal bones end and the cartilages begin. The nasal bones are often fractured by blows to the nose.

Inferior Nasal Conchae

There are three conchae in the nasal cavity. The superior and middle conchae, as discussed earlier, are parts of the ethmoid bone. The **inferior nasal concha**—the largest of the three—is a separate bone (fig. 7.13).

Vomer

The **vomer** forms the inferior portion of the nasal septum (see figs. 7.3 and 7.4b). Its name literally means "plowshare," which refers to its resemblance to the blade of a plow. The superior half of the nasal septum is formed by the perpendicular plate of the ethmoid bone, as mentioned earlier. The vomer and perpendicular plate support a wall of *septal cartilage* that forms most of the anterior part of the septum.

Mandible

The **mandible** (fig. 7.15) is the strongest bone of the skull and the only one that can move significantly. It supports the lower teeth and provides attachment for muscles of mastication and facial expression. The horizontal portion, bearing the teeth, is called the **body;** the vertical to oblique posterior portion is the **ramus** (RAY-mus)—plural, *rami* (RAY-my); and these two portions meet at a corner called the **angle.** The point of the chin is the **mental protuberance.** The inner (posterior) surface of the mandible in this region has a pair of small points, the **mental spines,** which serve for attachment of certain chin muscles (see fig. 7.4b). On the anterolateral surface of the body, the **mental foramen** permits the passage of nerves and blood vessels of the chin. The inner surface of the body has a number of shallow depressions and ridges to accommodate muscles and salivary glands. The angle of the mandible has a rough lateral surface for insertion of the *masseter,* a muscle of mastication. Like the maxilla, the mandible has pointed alveolar processes between the teeth.

The ramus is somewhat Y-shaped. Its posterior branch, called the **condylar** (CON-dih-lur) **process,** bears the **mandibular condyle**—an oval knob that articulates with the mandibular fossa of the temporal bone. This articulation is the jaw joint, or **temporomandibular joint (TMJ).** The anterior branch of the ramus is a blade called the **coronoid process.** It serves for insertion for the temporalis muscle, which pulls the mandible upward when you bite. The U-shaped arch between the two processes is called the **mandibular notch.** Just below the notch, on the medial surface of the ramus, is the **mandibular foramen,** a passage for a nerve and blood vessels that enter the bone here to reach the lower teeth (see fig. 7.4b).



Figure 7.15 The Mandible. APR

---

[25] *zygo* = to join, unite
[26] *lacrim* = tear, to cry



Figure 7.16 **The Hyoid Bone.**
• *Why would a fractured hyoid bone be a common finding in strangulation cases?*

Bones Associated with the Skull

Seven bones are closely associated with the skull but not considered part of it. These are the three auditory ossicles in each middle-ear cavity and the hyoid bone beneath the chin. The **auditory ossicles**[27]—named the **malleus** (hammer), **incus** (anvil), and **stapes** (STAY-peez) (stirrup)—are discussed in connection with hearing in chapter 17. The **hyoid**[28] **bone** is a slender U-shaped bone between the chin and larynx (fig. 7.16). It is one of the few bones that does not articulate with any other. The hyoid is suspended from the styloid processes of the skull, somewhat like a hammock, by the small *stylohyoid muscles* and *stylohyoid ligaments.* The medial **body** of the hyoid is flanked on either side by projections called the **greater** and **lesser horns.** The larynx (voice box) is suspended from the hyoid bone by a broad ligament (see fig. 23.4, p. 636), and the hyoid serves also for attachment of several muscles that control the larynx, mandible, and tongue. Forensic pathologists look for a fractured hyoid as evidence of strangulation.

Adaptations of the Skull for Bipedalism

Some mammals can stand, hop, or walk briefly on their hind legs, but humans are the only mammals that are habitually bipedal. Efficient bipedal locomotion is possible only because of several adaptations of the feet, legs, vertebral column, and skull. The human head is balanced on the vertebral column with the gaze directed forward. This was made possible in part by an evolutionary remodeling of the skull. The foramen magnum moved to a more inferior location in the course of human evolution, and the face is much flatter than an ape's face, so there is less weight anterior to the occipital condyles and the head has less tendency to tip forward (fig. 7.17).



Figure 7.17 **Adaptations of the Skull for Bipedalism.** Comparison of chimpanzee and human skulls. The foramen magnum is shifted rostrally and the face is flatter in humans. Thus, the skull is balanced on the vertebral column and the gaze is directed forward when a person is standing.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

4. Name the paranasal sinuses and state their locations. Name any four other cavities in the skull.
5. Explain the difference between a cranial bone and a facial bone. Give four examples of each.
6. Draw an oval representing a superior view of the calvaria. Draw lines representing the coronal, lambdoid, and sagittal sutures. Label the four bones separated by these sutures.
7. State which bone has each of these features: a squamous part, hypoglossal foramen, greater horn, greater wing, condylar process, and cribriform plate.
8. Palpate as many of the following structures as possible, and identify which ones cannot normally be palpated on a living person: the mastoid process, crista galli, superior orbital fissure, palatine processes, zygomatic bone, mental protuberance, and stapes.

---

[27] *os* = bone; *icle* = little
[28] *hy* = the letter *U; oid* = resembling

7.3 The Vertebral Column and Thoracic Cage

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the general features of the vertebral column and those of a typical vertebra;
b. describe the structure of the intervertebral discs and their relationship to the vertebrae;
c. describe the special features of vertebrae in different regions of the vertebral column, and discuss the functional significance of the regional differences;
d. relate the shape of the vertebral column to upright locomotion; and
e. describe the anatomy of the sternum and ribs and how the ribs articulate with the thoracic vertebrae.

General Features of the Vertebral Column

The **vertebral column (spine)** physically supports the skull and trunk, allows for their movement, protects the spinal cord, and absorbs stresses produced by walking, running, and lifting. It also provides attachment for the limbs, thoracic cage, and postural muscles. Although commonly called the backbone, it consists not of a single bone but a chain of 33 **vertebrae** with **intervertebral discs** of fibrocartilage between most of them. The adult vertebral column averages about 71 cm (28 in.) long, with the 23 intervertebral discs accounting for about one-quarter of the length. Most people are about 1% shorter when they go to bed at night than when they first rise in the morning. This is because during the day, the weight of the body compresses the intervertebral discs and squeezes water out of them. When one is sleeping, with the weight off the spine, the discs reabsorb water and swell.

As shown in figure 7.18, the vertebrae are divided into five groups: 7 *cervical* (SUR-vih-cul) *vertebrae* in the neck, 12 *thoracic vertebrae* in the chest, 5 *lumbar vertebrae* in the lower back, 5 *sacral vertebrae* at the base of the spine, and 4 tiny


Anterior view
Posterior view
Atlas (C1)
Axis (C2)
C7
T1
T12
L1
L5
S1
S5
Coccyx
Cervical vertebrae
Thoracic vertebrae
Lumbar vertebrae
Sacrum
Coccyx

Figure 7.18 The Vertebral Column. APR


C1
Cervical curvature
C7
T1
Thoracic curvature
T12
L1
Lumbar curvature
L5
S1
Pelvic curvature

Figure 7.19 Curvatures of the Adult Vertebral Column.

coccygeal (coc-SIDJ-ee-ul) *vertebrae.* All mammals have 7 cervical vertebrae—even the giraffe, with its fantastically long neck. To help remember the numbers of cervical, thoracic, and lumbar vertebrae—7, 12, and 5—you might think of a typical workday: Leave for work at 7, have lunch at 12, and go home at 5.

Variations in this arrangement occur in about 1 person in 20. For example, the last lumbar vertebra is sometimes incorporated into the sacrum, producing 4 lumbar and 6 sacral vertebrae. In other cases, the first sacral vertebra fails to fuse with the second, producing 6 lumbar and 4 sacral vertebrae. The cervical and thoracic vertebrae are more constant in number.

Beyond the age of 3 years, the vertebral column is slightly S-shaped, with four bends called the **cervical, thoracic, lumbar,** and **pelvic curvatures** (fig. 7.19). The thoracic and pelvic curvatures are called *primary curvatures* because they are present at birth, when the spine has a single C-shaped curvature. The cervical and lumbar curvatures are called *secondary curvatures* because they develop later, in the child's first few years of crawling and walking, as described later in this chapter. The resulting S shape makes sustained bipedal walking possible because the trunk of the body does not lean forward as it does in primates such as a chimpanzee; the head is balanced over the body's center of gravity; and the eyes are directed straight forward (fig. 7.20). Abnormal lateral or anterior–posterior spinal curvatures are among the most common back problems (see Deeper Insight 7.3).



Figure 7.20 **Comparison of Chimpanzee and Human Vertebral Columns.** The S-shaped human vertebral column is an adaptation for bipedal locomotion.

DEEPER INSIGHT 7.3

Abnormal Spinal Curvatures

Abnormal spinal curvatures (fig. 7.21) can result from abdominal weight gain in obesity or pregnancy; poor posture; weakness or paralysis of the trunk muscles; some diseases; or congenital defects in vertebral anatomy. The most common deformity is an abnormal lateral curvature called *scoliosis*. It occurs most often in the thoracic region, particularly among adolescent girls. It sometimes results from a developmental abnormality in which the body and arch of a vertebra fail to develop on one side. If the person's skeletal growth is not yet complete, scoliosis can be corrected with a back brace.

An exaggerated thoracic curvature is called *kyphosis* (hunchback, in lay language). It is usually a result of osteoporosis, but it also occurs in people with osteomalacia or spinal tuberculosis and in adolescents who engage heavily in such sports as wrestling and weight lifting. An exaggerated lumbar curvature is called *lordosis* (swayback). It can have the same causes as kyphosis, or it can result from added abdominal weight in pregnancy or obesity.



Figure 7.21 **Abnormal Spinal Curvatures.** (a) Scoliosis, an abnormal lateral deviation. (b) Kyphosis, an exaggerated thoracic curvature common in old age. (c) Lordosis, an exaggerated lumbar curvature common in pregnancy and obesity.

General Structure of a Vertebra

A representative vertebra and intervertebral disc are shown in figure 7.22. The most obvious feature of a vertebra is the **body,** or **centrum**—a mass of spongy bone and red bone marrow covered with a thin shell of compact bone. This is the weight-bearing portion of the vertebra. Its rough superior and inferior surfaces provide firm attachment for the intervertebral discs.

Apply What You Know

The lower we look on the vertebral column, the larger the vertebral bodies and intervertebral discs are. What is the functional significance of this trend?

Posterior to the body of each vertebra is an ovoid to triangular space called the **vertebral foramen.** Collectively, these foramina form the **vertebral canal,** a passage for the spinal cord. The foramen is bordered by a bony **vertebral arch** composed of two parts on each side, a pillarlike **pedicle**[29] and platelike **lamina.**[30] Extending from the apex of the arch, a projection called the **spinous process** is directed toward the rear and downward. You can see and feel the spinous processes as a row of bumps along the spine.



(a) 2nd lumbar vertebra (L2)



(b) Intervertebral disc

Figure 7.22 **A Representative Vertebra and Intervertebral Disc, Superior Views.** (a) A typical vertebra. (b) An intervertebral disc oriented the same way as the vertebral body in part (a) for comparison. (See figs. 7.23 and 7.25b for lateral views.)

A **transverse process** extends laterally from the point where the pedicle and lamina meet. The spinous and transverse processes provide points of attachment for spinal muscles and ligaments.

A pair of **superior articular processes** project upward from one vertebra and meet a similar pair of **inferior articular processes** that project downward from the vertebra above (fig. 7.23a). Each process has a flat articular surface (facet) facing that of the adjacent vertebra. These processes restrict twisting of the vertebral column, which could otherwise severely damage the spinal cord.

Where two vertebrae are joined, they exhibit an opening between their pedicles called the **intervertebral foramen.** This allows passage for spinal nerves that connect with the spinal cord at regular intervals. Each foramen is formed by an **inferior vertebral notch** in the pedicle of the superior vertebra and a **superior vertebral notch** in the pedicle of the one below it (fig. 7.23b).

Intervertebral Discs

An **intervertebral disc** is a cartilaginous pad located between the bodies of two adjacent vertebrae. It consists of an inner gelatinous **nucleus pulposus** surrounded by a ring of fibrocartilage called the **anulus fibrosus** (fig. 7.22). There are 23 discs—the first one between cervical vertebrae 2 and 3 and the last one between the last lumbar vertebra and the sacrum. The discs help to bind adjacent vertebrae together, enhance spinal flexibility, support the weight of the body, and absorb shock. Under stress—for example, when you lift a heavy weight—the discs bulge laterally. Excessive stress can cause a *herniated disc* (see p. 180).

Regional Characteristics of Vertebrae

We are now prepared to consider how vertebrae differ from one region of the vertebral column to another and from the generalized anatomy just described. Knowing these variations will enable you to identify the region of the spine from which an isolated vertebra was taken. More importantly, these modifications in form reflect functional differences among the vertebrae.

Cervical Vertebrae

The **cervical vertebrae (C1–C7)** are relatively small. Their function is to support the head and allow for its movements. The first two (C1 and C2) have unique structures for this purpose (fig. 7.24). Vertebra C1 is called the **atlas** because it supports the head in a manner reminiscent of Atlas, the giant of Greek mythology who was condemned by Zeus to carry the heavens on his shoulders. It scarcely resembles the typical vertebra; it has no body and is little more than a delicate ring surrounding a large vertebral foramen. On each side is a **lateral mass** with a deeply concave **superior articular facet,** which articulates with the occipital condyle of the skull. In nodding motions of the skull, as in gesturing "yes," the occipital condyles rock back and forth on these facets. The **inferior articular facets,** which are comparatively flat or only slightly concave, articulate with C2. The lateral masses are connected by an **anterior arch** and a **posterior arch,** which bear slight protuberances called the **anterior** and **posterior tubercle,** respectively.

---

[29] *ped* = foot; *icle* = little
[30] *lamina* = layer, plate


Transverse process
Body (centrum)
Intervertebral disc
Inferior articular process of L2
Superior articular process of L3
Lamina
L2
L3
L1
L2
L3
Superior articular process of L1
Inferior vertebral notch of L1
Intervertebral foramen
Superior vertebral notch of L2
Spinous process
Intervertebral disc
Inferior articular process of L3

(a) Posterior (dorsal) view **(b) Left lateral view**

Figure 7.23 **Articulated Vertebrae.**


Anterior tubercle
Anterior arch
Superior articular facet
Transverse foramen
Lateral masses
Posterior arch
Posterior tubercle
Dens (odontoid process)
Superior articular facet
Transverse foramen
Transverse process
Inferior articular process
Lamina
Spinous process
Pedicle
Body
Axis of rotation
Dens
Atlas
Transverse ligament
Axis

(a) Atlas

(b) Axis

(c) Atlantoaxial joint

Figure 7.24 **The Atlas and Axis, Cervical Vertebrae C1 and C2.** (a) The atlas, superior view. (b) The axis, posterosuperior view. (c) Articulation of the atlas and axis and rotation of the atlas. This movement turns the head from side to side, as in gesturing "no." Note the transverse ligament holding the dens of the axis in place.

- *What serious consequence could result if the transverse ligament was ruptured, allowing the dens to slip anteriorly?*

Vertebra C2, the **axis,** allows rotation of the head as in gesturing "no." Its most distinctive feature is a prominent anterior knob called the **dens** (pronounced "denz"), or **odontoid**[31] **process.** No other vertebra has a dens. It begins to form as an independent ossification center during the first year of life and fuses with the axis by the age of 3 to 6 years. It projects into the vertebral foramen of the atlas, where it is nestled in a facet and held in place by a **transverse ligament** (fig. 7.24c). A heavy blow to the top of the head can cause a fatal injury in which the dens is driven through the foramen magnum into the brainstem. The articulation between the atlas and the cranium is called the **atlanto–occipital joint;** the one between the atlas and axis is called the **atlantoaxial joint.**

The axis is the first vertebra that exhibits a spinous process. In vertebrae C2 through C6, the process is forked, or *bifid,*[32] at its tip

---

[31] *dens* = *odont* = tooth; *oid* = resembling

[32] *bifid* = cleft into two parts

(fig. 7.25a). This fork provides attachment for the *nuchal ligament* of the back of the neck. All seven cervical vertebrae have a prominent round **transverse foramen** in each transverse process. These foramina provide passage and protection for the *vertebral arteries,* which supply blood to the brain, and *vertebral veins,* which drain blood from various neck structures (but not from the brain). Transverse foramina occur in no other vertebrae and thus provide an easy means of recognizing a cervical vertebra.

Apply What You Know

How would head movements be affected if vertebrae C1 and C2 had the same structure as C3? What is the functional advantage of the lack of a spinous process in C1?

Cervical vertebrae C3 through C6 are similar to the typical vertebra described earlier, with the addition of the transverse foramina and bifid spinous processes. Vertebra C7 is a little different—its spinous process is not bifid, but it is especially long and forms a prominent bump on the lower back of the neck. C7 is sometimes called the *vertebra prominens* because of this especially conspicuous spinous process. This feature is a convenient landmark for counting vertebrae. One can easily identify the largest bump on the neck as C7, then count up or down from there to identify others.

Thoracic Vertebrae

There are 12 **thoracic vertebrae (T1–T12),** corresponding to the 12 pairs of ribs attached to them; no other vertebrae have ribs. One function of the thoracics is to support the thoracic cage enclosing the heart and lungs. They lack the transverse foramina and bifid


Superior views
Lateral views
Spinous process
Lamina
Superior articular facet
Transverse foramen
Transverse process
Body
Spinous process
Inferior articular process
(a) Cervical vertebrae
Spinous process
Lamina
Superior articular facet
Transverse process
Transverse costal facet
Superior costal facet
Inferior costal facet
Body
Transverse costal facet
Inferior articular facet
Spinous process
(b) Thoracic vertebrae
Spinous process
Superior articular facet
Superior articular process
Transverse process
Pedicle
Body
Spinous process
Inferior articular facet
(c) Lumbar vertebrae

Figure 7.25 **Typical Cervical, Thoracic, and Lumbar Vertebrae.** The left-hand figures are superior views, and the right-hand figures are left lateral views. AP|R

processes that distinguish the cervicals, but possess the following distinctive features of their own (fig. 7.25b):

- The spinous processes are relatively pointed and angle sharply downward.
- The body is somewhat heart-shaped and more massive than in the cervical vertebrae, but less than in the lumbar vertebrae.
- The body has small, smooth, slightly concave spots called *costal facets* for attachment of the ribs.
- Vertebrae T1 through T10 have a shallow, cuplike **transverse costal**[33] **facet** at the end of each transverse process. These provide a second point of articulation for ribs 1 through 10. There are no transverse costal facets on T11 and T12, and ribs 11 and 12 attach only to the bodies of the vertebrae.

Thoracic vertebrae vary among themselves mainly in the mode of articulation with the ribs. In most cases, a rib inserts between two vertebrae, so each vertebra contributes one-half of the articular surface—the rib articulates with the **inferior costal facet** of the upper vertebra and the **superior costal facet** of the vertebra below that (see fig. 7.29). This terminology may be a little confusing, but note that the facets are named for their position on the vertebral body, not for which part of the rib's articulation they provide. Vertebrae T1, T10, T11, and T12, however, have complete costal facets on the bodies for ribs 1 and 10 through 12, which articulate on the vertebral bodies instead of between vertebrae. These variations will be more functionally understandable after you have studied the anatomy of the ribs, so we will return then to the details of these articular surfaces.

Vertebra T12 differs in its articular processes from those above it. Its superior articular processes face posteriorly to meet the anteriorly facing inferior processes of T11, but the inferior articular processes of T12 face laterally like those of the lumbar vertebrae, described next. T12 thus represents a transition between the thoracic and lumbar pattern.

Lumbar Vertebrae

There are five **lumbar vertebrae (L1–L5).** Their most distinctive features are a thick, stout body adapted for bearing the weight of the upper body, and blunt, squarish spinous processes adapted for attachment of the strong, weight-bearing lumbar muscles (fig. 7.25c). In addition, their articular processes are oriented differently than those of other vertebrae. In thoracic vertebrae, the superior processes face posteriorly and the inferior processes face anteriorly. In lumbar vertebrae, the superior processes face medially (like the palms of your hands about to clap), and the inferior processes face laterally, toward the superior processes of the next vertebra. This arrangement resists twisting of the lower spine. These differences are best observed on an articulated (assembled) skeleton.

Sacral Vertebrae

The five **sacral vertebrae (S1–S5)** of a child begin to fuse around age 16, and by age 26 they are usually fused into a single bony plate, the **sacrum** (SACK-rum or SAY-krum) (fig. 7.26). The sacrum forms the posterior wall of the pelvic cavity and protects the organs within. It was named *sacrum* for its prominence as the largest and most durable bone of the vertebral column.[34]

The anterior surface of the sacrum is relatively smooth and concave and has four transverse lines that indicate where the five vertebrae have fused. This surface exhibits four pairs of large **anterior sacral (pelvic) foramina,** which allow for the passage of nerves and arteries to the pelvic organs. The posterior

---

[33] *costa* = rib; *al* = pertaining to

[34] *sacr* = great, prominent



(a) Anterior view

(b) Posterior view

Figure 7.26 **The Sacrum and Coccyx.** (a) The anterior surface, which faces the viscera of the pelvic cavity. (b) The posterior surface, whose surface features can be palpated in the sacral region. APR

surface of the sacrum is very rough. The spinous processes of the vertebrae fuse into a posterior ridge called the **median sacral crest.** The transverse processes fuse into a less prominent **lateral sacral crest** on each side of the median crest. Again on the posterior side of the sacrum, there are four pairs of openings for spinal nerves, the **posterior sacral foramina.** The nerves that emerge here supply the gluteal region and lower limbs.

A **sacral canal** runs through the sacrum and ends in an inferior opening called the **sacral hiatus** (hy-AY-tus). This canal contains spinal nerve roots in life. On each side of the sacrum is an ear-shaped **auricular**[35] (aw-RIC-you-lur) **surface.** This articulates with a similarly shaped surface on the hip bone and forms the strong, nearly immovable **sacroiliac (SI) joint** (SAY-cro-ILL-ee-ac). The body of vertebra S1 juts anteriorly to form a **sacral promontory,** which supports the body of vertebra L5. Lateral to the median sacral crest, S1 also has a pair of **superior articular processes** that articulate with L5. Lateral to these are a pair of large, rough, winglike extensions called the **alae**[36] (AIL-ee).

Coccygeal Vertebrae

Four (sometimes five) tiny **coccygeal vertebrae** (Co1 to Co4 or Co5) fuse by the age of 20 to form the **coccyx**[37] (fig. 7.26). The Roman anatomist Claudius Galen (c. 130–c. 200) named it this because he thought it resembled the beak of a cuckoo. It is colloquially called the tailbone and it is indeed the vestige of a tail, but it is not entirely useless; it provides attachment for muscles of the pelvic floor. Vertebra Co1 has a pair of **horns (cornua),** which serve as attachment points for ligaments that bind the coccyx to the sacrum. The coccyx can be fractured by a difficult childbirth or a hard fall on the buttocks.

The Thoracic Cage

The **thoracic cage** (fig. 7.27) consists of the thoracic vertebrae, sternum, and ribs. It forms a roughly conical enclosure for the lungs and heart and provides attachment for the pectoral girdle and upper limb. It has a broad base and a narrower superior apex. Its inferior border is the arc of the lower ribs, called the **costal margin.** The cage protects not only the thoracic organs but also the spleen, most of the liver, and to some extent the kidneys. Most important is its role in breathing; it is rhythmically expanded by the respiratory muscles to create a vacuum that draws air into the lungs, and then compressed to expel air.

The Sternum

The **sternum** (breastbone) is a bony plate anterior to the heart (fig. 7.27). It is subdivided into three regions: the *manubrium, body,* and *xiphoid process.* The **manubrium**[38] (ma-NOO-bree-um) is the broad superior portion, shaped like the knot in a necktie. It lies at the level of vertebrae T3 to T4. It has a median **suprasternal notch**

---

[35] *auri* = ear; *cul* = little; *ar* = pertaining to

[36] *alae* = wings

[37] *coccyx* = cuckoo (named for resemblance to a cuckoo's beak)

[38] *manubrium* = handle



Figure 7.27 The Thoracic Cage and Pectoral Girdle, Anterior View. APR

(jugular notch), which you can easily palpate between your clavicles (collarbones), and right and left **clavicular notches** where it articulates with the clavicles. The swordlike **body,** or **gladiolus,**[39] is the longest part of the sternum, lying at the level of vertebrae T5 through T9. It joins the manubrium at the **sternal angle,** which can be palpated as a transverse ridge at the point where the sternum projects farthest forward. In some people, however, the angle is rounded or concave. The second rib attaches here, making the sternal angle a useful landmark for counting ribs in a physical examination. The manubrium and body have scalloped lateral margins where cartilages of the ribs are attached. At the inferior end is a small, daggerlike **xiphoid**[40] (ZIF-oyd) **process** at the level of vertebrae T10 to T11. It provides attachment for some of the abdominal muscles. In cardiopulmonary resuscitation, improperly performed chest compression can drive the xiphoid process into the liver and cause a fatal hemorrhage.

The Ribs

There are 12 pairs of **ribs,** with no difference in number between the sexes (despite popular belief). Each is attached at its posterior (proximal) end to the vertebral column, and all but the last two arch around the flank of the chest and attach by way of a cartilaginous strip, the **costal cartilage,** to the sternum.

As a rule, the ribs increase in length from 1 through 7 and become progressively smaller again through rib 12. They are increasingly oblique (slanted) in orientation from 1 through 9, then less so from 10 through 12. They also differ in their individual structure and attachments at different levels of the thoracic cage, so we will examine them in order as we descend the chest, taking note of their universal characteristics as well as their individual variations.

Rib 1 is peculiar. On an articulated skeleton, you must look for its vertebral attachment just below the base of the neck; much of this rib lies above the level of the clavicle (fig. 7.27). It is a short, flat, C-shaped plate of bone (fig. 7.28a). At the vertebral end, it exhibits a knobby **head** that articulates with the body of vertebra T1. On an isolated vertebra, you can find a smooth costal facet for the attachment on the middle of the body. Immediately distal to the head, the rib narrows to a **neck** and then widens again to form a rough area called the **tubercle.** This is its point of attachment to the transverse costal facet of the same vertebra. Beyond the tubercle, the rib flattens and widens into a gently sloping bladelike **shaft.** The shaft ends distally in a squared-off, rough area. In the living individual, the costal cartilage begins here and spans the rest of the distance to the upper sternum. The shaft has a groove on the superior surface that serves as a platform for two blood vessels called the *subclavian artery* and *vein.*

Ribs 2 through 7 present a more typical appearance (fig. 7.28b). At the proximal end, each exhibits a head, neck, and tubercle. The head is wedge-shaped and inserts between two vertebrae. Each margin of the wedge has a smooth surface called an *articular facet.* The **superior articular facet** joins the inferior costal facet of the vertebra above; the **inferior articular facet** joins the superior costal facet of the vertebra below. The tubercle of the rib articulates with the transverse costal facet of each same-numbered vertebra. Figure 7.29 details the three rib–vertebra attachments typical of this region of the rib cage.



(a) Rib 1


Tubercle
Neck
Head
Superior
Inferior
Articular facets for vertebral bodies
Angle
Articular facet for transverse process
Costal groove
Shaft

(b) Ribs 2–10



(c) Ribs 11–12

Figure 7.28 **Anatomy of the Ribs.** (a) Rib 1 is an atypical flat plate. (b) Typical features of ribs 2 through 10. (c) Appearance of the floating ribs, 11 and 12.

Beyond the tubercle, each rib makes a sharp curve around the side of the chest and then progresses anteriorly to approach the sternum (see fig. 7.27). The curve is called the **angle** of the rib and the rest of the bony blade distal to it is called the shaft. The broad surfaces of the shafts are oriented vertically. The inferior margin of the shaft has a **costal groove** that marks the path of the intercostal blood vessels and nerve. Each of these ribs, like rib 1, ends in a blunt, rough area where the costal cartilage begins. Each has its own costal cartilage connecting it to the sternum; because of this feature, ribs 1 through 7 are called **true ribs.**

Ribs 8 through 12 are called **false ribs** because they lack independent cartilaginous connections to the sternum. In 8 through 10, the costal cartilages sweep upward and end on the costal cartilage of rib 7 (see fig. 7.27). Rib 10 also differs from 2 through 9 in that it attaches to the body of a single vertebra (T10) rather than between vertebrae. Thus, vertebra T10 has a complete costal facet on its body for rib 10.

Ribs 11 and 12 are again unusual (fig. 7.28c). Posteriorly, they articulate with the bodies of vertebrae T11 and T12, but they do not have tubercles and do not attach to the transverse processes of the vertebrae. Those two vertebrae therefore have no transverse costal facets. At the distal end, these two relatively small, delicate ribs taper to a point and are capped by a small cartilaginous tip, but there is no cartilaginous connection to the sternum or to any of the higher costal cartilages. The ribs are merely embedded in lumbar muscle at this end. Consequently, 11 and 12 are also called **floating ribs.** Among the Japanese and some other people, rib 10 is also usually floating.

---

[39] *gladiolus* = sword
[40] *xipho* = sword; *oid* = resembling

Table 7.4 summarizes these variations in rib anatomy and their vertebral and sternal attachments.


Inferior costal facet of T5
Superior articular facet of rib 6
Vertebral body T5
Rib 6
Inferior articular facet of rib 6
Vertebral body T6
Superior costal facet of T6

(a) Anterior view


Superior articular facet
Transverse costal facet for rib 6
Tubercle
Superior costal facet for rib 6
Neck
Rib 6
Head
T6

(b) Superior view

Figure 7.29 Articulation of Rib 6 with Vertebrae T5 and T6. (a) Anterior view. Note the relationship of the articular facets of the rib with the costal facets of the two vertebrae. (b) Superior view. Note that the rib articulates with a vertebra at two points: the costal facet of the vertebral body and the transverse costal facet on the transverse process.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

9. Discuss the contributions of the intervertebral discs to the length and flexibility of the spine.
10. Make a table with three columns headed *cervical, thoracic,* and *lumbar.* In each column, list the distinctive characteristics of each type of vertebra.
11. Name the three parts of the sternum. How many ribs attach (directly or indirectly) to each part?
12. Describe how rib 5 articulates with the spine. How do ribs 1 and 12 differ from this and from each other in their modes of articulation?
13. Distinguish between true, false, and floating ribs. Which ribs fall into each category?
14. Palpate as many of the following structures as possible, and identify which ones cannot normally be palpated on a living person: the dens; the spinous process of vertebra C7; the transverse process of vertebra T12; the median sacral crest; the coccyx; the manubrium; the xiphoid process; and the costal cartilage of rib 5.

TABLE 7.4 Articulations of the Ribs

Rib	Type	Costal Cartilage	Articulating Vertebral Bodies	Articulating with a Transverse Costal Facet?	Rib Tubercle
1	True	Individual	T1	Yes	Present
2	True	Individual	T1 and T2	Yes	Present
3	True	Individual	T2 and T3	Yes	Present
4	True	Individual	T3 and T4	Yes	Present
5	True	Individual	T4 and T5	Yes	Present
6	True	Individual	T5 and T6	Yes	Present
7	True	Individual	T6 and T7	Yes	Present
8	False	Shared with rib 7	T7 and T8	Yes	Present
9	False	Shared with rib 7	T8 and T9	Yes	Present
10	False	Shared with rib 7	T10	Yes	Present
11	False, floating	None	T11	No	Absent
12	False, floating	None	T12	No	Absent

7.4 Developmental and Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the prenatal development of the axial skeleton; and
b. describe some common disorders of the axial skeleton.

Development of the Axial Skeleton

The axial skeleton develops primarily by endochondral ossification. This is a two-step process: (1) **chondrification,** in which embryonic mesenchyme condenses and differentiates into hyaline cartilage; and (2) **ossification,** in which the cartilage is replaced by bone, as described in chapter 6. Parts of the skull develop by intramembranous ossification, with no cartilage precursor.

The Skull

Development of the skull is very complex, and we will take only a broad overview of the process here. We can view the skull as developing in three major parts: the base, the calvaria, and the facial bones. The base and calvaria are collectively called the **neurocranium** because they enclose the brain; the facial skeleton is called the **viscerocranium** because it develops from the pharyngeal (visceral) arches described on page 92. Both the neurocranium and viscerocranium have regions of cartilaginous and membranous origin. The cartilaginous neurocranium is also called the **chondrocranium.**

The base of the cranium develops from several pairs of cartilaginous plates. They give rise to most parts of the sphenoid, ethmoid, temporal, and occipital bones. The flat bones of the calvaria form, in contrast, by the intramembranous method. They begin to ossify in week 9, slightly later than the cranial base. As a membranous bone ossifies, trabeculae and spicules of osseous tissue first appear in the center and then spread toward the edges of the bone (fig. 7.30).

Facial bones develop mainly from the first two pharyngeal arches. Although these arches are initially supported by cartilage, that cartilage does not transform into bone. It becomes surrounded by developing membranous bone, and while some of the cartilages become middle-ear bones and part of the hyoid bone, others simply degenerate and disappear. Thus, the facial bones are built *around* cartilages but develop by the intramembranous process.

The skull therefore develops from a multitude of separate pieces. These undergo considerable fusion by the time of birth, but their fusion is by no means complete then. At birth, the frontal bones are still paired. The right and left bones usually fuse by the age of 5 or 6 years, but in some people a *metopic*[41] *suture* persists in the forehead between them. Traces of this suture are evident in some adult skulls.



Figure 7.30 **The Fetal Skeleton at 12 Weeks.** The red-stained regions are ossified at this age, whereas the elbow, wrist, knee, and ankle joints appear translucent because they are still cartilaginous. The cranial bones are still widely separated.

- *Why are the joints of an infant weaker than those of an older child?*

The cranial bones are separated at birth by gaps called **fontanels,**[42] bridged by fibrous membranes (fig. 7.31). The term refers to the fact that pulsation of the infant's blood can be felt there. Fontanels permit the bones to shift as the infant squeezes through the birth canal. This shifting may deform the infant's head, but it usually assumes a normal shape within a few days after birth. Four of the fontanels are especially prominent and regular in location: the **anterior, posterior, sphenoid,** and **mastoid fontanels.** The fontanels close by intramembranous ossification. Most are fully ossified by 12 months of age, but the largest one, the anterior fontanel, does not close for 18 to 24 months. Up to that age, a "soft spot" can be palpated in the corner between the four frontal and parietal bones.

The mandible changes markedly with age. At birth, it consists of right and left bones joined medially by the *mental symphysis,* a zone of cartilage and fibrous connective tissue. The halves begin to fuse in the first year and become fully united into a single bone by age 3. The body of the mandible is very slender at birth, and the ramus is not strongly developed (fig. 7.31a). In early childhood, the mandible grows in a generally downward and forward direction, making the ramus longer and the chin more pronounced. The deciduous ("baby") teeth begin to erupt at about 7 months and continue through the second year, while the body of the mandible widens to accommodate their roots. The deciduous teeth are replaced with permanent teeth mostly between the ages of 6 and 13 years, although the third molar, if it emerges at all, may come as late as age 25 (see fig. 24.6, p. 660). If teeth are lost in old age, the alveoli are resorbed and the body of the mandible becomes narrower, much as it was in infancy.

---

[41] *met* = beyond; *op* = the eyes

[42] *fontan* = fountain; *el* = little


Parietal bone
Lambdoid suture
Squamous suture
Occipital bone
Mastoid fontanel
Temporal bone
Coronal suture
Frontal bone
Sphenoid fontanel
Nasal bone
Maxilla
Zygomatic bone
Mandible
Sphenoid bone

(a) Lateral view


Frontal bone
Anterior fontanel
Sagittal suture
Parietal bone
Posterior fontanel

(b) Superior view

Figure 7.31 The Fetal Skull Near the Time of Birth.

Apply What You Know

Suppose you were studying a skull with some teeth missing. How could you tell whether the teeth had been lost after the person's death or years before it?

The face of a newborn is flat and small compared to the large cranium. It enlarges as the mandible, teeth, and paranasal sinuses develop. To accommodate the growing brain, a child's skull grows more rapidly than the rest of the skeleton. It reaches about half its adult size by age 9 months, three-quarters by age 2, and nearly final size by 8 or 9 years. The heads of babies and young children are therefore much larger in proportion to the trunk than are the heads of adults—an attribute thoroughly exploited by cartoonists and advertisers who draw big-headed characters to give them a more endearing or immature appearance. In humans and other animals, the large, rounded heads of the young are thought to promote survival by stimulating parental caregiving instincts.

The Vertebral Column

One of the universal characteristics of all chordate animals, including humans, is the **notochord,** a flexible, middorsal rod of mesodermal tissue. In humans, the notochord is evident inferior to the neural tube in the third week of development. Segments of embryonic mesoderm called *somites* lie on each side of the notochord and neural tube (see p. 92 and fig. 4.11, p. 97). In week 4, part of each somite becomes a *sclerotome*. This gives rise to vertebral cartilage, which is replaced by bone through endochondral ossification. The sclerotomes are temporarily separated by zones of looser mesenchyme (fig. 7.32a).

As shown in figure 7.32b, each vertebral body arises from portions of two adjacent sclerotomes and the loose mesenchyme between them. The midportion of each sclerotome gives rise to the anulus fibrosus of the intervertebral disc. The notochord


Notochord
Sclerotome
Loose mesenchyme
Degenerating notochord
Precartilaginous vertebral body
Future intervertebral disc
Anulus fibrosus
Nucleus pulposus
Vertebral body
Transverse process
Intervertebral disc
(a)
(b)
(c)
(d)

Figure 7.32 **Development of the Vertebrae and Intervertebral Discs.** (a) The notochord is flanked by sclerotomes, which are separated by zones of loose mesenchyme. (b) Each vertebral body forms by the condensation of parts of two sclerotomes and the loose mesenchyme between them. The midregion of each sclerotome remains less condensed and forms the anulus fibrosus of the intervertebral disc. The notochord degenerates in the regions of condensing mesenchyme but persists between vertebral bodies as the nucleus pulposus. Dashed lines indicate which regions of the sclerotomes in part (a) give rise to the vertebral body and intervertebral disc in part (b). (c) Further condensation of the vertebral bodies. The notochord has now disappeared except at the nucleus pulposus of each disc. (d) Chondrification and ossification give rise to the fully developed vertebral bodies.



Figure 7.33 **Development of a Thoracic Vertebra.** (a) At 5 weeks. (b) At birth. In part (a), the vertebra is composed of mesenchyme surrounding the neural tube. The notochord is still present. The costal process is the forerunner of the rib. In part (b), the vertebra shows three centers of ossification at birth—the body and the two vertebral arches. Hyaline cartilage (blue) still composes the spinous process, the joints between the vertebral arches and the body, and the joints between the ribs and the vertebra.

degenerates and disappears in the regions of the developing vertebral bodies, but persists and expands between the vertebrae to form the nucleus pulposus of the intervertebral discs.

Meanwhile, mesenchyme surrounding the neural tube condenses and forms the vertebral arches of the vertebrae. Approaching the end of the embryonic stage, the mesenchyme of the sclerotomes forms the cartilaginous forerunners of the vertebral bodies (fig. 7.33a). The two halves of the arch fuse with each other and with the body, and the spinous and transverse processes grow outward from the arch. Thus, a complete cartilaginous vertebral column is established.

Ossification of the vertebrae begins during the embryonic period but is not completed until age 25. Each vertebra develops three primary ossification centers: one in the body and one in each half of the vertebral arch. At birth, these three bony parts are still connected by hyaline cartilage (fig. 7.33b). The two halves of the arch finish ossifying and fuse around 3 to 5 years of age, beginning in the lumbar region and progressing rostrally. The attachments of the arch to the body remain cartilaginous for a time in order to allow for growth of the spinal cord. These attachments ossify at 3 to 6 years. Secondary ossification centers form in puberty at the tips of the spinous and transverse processes and in a ring encircling the body. They unite with the rest of the vertebra by age 25.

At birth, the vertebral column exhibits one continuous C-shaped curve (fig. 7.34), as it does in monkeys, apes, and most other four-legged animals. As an infant begins to crawl and lift its head, the cervical curvature forms, enabling an infant on its belly to look forward. The lumbar curvature—completing the S shape of the spine—starts to appear when a toddler begins walking.

The Ribs and Sternum

At 5 weeks, a developing thoracic vertebra consists of a body of mesenchyme with a vertebral body, vertebral foramen, and a pair of winglike lateral extensions called the **costal processes** (fig. 7.33a), which soon give rise to the ribs. At 6 weeks, a chondrification center develops at the base of each process. At 7 weeks, these centers begin to undergo endochondral ossification. A *costovertebral joint* now appears at the base of the process, separating it from the vertebral body (fig. 7.33b). By this time, the first seven ribs (true ribs) connect to the sternum by way of costal cartilages. An ossification center soon appears at the angle of the rib, and endochondral ossification proceeds from there to the distal end of the shaft. Secondary ossification centers appear in the tubercle and head of the rib during adolescence.


© McGraw-Hill Education/Bob Coyle, photographer

Figure 7.34 **Spinal Curvature of the Newborn Infant.** At this age, the spine forms a single C-shaped curve.

The sternum begins as a pair of longitudinal strips of condensed mesenchyme called the **sternal bars.** These form initially in the anterolateral body wall and migrate medially during chondrification. The right and left sternal bars begin to fuse in week 7 as the most superior ribs contact them. Fusion of the sternal bars progresses downward, ending with the formation of the xiphoid process in week 9. The sternal bones form by endochondral ossification beginning superiorly and progressing toward the xiphoid. Ossification begins in month 5 and is completed shortly after birth. In some cases, the sternal bars fail to fuse completely at the inferior end, so the infant xiphoid process is forked or perforated.

Pathology of the Axial Skeleton

Disorders that affect all parts of the skeleton are discussed in chapter 6, especially fractures and osteoporosis. Table 7.5 lists some disorders that affect especially the axial skeleton. We will consider in slightly more depth skull fractures, vertebral fractures and dislocations, and herniated intervertebral discs.

Skull Fractures

The domed shape of the skull distributes the strain of most blows to the head and tends to minimize their effects. Hard blows can nevertheless fracture the calvaria (fig. 7.35a). Most cranial fractures are *linear fractures* (elongated cracks), which can radiate away from the point of impact. In a *depressed fracture,* the cranium caves inward and may compress and damage underlying brain tissue. If a blow occurs in an area where the calvaria is especially thick, as in the occipital region, the bone may bend inward at the point of impact without breaking, but as the strain is distributed through the cranium, it can generate a fracture some distance away, even on the opposite side of the skull (a *contrafissura fracture*). In addition to damaging brain tissue, skull fractures can damage cranial nerves and meningeal blood vessels. A break in a blood vessel may cause a hematoma (mass of clotted blood) that compresses the brain tissue, potentially leading to death within a few hours.

Facial trauma can produce linear *Le Fort*[43] *fractures,* which predictably follow lines of weakness in the facial bones. The three typical Le Fort fractures are shown in figure 7.35b. The type II Le Fort fracture separates the entire central region of the face from the rest of the skull.

Apply What You Know

Describe two accidents or other incidents in a person's life that could result in a depressed fracture of the calvaria, and two that could result in a Le Fort facial fracture.

Vertebral Fractures and Dislocations

Injury to the cervical vertebrae (a "broken neck") often results from violent blows to the head, as in diving, motorcycle, and equestrian accidents, and sudden flexion or extension of the neck, as in automobile accidents. Such injuries often crush the body or arches of a vertebra or cause one vertebra to slip forward relative to the one below it. The dislocation of one vertebra relative to the next can cause irreparable damage to the spinal cord. "Whiplash" often results from rear-end automobile collisions causing violent hyperextension of the neck (backward jerking of the head). This stretches or tears the *anterior longitudinal ligament* that courses along the front of the vertebral bodies, and it may fracture the vertebral body (fig. 7.36a). Dislocations are relatively rare in the thoracic and lumbar regions because of the way the vertebrae are tightly interlocked. When fractures occur in these regions ("broken back"), they most often involve vertebra T11 or T12, at the transition from the thoracic to lumbar spine.

---

[43] Léon C. Le Fort (1829–93), French surgeon and gynecologist

TABLE 7.5 Disorders of the Axial Skeleton

Craniosynostosis	Premature closure of the cranial sutures within the first 2 years after birth, resulting in skull asymmetry, deformity, and sometimes mental retardation. Cause is unknown. Surgery can limit brain damage and improve appearance.
Spinal stenosis	Abnormal narrowing of the vertebral canal or intervertebral foramina caused by hypertrophy of the vertebral bone. Most common in middle-aged and older people. May compress spinal nerves and cause low back pain or muscle weakness.
Spondylosis	A defect of the laminae of the lumbar vertebrae. Defective vertebrae may shift anteriorly, especially at the L5 through S1 level. Stress on the bone may cause microfractures in the laminae and eventual dissolution of the laminae. May be treated by nonsurgical manipulation or by surgery, depending on severity.

Disorders Described Elsewhere

Cleft palate	104
Ethmoid bone fractures	164
Herniated discs	180
Kyphosis	168
Lordosis	168
Scoliosis	168
Skull fractures	179
Spina bifida	367
Vertebral fractures	179


Depressed fracture
Linear fracture
Basilar fracture
III
II
I

(a) Medial view

(b) Anterior view

Figure 7.35 **Skull Fractures.** (a) Medial view showing linear and depressed fractures of the frontal bone and a basilar fracture of the occipital bone. (b) The three types of Le Fort fractures of the facial bones.

Herniated Discs

A **herniated** ("slipped" or "ruptured") **disc** is cracking of the anulus fibrosus of an intervertebral disc under strain, often caused by violent flexion of the vertebral column or by lifting heavy weights. Cracking of the anulus allows the gelatinous nucleus pulposus to ooze out, sometimes putting pressure on a spinal nerve root or the spinal cord (fig. 7.36b). Back pain results from both pressure on the nervous tissue and inflammation stimulated by the nucleus pulposus. About 95% of disc herniations occur at levels L4/L5 and L5/S1. The nucleus pulposus usually escapes in a posterolateral direction, where the anulus is thinnest. Herniated discs rarely occur in young people because their discs are well hydrated and absorb pressure well. As people get older, the discs become dehydrated and they degenerate and grow thinner, becoming more susceptible to herniation. After middle age, however, the anulus fibrosus becomes thicker and tougher, and the nucleus pulposus is smaller, so disc herniations again become less common.


Forward motion of body
Fracture dislocation of vertebrae
Anterior longitudinal ligament
Spinal cord

(a) Whiplash


Herniation of nucleus pulposus
Spinal nerve roots
Crack in anulus fibrosus
Spinal nerve
Nucleus pulposus
Anulus fibrosus

(b) Herniated disc

Figure 7.36 **Injuries to the Vertebral Column.** (a) Whiplash injury. Violent hyperextension of the neck has torn the anterior longitudinal ligament and fractured the vertebral body. (b) Herniated intervertebral disc. The nucleus pulposus is oozing into the vertebral canal and compressing a bundle of spinal nerve roots that passes through the lumbar vertebrae.

- *Herniated discs are more common in the lumbar region than in the cervical region. Explain.*

Before You Go On

Answer the following questions to test your understanding of the preceding section:

15. Define *chondrocranium* and *viscerocranium*, and explain why each of them is named that.
16. What is the functional significance of fontanels? When does the last fontanel close?
17. What structure in the adult is a remnant of the embryonic notochord?
18. What is a Le Fort fracture? What is whiplash?
19. Explain why a herniated disc can cause nerve pain (neuralgia).

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

7.1 Overview of the Skeleton (p. 152)

1. The distinction between the axial and appendicular skeletons
2. Changes in the number of bones with age; the typical adult number; and reasons why the adult number varies from one person to another
3. Terminology of the surface features of bones

7.2 The Skull (p. 155)

1. Names and locations of the cavities in the skull
2. Definitions of *suture* and *foramen* in skull anatomy
3. The distinction between cranial bones and facial bones
4. Names and locations of the cranial bones, and names of the sutures that form their boundaries (to the extent that this book names them)
5. The relationship of the cranial bones to the meninges and brain tissue
6. The distinction between the calvaria and the base of the cranium
7. Names and locations of the three cranial fossae and their relationship to the anatomy of the brain
8. Recognition of the important anatomical features (especially those boldfaced in the text) of the cranial bones: the frontal, parietal, temporal, occipital, sphenoid, and ethmoid bones
9. Recognition of the important anatomical features (especially those boldfaced in the text) of the facial bones: the maxilla; inferior nasal concha; vomer; mandible; and the palatine, zygomatic, lacrimal, and nasal bones
10. The location, anatomy, and function of the hyoid bone
11. The names, locations, and anatomy of the three auditory ossicles, and their collective function
12. How the location of the foramen magnum and relative flatness of the human face are related to the bipedal stance of humans

7.3 The Vertebral Column and Thoracic Cage (p. 167)

1. Functions of the vertebral column
2. The five classes of vertebrae; and the number of vertebrae in each class
3. The number of intervertebral discs; which vertebrae have discs between them and which ones do not; and the structure of a disc
4. The overall shape of the adult vertebral column and the names of its four curvatures
5. The anatomical features of a generalized vertebra
6. Surfaces of the vertebrae that articulate with adjacent vertebrae and with the ribs
7. The relationships of the vertebral and intervertebral foramina to the spinal cord and spinal nerves
8. Anatomical features that distinguish cervical, thoracic, and lumbar vertebrae from each other
9. The unique features and names of each of the first two cervical vertebrae (C1–C2); names of the joints between the skull and C1 and between C1 and C2; and how the features of these two vertebrae relate to head movements
10. Anatomy of the articulations between the ribs and thoracic vertebrae
11. Anatomical features of the sacrum and coccyx and of the articulations between the sacrum and hip bones
12. Components of the thoracic cage
13. The three parts of the sternum; its other features; and its articulations with the clavicles and ribs
14. The categories of ribs; how each category is defined; the total number of ribs; and which ribs belong to each category
15. The generalized anatomy of a rib; how rib 1 and ribs 11 and 12 anatomically differ from the others; and the relationships of the ribs to the costal cartilages, sternum, and vertebral bodies and transverse processes

7.4 Developmental and Clinical Perspectives (p. 176)

1. The complementary roles of intramembranous and endochondral ossification in the prenatal development of the skull
2. The portions of the skull that constitute the neurocranium, viscerocranium, and chondrocranium
3. The role of pharyngeal arches in development of the skull
4. Developmental changes in the skull after birth
5. The names and locations of the fontanels in the fetal skull, why they exist, and what becomes of them

6. The role of the embryonic notochord and sclerotomes in development of the vertebral column
7. The ossification process of a vertebra
8. Development of the ribs from the embryonic vertebrae
9. Embryonic development of the sternum
10. The common types of skull fractures: linear, depressed, contrafissura, and Le Fort fractures
11. Causes and effects of vertebral fractures and dislocations
12. The causes, anatomical aspects, and effects of herniated intervertebral discs

Testing Your Recall

1. Which of these is *not* a paranasal sinus?
    a. frontal
    b. temporal
    c. sphenoid
    d. ethmoid
    e. maxillary
2. Which of these is a facial bone?
    a. frontal
    b. ethmoid
    c. occipital
    d. temporal
    e. lacrimal
3. What occupies the transverse foramina seen in certain vertebrae?
    a. vertebral arteries
    b. nucleus pulposus
    c. spinal nerves
    d. carotid arteries
    e. internal jugular veins
4. All of the following are groups of vertebrae *except* for _____, which is a spinal curvature.
    a. thoracic
    b. cervical
    c. lumbar
    d. pelvic
    e. sacral
5. Thoracic vertebrae do *not* have
    a. transverse foramina.
    b. costal facets.
    c. transverse costal facets.
    d. transverse processes.
    e. pedicles.
6. Which of these bones forms by intramembranous ossification?
    a. a vertebra
    b. a parietal bone
    c. the occipital bone
    d. the sternum
    e. a rib
7. The viscerocranium includes
    a. the maxilla.
    b. the parietal bones.
    c. the occipital bone.
    d. the temporal bone.
    e. the atlas.
8. Which of these is *not* a suture?
    a. parietal
    b. coronal
    c. lambdoid
    d. sagittal
    e. squamous
9. The sella turcica contains
    a. the pituitary gland.
    b. the auditory ossicles.
    c. air cells.
    d. the foramen lacerum.
    e. the lacrimal sac.
10. The nasal septum is composed partly of the same bone as
    a. the zygomatic arch.
    b. the hard palate.
    c. the cribriform plate.
    d. the nasal concha.
    e. the centrum.
11. Gaps between the cranial bones of an infant are called _____.
12. The external acoustic meatus is an opening in the _____ bone.
13. Bones of the skull are joined along lines called _____.
14. The _____ bone has greater and lesser wings and protects the pituitary gland.
15. A herniated disc occurs when a ring called the _____ cracks.
16. The transverse ligament of the atlas holds the _____ of the axis in place.
17. The sacroiliac joint is formed where the _____ surface of the sacrum articulates with that of the ilium.
18. We have five pairs of _____ ribs and two pairs of _____ ribs.
19. Ribs 1 through 10 are joined to the sternum by way of strips of connective tissue called _____.
20. The point at the inferior end of the sternum is the _____.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. crani-
2. tempor-
3. masto-
4. petr-
5. lamina
6. pterygo-
7. crista
8. lacrimo-
9. costo-
10. ped-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. The bodies of the vertebrae are derived from the notochord of the embryo.
2. Adults have more bones than children do.
3. A smooth round knob on a bone is called a condyle.
4. The zygomatic arch consists entirely of the zygomatic bone.
5. The dura mater adheres tightly to the entire inner surface of the cranial cavity.
6. The sphenoid bone forms part of the orbit.
7. The nasal septum is not entirely bony.
8. Not everyone has a frontal sinus.
9. The anterior surface of the sacrum is smoother than the posterior surface.
10. The lumbar vertebrae do not articulate with any ribs and therefore do not have transverse processes.

Answers in appendix A

Testing Your Comprehension

1. A child was involved in an automobile collision. She was not wearing a safety restraint, and her chin struck the dashboard hard. When the physician looked into her auditory canal, he could see into her throat. What do you infer from this about the nature of her injury?
2. Chapter 1 noted that there are significant variations in the internal anatomy of different people (p. 6). Give some examples from this chapter other than pathological cases (such as cleft palate) and normal age-related differences.
3. Vertebrae T12 and L1 look superficially similar and are easily confused. Explain how to tell the two apart.
4. What effect would you predict if an ossification disorder completely closed off the superior orbital fissure?
5. For each of the following bones, name all the other bones with which it articulates: parietal, zygomatic, temporal, and ethmoid bones.



X-ray of an adult foot

© Medical Body Scans/Science Source

CHAPTER 8

THE SKELETAL SYSTEM III
APPENDICULAR SKELETON

CHAPTER OUTLINE

8.1 The Pectoral Girdle and Upper Limb 185
- Pectoral Girdle 185
- Upper Limb 186

8.2 The Pelvic Girdle and Lower Limb 190
- Pelvic Girdle 190
- Lower Limb 193

8.3 Developmental and Clinical Perspectives 200
- Development of the Appendicular Skeleton 200
- Pathology of the Appendicular Skeleton 201

Study Guide 203

DEEPER INSIGHTS

8.1 Clavicular Fractures 185
8.2 Femoral Fractures 196
8.3 Anatomical Position—Clinical and Biological Perspectives 199

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:

- Terminology of the appendicular region (p. 16)
- General features of bones (p. 133)
- Intramembranous and endochondral ossification (p. 139)

Anatomy & Physiology REVEALED
aprevealed.com

Module 5: Skeletal System

In this chapter, we turn our attention to the *appendicular skeleton*—the bones of the upper and lower limbs and the pectoral and pelvic girdles that attach them to the axial skeleton. We depend so heavily on the limbs for mobility and the ability to manipulate objects that deformities and injuries to the appendicular skeleton are more disabling than most disorders of the axial skeleton. Hand injuries, especially, can disable a person far more than a comparable amount of tissue injury elsewhere on the body. Injuries to the appendicular skeleton are especially common in athletics, recreation, and the workplace. A knowledge of the anatomy of the appendicular skeleton is therefore especially important to such professionals as athletic trainers, physical therapists, and other health-care providers.

8.1 The Pectoral Girdle and Upper Limb

Expected Learning Outcomes

When you have completed this section, you should be able to

a. identify and describe the features of the clavicle, scapula, humerus, radius, ulna, and bones of the wrist and hand; and
b. describe the evolutionary innovations of the human forelimb.

Pectoral Girdle

The **pectoral**[1] **girdle** (shoulder girdle) supports the arm and links it to the axial skeleton. It consists of two bones on each side of the body: the *clavicle* (collarbone) and *scapula* (shoulder blade). The medial end of the clavicle articulates with the sternum at the **sternoclavicular joint,** and its lateral end articulates with the scapula at the **acromioclavicular**[2] **joint** (see fig. 7.27, p. 173). The scapula also articulates with the humerus at the **glenohumeral**[3] (shoulder) **joint.** These are loose attachments that result in a shoulder far more flexible than that of most other mammals, but they also make the shoulder joint easy to dislocate.

Clavicle

The **clavicle**[4] (fig. 8.1) is a slightly S-shaped bone, somewhat flattened from the upper to lower surface, and easily seen and palpated on the upper thorax (see fig. A.1b, p. 331). The superior surface is relatively smooth and rounded, whereas the inferior surface is flatter and marked by grooves and ridges for muscle attachment. The medial **sternal end** has a rounded, hammerlike head, and the lateral **acromial end** is markedly flattened. Near the acromial end is a rough tuberosity called the **conoid**[5] **tubercle**—a ligament attachment that faces posteriorly and slightly downward.



(a) Superior view



(b) Inferior view

Figure 8.1 **The Right Clavicle (Collarbone).**
- *The clavicle is broken more often than any other bone in the body. State some reasons why.* AP|R

The clavicles brace the shoulders, keeping the upper limbs away from the midline of the body. Without the clavicles, the pectoralis major muscles would pull the shoulders forward and medially—which indeed happens when a clavicle is fractured (see Deeper Insight 8.1). The clavicle also transfers force from the arm to the axial region of the body, as in doing push-ups. It is thickened in people who do heavy manual labor, and is usually stronger and shorter on the side with the dominant limb (the right clavicle in right-handed people).

Scapula

The **scapula**[6] (fig. 8.2) is a triangular plate that overlies ribs 2 through 7. Its only direct attachment to the thoracic cage is by muscles; it glides over the rib cage as the arm and shoulder move. The three sides of the scapular triangle are called the **superior, medial (vertebral),** and **lateral (axillary) borders,** and its three angles are the **superior, inferior,** and **lateral angles.**

DEEPER INSIGHT 8.1

Clavicular Fractures

The clavicle is the most frequently broken bone of the body. It can break when one falls directly on the shoulder or thrusts out an arm to break a fall and the force of the fall is transmitted through the limb to the pectoral girdle. Fractures most often occur at a weak point about one-third of the way from the lateral end. When the clavicle is broken, the shoulder tends to drop, the sternocleidomastoid muscle of the neck elevates the medial fragment, and the pectoralis major muscle of the chest may pull the lateral fragment toward the sternum. In wide-shouldered infants, the clavicle sometimes fractures during birth, but these neonatal fractures heal quickly. In children, clavicular fractures are often of the greenstick type.

---

[1] *pect* = chest; *oral* = pertaining to
[2] *acr* = extremity, peak; *omo* = shoulder
[3] *gleno* = socket
[4] *clav* = hammer, club; *icle* = little
[5] *con* = cone; *oid* = shaped
[6] *scap* = spade, shovel; *ula* = little



Figure 8.2 The Right Scapula.

- *Identify the two points where this bone is attached to the rest of the skeleton.* AP|R

A conspicuous **suprascapular notch** in the superior border provides passage for a nerve. The broad anterior surface of the scapula, called the **subscapular fossa,** is slightly concave and relatively featureless. The posterior surface has a transverse shelflike ridge called the **spine,** a deep indentation superior to the spine called the **supraspinous fossa,** and a broad surface inferior to it called the **infraspinous fossa.**[7]

The most complex region of the scapula is the lateral angle, which has three main features:

1. The **acromion** (ah-CRO-me-on) is a platelike extension of the scapular spine that forms the apex of the shoulder. It articulates with the clavicle, which forms the sole bridge from the appendicular to the axial skeleton.
2. The **coracoid**[8] (COR-uh-coyd) **process** is shaped like a bent finger but named for a vague resemblance to a crow's beak; it provides attachment for tendons of the *biceps brachii* and other muscles of the arm.
3. The **glenoid** (GLEN-oyd) **cavity** is a shallow socket that articulates with the head of the humerus, forming the glenohumeral joint.

Apply What You Know

What part of the scapula do you think is most commonly fractured? Why?

Upper Limb

The upper limb is divided into 3 segments containing a total of 30 bones per limb:

1. The **brachium**[9] (BRAY-kee-um), or arm proper, extends from shoulder to elbow. It contains only one bone, the *humerus.*
2. The **antebrachium,**[10] or forearm, extends from elbow to wrist and contains two bones—the *radius* and *ulna.* In anatomical position, these bones are parallel and the radius is lateral to the ulna.
3. The **manus,**[11] or hand, contains 27 bones in three groups—8 *carpal*[12] bones in the base of the hand, 5 *metacarpals* in the palm, and 14 *phalanges* in the digits.

Humerus

The **humerus** has a hemispherical **head** that articulates with the glenoid cavity of the scapula (fig. 8.3). The smooth surface of the head (covered with articular cartilage in life) is bordered by a groove called the **anatomical neck.** Other prominent features of the proximal end are muscle attachments called the **greater** and **lesser tubercles** and an **intertubercular sulcus (groove)** between them that accommodates a tendon of the biceps muscle. The **surgical neck,** a common fracture site, is a narrowing of the bone just distal to the tubercles, at the transition from the head to the shaft.

---

[7] *supra* = above; *infra* = below
[8] *corac* = crow; *oid* = shaped, resembling
[9] *brachi* = arm
[10] *ante* = before
[11] *man* = hand
[12] *carp* = wrist


Greater tubercle
Lesser tubercle
Intertubercular sulcus
Deltoid tuberosity
Head
Surgical neck
Greater tubercle
Anatomical neck
Nutrient foramen
Deltoid tuberosity
Coronoid fossa
Radial fossa
Lateral epicondyle
Capitulum
Medial supracondylar ridge
Medial epicondyle
Trochlea
Lateral supracondylar ridge
Lateral epicondyle
Olecranon fossa

(a) Anterior view **(b) Posterior view**

Figure 8.3 **The Right Humerus.** AP|R

The shaft has a rough area called the **deltoid tuberosity** on its lateral surface. This is an insertion for the *deltoid muscle* of the shoulder.

The distal end of the humerus has two smooth condyles. The lateral one, called the **capitulum**[13] (ca-PIT-you-lum), is shaped like a fat wheel and articulates with the radius. The medial one, called the **trochlea**[14] (TROCK-lee-uh), is pulleylike and articulates with the ulna. Immediately proximal to these condyles, the humerus flares out to form two bony processes, the **lateral** and **medial epicondyles,** which are easily palpated at the widest point of your elbow. The medial epicondyle protects the *ulnar nerve,* which passes close to the surface across the back of the elbow. This epicondyle is popularly known as the "funny bone" because a sharp blow to the elbow at this point stimulates the ulnar nerve and produces an intense tingling sensation. Immediately proximal to the epicondyles, the margins of the humerus are sharply angular and form the **lateral** and **medial supracondylar ridges.** These are attachments for certain forearm muscles.

The distal end of the humerus also shows three deep pits—two anterior and one posterior. The posterior pit, called the **olecranon**[15] (oh-LEC-ruh-non) **fossa,** accommodates a process of the ulna called the olecranon when the elbow is extended. On the anterior surface, a medial pit called the **coronoid**[16] **fossa** accommodates the coronoid process of the ulna when the elbow is flexed. The lateral pit is the **radial fossa,** named for the nearby head of the radius.

Radius

The **radius** extends from elbow to wrist on the lateral side of the forearm, ending just proximal to the base of the thumb (fig. 8.4).


Olecranon
Radial notch of ulna
Head of radius
Neck of radius
Radial tuberosity
Trochlear notch
Coronoid process
Ulnar tuberosity
Olecranon
Head of radius
Neck of radius
Ulna
Radius
Interosseous borders
Interosseous membrane
Ulnar notch of radius
Head of ulna
Styloid process
Articular facets
Styloid process
Styloid process

(a) Anterior view **(b) Posterior view**


Humerus
Capitulum
Trochlea
Radial head
Radius
Ulna
Coronoid process
Trochlear notch
Olecranon

(c) Medial view

Figure 8.4 **The Right Radius and Ulna.** Part (c) shows the relationship of the trochlear notch of the ulna to the trochlea of the humerus, with the elbow flexed 90°. AP|R

---

[13] *capit* = head; *ulum* = little
[14] *troch* = wheel, pulley
[15] *olecranon* = elbow
[16] *coron* = something curved; *oid* = shaped

It has a distinctive discoidal **head** at its proximal end. When the forearm is rotated so the palm turns forward and back, the circular superior surface of this disc spins on the capitulum of the humerus, and the edge of the disc spins on the radial notch of the ulna. Immediately distal to the head, the radius has a narrower **neck** and then widens to a rough prominence, the **radial tuberosity,** on its medial surface. The distal tendon of the biceps muscle terminates on this tuberosity.

The distal end of the radius has the following features, from lateral to medial:

1. A bony point, the **styloid**[17] **process,** can be palpated proximal to the thumb.
2. Two shallow depressions (articular facets) articulate with the scaphoid and lunate bones of the wrist.
3. The **ulnar notch** articulates with the end of the ulna.

Ulna

The **ulna**[18] is the medial bone of the forearm (fig. 8.4). Its proximal end has a wrenchlike shape, with a deep, C-shaped **trochlear notch** that wraps around the trochlea of the humerus. The posterior side of this notch is formed by a prominent **olecranon**—the bony point where you rest your elbow on a table. The anterior side is formed by a less prominent **coronoid process.** Laterally, the head of the ulna has a less conspicuous **radial notch,** which accommodates the edge of the head of the radius. At the distal end of the ulna is a medial **styloid process.** The bony lumps you can palpate on each side of your wrist are the styloid processes of the radius and ulna.

The radius and ulna are attached along their shafts by a ligament called the **interosseous**[19] (IN-tur-OSS-ee-us) **membrane (IM),** which is attached to an angular ridge called the **interosseous border** on the facing margins of each bone. Most fibers of the IM are oriented obliquely, slanting upward from the ulna to the radius. If you lean forward on a table supporting your weight on your hands, about 80% of the force is borne by the radius. This tenses the IM, which pulls the ulna upward and transfers some of this force through the ulna to the humerus. The IM therefore enables the two elbow joints (between humerus and radius, and humerus and ulna) to share the load and reduces the wear and tear that one joint would otherwise have to bear alone. The IM also serves as an attachment for several forearm muscles.

Carpal Bones

The **carpal bones** are arranged in two rows of four bones each (fig. 8.5). Although they are commonly called the wrist bones, they are located in the base of the hand. The narrow point where one might wear a watch or bracelet is at the distal ends of the radius and ulna. The short carpal bones allow movements of the wrist from side to side and anterior to posterior. The carpal bones of the proximal row, starting at the lateral (thumb) side, are the **scaphoid, lunate, triquetrum** (tri-QUEE-trum), and **pisiform** (PY-sih-form)—Latin for boat-, moon-, triangle-, and pea-shaped, respectively. Unlike the other carpal bones, the pisiform is a sesamoid bone; it is not present at birth but develops around the age of 9 to 12 years within the tendon of the *flexor carpi ulnaris muscle.*

The bones of the distal row, again starting on the lateral side, are the **trapezium,**[20] **trapezoid, capitate,**[21] and **hamate.**[22] The hamate can be recognized by a prominent hook, or **hamulus,** on the palmar side. The hamulus is an attachment for the *flexor retinaculum,* a fibrous sheet in the wrist that covers the carpal tunnel (see fig. 12.9, p. 307).

Metacarpal Bones

Bones of the palm are called **metacarpals.**[23] Metacarpal I is located proximal to the thumb and metacarpal V is proximal to the little finger (fig. 8.5). On a skeleton, the metacarpals look like extensions of the fingers, so the fingers seem much longer than they really are. The proximal end of a metacarpal bone is called the **base,** the shaft is called the **body,** and the distal end is called the **head.** The heads of the metacarpals form the knuckles when you clench your fist.

Phalanges

The bones of the fingers are called **phalanges** (fah-LAN-jeez); in the singular, *phalanx*[24] (FAY-lanks). There are two phalanges in the **pollex** (thumb) and three in each of the other digits (fig. 8.5). Phalanges are identified by roman numerals preceded by *proximal, middle,* and *distal.* For example, proximal phalanx I is in the basal segment of the thumb (the first segment beyond the web between the thumb and palm); the left proximal phalanx IV is where people usually wear wedding rings; and distal phalanx V forms the tip of the little finger. The three parts of a phalanx are the same as in a metacarpal: *base, body,* and *head.* The ventral surface of a phalanx is slightly concave from end to end and flattened from side to side; the dorsal surface is rounder and slightly convex from end to end.

Evolution of the Forelimb

Elsewhere in chapters 7 and 8, we examine how the evolution of bipedal locomotion in humans has affected the skull, vertebral column, and lower limb. The effects of bipedalism on the upper limb are less immediately obvious, but nevertheless substantial. In apes, all four limbs are adapted primarily for walking and climbing, and the forelimbs are longer than the hindlimbs. Thus, the shoulders are higher than the hips when the animal walks. When some apes such as orangutans and gibbons walk bipedally, they typically hold their long forelimbs over

---

[17] *styl* = pillar; *oid* = shaped
[18] *ulna* = elbow
[19] *inter* = between; *osse* = bones
[20] *trapez* = table, grinding surface
[21] *capit* = head; *ate* = possessing
[22] *ham* = hook; *ate* = possessing
[23] *meta* = beyond; *carp* = wrist
[24] *phalanx* = line of soldiers, closely knit row


Distal phalanx II
Middle phalanx II
Proximal phalanx II
Key to carpal bones
🟩 Distal row
🟨 Proximal row
Distal phalanx I
Proximal phalanx I
First metacarpal
IV
III
II
V
I
Phalanges
Head
Body
Base
Metacarpal bones
Head
Body
Base
Carpal bones
Hamulus of hamate
Hamate
Pisiform
Triquetrum
Lunate
Trapezoid
Trapezium
Capitate
Scaphoid
Carpal bones

(a) Anterior view


Lateral
Hamulus
Articulation with triquetrum
Articulation with capitate
Sesamoid bone

© NHS Trust/Tony Stone Images/Getty Images

(b) Hamate bone

(c) X-ray of adult hand

Figure 8.5 **The Right Hand, Anterior (Palmar) View.** (a) Carpal bones are color-coded to distinguish the proximal (yellow) and distal (green) rows. Some people remember the names of the carpal bones with the mnemonic, "Sally left the party to take Charlie home." The first letters of these words correspond to the first letters of the carpal bones, from lateral to medial, proximal row first. (b) The right hamate bone, viewed from the proximal side of the wrist to show its distinctive hook. This unique bone is a useful landmark for locating the others when studying the skeleton. (c) Color-enhanced X-ray of an adult hand. Identify the unlabeled bones in the X-ray by comparing it with the drawing in part (a). A small sesamoid bone is visible at the base of the thumb. The pisiform bone in part (a) is also a sesamoid bone.
- *How does part (c) differ from the X-ray of a child's hand in figure 6.10, p. 141?* APR

their heads to prevent them from dragging on the ground. By contrast, the human forelimbs are adapted primarily for reaching out, exploring the environment, and manipulating objects. They are shorter than the hindlimbs and far less muscular than the forelimbs of apes. No longer needed for locomotion, our forelimbs, especially the hands, have become better adapted for carrying objects, holding things closer to the eyes, and manipulating them more precisely. Although the forelimbs have the same basic bone and muscle pattern as the hindlimbs, the joints of the shoulders and hands, especially, give the forelimbs far greater mobility.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. Describe how to distinguish the medial and lateral ends of the clavicle from each other and how to distinguish its superior and inferior surfaces.
2. Name the three fossae of the scapula and describe the location of each.
3. What three bones meet at the elbow? Identify the fossae, articular surfaces, and processes of this joint and state to which bone each of these features belongs.
4. Name the carpal bones of the proximal row from lateral to medial, and then the bones of the distal row in the same order.
5. Name the four bones from the tip of the little finger to the base of the hand.
6. Palpate as many of the following structures as possible, and identify which ones cannot normally be palpated on a living person: the inferior angle of the scapula, the subscapular fossa, the acromion, the epicondyles of the humerus, the olecranon, and the interosseous membrane of the forearm.

8.2 The Pelvic Girdle and Lower Limb

Expected Learning Outcomes

When you have completed this section, you should be able to

a. identify and describe the features of the pelvic girdle, femur, patella, tibia, fibula, and bones of the foot;
b. compare the anatomy of the male and female pelvic girdles and explain the functional significance of the differences; and
c. describe the evolutionary adaptations of the pelvis and hindlimb for bipedal locomotion.

Pelvic Girdle

The terms *pelvis* and *pelvic girdle* are used in contradictory ways by various authorities. Here we will follow the practice of *Gray's Anatomy* in considering the **pelvic girdle** to consist of a complete ring composed of three bones (fig. 8.6)—two **hip (coxal) bones** and the sacrum (which of course is also part of the vertebral column). The hip bones are also frequently called the *ossa coxae*[25] (OS-sa COC-see) (singular, *os coxae*) and sometimes *innominate*[26] bones—arguably the most self-contradictory term in human anatomy ("the bones with no name"). The **pelvis** is a bowl-shaped structure composed of these bones as well as their ligaments and the muscles that line the pelvic cavity and form its floor. The pelvic girdle supports the trunk on the lower limbs and encloses and protects the viscera of the pelvic cavity—mainly the lower colon, urinary bladder, and internal reproductive organs.

Each hip bone is joined to the vertebral column at one point, the **sacroiliac (SI) joint,** where its **auricular**[27] **surface** matches the auricular surface of the sacrum. The two hip bones articulate with each other on the anterior side of the pelvis, where they are joined by a pad of fibrocartilage called the **interpubic disc.** The interpubic disc and the adjacent region of pubic bone on each side constitute the **pubic symphysis,**[28] which can be palpated as a hard prominence immediately above the genitalia.

True to its name, the pelvis[29] has a bowl-like shape with the broad **greater (false) pelvis** between the flare of the hips and the narrow **lesser (true) pelvis** below (fig. 8.6b). The two are separated by a somewhat round margin called the **pelvic brim.** The greater pelvis forms the walls of the lower abdominal cavity, whereas the lesser pelvis encloses the pelvic cavity. The opening circumscribed by the brim is called the **pelvic inlet**—an entry into the lesser pelvis through which an infant's head passes during birth. The lower margin of the lesser pelvis is called the **pelvic outlet.**

The hip bones have three distinctive features that will serve as landmarks for further description. These are the **iliac**[30] **crest** (superior crest of the hip); **acetabulum**[31] (ASS-eh-TAB-you-lum) (the hip socket—named for its resemblance to vinegar cups used on ancient Roman dining tables); and **obturator**[32] **foramen** (a large round-to-triangular hole below the acetabulum, closed in life by a ligament called the *obturator membrane*).

The adult hip bone forms by the fusion of three childhood bones called the *ilium* (ILL-ee-um), *ischium* (ISS-kee-um), and

---

[25] *os, ossa* = bone, bones; *coxae* = of the hip(s)
[26] *in* = without; *nomin* = name; *ate* = possessing
[27] *aur* = ear; *icul* = little; *ar* = like
[28] *sym* = together; *physis* = growth
[29] *pelvis* = basin, bowl
[30] *ili* = flank, loin; *ac* = pertaining to
[31] *acetabulum* = vinegar cup
[32] *obtur* = to close, stop up; *ator* = that which


Ilium
Iliac crest
Iliac fossa
Anterior superior iliac spine
Anterior inferior iliac spine
Ischium
Spine
Body
Ramus
Pubis
Superior ramus
Inferior ramus
Body
Pubic symphysis
Base of sacrum
Sacroiliac joint
Pelvic surface of sacrum
Pelvic inlet
Coccyx
Acetabulum
Interpubic disc
Obturator foramen

(a) Anterosuperior view


Pelvic brim
Pelvic inlet
Pelvic outlet
Key
Greater pelvis
Lesser pelvis

(b) Median section

Figure 8.6 The Pelvic Girdle. (a) Anterosuperior view, tilted slightly toward the viewer to show the base of the sacrum and the pelvic inlet. (b) Median section to show the greater and lesser pelvis and the pelvic inlet and outlet.

- *How is this anatomy related to the existence of fontanels in the skull of the newborn infant?*

pubis (PEW-biss), identified by color in figure 8.7. The largest of these is the **ilium,** which extends from the iliac crest to the center of the acetabulum. The iliac crest extends from an anterior point or angle called the **anterior superior iliac spine** to a sharp posterior angle called the **posterior superior iliac spine.** In a lean person, the anterior spines form visible anterior protrusions at a point where the pockets usually open on a pair of pants, and the posterior spines are sometimes marked by dimples above the buttocks where connective tissue attached to the spines pulls inward on the skin (see fig. A.15, p. 343).

Below the superior spines are the **anterior** and **posterior inferior iliac spines.** Below the latter is a deep **greater sciatic**[33] (sy-AT-ic) **notch,** named for the sciatic nerve that passes through it and continues down the posterior side of the thigh.

The posterolateral surface of the ilium is relatively rough-textured because it serves for attachment of several muscles of the buttocks and thighs. The anteromedial surface, by contrast, is the smooth, slightly concave **iliac fossa,** covered in life by the broad *iliacus muscle.* Medially, the ilium exhibits an auricular surface that matches the one on the sacrum, so the two bones form the sacroiliac joint.

The **ischium**[34] forms the inferoposterior portion of the hip bone. Its heavy **body** is marked with a prominent **spine.** Inferior to the spine is a slight indentation, the **lesser sciatic notch,** and then the thick, rough-surfaced **ischial tuberosity,** which supports your body when you are sitting. The tuberosity can be palpated by sitting on your fingers. The **ramus** of the ischium joins the inferior ramus of the pubis anteriorly.

---

[33] *sciat* = hip or ischium; *ic* = pertaining to

[34] *ischium* = hip


Ilium
Ischium
Pubis
Iliac crest
Anterior gluteal line
Inferior gluteal line
Anterior superior iliac spine
Posterior gluteal line
Posterior superior iliac spine
Posterior inferior iliac spine
Anterior inferior iliac spine
Greater sciatic notch
Body of ilium
Acetabulum
Superior ramus of pubis
Ischial spine
Body of pubis
Lesser sciatic notch
Inferior ramus of pubis
Body of ischium
Obturator foramen
Ischial tuberosity
Ramus of ischium

(a) Lateral view


Iliac crest
Iliac fossa
Anterior superior iliac spine
Posterior superior iliac spine
Arcuate line
Auricular surface
Anterior inferior iliac spine
Posterior inferior iliac spine
Greater sciatic notch
Pectineal line
Ischial spine
Location of pubic symphysis
Obturator foramen
Ramus of ischium

(b) Medial view

Figure 8.7 **The Right Hip Bone.** The three childhood bones that fuse to form the adult hip bone are identified by color. APR

The **pubis (pubic bone)** is the most anterior portion of the hip bone; it is nearly horizontal, and forms a platform that supports the urinary bladder. It has a **superior** and **inferior ramus** and a triangular **body.** The body of one pubis meets the body of the other at the pubic symphysis. The pubis and ischium encircle the obturator foramen. The pubis is sometimes fractured when the pelvis is subjected to violent anteroposterior compression, as in seat-belt injuries.

Human pelvic anatomy is a compromise between two requirements—bipedalism and childbirth. In apes and other quadrupedal (four-legged) mammals, the abdominal viscera are supported by the muscular wall of the abdomen. In humans, however, they bear down on the floor of the pelvic cavity, and a bowl-shaped pelvis helps support their weight. This has resulted in a narrower pelvic outlet—a condition that creates pain and difficulty in giving birth to the large-brained infants of our species. Humans must be born before the cranial bones fuse so that the head can squeeze through the outlet. This is thought to be the reason why our infants are born in such an immature state compared to those of other primates.

The largest muscle of the buttock, the *gluteus maximus,* serves in chimpanzees and other apes primarily as an abductor of the thigh—that is, it moves the lower limb laterally. In humans, however, the ilium has expanded posteriorly, so the gluteus maximus originates behind the hip joint. This changes the function of the muscle—instead of abducting the thigh, it pulls it back in the second half of a stride (pulling back on your right thigh, for example, when your left foot is off the ground and swinging forward). When one is standing, the gluteus maximus also pulls the pelvis posteriorly so that the body's weight is better balanced on the lower limbs. This helps us to stand upright without expending a great deal of energy to keep from falling forward. The posterior growth of the ilium is the reason the greater sciatic notch is so deeply concave (fig. 8.8). The ilium also curves farther anteriorly in humans than in apes. This positions other gluteal muscles (the *gluteus medius* and *minimus*) in front of the hip joint, where they rotate and balance the trunk so we don't sway from side to side like chimpanzees do when they walk bipedally. These evolutionary changes in the pelvis and associated muscles account for the smooth, efficient stride of a human as compared to the awkward, shuffling gait of a chimpanzee or gorilla when it walks upright.



Figure 8.8 **Chimpanzee and Human Hip Bones.** Lateral views of the right hip bone. The human ilium forms a more bowl-like greater pelvis and is expanded posteriorly (toward page left) so that the gluteus maximus muscle produces an effective backswing of the thigh during the stride.

The pelvis is the most *sexually dimorphic* part of the skeleton—that is, the one whose anatomy most differs between the sexes. In identifying the sex of skeletal remains, forensic scientists focus especially on the pelvis. The average male pelvis is more robust (heavier and thicker) than the female's, owing to the forces exerted on the bone by stronger muscles. The female pelvis is adapted to the needs of pregnancy and childbirth. It is wider and shallower and has a larger pelvic inlet and outlet for passage of the infant's head. Table 8.1 and figure 8.9 summarize the most useful features of the pelvis in the sexual identification of skeletal remains.

Lower Limb

The number and arrangement of bones in the lower limb are similar to those of the upper limb. In the lower limb, however, they are adapted for weight bearing and locomotion and are therefore shaped and articulated differently. The lower limb is divided into four regions containing a total of 30 bones per limb:

1. The **femoral region,** or thigh, extends from hip to knee and contains the *femur.* The *patella* (kneecap) is a sesamoid bone at the junction of the femoral and crural regions.
2. The **crural** (CROO-rul) **region,** or leg proper, extends from knee to ankle and contains two bones, the medial *tibia* and lateral *fibula.*
3. The **tarsal region (tarsus),** or ankle, is the union of the crural region with the foot. The tarsal bones are treated as part of the foot.
4. The **pedal region (pes),** or foot, is composed of 7 *tarsal bones,* 5 *metatarsals,* and 14 *phalanges* in the toes.

Femur

The **femur** (FEE-mur) is the longest and strongest bone of the body, measuring about one-quarter of one's height (fig. 8.10). It has a hemispherical head that articulates with the acetabulum of the pelvis, forming a quintessential *ball-and-socket joint.* A ligament extends from the acetabulum to a pit, the **fovea capitis**[35] (FOE-vee-uh CAP-ih-tiss), in the head of the femur. Distal to the head is a constricted **neck,** a common site of femoral fractures

---

[35] *fovea* = pit; *capitis* = of the head

TABLE 8.1 Comparison of the Male and Female Pelvis

Feature	Male	Female
General appearance	More massive; rougher; heavier processes	Less massive; smoother; more delicate processes
Tilt	Upper end of pelvis relatively vertical	Upper end of pelvis tilted forward
Depth of greater pelvis	Deeper; ilium projects farther above sacroiliac joint	Shallower; ilium does not project as far above sacroiliac joint
Width of greater pelvis	Hips less flared; anterior superior spines closer together	Hips more flared; anterior superior spines farther apart
Pelvic inlet	Heart-shaped	Round or oval
Pelvic outlet	Smaller	Larger
Subpubic angle	Narrower, usually 90° or less	Wider, usually greater than 100°
Pubic symphysis	Taller	Shorter
Body of pubis	More triangular	More rectangular
Greater sciatic notch	Narrower	Wider
Obturator foramen	Rounder	More oval to triangular
Acetabulum	Larger, faces more laterally	Smaller, faces slightly anteriorly
Sacrum	Narrower and deeper	Wider and shallower
Coccyx	Less movable; more vertical	More movable; tilted posteriorly


Male
Female
Narrow greater sciatic notch
Tall pubic symphysis
Wide greater sciatic notch
Short pubic symphysis
Deep greater pelvis
Narrow sacrum
Triangular body of pubis
Shallow greater pelvis
Wide sacrum
Rectangular body of pubis
Narrow subpubic angle
Wide subpubic angle

© David Hunt/Specimens from the National Museum of Natural History, Smithsonian Institution

© VideoSurgery/Science Source

© David Hunt/Specimens from the National Museum of Natural History, Smithsonian Institution

© VideoSurgery/Science Source

Figure 8.9 **Comparison of Male and Female Pelvic Girdles.** Top: Medial views of hip bone. Bottom: Anterior views of pelvic girdle. Compare table 8.1.


Fovea capitis
Greater trochanter
Head
Greater trochanter
Neck
Intertrochanteric line
Intertrochanteric crest
Lesser trochanter
Spiral line
Gluteal tuberosity
Linea aspera
Shaft
Medial supracondylar line
Lateral supracondylar line
Popliteal surface
Lateral epicondyle
Medial epicondyle
Lateral epicondyle
Patellar surface
Lateral condyle
Medial condyle
Intercondylar fossa
Base of patella
Articular facets
Apex of patella
(a) Anterior view
(b) Posterior view

Figure 8.10 The Right Femur and Patella.

- *How many articular surfaces can you identify on the femur? Where are they?* AP|R

(see Deeper Insight 8.2 and fig. 8.11). Just beyond the neck are two massive, rough processes called the **greater** and **lesser trochanters**[36] (tro-CAN-turs), which are insertions for the powerful muscles of the hip. The trochanters are connected on the posterior side by a thick oblique ridge of bone, the **intertrochanteric crest,** and on the anterior side by a more delicate **intertrochanteric line.**

The primary feature of the shaft is a posterior ridge called the **linea aspera**[37] (LIN-ee-uh ASS-peh-ruh). At its upper end, the linea aspera forks into a medial **spiral line** and a lateral **gluteal tuberosity.** The gluteal tuberosity is a rough ridge (sometimes a depression) that serves for attachment of the gluteus maximus muscle. At its lower end, the linea aspera forks into **medial** and **lateral supracondylar lines,** which continue down to the respective epicondyles.

The distal end of the femur flares into **medial** and **lateral epicondyles,** the widest points of the femur at the knee. These and the supracondylar lines are attachments for certain thigh and leg muscles and knee ligaments. Distal to these are two smooth round surfaces of the knee joint, the **medial** and **lateral condyles,** separated by a groove called the **intercondylar** (IN-tur-CON-dih-lur) **fossa.** During knee flexion and extension, the condyles rock on the superior surface of the tibia. On the anterior side of the femur, a smooth medial depression called the **patellar surface** articulates with the patella. On the posterior side is a flat or slightly depressed area called the **popliteal surface.**

---

[36] *trochanter* = to run

[37] *linea* = line; *asper* = rough

DEEPER INSIGHT 8.2

Femoral Fractures

The femur is a very strong bone, well guarded by the thigh muscles, and it is not often fractured. Nevertheless, it can break in high-impact trauma suffered in automobile and equestrian accidents, figure skating falls, and so forth. If a person in an automobile collision has the feet braced against the floor or brake pedal with the knees locked, the force of impact is transmitted up the shaft and may fracture the shaft or neck of the femur (fig. 8.11). Comminuted and spiral fractures of the shaft can take up to a year to heal.

A "broken hip" is usually a fracture of the femoral neck, the weakest part of the femur. Elderly people often break the femoral neck when they stumble or are knocked down—especially women whose femurs are weakened by osteoporosis. Fractures of the femoral neck heal poorly because this is an anatomically unstable site and it has an especially thin periosteum with limited potential for ossification. In addition, fractures in this site often break blood vessels and cut off blood flow, resulting in degeneration of the head *(posttraumatic avascular necrosis).*



Figure 8.11 **Fractures of the Femur.** Violent trauma, as in automobile accidents, may cause spiral fractures of the femoral shaft. The femoral neck often fractures in elderly people as a result (or cause) of falls.

Although the femurs of apes are nearly vertical, in humans they angle medially from the hip to the knee (fig. 8.12). This places our knees closer together, beneath the body's center of gravity. We lock our knees when standing (see p. 213), allowing us to maintain an erect posture with little muscular effort. Apes cannot do this, and they cannot stand on two legs for very long without tiring—much as you would if you tried to maintain an erect posture with your knees slightly bent.

Patella

The **patella,**[38] or kneecap (see fig. 8.10), is a roughly triangular sesamoid bone embedded in the tendon of the knee. It is cartilaginous at birth and ossifies at 3 to 6 years of age. It has a broad superior **base,** a pointed inferior **apex,** and a pair of shallow **articular facets** on its posterior surface where it articulates with the femur. The lateral facet is usually larger than the medial. The *quadriceps femoris tendon* extends from the anterior *quadriceps femoris muscle* of the thigh to the patella, then continues as the *patellar ligament* from the patella to the tibia.



Figure 8.12 **Adaptation of the Lower Limb for Bipedalism.** In contrast to chimpanzees, which are quadrupedal, humans have the femurs angled medially so the knees are more nearly below the body's center of gravity.

---

[38] *pat* = pan; *ella* = little

This is a change in terminology more than a change in structure or function, as a tendon connects muscle to bone and a ligament connects bone to bone. Because of the way the quadriceps tendon loops over the patella, the patella modifies the direction of pull by the quadriceps muscle and improves its efficiency in extending the knee.

Tibia

The leg has two bones—a thick strong tibia (TIB-ee-uh) on the medial side and a slender fibula (FIB-you-luh) on the lateral side (fig. 8.13). The **tibia**[39] is the only weight-bearing bone of the crural region. Its broad superior head has two fairly flat articular surfaces, the **medial** and **lateral condyles,** separated by a ridge called the **intercondylar eminence.** The condyles of the tibia articulate with those of the femur. The rough anterior surface of the tibia, the **tibial tuberosity,** can be palpated just below the patella. This is where the patellar ligament inserts and the quadriceps muscle exerts its pull when it extends the leg. Distal to this, the shaft has a sharply angular **anterior border,** which can be palpated in the shin region. At the ankle, just above the rim of a standard dress shoe, you can palpate a prominent bony knob on each side. These are the **medial** and **lateral malleoli**[40] (MAL-ee-OH-lie). The medial malleolus is part of the tibia, and the lateral malleolus is part of the fibula.

Fibula

The **fibula**[41] (fig. 8.13) is a slender lateral strut that helps to stabilize the ankle. It does not bear any of the body's weight; indeed, orthopedic surgeons sometimes remove part of the fibula and use it to replace damaged or missing bone elsewhere in the body. The fibula is somewhat thicker and broader at its proximal end, the **head,** than at the distal end. The point of the head is called the **apex.** The distal expansion is the lateral malleolus. The fibula is joined to the tibia by a ligament called the *interosseous membrane,* similar to the one that joins the ulna and radius, and by shorter ligaments at the superior and inferior ends where the head and apex contact the tibia.

The Ankle and Foot

The **tarsal bones** of the ankle are arranged in proximal and distal groups somewhat like the carpal bones of the wrist (fig. 8.14). Because of the load-bearing role of the ankle, however, their shapes and arrangement are conspicuously different from those of the carpal bones, and they are thoroughly integrated into the structure of the foot. The largest tarsal bone is the



(a) Anterior view (b) Posterior view

Figure 8.13 The Right Tibia and Fibula. AP|R

---

[39] *tibia* = shinbone

[40] *malle* = hammer; *olus* = little

[41] *fib* = pin; *ula* = little


Distal phalanx I
Proximal phalanx I
Metatarsal
I
II
III
IV
V
Distal phalanx V
Middle phalanx V
Proximal phalanx V
Medial cuneiform
Intermediate cuneiform
Lateral cuneiform
Navicular
Talus
Trochlear surface of talus
Cuboid
Calcaneus
Tuberosity of calcaneus
V
IV
III
II
I
Head
Body
Base
Phalanges
Metatarsal bones
Tarsal bones
Key to tarsal bones
🟩 Distal group
🟨 Proximal group

(a) Superior (dorsal) view **(b) Inferior (plantar) view**


Navicular
Talus
Trochlear surface
Metatarsals
Phalanges
Sesamoid bone
Cuneiforms
Calcaneus

(c) Medial view

Figure 8.14 **The Right Foot.**
- *In part (c), what one bone is least likely to be present in a year-old infant? Explain.*

calcaneus[42] (cal-CAY-nee-us), which forms the heel. Its posterior end is the point of attachment for the **calcaneal (Achilles) tendon** from the calf muscles. The second-largest tarsal bone, and the most superior, is the **talus.**[43] It has three articular surfaces: an inferoposterior one that articulates with the calcaneus, a superior **trochlear**[44] **surface** that articulates with the tibia, and an anterior surface that articulates with a short, wide tarsal bone called the **navicular.**[45] The talus, calcaneus, and navicular are considered the proximal row of tarsal bones.

The distal group forms a row of four bones. Proceeding from medial side to lateral, these are the **medial, intermediate,** and **lateral cuneiforms**[46] (cue-NEE-ih-forms) and the **cuboid.**[47] The cuboid is the largest.

Apply What You Know

The upper and lower limbs each contain 30 bones, yet we have 8 carpal bones in the upper limb and only 7 tarsal bones in the lower limb. What makes up the difference in the lower limb?

---

[42] *calc* = stone, chalk
[43] *talus* = ankle
[44] *trochle* = pully; *ar* = like
[45] *nav* = boat; *icul* = little; *ar* = like
[46] *cunei* = wedge; *form* = in the shape of
[47] *cub* = cube; *oid* = shaped

The remaining bones of the foot are similar in arrangement and name to those of the hand. The proximal **metatarsals**[48] are similar to the metacarpals. They are **metatarsals I** through **V** from medial to lateral, metatarsal I being proximal to the great toe. Note that roman numeral I represents the *medial* group of bones in the foot but the *lateral* group in the hand. In both cases, however, it refers to the largest digit of the limb (see Deeper Insight 8.3). Metatarsals I through III articulate with the three cuneiforms; metatarsals IV and V articulate with the cuboid.

Bones of the toes, like those of the fingers, are called phalanges. The great toe is the **hallux** and contains only two bones, the proximal and distal phalanx I. The other toes each contain a proximal, middle, and distal phalanx. The metatarsal and phalangeal bones each have a base, body, and head, like the bones of the hand. All of them, especially the phalanges, are slightly concave on the inferior (plantar) side.

As important as the hand has been to human evolution, the foot may be an even more significant adaptation. Unlike other mammals, humans support their entire body weight on two feet. The tarsal bones are tightly articulated with each other, and the calcaneus is strongly developed. The hallux is not opposable as it is in most Old World monkeys and apes (fig. 8.15)—that is, humans cannot effectively grasp objects with the great toe—but it is highly developed so that it provides the "toe-off" that pushes the body forward in the last phase of the stride. For this reason, loss of the hallux has a more crippling effect than the loss of any other toe.

Although apes are flat-footed, humans have strong, springy foot arches that distribute the body's weight between the heels and the heads of the metatarsal bones and absorb stress as the body jostles up and down during walking and running (fig. 8.16). The **medial longitudinal arch,** which essentially extends from heel to hallux, is formed from the calcaneus, talus, navicular, cuneiforms, and metatarsals I through III. It is normally well above the ground, as evidenced by the shape of a wet footprint.

DEEPER INSIGHT 8.3

Anatomical Position—Clinical and Biological Perspectives

It may seem puzzling that we count metacarpal bones I through V from lateral to medial, but count metatarsal bones I through V from medial to lateral. This minor point of confusion is the legacy of a committee of anatomists who met in the early 1900s to define anatomical position. A controversy arose as to whether the arms should be presented with the palms forward or facing the rear in anatomical position. Veterinary anatomists argued that palms to the rear (forearms pronated) would be a more natural position comparable to forelimb orientation in other animals. It is more comfortable to stand with the forearms pronated, and when a child crawls on all fours, he or she does so with the palms on the floor, in the pronated position. In this animal-like stance, the largest digits (thumbs and great toes) are medial on all four limbs. Human clinical anatomists, however, argued that if you ask patients to "show me your arms" or "show me your hands," most present the palms forward or upward—that is, supinated. The clinical anatomists won the debate, forcing us, the heirs to this terminology, to number the hand and foot bones in a biologically less rational order.

A few other anatomical terms also reflect less than perfect logic. The *dorsum* of the foot is its superior surface—it does not face dorsally—and the *dorsal artery* and *dorsal nerve* of the penis lie along the surface that faces anteriorly (ventrally) (see fig. 26.9, p. 713). In a cat, dog, or other quadrupedal mammal, however, the dorsum of the foot and the dorsal artery and nerve of the penis do face dorsally (upward). However illogical some of these terms may seem, we inherit them from comparative anatomy and the habit of naming human structures after the corresponding structures in other species.



Figure 8.15 **Some Adaptations of the Foot for Bipedalism.** The great toe (hallux) of the chimpanzee is prehensile—able to encircle and grasp objects. The human great toe is nonprehensile but is more robust and is adapted for the toe-off part of the long bipedal stride.

---

[48] *meta* = beyond; *tars* = ankle



© Medical Body Scans/Science Source

(a) Inferior (plantar) view **(b) X-ray of right foot, lateral view**

Figure 8.16 Arches of the Foot.

The **lateral longitudinal arch** extends from heel to little toe and includes the calcaneus, cuboid, and metatarsals IV and V. The **transverse arch** includes the cuboid, cuneiforms, and proximal heads of the metatarsals. These arches are held together by short, strong ligaments. Excessive weight, repetitious stress, or congenital weakness of these ligaments can stretch them, resulting in *pes planus* (commonly called flat feet or fallen arches). This condition makes a person less tolerant of prolonged standing and walking.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

7. Name the bones of the adult pelvic girdle. What three bones of a child fuse to form the hip bone of an adult?
8. Name any four structures of the pelvis that you can palpate, and describe where to palpate them.
9. Describe several ways in which the male and female pelvic girdles differ.
10. What parts of the femur are involved in the hip joint? What parts are involved in the knee joint?
11. Name the prominent knobs on each side of your ankle. What bones contribute to these structures?
12. Name all the bones that articulate with the talus and describe the location of each.
13. Describe several ways in which the human and ape pelvis and hindlimb differ, and the functional reason for the differences.

8.3 Developmental and Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the pre- and postnatal development of the appendicular skeleton; and
b. describe some common disorders of the appendicular skeleton.

Development of the Appendicular Skeleton

With few exceptions, the bones of the limbs and their girdles arise by endochondral ossification. Exceptions include the clavicle, which forms primarily by intramembranous ossification, and sesamoid bones (the pisiform and patella). Although limb and limb girdle ossification is well under way at the time of birth, it is not completed until a person is in his or her 20s.

The first sign of limb development is the appearance of upper **limb buds** around day 26 to 27 and lower limb buds 1 or 2 days later. A limb bud consists of a core of mesenchyme covered with ectoderm. The limb buds elongate as the mesenchyme proliferates. The distal ends of the limb buds flatten into paddlelike **hand** and **foot plates.** By day 38 in the hand and day 44 in the foot, these plates show parallel ridges called **digital rays,** the future fingers and toes. The mesenchyme between the digital rays breaks down by apoptosis, forming notches between the rays that deepen until, at the end of week 8, the digits are well separated.

Condensed mesenchymal models of the future limb bones first appear during week 5. Chondrification is apparent by the end of that week, and by the end of week 6, a complete cartilaginous limb skeleton is present. The long bones begin to ossify in the following week, in the manner described in chapter 6 (see fig. 6.9, p. 141). The humerus, radius, ulna, femur, and tibia develop primary ossification centers in weeks 7 to 8; the scapula and ilium in week 9; the metacarpals, metatarsals, and phalanges over the next 3 weeks; and the ischium and pubis in weeks 15 and 20, respectively. The clavicle ossifies intramembranously beginning early in week 7.

The carpal bones are still cartilaginous at birth. Some of them ossify as early as 2 months of age (the capitate) and some as late as 9 years (the pisiform). Among the tarsal bones, the calcaneus and talus begin to ossify prenatally at 3 and 6 months, respectively; the cuboid begins to ossify just before or after birth; and the cuneiforms do not ossify until 1 to 3 years of age. The patella ossifies at 3 to 6 years. The epiphyses of the long bones are cartilaginous at birth, with their secondary ossification centers just beginning to form. The epiphyseal plates persist until about age 20, at which time the epiphysis and diaphysis fuse and bone elongation ceases. The ilium, ischium, and pubis are not fully fused into a single hip bone until the age of 25.

It may seem curious that the largest digits (the thumb and great toe) are lateral in the hand but medial in the foot, and that the elbows and knees flex in opposite directions. This results from a rotation of the limbs that occurs in week 7. Early that week, the limbs extend anteriorly from the body, the hand plate shows the first traces of separation of the finger buds, and the foot is still a relatively undifferentiated foot plate (fig. 8.17a). The future thumb and great toe are both directed superiorly, and the future palms and soles face each other medially. But then the limbs rotate about 90° in opposite directions. The upper limb rotates laterally. To visualize this, hold your hands straight out in front of you with the palms facing each other as if you were about to clap. Then rotate your forearms so the thumbs face away from each other (laterally) and the palms face upward. The lower limbs rotate in the opposite direction, medially, so that the soles face downward and the great toes become medial. Thus, the thumb and great toe end up on opposite sides of the hand and foot (fig. 8.17b). This rotation also explains why the elbow and knee flex in opposite directions, and why (as you will see in chapter 12) the muscles that flex the elbow are on the anterior side of the arm, but those that flex the knee are on the posterior side of the thigh.



(a) Seven weeks (b) Eight weeks

Figure 8.17 Embryonic Limb Rotation. In the seventh week of development, the forelimbs and hindlimbs of the embryo rotate about 90° in opposite directions. This explains why the largest digits (digit I) are on opposite sides of the hand and foot, and why the elbow and knee flex in opposite directions.

Pathology of the Appendicular Skeleton

The appendicular skeleton is subject to several developmental abnormalities, occurring in as many as 2 out of 1,000 live births. The most striking is **amelia,**[49] a complete absence of one or more limbs. The partial absence of a limb is called **meromelia.**[50] Meromelia typically entails an absence of the long bones, with rudimentary hands or feet attached directly to the trunk (see fig. 4.14, p. 103). Such defects are often accompanied by deformities of the heart, urogenital system, or craniofacial skeleton. These abnormalities are usually hereditary, but they can be induced by teratogenic chemicals such as thalidomide. The limbs are most vulnerable to teratogens in the fourth and fifth weeks of development.

Another class of developmental limb disorders includes **polydactyly,**[51] the presence of extra fingers or toes (fig. 8.18a), and **syndactyly,**[52] the fusion of two or more digits. The latter results from a failure of the digital rays to separate. *Cutaneous syndactyly,* most common in the foot, is the persistence of a skin web between the digits, and is relatively easy to correct surgically. *Osseous syndactyly* is fusion of the bones of the digits, owing to failure of the notches to form between the embryonic digital rays. Polydactyly and syndactyly are usually hereditary, but can also be induced by teratogens.

Clubfoot, or **talipes**[53] (TAL-ih-peez), is a congenital deformity in which the feet are adducted and plantar flexed (defined in chapter 9), with the soles turned medially (fig. 8.18b). This is a relatively common birth defect, present in about 1 out of 1,000 live births, but the cause remains obscure. It is sometimes hereditary, and some think it may also result from malposition of the fetus in the uterus, but the latter hypothesis remains unproven. Children with talipes cannot support their weight on their feet and tend to walk on their ankles. In some cases, talipes requires that the foot be manipulated and set in a new cast every week beginning in the neonatal nursery and lasting 4 to 6 months. Some cases require surgery at 6 to 9 months to release tight ligaments and tendons and realign the foot.

---

[49] *a* = without; *melia* = limb
[50] *mero* = part; *melia* = limb
[51] *poly* = many; *dactyl* = finger
[52] *syn* = together; *dactyl* = finger
[53] *tali* = heel; *pes* = foot


© SPL/Science Source

© Jim Stevenson/SPL/Science Source

(a) Polydactyly **(b) Talipes (clubfoot)**

Figure 8.18 **Congenital Deformities of the Hands and Feet.**

The most common noncongenital disorders of the appendicular skeleton are osteoporosis, fractures, dislocations, and arthritis. Even though these disorders can affect the axial skeleton as well, they are more common and more often disabling in the appendicular skeleton. The general classification of bone fractures is discussed in chapter 6, and some fractures specific to the appendicular skeleton are discussed in Deeper Insights 8.1 and 8.2 of this chapter. Arthritis, dislocation, and other joint disorders are described in chapter 9. Table 8.2 describes some other disorders of the appendicular skeleton.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

14. Describe the progression from a limb bud to a hand with fully formed and separated fingers.
15. Name some appendicular bones that do not ossify until a person is at least a few years old.
16. Distinguish between amelia and meromelia, and between polydactyly and syndactyly.

TABLE 8.2 **Disorders of the Appendicular Skeleton**

Avulsion	A fracture in which a body part, such as a finger, is completely torn from the body, as in many accidents with farm and factory machinery. The term can also refer to nonosseous structures such as the avulsion of an ear.
Calcaneal (heel) spurs	Abnormal outgrowths of the calcaneus. Often results from high-impact exercise such as aerobics and running, especially if done with inappropriate footwear. Stress on the plantar aponeurosis (a connective tissue sheet in the sole of the foot) stimulates exostosis, or growth of a bony spur, and can cause severe foot pain.
Colles[54] fracture	Pathological fracture at the distal end of the radius and ulna, often occurring when stress is placed on the wrist (as in pushing oneself up from an armchair) and the bones have been weakened by osteoporosis.
Epiphyseal fracture	Separation of the epiphysis from the diaphysis of a long bone. Common in children and adolescents because of their cartilaginous epiphyseal plates. May present a threat to normal completion of bone growth.
Pes planus[55]	"Flat feet" or "fallen arches" (absence of visible arches) in adolescents and adults. Caused by stretching of plantar ligaments due to prolonged standing or excess weight.
Pott[56] fracture	Fracture of the distal end of the tibia, fibula, or both; a sports injury common in football, soccer, and snow skiing.
Disorders Described Elsewhere	
Fracture of the clavicle 185	Fracture of the femur 196

---

[54] Abraham Colles (1773–1843), Irish surgeon
[55] *pes* = foot; *planus* = flat
[56] Sir Percivall Pott (1713–88), British surgeon

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

8.1 The Pectoral Girdle and Upper Limb (p. 185)

1. The function of the pectoral girdle; the bones that compose it; and all points at which these bones articulate with each other, with the upper limb, and with the axial skeleton
2. The anatomical features of the clavicle and scapula
3. The four segments (regions) of the upper limb
4. The names and locations of all 30 bones of the upper limb, and all points at which they articulate with each other
5. The anatomical features of the humerus, radius, ulna, carpal bones (especially the hamate), metacarpal bones, and phalanges
6. How the upper limb is anatomically adapted to the bipedalism of humans

8.2 The Pelvic Girdle and Lower Limb (p. 190)

1. The distinction between the pelvic girdle and pelvis
2. The function of the pelvic girdle; the bones that compose it; and all points at which these bones articulate with each other, with the lower limb, and with the axial skeleton
3. The anatomical features of the hip bone, and the names and boundaries of the three childhood bones from which it arises
4. The meaning of *greater pelvis, lesser pelvis, pelvic brim, pelvic inlet,* and *pelvic outlet,* and the relationship of these structures to pregnancy and childbirth
5. How the pelvic girdle and gluteal muscles are anatomically adapted to the bipedalism of humans
6. Differences between the male and female pelvic girdles
7. The four segments (regions) of the lower limb
8. The names and locations of all 30 bones of the lower limb, and all points at which they articulate with each other
9. The anatomical features of the femur, patella, tibia, fibula, talus, calcaneus, navicular, cuboid, cuneiforms, metatarsals, and phalanges
10. The names and landmarks of the three foot arches
11. How the lower limb is adapted to the bipedalism of humans, including the angle of the femurs, locking of the knees, the great toe, and the foot arches

8.3 Developmental and Clinical Perspectives (p. 200)

1. What portions of the appendicular skeleton are formed by intramembranous and endochondral ossification
2. Development of the limb buds and the manner in which they differentiate into the limbs, especially the processes of hand and foot development
3. The developmental processes that result in opposite directions of knee and elbow flexion and opposite orientations of the pollex and hallux
4. Developmental abnormalities of the appendicular skeleton including amelia, meromelia, polydactyly, syndactyly, and talipes
5. The most common noncongenital disorders of the appendicular skeleton

Testing Your Recall

1. The hip bone is attached to the axial skeleton through its
   a. auricular surface.
   b. articular cartilage.
   c. pubic symphysis.
   d. conoid tubercle.
   e. coronoid process.
2. Which of these bones supports the most body weight?
   a. ilium
   b. pubis
   c. femur
   d. tibia
   e. talus
3. Which of these structures can be most easily palpated on a living person?
   a. the deltoid tuberosity
   b. the greater sciatic notch
   c. the medial malleolus
   d. the coracoid process of the scapula
   e. the glenoid cavity
4. Compared to the male pelvis, the pelvis of a female
   a. has a less movable coccyx.
   b. has a rounder pelvic inlet.
   c. is narrower between the iliac crests.
   d. has a narrower pubic arch.
   e. has a narrower sacrum.
5. The lateral and medial malleoli are most similar to
   a. the radial and ulnar styloid processes.
   b. the humeral capitulum and trochlea.
   c. the acromion and coracoid process.
   d. the base and head of a metacarpal bone.
   e. the anterior and posterior superior iliac spines.
6. When you rest your hands on your hips, you are resting them on
   a. the pelvic inlet.
   b. the pelvic outlet.
   c. the pelvic brim.
   d. the iliac crests.
   e. the auricular surfaces.
7. The disc-shaped head of the radius articulates with the _____ of the humerus.
   a. radial tuberosity
   b. trochlea
   c. capitulum
   d. olecranon process
   e. glenoid cavity
8. All of the following are carpal bones *except* the _____, which is a tarsal bone.
   a. trapezium
   b. cuboid
   c. trapezoid
   d. triquetrum
   e. pisiform
9. The bone that supports your body weight when you are sitting down is
   a. the acetabulum.
   b. the pubis.
   c. the ilium.
   d. the coccyx.
   e. the ischium.
10. Which of these is the bone of the heel?
    a. cuboid
    b. calcaneus
    c. navicular
    d. trochlear
    e. talus

11. The Latin anatomical name for the thumb is _____, and the name for the great toe is _____.
12. The acromion and coracoid process are parts of what bone?
13. How many phalanges, total, does the human body have?
14. The bony prominences on each side of your elbow are the lateral and medial _____ of the humerus.
15. One of the wrist bones, the _____, is characterized by a prominent hook.
16. The fibrocartilage pad that holds the pelvic girdle together anteriorly is called the _____.
17. The leg proper, between the knee and ankle, is called the _____ region.
18. The _____ processes of the radius and ulna form bony protuberances on each side of the wrist.
19. Two massive protuberances unique to the proximal end of the femur are the greater and lesser _____.
20. The _____ arch of the foot extends from the heel to the great toe.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning for each of the following word elements, and give a term in which it is used.

1. pect-
2. acro-
3. -icle
4. supra-
5. carpo-
6. capit-
7. -ulum
8. meta-
9. auro-
10. tarso-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. There are more carpal bones than tarsal bones.
2. The hands have more phalanges than the feet.
3. The upper limb is attached to the axial skeleton at only one point, the acromioclavicular joint.
4. On a living person, it would be possible to palpate the muscles in the infraspinous fossa but not those of the subscapular fossa.
5. In strict anatomical terminology, the words *arm* and *leg* both refer to regions with only one bone.
6. If you rest your chin on your hands with your elbows on a table, the olecranon of the ulna rests on the table.
7. The most frequently broken bone in humans is the humerus.
8. The proximal end of the radius articulates with both the humerus and ulna.
9. The pisiform bone and patella are both sesamoid bones.
10. The pelvic outlet is the opening in the floor of the greater pelvis leading into the lesser pelvis.

Answers in appendix A

Testing Your Comprehension

1. In adolescents, trauma sometimes separates the head of the femur from the neck. Why do you think this is more common in adolescents than in adults?
2. By palpating the hind leg of a cat or dog or examining a laboratory skeleton, you can see that cats and dogs stand on the heads of their metatarsal bones; the calcaneus does not touch the ground. How is this similar to the stance of a woman wearing high-heeled shoes? How is it different?
3. A deer hunter discovers a human skeleton in the woods and notifies authorities. A news report on the finding describes it as the body of an unidentified male between 17 and 20 years of age. What skeletal features would have been most useful for determining the sex and approximate age of the individual?
4. A surgeon has removed 8 cm of Joan's radius because of osteosarcoma, a bone cancer, and replaced it with a graft taken from one of the bones of Joan's lower limb. What bone do you think would most likely be used as the source of the graft? Explain your answer.
5. Andy, a 55-year-old, 75 kg (165-pound) roofer, is shingling the steeply pitched roof of a new house when he loses his footing and slides down the roof and over the edge, feet first. He braces himself for the fall, and when he hits the ground, he cries out and doubles up in excruciating pain. Emergency medical technicians called to the scene tell him he has broken his hips. Describe, more specifically, where his fractures most likely occurred. On the way to the hospital, Andy says, "You know it's funny, when I was a kid, I used to jump off roofs that high, and I never got hurt." Why do you think Andy was more at risk of a fracture as an adult than he was as a boy?

X-ray of an artificial knee joint (prosthesis)

© Dr. P. Marazzi/Getty Images

CHAPTER 9

THE SKELETAL SYSTEM IV
JOINTS

CHAPTER OUTLINE

9.1 Joints and Their Classification 206
- Bony Joints 206
- Fibrous Joints 206
- Cartilaginous Joints 208

9.2 Synovial Joints 209
- General Anatomy 210
- Classes of Synovial Joints 210
- Movements of Synovial Joints 213
- Range of Motion 219

9.3 Anatomy of Selected Synovial Joints 220
- The Jaw Joint 220
- The Shoulder Joint 221
- The Elbow Joint 223
- The Hip Joint 224
- The Knee Joint 225
- The Ankle Joint 228

9.4 Clinical Perspectives 230
- Arthritis 230
- Joint Prostheses 231

Study Guide 232

DEEPER INSIGHTS

9.1 Exercise and Articular Cartilage 210
9.2 TMJ Syndrome 220
9.3 Pulled Elbow 224
9.4 Knee Injuries and Arthroscopic Surgery 227

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:

- Anatomical planes (p. 12)
- The distinction between hyaline cartilage and fibrocartilage (p. 69)
- Anatomy of the skeletal system (chapters 7 and 8)

Anatomy & Physiology REVEALED®
aprevealed.com

Module 5: Skeletal System

Joints, or articulations, link the bones of the skeletal system into a functional whole—a system that supports the body, permits effective movement, and protects the softer organs. Joints such as the shoulder, elbow, and knee are remarkable specimens of biological design—self-lubricating, almost frictionless, and able to bear heavy loads and withstand compression while executing smooth and precise movements. Yet, it is equally important that other joints be less movable or even immobile. Such joints are better able to support the body and protect delicate organs. The vertebral column, for example, is only moderately mobile, for it must allow for flexibility of the torso and yet protect the delicate spinal cord and support much of the body's weight. Bones of the cranium must protect the brain and sense organs, but need not allow for movement (except during birth); thus, they are locked together by immobile joints, the sutures studied in chapter 7.

In everyday life, we take the greatest notice of the most freely movable joints of the limbs, and it is here that people feel most severely compromised by disabling diseases such as arthritis. Much of the work of physical therapists focuses on limb mobility. In this chapter, we will survey all types of joints, from the utterly immobile to the most mobile, but with an emphasis on the latter. This survey of joint anatomy and movements will provide a foundation for the study of muscle actions in chapters 11 and 12.

9.1 Joints and Their Classification

Expected Learning Outcomes

When you have completed this section, you should be able to

a. explain what joints are, how they are named, and what functions they serve;
b. name and describe the four major classes of joints;
c. name some joints that become solidly fused by bone as they age;
d. describe the three types of fibrous joints and give an example of each;
e. distinguish between the three types of sutures; and
f. describe the two types of cartilaginous joints and give an example of each.

Any point where two bones meet is called a **joint (articulation),** whether or not the bones are movable at that interface. The science of joint structure, function, and dysfunction is called **arthrology.**[1] The study of musculoskeletal movement is **kinesiology**[2] (kih-NEE-see-OL-oh-jee). This is a branch of **biomechanics,** which deals with a broad variety of movements and mechanical processes in the body, including the physics of blood circulation, respiration, and hearing.

The name of a joint is typically derived from the names of the bones involved. For example, the *atlanto–occipital joint* is where the atlas meets the occipital condyles, the *glenohumeral joint* is where the glenoid cavity of the scapula meets the humerus, and the *radioulnar joint* is where the radius meets the ulna.

Joints can be classified according to the manner in which the adjacent bones are bound to each other, with corresponding differences in how freely the bones can move. Authorities differ in their classification schemes, but one common view places the joints in four major categories: *bony, fibrous, cartilaginous,* and *synovial joints.* This section will describe the first three of these and the subclasses of each. The remainder of the chapter will then be concerned primarily with synovial joints.

Bony Joints

A **bony joint,** or **synostosis**[3] (SIN-oss-TOE-sis), is an immobile joint formed when the gap between two bones ossifies and they become, in effect, a single bone. Bony joints can form by ossification of either fibrous or cartilaginous joints. An infant is born with right and left frontal and mandibular bones, for example, but these soon fuse seamlessly to form single bones. In old age, some cranial sutures become obliterated by ossification, and the adjacent cranial bones, such as the parietal bones, fuse. The epiphyses and diaphyses of the long bones are joined by cartilaginous joints in childhood and adolescence, and these become synostoses in early adulthood. The attachment of the first rib to the sternum also becomes a synostosis with age.

Fibrous Joints

A **fibrous joint** is also called a **synarthrosis**[4] (SIN-ar-THRO-sis) or **synarthrodial joint.** It is a point at which adjacent bones are bound by collagen fibers that emerge from the matrix of one bone, cross the space between them, and penetrate into the matrix of the other (fig. 9.1). There are three kinds of fibrous joints: *sutures, gomphoses,* and *syndesmoses.* In sutures and gomphoses, the fibers are very short and allow for little or no movement. In syndesmoses, the fibers are longer and the attached bones are more movable.

Sutures

Sutures are immobile or only slightly mobile fibrous joints that closely bind the bones of the skull to each other; they occur nowhere else. In chapter 7, we did not take much notice of the differences between one suture and another, but some differences might have caught your attention as you studied the diagrams in that chapter or examined laboratory specimens. Sutures can be classified as *serrate, lap,* and *plane sutures.* Readers with some knowledge of woodworking may recognize that the structures and functional properties of these sutures have something in common with basic types of carpentry joints (fig. 9.2).

---

[1] *arthro* = joint; *logy* = study of
[2] *kinesio* = movement; *logy* = study of
[3] *syn* = together; *ost* = bone; *osis* = condition
[4] *syn* = together; *arthr* = joined; *osis* = condition

Figure 9.1 **Fibrous Joints.** (a) A suture between the parietal bones. (b) A gomphosis between a tooth and the jaw. (c) A syndesmosis between the tibia and fibula.

- *Which of these is* not *a joint between two bones? Why?*


Fibrous connective tissue
(a) Suture
(b) Gomphosis
(c) Syndesmosis

Figure 9.2 **Sutures.** Serrate, lap, and plane sutures compared to some common wood joints.


Serrate suture
Lap suture
Plane suture
Bone
Wood
Dovetail joint
Miter joint
Butt joint

A **serrate suture** is one in which the adjoining bones firmly interlock by their serrated margins, like pieces of a jigsaw puzzle. It is analogous to a dovetail wood joint. On the surface, it appears as a wavy line between the two bones, as we see in the coronal, sagittal, and lambdoid sutures that border the parietal bones.

A **lap (squamous) suture** is one in which the adjacent bones have overlapping beveled edges, like a miter joint in carpentry. An example is the squamous suture that encircles most of the temporal bone. Its beveled edge can be seen in figure 7.10b (p. 161). On the surface, a lap suture appears as a relatively smooth (nonserrated) line.

A **plane (butt) suture** is one in which the adjacent bones have straight nonoverlapping edges. The two bones merely border each other, like two boards glued together in a butt joint. An example is seen in the intermaxillary suture in the roof of the mouth.

Gomphoses

Even though the teeth are not bones, the attachment of a tooth to its socket is classified as a **gomphosis** (gom-FOE-sis). The term refers to its similarity to a nail hammered into wood.[5] The tooth is held firmly in place by a fibrous **periodontal ligament,** which consists of collagen fibers that extend from the bone matrix of the jaw into the dental tissue (fig. 9.1b). The ligament allows the tooth to move or give a little under the stress of chewing. Along with associated nerve endings, this slight tooth movement enables us to sense how hard we are biting and to sense a particle of food stuck between the teeth.

Syndesmoses

A **syndesmosis**[6] (SIN-dez-MO-sis) is a fibrous joint at which two bones are bound by relatively long collagenous fibers. The separation between the bones and length of the fibers gives these joints more mobility than a suture or gomphosis. An especially movable syndesmosis exists between the shafts of the radius and ulna, which are joined by a broad fibrous *interosseous membrane.* This syndesmosis permits such movements as pronation and supination of the forearm. A less mobile syndesmosis is the one that binds the distal ends of the tibia and fibula together, side by side (fig. 9.1c).

Cartilaginous Joints

A **cartilaginous joint** is also called an **amphiarthrosis**[7] (AM-fee-ar-THRO-sis) or **amphiarthrodial joint.** In these joints, two bones are linked by cartilage (fig. 9.3). The two types of cartilaginous joints are *synchondroses* and *symphyses*.

Synchondroses

A **synchondrosis**[8] (SIN-con-DRO-sis) is a joint in which the bones are bound by hyaline cartilage. An example is the temporary joint between the epiphysis and diaphysis of a long bone in a child, formed by the cartilage of the epiphyseal plate. Another is the attachment of the first rib to the sternum by a hyaline costal cartilage (fig. 9.3a). (The other costal cartilages are joined to the sternum by synovial joints.)

Symphyses

In a **symphysis**[9] (SIM-fih-sis), two bones are joined by fibrocartilage (fig. 9.3b, c). One example is the pubic symphysis, in which the right and left pubic bones are joined by the cartilaginous interpubic disc. Another is the joint between the bodies of two vertebrae, united by an intervertebral disc. The surface of each vertebral body is covered with hyaline cartilage. Between the vertebrae, this cartilage becomes infiltrated with collagen bundles to form fibrocartilage. Each intervertebral disc permits only slight movement between adjacent vertebrae, but the collective effect of all 23 discs gives the spine considerable flexibility.

Apply What You Know

The intervertebral joints are symphyses only in the cervical through the lumbar region. How would you classify the intervertebral joints of the sacrum and coccyx in a middle-aged adult?

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. What is the difference between arthrology and kinesiology?
2. Explain the distinction between a synostosis, amphiarthrosis, and synarthrosis.
3. Give some examples of joints that become synostoses with age.
4. Define *suture, gomphosis,* and *syndesmosis,* and explain what these three joints have in common.
5. Name the three types of sutures and describe how they differ.
6. Name two synchondroses and two symphyses.

---

[5] *gomph* = nail, bolt; *osis* = condition
[6] *syn* = together; *desm* = band; *osis* = condition
[7] *amphi* = on all sides; *arthr* = joined; *osis* = condition
[8] *syn* = together; *chondr* = cartilage; *osis* = condition
[9] *sym* = together; *physis* = growth



Figure 9.3 **Cartilaginous Joints.** (a) A synchondrosis, represented by the costal cartilage joining rib 1 to the sternum. (b) The pubic symphysis. (c) Intervertebral discs, which join adjacent vertebrae to each other by symphyses.
- *What is the difference between the pubic symphysis and the interpubic disc?*

9.2 Synovial Joints

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the anatomy of a synovial joint and its associated structures;
b. describe the six types of synovial joints;
c. list and demonstrate the types of movements that occur at diarthroses; and
d. discuss the factors that affect the range of motion of a joint.

The most familiar type of joint is the **synovial** (sih-NO-vee-ul) **joint,** also called a **diarthrosis**[10] (DY-ar-THRO-sis) or **diarthrodial joint.** Ask most people to point out any joint in the body, and they are likely to point to a synovial joint such as the elbow, knee, or knuckles. Many synovial joints, like these examples, are freely movable. Others, such as the joints between the wrist and ankle bones and between the articular processes of the vertebrae, have more limited mobility. Synovial joints are the most structurally complex type of joint and are the most likely to develop uncomfortable and crippling dysfunctions.

---

[10] *dia* = separate, apart; *arthr* = jointed; *osis* = condition

General Anatomy

In synovial joints, the facing surfaces of the two bones are covered with **articular cartilage,** a layer of hyaline cartilage usually about 2 or 3 mm thick. These surfaces are separated by a narrow space, the **joint (articular) cavity,** containing a slippery lubricant called **synovial fluid** (fig. 9.4). This fluid, for which the joint is named, is rich in albumin and hyaluronic acid, which give it a viscous, slippery texture similar to raw eggwhite.[11] It nourishes the articular cartilages, removes their wastes, and makes movements at synovial joints almost friction-free. A connective tissue **joint (articular) capsule** encloses the cavity and retains the fluid. It has an outer **fibrous capsule** continuous with the periosteum of the adjoining bones, and an inner, cellular **synovial membrane.** The synovial membrane consists mainly of fibroblast-like cells that secrete the fluid, and is populated by macrophages that remove debris from the joint cavity.

In a few synovial joints, fibrocartilage grows inward from the joint capsule and forms a pad between the articulating bones. In the jaw and distal radioulnar joints, and at both ends of the clavicle (sternoclavicular and acromioclavicular joints), the pad crosses the entire joint capsule and is called an **articular disc** (see fig. 9.18c). In the knee, two cartilages extend inward from the left and right but do not entirely cross the joint (see fig. 9.23d). Each is called a **meniscus**[12] because of its crescent shape. These cartilages absorb shock and pressure, guide the bones across each other, improve the fit between the bones, and stabilize the joint, reducing the chance of dislocation.



Figure 9.4 **Structure of a Simple Synovial Joint.** Most synovial joints are more complex than the interphalangeal joint shown here.
• *Why is a meniscus unnecessary in an interphalangeal joint?*

Accessory structures associated with a synovial joint include tendons, ligaments, and bursae. A **tendon** is a strip or sheet of tough collagenous connective tissue that attaches a muscle to a bone. Tendons are often the most important structures in stabilizing a joint. A **ligament** is a similar tissue that attaches one bone to another. Several ligaments are named and illustrated in our later discussion of individual joints, and tendons are more fully considered in chapters 10 through 12 along with the gross anatomy of muscles.

A **bursa**[13] is a fibrous sac filled with synovial fluid, located between adjacent muscles, between bone and skin, or where a tendon passes over a bone (see fig. 9.19). Bursae cushion muscles, help tendons slide more easily over the joints, and sometimes enhance the mechanical effect of a muscle by modifying the direction in which its tendon pulls. Bursae called **tendon sheaths** are elongated cylinders wrapped around a tendon. These are especially numerous in the hand and foot (fig. 9.5), and allow easier longitudinal movement of a tendon as forearm muscles pull on bones of the hand. **Bursitis** is inflammation of a bursa, usually due to overexertion of a joint. **Tendinitis** is a form of bursitis in which a tendon sheath is inflamed.

Classes of Synovial Joints

There are six fundamental classes of synovial joints, distinguished by patterns of motion determined by the shapes of the articular surfaces of the bones (table 9.1). We will examine them here in descending order of mobility, from multiaxial to monaxial joints.

DEEPER INSIGHT 9.1

Exercise and Articular Cartilage

When synovial fluid is warmed by exercise, it becomes thinner (less viscous) and more easily absorbed by the articular cartilage. The cartilage then swells and provides a more effective cushion against compression. For this reason, a warm-up period before vigorous exercise helps protect the articular cartilage from undue wear and tear.

Because cartilage is nonvascular, its repetitive compression during exercise is important to its nutrition and waste removal. Each time a cartilage is compressed, fluid and metabolic wastes are squeezed out of it. When weight is taken off the joint, the cartilage absorbs synovial fluid like a sponge, and the fluid carries oxygen and nutrients to the chondrocytes. Lack of exercise causes the articular cartilages to deteriorate more rapidly from lack of nutrition, oxygenation, and waste removal.

Weight-bearing exercise builds bone mass and strengthens the muscles that stabilize many of the joints, thus reducing the risk of joint dislocations. Excessive joint stress, however, can hasten the progression of osteoarthritis (p. 230) by damaging the articular cartilage. Swimming is a good way of exercising the joints with minimal damage.

---

[11] *ovi* = egg
[12] *men* = moon, crescent; *iscus* = little
[13] *burs* = purse


Tendon of flexor carpi radialis
Tendon of flexor pollicis longus
Radial bursa (cut)
Tendons of flexor digitorum superficialis and flexor digitorum profundus
Ulnar bursa (cut)
Flexor retinaculum (cut)
Lumbrical muscles
Tendons of flexor digitorum superficialis
Tendon sheaths
Tendon sheath (opened)
Tendon of flexor digitorum superficialis
Tendon of flexor digitorum profundus

Figure 9.5 Tendon Sheaths and Other Bursae in the Hand and Wrist.

TABLE 9.1 Anatomical Classification of the Joints

Joint	Characteristics and Examples
Bony joint (synostosis)	Former fibrous or cartilaginous joint in which adjacent bones have become fused by ossification. Examples: median line of frontal bone; fusion of epiphysis and diaphysis of an adult long bone; and fusion of ilium, ischium, and pubis to form hip bone
Fibrous joint (synarthrosis)	Adjacent bones bound by collagen fibers extending from the matrix of one into the matrix of the other
Suture (figs. 9.1a and 9.2)	Immobile fibrous joint between cranial or facial bones
Serrate suture	Bones joined by a wavy line formed by interlocking teeth along the margins. Examples: coronal, sagittal, and lambdoid sutures
Lap suture	Bones beveled to overlap each other; superficial appearance is a smooth line. Example: squamous suture around temporal bone
Plane suture	Bones butted against each other without overlapping or interlocking. Example: palatine suture
Gomphosis (fig. 9.1b)	Insertion of a tooth into a socket, held in place by collagen fibers of periodontal ligament
Syndesmosis (fig. 9.1c)	Slightly movable joint held together by ligaments or interosseous membranes. Example: tibiofibular joint
Cartilaginous joint (amphiarthrosis)	Adjacent bones bound by cartilage
Synchondrosis (fig. 9.3a)	Bones held together by hyaline cartilage. Examples: articulation of rib 1 with sternum, and epiphyseal plate uniting the epiphysis and diaphysis of a long bone of a child
Symphysis (fig. 9.3b, c)	Slightly movable joint held together by fibrocartilage. Examples: intervertebral discs and pubic symphysis
Synovial joint (diarthrosis) (figs. 9.4 and 9.6)	Adjacent bones covered with hyaline articular cartilage, separated by lubricating synovial fluid and enclosed in a fibrous joint capsule
Ball-and-socket joint	Multiaxial diarthrosis in which a smooth hemispherical head of one bone fits into a cuplike depression of another. Examples: shoulder and hip joints
Condylar (ellipsoid) joint	Biaxial diarthrosis in which an oval convex surface of one bone articulates with an elliptical depression of another. Examples: radiocarpal and metacarpophalangeal joints
Saddle joint	Joint in which each bone surface is saddle-shaped (concave on one axis and convex on the perpendicular axis). Examples: trapeziometacarpal and sternoclavicular joints
Plane (gliding) joint	Usually a biaxial diarthrosis with slightly concave or convex bone surfaces that slide across each other. Examples: intercarpal and intertarsal joints; joints between the articular processes of the vertebrae
Hinge joint	Monaxial diarthrosis, able to flex and extend in only one plane. Examples: elbow, knee, and interphalangeal joints
Pivot joint	Joint in which a projection of one bone fits into a ringlike ligament of another, allowing one bone to rotate on its longitudinal axis. Examples: atlantoaxial joint and proximal radioulnar joint

A **multiaxial** joint is one that can move in any of the three fundamental mutually perpendicular planes (*x, y,* and *z*); a **biaxial** joint is able to move in only two planes; and a **monaxial** joint moves in only one plane. Ball-and-socket joints are the only multiaxial type; condylar, saddle, and plane joints are biaxial; and hinge and pivot joints are monaxial. As we see in figure 9.6, all six types of synovial joints have representatives in the upper limb.

1. **Ball-and-socket joints.** These are the shoulder and hip joints. In both cases, one bone (the humerus or femur) has a smooth hemispherical head that fits into a cuplike socket on the other (the glenoid cavity of the scapula or the acetabulum of the hip bone).
2. **Condylar (ellipsoid) joints.** These joints exhibit an oval convex surface on one bone that fits into a complementary depression on the other. The radiocarpal joint of the wrist and metacarpophalangeal (MET-uh-CAR-po-fah-LAN-jee-ul) joints at the bases of the fingers are examples. To demonstrate their biaxial motion, hold your hand with the palm facing you. Make a fist, and these joints flex in the sagittal plane. Fan your fingers apart, and they move in the frontal plane.
3. **Saddle joints.** Here, both bones have a saddle-shaped surface—concave in one direction (like the front to rear curvature of a horse's saddle) and convex in the other (like the left to right curvature of a saddle). The clearest example

Figure 9.6 **The Six Types of Synovial Joints.** All six have representatives in the forelimb. Mechanical models show the types of motion possible at each joint.


Ball-and-socket joint
(humeroscapular)
Head of humerus
Scapula
Humerus
Hinge joint
(humeroulnar)
Ulna
Pivot joint
(radioulnar)
Radius
Ulna
Plane joint
(intercarpal)
Carpal bones
Saddle joint
(trapeziometacarpal)
Carpal bone
Metacarpal bone
Condylar joint
(metacarpophalangeal)
Metacarpal
bone
Phalanx

of this is the trapeziometacarpal joint between the trapezium of the wrist and metacarpal I at the base of the thumb. Saddle joints are also biaxial. The thumb, for example, moves in a frontal plane when you spread the fingers apart, and in a sagittal plane when you move it as if to grasp a tool such as a hammer. This range of motion gives us and other primates that anatomical hallmark, the opposable thumb. Another saddle joint is the sternoclavicular joint, where the clavicle articulates with the sternum. The clavicle moves vertically in the frontal plane at this joint when you lift a suitcase, and moves horizontally in the transverse plane when you reach forward to push open a door.

4. **Plane (gliding) joints.** Here the bone surfaces are flat or only slightly concave and convex. The adjacent bones slide over each other and have relatively limited movement. Plane joints are found between the carpal bones of the wrist, the tarsal bones of the ankle, and the articular processes of the vertebrae. Their movements, although slight, are complex. They are usually biaxial. For example, when the head is tilted forward and back, the articular facets of the vertebrae slide anteriorly and posteriorly; when the head is tilted from side to side, the facets slide laterally. Although any one joint moves only slightly, the combined action of the many joints in the wrist, ankle, and vertebral column allows for a significant amount of overall movement.
5. **Hinge joints.** These are essentially monaxial joints, moving freely in one plane with very little movement in any other, like a door hinge. Examples occur at the elbow, knee, and interphalangeal (finger and toe) joints. In these cases, one bone has a convex (but not hemispherical) surface, such as the trochlea of the humerus and the condyles of the femur. This fits into a concave depression on the other bone, such as the trochlear notch of the ulna and the condyles of the tibia.
6. **Pivot joints.** These are monaxial joints in which a bone spins on its longitudinal axis. There are two principal examples: the radioulnar joint at the elbow and the atlantoaxial joint between the first two vertebrae. At the atlantoaxial joint, the dens of the axis projects into the vertebral foramen of the atlas and is held against its anterior arch by the transverse ligament (see fig. 7.24, p. 170). As the head rotates left and right, the skull and atlas pivot around the dens. At the radioulnar joint, the anular ligament of the ulna wraps around the neck of the radius. During pronation and supination of the forearm, the disclike radial head pivots like a wheel turning on its axle. The edge of the wheel spins against the radial notch of the ulna like a car tire spinning in snow.

Some joints cannot be easily classified into any one of these six categories. The jaw joint, for example, has some aspects of condylar, hinge, and plane joints. It clearly has an elongated condyle where it meets the temporal bone of the cranium, but it moves in a hingelike fashion when the mandible moves up and down in speaking, biting, and chewing; it glides slightly forward when the jaw juts (protracts) to take a bite; and it glides from side to side to grind food between the molars. The knee is a classic hinge joint, but has an element of the pivot type; when we lock our knees to stand more effortlessly, the femur pivots slightly on the tibia. The humeroradial joint (between humerus and radius) acts as a hinge joint when the elbow flexes and a pivot joint when the forearm pronates.

Movements of Synovial Joints

Kinesiology, physical therapy, and other medical and scientific fields have a specific vocabulary for the movements of synovial joints. The following terms form a basis for describing the muscle actions in chapters 11 and 12 and may also be indispensable to your advanced coursework or intended career. This section introduces the terms for joint movements, many of which are presented in pairs or groups with opposite or contrasting meanings. This section relies on familiarity with the three cardinal anatomical planes and the directional terms in chapter 1 (p. 12). All directional terms used here refer to a person in standard anatomical position. When one is in anatomical position, each joint is said to be in its **zero position.** Joint movements can be described as deviation from the zero position or returning to it.

Flexion and Extension

Flexion (fig. 9.7) is a movement that decreases a joint angle, usually in the sagittal plane. This is particularly common at hinge joints—for example, bending the elbow so that the arm and forearm go from a 180° angle to one of 90° or less. It occurs in other types of joints as well. If you hold out your hands with the palms up, flexion of the wrist tips your palms toward you. The meaning of *flexion* is perhaps least obvious in the ball-and-socket joints of the shoulder and hip. At the shoulder, it means to raise your arm as if pointing at something directly in front of you or to continue in that arc and point toward the sky. At the hip, it means to raise the thigh, for example to place your foot on the next higher step when ascending a flight of stairs.

Extension is a movement that straightens a joint and generally returns a body part to the zero position—for example, straightening the elbow, wrist, or knee, or returning the arm or thigh back to zero position. In stair climbing, both the hip and knee extend when lifting the body to the next higher step.

Extreme extension of a joint, beyond the zero position, is called **hyperextension**.[14] For example, if you hold your hand in front of you with the palm down, then raise the back of your hand as if you were admiring a new ring, you hyperextend the wrist (see the hand in fig. 9.10a). Hyperextension of the upper or lower limb means to move the limb to a position behind the frontal plane of the trunk, as in reaching around with your arm to take your wallet out of your hip pocket. Each backswing of the lower limb when you walk hyperextends the hip.

Flexion and extension occur at nearly all diarthroses, but hyperextension is limited to only a few. At most diarthroses, ligaments or bone structure prevents hyperextension.

Apply What You Know

Try hyperextending some of your synovial joints and list a few for which this is impossible.

---

[14] *hyper* = excessive, beyond normal



© McGraw-Hill Education. Timothy L. Vacula, photographer

© McGraw-Hill Education/Timothy L. Vacula, photographer

© McGraw-Hill Education/Timothy L. Vacula, photographer

© McGraw-Hill Education/Timothy L. Vacula, photographer

Figure 9.7 **Flexion and Extension.** (a) Flexion and extension of the elbow. (b) Flexion, extension, and hyperextension of the wrist. (c) Flexion and hyperextension of the shoulder. (d) Flexion and extension of the hip and knee.

Abduction and Adduction

Abduction[15] (ab-DUC-shun) (fig. 9.8a) is the movement of a body part in the frontal plane away from the midline of the body—for example, moving the feet apart to stand spread-legged, or raising an arm to one side of the body. **Adduction**[16] (fig. 9.8b) is movement in the frontal plane back toward the midline. Some joints can be **hyperadducted**, as when you stand with your ankles crossed, cross your fingers, or hyperadduct the shoulder to stand with your elbows straight and your hands clasped below your waist. You **hyperabduct** the arm if you raise it high enough to cross slightly over the front or back of your head.

Elevation and Depression

Elevation (fig. 9.9a) is a movement that raises a body part vertically in the frontal plane. **Depression** (fig. 9.9b) lowers a body part in the same plane. For example, to lift a heavy suitcase from the floor, you elevate your scapula; in setting it down again, you depress the scapula. These are also important jaw movements in biting.

Protraction and Retraction

Protraction[17] (fig. 9.10a) is the anterior movement of a body part in the transverse (horizontal) plane, and **retraction**[18] (fig. 9.10b)

---

[15] *ab* = away; *duc* = to lead or carry
[16] *ad* = toward; *duc* = to lead or carry
[17] *pro* = forward; *trac* = to pull or draw
[18] *re* = back; *trac* = to pull or draw



© McGraw-Hill Education/Timothy L. Vacula, photographer

© McGraw-Hill Education/Timothy L. Vacula, photographer

(a) Abduction

(b) Adduction

Figure 9.8 Abduction and Adduction.



© McGraw-Hill Education/Timothy L. Vacula, photographer

© McGraw-Hill Education/Timothy L. Vacula, photographer

(a) Elevation

(b) Depression

Figure 9.9 Elevation and Depression.



© McGraw-Hill Education/Timothy L. Vacula, photographer

© McGraw-Hill Education/Timothy L. Vacula, photographer

(a) Protraction

(b) Retraction

Figure 9.10 Protraction and Retraction.


© McGraw-Hill Education/Timothy L. Vacula, photographer

Figure 9.11 **Circumduction.**

is posterior movement. Your shoulder protracts, for example, when you reach in front of you to push a door open. It retracts when you return it to the resting (zero) position or pull the shoulders back to stand at military attention. Such exercises as rowing a boat, bench presses, and push-ups involve repeated protraction and retraction of the shoulders.

Circumduction

In **circumduction**[19] (fig. 9.11), one end of an appendage remains fairly stationary while the other end makes a circular motion. If an artist standing at an easel reaches forward and draws a circle on a canvas, she circumducts the upper limb; the shoulder remains stationary while the hand moves in a circle. A baseball player winding up for the pitch circumducts the upper limb in a more extreme "windmill" fashion. One can also circumduct an individual finger, the hand, the thigh, the foot, the trunk, and the head.

Apply What You Know

Choose any example of circumduction and explain why this motion is actually a sequence of flexion, abduction, extension, and adduction.

Rotation

In one sense, the term *rotation* applies to any bone turning around a fixed axis, as described earlier. But in the terminology of specific joint movements, **rotation** (fig. 9.12) is a movement in which a bone spins on its longitudinal axis. For example, if you stand with bent elbow and move your forearm to place your palm against your abdomen, your humerus spins in a motion called **medial (internal) rotation.** If you make the opposite action, so the forearm points away from the trunk, your humerus undergoes **lateral (external) rotation.** A tennis player's forehand and backhand strokes entail vigorous rotation of the humerus. If you are standing and turn your right foot so your toes are pointing away from your left foot, and then turn it so your toes are pointing toward your left foot, your femur undergoes lateral and medial rotation, respectively. Other examples are given in the ensuing discussions of forearm and head movements.

Supination and Pronation

Supination and pronation (fig. 9.13) are known primarily as forearm movements, but see also the later discussion of foot movements. **Supination**[20] (SOO-pih-NAY-shun) of the forearm is a movement that turns the palm to face anteriorly or upward; in anatomical position, the forearm is supinated and the radius is parallel to the ulna. **Pronation**[21] is the opposite movement, causing the palm to face posteriorly or downward and the radius to cross the ulna like an X. During these movements, the concave end of the disc-shaped head of the radius spins on the capitulum of the humerus, and the edge of the disc spins in the radial notch of the ulna. The ulna remains relatively stationary.

As an aid to remembering these terms, think of it this way: You are *prone* to stand in the most comfortable position, which is with the forearm *pronated.* But if you were holding a cup of *soup* in your palm, you would need to *supinate* the forearm to keep from spilling it.


© McGraw-Hill Education/Timothy L. Vacula, photographer

© McGraw-Hill Education/Timothy L. Vacula, photographer

(a) Medial (internal) rotation **(b) Lateral (external) rotation**

Figure 9.12 **Medial (Internal) and Lateral (External) Rotation.** Shows rotation of both the humerus and the femur.

---

[19] *circum* = around; *duc* = to lead or carry

[20] *supin* = to lay back

[21] *pron* = to bend forward



© McGraw-Hill Education/Timothy L. Vacula, photographer

(a) Supination



© McGraw-Hill Education/Timothy L. Vacula, photographer

(b) Pronation

Figure 9.13 **Supination and Pronation.** Note the way these forearm rotations affect the relationship of the radius and ulna. Relative positions of muscles, nerves, and blood vessels are similarly affected.

Chapter 12 describes the muscles that perform these actions. Of these, the *supinator* is the most powerful. Supination is the type of movement you would usually make with your right hand to turn a doorknob clockwise or to drive a screw into a piece of wood. The threads of screws and bolts are designed with the relative strength of the supinator in mind, so the greatest power can be applied when driving them with a screwdriver in the right hand.

We will now consider a few body regions that combine the foregoing motions or have unique movements and terminology.

Special Movements of the Head and Trunk

Flexion of the spine produces forward-bending movements, as in tilting the head forward or bending at the waist in a toe-touching exercise (fig. 9.14a). *Extension* of the spine straightens the trunk or neck, as in standing up or returning the head to a forward-looking zero position. *Hyperextension* is employed in looking toward the sky or bending over backward (fig. 9.14b).

Lateral flexion is tilting the head or the trunk to the right or left of the midline (fig. 9.14c). Twisting at the waist or turning the head is called **right rotation** or **left rotation** when the chest or the face turns to the right or left of the forward-facing zero position (fig. 9.14d, e). Powerful right and left rotation at the waist is important in baseball pitching, golf, discus throwing, and other sports.

Special Movements of the Mandible

Movements of the mandible are concerned especially with biting and chewing (fig. 9.15). Imagine taking a bite of raw carrot. Most people have some degree of overbite; at rest, the upper incisors (front teeth) overhang the lower ones. For effective biting, however, the chisel-like edges of the incisors must meet. In preparation to bite, we therefore *protract* the mandible to bring the lower incisors forward. After the bite is taken, we *retract* it. To actually take the bite, we must *depress* the mandible to open the mouth, then *elevate* it so the incisors can cut off the piece of food.

Next, to chew the food, we do not simply raise and lower the mandible as if hammering away at the food between the teeth; rather, we exercise a grinding action that shreds the food between the broad, bumpy surfaces of the premolars and molars. This entails a side-to-side movement of the mandible called **lateral excursion** (movement to the left or right of the zero position) and **medial excursion** (movement back to the median, zero position).

Special Movements of the Hand and Fingers

The hand moves anteriorly and posteriorly by flexion and extension of the wrist. It can also move in the frontal plane. **Radial flexion** tilts the hand toward the thumb, and **ulnar flexion** tilts it toward the little finger (fig. 9.16a, b). We often use such motions when waving hello to someone with a side-to-side wave of the hand, or when washing windows, polishing furniture, or keyboarding.

Movements of the fingers are more varied, especially those of the thumb (fig. 9.16c–e). *Flexion* of the fingers is curling them; *extension* is straightening them. Most people cannot hyperextend their fingers. Spreading the fingers apart is *abduction,* and bringing them together again so they touch along their surfaces is *adduction.*

The thumb is different, however, because in embryonic development it rotates nearly 90° from the rest of the hand.



© McGraw-Hill Education/Timothy L. Vacula, photographer

(a) Flexion

© McGraw-Hill Education/Timothy L. Vacula, photographer

(b) Hyperextension

© McGraw-Hill Education/Timothy L. Vacula, photographer

(c) Lateral flexion



© McGraw-Hill Education/Timothy L. Vacula, photographer

(d) Rotation

© McGraw-Hill Education/Timothy L. Vacula, photographer

(e) Right rotation

Figure 9.14 Movements of the Head and Trunk.
- *In rotation of the head (d), what bone spins on its axis?*



© McGraw-Hill Education/Timothy L. Vacula, photographer

(a) Protraction

© McGraw-Hill Education/Timothy L. Vacula, photographer

(b) Retraction



© McGraw-Hill Education/Timothy L. Vacula, photographer

(c) Lateral excursion

© McGraw-Hill Education/Timothy L. Vacula, photographer

(d) Medial excursion

Figure 9.15 Movements of the Mandible.



© McGraw-Hill Education/Timothy L. Vacula, photographer

(a) Radial flexion

© McGraw-Hill Education/Timothy L. Vacula, photographer

(b) Ulnar flexion

© McGraw-Hill Education/Timothy L. Vacula, photographer

(c) Abduction of fingers



© McGraw-Hill Education/Timothy L. Vacula, photographer

(d) Palmar abduction of thumb

© McGraw-Hill Education/Timothy L. Vacula, photographer

(e) Opposition of thumb

Figure 9.16 **Movements of the Hand and Fingers.** (a) Radial flexion of the wrist. (b) Ulnar flexion of the wrist. (c) Abduction of the fingers. The thumb position in this figure is called *radial abduction.* Parts (a) and (b) show adduction of the fingers. (d) Palmar abduction of the thumb. (e) Opposition of the thumb (reposition is shown in parts [a] and [b]).

If you hold your hand in a completely relaxed position (but not resting on a table), you will probably see that the plane that contains your thumb and index finger is about 90° to the plane that contains the index through little fingers. Much of the terminology of thumb movement therefore differs from that of the other four fingers. *Flexion* of the thumb is bending the joints so the tip of the thumb is directed toward the palm, and *extension* is straightening it. If you now place the palm of your hand on a tabletop with all five fingers parallel and touching, the thumb is extended. Keeping your hand there, if you move your thumb away from the index finger so they form a 90° angle (but both are on the plane of the table), the thumb movement is called **radial abduction.** Another movement, **palmar abduction,** moves the thumb away from the plane of the hand so it points anteriorly, as you would do if you were about to wrap your hand around a tool handle (fig. 9.16d). From either position—radial or palmar abduction—*adduction* of the thumb means to bring it back to touch the base of the index finger.

Two additional terms are unique to the thumb: **Opposition**[22] means to move the thumb to approach or touch the tip of other fingers (fig. 9.16e). **Reposition**[23] is the return to zero position.

Special Movements of the Foot

A few additional movement terms are unique to the foot (fig. 9.17). **Dorsiflexion** (DOR-sih-FLEC-shun) is a movement in which the toes are elevated, as one might do in applying toenail polish. In each step you take, the foot dorsiflexes as it comes forward. This prevents you from scraping your toes on the ground and results in the characteristic *heel strike* of human locomotion when the foot touches down in front of you. **Plantar flexion** is movement of the foot so the toes point downward, as in pressing the gas pedal of a car or standing on tiptoes. This motion also produces the *toe-off* in each step you take, as the heel of the foot behind you lifts off the ground. Plantar flexion can be a very powerful motion, epitomized by high jumpers and the jump shots of basketball players.

Inversion[24] is a foot movement that tips the soles medially, somewhat facing each other, and **eversion**[25] is a movement that tips them laterally, away from each other. These movements are common in fast sports such as tennis and football, and sometimes cause ankle sprains. These terms also refer to congenital deformities of the feet, which are often corrected by orthopedic shoes or braces.

Pronation and *supination,* while used mainly for forearm movements, also apply to the feet but refer here to a more complex combination of movements. Pronation of the foot is a combination of dorsiflexion, eversion, and abduction—that is, the toes are elevated and turned away from the other foot and the sole is tilted away. Supination of the foot is a combination of plantar flexion, inversion, and adduction—the toes are lowered and turned toward the other foot and the sole is tilted toward it. These may seem a little difficult to visualize and perform, but they are ordinary motions in walking, running, ballet, and crossing uneven surfaces such as stepping stones.

You can perhaps understand why these terms apply to the feet if you place the palms of your hands on a table and pretend they are your soles. Tilt your hands so the inner edge (thumb side) of each is raised from the table. This is like raising the medial edge of your foot from the ground, and as you can see, it involves a slight supination of your forearms. Resting your hands palms down on a table, your forearms are already pronated; but if you raise the outer edges of your hands (the little finger side), like pronating the feet, you will see that it involves a continuation of the pronation movement of the forearm.

Range of Motion

A joint's **range of motion (ROM)** is the number of degrees through which one bone can move relative to another at that joint. For example, the ankle has an ROM of about 74°, the first knuckle about 90°, and the knee about 130° to 140°. Range of motion obviously affects a person's functional independence and quality of life. It is also an important consideration in training for

---

[22] *op* = against; *posit* = to place
[23] *re* = back; *posit* = to place
[24] *in* = inward; *version* = turning
[25] *e* = outward; *version* = turning



© McGraw-Hill Education/Timothy L. Vacula, photographer

(a) Flexion of ankle

© McGraw-Hill Education/Timothy L. Vacula, photographer

(b) Inversion

© McGraw-Hill Education/Timothy L. Vacula, photographer

(c) Eversion

Figure 9.17 **Movements of the Foot.**
• *Identify some common activities in which inversion and eversion of the foot would be important.*

athletics or dance, in clinical diagnosis, and in monitoring the progress of rehabilitation. Several factors affect the ROM and stability of a joint:

- **Structure of the articular surfaces of the bones.** In many cases, joint movement is limited by the shapes of the bone surfaces. For example, you cannot straighten your elbow beyond 180° or so because, as it straightens, the olecranon of the ulna swings into the olecranon fossa of the humerus and cannot move farther.
- **Strength and tautness of ligaments and joint capsules.** Some bone surfaces impose little if any limitation on joint movement. The articulations of the phalanges are an example; as one can see by examining a dry skeleton, an interphalangeal joint can bend through a broad arc. In the living body, however, these bones are joined by ligaments that limit their movement. As you flex one of your knuckles, ligaments on the anterior (palmar) side of the joint go slack, but ligaments on the posterior (dorsal) side tighten and prevent the joint from flexing beyond 90° or so. The knee is another case in point. In kicking a football, the knee rapidly extends to about 180°, but it can go no farther. Its motion is limited in part by a *cruciate ligament* and other knee ligaments described later. Gymnasts, dancers, and acrobats increase the ROM of their synovial joints by gradually stretching their ligaments during training. "Double-jointed" people have unusually large ROMs at some joints, not because the joint is actually double or fundamentally different from normal in its anatomy, but because the ligaments are unusually long or slack.
- **Action of the muscles and tendons.** Extension of the knee is also limited by the *hamstring muscles* on the posterior side of the thigh. In many other joints, too, pairs of muscles oppose each other and moderate the speed and range of joint motion. Even a resting muscle maintains a state of tension called *muscle tone,* which serves in many cases to stabilize a joint. One of the major factors preventing dislocation of the shoulder joint, for example, is tension in the *biceps brachii* muscle, whose tendons cross the joint, insert on the scapula, and hold the head of the humerus against the glenoid cavity. The nervous system continually monitors and adjusts joint angles and muscle tone to maintain joint stability and limit unwanted movements.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

7. What are the two components of a joint capsule? What is the function of each?
8. Give at least one example each of a monaxial, biaxial, and multiaxial joint, and explain the reason for its classification.
9. Name the joints that would be involved if you reached directly overhead and screwed a lightbulb into a ceiling fixture. Describe the joint actions that would occur.

9.3 Anatomy of Selected Synovial Joints

Expected Learning Outcomes

When you have completed this section, you should be able to

a. identify the major anatomical features of the jaw, shoulder, elbow, hip, knee, and ankle joints; and
b. explain how the anatomical differences between these joints are related to differences in function.

We now examine the gross anatomy of certain diarthroses. It is beyond the scope of this book to discuss very many of them, but the ones selected here most often require medical attention and most have a strong bearing on athletic performance and everyday function.

The Jaw Joint

The **temporomandibular joint (TMJ)** is the articulation of the condyle of the mandible with the mandibular fossa of the temporal bone (fig. 9.18). You can feel its action by pressing your fingertips against the jaw immediately anterior to the ear while opening and closing your mouth. This joint combines elements of condylar, hinge, and plane joints. It functions in a hingelike fashion when the mandible is elevated and depressed, it glides from side to side to grind food between the molars, and it glides slightly forward when the jaw is protracted to take a bite or when the mouth is opened widely. If you palpate the joint just anterior to your earlobe while opening the mouth, you can feel this forward glide of the condylar process. You can get a sense of the necessity of this movement if you press on your chin with the heel of your hand to prevent the mandible from gliding anteriorly; you will find it difficult to open the mouth very far.

DEEPER INSIGHT 9.2

TMJ Syndrome

Temporomandibular joint (TMJ) syndrome has received medical recognition only recently, although it may affect as many as 75 million Americans. It can cause moderate intermittent facial pain, clicking sounds in the jaw, limitation of jaw movement, and in some people, more serious symptoms—severe headaches, vertigo (dizziness), tinnitus (ringing in the ears), and pain radiating from the jaw down the neck, shoulders, and back. It seems to be caused by a combination of psychological tension and malocclusion (misalignment of the teeth). Treatment may involve psychological management, physical therapy, analgesic and anti-inflammatory drugs, and sometimes corrective dental appliances to align the teeth properly.


Sphenomandibular ligament
Lateral ligament
Joint capsule
External acoustic meatus
Styloid process
Stylomandibular ligament

(a) Lateral view


Sphenoid sinus
Occipital bone
Sphenomandibular ligament
Styloid process
Stylomandibular ligament
Mandibular fossa of temporal bone
Superior joint cavity
Articular disc
Inferior joint cavity
Mandibular condyle
Synovial membrane
Joint capsule

(b) Medial view

(c) Sagittal section

Figure 9.18 The Jaw (Temporomandibular) Joint. AP|R

The synovial cavity of the TMJ is divided into superior and inferior chambers by an articular disc, which permits lateral and medial excursion. Two ligaments support the joint. The **lateral ligament** prevents posterior displacement of the mandible. If the jaw receives a hard blow, this ligament normally prevents the condylar process from being driven upward and fracturing the base of the skull. The **sphenomandibular ligament** on the medial side of the joint extends from the sphenoid bone to the ramus of the mandible. A *stylomandibular ligament* extends from the styloid process to the angle of the mandible but is not part of the TMJ proper.

A deep yawn or other strenuous depression of the mandible can dislocate the TMJ by making the condyle pop out of the fossa and slip forward. The joint can be relocated by pressing down on the molars while pushing the jaw backward.

The Shoulder Joint

The **glenohumeral (humeroscapular) joint,** or shoulder joint, is where the hemispherical head of the humerus articulates with the glenoid cavity of the scapula (fig. 9.19). Together, the shoulder and elbow joints serve to position the hand for the performance of a task; without a hand, shoulder and elbow movements are far less useful. The relatively loose shoulder joint capsule and shallow glenoid cavity sacrifice joint stability for freedom of movement. The cavity, however, has a ring of fibrocartilage called the **glenoid labrum**[26] around its margin, making it somewhat deeper than it looks on a dried skeleton.

Five principal ligaments support this joint. The **coracohumeral ligament** extends from the coracoid process of the scapula to the greater tubercle of the humerus, and the **transverse humeral ligament** extends from the greater to the lesser tubercle of the humerus, creating a tunnel, the intertubercular sulcus, through which a tendon of the biceps brachii passes. The other three ligaments, called **glenohumeral ligaments,** are relatively weak and sometimes absent.

A tendon of the biceps brachii muscle is the most important stabilizer of the shoulder. It originates on the margin of the glenoid cavity, passes through the joint capsule, and emerges into the intertubercular sulcus, where it is held by the transverse humeral ligament. Inferior to the sulcus, it merges into the biceps brachii. Thus, the tendon functions as a taut, adjustable strap that holds the humerus against the glenoid cavity.

---

[26] *labrum* = lip


Acromioclavicular joint
Acromion of scapula
Clavicle
Head of humerus
Coracobrachialis muscle
Deltoid muscle (cut and folded back)
Pectoralis major muscle
Biceps brachii muscle:
Short head
Long head
Acromion
Subacromial bursa
Supraspinatus tendon
Coracohumeral ligament
Subdeltoid bursa
Subscapularis tendon
Transverse humeral ligament
Tendon sheath
Biceps brachii tendon (long head)
Humerus
Acromioclavicular ligament
Clavicle
Coraco-clavicular ligament
Coraco-acromial ligament
Coracoid process
Sub-coracoid bursa
Sub-scapular bursa
Gleno-humeral ligaments

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

(a) Anterior dissection

(b) Anterior view


Acromion
Subdeltoid bursa
Deltoid muscle
Humerus
Supraspinatus tendon
Capsular ligament
Glenoid labrum
Synovial membrane
Glenoid cavity of scapula
Glenoid labrum
Acromion
Supraspinatus tendon
Subdeltoid bursa
Infraspinatus tendon
Glenoid cavity (articular cartilage)
Teres minor tendon
Synovial membrane (cut)
Coracoid process
Coracohumeral ligament
Superior glenohumeral ligament
Biceps brachii tendon (long head)
Subscapular bursa
Subscapularis tendon
Middle glenohumeral ligament
Inferior glenohumeral ligament

(c) Frontal section

(d) Lateral view, humerus removed

Figure 9.19 **The Shoulder (Glenohumeral) Joint.**
• *The socket of the shoulder joint is a little deeper in life than it appears on a dried skeleton. What structure makes it so?* APR

In addition to the biceps brachii, four muscles important in stabilizing the glenohumeral joint are the *subscapularis, supraspinatus, infraspinatus,* and *teres minor.* The tendons of these four muscles form the *rotator cuff,* which is fused to the joint capsule on all sides except inferiorly. The rotator cuff is discussed more fully on page 300.

Four bursae are associated with the shoulder joint. Their names describe their locations—the **subdeltoid, subacromial, subcoracoid,** and **subscapular bursae.**

Shoulder dislocations are very painful and sometimes result in permanent damage. The most common dislocation is downward displacement of the humerus, because (1) the rotator cuff protects the joint in all directions except inferiorly, and (2) the joint is protected from above by the coracoid process, acromion, and clavicle. Dislocations most often occur when the arm is abducted and then receives a blow from above—for example, when the outstretched arm is struck by heavy objects falling off a shelf. They also occur in children who are jerked off the ground by one arm or forced to follow by a hard tug on the arm. Children are especially prone to such injury not only because of the inherent stress caused by such abuse, but also because a child's shoulder is not fully ossified and the rotator cuff is not strong enough to withstand such stress. Because this joint is so easily dislocated, you should never attempt to move an immobilized person by pulling on his or her arm.

The Elbow Joint

The elbow includes a hinge joint composed of two articulations—the **humeroulnar joint,** where the trochlea of the humerus joins the trochlear notch of the ulna, and the **humeroradial joint,** where the capitulum of the humerus meets the head of the radius (fig. 9.20). Both are enclosed in a single joint capsule. On the posterior side of the elbow, there is a prominent **olecranon bursa** to ease the movement of tendons over the elbow. Side-to-side motions of the elbow joint are restricted by a pair of ligaments, the **radial (lateral) collateral ligament** and **ulnar (medial) collateral ligament.**

Another joint occurs in the elbow region, the **proximal radioulnar joint,** but it is not involved in the hinge. At this joint, the disclike head of the radius fits into the radial notch


Humerus
Lateral epicondyle
Medial epicondyle
Joint capsule
Radial collateral ligament
Ulnar collateral ligament
Anular ligament
Tendon of biceps brachii (cut)
Ulna
Radius
Joint capsule
Humerus
Coronoid process
Trochlea
Olecranon bursa
Radius
Articular cartilage
Olecranon
Ulna

(a) Anterior view

(b) Sagittal section


Anular ligament
Humerus
Tendon of biceps brachii (cut)
Radius
Joint capsule
Tendon of triceps brachii
Coronoid process
Ulnar collateral ligament
Olecranon bursa
Ulna
Humerus
Joint capsule
Anular ligament
Lateral epicondyle
Tendon of biceps brachii (cut)
Radial collateral ligament
Radius
Joint capsule
Ulna
Olecranon

(c) Medial view

(d) Lateral view

Figure 9.20 The Elbow Joint. This region includes two joints that form the elbow hinge—the humeroulnar and humeroradial—and one joint, the radioulnar, not involved in the hinge but involved in forearm rotation. APR

DEEPER INSIGHT 9.3

Pulled Elbow

The immature skeletons of children and adolescents are especially vulnerable to injury. Pulled elbow (dislocation of the radius) is a common injury in preschool children (especially girls). It typically results from an adult lifting or jerking a child up by one arm when the arm is pronated, as in lifting a child into a high chair or shopping cart (fig. 9.21). This tears the anular ligament from the head of the radius, and the radius pulls partially or entirely out of the ligament. The proximal part of the torn ligament is then painfully pinched between the radial head and the capitulum of the humerus. Radial dislocation is treated by supinating the forearm with the elbow flexed and then putting the arm in a sling for about 2 weeks—time enough for the anular ligament to heal.


Radius
Ulna
Radial head pulled from ligament
Anular ligament
Humerus
(a)
Dislocated radial head pinches anular ligament
(b)

Figure 9.21 **Pulled Elbow.** Jerking a child by the arm can dislocate the radius. (a) The anular ligament tears, and the radial head is pulled from the ligament. (b) Muscle contraction pulls the radius upward. The head of the radius produces a lump on the lateral side of the elbow and may painfully pinch the anular ligament.

of the ulna and is held in place by the **anular ligament**, which encircles the head of the radius and attaches at each end to the ulna.

The Hip Joint

The **coxal (hip) joint** is the point where the head of the femur inserts into the acetabulum of the hip bone (fig. 9.22). Because the coxal joints bear much of the body's weight, they have deep sockets and are much more stable than the shoulder joints. The depth of the socket is somewhat greater than you see on dried bones because a horseshoe-shaped ring of fibrocartilage, the **acetabular labrum,** is attached to its rim. A **transverse acetabular ligament** bridges a gap in the inferior margin of the acetabular labrum. Dislocations of the hip are rare, but some infants suffer congenital dislocations because the acetabulum is not deep enough to hold the head of the femur in place. If detected early, this condition can be treated with a harness, worn for 2 to 4 months, that holds the head of the femur in proper position until the joint is stronger.

Apply What You Know

Where else in the body is there a structure similar to the acetabular labrum? What do those two locations have in common?

Ligaments that support the coxal joint include the **iliofemoral** (ILL-ee-oh-FEM-or-ul) and **pubofemoral** (PYU-bo-FEM-or-ul) **ligaments** on the anterior side and the **ischiofemoral** (ISS-kee-oh-FEM-or-ul) **ligament** on the posterior side. The name of each ligament refers to the bones to which it attaches—the femur and the ilium, pubis, or ischium. When you stand up, these


Acetabular labrum
Acetabulum
Head of femur
Greater trochanter
Round ligament
Shaft of femur
Round ligament (cut)
Fovea capitis
Acetabulum
Head of femur
Labrum
Greater trochanter
Ischial tuberosity
Obturator membrane
Femur
Transverse acetabular ligament

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

(a) Anterior dissection **(b) Lateral view, femur retracted**


Ilium
Pubofemoral ligament
Iliofemoral ligament
Greater trochanter
Femur
Lesser trochanter
Pubis
Iliofemoral ligament
Ischiofemoral ligament
Greater trochanter
Ischial tuberosity
Femur

(c) Anterior view **(d) Posterior view**

Figure 9.22 The Hip (Coxal) Joint.

ligaments become twisted and pull the head of the femur tightly into the acetabulum. The head of the femur has a conspicuous pit called the *fovea capitis.* The **round ligament,** or **ligamentum teres**[27] (TERR-eez), arises here and attaches to the lower margin of the acetabulum. This is a relatively slack ligament, so it is doubtful that it plays a significant role in holding the femur in its socket. It does, however, contain an artery that supplies blood to the head of the femur.

The Knee Joint

The **tibiofemoral** (knee) **joint** is the largest and most complex diarthrosis of the body (figs. 9.23 and 9.24). It is primarily a hinge joint, but when the knee is flexed it is also capable of slight rotation

---

[27] *teres* = round


Femur
Patellar surface
Lateral condyle
Fibular collateral ligament
Lateral meniscus
Transverse ligament
Fibula
Tibia
Medial condyle
Posterior cruciate ligament
Anterior cruciate ligament
Medial meniscus
Tibial collateral ligament
Patellar ligament (cut)
Femur
Medial condyle
Tibial collateral ligament
Medial meniscus
Posterior cruciate ligament
Fibula
Tibia
Anterior cruciate ligament
Fibular collateral ligament
Lateral meniscus
Articular cartilage of tibia

(a) Anterior view **(b) Posterior view**


Femur
Bursa under lateral head of gastrocnemius
Joint capsule
Articular cartilage
Meniscus
Tibia
Quadriceps femoris
Quadriceps femoris tendon
Suprapatellar bursa
Prepatellar bursa
Patella
Synovial membrane
Joint cavity
Infrapatellar fat pad
Superficial infrapatellar bursa
Patellar ligament
Deep infrapatellar bursa
Lateral meniscus
Lateral condyle of tibia
Posterior cruciate ligament
Medial meniscus
Synovial membrane
Medial condyle of tibia
Anterior cruciate ligament

(c) Sagittal section **(d) Superior view of tibia and menisci**

Figure 9.23 **The Knee (Tibiofemoral) Joint.** APR

and lateral gliding. The patella and its ligament also form a plane **patellofemoral joint** with the femur.

The joint capsule encloses only the lateral and posterior sides of the patellar ligament and the *lateral* and *medial patellar retinacula* (not illustrated). These are extensions of the tendon of the *quadriceps femoris* muscle, the large anterior muscle of the thigh. The knee is stabilized mainly by the quadriceps tendon in front and the tendon of the *semimembranosus* muscle on the rear of the thigh. Developing strength in these muscles therefore reduces the risk of knee injury.

The joint cavity contains two C-shaped cartilages called the **lateral** and **medial menisci (singular, meniscus)** joined by a


Lateral
Medial
Femur:
Shaft
Patellar surface
Medial condyle
Lateral condyle
Joint capsule
Joint cavity:
Anterior cruciate ligament
Medial meniscus
Lateral meniscus
Tibia:
Lateral condyle
Medial condyle
Tuberosity
Patellar ligament
Patella (posterior surface)
Articular facets
Quadriceps tendon (reflected)

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Figure 9.24 **The Right Knee, Anterior Dissection.** The quadriceps tendon has been cut and folded (reflected) downward to expose the joint cavity and the posterior surface of the patella.

transverse ligament. They absorb the shock of the body weight jostling up and down on the knee and prevent the femur from rocking from side to side on the tibia. The posterior side of the knee, the **popliteal** (pop-LIT-ee-ul) **region,** is supported by a complex array of **intracapsular ligaments** within the joint capsule and **extracapsular ligaments** external to it. The extracapsular ligaments are the **oblique popliteal ligament** (an extension of the tendon of the *semimembranosus* hamstring muscle), **arcuate** (AR-cue-et) **popliteal ligament, fibular (lateral) collateral ligament,** and **tibial (medial) collateral ligament.** Only the two collateral ligaments are illustrated; they prevent the knee from rotating when the joint is extended.

There are two intracapsular ligaments deep within the joint cavity. The synovial membrane folds around them, however, so that they are excluded from the fluid-filled synovial cavity.

DEEPER INSIGHT 9.4

Knee Injuries and Arthroscopic Surgery

Although the knee can bear a lot of weight, it is highly vulnerable to rotational and horizontal stress, especially when the knee is flexed (as in skiing or running) and receives a blow from behind or from the side (fig. 9.25). The most common injuries are to a meniscus or the anterior cruciate ligament (ACL). Knee injuries heal slowly because ligaments and tendons have a scanty blood supply and cartilage usually has no blood vessels at all.

The diagnosis and surgical treatment of knee injuries have been greatly improved by *arthroscopy,* a procedure in which the interior of a joint is viewed with a pencil-thin instrument, the *arthroscope,* inserted through a small incision. The arthroscope has a light, a lens, and fiber optics that allow a viewer to see into the cavity and take photographs or video recordings. A surgeon can also withdraw samples of synovial fluid by arthroscopy or inject saline into the joint cavity to expand it and provide a clearer view. If surgery is required, additional small incisions can be made for the surgical instruments and the procedures can be observed through the arthroscope or on a monitor. Arthroscopic surgery produces much less tissue damage than conventional surgery and enables patients to recover more quickly.

Orthopedic surgeons often replace a damaged ACL with a graft from the patellar ligament or a hamstring tendon. The surgeon "harvests" a strip from the middle of the patient's ligament or tendon, drills a hole into the femur and tibia within the joint cavity, threads the ligament through the holes, and fastens it with biodegradable screws. The grafted ligament is more taut and "competent" than the damaged ACL. It becomes ingrown with blood vessels and serves as a substrate for the deposition of more collagen, which further strengthens it in time. Following arthroscopic ACL reconstruction, a patient typically must use crutches for 7 to 10 days and undergo physical therapy for 6 to 10 weeks, followed by self-directed exercise therapy. Healing is completed in about 9 months.


Twisting motion
Foot fixed
Anterior cruciate ligament (torn)
Tibial collateral ligament (torn)
Medial meniscus (torn)
Patellar ligament

Figure 9.25 **Knee Injuries.**

These ligaments cross each other in the form of an X; hence, they are called the **anterior cruciate**[28] (CROO-she-ate) **ligament (ACL)** and **posterior cruciate ligament (PCL).** These are named according to whether they attach to the anterior or posterior side of the tibia, not for their attachments to the femur. When the knee is extended, the ACL is pulled tight and prevents hyperextension. The PCL prevents the femur from sliding off the front of the tibia and prevents the tibia from being displaced backward. The ACL is one of the most common sites of knee injury (see Deeper Insight 9.4).

An important aspect of human bipedalism is the ability to lock the knees and stand erect without tiring the extensor muscles of the thigh. When the knee is extended to the fullest degree allowed by the ACL, the femur rotates medially on the tibia. This action locks the knee, and in this state, all the major knee ligaments are twisted and taut. To unlock the knee, the *popliteus* muscle rotates the femur laterally, causing the ligaments to untwist.

The knee joint has at least 13 bursae. Four of these are anterior—the **superficial infrapatellar, suprapatellar, prepatellar,** and **deep infrapatellar.** Located in the popliteal region are the **popliteal bursa** and **semimembranosus bursa** (not illustrated). At least seven more bursae are found on the lateral and medial sides of the knee joint. From figure 9.23a, your knowledge of the relevant word elements *(infra-, supra-, pre-),* and the terms *superficial* and *deep,* you should be able to work out the reasoning behind most of these names and develop a system for remembering the locations of these bursae.

The Ankle Joint

The **talocrural**[29] **(ankle) joint** includes two articulations—a medial joint between the tibia and talus and a lateral joint between the fibula and talus, both enclosed in one joint capsule (fig. 9.26). The malleoli of the tibia and fibula overhang the talus

---

[28] *cruci* = cross; *ate* = characterized by

[29] *talo* = ankle; *crural* = pertaining to the leg


Fibula
Tibia
Anterior and posterior tibiofibular ligaments
Calcaneal tendon
Calcaneus
Lateral ligament:
Posterior talofibular ligament
Calcaneofibular ligament
Anterior talofibular ligament
Tendons of fibularis longus and brevis
Metatarsal V

(a) Lateral view

© McGraw-Hill Education/Photo and Dissection by Christine Eckel


Fibula
Tibia
Anterior tibiofibular ligament
Talus
Dorsal talonavicular ligament
Calcaneocuboid ligament
Calcaneus
Cuboid
Long plantar ligament

(b) Lateral dissection


Medial ligament
Navicular
Metatarsal I
Tendons of tibialis anterior and posterior
Tibia
Calcaneal tendon
Calcaneus

(c) Medial view


Tibia
Fibula
Interosseous membrane
Medial malleolus
Posterior tibiofibular ligament
Lateral malleolus
Posterior talofibular ligament
Calcaneofibular ligament
Calcaneus

(d) Posterior view

Figure 9.26 The Ankle (Talocrural) Joint of the Right Foot. APR

on each side like a cap and prevent most side-to-side motion. The ankle therefore has a more restricted range of motion than the wrist.

The ligaments of the ankle include (1) **anterior** and **posterior tibiofibular ligaments**, which bind the tibia to the fibula; (2) a multipart **medial (deltoid) ligament,** which binds the tibia to the foot on the medial side; and (3) a multipart **lateral collateral ligament,** which binds the fibula to the foot on the lateral side. The **calcaneal (Achilles) tendon** extends from the calf muscles to the calcaneus. It plantar flexes the foot and limits dorsiflexion. Plantar flexion is limited by extensor tendons on the anterior side of the ankle and by the anterior part of the joint capsule.

Sprains (torn ligaments and tendons) are common at the ankle, especially when the foot is suddenly inverted or everted to excess. They are painful and usually accompanied by immediate swelling. They are best treated by immobilizing the joint and reducing swelling with an ice pack, but in extreme cases may require a cast or surgery.

The synovial joints described in this section are summarized in table 9.2.

TABLE 9.2 Review of the Principal Diarthroses

Joint	Major Anatomical Features and Actions
Jaw joint (fig. 9.18)	*Type:* condylar, hinge, and plane *Movements:* elevation, depression, protraction, retraction, lateral and medial excursion *Articulation:* condyle of mandible, mandibular fossa of temporal bone *Ligaments:* lateral, sphenomandibular *Cartilage:* articular disc
Shoulder joint (fig. 9.19)	*Type:* ball-and-socket *Movements:* adduction, abduction, flexion, extension, circumduction, medial and lateral rotation *Articulation:* head of humerus, glenoid fossa of scapula *Ligaments:* coracohumeral, transverse humeral, three glenohumerals *Tendons:* rotator cuff (tendons of subscapularis, supraspinatus, infraspinatus, teres minor), tendon of biceps brachii *Bursae:* subdeltoid, subacromial, subcoracoid, subscapular *Cartilage:* glenoid labrum
Elbow joint (fig. 9.20)	*Type:* hinge and pivot *Movements:* flexion, extension, pronation, supination, rotation *Articulations:* humeroulnar—trochlea of humerus, trochlear notch of ulna; humeroradial—capitulum of humerus, head of radius; radioulnar—head of radius, radial notch of ulna *Ligaments:* radial collateral, ulnar collateral, anular *Bursa:* olecranon
Hip joint (fig. 9.22)	*Type:* ball-and-socket *Movements:* adduction, abduction, flexion, extension, circumduction, medial and lateral rotation *Articulation:* head of femur, acetabulum of hip bone *Ligaments:* iliofemoral, pubofemoral, ischiofemoral, ligamentum teres, transverse acetabular *Cartilage:* acetabular labrum
Knee joint (fig. 9.23)	*Type:* primarily hinge *Movements:* flexion, extension, slight rotation *Articulations:* tibiofemoral, patellofemoral *Ligaments:* anterior—lateral patellar retinaculum, medial patellar retinaculum; popliteal intracapsular—anterior cruciate, posterior cruciate; popliteal extracapsular—oblique popliteal, arcuate popliteal, lateral collateral, medial collateral *Bursae:* anterior—superficial infrapatellar, suprapatellar, prepatellar, deep infrapatellar; popliteal—popliteal, semimembranosus; medial and lateral—seven other bursae not named in this chapter *Cartilages:* lateral meniscus, medial meniscus (connected by transverse ligament)
Ankle joint (fig. 9.26)	*Type:* hinge *Movements:* dorsiflexion, plantar flexion, extension *Articulations:* tibia–talus, fibula–talus, tibia–fibula *Ligaments:* anterior and posterior tibiofibular, deltoid, lateral collateral *Tendon:* calcaneal (Achilles)

Before You Go On

Answer the following questions to test your understanding of the preceding section:

10. What keeps the mandibular condyle from slipping out of its fossa in a posterior direction?
11. List at least three ways that the shoulder joint is stabilized.
12. What keeps the femur from slipping backward off the tibia?
13. What keeps the tibia from slipping sideways off the talus?

9.4 Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. define *rheumatism* and describe the profession of rheumatology;
b. define *arthritis* and describe its forms and causes;
c. discuss the design and application of artificial joints; and
d. identify several joint diseases other than arthritis.

Our quality of life depends greatly on mobility, and mobility depends on proper functioning of the diarthroses. Not surprisingly, therefore, joint dysfunctions are among the most common medical complaints. **Rheumatism** is a broad term for any pain in the supportive and locomotor organs of the body, including bones, ligaments, tendons, and muscles. Physicians who deal with the study, diagnosis, and treatment of joint disorders are called **rheumatologists**.

Arthritis

The most widespread crippling disorder in the United States is **arthritis,**[30] a broad term that embraces more than a hundred diseases of largely obscure or unknown causes. In general, *arthritis* means inflammation of a joint. Nearly everyone develops arthritis to some degree after middle age and sometimes earlier.

The most common form of arthritis is **osteoarthritis (OA),** also called "wear-and-tear arthritis" because it is apparently a normal consequence of years of wear on the joints. As joints age, the articular cartilage softens and degenerates. As the cartilage becomes roughened by wear, joint movement may be accompanied by crunching or crackling sounds called *crepitus.* Osteoarthritis affects especially the fingers, intervertebral joints, hips, and knees. As the articular cartilage wears away, exposed bone tissue often develops spurs that grow into the joint cavity, restrict movement, and cause pain. Though OA rarely occurs before age 40, it affects about 85% of people older than 70. It usually does not cripple, but in severe cases it can immobilize the hip.

Rheumatoid arthritis (RA), which is far more severe, results from an autoimmune attack against the joint tissues. Like other autoimmune diseases, RA is caused by an *autoantibody*—a misguided antibody that attacks the body's own tissues instead of limiting its attack to foreign matter. In RA, an autoantibody called *rheumatoid factor* attacks the synovial membranes. Inflammatory cells accumulate in the synovial fluid and produce enzymes that degrade the articular cartilage. The synovial membrane thickens and adheres to the articular cartilage, fluid accumulates in the joint capsule, and the capsule is invaded by fibrous connective tissue. As articular cartilage degenerates, the joint begins to ossify, and sometimes the bones become solidly fused and immobilized, a condition called **ankylosis**[31] (fig. 9.27). RA tends to develop symmetrically—if the right wrist or hip develops RA, so does the left.



(a)



(b)

Figure 9.27 Rheumatoid Arthritis (RA). (a) A severe case with ankylosis of the joints. (b) Colorized X-ray of hands with RA.

---

[30] *arthr* = joint; *itis* = inflammation

[31] *ankyl* = bent, crooked; *osis* = condition

TABLE 9.3	Disorders of the Joints
Dislocation (luxation)	Displacement of a bone from its normal position at a joint, usually accompanied by a sprain of the adjoining connective tissues. Most common at the fingers, thumb, shoulder, and knee.
Gout	A hereditary disease, most common in men, in which uric acid crystals accumulate in the joints and irritate the articular cartilage and synovial membrane. Causes *gouty arthritis,* with swelling, pain, tissue degeneration, and sometimes fusion of the joint. Most commonly affects the great toe.
Strain	Painful overstretching of a tendon or muscle without serious tissue damage. Often results from inadequate warm-up before exercise.
Subluxation	Partial dislocation in which two bones maintain contact between their articular surfaces.
Synovitis	Inflammation of a joint capsule, often as a complication of a sprain.

Disorders Described Elsewhere

Ankle sprains	219
Bursitis	210
Congenital hip dislocation	224
Dislocation of the elbow	224
Dislocation of the shoulder	222
Knee injuries	227
Osteoarthritis	230
Rheumatoid arthritis	230
Rotator cuff injury	300
Tendinitis	210
TMJ syndrome	220

Rheumatoid arthritis tends to flare up and subside (go into remission) periodically.[32] It affects women far more than men and typically begins between the ages of 30 and 40. There is no cure, but joint damage can be slowed with hydrocortisone or other steroids. Because long-term use of steroids weakens the bone, however, aspirin is the treatment of first choice to control the inflammation. Physical therapy is also used to preserve the joint's range of motion and the patient's functional ability.

Several common pathologies of the joints are briefly described in table 9.3.

Joint Prostheses

Arthroplasty,[33] a treatment of last resort, is the replacement of a diseased joint with an artificial device called a **joint prosthesis.**[34] Joint prostheses were first developed to treat war injuries in World War II and the Korean War. Total hip replacement (THR), first performed in 1963 by English orthopedic surgeon Sir John Charnley, is now the most common orthopedic procedure for the elderly. The first knee replacements were performed in the 1970s. Joint prostheses are now available for finger, shoulder, elbow, hip, and knee joints. Arthroplasty is performed on over 250,000 patients per year in the United States, primarily to relieve pain and restore function in elderly people with OA or RA.

Arthroplasty presents ongoing challenges for biomedical engineering. An effective prosthesis must be strong, nontoxic, and corrosion-resistant. In addition, it must bond firmly to the patient's bones and enable a normal range of motion with a minimum of friction. The heads of long bones are usually replaced with prostheses made of a metal alloy such as cobalt-chrome, titanium alloy, or stainless steel. Joint sockets are made of polyethylene (fig. 9.28). Prostheses are bonded to the patient's bone with screws or bone cement.

Over 90% of artificial knees last 10 years, 85% for 15 years, and 75% for 20 years. The most common form of failure is detachment of the prosthesis from the bone. This problem has been reduced by using *porous-coated prostheses,* which become infiltrated by the patient's own bone and create a firmer bond. A prosthesis is not as strong as a natural joint, however, and is not an option for many young, active patients.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

14. Define *arthritis.* How do the causes of osteoarthritis and rheumatoid arthritis differ? Which type is more common?
15. What are the major engineering problems in the design of joint prostheses? What is the most common cause of failure of a prosthesis?

---

[32] *rheumat* = tending to change
[33] *arthro* = joint; *plasty* = surgical repair
[34] *prosthe* = something added



© Southern Illinois University

© Southern Illinois University/Science Source

© Ron Mensching/Phototake

© Mehau Kulyk/SPL/Science Source

Figure 9.28 **Joint Prostheses.** (a) Artificial femoral condyles affixed to the distal end of the femur. (b) An artificial knee joint bonded to a natural femur and tibia (compare X-ray on p. 205). (c) A porous-coated hip prosthesis. The caplike portion replaces the acetabulum of the hip bone, and the ball and shaft below it are bonded to the proximal end of the femur. (d) X-ray of a patient with a total hip replacement.

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

9.1 Joints and Their Classification (p. 206)

1. The definition of *joint (articulation)*
2. Names of the sciences concerned with joint structure and movement
3. The general rule for how joints are commonly named
4. The criteria used to classify joints into anatomical and functional categories
5. The distinguishing characteristics of bony joints, fibrous joints, and cartilaginous joints; synonyms for these terms; and examples of joints in each category
6. The three subclasses of fibrous joints and three types of sutures, and examples of each
7. The two subclasses of cartilaginous joints, and examples of each

9.2 Synovial Joints (p. 209)

1. The definition of *synovial joint*
2. The anatomical features of a generalized synovial joint
3. The functions of articular discs and menisci at certain synovial joints, where they can be found, and their appearance
4. The defining characteristics of tendons, ligaments, and bursae, and the roles they play at the joints; how tendon sheaths differ from other bursae
5. The distinction between monaxial, biaxial, and multiaxial joints
6. The six types of synovial joints and where they can be found
7. The definitions of joint *flexion, extension,* and *hyperextension;* some everyday scenarios in which these movements occur; and the ability to demonstrate them with your own body
8. The same for *abduction, adduction, hyperabduction,* and *hyperadduction*
9. The same for *elevation* and *depression*
10. The same for *protraction* and *retraction*
11. The same for *circumduction*
12. The same for *medial (internal)* and *lateral (external) rotation*

13. The same for *supination* and *pronation* of the forearm
14. The same for *flexion, extension, hyperextension,* and *lateral flexion* of the vertebral column
15. The same for *rotation* of the head or torso
16. The same for *lateral* and *medial excursion* of the mandible
17. The same for wrist *flexion* and *extension* anteriorly and posteriorly, and *ulnar* and *radial flexion* from side to side
18. The same for the thumb movements of *radial abduction, palmar abduction, opposition,* and *reposition*
19. The same for the ankle or foot movements of *dorsiflexion, plantar flexion, inversion,* and *eversion,* and how several of these movements are combined in foot pronation and supination
20. How a joint's range of motion (ROM) is measured and what anatomical features govern the ROM

9.3 Anatomy of Selected Synovial Joints (p. 220)

1. Special functional qualities of the temporomandibular joint (TMJ); its major anatomical features; and two common disorders of the TMJ
2. Special functional qualities of the glenohumeral joint; its major anatomical features; and two of its common injuries
3. The names of the three joints that occur at the elbow; how they enable the varied movements of the forearm; and the major anatomical features of the elbow joints
4. Special functional qualities of the coxal joint; its major anatomical features; and the actions of the ligaments at this joint when a person stands
5. Special functional qualities of the tibiofemoral joint; its major anatomical features (especially its menisci and cruciate ligaments); and the common injuries of this joint
6. Special functional qualities of the talocrural joint; its major anatomical features; and the nature of sprains at this joint

9.4 Clinical Perspectives (p. 230)

1. The range of disorders included in the concept of rheumatism, and the related term for physicians who specialize in joint disorders
2. The general meaning of *arthritis,* and the pathology and distinctions between osteoarthritis and rheumatoid arthritis
3. Joint prostheses and arthroplasty

Testing Your Recall

1. Lateral and medial excursion are movements unique to
   a. the ankle.
   b. the thumb.
   c. the mandible.
   d. the knee.
   e. the clavicle.
2. Which of the following is the least movable?
   a. a diarthrosis
   b. a synostosis
   c. a symphysis
   d. a syndesmosis
   e. a condylar joint
3. Which of the following movements are unique to the foot?
   a. dorsiflexion and inversion
   b. elevation and depression
   c. circumduction and rotation
   d. abduction and adduction
   e. opposition and reposition
4. Which of the following joints cannot be circumducted?
   a. trapeziometacarpal
   b. metacarpophalangeal
   c. glenohumeral
   d. coxal
   e. interphalangeal
5. Which of the following terms denotes a general condition that includes the other four?
   a. gout
   b. arthritis
   c. rheumatism
   d. osteoarthritis
   e. rheumatoid arthritis
6. In the adult, the ischium and pubis are united by
   a. a synchondrosis.
   b. a diarthrosis.
   c. a synostosis.
   d. an amphiarthrosis.
   e. a symphysis.
7. Articular discs are found only in certain
   a. synostoses.
   b. symphyses.
   c. diarthroses.
   d. synchondroses.
   e. amphiarthroses.
8. Which of the following joints has anterior and posterior cruciate ligaments?
   a. the shoulder
   b. the elbow
   c. the hip
   d. the knee
   e. the ankle
9. To bend backward at the waist involves _____ of the vertebral column.
   a. rotation
   b. hyperextension
   c. dorsiflexion
   d. abduction
   e. flexion
10. If you sit on a sofa and then raise your left arm to rest it on the back of the sofa, your left shoulder joint undergoes primarily
    a. lateral excursion.
    b. abduction.
    c. elevation.
    d. adduction.
    e. extension.
11. The lubricant of a diarthrosis is _____.
12. A fluid-filled sac that eases the movement of a tendon over a bone is called a/an _____.
13. A _____ joint allows one bone to swivel on another.
14. _____ is the science of movement.
15. The joint between a tooth and the mandible is called a/an _____.
16. In a/an _____ suture, the articulating bones have interlocking wavy margins, somewhat like a dovetail joint in carpentry.
17. In kicking a football, what type of action does the knee joint exhibit?
18. The angle through which a joint can move is called its _____.
19. A person with a degenerative joint disorder would most likely be treated by a physician called a/an _____.
20. The femur is prevented from slipping sideways off the tibia in part by a pair of cartilages called the lateral and medial _____.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. arthro-
2. re-
3. sym-
4. amphi-
5. -physis
6. circum-
7. ab-
8. ad-
9. duc-
10. kinesio-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. More people get rheumatoid arthritis than osteoarthritis.
2. A doctor who treats arthritis is called a kinesiologist.
3. Synovial joints are also known as synarthroses.
4. Most ligaments, but not all, connect one bone to another.
5. Reaching behind you to take something out of your hip pocket involves hyperextension of the elbow.
6. The anterior cruciate ligament normally prevents hyperextension of the knee.
7. There is no meniscus in the elbow joint.
8. The knuckles are diarthroses.
9. Synovial fluid is secreted by the bursae.
10. Most condylar joints can move in more planes than a hinge joint.

Answers in appendix A

Testing Your Comprehension

1. Why are there menisci in the knee joint but not in the elbow, the corresponding joint of the upper limb? Why is there an articular disc in the temporomandibular joint?
2. What ligaments would most likely be torn if you slipped and your foot was suddenly forced into an excessively inverted position: (a) the posterior talofibular and calcaneofibular ligaments, or (b) the medial ligament? Explain. What would the resulting condition of the ankle be called?
3. In order of occurrence, list the joint actions (flexion, pronation, etc.) and the joints where they would occur as you (a) sit down at a table, (b) reach out and pick up an apple, (c) take a bite, and (d) chew it. Assume that you start in anatomical position.
4. What structure in the elbow joint serves the same purpose as the anterior cruciate ligament (ACL) of the knee?
5. List the six types of synovial joints and for each one, if possible, identify a joint in the upper limb and a joint in the lower limb that fall into each category. Which of these six joints have no examples in the lower limb?



Neuromuscular junctions (SEM). Muscle fibers are shown in blue and nerve fibers in yellow.

© Dr. Donald Fawcett/Science Source

CHAPTER 10

THE MUSCULAR SYSTEM I
INTRODUCTION

CHAPTER OUTLINE

10.1 Muscle Types and Functions 236
- Types of Muscle 236
- Functions of Muscle 236
- Universal Properties of Muscle 237

10.2 General Anatomy of Muscles 237
- Connective Tissues and Fascicles 237
- Fascicles and Muscle Shapes 238
- Muscle Attachments 239
- Functional Groups of Muscles 240
- Intrinsic and Extrinsic Muscles 241
- Muscles, Bones, and Levers 241

10.3 Microscopic Anatomy of Skeletal Muscle 244
- Ultrastructure of Muscle Fibers 244
- The Nerve–Muscle Relationship 248
- The Blood Supply 250

10.4 Relating Structure to Function 250
- Contraction and Relaxation 250
- Muscle Growth and Atrophy 251
- Physiological Classes of Muscle Fibers 253

10.5 Cardiac and Smooth Muscle 254
- Cardiac Muscle 254
- Smooth Muscle 255

10.6 Developmental and Clinical Perspectives 257
- Embryonic Development of Muscle 257
- The Aging Muscular System 258
- Diseases of the Muscular System 258

Study Guide 260

DEEPER INSIGHTS

10.1 Muscle-Bound 241
10.2 Neuromuscular Toxins and Paralysis 249

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:

- Proteins of the plasma membrane (p. 32)
- Components of a neuron (p. 72)
- The three types of muscle (p. 74)
- Embryonic mesoderm, somites, and myotomes (p. 92)
- Skeletal anatomy (chapters 7 and 8)

Anatomy & Physiology REVEALED®
aprevealed.com

Module 6: Muscular System

Muscles constitute nearly half of the body's weight and occupy a place of central interest in several fields of health care and fitness. Physical and occupational therapists must be well acquainted with the muscular system to plan and carry out rehabilitation programs. Athletes and trainers, dancers and acrobats, and amateur fitness enthusiasts follow programs of resistance training to strengthen individual muscle groups through movement regimens based on knowledge of muscle, bone, and joint anatomy. Nurses employ their knowledge of the muscular system to give intramuscular injections correctly and to safely and effectively move patients who are physically incapacitated. Gerontological nurses are keenly aware of how deeply a person's muscular condition affects the quality of life in old age. The muscular system is highly important to biomedical disciplines even beyond the scope of the movement sciences. It is the primary source of body heat in the moving individual, and through its absorption, storage, and use of glucose, it is a significant factor in blood glucose level and diabetes prevention.

The next three chapters focus on the muscular system—the functional anatomy of muscular tissue in this chapter, muscles of the axial region of the body (head and trunk) in chapter 11, and muscles of the appendicular region (limbs and limb girdles) in chapter 12. These chapters draw on what we have covered in the preceding chapters—bone and joint structure—to flesh out our comprehension of body posture and movement. The current chapter also considers cardiac and smooth muscle and how they compare with skeletal muscle.

10.1 Muscle Types and Functions

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the distinctions between the three types of muscular tissue; and
b. list the functions of muscular tissue and the properties it must have to carry out these functions.

As we saw in chapter 3, there are three kinds of muscular tissue in the human body—skeletal, cardiac, and smooth. All types, however, are specialized for one fundamental purpose: to convert the chemical energy of ATP into the mechanical energy of motion. Muscle cells exert a useful force on other cells or tissues—either to produce desirable movements or to prevent undesirable ones.

Although we examine all three muscle types in this chapter, most of our attention will focus on the **muscular**[1] **system,** composed of the skeletal muscles only. The word *muscle* means "little mouse," apparently referring to the appearance of muscles rippling under the skin. The study of the skeletal muscles is called **myology.**[2]



© Ed Reschke/Getty Images

Figure 10.1 **Skeletal Muscle Fibers.**
• *What tissue characteristics evident in this photo distinguish this from cardiac and smooth muscle?* APR

Types of Muscle

Skeletal muscle may be defined as voluntary striated muscle that is usually attached to one or more bones. It is called *voluntary* because it is usually subject to conscious control; we can decide when to contract a skeletal muscle. It is called *striated* because it exhibits a microscopic pattern of alternating light and dark bands, or **striations,** which result from the overlapping arrangement of the contractile proteins within each cell (fig. 10.1). A typical skeletal muscle cell is about 100 µm in diameter and 3 cm (30,000 µm) long; some are as thick as 500 µm and as long as 30 cm. Because of their extraordinary length, skeletal muscle cells are usually called **muscle fibers** or **myofibers.**

Cardiac muscle is also striated, but it is **involuntary**—not normally under conscious control. Its cells are not fibrous in shape, but relatively short and stumpy, somewhat like logs with notched ends. Thus, they are called **cardiocytes** or **myocytes** rather than fibers. Cardiocytes are commonly about 80 µm long by 15 µm wide.

Smooth muscle is also involuntary, and unlike skeletal and cardiac muscle, it lacks striations—hence the description *smooth.* It contains the same contractile proteins as the other muscle types, but they are not arranged in a regularly overlapping way, so there are no striations. Its cells, also called myocytes, are fusiform in shape—thick in the middle and tapered at the ends. They average about 200 µm long by 5 µm wide at the thickest part, but they can be as short as 20 µm in small blood vessels or as long as 500 µm in the pregnant uterus.

Functions of Muscle

The functions of muscular tissue are as follows:

- **Movement.** Muscles enable us to move from place to place and to move individual body parts; they move body contents in the course of breathing, blood circulation, feeding and digestion, defecation, urination, and childbirth; and they serve various roles in communication—speech, writing, facial expressions, and other body language.

---

[1] *mus* = mouse; *cul* = little; *ar* = resembling
[2] *myo* = muscle; *logy* = study of

- **Stability.** Muscles maintain posture by preventing unwanted movements. Some are called *antigravity muscles* because, at least part of the time, they resist the pull of gravity and prevent us from falling or slumping over. Many muscles also stabilize the joints by maintaining tension on tendons and bones.
- **Control of body openings and passages.** Muscles encircling the mouth serve not only for speech but also for food intake and retention of food while chewing. In the eyelid and pupil, they regulate the admission of light to the eye. Internal muscular rings control the movement of food, bile, blood, and other materials within the body. Muscles encircling the urethra and anus control the elimination of waste.
- **Heat production.** Body heat is necessary for enzymes to function and regulate one's metabolism. The skeletal muscles produce 20% to 30% of our body heat at rest and up to 40 times as much during exercise.
- **Glycemic control.** This means the regulation of blood glucose within normal limits. The skeletal muscles absorb, store, and use a large share of one's glucose and play a significant role in stabilizing its blood concentration. In old age, in obesity, and when muscles become deconditioned and weakened, people suffer an increased risk of type 2 diabetes mellitus because of the decline in this glucose-buffering function.

Universal Properties of Muscle

To carry out the foregoing functions, muscle cells must have the following properties:

- **Excitability (responsiveness).** This is a property of all living cells, but it is developed to the highest degree in muscle and nerve cells. When stimulated by chemical signals, stretch, and other stimuli, muscle cells exhibit electrical and mechanical responses.
- **Conductivity.** Local electrical excitation produced at the point of muscle stimulation is conducted throughout the entire plasma membrane, stimulating all regions of the muscle cell and initiating the events that lead to contraction.
- **Contractility.** Muscle cells are unique in their ability to shorten substantially when stimulated. This enables them to pull on bones and other organs to create movement.
- **Extensibility.** Most cells rupture if they are stretched even a little, but skeletal muscle cells are unusually extensible; they can stretch to as much as three times their contracted length without harm. If not for this property, the muscle on one side of a joint would resist the action of a muscle on the other side. An elbow flexor such as the *biceps brachii,* for example, would resist elbow extension by the *triceps brachii* (see fig. 10.4).
- **Elasticity.** When a muscle cell is stretched and then the tension is released, it recoils to a shorter original length. If not for this elastic recoil, resting muscles would be flabby.

From this point on, this chapter concerns skeletal muscles unless otherwise stated.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. What general function of muscular tissue distinguishes it from other tissue types?
2. What are the basic structural differences between skeletal, cardiac, and smooth muscle?
3. State four functions of the muscular system.
4. State five special properties of muscular tissue that enable it to perform its functions.

10.2 General Anatomy of Muscles

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the connective tissues and associated structural organization of a muscle;
b. explain how muscles are classified by the arrangement of their fiber bundles (fascicles);
c. describe the types of muscle–bone attachments;
d. describe the parts of a typical muscle;
e. describe the way that muscles are arranged in groups with complementary actions at a joint;
f. explain what intrinsic and extrinsic muscles are; and
g. describe three types of musculoskeletal levers and their respective advantages.

Connective Tissues and Fascicles

A skeletal muscle is more than muscular tissue. It also contains connective tissue, nerves, and blood vessels. The connective tissue components, from the smallest to largest and from deep to superficial, are as follows (fig. 10.2):

- **Endomysium**[3] (EN-doe-MIZ-ee-um). This is a thin sleeve of loose connective tissue that surrounds each muscle fiber. It creates room for blood capillaries and nerve fibers to reach every muscle fiber. The endomysium also provides the extracellular chemical environment for the muscle fiber and its associated nerve ending. Excitation of a muscle fiber is based on the exchange of calcium, sodium, and potassium ions between the endomysial tissue fluid and the nerve and muscle fibers.

---

[3] *endo* = within; *mys* = muscle


Tendon
Fascia
Skeletal muscle
Muscle fascicle
Nerve
Blood vessels
Epimysium
Perimysium
Endomysium
Muscle fiber
Muscle fascicle
Perimysium
Muscle fiber
(a)
Posterior
Lateral
Medial
Anterior
Skin
Subcutaneous fat
Fascia
Vein
Artery
Nerve
Femur
Fascicles
Individual muscle
(b)
Perimysium
Endomysium
Muscle fiber, c.s.
Fascicle, c.s.
Muscle fiber, l.s.
Fascicle, l.s.
(c)

© Victor Eroschenko

Figure 10.2 **The Connective Tissues of a Skeletal Muscle.** (a) The muscle–bone attachment. There is a continuity of connective tissue from endomysium around the muscle fibers to the perimysium, epimysium, fascia, and tendon, grading into the periosteum and finally the matrix of the bone. (b) A cross section of the thigh showing the relationship of neighboring muscles to fascia and bone. (c) Muscle fascicles in the tongue. Vertical fascicles passing between the superior and inferior surfaces of the tongue are seen alternating with cross-sectioned horizontal fascicles that pass from the tip to the rear of the tongue. A fibrous perimysium can be seen between the fascicles, and endomysium can be seen between individual muscle fibers within each fascicle. (c.s. = cross section; l.s. = longitudinal section)

- **Perimysium.**[4] This is a thicker connective tissue sheath that wraps muscle fibers together in bundles called **fascicles**[5] (FASS-ih-culs). Fascicles are visible to the naked eye as parallel strands—the "grain" in a cut of meat; tender roast beef is easily pulled apart along its fascicles. The perimysium carries the larger nerves and blood vessels as well as stretch receptors called muscle spindles (see p. 463).
- **Epimysium.**[6] This is a fibrous sheath that surrounds the entire muscle. On its outer surface, the epimysium grades into the fascia, and its inner surface issues projections between the fascicles to form the perimysium.
- **Fascia** (FASH-ee-uh). This is a sheet of connective tissue that separates neighboring muscles or muscle groups from each other and from the subcutaneous tissue. Muscles are grouped in *compartments* separated from each other by fascia.

Fascicles and Muscle Shapes

The strength of a muscle and the direction of its pull are determined partly by the orientation of its fascicles. Muscles can be classified according to fascicle orientation as follows (fig. 10.3):

- **Fusiform**[7] **muscles** are thick in the middle and tapered at each end. The *biceps brachii* of the arm and *gastrocnemius* of

---

[4] *peri* = around
[5] *fasc* = bundle; *icle* = little
[6] *epi* = upon, above
[7] *fusi* = spindle; *form* = shape



Figure 10.3 **Classification of Muscles According to Fascicle Orientation.** The fascicles are the "grain" visible in each illustration.
• *Why could some parallel muscles be stronger than some pennate muscles?*

the calf are examples of this type. Strength is proportional to a muscle's diameter at its thickest point, and fusiform muscles are relatively strong.

- **Parallel muscles** have a fairly uniform width and parallel fascicles. Some of these are elongated straps, such as the *rectus abdominis* of the abdomen, *sartorius* of the thigh, and *zygomaticus major* of the face. Others are more squarish and are called *quadrilateral* (four-sided) muscles, such as the *masseter* of the jaw. Parallel muscles can span long distances, such as from hip to knee, and they shorten more than other muscle types. However, having fewer muscle fibers than fusiform muscles of comparable mass, they produce less force.
- **Triangular (convergent) muscles** are fan-shaped—broad at one end and narrower at the other. Examples include the *pectoralis major* in the chest and the *temporalis* on the side of the head. Despite their small localized attachments to a bone, these muscles are relatively strong because they contain a large number of fibers in the wider part of the muscle.
- **Pennate**[8] **muscles** are feather-shaped. Their fascicles lead obliquely to a tendon that runs the length of the muscle, like the shaft of a feather. There are three types of pennate muscles: *unipennate,* in which all fascicles approach the tendon from one side (for example, the *palmar interosseous muscles* of the hand and *semimembranosus* of the thigh); *bipennate,* in which fascicles approach the tendon from both sides (for example, the *rectus femoris* of the thigh); and *multipennate,* shaped like a bunch of feathers with their quills converging on a single point (for example, the *deltoid* of the shoulder). These muscles generate more force than the preceding types because they fit more muscle fibers into a given length of muscle.
- **Circular muscles (sphincters)** form rings around certain body openings. When they contract, they constrict the opening and tend to prevent the passage of material through it. Examples include the *orbicularis oculi* of the eyelids and the *external urethral* and *anal* sphincters. Smooth muscle can also form sphincters—for example, the *pyloric valve* at the passage from the stomach to the small intestine and internal sphincters of the urinary tract and anal canal.

Muscle Attachments

Skeletal muscles attach to bones through extensions of their connective tissue components. There are two forms of attachment—*indirect* and *direct.*

In an **indirect attachment,** the muscle ends conspicuously short of its bony destination, and the gap is bridged by a fibrous band or sheet called a **tendon.** See, for example, the two ends of the biceps brachii in figure 10.4 and the photographs in figures 12.10b (p. 308) and 12.15 (p. 317). You can easily palpate tendons and feel their texture just above the heel (your *calcaneal* or *Achilles tendon*) and on the anterior side of the wrist (tendons of the *palmaris longus* and *flexor carpi radialis* muscles). Collagen fibers of the muscle (the endo-, peri-, and epimysium) continue into the tendon and from there into the periosteum and matrix of the bone, creating very strong structural continuity from muscle to bone. The thick midregion of a muscle between its tendons is called the **belly**.

In some cases, the tendon is a broad sheet called an **aponeurosis**[9] (AP-oh-new-RO-sis). This term originally referred to the tendon located beneath the scalp, hence the name, but now it also refers to similar tendons associated with certain abdominal, lumbar, hand, and foot muscles. For example, the palmaris longus tendon passes through the wrist and then expands into a fanlike *palmar aponeurosis* beneath the skin of the palm (see fig. 12.8a, p. 305).

In a **direct (fleshy) attachment,** there is so little separation between muscle and bone that to the naked eye, the red muscular tissue seems to emerge directly from the bone—for example,

---

[8] *penna* = feather; *ate* = characterized by

[9] *apo* = upon, above; *neuro* = nerve, nervous tissue



Figure 10.4 **Muscle Groups Acting on the Elbow.** The biceps brachii and brachialis are synergists in elbow flexion. The brachialis is the prime mover in flexion. The triceps brachii is an antagonist of these two muscles and is the prime mover in elbow extension.

- *Which of these muscles have direct attachments to the bones, and which have indirect attachments?*

along the margins of the *brachialis* and lateral head of the *triceps brachii* in figure 10.4. At a microscopic level, however, the muscle fibers stop slightly short of the bone, and the gap between muscle and bone is spanned by collagen fibers that penetrate into the bone.

Some authorities contend that the tendons and other collagenous tissues stretch and recoil significantly during muscle action and contribute to the power output and efficiency of a muscle. When you are running, for example, recoil of the calcaneal tendon may help to lift the heel and produce some of the thrust as your toes push off from the ground. (Such recoil contributes significantly to the long, energy-efficient leaping of kangaroos.) Others feel the elasticity of these components is negligible in humans and that the recoil is produced entirely by certain intracellular proteins of the muscle fibers themselves.

Muscle Origins and Insertions

Most skeletal muscles are attached to a different bone at each end, so either the muscle or its tendon spans at least one joint. When the muscle contracts, it moves one bone relative to the other. Traditionally, the bony site of attachment at the relatively stationary end has been called the *origin* of the muscle, and the attachment at the more mobile end has been called its *insertion*. The terminology of origins and insertions, however, was imperfect and sometimes misleading. One end of a muscle can function as its stationary origin during one action, but as its moving insertion during a different action. For example, consider the *quadriceps femoris* muscle on the anterior side of the thigh. It is a powerful extensor of the knee, connected at its proximal end mainly to the femur and at its distal end to the tibia, just below the knee. If you kick a soccer ball, the tibia moves more than the femur, so the tibia would be considered the insertion of the quadriceps and the femur would be considered its origin. But when you stand up from a chair, the tibia remains stationary and the femur moves. By the foregoing definitions, the tibia would now be considered the origin of the quadriceps and the femur would be its insertion.

Similarly, consider the difference in the relative movements of the humerus and ulna when flexing the elbow to lift dumbbells as compared with flexing the elbow to perform chin-ups or scale a climbing wall. For such reasons, *Gray's Anatomy* and other authorities have lately abandoned origin and insertion terminology and speak instead of a muscle's proximal and distal or superior and inferior attachments, especially in the limbs.

Some muscles attach to tissues other than bone, such as the fascia or tendon of another muscle or the dermis of the skin. The distal tendon of the biceps brachii, for example, attaches partly to the fascia of the forearm. Many facial muscles attach to the dermis, enabling them to produce expressions such as a smile.

Functional Groups of Muscles

The effect produced by a muscle, whether it is to produce or prevent a movement, is called its **action.** Skeletal muscles seldom act independently; instead, they function in groups whose combined actions produce the coordinated control of a joint. Muscles can be classified into four categories according to their actions, but it must be stressed that a particular muscle can act in a certain way during one joint action and in a different way during other actions of the same joint. The following examples are illustrated in figure 10.4:

1. The **prime mover (agonist)** is the muscle that produces most of the force during a particular joint action. In flexing the elbow, for example, the prime mover is the *brachialis.*
2. A **synergist**[10] (SIN-ur-jist) is a muscle that aids the prime mover. Two or more synergists acting on a joint can produce more power than a single larger muscle. The *biceps brachii,* for example, overlies the brachialis and works with it as a synergist to flex the elbow. The actions of a prime mover and its synergist are not necessarily identical and redundant. If the prime mover worked alone at a joint, it might cause rotation or other undesirable movements of a bone. A synergist may stabilize a joint and restrict these movements, or modify the direction of a movement so that the action of the prime mover is more coordinated and specific.
3. An **antagonist**[11] is a muscle that opposes the prime mover. In some cases, it relaxes to give the prime mover almost complete control over an action. More often, however, the

---

[10] *syn* = together; *erg* = work
[11] *ant* = against; *agonist* = actor, competitor

antagonist maintains some tension on a joint and thus limits the speed or range of the prime mover, preventing excessive movement, joint injury, or inappropriate actions. If you extend your arm to reach out and pick up a cup of tea, for example, your *triceps brachii* serves as the prime mover of elbow extension, and your brachialis acts as an antagonist to slow the extension and stop it at the appropriate point. If you extend your arm rapidly to throw a dart, however, the brachialis must be quite relaxed. The brachialis and triceps represent an **antagonistic pair** of muscles that act on opposite sides of a joint. We need antagonistic pairs at a joint because a muscle can only pull, not push—for example, a single muscle cannot flex *and* extend the elbow. Which member of the pair acts as the prime mover depends on the motion under consideration. In flexion of the elbow, the brachialis is the prime mover and the triceps is the antagonist; when the elbow is extended, their roles are reversed.

4. A **fixator** is a muscle that prevents a bone from moving. To *fix* a bone means to hold it steady, allowing another muscle attached to it to pull on something else. For example, consider again the flexion of the elbow by the biceps brachii. The biceps extends from the scapula to the radius. The scapula is loosely attached to the axial skeleton, so when the biceps contracts, it seems that it would pull the scapula laterally. However, there are fixator muscles (the *rhomboids*) that attach the scapula to the vertebral column. They contract at the same time as the biceps, holding the scapula firmly in place and ensuring that the force generated by the biceps moves the radius rather than the scapula.

Intrinsic and Extrinsic Muscles

In places such as the tongue, larynx, back, hand, and foot, anatomists distinguish between intrinsic and extrinsic muscles. An **intrinsic muscle** is entirely contained within a particular region, having both of its attachments there. An **extrinsic muscle** acts upon a designated region but originates elsewhere. For example, some movements of the fingers are produced by extrinsic muscles in the forearm, whose long tendons reach to the phalanges; other finger movements are produced by intrinsic muscles between the metacarpal bones.

Muscles, Bones, and Levers

Many bones, especially the long bones, act as levers on which the muscles exert their force. A **lever** is any elongated, rigid object that rotates around a fixed point called the **fulcrum** (fig. 10.5). Rotation occurs when an **effort** applied to one point on the lever overcomes a **resistance (load)** located at some other point. The part of a lever from the fulcrum to the point of effort is called the **effort arm,** and the part from the fulcrum to the point of resistance is the **resistance arm.** In the body, a bone acts as a lever, a joint serves as the fulcrum, and the effort is generated by a muscle.

The function of a lever is to produce a gain in the speed, distance, or force of a motion—either to exert more force against a resisting object than the force applied to the lever (for example, in moving a heavy object with a crowbar) or to move the resisting object farther or faster than the effort arm is moved (as in rowing a boat). A single lever cannot confer both advantages. There is a trade-off between force on one hand and speed or distance on the other—as one increases, the other decreases.



Figure 10.5 **Basic Components of a Lever.**
• *Is this a first-, second-, or third-class lever? How do you know?*

The **mechanical advantage (MA)** of a lever is the ratio of its output force to its input force. It is equal to the length of the effort arm, L_E, divided by the length of the resistance arm, L_R; that is, $MA = L_E/L_R$. If MA is greater than 1.0, the lever produces more force, but less speed or distance, than the force exerted on it. If MA is less than 1.0, the lever produces more speed or distance, but less force, than the input. Consider the forearm, for example (fig. 10.6a). The resistance arm of the ulna is longer than the effort arm, so we know from the preceding formula that the mechanical advantage is less than 1.0. The figure shows some representative values for L_E and L_R that yield $MA = 0.15$. The brachialis puts more power into the ulna than we get out of it, but the hand moves farther and faster than the ulnar attachment of the brachialis tendon. By contrast, when the digastric muscle depresses the mandible, the MA is about 2.7. The coronoid process of the mandible moves with greater force, but a shorter distance, than the mental protuberance of the chin (fig. 10.6b).

DEEPER INSIGHT 10.1

Muscle-Bound

Any well-planned program of resistance (strength) training or bodybuilding must include exercises aimed at proportional development of the different members of a muscle group, such as flexors and extensors of the arm. Otherwise, the muscles on one side of a joint may develop out of proportion to their antagonists and restrict the joint's range of motion (ROM). If the biceps brachii is heavily developed without proportionate attention to the triceps brachii, for example, the stronger biceps will cause the elbow to be somewhat flexed constantly, and the ROM of the elbow will be restricted. The joint is then said to be "muscle-bound." People with muscle-bound joints move awkwardly and are poor at activities that require agility, such as dance and ball games.



Figure 10.6 **Mechanical Advantage (MA).** MA is calculated as the length of the effort arm divided by the length of the resistance arm. (a) The forearm acts as a third-class lever during flexion of the elbow. (b) The mandible acts as a second-class lever when the jaw is forcibly opened. The digastric muscle and others provide the effort, while tension in the temporalis muscle and others provides the resistance.

As we have already seen, some joints have two or more muscles acting on them that seemingly produce the same effect, such as elbow flexion. At first, you might consider this arrangement redundant, but it makes sense if the tendinous attachments of the muscles are at slightly different places and produce different mechanical advantages. A runner taking off from the starting line, for example, uses "low-gear" (high-MA) muscles that do not generate much speed but have the power to overcome the inertia of the body. A runner then "shifts into high gear" by using muscles with different attachments that have a lower mechanical advantage but produce more speed at the feet. This is analogous to the way an automobile transmission works to get a car moving and then shifts gears to cruise at high speed.

There are three classes of levers that differ with respect to which component is in the middle—the fulcrum (F), effort (E), or resistance (R). A **first-class lever** (fig. 10.7a) is one with the fulcrum in the middle (EFR), such as a seesaw. An anatomical example is the atlanto–occipital joint of the neck, where the muscles of the back of the neck pull down on the occipital bone of the skull and oppose the tendency of the head to tip forward. Loss of muscle tone here can be embarrassing if you nod off in class.

A **second-class lever** (fig. 10.7b) is one in which the resistance is in the middle (FRE). Lifting the handles of a wheelbarrow, for example, makes it pivot on its wheel at the opposite end and lift a load in the middle. If you sit in a chair and raise one knee, as in bouncing a child on your knee, the femur pivots on the hip joint (the fulcrum), the quadriceps muscle of the anterior thigh elevates the tibia like the wheelbarrow handles, and the resistance is the weight of the child or of the thigh itself.

In a **third-class lever** (fig. 10.7c), the effort is applied between the fulcrum and resistance (FER). For example, in paddling a canoe, the relatively stationary grip at the upper end of the paddle is the fulcrum, the effort is applied to the middle of the shaft, and the resistance is produced by the water against the blade. Most musculoskeletal levers are third-class. The forearm acts as a third-class lever when you flex your elbow. The fulcrum is the joint between the ulna and humerus; the effort is applied by the brachialis and biceps brachii muscles; and the resistance can be provided by any weight in the hand or the weight of the forearm itself. The mandible acts as a third-class lever when you close your mouth to bite off a piece of food. The temporomandibular joint is the fulcrum, the temporalis muscle exerts the effort at the coronoid process of the mandible, and the resistance is supplied by the item of food being bitten.

Apply What You Know

Sit on the edge of a desk with your feet off the floor. Plantarflex your foot. Where is the effort? Where is the fulcrum? (Name the specific joint, based on chapter 9.) Where is the resistance? Which class of lever does the foot represent in plantar flexion?


Resistance
Effort
R
E
F
Fulcrum
R
Resistance
Effort
E
F
Fulcrum
F
Resistance
Effort

(a) First-class lever


Resistance
R
E
F
Effort
Fulcrum
Resistance
R
E
Effort
F
Fulcrum
Effort
Resistance
F

(b) Second-class lever


Resistance
Effort
E
R
F
Fulcrum
Fulcrum
F
E
Effort
Resistance
R
Resistance
Effort
F

(c) Third-class lever

Figure 10.7 **The Three Classes of Levers.** *Left:* The lever classes defined by the relative positions of the resistance (load), fulcrum, and effort. *Center:* Mechanical examples. *Right:* Anatomical examples. (a) Muscles at the back of the neck pull down on the occipital bone to oppose the tendency of the head to tip forward. The fulcrum is the occipital condyles. (b) In a sitting position, the quadriceps muscle of the anterior thigh elevates the leg. The fulcrum is the hip joint. (c) In flexing the elbow, the biceps brachii exerts an effort on the radius. Resistance is provided by the weight of the forearm or anything held in the hand. The fulcrum is the elbow joint.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

5. Name the connective tissue layers of a muscle beginning with the individual muscle fiber and ending with the tissue that separates the muscles from the skin.
6. Sketch the fascicle arrangements that define a fusiform, parallel, convergent, pennate, and circular muscle.
7. Define the *action* of a muscle.
8. Distinguish between a prime mover, synergist, antagonist, and fixator.
9. What is the difference between intrinsic and extrinsic muscles that control the fingers?
10. What is the principal benefit of a joint action with a mechanical advantage less than 1.0? What is the principal benefit of a joint action with a mechanical advantage greater than 1.0?
11. Define a *first-, second-,* and *third-class lever* and give an example of each in the musculoskeletal system.

10.3 Microscopic Anatomy of Skeletal Muscle

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the ultrastructure of a muscle fiber and its myofilaments;
b. explain what accounts for the striations of skeletal muscle;
c. describe the relationship of a nerve fiber to a muscle fiber;
d. define a *motor unit* and discuss its functional significance; and
e. describe the blood supply to a skeletal muscle.

Ultrastructure of Muscle Fibers

In order to understand muscle function, you must know how the organelles and macromolecules of a muscle fiber are arranged. Perhaps more than any other cell, a muscle fiber exemplifies the adage, form follows function. It has a complex, tightly organized internal structure in which even the spatial arrangement of protein molecules is closely tied to its contractile function (fig. 10.8).



Figure 10.8 Structure of a Skeletal Muscle Fiber. This is a single cell containing 11 myofibrils (9 shown at the left and 2 cut off at midfiber). A few myofilaments are shown projecting from the myofibril at the left. Their finer structure is shown in figure 10.9.
- *Why is it important for the transverse tubule to be so closely associated with the terminal cisternae?*

The plasma membrane is called the **sarcolemma**[12] and the cytoplasm is called the **sarcoplasm.** The sarcoplasm is occupied mainly by anywhere from several dozen to a thousand or more long protein bundles called **myofibrils,** each about 1 µm in diameter. It also contains an abundance of **glycogen,** a starchlike carbohydrate that provides energy for the cell during periods of heightened exercise, and the red pigment **myoglobin,** which provides some of the oxygen needed for muscular activity.

Muscle fibers have numerous flattened or sausage-shaped nuclei pressed against the inside of the sarcolemma. This unusual multinuclear condition results from the embryonic development of the muscle fiber, as we will see near the end of this chapter. Most other organelles of the cell, such as mitochondria, are packed into the spaces between the myofibrils. The smooth endoplasmic reticulum, here called the **sarcoplasmic reticulum (SR),** forms a network around each myofibril (the blue web in fig. 10.8). It periodically exhibits dilated end sacs called **terminal cisternae,** which cross the muscle fiber from one side to the other. The sarcolemma turns inward at many points to form tunnels called **transverse (T) tubules,** which penetrate through the cell and emerge on the other side. Each T tubule is intimately associated with two terminal cisternae, which run alongside it. The T tubule carries electrical signals from the cell surface into the interior and induces gates in the SR membrane to open. The SR is a reservoir of calcium ions (Ca^{2+}). On command, it opens the gates and releases a flood of Ca^{2+} into the cytosol, and the Ca^{2+} activates muscle contraction.

Myofilaments

Each myofibril is composed of parallel protein microfilaments called **myofilaments.** The key to muscle contraction lies in the arrangement and action of these myofilaments, so we must examine these at a molecular level. There are three kinds of myofilaments:

1. **Thick filaments** (fig. 10.9a, b) are about 15 nm in diameter. Each is made of several hundred molecules of a protein called **myosin.** A myosin molecule is shaped like a golf club, with two chains that intertwine to form a shaftlike *tail* and a double globular *head* projecting from it at an angle. A thick filament may be likened to a bundle of 200 to 500 such "golf clubs," with their heads directed outward in a helical array around the bundle. The heads on one half of the thick filament angle to the left, and the heads on the other half angle to the right; in the middle is a *bare zone* with no heads.
2. **Thin filaments** (fig. 10.9c, d), 7 nm in diameter, are composed primarily of two intertwined strands of a protein called **fibrous (F) actin.** Each F actin is like a bead necklace, consisting of a string of subunits called **globular (G) actin.** Each G actin has an **active site** that can bind to the head of a myosin molecule (see fig. 10.14).

   A thin filament also has 40 to 60 molecules of yet another protein called **tropomyosin.** When a muscle fiber is relaxed, tropomyosin blocks the active sites of actin and prevents myosin from binding to them. Each tropomyosin molecule, in turn, has a smaller calcium-binding protein called **troponin** bound to it.



(a) Myosin molecule



(b) Thick filament



(c) Thin filament



(d) Portion of a sarcomere showing the overlap of thick and thin filaments

Figure 10.9 Molecular Structure of Thick and Thin Filaments. (a) A single myosin molecule consists of two intertwined proteins forming a filamentous tail and a double globular head. (b) A thick filament consists of 200 to 500 myosin molecules bundled together with the heads projecting outward in a helical array. (c) A thin filament consists of two intertwined chains of G actin molecules, smaller filamentous tropomyosin molecules, and a calcium-binding protein called troponin associated with the tropomyosin. (d) A region of overlap between the thick and thin myofilaments.

---

[12] *sarco* = flesh, muscle; *lemma* = husk

3. **Elastic filaments** (fig. 10.10b), 1 nm in diameter, are made of a huge springy protein called **titin**[13] **(connectin).** They run through the core of each thick filament and anchor it to structures called the *Z discs* at one end and *M line* at the other. This stabilizes the thick filament, centers it between the thin filaments, prevents overstretching, and contributes to elastic recoil when the muscle relaxes.

Myosin and actin are called **contractile proteins** because they do the work of shortening the muscle fiber. Tropomyosin and troponin are called the **regulatory proteins** because they act like a switch to determine when the fiber can contract and when it cannot.

At least seven other accessory proteins occur in the thick and thin filaments or are associated with them. They anchor the myofilaments, regulate their length, and keep them aligned with each other for optimal contractile effectiveness. The most clinically important of these is **dystrophin,** an enormous protein located just under the sarcolemma in the vicinity of each *I band* of the striations described in the next section. It links the actin filaments to transmembrane proteins in the sarcolemma. These, in turn, are linked to proteins immediately external to the muscle fiber and ultimately to the endomysium. Thus, it is dystrophin that links the shortening of components within the fiber to a mechanical pull on the connective tissue external to the muscle fiber. Genetic defects in dystrophin are responsible for the disabling disease, muscular dystrophy (see p. 259).

Striations and Sarcomeres

Myosin and actin are not unique to muscle; these proteins occur in all cells, where they function in cellular motility, mitosis, and transport of intracellular materials. In skeletal and cardiac muscle they are especially abundant, however, and are organized into a precise array that accounts for the striations of these two muscle types (fig. 10.10).

Striated muscle has dark **A bands** alternating with lighter **I bands.** (*A* stands for *anisotropic* and *I* for *isotropic,* which refer to the way these bands affect polarized light. To help remember which band is which, think "dArk" and "lIght.") Each A band consists of thick filaments lying side by side. Part of the A band, where thick and thin filaments overlap, is especially dark. In this region, each thick filament is surrounded by six thin filaments arranged in an orderly hexagon. In the middle of the A band, there is a lighter region called the **H band,**[14] into which the thin filaments do not reach. A dark **M line** in the middle of the H band is a region in which the thick filaments are anchored to a protein that crosses the myofibril.

Each light I band is bisected by a dark, narrow, coin-shaped **Z disc**[15] **(Z line),** which provides anchorage for the thin filaments



© Don W. Fawcett/ Science Source

Figure 10.10 Muscle Striations and Their Molecular Basis. (a) Five myofibrils of a single muscle fiber, showing the striations in the relaxed state (TEM). (b) The overlapping pattern of thick and thin myofilaments that accounts for the striations seen in part (a). AP|R

---

[13] *tit* = giant; *in* = protein

[14] H = *helle* = bright (German)

[15] Z = *Zwischenscheibe* = between disc (German)

and elastic filaments. Each segment of a myofibril from one Z disc to the next is called a **sarcomere**[16] (SAR-co-meer), the functional contractile unit of the muscle fiber. A muscle shortens because its individual sarcomeres shorten and pull the Z discs closer to each other, and dystrophin and the linking proteins pull on the extracellular proteins of the muscle.

Table 10.1 reviews the organization of skeletal muscle at successive structural levels from the whole muscle to the molecular myofilaments.

---

[16] *sarco* = muscle; *mere* = part, segment

TABLE 10.1 The Structural Hierarchy of a Skeletal Muscle

Structural Level	Description
Muscle  Muscle Muscle fibers Tendon Fascicles Epimysium Perimysium	A contractile organ, usually attached to bones by way of tendons, composed of bundles (fascicles) of tightly packed, long, parallel cells (muscle fibers). Supplied with nerves and blood vessels and enclosed in a fibrous epimysium separating it from neighboring muscles.
Fascicle  Muscle fibers Perimysium	A bundle of muscle fibers within a muscle. Supplied by nerves and blood vessels and enclosed in a fibrous perimysium separating it from neighboring fascicles.
Muscle Fiber  Z disc Sarcolemma Myofibrils Myofilaments	A single muscle cell. Slender, elongated, threadlike, enclosed in a plasma membrane (sarcolemma). Contains densely packed bundles (myofibrils) of contractile protein filaments, multiple nuclei immediately beneath the sarcolemma, and an extensive network of specialized smooth endoplasmic reticulum (sarcoplasmic reticulum). Enclosed in a thin fibrous sleeve called endomysium.
Myofibril  T tubule Z disc Myofilaments: Thick Thin Sarcoplasmic reticulum	A bundle of protein myofilaments within a muscle fiber. Myofibrils fill most of the cytoplasm. Each surrounded by sarcoplasmic reticulum and mitochondria. Has a banded (striated) appearance due to orderly overlap of protein myofilaments.
Sarcomere  Sarcomere Thick filament Thin filament Z-disc Z-disc	A segment of myofibril from one Z disc to the next in the fiber's striation pattern. Hundreds of end-to-end sarcomeres compose a myofibril. The functional, contractile unit of the muscle fiber.
Myofilaments  Thick filament Thin filament	Fibrous protein strands that carry out the contraction process. Two types: thick filaments composed mainly of myosin, and thin filaments composed mainly of actin. Thick and thin filaments slide over each other to shorten each sarcomere. Shortening of end-to-end sarcomeres shortens the entire muscle.

The Nerve–Muscle Relationship

Skeletal muscle never contracts unless it is stimulated by a nerve (or artificially with electrodes). If its nerve connections are severed or poisoned, a muscle is paralyzed. Thus, muscle contraction cannot be understood without first understanding the relationship between nerve and muscle cells. Any point where a nerve fiber meets and stimulates another cell is called a **synapse** (SIN-aps). The other cell can be another neuron, a gland cell, a muscle cell, or other type of cell. The heart of the nerve–muscle relationship is the synapse formed by a nerve cell and a skeletal muscle fiber.

Motor Neurons

Skeletal muscles are innervated by nerve cells called *somatic motor neurons* (see fig. 3.24, p. 72). The cell bodies of these neurons lie in the brainstem and spinal cord; their axons, called **somatic motor fibers,** lead to the skeletal muscles. At its distal end, each somatic motor fiber branches out to innervate a number of muscle fibers, but any given muscle fiber is supplied by only one motor neuron.

The Neuromuscular Junction

As a nerve fiber approaches an individual muscle fiber, it branches again to establish several points of contact within an ovoid region called the **neuromuscular junction (NMJ),** or **motor end plate** (fig. 10.11). Each terminal branch of the nerve fiber within the NMJ forms a synapse with the muscle fiber. The sarcolemma of the NMJ is irregularly indented, a little like a handprint pressed into soft clay. If you imagine the nerve fiber to be like your forearm and your hand to be spread out in this handprint, the individual synapses would be like the points where your fingertips contact the clay. Thus, one nerve fiber stimulates the muscle fiber at several points within each NMJ.

At each synapse, the nerve fiber ends with a bulbous swelling called a **presynaptic terminal.** The terminal doesn't directly touch the muscle fiber, but is separated from it by a narrow space called the **synaptic cleft,** about 60 to 100 nm wide (scarcely wider than the thickness of one plasma membrane). A third cell, called a *Schwann cell,* envelops the entire junction and isolates it from the surrounding tissue fluid.


Motor nerve fibers
Neuromuscular junction
Muscle fibers
(a)
100 µm
Motor nerve fiber
Myelin
Schwann cell
Presynaptic terminal
Basal lamina
Synaptic vesicles (containing ACh)
Sarcolemma
Synaptic cleft
Nucleus
ACh receptor
Junctional folds
Nucleus
Mitochondria
Sarcoplasm
Myofilaments
(b)

© Victor B. Eichler

Figure 10.11 **Innervation of Skeletal Muscle.** (a) Neuromuscular junctions, with muscle fibers slightly teased apart (LM; compare the SEM on page 235). (b) Structure of a single neuromuscular junction.

The presynaptic terminal contains spheroid organelles called **synaptic vesicles,** which are filled with a chemical called **acetylcholine (ACh)** (ASS-eh-till-CO-leen). When a nerve signal arrives at the terminal, some of these vesicles release their ACh by exocytosis. ACh diffuses across the synaptic cleft and binds to membrane proteins called **ACh receptors** on the sarcolemma. These receptors respond to ACh by initiating electrical events that lead to muscle contraction. The sarcolemma has infoldings called **junctional folds** that increase the membrane surface area and allow for more ACh receptors, and thus more sensitivity of the muscle fiber to nervous stimulation.

DEEPER INSIGHT 10.2

Neuromuscular Toxins and Paralysis

Toxins that interfere with synaptic function can paralyze the muscles. Organophosphate pesticides such as malathion contain *cholinesterase inhibitors* that bind to AChE and prevent it from degrading ACh. Depending on the dose, this can prolong the action of ACh and produce *spastic paralysis,* a state in which the muscles contract and cannot relax. Clinically, this is called a *cholinergic crisis*. It poses the danger of suffocation if it affects the laryngeal and respiratory muscles. *Tetanus* (lockjaw) is a form of spastic paralysis caused by the toxin of a soil bacterium, *Clostridium tetani.* In the spinal cord, a chemical called glycine normally stops motor neurons from producing unwanted muscle contractions. The tetanus toxin blocks glycine release and thus causes overstimulation and spastic paralysis of the muscles.

Flaccid paralysis is a state in which the muscles are limp and cannot contract. This too can cause respiratory arrest if it affects the thoracic muscles. Flaccid paralysis can be caused by poisons such as curare (cue-RAH-ree), which competes with ACh for receptor sites but does not stimulate the muscle. Curare is extracted from certain plants and used by some South American natives to poison blowgun darts. It has been used to treat muscle spasms in some neurological disorders and to relax abdominal muscles for surgery, but other muscle relaxants have now replaced curare for most purposes.

Botulism is a type of food poisoning caused by a neuromuscular toxin secreted by the bacterium *Clostridium botulinum.* Botulinum toxin blocks the release of ACh and causes flaccid muscle paralysis. Purified botulinum toxin was approved by the U.S. Food and Drug Administration (FDA) in 2002 for cosmetically treating “frown lines” caused by muscle tautness between the eyebrows. Marketed as Botox Cosmetic (a prescription drug despite the name), it is injected in small doses into specific facial muscles. The wrinkles gradually disappear as flaccid paralysis sets in over the next few hours. The effect lasts about 4 months until the muscles retighten and the wrinkles return. Botox treatment has become the fastest-growing cosmetic medical procedure in the United States, with many people going for treatment every few months in their quest for a youthful appearance. It has begun to have some undesirable consequences, however, as it is sometimes administered by unqualified practitioners. Even some qualified physicians use it for treatments not yet approved by the FDA, and some host festive “Botox parties” for treatment of patients in assembly-line fashion.

The entire muscle fiber is surrounded by a *basal lamina,* a thin layer composed partly of collagen and glycoproteins, which separates it from the surrounding connective tissue. The basal lamina passes through the synaptic cleft and virtually fills it, and covers the Schwann cell of the neuromuscular junction. An enzyme called **acetylcholinesterase (AChE)** (ASS-eh-till-CO-lin-ESS-ter-ase) is found in both the sarcolemma and basal lamina. It breaks down ACh after the ACh has stimulated the muscle cell; thus, it is important in turning off muscle contraction (see Deeper Insight 10.2).

The Motor Unit

When a nerve signal approaches the end of an axon, it spreads out over all of its terminal branches and stimulates all muscle fibers supplied by them. These muscle fibers therefore contract in unison. Since they behave as a single functional unit, one nerve fiber and all the muscle fibers innervated by it are called a **motor unit.** The muscle fibers of a single motor unit are not clustered together but are dispersed throughout a muscle (fig. 10.12). Thus, when they are stimulated, they cause a weak contraction over a wide area—not just a localized twitch in one small region. Effective muscle contraction usually requires the activation of several motor units at once.

On average, there are about 200 muscle fibers per motor neuron. But where fine control is needed, we have *small motor units.* In the muscles of eye movement, for example, there are about 3 to 6 muscle fibers per nerve fiber. Small motor units are not very strong, but they provide the fine degree of control needed



Figure 10.12 **Motor Units.** A motor unit consists of one motor neuron and all skeletal muscle fibers that it innervates. Two motor units here are represented by the red and blue nerve and muscle fibers. Note that the muscle fibers of a motor unit are not clustered together, but distributed throughout the muscle and commingled with the fibers of other motor units.

for subtle movements. They also have small neurons that are easily stimulated. Where strength is more important than fine control, we have *large motor units.* The gastrocnemius muscle of the calf, for example, has about 1,000 muscle fibers per nerve fiber. Large motor units are much stronger, but have larger neurons that are harder to stimulate, and they do not produce such fine control.

One advantage of having multiple motor units in a muscle is that they are able to "work in shifts." Muscle fibers fatigue when subjected to continual stimulation. If all of the fibers in one of your postural muscles fatigued at once, for example, you might collapse. To prevent this, other motor units take over while the fatigued ones rest, and the muscle as a whole can sustain long-term contraction. Another advantage is that the strength of muscle contraction can be varied by activating more or fewer motor units.

The Blood Supply

The muscular system as a whole receives about 1.25 L of blood per minute at rest—which is about one-quarter of the blood pumped by the heart. During heavy exercise, total cardiac output rises, and the muscular system's share of it is more than three-quarters, or 11.6 L/min. Working muscle has a great demand for glucose and oxygen. Blood capillaries ramify through the endomysium to reach every muscle fiber, sometimes so intimately associated with the muscle fibers that the fibers have surface indentations to accommodate them. The capillaries of skeletal muscle undulate or coil when the muscle is contracted (fig. 10.13), allowing them enough slack to stretch out straight, without breaking, when the muscle lengthens.



© Susumu Nishinaga/Science Source

Figure 10.13 A Polymer Cast of the Blood Vessels in a Contracted Skeletal Muscle.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

12. What special terms are given to the plasma membrane, cytoplasm, and smooth ER of a muscle cell?
13. Name the proteins that compose the thick and thin filaments of a muscle fiber and describe their structural arrangement.
14. Define *sarcomere.* Describe the striations of a sarcomere and sketch the arrangement of thick and thin filaments that accounts for the striations.
15. Describe the role of a presynaptic terminal, synaptic vesicles, synaptic cleft, and acetylcholine in neuromuscular function.
16. What is a motor unit? How do large and small motor units differ functionally?
17. Why is it important that the blood capillaries of a contracted muscle have an undulating or coiled arrangement?

10.4 Relating Structure to Function

Expected Learning Outcomes

When you have completed this section, you should be able to

a. explain how a muscle fiber contracts and relaxes, and relate this to its ultrastructure;
b. describe how muscle grows and shrinks with use and disuse; and
c. discuss two physiological categories of muscle fibers and their respective advantages.

Contraction and Relaxation

We noted earlier that a muscle fiber epitomizes the essential unity of form and function. Having examined the structure of a muscle fiber down to its molecular details, our task would be incomplete if we didn't ask ourselves what all of this is for. *Why* are all the molecules and organelles of the muscle fiber so closely packed and in such a precisely organized way? To answer that, we'll look briefly at the essential aspects of muscle contraction and relaxation. These form a cycle of events with four main phases:

1. **Excitation,** in which a nerve fiber releases ACh, ACh excites the muscle fiber, and a wave of electrical excitation spreads into the sarcoplasm by way of the T tubules.
2. **Excitation–contraction coupling,** consisting of events that link this electrical stimulus to the onset of muscle tension. Excitation of the T tubules induces the sarcoplasmic reticulum (SR) to release calcium ions, and calcium clears the way for the myosin of the thick filaments to bind to the actin of the thin filaments.
3. **Contraction,** in which the myosin heads repeatedly attach to the thin filaments and pull on them, causing the thin filaments to slide across the thick filaments and shorten the cell.
4. **Relaxation,** in which nerve signaling ceases, myosin is once again blocked from binding to actin, and muscle tension subsides.

Figure 10.14 shows a few of the finer steps of this process, numbered to correspond to the following description.

Excitation

1 A nerve signal arrives at the presynaptic terminal.

2 The synaptic vesicles release ACh, which diffuses across the synaptic cleft and binds to receptors on the sarcolemma of the muscle fiber. This opens ion gates in the sarcolemma, resulting in sodium and potassium movements through the membrane that electrically excite the muscle fiber.

3 A self-propagating wave of excitation spreads down the length of the fiber and into the T tubules.

Excitation–Contraction Coupling

4 Electrical events in the T tubule lead to the opening of calcium gates in the sarcoplasmic reticulum. The SR releases a flood of calcium ions into the cytosol.

5 Calcium ions bind to troponin molecules in the thin myofilaments. Troponin induces the long tropomyosin molecule to shift position, sinking into the groove between the two F actin filaments and exposing the active sites on the G actin.

6 Meanwhile, myosin has been "waiting" in a flexed position, like a bent elbow, with a molecule of ATP bound to its head. The head contains an enzyme called *myosin ATPase,* which breaks down ATP into adenosine diphosphate (ADP) and an inorganic phosphate group (P_i). The energy liberated by this reaction straightens the myosin head into an extended, high-energy "cocked" position.

Contraction

7 Myosin forms a link, or *cross-bridge,* with one of the active sites of actin, and releases the ADP and P_i.

8 Myosin flexes and tugs on the thin filament, like flexing your elbow to pull in the rope of a boat anchor, and the thin filament slides a short distance along the thick filament. This movement is called the *power stroke.* Myosin binds a new ATP, lets go of the thin filament, breaks down the ATP, and recocks; this is the *recovery stroke.* Whenever one myosin head lets go of the thin filament, other myosin heads hold on, so the thin filament is never entirely released as long as the muscle is contracting. The myosin heads take turns pulling on the actin filament and letting go.

Steps 6 through 8 occur repeatedly. The overall effect is that the thin filament slides smoothly alongside the thick filament; this model of muscle contraction is therefore called the *sliding filament theory.* No myofilaments get shorter during contraction—they merely slide across each other. Since the thin filaments are connected through dystrophin to the sarcolemma and ultimately to the extracellular connective tissue, their sliding shortens the entire cell and its endomysium. If all the myosin heads in a muscle fiber executed a single cycle of power and recovery strokes, the muscle fiber would shorten about 1%. Through repetition of the process, however, a fiber can shorten by as much as 40%.

Relaxation

9 The first step needed to make a muscle fiber relax is to stop stimulating it. The motor neuron stops firing and releasing ACh, so the muscle fiber is no longer electrically excited.

10 The sarcoplasmic reticulum reabsorbs the calcium ions and stores them until the next time the muscle is stimulated. Without calcium, troponin moves back into the position that blocks the active sites and prevents myosin–actin cross-bridges from forming. Thus, the muscle can no longer maintain tension. It relaxes, and the action of gravity or an antagonistic muscle at the same joint stretches it back to its resting length.

Apply What You Know

During muscle contraction, which band(s) of the muscle striations would you expect to become narrower or disappear? Which would remain the same width as in relaxed muscle? Explain.

Muscle Growth and Atrophy

It is common knowledge that muscles grow larger when exercised and shrink when they are not used. This is the basis for *resistance exercises* such as weight lifting. And yet, skeletal muscle fibers are


Nerve signal
Motor nerve fiber
①
Excitation of muscle fiber
Presynaptic terminal
ACh
Synaptic vesicles
②
③
Sarcolemma
ACh receptors
Synaptic cleft
T tubule
Sarcoplasmic reticulum (SR)
Ca^{2+}
Myofilaments
Terminal cisterna of SR
④
Ca^{2+}
⑤
Troponin
Tropomyosin
Actin
Active sites
⑥
ADP
ATP
P_i
Myosin
Cross-bridge
⑦
ADP
P_i
⑧
⑨
⑩

Figure 10.14 **The Principal Events in Muscle Contraction and Relaxation.** Steps 1 to 3 are the excitation phase; steps 4 to 6 are excitation–contraction coupling; contraction entails several repetitions of steps 6 to 8; and steps 9 to 10 are relaxation. See the corresponding numbers on page 251 for explanations of each step.

incapable of mitosis. We have about the same number of muscle fibers in adulthood as we do in late childhood. How, then, does a muscle grow?

Exercise stimulates the muscle fiber to produce more protein myofilaments. As a result, the myofibrils grow thicker. At a certain point, a large myofibril splits longitudinally, so a well-conditioned muscle has more myofibrils per muscle fiber than does a weakly conditioned one. The entire muscle grows in bulk (thickness), not by the mitosis of existing cells (hyperplasia), but by the enlargement of cells that have existed since childhood (hypertrophy). Some authorities, however, think that entire muscle fibers (not just their myofibrils) may split longitudinally when they reach a certain size, thus giving rise to an increase in the number of fibers—not by mitosis but by a process more akin to tearing. Well-exercised muscles also develop more mitochondria, more myoglobin and glycogen, and a greater density of blood capillaries.

When a muscle is not used, it shrinks (atrophies). This can result from spinal cord injuries or other injuries that sever the nerve connections to a muscle *(denervation atrophy),* from lack of exercise *(disuse atrophy),* or from aging *(senescence atrophy).* The shrinkage of a limb that has been in a cast for several weeks is a good example of disuse atrophy. Muscle quickly regrows when exercise resumes, but if the atrophy becomes too advanced, muscle fibers die and are not replaced. Physical therapy is therefore important for maintaining muscle mass in people who are unable to use the muscles voluntarily.

TABLE 10.2 Classification of Skeletal Muscle Fibers

Properties	Slow Oxidative Fibers	Fast Glycolytic Fibers
Twitch duration	As long as 100 ms	As short as 7.5 ms
Relative diameter	Smaller	Larger
ATP synthesis	Aerobic	Anaerobic
Fatigue resistance	Good	Poor
ATP hydrolysis	Slow	Fast
Glycolysis	Moderate	Fast
Myoglobin content	Abundant	Low
Glycogen content	Low	Abundant
Mitochondria	Abundant and large	Fewer and smaller
Capillaries	Abundant	Fewer
Color	Red	White, pale
Representative Muscles in Which Fiber Type Is Predominant		
	Soleus	Gastrocnemius
	Erector spinae	Biceps brachii
	Quadratus lumborum	Muscles of eye movement

Physiological Classes of Muscle Fibers

Not all muscle fibers are metabolically alike or adapted to perform the same task. Some respond slowly but are relatively resistant to fatigue, while others respond more quickly but also fatigue quickly. Each primary type of fiber goes by several names. Table 10.2 summarizes their differences.

- **Slow oxidative (SO), slow-twitch, red,** or **type I fibers.** These fibers have relatively abundant mitochondria, myoglobin, and blood capillaries, and therefore a relatively deep red color. They are well adapted to aerobic respiration and do not fatigue easily. However, in response to a single stimulus, they exhibit a relatively long *twitch,* or contraction, lasting about 100 milliseconds (ms). The soleus muscle of the calf and the postural muscles of the back are composed mainly of these slow-twitch, fatigue-resistant fibers.
- **Fast glycolytic (FG), fast-twitch, white,** or **type II fibers.** These fibers are rich in enzymes for anaerobic fermentation, a process independent of oxygen. They respond quickly, with twitches as short as 7.5 ms, but fatigue more easily than SO fibers. They are poorer in mitochondria, myoglobin, and blood capillaries than SO fibers, so they are relatively pale (hence the expression *white* fibers). They are well adapted for quick responses but not for endurance. Thus, they are especially important in sports such as basketball that require stop-and-go activity and frequent changes of pace. The gastrocnemius muscle of the calf, biceps brachii of the arm, and the muscles of eye movement consist mainly of FG fibers.

Some authorities recognize two subtypes of FG fibers called types IIA and IIB. Type IIB is the common type just described, whereas IIA, or **intermediate fibers,** combine fast-twitch responses with aerobic fatigue-resistant metabolism. Type IIA fibers, however, are relatively rare except in some endurance-trained athletes.

Nearly all muscles are composed of both SO and FG fibers, but the proportions of these fiber types differ from one muscle to another. Muscles composed mainly of SO fibers are called *red muscles* and those composed mainly of FG fibers are called *white muscles.* People with different types and levels of physical activity differ in the proportion of one fiber type to another even in the same muscle, such as the quadriceps femoris (table 10.3). It is thought that people are born with a genetic predisposition for a certain ratio of fiber types. Those who go into competitive sports discover the sports at which they can excel and gravitate toward those for which heredity has best equipped them. One person might be a “born sprinter” and another a “born marathoner.”

We noted earlier that sometimes two or more muscles act across the same joint and superficially seem to have the same function. We have already seen why such muscles are not as redundant as they seem, such as differences in mechanical advantage. Another reason is that they may differ in the proportion of SO to FG fibers.

TABLE 10.3 Proportion of Slow Oxidative and Fast Glycolytic Fibers in the Quadriceps Femoris of Male Athletes

Sample Population	Slow Oxidative (SO)	Fast Glycolytic (FG)
Marathon runners	82%	18%
Swimmers	74	26
Average males	45	55
Sprinters and jumpers	37	63

For example, the gastrocnemius and soleus muscles of the calf both insert on the calcaneus through the calcaneal tendon, so they exert the same pull on the heel. The gastrocnemius, however, is a predominantly fast glycolytic muscle adapted for quick, powerful movements such as jumping, whereas the soleus is a predominantly slow oxidative muscle that does most of the work in endurance exercises such as jogging and skiing.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

18. What role does the sarcoplasmic reticulum play in muscle contraction? What role does it play in muscle relaxation?
19. Why does tropomyosin have to move before a muscle fiber can contract? What makes it move?
20. What role does ATP play in muscle contraction?
21. What is the mechanism of muscle growth? Describe the growth process in muscle and distinguish it from hyperplasia.
22. What are the basic functional differences between slow oxidative and fast glycolytic muscle fibers?

10.5 Cardiac and Smooth Muscle

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe cardiac muscle tissue and compare its structure and physiology to the other types; and
b. describe smooth muscle tissue and compare its structure and physiology to the other types.

Cardiac and smooth muscle have special structural and physiological properties related to their distinctive functions. They also have certain properties in common with each other but different from those of skeletal muscle.

Cardiac Muscle

Cardiac muscle constitutes most of the heart. Its form and function are discussed extensively in chapter 20 so that you will be able to relate these to the actions of the heart. Here, we only briefly compare it to skeletal and smooth muscle (table 10.4).

Cardiac muscle is striated like skeletal muscle, but otherwise exhibits several differences (fig. 10.15). Its *cardiocytes (myocytes)* are not long multinuclear fibers but short, stumpy, slightly branched cells. Microscopically, cardiac muscle exhibits characteristic dark lines called **intercalated** (in-TUR-kuh-LAY-ted) **discs** where the cells meet. These are steplike regions containing electrical gap junctions that allow the cells to communicate with each other, and various mechanical junctions that prevent the cells from pulling apart when they contract (see details in chapter 20). Each myocyte can join several others at its intercalated discs.

Cardiocytes usually have only one, centrally placed nucleus (occasionally two) (fig 10.16), often surrounded by glycogen. Cardiac muscle is very rich in glycogen and myoglobin, and it has especially large mitochondria that fill about 25% of the cell, compared to smaller mitochondria occupying about 2% of a skeletal muscle fiber. Cardiac muscle is therefore well adapted to aerobic



© Ed Reschke/Getty Images

Figure 10.15 Cardiac Muscle.



© McGraw-Hill Education/Dennis Strete, photographer

Figure 10.16 Smooth Muscle. APR

TABLE 10.4 Comparison of Skeletal, Cardiac, and Smooth Muscle

Feature	Skeletal Muscle	Cardiac Muscle	Smooth Muscle
Location	Associated with skeletal system	Heart	Walls of viscera and blood vessels, iris of eye, piloerectors of hair follicles
Cell shape	Long cylindrical fibers	Short branched cells	Fusiform cells
Cell length	100 μm–30 cm	50–100 μm	30–200 μm
Cell width	10–500 μm	10–20 μm	5–10 μm
Striations	Present	Present	Absent
Nuclei	Multiple nuclei, adjacent to sarcolemma	Usually one nucleus, near middle of cell	One nucleus, near middle of cell
Connective tissues	Endomysium, perimysium, epimysium	Endomysium only	Endomysium only
Sarcoplasmic reticulum	Abundant	Present	Scanty
T tubules	Present, narrow	Present, wide	Absent
Gap junctions	Absent	Present in intercalated discs	Present in single-unit smooth muscle
Ca^{2+} source	Sarcoplasmic reticulum	Sarcoplasmic reticulum and extracellular fluid	Mainly extracellular fluid
Innervation and control	Somatic motor fibers (voluntary)	Autonomic fibers (involuntary)	Autonomic fibers (involuntary)
Nervous stimulation required?	Yes	No	No
Mode of tissue repair	Limited regeneration, mostly fibrosis	Limited regeneration, mostly fibrosis	Relatively good capacity for regeneration by mitosis

respiration and very resistant to fatigue, although it is highly vulnerable to interruptions in its oxygen supply. The sarcoplasmic reticulum is less developed than in skeletal muscle, but the T tubules are larger and admit calcium from the extracellular fluid. Cardiac myocytes have little capacity for mitosis; the repair of damaged cardiac muscle is primarily by fibrosis.

Cardiac muscle is innervated by the *autonomic nervous system (ANS)* rather than by somatic motor neurons. The ANS is a division of the nervous system that usually operates without one's conscious awareness or control. It does not generate the heartbeat, but it modulates the heart rate and contraction strength. The heart beats rhythmically even without nervous stimulation; this property is called *autorhythmicity.* Each beat is triggered by the heart's pacemaker.

Smooth Muscle

Smooth muscle differs from skeletal muscle in several ways (table 10.4). It is named *smooth* because it has no striations, for a reason to be described shortly. Its myocytes are relatively small, allowing for fine control of such tissues and organs as a single hair, the iris of the eye, and the tiniest arteries; yet in the pregnant uterus, the myocytes become quite large and produce the powerful contractions of childbirth.

Smooth muscle myocytes have a fusiform shape, typically about 5 to 10 μm wide at the middle, tapering to a point at each end (fig. 10.16). There is only one nucleus, located near the middle of the cell. Thick and thin myofilaments are present, but there are no striations, sarcomeres, or myofibrils because the myofilaments are not bundled and aligned with each other the way they are in striated muscle. Z discs are absent. In their place are protein plaques called **dense bodies,** some associated with the inner face of the plasma membrane and others dispersed throughout the sarcoplasm. The membrane-associated dense bodies of one cell are often directly across from those of another, with linkages between them so that contractile force can be transmitted from cell to cell. Associated with the dense bodies is an extensive cytoskeletal network of intermediate filaments. The actin thin filaments attach to the intermediate filaments as well as directly to the dense bodies, so their movement (powered by myosin) is transferred to the sarcolemma and shortens the cell.

The sarcoplasmic reticulum is scanty, and there are no T tubules. The calcium needed to activate smooth muscle contraction comes mainly from the extracellular fluid by way of calcium channels, which are especially concentrated in little pits of the sarcolemma called **caveolae.** During relaxation, calcium is pumped back out of the cell.

Smooth muscle does not form organs in itself, but usually forms layers in the walls of larger organs such as the stomach, intestines, uterus, and urinary bladder. In such cases, the muscle layer is quite variable in complexity. It can consist of as little as one cell in small arteries. The esophagus and intestines have a thick outer layer of longitudinal smooth muscle adjacent to a deeper, thick inner layer of circular muscle (fig. 10.17). When the longitudinal layer contracts, it shortens and dilates the organ; when the circular layer contracts, it constricts and lengthens the organ (like a roll of dough squeezed in your hands). In the stomach, urinary bladder, and uterus, it forms three or more layers with bundles of myocytes running in multiple directions.

Smooth muscle often serves to propel the contents of an organ, such as driving food through the digestive tract, voiding urine and feces, and expelling the infant in childbirth. By dilating or constricting the blood vessels and airway, it can modify the speed of air and blood flow, maintain blood pressure, and reroute blood from one pathway to another. In the iris of the eye, it regulates pupil diameter. Smooth muscle also forms the piloerector muscles of the hair follicles. In such places as the digestive tract and ureters, it produces a wave of contraction called **peristalsis,** moving the contents of a tubular organ from one end to the other.

Smooth muscle is not always innervated, but when it is, the nerve supply is autonomic, like that of the heart. Autonomic nerve fibers do not form precisely localized neuromuscular junctions with the myocytes. Rather, each nerve fiber has as many as 20,000 periodic swellings called **varicosities** along its length (fig. 10.18). Each varicosity contains synaptic vesicles from which it releases neurotransmitters—usually norepinephrine from the sympathetic fibers and acetylcholine from the parasympathetic fibers.

There are two functional categories of smooth muscle called *multiunit* and *single-unit* types (fig. 10.18). **Multiunit smooth muscle** occurs in some of the largest arteries and pulmonary air passages, in the piloerector muscles of the hair follicles, and in the iris of the eye. Its innervation, although autonomic, is to some degree similar to that of skeletal muscle—each varicosity is associated with a single myocyte, and each myocyte contracts independently of the others.

Single-unit smooth muscle is more widespread. It occurs in most blood vessels and in the digestive, respiratory, urinary, and reproductive tracts—thus, it is also called **visceral muscle.** In this type, the varicosities are not associated with specific myocytes, but release a flood of neurotransmitters that stimulate multiple nearby myocytes at once. Each myocyte has neurotransmitter receptors scattered across its entire surface and may respond to several nearby nerve fibers. Furthermore, the myocytes are connected to each other by gap junctions. Thus, they directly stimulate each other and a large number of cells contract as a unit, almost as if they were a single cell. This is the reason that this muscle type is called *single-unit*.



Figure 10.17 **Layers of Visceral Muscle in a Cross Section of the Esophagus.** Many hollow organs have alternating circular and longitudinal layers of smooth muscle.



(a) Multiunit smooth muscle

(b) Single-unit smooth muscle

Figure 10.18 **Multiunit and Single-Unit Smooth Muscle.** (a) Multiunit smooth muscle, in which each muscle cell receives its own nerve supply and contracts independently. (b) Single-unit smooth muscle, in which a nerve fiber passes through the tissue without synapsing with any specific muscle cell, and muscle cells are coupled by electrical gap junctions.

Whether innervated or not, smooth muscle responds to a wide variety of stimuli and often without any electrical excitation of the sarcolemma. It responds not only to nerve fibers but also to other local chemicals and stretch. Its metabolism is mostly aerobic, but it has a very low energy requirement compared to skeletal and cardiac muscle, so it is highly fatigue-resistant. This enables smooth muscle to maintain a state of continual, partial contraction called **smooth muscle tone.** This tone maintains blood pressure by keeping the blood vessels partially constricted, and it prevents such organs as the stomach, intestines, urinary bladder, and uterus from becoming flaccid when empty.

Unlike skeletal and cardiac muscle, smooth muscle is capable of not only hypertrophy (cellular growth) but also mitosis and hyperplasia. Thus, an organ such as the pregnant uterus grows by the addition of new myocytes as well as the enlargement of existing ones. Injured smooth muscle regenerates well thanks to its mitotic capability.

Table 10.4 compares some properties of skeletal, cardiac, and smooth muscle.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

23. What organelles are more abundant and larger in cardiac muscle than in skeletal muscle? What is the functional significance of this?
24. What organelle is less developed in cardiac muscle than in skeletal muscle? How does this affect the activation of muscle contraction in the heart?
25. What factors make cardiac muscle more resistant to fatigue than skeletal muscle? What accounts for the relative fatigue resistance of smooth muscle?
26. How are single-unit and multiunit smooth muscle different? Which type is more abundant?

10.6 Developmental and Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe how the three types of muscle develop in the embryo;
b. describe the changes that occur in the muscular system in old age;
c. discuss two muscle diseases, muscular dystrophy and myasthenia gravis; and
d. briefly define and discuss several other disorders of the muscular system.

Embryonic Development of Muscle

Muscular tissue arises from embryonic mesoderm, with the exception of the piloerector muscles and the muscles within the eye. As described in chapter 4, the mesoderm of the trunk forms segmentally arranged blocks of tissue called somites, which then divide into regions called the dermatomes, sclerotomes, and myotomes. Beginning in week 4, some mesodermal cells migrate to the center of a somite and form the myotome, which will give rise to major axial muscles such as the erector spinae of the back. Others migrate away from the somite to the limb buds and body wall, where they will give rise to limb, abdominal, thoracic, and other muscles.

In these locations, the mesodermal cells elongate into spindle-shaped **myoblasts**[17] and rapidly multiply (fig. 10.19). Myoblasts fuse into long multinuclear masses called the **primary myotubes,** with the nuclei in a chain down the core. These myotubes, the future muscle fibers, attach at each end to the developing tendons and skeleton. Internally, they begin assembling muscle proteins into sarcomeres, starting at the periphery of the myotube and progressing inward. Nuclei migrate to the periphery as the center becomes filled with myofibrils. Additional waves of myoblasts aggregate along the primary myotubes and form smaller *secondary* and *tertiary myotubes* (sometimes more in larger muscles) that fuse with the primary myotube to thicken the fiber.

By 9 weeks, most muscle groups are present, and nerve fibers have synapsed with the muscle fibers. The muscle fibers begin contracting in response to stimulation by week 10. By week 17, the contractions are strong enough to be felt by the mother. It was once thought that the fetus first comes alive at this time, so this stage of development is called *quickening*.[18]

Late in fetal development, additional myoblasts associate with the muscle fiber and become **satellite cells.** These are stem cells that persist throughout life. Some of them fuse with growing muscle fibers and contribute nuclei to it through childhood, and satellite cells can regenerate damaged skeletal muscle even in adults. The development of new muscle fibers by mitosis ends, according to various estimates, from week 24 of gestation to 1 year after birth. After that, all muscle growth is by hypertrophy (enlargement of existing fibers) or longitudinal, nonmitotic splitting of large fibers. After age 25, the number of fibers in each muscle begins to decline.

Cardiac muscle develops in association with an embryonic *heart tube* described in chapter 20. Mesenchymal cells near the heart tube differentiate into myoblasts, and these proliferate mitotically as they do in the development of skeletal muscle. But in contrast to skeletal muscle development, the myoblasts do not fuse. They remain joined to each other and develop intercalated discs at their points of adhesion. The heart begins beating in week 3. Mitosis in cardiac myocytes continues after birth and is active until about age 9, although there is now evidence of limited mitotic capability even in adults. There is understandable interest in being able to stimulate this process in hopes of promoting regeneration of cardiac muscle damaged by heart attacks.

---

[17] *myo* = muscle; *blast* = precursor
[18] *quick* = alive



① **Primary myotube formation**

Myoblasts migrate to sites of muscle formation, multiply, and fuse to form multinucleated primary myotubes. Myotubes begin producing sarcomeres.



② **Secondary myotube formation**

A new wave of myoblasts gather on the primary myotube (top) and fuse to form a smaller secondary myotube (bottom), which later fuses with the primary myotube to add thickness.



③ **Innervation and maturation**

A neuromuscular junction forms, myofibrils and sarcomeres continue to be added, and a final wave of myoblasts form satellite cells that contribute to later muscle growth and repair.

Figure 10.19 Embryonic Development of Skeletal Muscle Fibers.

Smooth muscle develops similarly from myoblasts associated with the embryonic gut, blood vessels, and other organs. As in cardiac muscle, these myoblasts never fuse with each other, but in single-unit smooth muscle, they do become interconnected through gap junctions.

The Aging Muscular System

One of the most noticeable changes we experience with age is the loss of lean body mass (muscle) and accumulation of fat. The change is dramatically exemplified by CT scans of the thigh. In a young well-conditioned male, muscle accounts for 90% of the cross-sectional area of the midthigh; in a frail 90-year-old woman, it is only 30%. Muscular strength and mass peak in the 20s; by the age of 80, most people have only half as much strength and endurance. Many people over age 75 cannot lift a 4.5 kg (10-pound) weight with their arms; a simple task such as carrying a sack of groceries into the house may become impossible. The loss of strength is a major contributor to falls, fractures, and dependence on others for the routine activities of daily living. Fast glycolytic (fast-twitch) fibers exhibit the earliest and most severe atrophy, thus increasing reaction time and reducing coordination.

There are multiple reasons for the loss of strength. Aged muscle fibers have fewer myofibrils, so they are smaller and weaker. The sarcomeres are increasingly disorganized, and muscle mitochondria are smaller and have reduced quantities of oxidative enzymes. Aged muscle has less ATP, glycogen, and myoglobin; consequently, it fatigues quickly. Muscles also exhibit more fat and fibrous tissue with age, which limits their movement and blood circulation. With reduced circulation, muscle injuries heal more slowly and with more scar tissue.

But the weakness and easy fatigue of aged muscle also stem from the aging of other organ systems. There are fewer motor neurons in the spinal cord, and some muscle shrinkage may represent denervation atrophy. The remaining neurons produce less acetylcholine and show less efficient synaptic transmission, which makes the muscles slower to respond to stimulation. As muscle atrophies, motor units have fewer muscle fibers per motor neuron, and more motor units must be recruited to perform a given task. Tasks that used to be easy, such as buttoning the clothes or eating a meal, take more time and effort. The sympathetic nervous system is also less efficient in old age, and less effective in increasing the blood flow to the muscles during exercise. This contributes to reduced endurance.

The muscles can be significantly reconditioned, however, even by exercise begun late in life. A person in his or her 90s can increase muscle strength two- or threefold in 6 months with as little as 40 minutes of exercise per week.

Diseases of the Muscular System

Diseases of muscular tissue are called **myopathies.** The muscular system suffers fewer diseases than any other organ system, but two of particular importance are muscular dystrophy and myasthenia gravis.



Figure 10.20 **Myasthenia Gravis (MG).** The subject is told to gaze upward (top panel). Within 60 seconds (middle panel) to 90 seconds (bottom), there is obvious sagging of the left eyelid (ptosis) due to inability to sustain stimulation and contraction of the orbicularis oculi muscle.

Muscular dystrophy[19] is a collective term for several hereditary diseases in which the skeletal muscles degenerate, lose strength, and are gradually replaced by fat and scar tissue. This new connective tissue impedes blood circulation, which in turn accelerates muscle degeneration, creating a fatal spiral of positive feedback. The most common form of the disease is *Duchenne*[20] *muscular dystrophy (DMD),* a sex-linked disease that occurs especially in males (about 1 in 3,500 live-born males). It results from a defective gene for dystrophin. In the absence of dystrophin, the sarcolemma tears and the muscle fiber dies. DMD is not evident at birth, but difficulties appear as a child begins to walk. The child falls frequently and has difficulty standing up again. The disease affects the hips first, then the lower limbs, and progresses to the abdominal and spinal muscles. The muscles shorten as they atrophy, causing postural abnormalities such as scoliosis. DMD is incurable, but is treated with exercise to slow the atrophy and with braces to reinforce the weakened hips and correct the posture. Patients are usually confined to a wheelchair by early adolescence and rarely live beyond the age of 20.

Myasthenia gravis[21] **(MG)** (MY-ass-THEE-nee-uh GRAV-iss) is most prevalent in women from 20 to 40 years old. It is an autoimmune disease in which antibodies attack the neuromuscular junctions and trigger the destruction of ACh receptors. As a result, the muscle fibers become less and less sensitive to ACh. The effects often appear first in the facial muscles and include drooping eyelids (fig. 10.20) and double vision (due to weakness of the eye muscles). These signs are often followed by difficulty swallowing, weakness of the limbs, and poor physical endurance. Some people with MG die quickly as a result of respiratory failure, while others have normal life spans. The symptoms can be controlled with cholinesterase inhibitors, which retard the breakdown of ACh and prolong its action on the muscles, and with drugs that suppress the immune system and thus slow the attack on ACh receptors.

Some other disorders of the muscular system in general are briefly described in table 10.5, whereas disorders more specific to the axial or appendicular musculature are described in chapters 11 and 12.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

27. What cells come between mesodermal cells and the muscle fiber in the stages of skeletal muscle development? Describe how several uninuclear cells transform into a multinuclear muscle fiber.
28. What is the principal difference between the way cardiac muscle and smooth muscle form and the way skeletal muscle forms?
29. Describe the major changes seen in the muscular system in old age.
30. What is the root cause of Duchenne muscular dystrophy? What is the normal function of dystrophin?
31. How is synaptic function altered in myasthenia gravis? How does this synaptic dysfunction affect a person with MG?

---

[19] *dys* = bad, abnormal; *trophy* = growth

[20] Guillaume B. A. Duchenne (1806–75), French physician

[21] *my* = muscle; *asthen* = weakness; *grav* = severe

TABLE 10.5	Disorders of the Muscular System
Charley horse	Slang for any painful tear, stiffness, and blood clotting in a muscle caused by contusion (a blow to the muscle causing hemorrhaging).
Contracture	Abnormal muscle shortening not caused by nervous stimulation. Can result from a persistence of calcium in the sarcoplasm after stimulation or from contraction of scar tissue.
Crush syndrome	A shocklike state following the massive crushing of muscles, associated with a high and potentially fatal fever; cardiac irregularities caused by K^+ released from the injured muscles; and kidney failure caused by blockage of the renal tubules with myoglobin released by the traumatized muscle. Myoglobin in the urine *(myoglobinuria)* is a common sign.
Delayed onset muscle soreness	Pain and stiffness felt from several hours to a day after strenuous exercise. Associated with microtrauma to the muscles, with disrupted Z discs, myofibrils, and plasma membranes, and with elevated blood levels of myoglobin and enzymes released by damaged muscle fibers.
Rhabdomyoma	A rare, benign muscle tumor, usually occurring in the tongue, neck, larynx, nasal cavity, throat, heart, or vulva. Treated by surgical removal.
Rhabdomyosarcoma	A malignant muscle tumor; the most common form of pediatric soft-tissue sarcoma, although accounting for <3% of childhood cancers and rarely seen in adults. Results from abnormal proliferation of myoblasts. Begins as a painless mass in a muscle but metastasizes rapidly. Diagnosed by biopsy and treated with surgery, chemotherapy, or radiation therapy.

Disorders Described Elsewhere

Atrophy	253
Back injuries	286
Compartment syndrome	294
Hamstring injuries	316
Muscular dystrophy	259
Myasthenia gravis	259
Paralysis	249, 394
Sports injuries	325

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

10.1 Muscle Types and Functions (p. 236)

1. The scope of myology and of the term *muscular system,* and what muscular tissues are not included in the muscular system
2. Differences between skeletal, cardiac, and smooth muscle with respect to the presence or absence of striations; voluntary or involuntary control; the shapes of their cells; and terms for the three types of muscle cells
3. The multiple functions of muscular tissue
4. Five physiological properties that muscle cells must have to carry out their functions

10.2 General Anatomy of Muscles (p. 237)

1. The tissues that constitute a skeletal muscle
2. The arrangement of a muscle's endomysium, perimysium, and epimysium; how these relate to the muscle fibers and fascicles; and the relationship of the connective tissue of a muscle with the periosteum of an associated bone
3. The separation of muscles by fasciae and the grouping of muscles into compartments
4. Orientation of the fascicles in fusiform, parallel, triangular, pennate, and circular muscles; and how this relates to muscle strength
5. The difference between an indirect and direct muscle attachment
6. How an aponeurosis differs from other tendons; what it has in common with them; and the locations of some aponeuroses
7. The traditional meaning of a muscle's *origin*, *insertion*, and *belly;* why the origin–insertion distinction is imperfect, with examples to support this argument
8. Some muscle attachments and actions on tissues other than bone
9. The meaning of a muscle's *action*
10. The functional interactions of prime movers, synergists, antagonists, and fixators; and examples of each
11. The distinction between intrinsic and extrinsic muscles, and examples of each
12. The fundamental parts of a musculoskeletal lever system
13. How to calculate the mechanical advantage (MA) of a musculoskeletal lever if given the necessary measurements; the benefits and limitations of musculoskeletal levers in which the MA is greater than 1 versus those in which it is less than 1
14. The difference between a first-, second-, and third-class lever; and both a nonliving and a musculoskeletal example of each

10.3 Microscopic Anatomy of Skeletal Muscle (p. 244)

1. The internal ultrastructure of a skeletal muscle fiber; the special names given to some of its organelles and cytoskeletal components; and the functions of each component
2. The relationship between myofilaments, myofibrils, and muscle fibers
3. The purposes of glycogen and myoglobin in a muscle fiber
4. The structural network of the sarcoplasmic reticulum and its physiological function
5. The three types of myofilaments that compose a myofibril; what they are made of; and what roles they play
6. The location and role of dystrophin in a muscle fiber
7. The names of the striations in skeletal and cardiac muscle and how the overlapping myofilaments account for the striations
8. The definition of a *sarcomere;* its relationship to the Z discs; and the basic action of the sarcomeres in muscle contraction

9. The relationship of a somatic motor neuron to a group of skeletal muscle fibers
10. The structure of a neuromuscular junction and the functions of all of its components
11. The roles of acetylcholine (ACh), acetylcholine receptors, and acetylcholinesterase at a neuromuscular junction; where ACh comes from when a muscle is stimulated; and what becomes of it afterward
12. The components of a motor unit; what is meant by the size of a motor unit; the respective advantages of large and small motor units; and some places where large and small motor units can be found
13. The blood supply to the skeletal muscles, and the share of the circulating blood that the muscular system receives in rest and exercise

10.4 Relating Structure to Function (p. 250)

1. The four stages of muscle contraction and relaxation
2. The events of excitation—how a signal in a motor nerve fiber results in a chain reaction of electrical excitation in the muscle fiber; the roles of acetylcholine and gated ion channels in producing these events
3. The events of excitation–contraction coupling; how electrical excitation of the muscle fiber leads to changes in the myofilaments that make it possible for a sarcomere to contract; and the roles of the sarcoplasmic reticulum, calcium, troponin, and tropomyosin in this process
4. The repetitive cycle of myosin–actin interactions that result in muscle contraction; the role of ATP in this process
5. The events of relaxation; how a muscle fiber is allowed to stop contracting
6. The effects of regular resistance exercise on a muscle, and the mode of muscle growth
7. The definition of muscle *atrophy,* and its causes
8. Differences between slow oxidative (SO) and fast glycolytic (FG) muscle fibers; examples of some muscles in which each of these fiber types is dominant; and the properties of intermediate fibers

10.5 Cardiac and Smooth Muscle (p. 254)

1. The structure of cardiac muscle cells and how they are joined to each other
2. The spontaneous activity of cardiac muscle and how it is influenced by the nervous system
3. The special cytological properties of cardiac muscle cells that make them highly resistant to fatigue
4. Similarities and differences between smooth muscle cells and skeletal muscle fibers with respect to their organelle systems and the reason for the absence of striations in smooth muscle
5. The functional differences between multiunit and single-unit smooth muscle; how they differ in their relationships with motor nerve fibers; and where each type occurs
6. Differences in the behavior of smooth muscle versus skeletal muscle, and why smooth muscle is advantageous for certain purposes

10.6 Developmental and Clinical Perspectives (p. 257)

1. The development of embryonic mesenchymal cells into skeletal muscle fibers
2. How cardiac and smooth muscle differ from skeletal muscle in the embryonic development of their cells
3. Changes seen in the skeletal muscles in old age; and multiple reasons for the reduced strength, endurance, and efficiency of the muscles with age
4. The mode of inheritance and pathology of muscular dystrophy
5. The cause and effects of myasthenia gravis

Testing Your Recall

1. A fascicle is bounded and defined by
   a. the endomysium.
   b. the fascia.
   c. the myofilaments.
   d. the epimysium.
   e. the perimysium.
2. Muscle cells must have all of the following properties *except* _____ to carry out their function.
   a. extensibility
   b. elasticity
   c. autorhythmicity
   d. contractility
   e. conductivity
3. If a tendon runs longitudinally throughout a muscle and fascicles insert obliquely on it along both sides, the muscle is classified as
   a. parallel.
   b. oblique.
   c. bipennate.
   d. convergent.
   e. multipennate.
4. A muscle that holds a bone still during a particular action is called
   a. a fixator.
   b. an antagonist.
   c. an agonist.
   d. a synergist.
   e. an intrinsic muscle.
5. Which of the following muscle proteins is *not* intracellular?
   a. actin
   b. myosin
   c. collagen
   d. troponin
   e. dystrophin
6. Smooth muscle cells have _____, whereas skeletal muscle fibers do not.
   a. T tubules
   b. ACh receptors
   c. thick myofilaments
   d. thin myofilaments
   e. dense bodies
7. ACh receptors are found in
   a. synaptic vesicles.
   b. terminal cisternae.
   c. thick filaments.
   d. thin filaments.
   e. junctional folds.
8. Single-unit smooth muscle cells can stimulate each other because they have
   a. pacemakers.
   b. diffuse junctions.
   c. gap junctions.
   d. tight junctions.
   e. calcium pumps.
9. A second-class lever always has
   a. the fulcrum in the middle.
   b. the effort applied between the fulcrum and resistance.
   c. a mechanical advantage less than 1.
   d. a mechanical advantage greater than 1.
   e. the resistance at one end.
10. Slow oxidative muscle fibers have all of the following *except*
    a. an abundance of myoglobin.
    b. an abundance of glycogen.
    c. high fatigue resistance.
    d. a red color.
    e. a high capacity to synthesize ATP aerobically.
11. Acetylcholine is released from organelles called _____.
12. The region where a motor nerve fiber meets a skeletal muscle fiber is called a/an _____.
13. Parts of the sarcoplasmic reticulum called _____ lie on each side of a T tubule.
14. Thick myofilaments consist mainly of the protein _____.

15. Sheets of fibrous connective tissue called _____ separate a muscle or muscle group from neighboring muscles.
16. Muscle contains an oxygen-storage pigment called _____.
17. The _____ of skeletal muscle play the same role as dense bodies in smooth muscle.
18. A circular muscle that controls a body opening or passage is called a/an _____.
19. Skeletal muscle fibers develop by the fusion of embryonic cells called _____.
20. A wave of contraction passing along the esophagus or small intestine is called _____.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. myo-
2. fasc-
3. fusi-
4. sarco-
5. dys-
6. mys-
7. anti-
8. erg-
9. -mer
10. penna-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. Pennate muscles are stronger than parallel muscles of comparable size.
2. A given muscle may be an agonist in one joint movement and an antagonist in a different movement of that joint.
3. Extrinsic muscles are not located entirely within the body region that they control.
4. Cardiac myocytes are of the fatigue-resistant, slow oxidative type.
5. One motor neuron can supply only one muscle fiber.
6. To initiate muscle contraction, calcium ions must bind to the myosin heads.
7. A first-class lever can have a mechanical advantage either greater than or less than 1.
8. Slow oxidative fibers are more fatigue-resistant than fast glycolytic fibers.
9. The blood vessels of a skeletal muscle are more wavy or coiled when a muscle is relaxed than when it contracts.
10. Well-exercised muscles generally gain in thickness by the addition of new muscle fibers.

Answers in appendix A

Testing Your Comprehension

1. In a baseball game, the pitcher hits the batter in the thigh with a fastball. Which of the following conditions would this most likely cause: atrophy, charley horse, contracture, crush syndrome, or rhabdomyoma? Explain your choice.
2. What would be the consequences for muscular system function if muscle fibers were not elastic? What if they were not extensible?
3. For each of the following muscle pairs, state which muscle you think would have the higher percentage of fast glycolytic fibers: (a) Muscles that move the eyes or muscles of the upper throat that initiate swallowing. (b) The abdominal muscles employed in doing sit-ups or the muscles employed in handwriting. (c) Muscles of the tongue or the skeletal muscle sphincter of the anus. Explain each answer.
4. The forearm contains five flexor muscles that flex the wrist and fingers. Explain why it is better for them to have an indirect attachment rather than a direct attachment to the bones on which they act.
5. The brachialis muscle is the most powerful flexor of the elbow. Examine its bone attachments in figure 12.3 (p. 298) and table 12.3 (p. 301). From a functional standpoint, identify what bone attachment would be its origin and what would be its insertion in a person lifting barbells. Then identify which would be the origin and insertion in a person climbing the face of a cliff. In light of your conclusions, concisely explain the imperfection in such conventional terminology for its attachments.



CT scan of the lumbar region; body-wall muscles (and bowel) in light green

© Scott Camazine/Science Source

CHAPTER 11

THE MUSCULAR SYSTEM II
AXIAL MUSCULATURE

CHAPTER OUTLINE

11.1 Learning Approaches 264
- How Muscles Are Named 264
- Muscle Innervation 264
- A Learning Strategy 264

11.2 Muscles of the Head and Neck 268
- Muscles of Facial Expression 268
- Muscles of Chewing and Swallowing 273
- Muscles Acting on the Head 277

11.3 Muscles of the Trunk 279
- Muscles of Respiration 279
- Muscles of the Anterior Abdominal Wall 281
- Muscles of the Back 284
- Muscles of the Pelvic Floor 287

Study Guide 290

DEEPER INSIGHTS

11.1 Difficulty Breathing 280
11.2 Heavy Lifting and Back Injuries 286
11.3 Hernias 289

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:
- Anatomy of the axial skeleton (chapter 7)
- Terminology of joint actions (pp. 213–219)
- Shapes of muscles (fusiform, pennate, circular, etc.) (pp. 238–239)
- Indirect versus direct muscle attachments (p. 239)
- The shortcomings of traditional muscle origin and insertion terminology (p. 240)
- Prime movers, synergists, antagonists, and fixators (pp. 240–241)
- Intrinsic and extrinsic muscles (p. 241)

Anatomy & Physiology REVEALED®
aprevealed.com

Module 6: Muscular System

There are about 600 skeletal muscles in the human body. Chapters 11 and 12 describe fewer than one-third of these. This chapter deals with the muscles that act on the axial division of the body—that is, on the head and trunk. Muscles that act on the limbs and limb girdles (the appendicular division) are described in chapter 12. This chapter opens with some tips to help you study the muscles more insightfully.

11.1 Learning Approaches

Expected Learning Outcomes

When you have completed this section, you should be able to

a. translate several Latin words commonly used in the naming of muscles;
b. define the *innervation* of a muscle;
c. describe the sources of the nerves to the head–neck and trunk muscles and explain the numbering system for the cranial and spinal nerves; and
d. describe and practice some methods that will help in the learning of the skeletal muscles.

How Muscles Are Named

Figure 11.1 shows an overview of the major superficial muscles. Learning the names of these and other muscles may seem a forbidding task at first, especially when some of them have such long Latin names as *depressor labii inferioris* and *flexor digiti minimi brevis*. Such names, however, typically describe some distinctive aspects of the structure, location, or **action** of a muscle—the movement that results from its contraction or, in a few cases, unwanted movement that it prevents. The names become very helpful once we grow familiar with a few common Latin words. For example, the depressor labii inferioris is a muscle that lowers (depresses) the bottom (inferior) lip (labium), and the flexor digiti minimi brevis is a short (brevis) muscle that flexes the smallest (minimi) finger (digit). Several of the most common words in muscle names are interpreted in table 11.1, and others are explained in footnotes throughout the chapter. Familiarity with these terms and attention to the footnotes will help you translate muscle names and remember the location, appearance, and action of the muscles.

Muscle Innervation

The **innervation** of a muscle refers to the identity of the nerve that stimulates it. Knowing the innervation to each muscle enables clinicians to diagnose nerve, spinal cord, and brainstem injuries from their effects on muscle function, and to set realistic goals for rehabilitation. The innervations described in this chapter will be more meaningful after you have studied the peripheral nervous system (chapters 14 and 15), but a brief orientation will be helpful here. The muscles are innervated by two groups of nerves:

- **Spinal nerves** arise from the spinal cord, emerge through the intervertebral foramina, and innervate muscles below the neck. Spinal nerves are identified by letters and numbers that refer to the adjacent vertebrae—for example, T6 for the sixth thoracic nerve and S2 for the second sacral nerve. Immediately after emerging from an intervertebral foramen, each spinal nerve branches into a *posterior* and *anterior* *ramus.*[1] You will note references to nerve numbers and rami in many of the muscle tables. The term *plexus* in some of the tables refers to weblike networks of spinal nerves adjacent to the vertebral column. All of the spinal nerves named here are illustrated—and most are also discussed—in chapter 14.
- **Cranial nerves** arise mainly from the base of the brain, emerge through the skull foramina, and innervate muscles of the head and neck. Cranial nerves are identified by roman numerals (CN I–XII) and by names given in chapter 15, although not all 12 of them innervate skeletal muscles.

A Learning Strategy

The following suggestions can help you develop a rational strategy for learning the skeletal muscles as you first encounter them in the textbook and laboratory:

- Examine models, cadavers, dissected animals, or an anatomical atlas as you read about the muscles. Visual images are often easier to remember than words, and direct observation of a muscle may stick in your memory better than descriptive text or two-dimensional drawings.
- When studying a particular muscle, palpate it on yourself if possible. Contract the muscle to feel it bulge and sense its action. Doing so will make muscle locations and actions less abstract. The atlas following chapter 12 shows where you can see and palpate several muscles on the living body.
- Locate the muscle attachments on an articulated skeleton. Some study skeletons are painted and labeled to show these. This will help you visualize the locations of muscles and understand how they produce particular joint actions.
- Study the derivations of the muscle names; look for descriptive meaning in their names.
- Say the names *aloud* to yourself or a study partner. It is harder to remember and spell terms you cannot pronounce, and silent pronunciation is not nearly as effective as speaking and hearing the names. Pronunciation guides are provided in the muscle tables for all but the most obvious cases.

---

[1] *ramus* = branch

TABLE 11.1 **Words Commonly Used to Name Muscles**

Criterion	Term and Meaning	Examples of Usage
Size	Brevis (short)	Extensor pollicis brevis
	Longus (long)	Abductor pollicis longus
	Major (large)	Pectoralis major
	Maximus (largest)	Gluteus maximus
	Minimus (smallest)	Gluteus minimus
	Minor (small)	Pectoralis minor
Shape	Deltoid (triangular)	Deltoid
	Quadratus (four-sided)	Pronator quadratus
	Rhomboid (rhomboidal)	Rhomboid major
	Teres (round, cylindrical)	Pronator teres
	Trapezius (trapezoidal)	Trapezius
Location	Abdominis (of the abdomen)	Rectus abdominis
	Brachii (of the arm)	Biceps brachii
	Capitis (of the head)	Splenius capitis
	Carpi (of the wrist)	Flexor carpi ulnaris
	Cervicis (of the neck)	Semispinalis cervicis
	Digiti (of a finger or toe, singular)	Extensor digiti minimi
	Digitorum (of the fingers or toes, plural)	Flexor digitorum profundus
	Femoris (of the femur, or thigh)	Quadriceps femoris
	Fibularis (of the fibula)	Fibularis longus
	Hallucis (of the great toe)	Abductor hallucis
	Indicis (of the index finger)	Extensor indicis
	Intercostal (between the ribs)	External intercostals
	Lumborum (of the lower back)	Quadratus lumborum
	Pectoralis (of the chest)	Pectoralis major
	Pollicis (of the thumb)	Opponens pollicis
	Profundus (deep)	Flexor digitorum profundus
	Superficialis (superficial)	Flexor digitorum superficialis
	Thoracis (of the thorax)	Spinalis thoracis
Number of heads	Biceps (two heads)	Biceps femoris
	Triceps (three heads)	Triceps brachii
	Quadriceps (four heads)	Quadriceps femoris
Orientation	Oblique (slanted)	External abdominal oblique
	Rectus (straight)	Rectus abdominis
Action	Abductor	Abductor digiti minimi
	Adductor	Adductor pollicis
	Depressor	Depressor anguli oris
	Extensor	Extensor carpi radialis
	Flexor	Flexor carpi radialis
	Levator	Levator scapulae
	Pronator	Pronator teres
	Supinator	Supinator


Superficial
Deep
Frontalis
Orbicularis oculi
Zygomaticus major
Platysma
Deltoid
Pectoralis major
Biceps brachii
Brachioradialis
Flexor carpi radialis
External abdominal oblique
Tensor fasciae latae
Masseter
Orbicularis oris
Sternocleidomastoid
Trapezius
Pectoralis minor
Coracobrachialis
Serratus anterior
Brachialis
Rectus abdominis
Supinator
Flexor digitorum profundus
Flexor pollicis longus
Transverse abdominal
Internal abdominal oblique
Pronator quadratus
Adductor longus
Sartorius
Rectus femoris
Vastus lateralis
Vastus medialis
Adductors
Vastus lateralis
Vastus intermedius
Gracilis
Fibularis longus
Tibialis anterior
Extensor digitorum longus
Gastrocnemius
Soleus
Extensor digitorum longus

(a) Anterior view

Figure 11.1 The Muscular System. In each figure, major superficial muscles are shown on the anatomical right, and some of the deeper muscles are shown on the left. Muscles not labeled here are shown in more detail in later figures.


Deep
Superficial
Occipitalis
Semispinalis capitis
Sternocleidomastoid
Splenius capitis
Trapezius
Levator scapulae
Supraspinatus
Rhomboid minor
Rhomboid major
Infraspinatus
Deltoid (cut)
Teres minor
Infraspinatus
Teres major
Serratus anterior
Triceps brachii
Triceps brachii (cut)
Latissimus dorsi
Serratus posterior inferior
Extensor carpi radialis longus and brevis
External abdominal oblique
Internal abdominal oblique
External abdominal oblique
Erector spinae
Extensor digitorum
Gluteus medius
Flexor carpi ulnaris
Extensor carpi ulnaris
Extensor digitorum (cut)
Gluteus maximus
Gluteus minimus
Lateral rotators
Adductor magnus
Gracilis
Iliotibial tract
Semitendinosus
Semimembranosus
Iliotibial tract
Biceps femoris
Biceps femoris
Gastrocnemius (cut)
Soleus (cut)
Gastrocnemius
Tibialis posterior
Flexor digitorum longus
Soleus
Flexor hallucis longus
Fibularis longus
Calcaneal tendon

(b) Posterior view

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. What is meant by the *innervation* of a muscle? Why is it important to know this? What two major groups of nerves innervate the skeletal muscles?
2. In table 11.1, pick a muscle name from the right column that you think meets each of the following descriptions: (a) lies beside the radius and straightens the wrist; (b) pulls down the corners of your mouth when you frown; (c) raises your shoulder blades; (d) moves your little finger laterally, away from the fourth digit; (e) is the largest muscle deep to the breast.

11.2 Muscles of the Head and Neck

Expected Learning Outcomes

When you have completed this section, you should be able to

a. name and locate the muscles that produce facial expressions;
b. name and locate the muscles used for chewing and swallowing;
c. name and locate the neck muscles that move the head; and
d. identify the attachments, action, and innervation of any of these muscles.

Muscles of the head and neck will be treated here from a regional and functional perspective, thus placing them in the following groups: muscles of facial expression, muscles of chewing and swallowing, and muscles that move the head as a whole (tables 11.2–11.4). In these tables and throughout the rest of the chapter, each muscle entry provides the following information:

- the name of the muscle;
- the pronunciation of the name, unless it is self-evident or uses words whose pronunciations have been provided in a recent entry;
- the actions of the muscle;
- the muscle's skeletal attachments; in this column, the first bullet indicates what was traditionally regarded as the origin and the second, the insertion (but see p. 240 on why those terms are falling out of use); and
- the muscle's innervation.

TABLE 11.2 Muscles of Facial Expression

Humans have much more expressive faces than other mammals because of a complex array of muscles that insert in the dermis and subcutaneous tissues (figs. 11.2 and 11.3). These muscles tense the skin and produce such expressions as a pleasant smile, a threatening scowl, a puzzled frown, or a flirtatious wink (fig. 11.4). They add subtle shades of meaning to our spoken words. Facial muscles also contribute directly to speech, chewing, and other oral functions. All but one of these muscles are innervated by the facial nerve (CN VII). This nerve is especially vulnerable to injury from lacerations and skull fractures, which can paralyze the muscles and cause parts of the face to sag. The only muscle in this table not innervated by the facial nerve is the levator palpebrae superioris, innervated by the oculomotor nerve (CN III).



© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Figure 11.2 **Some Facial Muscles of the Cadaver.** Boldface labels indicate muscles employed in facial expression.

TABLE 11.2 Muscles of Facial Expression (continued)

Figure 11.3 **Muscles of Facial Expression.** Boldface labels indicate muscles employed in facial expression.


Superficial
Deep
Galea aponeurotica
Frontalis
Corrugator supercilii
Orbicularis oculi
Nasalis
Levator labii superioris
Levator anguli oris
Zygomaticus minor
Masseter
Zygomaticus major
Buccinator
Risorius
Modiolus
Orbicularis oris
Depressor anguli oris
Mentalis (cut)
Depressor labii inferioris
Platysma

(a) Anterior view


Galea aponeurotica
Frontalis (cut)
Temporalis
Corrugator supercilii
Orbicularis oculi
Occipitalis
Nasalis
Levator labii superioris
Zygomatic arch
Zygomaticus minor
Zygomaticus major
Orbicularis oris
Masseter
Sternocleidomastoid
Modiolus
Levator scapulae
Inferior pharyngeal constrictor
Risorius (cut)
Mentalis
Thyrohyoid
Depressor labii inferioris
Sternothyroid
Omohyoid
Depressor anguli oris
Sternohyoid
Buccinator

(b) Lateral view

TABLE 11.2 Muscles of Facial Expression (continued)

The Scalp. The *occipitofrontalis* overlies the dome of the cranium. It is divided into the *frontalis* of the forehead and *occipitalis* at the rear of the head, named for the frontal and occipital bones underlying them. They are connected to each other by a broad aponeurosis, the **galea aponeurotica**[2] (GAY-lee-uh AP-oh-new-ROT-ih-cuh).

Name	Action	Skeletal Attachments	Innervation
Frontalis (frun-TAY-lis)	Elevates eyebrows in glancing upward and expressions of surprise or fright; draws scalp forward and wrinkles skin of forehead	• Galea aponeurotica • Subcutaneous tissue of eyebrows	Facial nerve
Occipitalis (oc-SIP-ih-TAY-lis)	Retracts scalp; fixes galea aponeurotica so frontalis can act on eyebrows	• Superior nuchal line and temporal bone • Galea aponeurotica	Facial nerve
The Orbital and Nasal Regions. The *orbicularis oculi* is a sphincter of the eyelid that encircles and closes the eye. The *levator palpebrae superioris* lies deep to the orbicularis oculi, in the eyelid and orbital cavity (see fig. 17.20, p. 481), and opens the eye. Other muscles in this group move the eyelids and skin of the forehead and dilate the nostrils. Muscles within the orbit that move the eyeball itself are discussed in chapter 17.			
Orbicularis Oculi[3] (or-BIC-you-LERR-is OC-you-lye)	Sphincter of the eyelids; closes eye in blinking, squinting, and sleep; aids in flow of tears across eye	• Lacrimal bone, adjacent regions of frontal bone and maxilla, medial angle of eyelids • Upper and lower eyelids, skin around margin of orbit	Facial nerve
Levator Palpebrae Superioris[4] (leh-VAY-tur pal-PEE-bree soo-PEER-ee-OR-is)	Elevates upper eyelid, opens eye	• Lesser wing of sphenoid in posterior wall of orbit • Upper eyelid	Oculomotor nerve
Corrugator Supercilii[5] (COR-oo-GAY-tur SOO-per-SIL-ee-eye)	Draws eyebrows medially and downward in frowning and concentration; reduces glare of bright sunlight	• Medial end of supraorbital margin • Skin of eyebrow	Facial nerve
Nasalis[6] (nay-ZAIL-is)	Widens nostrils; narrows internal air passage between vestibule and nasal cavity	• Maxilla just lateral to nose • Bridge and alar cartilages of nose	Facial nerve
The Oral Region. The mouth is the most expressive part of the face, and lip movements are necessary for intelligible speech; thus, it is not surprising that the muscles here are especially diverse. The *orbicularis oris* is a complex of muscles in the lips that encircle the mouth; until recently it was misinterpreted as a sphincter, or circular muscle, but it is actually composed of four independent quadrants that interlace and give only an appearance of circularity. Other muscles in this region approach the lips from all directions and thus draw the lips or angles (corners) of the mouth upward, laterally, and downward. Some of these arise from or end in a complex cord called the **modiolus**[7] just lateral to each angle of the lips (fig. 11.3). Named for the hub of a cartwheel, the modiolus is a point of convergence of several muscles of the lower face. You can palpate it by inserting one finger just inside the corner of your lips and pinching the corner between the finger and thumb, feeling for a thick knot of tissue.			
Orbicularis Oris[8] (or-BIC-you-LERR-is OR-is)	Encircles mouth, closes lips, protrudes lips as in kissing; uniquely developed in humans for speech	• Modiolus of mouth • Submucosa and dermis of lips	Facial nerve
Levator Labii Superioris[9] (leh-VAY-tur LAY-bee-eye soo-PEER-ee-OR-is)	Elevates and everts upper lip in sad, sneering, or serious expressions	• Zygomatic bone and maxilla near inferior margin of orbit • Muscles of upper lip	Facial nerve
Levator Anguli Oris[10] (leh-VAY-tur ANG-you-lye OR-is)	Elevates angle of mouth as in smiling	• Maxilla just below infraorbital foramen • Muscles at angle of mouth	Facial nerve
Zygomaticus[11] **Major** (ZY-go-MAT-ih-cus)	Draws angle of mouth upward and laterally as in laughing	• Zygomatic bone • Superolateral angle of mouth	Facial nerve
Zygomaticus Minor	Elevates upper lip, exposes upper teeth in smiling or sneering	• Zygomatic bone • Muscles of upper lip	Facial nerve
Risorius[12] (rih-SOR-ee-us)	Draws angle of mouth laterally in expressions of laughing, horror, or disdain	• Zygomatic arch, fascia near ear • Modiolus of mouth	Facial nerve

---

[2] *galea* = helmet; *apo* = above; *neuro* = nerves, brain
[3] *orb* = circle; *ocul* = eye
[4] *levat* = to raise; *palpebr* = eyelid; *superior* = upper
[5] *corrug* = wrinkle; *supercil* = eyebrow
[6] *nas* = nose
[7] *modiolus* = hub
[8] *orb* = circle; *or* = mouth
[9] *levat* = to raise; *labi* = lip; *superior* = upper
[10] *angul* = angle, corner; *or* = mouth
[11] *zygo* = join, unite (refers to zygomatic bone)
[12] *risor* = laughter

TABLE 11.2 Muscles of Facial Expression (continued)


Frontalis
Levator palpebrae superioris
Zygomaticus major and minor
Levator anguli oris
Levator labii superioris
Depressor labii inferioris
Frontalis
Levator palpebrae superioris
Nasalis
Risorius
Depressor labii inferioris
Platysma
Frontalis
Levator palpebrae superioris
Corrugator supercilii
Orbicularis oris
Depressor anguli oris
Mentalis
Orbicularis oculi
Orbicularis oris
Depressor anguli oris
Mentalis

© McGraw-Hill Education/Joe De Grandis, photographer

© McGraw-Hill Education/Joe De Grandis, photographer

© McGraw-Hill Education/Joe De Grandis, photographer

© McGraw-Hill Education/Joe De Grandis, photographer

Figure 11.4 **Expressions Produced by Several of the Facial Muscles.** The ordinary actions of these muscles are usually more subtle than these demonstrations.

- *Name an antagonist of each of these muscles: the depressor anguli oris, orbicularis oculi, and levator labii superioris.*

TABLE 11.2 Muscles of Facial Expression (continued)

<table>
<tr><th>Name</th><th>Action</th><th>Skeletal Attachments</th><th>Innervation</th></tr>
<tr><td>Depressor Anguli Oris[13]</td><td>Draws angle of mouth laterally and downward in opening mouth or sad expressions</td><td>• Inferior margin of mandibular body
• Modiolus of mouth</td><td>Facial nerve</td></tr>
<tr><td>Depressor Labii Inferioris[14]</td><td>Draws lower lip downward and laterally in chewing and expressions of melancholy or doubt</td><td>• Near mental protuberance
• Skin and mucosa of lower lip</td><td>Facial nerve</td></tr>
<tr><td colspan="4">The Mental and Buccal Regions. Adjacent to the oral orifice are the mental region (chin) and buccal region (cheeks). In addition to muscles already discussed that act directly on the lower lip, the mental region has a pair of small <i>mentalis</i> muscles extending from the upper margin of the mandible to the skin of the chin. In some people, these muscles are especially thick and have a visible dimple between them called the <i>mental cleft.</i> The <i>buccinator</i> is the muscle in the cheek. It has multiple functions in chewing, sucking, and blowing. If the cheek is inflated with air, compression of the buccinator blows it out. Sucking is achieved by contracting the buccinators to draw the cheeks inward, and then relaxing them. This action is especially important to nursing infants. To feel this action, hold your fingertips lightly on your cheeks as you make a kissing noise. You will notice the relaxation of the buccinators at the moment air is sharply drawn in through the pursed lips.</td></tr>
<tr><td>Mentalis
(men-TAY-lis)</td><td>Elevates and protrudes lower lip in drinking, pouting, and expressions of doubt or disdain; elevates and wrinkles skin of chin</td><td>• Mandible near inferior incisors
• Skin of chin at mental protuberance</td><td>Facial nerve</td></tr>
<tr><td>Buccinator[15]
(BUC-sin-AY-tur)</td><td>Compresses cheek against teeth and gums; directs and retains food between teeth for chewing; retracts cheek from teeth when mouth is closing to prevent biting cheek; used in drinking from a straw and suckling by infants; expels air and liquid; helps control airflow in speech</td><td>• Alveolar processes on lateral surfaces of maxilla and mandible
• Orbicularis oris; submucosa of cheek and lips</td><td>Facial nerve</td></tr>
<tr><td colspan="4">The Cervical and Mental Region. The <i>platysma</i> is a thin superficial muscle of the upper chest and lower face. It is relatively unimportant, but when men shave, they tend to tense the platysma to make the concavity between the jaw and neck shallower and the skin tauter.</td></tr>
<tr><td>Platysma[16]
(plah-TIZ-muh)</td><td>Draws lower lip and angle of mouth downward in expressions of horror or surprise; may aid in opening mouth widely</td><td>• Fascia of deltoid and pectoralis major
• Mandible; skin and subcutaneous tissue of lower face</td><td>Facial nerve</td></tr>
</table>

---

[13] *depress* = to lower; *angul* = angle, corner; *or* = mouth

[14] *labi* = lip; *inferior* = lower

[15] *buccinator* = trumpeter

[16] *platy* = flat

TABLE 11.3 Muscles of Chewing and Swallowing

The following muscles contribute to facial expression and speech, but are primarily concerned with food manipulation.

Extrinsic Muscles of the Tongue. The tongue is a very agile organ. It pushes food between the molars for chewing *(mastication)* and later forces the food into the pharynx for swallowing *(deglutition);* it is also, of course, of crucial importance to speech. Both intrinsic and extrinsic muscles are responsible for its complex movements. The intrinsic muscles consist of a variable number of vertical fascicles that extend from the superior to the inferior sides of the tongue, transverse fascicles that extend from right to left, and longitudinal fascicles that extend from root to tip (see figs. 10.2c, p. 238, and 24.5b, p. 659). The extrinsic muscles listed here connect the tongue to other structures in the head (fig. 11.5). Three of these are innervated by the hypoglossal nerve (CN XII), whereas the fourth is innervated by both the vagus (CN X) and accessory (CN XI) nerves.


Palatoglossus
Styloglossus
Inferior longitudinal muscle of tongue
Genioglossus
Mylohyoid (cut)
Geniohyoid
Larynx
Trachea
Styloid process
Mastoid process
Posterior belly of digastric (cut)
Superior pharyngeal constrictor (cut)
Stylohyoid
Middle pharyngeal constrictor
Hyoglossus
Hyoid bone
Inferior pharyngeal constrictor
Esophagus

Figure 11.5 Muscles of the Tongue and Pharynx.

Name	Action	Skeletal Attachments	Innervation
Genioglossus[17] (JEE-nee-oh-GLOSS-us)	Unilateral action draws tongue to one side; bilateral action depresses midline of tongue or protrudes tongue	• Superior mental spine on posterior surface of mental protuberance • Inferior surface of tongue from root to apex	Hypoglossal nerve
Hyoglossus[18] (HI-oh-GLOSS-us)	Depresses tongue	• Body and greater horn of hyoid bone • Lateral and inferior surfaces of tongue	Hypoglossal nerve
Styloglossus[19] (STY-lo-GLOSS-us)	Draws tongue upward and posteriorly	• Styloid process of temporal bone and ligament from styloid process to mandible • Superolateral surface of tongue	Hypoglossal nerve
Palatoglossus[20] (PAL-a-toe-GLOSS-us)	Elevates root of tongue and closes oral cavity off from pharynx; forms palatoglossal arch at rear of oral cavity	• Soft palate • Lateral surface of tongue	Vagus and accessory nerves

---

[17] *genio* = chin; *gloss* = tongue
[18] *hyo* = hyoid bone; *gloss* = tongue
[19] *stylo* = styloid process; *gloss* = tongue
[20] *palato* = palate; *gloss* = tongue

TABLE 11.3 Muscles of Chewing and Swallowing (continued)

Muscles of Chewing. Four pairs of muscles produce the biting and chewing movements of the mandible: the *temporalis, masseter,* and two pairs of *pterygoid muscles* (fig. 11.6). Their actions include depression to open the mouth for receiving food; elevation for biting off a piece of food or crushing it between the teeth; protraction so that the incisors meet in cutting off a piece of food, and retraction to draw the lower incisors behind the upper incisors and make the rear teeth meet; and lateral and medial excursion, the side-to-side movements that grind food between the rear teeth. The last four of these movements are shown in figure 9.15 (p. 218). All of these muscles are innervated by the mandibular nerve, which is a branch of the trigeminal (CN V).



(a) Lateral view **(b) Posterior view**

Figure 11.6 **Muscles of Chewing.** Boldface labels indicate muscles that act on the mandible in its chewing movements. (a) Right lateral view. In order to expose the attachment of the temporalis muscle to the mandible, part of the zygomatic arch and masseter muscle are removed. (b) View of the pterygoid muscles looking into the oral cavity from behind the skull.

- *Explain how the medial pterygoid muscles can produce both lateral and medial excursion of the mandible.*

Name	Action	Skeletal Attachments	Innervation
Temporalis[21] (TEM-po-RAY-liss)	Elevation, retraction, and lateral and medial excursion of the mandible	• Temporal lines and temporal fossa of cranium • Coronoid process and anterior border of mandibular ramus	Trigeminal nerve
Masseter[22] (ma-SEE-tur)	Elevation of the mandible, with smaller roles in protraction, retraction, and lateral and medial excursion	• Zygomatic arch • Lateral surface of mandibular ramus and angle	Trigeminal nerve
Medial Pterygoid[23] (TERR-ih-goyd)	Elevation, protraction, and lateral and medial excursion of the mandible	• Medial surface of lateral pterygoid plate, palatine bone, lateral surface of maxilla near molar teeth • Medial surface of mandibular ramus and angle	Trigeminal nerve
Lateral Pterygoid	Depression (in wide opening of the mouth), protraction, and lateral and medial excursion of the mandible	• Lateral surfaces of lateral pterygoid plate and greater wing of sphenoid • Neck of mandible (just below condyle); articular disc and capsule of temporomandibular joint	Trigeminal nerve

---

[21] *temporalis* = of the temporal region of the head
[22] *masset* = chew
[23] *pteryg* = wing; *oid* = resembling (refers to pterygoid plate of sphenoid bone)

TABLE 11.3 Muscles of Chewing and Swallowing (continued)

Hyoid Muscles—Suprahyoid Group. Several aspects of chewing, swallowing, and vocalizing are aided by eight pairs of *hyoid muscles* associated with the hyoid bone (fig. 11.7). The **suprahyoid group** is composed of the four pairs superior to the hyoid—the *digastric, geniohyoid, mylohyoid,* and *stylohyoid.* The digastric is an unusual muscle, named for its two bellies. Its *posterior belly* arises from the mastoid notch of the cranium and slopes downward and forward. The *anterior belly* arises from a trench called the *digastric fossa* on the inner surface of the mandibular body. It slopes downward and backward. The two bellies meet at a constriction, the *intermediate tendon.* This tendon passes through a connective tissue loop, the *fascial sling,* attached to the hyoid bone. Thus, when the two bellies of the digastric contract, they pull upward on the hyoid; but if the hyoid is fixed from below, the digastric aids in wide opening of the mouth. The lateral pterygoids are more important in wide mouth opening, with the digastrics coming into play only in extreme opening, as in yawning or taking a large bite of an apple. Cranial nerves V (trigeminal), VII (facial), and XII (hypoglossal) innervate these muscles.

Name	Action	Skeletal Attachments	Innervation
Digastric[24]	Depresses mandible when hyoid is fixed; opens mouth widely, as when ingesting food or yawning; elevates hyoid when mandible is fixed	• Mastoid notch of temporal bone, digastric fossa of mandible • Hyoid bone, via fascial sling	Posterior belly: facial nerve Anterior belly: trigeminal nerve
Geniohyoid[25] (JEE-nee-oh-HY-oyd)	Depresses mandible when hyoid is fixed; elevates and protracts hyoid when mandible is fixed	• Inferior mental spine of mandible • Hyoid bone	Spinal nerve C1 via hypoglossal nerve
Mylohyoid[26]	Spans mandible from side to side and forms floor of mouth; elevates floor of mouth in initial stage of swallowing	• Mylohyoid line near inferior margin of mandible • Hyoid bone	Trigeminal nerve
Stylohyoid	Elevates and retracts hyoid, elongating floor of mouth; roles in speech, chewing, and swallowing are not yet clearly understood.	• Styloid process of temporal bone • Hyoid bone	Facial nerve

Hyoid Muscles—Infrahyoid Group. The **infrahyoid group** is inferior to the hyoid bone. By fixing the hyoid from below, they enable the suprahyoid muscles to open the mouth. The *omohyoid* is unusual in that it arises from the shoulder, passes under the sternocleidomastoid, and then ascends to the hyoid bone. Like the digastric, it has two bellies. The *thyrohyoid,* named for the hyoid bone and the large shield-shaped *thyroid cartilage* of the larynx, helps prevent choking. It elevates the larynx during swallowing so that its superior opening is sealed by a flap of tissue, the *epiglottis.* You can feel this effect by placing your finger on the "Adam's apple" (the anterior prominence of the thyroid cartilage) and feeling it bob up as you swallow. The *sternothyroid* muscle then pulls the larynx down again so you can resume breathing; it is the only infrahyoid muscle with no connection to the hyoid bone. The sternohyoid lowers the hyoid bone after it has been elevated.

The infrahyoid muscles that act on the larynx are regarded as the extrinsic muscles of the larynx. The *intrinsic muscles*, considered in chapter 23, are concerned with control of the vocal cords and laryngeal opening. The *ansa cervicalis*,[27] which innervates three of these muscles, is a loop of nerve on the side of the neck formed by certain fibers from cervical nerves 1 to 3 (see fig. 14.13, p. 386). Cranial nerves IX (glossopharyngeal), X (vagus), and XII (hypoglossal) also innervate these muscles.

Name	Action	Skeletal Attachments	Innervation
Omohyoid[28]	Depresses hyoid after it has been elevated	• Superior border of scapula • Hyoid bone	Ansa cervicalis
Sternohyoid[29]	Depresses hyoid after it has been elevated	• Manubrium of sternum, medial end of clavicle • Hyoid bone	Ansa cervicalis
Thyrohyoid[30]	Depresses hyoid; with hyoid fixed, elevates larynx as in singing high notes	• Thyroid cartilage of larynx • Hyoid bone	Spinal nerve C1 via hypoglossal nerve
Sternothyroid	Depresses larynx after it has been elevated in swallowing and vocalization; aids in singing low notes	• Manubrium of sternum, costal cartilage 1 • Thyroid cartilage of larynx	Ansa cervicalis

Muscles of the Pharynx. The three pairs of *pharyngeal constrictors* encircle the pharynx on its posterior and lateral sides, forming a muscular funnel that aids in swallowing (fig. 11.5).

Name	Action	Skeletal Attachments	Innervation
Pharyngeal Constrictors (three muscles)	During swallowing, contract in order from *superior* to *middle* to *inferior constrictor* to drive food into esophagus	• Medial pterygoid plate, mandible, hyoid bone, stylohyoid ligament, cricoid and thyroid cartilages of larynx • Median pharyngeal raphe (seam on posterior side of pharynx); basilar part of occipital bone	Glossopharyngeal and vagus nerves

---

[24] *di* = two; *gastr* = bellies
[25] *genio* = chin
[26] *mylo* = mill, molar tooth
[27] *ansa* = handle; *cervic* = neck; *alis* = of, belonging to
[28] *omo* = shoulder
[29] *sterno* = chest, sternum
[30] *thyro* = shield (refers to thyroid cartilage)

TABLE 11.3 Muscles of Chewing and Swallowing (continued)


Superficial
Deep
Suprahyoid group
Digastric:
Anterior belly
Posterior belly
Stylohyoid
Mylohyoid
Levator scapulae
Infrahyoid group
Sternohyoid
Omohyoid:
Superior belly
Inferior belly
Sternocleidomastoid
Hyoid bone
Common carotid artery
Internal jugular vein
Thyrohyoid
Sternothyroid
Infrahyoid group
Clavicle

(a) Anterior view


Stylohyoid
Hyoglossus
Mylohyoid
Digastric (anterior belly)
Hyoid bone
Thyrohyoid
Omohyoid (superior belly)
Sternothyroid
Sternohyoid
Digastric (posterior belly)
Splenius capitis
Inferior pharyngeal constrictor
Sternocleidomastoid
Trapezius
Levator scapulae
Scalenes
Omohyoid (inferior belly)

(b) Lateral view

Figure 11.7 Muscles of the Neck. Boldface labels indicate muscles of the suprahyoid and infrahyoid groups. Another muscle of the suprahyoid group, the geniohyoid, lies deep to the mylohyoid and can be seen in figure 11.5.

TABLE 11.4 Muscles Acting on the Head

Muscles that move the head extend from the vertebral column, thoracic cage, and pectoral girdle to the cranial bones. Their actions include flexion (tipping the head forward), lateral flexion (tilting the head to one side), extension (holding the head erect), hyperextension (as in looking upward), and rotation (turning the head to look left or right). Flexion, extension, and hyperextension involve simultaneous action of the right and left muscles of a pair; the other actions require the muscle on one side to contract more strongly than its mate. Many head actions result from a combination of these movements—for example, looking up over the shoulder involves a combination of rotation and hyperextension.

Depending on the relations of the muscle attachments, a muscle may cause a contralateral[31] movement of the head (toward the opposite side, as when contraction of a muscle on the left turns the face toward the right) or an ipsilateral[32] movement (toward the same side as the muscle, as when contraction of a muscle on the left tilts the head to the left).

The muscles of head movement are innervated mainly by cervical spinal nerves, with some contribution from CN XI (the accessory nerve) and thoracic nerves.

Flexors of the Neck. The prime mover of neck flexion is the *sternocleidomastoid,* a thick muscular cord that extends from the upper chest (sternum and clavicle) to the mastoid process behind the ear (fig. 11.7). This is most easily seen when the head is rotated to one side and slightly extended. To visualize the action of a single sternocleidomastoid, place the index finger of your left hand on your left mastoid process and the index finger of your right hand on your suprasternal notch. Now contract your left sternocleidomastoid to bring your two fingertips as close together as possible. You will see that this tilts your head so that your left ear approaches the shoulder and you look toward the right and slightly upward.

The three *scalenes*[33] (*anterior, middle,* and *posterior*), located on the side of the neck, are named for being arranged somewhat like a staircase. Their actions are similar so they are considered collectively.

Name	Action	Skeletal Attachments	Innervation
Sternocleidomastoid[34] (STIR-no-CLY-do-MAST-oyd)	Unilateral action tilts head slightly upward and toward the opposite side, as in looking over one's contralateral shoulder. The most common action is probably rotating the head to the left and right. Bilateral action draws the head straight forward and down, as when eating or reading. Aids in deep breathing when head is fixed.	• Manubrium of sternum, medial one-third of clavicle • Mastoid process and lateral half of superior nuchal line	Accessory nerve, spinal nerves C2–C4
Scalenes (Anterior, Middle, and Posterior) (SCAY-leens)	Unilateral contraction causes ipsilateral flexion or contralateral rotation (tilts head toward same shoulder, or rotates face away), depending on action of other muscles. Bilateral contraction flexes neck. If spine is fixed, scalenes elevate ribs 1–2 and aid in breathing.	• Transverse processes of all cervical vertebrae (C1–C7) • Ribs 1–2	Anterior rami of C3–C8

Extensors of the Neck. The extensors are located mainly in the nuchal region (back of the neck; fig. 11.8) and therefore tend to hold the head erect or draw it back. The *trapezius* is the most superficial of these. It extends from the nuchal region over the shoulders and halfway down the back (see fig. 11.13). It is named for the fact that the right and left trapezii together form a trapezoidal (diamond) shape. The *splenius* is a deeper, elongated muscle with *splenius capitis* and *splenius cervicis* regions in the head and neck, respectively. It is nicknamed the "bandage muscle" because of the way it wraps around still deeper neck muscles. One of those deeper muscles is the *semispinalis,* another elongated muscle with head, neck, and thoracic regions. Only the *semispinalis capitis* and *cervicis* are tabulated here; the *semispinalis thoracis* does not act on the neck, but is included in table 11.7.

Name	Action	Skeletal Attachments	Innervation
Trapezius[35] (tra-PEE-zee-us)	Extends neck as in looking up; laterally flexes neck. See also roles in scapular movement in table 12.1 (p. 296).	• External occipital protuberance, medial one-third of superior nuchal line, nuchal ligament, spinous processes of vertebrae C7–T12 • Acromion and spine of scapula, lateral one-third of clavicle	Accessory nerve

---

[31] *contra* = other, opposite; *later* = side
[32] *ipsi* = same; *later* = side
[33] *scal* = staircase
[34] *sterno* = chest, sternum; *cleido* = hammer, clavicle; *mastoid* = breastlike, mastoid process
[35] *trapez* = table, trapezoid

TABLE 11.4 Muscles Acting on the Head (continued)



© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Figure 11.8 Muscles of the Shoulder and Nuchal Regions. AP|R

Name	Action	Skeletal Attachments	Innervation
Splenius Capitis[36] (SPLEE-nee-us CAP-ih-tiss) and **Splenius Cervicis**[37] (SIR-vih-sis)	Acting unilaterally, produce ipsilateral flexion and slight rotation of head; extend head when acting bilaterally	• Inferior half of nuchal ligament, spinous processes of vertebrae C7–T6 • Mastoid process and occipital bone just below the superior nuchal line; cervical vertebrae C1–C2 or C3	Posterior rami of middle cervical nerves
Semispinalis Capitis (SEM-ee-spy-NAY-lis) and **Semispinalis Cervicis**	Extend and contralaterally rotate head	• Articular processes of vertebrae C4–C7, transverse processes of T1–T6 • Occipital bone between nuchal lines, spinous processes of vertebrae C2–C5	Posterior rami of cervical and thoracic nerves

Apply What You Know

Of the muscles you have studied so far, name three that you would consider intrinsic muscles of the head and three that you would classify as extrinsic. Explain your reason for each.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

3. Name two muscles that elevate the upper lip and two that depress the lower lip.
4. Name the four paired muscles of mastication and state where they attach to the mandible.
5. Distinguish between the functions of the suprahyoid and infrahyoid muscles.
6. List the prime movers of neck extension and flexion.

---

[36] *splenius* = bandage; *capitis* = of the head
[37] *cervicis* = of the neck

11.3 Muscles of the Trunk

Expected Learning Outcomes

When you have completed this section, you should be able to

a. name and locate the muscles of respiration and explain how they affect airflow and abdominal pressure;
b. name and locate the muscles of the abdominal wall, back, and pelvic floor; and
c. identify the attachments, action, and innervation of any of these muscles.

In this section, we will examine muscles of the trunk of the body in three functional groups concerned with respiration, support of the abdominal wall and pelvic floor, and movement of the vertebral column (tables 11.5–11.8). In the illustrations, you will note some major muscles that are not discussed in the associated tables—for example, the pectoralis major and serratus anterior. Although they are *located in* the trunk, they *act upon* the limbs and limb girdles and are therefore discussed in chapter 12.

TABLE 11.5 Muscles of Respiration

We breathe primarily by means of muscles that enclose the thoracic cavity—the diaphragm and the external intercostal, internal intercostal, and innermost intercostal muscles (fig. 11.9).

The *diaphragm* is a muscular dome between the thoracic and abdominal cavities, bulging upward against the base of the lungs. It has openings for passage of the esophagus, major blood and lymphatic vessels, and nerves between the two cavities. Its fibers converge from the margins toward a fibrous **central tendon.** When the diaphragm contracts, it flattens slightly and enlarges the thoracic cavity, causing air intake *(inspiration);* when it relaxes, it rises and shrinks the thoracic cavity, expelling air *(expiration).*

Three layers of muscle lie between the ribs: the external, internal, and innermost intercostal muscles. The 11 pairs of *external intercostal muscles* constitute the most superficial layer. They extend from the rib tubercle posteriorly almost to the beginning of the costal cartilage anteriorly. Each one slopes downward and anteriorly from one rib to the next inferior one. The 11 pairs of *internal intercostal muscles* lie deep to the external intercostals and extend from the margin of the sternum to the angles of the ribs. They are thickest in the region between the costal cartilages and grow thinner in the region where they overlap the external intercostals. Their fibers slope downward and posteriorly from each rib to the one below, at nearly right angles to the external intercostals. Each is divided into an *intercartilaginous part* between the costal cartilages and an *interosseous part* between the ribs proper. The two parts differ in their respiratory roles. The *innermost intercostals* vary in number, as they are sometimes absent from the upper thoracic cage. Their fibers run in the same direction as the internal intercostals, and they are presumed to serve the same function. Intercostal nerves and blood vessels travel through the fascia between the internal and innermost intercostals (see fig. 14.12, p. 385).

The primary function of the intercostal muscles is to stiffen the thoracic cage during respiration so that it does not cave inward when the diaphragm descends. However, they also contribute to enlargement and contraction of the thoracic cage and thus add to the air volume that ventilates the lungs.



(b) Inferior view of diaphragm

(a) Lateral view of intercostal muscles

Figure 11.9 Muscles of Respiration. APR

TABLE 11.5 Muscles of Respiration (continued)

Name	Action	Skeletal Attachments	Innervation
Diaphragm[38] (DY-ah-fram)	Prime mover of inspiration (responsible for about two-thirds of air intake); contracts in preparation for sneezing, coughing, crying, laughing, and weight lifting; contraction compresses abdominal viscera and aids in childbirth and expulsion of urine and feces.	• Xiphoid process of sternum; ribs and costal cartilages 7–12; lumbar vertebrae • Central tendon of diaphragm	Phrenic nerves
External Intercostals[39] (IN-tur-COSS-tul)	When scalenes fix rib 1, external intercostals elevate and protract ribs 2–12; this expands the thoracic cavity and creates a partial vacuum, causing inflow of air. Exercise a braking action during expiration so that expiration is not overly abrupt.	• Inferior margins of ribs 1–11 • Superior margin of next lower rib	Intercostal nerves
Internal Intercostals	In inspiration, the intercartilaginous part aids in elevating the ribs and expanding the thoracic cavity. In expiration, the interosseous part depresses and retracts the ribs, compressing the thoracic cavity and expelling air. The latter occurs only in forceful expiration, not in relaxed breathing.	• Superior margins and costal cartilages of ribs 2–12; margin of sternum • Inferior margin of next higher rib	Intercostal nerves
Innermost Intercostals	Presumed to have the same action as the internal intercostals.	• Superomedial surface of ribs 2–12; may be absent from upper ribs • Medial edge of costal groove of next higher rib	Intercostal nerves

Many other muscles of the chest and abdomen contribute significantly to breathing (see Deeper Insight 11.1): the sternocleidomastoid and scalenes of the neck; pectoralis major and serratus anterior of the chest; serratus posterior superior and serratus posterior inferior of the back; latissimus dorsi of the lower back; internal and external abdominal obliques and transverse abdominal muscle; and even some of the anal muscles. The respiratory actions of all these muscles are described in chapter 23.

DEEPER INSIGHT 11.1

Difficulty Breathing

Asthma, emphysema, heart failure, and other conditions can cause *dyspnea,* difficulty catching one's breath. People with dyspnea make increased use of accessory muscles to aid the diaphragm and intercostals in breathing, and often lean on a table or chair back to breathe more deeply. This action fixes the clavicles and scapulae so that accessory muscles such as the *pectoralis major* and *serratus anterior* (see chapter 12) move the ribs instead of the bones of the pectoral girdle.

Apply What You Know

What muscles are eaten as "spare ribs"? What is the tough fibrous membrane between the meat and the bone?

---

[38] *dia* = across; *phragm* = partition
[39] *inter* = between; *costa* = rib

TABLE 11.6 Muscles of the Anterior Abdominal Wall

Unlike the thoracic cavity, the abdominal cavity has little skeletal support. It is enclosed, however, in layers of broad flat muscles whose fibers run in different directions, strengthening the abdominal wall on the same principle as the alternating layers of plywood. Three layers of muscle enclose the lumbar region and extend about halfway across the anterior abdomen (fig. 11.10). The most superficial layer is the *external abdominal oblique.* Its fibers pass downward and anteriorly. The next deeper layer is the *internal abdominal oblique,* whose fibers pass upward and anteriorly, roughly perpendicular to those of the external oblique. The deepest layer is the *transverse abdominal (transversus abdominis),* with horizontal fibers. Anteriorly, a pair of vertical *rectus abdominis muscles* extend from sternum to pubis. These are divided into segments by three transverse **tendinous intersections,** giving them an appearance that bodybuilders nickname the "six pack."

The tendons of the oblique and transverse muscles are *aponeuroses*—broad fibrous sheets that continue medially and inferiorly (figs. 11.11 and 11.12). At the rectus abdominis, they diverge and pass around its anterior and posterior sides, enclosing the muscle in a vertical sleeve called the **rectus sheath.** They meet again at a median line called the **linea alba** between the rectus muscles. Another line, the **linea semilunaris,** marks the lateral boundary where the rectus sheath meets the aponeurosis. The aponeurosis of the external oblique also forms a cordlike **inguinal ligament** at its inferior margin. This extends obliquely from the anterior superior spine of the ilium to the pubis. The linea alba, linea semilunaris, and inguinal ligament are externally visible on a person with good muscle definition (see fig. A.8, p. 338).



Figure 11.10 Cross Section of the Anterior Abdominal Wall.

Name	Action	Skeletal Attachments	Innervation
External Abdominal Oblique	Supports abdominal viscera against pull of gravity; stabilizes vertebral column during heavy lifting; maintains posture; compresses abdominal organs, thus aiding in forceful expiration and loud vocalization as in singing and public speaking; aids in childbirth, urination, defecation, and vomiting. Unilateral contraction causes contralateral rotation of waist.	• Ribs 5–12 • Anterior half of iliac crest, pubic symphysis, and superior margin of pubis	Anterior rami of spinal nerves T7–T12
Internal Abdominal Oblique	Same as external oblique except that unilateral contraction causes ipsilateral rotation of waist	• Inguinal ligament, iliac crest, and thoracolumbar fascia • Ribs 10–12, costal cartilages 7–10, pubis	Anterior rami of spinal nerves T7–L1
Transverse Abdominal	Compresses abdominal contents, with same effects as external oblique, but does not contribute to movements of vertebral column	• Inguinal ligament, iliac crest, thoracolumbar fascia, costal cartilages 7–12 • Linea alba, pubis, aponeurosis of internal oblique	Anterior rami of spinal nerves T7–L1
Rectus[40] Abdominis (REC-tus ab-DOM-ih-nis)	Flexes lumbar region of vertebral column; flexes waist as in bending forward or doing sit-ups; stabilizes pelvic region during walking; compresses abdominal viscera	• Pubic symphysis and superior margin of pubis • Xiphoid process, costal cartilages 5–7	Anterior rami of spinal nerves T6–T12

---

[40] *rectus* = straight

TABLE 11.6 Muscles of the Anterior Abdominal Wall (continued)


Tendinous intersections
Umbilicus
Linea alba
Aponeurosis of external oblique
Inguinal ligament
Superficial inguinal ring
Spermatic cord
External oblique
Internal oblique
Transversus abdominis
Rectus abdominis

© McGraw-Hill Education/Photo and Dissection by Christine Eckel

Figure 11.11 **Thoracic and Abdominal Muscles of the Cadaver.** The rectus sheath is removed on the anatomical left to expose the left rectus abdominis muscle. Inset shows area of dissection.


Pectoralis major
Tendinous intersections
Rectus sheath
Umbilicus
Linea semilunaris
Linea alba
Aponeurosis of external abdominal oblique
Latissimus dorsi
Serratus anterior
Rectus sheath (cut edges)
Transverse abdominal
Internal abdominal oblique (cut)
External abdominal oblique (cut)
Rectus abdominis
Inguinal ligament

(a) Superficial


Subclavius
Pectoralis minor (cut)
Pectoralis minor
Internal intercostals
Serratus anterior
External intercostals
Rectus abdominis (cut)
Rectus sheath
External abdominal oblique (cut)
Internal abdominal oblique
Internal abdominal oblique (cut)
Posterior wall of rectus sheath (rectus abdominis removed)
Inguinal ligament
Transverse abdominal (cut)

(b) Deep

Figure 11.12 **Thoracic and Abdominal Muscles.** (a) Superficial muscles. The left rectus sheath is cut away to expose the rectus abdominis muscle. (b) Deep muscles. On the anatomical right, the external abdominal oblique has been removed to expose the internal abdominal oblique, and the pectoralis major has been removed to expose the pectoralis minor. On the anatomical left, the internal abdominal oblique has been cut to expose the transverse abdominal, and the middle of the rectus abdominis has been cut out to expose the posterior rectus sheath.

- *Name at least three muscles that lie deep to the pectoralis major.* AP|R

TABLE 11.7 Muscles of the Back

Muscles of the back primarily extend, rotate, and laterally flex the vertebral column. The most prominent superficial back muscles are the latissimus dorsi and trapezius (fig. 11.13), but they are concerned with upper limb movements and covered in chapter 12. Deep to these are the *serratus posterior superior* and *inferior* (fig. 11.14). They extend from the vertebrae to the ribs. They aid in deep breathing and are discussed in chapter 23.

Deep to these is a prominent muscle, the *erector spinae,* which runs vertically for the entire length of the back from the cranium to the sacrum. It is a thick muscle, easily palpated on each side of the vertebral column in the lumbar region. (Pork chops and T-bone steaks are erector spinae muscles.) As it ascends, it divides in the upper lumbar region into three parallel columns (figs. 11.14 and 11.15). The most lateral of these is the *iliocostalis,*[41] which is divided from inferior to superior into the *iliocostalis lumborum, iliocostalis thoracis,* and *iliocostalis cervicis* (lumbar, thoracic, and cervical regions). The next medial column is the *longissimus,*[42] divided from inferior to superior into the *longissimus thoracis, longissimus cervicis,* and *longissimus capitis* (thoracic, cervical, and cephalic regions). The most medial column is the *spinalis,* divided into *spinalis thoracis, spinalis cervicis,* and *spinalis capitis.* The functions of all three columns are sufficiently similar that we will treat them collectively as the erector spinae.

The major deep muscles are the *semispinalis thoracis* in the thoracic region and *quadratus lumborum* in the lumbar region. The erector spinae and quadratus lumborum are enclosed in a fibrous sheath called the **thoracolumbar fascia,** an attachment for some of the abdominal and lumbar muscles. The *multifidus* is a collective name for a series of tiny muscles that connect adjacent vertebrae to each other from the cervical to lumbar region.

Figure 11.13 **Neck, Back, and Gluteal Muscles.** The most superficial muscles are shown on the left and the next deeper layer on the right. AP|R


Superficial
Deep
Sternocleidomastoid
Trapezius
Deltoid
Erector spinae
Latissimus dorsi
External abdominal oblique
Thoracolumbar fascia
Gluteus medius
Gluteus maximus
Semispinalis capitis
Splenius capitis
Levator scapulae
Rhomboid minor
Rhomboid major
Supraspinatus
Infraspinatus
Teres minor
Teres major
Serratus anterior
Serratus posterior inferior
External abdominal oblique
Internal abdominal oblique
Gluteus minimus
Lateral rotators

---

[41] *ilio* = ilium of the hip bone; *costalis* = pertaining to the ribs

[42] *longissimus* = longest

TABLE 11.7 **Muscles of the Back (continued)**

Name	Action	Skeletal Attachments	Innervation
Erector Spinae[43] (eh-REC-tur SPY-nee)	Maintains posture; straightens spine after one bends at the waist; arches back; laterally flexes vertebral column; longissimus capitis also produces ipsilateral rotation of the head	• Nuchal ligament, ribs 3–12, thoracic and lumbar vertebrae, median and lateral sacral crests, thoracolumbar fascia • Mastoid process, cervical and thoracic vertebrae, and all ribs	Posterior rami of cervical to lumbar spinal nerves
Semispinalis Thoracis (SEM-ee-spy-NAY-liss tho-RA-sis)	Extension and contralateral rotation of vertebral column	• Vertebrae T6–T10 • Vertebrae C6–T4	Posterior rami of cervical and thoracic spinal nerves


Superior nuchal line
Longissimus capitis
Splenius capitis
Serratus posterior superior
Splenius cervicis
Erector spinae:
Iliocostalis
Longissimus
Spinalis
Serratus posterior inferior
Internal abdominal oblique
External abdominal oblique (cut)
Semispinalis capitis
Semispinalis cervicis
Semispinalis thoracis
Multifidus
Quadratus lumborum

Figure 11.14 **Muscles Acting on the Vertebral Column.** Those on the right are deeper than those on the left. APR

---

[43] *erector* = that which straightens; *spinae* = of the spine

TABLE 11.7 **Muscles of the Back (continued)**

Name	Action	Skeletal Attachments	Innervation
Quadratus Lumborum[44] (quad-RAY-tus lum-BORE-um)	Aids respiration by fixing rib 12 and stabilizing inferior attachments of diaphragm. Unilateral contraction causes ipsilateral flexion of lumbar vertebral column; bilateral contraction extends lumbar vertebral column.	• Iliac crest, iliolumbar ligament • Rib 12 and vertebrae L1–L4	Anterior rami of spinal nerves T12–L4
Multifidus[45] (mul-TIFF-ih-dus)	Stabilization of adjacent vertebrae, maintenance of posture, control of vertebral movement when erector spinae acts on vertebral column	• Vertebrae C4–L5, posterior superior iliac spine, sacrum, aponeurosis of erector spinae • Laminae and spinous processes of vertebrae	Posterior rami of cervical to lumbar spinal nerves



Figure 11.15 Deep Back Muscles of the Cadaver.

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

DEEPER INSIGHT 11.2

Heavy Lifting and Back Injuries

When a skeletal muscle is excessively stretched, its sarcomeres are so stretched that its thick and thin myofilaments have little or no overlap. When such a muscle is stimulated to contract, few of the myosin heads are able to attach to the actin filaments (see chapter 10), the contraction is very weak, and the muscle and connective tissues are subject to injury.

When you are fully bent over forward, as in touching your toes, the erector spinae is extremely stretched. Standing up from such a position is therefore initiated by the hamstring muscles on the back of the thigh and the gluteus maximus of the buttocks. The erector spinae joins in the action when it is partially contracted. Standing too suddenly or improperly lifting a heavy weight, however, can strain the erector spinae, cause painful muscle spasms, tear tendons and ligaments of the lower back, and rupture intervertebral discs. The lumbar muscles are adapted for maintaining posture, not for lifting. This is why it is important, in heavy lifting, to bend at the knees and use the powerful extensor muscles of the thighs and buttocks to lift the load.

---

[44] *quadrat* = four-sided; *lumborum* = of the lumbar region

[45] *multi* = many; *fid* = branched, sectioned

TABLE 11.8 Muscles of the Pelvic Floor

The floor of the pelvic cavity is formed mainly by an extensive muscle called the *levator ani*. Inferior to this is the **perineum** (PERR-ih-NEE-um), a diamond-shaped area between the thighs bordered by four bony landmarks: the pubic symphysis anteriorly, the coccyx posteriorly, and the ischial tuberosities laterally. The pelvic floor and perineum are penetrated by the anal canal, urethra, and vagina. The anterior half of the perineum is the **urogenital triangle** and the posterior half is the **anal triangle** (fig. 11.16b). These are especially important landmarks in obstetrics. The urogenital triangle is divided into two muscle compartments separated by a strong fibrous **perineal membrane.** The muscle compartment between this membrane and the skin is called **superficial perineal space,** and the compartment between the perineal membrane and levator ani is the **deep perineal space.** We will examine these structures beginning inferiorly, just beneath the skin, and progressing superiorly to the pelvic floor.

Superficial Perineal Space. The superficial perineal space (fig. 11.16a) contains three pairs of muscles: the ischiocavernosus, bulbospongiosus, and superficial transverse perineal. In females, this space also contains the clitoris; various glands and erectile tissues of the genitalia (see fig. 26.20, p. 725); and adipose tissue, which extends into and fattens the mons pubis and labia majora. In males, it contains the root of the penis. The *ischiocavernosus* muscles converge like a V from the ischial tuberosities toward the penis or clitoris. In males, the *bulbospongiosus (bulbocavernosus)* muscles form a sheath around the root of the penis, and in females they enclose the vagina like a pair of parentheses. *Cavernosus* in these names refers to the spongy, cavernous structure of tissues in the penis and clitoris. The *superficial transverse perineal* muscles extend from the ischial tuberosities to a strong median fibromuscular anchorage, the **perineal body,** and a median seam called the **perineal raphe** (RAY-fee) that extends anteriorly from the perineal body. The muscles may help to anchor the perineal body, but they are weakly developed and not always present, therefore not tabulated below. The other two muscle pairs of this layer serve primarily sexual functions.

Name	Action	Skeletal Attachments	Innervation
Ischiocavernosus[46] (ISS-kee-oh-CAV-er-NO-sus)	Maintains erection of penis or clitoris by compressing deep structures of the organ and forcing blood forward into its body	• Ramus and tuberosity of ischium • Ensheaths internal structures of penis or clitoris	Pudendal nerve
Bulbospongiosus[47] (BUL-bo-SPUN-jee-OH-sus)	Expels residual urine from urethra after bladder has emptied. Aids in erection of penis or clitoris. In males, spasmodic contractions expel semen during ejaculation. In females, contractions constrict vaginal orifice and expel secretions of greater vestibular glands.	• Perineal body and median raphe • Male: Ensheaths root of penis Female: Pubic symphysis	Pudendal nerve

Deep Perineal Space. The deep perineal space (fig. 11.16b) contains a pair of *deep transverse perineal* muscles and, in females only, the *compressor urethrae* muscles. The deep transverse perineal muscles anchor the perineal body on the median plane; the perineal body, in turn, anchors other pelvic muscles. The female *external urethral sphincter*, long thought to be part of the deep perineal space, is now regarded as part of the urethra itself and not part of the pelvic floor musculature.

Deep Transverse Perineal	Anchors perineal body, which supports other pelvic muscles; supports vaginal and urethral canals	• Ischiopubic rami • Perineal body	Pudendal nerve
Compressor Urethrae	Aids in urine retention; found in female only	• Ischiopubic rami • Right and left compressor urethrae meet each other inferior to external urethral sphincter	Pudendal nerve; spinal nerves S2–S4; pelvic splanchnic nerve

Anal Triangle. The anal triangle contains the *external anal sphincter* and *anococcygeal ligament* (fig. 11.16b). The external anal sphincter is a tubular muscle surrounding the lower anal canal. The anococcygeal ligament is the median attachment of the levator ani muscles, and the ligament, in turn, leads to the coccyx. It is therefore a major anchorage for the structures that compose the pelvic floor.

External Anal Sphincter	Retains feces in rectum until voluntarily voided	• Coccyx, perineal body • Encircles anal canal and orifice	Pudendal nerve; spinal nerves S2–S4; pelvic splanchnic nerve

Pelvic Diaphragm. The pelvic diaphragm (fig. 11.16c) is deep to the foregoing structures and is composed mainly of the right and left *levator ani muscles*. (The piriformis, also illustrated, is primarily a lower limb muscle.) The levator ani spans most of the pelvic outlet and forms the floor of the lesser (true) pelvis. It is divided into three portions that are sometimes regarded as separate muscles—the *ischiococcygeus* (or *coccygeus*), *iliococcygeus*, and *pubococcygeus*. The left and right levator ani muscles converge on the anococcygeal ligament, through which they are indirectly anchored to the coccyx.

Levator Ani[48] (leh-VAY-tur AY-nye)	Compresses anal canal and reinforces external anal and urethral sphincters; supports uterus and other pelvic viscera; aids in the falling away of the feces; vertical movements affect pressure differences between abdominal and thoracic cavities and thus aid in deep breathing.	• Inner surface of lesser pelvis from pubis through margin of obturator internus to spine of ischium • Coccyx via anococcygeal body; walls of urethra, vagina, and anal canal	Pudendal nerve; spinal nerves S2–S3

---

[46] *ischio* = ischium of the hip bone; *cavernosus* = corpus cavernosum of the penis or clitoris
[47] *bulbo* = bulb of the penis; *spongiosus* = corpus spongiosum of the penis
[48] *levat* = to elevate; *ani* = of the anus

TABLE 11.8 Muscles of the Pelvic Floor (continued)


Perineal body
Superficial transverse perineal
Coccyx
Ischiocavernosus
Bulbospongiosus
Levator ani
Gluteus maximus

(a) Superficial perineal space, inferior view, male


Clitoris
Vagina
Perineal body
Deep transverse perineal
External anal sphincter
Urogenital triangle
Urethra
Compressor urethrae
Anus
Anal triangle

(b) Deep perineal space, inferior view, female


Pubic symphysis
Levator ani:
Pubococcygeus
Iliococcygeus
Ischiococcygeus
Piriformis
Nerve roots
Urethra
Vagina
Rectum
Fascia of obturator internus
Anococcygeal body
Sacrum

(c) Pelvic diaphragm, superior view, female

Figure 11.16 **Muscles of the Pelvic Floor.** (a) The superficial perineal space, male, viewed from below (the inferior aspect). (b) The deep perineal space, female, viewed from the same perspective. Other than the vaginal canal, the sexes are nearly identical at this level, including the urogenital and anal triangles. The root of the penis does not extend to this level. (c) The pelvic diaphragm, female, viewed from above (from within the pelvic cavity).

DEEPER INSIGHT 11.3

Hernias

A hernia is any condition in which the viscera protrude through a weak point in the muscular wall of the abdominopelvic cavity. The most common type to require treatment is an *inguinal hernia* (fig. 11.17). In the male fetus, each testis descends from the pelvic cavity into the scrotum by way of a passage called the *inguinal canal* through the muscles of the groin. This canal remains a weak point in the pelvic floor, especially in infants and children. When pressure rises in the abdominal cavity, it can force part of the intestine or bladder into this canal or even into the scrotum. This also sometimes occurs in men who hold their breath while lifting heavy weights. When the diaphragm and abdominal muscles contract, pressure in the abdominal cavity can soar to 1,500 pounds per square inch—more than 100 times the normal pressure and quite sufficient to produce an inguinal hernia, or "rupture." Inguinal hernias rarely occur in women.

Two other sites of hernia are the diaphragm and navel. A *hiatal hernia* is a condition in which part of the stomach protrudes through the diaphragm into the thoracic cavity. This is most common in overweight people over age 40. It may cause heartburn due to the regurgitation of stomach acid into the esophagus, but most cases go undetected. In an *umbilical hernia,* abdominal viscera protrude through the navel.


Aponeurosis of external abdominal oblique muscle
Inguinal canal
External inguinal ring
Herniated loop of small intestine
Upper scrotum

Figure 11.17 **Inguinal Hernia.** A loop of small intestine has protruded through the inguinal canal into a space beneath the skin.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

7. Which muscles are used more often, the external intercostals or internal intercostals? Explain.
8. Explain how pulmonary ventilation affects abdominal pressure, and vice versa.
9. Name a major superficial muscle and two major deep muscles of the back.
10. Define *perineum, urogenital triangle,* and *anal triangle.*
11. Name one muscle in the superficial perineal space, one in the urogenital diaphragm, and one in the pelvic diaphragm. State the function of each.

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

General

1. For all muscles named in this study guide, and to the extent specified by your course or instructor, an ability to locate the muscle on a model, photograph, diagram, or dissection; to palpate the muscle or its tendons on the living body; and to identify its attachments, innervation, and actions

11.1 Learning Approaches (p. 264)

1. Ability to translate words commonly used in the naming of muscles and denoting such characteristics as muscle size, shape, location, number of heads, orientation, and action (table 11.1)
2. The meaning of muscle *innervation;* the relationship of cranial and spinal nerves to the muscles; and the common symbols for these nerves

11.2 Muscles of the Head and Neck (p. 268)

1. Two scalp muscles—the *frontalis* and *occipitalis*—and their relationship to the galea aponeurotica (table 11.2)
2. Three muscles of the ocular region—the *orbicularis oculi, levator palpebrae superioris,* and *corrugator supercilii* (table 11.2)
3. The *nasalis muscle* of the nasal region (table 11.2)
4. The location of the modiolus and how it is related to muscles of the oral and buccal regions
5. Nine muscles of the oral region—the *orbicularis oris, levator labii superioris, levator anguli oris, zygomaticus major* and *minor, risorius, depressor anguli oris,* and *depressor labii inferioris* (table 11.2)
6. Three muscles of the cheek, chin, and anterior neck—the *mentalis, buccinator,* and *platysma* (table 11.2)
7. The difference between the intrinsic and extrinsic muscles of the tongue
8. Four extrinsic tongue muscles—the *genioglossus, hyoglossus, styloglossus,* and *palatoglossus* (table 11.3)
9. Four muscles of chewing—the *temporalis, masseter, medial pterygoid,* and *lateral pterygoid* (table 11.3)
10. The difference between the suprahyoid and infrahyoid muscle groups
11. Four muscles in the suprahyoid group—the *digastric, geniohyoid, mylohyoid,* and *stylohyoid* (table 11.3)
12. Four muscles of the infrahyoid group—the *omohyoid, sternohyoid, thyrohyoid,* and *sternothyroid* (table 11.3)
13. The three *pharyngeal constrictors* and their role in swallowing (table 11.3)
14. Four flexor muscles of the neck—the *sternocleidomastoid* and three *scalene muscles*
15. Locations of the anterior and posterior triangles of the neck in relation to the sternocleidomastoid
16. Five major extensors of the neck—the *trapezius, splenius capitis, splenius cervicis, semispinalis capitis,* and *semispinalis cervicis* (table 11.4)

11.3 Muscles of the Trunk (p. 279)

1. The *diaphragm* and the three layers of intercostal muscles—*external, internal,* and *innermost intercostals* (table 11.5)
2. The contributions of other thoracic and abdominopelvic muscles to breathing
3. The four principal muscles that form the abdominal wall—the *external abdominal oblique, internal abdominal oblique, transverse abdominal,* and *rectus abdominis* (table 11.6)
4. The relationship of the abdominal muscles to the rectus sheath, inguinal ligament, linea alba, and linea semilunaris
5. The erector spinae and its three columns—the *iliocostalis, longissimus,* and *thoracis*—and the regional subdivisions of each column (lumbar, thoracic, cervical, and cephalic, with variations from one column to another) (table 11.7)
6. The *semispinalis thoracis, quadratus lumborum,* and *multifidus* (table 11.7)
7. The thoracolumbar fascia and its relationship to the erector spinae and quadratus lumborum
8. The boundaries of the perineum; its two triangles; and its two muscle compartments
9. The two main muscles of the superficial perineal space—the *ischiocavernosus* and *bulbospongiosus* (table 11.8)
10. The deep perineal space and its principal muscle, the *deep transverse perineal muscle* (table 11.8); how the sexes differ in anatomy of the deep perineal space
11. The one muscle of the anal triangle—the *external anal sphincter*—and significance of the anococcygeal ligament
12. The pelvic diaphragm and its *levator ani muscles*

Testing Your Recall

1. Which of the following muscles is the prime mover in spitting out a mouthful of liquid?
   a. platysma
   b. buccinator
   c. risorius
   d. masseter
   e. palatoglossus

2. The word _____ in a muscle name indicates a function related to the head.
   a. cervicis
   b. carpi
   c. capitis
   d. hallucis
   e. teres

3. Which of these is *not* a suprahyoid muscle?
   a. genioglossus
   b. geniohyoid
   c. stylohyoid
   d. mylohyoid
   e. digastric

4. Which of these muscles is an extensor of the neck?
   a. external oblique
   b. sternocleidomastoid
   c. splenius capitis
   d. iliocostalis
   e. latissimus dorsi
5. Which of these muscles of the pelvic floor is the deepest?
   a. superficial transverse perineal
   b. bulbospongiosus
   c. ischiocavernosus
   d. deep transverse perineal
   e. levator ani
6. The facial nerve supplies all of the following muscles *except*
   a. the frontalis.
   b. the orbicularis oculi.
   c. the orbicularis oris.
   d. the depressor labii inferioris.
   e. the mylohyoid.
7. The _____ produce(s) lateral grinding movements of the jaw.
   a. pterygoids
   b. temporalis
   c. hyoglossus
   d. zygomaticus major and minor
   e. risorius
8. All of the following muscles act on the vertebral column *except*
   a. the serratus posterior superior.
   b. the iliocostalis thoracis.
   c. the longissimus thoracis.
   d. the spinalis thoracis.
   e. the multifidus.
9. A muscle that aids in chewing without moving the mandible is
   a. the temporalis.
   b. the mentalis.
   c. the buccinator.
   d. the levator anguli oris.
   e. the splenius cervicis.
10. Which of the following muscles raises the upper lip?
    a. levator palpebrae superioris
    b. orbicularis oris
    c. masseter
    d. zygomaticus minor
    e. mentalis
11. The prime mover of spinal extension is the _____.
12. Ejaculation results from contraction of the _____ muscle.
13. The muscle that opens your eyes is the _____.
14. As its name implies, the _____ nerve controls several muscles of the tongue.
15. The _____ muscle, named for its two bellies, opens the mouth.
16. The anterior half of the perineum is a region called the _____.
17. The abdominal aponeuroses converge on a median fibrous band on the abdomen called the _____.
18. The thyrohyoid muscle attaches to the thyroid cartilage of the _____.
19. The _____ muscles diverge like a V from the middle of the upper thorax to attachments behind the ears.
20. The largest muscle of the upper back is the _____.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. delt-
2. levat-
3. oculo-
4. apo-
5. oris
6. digito-
7. labio-
8. ipsi-
9. glosso-
10. di-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. The sternocleidomastoid muscle acts mainly as a fixator of the sternum.
2. The largest deep muscle of the lower back is the quadratus lumborum.
3. The muscle used to stick out your tongue is the genioglossus.
4. The abdominal oblique muscles rotate the vertebral column.
5. Exhaling requires contraction of the internal intercostal muscles.
6. The digastric muscles form the floor of the mouth.
7. The scalenes are superficial to the trapezius.
8. Cutting the phrenic nerves would paralyze the prime mover of respiration.
9. The orbicularis oculi and orbicularis oris are sphincters.
10. All of the cranial nerves innervate muscles of the head and neck.

Answers in appendix A

Testing Your Comprehension

1. Name one antagonist of each of the following muscles: (a) orbicularis oculi, (b) genioglossus, (c) masseter, (d) sternocleidomastoid, (e) rectus abdominis.
2. Name one synergist of each of the following muscles: (a) temporalis, (b) diaphragm, (c) platysma, (d) semispinalis capitis, (e) bulbospongiosus.
3. Dental procedures, vaccination, HIV infection, and some other infections occasionally injure branches of the facial nerve and weaken or paralyze the affected muscles. Predict the problems that a person would have if the orbicularis oris and buccinator muscles were paralyzed by such a nerve lesion.
4. Removal of cancerous lymph nodes from the neck sometimes requires removal of the sternocleidomastoid on that side. How would this affect a patient's range of head movement?
5. Deeper Insight 10.2 (p. 249) remarked that the Food and Drug Administration approved Botox Cosmetic only for the treatment of frown lines between the eyebrows. From the knowledge you have gained in this chapter, name the muscles into which a physician following those guidelines would inject Botox.



MRI image of muscles of the lumbar and pelvic region

© Simon Fraser/Science Source

CHAPTER

12

THE MUSCULAR SYSTEM III

APPENDICULAR MUSCULATURE

CHAPTER OUTLINE

12.1 Muscles Acting on the Shoulder and Upper Limb 294
- Muscle Groups and Compartments 294
- Muscles Acting on the Shoulder 295
- Muscles Acting on the Arm 297
- Muscles Acting on the Forearm 301
- Muscles Acting on the Wrist and Hand 303
- Intrinsic Muscles of the Hand 308

12.2 Muscles Acting on the Hip and Lower Limb 310
- Muscles Acting on the Hip and Thigh 310
- Muscles Acting on the Knee and Leg 313
- Muscles Acting on the Foot 316
- Intrinsic Muscles of the Foot 322

12.3 Muscle Injuries 324

Study Guide 326

DEEPER INSIGHTS

12.1 Compartment Syndrome 294
12.2 Evolution of Limb Muscles 300
12.3 Carpal Tunnel Syndrome 307
12.4 Intramuscular Injections 315
12.5 Hamstring Injuries 316

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:

- Terminology of the limb regions (p. 16)
- Anatomy of the appendicular skeleton (chapter 8)
- Terminology of joint actions (pp. 213–219)
- Shapes of muscles (fusiform, pennate, circular, etc.) (pp. 238–239)
- Prime movers, synergists, antagonists, and fixators (pp. 240–241)
- Intrinsic and extrinsic muscles (p. 241)
- Muscle innervation (p. 264)
- Greek and Latin words commonly used to name muscles (table 11.1, p. 265)

Anatomy & Physiology REVEALED®
aprevealed.com

Module 6: Muscular System

The appendicular musculature includes not only the muscles of the upper and lower limbs (appendages), but also several prominent muscles of the trunk that act on the limbs. In most vertebrate animals, these muscles serve for little more than locomotion, with such exceptions as digging (moles) and limited manipulation of objects (squirrels, raccoons). The upright locomotion of humans, however, has been associated with a number of evolutionary changes—large, heavily muscled lower limbs for standing, walking, and running, and upper limbs that have less muscular bulk but more mobile joints and an array of smaller muscles adapted for climbing and, more importantly, precise manipulation of objects. In this chapter, we examine the four major groups of appendicular muscles—those of the pectoral girdle, upper limb, pelvic girdle, and lower limb. We also consider several muscle injuries, which are more common in the appendicular region than in the axial region.

12.1 Muscles Acting on the Shoulder and Upper Limb

Expected Learning Outcomes

When you have completed this section, you should be able to

a. explain what muscle compartments are and describe how they are separated from each other;
b. name and locate the muscles that act on the shoulder, arm, forearm, wrist, and hand;
c. relate the actions of these muscles to the joint movements described in chapter 9; and
d. describe the attachments and innervation of each muscle.

Muscle Groups and Compartments

The upper and lower limbs have numerous muscles that serve primarily for movement of the body and manipulation of objects. Although their number presents a learning challenge, they are arranged in logical groups that make their functional relationships easier to understand. Their names alone are often helpful indications of their functions and locations. For example, *flexor carpi ulnaris* translates "flexor of the wrist (associated with) the ulna." As a flexor, it is found on the anterior side of the forearm so it can bend the wrist anteriorly, and the name further tells us that it is on the ulnar (medial) side of the forearm. You may find it helpful to review table 11.1 (p. 265) on the naming of muscles and to pay attention to the footnotes in this chapter until such terms as *flexor* and *ulnaris* become intuitively easy to remember.

In the limbs, fibrous sheets of connective tissue, the *fasciae,* enclose spaces called **compartments.** Each compartment contains one or more functionally related muscles along with their nerve and blood supplies (fig. 12.1). We have already seen such compartmentalization in the abdominal wall and pelvic floor (chapter 11). In the ensuing tables, you will find muscles of the upper limb divided into anterior and posterior compartments, and those of the lower limb divided into anterior, posterior, medial, and lateral compartments. These major compartments are separated from each other by especially thick fasciae called **intermuscular septa,** and by the interosseous membranes of the forearm and leg (see chapter 8). In most limb regions, the muscle groups are further subdivided by thinner fasciae into superficial and deep layers. A serious problem called *compartment syndrome,* occurring when one of the muscles or blood vessels in a compartment is injured, is due partly to the fact that the muscles are so tightly bound by their fasciae (see Deeper Insight 12.1).

The upper limb is used for a broad range of both powerful and subtle actions, ranging from climbing, grasping, and throwing to writing, playing musical instruments, and manipulating small objects. Tables 12.1 through 12.5 group these into muscles that act on the scapula, those that act on the humerus and shoulder joint, those that act on the forearm and elbow joint, extrinsic (forearm) muscles that act on the wrist and hand, and intrinsic (hand) muscles that act on the fingers.

DEEPER INSIGHT 12.1

Compartment Syndrome

The fasciae of the upper and lower limb enclose the muscle compartments very snugly. If a blood vessel in a compartment is damaged by overuse or contusion (a bruising injury), blood and tissue fluid accumulate in the compartment. The fasciae prevent the compartment from expanding to relieve the pressure. Mounting pressure on the muscles, nerves, and blood vessels triggers a sequence of degenerative events called *compartment syndrome.* Blood flow to the compartment is obstructed by pressure on its arteries. If *ischemia* (poor blood flow) persists for more than 2 to 4 hours, nerves begin to die, and after 6 hours, so does muscle tissue. Nerves can regenerate after the pressure is relieved, but muscle necrosis is irreversible. The breakdown of muscle releases myoglobin into the blood. *Myoglobinuria,* the presence of myoglobin in the urine, gives the urine a dark color and is one of the key signs of compartment syndrome and some other degenerative muscle disorders. Compartment syndrome is treated by immobilizing and resting the limb and, if necessary, making an incision *(fasciotomy)* to relieve the compartment pressure.


Anterior
Lateral
Medial
Posterior
Tibia
Fibula
Interosseous membrane
Artery, veins, and nerve
Intermuscular septa
Fasciae
Subcutaneous fat
Key
Anterior compartment
Lateral compartment
Posterior compartment, deep layer
Posterior compartment, superficial layer

Figure 12.1 **Muscular Compartments.** A cross section of the left leg slightly above midcalf, oriented the same way as the reader's.

TABLE 12.1 Muscles Acting on the Shoulder

Muscles that act on the pectoral girdle arise from the axial skeleton and insert on the clavicle and scapula. The scapula is only loosely attached to the thoracic cage and is capable of considerable movement (fig. 12.2)—rotation (as in raising and lowering the apex of the shoulder), elevation and depression (as in shrugging and lowering the shoulders), and protraction and retraction (pulling the shoulders forward and back). The clavicle braces the shoulder and moderates these movements.

Anterior Group. Muscles of the pectoral girdle fall into anterior and posterior groups (fig. 12.3 in table 12.2). The major muscles of the anterior group are the *pectoralis minor* and *serratus anterior* (see fig. 11.12b, p. 283). The pectoralis minor arises by three heads from ribs 3 to 5 and converges on the coracoid process of the scapula. The serratus anterior arises from separate heads on all or nearly all of the ribs, wraps laterally around the chest and passes across the back between the rib cage and scapula, and inserts on the medial (vertebral) border of the scapula. Thus, when it contracts, the scapula glides laterally and slightly forward around the ribs.

Name	Action	Skeletal Attachments	Innervation
Pectoralis[1] Minor (PECK-toe-RAY-lis)	With serratus anterior, draws scapula laterally and forward around chest wall, protracting shoulder as in reaching out for a door handle; with other muscles, rotates scapula and depresses apex of shoulder, as in reaching down to pick up a suitcase	• Ribs 3–5 and overlying fascia • Coracoid process of scapula	Medial and lateral pectoral nerves
Serratus[2] Anterior (serr-AY-tus)	Holds scapula against rib cage; with pectoralis minor, draws scapula laterally and forward around chest wall; protracts scapula, and is the prime mover in all forward-reaching, throwing, and pushing actions (nicknamed the "boxer's muscle" for its role in powerful thrusting movements such as a boxer's jab); aids in rotating scapula to elevate apex of shoulder, as in lifting a suitcase; fixes scapula during abduction of arm	• All or nearly all ribs • Medial border of scapula	Long thoracic nerve

---

[1] *pectoral* = of the chest
[2] *serrat* = scalloped, zigzag

TABLE 12.1 Muscles Acting on the Shoulder (continued)


Lateral rotation
Trapezius (superior part)
Serratus anterior
Elevation
Levator scapulae
Trapezius (superior part)
Rhomboid major
Rhomboid minor
Retraction
Rhomboid major
Rhomboid minor
Trapezius
Protraction
Pectoralis minor
Serratus anterior
Medial rotation
Levator scapulae
Rhomboid major
Rhomboid minor
Depression
Trapezius (inferior part)
Serratus anterior

Figure 12.2 **Actions of Some Thoracic Muscles on the Scapula.** Note that an individual muscle can contribute to multiple actions, depending on which fibers contract and what synergists act with it.

Posterior Group. The posterior muscles that act on the scapula include the large, superficial trapezius, already discussed (table 11.4, p. 277), and three deep muscles: the *rhomboid minor, rhomboid major* (the *rhomboids*), and *levator scapulae* (see fig. 11.13, p. 284). The action of the trapezius depends on whether its superior, middle, or inferior fibers contract and whether it acts alone or with other muscles. The levator scapulae and superior fibers of the trapezius rotate the scapula in opposite directions if either of them acts alone. If both act together, their opposite rotational effects balance each other and they elevate the scapula and shoulder, as when you lift a suitcase from the floor. Depression of the scapula occurs mainly by gravitational pull, but the trapezius and serratus anterior can depress it more rapidly and forcefully, as in swimming, hammering, and rowing.

Name	Action	Skeletal Attachments	Innervation
Trapezius (tra-PEE-zee-us)	Stabilizes scapula and shoulder during arm movements; elevates apex of shoulder; acts with other muscles to rotate and retract scapula, as in pulling a rope; produces fast, forcible depression of scapula as in swimming and hammering (see also roles in head and neck movements in table 11.4)	• External occipital protuberance; medial one-third of superior nuchal line; nuchal ligament; spinous processes of vertebrae C7–T12 • Acromion and spine of scapula; lateral one-third of clavicle	Accessory nerve
Levator Scapulae (leh-VAY-tur SCAP-you-lee)	Elevates scapula if cervical vertebrae are fixed; flexes neck laterally if scapula is fixed; retracts scapula and braces shoulder; rotates scapula and depresses apex of shoulder	• Transverse processes of vertebrae C1–C4 • Superior angle to medial border of scapula	Spinal nerves C3–C4, and C5 via dorsal scapular nerve
Rhomboid Minor[3] (ROM-boyd)	Retracts scapula and braces shoulder; fixes scapula during arm movements	• Spinous processes of vertebrae C7–T1; nuchal ligament • Medial border of scapula	Posterior scapular nerve
Rhomboid Major	Same as rhomboid minor	• Spinous processes of vertebrae T2–T5 • Medial border of scapula	Posterior scapular nerve

---

[3] *rhomb* = rhombus; *oid* = like; *minor* = small

TABLE 12.2 Muscles Acting on the Arm

Axial Muscles. Nine muscles cross the shoulder joint and end on the humerus. Two are considered **axial muscles** because they arise primarily from the axial skeleton—the *pectoralis major* and *latissimus dorsi* (figs. 12.3 and 12.4). The pectoralis major is the thick, fleshy muscle of the mammary region, and the latissimus dorsi is a broad muscle of the back that extends from the waist to the axilla. These muscles bear the primary responsibility for attaching the arm to the trunk and are the prime movers of the shoulder joint. The axilla (armpit) is the depression between these two muscles.

Name	Action	Skeletal Attachments	Innervation
Pectoralis Major (PECK-toe-RAY-liss)	Flexes, adducts, and medially rotates humerus, as in climbing or hugging; aids in deep inspiration	• Medial half of clavicle; lateral margin of sternum; costal cartilages 1–7; aponeurosis of external oblique • Lateral lip of intertubercular sulcus of humerus	Medial and lateral pectoral nerves
Latissimus Dorsi[4] (la-TISS-ih-mus DOR-sye)	Adducts and medially rotates humerus; extends the shoulder joint as in pulling on oars of a rowboat; produces backswing of arm in such actions as walking or bowling; with hands grasping overhead objects, pulls body forward and upward, as in climbing; produces strong downstrokes of arm as in hammering and swimming (nicknamed the "swimmer's muscle"); aids in deep inspiration, sudden expiration as in sneezing and coughing, and prolonged forceful expiration as in singing or playing a wind instrument	• Vertebrae T7–L5; lower three or four ribs; iliac crest; thoracolumbar fascia • Floor of intertubercular sulcus of humerus	Thoracodorsal nerve

Scapular Muscles. The other seven muscles of the shoulder are considered **scapular muscles** because they arise from the scapula. Four of them form the rotator cuff and are treated in the next section. The most conspicuous scapular muscle is the *deltoid,* the thick, triangular muscle that caps the shoulder. This is a commonly used site for drug injections. Its anterior, lateral, and posterior fibers act like three different muscles.

Name	Action	Skeletal Attachments	Innervation
Deltoid[5]	Anterior fibers flex and medially rotate arm; lateral fibers abduct arm; posterior fibers extend and laterally rotate arm; involved in arm swinging during such actions as walking or bowling, and in adjustment of hand height for various manual tasks	• Acromion and spine of scapula; clavicle • Deltoid tuberosity of humerus	Axillary nerve
Teres Major[6] (TERR-eez)	Extends and medially rotates humerus; contributes to arm swinging	• Inferior angle of scapula • Medial lip of intertubercular sulcus of humerus	Lower subscapular nerve
Coracobrachialis (COR-uh-co-BRAY-kee-AL-iss)	Flexes and medially rotates arm; resists deviation of arm from frontal plane during abduction	• Coracoid process of scapula • Medial aspect of humeral shaft	Musculocutaneous nerve

Apply What You Know

Since a muscle can only pull on a bone, and not push, antagonistic muscles are needed to produce opposite actions at a joint. Reconcile this fact with the observation that the deltoid muscle both flexes and extends the shoulder.

---

[4] *latissimus* = broadest; *dorsi* = of the back
[5] *deltoid* = triangular, like a Greek delta (Δ)
[6] *teres* = round; *major* = larger

TABLE 12.2 Muscles Acting on the Arm (continued)


Clavicle
Sternum
Deltoid
Pectoralis major
Triceps brachii:
Lateral head
Long head
Medial head
Coracobrachialis
Biceps brachii
Brachialis
Brachioradialis
Supraspinatus
Spine of scapula
Greater tubercle of humerus
Infraspinatus
Humerus
Teres minor
Teres major
Triceps brachii:
Lateral head
Long head
Latissimus dorsi

(a) Anterior view **(b) Posterior view**


Biceps brachii:
Long head
Short head
Subscapularis
Coracobrachialis
Brachialis

(c) Anterior view **(d) Anterior view**

Figure 12.3 **Pectoral and Brachial Muscles.** (a) Superficial muscles, anterior view. (b) Superficial muscles, posterior view (trapezius removed). (c) The biceps brachii, the superficial flexor of the elbow. (d) The brachialis, the deep flexor of the elbow, and the coracobrachialis and subscapularis, which act on the humerus.

- *What muscle serves as an antagonist of the pectoralis major?* AP|R

TABLE 12.2 Muscles Acting on the Arm (continued)


Deltoid
Pectoralis major
Biceps brachii:
Long head
Short head
Serratus anterior
External abdominal oblique

(a) Anterior view

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections


Levator scapulae
Rhomboid minor
Rhomboid major
Deltoid
Infraspinatus
Teres minor
Medial border of scapula
Teres major
Triceps brachii:
Lateral head
Long head
Latissimus dorsi

(b) Posterior view

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Figure 12.4 Pectoral and Brachial Muscles of the Cadaver.

TABLE 12.2 Muscles Acting on the Arm (continued)

The Rotator Cuff. Tendons of the remaining four scapular muscles form the **rotator cuff** (fig. 12.5). These muscles are nicknamed the "SITS muscles" for the first letters of their names—*supraspinatus, infraspinatus, teres minor,* and *subscapularis.* The first three muscles lie on the posterior side of the scapula (see fig. 12.3b). The supraspinatus and infraspinatus occupy the supraspinous and infraspinous fossae, above and below the scapular spine. The teres minor lies inferior to the infraspinatus. The subscapularis occupies the subscapular fossa on the anterior surface of the scapula, between the scapula and ribs (see fig. 12.3d). The tendons of these muscles merge with the joint capsule of the shoulder as they cross it en route to the humerus. They terminate on the proximal end of the humerus, forming a partial sleeve around it. The rotator cuff reinforces the joint capsule and holds the head of the humerus in the glenoid cavity.

Rotator cuff injuries are common in sports and recreation. The tendon of the supraspinatus, especially, is easily damaged by strenuous circumduction (as in baseball pitching and bowling), falls (as in skiing), and hard blows from the side (as when a hockey player is slammed against the boards).



Figure 12.5 **Rotator Cuff Muscles in Relation to the Scapula.** Lateral view. For posterior and anterior views of these muscles, see figure 12.3b, d.

Name	Action	Skeletal Attachments	Innervation
Supraspinatus[7] (SOO-pra-spy-NAY-tus)	Aids deltoid in abduction of arm; resists downward slippage of humeral head when arm is relaxed or when carrying weight	• Supraspinous fossa of scapula • Greater tubercle of humerus	Suprascapular nerve
Infraspinatus[8] (IN-fra-spy-NAY-tus)	Modulates action of deltoid, preventing humeral head from sliding upward; laterally rotates humerus	• Infraspinous fossa of scapula • Greater tubercle of humerus	Suprascapular nerve
Teres Minor (TERR-eez)	Modulates action of deltoid, preventing humeral head from sliding upward as arm is abducted; adducts and laterally rotates humerus	• Lateral border and adjacent posterior surface of scapula • Greater tubercle of humerus; posterior surface of joint capsule	Axillary nerve
Subscapularis[9] (SUB-SCAP-you-LERR-iss)	Modulates action of deltoid, preventing humeral head from sliding upward as arm is abducted; medially rotates humerus	• Subscapular fossa of scapula • Lesser tubercle of humerus; anterior surface of joint capsule	Upper and lower subscapular nerves

DEEPER INSIGHT 12.2

Evolution of Limb Muscles

We can get deeper insights into human muscle functions by comparing our own muscles with those of other animals. The deltoid is a strong and prominent muscle in all hominoids (apes and humans). In its role as an abductor, it raises the arm above the shoulder—an action that a four-legged animal (quadruped) such as a horse or dog cannot perform. We take advantage of this whenever we reach for something on a high shelf or reach up for a handhold while climbing a ladder or rock wall. It is vitally important to monkeys and apes for climbing trees and swinging from overhead limbs.

The latissimus dorsi is another important muscle in climbing. We use this to pull the body up, as in rock climbing or performing pull-ups, and we condition it with "lat pulldown" exercises in fitness centers. In quadrupedal mammals, the latissimus dorsi binds the humerus to the trunk and produces a powerful backward thrust of the forelimb during walking and running.

---

[7] *supra* = above; *spin* = spine of scapula
[8] *infra* = below, under; *spin* = spine of scapula
[9] *sub* = below, under

TABLE 12.3 Muscles Acting on the Forearm

The elbow and forearm are capable of four motions—flexion, extension, pronation, and supination—carried out by muscles in both the brachium and antebrachium (arm and forearm).

Muscles with Bellies in the Arm (Brachium). The principal elbow flexors are in the anterior compartment of the arm—the brachialis and biceps brachii (see fig. 12.3c, d). The *biceps brachii* appears as a large anterior bulge and commands considerable interest among bodybuilders, but the *brachialis* underlying it generates about 50% more power and is thus the prime mover of elbow flexion. The biceps is not only a flexor but also a powerful forearm supinator. It is named for its two heads: a **short head** whose tendon arises from the coracoid process of the scapula, and a **long head** whose tendon arises from the superior margin of the glenoid cavity, loops over the shoulder, and braces the humerus against the glenoid cavity (see p. 222). The two heads converge close to the elbow on a single distal tendon that inserts on the radius and on the fascia of the medial side of the upper forearm.

The *triceps brachii* is a three-headed muscle in the posterior compartment and is the prime mover of elbow extension (see fig. 12.3b).

Name	Action	Skeletal Attachments	Innervation
Brachialis (BRAY-kee-AL-iss)	Prime mover of elbow flexion	• Anterior surface of distal half of humerus • Coronoid process and tuberosity of ulna	Musculocutaneous nerve, radial nerve
Biceps Brachii[10] (BY-seps BRAY-kee-eye)	Rapid or forceful supination of forearm; synergist in elbow flexion; slight shoulder flexion; tendon of long head stabilizes shoulder by holding humeral head against glenoid cavity	• Long head—superior margin of glenoid cavity Short head—coracoid process • Tuberosity of radius; fascia of forearm	Musculocutaneous nerve
Triceps[11] **Brachii** (TRI-seps BRAY-kee-eye)	Extends elbow; long head extends and adducts humerus	• Long head—inferior margin of glenoid cavity and joint capsule Lateral head—posterior surface of proximal end of humerus Medial head—posterior surface of entire humeral shaft • Olecranon; fascia of forearm	Radial nerve

Muscles with Bellies in the Forearm (Antebrachium). Most forearm muscles act on the wrist and hand, but two of them are synergists in elbow flexion and extension, and three of them function in pronation and supination. The *brachioradialis* is the large fleshy mass of the lateral (radial) side of the forearm just distal to the elbow (see figs. 12.3a and 12.7c). It arises from the distal end of the humerus and ends on the distal end of the radius. With its radial attachment so far from the fulcrum of the elbow, it does not generate as much force as the brachialis and biceps; it is effective mainly when those muscles have already partially flexed the elbow. The *anconeus* is a weak synergist of elbow extension on the posterior side of the elbow (see fig. 12.8e). Pronation is achieved by the *pronator quadratus* (the prime mover) near the wrist and the *pronator teres* near the elbow. Supination is usually achieved by the *supinator* of the upper forearm, with the biceps brachii aiding when additional speed or power is required (fig. 12.6).

Name	Action	Skeletal Attachments	Innervation
Brachioradialis (BRAY-kee-oh-RAY-dee-AL-iss)	Flexes elbow	• Lateral supracondylar ridge of humerus • Lateral surface of radius near styloid process	Radial nerve
Anconeus[12] (an-CO-nee-us)	Extends elbow; may help to control ulnar movement during pronation	• Lateral epicondyle of humerus • Olecranon and posterior surface of ulna	Radial nerve
Pronator Quadratus[13] (PRO-nay-tur quad-RAY-tus)	Prime mover of forearm pronation; also resists separation of radius and ulna when force is applied to forearm through wrist, as in doing push-ups	• Anterior surface of distal ulna • Anterior surface of distal radius	Median nerve
Pronator Teres (PRO-nay-tur TERR-eez)	Assists pronator quadratus in pronation, but only in rapid or forceful action; weakly flexes elbow	• Humeral shaft near medial epicondyle; coronoid process of ulna • Lateral surface of radial shaft	Median nerve
Supinator (SOO-pih-NAY-tur)	Supinates forearm, as in turning a doorknob or driving a screw into wood with the right hand	• Lateral epicondyle of humerus; supinator crest and fossa of ulna just distal to radial notch; anular and radial collateral ligaments of elbow • Proximal one-third of radius	Radial nerve

---

[10] *bi* = two; *ceps* = head; *brachii* = of the arm
[11] *tri* = three; *ceps* = head
[12] *anconeus* = elbow
[13] *quadratus* = four-sided

TABLE 12.3 **Muscles Acting on the Forearm (continued)**


Lateral epicondyle
Medial epicondyle
Supinator
Pronator teres
Ulna
Radius
Pronator quadratus
Biceps brachii
Radius
Bursa
Supinator
Ulna
(b) Muscle actions in supination
(a) Supination
(c) Pronation

Figure 12.6 **Actions of the Rotator Muscles on the Forearm.** (a) Supination. (b) Cross section just distal to the elbow, showing the synergistic action of the biceps brachii and supinator. (c) Pronation.

- *What do the names of the pronator teres and pronator quadratus indicate about their shapes?*

TABLE 12.4 Muscles Acting on the Wrist and Hand

The hand is acted upon by extrinsic muscles in the forearm and intrinsic muscles in the hand itself. The bellies of the extrinsic muscles form the fleshy roundness of the upper forearm (along with the brachioradialis, table 12.3), with their tendons extending into the wrist and hand. Their actions are mainly flexion and extension of the wrist and digits, but also include radial and ulnar flexion, finger abduction and adduction, and thumb opposition. These muscles are numerous and complex, but their names often describe their location, appearance, and function.

Many of them act on the **metacarpophalangeal joints,** between the metacarpal bones of the hand and the proximal phalanges of the fingers, and the **interphalangeal joints,** between the proximal and middle or the middle and distal phalanges (or proximal–distal in the thumb, which has no middle phalanx). The metacarpophalangeal joints form the knuckles at the bases of the fingers, and the interphalangeal joints form the second and third knuckles. Some tendons cross multiple joints before ending on a middle or distal phalanx, and can flex or extend all the joints they cross.

Most tendons of the extrinsic muscles pass under a fibrous, braceletlike sheet called the **flexor retinaculum** on the anterior side of the wrist or the **extensor retinaculum** on the posterior side (see fig. 3.13, p. 64). These ligaments prevent the tendons from standing up like taut bowstrings when the muscles contract. The **carpal tunnel** is a tight space between the flexor retinaculum and carpal bones. The flexor tendons passing through the tunnel are enclosed in tendon sheaths that enable them to slide back and forth quite easily, although this region is very subject to painful inflammation—*carpal tunnel syndrome*—resulting from repetitive motion (see Deeper Insight 12.3 and fig. 12.9).

Fasciae divide the forearm muscles into anterior and posterior compartments and each compartment into superficial and deep layers (fig. 12.7). The muscles will be described in these four groups.

Anterior (Flexor) Compartment, Superficial Layer. Most muscles of the anterior compartment are wrist and finger flexors that arise from a common tendon on the humerus (fig. 12.8a, b). At the distal end, the tendon of the *palmaris longus* passes over the flexor retinaculum, whereas the other tendons pass beneath it, through the carpal tunnel. The two prominent tendons you can palpate at the wrist belong to the palmaris longus on the medial side and the *flexor carpi radialis* on the lateral side (see fig. A.19a, p. 345). The latter is an important landmark for finding the radial artery, where the pulse is usually taken. The palmaris longus is absent on one or both sides (most commonly the left) in about 14% of people. To see if you have one, flex your wrist and touch the tips of your thumb and little finger together. If present, the palmaris longus tendon will stand up prominently on the wrist.

Name	Action	Skeletal Attachments	Innervation
Flexor Carpi Radialis[14] (FLEX-ur CAR-pye RAY-dee-AL-iss)	Flexes wrist anteriorly; aids in radial flexion of wrist	• Medial epicondyle of humerus • Base of metacarpals II–III	Median nerve
Flexor Carpi Ulnaris[15] (ul-NAY-ris)	Flexes wrist anteriorly; aids in ulnar flexion of wrist	• Medial epicondyle of humerus; medial margin of olecranon; posterior surface of ulna • Pisiform; hamate; metacarpal V	Ulnar nerve
Flexor Digitorum Superficialis[16] (DIDJ-ih-TOE-rum SOO-per-FISH-ee-AY-lis)	Flexes wrist, metacarpophalangeal, and interphalangeal joints depending on action of other muscles	• Medial epicondyle of humerus; ulnar collateral ligament; coronoid process; superior half of radius • Middle phalanges II–V	Median nerve
Palmaris Longus (pal-MERR-is)	Anchors skin and fascia of palmar region; resists shearing forces when stress is applied to skin by such actions as climbing and tool use. Weakly developed and sometimes absent.	• Medial epicondyle of humerus • Flexor retinaculum, palmar aponeurosis	Median nerve

Anterior (Flexor) Compartment, Deep Layer. The following two flexors constitute the deep layer (fig. 12.8c). The *flexor digitorum profundus* flexes fingers II–V, but the thumb (pollex) has a flexor of its own—one of several muscles serving exclusively for thumb movements.

Name	Action	Skeletal Attachments	Innervation
Flexor Digitorum Profundus[17]	Flexes wrist, metacarpophalangeal, and interphalangeal joints; sole flexor of the distal interphalangeal joints	• Proximal three-quarters of ulna; coronoid process; interosseous membrane • Distal phalanges II–V	Median nerve; ulnar nerve
Flexor Pollicis[18] **Longus** (PAHL-ih-sis)	Flexes phalanges of thumb	• Radius; interosseous membrane • Distal phalanx I	Median nerve

---

[14] *carpi* = of the wrist; *radialis* = of the radius
[15] *ulnaris* = of the ulna
[16] *digitorum* = of the digits; *superficialis* = shallow, near the surface
[17] *profundus* = deep
[18] *pollicis* = of the thumb (pollex)

TABLE 12.4 Muscles Acting on the Wrist and Hand (continued)


(a)
(b)
(c)
Deltoid
Pectoralis major
Biceps brachii:
Long head
Short head
Coracobrachialis
Humerus
Latissimus dorsi tendon
Teres major
Triceps brachii:
Lateral head
Long head
(a)
Anterior
Lateral
Medial
Posterior
Biceps brachii
Brachialis
Triceps brachii:
Medial head
Long head
Lateral head
Key
Anterior (flexor) compartment, superficial
Anterior (flexor) compartment, deep
Posterior (extensor) compartment
Other muscles
(b)
Brachioradialis
Supinator
Radius
Extensor carpi radialis longus
Extensor carpi radialis brevis
Extensor digitorum
Extensor digiti minimi
Extensor carpi ulnaris
Pronator teres
Flexor carpi radialis
Palmaris longus
Flexor digitorum superficialis
Flexor pollicis longus
Flexor carpi ulnaris
Flexor digitorum profundus
Ulna
Anconeus
(c)

Figure 12.7 **Serial Cross Sections Through the Upper Limb.** Each section is taken at the correspondingly lettered level in the figure at the left and is pictured with the posterior muscle compartment facing the bottom of the page.

- *Why are the extensor pollicis longus and extensor indicis not seen in part (c)?*

TABLE 12.4 Muscles Acting on the Wrist and Hand (continued)


Anterior view
Biceps brachii
Triceps brachii
Brachialis
Common flexor tendon
Pronator teres
Aponeurosis of biceps brachii
Brachioradialis
Flexor carpi radialis
Palmaris longus
Flexor carpi ulnaris
Extensor carpi radialis longus and brevis
Flexor digitorum superficialis
Flexor retinaculum
Palmar aponeurosis
Common flexor tendon
Flexor digitorum superficialis
Flexor pollicis longus
Flexor digitorum superficialis tendons
Flexor digitorum profundus tendons
Supinator
Interosseous membrane
Flexor digitorum profundus
Flexor pollicis longus
Flexor digitorum superficialis tendons
Flexor digitorum profundus tendons

(a) Superficial flexors **(b) Intermediate flexor** **(c) Deep flexors**

Figure 12.8 **Muscles of the Forearm.** Parts (a) to (c) are anterior views of the flexor muscles. Muscles labeled in boldface are (a) superficial flexors; (b) the flexor digitorum superficialis, deep to the muscles in (a) but also classified as a superficial flexor; and (c) deep flexors. (continued)

Posterior (Extensor) Compartment, Superficial Layer. Superficial muscles of the posterior compartment are mostly wrist and finger extensors and share a single tendon arising from the humerus (fig. 12.8d). *The extensor digitorum* has four distal tendons that can easily be seen and palpated on the back of the hand when the fingers are strongly extended (see fig. A.19b, p. 345). It serves digits II through V, and the other muscles in this group each serve a single digit. From lateral to medial, these extensors are as follows.

Name	Action	Skeletal Attachments	Innervation
Extensor Carpi Radialis Longus	Extends wrist; aids in radial flexion of wrist	• Lateral supracondylar ridge of humerus • Base of metacarpal II	Radial nerve
Extensor Carpi Radialis Brevis[19] (BREV-iss)	Extends wrist; aids in radial flexion of wrist	• Lateral epicondyle of humerus • Base of metacarpal III	Radial nerve
Extensor Digitorum	Extends wrist, metacarpophalangeal, and interphalangeal joints; tends to spread fingers apart when extending metacarpophalangeal joints	• Lateral epicondyle of humerus • Dorsal surfaces of phalanges II–V	Radial nerve
Extensor Digiti Minimi[20] (DIDJ-ih-ty MIN-ih-my)	Extends wrist and all joints of little finger	• Lateral epicondyle of humerus • Proximal phalanx V	Radial nerve
Extensor Carpi Ulnaris	Extends and fixes wrist when fist is clenched or hand grips an object; aids in ulnar flexion of wrist	• Lateral epicondyle of humerus; posterior surface of ulnar shaft • Base of metacarpal V	Radial nerve

---

[19] *brevis* = short
[20] *digit* = finger; *minim* = smallest

TABLE 12.4 Muscles Acting on the Wrist and Hand (continued)


Posterior view
Triceps brachii
Anconeus
Flexor carpi ulnaris
Extensor carpi ulnaris
Extensor digiti minimi
Tendon of extensor indicis
Tendons of extensor digitorum
Brachioradialis
Extensor carpi radialis longus
Extensor carpi radialis brevis
Extensor digitorum
Abductor pollicis longus
Extensor pollicis brevis
Extensor pollicis longus
Tendons of extensor carpi radialis longus and brevis
Olecranon
Extensor pollicis longus
Extensor indicis
Anconeus
Supinator
Abductor pollicis longus
Extensor pollicis brevis

(d) Superficial extensors **(e) Deep extensors**

Figure 12.8 **Muscles of the Forearm (continued).** Parts (d) and (e) are posterior views of the extensor muscles. Muscles labeled in boldface are (d) superficial extensors and (e) deep extensors. APR

Posterior (Extensor) Compartment, Deep Layer. The deep muscles that follow serve only the thumb and index finger (fig. 12.8e). By strongly abducting and extending the thumb into a hitchhiker's position, you may see a deep dorsolateral pit at the base of the thumb, with a taut tendon on each side of it (see fig. A.19b, p. 345). This depression is called the **anatomical snuffbox** because it was once fashionable to place a pinch of snuff here and inhale it. It is bordered laterally by the tendons of the *abductor pollicis longus* and *extensor pollicis brevis,* and medially by the tendon of the *extensor pollicis longus*. These muscles from lateral to medial are as follows.

Name	Action	Skeletal Attachments	Innervation
Abductor Pollicis Longus	Abducts thumb in frontal (palmar) plane (radial abduction); extends thumb at carpometacarpal joint	• Posterior surfaces of radius and ulna; interosseous membrane • Trapezium; base of metacarpal I	Radial nerve
Extensor Pollicis Brevis	Extends metacarpal I and proximal phalanx of thumb	• Shaft of radius; interosseous membrane • Proximal phalanx I	Radial nerve
Extensor Pollicis Longus	Extends distal phalanx I; aids in extending proximal phalanx I and metacarpal I; adducts and laterally rotates thumb	• Posterior surface of ulna; interosseous membrane • Distal phalanx I	Radial nerve
Extensor Indicis (IN-dih-sis)	Extends wrist and index finger	• Posterior surface of ulna; interosseous membrane • Middle and distal phalanges of index finger (II)	Radial nerve

Apply What You Know

Why are the prime movers of finger extension and flexion located in the forearm rather than in the hand, closer to the fingers?

DEEPER INSIGHT 12.3

Carpal Tunnel Syndrome

Prolonged, repetitive motions of the wrist and fingers can cause tissues in the carpal tunnel to become inflamed, swollen, or fibrotic. Since the carpal tunnel cannot expand, swelling puts pressure on the median nerve, which passes through the carpal tunnel with the flexor tendons (fig. 12.9). This pressure causes tingling and muscular weakness in the palm and lateral side of the hand and pain that may radiate to the arm and shoulder. This condition, called *carpal tunnel syndrome,* is common among pianists, meat cutters, and others who spend long hours making repetitive wrist motions. It can also be caused by other factors that reduce the size of the carpal tunnel, including tumors, infections, and bone fractures. Carpal tunnel syndrome is treated with aspirin and other anti-inflammatory drugs, immobilization of the wrist, and sometimes surgical removal of part or all of the flexor retinaculum to relieve pressure on the nerve.


Palmaris longus tendon (cut)
Flexor carpi radialis tendon
Flexor pollicis longus tendon
Palmar carpal ligament (cut)
Radial artery
Median nerve
Trapezium
Flexor digitorum superficialis tendon
Flexor digitorum profundus tendon
Flexor carpi ulnaris tendon
Ulnar artery
Ulnar nerve
Flexor retinaculum covering carpal tunnel
Bursa
Superficial palmar arterial arch

(a) Anterior view


Anterior
Lateral
Medial
Posterior
Palmaris longus tendon
Thenar muscles
Flexor digitorum superficialis tendons
Trapezium
Flexor digitorum profundus tendons
Radial artery
Trapezoid
Scaphoid
Median nerve
Ulnar artery
Flexor retinaculum
Carpal tunnel
Hypothenar muscles
Ulnar bursa
Hamate
Capitate
Extensor tendons

(b) Cross section

Figure 12.9 **The Carpal Tunnel.** (a) Dissection of the wrist (anterior aspect) showing the tendons, nerve, and bursae that pass under the flexor retinaculum. (b) Cross section of the wrist, viewed as if from the distal end of a person's right forearm extended toward you with the palm up. Note how the flexor tendons and median nerve are confined in the tight space between the carpal bones and flexor retinaculum. That tight packing and repetitive sliding movements of the flexor tendons through the tunnel contribute to carpal tunnel syndrome.

TABLE 12.5 Intrinsic Muscles of the Hand

The intrinsic muscles of the hand assist the flexors and extensors in the forearm and make finger movements more precise. They are divided into three groups: the **thenar group** at the base of the thumb, the **hypothenar group** at the base of the little finger, and the **midpalmar group** between these (fig. 12.10).


Tendon sheath
Tendon of flexor digitorum profundus
Tendon of flexor digitorum superficialis
Lumbricals
Opponens digiti minimi
Flexor digiti minimi brevis
Abductor digiti minimi
Flexor retinaculum
Tendons of:
Flexor carpi ulnaris
Flexor digitorum superficialis
Palmaris longus
First dorsal interosseous
Adductor pollicis
Tendon of flexor pollicis longus
Flexor pollicis brevis
Abductor pollicis brevis
Opponens pollicis
Tendons of:
Abductor pollicis longus
Flexor carpi radialis
Flexor pollicis longus
Tendon of flexor digitorum superficialis
Lumbrical
Opponens digiti minimi
Flexor digiti minimi brevis
Abductor digiti minimi
Pisiform bone
Flexor digitorum superficialis
Adductor pollicis
Flexor pollicis brevis
Abductor pollicis brevis
Tendon of extensor pollicis brevis
Tendon of flexor carpi radialis

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

(a) Palmar aspect, superficial **(b) Palmar dissection, superficial**


Palmar interosseous
Opponens digiti minimi
Flexor retinaculum (cut)
Carpal tunnel
Opponens pollicis
Tendons of:
Abductor pollicis longus
Flexor carpi radialis
Flexor carpi ulnaris
Adductor pollicis
Abductor pollicis brevis
Common tendon sheath of extensor digitorum and extensor indicis
Tendons of extensor pollicis brevis and abductor pollicis longus
Tendons of extensor digitorum (cut)
Dorsal interosseous
Abductor digiti minimi
Extensor retinaculum
Tendons of:
Extensor digiti minimi
Extensor carpi ulnaris
Extensor pollicis longus
Extensor digitorum

(c) Palmar aspect, deep **(d) Dorsal aspect**

Figure 12.10 **Intrinsic Muscles of the Hand.** The boldface labels in parts (a), (c), and (d) indicate the muscles that belong to the respective layers. APR

TABLE 12.5 Intrinsic Muscles of the Hand (continued)

Thenar[21] Group. The thenar group of muscles forms the thick, fleshy mass **(thenar eminence)** at the base of the thumb, and the *adductor pollicis* forms the web between the thumb and palm. All are concerned with thumb movements. The adductor pollicis has an *oblique head* that extends from the capitate bone of the wrist to the ulnar side of the base of the thumb, and a *transverse head* that extends from metacarpal III to the same attachment as the oblique head.

Name	Action	Skeletal Attachments	Innervation
Adductor Pollicis	Draws thumb toward palm as in gripping a tool	• Capitate; bases of metacarpals II–III; anterior ligaments of wrist; tendon sheath of flexor carpi radialis • Medial surface of proximal phalanx I	Ulnar nerve
Abductor Pollicis Brevis	Abducts thumb in sagittal plane	• Mainly flexor retinaculum; also scaphoid, trapezium, and abductor pollicis longus tendon • Lateral surface of proximal phalanx I	Median nerve
Flexor Pollicis Brevis	Flexes metacarpophalangeal joint of thumb	• Trapezium; trapezoid; capitate; anterior ligaments of wrist; flexor retinaculum • Proximal phalanx I	Median nerve; ulnar nerve
Opponens Pollicis (op-PO-nenz)	Flexes metacarpal I to oppose thumb to fingertips	• Trapezium; flexor retinaculum • Metacarpal I	Median nerve
Hypothenar Group. The hypothenar group forms the fleshy mass **(hypothenar eminence)** at the base of the little finger. All of these muscles are concerned with movement of that digit.			
Abductor Digiti Minimi	Abducts little finger, as in spreading fingers apart	• Pisiform; tendon of flexor carpi ulnaris • Medial surface of proximal phalanx V	Ulnar nerve
Flexor Digiti Minimi Brevis	Flexes little finger at metacarpophalangeal joint	• Hamulus of hamate bone; flexor retinaculum • Medial surface of proximal phalanx V	Ulnar nerve
Opponens Digiti Minimi	Flexes metacarpal V at carpometacarpal joint when little finger is moved into opposition with tip of thumb; deepens palm of hand	• Hamulus of hamate bone; flexor retinaculum • Medial surface of metacarpal V	Ulnar nerve
Midpalmar Group. The midpalmar group occupies the hollow of the palm. It has 11 small muscles divided into three groups.			
Four **Dorsal Interosseous[22] Muscles** (IN-tur-OSS-ee-us)	Abduct fingers; strongly flex metacarpophalangeal joints but extend interphalangeal joints, depending on action of other muscles; important for grip strength	• Each with two heads arising from facing surfaces of adjacent metacarpals • Proximal phalanges II–IV	Ulnar nerve
Three **Palmar Interosseous Muscles**	Adduct fingers; other actions same as for dorsal interosseous muscles	• Metacarpals I, II, IV, V • Proximal phalanges II, IV, V	Ulnar nerve
Four **Lumbrical[23] Muscles** (LUM-brih-cul)	Extend interphalangeal joints; contribute to ability to pinch objects between fleshy pulp of thumb and finger, instead of these digits meeting by the edges of their nails	• Tendons of flexor digitorum profundus • Proximal phalanges II–V	Median nerve; ulnar nerve

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. Name a muscle that terminates on the scapula and plays a significant role in each of the following actions: (a) pushing a stalled car, (b) paddling a canoe, (c) squaring the shoulders in military attention, (d) lifting the shoulder to carry a heavy box on it, and (e) lowering the shoulder to grasp a suitcase handle.
2. Describe three contrasting actions of the deltoid muscle.
3. Name the four rotator cuff muscles and describe the scapular surfaces against which they lie.
4. Name the prime movers of elbow flexion and extension.
5. Identify three functions of the biceps brachii.
6. Name three extrinsic muscles and two intrinsic muscles that flex the phalanges.

---

[21] *thenar* = of the palm
[22] *inter* = between; *osse* = bones
[23] *lumbrical* = resembling an earthworm

12.2 Muscles Acting on the Hip and Lower Limb

Expected Learning Outcomes

When you have completed this section, you should be able to

a. name and locate the muscles that act on the hip, knee, ankle, and toe joints;
b. relate the actions of these muscles to the joint movements described in chapter 9; and
c. describe the attachments and innervation of each muscle.

The largest muscles are found in the lower limb. Unlike those of the upper limb, they are adapted less for precision than for the strength needed to stand, maintain balance, walk, and run. Several of them cross and act on two or more joints, such as the hip and knee. To avoid confusion in this discussion, remember that in the anatomical sense the word *leg* refers only to that part of the limb between the knee and ankle. The term *foot* includes the tarsal region (ankle), metatarsal region, and toes. Tables 12.6 through 12.9 group the muscles of the lower limb into those that act on the femur and hip joint, those that act on the leg and knee joint, extrinsic (leg) muscles that act on the foot and ankle joint, and intrinsic (foot) muscles that act on the arches and toes.

TABLE 12.6 Muscles Acting on the Hip and Thigh



Figure 12.11 **Muscles That Act on the Hip and Femur.** Anterior view. APR

Anterior Muscles of the Hip. Most muscles that act on the femur originate on the hip bone. The two principal anterior muscles are the *iliacus,* which fills most of the broad iliac fossa of the pelvis, and the *psoas major,* a thick rounded muscle that arises mainly from the lumbar vertebrae (fig. 12.11). Collectively, they are called the **iliopsoas** and share a common tendon to the femur.

Name	Action	Skeletal Attachments	Innervation
Iliacus[24] (ih-LY-uh-cus)	Flexes thigh at hip when trunk is fixed, as in stair climbing; flexes trunk at hip when thigh is fixed, as in bending forward in a chair or sitting up in bed; balances trunk during sitting	• Iliac crest and fossa; superolateral region of sacrum; anterior sacroiliac and iliolumbar ligaments • Lesser trochanter and nearby shaft of femur	Femoral nerve
Psoas[25] **Major** (SO-ass)	Same as iliacus	• Bodies and intervertebral discs of vertebrae T12–L5; transverse processes of lumbar vertebrae • Lesser trochanter and nearby shaft of femur	Anterior rami of lumbar spinal nerves

---

[24] *ili* = loin, flank

[25] *psoa* = loin

TABLE 12.6 Muscles Acting on the Hip and Thigh (continued)

<table>
<tr><td colspan="4">Lateral and Posterior Muscles of the Hip. On the lateral and posterior sides of the hip are the <i>tensor fasciae latae</i> and three gluteal muscles. The fascia lata is a fibrous sheath that encircles the thigh like a subcutaneous stocking and tightly binds its muscles. On the lateral surface, it combines with the tendons of the gluteus maximus and tensor fasciae latae to form the iliotibial tract, which extends from the iliac crest to the lateral condyle of the tibia (see figs. 12.13 and 12.14). The tensor fasciae latae tautens the iliotibial tract and braces the knee, especially when the opposite foot is lifted.
The gluteal muscles are the <i>gluteus maximus, gluteus medius,</i> and <i>gluteus minimus</i> (fig. 12.12). The gluteus maximus is the largest of these and forms most of the lean mass of the buttock. It is an extensor of the hip joint that produces the backswing of the leg in walking and provides most of the lift when you climb stairs. It generates its maximum force when the thigh is flexed at a 45° angle to the trunk. This is the advantage in starting a foot race from a crouched position. The gluteus medius is deep and lateral to the gluteus maximus. Its name refers to its size, not its position. The gluteus minimus is the smallest and deepest of the three.</td></tr>
<tr><th>Name</th><th>Action</th><th>Skeletal Attachments</th><th>Innervation</th></tr>
<tr><td>Tensor Fasciae Latae[26]
(TEN-sur FASH-ee-ee LAY-tee)</td><td>Extends knee, laterally rotates tibia, aids in abduction and medial rotation of femur; during standing, steadies pelvis on femoral head and steadies femoral condyles on tibia</td><td>• Iliac crest; anterior superior spine; deep surface of fascia lata
• Lateral condyle of tibia via iliotibial tract</td><td>Superior gluteal nerve</td></tr>
<tr><td>Gluteus Maximus[27]</td><td>Extends thigh at hip as in stair climbing (rising to next step) or running and walking (backswing of limb); abducts thigh; elevates trunk after stooping; extends waist after bending forward; prevents trunk from pitching forward during walking and running; helps stabilize femur on tibia</td><td>• Posterior gluteal line of ilium, on posterolateral surface from iliac crest to posterior superior spine; coccyx; posterior surface of lower sacrum; aponeurosis of erector spinae
• Gluteal tuberosity of femur; lateral condyle of tibia via iliotibial tract</td><td>Inferior gluteal nerve</td></tr>
<tr><td>Gluteus Medius and Gluteus Minimus</td><td>Abduct and medially rotate thigh; during walking, shift weight of trunk toward limb with foot on the ground as other foot is lifted</td><td>• Most of lateral surface of ilium between crest and acetabulum
• Greater trochanter of femur</td><td>Superior gluteal nerve</td></tr>
<tr><td colspan="4">Lateral Rotators. Inferior to the gluteus minimus and deep to the other two gluteal muscles are six muscles called the lateral rotators, named for their action on the femur (fig. 12.12). Their action is most clearly visualized when you cross your legs to rest an ankle on your knee, causing your femur to rotate and the knee to point laterally. Thus, they oppose medial rotation by the gluteus medius and minimus. Most of them also abduct or adduct the femur. The abductors are important in walking because when one lifts a foot from the ground, they shift the body weight to the other leg and prevent falling.</td></tr>
<tr><td>Gemellus[28] Superior
(jeh-MEL-us)</td><td>Laterally rotates extended thigh; abducts flexed thigh; sometimes absent</td><td>• Ischial spine
• Greater trochanter</td><td>Nerve to obturator internus</td></tr>
<tr><td>Gemellus Inferior</td><td>Same as gemellus superior</td><td>• Ischial tuberosity
• Greater trochanter</td><td>Nerve to quadratus femoris</td></tr>
<tr><td>Obturator[29] Externus
(OB-too-RAY-tur)</td><td>Not well understood; thought to laterally rotate thigh in climbing</td><td>• External surface of obturator membrane; rami of pubis and ischium
• Femur between head and greater trochanter</td><td>Obturator nerve</td></tr>
<tr><td>Obturator Internus</td><td>Not well understood; thought to laterally rotate extended thigh and abduct flexed thigh</td><td>• Ramus of ischium; inferior ramus of pubis; anteromedial surface of lesser pelvis
• Greater trochanter</td><td>Nerve to obturator internus</td></tr>
<tr><td>Piriformis[30]
(PIR-ih-FOR-mis)</td><td>Laterally rotates extended thigh; abducts flexed thigh</td><td>• Anterior surface of sacrum; gluteal surface of ilium; capsule of sacroiliac joint
• Greater trochanter</td><td>Spinal nerves L5–S2</td></tr>
<tr><td>Quadratus Femoris[31]
(quad-RAY-tus FEM-oh-ris)</td><td>Laterally rotates thigh</td><td>• Ischial tuberosity of femur
• Intertrochanteric crest</td><td>Nerve to quadratus femoris</td></tr>
<tr><td colspan="4">Medial (Adductor) Compartment of the Thigh. Fasciae divide the thigh into three compartments: the <i>anterior (extensor) compartment, posterior (flexor) compartment,</i> and <i>medial (adductor) compartment.</i> Muscles of the anterior and posterior compartments function mainly as extensors and flexors of the knee, respectively, and are treated in table 12.7. The five muscles of the medial compartment act primarily as adductors of the thigh (fig. 12.11), but some of them cross both the hip and knee joints and have additional actions as follows.</td></tr>
<tr><td>Adductor Brevis</td><td>Adducts thigh</td><td>• Body and inferior ramus of pubis
• Linea aspera and spiral line of femur</td><td>Obturator nerve</td></tr>
<tr><td>Adductor Longus</td><td>Adducts and medially rotates thigh; flexes thigh at hip</td><td>• Body and inferior ramus of pubis
• Linea aspera of femur</td><td>Obturator nerve</td></tr>
</table>

---

[26] *fasc* = band; *lat* = broad

[27] *glut* = buttock; *maxim* = largest

[28] *gemellus* = twin

[29] *obtur* = to close, stop up

[30] *piri* = pear; *form* = shaped

[31] *quadrat* = four-sided; *femoris* = of the thigh or femur


Iliac crest
Gluteus medius
Sacrum
Gluteus maximus
Coccyx
Gracilis
Iliotibial tract
Hamstring group:
Biceps femoris
Long head
Short head
Semitendinosus
Semimembranosus
Popliteal fossa
Gluteus minimus
Lateral rotators:
Piriformis
Gemellus superior
Obturator internus
Obturator externus
Gemellus inferior
Quadratus femoris
Ischial tuberosity
Adductor magnus
Gracilis
Vastus lateralis
Gastrocnemius:
Medial head
Lateral head

Figure 12.12 **Posterior Gluteal and Thigh Muscles.** The left side shows the superficial muscles. On the right, the gluteus medius and maximus are removed to show the deeper gluteus minimus, lateral rotator group, and hamstring attachments.

- *Describe two everyday movements of the body that employ the power of the gluteus maximus.* APR

Name	Action	Skeletal Attachments	Innervation
Adductor Magnus	Adducts and medially rotates thigh; extends thigh at hip	• Inferior ramus of pubis; ramus and tuberosity of ischium • Linea aspera, gluteal tuberosity, and medial supracondylar line of femur	Obturator nerve; tibial nerve
Gracilis[32] (GRASS-ih-lis)	Flexes and medially rotates tibia at knee	• Body and inferior ramus of pubis; ramus of ischium • Medial surface of tibia just below condyle	Obturator nerve
Pectineus[33] (pec-TIN-ee-us)	Flexes and adducts thigh	• Superior ramus of pubis • Spiral line of femur	Femoral nerve

---

[32] *gracil* = slender
[33] *pectin* = comb

TABLE 12.7 Muscles Acting on the Knee and Leg

The following muscles form most of the mass of the thigh and produce their most obvious actions on the knee joint. Some of them, however, cross both the hip and knee and produce actions at both, moving the femur, tibia, and fibula.

Anterior (Extensor) Compartment of the Thigh. The anterior compartment of the thigh contains the large *quadriceps femoris muscle,* the prime mover of knee extension and the most powerful muscle of the body (figs. 12.13 and 12.14; see also fig. 12.19). As the name implies, it has four heads: the *rectus femoris, vastus lateralis, vastus medialis,* and *vastus intermedius*. All four converge on a single **quadriceps (patellar) tendon,** which extends to the patella, then continues as the **patellar ligament** and inserts on the tibial tuberosity. (Remember that a tendon usually extends from muscle to bone, and a ligament from bone to bone.) The patellar ligament is struck with a rubber reflex hammer to test the knee-jerk reflex. The quadriceps extends the knee when you stand up, take a step, or kick a ball. One head, the rectus femoris, contributes to running by acting with the iliopsoas to flex the hip in each airborne phase of the leg's cycle of motion. It also flexes the hip in such actions as high kicks, stair climbing, or simply in drawing the leg forward during a stride.

Crossing the quadriceps from the lateral side of the hip to the medial side of the knee is the narrow, straplike *sartorius,* the longest muscle of the body. It flexes the hip and knee joints and laterally rotates the thigh, as in crossing the legs. It is colloquially called the "tailor's muscle," after the cross-legged posture of a tailor supporting his work on the raised knee.



Figure 12.13 **Anterior Superficial Thigh Muscles of the Cadaver.** Right limb.

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Name	Action	Skeletal Attachments	Innervation
Quadriceps Femoris (QUAD-rih-seps FEM-oh-ris)	Extends the knee, as in kicking a ball and rising from a chair, in addition to actions of individual heads noted below	• Varies; see individual heads below • Patella; tibial tuberosity; lateral and medial condyles of tibia	Femoral nerve
Rectus Femoris	Extends knee; flexes thigh at hip; flexes trunk on hip if thigh is fixed	• Ilium at anterior inferior spine and superior margin of acetabulum; capsule of hip joint • See quadriceps femoris above	Femoral nerve
Vastus[34] Lateralis	Extends knee; retains patella in groove on femur during knee movements	• Femur at greater trochanter, intertrochanteric line, gluteal tuberosity, and linea aspera • See quadriceps femoris above	Femoral nerve
Vastus Medialis	Same as vastus lateralis	• Femur at intertrochanteric line, spiral line, linea aspera, and medial supracondylar line • See quadriceps femoris above	Femoral nerve
Vastus Intermedius	Extends knee	• Anterior and lateral surfaces of femoral shaft • See quadriceps femoris above	Femoral nerve
Sartorius[35]	Aids in knee and hip flexion, as in sitting or climbing; abducts and laterally rotates thigh	• On and near anterior superior spine of ilium • Medial surface of proximal end of tibia	Femoral nerve

---

[34] *vastus* = large, extensive
[35] *sartor* = tailor

TABLE 12.7 Muscles Acting on the Knee and Leg (continued)


Iliac crest
Iliopsoas:
Iliacus
Psoas major
L5
Anterior superior iliac spine
Tensor fasciae latae
Medial compartment:
Adductor magnus
Pectineus
Adductor brevis
Adductor longus
Gracilis
Iliotibial tract
Anterior compartment:
Sartorius
Quadriceps femoris:
Vastus intermedius
Rectus femoris
Vastus lateralis
Vastus medialis
Quadriceps femoris tendon
Patella
Patellar ligament

(a) Superficial **(b) Deep**

Figure 12.14 **Anterior Muscles of the Thigh.** (a) Superficial muscles. (b) Rectus femoris and other muscles removed to expose the other three heads of the quadriceps femoris.

TABLE 12.7 **Muscles Acting on the Knee and Leg (continued)**

Posterior (Flexor) Compartment of the Thigh. The posterior compartment contains three muscles colloquially known as the **hamstring muscles;** from lateral to medial, they are the *biceps femoris, semitendinosus,* and *semimembranosus* (fig. 12.12). The pit at the back of the knee, known anatomically as the *popliteal fossa,* is colloquially called the *ham*. The tendons of these muscles can be felt as prominent cords on both sides of the pit—the biceps tendon on the lateral side and the semimembranosus and semitendinosus tendons on the medial side. When wolves attack large prey, they often attempt to sever the hamstring tendons, because this renders the prey helpless. The hamstrings flex the knee, and aided by the gluteus maximus, they extend the hip during walking and running. The semitendinosus is named for its unusually long tendon. This muscle also is usually bisected by a transverse or oblique tendinous band. The semimembranosus is named for the flat shape of its superior attachment.

Name	Action	Skeletal Attachments	Innervation
Biceps Femoris	Flexes knee; extends hip; elevates trunk from stooping posture; laterally rotates tibia on femur when knee is flexed; laterally rotates femur when hip is extended; counteracts forward bending at hips	• Long head—ischial tuberosity Short head—linea aspera and lateral supracondylar line of femur • Head of fibula	Tibial nerve; common fibular nerve
Semitendinosus[36] (SEM-ee-TEN-din-OH-sus)	Flexes knee; medially rotates tibia on femur when knee is flexed; medially rotates femur when hip is extended; counteracts forward bending at hips	• Ischial tuberosity • Medial surface of upper tibia	Tibial nerve
Semimembranosus[37] (SEM-ee-MEM-bra-NO-sus)	Same as semitendinosus	• Ischial tuberosity • Medial condyle and nearby margin of tibia; intercondylar line and lateral condyle of femur; ligament of popliteal region	Tibial nerve

Posterior Compartment of the Leg. Most muscles in the posterior compartment of the leg act on the ankle and foot and are reviewed in table 12.8, but the popliteus acts on the knee (see fig. 12.17b).

Name	Action	Skeletal Attachments	Innervation
Popliteus[38] (pop-LIT-ee-us)	Rotates tibia medially on femur if femur is fixed (as in sitting), or rotates femur laterally on tibia if tibia is fixed (as in standing); unlocks knee to allow flexion; may prevent forward dislocation of femur during crouching	• Lateral condyle of femur; lateral meniscus and joint capsule • Posterior surface of upper tibia	Tibial nerve

---

[36] *semi* = half; *tendinosus* = tendinous
[37] *semi* = half; *membranosus* = membranous
[38] *poplit* = ham (pit) of the knee

DEEPER INSIGHT 12.4

Intramuscular Injections

Muscles with thick bellies are commonly used for intramuscular (I.M.) drug injections. Since drugs injected into these muscles are absorbed into the bloodstream gradually, it is safe to administer relatively large doses (up to 5 mL) that could be dangerous or even fatal if injected directly into the bloodstream. I.M. injections also cause less tissue irritation than subcutaneous injections.

Knowledge of subsurface anatomy is necessary to avoid damaging nerves or accidentally injecting a drug into a blood vessel. Anatomical knowledge also enables a clinician to position a patient so that the muscle is relaxed, making the injection less painful.

Amounts up to 2 mL are commonly injected into the deltoid muscle about two finger widths below the acromion. A misplaced injection into the deltoid can injure the axillary nerve and cause atrophy of the muscle. Drug doses over 2 mL are commonly injected into the gluteus medius, in the superolateral quadrant of the gluteal area, at a safe distance from the sciatic nerve and major gluteal blood vessels. Injections are often given to infants and young children in the vastus lateralis of the thigh, because their deltoid and gluteal muscles are not well developed.

DEEPER INSIGHT 12.5

Hamstring Injuries

Hamstring injuries are common among sprinters, soccer players, and other athletes who depend on quick extension of the knee to kick or jump forcefully. Rapid knee extension stretches the hamstrings and often tears the proximal tendons where they originate on the ischial tuberosity. These muscle strains are excruciatingly painful. Hamstring injuries often result from failure to warm up adequately before competition or practice.

TABLE 12.8 Muscles Acting on the Foot

The fleshy mass of the leg is formed by a group of **crural muscles,** which act on the foot (fig. 12.15). These muscles are tightly bound by fasciae that compress them and aid in the return of blood from the legs. The fasciae separate the crural muscles into anterior, lateral, and posterior compartments (see fig. 12.19b).

Anterior (Extensor) Compartment of the Leg. Muscles of the anterior compartment dorsiflex the ankle and prevent the toes from scuffing the ground during walking. From lateral to medial, these muscles are the *fibularis tertius, extensor digitorum longus* (extensor of toes II–V), *extensor hallucis longus* (extensor of the great toe), and *tibialis anterior*. Their tendons are held tightly against the ankle and kept from bowing by two **extensor retinacula** similar to the one at the wrist (fig. 12.16).

Name	Action	Skeletal Attachments	Innervation
Fibularis (Peroneus[39]) Tertius[40] (FIB-you-LERR-iss TUR-she-us)	Dorsiflexes and everts foot during walking; helps toes clear the ground during forward swing of leg	• Medial surface of lower one-third of fibula; interosseous membrane • Metatarsal V	Deep fibular (peroneal) nerve
Extensor Digitorum Longus (DIDJ-ih-TOE-rum)	Extends toes; dorsiflexes foot; tautens plantar aponeurosis	• Lateral condyle of tibia; shaft of fibula; interosseous membrane • Middle and distal phalanges II–V	Deep fibular (peroneal) nerve
Extensor Hallucis[41] Longus (ha-LOO-sis)	Extends great toe; dorsiflexes foot	• Anterior surface of middle of fibula; interosseous membrane • Distal phalanx I	Deep fibular (peroneal) nerve
Tibialis[42] Anterior (TIB-ee-AY-lis)	Dorsiflexes and inverts foot; resists backward tipping of body (as when standing on a moving boat deck); helps support medial longitudinal arch of foot	• Lateral condyle and lateral margin of proximal half of tibia; interosseous membrane • Medial cuneiform; metatarsal I	Deep fibular (peroneal) nerve

Posterior (Flexor) Compartment of the Leg, Superficial Group. The posterior compartment has superficial and deep muscle groups. The three muscles of the superficial group are plantar flexors: the *gastrocnemius, soleus,* and *plantaris* (fig. 12.17). The first two of these, collectively known as the **triceps surae,**[43] converge on the calcaneus by way of the **calcaneal (Achilles) tendon.** This is the strongest tendon of the body but is nevertheless a common site of sports injuries resulting from sudden stress. The plantaris, a weak synergist of the triceps surae, is a relatively unimportant muscle and is absent from many people; it is not tabulated here. Surgeons often use the plantaris tendon for tendon grafts needed in other parts of the body.

Name	Action	Skeletal Attachments	Innervation
Gastrocnemius[44] (GAS-trock-NEE-me-us)	Plantar flexes foot; flexes knee; active in walking, running, and jumping	• Condyles and popliteal surface of femur; lateral supracondylar line; capsule of knee joint • Calcaneus	Tibial nerve
Soleus[45] (SO-lee-us)	Plantar flexes foot; steadies leg on ankle during standing	• Posterior surface of head and proximal one-fourth of fibula; middle one-third of tibia; interosseous membrane • Calcaneus	Tibial nerve

---

[39] *perone* = pinlike (fibula)
[40] *fibularis* = of the fibula; *tert* = third
[41] *hallucis* = of the great toe (hallux)
[42] *tibialis* = of the tibia
[43] *sura* = calf of leg
[44] *gastro* = belly; *cnem* = leg
[45] Named for its resemblance to a flatfish (sole)

TABLE 12.8 **Muscles Acting on the Foot (continued)**


Patella
Head of fibula
Gastrocnemius (lateral head)
Soleus
Fibularis longus
Tibialis anterior
Tibia
Extensor digitorum longus
Fibularis brevis
Extensor hallucis longus tendon
Extensor retinaculum
Fibularis tertius
Calcaneal tendon
Extensor hallucis brevis
Lateral malleolus
Extensor digitorum brevis
Fibularis tertius tendon
Extensor digitorum longus tendons
Extensor digitorum brevis
Head of 5th metatarsal

(a) Lateral view **(b) Anterior view**

© McGraw-Hill Education/Photo and Dissection by Christine Eckel

© McGraw-Hill Education/Photo and Dissection by Christine Eckel

Figure 12.15 **Superficial Muscles of the Right Leg of the Cadaver.** APR

Apply What You Know

Not everyone has the same muscles. From the information provided in this chapter, identify two muscles that are lacking in some people.

TABLE 12.8 Muscles Acting on the Foot (continued)


Patella
Patellar ligament
Fibularis longus
Fibularis brevis
Extensor digitorum longus
Extensor retinacula
Tibia
Gastrocnemius
Soleus
Tibialis anterior
Tibialis anterior
Extensor hallucis brevis
Extensor digitorum brevis
Extensor hallucis longus
Fibularis tertius
Extensor digitorum longus
(a)
(b)
(c)
(d)

Figure 12.16 **Muscles of the Leg, Anterior Compartment.** Boldface labels identify muscles belonging to the anterior compartment. (a) Superficial anterior view of the leg. Some muscles of the posterior and lateral compartments are also partially visible. (b–d) Individual muscles of the anterior compartment of the leg and superior aspect of the foot.

- *Palpate the hard anterior surface of your own tibia at midshaft, then continue medially until you feel muscle. What muscle is that?* AP|R

TABLE 12.8 Muscles Acting on the Foot (continued)


Gastrocnemius:
Medial head
Lateral head
Tendon of gastrocnemius
Calcaneal tendon
Plantaris
Popliteus
Tendon of plantaris
Flexor digitorum longus
Calcaneus
Heads of gastrocnemius (cut)
Fibularis longus
Soleus
Gastrocnemius (cut)
Fibularis longus
Fibularis brevis
Flexor hallucis longus
(a)
(b)

Figure 12.17 **Superficial Muscles of the Leg, Posterior Compartment.** (a) The gastrocnemius. (b) The soleus, deep to the gastrocnemius and sharing the calcaneal tendon with it. The gastrocnemius and soleus are collectively called the triceps surae. APR

TABLE 12.8 **Muscles Acting on the Foot (continued)**


Plantaris (cut)
Gastrocnemius (cut)
Popliteus
Soleus (cut)
Fibula
Tibialis posterior
Fibularis longus
Flexor digitorum longus
Flexor hallucis longus
Fibularis brevis
Calcaneal tendon (cut)
Calcaneus
(a)
Tibialis posterior
(b)
Flexor digitorum longus
(c)
Popliteus
Flexor hallucis longus
Plantar surface of the foot
(d)

Figure 12.18 **Deep Muscles of the Leg, Posterior and Lateral Compartments.** (a) Muscles deep to the soleus. (b–d) Exposure of some individual deep muscles with the foot plantar flexed (sole facing viewer). APR

TABLE 12.8 Muscles Acting on the Foot (continued)

Posterior (Flexor) Compartment of the Leg, Deep Group. There are four muscles in the deep group (fig. 12.18). The *flexor digitorum longus, flexor hallucis longus,* and *tibialis posterior* are plantar flexors. The fourth muscle, the *popliteus,* was described in table 12.7 because it acts on the knee rather than on the foot.

Name	Action	Skeletal Attachments	Innervation
Flexor Digitorum Longus	Flexes phalanges of digits II–V as foot is raised from ground; stabilizes metatarsal heads and keeps distal pads of toes in contact with ground in toe-off and tiptoe movements	• Posterior surface of tibial shaft • Distal phalanges II–V	Tibial nerve
Flexor Hallucis Longus	Same actions as flexor digitorum longus, but for great toe (digit I)	• Inferior two-thirds of fibula and interosseous membrane • Distal phalanx I	Tibial nerve
Tibialis Posterior	Inverts foot; may assist in strong plantar flexion or control pronation of foot during walking	• Posterior surface of proximal half of tibia, fibula, and interosseous membrane • Navicular, medial cuneiform, metatarsals II–IV	Tibial nerve
Lateral (Fibular) Compartment of the Leg. The lateral compartment includes the *fibularis brevis* and *fibularis longus* (figs. 12.15a, 12.16a, and 12.19b). They plantar flex and evert the foot. Plantar flexion is important not only in standing on tiptoes but in providing lift and forward thrust each time you take a step.			
Fibularis (Peroneus) Brevis	Maintains concavity of sole during toe-off and tiptoeing; may evert foot and limit inversion and help steady leg on foot	• Lateral surface of distal two-thirds of fibula • Base of metatarsal V	Superficial fibular (peroneal) nerve
Fibularis (Peroneus) Longus	Maintains concavity of sole during toe-off and tiptoeing; everts and plantar flexes foot	• Head and lateral surface of proximal two-thirds of fibula • Medial cuneiform; metatarsal I	Superficial fibular (peroneal) nerve


Key a
Anterior (extensor) compartment
Medial (adductor) compartment
Posterior (flexor) compartment (hamstrings)
(a)
(b)
Posterior
Lateral
Medial
Anterior
Key b
Anterior (extensor) compartment
Lateral (fibular) compartment
Posterior (flexor) compartment, superficial
Posterior (flexor) compartment, deep
Biceps femoris:
Long head
Short head
Femur
Vastus lateralis
Vastus intermedius
Rectus femoris
(a)
Semitendinosus
Semimembranosus
Adductor magnus
Gracilis
Adductor brevis
Adductor longus
Sartorius
Vastus medialis
Gastrocnemius (lateral head)
Fibula
Fibularis longus
Fibularis brevis
Extensor hallucis longus
Extensor digitorum longus
(b)
Gastrocnemius (medial head)
Soleus
Flexor hallucis longus
Flexor digitorum longus
Tibialis posterior
Tibia
Tibialis anterior

Figure 12.19 **Serial Cross Sections Through the Lower Limb.** Each section is taken at the correspondingly lettered level in the figure at the left.

TABLE 12.9 Intrinsic Muscles of the Foot

The intrinsic muscles of the foot help to support the arches and act on the toes in ways that aid locomotion. Several of them are similar in name and location to the intrinsic muscles of the hand.

Dorsal Aspect of Foot. Only one of the intrinsic muscles, the *extensor digitorum brevis,* is on the dorsal (superior) side of the foot (see fig. 12.16b). The medial slip of this muscle, serving the great toe, is sometimes called the *extensor hallucis brevis*.

Name	Action	Skeletal Attachments	Innervation
Extensor Digitorum Brevis	Extends proximal phalanx I and all phalanges of digits II–IV	• Calcaneus; inferior extensor retinaculum of ankle • Proximal phalanx I; tendons of extensor digitorum longus to middle and distal phalanges II–IV	Deep fibular (peroneal) nerve

Ventral Layer 1 (Most Superficial). All remaining intrinsic muscles are on the ventral (inferior) aspect of the foot or between the metatarsal bones. They are grouped in four layers (fig. 12.20). Dissecting into the foot from the plantar surface, one first encounters a tough fibrous sheet, the **plantar aponeurosis,** between the skin and muscles. It diverges like a fan from the calcaneus to the bases of all the toes. Several ventral muscles arise from the aponeurosis, including the stout *flexor digitorum brevis* on the midline of the foot, with its four tendons that supply all digits except the hallux, and two muscles that flank it—the *abductor digiti minimi laterally* and the *abductor hallucis* medially.

Flexor Digitorum Brevis	Flexes digits II–IV; supports arches of foot	• Calcaneus; plantar aponeurosis • Middle phalanges II–V	Medial plantar nerve
Abductor Digiti Minimi[46]	Abducts and flexes little toe; supports arches of foot	• Calcaneus; plantar aponeurosis • Proximal phalanx V	Lateral plantar nerve
Abductor Hallucis	Abducts great toe; supports arches of foot	• Calcaneus; plantar aponeurosis; flexor retinaculum • Proximal phalanx I	Medial plantar nerve

Ventral Layer 2. The next deeper layer consists of the thick *quadratus plantae* in the middle of the foot and the four *lumbrical muscles* located between the metatarsals (fig. 12.20b).

Quadratus Plantae[47] (quad-RAY-tus PLAN-tee)	Flexes phalanges of digits II–V as foot is raised from ground; stabilizes metatarsal heads and keeps distal pads of toes in contact with ground in toe-off and tiptoe movements (same as flexor digitorum longus); flexion of digits II–V and associated locomotor functions	• Two heads on the medial and lateral sides of calcaneus • Distal phalanges II–V via flexor digitorum longus tendons	Lateral plantar nerve
Four **Lumbrical Muscles** (LUM-brih-cul)	Flex toes II–V	• Tendon of flexor digitorum longus • Proximal phalanges II–V	Lateral and medial plantar nerves

Ventral Layer 3. The muscles of this layer serve only the great and little toes (fig. 12.20c). They are the *flexor digiti minimi brevis, flexor hallucis brevis,* and *adductor hallucis.* The adductor hallucis has an *oblique head* that extends diagonally from the midplantar region to the base of the great toe, and a *transverse head* that passes across the bases of digits II–IV and meets the long head at the base of the great toe.

Flexor Digiti Minimi Brevis	Flexes little toe	• Metatarsal V; sheath of fibularis longus • Proximal phalanx V	Lateral plantar nerve
Flexor Hallucis Brevis	Flexes great toe	• Cuboid; lateral cuneiform; tibialis posterior tendon • Proximal phalanx I	Medial plantar nerve
Adductor Hallucis	Adducts great toe	• Metatarsals II–IV; fibularis longus tendon; ligaments at bases of digits III–V • Proximal phalanx I	Lateral plantar nerve

Ventral Layer 4 (Deepest). This layer consists only of the small interosseous muscles located between the metatarsal bones—four dorsal and three plantar (fig. 12.20d, e). Each *dorsal interosseous muscle* is bipennate and originates on two adjacent metatarsals. The *plantar interosseous muscles* are unipennate and originate on only one metatarsal each.

Four **Dorsal Interosseous Muscles**	Abduct toes II–IV	• Each with two heads arising from facing surfaces of two adjacent metatarsals • Proximal phalanges II–IV	Lateral plantar nerve
Three **Plantar Interosseous Muscles**	Adduct toes III–V	• Medial aspect of metatarsals III–V • Proximal phalanges III–V	Lateral plantar nerve

---

[46] *digit* = toe; *minim* = smallest

[47] *quadrat* = four-sided; *plantae* = of the plantar region

TABLE 12.9 Intrinsic Muscles of the Foot (continued)


Flexor digiti minimi brevis
Abductor digiti minimi
Abductor hallucis
Flexor digitorum brevis
Plantar aponeurosis (cut)
Calcaneus
Lumbricals
Flexor hallucis longus tendon
Flexor digitorum longus tendon
Abductor hallucis (cut)
Quadratus plantae
Flexor digitorum brevis (cut)

(a) Layer 1, plantar view

(b) Layer 2, plantar view


Adductor hallucis
Flexor digiti minimi brevis
Flexor hallucis brevis
Flexor hallucis longus tendon (cut)
Abductor hallucis (cut)
Quadratus plantae (cut)
Flexor digitorum longus tendon (cut)
Plantar interosseous
Dorsal interosseous

(c) Layer 3, plantar view

(d) Layer 4, plantar view

(e) Layer 4, superior view

Figure 12.20 **Intrinsic Muscles of the Foot.** (a–d) First through fourth layers, respectively, in inferior (plantar) views. (e) Fourth layer, superior view. The muscles belonging to each layer are shown in color and with boldface labels. APR

Before You Go On

Answer the following questions to test your understanding of the preceding section:

7. In the middle of a stride, you have one foot on the ground and you are about to swing the other leg forward. What muscles produce the movements of that leg?
8. Name the muscles that cross both the hip and knee joints and produce actions at both.
9. List the major actions of the muscles of the anterior, medial, and posterior compartments of the thigh.
10. Describe the role of plantar flexion and dorsiflexion in walking. What muscles produce these actions?

12.3 Muscle Injuries

Expected Learning Outcomes

When you have completed this section, you should be able to

a. explain how to reduce the risk of muscle injuries; and
b. define several types of muscle injuries often incurred in sports and recreation.

Although the muscular system suffers fewer diseases than most organ systems, it is particularly vulnerable to injuries resulting from sudden and intense stress placed on muscles and tendons. Each year, thousands of athletes from high school to professional level sustain some type of muscle injury, as do increasing numbers of people who have taken up running and other forms of physical conditioning. Overzealous exertion without proper preparation and warm-up is frequently the cause. Some of the most common athletic injuries are briefly described in table 12.10. (See table 10.5, p. 260, for more general disorders of the muscular system.)

Most athletic injuries can be prevented by proper conditioning. A person who suddenly takes up vigorous exercise may not have sufficient muscle and bone mass to withstand the stresses such exercise entails. These must be developed gradually. Stretching exercises keep ligaments and joint capsules supple and therefore reduce injuries. Warm-up exercises promote more efficient and less injurious musculoskeletal function in several ways. Most of all, moderation is important, as most injuries simply result from overuse of the muscles. “No pain, no gain” is a dangerous misconception.

Muscular injuries can be treated initially with “RICE”: **R**est to prevent further injury and allow repair to occur; **I**ce to reduce swelling; **C**ompression with an elastic bandage to prevent fluid accumulation and swelling; and **E**levation of an injured limb to promote drainage of blood from the affected area and limit further swelling. If these measures are not enough, anti-inflammatory drugs such as hydrocortisone and aspirin may be employed.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

11. Explain why stretching exercises may reduce the incidence of muscle injuries.
12. Explain the reason for each of the four treatments in the RICE approach to muscle injuries.

TABLE 12.10	Muscle Injuries
Baseball finger	Tears in the extensor tendons of the fingers resulting from the impact of a baseball with the extended fingertip
Blocker's arm	Abnormal calcification in the lateral margin of the forearm as a result of repeated impact such as occurs in football
Pitcher's arm	Inflammation at the attachments of the wrist flexors resulting from hard wrist flexion in releasing a baseball
Pulled groin	Strain in the adductor muscles of the thigh; common in gymnasts and dancers who perform splits and high kicks
Pulled hamstrings	Strained hamstring muscles or a partial tear in the tendinous attachment, often with a hematoma (blood clot) in the fascia lata; frequently caused by repetitive kicking (as in football and soccer) or long, hard running
Rider's bones	Calcification in the tendons of the thigh adductors; results from prolonged abduction of the thighs when riding horses
Shinsplints	General term for several kinds of injury with pain in the crural region—tendinitis of the tibialis posterior, inflammation of the tibial periosteum, and anterior compartment syndrome. May result from unaccustomed jogging, walk-a-thons, walking on snowshoes, or any vigorous activity of the legs after a period of inactivity.
Tennis elbow	Inflammation at the attachment of the extensor carpi muscles to the lateral epicondyle of the humerus. Can result from any activity that requires rotary movements of the forearm and a firm grip of the hand, such as using a screwdriver or when extensor carpi muscles are repeatedly tensed during backhand tennis strokes and then strained by sudden impact with the tennis ball.
Tennis leg	Partial tear in the lateral attachments of the gastrocnemius to the distal femur; results from repeated strains put on the muscle while supporting the body weight on the toes

Disorders Described Elsewhere

Back injuries	286	Hamstring injuries	316
Carpal tunnel syndrome	307	Hernias	289
Compartment syndrome	294	Rotator cuff injury	300

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

General

1. For all muscles named in this study guide, and to the extent specified by your course or instructor, an ability to locate the muscle on a model, photograph, diagram, or dissection; to palpate the muscle or its tendons on the living body; and to state its bone attachments, innervation, and actions

12.1 Muscles Acting on the Shoulder and Upper Limb (p. 294)

1. Muscle compartments and the connective tissue sheets that separate them
2. Two anterior muscles that act on the pectoral girdle—the *pectoralis minor* and *serratus anterior* (table 12.1)
3. Four posterior muscles that act on the pectoral girdle—the *trapezius, levator scapulae, rhomboid minor,* and *rhomboid major* (table 12.1)
4. The four "SITS muscles" of the rotator cuff—the *supraspinatus, infraspinatus, teres minor,* and *subscapularis* (table 12.2)—and the vulnerability of the rotator cuff to injuries
5. Five additional muscles that, like the rotator cuff, also cross the shoulder joint and act on the humerus—the *pectoralis major, latissimus dorsi, deltoid, teres major,* and *coracobrachialis* (table 12.2)
6. Muscles of the arm that act on the elbow joint—the *brachialis, biceps brachii,* and *triceps brachii* (table 12.3)—including the individual names and courses of the two heads of the biceps and three heads of the triceps
7. Muscles of the forearm that produce forearm movements—the *brachioradialis, anconeus, pronator quadratus, pronator teres,* and *supinator* (table 12.3)
8. Superficial muscles of the anterior compartment of the forearm that act on the wrist and hand—the *flexor carpi radialis, flexor carpi ulnaris, flexor digitorum superficialis,* and *palmaris longus* (table 12.3)
9. Deep muscles of the anterior compartment of the forearm—the *flexor digitorum profundus* and *flexor pollicis longus*
10. The relationship of anterior compartment muscles to the flexor retinaculum and carpal tunnel, and the pathology of carpal tunnel syndrome
11. Superficial muscles of the posterior compartment of the forearm—the *extensor carpi radialis longus, extensor carpi radialis brevis, extensor digitorum, extensor digiti minimi,* and *extensor carpi ulnaris*
12. Deep muscles of the posterior compartment of the forearm—the *abductor pollicis longus, extensor pollicis brevis, extensor pollicis longus,* and *extensor indicis*
13. The general role of the intrinsic muscles of the hand; the three major groups into which they can be classified; and the locations of the thenar and hypothenar eminences (table 12.5)
14. The thenar group of hand muscles—the *adductor pollicis, abductor pollicis brevis, flexor pollicis brevis,* and *opponens pollicis* (table 12.5)
15. The hypothenar group of hand muscles—the *abductor digiti minimi, flexor digiti minimi brevis,* and *opponens digiti minimi* (table 12.5)
16. The midpalmar group of hand muscles—four *dorsal interosseous muscles;* three *palmar interosseous muscles;* and four *lumbrical muscles*

12.2 Muscles Acting on the Hip and Lower Limb (p. 310)

1. The *iliopsoas* of the anterior pelvic region, and the two muscles of the iliopsoas group—the *iliacus* and *psoas major* (table 12.6)
2. The three gluteal muscles—*gluteus maximus, gluteus medius,* and *gluteus minimus* (table 12.6)
3. The *tensor fasciae latae* of the hip and its relationship to the fibrous fascia lata and iliotibial tract of the lateral thigh (table 12.6)
4. The deep lateral rotators of the hip—the *gemellus superior, gemellus inferior, obturator externus, obturator internus, piriformis,* and *quadratus femoris* (table 12.6)
5. Locations of the medial (adductor) compartment, anterior (extensor) compartment, and posterior (flexor) compartment of the thigh
6. Muscles of the medial compartment of the thigh—the *adductor brevis, adductor longus, adductor magnus, gracilis,* and *pectineus* (table 12.6)
7. Muscles of the anterior compartment of the thigh—the *sartorius* and the four heads of the *quadriceps femoris: rectus femoris, vastus lateralis, vastus medialis,* and *vastus intermedius*—and the course of the quadriceps tendon and its extension, the patellar ligament (table 12.7)
8. The hamstring muscles of the posterior compartment of the thigh—the semitendinosus, semimembranosus, and *biceps femoris*—and the nearby popliteus (table 12.7)
9. Locations of the anterior, posterior, and lateral compartments of the leg (table 12.8)
10. Anterior compartment muscles of the leg—the *fibularis tertius, extensor digitorum longus, extensor hallucis longus,* and *tibialis anterior* (table 12.8)
11. Superficial posterior compartment muscles of the leg—the *gastrocnemius* and *soleus*—and their relationship to the prominent calcaneal (Achilles) tendon (table 12.8)
12. Deep posterior compartment muscles of the leg—the *flexor digitorum longus, flexor hallucis longus,* and *tibialis posterior* (table 12.8)
13. Lateral compartment muscles of the leg—the *fibularis brevis* and *fibularis longus* (table 12.8)
14. Intrinsic muscles of the foot, their general functions, and the one muscle of the superior side—the *extensor digitorum brevis* (table 12.9)
15. The inferior intrinsic muscles of the foot and their layered arrangement—the *flexor digitorum brevis, abductor digiti minimi,* and *abductor hallucis* of layer 1 (the most superficial layer); the *quadratus plantae* and four *lumbrical muscles* of layer 2; the *adductor hallucis, flexor digiti minimi brevis,* and *flexor hallucis brevis* of layer 3; and the four *dorsal interosseous muscles* and three *plantar interosseous muscles* of layer 4 (the deepest). The plantar aponeurosis and its relationship to the layer 1 muscles (table 12.9)

12.3 Muscle Injuries (p. 324)

1. The common causes, prevention, and treatment of muscle injuries
2. The anatomical sites and causes of several common muscle and tendon injuries—baseball finger, blocker's arm, pitcher's arm, pulled groin, pulled hamstrings, rider's bones, shinsplints, tennis elbow, and tennis leg (table 12.10)

Testing Your Recall

1. Which of the following muscles could you most easily do without?
   a. flexor digitorum profundus
   b. trapezius
   c. palmaris longus
   d. triceps brachii
   e. tibialis anterior
2. Which of the following has the least in common with the other four?
   a. vastus intermedius
   b. vastus lateralis
   c. vastus medialis
   d. rectus femoris
   e. biceps femoris
3. The triceps surae is a muscle group composed of
   a. the flexor hallucis longus and brevis.
   b. the gastrocnemius and soleus.
   c. lateral, medial, and long heads.
   d. the biceps brachii and triceps brachii.
   e. the vastus lateralis, medialis, and intermedius.
4. The interosseous muscles lie between
   a. the ribs.
   b. the tibia and fibula.
   c. the radius and ulna.
   d. the metacarpal bones.
   e. the phalanges.
5. Which of these muscles does *not* contribute to the rotator cuff?
   a. the supraspinatus
   b. the infraspinatus
   c. the subscapularis
   d. the teres major
   e. the teres minor
6. Which of these actions is *not* performed by the trapezius?
   a. extension of the neck
   b. depression of the scapula
   c. elevation of the scapula
   d. rotation of the scapula
   e. adduction of the humerus
7. Both the hands and feet are acted upon by a muscle or muscles called
   a. the extensor digitorum.
   b. the abductor digiti minimi.
   c. the flexor digitorum profundus.
   d. the abductor hallucis.
   e. the flexor digitorum longus.
8. Which of the following muscles does *not* extend the hip joint?
   a. rectus femoris
   b. gluteus maximus
   c. biceps femoris
   d. semitendinosus
   e. semimembranosus
9. Both the gastrocnemius and _____ muscles insert on the heel by way of the calcaneal tendon.
   a. semimembranosus
   b. tibialis posterior
   c. tibialis anterior
   d. soleus
   e. plantaris
10. Which of these is *not* in the anterior compartment of the thigh?
    a. semimembranosus
    b. rectus femoris
    c. vastus intermedius
    d. vastus lateralis
    e. sartorius
11. The major superficial muscle of the shoulder, where injections are often given, is the _____.
12. If a muscle has the word *hallucis* in its name, it must cause movement of the _____.
13. Pronation of the forearm is achieved by two muscles, the pronator _____ just distal to the elbow and the pronator _____ near the wrist.
14. The three large muscles on the posterior side of the thigh are collectively known by the colloquial name of _____ muscles.
15. Connective tissue bands called _____ prevent flexor tendons from rising like bowstrings.
16. The web between your thumb and palm consists mainly of the _____ muscle.
17. The patella is embedded in the tendon of the _____ muscle.
18. The _____ muscle, named for its skeletal attachments, originates on the coracoid process of the scapula, ends on the humerus, and adducts the arm.
19. The most medial adductor muscle of the thigh is the long, slender _____.
20. The _____ and _____ are hip flexors that originate on the pelvis and lumbar vertebrae and converge on a shared tendon that ends on the lesser trochanter of the femur.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. serrat-
2. dorsi-
3. -ceps
4. infra-
5. teres
6. profund-
7. osse-
8. ili-
9. lat-
10. maxim-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. All plantar flexors in the posterior compartment of the calf converge on the heel by way of the calcaneal tendon.
2. The trapezius can act as both a synergist and antagonist of the levator scapulae.
3. To push someone away from you, you would use the serratus anterior muscle more than the trapezius.
4. Both the extensor digitorum and extensor digiti minimi extend the little finger.
5. The interosseous muscles are fusiform.
6. The actions of the palmaris longus and plantaris muscles are weak and relatively dispensable.
7. The psoas major is an antagonist of the rectus femoris.
8. Rapid flexion of the knee often causes hamstring injuries.
9. Curling your toes employs the quadratus plantae muscle.
10. The tibialis posterior and tibialis anterior are synergists.

Answers in appendix A

Testing Your Comprehension

1. Radical mastectomy, once a common treatment for breast cancer, involved removal of the pectoralis major along with the breast. What functional impairments would result from this? What synergists could a physical therapist train a patient to use to recover some lost function?
2. Table 12.4 describes a simple test for determining whether you have a palmaris longus muscle. Why do you think the other major tendon of the anterior wrist, the flexor carpi radialis tendon, does not stand out conspicuously in such a test?
3. Poorly conditioned, middle-aged people may suffer a rupture of the calcaneal tendon when the foot is suddenly dorsiflexed. Explain each of the following signs of a ruptured calcaneal tendon: (a) a prominent lump typically appears in the calf; (b) the foot can be dorsiflexed farther than usual; and (c) the patient cannot plantar flex the foot very effectively.
4. Women who habitually wear high heels may suffer painful “high heel syndrome” when they go barefoot or wear flat shoes. What muscle(s) and tendon(s) are involved? Explain.
5. A student moving out of a dormitory crouches in correct fashion to lift a heavy box of books. What prime movers are involved as he straightens his legs to lift the box?

How many muscles can you identify from their surface appearance?

© Jupiterimages/Getty Images RF

ATLAS

A

ATLAS OF REGIONAL AND SURFACE ANATOMY

ATLAS OUTLINE

A.1 Introduction 330
- Regional Anatomy 330
- Surface Anatomy 330
- Learning Strategy 330

A.2 The Head and Neck 331 (figs. A.1–A.2)

A.3 The Trunk 333 (figs. A.3–A.16)

A.4 The Upper Limb 344 (figs. A.17–A.19)

A.5 The Lower Limb 346 (figs. A.20–A.24)

A.6 Test of Muscle Recognition 350 (fig. A.25)

Anatomy & Physiology REVEALED® aprevealed.com

Module 6: Muscular System

A.1 Introduction

Regional Anatomy

On the whole, this book takes a **systems approach** to anatomy, examining the structure and function of each organ system, one at a time, regardless of which body regions it may traverse. Physicians and surgeons, however, think and act in terms of **regional anatomy.** If a patient presents with pain in the lower right quadrant (LRQ) (see fig. 1.11, p. 15), the source may be the appendix, the small intestine, an ovary or uterine tube, or an inguinal muscle, among other possibilities. The question is to think not of an entire organ system (the esophagus is probably irrelevant to the LRQ), but of what organs are present in that region and what possibilities must be considered as the cause of the pain. This atlas presents several views of the body region by region so that you can see some of the spatial relationships that exist among the organ systems considered in their separate chapters.

Surface Anatomy

In the study of human anatomy, it is easy to become so preoccupied with internal structure that we forget the importance of what we can see and feel externally. Yet external anatomy and appearance are major concerns in giving a physical examination and in many aspects of patient care. A knowledge of the body's surface landmarks is essential to one's competence in physical therapy, cardiopulmonary resuscitation, surgery, making X-rays and electrocardiograms, giving injections, drawing blood, listening to heart and respiratory sounds, measuring the pulse and blood pressure, and finding pressure points to stop arterial bleeding, among other procedures. A misguided attempt to perform some of these procedures while disregarding or misunderstanding external anatomy can be very harmful and even fatal to a patient.

Having just studied skeletal and muscular anatomy in the preceding chapters, this is an opportune time for you to study the body surface. Much of what we see there reflects the underlying structure of the superficial bones and muscles. A broad photographic overview of surface anatomy is given in chapter 1 (see fig. 1.10, p. 14), where it was necessary for providing a vocabulary for reference in the chapters that followed. This atlas shows this surface anatomy in closer detail so you can relate it to the musculoskeletal anatomy of chapters 7 through 12.

Learning Strategy

To make the most profitable use of this atlas, refer back to earlier chapters as you study these illustrations. Relate drawings of the clavicles in chapter 7 to the photograph in figure A.1, for example. Study the shape of the scapula in chapter 8 and see how much of it you can trace on the photographs in figure A.9. See if you can relate the tendons visible on the hand (see fig. A.19) to the muscles of the forearm illustrated in chapter 12, and the external landmarks of the pelvic girdle (see fig. A.15) to the bone structure in chapter 8.

For learning surface anatomy, there is a resource available to you that is far more valuable than any laboratory model or textbook illustration—your own body. For the best understanding of human structure, compare the art and photographs in this book with your body or with structures visible on a study partner. In addition to bones and muscles, you can palpate a number of superficial arteries, veins, tendons, ligaments, and cartilages, among other structures. By palpating regions such as the shoulder, elbow, or ankle, you can develop a mental image of the subsurface structures better than you can obtain by looking at two-dimensional textbook images. And the more you can study with other people, the more you will appreciate the variations in human structure and be able to apply your knowledge to your future patients or clients, who will not look quite like any textbook diagram or photograph you have ever seen. Through comparisons of art, photography, and the living body, you will get a much deeper understanding of the body than if you were to study this atlas in isolation from the earlier chapters.

At the end of this atlas, you can test your knowledge of externally visible muscle anatomy. The two photographs in figure A.25 have 30 numbered muscles and a list of 26 names, some of which are shown more than once in the photographs and some of which are not shown at all. Identify the muscles to your best ability without looking back at the previous illustrations, and then check your answers in appendix A at the back of the book.

Throughout these illustrations, the following abbreviations apply: a. = artery; m. = muscle; n. = nerve; and v. = vein. Double letters such as mm. or vv. represent the plurals.


Occipital
Temporal
Auricular
Buccal (cheek)
Nuchal (posterior cervical)
Frontal
Orbital
Nasal
Oral
Mental
Cervical

© McGraw-Hill Education/Joe De Grandis, photographer

(a) Lateral view


Frons (forehead)
Root of nose
Bridge of nose
Superciliary ridge
Superior palpebral sulcus
Inferior palpebral sulcus
Auricle (pinna) of ear
Philtrum
Labia (lips)
Supraclavicular fossa
Lateral commissure
Medial commissure
Dorsum nasi
Apex of nose
Ala nasi
Mentolabial sulcus
Mentum (chin)
Sternoclavicular joints
Clavicle
Suprasternal notch
Sternum

© McGraw-Hill Education/Joe De Grandis, photographer

(b) Anterior view

Figure A.1 The Head and Neck. (a) Anatomical regions of the head. (b) Features of the facial region and upper thorax.
- *What muscle underlies the region of the philtrum? What muscle forms the slope of the shoulder?*


Scalp
Cranium
Frontal sinus
Nasal cavity
Palate
Oral cavity
Tongue
Epiglottis
Pharynx
Vocal cord
Larynx
Trachea
Esophagus
Cerebrum
Brainstem
Cerebellum
Foramen magnum of skull
Spinal cord
Vertebral column
Intervertebral discs

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Figure A.2 **Median Section of the Head.** Shows contents of the cranial, nasal, and oral cavities and vertebral canal.


Platysma m.
Trapezius m.
Clavicle
Deltoid m.
Cephalic v.
Breast
Biceps brachii m.
External abdominal oblique m.
Inguinal ligament
Tensor fasciae latae m.
Sartorius m.
Femoral v.
Great saphenous v.
Vastus lateralis m.
Rectus femoris m.
Pectoralis major m.
Sheath of rectus abdominis m.
Umbilicus
Anterior superior spine of ilium
Mons pubis
Adductor longus m.
Gracilis m.

Figure A.3 **Superficial Anatomy of the Trunk (Female).** Surface anatomy is shown on the anatomical left, and structures immediately deep to the skin on the right.


Internal jugular v.
External jugular v.
Omohyoid m.
Clavicle
Internal intercostal mm.
External intercostal mm.
Costal cartilages
Liver
Gallbladder
External abdominal oblique m.
Internal abdominal oblique m.
Transverse abdominal m.
Greater omentum
Urinary bladder
Penis
Scrotum
Common carotid a.
Sternum
Sub-scapularis m.
Coraco-brachialis m.
Lung
Pericardium
Pleura
Diaphragm
Stomach
Large intestine
Femoral n.
Femoral a.
Femoral v.

Figure A.4 **Anatomy at the Level of the Rib Cage and Greater Omentum (Male).** The anterior body wall is removed, and the ribs, intercostal muscles, and pleura are removed from the anatomical left.


Thyroid cartilage of larynx
Thyroid gland
Brachial nerve plexus
Superior vena cava
Coraco-brachialis m.
Humerus
Lobes of lung
Small intestine
Cecum
Appendix
Tensor fasciae latae m.
Pectineus m.
Adductor longus m.
Gracilis m.
Adductor magnus m.
Rectus femoris m.
Brachio-cephalic v.
Subclavian v.
Subclavian a.
Aortic arch
Axillary v.
Axillary a.
Cephalic v.
Brachial v.
Brachial a.
Heart
Spleen
Stomach
Large intestine
Penis (cut)
Ductus deferens
Epididymis
Testis
Scrotum

Figure A.5 **Anatomy at the Level of the Lungs and Intestines (Male).** The sternum, ribs, and greater omentum are removed.
• *Name several viscera that are protected by the rib cage.*


Trachea
Superior vena cava
Bronchus
Lung
(sectioned)
Esophagus
Thoracic aorta
Pleural cavity
Hepatic vv.
Spleen
Inferior vena cava
Adrenal gland
Splenic a.
Pancreas
Duodenum
Kidney
Superior mesenteric v.
Superior
mesenteric a.
Abdominal aorta
Inferior
mesenteric a.
Common iliac a.
Ureter
Ovary
Tensor fasciae
latae m. (cut)
Uterine tube
Sartorius m. (cut)
Uterus
Urinary bladder
Rectus
femoris m. (cut)
Pectineus m.
Gracilis m.
Adductor brevis m.
Vastus intermedius
m.
Adductor longus m.
Adductor
longus m. (cut)
Vastus lateralis m.
Vastus medialis m.

Figure A.6 **Anatomy at the Level of the Retroperitoneal Viscera (Female).** The heart is removed, the lungs are frontally sectioned, and the viscera of the peritoneal cavity and the peritoneum itself are removed.


Right common carotid a.
Right subclavian a.
Brachiocephalic trunk
External intercostal m.
Ribs
Internal intercostal m.
Quadratus lumborum m.
Psoas major m.
Iliacus m.
Gluteus medius m.
Rectum
Vagina
Urethra
Femur
Gracilis m.
Adductor longus m.
Left common carotid a.
Left subclavian a.
Thoracic aorta
Esophagus
Diaphragm
Abdominal aorta
Intervertebral disc
Lumbar vertebra
Iliac crest
Ilium
Sacrum
Anterior superior spine of ilium
Brim of pelvis
Adductor magnus m.
Adductor brevis m.

Figure A.7 **Anatomy at the Level of the Posterior Body Wall (Female).** The lungs and retroperitoneal viscera are removed.


Supraclavicular fossa
Clavicle
Acromion
Deltoid m.
Pectoralis major m.
Nipple
Rectus abdominis m.
Tendinous intersection of rectus abdominis m.
Anterior superior spine of ilium
Iliac crest
Inguinal ligament
Sternocleidomastoid m.
Thyroid cartilage
Trapezius m.
Sternum:
Suprasternal notch
Manubrium
Angle
Body
Xiphoid process
Serratus anterior mm.
Linea semilunaris
Linea alba
Umbilicus
External abdominal oblique m.

© McGraw-Hill Education/Joe De Grandis, photographer

(a) Male


Supraclavicular fossa
Clavicle
Acromion
Deltoid m.
Breast:
Axillary tail
Nipple
Areola
Corpus (body)
Costal margin
Linea semilunaris
External abdominal oblique m.
Trapezius m.
Sternum:
Suprasternal notch
Manubrium
Angle
Body
Xiphoid process
Linea alba
Rectus abdominis m.
Umbilicus
Anterior superior spine of ilium

© McGraw-Hill Education/Joe De Grandis, photographer

(b) Female

Figure A.8 **The Thorax and Abdomen, Anterior View.** All of the features labeled are common to both sexes, though some are labeled only on the photograph that better shows them.

- *The V-shaped tendons on each side of the suprasternal notch in part (a) belong to what muscles?*


Flexor carpi ulnaris
Brachioradialis
Biceps brachii
Triceps brachii
Deltoid:
Anterior part
Middle part
Posterior part
Teres major
Infraspinatus
Medial border of scapula
Trapezius
Vertebral furrow
Erector spinae
Latissimus dorsi
Iliac crest

© McGraw-Hill Education/Joe De Grandis, photographer

(a) Male


Infraspinatus
Trapezius
Olecranon
Iliac crest
Gluteus medius
Gluteus maximus
Hamstring muscles
Acromion
Medial border of scapula
Inferior angle of scapula
Latissimus dorsi
Erector spinae
Sacrum
Coccyx
Natal cleft
Greater trochanter of femur
Gluteal fold

© McGraw-Hill Education/Joe De Grandis, photographer

(b) Female

Figure A.9 **The Back and Gluteal Region.** All of the features labeled are common to both sexes, though some are labeled only on the photograph that better shows them.


Internal jugular v.
Subclavian v.
Nerves
Lungs
Ribs
Heart
Diaphragm

© McGraw-Hill Education

Figure A.10 **Frontal View of the Thoracic Cavity.**


Anterior
Pectoralis major m.
Ventricles of heart
Pericardial cavity
Atria of heart
Left lung
Pleural cavity
Fat of breast
Sternum
Ribs
Right lung
Esophagus
Aorta
Vertebra
Spinal cord
Posterior

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Figure A.11 **Transverse Section of the Thorax.** Section taken at the level shown by the inset and oriented the same as the reader's body.
- *In this section, which term best describes the position of the aorta relative to the heart: posterior, lateral, or proximal?*


Lung
Diaphragm
Transverse colon
Gallbladder
Small intestine
Mesenteric arteries and veins
Mesentery
Descending colon
Cecum
Sigmoid colon

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Figure A.12 **Frontal View of the Abdominal Cavity.**


Anterior
Posterior
Duodenum
Stomach
Large intestine
Pancreas
Kidney
Perirenal fat of kidney
Erector spinae m.
Subcutaneous fat
Rectus abdominis m.
Superior mesenteric artery and vein
Inferior vena cava
Liver
Peritoneal cavity
Peritoneum
Aorta
Vertebra
Spinal cord

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Figure A.13 **Transverse Section of the Abdomen.** Section taken at the level shown by the inset and oriented the same as the reader's body.
- *What tissue in this photograph is immediately superficial to the rectus abdominis muscle?*


Urinary bladder
Pubic symphysis
Seminal vesicle
Prostate gland
Penis:
Root
Bulb
Shaft:
Corpus cavernosum
Corpus spongiosum
Glans
Sigmoid colon
Rectum
Anal canal
Anus
Epididymis
Scrotum
Testis

© McGraw-Hill Education/Dennis Strete, photographer

(a) Male


Mesentery
Small intestine
Uterus
Cervix
Urinary bladder
Pubic symphysis
Urethra
Vagina
Labium minus
Prepuce
Labium majus
Vertebra
Red bone marrow
Intervertebral disc
Sacrum
Sigmoid colon
Rectum
Anal canal
Anus

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

(b) Female

Figure A.14 Median Sections of the Pelvic Cavitiy. Viewed from the left.


© McGraw-Hill Education/Joe De Grandis, photographer
© McGraw-Hill Education/Joe De Grandis, photographer

(a) Anterior view **(b) Posterior view**

Figure A.15 **Pelvic Landmarks.** (a) The anterior superior spines of the ilium are marked by anterolateral protuberances (arrows) at about the location where the pockets usually open on a pair of pants. (b) The posterior superior spines are marked in some people by dimples in the sacral region (arrows).


Olecranon
Biceps brachii
Triceps brachii
Anterior axillary fold (pectoralis major)
Posterior axillary fold (latissimus dorsi)
Deltoid
Axilla (armpit)
Pectoralis major
Latissimus dorsi

© McGraw-Hill Education/Joe De Grandis, photographer

Figure A.16 **The Axillary Region.**


Interphalangeal joints
Metacarpophalangeal joints
Styloid process of radius
Extensor digitorum
Trapezius
Acromion
Deltoid
Pectoralis major
Biceps brachii
Triceps brachii:
Lateral head
Long head
Brachioradialis
Extensor carpi radialis longus
Lateral epicondyle of humerus
Olecranon

© McGraw-Hill Education/Joe De Grandis, photographer

Figure A.17 **The Upper Limb, Lateral View.**


Cubital fossa
Cephalic vein
Median cubital vein
Brachioradialis
Styloid process of radius
Thenar eminence
Palmar surface of hand
Pollex (thumb)
Flexion lines
Biceps brachii
Medial epicondyle of humerus
Flexor carpi radialis
Palmaris longus
Flexor carpi ulnaris
Styloid process of ulna
Hypothenar eminence
Flexion lines
Volar surface of fingers
Triceps brachii
Olecranon
Head of radius
Brachioradialis
Flexor carpi ulnaris
Extensor carpi ulnaris
Extensor digitorum
Tendons of extensor digitorum
Dorsum of hand

© McGraw-Hill Education/Joe De Grandis, photographer

© McGraw-Hill Education/Joe De Grandis, photographer

(a) Anterior view

(b) Posterior view

Figure A.18 **The Right Antebrachium (Forearm).**

- *Only two tendons of the extensor digitorum are labeled, but how many tendons does this muscle have in all?*


V
IV
III
II
I
Interphalangeal joints
Metacarpophalangeal joint
Flexion lines
Pollex (thumb)
Hypothenar eminence
Thenar eminence
Flexion lines
Flexor carpi radialis tendon
Palmaris longus tendon

© McGraw-Hill Education/Joe De Grandis, photographer

(a) Anterior (palmar) view


Adductor pollicis
Extensor digitorum tendons
Extensor pollicis longus tendon
Anatomical snuffbox
Extensor pollicis brevis tendon
Styloid process of radius
Styloid process of ulna

© McGraw-Hill Education/Joe De Grandis, photographer

(b) Posterior (dorsal) view

Figure A.19 The Right Wrist and Hand.

- *Mark the spot on one or both photographs where a saddle joint can be found.*


Lateral
Medial
Tensor fasciae latae
Rectus femoris
Gracilis
Vastus lateralis
Vastus medialis
Quadriceps femoris tendon
Iliotibial tract
Patella
Patellar ligament
Tibial tuberosity
Medial
Lateral
Vastus lateralis
Biceps femoris (long head)
Semitendinosus
Semimembranosus
Gracilis
Popliteal fossa
Gastrocnemius

© McGraw-Hill Education/Joe De Grandis, photographer

© McGraw-Hill Education/Joe De Grandis, photographer

(a) Anterior view

(b) Posterior view

Figure A.20 **The Right Thigh and Knee.** Locations of posterior thigh muscles are indicated, but the boundaries of the individual muscles are rarely visible on a living person.

- *Mark the spot on part (a) where the vastus intermedius would be found.*


Vastus lateralis
Biceps femoris
Iliotibial tract
Lateral epicondyle of femur
Head of fibula
Patellar ligament
Gastrocnemius, lateral head
Soleus
Fibularis longus
Tibialis anterior
Tendons of fibularis longus and brevis
Calcaneal tendon
Lateral malleolus of fibula
Calcaneus
Semimembranosus and tendon
Vastus medialis
Patella
Semitendinosus tendon
Medial epicondyle of femur
Medial condyle of tibia
Gastrocnemius, medial head
Soleus
Tibia
Medial malleolus
Tibialis anterior tendon
Medial longitudinal arch
Abductor hallucis
Head of metatarsal I

© McGraw-Hill Education/Joe De Grandis, photographer

(a) Lateral view

© McGraw-Hill Education/Joe De Grandis, photographer

(b) Medial view

Figure A.21 **The Leg and Foot.** (a) Lateral view of the left limb. (b) Medial view of the right limb.

- *The lateral malleolus is part of what bone?*


Medial
Lateral
Biceps femoris tendon
Semitendinosus tendon
Popliteal fossa
Gastrocnemius:
Medial head
Lateral head
Soleus
Fibularis longus
Tibialis anterior
Calcaneal tendon
Lateral malleolus
Extensor digitorum brevis
Calcaneus

© McGraw-Hill Education/Joe De Grandis, photographer

Figure A.22 **The Right Leg and Foot, Posterior View.**


Hallux (great toe)
Head of metatarsal I
Transverse arch
Head of metatarsal V
Abductor digiti minimi
Abductor hallucis
Medial longitudinal arch
Lateral longitudinal arch
Lateral malleolus
Calcaneus
II
III
I
IV
V
Soleus
Tibia
Tibialis anterior
Medial malleolus
Lateral malleolus
Site for palpating dorsal pedal artery
Extensor hallucis longus tendon
Extensor digitorum longus tendons
Head of metatarsal I
V
IV
III
II
I
Hallux (great toe)

© McGraw-Hill Education/Joe De Grandis, photographer

© McGraw-Hill Education/Joe De Grandis, photographer

(a) Plantar view **(b) Dorsal view**

Figure A.23 **The Foot, Plantar and Dorsal Views.** Compare the arches in part (a) to the skeletal anatomy in figure 8.16 (p. 200).


Calcaneal tendon
Lateral malleolus
Extensor digitorum brevis
Extensor digitorum longus tendons
Lateral longitudinal arch

© McGraw-Hill Education/Joe De Grandis, photographer

(a) Lateral view


Medial malleolus
Calcaneal tendon
Medial longitudinal arch
Calcaneus
Head of metatarsal I

© McGraw-Hill Education/Joe De Grandis, photographer

(b) Medial view

Figure A.24 **The Foot, Lateral and Medial Views.**
- *Indicate the location of middle phalanx I on each photograph.*



© McGraw-Hill Education/Joe De Grandis, photographer

© McGraw-Hill Education/Joe De Grandis, photographer

(a) Anterior view

(b) Posterior view

Figure A.25 Test of Muscle Recognition. To test your knowledge of muscle anatomy, match the 30 labeled muscles on these photographs to the following alphabetical list of muscles. Answer as many as possible without referring back to the previous illustrations. Some of these names will be used more than once since the same muscle may be shown from different perspectives, and some of these names will not be used at all. The answers are in appendix A.

a. biceps brachii
b. brachioradialis
c. deltoid
d. erector spinae
e. external abdominal oblique
f. flexor carpi ulnaris
g. gastrocnemius
h. gracilis
i. hamstrings
j. infraspinatus
k. latissimus dorsi
l. pectineus
m. pectoralis major
n. rectus abdominis
o. rectus femoris
p. serratus anterior
q. soleus
r. splenius capitis
s. sternocleidomastoid
t. subscapularis
u. teres major
v. tibialis anterior
w. trapezius
x. triceps brachii
y. vastus lateralis
z. vastus medialis



A Purkinje cell, a neuron from the cerebellum of the brain

© David Becker/Science Source

PART THREE

CHAPTER 13

THE NERVOUS SYSTEM I
NERVOUS TISSUE

CHAPTER OUTLINE

13.1 Overview of the Nervous System 352

13.2 Nerve Cells (Neurons) 353
- Universal Properties of Neurons 353
- Functional Classes of Neurons 354
- Structure of a Neuron 354
- Neuronal Variety 356

13.3 Supportive Cells (Neuroglia) 357
- Types of Neuroglia 357
- Myelin 359
- Unmyelinated Nerve Fibers 360
- Myelin and Signal Conduction 360
- Schwann Cells and Nerve Regeneration 361

13.4 Synapses and Neural Circuits 361
- Synapses 361
- Neural Pools and Circuits 363

13.5 Developmental and Clinical Perspectives 365
- Development of the Nervous System 365
- Developmental Disorders 367

Study Guide 368

DEEPER INSIGHTS

13.1 Glial Cells and Brain Tumors 360
13.2 Diseases of the Myelin Sheath 361

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concept:
- Early embryonic development (pp. 90–92)

Anatomy & Physiology REVEALED
aprevealed.com

Module 7: Nervous System

The next five chapters are concerned with the nervous system. This is a system of great complexity and mystery. It is the foundation of all our conscious experiences, personality, and behavior. It profoundly intrigues biologists, physicians, psychologists, and even philosophers. Understanding this fascinating system is regarded by many as the ultimate challenge facing the behavioral and life sciences.

We begin our study at the simplest organizational level—the nerve cells *(neurons)* and cells called *neuroglia* that support their function in various ways. We then progress to the organ level to examine the spinal cord (chapter 14), brain (chapter 15), autonomic nervous system (chapter 16), and sense organs (chapter 17).

13.1 Overview of the Nervous System

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the function of the nervous system;
b. describe the anatomical subdivisions of the nervous system;
c. explain the functional differences between these subdivisions; and
d. define *nerve, ganglion, receptor,* and *effector*.

If the body is to maintain homeostasis and function effectively, its trillions of cells must work together in a coordinated fashion. If each cell behaved without regard to what others are doing, the result would be physiological chaos and death. We have two organ systems dedicated to maintaining internal coordination—the **endocrine system,** which communicates by means of chemical messengers (hormones) secreted into the blood, and the **nervous system** (fig.13.1), which employs electrical and chemical means to send messages very quickly from cell to cell. The study of the nervous system is called **neurobiology.** Its primary subdisciplines are **neuroanatomy** and **neurophysiology.**

The nervous system carries out its coordinating task in three basic steps: (1) Through sensory nerve endings, it receives information about changes in the body and external environment and it transmits coded messages to the spinal cord and brain. (2) The spinal cord and brain process this information, relate it to past experience, and determine what response, if any, is appropriate to the circumstances. (3) The spinal cord and brain issue commands primarily to muscle and gland cells to carry out such responses.

The nervous system has two major anatomical subdivisions (fig. 13.2):

- The **central nervous system (CNS)** consists of the brain and spinal cord, which are enclosed and protected by the cranium and vertebral column.


Central nervous system (CNS)
Peripheral nervous system (PNS)
Brain
Spinal cord
Nerves
Ganglia

Figure 13.1 The Nervous System.
- *Which division, the CNS or PNS, is likely to suffer the most frequent injuries? Why?*


Central nervous system
Peripheral nervous system
Brain
Spinal cord
Sensory division
Motor division
Visceral sensory division
Somatic sensory division
Visceral motor division
Somatic motor division
Sympathetic division
Parasympathetic division

Figure 13.2 Subdivisions of the Nervous System.

- The **peripheral nervous system (PNS)** consists of all the nervous system except the brain and spinal cord. It is composed of nerves and ganglia. A **nerve** is a bundle of nerve fibers (axons) wrapped in fibrous connective tissue. Nerves emerge from the CNS through foramina of the skull and vertebral column and carry signals to and from other organs of the body. A **ganglion**[1] (plural, *ganglia*) is a knotlike swelling in a nerve where the cell bodies of neurons are concentrated.

The peripheral nervous system is functionally divided into *sensory* and *motor* divisions, and each of these is further divided into *somatic* and *visceral* divisions.

- The **sensory (afferent**[2]**) division** carries sensory signals from various **receptors** (sense organs and simple sensory nerve endings) to the CNS. This is the pathway that informs the CNS of stimuli within and around the body.
  - The **somatic**[3] **sensory division** carries signals from receptors in the skin, muscles, bones, and joints.
  - The **visceral sensory division** carries signals mainly from the viscera of the thoracic and abdominal cavities, such as the heart, lungs, stomach, and urinary bladder.
- The **motor (efferent**[4]**) division** carries signals from the CNS to gland and muscle cells that carry out the body's responses. Cells and organs that respond to commands from the nervous system are called **effectors.**
  - The **somatic motor division** carries signals to the skeletal muscles. This output produces muscular contractions that are under voluntary control, as well as involuntary muscle contractions called *somatic reflexes.*
  - The **visceral motor division (autonomic**[5] **nervous system, ANS)** carries signals to glands, cardiac muscle, and smooth muscle. We usually have no voluntary control over these effectors, and this system operates at an unconscious level. The responses of this system and its effectors are *visceral reflexes.* The autonomic nervous system has two further divisions:
    - The **sympathetic division** tends to arouse the body for action—for example, by accelerating the heartbeat and increasing respiratory airflow—but it inhibits digestion.
    - The **parasympathetic division** adapts the body for energy intake and conservation. It stimulates digestion but slows down the heartbeat and reduces respiratory airflow, for example.

The foregoing terminology may give the impression that the body has several nervous systems—central, peripheral, sensory, motor, somatic, and visceral. These are just terms of convenience, however. There is only one nervous system, and these subsystems are interconnected parts of the whole.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. Define *receptor* and *effector*. Give two examples of each.
2. Distinguish between the central and peripheral nervous systems, and between the visceral and somatic divisions of the sensory and motor systems.
3. What is another name for the visceral motor nervous system? What are the two subdivisions of this system? How do they differ in their effects on the body?

13.2 Nerve Cells (Neurons)

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the properties that neurons must have to carry out their function;
b. define three functional classes into which all neurons fall;
c. describe the structure of a representative neuron; and
d. describe some variations in neuron structure.

Universal Properties of Neurons

The functional unit of the nervous system is the **nerve cell,** or **neuron;** neurons carry out the system's communicative role. These cells have three fundamental physiological properties that are necessary to this function:

1. **Excitability (irritability).** All cells possess excitability, or responsiveness to environmental changes called **stimuli.** Neurons have developed this property to the highest degree.
2. **Conductivity.** Neurons respond to stimuli by producing traveling electrical signals that quickly reach other cells at distant locations.
3. **Secretion.** When the electrical signal reaches the end of a nerve fiber, the neuron usually secretes a chemical called a *neurotransmitter* that crosses a small gap between cells and stimulates the next cell.

Apply What You Know

What basic physiological properties do a nerve cell and a muscle cell have in common? Identify one property that each cell type has that the other one lacks.

---

[1] *gangli* = knot
[2] *af* = *ad* = toward; *fer* = to carry
[3] *somat* = body; *ic* = pertaining to
[4] *ef* = *ex* = out, away; *fer* = to carry
[5] *auto* = self; *nom* = law, governance


Peripheral nervous system
Central nervous system
① Sensory (afferent) neurons conduct signals from receptors to the CNS.
② Interneurons are confined to the CNS.
③ Motor (efferent) neurons conduct signals from the CNS to effectors such as muscles and glands.

Figure 13.3 **Functional Classes of Neurons.** Sensory (afferent) neurons carry signals to the central nervous system (CNS); interneurons are contained entirely within the CNS and carry signals from one neuron to another; and motor (efferent) neurons carry signals from the CNS to muscles and glands.

- *How do the origins of the words* afferent *and* efferent *relate to the functions of the respective neurons?*

Functional Classes of Neurons

There are three general classes of neurons (fig. 13.3) corresponding to the three major aspects of nervous system function listed earlier:

1. **Sensory (afferent) neurons** are specialized to detect stimuli such as light, heat, pressure, and chemicals and to transmit information about them to the CNS. These neurons can begin in almost any organ of the body but always end in the brain or spinal cord; the word *afferent* refers to signal conduction *toward* the CNS. Some sensory receptors, such as pain and smell receptors, are themselves neurons. In other cases, such as taste and hearing, the receptor is a separate cell that communicates directly with a sensory neuron.
2. **Interneurons**[6] lie entirely within the CNS. They receive signals from many other neurons and carry out the *integrative* function of the nervous system—that is, they process, store, and retrieve information and "make decisions" about how the body responds to stimuli. About 90% of human neurons are interneurons. The word *interneuron* refers to the fact that they lie *between*, and interconnect, the incoming sensory pathways and the outgoing motor pathways of the CNS.
3. **Motor (efferent) neurons** send signals predominantly to muscle and gland cells, the effectors that carry out the body's responses to stimuli. They are called *motor* neurons because most of them lead to muscle cells, and *efferent* neurons to signify that they conduct signals *away from* the CNS.

Structure of a Neuron

There are several varieties of neurons, as we shall see, but a good starting point for discussing neuron stucture is a motor neuron of the spinal cord (fig. 13.4). The control center of the neuron is its **neurosoma,**[7] also called the **soma** or **cell body.** It has a single, centrally located nucleus with a large nucleolus. The cytoplasm contains mitochondria, lysosomes, a Golgi complex, numerous inclusions, and an extensive rough endoplasmic reticulum and cytoskeleton. The cytoskeleton consists of a dense mesh of microtubules and **neurofibrils** (bundles of actin filaments) that compartmentalize the rough ER into dark-staining regions called *Nissl*[8] *bodies,* unique to neurons (fig. 13.4d, e). Nissl bodies are a helpful clue to identifying neurons in tissue sections with mixed cell types. Mature neurons lack centrioles and apparently undergo no further mitosis after adolescence, but they are unusually long-lived cells, capable of functioning for over a hundred years. Even in old age, however, there are unspecialized stem cells in the CNS that divide and develop into new neurons.

The major cytoplasmic inclusions in a neuron are glycogen granules, lipid droplets, melanin, and a golden brown pigment called *lipofuscin*[9] (LIP-oh-FEW-sin)—produced when lysosomes digest worn-out organelles and other products. Lipofuscin collects with age and pushes the nucleus to one side of the cell. Lipofuscin granules are also called "wear-and-tear granules" because they are most abundant in old neurons.

The soma of a spinal motor neuron gives rise to a few thick processes that branch into a vast number of **dendrites**[10]—named for their striking resemblance to the bare branches of a tree in winter. The dendrites are the primary sites for receiving signals from other neurons. Some neurons have only one dendrite and some have thousands. The more dendrites a neuron has, the more information it can receive from other cells and incorporate into its decision making. As tangled as the dendrites may seem, they provide exquisitely precise pathways for the reception and processing of neural information.

On one side of the soma is a mound called the **axon hillock,** from which the **axon (nerve fiber)** originates. The axon hillock and nearby portion of the axon *(initial segment)* are collectively called the **trigger zone,** because this is usually where the neuron first generates **action potentials**—electrical changes that constitute the nerve signal. An axon is specialized for rapid conduction of nerve signals to points remote from the soma. It is cylindrical and relatively unbranched for most of its length; however, it may give rise to a few branches called *axon collaterals* along the way, and most axons branch extensively at their distal end. An axon's cytoplasm is called the **axoplasm** and its membrane the **axolemma.**[11] A neuron never has more than one axon, and some neurons in the retina and

---

[6] *inter* = between

[7] *soma* = body

[8] Franz Nissl (1860–1919), German neuropathologist

[9] *lipo* = fat, lipid; *fusc* = dusky, brown

[10] *dendr* = tree, branch; *ite* = little

[11] *axo* = axis, axon; *lemma* = husk, peel, sheath


Dendrites
Soma
Nucleus
Nucleolus
Trigger zone:
Axon hillock
Initial segment
Axon collateral
Axon
Direction of signal transmission
Internodes
Node of Ranvier
Myelin sheath
Schwann cell
Terminal arborization
Presynaptic terminals
(a)
(b)
Axoplasm
Schwann cell nucleus
Axolemma
Neurilemma
Myelin sheath
(c)
Neurofibrils
Axon
(d)
Nissl bodies
Axon hillock
(e)

© Ed Reschke/Getty Images

Figure 13.4 **A Representative Neuron.** The Schwann cells and myelin sheath are explained later in this chapter. (a) A multipolar neuron such as a spinal motor neuron. (b) Photograph of this neuron type. (c) Detail of myelin sheath. (d) Neurofibrils of the soma. (e) Nissl bodies, stained masses of rough ER separated by the bundles of neurofibrils shown in part (d).

- *What feature of this neuron is the basis for classifying it as multipolar? (Relate this figure to the discussion of fig. 13.5.)*

brain have none. Many axons are covered in a myelin sheath, which increases the neuron's energy efficiency and speed of signal conduction. Myelin is explained in more detail in chapter section 13.3.

Neurosomas range from 5 to 135 µm in diameter, whereas axons range from 1 to 20 µm in diameter and from a few millimeters to more than a meter long. Such dimensions are more impressive when we scale them up to the size of familiar objects. If the soma of a spinal motor neuron was the size of a tennis ball, its dendrites would form a huge bushy mass that could fill a 30-seat classroom from floor to ceiling. Its axon would be up to a mile long but a little narrower than a garden hose. This is quite a point to ponder. The neuron must assemble molecules and organelles in its "tennis ball" soma and deliver them through its "mile-long garden hose" to the end of the axon. In a process called *axonal transport,* neurons employ *motor proteins* that can carry organelles and macromolecules as they crawl along the cytoskeleton of the nerve fiber to distant destinations in the cell.

At the distal end, an axon usually has a **terminal arborization**[12]—an extensive complex of fine branches. Each branch ends in a dilated tip called the **presynaptic terminal (terminal button).** Here, the terminal forms a junction *(synapse*[13]*)* with a muscle cell, gland cell, or another neuron. Synapses are described in detail later in this chapter. Autonomic fibers do not have presynaptic terminals, but have numerous beads called **varicosities** along their terminal branches (see fig. 10.18, p. 256). Each varicosity secretes neurotransmitter into its general vicinity and stimulates many target cells at once.

Apply What You Know

When proteins are needed in the presynaptic terminal, they must be made in the neurosoma, which is sometimes far away, and transported down the axon to the terminal. Why do you think they cannot simply be made locally, in the terminal itself?

Neuronal Variety

Not all neurons fit every detail of the preceding description. Neurons are classified structurally according to the number of processes extending from the soma (fig. 13.5).

- **Multipolar neurons** are those, like the preceding, that have one axon and two or more (usually many) dendrites. This is the most common type of neuron and includes most neurons of the brain and spinal cord.
- **Bipolar neurons** have one axon and one dendrite. Examples include olfactory cells of the nasal cavity, some neurons of the retina, and sensory neurons of the inner ear.
- **Unipolar neurons** have only a single process leading away from the soma. They are represented by the neurons that carry sensory signals to the spinal cord. These neurons are also called *pseudounipolar*[14] because they start out as bipolar neurons in the embryo, but their two processes fuse into one as the neuron matures. A short distance away from the soma, the process



Figure 13.5 Variation in Neuron Structure. *Top row, left to right:* Two multipolar neurons of the brain—a pyramidal cell and a Purkinje cell. *Second row, left to right:* Two bipolar neurons—a bipolar cell of the retina and an olfactory neuron. *Third row:* A unipolar neuron of the type involved in the senses of touch and pain. *Bottom row:* An anaxonic neuron (amacrine cell) of the retina.

---

[12] *arbor* = treelike
[13] *syn* = together; *aps* = to touch, join
[14] *pseudo* = false

branches like a T, with a *peripheral fiber* carrying signals from the source of sensation and a *central fiber* continuing into the spinal cord. In most other neurons, a dendrite carries signals toward the soma, and an axon carries them away. In unipolar neurons, however, there is one long fiber that bypasses the soma and carries nerve signals directly to the spinal cord. The dendrites are the branching receptive endings in the skin or other place of origin, while the rest of the fiber is considered to be the axon (defined in these neurons by the presence of myelin and the ability to generate action potentials).

- **Anaxonic neurons** have multiple dendrites but no axon. They communicate over short distances through their dendrites and do not produce action potentials. Anaxonic neurons are found in the brain, retina, and adrenal medulla. In the retina, they help in visual processes such as the perception of contrast.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

4. Explain why neurons could not function without the properties of excitability, conductivity, and secretion.
5. Distinguish between sensory neurons, interneurons, and motor neurons.
6. Define each of the following and explain its importance to neuronal function: *dendrites, soma, axon,* and *presynaptic terminal.*
7. Sketch a multipolar, bipolar, unipolar, and anaxonic neuron; next to each sketch, state one place where such a neuron could be found.

13.3 Supportive Cells (Neuroglia)

Expected Learning Outcomes

When you have completed this section, you should be able to

a. name six types of cells that aid neuron function and state their respective locations and functions;
b. describe the myelin sheath that is formed around certain nerve fibers;
c. describe how the speed of nerve signal conduction varies with nerve fiber diameter and the presence or absence of myelin; and
d. explain the relevance of neuroglia to the regeneration of damaged nerve fibers.

There are about a trillion (10^{12}) neurons in the nervous system—10 times as many neurons in one person as there are stars in our galaxy! Because they are so extensively branched, they make up about 50% of the volume of the nervous tissue. Yet they are outnumbered at least 10 to 1 by supportive cells called **neuroglia** (noo-ROG-lee-uh), or **glial** (GLEE-ul) **cells.** Glial cells protect the neurons and aid their function. The word *glia,* which means "glue," implies one of their roles—they bind neurons together. In the fetus, glial cells form a scaffold that guides young migrating neurons to their destinations. Wherever a mature neuron is not in synaptic contact with another cell, it is covered with glial cells. This prevents neurons from contacting each other except at points specialized for signal transmission, and thus lends precision to their conduction pathways.

Types of Neuroglia

There are six major categories of neuroglia, each with a unique function (table 13.1). Four types occur only in the central nervous system (fig. 13.6):

1. **Oligodendrocytes**[15] (OL-ih-go-DEN-dro-sites) somewhat resemble an octopus; they have a bulbous body with as many as 15 armlike processes. Each process reaches out to a nerve fiber and spirals around it like electrical tape wrapped repeatedly around a wire. This wrapping, called the *myelin sheath,* insulates the nerve fiber from the extracellular fluid and speeds up signal conduction in the nerve fiber.

TABLE 13.1 Types of Glial Cells

Type	Location	Functions
Oligodendrocytes	CNS	Form myelin in brain and spinal cord
Ependymal cells	CNS	Line cavities of brain and spinal cord; secrete and circulate cerebrospinal fluid
Microglia	CNS	Phagocytize and destroy microorganisms, foreign matter, and dead nervous tissue
Astrocytes	CNS	Cover brain surface and nonsynaptic regions of neurons; form supportive framework for the CNS; stimulate formation of blood–brain barrier; nourish neurons and secrete growth stimulants; influence synaptic signaling between neurons; help to regulate composition of the extracellular fluid in the CNS; form scar tissue to replace damaged nervous tissue
Schwann cells	PNS	Form neurilemma around all PNS nerve fibers and myelin around most of them; aid in regeneration of damaged nerve fibers
Satellite cells	PNS	Surround somas of neurons in the ganglia; insulate them and regulate their chemical environment

---

[15] *oligo* = few; *dendro* = branches; *cyte* = cell



Figure 13.6 Neuroglia of the Central Nervous System.

2. **Ependymal**[16] (ep-EN-dih-mul) **cells** resemble a cuboidal epithelium lining the internal cavities of the brain and spinal cord. Unlike true epithelial cells, however, they have no basement membrane and they exhibit rootlike processes that penetrate into the underlying tissue. Ependymal cells produce a significant fraction of the *cerebrospinal fluid (CSF),* a clear liquid that bathes the CNS and fills its internal cavities. Some ependymal cells have patches of cilia on their apical surfaces that help to circulate the CSF. Ependymal cells and CSF are considered in more detail in chapter 15 (p. 404).
3. **Microglia** are small macrophages that develop from white blood cells called monocytes. They wander through the CNS, putting out fingerlike extensions to constantly probe the tissue for cellular debris or other problems. They are thought to perform a complete checkup on the brain tissue several times a day, phagocytizing dead tissue, microorganisms, and other foreign matter. They become concentrated in areas damaged by infection, trauma, or stroke. Pathologists look for clusters of microglia in histological sections of the brain as a clue to sites of injury. Microglia also aid in synaptic remodeling—changing the connections between neurons during nervous system development.
4. **Astrocytes**[17] are the most abundant glial cells in the CNS and constitute over 90% of the tissue in some areas of the brain. They cover the entire brain surface and most nonsynaptic regions of the neurons in the gray matter of the CNS. They are named for their many-branched, somewhat starlike shape. They have the most diverse functions of any glia:
   - They form a supportive framework for the nervous tissue.
   - They have extensions called *perivascular feet,* which contact the blood capillaries and stimulate them to form a tight seal called the *blood–brain barrier.* This barrier isolates the blood from the brain tissue and limits what substances are able to get to the brain cells, thus protecting the neurons (see p. 405).
   - They convert blood glucose to lactate and supply this to the neurons for nourishment.
   - They monitor neuron activity and signal blood vessels to dilate or constrict, thus changing the regional blood flow of the brain tissue in accordance with changing needs for oxygen and nutrients.
   - They secrete proteins called *nerve growth factors* that promote neuron growth and synapse formation.
   - They communicate electrically with neurons and may influence synaptic signaling between neurons.
   - They regulate the chemical composition of the tissue fluid. When neurons transmit signals, they release neurotransmitters and potassium ions. Astrocytes absorb these substances and prevent them from reaching excessive levels in the tissue fluid.
   - When neurons are damaged, astrocytes form hardened scar tissue and fill space formerly occupied by the neurons. This process is called *astrocytosis* or *sclerosis.*

The other two types of glial cells occur only in the peripheral nervous system:

5. **Schwann**[18] **cells** (pronounced “shwon”), or **neurilemmocytes,** envelop nerve fibers of the PNS, forming a sleeve around them called the *neurilemma* (see fig. 13.4). In most cases, a Schwann cell winds repeatedly around a nerve fiber and produces a myelin sheath between the neurilemma and nerve fiber. This is similar to the myelin sheath produced by oligodendrocytes in the CNS, but there are differences in the way myelin is produced, as described later. In addition to myelinating peripheral nerve fibers, Schwann cells assist in the regeneration of damaged fibers.

---

[16] *ependyma* = upper garment
[17] *astro* = star; *cyte* = cell
[18] Theodor Schwann (1810–82), German histologist

6. **Satellite cells** surround the neurosomas in ganglia of the PNS. They provide electrical insulation around the soma and regulate the chemical environment of the neurons.

Myelin

The **myelin** (MY-eh-lin) **sheath** is an insulating layer around a nerve fiber, somewhat like the rubber insulation on a wire. It is formed by oligodendrocytes in the central nervous system and Schwann cells in the peripheral nervous system. Since it consists of the plasma membranes of these glial cells, its composition is like that of plasma membranes in general. It is about 20% protein and 80% lipid, the latter including phospholipids, glycolipids, and cholesterol. Myelin imparts a glistening white color to certain regions of nervous tissue, such as the *white matter* of the brain and spinal cord.

Production of the myelin sheath is called **myelination.** In the PNS, a Schwann cell spirals repeatedly around a single nerve fiber, laying down as many as a hundred compact layers of its own membrane with almost no cytoplasm between the membranes (fig. 13.7a).


Schwann cell
Axon
Nucleus
Basal lamina
Endoneurium
Neurilemma
Myelin sheath
(a)
Oligodendrocyte
Myelin
Nerve fiber
(b)
Myelinated axon
Schwann cell cytoplasm
Basal lamina
Neurilemma
Unmyelinated axon
(c)
3 µm

Figure 13.7 **Myelination.** (a) A Schwann cell of the PNS wrapping repeatedly around an axon to form the multilayered myelin sheath. The myelin spirals outward as it is laid down. The outermost coil of the Schwann cell constitutes the neurilemma. (b) An oligodendrocyte of the CNS wrapping around the axons of multiple neurons. Here, the myelin spirals inward toward the axon as it is laid down. (c) A myelinated axon (top) and unmyelinated axon (bottom) (TEM).

© McGraw-Hill Education/Dr. Dennis Emrey, Dept. of Zoology and Genetics, Iowa State University, photographer

DEEPER INSIGHT 13.1

Glial Cells and Brain Tumors

A tumor consists of a mass of rapidly dividing cells. Mature neurons, however, have little capacity for mitosis and seldom form tumors. Some brain tumors arise from the meninges (protective membranes of the CNS) or arise by metastasis from tumors elsewhere, such as malignant melanoma and colon cancer. Most adult brain tumors, however, are composed of glial cells, which are mitotically active throughout life. Such tumors, called *gliomas*,[19] grow rapidly and are highly malignant. Because of the blood–brain barrier, brain tumors usually do not yield to chemotherapy and must be treated with radiation or surgery.

These layers constitute the myelin sheath. The Schwann cell spirals outward as it wraps the nerve fiber, finally ending with a thick outermost coil called the **neurilemma**[20] (noor-ih-LEM-ah). Here, the bulging body of the Schwann cell contains its nucleus and most of its cytoplasm. External to the neurilemma is a basal lamina and then a thin sleeve of fibrous connective tissue called the *endoneurium.*

To visualize this myelination process, imagine that you wrap an almost-empty tube of toothpaste tightly around a pencil. The pencil represents the axon, and the spiral layers of toothpaste tube (with the toothpaste squeezed out) represent the myelin. The toothpaste would be forced to one end of the tube, which would form a bulge on the external surface of the wrapping, like the body of the Schwann cell.

In the CNS, each oligodendrocyte reaches out to myelinate several nerve fibers in its immediate vicinity (fig. 13.7b). Since it is anchored to multiple nerve fibers, it cannot migrate around any one of them like a Schwann cell does. It must push newer layers of myelin under the older ones, so myelination spirals inward toward the nerve fiber. Nerve fibers of the CNS have no neurilemma or endoneurium.

In both the PNS and CNS, a nerve fiber is much longer than the reach of a single glial cell, so it requires many Schwann cells or oligodendrocytes to cover one fiber. Consequently, the myelin sheath is segmented. The gaps between the segments are called **nodes of Ranvier**[21] (RON-vee-AY), and the myelin-covered segments from one gap to the next are called **internodes.** The internodes are about 0.2 to 1.0 mm long.

Unmyelinated Nerve Fibers

Many nerve fibers in the CNS and PNS are unmyelinated. In the PNS, however, even the unmyelinated fibers are enveloped in Schwann cells. In this case, one Schwann cell harbors from 1 to 12 small nerve fibers in grooves in its surface (fig. 13.8). The Schwann cell's plasma membrane does not spiral repeatedly around the fiber as it does in a myelin sheath, but folds once around each fiber and somewhat overlaps itself along the edges. This wrapping is the neurilemma. Most nerve fibers travel through their own channels in the Schwann cell, but small fibers are sometimes bundled together in a single channel. A basal lamina surrounds the entire Schwann cell along with its nerve fibers.



Figure 13.8 **Unmyelinated Nerve Fibers.** Multiple unmyelinated fibers are enclosed in channels in the surface of a single Schwann cell. •*What is the functional disadvantage of an unmyelinated nerve fiber? What is its anatomical advantage?*

Myelin and Signal Conduction

The speed at which a signal travels along a nerve fiber depends on two factors: the diameter of the fiber and the presence or absence of myelin. Signal conduction occurs along the surface of a fiber, not deep within its axoplasm. Large fibers have more surface area and conduct signals more rapidly than small fibers. Myelin further speeds signal conduction for physiological reasons beyond the scope of this book. Nerve signals travel about 0.5 to 2.0 m/s in small unmyelinated fibers (2–4 μm in diameter); 3 to 15 m/s in myelinated fibers of the same size; and as fast as 120 m/s in large myelinated fibers (up to 20 μm in diameter).

One might wonder why all of our nerve fibers are not large, myelinated, and fast, but if this was so, our nervous system would be impossibly bulky or limited to far fewer fibers. Large nerve fibers require large somas and a large expenditure of energy to maintain them. The evolution of myelin allowed for the subsequent

---

[19] *glia* = glial cells; *oma* = tumor
[20] *neuri* = nerve; *lemma* = husk, peel, sheath
[21] L. A. Ranvier (1835–1922), French histologist and pathologist

DEEPER INSIGHT 13.2

Diseases of the Myelin Sheath

Multiple sclerosis and Tay–Sachs disease are degenerative disorders of the myelin sheath. In *multiple sclerosis*[22] *(MS),* the oligodendrocytes and myelin sheaths of the CNS deteriorate and are replaced by hardened scar tissue, especially between the ages of 20 and 40. Nerve conduction is disrupted with effects that depend on what part of the CNS is involved—numbness, double vision, blindness, speech defects, neurosis, or tremors. Patients experience variable cycles of milder and worse symptoms until they eventually become bedridden. The cause of MS remains uncertain; most hypotheses suggest that it is an *autoimmune disease*—a disorder in which one's immune system turns against one's own tissues—perhaps triggered by a virus in genetically susceptible individuals. There is no cure. There is conflicting evidence as to how much it shortens a patient's life expectancy, if at all. Some die within a year of diagnosis, but many people live with MS for 25 or 30 years.

Tay–Sachs[23] *disease* is a hereditary disorder seen mainly in infants of Eastern European Jewish ancestry. It results from the abnormal accumulation of a glycolipid called GM_2 (ganglioside) in the myelin sheath. GM_2 is normally decomposed by a lysosomal enzyme, but this enzyme is lacking from those who inherit the recessive Tay–Sachs gene from both parents. As GM_2 accumulates, it disrupts the conduction of nerve signals, and the victim typically suffers blindness, loss of coordination, and dementia. Signs begin to appear before the child is a year old and most victims die by the age of 3 or 4 years. Asymptomatic adult carriers can be identified by a blood test and advised by genetic counselors on the risk of their children having the disease.

evolution of more complex and responsive nervous systems with smaller, more energy-efficient neurons. Slow unmyelinated fibers are quite sufficient for processes in which quick responses are not particularly important, such as secreting stomach acid or dilating the pupil. Fast myelinated fibers are employed where speed is more important, as in motor commands to the skeletal muscles and sensory signals for vision and balance.

Schwann Cells and Nerve Regeneration

Nerve fibers in the peripheral nervous system are often damaged by cuts and other injuries, but if the cell body remains intact, an axon can often regenerate. Two things are required for regeneration of an axon: a neurilemma and an endoneurium. Both of these are lacking from the CNS, so damaged CNS nerve fibers cannot regenerate at all. However, since the CNS is encased in bone, it suffers less trauma than the PNS. In the PNS, Schwann cells of the neurilemma secrete *nerve growth factors* that stimulate regrowth of the axon, and the Schwann cells and endoneurium together form a **regeneration tube** that guides the growing axon to its destination, such as a muscle fiber. The axon grows down the middle of the tube and, if successful, it reestablishes synaptic contact with its target cell. The process is not perfect—some injured neurons fail to find the target cell, and some simply die. Nerve injuries therefore may leave a person with some loss of fine motor control. Even when regeneration is achieved, the slow rate of axon regrowth means that some nerve functions may take as long as 2 years to be restored.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

8. From memory, make your own table of the six kinds of glial cells and the functions of each. Which type has the most varied functions?
9. Summarize the major ways in which oligodendrocytes and Schwann cells differ in the way they produce a myelin sheath, and state where the glial cell body of each type is located relative to the myelin and nerve fiber.
10. Compare the signal conduction speed in myelinated fibers versus unmyelinated ones. Why aren't *all* nerve fibers in the body myelinated?
11. Explain why damaged nerve fibers in the PNS can regenerate but damaged fibers in the CNS cannot.

13.4 Synapses and Neural Circuits

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the synaptic junctions between one neuron and another;
b. describe the variety of interconnections that exist between two neurons; and
c. describe four basic variations in the circuitry or "wiring patterns" of the nervous system.

No neuron functions in isolation from others; neurons work in groups of cells that are connected in patterns similar to the electrical circuits of radios and other electronic devices. In this section, we examine the connections between neurons and the functional circuits of neuron groups.

Synapses

The meeting point between a neuron and any other cell is called a **synapse.** The other cell may be an epithelial, muscular, glandular, or other cell type, but in most cases it is another neuron. Synapses make *neural integration* (information processing) possible; each is a "decision-making" device that determines whether a second cell will respond to signals from the first. Without synapses, signals would simply be transmitted automatically from receptors to effectors, effectors would respond to every stimulus, and the nervous system would be incapable of any decision making. But in reality, one neuron can have an enormous number of synapses and thus a great deal of information-processing capability (fig. 13.9). For example, a spinal motor neuron receives about 8,000 synaptic contacts from other neurons on its dendrites and another 2,000 on its soma. In part of the brain called the cerebellum, one neuron can have as many as 100,000 synapses. The cerebral cortex (the main information-processing tissue of the brain) is estimated to have 100 trillion (10^{14}) synapses. To get some impression of this number, imagine trying to count them. Even if you could count two synapses per second, night and day without a coffee break, and you were immortal, it would take you 1.6 million years.

---

[22] *scler* = hard, tough; *osis* = condition

[23] Warren Tay (1843–1927), English physician; Bernard Sachs (1858–1944), American neurologist

A nerve signal arrives at a synapse by way of the **presynaptic neuron,** then may continue on its way via the **postsynaptic neuron** (fig. 13.10a). When a presynaptic axon ends at the dendrite of a postsynaptic neuron, the two cells are said to form an **axodendritic synapse.** When the presynaptic axon terminates on the soma of the next cell, they form an **axosomatic synapse.** When it terminates on the axon of the next cell, they form an **axoaxonic synapse** (fig. 13.10b).

Chemical Synapses and Neurotransmitters

A **chemical synapse** is a junction at which the presynaptic neuron releases a neurotransmitter to stimulate the postsynaptic cell. The neuromuscular junction (NMJ) described in chapter 10 (p. 248) is an example of this. The NMJ and many other synapses employ *acetylcholine* as a neurotransmitter. Postsynaptic neurons of the sympathetic nervous system use *norepinephrine.*

Some neurotransmitters are excitatory and tend to generate a nerve signal in the postsynaptic cell. Some widely used excitatory neurotransmitters in the central nervous system (CNS) are *glutamate* in the brain and *aspartate* in the spinal cord. Other neurotransmitters are inhibitory and suppress responses in the postsynaptic cell. The most widely used inhibitory neurotransmitters in the CNS are *gamma-aminobutyric acid (GABA)* in the brain and *glycine* in the spinal cord. Some other well-known neurotransmitters are *dopamine, serotonin, histamine,* and *beta-endorphin.* There are over 100 known neurotransmitters.

At a chemical synapse, the presynaptic terminal of one neuron is separated from the next cell by a 20 to 40 nm gap called the **synaptic cleft** (fig. 13.11). The presynaptic terminal contains membrane-bounded secretory vesicles called **synaptic vesicles,** which contain the neurotransmitter. Many of these vesicles are "docked" at release sites on the inside of the plasma membrane, ready to release their neurotransmitter on demand. A reserve pool of synaptic vesicles is located a little farther away from the membrane, clustered near the release sites and tethered to the cytoskeleton by protein microfilaments. These vesicles stand by and "step forward" to dock on the membrane and release their neurotransmitter after the previously docked vesicles have expended their contents. Synaptic vesicles are found in a few cells other than neurons, such as the sensory cells of taste, hearing, and equilibrium. They release neurotransmitter to stimulate a nearby nerve cell.

A postsynaptic neuron does not show such conspicuous specializations. At this end, a neuron has no synaptic vesicles and cannot release neurotransmitters. Its membrane does, however, contain proteins that function as neurotransmitter receptors, and it may be folded to increase its receptor-laden surface area and, therefore, its sensitivity to the neurotransmitter. A signal always travels in only one direction across a chemical synapse, from the presynaptic cell with synaptic vesicles to the postsynaptic cell with neurotransmitter receptors. This one-way transmission ensures the precise routing of nerve signals in the body.



© Omikron/Science Source

Figure 13.9 **Presynaptic Terminals on the Soma of a Neuron in a Marine Slug, *Aplysia* (SEM).**
• *To which of the three classes of synapses (compare fig. 13.10) would these belong?*



Figure 13.10 **Synaptic Relationships Between Neurons.** (a) Pre- and postsynaptic neurons. (b) Types of synapses defined by the site of contact on the postsynaptic neuron.


Microtubules of cytoskeleton
Axon of presynaptic neuron
Mitochondria
Postsynaptic neuron
Presynaptic terminal
Synaptic vesicles containing neurotransmitter
Synaptic cleft
Neurotransmitter receptor
Neurotransmitter release
Postsynaptic neuron

Figure 13.11 Structure of a Chemical Synapse.

Synaptic transmission begins when a nerve signal arrives at the end of the presynaptic neuron. Synaptic vesicles release neurotransmitter into the synaptic cleft, where it diffuses across to the postsynaptic cell and binds to receptors on that cell's membrane. Depending on the neurotransmitter and the type of receptor, this may either stimulate or inhibit the postsynaptic cell. The postsynaptic cell "decides" whether or not to initiate a new nerve signal based on the composite effects of excitatory and inhibitory input through the many synapses on its dendrites and soma. Therefore, a large number of presynaptic neurons may "get to vote" on whether the postsynaptic cell fires.

Apply What You Know

Of all the methods of membrane transport described in chapter 2, which one is the mechanism of neurotransmitter release?

Electrical Synapses

Another type of synapse, called an **electrical synapse,** connects some neurons, neuroglia, and cardiac and single-unit smooth muscle cells. Here, adjacent cells are joined by gap junctions that allow ions to diffuse directly from one cell into the next. These junctions have the advantage of quick transmission because there is no delay for the release and binding of neurotransmitter. Two disadvantages, however, are that they cannot integrate information and make decisions, and that signals can travel in either direction over an electrical synapse, so there is no way of directing signals to a specific destination.

Neural Pools and Circuits

Neurons function in ensembles called **neural pools.** One neural pool may consist of thousands to millions of interneurons concerned with a particular body function—one to control the rhythm of your breathing, one to move your limbs rhythmically as you walk, one to regulate your sense of hunger, and another to interpret smells, for example. The functioning of a neural pool hinges on the anatomical organization of its neurons, much like the functioning of a radio depends on the particular way its transistors, diodes, and capacitors are laid out. The interconnections between neurons are called **neural circuits.** A wide variety of



Figure 13.12 **Four Types of Neural Circuits.** Arrows indicate the direction of signal transmission.

neural functions result from the operation of four principal kinds of circuits (fig. 13.12):

1. In a **diverging circuit,** one nerve fiber branches and synapses with several postsynaptic cells. Each of those may synapse with several more, so input from just one neuron may produce output through dozens more. Such a circuit allows one motor neuron of the brain, for example, to ultimately stimulate thousands of muscle fibers.
2. A **converging circuit** is the opposite of a diverging circuit—input from many different sources is funneled to one neuron or neural pool. Through neural convergence, a respiratory center in the brainstem receives input from other parts of the brain, from receptors for blood chemistry in the arteries, and from stretch receptors in the lungs. The respiratory center can then produce an output that takes all of these factors into account and sets an appropriate pattern of breathing.
3. In a **reverberating circuit,** neurons stimulate each other in a linear sequence such as $A \rightarrow B \rightarrow C \rightarrow D$, but neuron *C* sends an axon collateral back to *A*. As a result, every time *C* fires, it not only stimulates output from neuron *D,* but also restimulates *A* and starts the process over. Such a circuit produces a repetitive output that lasts until one or more neurons in the circuit fail to fire or an inhibitory signal from another source stops one of them from firing. A reverberating circuit sends repetitious signals to the diaphragm and intercostal muscles, for example, to make you inhale. When the circuit stops firing, you exhale; the next time it fires, you inhale again. Reverberating circuits may also be involved in short-term memory (for example, in the way a telephone number "echoes" in your memory from the time you look it up in the phone book until the time you dial it). They may also play a role in the uncontrolled "storms" of neural activity that occur in epilepsy.
4. In a **parallel after-discharge circuit,** an input neuron diverges to stimulate several chains of neurons. Each chain has a different number of synapses, but eventually they all reconverge on the same output neuron. Each synapse delays a nerve signal by about 0.5 ms, so the more synapses there are in a pathway, the longer it takes a nerve signal to get through that pathway to the output neuron. The output neuron, receiving signals from multiple pathways, may go on firing for some time after the input has ceased. Unlike a reverberating circuit, this type has no feedback loop. Once all the neurons in the circuit have fired, the output ceases. Continued firing after the stimulus stops is called *after-discharge.* It explains why you can stare at a lamp, then close your eyes or turn the lamp off and continue to see an image of it for a while. Such a circuit is also important to certain reflexes—for example, when a brief pain produces a longer-lasting output to the limb muscles and causes you to draw back your hand or foot from danger. (See the discussion of *reflex arcs* in chapter 14, p. 392.)

Before You Go On

Answer the following questions to test your understanding of the preceding section:

12. At a given synapse, what features are present on the presynaptic neuron that are absent from the postsynaptic neuron?
13. In synaptic transmission, where does the neurotransmitter come from? How does it affect the postsynaptic neuron?

14. Name any four neurotransmitters and state some functional differences between them.
15. What is an electrical synapse? Where can electrical synapses be found? Identify an advantage and a disadvantage of an electrical synapse compared to a chemical synapse.
16. What is the difference between a neural pool and a neural circuit?
17. Name the four types of neural circuits and briefly describe the functional differences between them, or an advantage of each type for certain purposes.

13.5 Developmental and Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe how the nervous system develops in an embryo; and
b. describe a few birth defects that result from abnormalities of this developmental process.

Development of the Nervous System

Some aspects of nervous system development, or **neurulation,** were briefly discussed in chapter 4 (p. 91). Further understanding of this process will form a basis for understanding the brain and spinal cord anatomy presented in chapters 14 and 15.

The first embryonic trace of the central nervous system appears early in the third week of development. A dorsal streak called the *neuroectoderm* appears along the length of the embryo and thickens to form a **neural plate** (fig. 13.13). This is destined to give rise to most neurons and to all glial cells except microglia, which come from mesoderm. As development progresses, the neural plate sinks and the edges of it thicken, thus forming a **neural groove** with a raised **neural fold** along each side. The neural folds then fuse along the midline, somewhat like a closing zipper, beginning in the cervical (neck) region of the neural groove and progressing rostrally (toward the head) and caudally (toward the tail). By 4 weeks, this process creates a hollow channel called the **neural tube.** For a time, the neural tube is open to the amniotic fluid at the rostral and caudal ends. These openings close at 25 and 27 days, respectively. The lumen of the neural tube becomes a fluid-filled space that later constitutes the *central canal* of the spinal cord and *ventricles* of the brain.

Following closure, the neural tube separates from the overlying ectoderm, sinks a little deeper, and grows lateral processes that later give rise to motor nerve fibers. Some ectodermal cells that originally lay along the margin of the neural groove separate from



Figure 13.13 **Formation of the Neural Tube.** The left-hand figure in each case is a dorsal view of the embryo, and the right-hand figure is a three-dimensional representation of the tissues at the indicated level of the respective embryo. The ages are days after fertilization.


Telencephalon
Prosencephalon
Optic vesicle
Diencephalon
Mesencephalon
Metencephalon
Rhombencephalon
Myelencephalon
Spinal cord
(a) 4 weeks
(b) 5 weeks
Telencephalon
Diencephalon
Forebrain
Mesencephalon
Midbrain
Pons
Metencephalon
Cerebellum
Hindbrain
Myelencephalon
(medulla oblongata)
Spinal cord
(c) Fully developed

Figure 13.14 **Primary and Secondary Vesicles of the Embryonic Brain.** (a) The three primary vesicles at 4 weeks. (b) The secondary vesicles at 5 weeks. (c) The fully developed brain, color-coded to relate its structures to the secondary embryonic vesicles.

the rest and form a longitudinal column on each side called the **neural crest.** Neural crest cells give rise to most of the peripheral nervous system, including the sensory and autonomic nerves and ganglia; Schwann cells; the adrenal medulla (a gland described on p. 507); the two inner membranes *(meninges)* around the brain and spinal cord; melanocytes of the skin; the dermis; and some bones of the head and neck, as well as a few other structures.

By the fourth week, the neural tube exhibits three anterior bulges, or *primary vesicles,* called the **forebrain** *(prosencephalon*[24]*)* (PROSS-en-SEF-uh-lon), **midbrain** *(mesencephalon*[25]*)* (MEZ-en-SEF-uh-lon), and **hindbrain** *(rhombencephalon*[26]*)* (ROM-ben-SEF-uh-lon) (fig. 13.14). While these vesicles develop, the neural tube bends at the junction of the hindbrain and spinal cord to form the **cervical flexure,** and in the midbrain region to form the **cephalic flexure.**

By the fifth week, the neural tube undergoes further flexion and subdivides into five *secondary vesicles.* The forebrain divides into two of them, the **telencephalon**[27] (TEL-en-SEF-uh-lon) and **diencephalon**[28] (DY-en-SEF-uh-lon); the midbrain remains undivided and retains the name **mesencephalon;** and the hindbrain divides into two vesicles, the **metencephalon**[29] (MET-en-SEF-uh-lon) and **myelencephalon**[30] (MY-el-en-SEF-uh-lon). The telencephalon has a pair of lateral outgrowths that later become the *cerebral hemispheres,* and the diencephalon exhibits a pair of small cuplike *optic vesicles* that become the retinas of the eyes. Figure 13.14c shows structures of the fully developed brain that arise from each of the secondary vesicles.

---

[24] *pros* = before, in front; *encephal* = brain
[25] *mes* = middle
[26] *rhomb* = rhombus
[27] *tele* = end, remote
[28] *di* = through, between
[29] *met* = behind, beyond, distal to
[30] *myel* = spinal cord

In week 14, Schwann cells and oligodendrocytes begin spiraling around the nerve fibers, laying down layers of myelin and giving the fibers a white appearance. Yet very little myelin is present in the brain even at birth, and there is little visible distinction between the *gray matter* and *white matter* of the newborn brain. Myelination proceeds rapidly in infancy, and it is this, far more than the multiplication or enlargement of neurons, that accounts for most postnatal brain growth. Myelination is not completed until late adolescence. Since myelin has such a high lipid content, dietary fat is important to early nervous system development. Well-meaning parents can do their children significant harm by giving them the sort of low-fat diets (skimmed milk, etc.) that may be beneficial to an adult.

In the third month, the spinal cord extends for the full length of the embryo. As the vertebrae develop (see p. 177), *spinal nerves* arise from the cord and pass straight laterally to emerge between the vertebrae, through the intervertebral foramina. Subsequently, however, the vertebral column grows faster than the spinal cord. By birth, the cord ends in the vertebral canal of the third lumbar vertebra (L3), and by adulthood, it ends at the level of L1 to L2. As the vertebral column elongates, the spinal nerve roots elongate, so they still emerge between the same vertebrae, but the lower vertebral canal is occupied by a bundle of nerve roots instead of spinal cord. The resulting adult anatomy is described in chapter 14.

Developmental Disorders

The central nervous system is subject to multiple aberrations in embryonic development. Approximately 1 out of 100 live-born infants exhibit major defects in brain development. Common among these are **neural tube defects (NTDs)** such as **spina bifida** (SPY-nuh BIF-ih-duh). Spina bifida occurs when one or more vertebrae fail to form a complete neural arch for enclosure of the spinal cord. It is especially common in the lumbosacral region. The mildest form, *spina bifida occulta,*[31] involves only one to a few vertebrae and causes no functional problems. Its only external sign is a dimple or patch of hairy pigmented skin on the lower back. *Spina bifida cystica*[32] is more serious (fig. 13.15). A sac protrudes from the spine and may contain parts of the spinal cord and nerve roots, meninges, and cerebrospinal fluid. In extreme cases, inferior spinal cord function is absent, causing paralysis of the lower limbs and urinary bladder and lack of bowel control. Bladder paralysis can lead to chronic urinary infections and renal failure. Women can significantly reduce the risk of bearing a child with spina bifida by taking supplemental folic acid (a B vitamin). However, this works only if taken habitually even before the egg is fertilized; folic acid supplements are ineffective if begun after a woman realizes she is pregnant because by then, any neural tube damage will have already occurred. This is the reason that the U.S. Food and Drug Administration decided in 1996 to add folic acid to flour and other grain products, a policy that has resulted in a dramatic decrease in the incidence of neural tube defects.

---

[31] *bifid* = divided, forked; *occult* = hidden
[32] *cyst* = sac, bladder


© Biophoto Associates/Science Source

Figure 13.15 An Infant with Spina Bifida Cystica. The sac in the lumbar region is called a myelomeningocele.

Other severe neural tube defects include microcephaly and anencephaly. In **microcephaly,**[33] the face is of normal size but the brain and calvaria are abnormally small. Microcephaly is accompanied by profound mental retardation. **Anencephaly**[34] results from failure of the rostral end of the neural tube to close. This leaves the brain exposed to the amniotic fluid. The brain tissue degenerates, most of the brain is absent at birth, and the head is relatively flat or truncated above the eyes. Such infants generally die within a few hours. Neural tube defects sometimes run in families but can also be caused by teratogens and nutritional deficiencies.

Other disorders of the nervous system are described in chapters 14 through 17.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

18. How does the neural crest originate? What cells or tissues arise from it?
19. Where does closure of the neural tube begin? What are the last regions to close?
20. What single adult structure arises from all five of the secondary vesicles of the neural tube?
21. When does myelination begin? When does it end?

---

[33] *micro* = small; *cephal* = head
[34] *an* = without; *encephal* = brain

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

13.1 Overview of the Nervous System (p. 352)

1. The body's two principal mechanisms of internal communication and coordination, and how they differ from each other
2. The constituents of the central nervous system (CNS) and peripheral nervous system (PNS)
3. The two divisions of the PNS and the two subdivisions of each of those, including the types of organs innervated by each subdivision
4. The autonomic nervous system, its effectors, and its two subdivisions

13.2 Nerve Cells (Neurons) (p. 353)

1. The three properties that any neuron must have to perform its function
2. The three functional classes of neurons: sensory neurons, interneurons, and motor neurons; how each is defined; and synonyms for sensory and motor neurons
3. The parts of a typical neuron
4. The four types of neurons distinguished by the number of processes that arise from the neurosoma

13.3 Supportive Cells (Neuroglia) (p. 357)

1. The meaning of *neuroglia (glial cells)* and the general purpose of the neuroglia
2. The four kinds of neuroglia found in the CNS, and their respective functions
3. The two kinds of neuroglia found in the PNS, and their respective functions
4. The structure, composition, and function of the myelin sheath; how the CNS and PNS differ with respect to the glial cells that produce their myelin; and how the two glial types do so
5. The relationship of Schwann cells to the myelin, neurilemma, basal lamina, and endoneurium
6. Why the myelin sheath consists of short internodes interrupted by nodes of Ranvier, rather than one continuous sheath
7. The roles of Schwann cells in relation to unmyelinated nerve fibers
8. How the velocity of a nerve signal varies with a nerve fiber's diameter and presence or absence of myelin
9. The necessity of the neurilemma and endoneurium for the regeneration of damaged nerve fibers; the role that they play in regeneration; and why damaged nerve fibers in the CNS cannot regenerate

13.4 Synapses and Neural Circuits (p. 361)

1. The definition of *synapse* and the function of synapses
2. How the presynaptic and postsynaptic neurons are defined at a given synapse
3. Three types of synapses defined by where the presynaptic nerve fiber ends on the postsynaptic neuron
4. The defining qualities of a chemical synapse
5. The names of several familiar neurotransmitters
6. The two types of effects that a neurotransmitter can have on a postsynaptic neuron
7. The mechanism of signal transmission across a synapse by a neurotransmitter
8. How the plasma membrane of the postsynaptic neuron differs from that of the presynaptic neuron at a synapse
9. Where electrical synapses can be found, and how they differ structurally and functionally from chemical synapses
10. The meaning of *neural pool* and some functions performed by neural pools
11. The four principal types of neural circuits—diverging, converging, reverberating, and parallel after-discharge circuits—and how they differ in function; some everyday scenarios that involve the activity of these different types of neural circuits

13.5 Developmental and Clinical Perspectives (p. 365)

1. The embryonic progression from a neural plate to a neural tube
2. The origin, location, and fate of the neural crest
3. Expansion of the neural tube into three primary vesicles, and their names; their further differentiation into five secondary vesicles, and their names; and the fate of each of the five secondary vesicles
4. The timetable of prenatal and postnatal myelination
5. The developmental explanation for why the adult spinal cord reaches only as far as the first or second lumbar vertebra
6. The meaning of *neural tube defects;* their causes; the defining attributes of spina bifida occulta, spina bifida cystica, microcephaly, and anencephaly; and what can be done to minimize the risk of neural tube defects

Testing Your Recall

1. The integrative functions of the nervous system are performed mainly by
   a. afferent neurons.
   b. efferent neurons.
   c. neuroglia.
   d. sensory neurons.
   e. interneurons.
2. Neurons arise from embryonic
   a. endoderm.
   b. epidermis.
   c. mesoderm.
   d. mesenchyme.
   e. ectoderm.
3. The soma of a mature neuron lacks
   a. a nucleus.
   b. endoplasmic reticulum.
   c. lipofuscin.
   d. centrioles.
   e. ribosomes.
4. The glial cells that destroy microorganisms in the CNS are
   a. microglia.
   b. satellite cells.
   c. ependymal cells.
   d. oligodendrocytes.
   e. astrocytes.
5. A friend takes a flash photograph of you, and you continue to see an image of the flash unit for several seconds afterward. This phenomenon is the result of a _____ circuit.
   a. diverging
   b. converging
   c. presynaptic
   d. reverberating
   e. parallel after-discharge
6. Neurotransmitters are found in
   a. the cell bodies of neurons.
   b. the dendrites.
   c. the axon hillock.
   d. the presynaptic terminal.
   e. the postsynaptic plasma membrane.
7. Another name for the axon of a neuron is
   a. nerve fiber.
   b. neurofibril.
   c. neurilemma.
   d. axoplasm.
   e. endoneurium.
8. Nerves that directly control the motility of the stomach or rate of the heartbeat would belong to
   a. the central nervous system.
   b. the somatic sensory division.
   c. the somatic motor division.
   d. the visceral motor division.
   e. the visceral sensory division.
9. The glial cells that guide migrating neurons in the developing fetal brain are
   a. astrocytes.
   b. oligodendrocytes.
   c. satellite cells.
   d. ependymal cells.
   e. microglia.
10. Which of the following appears earlier than all the rest in prenatal development of the nervous system?
    a. the neural groove
    b. a pair of primary vesicles
    c. the neural plate
    d. the neural crest
    e. the neural tube
11. Neurons that convey information to the CNS are called sensory, or _____, neurons.
12. Motor effects that depend on repetitive output from a neural pool are most likely to use the _____ type of neural circuit.
13. Prenatal degeneration of the forebrain results in a birth defect called _____.
14. Neurons receive incoming signals by way of specialized processes called _____.
15. In the central nervous system, cells called _____ perform one of the same functions that Schwann cells do in the peripheral nervous system.
16. A/An _____ synapse is formed when a presynaptic neuron synapses with the cell body of a postsynaptic neuron.
17. All of the nervous system except the brain and spinal cord is called the _____.
18. The _____ and _____ are necessary for regeneration of damaged nerve fibers in the peripheral nervous system.
19. In the peripheral nervous system, the somas of the neurons are concentrated in enlarged, knotlike structures called _____ connected to the nerves.
20. At a given synapse, the _____ neuron has neurotransmitter receptors.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. -ic
2. somato-
3. neuro-
4. lipo-
5. dendro-
6. -ite
7. pseudo-
8. oligo-
9. fer-
10. sclero-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. Adult neurons are incapable of mitosis.
2. Most neurons have more dendrites than axons.
3. Dendrites never contain synaptic vesicles.
4. Interneurons connect sense organs to the CNS.
5. Nerve signals travel faster in myelinated nerve fibers than in unmyelinated ones.
6. The myelin sheath covers the neurilemma of a nerve fiber.
7. Nodes of Ranvier are present only in myelinated fibers of the PNS.
8. Interneurons occur in the brain and spinal cord of the CNS and in ganglia of the PNS.
9. Unipolar neurons cannot produce action potentials because they have no axon.
10. There are more glial cells than neurons in the nervous system.

Answers in appendix A

Testing Your Comprehension

1. Suppose some hypothetical disease prevented the formation of astrocytes in the fetal brain. How would you expect this to affect brain development?
2. How would nervous system function be affected if both the presynaptic and postsynaptic neurons at every synapse had both synaptic vesicles and neurotransmitter receptors?
3. What unusual characteristic of neurons can be attributed to their lack of centrioles?
4. When you cut your finger, the pain signals are conducted to the CNS by unipolar sensory neurons whose somas are near the spinal cord, amid the vertebrae. Suggest a good reason for the somas to be there, instead of in the skin closer to the origin of the pain.
5. State what division or subdivision of the peripheral nervous system would control each of the following: constriction of the pupils in bright light; the movements of your hand as you write; the sensation of a stomachache; blinking as a particle of dust is blown toward your eye; your awareness of the position of your hand as you touch your nose with your eyes closed. Briefly explain each answer.


Cross section of a nerve showing parts of two fascicles of nerve fibers (maroon)

© Ed Reschke/Getty Images

CHAPTER

14

THE NERVOUS SYSTEM II

SPINAL CORD AND SPINAL NERVES

CHAPTER OUTLINE

14.1 The Spinal Cord 372
- Functions 372
- Surface Anatomy 372
- Spinal Meninges—Protective Membranes 373
- Cross-Sectional Anatomy 375
- Spinal Tracts 375

14.2 The Spinal Nerves 379
- General Anatomy of Nerves and Ganglia 380
- Spinal Nerves 382
- Nerve Plexuses 385
- Cutaneous Innervation and Dermatomes 391

14.3 Somatic Reflexes 391

14.4 Clinical Perspectives 393

Study Guide 395

DEEPER INSIGHTS

14.1 Spinal Taps 375
14.2 Poliomyelitis and Amyotrophic Lateral Sclerosis 380
14.3 Shingles 384
14.4 Nerve Injuries 388

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:

- Divisions of the nervous system (p. 352)
- Functional classes of neurons (p. 354)
- Embryonic development of the CNS (p. 365)

Anatomy & Physiology REVEALED
aprevealed.com

Module 7: Nervous System

The spinal cord is the "information highway" that connects the brain with the lower body. Below the neck, nearly all intentional muscle movements rely on signals that travel down the spinal cord to neurons that innervate the muscles, and the sensory information that enters our conscious awareness travels up the cord to the brain. Injuries to the spinal cord can thus leave one partially or completely paralyzed, unaware of stimulation of the lower body, or both—with devastating effects on one's quality of life. The treatment of spinal cord injuries is one of the most lively areas of medical research today. Therapists who treat spinal patients must know spinal cord anatomy and function to understand their patients' deficits and prospects for improvement, and to carry out an appropriate regimen of treatment.

In this chapter, we will study not only the spinal cord but also the spinal nerves that arise from it with ladderlike regularity at intervals along its length. Thus, we will examine components of both the central and peripheral nervous systems, but these are so closely related structurally and functionally that it is appropriate to consider them together. Similarly, the brain and cranial nerves will be considered together in the following chapter. These two chapters therefore elevate our study of the nervous system from the cellular level (chapter 13) to the organ and system levels.

14.1 The Spinal Cord

Expected Learning Outcomes

When you have completed this section, you should be able to

a. enumerate the functions of the spinal cord;
b. describe the surface and cross-sectional anatomy of the cord;
c. explain the difference between the gray and white matter of the cord; and
d. identify the major pathways (tracts) that conduct signals up and down the spinal cord, and identify the types of signals they carry.

Functions

The spinal cord serves four principal functions:

1. **Conduction.** The spinal cord contains bundles of nerve fibers that conduct information up and down the body, connecting different levels of the trunk with each other and with the brain. It enables sensory information to reach the brain, motor commands to reach the muscles and other effectors, and input received at one level of the cord to affect output from another level.
2. **Neural integration.** Pools of spinal neurons receive input from multiple sources, integrate the information, and execute an appropriate output. For example, the spinal cord integrates stretch signals from a full bladder with cerebral input concerning the appropriate time and place to urinate, and executes control of the bladder accordingly.
3. **Locomotion.** Walking involves repetitive, coordinated contractions of several muscle groups in the limbs. Motor neurons in the brain initiate walking and determine its speed, distance, and direction, but the simple repetitive muscle contractions that put one foot in front of another, over and over, are coordinated by groups of neurons called **central pattern generators** in the cord. These neural circuits produce the sequence of outputs to the extensor and flexor muscles that cause alternating movements of the lower limbs.
4. **Reflexes.** Reflexes are involuntary stereotyped responses to stimuli. They involve the brain, spinal cord, and peripheral nerves.

Surface Anatomy

The **spinal cord** (fig. 14.1) is a cylinder of nervous tissue that arises from the brainstem at the foramen magnum of the skull. It passes down the vertebral canal as far as the inferior margin of the first lumbar vertebra (L1) or slightly beyond. In adults, it averages about 45 cm long and 1.8 cm thick—about as thick as one's little finger. It occupies only the upper two-thirds of the vertebral canal; the lower one-third is described shortly. The cord exhibits longitudinal grooves on its anterior and posterior sides—the *anterior median fissure* and *posterior median sulcus,* respectively.

The cord gives rise to 31 pairs of spinal nerves. Although the spinal cord is not visibly segmented, the part supplied by each pair of spinal nerves is called a *segment.*

The spinal cord is divided into **cervical, thoracic, lumbar,** and **sacral regions.** It may seem odd that it has a sacral region when the cord itself ends well above the sacrum. These regions, however, are named for the level of the vertebral column from which the spinal nerves emerge, not for the vertebrae that contain the cord itself.

The cord widens at two points along its course: a **cervical enlargement** in the inferior cervical region, where it gives rise to nerves of the upper limbs; and a similar **lumbar enlargement** in the lumbosacral region, where it gives rise to nerves of the pelvic region and lower limbs. Inferior to the lumbar enlargement, the cord tapers to a point called the **medullary cone (conus medullaris).** The lumbar enlargement and medullary cone give off a bundle of nerve roots that occupy the vertebral canal from L2 to S5. This bundle, named the **cauda equina**[1] (CAW-duh ee-KWY-nah) for its resemblance to a horse's tail, innervates the pelvic organs and lower limbs.

---

[1] *cauda* = tail; *equin* = horse


C1
Cervical enlargement
Cervical spinal nerves
C7
Dural sheath
Subarachnoid space
Thoracic spinal nerves
Lumbar enlargement
T12
Medullary cone
Cauda equina
Lumbar spinal nerves
L5
Terminal filum
Sacral spinal nerves
S5
Co1
(a)
Spinal cord
Vertebra (cut)
Spinal nerve
Spinal nerve rootlets
Posterior median sulcus
Subarachnoid space
Epidural space
Posterior root ganglion
Rib
Arachnoid mater
Dura mater
(b)

Figure 14.1 **The Spinal Cord (Posterior View).** (a) Overview of spinal cord structure. (b) Detail of the spinal cord and associated nerves, meninges, and vertebrae. APR

Apply What You Know

Spinal cord injuries commonly result from fractures of vertebrae C5 to C6 (a "broken neck"), but never from fractures of L3 to L5. Explain both observations.

Spinal Meninges—Protective Membranes

The spinal cord and brain are enclosed in three membranes called **meninges** (meh-NIN-jeez)—singular, *meninx*[2] (MEN-inks). These membranes separate the soft tissue of the central nervous system from the bones of the vertebrae and skull. From superficial to deep, they are the dura mater, arachnoid mater, and pia mater (fig. 14.2).

The **dura mater**[3] (DOO-ruh MAH-tur) forms a loose-fitting sleeve called the **dural sheath** around the spinal cord. It is a tough collagenous membrane about as thick as a rubber kitchen glove. The space between the sheath and vertebral bones, called the **epidural space,** is occupied by blood vessels, adipose tissue, and loose connective tissue (fig. 14.2a). Anesthetics are sometimes introduced to this space to block pain signals during childbirth or surgery; this procedure is called *epidural anesthesia.*

---

[2] *menin* = membrane

[3] *dura* = tough; *mater* = mother, womb


Posterior
Spinous process of vertebra
Fat in epidural space
Subarachnoid space
Spinal cord
Denticulate ligament
Posterior root ganglion
Spinal nerve
Vertebral body
Meninges:
Dura mater (dural sheath)
Arachnoid mater
Pia mater
Anterior

(a) Spinal cord and vertebra (cervical)


Gray matter:
Posterior horn
Gray commissure
Lateral horn
Anterior horn
Central canal
Posterior median sulcus
White matter:
Posterior column
Lateral column
Anterior column
Posterior root of spinal nerve
Posterior root ganglion
Spinal nerve
Anterior root of spinal nerve
Anterior median fissure
Meninges:
Pia mater
Arachnoid mater
Dura mater (dural sheath)

© Ed Reschke/Getty Images

(b) Spinal cord and meninges (thoracic) **(c) Lumbar spinal cord**

Figure 14.2 **Cross-Sectional Anatomy of the Spinal Cord.** (a) Relationship to the vertebra, meninges, and spinal nerve. (b) Detail of the spinal cord, meninges, and spinal nerves. (c) Cross section of the lumbar spinal cord with spinal nerves.

The **arachnoid**[4] (ah-RACK-noyd) **mater** consists of a simple squamous epithelium, the *arachnoid membrane,* adhering to the inside of the dura, and a loose mesh of collagenous and elastic fibers spanning the gap between the arachnoid membrane and the pia mater. This gap, called the **subarachnoid space,** is filled with cerebrospinal fluid (CSF), a clear liquid discussed on p. 404. Inferior to the medullary cone, the subarachnoid space is called the **lumbar cistern** and is occupied by the cauda equina and CSF (see Deeper Insight 14.1).

The **pia**[5] (PEE-uh) **mater** is a delicate, translucent membrane that closely follows the contours of the spinal cord. It continues

---

[4] *arachn* = spider, spider web; *oid* = resembling

[5] *pia* = through mistranslation, now construed as tender, soft

DEEPER INSIGHT 14.1

Spinal Taps

Several neurological diseases are diagnosed in part by examining cerebrospinal fluid for bacteria, blood, white blood cells, or abnormalities of chemical composition. CSF is obtained by a procedure called a *spinal tap,* or *lumbar puncture.* The patient leans forward or lies on one side with the spine flexed, thus spreading the vertebral laminae and spinous processes apart. The skin over the lumbar vertebrae is anesthetized, and a needle is inserted between the spinous processes of L3 and L4 (sometimes L4 and L5). This is the safest place to obtain CSF because the spinal cord does not extend this far and is not exposed to injury by the needle. At a depth of 4 to 6 cm, the needle punctures the dura mater and enters the lumbar cistern. CSF normally drips out at a rate of about 1 drop per second. A lumbar puncture is not performed if a patient has signs of high intracranial pressure, because the sudden release of pressure (causing CSF to jet from the puncture) can cause fatal herniation of the brainstem and cerebellum into the vertebral canal.

beyond the medullary cone as a fibrous strand, the *terminal filum,* forming part of the **coccygeal ligament** that anchors the cord to the coccyx. At regular intervals along the cord, extensions of the pia called **denticulate ligaments** extend through the arachnoid to the dura, anchoring the cord and limiting side-to-side movements.

Cross-Sectional Anatomy

Figure 14.2 shows the relationship of the spinal cord to a vertebra and the spinal nerves. The spinal cord, like the brain, consists of two kinds of nervous tissue called gray and white matter. **Gray matter** has a relatively dull color because it contains little myelin. It contains the somas, dendrites, and proximal parts of the axons of neurons. It is the site of synaptic contact between neurons and therefore the site of all synaptic integration (information processing) in the central nervous system. **White matter** contains an abundance of myelinated axons, which give it a bright, pearly white appearance. It is composed of bundles of axons, called **tracts,** that carry signals from one part of the CNS to another. In silver-stained nervous tissue sections, gray matter tends to have a brown or golden color and white matter a lighter tan to yellow color.

Gray Matter

The spinal cord has a central core of gray matter that looks somewhat butterfly- or H-shaped in cross sections. The core consists mainly of two **posterior (dorsal) horns,** which extend to the posterolateral surfaces of the cord, and two wider **anterior (ventral) horns,** which extend toward the anterolateral surfaces. The right and left sides are connected by a **gray commissure.** In the middle of the commissure is the **central canal,** which is collapsed in most areas of the adult spinal cord, but in some places (and in young children) remains open, lined with ependymal cells, and filled with CSF. The canal is a remnant of the lumen of the embryonic neural tube (see p. 365).

Near its attachment to the spinal cord, a spinal nerve branches into a *posterior root* and *anterior root.* The posterior root carries sensory nerve fibers, which enter the posterior horn of the cord and sometimes synapse with an interneuron there. Such interneurons are especially numerous in the cervical and lumbar enlargements and are quite evident in histological sections at these levels. The anterior horns contain the large somas of the somatic motor neurons. Axons from these neurons exit by way of the anterior root of the spinal nerve and lead to the skeletal muscles. The spinal nerve roots are described more fully later in this chapter.

In the thoracic and lumbar regions, an additional **lateral horn** is visible on each side of the gray matter. It contains neurons of the sympathetic nervous system, which send their axons out of the cord by way of the anterior root along with the somatic efferent fibers.

White Matter

The white matter of the spinal cord surrounds the gray matter. It consists of bundles of axons that course up and down the cord and provide avenues of communication between different levels of the CNS. These bundles are arranged in three pairs called **columns,** or **funiculi**[6] (few-NIC-you-lie)—a **posterior (dorsal), lateral,** and **anterior (ventral) column** on each side. Each column consists of subdivisions called **tracts,** or **fasciculi**[7] (fah-SIC-you-lye).

Spinal Tracts

Knowledge of the locations and functions of the spinal tracts is essential in diagnosing and managing spinal cord injuries. **Ascending tracts** carry sensory information up the cord and **descending tracts** conduct motor impulses down. All nerve fibers in a given tract have a similar origin, destination, and function. Many of these fibers have their origin or destination in a region called the *brainstem.* Described more fully in chapter 15 (see fig. 15.6, p. 407), this is a vertical stalk that supports the large *cerebellum* at the rear of the head and, even larger, two globes called the *cerebral hemispheres* that dominate the brain. In the following discussion, you will find references to brainstem and other regions where the spinal cord tracts begin and end. Spinal cord anatomy will grow in meaning when you study the brain.

Several of these tracts undergo **decussation**[8] (DEE-cuh-SAY-shun) as they pass up or down the brainstem and spinal cord—meaning that they cross over from the left side of the body to the right, or vice versa. As a result, the left side of the brain receives sensory information mainly from the right side of the body and sends its motor commands to that side, whereas the right side of the brain senses and controls mainly the left side of the body. A stroke that damages motor centers of the right side of the brain can therefore cause paralysis of the left limbs, and vice versa. When the origin and destination of a tract are on opposite sides of the body, we say they are **contralateral**[9] to each other. When a tract does not decussate, so the origin and destination of its fibers are on the same side of the body, we say they are **ipsilateral.**[10]

---

[6] *funicul* = little rope, cord
[7] *fascicul* = little bundle
[8] *decuss* = to cross, form an X
[9] *contra* = opposite; *later* = side
[10] *ipsi* = the same; *later* = side

TABLE 14.1 Major Spinal Tracts

Tract	Column	Decussation	Functions
Ascending (Sensory) Tracts			
Gracile fasciculus	Posterior	In medulla	Sensations of limb and trunk position and movement, deep discriminative touch, vibration, and visceral pain, below level T6
Cuneate fasciculus	Posterior	In medulla	Same as gracile fasciculus, but from level T6 up
Spinothalamic	Lateral and anterior	In spinal cord	Sensations of light touch, tickle, itch, temperature, pain, and pressure
Spinoreticular	Lateral and anterior	In spinal cord (some fibers)	Sensation of pain from tissue injury
Posterior spinocerebellar	Lateral	None	Feedback from muscles (proprioception)
Anterior spinocerebellar	Lateral	In spinal cord	Same as posterior spinocerebellar
Descending (Motor) Tracts			
Lateral corticospinal	Lateral	In medulla	Fine control of limbs
Anterior corticospinal	Anterior	In spinal cord	Fine control of limbs
Tectospinal	Anterior	In midbrain	Reflexive head-turning in response to visual and auditory stimuli
Lateral reticulospinal	Lateral	None	Balance and posture; regulation of awareness of pain
Medial reticulospinal	Anterior	None	Same as lateral reticulospinal
Lateral vestibulospinal	Anterior	None	Balance and posture
Medial vestibulospinal	Anterior	In medulla (some fibers)	Control of head position


Ascending tracts
Descending tracts
Posterior column:
Gracile fasciculus
Cuneate fasciculus
Posterior spinocerebellar tract
Anterior spinocerebellar tract
Anterolateral system (containing spinothalamic and spinoreticular tracts)
Anterior corticospinal tract
Lateral corticospinal tract
Lateral reticulospinal tract
Tectospinal tract
Medial reticulospinal tract
Lateral vestibulospinal tract
Medial vestibulospinal tract

Figure 14.3 Tracts of the Spinal Cord. All of the illustrated tracts occur on both sides of the cord, but only the ascending sensory tracts are shown on the left (red), and only the descending motor tracts on the right (green).

- *Suppose you were told that this is a cross section either at level T4 or T10. After you have finished reading section 14.1, explain how you could determine which is correct.*

The major spinal cord tracts are summarized in table 14.1 and figure 14.3. Bear in mind that each tract is repeated on the right and left sides of the spinal cord.

Ascending Tracts

Ascending tracts carry sensory signals up the spinal cord. Sensory signals typically travel across three neurons from their origin in the receptors to their destination in the sensory areas of the brain: a **first-order neuron** that detects a stimulus and conducts a signal to the spinal cord or brainstem; a **second-order neuron** that continues as far as a "gateway" called the *thalamus* at the upper end of the brainstem; and a **third-order neuron** that carries the signal the rest of the way to the sensory region of the cerebral cortex, the level of consciousness. The axons of these neurons are called the *first*- through *third-order nerve fibers.* Variations on this pattern will be noted for some of the sensory systems to follow.

The major ascending tracts are as follows. Other than the first two, their names consist of the prefix *spino*- followed by a root denoting the destination of their fibers in the brain.

- The **gracile**[11] **fasciculus** (GRAS-el fah-SIC-you-lus) (fig. 14.4a) carries signals from the midthoracic and lower parts of the body. Below vertebra T6, it composes the entire

---

[11] *gracil* = thin, slender


Somatosensory cortex (postcentral gyrus)
Third-order neuron
Thalamus
Cerebrum
Midbrain
Medial lemniscus
Second-order neuron
Gracile nucleus
Cuneate nucleus
Medulla
Medial lemniscus
First-order neuron
Gracile fasciculus
Cuneate fasciculus
Spinal cord
Receptors for body movement, limb positions, fine touch discrimination, and pressure
(a)
Somatosensory cortex (postcentral gyrus)
Third-order neuron
Thalamus
Cerebrum
Midbrain
Second-order neuron
Medulla
Spinothalamic tract
Spinal cord
First-order neuron
Anterolateral system
Receptors for pain, heat, and cold
(b)

Figure 14.4 Some Ascending Tracts of the CNS. The spinal cord, medulla oblongata, and midbrain are shown in cross section and the cerebrum and thalamus (top) in frontal section. Nerve signals enter the spinal cord at the bottom of the figure and carry somatosensory information to the cerebral cortex at the top. (a) The cuneate fasciculus and medial lemniscus. (b) The spinothalamic tract.

• *On the basis of this figure, explain why the* right *cerebral hemisphere perceives heat and cold on the* left *side of the body. What is the name of the phenomenon that accounts for this transmission of sensory information from one side of the body to the opposite side of the brain?*

posterior column. At T6, it is joined by the cuneate fasciculus, discussed next. The gracile fasciculus consists of first-order nerve fibers that travel up the ipsilateral side of the spinal cord and terminate at the *gracile nucleus* in the medulla oblongata of the brainstem. These fibers carry signals for vibration, visceral pain, deep and discriminative touch (touch whose location one can precisely identify), and especially *proprioception*[12] from the lower limbs and lower trunk. (Proprioception is the nonvisual sense of the position and movements of the body.)
- The **cuneate**[13] (CUE-nee-ate) **fasciculus** (fig. 14.4a) joins the gracile fasciculus at the T6 level. It occupies the lateral portion of the posterior column and forces the gracile fasciculus medially. It carries the same type of sensory signals, originating from level T6 and up (from the upper limb and chest). Its fibers end in the *cuneate nucleus* on the ipsilateral side of the medulla oblongata. In the medulla, second-order fibers of the gracile and cuneate systems decussate and form the **medial lemniscus**[14] (lem-NIS-cus), a tract of nerve fibers that leads the rest of the way up the brainstem to the contralateral thalamus. Third-order fibers go from the thalamus to the cerebral cortex. Because of decussation, the signals carried by the right gracile and cuneate fasciculi ultimately go to the left cerebral hemisphere, and vice versa.
- The **spinothalamic** (SPY-no-tha-LAM-ic) **tract** (fig. 14.4b) and some smaller tracts form the *anterolateral system,* which passes up the anterior and lateral columns of the spinal cord. The spinothalamic tract carries signals for pain, temperature, pressure, tickle, itch, and light or crude touch. Light touch is the sensation produced by stroking hairless skin with a feather or cotton wisp, without indenting the skin; crude touch is touch whose location one can only vaguely identify. In this pathway, first-order neurons end in the posterior horn of the spinal cord near the point of entry. Here they synapse with second-order neurons, which decussate to the opposite side of the spinal cord and form the ascending spinothalamic tract. These fibers lead all the way to the thalamus. Third-order neurons continue from there to the cerebral cortex. Because of its decussation, the spinothalamic tract ultimately sends its signals to the contralateral cerebral hemisphere.
- The **spinoreticular tract** also travels up the anterolateral system. It carries pain signals resulting from tissue injury. The first-order sensory neurons enter the posterior horn and immediately synapse with second-order neurons. These decussate to the opposite anterolateral system, ascend the cord, and end in a loosely organized core of gray matter called the *reticular formation* in the medulla and pons. Third-order neurons continue from the pons to the thalamus, and fourth-order neurons complete the path from there to the cerebral cortex. The reticular formation is further described in chapter 15, and the role of the spinoreticular tract in pain sensation is further discussed in chapter 17.
- The **posterior** and **anterior spinocerebellar** (SPY-no-SERR-eh-BEL-ur) **tracts** travel through the lateral column and carry proprioceptive signals from the limbs and trunk to the cerebellum, a large motor control area at the rear of the brain. The first-order neurons of this system originate in the muscles and tendons and end in the posterior horn of the spinal cord. Second-order neurons send their fibers up the spinocerebellar tracts and end in the cerebellum. Fibers of the posterior tract travel up the ipsilateral side of the spinal cord. Those of the anterior tract cross over and travel up the contralateral side but then cross back in the brainstem to enter the ipsilateral side of the cerebellum. Both tracts provide the cerebellum with feedback needed to coordinate muscle action, as discussed in chapter 15.

Descending Tracts

Descending tracts carry motor signals down the brainstem and spinal cord. A descending motor pathway typically involves two neurons called the upper and lower motor neurons. The **upper motor neuron** begins with a soma in the cerebral cortex or brainstem and has an axon that terminates on a **lower motor neuron** in the brainstem or spinal cord. The axon of the lower motor neuron then leads the rest of the way to the muscle or other target organ. The names of most descending tracts consist of a word root denoting the point of origin in the brain, followed by the suffix *-spinal.* The major descending tracts are described here.

- The **corticospinal** (COR-tih-co-SPY-nul) **tracts** carry motor signals from the cerebral cortex for precise, finely coordinated limb movements. The fibers of this system form ridges called *pyramids* on the anterior surface of the medulla oblongata, so these tracts were once called *pyramidal tracts.* Most corticospinal fibers decussate in the lower medulla and form the **lateral corticospinal tract** on the contralateral side of the spinal cord. A few fibers remain uncrossed and form the **anterior corticospinal tract** on the ipsilateral side (fig. 14.5). Fibers of the anterior tract decussate lower in the spinal cord, however, so even they control contralateral muscles. This tract gets smaller as it descends, giving off fibers to the upper body, and it usually disappears by midthoracic level.
- The **tectospinal** (TEC-toe-SPY-nul) **tract** begins in a midbrain region called the *tectum* and crosses to the contralateral side of the midbrain. It descends through the brainstem to the upper spinal cord on that side, going only as far as the neck. It is involved in reflex turning of the head, especially in response to sights and sounds.
- The **lateral** and **medial reticulospinal** (reh-TIC-you-lo-SPY-nul) **tracts** originate in the reticular formation. They control muscles of the upper and lower limbs, especially to maintain posture and balance. They also contain *descending analgesic fibers* that reduce the transmission of pain signals to the brain (see p. 466).
- The **lateral** and **medial vestibulospinal** (vess-TIB-you-lo-SPY-nul) **tracts** begin in the brainstem *vestibular nuclei,* which receive impulses for balance from the inner ear. The lateral vestibulospinal tract passes down the anterior column

---

[12] *proprio* = one's own; *cept* = receive, sense
[13] *cune* = wedge
[14] *lemniscus* = ribbon


Motor cortex
(precentral gyrus)
Internal capsule
Cerebrum
Midbrain
Cerebral peduncle
Upper motor neurons
Medulla
Medullary pyramid
Decussation in medulla
Lateral corticospinal tract
Spinal cord
Anterior corticospinal tract
Decussation in spinal cord
Spinal cord
Lower motor neurons
To skeletal muscles

Figure 14.5 **Two Descending Tracts of the CNS.** The anterior and lateral corticospinal tracts, which carry signals for voluntary muscle contraction. Nerve signals originate in the cerebral cortex at the top of the figure and carry motor commands down the spinal cord. Pathways shown at the bottom right are duplicated on the left.

of the spinal cord and facilitates neurons that control the extensor muscles of the limbs, thus inducing the limbs to stiffen and straighten. This is an important reflex in responding to body tilt and keeping one's balance. The medial vestibulospinal tract splits into ipsilateral and contralateral fibers that descend through the anterior column on both sides of the spinal cord and terminate in the neck. It plays a role in the control of head position.

Rubrospinal tracts are prominent in other mammals, where they aid in muscle coordination. Although often pictured in illustrations of supposedly human anatomy, they are almost nonexistent in humans and have little functional importance.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. Name the four major regions and two enlargements of the spinal cord.
2. Describe the distal (inferior) end of the spinal cord and the contents of the vertebral canal from level L2 through S5.
3. Sketch a cross section of the spinal cord showing the posterior and anterior horns. Where are the gray and white matter? Where are the columns and tracts?
4. Give an anatomical explanation as to why a stroke in the right cerebral hemisphere can paralyze the limbs on the left side of the body.
5. Identify each of the following spinal tracts with respect to whether it is ascending or descending; its origin and destination; and what sensory or motor purpose it serves: the lateral corticospinal, lateral reticulospinal, and spinothalamic tracts, and gracile fasciculus.

14.2 The Spinal Nerves

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the anatomy of nerves and ganglia in general;
b. describe the attachment of a spinal nerve to the spinal cord;
c. trace the branches of a generalized spinal nerve distal to its attachment;
d. name the five plexuses of spinal nerves and describe their general anatomy;
e. name some major nerves that arise from each plexus; and
f. explain the relationship of dermatomes to the spinal nerves.

DEEPER INSIGHT 14.2

Poliomyelitis and Amyotrophic Lateral Sclerosis

Poliomyelitis[15] and *amyotrophic lateral sclerosis*[16] (ALS) are two diseases that result from the destruction of motor neurons. In both diseases, the skeletal muscles atrophy from lack of innervation.

Poliomyelitis is caused by the poliovirus, which destroys motor neurons in the brainstem and anterior horn of the spinal cord. Signs of polio include muscle pain, weakness, and loss of some reflexes, followed by paralysis, muscular atrophy, and sometimes respiratory arrest. The virus spreads through water contaminated by feces. Historically, polio afflicted many children who contracted the virus from contaminated public swimming pools. For a time, the polio vaccine nearly eliminated new cases, but the disease has lately begun to reemerge among children in some countries because of antivaccination politics.

ALS is also known as Lou Gehrig[17] disease after the baseball player who had to retire from the sport because of it. It is marked not only by the degeneration of motor neurons and atrophy of the muscles, but also sclerosis (scarring) of the lateral regions of the spinal cord—hence its name. Most cases occur when astrocytes fail to reabsorb the neurotransmitter glutamate from the tissue fluid, allowing it to accumulate to a neurotoxic level. The early signs of ALS include muscular weakness and difficulty in speaking, swallowing, and using the hands. Sensory and intellectual functions remain unaffected, as evidenced by the accomplishments of astrophysicist and best-selling author Stephen Hawking (fig. 14.6), who was stricken with ALS while he was in college. Despite near-total paralysis, he remains highly productive and communicates with the aid of a speech synthesizer and computer. Tragically, many people are quick to assume that those who have lost most of their ability to communicate their ideas and feelings have no ideas and feelings to communicate. To a victim, this may be more unbearable than the loss of motor function itself.

© Justin Sullivan/Getty Images

Figure 14.6 Stephen Hawking (1942–), Lucasian Professor of Mathematics at Cambridge University.

General Anatomy of Nerves and Ganglia

The spinal cord communicates with the rest of the body by way of the spinal nerves. Before we discuss those specific nerves, however, it is necessary to be familiar with the structure of nerves and ganglia in general.

A **nerve** is a cord composed of numerous nerve fibers (axons) bound together by connective tissue (fig. 14.7). If we compare a nerve fiber to a wire carrying an electrical current in one direction, a nerve would be comparable to an electrical cable composed of thousands of wires carrying currents in opposite directions. A nerve contains anywhere from a few nerve fibers to more than a million. Nerves usually have a pearly white color and resemble frayed string as they divide into smaller and smaller branches.

Nerve fibers of the peripheral nervous system are ensheathed in Schwann cells, which form a neurilemma and often a myelin sheath around the axon (see p. 359). External to the neurilemma, each fiber is surrounded by a basal lamina and then a thin sleeve of loose connective tissue called the **endoneurium.** In most nerves, the nerve fibers are gathered in bundles called **fascicles,** each wrapped in a sheath called the **perineurium.** The perineurium is composed of up to 20 layers of overlapping, squamous, epithelium-like cells. Several fascicles are then bundled together and wrapped in an outer **epineurium** to compose the nerve as a whole. The tough epineurium consists of dense irregular fibrous connective tissue and protects the nerve from stretching and injury. Nerves have a high metabolic rate and need a plentiful blood supply, which is furnished by blood vessels that penetrate these connective tissue coverings.

Apply What You Know

How does the structure of a nerve compare to that of a skeletal muscle? Which of the descriptive terms for nerves have similar counterparts in muscle histology?

---

[15] *polio* = gray matter; *myel* = spinal cord; *itis* = inflammation

[16] *a* = without; *myo* = muscle; *troph* = nourishment

[17] Lou Gehrig (1903–41), American baseball player


Rootlets
Posterior root
Posterior root ganglion
Anterior root
Spinal nerve
Epineurium
Perineurium
Endoneurium
Nerve fiber
Fascicle
Blood vessels
(b)
Blood vessels
Fascicle
Epineurium
Perineurium
Unmyelinated nerve fibers
Myelinated nerve fibers
Endoneurium
Myelin
(a)

© ISM/Phototake

Figure 14.7 **Anatomy of a Nerve.** (a) A spinal nerve and its association with the spinal cord. (b) Cross section of a nerve (SEM). Myelinated nerve fibers appear in the photograph as white rings and unmyelinated fibers as solid gray.

Peripheral nerve fibers are of two kinds: *sensory (afferent) fibers* carry signals from sensory receptors to the CNS, and *motor (efferent) fibers* carry signals from the CNS to muscles and glands. Both sensory and motor fibers can also be described as *somatic* or *visceral* and as *general* or *special* depending on the organs they innervate (table 14.2).

Purely **sensory nerves,** composed only of afferent fibers, are rare; they include the olfactory and optic nerves described in chapter 15. **Motor nerves** carry only efferent fibers. Most nerves, however, are mixed. A **mixed nerve** consists of both afferent and efferent fibers and therefore conducts signals in two directions, although any one fiber within the nerve carries signals in one direction only. Many nerves often described as motor are actually mixed because they carry sensory signals of proprioception from the muscles back to the CNS.

TABLE 14.2 **The Classification of Nerve Fibers**

Class	Description
Afferent fibers	Carry sensory signals from receptors to the CNS
Efferent fibers	Carry motor signals from the CNS to effectors
Somatic fibers	Innervate skin, skeletal muscles, bones, and joints
Visceral fibers	Innervate blood vessels, glands, and viscera
General fibers	Innervate widespread organs such as muscles, skin, glands, viscera, and blood vessels
Special fibers	Innervate more localized organs in the head, including the eyes, ears, olfactory and taste receptors, and muscles of chewing, swallowing, and facial expression


Direction of signal conduction
Spinal cord
Posterior root ganglion
Anterior root
Posterior root ganglion
Somatosensory neurons
Sensory nerve fibers
Sensory pathway
Spinal nerve
Posterior root
Epineurium
Blood vessels
Anterior root
Motor nerve fibers
Motor pathway
To spinal cord
To peripheral receptors and effectors

Figure 14.8 **Anatomy of a Ganglion.** Longitudinal section. The posterior root ganglion contains the somas of sensory neurons conducting signals from peripheral sense organs to the spinal cord. Below this is the anterior root of the spinal nerve, which conducts motor signals away from the spinal cord, toward muscles and other peripheral effectors. (The anterior root is not part of the ganglion.)

- *To which morphological category of neurons (see p. 356) do the somatosensory neurons in this figure belong?*

If a nerve resembles a thread, a **ganglion**[18] resembles a knot in the thread. A ganglion is a cluster of neurosomas outside the CNS. It is enveloped in an epineurium continuous with that of the nerve. Among the neurosomas are bundles of nerve fibers leading into and out of the ganglion. Figure 14.8 shows a type of ganglion associated with the spinal nerves.

Spinal Nerves

There are 31 pairs of **spinal nerves:** 8 cervical (C1–C8), 12 thoracic (T1–T12), 5 lumbar (L1–L5), 5 sacral (S1–S5), and 1 coccygeal (Co1) (fig. 14.9). The first cervical nerve emerges between the skull and atlas, and the others emerge through intervertebral foramina, including the anterior and posterior foramina of the sacrum and the sacral hiatus.

Proximal Branches

Each spinal nerve arises from two points of attachment to the spinal cord. In each segment of the cord, six to eight nerve **rootlets** emerge from the anterior surface and converge to form the **anterior (ventral) root** of the spinal nerve. Another six to eight rootlets emerge from the posterior surface and converge to form the **posterior (dorsal) root** (see figs. 14.1b and 14.10). A short distance away from the spinal cord, the posterior root swells into a **posterior (dorsal) root ganglion,** which contains the somas of sensory neurons (fig. 14.8). There is no corresponding ganglion on the anterior root.

Distal to the ganglion, the anterior and posterior roots merge, leave the dural sheath, and form the spinal nerve proper (fig. 14.11). The nerve then exits the vertebral canal through the intervertebral foramen. The spinal nerve is a mixed nerve, carrying sensory signals to the spinal cord by way of the posterior root and ganglion, and motor signals out to more distant parts of the body.

The anterior and posterior roots are shortest in the cervical region and become longer inferiorly. The roots that arise

---

[18] *gangli* = knot


Vertebra C1 (atlas)
Cervical plexus (C1–C5)
Brachial plexus (C5–T1)
Vertebra T1
Intercostal (thoracic) nerves (T1–T12)
Lumbar enlargement
Vertebra L1
Lumbar plexus (L1–L4)
Sacral plexus (L4–S4)
Coccygeal plexus (S4–Co1)
C1
C2
C3
C4
C5
C6
C7
C8
T1
T2
T3
T4
T5
T6
T7
T8
T9
T10
T11
T12
L1
L2
L3
L4
L5
S1
S2
S3
S4
S5
Cervical nerves (8 pairs)
Cervical enlargement
Thoracic nerves (12 pairs)
Medullary cone
Lumbar nerves (5 pairs)
Cauda equina
Sacral nerves (5 pairs)
Coccygeal nerves (1 pair)
Sciatic nerve

Figure 14.9 **The Spinal Nerve Roots and Plexuses (Posterior View).**


Posterior median sulcus
Gracile fasciculus
Cuneate fasciculus
Lateral column
Segment C5
Cross section
Arachnoid mater
Dura mater
Neural arch of vertebra C3 (cut)
Spinal nerve C4
Vertebral artery
Spinal nerve C5:
Rootlets
Posterior root
Posterior root ganglion
Anterior root

© From *A Stereoscopic Atlas of Anatomy* by David L. Bassett. Courtesy of Dr. Robert A. Chase, M.D.

Figure 14.10 **The Point of Entry of Two Spinal Nerves into the Spinal Cord.** Posterior view with vertebrae cut away. Note that each posterior root divides into several rootlets that enter the spinal cord. A segment of the spinal cord is the portion receiving all the rootlets of one spinal nerve.

- *What would be the consequences of surgically cutting the spinal nerve rootlets shown in this photograph?*

from segments L2 to Co1 of the cord form the cauda equina. Some viruses invade the CNS by way of these roots (see Deeper Insight 14.3).

Distal Branches

Distal to the vertebrae, the branches of a spinal nerve are more complex (figs. 14.11 and 14.12). Immediately after emerging from the intervertebral foramen, the nerve divides into a **posterior ramus,**[19] an **anterior ramus,** and a small **meningeal branch.** Thus, each spinal nerve branches on both ends—into posterior and anterior *roots* approaching the spinal cord, and posterior and anterior *rami* leading away from the vertebral column.

The meningeal branch reenters the vertebral canal and innervates the meninges, vertebrae, and spinal ligaments with sensory and motor fibers. The posterior ramus innervates the muscles and joints in that region of the spine and the skin of the back. The anterior ramus, largest of the three, innervates the anterior and lateral skin and muscles of the trunk and gives rise to nerves of the limbs.

The anterior ramus differs from one region of the trunk to another. In the thoracic region, it forms an **intercostal nerve** that travels along the inferior margin of a rib and innervates the skin and intercostal muscles (thus contributing to breathing), as well as the internal oblique, external oblique, and transverse abdominal muscles. All other anterior rami form webs called *nerve plexuses,* described next.

---

[19] *ramus* = branch

DEEPER INSIGHT 14.3

Shingles

Chickenpox *(varicella),* a common disease of early childhood, is caused by the *varicella-zoster* virus. It produces an itchy rash that usually clears up without complications. The virus, however, remains for life in the posterior root ganglia, kept in check by the immune system. If the immune system is compromised, however, the virus can travel down the sensory nerves by axonal transport and cause *shingles (herpes zoster)*—characterized by a painful trail of skin discoloration and fluid-filled vesicles along the path of the nerve. These signs usually appear in the chest and waist, often on just one side of the body. In some cases, lesions appear on one side of the face, especially in and around the eye and occasionally in the mouth.

There is no cure, and the vesicles generally heal spontaneously within 1 to 3 weeks. In the meantime, aspirin and steroidal ointments can help to relieve the pain and inflammation of the lesions. Antiviral drugs such as acyclovir can shorten the course of an episode of shingles, but only if taken within the first 2 to 3 days of outbreak. Even after the lesions disappear, however, some people suffer intense pain along the course of the nerve *(postherpetic neuralgia, PHN),* lasting for months or even years. PHN has proven very difficult to treat, but pain relievers and antidepressants are of some help. Shingles is particularly common after the age of 50. Childhood vaccination against varicella reduces the risk of shingles later in life. A vaccine (Zostavax) is recommended for all healthy adults over age 60.



Figure 14.11 Branches of a Spinal Nerve in Relation to the Spinal Cord and Vertebra (Cross Section). AP|R


Posterior and anterior rootlets of spinal nerve
Posterior root
Posterior root ganglion
Anterior root
Spinal nerve
Anterior ramus of spinal nerve
Sympathetic chain ganglion
Posterior ramus of spinal nerve
Communicating rami
(a) Anterolateral view
Spinal nerve
Posterior ramus
Anterior ramus
Communicating rami
Intercostal nerve
Sympathetic chain ganglion
Thoracic cavity
Lateral cutaneous nerve
Intercostal muscles
Anterior cutaneous nerve
(b) Cross section

Figure 14.12 **Rami of the Spinal Nerves.** (a) Anterolateral view of the spinal nerves and their subdivisions in relation to the spinal cord and vertebrae. (b) Cross section of the thorax showing innervation of muscles and skin of the chest and back. This section is cut through the intercostal muscles between two ribs.

Nerve Plexuses

Except in the thoracic region, the anterior rami branch and anastomose (merge) repeatedly to form five nerve plexuses: the small **cervical plexus** in the neck, the **brachial plexus** in the shoulder, the **lumbar plexus** of the lower back, the **sacral plexus** immediately inferior to this, and finally, the tiny **coccygeal plexus** adjacent to the lower sacrum and coccyx. A general view of these plexuses is shown in figure 14.9; they are illustrated and described in tables 14.3 through 14.6. The spinal nerve roots that give rise to each plexus are indicated in violet in each table. Some of these roots give rise to smaller branches called *trunks, anterior divisions, posterior divisions,* and *cords,* which are color-coded and explained in the individual tables.

The nerves tabulated here have somatosensory and motor functions. *Somatosensory* means that they carry sensory signals from bones, joints, muscles, and the skin, in contrast to sensory input from the viscera or from special sense organs such as the eyes and ears. These somatosensory signals are for touch, heat, cold, stretch, pressure, pain, and other sensations. One of the most important sensory roles of these nerves is proprioception, in which the brain receives information about body position and movements from nerve endings in the muscles, tendons, and joints. The brain uses this information to adjust muscle actions and thereby maintain equilibrium (balance) and coordination.

The motor function of these nerves is primarily to stimulate the contraction of skeletal muscles. These nerves also carry autonomic fibers to the blood vessels of the skin, muscles, and other organs, thus adjusting blood flow to changing local needs.

The following tables identify the areas of skin innervated by the sensory fibers and the muscle groups innervated by the motor fibers of the individual nerves. The muscle tables in chapters 11 and 12 provide a more detailed breakdown of the muscles supplied by each nerve and the actions they perform. You may assume that for each muscle, these nerves also carry autonomic fibers to its blood vessels and sensory fibers from its proprioceptors. Throughout these tables, the abbreviations *n.* and *nn.* stand for *nerve* and *nerves.*

TABLE 14.3 The Cervical Plexus

The cervical plexus (fig. 14.13) receives fibers from the anterior rami of nerves C1 to C5 and gives rise to the nerves listed below, in order from superior to inferior. The most important of these are the *phrenic*[20] *nerves,* which travel down each side of the mediastinum, innervate the diaphragm, and play an essential role in breathing (see fig. 16.3, p. 446). In addition to the major nerves listed here, there are several motor branches that innervate the geniohyoid, thyrohyoid, scalene, levator scapulae, trapezius, and sternocleidomastoid muscles.

Nerve	**Composition**	**Cutaneous and Other Sensory Innervation**	**Muscular Innervation (Motor and Proprioceptive)**
Lesser occipital n.	Somatosensory	Upper third of medial surface of external ear, skin posterior to ear, posterolateral neck	None
Great auricular n.	Somatosensory	Most of the external ear, mastoid region, region from parotid salivary gland (see fig. 11.2, p. 268) to slightly inferior to angle of mandible	None
Transverse cervical n.	Somatosensory	Anterior and lateral neck, underside of chin	None
Ansa cervicalis	Mixed	(None)	Omohyoid, sternohyoid, and sternothyroid muscles
Supraclavicular nn.	Somatosensory	Lower anterior and lateral neck, shoulder, anterior chest	None
Phrenic n.	Mixed	Diaphragm, pleura, and pericardium	Diaphragm


🟪 Roots
C1
C2
C3
C4
C5
Hypoglossal nerve (XII)
Lesser occipital nerve
Great auricular nerve
Transverse cervical nerve
Ansa cervicalis:
Anterior root
Posterior root
Supraclavicular nerves
Phrenic nerve

Figure 14.13 **The Cervical Plexus.**
•*Predict the effect of a surgical accident in which the phrenic nerve is severed.* APR

---

[20] *phren* = diaphragm

TABLE 14.4 The Brachial Plexus

The brachial plexus (figs. 14.14 and 14.15) is formed predominantly by nerves C5 to T1 (C4 and T2 make smaller contributions). It passes over the first rib into the axilla and innervates the upper limb and some muscles of the neck and shoulder. This plexus is well known for its conspicuous M or W shape when seen in cadaver dissection. The subdivisions of this plexus are called *roots, trunks, divisions,* and *cords* (color-coded in fig. 14.14). The five **roots** are the anterior rami of C5 through T1. Roots C5 and C6 converge to form the **upper trunk;** C7 continues as the **middle trunk;** and C8 and T1 converge to form the **lower trunk.** Each trunk divides into an **anterior** and **posterior division;** as the body is dissected from the anterior surface of the shoulder inward, the posterior divisions are found behind the anterior ones. Finally, the six divisions merge to form three large fiber bundles—the **lateral, posterior,** and **medial cords.** From these cords arise the following major nerves, listed in order of the illustration from superior to inferior.

Nerve	Composition	Cord of Origin	Cutaneous and Joint Innervation (Sensory)	Muscular Innervation (Motor and Proprioceptive)
Musculocutaneous n.	Mixed	Lateral	Skin of anterolateral forearm; elbow joint	Brachialis, biceps brachii, and coracobrachialis muscles
Axillary n.	Mixed	Posterior	Skin of lateral shoulder and arm; shoulder joint	Deltoid and teres minor muscles
Radial n.	Mixed	Posterior	Skin of posterior arm; posterior and lateral forearm and wrist; joints of elbow, wrist, and hand	Mainly extensor muscles of posterior arm and forearm (see tables 12.3 and 12.4)
Median n.	Mixed	Lateral and medial	Skin of lateral two-thirds of hand; tips of digits I–IV; joints of hand	Mainly forearm flexors; thenar group and lumbricals I–II of hand (see tables 12.3 to 12.5)
Ulnar n.	Mixed	Medial	Skin of palmar and medial hand and digits III–V; joints of elbow and hand	Some forearm flexors; adductor pollicis; hypothenar group; interosseous muscles; lumbricals III–IV (see tables 12.4 and 12.5)


C5
C6
C7
C8
T1
Dorsal scapular nerve
Suprascapular nerve
Lateral cord
Posterior cord
Medial cord
Long thoracic nerve
Musculocutaneous nerve
Axillary nerve
Radial nerve
Median nerve
Ulnar nerve
🟪 Roots
🟥 Trunks
🟩 Anterior divisions
🟦 Posterior divisions
🟫 Cords
Lateral cord
Posterior cord
Medial cord
Axillary nerve
Musculocutaneous nerve
Median nerve
Radial nerve
Ulna
Ulnar nerve
Median nerve
Radial nerve
Radius
Superficial branch of ulnar nerve
Digital branch of ulnar nerve
Digital branch of median nerve

Figure 14.14 **The Brachial Plexus.** The labeled nerves innervate muscles tabulated in chapter 12, and those in boldface are further detailed in this table. APR

TABLE 14.4 **The Brachial Plexus (continued)**



© McGraw-Hill Education/Photo and Dissection by Christine Eckel

Figure 14.15 **The Brachial Plexus of a Cadaver.** Anterior view of the left shoulder.

DEEPER INSIGHT 14.4

Nerve Injuries

The radial and sciatic nerves are especially vulnerable to injury. The radial nerve, which passes through the axilla, may be compressed against the humerus by improperly adjusted crutches, causing *crutch paralysis*. A similar injury often resulted from the discredited practice of trying to correct a dislocated shoulder by putting a foot in a person's armpit and pulling on the arm. One consequence of radial nerve injury is *wrist drop*—the fingers, hand, and wrist are chronically flexed because the extensor muscles supplied by the radial nerve are paralyzed.

Because of its position and length, the sciatic nerve of the hip and thigh (see p. 390) is the most vulnerable nerve in the body. Trauma to this nerve produces *sciatica,* a sharp pain that travels from the gluteal region along the posterior side of the thigh and leg as far as the ankle. Ninety percent of cases result from a herniated intervertebral disc or osteoarthritis of the lower spine, but sciatica can also be caused by pressure from a pregnant uterus, dislocation of the hip, injections in the wrong area of the buttock, or sitting for a long time on the edge of a hard chair. Men sometimes suffer sciatica because of the habit of sitting on a wallet carried in the hip pocket.

TABLE 14.5 The Lumbar Plexus

The lumbar plexus (fig. 14.16) is formed from the anterior rami of nerves L1 to L4 and some fibers from T12. With only five roots and two divisions, it is less complex than the brachial plexus. It gives rise to the following nerves.

Nerve	Composition	Cutaneous and Joint Innervation (Sensory)	Muscular Innervation (Motor and Proprioceptive)
Iliohypogastric n.	Mixed	Skin of lower anterior abdominal and posterolateral gluteal regions	Internal and external abdominal oblique and transverse abdominal muscles
Ilioinguinal n.	Mixed	Skin of upper medial thigh; male scrotum and root of penis; female labia majora	Internal abdominal oblique
Genitofemoral n.	Mixed	Skin of middle anterior thigh; male scrotum; female labia majora	Male cremaster muscle (705)
Lateral femoral cutaneous n.	Somatosensory	Skin of anterior and upper lateral thigh	None
Femoral n.	Mixed	Skin of anterior, medial, and lateral thigh and knee; skin of medial leg and foot; hip and knee joints	Iliacus, pectineus, quadriceps femoris, and sartorius muscles
Obturator n.	Mixed	Skin of medial thigh; hip and knee joints	Obturator externus; medial (adductor) thigh muscles (see table 12.6)


Roots
Anterior divisions
Posterior divisions
L1
L2
L3
L4
L5
Iliohypogastric nerve
Ilioinguinal nerve
Genitofemoral nerve
Obturator nerve
Lateral femoral cutaneous nerve
Femoral nerve
Obturator nerve
Lumbosacral trunk
Anterior view
From lumbar plexus
From sacral plexus
Hip bone
Sacrum
Femoral nerve
Pudendal nerve
Sciatic nerve
Femur
Tibial nerve
Common fibular nerve
Superficial fibular nerve
Deep fibular nerve
Fibula
Tibia
Tibial nerve
Medial plantar nerve
Lateral plantar nerve
Posterior view

Figure 14.16 **The Lumbar Plexus.** The nerves in boldface are further detailed in this table. APR

TABLE 14.6 The Sacral and Coccygeal Plexuses

The sacral plexus (fig. 14.17) is formed from the anterior rami of nerves L4, L5, and S1 through S4. It has six roots and anterior and posterior divisions. Since it is connected to the lumbar plexus by fibers that run through the *lumbosacral trunk,* the two plexuses are sometimes referred to collectively as the *lumbosacral plexus.* The coccygeal plexus is a tiny plexus formed from the anterior rami of S4, S5, and Co1.

The *tibial* and *common fibular nerves* travel together through a connective tissue sheath; they are referred to collectively as the **sciatic** (sy-AT-ic) **nerve.** The sciatic nerve passes through the greater sciatic notch of the pelvis, extends for the length of the thigh, and ends at the popliteal fossa. Here, the tibial and common fibular nerves diverge and follow their separate paths into the leg. The tibial nerve descends through the leg and then gives rise to the medial and plantar nerves in the foot. The common fibular nerve divides into deep and superficial fibular nerves. The sciatic nerve is a common focus of injury and pain (see Deeper Insight 14.4).

Nerve	Composition	Cutaneous and Joint Innervation (Sensory)	Muscular Innervation (Motor and Proprioceptive)
Superior gluteal n.	Mixed	(None)	Gluteus minimus, gluteus medius, and tensor fasciae latae muscles
Inferior gluteal n.	Mixed	(None)	Gluteus maximus muscle
Posterior cutaneous n.	Somatosensory	Skin of gluteal region, perineum, posterior and medial thigh, popliteal fossa, and upper posterior leg	None
Tibial n.	Mixed	Skin of posterior leg; plantar skin; knee and foot joints	Hamstring muscles; posterior muscles of leg (see tables 12.6 and 12.7); most intrinsic foot muscles (via plantar nerves) (see table 12.8)
Fibular (peroneal) n. (common, deep, and superficial)	Mixed	Skin of anterior distal third of leg, dorsum of foot, and toes I–II; knee joint	Biceps femoris muscle; anterior and lateral muscles of leg; extensor digitorum brevis muscle of foot (see tables 12.7 to 12.9)
Pudendal n.	Mixed	Skin of penis and scrotum of male; clitoris, labia majora and minora, and lower vagina of female	Muscles of perineum (see table 11.8)



Figure 14.17 The Sacral and Coccygeal Plexuses. APR

Cutaneous Innervation and Dermatomes

Each spinal nerve except C1 receives sensory input from a specific area of skin called a **dermatome,**[21] derived from the embryonic dermatomes described in chapter 4. A *dermatome map* (fig. 14.18) is a diagram of the cutaneous regions innervated by each spinal nerve. Such a map is oversimplified, however, because the dermatomes overlap at their edges by as much as 50%. Therefore, severance of one sensory nerve root does not entirely deaden sensation from a dermatome. It is necessary to sever or anesthetize three sequential spinal nerves to produce a total loss of sensation from one dermatome. Spinal nerve damage is assessed by testing the dermatomes with pinpricks and noting areas in which the patient has no sensation.



Figure 14.18 A Dermatome Map of the Anterior Aspect of the Body. Each zone of the skin is innervated by sensory branches of the spinal nerves indicated by the labels. Nerve C1 does not innervate the skin.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

6. What is meant by the *posterior* and *anterior roots* of a spinal nerve? Which of these is sensory, and which is motor?
7. Where are the somas of the posterior root located? Where are the somas of the anterior root?
8. List the five plexuses of spinal nerves and state where each one is located.
9. State which plexus gives rise to each of the following nerves: axillary, ilioinguinal, obturator, phrenic, pudendal, radial, and sciatic.

14.3 Somatic Reflexes

Expected Learning Outcomes

When you have completed this section, you should be able to

a. define *reflex* and explain how reflexes differ from other motor actions;
b. describe the general components of a typical reflex arc; and
c. describe some common variations in reflex arcs.

Reflexes are quick, involuntary, stereotyped reactions of glands or muscles to stimulation. This definition sums up four important properties of a reflex:

1. Reflexes *require stimulation*—they are not spontaneous actions like muscle tics but responses to sensory input.
2. Reflexes are *quick*—they generally involve few if any interneurons and minimal synaptic delay.
3. Reflexes are *involuntary*—they occur without intent, often without our awareness, and they are difficult to suppress. Given an adequate stimulus, the response is essentially automatic. You may become conscious of the stimulus that evoked a reflex, and this awareness may enable you to correct or avoid a potentially dangerous situation, but awareness is not a part of the reflex itself. It may come after the reflex action has been completed, and some reflexes occur even if the spinal cord has been severed so that no stimuli reach the brain.

---

[21] *derma* = skin; *tome* = segment, part

4. Reflexes are *stereotyped*—they occur in essentially the same way every time, unlike our more variable learned and voluntary behaviors; a reflex is very predictable.

Visceral reflexes are responses of glands, cardiac muscle, and smooth muscle. They are controlled by the autonomic nervous system and discussed in chapter 16. **Somatic reflexes** are responses of skeletal muscles, such as the quick withdrawal of your hand from a hot stove or the lifting of your foot when you step on something sharp. They are controlled by the somatic nervous system. They have traditionally been called *spinal reflexes,* although this is a misleading expression for two reasons: (1) Spinal reflexes are not exclusively somatic; the autonomic (visceral) reflexes also involve the spinal cord. (2) Some somatic reflexes are mediated more by the brain than by the spinal cord.

Somatic reflexes will be briefly discussed here from the anatomical standpoint. A somatic reflex employs a rather simple neural pathway called a **reflex arc,** from a sensory nerve ending to the spinal cord or brainstem and back to a skeletal muscle (fig. 14.19). The components of a reflex arc are as follows:

1. *Somatic receptors* in the skin, a muscle, or a tendon. These include simple nerve endings for heat and pain in the skin, specialized stretch receptors called *muscle spindles* embedded in the skeletal muscles, and other types (see chapter 17, p. 462).
2. *Afferent nerve fibers,* which carry information from these receptors into the posterior horn of the spinal cord.
3. An *integrating center,* a neural pool in the gray matter of the spinal cord or brainstem. In most reflex arcs, the integrating center has one or more interneurons. Synaptic events in the integrating center determine whether the efferent (output) neuron issues a signal to the muscle.
4. *Efferent nerve fibers,* which originate in the anterior horn of the spinal cord and carry motor impulses to the skeletal muscles.
5. *Skeletal muscles,* the somatic effectors that carry out the response.

In the simplest type of reflex arc, there is no interneuron. The afferent neuron synapses directly with an efferent neuron, so this kind of pathway is called a **monosynaptic reflex arc.** Synaptic delay is minimal, and the response is especially quick. Most reflex arcs, however, have one or more interneurons, and indeed often involve multineuron circuits with many synapses. Such reflex arcs produce


Axon of sensory neuron
Spinal cord
Cell body of sensory neuron
Effector (quadriceps femoris muscle)
Dendrite of sensory neuron
Cell body of motor neuron
Axon of motor neuron
Patellar ligament
Tibia

Figure 14.19 **A Representative Reflex Arc.** The monosynaptic reflex arc of the patellar tendon reflex. The pathway is shown in greatly simplified form. Numerous afferent and efferent fibers would be necessary to produce an effective response.

- *This diagram shows motor output to the quadriceps femoris muscle. For the patellar tendon reflex to work, it is also necessary to inhibit contraction of the ipsilateral hamstring muscles, using a pathway not illustrated here. Explain the necessity for this inhibitory reflex.* AP|R more prolonged muscular responses and, by way of diverging circuits, may stimulate multiple muscles at once.

Apply What You Know

There is actually a second synapse in a "monosynaptic" reflex arc. Identify its location.

A reflex like the one diagrammed in figure 14.19 is described as an **ipsilateral reflex** because the CNS input and output are on the same side of the body. Others such as the crossed extension reflex (table 14.7) are called **contralateral reflexes** because the sensory input enters the spinal cord on one side of the body and the motor output leaves on the opposite side. In an **intersegmental reflex,** the sensory signal enters the spinal cord at one level (segment), and the motor output leaves the cord from a higher or lower level. For example, if you step on something sharp and lift your foot from the ground, some motor output leaves the spinal cord higher up and goes to trunk muscles that flex your waist. This shifts your center of gravity over the leg still on the ground, preventing you from falling over.

Table 14.7 describes several types of somatic reflexes. These reflexes are controlled primarily by the cerebrum and cerebellum of the brain, but a weak response is mediated through the spinal cord and persists even if the spinal cord is severed from the brain. The spinal component can be more pronounced if the stimulus is sudden or intense, as in the clinical testing of the knee-jerk (patellar) reflex and other stretch reflexes.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

10. Define *reflex.* Distinguish between somatic and visceral reflexes.
11. List and define the five components of a typical somatic reflex arc.
12. Describe a situation in which each of the following would be functionally relevant: an ipsilateral, a contralateral, and an intersegmental reflex arc.

14.4 Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe some effects of spinal cord injuries; and
b. define the types of paralysis and explain the basis for their differences.

Some developmental abnormalities of the spinal cord are described in chapter 13. In children and adults, the most significant disorder of the spinal cord is trauma. Each year in the United States, 10,000 to 12,000 people become paralyzed by spinal cord trauma, usually as a result of vertebral fractures. The group at greatest risk is males from 16 to 30 years old, because of their high-risk behaviors. Fifty-five percent of their spinal injuries are from automobile and motorcycle accidents, 18% from sports, and 15% from gunshot and stab wounds. Elderly people are also at above-average risk because of falls, and in times of war, battlefield injuries account for many cases.

Complete *transection* (severance) of the spinal cord causes immediate loss of motor control at and below the level of the injury. Victims also lose all sensation from the level of injury and below, although some patients temporarily feel burning pain within one or two dermatomes of the level of the lesion.

Apply What You Know

Respiratory paralysis typically results from spinal cord transection above level C4, but not from injuries below that level. Explain.

In the early stage, victims exhibit a syndrome (a suite of signs and symptoms) called **spinal shock.** The muscles below the level of injury exhibit flaccid paralysis (inability to contract) and an absence of reflexes because of the lack of stimulation from higher levels of the CNS. For 8 days to 8 weeks after the

TABLE 14.7 Types of Somatic Reflexes

Stretch reflex	Increased muscle tension in response to stretch. Serves to maintain equilibrium and posture, stabilize joints, and make joint actions smoother and better coordinated. The knee-jerk reflex (patellar reflex, fig. 14.19) is a familiar monosynaptic spinal reflex.
Flexor reflex	Contraction of flexor muscles resulting in withdrawal of a limb from an injurious stimulus, as in withdrawal from a burn or pinprick
Crossed extension reflex	Contraction of extensor muscles in one limb when the flexor muscles of the opposite limb contract. Stiffens one leg, for example, when the opposite leg is lifted from the ground, so that one does not fall over.
Tendon reflex	Inhibition of muscle contraction when a tendon is excessively stretched, serving to prevent tendon injuries

accident, the patient typically lacks bladder and bowel reflexes and thus retains urine and feces. Lacking sympathetic stimulation to the blood vessels, a patient may exhibit *neurogenic shock* in which the vessels dilate and blood pressure drops dangerously low. Spinal shock can last from a few days to 3 months, but typically lasts 7 to 20 days.

As spinal shock subsides, somatic reflexes begin to reappear, at first in the toes and progressing to the feet and legs. Autonomic reflexes also reappear. Contrary to the earlier urinary and fecal retention, a patient now has the opposite problem, incontinence, as the rectum and bladder empty reflexively in response to stretch. Both the somatic and autonomic nervous systems typically exhibit exaggerated reflexes, a state called *hyperreflexia* or the *mass reflex reaction.* Stimuli such as a full bladder or cutaneous touch can trigger an extreme cardiovascular reaction. The systolic blood pressure, normally about 120 mm Hg, jumps as high as 300 mm Hg, sometimes causing a stroke. Pressure receptors in the major arteries sense this rise in blood pressure and activate a reflex that slows the heart, sometimes to a rate as low as 30 or 40 beats/minute *(bradycardia).* Men at first lose the capacity for erection and ejaculation. They may recover these functions later and become capable of climaxing and fathering children, but still lack sexual sensation.

The most serious permanent effect of spinal cord trauma is paralysis. As reflexes reappear, they lack inhibitory control from the brain. Consequently, the initial flaccid paralysis of spinal shock changes to spastic paralysis. This typically starts with chronic flexion of the hips and knees *(flexor spasms)* and progresses to a state in which the limbs become straight and rigid *(extensor spasms).* Three forms of muscle paralysis are **paraplegia,** a paralysis of both lower limbs resulting from spinal cord lesions at levels T1 to L1; **quadriplegia,** the paralysis of all four limbs resulting from lesions above level C5; and **hemiplegia,** paralysis of one side of the body, usually resulting not from spinal cord injuries but from a stroke or other brain lesion. Spinal cord lesions from C5 to C7 can produce a state of partial quadriplegia—total paralysis of the lower limbs and partial paralysis (*paresis,* or weakness) of the upper limbs.

Treatment of spinal cord injuries is an area of intense medical research, with hopes for recovery of spinal functions stimulated by new insights into the physiological mechanisms of spinal cord tissue death and the potential for embryonic stem cells to regenerate damaged cord tissue.

Table 14.8 describes some injuries and other disorders of the spinal cord and spinal nerves.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

13. Describe the signs of spinal shock.
14. Describe the difference between flaccid paralysis and spastic paralysis.
15. Distinguish between the causes of paraplegia, quadriplegia, and hemiplegia.

TABLE 14.8 Some Disorders of the Spinal Cord and Spinal Nerves

Guillain-Barré syndrome	An acute demyelinating nerve disorder often triggered by viral infection, resulting in muscle weakness, elevated heart rate, unstable blood pressure, shortness of breath, and sometimes death from respiratory paralysis
Neuralgia	General term for nerve pain, often caused by pressure on spinal nerves from herniated intervertebral discs or other causes
Paresthesia	Abnormal sensations of prickling, burning, numbness, or tingling; a symptom of nerve trauma or other peripheral nerve disorders
Peripheral neuropathy	Any loss of sensory or motor function due to nerve injury; also called *nerve palsy*
Rabies (hydrophobia)	A disease usually contracted from animal bites, involving viral infection that spreads via somatic motor nerve fibers to the CNS and then out of the CNS via autonomic nerve fibers, leading to seizures, coma, and death; invariably fatal if not treated before CNS symptoms appear
Spinal meningitis	Inflammation of the spinal meninges due to viral, bacterial, or other infection

Disorders Described Elsewhere

Amyotrophic lateral sclerosis	380	Leprosy	465	Sciatica	388
Carpal tunnel syndrome	307	Multiple sclerosis	361	Shingles	384
Crutch paralysis	388	Poliomyelitis	380	Spina bifida	367
Diabetic neuropathy	465	Paraplegia	394	Spinal cord trauma	393
Hemiplegia	394	Quadriplegia	394		

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

14.1 The Spinal Cord (p. 372)

1. Four functions of the spinal cord and their relationship to spinal tracts, central pattern generators, and reflex arcs in the cord
2. The extent of the spinal cord in relation to the vertebrae, and the location and composition of the cauda equina
3. The four regions of the spinal cord and the basis for their names
4. What is meant by a *segment* of the spinal cord
5. The locations and functional significance of the cervical and lumbar enlargements of the cord
6. The three meninges associated with the spinal cord and their relationships with the epidural space, dural sheath, subarachnoid space, denticulate and coccygeal ligaments, and lumbar cistern
7. The arrangement of the gray matter and white matter of the spinal cord as seen in cross section, and the composition of each tissue
8. The locations and functional differences between the posterior horn, anterior horn, and lateral horn of the spinal gray matter
9. The columns and tracts of spinal white matter
10. The general function of the ascending tracts; the system used for naming most of them; and their individual names, locations, and functions
11. First- through third-order neurons; decussation in the ascending tracts; and the implication of this decussation for the relationship between the cerebral hemispheres and the origin of sensory signals from the lower body
12. The general function of the descending tracts; the system for naming them; and their individual names, locations, and functions
13. Upper and lower motor neurons; decussation in the descending tracts; and the implication of this decussation for the relationship between the cerebral hemispheres and motor control of the lower body

14.2 The Spinal Nerves (p. 379)

1. The structure of a nerve, including its three layers of connective tissue and how they relate to the organization of nerve fibers into fascicles
2. The differences between afferent and efferent nerve fibers; somatic and visceral fibers; and general and special fibers
3. The difference between sensory, motor, and mixed nerves
4. The structure of a ganglion; where ganglia are found; and the relationship between a ganglion and a nerve
5. The number of spinal nerves and the system for naming and numbering them
6. The structure of the proximal portion of a spinal nerve, including its posterior and anterior roots, their rootlets, and the posterior root ganglion; and how the posterior and anterior roots relate to the posterior and anterior horns of the spinal cord
7. The structure of the distal portion of a spinal nerve, particularly its division into a posterior ramus, anterior ramus, and meningeal branch, and where these three branches lead
8. The five plexuses of spinal nerves—their names, locations, and structure; the nerves that arise from them; and the structures innervated by these nerves (tables 14.3 through 14.6)

14.3 Somatic Reflexes (p. 391)

1. The general characteristics of a reflex, and how visceral reflexes differ from somatic reflexes
2. The components of a reflex arc and the path followed by the afferent and efferent nerve signals of a somatic reflex
3. The differences between a monosynaptic and a polysynaptic reflex arc
4. The differences between ipsilateral, contralateral, and intersegmental reflex arcs, and some reflexes that would employ each type
5. The nature of a stretch reflex, flexor reflex, crossed extension reflex, and tendon reflex

14.4 Clinical Perspectives (p. 393)

1. Causes and risk factors for spinal cord trauma
2. The effects of spinal cord trauma including spinal shock, hyperreflexia, and flaccid and spastic paralysis
3. The differences between paraplegia, quadriplegia, and hemiplegia with respect to their causes and parts of the body affected

Testing Your Recall

1. Below L2, the vertebral canal is occupied by a bundle of spinal nerve roots called
   a. the terminal filum.
   b. the descending tracts.
   c. the gracile fasciculus.
   d. the medullary cone.
   e. the cauda equina.
2. The brachial plexus gives rise to all of the following nerves *except*
   a. the axillary nerve.
   b. the radial nerve.
   c. the obturator nerve.
   d. the median nerve.
   e. the ulnar nerve.
3. Between the dura mater and vertebral bone, one is most likely to find
   a. arachnoid mater.
   b. denticulate ligaments.
   c. cartilage.
   d. adipose tissue.
   e. spongy bone.
4. Which of these tracts carries motor signals destined for the postural muscles?
   a. the gracile fasciculus
   b. the cuneate fasciculus
   c. the spinothalamic tract
   d. the vestibulospinal tract
   e. the tectospinal tract
5. A patient has a gunshot wound that caused a bone fragment to nick the spinal cord. The patient now feels no pain or temperature sensations from that level of the

body down. Most likely, the _____ was damaged.
   a. gracile fasciculus
   b. medial lemniscus
   c. tectospinal tract
   d. lateral corticospinal tract
   e. spinothalamic tract

6. Which of these is *not* a region of the spinal cord?
   a. cervical
   b. thoracic
   c. pelvic
   d. lumbar
   e. sacral
7. In the spinal cord, the somas of the lower motor neurons are found in
   a. the cauda equina.
   b. the posterior horns.
   c. the anterior horns.
   d. the posterior root ganglia.
   e. the fasciculi.
8. The outermost connective tissue wrapping of a nerve is called
   a. the epineurium.
   b. the perineurium.
   c. the endoneurium.
   d. the arachnoid mater.
   e. the dura mater.
9. The intercostal nerves between the ribs arise from which spinal nerve plexus?
   a. cervical
   b. brachial
   c. lumbar
   d. sacral
   e. none of them
10. All somatic reflexes share all of the following properties *except*
    a. they are quick.
    b. they are monosynaptic.
    c. they require stimulation.
    d. they are involuntary.
    e. they are stereotyped.
11. Outside the CNS, the somas of neurons are clustered in swellings called _____.
12. Distal to the intervertebral foramen, a spinal nerve branches into a posterior and anterior _____.
13. The cerebellum receives feedback from the muscles and joints by way of the _____ tracts of the spinal cord.
14. Motor innervation of the leg proper comes predominantly from the _____ plexus.
15. Neural circuits called _____ in the spinal cord produce the rhythmic muscular contractions of walking.
16. The _____ nerves arise from the cervical plexus and innervate the diaphragm.
17. The crossing of a nerve fiber or tract from the right side of the CNS to the left, or vice versa, is called _____.
18. The nonvisual awareness of the body's position and movements is called _____.
19. The _____ ganglion contains the somas of neurons that carry sensory signals to the spinal cord.
20. The sciatic nerve is a composite of two nerves, the _____ and _____.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. caudo-
2. contra-
3. later-
4. proprio-
5. gracil-
6. myelo-
7. a-
8. -itis
9. phreno-
10. tom-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. The gracile fasciculus is a descending spinal tract.
2. At the inferior end, the adult spinal cord ends before the vertebral column does.
3. Each spinal cord segment has only one pair of spinal nerves.
4. Some spinal nerves are sensory and others are motor.
5. The dura mater adheres tightly to the bone tissue of the vertebral canal.
6. The anterior and posterior horns of the spinal cord are composed of gray matter.
7. The corticospinal tracts carry motor signals down the spinal cord.
8. The dermatomes are nonoverlapping regions of skin innervated by different spinal nerves.
9. Somatic reflexes are those that do not involve the brain.
10. The Golgi tendon reflex acts to inhibit muscle contraction.

Answers in appendix A

Testing Your Comprehension

1. Jillian is thrown from a horse. She strikes the ground with her chin, causing severe hyperextension of the neck. Emergency medical technicians properly immobilize her neck and transport her to a hospital, but she dies 5 minutes after arrival. An autopsy shows multiple fractures of vertebrae C1, C6, and C7 and extensive damage to the spinal cord. Assuming that these

facts alone could account for her death, explain why she died rather than being left quadriplegic.

2. Wallace is the victim of a hunting accident. A bullet grazed his vertebral column, and bone fragments severed the left half of his spinal cord at segments T8 through T10. Since the accident, Wallace has had a condition called *dissociated sensory loss,* in which he feels no sensations of deep touch or limb position on the *left* side of his body below the injury and no sensations of pain or heat on the *right* side. Explain what spinal tract(s) the injury has affected and why these sensory losses are on opposite sides of the body.
3. Anthony gets into a fight between rival gangs. As an attacker comes at him with a knife, he turns to flee, but stumbles. The attacker stabs him on the medial side of the right gluteal fold, and Anthony collapses. He loses all use of his right limb, being unable to extend his hip, flex his knee, or move his foot. He never fully recovers these lost functions. Explain what nerve injury Anthony has most likely suffered.
4. Stand with your right shoulder, hip, and foot firmly against a wall. Raise your left foot from the floor without losing contact with the wall at any point. What happens? Why? What principle of this chapter does this demonstrate?
5. When a patient needs a tendon graft, surgeons sometimes use the tendon of the palmaris longus, a relatively dispensable muscle of the forearm. The median nerve lies nearby and looks very similar to this tendon. There have been cases in which a surgeon mistakenly removed a section of this nerve instead of the tendon. What effects do you think such a mistake would have on the patient?



Frontal section of a brain with a large tumor (glioblastoma) in the right cerebral hemisphere

© Simon Fraser/Newcastle Hospitals NHS Trust
Calculate Price/Science Photo Library/Getty Images

CHAPTER
15

THE NERVOUS SYSTEM III

BRAIN AND CRANIAL NERVES

CHAPTER OUTLINE

15.1 Overview of the Brain 399
- Major Landmarks 399
- Gray and White Matter 402
- Meninges 402
- Ventricles and Cerebrospinal Fluid 404
- Blood Supply and the Brain Barrier System 404

15.2 The Hindbrain and Midbrain 406
- The Medulla Oblongata 406
- The Pons 409
- The Midbrain 409
- The Reticular Formation 410
- The Cerebellum 410

15.3 The Forebrain 413
- The Diencephalon 413
- The Cerebrum 415
- Integrative Brain Functions 419

15.4 The Cranial Nerves 427
- An Aid to Memory 437
- Classification 437
- Nerve Pathways 437

15.5 Developmental and Clinical Perspectives 437
- The Aging Central Nervous System 437
- Two Neurodegenerative Diseases 438

Study Guide 439

DEEPER INSIGHTS

15.1 Meningitis 404
15.2 Some Cranial Nerve Disorders 431

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:

- Anatomy of the cranium (pp. 155–164)
- Glial cells and their functions (p. 357)
- Embryonic development of the CNS (p. 365)
- Tracts of the spinal cord (p. 375)
- Structure of nerves and ganglia (p. 380)

Anatomy & Physiology REVEALED®
aprevealed.com

Module 7: Nervous System

The mystique of the brain continues to intrigue modern biologists and psychologists even as it did the philosophers of antiquity. Aristotle thought the brain was merely a radiator for cooling the blood, but generations earlier, Hippocrates had expressed a more accurate view. "Men ought to know," he said, "that from the brain, and from the brain only, arise our pleasures, joy, laughter and jests, as well as our sorrows, pains, griefs and tears. Through it, in particular, we think, see, hear, and distinguish the ugly from the beautiful, the bad from the good, the pleasant from the unpleasant."

Brain function is so strongly associated with what it means to be alive and human that the cessation of brain activity is taken as a clinical criterion of death even when other organs of the body are still functioning. With its hundreds of neural pools and trillions of synapses, the brain performs sophisticated tasks beyond our present understanding. Still, all of our mental functions, no matter how complex, are ultimately based on the cellular activities described in chapter 13. The relationship of the mind or personality to the cellular function of the brain is a question that will provide fertile ground for scientific study and philosophical debate long into the future.

This chapter is a study of the brain and the cranial nerves directly connected to it. Here we will plumb some of the mysteries of motor control, sensation, emotion, thought, language, personality, memory, dreams, and plans. Your study of this chapter is one brain's attempt to understand itself.

15.1 Overview of the Brain

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the major subdivisions and anatomical landmarks of the brain;
b. state the locations of the gray and white matter of the brain;
c. describe the meninges of the brain;
d. describe the system of fluid-filled chambers within the brain;
e. discuss the production, flow, and function of the cerebrospinal fluid in these chambers; and
f. explain the significance of the brain barrier system.

In the evolution of the central nervous system from the simplest vertebrate animals to humans, the spinal cord has changed very little while the brain has changed a great deal. In fishes and amphibians, the brain weighs about the same as the spinal cord, but in humans, it weighs 55 times as much. It averages about 1,600 g (3.5 pounds) in men and 1,450 g in women. The difference in weight is proportional to body size, not intelligence. The Neanderthal people had larger brains than modern humans do.

The human brain has a high opinion of itself, often claiming to be the most complex object in the known universe. Ours is the most sophisticated brain compared to others in terms of awareness of the environment, adaptability to environmental variation and change, quick execution of complex decisions, fine motor control and mobility of the body, and behavioral complexity. Over the course of human evolution, the brain has shown its greatest growth in areas concerned with vision, memory, cognition, and motor control of the prehensile hand.

Major Landmarks

Before we consider the form and function of specific regions of the brain, it will help to get a general overview of its major landmarks (figs. 15.1 and 15.2). These will provide important points of reference as we progress through a more detailed study.

Two directional terms often used to describe brain anatomy are *rostral* and *caudal.* **Rostral**[1] means "toward the nose" and **caudal**[2] means "toward the tail." These are apt descriptions for an animal such as a laboratory rat, on which so much neuroscience research has been done. The terms are retained for human neuroanatomy as well, but in references to the human brain, *rostral* means toward the forehead and *caudal* means toward the spinal cord. In the spinal cord and brainstem, which are vertically oriented, *rostral* means higher and *caudal* means lower.

The brain is divided into three major portions—the *cerebrum, cerebellum,* and *brainstem.* The **cerebrum** (seh-REE-brum or SER-eh-brum) constitutes about 83% of the brain's volume and consists of a pair of half globes called the **cerebral hemispheres.** Each hemisphere is marked by thick folds called **gyri**[3] (JY-rye; singular, *gyrus*) separated by shallow grooves called **sulci**[4] (SUL-sye; singular, *sulcus*). A very deep groove, the **longitudinal fissure,** separates the right and left hemispheres from each other. At the bottom of this fissure, the hemispheres are connected by a thick bundle of nerve fibers called the **corpus callosum**[5]—a prominent landmark for anatomical description (fig. 15.2).

The **cerebellum**[6] (SER-eh-BEL-um) lies inferior to the cerebrum in the posterior cranial fossa, and is separated from the cerebrum by the **transverse cerebral fissure.** It is also marked by gyri, sulci, and fissures. The cerebellum is the second-largest region of the brain, constituting about 10% of the brain's volume but containing over 50% of its neurons.

The third major part of the brain is the **brainstem,** the smallest of all and yet least dispensable to survival. Because it has such fundamental life-support functions, strokes and injuries in the brainstem are more likely to be fatal than comparable injuries to the cerebrum or cerebellum. Authorities differ on how they define *brainstem.* This book treats it as that which remains of the brain if the cerebrum and cerebellum are removed. Its major components, from rostral to caudal, are the *diencephalon, midbrain, pons,* and *medulla oblongata.*

---

[1] *rostr* = nose
[2] *caud* = tail
[3] *gyr* = turn, twist
[4] *sulc* = furrow, groove
[5] *corpus* = body; *call* = thick
[6] *cereb* = brain; *ellum* = little


Cerebral hemispheres
Frontal lobe
Central sulcus
Parietal lobe
Occipital lobe
Longitudinal fissure
Rostral
Caudal
Central sulcus
Gyri
Lateral sulcus
Temporal lobe
Brainstem
Cerebrum
Cerebellum
Spinal cord

(a) Superior view

(b) Lateral view


Precentral gyrus
Central sulcus
Frontal lobe
Insula
Temporal lobe
Postcentral gyrus
Parietal lobe
Arachnoid mater
Occipital lobe
Cerebellum
Blood vessels
Medulla oblongata

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

(c) Lateral view

Figure 15.1 Surface Anatomy of the Brain. (a) Superior view of the cerebral hemispheres. (b) Left lateral view. (c) The partially dissected brain of a cadaver. Part of the left hemisphere is cut away to expose the insula. The arachnoid mater is removed from the anterior (rostral) half of the brain to expose the gyri and sulci; the arachnoid mater with its blood vessels is seen on the posterior (caudal) half. Blood vessels of the brainstem are left in place.

- *After studying the meninges, determine which of the three had to be removed to expose any of the anatomy visible in part (c).* APR


Central sulcus
Parietal lobe
Cingulate gyrus
Corpus callosum
Frontal lobe
Parieto–occipital sulcus
Occipital lobe
Thalamus
Habenula
Pineal gland
Epithalamus
Anterior commissure
Hypothalamus
Posterior commissure
Optic chiasm
Mammillary body
Cerebral aqueduct
Pituitary gland
Fourth ventricle
Temporal lobe
Cerebellum
Midbrain
Pons
Medulla oblongata
(a)
Cingulate gyrus
Corpus callosum
Lateral ventricle
Parieto–occipital sulcus
Choroid plexus
Pineal gland
Thalamus
Occipital lobe
Hypothalamus
Midbrain
Posterior commissure
Pons
Fourth ventricle
Cerebellum
Medulla oblongata
(b)

© McGraw-Hill Education/Dennis Strete, photographer

Figure 15.2 **Medial Aspect of the Brain.** (a) Median section, left lateral view. (b) Median section of the cadaver brain. APR

The most common alternative definition includes only the last three of these. In a living person, the brainstem is oriented like a vertical stalk with the cerebrum perched on top of it like a mushroom cap. Postmortem changes give it a more oblique angle in the cadaver and consequently in many medical illustrations. Caudally, the brainstem ends at the foramen magnum of the skull, and the central nervous system (CNS) continues below this as the spinal cord.

Gray and White Matter

The brain, like the spinal cord, consists of gray and white matter. Gray matter, the site of the neurosomas, dendrites, and synapses, forms a surface layer called the **cortex** over the cerebrum and cerebellum, and deeper masses called **nuclei** surrounded by white matter (see fig. 15.4c). The white matter thus lies deep to the cortical gray matter in most of the brain, opposite from the relationship of gray and white matter in the spinal cord. As in the spinal cord, the white matter is composed of **tracts,** or bundles of axons, which here connect one part of the brain to another and to the spinal cord. It gets its bright white color from myelin. The tracts are described later in more detail.

Meninges

The brain is enveloped in three membranes, the meninges, which lie between the nervous tissue and bone. As in the spinal cord, these are the dura mater, arachnoid mater, and pia mater (fig. 15.3). They protect the brain and provide a structural framework for arteries, veins, and *dural sinuses.* In the cranial cavity, the dura mater consists of two layers—an outer *periosteal layer,* equivalent to the periosteum of the cranial bones, and an inner *meningeal layer.* Only the meningeal layer continues into the vertebral canal, where it forms the dural sheath around the spinal cord. The cranial dura mater lies closely against the cranial bone, with no intervening epidural space like the one in the vertebral canal. It is attached to the cranial bone in limited places—around the foramen magnum, the sella turcica, the crista galli, and the sutures of the skull.

In some places, the two layers of dura are separated by **dural sinuses,** spaces that collect blood that has circulated through the brain. Two major dural sinuses are the **superior sagittal sinus,** found just under the cranium along the midsagittal line, and the **transverse sinus,** which runs horizontally from the rear of the head toward each ear. These sinuses meet like an inverted T at the back of the brain and ultimately empty into the internal jugular veins of the neck. The anatomy of the dural sinuses is detailed in chapter 21.

In certain places, the meningeal layer of the dura mater folds inward to separate major parts of the brain from each other: The *falx*[7] *cerebri* (falks SER-eh-bry) extends into the longitudinal fissure as a vertical wall between the right and left cerebral hemispheres, and is shaped like the curved blade of a sickle; the *tentorium*[8]

---

[7] *falx* = sickle
[8] *tentorium* = tent



Figure 15.3 **The Meninges of the Brain.** Frontal section of the head.

(ten-TOE-ree-um) *cerebelli* stretches horizontally like a roof over the posterior cranial fossa and separates the cerebellum from the overlying cerebrum; and the vertical *falx cerebelli* partially separates the right and left halves of the cerebellum on the inferior side.

The arachnoid mater and pia mater are similar to those of the spinal cord. The arachnoid mater is a transparent membrane over the brain surface, visible in the caudal half of the cerebrum in figure 15.1c. A *subarachnoid space* separates the arachnoid from the pia, and in some places, a *subdural space* separates the dura from the


Caudal
Rostral
Lateral ventricles
Interventricular foramen
Third ventricle
Cerebral aqueduct
Fourth ventricle
Lateral aperture
Median aperture
Central canal
Cerebrum
Lateral ventricle
Interventricular foramen
Third ventricle
Cerebral aqueduct
Fourth ventricle
Lateral aperture
Median aperture

(a) Lateral view **(b) Anterior view**


Rostral (anterior)
Longitudinal fissure
Frontal lobe
Gray matter (cortex)
White matter
Lateral ventricle
Temporal lobe
Third ventricle
Lateral sulcus
Insula
Lateral ventricle
Occipital lobe
Corpus callosum (anterior part)
Caudate nucleus
Septum pellucidum
Sulcus
Gyrus
Thalamus
Choroid plexus
Corpus callosum (posterior part)
Longitudinal fissure
(c)
Caudal (posterior)

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Figure 15.4 **Ventricles of the Brain.** (a) Right lateral view. (b) Anterior view. (c) Superior view of a horizontal section of the cadaver brain, showing the lateral ventricles and some other features of the cerebrum. APR

DEEPER INSIGHT 15.1

Meningitis

Meningitis—inflammation of the meninges—is one of the most serious diseases of infancy and childhood. It occurs especially between 3 months and 2 years of age. Meningitis is caused by a variety of bacteria and viruses that invade the CNS by way of the nose and throat, often following respiratory, throat, or ear infections. The pia mater and arachnoid are most often affected, and from here the infection can spread to the adjacent nervous tissue. Meningitis can cause swelling of the brain, cerebral hemorrhaging, and sometimes death within mere hours of the onset of symptoms. Signs and symptoms include high fever, stiff neck, drowsiness, intense headache, and vomiting.

Bacterial meningitis is diagnosed partly by examining the cerebrospinal fluid (CSF) for bacteria and white blood cells. The CSF is obtained by making a *lumbar puncture (spinal tap)* between two lumbar vertebrae and drawing fluid from the subarachnoid space (see Deeper Insight 14.1, p. 375).

Death from meningitis can occur so suddenly that infants and children with a high fever should receive immediate medical attention. Freshman college students show a slightly elevated incidence of meningitis, especially those living in crowded dormitories rather than off campus.

arachnoid. The pia mater is a very thin, delicate membrane that closely follows all the contours of the brain surface, even dipping into the sulci. It is not usually visible without a microscope.

Ventricles and Cerebrospinal Fluid

The brain has four internal chambers called **ventricles.** The largest are the two **lateral ventricles,** which form an arc in each cerebral hemisphere (fig. 15.4). Through a pore called the **interventricular foramen,** each lateral ventricle is connected to the **third ventricle,** a narrow median space inferior to the corpus callosum. From here, a canal called the **cerebral aqueduct** passes down the core of the midbrain and leads to the **fourth ventricle,** a small triangular chamber between the pons and cerebellum (see fig. 15.2). Caudally, this space narrows and forms a **central canal** that extends through the medulla oblongata into the spinal cord.

On the floor or wall of each ventricle, there is a spongy mass of blood capillaries called a **choroid** (CO-royd) **plexus** (fig. 15.4c), named for its histological resemblance to the chorion of a fetus. Ependymal cells, a type of neuroglia, cover each choroid plexus, the entire interior surface of the ventricles, and the canals of the brain and spinal cord. The choroid plexuses produce cerebrospinal fluid.

Cerebrospinal fluid (CSF) is a clear, colorless liquid that fills the ventricles and canals of the CNS and bathes its external surface. The brain produces about 500 mL of CSF per day, but the fluid is constantly reabsorbed at the same rate and only 100 to 160 mL is present at one time. About 40% of it is formed in the subarachnoid space external to the brain, 30% by the general ependymal lining of the brain ventricles, and 30% by the choroid plexuses. CSF formation begins with the filtration of plasma through the blood capillaries of the brain. The ependymal cells chemically modify the filtrate as it passes through them into the ventricles and subarachnoid space.

The CSF is not a stationary fluid but continually flows through and around the CNS, driven by its own pressure, by beating of the cilia on the ependymal cells, and by rhythmic pulsations of the brain produced by each heartbeat. The CSF secreted in the lateral ventricles flows through the interventricular foramina into the third ventricle (fig. 15.5), then down the cerebral aqueduct to the fourth ventricle. The third and fourth ventricles and their choroid plexuses add more CSF along the way. A small amount of CSF fills the central canal of the spinal cord, but ultimately, all of it escapes through three pores in the walls of the fourth ventricle: a *median aperture* and two *lateral apertures.* These lead into the subarachnoid space on the surface of the brain and spinal cord. CSF is absorbed from this space by **arachnoid granulations,** cauliflower-like extensions of the arachnoid meninx that protrude through the dura mater into the superior sagittal sinus of the brain. CSF penetrates the walls of the granulations and mixes with the blood in the sinus.

Cerebrospinal fluid serves three purposes:

1. **Buoyancy.** Because the brain and CSF are very similar in density, the brain neither sinks nor floats in the CSF. It hangs from delicate specialized fibroblasts of the arachnoid meninx. A human brain removed from the body weighs about 1,500 g, but when suspended in CSF, its effective weight is only about 50 g. By analogy, consider how much easier it is to lift another person when you are immersed in a lake than it is on land. This buoyancy effect allows the brain to attain considerable size without being impaired by its own weight. If the brain rested heavily on the floor of the cranium, the pressure would kill the nervous tissue.
2. **Protection.** CSF also protects the brain from striking the cranium when the head is jolted. If the jolt is severe, however, the brain still may strike the inside of the cranium or suffer shearing injury from contact with the angular surfaces of the cranial floor. This is one of the common findings in child abuse (shaken child syndrome) and in head injuries (concussions) from auto accidents, boxing, and the like.
3. **Chemical stability.** The flow of CSF rinses metabolic wastes from the nervous tissue and homeostatically regulates its chemical environment. Slight changes in CSF composition can cause malfunctions of the nervous system. For example, a high glycine concentration disrupts the control of temperature and blood pressure, and a high pH causes dizziness and fainting.

Apply What You Know

What effect would you expect from a small brain tumor that blocked the left interventricular foramen?

Blood Supply and the Brain Barrier System

Although the brain constitutes only 2% of the adult body weight, it receives 15% of the blood (about 750 mL/min.) and consumes



① CSF is secreted by choroid plexus in each lateral ventricle.

② CSF flows through interventricular foramina into third ventricle.

③ Choroid plexus in third ventricle adds more CSF.

④ CSF flows down cerebral aqueduct to fourth ventricle.

⑤ Choroid plexus in fourth ventricle adds more CSF.

⑥ CSF flows out two lateral apertures and one median aperture.

⑦ CSF fills subarachnoid space and bathes external surfaces of brain and spinal cord.

⑧ At arachnoid granulations, CSF is reabsorbed into venous blood of dural venous sinuses.

Figure 15.5 The Flow of Cerebrospinal Fluid.

20% of the oxygen and glucose. But despite its critical importance to the brain, blood is also a source of agents such as bacterial toxins and antibodies that can harm the brain tissue. Damaged brain tissue is essentially irreplaceable, and the brain therefore must be well protected. Consequently, there is a **brain barrier system** that strictly regulates what substances get from the bloodstream into the tissue fluid of the brain.

One component of this system is the **blood–brain barrier (BBB),** which seals nearly all of the blood capillaries throughout the brain tissue. In the developing brain, astrocytes reach out and contact the capillaries with their perivascular feet. They do not fully surround the capillary, but stimulate the formation of tight junctions between the *endothelial cells* that line it. These junctions and the basement membrane around them constitute the BBB. Anything passing from the blood into the tissue fluid has to pass through the endothelial cells themselves, which are more selective than gaps between the cells can be.

At the choroid plexuses, there is a similar **blood–CSF barrier,** composed of ependymal cells joined by tight junctions. Tight junctions are absent from ependymal cells elsewhere, because it is important to allow exchanges between the brain tissue and CSF. That is, there is no brain–CSF barrier.

The brain barrier system (BBS) is highly permeable to water; glucose; lipid-soluble substances such as oxygen and carbon dioxide; and drugs such as alcohol, caffeine, nicotine, and anesthetics. While the BBS is an important protective device, it is an obstacle to the delivery of drugs such as antibiotics and cancer drugs, and thus complicates the treatment of brain diseases.

The BBB is absent from patches called **circumventricular organs (CVOs)** on the walls of the third and fourth ventricles. Here, the blood has direct access to the brain tissue, enabling the brain to monitor and respond to fluctuations in blood chemistry. Unfortunately, the CVOs also afford a route for the human immunodeficiency virus (HIV) to invade the brain.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. List the three major parts of the brain and describe their locations.
2. Define *gyrus* and *sulcus.*
3. Name the parts of the brainstem from caudal to rostral.
4. Name the three meninges from superficial to deep.
5. Describe three functions of the cerebrospinal fluid.
6. Where does the CSF originate, and what route does it take through and around the CNS?
7. Name the two components of the brain barrier system and explain the importance of this system.

15.2 The Hindbrain and Midbrain

Expected Learning Outcomes

When you have completed this section, you should be able to

a. list the components of the hindbrain and midbrain;
b. describe the major features of their anatomy; and
c. explain the functions of each hindbrain and midbrain region.

We will survey the functional anatomy of the brain in a caudal to rostral direction, beginning with the hindbrain and its relatively simple functions, and progressing to the forebrain, the seat of such complex functions as thought, memory, and emotion. This survey will be organized around the five secondary vesicles of the embryonic brain and their mature derivatives, as described in chapter 13.

The Medulla Oblongata

The embryonic hindbrain differentiates into two subdivisions, the myelencephalon and metencephalon (see fig. 13.14, p. 366). The myelencephalon gives rise to just one structure, the **medulla oblongata** (meh-DULL-uh OB-long-GAH-ta).

The medulla begins at the foramen magnum of the skull and extends for 3 cm rostrally, ending at a groove marking the boundary between medulla and pons. The medulla contains all nerve fibers that travel between the brain and spinal cord. Four pairs of cranial nerves begin or end at nuclei in the medulla. The medulla also contains several nuclei concerned with basic physiological functions: a **cardiac center,** which regulates the rate and force of the heartbeat; a **vasomotor center,** which regulates blood pressure and flow by dilating and constricting blood vessels; two **respiratory centers,** which regulate the rate and depth of breathing; and others involved in speech, coughing, sneezing, salivation, swallowing, gagging, vomiting, and sweating.

The external anatomy of the medulla oblongata is shown in figure 15.6. The anterior surface bears a pair of clublike ridges, the **pyramids.** Resembling side-by-side baseball bats, the pyramids are wider at the rostral end, taper caudally, and are separated by a longitudinal groove, the *anterior median fissure,* continuous with that of the spinal cord (fig. 15.6a). Lateral to each pyramid is a prominent bulge called the **olive.** The posterior surface of the medulla exhibits two pairs of ridges, the gracile and cuneate fasciculi, a continuation of the ones in the spinal cord (see pp. 377–378).

Figure 15.7c shows some of the internal structure of the medulla oblongata. Cross sections at other levels would reveal different structures, but in this representative section, we see the following:

- The **corticospinal tracts,** seen anteriorly (at the bottom of the figure). These tracts occupy the pyramids and consist of nerve fibers that descend from the cerebral cortex carrying motor signals to the spinal cord. About 90% of these fibers cross over (decussate) to the opposite side of the brainstem at a point called the *pyramidal decussation* near the caudal end of the pyramids (fig. 15.6a). As a result, muscles below the neck are controlled by the contralateral side of the brain.
- The **inferior olivary nucleus,** a wavy layer of gray matter immediately posterior to each corticospinal tract, occupying the olive. This nucleus receives signals from many levels of the brain and spinal cord and relays them mainly to the cerebellum.
- The **reticular formation,** a vaguely defined region of gray matter posterior to the inferior olivary nucleus. The reticular formation is an elongated body that begins in the upper spinal cord and ascends through the medulla, pons, and midbrain. It consists of numerous nuclei involved in many of the body's most basic physiological functions, some of which are discussed later in this chapter.
- The **gracile** and **cuneate nuclei,** where sensory fibers of the corresponding fasciculi terminate. These fibers synapse here with second-order nerve fibers that decussate and form the ribbonlike **medial lemniscus.**[9] In the lemniscus, they continue up the brainstem to the thalamus, synapsing there with third-order neurons that convey the signals to the cerebrum and one's conscious awareness.
- The **tectospinal tract,** posterior to the medial lemniscus, carries motor signals on their way to the cervical spinal cord. This tract mediates movements of the head and neck.
- The **posterior spinocerebellar tract** continues from the spinal cord into the posterolateral margins of the medulla. It carries sensory information destined for the cerebellum.
- The **fourth ventricle** is a CSF-filled space between the medulla and cerebellum (see fig. 15.2); the medulla forms its anterior boundary but does not completely contain it.
- **Cranial nerves** VIII, IX, X, and XII begin or end in the medulla oblongata. Their Latin names and individual functions are provided in table 15.3, starting on page 429.

---

[9] *lemn* = ribbon; *iscus* = little


Diencephalon:
Thalamus
Infundibulum
Mammillary body
Midbrain:
Cerebral peduncle
Pons
Medulla oblongata:
Pyramid
Anterior median fissure
Pyramidal decussation
Spinal cord
Optic tract
Cranial nerves:
Optic nerve (II)
Oculomotor nerve (III)
Trochlear nerve (IV)
Trigeminal nerve (V)
Abducens nerve (VI)
Facial nerve (VII)
Vestibulocochlear nerve (VIII)
Glossopharyngeal nerve (IX)
Vagus nerve (X)
Accessory nerve (XI)
Hypoglossal nerve (XII)
Spinal nerves
Regions of the brainstem
🟦 Diencephalon
🟧 Midbrain
🟩 Pons
🟩 Medulla oblongata

(a) Ventral view


Diencephalon:
Thalamus
Lateral geniculate body
Pineal gland
Medial geniculate body
Midbrain:
Superior colliculus
Inferior colliculus
Cerebral peduncle
Pons
Fourth ventricle
Medulla oblongata
Optic tract
Superior cerebellar peduncle
Middle cerebellar peduncle
Inferior cerebellar peduncle
Olive
Cuneate fasciculus
Gracile fasciculus
Spinal cord

(b) Dorsolateral view

Figure 15.6 The Brainstem. These illustrations are color-coded to match the embryonic origins in figure 13.14 (p. 366). The boundary between the middle and inferior cerebellar peduncles is indistinct. Authorities vary on whether to include the diencephalon in the brainstem. APR


Posterior
Tectum
Superior colliculus
Cerebral aqueduct
Medial geniculate nucleus
Reticular formation
Central gray matter
Cerebral peduncle:
Tegmentum
Oculomotor nucleus
Medial lemniscus
Red nucleus
Substantia nigra
Cerebral crus
Oculomotor nerve (III)
Anterior

(a) Midbrain


(a) Midbrain
(b) Pons
(c) Medulla


Vermis of cerebellum
Fourth ventricle
Superior cerebellar peduncle
Middle cerebellar peduncle
Anterior spinocerebellar tract
Trigeminal nerve nuclei
Tectospinal tract
Sensory root of trigeminal nerve
Anterolateral system
Trigeminal nerve
Reticular formation
Transverse fascicles
Medial lemniscus
Longitudinal fascicles

(b) Pons


Nucleus of hypoglossal nerve
Gracile nucleus
Fourth ventricle
Cuneate nucleus
Nucleus of vagus nerve
Posterior spinocerebellar tract
Trigeminal nerve:
Nucleus
Tract
Reticular formation
Tectospinal tract
Medial lemniscus
Inferior olivary nucleus
Olive
Hypoglossal nerve
Corticospinal tract
Pyramids of medulla

(c) Medulla oblongata

Figure 15.7 Cross Sections of the Brainstem. The level of each section is shown in the figure on the right, and all sections are shown with the posterior surface uppermost. (a) The midbrain, cut obliquely to pass through the superior colliculi. (b) The pons. The straight edges indicate cut edges of the peduncles where the cerebellum was removed. (c) The medulla oblongata.

- *Trace the route taken through all three of these sections by fibers from the gracile and cuneate fasciculi described in chapter 14.* AP|R

At the level of the tissue section in figure 15.7c, we see the nuclei of two of these, the vagus (X) and hypoglossal (XII) nerves. The trigeminal nerve (V) emerges from the pons, but its nucleus extends into the medulla and is also visible in this figure. Collectively, the sensory functions of cranial nerves VIII to XII include touch, pressure, temperature, taste, hearing, and pain. Their motor functions include chewing; swallowing; speech; respiration; cardiovascular control; gastrointestinal motility and secretion; and head, neck, and shoulder movements.

The Pons

The metencephalon develops into the pons and cerebellum. The **pons**[10] measures about 2.5 cm long. Most of it forms a broad anterior bulge in the brainstem just rostral to the medulla (fig. 15.6a). Posteriorly, the pons consists mainly of two pairs of thick stalks called *peduncles* that attach it to the cerebellum (fig. 15.6b); these are the cut edges of the upper half of figure 15.7b. The peduncles are further described with the cerebellum. The pons contains several nuclei involved in basic physiological functions including sleep, respiration, and bladder control.

In cross section, the pons exhibits continuations of the reticular formation, medial lemniscus, and tectospinal tract, all mentioned previously, as well as the following:

- Continuations of two spinal cord sensory tracts described in chapter 14—the **anterolateral system,** which contains the *spinothalamic tract* en route to the thalamus, and the **anterior spinocerebellar tract,** carrying signals en route to the cerebellum.
- Cranial nerves V through VIII begin or end in the pons, although we see only V (the trigeminal nerve) at the level of the cross section in figure 15.7b. The other three nerves emerge from the groove between the pons and medulla (see fig. 15.23); nerve VIII has endings in both the medulla and pons. Their individual names and functions are provided in table 15.3. Collectively, the sensory functions of these four nerves include hearing, equilibrium, taste, and facial sensations such as touch and pain. Their motor functions include eye movements, facial expressions, chewing, swallowing, and the secretion of saliva and tears.
- Tracts of white matter in the anterior half of the pons (lower half of the figure), including transverse fascicles that cross from left to right and connect the two hemispheres of the cerebellum, and longitudinal fascicles that course up and down the pons carrying signals ascending to the thalamus and signals descending from the cerebrum to the cerebellum and medulla.
- Part of the fourth ventricle is seen bordered by the pons, the tail-like *vermis* of the cerebellum, and the superior cerebellar peduncles.

Even though the cerebellum is part of the metencephalon, it is not part of the brainstem. It will be clearer to continue this brainstem discussion with the midbrain and then return to the cerebellum.

The Midbrain

The embryonic mesencephalon produces just one mature brain structure, the **midbrain**—a short segment of the brainstem that connects the hindbrain and forebrain (see fig. 15.2). The midbrain, too, contains continuations of the reticular formation and medial lemniscus. The cerebral aqueduct—the channel connecting the third ventricle to the fourth—passes through the midbrain and furnishes a useful landmark in figure 15.7a. Relative to the aqueduct, this cross section of the midbrain exhibits the following structures:

- The **central (periaqueductal) gray matter,** a region of gray matter surrounding the aqueduct. This functions with the reticular formation in controlling our awareness of pain (see chapter 17).
- The **tectum,**[11] a rooflike region posterior to the aqueduct. The tectum exhibits four bulges collectively called the *corpora quadrigemina*[12]—a rostral pair called the superior colliculi and a caudal pair called the inferior colliculi (fig. 15.6b). The **superior colliculi**[13] (col-LIC-you-lye) function in visual attention, such as visually tracking moving objects and reflexively turning the eyes and head in response to a visual stimulus—for example, to look at something you catch sight of in your peripheral vision. The **inferior colliculi** receive and process auditory input from lower levels of the brainstem and relay it to other parts of the brain, especially the thalamus. They are sensitive to time delays between sounds heard by the two ears and thus aid in locating the source of a sound in space, and they function in auditory reflexes such as turning the head toward a sound and the startle response to a loud noise.
- The **tegmentum,**[14] the main mass of the midbrain, located anterior to the aqueduct. The tegmentum contains the **red nucleus,** named for the pink color it gets from a high density of blood vessels. Fibers from the red nucleus form the *rubrospinal tract* in most mammals, but in humans its connections go mainly to and from the cerebellum, with which it collaborates in fine motor control.
- The **substantia nigra**[15] (sub-STAN-she-uh NY-gruh), a dark gray to black nucleus pigmented with melanin, located between the tegmentum and cerebral crura (discussed next). This is a motor center that relays inhibitory signals to the thalamus and basal nuclei (both discussed later). It improves motor performance by suppressing unwanted muscle contractions. Degeneration of the substantia nigra leads to the uncontrollable muscle tremors of Parkinson disease (see p. 439).
- The **cerebral crura** (CROO-ra; singular, *crus*[16]), which anchor the cerebrum to the brainstem. The crura, tegmentum, and substantia nigra collectively form the *cerebral peduncle.* Corticospinal and other tracts from the cerebrum descend through the crura on their way to lower levels of the brainstem and spinal cord.

---

[10] *pons* = bridge

[11] *tectum* = roof, cover

[12] *corpora* = bodies; *quadrigemina* = quadruplets

[13] *colli* = hill; *cul* = little

[14] *tegmen* = cover

[15] *substantia* = substance; *nigra* = black

[16] *crus* = leg


Radiations to cerebral cortex
Thalamus
Visual input
Auditory input
Reticular formation
Ascending general sensory fibers
Descending motor fibers to spinal cord

Figure 15.8 **The Reticular Formation.** The formation consists of over 100 nuclei scattered through the brainstem. Red arrows indicate routes of input to the reticular formation; blue arrows indicate the radiating relay of signals from the thalamus to the cerebral cortex; and green arrows indicate output from the reticular formation to the spinal cord.
• *Locate components of the reticular formation in all three parts of figure 15.7.*

- Cranial nerves III and IV, both concerned with eye movements, originate in the midbrain; only III (the oculomotor nerve) is visible at the level of the section in figure 15.7a.

This figure also shows the *medial geniculate nucleus,* but this is part of the thalamus, not the midbrain. It just happens to lie in the plane of this section. The *superior cerebellar peduncles* connect to the midbrain, but are not seen at this level.

The Reticular Formation

The **reticular**[17] **formation** is a loosely organized web of gray matter that runs vertically through all levels of the brainstem and has connections with many areas of the cerebrum (fig. 15.8). It occupies much of the space between the white fiber tracts and the more anatomically distinct brainstem nuclei. It consists of more than 100 small neural networks without well-defined boundaries. The functions of these networks include the following:

- **Somatic motor control.** Some motor neurons of the cerebral cortex and cerebellum send their axons to reticular formation nuclei, which then give rise to the *reticulospinal tracts* of the spinal cord. These tracts adjust muscle tension to maintain tone, balance, and posture, especially during body movements. The reticular formation also relays signals from the eyes and ears to the cerebellum so the cerebellum can integrate visual, auditory, and vestibular (balance and motion) stimuli into its role in motor coordination. Other reticular formation motor nuclei include *gaze centers,* which enable the eyes to track and fixate on objects, and *central pattern generators*—neural pools that produce rhythmic signals to the muscles of breathing and swallowing.
- **Cardiovascular control.** The reticular formation includes the previously mentioned cardiac and vasomotor centers of the medulla oblongata.
- **Pain modulation.** The reticular formation is one route by which pain signals from the lower body reach the cerebral cortex. It is also the origin of the *descending analgesic fibers* discussed in chapter 17 (p. 466). The nerve fibers in these pathways act in the spinal cord to block the transmission of pain signals to the brain.
- **Sleep and consciousness.** The reticular formation has projections to the cerebral cortex and thalamus that allow it some control over what sensory signals reach the cerebrum and come to our conscious attention. It plays a central role in states of consciousness such as alertness and sleep. Injury to the reticular formation can result in irreversible coma.
- **Habituation.** This is the process in which the brain learns to ignore repetitive, inconsequential stimuli while remaining sensitive to others. In a noisy city, for example, a person can sleep through traffic sounds but wake promptly to the sound of an alarm clock or a crying baby. The reticular formation screens out insignificant stimuli, preventing them from arousing cerebral centers of consciousness while it permits important or unusual sensory signals to pass. Reticular formation nuclei that modulate activity of the cerebral cortex are called the *reticular activating system* or *extrathalamic cortical modulatory system.*

The Cerebellum

The **cerebellum** is the largest part of the hindbrain and second-largest part of the brain as a whole. It consists of right and left **cerebellar hemispheres** connected by a narrow wormlike bridge, the **vermis**[18] (fig. 15.9). Each hemisphere exhibits slender, parallel folds called **folia**[19] separated by shallow sulci. The cerebellum has a surface cortex of gray matter and a deeper layer of white matter. In a sagittal section, the white matter shows a branching fernlike pattern called the **arbor vitae.**[20] Each hemisphere also has four masses of gray matter called **deep nuclei** embedded in the white matter. All cerebellar input goes to the cortex and all output comes from the deep nuclei.

The cerebellum is connected to the brainstem by three pairs of stalks called **cerebellar peduncles**[21] (peh-DUN-culs): Two *inferior*

---

[17] *ret* = network; *icul* = little

[18] *verm* = worm

[19] *foli* = leaf

[20] *arbor* = tree; *vitae* = of life

[21] *ped* = foot; *uncle* = little


Superior colliculus
Inferior colliculus
Pineal gland
Posterior commissure
Cerebral aqueduct
Mammillary body
Midbrain
White matter (arbor vitae)
Oculomotor nerve
Gray matter
Fourth ventricle
Pons
Medulla oblongata
(a) Median section
Anterior
Vermis
Anterior lobe
Posterior lobe
Folia
Cerebellar hemisphere
Posterior
(b) Superior view

Figure 15.9 **The Cerebellum.** (a) Median section, showing relationship to the brainstem. (b) Superior view. APR

peduncles connect it to the medulla oblongata, two *middle peduncles* to the pons, and two *superior peduncles* to the midbrain (see fig. 15.6b). These consist of thick bundles of nerve fibers that carry signals into and out of the cerebellum. Connections between the cerebellum and brainstem are complex, but overlooking some exceptions, we can draw a few generalizations. Most spinal input to the cerebellum comes from the spinocerebellar tracts and travels through the inferior peduncles; input from the rest of the brain enters by way of the middle peduncles; and the superior peduncles carry most cerebellar output.

The cerebellum monitors body movements by means of information coming from the muscles and joints via the spinocerebellar tracts (fig. 15.10a). The middle peduncles carry signals from the cerebrum about what the muscles were commanded to do, enabling the cerebellum to compare the command with the performance. These peduncles also carry information from the eyes and ears for hearing and the perception of body position and movement. Output through the superior peduncles leads to various points in the midbrain and thalamus. The thalamus relays cerebellar signals to the cerebral cortex so that the cerebrum can make fine adjustments in muscle performance (fig. 15.10b).

Although it is only 10% of the mass of the brain, the cerebellum has about 60% as much surface area as the cerebral cortex and contains more than half of all brain neurons—about 100 billion of them. Its tiny, densely spaced **granule cells** are the most abundant neurons in the entire brain. Its most distinctive neurons, however, are the large globose **Purkinje**[22] (pur-KIN-jee) **cells.** These have a tremendous profusion of dendrites compressed into a single plane like a flat tree (see fig. 13.5 top panel, p. 356, and the photograph on p. 351). Purkinje cells are arranged in single file, with these thick dendritic planes parallel to each other like books on a shelf. Their axons travel to the deep nuclei, where they synapse on output neurons that issue fibers to the brainstem.

The function of the cerebellum was unknown in the 1950s. By the 1970s, it had come to be regarded as a control center of

---

[22] Johannes E. von Purkinje (1787–1869), Bohemian anatomist


(a) Input to cerebellum
Motor cortex
Cerebrum
Cerebellum
Reticular formation
Brainstem
Eye
Inner ear
Spinocerebellar tracts of spinal cord
Muscle and joint proprioceptors
(b) Output from cerebellum
Cerebrum
Cerebellum
Brainstem
Reticulospinal and vestibulospinal tracts of spinal cord
Limb and postural muscles

Figure 15.10 **Principal Pathways of Cerebellar Input and Output.** (a) Afferent pathways sending input to the cerebellum. (b) Efferent pathways sending output from the cerebellum to the cerebrum and muscles.

TABLE 15.1 Hindbrain and Midbrain Functions

Medulla oblongata	Origin or termination of cranial nerves IX, X, and XII and some fibers of VIII. Sensory nuclei receive input from the taste buds, pharynx, and thoracic and abdominal viscera. Motor nuclei include the cardiac center (adjusts the rate and force of the heartbeat), vasomotor center (controls blood vessel diameter and blood pressure), two respiratory centers (control the rate and depth of breathing), and centers involved in speech, coughing, sneezing, salivation, swallowing, gagging, vomiting, sweating, gastrointestinal secretion, and movements of the tongue and head.
Pons	Sensory terminations and motor origins of cranial nerves V–VII and some fibers of VIII. Sensory nuclei receive input from the face, eyes, oral and nasal cavities, sinuses, and meninges, concerned with pain, touch, temperature, taste, hearing, and equilibrium. Cranial nerve motor nuclei control chewing, swallowing, eye movements, middle- and inner-ear reflexes, facial expression, and secretion of tears and saliva. Other nuclei of pons relay signals from cerebrum to cerebellum (provide most of the input to the cerebellum) or function in sleep, respiration, bladder control, and posture.
Midbrain	Origin of cranial nerves III–IV (concerned with eye movements). Red nucleus is concerned with fine motor control. Substantia nigra relays inhibitory signals to thalamus and basal nuclei of forebrain. Central gray matter modulates awareness of pain. Superior colliculi are concerned with visual attention and tracking movements of eyes, and visual reflexes such as shifting gaze to objects seen moving in peripheral vision. Inferior colliculi relay auditory signals to thalamus and mediate auditory reflexes such as the startle response to a loud noise.
Reticular formation	A network of over 100 nuclei extending throughout brainstem, including some nuclei described earlier in this table. Involved in somatic motor control, equilibrium, visual attention, breathing, swallowing, cardiovascular control, pain modulation, sleep, and consciousness.
Cerebellum	Muscular coordination, fine motor control, muscle tone, posture, equilibrium, judging passage of time; some involvement in emotion, processing tactile input, spatial perception, and language.

motor coordination. Now, however, positron emission tomography (PET), functional magnetic resonance imaging (fMRI), and behavioral studies of people with cerebellar lesions have created a much more expansive view of cerebellar function. It appears that the main role of the cerebellum is the subconscious evaluation of diverse kinds of sensory input; monitoring the movements of muscles is only a part of that general role. People with cerebellar lesions exhibit serious deficits in locomotor ability, but also in several sensory, linguistic, emotional, cognitive, and other nonmotor functions. More will be said of these later in the chapter.

Table 15.1 summarizes the hindbrain and midbrain functions discussed in the last several pages.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

8. Name several functions controlled by nuclei of the medulla.
9. Describe the anatomical and functional relationship of the pons to the cerebellum.
10. What are the functions of the corpora quadrigemina, substantia nigra, and central gray matter?
11. Describe the reticular formation and list several of its functions.
12. Describe the general functions of the cerebellum.

15.3 The Forebrain

Expected Learning Outcomes

When you have completed this section, you should be able to

a. name the three major components of the diencephalon and describe their locations and functions;
b. locate the five lobes of the cerebrum and identify their functions;
c. describe the three types of tracts in the cerebral white matter;
d. describe the distinctive cell types and histological arrangement of the cerebral cortex; and
e. discuss the locations and functions of the basal nuclei and limbic system.

The forebrain consists of the diencephalon and cerebrum. As noted earlier, some authorities treat the diencephalon as the most rostral part of the brainstem, while others exclude it from the brainstem.

The Diencephalon

The embryonic diencephalon has three major derivatives: the *thalamus, hypothalamus,* and *epithalamus.* These structures surround the third ventricle of the brain.

The Thalamus

Each side of the brain has a **thalamus,**[23] an ovoid mass perched at the superior end of the brainstem beneath the cerebral hemisphere (see figs. 15.4c, 15.6, and 15.15). The thalami constitute about four-fifths of the diencephalon. They protrude medially into the third ventricle and laterally into the lateral ventricles. In about 70% of people, the two thalami are joined medially by a narrow *intermediate mass.*

The thalamus is composed of at least 23 nuclei, but we will consider only five major functional groups into which most of these are classified: the anterior, medial, ventral, lateral, and posterior groups. These regions and their functions are shown in figure 15.11a.

---

[23] *thalamus* = chamber, inner room



(a) Thalamus

(b) Hypothalamus

	Thalamic nuclei	
🟨	Anterior group	Part of limbic system; memory and emotion
🟩	Medial group	Emotional output to prefrontal cortex; awareness of emotions
🟥	Ventral group	Somatosensory output to postcentral gyrus; signals from cerebellum and basal nuclei to motor areas of cortex
🟪	Lateral group	Somatosensory output to association areas of cortex; contributes to emotional function of limbic system
🟦	Posterior group	Relay of visual signals to occipital lobe (via lateral geniculate nucleus) and auditory signals to temporal lobe (via medial geniculate nucleus)
	Hypothalamic nuclei	
🟧	Anterior nucleus	Thirst center; thermoregulation
🟦	Arcuate nucleus	Regulates appetite; secretes releasing hormones that regulate anterior pituitary
🟦	Dorsomedial nucleus	Rage and other emotions
🟪	Mammillary nuclei	Relay between limbic system and thalamus; involved in long-term memory
🟪	Paraventricular nucleus	Produces oxytocin (involved in childbirth, lactation, orgasm); controls posterior pituitary
🟨	Posterior nucleus	Functions with periaqueductal gray matter of midbrain in emotional, cardiovascular, and pain control
🟩	Preoptic nucleus	Hormonal control of reproductive functions; monitors body temperature
🟥	Suprachiasmatic nucleus	Biological clock; regulates circadian rhythms and female reproductive cycle
🟨	Supraoptic nucleus	Produces antidiuretic hormone (involved in water balance); controls posterior pituitary
🟩	Ventromedial nucleus	Plays role in glucose and lipid metabolism, appetite, thermoregulation, sexual behavior, and emotion

Figure 15.11 **The Diencephalon.** Only some of the nuclei of the thalamus and hypothalamus are shown, and some of their functions listed. These lists are by no means complete. The third component of the diencephalon, the epithalamus, is not shown here; see figure 15.2a. APR

Generally speaking, the thalamus is the "gateway to the cerebral cortex." Nearly all sensory input and other information going to the cerebrum passes by way of synapses in the thalamic nuclei, including signals for taste; smell; hearing; equilibrium; vision; and such somatosensory functions as touch, pain, pressure, heat, and cold. The thalamic nuclei filter this information and relay only a small portion of it to the cerebral cortex.

The thalamus also plays a key role in motor control; it relays signals from the cerebellum to the cerebrum and provides feedback loops between the cerebral cortex and *basal nuclei* (deep cerebral motor centers). Finally, the thalamus is involved in the memory and emotional functions of the *limbic system,* a complex of structures that includes the cerebral cortex of the temporal and frontal lobes and some of the anterior thalamic nuclei. The role of the thalamus in motor and sensory circuits is further discussed later in this chapter and in chapter 17.

The Hypothalamus

The **hypothalamus** forms part of the walls and floor of the third ventricle. It extends anteriorly to the *optic chiasm* (ky-AZ-um), where the optic nerves meet, and posteriorly to and including a pair of humps called the *mammillary*[24] *bodies* (see fig. 15.2a). The mammillary bodies each contain three to four *mammillary nuclei.* Their primary function is to relay signals from the limbic system to the thalamus. The pituitary gland is attached to the hypothalamus by a stalk *(infundibulum)* between the optic chiasm and mammillary bodies.

The hypothalamus is the major control center of the autonomic nervous system and endocrine system and plays an essential role in the homeostatic regulation of nearly all organs of the body. Its nuclei include centers concerned with a wide variety of visceral functions (fig. 15.11b):

- **Hormone secretion.** The hypothalamus secretes hormones that control the anterior pituitary gland. Acting through the pituitary, it regulates growth, metabolism, reproduction, and stress responses. It also produces two hormones that are stored in the posterior pituitary gland—*oxytocin* concerned with labor contractions, lactation, and emotional bonding, and *antidiuretic hormone* concerned with water conservation. It sends nerve signals to the posterior pituitary to stimulate release of these hormones at appropriate times.
- **Autonomic effects.** The hypothalamus is a major integrating center for the autonomic nervous system. It sends descending fibers to nuclei lower in the brainstem that influence heart rate, blood pressure, pupillary diameter, and gastrointestinal secretion and motility, among other functions.
- **Thermoregulation.** The *hypothalamic thermostat* consists of a collection of neurons, concentrated especially in the preoptic nucleus, that monitor body temperature. When the body temperature deviates too much from normal, this center activates either a heat-loss center in the anterior hypothalamus or a heat-promoting center near the mammillary bodies in the posterior hypothalamus. Those centers activate mechanisms for raising or lowering the body temperature—shivering, sweating, or cutaneous vasoconstriction or vasodilation.
- **Food and water intake.** The hypothalamus regulates sensations of hunger and satiety. One nucleus in particular, the *arcuate nucleus,* has receptors for hormones that regulate short-term appetite and long-term body mass. Hypothalamic neurons called *osmoreceptors* monitor the osmolarity of the blood and stimulate water-seeking and drinking behavior when the body is dehydrated. Thus, our drives to eat and drink are under hypothalamic control.
- **Sleep and circadian rhythms.** The caudal part of the hypothalamus is part of the reticular formation. It contains nuclei that regulate the rhythm of sleep and waking. Superior to the optic chiasm, the hypothalamus contains a *suprachiasmatic nucleus* that controls our 24-hour *(circadian) rhythm* of activity.
- **Emotional and sexual responses.** The hypothalamus contains nuclei for a variety of emotional responses including anger, aggression, fear, pleasure, and contentment; and for sexual drive, copulation, and orgasm. The mammillary bodies provide a pathway by which emotional states can affect visceral function—for example, when anxiety accelerates the heart or upsets the stomach.
- **Memory.** In addition to their role in emotional circuits, the mammillary bodies lie in the pathway from the hippocampus to the thalamus. The hippocampus is a center for the creation of new memories—the cerebrum's "teacher"—so as intermediaries between the hippocampus and cerebral cortex, the mammillary bodies are essential for the acquisition of new memories.

The Epithalamus

The **epithalamus** consists mainly of the **pineal gland** (an endocrine gland discussed in chapter 18), the **habenula** (a relay from the limbic system to the midbrain), and a thin roof over the third ventricle (see fig. 15.2a).

The Cerebrum

The embryonic telencephalon becomes the cerebrum, the largest and most conspicuous part of the human brain. Your cerebrum enables you to turn these pages, read and comprehend the words, remember ideas, talk about them with others, and take an examination. It is the seat of sensory perception, voluntary motor actions, memory, and mental processes such as thought, judgment, and imagination, which most distinguish humans from other animals. It is the most complex and challenging frontier of neurobiology.

Gross Anatomy

The cerebrum so dwarfs and conceals the other structures that people often think of "cerebrum" and "brain" as synonymous. Its major anatomical landmarks were described on page 399 and should be reviewed if necessary (see figs. 15.1 and 15.2)—especially the two *cerebral hemispheres,* separated by the *longitudinal fissure* but connected by a prominent fiber tract, the *corpus callosum;* and the conspicuous wrinkles, or *gyri,* of each hemisphere, separated by grooves called *sulci.* The folding of the cerebral surface into gyri allows a greater amount of cortex to fit in the cranial cavity. The gyri give the cerebrum a surface area of about 2,500 cm^2, comparable to 4.5 pages of this book. If the cerebrum had a smooth surface, it would have only one-third as much area and proportionately less information-processing capability. This extensive folding is one of the greatest differences between the human brain and the relatively smooth-surfaced brains of most other mammals.

---

[24] *mammill* = nipple, little breast

Some gyri have consistent and predictable anatomy; others vary from brain to brain and from the right hemisphere to the left. Certain unusually prominent sulci divide each hemisphere into five anatomically and functionally distinct lobes, listed next. The first four of these are visible superficially and are named for the cranial bones overlying them (fig. 15.12); the fifth lobe is not visible from the surface.

1. The **frontal lobe** lies immediately behind the frontal bone, superior to the eyes. From the forehead, it extends caudally to a wavy vertical groove, the **central sulcus.** It is concerned with cognition (thought) and other higher mental processes, speech, and motor control.
2. The **parietal lobe** forms the uppermost part of the brain and underlies the parietal bone. Starting at the central sulcus, it extends caudally to the **parieto–occipital sulcus,** visible on the medial surface of each hemisphere (see fig. 15.2). It is the primary site for receiving and interpreting signals of the *general senses* described later in this chapter; taste (one of the *special senses*); and some visual processing.
3. The **occipital lobe** is at the rear of the head, caudal to the parieto–occipital sulcus and underlying the occipital bone. It is the principal visual center of the brain.
4. The **temporal lobe** is a lateral, horizontal lobe deep to the temporal bone, separated from the parietal lobe above it by a deep **lateral sulcus.** Among its functions are hearing, smell, learning, memory, and some aspects of vision and emotion.
5. The **insula**[25] is a small mass of cortex deep to the lateral sulcus, made visible only by retracting or cutting away some of the overlying cerebrum (see figs. 15.1c, 15.4c, and 15.15). It is less understood than the other lobes because it is less accessible to testing in living subjects, but it apparently plays roles in taste, visceral sensation, and understanding spoken language.

The Cerebral White Matter

Most of the volume of the cerebrum is white matter. This is composed of glia and myelinated nerve fibers that conduct signals from one region of the cerebrum to another and between the cerebrum and lower brain centers. These fibers travel in bundles called tracts. There are three types of cerebral tracts (fig. 15.13):

1. **Projection tracts** extend vertically between higher and lower brain or spinal cord centers and carry information between the cerebrum and the rest of the body. The corticospinal tracts, for example, carry motor signals from the cerebrum to the brainstem and spinal cord. Other projection tracts carry signals upward to the cerebral cortex. Superior to the brainstem, such tracts form a dense band called the *internal capsule* between the thalamus and basal nuclei, then radiate in a diverging, fanlike array (the *corona radiata*[26]) to specific areas of the cortex.
2. **Commissural tracts** cross from one cerebral hemisphere to the other through bridges called **commissures** (COM-ih-shurs). The great majority of commissural fibers pass through the corpus callosum. A few pass through the much



Figure 15.12 **Lobes of the Cerebrum.** The frontal and temporal lobes are retracted slightly to reveal the insula. APR

---

[25] *insula* = island
[26] *corona* = crown; *radiata* = radiating


Association tracts
Frontal lobe
Corpus callosum
Temporal lobe
Projection tracts
Parietal lobe
Occipital lobe

(a) Sagittal section


Longitudinal fissure
Corpus callosum
Basal nuclei
Cerebral peduncle
Projection tracts
Decussation in pyramids
Commissural tracts
Lateral ventricle
Thalamus
Third ventricle
Mammillary body
Pons
Pyramid
Medulla oblongata

(b) Frontal section

Figure 15.13 **Tracts of Cerebral White Matter.** (a) Sagittal section, showing association (red) and projection (green) tracts. (b) Frontal section, showing commissural (yellow) and projection tracts.

smaller **anterior** and **posterior commissures** (see fig. 15.2a). Commissural tracts enable the two cerebral hemispheres to communicate with each other.

3. **Association tracts** connect different regions of the same hemisphere. *Long association fibers* connect different lobes to each other, whereas *short association fibers* connect different gyri within a single lobe. Among their roles, association tracts link perceptual and memory centers of the brain; for example, they enable you to smell a rose, name it, and picture what it looks like.

The Cerebral Cortex

Neural integration is carried out in the gray matter of the cerebrum, which is found in three places—the cerebral cortex, basal nuclei, and limbic system. The **cerebral cortex**[27] is a layer about 2 to 3 mm thick covering the surface of the hemispheres. It constitutes about 40% of the mass of the brain and contains 14 to 16 billion neurons. It possesses two principal types of neurons called stellate and pyramidal cells (fig. 15.14). **Stellate cells** are anaxonic neurons with spheroidal somas and dendrites that project for short distances in all directions. They are concerned largely with receiving sensory input and processing information on a local level. **Pyramidal cells** are tall and conical (triangular in tissue sections). Their apex points toward the brain surface and has a thick dendrite with many branches and small, knobby *dendritic spines.* The base gives rise to horizontally oriented dendrites and an axon that passes into the white matter. The axon also has collaterals that synapse with other neurons in the cortex or in deeper regions of the brain. Pyramidal cells are the output neurons of the cerebrum—they are the only cerebral neurons whose fibers leave the cortex and connect with other parts of the CNS.

About 90% of the human cerebral cortex is a six-layered tissue called **neocortex**[28] because of its relatively recent evolutionary origin. Although vertebrates have existed for about 600 million

---

[27] *cortex* = bark, rind

[28] *neo* = new


Cortical surface
I
II
III
IV
V
VI
White matter
Small pyramidal cells
Stellate cells
Large pyramidal cells

Figure 15.14 **Histology of the Neocortex.** Neurons are arranged in six layers.

- *Are the long processes leading upward from each pyramidal cell dendrites or axons?*

years, the neocortex did not develop significantly until about 60 million years ago, when there was a sharp increase in the diversity of mammals. It attained its highest development by far in the primates. The six layers of neocortex (fig. 15.14) vary from one part of the cerebrum to another in relative thickness, cellular composition, synaptic connections, size of the neurons, and destination of their axons. Layer IV is thickest in sensory regions and layer V in motor regions, for example. All axons that leave the cortex and enter the white matter arise from layers III, V, and VI.

Some regions of cerebral cortex have fewer than six layers. The earliest type of cortex to appear in vertebrate evolution was a one- to five-layered tissue called *paleocortex* (PALE-ee-oh-cor-tex), limited in humans to part of the insula and certain areas of the temporal lobe concerned with smell. The next to evolve was a three-layered *archicortex* (AR-kee-cor-tex), found in the human hippocampus. The neocortex was the last to evolve.

The Limbic System

The **limbic**[29] **system** is an important center of emotion and learning. It was originally described in the 1850s as a ring of cerebral cortex on the medial side of the hemisphere, encircling the corpus callosum and thalamus. Its most anatomically prominent components are the **cingulate**[30] (SING-you-let) **gyrus** that arches over the top of the corpus callosum in the frontal and parietal lobes, the **hippocampus**[31] in the medial temporal lobe (fig. 15.15), and the **amygdala**[32] (ah-MIG-da-luh) immediately rostral to the hippocampus, also in the temporal lobe. There are still differences of opinion on what structures to consider as parts of the limbic system, but those three are

---

[29] *limbus* = border
[30] *cingulate* = girdle
[31] *hippocampus* = sea horse; named for its shape
[32] *amygdala* = almond; named for its shape


Cingulate gyrus
Corpus callosum
Medial prefrontal cortex
Orbitofrontal cortex
Basal nuclei
Amygdala
Temporal lobe
Fornix
Thalamic nuclei
Mammillary body
Hippocampu

Figure 15.15 **The Limbic System.** This ring of structures includes important centers of learning and emotion. In the frontal lobe, there is no sharp rostral boundary to limbic system components.



Figure 15.16 **The Basal Nuclei.** Frontal section of the brain. AP|R

agreed upon. Other components include the mammillary bodies and other hypothalamic nuclei, some thalamic nuclei, parts of the basal nuclei, and parts of the frontal lobe called *prefrontal* and *orbitofrontal cortex*. Limbic system components are interconnected through a complex loop of fiber tracts allowing for somewhat circular patterns of feedback among its nuclei and cortical neurons. All of these structures are bilaterally paired; there is a limbic system in each cerebral hemisphere.

The limbic system was long thought to be associated with smell because of its close association with olfactory pathways, but beginning in the early 1900s and continuing even now, experiments have abundantly demonstrated more significant roles in emotion and memory. Most limbic system structures have centers for both gratification and aversion. Stimulation of a gratification center produces a sense of pleasure or reward; stimulation of an aversion center produces disagreeable sensations such as fear, displeasure, or sorrow. Gratification centers dominate some limbic structures, such as the *nucleus accumbens* (not illustrated), whereas aversion centers dominate others, such as the amygdala. The roles of the amygdala in emotion and the hippocampus in memory are described in the coming pages.

The Basal Nuclei

The **basal nuclei** (fig. 15.16) are masses of cerebral gray matter buried deep in the white matter, lateral to the thalamus. They are often called *basal ganglia,* but the word *ganglion* is best restricted to clusters of neurons outside the CNS. Neuroanatomists disagree on how many brain centers to classify as basal nuclei, but agree on at least three: the **caudate**[33] **nucleus, putamen,**[34] and **globus pallidus.**[35] These three are collectively called the *corpus striatum* because of their striped appearance. The putamen and globus pallidus are also collectively called the *lentiform*[36] *nucleus,* named for its lenslike shape. The basal nuclei are involved in motor control, as discussed later.

Integrative Brain Functions

We will here examine a number of "higher" functions of the forebrain—sensory awareness, motor control, language, emotion, thought, and memory. These processes call attention especially to the cerebral cortex, but are not limited to the cerebrum; they involve also the diencephalon and cerebellum. It is impossible in many cases to assign a specific function to a specific brain region. Functions of the brain do not have such easily defined boundaries as its anatomy. Some functions overlap anatomically, some cross anatomical boundaries from one region to another, and some functions such as consciousness and memory are widely distributed through the cerebrum.

As a general principle for the functional discussion of the cerebrum, we distinguish between primary cortex and association cortex. **Primary cortex** consists of those regions that receive input directly from the sense organs or brainstem, or issue motor nerve fibers directly to the brainstem for distribution of the motor commands to cranial and spinal nerves. **Association cortex** consists of all regions other than the primary cortex involved in integrative functions such as interpretation of sensory input, planning of motor output, cognitive (thought) processes, and the storage and retrieval of memories. About 75% of the mass of the cerebral

---

[33] *caudate* = tailed, tail-like
[34] *putam* = pod, husk
[35] *glob* = globe, ball; *pallid* = pale
[36] *lenti* = lens; *form* = shape



Figure 15.17 **Some Functional Regions of the Cerebral Cortex.** The Broca and Wernicke areas for language abilities are found in only one hemisphere, usually the left. The other regions shown here are mirrored in both hemispheres.

cortex is association cortex. Typically, an area of primary cortex has an association area immediately adjacent to it, concerned with the same general function. For example, the primary visual cortex, which receives input from the eyes, is bordered by the visual association area, which interprets and makes cognitive sense of the visual stimuli. Some association areas are *multimodal;* instead of processing information from a single sensory source, they receive input from multiple senses and integrate this into the overall perception of one's surroundings. The association area of the frontal lobe is a very important center of cognitive and emotional function, the **prefrontal cortex.**

Special Senses

The *special senses* are taste, smell, hearing, equilibrium, and vision, mediated by relatively complex sense organs in the head. Signals from these organs are routed to widely separated areas of primary sensory cortex in the cerebrum. From an area of primary sensory cortex, signals are relayed to a nearby association area, where the present sensory experience is integrated with memory and made identifiable and intelligible. Here we will only briefly identify the regions of cerebral cortex concerned with each of the special senses (fig. 15.17). Chapter 17 details the pathways taken from the sense organs to these areas of the cerebrum.

- **Vision.** Visual signals are received by the **primary visual cortex** in the far posterior region of the occipital lobe. This is bordered anteriorly by the **visual association area,** which includes all the remainder of the occipital lobe, part of the parietal lobe, and much of the inferior temporal lobe. The association area integrates information so we can identify what we see.
- **Hearing.** Auditory signals are received by the **primary auditory cortex** in the superior region of the temporal lobe and in the nearby insula. The **auditory association area** occupies areas of temporal lobe inferior to the primary auditory cortex and deep within the lateral sulcus. This is where we become capable of recognizing spoken words, a familiar piece of music, or a voice on the telephone.
- **Equilibrium.** Signals from the inner ear for equilibrium project mainly to the cerebellum and several brainstem nuclei concerned with head and eye movements and visceral functions. Some fibers of this system, however, are routed through the thalamus to association areas in the roof of the lateral sulcus and near the lower end of the central sulcus. This is the seat of consciousness of our body movements and orientation in space.
- **Taste.** Gustatory signals are received by the **primary gustatory cortex** in the inferior end of the postcentral gyrus of the parietal lobe (discussed shortly) and an anterior region of the insula. The gustatory association area is integrated with the association area for smell.
- **Smell.** The primary olfactory cortex lies in the medial surface of the temporal lobe and inferior surface of the frontal lobe. The **orbitofrontal cortex** (fig. 15.16) contains an association area that integrates gustatory, olfactory, and visual information to create a sense of the overall flavor and desirability (or rejection) of food.

General Senses

The *general* (*somatosensory* or *somesthetic*[37]) *senses* are widely distributed over the body and have relatively simple receptors (see chapter 17). They include such senses as touch, pressure, stretch, temperature, and pain. Somatosensory signals arising from the neck down travel up the spinal cord in the gracile and cuneate fasciculi and spinothalamic tracts. Somatosensory nerve fibers decussate in the spinal cord or medulla before reaching the thalamus

---

[37] *som* = body; *esthet* = sensation

(see table 14.1 and fig. 14.4). Consequently, these signals ultimately arrive in the contralateral cerebral cortex—stimuli on the right side of the body are perceived in the left cerebral hemisphere, and vice versa. The thalamus routes all somatosensory signals to one specific fold of the cerebrum, the **postcentral gyrus.** This gyrus lies immediately caudal to the central sulcus and forms the anterior border of the parietal lobe (see fig. 15.1c). It rises from the lateral sulcus up to the crown of the head and then descends into the longitudinal fissure. The cortex of this gyrus is called the **primary somatosensory cortex** (fig. 15.18).

This gyrus is like an upside-down sensory map of the contralateral side of the body, traditionally diagrammed as a *sensory homunculus*[38] (fig. 15.18b). As the diagram shows, receptors in the lower limb project to superior and medial parts of the gyrus, and receptors in the face project to the inferior and lateral parts. There is a point-for-point correspondence, or **somatotopy,**[39] between an area of the body and an area of the postcentral gyrus. The reason for the bizarre, distorted appearace of the homunculus is that the amount of cerebral tissue devoted to a given body region is proportional to how richly innervated and sensitive that region is, not to its size. Thus, the hands and face are represented by a much larger region of somatosensory cortex than the trunk is.

The **somatosensory association area** is found in the parietal lobe posterior to the postcentral gyrus and in the roof of the lateral sulcus (fig. 15.17).

Motor Control

The intention to contract a skeletal muscle begins in the **motor association (premotor) area** of the frontal lobes (fig. 15.17). This is where we plan our behavior—where neurons compile a program for the degree and sequence of muscle contractions required for an action such as dancing, typing, or speaking. The program is then transmitted to neurons of the **precentral gyrus** (primary motor area), which is the most posterior gyrus of the frontal lobe, immediately anterior to the central sulcus (see fig. 15.1c). Neurons here send signals to the brainstem and spinal cord that ultimately result in muscle contractions.

The precentral gyrus, like the postcentral one, exhibits somatotopy. The neurons for toe movements, for example, are deep in the longitudinal fissure on the medial side of the gyrus. The summit of the gyrus controls the trunk, shoulder, and arm, and the inferolateral region controls the facial muscles. This map is diagrammed as a *motor homunculus* (fig. 15.19b). Like the sensory homunculus, it has a distorted look because the amount of cortex devoted to a given body region is proportional to the number of muscles and motor units in that region, not to the size of the region. The amount of cortical tissue that controls the thumb, for example, is considerably greater than that which controls the thigh, since the thumb is involved in a great variety of complex movements and requires finer control.

There is no exact point-for-point correspondence between an area of the precentral gyrus and a given muscle. A muscle is controlled by neurons at several points within a general area of the gyrus. Also, a given neuron in the gyrus may ultimately affect more than one muscle, such as muscles of shoulder and elbow movement that both

---

[38] *hom* = man; *unculus* = little
[39] *somato* = body; *top* = place



Figure 15.18 **The Primary Somatosensory Area (Postcentral Gyrus).** (a) Superior view of the brain showing the location of the postcentral gyrus (violet). (b) Sensory homunculus, drawn so that body parts are in proportion to the amount of cortex dedicated to their sensation. AP|R



Figure 15.19 **The Primary Motor Area (Precentral Gyrus).** (a) Superior view of the brain showing the location of the precentral gyrus (blue). (b) Motor homunculus, drawn so that body parts are in proportion to the amount of primary motor cortex dedicated to their control.

- *Which body regions are controlled by the largest area of motor cortex—regions with a few large muscles or regions with many small muscles?* AP|R

contribute to the coordinated positioning of one's hand. Although the homunculus identifies cortical areas that are broadly responsible for motor control of a given region, the boundaries between these cortical areas overlap and are not sharply defined.

The pyramidal cells of the precentral gyrus are called **upper motor neurons.** Their fibers project caudally, with about 19 million fibers ending in nuclei of the brainstem and 1 million forming the corticospinal tracts. These tracts decussate in the pyramids of the medulla oblongata and then continue into the spinal cord. Therefore, below the neck, each precentral gyrus controls muscles on the contralateral side of the body. In the brainstem or spinal cord, the fibers from the upper motor neurons synapse with **lower motor neurons** whose axons innervate the skeletal muscles.

Other areas of the brain important in muscle control are the basal nuclei and cerebellum. The basal nuclei receive signals from the cerebral cortex and direct their output back to the cortex via the thalamus. Nearly all areas of cerebral cortex, except for the primary visual and auditory areas, send signals to the basal nuclei. The basal nuclei process these and issue their output to the thalamus, which relays these signals back to the cerebral cortex—especially to the prefrontal cortex, motor association area, and precentral gyrus. The basal nuclei thus lie in a feedback circuit involved in the planning and execution of movement.

Among other functions, the basal nuclei assume control of highly practiced behaviors that one carries out with little thought—writing, typing, driving a car, using scissors, or tying one's shoes, for example. They also control the onset and cessation of planned movements and the repetitive movements at the shoulder and hip that occur during walking.

Lesions of the basal nuclei cause movement disorders called **dyskinesias.**[40] Some dyskinesias are characterized by abnormally inhibited movements—for example, difficulty rising from a chair or beginning to walk and a slow shuffling walk, as seen in Parkinson disease (see p. 439). Smooth, easy movements require the excitation of agonistic muscles and inhibition of their antagonists. In Parkinson disease, the antagonists are not inhibited. Therefore, opposing muscles at a joint fight each other, making it a struggle to move as one wishes. Other dyskinesias are characterized by exaggerated or unwanted movements, such as flailing of the limbs *(ballismus)* in Huntington disease.

The cerebellum is highly important in motor coordination. It aids in learning motor skills, maintains muscle tone and posture, smooths muscle contractions, coordinates eye and body movements, and coordinates the motions of different joints with each other (such as the shoulder and elbow in pitching a baseball). The cerebellum acts as a comparator in motor control. It receives information from the upper motor neurons of the cerebrum about what movements are intended, and information from proprioceptors in the muscles and joints about the actual performance of the movement (see fig. 15.10). The Purkinje cells of the cerebellum compare the two. If there is a discrepancy between the intent and the performance, they signal the deep cerebellar nuclei, which, in turn, relay signals to the thalamus and cerebral cortex. Motor neurons in the cortex then correct the muscle performance to match the intent. Lesions of the cerebellum can result in a clumsy, awkward gait *(ataxia)* and make some tasks such as climbing stairs virtually impossible.

---

[40] *dys* = bad, abnormal, difficult; *kines* = movement

Language

Language includes several abilities—reading, writing, speaking, and understanding spoken and printed words—assigned to different regions of cerebral cortex. The **Wernicke**[41] (WUR-nih-kee) **area** is responsible for the recognition of spoken and written language. It lies just posterior to the lateral sulcus, usually in the left hemisphere, at the crossroad between visual, auditory, and somatosensory areas of the cortex (see fig. 15.17). It is a sensory association area that receives input from all these neighboring regions of primary sensory cortex. The *angular gyrus,* part of the parietal lobe caudal and superior to the Wernicke area, is important in the ability to read and write.

When we intend to speak, the Wernicke area formulates phrases according to learned rules of grammar and transmits a plan of speech to the **Broca**[42] **area,** located in the inferior prefrontal cortex of the same hemisphere. PET scans show a rise in the metabolic activity of the Broca area as we prepare to speak. The Broca area generates a motor program for the muscles of the larynx, tongue, cheeks, and lips to produce speech. This program is then transmitted to the primary motor cortex, which executes it—that is, it issues commands to the lower motor neurons that supply the relevant muscles.

Lesions in the language areas of the brain tend to produce a variety of language deficits called **aphasias**[43] (ah-FAY-zee-uhs). They may include a complete inability to speak; slow speech with difficulty choosing words; invention of words that only approximate the correct ones; babbling, incomprehensible speech filled with invented words and illogical word order; inability to comprehend another person's written or spoken words; or inability to name objects that a person sees. Since cranial nerves VII and XII (the facial and hypoglossal nerves) control several of the muscles of speech, speech deficits can also result from lesions to these nerves or their brainstem nuclei.

Apply What You Know

Mr. Thompson has had a stroke that destroyed his Wernicke area. Ms. Meyers has had a stroke that destroyed her Broca area. What differences in language deficits would you expect between these two patients?

Emotion

Emotional feelings and memories are not exclusively cerebral functions, but rather result from an interaction between areas of the prefrontal cortex and the diencephalon. The hypothalamus and amygdala play especially important roles in emotion. Experiments by Swiss physiologist Walter Hess, leading to a 1949 Nobel Prize, showed that stimulation of various nuclei of the hypothalamus in cats could induce rage, attack, and other emotional responses. Nuclei involved in the senses of reward and punishment have been identified in the hypothalamus of cats, rats, monkeys, and other animals, as well as humans.

The *amygdala,* one of the most important centers of human emotion, is a major component of the limbic system described earlier. It receives processed information from the senses of vision, hearing, taste, smell, and general somatosensory and visceral senses. Thus, it is able to mediate emotional responses to such stimuli as a disgusting odor, a foul taste, a beautiful image, pleasant music, or a stomachache. It is especially important in the sense of fear. Output from the amygdala goes in two directions of special interest: (1) Some output projects to the hypothalamus and lower brainstem and thus influences the somatic and visceral motor systems. An emotional response to a sight or sound may, through these connections, make one's heart race, make the hair stand on end (piloerection), or induce vomiting. (2) Other output projects to areas of the prefrontal cortex that mediate conscious control and expression of the emotions, such as our ability to express love or control anger.

Many important aspects of personality depend on an intact, functional amygdala and hypothalamus. When specific regions of the amygdala or hypothalamus are destroyed or artificially stimulated, humans and other animals exhibit blunted or exaggerated expressions of anger, fear, aggression, self-defense, pleasure, pain, love, sexuality, and parental affection, as well as abnormalities in learning, memory, and motivation.

Cognition

Cognition[44] is the range of mental processes by which we acquire and use knowledge—sensory perception, thought, reasoning, judgment, memory, imagination, and intuition. Cognitive abilities of various kinds are widely distributed through the association areas of the cerebral cortex. This is the most difficult area of brain research and the most incompletely understood area of cerebral function. Much of what we know about cognitive functions of the brain has come from studies of patients with brain lesions—areas of tissue destruction resulting from cancer, stroke, and trauma. The many brain injuries incurred in World Wars I and II yielded an abundance of insights into regional brain functions. More recently, imaging methods such as positron emission tomography (PET) and functional magnetic resonance imaging (fMRI), described on page 413, have led to much more sophisticated insights into brain function. These methods allow a researcher to scan a person's brain while that person is performing various cognitive or motor tasks and to see which brain regions are most active in different mental and task states (fig. 15.20).

Attention to objects in the environment is based in the parietal lobe on the side opposite the Broca and Wernicke speech centers. Lesions here can produce *contralateral neglect syndrome,* in which a patient seems unaware of objects on one side of the body; fails even to recognize, dress, and take care of one side of his or her own body; or ignores all words on one side of a page of reading. Such patients are also unable to find their way around—say, to describe the route from home to work, or to navigate within a familiar building.

---

[41] Karl Wernicke (1848–1904), German neurologist

[42] Pierre Paul Broca (1824–80), French surgeon and anthropologist

[43] *a* = without; *phas* = speech

[44] *cognit* = to know, to learn



① The word *car* is seen in the visual cortex.

② Wernicke area conceives of the verb *drive* to go with it.

③ Broca area compiles a motor program to speak the word *drive*.

④ The primary motor cortex executes the program and the word is spoken.

© Marcus E. Raichle, M.D., Washington University School of Medicine, St. Louis, Missouri

© Marcus E. Raichle, M.D., Washington University School of Medicine, St. Louis, Missouri

© Marcus E. Raichle, M.D., Washington University School of Medicine, St. Louis, Missouri

© Marcus E. Raichle, M.D., Washington University School of Medicine, St. Louis, Missouri

Figure 15.20 **PET Scans of the Brain During Performance of a Language Task.** These scans represent computer-averaged images of the brains of one or more subjects who were shown a word *(car)* in print and asked to speak a word (such as *drive*) related to it. The most active brain areas are shown in red and the least active in blue. Such studies have shown that the Broca and Wernicke areas are not involved in simply repeating a word, but are active when a person must evaluate a word and choose an appropriate response. PET scans also show that different neural pools take over a task as a person practices and becomes more proficient at it.

The prefrontal cortex is concerned with many of our most distinctly human abilities, such as abstract thought, foresight, judgment, responsibility, a sense of purpose, and a sense of socially appropriate behavior. Lesions here tend to render a person easily distracted from a task, irresponsible, exceedingly stubborn, unable to anticipate future events, and incapable of any ambition or planning for the future.

The cerebellum also has lately shown a surprising amount of cognitive function. It exhibits increased PET activity in analyzing visual and tactile input, solving spatial puzzles, judging the passage of time, planning and scheduling activities, discriminating similar-sounding words, and performing other language tasks. For example, if a person is given a noun such as *apple* and asked to think of a related verb such as *eat,* the cerebellum is more active than when the person is asked simply to repeat *apple.* Touching sandpaper activates the cerebellum to some degree, but not as much as when one is asked to compare the texture of two different sandpapers. The cerebellum also helps in making short-term predictions about movement, such as where a baseball will be in a second or two so that one can catch it. People with cerebellar lesions have difficulty with emotional overreaction and impulse control. Many children with attention-deficit/hyperactivity disorder (AD/HD) have abnormally small cerebellums.

Memory

Memory is one of the cognitive functions, but warrants special attention. There are two kinds of memory—**procedural memory,** the retention of motor skills such as how to tie one's shoes, play the violin, or type on a keyboard; and **declarative memory,** the retention of events and facts that one can put into words, such as names, dates, or facts important to an upcoming examination. At the cellular level, both forms of memory probably involve the same processes: the creation of new synaptic contacts and physiological changes that make synaptic transmission more efficient along certain pathways.

The limbic system has important roles in the establishment of memories. The amygdala creates emotional memories, such as the chilling fear of being stung when a wasp alights on the skin. The *hippocampus* (see fig. 15.15) is critical to the creation of long-term declarative memories. It does not store memories, but organizes sensory and cognitive experiences into a unified long-term memory. The hippocampus learns from sensory input while an experience is happening, but it has a short memory. Later, perhaps when one is sleeping, it plays this memory repeatedly to the cerebral cortex, which is a "slow learner" but forms longer-lasting memories. This process of "teaching the cerebral cortex" until a long-term memory is established is called **memory consolidation.** Lesions of the hippocampus can abolish the ability to form new declarative memories, but they do not abolish old memories or the acquisition of new procedural memories, such as the ability to learn a new motor skill.

Long-term memories are stored in various areas of the cerebral cortex. The memory of language (vocabulary and grammatical rules) resides in the Wernicke area. Our memories of faces, voices, and familiar objects are stored in the superior temporal lobe. Memories of one's social role, appropriate behavior, goals, and plans are stored in the prefrontal cortex. Procedural memories are stored in the motor association area, basal nuclei, and cerebellum.

Cerebral Lateralization

The two cerebral hemispheres look identical at a glance, but close examination reveals a number of differences. For example, in women the left temporal lobe is longer than the right. In left-handed people, the left frontal, parietal, and occipital lobes are usually wider than those on the right. The two hemispheres also differ in some of their functions (fig. 15.21). Neither hemisphere is "dominant," but each is specialized for certain tasks. This difference in function is called **cerebral lateralization.** The idea that some people are "left-brained" and others "right-brained," however, is a discredited popular myth.

One hemisphere, usually the left, is called the *categorical hemisphere.* It is specialized for spoken and written language and for the sequential and analytical reasoning employed in such fields as science and mathematics. This hemisphere seems to break


Left hemisphere
Right hemisphere
Anterior
Posterior
Olfaction, right nasal cavity
Verbal memory
Speech
Right hand motor control
Feeling shapes with right hand
Hearing vocal sounds (right ear advantage)
Rational, symbolic thought
Superior language comprehension
Vision, right field
Olfaction, left nasal cavity
Memory for shapes
(Limited language comprehension, mute)
Left hand motor control
Feeling shapes with left hand
Hearing nonvocal sounds (left ear advantage)
Musical ability
Intuitive, nonverbal thought
Superior recognition of faces and spatial relationships
Vision, left field

Figure 15.21 **Lateralization of Cerebral Functions.** The two cerebral hemispheres are not functionally identical.
- *If a person is described as "left-brained," does this mean he or she makes little use of the right hemisphere?*

information into fragments and analyze it in a linear way. The other hemisphere, usually the right, is called the *representational hemisphere.* It perceives information in a more integrated, holistic way. It is the seat of imagination and insight; musical and artistic skill; perception of patterns and spatial relationships; perception of the rhythm, intonation, and emotional content of speech; and comparison of sights, sounds, smells, and tastes.

Figure 15.22 shows some of the forebrain structures in a coronal tissue section and a corresponding MRI of the cerebrum. Table 15.2 summarizes the forebrain functions described in the last several pages.

TABLE 15.2	Forebrain Functions
Diencephalon	
Thalamus	Sensory processing; relay of sensory and other signals to cerebrum; relay of cerebral output to other parts of brain
Hypothalamus	Hormone synthesis; control of pituitary secretion; autonomic responses affecting heart rate, blood pressure, pupillary diameter, digestive secretion and motility, and other visceral functions; thermoregulation; hunger and thirst; sleep and circadian rhythms; emotional responses; sexual function; memory
Epithalamus	Hormone secretion; relay of signals between midbrain and limbic system
Cerebral lobes	
Frontal lobe	Smell; motor aspects of speech; voluntary control of skeletal muscles; procedural memory; cognitive functions such as abstract thought, judgment, responsibility, foresight, ambition, planning, and ability to stay focused on a task
Parietal lobe	Somatosensory functions, taste, awareness of body movement and orientation, language recognition, nonmotor aspects of speech
Occipital lobe	Vision
Temporal lobe	Hearing, smell, interpreting visual information, learning, memory, emotion
Insula	Hearing, taste, visceral sensation
Basal nuclei	Motor control; procedural memory
Limbic system	Learning, emotion, gratification, and aversion responses


Longitudinal fissure
Frontal lobe
Corpus callosum
Choroid plexus
Insula
Lateral sulcus
Internal capsule
Hypothalamus
Temporal lobe
(a)
Gray matter
White matter
Lateral ventricle
Corona radiata
Caudate nucleus
Putamen
Globus pallidus
Third ventricle
Cranium
Frontal lobe
Lateral ventricle
Corona radiata
Caudate nucleus
Putamen
Third ventricle
Temporal lobe
Longitudinal fissure
Gray matter
White matter
Corpus callosum
Lateral sulcus
Insula
Hypothalamus
(b)

© Biophoto Associates/Science Source

© Medical Body Scans/Science Source

Figure 15.22 **Coronal Sections of the Cerebrum.** (a) Tissue section. (b) A corresponding MRI.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

13. What is the role of the thalamus in sensory function?
14. List at least six functions of the hypothalamus.
15. Name the five lobes of the cerebrum and describe their locations and boundaries.
16. Where are the basal nuclei located? What is their general function?
17. Where is the limbic system located? What component of it is involved in emotion? What component is involved in memory?
18. Describe the locations and functions of the somatosensory, visual, auditory, and frontal association areas.
19. Describe the somatotopy of the primary motor cortex and primary sensory cortex.
20. What are the roles of the Wernicke area, Broca area, and precentral gyrus in language?

15.4 The Cranial Nerves

Expected Learning Outcomes

When you have completed this section, you should be able to

a. list the 12 cranial nerves by name and number;
b. identify where each cranial nerve originates and terminates; and
c. state the functions of each cranial nerve.

To be functional, the brain must communicate with the rest of the body. Most of its input and output travels by way of the spinal cord, but it also communicates by way of 12 pairs of **cranial nerves** (table 15.3). These arise primarily from the base of the brain, exit the cranium through its foramina, and lead to muscles and sense organs primarily in the head and neck. They are numbered I through XII starting with the most rostral (fig. 15.23). Each nerve also has a descriptive name such as *optic nerve* and *vagus nerve*. Figure 15.24 shows their pathways to and from the peripheral organs, and each is separately illustrated in table 15.3.


Frontal lobe
Olfactory tract
Optic chiasm
Temporal lobe
Infundibulum
Midbrain
Pons
Medulla oblongata
Cerebellum
Spinal cord
(a)
Cranial nerves:
Olfactory bulb (from olfactory nerve, I)
Optic nerve (II)
Oculomotor nerve (III)
Trochlear nerve (IV)
Trigeminal nerve (V)
Abducens nerve (VI)
Facial nerve (VII)
Vestibulocochlear nerve (VIII)
Glossopharyngeal nerve (IX)
Vagus nerve (X)
Hypoglossal nerve (XII)
Accessory nerve (XI)
(b)
Frontal lobe
Longitudinal fissure
Olfactory trac
Temporal lob
Optic chiasm
Pons
Medulla oblongata
Cerebellum
Spinal cord

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Figure 15.23 **The Cranial Nerves.** (a) Base of the brain, showing the 12 pairs of cranial nerves. (b) Cranial nerves of the cadaver brain. APIR

Figure 15.24 **Cranial Nerve Pathways.** Pathways concerned with sensory function are shown in green, and those concerned with motor function are shown in red. All cranial nerves except I and II carry sensory fibers, but these functions are omitted in cases where the nerve is essentially motor and its sensory function is limited to proprioception from the muscles.


Optic, oculomotor, trochlear, and abducens nerves
Olfactory nerve
VI
IV
III
II
I
Trigeminal nerve, branch V_1
V_1
V_1
Facial nerve
VII
Vestibulocochlear nerve
VIII
V_2
Trigeminal nerve, branches $V_2 - V_3$
V_2
V_3
V_3
Glossopharyngeal nerve
IX
Vagus nerve
X
XII
XI
Hypoglossal nerve
Accessory nerve

TABLE 15.3 The Cranial Nerves

Cranial nerves listed as mixed or sensory are agreed by all authorities to be either mixed or purely sensory. Those classified as predominantly motor or sensory have fibers of the other type as well. Motor nerves also contain proprioceptive sensory fibers, but these may come from different muscles than the ones innervated by the motor fibers.

I. Olfactory Nerve. This is the nerve for the sense of smell. It consists of several separate fascicles that pass independently through the cribriform plate in the roof of the nasal cavity. It is not visible on brains removed from the skull because these fascicles are severed by removal of the brain.

Composition	Function	Origin	Termination	Cranial Passage	Effect of Damage	Clinical Test
Sensory	Smell	Olfactory mucosa in nasal cavity	Olfactory bulbs	Cribriform foramina of ethmoid bone	Impaired sense of smell	Determine whether subject can smell (not necessarily identify) aromatic substances such as coffee, vanilla, clove oil, or soap


Olfactory bulb
Olfactory tract
Cribriform plate of ethmoid bone
Fascicles of olfactory nerve (I)
Nasal mucosa

Figure 15.25 The Olfactory Nerve (I). AP|R

II. Optic Nerve. This is the nerve for vision.

Composition	Function	Origin	Termination	Cranial Passage	Effect of Damage	Clinical Test
Sensory	Vision	Retina	Thalamus and midbrain	Optic foramen	Blindness in part or all of visual field	Inspect retina with ophthalmoscope; test peripheral vision and visual acuity


Eyeball
Optic nerve (II)
Optic chiasm
Optic tract
Pituitary gland

Figure 15.26 The Optic Nerve (II). AP|R

TABLE 15.3 **The Cranial Nerves (continued)**

III. Oculomotor[45] Nerve (OC-you-lo-MO-tur). This nerve controls muscles that turn the eyeball up, down, and medially, as well as controlling the iris, lens, and upper eyelid.

Composition	Function	Origin	Termination	Cranial Passage	Effect of Damage	Clinical Test
Predominantly motor	Eye movements, opening of eyelid, pupillary constriction, focusing	Midbrain	Somatic fibers to levator palpebrae superioris; superior, medial, and inferior rectus muscles and inferior oblique muscle of eye. Autonomic fibers enter eyeball and lead to constrictor of iris and ciliary muscle of lens.	Superior orbital fissure	Drooping eyelid; dilated pupil; inability to move eye in some directions; tendency of eye to rotate laterally at rest; double vision; difficulty focusing	Look for differences in size and shape of right and left pupils; test pupillary response to light; test ability to track moving objects.



Figure 15.27 The Oculomotor Nerve (III). APR

IV. Trochlear[46] Nerve (TROCK-lee-ur). This nerve controls a muscle that rotates the eyeball medially and slightly depresses the eyeball when the head turns. This is the only cranial nerve that arises from the dorsal side of the brainstem. It is also unusual in being the only cranial nerve to completely decussate; the left trochlear nerve moves the right eye and vice versa.

Composition	Function	Origin	Termination	Cranial Passage	Effect of Damage	Clinical Test
Predominantly motor	Eye movements	Midbrain	Superior oblique muscle of contralateral eye	Superior orbital fissure	Double vision and inability to rotate eye inferolaterally; eye points superolaterally and subject tends to tilt head toward affected side	Test ability of eye to rotate; requires ophthalmoscopic examination



Figure 15.28 The Trochlear Nerve (IV). APR

---

[45] *oculo* = eye; *motor* = mover

[46] *trochlea* = pulley (for a loop through which the muscle's tendon passes)

TABLE 15.3 The Cranial Nerves (continued)

V. Trigeminal[47] Nerve (tri-JEM-ih-nul). This is the most important sensory nerve of the face, and the largest cranial nerve except for the optic nerve. It forks into three divisions: *ophthalmic* (V_1), *maxillary* (V_2), and *mandibular* (V_3) (see fig. 15.29 on page 432).

Composition	Function	Origin	Termination	Cranial Passage	Effect of Damage	Clinical Test
Ophthalmic division (V_1)						
Sensory	Touch, temperature, and pain sensations from upper face	Superior region of face as illustrated; surface of eyeball; lacrimal (tear) gland; superior nasal mucosa; frontal and ethmoid sinuses	Pons	Superior orbital fissure	Loss of sensation from upper face	Test corneal reflex (blinking in response to light touch to eyeball)
Maxillary division (V_2)						
Sensory	Same as V_1, lower on face	Middle region of face as illustrated; nasal mucosa; maxillary sinus; palate; upper teeth and gums	Pons	Foramen rotundum and infraorbital foramen	Loss of sensation from middle face	Test sense of touch, pain, and temperature with light touch, pinpricks, and hot and cold objects
Mandibular division (V_3)						
Mixed	*Sensory:* Same as V_1 and V_2, lower on face *Motor:* Mastication	*Sensory:* Inferior region of face as illustrated; anterior two-thirds of tongue (but not taste buds); lower teeth and gums; floor of mouth; dura mater *Motor:* Pons	*Sensory:* Pons *Motor:* Anterior belly of digastric; masseter, temporalis, mylohyoid, and pterygoid muscles; tensor tympani muscle of middle ear	Foramen ovale	Loss of sensation; impaired chewing	Assess motor functions by palpating masseter and temporalis while subject clenches teeth; test ability to move mandible from side to side and to open mouth against resistance

DEEPER INSIGHT 15.2

Some Cranial Nerve Disorders

Trigeminal neuralgia[48] *(tic douloureux*[49]*)* is a syndrome characterized by recurring episodes of intense stabbing pain in the trigeminal nerve. The cause is unknown; there is no visible change in the nerve. It usually occurs after the age of 50 and mostly in women. The pain lasts only a few seconds to a minute or two, but it strikes at unpredictable intervals and sometimes up to a hundred times a day. The pain usually occurs in a specific zone of the face, such as around the mouth and nose. It may be triggered by touch, drinking, tooth brushing, or washing the face. Analgesics (pain relievers) give only limited relief. Severe cases are treated by cutting the nerve, but this also deadens most other sensation in that side of the face.

Bell[50] *palsy* is a degenerative disorder of the facial nerve, probably due to a virus. It is characterized by paralysis of the facial muscles on one side with resulting distortion of the facial features, such as sagging of the mouth or lower eyelid. The paralysis may interfere with speech, prevent closure of the eye, and sometimes inhibit tear secretion. There may also be a partial loss of the sense of taste. Bell palsy may appear abruptly, sometimes overnight, and often disappears spontaneously within 3 to 5 weeks.

---

[47] *tri* = three; *gem* = born (*trigem* = triplets)
[48] *neur* = nerve; *algia* = pain
[49] *tic* = twitch, spasm; *douloureux* = painful (French)
[50] Sir Charles Bell (1774–1842), Scottish physician

TABLE 15.3 The Cranial Nerves (continued)


Ophthalmic division (V_1)
Trigeminal ganglion
Trigeminal nerve (V)
Maxillary division (V_2)
Mandibular division (V_3)
Infraorbital nerve
Superior alveolar nerves
Lingual nerve
Inferior alveolar nerve
Anterior trunk of V_3 to chewing muscles
Temporalis muscle
Lateral pterygoid muscle
Medial pterygoid muscle
Masseter muscle
Anterior belly of digastric muscle
V_1
V_3
V_2
Inset shows motor branches of the mandibular division (**V_3**)
Distribution of sensory fibers of each division

Figure 15.29 The Trigeminal Nerve (V). APR

VI. Abducens[51] Nerve (ab-DOO-senz). This nerve controls a muscle that turns the eyeball laterally.

Composition	Function	Origin	Termination	Cranial Passage	Effect of Damage	Clinical Test
Predominantly motor	Lateral eye movement	Inferior pons	Lateral rectus muscle of eye	Superior orbital fissure	Inability to turn eye laterally; at rest, eye turns medially because of action of antagonistic muscles	Test lateral eye movement


Lateral rectus muscle
Abducens nerve (VI)

Figure 15.30 The Abducens Nerve (VI). APR

---

[51] *ab* = away; *duc* = to lead or turn

TABLE 15.3 The Cranial Nerves (continued)

VII. Facial Nerve. This is the major motor nerve of the facial muscles. It divides into five prominent branches: *temporal, zygomatic, buccal, mandibular,* and *cervical.*

Composition	Function	Origin	Termination	Cranial Passage	Effect of Damage	Clinical Test
Mixed	*Sensory:* Taste *Motor:* Facial expression; secretion of tears, saliva, nasal and oral mucus	*Sensory:* Taste buds of anterior two-thirds of tongue *Motor:* Pons	*Sensory:* Thalamus *Motor:* Somatic fibers to digastric muscle, stapedius muscle of middle ear, stylohyoid muscle, muscles of facial expression. Autonomic fibers to submandibular and sublingual salivary glands, tear glands, nasal and palatine glands.	Internal acoustic meatus and stylomastoid foramen	Inability to control facial muscles; sagging due to loss of muscle tone; distorted sense of taste, especially for sweets	Test anterior two-thirds of tongue with substances such as sugar, salt, vinegar, and quinine; test response of tear glands to ammonia fumes; test subject's ability to smile, frown, whistle, raise eyebrows, close eyes, etc.


Facial nerve (VII)
Geniculate ganglion
Pterygopalatine ganglion
Lacrimal (tear) gland
Chorda tympani branch (taste and salivation)
Submandibular ganglion
Sublingual gland
Parasympathetic fibers
Submandibular gland
Motor branch to muscles of facial expression
to (b)
(a)
Temporal
Zygomatic
Buccal
Mandibular
Cervical
(b)
Temporal
Zygomatic
Buccal
Mandibular
Cervical
(c)

© McGraw-Hill Education/Joe De Grandis, photographer

Figure 15.31 **The Facial Nerve (VII).** (a) The facial nerve and associated organs. (b) The five major branches of the facial nerve. (c) A way to remember the distribution of the five major branches. AP|R

TABLE 15.3 The Cranial Nerves (continued)

VIII. Vestibulocochlear[52] Nerve (vess-TIB-you-lo-COC-lee-ur). This is the nerve of hearing and equilibrium, but it also has motor fibers that lead to cells of the cochlea that tune the sense of hearing (see chapter 17).

Composition	Function	Origin	Termination	Cranial Passage	Effect of Damage	Clinical Test
Predominantly sensory	Hearing and equilibrium	*Sensory:* Cochlea, vestibule, and semicircular ducts of inner ear *Motor:* Pons	*Sensory:* Fibers for hearing end in medulla; fibers for equilibrium end at junction of medulla and pons *Motor:* Outer hair cells of cochlea of inner ear	Internal acoustic meatus	Nerve deafness, dizziness, nausea, loss of balance, and nystagmus (involuntary rhythmic oscillation of eyes from side to side)	Look for nystagmus; test hearing, balance, and ability to walk a straight line


Vestibular ganglia
Vestibular nerve
Semicircular ducts
Cochlear nerve
Vestibulocochlear nerve (VIII)
Internal acoustic meatus
Cochlea
Vestibule

Figure 15.32 The Vestibulocochlear Nerve (VIII). APR

IX. Glossopharyngeal[53] Nerve (GLOSS-oh-fah-RIN-jee-ul). This is a complex, mixed nerve with numerous sensory and motor functions in the head, neck, and thoracic regions, including sensation from the tongue, throat, and outer ear; control of food ingestion; and some aspects of cardiovascular and respiratory function.

Composition	Function	Origin	Termination	Cranial Passage	Effect of Damage	Clinical Test
Mixed	*Sensory:* Taste; touch, pressure, pain and temperature sensations from tongue and outer ear; regulation of blood pressure and respiration *Motor:* Salivation, swallowing, gagging	*Sensory:* Pharynx; middle and outer ear; posterior one-third of tongue (including taste buds); internal carotid artery *Motor:* Medulla oblongata	*Sensory:* Medulla oblongata *Motor:* Parotid salivary gland; glands of posterior tongue; stylopharyngeal muscle (which dilates pharynx during swallowing)	Jugular foramen	Loss of bitter and sour taste; impaired swallowing	Test gag reflex, swallowing, and coughing; note any speech impediments; test posterior one-third of tongue with bitter and sour substances


Glossopharyngeal nerve (IX)
Superior ganglion
Inferior ganglion
Otic ganglion
Parotid salivary gland
Carotid sinus
Pharyngeal muscles

Figure 15.33 The Glossopharyngeal Nerve (IX). APR

---

[52] *vestibul* = entryway (vestibule of the inner ear); *cochlea* = conch, snail (cochlea of the inner ear)

[53] *glosso* = tongue; *pharyng* = throat

TABLE 15.3 **The Cranial Nerves (continued)**

X. Vagus[54] Nerve (VAY-gus). The vagus has the most extensive distribution of any cranial nerve, supplying not only organs in the head and neck but also most viscera of the thoracic and abdominal body cavities. It plays major roles in the control of cardiac, pulmonary, digestive, and urinary functions.

Composition	Function	Origin	Termination	Cranial Passage	Effect of Damage	Clinical Test
Mixed	*Sensory:* Taste; sensations of hunger, fullness, and gastrointestinal discomfort *Motor:* Swallowing, speech, deceleration of heart, broncho-constriction, gastro-intestinal secretion and motility	*Sensory:* Thoracic and abdominal viscera, root of tongue, pharynx, larynx, epiglottis, outer ear, dura mater *Motor:* Medulla oblongata	*Sensory:* Medulla oblongata *Motor:* Tongue, palate, pharynx, larynx, lungs, heart, liver, spleen, digestive tract, kidney, ureter	Jugular foramen	Hoarseness or loss of voice; impaired swallowing and gastrointestinal motility; fatal if both vagus nerves are damaged	Examine palatal movements during speech; check for abnormalities of swallowing, absence of gag reflex, weak hoarse voice, inability to cough forcefully



Figure 15.34 The Vagus Nerve (X). APR

---

[54] *vag* = wandering

TABLE 15.3 The Cranial Nerves (continued)

XI. Accessory Nerve. This nerve takes an unusual path. It arises from the upper spinal cord and not at all from the brain; therefore, strictly speaking, it is not a true cranial nerve. It ascends alongside the spinal cord, enters the cranial cavity through the foramen magnum, then exits the cranium through the jugular foramen, bundled with the vagus and glossopharyngeal nerves. The accessory nerve controls mainly swallowing and neck and shoulder muscles.

Composition	Function	Origin	Termination	Cranial Passage	Effect of Damage	Clinical Test
Predominantly motor	Swallowing; head, neck, and shoulder movements	Medulla oblongata and spinal cord segments C1 to C6	Palate; pharynx; trapezius and sternocleidomastoid muscles	Jugular foramen	Impaired movement of head, neck, and shoulders; difficulty shrugging shoulder on damaged side; paralysis of sternocleidomastoid, causing head to turn toward injured side	Test ability to rotate head and shrug shoulders against resistance


Jugular foramen
Foramen magnum
Spinal nerves C3 and C4
Vagus nerve
Accessory nerve (XI)
Sternocleidomastoid muscle
Trapezius muscle
Posterior view

Figure 15.35 The Accessory Nerve (XI). Posterior view. AP|R

XII. Hypoglossal[55] Nerve (HY-po-GLOSS-ul). This nerve controls tongue movements.

Composition	Function	Origin	Termination	Cranial Passage	Effect of Damage	Clinical Test
Predominantly motor	Tongue movements of speech, food manipulation, and swallowing	Medulla oblongata	Intrinsic and extrinsic muscles of tongue	Hypoglossal canal	Impaired speech and swallowing; inability to protrude tongue if both right and left nerves are damaged; deviation of tongue toward injured side, and atrophy on that side, if only one nerve is damaged	Note deviations of tongue as subject protrudes and retracts it; test ability to protrude tongue against resistance


Intrinsic muscles of the tongue
Extrinsic muscles of the tongue
Hypoglossal nerve (XII)

Figure 15.36 The Hypoglossal Nerve (XII). AP|R

---

[55] *hypo* = below; *gloss* = tongue

An Aid to Memory

Generations of biology and medical students have relied on mnemonic (memory-aiding) phrases and ditties, ranging from the sublimely silly to the unprintably ribald, to help them remember the cranial nerves and other anatomy. An old classic began, “On old Olympus’ towering tops . . . ,” with the first letter of each word matching the first letter of each cranial nerve (olfactory, optic, oculomotor, etc.). Some cranial nerves have changed names, however, since that passage was devised. A substitute now used by many students, taking the first letter of each nerve’s name, is “Oh, once one takes the anatomy final, very good vacation ahead.” The first two letters of *ahead* represent nerves XI and XII. One of the author’s former students, now a neurologist, devised a mnemonic that can remind you of the first two to four letters of most cranial nerves:

Old	**ol**factory (I)
Opie	**op**tic (II)
occasionally	**oc**ulomotor (III)
tries	**tr**ochlear (IV)
trigonometry	**trig**eminal (V)
and	**a**bducens (VI)
feels	**f**acial (VII)
very	**ve**stibulocochlear (VIII)
gloomy,	**glo**ssopharyngeal (IX)
vague,	**vagu**s (X)
and	**a**ccessory (XI)
hypoactive.	**hypo**glossal (XII)

Classification

Cranial nerves are traditionally classified as sensory (I, II, and VIII), motor (III, IV, VI, XI, and XII), or mixed (V, VII, IX, and X). In reality, only cranial nerves I and II (for smell and vision) are purely sensory, whereas all the rest contain both afferent and efferent fibers and are therefore mixed nerves. Those traditionally classified as motor not only stimulate muscle contractions but also contain afferent fibers of proprioception, which provide the brain with unconscious feedback for controlling muscle contraction and which make one consciously aware of such things as the position of the tongue and orientation of the head. Cranial nerve VIII, concerned with hearing and equilibrium, is traditionally classified as sensory, but also has motor fibers that return signals to the inner ear and “tune” it to sharpen one’s sense of hearing. The nerves traditionally classified as mixed have sensory functions quite unrelated to their motor functions—for example, the facial nerve (VII) has a sensory role in taste and a motor role in controlling facial expressions.

In order to teach the traditional classification (which is relevant for such purposes as board examinations and comparison to other books), yet remind you that all but two of these nerves are mixed, table 15.3 describes many of the nerves as *predominantly* sensory or motor.

Nerve Pathways

Most motor fibers of the cranial nerves begin in nuclei of the brainstem and lead to glands and muscles. The sensory fibers begin in receptors located mainly in the head and neck and lead mainly to the brainstem. Pathways for the special senses are described in chapter 17. Sensory fibers for proprioception begin in the muscles innervated by the motor fibers of the cranial nerves, but they often travel to the brain in a different nerve than the one that supplies the motor innervation.

Most cranial nerves carry fibers between the brainstem and ipsilateral receptors and effectors. Thus, a lesion on one side of the brainstem causes a sensory or motor deficit on the same side of the head. This contrasts with lesions to the motor and somatosensory cortex of the cerebrum, which, as we saw earlier, cause sensory and motor deficits on the contralateral side of the body. The exceptions are the optic nerve (cranial nerve II), where half the fibers decussate to the opposite side of the brain (see chapter 17), and the trochlear nerve (cranial nerve IV), in which all efferent fibers go to a muscle of the contralateral eye.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

21. List the purely sensory cranial nerves by name and number, and state the function of each.
22. What is the only cranial nerve to extend beyond the head–neck region? In general terms, where does it lead?
23. If the oculomotor, trochlear, or abducens nerve was damaged, the effect would be similar in all three cases. What would that effect be?
24. Which cranial nerve carries sensory signals from the largest area of the face?
25. Name two cranial nerves involved in the sense of taste and describe where their sensory fibers originate.

15.5 Developmental and Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe some ways in which neural function and cerebral anatomy change in old age; and
b. discuss Alzheimer and Parkinson diseases at the levels of neurotransmitter function and brain anatomy.

The Aging Central Nervous System

In chapter 13, we examined development of the nervous system at the beginning of life. As so many of us are regretfully aware, the nervous system also exhibits some marked changes at the other end of the life span. It attains its peak development and efficiency around age 30. By age 75, the average brain weighs slightly less than half what it did at age 30. The cerebral gyri are narrower, the sulci are wider, the cortex is thinner, and there is more space between the brain and meninges. The remaining neurons show signs that their metabolism is slowing down, such as less rough ER and Golgi complex. Old neurons accumulate lipofuscin pigment and begin to show *neurofibrillary tangles*—dense mats of cytoskeletal elements in their cytoplasm. In the extracellular material, *senile plaques* appear, especially in people with Down syndrome and Alzheimer disease. The plaques are composed of cells and altered nerve fibers surrounding a core of *amyloid protein.*

Old neurons are also less efficient at signal conduction and transmission. The degeneration of myelin sheaths slows down conduction along the axon. The neurons have fewer synapses, and for multiple reasons, signals are not transmitted across the synapses as well as in the younger years: The neurons produce less neurotransmitter, they have fewer receptors, and the neuroglia around the synapses is more leaky and allows neurotransmitter to diffuse away. Target cells have fewer receptors for norepinephrine, and the sympathetic nervous system thus becomes less able to regulate such variables as body temperature and blood pressure.

Not all functions of the central nervous system are equally affected by aging. Language skills and long-term memory hold up better than motor coordination, intellectual function, and short-term memory. Elderly people are often better at remembering things in the distant past than remembering recent events.

Two Neurodegenerative Diseases

Like a machine with a great number of moving parts, the nervous system is highly subject to malfunctions. Neurological disorders fill many volumes of medical textbooks and can hardly be touched upon here. We have considered meningitis and two cranial nerve disorders in Deeper Insights 15.1 and 15.2; several other neurological disorders are briefly described in table 15.4. We will close with a brief look at two of the most common brain dysfunctions, Alzheimer and Parkinson diseases. Both of these relate to neurotransmitter imbalances in the brain, and are considered to be *neurodegenerative diseases.* A basic understanding of these two diseases lends added clinical relevance to some areas of the brain studied in this chapter.

Alzheimer[56] disease (AD) affects about 11% of the U.S. population over the age of 65 and 47% by age 85. It accounts for nearly half of all nursing home admissions and is a leading cause of death among the elderly. AD may begin before the age of 50 with symptoms so slight and ambiguous that early diagnosis is difficult. One of its first symptoms is memory loss, especially for recent events. As the disease progresses, patients exhibit reduced attention span and may become disoriented and lost in previously familiar places. The AD patient may become moody, confused, paranoid, combative, or hallucinatory, and may eventually lose even the ability to read, write, talk, walk, and eat. Death ensues from pneumonia or other complications of confinement and immobility.

Diagnosis of AD is confirmed on autopsy. There is atrophy of some of the gyri of the cerebral cortex and hippocampus. Neurofibrillary tangles and senile plaques are abundant (fig. 15.37).

---

[56] Alois Alzheimer (1864–1915), German neurologist

TABLE 15.4 Some Disorders Associated with the Brain and Cranial Nerves

Cerebral palsy	Muscular incoordination resulting from damage to the motor areas of the brain during fetal development, birth, or infancy; causes include prenatal rubella infection, drugs, and radiation exposure; oxygen deficiency during birth; and hydrocephalus
Concussion	Damage to the brain typically resulting from a blow, often with loss of consciousness, disturbances of vision or equilibrium, and short-term amnesia
Encephalitis	Inflammation of the brain, accompanied by fever, usually caused by mosquito-borne viruses or herpes simplex virus; causes neural degeneration and necrosis; can lead to delirium, seizures, and death
Epilepsy	Disorder causing sudden, massive discharge of neurons (seizures) resulting in motor convulsions, sensory and psychic disturbances, and often impaired consciousness; may result from birth trauma, tumors, infections, drug or alcohol abuse, or congenital brain malformation
Migraine headache	Recurring headaches often accompanied by nausea, vomiting, dizziness, and aversion to light; often triggered by such factors as weather changes, stress, hunger, red wine, or noise; more common in women and sometimes hereditary
Schizophrenia	A thought disorder involving delusions, hallucinations, inappropriate emotional responses to situations, incoherent speech, and withdrawal from society, resulting from hereditary or developmental abnormalities in neural networks

Disorders Described Elsewhere

Alzheimer disease	436
Aphasia	423
Bell palsy	431
Brain tumors	360
Cerebellar ataxia	423
Cranial nerve injuries	429–436
Hydrocephalus	104
Meningitis	404
Multiple sclerosis	361
Parkinson disease	422, 439
Poliomyelitis	380
Tay–Sachs disease	361
Trigeminal neuralgia	431



© Science Source

© Simon Fraser/Science Source

Figure 15.37 **Alzheimer Disease.** (a) Brain of a person who died of AD. Note the shrunken gyri and wide sulci. (b) Cerebral tissue from a person with AD. Neurofibrillary tangles are present in the neurons, and a senile plaque is evident in the extracellular matrix.

Cholinergic neurons are reduced in number and the level of acetylcholine in affected areas of the brain is consequently low. Intense research efforts are currently geared toward identifying the cause of AD and developing treatment strategies. Researchers have identified three genes on chromosomes 1, 14, and 21 for various forms of early- and late-onset AD.

Parkinson[57] **disease (PD),** also called *paralysis agitans* or *parkinsonism,* is a progressive loss of motor function typically beginning in a person's 50s or 60s. It is due to degeneration of dopamine-releasing neurons in the substantia nigra of the midbrain. A gene has recently been identified for a hereditary form of PD, but most cases are nonhereditary and of little-known cause. Dopamine is an inhibitory neurotransmitter that normally prevents excessive activity in the basal nuclei. Degeneration of the dopamine-releasing neurons leads to hyperactivity of the basal nuclei and, therefore, involuntary muscle contractions. These take such forms as shaking of the hands (tremor) and compulsive "pill-rolling" motions of the thumb and fingers. In addition, the facial muscles may become rigid and produce a staring, expressionless face with a slightly open mouth. The patient's range of motion diminishes. He or she takes smaller steps and develops a slow, shuffling gait with a forward-bent posture and a tendency to fall forward. Speech becomes slurred and handwriting becomes cramped and eventually illegible. Tasks such as buttoning clothes and preparing food become increasingly laborious. Patients cannot be expected to recover from PD, but drugs, neurosurgery, and physical therapy can lessen the severity of its effects.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

26. Describe two respects in which neurons function less efficiently in old age.
27. Describe some changes seen in the brain with aging.
28. Describe the neuroanatomical and behavioral changes seen in Alzheimer and Parkinson diseases.

---

[57] James Parkinson (1755–1824), British physician

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

15.1 Overview of the Brain (p. 399)

1. The typical weight of the adult brain
2. The meanings of *rostral* and *caudal* in CNS anatomy
3. The three principal regions of the brain—cerebrum, cerebellum, and brainstem
4. Major landmarks of the brain, including the cerebral hemispheres, gyri and sulci, longitudinal and transverse cerebral fissures, and corpus callosum
5. Locations of the gray and white matter of the brain
6. The meninges of the brain; how they differ from those of the spinal cord; and the relationship of the dura mater to the dural sinuses
7. The four ventricles of the brain and their interconnections
8. The functions, sources, flow, and reabsorption of cerebrospinal fluid
9. The constituents of the brain barrier system; its significance in protecting the brain tissue; the limitations of this protection; and the significance of the barrier system as an obstacle to the treatment of some brain diseases

15.2 The Hindbrain and Midbrain (p. 406)

1. The location, anatomical features, and functions of the medulla oblongata, pons, and midbrain
2. The composition, location, and functions of the reticular formation
3. The gross anatomy and histology of the cerebellum, its routes of input and output, and its functions

15.3 The Forebrain (p. 413)

1. The two components of the forebrain and three components of the diencephalon
2. The location and general organization of the thalamus and its basic functions
3. The location and general organization of the hypothalamus and its functions
4. The location and components of the epithalamus and their functions
5. The major features of the cerebrum
6. The boundaries and functions of the five lobes of the cerebrum
7. The three types of fiber tracts in the white matter of the cerebrum, and what distinguishes the three from each other
8. The two types of neurons in the cerebral cortex, and what distinguishes the widespread neocortex from the more limited regions of paleocortex and archicortex
9. The location, major components, and general functions of the limbic system
10. The names and locations of the basal nuclei of the cerebrum, and their general function
11. The distinction between the primary cortex and the association areas of the cerebrum
12. The cerebral locations of primary and association cortex for each of the special senses: vision, hearing, equilibrium, taste, and smell
13. The somatosensory organization of the postcentral gyrus; the somatotopic correspondence between this gyrus and the contralateral side of the lower body; and the location and general function of the somatosensory association area
14. The somatic motor organization of the precentral gyrus; the somatotopic correspondence between this gyrus and the contralateral side of the lower body; and the location and general function of the motor association area
15. The locations and functional relationship of upper and lower motor neurons
16. The motor functions of the basal nuclei and cerebellum
17. The locations of the language centers of the cerebrum and how they interact in the comprehension of language, thinking of what to say or write, and speaking
18. Some causes of aphasia and some kinds of language deficit seen in aphasia
19. The roles of the hypothalamus, amygdala, and prefrontal cortex in the experience and expression of emotion
20. What is meant by *cognitive function*, and the roles of some brain areas in cognition
21. Forms of memory; roles of the amygdala and hippocampus in memory; and regions of cerebral cortex associated with various kinds of memory
22. The specialization of the two cerebral hemispheres for different cognitive, sensory, and motor functions, and the distinction between categorical and representational functions

15.4 The Cranial Nerves (p. 427)

1. The names and numbers of the 12 pairs of cranial nerves, and ability to identify them on the base of the brain
2. The origins, terminations, and functions of each of the cranial nerves I through XII, and of the individual subdivisions of the trigeminal nerve

15.5 Developmental and Clinical Perspectives (p. 437)

1. The common effects of aging on the central nervous system and the impact of these effects on one's functionality and quality of life
2. The signs and symptoms of Alzheimer disease (AD); the histological effects of AD that can be seen at autopsy; the relationship of AD to neurotransmitter function; and the genetic contribution to AD
3. The signs and symptoms of Parkinson disease (PD); the histological effects of PD that can be seen at autopsy; the relationship of PD to neurotransmitter function; and some treatment approaches to PD

Testing Your Recall

1. Which of these is caudal to the hypothalamus?
   a. the thalamus
   b. the optic chiasm
   c. the cerebral aqueduct
   d. the pituitary gland
   e. the corpus callosum
2. Hearing is associated mainly with
   a. the limbic system.
   b. the prefrontal cortex.
   c. the occipital lobe.
   d. the temporal lobe.
   e. the parietal lobe.
3. The blood–CSF barrier is formed by
   a. blood capillaries.
   b. endothelial cells.
   c. protoplasmic astrocytes.
   d. oligodendrocytes.
   e. ependymal cells.
4. The pyramids of the medulla oblongata contain
   a. descending corticospinal fibers.
   b. commissural fibers.
   c. ascending spinocerebellar fibers.
   d. fibers going to and from the cerebellum.
   e. ascending spinothalamic fibers.
5. Which of the following is *not* involved in vision?
   a. the temporal lobe
   b. the occipital lobe
   c. the midbrain tectum
   d. the trochlear nerve
   e. the vagus nerve
6. While studying in a noisy cafeteria, you get sleepy and doze off for a few minutes. You awaken with a start and realize that all the cafeteria sounds have just "come back." While you were dozing, this auditory input was blocked from reaching your auditory cortex by
   a. the temporal lobe.
   b. the thalamus.
   c. the reticular activating system.
   d. the medulla oblongata.
   e. the vestibulocochlear nerve.
7. Because of a brain lesion, a certain patient never feels full, but eats so excessively that she now weighs nearly 600 pounds. The lesion is most likely in her
   a. hypothalamus.
   b. amygdala.
   c. hippocampus.
   d. basal nuclei.
   e. pons.
8. The _____ is most closely associated with the cerebellum in embryonic development

and remains its primary source of input fibers throughout life.
   a. telencephalon
   b. thalamus
   c. midbrain
   d. pons
   e. medulla

9. Damage to the _____ nerve could result in defects of eye movement.
   a. optic
   b. vagus
   c. trigeminal
   d. facial
   e. abducens
10. All of the following *except* the _____ nerve begin or end in the orbit.
   a. optic
   b. oculomotor
   c. trochlear
   d. abducens
   e. accessory
11. The right and left cerebral hemispheres are connected to each other by a thick C-shaped bundle of fibers called the _____.
12. The brain has four chambers called _____ filled with _____ fluid.
13. In a sagittal section, the cerebellar white matter exhibits a branching pattern called the _____.
14. Part of the limbic system involved in forming new memories is the _____.
15. Cerebrospinal fluid is secreted partly by a mass of blood capillaries called the _____ in each ventricle.
16. The primary motor area of the cerebrum is the _____ gyrus of the frontal lobe.
17. Your personality is determined mainly by which lobe of the cerebrum?
18. Areas of cerebral cortex that identify or interpret sensory information are called _____.
19. Linear, analytical, and verbal thinking occurs in the _____ hemisphere of the cerebrum, which is on the left in most people.
20. The motor pattern for speech is generated in an area of cortex called the _____ and then transmitted to the primary motor cortex to be carried out.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. gyr-
2. sulc-
3. cereb-
4. pedunc-
5. insul-
6. -ellum
7. neo-
8. quadri-
9. foli-
10. radiat-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. The two hemispheres of the cerebrum are separated from each other by the transverse cerebral fissure.
2. Degeneration of the substantia nigra causes Alzheimer disease.
3. The midbrain is caudal to the thalamus.
4. The Broca area is ipsilateral to the Wernicke area.
5. Most of the cerebrospinal fluid is produced by the choroid plexuses.
6. Hearing is a function of the occipital lobe.
7. Respiration is controlled by nuclei in both the pons and medulla oblongata.
8. The trigeminal nerve carries sensory signals from a larger area of the face than the facial nerve does.
9. Unlike other cranial nerves, the vagus nerve extends far beyond the head–neck region.
10. The optic nerve controls movements of the eye.

Answers in appendix A

Testing Your Comprehension

1. Which cranial nerve conveys pain signals to the brain in each of the following situations: (a) sand blows into your eye; (b) you bite the rear of your tongue; and (c) your stomach hurts from eating too much?
2. How would a lesion in the cerebellum and a lesion in the basal nuclei differ in their effects on skeletal muscle function?
3. Suppose that a neuroanatomist performed two experiments on an animal species with the same basic spinal and brainstem structure as a human's: In experiment 1, he selectively transected (cut across) the pyramids on the anterior side of the medulla oblongata; and in experiment 2, he selectively transected the gracile and cuneate fasciculi on the posterior side. How would the outcomes of the two experiments differ?
4. A person can survive destruction of an entire cerebral hemisphere but cannot survive destruction of the hypothalamus, which is a much smaller mass of brain tissue. Explain this difference and describe some ways that destruction of a cerebral hemisphere would affect one's quality of life.
5. What would be the most obvious effects of lesions that destroyed each of the following: (a) the hippocampus, (b) the amygdala, (c) the Broca area, (d) the occipital lobe, and (e) the hypoglossal nerve?



Autonomic neurons in the myenteric plexus of the digestive tract

© Biophoto Associates/Science Source

CHAPTER

16

THE NERVOUS SYSTEM IV

AUTONOMIC NERVOUS SYSTEM AND VISCERAL REFLEXES

CHAPTER OUTLINE

16.1 General Properties of the Autonomic Nervous System 443
- General Actions 443
- Visceral Reflexes 443
- Divisions of the Autonomic Nervous System 444
- Neural Pathways 445

16.2 Anatomy of the Autonomic Nervous System 446
- The Sympathetic Division 446
- The Adrenal Glands 450
- The Parasympathetic Division 450
- The Enteric Nervous System 452

16.3 Autonomic Effects 453
- Neurotransmitters and Receptors 453
- Dual Innervation 454
- Central Control of Autonomic Function 455

16.4 Developmental and Clinical Perspectives 456
- Development and Aging of the Autonomic Nervous System 456
- Disorders of the Autonomic Nervous System 457

Study Guide 458

DEEPER INSIGHTS

16.1 Biofeedback 443
16.2 Megacolon 452
16.3 Drugs and the Autonomic Nervous System 455

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:

- Innervation of smooth muscle (p. 256)
- Overview of the nervous system (p. 352)
- Neurotransmitters and receptors (p. 362)
- General anatomy of nerves and ganglia (p. 380)
- Branches of the spinal nerves (p. 382)
- The hypothalamus (p. 415)
- The limbic system (p. 418)
- Cranial nerves, especially III, VII, IX, and X (pp. 430–435)

Anatomy & Physiology REVEALED®
aprevealed.com

Module 7: Nervous System

We are consciously aware of many of the activities of our nervous system discussed in the preceding chapters—the general and special senses, our cognitive processes and emotions, and our voluntary movements. But there is another branch of the nervous system that operates in comparative secrecy, usually without our willing it, thinking about it, or even being able to consciously modify or suppress it.

This secret agent is called the *autonomic nervous system (ANS).* Its name means "self-governed,"[1] as it is almost fully independent of our will. Its job is to regulate such fundamental states and life processes as heart rate, blood pressure, body temperature, respiratory airflow, pupillary diameter, digestion, energy metabolism, defecation, and urination. In short, the ANS quietly manages a multitude of unconscious processes responsible for the body's homeostasis.

Walter Cannon (1871–1945), the American physiologist who coined such expressions as *homeostasis* and the *fight-or-flight reaction,* dedicated his career to the study of the autonomic nervous system. He found that an animal can live without a functional sympathetic nervous system (one of the two divisions of the ANS), but it must be kept warm and free of stress. It cannot regulate its body temperature, tolerate any strenuous exertion, or even survive on its own. Indeed, the ANS is more necessary for survival than are many functions of the somatic nervous system; an absence of autonomic function is fatal because the body cannot maintain homeostasis without it. Thus, for an understanding of bodily function, the mode of action of many drugs, and other aspects of health care, we must be especially aware of how the ANS works.

16.1 General Properties of the Autonomic Nervous System

Expected Learning Outcomes

When you have completed this section, you should be able to

a. explain how the autonomic and somatic nervous systems differ in form and function;
b. explain what a visceral reflex is and describe some examples; and
c. explain how the two divisions of the autonomic nervous system differ in general function.

General Actions

The **autonomic nervous system (ANS)** can be defined as a motor nervous system that controls glands, cardiac muscle, and smooth muscle. It is also called the **visceral motor system** to distinguish it from the somatic motor system, which controls the skeletal muscles (see fig. 13.2, p. 352). The primary target organs of the ANS are the viscera of the thoracic and abdominopelvic cavities (such as the heart, lungs, and digestive and urinary tracts) and some structures of the body wall (such as cutaneous blood vessels, sweat glands, and piloerector muscles).

The somatic and visceral motor systems are often described as voluntary and involuntary, respectively. The somatic motor system innervates voluntary (skeletal) muscle, which is usually under the control of one's will (volition). Cardiac and smooth muscle are involuntary muscles; like glands, they are not usually subject to voluntary control. This voluntary–involuntary distinction is not, however, as clear-cut as it once seemed. Some skeletal muscle responses are quite involuntary, such as the somatic reflexes, and some skeletal muscles are difficult or impossible to control, such as the middle-ear muscles. On the other hand, therapeutic uses of biofeedback (see Deeper Insight 16.1) show that some people can learn to voluntarily control such visceral functions as blood pressure.

Visceral effectors do not depend on the autonomic nervous system to function, but only to adjust (modulate) their activity to the body's changing needs. The heart, for example, goes on beating even if all autonomic nerves to it are severed, but the ANS modulates the heart rate in conditions of rest and exercise. If the somatic nerves to a skeletal muscle are severed, the muscle exhibits flaccid paralysis—it no longer contracts at all. But if the autonomic nerves to cardiac or smooth muscle are severed, the muscle often exhibits exaggerated responses *(denervation hypersensitivity).*

Visceral Reflexes

The ANS works through **visceral reflexes.** These are unconscious, automatic, stereotyped responses to stimulation, much like the somatic reflexes discussed in chapter 14, but involving visceral receptors and effectors and somewhat slower responses. Some authorities regard the visceral afferent (sensory) pathways as part of the ANS, but most prefer to limit the term *ANS* to the efferent (motor) pathways. Regardless of this preference, however, autonomic activity involves a visceral reflex arc that includes receptors (nerve endings that detect stretch, tissue damage, blood chemicals, body

DEEPER INSIGHT 16.1

Biofeedback

Biofeedback is a technique in which an instrument produces auditory or visual signals in response to changes in a subject's blood pressure, heart rate, muscle tone, skin temperature, brain waves, or other physiological variables. It gives the subject awareness of changes that he or she would not ordinarily notice. Some people can be trained to control variables such as their blood pressure or heart rate in order to produce a certain tone or color of light from the apparatus. Eventually they can control them without the aid of the monitor. Biofeedback is not a quick, easy, infallible, or inexpensive cure for all ills, but it has been used successfully to treat hypertension, stress, and migraine headaches.

---

[1] *auto* = self; *nom* = rule

temperature, and other internal stimuli), afferent neurons leading to the CNS, interneurons in the CNS, efferent neurons carrying motor signals away from the CNS, and finally effectors.

For example, high blood pressure activates a visceral *baroreflex*.[2] It stimulates stretch receptors called *baroreceptors* in the carotid arteries and aorta, and they transmit signals via the glossopharyngeal nerves to the medulla oblongata (fig. 16.1). The medulla integrates this input with other information and transmits efferent signals back to the heart by way of the vagus nerves. The vagus nerves slow down the heart and reduce blood pressure, thus completing a homeostatic negative feedback loop. A separate baroreflex arc accelerates the heart when blood pressure above the heart drops—for example, when we change from lying down to standing up and gravity draws blood away from the upper body.

Another example of a visceral reflex is the autonomic response to chilling of the body. Cooling of the skin stimulates nerve endings called *cold receptors.* Nerve signals travel through spinal nerve fibers to the spinal cord and then up the spinothalamic tracts to the brainstem. This input is directed to the hypothalamic thermostat, a neural pool in the preoptic nucleus of the anterior hypothalamus. Neurons here also respond directly to cooling of the blood that circulates through the hypothalamus. In response, they transmit signals to the heat-promoting center of the posterior hypothalamus. Output from the heat-promoting center travels by nerve fibers that descend through the brainstem to the spinal cord and exit the cord through sympathetic pathways described later in this chapter. Sympathetic nerve fibers ultimately reach the blood vessels of the skin, stimulating contraction of the smooth muscle of the vessel walls. The resulting vasoconstriction diverts blood away from the skin surface, thus helping to reduce heat loss. Hypothalamic output can also increase muscle tone and induce shivering to generate additional body heat, but since this involves the skeletal muscles, it is a somatic reflex rather than a visceral one. Both the visceral and somatic components of thermoregulation, however, admirably exemplify the negative feedback loops that maintain homeostasis: A deviation from the homeostatic set point is detected (chilling of the body); signals are sent to neural integrating centers (the preoptic nucleus and the heat-promoting center of the hypothalamus); and responses are activated (cutaneous vasoconstriction, increased muscle tone, shivering) that return body temperature to the set point.


Integrating center
② Glossopharyngeal nerve transmits signals to medulla oblongata
Receptor
① Baroreceptors sense increased blood pressure
Internal carotid artery
③ Vagus nerve transmits inhibitory signals to cardiac pacemaker
Terminal ganglion
Effector
④ Heart rate decreases

Figure 16.1 An Autonomic Reflex Arc in the Regulation of Blood Pressure.

Divisions of the Autonomic Nervous System

The ANS has two divisions—*sympathetic* and *parasympathetic.* They differ in anatomy and function, but they often innervate the same target organs and have either antagonistic or cooperative effects on them. The **sympathetic division** adapts the body in many ways for physical activity—it increases alertness, heart rate, blood pressure, pulmonary airflow, blood glucose concentration, and blood flow to cardiac and skeletal muscle, but at the same time, it reduces blood flow to the skin and digestive tract. Cannon referred to extreme sympathetic responses as the "fight-or-flight" reaction because they come into play when an animal must attack, defend itself, or flee from danger. In our own lives, this reaction occurs in many situations involving arousal, exercise, competition, stress, danger, trauma, anger, or fear. Ordinarily, however, the sympathetic division has more subtle effects that we notice barely, if at all. The **parasympathetic division,** by comparison, has a calming effect on many body functions. It is associated with reduced energy expenditure and normal bodily maintenance, including such functions as digestion and waste elimination. This can be thought of as the "resting-and-digesting" state.

This does not mean that the body alternates between states in which one system or the other is active. Normally, both systems are active simultaneously. They exhibit a background rate of activity called **autonomic tone,** and the balance between *sympathetic tone* and *parasympathetic tone* shifts in accordance with the body's changing needs. Parasympathetic tone, for example, maintains smooth muscle tone in the intestines and holds the resting heart rate down to about 70 to 80 beats/min. If the parasympathetic vagus nerves to the heart are cut, the heart beats at its own intrinsic rate of about 100 beats/min. Sympathetic tone keeps most blood vessels partially constricted and thus maintains blood pressure.

---

[2] *baro* = pressure

A loss of sympathetic tone can cause such a rapid drop in blood pressure that a person goes into shock.

Neither division has universally excitatory or calming effects. The sympathetic division, for example, excites the heart but inhibits digestive and urinary functions, while the parasympathetic division has the opposite effects.

Neural Pathways

The ANS is often categorized as part of the peripheral nervous system, but it has components in both the central and peripheral nervous systems. It includes control nuclei in the hypothalamus and other regions of the brainstem, motor neurons in the spinal cord and peripheral ganglia, and nerve fibers that travel through the spinal and cranial nerves.

The autonomic motor pathway to a target organ differs significantly from somatic motor pathways. In somatic pathways, a motor neuron in the brainstem or spinal cord issues a myelinated axon that reaches all the way to a skeletal muscle. In autonomic pathways, the signal must travel across two nerve fibers to get to the target organ, and it must cross a synapse where the neurons meet in an autonomic ganglion (fig. 16.2). The first fiber, called the **preganglionic fiber,** leads from a soma in the brainstem or spinal cord to an autonomic ganglion outside the CNS. Here, it synapses with a neuron that issues a **postganglionic fiber** to the target cells. Autonomic preganglionic fibers are myelinated and the postganglionic fibers are unmyelinated.

In contrast to somatic motor nerve fibers, postganglionic fibers of the ANS do not end by synapsing with a specific target cell. Instead, they end in a chain of beadlike *varicosities* that diffusely release neurotransmitter into the tissue and stimulate many cells simultaneously (see fig. 10.18, p. 256).

Differences between the somatic and autonomic nervous systems are summarized in table 16.1.

TABLE 16.1 Comparison of the Somatic and Autonomic Nervous Systems

Feature	Somatic	Autonomic
Effectors	Skeletal muscle	Glands, smooth muscle, cardiac muscle
Control	Usually voluntary	Usually involuntary
Efferent pathways	One nerve fiber from CNS to effector; no ganglia	Two nerve fibers from CNS to effector; synapse at a ganglion
Distal nerve endings	Neuromuscular junctions	Varicosities
Neurotransmitters	Acetylcholine (ACh)	ACh and norepinephrine (NE)
Effect on target cells	Always excitatory	Excitatory or inhibitory
Effect of denervation	Flaccid paralysis	Denervation hypersensitivity


Somatic efferent innervation
Myelinated fiber
ACh
Somatic effectors (skeletal muscles)
Autonomic efferent innervation
ACh
ACh or NE
Myelinated preganglionic fiber
Unmyelinated postganglionic fiber
Visceral effectors (cardiac muscle, smooth muscle, glands)
Autonomic ganglion

Figure 16.2 Comparison of Somatic and Autonomic Efferent Pathways. The entire distance from CNS to effector is spanned by one neuron in the somatic system and two neurons in the autonomic system. Only acetylcholine (ACh) is employed as a neurotransmitter by the somatic neuron and the autonomic preganglionic neuron, but autonomic postganglionic neurons can employ either ACh or norepinephrine (NE).

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. How does the autonomic nervous system differ functionally and anatomically from the somatic motor system?
2. How does a visceral reflex resemble a somatic reflex? How does it differ?
3. What are the two divisions of the ANS? How do they functionally differ from each other?
4. Define *preganglionic* and *postganglionic fiber.* Why are these terms not used in describing the somatic motor system?

16.2 Anatomy of the Autonomic Nervous System

Expected Learning Outcomes

When you have completed this section, you should be able to

a. identify the anatomical components and nerve pathways of the sympathetic and parasympathetic divisions;
b. discuss the relationship of the adrenal glands to the sympathetic nervous system; and
c. describe the enteric nervous system of the digestive tract and explain its significance.

The Sympathetic Division

The sympathetic division is also called the *thoracolumbar division* because it arises from the thoracic and lumbar regions of the spinal cord. It has relatively short preganglionic and long postganglionic fibers. The preganglionic neurosomas are in the lateral horns and nearby regions of the gray matter of the spinal cord. Their fibers exit by way of spinal nerves T1 to L2 and lead to a nearby **sympathetic chain** of ganglia **(paravertebral[3] ganglia).** This is a longitudinal series of ganglia adjacent to each side of the vertebral column from the cervical to the coccygeal level. They are interconnected by longitudinal nerve cords (figs. 16.3 and 16.4). The number of ganglia varies from person to person, but usually there are 3 cervical (*superior, middle,* and *inferior*), 11 thoracic, 4 lumbar, 4 sacral, and 1 coccygeal ganglia in each chain.

It may seem odd that sympathetic ganglia exist in the cervical, sacral, and coccygeal regions considering that sympathetic fibers arise only from the thoracic and lumbar regions of the spinal cord (levels T1 to L2). But as shown in figure 16.4, nerve cords from the thoracic region ascend to the ganglia in the neck, and cords from the lumbar region descend to the sacral and coccygeal ganglia. Consequently, sympathetic nerve fibers are distributed to every level of the body. As a general rule, the head receives sympathetic output arising from spinal cord segment T1, the neck from T2, the thorax and upper limbs from T3 to T6, the abdomen from T7 to T11, and the lower limbs from T12 to L2. These nerve distributions, however, overlap and vary between individual people.

In the thoracolumbar region, each paravertebral ganglion is connected to a spinal nerve by two branches called *communicating*

---

[3] *para* = next to; *vertebr* = vertebral column



From *A Stereoscopic Atlas of Anatomy* by David L. Basett. Courtesy of Dr. Robert A. Chase, M.D.

Figure 16.3 **The Sympathetic Chain Ganglia.** Right lateral view of the thoracic cavity. (n. = nerve) APR


Pons
🟩 Preganglionic neurons
🟥 Postganglionic neurons
Regions of spinal cord
🟩 Cervical
🟦 Thoracic
🟧 Lumbar
🟨 Sacral
Postganglionic fibers to skin, blood vessels, adipose tissue
Sacral ganglia
Coccygeal ganglion
Sympathetic chain ganglia
Eye
Nasal glands
Salivary glands
Carotid plexuses
Cardiac and pulmonary plexuses
Heart
Lung
Celiac ganglion
Superior mesenteric ganglion
Inferior mesenteric ganglion
Liver and gallbladder
Stomach
Spleen
Pancreas
Small intestine
Large intestine
Rectum
Adrenal medulla
Kidney
Ovary
Uterus
Penis
Scrotum
Bladder

Figure 16.4 **Schematic of the Sympathetic Nervous System.** All of the nerve pathways and named ganglia occur on both left and right.

- *Does the sympathetic innervation of the lungs make a person inhale, exhale, both, or neither? Explain your answer.*

rami (fig. 16.5). The preganglionic fibers are small myelinated fibers that travel from the spinal nerve to the ganglion by way of the **white communicating ramus,**[4] which gets its color and name from the myelin. Unmyelinated postganglionic fibers leave the ganglion by various routes including a **gray communicating ramus,** named for its lack of myelin and duller color. This ramus forms a bridge back to the spinal nerve. Postganglionic fibers travel by way of the gray ramus and spinal nerve to the target organs.

Apply What You Know

Would autonomic postganglionic fibers have faster or slower conduction speeds than somatic motor fibers? Why? (See hints in chapter 13. Assume no significant difference in fiber diameter.)

After entering the sympathetic chain, preganglionic fibers may follow any of three courses:

- Some end in the ganglion that they enter and synapse immediately with a postganglionic neuron.
- Some travel up or down the chain and synapse in ganglia at other levels. It is these fibers that link the paravertebral ganglia into a chain. They are the only route by which ganglia at the cervical, sacral, and coccygeal levels receive input.
- Some pass through the chain without synapsing and continue as *splanchnic* (SPLANK-nic) *nerves,* to be considered shortly.

Nerve fibers leave the paravertebral ganglia by three routes: spinal, sympathetic, and splanchnic nerves. These are numbered in figure 16.5 to correspond to the following descriptions:

① **The spinal nerve route.** Some postganglionic fibers exit a ganglion by way of the gray ramus, return to the spinal nerve or its subdivisions, and travel the rest of the way to the target organ. This is the route to most sweat glands, piloerector muscles, and blood vessels of the skin and skeletal muscles.

② **The sympathetic nerve route.** Other postganglionic fibers leave the chain by way of sympathetic nerves that extend to the heart, lungs, esophagus, and thoracic blood vessels. These nerves form a **carotid plexus** around each carotid artery and issue fibers from there to effectors in the head—including sweat, salivary, and nasal glands;


🟩 Preganglionic neuron
🟥 Postganglionic neuron
🟪 Somatic neuron
Soma of preganglionic neuron
To iris, salivary glands, lungs, heart, thoracic blood vessels, esophagus
Sympathetic nerve
②
Spinal nerve
Preganglionic sympathetic fiber
Postganglionic sympathetic fiber
Somatic motor fiber
To somatic effector (skeletal muscle)
Soma of somatic motor neuron
To sweat glands, piloerector muscles, and blood vessels of skin and skeletal muscles
①
③
Splanchnic nerve
White ramus
Gray ramus
Communicating rami
Soma of postganglionic neuron
Collateral ganglion
Postganglionic sympathetic fibers
Sympathetic trunk
To liver, spleen, adrenal glands, stomach, intestines, kidneys, urinary bladder, reproductive organs
②
Sympathetic ganglion

Figure 16.5 Sympathetic Pathways (Right) Compared to Somatic Efferent Pathways (Left). Sympathetic fibers can follow any of the three numbered routes: (1) the spinal nerve route, (2) the sympathetic nerve route, or (3) the splanchnic nerve route.
• *Name the parts of the spinal cord where the somas of the sympathetic and somatic efferent neurons are located.*

---

[4] *ramus* = branch

piloerector muscles; blood vessels; and dilators of the iris. Some fibers from the superior and middle cervical ganglia form *cardiac nerves* to the heart. (The cardiac nerves also contain parasympathetic fibers.)

③ **The splanchnic[5] nerve route.** Some of the fibers that arise from spinal nerves T5 to T12 pass through the sympathetic ganglia without synapsing. Beyond the ganglia, they continue as **splanchnic nerves,** which lead to a second set of ganglia called **collateral (prevertebral) ganglia.** Here the preganglionic fibers synapse with the postganglionics.

The collateral ganglia contribute to a network, the **abdominal aortic plexus,** wrapped around the aorta (fig. 16.6). There are three major collateral ganglia in this plexus—the **celiac, superior mesenteric,** and **inferior mesenteric ganglia**—located at points where arteries of the same names branch off the aorta. The postganglionic fibers accompany these arteries and their branches to the target organs. Table 16.2 summarizes the innervation to and from the three major collateral ganglia.

The term *solar plexus* is used by some authorities as a collective name for the celiac and superior mesenteric ganglia, and by others as a synonym for the celiac ganglion only. The term comes from the nerves radiating from the ganglion like rays of the sun.

In summary, effectors in the muscles and body wall are innervated mainly by sympathetic fibers in the spinal nerves; effectors in the head and thoracic cavity by sympathetic nerves; and effectors in the abdominal cavity by splanchnic nerves.

---

[5] *splanchn* = viscera


Diaphragm
Esophagus
Celiac ganglia
Adrenal gland
Celiac trunk
Renal plexus
First lumbar sympathetic ganglion
Aortic plexus
Aorta
Pelvic sympathetic chain
(a)
Adrenal medulla
Adrenal cortex
(b)
Superior mesenteric ganglion
Superior mesenteric artery
Kidney
Inferior mesenteric artery
Inferior mesenteric ganglion

Figure 16.6 **Abdominal Components of the Sympathetic Nervous System.** (a) Collateral ganglia, abdominal aortic plexus, and adrenal glands. (b) The adrenal gland, frontal section. Only the adrenal medulla plays a role in the sympathetic nervous system; the adrenal cortex has unrelated roles described in chapter 18.

TABLE 16.2 **Innervation To and From the Collateral Ganglia**

Sympathetic Ganglia	→	Collateral Ganglion	→	Postganglionic Target Organs
Thoracic ganglia 5 to 9 or 10	→	Celiac ganglion	→	Stomach, spleen, liver, small intestine, and kidneys
Thoracic ganglia 9 and 10	→	Celiac and superior mesenteric ganglia	→	Small intestine, colon, and kidneys
Lumbar ganglia	→	Inferior mesenteric ganglion	→	Rectum, urinary bladder, and reproductive organs

There is no simple one-to-one relationship between preganglionic and postganglionic neurons in the sympathetic division. For one thing, each postganglionic cell may receive synapses from multiple preganglionic cells, thus exhibiting the principle of *neural convergence* discussed on page 364. Furthermore, each preganglionic fiber branches and synapses with multiple postganglionic fibers, thus showing *neural divergence.* Most sympathetic preganglionic neurons synapse with 10 to 20 postganglionic neurons. This means that when one preganglionic neuron fires, it can excite multiple postganglionic fibers leading to different target organs. The sympathetic division thus tends to have relatively widespread effects—as suggested by the name *sympathetic.*[6]

The Adrenal Glands

The paired **adrenal**[7] **(suprarenal) glands** rest like hats on the superior poles of the kidneys (fig. 16.6a). Each adrenal is actually two glands with different functions and embryonic origins. The outer rind, the **adrenal cortex,** secretes steroid hormones discussed in chapter 18. The inner core, the **adrenal medulla,** is essentially a sympathetic ganglion (fig. 16.6b). It consists of modified postganglionic neurons without dendrites or axons. Sympathetic preganglionic fibers penetrate through the cortex and terminate on these cells. The sympathetic nervous system and adrenal medulla are so closely related in development and function that they are referred to collectively as the *sympathoadrenal system.* The adrenal medulla secretes a mixture of hormones into the bloodstream—about 85% epinephrine (adrenaline), 15% norepinephrine (noradrenaline), and a trace of dopamine.

The Parasympathetic Division

The parasympathetic division is also called the *craniosacral division* because it arises from the brain and sacral region of the spinal cord; its fibers travel in certain cranial and sacral nerves. Somas of the preganglionic neurons are located in the midbrain, pons, medulla oblongata, and segments S2 to S4 of the spinal cord (fig. 16.7). They issue long preganglionic fibers that end in **terminal ganglia** in or near the target organ (see fig. 16.1). (If a terminal ganglion is embedded in the wall of a target organ, it is also called an *intramural*[8] *ganglion.*) Thus, the parasympathetic division has long preganglionic fibers, reaching almost all the way to the target cells, and short postganglionic fibers that cover the rest of the distance.

There is some neural divergence in the parasympathetic division, but much less than in the sympathetic. The parasympathetic division has a ratio of fewer than five postganglionic fibers to every preganglionic fiber. Furthermore, the preganglionic fiber reaches the target organ before even this slight divergence occurs. The parasympathetic division is therefore more selective than the sympathetic in its stimulation of target organs.

Parasympathetic fibers leave the brainstem by way of the following four cranial nerves. The first three supply all parasympathetic innervation to the head, and the last one supplies viscera of the thoracic and abdominopelvic cavities.

1. **Oculomotor nerve (III) (see page 430).** The oculomotor nerve carries parasympathetic fibers that control the lens and pupil of the eye. The preganglionic fibers enter the orbit and terminate in the *ciliary ganglion* behind the eyeball. Postganglionic fibers enter the eyeball and innervate the *ciliary muscle,* which thickens the lens, and the *pupillary constrictor,* which narrows the pupil.
2. **Facial nerve (VII) (see page 433).** The facial nerve carries parasympathetic fibers that regulate the tear glands, salivary glands, and nasal glands. Soon after the facial nerve emerges from the pons, its parasympathetic fibers split away and form two smaller branches. The superior branch ends at the *pterygopalatine ganglion* near the junction of the maxilla and palatine bone. Postganglionic fibers then continue to the tear glands and glands of the nasal cavity, palate, and other areas of the oral cavity. The inferior branch, called the *chorda tympani,* crosses the middle-ear cavity and ends at the *submandibular ganglion* near the angle of the mandible. Postganglionic fibers from here supply salivary glands in the floor of the mouth.
3. **Glossopharyngeal nerve (IX) (see page 434).** The glossopharyngeal nerve carries parasympathetic fibers concerned with salivation. The preganglionic fibers leave this nerve soon after its origin and form the *tympanic nerve.* A continuation of this nerve crosses the middle-ear cavity and ends in the *otic*[9] *ganglion* near the foramen ovale. The postganglionic fibers then follow the trigeminal nerve to the *parotid salivary gland* just in front of the earlobe.
4. **Vagus nerve (X) (see page 435).** The vagus nerve carries about 90% of all parasympathetic preganglionic fibers. It travels down the neck and forms three networks in the mediastinum—the **cardiac plexus,** which supplies fibers to the heart; the **pulmonary plexus,** whose fibers accompany the bronchi and blood vessels into the lungs; and the **esophageal plexus,** whose fibers regulate swallowing.

   At the lower end of the esophagus, the esophageal plexus gives off anterior and posterior **vagal trunks,** each of which contains fibers from both the right and left vagus nerves. These penetrate the diaphragm, enter the abdominal cavity,

---

[6] *sym* = together; *path* = feeling
[7] *ad* = near; *ren* = kidney
[8] *intra* = within; *mur* = wall
[9] *ot* = ear; *ic* = pertaining to


🟩 Preganglionic neurons
🟥 Postganglionic neurons
Pterygopalatine ganglion
Oculomotor n. (CN III)
Ciliary ganglion
Lacrimal gland
Eye
Facial n. (CN VII)
Submandibular ganglion
Submandibular salivary gland
Otic ganglion
Glossopharyngeal n. (CN IX)
Parotid salivary gland
Vagus n. (CN X)
Cardiac plexus
Heart
Pulmonary plexus
Esophageal plexus
Lung
Regions of spinal cord
🟩 Cervical
🟦 Thoracic
🟧 Lumbar
🟨 Sacral
Celiac ganglion
Abdominal aortic plexus
Stomach
Liver and gallbladder
Spleen
Pancreas
Pelvic splanchnic nerves
Kidney and ureter
Transverse colon
Descending colon
Inferior hypogastric plexus
Small intestine
Rectum
Pelvic nerves
Ovary
Uterus
Penis
Scrotum
Bladder

Figure 16.7 **Schematic of the Parasympathetic Nervous System.** All of the nerve pathways and named ganglia occur on both left and right.

- *Which nerve carries the most parasympathetic nerve fibers?* AP|R and contribute to the extensive *abdominal aortic plexus* mentioned earlier. As noted earlier, sympathetic fibers synapse here. The parasympathetic fibers, however, pass through the plexus without synapsing. They synapse farther along, in terminal ganglia in or near the liver, pancreas, stomach, small intestine, kidney, ureter, and proximal half of the colon.

The remaining parasympathetic fibers arise from levels S2 to S4 of the spinal cord. They travel a short distance in the anterior rami of the spinal nerves and then form **pelvic splanchnic nerves** that lead to the **inferior hypogastric plexus.** Some parasympathetic fibers synapse here, but most pass through this plexus and travel by way of **pelvic nerves** to the terminal ganglia in their target organs: the distal half of the large intestine, the rectum, urinary bladder, and reproductive organs. With few exceptions, the parasympathetic system does not innervate body wall structures (sweat glands, piloerector muscles, or cutaneous blood vessels).

The sympathetic and parasympathetic divisions of the ANS are compared in table 16.3.

Apply What You Know

Would autonomic functions be affected if the anterior roots of the cervical spinal nerves were damaged? Why or why not?

The Enteric Nervous System

The digestive tract has a nervous system of its own called the **enteric**[10] **nervous system.** Unlike the ANS proper, it does not arise from the brainstem or spinal cord, but like the ANS, it innervates smooth muscle and glands. Opinions differ on whether it should be considered part of the ANS. It consists of about 100 million neurons embedded in the wall of the digestive tract (see photograph on p. 442)—perhaps more neurons than there are in the spinal cord—and it has its own reflex arcs. The enteric nervous system regulates motility of the esophagus, stomach, and intestines and the secretion of digestive enzymes and acid. To function normally, however, these digestive activities also require regulation by the sympathetic and parasympathetic systems. The enteric nervous system is discussed in more detail in Deeper Insight 16.2 and chapter 24.

TABLE 16.3 Comparison of the Sympathetic and Parasympathetic Divisions

Feature	Sympathetic	Parasympathetic
Origin in CNS	Thoracolumbar	Craniosacral
Location of ganglia	Paravertebral ganglia adjacent to spinal column and prevertebral ganglia anterior to it	Terminal ganglia near or within target organs
Fiber lengths	Short preganglionic Long postganglionic	Long preganglionic Short postganglionic
Neuronal divergence	Extensive	Minimal
Effects of system	Often widespread and general	More local and specific

DEEPER INSIGHT 16.2

Megacolon

The importance of the enteric nervous system becomes vividly clear when it is absent. Such is the case in a hereditary defect called *Hirschsprung disease.*[11] During normal embryonic development, neural crest cells migrate to the large intestine and establish the enteric nervous system. In Hirschsprung disease, however, they fail to supply the distal parts of the large intestine, leaving the sigmoid colon and rectum (see fig. 24.16, p. 672) without enteric ganglia. In the absence of these ganglia, the sigmoidorectal region lacks motility, constricts permanently, and resists the passage of feces. Feces accumulate and become impacted above the constriction, resulting in *megacolon*—a massive dilation of the bowel accompanied by abdominal distension and chronic constipation. The most life-threatening complications are colonic gangrene, perforation of the bowel, and bacterial infection of the peritoneum *(peritonitis).* The treatment of choice is surgical removal of the affected segment and attachment of the healthy colon directly to the anal canal.

Hirschsprung disease is usually evident even in the newborn, which fails to have its first bowel movement. It affects four times as many infant boys as girls, and although its incidence in the general population is about 1 in 5,000 live births, it occurs in about 1 out of 10 infants with Down syndrome.

Hirschsprung disease is not the only cause of megacolon. In Central and South America, biting insects called *kissing bugs* transmit parasites called *trypanosomes* to humans. These parasites, similar to the ones that cause African sleeping sickness, cause *Chagas*[12] *disease.* Among other effects, they destroy the autonomic ganglia of the enteric nervous system, leading to a massively enlarged and often gangrenous colon.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

5. Explain why the sympathetic division is also called the thoracolumbar division even though its paravertebral ganglia extend all the way from the cervical to the sacral region.
6. Describe or diagram the structural relationships among the following: preganglionic fiber, postganglionic fiber, anterior ramus, gray ramus, white ramus, and paravertebral ganglion.
7. Explain in anatomical terms why the parasympathetic division affects target organs more selectively than the sympathetic division does.
8. Trace the pathway of a parasympathetic fiber of the vagus nerve from the medulla oblongata to the small intestine.

---

[10] *enter* = intestines; *ic* = pertaining to

[11] Harald Hirschsprung (1830–1916), Danish physician

[12] Carlos Chagas (1879–1934), Brazilian physician

16.3 Autonomic Effects

Expected Learning Outcomes

When you have completed this section, you should be able to

a. name the neurotransmitters employed by the ANS and define terms for neurons and synapses with different neurotransmitter and receptor types;
b. in terms of neurotransmitters and receptors, explain why the two divisions of the ANS can have contrasting effects on the same organs;
c. explain how the two divisions of the ANS interact when they both innervate the same organ; and
d. describe how the central nervous system regulates the ANS.

Neurotransmitters and Receptors

As noted earlier, the two divisions of the ANS often have contrasting effects on an organ. For example, the sympathetic division accelerates the heart, and the parasympathetic division slows it down. But this does not mean the sympathetic division is stimulatory and the parasympathetic division inhibitory to every organ. Each division stimulates some organs and inhibits others. For example, the parasympathetic division stimulates the contraction of intestinal smooth muscle but inhibits cardiac muscle. The sympathetic division has the opposite effects on these two muscular tissues. Several other examples of such contrasting effects are given in table 16.4. Cases in which one division has no effect are usually because it provides little or no innervation to that tissue or organ.

How can different autonomic neurons have such contrasting effects? There are two fundamental reasons: (1) Sympathetic and parasympathetic neurons secrete different neurotransmitters, and (2) cells respond in different ways even to the same neurotransmitter

TABLE 16.4 Effects of the Sympathetic and Parasympathetic Nervous Systems

Target	Effect of Sympathetic Division	Effect of Parasympathetic Division
Pupil of eye	Dilation	Constriction
Lens of eye	Thinning for far vision	Thickening for near vision
Lacrimal (tear) glands	None	Secretion
Sweat glands	Secretion	Usually no effect but produces palmar sweating
Piloerector muscles	Hair erection	No effect
Heart rate	Increased	Decreased
Blood vessels of most viscera	Vasoconstriction	Usually no effect but dilates gastrointestinal blood vessels
Blood vessels of skeletal muscles	Vasodilation	No effect
Blood vessels of skin	Vasoconstriction	Usually no effect but dilates some facial blood vessels, causing blushing
Bronchioles	Bronchodilation	Bronchoconstriction
Kidneys	Reduced urine output	No effect
Muscle of bladder wall	No effect	Contraction, emptying bladder
Salivary glands	Thick mucous secretion	Thin serous secretion
Gastrointestinal motility	Decreased	Increased
Gastrointestinal secretion	Decreased	Increased
Liver	Glycogen breakdown	Glycogen synthesis
Pancreatic enzyme secretion	Decreased	Increased
Penis and clitoris	Loss of erection	Erection
Ejaculation (smooth muscle roles—sperm propulsion and glandular secretion)	Stimulation	No effect

depending on what type of receptors they have for it. The basic categories of autonomic neurotransmitters and receptors are as follows (fig. 16.8 and table 16.5).

- **Acetylcholine (ACh).** This neurotransmitter is secreted by the preganglionic neurons in both divisions and the postganglionic neurons of the parasympathetic division. A few sympathetic postganglionics also secrete ACh—those that innervate sweat glands and some blood vessels. Any nerve fiber that secretes ACh is called a **cholinergic** (CO-li-NUR-jic) **fiber,** and any receptor that binds it is called a **cholinergic receptor.** There are two categories of cholinergic receptors:
    - **Muscarinic** (MUSS-cuh-RIN-ic) **receptors.** These are named for muscarine, a mushroom toxin used in their discovery. All cardiac muscle, smooth muscle, and gland cells that receive cholinergic innervation have muscarinic receptors. Because of different subclasses of muscarinic receptors, ACh excites some cells and inhibits others.
    - **Nicotinic** (NIC-oh-TIN-ic) **receptors.** These are named for another botanical toxin helpful to their discovery—nicotine. They occur at the synapses where autonomic preganglionic neurons stimulate the postganglionic cells; on cells of the adrenal medulla; and at the neuromuscular junctions of skeletal muscle fibers. ACh excites all cells with nicotinic receptors.
- **Norepinephrine (NE).** This neurotransmitter is secreted by nearly all sympathetic postganglionic neurons. Nerve fibers that secrete it are called **adrenergic fibers,** and the receptors for it are called **adrenergic receptors.** (NE is also called noradrenaline, the origin of the term *adrenergic*.) There are two principal categories of NE receptors:
    - **α-adrenergic receptors.** These usually have excitatory effects. For example, the binding of NE to the alpha receptors of uterine muscle promotes labor contractions.
    - **β-adrenergic receptors.** These are usually inhibitory. For example, the binding of NE to beta receptors inhibits intestinal motility.

  There are exceptions to both of these adrenergic effects because of physiologically different subclasses of both α- and β-adrenergic receptors, but we will not delve into such details.

Dual Innervation

Most of the viscera receive nerve fibers from both the sympathetic and parasympathetic divisions and thus are said to have **dual innervation.** In such cases, the two divisions may have either *antagonistic* or *cooperative effects* on the same organ. Antagonistic effects oppose each other. Thus, the sympathetic division dilates the pupil, and the parasympathetic division constricts it (fig. 16.9), among other examples already discussed and contrasted in table 16.4. Cooperative effects occur when the two divisions act on different effector cells in an organ to produce a unified overall effect. For example, the parasympathetic division stimulates the secretion of salivary enzymes, and the sympathetic division stimulates the secretion of salivary mucus.

Dual innervation is not always necessary for the ANS to produce opposite effects on an organ. The adrenal medulla, piloerector

(a) Parasympathetic fiber



(b) Sympathetic adrenergic fiber



(c) Sympathetic cholinergic fiber



Figure 16.8 **Neurotransmitters and Receptors of the Autonomic Nervous System.** (a) All parasympathetic fibers are cholinergic. (b) Most sympathetic postganglionic fibers are adrenergic; they secrete norepinephrine (NE), and the target cell bears adrenergic receptors. (c) A few sympathetic postganglionic fibers are cholinergic; they secrete acetylcholine (ACh), and the target cell has cholinergic receptors of the muscarinic class.

TABLE 16.5 **Locations of Cholinergic and Adrenergic Fibers in the ANS**

Division	Preganglionic Fibers	Postganglionic Fibers
Sympathetic	Always cholinergic	Mostly adrenergic; a few cholinergic
Parasympathetic	Always cholinergic	Always cholinergic

DEEPER INSIGHT 16.3

Drugs and the Autonomic Nervous System

The design of many drugs has been based on an understanding of autonomic neurotransmitters and receptor classes. *Sympathomimetics*[13] are drugs that enhance sympathetic action by stimulating adrenergic receptors or promoting norepinephrine release. For example, phenylephrine, found in such cold medicines as Dimetapp and Sudafed PE, aids breathing by stimulating certain α-adrenergic receptors and thus dilating the bronchioles, constricting nasal blood vessels, and reducing swelling in the nasal mucosa. *Sympatholytics*[14] are drugs that suppress sympathetic action by inhibiting norepinephrine release or binding to adrenergic receptors without stimulating them. Propranolol, for example, is a *β-blocker* used to treat hypertension. It blocks the action of epinephrine and norepinephrine on β-adrenergic receptors of the heart and blood vessels.

Parasympathomimetics enhance parasympathetic effects. Pilocarpine, for example, relieves glaucoma (excessive pressure within the eye) by dilating a vessel that drains fluid from the eye. *Parasympatholytics* inhibit ACh release or block its receptors. Atropine, for example, blocks muscarinic receptors and is sometimes used to dilate the pupils for eye examinations and to dry the mucous membranes of the respiratory tract before inhalation anesthesia. It is an extract of the deadly nightshade plant, *Atropa belladonna.*[15] Women of the Middle Ages used nightshade to dilate their pupils, which was regarded as a beauty enhancement.

The branch of medicine that deals with the effects of drugs on the nervous system—especially drugs that mimic, enhance, or inhibit the action of neurotransmitters—is called *neuropharmacology.*


Brain
Parasympathetic fibers of oculomotor nerve (III)
Sympathetic fibers
Superior cervical ganglion
Ciliary ganglion
Spinal cord
Cholinergic stimulation of pupillary constrictor
Iris
Pupil
Adrenergic stimulation of pupillary dilator
Sympathetic (adrenergic) effect
Parasympathetic (cholinergic) effect
Pupil dilated
Pupil constricted

Figure 16.9 **Dual Innervation of the Iris.** Antagonistic effects of the sympathetic (yellow) and parasympathetic (blue) divisions on the iris.
• *If a person is in a state of fear, would you expect the pupils to be dilated or constricted? Why?*

muscles, sweat glands, and many blood vessels receive only sympathetic fibers. An example of control without dual innervation is the regulation of blood flow. The sympathetic fibers to a blood vessel have a baseline sympathetic tone that keeps the vessels in a state of partial constriction called *vasomotor tone* (fig. 16.10). An increase in sympathetic stimulation causes vasoconstriction by increasing smooth muscle contraction. A drop in sympathetic stimulation allows the smooth muscle to relax and the vessel to dilate.

Central Control of Autonomic Function

In spite of its name, the ANS is not an independent nervous system. All of its output originates in the CNS, and it receives input from the cerebral cortex, hypothalamus, medulla oblongata, and somatic division of the PNS.

Effects of the cerebral cortex on autonomic function are evident when anger raises the blood pressure, fear makes the heart race, thoughts of good food make the stomach rumble, and sexual thoughts or images increase blood flow to the genitals. The limbic system (p. 418) is involved in many emotional responses and has extensive connections with the hypothalamus, an important autonomic control center. Thus, the limbic system provides a pathway connecting sensory and mental experiences with the autonomic nervous system.

The hypothalamus contains many nuclei for primitive autonomic functions, including hunger, thirst, thermoregulation, and sexual response. Artificial stimulation of different regions of the hypothalamus can activate the arousal response typical of the sympathetic nervous system or have the calming effects typical of the parasympathetic. Output from the hypothalamus travels largely to nuclei in more caudal regions of the brainstem and from there to the cranial nerves and the sympathetic preganglionic neurons in the spinal cord.

---

[13] *mimet* = imitate, mimic
[14] *lyt* = break down, destroy
[15] *bella* = beautiful, fine; *donna* = woman



(a) Vasoconstriction



(b) Vasodilation

Figure 16.10 **Sympathetic and Vasomotor Tone.** (a) Vasoconstriction in response to a high rate of sympathetic nerve firing. (b) Vasodilation in response to a low rate of sympathetic nerve firing. Smooth muscle relaxation allows blood pressure within the vessel to push the vessel wall outward. Black lines crossing each nerve fiber represent action potentials, with a high firing frequency in (a) and a lower frequency in (b).

The midbrain, pons, and medulla oblongata house the nuclei of cranial nerves that mediate several autonomic responses: the oculomotor nerve (pupillary constriction), facial nerve (lacrimal, nasal, palatine, and salivary gland secretion), glossopharyngeal nerve (salivation, blood pressure regulation), and vagus nerve (the chief parasympathetic supply to the thoracic and abdominal viscera).

The spinal cord also contains autonomic control nuclei. Such autonomic responses as the defecation and micturition (urination) reflexes are regulated here. Fortunately, the brain is able to inhibit these responses consciously, but when injuries sever the spinal cord from the brain, the autonomic spinal reflexes alone control the elimination of urine and feces.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

9. To what neurotransmitters do the terms *adrenergic* and *cholinergic* refer?
10. Why is a single autonomic neurotransmitter able to have opposite effects on different target cells?
11. What are the two ways in which the sympathetic and parasympathetic divisions can interact when they both innervate the same target organ? Give examples.
12. How can the sympathetic nervous system have contrasting effects in a target organ without dual innervation?
13. What system in the brain connects our conscious thoughts and feelings with the autonomic control centers of the hypothalamus?
14. List some autonomic responses that are controlled by nuclei in the hypothalamus.
15. What are the roles of the midbrain, pons, and medulla in autonomic control?
16. Name some visceral reflexes controlled by the spinal cord.

16.4 Developmental and Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the embryonic origins of the autonomic neurons and ganglia;
b. describe some consequences of aging of the autonomic nervous system; and
c. describe a few disorders of autonomic function.

Development and Aging of the Autonomic Nervous System

Preganglionic neurons of the autonomic nervous system develop from the *neural tube* described in chapter 13; their somas remain embedded in the brainstem and spinal cord for life. Autonomic ganglia and postganglionic neurons, however, develop from the *neural crest* adjacent to the neural tube. During the fifth week of embryonic development, some neural crest cells migrate and assume positions alongside the vertebral bodies to become the sympathetic chain ganglia; others assume positions alongside the aorta to form the abdominal aortic plexus; and others migrate to the heart, lungs, digestive tract, and other viscera to form the terminal ganglia of the parasympathetic division.

The adrenal medulla arises from cells that separate from a nearby sympathetic ganglion, and thus ultimately comes from neural crest (ectodermal) cells. During its development, the medulla is surrounded by cells of mesodermal origin that produce the outer layer of the adrenal gland, the adrenal cortex (which is not part of the autonomic nervous system).

The efficiency of the ANS declines in old age, like that of the rest of the nervous system (see chapter 15). Target organs of the ANS have fewer neurotransmitter receptors in old age and are thus less responsive to autonomic stimulation. As a result, elderly people may experience dry eyes and more eye infections; slower and less effective adaptation of the eye to changing light intensities, and poorer night vision; less efficient control of blood pressure; and reduced intestinal motility and increasing constipation. Because of reduced efficiency of the baroreflex, described earlier in this chapter, some elderly people experience *orthostatic hypotension,* a drop in blood pressure when they stand up, sometimes causing dizziness, loss of balance, or fainting.

Disorders of the Autonomic Nervous System

Table 16.6 describes some dysfunctions of the autonomic nervous system.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

17. How do the pre- and postganglionic neurons of the ANS differ in embryonic origin?
18. Briefly state how the intestines, eyes, and blood pressure are affected in old age by the declining efficiency of the autonomic nervous system.

TABLE 16.6 Some Disorders of the Autonomic Nervous System

Achalasia[16] of the cardia	A defect in autonomic innervation of the esophagus, resulting in impaired swallowing, accompanied by failure of the lower esophageal sphincter to relax and allow food to pass into the stomach. (The region of the stomach at its junction with the esophagus is called the *cardia.*) Results in enormous dilation of the esophagus and inability to keep food down. Most common in young adults; cause remains poorly understood.
Horner[17] syndrome	Chronic unilateral pupillary constriction, sagging of the eyelid, withdrawal of the eye into the orbit, flushing of the skin, and lack of facial perspiration. Results from lesions in the cervical ganglia, upper thoracic spinal cord, or brainstem that interrupt sympathetic innervation of the head.
Raynaud[18] disease	Occasional spasmodic contractions of the digital arteries, numbness, coldness, and pain in the fingers or toes. The digits may at first appear cyanotic, but then redden, with throbbing and paresthesia (tingling, burning, or itching sensations). Repeated and severe cases can lead to brittle nails and occasionally to gangrene and a necessity for amputation. Most common in young women and often triggered by emotional stress or brief exposure to cold. Sometimes treated by severing sympathetic nerves to affected regions.

Disorders Described Elsewhere

Autonomic effects of oculomotor and vagus nerve injuries 430, 435	Chagas disease 452	Mass reflex reaction 394
	Hirschsprung disease 452	Orthostatic hypotension 457

---

[16] *a* = without; *chalas* = relaxation
[17] Johann F. Horner (1831–86), Swiss ophthalmologist
[18] Maurice Raynaud (1834–81), French physician

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

16.1 General Properties of the Autonomic Nervous System (p. 443)

1. The general function and effectors of the autonomic nervous system (ANS)
2. The involuntary nature of the ANS
3. The nature of visceral reflex arcs
4. The contrast between the general physiological effects of the sympathetic and parasympathetic divisions of the ANS
5. Autonomic tone and the simultaneous activity of the sympathetic and parasympathetic divisions
6. The basic anatomical components of the ANS
7. The two-neuron pathway of autonomic output

16.2 Anatomy of the Autonomic Nervous System (p. 446)

1. The spinal cord regions from which the sympathetic nervous system arises
2. The anatomy of the sympathetic chain of ganglia, including the number of ganglia at each level and why the chain extends to levels higher and lower than the spinal cord origins of sympathetic nerves
3. The varied routes and terminations of the sympathetic preganglionic nerve fibers within and sometimes beyond the sympathetic chain
4. The place of the splanchnic nerves and abdominal aortic plexus in the sympathetic nervous system, and the three ganglia of the abdominal aortic plexus
5. The degree of neural divergence in the sympathetic division and the effect of this on the stimulation of target organs by this division
6. The role of the adrenal medulla and its hormones in the sympathetic nervous system
7. Identity of the cranial and spinal nerves that carry parasympathetic output
8. The routes and destinations of the parasympathetic fibers in cranial nerves III, VII, IX, and X, including the thoracic and abdominal nerve plexuses through which the fibers of the vagus nerve pass
9. The routes and destinations of the parasympathetic fibers that arise from the sacral spinal cord, including the pelvic splanchnic nerves, inferior hypogastric plexus, and pelvic nerves
10. The location and function of the enteric nervous system

16.3 Autonomic Effects (p. 453)

1. The determination of autonomic effects on a target cell by a combination of the neurotransmitter and the receptor type involved
2. The definition of *cholinergic nerve fibers* and where they occur in the ANS
3. The two classes of cholinergic receptors and how they differ in their effects
4. The definition of *adrenergic nerve fibers* and where they occur in the ANS
5. The two classes of adrenergic receptors and how they differ in their effects
6. Cases of dual innervation of a target organ by the ANS and varied ways in which the sympathetic and parasympathetic divisions interact when dual innervation occurs
7. How the sympathetic division can exert contrasting effects on a single target organ in the absence of dual innervation
8. The multiple levels of CNS control over the autonomic nervous system

16.4 Developmental and Clinical Perspectives (p. 456)

1. Which components of the ANS arise from the embryonic neural tube and which ones arise from the neural crest
2. How ANS function changes with age, and the effects of ANS aging on functionality and quality of life

Testing Your Recall

1. The autonomic nervous system innervates all of these *except*
   a. cardiac muscle.
   b. skeletal muscle.
   c. smooth muscle.
   d. salivary glands.
   e. blood vessels.

2. Muscarinic receptors bind
   a. epinephrine.
   b. norepinephrine.
   c. acetylcholine.
   d. cholinesterase.
   e. neuropeptides.

3. All of the following cranial nerves except the _____ carry parasympathetic fibers.
   a. vagus
   b. facial
   c. oculomotor
   d. glossopharyngeal
   e. hypoglossal

4. Which of the following cranial nerves carries sympathetic fibers?
   a. oculomotor
   b. facial
   c. trigeminal
   d. vagus
   e. none of the cranial nerves

5. Which of these ganglia is *not* involved in the sympathetic division?
   a. intramural
   b. paravertebral
   c. celiac
   d. inferior mesenteric
   e. superior cervical

6. Epinephrine is secreted by
   a. sympathetic preganglionic fibers.
   b. sympathetic postganglionic fibers.
   c. parasympathetic preganglionic fibers.
   d. parasympathetic postganglionic fibers.
   e. the adrenal medulla.

7. The most important autonomic control center in the CNS is
   a. the cerebral cortex.
   b. the limbic system.
   c. the midbrain.
   d. the hypothalamus.
   e. the sympathetic chain ganglia.

8. The gray communicating ramus contains
   a. visceral sensory fibers.
   b. parasympathetic motor fibers.
   c. sympathetic preganglionic fibers.
   d. sympathetic postganglionic fibers.
   e. somatic motor fibers.

9. The neural crest gives rise to all of the following *except*
   a. sympathetic chain ganglia.
   b. the celiac ganglion.
   c. parasympathetic preganglionic neurons.
   d. parasympathetic postganglionic neurons.
   e. the adrenal medulla.
10. Which of these does *not* result from sympathetic stimulation?
    a. dilation of the pupil
    b. acceleration of the heart
    c. digestive secretion
    d. bronchodilation
    e. piloerection
11. Nerve fibers that secrete norepinephrine are called _____ fibers.
12. _____ is a state in which a target organ receives both sympathetic and parasympathetic fibers.
13. _____ is a state of continual background activity of the sympathetic and parasympathetic divisions.
14. Most parasympathetic preganglionic fibers are found in the _____ nerve.
15. The digestive tract has a semi-independent nervous system called the _____ nervous system.
16. The embryonic tissue that gives rise to all autonomic ganglia and postganglionic neurons, but not to any preganglionic neurons, is the _____.
17. The adrenal medulla consists of modified postganglionic neurons of the _____ nervous system.
18. The sympathetic nervous system has short _____ and long _____ nerve fibers.
19. Orthostatic hypotension is the result of inefficiency of an autonomic reflex called the _____.
20. Sympathetic stimulation of blood vessels maintains a state of partial vasoconstriction called _____.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. nom-
2. baro-
3. splanchno-
4. reno-
5. path-
6. para-
7. lyt-
8. auto-
9. ram-
10. mur-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. The parasympathetic nervous system shuts down when the sympathetic nervous system is active, and vice versa.
2. Some blood vessels of the skin receive parasympathetic innervation.
3. Voluntary control of the ANS is not possible.
4. The sympathetic nervous system stimulates digestion.
5. Some sympathetic postganglionic fibers are cholinergic.
6. Urination and defecation cannot occur without signals from the brain to the bladder and rectum.
7. Some parasympathetic nerve fibers are adrenergic.
8. Parasympathetic effects are more localized and specific than sympathetic effects.
9. The parasympathetic division shows less neural divergence than the sympathetic division does.
10. The two divisions of the ANS have antagonistic effects on the iris.

Answers in appendix A

Testing Your Comprehension

1. You are dicing raw onions while preparing dinner, and the vapor makes your eyes water. Describe the afferent and efferent pathways involved in this response.
2. Suppose you are walking alone at night when you hear a dog growling close behind you. Describe the ways your sympathetic nervous system would prepare you to deal with this situation.
3. Suppose the cardiac nerves were destroyed. How would this affect the heart and the body's ability to react to a stressful situation?
4. What would be the advantage to a wolf in having its sympathetic nervous system stimulate the piloerector muscles? What happens in a human when the sympathetic system stimulates these muscles?
5. Pediatric literature has reported cases of poisoning of children with Lomotil, an antidiarrheal medicine. Lomotil works by means of the morphinelike effects of its chief ingredient, diphenoxylate, but it also contains atropine. Considering the mode of action described for atropine in Deeper Insight 16.3, why might it contribute to the antidiarrheal effect of Lomotil? In atropine poisoning, would you expect the pupils to be dilated or constricted? The skin to be moist or dry? The heart rate to be elevated or depressed? The bladder to retain urine or void uncontrollably? Explain each answer.



Microvilli forming a distinctive V-shaped row on a sensory cell of the inner ear

© SPL/Science Source

CHAPTER 17

THE NERVOUS SYSTEM V
SENSE ORGANS

CHAPTER OUTLINE

17.1 Receptor Types and the General Senses 461
- Classification of Receptors 461
- The General Senses 461
- The Receptive Field 463
- Somatosensory Projection Pathways 463
- Pain 464

17.2 The Chemical Senses 466
- Taste 466
- Smell 468

17.3 The Ear 470
- Anatomy of the Ear 470
- Auditory Function 474
- The Auditory Projection Pathway 475
- The Vestibular Apparatus 475
- Vestibular Projection Pathways 479

17.4 The Eye 480
- Accessory Structures of the Orbit 480
- Anatomy of the Eyeball 482
- Formation of an Image 485
- Structure and Function of the Retina 486
- The Visual Projection Pathway 489

17.5 Developmental and Clinical Perspectives 491
- Development of the Ear 491
- Development of the Eye 491
- Disorders of the Sense Organs 491

Study Guide 494

DEEPER INSIGHTS

17.1 The Value of Pain 465
17.2 Middle-Ear Infection 471
17.3 Deafness 474
17.4 Cataracts and Glaucoma 484

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:

- Converging circuits of neurons (p. 364)
- Spinal cord tracts (p. 375)
- Decussation (p. 375)
- Sensory areas of the cerebral cortex (p. 420)
- The cranial nerves (p. 427)

Anatomy & Physiology REVEALED®
apревealed.com

Module 7: Nervous System

Anyone who enjoys music, art, fine food, or a good conversation appreciates the human senses. Yet their importance extends beyond deriving pleasure from the environment. In the 1950s, behavioral scientists at Princeton University studied the methods used by Soviet Communists to extract confessions from political prisoners, including solitary confinement and sensory deprivation. Student volunteers were immobilized in dark soundproof rooms or suspended in dark chambers of water. In a short time, they experienced visual, auditory, and tactile hallucinations, incoherent thought patterns, deterioration of intellectual performance, and sometimes morbid fear or panic. Similar effects are sometimes seen in burn patients who are immobilized and extensively bandaged (including the eyes) and thus suffer prolonged lack of sensory stimulation. Patients connected to life-support equipment and confined under oxygen tents sometimes become delirious. In short, sensory input is vital to the integrity of the personality and intellectual function.

Furthermore, much of the information communicated by the sense organs never comes to our conscious attention—blood pressure, body temperature, and muscle tension, for example. By monitoring such conditions, however, the sense organs initiate somatic and visceral reflexes that are indispensable to homeostasis and to our very survival in a ceaselessly changing and challenging environment.

17.1 Receptor Types and the General Senses

Expected Learning Outcomes

When you have completed this section, you should be able to

a. define *receptor* and *sense organ;*
b. outline three ways of classifying sensory receptors;
c. define *general senses,* list several types, and describe their receptors;
d. explain the meaning and relevance of a sensory neuron's receptive field;
e. describe the pathways that the general senses take to the cerebral cortex; and
f. describe the types of pain and its projection pathways.

A sensory **receptor** is any structure specialized to detect a stimulus. Some receptors are simple nerve endings (dendrites), whereas others are **sense organs**—nerve endings combined with connective, epithelial, or muscular tissues that enhance or moderate the response to a stimulus. Our eyes and ears are obvious examples of sense organs, but there are also innumerable microscopic sense organs in our skin, muscles, joints, and viscera.

Classification of Receptors

Receptors can be classified by multiple overlapping systems:

1. By **modality** (type of stimulus):
   - **Thermoreceptors** respond to heat and cold.
   - **Photoreceptors,** the eyes, respond to light.
   - **Chemoreceptors** respond to chemicals, including odor, taste, and body fluid composition.
   - **Nociceptors**[1] (NO-sih-SEP-turs) are pain receptors; they respond to tissue damage resulting from trauma (blows, cuts), ischemia (poor blood flow), or excessive stimulation by agents such as heat and chemicals.
   - **Mechanoreceptors** respond to physical deformation of a tissue or cell caused by touch, pressure, stretch, tension, or vibration. They include the organs of hearing and balance and many receptors of the skin, viscera, and joints.
2. By the distribution of receptors in the body:
   - **General (somatosensory, somesthetic) senses** employ receptors that are widely distributed in the skin, muscles, tendons, joint capsules, and viscera. They detect touch, pressure, stretch, heat, cold, and pain, as well as many stimuli that we do not perceive consciously, such as blood pressure and blood chemistry. Their receptors are relatively simple in structure—sometimes nothing more than a bare dendrite.
   - **Special senses** are mediated by relatively complex sense organs of the head, innervated by the cranial nerves. They include vision, hearing, equilibrium, taste, and smell.
3. By the origins of the stimuli:
   - **Exteroceptors** sense stimuli external to the body; they include the receptors for vision, hearing, taste, smell, and the cutaneous (skin) senses such as heat, touch, and pain.
   - **Interoceptors** detect stimuli in the internal organs such as the stomach, intestines, and urinary bladder and produce such feelings as visceral pain, nausea, stretch, and pressure.
   - **Proprioceptors** sense the position and movements of the body or its parts. They occur in muscles, tendons, and joint capsules.

The General Senses

Receptors for the general senses are relatively simple in structure and physiology. They consist of one or a few nerve fibers and usually a sparse amount of connective tissue. Depending on the absence or presence of connective tissue, they are classified as unencapsulated or encapsulated nerve endings, respectively (table 17.1). Nine types of simple receptors for the general senses are described here and illustrated in figure 17.1.

Unencapsulated nerve endings are sensory dendrites that lack a connective tissue wrapping. They include the following:

- **Free nerve endings**—*warm receptors,* which respond to rising temperature; *cold receptors,* which respond to falling temperature; and *nociceptors,* or pain receptors. These are bare dendrites unassociated with any specific accessory cells or tissues. They are most abundant in the skin and mucous membranes. They typically show profuse, fine branches that penetrate through the connective tissue or between epithelial cells.

---

[1] *noci* = pain

TABLE 17.1 Receptors of the General Senses

Receptor Type	Locations	Modality
Unencapsulated endings		
Free nerve endings	Widespread, especially in epithelia and connective tissues	Pain, heat, cold
Tactile discs	Stratum basale of epidermis	Light touch, pressure
Hair receptors	Around hair follicle	Light touch, movement of hairs
Encapsulated nerve endings		
Tactile corpuscles	Dermal papillae of fingertips, palms, eyelids, lips, tongue, nipples, and genitals	Light touch, texture
End bulbs	Mucous membranes	Similar to tactile corpuscles
Bulbous corpuscles	Dermis, subcutaneous tissue, and joint capsules	Heavy continuous touch or pressure; joint movements
Lamellar corpuscles	Dermis, joint capsules, periosteum, breasts, genitals, and some viscera	Deep pressure, stretch, tickle, vibration
Muscle spindles	Skeletal muscles near tendon	Tension in muscles (proprioception)
Tendon organs	Tendons	Tension in tendons (proprioception)



Free nerve endings **Tactile disc** **Hair receptor**



Tactile corpuscle **End bulb** **Bulbous corpuscle**



Lamellar corpuscle **Muscle spindle** **Tendon organ**

Figure 17.1 **Receptors of the General (Somatosensory) Senses.** See table 17.1 for functions.

- **Tactile discs—**receptors for light touch and pressure on the skin. A tactile disc is a flattened nerve ending associated with a specialized *tactile (Merkel) cell* at the base of the epidermis.
- **Hair receptors (peritrichial[2] endings)—**dendrites that coil around a hair follicle and respond to movements of the hair. These are stimulated when, for example, an ant walks across one's skin, bending one hair after another. However, they adapt quickly, so we are not constantly irritated by the feel of clothing against the skin. Hair receptors are particularly important in the eyelashes, where the slightest touch evokes a protective blink reflex.

Encapsulated nerve endings are dendrites wrapped in glial cells or connective tissue. Most of them are mechanoreceptors for touch, pressure, and stretch. The connective tissues around a sensory dendrite enhance the sensitivity of the receptor or make it more selective with respect to which type of stimulus it responds to. They include the following:

- **Tactile corpuscles—**receptors for light touch and texture. They are tall, ovoid to pear-shaped, and consist of two or three nerve fibers meandering upward through a mass of flattened Schwann cells. They occur in the dermal papillae of the skin and are limited to sensitive hairless areas such as the fingertips, palms, eyelids, lips, nipples, and parts of the genitals. Drag your fingernails lightly across your forearm and then across your palm. The difference in sensation you feel is due to the high density of tactile corpuscles in your palmar skin. Tactile corpuscles enable you to tell the difference between silk and sandpaper, for example, by light strokes of your fingertips.
- **End bulbs—**ovoid bodies composed of a connective tissue sheath around a sensory nerve fiber. They are structurally and functionally similar to tactile corpuscles but occur in mucous membranes of the lips and tongue, in the conjunctiva of the eye surface, and in the epineurium of large nerves.
- **Bulbous corpuscles—**receptors for constant heavy pressure, stretching of the skin, and joint movements. They are flattened, elongated capsules containing a few nerve fibers and are located in the dermis, subcutaneous tissue, and joint capsules.
- **Lamellar (pacinian[3]) corpuscles—**receptors for vibration and perhaps joint movements, deep pressure, and stretching of the skin. These are up to 1 or 2 mm long and look like a sliced onion in cross sections. A single sensory dendrite travels through the center of the corpuscle. The innermost onionlike layers around it are flattened Schwann cells, but the greater bulk of the corpuscle consists of concentric layers of fibroblasts with narrow fluid-filled spaces between them. Lamellar corpuscles occur in the periosteum of bone; in joint capsules; in the pancreas and some other viscera; and deep in the dermis, especially on the hands, feet, breasts, and genitals. When you stroke a surface with the fingertips, the friction ridges of the fingers create vibration that is detected by the lamellar corpuscles deeper in the skin, and this gives one a sense of the texture of the surface.
- **Muscle spindles—**stretch receptors in the muscles that trigger a variety of somatic reflexes. A muscle spindle has an elongated fibrous capsule, about 4 to 10 mm long, with a fusiform shape (thick in the middle and tapered at the ends). It contains 3 to 12 modified muscle fibers called **intrafusal fibers,** which lack striations and the ability to contract except at the ends. Different types of sensory nerve fibers twine around the middle of the intrafusal fibers or have flowerlike endings that contact the ends of the muscle fibers.
- **Tendon organs—**stretch receptors in tendons that protect against tendon or muscle injury by responding to excessive stretch and inhibiting muscle contraction. A tendon organ is about 0.5 mm long and consists of an encapsulated bundle of small, loose collagen fibers and one or more nerve fibers that penetrate the capsule. These nerve fibers end in flattened, leaflike processes between the collagen fibers.

The Receptive Field

The area supplied by a single sensory neuron is called its **receptive field.** Any information arriving at the CNS by way of that neuron is interpreted as coming from that field, no matter where in the field the stimulus is applied. Thus, the brain's ability to determine the precise location of a stimulus depends on the size of the field. Tactile (touch) receptors on your back, for example, have receptive fields as big as 7 cm in diameter. Any touch within that area stimulates the same neuron (fig. 17.2a), so it is difficult to tell precisely where the touch occurs. Being simultaneously touched at two points 1 or 2 cm apart within the same field can feel like a single touch. On the fingertips, by contrast, the receptive fields may be less than 1 mm in diameter—that is, there is a higher density of tactile nerve fibers. Two points of contact only 2 mm apart would thus be felt separately (fig. 17.2b). Therefore, we say that the fingertips have finer *two-point touch discrimination* than the skin on the back. This is crucial for such functions as feeling textures and manipulating small objects. The receptive field concept applies not only to touch, but also to other senses such as vision (the ability to see two points separately rather than blurred together into a single image).

Apply What You Know

Braille uses symbols composed of dots that are raised about 1 mm from the page surface and spaced about 2.5 mm apart, which a person scans with the fingertips. When a blind person reads braille, do you think he or she employs neurons with large receptive fields or small ones? Which type of sensory nerve ending do you think is most important in reading braille? Explain.

Somatosensory Projection Pathways

The pathways followed by sensory signals to their ultimate destinations in the CNS are called **projection pathways.** From the

---

[2] *peri* = around; *trich* = hair

[3] Filippo Pacini (1812–83), Italian anatomist


Neuron
(a) One large receptive field (arrow)
1
2
3
Neuron 3
Neuron 2
Neuron 1
(b) Three small receptive fields (arrows)

Figure 17.2 **Receptive Fields of Sensory Neurons.** (a) A neuron with a large receptive field, as found in the skin of the back. If the skin is touched in two nearby places within this field, the brain senses only one point of contact. (b) Neurons with small receptive fields, as found in the fingertips. Two nearby points of contact here are likely to stimulate different neurons and be felt as separate touches.

receptor to the final destination in the brain, most somatosensory signals travel by way of three neurons called the **first-, second-,** and **third-order neurons.** Their axons are called first- through third-order nerve fibers. The first-order (afferent) fibers for touch, pressure, and proprioception are large, myelinated, and fast; those for heat and cold are small, unmyelinated or lightly myelinated, and slower.

Somatosensory signals from the head, such as facial sensations, travel by way of several cranial nerves (especially V, the trigeminal nerve) to the pons and medulla oblongata. In the brainstem, the first-order fibers of these neurons synapse with second-order neurons that decussate and end in the contralateral thalamus. Third-order neurons then complete the route to the cerebrum. Proprioceptive signals are an exception, as the second-order fibers carry these signals to the cerebellum.

Below the head, the first-order fibers enter the posterior horn of the spinal cord. Signals ascend the spinal cord in the spinothalamic and other pathways detailed in chapter 14. These pathways decussate either at or near the point of entry into the spinal cord or in the brainstem, so the primary somatosensory cortex in each cerebral hemisphere receives signals from the contralateral side of the body.

Signals for proprioception below the head travel up the spinocerebellar tracts to the cerebellum. Signals from the thoracic and abdominal viscera travel to the medulla oblongata by way of sensory fibers in the vagus nerve (cranial nerve X). Recent research has shown that visceral pain signals also ascend the spinal cord in the gracile fasciculus.

Pain

Pain is a discomfort caused by tissue injury or noxious stimulation, and typically leads to evasive action. It makes us conscious of potentially injurious situations or actual tissue injuries, allowing us to avoid injury or, failing that, to favor an injured region so that it has a better chance to heal (see Deeper Insight 17.1).

Pain is not merely an effect of overstimulation of somatosensory receptors. It has its own specialized receptors (nociceptors) and purpose. Nociceptors are especially dense in the skin and mucous membranes and occur in virtually all organs, although not in the brain or liver. In some brain surgery, the patient must remain conscious and able to talk with the surgeon; such patients need only a local anesthetic. Nociceptors do occur in the meninges of the brain, however, and play an important role in headaches.

There are two types of nociceptors corresponding to different pain sensations. Myelinated pain fibers conduct at speeds of 12 to 30 m/s and produce the sensation of *fast (first) pain*—a feeling of sharp, localized, stabbing pain perceived at the time of injury. Unmyelinated pain fibers conduct at speeds of 0.5 to 2.0 m/s and produce the *slow (second) pain* that follows—a longer-lasting, dull, diffuse feeling. Pain from the skin, muscles, and joints is called *somatic pain,* and pain from the viscera is called *visceral pain.* The latter often results from stretch, chemical irritants, or *ischemia* (poor blood flow), and it is often accompanied by nausea.

It is notoriously difficult for clinicians to locate the origin of a patient's pain because pain travels by such diverse and complex

DEEPER INSIGHT 17.1

The Value of Pain

Although we generally regard pain as undesirable, we would be far worse off without it. Leprosy (Hansen[4] disease) provides a good example of the protective function of pain. The infection of nerves by leprosy bacteria abolishes the sense of pain from affected areas. People fail to notice minor injuries such as scrapes and splinter wounds. Their neglect of the wounds leads to serious secondary infections that damage the bone and other deeper tissues. About 25% of untreated victims suffer crippling losses of fingers or toes as a result. Diabetes mellitus is also notorious for causing nerve damage *(diabetic neuropathy)* and loss of pain, contributing to lesions that often turn gangrenous and cost people their limbs.

routes and the sensation can originate anywhere along the routes. Pain signals reach the brain by two main pathways, but there are multiple subroutes within each of them:

1. Pain signals from the head travel to the brainstem by way of four cranial nerves: mainly the trigeminal (V), but also the facial (VII), glossopharyngeal (IX), and vagus (X) nerves. Trigeminal fibers enter the pons and descend to synapses in the medulla. Pain fibers of the other three cranial nerves also end in the medulla. Second-order neurons arise here and ascend to the thalamus, which relays the message to the cerebral cortex. We will consider the relay from thalamus to cortex shortly.
2. Pain signals from the neck down travel by way of three of the ascending spinal cord tracts: the spinothalamic tract, spinoreticular tract, and gracile fasciculus. These pathways are described in chapter 14 and need not be repeated here (see table 14.1 and fig. 14.4, pp. 376–377). The spinothalamic tract is the most significant pain pathway and carries most of the somatic pain signals that ultimately reach the cerebral cortex, making us conscious of pain. The spinoreticular tract carries pain signals to the reticular formation of the brainstem, and these are ultimately relayed to the hypothalamus and limbic system. These pain signals activate visceral, emotional, and behavioral reactions to pain, such as nausea, fear, and some reflex responses. The gracile fasciculus has not been recognized as a pain pathway until recently. It carries signals to the thalamus for visceral pain, such as the pain of a stomachache or from passing a kidney stone. Figure 17.3 shows the spinothalamic and spinoreticular pain pathways.

When the thalamus receives pain signals from the foregoing sources, it relays most of them through third-order neurons to their final destinations in the postcentral gyrus of the cerebrum. Exactly what part of this gyrus receives the signals depends on where the pain originated; recall the concept of somatotopy and the sensory homunculus in chapter 15 (see fig. 15.18, p. 421). Most of this gyrus is somatosensory; that is, it receives signals for somatic pain and other senses. A region of the gyrus deep within the lateral sulcus of the brain, however, is a viscerosensory area, which receives the signals of visceral pain conveyed by the gracile fasciculus.



Figure 17.3 Projection Pathways for Pain. A first-order nerve fiber conducts a pain signal to the posterior horn of the spinal cord, a second-order fiber conducts it to the thalamus, and a third-order fiber conducts it to the cerebral cortex. Signals from the spinothalamic tract pass through the thalamus. Signals from the spinoreticular tract bypass the thalamus on the way to the sensory cortex.

- *What is the name of the gyrus that contains the primary somatosensory cortex? To which of the five lobes of the cerebrum does this gyrus belong?*

Pain in the viscera is often mistakenly thought to come from the skin or other superficial sites—for example, the pain of a heart attack is felt “radiating” along the left shoulder and medial side of the arm (fig. 17.4a). This phenomenon, called **referred pain,** results from the convergence of neural pathways in the CNS. In the case of cardiac pain, for example, spinal cord segments T1 to T5 receive input from the heart as well as the chest and arm. Pain fibers from the heart and skin in this region converge on the same spinal interneurons, then follow the same pathway from there to the thalamus and cerebral cortex. The brain cannot distinguish which source the arriving signals are coming from. It acts as if it assumes that signals arriving by this path are most likely coming from the skin, since the skin has more pain receptors than the heart and suffers injury more often. Knowledge of the origins of referred pain is essential to the skillful diagnosis of organ dysfunctions (fig. 17.4b).

---

[4] Gerhard H. A. Hansen (1841–1912), Norwegian physician



Figure 17.4 **Referred Pain.** (a) The pain of a heart attack is often felt "radiating" down the left arm because the brain cannot distinguish whether the pain signals arise from the heart or from that area of skin. (b) Pain from the internal organs may be felt in specific areas of the skin. The pattern for women differs in some details from the one for men.

One of the most remarkable phenomena in the sense of pain is that mortally wounded people, such as soldiers in combat, often report that they feel little or no pain. This occurs because of a mechanism called the *spinal gating* of pain, in which pain signals from peripheral nerves are blocked in the spinal cord and never reach the brain.

The reticular formation gives rise to nerve fibers called **descending analgesic**[5] (pain-relieving) **fibers.** They travel down the reticulospinal tracts and synapse in the posterior horn of the spinal cord with the axons of the first-order pain neurons. Here, they secrete pain-relieving neurotransmitters called *enkephalins* and *dynorphins,* which inhibit the first-order pain neurons from releasing their own neurotransmitter. Pain signals are thus stopped at the first spinal synapse and do not reach the brain, so one feels less pain or none at all.

Before You Go On

Answer the following questions to test your understanding of the preceding section.

1. Distinguish between general and special senses.
2. Three schemes of receptor classification were presented in this section. In each scheme, how would you classify the receptors for a full bladder? How would you classify taste receptors?
3. What stimulus modalities are detected by free nerve endings?
4. Name any four encapsulated nerve endings and identify the stimulus modalities for which they are specialized.
5. Where do most second-order somatosensory neurons synapse with third-order neurons?
6. How do the spinothalamic tract and reticulospinal tract differ in their roles in the perception of pain?

17.2 The Chemical Senses

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the anatomy of taste and smell receptors; and
b. describe the projection pathways for these two senses.

Taste and smell are the chemical senses. In both cases, environmental chemicals bind to receptor cells and trigger nerve signals in certain cranial nerves. Other chemoreceptors, not discussed in this section, are located in the brain and blood vessels and monitor the chemistry of cerebrospinal fluid and blood.

Taste

Gustation, the sense of taste, begins with the chemical stimulation of sensory cells clustered in about 4,000 **taste buds.** Most of these are on the tongue, but some occur inside the cheeks and on the soft palate, pharynx, and epiglottis, especially in infants and children. The visible bumps on the tongue are not taste buds but various types of **lingual papillae** (fig. 17.5a):

1. **Filiform**[6] **papillae** are tiny spikes without taste buds (see fig. 17.5b). They are responsible for the rough feel of a cat's tongue and are important to many mammals for grooming the fur. They are the most abundant papillae on the human tongue, but they are small and play no gustatory role. They are innervated, however, and serve in one's sense of the texture of food, called *mouthfeel*.

---

[5] *an* = without; *alges* = pain

[6] *fili* = thread; *form* = shaped



Figure 17.5 **Gustatory (Taste) Receptors.** (a) Superior surface of the tongue and locations of its papillae. (b) Detail of the vallate papillae. (c) Taste buds on the walls of two adjacent foliate papillae. (d) Structure of a taste bud.

- *What cell(s) in part (d) would function to replace a taste cell that dies?* AP|R

Epiglottis
Lingual tonsil
Palatine tonsil
Vallate papillae
Foliate papillae
Fungiform papillae
Vallate papillae
Filiform papillae
Taste buds

(a) Tongue

(b) Vallate papillae



Foliate papilla
Taste pore
Taste bud
100 µm
Synaptic vesicles
Sensory nerve fibers
Basal cell
Supporting cell
Taste cell
Taste pore
Taste hairs
Tongue epithelium

© Ed Reschke/Getty Images

(c) Foliate papillae

(d) Taste bud

2. **Foliate**[7] **papillae** are also weakly developed in humans. They form parallel ridges on the sides of the tongue about two-thirds of the way back from the tip, adjacent to the molar and premolar teeth, where most chewing occurs and most flavor chemicals are released from the food. Most of their taste buds degenerate by the age of 2 or 3 years. Perhaps this partially explains why children so often reject foods that are tolerated or enjoyed by adults.
3. **Fungiform**[8] (FUN-jih-form) **papillae** are shaped somewhat like mushrooms. Each one has about three taste buds, located mainly on the apex. These papillae are widely distributed but are especially concentrated at the tip and sides of the tongue. Like filiform papillae, these also respond to food texture.
4. **Vallate**[9] **(circumvallate) papillae** are large papillae arranged in a V at the rear of the tongue. Each is surrounded by a deep circular trench. There are only 7 to 12 vallate papillae, but they contain up to half of all taste buds—around 250 each, located on the wall of the papilla facing the trench (fig. 17.5b).

Regardless of location, all taste buds look alike (fig. 17.5c, d). They are lemon-shaped groups of 50 to 150 cells of three kinds—*taste cells, supporting cells,* and *basal cells.* **Taste (gustatory) cells** are more or less banana-shaped and have a tuft of apical microvilli called **taste hairs,** which serve as receptor surfaces for taste molecules. The hairs project into a pit called a **taste pore** on the epithelial surface of the tongue. Taste cells are epithelial cells, not neurons, but at their bases, they synapse with sensory nerve fibers and have synaptic vesicles for the release of neurotransmitters. A taste cell lives 7 to 10 days. **Basal cells** are stem cells that multiply and replace taste cells that have died, but they also synapse with sensory nerve fibers and may play some role in the processing of sensory information before signals are conducted to the brain. **Supporting cells** resemble taste cells but have no taste hairs, synaptic vesicles, or sensory role.

---

[7] *foli* = leaf; *ate* = like

[8] *fungi* = mushroom; *form* = shaped

[9] *vall* = wall; *ate* = like, possessing

There are five *primary taste* sensations: sweet, salty, sour, bitter, and umami. Umami, the most recently discovered primary taste, is a meaty taste stimulated by certain amino acids, glutamate and aspartate. Pronounced "ooh-mommy," the word is Japanese and loosely means "delicious."

All of the primary taste sensations can be detected throughout the tongue. It was once popular to show "taste maps" of the tongue indicating where these modalities were localized, but sensory physiologists long ago discarded this concept because the tongue has no regional specializations of any significance to the brain's interpretation of modality.

The many flavors we perceive are not simply a mixture of these five primary tastes but are also influenced by food texture, aroma, temperature, and appearance, as well as one's state of mind, among other things. Many flavors depend on smell; without their aromas, cinnamon merely has a faintly sweet taste and coffee and peppermint are bitter. Some flavors such as pepper are due to stimulation of free endings of the trigeminal nerve. A branch of the trigeminal called the *lingual nerve* innervates filiform and fungiform papillae and carries signals for food texture.

The facial nerve (cranial nerve VII) collects sensory information from taste buds of the anterior two-thirds of the tongue; the glossopharyngeal nerve (IX) from the posterior one-third; and the vagus nerve (X) from taste buds of the palate, pharynx, and epiglottis. All taste fibers project to a site in the medulla oblongata called the *solitary nucleus.* Second-order neurons arise here and relay the signals to two destinations: (1) nuclei in the hypothalamus and amygdala that activate autonomic reflexes such as salivation, gagging, and vomiting; and (2) the thalamus, which relays signals to the insula and postcentral gyrus of the cerebrum (fig. 17.6), where we become conscious of the taste. Processed signals are further relayed to the orbitofrontal cortex (see fig. 15.15, p. 418) where they are integrated with signals from the nose and eyes and we form an overall impression of the flavor and palatability of food.

Smell

Olfaction, the sense of smell, is a response to airborne chemicals. These are detected by receptor cells in a patch of epithelium called the **olfactory mucosa,** on the roof of the nasal cavity (fig. 17.7). This epithelium covers about 5 cm^2 of the superior concha and nasal septum; the rest of the nasal cavity is lined by a nonsensory *respiratory mucosa.* Their location places the olfactory cells close to the brain, but it is poorly ventilated; forcible sniffing is often needed to identify an odor or locate its source. Nevertheless, the sense of smell is highly sensitive. We can detect extremely low concentrations of odor molecules, and most people can distinguish 2,000 to 4,000 different odors; some can distinguish as many as 10,000. On average, women are more sensitive to odors than men are, and they are more sensitive to some odors near the time of ovulation than during other phases of the menstrual cycle.



Figure 17.6 **Gustatory Projection Pathway to the Cerebral Cortex.** Other pathways not shown carry taste signals from the solitary nucleus to the hypothalamus and amygdala.

The olfactory mucosa has 10 to 20 million **olfactory neurons** as well as epithelial supporting cells and basal cells. It has a yellowish tint due to lipofuscin in the supporting cells. Note that olfactory cells are neurons whereas taste cells are not. Olfactory cells are the only neurons in the body directly exposed to the external environment. Apparently this is hard on them, because they have a life span of only 60 days. Unlike most neurons, however, they are replaceable. The basal stem cells continually divide and differentiate into new olfactory cells.

An olfactory cell is shaped a little like a bowling pin. Its widest part, the soma, contains the nucleus. The neck and head of the cell are a modified dendrite with a swollen tip bearing 10 to 20 immobile cilia called **olfactory hairs.** These cilia bear the binding sites for odor molecules, and lie in a tangled mass embedded in a thin layer of mucus on the epithelial surface. The basal end of each cell tapers to become an axon. These axons collect into small fascicles that leave the nasal cavity through pores *(olfactory foramina)* in the cribriform plate of the ethmoid bone. Collectively, the fascicles are regarded as cranial nerve I (the olfactory nerve).

When olfactory fibers pass through the roof of the nose, they enter a pair of **olfactory bulbs** beneath the frontal lobes of the brain (see fig. 15.23, p. 427). Here, they synapse with the dendrites of two types of neurons higher in the bulb, called *mitral cells* and *tufted cells.* Olfactory axons reach up, and mitral and tufted cell dendrites reach down, to meet each other in spherical clusters called *glomeruli* (fig. 17.7b). All olfactory fibers leading to any one glomerulus come from cells with the same receptor type; thus, each glomerulus is dedicated to a particular odor. Higher brain centers interpret complex odors such as chocolate, perfume, wine, or coffee by decoding signals from a combination of odor-specific glomeruli. This is similar to the way our visual system decodes all the colors of the spectrum using input from just three color-specific receptor cells of the eye.

The tufted and mitral cells carry the output from the glomeruli. Their axons form bundles called **olfactory tracts,** which course posteriorly along the underside of the frontal lobes. Most fibers of the olfactory tracts end in various neighboring regions of the inferior surface of the temporal lobe (fig. 17.8); collectively, we can regard all these regions as the **primary olfactory cortex.** It is noteworthy that olfactory signals reach the cerebral cortex directly, without first passing through the thalamus; this is not true of any of our other senses. Even in olfaction, however, some signals from the primary olfactory cortex continue to a relay in the thalamus on their way to olfactory association areas elsewhere.

From the primary olfactory cortex, signals travel to several other secondary destinations in the cerebrum and brainstem. Two important cerebral destinations are the insula and orbitofrontal cortex. The orbitofrontal cortex, which lies on the floor of the frontal lobe just above the eyes (see fig. 15.15, p. 418), seems to be the site where we identify and discriminate among odors. It receives inputs for both taste and smell and integrates these into our overall perception of flavor. Other secondary destinations for olfactory signals include the hippocampus, amygdala, and hypothalamus.


Olfactory tract
Olfactory bulb
Olfactory nerve fascicle
Olfactory mucosa (reflected)
(a)
Olfactory bulb
Granule cell
Olfactory tract
Mitral cell
Tufted cell
Glomerulus
Olfactory nerve fascicle
Cribriform plate of ethmoid bone
Basal cell
Supporting cells
Olfactory cell
Olfactory gland
Olfactory hairs
Mucus
Odor molecules
Airflow
(b)
Axon
Neurosoma
Dendrite
Olfactory hairs
(c)

Figure 17.7 Olfactory (Smell) Receptors. (a) Location of the olfactory mucosa in the nasal cavity, and the olfactory bulb of the brain. (b) The olfactory mucosa and conduction pathways to the olfactory tract of the brain. (c) Detail of an olfactory cell, a sensory neuron of the mucosa. APR



Figure 17.8 Olfactory Projection Pathways in the Brain.

Considering the roles of these brain areas, it is not surprising that the odor of certain foods, a perfume, a hospital, or decaying flesh can evoke strong memories, emotional responses, and visceral reactions such as sneezing or coughing, the secretion of saliva and stomach acid, or vomiting.

Most areas of the olfactory cortex also send fibers back to the olfactory bulbs by way of neurons called *granule cells.* Granule cells inhibit the mitral and tufted cells. An effect of this feedback is that odors can change in quality and significance under different conditions. Food may smell more appetizing when you are hungry, for example, than when you have just eaten or when you are ill.

Apply What You Know

Which taste sensations could be lost after damage to (1) the facial nerve and (2) the glossopharyngeal nerve? Why? A fracture of which cranial bone would most likely eliminate the sense of smell? Why?

Before You Go On

Answer the following questions to test your understanding of the preceding section.

7. What is the difference between a lingual papilla and a taste bud? Which is visible to the naked eye?
8. Which cranial nerves carry gustatory impulses to the brain?
9. What part of an olfactory cell bears the binding sites for odor molecules?
10. What region of the brain receives subconscious input from the olfactory cells? What region receives conscious input?

17.3 The Ear

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the gross and microscopic anatomy of the ear;
b. briefly explain how the ear converts vibrations to nerve impulses and discriminates between sounds of different intensity and pitch;
c. explain how the anatomy of the vestibular apparatus relates to our ability to interpret the body's position and movements; and
d. describe the pathways taken by auditory and vestibular signals to the brain.

Hearing is a response to vibrating air molecules, and *equilibrium* is the sense of motion and balance. These senses reside in the inner ear, a maze of fluid-filled passages and sensory cells encased in the temporal bone.

Anatomy of the Ear

The ear has three sections called the *outer, middle,* and *inner ear.* The first two are concerned only with conducting sound to the inner ear, where vibration is converted to nerve signals.

Outer Ear

The **outer (external) ear** is essentially a funnel for conducting airborne vibrations to the tympanic membrane (eardrum). It begins with the fleshy **auricle (pinna)** on the side of the head, shaped and supported by elastic cartilage except for the earlobe, which is mostly adipose tissue. The auricle has a predictable arrangement of whorls and recesses that direct sound into the auditory canal (fig. 17.9).



Figure 17.9 The Auricle (Pinna) of the Ear.

© McGraw-Hill Education/Joe De Grandis, photographer



Figure 17.10 Internal Anatomy of the Ear. APR

The **auditory canal,** or **external acoustic meatus** (me-AY-tus), is the passage through the temporal bone. It follows a slightly S-shaped course for about 3 cm to the tympanic membrane (fig. 17.10). It is lined with skin and supported by fibrocartilage at its opening and by the temporal bone for the rest of its length. The outer end of the canal is protected by stiff **guard hairs.** The canal has ceruminous and sebaceous glands whose secretions mix with dead skin cells and form **cerumen** (earwax). Cerumen is sticky and coats the guard hairs, making them more effective in blocking foreign particles from entering the auditory canal. Its stickiness may also be a deterrent to insects, ticks, or other pests. In addition, it contains lysozyme and has a low pH, both of which inhibit bacterial growth; it waterproofs the canal and protects its skin and the tympanic membrane from absorbing water; and it keeps the tympanic membrane pliable. Cerumen normally dries up and falls from the canal, but sometimes it becomes impacted and interferes with hearing.

Middle Ear

The **middle ear** is located in the **tympanic cavity** of the temporal bone. A space only 2 to 3 mm wide between the outer and inner ears, the tympanic cavity houses the three smallest bones and two smallest skeletal muscles of the body.

The middle ear begins with the **tympanic**[10] **membrane,** which closes the inner end of the auditory canal and separates it from the middle ear. The membrane is about 1 cm in diameter and slightly concave on its outer surface. It is suspended in a ring-shaped groove in the temporal bone and vibrates freely in response to sound. It is innervated by sensory branches of the vagus and trigeminal nerves and is highly sensitive to pain.

Posteriorly, the tympanic cavity is continuous with the mastoidal air cells in the mastoid process. The cavity is filled with air that enters by way of the **auditory** (**pharyngotympanic** or **eustachian**[11]) **tube,** a passage to the nasopharynx. (Be careful not to confuse *auditory tube* with *auditory canal.*) The auditory tube is normally flattened and closed, but swallowing or yawning opens it and allows air to enter or leave the tympanic cavity. This equalizes air pressure on both sides of the tympanic membrane, allowing it to vibrate freely. Excessive pressure on one side or the other muffles the sense of hearing. Unfortunately, the auditory tube also allows throat infections to spread to the middle ear (see Deeper Insight 17.2).

DEEPER INSIGHT 17.2

Middle-Ear Infection

Otitis[12] *media* (middle-ear infection) is especially common in children because their auditory tubes are relatively short and horizontal. Upper respiratory infections spread easily from the throat to the tympanic cavity and mastoidal air cells. Fluid accumulates in the cavity and causes pressure, pain, and impaired hearing. If otitis media goes untreated, it may spread from the mastoidal air cells and cause meningitis, a potentially deadly infection of the meninges. Chronic otitis media can also cause fusion of the middle-ear bones, preventing them from vibrating freely and thus causing hearing loss. It is sometimes necessary to drain fluid from the tympanic cavity by lancing the tympanic membrane and inserting a tiny drainage tube—a procedure called *tympanostomy.*[13] The tube, which is eventually discharged spontaneously by the ear, relieves the pressure and permits the infection to heal.

---

[10] *tympan* = drum

[11] Bartholomeo Eustachio (1520–74), Italian anatomist

[12] *ot* = ear; *itis* = inflammation

[13] *tympano* = drum; *stomy* = making an opening

The three middle-ear bones are called the **auditory ossicles**[14] (fig. 17.10). Progressing inward, the first is the **malleus,**[15] which has an elongated *handle* attached to the inner surface of the tympanic membrane; a *head,* which is suspended by a ligament from the wall of the tympanic cavity; and a *short process,* which articulates with the next ossicle. The second bone is the **incus.**[16] It has a roughly triangular *body* with an articular surface where it meets the malleus; a *short limb* (not illustrated) suspended by a ligament from the wall of the tympanic cavity; and a *long limb* that articulates with the third ossicle, the stapes.

The **stapes**[17] (STAY-peez) has a *head* that articulates with the incus, an arch, and an elliptical *base (footplate),* giving it an overall shape like a stirrup. The base is held by a ringlike ligament in an opening called the **oval window,** where the inner ear begins.

The muscles of the middle ear are the stapedius and tensor tympani. The **stapedius** (stay-PEE-dee-us) arises from the posterior wall of the cavity and inserts on the stapes. The **tensor tympani** (TEN-sor TIM-pan-eye) arises from the wall of the auditory tube, travels alongside it, and inserts on the malleus. In response to loud noises, these muscles contract and dampen the vibration of the ossicles, thus protecting the delicate sensory cells of the inner ear; this is called the *tympanic reflex.* The sensory cells can nevertheless be irreversibly damaged by sudden loud noises such as gunshots, and by sustained loud noise such as factory noise and loud music (see Deeper Insight 17.3).

Inner Ear

The **inner (internal) ear** is housed in a maze of passages called the **bony (osseous) labyrinth** in the petrous part of the temporal bone (see p. 161). The bony labyrinth contains a complex of fluid-filled chambers and fleshy tubes called the **membranous labyrinth** (fig. 17.11). The fluid in this labyrinth, similar to

---

[14] *oss* = bone; *icle* = little
[15] *malleus* = hammer, mallet
[16] *incus* = anvil
[17] *stapes* = stirrup


Temporal bone
(a)
Vestibule:
Saccule
Utricle
Ampullae
Semicircular ducts:
Anterior
Lateral
Posterior
Cochlea
Spiral ganglion of cochlea
Cochlear nerve
Facial nerve
Vestibular nerve
Vestibular ganglion
Endolymphatic sac
(b)
Temporal bone
Semicircular ducts:
Anterior
Posterior
Lateral
Semicircular canal
Ampulla
Tympanic membrane
Endolymphatic sac
Dura mater
Scala vestibuli
Scala tympani
Cochlear duct
Vestibule:
Saccule
Utricle
Stapes in oval window
Secondary tympanic membrane in round window
(c)

Figure 17.11 Anatomy of the Membranous Labyrinth. (a) Position and orientation within the petrous part of the temporal bone. (b) Structure of the membranous labyrinth and its nerves. (c) Relationship of the perilymph (green) and endolymph (blue) to the membranous labyrinth. AP|R

intracellular fluid, is called **endolymph.** Between the membranous labyrinth and bone is another liquid, similar to cerebrospinal fluid, called **perilymph.** The membranous labyrinth within the bony labyrinth is a tube-within-a-tube structure, somewhat like a bicycle inner tube within a tire.

Proceeding inward from the oval window, the first part of the bony labyrinth is an ovoid chamber called the **vestibule,** containing two organs of balance that we will consider later—the *utricle* and *saccule.* Arising from the vestibule are three bony **semicircular canals,** containing fleshy loops called the *semicircular ducts,* which detect rotation of the head. Also arising from the vestibule is a spiral tube called the **cochlea**[18] (COC-lee-uh or COKE-lee-uh), named for its snail-like shape. This contains the organ of hearing, called the **cochlear duct,** and is therefore the focus of our immediate interest.

In other vertebrates, the cochlea is straight or slightly curved. In most mammals, however, it assumes a spiral form that allows a longer cochlea to fit within a compact space of the temporal bone. In humans, it is about 9 mm wide at the base and 5 mm high. The apex points anterolaterally (fig. 17.11a). The cochlea winds for about two and a half coils around a screwlike axis of spongy bone called the **modiolus**[19] (mo-DY-oh-lus). The "threads of the screw" form a spiral platform that supports the fleshy cochlear duct.

The cochlear duct contains structures that convert sound waves to nerve signals. A vertical section cuts through the cochlea about five times (fig. 17.12a). A single cross section through it looks like figure 17.12b. It is important to realize that the structures seen in cross section actually have the form of spiral strips winding around the modiolus from base to apex. In cross section, the cochlear duct appears as a triangular space bounded by a thick **basilar membrane** below and a thin **vestibular membrane** above. Above the vestibular membrane is a space called the **scala**[20] **vestibuli** (SCAY-la vess-TIB-you-lye), and below the basilar membrane is

---

[18] *cochlea* = snail

[19] *modiolus* = hub

[20] *scala* = staircase


Oval window
Vestibular membrane
Cochlear duct (scala media)
Cochlear nerve
(a)
Spiral ganglion
Scala vestibuli (with perilymph)
Vestibular membrane
Cochlear duct (with endolymph)
Scala tympani (with perilymph)
Tectorial membrane
Spiral organ
Basilar membrane
(b)
Tectorial membrane
Hairs (stereocilia)
Outer hair cells
Supporting cells
Basilar membrane
Inner hair cell
Fibers of cochlear nerve
(c)

Figure 17.12 Anatomy of the Cochlea. (a) Vertical section. The apex of the cochlea faces downward and anterolaterally in anatomical position. (b) Detail of one section through the cochlea. (c) Detail of the spiral organ. APR

a space called the **scala tympani** (TIM-pan-eye). These are filled with perilymph and communicate with each other through a narrow channel at the apex of the cochlea. The scala vestibuli begins near the oval window and spirals to the apex; from there, the scala tympani spirals back down to the base and ends at the **round window** (fig. 17.11). The round window is covered by a membrane called the *secondary tympanic membrane.*

Within the cochlear duct, supported on the basilar membrane, is the **spiral organ,** also called the *acoustic organ* or *organ of Corti*[21] (COR-tee)—a thick epithelium with associated structures (the boxed area in figure 17.12b). This is the device that generates auditory nerve signals, so we must pay particular attention to its structural details.

The spiral organ has an epithelium composed of **hair cells** and supporting cells. Hair cells are named for the long, stiff microvilli called **stereocilia**[22] on their apical surfaces (see photo on p. 460). (Stereocilia should not be confused with true cilia. They do not have an axoneme of microtubules as seen in cilia, and they do not move by themselves.) Resting on top of the stereocilia is a gelatinous **tectorial**[23] **membrane,** which helps to stimulate the hair cells when the cochlea responds to sound waves.

The spiral organ has four rows of hair cells (fig. 17.13). About 3,500 of these, called **inner hair cells (IHCs),** are arranged in a row by themselves on the medial side of the basilar membrane (facing the modiolus). Each IHC has a cluster of 50 to 60 stereocilia, arranged in order from short to tall. Another 20,000 **outer hair cells (OHCs)** are neatly arranged in three rows across from the inner hair cells. Each OHC has about 100 stereocilia arranged in a V, with their tips embedded in the tectorial membrane. All that we hear comes from the IHCs, which supply 90% to 95% of the sensory fibers of the cochlear nerve. The function of the OHCs is to adjust the response of the cochlea to different frequencies and enable the IHCs to work with greater precision.

DEEPER INSIGHT 17.3

Deafness

Deafness means any hearing loss, from mild and temporary to complete and irreversible. *Conduction deafness* is a type that results from the impaired transmission of vibrations to the inner ear. It can result from a damaged tympanic membrane, otitis media, or blockage of the auditory canal. Another cause is *otosclerosis,*[24] fusion of the auditory ossicles to each other or fusion of the stapes to the oval window, preventing the bones from vibrating freely. *Sensorineural (nerve) deafness* results from the death of hair cells or any of the nervous elements concerned with hearing. It is a common occupational disease of musicians, construction workers, and others who work in noisy environments, and is part of the price many will pay for loud concerts, car stereos, and personal stereos. Deafness leads some people to develop delusions of being talked about, disparaged, or cheated. Beethoven said his deafness drove him nearly to suicide.



© Quest/SPL/Science Source

Figure 17.13 Apical Surfaces of the Cochlear Hair Cells (SEM). All signals that we hear come from the inner hair cells on the right.

Hair cells are not neurons, but synapse with nerve fibers at their base. Inner hair cells synapse with the dendrites of sensory neurons only. Outer hair cells synapse with both sensory dendrites, which conduct signals to the brain, and axons that carry motor signals from the brainstem to the hair cells. The sensory neurons of the cochlea are bipolar neurons whose somas form a **spiral ganglion** coiled around the modiolus. The dendrites of these cells lead from the spiral organ to the ganglion; their axons pass from the ganglion down the core of the cochlea, then form the cochlear part of cranial nerve VIII, the vestibulocochlear nerve. This nerve carries auditory signals to the brainstem.

Auditory Function

To make functional sense of this anatomy, we will examine the essential aspects of auditory function. Figure 17.14 is a mechanical model that presents some of the basic mechanisms in simple form. When sound waves vibrate the tympanic membrane, the three auditory ossicles transfer these vibrations to the inner ear. The base of the stapes moves the fluid in the inner ear, and fluid movements cause the basilar membrane to vibrate up and down. As it does so, the hair cells on the basilar membrane are thrust up and down, while the tectorial membrane immediately above them remains relatively still. Each upward movement of the hair cells crowds the stereocilia against the tectorial membrane, forcing them to rock back and forth. This rocking motion opens membrane channels that admit bursts of potassium ions into the hair cells, exciting the

---

[21] Alfonso Corti (1822–88), Italian anatomist

[22] *stereo* = solid

[23] *tect* = roof

[24] *oto* = ear; *scler* = hardening; *osis* = process, condition



Figure 17.14 **Mechanical Model of Auditory Function.** Each inward movement of the tympanic membrane pushes inward on the auditory ossicles of the middle ear and fluid of the inner ear. The fluid pushes down on the basilar membrane, and pressure is relieved by an outward bulge of the secondary tympanic membrane. Thus the basilar membrane vibrates up and down in synchrony with the vibrations of the tympanic membrane.

- *Why would high air pressure in the middle ear reduce the movements of the basilar membrane of the inner ear?*

cells. An excited hair cell releases a neurotransmitter from synaptic vesicles in its base, and the neurotransmitter excites the adjacent sensory nerve fiber. This creates a nerve signal, which we will trace in the next section.

The cochlea must generate signals that the brain can distinguish as differences in loudness and pitch. Loud sounds produce relatively vigorous vibrations of the basilar membrane, causing rapid firing of the cochlear nerve fibers. The nerve fibers fire more slowly in response to softer sounds. High- and low-pitched sounds vibrate different regions of the basilar membrane. High-pitched sounds especially stimulate hair cells near the base of the cochlea, and low-pitched sounds stimulate those near the tip. Thus, the brain distinguishes loudness and pitch from how fast the cochlear nerve fibers are firing and what regions of the spiral organ are generating the strongest signals.

In order to tune the cochlea and sharpen its frequency discrimination, the brainstem sends motor signals back through the cochlear nerve to the outer hair cells (OHCs). The OHCs are anchored to the basilar membrane below and anchored to the tectorial membrane through their stereocilia above. They contract in response to signals from the brain, tugging on the basilar and tectorial membranes and thus suppressing the vibration of specific regions of the basilar membrane. This enhances the ability of the brain to tell one sound frequency from another—an ability that is important for such purposes as distinguishing the words in someone else's speech.

The Auditory Projection Pathway

Sensory nerve fibers from the cochlea form the **cochlear nerve.** This joins the *vestibular nerve* (see fig. 17.11b) and the two together become the *vestibulocochlear nerve* (cranial nerve VIII). The vestibulocochlear nerve exits the internal acoustic meatus of the temporal bone, thus leaving the inner ear and entering the cranial cavity. It ends a short distance later in the *cochlear nucleus* of the medulla oblongata.

Cochlear nerve fibers synapse here with second-order neurons that lead to the nearby *superior olivary nucleus* of the pons (fig. 17.15). The superior olivary nucleus has multiple connections and functions:

- It sends signals back to the cochlea by way of cranial nerve VIII, stimulating the outer hair cells for the purpose of cochlear tuning.
- It sends signals by way of cranial nerves V_3 and VII to the tensor tympani and stapedius muscles, respectively, which are responsible for the protective tympanic reflex.
- It plays a role in *binaural*[25] *hearing*—comparing signals from the right and left ears to identify the direction from which a sound is coming.
- It issues fibers up the brainstem to the inferior colliculi of the midbrain.

The inferior colliculi aid in binaural hearing and issue fibers to the thalamus. In the thalamus, these, in turn, synapse with neurons that continue to the primary auditory cortex in the superior part of each temporal lobe. The temporal lobe is the site of conscious perception of sound; it completes the information processing essential to binaural hearing. The interpretation of sound in relation to memory—for example, the ability to recognize what a sound is—occurs in the auditory association area bordering the primary auditory cortex (see fig. 15.17, p. 420).

Extensive connections exist between the right and left nuclei of hearing throughout the brainstem, allowing for comparison of the inputs from the right and left ears and the localization of sounds in space. Thus, unlike the somatosensory cortex, the auditory cortex on each side of the brain receives signals from both ears. Because of this extensive decussation, damage to the right or left auditory cortex does not cause a unilateral loss of hearing.

The Vestibular Apparatus

The original function of the ear in vertebrate history was not hearing, but **equilibrium**—coordination, balance, and orientation in three-dimensional space. Only later did vertebrates evolve the cochlea, outer- and middle-ear structures, and auditory function of the ear. In humans, the receptors for equilibrium constitute the **vestibular apparatus,** which consists of three **semicircular ducts** and two chambers—an anterior **saccule**[26] (SAC-yule) and a posterior **utricle**[27] (YOU-trih-cul) (see fig. 17.11).

The sense of equilibrium is divided into **static equilibrium,** the perception of the orientation of the head when the body is stationary, and **dynamic equilibrium,** the perception of motion or acceleration. There are two kinds of acceleration: *linear acceleration,* a change in velocity in a straight line, as when riding in a car or elevator; and *angular acceleration,* a change in the rate of rotation, as when turning one's head. The saccule and utricle are responsible for static equilibrium and the sense of linear acceleration; the semicircular ducts detect only angular acceleration.

---

[25] *bin* = two; *aur* = ears
[26] *saccule* = little sac
[27] *utricle* = little bag


Primary auditory cortex
Temporal lobe of cerebrum
Medial geniculate nucleus of thalamus
Auditory reflex (head turning)
Neck muscles
Inferior colliculus of midbrain
Superior olivary nucleus of pons
Cranial nerves V_3 and VII
Tensor tympani and stapedius muscles
Cochlea
Cochlear tuning
Tympanic reflex
Cochlear nuclei of pons
Cranial nerve VIII
(a)
Thalamus
Primary auditory cortex
Inferior colliculus
Superior olivary nucleus
Cochlear nucleus
Cranial nerve VIII
Medulla oblongata
Cochlea
(b)

Figure 17.15 **Auditory Pathways in the Brain.** (a) Schematic. (b) Brainstem and frontal section of the cerebrum, showing the locations of auditory processing centers. (Cranial nerve V_3 = trigeminal nerve, mandibular division; CN VII = facial nerve; CN VIII = vestibulocochlear nerve)

The Saccule and Utricle

The saccule and utricle each have a 2 by 3 mm patch of hair cells and supporting cells called a *macula.*[28] The **macula sacculi** lies nearly vertically on the wall of the saccule, and the **macula utriculi** lies nearly horizontally on the floor of the utricle (fig. 17.16a). Each hair cell of a macula has 40 to 70 stereocilia and one true cilium called a **kinocilium.**[29] The tips of the stereocilia and kinocilium are embedded in a gelatinous **otolithic membrane.** This membrane is weighted with granules called **otoliths,**[30] composed of calcium carbonate and protein (fig. 17.16b). By adding to the density and inertia of the membrane, the otoliths enhance the sense of gravity and motion.

---

[28] *macula* = spot

[29] *kino* = moving

[30] *oto* = ear; *lith* = stone


Base of cochlea
Cochlear nerve
Utricle (cut open)
Saccule (cut open)
Semicircular ducts
(a)
Vestibular nerve
Macula sacculi
Macula utriculi
Otolithic membrane
Otoliths
Supporting cell
Hair cell
Vestibular nerve
(b)
Gravitational force
Stereocilia of hair cells bend
Otolithic membrane sags
(c)

Figure 17.16 **The Saccule and Utricle.** (a) Locations of the macula sacculi and macula utriculi. (b) Structure of a macula (cutaway view). (c) Action of the otolithic membrane on the hair cells when the head is tilted.

- *Why would the macula sacculi respond more strongly than the macula utriculi to a ride in an elevator?*

Figure 17.16c shows how the macula utriculi detects tilt of the head. With the head erect, the otolithic membrane bears directly down on the hair cells and stimulation is minimal. When the head is tilted, however, the heavy otolithic membrane sags and bends the stereocilia, stimulating the hair cells. Any orientation of the head causes a combination of stimulation to the utricles and saccules of the two ears. The brain interprets head orientation by comparing these inputs to each other and to other input from the eyes and stretch receptors in the neck, thereby detecting whether only the head is tilted or the entire body is tipping. The macula sacculi works similarly except that its vertical orientation makes it more responsive to up-and-down movements of the body—for example, when you stand up or jump down from a height.

The inertia of the otolithic membranes is especially important in detecting linear acceleration. Suppose you are sitting in a car at a stoplight and then begin to move. The heavy otolithic membrane of the macula utriculi briefly lags behind the rest of the tissues, bends the stereocilia backward, and stimulates the cells. When you stop at the next red light, the macula stops but the otolithic membrane keeps on going for a moment, bending the stereocilia forward. The hair cells convert this pattern of stimulation to nerve signals, and the brain is thus advised of changes in your linear velocity.

If you are standing in an elevator and it begins to move up, the otolithic membrane of the vertical macula sacculi lags behind briefly and pulls down on the hair cells. When the elevator stops, the otolithic membrane keeps on going for a moment and bends the hairs upward. The macula sacculi thus detects vertical acceleration. These sensations are important in such ordinary actions as sitting down, standing up, and falling, and as one's head bobs up and down during walking and running.


Ampullae
(cut open)
Semicircular ducts:
Anterior
Lateral
Posterior
(a)
Crista ampullaris
Cupula
Endolymph
Hair cells
Supporting cells
Crista ampullaris
Sensory nerve fibers
(b)
Direction of head rotation
Cupula is pushed over and stimulates hair cells
Endolymph lags behind because of inertia
(c)

Figure 17.17 **The Semicircular Ducts.** (a) Structure of the semicircular ducts, with each ampulla opened to show the crista ampullaris and cupula. (b) Detail of the crista ampullaris. (c) Action of the endolymph on the cupula and hair cells when the head is rotated.

The Semicircular Ducts

The head also rotates, such as when you spin in a rotating chair, walk down a hall and turn a corner, bend forward to pick something up from the floor, or tilt your head laterally when you lie down in bed. Such movements are detected by the three *semicircular ducts* (fig. 17.17), each housed in an osseous *semicircular canal* of the temporal bone. The *anterior* and *posterior semicircular ducts* are positioned vertically, at right angles to each other. The *lateral semicircular duct* is about 30° from horizontal. The orientation of the ducts causes a different duct to be stimulated by rotation of the head in different planes—turning it from side to side as in gesturing "no," nodding up and down as in gesturing "yes," or tilting it from side to side as in touching your ears to your shoulders.

The semicircular ducts are filled with endolymph. Each duct opens into the utricle and has a dilated sac at one end called an **ampulla.**[31] Within the ampulla is a mound of hair cells and supporting cells called the **crista ampullaris.**[32] The hair cells have stereocilia and a kinocilium embedded in the **cupula,**[33] a gelatinous membrane that extends from the crista to the roof of the ampulla. When the head turns, the duct rotates, but the endolymph lags behind and pushes the cupula over. This bends the stereocilia and stimulates the hair cells. After 25 to 30 seconds of continual rotation, however, the endolymph catches up with the movement of the duct, and stimulation of the hair cells ceases even though motion continues.

---

[31] *ampulla* = little jar
[32] *crista* = crest, ridge; *ampullaris* = of the ampulla
[33] *cupula* = little tub

Apply What You Know

The semicircular ducts do not detect motion itself, but only acceleration—a change in the rate of motion. Explain why.

Vestibular Projection Pathways

Hair cells of the macula sacculi, macula utriculi, and semicircular ducts synapse at their bases with sensory fibers of the **vestibular nerve.** This and the cochlear nerve merge to form the vestibulocochlear nerve. Fibers of the vestibular nerve lead to a complex of four **vestibular nuclei** on each side of the pons and medulla. Nuclei on the right and left sides of the brainstem communicate extensively with each other, so each receives input from both the right and left ears. They process signals about the position and movement of the body and relay information to five targets (fig. 17.18):

1. The cerebellum, which integrates vestibular information into its control of head movements, eye movements, muscle tone, and posture.
2. Nuclei of the oculomotor, trochlear, and abducens nerves (cranial nerves III, IV, and VI). These nerves produce eye movements that compensate for movements of the head (the *vestibulo–ocular reflex*). To observe this effect, hold a book in front of you at a comfortable reading distance and fix your gaze on the middle of the page. Move the book left and right about once per second, and you will be unable to read it. Now hold the book still and shake your head from side to side at the same rate. This time you will be able to read the page because the vestibulo–ocular reflex compensates for your head movements and keeps your eyes fixed on the target. This reflex enables you to keep your vision fixed on a distant object as you walk or run toward it.
3. The reticular formation, which is thought to adjust breathing and blood circulation to changes in posture.
4. The spinal cord, where fibers descend the two vestibulospinal tracts on each side (see fig. 14.3, p. 376) and synapse on motor neurons that innervate the extensor (antigravity) muscles. This pathway allows you to make quick movements of the trunk and limbs to keep your balance.
5. The thalamus, which relays signals to two areas of the cerebral cortex. One is at the inferior end of the postcentral gyrus adjacent to sensory regions for the face. It is here that we become consciously aware of body position and movement. The other is slightly rostral to this, at the inferior end of the central sulcus in the transitional zone from primary sensory to motor cortex. This area is thought to be involved in motor control of the head and body.

Before You Go On

Answer the following questions to test your understanding of the preceding section.

11. What is the benefit of having three auditory ossicles and two muscles in the middle ear?
12. Explain how vibration of the tympanic membrane ultimately causes cochlear hair cells to release a neurotransmitter.
13. How does the brain recognize the difference between high C and middle C of a piano? Between a loud sound and a soft one?
14. How does the function of the semicircular ducts differ from the function of the saccule and utricle?
15. How is the sensory mechanism of the semicircular ducts similar to that of the saccule and utricle?



Figure 17.18 **Vestibular Projection Pathways in the Brain.**

17.4 The Eye

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the anatomy of the eye and its accessory structures;
b. describe the histological structure of the retina and its receptor cells;
c. explain why different types of receptor cells and neural circuits are required for day and night vision; and
d. trace the visual projection pathway in the brain.

Vision is the ability to form a recognizable image of an object that emits or reflects light. It begins with focusing light on a membrane called the *retina*, the site of the sensory cells. Here, the light creates a chemical reaction that leads to the generation of a nerve signal. The brain must receive and interpret this nerve signal for the process of vision to be complete.

Accessory Structures of the Orbit

The eyeball occupies a bony socket called the **orbit.** This general area of the face, called the *orbital region*, contains structures that protect and aid the eye (figs. 17.19 and 17.20). These include the *eyebrows, eyelids, conjunctiva, lacrimal apparatus,* and *extrinsic eye muscles.*

- The **eyebrows** enhance facial expression and nonverbal communication and shield the eyes to some degree from glare and forehead perspiration.
- The **eyelids,** or **palpebrae** (pal-PEE-bree), close periodically to moisten the eye with tears, sweep debris from the surface, block foreign objects from the eye, and prevent visual stimuli from disturbing our sleep. The two eyelids are separated by the **palpebral fissure,** and the corners where they meet are called the **medial** and **lateral commissures (canthi).** The eyelid consists largely of the orbicularis oculi muscle covered with skin (fig. 17.20a). It also contains a supportive fibrous **tarsal plate,** which is thickened along the margin of the eyelid. Within this plate are 20 to 25 **tarsal glands** that open along the edge of the eyelid. They secrete an oil that coats the eye and reduces tear evaporation. The **eyelashes** are guard hairs that help to keep debris from the eye. Touching the eyelashes stimulates hair receptors and triggers the blink reflex.
- The **conjunctiva** (CON-junk-TY-vuh) is a transparent mucous membrane that covers the inner surface of the eyelid and anterior surface of the eyeball except the clear area (cornea). The layer on the inside of the eyelid is called the *palpebral conjunctiva,* the layer on the eye surface is the *bulbar conjunctiva,* and the space between them (beneath the eyelid) is the *conjunctival sac.* The primary purpose of the conjunctiva is to secrete a thin mucous film that prevents the eyeball from drying. It is richly innervated and highly sensitive to pain. It is also very vascular (contains abundant blood vessels), which is especially evident when the vessels are dilated and the eyes are "bloodshot." Because it is vascular and the cornea is not, the conjunctiva heals more quickly than the cornea when injured.



Figure 17.19 External Anatomy of the Orbital Region.

Apply What You Know

How would vision be affected if the conjunctiva covered the cornea?

- The **lacrimal**[34] **apparatus** (fig. 17.20b) consists of the lacrimal (tear) gland and a series of ducts that drain the tears into the nasal cavity. The almond-shaped **lacrimal gland** is nestled in a shallow fossa of the frontal bone in the superolateral corner of the orbit. About 12 short ducts lead from the gland to the surface of the conjunctiva. Tears cleanse and lubricate the eye surface, deliver oxygen and nutrients to the conjunctiva, and contain a bactericidal enzyme, *lysozyme,* that helps to prevent eye infections. After washing across the eye, the tears collect at the **lacrimal caruncle**[35] (CAR-un-cul), the pink fleshy mass near the medial commissure of the eye. Near the caruncle, each eyelid has a tiny pore called a lacrimal **punctum,**[36] which collects the tears and conveys them through a short **lacrimal canaliculus** into a **lacrimal sac.** From here, a **nasolacrimal duct** carries the tears to the inferior meatus of the nasal cavity—thus, an abundance of tears from crying or "watery eyes" can result in a runny nose. Normally, the tears are swallowed. When you have a cold, the nasolacrimal ducts become swollen and obstructed, the tears cannot drain, and they may overflow from the brim of your eye.

---

[34] *lacrim* = tear
[35] *car* = fleshy mass; *uncle* = little
[36] *punct* = point


Frontal bone
Levator palpebrae superioris muscle
Orbicularis oculi muscle
Superior rectus muscle
Tarsal plate
Tarsal glands
Cornea
Bulbar conjunctiva
Conjunctival sac
Palpebral conjunctiva
Lateral rectus muscle
Inferior rectus muscle
(a)
Lacrimal gland
Ducts
Lacrimal sac
Lacrimal punctum
Lacrimal canaliculus
Nasolacrimal duct
Inferior meatus of nasal cavity
Nostril
(b)

Figure 17.20 **Accessory Structures of the Orbit.** (a) Sagittal section of the eye and orbit. (b) The lacrimal apparatus. The arrows indicate the flow of tears from the lacrimal gland, across the front of the eye, into the lacrimal sac, and down the nasolacrimal duct.

- *What would be the effect of blockage of the lacrimal puncta?* APR


Optic nerve
Trochlea
Muscles:
Superior oblique
Superior rectus
Medial rectus
Lateral rectus
Inferior oblique
Inferior rectus
Superior oblique tendon
Muscles:
Superior rectus
Inferior rectus
Levator palpebrae superioris (cut)

(a) Lateral view

(b) Superior view


Trochlear nerve (IV)
Superior oblique muscle
Abducens nerve (VI)
Lateral rectus muscle
Levator palpebrae superioris muscle
Superior rectus muscle
Medial rectus muscle
Inferior rectus muscle
Inferior oblique muscle
Oculomotor nerve (III)

(c) Frontal view

Figure 17.21 **Extrinsic Muscles of the Eye.** (a) Lateral view of the right eye. The lateral rectus muscle is cut to expose a portion of the optic nerve. (b) Superior view of the right eye. (c) Innervation of the extrinsic muscles; arrows indicate the eye movement produced by each muscle.

- *Which would cause the greatest loss of visual function—trauma to cranial nerve III, IV, or VI? Why?* APR

- Six **extrinsic eye muscles** are attached to the walls of the orbit and to the external surface of each eyeball. *Extrinsic* means arising from without, and distinguishes these from the *intrinsic* muscles inside the eyeball, discussed later. The extrinsic muscles are responsible for movements of the eye (fig. 17.21). They include four *rectus* ("straight") muscles and two *oblique* muscles. The **superior, inferior, medial,** and **lateral rectus** arise from a tendinous ring on the posterior wall of the orbit and insert on the anterior region of the eyeball, just beyond the visible "white of the eye." They move the eye up, down, medially, and laterally. The **superior oblique** travels along the medial wall of the orbit. Its tendon passes through a fibrocartilage loop, the **trochlea**[37] (TROCK-lee-uh), and inserts on the superolateral aspect of the eyeball. The **inferior oblique** extends from the medial wall of the orbit to the inferolateral aspect of the eye. To visualize the function of the oblique muscles, suppose you turn your eyes to the right. The superior oblique muscle slightly depresses your right eye, while the inferior oblique slightly elevates the left eye. The opposite occurs when you look to the left. This is the primary function of the oblique muscles, but they also rotate the eyes, turning the "twelve o'clock pole" of each eye slightly toward or away from the nose. The superior oblique muscle is innervated by the trochlear nerve (IV), the lateral rectus muscle by the abducens nerve (VI), and the rest of these muscles by the oculomotor nerve (III).

The eye is surrounded on the sides and back by **orbital fat.** It cushions the eye, gives it freedom of motion, and protects blood vessels and nerves as they pass through the rear of the orbit.

Anatomy of the Eyeball

The eyeball itself is a sphere about 24 mm (1 inch) in diameter (fig. 17.22) with three principal components: (1) three layers (tunics) that form its wall; (2) optical components that admit and focus light; and (3) neural components, the retina and optic nerve. The retina is not only a neural component but also part of the inner tunic. The cornea is part of the outer tunic as well as one of the optical components.

The Tunics

There are three tunics forming the wall of the eyeball:

- The outer **fibrous layer (tunica fibrosa)** is divided into two regions, the sclera and cornea. The **sclera**[38] (white of the eye) covers most of the eye surface and consists of dense collagenous connective tissue perforated by blood vessels and nerves. The **cornea** is the anterior transparent region of modified sclera that admits light into the eye. It is composed mainly of very compact layers of collagen and thin flat fibroblasts. It is covered by a thin stratified squamous epithelium anteriorly and a simple squamous epithelium posteriorly. The anterior epithelium is a source of stem cells that give the cornea a great capacity for regeneration in response to injury.

---

[37] *trochlea* = pulley

[38] *scler* = hard, tough



Figure 17.22 The Eye (Sagittal Section). APR

- The middle **vascular layer (tunica vasculosa)** is also called the **uvea**[39] (YOU-vee-uh) because it resembles a peeled grape in fresh dissection. It consists of three regions—the choroid, ciliary body, and iris. The **choroid** (CO-royd) is a highly vascular, deeply pigmented layer of tissue behind the retina. It gets its name from a histological resemblance to the chorion of a fetus. Anteriorly, it thickens and grades into the **ciliary body,** which supports the lens and forms a muscular ring around it. The smooth muscle in the ciliary body, called the **ciliary muscle,** controls tension on the lens and is thus important in focusing it. The ciliary body also supports the iris and secretes a fluid called the aqueous humor. The **iris** is an adjustable diaphragm that controls the diameter of the **pupil,** its central opening. The iris has two pigmented layers. One is a posterior *pigment epithelium* that blocks stray light from reaching the retina. The other is the *anterior border layer,* which contains pigmented cells called **chromatophores.**[40] High concentrations of melanin in the chromatophores give the iris a black, brown, or hazel color. If the melanin is scanty, light reflects from the posterior pigment epithelium and gives the iris a blue, green, or gray color.

  The diameter of the pupil is controlled by two sets of contractile elements in the iris. The **pupillary constrictor** consists of concentric circles of smooth muscle cells around the pupil. The **pupillary dilator** consists of a spokelike arrangement of contractile processes that extend from the cells of the posterior pigment epithelium. Because of their dual epithelial and contractile nature, these cells are classified as *myoepithelial cells.* When their processes contract, they dilate the pupil and admit up to five times as much light as a fully constricted pupil. The pupils constrict in response to increased light intensity and when we focus on nearby objects; they dilate in dimmer light and when we focus on more distant objects. Their response to light is called the *photopupillary reflex.*

  The ciliary muscle, pupillary constrictor, and pupillary dilator are considered to be the **intrinsic eye muscles,** in contrast to the aforementioned extrinsic muscles found on the outside of the eyeball. Both sympathetic and parasympathetic nerve fibers enter the rear of the eyeball and innervate these muscles (see figs. 16.4 and 16.7, pp. 447 and 451). Sympathetic fibers from the superior cervical ganglion innervate the pupillary dilator and widen the pupil. Parasympathetic fibers reach the eye through the oculomotor nerve (cranial nerve III), innervate the pupillary constrictor, and narrow the pupil, thus antagonizing the sympathetic effect (see fig. 16.9, p. 455). The parasympathetic division also thickens the lens for near vision.
- The **inner layer (tunica interna)** consists of the *retina,* which internally lines the posterior two-thirds of the eyeball.

Optical Components

The optical components of the eye are transparent elements that admit light rays, bend (refract) them, and focus images on the retina. They include the *cornea, aqueous humor, lens,* and *vitreous body.* The cornea has been described already.

- The **aqueous humor** is a serous fluid secreted by the ciliary processes into a space between the iris and lens called the **posterior chamber** (fig. 17.23). It flows through the pupil

---

[39] *uvea* = grape

[40] *chromato* = color; *phore* = bearer



Figure 17.23 **Production and Reabsorption of Aqueous Humor.** Blue arrows indicate the flow of aqueous humor from the ciliary processes into the posterior chamber, through the pupil into the anterior chamber, and finally into the scleral venous sinus, the vein that reabsorbs the fluid.



© Ralph C. Eagle, M.D./Science Source

Figure 17.24 **Lens of the Eye (SEM).** Posterior view of the lens and the suspensory ligament that anchors it to the ciliary body.

into the **anterior chamber,** a space between the cornea and iris. From here, it is reabsorbed by a circular vein called the **scleral venous sinus (canal of Schlemm[41]).** Normally, the rate of reabsorption balances the rate of secretion. (See Deeper Insight 17.4 for an important exception.)

- The **lens** is composed of flattened, tightly compressed, transparent cells called **lens fibers.** It is suspended behind the pupil by a fibrous ring called the **suspensory ligament** (figs. 17.22 and 17.24), which attaches it to the ciliary body. Tension on the ligament somewhat flattens the lens, so it is about 9.0 mm in diameter and 3.6 mm thick at the middle. When the lens is removed from the eye and not under tension, it relaxes into a more spheroidal shape and resembles a plastic bead.
- The **vitreous[42] body (vitreous humor)** is a transparent jelly that fills a large space called the **vitreous chamber** behind the lens. An oblique channel through this body, called the *hyaloid canal,* is the remnant of a *hyaloid artery* present in the embryo (see fig. 17.22). The vitreous body serves to maintain the spherical shape of the eyeball and to keep the retina smoothly pressed against the inner surface of the chamber. This is essential for the focusing of images on the retina.

Neural Components

The neural components of the eye are the retina and optic nerve. The retina is a thin transparent membrane attached at only two points—the **optic disc** where the optic nerve leaves the rear (fundus) of the eye, and its scalloped anterior margin, the **ora serrata.**[43] The rest of the retina is held smoothly against the rear of the eyeball by the pressure of the vitreous body. It can detach (buckle away from the wall of the eyeball) because of blows to the head or insufficient pressure from the vitreous body. A *detached retina* may cause blurry areas in the field of vision. It can lead to blindness if the retina remains separated for too long from the choroid, on which it depends for oxygen, nutrition, and waste removal.

The inside rear of the eyeball, called the **fundus,** is routinely examined with an illuminating and magnifying instrument called an *ophthalmoscope.* Directly posterior to the center of the lens, on the visual axis of the eye, is a patch of cells called the **macula lutea,**[44] about 3 mm in diameter (fig. 17.25). In the center of the macula is a tiny pit, the **fovea[45] centralis.** It produces the most finely detailed images for a reason that will

DEEPER INSIGHT 17.4

Cataracts and Glaucoma

The two most common causes of blindness are cataracts and glaucoma. A *cataract* is clouding of the lens. It occurs as the lens fibers darken with age, fluid-filled bubbles (vacuoles) and clefts appear between the lens fibers, and the clefts accumulate debris from degenerating fibers. Cataracts are a common complication of diabetes mellitus, but can also be induced by heavy smoking, ultraviolet radiation, radiation therapy, certain viruses and drugs, and other causes. They cause the vision to appear milky or as if one was looking from behind a waterfall.[46] Cataracts can be treated by replacing the natural lens with a plastic one. The implanted lens improves vision almost immediately, but glasses still may be needed for near vision.

Glaucoma is a state of elevated pressure within the eye that occurs when the scleral venous sinus is obstructed so aqueous humor is not reabsorbed as fast as it is secreted. Pressure in the anterior and posterior chambers drives the lens back and puts pressure on the vitreous body. The vitreous body presses the retina against the choroid and compresses the blood vessels that nourish the retina. Without a good blood supply, retinal cells die and the optic nerve may atrophy, producing blindness. Symptoms often go unnoticed until the damage is irreversible. Illusory flashes of light are an early symptom of glaucoma. Late-stage symptoms include dimness of vision,[47] a narrowed visual field, and colored halos around artificial lights. Glaucoma can be halted with drugs or surgery, but lost vision cannot be restored. This disease can be detected at an early stage in the course of regular eye examinations. The field of vision is checked, the optic nerve is examined, and the intraocular pressure is measured with an instrument called a *tonometer.*

---

[41] Friedrich S. Schlemm (1795–1858), German anatomist
[42] *vitre* = glassy
[43] *ora* = border, margin; *serrata* = notched, serrated
[44] *macula* = spot; *lutea* = yellow
[45] *fovea* = pit, depression
[46] *cataract* = waterfall
[47] *glauco* = grayness



© Peter Dazeley/Getty Images

© Lisa Klancher

Figure 17.25 **Fundus (Rear) of the Eye.** (a) Use of the ophthalmoscope. (b) Ophthalmoscopic photograph of the fundus. (c) Anatomical features of the fundus. Note the blood vessels diverging from the optic disc, where they enter the eye with the optic nerve. An eye examination also serves as a partial check on cardiovascular health.

be apparent later. About 3 mm medial to the macula lutea is the optic disc. Nerve fibers converge on this point from neurons throughout the retina and leave here in a bundle that constitutes the optic nerve. Blood vessels travel through the optic nerve and enter and leave the eye at the optic disc. Eye examinations thus serve for more than evaluating the visual system; they allow for a direct, noninvasive examination of blood vessels for signs of hypertension, diabetes mellitus, atherosclerosis, and other vascular diseases.

The optic disc contains no receptor cells, so it produces a **blind spot** in the visual field of each eye. To see this effect, close your right eye and gaze straight ahead with your left; fixate on an object across the room. Now hold up a pencil about 30 cm (1 ft) from your face at eye level. Begin moving the pencil toward the left, but be sure you keep your gaze fixed on that point across the room. When the pencil is about 15° away from your line of vision, the end of it will disappear because its image falls on the blind spot of your left eye. One reason you do not normally notice a blind patch in your visual field is that the brain uses the image surrounding the blind spot to fill in that area with similar, essentially imaginary information. Another reason is that the eye continually undergoes minute fluttering movements that ensure that the same area of the visual field is not always projected on the same area of retina.

Formation of an Image

The visual process begins when light rays enter the eye, become focused on the retina, and produce a tiny inverted image. The cornea refracts incoming light rays toward the optical axis of the eye, and the lens makes relatively slight adjustments to fine focus the image. When you focus on something more than 6 m (20 ft) away, the lens flattens to a thickness of about 3.6 mm at the center and refracts light less. When you focus on something closer than 6 m, the lens thickens to about 4.5 mm at the center and refracts light rays more strongly. These changes in the lens are called *accommodation.* Abnormalities in lens flexibility, the shape of the cornea, or the length of the eyeball result in various deficiencies of vision explained in table 17.2 and figure 17.26.

TABLE 17.2 Common Defects of Image Formation

Myopia[48]	Nearsightedness—difficulty focusing on faraway objects because of an abnormally elongated eyeball. Light rays come into focus before they reach the retina and begin to diverge again by the time they fall on it. Corrected with concave lenses, which cause light rays to diverge slightly before entering the eye.
Hyperopia[49]	Farsightedness—difficulty focusing on nearby objects because of an abnormally short eyeball. The retina lies in front of the focal point of the lens, and the light rays have not yet come into focus when they reach the retina. Corrected with convex lenses, which cause light rays to converge slightly before entering the eye.
Presbyopia[50]	Declining ability to focus on nearby objects as one ages. An effect of declining elasticity of the aging lens, often first noticed around age 40 to 45. Results in difficulty in reading and doing close handwork. Corrected with reading glasses or bifocal lenses.
Astigmatism[51]	Inability to simultaneously focus light rays that enter the eye on different planes. Focusing on vertical lines, such as the edge of a door, may cause horizontal lines, such as a tabletop, to go out of focus. Caused by a deviation in the shape of the cornea so that it is shaped like the back of a spoon rather than like part of a sphere. Corrected with "cylindrical" lenses, which refract light more in one plane than another.



(a) Emmetropia (normal) **(b) Hyperopia (farsightedness)** **(c) Myopia (nearsightedness)**

Figure 17.26 **Two Common Visual Defects and the Effects of Corrective Lenses.** (a) The normal emmetropic eye, with light rays converging on the retina. (b) Hyperopia (farsightedness) and the corrective effect of a convex lens. The lens causes light rays to begin converging before they enter the eye, so they reach their focal point farther forward than usual, on the retina of the shortened eyeball. (c) Myopia (nearsightedness) and the corrective effect of a concave lens. By causing light rays to diverge before they enter the eye, this lens shifts the focal point posteriorly so that it falls on the retina of the elongated eye.

Structure and Function of the Retina

The conversion of light energy into action potentials occurs in the retina. Its cellular organization is shown in figure 17.27. The most posterior layer is the **pigment epithelium,** a darkly pigmented layer that serves, like the black inside of a film camera, to absorb stray light so it does not degrade the visual image by reflecting back into the eye.

Apply What You Know

The vertebrate eye is often called a *camera eye* for its many resemblances to the mechanisms of a film camera. List as many comparisons as you can.

The neural apparatus of the retina consists of three principal cell layers. Progressing from the rear of the eye forward, the major retinal cells are the *photoreceptors* (mainly *rods* and *cones*), *bipolar cells,* and *ganglion cells.*

---

[48] *my* = near; *opia* = eye condition
[49] *hyper* = beyond; *opia* = eye condition
[50] *presby* = old age; *opia* = eye condition
[51] *a* = without; *stigma* = point; *ism* = condition


Back of eye
Sclera
Choroid
Pigment epithelium
Rod and cone outer segments
Rod and cone nuclei
Bipolar cells
Ganglion cells
Nerve fibers to optic nerve
Vitreous body
Front of eye
25 µm
(a)
Back of eye
Pigment epithelium
Photoreceptors:
Rod
Cone
Transmission of rod signals
Transmission of cone signals
Horizontal cell
Bipolar cell
Amacrine cell
Ganglion cell
To optic nerve
Nerve fibers
Direction of light
(b)

McGraw-Hill Education/Dennis Strete, photographer

Figure 17.27 **Histology of the Retina.** (a) Photomicrograph. (b) Schematic of the layers and circuitry of the retinal cells.

1. **Photoreceptor cells.** The photoreceptor cells include all cells that absorb light and generate a chemical or electrical signal. There are three kinds: rods, cones, and some of the ganglion cells. Only the rods and cones produce visual images; the ganglion cells are discussed shortly. Each rod or cone has an **outer segment** that points toward the wall of the eye and an **inner segment** facing the interior (fig. 17.28). The two segments are separated by a narrow constriction containing nine pairs of microtubules; the outer segment is actually a highly modified cilium specialized to absorb light. The inner segment contains mitochondria and other organelles. At its base, it gives rise to a cell body, which contains the nucleus, and to processes that synapse with retinal neurons in the next layer.

   In a **rod,** the outer segment is cylindrical and somewhat resembles a stack of coins in a paper roll—there is a plasma membrane around the outside and an orderly stack of about 1,000 membranous discs inside. Each disc is densely studded with globular proteins—the visual pigment *rhodopsin.* The membranes hold these pigment molecules in a position that maximizes light absorption. Rod cells are responsible for **night (scotopic[52]) vision** and produce images only in shades of gray *(monochromatic vision).* Even in ordinary indoor lighting, they are *saturated* (overstimulated) and nonfunctional.

   A **cone** is similar except that the outer segment tapers to a point and the discs are not detached from the plasma membrane but are parallel infoldings of it. Cones begin to respond in light as dim as starlight and are the only receptor cells functional in daylight intensities; thus, they are entirely responsible for our **day (photopic[53]) vision.** They are also responsible for **color vision** *(trichromatic vision),* because unlike rods, cones do not all carry the same visual pigment. Their pigments are called *photopsins.* Some cones have a photopsin that responds best at a wavelength of 420 nanometers (nm), a deep blue light; others respond best at 531 nm (green); and still others at 558 nm (orange-yellow). All colors we see are the result of various mixtures of input to the brain from these three types of cones.
2. **Bipolar cells.** Rods and cones synapse with the dendrites of bipolar neurons. These, in turn, feed directly or indirectly into the ganglion cells described next (fig. 17.27b).

---

[52] *scot* = dark; *op* = vision

[53] *phot* = light; *op* = vision



Figure 17.28 **Rods and Cones.** (a) Rods and cones of a salamander retina (SEM). The tall cylindrical cells are rods, and the short tapered cells in the foreground are cones. (b) Structure of human rods and cones.

Courtesy of Beckman Vision Center at UCSF School of Medicine/D. Copenhagen, S. Mittman, and M. Maglio

3. **Ganglion cells.** These are the largest neurons of the retina, arranged in a single layer close to the vitreous body. Most ganglion cells receive input from multiple bipolar cells. Their axons form the optic nerve. Some ganglion cells absorb light directly and conduct signals to brainstem nuclei that control pupillary diameter and the body's circadian rhythms. They do not contribute to visual images but detect only light intensity. Their sensory pigment is called *melanopsin.*

There are other retinal cells, but they do not form layers of their own. **Horizontal cells** and **amacrine**[54] (AM-ah-crin) **cells** form horizontal connections among rod, cone, and bipolar cells. Bipolar cells that carry rod signals do not synapse directly with ganglion cells, but only by way of amacrine cells. Horizontal and amacrine cells play diverse roles in enhancing the perception of contrast, the edges of objects, and changes in light intensity. In addition, much of the mass of the retina is composed of astrocytes and other types of glial cells.

There are approximately 130 million rods and 6.5 million cones in one retina, but only about 1 million nerve fibers in the optic nerve. With a ratio of nearly 140 receptor cells to 1 optic nerve fiber, it is obvious that there must be substantial *neural convergence* and information processing in the retina itself before signals are conducted to the brain proper. Convergence begins where multiple rod or cone cells converge on one bipolar cell, and occurs again where multiple bipolar cells converge on a single ganglion cell.

Retinal Circuitry and Visual Sensitivity

You may wonder why we have two types of photoreceptor cells, the rods and cones. Why can't we simply have one type that would produce detailed color vision, both day and night? The answer to this lies largely in the concept of neural convergence (see p. 364). The **duplicity theory** of vision holds that a single type of receptor cell cannot produce both high sensitivity and high resolution. It takes one type of cell and neural circuit, working at its maximum capacity, to provide sensitive night vision and a different type of receptor and circuit to provide high-resolution daytime vision.

The high sensitivity of rods in dim light stems partly from a cascade of chemical reactions that occurs when rhodopsin absorbs light. The cascade amplifies the effect of the light, so a small stimulus produces a relatively large output from each rod. But in addition, up to 600 rods converge on each bipolar cell, and then multiple bipolar cells converge (via amacrine cells) on each ganglion cell (fig. 17.29a). Weak stimulation of many rod cells can produce an additive effect on one bipolar cell, and several bipolar cells can collaborate to excite one ganglion cell. Thus, a ganglion cell can respond in dim light that only weakly stimulates an individual rod. A shortcoming of this system is that it cannot resolve finely detailed images. One ganglion cell receives input from all the rods in about 1 mm^2 of retina—its receptive field. What the brain perceives is therefore a coarse, grainy image similar to an overenlarged newspaper photograph.

Around the edges of the retina, receptor cells are especially large and widely spaced. If you fixate on the middle of a page of print, you will notice that you cannot read the words near the margins. Visual acuity decreases rapidly as the image falls away from the fovea centralis. Our peripheral vision is a low-resolution system that serves mainly to alert us to motion in the periphery and to stimulate us to look that way to identify what is there.

---

[54] *a* = without; *macr* = long; *in* = fiber



Figure 17.29 **Retinal Circuitry and Visual Sensitivity.** (a) In the scotopic (night vision) system, many rod cells converge on each bipolar cell, and many bipolar cells converge on each ganglion cell. This allows the rods to combine their effects and stimulate the ganglion cell, generating a nerve signal even in dim light. However, it means that each ganglion cell (and its optic nerve fiber) represents a relatively large area of retina and produces a grainy image. (b) In the photopic (day vision) system, there is little neural convergence. In the fovea, represented here, each cone cell has a "private line" to the brain, so each optic nerve fiber represents a tiny area of retina, and vision is relatively sharp. However, the lack of convergence means that photopic vision cannot function very well in dim light because weakly stimulated cones cannot collaborate to stimulate a ganglion cell. APR

When you look directly at something, its image falls on the fovea, which is occupied by about 4,000 tiny cones and no rods. The other neurons of the fovea are displaced to the sides, like parted hair, so they do not interfere with light falling on the cones. The smallness of these cones is like the smallness of the dots in a high-quality photograph; it is partially responsible for the high-resolution images formed at the fovea. In addition, the cones here show no neural convergence. Each cone synapses with only one bipolar cell and each bipolar cell with only one ganglion cell. This gives each foveal cone a "private line" to the brain, and each ganglion cell of the fovea reports to the brain on a receptive field of just 2 μm^2 of retinal area (fig. 17.29b). Cones distant from the fovea exhibit some neural convergence, but not nearly as much as rods do. The price of this lack of convergence at the fovea, however, is that cone cells cannot have additive effects on the ganglion cells, and the cone system therefore is less sensitive to light (requires brighter light to function).

Apply What You Know

If you look directly at a dim star in the night sky, it disappears, and if you look slightly away from it, it reappears. Why?

The Visual Projection Pathway

The first-order neurons in the visual pathway are the bipolar cells of the retina. They synapse directly or indirectly (via amacrine cells) with the second-order neurons, the retinal ganglion cells, whose axons are the fibers of the optic nerve (cranial nerve II). The optic nerves leave each orbit through the optic canal, then converge to form an X, the **optic chiasm**[55] (KY-az-um), inferior to the hypothalamus and anterior to the pituitary. Beyond this, the fibers continue as a pair of **optic tracts** (see fig. 15.26, p. 429). Within the chiasm, half the fibers of each optic nerve cross over to the opposite side of the brain (fig. 17.30). This is called **hemidecussation,**[56] since only half of the fibers decussate. As a result, the right cerebral hemisphere sees objects in the left visual field, because their images fall on the right half of each retina (the medial half of the left eye and lateral half of the right eye). You can trace the nerve fibers from each half of the retina in figure 17.30 to see that they lead to the right hemisphere. Conversely, the left hemisphere sees objects in the right visual field. Since the right brain controls motor responses on the left side of the body and vice

---

[55] *chiasm* = cross, X
[56] *hemi* = half; *decuss* = to cross, form an X


Uncrossed (ipsilateral) fiber
Crossed (contralateral) fiber
Optic radiation
Right eye
Fixation point
Occipital lobe (visual cortex)
Left eye
Optic nerve
Optic chiasm
Optic tract
Pretectal nucleus
Lateral geniculate nucleus of thalamus
Superior colliculus

Figure 17.30 **The Visual Projection Pathway.** Note that the hemidecussation at the optic chiasm results in the occipital lobe of each cerebral hemisphere receiving input from both eyes.

versa, each side of the brain sees what is on the side of the body where it exerts motor control. The visual fields of the two eyes and hemispheres overlap in the middle.

The optic tracts pass laterally around the hypothalamus, and most of their axons end in the **lateral geniculate**[57] (jeh-NIC-you-late) **nucleus** of the thalamus. Third-order neurons arise here and form the **optic radiation** of fibers in the white matter of the cerebrum. These fibers project to the primary visual cortex of the occipital lobe, where the conscious perception of an image occurs. A stroke that destroys occipital lobe tissue can cause blindness even if the eyes are fully functional.

Optic nerve fibers from the photosensitive ganglion cells take a different route; they project to the midbrain and terminate in the superior colliculi and adjacent *pretectal nuclei.* The superior colliculi control the visual reflexes of the extrinsic muscles, and the pretectal nuclei are involved in the photopupillary and accommodation reflexes of the intrinsic muscles. Thus, these retinal ganglion cells (about 1% to 2% of the total) are not engaged in producing the images we see, but only in providing input to evoke these somatic and autonomic reflexes of the eyes.

The mechanisms of visual information processing in the brain are very complex and beyond the scope of this book. Some processing, such as contrast, brightness, motion, and stereoscopic vision, begins in the retina. The primary visual cortex is connected by association tracts to nearby visual association areas in the posterior part of the parietal lobe and inferior part of the temporal lobe. These areas process visual data to extract information about the location, motion, color, shape, boundaries, and other qualities of the objects we observe. They also store visual memories and enable the brain to identify what we are seeing—for example, to recognize printed words or name the objects we see. What is yet to be learned about visual processing promises to have important implications for biology, medicine, psychology, and even philosophy.

Before You Go On

Answer the following questions to test your understanding of the preceding section.

16. List the optical components of the eye and state the role of each one in the formation of an image.
17. List as many structural and functional differences between rods and cones as you can.
18. Trace the signal pathway from the point where a retinal cell absorbs light to the point where a third-order nerve fiber ends in the occipital lobe.
19. Discuss the duplicity theory of vision, summarizing the advantage of having different types of retinal photoreceptor cells.

---

[57] *geniculate* = bent like a knee

17.5 Developmental and Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the prenatal development of the major features of the eye and ear; and
b. describe some disorders of taste, vision, hearing, equilibrium, and somatosensory function.

Development of the Ear

The ear develops from the first pharyngeal pouch (see p. 92) and adjacent tissues of the first and second pharyngeal arches. The first section to develop is the inner ear. Its earliest trace is a thickening called the **otic placode**[58] **(otic disc),** which develops in the ectoderm near the hindbrain in week 3. The placode invaginates, forming an **otic pit** and then a fully enclosed **otic vesicle,** which detaches from the overlying ectoderm by the end of week 4 (fig. 17.31a).

The otic vesicle differentiates into two chambers, the utricle and saccule. In week 5, the lower tip of the saccule elongates and begins to form the cochlear duct; soon after, three pouches grow from the utricle and begin to form the semicircular ducts (fig. 17.31b). These structures are still embedded in mesenchyme, which in week 9 chondrifies and forms a cartilaginous **otic capsule** enclosing the inner-ear structures. The capsule later ossifies to form the petrous part of the temporal bone and its bony labyrinth.

The middle-ear cavity and auditory tube arise by elongation of the first pharyngeal pouch, beginning in week 5. Mesenchyme of the first two pharyngeal arches gives rise to the three auditory ossicles and the two middle-ear muscles. These bones and muscles remain solidly embedded in mesenchyme until the last month of fetal development, at which time the mesenchyme degenerates and leaves the hollowed-out middle-ear cavity (fig. 17.31c).

At the same time as the middle ear begins to form, the facing edges of the first and second pharyngeal arches form three pairs of humps called *auricular hillocks* (fig. 17.31d). These enlarge, fuse, and differentiate into the folds and whorls of the auricle by week 7. As this is happening, the first pharyngeal groove between these two arches begins to elongate, grow inward, and form the auditory canal. The tympanic membrane arises from the wall between the auditory canal and tympanic cavity, and thus has an outer ectodermal layer and inner endodermal layer, with a thin layer of mesoderm between.

Development of the Eye

An early indication of the development of the eye is the **optic vesicle,** seen by day 24 as an outgrowth on each side of the diencephalon, continuous with the neural tube (fig. 17.32a, b). As the optic vesicle reaches the overlying ectoderm, it invaginates and forms a double-walled **optic cup,** while its connection to the diencephalon narrows and becomes a hollow **optic stalk.** The outer wall of the optic cup becomes the *pigment retina,* later becoming the pigment epithelium discussed earlier. The inner wall becomes the *neural retina.* Starting around the end of week 6, the neural retina produces waves of cells that migrate toward the vitreous body and arrange themselves into layers of receptor cells (rods and cones) and neurons. The narrow space between the pigment retina and neural retina becomes obliterated, but these two walls of the cup never fuse. This is why the retina is so easily detached later in life. By the eighth month, all cell layers of the retina are present. Nerve fibers grow from the ganglion cells into the optic stalk, occupying and eliminating its lumen as they become the optic nerve.

A seemingly peculiar aspect of the retinas of humans and other vertebrate animals is that the rods and cones face the back of the eye, *away from the incoming light.* This arrangement, called an *inverted retina,* is quite opposite the seemingly more sensible arrangement of the octopus eye, which is like ours in many respects but has its receptor cells aimed toward the light. The reason for the inverted retina of humans is that the rods and cones are homologous to the ependymal cells of the neural tube—that is, they develop from the same embryonic origin, and thus face inward toward the lumen of the optic cup just like the mature ependymal cells that face inward toward the ventricles of the brain. The homology between these retinal cells and ependymal cells is also seen in their cilia. Ependymal cells have conventional motile cilia, whereas rod and cone outer segments are modified cilia.

As the optic cup contacts the ectoderm on the surface of the embryo, it induces ectodermal cells to thicken into a **lens placode** (fig. 17.32c). The placode invaginates and forms a **lens pit,** which separates from the ectoderm by day 32 and becomes a **lens vesicle** nestled within the optic cup (fig. 17.32d). (This is quite similar to the development of the otic vesicle of the ear.) The lens vesicle is hollow at first, but becomes filled in with lens fibers by day 33. The vitreous body develops from a gelatinous secretion that accumulates in the space between the lens vesicle and optic cup.

Mesenchyme grows to completely surround and enclose the optic cup, and differentiates into the extrinsic muscles, some other accessory structures of the orbit, and some components of the eyeball including the choroid and sclera. The choroid is homologous to the pia mater and arachnoid mater, and the sclera is homologous to the dura mater—that is, they arise from the same embryonic tissues as these meninges. The mesenchyme lateral to the optic cup (near the surface) develops a split that becomes the anterior chamber of the eye. The cornea develops from both the lateral mesenchyme and the overlying ectoderm. The iris grows inward from the anterior margin of the optic cup around the end of month 3. The eyelids develop from folds of ectoderm with a mesenchymal center. The upper and lower eyelids approach each other and fuse, closing the eyes, at the end of month 3; they separate again, and the eyes open, between months 5 and 7 (fig. 17.32e).

Disorders of the Sense Organs

Several disorders of the senses have already been discussed in this chapter. These are listed in table 17.3 along with brief descriptions of five additional disorders of multiple sensory modalities.

---

[58] *ot* = ear; *ic* = pertaining to; *plac* = plate; *ode* = form, shape


Otic placode
Neural tube
Notochord
Day 20
Otic pit
Day 24
Otic vesicle
Day 28 (week 4)

(a) Development of the otic vesicle


Utricle
Saccule
Week 4
Cochlear duct
Week 5
Semicircular ducts
Cochlear duct
Week 7

(b) Development of the membranous labyrinth from the otic vesicle


Otic vesicle
Pharyngeal groove I
Pharyngeal pouch I
Week 5
Auditory ossicles
Utricle
Saccule
Auditory canal
Cochlear duct
Tissue plug
Week 7
Temporal bone
Tympanic membrane
Middle-ear cavity
Auditory tube
Near birth

(c) Development of the auditory canal and middle ear

Figure 17.31 Development of the Ear. See text for explanation. In part (d), the auricular hillocks are numbered to show what parts of the fully developed auricle arise from each one.


Pharyngeal arches I–II
Pharyngeal groove I
3
4
2
5
1
6
Auricular hillocks
Week 6
3
4
2
5
1
6
Week 8
3
4
2
5
1
6
Week 38 (newborn)

(d) Development of the auricle

Before You Go On

Answer the following questions to test your understanding of the preceding section.

20. Describe the contributions of the first pharyngeal pouch and the first two pharyngeal arches to the development of the ear.
21. From an embryological standpoint, explain why rod and cone outer segments face away from the incoming light.
22. How are paresthesia and tinnitus similar (table 17.3)?
23. How are anosmia (p. 164) and ageusia (table 17.3) similar?


Cephalic
Telencephalon
Diencephalon
Optic vesicle
Surface ectoderm
Spinal cord
Caudal
(a) Day 24
Optic vesicle
Surface ectoderm
(b) Day 28
Optic stalk
Lens placode
Optic cup
(c) Day 32
Pigment retina
Neural retina
Lens vesicle
Mesenchyme
Vitreous body
Surface ectoderm
(d) Day 33
Sclera
Choroid
Vitreous body
Eyelid
Cornea
Iris
Lens
Retina
(e) 5 months

Figure 17.32 **Development of the Eye.** (a) Horizontal section of the head of an embryo. The optic vesicles show as outgrowths of the diencephalon. (b) Around day 28, the leading edge of the optic vesicle contacts the surface ectoderm. (c) The optic vesicle invaginates and becomes an optic cup, while inducing the ectoderm to form the lens placode. (d) The lens vesicle is now separated from the surface ectoderm and nestled in the optic cup, and a gelatinous vitreous body has been secreted between the lens vesicle and retina. (e) At 5 months, the lens vesicle is solidly filled with lens fibers; the sclera, choroid, iris, and cornea are partially formed; and the eyelids are just about to separate and reopen the eye.

TABLE 17.3	Some Sensory Disorders
Ageusia	Loss of the sense of one or more taste modalities, often due to damage to the hypoglossal nerve (loss of bitter taste) or facial nerve (loss of sweet, sour, and salty tastes).
Color blindness	Inability to distinguish certain colors from each other, such as green and orange, due to a hereditary lack of one of the three types of cones. A sex-linked recessive trait that affects more men than women.
Ménière disease	A disorder of proprioception in which one experiences episodes of vertigo (dizziness) often accompanied by nausea, tinnitus, and pressure in the ears. Usually accompanied by progressive hearing loss.
Paresthesia	Feelings of numbness, prickling, tingling, heat, or other sensations in the absence of stimulation; a symptom of nerve injuries and other neurological disorders.
Tinnitus	Perception of imaginary sounds such as whistling, buzzing, clicking, or ringing in the ear. May be temporary or permanent, intermittent or constant; typically associated with hearing loss in the high frequencies. May result from cochlear damage, aspirin or other drugs, ear infections, Ménière disease, or other causes.

Disorders Described Elsewhere

Anosmia	164	Detached retina	484	Leprosy	465
Astigmatism	486	Diabetic neuropathy	465	Middle-ear infection	471
Cataracts	484	Glaucoma	484	Myopia	486
Deafness	474	Hyperopia	486	Presbyopia	486

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

17.1 Receptor Types and the General Senses (p. 461)

1. The meaning of *sensory receptor* and the range of structures encompassed by the term
2. How receptors are classified by stimulus modality
3. The differences between general (somatosensory) and special senses, and which senses fall into each category
4. How receptors are classified by the origins of their stimuli
5. The types of sensory nerve endings considered to be unencapsulated, and the stimuli they are specialized to detect
6. The types of sensory nerve endings considered to be encapsulated, why they are called that, and the stimuli they are specialized to detect
7. The concept of a receptive field and what it implies about sensory effects in relation to the distance between two points of stimulation
8. The concepts of a sensory projection pathway and the first- through third-order neurons of the pathway
9. The projection pathways followed by somatosensory signals to reach the cerebral cortex and cerebellum
10. A definition of *pain,* the distinction between fast and slow pain, and the distinction between somatic pain and visceral pain
11. The projection pathways for pain signals from the head and from the rest of the body
12. An explanation for referred pain, and some examples of it
13. The role of the reticular formation and descending analgesic fibers in modulating one's sensitivity to pain

17.2 The Chemical Senses (p. 466)

1. The relationship of taste buds to the lingual papillae; types of lingual papillae and where on the tongue they are located; which types of papillae have taste buds and which ones do not; and some locations of taste buds other than on the tongue
2. The structure of a taste bud and taste cells
3. The five primary taste sensations and the difference between taste and flavor
4. The projection pathway taken by taste signals to their final destinations in the cerebral cortex
5. The location and structure of the olfactory mucosa and olfactory neurons
6. The projection pathways taken by olfactory signals from the mucosa to multiple destinations in the cerebral cortex, limbic system, and hypothalamus
7. The influence of the cerebral cortex on the perception of odors, especially from the anatomical perspective

17.3 The Ear (p. 470)

1. The three principal subdivisions of the ear
2. The parts of the outer ear
3. The parts of the middle ear, including its three auditory ossicles and two muscles
4. The major components of the membranous labyrinth of the inner ear
5. The anatomy of the cochlea and the functional difference between its inner and outer hair cells
6. How vibrations in the ear lead to the generation of nerve signals
7. How cochlear function enables the brain to distinguish loudness and pitch
8. The projection pathway taken by auditory signals from the cochlea to the primary auditory cortex of the brain; the functions served by the superior olivary nucleus and inferior colliculus along the way
9. The differences between static and dynamic equilibrium and between linear and angular acceleration; the inner-ear structures specialized to detect these
10. The structure of the saccule and utricle and the macula of each
11. The action of the otolithic membrane in stimulating the macula sacculi and macula utriculi
12. How the saccules and utricles of the two ears enable one to sense the orientation of the head and distinguish between vertical and horizontal acceleration
13. The structure of the semicircular ducts and how angular movements of the head stimulate their hair cells
14. The projection pathways taken by signals of equilibrium to multiple destinations in the brainstem, cerebellum, and cerebrum

17.4 The Eye (p. 480)

1. The accessory structures of the orbit and their anatomy
2. The three layers of the wall of the eye and the constituents of each layer
3. The optical components of the eye and how they act to control light and focus images on the retina
4. The neural components of the eye and how different regions of the retina differ in function
5. The structure of rod and cone cells, where in each cell the visual pigments are located, and how the two cell types differ in function
6. The relationship of the rods and cones with bipolar cells and ganglion cells in the retina, and the origin of the optic nerve fibers
7. The photosensory but nonvisual role of some of the ganglion cells
8. The locations of horizontal cells and amacrine cells in the retina, and their roles in vision
9. The reasons why both high light sensitivity and high resolution cannot be obtained with a single type of retinal circuit (rod or cone circuit), and in relation to this, how the rod and cone circuits in the retina differ from each other
10. The projection pathways taken by retinal signals to the occipital lobe and midbrain, including the hemidecussation that occurs at the optic chiasm and how this relates to occipital lobe input from the right and left eyes
11. The functions of the midbrain and occipital lobe in vision

17.5 Developmental and Clinical Perspectives (p. 491)

1. How the principal structures of the inner ear develop from the otic placode
2. How the structures of the outer and middle ear develop from the first two pharyngeal arches and the first pharyngeal pouch
3. How the optic vesicle arises and how it leads to the development of the retina
4. How the lens, vitreous body, anterior chamber, cornea, iris, and eyelids arise in the embryo

Testing Your Recall

1. Hot and cold stimuli are detected by
   a. free nerve endings.
   b. proprioceptors.
   c. end bulbs.
   d. lamellar corpuscles.
   e. tactile corpuscles.
2. Sensory signals for all of the following *except* _____ must pass through the thalamus before they can reach the cerebral cortex.
   a. smell
   b. taste
   c. hearing
   d. equilibrium
   e. vision
3. The vallate papillae are more sensitive to _____ than to any of these other tastes.
   a. bitter
   b. sour
   c. sweet
   d. umami
   e. salty
4. The ear is somewhat protected from loud noises by
   a. the vestibule.
   b. the modiolus.
   c. the stapes.
   d. the stapedius.
   e. the superior rectus.
5. The sensory neurons that begin in the spiral organ of the ear end in
   a. the spiral ganglion.
   b. the cochlear nucleus.
   c. the superior olivary nucleus.
   d. the inferior colliculus.
   e. the temporal lobe.
6. The spiral organ rests on
   a. the tympanic membrane.
   b. the secondary tympanic membrane.
   c. the tectorial membrane.
   d. the vestibular membrane.
   e. the basilar membrane.
7. The acceleration you feel when an elevator begins to rise is sensed by
   a. the anterior semicircular duct.
   b. the spiral organ.
   c. the crista ampullaris.
   d. the macula sacculi.
   e. the macula utriculi.
8. The highest density of cone cells is found in
   a. the crista ampullaris.
   b. the optic disc.
   c. the fovea centralis.
   d. the chorion.
   e. the basilar membrane.
9. The dilated blood vessels seen in “bloodshot” eyes are vessels of
   a. the retina.
   b. the cornea.
   c. the conjunctiva.
   d. the sclera.
   e. the choroid.
10. A person would look cross-eyed if _____ muscles contracted at once.
    a. both medial rectus
    b. both lateral rectus
    c. the right medial rectus and left lateral rectus
    d. both superior oblique
    e. the left superior oblique and right inferior oblique
11. The most finely detailed vision occurs when an image falls on a pit in the retina called the _____.
12. Fibers of the optic nerve come from the _____ cells of the retina.
13. A sensory nerve ending specialized to detect tissue injury and produce a sensation of pain is called a/an _____.
14. The gelatinous membranes of the macula sacculi and macula utriculi are weighted by calcium carbonate–protein granules called _____.
15. Three rows of _____ in the cochlea have V-shaped arrays of stereocilia and tune the frequency sensitivity of the cochlea.
16. The _____ is a tiny bone that vibrates in the oval window and thereby transfers sound vibrations to the inner ear.
17. The _____ of the midbrain receive auditory input and trigger the head-turning auditory reflex.
18. The apical microvilli of a gustatory cell are called _____.
19. Olfactory neurons synapse with mitral cells and tufted cells in the _____, which lies inferior to the frontal lobe.
20. In the phenomenon of _____, pain from the viscera is perceived as coming from an area of the skin.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. noci-
2. an-
3. fili-
4. oto-
5. trochle-
6. fovea
7. alges-
8. -ate
9. tympano-
10. -stomy

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. Interoceptors belong to the general senses.
2. The sensory (afferent) neurons for touch end in the thalamus.
3. The right cerebral hemisphere perceives things we touch with our left hand.
4. The optic nerve is composed of the axons of the rod and cone cells.
5. Filiform papillae of the tongue have no taste buds.
6. Some chemoreceptors are exteroceptors and some are interoceptors.

7. Humans have more photoreceptor cells than taste cells.
8. Human neurons are never exposed to the external environment of the body.
9. The tympanic membrane has no nerve fibers.
10. The vitreous body occupies the posterior chamber of the eye.

Answers in appendix A

Testing Your Comprehension

1. The principle of neural convergence was explained in chapter 13. Discuss its relevance to referred pain and scotopic vision.
2. What type of cutaneous receptor enables you to feel an insect crawling through your hair? What type enables you to palpate a patient's pulse? What type would give you a feeling that your belt is too tight?
3. Predict the consequences of a hypothetical disorder in which the eye begins to break down or reabsorb the gel of the vitreous body.
4. Suppose a virus was able to selectively invade and destroy the following nervous tissues. Predict the sensory consequences of each infection: (a) the spiral ganglion, (b) the vestibular nucleus, (c) the motor fibers of cranial nerve VIII, (d) the motor fibers of cranial nerve VII, (e) the posterior horns of spinal cord segments L3 through S5.
5. Summarize the similarities and differences between olfactory cells and taste cells.



An ovarian follicle (SEM). Layered cells of the follicle wall secrete steroid hormones.

© P. Bagavandoss/Science Source

CHAPTER 18

THE ENDOCRINE SYSTEM

CHAPTER OUTLINE

18.1 Overview of the Endocrine System 498
- Comparison of Endocrine and Exocrine Glands 498
- Comparison of the Endocrine and Nervous Systems 498

18.2 The Hypothalamus and Pituitary Gland 500
- Anatomy 500
- Hypothalamic Hormones 502
- Anterior Pituitary Hormones 502
- Posterior Pituitary Hormones 503

18.3 Other Endocrine Glands 504
- The Pineal Gland 504
- The Thymus 505
- The Thyroid Gland 505
- The Parathyroid Glands 506
- The Adrenal Glands 507
- The Pancreatic Islets 508
- The Gonads 509
- Endocrine Cells in Other Tissues and Organs 510

18.4 Developmental and Clinical Perspectives 512
- Prenatal Development of the Endocrine Glands 512
- The Aging Endocrine System 514
- Endocrine Disorders 515

Study Guide 516

DEEPER INSIGHTS

18.1 Empty Sella Syndrome 500
18.2 A Lethal Effect of Postsurgical Hypoparathyroidism 506

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:
- Embryonic development of the pharyngeal pouches (p. 92)
- Embryonic development of the neural crest (pp. 365–366)
- The hypothalamus (p. 415)

Anatomy & Physiology REVEALED®
aprevealed.com

Module 8: Endocrine System

If the body is to function as an integrated whole, its organs must communicate with each other and coordinate their activities. Even simple organisms of just a few cells have mechanisms for intercellular communication. Complex animals such as ourselves achieve this through the nervous and endocrine systems, which communicate with neurotransmitters and hormones, respectively.

Nearly everyone has heard of at least some hormones, such as growth hormone, thyroid hormone, estrogen, and insulin. At least passingly familiar, too, are some of the glands that secrete them (the pituitary and thyroid glands, for example) and some of the disorders that result from hormone excesses, deficiencies, or dysfunctions (diabetes, goiter, dwarfism, and many others). This chapter surveys the glands and cells that produce the human hormones, with emphasis on their gross anatomy and histology. While the emphasis of this book is not on physiology or pathology, we will also include here some cursory insights into what hormones are, how they act, how they change over the life span, and a few of the many things that can go wrong with this system.

18.1 Overview of the Endocrine System

Expected Learning Outcomes

When you have completed this section, you should be able to

a. define *hormone* and *endocrine system;*
b. explain the concept of target organs;
c. describe how endocrine glands differ from exocrine glands; and
d. compare and contrast the endocrine and nervous systems.

Hormones[1] are chemical messengers secreted into the bloodstream that stimulate physiological responses in distant organs. Their sources include a classic inventory of **endocrine glands** depicted in figure 18.1, but also include specialized secretory cells found in many tissues and organs not usually thought of as glands—including the brain, heart, small intestine, and adipose tissue. The **endocrine system** consists of all of these hormone-producing cells and glands. The study and treatment of this system are called **endocrinology.**

Endocrine glands have an unusually high density of blood capillaries, which serve to pick up and carry away their hormones. These vessels are an especially permeable type called *fenestrated capillaries,* which have patches of large pores in their walls allowing for the easy uptake of matter from the gland tissue (see fig. 21.6, p. 569).

Once a hormone enters the bloodstream, it goes wherever the blood goes; there is no way to send it selectively to a particular organ. However, the only organs or cells that respond to it are those with receptors for that hormone. We call these the **target organs** or **target cells**. Thyroid-stimulating hormone, for example, circulates everywhere the blood goes, but only the thyroid gland responds to it.

Comparison of Endocrine and Exocrine Glands

In chapter 3, we examined another category of glands, the *exocrine* glands. The classical distinction between exocrine and endocrine glands is the presence or absence of ducts, respectively. Most exocrine glands secrete their products by way of a duct onto an epithelial surface such as the skin or intestinal mucosa (see fig. 3.29, p. 76); sweat glands and salivary glands are good examples. By contrast, endocrine glands such as the pituitary and thyroid are ductless and release their secretions (hormones) into the bloodstream. For this reason, hormones were originally called the body's "internal secretions"; the word *endocrine*[2] still alludes to this fact. Some glands, such as the pancreas, contain both exocrine and endocrine components.

Some glands and secretory cells defy any classification as simple as exocrine versus endocrine. Liver cells, for example, behave as exocrine cells in the traditional sense when they secrete bile into ducts that lead ultimately to the small intestine. However, they also secrete hormones directly into the blood, and in this respect they act as endocrine cells. They secrete albumin and blood-clotting factors directly into the blood as well. These don't fit the traditional concept of exocrine secretions, because they are not released by way of ducts; nor do they fit the concept of endocrine secretions, because they are not hormones. Liver cells are just one of nature's myriad ways of confounding our impulse to rigidly classify things.

Comparison of the Endocrine and Nervous Systems

The nervous and endocrine systems both serve for internal communication, but they are not redundant; they complement rather than duplicate each other's functions. One important difference is the speed with which they start and stop responding to a stimulus. The nervous system typically responds within a few milliseconds, whereas it takes from several seconds to days for a hormone to act. When a stimulus ceases, the nervous system stops responding almost immediately, whereas hormonal effects can last for days or even longer. Another difference is that an efferent nerve fiber innervates only one organ and a limited number of cells within that organ, so its effects are usually precisely targeted and relatively specific. Some hormones, by contrast, have very widespread effects on the body, such as thyroid hormone and growth hormone.

The differences, however, should not blind us to the similarities and interactions between the two systems. Both communicate chemically, and several chemicals function as both hormones and neurotransmitters—for example, norepinephrine, dopamine, and cholecystokinin. Thus, a particular chemical such as dopamine can be regarded as a hormone when it is secreted by the adrenal gland

---

[1] *hormone* = to excite, set in motion

[2] *endo* = internal; *crin* = to secrete



Figure 18.1 **Major Organs of the Endocrine System.** This system also includes gland cells in many organs not shown here.
- *After reading this chapter, name at least three hormone-secreting organs that are not shown in this illustration.* AP|R

or as a neurotransmitter when it is secreted by a neuron of the brain. Another similarity is that some hormones and neurotransmitters produce identical effects on the same target cells. For example, both norepinephrine and glucagon stimulate the liver to break down glycogen and release glucose.

The nervous and endocrine systems continually regulate each other as they coordinate the activities of other organ systems. Some neurons trigger hormone secretion, and some hormones stimulate or inhibit neurons.

Some cells defy any attempt to rigidly classify them as neurons or gland cells. They act like neurons in many respects, but like endocrine cells, they release their secretions (such as oxytocin) into the blood. Thus, we give them a hybrid name—**neuroendocrine cells.**

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. Define the word *hormone.* Compare hormones and neurotransmitters (see chapter 13). What do they have in common? How do they differ?
2. Define the term *target cell.*
3. Compare and contrast exocrine and endocrine glands. Explain why this is an imperfect distinction.
4. How do the nervous and endocrine systems differ? How are they alike? What are some ways in which they overlap each other's functions and interact with each other?

18.2 The Hypothalamus and Pituitary Gland

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the location and anatomy of the pituitary gland and its anatomical relationship with the hypothalamus;
b. explain how the hypothalamus controls pituitary function; and
c. list the hormones produced by the two lobes of the pituitary gland and state their functions.

There is no master control center that regulates the entire endocrine system, but the pituitary gland and a nearby region of the brain, the hypothalamus, do regulate much of it. They are an appropriate place to start our survey of endocrine glands.

Anatomy

The **hypothalamus,** shaped like a flattened funnel, forms the floor and walls of the third ventricle of the brain; it is further detailed in chapter 15 (see p. 415). It regulates primitive functions of the body ranging from water balance to sex drive and carries out many of its roles by way of the pituitary gland.

The **pituitary gland (hypophysis**[3]**)** is attached to the hypothalamus by a stalk and is partially enclosed in the saddlelike *sella turcica* of the sphenoid bone (described on p. 162). It is an ovoid gland about 1.3 cm wide (approximately the size of a kidney bean), but grows 50% larger during pregnancy. Although it looks like a single gland on casual inspection, its histology and embryology show it to be composed of two lobes—the *anterior* and *posterior pituitary*—with independent origins and separate functions. In the fetus, there is a strip of tissue called *the pars intermedia* ("intermediate part") between the two lobes, but during subsequent development, its cells mingle with those of the anterior lobe. There is no longer a separate pars intermedia in adults.

The **anterior pituitary,** also called the *anterior lobe* or *adenohypophysis*[4] (AD-eh-no-hy-POFF-ih-sis), is the anterior three-quarters of the pituitary (fig. 18.2). It has three classes of cells (fig. 18.3a): **acidophils** and **basophils,** which stain darkly with acidic and basic dyes, respectively; and **chromophobes,**[5] which take up little dye and appear relatively pale. Acidophils and basophils secrete the anterior pituitary hormones. There are at least five subclasses of these cells, but they are indistinguishable with ordinary histological stains. Chromophobes exhibit little or no secretory activity and are of uncertain function. Some of them may be stem cells that give rise to acidophils and basophils.

The anterior pituitary has no nervous connection to the hypothalamus, but is linked to it by a complex of blood vessels called the **hypophyseal portal system.** In circulatory anatomy, a portal system is a route in which blood flows through two capillary beds, one after another, before returning to the heart. The pituitary gland is fed by a *superior hypophyseal artery,* which breaks up into a bed of *primary capillaries* in the hypothalamus. These capillaries drain into *portal venules* (small veins) that travel down the pituitary stalk to a bed of *secondary capillaries* in the anterior pituitary. The hypothalamus controls the pituitary by secreting hormones that enter the primary capillaries, travel down the portal venules, and leave the secondary capillaries when they get to the anterior lobe. Some of these hormones stimulate the pituitary to release its own hormones, and others inhibit it.

The **posterior pituitary,** also called the *posterior lobe* or *neurohypophysis,* is the posterior one-quarter of the pituitary. The **stalk (infundibulum)** that connects the pituitary to the hypothalamus is part of the posterior lobe. The posterior pituitary is not a true gland but a mass of nervous tissue—neuroglia intermingled with axons that arise from certain hypothalamic neuroendocrine cells (fig. 18.3b). The axons travel through the stalk as a bundle called the **hypothalamo–hypophyseal tract** and end in the posterior lobe. The neurons in the hypothalamus secrete hormones that are transported down the axons and stored in the posterior lobe. Later, a nerve signal traveling down the same axons can trigger the release of these hormones into the blood.

DEEPER INSIGHT 18.1

Empty Sella Syndrome

A radiologist normally expects to see the pituitary gland "at home" in the sella turcica, but sometimes in the course of tests for pituitary disorders, a CT or MRI scan reveals an empty sella turcica and seeming absence of a pituitary. This is called *empty sella syndrome (ESS).* Given the vital importance of the pituitary gland, ESS might seem to be a life-threatening condition, yet it is often associated with no endocrine dysfunctions and it usually requires no treatment. More than three-quarters of ESS patients are obese women, and many are hypertensive. Many of these patients have elevated fluid pressure within the cranium, and some even seep cerebrospinal fluid from the nose. Elevated intracranial pressure can flatten the pituitary tissue against the wall of the sella turcica, creating the appearance of an empty sella even though the pituitary is present and functional. Some cases of ESS, however, result from the shrinkage of pituitary tissue following surgery, radiation therapy, or trauma. These cases are more often associated with systemic endocrine dysfunctions and may require hormone replacement therapy.

---

[3] *hypo* = below; *physis* = growth

[4] *adeno* = gland

[5] *chromo* = color, dye; *phob* = fearing, repelling


Anterior
Posterior
Third ventricle of brain
Floor of hypothalamus
Nuclei of hypothalamus:
Paraventricular nucleus
Supraoptic nucleus
Optic chiasm
Anterior pituitary
Stalk
Posterior pituitary
Oxytocin
Antidiuretic hormone
(a)
Axons to primary capillaries
Neuron cell body
Primary capillaries
Superior hypophyseal artery
Hypothalamic hormones
Gonadotropin-releasing hormone
Thyrotropin-releasing hormone
Corticotropin-releasing hormone
Prolactin-inhibiting hormone
Growth hormone–releasing hormone
Somatostatin
Portal venules
Secondary capillaries
Anterior pituitary
Posterior pituitary
Anterior lobe hormones
Follicle-stimulating hormone
Luteinizing hormone
Thyroid-stimulating hormone (thyrotropin)
Adrenocorticotropic hormone
Prolactin
Growth hormone
(b)

Figure 18.2 **Anatomy of the Pituitary Gland.** (a) Major structures of the pituitary as a whole, and hormones of the posterior lobe. Note that these hormones are produced by two nuclei of neuroendocrine cells in the hypothalamus and later released from the posterior lobe. (b) The hypophyseal portal system. The hormones in the violet box are secreted by the hypothalamus and travel in the portal blood vessels to the anterior pituitary. The hormones in the pink box are secreted by the anterior pituitary under the control of these releasing and inhibiting hormones from the hypothalamus.

- *Which pituitary lobe is essentially composed of brain tissue?* APR



(a) Anterior pituitary

© Biophoto Associates/Science Source

(b) Posterior pituitary

© Biophoto Associates/Science Source

Figure 18.3 **Histology of the Pituitary Gland.** (a) The anterior lobe. Basophils include gonadotropes, thyrotropes, and corticotropes. Acidophils include somatotropes and lactotropes. These subtypes are not distinguishable with this histological stain. The chromophobes resist staining, and their function is not yet known. (b) The posterior lobe, composed of nervous tissue.

Hypothalamic Hormones

We now survey the hormones produced by these three regions—the hypothalamus, anterior lobe, and posterior lobe—including brief descriptions of the most basic functions of each hormone.

The hypothalamus produces six hormones that regulate the anterior pituitary (fig. 18.2 and table 18.1). Four of these are *releasing hormones,* which stimulate the anterior pituitary to secrete its hormones; two of them are *inhibiting hormones,* which suppress pituitary secretion. In most cases, the name of the hypothalamic hormone indicates the pituitary hormone whose secretion it stimulates or inhibits; *thyrotropin-releasing hormone,* for example, stimulates the anterior pituitary to release *thyrotropin.* Gonadotropin-releasing hormone controls both *follicle-stimulating hormone* and *luteinizing hormone,* collectively called *gonadotropins. Growth hormone–inhibiting hormone (GHIH)* is also known as *somatostatin*. The other two hypothalamic hormones—**oxytocin (OT)** and **antidiuretic hormone (ADH)**—are synthesized in the brain but stored and secreted by the posterior pituitary. They will be discussed later in connection with posterior pituitary function.

Anterior Pituitary Hormones

The anterior lobe of the pituitary gland synthesizes and secretes six principal hormones (table 18.2). The first four of these are called **tropic**[6] or **trophic**[7] hormones because they stimulate the growth of other endocrine glands. The first two, targeted to the gonads, are called **gonadotropins.** Figure 18.4 shows the relationships of these hormones to their downstream target organs.

1. **Follicle-stimulating hormone (FSH).** FSH is secreted by pituitary cells called *gonadotropes,* in the basophil class. Its target organs are the ovaries and testes. In the ovaries, it stimulates the secretion of ovarian hormones and the development of the bubblelike *follicles* that contain the eggs. In the testes, it stimulates the production of sperm.
2. **Luteinizing hormone (LH).** LH is also secreted by the gonadotropes. In females, it stimulates *ovulation* (the release of an egg). LH is named for the fact that after ovulation, it stimulates the remainder of the follicle to develop into a yellowish body called the **corpus luteum.**[8] It also stimulates the corpus luteum to secrete progesterone, a hormone important in pregnancy. In males, LH stimulates the testes to secrete testosterone.
3. **Thyroid-stimulating hormone (TSH),** or **thyrotropin.** TSH is secreted by basophils called *thyrotropes.* It stimulates growth of the thyroid gland and the secretion of thyroid hormone, whose effects are described later.
4. **Adrenocorticotropic hormone (ACTH),** or **corticotropin.** ACTH is secreted by basophils called *corticotropes.* It is important in regulating the body's response to stress. It is named for its effect on the adrenal cortex, the outer layer of an endocrine gland near the kidney. ACTH stimulates the adrenal cortex to secrete hormones called *glucocorticoids,* discussed later.

TABLE 18.1 **Hypothalamic Releasing and Inhibiting Hormones That Regulate the Anterior Pituitary**

Hypothalamic Hormone	Principal Effects on Anterior Pituitary
Thyrotropin-releasing hormone (TRH)	Promotes secretion of thyroid-stimulating hormone and prolactin
Corticotropin-releasing hormone (CRH)	Promotes secretion of adrenocorticotropic hormone
Gonadotropin-releasing hormone (GnRH)	Promotes secretion of follicle-stimulating hormone and luteinizing hormone
Growth hormone–releasing hormone (GHRH)	Promotes secretion of growth hormone
Growth hormone–inhibiting hormone (GHIH) (somatostatin)	Inhibits secretion of growth hormone and thyroid-stimulating hormone
Prolactin-inhibiting hormone (PIH)	Inhibits secretion of prolactin

---

[6] *trop* = to turn, change
[7] *troph* = to feed, nourish
[8] *corpus* = body; *lute* = yellow

TABLE 18.2 Pituitary Hormones

Hormone	Target Organs	Principal Effects
Anterior pituitary		
Follicle-stimulating hormone (FSH)	Ovaries, testes	Female: growth of ovarian follicles and secretion of estrogen Male: sperm production
Luteinizing hormone (LH)	Ovaries, testes	Female: ovulation, production and maintenance of corpus luteum Male: testosterone secretion
Thyroid-stimulating hormone (TSH)	Thyroid gland	Growth of thyroid, secretion of thyroid hormone
Adrenocorticotropic hormone (ACTH)	Adrenal cortex	Growth of adrenal cortex, secretion of glucocorticoids
Prolactin (PRL)	Mammary glands, testes	Female: milk synthesis Male: increased LH sensitivity and testosterone secretion
Growth hormone (GH)	Liver, bone, cartilage, muscle, fat	Widespread tissue growth, especially in the stated tissues
Posterior pituitary		
Antidiuretic hormone (ADH)	Kidneys	Water retention
Oxytocin (OT)	Uterus, mammary glands, brain	Labor contractions, milk release; possibly involved in ejaculation, sperm transport in the female, sexual affection, and parent–offspring bonding

5. **Prolactin**[9] **(PRL).** PRL is secreted by acidophils called *lactotropes (mammotropes),* which increase greatly in size and number during pregnancy. They secrete PRL during pregnancy and for as long as a woman nurses, although PRL has no effect on the mammary glands until after she gives birth. Then, it stimulates them to synthesize milk. The physiological significance of PRL in males remains uncertain. A tumor of the lactotropes sometimes causes milk secretion in men and in women who are not nursing; this condition is called *galactorrhea.*
6. **Growth hormone (GH),** or **somatotropin.** GH is secreted by acidophils called *somatotropes,* the most numerous cells in the anterior pituitary. The pituitary produces at least a thousand times as much GH as any other hormone. Unlike the foregoing hormones, it is not targeted to one or a few organs, but has widespread effects on the body, especially on cartilage, bone, muscle, and fat. Its general effect is to promote mitosis and cellular differentiation and thus to promote widespread tissue growth. GH not only stimulates the foregoing tissues directly, but also stimulates the liver and other tissues to secrete **insulin-like growth factors (somatomedins**[10]**),** or **IGFs.** IGFs stimulate the same target organs as GH (fig. 18.4). Together, they support tissue growth by mobilizing energy from fat, increasing levels of calcium and other electrolytes, and stimulating protein synthesis. Their most conspicuous effects occur during childhood and adolescence. They continue to function in energy metabolism and tissue maintenance throughout adult life, but adults suffer no ill effects from a GH deficiency.

Posterior Pituitary Hormones

The two posterior lobe hormones are ADH and OT. Both are synthesized in the hypothalamus, transported down the stalk, stored in the posterior pituitary, and released on demand (fig. 18.2).

1. **Antidiuretic**[11] **hormone (ADH).** ADH is synthesized primarily in a pair of neuron clusters called the **supraoptic nuclei,** located on the left and right sides of the hypothalamus just above the optic chiasm. ADH increases water retention by the kidneys, reduces urine volume, and helps prevent dehydration. It is also called *arginine vasopressin* because it can cause vasoconstriction. This requires concentrations so unnaturally high for the human body, however, that this effect is of doubtful significance except in pathological states. ADH also functions as a brain neurotransmitter and is usually called arginine vasopressin in the neuroscience literature.
2. **Oxytocin**[12] **(OT).** OT is synthesized primarily by a pair of hypothalamic nuclei called the **paraventricular nuclei,** located in the left and right walls of the third ventricle. It has a variety of reproductive roles. In childbirth, it stimulates labor contractions, and in lactating mothers, it stimulates the flow of milk to the nipple, making it accessible to the nursing infant. In both sexes, OT surges during sexual arousal and orgasm; this surge may play a role in the propulsion of semen through the male reproductive tract and in uterine contractions that help transport sperm up the female reproductive tract. It also evidently functions in feelings of sexual satisfaction and emotional bonding between partners and in maternal bonding with an infant. In the absence of oxytocin, female mammals tend to neglect their helpless infants.

---

[9] *pro* = favoring; *lact* = milk
[10] Acronym for *soma*totropin *med*iating prote*in*
[11] *anti* = against; *diuret* = to pass through, urinate
[12] *oxy* = sharp, quick; *toc* = childbirth



Figure 18.4 **Hormones and Target Organs of the Anterior Pituitary Gland.** Hypothalamic releasing hormones, shown at the top, stimulate secretion of all of the anterior pituitary hormones (bottom).

Before You Go On

Answer the following questions to test your understanding of the preceding section:

5. What are two good reasons for considering the pituitary to be two separate glands?
6. Describe two anatomical routes by which the hypothalamus sends signals to the pituitary gland.
7. Construct a three-column table. In the middle column, list the six hormones of the anterior pituitary gland. On the left, list the hypothalamic hormones that control these pituitary secretions. On the right, list the target organ and effect of each anterior pituitary hormone.
8. Name the two hormones released by the posterior lobe of the pituitary, state where they are produced, and state their functions.

18.3 Other Endocrine Glands

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the structure and location of the remaining endocrine glands;
b. name the hormones that these endocrine glands produce and state their functions; and
c. discuss the roles of endocrine cells in organs other than the classic endocrine glands.

The Pineal Gland

The **pineal**[13] **gland (epiphysis cerebri)** is attached to the roof of the third ventricle beneath the posterior end of the corpus callosum

---

[13] *pineal* = pine cone

(see fig. 15.2, p. 401, and fig. 18.1). Its name alludes to a shape resembling a pine cone. The philosopher René Descartes (1596–1650) thought it was the seat of the human soul. If so, children must have more soul than adults—a child's pineal gland is about 8 mm long and 5 mm wide, but after age 7, it regresses rapidly and is no more than a shrunken mass of fibrous tissue in the adult. Pineal secretion peaks between the ages of 1 and 5 years; by the end of puberty, it declines 75%. Such shrinkage of an organ is called **involution.** It is accompanied by the appearance of calcified granules called *pineal sand.* These granules are visible on X-rays, enabling radiologists to determine the position of the gland. Displacement of the pineal from its normal location can be evidence of a brain tumor or other structural abnormality.

We no longer look for the human soul in the pineal gland, but this little organ remains an intriguing mystery with obscure functions. During the night, it synthesizes **melatonin,** which may suppress gonadotropin secretion and prevent premature sexual maturation (see p. 515). The pineal is also thought to play a role in our 24-hour *circadian rhythms* of physiological function synchronized with the cycle of daylight and darkness. It may be involved in human mood disorders such as premenstrual syndrome and seasonal affective disorder.

The Thymus

The **thymus** plays a role in three systems: endocrine, lymphatic, and immune. It is a bilobed gland in the mediastinum superior to the heart, behind the sternal manubrium. In the fetus and infant, it is enormous in comparison to adjacent organs, sometimes protruding between the lungs nearly as far as the diaphragm and extending upward into the neck (fig. 18.5a). It continues to grow until the age of 5 or 6 years, although not as fast as other thoracic organs, so its *relative* size decreases. After the age of 14, it undergoes rapid involution. It weighs about 20 g up to age 60, but it becomes increasingly fatty and less glandular with age. In the elderly, it is a small fibrous and fatty remnant barely distinguishable from the surrounding mediastinal tissues (fig. 18.5b).

The thymus is a site of maturation for certain white blood cells that are critically important for immune defense (T lymphocytes, *T* for *thymus*). It secretes several hormones (**thymopoietin, thymosin,** and **thymulin**) that stimulate the development of other lymphatic organs and regulate the development and activity of the T lymphocytes. Its histology is discussed more fully in chapter 22 in relation to its immune function.

The Thyroid Gland

The **thyroid gland** is the largest adult gland to have purely endocrine functions; it weighs 20 to 25 g. It is composed of two lobes that wrap like a butterfly around the trachea, immediately below the larynx (fig. 18.6a). It is named for the nearby, shieldlike *thyroid*[14] *cartilage* of the larynx. Each lobe of the gland is bulbous at the inferior end and tapers superiorly. Near the inferior end, the two lobes are joined by a narrow bridge of tissue, the **isthmus,** which crosses the front of the trachea. About 50% of people have an accessory *pyramidal lobe,* usually small, growing upward from the isthmus. Some people lack an isthmus, and some have thyroid tissue embedded in the root of the tongue, the thymus, or other places in the neck.

The thyroid gland receives one of the body's highest rates of blood flow per gram of tissue. Its abundant blood vessels give the gland a dark reddish brown color. It is supplied by a pair of *superior thyroid arteries* that arise from the external carotid arteries of the neck, and a pair of *inferior thyroid arteries* that arise from the subclavian arteries near the clavicles. It is drained by two to three pairs of thyroid veins (*superior, middle,* and *inferior*), which flow into the internal jugular and brachiocephalic veins.

---

[14] *thyr* = shield; *oid* = like, resembling



(a) Newborn

(b) Adult

Figure 18.5 **The Thymus.** (a) The neonatal thymus is deeper red than the adult thymus because of a richer blood flow. (b) In the thymus of an older adult, circulation is greatly reduced and much of the glandular tissue is replaced with fat and fibrous tissue.



© Biophoto Associates/Science Source

Figure 18.6 **The Thyroid Gland.** (a) Gross anatomy, anterior view. Major blood vessels are shown only on the anatomical right. (b) Histology, showing the saccular thyroid follicles (source of thyroid hormone) and a nest of C cells.

- *What is the function of the C cells?* AP|R

The main histological feature of the thyroid is that it is composed mostly of sacs called **thyroid follicles** (fig. 18.6b), which are lined by a simple cuboidal epithelium of **follicular cells** and filled with a protein-rich colloid. Follicular cells secrete mainly the hormone **thyroxine,** also known as **tetraiodothyronine** (TET-ra-EYE-oh-doe-THY-ro-neen), or **T_4,** because it has four iodine atoms in its structure. The thyroid also produces **triiodothyronine** (try-EYE-oh-doe-THY-ro-neen), or **T_3,** with three iodine atoms. The expression **thyroid hormone (TH)** refers to T_4 and T_3 collectively.

Thyroid hormone stimulates prenatal and childhood brain development and bone growth, promotes pituitary secretion of growth hormone, quickens the somatic reflexes, raises the heart rate and metabolic rate, promotes intestinal absorption of carbohydrates, and lowers the plasma cholesterol level. TH also stimulates one's metabolic rate and makes a significant contribution to the body's heat production. This is called the **calorigenic**[15] **effect.**

The thyroid gland also contains nests of less numerous **C (clear) cells,** or **parafollicular cells,** at the periphery of the follicles. They secrete the hormone **calcitonin** when the blood calcium level rises above normal (a state called *hypercalcemia*). Calcitonin tips the balance between bone deposition and resorption in favor of deposition, and the blood calcium level falls as calcium is incorporated into the bones. This effect, however, is significant only in children; in healthy adults, the effect of calcitonin is negligible.

The Parathyroid Glands

The **parathyroid glands** are small ovoid glands in the neck measuring about 3 to 8 mm long and 2 to 5 mm wide. Usually there are four of them, but about 5% of people have more. They most often adhere to the posterior side of the thyroid gland in the approximate positions shown in figure 18.7a, but the parathyroids are highly variable in location and not always attached to the thyroid. They can occur as far superiorly as the hyoid bone and as far inferiorly as the aortic arch. They have a thin fibrous capsule separating them from the thyroid tissue (fig. 18.7b). They are supplied with blood and drained by the same vessels as the thyroid gland.

Hypocalcemia, a calcium deficiency, stimulates the **chief cells** of the parathyroids to secrete **parathyroid hormone (PTH).** PTH raises blood calcium levels by promoting intestinal calcium absorption, inhibiting urinary calcium excretion, and indirectly stimulating osteoclasts to resorb bone.

DEEPER INSIGHT 18.2

A Lethal Effect of Postsurgical Hypoparathyroidism

Thyroid cancer and other dysfunctions sometimes require the surgical removal of thyroid tissue. Because of their variable location and small size, the parathyroid glands are sometimes accidentally removed along with it. Without hormone replacement therapy, the lack of parathyroid hormone *(hypoparathyroidism)* leads to a rapid decline in blood calcium levels. *Hypocalcemia,* a deficiency of blood-borne calcium, makes the skeletal muscles overly excitable and prone to exhibit spasmodic contractions called *hypocalcemic tetany.* One sign of this is spasmodic flexion of the hands and feet *(carpopedal spasm).* A more serious effect is tetany of the laryngeal muscles, closing off the airway and causing suffocation. A patient can die in as little as 3 or 4 days without treatment. Because of this danger, surgeons usually try to leave the posterior part of the thyroid gland intact.

---

[15] *calori* = heat; *genic* = producing



© Michael Ross/Science Source

Figure 18.7 **The Parathyroid Glands.** (a) There are usually four parathyroid glands embedded in the posterior surface of the thyroid gland. (b) Histology. AP|R

The Adrenal Glands

An **adrenal (suprarenal) gland** is attached to the superior to medial aspect of each kidney (fig. 18.8). The right adrenal gland is more or less triangular and rests on the superior pole of the kidney. The left adrenal gland is more crescent-shaped and extends from the medial indentation (hilum) of the kidney to its superior pole. Like the kidneys, the adrenal glands are retroperitoneal, lying outside the peritoneal cavity between the peritoneum and posterior body wall. Each adult adrenal gland measures about 5 cm high, 3 cm wide, and 1 cm from anterior to posterior. It weighs 7 to 10 g in adults but about twice this much in the newborn. By the age of 2 months, its weight drops about 50%, mostly because of involution of the outer layer, the adrenal cortex.

Like the pituitary, the adrenal gland forms by the merger of two fetal glands with different origins and functions. Its inner core, the **adrenal medulla,** is 10% to 20% of the gland. Depending on blood flow, its color ranges from gray to dark red. Surrounding it is a much thicker **adrenal cortex,** constituting 80% to 90% of the mass of the gland and having a yellowish color due to its high concentration of cholesterol and other lipids. The entire gland is enclosed in a fibrous capsule.

The adrenal gland receives blood from three arteries: a *superior suprarenal artery* arising from the phrenic artery of the diaphragm; a *middle suprarenal artery* arising from the aorta; and an *inferior suprarenal artery* arising from the renal artery of the kidney. It is drained by a *suprarenal vein,* which empties from the right adrenal gland into the inferior vena cava and from the left adrenal gland into the left renal vein.

The Adrenal Medulla

The adrenal medulla has a dual nature, acting as both an endocrine gland and a ganglion of the sympathetic nervous system (see p. 450). Sympathetic preganglionic nerve fibers penetrate through the adrenal cortex to reach **chromaffin** (cro-MAFF-in) **cells** in the adrenal medulla. These cells, named for their tendency to stain brown with certain dyes, are essentially sympathetic postsynaptic neurons. However, they have no axon or dendrites, and they release their products directly into the bloodstream like any other endocrine gland; thus, they are considered to be neuroendocrine cells. Upon stimulation by the nerve fibers, they secrete a mixture of **epinephrine, norepinephrine,** and **dopamine.** Secretion rises in conditions of fear, pain, and other kinds of stress, and they mimic and supplement the arousing effects of the sympathetic nervous system. Among other effects, they raise the metabolic rate, increase the heart rate and contraction strength, and mobilize glucose and fatty acids to meet the body's elevated energy requirement.

The Adrenal Cortex

The adrenal cortex surrounds the medulla on all sides. It produces more than 25 steroid hormones, known collectively as the **corticosteroids** or **corticoids.** All of them are synthesized from cholesterol, which, along with other lipids, imparts a yellow color to the cortex. Only five corticosteroids are physiologically significant for present purposes. The cortex is composed of three layers of tissue, which differ in their histology and hormone output (fig. 18.8b).

1. The **zona glomerulosa**[16] (glo-MER-you-LO-suh) is a thin layer, less developed in humans than in some other mammals, located just beneath the capsule at the gland surface. The name *glomerulosa* ("full of little balls") refers to the arrangement of

---

[16] *glomerul* = little ball; *osa* = full of



© Victor Eroschenko

Figure 18.8 **The Adrenal Gland.** (a) Location and gross anatomy. (b) Drawing and photograph of adrenal histology. AP|R

its cells in little round clusters. The zona glomerulosa secretes a family of hormones called *mineralocorticoids*.

2. The **zona fasciculata**[17] (fah-SIC-you-LAH-ta) is a thick middle layer constituting about three-quarters of the cortex. Here the cells are arranged in parallel cords (fascicles), separated by blood capillaries, perpendicular to the adrenal surface. The cells of the fasciculata are called **spongiocytes** because of a foamy appearance caused by their abundance of cytoplasmic lipid droplets. This zone secretes hormones called *glucocorticoids* and *sex steroids*.
3. The **zona reticularis**[18] (reh-TIC-you-LAR-iss) is the narrow, innermost layer, adjacent to the adrenal medulla. Its cells form a branching network for which the zone is named. This layer secretes sex steroids—**androgens** and smaller amounts of **estrogens.** Androgens are present and important in both sexes but are named for their best-known effect—stimulating many aspects of male development and reproductive physiology. The androgens of the adrenal cortex are **dehydroepiandrosterone (DHEA)** (dee-HY-dro-EP-ee-an-DROSS-ter-own) and **androstenedione** (AN-dro-STEEN-di-own). These are similar to testosterone but less potent. They stimulate the prenatal development of the male reproductive tract; the growth of pubic and axillary hair and apocrine scent glands in puberty in both sexes; and the libido (sex drive) of both sexes in adolescence and adulthood.

Aldosterone is the most significant mineralocorticoid, and is secreted only by the zona glomerulosa. It acts on the kidneys to retain sodium in the body fluids and excrete potassium in the urine. Since water is retained with the sodium by osmosis, aldosterone helps to maintain blood volume and pressure. **Cortisol (hydrocortisone),** the most potent glucocorticoid, is secreted by the zona fasciculata and zona reticularis. It stimulates fat and protein breakdown, glucose synthesis, and the release of fatty acids and glucose into the blood. It helps the body adapt to stress and to rebuild damaged tissues. **Androgens** and **estrogens** are sex steroids secreted by the zona fasciculata and zona reticularis. The adrenal androgens are testosterone relatives concerned with reproductive development and behavior and with maintenance of bone mass. In men, the large amount of androgen secreted by the testes overshadows that of the adrenals, but in women, the adrenal glands meet about 50% of the androgen requirement. Adrenal estrogen is normally of minor importance in women of reproductive age because its quantity is small compared to that produced by the ovaries. After menopause, however, the ovaries no longer function and only the adrenals secrete estrogen.

Apply What You Know

The zona fasciculata thickens significantly in pregnant women. What do you think would be the benefit of this phenomenon?

The Pancreatic Islets

The **pancreas** is an elongated, spongy gland located below and behind the stomach; most of it is retroperitoneal (fig. 18.9). It is approximately 15 cm long and 2.5 cm thick. Most of it is an exocrine digestive gland, and its gross anatomy is therefore discussed in chapter 24 (see p. 677). Dispersed throughout the exocrine tissue,

---

[17] *fascicul* = little bundle; *ata* = possessing
[18] *reticul* = little network; *aris* = pertaining to



© Ed Reschke/Getty Images

Figure 18.9 **The Pancreas.** (a) Gross anatomy and relationship to the duodenum. (b) Cells of a pancreatic islet. PP and G cells are not shown; they are few in number and cannot be distinguished with ordinary histological stains. (c) Light micrograph of a pancreatic islet amid the darker exocrine tissue.

- *What is the function of the exocrine cells in this gland?* AP|R

however, are about 1 to 2 million endocrine cell clusters called the **pancreatic islets (islets of Langerhans[19]).** Although they are less than 2% of the mass of the pancreas, the islets secrete hormones of vital importance to metabolism—especially insulin and glucagon. The major effect of these hormones is to regulate *glycemia,* the concentration of glucose in the blood.

A typical pancreatic islet measures about 75 × 175 μm. Islets contain from a few to 3,000 cells, belonging primarily to three classes:

1. **Alpha (α) cells,** or **A cells,** which secrete **glucagon.** Glucagon is secreted between meals when the blood glucose level falls. Its effects are to stimulate the release of stored glucose from the liver and fatty acids from adipose tissue, thereby providing the body with blood-borne fuel until the next meal.
2. **Beta (β) cells,** or **B cells,** which secrete **insulin** and **amylin.** Insulin is secreted during and immediately after a meal in response to rising levels of blood-borne nutrients such as glucose and amino acids. It stimulates most body tissues to absorb these nutrients and store or metabolize them. Amylin enhances the effects of insulin and influences gastric emptying and bile secretion.
3. **Delta (δ) cells,** or **D cells,** which secrete **somatostatin** (growth hormone–inhibiting hormone). Somatostatin is secreted under the same conditions as insulin. It helps to regulate the speed of digestion and nutrient absorption, and perhaps modulates the activity of other pancreatic islet cells.

Other, minor types of pancreatic cells are called PP and G cells. Their functions remain obscure and controversial, so we will not further consider them. The proportions of these pancreatic cells are about 20% alpha, 70% beta, 5% delta, and small numbers of PP and G cells.

The Gonads

Like the pancreas, the **gonads** (ovaries and testes) function as both endocrine and exocrine glands. Their exocrine products are eggs and sperm, and their endocrine products are the *gonadal hormones,* most of which are steroids. Their gross anatomy is described in chapter 26.

The ovaries secrete chiefly **estrogen, progesterone,** and **inhibin.** Each egg develops in its own bubblelike follicle (fig. 18.10a), which is lined by a wall of **granulosa cells** and surrounded by a capsule, the **theca.** The theca and granulosa cells collaborate to produce estrogen. Midway through the monthly ovarian cycle, the follicle ovulates (releases the egg) and begins to secrete an abundance of progesterone. Estrogen and progesterone contribute to the development of the reproductive system and feminine physique, regulate the menstrual cycle, sustain pregnancy, and prepare the mammary glands for lactation. Inhibin, which is also secreted by the follicle, is a signal from the ovaries to the anterior pituitary. It inhibits the secretion of follicle-stimulating hormone (FSH). The effects of these hormones are further considered in chapter 26.

---

[19] Paul Langerhans (1847–88), German anatomist


Granulosa cells (source of estrogen)
Egg cell (oocyte)
Theca
100 µm
Ovary
(a)
© Ed Reschke/Getty Images


Blood vessels
Seminiferous tubule
Germ cells
Connective tissue wall of tubule
Sustentacular cells
Interstitial cells (source of testosterone)
50 µm
Testis
(b)
© Ed Reschke/Getty Images

Figure 18.10 **The Gonads.** (a) Histology of an ovarian follicle; compare the SEM photo on page 497. (b) Histology of the testis. The granulosa cells of the ovary and interstitial cells of the testis are endocrine cells. AP|R

The testes secrete **testosterone,** lesser amounts of weaker androgens and estrogens, and inhibin. They consist mainly of minute tubules that produce sperm. The wall of the tubule is formed partly by **sustentacular (Sertoli[20]) cells,** the source of inhibin. By limiting FSH secretion, inhibin regulates the rate of sperm production. Nestled between the tubules are clusters of **interstitial cells (cells of Leydig[21])** (fig. 18.10b), the source of testosterone and the other sex steroids. Testosterone stimulates development of the male reproductive system in the fetus and adolescent, the development of the masculine physique in adolescence, and the sex drive. It sustains sperm production and the sexual instinct throughout adult life.

Endocrine Cells in Other Tissues and Organs

Several other tissues and organs beyond the classical endocrine glands have hormone-secreting cells:

- **The skin.** Keratinocytes of the epidermis produce *cholecalciferol,* the first step in the synthesis of **calcitriol (vitamin D_3),** a calcium-regulating hormone. The liver and kidneys complete the process.
- **The liver.** The liver is involved in the production of at least five hormones: (1) It converts cholecalciferol to *calcidiol,* the second step in calcitriol synthesis. (2) It secretes a protein called **angiotensinogen,** which is converted by the kidneys, lungs, and other organs into a hormone called **angiotensin II,** which raises blood pressure. (3) It secretes **erythropoietin (EPO)** (eh-RITH-ro-POY-eh-tin), a hormone that stimulates red blood cell (erythrocyte) production. (4) It secretes **hepcidin,** which regulates iron homeostasis. (5) It secretes **insulin-like growth factor I (IGF-I),** which mediates the action of growth hormone.
- **The kidneys.** The kidneys secrete most (85%) of the body's erythropoietin, and carry out the third and final step in calcitriol synthesis and the second step in angiotensin II synthesis.
- **The heart.** The heart secretes **natriuretic[22] peptides,** hormones that enhance sodium excretion in the urine and reduce blood pressure.
- **The stomach and small intestine.** These organs have various *enteroendocrine cells,*[23] which secrete at least 10 **enteric hormones.** These regulate feeding and digestion. They include **gastrin,** which stimulates acid secretion by the stomach; **cholecystokinin** (COAL-eh-SIS-toe-KY-nin), which stimulates the secretion of bile; **ghrelin** (GREL-in), which produces a sensation of hunger; and **peptide YY,** which creates a feeling of satiety (satisfaction of the appetite) and tends to terminate eating.
- **Adipose tissue.** Fat cells secrete **leptin,** which has long-term appetite-regulating effects on the brain and plays a role in the onset of puberty.
- **Osseous tissue (bone).** Osteoblasts secrete **osteocalcin,** which enhances the secretion and action of insulin and inhibits fat deposition (weight gain).

---

[20] Enrico Sertoli (1824–1910), Italian histologist
[21] Franz von Leydig (1821–1908), German histologist
[22] *natri* = sodium; *uretic* = pertaining to urine
[23] *entero* = intestine

- **The placenta.** This organ performs many functions in pregnancy, including fetal nutrition and waste removal. But it also secretes estrogen, progesterone, and other hormones that regulate pregnancy and stimulate development of the fetus and the mother's mammary glands.

Apply What You Know

Often, two hormones have opposite *(antagonistic)* effects on the same target organs. For example, oxytocin stimulates labor contractions, and progesterone inhibits premature labor. Name some other examples of antagonistic effects among the hormones in this chapter.

You can see that the endocrine system is extensive. It includes numerous discrete glands as well as individual cells in the tissues of other organs. The endocrine organs and tissues other than the hypothalamus and pituitary are reviewed in table 18.3.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

9. Name two endocrine glands that are larger in children than in adults. What are their functions?
10. What hormone increases the body's heat production in cold weather? What other functions does this hormone have?
11. Name the main hormone secreted by each layer of the adrenal cortex and one secreted by the adrenal medulla, and state the function of each.
12. What is the difference between a gonadal hormone and a gonadotropin?
13. What hormones are most important in regulating blood glucose concentration? What cells produce them? Where are these cells found?
14. Name one hormone produced by each of the following organs—the heart, liver, and placenta—and state the function of each hormone.

TABLE 18.3 Hormones from Sources Other Than the Hypothalamus and Pituitary

Source	Hormone	Target Organs and Tissues	Principal Effects
Pineal gland	Melatonin	Brain	Influences mood; may regulate the timing of puberty
Thymus	Thymopoietin, thymosin, thymulin	T lymphocytes	Stimulate T lymphocyte development and activity
Thyroid gland	Thyroxine (T_4) and triiodothyronine (T_3)	Most tissues	Elevate metabolic rate and heat production; promote alertness, quicker reflexes, enhanced absorption of dietary carbohydrates, protein synthesis, fetal and childhood growth, and CNS development
	Calcitonin	Bone	Promotes net deposition of bone by inhibiting osteoclasts; reduces blood Ca^{2+} level
Parathyroid glands	Parathyroid hormone (PTH)	Bone, kidneys, small intestine	Increases blood Ca^{2+} level by stimulating bone resorption, calcitriol synthesis, and intestinal Ca^{2+} absorption, and reducing urinary Ca^{2+} excretion
Adrenal medulla	Epinephrine, norepinephrine, dopamine	Most tissues	Adaptive responses to arousal and stress
Adrenal cortex	Aldosterone	Kidney	Promotes Na^+ retention and K^+ excretion; maintains blood pressure and volume
	Cortisol and corticosterone	Most tissues	Stimulate fat and protein catabolism, gluconeogenesis, stress resistance, and tissue repair
	Androgens	Bone, muscle, integument, many other tissues	Growth of pubic and axillary hair, bone growth, sex drive, male prenatal development
Pancreatic islets	Glucagon	Primarily liver	Stimulates glucose synthesis, glycogen and fat breakdown, release of glucose and fatty acids into circulation
	Insulin	Most tissues	Stimulates glucose and amino acid uptake; lowers blood glucose level; promotes glycogen, fat, and protein synthesis
	Somatostatin	Stomach, small intestine, pancreatic islets	Inhibits digestion and nutrient absorption; inhibits glucagon and insulin secretion
	Amylin	Stomach, gallbladder	Enhances action of insulin; helps regulate gastric emptying and bile secretion

(continued)

TABLE 18.3 Hormones from Sources Other Than the Hypothalamus and Pituitary (continued)

Source	Hormone	Target Organs and Tissues	Principal Effects
Ovaries	Estrogen	Many tissues	Stimulates female reproductive development and adolescent growth; regulates menstrual cycle and pregnancy; prepares mammary glands for lactation
	Progesterone	Uterus, mammary glands	Regulates menstrual cycle and pregnancy; prepares mammary glands for lactation
	Inhibin	Anterior pituitary	Inhibits FSH secretion
Testes	Testosterone	Many tissues	Stimulates reproductive development, musculoskeletal growth, sperm production, and sex drive
	Inhibin	Anterior pituitary	Inhibits FSH secretion
Skin	Cholecalciferol	—	Precursor of calcitriol (see kidneys)
Liver	Calcidiol	—	Precursor of calcitriol (see kidneys)
	Angiotensinogen	—	Precursor of angiotensin II (see kidneys)
	Erythropoietin	Red bone marrow	Promotes red blood cell production
	Hepcidin	Small intestine	Promotes iron absorption
	Insulin-like growth factor I	Many tissues	Mediates action of growth hormone
Kidneys	Erythropoietin	Red bone marrow	Promotes red blood cell production
	Calcitriol	Small intestine	Increases blood calcium level mainly by promoting intestinal absorption of dietary calcium
	Angiotensinogen I	—	Precursor of angiotensin II, a vasoconstrictor
Heart	Natriuretic peptides	Kidney	Lower blood volume and pressure by promoting Na^+ and water loss
Stomach and small intestine	Gastrin	Stomach	Acid secretion
	Cholecystokinin	Gallbladder; brain	Bile release; appetite suppression
	Ghrelin	Brain	Sensation of hunger; initiation of feeding
	Peptide YY	Brain	Sense of satiety; termination of feeding
	Other enteric hormones	Stomach, intestines	Coordination of secretion and motility in different regions of digestive tract
Adipose tissue	Leptin	Brain	Long-term appetite regulation
Osseous tissue	Osteocalcin	Pancrease, adipose tissue	Increased insulin secretion; enhanced insulin sensitivity of target organs; reduced fat deposition
Placenta	Estrogen, progesterone, and others	Many tissues of mother and fetus	Stimulation of fetal development and maternal bodily adaptations to pregnancy; preparation for lactation

18.4 Developmental and Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the embryonic development of each major endocrine gland;
b. identify which endocrine glands or hormone levels change the most in old age, and state some of the consequences of these changes; and
c. describe a few common disorders of the endocrine system, especially diabetes mellitus.

Prenatal Development of the Endocrine Glands

The endocrine glands, like other glands, develop mainly from embryonic epithelia, but lose their connection to the epithelial surface as they mature—hence the absence of ducts (see fig. 3.28, p. 75). All three embryonic germ layers—ectoderm, mesoderm, and endoderm—contribute to the endocrine system.

The pituitary has a dual origin (fig. 18.11a–c). The adenohypophysis begins with a pocket called the *hypophyseal pouch* that grows upward from the ectoderm of the pharynx. The pouch breaks away from the ectodermal surface and forms a hollow sac that continues to migrate upward. Meanwhile, growing down toward it, the neurohypophysis arises as an extension of the hypothalamus called the *neurohypophyseal bud.* The bud retains its connection


Telencephalon of brain
Future hypothalamus
Neurohypophyseal bud
Hypophyseal pouch
Pharynx
Tongue
Thyroid diverticulum
Mouth
(a) 4 weeks
Pituitary development
Hypothalamus
Neurohypophyseal bud
Hypophyseal pouch
Pharynx
(b) 8 weeks
Hypothalamus
Optic chiasm
Pituitary stalk
Posterior lobe
Anterior lobe
Sphenoid bone
Pharynx
(c) 16 weeks
Thyroid development
Tongue
Esophagus
Trachea
Thyroid gland
(d) 5 weeks
Esophagus
Larynx
Thyroid gland
(e) 7 weeks

Figure 18.11 **Embryonic Development of the Pituitary and Thyroid Glands.** (a) Sagittal section of a 4-week embryo showing the early buds (future glands) of the anterior pituitary, posterior pituitary, and thyroid glands. (b) At 8 weeks, the hypophyseal pouch separates from the pharynx. (c) At 16 weeks, the structure of the pituitary is essentially complete. (d) At 5 weeks, the thyroid gland descends through the neck, and its connection to the tongue breaks down. (e) By 7 weeks, the thyroid has reached its final location on the trachea inferior to the larynx.

to the brain throughout life as the pituitary stalk. The pouch and bud come to lie side by side and to be enclosed in the sella turcica of the sphenoid bone. They become so closely joined to each other that they look like a single gland.

The other endocrine gland associated with the brain, the pineal gland, develops from ependymal cells lining the third ventricle. A trace of the third ventricle persists as a canal in the stalk of the pineal gland.

The thyroid gland begins with an endodermal pouch *(thyroid diverticulum)* growing from the floor of the pharynx slightly posterior to the hypophyseal pouch. It migrates posteriorly to its position slightly inferior to the future larynx (fig. 18.11a, d, e).

In and near the neck, the thymus, parathyroid glands, and thyroid C cells arise from the *pharyngeal pouches* described in chapter 4 (p. 92). Cell masses break away from the third and fourth pouches and then split into posterior and anterior cell groups. The posterior groups form the parathyroid glands, which normally join the migrating thyroid and adhere to its posterior side. The anterior groups migrate medially and merge with each other to become the thymus. Cells from the fifth pharyngeal pouch become the thyroid C cells; they mingle with the rest of the thyroid tissue as the future thyroid gland migrates toward the larynx (see fig. 4.7, p. 93).

The adrenal gland, like the pituitary, has a dual origin (fig. 18.12). Recall from chapter 13 (p. 366) that ectodermal *neural crest cells* break away from the neural tube and give rise to sympathetic neurons and other cells. Some of the neural crest cells become the adrenal medulla. These neural crest masses, in turn, stimulate cell multiplication in the overlying mesothelium, the serous lining of the embryonic peritoneal cavity. The mesothelium thickens and grows around the medulla, eventually completely enclosing it and becoming the adrenal cortex. The adrenal gland is not fully developed until the age of 3 years.

The Aging Endocrine System

Endocrine glands vary widely in functionality over the life span. As we have seen in this chapter, the adrenal gland shrinks to half its size even in the first 2 months after birth. The pineal gland and thymus undergo pronounced involution after puberty. In old age, they are but shriveled vestiges of the childhood glands, with most of their secretory tissue replaced by fat or fiber.

Impaired glucose metabolism is common among the elderly and stems from causes as diverse as poor diet, lack of exercise, the presence of more fat and less muscle, reduced insulin secretion, and blunted effectiveness of insulin. Muscle ordinarily absorbs a large percentage of the blood glucose after a meal and is therefore a major means of stabilizing glycemia (blood sugar level). But when the aging individual loses muscle mass, glycemia remains elevated after a meal longer than it would in one with more muscle, and the risk of diabetes mellitus rises even if insulin secretion is normal.

Ovarian function drops precipitously at menopause, around 50 to 55 years of age, when the follicles are depleted and cease to secrete estrogen. The remaining estrogen comes mainly from the enzymatic conversion of androgens secreted by the adrenal glands, and its level is very low and noncyclic in contrast to the premenopausal state. This raises the risk of cardiovascular disease, bone loss (osteoporosis), and dementia in postmenopausal women. Androgen levels—both testosterone and adrenal DHEA—fall more gradually in men. The circulating testosterone concentration in an 80-year-old man is about 20% of that seen in a 20-year-old. Age-related changes in reproductive function are discussed further in chapter 26.

In a number of cases, the waning of endocrine function with age results not from declining hormone secretion but from diminished effectiveness of the hormone that exists. This is the case in type 2 diabetes mellitus, which results from a deficiency or dysfunction of insulin receptors. Thyroid function declines in old age not because the gland secretes significantly less thyroxine (T_4), but because the target organs become less efficient in converting it to T_3, the more active form. The stress response also is more poorly controlled in the elderly. Normally, the anterior pituitary secretes ACTH; this stimulates the adrenal cortex to secrete cortisol; and cortisol induces the pituitary to lower the ACTH output. But in the elderly, the pituitary is less responsive to cortisol, so the ACTH level remains elevated, and the stress response lasts longer than it would in one's younger years.



Figure 18.12 **Embryonic Development of the Adrenal Gland.** (a) A 4-week embryo with the plane of section seen in part (b). (b) The future adrenal medulla begins as a mass of cells that separate from the neural crest. (c) Growth of the adrenal medulla and bulging of the mesothelium into the body cavity (coelom). (d) The mesothelium thickens and encloses the adrenal medulla, giving rise to the adrenal cortex.

Endocrine Disorders

Most disorders of the endocrine system revolve around three causes:

1. A hormone deficiency, or **hyposecretion,** exemplified by the insulin deficiency in type 1 diabetes mellitus.
2. A hormone excess, or **hypersecretion,** exemplified by pituitary gigantism, in which people grow to extraordinary heights because of excessive growth hormone secretion in childhood.
3. A **hormone insensitivity,** in which the hormone is present but a receptor defect causes the body to be unresponsive to it, as in the insulin resistance that characterizes type 2 diabetes mellitus.

These disorders are primarily physiological and therefore beyond the scope of this book, but hypo- and hypersecretion are sometimes caused by or associated with anatomical abnormalities worthy of mention here. Often, these abnormalities result from endocrine tumors or trauma.

Consider the pituitary gland, for example, snugly nestled in the sella turcica of the sphenoid bone and seemingly well protected. But surprisingly, the sphenoid is the most commonly fractured of all skull bones, with potentially grave consequences for pituitary function. A sphenoid fracture can sever the pituitary stalk, including the portal system, the hypothalamo–hypophyseal tract, or both. Such injuries cut off communication between the brain and the pituitary, thereby disrupting pituitary functions that depend on neural or hormonal signals from the hypothalamus. Anterior lobe effects can include loss of sexual functions (menstrual irregularity, sterility, and impotence due to loss of gonadotropins), and inadequate thyroid and adrenal gland function due to hyposecretion of thyroid-stimulating hormone and ACTH. Growth hormone secretion also declines markedly, although this has no clinical effect on adults. Severance of the hypothalamo–hypophyseal tract adversely affects secretion of the posterior lobe hormones oxytocin and antidiuretic hormone (see Testing Your Comprehension question 1 at the end of the chapter). Surgical accidents are another source of endocrine trauma with sometimes serious consequences (see Deeper Insight 18.2).

Tumors are another form of anatomical disorder with endocrine consequences. Pineal tumors are a case in point. They occur most often in childhood and sometimes cause premature sexual development, called *precocial puberty,* especially in boys. This lends some evidence to the theory that the pineal gland may play a role in the timing of puberty. However, precocial puberty occurs only when the tumor also affects the nearby hypothalamus, so it is difficult to say whether the effect is due specifically to the pineal damage. Other effects of pineal tumors stem from the anatomical relationship of this gland to nearby brain structures (see Testing Your Comprehension question 2 at the end of this chapter).

A more common endocrine tumor is *pheochromocytoma* (FEE-oh-CRO-mo-sy-TOE-ma), a tumor of the adrenal medulla that causes hypersecretion of epinephrine and norepinephrine. The hormone excess causes nervousness, indigestion, sweating, tachycardia, hypertension, and an elevated metabolic rate. Patients often feel a sense of panic or impending doom. Most pheochromocytomas are benign (noncancerous), yet the hypertension is life-threatening and the tumor usually calls for surgical removal.

A more conspicuous, often striking anatomical abnormality of an endocrine gland is **endemic goiter.** This is a disorder of the thyroid gland that results from a deficiency of dietary iodine. Normally, as the gland produces thyroid hormone (TH), it sends a feedback signal to the hypothalamus and anterior pituitary. In response, they modulate their secretion of thyrotropin-releasing hormone (TRH) and thyroid-stimulating hormone (TSH) and the thyroid, as a result, is not overstimulated. An iodine deficiency, however, reduces TH secretion and the feedback effect. The pituitary secretes a slightly but constantly elevated level of TSH, leading to hypertrophy of the thyroid gland. The overgrown thyroid is often visible in the neck as a goiter (fig. 18.13). Endemic goiter has become almost nonexistent in developed countries because of the addition of iodine to table salt, animal feeds, and fertilizers. It occurs most often in localities that have neither these benefits nor access to iodine-rich seafood—notably, central Africa and mountainous regions of South America, central Asia, and Indonesia. The word *endemic* refers to the occurrence of a disease in a defined geographic locality.

Some other endocrine disorders are described in table 18.4.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

15. With respect to embryonic development, what does the pituitary gland have in common with the thyroid gland? What does it have in common with the adrenal gland? Explain each comparison.
16. In some cases, endocrine function can decline in old age even if there is little change in the level of hormone secretion. Explain why, and support your explanation with examples.
17. Suppose an auto accident had fractured a pregnant woman's sphenoid bone and severed the pituitary stalk. Assuming that she nevertheless carried the pregnancy to full term, how might this accident affect her labor contractions? How might it affect her ability to breast-feed? Explain both effects.
18. What physical appearance might lead you to suspect that a person had a deficiency of iodine in the diet? Why would you find it more surprising to see this in a native of Tennessee than in a native of Tibet?



© Collection CNRI/Phototake

Figure 18.13 **A Severe Case of Endemic Goiter.**

TABLE 18.4	Disorders of the Endocrine System
Addison disease	Hyposecretion of adrenal glucocorticoids or mineralocorticoids, causing hypoglycemia, hypotension, weight loss, weakness, loss of stress resistance, darkening of the skin, and potentially fatal dehydration and electrolyte imbalances
Adrenogenital syndrome	Hypersecretion of adrenal androgens. Prenatal hypersecretion can cause girls to be born with masculinized genitalia and to be misidentified as boys. In children, it often causes enlargement of the penis or clitoris and premature puberty. In women, it causes masculinizing effects such as increased body hair, beard growth, and deepening of the voice.
Congenital hypothyroidism	Thyroid hyposecretion present from birth, resulting in stunted physical development, thickened facial features, low body temperature, lethargy, and irreversible brain damage in infancy
Cushing syndrome	Cortisol hypersecretion resulting from overactivity of the adrenal cortex. Results in disruption of carbohydrate and protein metabolism, hyperglycemia, edema, loss of bone and muscle mass, and sometimes abnormal fat deposition in the face or between the shoulders.
Myxedema	A result of severe or prolonged adult hypothyroidism, characterized by low metabolic rate, sluggishness and sleepiness, weight gain, constipation, hypertension, dry skin and hair, abnormal sensitivity to cold, and tissue swelling
Pituitary dwarfism	Abnormally short stature, with a normal proportion of limbs to trunk, resulting from growth hormone hyposecretion in childhood

Disorders Described Elsewhere

Acromegaly	148	Hypoparathyroidism	506	Pineal tumors	515
Empty sella syndrome	500	Pheochromocytoma	515	Pituitary trauma	515
Endemic goiter	515				

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

18.1 Overview of the Endocrine System (p. 498)

1. The definitions of *hormone* and *endocrine system*
2. The unusual nature of the blood capillaries typical of endocrine glands, and the functional significance of this capillary type
3. How hormones travel about the body
4. The terms for the cells and organs that respond to them and the reason that other cells and organs are unresponsive to a given hormone even if exposed to it
5. The characteristics of an endocrine gland and how it contrasts with an exocrine gland
6. Examples of glands with dual endocrine and exocrine functions, and of secretory cells that defy classification by any simple endocrine–exocrine criteria
7. Functional differences and similarities between the endocrine and nervous systems

18.2 The Hypothalamus and Pituitary Gland (p. 500)

1. The location and anatomy of the pituitary gland and its relationship with the hypothalamus and sphenoid bone
2. The location of the adenohypophysis; its three parts in the human fetus; and which part is no longer present in adults
3. The three types of cells in the adenohypophysis and the differences between them
4. The anatomy of the hypophyseal portal system and its role in communication between the hypothalamus and adenohypophysis
5. The location of the neurohypophysis; its three parts; and the structure and function of the hypothalamo–hypophyseal tract
6. The six hypothalamic hormones that regulate the anterior pituitary, and the function of each one
7. The two hormones that are synthesized in the hypothalamus and stored in the posterior pituitary until release
8. The target organs or tissues and the functions of the anterior pituitary hormones: follicle-stimulating hormone, luteinizing hormone, thyroid-stimulating hormone, adrenocorticotropic hormone, prolactin, growth hormone, and insulin-like growth factors
9. The sites of synthesis, the target organs, and the functions of the posterior pituitary hormones: oxytocin and antidiuretic hormone

18.3 Other Endocrine Glands (p. 504)

1. The location and anatomy of the pineal gland, its changes through the life span, and the functions of melatonin
2. The location and anatomy of the thymus, its changes through the life span, its role in immunity, and the hormones that serve this role
3. The location, anatomy, and histology of the thyroid gland; its blood supply; its three hormones and which thyroid cells secrete them; and the functions of these hormones

4. The location and anatomy of the parathyroid glands; their hormone; and the function of that hormone
5. The location and anatomy of the adrenal glands, and their blood supply
6. The relationship of the adrenal medulla to the sympathetic nervous system; the hormones of the medulla; and the effects of those hormones
7. The three layers of the adrenal cortex; their histological differences; the hormones secreted by each layer; and the effects of those hormones
8. The location and structure of the pancreatic islets; the three primary types of islet cells; the hormone secreted by each cell type; and the functions of those hormones
9. Locations and names of the endocrine cells in the ovary and testis; their hormones; and the functions of those hormones
10. The roles of the skin, liver, kidneys, heart, stomach, small intestine, adipose tissue, bone, and placenta in synthesizing and secreting hormones, or carrying out a step in hormone synthesis; and the names and functions of these hormones

18.4 Developmental and Clinical Perspectives (p. 512)

1. Changes in insulin secretion and action with age
2. Changes in sex hormone secretion with age, and the bodily effects especially of the cessation of ovarian function at menopause
3. Some consequences of reduced hormone effectiveness in old age
4. A cause, and the effects, of trauma to the pituitary gland
5. The effects of tumors of the pineal gland and adrenal medulla
6. The cause and effects of endemic goiter

Testing Your Recall

1. Which of the following hormones is *not* synthesized by the brain?
   a. thyrotropin-releasing hormone
   b. antidiuretic hormone
   c. prolactin-releasing hormone
   d. follicle-stimulating hormone
   e. oxytocin
2. Which of the following hormones has the least in common with the others?
   a. adrenocorticotropic hormone
   b. follicle-stimulating hormone
   c. thyrotropin
   d. thyroxine
   e. prolactin
3. Which hormone would no longer be secreted if the hypothalamo–hypophyseal tract was destroyed?
   a. oxytocin
   b. follicle-stimulating hormone
   c. growth hormone
   d. adrenocorticotropic hormone
   e. corticosterone
4. Which of the following is *not* a hormone?
   a. prolactin
   b. thymosin
   c. iodine
   d. natriuretic peptide
   e. insulin-like growth factor
5. The _____ has/have no other function but hormone production, whereas the rest of these produce other secretions in addition to hormones.
   a. liver
   b. gonads
   c. salivary glands
   d. parathyroid glands
   e. pancreas
6. Which of these glands develops from the pharyngeal pouches?
   a. the anterior pituitary
   b. the posterior pituitary
   c. the thyroid gland
   d. the thymus
   e. the adrenal gland
7. Which of these glands has more exocrine than endocrine tissue?
   a. the pancreas
   b. the adenohypophysis
   c. the thyroid gland
   d. the pineal gland
   e. the adrenal gland
8. _____ leads to increased osteoclast activity and elevates the blood calcium concentration.
   a. Parathyroid hormone
   b. Calcitonin
   c. Calcitriol
   d. Aldosterone
   e. ACTH
9. Which of these endocrine glands is most directly involved in immune function?
   a. the pancreas
   b. the thymus
   c. the adenohypophysis
   d. the adrenal glands
   e. the thyroid gland
10. Both the _____ are involved in the synthesis of calcitriol and erythropoietin.
    a. anterior and posterior pituitary
    b. thyroid gland and thymus
    c. liver and kidneys
    d. parathyroids and pancreatic islets
    e. epidermis and liver
11. The _____ develops from the hypophyseal pouch of the embryo.
12. Antidiuretic hormone is produced by a group of neurons in the hypothalamus called the _____.
13. Adipocytes secrete the hormone _____, which signals the brain and helps to regulate the appetite.
14. The heart secretes two hormones called _____ that increase the urinary output of sodium and water.
15. Adrenal steroids that regulate glucose metabolism are collectively called _____.
16. The hypophyseal portal system is a means for the brain to communicate with the _____.
17. _____ cells are hormone-secreting neurons or cells derived from neurons.
18. In males, testosterone is secreted mainly by the _____ cells.
19. Cortisol is secreted by a layer of the adrenal cortex called the _____ in response to the pituitary hormone _____.
20. The hormones secreted by the stomach and small intestine are collectively called _____.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. crin-
2. oxy-
3. pro-
4. troph-
5. corpo-
6. thyro-
7. natri-
8. calori-
9. lact-
10. -phob

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. Tumors can lead to either hormone hypersecretion or hyposecretion.
2. All hormones are secreted by endocrine glands.
3. If fatty plaques of atherosclerosis blocked the arteries of the hypophyseal portal system, it could cause the ovaries and testes to malfunction.
4. The pineal gland and thymus become larger as one ages.
5. The tissue at the center of the adrenal gland is called the zona reticularis.
6. Unlike neurotransmitters, hormones cannot be selectively delivered to just one particular target organ.
7. The adenohypophysis and thyroid gland are more similar to each other in their embryonic origin than are the adenohypophysis and neurohypophysis.
8. Oxytocin and antidiuretic hormone are secreted through a duct called the pituitary stalk or infundibulum.
9. Of the endocrine glands covered in this chapter, only the adrenal glands are paired. The rest are single.
10. Enlargement of the thyroid gland would produce a swelling in the neck.

Answers in appendix A

Testing Your Comprehension

1. A young man is involved in a motorcycle accident that fractures his sphenoid bone and severs the pituitary stalk. Shortly thereafter, he begins to excrete enormous amounts of urine, up to 30 liters per day, and suffers intense thirst. Explain how his head injury could have resulted in these effects.
2. Examine the anatomical relationship between the pineal gland and nearby brain structures, and as necessary, review the functions of those brain structures in chapter 15. In light of this information, explain why a large pineal tumor might result in (a) hydrocephalus and (b) paralysis of some eye movements.
3. Renal failure puts a person at risk of anemia and hypocalcemia. To prevent this, renal dialysis patients are routinely given hormone replacement therapy. Explain the hormonal connection between renal failure and each of these conditions, and identify what hormones would be administered to correct or prevent them.
4. Hormones of the adrenal cortex are steroids, whereas insulin is a protein. In view of this, what major difference would you expect to see in the organelles of an adrenal spongiocyte and a pancreatic beta cell if you compared them with an electron microscope?
5. Selective destruction or removal of the adrenal cortex is fatal, but destruction or removal of the adrenal medulla produces no clear adverse effect. Explain why these two parts of the adrenal gland would differ so much in their necessity to life.



Red and white blood cells, platelets, and sticky threads of fibrin (SEM)

© Dr. Yorgos Nikas/Science Source

PART FOUR

CHAPTER 19

THE CIRCULATORY SYSTEM I
BLOOD

CHAPTER OUTLINE

19.1 Introduction 520
- Functions of the Circulatory System 520
- Components and General Properties of Blood 520
- Blood Plasma 522

19.2 Erythrocytes 523
- Form and Function 523
- Quantity of Erythrocytes 524
- Hemoglobin 524
- The Erythrocyte Life Cycle 524
- Blood Types 525

19.3 Leukocytes 527
- Form and Function 527
- Types of Leukocytes 527
- The Leukocyte Life Cycle 530

19.4 Platelets 532
- Form and Function 532
- Platelet Production 533
- Hemostasis 533

19.5 Clinical Perspectives 534
- Hematology in Old Age 534
- Disorders of the Blood 534

Study Guide 536

DEEPER INSIGHTS

19.1 Bone Marrow and Cord Blood Transplants 526
19.2 The Complete Blood Count 532
19.3 Sickle-Cell Disease 536

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:
- Osmosis (p. 34)
- Red bone marrow (p. 138)
- Erythropoietin (p. 510)

Anatomy & Physiology REVEALED®
aprevealed.com

Module 9: Cardiovascular System

Blood has always had a special mystique. Since ancient times, people have seen blood flow from the body and with it, the life of the individual. It is no wonder that blood was seen as a source of a mysterious "vital force." Even today, we become especially alarmed when we find ourselves bleeding, and the emotional impact of blood is enough to make many people faint at the sight of it. From ancient Egypt to nineteenth-century America, physicians drained "bad blood" from their patients to treat everything from gout to headaches, from menstrual cramps to mental illness. Indeed, bloodletting was a likely factor in the death of George Washington, who had a probable streptococcus infection and insisted that his doctors bleed him. It was long thought that hereditary and even moral traits were transmitted through the blood, and people still use such unfounded or metaphorical expressions as "I have one-quarter Cherokee blood."

Even though it is an especially accessible tissue, little was known about the specific functions of blood before the mid-twentieth century. But over the past several decades, technology has ushered in a new era for **hematology,**[1] the study of blood. Diseases such as cancer and AIDS have given added impetus to hematology research, and recent discoveries have saved and improved the lives of countless people who otherwise would have suffered and died.

19.1 Introduction

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the functions and major components of the circulatory system;
b. describe the components and physical properties of blood; and
c. describe the composition of blood plasma.

Functions of the Circulatory System

The **circulatory system** consists of the heart, blood vessels, and blood. The term **cardiovascular system**[2] refers only to the heart and blood vessels, which are the subject of chapters 20 and 21.

The fundamental purpose of the circulatory system is to transport substances from place to place in the blood. Blood is the liquid medium in which these materials travel; blood vessels ensure the proper routing of blood to its destinations; and the heart is the pump that keeps the blood flowing.

More specifically, the functions of the circulatory system are as follows:

Transport

- The blood carries oxygen from the lungs to all of the body's tissues, while it picks up carbon dioxide from those tissues and carries it to the lungs to be removed from the body.
- It picks up nutrients from the digestive tract and delivers them to all of the body's tissues.
- It carries metabolic wastes to the kidneys for removal.
- It carries hormones from endocrine cells to their target organs.
- It transports a variety of stem cells from the bone marrow and other origins to the tissues where they lodge and mature.

Protection

- The blood plays several roles in inflammation, a mechanism for limiting the spread of infection.
- White blood cells destroy microorganisms and cancer cells.
- Antibodies and other blood proteins neutralize toxins and help to destroy pathogens (disease agents).
- Platelets secrete factors that initiate blood clotting and other processes for minimizing blood loss.

Regulation

- Blood helps maintain optimal fluid balance and distribution in the body by absorbing or giving off fluid under different conditions.
- Blood proteins stabilize the pH of extracellular fluids by buffering acids and bases.
- Shifts in blood flow help to regulate body temperature by routing blood to the skin for heat loss or retaining blood deeper in the body for heat retention.

Considering the importance of efficiently transporting nutrients, wastes, hormones, and especially oxygen from place to place, it is easy to understand why an excessive loss of blood is quickly fatal, and why the circulatory system needs mechanisms for minimizing such losses.

Components and General Properties of Blood

Most adults have about 4 to 6 liters of blood. It is a liquid connective tissue composed, like other connective tissues, of cells and an extracellular matrix. The matrix is the blood **plasma,** a clear, light yellow fluid constituting a little over half of the blood volume. Suspended in the plasma are the **formed elements**—cells and cell fragments including the red blood cells, white blood cells, and platelets (fig. 19.1). The term *formed element* denotes that these are membrane-enclosed bodies with a definite visible structure. They can't all be called cells because the platelets, as explained later, are merely fragments of certain bone marrow cells. The formed elements are classified as follows:

Erythrocytes[3] (red blood cells, RBCs)
Platelets

---

[1] *hem, hemato* = blood; *logy* = study of
[2] *cardio* = heart; *vas* = vessel
[3] *erythro* = red; *cyte* = cell


Monocyte
Platelets
Small lymphocyte
Neutrophil
Large lymphocyte
Basophil
Small lymphocyte
Neutrophil
Eosinophil
Erythrocyte
Young (band) neutrophil
Monocyte
Neutrophil

Figure 19.1 **The Formed Elements of Blood.**
- *What do erythrocytes and platelets lack that the other formed elements have?*

Leukocytes[4] (white blood cells, WBCs)
    Granulocytes
        Neutrophils
        Eosinophils
        Basophils
    Agranulocytes
        Lymphocytes
        Monocytes

Thus, there are seven kinds of formed elements: the erythrocytes, platelets, and five kinds of leukocytes. The five leukocyte are divided into two categories, the *granulocytes* and *agranulocytes,* on grounds explained later.

The ratio of formed elements to plasma can be seen by taking a sample of blood in a tube and spinning it for a few minutes in a centrifuge (fig. 19.2). Erythrocytes, the densest elements, settle to the bottom of the tube and typically constitute about 37% to 52% of the total volume of whole blood—a value called the *hematocrit*. Leukocytes and platelets settle into a narrow cream- or buff-colored layer called the *buffy coat* just above the erythrocytes; they total 1% or less of the blood volume. At the top of the tube is the plasma, usually constituting about 47% to 63% of the volume.

Some general properties of blood are listed in table 19.1. Some of the terms in that table are defined later in this chapter.


Withdraw blood
Centrifuge
Plasma (55% of whole blood)
Buffy coat: leukocytes and platelets (<1% of whole blood)
Erythrocytes (45% of whole blood)
Formed elements

Figure 19.2 **Separating the Plasma and Formed Elements of Blood.** A small sample of blood is taken in a glass tube and spun in a centrifuge to separate the cells from the plasma. Erythrocytes are the densest components and settle to the bottom of the tube; platelets and WBCs are next; and plasma remains at the top of the tube.

---

[4] *leuko* = white; *cyte* = cell

TABLE 19.1 General Properties of Blood*

Mean fraction of body weight	8%
Volume in adult body	Female: 4–5 L; male: 5–6 L
Volume/body weight	80–85 mL/kg
Mean temperature	38°C (100.4°F)
pH	7.35–7.45
Viscosity (relative to water)	Whole blood: 4.5–5.5; plasma: 2.0
Osmolarity	280–296 mOsm/L
Mean salinity (mainly NaCl)	0.9%
Hematocrit (packed cell volume)	Female: 37%–48% Male: 45%–52%
Hemoglobin	Female: 12–16 g/dL Male: 13–18 g/dL
Mean RBC count	Female: 4.2–5.4 million/µL Male: 4.6–6.2 million/µL
Platelet count	130,000–360,000/µL
Total WBC count	5,000–10,000/µL

*Values vary slightly depending on the testing methods used.

Blood Plasma

Plasma is a complex mixture of water, proteins, nutrients, electrolytes, nitrogenous wastes, hormones, and gases (table 19.2). When the blood clots and the solids are removed, the remaining fluid is the blood **serum.** Serum is essentially identical to plasma except for the absence of the clotting protein fibrinogen.

Protein is the most abundant plasma solute by weight, totaling 6 to 9 grams per deciliter (g/dL). Plasma proteins play a variety of roles including clotting, defense, and transport of other solutes such as iron, copper, lipids, and hydrophobic hormones. There are three major categories of plasma proteins: albumin, globulins, and fibrinogen (table 19.3). Many other plasma proteins are indispensable to survival, but they account for less than 1% of the total.

Apply What You Know

Based on your body weight, estimate the volume (in liters) and weight (in kilograms) of your own blood.

Albumin is the smallest and most abundant plasma protein. It transports various solutes and buffers the pH of the blood. It also makes a major contribution to two physical properties of blood: its *viscosity* (thickness, or resistance to flow) and *osmolarity* (the concentration of particles that cannot pass through the walls of the blood vessels). Through its effects on these two variables, changes in albumin concentration can significantly affect blood volume, pressure, and flow. **Globulins** are divided into three subclasses; from smallest to largest in molecular weight, they are the alpha (α), beta (β), and gamma (γ) globulins. Globulins play various roles in solute transport, clotting, and immunity. **Fibrinogen** is a soluble precursor of *fibrin,* a sticky protein that forms the framework of a blood clot. Some of the other plasma proteins are enzymes involved in the clotting process.

The liver produces as much as 4 g of plasma protein per hour, contributing all of the major proteins except gamma globulins. The gamma globulins come from *plasma cells*—connective tissue cells that are descended from white blood cells called *B lymphocytes.*

TABLE 19.2 Composition of Blood Plasma

Water	92% by weight
Proteins	Albumin, globulins, fibrinogen, other clotting factors, enzymes, and others (see table 19.3)
Nutrients	Glucose, amino acids, lactic acid, lipids (cholesterol, fatty acids, lipoproteins, triglycerides, and phospholipids), iron, trace elements, and vitamins
Electrolytes	Salts of sodium, potassium, magnesium, calcium, chloride, bicarbonate, phosphate, and sulfate
Nitrogenous wastes	Urea, uric acid, creatinine, creatine, bilirubin, and ammonia
Hormones	All hormones transported in the blood
Gases	Oxygen, carbon dioxide, and nitrogen

TABLE 19.3 Major Proteins of the Blood Plasma

Proteins	Functions
Albumin (60%)*	Major contributor to blood viscosity and osmolarity; transports lipids, hormones, calcium, and other solutes; buffers blood pH
Globulins (36%)*	
Alpha (α) globulins	
Haptoglobulin	Transports hemoglobin released by dead erythrocytes
Ceruloplasmin	Transports copper
Prothrombin	Promotes blood clotting
Others	Transport lipids, fat-soluble vitamins, and hormones
Beta (β) globulins	
Transferrin	Transports iron
Complement proteins	Aid in destruction of toxins and microorganisms
Others	Transport lipids
Gamma (γ) globulins	Antibodies; combat pathogens
Fibrinogen (4%)*	Becomes fibrin, the major component of blood clots

*Percentage of the total plasma protein by weight.

Apply What You Know

How could a disease such as liver cancer or hepatitis result in impaired blood clotting?

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. List some transport, protective, and regulatory functions of the blood.
2. What are the two principal components of the blood? Outline the classification of its formed elements.
3. List the three major classes of plasma proteins. Which one is missing from blood serum?
4. What are the functions of blood albumin?

19.2 Erythrocytes

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the morphology and functions of erythrocytes (RBCs);
b. explain some clinical measurements of RBC and hemoglobin quantities;
c. describe the structure and function of hemoglobin;
d. discuss the formation, life span, and death of RBCs; and
e. explain the chemical and immunologic basis and the clinical significance of blood types.

Erythrocytes, or **red blood cells (RBCs),** have two principal functions: (1) to pick up oxygen from the lungs and deliver it to tissues elsewhere, and (2) to pick up carbon dioxide from the tissues and unload it in the lungs. RBCs are the most abundant formed elements of the blood and therefore the most obvious things one sees upon its microscopic examination. They are also the most critical to survival; a severe deficiency of leukocytes or platelets can be fatal within a few days, but a severe deficiency of erythrocytes can be fatal within a few minutes. It is the lack of life-giving oxygen, carried by erythrocytes, that leads rapidly to death in cases of major trauma or hemorrhage.

Form and Function

An erythrocyte is a discoid cell with a biconcave shape—a thick rim and a thin sunken center. It is about 7.5 µm in diameter and 2.0 µm thick at the rim (fig. 19.3). While most cells, including white blood cells, have an abundance of organelles, RBCs lose their nucleus and nearly all other organelles during their development



© Susumu Nishinaga/Getty Images

© Thomas Deernick, NCMIR/Science Source

Figure 19.3 The Structure of Erythrocytes. (a) Dimensions and shape of an erythrocyte. (b) Scanning electron micrograph. Note the concave shape of the cells. (c) Transmission electron micrograph of erythrocytes in a blood capillary. Note how thin the cells are at the center, and their lack of organelles or other internal structure.

- *Why do erythrocytes cave in at the center?* AP|R and are remarkably devoid of internal structure. With the transmission electron microscope, the interior of an RBC appears uniformly gray. Lacking mitochondria, RBCs rely exclusively on anaerobic fermentation to produce ATP. The lack of aerobic respiration prevents them from consuming the oxygen they must transport to other tissues.

Lacking a nucleus and DNA, RBCs are incapable of protein synthesis and mitosis. However, the lack of a nucleus has an overriding advantage. When the developing RBC loses its nucleus, it caves in at the center and acquires its biconcave shape. The primary benefit of this shape is that it enables the dense slurry of RBCs to flow through the large blood vessels with a smooth *laminar flow* that minimizes turbulence, and it allows the RBC to bend and pass through the tiniest blood vessels. It has also been argued that this is simply the easiest, most stable shape for the cell and its cytoskeleton to relax into when the nucleus is removed, and it may have no physiological function at all.

The plasma membrane of a mature RBC has glycolipids on the outer surface that determine a person's blood type. On the inner surface of the membrane are two cytoskeletal proteins, *spectrin* and *actin,* which give it resilience and durability. This is especially important when RBCs pass through small blood capillaries and sinusoids. Many of these passages are narrower than the diameter of an RBC, forcing the RBCs to stretch, bend, and fold as they squeeze through. When they enter larger vessels, RBCs spring back to their discoid shape, like an air-filled inner tube.

With no space occupied by organelles, RBCs can carry more hemoglobin for a given cell volume. Their cytoplasm consists mainly of a 33% solution of hemoglobin (about 280 million molecules per cell). Hemoglobin is known especially for its oxygen-transport function, but it also aids in the transport of carbon dioxide and the buffering of blood pH.

Quantity of Erythrocytes

The quantity of circulating erythrocytes is critically important to health, because it determines the amount of oxygen the blood can carry. Two of the most routine measurements in hematology are measures of RBC quantity: the **RBC count** and the **hematocrit,**[5] or **packed cell volume (PCV).** The RBC count is normally 4.6 to 6.2 million RBCs/μL in men and 4.2 to 5.4 million/μL in women. (A microliter, μL, is the same volume as a cubic millimeter, mm^3; RBC counts are also expressed as RBCs/mm^3.) The hematocrit is the percentage of blood volume composed of RBCs (fig. 19.2). In men, it normally ranges between 45% and 52%; in women, between 37% and 48%.

Hemoglobin

The red color of blood is due to its **hemoglobin (Hb),** an iron-containing gas-transport protein normally found only in the RBCs. Hemoglobin consists of four protein chains called **globins** (fig. 19.4a). In adult hemoglobin, two of these, the *alpha* (α) *chains,* are 141 amino acids long, and the other two, the *beta* (β) *chains,* are 146 amino acids long. A nonprotein component called the **heme** group is bound to each protein chain (fig. 19.4b). At the center of each heme is an iron atom (Fe), the binding site for oxygen. Having four heme groups, each hemoglobin molecule can transport up to four O_2. About 5% of the CO_2 in the bloodstream is also transported by hemoglobin, but this is bound to the globin component rather than to the heme, and a hemoglobin molecule can therefore transport both gases simultaneously. The **hemoglobin concentration** of whole blood is normally 13 to 18 g/dL in men and 12 to 16 g/dL in women.



Figure 19.4 **The Structure of Hemoglobin.** (a) The hemoglobin molecule consists of two alpha proteins and two beta proteins, with a nonprotein heme group bound to each. (b) Structure of the heme group.

- *Where does oxygen bind to this molecule?*

The Erythrocyte Life Cycle AP|R

The production of blood in general is called **hemopoiesis** (HE-mo-poy-EE-sis). Knowledge of hemopoiesis provides a foundation for understanding leukemia, anemia, and other blood disorders. We will survey some general aspects of hemopoiesis before examining red cell production specifically.

The tissues that produce blood cells are called **hemopoietic tissues.** The first such tissues of the human embryo form in the

---

[5] *hemato* = blood; *crit* = to separate

yolk sac, a membrane associated with all vertebrate embryos (see fig. 4.5, p. 91). In most vertebrates (fish, amphibians, reptiles, and birds), this sac encloses the egg yolk, transfers yolk nutrients to the growing embryo, and produces the forerunners of the first blood cells. Even animals that don't lay eggs, however, have a yolk sac that retains its hemopoietic function. (It is also the source of cells that later produce eggs and sperm.) Cell clusters called *blood islands* form here by the third week of human development. They produce stem cells that migrate into the embryo proper and colonize the bone marrow, liver, spleen, and thymus. Here, the stem cells multiply and give rise to blood cells throughout fetal development. The liver stops producing blood cells around the time of birth. The spleen stops producing RBCs soon after, but it continues to produce lymphocytes for life.

From infancy onward, the red bone marrow produces all seven kinds of formed elements, while lymphocytes are produced not only there but also in the lymphatic tissues and organs—especially the thymus, tonsils, lymph nodes, spleen, and patches of lymphatic tissue in the mucous membranes. Blood formation in the bone marrow and lymphatic organs is called, respectively, **myeloid**[6] and **lymphoid hemopoiesis.**

All formed elements trace their origins to a common type of bone marrow stem cell, the **hemopoietic stem cell (HSC).** HSCs are so named because they have the potential to develop into multiple mature cell types. They multiply at a relatively slow rate and thus maintain a small population in the bone marrow. Some of them go on to differentiate into a variety of more specialized cells called **colony-forming units (CFUs),** each type destined to produce one or another class of formed elements. Through a series of **precursor cells,** the CFUs divide and differentiate into mature formed elements.

The production of red blood cells specifically is called **erythropoiesis**[7] (eh-RITH-ro-poy-EE-sis). It begins when an HSC becomes an *erythrocyte colony-forming unit (ECFU)* (fig. 19.5). The hormone *erythropoietin (EPO)* stimulates the ECFU to develop into a *proerythroblast,* followed by an *erythroblast (normoblast).* Erythroblasts multiply and synthesize hemoglobin. When this task is completed, the nucleus shrivels and is discharged from the cell. The cell is now called a *reticulocyte,*[8] named for a temporary network composed of clusters of ribosomes *(polyribosomes).* Reticulocytes leave the bone marrow and enter the circulating blood. When the last of the polyribosomes disintegrate and disappear, the cell is a mature erythrocyte. Normally, about 0.5% to 1.5% of the circulating RBCs are reticulocytes, but this percentage rises when the body is making RBCs especially rapidly, as when compensating for blood loss.

The entire process of transformation from HSC to mature RBC takes 3 to 5 days and involves four major developments—a reduction in cell size, an increase in cell number, the synthesis of hemoglobin, and the loss of the nucleus and other organelles. The process normally generates about 1 million RBCs per second, or 20 mL of packed RBCs per day.

The average RBC lives about 120 days after its release from the bone marrow. As it ages, its membrane proteins (especially spectrin) deteriorate, and the membrane grows increasingly fragile. Without a nucleus or ribosomes, an RBC cannot synthesize new spectrin. Eventually, it ruptures as it tries to flex its way through narrow capillaries and sinusoids. The spleen has been called an "erythrocyte graveyard" because RBCs have an especially difficult time passing through its small channels. Here the old cells become trapped, broken up, and destroyed.

The life span of an RBC is often described as relatively short, owing to the fact that it lacks protein synthesis organelles and cannot repair itself. However, this 120 days is actually a relatively long life compared to other formed elements. Most leukocytes (which have nuclei) live less than a week, and platelets live about 10 days. Only monocytes and lymphocytes outlive the RBCs.

Blood Types

There are numerous genetically determined *blood groups* in the human population, each of which contains multiple **blood types.** The most familiar of these are the ABO group (with blood types A, B, AB, and O) and Rh group (with blood types Rh-positive and Rh-negative). These types differ with respect to the chemical composition of glycolipids on the RBC surface;

---

[6] *myel* = bone marrow
[7] *erythro* = red; *poiesis* = formation of
[8] *reticulo* = little network; *cyte* = cell



Figure 19.5 Erythropoiesis. Stages in the development of erythrocytes.

DEEPER INSIGHT 19.1

Bone Marrow and Cord Blood Transplants

A bone marrow transplant is one treatment option for leukemia, sickle-cell disease, some forms of anemia, and other disorders. The principle is to replace cancerous or otherwise defective marrow with donor stem cells in hopes that they will rebuild a population of normal marrow and blood cells. The patient is first given chemotherapy or radiation to destroy the defective marrow and eliminate immune cells (T cells) that would attack the donated marrow. Bone marrow is drawn from the donor's sternum or hip bone and injected into the recipient's circulatory system. Donor stem cells colonize the patient's marrow cavities and, ideally, build healthy marrow.

There are, however, several drawbacks to bone marrow transplant. For one, it is difficult to find compatible donors. Surviving T cells in the patient may attack the donor marrow, and donor T cells may attack the patient's tissues (the *graft-versus-host response*). To inhibit graft rejection, the patient must take immunosuppressant drugs for life. These drugs leave a person vulnerable to infection and have many other adverse side effects. Infections are sometimes contracted from the donated marrow itself. In short, marrow transplant is a high-risk procedure; up to one-third of patients die from complications of treatment.

An alternative with several advantages is to use blood from placentas, which are normally discarded at every childbirth. Placental blood contains more stem cells than adult bone marrow, and is less likely to carry infectious microbes. With the parents' consent, it can be harvested from the umbilical cord with a syringe; and it can be stored almost indefinitely, frozen in liquid nitrogen at cord blood banks. The immature immune cells in cord blood have less tendency to attack the recipient's tissues; thus, cord blood transplants have lower rejection rates and do not require as close a match between donor and recipient, meaning that more donors are available to a patient in need. Pioneered in the 1980s, cord blood transplants have successfully treated leukemia and a wide range of other blood diseases. Efforts are being made to further improve the procedure by stimulating placental stem cells to multiply before the transplant, and by removing placental T cells that may react against the recipient.



Figure 19.6 **Chemical Basis of the ABO Blood Types.** Blood types are determined by the chemistry of glycolipids of the RBC plasma membrane. Types A, B, AB, and O erythrocytes differ only in the terminal three to four carbohydrates of the glycolipid molecules. All of them end with galactose and fucose, but they differ in the presence or absence, and type, of additional sugar bonded to the galactose. The additional sugar is absent in type O; it is *N*-acetylgalactosamine in type A; it is another galactose in type B; and type AB cells have both the type A and B chains.

figure 19.6 shows how the ABO types differ in this regard. The glycolipids act as *antigens,* substances capable of evoking an immune reaction. The blood plasma contains *antibodies* that react against incompatible antigens on foreign RBCs.

RBC antigens and plasma antibodies determine the compatibility of donor and recipient blood in transfusions. For example, a person with blood type A has anti-B antibodies in the blood plasma. If this person is mistakenly given a transfusion of type B blood, those antibodies attack the donor RBCs. The RBCs agglutinate—they form clumps that obstruct the circulation in small blood vessels, with devastating consequences for such crucial organs as the brain, heart, lungs, and kidneys. The agglutinated RBCs also rupture *(hemolyze)* and release their hemoglobin. This free hemoglobin is filtered out by the kidneys, clogs the microscopic kidney tubules, and can cause death from renal failure within a week or so. The same can happen if a type B person receives type A blood, or if a type O person receives either type A or type B. Incompatibility of Rh types between the mother and fetus sometimes causes severe anemia in the newborn infant *(hemolytic disease of the newborn).*

Apply What You Know

Why might a court of law be interested even in human blood types that have no connection to disease?

Before You Go On

Answer the following questions to test your understanding of the preceding section:

5. What are the two main functions of RBCs?
6. Define *hematocrit* and *RBC count,* and state some normal clinical values for each.
7. Describe the structure of a hemoglobin molecule. Explain where O_2 and CO_2 are carried on a hemoglobin molecule.
8. Name the stages in the production of an RBC, and state the differences between them.
9. Explain what plasma and RBC components are responsible for blood types, and why blood types are clinically important.

19.3 Leukocytes

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the appearance of the five kinds of leukocytes;
b. explain the function of WBCs in general and the individual roles of each WBC type;
c. describe the formation and life history of WBCs; and
d. describe the production, death, and disposal of leukocytes.

Form and Function

Leukocytes, or **white blood cells (WBCs),** are the least abundant formed elements, totaling only 5,000 to 10,000 WBCs/μL. Yet we cannot live long without them, because they afford protection against infectious microorganisms and other pathogens. WBCs are easily recognized in stained blood films because they have conspicuous nuclei that stain from light violet to dark purple with the most common blood stains. They are much more abundant in the body than their low number in blood films would suggest, because they spend only a few hours in the bloodstream, then migrate through the walls of the capillaries and venules and spend the rest of their lives in the connective tissues. It's as if the bloodstream was merely the subway that the WBCs take to work; in blood films, we see only the ones on their way to work, not the WBCs already in the tissues.

Leukocytes differ from erythrocytes in that they retain their organelles throughout life; thus, when viewed with the transmission electron microscope, they show a complex internal structure (fig. 19.7). Among these organelles are the usual instruments of protein synthesis—the nucleus, rough endoplasmic reticulum, ribosomes, and Golgi complex—for leukocytes must synthesize proteins in order to carry out their functions. Some of these proteins are packaged into lysosomes and other organelles, which appear as conspicuous cytoplasmic granules that distinguish one WBC type from another.

Types of Leukocytes

As outlined at the beginning of this chapter, there are five kinds of leukocytes (table 19.4). They are distinguished from each other by their relative size and abundance, the size and shape of their nuclei, the presence or absence of certain cytoplasmic granules, the coarseness and staining properties of those granules, and most importantly by their functions. All WBCs have lysosomes called **nonspecific (azurophilic[9]) granules** in the cytoplasm, so named because they absorb the blue or violet dyes of blood stains. Three of the five WBC types—neutrophils, eosinophils, and basophils—are called **granulocytes** because they also have various types of **specific granules** that stain conspicuously and distinguish each cell type from the others. Basophils are named for the fact that their specific granules stain intensely with methylene blue, a basic dye in a common blood staining mixture called Wright's stain. Eosinophils are so named because their specific granules stain with eosin, an acidic dye in Wright's stain. The specific granules of neutrophils do not stain intensely with either dye. Specific granules contain enzymes and other chemicals employed in defense against pathogens. The two remaining WBC types—monocytes and lymphocytes—are called **agranulocytes** because they lack specific granules. Nonspecific granules are inconspicuous to the light microscope, and these cells therefore have relatively clear-looking cytoplasm.

Bear in mind that the color of WBC nuclei (usually violet) and the colors described for their granules are not natural colors. They result from the dyes used to stain blood films, and they vary depending on what stain was used on any blood films you may study. The **differential count** given for each type of WBC refers to the number of cells of that type relative to the other WBCs.

Granulocytes

- **Neutrophils** (NEW-tro-fills) are the most abundant WBCs—constituting 60% to 70% of the circulating leukocytes. The nucleus is clearly visible and, in a mature neutrophil, typically consists of three to five lobes connected by slender nuclear strands. These strands are sometimes so delicate that they are scarcely visible, and the neutrophil may seem as if it has multiple nuclei. Young neutrophils have an undivided nucleus often shaped like a band; thus, they are called *band cells* or *stab[10] cells.* Neutrophils are also called *polymorphonuclear leukocytes (PMNs)* because of their varied nuclear shapes.

  The cytoplasm contains fine reddish to violet specific granules, which contain lysozyme and other antimicrobial



Figure 19.7 **Structure of an Eosinophil.** In contrast to an RBC, the WBC cytoplasm is crowded with organelles, including a nucleus.

---

[9] *azuro* = blue; *philic* = loving

[10] *stab* = band, bar (German)

TABLE 19.4 The White Blood Cells (Leukocytes)

Neutrophils

Percentage of WBCs	60%–70%
Mean count	4,150 cells/µL
Diameter	9–12 µm

Appearance*

Nucleus usually with 3–5 lobes in S- or C-shaped array
Fine reddish to violet specific granules in cytoplasm

Differential Count

Increases in bacterial infections

Functions

Phagocytize bacteria
Secrete antimicrobial chemicals



Neutrophils

© Ed Reschke/Getty Images

Eosinophils

Percentage of WBCs	2%–4%
Mean count	170 cells/µL
Diameter	10–14 µm

Appearance*

Nucleus usually with two large lobes connected by thin strand
Large orange-pink specific granules in cytoplasm

Differential Count

Fluctuates greatly from day to night, seasonally, and with phase of menstrual cycle
Increases in parasitic infections, allergies, collagen diseases, and diseases of spleen and central nervous system

Functions

Phagocytize antigen–antibody complexes, allergens, and inflammatory chemicals
Secrete enzymes that weaken or destroy parasites such as worms



Eosinophil

© Ed Reschke

Basophils

Percentage of WBCs	<0.5%
Mean count	40 cells/µL
Diameter	8–10 µm

Appearance*

Nucleus large and irregularly shaped, but typically obscured from view
Coarse, abundant, dark violet specific granules in cytoplasm

Differential Count

Relatively stable
Increases in chickenpox, sinusitis, diabetes mellitus, myxedema, and polycythemia

Functions

Secrete histamine (a vasodilator), which increases blood flow to a tissue
Secrete heparin (an anticoagulant), which promotes mobility of other WBCs by preventing clotting



Basophil

© Ed Reschke/Getty Images

TABLE 19.4 The White Blood Cells (Leukocytes) (continued)

Monocytes



Monocyte

© Michael Ross/Science Source

Percentage of WBCs	3%–8%
Mean count	460 cells/µL
Diameter	12–15 µm

Appearance*

Nucleus ovoid, kidney-shaped, or horseshoe-shaped
Abundant light violet cytoplasm with sparse, fine, nonspecific granules
Sometimes very large with stellate or polygonal shapes

Differential Count

Increases in viral infections and inflammation

Functions

Differentiate into macrophages (large phagocytic cells of the tissues)
Phagocytize pathogens, dead neutrophils, and debris of dead cells
Present antigens to activate other cells of immune system

Lymphocytes



Lymphocyte

© Michael Ross/Science Source

Percentage of WBCs	25%–33%
Mean count	2,200 cells/µL
Diameter	
Small class	5–8 µm
Medium class	10–12 µm
Large class	14–17 µm

Appearance*

Nucleus round, ovoid, or slightly dimpled on one side, of uniform dark violet color
In small lymphocytes, nucleus fills nearly all of the cell and leaves only a scanty rim of clear, light blue cytoplasm
In larger lymphocytes, cytoplasm is more abundant; large lymphocytes may be hard to differentiate from monocytes

Differential Count

Increases in diverse infections and immune responses

Functions

Several functional classes indistinguishable by light microscopy
Destroy cancer cells, cells infected with viruses, and foreign cells
Present antigens to activate other cells of immune system
Coordinate actions of other immune cells
Secrete antibodies
Serve in immune memory

*Appearance pertains to blood films dyed with Wright's stain.

agents. The individual granules are very small, barely visible with the light microscope, but they give the cytoplasm a pale lilac color.

Neutrophils are aggressive antibacterial cells. They have two ways of destroying bacteria. One is to phagocytize and digest them. The other is to release a potent mix of toxic chemicals, including hypochlorite (HClO) (the active agent in household bleach) and the superoxide anion ($O_2\bullet^-$), which reacts with hydrogen ions to produce hydrogen peroxide (H_2O_2). Just as bleach and hydrogen peroxide are often used around the home as disinfectants, they are deadly to bacteria in the tissues. These chemicals form a **killing zone** around the neutrophil, lethal to the invaders but also to the neutrophil itself. Neutrophils are thus the body's suicidal guardians against infection. Bacterial infections commonly stimulate neutrophilia—a rise in neutrophil count—as this army of cells is mobilized against them.

- **Eosinophils** (EE-oh-SIN-oh-fills) are harder to find in a blood film because they are only 2% to 4% of the WBC population. The eosinophil count fluctuates greatly, however, from day to night, seasonally, and with the phase of the menstrual cycle. It rises *(eosinophilia)* in allergies, parasitic infections, collagen diseases, and diseases of the spleen and central nervous system. Although relatively scanty in the blood, eosinophils are abundant in the mucous membranes of the respiratory, digestive, and lower urinary tracts. The eosinophil nucleus usually has two large lobes connected by a thin strand, and the cytoplasm has an abundance of coarse rosy to pinkish orange specific granules. Eosinophils secrete chemicals that weaken or destroy relatively large parasites such as hookworms and tapeworms, too big for any one WBC to phagocytize. Eosinophils also phagocytize and dispose of inflammatory chemicals, antigen–antibody complexes (masses of antigen molecules stuck together by antibodies), and allergens (foreign antigens that trigger allergies).

- **Basophils** (BASE-oh-fills) are the rarest of the WBCs and, indeed, of all formed elements, usually less than 0.5% of the WBC count. They can be recognized mainly by an abundance of very coarse, dark violet specific granules. The nucleus is largely hidden from view by these granules, but is large, pale, and typically S- or U-shaped. Basophils secrete two chemicals that aid in the body's defense processes: (1) **histamine,** a vasodilator that widens the blood vessels, speeds the flow of blood to an injured tissue, and makes the blood vessels more permeable so that blood components such as neutrophils and clotting proteins can get into the connective tissues more quickly; and (2) **heparin,** an anticoagulant that inhibits blood clotting and thus promotes the mobility of other WBCs in the area. They also release chemical signals that attract eosinophils and neutrophils to a site of infection. Basophil count often rises in diabetes, chickenpox, and various other diseases.

Agranulocytes

- **Monocytes** (MON-oh-sites) are large WBCs, often two or three times the diameter of an RBC. They number about 3% to 8% of the WBC count. The nucleus is large and clearly visible, often relatively light violet, and typically ovoid, kidney-shaped, or horseshoe-shaped. The cytoplasm is abundant and contains sparse, fine granules. In prepared blood films, monocytes often assume sharply angular to spiky shapes (see fig. 19.1). The monocyte count rises in inflammation and viral infections. Monocytes go to work only after leaving the bloodstream and transforming into large tissue cells called **macrophages**[11] (MAC-ro-fay-jez). In one hour, a macrophage can consume an amount of foreign matter equivalent to 25% of its own volume. They destroy dead or dying host and foreign cells, pathogenic chemicals and microorganisms, and other foreign matter. They also chop up or "process" foreign antigens and "display" fragments of them on the cell surface to alert the immune system to the presence of a pathogen. Thus, they and a few other cells are called *antigen-presenting cells (APCs).* There are several kinds of macrophages in the body descended from monocytes or from the same hemopoietic stem cells as monocytes. Some of them have special names, such as the *microglia* of the central nervous system, *alveolar macrophages (dust cells)* of the lungs, and *hepatic macrophages (Kupffer cells)* of the liver.
- **Lymphocytes** (LIM-fo-sites) include the smallest WBCs; at 5 to 17 μm in diameter, they range from smaller than RBCs to two and a half times as large, but those in circulating blood are generally at the small end of the range. They are second to neutrophils in abundance and are thus quickly spotted when you examine a blood film. They number about 2,200 cells/μL and are 25% to 33% of the WBC count. The lymphocyte nucleus is round, ovoid, or slightly dimpled on one side. It usually stains dark violet and fills nearly the entire cell, especially in small lymphocytes. The cytoplasm stains light blue and forms a narrow and often barely detectable rim around the nucleus, although it is more abundant in the larger lymphocytes. Small lymphocytes are sometimes difficult to distinguish from basophils, but most basophils are conspicuously grainy whereas the lymphocyte nucleus is uniform or merely mottled. Basophils also lack the rim of clear cytoplasm seen in most lymphocytes. Large lymphocytes can be difficult to distinguish from monocytes.

  The lymphocyte count increases in diverse infections and immune responses. Some of them function in nonspecific defense of the body against viruses and cancer, but most of them are involved in *adaptive immunity,* a defense in which the body recognizes a certain antigen it has encountered before and mounts such a quick response that a person notices little or no illness. The various lymphocytes are not distinguishable by light microscopy, but differ in their functions. As you will see in chapter 22, there are three functional classes of lymphocytes—*NK (natural killer) cells, B cells,* and *T cells,* which attack different categories of pathogens.

The Leukocyte Life Cycle

Leukopoiesis (LOO-co-poy-EE-sis), the production of white blood cells, begins with the same hemopoietic stem cells (HSCs) as erythropoiesis. Some HSCs differentiate into the distinct types of colony-forming units, which then go on to produce any of three cell lines (fig. 19.8)—(1) *myeloblasts*, committed to producing the three kinds of granulocytes; (2) *monoblasts*, which produce monocytes; or (3) *lymphoblasts*, which produce lymphocytes.

Granulocytes and monocytes stay in the red bone marrow until they are needed; the marrow contains 10 to 20 times as many of these cells as the circulating blood does. Lymphocytes, by contrast, begin developing in the bone marrow but then migrate elsewhere. **B lymphocytes (B cells)** mature in the bone marrow and some remain there, while others disperse and colonize the lymph nodes, spleen, tonsils, and mucous membranes. To remember their site of maturation, it may help to think "B for bone marrow," although these cells were actually named for an organ in chickens (the *bursa of Fabricius*) where they were discovered. **T lymphocytes (T cells)** begin development in the bone marrow but then migrate

---

[11] *macro* = big; *phage* = eater


Hemopoietic stem cell
Colony-forming units (CFUs)
Precursor cells
Mature cells
Eosinophilic CFU
Eosinophilic myeloblast
Eosinophilic promyelocyte
Eosinophilic myelocyte
Eosinophil
Basophilic CFU
Basophilic myeloblast
Basophilic promyelocyte
Basophilic myelocyte
Basophil
Neutrophilic CFU
Neutrophilic myeloblast
Neutrophilic promyelocyte
Neutrophilic myelocyte
Neutrophil
Monocytic CFU
Monoblast
Promonocyte
Monocyte
B prolymphocyte
B lymphocyte
Lymphocytic CFU
Lymphoblast
T prolymphocyte
T lymphocyte
NK prolymphocyte
NK cell

Figure 19.8 **Leukopoiesis.** Stages in the development of leukocytes.
• *Explain the meaning and relevance of the combining form* myelo-, *seen in so many of these cell names.*

to the thymus (a gland in the mediastinum just above the heart) and mature there. The *T* stands for *thymus-dependent.* Mature T lymphocytes disperse from the thymus and colonize the same organs as B lymphocytes. **Natural killer (NK) cells** develop in the bone marrow like B cells.

Circulating WBCs do not stay in the blood for very long. Granulocytes circulate for 4 to 6 hours and then migrate into the tissues, where they live for another 4 or 5 days. Monocytes travel in the blood for 10 or 20 hours, then migrate into the tissues and transform into a variety of macrophages, which live as long as a few

DEEPER INSIGHT 19.2

The Complete Blood Count

One of the most common clinical procedures in both routine physical examinations and the diagnosis of disease is a *complete blood count (CBC).* The CBC yields a highly informative profile of data on multiple blood values: the number of RBCs, WBCs, and platelets per microliter of blood; the relative numbers (percentages) of each WBC type, called a *differential WBC count;* hematocrit; hemoglobin concentration; and various *RBC indices* such as RBC size *(mean corpuscular volume, MCV)* and hemoglobin concentration per RBC *(mean corpuscular hemoglobin, MCH).*

RBC and WBC counts used to require the microscopic examination of films of diluted blood on a calibrated slide, and a differential WBC count required examination of stained blood films. Today, most laboratories use *electronic cell counters.* These devices draw a blood sample through a very narrow tube with sensors that identify cell types and measure cell sizes and hemoglobin content. These counters give faster and more accurate results based on much larger numbers of cells than the old visual methods. However, cell counters still misidentify some cells, and a medical technologist must review the results for suspicious abnormalities and identify cells that the instrument cannot.

The wealth of information gained from a CBC is too vast to give more than a few examples here. Various forms of anemia are indicated by low RBC counts or abnormalities of RBC size, shape, and hemoglobin content. A platelet deficiency can indicate an adverse drug reaction. A high neutrophil count suggests bacterial infection, and a high eosinophil count suggests an allergy or parasitic infection. Elevated numbers of specific WBC types or WBC stem cells can indicate various forms of leukemia. If a CBC does not provide enough information or if it suggests other disorders, additional tests may be done, such as coagulation time and bone marrow biopsy.

years. Lymphocytes, responsible for long-term immunity, have life spans ranging from weeks to decades.

When leukocytes die, they are generally phagocytized and digested by macrophages. Dead neutrophils, however, are responsible for the creamy color of pus, and are sometimes disposed of by the rupture of a blister onto the skin surface.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

10. What is the purpose of WBCs in general?
11. Name the five kinds of WBCs and state the specific functions of each.
12. Describe the key features that enable one to microscopically identify each WBC type.
13. What are macrophages? What class of WBCs do they arise from? Name some types of macrophages.

19.4 Platelets

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the structure of blood platelets;
b. explain the multiple roles played by platelets in hemostasis and blood vessel maintenance;
c. describe platelet production and state their longevity; and
d. describe the general processes of hemostasis.

Circulatory systems developed very early in animal evolution, and with them evolved mechanisms for stopping leaks, which are potentially fatal. Platelets are the major players in cessation of bleeding, and are the focus of this section.

Form and Function

Platelets are not cells but small fragments of marrow cells called *megakaryocytes.* They are the second most abundant formed elements, after erythrocytes; a normal platelet count in blood from a fingerstick ranges from 130,000 to 400,000 platelets/μL (averaging about 250,000). The platelet count can vary greatly, however, under different physiological conditions and in blood samples taken from various places in the body. In spite of their numbers, platelets are so small (2 to 4 μm in diameter) that they contribute even less than WBCs to the blood volume.

Platelets have a complex internal structure that includes lysosomes, mitochondria, microtubules and microfilaments, granules filled with platelet secretions, and a system of channels called the **open canalicular system,** which opens onto the platelet surface (fig. 19.9a). They have no nucleus. When activated, they form pseudopods and are capable of ameboid movement.

Despite their small size, platelets have a greater variety of functions than any of the true blood cells:

- They secrete *vasoconstrictors,* chemicals that cause spasmodic constriction of broken vessels and thus help reduce blood loss.
- They stick together to form temporary *platelet plugs* to seal small breaks in injured blood vessels.
- They secrete *procoagulants,* or clotting factors, which promote blood clotting.
- They initiate the formation of a clot-dissolving enzyme that dissolves blood clots that have outlasted their usefulness.
- They secrete chemicals that attract neutrophils and monocytes to sites of inflammation.
- They internalize and destroy bacteria.
- They secrete *growth factors* that stimulate mitosis in fibroblasts and smooth muscle and thus help to maintain and repair blood vessels.

Platelet Production

The production of platelets is a division of hemopoiesis called **thrombopoiesis.** (Platelets are occasionally called *thrombocytes,*[12] but this term is now usually reserved for nucleated true cells in other animals such as birds and reptiles.) Some hemopoietic stem cells produce receptors for the hormone *thrombopoietin,* thus becoming *megakaryoblasts,* cells committed to the platelet-producing line. The megakaryoblast duplicates its DNA repeatedly without undergoing nuclear or cytoplasmic division. The result is a **megakaryocyte**[13] (meg-ah-CAR-ee-oh-site), a gigantic cell up to 150 µm in diameter, visible to the naked eye, with a huge multilobed nucleus and multiple sets of chromosomes (fig. 19.9b). Most megakaryocytes live in the red bone marrow adjacent to blood-filled spaces called sinusoids, which are lined with a thin simple squamous epithelium called the endothelium (see fig. 22.9, p. 617).

A megakaryocyte sprouts long, beaded tendrils called *proplatelets* that protrude through the endothelium into the blood of the sinusoid. The blood flow shears off the proplatelets, which break up into platelets as they travel in the bloodstream. Much of this breakup is thought to occur in the small vessels of the lungs; proplatelets are relatively abundant in blood entering the lungs, but blood exiting the lungs shows more platelets and few proplatelets. About 25% to 40% of the platelets are stored in the spleen and released as needed. The remainder circulate freely in the blood and live for about 5 or 6 days.

Hemostasis

Hemostasis[14] is the cessation of bleeding. The details of hemostasis are beyond the scope of an anatomy textbook, but the basic roles of platelets in the process will be briefly surveyed here. Upon injury to a blood vessel, platelets release *serotonin.* This chemical stimulates *vasoconstriction,* or narrowing of the blood vessel, to reduce blood loss. Platelets also adhere to the vessel wall and to each other, forming a sticky mass called a *platelet plug.* Platelet plugs temporarily seal breaks in small blood vessels. Platelets and injured tissues around the blood vessel also release *clotting factors.* Through a series of enzymatic reactions, clotting factors convert the plasma protein *fibrinogen* into the sticky protein *fibrin.* Fibrin adheres to the wall of the blood vessel, and as blood cells and platelets arrive, many of them stick to the fibrin like insects in a spider web. The resulting mass of fibrin, platelets, and blood cells (fig. 19.10) forms a clot that ideally seals the break in the blood vessel long enough for the vessel to heal.



© NIBSC/SPL/Science Source

Figure 19.9 **Platelets.** (a) Structure of blood platelets (TEM). (b) Platelets being produced by the shearing of proplatelets from a megakaryocyte. Note the size of the megakaryocyte relative to the RBCs, WBCs, and platelets. AP|R



© Professor Pietro M. Motta/SPL/Science Source

Figure 19.10 **A Blood Clot (SEM).** Platelets are seen trapped in a sticky protein mesh.

- *What is the name of this protein?*

---

[12] *thrombo* = clotting; *cyte* = cell

[13] *mega* = giant; *karyo* = nucleus; *cyte* = cell

[14] *hemo* = blood; *stasis* = stability

Once the leak is sealed and the crisis has passed, platelets secrete *platelet-derived growth factor (PDGF),* a substance that stimulates fibroblasts and smooth muscle to proliferate and replace the damaged tissue of the blood vessel. When tissue repair is completed and the blood clot is no longer needed, the clot must be disposed of. Platelets then secrete *factor XII,* a protein that initiates a series of reactions leading to the formation of a fibrin-digesting enzyme called *plasmin.* Plasmin dissolves the old blood clot.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

14. List several functions of blood platelets.
15. How are blood platelets produced? How long do they live?
16. Briefly describe the stages in which platelets help to stop bleeding and repair a damaged blood vessel.

19.5 Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe changes that occur in the blood in old age; and
b. describe some common abnormalities of RBC, WBC, and platelet count and morphology, and the consequences of these abnormalities.

Hematology in Old Age

We have considered the embryonic origin and ongoing hemopoietic development of the blood in previous sections. At the other end of the life span, aging has multiple effects on the blood. Evidence suggests that the baseline rate of erythropoiesis does not change much with age; cell counts, hemoglobin concentration, and other variables are about the same among healthy people in their 70s as in the 30s. However, older people do not adapt well to stress on the hemopoietic system, perhaps because of the senescence of other organ systems.

Factors that cause anemia in older people are very complicated and interrelated. It can result from nutritional deficiencies, inadequate exercise, or specific diseases. The normal atrophy of the kidneys in old age can be a contributing factor, since the kidneys secrete erythropoietin, the principal stimulus for RBC production. There may also be an intrinsic limit to how many times the hemopoietic stem cells can divide and continue producing new blood cells. It is almost impossible to determine whether aging alone causes anemia in the absence of other contributing factors such as poor exercise or nutritional habits.

Thrombosis, the abnormal clotting of blood in an unbroken blood vessel, becomes increasingly problematic in old age. Plaques of atherosclerosis in the blood vessels can act as sites of blood clotting. The blood clots especially easily in the veins, where blood flow is slowest. About 25% of people over age 50 experience venous blockage by thrombosis, especially people who do not exercise regularly and people confined to a bed or wheelchair. Stationary blood clots can cause stroke, heart failure, or kidney failure, and clots can break free and travel in the bloodstream (a condition called *thromboembolism*) until they lodge in small vessels and cut off the blood flow to other organs. Pulmonary failure often results from thromboembolism.

Disorders of the Blood

We conclude with a survey of some clinical aspects of hematology, especially disorders that affect the relative numbers of formed elements and thus the appearance of stained blood films, or that alter the appearance of the individual formed elements. Some common nonstructural blood disorders are described in table 19.5.

Erythrocyte Disorders

The two principal RBC disorders are **anemia**[15] (an RBC or hemoglobin deficiency) and **polycythemia**[16] (an RBC excess). The latter is also known as *erythrocytosis.*

There are three fundamental categories of anemia:

1. **Depressed erythropoiesis or hemoglobin synthesis.** In such cases, erythropoiesis fails to keep pace with the normal death of RBCs. We have already seen that atrophy of the kidneys in the elderly can reduce erythropoietic rates because of a deficiency of erythropoietin. At any age, a dietary deficiency of iron or certain vitamins can cause nutritional anemias (such as *iron-deficiency anemia*). Radiation, viruses, and some poisons cause anemia by destroying bone marrow.
2. **Hemolytic anemia.** This is a result of rapid RBC destruction exceeding the rate of erythropoiesis. Hemolytic anemia can result from a variety of poisons, drug reactions, sickle-cell disease, animal venoms, or blood-destroying parasitic infections such as malaria.
3. **Hemorrhagic anemia.** This is an RBC deficiency resulting from bleeding. It can be a consequence of trauma such as gunshot, automobile, or battlefield injuries; hemophilia; bleeding ulcers; ruptured aneurysms; or heavy menstruation.

Although anemia most obviously affects the RBC count, it can also affect RBC morphology. *Thalassemia,* for example, is a hereditary blood disease among people of Mediterranean descent. It is characterized by deficient hemoglobin synthesis, and not only is the RBC count reduced but the existing RBCs are *microcytic* (abnormally small) and *hypochromic* (pale). Iron-deficiency anemia is characterized by these structural abnormalities as well

---

[15] *an* = without; *em* = blood; *ia* = condition
[16] *poly* = many; *cyt* = cells; *hemia* = blood condition

TABLE 19.5 Some Disorders of the Blood

Disseminated intravascular coagulation (DIC)	Widespread clotting within unbroken vessels, limited to one organ or occurring throughout the body. Usually triggered by septicemia but also occurs when blood circulation slows markedly (as in cardiac arrest). Marked by widespread hemorrhaging, congestion of the vessels with clotted blood, and tissue necrosis in blood-deprived organs.
Embolism	The presence of any abnormal object *(embolus)* traveling in the bloodstream, such as an air bubble *(air embolism),* agglutinated RBCs or bacteria, or traveling blood clot *(thromboembolism).* Presents a danger of blocking small blood vessels and shutting off the blood flow to vital tissues, thus causing stroke, heart failure, kidney failure, or pulmonary failure.
Hemophilia	Abnormally slow blood clotting as a result of the hereditary deficiency of a clotting factor, usually factor VIII (a liver product). Prolonged bleeding results in the painful pooling of clotted blood *(hematomas)* in such sites as the muscles and joints, or in fatal blood loss. Treatable with injections of the missing clotting factor.
Infectious mononucleosis	Infection of B lymphocytes with Epstein–Barr virus. Usually transmitted by exchange of saliva, as in kissing; most common in adolescents and young adults. Causes fever, fatigue, sore throat, inflamed lymph nodes, and leukocytosis. Usually self-limiting and resolves within a few weeks.
Septicemia	Bacteria in the bloodstream, stemming from infection elsewhere in the body. Often causes fever, chills, and nausea, and may cause septic shock.

Disorders Described Elsewhere

Anemia	534
Leukemia	535
Leukocytosis	535
Leukopenia	535
Polycythemia	535
Sickle-cell disease	536
Thalassemia	534
Thrombocytopenia	535
Thrombosis	534

as *poikilocytosis,*[17] in which RBCs assume teardrop, pencil, and other variable and abnormal shapes. Sickle-cell disease is another well-known hereditary anemia with abnormal RBC morphology (see Deeper Insight 19.3).

Whatever the cause of anemia, it may result in tiredness, lethargy, shortness of breath, or more serious consequences—organ deterioration (necrosis) stemming from oxygen deprivation (hypoxia).

Polycythemia (POL-ee-sih-THEME-ee-uh), an excess RBC count, can result from cancer of the bone marrow *(primary polycythemia)* or from a multitude of other conditions *(secondary polycythemia).* The latter include abnormally high oxygen demand (as in people who engage in overzealous aerobic exercise) or low oxygen supply (as in people who live at high altitudes or suffer lung diseases such as emphysema). RBC counts can rise as high as 11 million RBCs/µL and hematocrit as high as 80%. The thick blood sludges in the vessels, tremendously increases blood pressure, and puts a dangerous strain on the cardiovascular system that can lead to heart failure or stroke.

Leukocyte Disorders

A WBC deficiency is called **leukopenia,** and can result from heavy metal poisoning, radiation exposure, and infectious diseases such as measles, chickenpox, polio, and AIDS. Such a deficiency of disease-fighting WBCs leaves a person susceptible to *opportunistic infections,* infections that a normal person could fight off but that can be overwhelming or even life-threatening to a person with a compromised immune system. An abnormally high WBC count is called **leukocytosis.** It usually results from an infection or allergy, but can also stem from such causes as emotional stress and dehydration (WBCs become more concentrated when water is lost from the bloodstream). **Leukemia** is a cancer of the hemopoietic tissues that results in a high number of circulating WBCs. It, too, makes a person vulnerable to opportunistic infection, because even though the WBC count is high, these are immature WBCs incapable of performing their normal defensive roles—like having a large army of children. Leukemia tends to lead to anemia and thrombocytopenia (see the next section) because stem cells are diverted into the rapid production of WBCs instead of RBCs and platelets.

Platelet Disorders

Thrombocytopenia, a platelet count less than 100,000/µL, results from such causes as leukemia, radiation, or bone marrow poisoning. It results not only in impaired clotting when a vessel is injured, but also in increased spontaneous bleeding because of a loss of the normal blood vessel maintenance function of platelets.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

17. What are the terms for an excess and a deficiency of RBCs? An excess and a deficiency of WBCs?
18. What are the three basic categories of anemia?
19. In what way are leukocytosis and leukemia alike? What is the difference between them?
20. Describe some causes and effects of thrombocytopenia.

---

[17] *poikilo* = variable; *cyt* = cell; *osis* = condition

DEEPER INSIGHT 19.3

Sickle-Cell Disease

Sickle-cell disease is a hereditary hemoglobin defect occurring mostly among people of African descent; its symptoms occur in about 1.3% of American blacks, and about 8.3% are asymptomatic carriers with the potential to pass it to their children. The disease is caused by a defective gene that results in the substitution of valine for a glutamic acid in each beta hemoglobin chain. The abnormal hemoglobin (HbS) turns to gel at low oxygen levels, as when blood passes through the oxygen-hungry skeletal muscles. The RBCs become elongated, stiffened, and pointed (sickle-shaped; fig 19.11). These deformed, inflexible cells cannot pass freely through the tiny blood capillaries, and they tend to adhere to each other and to the capillary wall. Thus, they congregate in the small blood vessels and block the circulation. Obstruction of the circulation produces severe pain and can lead to kidney or heart failure, stroke, or paralysis, among many other effects. The spleen removes defective RBCs faster than they can be replaced, thus leading to anemia and poor physical and mental development of the individual. Without treatment, a child with sickle-cell disease has little chance of living to age 2, and even with the best treatment, few victims live to age 50.

Sickle-cell disease originated in areas of Africa where millions of lives are lost to malaria. Malarial parasites normally invade and reproduce in RBCs, but they cannot survive in RBCs with HbS hemoglobin. Thus the sickle-cell gene confers resistance to malaria, even in individuals who are heterozygous for it (carry only one copy of the gene) and do not have sickle-cell disease. The lives saved by HbS in Africa far outnumber the deaths from sickle-cell disease, so natural selection favors the persistence of the gene rather than its elimination. But in North America, where malaria is rare, the prevalence of the gene has declined because there is little evolutionary benefit from possessing it and so many of those who do possess it die young, before reproducing.



© Eye of Science/Science Source

Figure 19.11 **Sickle-Cell Disease.** The lower left RBC has become deformed into the pointed sickle shape diagnostic of this genetic disorder.

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

19.1 Introduction (p. 520)

1. The components of the circulatory system and the distinction between the circulatory system and cardiovascular system
2. Functions of the circulatory system
3. The proportion of formed elements to plasma in blood
4. The seven major types of formed elements
5. The composition of blood plasma
6. The types and sources of plasma proteins

19.2 Erythrocytes (p. 523)

1. The functions, shape, and contents of erythrocytes (RBCs)
2. The functions of hemoglobin
3. The meanings and typical values, including units of measurement, of *RBC count, hematocrit,* and *hemoglobin concentration;* and how men and women differ in these values
4. The structure of hemoglobin and where oxygen and carbon dioxide bind to the molecule
5. The meaning of *hemopoiesis,* and the organs and tissues in which it occurs both before and after birth
6. The stages of erythropoiesis and the identity of the hormone that stimulates this process
7. The life span of an RBC
8. ABO and Rh blood types; the chemical basis of differences between ABO types; and the relevance of blood types to transfusion and pregnancy

19.3 Leukocytes (p. 527)

1. The total number of leukocytes (WBCs) per microliter of blood
2. How the internal structure of a WBC differs from that of an RBC
3. The general function of WBCs
4. The distinction between granulocytes and agranulocytes
5. The three types of granulocytes, two types of agranulocytes, and how all five of these WBC types can be visually recognized in stained blood smears
6. The primary function of neutrophils and their methods of carrying it out
7. The functions of eosinophils

8. The two secretions of basophils and the function of each secretion
9. The relationship of monocytes to macrophages; the two principal functions of macrophages
10. The general functions and the three major families of lymphocytes
11. The three major cell lines of leukopoiesis
12. The roles of the red bone marrow and thymus in leukopoiesis
13. The migrations and life span of various WBC types, and the fate of expired WBCs

19.4 Platelets (p. 532)

1. The origin and structure of blood platelets, and why they are considered formed elements but not cells
2. The diverse functions of platelets
3. The process of thrombopoiesis
4. The roles that platelets play in blood clotting and the disposal of old clots

19.5 Clinical Perspectives (p. 534)

1. Ways in which the blood and hemopoietic system change in old age and some reasons for the changes
2. The meaning of *anemia;* its three basic categories; and its effects
3. The meaning of *polycythemia;* its causes; and its effects
4. The meaning of *leukopenia;* its causes; and its effects
5. The meaning and causes of *leukocytosis*
6. The meaning of *leukemia;* its effects on infection resistance; and its effects on RBC and platelet counts
7. The meaning, causes, and effects of *thrombocytopenia*

Testing Your Recall

1. Antibodies belong to a class of plasma proteins called
   a. albumins.
   b. gamma globulins.
   c. alpha globulins.
   d. procoagulants.
   e. agglutinins.
2. Serum is blood plasma minus its
   a. sodium ions.
   b. calcium ions.
   c. fibrinogen.
   d. albumin.
   e. cells.
3. The most abundant formed elements seen in most stained blood films are
   a. erythrocytes.
   b. neutrophils.
   c. lymphocytes.
   d. platelets.
   e. monocytes.
4. Heparin and histamine are secreted by
   a. plasma cells.
   b. basophils.
   c. B lymphocytes.
   d. platelets.
   e. neutrophils.
5. _____ have a finely granular cytoplasm and a nucleus typically divided into three to five lobes.
   a. Basophils
   b. Eosinophils
   c. Lymphocytes
   d. Monocytes
   e. Neutrophils
6. Platelets have all of the following functions *except*
   a. coagulation.
   b. plugging broken blood vessels.
   c. stimulating vasoconstriction.
   d. transporting oxygen.
   e. recruiting neutrophils.
7. Which of these is a granulocyte?
   a. a monocyte
   b. a lymphocyte
   c. a macrophage
   d. an eosinophil
   e. an erythrocyte
8. Allergies stimulate a rise in _____ count.
   a. erythrocyte
   b. platelet
   c. eosinophil
   d. monocyte
   e. neutrophil
9. Anemia is most likely to result from failure of which of these organs?
   a. the heart
   b. the lungs
   c. the pituitary gland
   d. the kidneys
   e. the spleen
10. Oxygen binds to the _____ of a hemoglobin molecule.
   a. valine
   b. Fe
   c. globin
   d. spectrin
   e. beta chain
11. Production of all the formed elements of blood is called _____.
12. The percentage of blood volume composed of RBCs is called the _____.
13. Microglia and Kupffer cells are two kinds of _____.
14. An excessively low WBC count is called _____.
15. _____ is the fluid that remains if all the formed elements and fibrinogen are removed from the blood.
16. The overall cessation of bleeding, involving several mechanisms, is called _____.
17. _____ results from a mutation that changes one amino acid in each beta chain of the hemoglobin molecule.
18. An excessively high RBC count is called _____.
19. Platelets are produced by giant bone marrow cells called _____.
20. The kidney hormone _____ stimulates RBC production.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. hemato-
2. leuko-
3. -emia
4. -blast
5. erythro-
6. mega-
7. myelo-
8. thrombo-
9. macro-
10. -poiesis

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. By volume, the blood usually contains more plasma than blood cells.
2. An increase in the albumin concentration of the blood tends to affect blood pressure.
3. Anemia is caused by a low oxygen concentration in the blood.
4. The most important WBCs in combating a bacterial infection are basophils.
5. Platelets and erythrocytes lack nuclei.
6. Lymphocytes are the most abundant WBCs in the blood.
7. Platelet count is often depressed in people with leukemia.
8. All formed elements of the blood come ultimately from hemopoietic stem cells.
9. Since RBCs have no nuclei, they do not live as long as the granulocytes do.
10. Leukemia is a severe deficiency of white blood cells.

Answers in appendix A

Testing Your Comprehension

1. Considering the quantity of hemoglobin in an erythrocyte and the oxygen-binding properties of hemoglobin, calculate how many molecules of oxygen one erythrocyte could carry.
2. A patient is found to be seriously dehydrated and to have an elevated RBC count. Does the RBC count necessarily indicate a disorder of erythropoiesis? Why or why not?
3. Patients suffering from renal failure are typically placed on hemodialysis and erythropoietin (EPO) replacement therapy. Explain the reason for giving EPO, and predict what the consequences would be of not including this in the treatment regimen.
4. A leukemia patient exhibits minute hemorrhagic spots *(petechiae)* in her skin. Explain why leukemia could produce this effect.
5. Do you think platelets can synthesize proteins? Why or why not?

Three-dimensional CT scan of the heart. Left lateral view of a person facing left.

© Gondelon/Science Source

CHAPTER 20

THE CIRCULATORY SYSTEM II
THE HEART

CHAPTER OUTLINE

20.1 Overview of the Cardiovascular System 540
- The Pulmonary and Systemic Circuits 540
- Position, Size, and Shape of the Heart 541
- The Pericardium 543

20.2 Gross Anatomy of the Heart 543
- The Heart Wall 543
- The Chambers 545
- The Valves 545
- Blood Flow Through the Chambers 547

20.3 Coronary Circulation 549
- Arterial Supply 549
- Venous Drainage 552

20.4 The Cardiac Conduction System and Cardiac Muscle 552
- The Conduction System 552
- Structure of Cardiac Muscle 553
- Nerve Supply to the Heart 554
- The Cardiac Cycle 555

20.5 Developmental and Clinical Perspectives 557
- Prenatal Development of the Heart 557
- Changes at Birth 557
- The Aging Heart 558
- Heart Disease 559

Study Guide 560

DEEPER INSIGHTS

20.1 Coronary Artery Disease 551
20.2 Heart Block 553
20.3 The Electrocardiogram 555
20.4 Patent Ductus Arteriosus 559

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:
- Thoracic cavity anatomy (p. 17)
- Desmosomes and gap junctions (pp. 38–40)
- Endothelium (p. 79)
- Ultrastructure of striated muscle (p. 244)
- Anatomy of the autonomic nervous system (chapter 16)

Anatomy & Physiology REVEALED
aprevealed.com

Module 9: Cardiovascular System

We are more conscious of our heart than we are of most organs, and more wary of its failure. Speculation about the heart is at least as old as written history. Some ancient Chinese, Egyptian, Greek, and Roman scholars correctly surmised that it was a pump for filling the vessels with blood. Aristotle's views, however, were a step backward. Perhaps because the heart quickens its pace when we are emotionally aroused and because grief causes "heartache," he thought it served primarily as the seat of emotion, but speculated that it might also be a source of heat to aid digestion. During the Middle Ages, Western medical schools clung dogmatically to Aristotle's ideas. In that era, perhaps the only significant advance came when thirteenth-century Arab physician Ibn an-Nafis described the role of the coronary blood vessels in nourishing the heart. The sixteenth-century dissections and anatomical charts of Vesalius, however, greatly improved knowledge of cardiovascular anatomy and set the stage for a more scientific study of the heart and treatment of its disorders.

In the early decades of the twentieth century, little could be recommended for heart disease other than bed rest. Then nitroglycerin was found to improve coronary circulation and relieve the pain resulting from physical exertion; digitalis proved effective for treating abnormal heart rhythms; and diuretics were first used to reduce hypertension. In the last several decades, such advances as coronary bypass surgery, clot-dissolving enzymes, valve replacements, heart transplants, artificial pacemakers, and artificial hearts have made cardiology one of the most dramatic and attention-getting fields of medicine.

20.1 Overview of the Cardiovascular System

Expected Learning Outcomes

When you have completed this section, you should be able to

a. define and distinguish between the *pulmonary* and *systemic* circuits;
b. describe the general location, size, and shape of the heart; and
c. describe the pericardial sac that encloses the heart.

The **cardiovascular system** consists of the heart and blood vessels. The heart functions as a muscular pump that keeps blood flowing through the vessels. The vessels deliver the blood to all the body's organs and then return it to the heart. This chapter focuses on **cardiology**[1]—a field that embraces the study of the heart, clinical evaluation of its function and disorders, and treatment of cardiac diseases. The blood vessels are discussed in chapter 21.

The Pulmonary and Systemic Circuits

The cardiovascular system has two major divisions: a **pulmonary circuit,** which carries blood to the lungs for gas exchange and returns it to the heart, and a **systemic circuit,** which supplies blood to every organ of the body (fig. 20.1), including other parts of the lungs and the wall of the heart itself.



Figure 20.1 **General Schematic of the Cardiovascular System.**
• *Are the lungs supplied by the pulmonary circuit, the systemic circuit, or both? Explain.* APR

---

[1] *cardio* = heart; *logy* = study

The right half of the heart supplies the pulmonary circuit. It receives blood that has circulated through the body and pumps it into a large artery, the *pulmonary trunk.* From there, the oxygen-poor blood is distributed to the lungs, where it unloads carbon dioxide and picks up a fresh load of oxygen. It then returns to the left side of the heart by way of the *pulmonary veins* (see fig. 20.3).

The left half of the heart supplies the systemic circuit. It pumps blood into the body's largest artery, the *aorta.* The aorta gives off branches that ultimately deliver oxygen to every organ of the body and pick up their carbon dioxide and other wastes. After exchanging gases with the tissues, this blood returns to the heart by way of the body's two largest veins—the *superior vena cava,* which drains the upper body, and the *inferior vena cava,* which drains everything below the diaphragm. The pulmonary trunk, pulmonary veins, aorta, and the two venae cavae are called the *great vessels* (*great arteries* and *veins*) because of their relatively large diameters.

Position, Size, and Shape of the Heart

The heart is located in the thoracic cavity in the mediastinum, between the lungs and deep to the sternum. From its superior to inferior midpoints, it is tilted toward the left, so about two-thirds of the heart lies to the left of the median plane (fig. 20.2; see also fig. A.10, p. 340). The broad superior portion of the heart, called the **base,** is the point of attachment for the great vessels described previously. The inferior end tapers to a blunt point, the **apex** of the heart, immediately above the diaphragm (fig. 20.3).


Sternum
3rd rib
Diaphragm
(a)
Anterior
Sternum
Interventricular septum
Right ventricle
Left ventricle
Thoracic vertebra
Pericardial cavity
Lungs
(b)
Posterior
Aorta
Pulmonary trunk
Superior vena cava
Right lung
Base of heart
Parietal pleura (cut)
Pericardial sac (cut)
Apex of heart
Diaphragm
(c)

Figure 20.2 Position of the Heart in the Thoracic Cavity. (a) Relationship to the thoracic cage. (b) Cross section of the thorax at the level of the heart. Structures have the same orientation as in the viewer's body. (c) Frontal view of the thoracic cavity with the lungs slightly retracted and the pericardial sac opened.

- *Does most of the heart lie to the right or left of the median plane?* APR


Aortic arch
Superior vena cava
Branches of the right pulmonary artery
Right pulmonary veins
Right auricle
Right atrium
Coronary sulcus
Right ventricle
Inferior vena cava
Ligamentum arteriosum
Ascending aorta
Left pulmonary artery
Pulmonary trunk
Left pulmonary veins
Left auricle
Anterior interventricular sulcus
Left ventricle
Apex of heart

(a) Anterior view


Aorta
Left pulmonary artery
Left pulmonary veins
Left atrium
Coronary sulcus
Coronary sinus
Fat
Left ventricle
Apex of heart
Superior vena cava
Right pulmonary artery
Right pulmonary veins
Right atrium
Inferior vena cava
Posterior interventricular sulcus
Right ventricle

(b) Posterior view

Figure 20.3 Surface Anatomy of the Heart. The coronary blood vessels on the heart surface are identified in figure 20.11. APR

The adult heart weighs about 300 g (10 ounces) and measures about 9 cm (3.5 in.) wide at the base, 13 cm (5 in.) from base to apex, and 6 cm (2.5 in.) from anterior to posterior at its thickest point. Whatever one's body size, from child to adult, the heart is roughly the same size as the fist.

The Pericardium

The heart is enclosed in a double-walled sac called the **pericardium.** The outer wall, called the **pericardial sac (parietal pericardium),** has a tough, superficial *fibrous layer* of dense irregular connective tissue and a deep, thin *serous layer.* The serous layer turns inward at the base of the heart and forms the **epicardium (visceral pericardium)** of the heart surface (fig. 20.4), which is described later in the discussion of the heart wall. The pericardial sac is anchored by ligaments to the diaphragm below and the sternum anterior to it, and more loosely anchored by fibrous connective tissue to mediastinal tissue posterior to the heart.

The space between the parietal and visceral membranes is called the **pericardial cavity** (see figs. 20.2b and 20.4). The heart is not inside the pericardial cavity but enfolded by it. The relationship of the heart to the pericardium is often described as resembling a fist pushed into an underinflated balloon (fig. 20.4c). The balloon surface in contact with the fist is like the epicardium; the outer balloon surface is like the pericardial sac; and the air space between them is like the pericardial cavity.



Figure 20.4 The Pericardium and Heart Wall. (a) Frontal section of the heart showing the three layers of the heart wall and relationship to the pericardium. (b) Detail of the pericardial sac (parietal pericardium), epicardium (visceral pericardium), and pericardial cavity between them. (c) A fist in a balloon shows, by analogy, how the double-walled pericardium wraps around the heart. APR

The pericardial cavity contains only 5 to 30 mL of **pericardial fluid,** exuded by the serous layer of the pericardial sac. The fluid lubricates the membranes and allows the heart to beat with minimal friction. In *pericarditis*—inflammation of the pericardium—the membranes may become roughened and produce a painful *friction rub* with each heartbeat. In addition to reducing friction, the pericardium isolates the heart from other thoracic organs and anchors it within the thorax. It allows the heart room to expand, yet resists excessive expansion (see *cardiac tamponade* in Deeper Insight 1.2, p. 17).

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. Distinguish between the pulmonary and systemic circuits and state which part of the heart supplies each one.
2. Make a two-color sketch of the pericardium, using one color for the pericardial sac and another for the epicardium. For the pericardial sac, label both the fibrous and serous layers. Show the relationship between the pericardium, pericardial cavity, and heart wall.

20.2 Gross Anatomy of the Heart

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the three layers of the heart wall;
b. identify the four chambers of the heart;
c. identify the surface features of the heart and correlate them with its internal four-chambered anatomy;
d. identify the four valves of the heart; and
e. trace the flow of blood through the chambers and valves of the heart and the adjacent blood vessels.

The Heart Wall

The heart wall consists of three layers—a thin epicardium covering its external surface, a thick muscular myocardium in the middle, and a thin endocardium lining the interior of the chambers (fig. 20.4).

The **epicardium**[2] is a serous membrane on the heart surface. It consists mainly of a simple squamous epithelium overlying a thin layer of areolar tissue. In most places, it is as thin as tissue paper and is translucent, so the muscle of the myocardium shows through (fig. 20.5a). In some areas, it also includes a thick layer of adipose tissue. The largest branches of the coronary blood vessels travel through the epicardium.

The **endocardium**[3] lines the interior of the heart chambers, covers the valves, and is continuous with the inner lining *(endothelium)*

---

[2] *epi* = upon; *cardi* = heart
[3] *endo* = internal; *cardi* = heart


Fat in interventricular sulcus
Left ventricle
Right ventricle
Anterior interventricular artery
© McGraw-Hill Education

(a) Anterior view, external anatomy


Superior vena cava
Inferior vena cava
Interatrial septum
Left atrium
Left AV valve
Coronary blood vessels
Tendinous cords
Left ventricle
Endocardium
Myocardium
Epicardium
Base of heart
Right atrium
Opening of coronary sinus
Right AV valve
Trabeculae carneae
Right ventricle
Papillary muscles
Epicardial fat
Interventricular septum
Apex of heart
© McGraw-Hill Education

(b) Posterior view, internal anatomy

Figure 20.5 The Heart of a Human Cadaver. APR

of the blood vessels. Like the epicardium, it is composed of a simple squamous epithelium overlying a thin areolar tissue layer, but it has no adipose tissue.

The **myocardium,**[4] composed of cardiac muscle, lies between these two layers and composes most of the mass of the heart. It performs the work of the heart, and its thickness varies according to the workload on the individual chambers. The cells of cardiac muscle are called cardiac **myocytes,** or **cardiocytes.** They are grouped in bundles that coil around the heart in a spiral called the **myocardial vortex** (fig. 20.6). This arrangement causes the heart to contract with a twisting or wringing motion that enhances the ejection of blood.

The heart also has a connective tissue framework of collagenous and elastic fibers called the **fibrous skeleton.** This tissue is especially concentrated in the walls between the heart chambers, in *fibrous rings (anuli fibrosi)* around the valves, and in sheets of tissue that interconnect these rings (see fig. 20.8). The fibrous skeleton has multiple functions: (1) It provides structural support for the heart, especially around the valves and the openings of

---

[4] *myo* = muscle; *cardi* = heart



Photo and Illustration by Roy Schneider, University of Toledo. Plastinated heart model for illustration courtesy of Dr. Carlos Baptista, University of Toledo

Photo and Illustration by Roy Schneider, University of Toledo. Plastinated heart model for illustration courtesy of Dr. Carlos Baptista, University of Toledo

Figure 20.6 **The Myocardial Vortex.** (a) Anterior view of the heart with the epicardium rendered transparent to expose the bundles of myocardial muscle. (b) View from the apex to show the way the muscle coils around the heart. This results in a twisting motion when the ventricles contract.

the great vessels; it holds these orifices open and prevents them from being excessively stretched when blood surges through them. (2) It anchors the cardiocytes and gives them something to pull against. (3) As a nonconductor of electricity, it serves as electrical insulation between the atria and the ventricles, so the atria cannot stimulate the ventricles directly. This insulation is important in the timing and coordination of electrical and contractile activity. (4) Some authorities think (though others disagree) that elastic recoil of the fibrous skeleton may aid in refilling the heart with blood after each beat, like the rubber bulb of a turkey baster that expands when you relax your grip.

Apply What You Know

Parts of the fibrous skeleton sometimes become calcified in old age. How would you expect this to affect cardiac function?

The Chambers

The heart has four chambers, best seen in frontal section (fig. 20.7). The two at the superior pole (base) of the heart are the **right** and **left atria** (AY-tree-uh; singular, *atrium*[5]). They are thin-walled receiving chambers for blood returning to the heart by way of the great veins. Most of the mass of each atrium is on the posterior side of the heart, so only a small portion is visible from an anterior view. Here, each atrium has a small earlike extension called an **auricle**[6] that slightly increases its volume.

The two inferior heart chambers, the **right** and **left ventricles,**[7] are the pumps that eject blood into the arteries and keep it flowing around the body. The right ventricle constitutes most of the anterior portion of the heart, and the left ventricle forms the apex and inferoposterior portion.

On the surface, the boundaries of the four chambers are marked by three sulci (grooves), which are largely filled with fat and the coronary blood vessels (fig. 20.5a). The **coronary**[8] **(atrioventricular) sulcus** encircles the heart near the base and separates the atria above from the ventricles below. It can be exposed by lifting the margins of the atria. The other two sulci extend obliquely down the heart from the coronary sulcus to the apex—one on the front of the heart called the **anterior interventricular sulcus** and one on the back called the **posterior interventricular sulcus.** These sulci overlie an internal wall, the *interventricular septum,* that divides the right ventricle from the left. The coronary sulcus and two interventricular sulci harbor the largest of the coronary blood vessels.

The atria exhibit thin flaccid walls corresponding to their light workload—all they do is pump blood into the ventricles immediately below. They are separated from each other by a wall called the **interatrial septum.** The right atrium and both auricles exhibit internal ridges of myocardium called **pectinate**[9] **muscles.** The **interventricular septum** is a much more muscular, vertical wall between the ventricles.

The right ventricle pumps blood only to the lungs and back to the left atrium, so its wall is only moderately muscular. The wall of the left ventricle is two to four times as thick because it bears the greatest workload of all four chambers, pumping blood through the entire body.

Both ventricles exhibit internal ridges called **trabeculae carneae**[10] (trah-BEC-you-lee CAR-nee-ee). It is thought that these ridges may serve to keep the ventricular walls from clinging to each other like suction cups when the heart contracts, and thus allow the chambers to expand more easily when they refill. If you wet your hands, press your palms firmly together, then pull them apart, you can appreciate how smooth wet surfaces cling to each other and how, without trabeculae, the heart walls might also do so.

The Valves

To pump blood effectively, the heart needs valves that ensure a predominantly one-way flow. There is a valve between each atrium and the corresponding ventricle and another at the exit from each ventricle into its great artery (fig. 20.7), but there are no valves where the great veins empty into the atria. Each valve consists of two or three fibrous flaps of tissue called **cusps** or **leaflets,** covered with endocardium.

The **atrioventricular (AV) valves** regulate the openings between the atria and ventricles (fig. 20.8). The **right AV valve**

---

[5] *atrio* = entryway

[6] *auricle* = little ear

[7] *ventr* = belly, lower part; *icle* = little

[8] *coron* = crown; *ary* = pertaining to

[9] *pectin* = comb; *ate* = like

[10] *trabec* = beam; *ula* = little; *carne* = flesh, meat


Aorta
Right pulmonary artery
Superior vena cava
Right pulmonary veins
Interatrial septum
Right atrium
Fossa ovalis
Pectinate muscles
Right AV valve
Tendinous cords
Trabeculae carneae
Right ventricle
Inferior vena cava
Left pulmonary artery
Pulmonary trunk
Left pulmonary veins
Pulmonary valve
Left atrium
Aortic valve
Left AV valve
Left ventricle
Papillary muscle
Interventricular septum
Endocardium
Myocardium
Epicardium

Figure 20.7 **Internal Anatomy of the Heart (Anterior View).**
- *Do the atrial pectinate muscles more nearly resemble the ventricular papillary muscles or the trabeculae carneae?* **APR**

has three cusps and is therefore also called the **tricuspid valve.** The **left AV valve** is also known as the **mitral** (MY-trul) **valve** after its resemblance to a miter, the headdress of a church bishop. It was also formerly called the *bicuspid valve,* but this term has fallen out of use. It came from an early nineteenth-century misconception that it has only two cusps, but closer examination shows it to have small accessory cusps between the two main ones.

Stringy **tendinous cords (chordae tendineae),** reminiscent of the shroud lines of a parachute, connect the valve cusps to conical **papillary muscles** on the floor of the ventricle. The papillary muscles do not help the valves open. Rather, they contract along with the rest of the ventricular myocardium and tug on the tendinous cords. This prevents the AV valves from bulging excessively into the atria or flipping inside out like windblown umbrellas. Excessive bulging due to slack tendinous cords is called *valvular prolapse* (see table 20.1). Each papillary muscle has two or three basal attachments to the chamber floor. These multiple attachments may govern the timing of electrical excitation of the papillary muscles, and they may distribute mechanical stress in a way similar to the weight of the Eiffel Tower supported on its four legs. The multiple attachments may also provide some redundancy that protects an AV valve from total mechanical failure should one attachment fail.

The **semilunar**[11] **valves** (pulmonary and aortic valves) regulate the flow of blood from the ventricles into the great arteries. The **pulmonary valve** controls the opening from the right ventricle into the pulmonary trunk, and the **aortic valve** controls the opening from the left ventricle into the aorta. Each has three cusps shaped like shirt pockets. When blood is ejected from the ventricles, it pushes through these valves from below and presses their cusps against the arterial walls. When the ventricles relax and expand, arterial blood flows backward toward the ventricles, but quickly fills the cusps. The inflated pockets meet at the center and quickly seal the opening, so little blood is able to return to the ventricles. Because of the way these cusps are attached to the arterial wall,

---

[11] *semi* = half; *lun* = moon; *ar* = like



© Biophoto Associates/Science Source

© McGraw-Hill Education

Figure 20.8 **The Heart Valves.** (a) Superior view of the heart with the atria removed. (b) The aortic valve, superior view, showing the three cusps meeting like a Y. One cusp is darkened by a blood clot. (c) Papillary muscle and tendinous cords seen from within the right ventricle. The upper ends of the cords are attached to the cusps of the right AV valve.

they cannot prolapse any more than a shirt pocket turns inside out if you jam your hand into it. Thus, they do not require or possess tendinous cords.

Heart valves do not open and close by any muscular effort of their own. The cusps are simply pushed open and closed by changes in blood pressure (fig. 20.9). When the ventricles are relaxed and their pressure is low, the AV valve cusps hang down limply and both AV valves are open. Blood flows freely from the atria through the valves and into the ventricles below. When the ventricles have filled with blood, they begin to contract and force blood upward against the underside of these valves. This pushes the valve cusps together and closes the openings, so the blood is not simply squirted back into the atria. A moment later, the rising pressure in the ventricles forces the pulmonary and aortic valves open, and blood is ejected from the heart.

Blood Flow Through the Chambers

Until the sixteenth century, anatomists thought that blood flowed directly from the right ventricle to the left through invisible pores in the septum. This is incorrect; blood in the right and left chambers of the heart is kept entirely separate. Figure 20.10 shows the



Atrioventricular valves open

Atrioventricular valves closed

(a)



Semilunar valves open

Semilunar valves closed

(b)

Figure 20.9 Operation of the Heart Valves. (a) The atrioventricular valves. When atrial pressure is greater than ventricular pressure, the valve opens and blood flows through. When ventricular pressure rises above atrial pressure, the blood in the ventricle pushes the valve cusps closed. (b) The semilunar valves. When the pressure in the ventricle is greater than the pressure in the artery, the valve is forced open and blood is ejected. When ventricular pressure is lower than arterial pressure, arterial blood holds the valve closed.

- *What role do the tendinous cords play?*

pathway of the blood as it travels from the right atrium through the body and back to the starting point.

Blood that has been through the systemic circuit arrives at the right atrium by way of the superior and inferior venae cavae. It flows directly from the right atrium, through the right AV valve, into the right ventricle. When the right ventricle contracts, it ejects this blood through the pulmonary valve into the pulmonary trunk, on its way to the lungs to exchange carbon dioxide for oxygen.

Blood returns from the lungs by way of two pulmonary veins on the left and two on the right; all four of these empty into the left atrium. Blood flows through the left AV (mitral) valve into the left ventricle. Contraction of the left ventricle ejects this blood through the aortic valve into the ascending aorta, on its way to another trip around the systemic circuit.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

3. Name the three layers of the heart and describe their structural differences.
4. What are the functions of the fibrous skeleton?
5. Trace the flow of blood through the heart, naming each chamber and valve in order.



① Blood enters right atrium from superior and inferior venae cavae.

② Blood in right atrium flows through right AV valve into right ventricle.

③ Contraction of right ventricle forces pulmonary valve open.

④ Blood flows through pulmonary valve into pulmonary trunk.

⑤ Blood is distributed by right and left pulmonary arteries to the lungs, where it unloads CO_2 and loads O_2.

⑥ Blood returns from lungs via pulmonary veins to left atrium.

⑦ Blood in left atrium flows through left AV valve into left ventricle.

⑧ Contraction of left ventricle (simultaneous with step ③) forces aortic valve open.

⑨ Blood flows through aortic valve into ascending aorta.

⑩ Blood in aorta is distributed to every organ in the body, where it unloads O_2 and loads CO_2.

⑪ Blood returns to right atrium via venae cavae.

Figure 20.10 **The Pathway of Blood Flow Through the Heart.** The pathway from 4 to 6 is the pulmonary circuit, and the pathway from 9 to 11 is the systemic circuit. Violet arrows indicate oxygen-poor blood, and orange arrows indicate oxygen-rich blood.

20.3 Coronary Circulation

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the arteries that nourish the myocardium and the veins that drain it; and
b. define *myocardial infarction* and relate it to the coronary arteries.

If your heart lasts for 80 years and beats an average of 75 times a minute, it will beat more than 3 billion times and pump more than 200 million liters of blood. It is, in short, a remarkably hard-working organ, and understandably, it needs an abundant supply of oxygen and nutrients. These needs are not met to any appreciable extent by the blood in the chambers, because the diffusion of substances from there through the myocardium would be too slow. Instead, the myocardium has its own supply of arteries and capillaries that deliver blood to every cardiocyte. The blood vessels of the heart wall constitute the **coronary circulation.**

At rest, the coronary blood vessels supply the myocardium with about 250 mL of blood per minute. This constitutes about 5% of the circulating blood going to meet the metabolic needs of the heart alone, even though the heart is only 0.5% of the body's weight. It receives 10 times its "fair share" to sustain its strenuous workload.

Arterial Supply

The coronary circulation is the most variable aspect of cardiac anatomy. The following description covers only the pattern seen in about 70% to 85% of persons, and only the few largest vessels (compare the great density of small vessels seen in fig. 20.11c).

Immediately after the aorta leaves the left ventricle, it gives off a right and left coronary artery. The orifices of these two arteries lie deep in the pockets formed by two of the aortic valve cusps (see fig. 20.8a). The **left coronary artery (LCA)** travels through the coronary sulcus under the left auricle and divides into two branches (fig. 20.11):

1. The **anterior interventricular branch** travels down the anterior interventricular sulcus to the apex, rounds the bend, and travels a short distance up the posterior side of the heart. There it joins the posterior interventricular branch described shortly. Clinically, it is also called the *left anterior descending*


Right coronary artery (RCA)
Small cardiac vein
Right marginal branch of RCA
Left coronary artery (LCA)
Left auricle (reflected)
Circumflex branch of LCA
Great cardiac vein
Anterior interventricular branch of LCA
Great cardiac vein
Circumflex branch of LCA
Coronary sinus
Left marginal branch of LCA
Left marginal vein
Right coronary artery (RCA)
Right marginal branch of RCA
Posterior interventricular branch of RCA
Posterior interventricular vein

(a) Anterior view

(b) Posterior view



© SPL/Science Source

(c)

Figure 20.11 **The Principal Coronary Blood Vessels.** (a) Anterior view. (b) Posterior view. (c) A polymer cast of the coronary circulation.

(LAD) branch. This artery supplies blood to both ventricles and the anterior two-thirds of the interventricular septum.

2. The **circumflex branch** continues around the left side of the heart in the coronary sulcus. It gives off a **left marginal branch** that passes down the left margin of the heart and furnishes blood to the left ventricle. The circumflex branch then ends on the posterior side of the heart, where it supplies blood to the left atrium and posterior wall of the left ventricle.

The **right coronary artery (RCA)** supplies the right atrium and sinoatrial node (pacemaker), then continues along the coronary sulcus under the right auricle and gives off two branches of its own:

1. The **right marginal branch** runs toward the apex of the heart and supplies the lateral aspect of the right atrium and ventricle.
2. The RCA continues around the right margin of the heart to the posterior side, sends a small branch to the atrioventricular node, then gives off a large **posterior interventricular branch.** This branch travels down the corresponding sulcus and supplies the posterior walls of both ventricles as well as the posterior portion of the interventricular septum. It ends by joining the anterior interventricular branch of the LCA.

The energy demand of the cardiac muscle is so critical that an interruption of the blood supply to any part of the myocardium can cause necrosis within minutes. A fatty deposit or blood clot in a coronary artery can produce a **myocardial infarction**[12] **(MI),** the sudden death of a patch of tissue deprived of its blood flow

---

[12] *infarct* = to stuff

DEEPER INSIGHT 20.1

Coronary Artery Disease

Coronary artery disease (CAD) is a narrowing of the coronary arteries resulting in insufficient blood flow to maintain the myocardium. It is usually caused by *atherosclerosis,* a vascular disorder in which fatty deposits form in an arterial wall, causing arterial degeneration and obstructed blood flow. The atherosclerotic *plaque (atheroma)* is composed of lipids, smooth muscle, and scar tissue, and may progress to a calcified *complicated plaque,* causing the arterial walls to become rigid. *Myocardial infarction* (heart attack) can occur when the artery becomes so occluded that cardiac muscle begins to die from lack of oxygen. Partial obstruction of an artery can cause a temporary sense of heaviness and chest pain called *angina pectoris* when the artery constricts.

There are multiple ways in which an atheroma can lead to heart attack. The atheroma itself may block so much of the artery that blood flow is insufficient to support the cardiac muscle (fig. 20.12), especially during exercise when the metabolic need of the myocardium increases sharply. Platelets often adhere to atheromas and produce blood clots. If the vessel space (lumen) is already largely closed off by the atheroma, a blood clot may finish the job. Furthermore, a clot can break free from the atheroma and block a smaller coronary artery downstream.



© Ed Reschke/Getty Images

© Ed Reschke/Getty Images

© Custom Medical Stock Photo/Newscom

Figure 20.12 **Coronary Atherosclerosis.** (a) Cross section of a healthy artery. (b) Cross section of an artery with advanced atherosclerosis. Most of the original lumen is obstructed by a plaque composed of calcified scar tissue. The lumen is reduced to a small space that can easily be blocked by a stationary or traveling blood clot or by vasoconstriction. (c) Coronary arteriogram showing 60% obstruction of the anterior interventricular artery (arrow).

(see Deeper Insight 20.1). Some protection from MI is provided by several **arterial anastomoses** (ah-NASS-tih-MO-seez), points where two arteries come together and combine their blood flow to points farther downstream. Anastomoses provide an alternative route, called **collateral circulation,** that can supply the heart tissue with blood if the primary route becomes obstructed.

In most organs, blood flow peaks when the ventricles contract and eject blood into the arteries, and diminishes when the ventricles relax and refill. The opposite is true in the coronary arteries: Flow peaks when the heart relaxes. There are three reasons for this. (1) Contraction of the myocardium compresses the coronary arteries and obstructs blood flow. (2) When the ventricles contract, the aortic valve is forced open and the valve cusps cover the openings to the coronary arteries, blocking blood from flowing into them. (3) When they relax, blood in the aorta briefly surges back toward the heart. It fills the aortic valve cusps and some of it flows into the coronary arteries, like water pouring into a bucket and flowing out through a hole in the bottom. In the coronary blood vessels, therefore, blood flow increases during ventricular relaxation.

Venous Drainage

Venous drainage refers to the route by which blood leaves an organ. After flowing through capillaries of the heart wall, about 20% of the coronary blood empties directly from multiple small *thebesian*[13] *veins* into the heart chambers, especially the right ventricle. The other 80% returns to the right atrium by the following route (fig. 20.11):

- The **great cardiac vein** collects blood from the anterior aspect of the heart and travels alongside the anterior interventricular artery. It carries blood from the apex of the heart toward the coronary sulcus, then arcs around the left side of the heart and empties into the coronary sinus described below.
- The **posterior interventricular (middle cardiac) vein,** found in the posterior interventricular sulcus, collects blood from the posterior aspect of the heart. It, too, carries blood from the apex upward and drains into the same sinus.
- The **left marginal vein** travels from a point near the apex of the heart up the left margin and empties into the coronary sinus.
- The **coronary sinus,** a large transverse vein in the coronary sulcus on the posterior side of the heart, collects blood from all three of the aforementioned veins as well as some smaller ones. It empties blood into the right atrium.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

6. What are the two principal branches of the left coronary artery? Where are they located on the heart surface? What are the branches of the right coronary artery, and where are they located?
7. What is the medical significance of anastomoses in the coronary arterial system?
8. Why do the coronary arteries carry a greater blood flow during ventricular relaxation than they do during ventricular contraction?
9. What are the three major veins that empty into the coronary sinus?

20.4 The Cardiac Conduction System and Cardiac Muscle

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the heart's electrical conduction system;
b. contrast the structure of cardiac and skeletal muscle; and
c. describe the types and significance of intercellular junctions between cardiac muscle cells.

The most obvious physiological fact about the heart is that it is autorhythmic.[14] It spontaneously contracts at regular intervals, typically about 75 beats per minute (bpm) in a resting adult. Among invertebrates such as clams, crabs, and insects, each heartbeat is triggered by a pacemaker in the nervous system. In vertebrates such as ourselves, however, the signal that triggers each heartbeat originates within the heart itself. Indeed, we can sever the nerves to the heart, remove it from the body and keep it in aerated saline, and it will beat for hours. Cut it into little pieces, and each piece continues its own rhythmic pulsations. Thus, it obviously doesn't depend on the nervous system for its rhythm. The heart has its own pacemaker and electrical conduction system, and it is to this that we now turn our attention.

The Conduction System

Some cardiocytes have lost the ability to contract and are specialized, instead, for generating and conducting electrical signals. These cells constitute the **cardiac conduction system,** which controls the route and timing of stimulation to ensure that the four heart chambers are coordinated with each other. Electrical signals arise and travel through the conduction system in the following order (fig. 20.13).

① The **sinoatrial (SA) node,** a patch of modified cardiocytes in the right atrium, just under the epicardium near the superior vena cava. This is the **pacemaker** that initiates each heartbeat and determines the heart rate.

② Signals from the SA node spread throughout the atria, as shown by the red arrows in the figure.

③ The **atrioventricular (AV) node,** located at the lower end of the interatrial septum near the right AV valve. This node acts as an electrical gateway to the ventricles. All electrical signals traveling to the ventricles must pass through the AV node because the fibrous skeleton acts as an insulator that prevents currents from traveling to the ventricles by any other route.

---

[13] Adam Christian Thebesius (1686–1732), German physician

[14] *auto* = self


Right atrium
Sinoatrial node (pacemaker)
Atrioventricular node
Atrioventricular bundle
Purkinje fibers
Left atrium
Purkinje fibers
Bundle branches
①
②
②
③
④
⑤
① SA node fires.
② Excitation spreads through atrial myocardium.
③ AV node fires.
④ Excitation spreads down AV bundle.
⑤ Purkinje fibers distribute excitation through ventricular myocardium.

Figure 20.13 **The Cardiac Conduction System.** Electrical signals travel along the pathways indicated by the arrows.
- *Which atrium is the first to receive the signal that induces atrial contraction?*

④ The **atrioventricular (AV) bundle (bundle of His[15]),** a cord of modified cardiocytes by which signals leave the AV node. The bundle soon forks into **right** and **left bundle branches,** which enter the interventricular septum and descend toward the apex of the heart.

⑤ **Purkinje[16]** (pur-KIN-jee) **fibers,** nervelike processes that arise from the lower end of the bundle branches and turn upward to spread throughout the ventricular myocardium. Purkinje fibers distribute the electrical excitation to the cardiocytes of the ventricles. They form a more elaborate network in the left ventricle than in the right.

After we examine the structure of cardiac muscle, we will see how this conduction system relates to the heart's cycle of contraction and relaxation.

Structure of Cardiac Muscle

The traveling electrical signal does not end with the Purkinje fibers, and Purkinje fibers do not reach every cardiocyte. Rather, the cardiocytes pass the signal from cell to cell. This is something that skeletal muscle cannot do, so to understand how the heartbeat is coordinated, one must understand the microscopic anatomy of cardiocytes and how they differ from skeletal muscle fibers.

Cardiac muscle is striated like skeletal muscle but otherwise differs from it in many structural and physiological ways. Cardiocytes are relatively short, thick cells, typically 50 to 100 µm long and 10 to 20 µm wide (fig. 20.14). The ends of the cell are slightly branched, like a log with notches in the end. Through its multiple end branches, each cardiocyte contacts several other cells, so collectively they form a network throughout a heart chamber. A cardiocyte usually has only one, centrally placed nucleus, often surrounded by a mass of the energy-storage carbohydrate, glycogen. The sarcoplasmic reticulum is less developed than in skeletal muscle; it lacks terminal cisternae, although it does have footlike sacs associated with the T tubules. The T tubules are much larger than in skeletal muscle. During excitation of the cell, they admit calcium ions from the extracellular fluid to activate muscle contraction. Cardiocytes have especially large mitochondria, which make up about 25% of the cell volume, compared to skeletal muscle mitochondria, which are much smaller and comprise only 2% of the cell volume.

DEEPER INSIGHT 20.2

Heart Block

Heart block is a condition in which electrical signals cannot travel normally through the cardiac conduction system because of disease and degeneration of the conduction system fibers. A *bundle branch block* exists when one or both of the atrioventricular bundle branches are diseased. *Total heart block* results from disease of the AV node. Heart block is one of the causes of cardiac arrhythmia, an irregularity in the heartbeat (see fig. 20.15c). In total heart block, signals from the SA node stop at the diseased AV node and cannot reach the ventricular myocardium. The ventricles then beat at their intrinsic rhythm of about 20 to 40 bpm, out of synchrony with the atria and at a rate too slow to sustain life for very long.

---

[15] Wilhelm His, Jr. (1863–1934), German physiologist
[16] Johannes E. Purkinje (1787–1869), Bohemian physiologist



© Ed Reschke/Getty Images

Figure 20.14 **Cardiac Muscle.** (a) Light micrograph. (b) Structure of a cardiocyte (red) and its relationship to adjacent cardiocytes. At each end, a cardiocyte is typically linked to two or more neighboring cells through the mechanical and electrical junctions of their intercalated discs. (c) Structure of an intercalated disc.

- *Which component of the intercalated disc allows a cardiocyte to electrically excite the neighboring cardiocytes?*

Apply What You Know

Why should mitochondria be larger and more abundant in cardiac muscle than in skeletal muscle?

Cardiocytes are joined end to end by thick connections called **intercalated** (in-TUR-ku-LAY-ted) **discs,** which appear as dark lines (thicker than the striations) in properly stained tissue sections. An intercalated disc is a complex steplike structure (fig. 20.14c) with three distinctive features not found in skeletal muscle:

1. **Interdigitating folds.** The plasma membrane at the end of the cell is folded somewhat like the bottom of an egg carton. The folds of adjoining cells interlock with each other and increase the surface area of intercellular contact.
2. **Mechanical junctions.** The cells are tightly joined by two types of mechanical junctions—the fascia adherens and desmosomes. The *fascia adherens*[17] (FASH-ee-ah ad-HEER-enz) is the most extensive. It is a broad band in which the actin of the thin myofilaments is anchored to the plasma membrane, and each cell is linked to the next by way of transmembrane proteins. Thus, the moving myofilaments of a contracting cell pull indirectly on the neighboring cells. The fascia adherens is interrupted here and there by *desmosomes.* Described in more detail on page 38, desmosomes are patches of mechanical linkage between cells. They prevent the contracting cardiocytes from pulling apart.
3. **Electrical junctions.** The intercalated discs also contain *gap junctions,* which form channels that allow ions to flow from the cytoplasm of one cell directly into the next (see p. 40 for their structure). These junctions enable each cardiocyte to electrically stimulate its neighbors. Thus, the entire myocardium of the two atria behaves almost as if it were a single cell, as does the entire myocardium of the two ventricles. This unified action is essential for the effective pumping of a heart chamber.

Skeletal muscle contains satellite cells that can divide and replace dead muscle fibers to some extent. Cardiac muscle lacks satellite cells, however, so the repair of damaged cardiac muscle is almost entirely by fibrosis (scarring). A limited capacity for myocardial mitosis and regeneration was discovered in 2001, raising some hope that this might one day be clinically enhanced to repair hearts damaged by myocardial infarction.

Nerve Supply to the Heart

Even though the heart has its own pacemaker, it also receives both sympathetic and parasympathetic nerves. They do not activate the heartbeat, but modify its rate and contraction strength. Sympathetic nerves can raise the heart rate to as high as 230 bpm, whereas parasympathetic nerves can reduce it to as low as 20 bpm or even stop the heart for a few seconds.

---

[17] *fascia* = band; *adherens* = adhering

The sympathetic pathway to the heart originates with neurons in the lower cervical to upper thoracic spinal cord. Efferent fibers from these neurons pass from the spinal cord to the sympathetic chain and travel up the chain to the three cervical ganglia. **Cardiac nerves** arise from the cervical ganglia, pass through a nerve web called the cardiac plexus, then continue to the ventricular myocardium (see fig. 16.4, p. 447). Stimulation by these nerves increases the force of ventricular contraction. Some fibers, however, innervate the atria and coronary arteries.

The parasympathetic pathway to the heart is through the vagus nerves. The right vagus nerve innervates mainly the SA node, and the left vagus nerve innervates mainly the AV node, although there is some cross-innervation from each nerve to both nodes. The ventricles receive little or no vagal stimulation. The vagus nerves slow the heartbeat. Without this influence, the SA node would produce an average resting heart rate of about 100 bpm, but steady background firing of the vagus nerves *(vagal tone)* normally holds the resting rate down to about 70 to 80 bpm.

The Cardiac Cycle

The foregoing anatomy should acquire more meaning if you can relate it to the **cardiac cycle**—one complete cycle of contraction and relaxation. This will show how the structures of the heart work together to achieve blood circulation.

The electrical events of the cardiac cycle can be recorded with skin electrodes as an **electrocardiogram (ECG)** (see Deeper Insight 20.3 and fig. 20.15). Electrical excitation of a heart chamber induces contraction, or **systole** (SIS-toe-lee), which expels blood from the chamber. The relaxation of any chamber is called **diastole** (dy-ASS-toe-lee) and allows the chamber to refill.

DEEPER INSIGHT 20.3

The Electrocardiogram

Next to listening to the heart sounds with a stethoscope *(auscultation),* the most common clinical method of evaluating heart function is the *electrocardiogram* (*ECG* or *EKG*[18])—recording the electrical activity of the heart by means of electrodes applied to the skin. As the myocardium of the atria and ventricles electrically discharges *(depolarizes)* and recharges *(repolarizes)*, it generates electrical currents that are conducted by electrolytes in the body fluids to the skin surface. Here the activity can be recorded as small voltage changes that show as upward and downward deflections of the ECG (fig. 20.15a).

Three major events are seen in the ECG, named the *P wave,* the *QRS complex,* and the *T wave.* (The letters were arbitrarily chosen; they do not stand for any words.) Each wave and interval between waves is correlated with events of the cardiac cycle as described in the main text. The QRS complex is the largest wave because it is produced mainly by depolarization of the ventricles, which constitute the largest muscle mass of the heart and generate the greatest electrical current.

Irregularities in the ECG help to diagnose disorders of cardiac function. In ventricular fibrillation (fig. 20.15b), the ECG exhibits random oscillations correlated with the uncoordinated ventricular squirming of a heart attack. In heart block (fig. 20.15c), some P waves are not followed by the usual QRS complex (see Testing Your Comprehension question 4, p. 562). Electrolyte imbalances, hormone imbalances, and many other disorders create telltale signs in other irregularities of the ECG.



(a) Normal electrocardiogram



(b) Ventricular fibrillation



(c) Heart block

Figure 20.15 **The Electrocardiogram.** (a) A normal ECG, showing the P wave, QRS complex, and T wave. (b) The abnormal ECG of ventricular fibrillation, with irregular electrical activity and squirming, uncoordinated contractions of the ventricular myocardium. This sort of ECG is typical of a heart attack. (c) The abnormal ECG of a heart block (see Deeper Insight 20.2).

---

[18] from the German spelling, Elektrokardiogramm

Figure 20.16 shows how the electrical and contractile activity of the heart relate to each other through the cardiac cycle.

① Initially, all four chambers are relaxed, in diastole. The AV valves are open, and as blood flows into the heart from the venae cavae and pulmonary veins, it flows through these valves and partially fills the ventricles.

② The sinoatrial (SA) node fires, exciting the atrial myocardium (see fig. 20.13), producing the P wave of the ECG and initiating atrial systole. The contracting atria finish filling the ventricles.

③ The atrioventricular (AV) node fires and electrical excitation spreads down the AV bundle, bundle branches, and Purkinje fibers and throughout the ventricles. Ventricular depolarization generates the QRS complex. This excitation sets off ventricular systole while the atria relax. Ventricular contraction forces the AV valves shut and the semilunar (aortic and pulmonary) valves open. The ventricles eject blood into the aorta and pulmonary trunk.

④ The ventricles repolarize (marked by the T wave) and relax; all four chambers are again in diastole. The semilunar valves reclose because of back pressure in the large arteries, the AV valves reopen, and the ventricles begin to refill in preparation for the next cycle.

This entire cycle repeats itself at intervals normally governed by the SA node—in a resting adult heart, typically every 0.8 second or so, generating a heart rate of about 75 bpm. The normal heartbeat, timed by the sinoatrial node, is called a *sinus rhythm.* Figure 20.15 (b and c) shows some contrasting, abnormal records resulting from diseases of the myocardium or conduction system.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

10. Why is the human heart described as autorhythmic? Where is its pacemaker, and what is it called?
11. List the components of the cardiac conduction system in the order traveled by signals from the pacemaker.
12. Identify any organelles that are less developed in cardiac muscle than in skeletal muscle, and any that are more developed. What is the functional significance of these differences?
13. Name two types of cell junctions in the intercalated discs and explain their functional importance.
14. Define *cardiac cycle, systole,* and *diastole*. How would shortening the diastole affect the heart rate and the duration of the cardiac cycle?



① All four chambers relaxed; AV valves open; ventricles filling

② Atrial systole completes ventricular filling

③ Ventricles contract; AV valves close; semilunar valves open; blood ejected into arteries

④ Heart returns to initial state of relaxation and refills

Figure 20.16 **The Cardiac Cycle.** Major events in one complete cycle of contraction and relaxation of the heart.

20.5 Developmental and Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the embryonic development of the human heart;
b. describe how and why cardiac anatomy changes at birth;
c. explain how and why the heart changes in old age; and
d. define or briefly describe several of the most common heart diseases.

Prenatal Development of the Heart

The heart is one of the earliest organs to begin functioning in the embryo. The first traces of it appear in week 3; by 22 to 23 days (usually before the mother is aware that she is pregnant), the heart is already beating; by day 24, it circulates blood throughout the embryo.

In week 3, a region of mesoderm at the anterior end of the embryo condenses into a pair of longitudinal cellular cords. By day 19, these become hollow, parallel **endocardial heart tubes** (fig. 20.17a). As the embryo grows and the head region folds, these tubes are pushed closer together, the tissues dividing them break down, and they fuse into a single heart tube (fig. 20.17b). As the tubes are fusing, the surrounding mesoderm forms a primordial myocardium, responsible for the inception of the heartbeat just a few days later. The fetal heartbeat first becomes audible with a stethoscope at about 20 weeks.

With continued folding of the head region, the heart tube elongates and segments into five dilated spaces, some of them corresponding to future heart chambers. From rostral to caudal, these are the **truncus arteriosus,**[19] **bulbus cordis,**[20] **ventricle, atrium,** and **sinus venosus** (fig. 20.17c). Two of these, the ventricle and bulbus cordis, grow more rapidly than the others, causing the heart to loop into a U and then an S shape similar to a fish heart (fig. 20.17d, e). In the course of this looping, the bulbus cordis shifts caudally, the ventricle shifts to the left, and the atrium and sinus venosus shift rostrally, as indicated by the arrows in the figure. During this looping, the heart bulges into the pericardial cavity. Looping is completed by day 28 and results in the forerunners of the adult atria and ventricles assuming their final relationship to each other (the future atria are now superior, or rostral, to the future ventricles). The primordial ventricle seen at day 21 becomes the left ventricle of the adult heart, and the inferior part of the bulbus cordis becomes the right ventricle. The superior part of the bulbus cordis and the truncus arteriosus are now collectively called the **conotruncus** (fig. 20.17e). This passage soon gives rise to the aorta and pulmonary trunk.

The next phase of development is the partitioning of the heart tube into separate chambers (two atria and two ventricles) through the growth of the interatrial and interventricular septa. The interatrial septum begins to form at the end of week 4 and is well established by about 33 days, except for an opening between the atria called the *foramen ovale.* This foramen persists until after birth; its significance is discussed in the next section. The sinus venosus is initially a separate heart chamber, but it becomes extensively remodeled. Originally, it branches into a right and left horn at its inferior end. The right horn enlarges and receives systemic blood from the superior and inferior venae cavae. It eventually becomes part of the right atrium. The left horn shrinks. Parts of it become the coronary sinus, the sinoatrial node (pacemaker), and a portion of the atrioventricular node.

The interventricular septum begins to appear on the floor of the ventricle at the end of week 4 (fig. 20.17f) and increases in height as the two ventricles grow on either side of it. The septum is complete by the end of week 7. Meanwhile, the inner portion of the ventricular wall becomes honeycombed with cavities and differentiates into the trabeculae carneae, papillary muscles, and tendinous cords.

Yet another septum forms during week 5 within the bulbus cordis and truncus arteriosus, dividing this outflow passage in two along its length. The separate halves of the passage become the ascending aorta and pulmonary trunk. The passage twists about 180° as the septum forms. The evidence of this twisting shows in the way the adult pulmonary trunk twists around the aorta. This twisting must be closely coordinated with the closure of the interventricular septum so that the right ventricle will open into the pulmonary trunk and the left ventricle will open into the aorta. Developmental irregularities at this stage are responsible for many cardiac birth defects.

Changes at Birth

There is little point to pumping all of the blood through the lungs of the fetus, because the fetal lungs are not yet inflated or functional. They receive enough blood to meet their metabolic and developmental needs, but most blood bypasses the pulmonary circuit by way of two anatomical shortcuts or *shunts* (fig. 20.18). One is the **foramen ovale,** the opening through the interatrial septum. Some of the blood entering the right atrium passes through this opening directly into the left atrium and from there into the left ventricle and systemic circuit. The other shunt is a short vessel, the **ductus arteriosus,** from the base of the left pulmonary artery to the aorta. Most of the blood that the right ventricle pumps into the pulmonary trunk takes this bypass directly into the aorta instead of following the usual path to the lungs.

At birth, the lungs inflate and their resistance to blood flow drops sharply. The sudden change in pressure gradients causes a flap of tissue to seal the foramen ovale. Blood in the right atrium is no longer able to flow directly into the left and bypass the lungs. In most people, the tissues grow together and permanently seal the foramen, leaving only a depression in the right atrial wall, the *fossa ovalis,* marking its former location. The foramen remains unsealed in about 15% of adults, but the tissue flap acts as a valve that prevents blood from passing through. The ductus arteriosus normally begins to constrict around 10 to 15 hours after birth. It is

---

[19] *truncus* = trunk; *arteriosus* = arterial
[20] *bulbus* = bulb; *cordis* = of the heart


Endocardial heart tubes
(a) Day 19
Heart tube
(b) Day 20
Truncus arteriosus
Bulbus cordis
Ventricle
Atrium
Sinus venosus
(c) Day 21
Truncus arteriosus
Bulbus cordis
Ventricle
Atrium
Sinus venosus
(d) Day 23
Conotruncus
Atrium
Bulbus cordis
Sinus venosus
Ventricle
Horns of sinus venosus
(e) Day 26
Conotruncus
Sinus venosus
Atrium
Left ventricle
Right ventricle
Interventricular septum
(f) Day 28

Figure 20.17 **Embryonic Development of the Heart.** (a) The endocardial heart tubes beginning to fuse at day 19. (b) Complete fusion by day 20, forming the heart tube. (c) Division of the heart tube into five dilated segments by day 21. The heart begins beating about a day later. (d) The heart begins looping around day 23, with the bulbus cordis migrating caudally (left arrow) and the atrium and sinus venosus migrating rostrally (right arrow). Blood circulates throughout the embryo within a day of this stage. (e) Looping is nearly completed by day 26. (f) Frontal section of the heart at 28 days. As the interventricular septum develops, the conotruncus will divide longitudinally into the ascending aorta and pulmonary trunk, receiving blood from the left and right ventricles, respectively. The single atrium seen here divides into the right and left atria by day 33.

effectively closed to blood flow within 2 to 4 days, and becomes a permanently closed fibrous cord *(ligamentum arteriosum)* by the age of 2 to 3 weeks (but see Deeper Insight 20.4).

The Aging Heart

A noteworthy effect of aging on the cardiovascular system is a stiffening of the arteries. While that itself is not a cardiac disease, it has important repercussions on the heart. Normally, when the ventricles eject blood, the arteries expand to accommodate the surge in pressure. When arteries are stiffened by age or calcified by arteriosclerosis, they cannot do so. They resist blood flow more than younger arteries, and the heart has to work harder to overcome this resistance. Like any other muscle, when the heart works harder, it grows. The ventricles enlarge, especially the left ventricle, which has to work the hardest to overcome the most resistance. In ventricular hypertrophy, the heart wall and interventricular septum can become so thick that the space within the ventricle is severely diminished. Cardiac output sometimes declines to the point of heart failure.

Many other changes are seen in the aging heart: The valve anuli become more fibrous or even calcified, and the AV valves (especially the mitral valve) thicken and tend to prolapse. The interventricular septum sometimes deviates to the left and interferes with the ejection of blood into the aorta. The fibrous skeleton becomes less elastic, so it has less capacity to rebound in diastole and aid in the filling of the heart. There is a loss of cells from the SA node and conduction system, so impulse conduction is less efficient and more irregular. Degeneration of the conduction system increases the risk of cardiac arrhythmia or heart block. Cardiocytes die off



Figure 20.18 **The Fetal Heart.** Note the two shunts (foramen ovale and ductus arteriosus) that allow most blood to bypass the nonfunctional lungs.

in the myocardium, and the heart thus becomes weaker. Exercise tolerance is further diminished by decreasing sensitivity to sympathetic stimulation in the elderly heart.

Heart Disease

Heart disease is the leading cause of death in the United States (about 30% of deaths per annum, averaged across all age groups). The most common form of heart disease is coronary atherosclerosis, often leading to myocardial infarction. However, there are a multitude of other heart diseases. The principal categories of heart disease are congenital defects in cardiac anatomy, myocardial hypertrophy or degeneration, inflammation of the pericardium and heart wall, valvular defects, and cardiac tumors. Several examples are described in the Deeper Insights in this chapter and in table 20.1.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

15. When does the embryonic heart begin to beat? At what gestational age does it become audible?
16. What are the five primitive chambers that develop from the heart tube? What becomes of each as the heart continues to develop?
17. Describe the two routes (shunts) by which fetal blood bypasses the lungs. What happens to each one shortly after birth?
18. Why does the heart tend to enlarge in old age? Why does the risk of cardiac arrhythmia increase?

DEEPER INSIGHT 20.4

Patent Ductus Arteriosus

Patent[21] *ductus arteriosus (PDA)* is the failure of the ductus arteriosus to close. For a short time after birth, PDA causes no problems; but as the lungs become better inflated and more functional, pulmonary blood pressure drops below aortic blood pressure. Blood may then begin to flow from the aortic arch back into the pulmonary circuit for an immediate second trip through the lungs. Since this blood soon returns to the left ventricle, it adds markedly to the left ventricular workload. The lungs sometimes respond to the persistent high blood flow with vascular changes that increase pulmonary resistance and stress the right ventricle as well.

The signs of PDA include poor weight gain in early childhood, frequent respiratory illnesses, *dyspnea* (difficulty breathing) on exertion, and *cardiomegaly* (enlargement of the heart). PDA is usually suspected at about 6 to 8 weeks of age because of a persistent "machinery-like" heart murmur; it is confirmed by X-ray and other cardiac imaging methods.

Usually, the ductus arteriosus can be stimulated to close with a prostaglandin inhibitor, but if this fails, surgery is required. Surgery is ideally performed between 1.5 and 2.5 years of age because there is a rising risk of *infective endocarditis* (table 20.1) if it is delayed. The usual procedure is to tie off the DA with several ligatures. This is a low-risk surgery with almost no mortality. However, other methods are available for blocking blood flow through the DA that are less invasive and give an easier recovery for the young patient.

---

[21] *patent* = open

TABLE 20.1 Common Cardiac Pathologies

Cardiac tamponade	Compression of the heart by serous fluid or clotted blood in the pericardial cavity, rendering the heart unable to expand and fill completely during diastole, thus reducing systolic output. (See also Deeper Insight 1.2, p. 17.)
Cardiomyopathy	Any disease of the myocardium from causes other than valvular dysfunction or vascular diseases. Can cause atrophy or hypertrophy of the heart wall and interventricular septum, or dilation and failure of the heart.
Congestive heart failure (CHF)	Failure of either ventricle to pump as much blood as the other one, resulting in accumulation of blood and edema (congestion) in peripheral tissues. Left ventricular failure results in pulmonary congestion and right ventricular failure in systemic congestion (once called *dropsy*). Failure of one ventricle stresses the other and may lead to its subsequent failure.
Infective endocarditis	Inflammation of the endocardium, usually due to bacterial infection with streptococci or staphylococci.
Mitral valve prolapse (MVP)	A valvular defect in which one or both mitral valve cusps balloon into the atrium during ventricular contraction. Often hereditary, affecting 1 out of 40 people overall, and young women especially. Causes significant illness in only 3% of cases, including chest pain, fatigue, shortness of breath, and occasionally infective endocarditis, arrhythmia, or stroke.
Rheumatic fever	Autoimmune disease triggered by a bacterial infection. Antibodies against streptococci or other bacteria attack tissues of the heart valves, causing scarring and constriction (stenosis) of the valves, especially the mitral valve. Regurgitation of blood through the incompetent valve causes turbulence heard as a *heart murmur*.
Septal defects	Abnormal openings in the interatrial or interventricular septum, allowing blood to flow directly between right and left heart chambers. Results in pulmonary hypertension, difficulty breathing, and fatigue. Often fatal in childhood if not corrected.
Ventricular fibrillation	Squirming, uncoordinated contractions of the ventricular myocardium with no effective ejection of blood. Often caused by myocardial infarction (MI); the usual cause of death in heart attack.

Disorders Described Elsewhere

Angina pectoris	551
Arrhythmia	553
Coronary artery disease	551
Heart block	553, 555
Myocardial infarction	551
Patent ductus arteriosus	559
Pericarditis	543

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

20.1 Overview of the Cardiovascular System (p. 540)

1. The two circuits of the cardiovascular system, the functions of each, and which side of the heart supplies each one
2. The great vessels and their associations with the heart chambers
3. The location and orientation of the heart relative to adjacent organs and the median plane of the body
4. The shape, size, and weight of the average adult heart
5. The pericardium, its parietal and visceral layers, the two tissue layers of the pericardial sac, and attachments of the pericardial sac to adjacent organs
6. The pericardial cavity and significance of the pericardial fluid

20.2 Gross Anatomy of the Heart (p. 543)

1. The names and histological composition of the three layers of the heart wall
2. The components and functions of the fibrous skeleton of the heart
3. The names, locations, and functions of the four heart chambers and the surface landmarks of the heart that correspond to the four chambers
4. Reasons for the differences in muscularity between the atria and ventricles and between the right and left ventricles
5. The great vessels and their relationships to the heart chambers
6. The internal septa that separate the heart chambers from each other
7. The names, locations, and anatomy of the two atrioventricular valves, and their relationships with the tendinous cords and papillary muscles
8. The names, locations, and anatomy of the two semilunar valves
9. The mode of operation of the heart valves
10. The path of blood flow through the heart chambers and valves

20.3 Coronary Circulation (p. 549)

1. The origins, branches, and distribution of the two coronary arteries
2. The major veins of the coronary circulation and the routes of coronary blood drainage into the right atrium
3. The cause of myocardial infarction and the protection afforded by collateral circulation in the heart
4. The reasons why coronary blood flow is greatest in diastole and diminished in systole, in contrast to arterial blood flow elsewhere in the body

20.4 The Cardiac Conduction System and Cardiac Muscle (p. 552)

1. The name and location of the pacemaker of the heart
2. The role of the atrioventricular bundle, bundle branches, Purkinje fibers, and myocardial gap junctions in conducting electrical excitation through the heart
3. The specialized structural features of cardiocytes, especially the components of the intercalated discs
4. The origins and terminations of sympathetic and parasympathetic nerves to the heart, and their respective effects on cardiac function
5. The four principal phases of the cardiac cycle and how they relate to cardiac anatomy

20.5 Developmental and Clinical Perspectives (p. 557)

1. The embryonic origin of the heart tube and how the tube divides and folds to produce the fully formed heart
2. The two shunts in and near the fetal heart that enable most blood to bypass the nonfunctional lungs
3. The changes in cardiac anatomy and blood flow that occur at birth when the infant begins to breathe on its own
4. The effects of aging on the heart
5. The principal categories of heart disease and essential features of some common heart diseases

Testing Your Recall

1. The cardiac conduction system includes all of the following *except*
   a. the SA node.
   b. the AV node.
   c. the bundle branches.
   d. the tendinous cords.
   e. the Purkinje fibers.
2. To get from the right atrium to the right ventricle, blood flows through the right AV, or _____, valve.
   a. pulmonary
   b. tricuspid
   c. semilunar
   d. aortic
   e. mitral
3. There is/are _____ pulmonary vein(s) emptying into the right atrium of the heart.
   a. no
   b. one
   c. two
   d. four
   e. more than four
4. The coronary blood vessels are part of the _____ circuit of the circulatory system.
   a. cardiac
   b. pulmonary
   c. systematic
   d. systemic
   e. cardiovascular
5. The outermost layer of the heart wall is known as
   a. the pericardial sac.
   b. the epicardium.
   c. the visceral pericardium.
   d. both *a* and *c*.
   e. both *b* and *c*.
6. These are some of the points that the blood passes as it circulates through the heart chambers, listed alphabetically: (1) left atrium, (2) left ventricle, (3) mitral valve, (4) pulmonary valve, (5) right atrium, (6) right ventricle, (7) tricuspid valve. Place these in the correct order from the time that blood enters the heart from the venae cavae to the time blood leaves the heart by way of the aorta.
   a. 1–3–2–4–5–7–6
   b. 1–2–3–5–7–6–4
   c. 5–3–6–4–1–2–7
   d. 6–7–5–4–2–3–1
   e. 5–7–6–4–1–3–2
7. The ascending aorta and pulmonary trunk develop from the embryonic
   a. bulbus cordis only.
   b. truncus arteriosus only.
   c. horns of the sinus venosus.
   d. conotruncus.
   e. ventricle.
8. The _____ prevent the AV valves from bulging into the atria during ventricular systole.
   a. tendinous cords
   b. pectinate muscles
   c. trabeculae carneae
   d. AV nodes
   e. cusps
9. Blood in the anterior interventricular branch of the left coronary artery flows into myocardial blood capillaries and next drains into
   a. the superior vena cava.
   b. the great cardiac vein.
   c. the left atrium.
   d. the middle cardiac vein.
   e. the coronary sinus.
10. Which of these is *not* characteristic of the heart in old age?
    a. ventricular enlargement
    b. thickening of the atrial walls
    c. a less elastic fibrous skeleton
    d. fewer cells in the conduction system
    e. less sensitivity to norepinephrine
11. The contraction of any heart chamber is called _____, and its relaxation is called _____.
12. The circulatory route from aorta to the venae cavae is the _____ circuit.
13. The circumflex branch of the left coronary artery travels in a groove called the _____.
14. The finest passages through which electrical signals pass before reaching the ventricular cardiocytes are called _____.
15. Electrical signals pass quickly from one cardiocyte to another through the _____ of the intercalated discs.
16. The abnormal bulging of the left AV valve into the atrium is called _____.
17. The _____ nerves innervate the heart and tend to reduce the heart rate.
18. The death of cardiac tissue from lack of blood flow is commonly known as a heart attack, but is clinically called _____.
19. Blood in the heart chambers is separated from the myocardium by a thin membrane called the _____.
20. The sinoatrial node develops from an embryonic heart tube chamber called the _____.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. cardio-
2. epi-
3. semi-
4. -ary
5. -icle
6. -genic
7. lun-
8. coron-
9. ventr-
10. fasci-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. All blood that has circulated through the myocardium eventually flows into the coronary sinus and from there to the right atrium.
2. The aorta is the body's largest artery.
3. Normally, the only way electrical signals can get from the atria to the ventricles is to pass through the AV node and AV bundle.
4. The epicardium contains adipose tissue, but the endocardium does not.
5. If all nerves from the central nervous system to the heart were severed, the heart would stop beating.
6. The thickest myocardium is normally found in the left ventricle.
7. Many of the cardiac veins have anastomoses that ensure the myocardium will receive blood even if one of the veins becomes blocked.
8. During embryonic development, a ventricular septum grows and divides the single primordial ventricle into right and left ventricles.
9. Blood in the superior and inferior venae cavae flows through the semilunar valves as it enters the right atrium.
10. Cardiocytes transmit electrical signals to each other by way of their gap junctions.

Answers in appendix A

Testing Your Comprehension

1. Mr. Jones, 78, dies of a massive myocardial infarction triggered by coronary thrombosis. Upon autopsy, necrotic myocardium is found in the lateral and posterior right ventricle and posterior interventricular septum. Based on the information in this chapter, where in the coronary circulation do you think the thrombosis occurred?
2. Becky, age 2, was born with a hole in her interventricular septum (*ventricular septal defect,* or *VSD*). Considering that the blood pressure in the left ventricle is significantly higher than blood pressure in the right ventricle, predict the effect of the VSD on Becky's pulmonary blood pressure, systemic blood pressure, and long-term changes in the ventricular walls.
3. Marcus is born with *transposition* of the great arteries, in which the aorta arises from the right ventricle and the pulmonary artery arises from the left. Assuming no other anatomical abnormalities, trace the flow of blood through the pulmonary and systemic routes in his case. Predict the consequences, if any, for the ability of Marcus's cardiovascular system to deliver oxygen to the systemic tissues. Do you think Marcus would require immediate surgical correction in early infancy, correction at the age of 2 or 3 years, or that it could be left alone and not seriously affect his life expectancy?
4. Review the condition of heart block in Deeper Insight 20.2, and examine the electrocardiogram for this condition in figure 20.15c. Explain why the second P wave in the ECG is followed by another P instead of a QRS complex.
5. In dilated cardiomyopathy of the left ventricle, the ventricle can become enormously enlarged. Explain why this might lead to regurgitation of blood through the mitral valve (blood flowing from the ventricle back into the left atrium) during ventricular systole.



Capillary beds

© Biophoto Associates/Science Source

CHAPTER 21

THE CIRCULATORY SYSTEM III
BLOOD VESSELS

CHAPTER OUTLINE

21.1 General Anatomy of the Blood Vessels 564
- The Vessel Wall 564
- Arteries 565
- Capillaries 567
- Veins 570
- Circulatory Routes 571

21.2 The Pulmonary Circuit 572

21.3 Systemic Vessels of the Axial Region 573
- The Aorta and Its Major Branches 576
- Arteries of the Head and Neck 576
- Veins of the Head and Neck 579
- Arteries of the Thorax 581
- Veins of the Thorax 582
- Arteries of the Abdomen and Pelvic Region 584
- Veins of the Abdomen and Pelvic Region 588

21.4 Systemic Vessels of the Appendicular Region 590
- Arteries of the Upper Limb 590
- Veins of the Upper Limb 592
- Arteries of the Lower Limb 594
- Veins of the Lower Limb 597

21.5 Developmental and Clinical Perspectives 601
- Embryonic Development of the Blood Vessels 601
- Changes at Birth 602
- The Aging Vascular System 603
- Vascular Diseases 603

Study Guide 605

DEEPER INSIGHTS

21.1 Aneurysm 566
21.2 Varicose Veins 571
21.3 Air Embolism 579
21.4 Central Venous Catheters 592
21.5 Arterial Pressure Points 600

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:

- Primary germ layers of the embryo (p. 89)
- Muscle compartments of the limbs (p. 294)
- The pulmonary and systemic circuits (p. 540)
- The great vessels associated with the heart (p. 541)
- Cardiac systole and diastole (p. 555)

Anatomy & Physiology REVEALED
aprevealed.com

Module 9: Cardiovascular System

The route taken by the blood after it leaves the heart was a point of much confusion for many centuries. In traditional Chinese medicine as early as 2650 BCE, blood was correctly believed to flow in a complete circuit around the body and back to the heart. But in the second century BCE, Roman physician Claudius Galen argued that it flowed back and forth in the veins, like air in the bronchial tubes. He believed that the liver received food directly from the esophagus and converted it to blood, the heart pumped the blood through the veins to all other organs, and those organs consumed it. The arteries were thought to contain only a mysterious vapor or "vital spirit."

The Chinese view was correct, but the first experimental demonstration of this did not come for another 4,000 years. English physician William Harvey (1578–1657) studied the filling and emptying of the heart in snakes; tied off the vessels above and below the heart to observe the effects on cardiac filling and output; measured cardiac output in a variety of living animals; and estimated the cardiac output in humans. He concluded that (1) the heart pumps more blood in half an hour than there is in the entire body; (2) not enough food is consumed to account for the continual production of so much blood; and therefore (3) the blood returns to the heart rather than being consumed by the peripheral organs. He could not explain how, since the microscope had yet to be developed to the point that allowed Marcello Malpighi (1628–94) and later, Antony van Leeuwenhoek (1632–1723), to discover the blood capillaries.

Harvey published his findings in 1628 in a short but elegant book entitled *Exercitio Anatomica de Motu Cordis et Sanguinis in Animalibus (Anatomical Studies on the Motion of the Heart and Blood in Animals).* This landmark in the history of biology and medicine was the first experimental study of animal physiology. But so entrenched were the ideas of Aristotle and Galen in the medical community, and so strange was the idea of doing experiments on living animals, that Harvey's contemporaries rejected his ideas. Indeed, some of them regarded him as a crackpot because his conclusion flew in the face of common sense—if the blood was continually recirculated and not consumed by the tissues, they reasoned, then what purpose could it possibly serve?

Harvey lived to a ripe old age, served as physician to the kings of England, and later did important work in embryology. His case is one of the most interesting in biomedical history, for it shows how empirical science overthrows old theories and spawns better ones, and how common sense and blind allegiance to authority can interfere with acceptance of the truth. But most importantly, Harvey's contributions represent the birth of experimental physiology.

21.1 General Anatomy of the Blood Vessels

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the structure of a blood vessel;
b. describe the different types of arteries, capillaries, and veins;
c. trace the general route usually taken by the blood from the heart and back again; and
d. describe some variations on this route.

There are three principal categories of blood vessels—arteries, veins, and capillaries. **Arteries** are the efferent vessels of the cardiovascular system—that is, vessels that carry blood away from the heart. **Veins** are the afferent vessels—vessels that carry blood back to the heart. **Capillaries** are microscopic, thin-walled vessels that connect the smallest arteries to the smallest veins. Aside from their general location and direction of blood flow, these three vessel types also differ in the histological structure of their walls.

The Vessel Wall

The walls of arteries and veins are composed of three layers called *tunics* (figs. 21.1 and 21.2):

1. The **tunica interna (tunica intima)** lines the inside of the vessel and is exposed to the blood. It consists of a simple squamous epithelium called the **endothelium,** overlying a basement membrane and a sparse layer of loose connective tissue; it is continuous with the endocardium of the heart. The endothelium acts as a selectively permeable barrier to materials entering or leaving the bloodstream; it secretes chemicals that stimulate the muscle of the vessel wall to contract or relax, thus narrowing or widening the vessel; and it normally repels blood cells and platelets so that they flow freely without sticking to the vessel wall. Under special circumstances, however, platelets and blood cells do adhere to it. When the endothelium is damaged, platelets can adhere and form a blood clot; and when the tissue around a vessel is inflamed, the endothelial cells produce *cell-adhesion molecules* that induce leukocytes to adhere to the surface. This causes leukocytes to congregate in tissues where their defensive actions are needed.
2. The **tunica media,** the middle layer, is usually the thickest. It consists of smooth muscle, collagen, and in some cases, elastic tissue. The relative amounts of muscle and elastic tissue vary greatly from one vessel to another and form a basis for the classification of vessels described in the next section. The tunica media strengthens the vessels and prevents blood pressure from rupturing them, and the muscle widens or narrows the vessel—actions called *vasodilation* and *vasoconstriction.*
3. The **tunica externa (tunica adventitia**[1]) is the outermost layer. It consists of loose connective tissue that often merges with that of neighboring blood vessels, nerves, or other organs. It anchors the vessel and allows small nerves, lymphatic vessels, and smaller blood vessels to reach and penetrate into the tissues of a larger vessel.

All blood vessels require nutrition, oxygenation, and waste-removal services for their own tissues, and the medium to large arteries and veins cannot have these needs adequately met by the blood flowing through them. That blood flows too rapidly and the vessel wall is too thick for adequate exchange of chemicals between the blood and tissue fluid. Therefore smaller vessels penetrate into the external surface of the large ones, gaining access through the tunica externa, and branch into capillaries that supply the tissues of the larger vessel. The network of smaller vessels serving the larger one is called the **vasa vasorum**[2] (VAY-za vay-SO-rum).

---

[1] *advent* = added to
[2] *vasa* = vessels; *orum* = of


Large vein
Lumen
Tunica interna:
Endothelium
Basement membrane
Tunica media
Tunica externa
Vasa vasorum
Nerve
Conducting (large) artery
Lumen
Tunica interna:
Endothelium
Basement membrane
Tunica media
Tunica externa
Vasa vasorum
Nerve
Medium vein
Tunica interna:
Endothelium
Basement membrane
Valve
Tunica media
Tunica externa
Inferior vena cava
Aorta
Distributing (medium) artery
Tunica interna:
Endothelium
Basement membrane
Internal elastic lamina
Tunica media
External elastic lamina
Tunica externa
Direction of blood flow
Venule
Tunica interna:
Endothelium
Basement membrane
Tunica media
Tunica externa
Arteriole
Tunica interna:
Endothelium
Basement membrane
Tunica media
Tunica externa
Endothelium
Basement membrane
Capillary

Figure 21.1 **Histological Structure of Blood Vessels.**
• *Why do the arteries have so much more elastic tissue than the veins do?*

They are most conspicuous in the tunica externa because the loose organization of the tissue here does not obscure the view of them as much as tissue of the tunica media does. They supply blood to at least the outer half of the vessel wall. Tissues of the inner half are thought to be nourished by diffusion from blood in the lumen.

Arteries

Arteries are considered to be the *resistance vessels* of the cardiovascular system because they have a relatively strong, resilient tissue structure that resists the high blood pressure within. Each beat of the heart creates a surge of pressure in the arteries as blood is ejected into them. Arteries are built to withstand these pressure surges. Being more muscular than veins, they retain their round shape even when empty, and they appear relatively circular in tissue sections.

Classes of Arteries

Arteries are divided into three classes by size, but of course there is a gradual transition from one class to the next.

1. **Conducting** (**elastic** or **large**) **arteries** are the biggest arteries. Like an interstate highway, they serve only to deliver blood at high speed to the major “exit ramps” that head off to individual organs. The aorta, common carotid and subclavian arteries, pulmonary trunk, and common iliac arteries are


Capillaries
Artery:
Tunica interna
Tunica media
Tunica externa
Nerve
Vein
(a)
1 mm
Tributaries of thyroid vein
Branches of thyroid artery
Capillary beds surrounding thyroid follicles
(b)
100 µm

© McGraw-Hill Education/Dennis Strete, photographer

© Susumu Nishinaga/Science Source

Figure 21.2 **Micrographs of Blood Vessels.** (a) A neurovascular bundle, composed of a small artery, small vein, and nerve traveling together in a common sheath of connective tissue. The dark wavy line near the lumen of the artery is the internal elastic lamina. (b) A polymer cast of blood vessels of the eye (SEM).

examples of conducting arteries. They have a layer of elastic tissue called the *internal elastic lamina* at the border between the interna and media, but microscopically, it is incomplete and difficult to distinguish from the elastic tissue of the tunica media. The tunica media consists of 40 to 70 layers of elastic sheets, perforated like slices of Swiss cheese, alternating with thin layers of smooth muscle, collagen, and elastic fibers. In histological sections, the view is dominated by this elastic tissue. The perforations allow nerves and vasa vasorum to penetrate through all layers of the vessel and for smooth muscle cells to communicate with each other through gap junctions. There is an *external elastic lamina* at the border between the media and externa, but it, too, is difficult to distinguish from the elastic sheets of the tunica media. The tunica externa is less than half as thick as the tunica media and relatively sparse in the largest arteries. It is well supplied with vasa vasorum.

Conducting arteries expand during ventricular systole to receive blood, and recoil during diastole. Their expansion takes some of the pressure off the blood so that smaller arteries downstream are subjected to less systolic stress. Their recoil between heartbeats prevents the blood pressure from dropping too low while the heart is relaxing and refilling. These effects lessen the fluctuations in blood pressure that would otherwise occur. Arteries stiffened by atherosclerosis cannot expand and recoil as freely. Consequently, the downstream vessels are subjected to greater stress and are more likely to develop aneurysms (see Deeper Insight 21.1).

DEEPER INSIGHT 21.1

Aneurysm

An aneurysm is a weak point in an artery or in the heart wall. It forms a thin-walled, bulging sac that pulsates with each beat of the heart and may eventually rupture. In a *dissecting aneurysm,* blood accumulates between the tunics of an artery and separates them, usually because of degeneration of the tunica media. The most common sites of aneurysms are the abdominal aorta (fig. 21.3), renal arteries, and the arterial circle at the base of the brain. Even without hemorrhaging, aneurysms can cause pain or death by putting pressure on brain tissue, nerves, adjacent veins, pulmonary air passages, or the esophagus. Other consequences include neurological disorders, difficulty in breathing or swallowing, chronic cough, or congestion of the tissues with blood. Aneurysms sometimes result from congenital weakness of the blood vessels and sometimes from trauma or bacterial infections such as syphilis. The most common cause, however, is the combination of atherosclerosis and hypertension.



© Zephyr/Science Source

Figure 21.3 **An Aortic Aneurysm.** This is a magnetic resonance angiogram (MRA) of the abdominal aorta of a patient with hypertension, showing a prominent bulge (aneurysm) of the aorta immediately superior to the common iliac arteries.

2. **Distributing** (**muscular** or **medium**) **arteries** are smaller branches that distribute blood to specific organs, like the exit ramps and state highways that serve individual towns. Most arteries that have specific anatomical names are in these first two size classes. The brachial, femoral, renal, and splenic arteries are examples of distributing arteries. Distributing arteries typically have up to 40 layers of smooth muscle, constituting about three-quarters of the wall thickness. In histological sections, smooth muscle is more conspicuous than the elastic tissue. Both the internal and external elastic laminae, however, are thick and often conspicuous.
3. **Resistance (small) arteries** are so called because their small diameter and great number make them the major point of resistance against blood flowing into any particular organ. In our highway analogy, they are like the city streets where traffic slows down substantially; the narrow diameter of these arteries is responsible for this slowing. These arteries usually have no specific anatomical names because their locations and arrangement are so variable from one person to another and even change over the course of a person's lifetime. They are less than 0.1 mm in diameter and usually have one to five layers of smooth muscle. The smallest resistance arteries, with only one to three layers of smooth muscle, are called **arterioles.** Arterioles have very little tunica externa. They are the major point of control over how much blood an organ or tissue receives.

In some places, short vessels called **metarterioles**[3] link arterioles and capillaries or provide shortcuts through which blood can bypass the capillaries and flow directly to a venule. Instead of a continuous tunica media, they have individual muscle cells spaced a short distance apart, each forming a **precapillary sphincter** that encircles the entrance to one capillary. Constriction of these sphincters reduces or shuts off blood flow through their respective capillaries and diverts blood to tissues or organs elsewhere.

Arterial Sense Organs

Certain major arteries above the heart have sensory receptors in their walls that monitor blood pressure and chemistry (fig. 21.4). These receptors transmit information to the brainstem that serves to regulate the heartbeat, vasomotion, and respiration. They are of three main kinds.

1. **Carotid sinuses** are *baroreceptors* (pressure sensors) that respond to changes in blood pressure. Ascending the neck on each side is a *common carotid artery* that branches near the angle of the mandible to form the *internal carotid artery* to the brain and *external carotid artery* to the face. The carotid sinuses are located in the wall of the internal carotid artery just above the branch point. The carotid sinus has a relatively thin tunica media and an abundance of glossopharyngeal nerve fibers in the tunica externa. A rise in blood pressure easily stretches the thin media and stimulates these nerve fibers. The glossopharyngeal nerve then transmits signals to the vasomotor and cardiac centers of the brainstem, and the brainstem responds by lowering the heart rate and dilating the blood vessels, thereby lowering the blood pressure. Similar baroreceptors also occur in the wall of the aortic arch.


Carotid body (containing chemoreceptors)
External carotid artery
Right common carotid artery
Right subclavian artery
Aortic arch
Internal carotid artery
Carotid sinus (containing baroreceptors)
Left common carotid artery
Aortic bodies (containing chemoreceptors)
Left subclavian artery
Baroreceptors

Figure 21.4 **Baroreceptors and Chemoreceptors in the Arteries Superior to the Heart.** The structures shown here are repeated in the left carotid arteries. AP|R

2. **Carotid bodies,** also located near the branch of the common carotid arteries, are oval receptors about 3 by 5 mm, innervated by sensory fibers of the glossopharyngeal nerves. They are *chemoreceptors* that monitor changes in blood composition. They primarily transmit signals to the brainstem respiratory centers, which adjust breathing to stabilize the blood pH and its CO_2 and O_2 levels.
3. **Aortic bodies** are one to three chemoreceptors located in the aortic arch near the arteries to the head and arms. They are structurally similar to the carotid bodies and have the same function. They are innervated by the vagus nerves.

Capillaries

For the blood to serve any purpose, materials such as nutrients, wastes, and hormones must pass between the blood and the tissue fluids, through the walls of the vessels. In nearly all of the larger vessels, the wall is too thick for significant passage of chemicals between the bloodstream and tissue fluid. There are only two places in the circulation where this occurs—the capillaries and venules. We can think of these as the "business end" of the cardiovascular system, because all the rest of the system exists to serve the exchange processes that occur here. Since capillaries greatly outnumber venules, they are the more important of the two. Capillaries are sometimes called the *exchange vessels* of the cardiovascular system. The smallest blood vessels—arterioles, capillaries, and venules—are also called the **microvasculature (microcirculation).**

---

[3] *meta* = beyond, next in a series

Blood capillaries (fig. 21.5) are composed of only an endothelium and basal lamina. Their walls are as thin as 0.2 to 0.4 µm. They average about 5 µm in diameter at the proximal end (where they receive arterial blood), they widen to about 9 µm at the distal end (where they empty into a small vein), and they often branch along the way. Since erythrocytes are about 7.5 µm in diameter, they often have to stretch into elongated shapes to squeeze through the smallest capillaries.

The number of capillaries has been estimated at a billion and their total surface area at 6,300 m^2, but a more important point is that scarcely any cell in the body is more than 60 to 80 µm (about four to six cell widths) away from the nearest capillary. There are a few exceptions: Capillaries are scarce in tendons and ligaments, rarely found in cartilage, and absent from epithelia and the cornea and lens of the eye.

Types of Capillaries

There are three types of capillaries, distinguished by the ease with which they allow substances to pass through their walls and by structural differences that account for their greater or lesser permeability.

1. **Continuous capillaries** (fig. 21.5) occur in most tissues, such as skeletal muscle. Their endothelial cells, held together by tight junctions, form a continuous tube like a water hose. Sometimes a single endothelial cell rolls into a tube, like a burrito, forming the entire wall at a given point. A thin protein–carbohydrate layer, the **basal lamina,** surrounds the endothelium and separates it from the adjacent connective tissues. The endothelial cells are usually separated by narrow **intercellular clefts** about 4 nm wide. Small solutes such as glucose can pass through these clefts, but plasma proteins, other large molecules, and platelets and blood cells are held back. The continuous capillaries of the brain lack intercellular clefts and have more complete tight junctions that form the blood–brain barrier discussed in chapter 15 (p. 405).



Figure 21.5 Structure of a Continuous Capillary (Cross Section).

Some continuous capillaries exhibit cells called **pericytes** that lie external to the endothelium. Pericytes have elongated tendrils that wrap around the capillary. They contain the same contractile proteins as muscle, and it is thought that they contract and regulate blood flow through the capillaries. They also can differentiate into endothelial and smooth muscle cells and thus contribute to vessel growth and repair.

2. **Fenestrated capillaries** have endothelial cells riddled with holes called **filtration pores (fenestrations**[4]**)** (fig. 21.6). These pores are about 60 to 80 nm in diameter, and are often spanned by a thin glycoprotein membrane. They allow for the rapid passage of small molecules and even molecules as large as protein hormones (for example, insulin), but they still retain most proteins and larger particles in the bloodstream. Fenestrated capillaries are important in organs that engage in rapid absorption or filtration—the kidneys, endocrine glands, small intestine, and choroid plexuses of the brain, for example.
3. **Sinusoids (discontinuous capillaries)** are irregular blood-filled spaces in the liver, bone marrow, spleen, and some other organs (fig. 21.7). They are twisted, tortuous passageways, typically 30 to 40 µm wide, that conform to the shape of the surrounding tissue. The endothelial cells are separated by wide gaps with no basal lamina, and the cells also frequently have especially large fenestrations through them. Even proteins and blood cells can pass through these pores; this is how albumin, clotting factors, and other proteins synthesized by the liver enter the blood, and how newly formed blood cells enter the circulation from the bone marrow and lymphatic organs. Some sinusoids contain macrophages or other specialized cells.

Capillary Permeability

The structure of a capillary wall is closely related to its permeability, the ease with which substances pass through it from the blood to the tissue fluid, or vice versa. There are three routes that materials can travel through a capillary wall (fig. 21.8): (1) the intercellular clefts between endothelial cells; (2) the filtration pores in fenestrated capillaries; and (3) the endothelial cell plasma membrane and cytoplasm. Nonpolar molecules such as O_2, CO_2, lipids, and thyroid hormone diffuse easily through the endothelial cells. Hydrophilic substances such as glucose, electrolytes, and large molecules such as insulin pass through the intercellular clefts and filtration pores, or cross through the endothelial cells by a process called *transcytosis:* The endothelial cell internalizes molecules or fluid droplets by endocytosis on one side of the capillary wall, transports the endocytotic vesicles to the other side of the cell, and releases the substances by exocytosis on that side.

Capillary Beds

Capillaries are organized into groups called **capillary beds**—usually 10 to 100 capillaries supplied by a single arteriole or metarteriole (fig. 21.9; see also photo on p. 563). Beyond the origins of the capillaries, the metarteriole continues as a **thoroughfare channel** leading directly to a venule. Capillaries empty into the distal end of the thoroughfare channel or directly into the venule.

---

[4] *fenestra* = window


Endothelial cells
Erythrocyte
Filtration pores (fenestrations)
Basal lamina
Intercellular cleft
(a)
Nonfenestrated area
(b)
400 µm
Courtesy of S. McNutt

Figure 21.6 **Structure of a Fenestrated Capillary.** (a) Cross section of the capillary wall. (b) Surface view of a fenestrated endothelial cell (SEM). The cell has patches of filtration pores (fenestrations) separated by nonfenestrated areas.

- *Identify some organs that have this type of capillary rather than continuous capillaries.*


Macrophage
Endothelial cells
Erythrocytes in sinusoid
Liver cell (hepatocyte)
Microvilli
Sinusoid

Figure 21.7 **A Sinusoid of the Liver.** Large gaps between the endothelial cells allow blood plasma to directly contact the liver cells, but retain blood cells in the lumen of the sinusoid.


Filtration pores
Transcytosis
Diffusion through endothelial cells
Intercellular clefts

Figure 21.8 **Pathways of Capillary Fluid Exchange.** Materials move through the capillary wall through filtration pores (in fenestrated capillaries only), by transcytosis, by diffusion through the endothelial cells, and through intercellular clefts. Although this figure depicts material leaving the bloodstream, material can also enter the bloodstream by the same methods.

When the precapillary sphincters are open, the capillaries are well supplied with blood and engage in exchanges with the tissue fluid. When the sphincters are closed, blood bypasses the capillaries, flows through the thoroughfare channel to a venule, and engages in relatively little fluid exchange. There is not enough blood in the body to fill the entire vascular system at once; consequently, about three-quarters of the body's capillaries are shut down at any given time. In the skeletal muscles, for example, about 90% of them have little to no blood flow during periods of rest. During exercise, they receive an abundant flow, while capillary beds elsewhere—for example, in the skin and intestines—shut down to compensate for it.



(a) Sphincters open



(b) Sphincters closed

Figure 21.9 **Regulation of Capillary Blood Flow.** (a) Precapillary sphincters dilated and capillaries abundantly supplied with blood. (b) Precapillary sphincters closed, with blood bypassing the capillaries.

Veins

Veins are regarded as the *capacitance vessels* of the cardiovascular system because they are relatively thin-walled and flaccid, and expand easily to accommodate an increased volume of blood; that is, they have a greater capacity for blood containment than arteries do. At rest, about 64% of the blood is found in the systemic veins as compared with only 13% in the systemic arteries (fig. 21.10). The reason that veins are so thin-walled and accommodating is that, being distant from the ventricles of the heart, they are subjected to relatively low blood pressure. In large arteries, blood pressure averages 90 to 100 mm Hg (millimeters of mercury) and surges to 120 mm Hg during systole, whereas in veins, it averages about 10 mm Hg. Furthermore, the blood flow in the veins is steady, rather than pulsating with the heartbeat like the flow in the arteries. Veins therefore do not require thick, pressure-resistant walls. They collapse when empty and thus have relatively flattened, irregular shapes in histological sections (see fig. 21.2).

As we trace blood flow in the arteries, we find it splitting off repeatedly into smaller and smaller *branches* of the arterial system. In the venous system, conversely, we find small veins merging to form larger and larger ones as they approach the heart. We refer to the smaller veins as *tributaries,* by analogy to the streams that converge and act as tributaries to rivers. In examining the types of veins, we will follow the direction of blood flow, working up from the smallest to the largest vessels.

1. **Postcapillary venules** are the smallest of the veins, beginning with diameters of about 15 to 20 µm. They receive blood from capillaries directly or by way of the distal ends of the thoroughfare channels. They have a tunica interna surrounded by only a few pericytes and reticular fibers—no muscle. Postcapillary venules are even more porous than capillaries; therefore, venules also exchange fluid with the surrounding tissues. Most leukocytes emigrate from the bloodstream through the venule walls.
2. **Muscular venules** receive blood from the postcapillary venules. Above 1 mm in diameter, they also have smooth muscle cells, which are scattered at first but become a continuous layer (tunica media) in the larger venules.
3. **Medium veins** range up to 10 mm in diameter. Most veins with individual names are in this category, such as the radial and ulnar veins of the forearm and the small and great



Figure 21.10 **Typical Distribution of the Blood in a Resting Adult.**
• *What anatomical fact allows the veins to contain so much more blood than the arteries do?*

saphenous veins of the leg. Medium veins have a tunica media of loosely organized bundles of smooth muscle interrupted by regions of collagenous, reticular, and elastic tissue. The tunica externa is relatively thick.

Many medium veins, especially in the limbs, exhibit infoldings of the tunica interna that meet in the middle of the lumen, forming **venous valves** directed toward the heart (fig. 21.11). The pressure in the veins is not high enough to push all of the blood upward against the pull of gravity in a standing or sitting person. The upward flow of blood in these vessels depends partly on the massaging action of skeletal muscles and the ability of these valves to keep the blood from dropping down again when the muscles relax. When the muscles surrounding a vein contract, they force blood through the valves. The propulsion of blood by muscular massaging, aided by the venous valves, is a mechanism of blood flow called the *skeletal muscle pump.* Varicose veins result in part from failure of the valves (see Deeper Insight 21.2). Such valves are absent from very small and large veins, veins of the abdominal cavity, and veins of the brain.

4. **Venous sinuses** are veins with especially thin walls, large lumens, and no smooth muscle. Examples include the coronary sinus of the heart and the dural sinuses of the brain. Unlike other veins, they are not capable of vasomotion.
5. **Large veins** have diameters greater than 10 mm. They have some smooth muscle in all three tunics. The tunica media is relatively thin with only a moderate amount of smooth muscle; the tunica externa is the thickest layer and contains longitudinal bundles of muscle. Large veins include the venae cavae, pulmonary veins, internal jugular veins, and renal veins.



(a) Contracted skeletal muscles **(b) Relaxed skeletal muscles**

Figure 21.11 **The Skeletal Muscle Pump.** (a) Muscle contraction squeezes the deep veins and forces blood through the next valve in the direction of the heart. Valves below the point of compression prevent backflow. (b) When the muscles relax, blood flows back downward under the pull of gravity but can flow only as far as the nearest valve.

Apply What You Know

Why would venous valves be unnecessary in the jugular veins of the neck?

Circulatory Routes

The simplest and most common route of blood flow is heart ⟶ arteries ⟶ capillaries ⟶ veins ⟶ heart. Blood usually passes through only one network of capillaries from the time it leaves the heart until the time it returns (fig. 21.12a), but there are exceptions, notably portal systems and anastomoses.

A **portal system** (fig. 21.12b) is a route in which blood flows through two capillary beds—one after the other—before returning to the heart. For example, in the *hepatic portal system,* the blood picks up nutrients from a capillary bed in the small intestine, then flows through a series of veins to the liver, where there is a second capillary bed (the liver sinusoids in fig. 21.7). The blood unloads some nutrients here, picks up substances produced by the liver cells, and then flows to the heart. Other portal systems occur in the kidneys (chapter 25) and connecting the hypothalamus to the anterior pituitary gland (chapter 18).

An **anastomosis** is a point where two veins or arteries merge without intervening capillaries. In an **arteriovenous anastomosis (shunt),** blood flows from an artery directly into a vein (fig. 21.12c). Shunts occur in the fingers, palms, toes, and ears, where they reduce heat loss in cold weather by allowing warm blood to bypass these exposed surfaces. Unfortunately, this makes these blood-deprived areas more susceptible to frostbite. In an **arterial anastomosis,** two arteries merge, providing *collateral* (alternative) routes of blood supply to a tissue (fig. 21.12e). Those of the coronary circulation were mentioned in chapter 20 (page 551). They are also common around joints where movement may temporarily compress an artery and obstruct one pathway. **Venous anastomoses,** where one vein empties directly into another, are the most common. They provide several alternative

DEEPER INSIGHT 21.2

Varicose Veins

In people who stand for long periods, such as barbers and cashiers, blood tends to pool in the lower limbs and stretch the veins. This is especially true of superficial veins, which are not surrounded by supportive tissue. Stretching pulls the cusps of the venous valves farther apart until they become incapable of sealing the vessel and preventing the backflow of blood. As the veins become further distended, their walls grow weak, and they develop into *varicose veins* with irregular dilations and twisted pathways. Obesity and pregnancy also promote development of varicose veins by putting pressure on large veins of the pelvic region and obstructing drainage from the limbs. Varicose veins sometimes develop because of hereditary weakness of the valves. With less drainage of blood, tissues of the leg and foot may become edematous and painful. *Hemorrhoids* are varicose veins of the anal canal.



Figure 21.12 Variations in Circulatory Pathways.
- *After studying tables 21.1 through 21.11, identify specific sites of three arterial anastomoses and three venous anastomoses.*

routes of drainage from an organ, so blockage of a vein is rarely as life-threatening as blockage of an artery. Several arterial and venous anastomoses are described later in this chapter.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. Name the three tunics of a typical blood vessel, and explain how they differ from each other.
2. Contrast the tunica media of a conducting artery, arteriole, and venule, and explain how the histological differences are related to the functional differences between these vessels.
3. Describe the differences between a continuous capillary, a fenestrated capillary, and a sinusoid.
4. Describe the differences between a medium vein and a medium (distributing or muscular) artery. State the functional reasons for these differences.
5. Contrast an anastomosis and a portal system with the more typical pathway of blood flow.
6. Describe three routes by which blood-borne substances can pass through a capillary wall into the tissue fluid.

21.2 The Pulmonary Circuit

Expected Learning Outcomes

When you have completed this section, you should be able to

a. trace the route of blood through the pulmonary circuit; and
b. explain the anatomical and functional differences between the pulmonary and systemic blood supplies to the lungs.

The remainder of this chapter centers on the names and pathways of the principal arteries and veins. The pulmonary circuit is described here; the section after this concerns the systemic arteries and veins of the axial region (head, neck, thoracic, and abdominopelvic regions); and the section following that concerns the systemic arteries and veins of the appendicular region (the limbs).

The pulmonary circuit (fig. 21.13) is the only route in the body where the arteries carry oxygen-poor blood and the veins carry oxygen-rich blood; the opposite condition prevails in the systemic circuit. The purpose of the pulmonary circuit is primarily to exchange CO_2 for O_2. The lungs also receive a separate systemic blood supply by way of the *bronchial arteries* (see part I.1 in table 21.4).

The pulmonary circuit begins with the **pulmonary trunk,** a large vessel that ascends diagonally from the right ventricle and branches into the right and left **pulmonary arteries.** As it approaches the lung, the right pulmonary artery branches in two, and both branches enter the lung at a medial indentation called the *hilum* (see fig. 23.9, p. 640). The upper branch is the **superior lobar artery,** serving the superior lobe of the lung. The lower branch divides again within the lung to form the **middle lobar** and **inferior lobar arteries,** supplying the lower two lobes of that lung. The left pulmonary artery is much more variable. It gives off several superior lobar arteries to the superior lobe before entering the hilum, then enters the lung and gives off a variable number of inferior lobar arteries to the inferior lobe.

In both lungs, these arteries lead ultimately to small basketlike capillary beds that surround the pulmonary alveoli (air sacs). This is where the blood unloads CO_2 and picks up O_2. After leaving the alveolar capillaries, the pulmonary blood flows into venules and veins, ultimately leading to the main **pulmonary veins** that exit the lung at the hilum. The left atrium of the heart receives two pulmonary veins on each side (see fig. 20.3b, p. 542).

Before You Go On

Answer the following questions to test your understanding of the preceding section:

7. Trace the flow of an RBC from right ventricle to left atrium, naming the vessels along the way.
8. Each lung has two separate arterial supplies. Explain their functions.


Right pulmonary artery
Superior lobar artery
Middle lobar artery
Inferior lobar artery
Right ventricle
Left ventricle
(a)
Superior lobar arteries
Left pulmonary artery
Inferior lobar artery
Pulmonary trunk
Pulmonary vein (to left atrium)
Pulmonary artery (from right ventricle)
Alveolar sacs and alveoli
Alveolar capillaries
(b)

Figure 21.13 **The Pulmonary Circulation.** (a) Gross anatomy. (b) Microscopic anatomy of the blood vessels that supply the pulmonary alveoli. All alveoli are surrounded by a basketlike mesh of capillaries; to show the alveoli, this drawing omits the capillaries from some of them.

21.3 Systemic Vessels of the Axial Region

Expected Learning Outcomes

When you have completed this section, you should be able to

a. identify the principal systemic arteries and veins of the axial region; and
b. trace the flow of blood from the heart to any major organ of the axial region and back to the heart.

The systemic circuit (figs. 21.14 and 21.15) supplies oxygen and nutrients to all organs and removes their metabolic wastes. Part of it, the coronary circulation, was described in chapter 20.

This section surveys the remaining arteries and veins of the axial region—the head, neck, and trunk. Tables 21.1 through 21.7 trace the arterial outflow and venous return, region by region. They outline only the most common circulatory pathways; there is a great deal of anatomical variation in the circulatory system from one person to another.

The names of the blood vessels often describe their location by indicating the body region traversed (as in *axillary artery* and *brachial vein*), an adjacent bone (as in *temporal artery* and *ulnar vein*), or the organ supplied or drained by the vessel (as in *hepatic artery* and *renal vein*). In many cases, an artery and adjacent vein have similar names (*femoral artery* and *femoral vein,* for example).

As you trace blood flow in these tables, it is important to refer frequently to the illustrations. Verbal descriptions alone may often seem obscure if you do not make full use of the accompanying explanatory illustrations.


Superficial temporal a.
Facial a.
External carotid a.
Internal carotid a.
Common carotid a.
Brachiocephalic trunk
Subclavian a.
Aortic arch
Diaphragm
Common hepatic a.
Splenic a.
Renal aa.
Superior mesenteric a.
Gonadal a.
Inferior mesenteric a.
Common iliac a.
Internal iliac a.
External iliac a.
Vertebral a.
Subclavian a.
Axillary a.
Internal thoracic a.
Subscapular a.
Deep brachial a.
Brachial a.
Radial collateral a.
Superior ulnar collateral a.
Aorta
Radial a.
Ulnar a.
Interosseous aa.
Palmar arches
Deep femoral a.
Femoral a.
Popliteal a.
Anterior tibial a.
Posterior tibial a.
Fibular a.
Dorsal pedal a.

Figure 21.14 **The Major Systemic Arteries (Anterior View).** Different arteries are illustrated on the left than on the right for clarity, but nearly all of those shown occur on both sides. (a. = artery; aa. = arteries)


External jugular v.
Internal jugular v.
Superior vena cava
Hepatic v.
Inferior vena cava
Renal v.
Brachial vv.
Gonadal vv.
Radial vv.
Ulnar vv.
Venous palmar arches
Brachiocephalic v.
Subclavian v.
Axillary v.
Diaphragm
Kidney
Cephalic v.
Basilic v.
Median cubital v.
Common iliac v.
Internal iliac v.
External iliac v.
Median antebrachial v.
Dorsal venous network
Deep femoral v.
Femoral v.
Popliteal v.
Anterior tibial vv.
Small saphenous v.
Great saphenous v.
Dorsal venous arch
Femoral v.
Posterior tibial vv.
Fibular vv.
Plantar venous arch

Figure 21.15 **The Major Systemic Veins (Anterior View).** Different veins are illustrated on the left than on the right for clarity, but nearly all of those shown occur on both sides. (v. = vein; vv. = veins)

TABLE 21.1 The Aorta and Its Major Branches

All systemic arteries arise from the aorta, which has three principal regions (fig. 21.16):

1. The **ascending aorta** rises for about 5 cm above the left ventricle. Its only branches are the coronary arteries, which arise behind two cusps of the aortic valve. They are the origins of the coronary circulation described in chapter 20.
2. The **aortic arch** curves to the left like an inverted U superior to the heart. It gives off three major arteries in this order: the **brachiocephalic**[5] (BRAY-kee-oh-seh-FAL-ic) **trunk, left common carotid** (cah-ROT-id) **artery,** and **left subclavian**[6] (sub-CLAY-vee-un) **artery.** These are further traced in tables 21.2 and 21.8.
3. The **descending aorta** passes downward posterior to the heart, at first to the left of the vertebral column and then anterior to it, through the thoracic and abdominal cavities. It is called the *thoracic aorta* above the diaphragm and the *abdominal aorta* below it. It ends in the lower abdominal cavity by forking into the *right* and *left common iliac arteries* (see table 21.6, part IV).



Figure 21.16 **The Thoracic Aorta.** (L. = left; R. = right; a. = artery)

AP|R

TABLE 21.2 Arteries of the Head and Neck

I. Origins of the Head–Neck Arteries

The head and neck receive blood from four pairs of arteries (fig. 21.17):

1. The **common carotid arteries.** Shortly after leaving the aortic arch, the brachiocephalic trunk divides into the *right subclavian artery* (further traced in table 21.4) and **right common carotid artery.** A little farther along the aortic arch, the **left common carotid artery** arises independently. The common carotids pass up the anterolateral region of the neck, alongside the trachea (see part II of this table).
2. The **vertebral arteries.** These arise from the right and left subclavian arteries and travel up the neck through the transverse foramina of vertebrae C1 through C6. They enter the cranial cavity through the foramen magnum (see part III of this table).
3. The **thyrocervical**[7] **trunks.** These tiny arteries arise from the subclavian arteries lateral to the vertebral arteries; they supply the thyroid gland and some scapular muscles.
4. The **costocervical**[8] **trunks.** These arteries arise from the subclavian arteries a little farther laterally. They supply the deep neck muscles and some of the intercostal muscles of the superior rib cage.

---

[5] *brachio* = arm; *cephal* = head
[6] *sub* = below; *clavi* = clavicle, collarbone
[7] *thyro* = thyroid gland; *cerv* = neck
[8] *costo* = rib

TABLE 21.2 Arteries of the Head and Neck (continued)


Superficial temporal a.
Posterior auricular a.
Occipital a.
Supraorbital a.
Ophthalmic a.
Maxillary a.
Internal carotid a.
External carotid a.
Carotid sinus
Vertebral a.
Facial a.
Lingual a.
Superior thyroid a.
Thyroid gland
Thyrocervical trunk
Costocervical trunk
Axillary a.
Common carotid a.
Subclavian a.
Brachiocephalic trunk
Anterior communicating a.
Anterior cerebral a.
Cerebral arterial circle
Ophthalmic a.
Middle cerebral a.
Internal cartoid aa.
Posterior communicating a.
Posterior cerebral a.
Basilar a.
Cerebellar aa.
Superficial temporal a.
Posterior auricular a.
Maxillary a.
Vertebral aa.
Occipital a.
Internal carotid aa.
Facial a.
Lingual a.
External carotid aa.
Superior thyroid a.
Common carotid aa.
Thyrocervical trunk
R. subclavian a.
Costocervical trunk
Brachiocephalic trunk
L. subclavian a.
Aortic arch

(a) Lateral view **(b) Anterior view, blood-flow schematic**

Figure 21.17 **Superficial (Extracranial) Arteries of the Head and Neck.** The upper part of the schematic (b) depicts the cerebral circulation in figure 21.18. (a. = artery; aa. = arteries) APR

II. Continuation of the Common Carotid Arteries

The common carotid arteries have the most extensive distribution of all the head–neck arteries. Near the laryngeal prominence ("Adam's apple"), each common carotid branches into an *external* and *internal carotid artery.*

1. The **external carotid artery** ascends the side of the head external to the cranium and supplies most external head structures except the orbits. It gives rise to the following arteries in ascending order:
   - a. the **superior thyroid artery** to the thyroid gland and larynx;
   - b. the **lingual artery** to the tongue;
   - c. the **facial artery** to the skin and muscles of the face;
   - d. the **occipital artery** to the posterior scalp;
   - e. the **maxillary artery** to the teeth, maxilla, oral cavity, and external ear; and
   - f. the **superficial temporal artery** to the chewing muscles, nasal cavity, lateral aspect of the face, most of the scalp, and the dura mater.
2. The **internal carotid artery** passes medial to the angle of the mandible and enters the cranial cavity through the carotid canal of the temporal bone. It supplies the orbits and about 80% of the cerebrum. Compressing the internal carotids near the mandible can therefore cause loss of consciousness. After entering the cranial cavity, each internal carotid gives rise to the following branches:
   - a. the **ophthalmic artery** to the orbit, nose, and forehead;
   - b. the **anterior cerebral artery** to the medial aspect of the cerebral hemisphere (see part IV of this table); and
   - c. the **middle cerebral artery,** which travels in the lateral sulcus of the cerebrum, supplies the insula, and then issues numerous branches to the lateral region of the frontal, temporal, and parietal lobes of the brain.

TABLE 21.2 Arteries of the Head and Neck (continued)

III. Continuation of the Vertebral Arteries

The vertebral arteries give rise to small branches that supply the spinal cord and its meninges, the cervical vertebrae, and deep muscles of the neck. They then enter the foramen magnum, supply the cranial bones and meninges, and converge to form a single **basilar artery** along the anterior aspect of the brainstem. Branches of the basilar artery supply the cerebellum, pons, and inner ear. At the pons–midbrain junction, the basilar artery divides and flows into the *cerebral arterial circle,* described next.

IV. The Cerebral Arterial Circle

Blood supply to the brain is so critical that it is furnished by several arterial anastomoses, especially an array of arteries called the **cerebral arterial circle (circle of Willis[9]),** which surrounds the pituitary gland and optic chiasm (fig. 21.18). The circle receives blood from the internal carotid and basilar arteries. Most people lack one or more of its components; only 20% have a complete arterial circle. Knowledge of the distribution of the arteries arising from the circle is crucial for understanding the effects of blood clots, aneurysms, and strokes on brain function. The anterior and posterior cerebral arteries described here and the middle cerebral artery described in part II provide the most significant blood supplies to the cerebrum. Refer to chapter 15 for reminders of the relevant brain anatomy.

1. Two **posterior cerebral arteries** arise from the basilar artery and sweep posteriorly to the rear of the brain, serving the inferior and medial regions of the temporal and occipital lobes as well as the midbrain and thalamus.
2. Two **anterior cerebral arteries** arise from the internal carotids, travel anteriorly, and then arch posteriorly over the corpus callosum as far as the posterior limit of the parietal lobe. They give off extensive branches to the frontal and parietal lobes.
3. The single **anterior communicating artery** is a short anastomosis between the right and left anterior cerebral arteries.
4. The two **posterior communicating arteries** are small anastomoses between the posterior cerebral and internal carotid arteries.


Cerebral arterial circle:
Anterior communicating a.
Anterior cerebral a.
Posterior communicating a.
Posterior cerebral a.
Basilar a.
Vertebral a.
Spinal aa.
Internal carotid a.
Middle cerebral a.
Cerebellar aa.:
Superior
Anterior inferior
Posterior inferior
Caudal
Rostral
Posterior cerebral a.
Anterior cerebral a.

(a) Inferior view

(b) Median section

Figure 21.18 **Cerebral Circulation.** (a) Inferior view of the brain showing the blood supply to the brainstem, cerebellum, and cerebral arterial circle. (b) Median section of the brain showing the more distal branches of the anterior and posterior cerebral arteries. Branches of the middle cerebral artery are distributed over the lateral surface of the cerebrum (not illustrated). AP|R

---

[9] Thomas Willis (1621–75), English anatomist

TABLE 21.3 Veins of the Head and Neck

The head and neck are drained mainly by three pairs of veins—the *internal jugular, external jugular,* and *vertebral veins.* We will trace these from their origins to the *subclavian veins.*

I. Dural Venous Sinuses

After blood circulates through the brain, it collects in large thin-walled veins called **dural venous sinuses**—blood-filled spaces between the layers of the dura mater (fig. 21.19a, b). A reminder of the structure of the dura mater will be helpful in understanding these sinuses. This tough membrane between the brain and cranial bone has a periosteal layer against the bone and a meningeal layer against the brain. In a few places, a space exists between these layers to accommodate a blood-collecting sinus. Between the two cerebral hemispheres is a vertical, sickle-shaped wall of dura called the *falx cerebri,* which contains two of the sinuses. There are about 13 dural venous sinuses in all; we survey only the few most prominent ones here.

1. The **superior sagittal sinus** is contained in the superior margin of the falx cerebri and overlies the longitudinal fissure of the brain (fig. 21.19a; see also figs. 15.3 and 15.5, pp. 402 and 405). It begins anteriorly near the crista galli of the skull and extends posteriorly to the very rear of the head, ending at the level of the posterior occipital protuberance of the skull. Here it bends, usually to the right, and drains into a *transverse sinus.*
2. The **inferior sagittal sinus** is contained in the inferior margin of the falx cerebri and arches over the corpus callosum, deep in the longitudinal fissure. Posteriorly, it joins the *great cerebral vein,* and their union forms the **straight sinus,** which continues to the rear of the head (see fig. 15.5). There, the superior sagittal and straight sinuses meet in a space called the **confluence of the sinuses.**
3. Right and left **transverse sinuses** lead away from the confluence and encircle the inside of the occipital bone, leading toward the ears (fig. 21.19b); their path is marked by grooves on the inner surface of the occipital bone (see fig. 7.5b, p. 157). The right transverse sinus receives blood mainly from the superior sagittal sinus, and the left one drains mainly the straight sinus. Laterally, each transverse sinus makes an S-shaped bend, the **sigmoid sinus,** then exits the cranium through the jugular foramen. From here, the blood flows down the internal jugular vein (see part II.1 of this table).
4. The **cavernous sinuses** are honeycombs of blood-filled spaces on each side of the body of the sphenoid bone (fig. 21.19b). They receive blood from the *superior ophthalmic vein* of the orbit and the *superficial middle cerebral vein* of the brain, among other sources. They drain through several outlets including the transverse sinus, internal jugular vein, and facial vein. They are clinically important because infections can pass from the face and other superficial sites into the cranial cavity by this route. Also, inflammation of a cavernous sinus can injure important structures that pass through it, including the internal carotid artery and cranial nerves III to VI.

II. Major Veins of the Neck

Blood flows down the neck mainly through three veins on each side, all of which empty into the subclavian vein (fig. 21.19c).

1. The **internal jugular**[10] (JUG-you-lur) **vein** courses down the neck deep to the sternocleidomastoid muscle. It receives most of the blood from the brain, picks up blood from the **facial vein, superficial temporal vein,** and **superior thyroid vein** along the way, passes behind the clavicle, and empties into the subclavian vein (which is further traced in table 21.5).
2. The **external jugular vein** courses down the side of the neck superficial to the sternocleidomastoid muscle and also empties into the subclavian vein. It drains tributaries from the parotid salivary gland, facial muscles, scalp, and other superficial structures. Some of this blood also follows venous anastomoses to the internal jugular vein.
3. The **vertebral vein** travels with the vertebral artery in the transverse foramina of the cervical vertebrae. Although the companion artery leads to the brain, the vertebral vein does not come from there. It drains the cervical vertebrae, spinal cord, and some of the small deep muscles of the neck, and empties into the subclavian vein.

Table 21.5 traces this blood flow the rest of the way to the heart.

DEEPER INSIGHT 21.3

Air Embolism

Injury to the dural sinuses or jugular veins presents less danger from loss of blood than from air sucked into the circulatory system. The presence of air in the bloodstream is called air embolism. This is an important concern to neurosurgeons, who sometimes operate with the patient in a sitting position. If a dural sinus is punctured, air can be sucked into the sinus and accumulate in the heart chambers, which blocks cardiac output and causes sudden death. Smaller air bubbles in the systemic circulation can cut off blood flow to the brain, lungs, myocardium, and other vital tissues.

---

[10] *jugul* = neck, throat

TABLE 21.3 **Veins of the Head and Neck (continued)**


Corpus callosum
Great cerebral v.
Straight sinus
Confluence of sinuses
Transverse sinus
Sigmoid sinus
Internal jugular v.
Superior sagittal sinus
Inferior sagittal sinus
Superior ophthalmic v.
Cavernous sinus
Sigmoid sinus
Transverse sinus
Confluence of sinuses
Superficial middle cerebral v.
To internal jugular v.
Straight sinus

(a) Dural venous sinuses, medial view **(b) Dural venous sinuses, inferior view**


Superior ophthalmic v.
Superficial temporal v.
Occipital v.
Vertebral v.
Facial v.
External jugular v.
Superior thyroid v.
Internal jugular v.
Thyroid gland
Subclavian v.
Axillary v.
Brachiocephalic v.

(c) Superficial veins of the head and neck

Figure 21.19 **Veins of the Head and Neck.** (a) Dural venous sinuses seen in a median section of the cerebrum. (b) Dural venous sinuses seen in an inferior view of the cerebrum. (c) Superficial (extracranial) veins of the head and neck. APR

TABLE 21.4 Arteries of the Thorax

The thorax is supplied by several arteries arising directly from the aorta (parts I and II of this table) and from the subclavian and axillary arteries (part III). The thoracic aorta begins distal to the aortic arch and ends at the **aortic hiatus** (hy-AY-tus), a passage through the diaphragm. Along the way, it sends off numerous small branches to the thoracic viscera and the body wall (fig. 21.20).

I. Visceral Branches of the Thoracic Aorta

These supply the viscera of the thoracic cavity:

1. **Bronchial arteries.** Although variable in number and arrangement, there are usually two of these on the left and one on the right. The right bronchial artery usually arises from one of the left bronchial arteries or from a *posterior intercostal artery* (see part II.1). The bronchial arteries supply the bronchi, bronchioles, and larger blood vessels of the lungs, the visceral pleura, the pericardium, and the esophagus.
2. **Esophageal arteries.** Four or five unpaired esophageal arteries arise from the anterior surface of the aorta and supply the esophagus.
3. **Mediastinal arteries.** Many small mediastinal arteries (not illustrated) supply structures of the posterior mediastinum.


Vertebral a.
Thyrocervical trunk
Costocervical trunk
Thoracoacromial trunk
Subscapular a.
Lateral thoracic a.
Anterior intercostal aa.
Internal thoracic a.
Common carotid aa.
Brachiocephalic trunk
L. subclavian a.
Aortic arch
Pericardiophrenic a.
Bronchial aa.
Descending aorta
Posterior intercostal aa.
Subcostal a.
Esophageal aa.

(a) Major arteries


Vertebral a.
Thyrocervical trunk
R. subclavian a.
Costocervical trunk
Internal thoracic a.
Subscapular a.
Lateral thoracic a.
Thoracoacromial trunk
Anterior intercostal aa.
R. common carotid a.
L. common carotid a.
L. subclavian a.
Pericardiophrenic a.
Bronchial aa.
Posterior intercostal aa.
Esophageal aa.
Subcostal a.

Figure 21.20 Arteries of the Thorax. APR

(b) Blood-flow schematic

TABLE 21.4 Arteries of the Thorax (continued)

II. Parietal Branches of the Thoracic Aorta

The following branches supply chiefly the muscles, bones, and skin of the chest wall; only the first are illustrated:

1. **Posterior intercostal arteries.** Nine pairs of these arise from the posterior surface of the aorta and course around the posterior side of the rib cage between ribs 3 through 12, then anastomose with the *anterior intercostal arteries* (see part III.1 in this table). They supply the intercostal, pectoralis, serratus anterior, and some abdominal muscles, as well as the vertebrae, spinal cord, meninges, breasts, skin, and subcutaneous tissue. They are enlarged in lactating women.
2. **Subcostal arteries.** A pair of these arise from the aorta inferior to the twelfth rib. They supply the posterior intercostal tissues, vertebrae, spinal cord, and deep muscles of the back.
3. **Superior phrenic**[11] (FREN-ic) **arteries** (not illustrated). These arteries, variable in number, arise at the aortic hiatus and supply the superior and posterior regions of the diaphragm.

III. Branches of the Subclavian and Axillary Arteries

The thoracic wall is also supplied by the following arteries, which arise in the shoulder region—the first one from the subclavian artery and the other three from its continuation, the axillary artery:

1. The **internal thoracic (mammary) artery** supplies the breast and anterior thoracic wall and issues the following branches:
   a. The **pericardiophrenic artery** supplies the pericardium and diaphragm.
   b. The **anterior intercostal arteries** arise from the thoracic artery as it descends alongside the sternum. They travel between the ribs, supply the ribs and intercostal muscles, and anastomose with the posterior intercostal arteries. Each of these sends one branch along the lower margin of the rib above and another branch along the upper margin of the rib below.
2. The **thoracoacromial**[12] (THOR-uh-co-uh-CRO-me-ul) **trunk** provides branches to the superior shoulder and pectoral regions.
3. The **lateral thoracic artery** supplies the pectoral, serratus anterior, and subscapularis muscles. It also issues branches to the breast and is larger in females than in males.
4. The **subscapular artery** is the largest branch of the axillary artery. It supplies the scapula and the latissimus dorsi, serratus anterior, teres major, deltoid, triceps brachii, and intercostal muscles.

TABLE 21.5 Veins of the Thorax

I. Tributaries of the Superior Vena Cava

The most prominent veins of the upper thorax are as follows. They carry blood from the shoulder region to the heart (fig. 21.21).

1. The **subclavian vein** drains the upper limb (see table 21.9). It begins at the lateral margin of the first rib and travels posterior to the clavicle. It receives the external jugular and vertebral veins, then ends where it receives the internal jugular vein.
2. The **brachiocephalic vein** is formed by union of the subclavian and internal jugular veins. The right brachiocephalic is very short, about 2.5 cm, and the left is about 6 cm long. They receive tributaries from the vertebrae, thyroid gland, and upper thoracic wall and breast, then converge to form the next vein.
3. The **superior vena cava** is formed by the union of the right and left brachiocephalic veins. It travels inferiorly for about 7 cm and empties into the right atrium of the heart. Its main tributary is the *azygos vein*. It drains all structures superior to the diaphragm except the pulmonary circuit and coronary circulation. It also receives drainage from the abdominal cavity by way of the azygos system, described next.

II. The Azygos System

The principal venous drainage of the thoracic organs is by way of the *azygos* (AZ-ih-goss) *system* (fig. 21.21). The most prominent vein of this system is the **azygos**[13] **vein,** which ascends the right side of the posterior thoracic wall and is named for the lack of a mate on the left. It receives the following tributaries, then empties into the superior vena cava at the level of vertebra T4.

1. The right **ascending lumbar vein** drains the right abdominal wall, then penetrates the diaphragm and enters the thoracic cavity. The azygos vein begins where the ascending lumbar vein meets the right **subcostal vein** beneath rib 12.
2. The right **posterior intercostal veins** drain the intercostal spaces. The first (superior) one empties into the right brachiocephalic vein; intercostals 2 and 3 join to form a *right superior intercostal vein* before emptying into the azygos; and intercostals 4 through 11 each enter the azygos vein separately.
3. The right **esophageal, mediastinal, pericardial,** and **bronchial veins** (not illustrated) drain their respective organs into the azygos.
4. The **hemiazygos**[14] **vein** ascends the posterior thoracic wall on the left. It begins where the left ascending lumbar vein, having just penetrated the diaphragm, joins the subcostal vein below rib 12. The hemiazygos then receives the lower three posterior intercostal veins, esophageal veins, and mediastinal veins. At the level of vertebra T9, it crosses to the right and empties into the azygos.
5. The **accessory hemiazygos vein** descends the posterior thoracic wall on the left. It receives drainage from posterior intercostal veins 4 through 8 and sometimes the left bronchial veins. It crosses to the right at the level of vertebra T8 and empties into the azygos vein.

The left posterior intercostal veins 1 through 3 are the only ones on this side that do not ultimately drain into the azygos vein. The first one usually drains directly into the left brachiocephalic vein. The second and third unite to form the *left superior intercostal vein,* which empties into the left brachiocephalic vein.

---

[11] *phren* = diaphragm
[12] *thoraco* = chest; *acr* = tip; *om* = shoulder
[13] unpaired; from *a* = without; *zygo* = union, mate
[14] *hemi* = half

TABLE 21.5 **Veins of the Thorax (continued)**


Posterior intercostal v.
Superior intercostal v.
Azygos v.
R. ascending lumbar v.
Lumbar vv.
Internal jugular v.
Brachiocephalic v.
Subclavian v.
Superior intercostal v.
Superior vena cava
T4
Accessory hemiazygos v.
Posterior intercostal vv.
T8
T9
Hemiazygos v.
T12
Subcostal v.
Rib 12
L. ascending lumbar v.
(a)
Brachiocephalic vv.
R. superior intercostal v.
R. posterior intercostal vv.
Azygos v.
R. subcostal v.
Diaphragm
R. lumbar vv.
R. ascending lumbar v.
R. iliolumbar v.
R. common iliac v.
1
2
3
4
5
6
7
8
9
10
11
L. superior intercostal v.
Superior vena cava
L. posterior intercostal vv.
Accessory hemiazygos v.
Hemiazygos v.
L. subcostal v.
Inferior vena cava
Renal vv.
L. lumbar vv.
L. ascending lumbar v.
L. iliolumbar v.
L. common iliac v.
(b)

Figure 21.21 **Venous Drainage of the Posterior Wall of the Thorax and Abdomen.** (a) The azygos system of the thoracic wall. This system provides venous drainage from the wall and viscera of the thorax, but the visceral tributaries are not illustrated. (b) Blood-flow schematic of thoracic and abdominal drainage. The components above the diaphragm constitute the azygos system. There is a great deal of individual variation in this pattern. APR

TABLE 21.6 Arteries of the Abdomen and Pelvic Region

After passing through the aortic hiatus, the aorta descends through the abdominal cavity and ends at the level of vertebra L4, where it branches into right and left *common iliac arteries.* The abdominal aorta is retroperitoneal.

I. Major Branches of the Abdominal Aorta

The abdominal aorta gives off arteries in the order listed here (fig. 21.22). Those indicated in the plural are paired right and left, and those indicated in the singular are solitary median arteries.

1. The **inferior phrenic arteries** supply the inferior surface of the diaphragm. They may arise from the aorta, celiac trunk, or renal artery. Each issues two or three small **superior suprarenal arteries** to the ipsilateral adrenal (suprarenal) gland.
2. The **celiac**[15] (SEE-lee-ac) **trunk** supplies the upper abdominal viscera (see part II of this table).
3. The **superior mesenteric artery** supplies the intestines (see part III).
4. The **middle suprarenal arteries** arise laterally from the aorta, usually at the same level as the superior mesenteric artery; they supply the adrenal glands.
5. The **renal arteries** supply the kidneys and issue a small **inferior suprarenal artery** to each adrenal gland.
6. The gonadal arteries (**ovarian arteries** in the female and **testicular arteries** in the male) are long, slender arteries that arise from the midabdominal aorta and descend along the posterior body wall to the female pelvic cavity or male scrotum. The gonads begin their embryonic development near the kidneys, and the gonadal arteries are then quite short. As the gonads descend to the pelvic cavity, these arteries grow and acquire their peculiar length and course.
7. The **inferior mesenteric artery** supplies the distal end of the large intestine (see part III).
8. The **lumbar arteries** arise from the lower aorta in four pairs. They supply the posterior abdominal wall (muscles, joints, and skin) and the spinal cord and other tissues in the vertebral canal.
9. The **median sacral artery,** a tiny medial artery at the inferior end of the aorta, supplies the sacrum and coccyx.
10. The **common iliac arteries** arise as the aorta forks at its inferior end. They are further traced in part IV of this table.



Figure 21.22 **The Abdominal Aorta and Its Major Branches.**

II. Branches of the Celiac Trunk

The celiac circulation to the upper abdominal viscera is perhaps the most complex route off the abdominal aorta. Because it has numerous anastomoses, the bloodstream does not follow a simple linear path but divides and rejoins itself at several points (fig. 21.23). As you study the following description, locate these branches in the figure and identify the points of anastomosis.

The short, stubby celiac trunk, barely more than 1 cm long, is a median branch of the aorta just below the diaphragm. It immediately gives rise to three branches—the *common hepatic, left gastric,* and *splenic arteries.*

1. The **common hepatic artery** passes to the right and issues two main branches—the gastroduodenal artery and the hepatic artery proper.
    a. The **gastroduodenal artery** gives off the **right gastro-omental (gastroepiploic**[16]**) artery** to the stomach. It then continues as the **superior pancreaticoduodenal** (PAN-cree-AT-ih-co-dew-ODD-eh-nul) **artery,** which splits into two branches that pass around the anterior and posterior sides of the head of the pancreas. These anastomose with the two branches of the *inferior pancreaticoduodenal artery,* discussed in part III.1.
    b. The **hepatic artery proper** ascends toward the liver. It gives off the **right gastric artery,** then branches into **right** and **left hepatic arteries.** The right hepatic artery issues a **cystic artery** to the gallbladder, then the two hepatic arteries enter the liver from below.
2. The **left gastric artery** supplies the stomach and lower esophagus, arcs around the *lesser curvature* (superomedial margin) of the stomach, and anastomoses with the right gastric artery (fig. 21.23b). Thus, the right and left gastric arteries approach from opposite directions and supply this margin of the stomach. The left gastric also has branches to the lower esophagus, and the right gastric also supplies the duodenum.
3. The **splenic artery** supplies blood to the spleen, but gives off the following branches on the way there:
    a. Several small **pancreatic arteries** supply the pancreas.
    b. The **left gastro-omental (gastroepiploic) artery** arcs around the *greater curvature* (inferolateral margin) of the stomach and anastomoses with the right gastro-omental artery. These two arteries stand off about 1 cm from the stomach itself and travel through the superior margin of the *greater omentum,* a fatty membrane suspended from the greater curvature (see figs. A.4, p. 334, and 24.3, p. 657). They furnish blood to both the stomach and omentum.
    c. The **short gastric arteries** supply the upper portion (fundus) of the stomach.

---

[15] *celi* = belly, abdomen
[16] *gastro* = stomach; *epi* = upon, above; *ploic* = pertaining to the greater omentum


Gallbladder
Liver
Spleen
Short gastric aa.
Cystic a.
Hepatic aa.
Aorta
Celiac trunk
Hepatic a. proper
R. gastric a.
L. gastric a.
Gastroduodenal a.
Splenic a.
Superior pancreaticoduodenal a.
L. gastro-omental a.
Pancreatic aa.
Pancreas
Common hepatic a.
Inferior pancreaticoduodenal a.
R. gastro-omental a.
Superior mesenteric a.
Duodenum
Left gastric a.
Short gastric aa.
Splenic a.
Right gastric a.
Gastroduodenal a.
Left gastro-omental a.
Right gastro-omental a.
Hepatic aa.
Liver
Aorta
Cystic a.
Celiac trunk
Splenic a.
Short gastric aa.
Hepatic a. proper
Common hepatic a.
Gastroduodenal a.
Spleen
R. gastric a.
Stomach
L. gastro-omental a.
R. gastro-omental a.
Superior pancreaticoduodenal a.
L. gastric a.
Pancreas
Superior mesenteric a.
Inferior pancreaticoduodenal a.
Intestines

(a) Branches of the celiac trunk

(b) Celiac circulation to the stomach

(c) Blood-flow schematic

Figure 21.23 **Branches of the Celiac Trunk.** (a) Anatomy of the celiac system with the stomach removed to expose the more posterior arteries. (b) Arterial supply to the stomach. (c) Blood-flow schematic of the celiac system. APR

TABLE 21.6 Arteries of the Abdomen and Pelvic Region (continued)

III. Mesenteric Circulation

The mesentery is a translucent sheet that suspends the intestines and other abdominal viscera from the posterior body wall (see figs. 1.15, p. 19, and 24.3, p. 657). It contains numerous arteries, veins, and lymphatic vessels that supply and drain the intestines. The arterial supply arises from the *superior* and *inferior mesenteric arteries;* numerous anastomoses between these ensure adequate collateral circulation to the intestines even if one route is temporarily obstructed.

The **superior mesenteric artery** (fig. 21.24a) is the most significant intestinal blood supply, serving nearly all of the small intestine and the proximal half of the large intestine. It arises medially from the upper abdominal aorta and gives off the following branches:

1. The **inferior pancreaticoduodenal artery,** already mentioned, branches to pass around the anterior and superior sides of the pancreas and anastomose with the two branches of the superior pancreaticoduodenal artery.
2. Twelve to 15 **jejunal** and **ileal arteries** form a fanlike array that supplies nearly all of the small intestine (portions called the jejunum and ileum).
3. The **ileocolic** (ILL-ee-oh-CO-lic) **artery** supplies the ileum, appendix, and parts of the large intestine (cecum and ascending colon).
4. The **right colic artery** also supplies the ascending colon.
5. The **middle colic artery** supplies most of the transverse colon.

The **inferior mesenteric artery** arises from the lower abdominal aorta and serves the distal part of the large intestine (fig. 21.24b):

1. The **left colic artery** supplies the transverse and descending colon.
2. The **sigmoid arteries** supply the descending and sigmoid colon.
3. The **superior rectal artery** supplies the rectum.


Inferior pancreaticoduodenal a.
Transverse colon
Aorta
Jejunum
Middle colic a.
Superior mesenteric a.
R. colic a.
Ileocolic a.
Jejunal aa.
Ascending colon
Ileal aa.
Cecum
Appendix
Ileum
Transverse colon
Descending colon
Aorta
Inferior mesenteric a.
Left colic a.
Sigmoid aa.
Superior rectal a.
Sigmoid colon
Rectum

(a) Distribution of superior mesenteric artery **(b) Distribution of inferior mesenteric artery**

Figure 21.24 The Mesenteric Arteries. APR

TABLE 21.6 Arteries of the Abdomen and Pelvic Region (continued)

IV. Arteries of the Pelvic Region

The two common iliac arteries arise by branching of the aorta, descend for another 5 cm, and then, at the level of the sacroiliac joint, each divides into an external and internal iliac artery. The external iliac supplies mainly the lower limb (see table 21.10). The **internal iliac artery** supplies mainly the pelvic wall and viscera. Its branches are shown only in schematic form in figure 21.30.

Shortly after its origin, the internal iliac divides into anterior and posterior trunks. The anterior trunk produces the following branches:

1. The **superior vesical**[17] **artery** supplies the urinary bladder and distal end of the ureter. It arises indirectly from the anterior trunk by way of a short *umbilical artery,* a remnant of the artery that supplies the fetal umbilical cord. The rest of the umbilical artery becomes a closed fibrous cord after birth.
2. In men, the **inferior vesical artery** supplies the bladder, ureter, prostate gland, and seminal vesicle. In women, the corresponding vessel is the **vaginal artery,** which supplies the vagina and part of the bladder and rectum.
3. The **middle rectal artery** supplies the rectum.
4. The **obturator artery** exits the pelvic cavity through the obturator foramen and supplies the adductor muscles of the medial thigh.
5. The **internal pudendal**[18] (pyu-DEN-dul) **artery** serves the perineum and erectile tissues of the penis and clitoris; it supplies the blood for vascular engorgement during sexual arousal.
6. In women, the **uterine artery** is the main blood supply to the uterus and supplies some blood to the vagina. It enlarges substantially in pregnancy. It passes up the uterine margin, then turns laterally at the uterine tube and anastomoses with the *ovarian artery,* thus supplying blood to the ovary as well (see part I.6 of table 21.6, and fig. 26.18, p. 722).
7. The **inferior gluteal artery** supplies the gluteal muscles and hip joint.

The posterior trunk produces the following branches:

1. The **iliolumbar artery** supplies the lumbar body wall and pelvic bones.
2. The **lateral sacral arteries** lead to tissues of the sacral canal, skin, and muscles posterior to the sacrum. There are usually two of these, superior and inferior.
3. The **superior gluteal artery** supplies the skin and muscles of the gluteal region and the muscle and bone tissues of the pelvic wall.

---

[17] *vesic* = bladder

[18] *pudend* = literally “shameful parts”; the external genitals

TABLE 21.7 Veins of the Abdomen and Pelvic Region

I. Tributaries of the Inferior Vena Cava

The **inferior vena cava (IVC)** is the body's largest blood vessel, having a diameter of about 3.5 cm. It forms by the union of the right and left common iliac veins at the level of vertebra L5 and drains many of the abdominal viscera as it ascends the posterior body wall. It is retroperitoneal and lies immediately to the right of the aorta. The IVC picks up blood from numerous tributaries in the following ascending order (fig. 21.25):

1. The **internal iliac veins** drain the gluteal muscles; the medial aspect of the thigh, the urinary bladder, rectum, prostate, and ductus deferens of the male; and the uterus and vagina of the female. They unite with the *external iliac veins,* which drain the lower limb and are described in table 21.11. Their union forms the **common iliac veins,** which then converge to form the IVC.
2. Four pairs of **lumbar veins** empty into the IVC, as well as into the ascending lumbar veins described in part II.
3. The gonadal veins (**ovarian veins** in the female and **testicular veins** in the male) drain the gonads. Like the gonadal arteries, and for the same reason (table 21.6, part I.6), these are long slender vessels that end far from their origins. The left gonadal vein empties into the left renal vein, whereas the right gonadal vein empties directly into the IVC.
4. The **renal veins** drain the kidneys into the IVC. The left renal vein also receives blood from the left gonadal and left suprarenal veins. It is up to three times as long as the right renal vein, since the IVC lies to the right of the median plane of the body.
5. The **suprarenal veins** drain the adrenal (suprarenal) glands. The right suprarenal empties directly into the IVC, and the left suprarenal empties into the left renal vein.
6. The **inferior phrenic veins** drain the inferior aspect of the diaphragm.
7. The **hepatic veins** drain the liver, extending a short distance from its superior surface to the IVC.

After receiving these inputs, the IVC penetrates the diaphragm and enters the right atrium of the heart from below. It does not receive any thoracic drainage.

II. Veins of the Abdominal Wall

A pair of **ascending lumbar veins** receives blood from the common iliac veins below and the aforementioned lumbar veins of the posterior body wall (see fig. 21.21b). The ascending lumbar veins give off anastomoses with the inferior vena cava beside them as they ascend to the diaphragm. The left ascending lumbar vein passes through the diaphragm via the aortic hiatus and continues as the hemiazygos vein above. The right ascending lumbar vein passes through the diaphragm to the right of the vertebral column and continues as the azygos vein. The further paths of the azygos and hemiazygos veins are described in table 21.5.



Figure 21.25 **The Inferior Vena Cava and Its Tributaries.** Compare the blood-flow schematic in figure 21.21b.

• *Why do the veins that drain the ovaries and testes terminate so far away from the gonads?* AP|R

TABLE 21.7 Veins of the Abdomen and Pelvic Region (continued)

III. The Hepatic Portal System

The **hepatic portal system** receives all of the blood draining from the abdominal digestive tract, as well as from the pancreas, gallbladder, and spleen (fig. 21.26). It is called a portal system because it connects capillaries of the intestines and other digestive organs to modified capillaries *(hepatic sinusoids)* of the liver; thus, the blood passes through two capillary beds in series before it returns to the heart. Intestinal blood is richly laden with nutrients for a few hours following a meal. The hepatic portal system gives the liver first claim to these nutrients before the blood is distributed to the rest of the body. It also allows the blood to be cleansed of bacteria and toxins picked up from the intestines, an important function of the liver. Its principal veins are as follows:

1. The **inferior mesenteric vein** receives blood from the rectum and distal part of the colon. It converges in a fanlike array in the mesentery and empties into the splenic vein.
2. The **superior mesenteric vein** receives blood from the entire small intestine, ascending colon, transverse colon, and stomach. It, too, exhibits a fanlike arrangement in the mesentery and then joins the splenic vein to form the hepatic portal vein.
3. The **splenic vein** drains the spleen and travels across the abdominal cavity toward the liver. Along the way, it picks up **pancreatic veins** from the pancreas, then the inferior mesenteric vein, then ends where it meets the superior mesenteric vein.
4. The **hepatic portal vein** is the continuation beyond the convergence of the splenic and superior mesenteric veins. It travels about 8 cm upward and to the right, receives the **cystic vein** from the gallbladder, then enters the inferior surface of the liver. In the liver, it ultimately leads to the innumerable microscopic hepatic sinusoids. Blood from the sinusoids empties into the hepatic veins described earlier, and they empty into the IVC. Circulation within the liver is described in more detail in chapter 24 (p. 676).
5. The left and right **gastric veins** form an arc along the lesser curvature of the stomach and empty into the hepatic portal vein.


Liver
Cystic v.
Hepatic portal v.
Gallbladder
Inferior vena cava
Colon
Ileum
Rectum
Hepatic vv.
Gastric vv.
Spleen
Splenic v.
R. gastro-omental v.
Inferior mesenteric v
Superior mesenteric v

(a) Tributaries of the hepatic portal system


Inferior vena cava
Liver
Gallbladder
Cystic v.
Hepatic portal v.
Superior mesenteric v.
R. gastro-omental v.
Hepatic v.
Hepatic sinusoids
L. gastric v.
R. gastric v.
Pancreatic vv.
Splenic v.
Spleen
Pancreas
L. gastro-omental v.
Inferior mesenteric v.

(b) Blood-flow schematic

Figure 21.26 The Hepatic Portal System.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

9. Concisely contrast the destinations of the external and internal carotid arteries.
10. Briefly state the organs or parts of organs that are supplied with blood by (a) the cerebral arterial circle, (b) the celiac trunk, (c) the superior mesenteric artery, and (d) the internal iliac artery.
11. If you were dissecting a cadaver, where would you look for the internal and external jugular veins? What muscle would help you distinguish one from the other?
12. Trace a blood cell from the left lumbar body wall to the superior vena cava, naming the vessels through which it would travel.
13. Explain the functional importance of having a hepatic portal system connect capillaries of the intestines to capillaries of the liver.

21.4 Systemic Vessels of the Appendicular Region

Expected Learning Outcomes

When you have completed this section, you should be able to

a. identify the principal systemic arteries and veins of the limbs; and
b. trace the flow of blood from the heart to any region of the upper or lower limb and back to the heart.

The principal vessels of the appendicular region are detailed in tables 21.8 through 21.11. While the appendicular arteries are usually deep and well protected, the veins occur in both deep and superficial groups; you may be able to see several of the superficial ones in your arms and hands. Deep veins run parallel to the arteries and often have similar names (*femoral artery* and *femoral vein,* for example). In several cases, the deep veins occur in pairs flanking the corresponding artery (such as the two *radial veins* traveling alongside the *radial artery*).

These blood vessels will be described in an order corresponding to the direction of blood flow. Thus, we will begin with the arteries in the shoulder and pelvic regions and progress to the hands and feet, whereas we will trace the veins beginning in the hands and feet and progressing toward the heart.

Venous pathways have more anastomoses than arterial pathways, so the route of flow is often not as clear. If all the anastomoses were illustrated, many of these venous pathways would look more like confusing networks than a clear route back to the heart. Therefore, most anastomoses—especially the highly variable and unnamed ones—are omitted from the figures to allow you to focus on the more general course of blood flow. The blood-flow schematics in several figures will also help to clarify these routes.

TABLE 21.8 Arteries of the Upper Limb

The upper limb is supplied by a prominent artery that changes name along its course from *subclavian* to *axillary* to *brachial,* then issues branches to the arm, forearm, and hand (fig. 21.27).

I. The Shoulder and Arm (Brachium)

1. The brachiocephalic trunk arises from the aortic arch and branches into the right common carotid artery and **left subclavian artery;** the **right subclavian artery** arises directly from the aortic arch. Each subclavian arches over the respective lung, rising as high as the base of the neck slightly superior to the clavicle. It then passes posterior to the clavicle, downward over the first rib, and ends in name only at the rib's lateral margin. In the shoulder, it gives off several small branches to the thoracic wall and viscera, described in table 21.4.

2. As the artery continues past the first rib, it is named the **axillary artery.** It continues through the axillary region, gives off small thoracic branches (see table 21.4), and ends, again in name only, at the neck of the humerus. Here, it gives off a pair of **circumflex humeral arteries,** which encircle the humerus, anastomose with each other laterally, and supply blood to the shoulder joint and deltoid muscle. Beyond this loop, the vessel is called the brachial artery.

3. The **brachial** (BRAY-kee-ul) **artery** continues down the medial and anterior sides of the humerus and ends just distal to the elbow, supplying the anterior flexor muscles of the brachium along the way. This artery is the most common site of blood pressure measurement, using an inflatable cuff that encircles the arm and compresses the artery.

4. The **deep brachial artery** arises from the proximal end of the brachial and supplies the humerus and triceps brachii muscle. About midway down the arm, it continues as the radial collateral artery.

5. The **radial collateral artery** descends in the lateral side of the arm and empties into the radial artery slightly distal to the elbow.

6. The **superior ulnar collateral artery** arises about midway along the brachial artery and descends in the medial side of the arm. It empties into the ulnar artery slightly distal to the elbow.

II. The Forearm, Wrist, and Hand

Just distal to the elbow, the brachial artery forks into the *radial* and *ulnar arteries.*

1. The **radial artery** descends the forearm laterally, alongside the radius, nourishing the lateral forearm muscles. The most common place to take a pulse is at the radial artery just proximal to the thumb.

2. The **ulnar artery** descends medially through the forearm, alongside the ulna, nourishing the medial forearm muscles.

TABLE 21.8 Arteries of the Upper Limb (continued)

3. The **interosseous**[19] **arteries** of the forearm lie between the radius and ulna. They begin with a short **common interosseous artery** branching from the upper end of the ulnar artery. The common interosseous quickly divides into anterior and posterior branches. The **anterior interosseous artery** travels down the anterior side of the interosseous membrane, nourishing the radius, ulna, and deep flexor muscles. It ends distally by passing through the interosseous membrane to join the posterior interosseous artery. The **posterior interosseous artery** descends along the posterior side of the interosseous membrane and nourishes mainly the superficial extensor muscles.
4. Two U-shaped **palmar arches** arise by anastomosis of the radial and ulnar arteries at the wrist. The **deep palmar arch** is fed mainly by the radial artery and the **superficial palmar arch** mainly by the ulnar artery. The arches issue arteries to the palmar region and fingers.

Figure 21.27 Arteries of the Upper Limb.
- *Why are arterial anastomoses especially common at joints such as the shoulder and elbow?* APR


Common carotid a.
Subclavian a.
Brachiocephalic trunk
Axillary a.
Circumflex humeral aa.
Brachial a.
Deep brachial a.
Superior ulnar collateral a.
Radial collateral a.
Interosseous aa.:
Common
Posterior
Anterior
Radial a.
Ulnar a.
Deep palmar arch
Superficial palmar arch
Lateral
Medial
Subclavian a.
Axillary a.
Circumflex humeral aa.
Brachial a.
Deep brachial a.
Superior ulnar collateral a.
Radial collateral a.
Radial a.
Ulnar a.
Interosseous aa.:
Common
Posterior
Anterior
Dorsal carpal arch
Deep palmar arch
Superficial palmar arch

(a) Major arteries

(b) Blood-flow schematic

---

[19] *inter* = between; *osse* = bones

TABLE 21.9 Veins of the Upper Limb

Both superficial and deep veins drain the upper limb, ultimately leading to axillary and subclavian veins that parallel the arteries of the same names (fig. 21.28). The superficial veins are often externally visible and are larger in diameter and carry more blood than the deep veins.

I. Superficial Veins

1. The **dorsal venous network** is a plexus of veins often visible through the skin on the back of the hand; it empties into the major superficial veins of the forearm, the cephalic and basilic.
2. The **cephalic**[20] (sef-AL-ic) **vein** arises from the lateral side of the network, travels up the lateral side of the forearm and arm to the shoulder, and joins the axillary vein there. Intravenous fluids are often administered through the distal end of this vein.
3. The **basilic**[21] (bah-SIL-ic) **vein** arises from the medial side of the network, travels up the posterior side of the forearm, and continues into the arm. It turns deeper about midway up the arm and joins the brachial vein at the axilla (see part II.4 of this table).

   As an aid to remembering which vein is cephalic and which is basilic, visualize your arm held straight away from the torso (abducted) with the thumb up, like the orientation of the embryonic limb bud. The cephalic vein runs along the upper side of the arm closer to the head (as suggested by *cephal,* "head"), and the name *basilic* is suggestive of the lower (basal) side of the arm (although not named for that reason).
4. The **median cubital vein** is a short anastomosis between the cephalic and basilic veins that obliquely crosses the cubital fossa (anterior bend of the elbow). It is often clearly visible through the skin and is the most common site for drawing blood.
5. The **median antebrachial vein** drains a network of blood vessels in the hand called the **superficial palmar venous network.** It travels up the medial forearm and terminates at the elbow, emptying variously into the basilic vein, median cubital vein, or cephalic vein.

II. Deep Veins

1. The **deep** and **superficial venous palmar arches** receive blood from the fingers and palmar region. They are anastomoses that join the radial and ulnar veins.
2. Two **radial veins** arise from the lateral side of the palmar arches and course up the forearm alongside the radius. Slightly distal to the elbow, they converge and give rise to one of the brachial veins described shortly.
3. Two **ulnar veins** arise from the medial side of the palmar arches and course up the forearm alongside the ulna. They unite near the elbow to form the other brachial vein.
4. The two **brachial veins** continue up the brachium, flanking the brachial artery, and converge into a single vein just before the axillary region.
5. The **axillary vein** forms by the union of the brachial and basilic veins. It begins at the lower margin of the teres major muscle and passes through the axillary region, picking up the cephalic vein along the way. At the lateral margin of the first rib, it changes name to the subclavian vein.
6. The **subclavian vein** continues into the shoulder posterior to the clavicle and ends where it meets the internal jugular vein of the neck. There it becomes the brachiocephalic vein. The right and left brachiocephalics converge and form the superior vena cava, which empties into the right atrium of the heart.

DEEPER INSIGHT 21.4

Central Venous Catheters

Veins of the upper limb, especially in the forearm and back of the hand, are the most commonly used sites for administration of intravenous (I.V.) drugs and for drawing blood specimens. Drugs may be given here either by syringe or by *intravenous cannula (catheter)*—a flexible tube usually only a few centimeters long inserted into a superficial vein. I.V. cannulas, however, present risks of phlebitis (venous inflammation) and sepsis (infection), and cannot be left in place more than 96 hours.

A *central venous catheter (CVC)*, or *central line*, however, can be left in place for longer periods, from weeks to as much as a year. The CVC is a long, thin, flexible tube commonly threaded into the cephalic, basilic, brachial, subclavian, or internal jugular vein until it reaches the superior vena cava close to the right atrium of the heart. Because these are deeper veins, CVC insertion is guided by bedside ultrasound and the final placement of the tip of the catheter is confirmed by X-ray.

There are various types of CVCs, including the *PICC line* (*peripherally inserted venous catheter;* pronounced "pick"). PICC lines are employed for long-term administration of fluids; nutrients; antibiotics, chemotherapy, and other drugs; and caustic drugs that would cause inflammation in smaller veins. They can be used to administer larger volumes of drugs compared to amounts given by syringe or I.V. catheter; to ensure that drugs are rapidly diluted and quickly distributed throughout the body; and for cardiac patients, to administer drugs quickly to the heart. They are also used for kidney dialysis, taking frequent blood samples, and monitoring central venous blood pressure in hospital patients. PICC lines also enable outpatients to take I.V. medications at home, usually under the guidance of a home health-care nurse, for long-term outpatient care.

---

[20] *cephalic* = related to the head
[21] *basilic* = royal, prominent, important

TABLE 21.9 Veins of the Upper Limb (continued)


Jugular vv.
External
Internal
Brachiocephalic vv.
Subclavian v.
Superior vena cava
Axillary v.
Cephalic v.
Basilic v.
Brachial vv.
Median cubital v.
Median antebrachial v.
Radial vv.
Ulnar vv.
Cephalic v.
Basilic v.
Deep venous palmar arch
Superficial venous palmar arch
Dorsal venous network
Superficial veins
Deep veins
Lateral
Medial
Internal jugular v.
Subclavian v.
Brachiocephalic v.
Superior vena cava
Axillary v.
Basilic v.
Cephalic v.
Brachial vv.
Median cubital v.
Radial vv.
Ulnar vv.
Median antebrachial v.
Superficial palmar venous network [not shown in part (a)]
Dorsal venous network
Venous palmar arches

(a) Major veins

(b) Blood-flow schematic

Figure 21.28 **Veins of the Upper Limb.** Variations on this pattern are highly common. Many venous anastomoses are omitted for clarity. APR

TABLE 21.10 Arteries of the Lower Limb

As we have already seen, the aorta forks at its lower end into the right and left common iliac arteries, and each of these soon divides again into an internal and external iliac artery. We traced the internal iliac artery in table 21.6 (part IV), and we now trace the external iliac as it supplies the lower limb (figs. 21.29 and 21.30).

I. Arteries from the Pelvic Region to the Knee

1. The **external iliac artery** sends small branches to the skin and muscles of the abdominal wall and pelvic girdle, then passes behind the inguinal ligament and becomes the femoral artery.
2. The **femoral artery** passes through the *femoral triangle* of the upper medial thigh, where its pulse can be palpated (see Deeper Insight 21.5). In the triangle, it gives off several small arteries to the skin and then produces the following branches before descending the rest of the way to the knee.
    a. The **deep femoral artery** arises from the lateral side of the femoral, within the triangle. It is the largest branch and is the major arterial supply to the thigh muscles.
    b. Two **circumflex femoral arteries** arise from the deep femoral, encircle the head of the femur, and anastomose laterally. They supply mainly the femur, hip joint, and hamstring muscles.
3. The **popliteal artery** is a continuation of the femoral artery in the popliteal fossa at the rear of the knee. It begins where the femoral artery emerges from an opening *(adductor hiatus)* in the tendon of the adductor magnus muscle and ends where it splits into the *anterior* and *posterior tibial arteries*. As it passes through the popliteal fossa, it gives off anastomoses called **genicular**[22] **arteries** that supply the knee joint.

II. Arteries of the Leg and Foot

In the leg proper, the three most significant arteries are the anterior tibial, posterior tibial, and fibular arteries.

1. The **anterior tibial artery** arises from the popliteal artery and immediately penetrates through the interosseous membrane of the leg to the anterior compartment. There, it travels lateral to the tibia and supplies the extensor muscles. Upon reaching the ankle, it gives rise to the following dorsal arteries of the foot.
    a. The **dorsal pedal artery** traverses the ankle and upper medial surface of the foot and gives rise to the arcuate artery.
    b. The **arcuate artery** sweeps across the foot from medial to lateral and gives rise to vessels that supply the toes.
2. The **posterior tibial artery** is a continuation of the popliteal artery that passes down the leg, deep in the posterior compartment, supplying flexor muscles along the way. Inferiorly, it passes behind the medial malleolus of the ankle and into the plantar region of the foot. It gives rise to the following:
    a. The **medial** and **lateral plantar arteries** originate by bifurcation of the posterior tibial artery at the ankle. The medial plantar artery supplies mainly the great toe. The lateral plantar artery sweeps across the sole of the foot and becomes the deep plantar arch.
    b. The **deep plantar arch** gives off another set of arteries to the toes.
3. The **fibular (peroneal) artery** arises from the proximal end of the posterior tibial artery near the knee. It descends through the lateral side of the posterior compartment, supplying lateral muscles of the leg along the way, and ends in a network of arteries in the heel.

---

[22] *genic* = knee


Lateral
Medial
Medial
Lateral
Aorta
Common iliac a.
Internal iliac a.
External iliac a.
Inguinal ligament
Obturator a.
Circumflex femoral aa.
Circumflex femoral aa.
Femoral a.
Descending branch of lateral circumflex femoral a.
Deep femoral a.
Descending branch of lateral circumflex femoral a.
Adductor hiatus
Genicular aa.
Popliteal a.
Genicular aa.
Anterior tibial a.
Fibular a.
Posterior tibial a.
Anterior tibial a.
Fibular a.
Dorsal pedal a.
Medial tarsal a.
Lateral plantar a.
Lateral tarsal a.
Medial plantar a.
Arcuate a.
Deep plantar arch

(a) Anterior view

(b) Posterior view

Figure 21.29 **Arteries of the Lower Limb.** The foot is strongly plantar flexed with the upper surface facing the viewer in part (a) and the sole facing the viewer in part (b). APR

TABLE 21.10 **Arteries of the Lower Limb (continued)**


Aorta
Common iliac aa.
External iliac a.
Femoral a.
Deep femoral a.
Circumflex femoral aa.
Popliteal a.
Anterior tibial a.
Posterior tibial a.
Fibular a.
Deep plantar arch
Internal iliac a.:
Anterior trunk
Posterior trunk
Iliolumbar a.
Lateral sacral aa.
Superior gluteal a.
Umbilical a.
Superior vesical a.
Inferior vesical a. (male
Vaginal a. (female)
Middle rectal a.
Obturator a.
Internal pudendal a.
Uterine a. (female)
Inferior gluteal a.
Dorsal pedal a.
Arcuate a.

Figure 21.30 **Arterial Schematic of the Pelvic Region and Lower Limb.** The pelvic schematic on the right is stretched for clarity. These arteries are not located as far inferiorly as the limb arteries depicted on the left.

Apply What You Know

There are certain similarities between the arteries of the hand and foot. What arteries of the wrist and hand are most comparable in arrangement and function to the arcuate artery and deep plantar arch of the foot?

TABLE 21.11 Veins of the Lower Limb

We will follow drainage of the lower limb from the toes to the inferior vena cava (figs. 21.31 and 21.32). As in the upper limb, there are deep and superficial veins with anastomoses between them. Most of the anastomoses are omitted from the illustrations.

I. Superficial Veins

1. The **dorsal venous arch** (fig. 21.31a) is often visible through the skin on the dorsum of the foot. It collects blood from the toes and more proximal part of the foot, and has numerous anastomoses similar to the dorsal venous network of the hand. It gives rise to the following two veins.
2. The **small (short) saphenous**[23] (sah-FEE-nus) **vein** arises from the lateral side of the arch and passes up that side of the leg as far as the knee. There, it drains into the popliteal vein.
3. The **great (long) saphenous vein,** the longest vein in the body, arises from the medial side of the arch and travels all the way up the leg and thigh to the inguinal region. It empties into the femoral vein slightly inferior to the inguinal ligament. It is commonly used as a site for the long-term administration of intravenous fluids; it is a relatively accessible vein in infants and in patients in shock whose veins have collapsed. Portions of this vein are commonly used as grafts in coronary bypass surgery. The great and small saphenous veins are among the most common sites of varicose veins.

II. Deep Veins

1. The **deep plantar venous arch** (fig. 21.31b) receives blood from the toes and gives rise to **lateral** and **medial plantar veins** on the respective sides. The lateral plantar vein gives off the *fibular veins,* then crosses over to the medial side and approaches the medial plantar vein. The two plantar veins pass behind the medial malleolus of the ankle and continue as a pair of *posterior tibial veins.*
2. The two **posterior tibial veins** pass up the leg embedded deep in the calf muscles. They converge like an inverted Y into a single vein about two-thirds of the way up the tibia.
3. The two **fibular (peroneal) veins** ascend the back of the leg and similarly converge like a Y.
4. The **popliteal vein** begins near the knee by convergence of these two inverted Ys. It passes through the popliteal fossa at the back of the knee.
5. The two **anterior tibial veins** travel up the anterior compartment of the leg between the tibia and fibula (fig. 21.31a). They arise from the medial side of the dorsal venous arch, converge just distal to the knee, and then flow into the popliteal vein.
6. The **femoral vein** is a continuation of the popliteal vein into the thigh. It drains blood from the deep thigh muscles and femur.
7. The **deep femoral vein** drains the femur and muscles of the thigh supplied by the deep femoral artery. It receives four principal tributaries along the shaft of the femur and then a pair of **circumflex femoral veins** that encircle the upper femur, then finally drains into the upper femoral vein.
8. The **external iliac vein** is formed by the union of the femoral and great saphenous veins near the inguinal ligament.
9. The **internal iliac vein** follows the course of the internal iliac artery and its distribution. Its tributaries drain the gluteal muscles; the medial aspect of the thigh; the urinary bladder, rectum, prostate, and ductus deferens in the male; and the uterus and vagina in the female.
10. The **common iliac vein** is formed by the union of the external and internal iliac veins. The right and left common iliacs then unite to form the inferior vena cava.

---

[23] *saphen* = standing


Lateral
Medial
Medial
Lateral
Inferior vena cava
Common iliac v.
Internal iliac v.
External iliac v.
Circumflex femoral vv.
Circumflex femoral vv.
Deep femoral v.
Femoral v.
Great saphenous v.
Popliteal v.
Anterior tibial v.
Small saphenous v.
Small saphenous v.
Superficial veins
Deep veins
Fibular vv.
Anterior tibial vv.
Posterior tibial vv.
Dorsal venous arch
Medial plantar v.
Lateral plantar v.
Deep plantar venous arch

(a) Anterior view **(b) Posterior view**

Figure 21.31 **Veins of the Lower Limb.** The foot is strongly plantar flexed with the upper surface facing the viewer in part (a) and the sole facing the viewer in part (b). AP|R

TABLE 21.11 **Veins of the Lower Limb (continued)**


Lateral
Medial
Common iliac v.
External iliac v.
Internal iliac v.
Circumflex femoral vv.
Popliteal v.
Fibular vv.
Posterior tibial vv.
Lateral plantar v.
Inferior vena cava
Femoral v.
Deep femoral v.
Great saphenous v.
Small saphenous v.
Anterior tibial vv.
Dorsal venous arch
Medial plantar v.
Deep plantar venous arch
Superficial veins
Deep veins

Figure 21.32 Venous Schematic of the Lower Limb.

DEEPER INSIGHT 21.5

Arterial Pressure Points

In some places, major arteries come close enough to the body surface to be palpated. These places can be used to take a pulse, and they can serve as emergency *pressure points,* where firm pressure can be applied to temporarily reduce arterial bleeding (fig. 21.33a). One of these points is the *femoral triangle* of the upper medial thigh (fig. 21.33b, c). This is an important landmark for arterial supply, venous drainage, and innervation of the lower limb. Its boundaries are the sartorius muscle laterally, the inguinal ligament superiorly, and the adductor longus muscle medially. The femoral artery, vein, and nerve run close to the surface at this point.


Superficial temporal a.
Facial a.
Common carotid a.
Radial a.
Brachial a.
Femoral a.
Popliteal a.
Posterior tibial a.
Dorsal pedal a.
(a)
Pubic tubercle
Adductor longus m.
Gracilis m.
Anterior superior iliac spine
Inguinal ligament
Femoral n.
Femoral a.
Femoral v.
Sartorius m.
Rectus femoris m.
Great saphenous v.
Vastus lateralis m.
(b)
Inguinal ligament
Sartorius
Adductor longus
(c)

Figure 21.33 Arterial Pressure Points. (a) Areas where arteries lie close enough to the surface that a pulse can be palpated or pressure can be applied to reduce arterial bleeding. (b) Structures in the femoral triangle. (c) Boundaries of the femoral triangle.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

14. Trace one possible path of a red blood cell from the left ventricle to the toes.
15. Trace one possible path of a red blood cell from the fingers to the right atrium.
16. The subclavian, axillary, and brachial arteries are really one continuous artery. What is the reason for giving it three different names along its course?
17. State two ways in which the great saphenous vein has special clinical significance. Where is this vein located?

21.5 Developmental and Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the embryonic development of the blood vessels;
b. explain how the circulatory system changes at birth; and
c. describe the changes that occur in the blood vessels in old age.

Embryonic Development of the Blood Vessels

The development of blood vessels, both in the embryo and later in life, is called **angiogenesis.**[24] The first trace of embryonic angiogenesis appears at 13 to 15 days of gestation. At this time, the embryo is a three-layered disc of ectoderm, mesoderm, and endoderm, attached to the uterus by an *embryonic stalk* and associated with three membranes, the *chorion, amnion,* and *yolk sac* (see fig. 4.3, p. 90). In the yolk sac, groups of mesenchymal cells differentiate into cell masses called *blood islands.* Spaces open in the middle of a blood island, and cells in these spaces differentiate into *hemoblasts,* the forerunners of the first blood cells. Cells of the margin become *angioblasts,* which give rise to the endothelium of the future blood vessel (fig. 21.34).

As blood islands proliferate and grow, they begin to connect with each other, and their internal spaces form the lumens of the blood vessels. By the end of week 3, the yolk sac is fully vascularized. In subsequent weeks, blood islands begin to appear in the liver, spleen, and bone marrow, and those of the yolk sac and other sites external to the embryo disappear. Also during this time, the heart tube forms and links up with the blood vessels. Around the end of week 3, the heart begins beating, and a week later, a unidirectional blood flow is established. The blood vessels are not long uniform tubes at this time, but a network of irregularly shaped channels. Those that receive the greatest blood flow develop a tunica media and externa and become more tubular, thus becoming typical blood vessels. Those with a lesser flow either degenerate or remain composed of nothing but endothelium, thus becoming capillaries. Capillaries and the larger vessels sprout lateral branches, giving rise to the eventual anatomical circuitry of the mature cardiovascular system.



(a) Early blood islands in yolk sac

(b) Differentiation of mesenchymal cells into angioblasts and hemoblasts

(c) Merger of blood islands to form blood vessels

Figure 21.34 Development of Blood Vessels and Erythrocytes from Embryonic Blood Islands.

---

[24] *angio* = vessel; *genesis* = origin, production

We will not examine the complex details of the embryonic development of all the major blood vessels, but primarily the major arteries and veins near the heart. Remember that the embryo forms five pairs of pharyngeal arches in weeks 4 to 5 (see chapter 4, p. 92). As these develop, a pouch called the *aortic sac* appears at the rostral end of the heart. An artery arises from each side of the sac, loops through the first pharyngeal arch, and ends in the dorsal aorta on that side. The loop is *aortic arch I.* Five more pairs of **aortic arches** (II–VI) later form between the pharyngeal pouches (fig. 21.35a). This reflects a primitive vertebrate pattern seen in fish, where the six aortic arches supply blood to the gills, but it becomes highly modified in humans and other mammals. The six arches actually never appear all at once as shown in the figure. Arches I and II degenerate before the most caudal arches appear, and arch V never develops to any great extent in mammals. Arches III, IV, and VI, however, play major roles in human development (fig. 21.35b). Arch III gives rise to the common carotid artery and the proximal portion of the internal carotid artery; the external carotid artery buds from the common carotid. The common carotids are short at first, but elongate as the embryo grows and the heart moves caudally. Arch IV degenerates on the right, but on the left it produces the aortic arch. Arch VI gives rise to the pulmonary arteries.

Initially, the embryo has two *dorsal aortae* that pass side by side for the length of the body. Caudal to the pharyngeal arches, however, these soon fuse into a single **dorsal aorta,** the forerunner of the adult descending aorta (fig. 21.36). The dorsal aorta issues about 30 pairs of *intersegmental arteries,* which supply blood to the somites and their derivatives. Most of these degenerate, but the adult intercostal arteries, lumbar arteries, and common iliac arteries are remnants of some of the embryonic intersegmental arteries.

The principal veins associated with the heart (fig. 21.36) are the *anterior cardinal vein,* which drains the head region; the *posterior cardinal vein,* which drains the body caudal to the heart; the *vitelline veins* from the yolk sac; and the *umbilical veins* from the placenta. There are initially two umbilical veins, but only the left one persists until birth. The cardinal veins provide most of the venous drainage of the embryonic body. They meet at a *common cardinal vein* just before entering the heart. The future superior vena cava develops from the right anterior cardinal and common cardinal veins. The posterior cardinal veins largely degenerate, however, leaving only the common iliac veins and part of the azygos system as remnants. The inferior vena cava develops separately, not from the posterior cardinal veins.

Changes at Birth

As we saw in chapter 20 (p. 557), the fetus has certain *shunts* that allow most blood to bypass the nonfunctional lungs: the *foramen ovale* and *ductus arteriosus.* After birth, when the lungs are functional, these shunts close, leaving a *fossa ovalis* in the interatrial



(a) 3–4 weeks **(b) 7 weeks**

Figure 21.35 **Development of Some Major Arteries from the Embryonic Aortic Arches.** (a) The six aortic arches, dorsal view. This is a composite diagram representing developments from day 22 through day 29. In reality, arch I degenerates as arches III and IV form, and arch II degenerates as arch VI forms. Aortic arch V develops very little, and sometimes not at all, in humans. (b) Remodeled arterial system at about 7 weeks. Pale colors and arch numbers in parentheses indicate the former positions of aortic arches that no longer exist at this time, for comparison to part (a). The left subclavian vein does not develop from an aortic arch and is not illustrated.



Figure 21.36 **Major Embryonic Blood Vessels at 26 Days.** Left lateral view of the embryo, yolk sac, and part of the placenta.

septum and *ligamentum arteriosum* between the aortic arch and left pulmonary artery. Another fetal shunt called the *ductus venosus* bypasses the liver, which also is not very functional before birth. This is a vein; blood returning from the placenta enters the fetus through the umbilical vein and flows into the ductus venosus. The ductus venosus then empties into the inferior vena cava. After birth, the ductus venosus constricts, and blood is forced to flow through the liver. The ductus venosus leaves a fibrous remnant, the *ligamentum venosum,* on the inferior surface of the liver.

The two umbilical arteries become the *superior vesical arteries* to the urinary bladder. The umbilical vein becomes a fibrous cord, the *round ligament,* which attaches the liver to the anterior body wall (fig. 21.37).

The Aging Vascular System

As we get older, our arteries become less distensible and absorb less systolic force. This increasing stiffness is called **arteriosclerosis** ("hardening of the arteries"). The primary cause of it is a lifetime of damage by free radicals, which cause gradual deterioration of the elastic and other tissues of the arterial walls—much like old rubber bands that become hardened and less stretchy. Another contributing factor is **atherosclerosis**, the growth of lipid deposits in the arterial walls (see Deeper Insight 20.1, p. 551). These deposits can become calcified *complicated plaques,* giving the arteries a hard, bonelike consistency. As a result of these changes, blood pressure rises with age and older people are at elevated risk for hypertension and its consequences, such as aneurysms, stroke, and kidney failure.

Another effect of aging is declining responsiveness of the baroreceptors, so vasomotor responses to changes in blood pressure are not as quick or efficient. Among some elderly people, the blunted response causes *orthostatic hypotension:* When one goes from a lying to a sitting or standing posture, blood is drawn away from the brain by gravity. Without a prompt corrective baroreflex, the drop in cerebral blood flow can cause dizziness or even fainting and falling, which in turn presents a risk of serious bone fractures.

Vascular Diseases

Atherosclerosis, the most common vascular disease, can lead to stroke, renal failure, or heart failure—most notoriously the last of these. Therefore, it was described in chapter 20 in the context of coronary artery disease. Table 21.12 describes a few other vascular diseases. Some of the hematologic and cardiac pathologies in the preceding chapters also include aspects of vascular pathology.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

18. What do angioblasts develop from, and what do they develop into?
19. Describe, in humans, what becomes of the six pairs of aortic arches typical of vertebrate embryos.
20. Name two blood vessels that close off and become fibrous cords soon after birth.
21. Describe two changes that occur in the blood vessels in old age, other than specific vascular diseases.


Ductus arteriosus
Lung
Foramen ovale
Ductus venosus
Liver
Umbilical vein
Umbilicus
Umbilical cord
Umbilical arteries
Placenta
Urinary bladder
Kidney
1
2
3
4
5
6
7
Inferior vena cava
Abdominal aorta
Common iliac artery
Oxygen content of blood
Low
High
Ligamentum arteriosum
Lung
Fossa ovalis
Ligamentum venosum
Liver
Round ligament
Kidney
Median umbilical ligaments
Urinary bladder
1
2
3
4
5
6

(a) Fetal circulation

① Blood bypasses the lungs by flowing directly from the right atrium through the foramen ovale into the left atrium.

② Blood also bypasses the lungs by flowing from the pulmonary trunk through the ductus arteriosus into the aorta.

③ Oxygen-poor, waste-laden blood flows through two umbilical arteries to the placenta.

④ The placenta disposes of CO_2 and other wastes and reoxygenates the blood.

⑤ Oxygenated blood returns to the fetus through the umbilical vein.

⑥ Placental blood bypasses the liver by flowing through the ductus venosus into the inferior vena cava (IVC).

⑦ Placental blood from the umbilical vein mixes with fetal blood from the IVC and returns to the heart.

(b) Neonatal circulation

① Foramen ovale closes and becomes fossa ovalis.

② Ductus arteriosus constricts and becomes ligamentum arteriosum.

③ Umbilical arteries degenerate and become median umbilical ligaments.

④ Umbilical vein constricts and becomes round ligament of liver.

⑤ Ductus venosus degenerates and becomes ligamentum venosum of liver.

⑥ Blood returning to the heart is now oxygen-poor, systemic blood only.

Figure 21.37 **Some Circulatory Changes Occurring at Birth.** (a) Circulatory system of the full-term fetus. (b) Circulatory system of the newborn.

TABLE 21.12 **Some Vascular Pathologies**

Hypertension	Abnormally high blood pressure. In a young adult, a BP up to 130/85 is considered normal, BP above 140/90 is considered hypertensive, and a BP between these ranges is borderline or "high normal." About 90% of cases of hypertension *(primary hypertension)* result from a poorly understood complex of hereditary, behavioral, and other factors. Risk factors include obesity, a sedentary lifestyle, diet, smoking, sex, and race. *Secondary hypertension* (10% of cases) results from other identifiable disorders such as renal insufficiency, atherosclerosis, hyperthyroidism, and polycythemia. Treated with dietary modification, weight loss, and drugs such as beta-blockers (which reduce responsiveness of the blood vessels to sympathetic stimulation), calcium channel blockers (which relax the vascular smooth muscle), diuretics (which reduce blood volume), and ACE inhibitors (which inhibit synthesis of the vasoconstrictor angiotensin II).
Phlebitis	Inflammation of a vein, causing pain, tenderness, edema, and skin discoloration along its course. Often of unknown cause, but may follow surgery, childbirth, or infections.
Stroke (cerebrovascular accident)	The sudden death (infarction) of brain tissue occurring when cerebral atherosclerosis, thrombosis, or hemorrhage of a cerebral aneurysm cuts off blood flow to part of the brain. Effects range from unnoticeable to fatal, depending on the extent of tissue damage and function of the affected tissue. Blindness, paralysis, loss of speech, and loss of sensation are among the sublethal effects.
Vasculitis	Inflammation of any blood vessel (see also phlebitis in this table), usually caused by an immune response or infectious pathogen, but sometimes by radiation, trauma, or toxins. Produces a wide variety of symptoms, including muscle and joint pain, fever, headache, myocardial ischemia, numbness, and blindness.

Disorders Described Elsewhere

Air embolism	535	Patent ductus arteriosus	559
Aneurysm	566	Raynaud disease	457
Atherosclerosis	603	Varicose veins	571
Orthostatic hypotension	603		

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

21.1 General Anatomy of the Blood Vessels (p. 564)

1. The meaning of *arteries, capillaries,* and *veins* with respect to the route of blood flow from and back to the heart
2. The names and characteristics of the three tissue layers (tunics) of arteries and veins
3. Why arteries are called *resistance vessels,* and how this relates to their histology
4. The three size classes of arteries; their histological and functional differences; and examples of arteries of the two largest types
5. The location, structure, and functions of metarterioles and precapillary sphincters
6. The locations and functions of the carotid sinuses, aortic baroreceptors, carotid bodies, and aortic bodies
7. The size and general structure of blood capillaries, and the various means by which substances can pass through the capillary wall to enter or leave the bloodstream
8. The distinction between continuous capillaries, fenestrated capillaries, and sinusoids
9. The structure of a capillary bed, and its relationship to a thoroughfare channel and precapillary sphincters
10. Why veins are called *capacitance vessels,* and how this relates to their volume, blood pressure, and histology
11. The distinction between postcapillary venules, muscular venules, medium veins, venous sinuses, and large veins
12. The locations, structure, and function of venous valves
13. Variations in the route of blood circulation, notably portal systems and the three kinds of anastomoses

21.2 The Pulmonary Circuit (p. 572)

1. The route of blood flow in the pulmonary circuit, including the names of its blood vessels in order from the point where blood leaves the right ventricle to the points where it enters the left atrium
2. The function of the pulmonary circuit and how this relates to the relative oxygen and carbon dioxide concentrations in its arteries and veins
3. The systemic blood supply to the lungs and how this differs functionally from the pulmonary circuit

21.3 Systemic Vessels of the Axial Region (p. 573)

1. The three principal regions of the aorta—ascending aorta, aortic arch, and descending aorta; the principal arteries that arise from the first two; the distinction between

the thoracic and abdominal aorta; and how the aorta ends (table 21.1)

2. The names and routes of the four arteries that ascend each side of the neck (table 21.2, part I)
3. The routes of the common carotid, external carotid, and internal carotid arteries; names of the branches given off by the external and internal carotids; and the regions supplied by those branches (table 21.2, part II)
4. The location and components of the cerebral arterial circle; the arteries that supply it; and the cerebral arteries that arise from it (table 21.2, parts III, IV)
5. The locations and names of the dural venous sinuses and their relationship with the internal jugular veins and facial veins (table 21.3, part I)
6. The locations of the internal and external jugular veins and the vertebral veins; the vessels from which these veins receive blood; and the vessels into which they ultimately drain (table 21.3, part II)
7. Branches of the thoracic aorta and the regions supplied by them (table 21.4, parts I, II)
8. The course of the subclavian and axillary arteries; the branches they give off along the way; and the regions supplied by those branches (table 21.4, part III)
9. The course of the subclavian and brachiocephalic veins; the regions drained by them; and how the superior vena cava originates and where it terminates (table 21.5, part I)
10. Locations of the azygos, hemiazygos, and accessory hemiazygos veins; the other veins that drain into this system; and where the blood of the azygos system flows next (table 21.5, part II)
11. The names, order of occurrence, and organs supplied by the arteries that branch off the abdominal aorta (table 21.6, part I)
12. The location of the celiac trunk; its three primary branches; and the organs supplied by these branches and their subdivisions (table 21.6, part II)
13. The origin of the superior mesenteric artery; its branches; and the regions of the digestive tract that it supplies (table 21.6, part III)
14. The origin of the inferior mesenteric artery; its branches; and the regions of the digestive tract that it supplies
15. The origin of the common iliac arteries; their branching into external and internal iliac arteries; the two trunks of the internal iliac; names of the branches of these two trunks; and the organs and tissues supplied by those branches (table 21.6, part IV)
16. The locations of the internal and external iliac veins; their convergence to form the common iliac vein; convergence of the two common iliac veins to form the inferior vena cava; and regions drained by the internal and external iliac veins (table 21.7, part I)
17. The tributaries that drain into the inferior vena cava, in order, as it ascends the abdominal cavity; the organs and regions drained by those tributaries; and where the inferior vena cava ends (table 21.7, part I)
18. The ascending lumbar veins and their relationships with the inferior vena cava and the azygos system (table 21.7, part II)
19. The general purpose of the hepatic portal system, and the locations of the two capillary beds that define this as a portal system (table 21.7, part III)
20. Tributaries that drain directly or indirectly into the hepatic portal vein before it enters the liver; the organs drained by these tributaries; and where the hepatic portal blood goes within the liver and after it leaves the liver (table 21.7, part III)

21.4 Systemic Vessels of the Appendicular Region (p. 590)

1. The arterial branches and alternative routes followed by the blood in getting from the subclavian artery to the palmar region, and structures supplied by their branches along the way (table 21.8)
2. The superficial veins followed by the blood in getting from the hand to the cephalic and basilic veins, and where those two veins end in the brachial region (table 21.9, part I)
3. The deep veins followed by the blood in getting from the hand to the subclavian vein, and where they pick up the blood from the cephalic and basilic veins (table 21.9, part II)
4. The arterial branches and alternative routes followed by the blood in getting from the common iliac artery to the foot, and structures supplied by their branches along the way (table 21.10)
5. The superficial veins followed by the blood in getting from the foot to the femoral vein (table 21.11, part I)
6. The deep veins followed by the blood in getting from the foot to the common iliac vein (table 21.11, part II)

21.5 Developmental and Clinical Perspectives (p. 601)

1. The origin of the first blood cells and blood vessels in the embryonic yolk sac
2. The anatomy of the embryonic aortic sac, paired dorsal aortae, and six aortic arches; and the fates of those aortic arches
3. The origin of a single dorsal aorta and of the intersegmental arteries, and some adult structures that arise from the intersegmental arteries
4. The routes of embryonic venous drainage by way of the anterior and posterior cardinal veins and the vitelline and umbilical veins, and the fate of the anterior and posterior cardinal veins
5. The shunts that allow most fetal blood to bypass the liver and lungs before birth, and what happens to these shunts shortly after birth
6. Multiple reasons why the arteries stiffen as one ages, and the health implications of this
7. The cardiovascular reason why elderly persons sometimes experience dizziness or even fainting and falling upon rising from a reclining to a sitting or standing posture

Testing Your Recall

1. Blood normally flows into a capillary bed from
   a. a distributing artery.
   b. a conducting artery.
   c. a metarteriole.
   d. a thoroughfare channel.
   e. a venule.
2. Plasma solutes enter the tissue fluid most easily from
   a. continuous capillaries.
   b. fenestrated capillaries.
   c. arteriovenous anastomoses.
   d. collateral vessels.
   e. venous anastomoses.
3. A blood vessel adapted to withstand great fluctuations in blood pressure would be expected to have
   a. an elastic tunica media.
   b. a thick tunica interna.
   c. one-way valves.
   d. a flexible endothelium.
   e. a rigid tunica media

4. A circulatory pathway in which the blood flows through two capillary beds in series before it returns to the heart is called
   a. an arteriovenous anastomosis.
   b. an arterial anastomosis.
   c. a venous anastomosis.
   d. a venous return pathway.
   e. a portal system.
5. Intestinal blood flows into the liver by way of
   a. the superior mesenteric vein.
   b. the hepatic portal vein.
   c. the abdominal aorta.
   d. the hepatic sinusoids.
   e. the hepatic veins.
6. Blood islands first form in the embryonic
   a. spleen.
   b. yolk sac.
   c. placenta.
   d. liver.
   e. red bone marrow.
7. Most blood flowing in all of the following arteries *except* the _____ is destined to circulate through the brain before returning to the heart.
   a. vertebral arteries
   b. internal carotid arteries
   c. basilar artery
   d. superficial temporal artery
   e. anterior communicating artery
8. All of the following blood vessels *except* the _____ are located in the upper limb.
   a. cephalic vein
   b. small saphenous vein
   c. brachial artery
   d. circumflex humeral arteries
   e. metacarpal arteries
9. The adult aortic arch develops from the embryonic
   a. right aortic arch IV.
   b. left aortic arch IV.
   c. right aortic arch V.
   d. conus arteriosus.
   e. dorsal aorta.
10. To get from the posterior tibial vein to the femoral vein, blood flows through
    a. the anterior tibial vein.
    b. the popliteal vein.
    c. the internal iliac vein.
    d. the great saphenous vein.
    e. the basilic vein.
11. Filtration pores are characteristic of _____ capillaries.
12. The capillaries of skeletal muscles are of the structural type called _____.
13. The epithelium that lines the inside of a blood vessel is called _____.
14. The two _____ veins unite like an upside-down Y to form the inferior vena cava.
15. Carotid and aortic bodies are called _____ because they respond to changes in blood chemistry.
16. Movement across the capillary endothelium by the uptake and release of fluid droplets is called _____.
17. The two largest veins that empty into the right atrium are the _____ and _____.
18. The pressure sensors in the major arteries near the head are called _____.
19. Most of the blood supply to the brain comes from a ring of arterial anastomoses called the _____.
20. The major superficial veins of the arm are the _____ on the medial side and _____ on the lateral side.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. vas-
2. advent-
3. fenestr-
4. cephalo-
5. jugul-
6. angio-
7. celi-
8. genic-
9. -orum
10. vesic-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. The lungs receive both a pulmonary and a systemic blood supply.
2. The pancreas and spleen receive their blood supply mainly from the superior mesenteric artery.
3. Veins anastomose more than arteries do.
4. From the time blood leaves the heart to the time it returns, it always passes through only one capillary bed.
5. The superior vena cava begins where the two subclavian veins meet.
6. Erythrocytes and endothelial cells arise from the same embryonic stem cells.
7. The smooth muscle of the tunica media of a large vessel is nourished mainly by the diffusion of nutrients from blood in the vessel lumen.
8. Venous blood from the intestines flows through the liver before it flows through the heart.
9. In a few unusual cases, one or more arteries of the cerebral arterial circle are lacking.
10. Arteries to the ovaries and testes originate relatively high in the abdominal cavity, near the kidneys.

Answers in appendix A

Testing Your Comprehension

1. Suppose a posterior tibial vein was obstructed by thrombosis. Describe one or more alternative routes by which blood from the foot could get to the common iliac vein.
2. Why would a ruptured aneurysm of the basilar artery be more serious than a ruptured aneurysm of the anterior communicating artery?
3. What differences would you expect between a sample of blood taken from the superior mesenteric vein and a sample taken from a hepatic vein? Consider, especially, differences in nutrient levels and bacterial count, and look forward in the book if necessary for a preview of liver functions.
4. Why could a choke hold (a tight grip around the neck) cause a person to pass out? What arteries would be involved?
5. Why is it better to have baroreceptors in the carotid sinus rather than in some other location such as the abdominal aorta or common iliac arteries?



Natural killer cells (yellow) attacking a human cancer cell (red)

© Eye of Science/Science Source

CHAPTER 22

THE LYMPHATIC SYSTEM AND IMMUNITY

CHAPTER OUTLINE

22.1 Lymph and Lymphatic Vessels 610
- Components and Functions of the Lymphatic System 610
- Lymph 610
- Lymphatic Vessels 610
- The Flow of Lymph 613

22.2 Lymphatic Cells, Tissues, and Organs 615
- Lymphatic Cells 615
- Lymphatic Tissues 616
- Overview of Lymphatic Organs 616
- Red Bone Marrow 616
- The Thymus 617
- Lymph Nodes 617
- Tonsils 620
- The Spleen 620

22.3 The Lymphatic System in Relation to Immunity 623
- Modes of Defense 623
- B Cells and Humoral Immunity 624
- T Cells and Cellular Immunity 624

22.4 Developmental and Clinical Perspectives 626
- Embryonic Development 626
- The Aging Lymphatic and Immune Systems 626
- Lymphatic and Immune Disorders 626

Study Guide 628

DEEPER INSIGHTS

22.1 Lymph Nodes and Metastatic Cancer 620
22.2 Splenectomy 622

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:

- General gland structure: capsule, septa, stroma, and parenchyma (p. 76)
- Antigens and antibodies (p. 526)
- Leukocyte types, especially lymphocytes (pp. 527–530)
- Angiogenesis (p. 601)

Anatomy & Physiology REVEALED®
aprevealed.com

Module 10: Lymphatic System

The lymphatic system is a network of tissues, organs, and vessels that help to maintain the body's fluid balance, cleanse the body fluids of foreign matter, and provide immune cells for defense. Of all the body systems, it is perhaps the least familiar to most people. Yet without it, neither the circulatory system nor the immune system could function—circulation would shut down from fluid loss, and the body would be overrun by infection for lack of immunity. This chapter discusses the anatomy of the lymphatic system in relation to its roles in fluid recovery and immunity. The structure and function of the lymphatic system are intimately tied to the immune system, also discussed in this chapter.

22.1 Lymph and Lymphatic Vessels

Expected Learning Outcomes

When you have completed this section, you should be able to

a. list the functions and basic components of the lymphatic system;
b. explain how lymph is formed;
c. describe the route that lymph takes to get into the bloodstream; and
d. explain what makes lymph flow through the lymphatic vessels.

Components and Functions of the Lymphatic System

The **lymphatic**[1] **system** (fig. 22.1) consists of the following components: (1) *lymph,* the fluid the system collects from the interstitial spaces of the tissues and returns to the bloodstream; (2) *lymphatic vessels,* which transport the lymph; (3) *lymphatic tissue,* composed of aggregates of lymphocytes and macrophages that populate many organs of the body; and (4) *lymphatic organs,* in which these cells are especially concentrated and which are set off from surrounding organs by connective tissue capsules. AP|R

The functions of the lymphatic system include the following:

1. **Fluid recovery.** Fluid continually filters from the blood capillaries into the tissue spaces. The blood capillaries reabsorb about 85% of it, but the 15% they do not absorb would amount, over the course of a day, to 2 to 4 L of water and one-quarter to one-half of the plasma protein. One would die of circulatory failure within hours if this water and protein were not returned to the bloodstream. One task of the lymphatic system is to reabsorb this excess and return it to the blood. Even partial interference with lymphatic drainage can cause tissues to swell with excess fluid—a condition called **edema** (fig. 22.2).
2. **Immunity.** As the lymphatic system recovers excess tissue fluid, it also picks up foreign cells and chemicals from the tissues. Some of these are **pathogens**[2]—microorganisms with the potential to cause disease. On its way back to the bloodstream, the fluid passes through lymph nodes, which act as filters where immune cells stand guard against pathogens and activate protective immune responses.
3. **Lipid absorption.** In the small intestine, special lymphatic vessels called *lacteals* absorb dietary lipids that cannot be absorbed by the intestinal blood capillaries (see p. 669).

Lymph

Lymph is usually a clear, colorless fluid, similar to blood plasma but low in protein. It originates as tissue fluid that has been taken up by the lymphatic vessels. Its composition varies substantially from place to place. After a meal, for example, lymph draining from the small intestine has a milky appearance because of its high lipid content. This intestinal lymph is called *chyle*[3] (pronounced "kile"). Lymph leaving the lymph nodes contains a large number of lymphocytes—indeed, this is the main supply of lymphocytes to the bloodstream. Lymph can also contain macrophages, hormones, bacteria, viruses, cellular debris, and even traveling cancer cells.

Lymphatic Vessels

Lymph flows through a system of **lymphatic vessels (lymphatics)** similar to blood vessels. These begin with microscopic **lymphatic capillaries (terminal lymphatics),** which penetrate nearly every tissue of the body but are absent from cartilage, bone, bone marrow, and the cornea. They are closely associated with blood capillaries, but unlike them, they are closed at one end (fig. 22.3). A lymphatic capillary consists of a sac of thin endothelial cells that loosely overlap each other like the shingles of a roof. The cells are tethered to surrounding tissue by protein filaments that prevent the sac from collapsing.

Unlike the endothelial cells of blood capillaries, lymphatic endothelial cells are not joined by tight junctions, nor do they have a continuous basal lamina; indeed, the gaps between them are so large that bacteria, lymphocytes, and other cells and particles can enter along with the tissue fluid. Thus, the composition of lymph arriving at a lymph node is like a report on the state of the upstream tissues.

The overlapping edges of the endothelial cells act as valvular flaps that can open and close. When tissue fluid pressure is high, it pushes the flaps inward (open) and fluid flows into the capillary. When pressure is higher in the lymphatic capillary than in the tissue fluid, the flaps are pressed outward (closed).

---

[1] *lympho* = water

[2] *patho* = disease; *gen* = producing

[3] *chyle* = juice


Cervical lymph nodes
R. lymphatic duct
Thymus
Thoracic duct
Cisterna chyli
Abdominal, intestinal, and mesenteric lymph nodes
Red bone marrow
Popliteal lymph nodes
Lymphatic vessels
Palatine tonsil
L. internal jugular v.
Thoracic duct
Axillary lymph node
Spleen
R. and l. lumbar trunks
Intestinal trunk
Inguinal lymph nodes

Figure 22.1 The Lymphatic System.



© MedicImage/Alamy

Figure 22.2 **Edema.** The person on the right shows severe edema of the legs and feet compared to a person without edema (left). Blockage of lymphatic vessels is one of several causes of edema.

Apply What You Know

Contrast the structure of a lymphatic capillary with that of a continuous blood capillary. Explain why their structural difference is related to their functional difference.

The larger lymphatic vessels are similar to veins in their histology. They have a *tunica interna* with an endothelium and valves (fig. 22.4), a *tunica media* with elastic fibers and smooth muscle, and a thin outer *tunica externa.* Their walls are thinner and their valves are closer together than those of the veins.

As the lymphatic vessels converge along their path, they become larger and larger vessels with changing names. The route from the tissue fluid back to the bloodstream is: lymphatic capillaries ⟶ collecting vessels ⟶ six lymphatic trunks ⟶ two collecting ducts ⟶ subclavian veins. Thus, there is a continual recycling of fluid from blood to tissue fluid to lymph and back to the blood (fig. 22.5).

The lymphatic capillaries converge to form **collecting vessels.** These often travel alongside veins and arteries and share a common connective tissue sheath with them. At irregular intervals, they empty into lymph nodes. The lymph trickles slowly through the node, where bacteria are phagocytized and immune cells monitor the fluid for foreign antigens. It leaves the other side of the node through another collecting vessel, traveling on and often encountering additional lymph nodes before it finally returns to the bloodstream.

Eventually, the collecting vessels converge to form larger **lymphatic trunks,** each of which drains a major portion of the body. There are 11 lymphatic trunks, whose names indicate their locations and parts of the body they drain—a solitary *intestinal trunk* and paired *jugular, subclavian, bronchomediastinal, intercostal,* and *lumbar trunks.* The lumbar trunk drains not only the lumbar region but also the lower limbs.

The lymphatic trunks converge to form two **collecting ducts,** the largest of the lymphatic vessels (fig. 22.6):



Figure 22.3 **Lymphatic Capillaries.** (a) Relationship of the lymphatic capillaries to a bed of blood capillaries. (b) Uptake of tissue fluid by a lymphatic capillary.

- *Why can traveling (metastasizing) cancer cells get into the lymphatic system more easily than they can enter the bloodstream?*

1. The **right lymphatic duct** is formed by the convergence of the right jugular, subclavian, and bronchomediastinal trunks in the right thoracic cavity. It receives lymphatic drainage from the right upper limb and right side of the thorax and head, and empties into the right subclavian vein.
2. The **thoracic duct,** on the left, is larger and longer. It begins just below the diaphragm, anterior to the vertebral column at the level of the second lumbar vertebra. Here, the two lumbar trunks and the intestinal trunk join and form a prominent sac called the **cisterna chyli** (sis-TUR-nuh KY-lye), named for the large amount of chyle that it collects after a meal.


Valve
(a)
Lymph
Lymph flows forward through open valves
Closed valves prevent backflow
(b)

© McGraw-Hill Education/ Dennis Strete, photographer

Figure 22.4 **Valves in the Lymphatic Vessels.** (a) Photograph of a lymphatic valve. (b) Operation of the valves to ensure a one-way flow of lymph.

The thoracic duct then passes through the diaphragm with the aorta and ascends the mediastinum, adjacent to the vertebral column. As it passes through the thorax, it receives additional lymph from the left bronchomediastinal, left subclavian, and left jugular trunks, then empties into the left subclavian vein. Collectively, this duct therefore drains all of the body below the diaphragm, and the left upper limb and left side of the head, neck, and thorax.

The Flow of Lymph

Lymph flows under forces similar to those that govern venous return, except that the lymphatic system has no pump like the heart, and it flows at even lower pressure and speed than venous blood. The primary mechanism of flow is rhythmic contractions of the lymphatic vessels themselves, induced when the flowing lymph stretches them. The valves of lymphatic vessels, like those of veins, prevent the fluid from flowing backward. Lymph flow is also produced by skeletal muscles squeezing the lymphatic vessels, like the skeletal muscle pump that moves venous blood. Since lymphatic vessels are often wrapped with an artery in a common connective tissue sheath, arterial pulsation may also rhythmically squeeze the lymphatic vessels and contribute to lymph flow. A thoracic (respiratory) pump promotes the flow of lymph from the abdominal to the thoracic cavity as one inhales. During inhalation, pressure in the thoracic cavity falls below the pressure in the abdominal cavity. Abdominal pressure squeezing on the abdominal lymphatic trunks and cisterna chyli causes lymph to flow upward into the thoracic lymphatics. Finally, at the point where the collecting ducts empty into the subclavian veins, the rapidly flowing bloodstream draws the lymph into it.


Lymphatic system
Cardiovascular system
Lymphatic capillaries
Lymph nodes
Lymphatic trunks
Collecting duct
Collecting vessels
Lymph flow
Lymphatic capillaries
Pulmonary circuit
Subclavian vein
Superior vena cava
Blood flow
Systemic circuit

Figure 22.5 **Fluid Exchange Between the Cardiovascular and Lymphatic Systems.** Blood capillaries lose fluid to the tissue spaces. The lymphatic system picks up excess tissue fluid and returns it to the bloodstream. The lymph flows from lymphatic capillaries through collecting vessels, lymphatic trunks, and collecting ducts, and is filtered through multiple lymph nodes before reentering the bloodstream at the subclavian veins.

- *Identify two benefits in having lymphatic capillaries pick up tissue fluid that is not reclaimed by the blood capillaries.*


Internal jugular veins
Right jugular trunk
Right lymphatic duct
Right subclavian trunk
Right bronchio-mediastinal trunk
Azygos vein
Diaphragm
Cisterna chyli
Right lumbar trunk
Left jugular trunk
Thoracic duct
Left subclavian trunk
Left bronchiomediastinal trunk
Thoracic duct
Thoracic lymph nodes
Hemiazygos vein
Intestinal trunk
Left lumbar trunk
(a)
Right lymphatic duct
Right subclavian vein
Axillary lymph nodes
Lymphatics of breast
(b)
Drained by right lymphatic duct
Drained by thoracic duct
(c)

Figure 22.6 **Lymphatics of the Thoracic Region.** (a) Lymphatics of the thorax and upper abdomen and their relationship to the subclavian veins, where the lymph returns to the bloodstream. (b) Lymphatic drainage of the right mammary and axillary regions. (c) Regions of the body drained by the right lymphatic duct and thoracic duct.

- *Why are the axillary lymph nodes often biopsied in cases of suspected breast cancer?* APR

Apply What You Know

Why does it make more functional sense for the collecting ducts to connect to the subclavian veins than it would for them to connect to the subclavian arteries? Further, why is it advantageous that they enter the superior surface of the subclavian veins rather than entering from below?

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. List the primary functions of the lymphatic system.
2. How does fluid get into the lymphatic system? What prevents it from draining back out?
3. Where does this fluid (lymph) go once it enters the lymphatic vessels? What makes it flow?

22.2 Lymphatic Cells, Tissues, and Organs

Expected Learning Outcomes

When you have completed this section, you should be able to

a. name the major types of cells in the lymphatic system and state their functions;
b. describe the types of lymphatic tissue; and
c. describe the anatomy and lymphatic and immune functions of the red bone marrow, thymus, lymph nodes, tonsils, and spleen.

In addition to lymphatic vessels, another component of the lymphatic system is the lymphatic tissues. These range from loosely scattered cells in the mucous membranes of the digestive, respiratory, reproductive, and urinary tracts, to compact cell populations encapsulated in lymphatic organs. These tissues are composed of a variety of lymphocytes and other cells with various roles in defense and immunity.

Lymphatic Cells APR

Aside from cells playing purely structural roles, the lymphatic system has six principal categories of defensive cells:

1. **Natural killer (NK) cells** are large lymphocytes that attack and lyse bacteria, transplanted tissue cells, and *host cells* (cells of one's own body) that have either become infected with viruses or turned cancerous (see photo on p. 609). They continually patrol the body "on the lookout" for abnormal cells to destroy. This is one of the body's most important defenses against cancer.
2. **T lymphocytes (T cells)** are so named because they develop for a time in the thymus and later depend on thymic hormones to regulate their activity. The *T* stands for *thymus-dependent.* There are four subclasses of T cells:
   - *Cytotoxic T (T_C) cells* are the only T lymphocytes that directly attack and kill other cells. They are especially responsive to cells of transplanted tissues and organs, cancer cells, and host cells infected with viruses, bacteria, or intracellular parasites. They are also called T8, CD8, or CD8+ cells for their surface glycoprotein, CD8. (*CD* stands for *cluster of differentiation,* a classification system for many cell-surface molecules.)
   - *Helper T (T_H) cells* respond to antigens and activate various defense mechanisms, but do not carry out the attack themselves; instead, they help other immune cells respond to the threat. T_H cells play a central coordinating role in multiple forms of defense. They are also called T4, CD4, or CD4+ cells because of a surface glycoprotein called CD4.
   - *Regulatory T (T_R) cells,* or *T-regs,* play an inhibitory role to prevent the immune system from running out of control.
   - *Memory T (T_M) cells* provide long-lasting memory of an antigen. Upon reexposure, the immune system neutralizes the antigen so quickly that it causes no disease symptoms. This is what we mean by being immune[4] to a disease.
3. **B lymphocytes (B cells)** differentiate into *plasma cells*—connective tissue cells that secrete defensive proteins called **antibodies.** They were named for an organ in chickens (the *bursa of Fabricius*[5]) in which they were first discovered; however, you may find it more helpful to think of *B* for *bone marrow,* the site where these cells mature. Some B cells become memory B cells instead of plasma cells, functioning like memory T cells to confer long-lasting immunity.

   In stained blood films, the different types of lymphocytes look essentially alike, but they are about 80% T cells, 15% B cells, and 5% NK and stem cells.
4. **Macrophages** develop from monocytes that have emigrated from the bloodstream. Macrophages are very large, avidly phagocytic cells. They phagocytize tissue debris, dead neutrophils, bacteria, and other foreign matter (fig. 22.7). They also process foreign matter and transport antigenically active fragments of it *(antigenic determinants)* to the cell surface, where they "display" it to T_C and T_H cells. This stimulates the T cells to launch an immune response against the foreign invader. Macrophages, B lymphocytes, and reticular cells are

---

[4] *immuno* = free
[5] Hieronymus Fabricius (Girolamo Fabrizzi) (1537–1619), Italian anatomist



Figure 22.7 **Macrophage Attacking Bacteria.** Filamentous pseudopods of the macrophage snare the rod-shaped bacteria and draw them to the cell surface, where they are phagocytized.



Figure 22.8 **Lymphatic Nodule in the Mucous Membrane of the Small Intestine.** This is an example of mucosa-associated lymphatic tissue (MALT).

collectively called **antigen-presenting cells (APCs)** because they display antigen fragments to other immune cells.

The macrophage system includes all of the body's phagocytic cells except leukocytes. Some of these phagocytes are wandering cells that actively seek pathogens; others are fixed in place and phagocytize only those pathogens that come to them—although they are strategically positioned for this to occur. Cells of the macrophage system include the macrophages of the loose connective tissue, *microglia* of the central nervous system, *alveolar macrophages* in the lungs, and *hepatic macrophages* in the liver. Alveolar and hepatic macrophages are described in chapters 23 and 24.

5. **Dendritic cells** are branched cells found in the epidermis, mucous membranes, and lymphatic organs. (In the skin, they are sometimes called *Langerhans*[6] *cells.*) They engulf foreign matter by receptor-mediated endocytosis rather than phagocytosis, but they otherwise function like macrophages and are included in the macrophage system.
6. **Reticular cells** are branched stationary cells that contribute to the stroma of the lymphatic organs and act as APCs in the thymus (see fig. 22.10). (They should not be confused with reticular *fibers,* which are fine branched collagen fibers common in lymphatic organs.)

Lymphatic Tissues

Lymphatic (lymphoid) tissues are aggregations of lymphocytes in the connective tissues of mucous membranes and various organs. The simplest form is **diffuse lymphatic tissue,** in which the lymphocytes are scattered rather than densely clustered. It is particularly prevalent in body passages that open to the exterior—the respiratory, digestive, urinary, and reproductive tracts—where it is called **mucosa-associated lymphatic tissue (MALT).**

In some places, lymphocytes and macrophages congregate in dense masses called **lymphatic nodules (follicles)** (fig. 22.8), which come and go as pathogens invade the tissues and the immune system answers the challenge. Abundant lymphatic nodules are, however, a relatively constant feature of the lymph nodes, tonsils, and appendix. In the ileum, the distal portion of the small intestine, they form clusters called **Peyer**[7] patches.

Overview of Lymphatic Organs

In contrast to the diffuse lymphatic tissue, **lymphatic (lymphoid) organs** have well-defined anatomical sites and at least partial connective tissue capsules that separate the lymphatic tissue from neighboring tissues. These organs include the red bone marrow, thymus, lymph nodes, tonsils, and spleen. The red bone marrow and thymus are regarded as *primary lymphatic organs* because they are the sites where B and T lymphocytes, respectively, become *immunocompetent*—that is, able to recognize and respond to antigens. The lymph nodes, tonsils, and spleen are called *secondary lymphatic organs* because they are populated with immunocompetent lymphocytes only after the cells have matured in the primary lymphatic organs.

Red Bone Marrow

Red bone marrow may not seem to be an organ; when aspirated from the bones for the purpose of biopsy or transfusion, it simply looks like extra-thick blood. Yet a careful microscopic examination of less disturbed marrow shows that it has a surprising degree of structure and is composed of multiple tissues, meeting the criteria of an organ, even if a very soft one.

---

[6] Paul Langerhans (1847–88), German anatomist

[7] Johann Conrad Peyer (1653–1712), Swiss anatomist

As discussed in chapter 7, there are two kinds of bone marrow: yellow and red. Yellow bone marrow is adipose tissue and can be disregarded for present purposes, but red bone marrow is involved in hemopoiesis (blood formation) and immunity. In children, it occupies the medullary spaces of nearly the entire skeleton. In adults, it is limited to parts of the axial skeleton and the proximal heads of the humerus and femur (see fig. 6.6, p. 138). Red bone marrow is an important supplier of lymphocytes to the immune system.

Red bone marrow is a soft, loosely organized, highly vascular material, separated from osseous tissue by the endosteum of the bone. It produces all classes of formed elements of the blood; its red color comes from the abundance of erythrocytes. Numerous small arteries enter *nutrient foramina* on the bone surface, penetrate the bone, and empty into large *sinusoids* in the marrow (fig. 22.9). The sinusoids drain into a *central longitudinal vein* that exits the bone via the same route that the arteries entered. The sinusoids, 45 to 80 μm wide, are lined by endothelial cells, like other blood vessels, and are surrounded by reticular connective tissue. The reticular cells secrete colony-stimulating factors that induce the formation of various leukocyte types. In the long bones of the limbs, aging reticular cells accumulate fat and transform into adipose cells, eventually replacing red bone marrow with yellow bone marrow.



Figure 22.9 **Histology of the Red Bone Marrow.** The formed elements of blood squeeze through the endothelial cells into the sinusoids, which converge on the central longitudinal vein at the lower left.

The spaces between the sinusoids are occupied by *islands (cords)* of hemopoietic cells, composed of macrophages and blood cells in all stages of development. The macrophages destroy malformed blood cells and the nuclei discarded by developing erythrocytes. As blood cells mature, they push their way through the reticular and endothelial cells to enter the sinus and flow away in the bloodstream. Platelets also enter the bloodstream in this way.

Apply What You Know

If we regard red bone marrow as a lymphatic organ and define lymphatic organs partly by the presence of a connective tissue capsule, what could we regard as the capsule of red bone marrow?

The Thymus

The **thymus** was introduced in chapter 18 because it is a member of both the endocrine and lymphatic systems. It houses developing lymphocytes and secretes hormones that regulate their later activity. It is a bilobed organ located between the sternum and aortic arch in the upper mediastinum (fig. 22.10). The two lobes are connected by a median bridge of tissue. In children, the organ is relatively firm and conical, much larger than it is in adults, and deep red due to its rich supply of blood vessels. After age 15 or so, it shrinks and contains less and less lymphatic tissue, and its color changes to gray and then yellowish as it becomes infiltrated with fat (see fig. 18.5, p. 505). In old age, it is barely distinguishable from the surrounding fat and fibrous tissue of the mediastinum.

The fibrous capsule of the thymus gives off trabeculae (septa) that penetrate into the gland and divide it into several angular lobules. Each lobule has a dense, dark-staining *cortex* and a lighter *medulla* inhabited by T lymphocytes (fig. 22.10b). **Reticular epithelial cells** and pericytes surround the blood capillaries of the cortex, forming a *blood–thymus barrier* that isolates immature lymphocytes from premature exposure to blood-borne antigens. The medulla exhibits whorls of keratinized cells called *thymic corpuscles,* which are useful for identifying the thymus histologically.

Reticular epithelial cells also secrete several signaling molecules that promote the development and action of T cells, including *thymosin, thymulin, thymopoietin, interleukins,* and *interferon*. If the thymus is removed from newborn mammals, they waste away and never develop immunity. Other lymphatic organs also seem to depend on thymosins or T cells and develop poorly in thymectomized animals. The relationship of T cell maturation to thymic histology is discussed later in this chapter.

Lymph Nodes

Lymph nodes are the most numerous lymphatic organs, numbering in the hundreds. They serve two functions: to cleanse the lymph and to act as a site of T and B cell activation. A lymph


Right lobe
Left lobe
Trabecula
Lobule
(a)
(b)
Trabecula
Cortex
Medulla
Reticular epithelial cells of cortex
T lymphocytes (thymocytes)
Macrophage
Capsule
Epithelium
Trabecula
Thymic corpuscle
Dendritic cell
Reticular epithelial cells of medulla
Medulla
Cortex
(c)

© McGraw-Hill Education/Dennis Strete, photographer

Figure 22.10 **The Thymus.** (a) Gross anatomy. (b) Histology. (c) Arrangement of the reticular epithelial cells to form the blood–thymus barrier separating the cortex from the medulla of one lobule.

• *Which of the cells in this organ secrete hormones?*

node is an elongated or bean-shaped structure, usually less than 3 cm long, often with an indentation called the **hilum** on one side (fig. 22.11). It is enclosed in a fibrous capsule with trabeculae that partially divide the interior of the node into compartments. Between the capsule and parenchyma is a narrow, relatively clear space called the **subcapsular sinus,** which contains reticular fibers, macrophages, and dendritic cells. Deep to this, the gland consists mainly of a stroma of reticular connective tissue (reticular fibers and reticular cells) and a parenchyma of lymphocytes and antigen-presenting cells.

The parenchyma is divided into an outer C-shaped **cortex** that encircles about four-fifths of the organ, and an inner **medulla** that extends to the surface at the hilum. The cortex consists mainly of ovoid to conical lymphatic nodules. When the lymph node is fighting a pathogen, these nodules acquire light-staining **germinal centers** where B cells multiply and differentiate into plasma cells. The medulla consists largely of a branching network of *medullary cords* composed of lymphocytes, plasma cells, macrophages, reticular cells, and reticular fibers. The cortex and medulla also contain lymph-filled sinuses continuous with the subcapsular sinus.

Several **afferent lymphatic vessels** lead into the node along its convex surface. Lymph flows from these vessels into the subcapsular sinus, percolates slowly through the sinuses of the cortex


Stroma:
Capsule
Reticular tissue
Trabecula
Cortex
Subcapsular sinus
Lymphatic nodule
Germinal center
Cortical sinuses
Medulla
Medullary sinus
Medullary cord
Afferent lymphatic vessels
(a)
Artery and vein
Efferent lymphatic vessel
Medullary cords
Medullary sinus
Macrophage
Trabecula
Lymphocytes
Reticular fibers
Venule
(b)
Lymphocytes
Reticular fibers
(c)
10 µm
© Francis Leroy, Biocosmos/Science Source

Figure 22.11 **Anatomy of a Lymph Node.** (a) Partially bisected lymph node showing pathway of lymph flow. (b) Detail of the boxed region in part (a). (c) Reticular fiber stroma and immune cells in a medullary sinus (SEM). APR

and medulla, and leaves the node through one to three **efferent lymphatic vessels** that emerge from the hilum. No other lymphatic organs have afferent lymphatic vessels; lymph nodes are the only organs that filter lymph as it flows along its course. With several afferent vessels but only a few efferent ones, the lymph node is a bottleneck that slows down lymph flow and allows time for cleansing it of foreign matter. The macrophages and reticular cells of the sinuses remove about 99% of the impurities before the lymph leaves the node. On its way to the bloodstream, lymph flows through one lymph node after another and thus becomes quite thoroughly cleansed of most impurities.

Blood vessels also penetrate the hilum of a lymph node. Arteries follow the medullary cords and give rise to capillary beds in the medulla and cortex. In the *deep cortex* near the junction with the medulla, lymphocytes can emigrate from the bloodstream into the parenchyma of the node. Most lymphocytes in the deep cortex are T cells.

Lymph nodes are widespread but especially concentrated in the following locations:

- *Cervical lymph nodes* occur in deep and superficial groups in the neck, and monitor lymph coming from the head and neck.
- *Axillary lymph nodes* are concentrated in the armpit (axilla) and receive lymph from the upper limb and the breast (see fig. 22.6b).
- *Thoracic lymph nodes* occur in the thoracic cavity and receive lymph from the lungs, airway, and mediastinum.

- *Abdominal lymph nodes* monitor lymph from the urinary and reproductive systems.
- *Intestinal* and *mesenteric lymph nodes* monitor lymph from the digestive tract (fig. 22.12a).
- *Inguinal lymph nodes* occur in the groin (fig. 22.12b) and receive lymph from the entire lower limb.
- *Popliteal lymph nodes* occur at the back of the knee and receive lymph from the leg proper.

Physicians routinely palpate the superficial lymph nodes of the cervical, axillary, and inguinal regions for swelling **(lymphadenitis[8]).** Lymph nodes are common sites of metastatic cancer (see Deeper Insight 22.1).

Tonsils

The **tonsils** are patches of lymphatic tissue located at the entrance to the pharynx, where they guard against ingested and inhaled pathogens. Each is covered by an epithelium and has deep pits called **tonsillar crypts** lined by lymphatic nodules (fig. 22.13). The crypts often contain food debris, dead leukocytes, bacteria, and antigenic chemicals. Below the crypts, the tonsils are partially separated from underlying connective tissue by an incomplete fibrous capsule.

There are three main sets of tonsils: (1) a single median **pharyngeal tonsil (adenoids)** on the wall of the pharynx just behind the nasal cavity; (2) a pair of **palatine tonsils** at the posterior margin of the oral cavity; and (3) numerous **lingual tonsils,** each with a single crypt, concentrated in a patch on each side of the root of the tongue (see fig. 24.5, p. 659).

DEEPER INSIGHT 22.1

Lymph Nodes and Metastatic Cancer

Metastasis is a phenomenon in which cancerous cells break free of the original *primary tumor,* travel to other sites in the body, and establish new tumors. Because of the high permeability of lymphatic capillaries, metastasizing cancer cells easily enter them and travel in the lymph. They tend to lodge in the first lymph node they encounter and multiply there, eventually destroying the node. Cancerous lymph nodes are swollen but relatively firm and usually painless. Cancer of a lymph node is called *lymphoma.*[9]

Once a tumor is well established in one node, cells may emigrate from there and travel to the next. However, if the metastasis is detected early enough, cancer can sometimes be eradicated by removing not only the primary tumor, but also the nearest lymph nodes downstream from that point. For example, breast cancer is often treated with a combination of lumpectomy or mastectomy along with removal of the nearby axillary lymph nodes.

The palatine tonsils are the largest and most often infected. *Tonsillitis* is an acute inflammation of the palatine tonsils, usually caused by a *Streptococcus* infection. Their surgical removal, called *tonsillectomy,*[10] used to be one of the most common surgical procedures performed on children, but it is done less often today. Tonsillitis is now usually treated with antibiotics.

Apply What You Know

Which tonsil(s) is or are most likely to be affected by an inhaled pathogen?

The Spleen

The **spleen** is the body's largest lymphatic organ, measuring up to 12 cm long and weighing about 150 g. It is located in the left hypochondriac region, just inferior to the diaphragm and posterolateral to the stomach (fig. 22.14; see also fig. A.6, p. 336). It is protected by ribs 10 through 12. The spleen fits snugly between the diaphragm, stomach, and kidney and has indentations called the *gastric area* and *renal area* where it presses against these adjacent viscera. It has a medial hilum penetrated by the splenic artery, splenic vein, and lymphatic vessels.

The parenchyma exhibits two types of tissue named for their appearance in fresh specimens (not in stained sections): **red pulp,** which consists of sinuses gorged with concentrated erythrocytes, and **white pulp,** which consists of lymphocytes and macrophages aggregated like sleeves along small branches of the splenic artery. In tissue sections, white pulp appears as an ovoid mass of lymphocytes with an arteriole passing through it. However, its three-dimensional shape is not egglike but cylindrical.

These two tissue types reflect the multiple functions of the spleen. Its blood capillaries are very permeable; they allow RBCs to leave the bloodstream, accumulate in the sinuses of the red pulp, and reenter the bloodstream later. The spleen is an "erythrocyte graveyard"—old, fragile RBCs rupture as they squeeze through the capillary walls into the sinuses. Macrophages phagocytize their remains, just as they dispose of blood-borne bacteria and other cellular debris. The spleen produces erythrocytes in the fetus and may resume this role in adults in the event of extreme anemia. Lymphocytes and macrophages of the white pulp monitor the blood for foreign agents, much like lymph nodes monitor the lymph. The spleen is a reservoir for a large "standing army" of monocytes, waiting in a state of emergency preparedness. In such events as microbial infection, myocardial infarction, or gaping wounds, the hormone angiotensin II stimulates the spleen to release great numbers of monocytes into the bloodstream. The monocytes help to combat infection and repair damaged tissues. The spleen also helps to stabilize blood volume by transferring excess plasma from the bloodstream into the lymphatic system.

---

[8] *adeno* = gland; *itis* = inflammation

[9] *oma* = tumor, mass

[10] *ec* = out; *tomy* = cutting


Transverse mesocolic lymph nodes
Colon
Superior mesenteric artery
Superior mesenteric lymph nodes
Inferior mesenteric artery
Ileocolic lymph nodes
Inferior mesenteric lymph nodes
Small intestine
Appendicular lymph nodes
Appendix
(a)


Internal abdominal oblique muscle
Superficial epigastric vein
Femoral nerve
Superficial inguinal lymph nodes
Femoral vein
Deep femoral artery
Femoral artery
Great saphenous vein
Sartorius muscle
(b)

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Figure 22.12 **Some Areas of Lymph Node Concentration.** (a) Mesenteric lymph nodes associated with the large intestine. (b) Inguinal lymph nodes in a female cadaver. APR



© Biophoto Associates/Science Source

Figure 22.13 **The Tonsils.** (a) Locations of the tonsils. (b) Histology of the palatine tonsil. APR

Apply What You Know

From an anatomical perspective, why are lymph nodes the only lymphatic organs that can filter the lymph?

Before You Go On

Answer the following questions to test your understanding of the preceding section:

4. What do T, B, and NK cells have in common? How do NK cells functionally differ from the other two? How do T and B cells functionally differ from each other?
5. What is the function of an antigen-presenting cell (APC)? Name three kinds of APCs.
6. What is a lymphatic nodule? Describe three places where lymphatic nodules can be found.
7. What are the two primary lymphatic organs? Why are they called that? Describe their collaborative relationship in producing the lymphocytes that populate other organs.
8. Describe the structural and functional differences between the cortex and medulla of a lymph node.
9. Name the three kinds of tonsils and state how they differ in number and location.
10. What are the two types of "pulp" in the spleen? What are their respective functions?
11. In what sense does the spleen serve the blood in the same way that the lymph nodes serve the lymph?

DEEPER INSIGHT 22.2

Splenectomy

A ruptured spleen is one of the most common consequences of blows to the left thoracic or abdominal wall, as in sports injuries and automobile accidents. It is especially likely to rupture if the lower ribs are fractured, and sometimes it is nicked during abdominal surgery. The spleen is such a pulpy and vascular organ that it bleeds profusely, and its capsule is so thin and delicate that it is difficult to repair surgically. To prevent fatal hemorrhaging, it is often necessary to quickly tie off the splenic artery and remove the spleen. This procedure is called *splenectomy.*

The loss of splenic function, called *hyposplenism,* is usually not serious; its functions are adequately carried out by hepatic and bone marrow macrophages. However, it does leave a person somewhat more at risk of septicemia (bacteria in the blood), pneumococcal infections, and premature death. Therefore, if possible, surgeons try to leave some of the spleen in place; the spleen regenerates rapidly in such cases.

Some people have overactive spleens *(hypersplenism),* in which excessive phagocytosis of the formed elements of blood can lead to anemia, leukopenia, or thrombocytopenia (see chapter 19). This can be another reason for performing a splenectomy.

Figure 22.14 **The Spleen.** (a) Position of the spleen in the upper left quadrant of the abdominal cavity. (b) Gross anatomy of the medial surface. (c) Histology.
- *What cells account for the different colors of the red pulp and white pulp?* AP|R


(a)
Diaphragm
Spleen
Splenic artery
Splenic vein
Pancreas
Kidney
Inferior vena cava
Aorta
Common iliac arteries
(b)
Superior
Gastric area
Hilum
Renal area
Splenic vein
Splenic artery
Inferior
(c)
Red pulp
Central artery (branching)
White pulp

© McGraw-Hill Education/Dennis Strete, photographer

© McGraw-Hill Education/Al Telser, photographer

22.3 The Lymphatic System in Relation to Immunity

Expected Learning Outcomes

When you have completed this section, you should be able to

a. define *immune system* and explain its relationship to the lymphatic system;
b. identify the body's three lines of defense against pathogens;
c. distinguish between nonspecific defense and adaptive immunity;
d. distinguish between humoral and cellular immunity; and
e. describe the life histories and immune functions of B cells and T cells, and how these relate to the anatomy of the lymphatic organs.

The **immune system** is not an organ system, but rather a population of disease-fighting cells that reside in the mucous membranes, lymphatic organs, and other localities in the body. Although it does not have a specific anatomy distinct from what we have already studied in this chapter, a brief survey of immune function will enhance your understanding of the defensive role of the lymphatic system.

Modes of Defense

We have three lines of defense against pathogens: (1) a system of physical barriers to invasion, chiefly the skin and mucous membranes; (2) a system of nonspecific actions against pathogens that get past the first defense; and (3) the immune system, which not only defeats the pathogen but "remembers" it, enabling the body to defeat it so quickly in future encounters that we never notice any symptoms of disease.

The first two defenses lack the capacity to remember a particular pathogen or to react to it differently in the future. Furthermore, they defend equally against a broad range of pathogens; thus, they are called **nonspecific defenses.** In addition to the skin and mucous membranes, these nonspecific defenses include neutrophils, macrophages, natural killer (NK) cells, various antimicrobial proteins such as interferons, and such processes as inflammation and fever.

The third defense confers a protection called **adaptive** or **specific immunity**—*adaptive* because the body adapts to a given pathogen and wards it off more easily in future exposures, and *specific* because the body must develop a separate immunity to each pathogen. For example, immunity to one disease, such as chickenpox, does not confer immunity against another, such as measles. The ability to distinguish one pathogen from another is based on their **antigens**—complex molecules such as proteins and glycoproteins that genetically distinguish organisms, and even different members of the same species, from each other and that trigger the immune response. The agents that carry out adaptive immune responses are T and B lymphocytes.

Some cells play roles in both adaptive and nonspecific defense—notably macrophages and helper T cells. Macrophages are fairly undiscriminating in the microbes they attack, but they also act to present foreign antigens to activate the lymphocytes of adaptive immunity. Helper T (T_H) cells activate not only the B and T_C cells of adaptive immunity, but also help to mediate the nonspecific inflammatory response.

There are two forms of adaptive immunity called *humoral* and *cellular immunity.* **Humoral (antibody-mediated) immunity** is carried out by B lymphocytes and antibodies. It is called *humoral* because the antibodies circulate freely in the body fluids; *humor* is an archaic term for a body fluid. **Cellular (cell-mediated) immunity** is carried out by cytotoxic T cells. We will not delve into the details of these defenses, but we will take a look at how the activities of B and T cells are related to the anatomy of the lymphatic organs. These lymphocytes are the most abundant cells of the lymphatic organs.

There are some things that B and T cells have in common, and we can address these before examining the differences in their life histories. Both types begin their development as *hemopoietic stem cells* (HSCs) in the red bone marrow. HSCs divide and give rise to *lymphocyte colony-forming units,* which ultimately produce B and T lymphocytes (see fig. 19.8, p. 531). Before they can take part in immune reactions, both types of lymphocytes must develop antigen receptors on their surfaces, giving them **immunocompetence**—the ability to recognize, bind, and respond to an antigen. In addition, the body must get rid of lymphocytes that react against its own (host) antigens so that the immune system will not attack one's own organs. The destruction or deactivation of self-reactive lymphocytes is called **negative selection.** Only about 2% of the lymphocytes survive this culling process. The developmental histories of B and T cells are contrasted in figure 22.15.

B Cells and Humoral Immunity

B cells achieve immunocompetence and go through negative selection in the red bone marrow. Many of the mature immunocompetent B cells remain there, while many more disperse and populate other sites such as the mucous membranes, spleen, and especially the cortical nodules of the lymph nodes, where they can sit and await the arrival of antigens in the incoming lymph.

The foundation of humoral immunity is the production of **antibodies**—proteins of the gamma globulin class (see p. 522) found in the blood, other body fluids, and surfaces of some immune cells. When a B cell encounters an antigen, it internalizes and digests it, and presents fragments of the antigen to a helper T cell. The helper T cell secretes chemical *helper factors* that stimulate the B cell to divide still more. Most of its daughter cells differentiate into **plasma cells,** which are larger than B cells and have an abundance of rough endoplasmic reticulum (fig. 22.16)—as well they might, for plasma cells secrete antibodies at the astounding rate of up to 2,000 molecules per second for a life span of 4 or 5 days. Plasma cells develop mainly in the germinal centers of the nodules of the lymph nodes. About 10% of them remain there, while the rest emigrate from the lymph nodes and populate the bone marrow and other lymphatic organs and tissues. Their antibodies travel throughout the body in the blood and other fluids and react in various ways against antigens that they encounter.

Instead of becoming plasma cells, some B cells become memory cells. These live for months to years, and respond very quickly if they ever encounter the same antigen again. This provides long-lasting immunity to that pathogen.

T Cells and Cellular Immunity AP|R

In early fetal development, immature T cell precursors migrate from the bone marrow to the cortex of the thymus, where they multiply and build up a large population. Branching reticular epithelial cells of the cortex contact nearly every one of these T cells and test their ability to respond to antigens. T cells that respond moderately are allowed to survive, whereas unresponsive cells, which would be useless for conferring immunity, die by apoptosis. This process is called **positive selection.**

The surviving T cells migrate to the medulla, where they undergo another test. Dendritic cells and macrophages of the medulla test their response to the body's own antigens. Overreactive cells are destroyed, preventing them from attacking one's own tissues and causing autoimmune diseases later. This is the *negative selection* described earlier. There is no blood–thymus barrier in the medulla, so the few remaining T cells can here enter the blood and lymphatic vessels and disperse throughout the body. They colonize the same sites as B cells do, including the red bone marrow. They become especially concentrated in the deep cortex of the lymph nodes.

When cytotoxic (T_C) cells encounter an enemy cell, they attack it directly and destroy it with a *lethal hit* of toxic chemicals. This is why immunity carried out by T cells is called *cellular (cell-mediated) immunity.* As in humoral immunity, some T cells remain as memory cells that live as long as a few decades and thus confer long-lasting protection.

Apply What You Know

Suppose a new virus emerged that selectively destroyed memory T and B cells. What would be the pathological effect of such a virus?


Key
Humoral immunity
Cellular immunity
(a)
(b)
B cells
Plasma cells
(b)
Tonsils
(c)
T stem cells
Lymph nodes
Spleen
(d)
(d)
(b)
Plasma cells
Immunocompetent T cells
Red bone marrow
Thymus
Other lymphatic tissues and organs

Figure 22.15 **The Life History and Migrations of B and T Cells.** Humoral immunity is represented by the violet pathways and cellular immunity by the red. (a) B cells achieve immunocompetence in the red bone marrow (left), and many emigrate to a variety of lymphatic tissues and organs, including the lymph nodes, tonsils, and spleen (right). (b) Plasma cells develop in the lymph nodes (among other sites) and emigrate to the bone marrow and other lymphatic organs, where they spend a few days secreting antibodies. (c) T stem cells emigrate from the bone marrow and attain immunocompetence in the thymus. (d) Immunocompetent T cells leave the thymus and recolonize the bone marrow or colonize various lymphatic organs (right).


Nucleus
Mitochondria
Rough endoplasmic reticulum
2 µm
2 µm

© Don W. Fawcett/Science Source **(a) B cell**

© Don W. Fawcett/Science Source **(b) Plasma cell**

Figure 22.16 **A B Cell and Plasma Cell.** (a) A B cell, with a nucleus occupying almost the entire cell volume. (b) A plasma cell, showing the extreme proliferation of rough endoplasmic reticulum in keeping with its protein- (antibody-) synthesizing function.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

12. What are the three lines of defense against pathogens?
13. How does adaptive immunity differ from nonspecific defense?
14. What is the difference between humoral and cellular immunity?
15. Where do B cells acquire immunocompetence? Where do T cells do so?
16. What are the structural and functional differences between a B cell and a plasma cell?

22.4 Developmental and clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the embryonic origins of the lymphatic organs;
b. describe changes in the lymphatic system that occur with old age; and
c. describe some common disorders of the lymphatic and immune systems.

Embryonic Development

Embryonic development of the thymus is described in chapter 18, page 514. Here, we will examine the development of the lymphatic vessels, lymph nodes, and spleen.

Lymphatic vessels begin as endothelium-lined channels in the mesoderm called **lymph sacs.** Some of these originate by budding from the blood vessels and then detaching from them; others originate as isolated mesodermal channels that fuse with each other and ultimately link up with the venous system. In a manner similar to blood vessel angiogenesis (see p. 601), lymph sacs proliferate, enlarge, and merge with each other to form larger and larger channels in the mesoderm (fig. 22.17a). Those with the greatest fluid flow later develop a tunica media and externa. The first to form are the *jugular lymph sacs* near the junction of the internal jugular and subclavian veins. By week 7, these sacs join the primitive veins and thus form the forerunners of the thoracic and right lymphatic ducts. The cisterna chyli arises from a *median lymph sac* that initially grows from the primitive vena cava and then breaks away from it. Smaller lymphatic vessels grow outward from the lymph sacs and follow blood vessels growing into the developing limbs.

Lymph nodes begin to develop as lymphocytes invade the lymph sacs and form cell clusters in the lumens. Blood vessels grow into these clusters, while a connective tissue capsule forms around them (fig. 22.17b).

The spleen develops from mesenchymal cells that invade the posterior mesentery leading to the stomach. Thus it remains enveloped in this mesentery and permanently connected to the stomach by a *gastrosplenic ligament.* The spleen is poorly developed at birth. Invasion of the splenic tissue by immunocompetent lymphocytes stimulates its postnatal development.

The Aging Lymphatic and Immune Systems

The effects of old age on the lymphatic system are seen not so much in anatomical changes as in declining immune function. There are several reasons for the reduced immune responsiveness. The quantities of red bone marrow and lymphatic tissue decline, so there are fewer hemopoietic stem cells, leukocytes, and antigen-presenting cells. As the thymus shrinks, the levels of thymic hormones decline. Perhaps because of this, an increasing percentage of lymphocytes fail to mature and achieve immunocompetence. There are fewer helper T cells, so both humoral and cellular immunity suffer from their absence. T_C cells are less responsive to antigens, and even antibody levels rise more slowly in response to infection. With fewer protective NK cells, cancer becomes more common in old age. Paradoxically, while normal antibody responses are weaker in old age, the level of circulating *autoantibodies* rises. These are antibodies that fail to distinguish between host and foreign antigens, and therefore attack the body's own tissues, causing a variety of *autoimmune*[11] *diseases* such as rheumatoid arthritis.

With reduced immunity in old age, infectious diseases can be not only more common but also more serious. Epidemics of influenza (flu), for example, take a disproportionate toll of lives among the elderly. It becomes increasingly important in old age to be vaccinated against such acute seasonal diseases.

Lymphatic and Immune Disorders

It is a delicate balancing act for the body to discriminate between foreign and host antigens, ward off foreign pathogens, and mount immune responses that are not too weak, not too strong, and not misdirected. It comes as no surprise, therefore, that many things can go wrong. Most immune disorders can be classified into three categories: autoimmune diseases, hypersensitivity, and immunodeficiency.

Autoimmune diseases, as already mentioned, are diseases resulting from an immune attack misdirected against one's own tissues. Insulin-dependent diabetes mellitus, rheumatic fever, rheumatoid arthritis, and systemic lupus erythematosus are some examples.

Hypersensitivity is an exaggerated, harmful immune response to antigens. The most prevalent examples are *allergies*—excessive reactions to environmental antigens *(allergens)* that most people tolerate. Allergens are found in a broad range of substances such as bee and wasp venoms; toxins from poison ivy and other plants; mold; dust; pollen; animal dander; foods such as nuts, milk, eggs, and shellfish; cosmetics; latex; vaccines; and drugs such as penicillin, tetracycline, and insulin. In many cases, an allergen stimulates

---

[11] *auto* = self



Figure 22.17 **Embryonic Development of the Lymphatic Vessels and Lymph Nodes.** (a) A 7-week embryo showing the right jugular lymph sac, which connects to the future subclavian vein; the primordial lymph sacs, which will merge to form the thoracic duct; and the median lymph sac, which will become the cisterna chyli. (b) Stages in the development of a lymph node. Top: Lymphocytes aggregate in a lymph sac, and blood vessels grow into the cluster. Middle: A fibrous capsule then forms around the sac as blood vessels proliferate. Bottom: Ingrowths of the capsule form trabeculae that partially subdivide the interior as the lymph node takes shape.

basophils and mast cells to release histamine and other chemicals that cause a broad range of symptoms: edema, congestion, watery eyes, runny nose, hives, cramps, diarrhea, vomiting, and sometimes catastrophic circulatory failure *(anaphylactic shock).*

Immunodeficiency diseases are failures of the immune system to respond strongly enough to ward off disease. One of these is a congenital (inborn) condition—*severe combined immunodeficiency disease (SCID),* in which an infant is born without a functional immune system and must live in a sterile enclosure to avoid fatal infections. The most notorious immunodeficiency disease, of course, is AIDS *(acquired immunodeficiency syndrome).* Unlike SCID, this is not inborn but results from an infection with the human immunodeficiency virus (HIV), usually acquired by sexual intercourse or use of contaminated needles for drug injection. HIV targets especially the helper T (CD4) cells. A normal T_H count is 600 to 1,200 cells/μL of blood; a criterion of AIDS is a count less than 200/μL. With such a severe depletion of T_H cells, a person is highly susceptible to *opportunistic infections*—infections that become established and produce disease only in people with weakened immune systems. In AIDS, some common examples are *Toxoplasma* (a protozoan that infects brain tissue), *Pneumocystis* (a group of respiratory fungi), *Candida* (a fungus that grows in white patches in the mouth), herpes simplex, cytomegalovirus, and tuberculosis. Opportunistic infection is the principal cause of death in AIDS.

A few more lymphatic system disorders are briefly described in table 22.1.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

17. How do lymph sacs form in the embryo? How do lymph nodes form?
18. Describe some reasons for the declining efficiency of the immune system in old age.
19. What are the three principal categories of immune system disorders? Give an example of each.

TABLE 22.1 Some Disorders of the Lymphatic System

Hodgkin[12] disease	A lymph node malignancy, with early symptoms including enlarged painful lymph nodes, especially in the neck; fever; anorexia; weight loss; night sweats; and severe itching. Diagnosis is confirmed by finding characteristic *Reed–Sternberg* cells in a lymph node biopsy. Often progresses to neighboring lymph nodes. Radiation and chemotherapy cure about three out of four patients.
Non-Hodgkin lymphoma	A lymphoma similar to Hodgkin disease, but more common, with more widespread distribution in the body (including axillary, inguinal, and femoral lymph nodes), and without Reed–Sternberg cells. Has a higher mortality rate than Hodgkin disease.
Lymphadenitis[13] (lim-FAD-en-EYE-tis)	Inflammation of a lymph node in response to challenge from a foreign antigen; marked by swelling and tenderness.
Lymphadenopathy[14] (lim-FAD-en-OP-a-thee)	Collective term for all diseases of the lymph nodes.
Lymphangitis[15] (LIM-fan-JY-tis)	Inflammation of a lymphatic vessel; marked by redness and pain along the course of the vessel.
Splenomegaly[16]	Enlargement of the spleen, sometimes without underlying disease but often indicating infections, autoimmune diseases, heart failure, cirrhosis, Hodgkin disease, and other cancers. The enlarged spleen may "hoard" erythrocytes, causing anemia, and it may become fragile and subject to rupture.

Disorders Described Elsewhere

AIDS	627	Opportunistic infection	627
Allergy	626	Ruptured spleen	622
Autoimmune diseases	626	Severe combined immunodeficiency disease	627
Cancer of lymph nodes	620	Tonsillitis	620

---

[12] Thomas Hodgkin (1798–1866), British physician
[13] *adeno* = gland; *itis* = inflammation
[14] *adeno* = gland; *pathy* = disease
[15] *ang* = vessel; *itis* = inflammation
[16] *megaly* = enlargement

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

22.1 Lymph and Lymphatic Vessels (p. 610)

1. The anatomical components of the lymphatic system
2. Three functions of the lymphatic system
3. The appearance and composition of the lymph
4. Structure of the lymphatic capillaries and how their structure enables them to pick up large particles from the tissue fluid
5. Histology of the lymphatic collecting vessels and their anatomical and functional relationships with the lymph nodes
6. The larger lymphatic vessels including the 11 lymphatic trunks, the two collecting ducts, and the points where the lymph is returned to the bloodstream
7. The mechanisms for making the lymph flow through the lymphatic vessels and for preventing it from going backward

22.2 Lymphatic Cells, Tissues, and Organs (p. 615)

1. The six principal defensive cell types in the lymphatic system
2. The function of NK cells
3. The four kinds of T lymphocytes, their functions, and what the *T* in their names stands for

4. The function of B lymphocytes, their relationship to plasma cells, and what the *B* stands for
5. The functions and types of macrophages, and their relation to blood monocytes
6. The locations and functions of dendritic cells and reticular cells
7. The histology, locations, and types of diffuse lymphatic tissue
8. The feature that distinguishes lymphatic organs from lymphatic tissues
9. The distinction between primary and secondary lymphatic organs, and the members of each category
10. The structure and function of red bone marrow and the reason it can be considered an organ and not merely a tissue
11. The location, gross anatomy, histology, and functions of the thymus, and its age-related changes
12. The gross anatomy, histology, and functions of a lymph node
13. The locations of lymph nodes and the names of the body's major lymph node aggregations
14. The names, locations, and functions of the tonsils, and the structural differences between the three types of tonsils
15. The location, gross anatomy, histology, and functions of the spleen

22.3 The Lymphatic System in Relation to Immunity (p. 623)

1. The definition of *immune system* and why this is not considered an organ system
2. The body's three lines of defense against pathogens and the distinction between nonspecific defense and adaptive immunity
3. The nature of antigens and their role in immune function
4. The multiple mechanisms of nonspecific defense
5. A definition of *adaptive immunity,* the two forms of adaptive immunity, and the agents that carry out each of these forms
6. The origin of B and T cells and the essential processes that both of these must go through before they are capable of participating in an immune response
7. Where the B cells become immunocompetent and where they subsequently reside
8. How B cells respond when they encounter a foreign antigen, and how they provide an immune memory in humoral immunity
9. Where the T cells become immunocompetent and where they subsequently reside
10. How T cells respond when they encounter an enemy cell, and how they provide an immune memory in cellular immunity

22.4 Developmental and Clinical Perspectives (p. 626)

1. How lymphatic vessels, lymph nodes, and the spleen develop in the human embryo
2. How the lymphatic tissues and immune responses change in old age, and why elderly people are more susceptible to infectious diseases, cancer, and autoimmune diseases
3. The three principal classes of immune system disorders
4. The cause of AIDS and the essential cellular mechanism of how it produces the signs and symptoms of this disease

Testing Your Recall

1. The only lymphatic organ with both afferent and efferent lymphatic vessels is
   a. the spleen.
   b. a lymph node.
   c. a tonsil.
   d. a Peyer patch.
   e. the thymus.
2. Which of the following cells are involved in nonspecific defense but not in adaptive immunity?
   a. helper T cells
   b. cytotoxic T cells
   c. natural killer cells
   d. B cells
   e. plasma cells
3. The lethal hit is used by _____ to kill enemy cells.
   a. neutrophils
   b. basophils
   c. mast cells
   d. NK cells
   e. cytotoxic T cells
4. Which of these is a macrophage?
   a. microglia
   b. a plasma cell
   c. a reticular cell
   d. a helper T cell
   e. a mast cell
5. Which of these lymphatic organs has a cortex and medulla: (I) spleen; (II) lymph node; (III) thymus; (IV) red bone marrow?
   a. II only
   b. III only
   c. II and III only
   d. III and IV only
   e. I, II, and III
6. What cells form the blood–thymus barrier?
   a. astrocytes
   b. Hassall corpuscles
   c. T cells
   d. dendritic cells
   e. reticular epithelial cells
7. Where do B cells attain immunocompetence?
   a. in the red bone marrow
   b. in the germinal centers of the lymph nodes
   c. in the thymic cortex
   d. in the thymic medulla
   e. in the splenic white pulp
8. If not for the process of negative selection, we would expect to see more
   a. allergies.
   b. lymphatic nodules in the MALT.
   c. antigen-presenting cells.
   d. immunodeficiency diseases.
   e. autoimmune diseases.
9. Lymph nodes tend to be especially concentrated in all of these sites *except*
   a. the cervical region.
   b. the popliteal region.
   c. the carpal region.
   d. the inguinal region.
   e. the mesenteries.
10. All lymph ultimately reenters the bloodstream at what point?
    a. the right atrium
    b. the common carotid arteries
    c. the internal iliac veins
    d. the subclavian veins
    e. the inferior vena cava
11. Any microorganism capable of causing disease is called a/an _____.
12. _____ is milky lymph, rich in fat, absorbed from the small intestine.

13. Lymphatic vessels called _____ carry lymph from one lymph node to the next.
14. The two lymphatics that empty into the subclavian veins are the _____ on the right and the _____ on the left.
15. The latter duct in question 14 begins with a sac called the _____ below the diaphragm.
16. B cells become _____ cells before they begin to secrete antibodies.
17. Any cells that process antigens and display fragments of them to activate immune reactions are called _____.
18. The _____ is a lymphatic organ composed mainly of hemopoietic islands and sinusoids.
19. The ovoid masses of lymphocytes that line the tonsillar crypts are called _____.
20. Any disease in which antibodies attack one's own tissues is called a/an _____ disease.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. -gen
2. -itis
3. adeno-
4. -ectomy
5. -pathy
6. lympho-
7. immuno-
8. -megaly
9. -oma
10. chylo-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. B cells play roles in both nonspecific defense and adaptive immunity.
2. T lymphocytes undergo negative selection in the thymus.
3. Lymphatic capillaries are more permeable than blood capillaries.
4. T lymphocytes are involved only in cellular immunity.
5. The white pulp of the spleen gets its color mainly from lymphocytes and macrophages.
6. Obstruction of a major lymphatic vessel is likely to cause edema.
7. Lymph nodes are populated by B cells but not T cells.
8. Lymphatic nodules are permanent structures enclosed in fibrous capsules.
9. Tonsillectomy is regarded as the current treatment of choice for most cases of tonsillitis.
10. Most plasma cells form in the germinal centers of the lymph nodes.

Answers in appendix A

Testing Your Comprehension

1. About 10% of people have one or more *accessory spleens,* typically about 1 cm in diameter and located near the hilum of the main spleen or embedded in the tail of the pancreas. If a surgeon is performing a splenectomy as a treatment for hypersplenism (see Deeper Insight 22.2), why would it be important to search for and remove any accessory spleens? What might be the consequences of overlooking one of these?
2. In treating a woman for malignancy in the right breast, the surgeon removes some of her axillary lymph nodes. Following surgery, the patient experiences edema of her right arm. Explain why.
3. Explain why a detailed knowledge of the pathways of lymphatic drainage is important to the clinical management of cancer.
4. A burn research center uses mice for studies of skin grafting. To prevent graft rejection, the mice are thymectomized at birth. Even though B cells do not develop in the thymus, these mice show no humoral immune response and are very susceptible to infection. Explain why the removal of the thymus would improve the success of skin grafts but adversely affect humoral immunity.
5. Contrast the structure of a B cell with that of a plasma cell, and explain how their structural difference relates to their functional difference.



© Mediscan/Alamy

The bronchial trees, with each bronchopulmonary segment shown in a different color (polymer cast)

CHAPTER 23

THE RESPIRATORY SYSTEM

CHAPTER OUTLINE

23.1 Overview of the Respiratory System 632

23.2 The Upper Respiratory Tract 633
- The Nose 633
- The Pharynx 635
- The Larynx 635

23.3 The Lower Respiratory Tract 637
- The Trachea and Bronchi 638
- The Lungs 639
- The Pleurae 642

23.4 Neuromuscular Aspects of Respiration 643
- The Respiratory Muscles 643
- Respiratory Neuroanatomy 645

25.4 Developmental and Clinical Perspectives 647
- Prenatal and Neonatal Development 647
- The Aging Respiratory System 649
- Respiratory Pathology 649

Study Guide 650

DEEPER INSIGHTS

23.1 Tracheostomy 639
23.2 Pulmonary Collapse 643
23.3 Ondine's Curse 645
23.4 Premature Birth and Respiratory Distress Syndrome 648

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:

- Serous and mucous membranes (p. 78)
- The ethmoid bone, maxilla, nasal bones, and vomer (pp. 162–165)
- Basic brainstem anatomy (pp. 406–410)
- Divisions of the autonomic nervous system (p. 444)
- Pulmonary blood circulation (p. 572)

Anatomy & Physiology REVEALED®
aprevealed.com

Module 11: Respiratory System

Breath represents life. The first breath of a baby and the last gasp of a dying person are two of the most dramatic moments of human experience. But why must we breathe? It comes down to the fact that most of our metabolism directly or indirectly requires ATP. Most ATP synthesis requires oxygen and generates carbon dioxide—thus driving the need to breathe in order to supply the former and eliminate the latter. The respiratory system consists essentially of tubes that deliver air to the lungs, where oxygen diffuses into the blood and carbon dioxide is removed from it.

The respiratory and cardiovascular systems have such a close functional and spatial relationship that a disorder of the lungs often has direct effects on the heart, and vice versa. The two systems are often considered jointly as the *cardiopulmonary system.*

23.1 Overview of the Respiratory System

Expected Learning Outcomes

When you have completed this section, you should be able to

a. state the functions of the respiratory system;
b. name the principal organs of this system;
c. distinguish between the conducting and respiratory divisions; and
d. distinguish between the upper and lower respiratory tracts.

The **respiratory system** is an organ system specialized to provide oxygen to the blood and remove carbon dioxide from it. It has more diverse functions than are commonly supposed:

1. **Gas exhange.** It provides for oxygen and carbon dioxide exchange between the blood and air.
2. **Communication.** It serves for speech and other vocalizations (laughing, crying).
3. **Olfaction.** It provides the sense of smell, which is important in social interactions, food selection, and avoiding danger (such as a gas leak or spoiled food).
4. **Acid–base balance.** By eliminating CO_2, it helps to control the pH of the body fluids. Excess CO_2 reacts with water and releases hydrogen ions:

   $$CO_2 + H_2O \longrightarrow H_2CO_3 \longrightarrow HCO_3^- + H^+$$

   Therefore, if the respiratory system does not keep pace with the rate of CO_2 production, H^+ accumulates and the body fluids have an abnormally low pH *(acidosis).*
5. **Blood pressure regulation.** The lungs carry out a step in the synthesis of a vasoconstrictor called *angiotensin II,* which helps to regulate blood pressure.
6. **Blood and lymph flow.** Breathing creates pressure gradients between the thorax and abdomen that promote the flow of lymph and venous blood.
7. **Expulsion of abdominal contents.** Taking a deep breath and holding it while contracting the abdominal muscles (the *Valsalva*[1] *maneuver*) helps to expel abdominal contents during urination, defecation, and childbirth.

The principal organs of the respiratory system are the nose, pharynx, larynx, trachea, bronchi, and lungs (fig. 23.1). Within the lungs, air flows along a dead-end pathway consisting essentially of bronchi ⟶ bronchioles ⟶ alveoli (with some details to be introduced later). During **inspiration**[2] (inhaling), incoming air stops in the *alveoli* (millions of thin-walled, microscopic air sacs) and exchanges gases with the bloodstream across the alveolar wall; it flows back out during **expiration** (exhaling).

The **conducting division** of the respiratory system consists of those passages that serve only for airflow, essentially from the nostrils through the bronchioles. No gases are exchanged with the blood in these passages because their walls are too thick to allow for sufficiently rapid gas diffusion. The **respiratory division** consists of the alveoli and other distal gas-exchange regions. The airway from the nose through the larynx is often called the **upper respiratory tract**



Figure 23.1 The Respiratory System. AP|R

---

[1] Antonio Maria Valsalva (1666–1723), Italian anatomist
[2] *spir* = to breathe

(that is, the respiratory organs in the head and neck), and the regions from the trachea through the lungs compose the **lower respiratory tract** (the respiratory organs of the thorax). However, these are inexact terms and various authorities place the dividing line between the upper and lower tracts at different points.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. What are some functions of the respiratory system other than supplying O_2 to the body and removing CO_2?
2. Which portions of the respiratory tract belong to the conducting division? What portions belong to the respiratory division? How do the two divisions differ functionally?
3. What is the distinction between the upper and lower respiratory tracts?

23.2 The Upper Respiratory Tract

Expected Learning Outcomes

When you have completed this section, you should be able to

a. trace the flow of air from the nose through the larynx;
b. describe the anatomy of these passages;
c. relate the anatomy of any portion of the upper respiratory tract to its function; and
d. describe the action of the vocal cords in speech.

The Nose

The **nose** has several functions: It warms, cleanses, and humidifies inhaled air; it detects odors in the airstream; and it serves as a resonating chamber that amplifies the voice. It extends from a pair of anterior openings called the **nostrils,** or **nares** (NAIR-eze) (singular, *naris*), to a pair of posterior openings called the **posterior nasal apertures** or **choanae**[3] (co-AH-nee) (fig. 23.2b).

The facial part of the nose is shaped by bone and hyaline cartilage. Its superior half is supported by a pair of small nasal bones medially and the maxillae laterally. The inferior half is supported by the **lateral** and **alar cartilages** (fig. 23.3). By palpating your own nose, you can easily find the boundary between the bone of the nasal bridge and the more flexible cartilage below. The flared portion at the lower end of the nose, called the **ala nasi**[4] (AIL-ah NAZE-eye), is shaped by the alar cartilages and dense connective tissue.

The **nasal cavity** begins with a small dilated chamber called the **vestibule** just inside each nostril, bordered by the ala nasi. This space is lined with stratified squamous epithelium like the facial skin and has stiff **guard hairs,** or **vibrissae** (vy-BRISS-ee), that block insects and large airborne particles from the nose. The nasal cavity is divided into right and left halves called **nasal fossae** (FAW-see) by a wall of bone and hyaline cartilage, the **nasal septum.** The septum has three components: the bony *vomer* forming the inferior part, the perpendicular plate of the *ethmoid bone* forming the superior part, and a hyaline *septal nasal cartilage* forming the anterior part. The roof of the nasal cavity is formed by the ethmoid and sphenoid bones, and the hard palate forms its floor. The palate separates the nasal cavity from the oral cavity and allows you to breathe while chewing food (see Deeper Insight 7.2, p. 165). The nasal cavity receives drainage from the paranasal sinuses (see p. 155) and the nasolacrimal ducts of the orbits (see p. 480).

There is not much space in the nasal cavity. Most of it is occupied by three bony scrolls covered by mucous membrane—the **superior, middle,** and **inferior nasal conchae**[5] (CON-kee), or **turbinates**—that project from the lateral walls toward the septum (fig. 23.2). Beneath each concha is a narrow air passage called a **meatus**[6] (me-AY-tus). The narrowness of these passages and the turbulence produced by the conchae ensure that most air contacts the mucous membrane on its way through. As it does, most dust in the air sticks to the mucus, and the air picks up moisture and heat from the mucosa. The conchae thus enable the nose to cleanse, warm, and humidify the air more effectively than if the air had an unobstructed flow through a cavernous space.

Odors are detected by sensory cells in the **olfactory epithelium,** which covers a small area of the roof of the nasal fossa and adjacent parts of the septum and superior concha (see fig. 17.7, p. 469). The rest of the nasal cavity, except for the vestibule, is lined with **respiratory epithelium.** Both of these are ciliated pseudostratified columnar epithelia. However, in the olfactory epithelium, the cilia are immobile and serve to bind odor molecules. In the respiratory epithelium, they are mobile and serve to move the nasal mucus. The respiratory epithelium is similar to the one seen in figure 3.7 (p. 59). Its wineglass-shaped **goblet cells** secrete mucus, and its **ciliated cells** propel it posteriorly toward the pharynx. The mucosa also contains mucous glands in the lamina propria (the connective tissue layer beneath the epithelium). They supplement the mucus produced by the goblet cells. Inhaled dust, pollen, bacteria, and other foreign matter stick to the mucus and are swallowed; they are either digested or pass through the digestive tract rather than contaminating the lungs. The lamina propria is also well populated by lymphocytes that mount immune defenses against inhaled pathogens, and by plasma cells that secrete antibodies into the tissue fluid.

The lamina propria contains large blood vessels that help to warm the air. The inferior concha has an especially extensive venous plexus called the **erectile tissue (swell body).** Every 30 to 60 minutes, the erectile tissue on one side becomes engorged with blood and restricts airflow through that fossa. Most air is then directed through the other nostril and fossa, allowing the engorged side time to recover from drying. Thus, the preponderant flow of air shifts between the right and left nostrils once or twice each hour.

---

[3] *choana* = funnel
[4] *ala* = wing; *nasi* = of the nose
[5] *concha* = seashell
[6] *meatus* = passage


Frontal sinus
Nasal conchae:
Superior
Middle
Inferior
Meatuses
Hard palate
Tongue
Larynx:
Epiglottis
Vestibular fold
Vocal cord
Trachea
(a)
Cribriform plate
Auditory tube
Sites of respiratory control nuclei:
Pons
Medulla oblongata
Nasopharynx
Uvula
Oropharynx
Laryngopharynx
Vertebral column
Esophagus
Frontal sinus
Nasal conchae:
Superior
Middle
Inferior
Vestibule
Guard hairs
Naris (nostril)
Hard palate
Upper lip
Tongue
Lower lip
Mandible
Vestibular fold
Vocal cord
Larynx
(b)
Meatuses:
Superior
Middle
Inferior
Sphenoid sinus
Posterior nasal aperture
Pharyngeal tonsil
Auditory tube
Soft palate
Uvula
Palatine tonsil
Lingual tonsil
Epiglottis
Trachea
Esophagus
Nasal septum:
Perpendicular plate
Septal cartilage
Vomer
Pharynx:
Nasopharynx
Oropharynx
Laryngopharynx
(c)

©McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Figure 23.2 **Anatomy of the Upper Respiratory Tract.** (a) Median section of the head. (b) Internal anatomy. (c) Regions of the pharynx.

- *Draw a line across part (b) of this figure to indicate the boundary between the upper and lower respiratory tracts.*



© McGraw-Hill Education/Joe De Grandis, photographer



© McGraw-Hill Education/Joe De Grandis, photographer

Figure 23.3 **Anatomy of the Nasal Region.** (a) External anatomy. (b) Connective tissues that shape the nose.

- *Which of the cartilages in part (b) extends most deeply into the face?*

The Pharynx

The **pharynx** (FAIR-inks), or throat, is a muscular funnel extending about 13 cm (5 in.) from the choanae to the larynx. It has three regions: the *nasopharynx, oropharynx,* and *laryngopharynx* (fig. 23.2c).

The **nasopharynx** lies posterior to the choanae and soft palate. It receives the auditory (eustachian) tubes from the middle ears and houses the pharyngeal tonsil. Inhaled air turns 90° downward as it passes through the nasopharynx. Relatively large particles (>10 µm) generally cannot make the turn because of their inertia. They collide with the posterior wall of the nasopharynx and stick to the mucosa near the tonsil, which is well positioned to respond to airborne pathogens.

The **oropharynx** is a space posterior to the root of the tongue. It extends from the inferior tip of the soft palate to the superior tip of the epiglottis. Its anterior border is formed by the base of the tongue and the *fauces* (FAW-seez), the opening of the oral cavity into the pharynx.

The **laryngopharynx** (la-RIN-go-FAIR-inks) begins at the tip of the epiglottis, passes downward posterior to the larynx, and ends where the esophagus begins at the level of the *cricoid cartilage* (described shortly).

The nasopharynx passes only air and is lined by pseudostratified columnar epithelium, whereas the oropharynx and laryngopharynx pass air, food, and drink and are lined by stratified squamous epithelium. Muscles of the pharynx play necessary roles in swallowing and speech.

The Larynx

The **larynx** (LAIR-inks) ("voice box") is a cartilaginous chamber about 4 cm long (fig. 23.4). Its primary function is to keep food and drink out of the airway, but it has evolved the additional role of sound production *(phonation)* in many animals, including humans.

The superior opening of the larynx is guarded by a flap of tissue called the **epiglottis**[7] (figs. 23.4c and 23.5a). At rest, the epiglottis usually stands almost vertically. During swallowing, however, *extrinsic muscles* of the larynx pull the larynx upward toward the epiglottis, the tongue pushes the epiglottis downward to meet it, and the epiglottis closes the airway and directs food and drink into the esophagus behind it.

In infants, the larynx is relatively high in the throat, and the epiglottis touches the soft palate. This creates a more or less continuous airway from the nasal cavity to the larynx and allows an infant to breathe continually while swallowing. The epiglottis deflects milk away from the airstream, like rain running off a tent while it remains dry inside. By age 2, the root of the tongue becomes more muscular and forces the larynx to descend to a lower position. It then becomes impossible to breathe and swallow at the same time without choking.

The framework of the larynx consists of nine cartilages. The first three are solitary and relatively large. The most superior one, the **epiglottic cartilage,** is a spoon-shaped supportive plate in the epiglottis. The largest, the **thyroid**[8] **cartilage,** is named for its shieldlike shape. It broadly covers the anterior and lateral aspects of the larynx. The "Adam's apple" is an anterior peak of the thyroid cartilage called the *laryngeal prominence.* Testosterone stimulates the growth of this prominence, which is therefore larger in males than in females. Inferior to the thyroid cartilage is a ringlike **cricoid**[9] (CRY-coyd) **cartilage.** The thyroid and cricoid cartilages essentially constitute the "box" of the voice box.

The remaining cartilages are smaller and occur in three pairs. Posterior to the thyroid cartilage are the two **arytenoid**[10] (AR-ih-TEE-noyd) **cartilages,** and attached to their upper ends is a pair of little horns, the **corniculate**[11] (cor-NICK-you-late)

---

[7] *epi* = above, upon; *glottis* = back of the tongue
[8] *thyr* = shield; *oid* = resembling
[9] *crico* = ring; *oid* = resembling
[10] *aryten* = ladle; *oid* = resembling
[11] *corni* = horn; *cul* = little; *ate* = possessing


Epiglottis
Hyoid bone
Thyrohyoid ligament
Thyroid cartilage
Laryngeal prominence
Arytenoid cartilage
Cricoid cartilage
Cricotracheal ligament
Trachea
Epiglottis
Hyoid bone
Epiglottic cartilage
Fat pad
Thyroid cartilage
Cuneiform cartilage
Corniculate cartilage
Vestibular fold
Vocal cord
Arytenoid cartilage
Arytenoid muscle
Cricoid cartilage
Tracheal cartilage

(a) Anterior **(b) Posterior** **(c) Median**

Figure 23.4 **Anatomy of the Larynx.** Most muscles are removed in order to show the cartilages.
• *What three cartilages in this figure are more mobile than any other?* AP|R

cartilages. The arytenoid and corniculate cartilages function in speech, as explained shortly. A pair of **cuneiform**[12] (cue-NEE-ih-form) **cartilages** supports the soft tissues between the arytenoids and epiglottis.

A group of fibrous ligaments bind the cartilages of the larynx together and form a suspension system for the upper airway. A broad sheet called the **thyrohyoid ligament** suspends the larynx from the hyoid bone above it, and below, the **cricotracheal ligament** suspends the trachea from the cricoid cartilage. These are collectively called *extrinsic ligaments* because they link the larynx to these other organs. The *intrinsic ligaments* are contained entirely within the larynx and link its nine cartilages to each other.

The walls of the larynx are also quite muscular. The deep *intrinsic muscles* operate the vocal cords, and the superficial *extrinsic muscles* connect the larynx to the hyoid bone and elevate the larynx during swallowing. The extrinsic muscles, also called the *infrahyoid group,* are named and described in table 11.3 (p. 275).

Within the larynx, two fibrous **vestibular ligaments** stretch like a V from the midpoint of the thyroid cartilage in front to two small cartilages posteriorly (fig. 23.5a). They support the **vestibular folds,** which close the larynx during swallowing to protect against choking. Inferior and parallel to these are the **vocal ligaments,** which support the **vocal cords (vocal folds).** The vocal cords and the opening between them are collectively called the **glottis.** The vocal cords are covered with stratified squamous epithelium, best suited to endure vibration and contact between the cords that occur during speech.

---

[12] *cune* = wedge; *form* = shape


Anterior
Epiglottis
Glottis
Vestibular fold
Vocal cord
Trachea
Corniculate cartilage
Posterior
(a)
Main bronchi
Carina
Tracheal mucosa
(b)

© CNRI/Science Source

© BSIP/Newscom

Figure 23.5 **Endoscopic Views of the Respiratory Tract.** (a) Superior view of the larynx, seen with a laryngoscope. (b) The tracheal bifurcation, where its inferior end branches into the right and left main bronchi, seen with a bronchoscope.

The intrinsic muscles control the vocal cords by pulling on the corniculate and arytenoid cartilages, causing the cartilages to pivot. Depending on their direction of rotation, the arytenoid cartilages abduct or adduct the vocal cords (fig. 23.6). Air forced between the adducted vocal cords vibrates them, producing a high-pitched sound when the cords are relatively taut and a lower-pitched sound when they are more relaxed. In adult males, the vocal cords are longer and thicker, vibrate more slowly, and produce lower-pitched sounds than in females. Loudness is determined by the force of the air passing between the vocal cords. Although the vocal cords produce most sound, they do not produce intelligible speech. The crude sounds coming from the larynx have been likened to a hunter's duck call. They are formed into words by actions of the pharynx, oral cavity, tongue, and lips.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

4. Describe the histology of the mucous membrane of the nasal cavity and the functions of the cell types present.
5. Name the anterior and posterior openings that mark the beginning and end of the nasal cavity.
6. What are the right and left halves of the nasal cavity called? What are the three scroll-like folds on the wall of each nasal fossa called? What is their function?
7. Palpate two of your laryngeal cartilages and name them. Name the ones that are impossible to palpate on a living person.
8. Describe the roles of the intrinsic muscles, corniculate cartilages, and arytenoid cartilages in speech.

23.3 The Lower Respiratory Tract

Expected Learning Outcomes

When you have completed this section, you should be able to

a. trace the flow of air from the trachea to the pulmonary alveoli;
b. describe the anatomy of these passages;
c. relate the gross anatomy of any portion of the lower respiratory tract to its function;
d. relate the microscopic anatomy of the pulmonary alveoli to their role in gas exchange; and
e. describe the relationship of the pleurae to the lungs.


Adduction of vocal cords
Abduction of vocal cords
Thyroid cartilage
Cricoid cartilage
Vocal cord
Lateral cricoarytenoid muscle
Arytenoid cartilage
Corniculate cartilage
Posterior cricoarytenoid muscle
Anterior
Posterior
(a)
(c)
Base of tongue
Epiglottis
Vestibular fold
Vocal cord
Glottis
Corniculate cartilage
(b)
(d)

Figure 23.6 **Action of Some of the Intrinsic Laryngeal Muscles on the Vocal Cords.** (a) Adduction of the vocal cords by the lateral cricoarytenoid muscles. (b) Adducted vocal cords seen with the laryngoscope. (c) Abduction of the vocal cords by the posterior cricoarytenoid muscles. (d) Abducted vocal cords seen with the laryngoscope.

If you palpate your larynx, you will find the laryngeal prominence of the thyroid cartilage only slightly above your sternum. Most of the rest of the respiratory tract is in the thorax rather than the head and neck, and is thus called the lower respiratory tract. This portion extends from the trachea to the pulmonary alveoli.

The Trachea and Bronchi

The **trachea** (TRAY-kee-uh), or "windpipe," is a tube about 12 cm (4.5 in.) long and 2.5 cm (1 in.) in diameter, lying anterior to the esophagus (fig. 23.7a). It is supported by 16 to 20 C-shaped rings of hyaline cartilage, some of which you can palpate between your larynx and sternum. The inner lining of the trachea is a pseudostratified columnar epithelium composed mainly of mucus-secreting goblet cells, ciliated cells, and short basal stem cells (figs. 23.7b and 23.8). The mucus traps inhaled particles, and the upward beating of the cilia drives the debris-laden mucus toward the pharynx, where it is swallowed. This mechanism of debris removal is called the **mucociliary escalator.**

The connective tissue beneath the tracheal epithelium contains lymphatic nodules, mucous and serous glands, and the tracheal cartilages. Like the wire spiral in a vacuum cleaner hose, the cartilage rings reinforce the trachea and keep it from collapsing when you inhale. The word *trachea*[13] refers to the rough, corrugated surface texture imparted by these cartilage rings. The open part of the C faces posteriorly and allows room for the esophagus to expand as swallowed food passes by. The gap is spanned by smooth muscle tissue called the **trachealis** (fig. 23.7c). Contraction or relaxation of this muscle narrows or widens the trachea to adjust airflow for conditions of rest or exercise. The outermost layer of the trachea, called the **adventitia,** is fibrous connective tissue that blends into the adventitia of other organs of the mediastinum.

At the level of the sternal angle and the superior margin of vertebra T5, the trachea forks into right and left bronchi. The lowermost tracheal cartilage has an internal median ridge called the **carina**[14] (ca-RY-na) that directs the airflow to the right and left (see fig. 23.5b). The bronchi are further traced in the discussion of the *bronchial tree* of the lungs.

---

[13] *trache* = rough
[14] *carina* = keel


Larynx
Thyroid cartilage
Cricoid cartilage
Trachea
Carina
Lobar bronchi
Main bronchi
Segmental bronchi
(a)
Mucus
Mucociliary escalator
Particles of debris
Epithelium:
Goblet cell
Ciliated cell
Mucous gland
Cartilage
Chondrocytes
(b)
Trachealis muscle
Hyaline cartilage ring
Lumen
Mucosa
Mucous gland
Perichondrium
Posterior
Anterior
(c)

Figure 23.7 **Anatomy of the Lower Respiratory Tract.** (a) Anterior view. (b) Longitudinal section of the trachea showing the action of the mucociliary escalator. (c) Cross section of the trachea showing the C-shaped tracheal cartilage. AP|R



© Prof. P.M. Motta/Univ. "La Sapienza", Rome/Science Source

Figure 23.8 **The Tracheal Epithelium Showing Ciliated Cells and Nonciliated Goblet Cells.** The small bumps on the goblet cells are microvilli.

- *What is the function of the goblet cells?*

The Lungs

Each **lung** (fig. 23.9) is a somewhat conical organ with a broad, concave **base** resting on the diaphragm and a blunt peak called the **apex** projecting slightly above the clavicle. The broad **costal surface** is pressed against the rib cage, and the smaller concave **mediastinal surface** faces medially. The mediastinal surface exhibits a slit called the **hilum** through which the lung receives the main bronchus, blood vessels, lymphatic vessels, and nerves. These structures constitute the **root** of the lung.

DEEPER INSIGHT 23.1

Tracheostomy

The functional importance of the nasal cavity becomes especially obvious when it is bypassed. If the upper airway is obstructed, it may be necessary to make a temporary opening in the trachea inferior to the larynx and insert a tube to allow airflow—a procedure called *tracheostomy.*[15] This prevents asphyxiation, but the inhaled air bypasses the nasal cavity and thus is not humidified. If the opening is left for long, the mucous membranes of the lower respiratory tract dry out and become encrusted, interfering with the clearance of mucus from the tract and promoting infection. When a patient is on a ventilator and air is introduced directly into the trachea, the air must be filtered and humidified by the apparatus to prevent respiratory tract damage.

The lungs are crowded by adjacent viscera and neither fill the entire rib cage, nor are they symmetric. Inferior to the lungs and diaphragm, much of the space within the rib cage is occupied by the liver, spleen, and stomach (see fig. A.5, p. 335). The right lung is shorter than the left because the liver rises higher on the right. The left lung, although taller, is narrower than the right because the heart tilts toward the left and occupies more space on this side of the mediastinum. On the medial surface, the left lung has an indentation called the **cardiac impression** where the heart presses against it (fig. 23.9a); part of this is visible anteriorly as a crescent-shaped **cardiac notch** in the margin of the lung. The right lung has three lobes—**superior, middle,** and **inferior.** A deep groove called the **horizontal fissure** separates the superior lobe from the middle lobe, and a similar groove called the **oblique fissure** separates the middle and inferior lobes. The left lung has only a superior and inferior lobe and a single oblique fissure.

The Bronchial Tree

Each lung contains a branching system of air tubes called the **bronchial tree,** extending from the *main bronchus* to the *terminal bronchioles.* From the fork in the trachea, the right **main bronchus**[16] (BRON-cus) measures about 2 to 3 cm long. It is slightly wider and more vertical than the left one; consequently, inhaled (aspirated) foreign objects lodge more often in the right bronchus than in the left. Just before entering the lung, the right main bronchus gives off a **superior lobar bronchus.** The main and lobar bronchi enter the hilum of the lung together. The superior lobar bronchus projects into the superior lobe of the lung, and the main bronchus continues a little farther and branches into **middle** and **inferior lobar bronchi** to the lower two lobes of the lung. The left main bronchus is about 5 cm long and is narrower and more horizontal than the right. It enters the hilum of the left lung before branching, then gives off superior and inferior lobar bronchi to the two lobes of that lung.

In both lungs, each lobar bronchus branches into **segmental bronchi.** Each of these ventilates one functionally independent unit of lung tissue called a **bronchopulmonary segment.** There are 10 of these in the right lung and 8 in the left (see photo on p. 631).

The main bronchi are supported, like the trachea, by C-shaped hyaline cartilages, whereas the lobar and segmental bronchi are supported by overlapping crescent-shaped cartilaginous plates. All of the bronchi are lined by a ciliated pseudostratified columnar epithelium, but the cells grow shorter and the epithelium thinner as we progress distally. The lamina propria beneath the epithelium exhibits mucous glands and many aggregations of lymphocytes *(mucosa-associated lymphatic tissue, MALT),* favorably positioned to respond to inhaled pathogens. All divisions of the bronchial tree also have a substantial amount of elastic connective tissue, which contributes to the recoil that expels air from the lungs in each respiratory cycle. The mucosa also has a well-developed layer of smooth muscle, the *muscularis mucosae,* which regulates airway diameter and airflow.

---

[15] *stomy* = making a hole

[16] *bronch* = windpipe


Larynx:
Thyroid cartilage
Cricoid cartilage
Trachea
Main bronchi
Apex of lung
Superior lobe
Superior lobar bronchus
Horizontal fissure
Middle lobar bronchus
Middle lobe
Inferior lobar bronchus
Oblique fissure
Inferior lobe
Base of lung
Mediastinal surfaces
Costal surface
Superior lobe
Cardiac impression
Inferior lobe
Oblique fissure

(a) Anterior view


Apex
Superior lobe
Pulmonary arteries
Hilum
Middle lobe
Inferior lobe
Lobar bronchi
Pulmonary veins
Pulmonary ligament
Diaphragmatic surface

(b) Mediastinal surface, right lung

Figure 23.9 **Gross Anatomy of the Lungs.** APR

Bronchioles (BRON-kee-oles) are continuations of the airway that lack supportive cartilage and are 1 mm or less in diameter. The portion of the lung ventilated by one bronchiole is called a **pulmonary**[17] **lobule.** The epithelium of the bronchioles starts out as ciliated pseudostratified columnar in the larger, more proximal passages. As we progress distally, it gets thinner (the cells do not grow as tall) and grades into simple columnar and finally simple cuboidal epithelium. Bronchioles lack mucous glands and goblet cells, but they are ciliated throughout. It is an important point that the cilia continue more deeply into the airway than the mucous glands and goblet cells do. This ensures that mucus draining distally from those gland cells can still be captured by the beating cilia and cleared from the airway. Aside from the epithelium, the mucosa of the bronchioles consists mainly of smooth muscle. Spasmodic contractions of this muscle at death cause the bronchioles to exhibit a wavy lumen in most histological sections (fig. 23.10a).

Each bronchiole divides into 50 to 80 **terminal bronchioles,** the final branches of the conducting division; there are about 65,000 of these in each lung. They measure 0.5 mm or less in diameter. Each terminal bronchiole gives off two or more smaller **respiratory bronchioles,** which have alveoli budding from their walls. Respiratory bronchioles are the beginning of the respiratory division. Their walls have scanty smooth muscle, and the smallest of them are nonciliated. Each respiratory bronchiole divides into 2 to 10 elongated, thin-walled passages called **alveolar ducts,** which also have alveoli along their walls (fig. 23.10). The alveolar ducts and smaller divisions have nonciliated simple squamous epithelia. The ducts end in **alveolar sacs,** which are clusters of alveoli arrayed around a central space called the **atrium** (fig. 23.10a). The distinction between an alveolar duct and atrium is their shape—an elongated passage or a space with about equal length and width. It is sometimes a subjective judgment whether to regard a space as an alveolar duct or atrium.

Since air in the conducting division of the respiratory tract cannot exchange gases with the blood, the lumen of the conducting division is called the *anatomical dead space.* In a state of relaxation, parasympathetic nerve fibers (from the vagus nerve) stimulate the muscularis mucosae and keep the airway partially constricted. This minimizes the dead space so that a greater percentage of the inhaled air goes to the alveoli, where it can oxygenate the blood. In exercise, the sympathetic nerves relax the smooth muscle and dilate the airway. Even though this increases the dead space, it enables air to flow more easily and rapidly so the alveoli are better ventilated in proportion to the demands of exercise. The increased airflow more than compensates for the increased dead space. Bronchioles exert the greatest control over

---

[17] *pulmon* = lung; *ary* = pertaining to



© Microscape/SPL/Science Source

© Biophoto Associates/Science Source

Figure 23.10 **Histology of the Lung.** (a) Light micrograph. (b) Scanning electron micrograph. Note the spongy texture of the lung.
• *Histologically, how can we tell that the large passage in the middle of part (a) is a bronchus and not a bronchiole?*

airflow for two reasons: (1) They are the most numerous components of the conducting division; and (2) with their well-developed smooth muscle and lack of restrictive cartilage, they can change relative diameter more than the larger air passages can. Narrowing of the bronchioles is called *bronchoconstriction,* and widening is called *bronchodilation.*

As described in chapter 20, the lungs receive blood from both the pulmonary arteries and bronchial arteries. Branches of the pulmonary artery closely follow the bronchial tree on their way to capillaries surrounding the alveoli (fig. 23.11), where gas exchange occurs. Branches of the bronchial arteries service the bronchi, bronchioles, and some other pulmonary tissues; they do not extend to the alveoli (see p. 581). The lungs are the only organs to receive both a pulmonary and a systemic blood supply.

Alveoli

Each human lung is a spongy mass with about 150 million little sacs, the alveoli, which provide about 70 m^2 of surface for gas exchange. An **alveolus**[18] (AL-vee-OH-lus) is a pouch about 0.2 to 0.5 mm in diameter (fig. 23.11). Thin, broad cells called **squamous (type I) alveolar cells** cover about 95% of the alveolar surface area. Their thinness allows for rapid gas diffusion between the alveolus and bloodstream. The other 5% is covered by round to cuboidal **great (type II) alveolar cells.** Even though they cover less surface area, great alveolar cells considerably outnumber the squamous alveolar cells. By analogy to baked goods, we could compare the shapes and surface areas of type I versus type II alveolar cells to a thinly rolled pie crust versus muffins, respectively. Great alveolar cells have two functions: (1) They repair the alveolar epithelium when the squamous alveolar cells are damaged; and (2) they secrete *pulmonary surfactant,* a mixture of phospholipids and protein that coats the alveoli and smallest bronchioles and prevents them from collapsing when one exhales. Without surfactant, the walls of a deflating alveolus would cling together like sheets of wet paper, and it would be very difficult to reinflate the alveoli on the next inspiration (see Deeper Insight 23.4).

The most numerous of all cells in the lung are **alveolar macrophages (dust cells),** which wander the lumens of the alveoli and the connective tissue between them. These cells keep the alveoli free of debris by phagocytizing dust particles that escape entrapment by mucus in the higher parts of the respiratory tract. In lungs that are infected or bleeding, the macrophages also phagocytize bacteria and loose blood cells. As many as 100 million alveolar macrophages perish each day as they ride up the mucociliary escalator to be swallowed and digested, ridding the lungs of their load of debris.

Each alveolus is surrounded by a basket of blood capillaries supplied by the pulmonary artery. The barrier between the alveolar air and blood, called the **respiratory membrane,** consists only of the squamous alveolar cell, the squamous endothelial cell of the capillary, and their shared basement membrane (fig. 23.11b). These have a total thickness of only 0.5 µm, in contrast to the 7 µm diameter of the erythrocytes passing through the capillaries.

It is very important to prevent fluid from accumulating in the alveoli, because gases diffuse too slowly through liquid to sufficiently aerate the blood. Except for the film of moisture on the alveolar wall, the alveoli are kept dry by the absorption of excess liquid by the blood capillaries and abundant lymphatic capillaries of the lungs. The lungs have a more extensive lymphatic drainage than any other organ in the body. This keeps us from drowning in our own serous fluid.

---

[18] *alveol* = small cavity, little space


Bronchiole
Pulmonary arteriole
Pulmonary venule
Alveoli
Alveolar sac
Capillary networks around alveoli
Terminal bronchiole
Respiratory bronchiole
(a)
Respiratory membrane
Capillary endothelial cell
Fluid with surfactant
Squamous alveolar cell
Lymphocyte
(b)
Great alveolar cell
Alveolar macrophage
Air
CO_2
O_2
Respiratory membrane:
Squamous alveolar cell
Shared basement membrane
Capillary endothelial cell
Blood
(c)

Figure 23.11 **Pulmonary Alveoli.** (a) Clusters of alveoli and their blood supply. (b) Structure of an alveolus. (c) Structure of the respiratory membrane.

The Pleurae

Each lung is enfolded in a two-layered serous membrane, the **pleura** (PLOOR-uh). The layer on the lung surface is called the visceral pleura and extends into the fissures between the lobes of the lung. At the hilum, the visceral pleura turns back on itself and forms the **parietal pleura,** which adheres to the mediastinum, inner surface of the rib cage, and superior surface of the diaphragm (fig. 23.12). An extension of the parietal pleura, the *pulmonary ligament,* connects it to the diaphragm.


Anterior
Pericardial cavity
Heart
Left lung
Visceral pleura
Pleural cavity
Parietal pleura
Breast
Sternum
Ribs
Right lung
Aorta
Vertebra
Spinal cord
Posterior

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Figure 23.12 **Cross Section Through the Thoracic Cavity.** This photograph is oriented the same way as the reader's body. The pleural cavity is especially evident where the left lung has shrunken away from the thoracic wall, but in a living person, the lung fully fills this space, the parietal and visceral pleurae are pressed together, and the pleural cavity is only a potential space between the membranes, as on the right side of this photograph.

The space between the parietal and visceral pleurae is called the **pleural cavity.** It contains only a thin film of slippery **pleural fluid;** thus, the pleural cavity is only a *potential space,* meaning there is normally no room between the membranes. Under pathological conditions, however, this space can fill with air or liquid, separating the membranes and compressing the lung (see *pneumothorax* in Deeper Insight 23.2).

The pleurae and pleural fluid have three functions:

1. **Reduction of friction.** Pleural fluid acts as a lubricant that enables the lungs to expand and contract with minimal friction.
2. **Creation of a pressure gradient.** During inspiration, the rib cage expands and draws the parietal pleura outward along with it. The visceral pleura clings to the parietal pleura, and since the visceral pleura is the lung surface, its outward movement expands the lung. The air pressure within the lung thus drops below the atmospheric pressure outside the body, and outside air flows down its pressure gradient into the lung.
3. **Compartmentalization.** The pleurae, mediastinum, and pericardium compartmentalize the thoracic organs and prevent infections of one organ from spreading easily to neighboring organs.

DEEPER INSIGHT 23.2

Pulmonary Collapse

Pulmonary collapse (collapsed lung), or *atelectasis*[19] (AT-eh-LEC-ta-sis), is a state in which part or all of a lung is devoid of air. It is the normal state of a fetus and a newborn that has not drawn the first breath. After breathing begins, cases of pulmonary collapse fall into two categories: compression and absorption atelectasis.

Compression atelectasis is due to external pressure on the lung preventing its complete expansion. The pressure may come from blood, serous fluid, or air in the pleural cavity. Air in the pleural cavity, a state called *pneumothorax,*[20] often results from "sucking wounds" to the chest—for example, when the thoracic wall is punctured by a knife or a broken rib and inspiration sucks air through the opening. The visceral and parietal pleurae separate and the lung recoils from the thoracic wall and collapses. Pneumothorax can also occur in the absence of a chest wound if a weakened, ballooning area of the lung surface (called a *bleb*) ruptures and air flows from the lung into the pleural cavity.

Absorption atelectasis occurs when gases are absorbed into the blood and not replaced by fresh air, resulting in collapse of the alveoli. It can occur when the airway is obstructed by a mucous plug or an aspirated foreign object such as a bite of food, or when it is compressed by an adjacent tumor or pulmonary aneurysm. It also frequently occurs after surgery, especially if a patient is in pain and is reluctant to breathe deeply or change position in bed. Postoperative patients are encouraged to breathe deeply because it promotes the clearance of secretions from the lungs, the even distribution of surfactant, and the flow of air from better-ventilated alveoli into less-ventilated ones.

When one lung collapses, the positive pressure in that pleural cavity can shift the entire mediastinum (including the heart and major blood vessels) toward the other pleural cavity, compressing and partially collapsing that lung as well.

Apply What You Know

In what ways does compression atelectasis of the lung (Deeper Insight 23.2) compare with cardiac tamponade (Deeper Insight 1.2)?

Before You Go On

Answer the following questions to test your understanding of the preceding section:

9. A dust particle is inhaled and gets into an alveolus without being trapped along the way. Describe the path it takes, naming all air passages from nostrils to alveoli. What would happen to it after arrival in an alveolus?
10. Contrast the epithelium of the bronchioles with that of the alveoli and explain how the structural difference is related to their functional differences.
11. Describe the relationship of the parietal and visceral pleurae to the lungs and thoracic wall.

23.4 Neuromuscular Aspects of Respiration

Expected Learning Outcomes

When you have completed this section, you should be able to

a. identify the muscles that ventilate the lungs and describe their respective roles;
b. describe the brainstem centers and peripheral nerves that control breathing, and explain their functions; and
c. identify the inputs that influence the activity of those brainstem centers.

The Respiratory Muscles

The lungs do not ventilate themselves. The only muscle they contain is smooth muscle in the walls of the bronchi and bronchioles, which does not create the airflow but only affects its speed. The driving force for pulmonary ventilation comes from the skeletal muscles of the trunk, especially the diaphragm and intercostal muscles (fig. 23.13).

The prime mover of pulmonary ventilation is the **diaphragm,** the muscular dome that separates the thoracic cavity from the abdominal cavity. It alone accounts for about two-thirds of the pulmonary airflow. When relaxed, it bulges upward to its farthest extent, pressing against the base of the lungs. The lungs

---

[19] *atel* = imperfect; *ectasis* = expansion
[20] *pneumo* = air, lung


Inspiration
Sternocleidomastoid (elevates sternum)
Scalenes (fix or elevate ribs 1–2)
External intercostals (elevate ribs 2–12, widen thoracic cavity)
Pectoralis minor (cut) (elevates ribs 3–5)
Internal intercostals, intercartilaginous part (aid in elevating ribs)
Diaphragm (descends and increases depth of thoracic cavity)
Forced expiration
Internal intercostals, costal part (depress ribs 1–11, narrow thoracic cavity)
Diaphragm (ascends and reduces depth of thoracic cavity)
Rectus abdominis (depresses lower ribs, pushes diaphragm upward by compressing abdominal organs)
External abdominal oblique (same effects as rectus abdominis)

Figure 23.13 **The Respiratory Muscles.** Boldface indicates the principal respiratory muscles; the others are accessory. Arrows indicate the direction of muscle pull. Muscles listed on the left are active during inspiration, and those on the right are active during forced expiration. Note that the diaphragm is active in both phases, and different parts of the internal intercostals serve for inspiration and expiration. Some other accessory muscles not shown here are discussed in the text.

are then at their minimum volume. When the diaphragm contracts, it tenses and flattens somewhat, dropping about 1.5 cm in relaxed inspiration and as much as 7 cm in deep breathing. This enlarges the thoracic cavity in the superior inferior direction, expanding the lungs and sucking in air. When the diaphragm relaxes, it bulges upward again, compresses the lungs, and expels air.

Several other muscles aid the diaphragm as synergists. Chief among these are the **internal** and **external intercostal muscles** between the ribs. Their primary function is to stiffen the thoracic cage during respiration and prevent it from caving inward when the diaphragm descends. However, they also contribute to enlargement and contraction of the thoracic cage and add about one-third of the air that ventilates the lungs. During quiet breathing, the scalene muscles of the neck act as fixators, holding ribs 1 and 2 stationary while the external intercostal muscles pull the other ribs upward. Since most ribs are anchored at both ends—by their attachment to the vertebral column at the proximal (posterior) end and their attachment through the costal cartilage to the sternum at the distal (anterior) end—they swing upward like the handle on a bucket and thrust the sternum forward. Descent of the diaphragm during inspiration also thrusts the sternum forward. These actions increase both the transverse (left to right) and anteroposterior dimensions of the chest. In deep breathing, the anteroposterior dimension increases by as much as 20%.

Other muscles of the chest and abdomen also aid in breathing, especially during forced respiration—that is, taking deeper breaths than normal. These are considered the *accessory muscles* of respiration. Deep inspiration is aided by the *erector spinae,* which arches the back and increases AP chest diameter, and by several muscles that elevate the upper ribs: the *sternocleidomastoids* and *scalenes* of the neck; the *pectoralis minor, pectoralis major,* and *serratus anterior* of the chest; the *serratus posterior superior;* and the *intercartilaginous (interchondral) part* of the internal intercostal muscles (the anterior part of the muscles between the costal cartilages). Although the scalenes merely fix the upper ribs during quiet respiration, they elevate them during forced inspiration.

Normal expiration is an energy-saving passive process achieved by the elasticity of the lungs and thoracic cage. The bronchial tree, the attachments of the ribs to the spine and sternum, and the tendons of the diaphragm and other respiratory muscles all have a degree of elasticity that causes them to spring back when the muscles relax. As these structures recoil, the thoracic cage diminishes in size, the air pressure in the lungs rises above the atmospheric pressure, and the air flows out. The only muscular effort involved in normal expiration is a braking action—that is, the muscles relax gradually rather than abruptly, thus preventing the lungs from recoiling too suddenly. This makes the transition from inspiration to expiration smoother.

But during forced expiration—for example, when singing or shouting, coughing or sneezing, or playing a wind instrument—the *rectus abdominis* pulls down on the sternum and lower ribs, while the *interosseous (costal) part* of the internal intercostal muscles (the part between the ribs proper) pulls the other ribs downward. These actions reduce the chest diameter and help to expel air more rapidly and thoroughly than usual. Other muscles that contribute to forced expiration are the *latissimus dorsi* of the lower back, the *transverse* and *oblique abdominal muscles,* the *serratus posterior inferior,* and even some muscles of the pelvic floor. They raise the pressure in the abdominal cavity and push some of the viscera, such as the stomach and liver, up against the diaphragm. This increases the pressure in the thoracic cavity and thus helps to expel air. This “abdominal breathing” is particularly important in singing, public speaking, coughing, and sneezing.

Respiratory Neuroanatomy

The heartbeat and breathing are the two most conspicuously rhythmic processes of the body, but the heart contains its own pacemaker whereas the lungs do not. As we have just seen, breathing requires the coordinated action of numerous skeletal muscles. These must be under centralized control; therefore, they depend on output from the brain. Breathing is controlled at two levels of the brain. One is cerebral and conscious, enabling us to inhale or exhale at will. Most of the time, however, we breathe without thinking about it—fortunately, for we otherwise could not go to sleep without fear of respiratory arrest (see Deeper Insight 23.3).

The automatic, unconscious cycle of breathing is controlled by three respiratory centers in the medulla oblongata and pons (fig. 23.14). Each of these is paired, left and right, with transverse connections between them.

1. The **ventral respiratory group (VRG)** is the primary pacemaker of the respiratory rhythm. It is an elongated neural network in the medulla that issues output signals to an integrating center in the spinal cord. The left and right spinal centers relay signals by way of the phrenic nerves to the diaphragm and by way of intercostal nerves to the external intercostal muscles. Periodic output from the VRG creates the basic cycle of contraction and relaxation of these muscles, causing inspiration and expiration. The following control centers alter that basic rhythm to meet ever-changing physiological needs.
2. The **dorsal respiratory group (DRG)** is an elongated mass of neurons that extends for much of the length of the medulla near the central canal, posterior to the VRG. It is apparently an integrating center that receives input from the pontine respiratory group (next); from central and peripheral chemoreceptors described shortly; and from receptors in the lungs for stretch and irritants. The DRG issues output to the VRG to modify the breathing rhythm.
3. The **pontine respiratory group (PRG)** (formerly called the *pneumotaxic center*) is a nucleus in the pons. It receives input from higher brain centers and issues output to the DRG and VRG. Its effect is to make breathing faster or slower, shallower or deeper; and to adapt to circumstances such as sleep, exercise, vocalization, and emotional responses.

These respiratory centers receive input from multiple sources:

- **Central chemoreceptors** are brainstem neurons that respond especially to changes in the pH of the cerebrospinal fluid. They are concentrated on each side of the medulla oblongata about 0.2 mm beneath its anterior surface.
- **Peripheral chemoreceptors** occur in the aortic arch and carotid bodies (fig. 23.15). They respond to the O_2 and CO_2 content and pH of the blood. The aortic bodies communicate with the medulla by way of the vagus nerves, and the carotid bodies communicate by way of the glossopharyngeal nerves.
- **Stretch receptors** are found in the smooth muscle of the bronchi and bronchioles and in the visceral pleura. They communicate with the DRG via the vagus nerves and respond to inflation of the lungs. Excessive inflation triggers a protective reflex that strongly inhibits inspiration.
- **Irritant receptors** are nerve endings in the epithelia of the airway. They respond to smoke, dust, pollen, chemical fumes, cold air, and excess mucus. They, too, transmit signals to the DRG via the vagus nerves. The DRG responds with protective reflexes such as coughing, bronchoconstriction, shallower breathing, or breath holding.
- **Higher brain centers** feed into the PRG, DRG, and spinal cord integrating centers. Thus, the limbic system, hypothalamus, and cerebral cortex influence the respiratory centers. This input allows for conscious control over breathing (as in holding one’s breath) and for emotions to affect respiration—for example, in gasping, crying, and laughing, and when anxiety provokes a bout of hyperventilation (rapid breathing in excess of physiological need). Signals for voluntary control over breathing travel down the corticospinal tracts to the respiratory neurons in the spinal cord, bypassing the brainstem centers.

DEEPER INSIGHT 23.3

Ondine’s Curse

In German legend, there was a water nymph named Ondine who took a mortal lover. When her lover proved unfaithful, the king of the nymphs put a curse on him that took away his automatic physiological functions. Consequently, he had to remember to take each breath, and he could not go to sleep or he would die of suffocation—which, as exhaustion overtook him, was indeed his fate.

Some people suffer a disorder called *Ondine’s curse,* in which the automatic respiratory functions are disabled—usually as a result of brainstem damage from poliomyelitis or as an accident of spinal cord surgery. Victims of Ondine’s curse must remember to take each breath and cannot sleep without using a mechanical ventilator or being awakened repeatedly by episodes of *apnea* (temporary cessation of breathing).


Key
🟩 Inputs to respiratory centers of medulla
🟥 Outputs to spinal centers and respiratory muscles
Output from hypothalamus, limbic system, and higher brain centers
Pons
Pontine respiratory group (PRG)
Dorsal respiratory group (DRG)
Ventral respiratory group (VRG)
Central chemoreceptors
Glossopharyngeal n.
Vagus n.
Medulla oblongata
Intercostal nn.
Phrenic n.
Spinal integrating centers
Diaphragm and intercostal muscles
Accessory muscles of respiration

Figure 23.14 **Respiratory Centers in the Central Nervous System.** The ventral respiratory group (VRG) is the primary pacemaker of the breathing rhythm. It communicates with the respiratory muscles by way of spinal integrating centers that send signals to the muscles through the intercostal and phrenic nerves. See the text for explanation of the various inputs shown here that modify the rhythm of the VRG. (n. = nerve, nn. = nerves)


Sensory nerve fiber in glossopharyngeal nerve
Carotid body
Sensory nerve fibers in vagus nerves
Common carotid artery
Aortic bodies
Aorta
Heart

Figure 23.15
The Peripheral Chemoreceptors of Respiration.

Apply What You Know

Some authorities refer to the respiratory rhythm as an *autonomic* function. Discuss whether you think this is an appropriate word for it. What are the effectors of the autonomic nervous system? (See chapter 16.) What are the effectors that ventilate the lungs? What bearing might this have on the question?

Before You Go On

Answer the following questions to test your understanding of the preceding section:

12. Explain why breathing is not controlled by a pacemaker in the lungs.
13. What is the prime mover of respiration? What muscle group acts as the most important synergist? What nerves innervate each of these?
14. Name some other synergists that act during forced inspiration and some that act during forced expiration.
15. State the names and locations of the three pairs of brainstem nuclei that regulate the respiratory rhythm. What role does each one play?
16. From what sources do the respiratory nuclei receive input that influences respiration?

23.5 Developmental and Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the prenatal development of the respiratory system;
b. describe the changes that occur in the respiratory system in old age; and
c. describe some common respiratory disorders.

Prenatal and Neonatal Development

The first embryonic trace of the respiratory system is a small pouch in the floor of the pharynx called the **pulmonary groove,** appearing at about 3.5 weeks. The groove grows down the mediastinum as an elongated tube, the future trachea, and branches into two **lung buds** by week 4 (fig. 23.16). The lung buds branch repeatedly and grow laterally and posteriorly, occupying the space posterior to the heart. Repeated branching produces the bronchial tree, which is completed as far as the bronchioles by the end of month 6. For the remainder of gestation and after birth, the bronchioles bud off alveoli. The adult number of alveoli is attained around the age of 10 years.

By week 8, the lungs are isolated from the heart by the growth of the pericardium; and by week 9, the diaphragm forms and separates the lungs and pleurae from the abdominal cavity. At 28 weeks, the respiratory system is usually adequately developed to support independent life (see Deeper Insight 23.4).

By 11 weeks, the fetus begins respiratory movements called **fetal breathing,** in which it rhythmically inhales and exhales amniotic fluid for as much as 8 hours per day. Fetal breathing stimulates lung development and conditions the respiratory muscles for life outside the womb. It ceases during labor. When the newborn infant begins breathing air, the fluid in the lungs is quickly absorbed by the pulmonary lymphatic and blood capillaries.

For the newborn infant, breathing is very laborious at first. The fetal lungs are collapsed and airless, and the neonate must take very strenuous first breaths to pop the alveoli open. Once they are fully inflated, the alveoli normally never collapse again. Even the pulmonary blood vessels are collapsed in the fetus, but as the infant takes its first breaths, the drop in thoracic pressure draws blood into the pulmonary circulation and expands the vessels. As pulmonary resistance drops, the foramen ovale and ductus arteriosus close (see p. 602), and pulmonary blood flow increases to match the airflow.

Apply What You Know

In a certain criminal investigation, the pathologist performing an autopsy on an infant removes the lungs, places them in a pail of water, and concludes that the infant was live-born. What do you think the pathologist saw that led to this conclusion? What contrasting observation would suggest that an infant had been stillborn?



Figure 23.16 Embryonic Development of the Respiratory System.

DEEPER INSIGHT 23.4

Premature Birth and Respiratory Distress Syndrome

Premature infants often suffer from *respiratory distress syndrome (RDS),* also called *hyaline membrane disease* (compare adult respiratory distress syndrome, table 23.1). They have not yet produced enough pulmonary surfactant to keep the alveoli open between inspirations. Consequently, the alveoli collapse during expiration, and a great effort is required to reinflate them. The infant becomes exhausted by the effort to breathe, and becomes progressively *cyanotic* (blue) because of the deficiency of oxygen in the blood *(hypoxemia*[21]*).* Progressive destruction of the alveolar epithelium and capillary walls leads to leakage of plasma into the alveolar air spaces and connective tissue between the alveoli. The plasma coagulates and the alveoli fill with stiff clear "membranes" of fibrin, fibrinogen, and cell debris. Eventually, the infant cannot inhale forcefully enough to inflate the alveoli again; without treatment, death ensues from hypoxemia and carbon dioxide retention *(hypercapnia*[22]*).*

RDS occurs in about 60% of infants born before 28 weeks of gestation, and 15% to 20% of those born between 32 and 36 weeks. It is the most common cause of neonatal death, with about 60,000 cases and 5,000 deaths per year in the United States. In addition to premature birth, some risk factors for RDS include maternal diabetes, oversedation of the mother during labor, aspiration of blood or amniotic fluid, and prenatal hypoxia caused by winding of the umbilical cord around the neck.

RDS can be treated with a ventilator that forces air into the lungs and keeps the alveoli inflated *(positive end-expiratory pressure, PEEP)* until the infant's lungs produce their own surfactant, and by giving a mist of surfactant from external sources such as calf lungs or genetically engineered bacteria. The infant may also be given oxygen therapy, but this is a limited and risky treatment because oxygen generates damaging free radicals that can cause blindness and severe bronchial problems. Oxygen toxicity can be minimized by a technique called *extracorporeal membrane oxygenation (ECMO),* which is similar to the heart–lung bypass procedure used in surgery. Blood flows from catheters in the baby's neck to a machine that oxygenates it, warms it, and returns it to the body. ECMO is, however, a high-risk procedure used only in extreme cases.

---

[21] *hypo* = deficiency; *ox* = oxygen; *emia* = blood condition
[22] *hyper* = excessive; *capn* = smoke, carbon dioxide; *ia* = condition

The Aging Respiratory System

Pulmonary ventilation declines steadily after the 20s and is one of several factors in a person's gradual loss of stamina. The costal cartilages and joints of the thoracic cage become less flexible, the lungs have less elastic tissue, and there are fewer alveoli in old age. There is a corresponding decline in the volume of air inhaled in each breath *(tidal volume),* the maximum amount of air a person can inhale *(vital capacity),* and the maximum speed of airflow *(forced expiratory volume).* The elderly are also less capable of clearing the lungs of irritants and pathogens, and therefore are increasingly susceptible to respiratory infections. Pneumonia causes more deaths in old age than any other communicable disease and is often contracted in hospitals and nursing homes.

Chronic obstructive pulmonary diseases (see next section) are more common in old age since they represent the cumulative effects of a lifetime of degenerative change. Declining pulmonary function also contributes to cardiovascular disease and hypoxemia, and the latter is a factor in degenerative disorders of all other organ systems. Respiratory health is therefore a major concern in aging.

Respiratory Pathology

Many of the respiratory disorders can be classified as *restrictive* or *obstructive disorders.* **Restrictive disorders** stiffen the lungs and reduce their *compliance* (ease of inflation) and vital capacity. An example is pulmonary fibrosis, in which much of the normal respiratory tissue of the lung is replaced by fibrous scar tissue. Fibrosis is an effect of such diseases as *tuberculosis* and the *black lung disease* of coal miners. **Obstructive disorders** narrow the airway and interfere with airflow, so expiration requires more effort and may be less complete than normal. Airway obstructions, bronchoconstriction, and tumors or aneurysms that compress the airways can cause obstructive disorders.

Chronic obstructive pulmonary diseases (COPDs) are disorders in which there is a long-term obstruction of airflow and a substantial reduction in pulmonary ventilation. The major COPDs are chronic bronchitis and emphysema. They are almost always caused by cigarette smoking, and are among the few leading causes of death in old age. **Chronic bronchitis** is characterized by airway congestion with *sputum,* a mixture of thick mucus and cellular debris, accompanied by chronic respiratory infection and bronchial inflammation. **Emphysema**[23] (EM-fih-SEE-muh) is characterized by a breakdown of alveolar walls and replacement of the spongy lung tissue with relatively large air-filled cavities, resulting in a reduction in alveolar surface area and reduced ability to oxygenate the blood. Any COPD can also lead to *cor pulmonale*—enlargement and potential failure of the right side of the heart due to obstruction of the pulmonary circulation.

Asthma is the most common chronic respiratory illness of children and the leading cause of school absenteeism and childhood hospitalization in the United States. About half of all cases develop before age 10 and only 15% after age 40. Asthma takes about 5,000 lives per year, and this number lately has been rising. It is usually an allergic reaction to airborne antigens (allergens) that stimulate intense bronchoconstriction and airway inflammation. The reaction commonly leads to severe coughing, wheezing, and sometimes suffocation. People who die of asthmatic suffocation typically show airways so plugged with gelatinous mucus that they could not exhale. The lungs remain hyperinflated even at autopsy. Asthma is treated with drugs that dilate the airway and relieve inflammation.

Lung cancer accounts for more deaths than any other form of cancer. The most important cause is cigarette smoking, distantly followed by air pollution. Lung cancer commonly follows or accompanies COPD. It begins with uncontrolled proliferation of cells of the surface epithelium or mucous glands of the bronchi. As the dividing epithelial cells invade the underlying tissues of the bronchial wall, the bronchus develops bleeding lesions. Dense masses of keratin and malignant cells appear in the lung parenchyma and replace functional respiratory tissue. Because of the extensive lymphatic drainage of the lungs, lung cancer quickly metastasizes to other organs—especially the pericardium, heart, bones, liver, lymph nodes, and brain. The chance of recovery is poor, with only 7% of patients surviving for 5 years after diagnosis.

Some other disorders of the respiratory system are briefly described in table 23.1.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

17. When and where does the pulmonary groove appear? Concisely describe its further development.
18. What changes in the lungs occur at birth? What corresponding changes occur in the cardiovascular system?
19. Identify some reasons why a person's vital capacity declines in old age.
20. Name and compare two COPDs and describe some pathological effects they have in common.
21. In what lung tissue does lung cancer originate? How does it kill?

---

[23] *emphys* = inflamed

TABLE 23.1	Some Disorders of the Respiratory System
Acute rhinitis	The common cold. Caused by many types of viruses that infect the upper respiratory tract. Symptoms include congestion, increased nasal secretion, sneezing, and dry cough. Transmitted especially by contact of contaminated hands with mucous membranes; not transmitted orally.
Adult respiratory distress syndrome	Acute lung inflammation and alveolar injury stemming from trauma, infection, burns, aspiration of vomit, inhalation of noxious gases, drug overdoses, and other causes. Alveolar injury is accompanied by severe pulmonary edema and hemorrhage, followed by fibrosis that progressively destroys lung tissue. Fatal in about 40% of cases under age 60 and in 60% of cases over age 65.
Pneumonia	A lower respiratory infection caused by any of several viruses, bacteria, fungi, or protozoa (most often the bacterium *Streptococcus pneumoniae*). Causes filling of alveoli with fluid and dead leukocytes and thickening of the respiratory membrane, which interferes with gas exchange and causes hypoxemia. Especially dangerous to infants, the elderly, and people with compromised immune systems, such as AIDS and leukemia patients.
Sleep apnea	Cessation of breathing for 10 seconds or longer during sleep; sometimes occurs hundreds of times per night, often accompanied by restlessness and snoring. Can result from altered function of CNS respiratory centers, airway obstruction, or both. Over time, may lead to daytime drowsiness, hypoxemia, polycythemia, pulmonary hypertension, congestive heart failure, and cardiac arrhythmia. Most common in obese people and in men.
Tuberculosis (TB)	Pulmonary infection with the bacterium *Mycobacterium tuberculosis,* which invades the lungs by way of air, blood, or lymph. Stimulates the lung to form fibrous nodules called tubercles around the bacteria. Progressive fibrosis compromises the elastic recoil and ventilation of the lungs and leads to pulmonary hemorrhaging and spitting up blood. Especially common among impoverished and homeless people and becoming increasingly common among people with AIDS.

Disorders Described Elsewhere

Airway obstruction	649	Chronic bronchitis	649	Neonatal respiratory distress syndrome	648
Asthma	649	Chronic obstructive pulmonary diseases	649	Ondine's curse	645
Atelectasis	643	Emphysema	649	Pneumothorax	643
Black lung disease	649	Lung cancer	649	Pulmonary fibrosis	649

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

23.1 Overview of the Respiratory System (p. 632)

1. The multiple functions of the respiratory system
2. The purpose and components of the conducting division of the respiratory tract
3. The purpose and components of the respiratory division of the respiratory tract
4. The boundary between the upper and lower respiratory tracts, and which organs belong to each region

23.2 The Upper Respiratory Tract (p. 633)

1. Functions of the nose
2. The anterior and posterior openings into the nasal cavity; the nasal septum and fossae; and the bones and cartilages that shape the external (facial) part of the nose
3. The components of the nasal septum, and the bones that contribute to the roof and floor of the nasal cavity
4. The nasal conchae and meatuses, and their functions
5. The histology, spatial distribution, and functions of the olfactory and respiratory epithelia of the nasal cavity
6. The location and function of the erectile tissues of the nasal cavity
7. The definition and three divisions of the pharynx, and the boundaries between the divisions
8. The definition and functions of the larynx, and its superior and inferior boundaries
9. The structure and function of the glottis and its mode of operation in infants and adults
10. The nine cartilages that frame the larynx, and the two ligaments that bind the larynx to the hyoid bone above and the trachea below
11. The locations and functions of the vestibular folds and vocal cords of the larynx
12. The mode of action of the intrinsic muscles of the larynx on the vocal cords, and how this affects vocalization

23.3 The Lower Respiratory Tract (p. 637)

1. The gross anatomy and histology of the trachea, and the functional significance of its mucociliary escalator, supportive cartilages, and trachealis muscle
2. The surface anatomy of the lungs, including the apex and base; costal and mediastinal surfaces; hilum; lobes and fissures; and differences between the right and left lungs
3. All the subdivisions of the bronchial tree and the air passages, in order, from main bronchi to alveoli; the histological differences between the regions of the airway; and the functional significance of these histological differences

4. Bronchoconstriction, bronchodilation, and the reason why the bronchioles are more important than any other region of the airway in regulating pulmonary airflow
5. The pulmonary and systemic blood supplies to the lungs, and the anatomical and functional differences between these two blood supplies
6. The structure of a pulmonary alveolus; the morphology and functions of its squamous and great alveolar cells and alveolar macrophages; and the source and function of pulmonary surfactant
7. Components of the respiratory membrane that separates the alveolar air space from the capillary bloodstream, and the relevance of this membrane to gas exchange
8. The two layers of the pleura; the pleural cavity and fluid; and the functions of the pleurae

23.4 Neuromuscular Aspects of Respiration (p. 643)

1. The roles of the diaphragm and intercostal muscles in breathing; the identity and roles of other accessory muscles of respiration; and the movements of the thoracic cage that cause ventilation of the lungs
2. Differences in muscular action between quiet and forced respiration
3. The energy-saving mechanism of quiet expiration
4. The three pairs of respiratory control nuclei in the brainstem; their locations; their input and output pathways; and the function of each
5. The central and peripheral chemoreceptors, stretch receptors, irritant receptors, and higher brain centers that influence respiration

23.5 Developmental and Clinical Perspectives (p. 647)

1. The development of the embryonic pulmonary groove and its differentiation into the respiratory tract and lungs
2. The onset and functions of fetal breathing
3. The respiratory adaptations of the newborn infant
4. Reasons for the normal decline in respiratory efficiency in old age, and how this affects other organ systems
5. The difference between restrictive and obstructive disorders of the respiratory system, and examples of each
6. The chronic obstructive pulmonary diseases (COPDs); the common causes of each; their pathology; and their effect on the heart
7. How lung cancer arises; how it spreads through the lung tissue; and how it metastasizes to other organs

Testing Your Recall

1. The nasal cavity is divided by the nasal septum into right and left
   a. nares.
   b. vestibules.
   c. fossae.
   d. choanae.
   e. conchae.
2. The intrinsic laryngeal muscles regulate speech by rotating
   a. the extrinsic laryngeal muscles.
   b. the thyroid cartilage.
   c. the arytenoid cartilages.
   d. the hyoid bone.
   e. the vocal cords.
3. The largest air passages that engage in gas exchange with the blood are
   a. the respiratory bronchioles.
   b. the terminal bronchioles.
   c. the main bronchi.
   d. the alveolar ducts.
   e. the alveoli.
4. Respiratory arrest would most likely result from a tumor of the
   a. pons.
   b. midbrain.
   c. thalamus.
   d. cerebellum.
   e. medulla oblongata.
5. A deficiency of pulmonary surfactant is most likely to cause
   a. chronic obstructive pulmonary disease.
   b. atelectasis.
   c. pneumothorax.
   d. chronic bronchitis.
   e. asthma.
6. The source of pulmonary surfactant is
   a. the visceral pleura.
   b. bronchial glands.
   c. alveolar capillaries.
   d. squamous alveolar cells.
   e. great alveolar cells.
7. Which of the following are fewest in number but largest in diameter?
   a. alveoli
   b. terminal bronchioles
   c. alveolar ducts
   d. segmental bronchi
   e. respiratory bronchioles
8. The rhythm of breathing is set by neurons in
   a. the medulla oblongata.
   b. the pons.
   c. the midbrain.
   d. the diaphragm.
   e. the cerebral cortex.
9. Which of the following muscles aid(s) in deep expiration?
   a. the scalenes
   b. the sternocleidomastoids
   c. the rectus abdominis
   d. the external intercostals
   e. the erector spinae
10. In the bronchial tree, which of the following would be found distal to all the rest?
    a. mucous glands
    b. ciliated cells
    c. alveolar ducts
    d. cartilage rings
    e. goblet cells
11. The digestive and respiratory tracts share a segment of the pharynx called the _____.
12. Within each lung, the airway forms a branching complex called the _____.
13. The flared areas of the nose lateral to the nostrils are shaped by _____ cartilages.
14. The three folds on the lateral walls of the nasal cavity are called _____.
15. _____ disorders reduce the speed of airflow through the airway.
16. Some inhaled air does not participate in gas exchange because it fills the _____ of the respiratory tract.
17. The largest cartilage of the larynx is the _____ cartilage.
18. The main pacemaker of the breathing rhythm is the _____ in the medulla oblongata.
19. The primary bronchi and pulmonary blood vessels penetrate the lung at a medial slit called the _____.
20. The last line of defense against inhaled particles are phagocytic cells called _____.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. trache-
2. alveol-
3. -ectasis
4. capn-
5. naso-
6. spir-
7. emphys-
8. pulmo-
9. broncho-
10. pneumo-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. The glottis is the opening from the larynx to the trachea.
2. The lungs contain more respiratory bronchioles than terminal bronchioles.
3. Each lung occupies a space between the parietal and visceral pleurae.
4. Expiration is normally caused by contraction of the internal intercostal muscles.
5. Atelectasis can result from causes other than pneumothorax.
6. Alveoli continue to be produced after birth.
7. Unlike bronchi, bronchioles have no cartilage.
8. Blood gases are monitored by the aortic and carotid sinuses.
9. The respiratory system begins its development by budding from the posterior side of the esophagus.
10. Extrinsic ligaments link the larynx to adjacent nonlaryngeal structures.

Answers in appendix A

Testing Your Comprehension

1. Discuss how the different functions of the conducting division and respiratory division relate to differences in their histology.
2. From the upper to the lower end of the trachea, the ratio of goblet cells to ciliated cells gradually changes. Would you expect the highest ratio of ciliated cells to goblet cells to be in the upper trachea or the lower trachea? Give a functional rationale for your answer.
3. The bronchioles are to the airway and airflow what the arterioles are to the circulatory system and blood flow. Explain or elaborate on this comparison.
4. A patient has suffered damage to the left phrenic nerve, resulting in paralysis of the left side of the diaphragm but not the right. X-rays show that during inspiration, the right side of the diaphragm descends as normal, but the left side *rises.* Explain the unusual motion of the left diaphragm.
5. An 83-year-old woman is admitted to the hospital, where a critical-care nurse attempts to insert a nasoenteric tube ("stomach tube") for feeding. The patient begins to exhibit dyspnea, and a chest X-ray reveals air in the right pleural cavity and a collapsed right lung. The patient dies 5 days later from respiratory complications. Name the conditions revealed by the X-ray and explain how they could have resulted from the nurse's procedure.



Mucosa of the small intestine

© Steve Gschmeissner/Science Source

CHAPTER

24

THE DIGESTIVE SYSTEM

CHAPTER OUTLINE

24.1 Digestive Processes and General Anatomy 654
- Digestive System Functions 654
- General Anatomy 654
- Innervation 655
- Circulation 656
- Relationship to the Peritoneum 657

24.2 The Mouth Through Esophagus 658
- The Mouth 658
- The Salivary Glands 661
- The Pharynx 663
- The Esophagus 663

24.3 The Stomach 664
- Gross Anatomy 664
- Microscopic Anatomy 664

24.4 The Small Intestine 667
- Gross Anatomy 667
- Microscopic Anatomy 669

24.5 The Large Intestine 671
- Gross Anatomy 671
- Microscopic Anatomy 673

24.6 Accessory Glands of Digestion 673
- The Liver 673
- The Gallbladder and Bile Passages 676
- The Pancreas 677

24.7 Developmental and Clinical Perspectives 678
- Prenatal Development 678
- The Aging Digestive System 678
- Digestive Disorders 680

Study Guide 681

DEEPER INSIGHTS

24.1 Tooth and Gum Disease 661
24.2 Gastroesophageal Reflux Disease 663
24.3 Peptic Ulcer 668
24.4 Gallstones (Cholelithiasis) 677

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:

- Brush borders and microvilli (p. 36)
- The embryonic disc and germ layers (pp. 88–89)
- The autonomic nervous system (chapter 16)
- The celiac and mesenteric blood circulation (pp. 584–586, 589)

Anatomy & Physiology REVEALED®
aprevealed.com

Module 12: Digestive System

Some of the most fundamental facts we know about digestion date to a grave accident in 1822. A Canadian voyageur, Alexis St. Martin, was accidentally hit by a shotgun blast while standing outside a trading post on Mackinac Island, Michigan. A frontier army doctor summoned to the scene, William Beaumont, found part of St. Martin's lung protruding through the wound, and a hole in his stomach "large enough to receive my forefinger." Surprisingly, St. Martin survived, but the wound left a permanent opening (fistula) into his stomach, covered for the rest of his life by only a loose flap of skin.

Beaumont saw this as an opportunity to learn something about digestion. Now disabled from wilderness travel, St. Martin agreed to participate in Beaumont's experiments in exchange for room and board. Working under crude frontier conditions with little idea of scientific methods, Beaumont nevertheless performed more than 200 experiments on St. Martin over a period of several years. He placed food into the stomach through the fistula and removed it hourly to observe the progress of digestion. He sent vials of gastric juice to chemists for analysis. He proved that digestion required hydrochloric acid and an unknown agent we now know to be the enzyme pepsin. St. Martin had a short temper, and during his emotional outbursts, Beaumont observed that little digestion occurred; we now know this to be due to the inhibitory effect of the sympathetic nervous system on digestion.

In 1833, Beaumont published a book on his results that laid a foundation for modern *gastroenterology,*[1] the scientific study and medical treatment of the digestive system. Many authorities continued to believe, for a time, that the stomach acted essentially as a grinding chamber, fermentation vat, or cooking pot. Some of them even attributed digestion to a supernatural spirit in the stomach. Beaumont was proven right, however, and his work had no equal until Russian physiologist Ivan Pavlov built upon it, receiving a Nobel Prize in 1904 for his studies of digestion.

24.1 Digestive Processes and General Anatomy

Expected Learning Outcomes

When you have completed this section, you should be able to

a. identify the functions and major processes of the digestive system;
b. list the regions and accessory organs of the digestive system;
c. identify the layers of the wall of the digestive tract;
d. describe the enteric nervous system; and
e. name the mesenteries and describe their relationship to the digestive system.

The digestive system is essentially a disassembly line—its primary purpose is to break nutrients down into forms that can be used by the body, and to absorb them so they can be distributed to the tissues. Most of what we eat cannot be used in the form found in our food. Nutrients must be broken down into smaller components, such as amino acids and monosaccharides, that are universal to all species. Consider what happens if you eat a piece of beef, for example. The myosin of beef differs very little from that of your own muscles, but the two are not identical, and even if they were, beef myosin could not be absorbed, transported in the blood, and properly installed in your muscle cells. Like any other dietary protein, it must be broken down into amino acids before it can be used. Since beef and human proteins are made of the same 20 amino acids, those of beef proteins might indeed become part of your own myosin but could equally well wind up in your insulin, fibrinogen, collagen, or any other protein.

Digestive System Functions APR

The **digestive system** is the organ system that processes food, extracts nutrients from it, and eliminates the residue. It does this in five stages:

1. **ingestion,** the selective intake of food;
2. **digestion,** the mechanical and chemical breakdown of food into a form usable by the body;
3. **absorption,** the uptake of nutrients into the blood and lymph;
4. **compaction,** absorbing water and consolidating the indigestible residue into feces; and finally,
5. **defecation,** the elimination of feces.

General Anatomy

The digestive system has two anatomical subdivisions, the digestive tract and the accessory organs (fig. 24.1). The **digestive tract** is a muscular tube extending from mouth to anus. It measures about 5 m (16 ft) long in a living person, but because of the loss of muscle tone at death, it is typically about 9 m (30 ft) long in the cadaver. It is also known as the *alimentary*[2] *canal* or *gut.* It includes the mouth, pharynx, esophagus, stomach, small intestine, and large intestine. Part of it, the stomach and intestines, constitutes the *gastrointestinal (GI) tract.* The **accessory organs** are the teeth, tongue, salivary glands, liver, gallbladder, and pancreas.

The digestive tract is open to the environment at both ends. Most of the material in it has not entered any body tissues and is considered to be external to the body until it is absorbed by epithelial cells of the alimentary canal. In the strict sense, defecated food residue was never in the body.

Most of the digestive tract follows the basic structural plan shown in figure 24.2, with a wall composed of the following tissue layers, in order from the inner to the outer surface:

- Mucosa
  - Epithelium
  - Lamina propria
  - Muscularis mucosae

---

[1] *gastro* = stomach; *entero* = intestine; *logy* = study of

[2] *aliment* = food

Submucosa
Muscularis externa
    Circular layer
    Longitudinal layer
Serosa
    Areolar tissue
    Mesothelium

Slight variations on this theme are found in different regions of the tract.

The inner lining of the tract, called its **mucosa** or **mucous membrane,** consists of an epithelium, a loose connective tissue layer called the **lamina propria,** and a thin layer of smooth muscle called the **muscularis mucosae** (MUSS-cue-LAIR-is mew-CO-see). The epithelium is simple columnar in most of the digestive tract, but the mouth, pharynx, esophagus, and anal canal differ. These upper and lower ends of the digestive tract are subject to more abrasion than the stomach and intestines, and thus have a stratified squamous epithelium. The muscularis mucosae tenses the mucosa, creating grooves and ridges that enhance its surface area and contact with food. This improves the efficiency of digestion and nutrient absorption. The mucosa often exhibits an abundance of lymphocytes and lymphatic nodules—the *mucosa-associated lymphatic tissue (MALT)* (see p. 616).



Figure 24.1 The Digestive System.

The **submucosa** is a thicker layer of loose connective tissue containing blood vessels, lymphatic vessels, a nerve plexus, and in some places, mucous glands. MALT also extends into the submucosa in some parts of the GI tract.

The **muscularis externa** consists of usually two layers of smooth muscle near the outer surface. Cells of the inner layer encircle the tract and those of the outer layer run longitudinally. In some places, the circular layer is thickened to form valves (sphincters) that regulate the passage of material through the digestive tract. The muscularis externa is responsible for peristalsis and other movements that mix food and digestive enzymes and propel material through the tract.

The **serosa** is composed of a thin layer of areolar tissue topped by a simple squamous mesothelium. It begins in the lower 3 to 4 cm of the esophagus and ends just before the rectum. The pharynx, most of the esophagus, and the rectum have no serosa but are surrounded by a fibrous connective tissue layer called the **adventitia** (AD-ven-TISH-ah), which blends into the adjacent connective tissues of other organs.

Innervation

Tongue movements, mastication, and the initial actions of swallowing employ skeletal muscles innervated by somatic motor fibers from six of the cranial nerves (V, VII, and IX–XII) and from the ansa cervicalis; these muscles and their innervation are detailed in table 11.3 (pp. 273–275). The salivary glands are innervated by sympathetic fibers from the superior cervical ganglion and parasympathetic fibers from cranial nerves VII and IX (see figs. 15.32, p. 433; 15.34, p. 434; and 16.4, p. 447).

From the lower esophagus to the anal canal, most of the muscle is smooth muscle (the external anal sphincter is the only exception), and therefore receives only autonomic innervation. Parasympathetic innervation dominates the digestive tract and comes mainly from the vagus nerves, which supply all of the tract from esophagus to transverse colon. The descending colon and rectum receive their parasympathetic innervation from pelvic nerves arising from the inferior hypogastric plexus (see fig. 16.7, p. 451). The parasympathetic nervous system relaxes sphincter muscles and stimulates gastrointestinal motility and secretion. Thus, in general, it promotes digestion.

The sympathetic nervous system plays a lesser role, but in general it inhibits motility and secretion and keeps the GI sphincters contracted and closed. Thus, it inhibits digestion. Sympathetic efferent pathways travel through the celiac ganglion to the stomach, liver, and pancreas; through the superior mesenteric ganglion to the small intestine and most of the large intestine; and through the inferior mesenteric ganglion to the rectum (see fig. 16.4).


Diaphragm
Esophageal hiatus
Enteric nervous system:
Myenteric plexus
Submucosal plexus
Parasympathetic ganglion of myenteric plexus
Lumen
Blood vessels
Mucosa:
Stratified squamous epithelium
Lamina propria
Muscularis mucosae
Submucosa:
Esophageal gland
Muscularis externa:
Inner circular layer
Outer longitudinal layer
Serosa

Figure 24.2 **Tissue Layers of the Digestive Tract.** Cross section of the esophagus just below the diaphragm.

Even though the digestive tract receives such extensive innervation from the CNS, it can function independently even if these nerves are severed. This is because the esophagus, stomach, and intestines have their own nervous network called the **enteric nervous system,** which is thought to have over 100 million neurons—more than the spinal cord!

These neurons are distributed in two networks: the **submucosal plexus** in the submucosa and the **myenteric plexus** between layers of the muscularis externa (fig. 24.2). Parasympathetic preganglionic fibers terminate in the autonomic ganglia of the myenteric plexus. Postganglionic fibers arising in this plexus not only innervate the muscularis externa, but also pass through its inner circular layer and contribute to the submucosal plexus. The myenteric plexus controls peristalsis and other contractions of the muscularis externa, while the submucosal plexus controls movements of the muscularis mucosae and glandular secretion of the mucosa.

Sensory nerve fibers monitor stretching of the GI wall and chemical conditions in the lumen. These fibers carry signals to adjacent regions of the GI tract in **short (myenteric[3]) reflex arcs** contained in the myenteric plexus, and to the central nervous system by way of **long (vagovagal) reflex arcs,** predominantly in the vagus nerves. These visceral reflex arcs enable different regions of the GI tract to regulate each other over both short and long distances.

Circulation

We will see near the end of this chapter that the embryonic digestive tract forms in three segments: the foregut, midgut, and hindgut. These segments are defined by their arterial blood supply.

- The **foregut** includes the mouth, pharynx, esophagus, stomach, and the beginning of the duodenum (to the point where the bile duct empties into it). Above the diaphragm, the thoracic aorta gives off a series of **esophageal arteries** to the esophagus. Below the diaphragm, the foregut receives blood from branches of the **celiac trunk** (see fig. 21.23, p. 585).
- The **midgut** begins at the opening of the bile duct and includes the rest of the duodenum, the jejunum and ileum (the second and third portions of the small intestine), and the large intestine as far as the first two-thirds of the transverse colon. It receives blood from the **superior mesenteric artery** (fig. 21.24a, p. 586).

---

[3] *my* = muscle; *enter* = intestine

- The **hindgut** includes the remainder of the large intestine, from the end of the transverse colon through the anal canal. It is supplied by branches of the **inferior mesenteric artery** (fig. 21.24b).

The most noteworthy general point about the venous drainage of the GI tract is that blood from the entire tract below the diaphragm ultimately drains into the **hepatic portal vein,** which enters the liver. The system of vessels connecting the lower digestive tract to the liver is the **hepatic portal system** (table 21.7, p. 589). It routes all blood from the stomach and intestines, as well as from some other abdominal viscera, through the liver before returning it to the general circulation. Like other portal systems, this one has two capillary networks in series. Capillaries in the small intestine receive digested nutrients, and capillaries in the liver (the *hepatic sinusoids* described later) deliver these nutrients to the liver cells. This gives the liver a chance to process most nutrients and cleanse the intestinal blood of bacteria.

Relationship to the Peritoneum

In processing food, the stomach and intestines undergo such strenuous contractions that they need freedom to move in the abdominal cavity. They are not tightly bound to the abdominal wall, but over most of their length, they are loosely suspended from it by connective tissue sheets called **mesenteries** (see figs. 1.14 and 1.15, pp. 18–19). The mesenteries hold the abdominal viscera in their proper relationship to each other and prevent the small intestine, especially, from becoming twisted and tangled by changes in body position and by its own contractions. Furthermore, they provide passage for the blood vessels and nerves that supply the digestive tract, and contain many lymph nodes and lymphatic vessels.

The parietal peritoneum is a serous membrane that lines the wall of the abdominal cavity (see p. 18). Along the posterior midline of the body, it turns inward and forms the **posterior (dorsal) mesentery,** a translucent two-layered membrane extending to the digestive tract. Upon reaching an organ such as the stomach or small intestine, the two layers separate and pass around opposite sides of the organ, forming its serosa. In some places, the two layers come together again on the far side of that organ and continue as another sheet of tissue, the **anterior (ventral) mesentery.** This mesentery may hang freely in the abdominal cavity or attach to the anterior abdominal wall or other organs. The relationship between the posterior and anterior mesenteries and the serosa is shown in figure 1.16.

Two mesenteries called *omenta* are associated with the stomach (see fig. 24.11). The **lesser omentum** extends the short distance from the liver to the right superior margin *(lesser curvature)* of the stomach (fig. 24.3a). A much larger and very fatty **greater omentum** hangs like an apron from the left inferior margin *(greater curvature)* of the stomach, loosely covering the small intestine. At its inferior margin, the greater omentum turns back on itself and passes upward, behind the superficial layer, forming a deep, empty pouch between the layers like an apron turned up at the hem. At the superior margin, the upturned layer continues as a serosa that encloses the spleen and transverse colon. From the transverse colon, it continues to the posterior abdominal wall, thus anchoring the colon. This mesentery of the colon is called the **mesocolon** (fig. 24.3b).



Figure 24.3 **Serous Membranes Associated with the Digestive Tract.** (a) The greater and lesser omenta. (b) Greater omentum and small intestine retracted to show the mesocolon and mesentery. These membranes contain the mesenteric arteries and veins. APR

The omenta have a loosely organized, lacy appearance due partly to many holes or gaps in the membranes and partly to an irregular distribution of adipose tissue. They adhere to perforations or inflamed areas of the stomach or intestines, contribute immune cells to the site, and isolate infections that might otherwise give rise to peritonitis. When a person gains abdominal weight, a great deal of it is fat deposited in these mesenteries.

When an organ is enclosed by mesentery (serosa) on both sides, it is considered to be within the peritoneal cavity, or **intraperitoneal.**[4] When an organ lies against the posterior body wall and is covered by peritoneum on the anterior side only, it is said to be outside the peritoneal cavity, or **retroperitoneal.**[5] The duodenum, most of the pancreas, and parts of the large intestine are retroperitoneal. The stomach, liver, and other parts of the small and large intestines are intraperitoneal.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. Name the principal regions of the digestive tract in order from mouth to anus.
2. What are the similarities and differences between the lamina propria and the submucosa?
3. What are the two components of the enteric nervous system? How do they differ in location and function?
4. What three major branches of the aorta supply the digestive tract? What is the relationship between these three arterial supplies and the embryonic development of the digestive tract?
5. Name the serous membranes that suspend the intestines from the posterior body wall. Name the external layer of the intestines formed by an extension of this membrane.

24.2 The Mouth Through Esophagus

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the teeth, tongue, and other organs of the oral cavity;
b. state the names and locations of the salivary glands;
c. describe the location and function of the pharyngeal constrictor muscles; and
d. describe the gross anatomy and histology of the esophagus.

The Mouth

The **mouth** is also known as the **oral (buccal**[6]**) cavity.** Its functions include ingestion (food intake), taste and other sensory responses to food, mastication (chewing), chemical digestion, swallowing, speech, and respiration. The mouth is enclosed by the cheeks, lips, palate, and tongue (fig. 24.4). Its anterior opening between the lips is the **oral fissure,** and its posterior opening into the throat is the **fauces**[7] (FAW-seez). The mouth is lined with stratified squamous epithelium. It is keratinized in areas subject to the greatest abrasion, such as the gums and hard palate, and nonkeratinized in other areas such as the floor of the mouth, the soft palate, and the inside of the cheeks and lips.

The Cheeks and Lips

The cheeks and lips retain food and push it between the teeth for mastication, and are essential for articulate speech and for sucking and blowing actions, including suckling by infants. Their fleshiness is due mainly to subcutaneous fat, the buccinator muscles of the cheeks, and the orbicularis oris muscle of the lips. A median fold called the **labial frenulum**[8] attaches each lip to the gum, between the anterior incisors. The **vestibule** is the space between the cheeks or lips and the teeth—the space where you insert your toothbrush when brushing the outer surfaces of the teeth.



Figure 24.4 **The Mouth.** For a photographic medial view, see page 332. APR

---

[4] *intra* = within
[5] *retro* = behind
[6] *bucca* = cheek
[7] *fauces* = throat
[8] *labi* = lip; *frenulum* = little bridle

The lips are divided into three areas: (1) The *cutaneous area* is colored like the rest of the face and has hair follicles and sebaceous glands; on the upper lip, this is where a mustache grows. (2) The *red area (vermilion),* is the hairless region where the lips meet (where some people apply lipstick). It has unusually tall dermal papillae, which allow blood capillaries and nerve endings to come closer to the epidermal surface. Thus, this area is redder and more sensitive than the cutaneous area. (3) The *labial mucosa* is the inner surface of the lip, facing the gums and teeth. It contains mucous *labial glands* that contribute to the saliva.

The Tongue

The tongue (fig. 24.5), although muscular and bulky, is an agile and sensitive organ with several functions: It aids in food intake; it has sensory receptors for taste, texture, and temperature that are important in the acceptance or rejection of food; it compresses and breaks up food; it maneuvers food between the teeth for mastication; it secretes mucus and enzymes; it compresses the chewed food into a soft mass, or *bolus,* that is easier to swallow; it initiates swallowing; and it is necessary for articulate speech. Its surface is covered with nonkeratinized stratified squamous epithelium and exhibits bumps and projections called **lingual papillae,** the site of the taste buds. Figure 24.5 shows the locations of the vallate, foliate, and fungiform types of papillae. Their details and relation to the taste buds are described in chapter 17 (p. 466).

The anterior two-thirds of the tongue, called the **body,** occupies the oral cavity; the posterior one-third, the **root,** occupies the oropharynx. The boundary between the body and root is marked by a V-shaped row of vallate papillae and, behind these, a groove called the **terminal sulcus.** Beneath the tongue, a median fold called the **lingual frenulum** attaches its body to the floor of the mouth. The root of the tongue contains the lingual tonsils. Amid the tongue muscles are serous and mucous **lingual glands,** which secrete a portion of the saliva.

The muscles of the tongue, which compose most of its mass, are described in chapter 11. The **intrinsic muscles,** contained entirely within the tongue, produce the relatively subtle tongue movements of speech. The **extrinsic muscles,** with origins elsewhere and insertions in the tongue, produce most of the stronger movements of food manipulation. The extrinsic muscles include the *genioglossus, hyoglossus, styloglossus,* and *palatoglossus* (see table 11.3, p. 273).

The Palate

The palate (fig. 24.4), separating the oral cavity from the nasal cavity, makes it possible to breathe while chewing food. Its anterior portion, the **hard (bony) palate,** is supported by the palatine processes of the maxillae and by the smaller palatine bones. It has transverse ridges called *palatine rugae* that aid the tongue in holding and manipulating food. Posterior to this is the **soft palate,** which has a more spongy texture and is composed mainly of skeletal muscle and glandular tissue, but no bone. It has a conical medial projection, the **uvula,**[9] visible at the rear of the mouth. The uvula helps to retain food in the mouth until one is ready to swallow.

At the rear of the mouth, two muscular arches on each side begin at the roof near the uvula and descend to the floor. The anterior one is the **palatoglossal arch** and the posterior one is the **palatopharyngeal arch.** The latter arch marks the beginning of the pharynx. The palatine tonsils are located on the wall between the arches.

---

[9] *uvula* = little grape



(a) Superior view **(b) Frontal section, anterior view**

Figure 24.5 **The Tongue.** For a sagittal section, see figure A.2 (p. 332).

The Teeth

The teeth are collectively called the **dentition.** They serve to masticate the food, breaking it into smaller pieces. This not only makes the food easier to swallow, but also exposes more surface area to the action of digestive enzymes and thus speeds up chemical digestion. Adults normally have 16 teeth in the mandible and 16 in the maxilla. From the midline to the rear of each jaw, there are two incisors, a canine, two premolars, and up to three molars (fig. 24.6a). The **incisors** are chisel-like cutting teeth used to bite off a piece of food. The **canines** are more pointed and act to puncture and shred it. They serve as weapons in many mammals but became reduced in the course of human evolution until they now project barely beyond the other teeth. The **premolars** and **molars** have relatively broad surfaces adapted for crushing, shredding, and grinding food.

Each tooth is embedded in a socket called an **alveolus,** forming a joint called a *gomphosis* between the tooth and bone (fig. 24.7). The alveolus is lined by a **periodontal** (PERR-ee-oh-DON-tul) **ligament,** a modified periosteum whose collagen fibers penetrate into the bone on one side and into the tooth on the other. This anchors the tooth firmly in the alveolus, but allows for slight movement under the stress of chewing. The gum, or **gingiva** (JIN-jih-vuh), covers the alveolar bone. Regions of a tooth are defined by their relationship to the gingiva: The **crown** is the portion above the gum, the **root** is the portion inserted into the alveolus below the gum, and the **neck** is the line where the crown, root, and gum meet. The space between the tooth and gum is the **gingival sulcus.** The hygiene of this sulcus is especially important for dental health (see Deeper Insight 24.1).

Most of a tooth consists of hard yellowish tissue called **dentin,** covered with **enamel** in the crown and **cementum** in the root. Dentin and cementum are living connective tissues with cells or cell processes embedded in a calcified matrix. Cells of the cementum *(cementocytes)* are scattered more or less randomly and occupy tiny cavities similar to the lacunae of bone. Cells of the dentin *(odontoblasts)* line the pulp cavity and have


Names of teeth
Age at eruption (months)
Central incisor
6–9
Lateral incisor
7–11
Canine
16–20
1st molar
12–16
2nd molar
20–26

(a) Deciduous (baby) teeth


Names of teeth
Age at eruption (years)
Central incisor
6–8
Lateral incisor
7–9
Canine
9–12
1st premolar
10–12
2nd premolar
10–12
1st molar
6–7
2nd molar
11–13
3rd molar (wisdom tooth)
17–25

(b) Permanent teeth

Figure 24.6 The Dentition. Each figure shows only the upper teeth. The ages at eruption are composite ages for the corresponding upper and lower teeth. Generally, the lower (mandibular) teeth erupt somewhat earlier than their upper (maxillary) counterparts.

- *Which teeth are absent from a 3-year-old child?* APR


Enamel
Dentin
Pulp in pulp cavity
Gingival sulcus
Gingiva
Alveolar bone
Periodontal ligament
Root canal
Cementum
Apical foramen
Artery, nerve, vein
Crown
Neck
Root

Figure 24.7 Structure of a Tooth and Its Alveolus. This particular example is a molar.

- *Of all the tooth components shown here, which is or are not living tissue(s)?*

DEEPER INSIGHT 24.1

Tooth and Gum Disease

Food leaves a sticky residue on the teeth called *plaque,* composed mainly of bacteria and sugars. If plaque is not thoroughly removed by brushing and flossing, bacteria accumulate, metabolize the sugars, and release lactic acid and other acids. These acids dissolve the minerals of enamel and dentin, and the bacteria enzymatically digest the collagen and other organic components. The eroded "cavities" of the tooth are known as *dental caries.*[10] If not repaired, caries may fully penetrate the dentin and spread to the pulp cavity. This requires either extraction of the tooth or *root canal therapy,* in which the pulp is removed and replaced with inert material.

When plaque calcifies on the tooth surface, it is called *calculus (tartar).* Calculus in the gingival sulcus wedges the tooth and gum apart and allows bacterial invasion of the sulcus. This leads to *gingivitis,* or gum inflammation. Nearly everyone has gingivitis at some time. In some cases, bacteria spread from the sulcus into the alveolar bone and begin to dissolve it, producing *periodontal disease.* About 86% of people over age 70 have periodontal disease, and many suffer tooth loss as a result. This accounts for 80% to 90% of adult tooth loss.

slender processes that travel through tiny parallel tunnels in the dentin. Enamel is not a tissue but a cell-free secretion produced before the tooth emerges above the gum. Damaged dentin and cementum can regenerate, but damaged enamel cannot—it must be artificially repaired.

Internally, a tooth has a dilated **pulp cavity** in the crown and upper root, and a narrow **root canal** in the lower root. These spaces are occupied by **pulp**—a mass of loose connective tissue, blood and lymphatic vessels, and nerves. These nerves and vessels enter the tooth through a pore, the **apical foramen,** at the inferior end of each root canal.

The meeting of the teeth when the mouth closes is called *occlusion* (ah-CLUE-zhun), and the surfaces where they meet are called the **occlusal surfaces.** The occlusal surface of a premolar has two rounded bumps called **cusps;** thus, the premolars are also known as **bicuspids.** The molars have four to five cusps. Cusps of the upper and lower premolars and molars mesh when the jaws are closed and slide over each other as the jaw makes lateral chewing motions. This grinds and tears food more effectively than if the occlusal surfaces were flat.

Teeth develop beneath the gums and **erupt** (emerge) in predictable order. Twenty **deciduous teeth** ("milk teeth" or "baby teeth") erupt from the ages of 6 to 30 months, beginning with the incisors (fig. 24.6a). Between 6 and 25 years of age, these are replaced by 32 **permanent teeth.** As a permanent tooth grows deep to a deciduous tooth (fig. 24.8), the root of the deciduous tooth dissolves and leaves little more than the crown by the time it falls out. The third molars (wisdom teeth) erupt around ages 17 to 25, if at all. Over the course of human evolution, the face became flatter and the jaws shorter, leaving little room for the third molars. Thus, they often remain below the gum and become *impacted*—so crowded against neighboring teeth and bone that they cannot erupt.



© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Figure 24.8 Permanent and Deciduous Teeth in a Child's Skull. This dissection shows erupted deciduous teeth and, deep to them and marked with asterisks, the permanent teeth waiting to erupt.

The Salivary Glands

Saliva moistens the mouth; digests a small amount of starch and fat; cleanses the teeth; inhibits bacterial growth; dissolves molecules so they can stimulate the taste buds; and moistens and lubricates food and binds particles together to aid in swallowing. It is a solution of 97.0% to 99.5% water and the following solutes:

- **salivary amylase,** an enzyme that begins starch digestion in the mouth;
- **lingual lipase,** an enzyme that is activated by stomach acid and digests fat after the food is swallowed;
- **mucus,** which binds and lubricates the food mass and aids in swallowing;
- **lysozyme,** an enzyme that kills bacteria;
- **immunoglobulin A (IgA),** an antibody that inhibits bacterial growth; and
- **electrolytes,** including sodium, potassium, chloride, phosphate, and bicarbonate salts.

There are two kinds of salivary glands, intrinsic and extrinsic. The **intrinsic salivary glands** are an indefinite number of small glands dispersed amid the other oral tissues. They include *lingual glands* in the tongue, *labial glands* on the inside of the lips, and *buccal glands* on the inside of the cheeks. They secrete saliva at a fairly constant rate whether we are eating or not, but in relatively small amounts. This saliva keeps the mouth moist and inhibits bacterial growth.

The **extrinsic salivary glands** are three pairs of larger, more discrete organs located outside of the oral mucosa. They

---

[10] *caries* = rottenness


Parotid gland
Parotid duct
Tongue
Sublingual ducts
Masseter muscle
Submandibular duct
Submandibular gland
Sublingual gland
Mandible
Opening of submandibular duct
Lingual frenulum

Figure 24.9 **The Extrinsic Salivary Glands.** Half of the mandible has been removed to expose the sublingual gland medial to it.


Mucous acinus
Mucous cells
Serous cells
Salivary duct
Serous acinus
Mixed acinus
Serous demilune on mixed acinus
(a)
Mucous cells
Serous demilune
Stroma
Duct
(b)

© McGraw-Hill Education/Dennis Strete, photographer

Figure 24.10 **Microscopic Anatomy of the Salivary Glands.** (a) Duct and acini of a generalized salivary gland with a mixture of mucous and serous cells. Serous cells often form crescent-shaped caps called serous demilunes over the ends of mucous acini. No one salivary gland shows all the features shown here. (b) Histology of the sublingual salivary gland.

communicate with the oral cavity by way of ducts (fig. 24.9). They are:

1. The **parotid**[11] **gland,** located just beneath the skin anterior to the earlobe. Its duct passes superficially over the masseter, pierces the buccinator, and opens into the mouth opposite the second upper molar tooth. *Mumps* is an inflammation and swelling of the parotid gland caused by a virus.
2. The **submandibular gland,** located halfway along the body of the mandible, medial to its margin, just deep to the mylohyoid muscle. Its duct empties into the mouth at a papilla on the side of the lingual frenulum, near the lower central incisors (see fig. 24.4).
3. The **sublingual gland,** located in the floor of the mouth. It has multiple ducts that empty into the mouth posterior to the papilla of the submandibular duct (see fig. 24.4).

These are all compound tubuloacinar glands with a treelike arrangement of branching ducts ending in acini. Some acini have only mucous cells, some have only serous cells, and some have a mixture of both (fig. 24.10). Typically on the last of these, called *mixed acini,* the mucous cells surround the lumen and the serous cells form a cap on one end, shaped a bit like a croissant, called the *serous demilune.*[12] Mucous cells secrete salivary mucus, and serous cells secrete a thinner fluid rich in amylase and electrolytes.

Salivation is controlled by groups of neurons called **salivatory nuclei** in the medulla oblongata and pons. They receive signals from sensory receptors in the mouth as well as from higher brain centers that respond to the odor, sight, or thought of food. Efferent nerve pathways to the salivary glands were described earlier (p. 655). Salivation is mostly under the control of parasympathetic fibers in cranial nerves VII and IX, which stimulate the secretion of watery, enzyme-rich saliva. Sympathetic fibers from cervical ganglia stimulate the secretion of thicker, mucus-rich saliva.

Apply What You Know

Explain why the mouth may feel dry or sticky when one is nervous. (*Hint:* Draw on information about the autonomic nervous system in chapter 16.)

---

[11] *par* = next to; *ot* = ear

[12] *demi* = half; *lune* = moon

The Pharynx

The pharynx, as described in chapter 23, is a muscular funnel that connects the oral cavity to the esophagus and the nasal cavity to the larynx; thus, it is a point where the digestive and respiratory tracts intersect. It consists of three regions called the nasopharynx, oropharynx, and laryngopharynx (see fig. 23.2c, p. 634). The first is exclusively respiratory and is lined with pseudostratified columnar epithelium; the last two are shared by the respiratory and digestive tracts and are lined with nonkeratinized stratified squamous epithelium, an adaptation to withstanding abrasion by passing food.

The pharynx has a deep layer of longitudinally oriented skeletal muscle and a superficial layer of circular skeletal muscle. The circular muscle is divided into **superior, middle,** and **inferior pharyngeal constrictors,** which force food downward during swallowing. When one is not swallowing, the inferior constrictor remains contracted to exclude air from the esophagus. This constriction is regarded as the **upper esophageal sphincter,** although it is not an anatomical feature of the esophagus. It disappears at the time of death when the muscle relaxes. Thus, it is regarded as a *physiological sphincter* rather than a constant anatomical structure.

The Esophagus

The **esophagus** is a straight muscular tube 25 to 30 cm long, posterior to the trachea (see figs. 24.1 and 24.2). Its superior opening lies between vertebra C6 and the cricoid cartilage of the larynx. After passing downward through the mediastinum, the esophagus penetrates the diaphragm at an opening called the **esophageal hiatus,** continues another 3 to 4 cm, and meets the stomach at the level of vertebra T7. Its opening into the stomach is called the **cardiac orifice** (for its proximity to the heart). Food pauses briefly at this point before entering the stomach because of a constriction called the **lower esophageal sphincter (LES).** The LES prevents stomach contents from regurgitating into the esophagus, thus protecting the esophageal mucosa from the erosive effect of the stomach acid (see Deeper Insight 24.2).

The wall of the esophagus is organized into the tissue layers described earlier, with some regional specializations. The mucosa has a nonkeratinized stratified squamous epithelium. The submucosa contains **esophageal glands,** which secrete lubricating mucus into the lumen. When the esophagus is empty, the mucosa and submucosa are deeply folded into longitudinal ridges, giving the lumen a starlike shape in cross section.

The muscularis externa is composed of skeletal muscle in the upper one-third of the esophagus, a mixture of skeletal and smooth muscle in the middle one-third, and only smooth muscle in the lower one-third.

Most of the esophagus is in the mediastinum. Here, it is covered with a connective tissue adventitia that merges into the adventitias of the trachea and thoracic aorta. The short segment below the diaphragm is partially covered by a serosa.

Swallowing, or *deglutition* (DEE-glu-TISH-un), is a complex action involving over 22 muscles in the mouth, pharynx, and esophagus, coordinated by the **swallowing center,** a pair of nuclei in the medulla oblongata. This center communicates with muscles of the pharynx and esophagus by way of the trigeminal, facial, glossopharyngeal, and hypoglossal nerves (cranial nerves V, VII, IX, and XII), and coordinates a complex series of muscle contractions to produce swallowing without choking.

DEEPER INSIGHT 24.2

Gastroesophageal Reflux Disease

It would seem that churning of the stomach would drive its contents back up the esophagus. Such backflow, or *gastroesophageal reflux,* is normally prevented, however, by the lower esophageal sphincter. Weakening of the LES leads to repetitive or chronic backflow, called *gastroesophageal reflux disease (GERD).* Stomach acid and sometimes bile acids and pancreatic enzymes regurgitate into the esophagus and irritate the mucosa. This causes the sensation of "heartburn," named for its location although it has nothing to do with the heart. GERD affects as much as 50% of the population in the United States, especially white males. Beside sex and race, risk factors include age (middle-aged or beyond), being overweight, and going to bed too soon after eating.

The heartburn sensation can often be managed with antacids and is commonly dismissed by physicians and patients as merely a nuisance. However, in a few cases, GERD can lead to more serious complications such as scarring and narrowing of the esophagus *(stricture),* erosion and inflammation of the esophageal wall *(erosive esophagitis),* a transformation (metaplasia) of esophageal epithelium to an intestinal-type columnar epithelium *(Barrett[13] esophagus),* and a form of esophageal cancer called *adenocarcinoma.* Although most people with Barrett esophagus and adenocarcinoma have a long-term history of GERD, only 5% to 15% of those with GERD progress to Barrett esophagus and fewer than 0.1% to adenocarcinoma.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

6. List as many functions of the tongue as you can.
7. Name the four types of teeth in order from the midline to the rear of the jaw. How do they differ in function?
8. What is the difference in function and location between intrinsic and extrinsic salivary glands? Name the extrinsic salivary glands and describe their locations.
9. Identify at least two histological features of the esophagus that are especially tied to its role in swallowing.

---

[13] Norman R. Barrett (1903–79), British surgeon

24.3 The Stomach APR

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the gross and microscopic anatomy of the stomach;
b. describe the nerve and blood supply to the stomach;
c. state the function of each type of epithelial cell in the gastric mucosa; and
d. explain how the stomach is protected from digesting itself.

The stomach is a muscular sac in the upper left abdominal cavity immediately inferior to the diaphragm (see fig. 24.1). It functions primarily as a food storage organ, with an internal volume of about 50 mL when empty and 1.0 to 1.5 L after a typical meal. When extremely full, it may hold up to 4 L and extend nearly as far as the pelvis. The stomach mechanically breaks up food particles, liquefies the food, and begins the chemical digestion of proteins and fat. This produces a soupy or pasty mixture of semidigested food called **chyme**[14] (pronounced "kime"). Most digestion occurs after the chyme passes on to the small intestine. The stomach also produces secretions that are important in vitamin absorption, appetite control, and coordination of different parts of the digestive tract with each other.

Gross Anatomy

The stomach is somewhat J-shaped (fig. 24.11) and vertical in tall people, whereas in short people it is more nearly horizontal. We can trace the margin of the stomach from esophagus to duodenum by a short way and a long way. The short way (about 10 cm) is along the superomedial margin, facing the liver, and is called the *lesser curvature*. The long way (about 40 cm) is along the inferolateral margin and is called the *greater curvature*. The lesser curvature is attached to a short *lesser omentum* that spans the space from there to the liver, and a large *greater omentum* is suspended from the greater curvature.

The stomach is divided into four regions: (1) The **cardiac region (cardia)** is the small area within about 3 cm of the cardiac orifice. (2) The **fundic region (fundus)** is the domelike roof superior to the esophageal attachment. (3) The **body (corpus)** makes up most of the stomach distal to the cardiac orifice. (4) The **pyloric region** is a slightly narrower pouch at the distal end; it is subdivided into a funnel-like **antrum**[15] and a narrower **pyloric canal.** The latter terminates at the **pylorus,**[16] a narrow passage into the duodenum. The pylorus is surrounded by a thick ring of smooth muscle, the **pyloric (gastroduodenal) sphincter,** which regulates the passage of chyme into the duodenum.

Microscopic Anatomy

The stomach wall has tissue layers similar to those of the esophagus, with some variations. The surface of the mucosa is a simple columnar glandular epithelium (fig. 24.12). The apical regions of its cells are filled with mucin. After it is secreted, mucin swells with water and becomes mucus. When the stomach is full, the mucosa and submucosa are flat and smooth, but as it empties, these layers fold into longitudinal wrinkles called **gastric rugae**[17] (ROO-jee). The lamina propria is almost entirely occupied by tubular glands, to be described shortly. The muscularis externa has three layers, rather than two—an outer longitudinal, middle circular, and inner oblique layer (fig. 24.11a).

Apply What You Know

Contrast the epithelium of the esophagus with that of the stomach. Why is each epithelial type best suited to the function of its respective organ?

The gastric mucosa is pocked with depressions called **gastric pits** lined with the same columnar epithelium as the mucosal surface. Two or three tubular glands open into the bottom of each gastric pit and span the rest of the lamina propria. The glands are simple wavy or coiled tubes of more or less uniform diameter, except for a constriction called the **neck** at the point where the gland opens into the pit. In the cardiac and pyloric regions, they are called **cardiac glands** and **pyloric glands,** respectively. In the rest of the stomach, they are called **gastric glands** (fig. 24.12b, c). Collectively, the glands have the following cell types (table 24.1, p. 667):

- **Mucous cells,** which secrete mucus, predominate in the cardiac and pyloric glands. In gastric glands, they are called *mucous neck cells* and are concentrated in the neck of the gland.
- **Regenerative (stem) cells,** found in the base of the pit and neck of the gland, divide rapidly and produce a continual supply of new cells. Newly generated cells migrate upward to the gastric surface as well as downward into the glands to replace cells that die and fall off into the lumen of the stomach.
- **Parietal cells,** found mostly in the upper half of the gland, secrete hydrochloric acid (HCl), a digestive aid; *intrinsic factor,* a glycoprotein needed for the absorption of dietary vitamin B_{12}; and an appetite-regulating hormone named *ghrelin* (GREL-in). They are found mostly in the gastric glands, but a few occur in the pyloric glands.
- **Chief cells,** so named because they are the most numerous, secrete the fat-digesting enzyme *gastric lipase,* as well as *pepsinogen,* the precursor of a protein-digesting enzyme called *pepsin.* They dominate the lower half of the gastric glands but are absent from cardiac and pyloric glands.
- **Enteroendocrine cells,** concentrated especially in the lower end of a gland, secrete hormones and other chemical signals that regulate digestion. They are found in all regions of the stomach, but are most numerous in the gastric and pyloric glands. There are at least eight kinds, each of which produces

---

[14] *chyme* = juice
[15] *antrum* = cavity
[16] *pylorus* = gatekeeper
[17] *ruga* = fold, crease


Diaphragm
Lesser omentum
Fundic region
Cardiac region
Lesser curvature
Body
Pyloric region:
Antrum
Pyloric canal
Pylorus
Pyloric sphincter
Longitudinal muscle
Circular muscle
Oblique muscle
Gastric rugae
Greater curvature
Greater omentum
Duodenum
(a)
Esophagus
Fundic region
Lesser curvature
Cardiac orifice
Cardiac region
Duodenum
Body
Pyloric region:
Pylorus
Gastric rugae
Pyloric sphincter
Pyloric canal
Antrum
Greater curvature
(b)

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Figure 24.11 **The Stomach.** (a) Gross anatomy. (b) Photograph of the internal surface.

- *How does the muscular wall of the stomach differ from that of the esophagus?* APR


Lumen of stomach
Epithelium
Gastric pit
Gastric gland
Lamina propria
Lymphatic nodule
Muscularis mucosae
Artery
Vein
Oblique layer of muscle
Circular layer of muscle
Longitudinal layer of muscle
Mucosa
Submucosa
Muscularis externa
Serosa
Mucous neck cell
Parietal cell
Mucous cell
Chief cell
G cell

(a) Stomach wall

(b) Pyloric gland

(c) Gastric gland

(d) Gastric pits

© Steve Gschmeissner/Science Source

Figure 24.12 Microscopic Anatomy of the Stomach Wall. (a) A block of tissue showing all layers from the mucosa (top) to the serosa (bottom). (b) A pyloric gland from the inferior end of the stomach. Note the absence of chief cells and relatively few parietal cells. (c) A gastric gland, the most widespread type in the stomach. (d) The opening of several gastric pits into the stomach, surrounded by the rounded apical surfaces of the columnar epithelial cells of the mucosa (SEM). AP|R

TABLE 24.1 Major Secretions of the Gastric Glands

Secretory Cells	Secretion	Function
Mucous neck cells	Mucus	Protects mucosa from HCl and enzymes
Parietal cells	Hydrochloric acid (HCl)	Activates pepsin and lingual lipase; helps liquefy food; reduces dietary iron to usable form (Fe^{2+}); destroys ingested pathogens
	Intrinsic factor	Enables small intestine to absorb vitamin B_{12}
	Ghrelin	Secreted when stomach is empty; acts on brain to produce sensation of hunger
Chief cells	Pepsinogen	Converted to pepsin, which digests protein
	Gastric lipase	Digests fat
Enteroendocrine cells	Gastrin	Stimulates gastric glands to secrete HCl and enzymes; stimulates intestinal motility; relaxes ileocecal valve
	Serotonin	Stimulates gastric motility
	Histamine	Stimulates HCl secretion
	Somatostatin	Inhibits gastric secretion and motility; delays emptying of stomach; inhibits secretion by pancreas; inhibits gallbladder contraction and bile secretion; reduces blood circulation and nutrient absorption in small intestine

a different chemical messenger. **G cells,** for example, secrete a hormone called *gastrin,* which stimulates the exocrine cells of the gastric glands to secrete acid and enzymes.

In general, the cardiac and pyloric glands secrete mainly mucus; acid and enzyme secretion occur predominantly in the gastric glands; and hormones are secreted throughout the stomach.

Some people enjoy haggis and tripe, made from animal stomachs, and have no difficulty digesting them. Why, then, doesn't the human stomach digest itself? The living stomach is protected in three ways from the harsh chemical environment it creates:

1. **Mucous coat.** A thick, highly alkaline mucus resists the action of acid and enzymes.
2. **Tight junctions.** The epithelial cells are joined by tight junctions that prevent gastric juice from seeping between them and digesting the connective tissue below.
3. **Epithelial cell replacement.** In spite of these other protections, the stomach's epithelial cells live only 3 to 6 days and are then sloughed off into the chyme and digested with the food. They are replaced just as rapidly, however, by the division of stem cells in the gastric pits.

The breakdown of these protective mechanisms can result in inflammation and peptic ulcer (see Deeper Insight 24.3).

Before You Go On

Answer the following questions to test your understanding of the preceding section:

10. Distinguish between the cardiac region, fundic region, body, and pyloric region of the stomach.
11. Name the cell types in the gastric and pyloric glands and state what each one secretes.
12. Explain why the stomach does not digest itself.

24.4 The Small Intestine

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the gross and microscopic anatomy of the small intestine; and
b. describe the structural adaptations of the small intestine for digestion and nutrient absorption.

The stomach "spits" about 3 mL of chyme at a time into the small intestine. Nearly all chemical digestion and nutrient absorption occur here. To perform these roles efficiently, the small intestine must have a large surface area exposed to the chyme. This surface area is imparted to it by extensive folding of the mucosa, and by the great length of the small intestine. It measures about 2.7 to 4.5 m long in a living person, but in the cadaver, where there is no muscle tone, it is 4 to 8 m long. The expression *small* intestine refers not to its length but to its diameter—about 2.5 cm (1 in.).

Gross Anatomy

The small intestine is a coiled mass filling most of the abdominal cavity inferior to the stomach and liver. It is divided into three regions: the duodenum, jejunum, and ileum (fig. 24.14).

The **duodenum** (dew-ODD-eh-num or DEW-oh-DEE-num) constitutes the first 25 cm (10 in.). It begins at the pyloric sphincter, arcs around the head of the pancreas and passes to the left, and ends at a sharp bend called the **duodenojejunal flexure.** Its name refers to its length, about equal to the width of 12 fingers.[18] The first 2 cm of the duodenum is intraperitoneal, but the rest is retroperitoneal, along with the pancreas.

---

[18] *duoden* = 12

DEEPER INSIGHT 24.3

Peptic Ulcer

Inflammation of the stomach, called *gastritis,* can lead to a *peptic ulcer* as pepsin and hydrochloric acid erode the stomach wall (fig. 24.13). Peptic ulcers occur even more commonly in the duodenum and occasionally in the esophagus. If untreated, they can perforate the organ and cause fatal hemorrhaging or peritonitis. Most such fatalities occur in people over age 65.

There is no evidence to support the popular belief that peptic ulcers result from psychological stress. Hypersecretion of acid and pepsin is sometimes involved, but even normal secretion can cause ulceration if the mucosal defense is compromised by other causes. Many or most ulcers involve an acid-resistant bacterium, *Helicobacter pylori,* that invades the mucosa of the stomach and duodenum and opens the way to chemical damage to the tissue. Other risk factors include smoking and the use of aspirin and other nonsteroidal anti-inflammatory drugs (NSAIDs). NSAIDs suppress the synthesis of prostaglandins, which normally stimulate the secretion of protective mucus and acid-neutralizing bicarbonate. Aspirin itself is an acid that directly irritates the gastric mucosa.

Not long ago, the most widely prescribed drug in the United States was Cimetidine (Tagamet), which was designed to treat peptic ulcers by reducing acid secretion. Histamine stimulates acid secretion by binding to sites on the parietal cells called *H_2 receptors;* Cimetidine, an *H_2 blocker,* prevents this binding. Lately, however, ulcers have been treated more successfully with antibiotics against *Helicobacter* combined with bismuth suspensions such as Pepto-Bismol. This is a much shorter and less expensive course of treatment and permanently cures about 90% of peptic ulcers, as compared with a cure rate of only 20% to 30% for H_2 blockers.



© CNRI/SPL/Science Source

(a) Normal

© CNRI/SPL/Science Source

(b) Peptic ulcer

Figure 24.13 **Endoscopic Views of the Gastroesophageal Junction.** The esophagus can be seen opening into the cardiac stomach. (a) A view of the cardiac orifice from above, showing a healthy esophageal mucosa. The small white spots are reflections of light from the endoscope. (b) A bleeding peptic ulcer. A peptic ulcer typically has an oval shape and yellow-white color. Here the yellowish floor of the ulcer is partially obscured by black blood clots, and fresh blood is visible around the margin.

Internally, the duodenum exhibits transverse to spiral ridges, up to 10 mm high, called **circular folds (plicae circulares)** (see fig. 24.19). They involve only the mucosa and submucosa; they are not visible on the external surface of the intestine, which is smooth. They cause the chyme to flow on a spiral path along the mucosa, slowing its progress, causing more contact with the mucosa, and promoting thorough mixing, digestion, and nutrient absorption.

Adjacent to the head of the pancreas, the duodenal wall has a prominent wrinkle called the **major duodenal papilla** where the bile and pancreatic ducts open into the intestine. This papilla marks the boundary between the foregut and midgut. In most people, there is a smaller **minor duodenal papilla** a little proximal to this, which receives an *accessory pancreatic duct.*

The duodenum receives and mixes the stomach contents, pancreatic juice, and bile. Stomach acid is neutralized here by bicarbonate in the pancreatic juice, fats are physically broken up (emulsified) by the bile, pepsin is inactivated by the rise in pH, and pancreatic enzymes take over the job of chemical digestion.

The **jejunum** (jeh-JOO-num), by definition, is the first 40% of the small intestine beyond the duodenum—roughly 1.0 to 1.7 m in a living person. Its name refers to the fact that early anatomists typically found it to be empty.[19] The jejunum begins in the upper left quadrant of the abdomen but lies mostly within the umbilical region (see fig. 1.11, p. 15). It has large, tall, closely spaced

---

[19] *jejun* = empty, dry



Figure 24.14 Gross Anatomy of the Small Intestine.

circular folds. Its wall is relatively thick and muscular, and it has an especially rich blood supply that gives it a relatively red color. Most digestion and nutrient absorption occur here.

The **ileum**[20] forms the last 60% of the postduodenal small intestine—about 1.6 to 2.7 m. It occupies mainly the hypogastric region and part of the pelvic cavity. Compared with the jejunum, its wall is thinner, less muscular, less vascular, and has a paler pink color. Its circular folds are smaller and more sparse, and are lacking from the distal end. On the side opposite from its mesenteric attachment, the ileum has prominent lymphatic nodules in clusters called **Peyer**[21] **patches,** which are readily visible to the naked eye and become progressively larger approaching the large intestine.

The end of the small intestine is the **ileocecal** (ILL-ee-oh-SEE-cul) **junction,** where the ileum joins the *cecum* of the large intestine. The muscularis of the ileum is thickened at this point to form a sphincter, the **ileocecal** (ILL-ee-oh-SEE-cul) **valve,** which protrudes into the cecum and regulates the passage of food residue into the large intestine and prevents feces from backing up into the ileum.

Both the jejunum and ileum are intraperitoneal and thus covered on all sides with a serosa, which is continuous with the complex, folded mesentery that suspends the small intestine from the posterior abdominal wall. Because most of the duodenum, however, is retroperitoneal, the peritoneum forms a serosa only on its anterior surface and its other surfaces are covered with adventitia.

Microscopic Anatomy

The tissue layers of the small intestine are reminiscent of those in the esophagus and stomach with modifications appropriate for nutrient digestion and absorption. The lumen is lined with simple columnar epithelium. The muscularis externa is notable for a thick inner circular layer and a thinner outer longitudinal layer.

Effective digestion and nutrient absorption require the small intestine to have a large internal surface area. This is provided by its relatively great length and by three kinds of internal folds or projections: the circular folds, villi, and microvilli. If the mucosa of the small intestine was smooth, like the inside of a hose, it would have a surface area of about 0.3 to 0.5 m^2, but with these surface elaborations, its actual surface area is about 200 m^2—clearly a great advantage for nutrient absorption. The circular folds increase the surface area by a factor of 2 to 3, the villi by a factor of 10, and the microvilli by a factor of 20.

Villi (VIL-eye; singular, *villus*) are tongue- to finger-shaped projections that rise about 0.5 to 1.0 mm from the intestinal wall (fig. 24.15). They give the mucosa a fuzzy texture like a terrycloth towel. Villi are largest in the duodenum and progressively smaller in more distal regions of the small intestine. A villus is covered with two kinds of epithelial cells—columnar **enterocytes (absorptive cells)** and mucus-secreting **goblet cells.** Like epithelial cells of the stomach, those of the small intestine are joined by tight junctions that prevent digestive enzymes from seeping between them. The core of a villus is packed with areolar tissue of the lamina propria and contains a few smooth muscle cells that contract periodically. This enhances mixing of the chyme in the intestinal lumen and aids in the uptake of dietary fat.

The core also contains an arteriole, a bed of blood capillaries, a venule, and a lymphatic capillary called a **lacteal** (LAC-tee-ul). The blood capillaries absorb most nutrients, but the lacteal absorbs most dietary lipid. The reason lipids are little absorbed by the blood capillaries concerns their "packaging." The enterocytes package them in protein- and phospholipid-coated droplets called *chylomicrons,* then release these into the core of the villus. Chylomicrons are too large (60 to 750 nm) to pass through the blood capillary walls into the bloodstream, but lymphatic capillaries have larger gaps between their cells (see fig. 22.3, p. 612) that allow for the uptake of these large droplets into the lymph. The lymphatic system eventually delivers them to the bloodstream. The fatty lymph in the lacteal is called *chyle.* It has a milky appearance for which the lacteal is named.[22]

Apply What You Know

Identify the exact place in the body where chylomicrons enter the blood. (*Hint:* See chapter 22.)

Microvilli are hairlike projections, about 1 μm high, that form a dense, fuzzy brush border on the surface of each enterocyte (see fig. 2.12, p. 36). Adding to the intestinal surface area is immensely important, but it is not their only function. Certain digestive enzymes called *brush border enzymes* are embedded in their plasma membranes and perform the final steps in digesting protein and carbohydrates. The chyme must come into contact with the microvilli for this to occur, so this is called *contact digestion.* This is one reason that thorough mixing of the chyme is so important. The end products of digestion are then absorbed through the membranes of the microvilli.

---

[20] from *eilos* = twisted
[21] Johann K. Peyer (1653–1712), Swiss anatomist
[22] *lact* = milk


(a)
(b)
Villi
Intestinal crypts
Duodenal glands
Muscularis externa
Serosa
0.5 mm
(c)
Villi
Simple columnar epithelium
Brush border of microvilli
Capillary network
Goblet cell
Lacteal
Intestinal crypts
Venule
Arteriole
Lymphatic vessel
Paneth cell

© Meckes/Ottawa/Science Source

© McGraw-Hill Education/Dennis Strete, photographer

Figure 24.15 **Intestinal Villi.** (a) Villi (SEM). Each villus is about 1 mm high. (b) Histological section of the duodenum showing villi, intestinal crypts, and duodenal glands. (c) Structure of a villus.

On the floor of the small intestine, between the bases of the villi, there are numerous pores that open into tubular glands called **intestinal crypts** (**crypts of Lieberkühn;**[23] LEE-ber-koohn). These crypts, similar to the gastric glands, extend as far as the muscularis mucosae. In the upper half, they consist of enterocytes and goblet cells like those of the villi. The lower half is dominated by dividing stem cells. In its life span of 3 to 6 days, an epithelial cell migrates up the crypt to the tip of the villus, where it is sloughed off and digested. Also seen deep in the crypts are enteroendocrine cells and **Paneth**[24] **cells.** Paneth cells secrete the antimicrobial enzyme *lysozyme* and other defensive proteins that resist bacterial invasion of the mucosa.

The duodenum has prominent **duodenal glands** in the submucosa. They secrete an abundance of alkaline mucus, which neutralizes stomach acid and shields the mucosa from its erosive effects. Throughout the small intestine, the lamina propria and submucosa have a large population of lymphocytes that intercept pathogens before they can invade the bloodstream. In some places, these are aggregated into conspicuous lymphatic nodules (see fig. 22.8, p. 616), which become most conspicuous in the Peyer patches of the ileum.

---

[23] Johann N. Lieberkühn (1711–56), German anatomist

[24] Josef Paneth (1857–90), Austrian physician

Before You Go On

Answer the following questions to test your understanding of the preceding section:

13. Name the three regions of the small intestine and describe the distinctive features of each one.
14. Name the sphincters at the beginning and end of the small intestine.
15. What three structures increase the absorptive surface area of the small intestine?
16. Sketch a villus and label its epithelium, brush border, lamina propria, blood capillaries, and lacteal.

2.5 The Large Intestine

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the gross and microscopic anatomy of the large intestine; and
b. contrast the mucosa of the colon with that of the small intestine.

The large intestine (fig. 24.16) receives about 500 mL of indigestible food residue per day, reduces it to about 150 mL of feces by absorbing water and salts, and eliminates the feces by defecation.

Gross Anatomy

The large intestine measures about 1.5 m (5 ft) long and 6.5 cm (2.5 in.) in diameter in the cadaver. It is named for its relatively large diameter, not its length. It consists of four regions: the cecum, colon, rectum, and anal canal.

The **cecum**[25] is a pouch in the lower right abdominal quadrant inferior to the ileocecal valve. Attached to its lower end is the wormlike **appendix,** a blind tube 2 to 7 cm long. The mucosa of the appendix is densely populated with lymphocytes and is a significant source of immune cells. Herbivorous primates such as gorillas and orangutans have an enormous cecum, packed with bacteria that digest the plant fiber in their coarse diet. Humans, with their more mixed and easily digested diet, have only the appendix as a vestige of the larger cecum.

The **colon** is that portion of the large intestine between the ileocecal junction and the rectum (not including the cecum, rectum, or anal canal). It is divided into the ascending, transverse, descending, and sigmoid regions. The **ascending colon** begins at the ileocecal valve and passes up the right side of the abdominal cavity. It makes a 90° turn at the **right colic (hepatic) flexure,** near the right lobe of the liver, and becomes the **transverse colon.** This passes horizontally across the upper abdominal cavity and turns 90° downward at the **left colic (splenic) flexure** near the spleen. Here it becomes the **descending colon,** which passes down the left side of the abdominal cavity. Ascending, transverse, and descending colons thus form a squarish, three-sided frame around the small intestine. The pelvic cavity is narrower than the abdominal cavity, so the colon turns medially and downward at the iliac crest, then descends through the pelvic inlet and becomes the rectum. This results in a roughly S-shaped portion called the **sigmoid**[26] **colon.** (Visual examination of this region is performed with an instrument called a *sigmoidoscope.*)

The **rectum,**[27] about 15 cm long, is the continuation of the large intestine into the pelvic cavity. In spite of its name, it is not perfectly straight but has three slight lateral curves as well as an anteroposterior curve. The rectal mucosa is smoother than that of the colon. It has three internal **transverse rectal folds (rectal valves)** that enable it to retain feces while passing gas. The large intestine contains about 7 to 10 L of gas, expelling about 500 mL/day anally as *flatus* and reabsorbing the rest through the colonic wall.

The final 3 cm of the large intestine is the **anal canal** (fig. 24.16b), which passes through the levator ani muscle of the pelvic floor and terminates at the anus. The mucosa of the anal canal forms longitudinal ridges called **anal columns** with depressions between them called **anal sinuses.** As feces pass through the canal, they press against the sinuses and cause them to exude extra mucus, which lubricates the canal during defecation. Prominent **hemorrhoidal veins** form superficial plexuses in the anal columns and around the orifice. Unlike veins in the limbs, they lack valves and are particularly subject to distension and venous pooling. *Hemorrhoids* are permanently distended veins that protrude into the anal canal or form bulges external to the anus.

The muscularis externa of the colon is unusual. Although it completely encircles the colon just as it does the small intestine, its longitudinal fibers are especially concentrated in three thickened, ribbonlike strips called the **taeniae coli** (TEE-nee-ee CO-lye). The muscle tone of the taeniae coli contracts the colon lengthwise and causes its wall to bulge, forming pouches called **haustra**[28] (HAW-stra; singular, *haustrum*). In the rectum and anal canal, however, the longitudinal muscle forms a continuous sheet and haustra are absent. The anus is normally held shut by two muscular rings—an **internal anal sphincter** composed of smooth muscle of the muscularis externa, and an **external anal sphincter** composed of skeletal muscle of the pelvic diaphragm. The internal anal sphincter is under involuntary control and relaxes automatically when the rectum is distended with feces. The external anal sphincter is under voluntary control and enables one to postpone defecation when appropriate.

The ascending and descending colon are retroperitoneal, whereas the transverse and sigmoid colon are covered with serosa and anchored to the posterior abdominal wall by the mesocolon. The serosa of the transverse through sigmoid colon often has clublike fatty pouches of unknown function, called **omental appendages.**

---

[25] *cec* = blind

[26] *sigm* = sigma or S; *oid* = resembling

[27] *rect* = straight

[28] *haustr* = to draw (like a purse string)


Right colic flexure
Transverse colon
Superior mesenteric artery
Haustrum
Ascending colon
Ileocecal valve
Ileum
Cecum
Appendix
Rectum
Anal canal
Greater omentum (retracted)
Left colic flexure
Taenia coli
Mesocolon
Descending colon
Omental appendages
Sigmoid colon
External anal sphincter

(a) Gross anatomy


Rectum
Rectal valve
Anal canal
Levator ani muscle
Hemorrhoidal veins
Internal anal sphincter
External anal sphincter
Anus
Anal columns
Anal sinuses

(b) Anal canal

Figure 24.16 **The Large Intestine.**

• *Which anal sphincter is controlled by the autonomic nervous system? Which is controlled by the somatic nervous system? Explain the basis for your answers.* **APR**

Microscopic Anatomy

The mucosa of the large intestine has a simple columnar epithelium in all regions except the lower half of the anal canal, where it has a nonkeratinized stratified squamous epithelium. The latter provides more resistance to the abrasion caused by the passage of feces. There are no circular folds or villi in the large intestine, but there are intestinal crypts. They are deeper than in the small intestine and have a greater density of goblet cells; mucus is their only significant secretion. The lamina propria and submucosa have an abundance of lymphatic tissue, providing protection from the bacteria that densely populate the large intestine.

The mucosa of the ascending and transverse colon is specialized for fluid and electrolyte absorption. During the process of digestion, a great deal of water is secreted by the salivary glands, stomach, and small intestine. Almost all of this is reabsorbed by the large intestine. When absorption is hindered, as in some bacterial infections, the result is diarrhea—an increase in the liquid eliminated with the feces. Severe diarrhea can lead to serious and sometimes fatal dehydration and electrolyte imbalances.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

17. Name the regions of the large intestine in order from cecum to anus.
18. How does the mucosa of the large intestine differ from that of the small intestine? How does the muscularis externa differ?
19. How do the two anal sphincters differ in location, tissue composition, and function?

24.6 Accessory Glands of Digestion

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the gross and microscopic anatomy of the liver, gallbladder, and bile duct system;
b. describe the functions of the liver and bile;
c. describe the gross and microscopic anatomy of the pancreas; and
d. list the digestive secretions of the pancreas and their functions.

The small intestine receives not only chyme from the stomach but also secretions from the liver and pancreas, which empty into the digestive tract near the junction of the stomach and small intestine. These are regarded as accessory organs of digestion. Another accessory organ, the gallbladder, is associated with the liver in its anatomy and digestive function.

The Liver APR

The liver (fig. 24.17) is a reddish brown gland located immediately inferior to the diaphragm, filling most of the right hypochondriac and epigastric regions. It is the body's largest gland, weighing about 1.4 kg (3 pounds). The liver has numerous functions (table 24.2). From their variety and importance, it is not hard to understand why liver diseases such as cirrhosis, hepatitis, and liver cancer are so serious and often fatal. Only one of these functions contributes to digestion—the secretion of bile. **Bile** is a green fluid containing minerals, cholesterol, neutral fats, phospholipids, bile pigments, and bile acids. The principal pigment is *bilirubin,* derived from the decomposition of hemoglobin. Bacteria of the large intestine metabolize bilirubin to *urobilinogen,* which is responsible for the brown color of feces. In the absence of bile secretion, the feces are grayish white and marked with streaks of undigested fat *(acholic feces). Bile acids (bile salts)* are steroids synthesized from cholesterol. Bile acids and *lecithin,* a phospholipid, emulsify fat—breaking globules of dietary fat into smaller droplets with more surface area exposed to enzyme action. Emulsification greatly enhances the efficiency of fat digestion.

Gross Anatomy

The liver is enclosed in a fibrous capsule and, external to this, most of it is covered by serosa. The serosa is absent from the *bare area* where its superior surface is attached to the diaphragm.

The liver is superficially subdivided into the right, left, quadrate, and caudate lobes. From an anterior view, we see only the large **right lobe** and smaller **left lobe.** They are separated from each other by the **falciform**[29] **ligament,** a sheet of mesentery that attaches the liver to the anterior abdominal wall. Superiorly, the falciform ligament forks into right and left **coronary**[30] **ligaments,** which suspend the liver from the diaphragm. The **round ligament (ligamentum teres),** visible anteriorly at the lower end of the falciform, is a fibrous remnant of the umbilical vein, which carries blood from the umbilical cord to the liver of a fetus.

From the inferior view, we also see a squarish anterior **quadrate lobe** next to the gallbladder and a tail-like **caudate**[31] **lobe** posterior to that. An irregular opening between these lobes, the **porta hepatis,**[32] is a point of entry for the hepatic portal vein and hepatic arteries and a point of exit for the bile passages. All of these blood vessels and bile passages travel in the lesser omentum. The gallbladder adheres to a depression on the inferior surface of the liver between the right and quadrate lobes. The posterior aspect of the liver has a deep groove (sulcus) occupied by the inferior vena cava.

Microscopic Anatomy

The interior of the liver is filled with an enormous number of tiny cylinders called **hepatic lobules,** about 2 mm long by 1 mm in diameter. A lobule consists of a **central vein** passing down its core, surrounded by radiating sheets of cuboidal cells called **hepatocytes** (fig. 24.18). Imagine spreading a book wide open until its front

---

[29] *falci* = sickle; *form* = shape
[30] *coron* = crown; *ary* = like, resembling
[31] *caud* = tail
[32] *porta* = gateway, entrance; *hepatis* = of the liver



(a) Location

(b) Anterior view

(c) Inferior view

Figure 24.17 Gross Anatomy of the Liver. APR

TABLE 24.2	Functions of the Liver
Digestion	Synthesizes bile acids and lecithin, which emulsify fat and promote its digestion.
Carbohydrate metabolism	Converts dietary fructose and galactose to glucose. Stabilizes blood glucose concentration by storing excess glucose as glycogen *(glycogenesis),* releasing glucose from glycogen when needed *(glycogenolysis),* and synthesizing glucose from fats and amino acids *(gluconeogenesis)* when glucose demand exceeds glycogen reserves. Receives lactic acid generated by anaerobic fermentation in skeletal muscle and other tissues and converts it to pyruvic acid or glucose 6-phosphate for storage or energy-releasing metabolism.
Lipid metabolism	Degrades chylomicron remnants. Carries out most of the body's fat synthesis *(lipogenesis)* and synthesizes cholesterol and phospholipids. Produces *very-low-density lipoproteins* (VLDLs) to transport lipids to adipose tissue and other tissues for storage or use, and stores fat in its own cells. Carries out most fatty acid oxidation. Produces protein shells of *high-density lipoproteins* (HDLs), which pick up excess cholesterol from other tissues and return it to the liver; liver excretes the excess cholesterol in bile.
Protein and amino acid metabolism	Metabolizes amino acids; removes their $—NH_2$ and converts the resulting ammonia to *urea,* the major nitrogenous waste in the urine. Synthesizes some amino acids.
Vitamin and mineral metabolism	Converts vitamin D_3 to calcidiol, a step in the synthesis of the hormone calcitriol; stores a 3- to 4-month supply of vitamin D. Stores a 10-month supply of vitamin A and enough vitamin B_{12} to last one to several years. Stores iron in ferritin and releases it as needed. Excretes excess calcium by way of the bile.
Synthesis of plasma proteins	Synthesizes nearly all the proteins of blood plasma, including albumin, alpha and beta globulins, fibrinogen, prothrombin, and several other clotting factors. (Does not synthesize plasma enzymes, peptide hormones, or gamma globulins.)
Disposal of drugs, toxins, and hormones	Detoxifies alcohol, antibiotics, and many other drugs. Metabolizes bilirubin from RBC breakdown and excretes it as bile pigments. Deactivates thyroxine and steroid hormones and excretes them or converts them to a form more easily excreted by the kidneys.
Cleansing of blood	Hepatic macrophages cleanse the blood of bacteria and other foreign matter.

and back covers touch. The pages of the book would fan out around the spine somewhat like the plates of hepatocytes fan out from the central vein of a liver lobule.

Each plate of hepatocytes is an epithelium one or two cells thick. The spaces between the plates are blood-filled channels called **hepatic sinusoids.** The sinusoids are lined by a fenestrated endothelium that separates the hepatocytes from the blood cells, but allows blood plasma into the space between the hepatocytes and endothelium. The hepatocytes have a brush border of microvilli that project into this space. After a meal, as blood from the intestines circulates



Hepatocytes
Bile canaliculi
Stroma
Central vein
Hepatic triad:
Branch of hepatic portal vein
Branch of hepatic artery proper
Bile ductule
Hepatic sinusoid
Stroma
(a)
Stroma
Central vein
Hepatic lobule
Branch of hepatic portal vein
Bile ductule
Lymphatic vessel
Branch of hepatic artery proper
(b)
0.5 mm
Hepatic macrophage
Hepatocyte
Erythrocytes in sinusoid
Endothelial cells
Fenestration
Sinusoid
Blood flow
(c)

© McGraw-Hill Education/Dennis Strete, photographer

Figure 24.18 **Microscopic Anatomy of the Liver.** (a) Hepatic lobules and their relationship to the blood vessels and bile tributaries. (b) Histological section of the liver. (c) A hepatic sinusoid.

- *What blood vessels in chapter 21 contribute blood to the hepatic sinusoids?* APR through the hepatic sinusoids, the hepatocytes rapidly remove glucose, amino acids, iron, vitamins, and other nutrients for metabolism or storage. They also remove and degrade hormones, toxins, bile pigments, and drugs. Conversely, they secrete albumin, lipoproteins, clotting factors, glucose, and other products into the blood. The sinusoids also contain phagocytic cells called **hepatic macrophages,** which remove bacteria and debris from the blood.

The hepatocytes secrete bile into narrow channels, the **bile canaliculi,** between the cell plates within each lobule. Bile passes from there into the small **bile ductules** between lobules. These ductules lead ultimately to the **right** and **left hepatic ducts,** which exit the inferior surface of the liver at the porta hepatis.

The hepatic lobules are separated by a sparse connective tissue stroma. In cross sections, the stroma is especially visible in the triangular areas where three or more lobules meet. Here, there is often a **hepatic triad** of two blood vessels and a bile ductule. The blood vessels are small branches of the hepatic arteries and hepatic portal vein.

Circulation

The liver receives blood from two sources: about 70% from the **hepatic portal vein** and 30% from the **hepatic arteries.** The hepatic portal vein receives blood from veins of the stomach, intestines, pancreas, and spleen, and carries it into the liver at the porta hepatis; see the hepatic portal system in table 21.7 (p. 589). All nutrients absorbed by the small intestine reach the liver by this route except for lipids (transported in the lymphatic system). Arterial blood bound for the liver exits the aorta at the celiac trunk and follows the route shown in figure 21.23 (p. 585): celiac trunk ⟶ common hepatic artery ⟶ hepatic artery proper ⟶ right and left hepatic arteries, which enter the liver at the porta. These arteries deliver oxygen and other materials to the liver. Branches of the hepatic portal vein and hepatic arteries meet each other in the spaces between the liver lobules and both drain into the liver sinusoids. Hence, there is an unusual mixing of venous and arterial blood in the sinusoids. After processing by the hepatocytes, the blood collects in the central vein at the core of the lobule. Blood from the central veins ultimately converges in three **hepatic veins** that exit the superior surface of the liver and empty into the nearby inferior vena cava.

The Gallbladder and Bile Passages

Since the only digestive role of the liver is bile secretion, we will further trace the flow of bile through organs associated with the liver. The most conspicuous of these is the **gallbladder,** a pear-shaped sac on the underside of the liver that serves to store and concentrate the bile (fig. 24.19). It is about 10 cm long and internally lined by a highly folded mucosa with a simple columnar epithelium. Its head *(fundus)* usually projects slightly beyond the inferior



Figure 24.19 **Gross Anatomy of the Gallbladder, Pancreas, and Bile Passages.** The liver is omitted to show the gallbladder, which adheres to its inferior surface, and to show the hepatic ducts, which emerge from the liver tissue. APR

DEEPER INSIGHT 24.4

Gallstones (Cholelithiasis)

Gallstones (biliary calculi) are hard masses in the gallbladder or bile ducts, usually composed of cholesterol, calcium carbonate, and bilirubin. *Cholelithiasis,*[33] the formation or presence of gallstones, is most common in obese women over the age of 40, but certainly not limited to them. It can result from excess cholesterol or a variety of other causes. The gallbladder may contain several gallstones, some over 1 cm in diameter. Gallstones can cause excruciating pain when they obstruct the bile ducts or when the gallbladder or bile ducts contract. When they block the flow of bile into the duodenum, they cause jaundice (yellowing of the skin due to bile pigment accumulation), poor fat digestion, and impaired absorption of fat-soluble vitamins. Gallstones can be removed by minimally invasive laparoscopic surgery.

margin of the liver. Its neck *(cervix)* leads into the **cystic duct,** through which bile enters and leaves the gallbladder.

When the two hepatic ducts leave the porta hepatis, they converge almost immediately to form the **common hepatic duct.** This duct goes only a short distance before joining the cystic duct; it then becomes the **bile duct,** which descends through the lesser omentum to the duodenum. The bile duct and main pancreatic duct both approach the major duodenal papilla. Usually, just before emptying into the duodenum, the two ducts join each other and form an expanded chamber called the **hepatopancreatic ampulla.** A muscular **hepatopancreatic sphincter** regulates the release of bile and pancreatic juice from the ampulla into the duodenum.

The Pancreas

Most digestion is carried out by pancreatic enzymes. The **pancreas** (fig. 24.19) is a spongy digestive gland posterior to the greater curvature of the stomach. It is about 15 cm long and divided into a globose *head* encircled on the right by the duodenum; a midportion called the *body;* and a blunt, tapered *tail* on the left near the spleen. It has a very thin connective tissue capsule and a nodular surface. It is retroperitoneal; its anterior surface is covered by parietal peritoneum, whereas its posterior surface contacts the aorta, left kidney, left adrenal gland, and other viscera on the posterior body wall.

The pancreas is both an endocrine and exocrine gland. Its endocrine part is the pancreatic islets, which secrete the hormones insulin and glucagon (see p. 509). Islets are most concentrated in the pancreatic tail. Ninety-nine percent of the pancreas is exocrine tissue, which secretes enzymes and sodium bicarbonate. The exocrine pancreas is a compound tubuloacinar gland—that is, it has a system of branching ducts whose finest branches end in sacs of secretory cells, the acini. The cells of the acini exhibit a high density of rough ER and *zymogen granules,* which are vesicles filled with secretion (fig. 24.20). The smaller ducts converge on a main **pancreatic duct,** which runs lengthwise through the middle of the gland and joins the bile duct at the hepatopancreatic ampulla. Usually, there is a smaller **accessory pancreatic duct** that branches from the main pancreatic duct and opens independently into the duodenum at the minor duodenal papilla, proximal to the major papilla. The accessory duct bypasses the hepatopancreatic sphincter and allows pancreatic juice to be released into the duodenum even when bile is not.



© McGraw-Hill Education/Dennis Strete, photographer

Figure 24.20 **Microscopic Anatomy of the Pancreas.** (a) An acinus. (b) Histological section of the exocrine tissue and some of the connective tissue stroma.

The pancreas secretes 1,200 to 1,500 mL of *pancreatic juice* per day. This fluid is an alkaline mixture of water, sodium bicarbonate, other electrolytes, enzymes, and zymogens (table 24.3). Zymogens are inactive precursors of enzymes that are activated after they are secreted.

---

[33] *chole* = bile, gall; *lith* = stone; *iasis* = medical condition

TABLE 24.3 Exocrine Secretions of the Pancreas

Secretion	Function
Sodium bicarbonate	Neutralizes HCl
Zymogens	Converted to active digestive enzymes after secretion
Trypsinogen	Becomes trypsin, which digests protein
Chymotrypsinogen	Becomes chymotrypsin, which digests protein
Procarboxypeptidase	Becomes carboxypeptidase, which hydrolyzes the terminal amino acid from the carboxyl (—COOH) end of small peptides
Enzymes	
Pancreatic amylase	Digests starch
Pancreatic lipase	Digests fat
Ribonuclease	Digests RNA
Deoxyribonuclease	Digests DNA

Before You Go On

Answer the following questions to test your understanding of the preceding section:

20. What does the liver contribute to digestion? List several of its nondigestive functions.
21. Describe the structure of a hepatic lobule and the blood flow through a lobule.
22. Describe the pathway that bile takes from a hepatocyte that secretes it to the point where it enters the duodenum.
23. Describe the pathway taken by pancreatic juice from a gland acinus to the duodenum.
24. Explain why the pancreas is considered to be both an endocrine and an exocrine gland. How does the pancreas contribute to digestion?

24.7 Developmental and Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the prenatal development of the digestive tract, liver, and pancreas;
b. describe the structural and functional changes in the digestive system in old age; and
c. define and describe some common disorders of the digestive system.

Prenatal Development

The digestive system is one of the earliest organ systems to appear in the embryonic stage of development. Shortly after the three-layered embryonic disc is formed at 2 weeks, it elongates in the cephalocaudal (head-to-tail) direction. Endodermal pockets form at each end that become the foregut and hindgut (fig. 24.21a). Initially, there is a wide opening between the embryo and the yolk sac, but as the embryo continues to grow, the passage between them becomes constricted and a distinct tubular midgut appears. Temporarily, the midgut continues to communicate with the yolk sac through a narrow **vitelline duct.** In week 4, the anterior end of the digestive tract breaks through to form the mouth, and 3 weeks later, the posterior end breaks through to form the anus.

Growth of the embryonic body segments *(somites)* causes the lateral margins of the embryo to fold inward, changing the flat embryonic disc into a more cylindrical body and separating the embryonic body cavity from the yolk sac. By week 5, the gut is an elongated tube suspended from the body wall by the posterior (dorsal) mesentery (fig. 24.21b). Although the inner epithelial lining of the gut is endoderm, the tube is covered by a layer of mesoderm that gives rise to all other tissue layers of the digestive tract: the lamina propria, submucosa, muscle layers, and serosa.

At 4 weeks, the foregut exhibits a dilation that is the first sign of the future stomach (fig. 24.22). Further development of the digestive tract entails elongation, rotation, and differentiation of its regions into the esophagus, stomach, and small and large intestines. At 6 weeks, the body cavity is crowded by the rapidly growing liver and the intestine is so long and crowded that a loop of it herniates into the umbilical cord. This loop normally withdraws back into the enlarged body cavity in week 10, but in some tragic cases it fails to do so, resulting in severely deformed infants with part of the bowel outside the body *(omphalocele*[34]*).*

The liver appears in the middle of week 3 as a **liver bud,** a pocketlike outgrowth of the endodermal tube at the junction of the foregut and midgut. Its connection to the gut narrows and becomes the bile duct. A small outgrowth from the ventral side of the bile duct becomes the gallbladder and cystic duct. By week 12, the liver secretes bile into the gut, so the gut contents become dark green. The liver produces blood cells throughout most of fetal development, but this function gradually subsides in the last 2 months.

The pancreas originates as two buds, a **dorsal** and **ventral pancreatic bud,** around week 4. The ventral bud eventually rotates dorsally and merges with the dorsal bud. Pancreatic islets appear in the third month and begin secreting insulin at 5 months.

At birth, the digestive tract contains dark, sticky feces called **meconium,** which is discharged in the first few bowel movements of the neonate.

The Aging Digestive System

Like most other organ systems, the digestive system shows significant degenerative change *(senescence)* in old age. Less saliva is secreted in old age, making food less flavorful, swallowing more

---

[34] *omphalo* = navel, umbilicus; *cele* = swelling, herniation


Ectoderm
Amniotic cavity
Foregut
Hindgut
Heart tube
Lung bud
Liver bud
Midgut
Allantois
Vitelline duct
Yolk sac
Yolk sac
Endoderm
Allantois
Day 14
Day 21
Day 24
Day 28

(a) Longitudinal sections showing cephalocaudal folding


Amniotic cavity
Amniotic cavity
Surface ectoderm
Surface ectoderm
Dorsal mesentery
Mesoderm
Neural tube
Gut
Notochord
Peritoneal cavity
Yolk sac
Vitelline duct
Day 14
Day 21
Day 28

(b) Cross sections showing lateral folding

Figure 24.21 **Embryonic Development of the Digestive Tract.** (a) Cephalocaudal (head-to-tail) folding from days 14 to 28 produces the foregut and hindgut. The connection between the midgut and yolk sac grows progressively narrower. (b) Lateral folding over the same time period encloses the tubular gut and reduces the yolk sac connection to a narrow vitelline duct. The 28-day embryo in (b) is sectioned a little farther caudally than the 28-day embryo in (a) to show a region of hindgut already fully enclosed within the peritoneal cavity.

difficult, and the teeth more prone to caries. Many elderly people wear dentures because they have lost their teeth to caries and periodontal disease. The stratified squamous epithelium of the oral cavity and esophagus is thinner and more vulnerable to abrasion.

The gastric mucosa atrophies and secretes less acid and intrinsic factor. Acid deficiency reduces the absorption of calcium, iron, zinc, and folic acid. The declining level of intrinsic factor reduces the absorption of vitamin B_{12}. Since this vitamin is needed for hemopoiesis, the deficiency can lead to anemia.

Heartburn becomes more common in old age as the weakening lower esophageal sphincter fails to prevent reflux into the esophagus. The most common digestive complaint of older people is constipation, which results from the reduced muscle tone and weaker peristalsis of the colon. This seems to stem from a combination of factors: atrophy of the muscularis externa, reduced sensitivity to neurotransmitters, less fiber and water in the diet, and less exercise. The liver, gallbladder, and pancreas show only slightly reduced function in old age. Any drop in liver



Figure 24.22 **Lateral View of the 5-Week Embryo.** The primordial stomach is present as a foregut dilation, and the liver and pancreatic buds are present. The loop of midgut approaching the vitelline duct herniates into the umbilical cord within the next week.

function, however, makes it harder to detoxify drugs and can contribute to overmedication.

Many older people eat less because of lower energy demand and appetite, because declining sensory functions make food less appealing, and because reduced mobility makes it more difficult to shop and prepare meals. However, they need fewer calories than younger people because they have lower basal metabolic rates and tend to be less physically active. Protein, vitamin, and mineral requirements remain essentially unchanged, although vitamin and mineral supplements may be needed to compensate for reduced food intake and intestinal absorption. Malnutrition is common among older people and is an important factor in anemia and reduced immunity.

Digestive Disorders

The digestive system is subject to a wide variety of disorders, several of which are described in table 24.4. Disorders of motility include difficulty swallowing *(dysphagia),* gastroesophageal reflux disease (GERD), and pyloric obstruction. Inflammatory diseases

TABLE 24.4	**Some Digestive System Diseases**
Acute pancreatitis	Severe pancreatic inflammation, perhaps caused by trauma, leading to leakage of pancreatic enzymes into parenchyma, where they digest tissue and cause inflammation and hemorrhage.
Appendicitis	Inflammation of the appendix, with swelling, pain, and a threat of gangrene, perforation, and peritonitis.
Ascites	Accumulation of serous fluid in the peritoneal cavity, often causing extreme distension of the abdomen. Most often caused by cirrhosis of the liver and frequently associated with alcoholism. The diseased liver "weeps" fluid into the abdomen.
Cirrhosis[35] of the liver	An irreversible inflammatory disease of the liver often caused by alcoholism. Gives the liver a "cobbly" appearance and hard consistency due to fibrosis and nodular regeneration of damaged tissue. Obstruction of bile ducts causes jaundice, and obstruction of the circulation causes new vessels to grow and bypass the liver, leaving the liver subject to hypoxia, further necrosis, and failure.
Crohn[36] disease	Inflammation of small and large intestines, similar to ulcerative colitis in symptoms and hereditary predisposition. Produces granular lesions and fibrosis of intestine; diarrhea; and lower abdominal pain.
Diverticulitis	Presence of inflamed herniations (outpocketings, diverticula) of the colon, associated especially with low-fiber diets. Diverticula may rupture, leading to peritonitis.
Dysphagia[37]	Difficulty swallowing. Can result from esophageal obstructions (tumors, constrictions) or impaired peristalsis (due to neuromuscular disorders).
Hiatal hernia	Protrusion of part of the stomach into the thoracic cavity, where the negative thoracic pressure may cause it to balloon. Often causes gastroesophageal reflux (especially when a person is supine).
Ulcerative colitis	Chronic inflammation resulting in ulceration of the large intestine, especially the sigmoid colon and rectum. Tends to be hereditary but exact causes are not well known.

Disorders Described Elsewhere

Constipation	679
Dental caries	661, 679
Diarrhea	673
Esophageal cancer	663
Gallstones	677
Gastroesophageal reflux disease	663
Gingivitis	661
Hemorrhoids	671
Impacted molars	661
Megacolon	452
Mumps	662
Omphalocele	678
Peptic ulcer	668
Periodontal disease	661, 679

---

[35] *cirrho* = orange-yellow; *osis* = condition
[36] Burrill B. Crohn (1884–1983), American gastroenterologist
[37] *dys* = bad, difficult, abnormal; *phag* = eating, swallowing

include esophagitis, gastritis, appendicitis, colitis, diverticulitis, pancreatitis, hepatitis, and cirrhosis. Cancer can occur in virtually every part of the digestive system: oral, esophageal, gastric, colon, rectal, hepatic, and pancreatic. Colon and pancreatic cancer are among the leading causes of cancer deaths in the United States.

Digestive disorders can be manifested in a variety of signs and symptoms: anorexia (loss of appetite), vomiting, constipation, diarrhea, abdominal pain, or gastrointestinal bleeding. Many of these are nonspecific; they do not by themselves identify a particular digestive disorder. Gastrointestinal bleeding, for example, can result from *varices* (varicose veins) in the digestive tract wall, intestinal polyps, GI inflammation, hemorrhoids, peptic ulcers, parasitic infections, or cancer. Nausea is even less specific; it may result not only from nondigestive disorders but also from such causes as tumors in the abdomen or brainstem, trauma to the urogenital organs, or inner-ear dysfunction.

It was remarked earlier that the foregut, midgut, and hindgut are defined by differences in arterial blood supply. This embryonic division also extends to the nerve supply and to the perception of pain from the digestive tract. Gastrointestinal pain is often perceived as if it was coming from the abdominal wall (see *referred pain,* p. 465). Pain arising from the foregut is referred to the epigastric region, midgut pain to the umbilical region, and hindgut pain to the hypogastric region.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

25. Explain why the foregut and hindgut appear in the embryo earlier than the midgut.
26. What accessory digestive gland arises as a single bud from the embryonic gut? What gland arises as a pair of buds that later merge?
27. Explain why dental caries, constipation, and heartburn become more common as the digestive system ages.
28. Explain why gastrointestinal bleeding and nausea provide only inconclusive evidence for the existence and location of a digestive system disorder.

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

24.1 Digestive Processes and General Anatomy (p. 654)

1. The essential function of the digestive system and the five stages in which it performs this function
2. The distinction between the digestive tract and the accessory organs of this system, and the members of both categories
3. The tissue layers and sublayers of the wall of the digestive tract, and the histology and functional role of each layer
4. The cranial nerves that supply the digestive system; the parasympathetic and sympathetic innervation of the system; and the effects of those two divisions on digestion
5. The anatomical components of the enteric nervous system, and its role in digestion
6. Components of the foregut, midgut, and hindgut, and the blood supply to each
7. The hepatic portal system and its relationship to the digestive system
8. The relationships of the posterior and anterior mesenteries to the digestive system, to the peritoneum, and to the serosa; anatomy of the greater and lesser omentum and the mesocolon
9. The meaning of *intraperitoneal* and *retroperitoneal* organs, and which digestive organs are in each class

24.2 The Mouth Through Esophagus (p. 658)

1. The diverse functions of the mouth (oral cavity)
2. All of the anatomical boundaries and contents of the oral cavity
3. Anatomy and functions of the cheeks and lips
4. Anatomy and functions of the tongue, and the distinction between its intrinsic and extrinsic muscles
5. The boundaries, structure, and function of the hard and soft palates; the palatoglossal and palatopharyngeal arches and their relationship with the palatine tonsils
6. Names of the adult teeth (dentition); the tissues and anatomy of an individual tooth; and the relationship of the teeth to the alveoli, periodontal ligaments, and gingivae
7. The purposes served by mastication
8. The composition and functions of saliva
9. The distinction between intrinsic and extrinsic salivary glands; the names and locations of the extrinsic salivary glands and the points at which their saliva is released into the oral cavity
10. The duct system, acini, and types of secretory cells in a salivary gland
11. The neural control of salivation
12. The anatomical regions and three constrictor muscles of the pharynx
13. The points at which the esophagus begins and ends; its upper and lower sphincters and their purposes; and the histological structure of its wall
14. The neural control of swallowing

24.3 The Stomach (p. 664)

1. The location and orientation of the stomach; its internal volume; and its functions
2. The shape and anatomical regions of the stomach; its relationship to the greater and lesser omentum; and the sphincters that regulate its entrance and exit
3. Ways in which the stomach wall differs histologically from the esophagus and other parts of the digestive tract
4. Gastric pits and their relationship with the glands of the mucosa
5. The three types of glands in the gastric mucosa; how they differ in location and

function; the five kinds of cells in these glands; and the secretions of each cell type and the functions of those secretions
6. How the stomach is protected from digesting itself

24.4 The Small Intestine (p. 667)

1. The essential functions of the small intestine; and how its exceptional length is related to its functions
2. The anatomical landmarks that define the beginning and end of the duodenum; its length; its relationship to the peritoneum; the structure of its wall; its relationship to the bile and pancreatic ducts; and how its functions differ from other parts of the small intestine
3. How the jejunum is defined relative to the other parts of the small intestine; its length; how its role differs from that of the duodenum and ileum; and how its role is related to its unique appearance
4. How the ileum is defined relative to the other parts of the small intestine; its length; how its role differs from that of the duodenum and jejunum; and how its role is related to its anatomy
5. The structure of the ileocecal junction and valve, and functions of the valve
6. How the circular folds, villi, and brush border contribute to the functional efficiency of the small intestine
7. The structure of a villus; the cell types of its epithelium; the contents of its core; and how its blood capillaries and lacteal differ in their roles in nutrient absorption
8. The role of the brush border in contact digestion and nutrient absorption
9. The structure and cellular composition of the intestinal crypts of the small intestine
10. Features of the small intestine that serve to protect it from stomach acid and bacterial invasion

24.5 The Large Intestine (p. 671)

1. Functions of the large intestine
2. The four regions of the large intestine, their defining landmarks, and their total length
3. The location, structure, and functional significance of the appendix
4. The four segments of the colon and the anatomical landmarks of the transition from one to another
5. The extent, shape, and internal anatomy of the rectum and anal canal
6. The unusual musculature of the large intestine, including its taeniae coli and internal and external anal sphincters
7. The relationship of different parts of the large intestine to the peritoneum and mesocolon, and the omental appendages of its serosa
8. How the mucosa of the large intestine compares and contrasts with that of the small intestine

24.6 Accessory Glands of Digestion (p. 673)

1. The size, shape, location, and functions of the liver, and which of its functions contribute(s) to digestion
2. The composition and functional significance of bile
3. The lobes and ligaments of the liver, and the locations of the porta hepatis and gallbladder
4. The structure of the hepatic lobules and sinusoids; the relationship of the hepatocytes to the blood in the sinusoids; and the location and role of the hepatic macrophages
5. The venous and arterial blood supplies to the liver; where the venous and arterial blood mix; and the route by which blood exits the liver
6. Where bile is produced, and the route by which it is secreted from the liver
7. The location, anatomy, and function of the gallbladder; and anatomy of the bile passages that connect the liver, gallbladder, and duodenum
8. The location, gross anatomy, histology, and both endocrine and exocrine (digestive) functions of the pancreas
9. The anatomical relationships of the pancreatic ducts to the bile duct and duodenum
10. Functions of the exocrine secretions of the pancreas

24.7 Developmental and Clinical Perspectives (p. 678)

1. How the elongation and folding of the embryonic disc give rise to the foregut, hindgut, and finally the midgut
2. How the development of the digestive tract explains why its mucosal epithelium is endodermal whereas the other tissue layers of its wall are mesodermal
3. How the simple tubular embryonic gut transforms into a tract with regional differentiation into esophagus, stomach, and intestines
4. How the liver and pancreas arise from the embryonic gut
5. How aging affects salivation, the dentition, the gastrointestinal mucosa, intestinal motility, liver function, appetite, and nutrition
6. Some categories of digestive system disorders; examples in each category; and some common signs and symptoms of gastrointestinal disease

Testing Your Recall

1. All of the following are retroperitoneal *except*
   a. the liver.
   b. the pancreas.
   c. the duodenum.
   d. the ascending colon.
   e. the descending colon.
2. The falciform ligament attaches the _____ to the abdominal wall.
   a. colon
   b. liver
   c. spleen
   d. pancreas
   e. stomach
3. A brush border is found on the
   a. goblet cells.
   b. enterocytes.
   c. enteroendocrine cells.
   d. parietal cells.
   e. chief cells.
4. The yolk sac is connected to the embryonic _____ by way of the vitelline duct.
   a. liver bud
   b. stalk
   c. foregut
   d. midgut
   e. hindgut
5. Lacteals absorb dietary
   a. proteins.
   b. carbohydrates.
   c. enzymes.
   d. vitamins.
   e. lipids.
6. All of the following contribute to the absorptive surface area of the small intestine *except*
   a. its length.
   b. the brush border.
   c. haustra.
   d. circular folds.
   e. villi.
7. Which of the following is a periodontal tissue?
   a. gingiva
   b. enamel
   c. cementum
   d. pulp
   e. dentin
8. The _____ of the stomach most closely resemble the _____ of the small intestine.
   a. gastric pits, intestinal crypts
   b. pyloric glands, intestinal crypts

c. rugae, Peyer patches
d. parietal cells, goblet cells
e. gastric glands, duodenal glands

9. Which of the following cells secrete digestive enzymes?
   a. chief cells
   b. mucous neck cells
   c. parietal cells
   d. goblet cells
   e. enteroendocrine cells
10. The tissue layer between the muscularis mucosae and muscularis externa of the digestive tract is
    a. the mucosa.
    b. the lamina propria.
    c. the submucosa.
    d. the serosa.
    e. the adventitia.
11. The alimentary canal has an extensive nervous network called the _____.
12. The passage of chyme from the stomach into the duodenum is controlled by a muscular ring called the _____.
13. The _____ salivary gland is named for its location near the ear.
14. The _____ is a complex of veins that carry blood from the stomach and intestines to the liver.
15. Nervous stimulation of gastrointestinal activity is mediated mainly through the parasympathetic fibers of the _____ nerves.
16. Hydrochloric acid is secreted by _____ cells of the stomach.
17. Hepatic macrophages occur in blood-filled spaces of the liver called _____.
18. The superior opening into the stomach is called the _____.
19. The root of a tooth is covered with a calcified tissue called _____.
20. Protrusions of the tongue surface, some of which bear taste buds, are called _____.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. gastro-
2. entero-
3. aliment-
4. retro-
5. bucco-
6. pyloro-
7. ruga-
8. sigmo-
9. recto-
10. hepato-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. The liver and pancreas are retroperitoneal.
2. A tooth is composed mostly of enamel.
3. Hepatocytes secrete bile into the hepatic sinusoids.
4. The small intestine is much shorter in a living person than it is after death.
5. Peristalsis is controlled by the myenteric nerve plexus.
6. The pylorus is a gateway from the stomach to the duodenum.
7. The greater omentum suspends the stomach from the body wall.
8. Salivary acini can be composed of mucous cells, serous cells, or both.
9. In all parts of the digestive tract, the muscularis externa has two layers.
10. The external anal sphincter is under voluntary control; the internal sphincter is not.

Answers in appendix A

Testing Your Comprehension

1. People who suffer from GERD (see Deeper Insight 24.2) when they lie down often find their heartburn is worse when they lie on the right side than when they lie on the left. Give an anatomical explanation for this effect.
2. Cystic fibrosis (CF) is characterized by unusually thick, sticky mucus that obstructs the respiratory tract and pancreatic duct. Predict the effect of CF on digestion, nutrition, and growth in childhood.
3. Explain why the small intestine would function poorly if it had the same type of mucosal epithelium as the esophagus.
4. News reports of patients (especially children) in need of organ transplants often prompt people to call and offer to donate one of their organs, such as a kidney, to save the patient's life. If you worked in an organ donor program, what would you say to a well-meaning volunteer offering to donate a liver?
5. What do you think is the functional significance of the Peyer patches in the distal ileum? Why should they be concentrated here but not found in the duodenum or jejunum?



The renal glomerulus, a mass of capillaries where the kidney filters the blood (SEM of a polymer cast)

© SPL/Science Source

CHAPTER

25

THE URINARY SYSTEM

CHAPTER OUTLINE

25.1 Functions of the Urinary System 685

25.2 The Kidney 686
- Position and Associated Structures 686
- Gross Anatomy 686
- Renal Circulation 687
- Renal Innervation 689
- The Nephron 689

25.3 The Ureters, Urinary Bladder, and Urethra 695
- The Ureters 696
- The Urinary Bladder 696
- The Urethra 696

25.4 Developmental and Clinical Perspectives 697
- Prenatal Development 697
- The Aging Urinary System 698
- Urinary System Disorders 700

Study Guide 701

DEEPER INSIGHTS

25.1 Blood and Protein in the Urine 692
25.2 The Kidney and Life on Dry Land 694
25.3 Kidney Stones (Nephrolithiasis) 696
25.4 Urinary Tract Infections 696
25.5 Developmental Abnormalities of the Urinary System 698

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:

- Transitional epithelium (p. 61)
- General exocrine gland architecture (p. 76)
- Fenestrated capillaries (p. 568)

Anatomy & Physiology REVEALED
aprevealed.com

Module 13: Urinary System

To live is to metabolize, and metabolism unavoidably generates a variety of waste products that are not merely unneeded by the body, but indeed toxic if they are allowed to accumulate. We rid the body of some of these wastes through the respiratory and digestive tracts and the sweat glands, but the urinary system is the principal means of waste excretion. The kidneys are glands that separate metabolic wastes from the blood. The rest of the urinary system serves only for the transport, storage, and elimination of urine.

The tasks of the kidneys go far beyond waste excretion, though. They also play indispensable roles in regulating blood volume and pressure, erythrocyte count, blood gases, blood pH, and electrolyte and acid–base balance. In performing these tasks, they have a very close physiological relationship with the endocrine, circulatory, and respiratory systems.

Anatomically, however, the urinary system is closely associated with the reproductive system. In many animals the eggs and sperm are emitted through the urinary tract, and the two systems share some aspects of their evolutionary history, embryonic development, and adult anatomy. This is reflected in humans, where the systems develop together in the embryo and, in the male, the urethra continues to serve as a passage for both urine and sperm. Thus, the urinary and reproductive systems are often collectively called the *urogenital (U-G) system,* and *urologists* treat both urinary and reproductive disorders. Because of their anatomical and developmental relationship, we consider the urinary and reproductive systems in these last two chapters.

25.1 Functions of the Urinary System APR

Expected Learning Outcomes

When you have completed this section, you should be able to

a. name and locate the organs of the urinary system;
b. list several functions of the kidneys in addition to urine formation;
c. define *excretion;* and
d. identify the major nitrogenous waste excreted by the kidneys.

The **urinary system** serves primarily to cleanse the blood of metabolic wastes and eliminate them in the urine. It consists of six principal organs: two **kidneys,** two **ureters,** the **urinary bladder,** and the **urethra.** Figure 25.1 shows these organs in anterior and



(a) Anterior view (b) Posterior view

Figure 25.1 **The Urinary System.** Organs of the urinary system are indicated in boldface.
- *On yourself or another person, palpate the location of the kidneys. What landmark can be used to locate them?* APR

posterior views. The urinary tract has especially important relationships with the uterus and vagina in females and the prostate gland in males. These relationships are best appreciated from the sagittal views in figures 26.1 (male) and 26.10 (female) (pp. 706 and 716). Most of the focus of the present chapter is on the kidneys.

Although the primary function of this system is excretion, the kidneys play more roles than are commonly realized:

- They filter blood plasma and excrete the toxic metabolic wastes.
- They regulate blood volume, pressure, and osmolarity by regulating water output.
- They regulate the electrolyte and acid–base balance of the body fluids.
- They secrete the hormone *erythropoietin,* which stimulates the production of red blood cells and thus supports the oxygen-carrying capacity of the blood.
- They contribute to calcium homeostasis and bone metabolism by performing a step in the synthesis of the hormone calcitriol (vitamin D).
- They clear hormones and drugs from the blood and thereby limit their action.
- They detoxify free radicals.
- In conditions of extreme starvation, they help to support blood glucose level by synthesizing glucose from amino acids (a process called *gluconeogenesis*).

Excretion, the most obvious function of the urinary system, is the process of extracting wastes from the body fluids and eliminating them, thus preventing metabolic poisoning of the body. Among other things, the kidneys excrete nitrogen-containing molecules called **nitrogenous wastes.** The most abundant of these is **urea,** a product of protein metabolism. If the kidneys do not function adequately, one develops a condition called **azotemia**[1] (AZ-oh-TEE-me-uh), in which the urea concentration in the blood *(blood urea nitrogen, BUN)* is abnormally high. In severe renal failure, azotemia progresses to **uremia** (you-REE-me-uh), a syndrome of diarrhea, vomiting, dyspnea (labored breathing), and cardiac arrhythmia. Convulsions, coma, and death can follow within a few days, underscoring the importance of adequate renal function.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. State at least four kidney functions other than forming urine.
2. What is the most abundant nitrogenous waste in the urine? What terms describe an abnormally high level of this waste in the blood, and poisoning by this waste?

25.2 The Kidney AP|R

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the location and general appearance of the kidney, and its relationship to neighboring organs;
b. identify the major external and internal features of the kidney;
c. trace the flow of blood through the kidney;
d. describe the nerve supply to the kidney;
e. trace the flow of fluid through the renal tubules; and
f. state the function of each segment of a renal tubule.

Position and Associated Structures

The kidneys lie against the posterior abdominal wall at the level of vertebrae T12 to L3. Rib 12 crosses the approximate middle of the left kidney. The right kidney is slightly lower than the left because of the space occupied by the large right lobe of the liver above it. The kidneys are retroperitoneal, along with the ureters, urinary bladder, renal artery and vein, and the adrenal[2] glands (fig. 25.2). The left adrenal gland rests on the superior pole of that kidney, and the right adrenal gland lies against the superomedial surface of its kidney. Their functions are not as directly related to the kidneys as their spatial relationship might suggest, although the kidneys and adrenals do influence each other.

Gross Anatomy

The kidney is a compound tubular gland containing about 1.2 million functional excretory units called **nephrons**[3] (NEF-rons). Each kidney weighs about 150 g and measures about 11 cm long, 6 cm wide, and 3 cm thick—about the size of a bar of bath soap. The lateral surface is convex, whereas the medial surface is concave and has a slit, the **hilum,** where it receives the renal nerves, blood vessels, lymphatics, and ureter.

The kidney is protected by three layers of connective tissue (fig. 25.2): (1) A fibrous **renal fascia,** immediately deep to the parietal peritoneum, binds the kidney and associated organs to the abdominal wall. (2) The **perirenal fat capsule,** a layer of adipose tissue, cushions the kidney and holds it in place. (3) The **fibrous capsule** encloses the kidney like a cellophane wrapper anchored at the hilum, and protects it from trauma and infection. The kidneys are suspended by collagen fibers that extend from the fibrous capsule, through the fat, to the renal fascia. The renal fascia is fused with the peritoneum anteriorly and with the fascia of the lumbar muscles posteriorly. In spite of all this, the kidneys drop about 3 cm when one goes from lying down to standing, as when getting out of bed in the morning. Under some circumstances, they become detached and drift even lower, with pathological results (see nephroptosis, or "floating kidney," in table 25.1, p. 700).

---

[1] *azot* = nitrogen; *emia* = blood condition

[2] *ad* = to, toward, near; *ren* = kidney; *al* = pertaining to

[3] *nephro* = kidney



Figure 25.2 **Location of the Kidney.** Cross section of the abdomen at the level of vertebra L1, showing the relationship of the kidney to the body wall and peritoneum.

- *If the kidney were* not *retroperitoneal, where on this figure would you have to relocate it?*

The renal parenchyma—the glandular tissue that produces the urine—appears C-shaped in frontal section. It encircles a medial cavity, the **renal sinus,** occupied by blood and lymphatic vessels, nerves, and urine-collecting structures. Adipose tissue fills the remaining space in the sinus and holds these structures in place.

The parenchyma is divided into two zones: an outer **renal cortex** about 1 cm thick and an inner **renal medulla** facing the sinus (fig. 25.3). Extensions of the cortex called **renal columns** project toward the sinus and divide the medulla into 6 to 10 **renal pyramids.** Each pyramid is conical, with a broad base facing the cortex and a blunt point called the **renal papilla** facing the sinus. One pyramid and the overlying cortex constitute one *lobe* of the kidney.

The papilla of each renal pyramid is nestled in a cup called a **minor calyx**[4] (CAY-lix), which collects its urine. Two or three minor calyces (CAY-lih-seez) converge to form a **major calyx,** and two or three major calyces converge in the sinus to form the funnel-like **renal pelvis.**[5] The ureter is a tubular continuation of the renal pelvis that drains the urine down to the urinary bladder.

Renal Circulation

Although the kidneys account for only 0.4% of the body weight, they receive about 1.2 liters of blood per minute, or 21% of the cardiac output (the *renal fraction*)—more for the purpose of waste removal than to meet the metabolic needs of the kidney tissue. This is a hint of how important the kidneys are in regulating blood volume and composition.

The larger divisions of the renal circulation are shown in figure 25.4. Each kidney is supplied by a **renal artery** arising from the aorta. Just before or after entering the hilum, the renal artery divides into a few **segmental arteries,** and each of these gives rise to a few **interlobar arteries.** An interlobar artery penetrates each renal column and travels between the pyramids toward the *corticomedullary junction,* the boundary between the cortex and medulla. Along the way, it branches again to form **arcuate arteries,** which make a sharp 90° bend and travel along the base of the pyramid. Each arcuate artery gives rise to several **cortical radiate arteries,** which pass upward into the cortex.

The finer branches of the circulation are shown in figure 25.5. As a cortical radiate artery ascends through the cortex, a series of **afferent arterioles** arise from it at nearly right angles like the limbs of a pine tree. Each afferent arteriole supplies one nephron. It leads to a spheroidal mass of capillaries called a **glomerulus**[6] (glo-MERR-you-lus), enclosed in a nephron structure called the *glomerular capsule,* to be discussed later. The glomerulus is drained by an **efferent arteriole.** The efferent arteriole usually leads to a plexus of **peritubular capillaries,** named for the fact that they form a network around the tubules of the nephron. These capillaries pick up the water and solutes reabsorbed by the tubules.

From the peritubular capillaries, blood flows to **cortical radiate veins, arcuate veins, interlobar veins,** and the **renal vein,** in that order. These veins travel parallel to the arteries of the

---

[4] *calyx* = cup
[5] *pelv* = basin
[6] *glomer* = ball; *ulus* = little


Renal cortex
Pyramid of renal medulla
Minor calyx
Major calyx
Renal column
Renal artery
Renal sinus
Renal vein
Renal pelvis
Ureter
(a)
(b)

© McGraw-Hill Education/Rebecca Gray, photographer

Figure 25.3 **Gross Anatomy of the Kidney (Posterior Views).** (a) Photograph of a frontal section. (b) Major anatomical features. APR


Cortical radiate artery and vein
Interlobar artery and vein
Segmental artery
Renal medulla
Renal artery and vein
Renal cortex
Arcuate artery and vein
(a)
Aorta
Renal a.
Segmental a.
Interlobar a.
Arcuate a.
Cortical radiate a.
Afferent arteriole
Glomerulus
Efferent arteriole
Peritubular capillaries
Vasa recta
Cortical radiate v.
Arcuate v.
Interlobar v.
Renal v.
Inferior vena cava
(b)

Figure 25.4 **Renal Circulation.** (a) The larger blood vessels of the kidney. (b) Flow chart of renal circulation. The pathway through the vasa recta (instead of peritubular capillaries) applies only to the juxtamedullary nephrons.

- *Is the kidney in this figure shown from an anterior or posterior view? How can you tell?*



Cortical nephron
Cortex
Medulla
Juxtamedullary nephron
PCT
DCT
Peritubular capillaries
Afferent arteriole
Glomerulus
Efferent arteriole
Cortical radiate artery
Cortical radiate vein
Corticomedullary junction
Arcuate artery
Arcuate vein
Vasa recta
Collecting duct
Nephron loop

Figure 25.5 **Renal Microcirculation.** For clarity, the vasa recta are shown only on the left and peritubular capillaries only on the right. In the juxtamedullary nephron (left), the efferent arteriole gives rise to the vasa recta of the medulla. In the cortical nephron (right), the nephron loop barely dips into the medulla, and the efferent arteriole gives rise to peritubular capillaries. (DCT = distal convoluted tubule; PCT = proximal convoluted tubule)

same names. (There are, however, no segmental veins corresponding to the segmental arteries.) The renal vein leaves the hilum and drains into the inferior vena cava.

The renal medulla receives only 1% to 2% of the total renal blood flow, supplied by a network of vessels called the **vasa recta.**[7] These arise from the nephrons in the deep cortex, closest to the medulla *(juxtamedullary nephrons).* Here, the efferent arterioles descend immediately into the medulla and give off the vasa recta instead of peritubular capillaries. Capillaries of the vasa recta lead into venules that ascend and empty into the arcuate and cortical radiate veins. The capillaries are wedged into the tight spaces between the medullary parts of the renal tubule, and carry away water and solutes reabsorbed by those sections of the tubule. Figure 25.4b summarizes the route of renal blood flow.

Apply What You Know

Can you identify a portal system in the renal circulation?

Renal Innervation

Wrapped around each renal artery is a **renal plexus** of nerves and ganglia (see fig. 16.6, p. 449). The plexus follows branches of the renal artery into the kidney, issuing nerve fibers to the blood vessels and convoluted tubules of the nephrons. The renal plexus includes both sympathetic and parasympathetic innervation, as well as afferent pain fibers from the kidneys en route to the spinal cord. The sympathetic nerves arise from the abdominal aortic plexus (especially its superior mesenteric and celiac ganglia). They control renal blood flow and the rate of urine production; when blood pressure falls, they stimulate the kidneys to secrete renin, an enzyme that activates hormonal mechanisms for restoring blood pressure. The parasympathetic innervation arises from the vagus nerves. Its function in the kidneys is unknown.

The Nephron APR

A nephron (fig. 25.6) consists of two principal parts: a *renal corpuscle,* which filters the blood plasma, and a long *renal tubule,* which converts the filtrate to urine.

---

[7] *vasa* = vessels; *recta* = straight


Renal capsule
Renal cortex
Nephron
Collecting duct
Renal medulla
Minor calyx
Renal papilla
(a)
Renal corpuscle:
Glomerular capsule
Glomerulus
Efferent arteriole
Afferent arteriole
Proximal convoluted tubule (PCT)
Distal convoluted tubule (DCT)
Nephron loop:
Descending limb
Ascending limb
Thick segment
Thin segment
Collecting duct (CD)
Papillary duct
Key
Flow of blood
Flow of tubular fluid
(b)
Cortical nephron
Convoluted tubule (PCT and DCT)
Juxtamedullary nephron
Cortex
Medulla
Nephron loops
Collecting duct
(c)

Figure 25.6 Microscopic Anatomy of the Nephron. (a) Location of the nephrons in one wedge-shaped lobe of the kidney. (b) Structure of a nephron. The nephron is stretched out to separate the convoluted tubules and is greatly shortened for the purpose of illustration. (c) The true proportions of the nephron loops relative to the convoluted tubules. Three nephrons are shown. Their proximal and distal convoluted tubules are commingled in a single mass in each nephron. Note the extreme lengths of the nephron loops.

Before we embark on the microscopic anatomy of the nephron, it will be helpful to have a broad overview of the process of urine production. This knowledge will lend functional meaning to the structural details. The kidney converts blood plasma to urine in four stages (fig. 25.7):

① **Glomerular filtration** is the passage of fluid from the bloodstream into the nephron, carrying not only wastes but also chemicals useful to the body. The fluid filtered from the blood is called *glomerular filtrate.* In contrast to the blood, it is free of cells and very low in protein. After it passes into the renal tubule, its composition is quickly modified by the following processes, and we call it *tubular fluid.*

② **Tubular reabsorption,** in which useful substances such as glucose are reabsorbed from the tubular fluid and returned to the blood.

③ **Tubular secretion,** in which tubule cells extract blood-borne substances such as hydrogen ions and some drugs from the peritubular capillaries and add them to the tubular fluid, to be eliminated in the urine.

④ **Water conservation,** achieved by reabsorbing variable amounts of water from the fluid so the body can eliminate metabolic wastes without losing excess water. If water reabsorption did not occur, a typical adult hypothetically would produce 180 liters of urine per day—although in reality, this would be an impossible feat considering that we have only about 5 liters of blood and about 40 liters of total body water. Usually, the kidneys excrete urine that is **hypertonic** to the blood plasma—that is, it has a higher ratio of waste solutes to water than the plasma does. Water reabsorption occurs in all parts of the renal tubule, but is the final change occurring in the urine as it passes through the collecting duct. The fluid is regarded as urine once it has entered this duct.


Blood flow
① Glomerular filtration
Creates a plasmalike filtrate of the blood
Renal corpuscle
Flow of filtrate
② Tubular reabsorption
Removes useful solutes from the tubular fluid, returns them to the blood
Peritubular capillaries
③ Tubular secretion
Removes additional wastes from the blood, adds them to the tubular fluid
Renal tubule
④ Water conservation
Removes water from the urine and returns it to blood; concentrates wastes
H_2O
H_2O
H_2O
Urine

Figure 25.7 **Basic Steps in the Formation of Urine.** Steps 2 and 3 occur simultaneously. APR

We can now examine the individual segments of the nephron, their contribution to the foregoing processes, and how their structures are adapted to their individual roles.

The Renal Corpuscle

The **renal corpuscle** (fig. 25.8) consists of the glomerulus and, enclosing it, a two-layered **glomerular capsule.** The inner, or visceral, layer of the glomerular capsule consists of elaborate cells called *podocytes* wrapped around the capillaries. The parietal (outer) layer is a simple squamous epithelium. The two layers are separated by a filtrate-collecting **capsular space.** In tissue sections, the capsular space appears as an empty circular or C-shaped space around the glomerulus.

Opposite sides of the renal corpuscle are called the vascular pole and urinary pole. At the **vascular pole,** the afferent arteriole enters the capsule, bringing blood to the glomerulus; close beside it, the efferent arteriole exits the capsule and carries blood away. The afferent arteriole is conspicuously larger than the efferent arteriole; that is, the glomerulus has a large inlet and small outlet. This gives its capillaries an unusually high blood pressure, which is the driving force of glomerular filtration. At the **urinary pole,** the parietal wall of the capsule turns away from the corpuscle and gives rise to the renal tubule. The simple squamous epithelium of the capsule becomes simple cuboidal in the renal tubule.

A **podocyte**[8] is shaped somewhat like an octopus, with a bulbous cell body and several thick arms (fig. 25.9). Each arm has numerous little extensions called **foot processes (pedicels**[9]**)** that wrap around the glomerular blood capillaries and interdigitate with each other, like wrapping your hands around a pipe and lacing your fingers together. The foot processes have narrow **filtration slits** between them.

The job of the renal corpuscle is glomerular filtration: Blood cells and plasma proteins are retained in the bloodstream because they are too large to pass through the barriers described shortly. Water, however, freely passes through and carries along small solute particles such as urea, glucose, amino acids, and electrolytes. The high blood pressure in the glomerulus drives the water and small solutes out through the capillary walls, into the capsular space. Pressure in the capsular space drives the filtrate into the renal tubule and ultimately all the way to the calyces and renal pelvis.

---

[8] *podo* = foot; *cyte* = cell
[9] *pedi* = foot; *cel* = little


Key
Flow of blood
Flow of filtrate
Afferent arteriole
Blood flow
Efferent arteriole
Blood flow
Glomerular capsule:
Parietal layer
Capsular space
Podocytes of visceral layer
Glomerulus
Proximal convoluted tubule
Glomerular capillaries (podocytes and capillary wall removed)
(a)
Proximal convoluted tubules
Peritubular capillary
Glomerular capillaries
Glomerular capsule:
Visceral layer
Capsular space
Parietal layer
Afferent arteriole
Macula densa
Nephron loop
(b)
100 µm

© McGraw-Hill Education/Al Telser, photographer

Figure 25.8 **The Renal Corpuscle.** (a) Anatomy of the corpuscle. (b) Light micrograph of the renal corpuscle and sections of the surrounding renal tubule. AP|R

Anything leaving the bloodstream must pass through a barrier called the **filtration membrane,** composed of three layers (fig. 25.9c):

1. **Capillary endothelium.** Glomerular capillaries have a fenestrated endothelium (see fig. 21.6, p. 569) honeycombed with large filtration pores about 70 to 90 nm in diameter. They are much more permeable than capillaries elsewhere, although the filtration pores are small enough to hold back blood cells.
2. **Basement membrane.** This is a layer of proteoglycan gel (a protein–carbohydrate complex) beneath the endothelial cells. For large molecules to pass through it is like trying to pass sand through a kitchen sponge. A few particles may penetrate its small spaces, but most are held back. On the basis of size alone, the basement membrane excludes any molecules larger than 8 nm. Some smaller molecules, however, are also held back by a negative electrical charge on the proteoglycans. Blood albumin is slightly less than 7 nm in diameter, but it is also negatively charged and thus repelled by the basement membrane. Therefore, the protein concentration is about 7% in the blood plasma but only 0.03% in the glomerular filtrate. The filtrate also contains traces of some polypeptide hormones.
3. **Filtration slits.** The slits between the podocyte foot processes are about 30 nm wide and are also negatively charged. This charge is a final barrier to large anions such as proteins.

Almost any molecule smaller than 3 nm passes freely through the filtration membrane. This includes water, electrolytes, glucose, fatty acids, amino acids, nitrogenous wastes, and vitamins. Such substances have about the same concentration in the filtrate as in the blood plasma. Some substances of low molecular weight are retained in the bloodstream because they are bound to plasma proteins that cannot get through the membrane. For example, most calcium, iron, and thyroid hormone in the blood are bound to plasma proteins that retard their filtration by the kidneys. The small fraction that is unbound, however, passes freely through the membrane and appears in the urine.

DEEPER INSIGHT 25.1

Blood and Protein in the Urine

Urinalysis, one of the most routine procedures performed upon patient admission and in routine medical examinations, is an analysis of the physical and chemical properties of the urine. It includes tests for blood and protein, both of which are normally lacking from urine. Damage to the filtration membrane, however, can result in blood or protein in the urine, called *hematuria*[10] and *proteinuria (albuminuria),* respectively. These can be signs of kidney infections, trauma, and other kidney diseases (see table 25.1 at the end of the chapter). They can be temporary conditions of little concern, or they can be chronic and gravely serious. Long-distance runners and swimmers often show temporary proteinuria and hematuria. Strenuous exercise reduces renal circulation as blood shifts to the muscles. With a reduced blood flow, the glomeruli deteriorate and leak protein and sometimes blood cells into the filtrate.

The Renal Tubule

The **renal tubule** is a duct that leads away from the glomerular capsule and ends at the tip of a medullary pyramid. It is about 3 cm long and divided into four major regions: the *proximal convoluted tubule, nephron loop, distal convoluted tubule,* and *collecting duct* (see fig. 25.6). Only the first three of these are parts of an individual nephron; the collecting duct receives fluid from many nephrons. Each region of the renal tubule has unique physiological properties and roles in the production of urine.

The **proximal convoluted tubule (PCT)** arises from the glomerular capsule. It is the longest and most coiled of the four regions and thus dominates histological sections of renal cortex. The PCT has a simple cuboidal epithelium with prominent

---

[10] *hemat* = blood; *uria* = urine condition


Efferent arteriole
Podocyte cell body
Glomerulus
Pedicels (separated by narrow filtration slits)
Afferent arteriole
(a)
100 μm
(b)
5 μm
Capsular space
Blood plasma
Erythrocyte
Capillary endothelium
Pedicels
Podocytes
Foot processes
Basement membrane
Endothelial cell
Filtration pores
Filtration slits
Podocyte cell body
(c)
0.5 μm
(d)

© Steve Gschmeissner/Getty Images

© Dr. Donald Fawcett/Science Source

© Biophoto Associates/Science Source

Figure 25.9 **Structure of the Glomerulus.** (a) A polymer cast of the glomerulus and nearby arteries (SEM). Note that the efferent arteriole is much narrower than the afferent arteriole, which causes blood pressure in the glomerulus to be unusually high. (b) Blood capillaries of the glomerulus closely wrapped in the spidery podocytes that form the visceral layer of the glomerular capsule (SEM). (c) A blood capillary and podocyte showing filtration pores of the capillary and filtration slits of the podocyte (TEM). (d) The production of glomerular filtrate by the passage of fluid through the endothelium and filtration slits.

- *Which is larger, the efferent arteriole or afferent arteriole? How does this affect the function of the glomerulus?*

microvilli (a brush border), which attests to the great deal of absorption that occurs here. The microvilli give the epithelium a distinctively shaggy look in tissue sections.

The PCT carries out both tubular reabsorption and secretion. It reabsorbs about 65% of the glomerular filtrate, and consumes about 6% of one's daily ATP expenditure in doing so. On the surface facing the tubular fluid, the epithelial cells have a variety of membrane transport proteins that carry solutes into the cells by active transport and facilitated diffusion. These solutes and water pass through the cell cytoplasm (the **transcellular**[11] **route**) and either diffuse out or are actively pumped out the basal and lateral cell surfaces, adjacent to peritubular blood capillaries waiting to receive them. Water and solutes also take a **paracellular**[12] **route** between the epithelial cells. Even though the cells are joined by tight junctions, these are quite leaky and allow a substantial amount of fluid to pass through.

---

[11] *trans* = across
[12] *para* = next to

Among the solutes reabsorbed by the PCT are sodium, potassium, magnesium, phosphate, chloride, bicarbonate, glucose, amino acids, lactate, protein, smaller peptides, amino acids, urea, and uric acid. Water follows by osmosis.

By tubular secretion, the PCT extracts many solutes from the blood and adds them to the tubular fluid: hydrogen and bicarbonate ions, ammonia, urea, uric acid, creatinine, bile acids, pollutants, and some drugs (aspirin, penicillin, and morphine, for example). Notice that urea and uric acid go both ways between the blood and tubular fluid, transported by both tubular reabsorption and tubular secretion. The kidneys do not completely cleanse the blood of these wastes; indeed, they remove only about half of the urea, but this is sufficient to keep the blood urea concentration down to a safe level.

Apply What You Know

The proximal convoluted tubule exhibits some of the same structural adaptations as the small intestine, and for the same reason. Discuss what they have in common, and the reason for it.

The **nephron loop (loop of Henle**[13]) is a long U-shaped portion of the renal tubule found mostly in the medulla. It begins where the PCT straightens out and dips toward or into the medulla, forming the **descending limb** of the loop. At its deep end, the loop turns 180° and forms the **ascending limb,** which returns to the cortex, traveling parallel and close to the descending limb (see fig. 25.6c). Some parts of the loop, called **thick segments,** have a simple cuboidal epithelium, whereas the **thin segment** has a simple squamous epithelium. The thick segments engage in the active transport of salts through the tubule wall, so they have a high ATP requirement and are loaded with mitochondria to supply it. This is why the cells are relatively thick (cuboidal). The thin segment is not engaged in active transport but is relatively permeable to water. It does not need as much ATP or as many mitochondria, which is why the cells are relatively thin (squamous). The thick segments form the initial part of the descending limb and part or all of the ascending limb. The thin segment forms the lower part of the descending limb and in some nephrons, rounds the bend and continues partway up the ascending limb.

The nephron loop reabsorbs about 25% of the sodium, potassium, and chloride and 15% of the water that was in the glomerular filtrate. Its primary function, however, is to maintain a gradient of osmolarity in the renal medulla. It does this by pumping Na^+, K^+, and Cl^- from the ascending limb into the medullary tissue fluid. At the corticomedullary junction, the tissue fluid is isotonic with the blood plasma (300 milliosmoles/liter), but deep in the medulla, it is four times as concentrated. The significance of this is explained later.

The nephron loops are not identical in all nephrons. Nephrons just beneath the renal capsule, close to the kidney surface, are called **cortical nephrons.** They have relatively short nephron loops that dip only slightly into the outer medulla before turning back (see fig. 25.6), or turn back even before leaving the cortex. Some cortical nephrons have no nephron loops at all. Nephrons close to the medulla are called **juxtamedullary**[14] **nephrons.** They have very long nephron loops that extend nearly to the apex of the renal pyramid. Only 15% of the nephrons are juxtamedullary, but these are almost solely responsible for maintaining the osmotic gradient of the medulla.

Immediately after reentering the renal cortex, the ascending limb of the nephron loop contacts the afferent and efferent arterioles at the vascular pole of the renal corpuscle. The two arterioles and the end of the nephron loop form the **juxtaglomerular** (JUX-tuh-glo-MER-you-lur) **apparatus**—a device for monitoring the fluid entering the distal convoluted tubule and adjusting the performance of the nephron (fig. 25.10). Three specialized cell types are found here:

1. The **macula densa**[15] is a patch of slender, closely spaced epithelial cells at the end of the loop on the side facing the afferent arteriole. These cells apparently act as sensors that monitor the flow or composition of the tubular fluid and communicate with the cells described next.
2. **Granular (juxtaglomerular) cells** are enlarged smooth muscle cells in the afferent arteriole and to some extent in the efferent arteriole, directly across from the macula densa. When stimulated by the macula, they dilate or constrict the arterioles. Granular cells also secrete *renin,* an enzyme that triggers corrective changes in blood pressure.
3. **Mesangial**[16] (mez-AN-jee-ul) **cells** occupy the cleft between the afferent and efferent arterioles and the spaces between the capillaries of the glomerulus. They are connected to the macula

DEEPER INSIGHT 25.2

The Kidney and Life on Dry Land

Physiologists first suspected that the nephron loop plays a role in water conservation because of their studies of a variety of animal species. Animals that must conserve water have longer, more numerous nephron loops than animals with little need to conserve it. Fish and amphibians lack nephron loops and produce urine that is isotonic to their blood plasma. Aquatic mammals such as beavers have short nephron loops and only slightly hypertonic urine.

But the kangaroo rat, a desert rodent, provides an instructive contrast. It lives on seeds and other dry foods and can live without drinking any water at all. The water produced by its aerobic respiration is enough to meet its needs because its kidneys are extraordinarily efficient at conserving it. They have extremely long nephron loops and produce urine that is 10 to 14 times as concentrated as their blood plasma (compared with about 4 times, at most, in humans).

Comparative studies thus suggested a hypothesis for the function of the nephron loop that was confirmed through a long line of ensuing research. This shows how comparative anatomy provides suggestions and insights into function and why physiologists do not study human function in isolation from other species.

---

[13] Friedrich G. J. Henle (1809–85), German anatomist

[14] *juxta* = next to

[15] *macula* = spot, patch; *densa* = dense

[16] *mes* = in the middle; *angi* = vessels



Figure 25.10 The Juxtaglomerular Apparatus.

densa and granular cells by gap junctions and communicate with them by means of hormonelike secretions. They also form a supportive matrix for the glomerulus, phagocytize tissue debris, and constrict or relax the glomerular capillaries to regulate their blood flow and filtration rate.

The **distal convoluted tubule (DCT)** is a coiled part of the renal tubule located in the cortex and beginning immediately after the macula densa. It is the end of the nephron. The DCT is shorter and less convoluted than the PCT, so fewer sections of it are seen in histological sections. It has a simple cuboidal epithelium with smooth-surfaced cells nearly devoid of microvilli. It absorbs variable amounts of sodium, calcium, chloride, and water, and secretes potassium and hydrogen into the tubular fluid. Unlike the PCT, which absorbs most solutes and water at a constant rate, the DCT reabsorbs these at variable rates determined by the hormone *aldosterone,* which regulates sodium and potassium excretion. *Parathyroid hormone* acts on both the PCT and DCT to regulate calcium and phosphate excretion.

The **collecting duct** is a straight tubule that passes down into the medulla. It is part of the renal tubule but not part of the nephron; the nephron and collecting duct have separate embryonic origins. The cortical part of the collecting duct receives fluid from the DCTs of several nephrons. The duct then continues into the medulla, where the greater part of it lies. Near the renal papilla, several collecting ducts converge to form a larger, short stretch called the **papillary duct.** About 30 papillary ducts drain from each papilla into a minor calyx. Once the urine drains into a minor calyx, it undergoes no further change in composition or concentration.

The collecting duct is lined with a simple cuboidal epithelium with two types of cells—intercalated (“in between”) cells and principal cells. **Intercalated cells** play a role in regulating the body’s acid–base balance by secreting either H^+ or bicarbonate ions (HCO_3^-) into the urine. **Principal cells** reabsorb Na^+ and water and secrete K^+ into the urine. They represent the kidney’s last chance to adjust the water content and thus the osmolarity of the urine. The principal cells also have water channels called *aquaporins* in their membranes. As the tubular fluid descends through the collecting duct, water passes by osmosis through these channels, out of the tubule and into the increasingly saline tissue fluid of the medulla. The osmotic gradient created by the nephron loop makes this reabsorption of water possible. The reabsorbed water is carried away by the blood capillaries of the vasa recta.

The collecting duct is influenced by two hormones called *natriuretic peptides,* which increase sodium excretion in the urine, and another called *antidiuretic hormone,* which promotes water retention and reduces urine volume.

To summarize, the flow of fluid from the point where the glomerular filtrate is formed to the point where urine leaves the kidney is glomerular capsule ⟶ proximal convoluted tubule ⟶ nephron loop ⟶ distal convoluted tubule ⟶ collecting duct ⟶ papillary duct ⟶ minor calyx ⟶ major calyx ⟶ renal pelvis ⟶ ureter.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

3. Arrange the following in order from the most numerous to the least numerous structures in a kidney: glomeruli, major calyces, minor calyces, cortical radiate arteries, interlobar arteries.
4. Trace the path taken by one red blood cell from the renal artery to the renal vein.
5. Concisely state the functions of the glomerulus, PCT, nephron loop, DCT, and collecting duct.
6. Describe the location and appearance of podocytes and explain their function.
7. Consider one molecule of urea in the urine. Trace the route that it took from the bloodstream to the point where it left the kidney.

25.3 The Ureters, Urinary Bladder, and Urethra

Expected Learning Outcome

When you have completed this section, you should be able to

a. describe the functional anatomy of the ureters, urinary bladder, and male and female urethra.

Urine is produced continually, but fortunately it does not drain continually from the body. Urination *(micturition)* is episodic—occurring when we allow it. This is made possible by an apparatus for storing urine and by neural controls for its timely release.

DEEPER INSIGHT 25.3

Kidney Stones (Nephrolithiasis)[17]

A *renal calculus*[18] (kidney stone) is a hard granule of calcium, phosphate, uric acid, and protein. Renal calculi form in the renal pelvis and are usually small enough to pass unnoticed in the urine flow. Some, however, grow as large as a few centimeters and block the renal pelvis or ureter, which can lead to the destruction of nephrons as pressure builds in the kidney. A large, jagged calculus passing down the ureter stimulates strong contractions that can be excruciatingly painful. It can also damage the ureter and cause hematuria. Causes of renal calculi include hypercalcemia (excess calcium in the blood), dehydration, pH imbalances, frequent urinary tract infections, or an enlarged prostate gland causing urine retention. Calculi are sometimes treated with stone-dissolving drugs, but often they require surgical removal. A nonsurgical technique called *lithotripsy*[19] uses ultrasound to pulverize the calculi into fine granules easily passed in the urine.

The Ureters

The renal pelvis funnels urine into the ureter, a retroperitoneal, muscular tube that extends to the urinary bladder. The ureter is about 25 cm long and reaches a maximum diameter of about 1.7 cm near the bladder. The lumen is very narrow and is easily obstructed by kidney stones (see Deeper Insight 25.3). The ureters pass posterior to the bladder and enter it from below, penetrating obliquely through its muscular wall and opening onto its floor. A small flap of bladder mucosa acts as a valve at the opening of each ureter to keep urine from backing up into the ureter when the bladder contracts.

The ureter has three layers: an inner mucosa, a middle muscularis, and an outer adventitia. Transitional epithelium lines the urinary tract beginning in the minor calyces of the kidneys and extending through the ureters, urinary bladder, and part of the urethra. The muscularis consists of two layers of smooth muscle over most of the ureter's length, but a third layer appears in the lower ureter. The inner muscular layer consists of longitudinal muscle cells; the cells in the next layer superficial to this have a circular arrangement; and the third and outermost layer in the lower ureter is again longitudinal. Peristaltic waves of contraction in the muscularis drive urine from the renal pelvis down to the bladder. The adventitia is a connective tissue layer that binds the ureter to the surrounding tissues. It blends with the capsule of the kidney at the superior end and with the connective tissue of the bladder wall at the inferior end.

The Urinary Bladder

The urinary bladder (fig. 25.11) is a muscular sac on the floor of the pelvic cavity, inferior to the peritoneum and posterior to the pubic symphysis. It is covered by parietal peritoneum on its flattened superior surface and by a fibrous adventitia elsewhere. The muscular layer of the bladder, called the **detrusor**[20] (deh-TROO-zur)**,** consists of three indistinctly separated layers of smooth muscle. The mucosa has conspicuous wrinkles called **rugae**[21] (ROO-jee). Filling of the bladder stretches and flattens the rugae, and they reappear when the bladder empties. The floor of the bladder has a permanently smooth area called the **trigone,**[22] a triangle defined by the openings of the urethra and two ureters. This is a common site of bladder infection (see Deeper Insight 25.4).

The mucosa is lined with transitional epithelium, whose unique surface *umbrella cells* protect it from the osmotic effect of hypertonic urine as described in chapter 3 (p. 62). The epithelium is better developed here than anywhere else in the urinary tract, since it is subject to the most prolonged exposure to urine. It is typically five or six cells thick in the empty bladder, but thins to about two or three cells thick when the bladder is full. The bladder is a highly distensible organ, capable of holding up to 800 mL of urine. For photographs of the relationship of the bladder and urethra to other pelvic organs in both sexes, see figure A.14 (p. 342).

The Urethra

The urethra conveys urine out of the body. In the female, it is a tube 3 to 4 cm long bound to the anterior wall of the vagina by fibrous connective tissue (fig. 25.11a). Its opening, the **external urethral orifice,** lies between the vaginal orifice and clitoris. The male urethra (fig. 25.11b) is about 18 cm long and has three regions: (1) The **prostatic urethra** begins at the urinary bladder and passes for about 2.5 cm through the prostate gland. During orgasm, it receives semen from the reproductive glands. (2) The **membranous urethra** is a short (0.5 cm), thin-walled portion where the urethra passes through the muscular floor of the pelvic cavity. (3) The **spongy (penile) urethra** is about 15 cm long and passes through the penis to the external urethral orifice. It is named for the *corpus spongiosum,*

DEEPER INSIGHT 25.4

Urinary Tract Infections

Infection of the urinary bladder is called *cystitis.*[23] It is especially common in females because bacteria such as *Escherichia coli* can travel easily from the perineum up the short urethra. Because of this risk, young girls should be taught never to wipe the anus in a forward direction. If cystitis is untreated, bacteria can spread up the ureters and cause *pyelitis,*[24] infection of the renal pelvis. If it reaches the renal cortex and nephrons, it is called *pyelonephritis.* Kidney infections can also result from invasion by blood-borne bacteria. Urine stagnation due to renal calculi or prostate enlargement increases the risk of infection.

---

[17] *nephro* = kidney; *lith* = stone; *iasis* = medical condition
[18] *calc* = calcium, stone; *ul* = little
[19] *litho* = stone; *tripsy* = crushing
[20] *de* = down; *trus* = push
[21] *ruga* = fold, wrinkle
[22] *tri* = three; *gon* = angle
[23] *cyst* = bladder; *itis* = inflammation
[24] *pyel* = pelvis


Ureter
Detrusor muscle
Ureteral openings
Trigone
Urethra
Urogenital diaphragm
External urethral orifice
Internal urethral sphincter
External urethral sphincter

(a) Female


Ureter
Rugae
Ureteral openings
Trigone
Prostate gland
Prostatic urethra
Membranous urethra
Bulbourethral gland
Spongy (penile) urethra
Corpus spongiosum
Penis
External urethral orifice
Detrusor muscle
Internal urethral sphincter
Urogenital diaphragm
External urethral sphincter

(b) Male

Figure 25.11 **The Urinary Bladder and Urethra (Frontal Sections).**
• *Why would an enlarged prostate gland make it more difficult to empty the bladder?*

an erectile tissue that surrounds it. The male urethra assumes an S shape: It passes downward from the bladder, turns anteriorly as it enters the root of the penis, and then turns about 90° downward again as it enters the external, pendant part of the penis. The penile urethra has mucous **urethral glands.** In both sexes, the mucosa has a transitional epithelium near the bladder, a stratified squamous epithelium near the external orifice, and between these, areas of stratified and pseudostratified columnar epithelium in the long urethra of the male and only pseudostratified in the short urethra of the female.

In both sexes, the detrusor muscle is thickened near the urethra to form an **internal urethral sphincter,** which compresses the urethra and retains urine in the bladder. Since this sphincter is composed of smooth muscle, it is under involuntary control. Where the urethra passes through the pelvic floor, it is encircled by an **external urethral sphincter** of skeletal muscle, which provides voluntary control over the voiding of urine.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

8. Describe the anatomical relationship of the ureter to the renal pelvis and to the bladder wall.
9. Compare and contrast the structure and function of the internal and external urethral sphincters.
10. Contrast the structure of the bladder wall when the bladder is empty with when it is full.
11. Name and define the three segments of the male urethra.

25.4 Developmental and Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the embryonic development of the urinary system;
b. describe the degenerative changes that occur in old age;
c. describe the causes and effects of renal failure; and
d. briefly define or describe several urinary system diseases.

Prenatal Development

Perhaps surprisingly, the embryonic urinary system develops two pairs of primitive, temporary kidneys before "settling down" and producing the permanent pair. The system develops as if replaying the evolutionary history of the vertebrate urinary system. Early in week 4, a rudimentary kidney called the *pronephros*[25] appears in the cervical region, resembling the kidneys of many fish and amphibian embryos and larvae. The pronephros disappears by the end of that week. As it degenerates, a second kidney, the *mesonephros,*[26] appears in the thoracic to lumbar region. It functions in the embryos of all vertebrates, but is of minor importance in most mammals, where wastes are eliminated via the placenta. Most of the mesonephros disappears by the end of month 2, but its collecting duct, the *mesonephric duct,* remains and contributes importantly to the male reproductive tract (see p. 727). This duct opens into an embryonic *cloaca,* a temporary rectumlike receiving chamber for the digestive, urinary, and reproductive systems. The final kidney, the *metanephros,*[27] appears in week 5 and thus overlaps the existence of the mesonephros.

The permanent urinary tract begins with a pouch called the **ureteric bud** growing from the lower end of each mesonephric duct. The closed, upper end of the bud dilates and branches to form the renal pelvis, then the major and minor calyces, and finally the collecting ducts (fig. 25.12). Each collecting duct has a cap of metanephric kidney tissue over its tip. The duct induces this cap to differentiate into an S-shaped tubule (fig. 25.13a). Blood capillaries grow into one end of the tubule and form a glomerulus as the tubule grows around it to form the double-walled glomerular capsule. The other end of the tubule breaks through to become continuous with the collecting duct. The tubule gradually lengthens and differentiates into the proximal convoluted tubule, nephron loop, and distal convoluted tubule. By the time of birth, each kidney will have formed over 1 million nephrons in this manner. No more nephrons form after birth, but the existing ones continue to grow. The kidney surface is lumpy at birth but smooths out because of nephron growth.

The kidneys originate in the pelvic region and later migrate superiorly—a movement called **ascent of the kidney.** Initially, the kidney is supplied by a pelvic branch of the aorta, but as it ascends, new arteries higher and higher on the aorta take over the job of supplying the kidney, while the lower arteries degenerate.

In weeks 4 to 7, the cloaca divides into an anterior *urogenital (U-G) sinus* and a posterior *anal canal.* The superior part of the U-G sinus forms the urinary bladder, and the inferior part forms the urethra. In infants and children, the urinary bladder is located in the abdomen. It begins to drop into the greater pelvis at about 6 years of age, but does not enter the lesser pelvis and become a true pelvic organ until after puberty. Early in its development, the bladder is connected to the allantois, an extraembryonic sac described in chapter 4 (p. 94). This connection eventually becomes a constricted passage, the *urachus* (yur-AY-kus), connecting the bladder to the umbilicus. In the adult, the urachus is reduced to a fibrous cord, the *median umbilical ligament.*

Urine production begins around week 12 of fetal development, but metabolic wastes are cleared by the placenta, not by the fetal urinary system. Fetal urine is continually recycled as the fetus voids it into the amniotic fluid, swallows it, and then excretes it again.

DEEPER INSIGHT 25.5

Developmental Abnormalities of the Urinary System

Several anomalies can occur during the embryonic development of the kidneys (see fig. 1.5, p. 7). *Pelvic kidney* is a condition in which the kidney fails to ascend and remains in the pelvic cavity for life. *Horseshoe kidney* is a single C-shaped kidney that arches across the lumbar region from left to right; it is formed when the ascending kidneys are crowded together and merge into one. The C typically snags on the inferior mesenteric artery, preventing the horseshoe kidney from ascending any farther. Some people have two ureters arising from a single kidney, resulting from a splitting of the ureteric bud in early embryonic development. Usually the two ureters empty into the bladder, but in rare cases, one of them empties into the uterus, vagina, urethra, or elsewhere. This requires surgical correction so that urine does not dribble continually from the urethra or vagina. In some cases, the urachus fails to close; Testing Your Comprehension question 3 (p. 702) addresses the consequences of this. Some kidneys have an *accessory renal artery* resulting from failure of one of the early, temporary renal arteries to degenerate as the permanent renal artery forms. Most such irregularities cause no functional problems and usually go unnoticed, but they may be discovered in surgery, radiography, or cadaver dissection.

The Aging Urinary System

The kidneys exhibit a striking degree of atrophy in old age. From ages 25 to 85, the number of nephrons declines by 30% to 40%, and up to one-third of the remaining glomeruli become atherosclerotic, bloodless, and nonfunctional. The kidneys of a 90-year-old are 20% to 40% smaller than those of a 30-year-old and receive only half as much blood. They are proportionately less efficient at clearing wastes from the blood. Although baseline renal function is adequate even in old age, the kidneys have little reserve capacity; thus, other diseases can lead to surprisingly rapid renal failure. Drug doses often need to be reduced for the elderly because the kidneys cannot clear drugs from the blood as rapidly. Reduced renal function is a significant factor in overmedication of the aged.

Water balance becomes more precarious in old age because the kidneys are less responsive to antidiuretic hormone and because the sense of thirst is blunted. Even with free access to water, many elderly people do not drink enough to maintain normal blood osmolarity, and dehydration is common.

Voiding and bladder control become a problem for both men and women. About 80% of men over the age of 80 are affected by *benign prostatic hyperplasia,* a noncancerous growth of the prostate gland that compresses the urethra, reduces the force of the urine stream, and makes it harder to empty the bladder. Urine retention can cause pressure to back up in the kidneys, aggravating the failure of the nephrons. Older women become increasingly subject to *urinary incontinence* (see table 25.1), especially if their history of pregnancy and childbearing has weakened the pelvic muscles and urethral sphincters. Senescence of the sympathetic nervous system

---

[25] *pro* = first; *nephros* = kidney
[26] *meso* = middle; *nephros* = kidney
[27] *meta* = beyond, next in a series; *nephros* = kidney


Degenerating pronephros
Mesonephros
Ureteric bud
Mesonephric duct
Metanephros
(a)
Outgrowing collecting ducts
Collecting ducts
Metanephros
Pelvis
Ureter
Minor calyx
Major calyx
(b)

Figure 25.12 **Embryonic Development of the Urinary Tract.** (a) Relationship of the early ureteric bud and metanephros to the lower mesonephric duct. (b) Progression in the development of the ureter, renal pelvis, calyces, and collecting ducts, all of which arise from the ureteric bud.


Renal tissue cap
Early nephron
Collecting duct
(a)
Collecting duct
Distal convoluted tubule
Glomerular capsule
Proximal convoluted tubule
(b)
Nephron loop

Figure 25.13 **Embryonic Development of the Nephron.** (a) The collecting duct induces mesoderm to differentiate into a renal (metanephric) tissue cap, as shown at the far left. This cap differentiates into an S-shaped tube that will become the nephron, as shown on the right fork of the duct (representing a later stage of development). (b) The renal tubule has begun to differentiate into proximal and distal convoluted tubules and nephron loop.

TABLE 25.1 Some Disorders of the Urinary System

Acute glomerulonephritis	An autoimmune inflammation of the glomeruli, often following a *Streptococcus* infection. Results in destruction of glomeruli leading to hematuria, proteinuria, edema, reduced glomerular filtration, and hypertension. Can progress to chronic glomerulonephritis and renal failure, but most individuals recover from acute glomerulonephritis without lasting effect.
Hydronephrosis[28]	Increase in fluid pressure in the renal pelvis and calyces owing to obstruction of the ureter by kidney stones, nephroptosis (below), or other causes. Can progress to complete cessation of glomerular filtration and atrophy of nephrons.
Nephroptosis[29] (NEFF-rop-TOE-sis)	Slippage of the kidney to an abnormally low position *(floating kidney)*. Occurs in people with too little body fat to hold the kidney in place, and in people who subject the kidneys to prolonged vibration, such as truck drivers, equestrians, and motorcyclists. Can twist or kink the ureter, which causes pain, obstructs urine flow, and potentially leads to hydronephrosis.
Nephrotic syndrome	Excretion of large amounts of protein in the urine (≥ 3.5 g/day) due to glomerular injury. Can result from trauma, drugs, infections, cancer, diabetes mellitus, lupus erythematosus, and other diseases. Loss of plasma protein leads to edema, ascites (pooling of fluid in the abdominal cavity), hypotension, and susceptibility to infection (because of immunoglobulin loss).
Urinary incontinence	Inability to hold the urine; involuntary leakage from the bladder. Can result from incompetence of the urinary sphincters; bladder irritation; pressure on the bladder in pregnancy; an obstructed urinary outlet so that the bladder is constantly full and dribbles urine *(overflow incontinence)*; uncontrollable urination due to brief surges in bladder pressure, as in laughing or coughing *(stress incontinence)*; and neurological disorders such as spinal cord injuries.

Disorders Described Elsewhere

Azotemia	686
Cystitis	696
Hematuria	692
Kidney stones	696
Proteinuria	692
Pyelitis	696
Pyelonephritis	696
Uremia	686

and nervous disorders such as stroke and Alzheimer disease can also cause incontinence.

Urinary System Disorders

The most serious disorder of the urinary system is renal failure. *Acute renal failure* is an abrupt decline in kidney function, often caused by trauma or by a hemorrhage or thrombosis cutting off blood flow to the nephrons. *Chronic renal failure* is a long-term, progressive, irreversible loss of functional nephrons. It can result from such causes as prolonged or repetitive kidney infections, trauma, poisoning, atherosclerosis of the renal arteries (often in conjunction with diabetes mellitus), or an autoimmune disease called acute glomerulonephritis (see table 25.1).

Nephrons can regenerate and restore kidney function after short-term injuries, and even when some nephrons are irreversibly destroyed, others can hypertrophy and compensate for their lost function. Indeed, a person can survive on as little as one-third of one kidney. When 75% of the nephrons are lost, however, the remaining ones cannot maintain homeostasis. The result is azotemia and acidosis, and if 90% of renal function is lost, uremia is likely. Loss of nephron function also leads to anemia, because erythrocyte production depends on the hormone erythropoietin, which is secreted mainly by the kidneys.

Renal insufficiency or failure must be treated either with a kidney transplant or with *hemodialysis*. The latter is a procedure in which, usually, arterial blood is pumped through a *dialysis machine*. In the machine, the blood passes through tubes of dialysis membrane immersed in dialysis fluid. Wastes and excess water diffuse from the blood into the fluid, which is discarded, and drugs can be added to the dialysis fluid to diffuse into the blood. Another method called *continuous ambulatory peritoneal dialysis (CAPD)* frees the patient from the dialysis machine and can be carried out at home. Dialysis fluid is introduced into the peritoneal cavity through a catheter, absorbs metabolic wastes, and then is drained from the body and discarded.

Some other urinary system disorders are briefly described in table 25.1.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

12. Explain why the nephron has a different embryonic origin from the passages that extend from collecting duct to urethra.
13. How does the number of functional nephrons change in old age? What are the implications of this change for homeostasis and medication dosages?
14. What are some causes of renal failure? Describe some clinical signs of renal failure.
15. Cover the right side of table 25.1 and define or describe the disorders on the left from memory.

---

[28] *hydro* = water; *nephr* = kidney; *osis* = medical condition

[29] *nephro* = kidney; *ptosis* = sagging, falling

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

25.1 Functions of the Urinary System (p. 685)

1. The six organs of the urinary system
2. The functions of the kidneys
3. The meaning of *excretion*
4. Nitrogenous wastes, azotemia, and uremia

25.2 The Kidney (p. 686)

1. The location of the kidneys and their relationship to adjacent organs and the peritoneum
2. The shape of the kidney and the location and purpose of the hilum
3. The three layers of connective tissue that surround and enclose the kidney
4. The relationships between the renal cortex, medulla, pyramids, and sinus
5. The relationships between a renal pyramid, minor calyx, major calyx, renal pelvis, and ureter
6. All branches of the renal artery leading to the glomerulus, peritubular capillaries, and vasa recta; and all tributaries leading from these vessels to the renal vein
7. The routes of sympathetic, parasympathetic, and sensory innervation of the kidney, and effects of the sympathetic nerves on renal function
8. The four basic steps of urine formation
9. The meaning of *nephron* and the anatomical components of this structure
10. The structural details of a renal corpuscle, especially the relationship of the podocytes to the glomerular capillaries
11. Components of the filtration membrane in the glomerulus, and the relevance of this membrane to the composition of urine
12. The path of fluid movement in glomerular filtration and flow into the renal tubule
13. Components of the renal tubule, in the order of fluid flow; which components belong to a single nephron and which ones are shared by multiple nephrons
14. Structural differences between the proximal convoluted tubule, nephron loop, distal convoluted tubule, and collecting duct; and the relevance of these structural differences to their functions
15. The contributions of each part of the renal tubule to the final composition of the urine
16. The location, components, function, and action of the juxtaglomerular apparatus

25.3 The Ureters, Urinary Bladder, and Urethra (p. 695)

1. The anatomy, function, and action of the ureters
2. The anatomy of the urinary bladder and how its structure relates to its functions
3. The anatomy of both the female and male urethra, locations of the internal and external urethral sphincters, and functional difference between the two sphincters

25.4 Developmental and Clinical Perspectives (p. 697)

1. The developmental sequence from pronephros to mesonephros to metanephros
2. The origin of the ureteric bud and the structures that arise from it
3. The pattern of development of the nephrons from mesonephric tissue
4. The cloaca, its differentiation into anal canal and urogenital sinus, and the further differentiation of the urogenital sinus into the organs of the lower urinary tract
5. Changes in the kidneys in old age, and the impact of this on one's health
6. Issues of urinary incontinence or urine retention experienced by elderly men and women, and reasons for this difference between the sexes
7. Causes, effects, and treatment of renal failure

Testing Your Recall

1. Which of these is *not* a function of the kidneys?
   a. to secrete hormones
   b. to excrete nitrogenous wastes
   c. to store urine
   d. to control blood volume
   e. to control acid–base balance
2. The compact ball of capillaries in a nephron is called
   a. the nephron loop.
   b. the peritubular plexus.
   c. the renal corpuscle.
   d. the glomerulus.
   e. the vasa recta.
3. Which of these is *not* true of the position of the kidneys in the body?
   a. They are medial to the aorta.
   b. They are retroperitoneal.
   c. The right kidney is lower than the left.
   d. They are inferior to the liver and spleen.
   e. They lie partially within the rib cage.
4. Which of these lies closest to the renal cortex?
   a. the parietal peritoneum
   b. the renal fascia
   c. the fibrous capsule
   d. the perirenal fat capsule
   e. the renal pelvis
5. The water that is reabsorbed by the collecting duct enters
   a. the nephron loop.
   b. the minor calyx.
   c. the ureter.
   d. the efferent arteriole.
   e. the vasa recta.
6. A glomerulus and glomerular capsule make up one
   a. renal capsule.
   b. renal corpuscle.
   c. kidney lobule.
   d. kidney lobe.
   e. nephron.
7. The kidney has more _____ than any of the other structures listed.
   a. arcuate arteries
   b. minor calyces
   c. medullary pyramids
   d. afferent arterioles
   e. collecting ducts
8. The _____ arises from the embryonic ureteric bud.
   a. nephron
   b. renal pelvis
   c. glomerulus
   d. urinary bladder
   e. proximal convoluted tubule
9. The _____ absorbs variable amounts of water depending on the level of antidiuretic hormone present.
   a. proximal convoluted tubule
   b. nephron loop
   c. distal convoluted tubule
   d. collecting duct
   e. urinary bladder

10. In cortical nephrons, blood of the efferent arteriole flows next into
    a. the peritubular capillaries.
    b. the arcuate artery.
    c. the arcuate vein.
    d. the vasa recta.
    e. the glomerulus.
11. The most abundant nitrogenous waste in the urine is _____.
12. The ureter, renal pelvis, calyces, and collecting duct arise from an embryonic pouch called the _____.
13. The openings of the two ureters and the urethra form the boundaries of a smooth area called the _____ on the floor of the urinary bladder.
14. The _____ is a group of epithelial cells at the distal end of the nephron loop that monitors the flow or composition of the tubular fluid.
15. To enter the capsular space, filtrate must pass between foot processes of the _____, which are cells that form the visceral layer of the glomerular capsule.
16. What part of the nephron is characterized by a brush border and especially great length?
17. Epithelial cells in the _____ of the nephron loop have few mitochondria and low metabolic activity, but they are very permeable to water.
18. The smooth muscle of the bladder wall is called the _____.
19. Each renal pyramid drains into a separate cuplike urine receptacle called a _____.
20. Blood flows through the _____ arteries just before entering the cortical radiate arteries.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. azot-
2. nephro-
3. glomerul-
4. litho-
5. podo-
6. -uria
7. macula
8. juxta-
9. pelv-
10. cysto-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. The ureters open through pores in the roof of the urinary bladder.
2. The kidneys secrete antidiuretic hormone to promote water retention and prevent dehydration.
3. The kidney has more distal convoluted tubules than collecting ducts.
4. Tight junctions prevent material from leaking between the epithelial cells of the renal tubule.
5. Many collecting ducts empty into each minor calyx.
6. The glomerulus is a complex of blood capillaries located in the capsular space of the glomerular capsule.
7. Each cortical radiate artery serves multiple nephrons.
8. Blood-borne solutes can become incorporated into the urine by either glomerular filtration or tubular secretion.
9. The kidneys are located in the pelvic cavity.
10. The kidneys develop in the pelvic region and ascend to a higher location in the abdominal cavity during fetal development.

Answers in appendix A

Testing Your Comprehension

1. What function could the collecting duct *not* perform if there were no nephron loops? Why?
2. Why would a simple squamous epithelium function poorly as an inner lining of the urinary bladder?
3. In some infants, the urachus fails to close; it remains as an open passage *(urachal fistula)* from the urinary bladder to the umbilicus. What would you expect to be the most obvious sign of a urachal fistula?
4. Suppose the ureters entered the bladder from above instead of from below. Which disorder in table 25.1 would you expect to result from this? Explain why.
5. In what ways do the proximal and distal convoluted tubules differ in structure? How is this related to their functional difference?



MRI scan of a fetus in the uterus at the 36th week of pregnancy

© Simon Fraser/Science Source

PART FIVE

CHAPTER 26

THE REPRODUCTIVE SYSTEM

CHAPTER OUTLINE

26.1 Sexual Reproduction 704
- The Two Sexes 704
- Overview of the Reproductive System 704

26.2 The Male Reproductive System 705
- The Scrotum 705
- The Testes 705
- Spermatogenesis and Sperm 709
- The Spermatic Ducts 712
- The Accessory Glands 713
- The Penis 713

26.3 The Female Reproductive System 715
- The Ovaries 716
- Oogenesis and Folliculogenesis 717
- The Uterine Tubes 721
- The Uterus 721
- The Vagina 724
- The External Genitalia 724
- The Breasts and Mammary Glands 725

26.4 Developmental and Clinical Perspectives 727
- Prenatal Development and Sexual Differentiation 727
- Puberty 731
- The Aging Reproductive System 731
- Reproductive Disorders of the Male 731
- Reproductive Disorders of the Female 732

Study Guide 735

DEEPER INSIGHTS

26.1 Prostate Diseases 713
26.2 Reproductive Effects of Pollution 715
26.3 Cervical Cancer and Pap Smears 733

BRUSHING UP

To understand this chapter, you may find it helpful to review the following concepts:

- Mitosis (p. 47)
- Chromosome structure (p. 48)
- Muscles of the pelvic floor (p. 287)
- Hypothalamic releasing factors and pituitary gonadotropins (p. 502)
- Androgens (p. 508)

Anatomy & Physiology | REVEALED®
aprevealed.com

Module 14: Reproductive System

From all we have learned of the structure and function of the human body, it seems a wonder that it works at all! The fact is, however, that even with modern medicine we can't keep it working forever. The body inevitably suffers degenerative changes as we age, and eventually we expire. Yet our genes live on in new containers—our offspring. This final chapter concerns the means of their production—the male and female reproductive systems.

26.1 Sexual Reproduction

Expected Learning Outcomes

When you have completed this section, you should be able to

a. define *sexual reproduction;*
b. identify the most fundamental biological distinction between male and female; and
c. define *primary sex organs, secondary sex organs,* and *secondary sex characteristics.*

The Two Sexes

The essence of sexual reproduction is that it is biparental—the offspring receive genes from two parents and therefore are not genetically identical to either one. To achieve this, the parents must produce **gametes**[1] (sex cells) that meet and combine their genes in a **zygote**[2] (fertilized egg). The gametes must have two properties for reproduction to be successful: motility so they can achieve contact, and nutrients for the developing embryo. A single cell cannot perform both of these roles optimally, because to contain ample nutrients means to be relatively large and heavy, and this is inconsistent with the need for motility. Therefore, these tasks are usually apportioned to two kinds of gametes. The small motile one—little more than DNA with a propeller—is the **sperm (spermatozoon),** and the large nutrient-laden one is the **egg (ovum).**

In any sexually reproducing species, by definition, an individual that produces eggs is female and one that produces sperm is male. This criterion is not always that simple, as we see in certain abnormalities in sexual development. Genetically, however, any human with a Y sex chromosome is classified as male and anyone lacking a Y is classified as female. Normally, a male inherits an X from the mother and Y from the father, and his sex chromosomes are thus designated XY. A female inherits an X from each parent, and therefore has an XX chromosome pair.

In mammals, the female is also the parent that provides a sheltered internal environment for the development and prenatal nutrition of the embryo. For fertilization and development to occur in the female, the male must have a copulatory organ, the penis, for introducing his gametes into the female reproductive tract and the female must have a copulatory organ, the vagina, for receiving the sperm.

Overview of the Reproductive System

The **reproductive system** in the male serves to produce sperm and introduce them into the female body. The female reproductive system produces eggs, receives the sperm, provides for the union of these gametes, harbors the fetus, gives birth, and nourishes the offspring.

In both sexes, the reproductive system consists of primary and secondary sex organs, or **genitalia.** The **primary sex organs,** or **gonads,**[3] are the organs that produce gametes—testes of the male and ovaries of the female. The **secondary sex organs** are organs other than gonads that are necessary for reproduction. In the male, they constitute a system of ducts, glands, and the penis, concerned with the storage, survival, and conveyance of sperm. In the female, they include the uterine tubes, uterus, and vagina, concerned with uniting the sperm and egg and harboring the fetus.

According to location, the reproductive organs are classified as **external** and **internal genitalia** (table 26.1). The external genitalia are located in the perineum—the diamond-shaped region marked by the pubic symphysis anteriorly, the coccyx posteriorly, and the ischial tuberosities laterally (see fig. 11.16, p. 288). Most of them are externally visible, except for the accessory glands of the female perineum (see fig. 26.20). The internal genitalia are located mainly in the pelvic cavity, except for the male testes and some associated ducts contained in the scrotum.

Secondary sex characteristics are features that develop in adolescence, further distinguish the sexes, and play a role in mate attraction. From the call of a bullfrog to the tail of a peacock, these are well known in the animal kingdom. In humans, the identification of secondary sex characteristics rests on somewhat subjective and culturally variable judgments of what is sexually attractive. Commonly considered among the secondary sex characteristics

TABLE 26.1 The External and Internal Genitalia

External Genitalia	Internal Genitalia
Male	
Penis Scrotum	Testes (s., *testis*) Epididymides (s., *epididymis*) Ductus deferentes (s., *ductus deferens*) Seminal vesicles Prostate Bulbourethral glands
Female	
Mons pubis Labia majora (s., *labium majus*) Labia minora (s., *labium minus*) Clitoris Vaginal orifice Vestibular bulbs Vestibular glands Paraurethral glands	Ovaries Uterine tube Uterus Vagina

---

[1] *gam* = marriage, union
[2] *zygo* = yoke, union
[3] *gon* = seed

are the pubic and axillary hair; male facial hair; apocrine scent glands associated with these patches of hair; differences in the texture and visibility of the hair on the limbs and trunk; the female breasts; differences in muscularity and the quantity and distribution of body fat; and differences in the pitch of the voice.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

1. Define *gonad* and *gamete*. Explain the relationship between the terms.
2. Define *male, female, sperm,* and *egg*.

26.2 The Male Reproductive System APIR

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the anatomy of the scrotum, testes, spermatic ducts, accessory glands, and penis;
b. describe the stages in spermatogenesis, the production of sperm; and
c. describe the structure of a sperm cell and the composition of semen.

Figure 26.1 shows the major organs of the male reproductive system. We will trace this system in the direction that sperm travel, therefore beginning with the testes and associated structures and ending with the penis.

The Scrotum

The testes are contained in the **scrotum,**[4] a pouch of skin, muscle, and fibrous connective tissue (figs. 26.2 and 26.3). The skin of the scrotum has sebaceous glands, sparse hair, rich sensory innervation, and somewhat darker pigmentation than skin elsewhere. The scrotum is divided into right and left compartments by an internal **median septum,** which protects each testis from infections of the other one. The location of the septum is externally marked by a seam called the **perineal raphe**[5] (RAY-fee), which also extends anteriorly along the ventral side of the penis and posteriorly as far as the margin of the anus (fig. 26.1). The left testis is usually suspended lower than the right so the two are not compressed against each other between the thighs.

The scrotum contains not only the testes but also the **spermatic cord**—a bundle of blood and lymphatic vessels, *testicular nerves*, fibrous connective tissue, and a sperm duct called the *ductus deferens*. The cord passes upward behind and superior to the testis, where it is easily palpated through the skin of the scrotum. It continues across the anterior side of the pubis and into a 4-cm-long **inguinal canal,** which leads through the muscles of the groin and emerges into the pelvic cavity. The inferior entrance into the inguinal canal is called the *external inguinal ring,* and its superior exit into the pelvic cavity is the *internal inguinal ring*.

In some mammals, the testes are in the abdominopelvic cavity and there is no scrotum. It is therefore unclear, and a subject of debate among reproductive biologists, why humans and most other mammals have the testes in a scrotum. Whatever the reason may be, however, they have adapted to this cooler environment and cannot produce sperm at the core body temperature of 37°C; they must be held at about 35°C. The scrotum has three mechanisms for regulating the temperature of the testes:

1. The **cremaster**[6] **muscle**—strips of the internal abdominal oblique muscle that enmesh the spermatic cord. When it is cold, the cremaster contracts and draws the testes closer to the body to keep them warm. When it is warm, the cremaster relaxes and the testes are suspended farther from the body.
2. The **dartos**[7] **muscle**—a subcutaneous layer of smooth muscle. It, too, contracts when cold, making the scrotum taut and wrinkled. This reaction holds the testes snugly against the warm body and reduces the surface area of the scrotum, thus reducing heat loss.
3. The **pampiniform**[8] **plexus**—an extensive network of veins from the testis that surround the testicular artery in the spermatic cord. The plexus prevents warm arterial blood from overheating the testis, which would inhibit sperm production. It acts as a *countercurrent heat exchanger.* Blood ascending through the plexus is relatively cool (about 35°C) and absorbs heat from the warmer (37°C) blood descending through the testicular artery. By the time arterial blood reaches the testis, it is 1.5° to 2.5°C cooler than it was when it left the pelvic cavity.

The Testes

The **testes (testicles)** are the male gonads—combined endocrine and exocrine glands that produce sex hormones and sperm. Each testis is oval and slightly flattened, about 4 cm long, 3 cm from anterior to posterior, and 2.5 cm from left to right (see fig. 26.4). Its anterior and lateral surfaces are covered by the **tunica vaginalis,**[9] a saccular extension of the peritoneum. The testis itself has a white fibrous capsule called the **tunica albuginea**[10] (TOO-nih-ca AL-byu-JIN-ee-uh). Connective tissue septa extend from the capsule into the parenchyma of the testis, dividing it into 200 to 300 wedge-shaped lobules. Each lobule contains one to three **seminiferous**[11] (SEM-ih-NIF-er-us) **tubules**—slender ducts up to 70 cm long

---

[4] *scrotum* = bag
[5] *raphe* = seam
[6] *cremaster* = suspender
[7] *dartos* = skinned
[8] *pampin* = tendril; *form* = shape
[9] *tunica* = coat; *vagina* = sheath
[10] *alb* = white
[11] *semin* = seed, sperm; *fer* = to carry



Urinary bladder
Pubic symphysis
Root of penis
Ductus (vas) deferens
Shaft of penis
Corpus cavernosum
Corpus spongiosum
Epididymis
Glans of penis
Prepuce
Testis
Scrotum
Rectum
Ampulla of ductus deferens
Seminal vesicle
Ejaculatory duct
Prostate gland
Bulbourethral gland
Bulbospongiosus muscle
Urethra
Urinary bladder
Prostate gland
Prostatic urethra
Membranous urethra
Ductus deferens
Efferent ductules
Epididymis
Spongy (penile) urethra
Glans of penis
Penis
Ureter
Ampulla
Seminal vesicle
Ejaculatory duct
Bulbourethral gland
Bulb
Crus
Corpus spongiosum
Corpus cavernosum
Testis

(a) Sagittal section

(b) Posterior view

Figure 26.1 **The Male Reproductive System.** See figure A.14a (p. 342) for a corresponding cadaver dissection photo. APR


Location of pubic symphysis
Perineal raphe
Urogenital triangle
Anal triangle
Location of coccyx
Anus
Location of ischial tuberosity

Figure 26.2 **The Male Perineum.** See figure 11.16 (p. 288) for details of the muscles of this region.

in which the sperm are produced. Between the seminiferous tubules are clusters of **interstitial (Leydig[12]) cells,** the source of testosterone.

A seminiferous tubule has a narrow lumen lined by a thick **germinal epithelium** (fig. 26.4). The epithelium consists of several layers of **germ cells** in the process of becoming sperm, and a much smaller number of tall **sustentacular**[13] (**Sertoli**[14] or nurse) **cells,** which protect the germ cells and promote their development. The germ cells depend on the sustentacular cells for nutrients, waste removal, growth factors, and other needs. The sustentacular cells also secrete a hormone, *inhibin,* which regulates the rate of sperm production; and *androgen-binding protein,* which makes the testis responsive to testosterone.

A sustentacular cell is shaped a little like a tree trunk whose roots spread out over the basement membrane, forming the boundary of the tubule, and whose thick trunk reaches to the tubule lumen. Tight junctions between adjacent sustentacular cells form a **blood–testis barrier (BTB),** which prevents antibodies and other large molecules in the blood and intercellular fluid from getting to the germ cells. This is important because

---

[12] Franz von Leydig (1821–1908), German anatomist
[13] *sustentacul* = support
[14] Enrico Sertoli (1842–1910), Italian histologist


External inguinal ring
Spermatic cord:
Cremaster muscle
Testicular artery
Ductus deferens
Pampiniform plexus
Epididymis
Tunica vaginalis
Testis
Fascia of spermatic cord
Superficial fascia of penis
Deep fascia of penis
Prepuce (foreskin)
Glans
Median septum of scrotum
Cremaster muscle
Dartos muscle
Scrotal skin

Figure 26.3 **The Scrotum and Spermatic Cord.**


Spermatic cord
Ductus deferens
Head of epididymis
Testis, covered by tunica albuginea
Tail of epididymis
Scrotum (folded down)
(a)
2 cm
Spermatic cord
Blood vessels and nerves
Head of epididymis
Ductus deferens
Efferent ductule
Rete testis
Body of epididymis
Seminiferous tubule
Septum
Lobule
Tunica vaginalis
Tunica albuginea
Tail of epididymis
(b)
Seminiferous tubule
Interstitial cells
Germ cells
Sperm tails
Sustentacular cells
(c)
Blood vessel
Seminiferous tubule
Spermatids
Sustentacular cell nuclei
Tubule lumen
Germ cells
Connective tissue wall of tubule
Interstitial cells
(d)
50 µm

© McGraw-Hill Education/Dennis Strete, photographer

© Steve Gschmeissner/Science Source

© Ed Reschke/Getty Images

Figure 26.4 **The Testis and Associated Structures.** (a) The scrotum is opened and folded downward to reveal the testis and associated organs. (b) Anatomy of the testis, epididymis, and spermatic cord. (c) Scanning electron micrograph of the seminiferous tubules. (d) Light micrograph. This region of the tubule did not have mature sperm at the time. AP|R

the germ cells, being genetically different from other cells of the body, would otherwise be attacked by the immune system. Some cases of sterility occur when the BTB fails to form adequately and the immune system produces antibodies against the germ cells.

Apply What You Know

Would you expect to find blood capillaries in the walls of the seminiferous tubules? Why or why not?

The seminiferous tubules lead into a network called the **rete**[15] (REE-tee) **testis,** embedded in the capsule on the posterior side. Sperm partially mature in the rete. They are moved along by the flow of fluid secreted by the sustentacular cells and by the cilia on some rete cells. Sperm do not swim while they are in the male reproductive tract, but remain immobile until ejaculated.

Each testis is supplied by a **testicular artery,** which arises from the abdominal aorta just below the renal artery. This is a very long, slender artery that winds its way down the posterior abdominal wall before passing through the inguinal canal into the scrotum. Its blood pressure is very low, and this is one of the few arteries to have no pulse. Consequently, blood flow to the testes is quite meager and they receive a poor oxygen supply. The sperm appear to compensate by developing unusually large mitochondria, which may precondition them for survival in the hypoxic environment of the female reproductive tract.

Blood leaves the testis by way of the pampiniform plexus of veins. As these veins pass through the inguinal canal, they converge and form the **testicular vein.** The right testicular vein drains into the inferior vena cava and the left one drains into the left renal vein. Lymphatic vessels also drain each testis. They travel through the inguinal canal with the veins and lead to lymph nodes adjacent to the lower aorta. Lymph from the penis and scrotum, however, travels to lymph nodes adjacent to the iliac arteries and veins and in the inguinal region.

Testicular nerves lead to the gonads from spinal cord segments T10 and T11. They are mixed sensory and motor nerves containing predominantly sympathetic but also some parasympathetic fibers. The sensory fibers are concerned primarily with pain and the autonomic fibers are predominantly vasomotor, for regulation of blood flow.

Spermatogenesis and Sperm

Spermatogenesis is the process of sperm production. It occurs in the seminiferous tubules and involves three principal events: (1) division and remodeling of a relatively large germ cell into four small, mobile cells with flagella; (2) reduction of the chromosome number by one-half, so that when the sperm and egg combine, we do not get a doubling of chromosome number in every generation; and (3) a shuffling of the genes so that each chromosome of the sperm carries new gene combinations that did not exist in the chromosomes received from the parents. This ensures genetic variety in the offspring. The genetic recombination and reduction in chromosome number are achieved through a form of cell division called **meiosis**, which produces four daughter cells that subsequently differentiate into sperm (fig. 26.5).

Early in prenatal development, **primordial germ cells** form in the yolk sac, migrate by ameboid motion into the embryo itself, and colonize the *gonadal ridges* (see p. 727). Here they become stem cells called **spermatogonia.** These cells remain dormant through childhood, lying along the periphery of the seminiferous tubules near the basement membrane, outside the blood–testis barrier (BTB). These cells are **diploid**[16]—they have 46 chromosomes (23 pairs) and are genetically identical to most other cells of the body, so they require no protection from the immune system.

At puberty, testosterone secretion rises, reactivates the spermatogonia, and brings on spermatogenesis. The essential steps of spermatogenesis are as follows; see the same-numbered steps in figure 26.6.

1. Spermatogonia divide by mitosis. One daughter cell from each division remains near the tubule wall as a stem cell called the *type A spermatogonium.* Type A spermatogonia serve as a lifetime supply of stem cells, so men normally remain fertile throughout old age. The other daughter cell, called the *type B spermatogonium,* migrates slightly away from the wall on its way to becoming sperm.

2. The type B spermatogonium enlarges and becomes a **primary spermatocyte.** Since this cell is about to undergo meiosis and become genetically different from other cells of the body, it must be protected from the immune system. Ahead of the primary spermatocyte, the tight junction between two sustentacular cells is dismantled, while a new tight junction forms behind the spermatocyte. The spermatocyte moves forward toward the lumen, like passing through the double-doored airlock of a spaceship, and is now protected by the BTB.

3. The primary spermatocyte undergoes *meiosis I,* a cell division that reduces the chromosome number by half. The daughter cells, called **secondary spermatocytes,** are therefore **haploid**[17]—they have 23 unpaired chromosomes, although each chromosome consists of two identical-looking strands called chromatids (see fig. 2.22, p. 50).

4. The secondary spermatocytes undergo another division, *meiosis II,* during which each chromosome splits into separate chromatids. The result is four daughter cells (two from each spermatocyte) called **spermatids,** each with 23 single-stranded chromosomes.

5. A spermatid divides no further, but undergoes a process called **spermiogenesis,** in which it differentiates into a

---

[15] *rete* = network

[16] *diplo* = double

[17] *haplo* = half



Meiosis I (first division)

Meiosis II (second division)

Early prophase I
Chromatin condenses to form visible chromosomes; each chromosome has 2 chromatids joined by a centromere.

Mid- to late prophase I
Homologous chromosomes form pairs called tetrads. Chromatids often break and exchange segments (crossing-over). Centrioles produce spindle fibers. Nuclear envelope disintegrates.

Metaphase I
Tetrads align on equatorial plane of cell with centromeres attached to spindle fibers.

Anaphase I
Homologous chromosomes separate and migrate to opposite poles of the cell.

Telophase I
New nuclear envelopes form around chromosomes; cell undergoes cytoplasmic division (cytokinesis). Each cell is now haploid.

Prophase II
Nuclear envelopes disintegrate again; chromosomes still consist of 2 chromatids. New spindle forms.

Metaphase II
Chromosomes align on equatorial plane.

Anaphase II
Centromeres divide; sister chromatids migrate to opposite poles of cell. Each chromatid now constitutes a single-stranded chromosome.

Telophase II
New nuclear envelopes form around chromosomes; chromosomes uncoil and become less visible; cytoplasm divides.

Final product is 4 haploid cells with single-stranded chromosomes.

Figure 26.5 **Meiosis.** For simplicity, the cell is shown with only two pairs of homologous chromosomes. Human cells begin meiosis with 23 pairs.


Cross section of seminiferous tubules
Lumen of seminiferous tubule
Sperm
5
Spermiogenesis
Spermatid
n
n
n
n
4
Meiosis II
Secondary spermatocyte
n
n
3
Meiosis I
Blood–testis barrier
Primary spermatocyte
2n
Sustentacular cell
2
Type B spermatogonium
2n
Tight junction
Type A spermatogonium
2n
1
Basement membrane of seminiferous tubule

Figure 26.6 **Spermatogenesis.** 2*n* indicates diploid cells, and *n* indicates haploid cells. The process proceeds from the bottom of the figure to the top. The daughter cells from secondary spermatocytes through spermatids remain connected by slender cytoplasmic bridges until spermiogenesis is complete and individual spermatozoa are released. See text for explanation of steps 1 through 5.

- *Why must the primary spermatocyte move through the blood–testis barrier before undergoing meiosis?*

single spermatozoon (sperm). The fundamental changes in spermiogenesis are a loss of excess cytoplasm and the growth of a tail (flagellum), making the sperm a lightweight, mobile cell (fig. 26.7).

All stages from primary spermatocyte to spermatozoon are enfolded in tendrils of the sustentacular cells and bound to them by tight junctions and gap junctions. In addition, the daughter cells do not completely separate from each other in meiosis I and II, but remain joined to each other by narrow cytoplasmic bridges. They do not completely separate until the very end of spermiogenesis.

At the conclusion of spermiogenesis, the spermatozoa are released and washed down the tubule by fluid from the sustentacular cells. It takes about 74 days for a spermatogonium to become mature sperm. A young adult male produces about 300,000 sperm per minute, or 400 million per day.

The Spermatozoon

The spermatozoon has two parts: a pear-shaped head and a long tail (fig. 26.8). The **head,** about 4 to 5 µm long and 3 µm wide at its broadest part, contains three structures: a nucleus, acrosome, and flagellar basal body. The most important of these is the nucleus, which fills most of the head and contains a haploid set of condensed, genetically inactive chromosomes. The **acrosome**[18] is a lysosome in the form of a thin cap covering the apical half of the nucleus. It contains enzymes that are later used to penetrate the egg if the sperm is successful. The basal body of the flagellum is nestled in an indentation at the posterior end of the nucleus.

The **tail** is divided into three regions called the midpiece, principal piece, and endpiece. The **midpiece,** a cylinder about 5 to 9 µm long and half as wide as the head, is the thickest part. It contains numerous large mitochondria that coil tightly around the axoneme of the flagellum. They produce the ATP needed for the beating of the tail when the sperm migrates up the female reproductive tract. The **principal piece,** 40 to 45 µm long, constitutes most of the tail and consists of the axoneme surrounded by a sheath of supportive fibers. The **endpiece,** 4 to 5 µm long, consists of the axoneme only and is the narrowest part of the sperm.

---

[18] *acro* = tip, peak; *some* = body


Golgi complex
Acrosomal vesicle
Nucleus
Basal body
Flagellum
① Appearance of acrosomal vesicle and flagellum in spermatid
Bridge to adjacent spermatid
② Growth of acrosome and flagellum
Excess cytoplasm
③ Shedding of excess cytoplasm
Acrosome
Head
Axoneme
Mitochondria
Midpiece of tail
④ Mature sperm

Figure 26.7 **Spermiogenesis.** In this process, the spermatids discard excess cytoplasm, grow tails, and become spermatozoa.


Acrosome
Nucleus
Basal body
Mitochondria
Axoneme
Principal piece of tail
2 µm
Head
Midpiece of tail
Principal piece of tail
Endpiece of tail
(a)
(b)

© BSIP SA/Alamy RF

Figure 26.8 **The Mature Spermatozoon.** (a) Head and part of the tail of a spermatozoon (TEM). (b) Sperm structure.

The Spermatic Ducts

After leaving the testis, the sperm travel through a series of *spermatic ducts* to reach the urethra. These include the following (see fig. 26.1):

- **Efferent ductules.** About 12 small efferent ductules arise from the posterior side of each testis and carry sperm to the epididymis (see fig. 26.4b). They have clusters of ciliated cells that help drive the sperm along.
- **Duct of the epididymis.** The **epididymis**[19] (EP-ih-DID-ih-miss; plural, *epididymides*) is a site of sperm maturation and storage. It adheres to the posterior side of the testis and consists of a clublike *head* at the superior end, a long middle *body,* and a slender *tail* at its inferior end. It contains a single coiled duct embedded in connective tissue. The duct is about 6 m (20 ft) long, but it is so slender and highly coiled that it is packed into an epididymis only 7.5 cm long. The duct reabsorbs about 90% of the fluid secreted by the testis. Sperm are physiologically immature (incapable of fertilizing an egg) when they leave the testis, but mature as they travel through the head and body of the epididymis. In 20 days or so, they reach the tail. They are stored here and in the adjacent portion of the ductus deferens. Stored sperm remain fertile for 40 to 60 days, but if they become too old without being ejaculated, they disintegrate and the epididymis reabsorbs them.
- **Ductus deferens.** The duct of the epididymis straightens out at the tail, turns 180°, and becomes the ductus deferens—also called the **vas deferens,** hence the term *vasectomy* for the surgical contraceptive procedure. This is a muscular tube about 45 cm long and 2.5 mm in diameter (see fig. 26.1). It passes upward through the spermatic cord and inguinal canal, and enters the pelvic cavity. There, it turns medially and approaches the urinary bladder. After passing between the bladder and ureter, the duct turns downward behind the bladder and widens into a terminal **ampulla.** The ductus deferens ends by uniting with the duct of the seminal vesicle, a gland considered later. It has a very narrow lumen and a thick wall of smooth muscle well innervated by sympathetic nerve fibers.
- **Ejaculatory duct.** Where the ductus deferens and duct of the seminal vesicle meet, they form a short (2 cm) ejaculatory duct, which passes through the prostate gland and empties into the urethra. The ejaculatory duct is the last of the spermatic ducts.

The male urethra is shared by the reproductive and urinary systems. It is about 20 cm long and consists of three regions: the *prostatic, membranous,* and *spongy (penile) urethra* (detailed on p. 696). Although it serves both urinary and reproductive roles, it cannot pass urine and semen simultaneously. During ejaculation, the internal urethral sphincter contracts to prevent the voiding of urine and keep semen out of the urinary bladder.

---

[19] *epi* = upon; *didym* = twins, testes

The Accessory Glands

There are three sets of *accessory glands* in the male reproductive system (see fig. 26.1):

- **Seminal vesicles.** These are a pair of glands posterior to the urinary bladder; one is associated with each ductus deferens. A seminal vesicle is about 5 cm long, or approximately the dimensions of one's little finger. It has a connective tissue capsule and underlying layer of smooth muscle. The secretory portion is a very convoluted duct with numerous branches that form a complex labyrinth. The duct empties into the ejaculatory duct.
- **Prostate**[20] (PROSS-tate) **gland.** This is a median structure that surrounds the urethra and ejaculatory ducts immediately inferior to the urinary bladder. It measures about 3 cm in diameter. It is actually a composite of 30 to 50 compound tubuloacinar glands enclosed in a single fibrous capsule. These glands empty into the urethra through about 20 pores in the urethral wall. The stroma of the prostate consists of connective tissue and smooth muscle, like that of the seminal vesicles. The prostate gland is the source of the two most common urogenital dysfunctions in older men (see Deeper Insight 26.1).
- **Bulbourethral (Cowper**[21]**) glands.** These are named for their position near a dilated bulb at the inner end of the penis and their association with the penile urethra. They are brownish, spherical glands about 1 cm in diameter, with a 2.5 cm duct to the urethra. During sexual arousal, they produce a clear slippery fluid that lubricates the head of the penis in preparation for intercourse. Perhaps more importantly, though, the fluid protects the sperm by neutralizing the acidity of residual urine in the urethra.

Semen

A typical ejaculation discharges 2 to 5 mL of **semen**[22] **(seminal fluid),** a complex mixture of sperm and glandular secretions. About 10% of it consists of sperm and fluids from the spermatic ducts; 30% is a thin, milky fluid from the prostate; and 60% is a viscous, yellowish fluid from the seminal vesicles. The bulbourethral glands contribute a trace of fluid. Normal semen contains about 50 to 120 million sperm per milliliter—the **sperm count.** A count lower than 20 to 25 million/mL is usually associated with *infertility (sterility),* the inability to fertilize an egg (see table 26.2).

Fresh semen is very sticky. This results from the action of a clotting enzyme in the prostatic fluid on a protein, *proseminogelin,* in the seminal vesicle fluid. The enzyme converts this to *seminogelin,* an adhesive protein very similar to the fibrin of a blood clot. The functional advantage of this seems to be that it ensures semen will adhere to the cervix and vagina rather than draining back out. Twenty to 30 minutes later, another prostatic enzyme, *serine protease,* breaks down seminogelin and liquifies the semen, liberating the sperm for their migration up the female reproductive tract. Sperm motility requires energy, which they get from fructose and other sugars provided by the seminal vesicles. The seminal vesicles also contribute lipids called *prostaglandins*—named for their discovery in the prostatic fluid of bulls, but later found to be even more abundant in the seminal vesicle fluid. Prostaglandins may contribute to the passage of sperm from the vagina into the uterus by thinning the mucus in the *cervical canal* (see p. 722) and perhaps inducing uterine peristaltic contractions that suck semen into the uterus.

DEEPER INSIGHT 26.1

Prostate Diseases

The prostate gland weighs about 20 g by age 20, remains at that weight until age 45 or so, and then begins to grow slowly again. By age 70, over 90% of men show some degree of *benign prostatic hyperplasia (BPH)*—noncancerous enlargement of the gland. The major complication of BPH is that it compresses the urethra, slows the flow of urine, and sometimes promotes bladder and kidney infections.

Prostate cancer is the second most common cancer in men (after lung cancer); it affects about 9% of men over the age of 50. Prostate tumors tend to form near the periphery of the gland, where they do not obstruct urine flow; therefore, they often go unnoticed until they cause pain. Prostate cancer often metastasizes to nearby lymph nodes and then to the lungs and other organs. It is more common among American blacks than whites and is rare among the Japanese.

The position of the prostate immediately anterior to the rectum allows it to be palpated through the rectal wall to check for tumors. This procedure is called *digital rectal examination (DRE).* Prostate cancer can also be diagnosed from elevated levels of *serine protease* (also known as *prostate specific antigen, PSA*) and *acid phosphatase* (another prostatic enzyme) in the blood. Up to 80% of men with prostate cancer survive when it is detected and treated early, but only 10% to 50% survive if it spreads beyond the prostatic capsule.

The Penis

The **penis**[23] serves to deposit semen in the vagina. Half of it is an internal **root** and half is the externally visible **shaft** and **glans**[24] (fig. 26.9). The glans is the expanded head at the distal end of the penis with the external urethral orifice at its tip. The external portion is about 8 to 10 cm (3–4 in.) long and 3 cm in diameter when flaccid (nonerect); the typical dimensions of an erect penis are 13 to 18 cm (5–7 in.) long and 4 cm in diameter.

The skin is loosely attached to the shaft, allowing for expansion during erection. It continues over the glans as the **prepuce,** or foreskin, which is often removed by circumcision. The glans and facing surface of the prepuce are covered with a mucous membrane and have sebaceous glands that produce a waxy secretion called **smegma.**[25] A ventral fold of tissue called the *frenulum* attaches the prepuce to the proximal margin of the glans. The mucous membrane of the glans is relatively thin and firmly attached to

---

[20] *pro* = before; *stat* = to stand; commonly misspelled and mispronounced "prostrate"
[21] William Cowper (1666–1709), British anatomist
[22] *semen* = seed
[23] *penis* = tail
[24] *glans* = acorn
[25] *smegma* = unguent, ointment, soap



Figure 26.9 **Anatomy of the Penis.** (a) Superficial dissection of shaft, lateral view. (b) Cross section at midshaft.
• *What is the functional benefit of the corpus spongiosum not having a tunica albuginea?* AP|R

the underlying erectile tissue. In circumcised males, it changes character to become a thin and less sensitive epidermis. This is an example of *metaplasia*—the transformation of one mature tissue type to another (see p. 79).

Directional terminology may be a little confusing in the penis, because the *dorsal* side is the one that faces anteriorly, at least when the penis is flaccid, whereas the *ventral* side of the penis faces posteriorly. This is because in most mammals, the penis is horizontal, held against the abdomen by skin, and points anteriorly. The urethra passes through its lower, more obviously ventral, half. Directional terminology in the human penis follows the same convention as for other mammals, even though our bipedal posture and more pendulous penis change these anatomical relationships.

The penis consists mainly of three cylindrical bodies called **erectile tissues,** which fill with blood during sexual arousal and account for its enlargement and erection. A single erectile body, the **corpus spongiosum,** passes along the ventral side of the penis and encloses the penile urethra. It expands at the distal end to fill the entire glans. Proximal to the glans, the dorsal side of the penis has a **corpus cavernosum** (plural, *corpora cavernosa*) on each side. Each is ensheathed in a tight fibrous sleeve called the **tunica albuginea,** and they are separated from each other by a **median septum.** (Note that the testes also have a tunica albuginea and the scrotum also has a median septum.)

All three cylinders of erectile tissue are spongy in appearance and contain numerous tiny blood sinuses called **lacunae.** The partitions between lacunae, called **trabeculae,** are composed of connective tissue and smooth **trabecular muscle.** In the flaccid penis, trabecular muscle tone collapses the lacunae, which appear as slits in the tissue.

At the body surface, the penis turns 90° posteriorly and continues inward as the root. The corpus spongiosum terminates at the internal end of the root as a dilated **bulb,** which is ensheathed in the bulbospongiosus muscle and anchored in the subcutaneous tissues of the urogenital triangle (see p. 707). The corpora cavernosa diverge like the arms of a Y. Each arm, called a **crus** (pronounced "cruss"; plural, *crura*), attaches the penis to the pubic arch of the pelvis and to the perineal membrane on its respective side. Each crus is enveloped by an ischiocavernosus muscle.

The penis receives blood from a pair of **internal pudendal (penile) arteries,** which branch from the internal iliac arteries. As each artery enters the root of the penis, it divides in two. One branch, the **dorsal artery,** travels dorsally along the penis not far beneath the skin, supplying blood to the skin, fascia, and corpus spongiosum. The other branch, the **deep artery,** travels through the core of the corpus cavernosum and gives off smaller **helicine**[26] **arteries,** which penetrate the trabeculae and empty into the lacunae. There are numerous anastomoses between the dorsal and deep arteries, so neither of them is the exclusive source of blood to any one erectile tissue.

---

[26] *helic* = coil, helix

When the deep arteries dilate, the lacunae fill with blood and the erectile tissues swell. The tunica albuginea around the corpora cavernosa cannot expand much, so pressure builds especially in these two erectile tissues and the penis becomes elongated and erect. The corpus spongiosum becomes less engorged, but swells and becomes more visible as a cordlike ridge along the ventral surface of the penis. When the penis is flaccid, most of its blood supply comes from the dorsal arteries. A median **deep dorsal vein** drains blood from the penis. It runs between the two dorsal arteries beneath the deep fascia and empties into a plexus of prostatic veins.

The penis is richly innervated by sensory and motor nerve fibers. The glans has an abundance of tactile, pressure, and temperature receptors, especially on its proximal margin and frenulum. They lead by way of a pair of prominent **dorsal nerves** to the **internal pudendal nerves,** then via the sacral plexus to spinal cord segments S2 to S4. Sensory fibers of the shaft, scrotum, perineum, and elsewhere are also highly important to sexual stimulation.

Both autonomic and somatic motor fibers carry signals from integrating centers in the spinal cord to the penis and other pelvic organs. Sympathetic nerve fibers arise from levels T12 to L2, pass through the hypogastric and pelvic nerve plexuses, and innervate the penile arteries, trabecular muscle, spermatic ducts, and accessory glands. They dilate the penile arteries and can induce erection even when the sacral region of the spinal cord is damaged. They also initiate erection in response to input from the special senses and to sexual thoughts.

Parasympathetic fibers extend from segments S2 to S4 of the spinal cord through the pudendal nerves to the arteries of the penis. They are involved in an autonomic reflex arc that causes erection in response to direct stimulation of the penis and other perineal organs.

DEEPER INSIGHT 26.2

Reproductive Effects of Pollution

In recent decades, wildlife biologists have noticed increasing numbers of male birds, fish, and alligators with a variety of abnormalities in reproductive development. These deformities have been attributed to chemical pollutants called *endocrine disruptors* or *estrogen mimics*. Evidence is mounting that humans, too, are showing declining fertility and increasing anatomical abnormalities due to pollutants in water, meat, vegetables, and even breast milk and the uterine environment.

Over the last several decades, there has been an alarming increase in the incidence of *cryptorchidism* (undescended testes) and *hypospadias* (a condition in which the urethra opens on the ventral side of the penis instead of at the tip). The rate of testicular cancer has more than tripled in that time. Data on 15,000 men from several countries also show a sharp drop in average sperm count—from 113 million/mL in 1940 to only 66 million/mL in 1990. Total sperm production decreased even more, because the average volume of semen per ejaculate dropped 19% over this period.

The pollutants implicated in this trend include a wide array of common herbicides, insecticides, industrial chemicals, and breakdown products of materials ranging from plastics to dishwashing detergents. Some authorities think these chemicals act by mimicking estrogens or blocking testosterone receptors. Other scientists question the data and feel the issue may be overstated, but there is nevertheless a strong interest at this time in screening industrial chemicals for endocrine effects. In 1996, the U.S. Congress directed the Environmental Protection Agency to screen and test thousands of environmental contaminants for endocrine effects, but the program became mired in bureaucracy and made little progress.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

3. Name the stages of spermatogenesis from spermatogonium to spermatozoon. How do they differ in the number of chromosomes per cell and chromatids per chromosome?
4. Name two types of cells in the testis other than the germ cells, and describe their locations and functions.
5. Describe the three major parts of a spermatozoon and state what organelles or cytoskeletal components are contained in each.
6. Name all the ducts the sperm follow, in order, from the time they form in the testis to the time of ejaculation.
7. Describe the locations and functions of the seminal vesicles, prostate, and bulbourethral glands.
8. Name the erectile tissues of the penis, and describe their locations relative to each other.

26.3 The Female Reproductive System APR

Expected Learning Outcomes

When you have completed this section, you should be able to

a. describe the structure of the ovary;
b. describe the stages of oogenesis and how these relate to changes in histology of the ovarian follicles;
c. trace the female reproductive tract and describe the gross anatomy and histology of each organ;
d. describe changes in the uterine lining through the menstrual cycle;
e. identify the ligaments that support the female reproductive organs;
f. describe the blood supply to the female reproductive tract;
g. identify the external genitalia of the female; and
h. describe the structure of the nonlactating breast and lactating mammary gland.

Figure 26.10 shows the female reproductive tract. The principal reproductive organs of the pelvic cavity are the *ovaries, uterine tubes, uterus,* and *vagina,* which will be described in that order.

The Ovaries

The female gonads are the **ovaries,**[27] which produce egg cells (ova) and sex hormones. The ovary is an almond-shaped organ nestled in a depression of the posterior pelvic wall called the *ovarian fossa.* It measures about 3 cm long, 1.5 cm wide, and 1 cm thick. Its capsule, like that of the testis, is called the **tunica albuginea.** The interior of the ovary is indistinctly divided into a central **medulla** and an outer **cortex** (fig. 26.11). The medulla is a core of fibrous connective tissue occupied by the principal arteries and veins of the ovary. The cortex is the site of the ovarian **follicles,** each of which consists of one developing ovum surrounded by numerous small **follicular cells.** The ovary does not have a system of tubules like the testis; eggs are released one at a time by the bursting of the follicles *(ovulation).* In childhood, the ovaries are smooth-surfaced. During the reproductive years, they become more corrugated because growing follicles of various stages produce bulges in the surface. After menopause, the ovaries become shrunken and composed mostly of scar tissue.

The ovaries and other internal genitalia are held in place by several connective tissue ligaments (fig. 26.12). The medial pole of the ovary is attached to the uterus by the **ovarian ligament** and its lateral pole is attached to the pelvic wall by the **suspensory ligament.** The anterior margin of the ovary is anchored by a peritoneal fold called the **mesovarium.**[28] This ligament extends to a sheet of peritoneum called the **broad ligament,** which flanks the uterus and encloses the uterine tube in its superior margin. If you picture these ligaments as a sideways T (⊣), the vertical bar would represent the broad ligament—flanking the uterus and enfolding


Round ligament
Uterus
Peritoneum
Urinary bladder
Pubic symphysis
Mons pubis
Urethra
Clitoris
Prepuce
Labium minus
Labium majus
Uterine tube
Fimbriae
Ovary
Vesicouterine pouch
Rectouterine pouch
Posterior fornix
Cervix of uterus
Anterior fornix
Rectum
Anus
Vaginal rugae
Vaginal orifice

Figure 26.10 **The Female Reproductive System.** See figure A.14b (p. 342) for a corresponding cadaver dissection photograph. APR

---

[27] *ov* = egg; *ary* = place for

[28] *mes* = middle; *ovari* = ovary



Figure 26.11 **Structure of the Ovary.** Arrows indicate the developmental sequence of the ovarian follicles; follicles do not migrate around the ovary, and not all the follicle types illustrated here are present simultaneously. AP|R

the uterine tube at its upper end—and the horizontal bar would represent the mesovarium enfolding the ovary at its free end.

The ovary receives blood from two arteries: the **ovarian branch of the uterine artery,** which passes through the mesovarium and approaches the medial pole of the ovary, and the **ovarian artery,** which passes through the suspensory ligament and approaches the lateral pole (see fig. 26.18). The ovarian artery is the female equivalent of the male testicular artery, arising high on the aorta and traveling down to the gonad along the posterior body wall. The ovarian and uterine arteries anastomose along the margin of the ovary and give off multiple small arteries that enter the ovary on that side. Ovarian veins, lymphatics, and nerves also travel through the suspensory ligament. The veins and lymphatics follow a course similar to those of the testes described earlier.

Oogenesis and Folliculogenesis AP|R

The most conspicuous feature of the ovary, upon microscopic examination, is a variety of follicles in various developmental stages (fig. 26.11). To make sense of its appearance requires at least a basic understanding of the processes of egg and follicle development.

Egg production is called **oogenesis**[29] (OH-oh-JEN-eh-sis) (fig. 26.13). Like spermatogenesis, it employs meiosis and produces haploid gametes. It differs from spermatogenesis in other respects, however: It is not a continual process, but occurs in a rhythm called the **ovarian cycle,** and for each original germ cell (oogonium), it produces only one functional gamete. The other daughter cells are tiny **polar bodies** that soon die.

Female primordial germ cells arise, like those of the male, from the yolk sac of the embryo. They colonize the gonadal ridges in the first 5 to 6 weeks and then differentiate into **oogonia** (OH-oh-GO-nee-uh). All of these become **primary oocytes** by the time of birth. Furthermore, most of them die in childhood—a "weeding out" process called *atresia.* The survivors remain dormant until puberty. Any stage from the primary oocyte to the time of fertilization can be called an *egg* or *ovum.* A girl has about 200,000 eggs at the onset of puberty, and they are considered to be her lifetime supply of germ cells.

A female in her reproductive years typically *ovulates,* or releases an egg from the ovary, about 14 days after the start of each menstrual period. That particular egg has a long history.

---

[29] *oo* = egg; *genesis* = production


Uterine tube
Mesovarium
Ovary
Broad ligament:
Mesosalpinx
Mesometrium
(b)
Infundibulum
Ampulla
Isthmus
Fundus
Body
Ovarian ligament
Mesosalpinx
Uterine tube
Ovarian artery
Ovarian vein
Suspensory ligament
Ovary
Mesometrium
Fimbriae
Perimetrium
Myometrium
Endometrium
Internal os
Cervical canal
Lateral fornix
Cervix
External os
Vagina
Round ligament
Broad ligament
Cardinal ligament
Uterosacral ligament
(a)
Suspensory ligament
Uterine tube:
Fimbriae
Infundibulum
Ampulla
Ovary
Ovarian ligament
Round ligament
Uterus:
Fundus
Body
Cervix
Vagina
(c)

© McGraw-Hill Education/Rebecca Gray, photographer/Don Kincaid, dissections

Figure 26.12 **The Female Reproductive Tract and Supportive Ligaments.** (a) Posterior view of the reproductive tract. (b) Relationship of the uterine tube and ovary to the supporting ligaments. (c) Anterior view of the major female reproductive organs from a cadaver. APR


Development of egg (oogenesis)
Development of follicle (folliculogenesis)
Before birth
Mitosis
2n
Multiplication of oogonia
2n
Primary oocyte
Oocyte
Nucleus
Follicular cells
Primordial follicle
No change
Adolescence to menopause
Meiosis I
n
Secondary oocyte
n
First polar body (dies)
Granulosa cells
Primary follicle
Granulosa cells
Zona pellucida
Theca folliculi
Secondary follicle
Antrum
Cumulus oophorus
Theca interna
Theca externa
Tertiary follicle
n
Secondary oocyte (ovulated)
If not fertilized
If fertilized
n
n
n
Dies
n
Second polar body (dies)
Meiosis II
2n
Zygote
Embryo
Bleeding into antrum
Ovulated oocyte
Follicular fluid
Ovulation of mature (graafian) follicle
Corpus luteum

© Ed Reschke/Getty Images

© Ed Reschke/Getty Images

© McGraw-Hill Education/Al Telser, photographer

© Ed Reschke/Getty Images

© Landrum B. Shettles, M.D.

© McGraw-Hill Education/Al Telser, photographer

Figure 26.13 Oogenesis (Left) and Corresponding Development of the Follicle (Right). APR

Except during pregnancy and lactation, a cohort of 20 to 25 follicles is awakened each month from its childhood dormancy. Their eggs begin a process of renewed development until one of them ovulates about 290 days later. The reason that a woman ovulates once a month is not because it takes only a month for the egg to develop, but because these 290-day ovarian cycles occur in overlapping waves.

A reactivated primary oocyte completes meiosis I, dividing into a large **secondary oocyte** and a small cell called the **first polar body** (fig. 26.13). Meiosis I reduces the chromosome number by half, so the secondary oocyte is haploid. It retains as much of the cytoplasm as possible, so that if it is fertilized, it can divide repeatedly and produce the numerous daughter cells needed to constitute an embryo. Splitting each oocyte into four equal but small parts would run counter to this purpose. The first polar body is simply a way of discarding the other haploid set of chromosomes, and it soon dies. The secondary oocyte begins meiosis II and then goes into developmental arrest again until after ovulation. If this egg is fertilized, it completes meiosis II and produces a **second polar body.** If not fertilized, it dies and never finishes meiosis.

The stages of oogenesis are accompanied by **folliculogenesis,** a series of changes in the follicle. The primary oocyte is initially enclosed in a **primordial follicle,** composed of a single layer of squamous follicular cells applied tightly to the oocyte (fig. 26.14a). Primordial follicles are concentrated near the surface of the ovary. As the egg develops and enlarges, the follicular cells around it expand into a cuboidal shape; a follicle with a single layer of cuboidal cells around the egg is termed a **primary follicle.** While the egg enlarges still more, the follicular cells multiply and pile atop each other. Once they form two or more layers, the cells are called **granulosa cells** and the follicle is called a **secondary follicle.** Granulosa cells secrete a layer of glycoprotein gel, the **zona pellucida,**[30] around the egg while the connective tissue surrounding them condenses into a fibrous husk called the **theca**[31] **folliculi** (THEE-ca fol-IC-you-lye). The theca and granulosa cells are the female's primary source of estrogen.

Most of the primary and secondary follicles degenerate with no further development, but a few of them begin to secrete pools of estrogen-rich **follicular fluid** among the granulosa cells. Once these pockets of fluid appear, the follicle is called a **tertiary follicle.** The fluid pools grow and merge until they form a single cavity, the **antrum;** because of this, tertiary and mature follicles are also called **antral follicles.** By this time, the theca folliculi also has further differentiated into two layers—an outer, fibrous *theca externa* and an inner, cellular *theca interna.* Follicles reach the antral stage about 40 to 50 days before ovulation. About 20 days before ovulation, one of them is somehow selected to be the dominant follicle, the one destined to ovulate. The others undergo atresia—they die.

During the week leading up to ovulation, the dominant follicle enlarges to as much as 2.5 cm in diameter and bulges like a blister from the surface of the ovary. It is now called a **mature (graafian**[32]**) follicle** (fig. 26.14b). Its oocyte is held against the follicular wall by a mound of granulosa cells called the **cumulus oophorus**[33] (CUE-mew-lus oh-OFF-or-us). The gelatinous zona pellucida still separates the granulosa cells from the oocyte and appears as a clear space in histological sections. The innermost layer of cumulus cells is called the **corona radiata.**[34] Microvilli from the corona cells and the oocyte span the zona pellucida. Like the blood–testis barrier of the male, the zona pellucida protects the egg from antibodies and other harmful chemicals, ensuring that nothing can get to the egg without being screened by the corona cells.

APR Ovulation, typically occurring around day 14 of the menstrual cycle, takes only 2 or 3 minutes. A nipplelike **stigma** appears on the ovarian surface overlying the mature follicle. The follicle ruptures, releasing the oocyte through the stigma (fig. 26.15). The rest of the follicle collapses and bleeds into the antrum. As the clotted

---

[30] *zona* = zone; *pellucid* = clear, transparent

[31] *theca* = box, case

[32] Reijnier de Graaf (1641–73), Dutch physiologist and histologist

[33] *cumulus* = little mound; *oo* = egg; *phor* = to carry

[34] *corona* = crown; *radiata* = radiating



© Ed Reschke/Getty Images

© Ed Reschke/Getty Images

Figure 26.14 **Ovarian Follicles.** (a) Primordial and primary follicles. Note the very thin layer of squamous cells around the oocyte in a primordial follicle, and the single layer of cuboidal cells in a primary follicle. (b) A mature (graafian) follicle. Just before ovulation, this follicle will grow to as much as 2.5 cm (1 in.) in diameter. APR



Figure 26.15 **Endoscopic Photograph of Human Ovulation.** The oocyte is shrouded by a blanket of cumulus oophorus cells.

blood is slowly absorbed, granulosa and theca interna cells multiply and fill the antrum, and a dense bed of blood capillaries grows amid them. The ovulated follicle has now become a structure called the **corpus luteum,**[35] named for a yellow lipid that accumulates in the theca interna cells (see fig. 26.11). These cells are now called **lutein cells.** The corpus luteum secretes a large amount of progesterone, which stimulates the uterus to prepare for possible pregnancy.

If pregnancy does not occur, the corpus luteum atrophies from days 24 to 26—a process called *involution.* By day 26 or so, involution is complete and the corpus luteum becomes an inactive scar, the **corpus albicans.**[36] If pregnancy occurs, however, the corpus luteum remains active for about 3 months, producing progesterone to sustain the early pregnancy. The placenta eventually takes over that task.

These events in the ovarian cycle are correlated with changes in uterine histology, which we will examine later.

The Uterine Tubes

An ovulated oocyte is swept into the **uterine tube,** also called the **oviduct** or **fallopian**[37] **tube** (see fig. 26.10). The tube is a ciliated canal about 10 cm long leading from the ovary to the uterus. At the distal (ovarian) end, it flares into a trumpet-shaped **infundibulum**[38] with feathery projections called **fimbriae**[39] (FIM-bree-ee); the middle and longest part of the tube is the **ampulla;** and the segment near the uterus is a narrower **isthmus.** The uterine tube is enclosed in the **mesosalpinx**[40] (MEZ-oh-SAL-pinks), which is the superior margin of the broad ligament.

The wall of the uterine tube is well endowed with smooth muscle. Its mucosa is highly folded into longitudinal ridges and has an epithelium of ciliated cells and a smaller number of secretory **peg cells** (fig. 26.16). The cilia beat toward the uterus and, with the help of muscular contractions of the tube, convey the egg in that direction.

The Uterus

The **uterus**[41] is a thick muscular chamber that opens into the roof of the vagina and usually tilts forward over the urinary bladder (see figs. 26.10 and 26.12). Its function is to harbor the fetus, provide it with a source of nutrition (the placenta, composed partially of uterine tissue), and expel the fetus at the end of gestation (pregnancy). It is somewhat pear-shaped, with a broad superior curvature called the **fundus,** a midportion called the **body (corpus),** and a narrow inferior end called the **cervix.** The uterus measures about 7 cm from cervix to fundus, 4 cm wide at its broadest point on the fundus, and 2.5 cm thick, but it is somewhat larger in women who have been pregnant.

The lumen of the uterus is roughly triangular, with its two upper corners opening into the uterine tubes. In the nonpregnant uterus, the lumen is not a hollow cavity but rather a *potential space* (see p. 18); the mucous membranes of the opposite walls



Figure 26.16 **Epithelial Lining of the Uterine Tube.** Secretory cells are shown in red and green, and cilia of the ciliated cells in yellow (SEM). APR

are pressed together with little room between them. The lumen communicates with the vagina by way of a narrow passage through the cervix called the **cervical canal.** The superior opening of this canal into the body of the uterus is the *internal os*[42] (pronounced "oz" or "ose"), and its opening into the vagina is the *external os.* The canal contains **cervical glands** that secrete mucus, thought to prevent the spread of microbes from the vagina into the uterus. Near the time of ovulation, the mucus becomes thinner than usual and allows easier passage for sperm.

---

[35] *corpus* = body; *lute* = yellow
[36] *corpus* = body; *alb* = white
[37] Gabriele Fallopio (1528–62), Italian anatomist and physician
[38] *infundibulum* = funnel
[39] *fimbria* = fringe
[40] *meso* = mesentery; *salpin* = trumpet
[41] *uterus* = womb

The Uterine Wall

The uterine wall consists of an external serosa called the *perimetrium,* a middle muscular layer called the *myometrium,* and an inner mucosa called the *endometrium.* The **perimetrium** is composed of simple squamous epithelium overlying a thin layer of areolar tissue. The **myometrium,**[43] about 1.25 cm thick in the nonpregnant uterus, constitutes most of the wall. It is composed mainly of bundles of smooth muscle that sweep downward from the fundus and spiral around the body of the uterus. The myometrium is less muscular and more fibrous near the cervix; the cervix itself is almost entirely fibrous (collagenous). The muscle cells of the myometrium are about 40 µm long immediately after menstruation, twice this long at the middle of the menstrual cycle, and up to 10 times as long in pregnancy. The function of the myometrium is to produce the labor contractions that help to expel the fetus.

The inner lining of the uterus, or mucosa, is called the **endometrium.**[44] It has a simple columnar epithelium, compound tubular glands, and a stroma populated by leukocytes, macrophages, and other cells (fig. 26.17). The superficial half to two-thirds of it, called the **functional layer** (**stratum functionalis),** is shed in each menstrual period. The deeper layer, called the **basal layer** (**stratum basalis),** stays behind and regenerates a new functionalis in the next cycle. When pregnancy occurs, the endometrium is the site of attachment of the embryo and forms the maternal part of the placenta.

Ligaments

The uterus is supported by the muscular floor of the pelvic outlet and folds of peritoneum that form supportive ligaments around the organ, as they do for the ovary and uterine tube (see fig. 26.12). The **broad ligament** has two parts: the *mesosalpinx* mentioned earlier and the *mesometrium* on each side of the uterus. The cervix and superior part of the vagina are supported by **cardinal (lateral cervical) ligaments** extending to the pelvic wall. A pair of **uterosacral ligaments** attach the posterior surface of the uterus to the sacrum, and a pair of **round ligaments** arise from the anterior surface of the uterus, pass through the inguinal canals, and terminate in the labia majora.

As the peritoneum folds around the various pelvic organs, it creates several dead-end recesses and pouches (extensions of the peritoneal cavity). Two major ones are the **vesicouterine**[45] **pouch,** which forms the space between the uterus and urinary bladder, and the **rectouterine pouch** between the uterus and rectum (see fig. 26.10).



© Ed Reschke/Getty Images

Figure 26.17 **Histology of the Endometrium.** This shows only the functional layer. APR

Blood Supply

The uterine blood supply is particularly important to the menstrual cycle and pregnancy. A **uterine artery** arises from each internal iliac artery and travels through the broad ligament to the uterus (fig. 26.18). It gives off several branches that penetrate into



Figure 26.18 **Blood Supply to the Female Reproductive Tract.** The vaginal, uterine, and ovarian arteries are exaggerated in length by the perspective of the drawing, moving the aorta away from the uterus for clarity.

---

[42] *os* = mouth
[43] *myo* = muscle; *metr* = uterus
[44] *endo* = inside; *metr* = uterus
[45] *vesico* = bladder

the myometrium and lead to **arcuate arteries.** Each arcuate artery travels in a circle around the uterus and anastomoses with the arcuate artery on the other side. Along its course, it gives rise to smaller arteries that penetrate the rest of the way through the myometrium, into the endometrium, and produce the **spiral arteries.** Spiral arteries coil between the endometrial glands toward the surface of the mucosa. They rhythmically constrict and dilate, making the mucosa alternately blanch and flush with blood.

Cyclic Changes in Uterine Histology

Uterine histology is not constant. In fertile women, it changes throughout the **menstrual cycle,** the monthly rhythm of endometrial buildup, breakdown, and discharge. This cycle averages 28 days long, with day 1 considered to be the first day of visible vaginal discharge of menstrual fluid. Why that discharge occurs is best understood by first considering the histological changes leading up to it.

The **proliferative phase** is a time of rebuilding of endometrial tissue lost at the last menstruation. At the end of menstruation, around day 5, the endometrium is about 0.5 mm thick and consists only of the basal layer. The functional layer is rebuilt by mitosis from day 6 to day 14, under the influence of estrogen from the growing ovarian follicles. By day 14, the endometrium is about 2 to 3 mm thick (fig. 26.19a).

The **secretory phase** is a period of further endometrial thickening, but results from secretion and fluid accumulation rather than mitosis. It extends from day 15 (after ovulation) to day 26 of a typical cycle, and is stimulated by progesterone from the corpus luteum. In this phase, the endometrial glands grow wider, longer, and more coiled. As a result of the coiling, a vertical section through the endometrium shows these glands with a sawtooth or zigzag appearance (fig. 26.19b). Endometrial cells and the uterine stroma accumulate glycogen during this phase. By the end of the secretory phase, the endometrium is about 5 to 6 mm thick—a soft, wet, nutritious bed available for embryonic development in the event of pregnancy.



(a) Proliferative phase (b) Secretory phase (c) Menstrual phase

Figure 26.19 **Endometrial Changes Through the Menstrual Cycle.** (a) Late proliferative phase. The endometrium is 2 to 3 mm thick and has relatively straight, narrow endometrial glands. Spiral arteries penetrate upward between the endometrial glands. (b) Secretory phase. The endometrium has thickened to 5 to 6 mm by accumulation of glycogen and mucus. The endometrial glands are much wider and more distinctly coiled, showing a zigzag or "sawtooth" appearance in histological sections. (c) Menstrual phase. Ischemic tissue has begun to die and fall away from the uterine wall, with bleeding from broken blood vessels and pooling of blood within the tissue and in the uterine cavity.

The **premenstrual phase** is a period of endometrial degeneration occuring in the last 2 days or so of the menstrual cycle. When the corpus luteum involutes, the spiral arteries exhibit spasmodic contractions that cause endometrial ischemia (interrupted blood flow). The premenstrual phase is therefore also called the **ischemic** (iss-KEE-mic) **phase.** Ischemia leads to tissue necrosis. As the endometrial glands, stroma, and blood vessels degenerate, pools of blood accumulate in the stratum functionalis. Necrotic endometrium falls away from the uterine wall, mixes with blood and serous fluid in the lumen, and forms the **menstrual fluid** (fig. 26.19c).

The **menstrual phase (menses)** begins when enough menstrual fluid has accumulated in the uterus that it begins to be discharged vaginally. The first day of external discharge marks day 1 of a new cycle.

The Vagina

The **vagina**[46] is a tube about 8 to 10 cm long that allows for the discharge of menstrual fluid, receipt of the penis and semen, and birth of a baby. The vaginal wall is thin but very distensible. It consists of an outer adventitia, a middle muscularis, and an inner mucosa. The vagina tilts posteriorly between the urethra and rectum; the urethra is bound to its anterior wall. The vagina has no glands, but it is lubricated by the *transudation* ("vaginal sweating") of serous fluid through its walls and by mucus from the cervical glands above it. The vagina extends slightly beyond the cervix and forms blind spaces called **fornices**[47] (FOR-nih-sees; singular, *fornix*) surrounding it (see fig. 26.10).

The lower end of the vagina has transverse friction ridges, or **vaginal rugae,** which contribute to both male and female stimulation during intercourse. At the vaginal orifice, the mucosa folds inward and forms a membrane, the **hymen,** which stretches across the opening. The hymen has one or more openings to allow menstrual fluid to pass, but it usually must be ruptured to allow for intercourse. A little bleeding often accompanies the first act of intercourse; however, the hymen is commonly ruptured before then by tampons, medical examinations, or strenuous exercise.

The vaginal epithelium is simple cuboidal in childhood, but the estrogens of puberty transform it into a stratified squamous epithelium. This is another example of metaplasia. The epithelial cells are rich in glycogen. Bacteria ferment this to lactic acid, which produces a low vaginal pH (about 3.5–4.0) that inhibits the growth of pathogens. The mucosa also has antigen-presenting cells called **dendritic cells,** which normally help in defense against infection but which also are a route by which HIV invades the female body.

Apply What You Know

Why do you think the vaginal epithelium changes type at puberty? Of all types of epithelium it might become, why stratified squamous?

The External Genitalia

The external genitalia of the female occupy most of the perineum, and are collectively also known as the **vulva**[48] or **pudendum**[49] (fig. 26.20). The perineum has the same skeletal landmarks in the female as in the male. The muscle layers of the female perineum are of special importance in obstetrics (see table 11.8 and figure 11.16, pp. 287–288).

The **mons**[50] **pubis** (see fig. 1.10a, p. 14) consists mainly of an anterior mound of adipose tissue overlying the pubic symphysis, covered with skin and bearing pubic hair. The **labia majora**[51] (singular, *labium majus*) are a pair of thick folds of skin and adipose tissue inferior to the mons, between the thighs; the fissure between them is the *pudendal cleft.* Pubic hair grows on the lateral surfaces of the labia majora at puberty, but the medial surfaces are hairless. Medial to the labia majora are entirely hairless and much thinner **labia minora**[52] (singular, *labium minus*). The area enclosed by them, called the **vestibule,** contains the urinary and vaginal orifices. At the anterior margin of the vestibule, the labia minora meet and form a hoodlike **prepuce** over the clitoris.

The **clitoris**[53] (CLIT-er-is or cli-TOR-is) is structured much like the penis in many respects, but has no urinary role. Its function is entirely sensory, serving as the primary center of sexual stimulation. Unlike the penis, it is almost entirely internal, it has no corpus spongiosum, and it does not enclose the urethra. Essentially, it is a pair of corpora cavernosa enclosed in connective tissue. Its head, the **glans,** protrudes slightly from the prepuce. The **body (corpus)** passes internally, inferior to the pubic symphysis (see fig. 26.10). At its internal end, the corpora cavernosa diverge like a Y as a pair of **crura,** which, like those of the penis, attach the clitoris to each side of the pubic arch. The circulation and innervation of the clitoris are largely the same as for the penis.

Just deep to the labia majora, a pair of subcutaneous erectile tissues called the **vestibular bulbs** bracket the vagina like parentheses. They become congested with blood during sexual excitement and cause the vagina to tighten somewhat around the penis, enhancing sexual stimulation.

Next to the vagina are a pair of pea-sized **greater vestibular (Bartholin**[54]**) glands** with short ducts opening into the vestibule or lower vagina (fig. 26.20b). These are the counterpart to the bulbourethral glands of the male. They keep the vulva moist, and during sexual excitement they provide most of the lubrication for intercourse. The vestibule is also lubricated by a number of **lesser vestibular glands.** A pair of mucous **paraurethral (Skene**[55]**) glands** opens into the vestibule near the external urethral orifice. These glands may eject fluid, sometimes abundantly, during orgasm ("female ejaculation"). They arise from the same embryonic structure as the male prostate, and their fluid is similar to the prostatic secretion.

---

[46] *vagina* = sheath
[47] *fornix* = arch, vault
[48] *vulva* = covering
[49] *pudend* = shameful
[50] *mons* = mountain
[51] *labi* = lip; *major* = larger, greater
[52] *minor* = smaller, lesser
[53] origin uncertain; possibly from *kleis* = door key, or *klei* + *ein* = to close
[54] Caspar Bartholin (1655–1738), Danish anatomist
[55] Alexander J. C. Skene (1838–1900), American gynecologist



Figure 26.20 **The Female Perineum.** (a) Surface anatomy. (b) Subcutaneous structures.

- *Which of the glands in part (b) is homologous to the male prostate gland?* AP|R

The Breasts and Mammary Glands

The mature female **breast** (fig. 26.21) is a mound of tissue overlying the pectoralis major. It enlarges at puberty and remains so for life, but most of this time it contains very little mammary gland. The **mammary gland** develops within the breast during pregnancy, remains active in the lactating breast, and atrophies when a woman ceases to nurse.

The breast has two principal regions: the conical to pendulous **body,** with the nipple at its apex, and an extension toward the armpit called the **axillary tail.** Lymphatics of the axillary tail are especially important as a route of breast cancer metastasis.

The nipple is surrounded by a circular colored zone, the **areola.** Dermal blood capillaries and nerves come closer to the surface here than in the surrounding skin and make the areola more sensitive and darker in color. In pregnancy, the areola and nipple often darken further, making them more visible to the indistinct vision of a nursing infant. Sensory nerve fibers of the areola are important in triggering a *milk ejection reflex* when an infant nurses. The areola has sparse hairs and **areolar glands,** visible as small bumps on the surface. These glands are intermediate between sweat glands and mammary glands in their degree of development. When a woman is nursing, secretions of the areolar glands and sebaceous glands protect the areola from chapping and cracking. The dermis of the areola has smooth muscle fibers that contract in response to cold, touch, and sexual arousal, wrinkling the skin and erecting the nipple.

Internally, the nonlactating breast consists mostly of adipose and collagenous tissue (fig. 26.21). Breast size is determined by the amount of adipose tissue and has no relationship to the amount of milk the mammary gland can produce. **Suspensory ligaments** attach the breast to the dermis of the overlying skin and to the fascia of the pectoralis major. The nonlactating breast contains very little glandular tissue, but it does have a system of ducts branching through its connective tissue stroma and converging on the nipple.

When the mammary gland develops during pregnancy, it exhibits 15 to 20 lobes arranged radially around the nipple, separated from each other by fibrous stroma. Each lobe is drained by a **lactiferous**[56] **duct,** which dilates to form a **lactiferous sinus** opening onto the nipple. Internally, this duct branches repeatedly with the finest branches ending in sacs called acini. The acini are organized into grapelike clusters (lobules) within each lobe of the breast. Each acinus consists of a sac of pyramidal secretory cells arranged around a central lumen (see fig. 3.29, p. 76). Like an orange in a plastic mesh bag, the acinus is surrounded by a network of contractile **myoepithelial cells** around the secretory cells (fig. 26.21d). When a woman nurses, stimulation of the nipple induces the posterior lobe of the pituitary gland to secrete oxytocin. Oxytocin stimulates the myoepithelial cells to contract, squeezing milk from the acini into the lactiferous ducts.

---

[56] *lact* = milk; *fer* = to carry


Adipose tissue
Suspensory ligaments
Lobe
Lobules
Areolar glands
Areola
Nipple
Lactiferous sinus
Lactiferous ducts

From *Anatomy & Physiology Revealed*, © McGraw-Hill Education/The University of Toledo, photography and dissection

(a) Anterior view

(b) Breast of cadaver


Rib
Intercostal muscles
Pectoralis minor
Pectoralis major
Fascia
Suspensory ligament
Lobules
Lobe
Adipose tissue
Nipple
Lactiferous sinus
Lactiferous duct
Secretory cells
Myoepithelial cells

© Dr. Donald Fawcett/Science Source

(c) Sagittal section

(d) Mammary acinus

Figure 26.21 **The Breast.** Parts (a), (c), and (d) depict the breast in a lactating state. Some of the features in (a) and (c) are absent from the nonlactating breast in part (b). The cluster of lobules boxed in (c) would contain numerous microscopic acini like the one in (d). Part (d) is not to be construed as an enlargement of the entire boxed area of (c).

- *What is the function of the myoepithelial cells in (d)?*

Before You Go On

Answer the following questions to test your understanding of the preceding section:

9. What are the stages of oogenesis? Describe all the ways in which it differs from spermatogenesis.
10. Describe the changes that occur in the ovarian follicles and uterine endometrium over the course of the ovarian and menstrual cycle.
11. How does the structure of the uterine tube mucosa relate to its function?
12. What structures are externally visible in the vulva? Describe their anatomical arrangement.
13. Name the accessory glands of the vulva and state their locations and functions.
14. How does the structure of the nonlactating breast differ from that of the lactating breast? What is the difference between the breast and the mammary gland?

26.4 Developmental and Clinical Perspectives

Expected Learning Outcomes

When you have completed this section, you should be able to

a. explain how sexual differentiation is determined by the sex chromosomes and prenatal hormones;
b. describe the embryonic development of the reproductive system;
c. describe what aspects of anatomical development the male and female have in common, and how they become differentiated from each other;
d. summarize the changes in reproductive function that occur in old age; and
e. describe some reproductive disorders of each sex.

Prenatal Development and Sexual Differentiation

The male and female reproductive systems begin with embryonic sex organs that are anatomically "indifferent," yet genetically destined to differentiate into the genitalia of one sex or the other. Thus, the testes and ovaries develop from an initially indistinguishable *indifferent gonad;* the glans of the penis and clitoris develop from a single embryonic *genital tubercle;* and the scrotum and labia majora develop from the embryonic *labioscrotal folds.* Organs that develop from the same embryonic precursor are said to be **homologous** to each other.

The Internal Genitalia

The gonad appears at 5 to 6 weeks as a **gonadal ridge** near the mesonephros, the primitive kidney. Adjacent to each gonadal ridge are two ducts, the **mesonephric**[57] and **paramesonephric**[58] **ducts.** In males, the mesonephric ducts develop into parts of the reproductive tract, and the paramesonephric ducts degenerate. In females, the opposite occurs (fig. 26.22).

The differentiation of these ducts into the organs of one sex or the other is determined by an interaction between genes and hormones. If the zygote has sex chromosomes X and Y, it is normally destined to develop into a male; if it has two X chromosomes and no Y, it will develop into a female. Thus, the sex of a child is determined at conception (fertilization), depending on whether the egg (always X) is fertilized by an X- or a Y-bearing sperm.

But why? The answer lies in the Y chromosome, where a gene called ***SRY*** (sex-determining region of the Y) codes for a protein called **testis-determining factor (TDF).** TDF then interacts with genes on some of the other chromosomes, including a gene on the X chromosome for androgen receptors and genes that initiate the development of male anatomy. By 8 to 9 weeks, the male gonadal ridge has become a rudimentary testis whose interstitial cells begin to secrete testosterone. Testosterone stimulates the mesonephric duct to develop into the system of male reproductive ducts. Sustentacular cells of the fetal testis secrete a hormone called **müllerian-inhibiting factor (MIF),** after the former name of the paramesonephric (müllerian) duct. MIF causes atrophy of the paramesonephric duct. Even an adult male, however, retains a tiny Y-shaped vestige of the paramesonephric ducts, like a vestigial uterus and uterine tubes, in the area of the prostatic urethra. It is named the *prostatic utricle.*[59]

In a female fetus, the absence of testosterone causes the mesonephric ducts to degenerate, and in the absence of MIF, the paramesonephric ducts develop "by default" into a female reproductive tract. Each duct differentiates into one of the uterine tubes. At their inferior end, the ducts fuse to form the single uterus and the upper one-third of the vagina. The lower two-thirds of the vagina develops as an outgrowth of the urogenital sinus described in chapter 25 (p. 698).

It may seem as if androgens should induce the formation of a male reproductive tract and estrogens induce a female reproductive tract. However, estrogen levels are always high during pregnancy, so if this mechanism was the case, it would feminize all fetuses. Thus, the development of a female results from the low level of androgens, not the presence of estrogens.

The External Genitalia

At 8 weeks, the external genitalia are represented by the following sexually undifferentiated structures (fig. 26.23):

- the **genital tubercle,** an anterior, median bud;
- **urogenital folds,** a pair of medial tissue folds slightly posterior to the genital tubercle; and
- **labioscrotal folds,** a larger pair of tissue folds lateral to the urogenital folds.

---

[57] *meso* = middle; *nephr* = kidney; named for the temporary embryonic kidney
[58] *para* = next to
[59] *utricle* = little bag


Mesonephros
Gonadal ridge
Kidney
Mesonephric duct
Paramesonephric (müllerian) duct
Cloaca
5 to 6 week embryo; sexually indifferent stage
Male
Female
Testes
Efferent ductules
Epididymis
Paramesonephric duct (degenerating)
Mesonephric duct forming the ductus deferens
Urinary bladder
Seminal vesicle
Urogenital sinus forming the urethra
7 to 8 weeks
Ovaries
Paramesonephric duct forming the uterine tube
Mesonephric duct (degenerating)
Fused paramesonephric ducts forming the uterus
Urinary bladder (moved aside)
Urogenital sinus forming the urethra and lower vagina
8 to 9 weeks
Urinary bladder
Seminal vesicle
Prostate gland
Bulbourethral gland
Ductus deferens
Epididymis
Testis
Urethra
Penis
At birth
Uterine tube
Ovary
Uterus
Urinary bladder (moved aside)
Vagina
Urethra
Hymen
Vestibule
At birth

Figure 26.22 **Embryonic Development of the Male and Female Reproductive Tracts.** Note that the male tract develops from the mesonephric duct and the female tract from the paramesonephric duct; the other duct in each sex degenerates.


Genital tubercle
Urogenital fold
Labioscrotal fold
Tail
6 weeks
8 weeks
Male
Phallus:
Developing glans of penis
Urethral groove
Anus
10 weeks
Urethral orifice
Glans of penis
Prepuce
Scrotum
Perineal raphe
Anus
12 weeks
Female
Developing glans of clitoris
Labia minora
Urethral groove
Labia majora
Anus
10 weeks
Prepuce
Glans of clitoris
Urethral orifice
Vaginal orifice
Perineal raphe
Anus
12 weeks

Figure 26.23 **Development of the External Genitalia.** By 6 weeks, the embryo has three primordial structures—the genital tubercle, urogenital folds, and labioscrotal folds—which will become the male or female genitalia. At 8 weeks, these structures have grown, but the sexes are still indistinguishable. Slight sexual differentiation is noticeable at 10 weeks. The sexes are fully distinguishable by 12 weeks. Matching colors identify homologous structures of the male and female.

These organs begin to show sexual differentiation by the end of week 9, and either male or female genitalia are distinctly identifiable by the end of week 12. In the female, the three structures just listed become the clitoral glans, labia minora, and labia majora, respectively. In the male, the genital tubercle elongates to form the *phallus;* the urogenital folds fuse to enclose the urethra, and join the phallus to form the penis; and the labioscrotal folds fuse to form the scrotum.

The homology of the male and female genitalia becomes strikingly evident in certain abnormalities of sexual development. In the presence of excess androgen, the clitoris may enlarge and the labioscrotal folds fuse, so closely resembling a penis and scrotum that a newborn girl can be misidentified as a boy. In other cases, the ovaries descend into the labia majora as if they were testes descending into a scrotum.

Descent of the Gonads

Both male and female gonads initially develop high in the abdominal cavity and migrate into the pelvic cavity (ovaries) or scrotum (testes). The most pronounced migration is the **descent of the testes** (fig. 26.24). In the embryo, a connective tissue cord called the **gubernaculum**[60] (GOO-bur-NACK-you-lum) extends from the gonad to the floor of the abdominopelvic cavity. As it continues to grow, it passes between the internal and external abdominal oblique muscles and into the scrotal swelling. Independently of any migration of the testis, the peritoneum also develops a fold that extends into the scrotum as the *vaginal process.* The gubernaculum and the vaginal process create a path of low resistance through the groin, the inguinal canal—the most common site of herniation in boys and men (*inguinal hernia;* see Deeper Insight 11.3, p. 289).

The descent of the testes begins as early as week 6. The superior part of the embryonic gonad degenerates, and its inferior part migrates downward, guided by the gubernaculum. In the seventh month, the testes abruptly pass through the inguinal canals, anterior to the pubic symphysis, into the scrotum. As they descend, they are accompanied by ever-elongating testicular arteries and veins and by lymphatic vessels, nerves, sperm ducts, and extensions of the internal abdominal oblique muscle that become the cremaster muscle. The vaginal process becomes separated from the peritoneal cavity and persists as a sac, the *tunica vaginalis,* enfolding the anterior side of the testis. Although multiple hypotheses have been offered, the actual mechanism of descent remains obscure. Testosterone stimulates the descent, but it is unknown how. About 3% of boys, however, are born with undescended testes, or *cryptorchidism* (see table 26.2).

The ovaries also descend, but to a much lesser extent. A gubernaculum extends from the inferior pole of the ovary to the labioscrotal fold. The ovaries eventually lodge just inferior to the brim of the lesser pelvis. The inferior part of the gubernaculum becomes the round ligament of the uterus, and the superior part becomes the ovarian ligament.

---

[60] *gubern* = rudder, to steer, guide



3-month fetus

8-month fetus

1-month-old infant

Figure 26.24 Descent of the Testis. Note that the testis and spermatic ducts are retroperitoneal. An extension of the peritoneum called the *vaginal process* follows the testis through the inguinal canal and becomes the tunica vaginalis.

- *Why is this structure of male anatomy called the tunica vaginalis?*

Puberty

Unlike any other organ system, the reproductive system remains dormant for several years after birth. At age 10 to 12 in most boys and 8 to 10 in most girls, however, the hypothalamus begins to secrete gonadotropin-releasing hormone (GnRH), and the pituitary responds by secreting the two gonadotropins—follicle-stimulating hormone (FSH) and luteinizing hormone (LH). These hormones, in turn, stimulate the gonads to secrete estrogens, progesterone, and testosterone. Combined with surges in the secretion of growth hormone and other hormones, the adolescent body exhibits pronounced anatomical changes. **Puberty,**[61] the first few years of **adolescence,**[62] has begun.

In boys, the earliest sign of puberty is usually enlargement of the testes and scrotum; in girls, it is breast development, called **thelarche**[63] (thee-LAR-kee). These changes are soon followed by **pubarche** (pyu-BAR-kee), the growth of pubic and axillary hair, sebaceous glands, and apocrine glands. In girls, the third principal event is **menarche**[64] (men-AR-kee), the first menstrual period. Menarche does not immediately signify fertility. A girl's first few menstrual cycles are typically *anovulatory* (no egg is ovulated). Most girls begin ovulating regularly about a year after they begin menstruating, probably because, as noted earlier, an egg requires almost 300 days to mature before it ovulates. The male counterpart to menarche is the first ejaculation. Puberty ends when an individual is fully capable of reproducing; adolescence extends until a person reaches full height in the late teens to early twenties.

Puberty entails many other changes too numerous for the scope of this book. The internal and external genitalia enlarge. Changes in muscularity and fat deposition bring about some of the male–female differences known as the *secondary sex characteristics*. The male voice deepens as the larynx enlarges. Testosterone, estrogens, and growth hormone cause rapid elongation of the long bones, and thus the adolescent growth in stature. Also, to the great anxiety of the parents of adolescents, the anatomical readiness for reproduction is accompanied by psychological interest in sex, the *libido,* elicited in both sexes by testosterone. (Testosterone is produced not only by the testes but also, in small amounts, by the ovaries and adrenal cortex.)

The Aging Reproductive System

Fertility and sexual function decline in and beyond middle age, owing to declining levels of testosterone and estrogen. Around ages 50 to 55, both men and women go through a period of physical and psychological change called *climacteric,* although (jokes about "male menopause" aside) only women experience *menopause,* the cessation of menses.

Male Climacteric

Male climacteric, or **andropause,** is a period of declining reproductive function that becomes noticeable, if at all, typically in the early 50s. It is brought on by falling levels of testosterone and inhibin. Testosterone secretion peaks at about 7 mg/day at age 20 and then declines steadily to as little as one-fifth of this level by age 80. There is a corresponding decline in the number and secretory activity of the interstitial cells (the source of testosterone) and sustentacular cells (the source of inhibin). Along with the declining testosterone level, the sperm count and libido diminish. By age 65, sperm count is typically about one-third of what it was in a man's 20s. Nevertheless, men remain capable of fathering a child throughout old age.

With reduced levels of testosterone and inhibin, the pituitary is less inhibited and it secretes elevated levels of FSH and LH. In some cases, these gonadotropins cause mood changes, hot flashes, or even illusions of suffocation—symptoms similar to those that occur in perimenopausal women. Most men, however, notice little or no effect as they pass through climacteric, and not all authorities accept that male climacteric exists at all.

About 20% of men in their 60s and 50% of men in their 80s experience *erectile dysfunction (impotence),* the frequent inability to maintain a sufficient erection for intercourse. Erectile dysfunction can also result from hypertension, atherosclerosis, medication, diabetes mellitus, and psychological causes. Over 90% of men with erectile dysfunction nevertheless remain able to ejaculate.

Female Climacteric and Menopause

Female climacteric is brought on by declining ovarian function. It generally begins when the ovaries are down to their last 1,000 eggs or so, and the follicles and ova that remain are less responsive to gonadotropins. Consequently, the follicles secrete less estrogen and progesterone. Without these steroids, the uterus, vagina, and breasts atrophy. Intercourse may become uncomfortable, and vaginal infections more common, as the vagina becomes thinner, less distensible, and drier. The skin becomes thinner, cholesterol levels rise (increasing the risk of cardiovascular disease), and bone mass declines (increasing the risk of osteoporosis). Blood vessels constrict and dilate in response to shifting hormone balances, and the sudden dilation of cutaneous arteries may cause *hot flashes*—a spreading sense of heat from the abdomen to the thorax, neck, and face. Hot flashes may occur several times a day, sometimes accompanied by headaches resulting from the sudden vasodilation of arteries in the head. In some people, the changing hormonal profile also causes mood changes.

Female climacteric is accompanied by **menopause,** the cessation of menstruation and end of fertility. Menopause usually occurs between the ages of 45 and 55. The average age has increased steadily in the last century and is now about 52. It is difficult to precisely establish the time of menopause because the menstrual periods can stop for several months and then begin again. Menopause is generally considered to have occurred when there has been no menstruation for a year or more.

Reproductive Disorders of the Male

Prostate cancer (see Deeper Insight 26.1) is the most common cancer of the male reproductive system, but not the only one.

---

[61] *puber* = grown up
[62] *adolesc* = to grow up
[63] *thel* = breast, nipple; *arche* = beginning
[64] *men* = monthly; *arche* = beginning

Men are also subject to testicular, penile, and breast cancer. Testicular cancer is the most common of these three and often strikes at a relatively young age compared to prostate cancer. Testicular self-examination combined with regular physical examinations are important preventive measures. Some additional facts about these cancers and other male reproductive disorders are given in table 26.2.

Reproductive Disorders of the Female

The most important malignancies of the female reproductive system are breast and cervical cancer, although the increase in cigarette smoking has caused lung cancer to surpass both of these as a cause of female mortality in the United States. Breast cancer occurs in one out of every eight or nine American women. Breast tumors originate in cells of the mammary ducts and may metastasize to other organs by way of mammary and axillary lymphatics. Although some breast cancer is genetic, many nonhereditary risk factors are also known, including age, early menarche and late menopause, high alcohol or fat consumption, and smoking. Over 70% of cases of breast cancer, however, lack any identifiable risk factor. Early detection through regular breast X-rays (mammograms) are currently regarded as the best protection. Breast self-examination (BSE) may also be helpful, but recent research has cast doubt on whether tumors are detected early enough by BSE to significantly reduce female mortality.

Uterine cancer is of two kinds, endometrial and cervical. Cervical cancer is a slow-growing neoplasia of the lower cervical canal and can be detected by microscopic examination of squamous cells from the cervix (a Pap smear; see Deeper Insight 26.3).

There are many other disorders of female reproductive function, too numerous to discuss here. Pregnancy adds its own risks to women's health. Table 26.3 describes some of the more common complications of pregnancy.

More common than any of the foregoing male or female reproductive disorders are the **sexually transmitted diseases (STDs),** caused by infectious microorganisms transmitted by intercourse and other sexual activity, and to infants during or before birth. Most of these are caused by viruses and bacteria. Currently the most serious viral STDs are **hepatitis C** and

TABLE 26.2 Some Male Reproductive Disorders

Breast cancer	Accounts for 0.2% of male cancers in the United States, usually seen after age 60 but sometimes in children and adolescents. (For every male who gets breast cancer, about 175 females do so.) Usually felt as a lump near the nipple, often with crusting and discharge from the nipple. Often quite advanced by the time of diagnosis, with poor prospects for recovery, because of denial and delay in seeking treatment.
Cryptorchidism[65] (crip-TOR-ki-dizm)	Failure of one or both testes to descend completely into the scrotum. Leads to infertility if not corrected, because undescended testes are too warm for spermatogenesis. In most cases, the testes descend spontaneously in the first year of infancy; otherwise, the condition can be corrected with hormone injections or surgery.
Hypospadias[66] (HY-po-SPAY-dee-us)	A congenital defect in which the urethra opens on the ventral side or base of the penis rather than at the tip; usually corrected surgically at about 1 year of age.
Infertility	Inability to fertilize an egg because of a low sperm count (< 20–25 million/mL), poor sperm motility, or a high percentage of deformed sperm (two heads, defective tails, etc.). May result from malnutrition, gonorrhea and other infections, toxins, or testosterone deficiency.
Penile cancer	Accounts for 1% of male cancers in the United States; most common in black males aged 50 to 70 and of low income. Most often seen in men with nonretractable foreskins *(phimosis)* combined with poor penile hygiene; least common in men circumcised at birth.
Testicular cancer	The most common solid tumor in men 15 to 34 years old, especially white males of middle to upper economic classes. Typically begins as a painless lump or enlargement of the testis. Highly curable if detected early. Men should routinely palpate the testes for normal size and smooth texture.
Varicocele (VAIR-ih-co-seal)	Abnormal dilation of veins of the spermatic cord, so they resemble a "bag of worms." Occurs in 10% of males in the United States. Caused by absence or incompetence of venous valves. Reduces testicular blood flow and often causes infertility.

Disorders Described Elsewhere

Benign prostatic hyperplasia 713	Erectile dysfunction 731	Prostate cancer 713

---

[65] *crypt* = hidden; *orchid* = testes
[66] *hypo* = below; *spad* = to draw off (the urine)

DEEPER INSIGHT 26.3

Cervical Cancer and Pap Smears

Cervical cancer is common among women between the ages of 30 and 50, especially those who smoke, who began sexual activity at an early age, and who have histories of frequent sexually transmitted diseases or cervical inflammation. It is often caused by the human papillomavirus (HPV), a sexually transmitted pathogen. Cervical cancer usually begins in the epithelial cells of the lower cervix, develops slowly, and remains a local, easily removed lesion for several years. If the cancerous cells spread to the subepithelial connective tissue, however, the cancer is said to be *invasive* and is much more dangerous and potentially fatal.

The best protection against cervical cancer is early detection by means of a *Pap*[67] *smear*—a procedure in which loose cells are removed from the cervix and vagina with a small flat stick or cervical brush, then microscopically examined. The pathologist looks for cells with signs of *dysplasia* (abnormal development) or carcinoma (fig. 26.25). One system of grading Pap smears classifies abnormal results in three grades of *cervical intraepithelial neoplasia (CIN).* Findings are rated on the following scale, and further vigilance or treatment planned accordingly:

ASCUS—atypical squamous cells of undetermined significance

CIN I—mild dysplasia with cellular changes typically associated with HPV

CIN II—moderate dysplasia with precancerous lesions

CIN III—severe dysplasia, *carcinoma in situ* (preinvasive carcinoma of surface cells)

A rating of ASCUS or CIN I calls for a repeat Pap smear and visual examination of the cervix *(colposcopy*[68]*)* in 3 to 6 months. CIN II calls for a biopsy, often done with an "electric scalpel" in a procedure called LEEP (loop electrosurgical excision procedure). A cone of tissue is removed to evaluate the depth of invasion by the malignant or premalignant cells. This in itself may be curative if all margins of the specimen are normal, indicating all abnormal cells were removed. CIN III may be cause for *hysterectomy*[69] or radiation therapy.

An average woman is typically advised to have annual Pap smears for 3 years and may then have them less often at the discretion of her physician. Women with any of the risk factors listed may be advised to have more frequent examinations.



(a) Normal cells

(b) Malignant (CIN III) cells

© SPL/Science Source

© Parviz M. Pour/Science Source

Figure 26.25 **Pap Smears.** These are smears of squamous epithelial cells scraped from the cervix. In the malignant (cancerous) cells, note the loss of cell volume and the greatly enlarged nuclei.

AIDS (caused by the human immunodeficiency virus, HIV; see p. 627). The hepatitis C virus (HCV) is a common cause of liver failure and is the leading reason for liver transplants in the United States. Other viral STDs include genital herpes (usually caused by herpes simplex virus type 2, HSV-2) and genital warts (caused by 60 or more human papillomaviruses, HPVs). Some forms of HPV are associated with cervical, vaginal, penile, and anal cancer.

---

[67] George N. Papanicolaou (1883–1962), Greek–American physician and cytologist

[68] *colpo* = vagina; *scopy* = viewing

[69] *hyster* = uterus; *ectomy* = cutting out

TABLE 26.3 Some Female Reproductive Disorders

Disorders of Pregnancy	
Abruptio placentae[70]	Premature separation of the placenta from the uterine wall, often associated with preeclampsia or cocaine use. May require birth by cesarean section.
Ectopic[71] **pregnancy**	Implantation of the conceptus anywhere other than the normal location in the uterus, such as the uterine tube (over 90% of cases), cervix, or abdominal cavity; usually must be surgically terminated to prevent serious and potentially fatal hemorrhage.
Gestational diabetes	A form of diabetes mellitus that develops in about 1% to 3% of pregnant women, characterized by insulin insensitivity, hyperglycemia, glycosuria, and a risk of excessive fetal size and birth trauma. Glucose metabolism usually returns to normal after delivery of the infant, but 40% to 60% of women with gestational diabetes develop diabetes mellitus within 15 years after the pregnancy.
Hyperemesis gravidarum[72]	Prolonged vomiting, dehydration, alkalosis, and weight loss in early pregnancy, often requiring hospitalization to stabilize fluid, electrolyte, and acid–base balance; sometimes associated with liver damage.
Placenta previa[73]	Blockage of the cervical canal by the placenta, preventing birth of the infant before the placenta separates from the uterus. Requires birth by cesarean section.
Preeclampsia[74] **(toxemia of pregnancy) and eclampsia**	Rapid onset of hypertension and edema, with swelling especially of the face and hands; proteinuria and reduced glomerular filtration rate; increased blood clotting; sometimes with headaches, visual disturbances, and small cerebral infarctions. Seen in about 4% of pregnancies, especially in the third trimester of women pregnant for the first time. Can progress to *eclampsia,* with seizures and widespread vascular spasms that are sometimes fatal to the mother, fetus, or both. Eclampsia usually occurs shortly before or after childbirth.
Spontaneous abortion	Occurs in 10% to 15% of pregnancies, usually because of fetal deformities or chromosomal abnormalities incompatible with survival, but may also result from maternal abnormalities, infectious disease, and drug abuse.
Other Reproductive Disorders	
Amenorrhea[75]	Absence of menstruation. Normal in pregnancy, lactation, early adolescence, and perimenopausal years, but can also result from gonadotropin hyposecretion, genetic disorders, CNS disorders, or excessively low body fat.
Dysmenorrhea[76]	Painful menstruation in the absence of pelvic disease, caused by excessive endometrial prostaglandin secretion. Prostaglandins stimulate painful contractions of myometrium and uterine blood vessels. Usually begins around age 15 or 16 and affects up to 75% of women from 15 to 25 years old. May accompany leiomyoma or endometriosis.
Endometriosis	Growth of endometrial tissue in any site other than the uterus, including the uterine tubes, ovaries, urinary bladder, vagina, pelvic cavity, small or large intestine, or even the lungs or pleural cavity. May cause dysmenorrhea, abnormal vaginal bleeding, and infertility.
Leiomyomas[77] **(uterine fibroids)**	Benign tumors of uterine smooth muscle. Usually small and asymptomatic, but can become very large and may cause abnormal uterine bleeding, heavy menstruation, or dysmenorrhea.
Pelvic inflammatory disease (PID)	Acute, painful inflammation due to infection of the uterus, uterine tubes, or ovaries, usually with the organisms of sexually transmitted diseases. Causes abdominopelvic pain, pain on urination, and irregular bleeding.

Disorders Described Elsewhere

Breast cancer 732	Cervical cancer 733	Sexually transmitted diseases 732

Bacterial STDs include gonorrhea and syphilis, caused by the bacteria *Neisseria gonorrhoeae* and *Treponema pallidum,* respectively. Cases of these two diseases are outnumbered, however, by chlamydia (caused by *Chlamydia trachomatis*), which affects 3 to 5 million people per year in the United States.

Before You Go On

Answer the following questions to test your understanding of the preceding section:

15. What are mesonephric and paramesonephric ducts? What factors determine which one develops and which one regresses in the fetus?
16. What male structures develop from the genital tubercle and labioscrotal folds?
17. Define the *gubernaculum* and describe its function.
18. Which of the following occur in both men and women—thelarche, pubarche, climacteric, menopause, breast cancer, or cryptorchidism? Explain.

---

[70] *ab* = away; *rupt* = to tear; *placentae* = of the placenta
[71] *ec* = out of; *top* = place
[72] *hyper* = excessive; *emesis* = vomiting; *gravida* = pregnant woman
[73] *pre* = before; *via* = the way (obstructing the way)
[74] *ec* = forth; *lampsia* = shining
[75] *a* = without; *meno* = monthly; *rrhea* = flow
[76] *dys* = painful, abnormal; *meno* = monthly; *rrhea* = flow
[77] *leio* = smooth; *myo* = muscle; *oma* = tumor

STUDY GUIDE

Assess Your Learning Outcomes

To test your knowledge, discuss the following topics with a study partner or in writing, ideally from memory.

26.1 Sexual Reproduction (p. 704)

1. The definition of *sexual reproduction,* and how this relates to the necessity of gametes and a zygote
2. The division of roles between two types of gametes; how this relates to the biological definitons of *male* and *female;* and the chromosomal distinction between the sexes
3. How the sexes are distinguished by their chromosomes
4. The distinctions between primary sex organs, secondary sex organs, secondary sex characteristics, and internal and external genitalia, and examples of all of these

26.2 The Male Reproductive System (p. 705)

1. The surface anatomy and contents of the scrotum
2. The spermatic cord, its contents, and its relationship to the inguinal canal and the internal and external inguinal rings
3. The relevance of temperature to sperm development and the three mechanisms for maintaining proper testicular temperature
4. The surface anatomy of the testis; its internal division into lobules and seminiferous tubules; the rete testis; and the interstitial cells, their function, and their relationship with the seminiferous tubules
5. The epithelium of a seminiferous tubule; its cell types; and the functions of those cells
6. The structure and purpose of the blood–testis barrier
7. The route of blood flow from aorta to testicular artery, testis, pampiniform plexus, testicular vein, and ultimately the inferior vena cava (including the right–left difference in routes)
8. The anatomical course and functions of testicular lymphatics and nerves
9. The basic events of spermatogenesis; the necessity of meiosis for sexual reproduction; and the cellular stages of spermatogenesis and their relationship to meiosis I, meiosis II, and spermiogenesis
10. The structure of a spermatozoon and the function of each of its parts
11. The series of ducts that convey sperm from the testis to the urethra; the anatomy of each; and the three regions of the male urethra
12. The three sets of male accessory glands associated with the spermatic ducts; their anatomy; and the contribution of each to semen production and intercourse
13. The volume of semen and quantity of sperm in a typical ejaculate; the chemical components of the semen; and the functions and glandular sources of each
14. The anatomical regions and dimensions of the penis, and its relationships with adjacent organs
15. The three erectile tissues and other internal structures of the penis; the structure of an individual erectile tissue and how it relates to copulatory function
16. The arterial blood supply and venous drainage of the penis, and differences in blood flow between the flaccid and erect states
17. The nerve supply to the penis and how its sympathetic, parasympathetic, and sensory nerves relate to sexual function

26.3 The Female Reproductive System (p. 715)

1. The structure of the ovary
2. The supportive ligaments of the ovary; their relationship to the arterial blood supply to the ovary; and the venous and lymphatic drainage of the ovary
3. The principal events of oogenesis and how it differs from spermatogenesis
4. The cellular stages of oogenesis; how they relate to the stages of meiosis; and how they relate to ovulation and fertilization
5. The types of ovarian follicles; how they relate to oogenesis and ovulation; and the fate of a follicle after it ovulates
6. Details of the structure of a mature ovarian follicle
7. The gross anatomy and histology of the uterine tubes
8. The gross anatomy of the uterus; the names and histological characteristics of the three layers of the uterine wall
9. The supportive ligaments of the uterus; their relationship to the peritoneal pouches of the pelvic cavity; and their relationship to the blood vessels that supply the uterus
10. The histological changes that occur in the endometrium over the course of the menstrual cycle
11. The gross anatomy and histology of the vagina
12. The anatomy of the vulva, including the mons pubis; labia majora and minora; vestibule; clitoris and prepuce; vestibular bulbs; greater and lesser vestibular glands; and paraurethral glands
13. The gross anatomy of the breast; the distinction between breasts and mammary glands; and the structure of the mammary gland (particularly the acini), secretory and myoepithelial cells, and duct system

26.4 Developmental and Clinical Perspectives (p. 727)

1. Early features of genital development that are identical in males and females; the meaning of *homologous* structures, and examples; and the age at which the sexes become distinguishable
2. The mesonephric and paramesonephric ducts and the fate of each
3. How the sex chromosomes, *SRY* gene, and hormones interact to determine whether an individual develops male or female anatomy
4. Which male and female structures develop from the genital tubercle, urogenital folds, and labioscrotal folds
5. The descent of the gonads; the role of the gubernaculum; and how the descent differs in males and females
6. How puberty is hormonally induced; the distinction between puberty and adolescence; similarities and differences between boys and girls in the events of puberty; and the meaning of *thelarche, pubarche,* and *menarche* in girls
7. The hormonal causes of male and female climacteric, and the signs and symptoms of climacteric in each sex
8. The distinction between menopause and female climacteric, and why the exact time of menopause cannot be determined
9. Types of cancer that occur in the male reproductive organs, and other common male reproductive disorders
10. Types of cancer that occur in the female reproductive organs; common disorders of pregnancy; and other common female reproductive disorders
11. The most common viral and bacterial sexually transmitted diseases

Testing Your Recall

1. The ductus deferens develops from _____ of the embryo.
    a. the mesonephric duct
    b. the paramesonephric duct
    c. the phallus
    d. the labioscrotal folds
    e. the urogenital folds
2. Descent of the testes includes their passage through
    a. the inguinal canal.
    b. the spermatic cord.
    c. the ductus deferens.
    d. the seminiferous tubule.
    e. the ampulla.
3. Four spermatozoa arise from each
    a. primordial germ cell.
    b. type A spermatogonium.
    c. type B spermatogonium.
    d. secondary spermatocyte.
    e. spermatid.
4. Prior to ejaculation, sperm are stored primarily in
    a. the seminiferous tubules.
    b. the epididymis.
    c. the seminal vesicles.
    d. the bulb of the penis.
    e. the ejaculatory ducts.
5. Testosterone is produced primarily by
    a. the seminiferous tubules.
    b. the sustentacular cells.
    c. the interstitial cells.
    d. the seminal vesicles.
    e. the prostate gland.
6. The fluid-filled central cavity of a mature ovarian follicle is
    a. the antrum.
    b. the zona pellucida.
    c. the theca folliculi.
    d. the granulosa.
    e. the stigma.
7. The tissue lost in menstruation is
    a. the perimetrium.
    b. the myometrium.
    c. the basal layer.
    d. the functional layer.
    e. the stratum corneum.
8. The male scrotum is homologous to the female
    a. ovaries.
    b. vagina.
    c. labia majora.
    d. vestibular bulbs.
    e. clitoris.
9. The narrowest part of the uterus is
    a. the fundus.
    b. the infundibulum.
    c. the body.
    d. the ampulla.
    e. the cervix.
10. The vesicouterine pouch is a space in the peritoneal cavity between the uterus and
    a. the fornices.
    b. the uterine tube.
    c. the sacrum.
    d. the urinary bladder.
    e. the rectum.
11. Under the influence of androgens, the embryonic _____ duct develops into the male reproductive tract.
12. Spermatozoa obtain energy for locomotion from _____ in the semen.
13. The _____, a network of veins in the spermatic cord, helps keep the testes cooler than the core body temperature.
14. Each egg cell develops in its own fluid-filled space called a/an _____.
15. The mucosa of the uterus is called the _____.
16. Over half of the semen consists of secretions from a pair of glands called the _____.
17. The blood–testis barrier is formed by tight junctions between the _____ cells.
18. The female paraurethral glands arise from the same embryonic structure as the male _____.
19. A yellowish structure called the _____ secretes progesterone during the secretory phase of the menstrual cycle.
20. The funnel-like distal end of the uterine tube is called the _____ and has feathery processes called _____.

Answers in appendix A

Building Your Medical Vocabulary

State a medical meaning of each of the following word elements, and give a term in which it is used.

1. gameto-
2. gono-
3. hystero-
4. vagin-
5. alb-
6. ov-
7. oo-
8. -phor
9. lute-
10. metri-

Answers in appendix A

True or False

Determine which five of the following statements are false, and briefly explain why.

1. After ovulation, a follicle begins to move down the uterine tube to the uterus.
2. The uterine tubes develop from the embryonic mesonephric ducts.
3. Thelarche normally precedes menarche in female puberty.
4. The follicle that ovulates is called the primary follicle.
5. Sperm cannot develop at the core body temperature.
6. A high androgen level makes a fetus develop a male reproductive system, and a high estrogen level makes it develop a female reproductive system.
7. Most ovarian follicles degenerate before a girl reaches puberty.
8. The pampiniform plexus serves to keep the testes warm.
9. Prior to ejaculation, sperm are stored mainly in the epididymis.
10. The thickest layer of the uterine wall is the myometrium.

Answers in appendix A

Testing Your Comprehension

1. The most common method of male sterilization is vasectomy, in which the ductus (vas) deferens is tied, cut, or both. What is the equivalent method of female sterilization? Why are the difficulty and risks of that procedure greater than for a vasectomy?
2. *Uterus bicornis* (*bicorn* = two horns) is a rare condition in which a woman has two separate uteri, each opening by its own cervix into the vagina. What abnormal event of embryonic development do you think could account for this?
3. Suppose the corpus spongiosum became as engorged with blood as the corpora cavernosa do during erection of the penis. What problem would this create for sexual function? In light of this, why is it beneficial that the corpus spongiosum is not enclosed in a tunica albuginea?
4. What male structure(s) do you think is or are homologous to the vestibular bulbs of the female? Explain your reasoning.
5. An oocyte lives for only 24 hours after ovulation if it is not fertilized. The trip down the uterine tube, from infundibulum to uterus, takes about 72 hours. In light of this, where do you think fertilization normally occurs?

APPENDIX A

Answers to Study Guide Questions

Answers are provided here for the end-of-chapter Testing Your Recall, Building Your Medical Vocabulary, and True or False questions, and questions in the figure legends. Answers to Apply What You Know questions are available on the Saladin website at www.mhhe.com/saladinha5.

Chapter 1

Testing Your Recall

1. a
2. b
3. c
4. e
5. a
6. a
7. d
8. e
9. b
10. d
11. dissection
12. supinated
13. parietal
14. retroperitoneal
15. functional morphology
16. palpation
17. computed tomography
18. organ
19. ipsilateral, contralateral
20. cubital, popliteal

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. apart—anatomy
2. recording process—sonography
3. shape—morphology
4. below—hypogastric
5. process—supination
6. small—organelle
7. touch, feel—palpation
8. before, in front—antebrachial
9. within—intraperitoneal
10. listen—auscultation

True or False

(These items are false for the reasons given; all others are true.)

3. Auscultation is listening to sounds made by the body.
4. Radiology is concerned with all methods of medical imaging.
6. Nearly every cell contains many organelles.
7. The diaphragm is inferior to the lungs.
9. There is nothing but a thin film of fluid between the parietal and visceral pleurae.

Figure Legend Questions

1.3 MRI is better than X-ray at showing soft tissues such as the eye and its muscles and the brain tissue. X-ray is better than PET at showing hard, dense structures such as the bones and teeth.

1.4 Radiography and CT use X-rays, which have the potential to cause mutations and birth defects; sonography uses no harmful radiation.

1.8 Midsagittal or median

1.15 No, the urinary bladder lies outside the peritoneal cavity; the peritoneum passes over its superior surface.

Chapter 2

Testing Your Recall

1. e
2. d
3. b
4. b
5. e
6. a
7. d
8. a
9. d
10. d
11. micrometers (μm)
12. receptor
13. gates
14. mitochondria
15. tight junctions
16. squamous
17. mitochondrion, nucleus
18. peroxisomes, smooth ER
19. cell-adhesion molecules
20. phagocytosis

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. cell—cytology
2. flat, scale—squamous
3. shape—fusiform
4. many—polygonal
5. loving, attracted to—hydrophilic
6. eat—phagocytosis
7. into, within—endoplasmic
8. sugar—glycocalyx
9. color—chromosome
10. beyond, next in a series—metaphase

True or False

(These items are false for the reasons given; all others are true.)

2. Proteins are only 1% to 10% of the molecules of a plasma membrane.
6. Movement down a gradient does not employ ATP.
7. Osmosis is a case of simple diffusion.
9. Desmosomes provide no channels from one cell to another.
10. The nucleolus is not an organelle.

Figure Legend Questions

2.2 The cells are thinner in the center than around the rim, so more light shines through.

2.8 The region that projects into the cytoplasm

2.13 Microvilli are much smaller than cilia, they lack axonemes, and they have a supportive core of actin.

2.15 Gap junctions

2.16 Microfilaments have a supportive role in microvilli, and microtubules form the axonemes of cilia and flagella.

Chapter 3

Testing Your Recall

1. a
2. b
3. c
4. e
5. d
6. a
7. b
8. e
9. b
10. b
11. apoptosis (programmed cell death)
12. mesothelium
13. lacunae
14. fibers
15. collagen
16. gangrene
17. basement membrane
18. matrix
19. holocrine
20. simple

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. tissue—histology
2. between—intercellular
3. plate—lamella
4. form, give rise to—fibroblast
5. network—reticulocyte
6. cartilage—chondrocyte
7. around—periosteum
8. nipple, female—epithelium
9. out of—exocytosis
10. dead, death—necrosis

True or False

(These items are false for the reasons given; all others are true.)

2. The noncellular components include ground substance and fibers.
5. The tongue epithelium is nonkeratinized.
6. Macrophages develop from monocytes.
8. Brown fat produces no ATP.
9. In metaplasia, one mature tissue type transforms into another.

Figure Legend Questions

3.1 The microtubule could be drawn roughly as two parallel bars, like the upper right diagram of figure 3.2, but if the globular tubulin molecules were taken into account (see fig. 2.17), each bar could be shown as a linear chain of spherical tubulin molecules.

3.13 Dense regular connective tissue

3.29 Exocytosis

3.31 The holocrine gland (c), because its cells are destroyed in the process of becoming the secretion and they need continual replacement.

3.32 The esophagus, stomach, and intestines, for example, are lined with mucous membranes; the outer surfaces of the liver, spleen, stomach, and intestines are covered with serous membranes.

Chapter 4

Testing Your Recall

1. b
2. b
3. d
4. c
5. a
6. e
7. c
8. a
9. e
10. d
11. teratogens
12. nondisjunction
13. neural groove or neural tube
14. implantation
15. chorionic villi
16. acrosome
17. uterine tube
18. somites
19. polyspermy
20. embryo

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. half—haploid
2. sex cell—gametogenesis
3. union—zygote
4. nourish—trophoblast
5. head—hydrocephalus
6. female—gynecomastia
7. production of—embryogenesis
8. together, united—syncytiotrophoblast
9. middle—mesoderm
10. monster—teratogen

True or False

(These items are false for the reasons given; all others are true.)

1. Sperm must undergo capacitation first.
2. Fertilization occurs in the uterine tube.
3. Several sperm must digest a path for the one that fertilizes the egg.
8. Oogenesis produces one large oocyte and small discarded polar bodies.
10. The energy comes from the midpiece mitochondria.

Figure Legend Questions

4.2 An egg will have died by the time it reaches the uterus if it was not already fertilized.

4.9 At about 8 weeks

4.10 There are two arteries and one vein. Blood in the vein is more oxygenated than blood in the arteries.

4.12 If an XX egg was fertilized by a Y-bearing sperm, the result would be Klinefelter syndrome (XXY). If the egg with no sex chromosome was fertilized by a Y-bearing sperm, the resulting YO zygote would soon die for lack of critical genes found only on X chromosomes; no birth would result.

4.13 It was a female, as we can tell from the two X chromosomes at the lower right.

Chapter 5

Testing Your Recall

1. d
2. c
3. d
4. b
5. a
6. e
7. c
8. a
9. a
10. d
11. dermato-, cutane-
12. piloerector (arrector pili)
13. keratin, collagen
14. cyanosis
15. dermal papillae
16. earwax
17. sebaceous glands
18. cuticle
19. dermal papilla
20. second-degree

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. skin—dermatology
2. above, upon—epidermal
3. below—subcutaneous
4. nipple—papillary
5. black—melanoma
6. blue—cyanosis
7. clear—stratum lucidum
8. little—papilla
9. hair—piloerector
10. cancer—carcinoma

True or False

(These items are false for the reasons given; all others are true.)

3. The dermis is mainly collagen.
4. Vitamin D synthesis begins in the keratinocytes and is completed in the liver and kidneys.
7. The hypodermis is not part of the skin.
8. People of all colors have similar densities of melanocytes.
9. Melanoma is the most deadly but least common form of skin cancer.

Figure Legend Questions

5.5 Keratinocytes

5.7 The cuticle

5.10 Terminal hair; they are connected to the follicles of the coarse hairs of the pubic, axillary, and beard regions.

5.13 Asymmetry (A), border irregularity (B), and color (C). The photograph does not provide enough information to judge diameter (D).

Chapter 6

Testing Your Recall

1. e
2. a
3. d
4. c
5. d
6. c
7. d
8. e
9. b
10. d
11. hydroxyapatite
12. canaliculi
13. appositional
14. osteons
15. parathyroid
16. articular cartilage
17. osteoblasts
18. osteoporosis
19. metaphysis
20. intramembranous ossification

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. bone—periosteum
2. double—diploe
3. space, cavity—lacuna
4. breakdown, destroyer—osteoclast
5. medical condition—osteoporosis
6. across—diaphysis
7. study of—osteology
8. joint—articular
9. little—canaliculus
10. like, resembling—osteoid

True or False

(These items are false for the reasons given; all others are true.)

3. The most common bone disorder is osteoporosis.
4. The growth zone is the epiphyseal plate.
5. Osteoclasts develop from stem cells related to monocytes.
7. The protein of the bone matrix is collagen.
9. Only the red bone marrow is hemopoietic.

Figure Legend Questions

6.1 The wide epiphyses provide expanded surface area for bone articulation and for tendon and ligament attachments. Joints would be very unstable if they were as narrow as the diaphysis.

6.4 Spongy bone

6.6 The crest of the hip and the sternum

6.7 The parietal and frontal bones (answers may vary)

6.9 The humerus, radius, ulna, femur, tibia, and fibula (any two)

6.11 The zones of cell proliferation and hypertrophy (2 and 3)

Chapter 7

Testing Your Recall

1. b
2. e
3. a
4. d
5. a
6. b
7. a
8. a
9. c
10. c
11. fontanels
12. temporal
13. sutures
14. sphenoid
15. anulus fibrosus
16. dens
17. auricular
18. false, floating
19. costal cartilages
20. xiphoid process

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. skull—cranial
2. time—temporal bone
3. breast—mastoid process
4. stone—petrous
5. layer—lamina
6. wing—pterygoid
7. crest, ridge—crista galli
8. tears—lacrimal bone
9. rib—costal cartilage
10. foot—pedicle

True or False

(These items are false for the reasons given; all others are true.)

1. The vertebral bodies are derived from the sclerotomes.
2. Adults have fewer bones than children do.
4. The zygomatic processes of the temporal bone and maxilla also contribute to the arch.
5. The dura mater lies loosely against most of the cranium.
10. Lumbar vertebrae have transverse processes, but not transverse costal facets.

Figure Legend Questions

7.7 They produce turbulence in the airflow and support the mucous membranes that warm, cleanse, and humidify inhaled air.

7.8 The anterior portion of the skull would be much heavier and the skull would tend to tip forward. More effort would be required to oppose this.

7.16 The hyoid is a delicate, easily broken bone, and its location subjects it to fracture by a rope, hands, or other means of strangulation applied around the neck.

7.24 The dens would rip through and severely damage the spinal cord.

7.30 Most joints of an infant are still cartilaginous and therefore not very resistant to stress.

7.36 The lumbar vertebrae and discs must bear more weight from the body and from heavy objects that one lifts, and are therefore the most likely ones to herniate. The cervical vertebrae and discs bear very little weight.

Chapter 8

Testing Your Recall

1. a
2. e
3. c
4. b
5. a
6. d
7. c
8. b
9. e
10. b
11. pollex, hallux
12. scapula
13. 56
14. epicondyles
15. hamate
16. interpubic disc
17. crural
18. styloid
19. trochanters
20. medial longitudinal

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. chest—pectoralis
2. peak, apex, extremity—acromion
3. little—ossicle
4. above—supraspinous
5. wrist—carpal
6. head—capitulum
7. little—acetabulum
8. beyond, next in a series—metacarpal
9. ear—auricular
10. ankle—tarsal

True or False

(These items are false for the reasons given; all others are true.)

2. Each hand and foot has 14 phalanges.
3. The upper limb is attached at the glenohumeral joint.
5. The arm contains only the humerus, but the leg contains the tibia and fibula.
7. The most frequently broken bone is the clavicle.
10. That opening is the pelvic inlet.

Figure Legend Questions

8.1 See Deeper Insight 8.1 for the reasons.

8.2 It is attached at the glenoid cavity to the humerus and attached at the acromion to the clavicle.

8.5 In this adult hand, the epiphyseal plates of childhood have closed and there are no gaps between the epiphyses and diaphyses.

8.6 During birth, the fetal head must pass through the narrow pelvic inlet and outlet. It could not do so if the cranial bones were immovably fused; the infant must be born before the bones fuse at the sutures and fontanels.

8.10 Four: the head, the medial condyle, the lateral condyle, and the patellar surface

8.14 The sesamoid bone. The others are present at birth, but sesamoid bones develop later in response to stresses such as walking.

Chapter 9

Testing Your Recall

1. c
2. b
3. a
4. e
5. c
6. c
7. c
8. d
9. b
10. b
11. synovial fluid
12. bursa
13. pivot
14. kinesiology
15. gomphosis
16. serrate
17. extension
18. range of motion
19. rheumatologist
20. menisci

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. joint—arthritis
2. back—reposition
3. together—symphysis
4. both—amphiarthrosis
5. growth—diaphysis
6. around—circumduction
7. away—abduction
8. toward—adduction
9. to lead—abduction
10. motion—kinesiology

True or False

(These items are false for the reasons given; all others are true.)

1. Osteoarthritis is much more common than rheumatoid arthritis.
2. A doctor who treats arthritis is a rheumatologist.
3. Synovial joints are diarthroses.
5. This action hyperextends the shoulder; the elbow cannot be hyperextended.
9. Synovial fluid fills the bursae but is secreted by the synovial membrane of the joint capsule.

Figure Legend Questions

9.1 A gomphosis is a joint between a bone and a tooth; teeth are not bones.

9.3 The interpubic disc is only the fibrocartilage pad; the pubic symphysis is the disc plus the adjacent areas of the pubic bones.

9.4 Interphalangeal joints are not subject to routine compression.

9.14 The atlas

9.17 Variable answers; for example, changing direction when walking or running, walking on a rocky trail, or inspecting the bottom of one's foot for a thorn

9.19 The glenoid labrum

Chapter 10

Testing Your Recall

1. e
2. c
3. c
4. a
5. c
6. e
7. e
8. c
9. d
10. b
11. synaptic vesicles
12. neuromuscular junction or motor end plate
13. terminal cisternae
14. myosin
15. fasciae
16. myoglobin
17. Z discs
18. sphincter
19. myoblasts
20. peristalsis

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. muscle—myofibril
2. band—fascicle
3. spindle—fusiform
4. flesh, muscle—sarcolemma
5. bad, abnormal, difficult—dystrophy
6. muscle—endomysium
7. against—antagonist
8. work, action—synergist
9. segment—sarcomere
10. feather—bipennate

True or False

(These items are false for the reasons given; all others are true.)

4. The expression *slow oxidative* refers to skeletal muscle fibers.
5. One motor neuron can supply from a few to a thousand muscle fibers.
6. Calcium binds to troponin, not to myosin.
9. The blood vessels become wavy when the muscle shortens.
10. Muscle growth involves an increase in muscle fiber thickness, not in their number.

Figure Legend Questions

10.1 Unlike the other muscle types, the skeletal muscle here exhibits long parallel fibers with no branching or tapering, and many nuclei in each fiber. Its striations also distinguish it from smooth muscle.

10.3 Strength depends on both fascicle arrangement and muscle diameter. A large parallel muscle could be stronger than a small pennate muscle.

10.4 The biceps brachii and distal end of the triceps brachii (both heads) exhibit indirect attachments. The brachialis and lateral head of the triceps brachii exhibit direct attachments.

10.5 It is a first-class lever because the fulcrum lies between the effort and resistance.

10.8 The function of the T tubule is to stimulate the opening of calcium gates in the terminal cisternae.

Chapter 11

Testing Your Recall

1. b
2. c
3. a
4. c
5. e
6. e
7. a
8. a
9. c
10. d
11. erector spinae
12. bulbospongiosus
13. levator palpebrae superioris
14. hypoglossal
15. digastric
16. urogenital triangle
17. linea alba
18. larynx
19. sternocleidomastoid
20. trapezius

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. triangular—deltoid
2. raise—levator labii superioris
3. eye—orbicularis oculi
4. away, apart—aponeurosis
5. mouth—orbicularis oris
6. finger, toe—flexor digitorum
7. lip—depressor labii inferioris
8. same—ipsilateral
9. tongue—hypoglossal
10. two—digastric

True or False

(These items are false for the reasons given; all others are true.)

1. The sternocleidomastoid tilts the head forward and medially.
5. Normal exhalation is passive and does not employ the internal intercostals.
6. The floor of the mouth is formed by the mylohyoid muscle.
7. The scalenes are deep to the trapezius.
10. Only cranial nerves III, V, VII, XI, and XII innervate head and neck muscles.

Figure Legend Questions

11.4 Zygomaticus major, levator palpebrae superioris, orbicularis oris (answers may vary)

11.6 If the mandible was already at its farthest right lateral excursion, the right medial pterygoid would help draw it back to the zero position or midline (medial excursion), or it could contract still more to cause left lateral excursion.

11.12 The pectoralis minor, subclavius, and the upper intercostal and serratus anterior muscles

Chapter 12

Testing Your Recall

1. c
2. e
3. b
4. d
5. d
6. e
7. b
8. a
9. d
10. a
11. deltoid
12. great toe
13. teres, quadratus
14. hamstring
15. retinacula
16. adductor pollicis
17. quadriceps femoris
18. coracobrachialis
19. gracilis
20. iliacus, psoas major

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. scalloped—serratus anterior
2. the back—latissimus dorsi
3. head—biceps
4. below—infraspinous
5. round—pronator teres
6. deep—flexor digitorum profundus
7. bone—interosseous
8. hip—iliacus
9. broad—latissimus dorsi
10. largest—gluteus maximus

True or False

(These items are false for the reasons given; all others are true.)

1. The plantaris muscle inserts on the foot by a tendon of its own.
5. The interosseous muscles are pennate.
7. The psoas major and rectus femoris are synergists in flexing the hip.
8. Hamstring injuries usually result from rapid extension of the knee, not flexion.
10. These muscles are on opposite sides of the tibia and act as antagonists.

Figure Legend Questions

12.3 The deltoid

12.6 *Teres* indicates that muscle's rounded, cordlike shape; *quadratus* indicates that muscle's angular, four-sided shape.

12.7 Those two muscles are found in the distal half of the forearm, whereas this section represents the more proximal muscles.

12.12 Lifting the body to the next higher step when climbing stairs; the backswing of the lower limb when walking or running (answers may vary)

12.16 The soleus

Atlas

Muscle Test (fig. A.25)

1. f
2. b
3. k
4. p
5. h
6. y
7. z
8. w
9. c
10. a
11. x
12. m
13. n
14. e
15. g
16. v
17. f
18. c
19. x
20. w
21. k
22. d
23. f
24. b
25. a
26. u
27. j
28. i
29. g
30. q

Figure Legend Questions

A.1 The orbicularis oris; the trapezius

A.5 Lungs, heart, thymus, liver, stomach, spleen, kidneys

A.8 The sternocleidomastoids

A.11 Posterior

A.13 Subcutaneous fat (adipose tissue)

A.18 Four

A.19 In part (a), at the base of the first metacarpal bone, between the two leaders from the "Flexion lines" label

A.20 Deep to the rectus femoris

A.21 The fibula

A.24 There is no such bone; the great toe has only two phalanges, proximal and distal.

Chapter 13

Testing Your Recall

1. e
2. e
3. d
4. a
5. e
6. d
7. a
8. d
9. a
10. c
11. afferent
12. reverberating
13. anencephaly
14. dendrites
15. oligodendrocytes
16. axosomatic
17. peripheral nervous system
18. neurilemma, endoneurium
19. ganglia
20. postsynaptic

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. pertaining to—anaxonic
2. body—axosomatic
3. nerve—neurosoma
4. lipid—lipofuscin
5. tree, branch—axodendritic
6. little—dendrite
7. false—pseudounipolar
8. few—oligodendrocyte
9. carry—afferent
10. hard—multiple sclerosis

True or False

(These items are false for the reasons given; all others are true.)

4. Sensory (afferent) neurons connect sense organs to the CNS.
6. The myelin sheath is deep to the neurilemma.
7. Nodes of Ranvier also exist in the CNS.
8. Interneurons are contained entirely within the CNS.
9. Unipolar neurons have an axon and produce action potentials.

Figure Legend Questions

13.1 The PNS, because it is more exposed to trauma than the CNS. The CNS is protected by the cranial and vertebral bones.

13.3 *Afferent* is derived from *af (ad),* meaning "toward," and *fer,* meaning "to carry." Afferent neurons carry signals toward the CNS. *Efferent* is derived from *ef (ex),* meaning "out." Efferent neurons carry signals out of the CNS.

13.4 The presence of multiple dendrites

13.8 Unmyelinated fibers conduct signals relatively slowly, but they occupy less space.

13.9 Axosomatic

Chapter 14

Testing Your Recall

1. e
2. c
3. d
4. d
5. e
6. c
7. c
8. a
9. e
10. b
11. ganglia
12. rami
13. spinocerebellar
14. sacral
15. central pattern generators
16. phrenic
17. decussation
18. proprioception
19. posterior root
20. tibial, common fibular

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. tail—caudal
2. opposite, against—contralateral
3. side—anterolateral
4. of one's own—proprioceptor
5. slender—gracile fasciculus
6. spinal cord—myelin

7. without—amyotrophic
8. inflammation—poliomyelitis
9. diaphragm—phrenic
10. cut, section—dermatome

True or False

(These items are false for the reasons given; all others are true.)

1. The gracile fasciculus is a sensory (ascending) tract.
4. All spinal nerves are mixed nerves.
5. The dura mater is set off from the vertebral bone by the epidural space.
8. Dermatomes overlap each other by as much as 50%.
9. Many somatic reflexes involve the brain.

Figure Legend Questions

14.3 It would have to be T4 because the cuneate fasciculus does not exist below level T6.

14.4 Heat and cold stimuli are carried to the opposite side of the spinal cord before ascending the spinothalamic tract to the brain. The phenomenon is called decussation.

14.8 Unipolar (or pseudounipolar)

14.10 It would result in a loss of sensation within the corresponding region on that side of the body.

14.13 Respiratory arrest would occur if both the right and left phrenic nerves were severed; severing only one of them paralyzes half of the diaphragm and severely diminishes ventilation of the ipsilateral lung.

14.19 If the hamstrings contracted, they would promote flexion of the knee and thus oppose the knee-extending patellar tendon reflex.

Chapter 15

Testing Your Recall

1. c
2. d
3. e
4. a
5. e
6. c
7. a
8. d
9. e
10. e
11. corpus callosum
12. ventricles, cerebrospinal
13. arbor vitae
14. hippocampus
15. choroid plexus
16. precentral
17. frontal
18. association cortex
19. categorical
20. Broca area

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. turn, twist—gyrus
2. groove—sulcus
3. brain—cerebrum
4. stalk—peduncle
5. island—insula
6. little—cerebellum
7. new—neocortex
8. four—corpora quadrigemina
9. leaf—folia
10. radiating—corona radiata

True or False

(These items are false for the reasons given; all others are true.)

1. The cerebral hemispheres are separated from each other by the longitudinal fissure
2. Degeneration of the substantia nigra causes Parkinson disease.
5. The choroid plexuses produce only 30% of the CSF.
6. Hearing is a temporal lobe function.
10. The optic nerve carries visual signals, not motor signals.

Figure Legend Questions

15.1 The dura mater

15.7 (To be answered by pointing out or marking structures in the illustration)

15.8 (To be answered by pointing out or marking structures in the illustration)

15.14 Dendrites

15.19 Those with many small muscles

15.21 No; everyone makes extensive use of both hemispheres.

Chapter 16

Testing Your Recall

1. b
2. c
3. e
4. e
5. a
6. e
7. d
8. d
9. c
10. c
11. adrenergic
12. dual innervation
13. autonomic tone
14. vagus
15. enteric
16. neural crest
17. sympathetic
18. preganglionic, postganglionic
19. baroreceptor
20. vasomotor tone

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. rule—autonomic
2. pressure—baroreceptor
3. viscera—splanchnic nerves
4. kidney—renal
5. feeling—sympathetic
6. next to—paravertebral
7. break down, destroy—sympatholytic
8. self—autonomic
9. branch—ramus
10. wall—intramural

True or False

(These items are false for the reasons given; all others are true.)

1. Normally both divisions are active simultaneously.
3. With biofeedback and other methods, some degree of voluntary control is possible.
4. It inhibits digestion.
6. These reflexes can occur, but are less controllable, without involvement of the brain.
7. All parasympathetic fibers are cholinergic.

Figure Legend Questions

16.4 No; as explained in chapter 11, inspiration and expiration are achieved by skeletal muscles, which are not under autonomic control.

16.5 Sympathetic neurons arise from the lateral horn and somatic neurons from the anterior horn of the spinal cord.

16.7 The vagus nerve

16.9 Dilated, because fear activates the sympathetic division, which stimulates the pupillary dilator

Chapter 17

Testing Your Recall

1. a
2. a
3. a
4. d
5. b
6. e
7. d
8. c
9. c
10. a
11. fovea centralis
12. ganglion
13. nociceptor
14. otoliths
15. outer hair cells
16. stapes
17. inferior colliculi
18. taste hairs
19. olfactory bulb
20. referred pain

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. pain—nociceptor
2. without—anosmia
3. thread—filiform
4. ear—otitis media
5. pulley—trochlea
6. pit, depression—fovea centralis
7. pain—analgesic
8. like—foliate
9. drum—tympanic
10. making a new opening—tympanostomy

True or False

(These items are false for the reasons given; all others are true.)

2. Afferent touch fibers end in the spinal cord and medulla oblongata.
4. It consists of the axons of the retinal ganglion cells.
8. Olfactory neurons are directly exposed to the external environment.
9. The tympanic membrane has sensory fibers of the vagus and trigeminal nerves.
10. The posterior chamber, between the iris and lens, is filled with aqueous humor.

Figure Legend Questions

17.3 Postcentral gyrus; parietal lobe

17.5 The basal cell can divide, and one of its daughter cells can become a new taste cell.

17.14 High middle-ear pressure would interfere with inward movements of the tympanic membrane and therefore reduce the transfer of vibrations to the inner ear.

17.16 The macula sacculi is vertically oriented, so up or down movements in an elevator would cause the otolithic membrane to shift up or down across the hair cells and bend their stereocilia.

17.20 Watery eyes; tears would be unable to drain from the eye surface and would spill over the eyelid.

17.21 CN III, the oculomotor nerve. This nerve controls four muscles, whereas the others each control only one. CN III is indispensable to the ability to look up, down, and sideways.

Chapter 18

Testing Your Recall

1. d
2. d
3. a
4. c
5. d
6. d
7. a
8. a
9. b
10. c
11. anterior pituitary
12. supraoptic nucleus
13. leptin
14. natriuretic peptides
15. glucocorticoids
16. anterior pituitary
17. neuroendocrine
18. interstitial
19. zona fasciculata, ACTH
20. enteric hormones

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. secrete, separate—endocrine
2. quick, sharp—oxytocin
3. for, favoring—prolactin
4. nourish—gonadotroph
5. body—corpus luteum
6. shield—thyroid
7. sodium—natriuretic
8. heat—calorigenic
9. milk—lactotrope
10. fear, repulsion—hydrophobic

True or False

(These items are false for the reasons given; all others are true.)

2. The heart, brain, stomach, and kidneys secrete hormones but are not usually thought of as endocrine glands.
4. The pineal gland and thymus shrink with age.
5. The center of the adrenal gland is the adrenal medulla.
8. The pituitary stalk is not a duct.
9. There are two pairs of parathyroids and one pair of gonads.

Figure Legend Questions

18.1 Heart, liver, stomach, placenta (answers may vary)

18.2 The posterior lobe, or neurohypophysis

18.6 To secrete calcitonin

18.9 To secrete digestive enzymes

Chapter 19

Testing Your Recall

1. b
2. c
3. a
4. b
5. e
6. d
7. d
8. c
9. d
10. b
11. hemopoiesis
12. hematocrit
13. macrophages
14. leukopenia
15. serum
16. hemostasis
17. sickle-cell disease
18. polycythemia
19. megakaryocytes
20. erythropoietin

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. blood—hematology
2. white—leukocyte
3. blood condition—anemia
4. precursor—erythroblast
5. red—erythrocyte
6. large—megakaryocyte
7. bone marrow—myeloid leukemia
8. blood clot—thrombosis
9. large—macrophage
10. formation, production—hemopoiesis

True or False

(These items are false for the reasons given; all others are true.)

3. Anemia is the cause, not the result, of low blood oxygen content.
4. Neutrophils are the most actively antibacterial WBCs.
6. Neutrophils are the most abundant WBCs.
9. RBCs live longer than most WBCs.
10. WBC count is elevated in leukemia.

Figure Legend Questions

19.1 Nuclei

19.3 The developing erythrocyte sinks in at this point when its nucleus shrivels and is ejected from the cell.

19.4 To the Fe at the center of the heme group

19.8 It means "marrow" and refers to the fact that this process occurs in the red bone marrow.

19.10 Fibrin

Chapter 20

Testing Your Recall

1. d
2. b
3. a
4. d
5. e
6. e
7. d
8. a
9. b
10. b
11. systole, diastole
12. systemic
13. coronary sulcus
14. Purkinje fibers
15. gap junctions
16. valvular prolapse
17. vagus
18. myocardial infarction
19. endocardium
20. sinus venosus

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. heart—cardiology
2. upon, above—epicardium
3. half—semilunar
4. pertaining to—coronary
5. small—ventricle
6. arising from—myogenic
7. moon—semilunar
8. crown—coronary
9. belly—ventricle
10. band—fascia adherens

True or False

(These items are false for the reasons given; all others are true.)

1. About 20% of the blood returns to the right atrium by way of thebesian veins.
5. The heart does not require nervous stimulation to beat.
7. It is anastomoses of the arteries, not veins, that serve this purpose.
8. The primordial ventricle develops into the left ventricle only.
9. There are no valves at the entrances to the right atrium.

Figure Legend Questions

20.1 Both. The pulmonary circuit delivers blood to the lungs for gas exchange. The systemic circuit delivers blood for nourishment of the pulmonary tissues.
20.2 To the left
20.7 The trabeculae carneae. They are ridges in the chamber wall, not anchors for tendinous cords.
20.9 They prevent the AV valves from prolapsing into the atria when the ventricles contract.
20.13 The right atrium
20.14 The gap junctions

Chapter 21

Testing Your Recall

1. c
2. b
3. a
4. e
5. b
6. b
7. d
8. b
9. b
10. b
11. fenestrated
12. continuous capillaries
13. endothelium
14. common iliac
15. chemoreceptors
16. transcytosis
17. superior vena cava, inferior vena cava
18. carotid sinuses
19. cerebral arterial circle
20. basilic, cephalic

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. vessel—vasodilation
2. added to—adventitia
3. window—fenestrated
4. head—brachiocephalic
5. neck, throat—jugular
6. vessel—angiogenesis
7. belly, abdomen—celiac trunk
8. knee—genicular artery
9. of, belonging to—vasa vasorum
10. bladder—vesical artery

True or False

(These items are false for the reasons given; all others are true.)

2. They receive blood from the celiac trunk.
4. Blood sometimes passes through portal systems (two capillary beds) or anastomoses (bypassing capillaries).
5. It is formed by the union of the two brachiocephalic veins.
7. The tunica media is nourished mainly by capillaries of the vasa vasorum.
9. One or more arteries of the circle are missing in 80% of people.

Figure Legend Questions

21.1 Arteries are subjected to greater blood pressure and must expand and recoil in phase with the heartbeat.
21.6 Endocrine glands, kidneys, small intestine (answers may vary)
21.10 Veins have thinner walls and less elastic tissue, and therefore expand more easily to accommodate a larger volume of blood.
21.12 Arterial anastomoses: the cerebral arterial circle, circumflex humeral arteries, and deep palmar arch. Venous anastomoses: union of the radial veins near the elbow, union of the left and right gastric veins, the dorsal venous arch of the foot joining the great and small saphenous veins. (Many other examples of both can be cited; answers may vary.)
21.25 Like the gonadal arteries, these veins are much shorter when the gonads begin their development high in the abdominal cavity, near the kidneys. The veins grow as the fetal gonads migrate downward.
21.27 Anastomoses allow for continued blood flow through alternate routes when joint movements temporarily compress an artery and shut off its flow.

Chapter 22

Testing Your Recall

1. b
2. c
3. e
4. a
5. c
6. e
7. a
8. e
9. c
10. d
11. pathogen
12. chyle
13. collecting vessels
14. right lymphatic duct, thoracic duct
15. cisterna chyli
16. plasma
17. antigen-presenting cells
18. red bone marrow
19. lymphatic nodules
20. autoimmune

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. producing—pathogen
2. inflammation—lymphadenitis
3. gland—lymphadenitis
4. cutting out—tonsillectomy
5. disease—lymphadenopathy
6. water—lymphatic
7. free—immunodeficiency
8. enlargement—splenomegaly
9. mass, tumor—lymphoma
10. juice—cisterna chyli

True or False

(These items are false for the reasons given; all others are true.)

1. B cells are involved in adaptive immunity only.
4. Helper T cells also play a role in humoral immunity.
7. Both B and T cells populate the lymph nodes.
8. Lymphatic nodules are temporary and have no capsules.
9. Tonsillectomy is now a much less common treatment than it used to be.

Figure Legend Questions

22.3 Gaps between the endothelial cells are much larger in lymphatic capillaries than they are in blood capillaries.
22.5 (1) It prevents the accumulation of excess tissue fluid (edema). (2) It enables immune cells in the lymph nodes to continually monitor the tissue fluids for foreign matter.
22.6 Cancer cells breaking free of a breast tumor enter the lymphatics and often lodge and seed the growth of secondary (metastatic) tumors in these nearby lymph nodes.
22.10 The reticular epithelial cells
22.14 Erythrocytes account for the color of red pulp; lymphocytes and macrophages account for the color of white pulp.

Chapter 23

Testing Your Recall

1. c
2. c
3. a
4. e
5. b
6. e
7. d
8. a
9. c
10. c
11. laryngopharynx
12. bronchial tree
13. alar
14. conchae
15. obstructive
16. dead space
17. thyroid
18. ventral respiratory group
19. hilum
20. alveolar macrophages

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. rough—trachea
2. small cavity—alveolus
3. expansion—atelectasis
4. smoke, carbon dioxide—hypercapnia
5. nose—nasal septum
6. to breathe—inspiration
7. inflammation—emphysema
8. lung—pulmonary

9. windpipe—bronchus
10. air, lung—pneumothorax

True or False

(These items are false for the reasons given; all others are true.)

1. The glottis is at the superior end of the larynx, not the inferior (tracheal) end.
3. The space between the parietal and visceral pleurae contains only a thin film of pleural fluid.
4. Normal expiration is not produced by muscular contraction.
8. The aortic and carotid sinuses monitor blood pressure.
9. The respiratory system begins as a bud arising from the floor of the pharynx.

Figure Legend Questions

23.2 The line should be drawn between the larynx and trachea labels.
23.3 The septal cartilage
23.4 The epiglottic, corniculate, and arytenoid cartilages
23.8 To secrete mucus
23.10 By its lack of cartilage

Chapter 24

Testing Your Recall

1. a
2. b
3. b
4. d
5. e
6. c
7. a
8. a
9. a
10. c
11. enteric nervous system
12. pyloric sphincter
13. parotid
14. hepatic portal system
15. vagus
16. parietal
17. hepatic sinusoids
18. cardiac orifice
19. cementum
20. lingual papillae

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. stomach—gastric
2. intestine—myenteric
3. food—alimentary
4. behind—retroperitoneal
5. cheek—buccal
6. gatekeeper—pylorus
7. fold, crease—ruga
8. letter S—sigmoid colon
9. straight—rectum
10. liver—hepatocyte

True or False

(These items are false for the reasons given; all others are true.)

1. The pancreas is retroperitoneal, but the liver is not.
2. A tooth is composed mainly of dentin.
3. Bile is secreted into bile canaliculi, not into the sinusoids.
7. The greater omentum is not attached to the body wall.
9. The muscularis externa of the stomach has three layers.

Figure Legend Questions

24.6 The premolars and third molars
24.7 The enamel
24.11 The stomach wall has three layers of muscle; the esophagus has two.
24.16 The autonomic nervous system controls the internal anal sphincter, and the somatic nervous system controls the external anal sphincter. This can be deduced from the fact that the internal sphincter is smooth (involuntary) muscle and the external sphincter is skeletal (voluntary) muscle.
24.18 The hepatic portal vein and the right and left hepatic arteries

Chapter 25

Testing Your Recall

1. c
2. d
3. a
4. c
5. e
6. b
7. d
8. b
9. d
10. a
11. urea
12. ureteric bud
13. trigone
14. macula densa
15. podocytes
16. proximal convoluted tubule
17. thin segment
18. detrusor
19. minor calyx
20. arcuate

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. nitrogen—azotemia
2. kidney—nephron
3. little ball—glomerulus
4. stone—lithotripsy
5. foot—podocyte
6. urine—anuria
7. patch—macula densa
8. next to—juxtaglomerular
9. basin—pelvis
10. bladder—cystitis

True or False

(These items are false for the reasons given; all others are true.)

1. The ureters open into the floor of the bladder.
2. ADH is secreted by the posterior lobe of the pituitary gland.
4. A substantial amount of fluid passes through the tight junctions.
6. The glomerulus is not located within the capsular space.
9. The kidneys are normally in the upper abdominal cavity.

Figure Legend Questions

25.1 The kidney itself cannot be palpated, but its position can be inferred by palpating ribs 11 and 12 and relating that to this figure.
25.2 It would have to be moved into the dark peritoneal cavity toward the upper left, where the spleen and colon are shown, anterior to the parietal peritoneum.
25.4 This is an anterior view, because the renal artery and vein lie anterior to the ureter. Compare the posterior view in figure 25.3b.
25.9 The afferent arteriole is larger than the efferent. This gives the glomerulus a large inlet, a small outlet, and consequently a high blood pressure, which is important for the filtration process.
25.11 An enlarged prostate gland compresses the prostatic urethra, the bladder's exit.

Chapter 26

Testing Your Recall

1. a
2. a
3. c
4. b
5. c
6. a
7. d
8. c
9. e
10. d
11. mesonephric
12. fructose
13. pampiniform plexus
14. follicle
15. endometrium
16. seminal vesicles
17. sustentacular
18. prostate gland
19. corpus luteum
20. infundibulum, fimbriae

Building Your Medical Vocabulary

(Answers may vary; these are acceptable examples.)

1. marriage, union—gamete
2. seed—gonorrhea
3. uterus—hysterectomy

4. sheath—vagina
5. white—tunica albuginea
6. egg—ovary
7. egg—oogenesis
8. to carry—cumulus oophorus
9. yellow—corpus luteum
10. uterus—endometrium

True or False

(These items are false for the reasons given; all others are true.)

1. The follicle does not leave the ovary.
2. The uterine tubes develop from paramesonephric ducts.
4. The follicle that ovulates is the mature (graafian) follicle.
6. The female reproductive system develops as a result of a low androgen level.
8. The pampiniform plexus helps to keep the testes cool.

Figure Legend Questions

26.6 After meiosis, the resulting daughter cells will be genetically different from the rest of the body and would be subject to attack by blood-borne antibodies or immune cells if not protected from them.

26.9 If it was confined within a tunica albuginea, engorgement of the corpus spongiosum would probably compress the urethra and block ejaculation.

26.20 The paraurethral glands

26.21 They compress the acinus and expel milk into the lactiferous ducts.

26.24 The word root *vagin* means "sheath," which aptly describes the tunica vaginalis as a sheath or pouch of peritoneum.

APPENDIX B

Lexicon of Biomedical Word Elements

a- no, not, without (atom, agranulocyte)
ab- away (abducens, abduction)
acetabulo- small cup (acetabulum)
acro- tip, extremity, peak (acromion, acromegaly, acrosome)
ad- to, toward, near (adsorption, adrenal)
adeno- gland (lymphadenitis, adenohypophysis, adenoids)
aero- air, oxygen (aerobic, anaerobe)
af- toward (afferent)
ag- together (agglutination)
-al pertaining to (parietal, pharyngeal, temporal)
ala- wing (ala nasi)
albi- white (albicans, linea alba, albino)
algi- pain (analgesic, myalgia)
aliment- nourishment (alimentary, hyperalimentation)
allo- other, different (allele, allopathic)
amphi- both, either (amphiphilic, amphiarthrosis)
an- without (anaerobic, anemic)
ana- **1.** up, build up (anabolic, anaphylaxis). **2.** apart (anaphase, anatomy). **3.** back (anastomosis)
andro- male (androgen, andropause)
angi- vessel (angiogram, angioplasty, hemangioma)
ante- before, in front (antebrachium)
antero- forward (anterior, anterograde)
anti- against (antidiuretic, antibody, antagonist)
apo- from, off, away, above (apocrine, aponeurosis)
arbor- tree (arboreal, arborization)
artic- **1.** joint (articulation). **2.** speech (articulate)
-ary pertaining to (axillary, coronary)
-ase enzyme (polymerase, kinase, amylase)
ast-, astro- star (aster, astrocyte)
-ata, -ate **1.** possessing like (corniculate, cruciate). **2.** plural of -a (stomata, carcinomata)
athero- fat (atheroma, atherosclerosis)
atrio- entryway (atrium, atrioventricular)
auri- ear (auricle, binaural)
auto- self (autonomic, autoimmune)
axi- axis, straight line (axial, axoneme, axon)
baro- pressure (baroreceptor, hyperbaric)
bene- good, well (benign, beneficial)
bi- two (bipedal, biceps, bifid)
bili- bile (biliary, bilirubin)
bio- life, living (biology, biopsy, microbial)
blasto- precursor, bud, producer (fibroblast, osteoblast, blastomere)
brachi- arm (brachium, brachialis, antebrachium)
brady- slow (bradycardia, bradypnea)
bucco- cheek (buccal, buccinator)
burso- purse (bursa, bursitis)
calc- calcium, stone (calcified, calcaneus, hypocalcemia)
callo- thick (callus, callosum)
calori- heat (calorie, calorimetry, calorigenic)
calv-, calvari- bald, skull (calvaria)
calyx cup, vessel, chalice (glycocalyx, renal calyx)
capito- head (capitis, capitate, capitulum)
capni- smoke, carbon dioxide (hypocapnia)
carcino- cancer (carcinogen, carcinoma)
cardi- heart (cardiac, cardiology, pericardium)
carot- **1.** carrot (carotene). **2.** stupor (carotid)
carpo- wrist (carpus, metacarpal)
case- cheese (caseosa, casein)
cata- down, break down (catabolism)
cauda- tail (cauda equina, caudate nucleus)
-cel little (pedicel)
celi- belly, abdomen (celiac)
centri- center, middle (centromere, centriole)
cephalo- head (cephalic, encephalitis)
cervi- neck, narrow part (cervix, cervical)
chiasm- cross, X (optic chiasm)
chole- bile (cholecystokinin, cholelithotripsy)
chondro- **1.** grain (mitochondria). **2.** cartilage, gristle (chondrocyte, perichondrium)
chromo- color (trichromat, chromatin, cytochrome)
chrono- time (chronotropic, chronic)
cili- eyelash (cilium, supraciliary)
circ- about, around (circadian, circumduction)
cis- cut (incision, incisor)
cisterna- reservoir (cisterna chyli)
clast- break down, destroy (osteoclast)
clavi- hammer, club (clavicle, supraclavicular)
-cle little (tubercle, corpuscle)
cleido- clavicle (sternocleidomastoid)
cnemo- lower leg (gastrocnemius)
co- together (coenzyme, cotransport)
collo- **1.** hill (colliculus). **2.** glue (colloid, collagen)
contra- opposite (contralateral)
corni- horn (cornified, corniculate, cornu)
corono- crown (coronary, corona, coronal)
corpo- body (corpus luteum, corpora quadrigemina)
corti- bark, rind (cortex, cortical)
costa- rib (intercostal, subcostal)
coxa- hip (os coxae, coxal)
crani- helmet (cranium, epicranius)
cribri- sieve, strainer (cribriform, area cribrosa)
crino- separate, secrete (holocrine, endocrinology)
crista- crest (crista ampullaris, mitochondrial crista)
crito- to separate (hematocrit)
cruci- cross (cruciate ligament)
-cule, -culus small (canaliculus, trabecula, auricular)
cune- wedge (cuneiform, cuneatus)
cutane-, cuti- skin (subcutaneous, cuticle)
cysto- bladder (cystitis, cholecystectomy)
cyto- cell (cytology, cytokinesis, monocyte)
de- down (defecate, deglutition, dehydration)
demi- half (demifacet, demilune)
den-, denti- tooth (dentition, dens, dental)
dendro- tree, branch (dendrite, oligodendrocyte)
derma-, dermato- skin (ectoderm, dermatology, hypodermic)
desmo- band, bond, ligament (desmosome, syndesmosis)
dia- **1.** across, through, separate (diaphragm, dialysis). **2.** day (circadian)
dis- **1.** apart (dissect, dissociate). **2.** opposite, absence (disinfect, disability)
diure- pass through, urinate (diuretic, diuresis)
dorsi- back (dorsal, dorsum, latissimus dorsi)
duc- to carry (duct, adduction, abducens)
dys- bad, abnormal, painful (dyspnea, dystrophy)
e- out (ejaculate, eversion)
-eal pertaining to (hypophyseal, arboreal)
ec-, ecto- outside, out of, external (ectopic, ectoderm, splenectomy)
ef- out of (efferent, effusion)
-el, -elle small (fontanel, organelle, micelle)
electro- electricity (electrocardiogram, electrolyte)
em- in, within (embolism, embedded)
emesi-, emeti- vomiting (emetic, hyperemesis)
-emia blood condition (anemia, hypoxemia, hypovolemic)
en- in, into (enzyme, parenchyma)
encephalo- brain (encephalitis, telencephalon)
enchym- poured in (mesenchyme, parenchyma)
endo- within, into, internal (endocrine, endocytosis)
entero- gut, intestine (mesentery, myenteric)
epi- upon, above (epidermis, epiphysis, epididymis)
ergo- work, action (allergy, adrenergic)
eryth-, erythro- red (erythema, erythrocyte)
esthesio- sensation, feeling (anesthesia, somesthetic)
eu- good, true, normal, easy (eukaryote, eupnea, aneuploidy)
exo- out (exocytosis, exocrine)
facili- easy (facilitated)
fasci- band, bundle (fascia, fascicle)
fenestr- window (fenestrated, fenestra vestibuli)
fer- to carry (efferent, uriniferous)
ferri- iron (ferritin, transferrin)
fibro- fiber (fibroblast, fibrosis)
fili- thread (myofilament, filiform)
flagello- whip (flagellum)
foli- leaf (folic acid, folia)
-form shape (cuneiform, fusiform)
fove- pit, depression (fovea)
funiculo- little rope, cord (funiculus)
fusi- **1.** spindle (fusiform). **2.** pour out (perfusion)
gamo- marriage, union (monogamy, gamete)
gastro- belly, stomach (digastric, gastrointestinal)
-gen, -genic, -genesis producing, giving rise to (pathogen, carcinogenic, glycogenesis)
genio- chin (geniohyoid, genioglossus)

germi- 1. sprout, bud (germinal, germinativum). **2.** microbe (germicide)
gero- old age (progeria, geriatrics, gerontology)
gesto- 1. to bear, carry (ingest). **2.** pregnancy (gestation, progesterone)
glia- glue (neuroglia, microglia)
globu- ball, sphere (globulin, hemoglobin)
glom- ball (glomerulus)
glosso- tongue (hypoglossal, glossopharyngeal)
glyco- sugar (glycogen, glycolysis, hypoglycemia)
gono- 1. angle, corner (trigone). **2.** seed, sex cell, generation (gonad, oogonium, gonorrhea)
gradi- walk, step (retrograde, gradient)
-gram recording of (sonogram, electrocardiogram)
-graph recording instrument (sonograph, electrocardiograph)
-graphy recording process (sonography, radiography)
gravi- severe, heavy (gravid, myasthenia gravis)
gyro- turn, twist (gyrus)
hallu- great toe (hallux, hallucis)
hemi- half (hemidesmosome, hemisphere, hemiazygos)
-hemia blood condition (polycythemia)
hemo- blood (hemophilia, hemoglobin, hematology)
hetero- different, other, various (heterozygous, heterosexual)
histo- tissue, web (histology, histone)
holo- whole, entire (holistic, holocrine)
homeo- constant, unchanging, uniform (homeostasis, homeothermic)
homo- same, alike (homologous, homozygous)
hyalo- clear, glassy (hyaline, hyaluronic acid)
hydro- water (dehydration, hydrolysis, hydrophobic)
hyper- above, above normal, excessive (hyperkalemia, hypertonic)
hypo- below, below normal, deficient (hypogastric, hyponatremia, hypophysis)
-ia condition (anemia, hypocalcemia, osteomalacia)
-ic pertaining to (isotonic, hemolytic, antigenic)
-icle, -icul small (ossicle, canaliculus, reticular)
ilia- flank, loin (ilium, iliac)
-illa, -illus little (bacillus)
-in protein (trypsin, fibrin, globulin)
infra- below (infraspinous, infrared)
ino- fiber (inotropic, inositol)
insulo- island (insula, insulin)
inter- between (intercellular, intercalated, intervertebral)
intra- within (intracellular, intraocular)
iono- ion (ionotropic, cationic)
ischi- to hold back (ischium, ischemia)
-ism 1. process, state, condition (metabolism, rheumatism). **2.** doctrine, belief, theory (holism, reductionism, naturalism)
iso- same, equal (isometric, isotonic, isomer)
-issimus most, greatest (latissimus, longissimus)
-ite little (dendrite, somite)
-itis inflammation (dermatitis, gingivitis)
jug- to join (conjugated, jugular)
juxta- next to (juxtamedullary, juxtaglomerular)
kali- potassium (hypokalemia)
karyo- seed, nucleus (megakaryocyte, karyotype, eukaryote)
kerato- horn (keratin, keratinocyte)
kine- motion, action (kinetic, kinase, cytokinesis)
labi- lip (labium, levator labii)
lacera- torn, cut (foramen lacerum, laceration)
lacrimo- tear, cry (lacrimal gland, puncta lacrimalia)
lacto- milk (lactose, lactation, prolactin)
lamina- layer (lamina propria, laminar flow)
latero- side (ipsilateral, vastus lateralis)
lati- broad (fascia lata, latissimus dorsi)
-lemma husk (sarcolemma, neurilemma)
lenti- lens (lentiform)
-let small (platelet)
leuko- white (leukocyte, leukemia)
levato- to raise (levator labii, elevation)
ligo- to bind (ligand, ligament)
line- line (linea alba, linea nigra)
litho- stone (otolith, lithotripsy)
-logy study of (histology, physiology, hematology)
lucid- light, clear (stratum lucidum, zona pellucida)
lun- moon, crescent (lunate, lunule, semilunar)
lute- yellow (macula lutea, corpus luteum)
lyso-, **lyto-** split apart, break down (lysosome, hydrolysis, electrolyte, hemolytic)
macro- large (macromolecule, macrophage)
macula- spot (macula lutea, macula sacculi, macula densa)
mali- bad (malignant, malocclusion, malformed)
malle- hammer (malleus, malleolus)
mammo- breast (mammary, Mammalia)
mano- hand (manus, manipulate)
manubri- handle (manubrium)
masto- breast (mastoid, gynecomastia)
medi- middle (medial, mediastinum, intermediate)
medullo- marrow, pith (medulla)
mega- large (megakaryocyte, hepatomegaly)
melano- black (melanin, melanocyte, melancholy)
meno- month (menstruation, menopause)
mento- chin (mental, mentalis)
mero- part, segment (isomer, centromere, merocrine)
meso- in the middle (mesoderm, mesenchyme, mesentery)
meta- beyond, next in a series (metaphase, metacarpal)
metabolo- change (metabolism, metabolite)
-meter measuring device (hemocytometer, spirometer)
metri- 1. length, measure (isometric, emmetropic). **2.** uterus (endometrium)
micro- small (microscopic, microglia)
mito- thread, filament (mitochondria, mitosis)
mono- one (monocyte, monomer, mononucleosis)
morpho- form, shape, structure (morphology, amorphous)
muta- change (mutagen, mutation)
myelo- 1. spinal cord (poliomyelitis, myelin). **2.** bone marrow (myeloid, myelocytic)
myo-, mysi- muscle (myoglobin, myosin, epimysium)
natri- sodium (hyponatremia, natriuretic)
neo- new (neonatal, gluconeogenesis)
nephro- kidney (nephron, hydronephrosis, mesonephros)
neuro- nerve (aponeurosis, neurosoma, neurology)
nucleo- nucleus, kernel (nucleolus, nucleic acid)
oo- egg (oogenesis, oocyte)
ob- 1. life (aerobic, microbe). **2.** against, toward, before (obstetrics, obturator, obstruction)
oculo- eye (oculi, oculomotor)
odonto- tooth (odontoblast, periodontal)
-oid like, resembling (colloid, sigmoid, ameboid)
-ole small (arteriole, bronchiole, nucleolus)
oligo- few, a little, scanty (oligopeptide, oligodendrocyte, oliguria)
-oma tumor, mass (carcinoma, hematoma)
omo- shoulder (omohyoid, acromion)
onycho- nail, claw (hyponychium)
op- vision (optics, myopia, photopic)
-opsy viewing, to see (biopsy, rhodopsin)
or- mouth (oral, orbicularis oris)
orbi- circle (orbicularis, orbit)
organo- tool, instrument (organ, organelle)
ortho- straight (orthopnea, orthodontics, orthopedics)
-ose 1. full of (adipose). **2.** sugar (sucrose, glucose)
-osis 1. process (osmosis, exocytosis). **2.** condition, disease (cyanosis, thrombosis). **3.** increase (leukocytosis)
osmo- push (osmosis, chemiosmotic)
osse-, oste- bone (osseous, osteoporosis)
oto- ear (otolith, otitis, parotid)
-ous 1. full of (nitrogenous, edematous). **2.** pertaining to (mucous, nervous). **3.** like, characterized by (squamous, filamentous)
ovo- egg (ovum, ovary, ovulation)
oxy- 1. oxygen (hypoxia, oxyhemoglobin). **2.** sharp, quick (oxytocin)
palli- pale (pallor, globus pallidus)
palpebro- eyelid (palpebra)
pan- all (pancreas, panhysterectomy)
panni- cloth, rag (pannus, panniculus)
papillo- nipple (papilla, papillary)
par- birth (postpartum, parturition, multiparous)
para- next to (parathyroid, parotid)
parieto- wall (parietal)
patho- 1. disease (pathology, pathogen). **2.** feeling (sympathetic)
pecto- 1. chest (pectoral, pectoralis). **2.** comblike (pectineus)
pedi- 1. foot (bipedal, pedicle). **2.** child (pediatrics)
pelvi- basin (pelvis, pelvic)
-penia deficiency (leukopenia, thrombocytopenia)
penna- feather (unipennate, bipennate)
peri- around (periosteum, peritoneum, periodontal)
perone- fibula (peroneus tertius, peroneal nerve)
phago- eat (phagocytosis, macrophage)
philo- loving, attracted to (hydrophilic, amphiphilic)
phobo- fearing, repelled by (hydrophobic)
phor- to carry, bear (diaphoresis, electrophoresis)
phragm- partition (diaphragm)
phreno- diaphragm (phrenic nerve)
physio- nature, natural cause (physiology, physician, physics)
-physis growth (diaphysis, hypophysis)
pilo- hair (piloerection)
pino- drink, imbibe (pinocytosis)
planto- sole of foot (plantaris, plantar wart)
plasi- growth (hyperplasia)
plasm- shaped, molded (cytoplasm, endoplasmic)
plasti- form (thromboplastin)
platy- flat (platysma)
pnea- breath, breathing (eupnea, dyspnea)
pneumo- air, breath, lung (pneumonia, pneumothorax)
podo- foot (pseudopod, podocyte)
poies- forming (hemopoiesis, erythropoietin)
poly- many, much, excessive (polypeptide, polyuria)
primi- first (primary, primipara, primitive)

pro- 1. before, in front, first (prokaryote, prophase, prostate). **2.** promote, favor (progesterone, prolactin)
pseudo- false (pseudopod)
psycho- mind (psychosis, psychosomatic)
ptero-, pterygo- wing (pterygoid)
-ptosis dropping, falling, sagging (apoptosis, nephroptosis)
puncto- point (puncta)
pyro- fire (pyrogen)
quadri- four (quadriceps, quadratus)
quater- fourth (quaternary)
radiat- radiating (corona radiata)
rami- branch (ramus)
recto- straight (rectus abdominis, rectum)
reno- kidney (renal, renin)
reti- network (reticular, rete testis)
retinac- retainer, bracelet (retinaculum)
retro- behind, backward (retroperitoneal, retrovirus)
rhombo- rhombus (rhomboideus, rhombencephalon)
rubo-, rubro- red (bilirubin, rubrospinal)
rugo- fold, wrinkle (ruga, corrugator)
sacculo- little sac (saccule)
sarco- flesh, muscle (sarcoplasm, sarcomere)
scala- staircase (scala tympani)
sclero- hard, tough (sclera, sclerosis)
scopo- see (microscope, endoscopy)
secto- cut (section, dissection)
semi- half (semilunar)
sepsi- infection (asepsis, septicemia)
-sis process (diapedesis, amniocentesis)
sole- sandal, flatfish (sole, soleus)
soma-, **somato-** body (somatic, somatotropin)
spheno- wedge (sphenoid)
spiro- breathing (inspiration, spirometry)
splanchno- viscera (splanchnic)
spleno- 1. bandage (splenius capitis). **2.** spleen (splenic artery)
squamo- scale, flat (squamous, desquamation)
stasi-, stati- put, remain, stay the same (hemostasis, homeostatic)
steno- narrow (stenosis)
ster-, stereo- solid, three-dimensional (steroid, stereoscopic)
sterno- breast, chest (sternum, sternocleidomastoid)
stria- stripe (striated, corpus striatum)
sub- below (subcutaneous, subclavicular)
sulc- furrow, groove (sulcus)
supra- above (supraspinous, supraclavicular)
sura- calf of leg (triceps surae)
sym- together (sympathetic, symphysis)
syn- together (synostosis, syncytium)
tachy- fast (tachycardia, tachypnea)
tarsi- ankle (tarsus, metatarsal)
tecto- roof, cover (tectorial membrane, tectum)
telo- last, end (telophase, telencephalon, telodendria)
tempo- time (temporal)
terti- third (tertiary)
theli- nipple, female, tender (epithelium, polythelia)
thermo- heat (thermogenesis, endothermic)
thrombo- blood clot (thrombosis, thrombin)
thyro- shield (thyroid cartilage, thyrohyoid)
-tion process (circulation, pronation)
toci- birth (oxytocin)
tomo- 1. cut (tomography, atom, anatomy). **2.** segment (dermatome, myotome, sclerotome)
tono- force, tension (isotonic, tonus, myotonia)
topo- place, position (isotope, ectopic)
trabo- plate (trabecula)
trans- across (transpiration, transdermal)
trapezi- 1. table, grinding surface (trapezium). **2.** trapezoid (trapezius)
tri- three (triceps, triglyceride)
tricho- hair (peritrichial)
trocho- wheel, pulley (trochlea)
troph- 1. food, nourishment (heterotrophic, trophoblast). **2.** growth (dystrophy, hypertrophy)
tropo- to turn, change (metabotropic, gonadotropin)
tunica- coat (tunica intima, tunica vaginalis)
tympano- drum, eardrum (tympanic, tensor tympani)
-ul small (trabecula, tubule, capitulum, glomerulus)
-uncle, -unculus small (homunculus, caruncle)
uni- one (unipennate, unipolar)
uri- urine (glycosuria, urinalysis, diuretic)
utriculo- little bag (utriculus)
vagino- sheath (invaginate, tunica vaginalis)
vago- wander (vagus)
vaso- vessel (vascular, vas deferens, vasa recta)
ventro- belly, lower part (ventral, ventricle)
vermi- worm (vermis)
vertebro- spine (vertebrae, intervertebral)
vesico- bladder, blister (vesical, vesicular)
villo- hair, hairy (microvillus)
vitre- glass (in vitro, vitreous humor)
vivi- life, alive (in vivo, revive)
zygo- union, join, mate (zygomatic, zygote, azygos)

GLOSSARY

This glossary defines terms likely to be most useful to the reader of this particular book, especially terms that are reintroduced most often and cannot be defined again at every introduction. Terms are defined only in the sense that they are used in this book. Some have broader meanings, even within biology and medicine, that are beyond its scope. Pronunciation guides are provided for words whose pronunciations may not be obvious. These guides should be quite intuitive, but a key at the end of the glossary indicates how to pronounce letter sequences within the guides if help is needed. Figures are cited where they will help convey the meaning of a term. Figure references such as A.3 refer to figures in the Atlas of Regional and Surface Anatomy (p. 329).

A

abdominal cavity The body cavity between the diaphragm and pelvic brim. (fig. 1.12)

abdominopelvic cavity Collective name for the abdominal and pelvic cavities, which constitute a continuous space between the diaphragm and pelvic floor. (fig. 1.12)

abduction Movement of a body part away from the median plane, as in raising the right arm away from the body to point to the right. (fig. 9.8)

accessory organ A smaller organ associated with or embedded in another and performing a related function; for example, the hair, nails, and sweat glands are accessory organs of the skin.

acetylcholine (ACh) (ASS-eh-till-CO-leen) A neurotransmitter released by somatic motor nerve fibers, parasympathetic nerve fibers, and some other neurons, composed of choline and an acetyl group.

acetylcholinesterase (AChE) (ASS-eh-till-CO-lin-ESS-ter-ase) An enzyme found in synaptic clefts and on postsynaptic cells that breaks down acetylcholine and stops synaptic signal transmission.

acidophil A cell that stains with acidic dyes, such as a pituitary acidophil. (fig. 18.3)

acinar gland (ah-SEE-nur) A gland in which the secretory cells form a dilated sac or acinus. (fig. 3.30)

acinus (ASS-in-nus) A sac of secretory cells at the inner end of a gland duct. (fig. 3.29)

acromial region The apex of the shoulder.

actin A filamentous intracellular protein that provides cytoskeletal support and interacts with other proteins, especially myosin, to cause cellular movement; important in muscle contraction and membrane actions such as phagocytosis, ameboid movement, and cytokinesis. *See also* microfilament.

action The movement produced by the contraction of a muscle.

action potential A rapid voltage change in which a plasma membrane briefly reverses electrical polarity; has a self-propagating effect that produces a traveling wave of excitation in nerve and muscle cells.

acute Pertaining to a disorder with a sudden onset, severe effects, and brief duration. *Compare* chronic.

adaptation **1.** An evolutionary process leading to the establishment of species characteristics that favor survival and reproduction. **2.** Any characteristic of anatomy, physiology, or behavior that promotes survival and reproduction. **3.** A sensory process in which a receptor adjusts its sensitivity or response to the prevailing level of stimulation, as in *dark adaptation* of the eye.

adduction (ah-DUC-shun) Movement of a body part toward the median plane, such as bringing the feet together from a spread-legged position. (fig. 9.8)

adenohypophysis The anterior two-thirds of the pituitary gland, consisting of the anterior lobe and pars tuberalis; synthesizes and secretes gonadotropins, thyrotropin, adrenocorticotropin, growth hormone, and prolactin. (fig. 18.2)

adenosine triphosphate (ATP) A molecule composed of adenine, ribose, and three phosphate groups that functions as a universal energy-transfer molecule; briefly captures energy in its phosphate bonds and transfers it to other chemical reactions, yielding adenosine diphosphate and a free phosphate group upon hydrolysis.

adipocyte A fat cell.

adipose tissue A loose connective tissue composed predominantly of adipocytes; fat. (fig. 3.18)

adrenal gland (ah-DREE-nul) An endocrine gland on the superior pole of each kidney; consists of an outer adrenal cortex and inner adrenal medulla, with separate functions and embryonic origins. (fig. 18.8)

adult stem cell Any of several kinds of undifferentiated cells that populate the body's organs, where they multiply and differentiate to replace cells that are lost to damage or normal cellular turnover. Adult stem cells have more limited developmental potential than embryonic stem cells. *See also* embryonic stem cell.

adventitia (AD-ven-TISH-uh) Loose connective tissue forming the outermost sheath around organs such as a blood vessel or the esophagus.

afferent Carrying toward, as in *afferent neurons,* which carry signals toward the central nervous system, and *afferent arterioles,* which carry blood toward a tissue.

afferent neuron *See* sensory neuron.

aging Any changes in the body that occur with the passage of time, including growth, development, and senescence.

agonist *See* prime mover.

agranulocyte Either of the two leukocyte types (lymphocytes and monocytes) that lack specific cytoplasmic granules. (fig. 19.1)

alveolus (AL-vee-OH-lus) **1.** A microscopic air sac of the lung. **2.** A gland acinus. **3.** A pit or socket in a bone, such as a tooth socket. **4.** Any small anatomical space.

Alzheimer disease (AD) (ALTS-hy-mur) A degenerative disease of the senescent brain, typically beginning with memory lapses and progressing to severe losses of mental and motor functions and ultimately death.

ameboid movement Ameba-like crawling of cells such as leukocytes by means of pseudopods.

amnion A transparent membrane that surrounds the developing fetus and contains the amniotic fluid; the "bag of waters" that breaks during labor. (fig. 4.11)

ampulla (AM-pyu-luh) A wide or saclike portion of a tubular organ such as a semicircular duct or uterine tube.

anastomosis (ah-NASS-tih-MO-sis) An anatomical convergence, the opposite of a branch; a point where two blood vessels merge and combine their bloodstreams or where two nerves or ducts converge. (fig. 21.12)

anatomical position A reference posture on which certain standardized anatomical terminology is based. A subject in anatomical position is standing with the feet flat on the floor, arms down to the sides, and the palms and eyes directed forward. (fig. 1.8)

anatomy **1.** Structure of the body. **2.** The study of structure. *See also* morphology.

anemia A deficiency of erythrocytes or hemoglobin.

aneurysm (AN-you-riz-um) A weak, bulging point in the wall of a heart chamber or blood vessel that presents a threat of hemorrhage. (fig. 21.3)

angiogenesis The growth of new blood vessels, both prenatally and postnatally.

angiography The process of visualizing blood vessels by injecting them with a radiopaque substance and photographing them with X-rays. (fig. 1.3)

antagonist **1.** A muscle that opposes the prime mover at a joint. **2.** Any agent, such as a hormone or drug, that opposes another.

antebrachium (AN-teh-BRAY-kee-um) The region from elbow to wrist; the forearm.

anterior **1.** Pertaining to the front (facial–abdominal aspect) of the human body; also called *ventral,* especially in embryos. **2.** Pertaining to the head end of nonhuman animals.

anterior root A branch of a spinal nerve that joins the spinal cord on its anterior side, composed of motor nerve fibers; also called *ventral root.* (fig. 14.11)

antibody A protein of the gamma globulin class that reacts with an antigen; found in the blood plasma, in other body fluids, and on the surfaces of certain leukocytes and their derivatives.

antigen (AN-tih-jen) Any large molecule capable of binding to an antibody and triggering an immune response.

antigen-presenting cell (APC) A cell that phagocytizes an antigen and displays fragments of it on its surface for recognition by other cells of the immune system; chiefly macrophages and B lymphocytes.

antrum A saccular or pouchlike space, such as at the inferior end of the stomach or in an ovarian follicle.

aorta A large artery that extends from the left ventricle to the lower abdominal cavity and gives rise to all other arteries of the systemic circulation. (fig. 21.16)

aortic arch **1.** In the embryo, any of six pairs of blood vessels that arise rostral to the heart and loop mainly through the pharyngeal arches; some of these later give rise to carotid and pulmonary arteries and the permanent aortic arch. (fig. 21.35) **2.** A segment of the adult aorta that arches over the heart like an inverted U; gives rise to the brachiocephalic trunk, left common carotid artery, and left subclavian artery; then continues posterior to the heart as the descending aorta. (fig. 21.16)

apex The summit or a pointed part of an organ or body region such as the heart, lung, or shoulder.

apical surface The uppermost surface of an epithelial cell, opposite from the basement membrane, usually exposed to the lumen of an organ. (fig. 2.5)

apocrine Pertaining to certain sweat glands with large lumens and relatively thick, aromatic secretions, and to similar glands such as the mammary gland; formerly thought to form secretions by pinching off bits of apical cytoplasm. (figs. 3.31, 5.10)

aponeurosis A broad, flat tendon that attaches a muscle to a bone or to other soft tissues in such locations as the abdominal wall and deep to the scalp.

apoptosis The normal death of cells that have completed their function, usually in a process involving self-destruction of the cell's DNA, shrinkage of the cell, and its phagocytosis by a macrophage; also called *programmed cell death. Compare* necrosis.

appendicular (AP-en-DIC-you-lur) Pertaining to the limbs and their supporting skeletal girdles. (fig. 7.1)

arcuate (AR-cue-et) Making a sharp L- or U-shaped bend (arc), or forming an arch, as in *arcuate arteries* of the kidneys and uterus.

areolar tissue (AIR-ee-OH-lur) A fibrous connective tissue with loosely organized, widely spaced fibers and cells and an abundance of fluid-filled space; found under nearly every epithelium, among other places. (fig. 3.14)

arrector pili *See* piloerector.

arteriole A small artery that empties into a metarteriole or capillary.

artery Any blood vessel that conducts blood away from the heart, or in the case of coronary arteries, away from the aorta and into the heart wall.

articular cartilage A thin layer of hyaline cartilage covering the articular surface of a bone at a synovial joint, serving to reduce friction and ease joint movement. (fig. 9.4)

articulation A skeletal joint; any point at which two bones meet; may or may not be movable.

aspect A particular view of the body or one of its structures, or a surface that faces in a particular direction, such as the anterior aspect.

association area A region of the cerebral cortex that does not directly receive sensory input or control skeletal muscles, but serves to interpret sensory information, to plan motor responses, and for memory and cognition.

atherosclerosis A degenerative disease of the blood vessels characterized by the presence of plaques on the vessel wall composed of lipid, smooth muscle, and macrophages; can lead to arterial occlusion, loss of arterial elasticity, hypertension, heart attack, kidney failure, and stroke.

ATP *See* adenosine triphosphate.

atrioventricular (AV) node (AY-tree-oh-ven-TRIC-you-lur) A group of autorhythmic cells in the interatrial septum of the heart that relays excitation from the atria to the ventricles.

atrioventricular (AV) valves The bicuspid (right) and tricuspid (left) valves between the atria and ventricles of the heart.

atrium **1.** Either of the two superior chambers of the heart, which receive systemic and pulmonary blood. **2.** The central space of an alveolar sac into which individual pulmonary alveoli open.

atrophy Shrinkage of a tissue due to age, disuse, or disease.

auditory ossicles Three small middle-ear bones that transfer vibrations from the tympanic membrane to the inner ear; the malleus, incus, and stapes.

auricle **1.** The portion of the ear external to the cranium; the pinna. **2.** An ear-shaped structure, such as the auricles of the heart.

autoantibody An antibody that fails to distinguish the body's own molecules from foreign molecules and thus attacks host tissues, causing autoimmune diseases.

autoimmune disease Any disease in which antibodies fail to distinguish between foreign and self-antigens and attack the body's own tissues; for example, systemic lupus erythematosus and rheumatic fever.

autolysis (aw-TAHL-ih-sis) Digestion of cells by their own internal enzymes.

autonomic nervous system (ANS) A motor division of the nervous system that innervates glands, smooth muscle, and cardiac muscle; consists of sympathetic and parasympathetic divisions and functions largely without voluntary control. *Compare* somatic nervous system.

autosome Any chromosome except the sex chromosomes. Genes on the autosomes are inherited without regard to the sex of the individual.

axial Pertaining to the head, neck, and trunk; the part of the body excluding the appendicular portion. (fig. 7.1)

axillary (ACK-sih-LERR-ee) Pertaining to the armpit.

axon A process of a neuron that conducts action potentials away from the soma; also called a *nerve fiber.* There is only one axon to a neuron, and it is usually much longer and much less branched than the dendrites. (fig. 13.4)

axoneme The core of a cilium or flagellum, usually composed of a "9 + 2" array of microtubules that provide support and motility. (fig. 2.13)

B

baroreceptor (BARE-oh-re-SEP-tur) Pressure sensor located in the heart, aortic arch, and carotid sinuses that triggers autonomic reflexes in response to fluctuations in blood pressure.

basal lamina A thin layer of collagen, proteoglycan, and glycoprotein that binds epithelial and other cells to adjacent connective tissue; forms part of the basement membrane of an epithelium, and surrounds some nonepithelial cells such as muscle fibers and Schwann cells. (fig. 13.8)

basal nuclei Masses of deep cerebral gray matter that play a role in the coordination of posture and movement and the performance of learned motor skills; also called *basal ganglia.* (fig. 15.16)

base The broadest part of a tapered organ such as the uterus, or the inferior aspect of an organ such as the brain.

basement membrane A thin layer of matter that underlies the deepest cells of an epithelium and binds them to the underlying connective tissue; consists of the basal lamina of the epithelial cells and fine reticular fibers of the connective tissue. (fig. 3.32)

basophil (BASE-oh-fill) **1.** A cell that stains with basic dyes, such as a pituitary basophil. (fig. 18.3) **2.** A leukocyte with coarse cytoplasmic granules that produces heparin, histamine, and other chemicals involved in inflammation. (fig. 19.1)

belly The thick part of a skeletal muscle between its points of attachment. (fig. 10.4)

bipedalism The habit of walking on two legs; a defining characteristic of the family Hominidae that underlies many skeletal and other characteristics of humans.

blastocyst A hollow spheroidal stage of the conceptus that implants in the uterine wall; consists of an inner cell mass, or embryoblast, enclosed in a saclike outer cell mass, or trophoblast. (fig. 4.3)

blood A liquid connective tissue composed of plasma, erythrocytes, platelets, and five kinds of leukocytes.

blood–brain barrier A barrier between the bloodstream and nervous tissue of the brain that is impermeable to many blood solutes and thus prevents them from affecting the brain tissue; formed by the tight junctions between capillary endothelial cells, the basement membrane of the endothelium, and the perivascular feet of astrocytes.

B lymphocyte A lymphocyte that functions as an antigen-presenting cell and, in humoral immunity, differentiates into an antibody-producing plasma cell; also called a *B cell.*

body **1.** The entire organism. **2.** Part of a cell, such as a neuron, containing the nucleus and most other organelles. **3.** The largest or principal part of an organ such as the stomach or uterus; also called the *corpus.*

bolus A mass of matter, especially food or feces traveling through the digestive tract.

bone **1.** A calcified connective tissue; also called *osseous tissue.* **2.** An organ of the skeleton composed of osseous tissue, fibrous connective tissue, marrow, cartilage, and other tissues.

brachial (BRAY-kee-ul) Pertaining to the brachium.

brachium The region between the shoulder and elbow; the arm proper.

brainstem The stalklike lower portion of the brain, composed of all of the brain except the cerebrum and cerebellum. (Many authorities exclude the diencephalon and regard only the medulla oblongata, pons, and midbrain as the brainstem.) (fig. 15.6)

bronchiole (BRON-kee-ole) A pulmonary air passage that is usually 1 mm or less in diameter and lacks cartilage, but has relatively abundant smooth muscle, elastic tissue, and a simple cuboidal, usually ciliated epithelium.

bronchus (BRON-kus) A relatively large pulmonary air passage with supportive cartilage in the wall; any passage beginning with the primary bronchus at the fork in the trachea and ending with tertiary bronchi, from which air continues into the bronchioles.

brush border A fringe of microvilli on the apical surface of an epithelial cell, serving to enhance surface area and promote absorption. (fig. 3.6)

buccal Pertaining to the cheek.

bulb A dilated terminal part of an organ such as the penis or hair, or the olfactory bulb at the beginning of the olfactory tract.

bursa A sac filled with synovial fluid at a synovial joint, serving to facilitate muscle or joint action. (fig. 9.5)

C

calcaneal tendon (cal-CAY-nee-ul) A thick tendon at the heel that attaches the triceps surae muscles to the calcaneus; also called the *Achilles tendon.* (fig. 12.18)

calcification The hardening of a tissue due to the deposition of calcium salts; also called *mineralization.*

calculus A calcified mass, especially a renal calculus (kidney stone) or biliary calculus (gallstone).

calvaria (cal-VERR-ee-uh) The rounded bony dome that forms the roof of the cranium; the general portion of the skull superior to the eyes and ears; skullcap.

calyx (CAY-lix) (plural, *calices*) A cuplike structure, as in the kidneys. (fig. 25.3)

canal A tubular passage or tunnel such as the auditory, semicircular, or condylar canal.

canaliculus (CAN-uh-LIC-you-lus) A microscopic canal, as in osseous tissue. (fig. 6.4)

cancellous bone *See* spongy bone.

capillary (CAP-ih-LERR-ee) The narrowest type of vessel in the cardiovascular and lymphatic systems; engages in fluid exchanges with surrounding tissues.

capillary bed A network of blood capillaries that arise from a single metarteriole and converge on a thoroughfare channel or venule. (fig. 21.9)

capsule The fibrous covering of a structure such as the spleen or a synovial joint.

carbohydrate A hydrophilic organic compound composed of carbon and a 2:1 ratio of hydrogen to oxygen; includes sugars, starches, glycogen, and cellulose.

cardiac center A nucleus in the medulla oblongata that regulates autonomic reflexes for controlling the rate and strength of the heartbeat.

cardiac muscle Striated involuntary muscle of the heart. (fig. 20.14)

cardiocyte A cardiac muscle cell.

cardiopulmonary system Collective name for the heart and lungs, emphasizing their close spatial and physiological relationship.

cardiovascular system An organ system consisting of the heart and blood vessels, serving for the transport of blood. *Compare* circulatory system.

carotid body (ca-ROT-id) A small cellular mass near the branch in the common carotid artery, containing sensory cells that detect changes in the pH and the carbon dioxide and oxygen content of the blood. (fig. 21.4)

carotid sinus A dilation at the base of the internal carotid artery; contains baroreceptors, which monitor changes in blood pressure. (fig. 21.4)

carpal Pertaining to the wrist (carpus).

carrier **1.** A protein that transports solutes through a cell membrane; also called a *transport protein.* **2.** A person who does not exhibit a particular hereditary disorder, but who has the gene for it and may pass it to the next generation.

cartilage A connective tissue with a rubbery matrix, cells (chondrocytes) contained in lacunae, and no blood vessels; covers the joint surfaces of many bones and supports organs such as the ear and larynx.

caudal (CAW-dul) **1.** Pertaining to a tail or narrow tail-like part of an organ. **2.** Pertaining to the inferior part of the trunk of the body, where the tail of other animals arises. *Compare* cranial. **3.** Relatively distant from the forehead, especially in reference to structures of the brain and spinal cord; for example, the medulla oblongata is caudal to the pons. *Compare* rostral.

celiac Pertaining to the abdomen.

celiac trunk An arterial trunk that arises from the abdominal aorta near the diaphragm, and quickly branches to give off arteries that supply the stomach, spleen, pancreas, liver, and other viscera of the upper abdominal cavity. (fig. 21.23)

cell The smallest subdivision of a tissue considered to be alive; consists of a plasma membrane enclosing cytoplasm and, in most cases, a nucleus.

cell body The main part of a cell, especially a neuron, where the nucleus is located; also called the *soma.*

cell junction A complex of proteins that joins adjacent cells to each other or binds a cell to extracellular material; also called an *intercellular junction* when it links two cells. Includes desmosomes, hemidesmosomes, tight junctions, gap junctions, and other types. (fig. 2.15)

central Located relatively close to the median axis of the body, as in *central nervous system;* opposite of *peripheral.*

central canal **1.** A canal that passes through the core of an osteon in bone, and contains blood vessels and nerves; also called a *haversian canal* or *osteonic canal.* **2.** A canal that passes through the center of the spinal cord, containing cerebrospinal fluid.

central nervous system (CNS) The brain and spinal cord. *Compare* peripheral nervous system.

central pattern generator A nucleus of neurons in the CNS that generates a repetitive motor output, producing rhythmic muscle contractions for such purposes as walking and breathing.

centriole (SEN-tree-ole) An organelle composed of a short cylinder of nine triplets of microtubules, usually paired with another centriole perpendicular to it; origin of the mitotic spindle; identical to the basal body of a cilium or flagellum. (fig. 2.19)

cephalic (seh-FAL-ic) Pertaining to the head.

cerebellum (SERR-eh-BEL-um) A large portion of the brain posterior to the brainstem and inferior to the cerebrum, responsible for equilibrium, motor coordination, some timekeeping functions, and learning of motor skills. (fig. 15.9)

cerebrospinal fluid (CSF) (SERR-eh-bro-SPY-nul, seh-REE-bro-SPY-nul) A liquid that fills the ventricles of the brain, the central canal of the spinal cord, and the space between the CNS and dura mater.

cerebrum (SERR-eh-brum, seh-REE-brum) The largest and most superior part of the brain, divided into two convoluted cerebral hemispheres separated by a deep longitudinal fissure.

cervical (SUR-vih-cul) Pertaining to the neck or any cervix.

cervix (SUR-vix) **1.** The neck. **2.** A narrow or necklike part of an organ such as the uterus and gallbladder. (fig. 26.12)

chemoreceptor An organ or cell specialized to detect chemicals, as in the carotid bodies and taste buds.

chief cell The majority type of cell in an organ or tissue such as the parathyroid glands or gastric glands.

choana (co-AN-ah) *See* posterior nasal aperture.

chondrocyte (CON-dro-site) A cartilage cell; a former chondroblast that has become enclosed in a lacuna in the cartilage matrix. (fig. 3.19)

chorion (CO-ree-on) A fetal membrane external to the amnion; forms part of the placenta and has diverse functions including fetal nutrition, waste removal, and hormone secretion. (fig. 4.8)

chromatid (CRO-muh-tid) One of two genetically identical rodlike bodies of a metaphase chromosome, joined to its sister chromatid at the centromere. (fig. 2.24)

chromatin (CRO-muh-tin) Filamentous material in the interphase nucleus, composed of DNA and protein; all of the chromosomes collectively.

chromosome A strand of DNA and protein carrying the genetic material of a cell's nucleus, having a fine filamentous structure during interphase and a condensed rodlike structure during mitosis and meiosis. Normally there are 46 chromosomes in the nucleus of each cell except germ cells. (fig. 2.24)

chronic Pertaining to a disorder with a gradual onset, slow progression, and long duration. *Compare* acute.

chyme (pronounced "kime") A slurry of partially digested food in the stomach and small intestine.

cilium (SIL-ee-um) A hairlike process, with an axoneme, projecting from the surface of many or most cells; usually immobile, solitary, and serving a sensory or unknown role; found in large numbers on the apical surfaces of some epithelial cells (as in the respiratory tract and uterine tube), where they are motile and serve to propel matter across the surface of the epithelium. (fig. 2.13)

circulatory system An organ system consisting of the heart, blood vessels, and blood. *Compare* cardiovascular system.

circumduction A joint movement in which one end of an appendage remains relatively stationary and the other end moves in a circle. (fig. 9.11)

cisterna (sis-TUR-nuh) A fluid-filled space or sac, such as the cisterna chyli of the lymphatic system and the cisternae of the endoplasmic reticulum and Golgi complex. (fig. 2.19)

coelom A body cavity bounded on all sides by mesoderm and lined with peritoneum. The embryonic coelom becomes the thoracic and abdominopelvic cavities.

collagen (COLL-uh-jen) The most abundant protein in the body, forming the fibers of many connective tissues in places such as the dermis, tendons, and bones.

colony-forming unit (CFU) A bone marrow cell that differentiates from a pluripotent stem cell and gives rise to precursor cells, which, in turn, produce a specific class of formed elements. (fig. 19.8)

commissure (COM-ih-shur) **1.** A bundle of nerve fibers that crosses from one side of the brain or spinal cord to the other. **2.** A corner or angle at which the eyelids, lips, or genital labia meet; in the eye, also called the *canthus.* (figs. 15.2, 17.19)

compact bone A form of osseous tissue found on bone surfaces and composed predominantly of osteons, with the tissue completely filled with mineralized matrix (other than lacunae and central canals) and leaving no room for bone marrow; also called *dense bone.* (fig. 6.4) *Compare* spongy bone.

computed tomography (CT) A method of medical imaging that uses X-rays and a computer to create an image of a thin section of the body; the image is called a *CT scan.* (fig. 1.3)

conception The fertilization of an egg, producing a zygote; the beginning of pregnancy.

conceptus All products of conception, ranging from a fertilized egg to the full-term fetus with its fetal membranes, placenta, and umbilical cord. *Compare* embryo; fetus; preembryo.

condyle (CON-dile) An articular surface on a bone, usually in the form of a knob (as on the mandible), but relatively flat on the proximal end of the tibia. (fig. 7.15)

congenital Present at birth; for example, an anatomical defect, a syphilis infection, or a hereditary disease.

congenital anomaly The abnormal structure or position of an organ at birth, resulting from a defect in prenatal development; a birth defect.

connective tissue A tissue usually composed of more extracellular than cellular volume and usually with a substantial amount of extracellular fiber; forms supportive frameworks and capsules for organs, binds structures together, holds them in place, stores energy (as in adipose tissue), or transports materials (as in blood).

contralateral On opposite sides of the body, as in reflex arcs where the stimulus comes from one side of the body and a response is given by muscles on the other side. *Compare* ipsilateral.

convergent Coming together, as in a *convergent muscle* and a converging neuronal circuit.

cornified Having a heavy surface deposit of keratin, as in the stratum corneum of the epidermis.

corona A halo- or crownlike structure, such as the corona radiata or coronal suture of the skull.

coronal plane *See* frontal plane.

corona radiata **1.** An array of nerve tracts in the brain that arise mainly from the thalamus and fan out to different regions of the cerebral cortex. **2.** The first layer of cuboidal cells immediately external to the zona pellucida around an egg cell.

coronary **1.** Crownlike; encircling. **2.** Pertaining to the heart.

coronary artery Either of two branching arteries that arise from the aorta near the heart and supply blood to the heart wall.

coronary circulation A system of blood vessels that serve the wall of the heart. (fig. 20.11)

corpus **1.** A body of tissue, such as the corpus cavernosum of the penis. **2.** The principal part (body) of an organ such as the uterus or stomach, as opposed to smaller regions of an organ such as its head, tail, fundus, or cervix.

corpus callosum (COR-pus ca-LO-sum) A prominent C-shaped band of nerve tracts that connect the right and left cerebral hemispheres to each other, seen superior to the third ventricle in a median section of the brain. (fig. 15.2)

corpus luteum A yellowish cellular mass that forms in the ovary from a follicle that has ovulated; secretes progesterone, hormonally regulates the second half of the menstrual cycle, and is essential to sustaining the first 7 weeks of pregnancy.

cortex (plural, *cortices*) The outer layer of some organs such as the adrenal gland, cerebrum, lymph node, and ovary; usually covers or encloses tissue called the medulla.

corticospinal tract A bundle of nerve fibers that descend through the brainstem and spinal cord and carry motor signals from the cerebral cortex to the neurons that innervate the skeletal muscles of the limbs; important in the fine control of limb movements. (fig. 14.5)

costal (COSS-tul) Pertaining to the ribs.

costal cartilage A bladelike plate of hyaline cartilage that attaches the distal end of a rib to the sternum; collectively the costal cartilages constitute much of the anterior part of the thoracic cage.

coxal Pertaining to the hip.

cranial **1.** Pertaining to the cranium. **2.** In a position relatively close to the head or a direction toward the head. *Compare* caudal.

cranial nerve Any of 12 pairs of nerves connected to the base of the brain and passing through foramina of the cranium.

cranium That portion of the skull that encloses the cranial cavity and protects the brain; also called the *braincase.* Comprises the frontal, parietal, temporal, occipital, sphenoid, and ethmoid bones.

crest A narrow ridge, such as the neural crest or the crest of the ilium.

cricoid cartilage The most inferior cartilage of the larynx, connecting the larynx to the trachea.

crista A crestlike structure, such as the crista galli of the ethmoid bone, crista ampullaris of the inner ear, or the crista of a mitochondrion.

cross section (c.s.) A cut perpendicular to the long axis of the body or of an organ. (fig. 3.2)

crural (CROO-rul) Pertaining to the leg proper or to the crus of a organ. *See also* crus.

crus (pronounced "cruss") (plural, *crura*) **1.** The region from the knee to the ankle; the leg proper. **2.** A leglike extension of an organ such as the penis and clitoris. (fig. 26.1) *See also* crural.

CT scan An image of the body made by computed tomography. (fig. 1.3)

cubital region The anterior region at the bend of the elbow.

cuboidal (cue-BOY-dul) A shape that is roughly like a cube or in which the height and width are about equal.

cuneiform (cue-NEE-ih-form) Wedge-shaped, as in *cuneiform cartilages* and *cuneiform bone.*

cusp **1.** One of the flaps of a valve of the heart, veins, and lymphatic vessels. **2.** A conical projection on the occlusal surface of a premolar or molar tooth.

cutaneous Pertaining to the skin; integumentary.

cuticle **1.** The outermost layer of a hair, consisting of a single layer of overlapping squamous cells. **2.** A layer of dead epidermal cells that cover the proximal end of a nail; also called the *eponychium.*

cytokinesis (SY-toe-kih-NEE-sis) Division of the cytoplasm of a cell into two cells following nuclear division.

cytology The study of cell structure and function.

cytoplasm The contents of a cell between the plasma membrane and the nuclear envelope, consisting of cytosol, organelles, inclusions, and the cytoskeleton.

cytoskeleton A system of protein microfilaments, intermediate filaments, and microtubules in a cell, serving for physical support, cellular movement, and the routing of molecules and organelles to their destinations within the cell. (fig. 2.16)

cytosol A clear, featureless, gelatinous colloid in which the organelles and other internal structures of a cell are embedded.

cytotoxic T cell A T lymphocyte that directly attacks and destroys infected body cells, cancerous cells, and the cells of transplanted tissues.

D

daughter cells Cells that arise from a parent cell by mitosis or meiosis.

decussation (DEE-cuh-SAY-shun) The crossing of nerve fibers from the right side of the central nervous system to the left, or vice versa, especially in the spinal cord, medulla oblongata, and optic chiasm. *Compare* hemidecussation.

deep Relatively far from the body surface; opposite of *superficial.* For example, the bones are deep to the skeletal muscles.

dendrite Process of a neuron that receives information from other cells or from environmental stimuli and conducts signals to the soma. Dendrites are usually shorter, more branched, and more numerous than the axon and are incapable of producing action potentials. (fig. 13.4)

dendritic cell An antigen-presenting cell of the epidermis, vaginal mucosa, and some other epithelia.

denervation atrophy The shrinkage of skeletal muscle that occurs when the motor neuron dies or is severed from the muscle.

dense bone *See* compact bone.

dense connective tissue A connective tissue with a high density of fiber, relatively little ground substance, and scanty cells; seen in tendons and the dermis, for example. Classified as *regular* if the extracellular fibers are more or less parallel and *irregular* if the fibers travel in highly varied directions. (figs. 3.16–3.17)

depression **1.** A sunken place on the surface of a bone. **2.** A joint movement that lowers a body part, as in dropping the shoulders or opening the mouth. (fig. 9.9)

dermal papilla **1.** A bump or ridge of dermis that extends upward to interdigitate with the epidermis, creating a wavy boundary that resists stress and slippage of the epidermis. (fig. 5.3) **2.** A projection of the dermis into the bulb of a hair, supplying blood to the hair. (fig. 5.6)

dermatome **1.** In the embryo, a group of mesodermal cells that arises from a somite and gives rise to the dermis on one side of one segment of the body. *Compare* myotome; sclerotome. **2.** In the adult, a region of skin on the neck, trunk, or limbs that is innervated by one spinal nerve. (fig. 14.18)

dermis The deeper of the two layers of the skin, underlying the epidermis and composed of fibrous connective tissue.

desmosome (DEZ-mo-some) A patchlike intercellular junction that mechanically links two cells together. (fig. 2.15)

desquamation *See* exfoliation.

diaphragm A muscular partition that separates the thoracic cavity from the abdominal cavity and plays a major role in respiration.

diaphysis (dy-AFF-ih-sis) The shaft of a long bone. (fig. 6.1)

diarthrosis *See* synovial joint.

diencephalon (DY-en-SEFF-uh-lon) A portion of the brain between the midbrain and corpus callosum; composed of the thalamus, epithalamus, and hypothalamus. (fig. 15.11)

differentiation Development of a relatively unspecialized cell or tissue into one with a more specific structure and function.

digestive system The organ system specialized for the intake and chemical breakdown of food, absorption of nutrients, and discharge of the indigestible residue.

digit A finger or toe.

digital rays The first ridgelike traces of fingers or toes to appear in the embryonic hand plate and foot plate.

dilation (dy-LAY-shun) Widening of an organ or passageway such as a blood vessel or the pupil of the eye.

diploid (2*n*) Pertaining to a cell or organism with chromosomes in homologous pairs. All nucleated cells of the human body are diploid except for germ cells beyond the meiosis I stage of cell division.

distal Relatively distant from a point of origin or attachment; for example, the wrist is distal to the elbow. *Compare* proximal.

dizygotic (DZ) twins Two individuals who developed simultaneously in one uterus but originated from separate fertilized eggs and therefore are not genetically identical.

dorsal *See* posterior.

dorsal root *See* posterior root.

dorsal root ganglion *See* posterior root ganglion.

dorsiflexion (DOR-sih-FLEC-shun) A movement of the ankle that reduces the joint angle and raises the toes. (fig. 9.17)

dorsum The dorsal surface of a body region, especially the hand or foot surface bearing the nails.

Down syndrome *See* trisomy-21.

duct An epithelium-lined, tubular passageway, such as a semicircular duct or a gland duct.

duodenum (DEW-oh-DEE-num, dew-ODD-eh-num) The first portion of the small intestine extending for about 25 cm from the pyloric valve of the stomach to a sharp bend called the duodenojejunal flexure; receives chyme from the stomach and secretions from the liver and pancreas.

dural sheath An extension of the dura mater into the vertebral canal, loosely enclosing the spinal cord.

dura mater The thickest and most superficial of the three meninges around the brain and spinal cord.

dynein (DINE-een) A motor protein involved in the beating of cilia and flagella and in the movement of molecules and organelles within cells.

dyspnea Labored breathing.

E

ectoderm The outermost of the three primary germ layers of an embryo; gives rise to the nervous system and epidermis.

ectopic (ec-TOP-ic) In an abnormal location; for example, ectopic pregnancy and ectopic pacemakers of the heart.

edema Accumulation of excess tissue fluid, resulting in swelling of a tissue.

effector A molecule, cell, or organ that carries out a response to a stimulus.

efferent (EFF-ur-ent) Carrying away or out, such as a blood vessel that carries blood away from a tissue or a nerve fiber that conducts signals away from the central nervous system.

efferent neuron *See* motor neuron.

elastic cartilage A form of cartilage with an abundance of elastic fibers in its matrix, lending flexibility and resilience to the cartilage; found in the epiglottis and ear pinna. (fig. 3.20)

elastic fiber A connective tissue fiber, composed of the protein elastin, that stretches under tension and returns to its original length when released; responsible for the resilience of organs such as the skin and lungs.

elasticity The tendency of a stretched structure to return to its original dimensions when tension is released.

elastin A fibrous protein with the ability to stretch and recoil; found in the skin, pulmonary airway, arteries, and elastic cartilage, among other locations.

elevation A joint movement that raises a body part, as in hunching the shoulders or closing the mouth. (fig. 9.9)

embryo In humans, a developing individual from the time the ectoderm, mesoderm, and endoderm have all formed at about 16 days, through the end of 8 weeks when all organ systems are represented; preceded by the *preembryo* and followed by the *fetus.* In other animals, any unborn stage of development beginning with the two-celled stage. *Compare* conceptus; fetus; preembryo.

embryogenesis A process of prenatal development that occurs during implantation of the blastocyst and gives rise to the three primary germ layers; embryogenesis ends with the existence of an embryo.

embryology The scientific study of prenatal development, from fertilization to birth.

embryonic disc A flat plate of cells in early embryonic development, composed of initially two and then three cell layers.

embryonic stage The stage of prenatal development from day 16 through the end of week 8. *See also* embryo; fetal stage.

embryonic stem cell An undifferentiated cell from a preembryo of up to 150 cells, capable of developing into any type of embryonic or adult cell.

encapsulated nerve ending Any sensory nerve ending that is surrounded by or associated with specialized connective tissues, which enhance its sensitivity or its mode of responding to stimulation.

endocardium A tissue layer that lines the inside of the heart, composed of a simple squamous epithelium overlying a thin layer of areolar tissue.

endochondral ossification A process of bone development in which the bone is preceded by a model of hyaline cartilage in roughly the shape of the bone to come, and the cartilage is then replaced by osseous tissue. *Compare* intramembranous ossification. (fig. 6.9)

endocrine gland (EN-doe-crin) A ductless gland that secretes hormones into the bloodstream; for example, the thyroid and adrenal glands. *Compare* exocrine gland.

endocrine system A system of internal chemical communication composed of all endocrine glands and the hormone-secreting cells found in other tissues and organs.

endocytosis Any process of vesicular transport of materials from the extracellular material into a cell; includes pinocytosis, receptor-mediated endocytosis, and phagocytosis. (fig. 2.11)

endoderm The innermost of the three primary germ layers of an embryo; gives rise to the mucosae of the digestive and respiratory tracts and to their associated glands.

endogenous (en-DODJ-eh-nus) Originating internally, such as the endogenous cholesterol synthesized in the body in contrast to the exogenous cholesterol coming from the diet. *Compare* exogenous.

endometrium (EN-doe-MEE-tree-um) The mucosa of the uterus; the site of implantation and source of menstrual discharge.

endoplasmic reticulum (ER) (EN-doe-PLAZ-mic reh-TIC-you-lum) An extensive system of interconnected cytoplasmic tubules or channels; classified as *rough ER* or *smooth ER* depending on the presence or absence of ribosomes on its membrane. (fig. 2.19)

endothelium (EN-doe-THEEL-ee-um) A simple squamous epithelium that lines the lumens of the blood vessels, heart, and lymphatic vessels.

enteric (en-TERR-ic) Pertaining to the small intestine, as in *enteric hormones.*

eosinophil (EE-oh-SIN-oh-fill) A leukocyte with a large, often bilobed nucleus and coarse cytoplasmic granules that stain with eosin; phagocytizes antigen–antibody complexes, allergens, and inflammatory chemicals and secretes enzymes that combat parasitic infections. (fig. 19.1)

epiblast The layer of cells in the early embryonic disc facing the amniotic cavity. These cells migrate during gastrulation to replace the hypoblast with endoderm, then to form the mesoderm, after which the remaining surface epiblast cells are called the ectoderm.

epicardium The outermost layer of the heart wall, composed of a simple squamous epithelium overlying a thin layer of areolar tissue, and in many areas, a much thicker layer of adipose tissue; also called the *visceral pericardium.*

epicondyle A bony projection or ridge superior to a condyle, for example at the distal ends of the humerus and femur. (fig. 8.10)

epidermis A stratified squamous epithelium that constitutes the superficial layer of the skin, overlying the dermis. (fig. 5.1)

epigastric Pertaining to a medial region of the abdomen superior to the umbilical region, bordered inferiorly by the subcostal line and laterally by the midclavicular lines. (fig. 1.11)

epiglottis A flap of tissue in the pharynx that covers the glottis during swallowing, deflecting swallowed matter away from the airway and into the esophagus.

epiphyseal plate (EP-ih-FIZZ-ee-ul) A plate of hyaline cartilage between the epiphysis and diaphysis of a long bone in a child or adolescent, serving as a growth zone for bone elongation. (fig. 6.9)

epiphysis (eh-PIFF-ih-sis) **1.** The head of a long bone. (fig. 6.1) **2.** The pineal gland (epiphysis cerebri).

epithelium A type of tissue consisting of one or more layers of closely adhering cells with little intercellular material and no blood vessels; forms the coverings and linings of many organs and the parenchyma of the glands.

equilibrium **1.** The sense of balance. **2.** A state in which opposing processes occur at comparable rates and balance each other so that there is little or no net change in the system, such as a chemical equilibrium.

erectile tissue A tissue that functions by swelling with blood, as in the penis, clitoris, and inferior concha of the nasal cavity.

erythrocyte (eh-RITH-ro-site) A red blood cell.

erythropoiesis (eh-RITH-ro-poy-EE-sis) The production of erythrocytes.

eversion A movement of the foot that turns the sole laterally. (fig. 9.17)

evolution A change in the genetic composition of a population over a period of time; the mechanism that produces adaptations in human form and function. *See also* adaptation.

excitability The ability of a cell to respond to a stimulus, especially the ability of nerve and muscle cells to produce membrane voltage changes in response to stimuli; irritability.

excretion The process of eliminating metabolic waste products from a cell or from the body. *Compare* secretion.

excursion A side-to-side movement of the mandible, as in chewing. (fig. 9.15)

exfoliation The shedding of squamous cells from the surface of a stratified squamous epithelium. Also called *desquamation.* Sampling and examination of these cells, such as a Pap smear, is called *exfoliate cytology.* (fig. 3.12)

exocrine gland (EC-so-crin) A gland that secretes its products into another organ or onto the body surface, usually by way of a duct; for example, salivary and gastric glands. *Compare* endocrine gland.

exocytosis A mode of vesicular transport in which a secretory vesicle of a cell fuses with the plasma membrane and releases its contents from the cell; a mode of glandular secretion and discharge of cellular wastes. (fig. 2.11)

exogenous (ec-SODJ-eh-nus) Originating externally, such as exogenous (dietary) cholesterol; extrinsic. *Compare* endogenous.

expiration **1.** Exhaling. **2.** Dying.

extension Movement of a joint that increases the angle between articulating bones (straightens the joint). *Compare* flexion. (fig. 9.7)

external acoustic meatus A canal in the temporal bone that conveys sound waves to the eardrum; also called the *external auditory meatus.*

exteroceptor A sensory receptor that responds to stimuli originating outside the body, such as the eye or ear. *Compare* interoceptor.

extracellular fluid (ECF) Any body fluid that is not contained in the cells; for example, blood, lymph, and tissue fluid.

extrinsic (ec-STRIN-sic) **1.** Originating externally, such as extrinsic blood-clotting factors; exogenous. **2.** Not fully contained within an organ but acting on it, such as the *extrinsic muscles* of the hand and eye. *Compare* intrinsic.

F

facet A smooth articular surface on a bone; may be flat, slightly concave, or slightly convex; for example, the articular facets of the vertebrae.

facilitated diffusion A process of solute transport through a cellular membrane, down its concentration gradient, with the aid of a carrier protein; the carrier does not consume ATP.

fallopian tube *See* uterine tube.

fascia (FASH-ee-uh) A layer of connective tissue between the muscles or between the muscles and the skin. (fig. 10.2)

fascicle (FASS-ih-cul) A bundle of muscle or nerve fibers ensheathed in connective tissue; multiple fascicles bound together constitute a muscle or nerve as a whole. Also called a *fasciculus.* (fig. 10.2)

fat **1.** A triglyceride molecule. **2.** Adipose tissue.

female In humans, any individual with no Y chromosome; normally, one possessing two X chromosomes in each somatic cell, and having reproductive organs that serve to produce eggs, receive sperm, provide sites of fertilization and prenatal development, expel the full-term fetus, and nourish the infant.

femoral Pertaining to the femur or the thigh.

femoral region The region between the hip and knee; the thigh.

femoral triangle A triangular region of the groin bounded by the sartorius muscle, adductor longus muscle, and inguinal ligament, and through which the femoral artery, femoral vein, and femoral nerve pass close to the body surface. (fig. 21.33)

fenestrated (FEN-eh-stray-ted) Perforated with holes or slits, as in certain blood capillaries and the elastic sheets of large arteries. (fig. 21.6)

fetal stage The period of prenatal development from the beginning of week 9 until birth; a period in which all organ systems are represented at the outset, and grow and differentiate until capable of supporting life outside the uterus. *See also* embryonic stage; fetus.

fetus In human development, an individual from the beginning of the ninth week when all of the organ systems are present, through the time of birth. *See also* conceptus; embryo.

fiber **1.** In muscular histology, a skeletal muscle cell *(muscle fiber).* **2.** In neurohistology, the axon of a neuron *(nerve fiber).* **3.** Any long threadlike structure, such as a Purkinje fiber of the heart, a collagen or elastic fiber of the connective tissues, or cellulose and other digestion-resistant dietary fiber.

fibrinogen A protein synthesized by the liver and present in blood plasma, semen, and other body fluids; precursor of the sticky protein fibrin, which forms the matrix of a clot.

fibroblast A connective tissue cell that produces collagen fibers and ground substance; the only type of cell in tendons and ligaments.

fibrocartilage A form of cartilage with coarse bundles of collagen fibers in the matrix, found in the intervertebral discs, joint menisci, pubic symphysis, and some tendon–bone junctions. (fig. 3.21)

fibrosis Replacement of damaged tissue with fibrous scar tissue rather than by the original tissue type; scarring. *Compare* regeneration.

fibrous connective tissue Any connective tissue with a preponderance of fiber, such as areolar, reticular, dense regular, and dense irregular connective tissues.

filament A fine threadlike structure such as the myofilaments of muscle and the microfilaments and intermediate filaments of the cytoskeleton.

filtration A process in which a fluid is physically forced through a membrane that allows water and some solutes to pass, and holds back larger particles; especially important in the emission of fluid from blood capillaries.

finger Any of the five digits of the hand, including the thumb.

first-order neuron An afferent (sensory) neuron that carries signals from a receptor to a second-order neuron in the spinal cord or brain. (fig. 14.4) *See also* second-order neuron; third-order neuron.

fissure **1.** A slit through a bone, such as the orbital fissure. **2.** A deep groove, such as the longitudinal fissure between the cerebral hemispheres.

fix **1.** To hold a structure in place, for example, by fixator muscles that prevent unwanted joint movements. **2.** To preserve a tissue by means of a fixative.

fixative A chemical that prevents tissue decay, such as formalin or ethanol.

fixator A muscle that minimizes or prevents bone movement in certain joint actions, such as the rhomboid major holding the scapula stationary while the biceps brachii flexes the elbow.

flagellum (fla-JEL-um) A long, motile, usually single hairlike extension of a cell; the tail of a sperm cell is the only functional flagellum in humans.

flat bone A bone with a platelike shape, such as the parietal bone or sternum.

flexion A joint movement that, in most cases, decreases the angle between two bones. (fig. 9.7) *Compare* extension.

flexor A muscle that flexes a joint.

fMRI *See* functional magnetic resonance imaging.

follicle (FOLL-ih-cul) A small space, such as a hair follicle, thyroid follicle, or ovarian follicle. (fig. 26.14) *See also* lymphatic nodule.

foramen (fo-RAY-men) A hole through a bone or other organ, in most cases providing passage for blood vessels and nerves.

foramen magnum The largest opening into the cranial cavity, at the point where the occipital bone articulates with the vertebral column; allows passage of the spinal cord and vertebral arteries into the cranial cavity.

foramen ovale **1.** An ovoid foramen in the sphenoid bone that allows for passage of the mandibular division of the trigeminal nerve. **2.** An opening in the fetal interatrial septum that allows blood to flow directly from the right atrium into the left atrium and bypass the pulmonary circulation.

forebrain The most rostral part of the brain, consisting of the cerebrum and diencephalon. (fig. 13.14)

foregut **1.** The most rostral part of the embryonic digestive tract; all of the tract rostral to the initial attachment of the yolk sac. (fig. 4.5) **2.** In adults, all of the digestive tract from the oral cavity to the major duodenal papilla, with a blood supply and innervation separate from those of the midgut and hindgut.

formed element An erythrocyte, leukocyte, or platelet; any normal component of blood or lymph that is a cell or cell fragment, as opposed to the extracellular fluid component.

fossa (FOSS-uh) A depression in an organ or tissue, such as the fossa ovalis of the heart or a cranial fossa of the skull.

fovea (FOE-vee-uh) A small pit, such as the fovea capitis of the femur or fovea centralis of the retina.

free nerve ending A bare sensory nerve ending, lacking associated connective tissue or specialized cells; includes receptors for heat, cold, and pain; also called an *unencapsulated nerve ending.*

frontal plane An anatomical plane that passes through the body or an organ from right to left and superior to inferior; also called a *coronal plane.* (fig. 1.8)

functional magnetic resonance imaging (fMRI) A variation on MRI that enables the visualization of moment-to-moment changes in the metabolic activity of a tissue, rather than static images; used to study quickly changing patterns of brain activity, among other diagnostic and research purposes.

fundus The base or broadest part of certain organs such as the stomach and uterus.

funiculus (few-NICK-you-lus) Any of the three major divisions of the white matter of the spinal cord, composed of multiple fascicles, or tracts; also called a *column.* The three funiculi on each side of the cord are the dorsal, lateral, and ventral columns.

fusiform (FEW-zih-form) Spindle-shaped; elongated, thick in the middle, and tapered at both ends, such as the shape of a smooth muscle cell or a muscle spindle. (fig. 2.3)

G

gamete (GAM-eet) An egg or sperm cell.

gametogenesis (GAM-eh-toe-JEN-eh-sis) The production of eggs or sperm.

ganglion (GANG-glee-un) A cluster of nerve cell bodies in the peripheral nervous system, often resembling a knot in a string.

gangrene Tissue necrosis resulting from ischemia.

gap junction A junction between two cells consisting of a pore surrounded by a ring of proteins in the plasma membrane of each cell, allowing solutes to diffuse from the cytoplasm of one cell to the next; functions include cell-to-cell nutrient transfer in the developing embryo and electrical communication between cells of cardiac and smooth muscle. (fig. 2.15)

gastric Pertaining to the stomach.

gastrointestinal (GI) system The part of the digestive tract composed of the stomach and intestines.

gate A protein channel in a cellular membrane that can open or close in response to chemical, electrical, or mechanical stimuli, thus controlling when substances are allowed to pass through the membrane.

general senses Senses such as touch, heat, cold, pain, vibration, and pressure, mediated by relatively simple sense organs that are distributed throughout the body. *See also* somesthetic; special senses.

genitalia The pelvic reproductive organs including the *internal genitalia* in the pelvic cavity and *external genitalia* in the perineum; most of the external genitalia are externally visible, but some are subcutaneous, between the skin and the muscles of the pelvic floor.

genitourinary (G-U) system *See* urogenital (U-G) system.

germ cell A gamete or any precursor cell destined to become a gamete.

germ layer Any of three tissue layers of an embryo: the ectoderm, mesoderm, or endoderm.

gestation (jess-TAY-shun) Pregnancy.

gland Any organ specialized for secretion or excretion; in some cases a single cell, such as a goblet cell.

glial cell (GLEE-ul, GLY-ul) Any of the six types of supporting cells of the nervous system (oligodendrocytes, astrocytes, microglia, and ependyma in the CNS; Schwann cells and satellite cells in the PNS); constitute most of the bulk of the nervous system and perform various protective and supportive roles for the neurons. Also called *neuroglia*.

glomerular capsule (glo-MERR-you-lur) A double-walled capsule around each glomerulus of the kidney; receives glomerular filtrate and empties into the proximal convoluted tubule. (fig. 25.8)

glomerulus A spheroid mass of blood capillaries in the kidney that filters plasma and produces glomerular filtrate, which is further processed to form the urine. (fig. 25.9)

glucose A monosaccharide ($C_6H_{12}O_6$) also known as blood sugar; glycogen, starch, cellulose, and maltose are made entirely of glucose, and glucose constitutes half of a sucrose or lactose molecule. The isomer involved in human physiology is also called *dextrose.*

gluteal Pertaining to the buttocks.

glycocalyx (GLY-co-CAY-licks) A layer of carbohydrate covalently bonded to the phospholipid and protein molecules of a plasma membrane; forms a surface coat on all human cells. (fig. 2.12)

glycogen A glucose polymer synthesized by liver, muscle, uterine, and vaginal cells that serves as an energy-storage polysaccharide.

glycolipid A phospholipid molecule with carbohydrate covalently bonded to it, found in the plasma membranes of cells.

glycoprotein A protein–carbohydrate complex in which the protein is dominant; found in mucus and the glycocalyx of cells, for example.

glycosaminoglycan (GAG) (GLY-cose-am-ih-no-GLY-can) A polysaccharide composed of modified sugars with amino groups; the major component of a proteoglycan. GAGs are largely responsible for the viscous consistency of tissue gel and the stiffness of cartilage.

goblet cell A mucus-secreting gland cell, shaped somewhat like a wineglass, found in the epithelia of many mucous membranes. (fig. 3.7)

Golgi complex (GOAL-jee) An organelle composed of several parallel cisternae, somewhat like a stack of saucers, that modifies and packages newly synthesized proteins and synthesizes carbohydrates. (fig. 2.19)

Golgi vesicle A membrane-bounded vesicle pinched from the Golgi complex, containing its chemical product; may be retained in the cell as a lysosome or become a secretory vesicle that releases the product by exocytosis.

gonad The ovary or testis.

gonadal ridge The earliest trace of the embryonic gonad, a streak of tissue adjacent to the kidney, populated by the first germ cells arriving from the yolk sac at 5 to 6 weeks of gestation; also called a *genital ridge.*

granulocyte (GRAN-you-lo-site) Any of three types of leukocytes (neutrophils, eosinophils, or basophils) with prominent cytoplasmic granules. (fig. 19.1)

granulosa cells Cells that form a stratified cuboidal epithelium lining an ovarian follicle; source of steroid sex hormones. (fig. 26.14)

gray matter A zone or layer of tissue in the central nervous system where the neuron cell bodies, dendrites, and synapses are found; forms the core of the spinal cord, nuclei of the brainstem, basal nuclei of the cerebrum, cerebral cortex, and cerebellar cortex. (fig. 15.4)

great toe The large medial toe; also called the *hallux.*

great vessels The largest of the blood vessels attached directly to the heart; the superior and inferior venae cavae, pulmonary trunk, and aorta.

gross anatomy Bodily structure that can be observed without magnification.

ground substance The clear, featureless material in which the fibers and cells of a connective tissue are embedded; includes the liquid plasma of the blood, tissue gel of areolar tissue, and calcified tissue of bone.

guard hairs Coarse, stiff hairs that prevent insects, debris, or other foreign matter from entering the ear, nose, or eye; also called *vibrissae.*

gustatory Pertaining to the sense of taste.

gyrus (JY-rus) A wrinkle or fold in the cortex of the cerebrum or cerebellum. (fig. 15.1)

H

hair cell A sensory cell of the cochlea, semicircular ducts, utricle, and saccule, with a fringe of surface microvilli that respond to the relative motion of a gelatinous membrane at their tips; responsible for the senses of hearing and equilibrium. (fig. 17.13)

hair follicle An oblique epithelial pit in the skin that contains a hair and extends into the dermis or hypodermis.

hair receptor Free sensory nerve endings entwined around a hair follicle, responsive to movement of the hair.

hallux The great toe; the medial digit of the foot.

haploid *(n)* Having a single set of unpaired chromosomes. In humans, the only haploid cells are germ cells past the meiosis I stage of cell division, including the mature egg and sperm.

haversian canal *See* central canal.

head **1.** The uppermost part of the human body, above the neck. **2.** The expanded end of an organ such as a bone, the pancreas, or the epididymis.

helper T cell A type of lymphocyte that performs a central coordinating role in humoral and cellular immunity; target of the human immunodeficiency virus (HIV).

hematocrit (he-MAT-oh-crit) The percentage of blood volume that is composed of erythrocytes.

hematoma (HE-muh-TOE-muh) A mass of clotted blood in the tissues; forms a bruise when visible through the skin.

hemidecussation Crossing-over of one-half of the nerve fibers in a nerve or tract to the opposite side of the central nervous system, especially at the optic chiasm. *Compare* decussation.

hemoglobin The red pigment of erythrocytes; binds and transports about 98.5% of the oxygen and 5% of the carbon dioxide carried in the blood.

hemopoiesis (HE-mo-poy-EE-sis) Production of any of the formed elements of blood.

hemopoietic tissue Any tissue in which hemopoiesis occurs, especially red bone marrow and lymphatic tissue.

hemostasis The cessation of bleeding by the mechanisms of vascular spasm, a platelet plug, and blood clotting.

hepatic Pertaining to the liver.

hepatic macrophage A macrophage found in the sinusoids of the liver; also called a *Kupffer cell.*

hepatic portal system A network of blood vessels that connect capillaries of the intestines to capillaries (sinusoids) of the liver, thus delivering newly absorbed nutrients directly to the liver.

hepatocyte Any of the cuboidal gland cells that constitute the parenchyma of the liver.

hiatus (hy-AY-tus) An opening or gap, such as the esophageal hiatus through the diaphragm.

hilum (HY-lum) A point on the surface of an organ where blood vessels, lymphatic vessels, or nerves enter and leave, usually marked by a depression and slit; the midpoint of the concave surface of any organ that is roughly bean-shaped, such as the lymph nodes, kidneys, and lungs. Also called the *hilus*. (fig. 23.9)

hindbrain The most caudal part of the brain, composed of the medulla oblongata, pons, and cerebellum. (fig. 13.14)

hindgut **1.** The most caudal part of the embryonic digestive tract; all of the tract caudal to the initial attachment of the yolk sac. (fig. 4.5) **2.** In adults, all of the digestive tract from the end of the transverse colon through the anal canal, with a blood supply and innervation separate from those of the foregut and midgut.

histological section A thin slice of tissue, usually mounted on a slide and artificially stained to make its microscopic structure more visible.

histology **1.** The microscopic structure of tissues and organs. **2.** The study of such structure.

holocrine gland An exocrine gland whose secretion is formed by the breakdown of entire gland cells; for example, a sebaceous gland.

homeostasis (HO-me-oh-STAY-sis) The tendency of a living body to maintain relatively stable internal conditions in spite of greater changes in its external environment.

homologous (ho-MOLL-oh-gus) **1.** Having the same embryonic or evolutionary origin but not necessarily the same function, such as the scrotum and labia majora. **2.** Pertaining to two chromosomes with identical structures and gene loci but not necessarily identical alleles; each member of the pair is inherited from a different parent.

hormone A chemical messenger that is secreted into the blood by an endocrine gland or isolated gland cell and triggers a physiological response in distant cells with receptors for it.

hyaline cartilage (HY-uh-lin) A form of cartilage with a relatively clear matrix and fine collagen fibers but no conspicuous elastic fibers or collagen bundles as in other types of cartilage. (fig. 3.19)

hyaluronic acid (HY-uh-loo-RON-ic) A glycosaminoglycan that is particularly abundant in connective tissues, where it becomes hydrated and forms the tissue gel.

hydrolysis (hy-DRAHL-ih-sis) A chemical reaction in which water is broken down into hydrogen and hydroxide ions and these are used to split a covalent bond in an organic molecule, for example, in digesting starch to glucose or protein to amino acids, or breaking ATP down into ADP and phosphate.

hyperextension A joint movement that increases the angle between two bones beyond 180°. (fig. 9.7)

hyperplasia (HY-pur-PLAY-zhuh) The growth of a tissue through cellular multiplication, not cellular enlargement. *Compare* hypertrophy.

hypertrophy (hy-PUR-tro-fee) The growth of a tissue through cellular enlargement, not cellular multiplication; for example, the growth of muscle under the influence of exercise. *Compare* hyperplasia.

hypoblast The layer of cells in the early embryonic disc facing away from the amniotic cavity; forms the yolk sac and is then replaced during gastrulation by migrating epiblast cells.

hypochondriac Pertaining to an area on each side of the abdomen superior to the subcostal line and lateral to the midclavicular line. (fig. 1.11)

hypodermis (HY-po-DUR-miss) A layer of connective tissue deep to the skin; also called *superficial fascia, subcutaneous tissue,* or when it is predominantly adipose, *subcutaneous fat.*

hypogastric Pertaining to a medial area of the lower abdomen inferior to the intertubercular line and medial to (between) the midclavicular lines; also called the *pubic region.* (fig. 1.11)

hypophyseal portal system A circulatory pathway that connects a capillary plexus in the hypothalamus to a capillary plexus in the anterior pituitary; carries hypothalamic releasing and inhibiting hormones to the anterior pituitary. (fig. 18.2)

hypophysis The pituitary gland.

hypothalamic thermostat A nucleus of neurons in the hypothalamus responsible for the homeostatic regulation of body temperature.

hypothalamo–hypophyseal tract A bundle of nerve fibers that begin in nuclei in the hypothalamus, travel through the pituitary stalk, and terminate in the posterior lobe of the pituitary gland. They deliver the hormones oxytocin and antidiuretic hormone to the posterior pituitary for storage, and signal the pituitary when to release them into the blood. (fig. 18.2)

hypothalamus (HY-po-THAL-uh-mus) The inferior portion of the diencephalon of the brain, forming the walls and floor of the third ventricle and giving rise to the posterior pituitary gland; controls many fundamental physiological functions such as appetite, thirst, and body temperature. (fig. 15.2)

hypothesis An informed conjecture that is capable of being tested and potentially falsified by experimentation or data collection.

hypoxemia A deficiency of oxygen in the blood.

hypoxia A deficiency of oxygen in any tissue; may lead to tissue necrosis.

I

immune system A population of cells, including leukocytes and macrophages, that occur in most organs of the body and protect against foreign organisms, some foreign chemicals, and cancerous or other aberrant host cells.

immunity The ability to ward off a specific infection or disease, usually as a result of prior exposure and the body's production of antibodies or lymphocytes against a pathogen.

implantation The process in which a conceptus attaches to the uterine endometrium and then becomes embedded in it.

inclusion Any visible object in the cytoplasm of a cell other than an organelle or cytoskeletal element; usually a foreign body or a stored cell product, such as a virus, dust particle, lipid droplet, glycogen granule, or pigment.

infarction **1.** The sudden death of tissue resulting from a loss of blood flow, often resulting from the occlusion of an artery; for example, cerebral infarction and myocardial infarction. **2.** A region of tissue that has died from lack of blood; also called an *infarct.*

inferior Lower than another structure or point of reference from the perspective of anatomical position; for example, the stomach is inferior to the diaphragm.

infundibulum (IN-fun-DIB-you-lum) Any funnel-shaped passage or structure, such as the distal portion of the uterine tube and the stalk that attaches the pituitary gland to the hypothalamus.

inguinal (IN-gwih-nul) Pertaining to the groin. (fig. 1.11)

innervation (IN-ur-VAY-shun) The nerve supply to an organ.

inspiration Inhaling.

integument The skin.

integumentary system An organ system consisting of the skin, cutaneous glands, hair, and nails.

interatrial septum The wall between the atria of the heart.

intercalated disc (in-TUR-kuh-LAY-ted) A complex of fascia adherens, gap junctions, and desmosomes that join two cardiac muscle cells end to end, microscopically visible as a dark line, which helps to histologically distinguish this muscle type; functions as a mechanical and electrical link between cells. (fig. 20.14)

intercellular Between cells.

intercellular junction *See* cell junction.

intercostal (IN-tur-COSS-tul) Between the ribs, as in the *intercostal* muscles, arteries, veins, and nerves.

interdigitate To fit together like the fingers of the folded hands; for example, at the dermal–epidermal boundary, podocytes of the kidney, and intercalated discs of the heart.

interneuron (IN-tur-NEW-ron) A neuron that is contained entirely in the central nervous system and, in the path of signal conduction, lies anywhere between an afferent pathway and an efferent pathway.

interoceptor A sensory receptor that responds to stimuli originating within the body. *Compare* exteroceptor.

interosseous membrane (IN-tur-OSS-ee-us) A fibrous membrane that connects the radius to the ulna and the tibia to the fibula along most of the shaft of each bone. (fig. 8.4)

interstitial (IN-tur-STISH-ul) **1.** Pertaining to the extracellular spaces in a tissue. **2.** Located between other structures, as in the *interstitial cells* of the testis.

interstitial fluid Fluid in the interstitial spaces of a tissue, also called *tissue fluid.*

intervertebral disc A cartilaginous pad between the bodies of two adjacent vertebrae.

intracellular Contained within a cell.

intracellular fluid (ICF) The fluid contained in the cells; one of the major fluid compartments.

intramembranous ossification A process of bone development in which there is no cartilage precursor; rather, the bone develops directly from a sheet of condensed mesenchyme. (fig. 6.7) *Compare* endochondral ossification.

intraperitoneal Within the peritoneal cavity. *Compare* retroperitoneal.

intrinsic **1.** Arising from within, such as intrinsic blood-clotting factors; endogenous. **2.** Fully contained within an organ, such as the intrinsic muscles of the hand and eye. *Compare* extrinsic.

inversion Movement of the foot that turns the sole medially. (fig. 9.17)

involuntary Not under conscious control, as in the case of the autonomic nervous system and cardiac and smooth muscle contraction.

involution Shrinkage of a tissue or organ by autolysis, such as shrinkage of the thymus after childhood and of the uterus after pregnancy.

ipsilateral (IP-sih-LAT-ur-ul) On the same side of the body, as in reflex arcs in which a muscular response occurs on the same side of the body as the stimulus. *Compare* contralateral.

ischemia A state in which the blood flow to a tissue is inadequate to meet its metabolic needs; may lead to tissue necrosis from hypoxia or waste accumulation.

isthmus A narrow zone of tissue connecting two larger masses; for example, at the front of the thyroid gland and connecting the uterine tube ampulla to the uterus.

J

joint *See* articulation.

K

keratin A tough protein formed by keratinocytes that constitutes the hair, nails, and stratum corneum of the epidermis.

keratinized Covered with keratin, such as the epidermis.

keratinocyte A cell of the epidermis that synthesizes keratin, then dies; most cells of the epidermis are keratinocytes, with dead ones constituting the stratum corneum.

Kupffer cell *See* hepatic macrophage.

kyphosis An exaggerated thoracic spinal curvature, often resulting from osteoporosis; also called *widow's hump* or *dowager's hump.*

L

labium (LAY-bee-um) A lip, such as those of the mouth and the labia majora and minora of the vulva.

lacrimal Pertaining to the tears or tear glands.

lacteal A lymphatic capillary located in the core of an intestinal villus, serving to absorb dietary lipids.

lacuna (la-CUE-nuh) A small cavity or depression in a tissue such as bone, cartilage, and the erectile tissues.

lamella A little plate or sheet of tissue, such as a lamella of bone. (fig. 6.4)

lamellar corpuscle A bulbous sensory receptor with one or a few dendrites enclosed in onionlike layers of Schwann cells; found in the dermis, mesenteries, pancreas, and some other viscera, and responsive to deep pressure, stretch, and high-frequency vibration. Also called a *pacinian corpuscle.* (fig. 17.1)

lamina (LAM-ih-nuh) A thin layer, such as the lamina of a vertebra or the lamina propria of a mucous membrane. (figs. 3.32, 7.25)

lamina propria (PRO-pree-uh) A thin layer of areolar tissue immediately deep to the epithelium of a mucous membrane. (fig. 3.32)

laryngopharynx (la-RIN-go-FAIR-inks) The portion of the pharynx formed by the union of the oropharynx and nasopharynx, beginning at the level of the hyoid bone and extending inferiorly to the opening of the esophagus. (fig. 23.2)

larynx (LAIR-inks) A cartilaginous chamber in the neck containing the vocal cords; the voicebox. (fig. 23.4)

lateral Away from the midline of an organ or median plane of the body; toward the side. *Compare* medial.

leg **1.** That part of the body between the knee and ankle; the crural region. **2.** A leglike extension of an organ. *See also* crus.

lesion A circumscribed zone of tissue injury, such as a skin abrasion or myocardial infarction.

leukocyte (LOO-co-site) Any nucleated blood cell; a neutrophil, eosinophil, basophil, lymphocyte, or monocyte. Also called a *white blood cell.* (fig. 19.1)

leukopoiesis The process of leukocyte development from hemopoietic stem cells.

libido The sex drive; a psychological desire for sex.

ligament A cord or band of tough collagenous tissue binding one organ to another, especially one bone to another, and serving to hold organs in place; for example, the cruciate ligaments of the knee and falciform ligament of the liver.

light microscope (LM) A microscope that produces images with visible light.

limb **1.** An appendage of the body arising from the shoulder or hip. *See also* lower limb; upper limb. **2.** An appendage or extension of another structure, such as the descending limb of the nephron loop.

limb bud An outgrowth of the embryo that develops into an upper or lower limb.

limbic system A ring of brain structures that encircle the corpus callosum and thalamus, including the cingulate gyrus, hippocampus, amygdala, and other structures; functions include learning and emotion. (fig. 15.15)

line **1.** Any long narrow mark. *See also* linea. **2.** An elongated, slightly raised ridge on a bone, such as the nuchal lines of the skull. (fig. 7.4)

linea (LIN-ee-uh) An anatomical line, such as the linea alba of the abdomen.

lingual (LING-wul) Pertaining to the tongue.

lipid A hydrophobic organic compound with a high ratio of hydrogen to oxygen; includes steroids, fatty acids, triglycerides (fats), phospholipids, and prostaglandins.

LM **1.** Light microscope. **2.** Light micrograph, a photograph made through the light microscope.

load **1.** To pick up oxygen or carbon dioxide for transport in the blood. **2.** The resistance acted upon by a muscle.

lobe **1.** A structural subdivision of an organ such as a gland, a lung, or the brain, bounded by a visible landmark such as a fissure or septum. **2.** The inferior, noncartilaginous, often pendant part of the ear pinna; the earlobe.

lobule (LOB-yool) A small subdivision of an organ or of a lobe of an organ, especially of a gland.

long bone A bone such as the femur or humerus that is markedly longer than wide and that generally serves as a lever.

longitudinal section (l.s.) A cut along the longest dimension of the body or of an organ. (fig. 3.2)

loose connective tissue Areolar or reticular tissue; a connective tissue that has an abundance of ground substance and widely spaced fibers and cells.

lower limb The appendage that arises from the hip, consisting of the thigh from hip to knee; the crural region from knee to ankle; the ankle; and the foot. Loosely called the leg, although that term properly refers only to the crural region.

lumbar Pertaining to the lower back and sides, between the thoracic cage and pelvis.

lumen The internal space of a hollow organ, such as a blood vessel or the esophagus, or a space surrounded by cells, as in a gland acinus.

lymph The fluid contained in lymphatic vessels and lymph nodes, produced by the absorption of tissue fluid.

lymphatic nodule A temporary, dense aggregation of lymphocytes in such places as mucous membranes and lymphatic organs; also called a *lymphatic follicle.* (fig. 22.8)

lymphatic system An organ system consisting of lymphatic vessels, lymph nodes, the tonsils, spleen, and thymus; functions include tissue fluid recovery and immunity.

lymph node A small organ found along the course of a lymphatic vessel; filters the lymph and contains lymphocytes and macrophages, which respond to antigens in the lymph. (fig. 22.11)

lymphocyte (LIM-foe-site) A relatively small leukocyte with numerous types and roles in nonspecific defense, humoral immunity, and cellular immunity. (fig. 19.1)

lysosome A membrane-bounded organelle containing a mixture of enzymes with a variety of intracellular and extracellular roles in digesting foreign matter, pathogens, and expired organelles. (fig. 2.19)

lysozyme An enzyme found in tears, milk, saliva, mucus, and other body fluids that destroys bacteria by digesting their cell walls; also called *muramidase.*

M

macrophage (MAC-ro-faje) Any cell of the body, other than a leukocyte, that is specialized for phagocytosis; usually derived from a blood monocyte and often functioning as an antigen-presenting cell.

macula (MAC-you-luh) A patch or spot, such as the macula lutea of the retina and macula sacculi of the inner ear.

magnetic resonance imaging (MRI) A method of producing a computerized image of the interior of the body using a strong magnetic field and radio waves. (fig. 1.3)

male In humans, any individual with a Y chromosome; normally, one possessing one X and one Y chromosome in each somatic cell, and having reproductive organs that serve to produce and deliver sperm.

mammary gland The milk-secreting gland that develops within the breast in pregnancy and lactation; only minimally developed in the breast of a nonpregnant or nonlactating woman.

mast cell A connective tissue cell, similar to a basophil, that secretes histamine, heparin, and other chemicals involved in inflammation; often concentrated along the course of a blood capillary.

matrix **1.** The extracellular material of a tissue. **2.** The substance or framework within which other structures are embedded, such as the fibrous matrix of a blood clot. **3.** A mass of epidermal cells from which a hair root or nail root develops. **4.** The fluid within a mitochondrion containing enzymes of the citric acid cycle.

meatus (me-AY-tus) An opening into a canal, such as an acoustic meatus.

mechanoreceptor A sensory nerve ending or organ specialized to detect mechanical stimuli such as touch, pressure, stretch, or vibration.

medial Toward the midline of an organ or median plane of the body. *Compare* lateral.

median plane The sagittal plane that divides the body or an organ into equal right and left halves; also called the *midsagittal plane.* (fig. 1.8) *Compare* sagittal plane.

mediastinum (ME-dee-ah-STY-num) The thick median partition of the thoracic cavity that separates one pleural cavity from the other and contains the heart, great blood vessels, and thymus. (fig. 1.12)

medical imaging Any of several noninvasive or minimally invasive methods for producing images of the interior of the body, including X-rays, MRI, PET, CT, and sonography.

medulla (meh-DUE-luh, meh-DULL-uh) Tissue deep to the cortex of certain organs such as the adrenal glands, lymph nodes, hairs, and kidneys.

medulla oblongata (OB-long-GAH-ta) The most caudal part of the brainstem, immediately superior to the foramen magnum of the skull, connecting the spinal cord to the rest of the brain. (fig. 15.2)

meiosis (my-OH-sis) A form of cell division in which a diploid cell divides twice and produces four haploid daughter cells; occurs only in gametogenesis.

melanin A brown or black pigment synthesized by melanocytes and some other cells; provides color to the skin, hair, eyes, and some other organs and tissues.

melanocyte A cell of the stratum basale of the epidermis that synthesizes melanin and transfers it to the keratinocytes.

meninges (meh-NIN-jeez) (singular, *meninx*) Three fibrous membranes between the central nervous system and surrounding bone: the dura mater, arachnoid mater, and pia mater. (fig. 15.3)

merocrine (MERR-oh-crin) Pertaining to gland cells that release their product by exocytosis; also called *eccrine.* (figs. 3.31, 5.10)

mesenchyme (MEZ-en-kime) A gelatinous embryonic connective tissue derived from the mesoderm; differentiates into all permanent connective tissues and most muscle.

mesentery (MEZ-en-tare-ee) A serous membrane that binds the intestines together and suspends them from the abdominal wall; the visceral continuation of the peritoneum. (figs. 1.15, 24.3)

mesocolon A dorsal mesentery that anchors parts of the colon to the abdominal wall. (fig. 24.3)

mesoderm (MEZ-oh-durm) The middle layer of the three primary germ layers of an embryo; gives rise to muscle and connective tissue.

mesonephric ducts A pair of embryonic ducts that forms in association with the temporary mesonephric kidney; they degenerate in the female, but in the male, they develop into parts of the reproductive tract. (fig. 26.22)

mesothelium (MEZ-oh-THEEL-ee-um) A simple squamous epithelium that covers the serous membranes.

metaphysis A growth zone at the junction between the diaphysis and epiphysis of a long bone, where cartilage is replaced by osseous tissue and the bone grows in length. (fig. 6.9)

metaplasia Transformation of one mature tissue type into another; for example, a change from pseudostratified columnar to stratified squamous epithelium in an overventilated nasal cavity.

metarteriole A short blood vessel that links an arteriole to a bed of blood capillaries, with no tunica media except for a smooth muscle precapillary sphincter at the opening to each capillary. (fig. 21.9)

metastasis (meh-TASS-tuh-sis) The spread of cancer cells from the original tumor to a new location, where they seed the development of a new tumor.

microfilament A thin filament of actin in the cytoskeleton of a cell, involved especially in the supportive core of a microvillus, the membrane skeleton just deep to the plasma membrane, and in muscle contraction. *See also* actin.

micrograph A photograph made with a microscope.

micrometer (µm) One-thousandth of a millimeter, or 10^{-6} meter; a convenient unit of length for expressing the sizes of cells.

microtubule An intracellular cylinder composed of the protein tubulin, forming centrioles, the axonemes of cilia and flagella, and part of the cytoskeleton.

microvillus An outgrowth of the plasma membrane that increases the surface area of a cell and functions in absorption and some sensory processes; distinguished from cilia and flagella by its smaller size and lack of an axoneme.

midbrain A short section of the brainstem between the pons and diencephalon. (fig. 15.2)

midgut **1.** The middle part of the embryonic digestive tract, located at the attachment of the yolk sac. (fig. 4.5) **2.** In adults, all of the digestive tract from the major duodenal papilla through the end of the transverse colon, with a blood supply and innervation separate from those of the foregut and hindgut.

midsagittal plane *See* median plane.

mineralization *See* calcification.

mitochondrion (MY-toe-CON-dree-un) An organelle specialized to synthesize ATP, enclosed in a double unit membrane with infoldings of the inner membrane called cristae.

mitosis A form of cell division in which a cell divides once and produces two genetically identical daughter cells; sometimes used to refer only to the division of the genetic material or nucleus and not to include cytokinesis, the subsequent division of the cytoplasm.

mixed nerve A nerve containing both afferent (sensory) and efferent (motor) nerve fibers.

monocyte A leukocyte specialized to migrate into the tissues and transform into a macrophage. (fig. 19.1)

monozygotic (MZ) twins Two individuals that develop from the same zygote and are therefore genetically identical.

morphology Anatomy, especially as interpreted from a functional perspective.

morula A preembryonic stage of development consisting of 16 or more identical-looking cells having a bumpy surface appearance reminiscent of a mulberry. The morula develops into a blastocyst and then implants on the uterine wall.

motor neuron A neuron that transmits signals from the central nervous system to any effector (muscle or gland cell); also called an *efferent neuron.* The axon of a motor neuron is an *efferent nerve fiber.*

motor protein Any protein that produces movements of a cell or its components owing to its ability to undergo quick repetitive changes in conformation and to bind reversibly to other molecules; for example, myosin, dynein, and kinesin.

motor unit One motor neuron and all the skeletal muscle fibers innervated by it.

mouth **1.** A narrow opening into any cavity or hollow organ. **2.** The oral (buccal) cavity, bordered by the lips, cheeks, and fauces.

MRI *See* magnetic resonance imaging.

mucosa (mew-CO-suh) A tissue layer that forms the inner lining of an anatomical tract that is open to the exterior (the respiratory, digestive, urinary, and reproductive tracts). Composed of epithelium, connective tissue (lamina propria), and often smooth muscle (muscularis mucosae). Also called a *mucous membrane.* (fig. 3.32)

mucosa-associated lymphatic tissue (MALT) Aggregations of lymphocytes, including lymphatic nodules, in the mucous membranes.

mucous gland A gland that secretes mucus, such as the glands of the large intestine and nasal cavity. *Compare* serous gland.

mucous membrane *See* mucosa.

mucus A viscous, slimy or sticky secretion produced by mucous cells and mucous membranes and consisting of a hydrated glycoprotein, mucin; serves to bind particles together, such as bits of masticated food, and to protect the mucous membranes from infection and abrasion.

multipotent Pertaining to a stem cell that is capable of differentiating into multiple, but not unlimited, adult cell types; for example, bone marrow colony-forming units that can produce multiple types of leukocytes.

muscle fiber One skeletal muscle cell. *Compare* myocyte.

muscularis externa The external muscular wall of certain viscera such as the esophagus and small intestine. (fig. 24.2)

muscularis mucosae (MUSS-cue-LERR-iss mew-CO-see) A layer of smooth muscle immediately deep to the lamina propria of a mucosa. (fig. 3.32)

muscular system An organ system composed of the skeletal muscles, specialized mainly for maintaining postural support and producing movements of the bones. Cardiac and smooth muscle are not regarded as part of the muscular system.

muscular tissue A tissue composed of elongated, electrically excitable cells specialized for contraction; the three types are skeletal, cardiac, and smooth muscle.

mutagen (MEW-tuh-jen) Any agent that causes a mutation, including viruses, chemicals, and ionizing radiation.

mutation Any change in the structure of a chromosome or a DNA molecule, often resulting in a change of organismal structure or function.

myelin (MY-eh-lin) A lipid sheath around a nerve fiber, formed from closely spaced spiral layers of the plasma membrane of an oligodendrocyte or Schwann cell. (fig. 13.7)

myelination The process in which an oligodendrocyte or Schwann cell deposits myelin around a nerve fiber.

myeloid tissue Bone marrow.

myenteric plexus A plexus of parasympathetic neurons located between the layers of the muscularis externa of the digestive tract; controls peristalsis.

myocardium The middle, muscular layer of the heart.

myocyte A muscle cell, especially a cell of cardiac or smooth muscle. *Compare* muscle fiber.

myoepithelial cell An epithelial cell that has become specialized to contract like a muscle cell; important in dilation of the pupil and ejection of secretions from gland acini.

myofibril (MY-oh-FY-bril) A bundle of myofilaments forming an internal subdivision of a cardiac or skeletal muscle cell. (fig. 10.8)

myofilament A protein microfilament responsible for the contraction of a muscle cell, composed mainly of myosin or actin. (fig. 10.9)

myosin A motor protein that constitutes the thick myofilaments of muscle and has globular, mobile heads of ATPase that bind to actin molecules.

myotome A group of mesodermal cells that arise from a somite in the fourth week of development and give rise to body wall muscles in that region of the trunk of the body. *Compare* dermatome; sclerotome.

N

nasal concha One of three curved or scroll-like plates of bone and mucous membrane that extends from the lateral wall toward the septum in each nasal fossa; serves to warm, cleanse, and humidify inhaled air. (fig. 23.2)

nasal septum A wall of bone and cartilage that separates the right and left nasal fossae.

nasopharynx That region of the pharynx that lies caudal to the nasal choanae and posterior or superior to the soft palate. (fig. 23.2)

natural killer (NK) cell A lymphocyte that attacks and destroys cancerous or infected cells of the body without requiring prior exposure or a specific immune response; one of the body's nonspecific defenses.

necrosis (neh-CRO-sis) Pathological tissue death due to such causes as infection, trauma, or hypoxia. *Compare* apoptosis.

neonate An infant up to 4 weeks old.

neoplasia (NEE-oh-PLAY-zee-uh) Abnormal growth of new tissue, such as a tumor, with no useful function.

nephron One of approximately 1.2 million blood-filtering, urine-producing units in each kidney; consists of a glomerulus, glomerular capsule, proximal convoluted tubule, nephron loop, and distal convoluted tubule. (fig. 25.6) *Compare* renal tubule.

nerve A cordlike organ of the peripheral nervous system composed of multiple nerve fibers ensheathed in connective tissue.

nerve fiber The axon of a single neuron.

nerve impulse A wave of self-propagating action potentials spreading along a nerve fiber; the nerve signal.

nervous system An organ system composed of the brain, spinal cord, nerves, and ganglia, specialized for rapid communication of information.

nervous tissue A tissue composed of neurons and neuroglia.

neural circuit A group of interconnected neurons that conduct signals along defined pathways to produce a sustained, repetitive, convergent, or divergent output. (fig. 13.12)

neural crest A mass of ectoderm that begins at the edges of the neural groove, then separates from the neural tube and gives rise primarily to nerves, ganglia, and the adrenal medulla. (fig. 13.13)

neural groove A longitudinal depression in the ectoderm of the embryo that closes up to form the neural tube, forerunner of the central nervous system. (fig. 13.13)

neural pool A group of interconnected neurons of the central nervous system that perform a single collective function; for example, the vasomotor center of the brainstem and speech centers of the cerebral cortex.

neural tube A dorsal hollow ectodermal tube in the embryo that develops into the central nervous system. (fig. 13.13)

neuroglia (noo-ROG-lee-uh) All cells of nervous tissue except neurons; cells that perform various supportive and protective roles for the neurons.

neurohypophysis The posterior one-third of the pituitary gland, consisting of the posterior lobe, a stalk that attaches the pituitary to the hypothalamus, and the median eminence of the hypothalamic floor; stores and secretes antidiuretic hormone and oxytocin. (fig. 18.2)

neuromuscular junction (NMJ) A synapse between a nerve fiber and a muscle cell. (fig. 10.11)

neuron (NOOR-on) A nerve cell; an electrically excitable cell specialized for producing and transmitting action potentials and secreting chemicals that stimulate adjacent cells. (fig. 13.4)

neurosoma The cell body of a neuron, containing the nucleus and usually giving rise to the axon and dendrites; also called the *soma* or *perikaryon.* (fig. 13.4)

neurotransmitter A chemical released at the distal end of an axon that stimulates an adjacent cell; for example, acetylcholine, norepinephrine, and serotonin.

neutrophil (NOO-tro-fill) A leukocyte, usually with a multilobed nucleus, that serves especially to destroy bacteria by means of phagocytosis, intracellular digestion, and secretion of bactericidal chemicals. (fig. 19.1)

nitrogenous waste Any nitrogen-containing substance produced as a metabolic waste and excreted in the urine; chiefly ammonia, urea, uric acid, and creatinine.

nociceptor (NO-sih-SEP-tur) A nerve ending specialized to detect tissue damage and produce a sensation of pain; pain receptor.

node of Ranvier A gap between adjacent segments of myelin in a myelinated nerve fiber; the point where action potentials are generated in a myelinated fiber.

nonkeratinized Pertaining to a stratified squamous epithelium that lacks a surface layer of dead compacted keratinocytes; found in the oral cavity, pharynx, esophagus, anal canal, and vagina.

notochord A middorsal supportive rod that develops in all chordate embryos, including humans; represented in the adult only by the nuclei of the intervertebral discs.

nuchal Pertaining to the back of the neck.

nuclear envelope (NEW-clee-ur) A pair of unit membranes enclosing the nucleus of a cell, with prominent pores allowing traffic of molecules between the nucleoplasm and cytoplasm. (fig. 2.19)

nuclear medicine Any use of radioisotopes to treat disease or form diagnostic images of the body.

nucleus (NEW-clee-us) **1.** A cell organelle containing DNA and surrounded by a double unit membrane. **2.** A mass of neurons (gray matter) surrounded by white matter of the brain, including the basal nuclei and brainstem nuclei. **3.** A central structure, such as the nucleus pulposus of an intervertebral disc or nucleus of an atom.

nucleus pulposus The gelatinous center of an intervertebral disc.

O

oblique section A cut through an elongated organ on a slant, between a longitudinal and a cross section. (fig. 3.2)

occlusion **1.** Meeting of the surfaces of the teeth when one bites. **2.** Obstruction of an anatomical passageway, such as blockage of an artery by a thrombus or atherosclerotic plaque.

olfactory Pertaining to the sense of smell.

omentum A ventral mesentery that extends from the stomach to the liver *(lesser omentum)* or is suspended from the greater curvature of the stomach and overhangs the intestines *(greater omentum).* (fig. 24.3)

oocyte (OH-oh-site) In the development of an egg cell, a haploid stage between meiosis I and fertilization.

oogenesis (OH-oh-JEN-eh-sis) The production of a fertilizable egg cell through a series of mitotic and meiotic cell divisions; female gametogenesis.

ophthalmic (off-THAL-mic) Pertaining to the eye or vision; optic.

opposition A movement of the thumb in which it approaches or touches any fingertip of the same hand. (fig. 9.16)

optic Pertaining to the eye or vision.

optic chiasm An X-shaped point at the base of the brain, immediately rostral to the hypothalamus, where the two optic nerves meet and continue as optic tracts.

oral cavity The space enclosed by the lips anteriorly, the cheeks laterally, and the fauces posteriorly; also called the *buccal cavity.*

orbit The eye socket of the skull.

organ Any anatomical structure that is composed of at least two different tissue types, has recognizable structural boundaries, and has a discrete function different from the structures around it. Many organs are microscopic, and many organs contain smaller organs, such as the skin containing numerous microscopic sense organs.

organelle Any structure within a cell that carries out one of its metabolic roles, such as mitochondria, centrioles, endoplasmic reticulum, and the nucleus; an intracellular structure other than the cytoskeleton and inclusions.

organism Any living individual; the entire body of any living thing such as a bacterium, plant, or human.

organogenesis The prenatal developmental process in which embryonic germ layers differentiate into specific organs and organ systems; the process that converts an embryo to a fetus, occurring between day 16 and the end of week 8 of gestation.

organ system Any of 11 systems of interconnected or physiologically interrelated organs that perform one of the body's basic functions; for example, the digestive, urinary, and respiratory systems.

oropharynx That part of the pharynx that is caudal to the fauces at the rear of the oral cavity, and anterior or inferior to the soft palate. (fig. 23.2)

osmoreceptor (OZ-mo-re-SEP-tur) A neuron of the hypothalamus that responds to changes in the osmolarity of the extracellular fluid.

osmosis The diffusion of water through a selectively permeable membrane from the side with less concentrated solutes to the side with more concentrated solutes.

osseous (OSS-ee-us) Pertaining to bone.

ossification (OSS-ih-fih-CAY-shun) Bone formation; also called *osteogenesis. See also* endochondral ossification; intramembranous ossification.

osteoarthritis (OA) A chronic degenerative joint disease characterized by loss of articular cartilage, growth of bone spurs, and impaired movement; occurs to various degrees in almost all people with age.

osteoblast A bone-forming cell that arises from an osteogenic cell, deposits bone matrix, and eventually becomes an osteocyte.

osteoclast A macrophage of the bone surface that dissolves the matrix and returns minerals to the extracellular fluid.

osteocyte A mature bone cell formed when an osteoblast becomes surrounded by its own matrix and entrapped in a lacuna.

osteogenesis *See* ossification.

osteon A structural unit of compact bone consisting of a central canal surrounded by concentric cylindrical lamellae of matrix. (fig. 6.4)

osteoporosis (OSS-tee-oh-pore-OH-sis) A degenerative bone disease characterized by a loss of bone mass, increasing susceptibility to spontaneous fractures, and sometimes deformity of the vertebral column; causes include aging, estrogen hyposecretion, and insufficient resistance exercise.

ovary The female gonad; produces eggs, estrogen, and progesterone.

oviduct *See* uterine tube.

ovulation The release of a mature oocyte by the bursting of an ovarian follicle.

ovum Any stage of the female gamete from the conclusion of meiosis I until fertilization; a primary oocyte; an egg.

P

pacinian corpuscle *See* lamellated corpuscle.

palate A horizontal partition between the oral and nasal cavities.

palatine Pertaining to the palate, such as palatine bones and tonsils.

palmar region The anterior surface (palm) of the hand.

pancreas A gland of the upper abdominal cavity, near the stomach, that secretes digestive enzymes and sodium bicarbonate into the duodenum and secretes hormones into the blood.

pancreatic islets (PAN-cree-AT-ic EYE-lets) Small clusters of endocrine cells in the pancreas that secrete insulin, glucagon, somatostatin, and other intercellular messengers; also called *islets of Langerhans.* (fig. 18.9)

papilla (pa-PILL-uh) A conical or nipplelike structure, such as a lingual papilla of the tongue or the papilla of a hair bulb.

papillary (PAP-ih-lerr-ee) **1.** Pertaining to or shaped like a nipple, such as the papillary muscles of the heart. **2.** Having papillae, such as the papillary layer of the dermis.

paramesonephric ducts A pair of embryonic ducts that forms beside the mesonephric ducts; they degenerate in the male; in the female, they form the uterine tubes, uterus, and part of the vagina. (fig. 26.22)

parasympathetic nervous system (PERR-uh-SIM-pa-THET-ic) A division of the autonomic nervous system that issues efferent fibers through the cranial and sacral nerves and exerts cholinergic effects on its target organs. (fig. 16.7)

parathyroid glands (PERR-uh-THY-royd) Small endocrine glands, usually four in number, adhering to the posterior side of the thyroid gland. (fig. 18.7)

parenchyma (pa-REN-kih-muh) The tissue that performs the main physiological functions of an organ, especially a gland, as opposed to the tissues (stroma) that mainly provide structural support.

parietal (pa-RY-eh-tul) **1.** Pertaining to a wall, as in the *parietal cells* of the gastric glands and *parietal bone* of the skull. **2.** The outer or more superficial layer of a two-layered membrane such as the pleura, pericardium, or glomerular capsule. (fig. 1.13) *Compare* visceral.

pathogen Any disease-causing microorganism.

pectoral Pertaining to the chest.

pectoral girdle The circle of bones that connect the upper limb to the axial skeleton; composed of the two scapulae and the two clavicles.

pedal region The foot.

pedicel *See* pedicle.

pedicle (PED-ih-cul) A small footlike process, as in the vertebrae and the renal podocytes; also called a *pedicel.* (fig. 7.22)

pelvic cavity The space enclosed by the true (lesser) pelvis, containing the urinary bladder, rectum, and internal reproductive organs. (fig. 1.12)

pelvic girdle A ring of three bones—the two hip (coxal) bones and the sacrum—that attaches the lower limbs to the axial skeleton. *See also* pelvis. (fig. 8.6)

pelvis **1.** A basinlike cradle composed of the pelvic girdle and its associated ligaments and muscles, forming the walls and floor of the lower abdominal and pelvic cavities. **2.** A basinlike structure such as the renal pelvis of the kidney. (fig. 25.3)

perfusion Loosely, blood flow to any tissue or organ. More specifically, the volume of blood received by a given mass of tissue in a given unit of time, such as milliliters per gram per minute.

pericardial cavity A narrow space between the parietal and visceral layers of the pericardium, containing pericardial fluid.

pericardium A two-layered serous membrane that folds around the heart. Its visceral layer forms the heart surface *(epicardium),* and its parietal layer forms a fibrous *pericardial sac* around the heart. (fig. 20.4)

perichondrium (PERR-ih-CON-dree-um) A layer of fibrous connective tissue covering the surface of hyaline or elastic cartilage. (fig. 3.19)

perineum (PERR-ih-NEE-um) The region between the thighs bordered by the coccyx, pubic symphysis, and ischial tuberosities; contains the orifices of the urinary, reproductive, and digestive systems. (figs. 26.2, 26.20)

periosteum (PERR-ee-OSS-tee-um) A layer of fibrous connective tissue covering the surface of a bone. (fig. 6.4)

peripheral Away from the center of the body or of an organ, as in *peripheral vision* and *peripheral blood vessels;* opposite of central.

peripheral nervous system (PNS) A subdivision of the nervous system composed of all nerves and ganglia; all of the nervous system except the central nervous system. *Compare* central nervous system.

peristalsis (PERR-ih-STAL-sis) A wave of constriction traveling along a tubular organ such as the esophagus or ureter, serving to propel its contents.

peritoneum (PERR-ih-toe-NEE-um) A serous membrane that lines the peritoneal cavity of the abdomen and covers the mesenteries and viscera.

perivascular (PERR-ih-VASS-cue-lur) Pertaining to the region surrounding a blood vessel.

peroxisome An organelle composed of a unit membrane enclosing a mixture of enzymes; serves to detoxify free radicals, alcohol, and other drugs, and to break down fatty acids; named for the hydrogen peroxide that it generates in the course of these activities.

PET *See* positron emission tomography.

phagocytosis (FAG-oh-sy-TOE-sis) A form of endocytosis in which a cell surrounds a foreign particle with pseudopods and engulfs it, enclosing it in a cytoplasmic vesicle called a phagosome. (fig. 2.11)

pharyngeal arch One of five pairs of bulbous swellings in the pharyngeal region of an embryo. (fig. 4.7)

pharyngeal pouch One of six pairs of outpocketings of the pharynx between and adjacent to the pharyngeal arches of an embryo; these form gill slits in fishes and amphibians but in humans give rise to such structures as the middle-ear cavities, palatine tonsils, thymus, parathyroid glands, and C cells of the thyroid gland. (fig. 4.7)

pharynx (FAIR-inks) A muscular passage in the throat at which the respiratory and digestive tracts cross. (fig. 23.2)

phospholipid A lipid composed of a hydrophilic head with a phosphate group and a nitrogenous group such as choline, and two hydrophobic fatty acid tails; especially important as the most numerous molecules of the plasma membrane and other unit membranes of a cell, but also involved in emulsification of dietary fat and as a component of pulmonary surfactant. (fig. 2.7)

photoreceptor Any cell or organ specialized to absorb light and generate a nerve signal; the eye and its rods, cones, and some of its ganglion cells.

phrenic (FREN-ic) **1.** Pertaining to the diaphragm, as in *phrenic nerve.* **2.** Pertaining to the mind, as in *schizophrenic.*

physiology **1.** The functional processes of the body. **2.** The study of such function.

piloerector A bundle of smooth muscle cells associated with a hair follicle, responsible for erection of the hair; also called *arrector pili.* (fig. 5.6)

pineal gland (PIN-ee-ul) A small conical endocrine gland arising from the roof of the third ventricle of the brain; produces melatonin and serotonin and may be involved in mood and timing the onset of puberty. (fig. 15.2)

pinocytosis A form of endocytosis in which the plasma membrane sinks in and internalizes a droplet of extracellular fluid in a pinocytotic vesicle. (fig. 2.11)

pituitary gland (pih-TOO-ih-terr-ee) An endocrine gland suspended from the hypothalamus and housed in the sella turcica of the sphenoid bone; secretes numerous hormones, most of which regulate the activities of other glands. (fig. 18.2)

placenta (pla-SEN-tuh) A thick discoid organ on the wall of the pregnant uterus, composed of a combination of maternal and fetal tissues, serving multiple functions in pregnancy including gas, nutrient, and waste exchange between mother and fetus. (fig. 4.10)

plantar (PLAN-tur) Pertaining to the sole of the foot.

plantar flexion A movement of the ankle that points the toes downward, as in pressing on the gas pedal of a car or standing on tiptoes. (fig. 9.17)

plaque A small scale or plate of matter, such as dental plaque, the fatty plaques of atherosclerosis, and the amyloid plaques of Alzheimer disease.

plasma The noncellular portion of the blood.

plasma cell A connective tissue cell that differentiates from a B lymphocyte and secretes antibodies. (fig. 22.16)

plasma membrane The unit membrane that encloses a cell and controls the traffic of molecules into and out of it. (fig. 2.6)

platelet A formed element of the blood derived from the peripheral cytoplasm of a megakaryocyte, known especially for its roles in stopping bleeding but also serves in dissolving blood clots, stimulating inflammation, and promoting tissue growth. (fig. 19.9)

pleura (PLOOR-uh) A two-layered serous membrane that folds around the lung. Its visceral layer forms the lung surface, and its parietal layer lines the inside of the rib cage. (fig. 23.12)

pleural cavity A narrow space between the parietal and visceral layers of the pleura, containing pleural fluid. (fig. 23.12)

plexus A network of blood vessels, lymphatic vessels, or nerves, such as a choroid plexus of the brain or the brachial plexus of nerves. (fig. 14.14)

pluripotent Pertaining to an embryonic stem cell from the morula that is capable of producing any type of embryonic or adult cell. More loosely, describing certain adult stem cells with an especially broad developmental potential, able to produce a wide variety of differentiated cell types. *See also* pluripotent stem cell.

pluripotent stem cell (PPSC) A stem cell of the bone marrow that can produce any of the formed elements of blood.

pollex The thumb.

pons The section of the brainstem between the midbrain and medulla oblongata.

popliteal (po-LIT-ee-ul) Pertaining to the posterior aspect of the knee.

portal system A circulatory pathway in which blood passes through two capillary beds in series in a single trip from the heart and back. (fig. 21.12)

positron emission tomography (PET) A method of producing a computerized image of the physiological state of a tissue using injected radioisotopes that emit positrons. (fig. 1.3)

posterior 1. Pertaining to the back aspect of the human body; also called *dorsal,* especially in embryos. 2. Pertaining to the tail end of nonhuman animals.

posterior nasal aperture The opening at the posterior limit of each nasal fossa, where air from the nasal cavity enters the pharynx; also called a *choana* or *posterior naris.* (fig. 23.2)

posterior root A branch of a spinal nerve that joins the spinal cord on its posterior side, composed of sensory nerve fibers; also called the *dorsal root.* (fig. 14.10)

posterior root ganglion A swelling in the posterior root of a spinal nerve, near the spinal cord, containing the neurosomas of the afferent neurons of the nerve; also called the *dorsal root ganglion*. (fig. 14.10)

postganglionic Pertaining to a neuron that transmits signals from a ganglion to a more distal target organ. (fig. 16.2)

postsynaptic Pertaining to a neuron or other cell that receives signals from the presynaptic neuron at a synapse. (fig. 13.10)

potential space An anatomical space that is usually obliterated by contact between two membranes but opens up if air, fluid, or other matter comes between them. Examples include the pleural cavity and the lumen of the uterus.

preembryo A developing human that has not yet formed ectoderm, mesoderm, and endoderm; when those germ layers have formed, the individual is regarded as an embryo. *Compare* conceptus; embryo.

preembryonic stage Any stage of prenatal development from fertilization through 16 days, when the primary germ layers exist and the embryonic stage begins.

preganglionic Pertaining to a neuron that transmits signals from the central nervous system to a ganglion. (fig. 16.2)

prepuce A fold of tissue over the glans of the penis or clitoris; the penile foreskin or clitoral hood.

presynaptic Pertaining to a neuron that transmits signals to a synapse. (fig. 13.10)

presynaptic terminal The swollen tip at the distal end of an axon; the site of synaptic vesicles and neurotransmitter release. (fig. 13.11)

prime mover The muscle primarily responsible for a given joint action; agonist.

process An outgrowth of bone or other tissue, such as the mastoid process of the skull.

programmed cell death (PCD) *See* apoptosis.

projection pathway The route taken by nerve signals from their point of origin (such as a sense organ) to their point of termination (such as the primary sensory cortex). (fig. 17.15)

pronation A rotational movement of the forearm that turns the palm downward or posteriorly. (fig. 9.13)

prone A position in which the body is lying face down.

proprioception (PRO-pree-oh-SEP-shun) The nonvisual perception, usually subconscious, of the position and movements of the body, resulting from input from proprioceptors and the vestibular apparatus of the inner ear.

proprioceptor (PRO-pree-oh-SEP-tur) A sensory receptor of the muscles, tendons, and joint capsules that detects muscle contractions and joint movements.

prostate gland (PROSS-tate) A male reproductive gland that encircles the urethra immediately inferior to the bladder and contributes to the semen. (fig. 26.1)

protein A polypeptide of 50 amino acids or more.

proteoglycan A protein–carbohydrate complex in which the carbohydrate is dominant; forms a gel that binds cells and tissues together, fills the umbilical cord and eye, lubricates the joints, and forms the rubbery texture of cartilage. Formerly called *mucopolysaccharide.*

protraction Forward movement of a body part in the horizontal plane, such as moving the mandible forward in preparation to take a bite from an apple. (fig. 9.15)

protuberance A bony outgrowth or protruding part, such as the mental protuberance of the mandible.

proximal Relatively near a point of origin or attachment; for example, the shoulder is proximal to the elbow. *Compare* distal.

pseudopod (SOO-doe-pod) A temporary cytoplasmic extension of a cell used for locomotion (ameboid movement) and phagocytosis.

pseudostratified columnar epithelium An epithelium in which every cell contacts the basement membrane, but not all of them reach the free surface, thus giving an appearance of stratification. (fig. 3.7)

pubic Concerning the region of the genitalia. *See also* hypogastric.

pudendum *See* vulva.

pulmonary Pertaining to the lungs.

pulmonary circuit A route of blood flow that supplies blood to the pulmonary alveoli for gas exchange and then returns it to the heart; all blood vessels between the right ventricle and the left atrium of the heart. (fig. 21.13)

R

radiography The use of X-rays to form an image of the interior of the body. (fig. 1.3)

radiology The branch of medicine concerned with producing images of the interior of the body, using such methods as X-rays, sonography, MRI, CT, and PET.

ramus (RAY-mus) An anatomical branch, as in a nerve or in the pubis.

receptive field An area of the environment or of an epithelial surface from which a given neuron receives sensory information. (fig. 17.2)

receptor **1.** A cell or organ specialized to detect a stimulus, such as a taste cell or the eye. **2.** A protein molecule that binds and responds to a chemical such as a hormone, neurotransmitter, or odor molecule.

receptor-mediated endocytosis A mode of vesicular transport in which cell surface receptors bind a specific molecule in the extracellular fluid, then cluster together to be internalized by the cell. (fig. 2.11)

rectus Straight; used in muscle names such as *rectus femoris* and *rectus abdominis.*

reflected Folded back or away from something, often to expose another structure in anatomical demonstrations. (fig. 9.24)

reflex A stereotyped, automatic, involuntary response to a stimulus; includes somatic reflexes, in which the effectors are skeletal muscles, and visceral (autonomic) reflexes, in which the effectors are usually visceral muscle, cardiac muscle, or glands.

reflex arc A simple neural pathway that mediates a reflex; involves a receptor, an afferent nerve fiber, sometimes one or more interneurons, an efferent nerve fiber, and an effector. (fig. 14.19)

regeneration Replacement of damaged tissue with new tissue of the original type. *Compare* fibrosis.

renal (REE-nul) Pertaining to the kidney.

renal tubule A urine-forming duct that converts glomerular filtrate to urine by processes of reabsorption and secretion of water and solutes. Consists of the proximal convoluted tubule, nephron loop, and distal convoluted tubule of an individual nephron, plus a collecting duct and papillary duct shared by multiple nephrons. (fig. 25.6) *Compare* nephron.

renin An enzyme produced by the kidney that converts angiotensinogen to angiotensin I, the first step in producing the vasoconstrictor angiotensin II.

reproductive system An organ system specialized for the production of offspring.

resistance **1.** Opposition to the flow of fluid, such as blood in a vessel or air in a bronchiole. **2.** Opposition to the movement of a joint; the load against which a muscle works. **3.** A nonspecific ability to ward off an infection or disease, as opposed to the pathogen-specific defense provided by immunity.

respiratory system An organ system specialized for the intake of air and exchange of gases with the blood, consisting of the lungs and the air passages from the nose to the bronchi.

reticular cell (reh-TIC-you-lur) A delicate, branching cell in the reticular connective tissue of the lymphatic organs.

reticular fiber A fine, branching collagen fiber coated with glycoprotein, found in the stroma of lymphatic organs and some other tissues and organs.

reticular tissue A connective tissue composed of reticular cells and reticular fibers, found in bone marrow, lymphatic organs, and in lesser amounts elsewhere. (fig. 3.15)

retraction Movement of a body part posteriorly on the horizontal plane; for example, retracting the mandible to grind food between the molars. (fig. 9.15)

retroperitoneal Located between the peritoneum and body wall, rather than in the peritoneal cavity; descriptive of certain abdominal viscera such as the kidneys, ureters, and pancreas. (fig. 1.14) *Compare* intraperitoneal.

ribosome A granule found free in the cytoplasm or attached to the rough endoplasmic reticulum and nuclear envelope, composed of ribosomal RNA and enzymes; specialized to read the nucleotide sequence of messenger RNA and assemble a corresponding sequence of amino acids to make a protein.

risk factor Any environmental factor or characteristic of an individual that increases one's chance of developing a particular disease; includes such intrinsic factors as age, sex, and race and such extrinsic factors as diet, smoking, and occupation.

root **1.** Part of an organ that is embedded in other tissue and therefore not externally visible, such as the root of a tooth, a hair, or the penis. *Compare* shaft. **2.** The proximal end of a spinal nerve, adjacent to the spinal cord.

rostral Relatively close to the forehead, especially in reference to structures of the brain and spinal cord; for example, the frontal lobe is rostral to the parietal lobe. *Compare* caudal.

rotation Movement of a body part such as the humerus or forearm around its longitudinal axis. (fig. 9.14)

rough endoplasmic reticulum Regions of endoplasmic reticulum characterized by flattened, parallel cisternae externally studded with ribosomes; involved in making proteins for export from the cell, among other functions. *See also* endoplasmic reticulum; smooth endoplasmic reticulum. (fig. 2.19)

ruga (ROO-ga) **1.** An internal fold or wrinkle in the mucosa of a hollow organ such as the stomach and urinary bladder; typically present when the organ is empty and relaxed but not when the organ is full and stretched. **2.** A tissue ridge in such locations as the hard palate and vagina. (fig. 24.11)

S

sagittal plane (SADJ-ih-tul) Any plane that extends from anterior to posterior and cephalic to caudal, and divides the body into right and left portions. (fig. 1.8) *Compare* median plane.

sarcomere (SAR-co-meer) In skeletal and cardiac muscle, the portion of a myofibril from one Z disc to the next, constituting one contractile unit. (fig. 10.10)

sarcoplasmic reticulum (SR) The smooth endoplasmic reticulum of a muscle cell, serving as a calcium reservoir. (fig. 10.8)

satellite cell **1.** A type of glial cell found surrounding the somas of neurons in ganglia of the peripheral nervous system. **2.** Stem cells of skeletal muscle that can multiply in response to muscle injury and contribute to some extent to regeneration of muscle fibers.

scanning electron microscope (SEM) A microscope that uses an electron beam in place of light to form high-resolution, three-dimensional images of the surfaces of objects; capable of much higher magnifications than a light microscope. *Compare* transmission electron microscope.

Schwann cell A glial cell that forms the neurilemma around all peripheral nerve fibers and the myelin sheath around many of them; also encloses neuromuscular junctions; also called a *neurilemmocyte*. (fig. 13.4)

sclerosis (scleh-RO-sis) Hardening or stiffening of a tissue, usually with scar tissue, as in *multiple sclerosis* of the central nervous system and *atherosclerosis* of the blood vessels.

sclerotome A group of mesodermal cells that arise from a somite in the fourth week of development and give rise to a segment of the vertebral column. *Compare* dermatome; myotome.

sebaceous gland A holocrine gland that is usually associated with a hair follicle and produces an oily secretion, sebum. (fig. 5.10)

sebum (SEE-bum) An oily secretion of the sebaceous glands that keeps the skin and hair pliable.

secondary sex characteristic Any feature that develops at puberty, further distinguishes the sexes from each other, and is not required for reproduction but promotes attraction between the sexes; examples include the distribution of subcutaneous fat, pitch of the voice, female breasts, male facial hair, and apocrine scent glands.

secondary sex organ An organ other than the ovaries and testes that is essential to reproduction, such as the external genitalia, internal genital ducts, and accessory reproductive glands.

second-order neuron An interneuron that receives sensory signals from a first-order neuron and relays them to a more rostral destination in the central nervous system (usually the thalamus). (fig. 14.4) *See also* first-order neuron; third-order neuron.

secretion **1.** A chemical released by a cell to serve a physiological function, such as a hormone or digestive enzyme, as opposed to a waste product. **2.** The process of releasing such a chemical, usually by exocytosis. *Compare* excretion.

secretory vesicle An organelle that arises from the Golgi complex and carries a secretion to the cell surface to be released by exocytosis.

section *See* histological section.

selection pressure A force of nature that favors the reproduction of some individuals over others and thus drives the evolutionary process; includes climate, predators, diseases, competition, and food supply. Human anatomy and physiology reflect adaptations to selection pressures encountered in the evolutionary history of the species.

SEM **1.** Scanning electron microscope. **2.** Scanning electron micrograph, a photograph taken with the scanning electron microscope. *Compare* TEM.

semen The fluid ejaculated by a male, including spermatozoa and the secretions of the prostate gland and seminal vesicles.

semicircular duct A ring-shaped, fluid-filled tube of the inner ear that detects angular acceleration of the head; enclosed in a bony passage called the semicircular canal. There are three semicircular ducts in each ear. (fig. 17.11)

semilunar valve A valve that consists of crescent-shaped cusps, including the aortic and pulmonary valves of the heart and valves of the veins and lymphatic vessels. (fig. 20.7)

sense organ Any organ that is specialized to respond to stimuli and generate a meaningful pattern of nerve signals; may be microscopic and simple, such as a tactile corpuscle, or macroscopic and complex, such as the eye or ear; may respond to stimuli arising within the body or from external sources.

sensory neuron A nerve cell that responds to a stimulus and conducts signals to the central nervous system; also called an *afferent neuron*. The axon of a sensory neuron is an *afferent nerve fiber.*

septum An anatomical wall between two structures or spaces, such as the nasal septum or the interventricular septum of the heart.

serosa *See* serous membrane.

serous fluid (SEER-us) A watery fluid similar to blood serum, formed as a filtrate of the blood or tissue fluid or as a secretion of serous gland cells; moistens the serous membranes.

serous gland A gland that secretes a relatively nonviscous product, such as the pancreas or a tear gland. *Compare* mucous gland.

serous membrane A membrane such as the peritoneum, pleura, or pericardium that lines a body cavity or covers the external surfaces of the viscera; composed of a simple squamous mesothelium and a thin layer of areolar connective tissue. (fig. 3.32)

Sertoli cell *See* sustentacular cell.

serum **1.** The fluid that remains after blood has clotted and the solids have been removed; essentially the same as blood plasma except for a lack of fibrinogen. Used as a vehicle for vaccines. **2.** Serous fluid.

sex chromosomes The X and Y chromosomes, which determine the sex of an individual.

shaft **1.** The midpart, or diaphysis, of a long bone. **2.** The external, cylindrical part of an organ such as a hair or the penis. *Compare* root.

short bone A bone that is not markedly longer than it is wide, such as the bones of the wrist and ankle.

sign An objective indication of disease that can be verified by any observor, such as cyanosis or a skin lesion. *Compare* symptom.

simple columnar epithelium An epithelium composed of a single layer of cells that are noticeably taller than they are wide. (fig. 3.6)

simple cuboidal epithelium An epithelium composed of a single layer of cells that are about equal in height and width; often, but not always, the cells appear squarish in tissue sections. (fig. 3.5)

simple diffusion Net movement of particles from a place of high concentration to a place of low concentration (down their concentration gradient), resulting from their own spontaneous motion; may or may not involve passage through a cell membrane or other membranes such as dialysis tubing.

simple squamous epithelium An epithelium composed of a single layer of thin, flat cells. (fig. 3.4)

sinoatrial (SA) node A mass of autorhythmic cells near the surface of the right atrium of the heart that serves as the pacemaker of the cardiac rhythm.

sinus **1.** An air-filled space in the cranium. (fig. 7.8) **2.** A modified, relatively dilated vein that lacks smooth muscle and is incapable of vasomotion, such as the dural sinuses of the cerebral circulation and coronary sinus of the heart. **3.** A small fluid-filled space in an organ such as the lymph nodes. **4.** Pertaining to the sinoatrial node of the heart, as in *sinus rhythm.*

sinusoid An irregularly shaped, blood-filled space in a tissue, with wide gaps between the endothelial cells; found in the liver, bone marrow, spleen, and some other organs. (fig. 22.9)

skeletal muscle Striated voluntary muscle, almost all of which is attached to the bones. (fig. 10.1)

skeletal system An organ system consisting of the bones, ligaments, bone marrow, periosteum, articular cartilages, and other tissues associated with the bones.

smear A tissue prepared for microscopic study by wiping it across a slide, rather than by sectioning; for example, blood, bone marrow, spinal cord, and Pap smears.

smooth endoplasmic reticulum Regions of endoplasmic reticulum characterized by tubular, branching cisternae lacking ribosomes; involved in detoxification, steroid synthesis, and in muscle, storage of calcium ions. *See also* endoplasmic reticulum; rough endoplasmic reticulum. (fig. 2.19)

smooth muscle Nonstriated involuntary muscle found in the walls of the blood vessels, many of the viscera, and other places. (fig. 3.27)

sodium–potassium pump An active transport protein, which, in each cycle of activity, pumps three sodium ions out of a cell and two potassium ions into the cell, with the expenditure of one ATP.

soma *See* cell body.

somatic **1.** Pertaining to the body as a whole. **2.** Pertaining to the skin, bones, and skeletal muscles as opposed to the viscera. **3.** Pertaining to all cells other than germ cells.

somatic motor fiber A nerve fiber that innervates skeletal muscle and stimulates its contraction, as opposed to autonomic fibers.

somatic nervous system A division of the nervous system that includes afferent fibers mainly from the skin, muscles, and skeleton and efferent fibers to the skeletal muscles. *Compare* autonomic nervous system.

somatosensory **1.** Pertaining to widely distributed general senses in the skin, muscles, tendons, joint capsules, and viscera, as opposed to the *special senses* found in the head only; also called *somesthetic.* **2.** Pertaining to the cerebral cortex of the postcentral gyrus, which receives input from such receptors. *See also* general senses; special senses.

somatotopy A point-for-point correspondence between the locations where stimuli arise and locations in the brain or spinal cord to which the sensory signals project, thus producing in the CNS a sensory "map" of part of the body. (fig. 15.18)

somesthetic *See* somatosensory.

somite One of the segmental blocks of embryonic mesoderm that begin to appear around day 20 and eventually number up to 44 pairs; a somite subdivides into three tissue masses—dermatome, myotome, and sclerotome, which give rise to certain aspects of the skin, muscles, and vertebrae. *See also* dermatome; myotome; sclerotome. (fig. 4.11)

sonography Production of an image of the interior of the body by means of ultrasound. (fig. 1.4)

special senses The senses of taste, smell, hearing, equilibrium, and vision, mediated by sense organs that are confined to the head and in most cases are relatively complex in structure. *See also* general senses.

sperm **1.** A spermatozoon. **2.** The fluid ejaculated by the male; semen. Contains spermatozoa and glandular secretions.

spermatogenesis (SPUR-ma-toe-JEN-eh-sis) The production of sperm cells through a series of mitotic and meiotic cell divisions; male gametogenesis.

spermatozoon (SPUR-ma-toe-ZOE-on) A sperm cell; the male gamete. (fig. 26.8)

sphincter (SFINK-tur) A ring of muscle that opens or closes an opening or passageway; found, for example, in the eyelids, around the urinary orifice, and at the junction of the stomach and duodenum. (fig. 24.11)

spinal column *See* vertebral column.

spinal cord The nerve cord that passes through the vertebral column and constitutes all of the central nervous system except the brain.

spinal nerve Any of the 31 pairs of nerves that arise from the spinal cord and pass through the intervertebral foramina. (fig. 14.10)

spindle **1.** An elongated structure that is thick in the middle and tapered at the ends (fusiform). **2.** A football-shaped complex of microtubules that guide the movement of chromosomes in mitosis and meiosis. (fig. 2.23) **3.** A stretch receptor in the skeletal muscles. (fig. 17.1)

spine **1.** The vertebral column. **2.** A pointed process or sharp ridge on a bone, such as the styloid process of the cranium and spine of the scapula. (fig. 8.2)

spinothalamic tract A bundle of nerve fibers that ascend the spinal cord and brainstem and carry signals to the thalamus for light touch, tickle, itch, heat, cold, pain, and pressure. (fig. 14.4)

splanchnic (SPLANK-nic) Pertaining to the digestive tract.

spongy bone A form of osseous tissue found in the interiors of flat, irregular, and short bones and the epiphyses of long bones, with a matrix that forms a porous network of plates and bars, enclosing connected channels filled with bone marrow; also called *cancellous bone. Compare* compact bone. (fig. 6.4)

squamous Flat, scalelike, as in the surface epithelial cells of the epidermis and serous membranes. (figs. 2.3, 3.12)

stain A pigment applied to tissues to color and enhance the contrast between their nuclei, cytoplasm, extracellular material, and other tissue components.

stem cell Any undifferentiated cell that can divide and differentiate into more functionally specific cell types such as blood cells and germ cells.

stenosis The pathological constriction or narrowing of a tubular passageway or orifice of the body, such as the esophagus, uterine tube, or a valve orifice of the heart.

stereocilium An unusually long, sometimes branched microvillus lacking the axoneme and motility of a true cilium; serves such roles as absorption in the epididymis and sensory transduction in the inner ear.

sternal Pertaining to the breastbone or sternum, or the overlying region of the chest.

stimulus A chemical or physical agent in a cell's surroundings that is capable of creating a physiological response in the cell, especially agents detected by sensory cells, such as chemicals, light, and pressure.

strain The extent to which a bone or other structure is deformed when subjected to stress. *Compare* stress.

stratified **1.** Layered. **2.** A class of epithelia in which there are two or more cell layers, with some cells resting atop others rather than contacting the basement membrane.

stratified cuboidal epithelium An epithelium composed of two or more layers of cells in which the cells at the surface are about equal in height and width. (fig. 3.10)

stratified squamous epithelium An epithelium composed of two or more layers of cells in which the cells at the surface are flat and thin. (fig. 3.9)

stratum Any layer of tissue, such as the stratum corneum of the skin or stratum basalis of the uterus.

stratum corneum The surface layer of dead keratinocytes of the skin. (fig. 5.1)

stress **1.** A mechanical force applied to any part of the body; important in stimulating bone growth, for example. *Compare* strain. **2.** A condition in which any environmental influence disturbs the homeostatic equilibrium of the body and stimulates a physiological response, especially involving the increased secretion of hormones of the pituitary–adrenal axis.

striated muscle Muscular tissue in which the cells exhibit striations; skeletal and cardiac muscle. *See also* striations.

striations Alternating light and dark bands in skeletal and cardiac muscle produced by the pattern of overlapping myofilaments. (fig. 10.1)

stroma The connective tissue framework of a gland, lymphatic organ, or certain other viscera, as opposed to the tissue (parenchyma) that performs the physiological functions of the organ.

subcutaneous Beneath the skin.

submucosa A layer of loose connective tissue deep to the mucosa of an organ. (fig. 24.2)

submucosal plexus A plexus of parasympathetic neurons in the submucosa of the digestive tract, responsible for controlling glandular secretion by the mucosa and movements of the muscularis mucosae.

sulcus A groove in the surface of an organ, as in the cerebrum, the heart, or a bone. (fig. 15.1)

superficial Relatively close to the surface; opposite of *deep.* For example, the ribs are superficial to the lungs.

superior Higher than another structure or point of reference from the perspective of anatomical position; for example, the lungs are superior to the diaphragm.

supination (SOO-pih-NAY-shun) A rotational movement of the forearm that turns the palm so that it faces upward or forward. (fig. 9.13)

supine A position in which the body is lying face up.

suprarenal Pertaining to the adrenal (suprarenal) glands, as in *suprarenal artery.*

surfactant A chemical that interferes with the formation of hydrogen bonds between water molecules, and thus reduces the cohesion of water; in the lung, a mixture of phospholipid and protein that prevents the alveoli from collapsing during expiration.

sustentacular cell **1.** A cell in the wall of a seminiferous tubule of the testis that supports and protects the germ cells and secretes the hormone inhibin; also called a *Sertoli cell.* (fig. 26.6) **2.** In many epithelia, such as taste buds and olfactory mucosa, any cell that supports and spaces the primary functional cells of the tissue; also called a *supporting cell.* (fig. 17.5)

suture A line along which any two bones of the skull are immovably joined, such as the coronal suture between the frontal and parietal bones. (fig. 7.6)

sympathetic nervous system A division of the autonomic nervous system that issues efferent fibers through the thoracic and lumbar nerves and usually exerts adrenergic effects on its target organs; includes a chain of paravertebral ganglia adjacent to the vertebral column, and the adrenal medulla. (fig. 16.4)

symphysis (SIM-fih-sis) A joint in which two bones are held together by fibrocartilage; for example, between bodies of the vertebrae and between the right and left pubic bones. (fig. 8.6)

symptom A subjective indication of disease that can be felt by the person who is ill but not objectively observed by another person, such as nausea or headache. *Compare* sign.

synapse (SIN-aps) **1.** A junction at the end of an axon where it stimulates another cell. (fig. 13.11) **2.** A gap junction between two cardiac or smooth muscle cells at which one cell electrically stimulates the other; called an *electrical synapse.*

synaptic cleft A narrow space between the presynaptic terminal of an axon and the adjacent cell, across which a neurotransmitter diffuses. (fig. 13.11)

synaptic vesicle A spheroidal organelle in a presynaptic terminal; contains neurotransmitter. (fig. 13.11)

syndrome A group of signs and symptoms that occur together and characterize a particular disease.

synergist (SIN-ur-jist) A muscle that works with the agonist to contribute to the same overall action at a joint.

synovial fluid (sih-NO-vee-ul) A lubricating fluid similar to egg white in consistency, found in the synovial joint cavities and bursae.

synovial joint A point where two bones are separated by a narrow, encapsulated space filled with lubricating synovial fluid; most such joints are relatively mobile. Also called a *diarthrosis.* (fig. 9.4)

systemic Widespread or pertaining to the body as a whole, as in *systemic circulation.*

systemic circuit All blood vessels that convey blood from the left ventricle to all organs of the body and back to the right atrium of the heart; all of the cardiovascular system except the heart and pulmonary circuit. (fig. 20.1)

T

TA *See Terminologia Anatomica*.

tactile Pertaining to the sense of touch.

tail **1.** A slender process at one end of an organ, such as the tail of the pancreas or epididymis. (fig. 24.19) **2.** In vertebrate animals, an appendage that extends beyond the anus and contains part of the vertebral column; in humans, limited to the embryo. (fig. 4.11)

target cell A cell acted upon by a nerve fiber or by a chemical messenger such as a hormone.

tarsal **1.** Pertaining to the ankle. **2.** Pertaining to the margin of the eyelid.

TEM **1.** Transmission electron microscope. **2.** Transmission electron micrograph, a photograph taken with the transmission electron microscope. *Compare* SEM.

temporal **1.** Pertaining to time, as in *temporal summation* in neurons. **2.** Pertaining to the side of the head, as in *temporal bone.*

tendinous cords Fibers that extend from the papillary muscles to the atrioventricular valve cusps in each ventricle of the heart, and serve to keep the valves from prolapsing during ventricular systole; also called *chordae tendineae.* (fig. 20.7)

tendon A collagenous band or cord associated with a muscle, usually attaching it to a bone and transferring muscular tension to it. *See also* aponeurosis.

teratogen Any agent capable of causing birth defects, including chemicals, infectious microorganisms, and radiation.

teres (TERR-eez) Round, cylindrical; used in the names of muscles and ligaments such as *teres major* and *ligamentum teres.*

Terminologia Anatomica A code of standard anatomical terms developed by an international committee of anatomists, the Federative Committee on Anatomical Terminology, and published in 1998; provides a worldwide standard for naming human structures.

testis The male gonad; produces spermatozoa and testosterone.

thalamus (THAL-uh-muss) The largest part of the diencephalon, located immediately inferior to the corpus callosum and bulging into each lateral ventricle; a point of synaptic relay of nearly all signals passing from lower levels of the CNS to the cerebrum. (fig. 15.11)

theory An explanatory statement, or set of statements, that concisely summarizes the state of knowledge on a phenomenon and provides direction for further study; for example, the fluid-mosaic theory of the plasma membrane and the sliding filament theory of muscle contraction.

thermoreceptor A neuron specialized to respond to heat or cold, found in the skin and mucous membranes, for example.

third-order neuron An interneuron of the brain that receives sensory signals from a second-order neuron (often at the thalamus) and usually relays them to their final destination in the primary sensory cortex of the brain; in a few cases, a fourth-order neuron completes the pathway. (fig. 14.4) *See also* first-order neuron; second-order neuron.

thoracic Pertaining to the chest.

thorax A region of the trunk between the neck and the diaphragm; the chest.

thymus A lymphatic organ in the mediastinum superior to the heart; the site where T lymphocytes differentiate and become immunocompetent. (fig. 18.5)

thyroid cartilage A large shieldlike cartilage that encloses the larynx anteriorly and laterally and provides an anterior anchorage for the vocal cords and insertion for the infrahyoid muscles. (fig. 23.4)

thyroid gland An endocrine gland in the neck, partially encircling the trachea immediately inferior to the larynx. (fig. 18.6)

tight junction A zipperlike junction between epithelial cells that limits the passage of substances between them. (fig. 2.15)

tissue An aggregation of cells and extracellular materials, usually forming part of an organ and performing some discrete function for it; the four primary classes are epithelial, connective, muscular, and nervous tissue.

tissue gel The viscous colloid that forms the ground substance of many tissues; gets its consistency from hyaluronic acid or other glycosaminoglycans.

T lymphocyte A type of lymphocyte involved in nonspecific defense, humoral immunity, and cellular immunity; occurs in several forms including helper, cytotoxic, and suppressor T cells; also called a *T cell.*

trabecula (tra-BEC-you-la) A thin plate or sheet of tissue, such as the calcified trabeculae of spongy bone or the fibrous trabeculae that subdivide a gland. (fig. 6.4)

trachea (TRAY-kee-uh) A cartilage-supported tube from the inferior end of the larynx to the origin of the primary bronchi; conveys air to and from the lungs; the “windpipe.”

tract **1.** In the central nervous system, a bundle of nerve fibers with a similar origin, destination, and function, such as the corticospinal tracts of the spinal cord and commissural tracts of the cerebrum. **2.** A continuous anatomical pathway such as the digestive tract.

transitional epithelium A stratified epithelium of the urinary tract that is capable of changing thickness and number of cell layers from relaxed to stretched states. (fig. 3.11)

transmembrane protein A protein of the plasma membrane that penetrates all the way through the membrane and contacts the intracellular and extracellular fluids. (fig. 2.8)

transmission electron microscope (TEM) A microscope that uses an electron beam in place of light to form high-resolution, two-dimensional images of ultrathin slices of cells or tissues; capable of extremely high magnification. *Compare* scanning electron microscope.

transport protein *See* carrier.

transverse plane A plane that cuts perpendicular to the long axis of an organ or passes horizontally through a human body in anatomical position. (fig. 1.8)

transverse section *See* cross section.

transverse (T) tubule A tubular extension of the plasma membrane of a muscle cell that conducts action potentials into the sarcoplasm and excites the sarcoplasmic reticulum. (fig. 10.8)

trauma Physical injury caused by external forces such as falls, gunshot wounds, motor vehicle accidents, or burns.

trisomy-21 The presence of three copies of chromosome 21 instead of the usual two; causes variable degrees of mental retardation, a shortened life expectancy, and structural anomalies of the face and hands. Also called *Down syndrome*.

trochanter Either of two massive processes serving for muscle attachment at the proximal end of the femur.

trunk **1.** That part of the body excluding the head, neck, and limbs. **2.** A major blood vessel, lymphatic vessel, or nerve that gives rise to smaller branches; for example, the pulmonary trunk and spinal nerve trunks. (fig. 14.14)

T tubule *See* transverse tubule.

tubercle A rounded process on a bone, such as the greater tubercle of the humerus.

tuberosity A rough area on a bone, such as the tibial or ischial tuberosity.

tubuloacinar gland A gland in which secretory cells are found in both the tubular and acinar portions. (fig. 3.30)

tunic A layer that encircles or encloses an organ, such as the tunics of a blood vessel or eyeball; also called a *tunica*. (fig. 21.1)

tympanic membrane The eardrum.

U

ultrastructure Structure at or near the molecular level, made visible by the transmission electron microscope.

umbilical (um-BIL-ih-cul) **1.** Pertaining to the cord that connects a fetus to the placenta. **2.** Pertaining to the navel (umbilicus).

undifferentiated Pertaining to a cell or tissue that has not yet attained a mature functional form; capable of differentiating into one or more specialized functional cells or tissues; for example, stem cells and embryonic tissues.

unencapsulated nerve ending *See* free nerve ending.

unipotent Pertaining to a stem cell that is capable of differentiating into only one type of mature cell, such as a spermatogonium able to produce only sperm, or an epidermal basal cell able to produce only keratinocytes.

unit membrane Any cellular membrane composed of a bilayer of phospholipids and embedded proteins. A single unit membrane forms the plasma membrane and encloses many organelles of a cell, whereas double unit membranes enclose the nucleus and mitochondria. (fig. 2.6)

unmyelinated Lacking a myelin sheath. (fig. 13.7)

upper limb The appendage that arises from the shoulder, consisting of the brachium from shoulder to elbow, the antebrachium from elbow to wrist, the wrist, and the hand; loosely called the *arm,* but that term properly refers only to the brachium.

urea The most abundant nitrogenous waste in urine, formed in the liver by a reaction between ammonia and carbon dioxide.

urethra The passage that conveys urine from the urinary bladder to the outside of the body; in males, it also conveys semen and acts as part of both the urinary and reproductive tracts.

urinary system An organ system specialized to filter the blood plasma, excrete waste products from it, and regulate the body's water, acid–base, and electrolyte balance.

urogenital (U-G) system Collective term for the reproductive and urinary tracts; also called the *genitourinary (G-U) system.*

uterine tube A duct that extends from the ovary to the uterus and conveys an egg or conceptus to the uterus; also called the *fallopian tube* or *oviduct.*

V

varicose vein A vein that has become permanently distended and convoluted due to a loss of competence of the venous valves; especially common in the lower limb, esophagus, and anal canal (where they are called *hemorrhoids*).

vas (vass) (plural, *vasa*) A vessel or duct.

vascular Possessing or pertaining to blood vessels.

vasoconstriction (VAY-zo-con-STRIC-shun) The narrowing of a blood vessel due to muscular constriction of its tunica media.

vasodilation (VAY-zo-dy-LAY-shun) The widening of a blood vessel due to relaxation of the muscle of its tunica media and the outward pressure of the blood exerted against the wall.

vasomotion Any constriction or dilation of a blood vessel.

vein Any blood vessel that carries blood toward either atrium of the heart.

ventral *See* anterior.

ventral root *See* anterior root.

ventricle A fluid-filled chamber of the brain or heart. (figs. 15.4, 20.7)

venule (VEN-yool) The smallest type of vein, receiving drainage from capillaries.

vertebra (VUR-teh-bra) One of the bones of the vertebral column.

vertebral column (VUR-teh-brul) A posterior series of usually 33 vertebrae; encloses the spinal cord, supports the skull and thoracic cage, and provides attachment for the limbs and postural muscles. Also called the *spine* or *spinal column.*

vesicle **1.** A fluid-filled tissue sac such as the seminal vesicle. **2.** A fluid-filled spheroidal organelle such as a synaptic or secretory vesicle.

vestibular apparatus Structures of the inner ear concerned with equilibrium and the perception of the movements and orientation of the head, including the semicircular ducts, utricle, and saccule.

vestibule An anatomical receiving chamber; for example, the vestibule between the teeth and cheek, the space immediately inside the nostril, the space enclosed by the female labia majora, and the chamber of the inner ear to which the cochlea and semicircular ducts are attached.

viscera (VISS-er-uh) (singular, *viscus*) The organs contained in the body cavities, such as the brain, heart, lungs, stomach, intestines, and kidneys.

visceral **1.** Pertaining to the viscera. **2.** The inner or deeper layer of a two-layered membrane such as the pleura, pericardium, or glomerular capsule. (fig. 1.13) *Compare* parietal.

visceral muscle Single-unit smooth muscle found in the walls of blood vessels and the digestive, respiratory, urinary, and reproductive tracts.

volar Pertaining to the anterior surfaces of the fingers (the surfaces continuous with the palmar skin).

voluntary Under conscious control, as in skeletal muscle.

vulva The female external genitalia; the mons pubis, labia majora, and all superficial structures between the labia majora; also called the *pudendum.* (fig. 26.20)

W

white matter White myelinated nervous tissue deep to the cortex of the cerebrum and cerebellum and superficial to the gray matter of the spinal cord. (fig. 15.4)

X

X chromosome The larger of the two sex chromosomes; males have one X chromosome and females have two in each somatic cell.

xiphoid process (ZIFF-oyd, ZYE-foyd) A small pointed cartilaginous or bony process at the inferior end of the sternum. (fig. 7.27)

X-ray **1.** A high-energy, penetrating electromagnetic ray with wavelengths in the range of 0.1 to 10 nm; used in diagnosis and therapy. **2.** A photograph made with X-rays; radiograph.

Y

Y chromosome The smaller of the two sex chromosomes, found only in males and having little if any genetic function except development of the testis.

yolk sac An embryonic membrane that encloses the yolk in vertebrates that lay eggs and serves in humans as the origin of the first blood and germ cells. (fig. 4.5)

Z

zygomatic arch An arch of bone anterior to the ear, formed by the zygomatic processes of the temporal, frontal, and zygomatic bones; origin of the masseter muscle. (fig. 7.5)

zygote A single-celled, fertilized egg.

Key to Pronunciation Guides

Pronounce letter sequences in the pronunciation guides as follows:

ah	as in father
al	as in pal
ay	as in day
bry	as in bribe
byu	as in bureau
c	as in calculus
cue	as in ridiculous
cuh	as in cousin
cul	as in bicycle
cus	as in custard
dew	as in dual
eez	as in ease
eh	as in feather
err	as in merry
fal	as in fallacy
few	as in fuse
ih	as in fit
iss	as in sister
lerr	as in lair
lur	as in learn
ma	as in man
mah	as in mama
me	as in meat
merr	as in merry
mew	as in music
muh	as in mother
na	as in corona
nerr	as in nary
new	as in news
nuh	as in nothing
odj	as in dodger
oe	as in go
oh	as in home
ol	as in alcohol
oll	as in doll
ose	as in gross
oss	as in floss
perr	as in pair
pew	as in pewter
ruh	as in rugby
serr	as in serration
sterr	as in stereo
sy	as in siren
terr	as in terrain
thee	as in theme
tirr	as in tyranny
uh	as in mother
ul	as in bicycle
verr	as in very
y	as in why
zh	as in measure
zy	as in enzyme

INDEX

A

- A bands (striated muscle), *246,* 246–247
- ABCD rule, melanoma recognition, 126
- Abdomen
  - anatomy, *338*
  - transverse section, *341*
- Abdominal cavity, *341*
  - serous membranes, 17, *19*
    - Abdominal region, 13, 15–16, *15–16, 335–338*
  - arteries, *584–586,* 584*t*–587*t*
  - vein(s), *588–589,* 588*t*–589*t*
    - Abdominopelvic cavity, 17–18
- Abduction, 214, *215*
  - hand and fingers, *218,* 219
- ABO blood types, 525–526, *526*
- Abortion, spontaneous, 100, 734*t*
- Abruptio placentae, 95, 734*t*
- Absorption atelectasis, 643
- Acceleration, vestibular apparatus, 475–478, *476–478*
- Accesory organs, 116–120, 654–655, *655*
- Accessory glands
  - digestive system, 673
  - male reproductive system, 713
- Accessory pancreatic duct, 677
- Acetabular labrum, 224, *225*
- Acetabulum, 190, *191–192*
- Acetylcholine (ACh), 362–363, *363*
  - autonomic nervous system, 454, *454,* 454*t*
  - neuromuscular junction, *248,* 249
- Achalasia, 457*t*
- Achilles tendon, 198, *198,* 316*t, 318*
- Acholic feces, 673
- Achondroplastic dwarfism, 143
- ACh receptors, 249
- Acid-base balance, 631
- Acidophils, pituitary gland, 500, *501–502,* 502–503, 503*t, 504*
- Acid phosphatase, 713
- Acinar cells, 677, *677*
- Acinar glands, *75,* 76
- Acinus, 76
- Acoustic meatus
  - external, *470–471*
  - internal, 161, *433–434*
- Acromial end (clavicle), 185, *185*
- Acromioclavicular joint, *173,* 185
- Acromion, 186, *186, 338–339, 344*
- Acrosomal reaction, 86, *86*
- Acrosome, 86
- Acrosome, spermatozoon, 711, *712*
- Actin, myofilaments, 245, *245*
- Action, of muscles, 240, 264
- Action potential, 354, *355*
- Active transport, *34,* 35
- Acute glomerulonephritis, 700*t*
- Acute pancreatitis, 680*t*
- Acute rhinitis, 650*t*
- Adaptive immunity, 530
- Adduction, 214, *215*
- Adenohypophysis, 500, *501–502,* 502–503, 503*t, 504*
- Adhesive glycoproteins, 64
- Adipocytes, 63, 67–68, 68*t*
- Adipose tissue, 67–68, *68,* 68*t*
  - breast, *726*
  - endocrine cells in, 510
  - parathyroid gland, *507*
  - renal sinus, 687, *688*
- Adolescence, 731
- Adrenal cortex, 449–450, *459,* 507–508, *508,* 511*t*
  - hormones, *504*
  - prenatal development, 514, *514*
- Adrenal glands, *336,* 449–450, *459, 499,* 507–508, *508,* 514, *514, 685*
  - disorders, 515, 516*t*
  - prenatal development, 514, *514*
  - sympathetic nervous system, 449–450, *459*
- Adrenal medulla, 449–450, *459,* 507, *508,* 511*t*
  - development, 457
  - prenatal development, 514, *514*
- Adrenergic fibers, 454, *454,* 454*t*
- Adrenergic receptors, 454, *454,* 454*t*
- Adrenocorticotropic hormone, *501,* 502, 503*t, 504*
- Adult respiratory distress syndrome (ARDS), 648, 650*t*
- Adult stem (AS) cells, 50
- Adventitia, 638–639, *638–639,* 655
- Aerobic respiration, 46
- Afferent nerve fibers, 381, 381*t*, 392
- Afferent pathways, 411, *412*
- Ageusia, 493*t*
- Aging
  - autonomic nervous system, 456–457
  - central nervous system, 437–438
  - digestive system, 678, 680
  - endocrine system, 514
  - heart, 558–559
  - hematology, 534
  - integumentary system, 125
  - muscular system, 258
  - reproductive system, 731
  - respiratory system, 649
  - skeletal system and, 144
  - urinary system, 698, 700
  - vascular system, 603
- Agonist muscle, 240
- Agranulocytes, 521, *521,* 522*t*, 527
- AIDS (acquired immunodeficiency syndrome), 733
- Air embolism, 579
- Ala nasi, *331,* 633–634, *634–635*
- Albinism, 115
- Albumin, plasma, 522, 522*t*
- Aldosterone, 508, 511*t*
- Allantoic duct, *94,* 95, *680*
- Allantois, 92–95, *94, 679*
- Alopecia, 119
- Alpha cells, 509, *509*
- Alpha globulins, 522, 522*t*
- Alveolar ducts, 640, *641*
- Alveolar macrophages, 530, 641, *642*
- Alveolar sacs, *642*
  - pulmonary circuit, *573*
- Alveoli (pulmonary), 641, *642*
- Alveolus, 76, 164
  - teeth, 660–661, *660–661*
- Alzheimer disease (AD), 438–439, 438*t, 439*
- Amacrine cells, *487,* 488
- Amelia, 201–202, *202,* 202*t*
- Amenorrhea, 734*t*
- Amino acid metabolism, 674*t*
- Amnion, 92–95, *94*
- Amniotic cavity, 88, *90, 679*
- Amphiarthrosis, 208, *209*
- Amphimixis, *86,* 87
- Ampullae, *472,* 478, *478, 676,* 676–677
  - ductus deferens, *706–707,* 712
  - female reproductive tract, *718*
  - uterine tube, 721
- Amygdala, 418, *418, 420,* 423
  - olfactory projection pathways, 470, *470*
- Amylin, 509, *509,* 511*t*
- Amyotrophic lateral sclerosis (ALS), 380, *380*
- Anagen phase, hair cycle, 119, *119*
- Anal canal, *342, 655,* 671, *672*
- Anal columns, 671, *672*
- Anal sphincter, internal and external, 671, *672*
- Anal triangle, 287*t, 288*
  - male, *707*
- Anaphase
  - meiosis, *710*
  - mitosis, 48, *49*
- Anastomosis, 571–572, *572*
  - circulatory routes, 571–572, *572*
- Anatomical dead space, 640
- Anatomical neck (humerus), 186–187, *187*
- Anatomical planes of reference, 12, *12*
- Anatomical position, 9, *12*
- Anatomical quadrants, 15, *15*
- Anatomical regions, 13–16, *14, 15*
- Anatomical snuff box, 306*t, 345*
- Anatomy, 1–22
  - bone(s), 153, *154,* 154*t*
  - directional terms, 12–13, 13*t*
  - regional, 330
  - skeletal muscle, 237–244
  - structural hierarchy, 8, *8*
  - surface, 330
  - synovial joints, 220–230
  - systems approach, 330
  - variation in, 6, *7*
- Anaxonic neurons, *356,* 357
- Anconeus muscle, 301*t, 302*
- Androgen-binding protein, 707
- Androgens, 508, *508,* 511*t*
- Andropause, 731
- Androstenedione, 508
- Anemia, 534, 535*t*
- Anencephaly, 368
- Aneuploidy, 100
- Aneurysms, 566, *566*
- Angioblasts, 601, *601*
- Angiogenesis, 601
- Angiotensin II, 510
- Angiotensinogen, 510, 512*t*
- Angle
  - mandible, 165, *165*
  - nasofacial, *635*
  - ribs, 174, *174, 338*
- Angular gyrus, *420,* 423
- Ankle
  - bones of, 197–199, *198*
  - joints, *228,* 228–229, 229*t*
- Ankylosis, 230–231, *230–232,* 231*t*
- Anococcygeal ligament, 287*t, 288*
- Anovulation, 731
- Antagonist muscle, 240–241
- Antebrachial region, 16
- Antebrachium, 186
- Anterior arch, 169–170, *170*
- Anterior border layer, 483
- Anterior chamber, 482–484, *482–484*
- Anterior cruciate ligament, 228
- Anterior longitudinal ligament, 179–180, *180*
- Anterior mesentery, 18, *19*
- Anterior spinal tracts, 375, *376,* 376*t,* 378, *379*
- Anterior tubercle, 169–170, *170*
- Anterolateral system, 378, *407–408,* 409
- Antibodies, blood types, 526
- Antidiuretic hormone, 415, 503, 503*t, 504,* 695
- Antigen-presenting cells (APCs), 530
- Antigens, blood types, 526
- Antihelix, *470–471*
- Antitragus, *470–471*
- Antral follicles, *719,* 720
- Antrum, 664, *665–666,* 667, 667*t*
  - oogenesis, *719,* 720
- Anular ligament, *223,* 224
- Anulus fibrosus, 169, *169*
- Anus, *342, 655*
  - female, *725*
  - male, *707*
  - prenatal development, *729*
- Aorta, *340–341, 546, 549*
  - abdominal, *336, 337, 584–585,* 584*t, 685, 687*
  - aneurysm, 566, *566*
  - ascending, *542, 576,* 576*t*
  - descending, *576,* 576*t, 581*
  - female reproductive tract, *722*
  - histology, *565*
  - lower limb, *595–596*
  - mesenteric, *584*
  - prenatal development, 601, *601–602*
  - respiratory system, *647*
  - systemic circuit, 541, *574, 576,* 576*t*
  - thoracic, *336–337, 576,* 576*t, 581–582,* 581*t*–582*t*

Aortic arch, *335, 542, 559, 567, 574, 576,* 576*t*–578*t, 577–578*
  prenatal development, 601, *601*
  thoracic region, *581*
Aortic bodies, 567, *567, 647*
Aortic hiatus, *576, 581,* 581*t, 584*
Aortic sac, 601, *601–602*
Aortic valve, 546, *546–547*
Apex
  lung, *640*
  nasal, *635*
Aphasias, 423
Apocrine glands, 120–121, *121*
  prenatal development, 124, *124*
Apocrine secretion, 78
Aponeurosis, 239–240, *240*
  abdominal wall, 281*t*–283*t*
Apoptosis, 46, 80–81
Appendages, accesory organs, 116–120
Appendicitis, 680*t*
Appendicular region, 16
  muscle system, 293–325
  systemic circuit, 590–600
Appendicular skeleton, 152–153, 153*t,* 184–202
  anatomical clinical and biological perspectives, 199–200, *199–200*
  development, 200–201, *201*
  pathology, 201–202, *202,* 202*t*
  pectoral girdle and lower limb, 190–199
  pectoral girdle and upper limb, 185–190
Appendix, *335, 584, 655,* 671, *672*
Appositional growth, bone widening and thickening, 143
Aquaporins, 34
Aqueous humor, *483,* 483–484
Arachnoid granulations, 404
Arachnoid mater, 374, *374, 400,* 403
Arachnoid membrane, 374, *374*
Arbor vitae, 410, *411–412*
Arches of foot, 199–200, *199–200*
Areola, breast, *338,* 725–726, *726*
Areolar glands, 725–726, *726*
Areolar tissue, 64, *65,* 65*t,* 67
Arm
  bones of, 185–190
  muscles of, 297*t*–300*t, 298–300*
Arm buds, 92, *97*
Arrector pili, 118
Arterial anastomoses, 551, 571–572, *572*
Arterial pressure points, 600, *600*
Arteries, 96, 601, *601–602*
  abdominal region, *584–586,* 584*t*–587*t*
  accessory renal, 698
  arcuate, 594*t, 595–596,* 687, *688–689, 722,* 723
  arm, 590*t*–591*t, 591*
  auricular, 576*t*–578*t, 577–578,* 577*t*–578*t*
  axillary, *335, 574,* 576*t*–578*t, 577–578,* 582*t,* 590*t*–591*t, 591*
  basilar, *578*
  brachial, *335, 574,* 590*t*–591*t, 591*
  brachiocephalic, *338, 574, 576,* 576*t,* 576*t*–578*t, 577–578*
  bronchial, *581,* 581*t*
  carotid, *334, 338, 444,* 567, *567, 574, 576,* 576*t,* 576*t*–578*t, 577–578, 581, 591,* 591*t,* 601, *601, 647*
  cerebellar, *577–578,* 577*t*–578*t*
  cerebral, *577–578,* 577*t*–578*t*
  circumflex femoral, 594*t, 595–596*
  circumflex humeral, 590*t*–591*t, 591*
  classification, 565–567, *566–567*
  colic, *586,* 586*t*
  communicating, *577–578,* 577*t*–578*t*
  conducting, 566–567
  coronary, *576*
  cortical radiate, 594*t, 595–596,* 687, *688–689*
  cystic, 584*t, 585*
  deep brachial, *574,* 590*t*–591*t, 591*
  deep femoral, *574,* 594*t, 595–596*
  deep plantar arch, 594*t, 595–596*
  diaphragm, *574*
  distributing, *565,* 567
  dorsal, 714, *714*
  dorsal pedal, *574,* 594*t, 595–596*
  esophageal, *581,* 581*t,* 656–657
  facial, *574,* 576*t*–578*t, 577–578*
  femoral, *334, 574,* 594*t, 595–596*
  fibular, *574,* 594*t, 595–596*
  foot, 594*t, 595–596*
  forearm, 590*t*–591*t, 591*
  gastric, 584*t, 585*
  gastroduodenal, 584*t, 585*
  gastro-omental, 584*t, 585*
  general anatomy, 564–572
  genicular, 594*t, 595–596*
  gluteal, *587,* 587*t*
  gonadal, *574, 584*
  hand, 590*t*–591*t, 591*
  head, 576*t*–578*t, 577–578*
  helicine, 714
  hepatic, *574,* 584*t, 585, 674–675,* 676
  hyaloid, *482,* 484
  hypophyseal, 500, *501–502,* 502–503, 503*t, 504*
  ileal, *586,* 586*t*
  ileocolic, *586,* 586*t*
  iliac, *336, 574, 584,* 594*t, 595–596, 722*
  iliolumbar, *587,* 587*t*
  intercostal, *581,* 582*t*
  interlobular, 687, *688–689, 693*
  interosseous, *574, 591,* 591*t*
  intersegmental, 601, *601–602*
  interventricular, *544*
  jejunal, *586,* 586*t*
  left coronary, *547,* 549–550, *550*
  leg, 594*t, 595–596*
  lingual, *577–578,* 577*t*–578*t*
  lobar, 572, *573*
  lower limb, 594*t, 595–596*
  lumbar, *584*
  mammary, 582*t*
  maxillary, 576*t*–578*t, 577–578*
  mediastinal, *581,* 581*t*
  mesenteric, *336, 341, 574, 584–586,* 584*t*–587*t, 586,* 656–657, *672*
  obturator, *587,* 587*t, 595*
  occipital, 576*t*–578*t, 577–578*
  ophthalmic, 576*t*–578*t, 577–578*
  ovarian, *584–586,* 584*t*–587*t,* 717, *718, 722*
  palmar, *574, 591,* 591*t*
  pancreatic, 584*t, 585*
  pancreaticoduocenal, 584*t, 585, 586,* 586*t*
  pelvic region, *584–586,* 584*t*–587*t,* 594*t, 595–596*
  penile, 714, *714*
  pericardiophrenic, *581,* 582*t*
  phrenic, *584–585,* 584*t*
  placental, 601, *601–602*
  plantar, 594*t, 595–596*
  popliteal, *574,* 594*t, 595–596*
  pudendal, *587,* 587*t*
  pulmonary, *542, 546, 548–549, 555,* 572, *573,* 601, *601, 641*
  radial, *574,* 590*t*–591*t, 591*
  radial collateral, *574,* 590*t*–591*t, 591*
  rectal, *586,* 586*t, 587,* 587*t*
  renal, *574, 584–586,* 584*t*–587*t, 685,* 687, *687–689*
  resistance, 567
  retinal, 482–484, *482–484*
  right coronary, *550,* 550–551
  sacral, *584, 587,* 587*t*
  segmental, 687, *688–689*
  sense organs, 567, *567*
  shoulder, 590*t*
  sigmoid, *586,* 586*t*
  spinal, *578*
  spiral, *722–723,* 723
  splenic, *336, 574,* 584*t, 585*
  stomach, *666*
  subclavian, *335, 338, 567, 574, 576,* 576*t, 581,* 582*t,* 590*t*–591*t, 591,* 601, *601*
  subcostal, *581,* 582*t*
  subscapular, *574, 581,* 582*t*
  superficial temporal, *574, 577–578,* 577*t*–578*t*
  superior phrenic, 582*t*
  superior vesical, 603
  supply, 549–552, *550–551*
  supraorbital, 576*t*–578*t, 577–578*
  suprarenal, 507–508, *508, 584–586,* 584*t*–587*t*
  systemic, *574*
  testicular, *584–586,* 584*t*–587*t, 707,* 709
  thoracic, *574, 581,* 581*t*–582*t*
  thoracoacromial, 582*t*
  thyroid, 505–506, *505–506, 566,* 576*t*–578*t, 577–578,* 577*t*–578*t*
  tibial, *574,* 594*t, 595–596*
  ulnar, *574,* 590*t*–591*t, 591*
  ulnar collateral, *574,* 590*t*–591*t, 591*
  umbilical, 96, *604*
  upper limb, 590*t*–591*t, 591*
  uterine, *587,* 587*t,* 717, *722,* 722–723
  vaginal, *587,* 587*t*
  vertebral, *574,* 576*t*–578*t, 577–578, 581,* 581*t*
  vesical, *587,* 587*t*
  wrist, 590*t*–591*t, 591*
Arteriole(s), *565,* 567
  afferent, 687, *688–690, 692–693, 695*
  efferent, 687, *688–690, 692–693, 695*
  fundus, *485*
  precapillary sphincters, *570*
  pulmonary, *642*
  small intestine, *670*
Arteriosclerosis, 603
Arteriovenous anastomosis (shunt), 571–572, *572*
Arthritis, 230–231, *230–232,* 231*t*
Arthroplasty, 231, *232*
Arthroscopic surgery, knee, 227, *227–228*
Articular cartilage, 134, 210, *210*
  exercise and, 210
Articular disc, 210
Artificial skin, 128
Ascending spinal tracts, 375–378, *376,* 376*t, 377*
Ascites, 680*t*
Aspartate, 362–363, *363*
Association tracts, 417
Asthma, 649
Astigmatism, *486,* 486*t*
Astrocytes, 357*t,* 358, *358*
Astrocytosis, 358
Atelectasis, 643
Atheroma, 551, *551*
Atherosclerosis, 551, *551,* 603
Atherosclerotic plaque, 551, *551*
Atlantoaxial joint, 170, *170*
Atlanto-occipital joint, 170, *170*
Atlas, 169, *170*
Atoms, 9
Atresia, 717
Atria
  heart, *542, 544,* 545, *546, 548–549, 553,* 557, *558*
Atrioventricular bundle, 553, *553*
Atrioventricular (AV) node, 552, *553*
Atrium (pulmonary), 640, *641*
Atrophy, tissue, 80
Auditory canal, 471, *471, 492*
Auditory function, 474–475, *475*
Auditory ossicles, 166, 471–472, *471–472, 492*
Auditory tube, 471–472, *471–472, 475, 492, 634*
Auricles
  ear (pinna), *331,* 470–471, *470–471, 492*
  heart, *542,* 545, *546, 550*
Auricular hillocks, 491, *492*
Auricular surface, *172,* 173, 190, *191–192, 331*
Auscultation, 3–4
Autoantibodies, 39
Autoimmune disease, 361
Autonomic nervous system (ANS), *352,* 353, 443–457
  anatomy, *446–449,* 446–452
  cardiac muscle and, 255
  central control, 455–456, *456*
  development and aging, 456–457
  disorders, 457*t*
  divisions, 444–445, *445*
  drugs and, 455
  dual innervation, 454–455, *455*
  effects, 453–456, 453*t*
  general properties, 443–445, *444–445,* 445*t*
  hypothalamic control, 415
  neural pathways, 445, *445,* 445*t*

  neurotransmitters and receptors, 453–454, 453*t*, *454*, 454*t*
  respiratory function, 645, *646–647*
  visceral reflexes, 443–444, *444*
Autonomic tone, 444–445, *445*
Autophagy, 46
Avulsion fracture, 202*t*
Axial musculature, 263–289, 297*t*
  nomenclature, 265*t*
Axial region, 13, *14*
  systemic circulation, 573, *574–590*
Axial skeleton, 151–180
  development, *176–178*, 176–179
  overview, *152*, 152–153
  pathology, 179–180, 179*t*, *180*
Axilla, *343*
Axillary folds, *343*
Axillary region, *343*
Axillary tail, *338*
Axis, vertebral, 170–171, *170–171*
Axoaxonic synapse, 362, *362*
Axolemma, 354, *355*
Axoneme, 37, *37*
Axon hillock, 354, *355*
Axons. *See* Nerve fibers (axons)
Axoplasm, 354, *355*
Axosomatic synapses, 362, *362*
Azotemia, 686
Azurophilic granules, 527
Azygos system, 582*t*, *583*

B

Back
  injuries, 286
  muscles, *284–286*, 284*t*–286*t*, *339*
Baldness, 119
Ball-and-socket joints, 212, *212*
Band cells, 527
Bare area (liver), 673, *674*
Baroreceptors, 444, *444*, 567, *567*
Baroreflex, 444, *444*
Bartholin glands, 724, *725*
Basal body, 37, 46
Basal cells
  carcinoma, 126, *126*
  tongue, *467*, 468
Basal layer, 123, *123*
  endometrium, 722, *722*
Basal skull, *157*, 159
Base, of lung, *640*
Baseball finger, 325*t*
Basement membrane, 28, 56, *642*, 692, *693*
  blood vessels, *565*
  seminiferous tubules, *711*
Basilar membrane, 473, *473*, *475*
Basilar part, 161
Basophils, 521, *521*, 522*t*, *528*, 528*t*, 530
  pituitary gland, 500, *501–502*, 502–503, 503*t*, *504*
Bed sores, 80
Bell palsy, 431
Belly (of muscle), 239–240, *240*, 300–301*t*, *301*
Benign prostatic hyperplasia, 698, 713
Beta cells, 509, *509*
Beta globulins, 522, 522*t*
Biaxial joint, 212, *212*
Bicuspids, 661
Bile, 673
Bile acids (salts), 673
Bile duct, *655*, *674–675*, *676*, 676–677
Bile ductule, *675*, 676
Bilirubin, 673
Biofeedback, 444
Bipedalism
  foot adaptations, *199*, 199–200
  skull adaption, 166, *166*
Bipolar cells, 486–489, *487–489*
Bipolar neurons, 356, *356*
Birth defects, 100–103, 104*t*
Bis-phosphonates, 147
Black lung disease, 649
Bladder, urinary, *334*, *336*, *604*, *680*
  anatomy, *342*, 685, *685*, 696, *697*
  female, *716–717*
  male, *706*
  prenatal development, *728*
Blastocoel, 88, *90*
Blastocyst, 88, *90*
Blastomeres, 88, *89*
Blind spot, 485
Blocker's arm, 325*t*
Blood
  circulatory routes, 571–572, *572*
  cleansing, 674*t*
  components and general properties, 520–521, *521*, 522*t*
  disorders, 534–535, 535*t*
  distribution, *570*
  flow pathway through heart, 547–548, *549*
  histology, 71, *71*, 71*t*
  islands, 525
  plasma, 71
  respiratory system, 631
  types, 525–526, *526*
  in urine, 692
Blood-brain barrier, 358, 405
Blood-CSF barrier, 405
Blood islands, 601, *601*
Blood pressure, respiratory system, 631
Blood supply, 656–657
  bone, 136, *137*
  eye, 485, *485*
  female reproductive tract, *722*, 722–723
  gonads, 510, *510*
  liver, *675*, 676
  muscles, 250, *250*
  renal system, 687, *688–689*, 689
  thyroid, 505–506, *505–506*
Blood-testis barrier (BTB), 707, 709, *711*
Blood urea nitrogen (BUN), 686
Blood vessels. *See also* Arteries; Capillaries; Vein(s)
  appendicular region, 590–600
  coronary, *544*, *550*
  digestive tract, *656*
  diseases, 605*t*
  female reproductive system, *717*
  general anatomy, 564–572
  histological structure, 564–565, *565*
  micrographs, *566*
  prenatal development, 601–603, *601–603*
  renal, 687, *688–689*, 689
  testes, *708*
  wall structure, 564–565, *565*
B lymphocytes, 522, 522*t*
Body (corpus)
  breast, 725–726, *726*
  female reproductive tract, *718*
  mandible, 165, *165*
  stomach, 664, *665–666*, 667, 667*t*
  uterus, 721–722, *722*
  vagina, 724, *725*
  vertebrae, 169, *169*
Body cavities and membranes, *16*, 16–20, 16*t*. *See* specific cavities, e.g., Middle ear cavity
Body functions, muscular control, 237
Bone marrow, 138, *138*
  transplants, 526
Bone(s). *See also* specific bones
  anatomy, 133–134, *133–134*, 153, *154*, 154*t*
  ankle, 197–199, *198*
  arm, 185–190
  blood supply, 136, *137*
  cancellous, 133, *133*
  cancer, 132
  capitate, 188, *189*
  carpal, 188, *189*
  cells, 134, *135*
  compact (dense), 70, *70*, 70*t*, 133, *133*
  compact bone, 136, *137*
  cranial, 155, 159, 176, *176*
  cuboid, 198, *198*
  deposition, 142
  dermal, 139
  development, 139–145
  elongation, *141–142*, 141–143
  endocrine cells in, 510
  ethmoid, *153*, *157*, 162–164, *163*
  facial, 164–166, *164–166*, 177, 179–180, *180*
  flat, 133, *134*
  foot, 197–199, *198*
  forearm, 186–190, *187–189*
  fractures, 145–146, 145*t*, *146*
  frontal, 159–160, *481*
  growth, 140–143, *141*, *142*
  hamate, 188, *189*
  hand, 186, 188, 189, *189*
  hip, 190, *191*
  hormones and, *504*
  hyoid, 166, *166*, *636*, *659*
  intermediate, 198, *198*
  irregular, 133
  jaw, 165, *165*
  knee, 195, *196–197*
  lacrimal, *164*, 165
  leg, 193, 195–199, *347*
  long, 133, *133*
  lower limb, 193, 195–199
  lunate, 188, *189*
  matrix, 135–136
  medial, 198, *198*
  metacarpal, 188, *190*
  middle-ear, 471–472, *471–472*
  muscles and, 241, *241*
  nasal bones, *155*, 165
  nutritional and hormonal factors in growth, 144
  occipital, *157*, 161, *331*
  osseous tissue and, 132–133
  palatine, *157*, *163*, 165
  parietal, *156*, *158*, 160
  pectoral girdle, 185–186, 185–190, *186*, 190–199
  pelvic, 190–193, *191–192*
  pisiform, 188, *189*
  pollex, 188, *190*, *344–345*
  polymers and ceramics and, 136
  remodeling, 143–144
  scaphoid, 188, *189*
  sesamoid, 153
  short, 133
  shoulder, 185–186, *186*
  skeletal system, 153, 153*t*
  skull, 166, *166*
  sphenoid, 162, *162*
  spongy, 70, *70*, 70*t*, 133, *133*, 136, *137–138*, 138
  squamous temporal, 160, *161*
  structural disorders, 145–148, *147*, 148*t*
  sutural, 153
  temporal, 160, *161*
  temporal bones, 160, *161*, *331*, *433*, *472*, *492*
  tissue, 70, *70*, 70*t*
  trabezoid, 188, *189*
  trapezium, 188, *189*
  triquetrum, 188, *189*
  upper limb, 185–190, 186–190, *187–189*
  widening and thickening, 143
  wormian bones, 153
  wrist, 185–190, *189–190*
  zygomatic, *156–157*, 165
Bony joints, 206
Bony (osseus) labyrinth, *472–473*, 472–474
Brachialis muscle, 301*t*, *302*
Brachial region, 16
Brachioradialis muscle, 301*t*, *302*
Brachium, 186
Bradycardia, 394
Braille, 463
Brain
  auditory pathways, *472*, 475, *476*
  barrier system, 404–405
  blood supply, 404–405
  disorders, 438–439, 438*t*
  embryonic, 366, *366*
  hindbrain, 406
  integrative functions, 419–426
  landmarks, 399, *400–401*, 402
  midbrain, 406
  motor control, 421–422
  olfactory projection pathways, 469, *470*
  respiratory centers, 645, *646*
  sensory functions, 420–421, *421*
Brainstem, *332*, *366*, 375, 399, *400–401*, 402, 406–409, *407–408*
  auditory function, 475, *476*
Breast, *333*, *338*, 725–726, *726*
  cancer, 732*t*, 734*t*
  fat, *340*
Breathing
  difficulties, 280
  fetal, 647, *648*
  respiratory system, 631
Bridge, nasal, *635*

Broca area, *420*, 423–424, *424*
Bromhidrosis, 121
Bronchi (bronchus), *336*, *446*, *631*, *636*
  anatomy, 639–640, *640*
  lobar, *638*
  main, 639–640, *640*
  prenatal development, *648*
  segmental, *638*, 639–640, *640–641*
Bronchial mucosa, *641*
Bronchial tree, 639–640
Bronchiole, *642*
Bronchitis, chronic, 649
Bronchopulmonary segment, *631*, 639–640
Brown fat, 68
Brush border anatomy, 36, 669, *670*
Brush border enzymes, 669
Buffy coat (blood cells), 521
Bulb, hair, 117, 123–124, *124*
Bulb, penis, 714
Bulbar conjunctiva, 480, *481*
Bulbocavernosus muscle, 287*t*, *288*
Bulbourethral gland, *706–707*, 713
  prenatal development, *728*
Bulbous corpuscle, *462*, 462*t*, 463
Bulbus cordis, 557, *558*
Bulge, hair, *117*, 118
Bundle branches, 553, *553*
Burn injuries, skin, 126–127, *127*
Bursae
  elbow, *223*, 223–224
  infrapatellar, 228
  joints and, 210, *211*
  popliteal, 228
  prepatellar, 228
  semimembranous, 228
  shoulder joint, 223, *223*
  suprapatellar, 228
Bursitis, 210

C

Cadaver, 2, *4*
Calcaneal (heel) spurs, 202*t*
Calcaneal (Achilles) tendon, 198, *198*, *228*, 229, 316*t*, *318*
Calcaneus, 198, *198*, *347*, *348*
Calcification, bone, 132–133
Calcitonin, 506, 511*t*
  bone growth and, 144
Calcitriol, 510, 512*t*
Calcium phosphate
  bone growth and, 144
  intramembranous ossification, 139, *140*
Calculi
  biliary, 677
  dental, 661
  renal, 696
Caldidiol, 512*t*
Calvaria, 155, *158*, 159
  fracture, 179–180, *180*
Calyxes, renal, 687, *688*, *690*, *699*
Canaliculi, 70, 134
  bile, *675*, 676
  lacrimal, 480, *481*
Canal of Schlemm, *483*, 484
Cancer
  bone cancer, 132
  breast, 732*t*, 734*t*
  cell division in, 48, *48*
  cervical, 733
  digestive system, 681
  penile, 732*t*
  prostate, 713
  skin, 125–126, *126*
  testicular, 715, 732*t*
Cannon, Walter, 443
Canthi, medial and lateral, 480, *480*
Capacitation, sperm, 86
Capillaries, 564–566
  alveolar, *573*, *642*
  blood flow regulation, *570*
  continuous, 568, *568*
  fenestrated, 568, *569*
  histology, *565*
  lacteal, 669, *670*
  micrographs, *566*
  peritubular, 687, *688–689*, *691*
  permeability, 568, *569*
  structure, 567–570, *568–570*
Capillary beds, 568, *570*
Capillary endothelial cell, *569*, *642*, 692, *693*
Capitulum, 187, *187*
Capsular space, 691, *693*
Capsule(s)
  exocrine glands, 76
  of exocrine glands, 75
  fibrous, 686–687, *687*
  glomerular, *690*, 691
  perirenal fat capsule, 686–687, *687*
  renal, *690*
Carbohydrate metabolism, 674*t*
Carcinogens, 48
Cardia (stomach)
  achalasia, 457*t*
  anatomy, 664, *665–666*, 667, 667*t*
Cardiac center, 406, *407–408*
Cardiac conduction system, 552–553, *553*
Cardiac cycle, 555–556
Cardiac glands, 664, *665–666*, 667, 667*t*
Cardiac impression, 639, *640*
Cardiac muscle, 73, *74*, 74*t*, 236, *254*, 254–255, 255*t*
  development of, 257–258, *258*
  structure, 553–554, *554*
Cardiac notch, 639, *640*
Cardiac orifice, 663
Cardiac tamponade, 17, 560*t*
Cardiocytes, 73, 236, *254*, 254–255, 255*t*, 544
Cardiology, 540
Cardiomegaly, 559
Cardiomyopathy, 560*t*
Cardiovascular system, 520. *See also* Heart
  overview, *540*, 540–541, *541–542*, 543
  reticular formation, 410
Carina, *636*, 638–639, *638–639*
Cariogenic effect, 506
Carotene, skin color and, 115
Carotid bodies, 567, *567*, *647*
Carotid canal, 161
Carpal region, 16
Carpal tunnel, 303*t*
  syndrome, 307, *307*
Carrier-mediated transport, *34*, 34–35
Carrier proteins. *See* Transport proteins
Cartilage, 68, *69*, 69*t*
  alar, 633–634, *634–635*, *635*
  articular cartilage, 134, 210, *210*
  arytenoid, 635, *636–637*
  bronchial, *641*
  corniculate, 635, *636–637*
  costal, 174, *174*, *334*
  cricoid, 635, *636–637*, *638*, *640*
  cuneiform, 636, *636*
  epiglottic, 635, *636–637*
  knee, 226, *226–227*
  lateral, 633–634, *634–635*, *635*
  septal, *634*
  thyroid, 277*t*, *278*, *335*, *338*, 506, *506*, 635, *636–637*, *638*, *640*
  zone of rserve cartilage, 141
Cartilaginous joints, 208, *209*, 211*t*
Catagen phase, hair cycle, 119, *119*
Cataracts, 484
Categorical hemisphers, 424–425, *425*
Catheterization, 592
Cauda equina, 372, *373*
Caudal direction, 399, *400–401*, 402
Caudal end, embryo, 89
Caveolae, smooth muscle, 255
C (clear) cells, 506
Cecum, *335*, *341*, *655*, 671, *672*
Cell-adhesion molecules (CAMs), 33, *33*
Cell body. *See* Neurosoma
Cell cycle, 47, *47*
Cell-identity markerss, 33, *33*
Cell junctions, 38–39, *39*
Cell(s). *See also* Cytology; Stem cells
  acinar, 677, *677*
  apical surface, 28, *29*
  basal surface, 28
  basic components, *29*, 29–30, 30*t*
  blood (*See* specific blood cells, e.g., Erythrocytes)
  bone(s), 134–138, *135*, *137–138*
  C (clear) cells, 506
  chief cells, 506, 664, 667*t*
  chromaffin, 507, *508*
  diploid, 85, 709, *710*
  division, 47–48, *48–49*, 85
  enterocytes, 669, *669–670*
  enteroendocrine, 664, 667*t*
  epidermal, 110–111, *111*
  fibrous tissue, 63
  follicular, 716–717, *716–717*
  G cells, 667
  goblet, 67, 633, *633–635*, *638–639*, 669, *669–670*
  gonadal, 510, *510*
  granular (juxtaglomerular) cells, 694, *695*
  haploid, 85, 709, *710*
  intercalated, 695
  interior structures, 40–48
  lateral surface, 28
  life cycle, 47–50
  mesangial cells, 694–695, *695*
  mucous, 664, *665–666*, 667, 667*t*
  nerve cell (*See* Neurons)
  parietal, 664, 667*t*
  plasma, 522, 522*t*
  principal, 695
  shapes and sizes, 27–29, *28*, *57*
  surface area and volume, *28–29*, 28–30
  surface extensions, 36–38, *37*
  target cells, 498–499, *499*
  umbrella, 62, 696, *697*
Cell theory, 26
Cementum, tooth, 660–661, *660–661*
Central canal(s)
  brain, *403*, 404
  haversian canals, 70, *70*, 70*t*, 136, *137*
  spinal cord, *374*, 375
Central nervous system (CNS)
  aging, 437–438
  oligodendrocytes, 360, *360*
  overview, *352*, 352–353
  projection pathways, 463–464
  respiratory system and, 645, *646*
Central pattern generators, 372, 410
Central sulcus, *400–401*, 416
Central tendon, respiratory system, 279*t*
Central venous catheters, 592
Centrioles, *44*, 46
  meiosis, *710*
Centromere
  meiosis, *710*
  mitosis, 48, *50*
Centrosome, 46
Centrum (vertebrae), 169, *169*
Cephalic end, embryo, 89
Cephalic flexure, 366, *366*
Ceramics, bones and, 136
Cerebellar hemispheres, 410–413, *411–412*
Cerebellar peduncles, 410–411, *411–412*
Cerebelli, *402*, 403
Cerebellum, *332*, 375, 399, *400–401*, 410–413, *411–412*, 413*t*, 424, *427*
  motor controll, 422
  pathways, *412*
  vestibular projection pathway, *479*
Cerebral aqueduct, *403*, 404
Cerebral-arterial circle, *577–578*, 577*t*–578*t*
Cerebral cortex, 402, *403*, 417, *418*. *See* Cerebral cortex
  functional regions, *420*
  gustatory projection pathway, 468, *468*
Cerebral crura, 409
Cerebral hemispheres, 375, 399, *400–401*, 415, 425*t*, *426*
  lateralization, 424–425, *425*
Cerebral palsy, 104, 438*t*
Cerebral peduncle, 409
Cerebrospinal fluid, 358
  flow, *405*
  functions, 404
  meningitis, 404
Cerebrovascular accident, 605*t*
Cerebrum, *332*, 399, *400–401*, 425, *426*
  auditory function, 475, *476*
  circulation, *578*, 578*t*
  gross anatomy, *400–401*, *412*, 415–416
  taste, 468, *468*

Ceruloplasmin, 522, 522*t*
Cerumen, 122, 471, *471*
Ceruminous glands, *121,* 122, 470
Cervical canal, 713, *718,* 722
Cervical cancer, 733, *733*
Cervical curvature, 168, *168*
Cervical enlargement, 372, *373*
Cervical flexure, 366, *366*
Cervical glands, 722
Cervical intraepithelial neoplasia (CIN), 733, *733*
Cervical region, 13, *14, 331,* 372, *373*
  muscles of, 272*t*
Cervical vertebrae, 167, *167–168,* 169–171, *170–171*
  fractures and dislocations, 179–180, *180*
Cervix, *342, 716–717, 718,* 721–722, *722*
Chambers of heart, 545, *546*
Channel proteins, 32–33, *33*
Charley horse, 260*t*
Cheeks, 658–659
Chemical senses, 466–470, *467–470*
Chemical synapses, 362–363, *363*
Chemoreceptors, 461
  cardiac, 567, *567*
  respiratory system, 645, *646*
Chewing muscles, 273*t*–276*t, 276*
Chief cells, 506, 664, 667*t*
Choanae, 162, *162,* 633–634, *634–635*
Cholecalciferol, 512*t*
Cholecystokinin, 510, 512*t*
Cholelithiasis, 677
Cholesterol, 31
Cholinergic fiber, 454
Chondrification, 176
Chondroblasts, 68
Chondrocranium, 176
Chondrocytes, 68, *638*
Chorda tympani, *433*
Chorion, 93–95, *94*
Chorionic villi, *94,* 95, 96
Choroid (eyeball), 482–484, *482–484, 487, 493*
Chromaffin cells, 507, *508*
Chromatids
  meiosis, *710*
  mitosis, 48, *49–50*
Chromatin, 43
Chromatophores, 483
Chromophobes, 500, *501–502,* 502–503, 503*t, 504*
Chromosomes, 43
  disjunction/nondisjunction, 100–102, *101*
  meiosis, *710*
  mitosis, *50*
  sexual reproduction, 704
Chronic obstructive pulmonary disease (COPD), 649
Chylomicrons, 669
Chyme, 664
Chymotrypsinogen, 678*t*
Cilia, 36–37, *37*
Ciliary body, 482–484, *482–484*
Ciliated cells, 633, *634–635*
Ciliopathies, 36
Cingulate gyrus, 418, *418*
Circadian rhythms, 415, 505
Circle of Willis, 578*t*
Circular folds, 668, *669–670, 676,* 676–677
Circulatory system, 9, *11. See also* Heart
  axial region, 573, *574–575*
  at birth, *604*
  circulatory routes, 571–572, *572*
  collateral circulation, 551–552
  coronary circulation, 549–552, *550–551*
  digestive tract, 656–657
  fetal, *604*
  functions, 520
  hypophyseal portal system, 500, *501–502,* 502–503, 503*t, 504*
  liver, *675,* 676
  neonatal, *604*
  pulmonary circuit, 572, *573*
  renal circulation, 687, *688–689,* 689
Circumduction, synovial joints, 216, *216*
Circumferential lamellae, compact bone, 136, *137*
Circumventricular organs (CVOs), 405
Cirrhosis, 680*t*
Cisternae, 43
  terminal, 245
Clavicle, 185, *185, 331, 333, 334, 338*
  fractures, 185
Clavicular notches, *173,* 174
Cleavage, preembryonic stage, 88
Cleavage furrow, 50
  meiosis, *710*
Climateric change, 731
Clitoris, *716–717,* 724, *725*
  prenatal development, *729*
Cloaca, *728*
Clotting factors, *533,* 533–534
Clubfoot, 201–202, *202,* 202*t*
Club hair, 119, *119*
Coccygeal ligament, *374,* 375
Coccygeal vertebrae, *167–168,* 167–175, *172,* 173
Coccyx, *172,* 173, *339*
  male, *707*
Cochlea, *434,* 471, *471–473,* 473
  auditory function, 475, *476–477*
Cochlear duct, 473, *473, 492*
Coelom, 17, 91, *91*
  prenatal development, 514, *514*
Cognition, 423
Cold receptors, 444, *444*
  thermoreceptors, 461
Collagen diseases, 64
Collagenous fibers, 63–64, *64*
Collarbone, 185, *185*
Collateral ligaments
  ankle, *228,* 229
  knee, 226, *226–227*
Collecting duct, 689, *689, 690,* 695
  prenatal, *699*
Colles fracture, 202*t*
Colliculi, *407,* 409
  inferior, *407,* 409, *420,* 475, *476*
  superior, 490, *490*
Colon
  anatomy, 671, *672,* 673, *687*
  ascending, *655, 657,* 671, *672,* 673
  descending, *341, 584, 655, 657,* 671, *672*
  sigmoid, *341, 342, 655, 657,* 671, *672*
  transverse, *341, 584, 655, 657,* 671, *672*
  vagus nerve, *435*
  veins, *589*
Colony-forming units (CFUs), 525, *525, 531*
Color blindness, 493*t*
Color vision, 487
Columnar cells, 27, *28*
  simple epithelia, 57, *59,* 59*t, 670*
  stratified epithelia, 57, *60,* 60*t*
Columns (funiculi), spinal cord, *374,* 375
Commissural tracts, 416, *417*
Commissure(s)
  cerebral, *401,* 416–417, *417*
  gray, *374,* 375
  lateral, *331*
  medial, *331*
  medial and lateral, 480, *480*
Comparative anatomy, 3
Compartments
  lower lim, *313–315,* 313*t*–315*t*
  upper limb, 294, *295*
  wrist and hand, 303*t*–306*t, 304–306*
Compartment syndrome, 294
Complement proteins, 522, 522*t*
Complete blood count (CBC), 532
Complicated plaques, 603
Compression atelectasis, 643
Compressor urethrae muscles, 287*t, 288*
Computed tomography (CT), 4, *5*
Concentric lamellae, compact bone, 136, *137*
Conception, 87
Conceptus, 87, *89*
  implantation, 95
Concha, *470–471*
Conchae, nasal, 633, *634–635*
Concussion, 438*t*
Conduction
  cardiac conduction system, 552–553, *553*
  spinal cord, 372
Conduction deafness, 474
Conductivity
  muscular, 237
  neuronal, 353
Condylar canal, 161
Condylar joints, 212, *212*
Condyles of bone
  femoral, medial and lateral, 195, *195, 347*
  mandibular, 165, *165*
  tibia, medial and lateral, 197, *197*
Cones, 486–489, *487–489*
Congenital anomaly, 100
  hands and feet, 201–202, *202,* 202*t*
Congestive heart failure, 560*t*
Conjunctiva, 480, *481*
Conjunctival sac, *481*
Connective tissue, 63–71
  fibrous tissue, *63–66,* 63–67, 63*t*–66*t*
  gonads, 510, *510*
  muscles, 237–238, *238*
  nasal, *635*
  root sheath, *117,* 118
  teeth, 660–661, *660–661*
Conotruncus, 557, *558*
Consciousness, 410
Constrictors, pharyngeal, 663
Contact digestion, 669
Continuous ambulatory peritoneal dialysis (CAPD), 700
Contractile proteins, 246
Contraction, muscular, 250–251, *252*
Contracture, 260*t*
Contralateral reflex, 393, 393*t*
Conus medullaris, 372, *373*
Converging neural circuit, 364, *364*
Convoluted tubules, *690*
Coracohumeral ligament, 221–223, *223*
Cord blood transplants, 526
Cornea, *481,* 482–484, *482–484, 493*
Coronal suture, *156, 158,* 160
Corona radiata, *426,* 720
Coronary artery disease, 551, *551*
Coronary atherosclerosis, 551, *551*
Coronary circulation, 549–552, *550–551*
Corpora quadrigemina, *407,* 409
Corpus albicans, *717,* 721
Corpus callosum, 399, *400–401,* 415, *426,* 714, *714*
  veins, *580*
Corpus cavernosum, *342, 706*–707
Corpus luteum, 502, 503*t, 504, 717, 719,* 721
Corpus spongiosum, *342, 697, 706*–707, 714, *714*
Corpus striatum, 419, *419*
Corrugator supercilli muscle, 270*t, 271*
Cortex
  adrenal (*See* Adrenal cortex)
  association, 419, *420*
  auditory, 419, *420, 476*
  hair matrix, 117
  primary, 419, *420, 476*
  vestibular, *479*
Cortical granules, *86,* 87
Cortical nephron, *690,* 694
Corticomedullary junction, 687, *689*
Corticospinal tracts, 406, *407–408*
  anterior, 375 *376,* 376*t, 377,* 378, *379*
  lateral, 375 *376,* 376*t, 377,* 378, *379*
Corticosteroids, 507–508, *508,* 511*t*
Corticotropin-releasing hormone, *501,* 502, 502*t, 504*
Cortisol, 508, *508,* 511*t*
Costal groove, 174, *174*
Costal margin, 173, *338*
Costal surface, *640*
Costovertebral joint, *178,* 178–179
Countercurrent heat exchange, 705, *706–707*
Cowper's gland, *706–707,* 713
Coxal (hip) joint, 224, *225*
Cranial cavity, 17, 155, *157–158,* 159
Cranial nerves, *401, 403,* 404, 406, *407–408,* 409, *427,* 427–437, 429*t. See* Cranial nerves
  abducens (VI), *427–428, 432, 481*
  accessory (XI), *427–428, 436*
  aids to memorizaiton of, 437
  auditory function, 475, *476*
  classification, 427*t*–437*t,* 437

Cranial nerves (*continued*)
  - digestive system, *433–434, 447,* 655–656, *656*
  - disorders, 431, 438–439, 438*t*
  - eye, 482
  - facial (VIII), *427–428, 433,* 450, *451,* 468, *468, 472*
  - glossopharyngeal (IX), *427–428, 434, 444,* 450, *451, 646–647*
  - hypoglossal (XII), *427–428, 436*
  - oculomotor (III), *427–428, 430,* 450, *451, 481*
  - olfactory (I), *427–429,* 429*t*
  - optic (II), *427–429, 481,* 482–484, *482–484,* 487–490, *487–490*
  - pain signals, 465
  - pathways, *428,* 437
  - respiratory function, *646–647*
  - taste and, 468, *468*
  - trigeminal (V), *427–428, 431–432*
  - trochlear (IV), *427–428, 430, 481*
  - vagus (X), *427–428, 435, 444, 446,* 450, *451,* 452
  - vestibular projection pathways, 479, *479*
  - vestibulococclear (VIII), *427–428, 434,* 475, 479, *479*

- Craniosynostosis, 179*t*
- Cranium, 155, 159, *332*
- Cribriform plate, *157,* 163, *163, 429, 634*
- Crista ampullaris, 478, *478*
- Cristae, 46
- Crista galli, 163, *163*
- Crohn disease, 680*t*
- Cross-bridging, excitation-contraction coupling, 251, *252*
- Crossed extension reflex, 393, 393*t*
- Cross section, tissue, 55, *56*
- Crown-to-rump length (CRL), 96
- Crura, 724, *725*
- Crural region, 16, 193
- Crus, *706*–707, 714
- Crush syndrome, 260*t*
- Crutch paralysis, 388
- Cryptorchidism, 715, 732*t*
- Crypts of Lieberkühn, 670, *670*
- Cuboidal cells, 27, *28*
  - alveoli, 641, *642*
  - simple epithelia, 57, *58,* 58*t*
  - stratified epithelia, 57, *61,* 61*t*
- Cumulus oophorus, *719–720,* 720
- Cuneate fasciculus, *376–377,* 376*t,* 378
- Cupula, 478, *478*
- Curvatures
  - stomach, 664, *665–666*
  - vertebral column, 168, *168,* 169
- Cusps, 661
- Cutaneous glands, 120–122, *121,* 122*t*. *See also* Sebaceous glands; Sweat glands
- Cutaneous membrane, 78
- Cutaneous nerves, *386,* 386*t*
- Cutaneous vasoconstriction, 109
- Cutaneous vasodilation, 109
- Cuticle, 120, *120*
- Cyanosis, skin color and, 115
- Cystic duct, *676,* 677
- Cystitis, 696
- Cytogenic glands, 75
- Cytokinesis, 50
- Cytology, 2, 25–50
  - microscopy, 26–27, *27*
- Cytoplasm, 30
- Cytoskeleton, 30, 40, *41*
- Cytosol, 30
- Cytotrophoblast, 88, *90*

D

- Dander, 112
- Daughter chromosome, mitosis, 48
- Day vision, 487
- Dcubitus ulcers, 80
- Deafness, 474
- Decidual cells, 95
- Declarative memory, 424
- Decussation, spinal tracts, 375, *376,* 376*t,* 378
- Deep fascia of penis, *707, 714*
- Deep perineal space, 287*t, 288*
- Deep transverse perineal muscles, 287*t, 288*
- Degenerating pronephros, *699*
- Dehydroepiandrosterone (DHEA), 508
- Delayed onset muscle soreness, 260*t*
- Delta cells, 509, *509*
- Dendrites, *72,* 72*t,* 73, 354, *355*
  - olfactory, 469, *469–470*
- Dendritic cells
  - Langerhans, 111, *111*
  - vaginal, 724
- Dendritic spines, 417, *418*
- Dens (vertebrae), 170, *170*
- Dense bodies, smooth muscle, 255
- Dense connective tissue, 64, *66,* 66*t,* 67
- Denticulate ligaments, *374,* 375
- Dentin, 660–661, *660–661*
- Dentition, 660–661, *660–661*
- Deoxyribonuclease, 678*t*
- Depression
  - of mandible, 217, *218*
  - synovial joints, 214, *215*
- Depressor anguli oris muscle, *271,* 272*t*
- Depressor labii inferioris muscle, *271,* 272*t*
- Dermal papillae, 112, 117
- Dermatology, 109
- Dermatome, 92
- Dermatomes, 391, *391*
- Dermis, 109, *110*
  - structure, 112–113, *113*
- Descending spinal tracts, 375, *376,* 376*t,* 378, *379*
- Desmosomes, 38–39, *39*
- Desquamation, 62, *62*
- Developmental plasticity, 50
- Dextrocardia, 6
- Dialysiis, 700
- Diaphragm
  - abdominal region, 17, *334, 337, 340–341, 446, 541, 574, 666, 685*
  - blood vessels, *574–575*
  - digestive tract, *655*
  - pelvic, 287*t, 288*
  - pulmonary ventilation, 643–644, *644, 646*
  - respiratory region, *279,* 279*t,* 280*t*
  - respiratory system, *631*
  - urogenital, *697*
- Diaphysis, 133
- Diarthroses, 209, 229*t*
- Diastolic contraction, *555,* 555–556
- Diencephalon, 366, *366,* 413–415, *414,* 425*t, 493*
- Differentiation, tissue changes, 79
- Diffusion, membrane transport, 33–36, *34–35*
- Digestive system, 9, *11,* 654–681
  - accessory glands, 673
  - aging, 678, 680
  - anatomy, 654–655, *655*
  - circulation, 656–657
  - diseases, 680–681, 680*t*
  - functions, 654
  - innervation, 655–656, *656*
  - liver function, 674*t*
  - mouth through esophagus, 658–663
  - prenatal development, 678, *679–680*
- Digestive tract, 654–655, *655*
  - peritoneum and, 657–658
  - prenatal development, 514, *514*
  - tissue layers, *656*
- Digital rays, 200–201, *201*
- Digital rectal examination, 713
- Diploe, 134, *134,* 160
- Diploid cells, 85, 709, *710*
- Direct attachment, skeletal muscle, 239–240, *240*
- Discoid cells, 28, *28*
- Disjunction, chromosomal, 100–102, *101*
- Dislocations
  - elbow, 224, *224*
  - joint(s), 231*t*
  - shoulder, 223–224
  - vertebrae, 179–180, *180*
- Dissecting aneurysm, 566, *566*
- Dissection, 4, *4*
- Disseminated intravascular coagulation (DIC), 535*t*
- Distal convoluted tubule (DCT), *689–690,* 695, *699*
- Diverging neural circuit, 364, *364*
- Diverticulitis, 680*t*
- Dopamine, 507, *508*
- Dorsal aorta, 601, *601–602*
- Dorsal artery, 199
- Dorsal interosseous muscles, *308,* 309*t,* 322*t, 323*
- Dorsal nerve, 199
- Dorsal respiratory group, 645, *646*
- Dorsiflexion, 219, *219*
- Dorsum, 13, 199
  - hand, *344*
- Dorsum nasi, *331, 635*
- Dorsum sellae, *157,* 161
- Down syndrome, 101–102, *102*
- Drugs
  - autonomic nervous system, 455
  - metabolism, 674*t*
- Dry gangrene, 80
- Dual-energy X-ray absorptionmetry (DEXA), 147
- Ducts, glands, 75–78
- Ductus arteriosus, 557, *558–559,* 559, 601, *601–602, 604*
- Ductus deferens, *335,* 705, *706–708,* 712
  - prenatal development, *728, 730*
- Ductus venosus, *604*
- Duodenal glands, *616,* 670, *670*
- Duodenal papilla, 668, *669–670, 676,* 676–677
- Duodenojejunal flexure, 667–670, *668–670, 676,* 676–677
- Duodenum, *336, 341,* 667–670, *668–670, 676,* 676–677
- Duplicity theory, 488
- Dural sheath, 373, *374*
- Dural sinuses, 402, *402*
- Dura mater, 373, *374, 472*
- Dynamic equilibrium, 475–478, *476–478*
- Dynein, 37–38
- Dynorphins, pain and, 466
- Dyskinesias, 422
- Dysmenorrhea, 734*t*
- Dysphagia, 680*t*
- Dyspnea, 559
- Dystrophin, 246

E

- Ear
  - anatomy, 470–474, *470–474*
  - auditory function, 474–475, *475*
  - auditory projection pathways, *472,* 475, *476–477,* 476–478
  - development of, 491, *492*
  - inner ear, *472–473,* 472–474
  - middle ear, 471–472, *471–472*
  - outer (external), 470–471, *470–471*
  - vestibular apparatus, 475–478, *476–478*
  - vestibular projection pathways, 479, *479*
- Earlobe, *470–471*
- Eccrine glands, 76–77, 120, 121, *121*
- Ectoderm, 89, *90,* 92*t,* 678, *679–680*
  - eye development, 491, *493*
- Ectopic pregnancy, 89, 734*t*
- Edward syndrome, 101
- Effectors, nervous system, *352,* 353
  - autonomic nervous system, 445*t*
- Efferent ductules, *706–708,* 712, *728*
- Efferent nerve fibers, 381, 381*t,* 392
- Efferent pathways, 411, *412*
  - somatic *vs.* autonomic, 445, *445,* 445*t*
- Effort, muscular, 241, *241*
- Egg (ovum), 704, 717, *718–719*
- Egg cell, 510, *510*
- Ehlers-Danlos syndrome, 64
- Ejaculatory duct, *706*–707, 712
- Elastic cartilage, 68, *69,* 69*t,* 70
- Elastic fibers, 64
- Elasticity, muscles, 237
- Elastic tissue, 67
- Elastin, 64, 67
- Elbow
  - injuries, 224, *224,* 325*t*
  - joints of, *223,* 223–224, 229*t*
  - pulled elbow, 224, *224*
- Electrical synapses, 363
- Electrocardiogram, 555
- Electrolytes, 661
  - in plasma, 522, 522*t*

Electron microscopy, 26, *27*
Eleidin, 112
Elevation, synovial joints, 214, *215*
Embolism, 535*t*
  air embolism, 579
Embryo, 90
  limb rotation in, 200–201, *201*
  muscle development in, 257–258, *258*
Embryoblast, 88, *90*
Embryogenesis, 88, *90*
Embryology
  gametogenesis and fertilization, 85–87, *87*
  prenatal development, 87–99
Embryonic disc (blastodisc), 88, *90*
Embryonic folding, 90–92, *91*
Embryonic stage, prenatal development, 87, 88*t*, 90–96, *91–96*
Embryonic stem (ES) cells, 50
Emotional responses, 415, 423
Emphysema, 649
Empty sella syndrome, 500
Enamel, tooth, 660–661, *660–661*
Encapsulated nerve endings, *462,* 462*t*, 463
Encephalitis, 438*t*
End bulb, *462,* 462*t,* 463
Endemic goiter, 515, *515*
Endocardial heart tubes, 557, *558*
Endocardium, *543,* 543–544, *544, 546*
Endochondral ossification, 139–140, *141*
Endocrin disruptors, 715
Endocrine cells, in tissues and organs, 510–511, 511*t*
Endocrine glands, *75,* 75–78, 498–499, *499,* 512–514, *513–514*. *See also* specific glands
  comparative anatomy, 498–499, *499*
  prenatal development, 512–514, *513–514*
Endocrine system, 9, *11,* 497–516
  aging and, 514
  disorders, 515, 516*t*
  nervous system and, 352, *352,* 498–499
  overview, 498–499, *499*
Endocrinology, 498–499, *499*
Endocytosis, 35
Endoderm, 89, *90,* 92*t,* 678, *679–680*
Endolymph, 473, *478*
Endolymphatic sac, *472*
Endometrial gland, *723*
Endometriosis, 734*t*
Endometrium, *718,* 722, *722*
Endomysium, 237, *238*
Endoneurium, 360, 380, *381–382*
Endoplasmic reticulum (ER), 43, *44*
Endosteum, 133
Endothelial cells, *568–569, 693*
  liver, *675*
Endothelium
  blood vessels, 564, *565*
  capillary, *569,* 692
Enkephalins, pain and, 466
Enteric hormones, 510, 512*t*
Enteric nervous system, *442,* 452
  digestive tract, 656, *656*
Enterocytes, 669, *669–670*
Enteroendocrine cells, 664, 667*t*
Enzymes, membrane proteins, 32, *33*
Eosinophils, 521, *521,* 522*t*
  structure, 527, *527–528,* 528*t,* 529–530
Ependymal cells, 357*t,* 358, *358*
Epiblast, 88, *90*
Epicardium, 17, 543, *543–544, 546*
Epicondyles
  femoral, 195, *195, 347*
  humerus, 187, *187, 344*
Epidermal ridges, 112
Epidermal water barrier, 109, 112
Epidermis, 109, *110*
  cells of, 110–111, *111*
  layers, *111,* 111–112, 114*t*
Epididymis, *335, 342, 706–708*
  duct, 712
  prenatal development, *728, 730*
Epidural anesthesia, 373
Epidural space, 373, *374*
Epigastric region, 16
Epiglottis, *332, 467, 631, 634,* 635, *636–637*
Epilepsy, 438*t*
Epimysium, 238, *238*
Epinephrine, 507, *508*
Epineurium, 380, *381–382*
Epiphyseal fracture, 202*t*
Epiphyseal plate, 133, 140
Epiphysis, 133
Epithalamus, 413–415, *414,* 425*t, 426*
Epithelia, 28
  simple epithelia, 57, 58*t*–59*t*
  stratified epithelia, 57, *60,* 60*t*
Epithelial root sheath, *117,* 118
Epithelium, 56–62, *57–62*
  cell replacement, 667
  large intestine, 671
  olfactory, *469,* 633, *634–635*
  pigment, 483, 486–489, *487–489*
  respiratory, *59,* 633, *634–635*
  stomach, *666*
  stratified squamous, *656*
  tracheal, *639*
Eponychium, 120, *120*
Eponyms, medical terminology, 20
Equatorial plane, meiosis, *710*
Equilibrium, 420
  dynamic, 475–478, *476–478*
  static, 475–478, *476–478*
  vestibular apparatus, 475–478, *476–478*
  vestibulococclear (VIII) nerve, *434*
Erectile tissue, 633, *634–635,* 714
Erythema, 115
Erythrocytes, 71, 520–521, *521,* 522*t,* 523–526, *523–526*
  capillaries, *568–569*
  disorders, 534–535, 535*t*
  glomerulus, *693*
  hepatic sinusoid, *675*
  prenatal development, 601, *601*
Erythrocytosis, 534, 535*t*
Erythropoiesis, 525, *525*
  disorders of, 534, 535*t*
Erythropoietin (EPO), 510, 512*t*
Eschar tissue, 127
Esophageal gland, *656,* 663
Esophageal hiatus, *656,* 663
Esophageal sphincter, 663
Esophagus, *332, 336, 337, 340, 631, 634, 655, 665*
  anatomy, 663
  parathyroid gland, *507*
  prenatal development, *513, 680*
  ulcers, 668, *668*
Estrogens, 508, *508,* 509–510, *510,* 512*t*
  mimics, 715
Ethmoidal cells, 163, *163*
Ethmoid sinus, 155, *155, 159,* 163, *163*
Eumelanin, 114
Eustachian tube, 471–472, *471–472*
Eversion, of foot, 219, *219*
Excitability
  muscles, 237
  neurons, 353
Excitable tissues, 72–74
Excitation, muscular, 251
Excitation-contraction coupling, 251
Excretion, 686
Excursion, of mandible, 217, *218*
Exfoliation, 62, *62*
Exocrine acinar cells, 677, *677*
Exocrine glands, *75–76,* 75–78, 498–499, *499*
  comparative anatomy, 498–499, *499*
  secretions, 76, *77*
  simple and compound, 76, *77*
Exocytosis, 35, *35*
Expiration, 631
Exploratory surgery, 4
Extensibility, muscular, 237
Extension of joints, 213, *214*
Extensor(s)
  neck, 277*t*
  retinaculum, 303*t,* 316*t, 318*
Extensor spasms, 394
External acoustic meatus, 160, *161*
External anal sphincter, 287*t, 288*
External genitalia, 704, 704*t,* 724
  prenatal development, 727, *728–730,* 730
External os, *718,* 722
External urethral orifice, 696, *697*
External urethral sphincter muscle, 287*t, 288*
Exteroceptors, 461
Extracellular face, 30–31
Extracellular fluid (ECF), 30
  tissue, 54
Extracellular matrix, primary tissue, 54
Extracorporeal membrane oxygenation (ECMO), 648
Extraembryonic membranes, 92–95, *94*
Extra nipples, 122
Extrinsic muscle, 241
Eyeball, *429*
  anatomy, 482–484, *482–484*
Eyebrow, 480, *480*
Eyelashes, 480, *481*
Eyelids, 480, *480, 493*
Eye(s), 480–490. *See also* Retina
  development, 491, *493*
  image formation, 485, *486,* 486*t*
  movements, *430*
  muscles, 482
  neural components, 484–485, *485*
  oculomotor nerve, *430*
  optical components, 483–484, *483–484*
  visual projection pathways, 489–490, *490*

F

Facets of bone
  articular, patella, *195,* 196–197
  costal, *171,* 172
  inferior articular, 169–170, *170*
  ribs, 174, *174*
  vertebrae, 169–170, *170–171,* 172
Facial muscles, 268, *268–269,* 268*t*–271*t, 271*
Facilitated diffusion, 34, *34*
Factor XII, 534
Fallopian tube, 721
  gametogenesis, 85–86
False ribs, 174, *174*
Falx cerebelli, *402,* 403
Falx cerebri, 402, *402*
Fascia
  breast, *726*
  spermatic cord, *707*
Fascia adherens, 554, *554*
Fascicles
  nerves, 380, *381–382*
  olfactory nerve, 469, *469–470*
  skeletal muscle, *238,* 238–239, 247*t*
Fast glycolytic muscle fibers, 253–254, 253*t,* 254*t*
Fast-twitch muscle fibers, 253–254, 253*t,* 254*t*
Fat
  adipose tissue as, 67–68, *68,* 68*t*
  epicardial, *544*
  in heart, *542*
  hormones and, *504*
  subcutaneous fat, 113–114, *341*
Fat cells, 63
Fat pad, larynx, *636*
Fauces, 658
Feces, 673
Female reproductive system, 9, *11,* 715–734
  aging, 731
  disorders of, 732, 734*t*
  gonads, *499,* 509–510, *510*
  prenatal development, 727, *728–730,* 730
Female(s)
  back and gluteal region, *339*
  bladder anatomy, 697, *697*
  pelvic cavity, *342*
  pelvis, 193, *194,* 194*t*
  retroperitoneal viscera, *336*
  thorax and abdomen, *338*
  trunk, anatomy, *333*
  urinary tract, *685,* 686, *716*
Femoral region, 16, 193
Femur, 193, 195–196, *195–196, 337*
  fractures, 196, *196*
  greater trochanter, *339*
Fenestration
  capillaries, 568, *569*
  liver, *675*
Fertilization, *86,* 86–87
  membrane, *86,* 87

Fetal alcohol syndrome (FAS), 103
Fetal breathing, 647, *648*
Fetal circulation, *604*
Fetal stage, 96, *97–98,* 99, 99*t*
  prenatal development, 87, 88*t*
Fibers, 63–64
  muscle, 236, *236,* 244–247, *244–247*
Fibrillin, 67
Fibrin, *533,* 533–534
  plasma, 522, 522*t*
Fibrinogen, *533,* 533–534
  plasma, 522, 522*t*
Fibroblasts, 63
Fibrocartilage, 68, *69,* 69*t,* 70
  hip joints, 224, *225*
Fibrosis, 80, 649
Fibrous actin, 245, *245*
Fibrous capsule, 686–687, *687–688*
Fibrous cells, 28, *28*
Fibrous connective tissue, *63–66,* 63–67, 63*t*–66*t*
Fibrous joints, 206, *207*
Fibrous rings, 544, *546*
Fibrous skeleton, 544, *547*
Fibula, 197, *197, 347*
Fibularis tertius tendon, 316*t, 317*
Fight-or-flight reaction, 443
Filiform papillae, 466, *467*
Filtration
  membrane transport, 33–36, *34–35,* 692, *693*
  pores, 568, *569, 693*
  slits, 691, 692, *693*
Filtration pores, 33
Fimbriae, *716–718, 721*
Fingers (digits), 16
  anatomy, *344*
  movements of, 217, *218,* 219
First-class lever, 242, *243*
First-degree burns, 127, *127*
First gap (G_1) phase, cell cycle, 47
Fissures
  horizontal, 639, *640*
  inferior orbital fissure, 164, *164*
  longitudinal fissure, 399, *400–401,* 415, *426*
  oblique, 639, *640*
  oral, 658
  palpebral, 480, *480*
  superior orbital, 162, *162, 430, 432*
  transverse cerebral fissure, 399, *400–401*
Fixative, tissue sections, 54–55
Fixator muscles, 241
Flagella, 38
Flat feet, 202*t*
Flexion
  of foot, 219, *219*
  hand and fingers, 217, *218,* 219
  of head, 217, *218*
  of joints, 213, *214*
Flexion lines (creases), 116, *344–345*
Flexor(s)
  carpal tunnel syndrome, 307, *307*
  neck, 277*t*
  reflex, 393, 393*t*
  reticnaculum, 188, 303*t, 307*
  spasms, 394
Floating kidney, 687, *700*
Floating ribs, 174–175, *175*
Folia, 410, *411–412*
Foliate papillae, 467, *467,* 659, *659*
Follicles, ovarian, 716–717, *716–717, 719–720* 720
Follicle-stimulating hormone, *501,* 502–503, 503*t, 504,* 509–510, *510*
Follicular cells
  ovarian, 716–717, *716–717, 720*
  thyroid anatomy, 506, *506, 566*
Follicular fluid, *719*
Folliculogenesis, 717, *718–719,* 720
Fontanels, 176, *177*
Food and water intake, 415
Foot
  anatomy, *347–349*
  development, 200–201, *201*
  movements of, 219, *219*
  muscles of, 316*t*–323*t, 317–321, 323*
Foot processes, 691, *693*
Foramina, 155, *155,* 159*t*
  apical, 661
  cribriform (olfactory), 163, *163, 429*
  greater palatine, *163,* 165
  infraorbital, 164
  interventricular, *403,* 404
  intervertebral, 169, *170*
  jugular, 161, *434–436*
  lacerum, 162, *162*
  magnum, *157,* 161, *332, 436*
  mandibular, 165, *165*
  mastoid, 161
  mental, 165
  obturator, 190, *191–192*
  olfactory, 468, *469–470*
  optic, *429*
  ovale, 162, *162,* 557, *558–559, 604*
  parietal, *156,* 160
  rotundum, 162, *162*
  sacral, *172,* 172–173
  spinosum, 162, *162*
  stylomastoid, *157,* 161, *433*
  supraorbital, 160
  transverse, 171, *171*
  vertebral, 169, *169*
  zygomaticofacial, 165
Forearm
  anatomy, *344*
  muscle, 301*t*–302*t, 302*
Forebrain, 366, *366,* 413–426
  functions, 425*t*
  structures, 425, *426*
Foregut, 656–657, 678, *679–680*
Forelimb, evolution of, 188, 190
Formed elements, blood, 71, 520–521, *521,* 522*t*
Fornices, *718,* 724
  posterior and anterior, *716–717*
Fossae
  coronoid, *187,* 187–188
  cranial, 159, *160*
  cubital, *344*
  iliac, 191, *192*
  infraspinous, 186, *186*
  intercondylar, 195, *195*
  lacrimal, 165
  mandibular, 160, *161*
  nasal, 163, *163,* 633, *634–635*
  olecranon, 187, *187*
  ovalis, *546,* 601, *602, 604*
  popliteal, *314,* 315*t, 346, 348*
  radial, 187, *187*
  subscapular, 186, *186*
  supraclavicular, *331, 338*
  suprascapular, 186, *186*
  supraspinous, 186, *186*
  triangular, *470–471*
Fourth-degree burns, 127, *127*
Fovea capitis, 193, 195, *195*
Fovea centralis, 482–484, *482–485*
Fractures
  avulsion, 202*t*
  classification, 145, 145*t,* 146, *146*
  clavicular, 185
  Colles fracture, 202*t*
  contrafissura, 179–180, *180*
  depressed, 179–180, *180*
  epiphyseal, 202*t*
  femoral, 196, *196*
  healing process, 146, *146*
  Le Fort, 179–180, *180*
  linear, 179–180, *180*
  oxalate intake and, 145
  Pott fracture, 202*t*
  skull, 179–180, *180*
  vertebral, 179–180, *180*
Freckles, 116
Free edge (nails), 119–120, *120*
Free nerve endings, 461–463, *462,* 462*t*
Freeze-fracture method, 26
Frenulum, penis, 713, *714*
Friction ridges, 112, 116
Friction rub, 543
Frons, *331*
Frontalis muscle, 270*t, 271*
Frontal lobe, *400–401,* 416, 425*t, 426, 427*
Frontal plane, 12, *12, 331*
Frontal (coronal) plane, 12, *12*
Frontal sinus, 155, *155*
Fulcrum, muscles, 241, *241*
Full-thickness burns, 127, *127*
Functional magnetic resonance imaging (fMRI), 5
Functional morphology, anatomy and, 2
Fundus
  eyeball, 484, *485*
  female reproductive tract, *718*
  gallbladder, *676,* 676–677
  stomach, 664, *665–666,* 667, 667*t*
  uterus, *718,* 721–722, *722*
Fungiform papillae, 467, *467,* 659, *659*
Fusiform cells, 28, *28*
Fusiform muscles, 238–239, *239*

G

Galea aponeurotica, 270*t*
Gallbladder, *334, 341, 585, 589, 655, 657, 674*
  anatomy, *676,* 676–677
Gallstones, 677
Gametes, 85, 704
Gametogenesis, 85–86
Gamma globulins, 522, 522*t*
Ganglia, 353
  anatomy, 382, *382*
  basal ganglia, 419, *419*
  ciliary, *430,* 450, *451*
  coccygeal, *447*
  collateral (prevertebral), 449, *449,* 450*t*
  geniculate, *433*
  inferior, *434*
  intramural, 450
  mesenteric, 449, *449*
  otic, *434,* 450, *451*
  parasympathetic, *656*
  paravertebral, 446
  pterygopalatine, 450, *451*
  retina, 486–489, *487–489*
  sacral, *447*
  spiral ganglion of cochlea, *472–473,* 474
  superior, *434*
  sympathetic chain, 446, *446–447*
  terminal, *444,* 450, *451*
  thoracic, *446*
  trigeminal, *432*
  vestibular, *434, 472*
Ganglion cells, *487,* 488
Gangrene, 80
Gap junctions, 38, *39,* 40
Gases, blood, 522, 522*t*
Gas exchange, respiratory system, 631
Gastric glands, 664, *665–666,* 667, 667*t*
Gastric lipase, 664
Gastric pit, 664, *665–666,* 667, 667*t*
Gastric rugae, *665*
Gastrin, 510, 512*t*
Gastritis, 668, *668*
Gastroduodenal sphincter, 664, *665–666,* 667, 667*t*
Gastroesophageal reflux disease, 663
Gastrointestinal bleeding, 681
Gastrulation, 89, *90*
Gated channels, 33, *33*
Gaze centers, 410
G cells, 667
Gemellus superior and inferior muscles, 311*t, 312*
Genetic anomalies, 100–102
Genitalia, 704, 704*t*
Genitoglossus muscle, *273*
Germ cells, 510, *510*
  male, 707, *708,* 709, *710*–712
Germinal epithelium, 707, *708*
Germinal matrix, 123–124, *124*
Germinative layer, 123, *123*
Germ layers, derivatives, 89, *90,* 92*t*
Gestation, 87
Gestational diabetes, 734*t*
Ghrelin, 510, 512*t*
Gingiva, *207,* 208, 660–661, *660–661*
Gingivitis, 661
Glabella, 160
Gladiolus, *173,* 174
Glands
  anatomy, 75
  prenatal development, 124, *124*
  tissue, 75–78
Glans, *342*
  female, 724, *725*
  male, 713–715, *714, 729*
Glans (penis), *706*–707

Glaucoma, 484
Glenohumeral joint, 185, 221–223, *223*
Glenohumeral ligament, 221–223, *223*
Glenoid cavity, 186, *186*
Glenoid labrum, 221–223, *223*
Glial cells. *See* Neuroglia (glial cells)
Globin proteins, 524, *524*
Globular actin, 245, *245*
Globulins, plasma, 522, 522*t*
Globus pallidus, 419, *419, 426*
Glomerular capsule, *690,* 691, *699*
Glomerular filtration, 691, *691*
Glomerulus, 687, *688–690, 693*
  olfactory system, 469, *469–470*
Glottis, 636, *636*
Glucagon, 509, *509*
Glucocorticoids, 508, *508*
Glutamate, 362–363, *363*
Gluteal fold, *339*
Glycemic control, muscles, 237
Glycocalyx, 31, *36,* 38
Glycogen
  cardiac muscle, 554, *554*
  muscle fiber, 245
Glycolipids, 31
Glycoproteins, 32
Glycosaminoglycans, 64
Goblet cells, 57
  nose, 633, *633–635, 638–639*
  small intestine, 669, *669–670*
Goiter, 515, *515*
Golgi complex, 43, *44–45*
Golgi vesicle, 43
Gomphoses, *207,* 208, 211*t*, 660–661, *660–661*
Gonadal ridge, 727, *728–730*
Gonadotropin-releasing hormone, *501,* 502, 502*t*, *504*
Gonadotropins, 502–503, 503*t*, *504*
Gonads, *499,* 509–510, *510,* 704, 704*t*
  descent of, 730, *730*
Gout, 231*t*
Graafian follicles, 720
Gracile fasciculus, *376–377,* 377–378
Grafts, skin, 128
Granular (juxtaglomerular) cells, 694, *695*
Granule cells, 410, *411–412*
  nonspecific granules, 527
  olfactory system, 469, *469–470*
  specific granules, 527
Granulocytes, 521, *521,* 522*t*, 527, *528–529,* 528*t*–529*t*, 530
Granulosa cells, 509–510, *510, 719,* 720, *720*
Gravitational force, auditory projection pathway, *477,* 477–478
Gray matter, 402, *403,* 409, *426*
  spinal cord, *374,* 375
Greater omentum, 18, *334*
Great vessels, systemic circuit, 541
Groin, injury, 325*t*
Gross anatomy, 2
Ground substance, tissue, 54, 64
Growth
  bones, 140–142, *141–142*
  hair, 119, *119*
  tissue, 79
Growth hormone, *501,* 503, 503*t*, *504*
  bone growth and, 144
Growth hormone-releasing hormone, *501,* 502, 502*t*, *504*
Guard hairs, 471, *471*
Gubernaculum, *730*
Guillain-Barré syndrome, 394*t*
Gum disease, 661
Gustation. *See* Taste
Gyri, 399, *400–401,* 415–416, *416, 479*
  taste and, 468, *468*
G-zero (G_0) phase, cell cycle, 47

H

H_2 receptor blockers, 668
Habituation, 410
Hair bud, 123–124, *124*
Hair follicle, 116–118, *117*
Hair matrix, 117
Hair peg, 123–124, *124*
Hair(s), 116–119
  color and texture, 118, *118*
  cycle, 119, *119*
  distribution and types, 116–117, *118*
  functions, 117, 117*t*
  growth and loss, 119, *119*
  guard hairs, 471, *471,* 480, *481,* 633
  inner ear, inner and outer cells, *473–474,* 474–475, *477*
  olfactory, 468, *469–470*
  prenatal development, 123–124, *124*
  receptors, *117,* 118, *462,* 462*t*, 463
  stereocilia, *473,* 474, *477*
  structure, *117,* 117–118
  taste hairs, 467, *467*
  vibrissae, 633
Hallux, *198,* 199, *199, 348*
Hamstring injuries, 316, 325*t*
Hamulus, 188, *189*
Hand
  anatomy, *345*
  bones of, 186, 188, *189*
  development, 200–201, *201*
  movements of, 217, *218,* 219
  muscles of, *308–309,* 308*t*–309*t*
  palmar surface, *344*
  tendons, 63–64, *64*
Haploid cells, 85, 709, *710*
Haptoglobulin, 522, 522*t*
Hard palate, 164, *164, 631, 634, 658*
Harvey, William, 564
Haustra, 671, *672*
Haversian canal, 136, *137*
Haversian system, 136, *137*
Hawking, Stephen, 380, *380*
H bands (striated muscle), *246,* 246–247
Head
  anatomy, 13, *14, 331*
  arteries of, 576*t*–578*t*, *577–578*
  median section, *332*
  movements, 217, *218*
  muscles of, 268, 277*t*–278*t*, *278*
  veins, 579*t*–580*t*, *580–581*
Head bulge (embryo), 92, *97*
Hearing, 470–479
  binaural, 475, *476*
  ear anatomy, 470–474, *470–474*
  vestibulococclear (VIII) nerve, *434*
Heart, *335, 340, 446*
  aging and, 558–559
  apex, 541, *541, 544*
  atria, *340*
  base, 541, *541–543*
  blood flow pathway, 547–548, *549*
  chambers of, 545, *546,* 547–548
  disease, 559, 560*t*
  endocrine cells in, 510, 512*t*
  fetal, *559*
  gross anatomy, 543–545, *544–545*
  lungs and, *642,* 642–643
  nerve supply, 554–555
  position, size and shape, *340,* 541–542, *541–542*
  prenatal development, 557–558, *558,* 601, *601–602, 648*
  respiratory system, *631, 647*
  vagus nerve, *435*
  wall of, *543,* 543–544
Heart block, 553
Heart bulge, 92, *97, 680*
Heart tube, 257–258, *258, 679*
Heart valves, 546–548
  atrioventricular, *548–549*
  blood vessels, *565*
  left AV, *544,* 546, *546, 549*
  mitral, 546
  operation, *548–549*
  right AV, *544,* 546, *546, 547, 549*
  semilunar, 546, *548*
  tricuspid, 546, *547*
Heat
  muscle production of, 237
  thermoreceptors, 461
Helicobacter pylori, 668
Helix (ear), *470–471*
Hemangiomas, 116
Hematocrit, 521, 524
Hematology, 520
  aging, 534
Hematoma, 115
Hematuria, 692
Heme group, 524, *524*
Hemidecussation, 489–490, *490*
Hemidesmosomes, 39
Hemiplegia, 394
Hemoblasts, 601, *601*
Hemodialysis, 700
Hemoglobin (Hb)
  concentration, 524
  structure, 524, *524*
  synthesis disorders, 534, 535*t*
Hemolysis, 526
Hemolytic anemia, 534, 535*t*
Hemolytic disease of the newborn, 526
Hemophilia, 535*t*
Hemopoiesis, 524–525
Hemopoietic stem cell (HSCs), 525, *525, 531*
Hemopoietic tissue, 524–525
Hemorrhagic anemia, 534, 535*t*
Hemorrhoids, 671, *672*
Hemostasis, *533,* 533–534
Heparin, 63, 530
Hepatic ducts, *675–676,* 676–677
Hepatic lobules, 673, *674–675*
Hepatic macrophages, 530
Hepatic portal system, *589,* 589*t*, 657, *674–675*
Hepatic sinusoids, 675, *675*
Hepatic triad, *675,* 676
Hepatocytes, 673, *674–675,* 675
  capillaries, *569*
Hepatopancreatic ampulla, *676,* 677
Hepatopancreatic sphincter, *676,* 677
Hepcidin, 510, 512*t*
Heptitatis C, 732–733
Herneated discs, 180, *180*
Hernias, 289, *289*
  hiatal, 680*t*
Hess, Walter, 423
Hiatal hernia, 680*t*
Hilum, 639, 686–687, *687*
Hindbrain, 366, *366,* 406, 413*t*
Hindgut, 657, *679*
Hinge joints, *212,* 213
Hip
  bones, 190, *191*
  human and chimpanzee, 193, *193*
  joints, 224–225, *225,* 229*t*
  muscles, 310, *310,* 310*t*–311*t*, *312*
Hippocampus, 418, *418*
  olfactory projection pathways, 470, *470*
Hirschsprung disease, 452
Histamine, 63, 530
Histological sections, 54–55, *55–56*
Histology (microscopic anatomy), 2, 54–81
  blood vessels, 564–565, *565*
  endometrium, 722, *722*
  retina, 487, *487*
Histopatholoy, 2
Holocrine glands, *77,* 78
Homeostasis, 443
Horizontal cells, *487,* 488
Horizontal plane, 12, *12*
Hormones, 75–78. *See also* Corticosteroids
  aging and, 514
  in blood, 522, 522*t*
  bone growth and, 144
  disorders, 515, 516*t*
  endocrine system and, 498–499, *499, 501*
  enteric, 510
  gonadal, 509–510, *510*
  hypothalamic, 415, *501,* 502, 502*t*
  insensitivity, 515, 516*t*
  metabolism, 674*t*
  parathyroid, 506, *507*
  steroid hormones, 507–508, *508*
  thymopoietin, 505, *505*
  thymosin, 505, *505*
  thymulin, 505, *505*
  thyroid, 506
  trophic, 502–503, 503*t*
  tropic, 502–503, 503*t*
Horner syndrome, 457*t*
Horns (cornua)
  anterior (ventral), *374,* 375
  coccygeal vertebrae, 173, *173*
  hyoid, 166, *166*
  lateral, *374,* 375
  posterior (dorsal), *374,* 375
Horseshoe kidney, 698
Human papillomavirus, 733
Humeroradial joint, *223,* 223–224
Humeroulnar joint, *223,* 223–224
Humerus, 186–187, *187, 334*

Huntington disease, 422
Hyaline cartilage, 68, *69,* 69*t,* 70, *638*
Hyaline membrane disease, 648
Hyaloid canal, 482–484, *482–484*
Hydrocortisone, 508, *508*
Hydronephrosis, 700*t*
Hydroxyapatite, 135–136
Hyerreflexia, 394
Hymen, 724
  prenatal development, *728*
Hyoglossus muscle, *273*
Hyoid muscles, 275*t, 276*
Hyperadduction, 214, *215*
Hypercalcemia, 506
Hyperemesis gravidarum, 93, 734*t*
Hyperextension, joints, 213, *214*
Hyperopia, *486,* 486*t*
Hyperplasia, 79
Hypersecretion disrorders, 515, 516*t*
Hypertension, 605*t*
Hypertonic urine, 691
Hypertrophy, 79
Hyphoblast, 88, *90*
Hypocalcemia, 506
Hypochondriac region, 16
Hypodermis, 109, *110*
  structure, 113–114, 114*t*
Hypogastric (pubic) region, 16
Hypoglossal canal, 161
Hyponychium, 120, *120*
Hypoparathyroidism, 506
Hypophyseal portal system, 500, *501–502,* 502–503, 503*t, 504*
Hypophyseal pouch, 512–513, *513–514*
Hypophysis. *See* Pituitary gland
Hyposecretion disorders, 515, 516*t*
Hypospadias, 715, 732*t*
Hypothalamo-hypophyseal tract, 500, 515
Hypothalamus, *414,* 415, 425*t, 426, 499*
  anatomy, 500, *501*
  emotional responses, 423
  hormones, 502, 502*t*
  olfactory projection pathways, 470, *470*
  prenatal development, *513*
  respiratory function, *646*
  visceral reflexes, 444
Hypothenar eminence, *344–345*
Hypothenar muscle group, *308,* 309*t*
Hypoxemia, 648

I

I bands (striated muscle), *246,* 246–247
Ileocecal junction, 669, *669–670*
Ileocecal valve, 669, *669–670*
Ileum, *589,* 669, *669–670*
Iliac crest, 190, *191–192, 337–339*
Iliac spine, 191, *192*
Iliofemoral ligament, 224, *225*
Iliopsoas muscles, *310,* 310*t*
Iliotibial tract, 311*t, 313–314, 347*
Ilium, 190–191, *191–192, 333, 337–338*
Image formation, 485, *486,* 486*t*
Immunoglobulin A, 661
Implantation, embryonic, 88, *90*
Incisive foramina, 164, *164*
Inclusions, 46
Incontinence, 698, 700*t*
Incus, 166, 471, *471,* 472, *472, 475*
Indirect attachment, skeletal muscle, 239–240, *240*
Infarction, 80
Infectious disease
  birth defects and, 103
  skin and, 109
Infectious mononucleosis, 535*t*
Infective endocarditis, 559, 560*t*
Inferior nasal concha, 163, *163,* 165
Inferior palpebral sulcus, *331*
Inferior peduncles, 410–411, *411–412*
Inferior vertebral notche, 169, *170*
Infertility, 713, 732*t*
Infrahyoid muscle group, 275*t, 276*
Infundibulum, 415
  female reproductive tract, *718,* 721, *721*
  pituitary gland, 500
Inguinal canal, 289, *289,* 705, *706–707, 730*
Inguinal hernia, 289, *289*
Inguinal region, 16
Inguinal ring, 705, *706–707*
Inhibin, 509–510, *510,* 512*t,* 707
Inner-ear cavity, 155, *158*
Inspection, anatomoical, 3
Inspiration, 631
Insula, *400, 403,* 416, *418,* 425*t, 426*
  olfactory projection pathways, 470, *470*
  taste and, 468, *468*
Insulin, 509, *509,* 511*t*
Insulin-like growth factors (IGFs), 503, *504,* 510, 512*t*
Integrating center, 392
Integument, 109
Integumentary system, 108–128
  aging, 125
  clinical perspectives, 123–128
  hair and nails, 116–122
  prenatal development, 123—124, *123–124*
  skin and subcutaneous tissue, 109–116
Intercalated cells, 695
Intercalated discs, 73, 554, *554*
  cardiac muscle, *254,* 254–255, 255*t*
Intercellular clefts, 568, *568–569*
Intercondylar eminence, 197, *197*
Intercostal nerves, 384, *384–385*
Interdigitating folds, 554, *554*
Interfusal fibers, *462,* 462*t,* 463
Intermaxillary suture, *155–157,* 164
Intermediate filaments, 40
Intermediate layer, 123, *123*
Intermediate muscle fibers, 253–254, 253*t,* 254*t*
Intermuscular septa, 294
Internal genitalia, 704, 704*t*
  prenatal development, 727, *728–730,* 730
Internal os, *718,* 722
Interneurons, 354, *354*
Interoceptors, 461
Interosseous border, *187,* 188
Interosseous membrane, *187,* 188, 197, *197*
Interphalangeal joints, muscles and, 303*t*–306*t, 304–306*
Interphase, cell cycle, 47
Interpubic disc, 190, *191–192*
Intersegmental reflex, 393, 393*t*
Interstitial cells, 510, *510,* 707, *708*
Interstitial fluid, 30
  tissue, 54
Interstitial growth, bone elongation, 143
Interstitial lamellae, compact bone, 136, *137*
Intertrochanteric crest, 195, *195*
Intertubercular sulcus, 186–187, *187*
Intervertebral discs, *167–168,* 167–175, 169, *169, 332, 337, 342*
  development, *177,* 177–178
  herniation, 180, *180*
Intestinal crypts, 670, *670*
Intestines. *See also* Large intestine; Small intestine
  celiac circulation, *585*
  regional anatomy, *334*
Inteumentary system, 9, *10*
Intracapsular ligaments, 226, *226–227*
Intracellular face, 30–31
Intracellular fluid (ICF), 30
Intramembranous ossification, 139–140, *140, 141*
Intramuscular injections, 315
Intraperitoneal region, 18, 658
Intravenous cannula, 592
Intrinsic muscle, 241
Invasive imaging, 4
Inversion, of foot, 219, *219*
Inverted retina, 491, *493*
In vitro fertilization (IVF), 50
Involuntary muscle contractions, 73, 236
Involution, pineal gland, 505
Ionizing radiation, 4
Ipsilateral reflex, 393, 393*t*
Iris, 482–484, *482–484, 493*
Iron-deficiency anemia, 534, 535*t*
Ischemic phase, menstruation, 724
Ischiocavernosus muscles, 287*t, 288*
Ischiofemoral ligament, 224, *225*
Ischium, 190–191, *192*
Islets of Langerhans, 508–509, *509*
Isthmus
  female reproductive tract, *718*
  thyroid gland, 505–506, *505–506*
  uterine tube, 721

J

Jaundice, 115–116
Jaw, temporomandibular joint, 220, *221*
Jejunum, *15, 657,* 668, *669–670, 676,* 676–677
Joint capsule, 210, *210*
  strength and tautness, 220
Joint cavities, glenoid, 186, *186*
Joint(s)
  acromioclavicular, *173,* 185
  ankle, *228,* 228–229
  atlantoaxial, 170, *170*
  atlanto-occipital, 170, *170*
  cartilaginous, 208, *209*
  classification, 206–208, *207, 209,* 211*t*
  clinical perspectives, 230–231, *230–232,* 231*t*
  costovertebral, *178,* 178–179
  dislocation, 230–231, *230–232,* 231*t*
  elbow, *223,* 223–224
  fibrous, 206, *207,* 208
  glenohumeral, 185
  hip, 224–225, *225*
  interphalangeal, 303*t*–306*t, 304–306, 344–345*
  jaw joint, 220, *220*
  knee, 225–228, *226–227*
  metacarpophalangeal, 303*t*–306*t, 304–306, 344–345*
  prostheses, 231, *232*
  range of motion, 219–220
  sacroiliac, *172,* 173, 190, *191–192*
  shoulder, 221–223, *223*
  skeletal system, 205–232
  sternoclavicular, 185, *331*
  synovial, 209–230, 229*t*
  temporomandibular, 165, *165*
Jugular notch, *173,* 174
Junctional folds, 249
Juxtaglomerular apparatus, 694, *695*
Juxtamedullary nephron, *689–690,* 689, 694

K

Kartagener syndrome, 38
Keratin, 62
  epidermis, 110–111, *111*
  skin function, 109
Keratinized epithelium, *60,* 62
Keratinocytes, 110–111, *111*
  life cycle, 112
  stratum spinosum, 111, *111*
Keratohyalin granules, *111,* 111–112
Kidney(s), *336, 341*
  anatomical variation, 6, *7*
  anatomy, 685, *685,* 686–687, *687*
  ascent, 698
  developmental abnormalities, 698
  endocrine cells in, 510, 512*t*
  horseshoe, 698
  nephron, 689, *690,* 690–695, *692–693, 695*
  perineal fat, *341*
  prenatal development, *728*
  renal circulation, 687, *688–689,* 689
  renal innervation, *449,* 689
  vagus nerve, *435*
Kidney stones, 696
Killing zone, neutrophils, 529
Kinetochore, 48, *49*
Kinocilium, 476, *477–478*
Klinefelter syndrome, 100
Knee
  anatomy, *346*
  bones of, 195, *196–197*
  injuries, 227, *227–228*
  joint, 225–228, *226–227,* 229*t*
  muscles, *313–315,* 313*t*–315*t, 346*
Kupffer cells, 530
Kyphosis, 147, *147,* 168, *168*

L

Labia (lips), *331*, 658–659
Labial frenulum, *658*, 658–659
Labial glands, 659
Labial mucosa, 659
Labialscrotal folds, 727, *728–730*, 730
Labia majora, 724, *725*, *729*
Labia minora, 724, *725*, *729*
Labium majus, *342*, *716–717*
Labium minus, *342*, *716–717*
Labyrinth, 163, *163*
Lacrimal apparatus, 480, *480–481*
Lacrimal caruncle, 480, *480–481*
Lacrimal (tear) gland, *433*
Lacrimal (tear) glands, *433*, 480, *481*
Lacrimal sac, 480, *481*
Lacteal capillary, 669
Lactiferous duct, 725–726, *726*
Lacunae, 68, 134
  penis, 714, *714*
Lambdoid suture, *156*, *158*, 160
Lamellae, 70
  compact bone, 136, *137*
Lamellar corpuscle, *462*, 462*t*, 463
Lamina (blood vessels), *565*, 566
  basal, 568, *569*
Lamina (vertebrae), 169, *169*
Lamina propria, 78, 655, *655–656*, *666*
Langerhans cells, 111, *111*
Language, brain and, 423–424, *424*
Lanugo, 116
Lap (squamous) suture, 206, *207*, 208, 211*t*
Large intestine, *334–335*, *669*. *See also* Colon
  anatomy, 671, *672*, 673
Laryngeal prominence, 635, *636–637*
Laryngopharynx, *634*, 635, 663
Larynx, *332*, *335*, *631*, *634*, 635–637, *636–637*
  prenatal development, *513*
Lateral cuneiforms, 198, *198*
Lateral ligament, 221, *221*
Lateral longitudinal arch, 200, *200*, *348*
Lateral mass (cervical vertebrae), 169, *170*
Lateral pterygoid plates, 162, *162*
Lateral spinal tracts, 375, *376*, 376*t*, 378, *379*
Lateral sulcus, *400–401*, 416, *420*, *426*
Learning strategies, 330
Lecithin, 673
Le Fort fractures, 179–180, *180*
Left colic (hepatic) flexure, 671, *672*
Left lower quadrant, 15, *15*
Left upper quadrant, 15, *15*
Leg
  anatomy, *346–348*
  bones of, 193, 195–199
  injuries, 325*t*
  muscles of, *313–315*, 313*t*–315*t*
Leg buds, 92, *97*
Leiomyomas, 734*t*
Lens, 482–484, *482–484*
  fibers, *483*, 484, *484*
Lens pit, 491, *493*
Lens placode, 491, *493*
Lens vesicle, 491, *493*
Leptin, 510, 512*t*
Lesions, skin cancer, 126
Lesser omentum, 18
Leukemia, 535
Leukocytes, 63, 71, 521, *521*, 522*t*, *527*, 527–532, *528–529*, 528*t*–529*t*, *531*
  disorders, 535
  life cycle, 530–532, *531*
  types of, 527, *528–529*, 528*t*–529*t*
Leukocytosis, 535
Leukopenia, 535
Leukopoiesis, *531*
Levator anguli oris muscle, 270*t*
Levator ani muscles, 287*t*, *288*
Levator labil superioris muscle, 270*t*
Levator palpebrae superioris muscle, 270*t*, *271*
Levator scapulae muscle, *296*, 296*t*
Levers, muscles as, 241–242, *241–243*
Leydig cells, 510, *510*, 707, *708*
Ligament(s)
  ankle, *228*, 229
  broad, 716–717, *716–718*, 722, *722*
  cardinal, *718*, 722, *722*
  coccygeal, *374*, 375
  coronary, 673, *674–675*
  cricotracheal, 636, *636*
  denticulate, *374*, 375
  elbow, *223*, 223–224
  falciform, 673, *674–675*
  hip, 224–225, *225*
  inguinal, 281*t*–283*t*, *333*, *338*, *595*
  of jaw, 221, *221*
  joints and, 210
  knee, *226–227*, 226–228
  ovarian, 716–717, *716–718*
  patellar, 196–197, *313*, 313*t*, *346*, *347*
  pelvic floor, 287*t*, *288*
  periodontal, *207*, 208, 660–661, *660–661*
  round, 225, *225*, 603, *604*, 673, *674–675*, *716–718*, 722, *722*
  shoulder, 221–223, *223*
  strength and tautness, 220
  suspensory, 482–484, *482–484*, 716–717, *716–718*, 722, *722*, 725–726, *726*
  thyrohyoid, 636, *636*
  tibiofibular, *228*, 229
  transverse acetabular, 224, *225*
  umbilical, *604*
  uterosacral, *718*, 722, *722*
  vestibular, 636, *636*
Ligamentum arteriosum, *542*, 603
Ligamentum teres, 225, *225*, 673, *674–675*
Ligamentum venosum, *604*
Light microscope (LM), 26, *27*
Liimbic system, 415
Limb buds, 200–201, *201*
Limbic system, 418, *418*, 425*t*, *426*
  respiratory function, *646*
Linea alba, *338*
Linea aspera, 195, *195*
Linea semilunaris, *338*
  abdominal wall, 281*t*–283*t*
Lines of bone
  epiphyseal, 143
  inferior nuchal, 161
  intertrochanteric line, 195, *195*
  spiral line, 195, *195*
  superior nuchal, 161
  supracondylar lines, 195, *195*
  temporal lines, *156*, 160
Lingual frenulum, *658*, 659, *659*
Lingual gland, 659, *659*
Lingual lipase, 661
Lingual papillae, 466, *467*, 659, *659*
Lingual tonsil, *634*
Lipid metabolism, 674*t*
Lipid rafts, 62
Lipids
  glycolipids, 31
  membrane lipids, 30–32, *30–32*
  phospholipids, 30, *32*
Lips, *634*, *658*, 658–659
Lithotripsy, 696
Liver, *334*, *341*, *585*, *655*, *657*
  anatomy, 673–676, *674–675*, 674*t*
  circulation, 676
  endocrine cells in, 510, 512*t*
  functions, 674*t*
  hepatic portal system, *589*, 589*t*
  hormones, *504*
  Kupffer cells, 530
  lobes, 673, *674–675*
  sinusoid capillaries, *569*
  vagus nerve, *435*
Liver bud, 678, *679–680*
Lobules
  breast, *726*
  earlobe, *470–471*
  exocrine glands, 76
Locomotion, spinal cord, 372
Longissimus musle, *284–286*, 284*t*–286*t*
Longitudinal tissue section, 55, *56*
Loop of Henle, 689, *689–690*, 694
Loose connective tissue, 64, *65*, 65*t*
Lordosis, 168, *168*
Lou Gerhig's disease, 380, *380*
Lower esophageal sphincter (LES), 663
Lower limb
  blood vessels, 594–599
  bones, 193, 195–199
  muscles, 310–324
Lower respiratory tract, 632, 637–643
Luetinizing hormone, *501*, 502–503, 502*t*, 503*t*, *504*
Lumbar cistern, 373, *374*
Lumbar curvature, 168, *168*
Lumbar enlargement, 372, *373*
Lumbar puncture, 375, 404
Lumbar region, 16, 372, *373*
Lumbar vertebrae, *167–168*, 167–175, 172, *172*, *337*
Lumbrical muscles, *308*, 309*t*, 322*t*, *323*
Lumen
  blood vessels, *565*
  esophagus, *656*
  small intestine, 669, *669–670*
  stomach, *666*
  tubule, *708*
Lung buds, 647, *648*, *680*
Lung cancer, 649
Lungs, regional anatomy, *334*
Lung(s), *334*, *336*, *340*, *341*
  heart and, *541–542*
  histology, *641*
  lobes, *335*, 639, *640*
  respiratory system, *631*
  vagus nerve, *435*
Lunule, 120, *120*
Lutein cells, 721
Lymphatic nodules, *616*, *666*, 670
Lymphatic system, 9, *10*
Lymphatic vessel
  liver, *675*
  small intestine, *670*
Lymphocytes, 521, *521*, 522*t*
  fibrous tissue, 63
  pulmonary, *642*
  structure, *529*, 529*t*, 530
Lymphoid hemopoiesis, 525
Lysosomes, 43, *44*, 45–46
  acrosome, 86
  osteoclasts, 135, *135*
Lysozyme, 661

M

Macrophages, 63, 530
  capillaries, *569*
  hepatic, *675*, 676
Macula
  densa, 694, *695*
  lutea, 482–485, *482–485*
  sacculi, 476, *477–478*
  utriculi, 476, *477–478*
Magnetic resonance imaging (MRI), 4–5, *5*
Magnification, 26, *27*
Major calyx, 687, *688*, *699*
Male reproductive system, 9, *11*, 705–715, *707*
  aging, 731
  disorders of, 731–732, 732*t*
  gonads, *499*, 509–510, *510*
  prenatal development, 727, *728–730*, 730
Male(s)
  back and gluteal region, *339*
  bladder anatomy, 696, *697*
  pelvic cavity, *342*
  pelvis, 193, *194*, 194*t*
  regional anatomy, *334–335*
  thorax and abdomen, *338*
  urinary tract, *685*, 686, *706*
Malignant tumors, 48, *48*
Malleoli, medial and lateral, 197, *197*, *347–348*
Malleus, 166, 471–472, *471–472*, *475*
Malpighi, Marcello, 564
Mamillary bodies, *401*, 415
Mammary glands, 78, 122, 122*t*, *504*, 725–726, *726*
  hormones, *504*
Mammary ridges, 122
Mandible, 165, *165*, *634*
  development, 176, *177*
  movements, 217, *218*
Mandibular division, *432*
Mandibular notch, 165, *165*
Manual region, 16
Manubrium, *173*, 173–174, *338*

Manus. *See* Hand
Marfan syndrome, 67
Marrow cavity, 133, *133*
Masseter muscle, *274,* 274*t*
Mass reflex reaction, 394
Mast cells, fibrous tissue, 63
Mastoid notch, *157,* 161
Mastoid part, 161, *161*
Matrix, osseous tissue, 135–136
Maxillae, 164
Maxillary division, *432*
Maxillary sinus, 155, *155, 159*
Meatus
  inferior, nasal cavity, *481*
  nasal, 633, *634–635*
Mechanical advantage, muscle(s), 241–242, *242*
Mechanical junctions, 554, *554*
Mechanical stress, spongy bone and, 138, *138*
Mechanoreceptors, 461
Meconium, 678
Medial lemniscus, 378, 406, *407–408*
Medial (deltoid) ligament, *228,* 229
Medial longitudinal arch, *199,* 199–200, *347–348*
Medial pterygoid plates, 162, *162*
Medial spinal tracts, 375, *376,* 376*t*
Median (midsagittal) plane, 12, *12*
Mediastinum, *16,* 17
Medical art, evolution of, *3*
Medical imaging, 4, *5*
Medical terminology, 20–22, 21*t*
Medulary cone, 372, *373*
Medulla
  hair matrix, 117
  ovarian, *716–717*
Medulla oblongata, *366,* 406–409, *407–408,* 413*t, 427, 634*
  auditory pathway, *476*
  gustatory projection pathway, 468, *468*
  respiratory system and, 645, *646*
Medullary cavity, 133, *133*
Megacolon, 452
Megakaryoblasts, 532
Megakaryocytes, 532, *533, 617*
Meiosis (reduction devision), 85
  oogenesis, *719*
  spermatogenesis, 709, *710*
Melanin, skin color, *114,* 114–115
Melanocytes, 110–111, *111*
Melanoma, 126, *126*
Melatonin, 505, 511*t*
Membrane-coating vesicles, 112
Membrane lipids, 30–32, *30–32*
Membrane proteins, 32–33, *33*
Membrane(s)
  of body, 16–20, 16*t*
  extraembryonic, 92–95, *93–94*
  fertilization membrane, *86,* 87
  tissue, 78–79
Membrane skeleton, 40
Membrane transport, 33–36, *34–35*
Membranous labyrinth, 161, *472,* 472–473
Membranous urethra, 696, *697*
Memory
  aids to, 437
  brain and, 424
Menarche, 731
Ménière disease, 493*t*
Meningeal layer, 402, *402*
Meninges, 17, 373–375, *374,* 402, *402*
Meningitis, 404
Meniscus, 210, 226, *226–227*
Menopause, 731
Menses, 724
Menstrual cycle, *723,* 723–724
Menstrual fluid, *723,* 724
Mentalis muscle, *271,* 272*t*
Mental protuberance, 165, *165, 331*
  muscles of, 272*t*
Mental spines, *156,* 165
Mental symphysis, 176, *177*
Mentolabial sulcus, *331*
Mentum (chin), *331*
Merkel cells, 111, *111*
Merocrine glands, 76–77, 120, 121, *121*
  prenatal development, 124, *124*
Meromelia, 201–202, *202,* 202*t*
Mesangial cells, 694–695, *695*
Mesencephalon, 366, *366*
Mesenchyme, 89, *90*
  intramembranous ossification, 139, *140*
  neural tube, 178, *178*
  optic development, 491, *493*
Mesenteries, 18, *19, 341, 342*
  anterior (ventral), 657
  circulation, *586,* 586*t*
  digestive tract, 657, *657*
  posterior (dorsal), 657
Mesocolon, 18, 657, *657, 672*
Mesoderm, 89, *90,* 92*t*
Mesometrium, *718*
Mesonephric duct, *699,* 727, *728, 728–730*
Mesonephros, *699, 728*
Mesosalpinx, *718,* 721, *722*
Mesothelium, prenatal development, 514, *514*
Mesovarium, 716–717, *716–718*
Metacarpophalangeal joints, muscles and, 303*t*–306*t, 304–306*
Metanephros, *699*
Metaphase
  meiosis, *710*
  mitosis, 48, *49*
Metaphysis, bone elongation, 141, *142*
Metaplasia, 79, 714
Metarterioles, 567, *570*
Metastases, 48, *48*
Metatarsals, *198,* 199, *347–348*
Metencephalon, 366, *366*
Microcephaly, 368
Microfilaments, 40
Microglial cells, 357*t,* 358, *358,* 530
Micrometer, cell size, 28
Microscopic anatomy, 2
Microscopy, cytology, 26–27, *27*
Microtubules, 37, *37,* 40, *42*
Microvasculature, 567–568
Microvilli, 36, *36*
  capillaries, *569*
  small intestine, 669, *669–670*
Midbrain, 366, *366, 401,* 406, *408,* 409, 413*t, 427*
  oculomotor nerve, *427–428, 430*
  optic nerve (II), *429*
  trochlear nerve, *430*
Middle-ear cavity, 155, *158, 492*
Middle-ear infection, 471
Middle nasal conchae, 163, *163*
Middle peduncles, 411, *411–412*
Midgut, 656–657, *679*
Midpalmar muscle group, *308,* 309*t*
Migraine headache, 438*t*
Milk lines, 122
Mineralization, bone, 132–133
Mineralocorticoid, 508
Mineral(s), metabolism, 674*t*
Minor calyx, 687, *688, 690, 699*
Mitochondria, cardiac muscle, 554, *554*
Mitochondrial DNA (mtDNA), 46
Mitochondrial matrix, 46
Mitochondrion, *44,* 46
Mitosis
  oogenesis and, *719*
  phases, 47–48, *49*
Mitotic (M) phase, cell cycle, 47
Mitotic spindle, 48
Mitral cells, 468–469, *469–470*
Mitral valve prolapse, 560*t*
Mixed acini, 662
Mixed nerves, 381
M line (striated muscle), *246,* 246–247
Modiolus, 270*t,* 473, *473*
Mole (nevus), 116
Molecules, 9
Monaxial joint, 212, *212*
Monocytes, 521, *521,* 522*t, 529,* 529*t,* 530
Monosynaptic reflex, 392, *392*
Mons pubis, *333*
  female genitalia, 724, *725*
  male genitalia, *716–717*
Morning sickness, 93
Morula, 88
Motor association area, *420,* 421, *422*
Motor cortex, *412,* 423–424, *424*
Motor efferent nervous system, *352,* 353
  neurons, 354, *354*
Motor end plate, *248,* 248–249
Motor homunculus, 421, *422*
Motor nerves, 381
Motor neurons, *72,* 248
  diseases, 380, *380*
  lower, 422
  upp, 422
Motor proteins, 37–38
Motor units, *249,* 249–250
Mouth, *658,* 658–662
Movement
  disorders, 422
  muscles, 236
Mucociliary escalatoor, 638–639, *638–639*
Mucosa, *638*
  digestive tract, 655, *655–656*
  large intestine, 671
  stomach, *666*
Mucosa-associated lymphatic tissue (MALT), *631,* 639–640, 655
Mucous cells, 664, *665–666,* 667, 667*t*
  neck cells, 667*t*
Mucous glands, *638*
Mucous membrane, 78, *78*
Mucous tripe, 667
Mucus, 661
Müllerian-inhibiting factor (MIF), 727
Multiaxial joint, 212, *212*
Multifidus muscles, *284–286,* 284*t*–286*t*
Multiple sclerosis, 361
Multipolar neurons, 356, *356*
Multipotent stem cells, 50
Multunit smooth muscle, 256, *256*
Muscarinic receptors, 454, *454,* 454*t*
Muscle fibers, 73, 236, *236*
  physiological classification, 253–254, 253*t,* 254*t*
  structural hierarchy of, 247*t*
  ultrastructure of, 244–247, *244–247*
Muscle(s)
  abdominal oblique, *280–283,* 281*t*–283*t, 333, 334, 338*
  abdominal wall, *280, 280–283,* 281*t,* 281*t*–283*t, 334*
  abductor digiti minimi, *308,* 309*t,* 322*t, 323, 348*
  abductor hallucis, 322*t, 323, 347–348*
  abductor pollicis brevis, *308,* 309*t*
  abductor pollicis longus, *306,* 306*t*
  action of, 220
  adductor brevis, 311*t, 312, 336–337*
  adductor hallucis, 322*t, 323*
  adductor longus, 311*t, 312, 333, 335–337*
  adductor magnus, *312,* 312*t, 335, 337*
  adductor pollicis, *308,* 309*t, 345*
  anatomy, 237–244
  arm, 297*t*–300*t, 298–300*
  arytenoid, *636*
  attachments, 239–240, *240*
  axial, 297*t*
  back, *284–286,* 284*t*–286*t, 339*
  biceps brachii, 221–223, *223,* 301*t, 302, 333, 339, 343–344*
  biceps femoris, *314,* 315*t, 346–347*
  blood supply, 250, *250*
  bones and levers, 241, *241*
  brachial, 297*t, 298,* 301*t, 302*
  brachioradioalis, *339, 344*
  bronchial, *641*
  buccal, 272*t, 331, 433*
  buccal region, 272*t*
  buccinator, 272*t,* 273*t,* 659, *659*
  bulbospongiosus, *706*–707
  cardiac, 73, *74,* 74*t,* 236, *254,* 254–255, 255*t,* 553–554, *554*
  cervical region, 272*t, 433*
  chewing and swallowing, 273*t*–276*t, 276*
  ciliary, 450, *451, 483,* 483–484
  circular, 239, *239, 666*
  common names, 265*t*
  connective tissue, 237–238, *238*
  contraction and relaxation, 250–253, *252*
  coracobrachialis, 297*t, 298–299, 334–335*
  cremaster, 705, *706–707*
  crural, 316*t*
  dartos, 705, *706–707*
  deltoid, 297*t, 298–299, 333, 338–339, 343–344*
  detrusor, 696, *697*

developmental and clinical perspectives, 257–259, 260*t*
digastric, *432, 433*
embryonic development, 257–258, *258*
erector spinae, *284–286,* 284*t*–286*t, 339, 341,* 644, *644*
extensor carpi radialis longus and brevis, *305,* 305*t, 344*
extensor digitorum, *305,* 305*t,* 316*t, 317, 318,* 322*t, 344, 348*
extensor hallucis longus, 316*t, 317–318,* 322*t*
extensor pollicis brevis and longus, *306,* 306*t*
extrinsic, 241
eye, *447, 451, 455,* 480, *480–481,* 482–483, *483*
facial, 268, *268–269,* 268*t*–271*t, 271*
fascicles, 237–239, *238–239*
femoral, 310, *310,* 310*t*–311*t, 312*
fibularis (peroneous) brevis and longus, *317–318, 321,* 321*t, 347–348*
flexor carpi radialis, *303–304,* 303*t*–305*t, 344*
flexor carpi ulnaris, 188, *189,* 303*t*–306*t, 304–306, 339, 344*
flexor digiti minimi brevis, *308,* 309*t,* 322*t, 323*
flexor digitorum brevis, 322*t, 323*
flexor digitorum longus, *320,* 321*t*
flexor digitorum profundus, *303–304,* 303*t*–305*t*
flexor hallucis, *320,* 321*t*
flexor pollicis brevis, *308,* 309*t*
flexor pollicis longus, *303–304,* 303*t*–305*t*
foot, 316*t*–323*t, 317–321, 323*
forearm, 301*t*–302*t, 302*
functional groups, 240–241
functions, 236–237
fusiform, 238–239, *239*
gastrocnemius, 316*t, 318–319, 346–348*
genioglossus, 273*t,* 659, *659*
gluteal, *284–286,* 284*t*–286*t,* 311*t, 312*
gluteus maximus, 193, 311*t, 312, 339*
gluteus medius, 193, 311*t, 312, 337, 339*
gluteus minimus, 193, 311*t, 312*
gracilis, *312,* 312*t, 333, 335–337, 346*
hand, *308,* 309*t*
of head and neck, 268–278, 269*t*–275*t,* 277*t,* 278*t*
hormones and, *504*
hyoglossus, 273*t,* 659, *659*
hyoid muscles, 275*t*
iliacus, *310,* 310*t, 337*
iliocostalis, *284–286,* 284*t*–286*t*
inferior oblique, *430, 481,* 482
inferior rectus, *481,* 482
infrahyoid group, 275*t*
infraspinatus, *299–300,* 300*t, 339*
injuries, 324, 325*t*
innervation, 264
intercostal, *279,* 279*t,* 280*t, 334, 337,* 644, *644, 646, 726*
intrinsic, 241
knee, *313–315,* 313*t*–315*t, 346*
laryngeal, 636–637, *637*
lateral rectus, *432, 481,* 482
latissimus dorsi, *284–286,* 284*t*–286*t,* 297*t, 298, 339, 343,* 645
leg, *346–347*
levator ani, *672*
levator palpebrae superioris, *430, 480–481*
longitudinal, *665–666*
lower limb, 310–324
lumbar, *687*
masseter, *432*
mechanical advantage in, 241–242, *242*
medial rectus, *481,* 482
mental region, 272*t*
middle ear, 472, *472*
mylohyoid, *659*
neck, 277*t, 284–286,* 284*t*–286*t*
nerve-muscle relationship, *248,* 248–249, 264
nuchal region, *278*
oblique abdominal, 645, *665–666*
obturator externus and internus muscles, 311*t, 312*
omohyoid, *334*
orbicularis oculi, 480, *481*
orbital, 268, 270*t*
origins and insertions, 240, 268
palatoglossus, *273,* 273*t,* 659, *659*
palmar interosseous, *308,* 309*t*
palmaris longus, *344*
papillary, *544,* 546, *546, 547*
parallel, 239, *239*
pectinate, 545, *546*
pectineus, *312,* 312*t, 335–336*
pectoral, 297*t, 298*
pectoralis major, 297*t, 298, 333, 338, 340, 343–344,* 644, *644, 726*
pectoralis minor, 295*t*–296*t, 296, 644, 726*
pelvic floor, 287*t*–288*t, 288*
pennate, 239, *239*
pharynx, 273*t,* 275*t, 434*
platysma, 272*t, 333*
psoas major, *310,* 310*t, 337*
pterygoid, *432*
quadratus femoris, 311*t, 312*
quadratus lumborum, *284–286,* 284*t*–286*t, 337*
quadratus plantae, 322*t, 323*
quadriceps femoris, 196–197, *313–314,* 313*t*
recognition test, *350*
rectus abdominis, *280–283,* 281*t*–283*t, 338, 341, 644,* 644–645
rectus femoris, *313,* 313*t, 333, 335–336, 346*
rectus inferior, medial, and superior, *430*
respiratory, 279*t,* 643, 643–645 *646–647, 644*
sartorius, *313,* 313*t, 333, 335*
scalenes, 644, *644*
scalp, 268, 270*t*
scapular, 297*t*
semimembranosus, 226, *226–227, 314,* 315*t, 346–347*
semispinalis, *284–286,* 284*t*–286*t*
semispinalis capitis, *278*
semitendinous, *314,* 315*t, 346*
serratus anterior, *338,* 644, *644*
serratus posterior, *644,* 644–645
serratus superior/inferior, *284–286,* 284*t*–286*t*
shoulder, 295*t*–296*t, 296*
skeletal muscle, 73, *74,* 74*t,* 236, *236*
smooth muscle, *254,* 255–257, 255*t, 256,* 256–257
soleus, 316*t, 318, 347–348*
stapedius, *433,* 472, *472,* 475, *476*
sternocleidomastoid, 277*t, 278, 338, 436,* 644, *644*
striations, 73, *246,* 246–247
structural hierarchy, 247*t*
styloglossus, 273*t,* 659, *659*
stylohyoid, *433*
subscapularis, *299–300,* 300*t, 334*
superior oblique, *430, 481,* 482
superior rectus, *481,* 482
suprahyoid group, 275*t*
swallowing, 273*t*–276*t, 276*
temporalis, *432*
tensor fascia latae, 311*t, 312, 333, 335–336, 346*
tensor tympanii, 471, *471,* 472, *472,* 475, *476*
teres major, 297*t, 298–299, 339*
thigh, *310,* 311*t, 312–315,* 313*t*–315*t, 346*
thoracic, *282–283*
tibialis anterior, 316*t, 317, 347–348*
tibialis posterior, *320,* 321*t*
tongue, 273*t, 436,* 659, *659*
trabecular, 714
transverse abdominal, *280–283,* 281*t*–283*t, 334*
trapezius, 277*t, 278, 284–286,* 284*t*–286*t, 296,* 296*t, 333, 338–339, 436*
triangular, 239, *239*
triceps brachii, 301*t, 302, 339, 343–344*
triceps surae, 316*t, 318*
trunk, 279–289
types and functions, *236,* 236–237
universal properties, 237
upper limb, 294–309
vastus intermedius, *313,* 313*t*
vastus lateralis, *313,* 313*t, 333, 336, 346–347*
vastus medialis, *313,* 313*t, 335–336, 346*
wrist, 303*t*–306*t, 304–306*
Muscle spindle, *462,* 462*t,* 463
Muscularis externa
  digestive tract, 655, *656*
  small intestine, 669, *669–670*
  stomach, *666*
Muscularis mucosae, 78, *631,* 639–640, 655, *655–656, 666*
Muscular system, 9, *10, 265–266*
  aging, 258
  appendicular musculature, 293–325
  axial musculature, 263–289
  diseases of, 258–259, *259,* 260*t*
  skeletal muscles, 235–260
  tissue, 72–74
Muscular tissue, 73, *74,* 74*t*
Mutagens, 48, 100–102
Mutations, 100
Myasthenia gravis (MG), 259, *259,* 260*t*
Myelencephalon, 366, *366*
Myelin, *359,* 359–360
  autonomic nervous system, *445*
  fetal development, 367
  signal conduction, 360–361
Myelination, *359,* 359–360
  fetal development, 367
Myelin sheath, 359, *359*
  diseases of, 361
Myeloid hemopoiesis, 525
Myoblasts, 257–258, *258*
Myocardial infarction, 550–552, *551*
Myocardial vortex, 544, *545*
Myocardium, 544, *544, 546*
Myocytes, 73, 236, 544
  smooth muscle, *254,* 255–256
Myoepithelial cells, 121, 483
  lactiferous, 725–726, *726*
Myofibrils, 245
  cardiac muscle, 554, *554*
  structural hierarchy, 247*t*
Myofilaments, 245–246, *245–246,* 247*t*
Myoglobin, muscle fiber, 245
Myology, 236
Myometrium, *718,* 722, *723*
Myopathies, 258–259, *259,* 260*t*
Myopia, *486,* 486*t*
Myosin, 245, *245*
  excitation-contraction coupling, 251, *252*
Myotome, 92
Myotubes, 257–258, *258*

N

Nail bed, 120, *120*
Nail body, 119–120, *120*
Nail fold, 120, *120*
Nail groove, 120, *120*
Nail matrix, 120, *120*
Nail plate, 119–120, *120*
Nail root, 119–120, *120*
Nails, 119–120, *120*
  prenatal development, 123–124, *124*
Nares, 633–634, *634–635*
Nasal aperture, *631,* 633–634, *634–635*
Nasal bones, *155,* 165, *635*
Nasal cavity, *153,* 155, *158, 332, 631,* 633–634, *634–635*
Nasal gland, *433*
Nasalis muscle, 270*t*
Nasal mucosa, *429,* 429*t*
Nasal region, *331*
  muscles of, 270*t*
Nasolacrimal duct, 480, *481*
Nasopharynx, *634,* 635, 663
Natal cleft, *339*
Natriuretic peptides, 510, 512*t,* 695
Natural killer cells, 531

Neck
  anatomy, 13, *14, 331*
  flexors and extensors, 277*t*
  muscles of, 268–278, 269*t*–275*t,* 277*t,* 278*t, 284–286,* 284*t*–286*t*
  veins, 579*t*–580*t, 580–581*
Necrosis, 80
Neocortex, 417–418, *418*
Neonatal circulation, *604*
Neoplasia, 79
Nephrolithiasis, 696
Nephron
  anatomy, 689, *690,* 690–695, *692–693, 695*
  cortical, *690,* 694
  juxtamedullary, *689–690,* 689. 694
  prenatal development, *699*
Nephron loop, 689, *689–690,* 694, *699*
Nephrons, 686–687, *687*
Nephroptosis, 700*t*
Nephrotic syndrome, 700*t*
Nerve cells. *See* Neurons
Nerve endings, senses, 461–463, *462,* 462*t*
Nerve fibers (axons), *72,* 72*t,* 73, 354, *355,* 356
  afferent, 381, 381*t*
  classification, 381, 381*t*
  descending analgesic, 466
  efferent, 381, 381*t*
  first- through third-order, 376–377, *377*
  myelinated, 360, *360*
  olfactory nerve, 469, *469–470*
  optic nerve, *487,* 488–490, *489–490*
  parasympathetic, *433*
  pituitary gland, *501*
  reflexes, 392
  sensory fibers, 466–468, *467–468, 478, 647*
  tongue, *467*
  unmyelinated, 360, *360*
  visceral, 381, 381*t*
Nerve growth factors, 358, 361
Nerve plexuses, 385, *386–390,* 386*t,* 387*t,* 389*t,* 390*t*
  brachial nerve, *335,* 385, *387–388,* 387*t*
  cervical, 385, *386,* 386*t*
  choroid, *426*
  coccygeal, *390,* 390*t*
  esophageal plexus, 450, *451*
  hypogastric plexus, *451,* 452, 655, *656*
  lumbar plexus, *389,* 389*t*
  lumbosacral plexus, 385, *390,* 390*t*
  myenteric, 656, *656*
  renal plexus, *449,* 689
  sacral p, 385, *390,* 390*t*
  submucosal, 656, *656*
Nerve(s), 353. *See also* specific nerves
  ansa cervicalis, *386,* 386*t*
  axillary, *387,* k387*t*
  blood vessels, *565, 566*
  cardiac, *446, 447,* 554–555
  cochlear, *434,* 471, *471–473,* 475, *476–477*
  distal, 445*t*
  dorsal, *714,* 714–715
  femoral, *334, 389,* 389*t*
  fibular (peroneal), *390,* 390*t*
  general anatomy, 380–382, *381–382,* 381*t*
  genitofemoral, *389,* 389*t*
  great auricular, *386,* 386*t*
  iliohypogastric, *389,* 389*t*
  ilioinguinal, *389,* 389*t*
  inferior alveolar, *432*
  inferior gluteal, *390,* 390*t*
  infraorbital, *432*
  injuries, 388
  intercostal, 384, *384–385, 646*
  laryngeal, *435*
  lateral femoral cutaneous, *389,* 389*t*
  lesser occipital, *386,* 386*t*
  lingual, *432,* 468, *468*
  median, *387,* 387*t*
  musculocutaneous, *387,* 387*t*
  nerve-muscle relationship, *248–249,* 248–250, 264
  obturator, *389,* 389*t*
  pelvic, *451,* 452
  phrenic, *386,* 386*t, 446, 646*
  pudendal, *390,* 390*t,* 715
  radial, *387–388,* 387*t*
  regeneration, 361
  respiratory system, 645, *646*
  rootlets, 382, *383–385*
  sciatic, *390,* 390*t*
  splanchnic, *446, 448,* 448–449, *451,* 452
  superior alveolar, *432*
  superior gluteal, *390,* 390*t*
  supraclavicular, *386,* 386*t*
  testicular, 705, *706–707,* 709
  thoracic region, *340*
  tibial, *390,* 390*t*
  transverse cervical, *386,* 386*t*
  tympanic, 450, *451*
  ulnar, *387,* 387*t*
  vestibular, *434,* 471, *471–472, 477,* 479, *479*
Nervous system, 9, *11. See also* Nervous tissue
  autonomic (*See* Autonomic nervous system)
  brain (*See* Brain)
  central (*See* Central nervous system)
  development, 365–368
  developmental disorders, 367–368, *368*
  endocrine system and, 352, *352,* 498–499
  organs (*See* Sense organs)
  overview, *352,* 352–353
  peripheral (*See* Peripheral nervous system)
  spinal cord (*See* Spinal cord)
  spinal nerves (*See* Spinal nerves)
Nervous tissue, *72,* 72–73, 72*t,* 351–368
Neuobiology, 352
Neural circuits
  neural pools and, 363–364, *364*
  synapses and, 361–363, *362–363*
Neural convergence, 364, 450, 488
Neural crest, 92, *92,* 366, 456–457, 514, *514*
Neural divergence, 450
Neural fold, 92, *92,* 365, *365*
Neuralgia, 394*t*
Neural groove, 92, *92,* 365, *365*
Neural integration, 362, *362*
  spinal cord, 372
Neural pathways, 445, *445,* 445*t*
Neural plate, 365, *365*
Neural pools, 363–364
Neural retina, 491, *493*
Neural tube, 491, *492,* 514, *514*
  defects, 92, 367–368, *368*
  formation, 91–92, *92, 365,* 365–366, 456–457
Neurilemma, *355,* 358, 360
Neuroanatomy, 352
Neurocranium, 176
Neurodegenerative diseases, 438–439, 438*t*
Neuroectoderm, 365, *365*
Neurofibrils, 354, *355*
Neurogenic shock, 394
Neuroglia (glial cells), *72,* 72–73, 72*t*
  brain tumors and, 360
  types of, 357–358, 357*t, 358*
Neurohypophyseal bud, 512–513, *513–514*
Neurohypophysis, *500*
Neuromuscular junction, *248–249,* 248–250, 362–363, *363*
Neuromuscular toxins, 249
Neurons, *72,* 72–73, 72*t,* 353–357
  endocrine system, *501*
  first-order, 376, *377,* 378, 464, 489–490, *490*
  functional classes, 354, *354*
  lower motor, 378
  olfactory, 468, *469–470*
  postganglionic, *447*
  postsynaptic, *362,* 362–363
  preganglionic, *447*
  presynaptic, *362,* 362–363
  second-order, 376, *377,* 378, 464
  structure, 354, *355,* 356
  synaptic relationships, 362–363, *363*
  third-order, 376, *377,* 378, 464
  upper motor, 378
  variation, *356,* 356–357
Neurophysiology, 352
Neurosoma, *72,* 72–73, 72*t,* 354, *355,* 356, 469, *469–470*
Neurotransmitters
  autonomic nervous system, 445*t,* 453–454, 453*t, 454,* 454*t*
  synapses and, 362–363, *363*
Neurulation, 91–92, *92,* 365
Neutrophils, 38, *38,* 46, 521, *521,* 522*t,* 527, *528,* 528*t,* 529
  fibrous tissue, 63
Nicotinic receptors, 454, *454,* 454*t*
Night vision, 487
Nipple(s), *338,* 725–726, *726*
Nissl bodies, 354, *355*
Nitrogenous wastes, 686
  in plasma, 522, 522*t*
Nociceptors, 461, 464–466
Nomina Anatomica (NA) system, 20
Nondisjunction, chromosomal, 100–102, *101*
Noninvasive imaging, 4
Nonkeratinized epithelium, *60,* 62
Nonspecific granules, 527, *528–529,* 528*t*–529*t*
Nonsteroidal anti-inflammatory drugs, 668
Nonverbal communication, skin and, 110, *110*
Norepinephrine, 362–363, *363,* 507, *508*
  receptors, 454, *454,* 454*t*
Nose, 633–634, *634–635*
  bridge of, *331*
  root of, *331*
Nostril(s), *481, 631,* 633–634, *634–635*
Notochord, 177–178, *177–178*
Nuchal ligament, *157,* 161
Nuchal region, *331*
  muscles, *278*
Nuclear envelope, 43
Nuclear lamina, 43
Nuclear medicine, 6
Nuclear pore complex, 43
Nuclei
  anterior nucleus, 413–415, *414*
  arcuate nucleus, 413–415, *414,* 415
  basal nuclei, *414,* 415, 419, *419,* 422, 425*t, 426*
  of brain, *400–401,* 402, *403*
  cardiac muscle, 554, *554*
  caudate, 419, *419, 426*
  cochlear, 475, *476*
  cuneate, 406, *407–408*
  deep nuclei, 410, *411–412*
  dorsomedial nucleus, 413–415, *414*
  eye movement, *479*
  geniculate nuclei, *408,* 410, 413–415, *414,* 490, *490*
  gracile nucleus, 406, *407–408*
  hypothalamic nuclei, 413–415, *414, 501*
  inferior olivary nucleus, 406, *407–408*
  lentiform nucleus, 419, *419*
  mamillary nuclei, 413–415, *414*
  paraventricular, 413–415, *414, 501,* 503
  pretectal, 490, *490*
  respiratory control, *634*
  rod and cone, *487*
  salivatory, 662
  solitary nucleus, 468, *468*
  superior olivary, 475, *476*
  suprachiasmatic nucleus, 415
  supraoptic, *501,* 503
  sustentacular cell, *708*
  thalamic, 413–415, *414*
  vestibular, 378–379, *379,* 479, *479*
Nucleoli, 43
Nucleoplasm, 30
Nucleus (cell), *42,* 42–43
  meiosis, *710*
Nucleus accumbens, 419
Nucleus pulposus, 169, *169*
Nutrient foramina, 133
Nutrients, in plasma, 522, 522*t*
Nutrition
  bone growth and, 144
  prenatal nutrition, 95, *95*

O

Oblique tissue section, 55, *56*
Occipital condyle, 161
Occipitalis muscle, 270*t, 271*

Occipital lobe, *400–401,* 416, 425*t,* *426,* 490, *490*
Occipital protuberance, 161
Occlusal surfaces, 661
Olecranon, *339, 343–344*
  bursa, *223,* 223–224
  radius and, *187,* 188
Olfaction. *See* Smell
  respiratory system, 631
Olfactory bulb, *427, 429,* 468, *469–470*
  cribriform (olfactory) foramina, 163, *163*
Olfactory epithelium, 633, *634–635*
Olfactory mucosa, 468, *469*
Olfactory tract, *429,* 469, *469–470*
Oligodendrocytes, 357, 357*t, 358,* 360, *360*
  fetal development, 367
Oligohydramnios, 93
Olive, 406, *407–408*
Omenta, greater and lesser, 18, *657,* 657–658, *666, 672*
Omental appendages, 671, *672*
Omphalocele, 678, *679–680*
Oncogenes, 48
Ondine's curse, 645
Oocyte, *717*
  primary, 717, *718–720*
  secondary, *719,* 720
Oogenesis, 85, 717, *718–719,* 720
Oogonia, 717, *718–719*
Open canicular system, 532, *533*
Ophthalmic division, *432*
Ophthalmoscope, 484, *485*
Opponens digiti minimi, *308,* 309*t*
Opponens pollicis, *308,* 309*t*
Opportunistic infections, leukocyte disorders, 535
Opposition, of thumb, *218,* 219
Optical canal, 162, *164*
Optic chiasm, 415, *427, 429,* 489–490, *490, 501*
  prenatal development, *513*
Optic cup, 491, *493*
Optic disc, 482–485, *482–485*
Optic radiation, 490, *490*
Optic stalk, 491, *493*
Optic tract, *429,* 489–490, *490*
Optic vesicles, 92, *97,* 491, *493*
Oral cavity, *332, 655, 658,* 658–662
Oral region, *331*
  muscles of, 270*t*
Ora serrata, 482–484, *482–484*
Orbicularis oculi muscle, 270*t, 271*
Orbicularis oris muscle, 270*t*
Orbit, 164, *164*
  accessory structures, 480–482, *481*
  muscles of, 268, 270*t*
Orbital plate, 163, *164*
Orbital region, *331, 480–481,* 480–482
  muscles of, 270*t*
Orbitofrontal cortex, *418,* 419, 420, *420*
  olfactory projection pathways, 469–470, *470*
Organelles, 9, 30
  nucleus, *42,* 42–43
  structure, *42–45,* 42–46
Organism, 8
Organogenesis, *91,* 91–92, 92*t,* 99*t*
Organ(s), 8–9
Organ systems, 8–9, *10–11*
  accesory organs, 116–120, 654–655, *655*
  connective tissue, 63
  endocrine cells in, 510–511, 511*t*
  target organs, 498–499, *499*
Oropharynx, *634,* 635, 663
Orthopedicx, 148
Osmolarity, plasma, 522, 522*t*
Osmoreceptors, 415
Osmosis, membrane transport, 34
Osseous tissue, 70, *70,* 70*t*
  bone and, 132–133
  endocrine cells in, 510
  histology, 134–138, *135, 137–138*
  matrix, 135–136
Ossification
  intramembranous, 139–140, *140*
  skeletal development, 176–178, *177–178*
Osteoarthritis, 230–231, *230–232,* 231*t*
Osteoblasts, 134, *135*
  intramembranous ossification, 139, *140*
Osteocalcin, 510, 512*t*
Osteoclasts, 135, *135*
Osteocytes, 70, 134, *135*
Osteogenesis imperfecta, 71
Osteogenic cells, 134, *135*
Osteology, 132–133
Osteon, 70, 136, *137*
Osteoporosis, 144, *147,* 147–148, 148*t*
Osteoprogenitor cells, 134, *135*
Osteosarcoma, radioactivity and, 132
Otic capsule, 491, *492*
Otic disc, 491, *492*
Otic pit, 491, *492*
Otic placode, 491, *492*
Otic vesicle, 491, *492*
Otolithic membrane, 476, –477 *477–478*
Otoliths, 476, *477–478*
Otosclerosis, 474
Oval window, 471–472, *471–473, 475*
Ovarian cycle, 717, *718–719,* 720
Ovarian follicle, histology, 510, *510*
Ovary(ies), *336, 499*
  anatomy, 716–717, *716–718*
  hormones, *504,* 512*t*
  prenatal development, *728*
Oviduct, 721
Ovoidal cells, 27, *28*
Ovulation, 717, *718–719,* 720–721, *721*
Oxytocin, 415, 503, 503*t, 504*

P

Pacemakers, 552
Pacinian corpuscles, *462,* 462*t,* 463
Packed cell volume (PCV), 524
Pain
  abdominal, 681
  receptors, 461
  referred pain, 465–466, *466*
  reticular formation, 410
  senses and, 464–466
  value of, 465
Palate, 164, *164, 332*
  anatomy, *658,* 659
  evolutionary significange, 165
Palatine gland, *433*
Palatine rugae, *658*
Palatine tonsils, *634, 658*
Palatoglossal arch, *658*
Palatopharyngeal arch, *658*
Pallor, 115
Palmar abduction, *218,* 219
Palpation, 3
Palpebrae. *See* Eyelids
Palpebral conjunctive, 480, *481*
Pampiniform plexus, 705, *706–707*
Pancreas, *336, 341, 509, 655*
  anatomy, 676–677, *676–677, 687* (*See also* Pancreatic islets)
    celiac circulation, *585*
  exocrine secretions, 678*t*
Pancreatic amylase, 678*t*
Pancreatic buds, 678, *679–680*
Pancreatic ducts, 668, *669–670, 676,* 676–677, *677*
Pancreatic islets, 508–509, *509,* 511*t*
Pancreatic juice, 677, 678*t*
Pancreatic lipase, 678*t*
Paneth cell, 670, *670*
Papillary duct, *690,* 695
Papillary layer, 113, *113*
Pap smears, 733, *733*
Paracellular route, 693
Paraesthesia, 493*t*
Parafollicular cells, 506, *506*
Parallel after-discharge neural circuit, 364, *364*
Parallel muscles, 239, *239*
Paralysis
  crutch paralysis, 388
  neuromuscular toxins, 249
  respiratory, 393
  spinal cord injury, 393–394, 394*t*
Paramesonephric duct, 727, *728, 728–730*
Paranasal sinuses, 155, *155, 159*
Paraplegia, 394
Parasagittal plane, 12, *12*
Parasympathetic nervous system, *352,* 353, 444–445, *445,* 450, *451,* 452
  digestive tract, 655–656, *656*
  effects, 453–456, 453*t*
  penis, 715
  renal innervation, *449,* 689
Parathyroid capsule, *507*
Parathyroid gland, *499,* 506, *507*
  hormones, 511*t*
Parathyroid hormone (PTH), 511*t*
  bone growth and, 144
Paraurethral glands, 724, *725*
Parenchyma, exocrine glands, 76
Paresthesia, 394*t*
Paresynaptic terminal, *355,* 356
Paricardial fluid, 17
Paricardial sac, 17
Paricarditis, 543
Parietal cells, 664, 667*t*
Parietal lobe, *400–401,* 416, 425*t, 426*
Parietal peritoneum, 18, 730, *730*
Parietal pleura, 17, *642,* 642–643
Parieto-occipital sulcus, *401,* 416
Parkinson disease, 422, 438*t,* 439, *439*
Parotid salivary, *434,* 450, *451, 655,* 662, *662*
Partial pericardium, 17
Partial-thickness burns, 127, *127*
Parturition (childbirth), 87
Patau syndrome, 101
Patella, *195,* 196–197, *346–347*
Patellar retinacula, 226
Patellar surface, 195, *195*
Patellofemoral joint, 226, *226–227*
Patent ductus arteriosus, 559
Pathological fracture, 145, 145*t, 146*
Pattern baldness, 119
Pectoral girdle, bones of, 185–190
Pedal region, 16, 193
Pedicels, 691, *693*
Pedicle, 169, *169*
Peg cells, 721, *721*
Pelvic brim, 190, *191–192, 337*
Pelvic cavity, 18
Pelvic curvature, 168, *168*
Pelvic floor, muscles of, 287*t*–288*t, 288*
Pelvic girdle, 190–193, *191–192*
Pelvic inflammatory disease, 734*t*
Pelvic inlet, 190, *191–192*
Pelvic kidney, 698
Pelvic landmarks, 343
Pelvis
  arteries, *584–586,* 584*t*–587*t*
  bones of, 190–193, *191–192*
  female, 193, 194*t*
  greater and lesser, 190, *191–192*
  male, 193, 194*t*
  renal pelvis, 687
  vein(s), *588–589,* 588*t*–589*t*
Penis, *334, 335, 342, 697, 706*–707
  anatomy, 713–715, *714*
  cancer, 732*t*
  prenatal development, *728,* 729, *730*
Pennate muscles, 239, *239*
Pepsin, 664
Pepsinogen, 664
Peptic ulcer, 668, *668*
Peptide YY, 510, 512*t*
Percursor cells, 525, *525*
Percussion, 4
Perforating canals, compact bone, 136, *137*
Perforating fibers, 133
Pericardial cavity, 17, *17, 340, 541, 541–542,* 543, *543, 642,* 642–643
Pericardial fluid, 543
Pericardial sac, 543, *543*
Pericardium, 17, *334,* 543, *543*
Perichondrium, 70, *638*
Pericytes, *568*
Periderm, 123, *123*
Perilymph, 473, *473*
Perimetrium, *718,* 722
Perimysium, 238, *238*
Perineal membrane, 287*t, 288*
Perineal raphe, 705, *707, 725*
  prenatal development, *729*
Perineum, 287*t*
Perineurium, 380, *381–382*
Periodontal disease, 661
Periosteal layer, 402, *402*

Periosteum, 70, 133
Peripherally inserted venous catheter, 592
Peripheral nerve fibers, 380, *380,* 380*t*
Peripheral nervous system (PNS), *352,* 353
Peripheral neuropathy, 394*t*
Peripheral proteins, 32
Perirenal fat capsule, 686–687, *687*
Peristalsis, smooth muscle, 256
Peritoneal cavity, *341*
Peritoneum, 18, *341, 687*
  female, *716–717*
Peritonitis, 452, 680*t*
Peroxisomes, 46
Perpendicular plate, *156,* 163, *163, 634*
Persynaptic terminal, *248,* 248–249
Pes planus, 202*t*
Petrous part, 161
Peyer patches, 669, *669–670*
Phagocytosis, 35, *35*
Phagosome, 35
Phalanges, 188, *190*
Pharyngeal arches, 92, *97*
Pharyngeal groove, *492*
Pharyngeal pouches, *492,* 513–514, *514, 648, 680*
  formation, 91–92, *93*
Pharyngeal tonsil, *634*
Pharynx, *332, 507, 631,* 635, *655*
  anatomy, *634,* 663
  muscles of, 273*t,* 275*t*
  prenatal development, *513*
Phemphigus vulgarus, 39
Pheochromocytoma, 515
Pheomelanin, 114
Philtrum, *331, 635*
Phlebitis, 605*t*
Phospholipids, structure, 30, *32*
Photomicrographs, 26
Photopic vision, 487, 488, *489*
Photoreceptors, 461, 486–489, *487–489*
Physiology, anatomy and, 2
Pia mater, *374,* 374–375
Pigmentation, skin, *114,* 114–115
Pigment retina, 491, *493*
Piloerector muscle, 118
Pilomotor muscle, 118
Pilus, 116
Pineal gland, *401, 499,* 504–505, 511*t*
  tumors, 515
Pinocytosis, 35, *35*
Pinocytotic vesicle, *568*
Piriformis muscle, 311*t, 312*
Pitcher's arm, 325*t*
Pituitary gland, 415, *429, 499*
  anatomy, 500, *501–502,* 502
  anterior and posterior, 500, *501–502,* 502–503, 503*t, 504*
  disorders, 515
  histology, *502*
  hormones, 502–503, 503*t, 504*
Pivot joints, *212,* 213
Placenta, *94,* 95–96, *96,* 96*t*
  disorders, 95
  endocrine cells in, 511
Placental conductivity, 96
Placental nutrition, 95, *95*
Placenta previa, 95, 734*t*
Plane (gliding) joints, *212,* 213
Plane (butt) suture, 206, *207,* 208, 211*t*
Plantar flexion, 219, *219*
Plantar interosseus muscles, 322*t, 323*
Plaque formation, 603
  dental plaque, 661
Plasma (blood)
  antibodies, 526
  components and general properties, 520–522, *521,* 522*t*
  urine production and, 691, *693*
Plasma, blood, 71
Plasma cells, fibrous tissue, 63
Plasma membrane, 30–36, *31*
Plasma proteins, 522, 522*t,* 674*t*
Plasmin, 534
Platelet-derived growth factor (PDGF), 534
Platelet plug, *533,* 533–534
Platelets, 71, 520–521, *521,* 522*t*
  disorders, 535
  form and function, 532, *533*
  production, 533, *533*
Pleurae, 17, *17, 334, 631, 642,* 642–643
Pleural cavity, 17–18, *336, 340, 631,* 643
Pleural fluid, 17
Pluripotent stem cells, 50
Pneumonia, 650*t*
Pneumothorax, 643
Podocytes, 691, *693, 695*
Poikilocytosis, 535
Polar body
  oogenesis, 717, *718–719,* 720
  spermatogenesis, 85
Poliomyelitis, 380, *380*
Pollution, reproduction and, 715
Polycythemia, 534–535 535*t*
Polydactyly, 201–202, *202,* 202*t*
Polygonal cells, 27, *28*
Polymastia, 122
Polymers, bones and, 136
Polymorphonuclear leukocytes (PMNS), 527, *528,* 528*t*
Polyribosomes, 525
Polyspermy, *86,* 86–87
Polythelia, 122
Pons, *407–408,* 409, 413*t, 427, 447, 634*
  abducens nerve, *432*
  respiratory system and, 645, *646*
  vestibulococclear (VIII) nerve, *434*
Pontine respiratory group, 645, *646*
Popliteal ligaments, 226, *226–227*
Popliteal region, 226
Popliteal surface, 195, *195*
Popliteus muscle, 315*t, 319–320*
Porta hepatis, 673, *674–675*
Portal circulation system, 571–572, *572*
Positive end-expiratory pressure (PEEP), 648
Positron emission tomography (PET), *5,* 6
Postcentral gyrus, 421, *421*
Posterior arch, 169–170, *170*
Posterior chamber, 482–484, *482–484*
Posterior cruciate ligament, 228
Posterior mesentery, 18, *19*
Posterior nasal apertures, 162, *162*
Posterior spinal tracts, 375, *376,* 376*t,* 378
Posterior tubercle, 169–170, *170*
Postganglionic fiber, 445, *445,* 445*t*
Posttraumatic avascular necrosis, 196
Potential spaces, 18, 643, 721–722
Pott fracture, 202*t*
Power stroke, excitation-contraction coupling, 251, *252*
Precapillary sphincter, 567, *570*
Precentral gyrus, *400,* 421, *422*
Precocial puberty, 515
Preeclampsia, 734*t*
Preembryonic stage
  events, 88–90, *89–90*
  prenatal development, 87, 88*t*
Prefrontal cortex, *418,* 419, 420, *420,* 424
Preganglionic fiber, 445, *445,* 445*t*
Pregnancy
  ectopic, 89
  trimesters, 87
Premature birth, respiratory distress syndrome, 648
Premenstrual phase, 724
Prenatal development
  autonomic nervous system, 456–457
  blood vessels, 601–603, *601–603*
  clinical perspectives, 100–104
  digestive system, 678, *679–680*
  ear, 491, *492*
  endocrine glands, 512–514, *513–514*
  eye, 491, *493*
  facial bones, 177
  foot, 200–201, *201*
  heart, 557–558, *558*
  integumentary system, 123–124, *123–124*
  intervertebral discs, *177,* 177–178
  merocrine glands, 124, *124*
  muscles, 257–259, *258,* 260*t*
  myelin, 367
  nervous system, 365–368, *368*
  reproductive systems, 727, *728–730,* 730
  respiratory system, 647, *648*
  skeleton, 176–178, *177–178*
  skin, 123–124, *123–124*
  skull, 176, *176–177*
  spinal nerves, 367
  stages, 87–99, 88*t, 97–98,* 99*t*
  upper limb, 200–201, *201*
  urinary system, 697–698, *699*
  vertebral column, 177–178, *178*
Prenatal nutrition, 95, *95*
Prepuce, *342*
  female, *716–717,* 724, *725*
  male, *706–707,* 713–715, *714*
  prenatal development, *729*
Presbyopia, *486,* 486*t*
Pressure sores, 80
Primary germ layer, 87
Primary gustatory cortex, 420, *420*
Primary nail field, 124
Primary narrow cavity, 139
Primary olfactory cortex, 469, *469–470*
Primary ossification center, 139
Primary somatosensory cortex, 421, *421*
Primary spermatocytes, 708, *710–712*
Primary tissue, 54, 54*t*
Prime mover muscle, 240
Primitive gut, formation, 91
Primitive streak, 89
Primordial germ cells, 709, *710*–712, *720*
Principal cells, 695
Procarboxypeptidase, 678*t*
Procedural memory, 424
Processes of bone
  alveolar, 164
  anterior clinoid, 162, *162*
  ciliary, *483,* 484
  condylar, 165, *165*
  coracoid, 186, *186*
  coronoid, 165, *165*
  costal, *178,* 178–179
  inferior articular, 169, *170*
  mastoid, 161, *161*
  middle ear, 471–472, *471–472*
  odontod, 170, *170*
  palatine, *157,* 164
  pterygoid, *157,* 162
  spinous, 169, *169,* 170–171, *171*
  styloid, 160, *161, 187,* 188, *344–345*
  superior articular, 169, *170, 172,* 173
  transverse, 169, *169*
  xiphoid, *173,* 174, *338*
  zygomatic, 160, *161*
Progesterone, 509–510, *510,* 512*t*
Programmed cell death, 46, 80–81
Projection pathways, *376–377,* 416, *417,* 463–465, *465*
  auditory, *472,* 475, *476–477,* 476–478
  gustatory, 468, *468*
  olfactory, 469, *470*
  somatosensory, 463–464, *465*
  vestibular, 479, *479*
  visual, 489–490, *490*
Prolactin, *501,* 503, 503*t, 504*
Prolactin-inhibiting hormone, *501,* 502, 502*t*
Pronation, 9
  of foot, 219, *219*
  synovial joints, 216–217, *217*
Pronator quadratus muscle, 301*t, 302*
Pronator teres muscle, 301*t, 302*
Prone position, 9
Pronuclei, *86,* 87
Prophase
  meiosis, *710*
  mitosis, 48, *49*
Proplatelets, 533
Proprioceptors, 461
Proseminogelin, 713
Prosencephalon, 366, *366*
Prostaglandins, 713
Prostate cancer, 713
Prostate gland, *342, 697, 706*–707, 713
  diseases, 713
  prenatal development, *728*
Prostate-specific antigen, 713
Prostatic urethra, 696, *697*
Prostatic utricle, 727
Prostheses, joints, 231, *232*
Proteasomes, 43, *44,* 45

Proteins
  contractile, 246
  globin, 524, *524*
  glycoproteins, 32
  membrane proteins, 32–33, *33*
  metabolism, 674*t*
  motor proteins, 37–38
  peripheral proteins, 32
  plasma, 522, 522*t*
  production, *45*
  regulatory, 246
  in urine, 692
Proteinuria, 692
Proteoglycans, 64
Prothrombin, 522, 522*t*
Protofilaments, 40, *42*
Protraction
  of mandible, 217, *218*
  synovial joints, 214, *215,* 216
Proximal convoluted tubule (PCT), *689–690,* 692–694, *699*
Pseudopods, 38, *38*
Pseudostratified columnar epithelium, 57, *59,* 59*t*
Pseudounipolar neurons, *356,* 356–357
Pterygoid muscles, *274,* 274*t*
Pterygoid plates, 162, *162*
Pubarche, 731
Puberty, 731
  precocial puberty, 515
Pubic symphysis, 190, *191–192, 342*
  female, *716–717, 730*
  male, *706–707, 707, 730*
Pubis, 190, *191–192,* 193
Pubofemoral ligament, 224, *225*
Pudendum, 724, *725*
Pulled elbow, 224, *224*
Pulmonary circuit, 540–541, *540–541,* 572, *573*
Pulmonary collapse, 643
Pulmonary groove, 647, *648*
Pulmonary surfactant, 641, *642*
Pulmonary valves, 546, *546–547*
Pulp cavity, 661
Punctum, 480, *481*
Pupil, 482–484, *482–484*
Pupillary constrictor, 450, *451,* 483
Pupillary dilator, 483
Purkinje cells, *351, 356,* 411, *412,* 422
Purkinje fibers, 553, *553*
Putamen, 419, *419, 426*
Pyelitis, 696
Pyelonephritis, 696
Pyloric canal, 664, *665–666,* 667, 667*t*
Pyloric glands, 664, *665–666,* 667, 667*t*
Pyloric region, 664, *665–666,* 667, 667*t*
Pyloric (gastroduodenal) sphincter, 664, *665–666,* 667, 667*t*
Pylorus, 664, *665–666,* 667, 667*t*
Pyramidal lobe, thyroid gland, 505–506, *505–506*
Pyramidal tracts, 378, *379*
Pyramids, 406, *407–408*
Pyrimidal cells, 417, *418,* 422

Q

Quadrants, anatomical, 15, *15*
Quadriplegia, 394

R

Rabies (hydrophobia), 394*t*
Radial abduction, *218,* 219
Radial collateral ligaments, *223,* 223–224
Radial flexion, 217, *218,* 219
Radial notch, *187,* 187–188
Radioactivity, bone cancer and, 132
Radiography, 4, *5*
Radiologic anatomy, 2, 4
Radiologic technicians, 4
Radiologists, 4
Radiology, 4
Radioulnar joints, *223,* 223–224
Radius, *187,* 187–188, *344*
  styloid process, *344*
Ramus (rami)
  communicating, *446*
  gray communicating, 448, *448*
  of ischium, 191, *192*
  of mandible, 165, *165*
  pubic, *725*
  of pubic bone, 193
  spinal nerves, 384, *384–385*
  white communicating, 448, *448*
Range of motion, synovial joints, 219–220
Raynaud disease, 457*t*
RBC count, 524
Receptive field, 463, *464*
Receptor-mediated endocytosis, 35, *35*
Receptors
  autonomic nervous system, 453–454, 453*t, 454,* 454*t*
  cholinergic, 454
  classification, 461
  irritant, 645, *646*
  membrane proteins, 32, *33*
  nervous system, *352,* 353
  olfactory, 469, *469–470*
  respiratory system, 645, *646*
  stretch, 645, *646*
Recovery stroke, excitation-contraction coupling, 251, *252*
Rectal valves, 671, *672*
Rectouterine pouch, *716–717,* 722
Rectum, *337, 342, 584, 589, 655*
  anatomy, 671, *672*
  female, *716–717*
  male, *706*–707
Rectus sheath, *333*
  abdominal wall, 281*t*–283*t*
Red blood cells (RBCs), 71, 523–526, *523–526*
  complete blood count (CBC), 532
  hypochromic, 534
  microcytic, 534
Red bone marrow, 138, *138, 342*
  erythrocyte production, 525
Reflex arcs, 392, *392*
  digestive tract, 656, *656*
Reflexes
  autonomic, 468, *468*
  monosynaptic, 392
  photopupillary, 483
  postural, 479, *479*
  somatic, 391–393, *392,* 393*t*
  spinal cord, 372, *373*
  tympanic, 475, *476*
  vestibulo-ocular, 479, *479*
  visceral, 392
Regeneration
  nerves, 361
  tissue repair, 79–80
Regeneration tube, 361
Regional anatomy, 2, 330
Regulatory proteins, 246
Relaxation, 250–251, *252*
Releasing hormones, 502, 502*t*
Renal agenesis, 93
Renal capsule, *690*
Renal circulation system, 687, *688–689,* 689
Renal columns, 687, *688*
Renal corpuscle, *689–693,* 690–695, *695*
Renal cortex, 687, *688, 690*
Renal failure, 700, 700*t*
Renal fascia, 686–687, *687*
Renal fraction, 687
Renal innervation, *449,* 689
Renal medulla, 687, *688–689*
Renal papilla, 687, *688, 690*
Renal pyramids, 687, *688*
Renal tissue cap, *699*
Renal tubule, 689, 690, *690, 692–693,* 692–695, *695*
Renin, 694
Reposition, of thumb, *218,* 219
Representational hemisphere, 424–425, *425*
Reproductive systems, 9, *11,* 703–734. *See also* Female reproductive system; Male reproductive system
  aging, 731
  disorders, 731–733, *732t, 733, 734*t
  overview, 704–705, 704*t*
  pollution and, 715
  prenatal development, 727, *728–730,* 730
  puberty, 731
Resistance, muscular, 241, *241*
Resolution, microscopy, 26, *27*
Resorption bays, 135, *135*
Respiratory center, 406, *407–408*
Respiratory distress syndrome (RDS), premature birth, 648
Respiratory membrane, 641, *642*
Respiratory mucosa, 468, *469*
Respiratory system, 9, *10,* 631–650
  aging, 649
  lower respiratory tract, 637–643
  muscles, 279*t*
  neuroanatomy, 645, *646*
  neuromuscular components, 643, *644, 646–647*
  obstructive disorders, 649
  overview, 631, *631*
  paralysis, 393
  pathology, 649, 650*t*
  prenatal development, 647, *648*
  restrictive disorders, 649
  upper respiratory tract, 632–637
Rete testis, *708,* 709
Reticular fibers, 64
  knee, 226
Reticular formation, 378, 406, *407–408,* 410, *410,* 413*t,* 479
Reticular layer, 113, *113*
Reticular tissue, 64, *65,* 65*t,* 67
Reticulocytes, 525
Reticulospinal tracts, 375, *376,* 376*t,* 378, *379,* 410, *412*
Retina, *429,* 482–484, *482–484*
  circuitry and visual sensitivity, 488–489, *489*
  detached, 484
  development, 491, *493*
  structure and function, 486–489, *487–489*
Retraction, synovial joints, 214, *215,* 216
Retroperitoneal region, 658
Retroperotineal region, 18, *18*
Reverberating neural circuit, 364, *364*
Reverse osmosis, 34
Rhabdomyoma, 260*t*
Rhabdomyosarcoma, 260*t*
Rheumatic fever, 560*t*
Rheumatism, 230–231, *230–232,* 231*t*
Rheumatoid arthritis, 230–231, *230–232,* 231*t*
Rheumatology, 230–231, *230–232,* 231*t*
Rh incompatibility, 526
Rhombencephalon, 366, *366*
Rhomboid major and minor muscles, *296,* 296*t, 299*
Rib cage
  anatomy, *334*
  breast, *726*
Ribonuclease, 678*t*
Ribosomes
  organelles, 42–43
  structure, 43
Rib(s), 174, *174, 337, 340, 446, 674, 685*
  articulation, 175*t*
  development, *178,* 178–179
RICE treatment (rest, ice, compression, elevation), 324
Rickets, 136
Rider’s bones, 325*t*
Right colic (hepatic) flexure, 671, *672*
Right lower quadrant, 15, *15*
Right upper quadrant, 15, *15*
Rods, 486–489, *487–489*
Root canal, 661
Root(s)
  connective tissue, *117,* 118
  epithelial, *117,* 118
  hair, 117, *117*
  lung, 639
  nail, 119–120, *120*
  nasal, *635*
  nose, *331*
  penis, *342, 706,* 713–715, *714*
  roots, 382, *383–385*
  teeth, 660–661, *660–661*
  tongue, 659, *659*
Rostral direction, 399, *400–401,* 402
Rotation
  of head, 217, *218*
  synovial joints, 216, *216*

Rotator cuff, *300,* 300*t*
Rough endoplasmic reticulum, 43
Round window, 471, *471–472,* 474, *475*
Rubrospinal tracts, 379, 409
Ruffled border, bone cell, 135, *135*
Rugae, 696, *697*
  vaginal, *716–717,* 724

S

Saccule, *472,* 475–478, *476–478, 492*
Sacral canal, *172,* 173
Sacral crest, median and lateral, *172,* 173
Sacral hiatus, *172,* 173
Sacral promontory, *172,* 173
Sacral region, 372, *373*
Sacral vertebrare, 167, *167–168, 172,* 172–173
Sacroiliac joint, *172,* 173, 190, *191–192*
Sacrum, *172,* 172–173, *337, 339, 342*
Saddle joints, *212,* 212–213
Sagital suture, *156, 158,* 160
Sagittal plane, 12, *12*
Salivary amylase, 661
Salivary ducts, orifices, *658*
Salivary glands, *76, 434,* 450, *451,* 661–662, *662*
  extrinsic, 661–662, *662*
  intrinsic, 661–662, *662*
Sarcolemma, 245
Sarcomeres, *246,* 246–247, 247*t*
Sarcoplasm, 245
Sarcoplasmic reticulum (SR), 245, 553–554, *554*
  smooth muscle, 255
Satellite cells
  muscle development, 257–258, *258*
  peripneral nervous system, 357*t, 358,* 359
Scala tympani, *472–473,* 473–474
Scala vestibuli, *472–473,* 473–474
Scalenes muscles, 277*t, 278*
Scalp, *332*
  muscles, 268, 270*t*
Scanning electron microscope (SEM), 26, *27*
Scapula, 185–186, *186*
  glenohumeral joint, 221–223, *223*
  inferior angle, *339*
  medial border, *339*
Scapular muscles, 297*t, 298*
Schizophrenia, 438*t*
Schwann cells, 357*t,* 358, *358*
  fetal development, 367
  nerve regeneration, 361
Sciatic nerve, *390,* 390*t*
Sciatic notch, 191, *192*
Sclera (eyeball), 482–484, *482–484, 487, 493*
Sclerosis, 358
Sclerotome, 92
Scoliosis, 168, *168*
Scotopic vision, 487, 488, *489*
Scrotum, *334, 335, 342,* 705, *706–708*
  prenatal development, *729–730*
Scurvy, 64
Sebaceous glands, *121,* 122
  prenatal development, 124, *124*
Sebum, 122
Secondary marrow cavity, 140
Secondary sex characteristics, 731
Secondary spermatocytes, 708, *710–712*
Second-class lever, 242, *243*
Second-degree burns, 127, *127*
Second gap (G_2) phase, cell cycle, 47
Secretion, neuronal, 353
Secretory cells, *726*
Secretory vesicles, 43
Segments, anatomical, 16
Sella turcica, 162, *162*
Semen, 713
Semicircular canals, *472,* 473
Semicircular ducts, *434,* 471, *471–472,* 475–478, *476–478, 492*
Seminal vesicle, *342, 706*–707, 713
  prenatal development, *728*
Seminiferous tubule, 510, *510,* 705, *706–708, 711*
Seminogelin, 713
Sense organs, 461. *See also* Ear; Eye; Tongue, etc.
  arterial, 567, *567*
  disorders of, 491, 493*t*
Senses
  chemical, 466–470
  general, 420–421, 461–463, *462,* 462*t*
  sense organs, 461
  smell, 468–470, *469–470*
  special, 420
  taste, 466–468, *467–468*
Sensorineural (nerve) deafness, 474
Sensory afferent nervous system, *352,* 353
  neurons, 354, *354*
Sensory homunculus, 421, *421,* 465
Sensory nerves, 381
Septa
  exocrine glands, 76
  interarterial, 545, *555*
  interatrial, *544,* 545, *546*
  intermuscular, 294
  interventricular, *541, 544,* 545, *546,* 557, *558*
  medium, 714, *714*
  nasal, 633, *634–635*
  scrotum, 705, *706–707*
Septal defects (heart), 560*t*
Septicemia, 535*t*
Serine protease, 713
Serosa, 18, *18,* 655, *656*
  liver, 673, *674–675*
  small intestine, *670*
  stomach, *666*
Serotonin, *533,* 533–534
Serous demilune, 662
Serous membranes, 17, *19, 78,* 79
  digestive tract, *657*
Serrate suture, 206, *207,* 208, 211*t*
Sertoli cells, 510, *510,* 707
Serum, plasma, 522, 522*t*
Sex characteristics, 704–705, 704*t*
Sex organs, primary and secondary, 704, 704*t*
Sex steroids, 508, *508*
  bone growth and, 144
Sexual differentiation, prenatal development, 727, *728–730,* 730
Sexual dimorphism, pelvis, 193
Sexually transmitted diseases, 732–734
Sexual reproduction, 704
Sexual responses, 415
Shaft, hair, 117, *117*
Shingles, 384
Shinsplints, 325*t*
Shock, spinal shock, 393–394, 394*t*
Shoulder
  bones, 185–186, *186*
  dislocations, 223–224
  joint, 221–223, *223,* 229*t*
  muscles, *278,* 295*t*–296*t, 296*
Sickle-cell disease, 536
Signal conduction, myelin and, 360–361
Simple diffusion, 33–34, *34*
Simple epithelia, 57, 58*t*–59*t*
Single-unit smooth muscle, 256, *256*
Sinoatrial (SA) node, 552, *553*
Sinuses
  anal, 671, *672*
  carotid, *434–435,* 567, 576*t*–578*t, 577–578*
  cavernous, 579*t*–580*t, 580–581*
  confluence, 579*t*–580*t, 580–581*
  coronary, *550,* 552
  dural, 402, *402*
  dural venous, 579*t*–580*t, 580–581*
  frontal, *332, 634*
  inferior sagittal, 579*t*–580*t, 580–581*
  lactiferous, 725–726, *726–727*
  renal, 687, *688*
  scleral venous, *483,* 484
  sigmoid, 579*t*–580*t, 580–581*
  skull, 155, *155, 159*
  sphenoid, *634*
  straight, 579*t*–580*t, 580–581*
  superior sagittal, 402, *402,* 579*t*–580*t, 580–581*
  transverse, 402, *402,* 579*t*–580*t, 580–581*
  urogenital, *728*
  venous, 571
Sinusoids (discontinuous capillaries), 568, *569*
  hepatic, *589*
Sinus venosus, 557, *558*
Sister chromatids, 48
Situs inversus, 6
Situs perversus, 6
Skeletal muscle, 73, *74,* 74*t,* 237–260
  anatomy, 237–244
  attachments, 239–240, *240*
  blood supply, 250, *250*
  contraction and relaxation, 250–253, *252*
  developmental and clinical perspectives, 257–259, 260*t*
  fibers, 236, *236,* 244–247, *244–247*
  functional groups, 240–241
  microscopic anatomy, 244–250
  muscle fiber classification, 253–254, 253*t,* 254*t*
  pump, 571, *571*
  reflexes, 392
  structural hierarchy, 247*t*
Skeletal system, 9, *10*
  aging and, 144–145
  appendicular skeleton, 184–202
  axial skeleton, 151–180
  bone development, 139
  bone disorders, 145–148
  bones of, 153, 153*t*
  developmental and clinical perspectives, 176–180
  fetal skeleton, 176, *176*
  functions, 132
  joints, 205–232
  osseous tissue histology, 134–145
  overview, *152,* 152–153, 153*t*
  skull, 155–166
  tissue and organs, 132–134
  vertebral column and thoracic cage, 167–175
Skene glands, 724, *725*
Skin, 109–116
  burns, 126–127, *127*
  cancer, 125–126, *126*
  color, *114,* 114–115
  disorders, 125–127, *125–127,* 125*t*
  endocrine cells in, 510, 512*t*
  functions, 109
  markings, 116
  prenatal development, 123–124, *123–124*
  scrotal, *707*
  stratification, 113–114, 114*t*
  structure, *76,* 109, *110*
Skin grafts, 128
Skull, 155, *155, 156–158,* 159–166, 159*t*
  bipedalism and adaptation of, 166, *166*
  development, 176, *176–177*
  fractures, 179–180, *180*
Sleep
  apnea, 645, 650*t*
  hypothalamic control, 415
  reticular formation, 410
Slow block to polyspermy, *86,* 86–87
Slow oxidative muscle fibers, 253–254, 253*t,* 254*t*
Slow-twitch muscle fibers, 253–254, 253*t,* 254*t*
Small intestine, *335, 341, 342, 435, 657*
  anatomy, 667–670, *668–670, 687*
  endocrine cells in, 510, 512*t*
Smears
  blood, 71
  tissue, 55
Smegma, 713
Smell, 420, *429,* 429*t,* 468–470, *469–470*
  receptors, 461
Smooth endoplasmic reticulum, 43
Smooth muscle, 73, *74,* 74*t,* 236, *254,* 255–257, 255*t, 256*
  bronchial, *641*
  juxtaglomerular apparatus, *695*
  tone, 257
Sodium bicarbonate, 677, 678*t*
Sodium-potassium (Na^{+}-K^{+}) pump, 35
Soft palate, 164, *631, 658*
Soma. *See* Neurosoma
Somatic efferent pathways, 445, *445,* 445*t, 448*

Somatic motor fibers, *72,* 248, 381, 381*t,* 410
  facial nerve, *433*
  oculomotor nerve, *427–428, 430*
Somatic motor nerves, *352,* 353, 443
Somatic receptors, 392
Somatic reflexes, 391–393, *392,* 393*t*
Somatic sensory nerves, *352,* 353
Somatomedins. *See* Insulin-like growth factors
Somatosensory association area, 421
Somatosensory nerves, *386,* 386*t,* 420–421
Somatosensory senses, 420–421
Somatostatin, *501,* 502, 502*t,* 509, *509,* 511*t*
Somatotopy, 421, *421*
Somatotropin. *See* Growth hormone
Somites, 91–92, *97,* 678, *679–680*
Sonography, 6, *6*
Sound waves, auditory function, 475, *475*
Spastic cerebral palsy, 104
Spatial orientation and movement, 478–479, *478–479*
Sperm, 704, 709, *710–712,* 711, *711*
Spermatic cord, 705, *706–708, 730*
Spermatic ducts, 712
Spermatids, *708,* 709, *710–712*
Spermatocytes, 708, *710–712*
Spermatogenesis, 709, *710–712,* 711
  meiosis, 85
  migration and capacitation, 85–86
Spermatogonia, 709, *710*–712
Spermatozoon, 711, *712*
Sperm count, 713
Spermiogenesis, 709, *710–712,* 711
Sphenoid sinus, 155, *155, 159*
Sphenomandibular ligament, 221, *221*
Spheroidal cells, 27, *28*
Sphincter muscles, 73
Spicules, 136
Spina bifida, 367–368, *368*
Spinal cord, *332, 340–341,* 372–379, *373–374, 376–377,* 376*t, 379, 427*
  central canal, *374,* 375
  cross-sectional anatomy, *374,* 375
  disorders, 393–394, 394*t*
  injury, *179,* 179–180, 393–394, 394*t*
  regions, *447*
  spinal nerves and, 384, *384–385*
  surface anatomy, 372, *373*
  tracts, 375, *376*
  vestibular projection pathways, *376,* 479
Spinal curvature, abnormal, 168, *168*
Spinal gating of pain, 466, *466*
Spinal meninges, 373–375, *374*
Spinal meningitis, 394*t*
Spinal nerves
  accessory nerve, *436*
  anatomy, 382, *383–385*
  distal branches, 384, *384–385*
  fetal development, 367
  proximal branches, 382, 384
  rami, 384, *385*
  sympathetic nervous system, 448
Spinal shock, 393–394, 394*t*
Spinal stenosis, 179*t*
Spinal taps, 375, 404
Spinal tracts, 375–379, *376–377,* 376*t, 379*
  ascending, 375–378, *376,* 376*t, 377*
  decussation, 375, *376,* 376*t,* 378
  descending, 375, *376,* 376*t,* 378–379, *379*
Spindle fibers, 48
  meiosis, *710*
Spine
  curvatures, vertebral column, 168, *168,* 169
  vertebral column, *167–168,* 167–175
Spinocerebellar tracts, 375, *376,* 376*t,* 378, 406, *407–408,* 409, *412*
Spinoreticular tract, *376,* 376*t,* 378
Spinothalamic tract, *376,* 376*t,* 378, *407–408,* 409
Spiral organ, *473,* 474
Spleen, *335, 336, 589, 687*
  celiac circulation, *585*
  vagus nerve, *435*
Splenius capitis and cervicis muscles, *278*
Spondylosis, 179*t*
Spongiocytes, 508, *508*
Spongy (penile) urethra, 696, *697*
Spontaneous abortion, 100, 734*t*
Spreads, tissue, 55
Squamous cell carcinoma, 126, *126*
Squamous cells, 27, *28*
  alveoli, 641, *642*
  simple epithelia, 57, *58,* 58*t*
  stratified epithelia, 57, *60,* 60*t*
Squamous suture, *156, 158,* 160
SRY gene, 727
Sserratus anterior muscle, 295*t*–296*t, 296*
Stab cells, 527
Stability, muscles, 237
Stains, tissue sections, 55
Stapes, 166, 471–472, *471–472, 475*
Static equilibrium, 475–478, *476–478*
Stellate cells, 27, *28, 418*
Stem cells, 50
  epidermis, 110–111, *111*
  hemopoietic stem cell, 525
  stomach, 664, *665–666,* 667, 667*t*
Sterility, 713, 714*t*
Sternal angle, *173,* 174
Sternal bars, 179
Sternal end (clavicle), 185, *185*
Sternoclavicular joint, 185
Sternum, *173,* 173–174, *331, 334, 338, 340, 541, 674*
  development, 179
Steroid hormones, 507–508, *508*
Stigma, ovulation, *720,* 720–721
Stimuli, neuronal, 353
Stomach, *334, 335, 341, 655, 657*
  anatomy, 664, *665–666,* 667, 667*t, 687*
  celiac circulation, *585*
  endocrine cells in, 510, 512*t*
  prenatal development, *680*
  vagus nerve, *435*
Strains, joints, 231*t*
Stratified epithelia, 57, *60,* 60*t*
Stratified epithelium, 57, *60–61,* 60–61*t*
Stratum basale, 111, *111,* 114*t*
  endometrium, 722, *722*
Stratum corneum, *111,* 112, 114*t*
Stratum functionalis, 722, *722*
Stratum granulosum, *111,* 111–112, 114*t*
Stratum lucidum, *111,* 112, 114*t*
Stratum spinosum, 111, *111,* 114*t*
Stress fractures, 145, 145*t, 146*
Stretch reflex, 393, 393*t*
Striae (stretch marks), 113
Striations
  cardiac muscle, 554, *554*
  muscle, 73, *246,* 246–247
  skeletal muscle, 236, *236*
Stroke, 605*t*
Stroma
  exocrine glands, 76
  liver, 675, *675*
  pancreatic, 677, *677*
Styloglossus muscle, *273*
Subacromial bursa, 223, *223*
Subarachnoid space, 374, *374, 400,* 403
Subcoracoid burse, 223, *223*
Subcutaneous fat, 113–114
Subcutaneous tissue, structure, 109–110, *110,* 113–114, 114*t*
Subdeltoid bursa, 223, *223*
Subdural space, *400,* 403
Sublingual gland, *433, 655, 659,* 662, *662*
Sublingual orifice, *658*
Subluxation, joints, 231*t*
Submandibular gland, *433, 655, 659,* 662, *662*
Submandibular orifice, *658*
Submucosa, 655, *656*
  stomach, *666*
Subscapular bursa, 223, *223*
Substantia nigra, 409
Sudorferous glands, 120–121, *121*
Sulcus (sulci)
  alar nasal, *635*
  of brain, 399, *400–401,* 415–416, *416, 479, 480*
  coronary, *542–544,* 545
  gingival, 660–661, *660–661*
  interventricular, *542, 544,* 545
  intraventricular, 545
  terminal, 659, *659*
Superciliary ridge, *331*
Superficial fascia of penis, *714*
Superficial perineal space, 287*t, 288*
Superior articular facet, 169, *170*
Superior cerebellar peduncles, 410
Superior colliculi, *407,* 409
Superior conchae, 163, *163*
Superior palpebral sulcus, *331*
Superior peduncles, *407,* 411, *411–412*
Superior sagittal sinus, 402, *402*
Superior vertebral notch, 169, *170*
Supination, 9
  of foot, 219, *219*
  synovial joints, 216–217, *217*
Supinator muscle, 301*t, 302*
Supine position, 9
Supporting cells (tongue), *467,* 468
Supracondylar ridges, 187, *187*
Suprahyoid muscle group, 275*t, 276*
Supraorbital margin, 160
Suprascapular notch, 186, *186*
Supraspinatus muscle, *299–300,* 300*t*
Suprasternal notch, 173, *173, 331, 338*
Surface anatomy, 2, 330
Surgery
  arthroscopic, 227, *227–228*
  exploratory, 4
  tension lines and, 113
Sustentacular cells, 510, *510,* 707, *708, 711*
Sutures
  joints, 206, *207,* 208, 211*t*
  skull, 155, *155, 156*
Swallowing center, 273*t*–276*t, 276,* 663
Sweat
  glands, *76,* 120–121, *121*
  skin function, 109–110
Sweat glands, 120–121, *121*
Swell body, 633, *634–635*
Sympathetic nervous system, *352,* 353, 444–445, *445,* 452*t*
  abdominal components, 449, *449*
  adrenal medulla, 507, *508*
  anatomy, *446–449,* 446–450
  central control, 455–456, *456*
  digestive tract, 655, *656*
  effects, 453–456, 453*t*
  heart and, 554–555
  pathways, 448, *448*
  prenatal development, 514, *514*
  renal innervation, *449,* 689, *695*
Symphyses, 208, *209,* 211*t*
Synapses
  chemical, 362–363, *363*
  electrical, 363
  neural circuits and, 361–363, *362–363*
Synaptic cleft, *248,* 248–249, 362, *363*
Synaptic vesicles, *248,* 249, 362, *363*
  tongue, *467*
Synarthrosis/synoarthroidal joint, 206, *207*
Synchondroses, 208, *209,* 211*t*
Syncytiotrophoblast, 88, *90*
Syndacytyly, 201–202, *202,* 202*t*
Syndesmosis, *207,* 208, 211*t*
Synergist muscle, 240
Synostosis, 206, 211*t*
Synovial fluid, 210, *210*
Synovial joints, 209–230, 229*t*
  abduction/adduction, 214, *215*
  anatomy, 210, *210,* 220–230
  circumduction, 216, *216*
  classification, 210–211, 211*t*
  elevation and depression, 214, *215*
  flexion and extension, 213, *214*
  movement, 213–219, *214–219*
  protraction and retraction, 214, *215,* 216
  range of motion, 219–220
  rotation, 216, *216*
  supination/pronation, 216–217, *217*
Synovial membrane, 210, *210*
Synovitis, 231*t*
Synthesis (S) phase, cell cycle, 47
Systemic anatomy, 2
  arteries, *574*
  veins, *575*
Systemic circuit, 540–541, *540–541*
  appendicular region, 590–600
  axial region, 573, *574–590*
Systolic contraction, *555,* 555–556

T

Tactile (Merkel) cells, 111, *111*
Tactile corpuscle, *462,* 462*t,* 463
Tactile disc, *462,* 462*t,* 463
Taeniae coli, 671, *672*
Talipes, 201–202, *202,* 202*t*
Talocrural (ankle) joint, *228,* 228–229
Target organs and cells, 498–499, *499*
Tarsal gland, 480, *481*
Tarsal plate, 480, *481*
Tarsal region, 16, 193
Taste, 420, 466–468, *467–468*
  cells, 467, *467*
  glossopharyngeal (IX) nerve, *434*
  hairs, 467, *467*
  pores, *467,* 467–468
  primary sensations, 468
  receptors, 461
Taste buds, 466–468, *467*
Tay-Sachs disease, 361
Tectorial membrane, *473,* 474
Tectospinal tracts, 375, *376,* 376*t,* 378, *379,* 406, *407–408*
Tectum, 378, *379, 407,* 409
Teeth, *655, 659,* 660–661, *660–661*
  diseases, 661
Tegmentum, *407,* 409
Telencephalon, *366,* 366–367, *493*
  prenatal development, *513*
Telogen phase, hair cycle, 119, *119*
Telophase
  meiosis, *710*
  mitosis, *49,* 50
Temporalis muscle, *274,* 274*t*
Temporal lobe, *400–401,* 416, 425*t,* *426, 427*
Temporomandibular joint, 165, *165*
  anatomy, 220, *221*
  syndrome, 220
Tendinitis, 210
Tendinous cords, *544,* 546, *546, 547*
Tendon organ, *462,* 462*t,* 463
Tendon(s). *See also* specific tendons
  abdominal wall, 281*t*–283*t*
  Achilles, *228,* 229, 316*t, 318*
  action of, 220
  biceps brachii, 221–223, *223*
  biceps femoris, *348*
  calcaneal, *348*
  carpal tunnel syndrome, 307, *307*
  elbow, *223,* 223–224
  extensor digits, *344, 345*
  extensor pollicis brevis, *345*
  extensor pollicis longus, *345*
  fibularis longus and brevis, *347*
  flexor carpi radialis, *345*
  foot, 316*t, 317*
  forearm, *306,* 306*t*
  joints and, 210
  knee, 226, *226–227, 313,* 313*t, 314,* 315*t*
  leg, *313,* 313*t, 314,* 315*t*
  muscle attachments, 239–240, *240*
  palmaris longus, *303–304,* 303*t*–305*t, 345*
  quadriceps femoris, 196–197, *346*
  quadriceps tendon, 226, *226–227*
  quadriceps (patellar) tendon, *313,* 313*t*
  reflex, 393, 393*t*
  respiratory system, 279*t*
  semimembranous, *347*
  semitendinosus, *347, 348*
  shoulder, 221–223, *223*
  superior oblique, *481*
  tibialis anterior, *347*
  wrist and hand, 303*t*–306*t, 304–306*
Tendon sheaths, 210, *211*
Tennis elbow, 325*t*
Tennis leg, 325*t*
Tension lines, surgery and, 113
Tentorium, *402,* 402–403
Teratogens, 102–103, *103*
Teratology, 100
Teres minor muscle, *299–300,* 300*t*
Terminal arborization, *355,* 356
Terminal bronchioles, 640, *641*
Terminal hair, 117
Terminal web, 40
Terminologia Anatomica (TA) system, 20
Testes, *335, 342, 499*
  anatomy, 705, *706–708*
  descent, 730, *730*
  histology, 510, *510*
  hormones, *504,* 512*t*
  prenatal development, *728, 730*
Testicular cancer, 715, 732*t*
Testis-determining factor (TDF), 727
Testosterone, 510, 512*t*
Tetrads, meiosis, *710*
Tetraiodothyronine, 506
Thalamus, *403, 407,* 410, *411–412,* 413–415, *414, 418*
  auditory function, *476*
  at brainstem, 376
  facial nerve, *433*
  geniculate nuclei of, 490, *490*
  optic nerve (II), *429*
  pain signals, 465
  taste and, 468, *468*
  vestibular projection pathways, *479*
Thalassemia, 534, 535*t*
Thalidomide, 103, *103*
Theca, 509–510, *510, 719*
Theca folliculi, *716–717, 719–720,* 720
Thelarche, 731
Thenar eminence, *344–345*
Thenar muscle group, *308,* 309*t*
Thermoreceptors, 109–110, 461
Thermoregulation, 415
  skin, 109–110
Thick skin, 109
Thigh, anatomy, *346*
Thin skin, 109
Third-class lever, 242, *243*
Third-degree burns, 127, *127*
Thoracic cage, 167, *173,* 173–175
Thoracic cavity, *16,* 17, *340*
  cross-section, *642,* 642–643
  heart in, 541, *541*
Thoracic curvature, 168, *168*
Thoracic region, 13, *14, 338, 340,* *372, 373*
  arteries, *581,* 581*t*–582*t*
Thoracic vertebrae, 167, *167–168,* *171,* 171–172
  development, 177–178, *178*
Thoracolumbar fascia, *284–286,* 284*t*–286*t*
Thoroughfare channel, 568
Thrombocytes, 533, *533*
Thrombocytopenia, 535
Thrombopoiesis, 533, *533*
Thrombopoietin, 532
Thrombosis, 534
Throroughfare channel, *570*
Thumb
  anatomy, *344–345*
  movements of, *218,* 219
Thymopoietin hormone, 505, *505,* 511*t*
Thymosin hormone, 505, *505,* 511*t*
Thymulin hormone, 505, *505,* 511*t*
Thymus gland, 17, *499,* 505, *505*
Thyroglobulin, 506, *506*
Thyroid diverticulum, *513,* 513–514, *514*
Thyroid follicles, 506, *506*
Thyroid gland, *335, 499,* 505–506, *505–507*
  disorders, 515, *515,* 516*t*
  hormones, *504,* 511*t*
  prenatal development, *513*
Thyroid hormone, 506
  disorders, 515, *515*
Thyroid-stimulating hormone, *501,* 502, 503*t, 504*
  disorders, 515, *515*
Thyrotropin. *See* Thyroid-stimulating hormone
Thyrotropin-releasing hormone, *501,* 502, 502*t, 504*
Thyroxine, 506, 511*t*
Tibia, 197, *197, 347–348*
Tibiofemoral joint, 225–228, *226–227*
Tic douloureux, 431
Tight junctions, 38, *39*
  capillaries, *568*
  spermatogenesis, *711*
  stomach, 667
Tinnitus, 493*t*
Tissue, 9. *See also* specific tissue types
  classification, 54, 54*t*
  connective tissue, 63–71
  digestive tract, *656*
  endocrine cells in, 510–511, 511*t*
  epithelial tissue, 56–62, *57–62*
  erectile, 633, *634–635,* 714
  glandular, 75–78
  growth, 79
  hemopoietic, 524–525
  histology (microscopic anatomy), 54–81
  interstitial fluid, 30
  membranes, 78–79
  neuromuscular tissue, 72–74
  osseous, 70, *70,* 70*t*
  repair, 79–80
  sections, 54–55, *55–56*
  shrinkage and death, 80–81
  skeletal system, 132–134
  subcutaneous tissue, 109–110, *110*
Tissue engineering, 80, *80*
Titin (connectin), 246, *246*
Tongue, *332, 634, 655*
  anatomy, 466–468, *467–468,* 659, *659*
  muscles of, 273*t*
  prenatal development, *513*
Tonometry, 484
Tonsils
  lingual, *467, 634*
  palatine, *467, 634*
  pharyngeal, *634*
Touch
  glossopharyngeal (IX) nerve, *434*
  receptive field, 463, *464*
Toxins, metabolism, 674*t*
Trabeculae, 136, *137–138,* 138
  carneae, *544,* 545, *546*
  exocrine glands, 76
  penis, 714
Trachea, *332, 336, 631*
  anatomy, 638–639, *638–639*
  parathyroid gland, *507*
  prenatal development, *513, 648*
  thyroid anatomy, 506, *506*
  upper respiratory tract, *631, 634,* 636, *636*
Trachealis, 638–639, *638–639*
Tracheal mucosa, *636*
Tranasverse tubules, 245
Transcellular route, 693
Transcytosis, *569*
Transection, spinal cord, 393–394, 394*t*
Transferrin, 522, 522*t*
Transmission electron microscope (TEM), 26, *27*
Transport proteins, 33, *34*
Transport vesicle, 43
Transverse arch, 200, *200*
Transverse humeral ligament, 221–223, *223*
Transverse ligament
  knee, 226–227, *226–227*
  vertebrae, 170, *170*
Transverse plane, 12, *12*
Transverse rectal folds, 671, *672*
Transverse sinus, 402, *402*
Transverse tissue section, tissue, 55, *56*
Trasitional epithelium, 57, *61,* 61*t,* 62
Trauma, skin, 109
Triangular muscles, 239, *239*
Trichromatic vision, 487
Trigeminal neuralgia, 431
Trigger zone, 354, *355*
Trigone, 696, *697*
Triiodothyronine, 506, 511*t*
Trimesters (pregnancy), 87
Triplo-X syndrome, 100
Trisomy-13, 101
Trisomy-18, 101
Trisomy-21, 101–102, *102*
Trochanters, 195, *195*
Trochlea, 187, *187, 481,* 482
Trochlear notch, *187,* 188
Trophoblast, 88, *90*
Trophoblastic (deciduous) nutrition, 95, *95*
Trophoblastic phase, 95
Tropomyosin, 245, *245*
Troponin, 245, *245*
True ribs, 174, *174*
Truncus arteriosus, 557, *558*
Trunk
  anatomy, 13, *14, 333–334*
  brachiocephalic, *577–578,* 577*t*–578*t, 581, 591*

  celiac, *584–585,* 584*t,* 656–657
  costocervical, 576*t*–578*t, 577–578, 581*
  female anatomy, *333*
  male anatomy, *334*
  movements, 217, *218*
  pulmonary, 541, *546, 549,* 572, *573,* 601, *601*
  thoracoacromial, *581*
  thyrocervical, 576*t*–578*t, 577–578, 581*
Trunk muscles, 279–289
Trypsinogen, 678*t*
Tubercle(s)
  conoid, 185, *185*
  genital, 727, *728–730,* 730
  humerus, 186–187, *187*
  ischial, 191, *192*
  ribs, 174, *174*
  vertebral, 169–170, *170*
Tuberculosis, 649, 650*t*
Tuberosities of bone
  deltoid, 187, *187*
  gluteal, 195, *195*
  ischial, *707, 725*
  radial, *187,* 188
  tibial, 197, *197, 346*
Tubular glands, 76
Tubular reabsorption, 691, *691*
Tubular secretion, 691, *691*
Tubule lumen, *708*
Tubulin, 40, *42*
Tubuloacinar gland, 76
Tufted cells, 468–469, *469–470*
Tumors, malignant tumors, 48, *48*
Tumor-suppressor (TS) genes, 48
Tunica albuginea
  female, 716–717, *716–717, 720*
  male, 705, *706–708,* 714, *714*
Tunica externa (tunica adventitia), 564, *565, 566,* 571
Tunica interna (tunica intima), 483, 564, *565, 566,* 571
Tunica media, 564, *565–566,* 571
Tunica vaginalis, 705, *706–708, 730*
Tunica vasculosa, 483
Turbinates, *158,* 163, *163,* 633, *634–635*
Turner syndrome, 101–102
Two-point touch discrimination, 463, *464*
Tympanic cavity, 471–472, *471–472*
Tympanic membrane, 471–472, *471–472, 475, 492*
Tympanic part, 160, *161*
Type A and B spermatogonium, 709
Type II muscle fibers, 253–254, 253*t,* 254*t*
Type I muscle fibers, 253–254, 253*t,* 254*t*

U

Ulcerative colitis, 680*t*
Ulcer(s), peptic, 668, *668*
Ulna, *187,* 188
Ulnar flexion, 217, *218,* 219
Ulnar notch, *187,* 188
Ultraviolet radiation, skin color and, 115
Umbilical cord, 95, 601, *601–602, 604*
Umbilical region, 16
Umbilicus, *333, 338*
Umbrella cells, 62, 696, *697*
Unencapsulated nerve endings, 461–463, *462,* 462*t*
Unicellular glands, 76, *76*
Unipolar neurons, 356, *356*
Unipotent stem cells, 50
Upper limb, *344. See also* Arm; Elbow; Hand; Shoulder; Wrist
  blood vessels, 590–593
  bones of, 185–190
  development, 200–201, *201*
  evolution of, 300
  muscles and compartments of, 294–309
Upper respiratory tract, 631
  components, 632–637
Urea, 686
Uremia, 686
Ureteric bud, 698
Ureter(s), *336, 687–688*
  anatomy, 685, *685,* 695–696
  male, *706*–707
Urethra, *337, 342*
  anatomy, 685, *685,* 696, *697*
  female, *716–717*
  male, *706–707,* 712, *714*
  membranous, 696, *697, 706*–707
  prenatal development, *728*
  prostatic, 696, *697*
  spongy (penile), 696, *697, 706*–707
Urethral glands, 697
Urethral groove, *729*
Urethral orifice
  female, *725*
  male, *714*
Urethral sphincter, *697*
Urinalysis, 692
Urinary incontinence, 698, 700*t*
Urinary pole, 691
Urinary system, 9, *10,* 684–700
  aging, 698, 700
  anatomy, 685, *685*
  bladder, *334, 336, 342, 604, 680,* 685, *685,* 696, *697, 716–717*
  developmental abnormalities, 698
  disorders, 700, 700*t*
  functions, 685–686
  prenatal development, 697–698, *699, 728*
  urine production, 691, *691*
Urinary tract, infections, 696
Urine, blood and protein in, 692
Urobilinogen, 673
Urogenital folds, 727, *728–730,* 730
Urogenital triangle, 287*t*–288*t, 288*
  male, *707*
Uroplakins, 62
Uterine milk, 95
Uterine tube, *336, 716–718,* 721, *721*
  prenatal development, *728*
Uterine wall, 722
Uterus, *336, 342, 716–717*
  anatomy, 721–722, *722*
  histology, 723
  prenatal development, *728*
Utricle, *472,* 475–478, *476–478, 492*
Uvula, *634, 658*

V

Vagal trunks, 450, *451*
Vagina, *337, 342, 718*
  anatomy, 724
  prenatal development, *728–729*
Vaginal orifice, *716–717, 725*
Vaginal process, *730*
Vaginal rugae, *716–717,* 724
Vallate papillae, 467, *467*
Valvular prolapse, 546
Van Leeuwenhoek, 564
Varices, 681
Varicocele, 732*t*
Varicose veins, 571
Varicosities
  neurons, *355,* 356
  smooth muscle, 256, *256,* 445
Vasa recta, 689, *689*
Vasa vasorum, 564, *565*
Vascular disease, 603, 605*t*
Vascular layer, 482–484, *482–484*
Vascular plexuses
  abdominal aortic, 449, *449, 451,* 452
  cardiac, 450, *451*
  carotid, 448
  pulmonary, 450, *451*
Vascular pole, 691
Vascular system, aging, 603
Vasculitis, 605*t*
Vas deferens, *706–708,* 712
  prenatal development, *728*
Vasectomy, 712
Vasoconstriction
  blood vessels, 564
  cutaneous, 109
  hemostasis, *533,* 533–534
Vasodilation, 564
  cutaneous, 109
Vasomotor center, 406, *407–408*
Vasomotor tone, 455–456, *456*
Vein(s)
  abdominal region, *588–589,* 588*t*–589*t*
  abdominal wall, *588,* 588*t*
  antebrachial, 592*t*–593*t, 593*
  arcuate, 687, *688–689*
  axillary, *335, 575, 580,* 592*t*–593*t, 593*
  azygos, 582*t, 583*
  basilic, *575,* 592*t*–593*t, 593*
  blood vessels, *566*
  brachial, *335, 575,* 592*t*–593*t, 593*
  brachiocephalic, *335, 575, 580,* 582*t, 583*
  bronchial, 582*t, 583*
  cardiac, *550*
  cardinal, 601, *601–602*
  central, 673, *674–675*
  cephalic, *333, 335, 344, 575,* 592*t*–593*t, 593*
  circumflex femoral, 597*t, 598–599*
  classification, 570–571, *570–571*
  cortical radial, 687, *688–689*
  cubital, *344, 575,* 592*t*–593*t, 593*
  cystic, *589,* 589*t*
  deep, 592*t*–593*t, 593,* 597*t, 598–599*
  deep femoral, *575,* 597*t, 598–599*
  deep plantar venous arch, 597*t, 598–599*
  diaphragm, *575*
  dorsal, *714,* 714–715
  dorsal venous network, *575,* 592*t*–593*t, 593,* 597*t, 598–599*
  esophageal, 582*t, 583*
  facial, 579*t*–580*t, 580–581*
  femoral, *333, 334, 575,* 597*t, 598–599*
  fibular, *575,* 597*t, 598–599*
  gastric, *589*
  gastro-omental, *589*
  general anatomy, 564–572
  gonadal, *575*
  great cardiac, 552
  great cerebral, *580*
  great saphenous, *333, 575,* 597*t, 598–599*
  head, 579*t*–580*t, 580–581*
  hemiazygos, 582*t, 583*
  hemorrhoidal, 671, *672*
  hepatic, *336, 575, 585, 588,* 588*t, 674–675,* 676
  hepatic portal system, *589,* 589*t,* 657, *674–675,* 676
  iliac, *583, 588,* 588*t,* 597*t, 598–599*
  iliolumbar, *583*
  intercostal, 582*t, 583*
  interlobar, 687, *688–689*
  interventricular, *550*
  jugular, *334, 340, 575,* 579*t*–580*t, 580–581, 583*
  kidney, *575*
  lower limb, 597*t, 598–599*
  lumbar, 582*t, 583, 588,* 588*t*
  marginal, *550,* 552
  median antebrachial, *575*
  mediastinal, 582*t, 583*
  medium, 570
  mesenteric, *341, 589,* 589*t*
  neck, 579*t*–580*t, 580–581*
  ophthalmic, *580*
  ovarian, *588,* 588*t,* 717, *718, 722*
  palmar arches, *575,* 592*t*–593*t, 593*
  palmar venous network, 592*t*–593*t, 593*
  pampiniform plexus, 705, *706–707*
  pancreatic, *589,* 589*t,* 677, *677*
  pelvic region, *588–589,* 588*t*–589*t*
  pericardial, 582*t, 583*
  phrenic, *588,* 588*t*
  plantar, 597*t, 598–599*
  plantar venous arch, *575*
  popliteal, *575,* 597*t, 598–599*
  posterior interventricular, 552
  prenatal development, 601, *601–602*
  pulmonary, 541, *542, 546, 548,* 572, *573*
  radial, *575,* 592*t*–593*t, 593*
  renal, *583, 588,* 588*t, 685,* 687, *687–689,* 689
  retinal, 482–484, *482–484*
  small saphenous, *575,* 597*t, 598–599*
  splenic, *589,* 589*t*
  stomach, *666*
  subclavian, *335, 340, 575,* 582*t, 583,* 592*t*–593*t, 593*
  subcostal, 582*t, 583*
  superficial, 592*t*–593*t, 593,* 597*t, 598–599*

Vein(s) (*continued*)
  superficial cerebral, *580*
  superficial temporal, 579*t*–580*t*, *580–581*
  superior mesenteric, *336*
  suprarenal, *588,* 588*t*
  systemic circuit, *575*
  testicular, *588,* 588*t,* 709
  thebesian, *550,* 552
  thoracic, 582*t, 583*
  thyroid, 505–506, *505–506, 566,* 579*t*–580*t, 580–581*
  tibial, *575,* 597*t, 598–599*
  ulnar, *575,* 592*t*–593*t, 593*
  umbilical, 96, 601, *601–602, 604*
  upper limb, 592*t*–593*t, 593*
  vertebral, 579*t*–580*t, 580–581*
  vitelline, 601, *601–602*
Vellus, 116
Vena cava
  inferior, *336, 341, 542, 544, 546, 565, 588–589,* 588*t, 674, 685, 687*
  superior, *335, 336, 446, 542, 544, 546, 549, 575,* 582*t, 583*
  systemic circuit, 541, *541*
Venous anastomoses, 571–572, *572*
Venous drainage, 552
Venous valves, 571, *571*
Ventral respiratory group, 645, *646*
Ventricles
  of brain, *401, 403,* 404, 406, *407–408, 426, 501*
  heart, *340,* 541–542, *541–542, 544,* 545, *546, 548–549,* 557, *558*
  pulmonary circuit, *573*
Ventricular fibrillation, 560*t*
Venule(s)
  fundus, *485*
  muscular, 570
  portal, 500, *501–502,* 502–503, 503*t, 504*
  postcapillary, 570
  precapillary sinuses, *570*
  pulmonary, *642*
  small intestine, *670*
Vermis, 410, *411–412*
Vernix caseosa, 124, *124*
Vertebrae, *167–168,* 167–175, *340–341, 342, 685*
  cervical, 169–171, *170–171*
  coccygeal, *172,* 173
  development, 177–178, *177–178*
  fractures and dislocations, 179–180, *180*
  lumbar, 172, *172*
  regional characteristics, 169–173, *170–172*
  sacral, 167, *167–168, 172,* 172–173
  spinal nerves and, 384, *384–385*
  structure, 169, *169*
  thoracic, *171,* 171–172, 177–178, *178, 541–542*
Vertebral arch, 169, *169*
Vertebral canal, 17, 169, *169*
Vertebral column, *167–168,* 167–175, *332, 634*
  development, 177–178, *177–178*
Vertebral furrow, *339*
Vertebra prominens, 171, *171*
Vesicouterine pouch, *716–717,* 722
Vesicular transport, *35,* 35–36
Vestibular apparatus, 475–478, *476–479*
Vestibular bulbs, 724, *725*
Vestibular fold, *634,* 636, *636*
Vestibular glands, 724, *725*
Vestibular membrane, 473, *473*
Vestibule
  ear, *434,* 471, *471–473,* 473
  mouth, 658–659
  nasal, 633–634, *634–635*
  vaginal, 724, *725, 728*
Vestibulospinal tracts, 375, *376,* 376*t,* 378, *379, 412, 479*
Villi, small intestine, 669, *669–670*
Viscera, 16, 16*t*
  retroperitoneal, *336*
Visceral motor nerves, *352,* 353. *See also* Autonomic nervous system (ANS)
Visceral muscle, 73, 256, *256*
Visceral nerve fibers, 381, 381*t*
Visceral pericardium, 17
Visceral peritoneum, 18
Visceral plueura, 17
Visceral reflexes, 392, 443–444, *444*
Visceral sensory nerves, *352,* 353
Viscerocranium, 176
Viscosity, plasma, 522, 522*t*
Vision, *429,* 480–490. *See also* Eye(s); Retina
  color, 487
  day, 487
  duplicity theory, 488
  image formation, 485, *486,* 486*t*
  night vision, 487
  receptive field, 463, *464*
  receptors, 461
Vistibulocochelar nerve, 161
Visual cortex, 423–424, *424,* 490, *490*
Vitamin A, bone growth and, 144
Vitamin C (ascorbic acid), bone growth and, 144
Vitamin D (calcitriol), 510
  bone growth and, 144
Vitamins, metabolism, 674*t*
Vitelline duct, 93, 678, *679–680*
Vitreous body (vitreous humor), 64, 482–484, *482–484, 487, 493*
Vitreous chamber, *482,* 484
Vocal cord, *332, 634,* 636–637, *636–637*
Volar surface, *344*
Voluntary muscle contractions, 73, 236
Vomer, *155–156,* 165, *634*
Vulva, 724, *725*

W

Water retention, 691, *691*
  skin, 109
Wernicke area, *420,* 423, *424*
Whiplash injury, 179–180, *180*
White blood cells (WBCs), 71, 521, *521,* 522*t, 527,* 527–529, 527–532, *528–529,* 528*t*–529*t, 531*
  complete blood count (CBC), 532
  differential count, 527
  disorders, 535
  fibrous tissue, 63
White fibers, 64
White matter, 403, *403,* 416, *417, 426*
  spinal cord, *374,* 375
Wilms tumor, *48*
Wolff's law of bone, 143–144
Wrist
  anatomy, *345*
  bones of, 185–190, *189–190*
  muscles of, 303*t*–306*t, 304–306*

X

X-ray imaging, 4, *5*
  risks of, 103

Y

Yellow bone marrow, 138, *138*
Yolk sac, *91,* 92–94, *94,* 525, *679*
  angiogenesis, 601, *601–603*

Z

Z line (striated muscle), *246,* 246–247
Zona fasisculata, 508, *508*
Zona glomerulosa, 507–508, *508*
Zona pellucida, *719–720,* 720
Zona reticularis, 508, *508*
Zone of bone deposition, 141
Zone of calcification, 141
Zone of cell hypertrophy, 141
Zone of cell proliferation, 141
Zone of reserve cartilage, 141
Zygomatic arch, 160, *161, 433*
Zygote, 85, *86,* 87, 704
Zymogen granules, 677, *677*
Zymogens, 677, 678*t*

Johannes W. Rohen
Chihiro Yokochi
Elke Lütjen-Drecoll

Color Atlas of Anatomy

FOURTH EDITION

A Photographic Study
of the Human Body



Structure of the human body and the skeleton. Blue = joints.
A Head (caput) B Thorax (thoracic cavity) C Abdominal and pelvic cavities

In contrast to most other mammals the human body is adapted for bipedal locomotion. Three general principles in the architecture of the human organism are recognizable:

1. The principle of **segmentation,** which dominates in the trunk. The vertebral column and the thorax consist of relatively equal, segmentally arranged elements.
2. The principle of **bilateral symmetry.** Both sides of the body are separated by a midsagittal plane and resemble each other like image and mirror-image.
3. The principle of **polarity** between the head at one end of the body and the lower extremities at the other. As the center of the information system the head contains the main sensory organs and the brain. The head has a predominantly spherical form while the extremities consist of radially formed skeletal elements, the number of which increases distally.

A. The **skull** consists of two parts: 1. a **cranial part** containing mainly the brain and the sensory organs and 2. a **facial part** which contains the nasal and oral cavity and the chewing apparatus. The cranial cavity is continuous with the vertebral canal which contains the spinal cord.

B. The **thorax** contains the respiratory and circulatory organs (lung, heart, etc.) but also some of the abdominal organs which are located underneath the diaphragm.

C. The **abdominal cavity** contains the organs of metabolism such as the liver, the stomach and the intestinal tract as well as the excretory and genital organs (kidney, uterus, urinary bladder, etc.). The latter are located primarily in the **pelvic cavity** with the exception of the testes.

1 Cranial part } of the skull
2 Facial part } of the skull
3 Vertebral column (cervical part)
4 Clavicle
5 Scapula
6 Ribs
7 Sternum
8 Arm (humerus)
9 Vertebral column (lumbar part)
10 Radius } forearm
11 Ulna } forearm
12 Pelvis
13 Wrist (carpals) } hand
14 Fingers (phalanges) } hand
15 Thigh (femur)
16 Patella and knee joint
17 Tibia } leg
18 Fibula } leg
19 Tarsals } foot
20 Metatarsals } foot


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24

Median section through the trunk (female).


25
28
29
30
31
32
33
4
5
7
26
34
27
10
35

Positon of the inner organs of the human body (anterior aspect)
The main cavities of the body and their contents.

1 Sternum
2 Right ventricle of heart
3 Diaphragma
4 **Liver**
5 **Stomach**
6 Transverse mesocolon
7 Transverse colon
8 Umbilicus
9 Mesentery
10 **Small intestine**
11 Uterus
12 Urinary bladder
13 Pubic symphysis
14 Left atrium of heart
15 Caudate lobe of liver
16 Omental bursa or lesser sac
17 Conus medullaris
18 **Pancreas**
19 Cauda equina
20 Intervertebral discs (lumbar vertebral column)
21 Sacral promontory
22 Sigmoid colon
23 Anal canal
24 Anus
25 Head (neurocranium) with brain
26 Ascending colon
27 Appendix
28 Facial region (viscerocranium) with oral and nasal cavities
29 Trachea and larynx
30 Thorax with the lungs
31 **Heart**
32 Surface projection of the diaphragm
33 **Spleen**
34 Descending colon
35 Testis


sup.
2
post.
lat.
1
lat.
ant.
med.
inf.
3



Sagittal section through the human body (female). Demonstration of the main cavities of the body. Internal organs are removed.

A_1 Cranial cavity
A_2 Vertebral canal
B_1 Thoracic cavity
B_2 Pericardial cavity
C_1 Abdominal cavity
C_2 Pelvic cavity
D Diaphragm

◁

Planes of the body

1 Transverse plane
2 Frontal plane
3 Sagittal plane (midsagittal)

Lines of direction

ant. = anterior
inf. = inferior
lat. = lateral
med. = medial
post. = posterior
sup. = superior



Position of the inner organs of the human body (lateral aspect).
The three main cavities of the body and their contents.

1 Head (neurocranium) with the brain
2 Facial bones with oral and nasal cavities
3 Vertebral column (cervical part)
4 Thorax with the lungs
5 Heart
6 Surface projection of the diaphragm
7 Scapula
8 Liver
9 Stomach
10 Ascending colon
11 Transverse colon
12 Ureter
13 Appendix
14 Small intestine
15 Ovary, uterine tube
16 Rectum
17 Uterus
18 Urinary bladder


3
1
4
5
7
6
8
9
19
15
21
16
18
10
17
14
11
22
23
22
27
24
12
25
13
26
28
30
31
34
33
32
35
36
37

Skeleton of a female adult (anterior aspect).


3
2
8
9
20
10
21
16
23
11
22
27
12
13
29
30
31
33
32
37
38
36

Skeleton of a female adult (posterior aspect).



Skeleton of a 5-year-old child (anterior aspect).
The zones of the cartilaginous growth plates are seen (arrows). In contrast to the adult, the ribs show a predominantly horizontal position.

Axial skeleton

Head

1 Frontal bone
2 Occipital bone
3 Parietal bone
4 Orbit
5 Nasal cavity
6 Maxilla
7 Zygomatic bone
8 Mandible

Trunk and thorax

Vertebral column

9 Cervical vertebrae
10 Thoracic vertebrae
11 Lumbar vertebrae
12 Sacrum
13 Coccyx
14 Intervertebral discs

Thorax

15 Sternum
16 Ribs
17 Costal cartilage
18 Infrasternal angle

Appendicular skeleton

Upper limb and shoulder girdle

19 Clavicle
20 Scapula
21 Humerus
22 Radius
23 Ulna
24 Carpal bones
25 Metacarpal bones
26 Phalanges of the hand

Lower limb and pelvis

27 Ilium
28 Pubis
29 Ischium
30 Symphysis pubis
31 Femur
32 Tibia
33 Fibula
34 Patella
35 Tarsal bones
36 Metatarsal bones
37 Phalanges of the foot
38 Calcaneus



1 Subscapular fossa
2 Coracoid process
3 Glenoid fossa
4 Acromion
5 Spine of scapula
6 Infraspinous fossa

Ossification of the scapula
(left: anterior aspect, right: posterior aspect).



1 Cartilage of the iliac crest
2 Ilium
3 Cartilage
4 Pubis
5 Ischium
6 Acetabulum

Ossification of the hip bone
(left: medial aspect, right: lateral aspect).



1 Bone tissue (vertebral body)
2 Cartilaginous tissue (lateral epiphysis)
3 Intervertebral discs

Ossification of the sacrum (anterior aspect).
Note the five vertebral bones, which are still separated from each other.



1 Bony tissue (center of ossification)
2 Vertebral arch (not completely united)
3 Cartilaginous tissue (lateral epiphysis)
4 Sacral canal

Ossification of the sacrum
(posterior aspect).



1 Ossification center in the head of the femur
2 Greater trochanter
3 Head of the femur
4 Neck of the femur
5 Lateral condyle
6 Medial condyle
7 Intercondylar notch
8 Diaphysis

Ossification of the femur (left: coronal section, right: posterior view of the femur). Arrows: distal epiphysis.



X-ray of the upper and lower limb of a newborn child.
Left: upper limb. Right: lower limb.
Arrows: ossification centers.

1 Scapula
2 Shoulder joint
3 Humerus
4 Elbow joint
5 Ulna
6 Radius
7 Tibia
8 Fibula
9 Knee joint
10 Femur



X-ray of hand and foot of a newborn.

1 Ulna
2 Radius
3 Metacarpals
4 Phalanges
5 Tibia
6 Fibula
7 Talus
8 Calcaneus
9 Metatarsals
10 Phalanges



Femur of the adult. Left: the periosteum and the nutrient vessels are preserved. Right: coronal section of the proximal and distal epiphyses to display the spongy bone and the medullary cavity.

1 Metaphysis
2 Spongy bone
3 Medullary cavity in the diaphysis
4 Compact bone
5 Nutrient canal
6 Diaphysis
7 Epiphyseal line (remnants of the epiphyseal plate)
8 Epiphysis (head of the femur)
9 Fovea of head
10 Trabeculae of spongy bone
11 Neck of the femur
12 Greater trochanter
13 Lesser trochanter
14 Articular surface
15 Periosteum
16 Skin
17 Vastus medialis muscle
18 Sartorius muscle
19 Femoral artery and vein
20 Great saphenous vein
21 Gracilis muscle
22 Adductor longus muscle
23 Adductor magnus muscle
24 Semimembranosus muscle
25 Semitendinosus muscle
26 Rectus femoris muscle
27 Vastus lateralis muscle
28 Femur and medullary cavity
29 Vastus intermedius muscle
30 Sciatic nerve
31 Biceps femoris muscle
32 Spongy bone trabeculae containing bone marrow
33 Compact bone
34 Osteon with Haversian lamellae
35 Periosteum
36 Blood vessels and nerves for periosteum and bone



Coronal section through the proximal end of the adult femur, revealing the characteristic trajectorial structure of the spongy bone.



Three dimensional representation on the trajectorial lines of the femoral head (according to B. Kummer).



MR-Image of the thigh (axial section through the middle of the left thigh, the same level as the CT-Image).



CT-Image of the section through the middle of the left thigh (axial section). Note the differences between the CT- and MR-Image (see text below).

The **bones** of the skeletal system consist of two different parts, the spongy and the compact bone. The spongy bone trabeculae are highly adapted to mechanical forces revealing a trajectorial structure. The intertrabecular spaces are filled with bone marrow, the site of blood formation. The appearance of bones, muscles and soft tisssues is quite different in **CT-** and **MR-Images**. The CT-images relate well to radiographs in that areas of great absorption such as bones are white, and those with little absorption such as fat appear black. In contrast, the intensity of signals in MR-Images, obtained without X-rays but by magnetic forces, is different so that dense areas of bones appear black and soft tissues such as bone marrow and fat appear white (for comparison see above figures).

A highly innervated **periosteum** is an essential structure for bone nutrition, blood supply, growth and bone repair.



Coronal section through the proximal epiphysis of the adult tibia. Note the zone of dense bone at the site of the former epiphyseal plate (dotted line).



Structure of bones of the skeletal system (after Benninghoff). Note that the compact bone reveals a lamellar structure with Haversian lamellae and canals.



Knee joint. Anterior aspect, showing menisci and cruciate ligaments (cut). Quadriceps tendon cut and patella reflected distally.



Coronal section through the knee joint. Anterior aspect of the right joint in extension.



Sagittal section through the lower limb and the foot.



Shoulder joint (anterior view). The anterior part of the articular capsule has been removed.

1 Femur
2 Anterior cruciate ligament
3 Lateral meniscus
4 Patella
5 Posterior cruciate ligament
6 Posterior meniscofemoral ligament
7 Medial meniscus
8 Fibular collateral ligament
9 Fibula
10 Tibia
11 Tibial collateral ligament
12 Articular cartilage
13 Articular capsule
14 Tendon of long head of biceps brachii muscle
15 Head of humerus
16 Glenoid labrum
17 Articular cartilage of glenoid fossa
18 Scapula
19 Talus
20 Interosseous talocalcaneal ligament
21 Navicular bone
22 Medial cuneiform bone
23 First metatarsal bone
24 Proximal phalanx of the hallux (great toe)
25 Distal phalanx of the hallux
26 Sesamoid bone



General architecture of a synovial joint with 2 articulating bones and a synovial cavity (right side, anterior view).

Coronal section throught the knee joint.

Red line = Articular capsule with synovial membrane.
Dotted red line = extension of articular capsule (suprapatellar bursa).

1 Articulating bones: a) Femur, b) Tibia
2 Epiphysial line
3 **Articular cartilage**
4 Intraarticular ligaments (e.g. cruciate ligaments)
5 Fibrocartilaginous disk (e.g. meniscus)
6 Collateral ligaments
7 Articular capsule with synovial membrane
8 **Tibiofibular articulation** (example of gliding synovial joint)
9 Fibula

	Movement	Examples
A Fibrous joints		
1 Sutures	No movements	Sutures of the skull
2 Syndesmoses	No movements	Distal tibiofibular joint
3 Gomphosis	No movements	Roots of teeth in alveolar process
B Cartilaginous joints		
1 Synchondroses	No movements	Epiphyseal plates
2 Symphyses	Slight movement	Symphysis pubis intervertebral discs
C Synovial joints		
1 Gliding	Monaxial	Intercarpal joint Intertarsal joint Sacroiliacal joint
2 Hinge	Monaxial	Interphalangeal joint Humeroulnar joint Talocrural joint
3 Pivot	Monaxial	Atlantoaxial joint Radioulnar joint
4 Ellipsoidal	Biaxial	Radiocarpal joint
5 Saddle	Biaxial	Carpometacarpal joint of the thumb
6 Ball-and-socket	Multiaxial	Shoulder and hip joint



Main types of joints. Arrows: axes of movement.

Fibrous joints (synarthroses)
10 Serrate suture
11 Syndesmosis

Synovial joints (diarthroses)
12 Hinge joints (monaxial) ginglymus
  A Extension
  B Flexion
13 Saddle joint (biaxial)
14 Pivot joint (monaxial, rotation)
15 Ball-and-socket joint (multiaxial)

An articulation or joint is the functional connection between two or more bones. Joints can be divided into two categories depending upon whether the articulating surfaces of the bones are separated by a real cavity (joint cavity) so that they are movable against each other **(synovial joints)** or whether the bones are firmly connected by fibrous or cartilaginous tissue and practically immovable (**fibrous joints, cartilaginous joints,** symphysis, etc.). Synovial joints always possess a joint capsule (with a vascularized synovial membrane), articular cartilages, and a joint cavity. They are grouped according to the degree of movement they permit. A hinge joint (ginglymus) permits movement in only one plane about a single axis **(uniaxial** or **monaxial),** an ellipsoidal joint permits movements in two planes **(biaxial),** and ball-and-socket joints permit a range of movements around several axes **(multiaxial).** The following survey gives a few examples of these types of articulation.

1. Fibrous joints

A Sutures

a) Serrate or dentate suture



Sagittal suture

Separated

b) Squamous suture (arrows)



Squamous suture

1 Parietal bone
2 Sphenoid bone
3 Squama of temporal bone

c) Plane suture (arrow)



Nasal bones

B Peg suture
(Gomphosis)



Teeth and alveolar process

2. Cartilaginous joints

a) Symphysis
(fibrocartilage)



Pubic symphysis

b) Synchondrosis
(hyaline cartilage)



Sternum a = manubrium; b = body

* Articular disc
(sternoclavicular joint)

3. Osseous joints
(synostosis)



Transverse ridge (arrows) Sacrum

1. Ball-and-socket joint



Shoulder joint



Hip joint *Acetabular labrum

2. Ellipsoid joint

OFFICIAL
Rugby Football
OFFICIAL
SIZE-WEIGHT



Radiocarpal joint

3. Hinge joint





Interphalangeal joint



Elbow joint (humeroulnar joint)

4. Pivot joint



Radioulnar joint; left: head of radius, right: radial notch of ulna

Supinated Pronated

5. Hinge joint

(but a gradually
tilting axis produces
a slight spiral motion)



Ankle joint: 1 = tibia; 2 = fibula; 3 = talus

6. Saddle joint



Carpometacarpal joint of the thumb

7. Plane joint



I = navicular; **II** = intermediate cuneiform; **III** = lateral cuneiform



Fusiform
(palmaris longus muscle)

Bicipital
(biceps brachii muscle)

Tricipital
(triceps surae muscle)

Quadricipital
(quadriceps femoris muscle)



Digastric
(omohyoid muscle)

Multiventral
(rectus abdominis muscle)

Multicaudal
(flexor prof. muscle)

Serrated
(serratus anterior muscle)



Bipennate
(tibialis anterior muscle)

Unipennate
(semimembranous muscle)

Semitendinous
(semitendinous muscle)

Broad, flat muscle
(latissimus dorsi muscle)

Ring-like
(external anal sphincter muscle)

1 Long head
2 Short head
3 Gastrocnemius muscle
(medial head, lateral head)
4 Soleus muscle
5 Achilles tendon
6 Vastus intermedius muscle
7 Vastus lateralis muscle
8 Patella
9 Rectus femoris muscle
10 Vastus medialis muscle
11 Intermediate tendon
12 Tendinous intersection
13 Aponeurosis
14 Tendinous intersection



Left half of the pelvis (posterior aspect).
Obturator internus muscle as an example of a muscle, the tendon of which does not act in the direction of the main muscle fibers. Its fibers originate at the internal aspect of the obturator foramen, turn around the posterior rim of the ischium and insert at the greater trochanter of the femur. The ischium thereby serves as a pulley.

1. Ilium
2. Greater trochanter
3. Coccyx
4. Obturator internus muscle
5. Pubis
6. Femur



Superior oblique muscle of the eyeball, right eye (superior aspect). The tendon of this muscle bends over the trochlea changing its direction so that it becomes attached to the posterior lateral quadrant of the eyeball.

1. Trochlea
2. Medial rectus muscle
3. Superior oblique muscle
4. Common annular tendon
5. Eyeball
6. Superior rectus muscle
7. Lateral rectus muscle
8. Superior rectus muscle (tendon)
9. Levator palpebrae superioris muscle (divided)



1. Digital synovial sheaths of the tendons of flexor digitorum superficialis and profundus muscles
2. Digital synovial sheaths of the tendon of long flexor pollicis longus muscle
3. Common flexor synovial sheaths of flexor digitorum superficialis and profundus muscles
4. Flexor retinaculum

The synovial sheaths of the tendons on the palmar aspect of the left wrist (colored fluid has been injected).



1. Mesotendon
2. Blood vessels
3. Synovial sheath
4. Tendon
5. Synovial bursa
6. Bone (tuberosity)

Structure of a tendon sheath. The synovial membrane which also forms the mesotendon is indicated in red. (Schematic drawing.)



1 Falx cerebri
2 Cerebral hemispheres
3 Tentorium cerebelli
4 Cerebellum
5 Medulla oblongata
6 Spinal cord, cervical enlargement
7 Spinal ganglia
8 Spinal cord, lumbar enlargement
9 Conus medullaris
10 Cauda equina
11 Cervical plexus (formed from ventral rami of C_1–C_4)
12 Brachial plexus (formed from ventral rami of C_5–T_1)
13 Lumbosacral plexus (formed from ventral rami of L_1–S_4)
14 Sympathetic trunk

Brain, the **spinal cord** and the **spinal nerves** in the fetus (posterior aspect).



Schematic drawing to illustrate the three main parts of the nervous system in general.

The **nervous system** can be divided into three, functionally distinct parts: 1. the cranial part which comprises the great sensory organs and the brain, 2. the spinal cord which shows a segmental structure and serves predominantly as a reflex-organ, and 3. the autonomic nervous system which controls the unvoluntary functions (subconscious control) of organs and tissues. The autonomic part of the nervous system forms many delicate plexus within the organs. At certain places these plexus contain aggregations of nerve cells (prevertebral and intramural ganglia). The spinal nerves leave the spinal cord at regular intervals, forming the 8 cervical, 12 thoracic, 5 lumbar, 5 sacral and a varying number of coccygeal segments. The ventral rami of the first four cervical spinal nerves (C_1–C_4) form the cervical plexus (for innervation of the anterior neck), the ventral rami of the lower cervical spinal nerves (C_5–T_1) form the brachial plexus which innervates the upper leg, and the ventral rami of the lumbar and sacral spinal nerves form the lumbosacral plexus (L_1–S_4) which innervates the pelvic and genital organs and the lower extremity.



Diagram illustrating the localization of the **three functional portions** of the **nervous system** (brain, spinal cord and autonomic nervous system). Yellow = sympathetic system; red = parasympathetic system.

1 Cerebrum
2 Cerebellum
3 Spinal cord
4 Sympathetic trunk and ganglion
5 Plexus and ganglia of the autonomic nervous system
6 Cranial autonomic system
7 Cranial nerves (n. III and n. VII)
8 Superior cervical ganglion
9 Vagus nerve (n. X)
10 Sacral autonomic system



Posterior part of the thorax. Cross-section at the level of the 5th thoracic segment. Spinal nerves and their connections to the sympathetic trunk.



Organization of the spinal cord in structurally equal segments which form the paired spinal nerves. A = connections to the brain; B = connections to the autonomic nervous system; C = connections to the trunk and extremities (intercostal nerves and plexus). (Schematic drawing.)

1 Spinal cord
2 **Dorsal root**
3 **Ventral root**
4 Intercostal nerves
5 Sympathetic trunk
6 Ganglia of the sympathetic trunk
7 Rami communicantes
8 Intercostal artery and vein
9 Subcostalis muscle
10 Lesser splanchnic nerve
11 Greater splanchnic nerve
12 Inferior vena cava
13 Dorsal ramus of spinal nerve
14 **Spinal (dorsal root) ganglion**
15 Body of the vertebra
16 Aorta
17 Azygos vein
18 Diaphragm
19 Left kidney
20 **Spinal nerve**
21 Gray matter of the spinal cord
22 White matter of the spinal cord



Superficial nerves and vessels of the lower leg, illustrating the structural differences between veins and nerves.

1 Crural fascia (fascia cruris)
2 Cutaneous nerves
3 Superficial cutaneous veins
4 Perforating vein



Organization of the circulatory system. Arrows: direction of the blood flow.

Vessel wall in red = Arteries
Vessel wall in blue = Veins
Yellow = Lymphatic vessels

A Systemic circulation
B Hepatic portal circulation
C Pulmonary circulation



Superficial nerves and vessels. Temporal region. Note the differences between arteries, veins and nerves.

1 Pulmonary vein
2 Superior vena cava
3 Thoracic duct
4 Inferior vena cava
5 Hepatic vein
6 Liver
7 Lymph nodes and lymphatic vessels
8 Lung
9 Pulmonary artery
10 Aorta
11 Heart
12 Small intestine with capillary network
13 Portal vein
14 Mesenteric artery
15 Superficial temporal artery
16 Superficial temporal vein
17 Auriculotemporal nerve
18 Perforating veins for subcutaneous fatty tissue
19 Small artery
20 Small nerves (branches of facial nerve)



Major vessels of the trunk. The position of the heart is indicated by the dotted line.



Major arteries of the human body. (Schematic drawing.)

1 Internal jugular vein
2 **Common carotid artery**
3 Vertebral artery
4 **Ascending aorta**
5 **Descending aorta**
6 **Inferior vena cava**
7 Celiac trunk
8 Superior mesenteric artery
9 Renal vein
10 **Common iliac artery**
11 Larynx
12 Trachea
13 Left subclavian artery
14 Left axillary vein
15 **Pulmonary veins**
16 Diaphragm
17 Suprarenal gland
18 Kidney
19 Ureter
20 Inferior mesenteric artery
21 **Femoral vein**
22 Facial artery
23 Axillary artery
24 Brachial artery
25 Radial artery
26 Ulnar artery
27 Deep palmar arch
28 Superficial palmar arch
29 Common palmar digital arteries
30 Profunda femoris artery
31 **Femoral artery**
32 Popliteal artery
33 Anterior tibial artery
34 Posterior tibial artery
35 Plantar arch



Major lymph vessels of the trunk.



Deep cervical nodes, adjacent to the internal jugular vein.



Lymphatic system. Course of the main lymphatic vessels and lymph nodes in the body. Dotted line = border between lymphatic vessels draining towards the right venous angle and towards the left.

1 Submandibular nodes
2 Deep cervical nodes
3 Right jugular trunk
4 Subclavian trunk
5 Right bronchomediastinal trunk
6 Thoracic duct
7 **Cisterna chyli**
8 **Intestinal trunk**
9 Right **lumbar trunk**
10 Internal iliac nodes
11 **Inguinal nodes**
12 **Axillary nodes**
13 Descending trunk
14 Descending aorta
15 Internal jugular vein
16 Subclavian vein
17 Left brachiocephalic vein
18 Mandible
19 Larynx
20 Internal jugular vein
21 **Deep cervical nodes**
22 Cervical nerve plexus
23 Superficial layer of deep fascia
24 Occipital nodes
25 Parotid nodes
26 Popliteal nodes

Lymphatic vessels originate as blind-ending tubes in the tissue spaces (lymph capillaries) and unite to form larger vessels (lymphatics). These resemble veins but have a much thinner wall, more valves and are interrupted by lymph nodes at various intervals. Large groups of lymph nodes are located in the inguinal and axillary regions, deep to the mandible and sternocleidomastoid muscle and within the root of the mesentery of the intestine.



1	Corpus callosum
2	**Hypothalamus**
3	Frontal sinus
4	Cribriform plate
5	Ethmoidal air cells
6	Middle nasal concha
7	Inferior nasal concha
8	Hard palate
9	**Tongue**
10	Epiglottis
11	Mandible
12	Mylohyoid muscle
13	Tentorium of cerebellum
14	Calcarine fissure
15	Cerebral aqueduct
16	**Pituitary gland**
17	Fourth ventricle
18	**Sphenoidal sinus**
19	Medulla oblongata
20	Nasopharynx
21	Uvula
22	Dens of axis
23	Constrictor muscle of pharynx
24	Oral part of pharynx
25	**Cerebrum** (right hemisphere)
26	Calvaria
27	**Cerebellum**

Sagittal section through head and neck (MR-Scan. 23-year-old female, courtesy of PD Dr. A. Heuck, Munich).



Sagittal section through the head
(schematic drawing). The red line represents the border between the neurocranium and viscerocranium forming the clivus angle. The neural cavity contains the brain; the viscerocranium comprises the orbit, the nasal cavity and the oral cavity arranged one beneath the other.



General architecture of the skull (lateral aspect). The different bones are indicated in color (numbers cf. table).

1 Coronal suture
2 **Frontal bone**
3 **Sphenoid bone**
4 Sphenofrontal suture
5 **Ethmoid bone**
6 **Nasal bone**
7 Nasomaxillary suture
8 **Lacrimal bone**
9 Lacrimomaxillary suture
10 Lacrimoethmoid suture
11 **Zygomatic bone**
12 Anterior nasal spine
13 **Maxilla**
14 **Mandible**
15 Mental foramen
16 Mental protuberance
17 Superior temporal line
18 Inferior temporal line
19 **Parietal bone**
20 **Temporal bone**
21 Squamous suture
22 Lambdoid suture
23 Temporal fossa
24 Parietomastoid suture
25 **Occipital bone**
26 Zygomatic arch
27 Occipitomastoid suture
28 External acoustic meatus
29 Mastoid process
30 Tympanic portion of temporal bone
31 Condylar process of mandible
32 Coronoid process of mandible



Lateral aspect of the disarticulated skull (palatine bone, lacrimal bone, ethmoid bone and vomer are not depicted).

2	Frontal bone (orange)	Cranial bones
19	Parietal bone (light green)	
3	Greater wing of sphenoid bone (red)	
25	Squama of occipital bone (blue)	
20	Squama of temporal bone (brown)	
5	Ethmoid bone (dark green)	Base of skull
3	Sphenoid bone (red)	
	Temporal bone excluding squama (brown)	
30	Tympanic portion of temporal bone (dark brown)	
	Occipital bone excluding squama (blue)	
6	Nasal bone (white)	Facial bones
8	Lacrimal bone (yellow)	
	Inferior nasal concha	
	Vomer	
11	Zygomatic bone (light yellow)	
	Palatine bone	
13	Maxilla (violet)	
14	Mandible (white)	
	Malleus Incus Stapes } within petrous portion of temporal bone	Auditory ossicles
	Hyoid	



Lateral aspect of the skull.

1 **Frontal bone**
2 Glabella
3 Supraorbital margin
4 **Parietal bone**
5 **Temporal bone** (squamous part)
6 Zygomatic process (articular tubercle)
7 Mastoid process
8 Tympanic part (tympanic plate) and external acoustic meatus
9 **Occipital bone** (squamous part)
10 External occipital protuberance
11 Occipital condyle
12 **Sphenoid bone** (greater wing)
13 Infratemporal crest of sphenoid
14 Pterygoid process (lateral pterygoid plate)
15 **Nasal bone**
16 **Ethmoid bone** (orbital part)
17 **Lacrimal bone**
18 **Zygomatic bone**
19 **Maxilla** (body)
20 Alveolar process and teeth
21 Frontal process
22 Anterior nasal spine
23 **Mandible** (body)
24 Coronoid process
25 Condylar process
26 Mental foramen
27 Mental protuberance
28 Angle of the mandible

Sutures

29 Coronal suture
30 Lambdoid suture
31 Squamous suture
32 Nasomaxillary suture
33 Frontosphenoid suture
34 Sphenosquamosal suture
35 Occipitomastoid suture



1 **Frontal bone**
2 Glabella
3 Supraorbital margin
4 Supraorbital notch
5 Trochlear spine
6 **Parietal bone**
7 **Temporal bone**
8 **Nasal bone**

Orbit
9 Lacrimal bone
10 Posterior lacrimal crest
11 Ethmoid bone

Sphenoid bone
12 Greater wing of sphenoid bone
13 Lesser wing of sphenoid bone
14 Superior orbital fissure
15 Inferior orbital fissure
16 **Zygomatic bone**

Maxilla
17 Frontal process
18 Infraorbital foramen
19 Zygomatic process
20 Body of maxilla
21 Alveolar process with teeth

Nasal cavity
22 Anterior nasal aperture
23 Middle nasal concha
24 Inferior nasal concha
25 Nasal septum, vomer

Mandible
26 Body of mandible
27 Ramus of mandible
28 Mental foramen
29 Alveolar part with teeth
30 Base of mandible
31 Mental protuberance

Sutures
32 Frontal suture
33 Coronal suture
34 Frontonasal suture
35 Internasal suture
36 Nasomaxillary suture
37 Zygomaticomaxillary suture
38 Intermaxillary suture

Anterior aspect of the skull.

The skull comprises a mosaic of numerous complicated bones which form the cranial cavity protecting the brain **(neurocranium)** and several cavities such as nasal and oral cavities in the facial region. The neurocranium consists of large bony plates which develop directly from the surrounding sheets of connective tissue **(desmocranium).** The bones of the skull base are formed out of cartilaginous tissue **(chondrocranium)** which ossifies secondarily. The **visceral skeleton** which, in fish, gives rise to the gills, has in higher vertebrates been transformed into the bones of the masticatory and auditory apparatus (maxilla, mandible, auditory ossicles and hyoid bone).



1 **Frontal bone**
2 Frontonasal suture
3 Frontomaxillary suture
4 Supraorbital margin
5 Internasal suture
6 Sphenofrontal suture
7 Optic canal in lesser wing of sphenoid bone
8 Superior orbital fissure
9 **Lacrimal bone**
10 **Sphenoid bone** (greater wing)
11 Inferior orbital fissure
12 Nasomaxillary suture
13 Infraorbital foramen
14 **Maxilla**
15 **Vomer**
16 Body of mandible
17 **Parietal bone**
18 **Temporal bone**
19 Sphenozygomatic suture
20 **Ethmoid bone**
21 **Zygomatic bone**
22 **Nasal bone**
23 Zygomaticomaxillary suture
24 Middle nasal concha
25 Inferior nasal concha
26 Anterior nasal aperture
27 Mental foramen
28 Ramus of mandible
29 Base of mandible
30 Mental protuberance

Bones
Frontal bone (brown)
Parietal bone (light green)
Temporal bone (dark brown)
Sphenoidal bone (red)
Zygomatic bone (yellow)
Ethmoid bone (dark green)
Lacrimal bone (yellow)
Vomer (orange)
Maxilla (violet)
Nasal bone (white)
Mandible (white)

Anterior aspect of the skull (individual bones indicated by color).

The following series of figures are arranged so that the mosaic-like pattern of the skull becomes understandable. It starts with the bones of the **skull base** (sphenoid and occipital) to which the other bones are added step by step. The facial skeleton is built up by the ethmoid bone to which the palatine bone and maxilla are attached laterally; the small nasal and lacrimal bones fill the remaining spaces. Cartilages remain only in the external part of the nose.


1
2
3
4
5
6
7
8
27
28
29
30
31
9
10
11
14
12
32
34
35
36
37

Sphenoid and occipital bone (from above).


8
5
25
11
26
16
22
38
39
40
41
42
43

Sphenoid and occipital bone in connection with the atlas and axis (1st and 2nd cervical vertebrae) (left lateral view).



Sphenoid bone (anterior aspect).



Sphenoid bone (posterior aspect).



Occipital bone (from below).

Sphenoid bone

1 **Greater wing**
2 **Lesser wing**
3 Cerebral or superior surface of greater wing
4 **Foramen rotundum**
5 Anterior clinoid process
6 Foramen ovale
7 Foramen spinosum
8 Dorsum sellae
9 Optic canal
10 Chiasmatic groove (sulcus chiasmatis)
11 **Hypophysial fossa (sella turcica)**
12 Lingula
13 Opening of sphenoidal sinus
14 Posterior clinoid process
15 **Pterygoid canal**
16 Lateral pterygoid plate of **pterygoid process**
17 Pterygoid notch
18 Pterygoid hamulus
19 Orbital surface of greater wing
20 Sphenoid crest
21 Sphenoid rostrum
22 Medial pterygoid plate
23 Superior orbital fissure
24 Spine of sphenoid
25 Temporal surface of greater wing
26 Infratemporal crest

Occipital bone

27 **Clivus** with basilar part of occipital bone
28 **Hypoglossal canal**
29 Fossa for cerebellar hemisphere
30 Internal occipital protuberance
31 Fossa for cerebral hemisphere
32 Jugular tubercle
33 Condylar canal
34 Jugular process
35 **Foramen magnum**
36 Groove for transverse sinus
37 Groove for superior sagittal sinus
38 **Squamous part** of the occipital bone
39 External occipital protuberance
40 Superior nuchal line
41 Inferior nuchal line
42 Condylar fossa
43 **Condyle**
44 Pharyngeal tubercle
45 External occipital crest



Sphenoid, occipital and left temporal bone (from above). Internal aspect of the base of the skull. The left temporal bone has been added to the preceeding figure.

Sphenoid bone
1 **Greater wing**
2 **Lesser wing**
3 Foramen rotundum
4 **Foramen ovale**
5 Foramen spinosum
6 Foramen lacerum
7 Anterior clinoid process
8 Hypophysial fossa (**sella turcica**)
9 Lingula
10 Dorsum sellae and posterior clinoid process
11 **Optic canal**
12 Sphenoid rostrum
13 Medial pterygoid plate
14 Lateral pterygoid plate
15 Pterygoid hamulus
16 Infratemporal crest
17 Body of the sphenoid

Temporal bone
18 **Squamous part**
19 **Carotid canal**
20 Hiatus of facial canal (for the greater petrosal nerve)
21 Arcuate eminence
22 Groove for the sigmoid sinus
23 Mastoid foramen
24 **Internal acoustic meatus**
25 Zygomatic process
26 Mandibular fossa
27 Petrotympanic fissure
28 Canalis musculotubarius (bony part of auditory tube)
29 **External acoustic meatus**
30 Styloid process (remnant only)
31 Stylomastoid foramen
32 Mastoid canaliculus
33 Jugular fossa
34 **Mastoid process**
35 Mastoid notch



Left temporal bone (medial aspect).



Left temporal bone (from above).


12
1
14
13
17
65
6
64
58
62
50
51
61
16
15
25
4
5
45
28
26
27
19
29
30
31
32
34
35
33
59
63
60

Sphenoid, occipital and left temporal bone.
Base of the skull (external aspect).

36 Groove for middle meningeal vessels
37 Parietal margin
38 Sphenoid margin
39 Occipital margin
40 Cochlear canaliculus
41 Aqueduct of the vestibule
42 Apex of the petrous part
43 **Tympanic part**
44 Trigeminal impression
45 **Articular tubercle**
46 Parietal notch
47 Groove for the superior petrosal sinus

Occipital bone

48 **Clivus**
49 Jugular tubercle
50 Condylar canal
51 **Foramen magnum**
52 Lower part of squamous occipital bone (cerebellar fossa)
53 Internal occipital protuberance
54 Groove for the transverse sinus
55 Groove for the superior sagittal sinus
56 Internal occipital crest
57 Upper part of squamous occipital bone (cerebral fossa)
58 **Condyle**
59 Nuchal plane
60 Superior nuchal line
61 **External occipital protuberance**
62 **Jugular foramen**
63 Inferior nuchal line
64 Pharyngeal tubercle
65 **Sphenooccipital synchondrosis**


37
18
38
25
45
26
27
42
46
39
29
43
34

Left temporal bone (lateral aspect).



Part of a disarticulated skull (right lateral aspect). The **frontal bone** and the maxilla are connected with the temporal bone by the zygomatic bone (orange). Sphenoid bone (green), palatine bone (red), lacrimal bone (yellow).



Frontal bone (inferior aspect). The ethmoidal foveolae cover the ethmoidal cavities of the ethmoid bone.



Frontal bone (posterior aspect).

Frontal bone

1 Nasal margin
2 Trochlear fossa
3 Fossa for lacrimal gland
4 Anterior ethmoidal foramen
5 Posterior ethmoidal foramen
6 Nasal spine
7 Supraorbital notch
8 Supraorbital margin
9 **Orbital plate**
10 Roofs of the ethmoidal air cells
11 Ethmoidal notch
12 Parietal margin
13 Groove for superior sagittal sinus
14 **Squamous part** of frontal bone
15 Frontal crest
16 Foramen cecum
17 Nasal spine
18 **Zygomatic process** of frontal bone
19 Juga cerebralia

20 **Maxilla**
21 Frontal process of maxilla
22 **Lacrimal bone** (yellow)
23 **Zygomatic bone** (orange)
24 Zygomaticofacial foramen

Temporal bone

25 Squamous part of temporal bone
26 External acoustic meatus
27 **Mastoid process**
28 **Styloid process**
29 **Mandibular fossa**
30 Articular tubercle
31 Zygomatic process

Occipital bone

32 Squamous part of occipital bone



Calvaria (superior aspect).



Calvaria (posterior aspect).



Left parietal bone (external aspect).



Left parietal bone (internal aspect).

1 **Frontal bone**
2 Coronal suture
3 Sagittal suture
4 **Parietal bone**
5 Superior temporal line
6 Parietal foramen
7 Parietal tuber or eminence
8 Sagittal margin
9 Occipital margin
10 Frontal margin
11 Squamous margin
12 Sphenoidal angle
13 Groove for middle meningeal artery
14 Lambdoid suture
15 **Occipital bone**
16 External occipital protuberance
17 Inferior nuchal line
18 Occipitomastoid suture
19 **Temporal bone**
20 Mastoid process
21 Mastoid notch



Base of the skull, calvaria removed (internal aspect).

1 Frontal crest
2 Foramen cecum
3 **Crista galli**
4 **Cribriform plate** of ethmoid bone
5 Lesser wing of sphenoid bone
6 Superior orbital fissure
7 **Foramen rotundum**
8 **Carotid sulcus**
9 Middle cranial fossa
10 **Foramen ovale**
11 Foramen spinosum
12 **Clivus**
13 Groove for superior petrosal sinus
14 **Jugular foramen**
15 Groove for sigmoid sinus
16 Internal occipital crest
17 Groove for transverse sinus
18 Internal occipital protuberance
19 Marking of brain convolutions
20 Anterior cranial fossa
21 Chiasmatic sulcus
22 Anterior clinoid process
23 **Optic canal**
24 **Sella turcica** (hypophysial fossa)
25 Posterior clinoid process
26 Dorsum sellae
27 **Foramen lacerum**
28 Groove for greater petrosal nerve
29 Internal acoustic meatus
30 **Hypoglossal canal**
31 **Foramen magnum**
32 Posterior cranial fossa
33 Diploe



Base of the skull (internal aspect, oblique lateral view from left side).



Base of the skull (internal aspect, superior view).
Individual bones indicated by color.

Canals, fissures and foramina of the base of the skull

1 Superior orbital fissure
2 Foramen rotundum
3 Optic canal
4 Foramen ovale
5 Foramen spinosum
6 Internal acoustic meatus
7 Jugular foramen
8 Foramen magnum

Bones

9 Frontal bone (orange)
10 Ethmoid bone (dark green)
11 Sphenoid bone (red)
12 Temporal bone (brown)
13 Parietal bone (yellow-green)
14 Occipital bone (blue)

Details of bones

15 Crista galli
16 Cribriform plate
17 Marking of brain convolutions (frontal bone)
18 Lesser wing of sphenoid bone
19 Foramen lacerum
20 Hypophysial fossa (sella turcica)
21 Anterior clinoid process
22 Depression for trigeminal ganglion
23 Petrous part of temporal bone
24 Groove for sigmoid sinus
25 Dorsum sellae (posterior clinoid process)
26 Greater wing of sphenoid bone, groove for middle meningeal artery
27 Hypoglossal canal



Median section through the skull, right half (internal aspect).

1	**Hypophysial fossa (sella turcica)**
2	Anterior clinoid process
3	**Frontal bone**
4	**Ethmoidal air cells**
5	**Sphenoidal sinus**
6	Superior concha
7	Middle concha
8	**Maxillary hiatus**
9	**Inferior concha**
10	Inferior meatus
11	Anterior nasal spine and maxilla
12	Mental spine or genial tubercle
13	Groove for middle meningeal artery
14	Dorsum sellae
15	Internal acoustic meatus
16	Groove for sigmoid sinus
17	**Hypoglossal canal**
18	**Occipital condyle**
19	Condylar process
20	Lateral pterygoid plate } of **pterygoid process**
21	Medial pterygoid plate } of **pterygoid process**
22	Lingula of mandible
23	**Mandibular foramen**
24	Mylohyoid groove
25	Mylohyoid line
26	Submandibular fovea



Facial part of the skull (viscerocranium), divided in two halves (lateral and medial aspect). Right inferior concha has been removed to show the maxillary hiatus. Left maxillary sinus opened.

1 Frontal sinus
2 **Frontal bone**
3 Crista galli
4 **Nasal bone**
5 Sphenoidal sinus
6 **Superior concha** } of **ethmoid**
7 **Middle concha** } **bone**
8 Frontal process
of maxilla
9 Ethmoidal bulla
10 **Uncinate process**
11 Maxillary hiatus
12 **Palatine bone**
13 Greater palatine foramen
14 **Alveolar process of maxilla**
15 Central incisor
16 Zygomatic bone
17 Ethmoid bone
18 **Lacrimal bone**
19 Pterygopalatine fossa
20 **Maxillary sinus**
21 Lateral pterygoid plate
22 Medial pterygoid plate
23 Third molar tooth
24 Pterygoid hamulus
25 Two premolar teeth



Median section through the skull. The nasal septum has been removed. Bones indicated by colors.

Bones (indicated by colors)
1 Frontal bone (yellow)
2 Nasal bone (white)
3 Ethmoid bone (dark green)
4 Lacrimal bone (yellow)
5 Inferior nasal concha (pink)
6 Palatine bone (white)
7 Maxilla (violet)
8 Mandible (white)
9 Parietal bone (light green)
10 Temporal bone (brown)
11 Sphenoid bone (red)
12 Petrous part of temporal
bone (brown)
13 Occipital bone (blue)
14 Ala of vomer (light brown)

Because of the upright posture which the man developed in the course of evolution, the cranial cavity greatly increased in size whereas the facial skeleton decreased. As a result, the base of the skull developed an angulation of about 120° between the clivus and the cribriform plate. The hypophysial fossa containing the pituitary gland lies at the angle formed between these two planes.



Part of the disarticulated base of the skull.
Ethmoid, sphenoid and occipital bones (from above).
Green = sphenoid bone; yellow = ethmoid bone.

Ethmoid bone

1 Crista galli
2 Cribriform plate
3 Ethmoidal air cells
4 Middle concha
5 Perpendicular plate (part of nasal septum)
6 Orbital plate

Sphenoid bone

7 Lesser wing
8 Greater wing
9 Anterior clinoid process
10 Posterior clinoid process
11 Foramen ovale
12 Foramen spinosum
13 Lingula of the sphenoid
14 Clivus
15 Optic canal
16 Tuberculum sellae
17 Foramen rotundum (right side)
18 Hypophysial fossa (sella turcica)
19 Dorsum sellae
20 Carotid sulcus
21 Sphenooccipital synchondrosis
22 Lateral pterygoid plate
23 Greater wing of sphenoid bone (orbital surface)
24 Greater wing of sphenoid bone (maxillary surface)
25 Foramen rotundum (left side)
26 Superior orbital fissure
27 Infratemporal crest of the greater wing



Ethmoid bone (lateral aspect), posterior portion to the right.



Ethmoid bone (anterior aspect).



Disarticulated base of the skull (anterior aspect).
Green = sphenoid bone; yellow = ethmoid bone; red = palatine bone.

Occipital bone
28 Jugular tubercle
29 Jugular process
30 Mastoid margin
31 Posterior cranial fossa
32 Lambdoid margin
33 Intrajugular process
34 Condylar canal
35 Lateral part of occipital bone
36 Hypoglossal canal
37 Foramen magnum
38 Internal occipital crest
39 Squamous part of occipital bone
40 Internal occipital protuberance

Maxilla
41 Orbital surface
42 Infraorbital groove
43 Maxillary tuberosity with foramina
44 Frontal process
45 Nasolacrimal groove
46 Infraorbital margin
47 Anterior nasal spine
48 Zygomatic process
49 Alveolar process

Palatine bone
50 Orbital process
51 Sphenopalatine notch
52 Sphenoidal process
53 Perpendicular plate
54 Horizontal plate
55 Pyramidal process



Right maxilla, ethmoid and palatine bone (lateral aspect).



Ethmoid bone (oblique anterior aspect).
(Schematic drawing.)



Part of a disarticulated skull base, similar to the foregoing figures, but with palatine bone. Green = sphenoid bone; yellow = ethmoid bone; red = palatine bone.

Ethmoid bone

1 Crista galli
2 Orbital plate
3 Middle concha

Palatine bone

4 Horizontal plate of palatine bone
5 Greater palatine canal
6 Pyramidal process
7 Maxillary process
8 Orbital process
9 Sphenopalatine notch
10 Perpendicular plate of palatine bone
11 Conchal crest
12 Nasal crest
13 Sphenoidal process

Sphenoid bone

14 Greater wing
15 Superior orbital fissure
16 Greater wing (orbital surface)
17 Lesser wing

Occipital bone

18 Squamous part of occipital bone

Maxilla

19 Maxillary tuberosity
20 Frontal process
21 Orbital surface
22 Infraorbital margin
23 Infraorbital groove
24 Zygomatic process
25 Alveolar process



Left palatine bone (medial aspect, posterior aspect to the left).



Left palatine bone (anterior aspect).



Right maxilla and right palatine bone (lateral aspect).



Occipital bone
1 Squamous part

Sphenoid bone
2 Dorsum sellae
3 Superior orbital fissure
4 Lesser wing
5 Greater wing (orbital surface)
6 Lateral pterygoid plate
7 Medial pterygoid plate

Ethmoid bone
8 Crista galli
9 Ethmoidal air cells
10 Perpendicular plate
11 Orbital plate

Palatine bone
12 Horizontal plate (nasal crest)

Maxilla
13 Frontal process
14 Inferior orbital fissure
15 Infraorbital groove
16 Orbital surface
17 Infraorbital foramen
18 Zygomatic process
19 Anterior lacrimal crest
20 Canine fossa
21 Alveolar process with teeth
22 Anterior nasal spine
23 Juga alveolaria (elevations formed by roots of teeth)
24 Lacrimal groove
25 Maxillary tuberosity with alveolar foramina
26 Palatine process of maxilla

Part of a disarticulated skull.
The left **maxilla** is added to the preceding specimen.



Left maxilla (lateral aspect). Probe = infraorbital canal.



Left maxilla (posterior aspect).



Part of a disarticulated base of skull. The mosaic of the facial bones [sphenoid bone (green), ethmoid bone (yellow), and palatine bone (red)] is seen from the anterior-lateral aspect.



Left maxilla and palatine bone (medial aspect).

Occipital bone

1 Groove for superior sagittal sinus
2 Internal occipital protuberance
3 Groove for transverse sinus
4 Internal occipital crest

Sphenoid bone

5 Greater wing (temporal surface)
6 Lateral pterygoid plate
7 Dorsum sellae
8 Lesser wing
9 Superior orbital fissure
10 Greater wing (orbital surface)

Ethmoid bone

11 Ethmoidal air cells
12 Crista galli
13 Orbital plate

Maxilla

14 Frontal process
15 Inferior orbital fissure
16 Alveolar process with teeth
17 Palatine process
18 Anterior nasal spine
19 Infraorbital groove
20 Zygomatic process
21 Location of infraorbital foramen
22 Middle nasal meatus
23 Inferior nasal meatus
24 Maxillary hiatus
(leading to maxillary sinus)
25 Third molar
26 Lacrimal groove
27 Conchal crest
28 Body of maxilla (nasal surface)
29 Nasal crest
30 Incisive canal

Palatine bone

31 Orbital process
32 Sphenopalatine notch
33 Sphenoidal process
34 Perpendicular plate
35 Conchal crest
36 Horizontal plate
37 Pyramidal process

Frontal bone

38 Squamous part
39 Supraorbital foramen
40 Frontal notch
41 Frontal spine

Inferior nasal concha

42 Inferior nasal concha
with maxillary process


1
7
5
12
13
14
26
27
29
30
17
6
34
25
36
24
28

Part of a disarticulated base of skull (medial aspect). Green = sphenoid bone; yellow = ethmoid bone; red = palatine bone; natural colored = left maxilla.


1
2
4
10
6
36
17
38
39
40
41
11
14
22
42
23

Part of a disarticulated base of skull. The same specimen as shown above but with frontal bone (oblique-lateral aspect).



Part of a disarticulated skull, showing the connection of the palatine bone (red) and the maxilla with ethmoid bone (yellow) and sphenoid bone (light green) (anterior aspect).

Frontal bone

1 Squamous part
2 Inferior temporal line
3 Temporal surface
4 Supraorbital foramen
5 Zygomatic process

Occipital bone

6 Squamous part

Sphenoid bone

7 Greater wing (temporal surface)
8 Optic canal within the lesser wing
9 Lateral pterygoid plate

Palatine bone

10 Orbital process
11 Perpendicular plate
12 Conchal crest
13 Nasal crest
14 Horizontal plate

Ethmoid bone

15 Orbital plate
16 Ethmoidal air cell
17 Middle concha
18 Perpendicular plate (part of bony nasal septum)

Maxilla

19 Infraorbital groove
20 Infraorbital foramen
21 Zygomatic process
22 Alveolar process with teeth
23 Palatine process

Left inferior nasal concha

24 Anterior part of inferior concha



Anterior view of a disarticulated skull, showing the connection of the maxilla with the frontal and zygomatic bones. Yellow = ethmoid bone; red = palatine bone; green = sphenoid bone.

Frontal bone

1 Squamous part
2 Frontal notch
3 Supraorbital foramen
4 Supraorbital margin
5 Zygomatic process
6 Frontal spine

Sphenoid bone

7 Greater wing (orbital surface)
8 Foramen rotundum
9 Pterygoid or Vidian canal
10 Lateral pterygoid plate
11 Medial pterygoid plate

Ethmoid bone

12 Orbital plate
13 Ethmoidal air cells
14 Middle concha

Palatine bone

15 Horizontal plate
15a Nasal crest
16 Pyramidal process
17 Lesser palatine foramen
18 Greater palatine foramen

Zygomatic bone

19 Frontal process
20 Orbital surface

Maxilla

21 Canine fossa
22 Frontal process
23 Palatine process
24 Zygomatic process
25 Alveolar process and teeth
26 Juga alveolaria
27 Infraorbital foramen
28 Infraorbital groove
29 Anterior nasal aperture
30 Anterior nasal spine

Incisive bone

31 Central incisor and incisive bone or premaxilla
32 Incisive fossa

Vomer

33 Ala of the vomer

Sutures and choanae

34 Median palatine suture
35 Transverse palatine suture
36 Choanae



Bony palate and teeth of the maxillae (from below).



Anterior view of both maxillae, forming the anterior bony aperture of the nose.



Paramedian section through the skull, right side (lateral aspect). Frontal and maxillary sinus are opened.



Illustration of canals and foramina connected with the right orbit and pterygopalatine fossa (compare the above figure). The greater wing of sphenoid bone (green) is shown as being transparent. Brown = temporal bone; yellow = ethmoid bone; red = laerimal bone; light red = inferior nasal concha; violet = maxilla; orange = palatine bone.

1. Occipital bone
2. Temporal bone (petrous part)
3. **Internal acoustic meatus**
4. **Carotid canal**
5. **Hypoglossal canal**
6. Occipital condyle
7. Lateral plate of pterygoid process
8. Dorsum of sella turcica
9. Sella turcica
10. Frontal sinus
11. **Optic canal**
12. **Posterior** and **anterior ethmoidal foramen**
13. Orbital plate of ethmoidal bone
14. Nasal bone
15. **Nasolacrimal canal**
16. Uncinate process
17. Inferior nasal concha (maxillary process)
18. Maxillary sinus
19. Anterior nasal spine
20. Alveolar process of maxilla
21. **Foramen rotundum**
22. **Pterygopalatine fossa**
23. Tuberosity of maxilla with **alveolar foramina**
24. **Sphenopalatine foramen**
25. Maxillary hiatus
26. **Pterygoid** or Vidian **canal**
27. **Lesser palatine canal**
28. **Greater palatine canal**
29. **Infraorbital canal**

1 **Occipital bone**
2 **Temporal bone**
3 **Frontal bone**
4 Nasal spine of frontal bone
5 **Zygomatic bone**
6 **Maxilla**
7 Frontal process of maxilla
8 **Ethmoid bone**
9 Orbital plate of ethmoid bone
10 Perpendicular plate of ethmoid bone
11 Site of **lacrimal bone**
12 Lacrimal groove of lacrimal bone
13 Posterior lacrimal crest
14 Fossa for lacrimal sac
15 Lacrimal hamulus
16 Nasolacrimal canal
17 Site of **nasal bone**
18 Nasal foramina of nasal bone
19 Anterior nasal spine of maxilla
20 **Vomer**
21 Greater wing of sphenoid bone
22 Anterior and posterior ethmoidal foramina
23 Optic canal
24 Superior orbital fissure
25 Inferior orbital fissure
26 Infraorbital groove
27 Infraorbital foramen



Anterior part of a disarticulated skull.
Orange = zygomatic bone; yellow = ethmoid bone; green = sphenoidal bone. The arrows indicate the locations of the lacrimal bone (11) and the nasal bone (17).



Left lacrimal bone (anterior aspect).



Left orbit (anterior aspect).



Left nasal bone (anterior aspect).



Lateral wall of the nasal cavity. Median section through the skull.

1 Frontal sinus
2 Ethmoidal air cells
3 Sphenoid sinus
4 Superior nasal concha
5 Middle nasal concha
6 Maxillary hiatus
7 Inferior nasal concha
8 Palatine bone
9 Maxilla
10 Inferior meatus
11 Palatine process of the maxilla

▷

To page 49:

Blue = Occipital bone
Light green = Parietal bone
Light brown = Frontal bone
Dark brown = Temporal bone
Red = Sphenoid bone
Dark green = Ethmoid bone
Light blue = Nasal bone
Pink = Inferior concha
Orange = Vomer
Violet = Maxilla
White = Palatine bone
White = Mandible

Inferior Concha and Vomer

1 Ethmoidal process
2 Anterior part of concha
3 Inferior border
4 Ala of vomer
5 Posterior border of nasal septum
6 Lacrimal process
7 Posterior part of concha
8 Maxillary process



Right inferior nasal concha (medial aspect). Anterior part to the left.



Right inferior nasal concha (lateral aspect). Anterior part to the right.



Vomer (posterior aspect).



Paramedian sagittal section through the skull including the nasal septum.

1 Crista galli
2 Cribriform plate of ethmoid bone
3 Perpendicular plate of ethmoid bone
4 Vomer
5 Ala of the vomer
6 Palatine bone (perpendicular process)
7 Palatine bone (horizontal plate)
8 Mandible
9 Nasal bone
10 Sphenoidal sinus
11 Hypophysial fossa (sella turcica)
12 Grooves for the middle meningeal artery

Cartilages of the nose

13 Lateral nasal cartilages
14 Greater alar cartilage
15 Lesser alar cartilages
16 Septal cartilage

17 Location of nasal bone



Cartilages of the nose (right anterior aspect). Arrow = nostril, framed by nasal wing.



Cartilages of the nose.
Schematic diagram of the external nose.


1
2
3
4
5
6
7
8
10
12
13
14
16
17
18
19
20
21
22
23
25
9
11
24
15
27
29
30
28
26

Base of the skull (inferior aspect).



Base of the skull (from below). The individual bones are indicated by different colours.



Skull of the newborn (inferior aspect).

A **Pterygoid canal**
B **Foramen ovale**
C Internal carotid artery within **carotid canal** and internal jugular vein within the venous part of jugular foramen
D **Stylomastoid foramen** (facial nerve)
E **Jugular foramen** (glossopharyngeal, vagus and accessory nerves)
F **Hypoglossal canal** (hypoglossal nerve)

1 Incisive canal
2 Median palatine suture
3 Palatine process of maxilla
4 Palatomaxillary suture
5 Greater and lesser palatine foramina
6 Inferior orbital fissure
7 Middle concha (process of ethmoid bone)
8 Vomer
9 Foramen ovale
10 Groove for auditory tube
11 Pterygoid canal
12 Styloid process
13 Carotid canal
14 Stylomastoid foramen
15 Jugular foramen
16 Groove for occipital artery
17 Occipital condyle
18 Condylar canal
19 Nuchal plane
20 External occipital protuberance
21 Zygomatic arch
22 Lateral pterygoid plate
23 Medial pterygoid plate
24 Mandibular fossa
25 Pharyngeal tubercle
26 Superior nuchal line
27 Mastoid process
28 Inferior nuchal line
29 Mastoid notch
30 Foramen magnum
31 **Incisive bone** or **premaxilla** (dark violet)
32 **Maxilla** (violet)
33 **Palatine bone** (white)
34 **Vomer** (orange)
35 **Sphenoid bone** (red)
36 **Zygomatic bone** (yellow)
37 **Temporal bone** (brown)
38 **Occipital bone** (blue)
39 Palatine process of maxilla
40 Vomer
41 Sphenoid bone
42 Petrous part of temporal bone
43 Basilar part
44 Lateral part } of occipital bone
45 Squamous part
46 Mandible
47 Zygomatic arch
48 Choana
49 Pterygoid process of sphenoid bone
50 Carotid canal
51 External acoustic meatus (tympanic annulus)
52 Sphenoidal fontanelle
53 Parietal bone
54 Mastoid fontanelle



1 Central incisor
2 Lateral incisor
3 Canines
4 First premolars or bicuspids
5 Second premolars or bicuspids
6 First molars
7 Second molars
8 Third molars
9 Articular tubercle
10 Mandibular fossa
11 Head of mandible
12 Condylar process

Normal position of teeth. Dentition in centric occlusion (lateral view).



Upper teeth of the adult (inferior aspect).



Lower teeth of the adult (superior aspect).

Table of dentition. Eruption of deciduous and permanent teeth (after C. Röse according to A. Kröncke).

Primary dentition (Deciduous teeth)	Maxilla months post partum	Mandible months
1. Central incisor	10.3	8.6
2. Lateral incisor	12.2	14.4
3. Cuspid incisor	19.5	20.1
4. First molar	15.5	16.5
5. Second molar	24.8	24.5

Secondary dentition (Permanent teeth)	years and months ♂	♀	years and months ♂	♀
1. Central incisor	7/8	7/5	6/10	6/7
2. Lateral incisor	8/11	8/6	7/11	7/7
3. Cuspid incisor	12/2	11/7	11/12	10/3
4. First premolar	10/5	10/1	11/3	10/8
5. Second premolar	11/4	11/1	12/0	11/7
6. First molar	6/7	6/6	6/5	6/3
7. Second molar	12/9	12/5	12/3	11/9



Comparison of the deciduous and permanent teeth. Notice that the breadth of the alveolar arch of the child's mandible and maxilla holding the deciduous teeth is nearly the same as the comparable portion in the jaws of the adult. Note the unerupted third molars.



Deciduous teeth in child's skull. The developing crowns of the permanent teeth are displayed in their sockets in the maxilla and mandible.

△

1 Permanent incisors
2 Permanent cuspid (canine)
3 Premolars
4 First permanent molar
5 Second permanent molar
6 Mental foramen



Isolated teeth of the alveolar part of the maxilla (top row) and the mandible (lower row), labial surface of the teeth.



Skull of the newborn (anterior aspect).



Skull of the newborn (superior aspect). Calvaria.

Cranial skeleton

1 Frontal tuber or eminence
2 Parietal tuber or eminence
3 Occipital tuber or eminence
4 Squamous part of temporal bone
5 Greater wing of sphenoid bone

Facial skeleton

6 Maxilla
7 Mandible
8 Zygomatic bone
9 Nasal bone

Sutures and fontanelles

10 Frontal suture
11 Coronal suture
12 Sagittal suture
13 Lambdoid suture
14 Anterior fontanelle
15 Posterior fontanelle
16 Sphenoidal fontanelle
17 Mastoid fontanelle

Base of the skull

18 Frontal bone
19 Ethmoid bone
20 Sphenoid bone
21 Hypophysial fossa (sella turcica)
22 Dorsum sellae
23 Temporal bone
24 Mastoid fontanelle
25 Occipital bone

In the newborn the facial skeleton, in contrast to the cranial skeleton, appears relatively small. There are no teeth presenting. The bones of the cranium are separated by wide fontanelles.



Skull of the newborn (lateral aspect).



Base of the skull of the newborn (internal aspect).



Lateral aspect of the facial bones. Mandible and teeth in the position of occlusion. Upper and lower jaw occluded.



Mandible of the adult (anterior aspect).



Right half of mandible (medial aspect).



Mandible of the adult (superior aspect).

1 **Temporal bone**
2 Temporal fossa (greater wing of sphenoid bone)
3 Infratemporal crest
4 Infratemporal fossa
5 Zygomatic arch
6 **Frontal bone**
7 **Zygomatic bone** (frontal process)
8 **Lacrimal bone**
9 **Nasal bone**
10 Lacrimal groove
11 **Maxilla** (canine fossa)
12 Alveolar process of maxilla

Mandible

13 Condylar process
14 Mandibular notch
15 Ramus of the mandible
16 Masseteric tuberosity
17 Angle of the mandible
18 Body of the mandible
19 Coronoid process
20 Alveolar process including teeth
21 Oblique line
22 Mental foramen
23 Mental protuberance
24 Head of the mandible
25 Genial tubercle or mental spine
26 Mandibular foramen (entrance to mandibular canal)
27 Lingula
28 Mylohyoid sulcus
29 Mylohyoid line
30 Submandibular fossa
31 Sublingual fossa



Temporomandibular joint with ligaments.

1 Zygomatic arch
2 Articular capsule
3 External acoustic meatus
4 **Lateral ligament**
5 Mandibular notch
6 **Stylomandibular ligament**
7 Ramus of the mandible
8 Zygomatic bone
9 Coronoid process
10 Maxilla
11 Articular cartilage of condylar process
12 Styloid process
13 Mandibular fossa
14 **Articular disc**
15 Articular tubercle
16 Lateral pterygoid muscle
17 Condylar process of mandible



Temporomandibular joint, sagittal section.



Ligaments of temporomandibular joint. Left half of the head (medial aspect).

1 Groove for sigmoid sinus
2 Mandibular nerve
3 Lateral pterygoid muscle
4 Styloid process
5 **Sphenomandibular ligament**
6 **Stylomandibular ligament**
7 Mylohyoid groove
8 **Ethmoidal air cells**
9 Ethmoidal bulla
10 **Hiatus semilunaris**
11 Middle meatus
12 **Inferior nasal concha**
13 Limen nasi
14 Vestibule with hairs
15 Inferior meatus
16 Hard palate
17 Soft palate
18 Vestibule of oral cavity
19 Lower lip
20 Mandible



Coronal section through the head at the level of the temporomandibular joint (right side, anterior aspect).

1 Insular lobe and temporal lobe
2 Temporalis muscle
3 **Articular disc of temporomandibular joint**
4 Maxillary artery and pterygoid venous plexus
5 Parotid gland
6 **Mandible**
7 **Medial pterygoid muscle**
8 **Masseter muscle**
9 Submandibular gland
10 Thyroid gland
11 Sternocleidomastoid muscle
12 Hippocampus
13 Internal carotid artery and sphenoid bone
14 Pharyngeal tonsil
15 Pharynx
16 Thyroid cartilage
17 Rima glottidis
18 Cricoid cartilage
19 **Hard palate** and palatine glands
20 **Oral cavity**
21 Upper molar
22 **Oral vestibule**
23 Lower molar
24 Platysma muscle
25 Maxillary sinus
26 Superior longitudinal muscle of tongue
27 **Transverse muscle of tongue**
28 Buccinator muscle
29 Inferior longitudinal muscle of tongue
30 Sublingual gland
31 **Genioglossus muscle**
32 Mastoid process
33 Styloid process
34 **Stylomandibular ligament**
35 Articular capsule
36 **Lateral ligament**
37 Zygomatic arch
38 **Sphenomandibular ligament**
39 Mandibular foramen



Coronal section through the oral cavity



Ligaments related to the **temporomandibular joint**

Temporalis and masseter muscles. The temporal fascia has been removed, the temporomandibular joint severed and the zygomatic arch displayed.



1	Galea aponeurotica
2	**Temporalis muscle**
3	Occipital belly of occipitofrontalis muscle
4	**Temporomandibular joint**
5	External acoustic meatus
6	Deep layer of **masseter muscle**
7	Superficial layer of masseter muscle
8	Stylohyoid muscle
9	Posterior belly of **digastric muscle**
10	Internal jugular vein and external carotid artery
11	**Sternocleidomastoid muscle**
12	Frontal belly of occipitofrontalis muscle
13	Depressor supercilii muscle
14	**Orbicularis oculi muscle**
15	Transverse part of nasalis muscle
16	Levator labii superioris alaeque nasi muscle
17	Levator labii superioris muscle
18	Levator anguli oris muscle
19	**Zygomaticus major muscle**
20	**Orbicularis oris muscle**
21	**Buccinator muscle**
22	Depressor labii inferioris muscle
23	Depressor anguli oris muscle
24	**Submandibular gland**
25	Lateral nasal cartilage
26	Greater alar cartilage (lateral part)
27	Lesser alar cartilages
28	Greater alar cartilage (medial part)
29	Infraorbital nerve
30	Anterior belly of digastric muscle
31	Hypoglossal nerve and hyoglossus muscle
32	Superior thyroid artery
33	**Zygomatic arch**
34	Internal carotid artery
35	Common carotid artery



Temporalis muscle and temporomandibular joint. The zygomatic arch and the masseter muscle have been partially severed to display the insertion of the temporalis muscle.



1	Periosteum
2	**Temporalis muscle**
3	Zygomatic arch
4	Articular capsule of temporomandibular joint
5	**Lateral pterygoid muscle** (upper and lower head)
6	**Medial pterygoid muscle**
7	Styloglossus muscle
8	Stylohyoid muscle
9	Posterior belly of digastric muscle
10	**Masseter muscle** (severed)
11	Mandible
12	Sternocleidomastoid muscle
13	Orbicularis oculi muscle
14	Orbicularis oris muscle
15	Buccinator muscle
16	Depressor anguli oris muscle
17	Depressor labii inferioris muscle
18	Platysma muscle
19	**Articular disc of temporomandibular joint**
20	Head of mandible
21	Anterior belly of digastric muscle
22	Mylohyoid muscle
23	Hyoid bone

Medial and lateral pterygoid muscles. A portion of the mandible and the zygomatic arch has been removed revealing the pterygoid region or infratemporal fossa.



Effect of the muscles of mastication on the temporomandibular joint (arrows).



Facial muscles (anterior aspect). Left side: superficial layer; right side: deeper layer.

1	Frontal belly of **occipitofrontalis muscle**
2	**Corrugator supercilii muscle**
3	Palpebral part of orbicularis oculi muscle
4a	Transverse part of nasalis muscle
4b	Alar part of **nasalis muscle**
5	Levator labii superioris alaeque nasi muscle
6	**Levator labii superioris muscle**
7	**Zygomaticus major muscle**
8	Levator anguli oris muscle
9	Parotid duct
10	**Orbicularis oris muscle**
11	Masseter muscle
12	**Depressor anguli oris muscle**
13	**Mentalis muscle**
14	Sternocleidomastoid muscle
15	**Procerus muscle**
16	**Depressor supercilii muscle**
17	Orbital part of **orbicularis oculi muscle**
18	Zygomaticus minor muscle
19	**Buccinator muscle**
20	Risorius muscle
21	**Depressor labii inferioris muscle**
22	**Platysma muscle**
23	Galea aponeurotica
24	**Temporoparietalis muscle**
25	Occipital belly of occipitofrontalis muscle
26	Parotid gland with fascia
27	Temporal fascia
28	**Orbicularis oculi muscle**
29	Parotid duct, masseter muscle



Facial muscles (schematic drawing). Left side: superficial layer; right side: deeper layer.



Facial muscles. Sphincter-like muscles surround the orifices of the head. Radially arranged muscles work as their antagonists.


1
15
17
4 a
4 b
17
5
6
18
10
7
20
21
12
22
23
24
25
26
14

Facial muscles (lateral aspect).


1
23
2
27
28
6
8
10
7
12
22
29
26
14

Facial muscles and parotid gland (lateral aspect).


17
7
10
21
20
26
22
14

Platysma muscle (oblique lateral aspect). Superficial lamina of cervical fascia partly removed.



Supra- and infrahyoid muscles, pharynx I (lateral aspect). Ramus of mandible, pterygoid muscles and insertion of temporalis muscle removed.



Supra- and infrahyoid muscles. (Schematic diagram.)

1 Galea aponeurotica
2 **Temporal fascia**
3 Tendon of temporalis muscle
4 Zygomatic arch
5 Lateral pterygoid plate
6 Tensor veli palatini muscle (styloid process)
7 Superior constrictor muscle of pharynx
8 **Styloglossus muscle**
9 Posterior belly of digastric muscle
10 **Stylohyoid muscle**
11 Longus capitis muscle
12 Sternocleidomastoid muscle (reflected)
13 Inferior constrictor of pharynx
14 Frontal belly of occipitofrontalis muscle
15 Orbital part of orbicularis oculi muscle
16 **Buccinator muscle**
17 Depressor anguli oris muscle
18 **Mylohyoid muscle**
19 Anterior belly of digastric muscle
20 **Thyrohyoid muscle**
21 **Sternohyoid muscle**
22 **Omohyoid muscle**
23 Hyoid bone
24 Sternothyroid muscle



Supra- and infrahyoid muscles, pharynx II. Buccinator muscle removed; oral cavity opened.

1 External acoustic meatus
2 Tensor veli palatini muscle
3 Styloid process
4 **Superior constrictor muscle of pharynx**
5 Stylopharyngeus muscle (divided)
6 **Middle constrictor muscle of pharynx**
7 Sternocleidomastoid muscle
8 Greater horn of hyoid bone
9 Longus capitis
10 **Inferior constrictor muscle of pharynx**
11 Temporal fascia
12 Tendon of temporalis muscle

13 Orbicularis oculi muscle
14 Zygomatic arch
15 Lateral pterygoid plate
16 Parotid duct
17 Gingiva of upper jaw (without teeth), buccinator muscle (divided)
18 Pterygomandibular raphe
19 Hyoglossus muscle
20 Mylohyoid muscle
21 Anterior belly of digastric muscle (hyoid bone)
22 Sternohyoid and thyrohyoid muscles
23 Omohyoid muscle



Coronal section through cranial, nasal and oral cavity at the level of sphenoidal sinus.



Pterygoid and palatine muscles (posterior aspect).

1 Temporalis muscle
2 **Sphenoidal sinus**
3 **Nasopharynx**
4 Masseter muscle
5 Superior longitudinal, transverse and vertical muscles of tongue
6 Hyoglossus muscle
7 Geniohyoid muscle
8 Corpus callosum (caudate nucleus)
9 Optic nerve
10 Cavernous sinus
11 Zygomatic arch
12 Cross section of lateral pterygoid muscle and maxillary artery
13 Section of medial pterygoid muscle
14 **Soft palate**
15 Mandible and inferior alveolar nerve
16 Septum of the tongue
17 **Mylohyoid muscle**
18 Submandibular gland
19 Platysma muscle
20 Foramen magnum, vertebral artery and spinal cord
21 Internal carotid artery
22 **Head of mandible**
23 Styloid process
24 Inferior alveolar nerve
25 Lingual nerve and chorda tympani nerve
26 **Medial pterygoid muscle**
27 Uvula
28 Anterior belly of digastric muscle (cut)
29 Condyle of occipital bone
30 Mastoid process
31 **Lateral pterygoid muscle**
32 Auditory tube and **levator veli palatini muscle**
33 **Tensor veli palatini muscle**



1 Superficial temporal artery and auriculotemporal nerve
2 Middle meningeal artery
3 **Maxillary artery**
4 Facial nerve (divided and reflected)
5 **External carotid artery**
6 Stylohyoid muscle
7 Digastric muscle (posterior belly)
8 Internal carotid artery and carotid sinus branch of glossopharyngeal nerve
9 Sternocleidomastoid muscle
10 Common carotid artery
11 Temporalis muscle
12 Pterygopalatine fossa
13 Posterior superior alveolar artery
14 Deep temporal artery
15 Infraorbital artery
16 Buccal nerve
17 Inferior alveolar artery and nerve
18 **Facial artery**
19 Submental artery
20 Hyoid bone
21 Superior thyroid artery (divided)

Dissection of maxillary artery. Mandible and lateral pterygoid muscle partly removed.



1 Superficial temporal artery

Branches of the first part
2 Deep auricular artery and anterior tympanic artery
3 Middle meningeal artery
4 Inferior alveolar artery

Branches of the second part
5 Deep temporal branches
6 Pterygoid branches
7 Masseteric artery
8 Buccal artery

Branches of the third part
9 Posterior superior alveolar artery
10 Infraorbital artery
11 Sphenopalatine artery and branches to the nasal cavity
12 Descending palatine artery
13 Artery of the pterygoid canal

Main branches of maxillary artery. (Schematic drawing.)



Base of the skull with cranial nerves (internal aspect). Both cerebral hemispheres and upper part of the brain stem removed. Incision on the right tentorium cerebelli to display the cranial nerves of the infratentorial space.

1	Superior sagittal sinus with falx cerebri	12	Hypophysial fossa, infundibulum, and diaphragma sellae
2	Olfactory bulb	13	Dorsum sellae
3	**Olfactory tract**	14	Midbrain (divided)
4	**Optic nerve** and internal carotid artery	15	**Trigeminal nerve** (n. V)
5	Anterior clinoid process and anterior attachment of tentorium cerebelli	16	**Facial nerve** (n. VII), nervus intermedius, and **vestibulocochlear nerve** (n. VIII)
6	**Oculomotor nerve** (n. III)	17	Cerebral aqueduct
7	**Abducens nerve** (n. VI)	18	Right hemisphere of cerebellum
8	Tentorial notch (incisura tentorii)	19	Vermis of cerebellum
9	**Trochlear nerve** (n. IV)	20	Straight sinus
10	Tentorium cerebelli		
11	Falx cerebri and confluence of sinuses		



Inferior aspect of the brain with cranial nerves. Midbrain divided.

1 **Frontal lobe**
2 **Temporal lobe**
3 Pedunculus cerebri
4 **Midbrain** (divided)
5 Cerebral aqueduct
6 Splenium of corpus callosum
7 **Occipital lobe**
8 Olfactory bulb
9 Olfactory tract
10 **Optic nerve and optic chiasma**
11 Infundibulum
12 **Oculomotor nerve** (n. III)
13 Mamillary body
14 Substantia nigra
15 **Trochlear nerve** (n. IV)

Cranial nerves

I = Olfactory nerves
II = Optic nerve
III = Oculomotor nerve
IV = Trochlear nerve
V = Trigeminal nerve
VI = Abducens nerve
VII = Facial nerve
VIII = Vestibulocochlear nerve
IX = Glossopharyngeal nerve
X = Vagus nerve
XI = Accessory nerve
XII = Hypoglossal nerve



Cranial nerves. Brain (inferior aspect).

1 Olfactory sulcus (termination)
2 Orbital gyri
3 Temporal lobe
4 Straight gyrus
5 Olfactory trigone and inferior temporal sulcus
6 Medial occipitotemporal gyrus
7 Parahippocampal gyrus, mamillary body, and interpeduncular fossa
8 Pons and cerebral peduncle
9 **Abducens nerve** (n. VI)
10 Pyramid
11 Lower part of olive
12 Cervical spinal nerves
13 Cerebellum
14 Tonsil of cerebellum
15 Occipital lobe (posterior pole)
16 Olfactory bulb
17 Orbital sulci of frontal lobe
18 **Olfactory tract**
19 **Optic nerve** (n. II) and anterior perforated substance
20 Optic chiasma
21 Optic tract
22 **Oculomotor nerve** (n. III)
23 **Trochlear nerve** (n. IV)
24 **Trigeminal nerve** (n. V)
25 **Facial nerve** (n. VII)
26 **Vestibulocochlear nerve** (n. VIII)
27 Flocculus of cerebellum
28 **Glossopharyngeal** (n. IX) and **vagus nerve** (n. X)
29 **Hypoglossal nerve** (n. XII)
30 **Accessory nerve** (n. XI)
31 Vermis of cerebellum
32 Longitudinal fissure



Brain stem and pharynx with cranial nerves (posterior aspect). Cranial cavity opened and cerebellum removed.

1	Falx cerebri	15	**Glossopharyngeal nerve** (n. IX) and vagus nerve (n. X)
2	Occipital lobe	16	**Accessory nerve** (intracranial portion) (n. XI)
3	Straight sinus	17	**Hypoglossal nerve** (intracranial portion) (n. XII)
4	Tentorium cerebelli	18	**Accessory nerve** (n. XI)
5	Transverse sinus	19	**Hypoglossal nerve** (n. XII)
6	Inferior colliculus of midbrain	20	**Vagus nerve** (n. X) and internal carotid artery
7	**Rhomboid fossa**	21	External carotid artery
8	Medulla oblongata	22	**Sympathetic trunk** and superior cervical ganglion
9	Posterior belly of digastric muscle	23	Ansa cervicalis (superior root of hypoglossal nerve)
10	Internal carotid artery	24	**Glossopharyngeal nerve** (n. IX) and stylopharyngeus muscle
11	Pharynx (middle constrictor muscle)		
12	Hyoid bone (greater horn)		
13	**Trochlear nerve** (n. IV)		
14	**Facial nerve** (n. VII), **vestibulocochlear nerve** (n. VIII)		



Cranial nerves of the orbit and pterygopalatine fossa. Left orbit (lateral aspect).
Note the zygomaticolacrimal anastomosis (arrow).

1 Frontal lobe
2 Supraorbital nerve
3 Lacrimal gland
4 Lacrimal nerve
5 Lateral rectus muscle (divided)
6 **Optic nerve** and short ciliary nerves
7 Inferior oblique muscle
8 Zygomatic nerve
9 Inferior branch of oculomotor nerve and inferior rectus muscle
10 Infraorbital nerve
11 Posterior superior alveolar nerves
12 Branches of superior alveolar plexus adjacent to mucous membrane of maxillary sinus
13 Central sulcus of insula
14 Superior rectus muscle
15 Periorbita (roof of orbit)
16 Nasociliary nerve
17 Ciliary ganglion
18 **Oculomotor nerve** (n. III)
19 **Trochlear nerve** (n. IV)
20 **Ophthalmic nerve** (n. V_1)
21 **Abducens nerve** (n. VI) (divided)
22 **Trigeminal nerve** (n. V)
23 Trigeminal ganglion
24 **Maxillary nerve** (n. V_2) and foramen rotundum
25 **Mandibular nerve** (n. V_3)
26 External acoustic meatus
27 Pterygopalatine nerves
28 Deep temporal nerves
29 Buccal nerve
30 Masseteric nerve
31 Auriculotemporal nerve
32 Trochlea and superior oblique muscle



Cranial nerves innervating extraocular muscles (lateral aspect).
(Schematic drawing.)



Cranial nerves of the orbit (superior aspect). Right side: superficial layer; left side: middle layer of the orbit (superior rectus muscle and frontal nerve divided and reflected). Tentorium and dura mater partly removed.



Cranial nerves at the skull base. The brain stem was divided and the tentorium fenestrated. Both hemispheres were removed.

1 Frontal sinus (enlarged)
2 Frontal nerve (divided and reflected)
3 Superior rectus muscle (divided) and eyeball
4 Superior oblique muscle
5 Short ciliary nerves and optic nerve (n. II)
6 Nasociliary nerve
7 **Abducens nerve** (n. VI) and lateral rectus muscle
8 Ciliary ganglion and superior rectus muscle (reflected)
9 **Oculomotor nerve** (n. III)
10 **Trochlear nerve** (n. IV)
11 Crus cerebri and midbrain
12 Inferior wall of the third ventricle connected with cerebral aqueduct
13 Lateral and medial branch of supraorbital nerve
14 Supratrochlear nerve
15 Superior rectus muscle
16 Lacrimal nerve
17 Frontal nerve
18 **Ophthalmic nerve** (n. V1)
19 Optic chiasma and internal carotid artery
20 Trigeminal ganglion
21 **Trigeminal nerve** (n. V)
22 Tentorial notch
23 Falx cerebri
24 Cerebellum
25 Infundibulum
26 Olfactory tract



Dissection of the trigeminal nerve in its entirety. Lateral wall of cranial cavity, lateral wall of orbit, zygomatic arch and ramus of the mandible have been removed and the mandibular canal opened.

1 Frontal lobe of cerebrum
2 Supraorbital nerve
3 Lacrimal nerve
4 Lacrimal gland
5 Eyeball
6 **Optic nerve** and short ciliary nerves
7 External nasal branch of anterior ethmoidal nerve
8 Ciliary ganglion
9 Zygomatic nerve
10 Infraorbital nerve
11 Infraorbital foramen and terminal branches of infraorbital nerve
12 Pterygopalatine ganglion and pterygopalatine nerves
13 Posterior superior alveolar nerves
14 Superior dental plexus
15 Buccinator muscle and buccal nerve
16 Inferior dental plexus
17 Mental foramen and mental nerve
18 Anterior belly of digastric muscle
19 **Ophthalmic nerve** (n. V_1)
20 **Oculomotor nerve** (n. III)
21 **Trochlear nerve** (n. IV)
22 Trigeminal nerve and pons
23 **Maxillary nerve** (n. V_2)
24 Trigeminal ganglion
25 **Mandibular nerve** (n. V_3)
26 Auriculotemporal nerve
27 External acoustic meatus (divided)
28 Lingual nerve and chorda tympani
29 Mylohyoid nerve
30 Medial pterygoid muscle
31 Inferior alveolar nerve
32 Posterior belly of digastric muscle
33 Stylohyoid muscle
34 Sternocleidomastoid muscle



Cranial nerves in connection with the brain stem. Left side (lateral superior aspect). Left half of brain and head partly removed. Notice the location of trigeminal ganglion.



Main branches of trigeminal nerve. (Schematic drawing of figure on opposite page.)

1 Frontal nerve
2 Lacrimal gland and eyeball
3 Lacrimal nerve
4 Lateral rectus muscle
5 **Ciliary ganglion** lateral to optic nerve
6 Zygomatic nerve
7 Inferior branch of oculomotor nerve
8 **Ophthalmic nerve** (n. V_1)
9 **Maxillary nerve** (n. V_2)
10 **Trigeminal ganglion**
11 **Mandibular nerve** (n. V_3)
12 Posterior superior alveolar nerves
13 Tympanic cavity, external acoustic meatus, and tympanic membrane
14 Inferior alveolar nerve
15 Lingual nerve
16 **Facial nerve** (n. VII)
17 **Vagus nerve** (n. X)
18 **Hypoglossal nerve** (n. XII) and superior root of ansa cervicalis
19 External carotid artery
20 **Olfactory tract** (n. I)
21 **Optic nerve** (n. II) (intracranial part)
22 **Oculomotor nerve** (n. III)
23 **Abducens nerve** (n. VI)
24 **Trochlear nerve** (n. IV)
25 **Trigeminal nerve** (n. V)
26 **Vestibulocochlear nerve** (n. VIII) and **facial nerve** (VII)
27 **Glossopharyngeal nerve** (n. IX) (leaving brain stem)
28 Rhomboid fossa
29 **Vagus nerve** (n. X) (leaving brain stem)
30 **Hypoglossal nerve** (n. XII) (leaving medulla oblongata)
31 **Accessory nerve** (n. XI) (ascending from foramen magnum)
32 Vertebral artery
33 Spinal ganglion and dura mater of spinal cord
34 Accessory nerve (n. XI)
35 Internal carotid artery
36 Lateral and medial branch of supraorbital nerve
37 Infratrochlear nerve
38 Infraorbital nerve
39 **Pterygopalatine ganglion** and middle superior alveolar nerve
40 Middle superior alveolar nerves (entering superior dental plexus)
41 Buccal nerve
42 Mental nerve and mental foramen
43 Auriculotemporal nerve
44 Otic ganglion (dotted line)
45 Chorda tympani
46 Mylohyoid nerve
47 Submandibular gland
48 Hyoid bone



Dissection of facial nerve in its entirety. Cranial cavity fenestrated; temporal lobe partly removed. Facial canal and tympanic cavity opened, posterior wall of external acoustic meatus removed. **Branches of facial nerve:** a = temporal branch; b = zygomatic branches; c = buccal branches; d = marginal mandibular branch.



Facial nerve. (Schematic drawing of the dissection above.)

1 Trochlear nerve
2 Facial nerve with geniculate ganglion
3 Cerebellum (right hemisphere)
4 Occipital belly of occipitofrontalis and greater occipital nerve
5 Facial nerve at stylomastoid foramen
6 Splenius capitis muscle
7 Cervical branch of facial nerve
8 Sternocleidomastoid muscle and retromandibular vein
9 Orbicularis oculi muscle
10 Chorda tympani
11 External acoustic meatus
12 Facial artery
13 Mastoid air cells
14 Posterior auricular nerve
15 Nucleus and genu of facial nerve



Cranial nerves in connection with the brain stem (oblique-lateral aspect). Lateral portion of the skull, brain, neck and facial structures, lateral wall of orbit and oral cavity have been removed. The tympanic cavity has been opened. The mandible has been divided and the muscles of mastication have been removed.

1 Optic tract
2 **Oculomotor nerve** (n. III)
3 Lateral rectus muscle and inferior branch of oculomotor nerve
4 Malleus and chorda tympani
5 Chorda tympani, **facial nerve** (n. VII), and **vestibulocochlear nerve** (n. VIII)
6 **Glossopharyngeal nerve** (n. XI)
7 Lingual nerve and inferior alveolar nerve
8 Styloid process and stylohyoid muscle
9 Styloglossus muscle
10 Lingual branches of glossopharyngeal nerve
11 Lingual branch of hypoglossal nerve
12 External carotid artery
13 Superior root of ansa cervicalis (branch of hypoglossal nerve)
14 Lateral ventricle with choroid plexus and cerebral peduncle
15 **Trochlear nerve** (n. IV)
16 **Trigeminal nerve** (n. V)
17 Fourth ventricle and rhomboid fossa
18 **Vagus nerve** (n. X)
19 **Accessory nerve** (n. XI)
20 Vertebral artery
21 Superior cervical ganglion
22 **Hypoglossal nerve** (n. XII)
23 Spinal ganglion with dural sheath
24 Dura mater of spinal cord
25 Internal carotid artery and carotid sinus branch of glossopharyngeal nerve
26 Dorsal roots of spinal nerve
27 Sympathetic trunk
28 Branch of cervical plexus (ventral primary ramus of third cervical spinal nerve)
29 Ansa cervicalis



Lateral superficial aspect of the face. Peripheral distribution of facial nerve. a–d = branches of facial nerve: a = temporal branch; b = zygomatic branches; c = buccal branches; d = marginal mandibular branch.



Superficial region of the face. Note the facial plexus within the parotid gland. (Semischematic drawing.)

1 Temporoparietalis muscle
2 Parietal branch of **superficial temporal artery** and **vein** and **auriculotemporal nerve**
3 Occipital belly of occipitofrontalis muscle and greater occipital nerve
4 **Facial nerve**
5 Lesser occipital nerve and **occipital artery**
6 Transverse facial artery
7 Masseter muscle
8 **Parotid gland** and great auricular nerve
9 Sternocleidomastoid muscle and external jugular vein
10 Splenius capitis muscle
11 Branches of cervical plexus
12 Trapezius muscle
13 Angular artery (terminal portion of facial artery)
14 Orbicularis oculi muscle
15 Levator labii superioris alaeque nasi muscle
16 **Facial artery** and zygomaticus minor muscle
17 Levator anguli oris muscle
18 Zygomaticus major muscle
19 Orbicularis oris muscle and superior labial artery
20 Parotid duct
21 Risorius muscle and inferior labial artery



Superficial layer of the head and neck. Parotid fascia removed. Branches of **facial nerve:** a = temporal branch; b = zygomatic branches; c = buccal branches; d = marginal mandibular branch.

1 Medial branch of supraorbital nerve
2 Nasalis muscle
3 Levator labii superioris alaeque nasi muscle
4 **Orbicularis oculi muscle**
5 Levator labii superioris muscle
6 **Facial artery and vein**
7 Zygomaticus minor and major muscle
8 Transverse facial artery
9 **Orbicularis oris muscle**
10 Buccal nerves, depressor labii inferioris muscle, **facial artery** and **vein**
11 **Parotid gland** and duct and masseter muscle
12 Depressor anguli oris muscle
13 Transverse cervical nerve
14 External jugular vein
15 **Platysma muscle**
16 Supraclavicular nerve
17 Galea aponeurotica
18 Lateral branches of the supraorbital nerve
19 Frontal belly of occipitofrontalis muscle and branches of superficial temporal vein and artery
20 Superficial temporal artery and vein
21 **Auriculotemporal nerve**
22 Zygomatico-orbital artery and temporoparietalis muscle
23 Lesser occipital nerve
24 Occipital belly of occipitofrontalis muscle
25 Occipital vein and occipital artery
26 **Great auricular nerve** and sternocleidomastoid muscle
27 Trapezius muscle
28 Greater petrosal nerve
29 Geniculate ganglion
30 Chorda tympani
31 Posterior auricular nerve
32 Stylomastoid foramen

◁ **to page 76**

22 Depressor labii inferioris muscle
23 Depressor anguli oris muscle
24 Platysma muscle
25 Terminal branches of transverse cervical nerve
26 Cervical branch of facial nerve
27 Orbicularis oris muscle
28 **Facial artery** and **vein**
29 Sternocleidomastoid muscle and retromandibular vein



Facial nerve. Main branches. (Schematic diagram.)



Lateral superficial aspect of the face. The parotid gland has been removed to display the parotid plexus of the facial nerve. a–e = branches of facial nerve: a = temporal branch; b = zygomatic branches; c = buccal branches; d = marginal mandibular branch; e = cervical branch.

1 Superficial temporal artery and auriculotemporal nerve
2 Posterior auricular artery and nerve and temporoparietalis muscle
3 Occipital artery
4 **Facial nerve** (n. VII) (**parotid plexus** [×])
  a Temporal branches
  b Zygomatic branches
  c Buccal branches
  d Marginal mandibular branch
  e Cervical branch
5 Posterior auricular nerve
6 Posterior auricular artery
7 Digastric muscle (posterior belly)
8 **Lesser occipital nerve**
9 Posterior auricular vein
10 Retromandibular vein
11 **Hypoglossal nerve** and sternocleidomastoid artery
12 **Great auricular nerve**
13 Internal carotid artery
14 External carotid artery
15 Common carotid artery
16 Branches of cervical plexus
17 Superior laryngeal artery and vein
18 External jugular vein and sternocleidomastoid muscle
19 Frontal branch of superficial temporal artery, lateral branch of supraorbital nerve, and frontal belly of occipitofrontalis muscle
20 Medial branch of supraorbital nerve
21 Dorsal nasal artery
22 Angular artery and nasalis muscle
23 **Orbicularis oculi muscle**
24 Zygomaticus minor muscle
25 Buccal fat pad, zygomaticus major muscle, and infraorbital nerve
26 **Orbicularis oris muscle**
27 **Parotid duct** and **masseter muscle**
28 Buccal artery and nerve
29 Buccinator muscle
30 Risorius muscle
31 **Facial artery** and **vein**
32 Submental artery and depressor anguli oris muscle
33 Mylohyoid nerve and mylohyoid muscle
34 Digastric muscle (anterior belly)
35 Facial vein and submandibular gland
36 **Superior thyroid artery**
37 Sternohyoid muscle



Lateral superficial aspect of the face. Masseter muscle and temporal fascia have been partly removed to display the masseteric artery and nerve.

1 Galea aponeurotica
2 Temporal fascia
3 **Temporalis muscle**
4 Parietal branch of **superficial temporal artery**
5 **Auriculotemporal nerve**
6 Frontal branch of superficial temporal artery
7 Superficial temporal vein
8 **Zygomatic arch**
9 **Articular disc of temporomandibular joint**
10 **Head of mandible**
11 Masseteric artery and nerve
12 Mandibular notch
13 Masseter muscle (divided)
14 **External carotid artery**
15 Great auricular nerve
16 Facial nerve (reflected)
17 Frontal belly of occipitofrontalis muscle
18 Medial branch of supraorbital nerve
19 **Angular artery**
20 Orbicularis oculi muscle
21 **Infraorbital nerve**
22 Zygomaticus major muscle
23 **Maxillar artery**
24 **Coronoid process**
25 Parotid duct (divided)
26 Buccal nerve
27 **Facial artery** and **vein**
28 **Mental nerve**
29 Mandibular branch of facial nerve
30 Cervical branch of facial nerve
31 Transverse cervical nerve (communicating branch with facial nerve) and sternocleidomastoid muscle



Deep dissection of facial and retromandibular regions. The coronoid process together with the insertions of temporalis muscle have been removed to display the maxillary artery. The upper part of the mandibular canal has been opened.

1 Parietal branch of the superficial temporal artery
2 Frontal branch of the superficial temporal artery
3 Auriculotemporal nerve
4 **Maxillary artery**
5 **Superficial temporal artery**
6 Communicating branches between facial and auriculotemporal nerves
7 **Facial nerve**
8 Posterior auricular artery and anterior auricular branch of superficial temporal artery
9 Internal jugular vein
10 Mylohyoid nerve
11 Posterior belly of digastric muscle
12 Great auricular nerve and sternocleidomastoid
13 External jugular vein
14 Retromandibular vein
15 Submandibular gland
16 Temporal fascia
17 **Temporalis tendon**
18 Deep temporal arteries
19 Posterior superior alveolar nerve
20 Sphenopalatine artery
21 Posterior superior alveolar arteries
22 Masseteric artery and nerve
23 **Buccal nerve and artery**
24 **Lateral pterygoid**
25 Transverse facial artery and parotid duct (divided)
26 Medial pterygoid
27 **Facial artery**
28 **Lingual nerve**
29 **Inferior alveolar artery and nerve** (mandibular canal opened)



Retromandibular region with maxillary artery and branches of trigeminal nerve (n. V).

1 Frontal belly of occipitofrontalis muscle
2 Depressor supercilii muscle
3 Temporalis muscle
4 **Orbicularis oculi muscle**
5 Nasalis muscle
6 Infraorbital artery
7 Levator labii superioris alaeque nasi muscle
8 Zygomaticus minor muscle
9 Levator labii superioris muscle
10 Infraorbital artery and nerve and posterior superior alveolar artery
11 **Zygomaticus major muscle**
12 **Lingual nerve**
13 **Inferior alveolar artery and nerve**
14 Buccinator muscle
15 Depressor anguli oris muscle
16 **Medial pterygoid muscle** and **mylohyoid nerve**
17 Depressor labii inferioris muscle
18 **Hypoglossal nerve** and **hyoglossus muscle**
19 Mylohyoid muscle
20 Anterior belly of diagastric muscle
21 Sternohyoid muscle
22 Thyrohyoid muscle
23 Galea aponeurotica
24 Occipital belly of occipitofrontalis muscle
25 **Lateral pterygoid muscle** and deep temporal artery
26 **Maxillary artery**
27 Internal jugular vein
28 Styloglossus muscle
29 Splenius capitis muscle
30 Posterior belly of diagastric muscle and occipital artery
31 Superficial temporal artery
32 **Stylohyoid muscle**
33 External carotid artery
34 Retromandibular vein
35 Superior thyroid artery
36 Inferior constrictor muscle of the pharynx
37 Sternocleidomastoid muscle
38 Omohyoid muscle
39 Common carotid artery and vagus nerve



Dissection of deep facial and retromandibular regions after removal of mandible. Pterygoid muscles removed, temporalis muscle fenestrated.



Transverse section through oral cavity and pharynx. The location of inferior alveolar nerve and artery is indicated by a needle.

1 Superficial temporal artery and vein and auriculotemporal nerve
2 Temporalis tendon, deep temporal nerves and artery
3 **Maxillary artery**
4 Middle meningeal artery
5 Occipital artery
6 Inferior alveolar artery and nerve
7 Posterior belly of digastric muscle
8 Great auricular nerve and sternocleidomastoid muscle
9 Hypoglossal nerve and superior root of ansa cervicalis
10 **External carotid artery**
11 Supratrochlear nerve and medial branch of supraorbital artery
12 Angular artery
13 Posterior superior alveolar artery
14 Infraorbital nerve
15 **Facial artery**
16 Parotid duct (divided) and buccinator muscle
17 Buccal artery and nerve



Para- and retropharyngeal regions. The mandible and the lateral wall of the orbit have been removed. The main branches of the trigeminal nerve and its ganglion are displayed.

18 Mylohyoid nerve
19 **Lingual nerve** and **submandibular ganglion**
20 Mental nerve and mental foramen
21 Inferior alveolar nerve
22 Mylohyoid muscle (divided) and hypoglossal nerve
23 Submental artery and vein
24 Submandibular gland
25 Superior thyroid artery
26 Common carotid artery
27 Buccinator muscle
28 Masseter muscle and mandible
29 Entrance of mandibular canal
30 Medial pterygoid muscle
31 Palatine tonsil
32 Oral vestibule
33 Tongue
34 Inferior alveolar nerve, artery and vein
35 Paryngeal constrictor muscle

36 Pharynx
37 Tentorium of cerebellum
38 **Trigeminal nerve** and **ganglion**
39 **Mandibular nerve**
40 Superficial temporal artery
41 Auriculotemporal nerve and middle meningeal artery
42 Facial nerve (divided)
43 Masseter muscle
44 Superior root of ansa cervicalis
45 Lateral branch of supraorbital nerve
46 **Ophthalmic nerve**
47 Lacrimal gland
48 Ciliary ganglion and short ciliary nerves
49 Angular artery
50 Inferior branch of oculomotor nerve
51 **Maxillary nerve**
52 Infraorbital nerve
53 Anterior superior alveolar nerve
54 Posterior superior alveolar nerve



Retropharyngeal and sublingual regions. The mandible has been completely removed.

1 Parietal branch of superficial temporal artery
2 Auriculotemporal nerve
3 Temporalis muscle tendon and zygomatic arch (cut)
4 Mandibular nerve (n. V_3)
5 Middle meningeal artery
6 Chorda tympani
7 Mylohyoid nerve
8 Inferior alveolar nerve
9 **Lingual nerve**
10 Posterior auricular artery
11 Facial nerve
12 Styloglossus muscle (cut)
13 Great auricular nerve
14 Maxillary artery, external carotid artery, and stylopharyngeus muscle
15 Posterior belly of digastric muscle
16 Styloid process and facial artery
17 Vagus nerve (n. X)
18 **Accessory nerve** (n. XI)
19 Hypoglossal nerve (n. XII) and retromandibular vein (cut)
20 Stylohyoid muscle and glossopharyngeal nerve (n. IX)
21 Facial vein
22 Hypoglossal nerve (n. XII) and hyoglossus muscle
23 Superior thyroid artery
24 Superior laryngeal artery and internal laryngeal nerve
25 Internal jugular vein
26 Common carotid artery and superior root of ansa cervicalis
27 Inferior pharyngeal constrictor muscle
28 Middle temporal artery
29 Deep temporal nerves and posterior deep temporal artery
30 Anterior deep temporal artery
31 Masseteric nerve
32 Posterior superior alveolar branches of maxillary artery and nerve
33 Pterygoid branches of mandibular nerve
34 Posterior superior alveolar artery
35 Lateral pterygoid plate and medial pterygoid muscle
36 Infraorbital nerve and artery
37 Buccal nerve
38 Facial artery
39 Parotid duct



Nerves and blood vessels of the scalp. Scalp and meninges are demonstrated by a series of window-like openings.

1 Skin
2 **Galea aponeurotica**
3 Pericranium (periosteum)
4 Skull with diploe
5 **Dura mater**
6 Subdural space
7 **Arachnoid mater**
8 **Subarachnoid space**
9 Arachnoid granulations
10 Superior sagittal sinus
11 **Pia mater** with cerebral vessels
12 Falx cerebri
13 Cerebral cortex
14 Arachnoid and pia mater with cortical vessels
15 Frontal belly of occipitofrontal muscle
16 Branch of middle meningeal artery
17 Lateral and medial branch of supraorbital nerve
18 Orbicularis oculi muscle
19 Zygomatico-orbital artery
20 **Auriculotemporal nerve, superficial temporal artery** and **vein**
21 Superior auricular muscle
22 Occipital belly of occipitofrontalis muscle
23 Branches of **greater occipital nerve**
24 **Occipital artery** and **vein**
25 Greater occipital nerve
26 Sternocleidomastoid muscle



A coronal **section through the vertex of the skull** showing the arrangement of the meninges and vessels of the brain. Together the arachnoid mater and the pia mater form the leptomeninx.



Cross-section of the scalp and the meninges. The subarachnoid space is shown.

40 Levator veli palatini muscle
41 Gingiva and buccinator muscle
42 Ascending pharyngeal artery and superior pharyngeal constrictor muscle (pterygopharyngeal part)
43 Lingual nerve
44 **Submandibular ganglion** and tongue
45 Palatoglossus muscle
46 Deep lingual artery

47 Submandibular duct and genioglossus muscle
48 Geniohyoid nerve and muscle
49 Mylohyoid muscle
50 Anterior belly of digastric muscle
51 Hyoid bone
52 Thyrohyoid muscle
53 Omohyoid muscle (superior belly)
54 Sternohyoid muscle
55 **Maxillary artery**



Median sagittal section through the head and neck.

1 Falx cerebri
2 **Corpus callosum** and **septum pellucidum**
3 Interventricular foramen and fornix
4 Choroid plexus of third ventricle and internal cerebral vein
5 **Third ventricle** and interthalamic adhesion
6 **Pineal body** and **colliculi of the midbrain**
7 Cerebral aqueduct
8 Mamillary body and basilar artery
9 Straight sinus
10 **Fourth ventricle** and **cerebellum**
11 Pons and falx cerebelli
12 **Medulla oblongata**
13 Central canal
14 **Cerebellomedullary cistern**
15 Dens of the axis (odontoid process)
16 Spinal cord
17 **Superior sagittal sinus**
18 **Anterior cerebral artery**
19 Anterior commissure
20 **Frontal sinus**
21 Crista galli
22 Optic chiasma
23 Pituitary gland (hypophysis)
24 Superior nasal concha
25 **Middle nasal concha** and **sphenoid sinus**
26 **Inferior nasal concha**
27 **Pharyngeal opening of auditory tube**
28 Superior longitudinal muscle of tongue
29 Vertical muscle of the tongue
30 **Uvula**
31 Genioglossus muscle
32 Pharynx
33 **Epiglottis**
34 Geniohyoid muscle
35 Mylohyoid muscle
36 Hyoid bone
37 Vocal fold and sinus of larynx
38 Esophagus



Dura mater and venous sinuses of the dura mater. The brain has been removed (oblique lateral aspect).

1 Falx cerebri
2 Position of middle meningeal artery and vein
3 Internal carotid artery
4 **Optic nerves** (n. II)
5 Frontal sinus
6 **Oculomotor nerve** (n. III)
7 Diploe
8 **Dura mater**
9 Superior sagittal sinus
10 Straight sinus
11 **Trigeminal nerve** (n. V)
12 Facial and vestibulocochlear nerve (n. VII and n. VIII)
13 **Tentorium cerebelli**
14 **Pituitary gland (hypophysis)**
15 Inferior sagittal sinus
16 Sigmoid sinus
17 Confluence of sinuses
18 Inferior petrosal sinus
19 Transverse sinus
20 Superior petrosal sinus
21 **Cavernous** and **intercavernous sinuses**



Dura mater and **venous sinuses** (left lateral aspect). (Schematic drawing.)



1. **Cranial cavity** with dura mater (the right cerebral hemisphere has been removed)
2. Frontal sinus
3. Hypophysial fossa with pituitary gland
4. Sphenoidal sinus
5. **Nasal cavity**
6. Soft palate (uvula)
7. **Oral cavity**
8. Tongue
9. Skin
10. Calvaria
11. Dura mater
12. Tentorium cerebelli
13. Confluence of sinuses
14. **Infratentorial space** (cerebellum and part of the brain stem have been removed)
15. Vertebral canal
16. Frontal branch of middle meningeal artery and veins
17. Middle meningeal artery
18. **Diploe**
19. Parietal branch of middle meningeal artery and vein
20. Occipital pole of left hemisphere covered with dura mater

Median section through the head. Demonstration of dura mater covering the cranial cavity. Brain and spinal cord are removed (right half of the head, as seen from medial).



Dissection of dura mater and meningeal vessels. Left half of calvaria removed.



1	Calvaria and skin of the scalp
2	Dura mater (divided)
3	Position of lateral sulcus
4	**Frontal lobe** covered by **arachnoid** and **pia mater**
5	Frontal sinus
6	Olfactory bulb
7	**Sphenoidal sinus**
8	Dura mater on clivus and basilar artery
9	Atlas (anterior arch, divided)
10	**Soft palate**
11	Tongue
12	Epiglottis
13	Vocal fold
14	Position of central sulcus
15	Superior cerebral veins
16	Tentorium (divided)
17	**Cerebellum**
18	Cerebellomedullary cistern
19	Position of foramen magnum and **spinal cord**
20	Dens of axis
21	Intervertebral disc

Dissection of the brain with pia mater and arachnoid in situ. The head is cut in half except for the brain, which is shown in its entirety.



1	Superior cerebral veins
2	Position of central sulcus
3	Position of lateral sulcus and **cistern of lateral cerebral fossa**
4	**Frontal pole**
5	Lateral sulcus (arrow)
6	**Temporal pole**
7	Pons and basilar artery
8	Vertebral arteries
9	Superior anastomotic vein
10	Occipital pole
11	Inferior cerebral veins
12	Hemisphere of **cerebellum**
13	Medulla oblongata

Brain with pia mater and arachnoid. Frontal pole to the left (lateral aspect).


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18

Brain and brain stem, median section. Frontal pole to the right.

1 Parietal lobe
2 Thalamus, **third ventricle** and intermediate mass
3 Great cerebral vein
4 **Occipital lobe**
5 Colliculi of the **midbrain** and **cerebral aqueduct**
6 Cerebellum
7 **Medulla oblongata**
8 Central sulcus
9 **Corpus callosum**
10 **Frontal lobe**
11 Fornix and anterior commissure
12 **Hypothalamus**
13 Optic chiasma
14 Midbrain
15 Temporal lobe
16 **Pons**
17 **Fourth ventricle**
18 Spinal cord
19 Inferior concha and nasal cavity
20 Alveolar process of maxilla
21 Tongue
22 Dens of axis
23 Oral part of pharynx
24 Alveolar process of mandible
25 Epiglottis


1
2
4
5
6
7
18
10
9
11
13
14
16
17
19
20
21
22
23
24
25

Median section through the head. (MR-Scan, cf. section on opposite page.)



1 Frontal lobe of cerebrum
2 Occipital lobe of cerebrum
3 **Corpus callosum**
4 Anterior commissure
5 **Lamina terminalis**
6 Optic chiasma
7 **Hypothalamus**
8 Thalamus and third ventricle
9 **Colliculi of the midbrain**
10 Midbrain (inferior portion)
11 **Cerebellum**
12 Pons
13 **Fourth ventricle**
14 Medulla oblongata
15 Central canal
16 **Spinal cord**

Median section through the head. Regions of the brain. Falx cerebri removed.



Scheme of brain divisions (cf. table).
Red = choroidal plexus. (Schematic drawing.)
1 Telencephalon (yellow) with lateral ventricles
2 Diencephalon (orange) with III ventricle, optic nerve and retina
3 Mesencephalon (blue) with cerebral aqueduct
4 Metencephalon (green) with IV ventricle
5 Myelencephalon (yellow-green)

I. Prosencephalon (forebrain)	1. Telencephalon (cerebral hemispheres, striatum, etc.)
	2. Diencephalon (thalamus, metathalamus, hypothalamus, etc.)
II. Mesencephalon (midbrain)	3. Mesencephalon (colliculi, cerebral peduncles, tegmentum)
III. Rhombencephalon (hindbrain)	4. Metencephalon (pons, cerebellum)
	5. Myelencephalon (medulla oblongata)

Main divisions of the brain
I-III = primary brain vesicles; 1-5 = secondary brain vesicles

Midbrain, pons and medulla oblongata are collectively termed the **brain stem.**



1 Superior cerebral veins and parietal lobe
2 Frontal lobe
3 Superficial middle cerebral vein and **cistern of lateral cerebral fossa**
4 Temporal lobe
5 Occipital lobe
6 Inferior cerebral veins and transverse occipital sulcus
7 Inferior anastomotic vein
8 Cerebellum
9 Medulla oblongata

Brain with pia mater. Cerebral veins (bluish). In the lateral sulcus the cistern of the lateral fossa is recognizable. Frontal lobe to the left.





Arteries of the brain. Coronal section. Areas supplied by cortical and central arteries. Dotted lines indicate boundaries of arterial supply areas; arrows: direction of blood flow.

◁

Coronal section through the right hemisphere showing arachnoid, pia mater, and the arterial blood supply (anterior aspect).

1 **Anterior cerebral artery**
2 **Middle cerebral arteries**
3 Arachnoid
4 Cortex
5 **Internal carotid artery**
6 Frontal lobe (white matter)
7 **Posterior cerebral artery**
8 Caudate nucleus
9 Internal capsule
10 Insular lobe
11 Claustrum
12 Putamen
13 Posterior striate branch
14 Insular artery
15 Pallidostriate artery
16 Thalamic artery
17 Corpus callosum
18 Pellucid septum
19 Lateral ventricle
20 Optic chiasm



1 Insula
2 **Middle cerebral artery** [2 branches:
a) Parietal branches,
b) Temporal branches]
3 Basilar artery
4 **Vertebral artery**
5 Central sulcus
6 Occipital lobe
7 Superior cerebellar artery
8 Cerebellum
9 **Anterior cerebral artery**
10 Ethmoidal arteries
11 Ophthalmic artery
12 **Internal carotid artery**
13 Posterior communicating artery
14 **Posterior cerebral artery**
15 Anterior inferior cerebellar artery
16 Posterior inferior cerebellar artery

Cerebral arteries. Lateral aspect of the left hemisphere. The upper part of the temporal lobe has been removed to display the insula and cerebral arteries.



Arteries of the brain.



1 Interventricular foramen
2 Septum pellucidum
3 Frontal lobe
4 **Anterior cerebral artery**
5 Anterior commissure
6 Optic chiasma and infundibulum
7 Mamillary body
8 Oculomotor nerve (n. III)
9 Pons
10 **Basilar artery**
11 Corpus callosum
12 **Fornix**
13 **Choroid plexus**
14 **Third ventricle**
15 Pineal body
16 **Tectum** and **cerebral aqueduct**
17 **Fourth ventricle**
18 Cerebellum (arbor vitae, vermis)
19 Median aperture of Magendie
20 Medulla oblongata

Median section through the brain and brain stem. Cerebral arteries injected with red resin.



1 Anterior communicating artery
2 Left **anterior cerebral artery**
3 **Internal carotid artery**
4 Pons and left **superior cerebellar artery**
5 **Anterior inferior cerebellar artery**
6 **Posterior inferior cerebellar artery**
7 Medulla oblongata
8 **Right anterior cerebral artery**
9 Olfactory tract
10 Optic nerve
11 **Middle cerebral artery**
12 Infundibulum
13 Oculomotor nerve and **posterior communicating artery**
14 **Posterior cerebral artery**
15 **Basilar artery** and abducens nerve (n. VI)
16 Anterior spinal artery
17 **Vertebral artery**
18 Cerebellum
19 Labyrinthine arteries
20 Posterior spinal artery
21 Right **superior cerebellar artery**
22 Olfactory bulb

Arteries of the brain (inferior aspect). Frontal pole above; right temporal lobe and cerebellum partly removed.



Arteries of the base of the brain, arterial circle of Willis. (Schematic drawing.)



Base of the cranial cavity (internal aspect). Left tentorium has been cut.

1 Anterior cerebral artery
2 Anterior communicating artery
3 **Middle cerebral artery**
4 Posterior communicating artery
5 **Oculomotor nerve**
6 **Trochlear nerve**
7 Posterior cerebral artery
8 **Trigeminal nerve**
9 Internal auditory artery
10 **Facial nerve** and **vestibulocochlear nerve**
11 **Glossopharyngeal nerve** and **vagus nerve**
12 **Hypoglossal nerve**
13 **Accessory nerve**
14 Anterior inferior cerebellar artery
15 Falx cerebri
16 **Optic nerve**
17 Optic chiasma
18 Infundibulum and pituitary gland
19 Anterior choroidal artery and choroid plexus
20 **Basilar artery**
21 **Abducens nerve**
22 Vertebral arteries
23 Medulla oblongata
24 Inferior sagittal sinus
25 Tentorium cerebelli
26 Superior sagittal sinus and confluence of sinuses
27 Anterior spinal artery
28 Internal carotid artery
29 Superior cerebellar artery
30 Anterior inferior cerebellar artery
31 Posterior inferior cerebellar artery
32 Posterior spinal artery
33 Ophthalmic artery



Arterial circle of Willis (superior aspect).
(Schematic drawing.)



Brain, left hemisphere (lateral aspect). Frontal pole to the left.

1 Central sulcus
2 Precentral gyrus
3 Precentral sulcus
4 **Frontal lobe**
5 Anterior ascending ramus of lateral sulcus
6 Anterior horizontal ramus of lateral sulcus
7 Lateral sulcus
8 **Temporal lobe**
9 **Parietal lobe**
10 Postcentral gyrus
11 Postcentral sulcus
12 **Occipital lobe**
13 Cerebellum
14 Superior frontal sulcus
15 Middle frontal gyrus
16 Lunate sulcus
17 Longitudinal fissure
18 Arachnoid granulations



Brain (superior aspect). Right hemisphere with arachnoid and pia mater.

Pink = Frontal lobe
Blue = Parietal lobe
Green = Occipital lobe
Yellow = Temporal lobe
Dark red = Precentral gyrus
Dark blue = Postcentral gyrus



Brain (superior aspect). Lobes of the left hemisphere indicated by color; right hemisphere is covered with arachnoid and pia mater.



1 Premotor area
2 Somatomotor area
3 Motor speech area of Broca
4 Acoustic area
(red: high tone; blue: low tone)
5 Somatosensory area
6 Sensory speech area of Wernicke
7 Reading comprehension area
8 Visuosensory area

Brain, left hemisphere (lateral aspect). **Main cortical areas** are colored. The lateral sulcus has been opened to display the insula and the inner surface of the temporal lobe.



1	Precentral gyrus	
2	Precentral sulcus	
3	Superior frontal gyrus	
4	**Central sulcus**	
5	Middle frontal gyrus	
6	Inferior frontal gyrus	
7	Ascending ramus	of lateral sulcus
8	Horizontal ramus	
9	Posterior ramus	
10	Superior temporal gyrus	
11	Middle temporal gyrus	
12	Inferior temporal gyrus	
13	Parietal lobule	
14	Postcentral sulcus	
15	Postcentral gyrus	
16	Supramarginal gyrus	
17	Angular gyrus	
18	**Occipital lobe**	
19	**Cerebellum**	
20	Horizontal fissure of cerebellum	
21	Medulla oblongata	

Brain, left hemisphere (lateral aspect). Frontal pole to the left.



Brain, right hemisphere (medial aspect). Frontal pole to the left (midbrain divided, cerebellum and inferior part of brainstem removed).



Brain (inferior aspect). Midbrain divided. Cerebellum and inferior part of brain stem removed. Frontal pole at the top.

1 **Precentral gyrus**
2 Precentral sulcus
3 Cingulate sulcus
4 **Cingulate gyrus**
5 Sulcus of corpus callosum
6 **Fornix**
7 Genu of **corpus callosum**
8 Interventricular foramen
9 Intermediate mass
10 Anterior commissure
11 **Optic chiasma**
12 **Infundibulum**
13 Uncus hippocampi
14 **Postcentral gyrus**
15 Body of corpus callosum
16 Third ventricle and thalamus
17 Stria medullaris
18 **Parietooccipital sulcus**
19 Splenium of corpus callosum
20 Communication of calcarine and parietooccipital sulcus
21 Calcarine sulcus
22 **Pineal body**
23 **Mamillary body**
24 **Parahippocampal gyrus**
25 **Olfactory bulb**
26 Olfactory tract
27 Gyrus rectus
28 **Optic nerve**
29 Infundibulum and optic chiasma
30 **Optic tract**
31 Oculomotor nerve
32 Pedunculus cerebri
33 **Red nucleus**
34 **Cerebral aqueduct**
35 Corpus callosum
36 Longitudinal fissure
37 Orbital gyri
38 Lateral root of olfactory tract
39 Medial root of olfactory tract
40 Olfactory tubercle and anterior perforated substance
41 Tuber cinereum
42 Interpeduncular fossa
43 **Substantia nigra**
44 Colliculi of the **midbrain**
45 Lateral occipitotemporal gyrus
46 Medial occipitotemporal gyrus

Pink = Frontal lobe
Blue = Parietal lobe
Green = Occipital lobe
Yellow = Temporal lobe
Dark red = Precentral lobe
Dark blue = Postcentral lobe
Orange = Limbic cortex (cingulate and parahippocampal gyri)



Brain (sagittal section). Frontal pole to the left.



Brain, with pia mater and blood vessels (inferior aspect).

1 Precentral gyrus
2 Cingulate gyrus
3 Cingulate sulcus
4 Septum pellucidum
5 Genu of corpus callosum
6 Fornix
7 **Frontal lobe**
8 Anterior commissure
9 **Hypothalamus**
10 Optic chiasma
11 Infundibulum
12 Oculomotor nerve
13 Uncus
14 **Temporal lobe**
15 Pons
16 Central sulcus
17 Postcentral gyrus
18 Body of corpus callosum
19 Interventricular foramen (arrow)
20 Parietooccipital sulcus
21 Intermediate mass
22 Splenium of corpus callosum
23 Pineal body
24 Calcarine sulcus
25 Colliculi of midbrain
26 Cerebral aqueduct
27 **Occipital lobe**
28 Mamillary body
29 Fourth ventricle
30 Vermis of cerebellum
31 Right hemisphere of cerebellum
32 Median aperture of Magendie (arrow)
33 Medulla oblongata
34 Olfactory tract
35 Optic nerve
36 **Internal carotid artery**
37 Interpeduncular cistern
38 Superior cerebellar artery
39 Anterior inferior cerebellar artery
40 **Vertebral artery**
41 Posterior inferior cerebellar artery
42 **Basilar artery**
43 Trigeminal nerve (n. V)
44 Facial nerve (n. VII)
45 Accessory nerve (n. XI), hypoglossal nerve (n. XII)
46 Cerebellum



Cerebellum (inferior anterior aspect). The cerebellar peduncles have been severed.



Cerebellum (inferior posterior aspect).



Median section through the cerebellum. Right cerebellar hemisphere and right half of vermis.

1 Superior cerebellar peduncle
2 Middle cerebellar peduncle
3 Cerebellar tonsil
4 Inferior semilunar lobule
5 **Vermis**
6 Central lobule of vermis
7 Inferior cerebellar peduncle
8 Superior medullary velum
9 **Nodule of vermis**
10 **Flocculus**
11 Biventral lobule
12 Left cerebellar hemisphere
13 Inferior semilunar lobule
14 Biventral lobule
15 Vermis of cerebellum
16 Tuber of vermis
17 Pyramid of vermis
18 Uvula of vermis
19 Tonsil of cerebellum
20 Floccule of cerebellum
21 Right cerebellar hemisphere
22 Vermis (central lobule)
23 Cerebellar lingula
24 Ala of central lobule
25 **Superior cerebellar peduncle**
26 Fastigium
27 **Fourth ventricle**
28 **Middle cerebellar peduncle**
29 Nodule of vermis
30 Flocculus of cerebellum
31 Cerebellar tonsil
32 Culmen of vermis
33 Declive of vermis
34 Tuber of vermis
35 Inferior semilunar lobule
36 Pyramis of vermis
37 Uvula of vermis



Brain and cerebellum (inferior aspect). Parts of the cerebellum have been removed to display the dentate nucleus and the main pathway to the midbrain (cerebellorubral tract).



Dissection of the cerebellar peduncles and their connection with midbrain and diencephalon. A small part of pulvinar thalami (*) has been cut to show inferior brachium.

1 Olfactory bulb
2 **Olfactory tract**
3 Lateral olfactory stria
4 Anterior perforated substance
5 Infundibulum (divided)
6 **Mamillary body**
7 Substantia nigra
8 Pedunculus cerebri
9 **Red nucleus**
10 Decussation of superior cerebellar peduncle
11 **Cerebellar hemisphere**
12 Medial olfactory stria
13 **Optic nerve**
14 Optic chiasma
15 Optic tract
16 Posterior perforated substance
17 Interpeduncular fossa
18 **Superior cerebellar peduncle** and cerebellorubral tract
19 **Dentate nucleus**
20 **Vermis of cerebellum**
21 Cingulate gyrus
22 **Corpus callosum**
23 Stria terminalis
24 Septum pellucidum
25 **Columna fornicis**
26 Cerebral peduncle at midbrain level
27 Pons
28 Inferior olive
29 Medulla oblongata with lateral pyramidal tract
30 Occipital lobe
31 Calcarine sulcus
32 **Thalamus**
33 Inferior colliculus with brachium
34 **Medial lemniscus**
35 **Superior cerebellar peduncle**
36 **Inferior cerebellar peduncle**
37 **Middle cerebellar peduncle**
38 Cerebellar hemisphere



1 Lateral longitudinal stria of indusium griseum
2 Medial longitudinal stria of indusium griseum
3 Cerebellum
4 Radiating fibers of the corpus callosum
5 Forceps minor of corpus callosum
6 Forceps major of corpus callosum
7 Splenium of corpus callosum

Dissection of the brain I. The fiber system of the corpus callosum has been displayed by removing the cortex lying above it. Frontal pole at top.



1 Longitudinal cerebral fissure
2 Genu of corpus callosum
3 Head of **caudate nucleus** and anterior horn of lateral ventricle
4 Cavum of septum pellucidum
5 **Septum pellucidum**
6 Stria terminalis
7 **Choroid plexus** of **lateral ventricle**
8 Splenium of **corpus callosum**
9 Calcar avis
10 Posterior horn of lateral ventricle
11 **Thalamus** (lamina affixa)
12 Commissure of fornix
13 Vermis of cerebellum

Dissection of the brain II. The lateral ventricles and subcortical nuclei of the brain are dissected. The corpus callosum has been partly removed. Frontal pole at the top.



Dissection of the brain III (superior view of lateral ventricle and subcortical nuclei of the brain). Corpus callosum partly removed. At right, the entire lateral ventricle has been opened, the insula with claustrum, extreme and external capsules have been removed, exposing the lentiform nucleus and the internal capsule.

1 Lateral longitudinal stria
2 Medial longitudinal stria
3 Genu of corpus callosum
4 Head of **caudate nucleus**
5 **Septum pellucidum**
6 Stria terminalis
7 **Thalamus** (lamina affixa)
8 Choroid plexus of third ventricle
9 **Choroid plexus** of **lateral ventricle**
10 Splenium of corpus callosum
11 Posterior horn of lateral ventricle
12 Anterior horn of lateral ventricle (head of caudate nucleus)
13 **Putamen** of **lentiform nucleus**
14 **Internal capsule**
15 Inferior horn of lateral ventricle
16 **Pes hippocampi**
17 **Crus of fornix**
18 Vermis of cerebellum with arachnoid and pia mater
19 Interventricular foramen
20 Right column of fornix
21 Collateral eminence



1	Lateral longitudinal stria
2	Medial longitudinal stria
3	**Corpus callosum**
4	Septum pellucidum
5	Insular gyri
6	Thalamostriate vein
7	Anterior tubercle of thalamus
8	**Thalamus**
9	Medullary stria of thalamus
10	Habenular trigone
11	Habenular commissure
12	**Vermis of the cerebellum**
13	Left **hemisphere of cerebellum**
14	**Head of caudate nucleus**
15	**Columns of fornix**
16	Putamen of lentiform nucleus
17	**Internal capsule**
18	Taenia of choroid plexus
19	Stria terminalis and thalamostriate vein
20	Lamina affixa
21	**Third ventricle**
22	**Pineal body**
23	Superior and inferior colliculus of midbrain

Dissection of the brain IVa. Temporal lobe, fornix and the posterior corpus callosum have been removed (this part of the specimen is depicted below). Frontal pole at top (superior aspect).



1	Inferior horn of lateral ventricle
2	**Hippocampal digitations**
3	Collateral eminence
4	Splenium of corpus callosum
5	Calcar avis
6	Posterior horn of lateral ventricle
7	**Uncus** of parahippocampal gyrus
8	Body and crus of **fornix**
9	**Parahippocampal gyrus**
10	**Pes hippocampi**
11	Dentate gyrus
12	Hippocampal fimbria
13	Lateral ventricle

Dissection of the brain IV b. Depicted is the portion of the brain removed from the specimen above. **Temporal lobe and limbic system** (superior aspect). Columns of fornix are served.



Dissection of the limbic system. Left side, lateral aspect. Corpus callosum has been cut in the median plane. The left thalamus and the left hemisphere have been partly removed.



Main pathways of **limbic and olfactory system.** (Schematic drawing.) Blue = afferent pathways; red = efferent pathways.

1 **Body of fornix**
2 Septum pellucidum
3 **Lateral longitudinal stria**
4 Genu of corpus callosum
5 **Column of fornix**
6 Medial olfactory stria
7 **Olfactory bulb** and **olfactory tract**
8 Optic nerve
9 Anterior commissure (left half)
10 Right temporal lobe
11 **Lateral olfactory stria**
12 **Amygdala**
13 Body of **corpus callosum**
14 Interthalamic adhesion
15 Third ventricle and right thalamus
16 **Mamillothalamic tract**
17 Part of the thalamus
18 Habenular commissure
19 Pineal body
20 Splenium of corpus callosum
21 Colliculi of midbrain
22 Vermis of cerebellum
23 **Stria terminalis**
24 **Mamillary body**
25 Fimbria of hippocampus and pes hippocampi
26 Left optic tract and lateral geniculate body
27 Lateral ventricle and **parahippocampal gyrus**
28 Collateral eminence
29 Hippocampal digitations
30 **Supracallosal gyrus** (longitudinal stria)
31 Stria medullaris thalami
32 Thalamus
33 Red nucleus
34 Mamillotegmental tract
35 Dorsal longitudinal fasciculus (Schütz)



Median section through the diencephalon. Medial part of the thalamus and septum pellucidum have been removed to show the fornix and mamillothalamic tract.

1 Paraventricular nucleus
2 Preoptic nucleus
3 Ventromedial nucleus
4 Supraoptic nucleus
5 Posterior nucleus
6 Dorsomedial nucleus
} **Hypothalamic nuclei**
7 **Mamillary body**
8 **Corpus callosum**
9 Lateral ventricle (showing caudate nucleus)
10 Anterior commissure
11 **Column of fornix**
12 Optic chiasma
13 **Crus of fornix**
14 Medullary stria of thalamus
15 Thalamus and interthalamic adhesion
16 **Mamillothalamic tract** of Vicq d'Azyr
17 Cerebral peduncle
18 **Pineal body**
19 Tectum of midbrain
20 Lamina terminalis



Median section through the diencephalon and midbrain; location of hypothalamic nuclei.



Position of main hypothalamic nuclei. (Schematic diagram.)

1 Circular sulcus of insula
2 Long gyrus of insula
3 Short gyri of insula
4 Limen insulae
5 Opercula (cut)
  a Frontal operculum
  b Frontoparietal operculum
  c Temporal operculum
6 **Corona radiata**
7 **Lentiform nucleus**
8 **Anterior commissure**
9 Olfactory tract
10 Cerebral arcuate fibers
11 Optic radiation
12 Cerebral peduncle
13 Trigeminal nerve (n. V)
14 Flocculus of cerebellum
15 **Pyramidal tract**
16 Decussation of pyramidal tract
17 Internal capsule
18 Optic tract
19 Optic nerve (n. II)
20 Infundibulum
21 Temporal lobe (right side)
22 Mamillary bodies
23 Oculomotor nerve (n. III)
24 Transverse fibers of pons



Insula (Reili). The opercula of the frontal, parietal and temporal lobes have been removed to display the insular gyri. Left hemisphere.



Dissection of the corona radiata, left hemisphere. Frontal pole on the left.



◁ **Corona radiata and internal capsule,** left hemisphere. Lentiform nucleus removed (frontal pole to the left).



Dissection of the subcortical nuclei and internal capsule, left hemisphere (lateral aspect). Frontal pole to the left. The lateral ventricle has been opened, and the insular gyri and claustrum have been removed, revealing the lentiform nucleus and the internal capsule.

1 Corona radiata
2 Anterior horn of lateral ventricle
3 Head of **caudate nucleus**
4 **Putamen**
5 Anterior commissure
6 Olfactory tract
7 **Amygdala**
8 Hippocampal digitations
9 **Internal capsule**
10 Calcar avis
11 Posterior horn of lateral ventricle
12 Choroid plexus of lateral ventricle
13 Caudal extremity of caudate nucleus
14 **Thalamus**
15 Cerebral arcuate fibers
16 Globus pallidus (remnants)



Dissection of the subcortical nuclei (lateral aspect). Lentiform nucleus removed, frontal pole to the left.



Brain stem and the connections with the cerebellum. Internal capsule (lateral aspect). Red = pyramidal tract; yellow = middle cerebellar peduncle; green = inferior cerebellar peduncle; pink = superior cerebellar peduncle.



Internal capsule and subcortical nuclei. Left brain, frontal pole to the left, horizontal section. (Semischematic drawing.) Blue = afferent tracts; red = efferent tracts.

1 **Putamen**
2 Genu of corpus callosum
3 Anterior cerebral artery
4 Anterior commissure
5 Subcallosal area
6 Amygdala
7 Olfactory tract
8 Optic nerve (n. II)
9 Internal carotid artery and infundibulum
10 Oculomotor nerve (right and left nerve, n. III)
11 **Basilar artery**
12 Pons and trigeminal nerve (n. V)
13 Abducens nerve (n. VI)
14 Facial nerve (n. VII)
15 Vestibulocochlear nerve (n. VIII)
16 Hypoglossal nerve (n. XII)
17 Olive
18 Pyramidal tract
19 **Internal capsule**
20 Posterior cerebral artery
21 Cerebral peduncle
22 **Colliculi of midbrain**
23 Trochlear nerve (n. IV)
24 Superior cerebellar peduncle
25 Inferior cerebellar peduncle
26 **Middle cerebellar peduncle**
27 Glossopharyngeal nerve (n. IX)
28 Vagus (n. X) and accessory nerves (n. XI)
29 **Corpus callosum**
30 Lateral ventricle (anterior horn)
31 Caudate nucleus
32 Internal capsule (anterior limb)
33 Insula
34 **Claustrum**
35 **Thalamus**
36 Superior and inferior colliculus of midbrain
37 Cerebellum
38 Middle peduncle of cerebellum (efferent tracts)
39 Medulla oblongata (afferent tracts)
40 Putamen of lentiform nucleus
41 **Globus pallidus** of lentiform nucleus
42 Genu and posterior limb of internal capsule



Cast of ventricular cavities of the brain (lateral aspect), frontal pole to the left.

1 Central part of the **lateral ventricle**
2 **Interventricular foramen** of Monro
3 Anterior horn of the lateral ventricle
4 Site of interthalamic adhesion
5 Notch for anterior commissure
6 **Third ventricle**
7 Optic recess
8 Notch for optic chiasma
9 Infundibular recess
10 Inferior horn of lateral ventricle with indentation of amygdaloid body
11 Lateral recess and lateral aperture of Luschka
12 Suprapineal recess
13 Pineal recess
14 Notch for posterior commissure
15 Posterior horn of lateral ventricle
16 **Cerebral aqueduct**
17 **Fourth ventricle**
18 Median aperture of Magendie
19 **Cerebellomedullary cistern**
20 Superior sagittal sinus
21 Inferior sagittal sinus
22 Intervaginal space of optic nerve
23 Arachnoid granulations of Pacchioni
24 Straight sinus



◁ **Position of ventricular cavities.** (Schematic drawing.)
The direction of flow of cerebrospinal fluid is indicated by arrows.
Green = Right lateral ventricle
Red = Choroidal plexus



Cast of ventricular cavities (posterior aspect).



Cast of ventricular cavities (superior aspect). Frontal pole at top.



Brain stem (left lateral aspect). Cerebellar peduncles have been severed, cerebellum and cerebral cortex have been removed.



Brain stem (dorsal aspect). Cerebellum removed.

1 **Internal capsule**
2 Head of the caudate nucleus
3 Olfactory trigone
4 Olfactory tracts
5 Optic nerves
6 Infundibulum
7 Oculomotor nerve
8 **Amygdaloid body**
9 **Pons**
10 Trigeminal nerve
11 Facial and vestibulocochlear nerves
12 Hypoglossal nerve
13 Glossopharyngeal and vagus nerves
14 **Olive**
15 Medulla oblongata
16 **Lentiform nucleus**
17 **Anterior commissure**
18 Tail of caudate nucleus
19 Superior colliculus
20 Inferior colliculus
21 Trochlear nerve
22 Superior cerebellar peduncle
23 Inferior cerebellar peduncle
24 **Middle cerebellar peduncle**
25 Accessory nerve (n. XI)
26 Columns of fornix (divided)
27 Lamina affixa
28 **Third ventricle**
29 Pulvinar of thalamus
30 Inferior brachium
31 Frenulum veli
32 Superior medullary velum
33 Facial colliculus
34 Striae medullares and rhomboid fossa
35 Hypoglossal triangle
36 Stria terminalis and thalamostriate vein
37 Habenular trigone
38 Choroid plexus of lateral ventricle
39 **Pineal body**
40 Medial geniculate body
41 Cerebral peduncle
42 Choroid plexus of fourth ventricle
43 Clava
44 Dorsal root of cervical nerve
45 Cuneate tubercle
46 Lateral geniculate body



Coronal section through the brain at the level of the anterior commissure. Section 1.



Coronal section through the brain at the level of the third ventricle and the interthalamic adhesion. Section 2.

1 Corpus callosum
2 Head of **caudate nucleus**
3 **Internal capsule**
4 **Putamen**
5 **Globus pallidus**
6 Anterior commissure
7 Optic tract
8 Amygdaloid body
9 Inferior horn of lateral ventricle
10 **Lateral ventricle**
11 Septum pellucidum
12 Lobus insularis (insula)
13 External capsule
14 Column of fornix
15 Optic recess
16 Infundibulum
17 **Thalamus**
18 Claustrum
19 Lenticular ansa
20 **Third ventricle** and **hypothalamus**
21 Basilar artery and pons
22 Cortex of temporal lobe
23 Inferior colliculus
24 Superior colliculus
25 Cerebral aqueduct
26 Red nucleus
27 Substantia nigra
28 Cerebral peduncle
29 Trochlear nerve (n. IV)
30 Gray matter
31 Nucleus of oculomotor nerve (nucleus of Edinger-Westphal)
32 Fibers of oculomotor nerve (n. III)
33 Vermis of cerebellum
34 Fourth ventricle
35 Reticular formation
36 Pons and transverse pontine fibers
37 Emboliform nucleus
38 Dentate nucleus
39 Middle cerebellar peduncle
40 Choroid plexus
41 Hypoglossal nucleus at rhomboid fossa
42 Medial longitudinal fasciculus
43 Trigeminal nerve (n. V.)
44 Inferior olivary nucleus
45 Corticospinal fibers and arcuate fibers
46 Fourth ventricle with choroid plexus
47 Vestibular nuclei
48 Nucleus and tractus solitarius
49 Inferior cerebellar peduncle (restiform body)
50 Reticular formation
51 Medial lemniscus
52 Cuneate nucleus of Burdach
53 Central canal
54 **Pyramidal tract**
55 Flocculus of cerebellum
56 Cerebellar hemisphere with pia mater
57 "Arbor vitae" of cerebellum
58 Nucleus gracilis of Goll
59 Lateral recess of choroid plexus of IVth ventricle
60 Posterior inferior cerebellar artery
61 Choroid plexus of lateral ventricle


23
24
25
26
27
28
29
30
31
32

Cross-section of the midbrain (mesencephalon) at the level of the superior colliculus (superior aspect). Section 4.


40
41
42
43
44
45
46
47
48
49
50
51

Cross-section of the rhombencephalon at the level of the olive (inferior aspect). Section 6.


33
34
35
36
37
38
39

Cross-section through the rhombencephalon at the level of pons (inferior aspect). Section 5.


33
52
53
54
55
56
57
58
44
59
60
21

Cross-section through medulla oblongata and cerebellum (inferior aspect). Section 7.


1
61
10
61
25
36

Coronal section at the level of **inferior colliculus** (posterior aspect). Section 3.



Right half of the brain. Levels of the sections are indicated.



Horizontal section through the head.
Section 1.



Horizontal section through the head.
Section 2.



MR-Scan of the human head at the level of section 2.

1 Skin of scalp
2 Calvaria (diploe of the skull)
3 **Falx cerebri**
4 Gray matter of brain (cortex)
5 Dura mater
6 **White matter of brain**
7 Arachnoid and pia mater with vessels
8 Subdural space (slightly expanded due to shrinkage of the brain)
9 Superior sagittal sinus
10 Anterior horn of lateral ventricle
11 **Septum pellucidum**
12 Choroid plexus
13 Thalamus
14 Splenium of corpus callosum
15 Parietal lobe
16 Frontal lobe
17 Anterior cerebral artery
18 Genu of corpus callosum
19 Caudate nucleus
20 **Central part of lateral ventricle**
21 Stria terminalis
22 Occipital lobe



Horizontal section through the head at the level of third ventricle of internal capsule and neighbouring nuclei. Section 3.

1 **Caudate nucleus**
2 Lobus insularis (insula)
3 **Lentiform nucleus**
4 Claustrum
5 External capsule
6 Internal capsule
7 **Thalamus**
8 Straight sinus (sinus rectus)
9 Superior sagittal sinus
10 Skin of scalp
11 Falx cerebri
12 Calvaria (diploe of skull)
13 Genu of corpus callosum
14 Anterior horn of lateral ventricle
15 **Septum pellucidum**
16 Column of fornix
17 Choroid plexus of third ventricle
18 Splenium of corpus callosum
19 Entrance to inferior horn of lateral ventricle with choroid plexus
20 Optic radiation
21 **Third ventricle**



MR-Scan at the corresponding level to the above figure. Section 3.



Sagittal section through the head. Levels of the horizontal sections are indicated.



Horizontal section through the brain, showing the subcortical nuclei and internal capsule. Section 1.

1 Genu of corpus callosum
2 **Head of caudate nucleus**
3 **Putamen**
4 **Claustrum**
5 **Globus pallidus**
6 Third ventricle
7 Thalamus
8 **Pineal body**
9 Splenium of corpus callosum
10 Choroid plexus of the lateral ventricle
11 Anterior horn of lateral ventricle
12 Cavity of septum pellucidum
13 **Septum pellucidum**
14 Anterior limb of internal capsule
15 Column of fornix
16 External capsule
17 **Lobus insularis** (insula)
18 Genu of **internal capsule**
19 Posterior limb of internal capsule
20 Posterior horn of lateral ventricle
21 Anterior commissure
22 Optic radiation
23 Falx cerebri
24 **Maxillary sinus**
25 Position of auditory tube
26 Tympanic cavity
27 External acoustic meatus
28 **Medulla oblongata**
29 Fourth ventricle
30 Cerebellum (left hemisphere)
31 Temporomandibular joint
32 Tympanic membrane
33 Base of cochlea
34 Mastoid air cells
35 Sigmoid sinus
36 Vermis of cerebellum
37 Intermediate mass



Horizontal section through the head. Section 2.



Horizontal section through the head. Section 4.



Horizontal section through the head. Section 3.

1 Upper lid (tarsal plate)
2 Lens
3 Ethmoidal sinus
4 **Optic nerve** (n. II)
5 Internal carotid artery
6 Infundibulum and **pituitary gland**
7 Temporal lobe
8 Basilar artery
9 Pons (cross section of brain stem)
10 **Cerebral aqueduct** (beginning of fourth ventricle)
11 Vermis of cerebellum
12 Straight sinus
13 Transverse sinus
14 Nasal septum
15 **Eyeball** (sclera)
16 Nasal cavity
17 Lateral rectus muscle
18 Sphenoidal sinus
19 Oculomotor nerve (n. III)
20 **Tentorium of cerebellum**
21 Skin of scalp
22 Calvaria
23 Occipital lobe
24 Striate cortex (visual cortex)



Horizontal section through the head. (CT-Scan.) Section 3.



Sagittal section through the head.
Levels of the horizontal sections are indicated.



Longitudinal section through the right temporal bone I. The outer and middle ear and auditory ossicles and tube are shown (anterior aspect).



Right **auditory and vestibular apparatus** (anterior aspect). (Schematic drawing.)

Outer ear

1 Auricle
2 Lobule of auricle
3 Helix
4 Tragus
5 External acoustic meatus

Middle ear

6 Tympanic membrane
7 Malleus
8 Incus
9 Stapes
10 Tympanic cavity
11 Mastoid process
12 Auditory tube
13 Tensor tympani muscle

Inner ear

14 Anterior semicircular duct
15 Posterior semicircular duct
16 Lateral semicircular duct
17 Cochlea
18 Vestibulocochlear nerve
19 Petrous part of the temporal bone

Additional structures

20 Superior ligament of malleus
21 Arcuate eminence
22 Internal carotid artery
23 Anterior surface of pyramid with dura mater
24 Stapes
25 Levator veli palatini muscle



Longitudinal section through the right outer, middle and inner ear II. The cochlea and semicircular canals have been further dissected (anterior aspect).



Internal acoustic meatus, left side. The bone was partly removed to show the bottom of the meatus.

1 Roof of tympanic cavity
2 **Lateral osseous semicircular canal**
3 **Facial nerve**
4 Incus
5 **Malleus**
6 External acoustic meatus
7 **Tympanic cavity** and **tympanic membrane**
8 Vestibulochochlear nerve
9 Anterior osseous semicircular canal
10 Geniculate ganglion and greater petrosal nerve
11 **Cochlea**
12 **Stapes**
13 Tensor tympani muscle
14 **Auditory tube**
15 Levator veli palatini muscle
16 Area of facial nerve
17 Superior vestibular area
18 Transverse crest
19 Foramen singulare
20 Foraminous spiral tract (outlet of cochlear part of vestibulocochlear nerve)
21 Base of cochlea



Longitudinal section through the outer, middle and inner ear III. Deeper dissection to display facial nerve and lesser and greater petrosal nerves (anterior aspect).



Right auricle (lateral aspect).

1 Helix
2 Scaphoid fossa
3 Triangular fossa
4 Concha
5 Antihelix
6 Tragus
7 Antitragus
8 Intertragic notch
9 Lobule

1 **Anterior osseous semicircular canal** (opened)
2 **Posterior osseous semicircular canal**
3 **Lateral osseous semicircular canal** (opened)
4 Facial nerve and chorda tympani
5 External acoustic meatus
6 Auricle
7 **Facial nerve**
8 Trigeminal nerve
9 Bony base of internal acoustic meatus
10 Internal carotid artery within cavernous sinus
11 **Cochlea**
12 **Facial nerve** with **geniculate ganglion**
13 Greater petrosal nerve
14 Lesser petrosal nerve
15 **Tympanic cavity**
16 Auditory tube
17 Levator veli palatini muscle
18 Internal carotid artery, internal jugular vein
19 Styloid process



Right temporal bone (lateral aspect). Petrosquamous portion has been partly removed to display the semicircular canals.



Right temporal bone (lateral aspect). Mastoid air cells and facial canal had been opened. The 3 semicircular canals were dissected.



Right temporal bone of the newborn (lateral aspect).



Frontal section through petrous part. (CT-Scan.)

1 Anterior semicircular canal (red)
2 Posterior semicircular canal (yellow)
3 Lateral or horizontal semicircular canal (green)
4 **Fenestra vestibuli**
5 **Fenestra cochleae**
6 Tympanic cavity
7 Mastoid process
8 **Petrotympanic fissure** (red probe: **chorda tympani**)
9 Lateral pterygoid plate
10 Mastoid air cells
11 **Facial canal** (blue)
12 Foramen ovale
13 **Carotid canal** (red)
14 **Tympanic ring**
15 Petromastoid part of temporal bone
16 Squamous part of temporal bone
17 Squamomastoid suture
18 Zygomatic process of temporal bone
19 Incisure of tympanic ring
20 **Promontory**
21 Apex of cochlea (cupula)
22 Spiral canal of cochlea at base of cochlea
23 Epitympanic recess
24 Auditory ossicles and tympanic cavity
25 Hypotympanic recess
26 Canaliculus chordae tympani (green probe)
27 Mastoid process
28 Canaliculus for stapedius nerve (red)
29 **Cochlea**
30 Canaliculus mastoideus (red probe)



1 Head of malleus
2 Anterior ligament of malleus
3 Tendon of tensor tympani muscle
4 Handle of **malleus**
5 Short crus of incus
6 Long crus of **incus**
7 Chorda tympani
8 Lenticular process
9 **Tympanic membrane**

Tympanic membrane with malleus and incus (internal aspect; right side).



1 Tympanic antrum
2 Lateral semicircular canal (opened)
3 **Facial canal**
4 Stapes with tendon of stapedius
5 Mastoid air cells
6 Chorda tympani (intracranial part)
7 Greater petrosal nerve
8 Tensor tympani muscle (processus cochleariformis)
9 Lesser petrosal nerve
10 Anterior tympanic artery
11 Middle meningeal artery
12 **Auditory tube**
13 **Promontory with tympanic plexus**
14 Fenestra cochleae

Tympanic cavity, medial wall. External auditory meatus and lateral wall of tympanic cavity together with incus. Malleus and tympanic membrane have been removed; mastoid air cells are opened (left side).



1 **Tympanic membrane**
2 Chorda tympani (intracranial part)
3 Floor of the external acoustic meatus
4 **Facial nerve** and facial canal
5 Incus
6 Head of malleus
7 Mandibular fossa
8 Spine of sphenoid
9 **Chorda tympani** (extracranial part)
10 Styloid process

Tympanic membrane (lateral aspect). External acoustic meatus and facial canal have been opened to expose the chorda tympani (magn. ~1.5×) (left side).



Frontal section through the petrous part of the left temporal bone at the level of the cochlea (posterior aspect). Position of tympanic membrane indicated by dotted line.



Medial wall of tympanic cavity and its relation to neighboring structures of the inner ear, facial nerve, and blood vessels. (Schematic drawing.) Frontal section through the right temporal bone (anterior aspect).

1 Anterior surface of the pyramid
2 Mastoid antrum
3 Lateral semicircular canal
4 Cochleariform process
5 External acoustic meatus
6 **Jugular fossa**
7 Foramen lacerum
8 Apex of petrous part
9 Position of **cochlea** (modiolus with crista spiralis ossea)
10 Carotid canal
11 Pterygoid process
12 Anterior semicircular duct
13 **Facial nerve**
14 Geniculate ganglion
15 Greater petrosal nerve
16 Lesser petrosal nerve
17 **Internal carotid artery**
18 Mastoid air cells
19 Lateral semicircular duct
20 Posterior semicircular duct
21 Stapes with stapedius muscle
22 Stylomastoid foramen
23 Inferior recess of tympanic cavity (hypotympanon)
24 **Internal jugular vein**
25 Promontory with tympanic plexus (position of cochlea)
26 Tensor muscle of tympanum
27 **Auditory tube**



Tympanic cavity with malleus, incus and stapes, left side (lateral aspect). Tympanic membrane removed, mastoid antrum opened.



Chain of auditory ossicles in connection with the inner ear, left side (anterior-lateral aspect).



Auditory ossicles (isolated).



Position and movements of the auditory ossicles. (Schematic diagram.)

Malleus
1 Head
2 Neck
3 Lateral process
4 Handle

Incus
5 Articular facet for malleus
6 Long crus
7 Short crus
8 Body
9 Lenticular process

Stapes
10 Head
11 Neck
12 Anterior and posterior crura
13 Base

Walls of tympanic cavity
14 Tympanic membrane
15 Promontory
16 Hypotympanic recess of tympanic cavity

Internal ear (labyrinth)
17 Lateral semicircular duct
18 Anterior semicircular duct
19 Posterior semicircular duct
20 Common crus
21 Ampulla
22 Beginning of endolymphatic duct
23 Utricular prominence
24 Saccular prominence
25 Incus
26 Malleus
27 Stapes
28 Cochlea

Tympanic cavity
29 Epitympanic recess
30 Mastoid antrum
31 Chorda tympani
32 Tendon of stapedius muscle
33 Round window (fenestra cochleae)



Cast of the right labyrinth (postero-medial aspect).

1 Ampulla (anterior semicircular canal)
2 Elliptical recess
3 Aqueduct of the vestibule
4 Spherical recess
5 **Cochlea**
6 Base of cochlea
7 **Anterior semicircular canal**
8 Crus commune or common limb
9 **Lateral semicircular canal**
10 Posterior bony ampulla
11 **Posterior semicircular canal** (posterior canal)
12 **Fenestra cochleae**
13 Bony ampulla
14 **Fenestra vestibuli**
15 Cupula of cochlea
16 External acoustic meatus
17 Mastoid air cells
18 Tympanic cavity and fenestra cochleae (probe)
19 External acoustic meatus
20 Facial canal
21 Base of cochlea and canalis musculotubarius
22 Malleus and incus
23 Stapes
24 Tympanic membrane
25 Tympanic cavity
26 Aqueduct of cochlea
27 Saccus endolymphaticus
28 Ductus endolymphaticus
29 Macula of utricle
30 Macula of saccule



Cast of the right labyrinth (lateral aspect).



Cast of the labyrinth and mastoid cells. Life size (posterior aspect).



Dissection of bony labyrinth in situ. Semicircular canals and cochlear duct opened.



Auditory and vestibular apparatus. Arrows: direction of sound waves; blue = perilymphatic ducts. (Schematic diagram.)



Bony labyrinth, petrous part of the temporal bone (from above). At left: semicircular canals opened, at right closed. Arrows: internal acoustic meatus.

1 Facial canal and semicanal of auditory tube
2 Superior vestibular area
3 Foramen ovale
4 Foramen lacerum
5 Cochlea
6 Vestibule
7 Anterior semicircular canal
8 Lateral semicircular canal
9 Posterior semicircular canal
10 Groove for sigmoid sinus
11 Sigmoid sinus
12 Tympanic cavity
13 Auditory tube
14 Mastoid air cells
15 Facial and vestibulocochlear nerves
16 Temporal fossa
17 Fenestra vestibuli
18 Promontory
19 Zygomatic process
20 Fenestra cochleae
21 Mastoid process



Bony labyrinth (left lateral aspect). Temporal and tympanic bone partly removed, semicircular canals opened.



Internal ear. Diagram showing the position of the membranous labyrinth and the tympanic cavity.



Dissection of the brain stem showing the acoustic pathway. Cerebellum and posterior part of the two hemispheres have been removed (dorsal aspect).

1 Left lateral ventricle and corpus callosum
2 Thalamus
3 Pineal gland (epiphysis)
4 Superior colliculus
5 Anterior cerebellar velum and superior cerebellar peduncle
6 Rhomboid fossa
7 **Vestibulocochlear nerve** (n. VIII)
8 **Dorsal acoustic striae** and inferior cerebellar peduncle
9 Insular lobe
10 Caudate nucleus and thalamus
11 Temporal lobe (superior temporal gyrus) (area of **acoustic centers**)
12 Transverse temporal gyri of Heschl (area of **primary acoustic centers**)
13 Acoustic radiation of internal capsule
14 Lateral geniculate body and optic radiation (cut)
15 **Medial geniculate body** and brachium of inferior colliculus
16 **Inferior colliculus**
17 Cerebral peduncle
18 **Lateral lemniscus**
19 Middle cerebellar peduncle
20 Dorsal (posterior) cochlear nucleus
21 Ventral (anterior) cochlear nucleus
22 Inferior olive with tractus olivocochlearis of Rasmussen (red)
23 Ganglion spirale
24 Obex
25 Frontal lobe
26 Temporal lobe
27 Middle temporal gyrus (area of **tertiary acoustic centers)**
28 Trapezoid body



Acoustic pathway (schematic drawing, compare with figure above).



Acoustic areas in the left hemisphere (superior lateral aspect). Parts of the frontal and parietal lobe have been removed.



Bones of the left orbit (indicated by different colors).



Frontal section through the posterior part of the orbit.

1. Frontal bone
2. Nasal bone
3. Lacrimal bone
4. Maxilla (frontal process)
5. Ethmoidal foramina
6. Lesser wing of sphenoid bone and optic canal
7. Superior orbital fissure
8. Greater wing of sphenoid bone
9. Orbital process of palatine bone
10. Orbital plate of ethmoid bone
11. Inferior orbital fissure
12. Infraorbital sulcus
13. Nasolacrimal canal
14. Zygomatic bone
15. Frontal sinus
16. **Superior rectus muscle**
17. Orbital fatty tissue
18. **Optic nerve**
19. **Sclera**
20. **Inferior rectus muscle**
21. Periorbita and maxilla
22. Maxillary sinus
23. Levator palpebrae superioris muscle
24. **Superior conjunctival fornix**
25. Superior tarsal plate
26. Inferior tarsal plate
27. **Inferior conjunctival fornix**
28. **Inferior oblique muscle**
29. **Lateral rectus muscle**
30. **Medial rectus muscle**
31. **Superior oblique muscle**
32. Nasal septum
33. Middle nasal concha
34. Inferior nasal concha
35. Tenon's space
36. Ophthalmic artery
37. **Cornea**
38. **Lens**



Sagittal section through orbit and eyeball.



Sagittal section through orbit and eyeball. (MR-Scan.)



Horizontal section through the human eye (2×).



Anterior segment of the eyeball (posterior aspect). The opacity of the lens is an artifact.



Organization of the eyeball. Demonstration of vascular tunic of bulb. (Schematic drawing.)



Lens (equatorial aspect), anterior pole to the right.



Lens (frontal aspect). Note the magnification effect.

1 **Cornea** and anterior chamber
2 Iris and lens
3 Transitional zone between corneal and conjunctival epithelium
4 Conjunctiva of the eyeball
5 **Ciliary body**
  a Ciliary processes (pars plicata)
  b Ciliary ring (pars plana)
6 Zonular fibers
7 **Ora serrata**
8 Vitreous body
9 **Retina**
10 **Choroid**
11 **Sclera**
12 Optic disc
13 Dura mater and subarachnoid space
14 **Optic nerve** (n. II)
15 Lens (posterior pole)
16 Equator of lens
17 **Lens** (anterior pole)
18 Canal of Schlemm
19 Ciliary muscle
20 Vena vorticosa
21 Long posterior ciliary artery
22 Retinal pigmented epithelium
23 Central retinal artery and vein
24 Short posterior ciliary arteries
25 External ocular muscle
26 Anterior ciliary artery
27 **Iris**



Fundus of a normal right eye (courtesy of Prof. Dr. R. Okamura, Univ. Eye Dept., Kumamoto/Japan). Notice, the arteries are smaller and lighter than the veins.



Anterior segment of the human eye (courtesy of Prof. Dr. G. O. H. Naumann, Eye Dept., University of Erlangen, FRG). Note the colored iris and the anterior lens surface.



Fluorescent angiography of the right eye; retinal vessels. The same eye as above. (Courtesy of Prof. Dr. R. Okamura, Univ. Eye Dept., Kumamoto/Japan.)



Diagram of the ophthalmic artery and its branches.

1 Posterior and anterior ethmoidal arteries
2 Long and short **posterior ciliary arteries**
3 Optic nerve and **ophthalmic artery**
4 Central retinal artery
5 Retinal arteries
6 Supratrochlear artery
7 Supraorbital artery
8 Dorsal nasal artery
9 **Anterior ciliary artery**
10 Iridial arteries
11 Circulus arteriosus major of iris
12 Iridial fold
13 Pupillary margin of iris
14 Anterior pole of lens
15 Lesser circle of **iris**
16 Greater circle of iris
17 Margin of cornea or limbus
18 Sclera
19 Superior temporal artery and vein of retina
20 Superior nasal artery and vein of retina
21 Superior macular artery
22 **Optic disc**
23 Inferior macular artery
24 Inferior temporal artery and vein
25 **Fovea centralis** and **macula lutea**
26 Superior temporal artery
27 Superior nasal artery
28 Inferior nasal artery
29 Inferior temporal artery
} of retina



Schematic diagram of the extraocular muscles. Right orbit (from above). Levator palpebrae superioris muscle has been severed.



The action of the extraocular muscles. Left orbit (anterior aspect).

A	Superior rectus muscle
B	Inferior oblique muscle
C	Medial rectus muscle
D	Lateral rectus muscle
E	Inferior rectus muscle
F	Superior oblique muscle



Right orbit with eyeball and extraocular muscles (from above). The roof of the orbit has been removed, the superior rectus muscle and the levator palpebrae superioris muscle have been severed.



Left orbit with eyeball and extraocular muscles (anterior aspect). Lids, conjunctiva and lacrimal apparatus have been removed.

1	**Superior oblique muscle** and ethmoid air cells
2	**Medial rectus muscle**
3	Trochlea
4	Tendon of superior oblique muscle
5	**Superior rectus muscle**
6	Cornea
7	Eyeball
8	Optic chiasma
9	Optic nerve (intracranial part)
10	Internal carotid artery
11	**Common annular tendon**
12	Levator palpebrae superioris muscle
13	**Superior rectus muscle**
14	Optic nerve (extracranial part)
15	**Lateral rectus muscle**
16	Nasolacrimal duct
17	**Inferior oblique muscle**
18	Nasal bone
19	Maxilla
20	Infraorbital foramen and nerves
21	Zygomatic bone
22	**Inferior rectus muscle**



Extraocular muscles and their nerves (lateral aspect of left eye). Lateral rectus divided and reflected.



Left orbit with extraocular muscles (anterior aspect). Eyeball removed.



Extraocular eye muscles (anterior-lateral aspect).

1 Supraorbital nerve
2 Cornea
3 Insertion of lateral rectus muscle
4 Eyeball (sclera)
5 **Inferior oblique muscle**
6 **Inferior rectus muscle** and inferior branch of oculomotor nerve
7 Infraorbital nerve
8 Superior rectus muscle and lacrimal nerve
9 Optic nerve
10 **Lateral rectus muscle**
11 Ciliary ganglion and abducens nerve (n. VI)
12 Oculomotor nerve (n. III)
13 Trochlear nerve (n. IV)
14 Ophthalmic nerve (n. V_1) and maxillary nerve (n. V_2)
15 Trochlea and tendon of superior oblique muscle
16 **Superior oblique muscle**
17 **Medial rectus muscle**
18 Levator palpebrae superioris muscle
19 **Superior rectus muscle**
20 **Inferior rectus muscle**
21 Greater alar cartilage
22 Supraorbital nerve and levator palpebrae superioris muscle
23 Levator labii superioris muscle



Dissection of the visual pathway (inferior aspect). Frontal pole at top, midbrain divided.

1 Medial olfactory stria
2 Olfactory trigone
3 Lateral olfactory stria
4 Anterior perforated substance
5 Oculomotor nerve (n. III)
6 Mamillary body
7 Cerebral peduncle
8 **Lateral geniculate body**
9 Medial geniculate body
10 **Pulvinar of thalamus**
11 Optic radiation
12 Splenium of the corpus callosum (commissural fibers)
13 Cuneus
14 Olfactory bulb
15 Olfactory tract
16 **Optic nerve** (n. II)
17 Infundibulum
18 Anterior commissure
19 **Genu of optic radiation**
20 **Optic tract**
21 Interpeduncular fossa and posterior perforated substance
22 Trochlear nerve (n. IV)
23 Substantia nigra
24 Cerebral aqueduct
25 **Visual cortex**
26 Line of Gennari
27 Gyrus of striate cortex
28 **Calcarine sulcus**



Frontal section of the striate cortex at the level of the striate area in the occipital lobe.



Horizontal section through the head at the level of optic chiasma and striate cortex (superior aspect). Note the relationship of hypothalamic infundibulum to optic chiasma.

1 Upper lid
2 Cornea
3 **Eyeball** (sclera, retina)
4 Head of optic nerve
5 Optic nerve
6 **Optic chiasma**
7 Infundibular recess of hypothalamus
8 Amygdaloid body
9 Substantia nigra and crus cerebri
10 Cerebral aqueduct
11 Vermis of cerebellum
12 Falx cerebri
13 Lateral rectus muscle
14 Optic canal
15 Internal carotid artery
16 **Optic tract**
17 Hippocampus
18 Inferior horn of lateral ventricle
19 Tentorium cerebelli
20 **Optic radiation** of Gratiolet
21 **Visual cortex (area calcarina, striate cortex)**
22 Lens
23 **Eyeball**
24 Ethmoidal cells
25 Optic nerve with dura sheath
26 Cerebral peduncle
27 Aqueduct of mesencephalon
28 Vermis of cerebellum



Horizontal section through the human head (MR-Scan, courtesy of Prof. W. J. Huk, Erlangen, FRG). Arrows = branches of arterial circle of Willis.



Diagram of the visual pathway and path of the light reflex.



3-D-Reconstruction of the human visual system (MR-Image flash 40°, courtesy of Prof. W. J. Huk, University of Erlangen, FRG).

29	Lateral rectus muscle
30	Medial rectus muscle
31	Temporalis muscle
32	Hypophysis (pituitary gland)
33	Midbrain
34	Ciliary nerves (long and short)
35	Ciliary ganglion
36	Oculomotor nerve
37	Accessory oculomotor nucleus
38	Colliculi of midbrain
39	Corpus callosum
40	Visual field
41	Retina
42	**Lateral geniculate body**
43	Frontal lobe
44	**Caudate nucleus**
45	Medial rectus muscle
46	Lateral rectus muscle
47	Skin
48	Diploe (skull)
49	Dura mater
50	**Thalamus**
51	**Anterior cerebral artery**
52	Nucleus caudatus
53	Frontal sinus
54	**Internal capsule**
55	Lentiform nucleus (putamen)
56	**Hippocampus**
57	Temporal lobe of left hemisphere



Dissection of brain stem in situ. Left hemisphere has been partly removed (compare with MR-Image above).

In **binocular vision** the visual field (40) is projected upon portions of both retinae (blue and red in the drawing). In the chiasma the fibers from the two retinal portions are combined to form the left optic tract. The fibers of the two eyes remain separated from each other throughout the entire visual pathway up to their final termination in the calcarine cortex (21). **Injuries** on the optic pathway produce visual defects whose nature depends on the location of the injury. Destruction of one optic nerve produces blindness in the corresponding eye with loss of pupillary light reflex. If lesions of the **chiasma** destroy the crossing fibers of the nasal portions of the retina, both temporal fields of vision are lost (bitemporal hemianopsia). If both lateral angles of the chiasma are compressed, the nondecussating fibers from the temporal retinae are affected resulting in loss of nasal visual fields (binasal hemianopsia). Lesions posterior to the chiasma (i. e., optic tract, lateral geniculate body, optic radiation or visual cortex) result in a loss of the entire opposite field of vision (homonymous hemianopsia).



Superficial layer of the left orbit (superior aspect). The roof of the orbit and a portion of the left tentorium have been removed.



Middle layer of the left orbit (superior aspect). The roof of the orbit has been removed and the superior extraocular muscles have been divided and reflected.

1 Lateral branch of frontal nerve
2 Lacrimal gland
3 Lacrimal vein
4 Lacrimal nerve
5 **Frontal nerve**
6 Superior rectus
7 Middle cranial fossa
8 **Abducens nerve** (n. VI)
9 Trigeminal nerve (n. V)
10 **Trochlear nerve** (intracranial part) (n. IV)
11 Frontal sinus
12 Levator palpebrae superioris muscle
13 Branches of supratrochlear nerve
14 Olfactory bulb
15 Superior oblique muscle
16 **Trochlear nerve** (intraorbital part) (n. IV)
17 **Optic nerve** (intracranial part)
18 Pituitary gland and infundibulum
19 Dorsum sellae
20 **Oculomotor nerve** (n. III)
21 Midbrain
22 Tendon of superior oblique muscle
23 Eyeball
24 Vena vorticosa
25 Short ciliary nerves
26 Optic nerve (extracranial part)
27 **Trigeminal ganglion**


33
12
2
6
23
24
25
34
35
36
30
5
7
27
8
10
9
37
38
15
28
39
40
41
28
42
43
44
17
18
20
45

Middle layer of the left orbit (superior aspect). The roof of the orbit and the superior extraocular muscles have been removed.


38
33
24
2
46
25
35
47
7
8
48
27
8
9
11
15
23
39
40
30
49
50
44
28
51
18
20
10
45

Deeper layer of the left orbit (superior aspect). The optic nerve has now been removed.

28 **Ophthalmic artery**
29 Superior ophthalmic vein
30 **Nasociliary nerve**
31 Levator palpebrae superioris muscle (reflected)
32 Superior rectus muscle (reflected)
33 Lateral branch of supraorbital nerve
34 Lacrimal nerve and artery
35 Lateral rectus muscle
36 Meningolacrimal artery (anastomosing with middle meningeal artery)
37 Trochlea
38 Medial branch of supraorbital nerve
39 Medial rectus muscle
40 Anterior ethmoidal artery and nerve
41 Long ciliary nerve
42 Superior oblique muscle and trochlear nerve
43 Common tendinous ring
44 Olfactory tract
45 Basilar artery and pons
46 Optic nerve (external sheath of optic nerve, divided)
47 **Ciliary ganglion**
48 Ophthalmic nerve (divided, reflected)
49 Inferior branch of oculomotor nerve and inferior rectus muscle
50 Superior branch of oculomotor nerve
51 Internal carotid artery



Eyelids (superficial layer, right side).



Eyelids (deeper layer, left side).

1 Supraorbital artery, supraorbital nerve, lateral branch
2 **Lacrimal gland**
3 Aponeurosis of levator palpebrae superioris muscle
4 Arterial arch of upper eyelid
5 Lateral palpebral ligament
6 Supratrochlear artery, supratrochlear nerve
7 Upper eyelid, tarsal plate
8 Lacrimal sac
9 **Medial palpebral ligament**
10 Angular artery and vein
11 Infraorbital artery, vein and nerve
12 Orbicularis oculi muscle
13 Infratrochlear nerve
14 Levator labii superioris alaeque nasi muscle
15 Facial artery and vein
16 **Superior lacrimal canaliculus**
17 **Inferior lacrimal canaliculus**
18 Lacrimal papilla and punctum
19 Lacrimal bone
20 **Lacrimal duct**
21 Mucous membrane of nasal cavity
22 Palpebral conjunctiva of lower eyelid
23 Lacrimal sac and superior lacrimal canaliculus
24 Lateral fixation of levator aponeurosis
25 Infraorbital foramen



Lacrimal apparatus of left eye (anterior aspect).



Lacrimal apparatus of left eye (anterior aspect).



Nasal septum, covered by a mucous membrane.



Nasal septum. Mucous membrane removed.



Nasal septum. Dissection of nerves and vessels.

1	Crista galli
2	Pituitary gland and sella turcica
3	**Sphenoidal sinus** (relatively large)
4	Tubal elevation
5	Pharyngeal opening of the **auditory tube**
6	Pharyngeal recess
7	Atlas (anterior arch)
8	Soft palate
9	Frontal sinus
10	Perpendicular plate of ethmoid
11	**Cartilage of nasal septum**
12	Vomer
13	Hard palate
14	Nasal branch of anterior ethmoidal artery and anterior ethmoidal nerve
15	Nasopharynx
16	Nasal septum
17	**Olfactory nerves**
18	Septal artery
19	Crest of nasal septum
20	Incisive canal
21	Anterior ethmoidal artery
22	Olfactory bulb
23	Olfactory tract
24	Internal carotid artery
25	Posterior nasal and septal arteries
26	Nasopalatine nerve
27	**Choana** (arrow)
28	Tongue



Lateral wall of the nasal cavity, septum removed.

1 Sphenoidal sinus
2 Superior meatus
3 Middle meatus
4 Tubal elevation
5 Pharyngeal tonsil
6 Pharyngeal orifice of **auditory tube**
7 Salpingopharyngeal fold
8 Pharyngeal recess
9 **Soft palate**
10 **Uvula**
11 Frontal sinus
12 Sphenoethmoidal recess
13 **Superior nasal concha**
14 **Middle nasal concha**
15 **Inferior nasal concha**
16 Vestibule
17 Inferior meatus
18 **Hard palate**
19 Grooves for the middle meningeal artery and parietal bone (light green)
20 **Maxillary hiatus**
21 Perpendicular process of palatine bone
22 Openings of ethmoidal air cells
23 Opening of frontal sinus
24 Medial pterygoid plate (red)
25 Horizontal plate of palatine process
26 **Ethmoidal air cells**
27 **Maxillary sinus**
28 Nasal septum
29 Pterygoid hamulus
30 Nasal bone (white)
31 Frontal process of maxilla (violet)
32 Palatine process of maxilla (violet)
33 Nasal atrium



Bones of left nasal cavity, medial aspect.



Schematic diagram showing the position of paranasal sinuses, openings indicated by arrows.



Median section through the head with nasal and oral cavity. The middle and inferior nasal conchae have been partly removed to show the openings of paranasal sinuses.



Lateral wall of nasal cavity. Openings indicated by red arrows. (Schematic drawing.)

1 Great cerebral vein (Galen's vein)
2 **Tectum of midbrain**
3 Straight sinus
4 **Sphenoidal sinus**
5 Cerebellum
6 **Pharyngeal tonsil**
7 **Cerebellomedullary cistern**
8 Median atlantoaxial joint
9 Spinal cord
10 Oral part of pharynx
11 Falx cerebri
12 Corpus callosum and anterior cerebral artery
13 **Frontal sinus**
14 Optic chiasm and pituitary gland
15 Superior nasal concha and ethmoidal bulla
16 **Semilunar hiatus**
17 Accessory **openings to maxillary sinus** and cut edge of middle nasal concha
18 Vestibule
19 **Opening of nasolacrimal duct**
20 Inferior nasal concha (cut)
21 **Opening of auditory tube**
22 **Incisive canal**
23 Levator veli palatini muscle
24 Salpingopharyngeal fold
25 Lingual nerve and submandibular ganglion
26 Submandibular duct
27 **Nasofrontal duct**
28 **Nasolacrimal duct**
29 Sphenoethmoidal recess (of Rosenmüller)
30 Salpingopalatine fold



Nerves of the lateral wall of nasal cavity I. Sagittal section through the head. Mucous membranes partly removed, pterygoid canal opened.



Arteriogram of the nasal septum, left side (lateral aspect).

1 Facial nerve
2 **Internal carotid artery** and **internal carotid plexus**
3 **Superior cervical ganglion**
4 Vagus nerve
5 Sympathetic trunk
6 Optic nerve and ophthalmic artery
7 Oculomotor nerve
8 Internal carotid artery and cavernous sinus
9 Sphenoidal sinus
10 Nerve of the pterygoid canal
11 **Pterygopalatine ganglion**
12 **Descending palatine artery**
13 Lateral inferior posterior nasal branches and lateral posterior nasal and septal arteries
14 Greater palatine nerves and artery
15 Lesser palatine nerves and arteries
16 Branches of ascending pharyngeal artery
17 Lingual artery
18 Epiglottis
19 **Sella turcica**
20 **Posterior lateral nasal and septal arteries** (branches of sphenopalatine artery)
21 Median atlanto-axial joint
22 Soft palate and lesser palatine arteries (branches of descending palatine artery)
23 Frontal sinus
24 Anterior meningeal artery
25 Anterior ethmoidal artery (branch of ophthalmic artery)
26 **Septal branch of anterior ethmoidal artery**
27 Dorsal nasal artery
28 Nasal branches of anterior ethmoidal artery
29 Incisive canal with nasopalatine artery
30 Hard palate and greater palatine artery (branch of descending palatine artery)
31 Tentorium cerebelli
32 Trochlear nerve
33 **Trigeminal nerve** with motor root
34 **Internal carotid plexus**
35 **Lingual nerve with chorda tympani**
36 Medial pterygoid muscle and medial pterygoid plate
37 **Inferior alveolar nerve**
38 **Sympathetic trunk**
39 Oculomotor nerve
40 **Palatine nerves**
41 Tongue
42 **Tringeminal ganglion**
43 Trigeminal nerve (n. V)
44 **Facial nerve** (n. VII)
45 Geniculate ganglion
46 Stylomastoid foramen
47 Medial pterygoid muscle


31
32
33
2
10
34
35
36
15
37
3
17
38
4
39
23
9
11
40
12
14
41

Nerves of the lateral wall of nasal cavity II. Carotid canal opened, mucous membranes of pharynx and nasal cavity partly removed.

48	**Greater petrosal nerve**
49	Maxillary nerve
50	Olfactory bulb
51	**Olfactory nerves**
52	Internal nasal branches of anterior ethmoidal nerve
53	Lateral superior posterior nasal branches
54	Lateral inferior posterior nasal branches
55	Incisive canal with nasopalatine nerve
56	**Greater palatine nerve**
57	**Deep petrosal nerve**
58	Mandibular nerve
59	Nasal cavity and inferior nasal concha
60	Opening of auditory tube
61	Tensor veli palatini muscle
62	Levator veli palatini muscle
63	Pharyngeal recess in the nasopharynx
64	Uvula
65	Palatoglossal arch
66	Tonsillar branch of ascending palatine artery
67	**Palatine tonsil**
68	Palatopharyngeal arch


59
60
61
62
63
64
41
65
66
67
68
41
18

Dissection of palatine tonsil located in the lateral wall of the nasopharynx (left side). Root of tongue reflected.


48
49
11
50
42
43
44
45
34
44
46
47
51
52
53
54
55
58
57
10
40
56

Nerves of the lateral wall of nassal cavity. Body of sphenoid bone appears transparent (schematic drawing).



Horizontal section through the nasal cavity, the orbits and temporal lobes of the brain at the level of pituitary gland.



Horizontal section through the head. CT-Scan. Bar = 2 cm.
Arrow: fracture.

1 Cornea
2 Lens
3 Vitreous body (**eyeball**)
4 Head of optic nerve
5 Medial rectus muscle
6 Lateral rectus muscle
7 **Optic nerve** with dural sheath
8 Internal carotid artery
9 **Pituitary gland** and **infundibulum**
10 **Oculomotor nerve**
11 Superior tarsal plate of eye lid
12 Fornix of conjunctiva
13 **Nasal cavity**
14 Sclera
15 Ethmoidal sinus
16 **Nasal septum**
17 **Sphenoidal sinus**
18 Temporal lobe
19 Clivus
20 Middle cranial fossa
21 External acoustic meatus
22 Superior sagittal sinus
23 Falx cerebri
24 Superior rectus and levator palpebrae superioris muscles
25 Eyeball and lacrimal gland
26 Inferior rectus muscle
27 Zygomatic bone
28 **Maxillary sinus**
29 Inferior nasal concha
30 Hard palate
31 Superior longitudinal muscle of tongue
32 Median fibrosus septum of tongue


22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
16
28
39
40
41
42
43

Coronal section through the head at the level of the second premolar of the mandible.


36
37
24
44
38
15
26
28
16
29
30
32
39
42
34
35

Coronal section through the head (MR-Scan, courtesy of Dr. A. Heuck, Munich). Note the situation of the head cavities.

33 Inferior longitudinal muscle of tongue
34 **Sublingual gland**
35 Mandible
36 Calvaria
37 Frontal lobe of brain and crista galli
38 Lateral and medial eye rectus muscles
39 Buccinator muscle
40 Vertical and transverse muscles of tongue
41 Second premolar of mandible
42 Genioglossus muscle
43 Platysma muscle
44 **Orbit** and **optic nerve**
45 Filiform papillae
46 **Foramen cecum**
47 **Root of tongue** (lingual tonsil)
48 **Palatine tonsil**
49 Vallecula of epiglottis
50 Vestibule of larynx
51 Median sulcus of tongue
52 Fungiform papillae
53 Foliate papillae
54 **Circumvallate papilla**
55 Sulcus terminalis
56 Epiglottis
57 Greater cornu of hyoid bone


51
45
52
53
54
55
46
47
48
48
49
56
50
57

Dorsal surface of the tongue and laryngeal inlet.



Median sagittal section through the oral cavity and pharynx.

1 Nasal cavity
2 **Hard palate**
3 Upper lip and orbicularis oris muscle
4 Vestibule of oral cavity
5 First incisor
6 Lower lip and orbicularis oris muscle
7 Mandible
8 Genioglossus muscle
9 Geniohyoid muscle
10 Anterior belly of diagastric muscle
11 Mylohyoid muscle
12 **Hyoid bone**
13 **Nasopharynx**
14 **Soft palate** and **uvula**
15 **Oropharynx**
16 Root of tongue and lingual tonsil
17 **Laryngopharynx**
18 Epiglottis
19 Aryepiglottic fold
20 Laryngopharynx continuous with esophagus
21 Larynx



Hyoid bone (oblique lateral aspect).



Hyoid bone (anterior aspect).

1 Greater cornu }
2 Lesser cornu } of hyoid bone
3 Body }



Muscles of the floor of the oral cavity (superior aspect).

1 Lesser cornu and body of hyoid bone
2 Hyoglossus muscle (divided)
3 Ramus of mandible and inferior alveolar nerve
4 **Geniohyoid muscle**
5 Genioglossus muscle (divided)
6 Stylohyoid muscle (divided)



Oral diaphragm, muscles (inferior aspect). Cut on the base.

7 **Mylohyoid muscle**
8 Anterior belly of **digastric muscle**
9 Hyoid bone
10 Mandible
11 Intermediate tendon of digastric muscle



Parapharyngeal and sublingual regions. Innervation of the tongue. Lateral part of face and mandible removed, oral cavity opened. Arrow: submandibular duct.

1 Styloid process
2 Styloglossus muscle
3 Digastric muscle (posterior belly)
4 Vagus nerve (n. X)
5 **Lingual nerve** (n. V_3)
6 **Glossopharyngeal nerve** (n. IX)
7 Submandibular ganglion
8 Hyoglossus muscle
9 **Hypoglossal nerve** (n. XII)
10 Stylohyoid muscle
11 Internal branch of superior laryngeal nerve (branch of vagus nerve, not visible)
12 Middle constrictor muscle of pharynx
13 Omohyoid muscle (divided)
14 Thyrohyoid muscle
15 Sternothyroid muscle
16 Esophagus
17 Parotid duct (divided)
18 Buccinator
19 Superior constrictor muscle of pharynx
20 Tongue
21 Terminal branches of lingual nerve
22 Mandible (divided)
23 Genioglossus and geniohyoid muscles
24 Mylohyoid muscle (divided and reflected)
25 Sternohyoid muscle (divided)
26 Thyroid cartilage
27 Anterior belly of digastric muscle
28 Hyoid bone



Supra- and infrahyoid muscles and pharynx (schematic drawing).



Submandibular triangle, superficial dissection. Right side (inferior aspect). Submandibular gland has been reflected.



Submandibular triangle, deep dissection. Right side. Mylohyoid muscle has been severed and reflected to display the lingual and hypoglossal nerves.

1 Parotid gland and retromandibular vein
2 Sternocleidomastoid
3 Retromandibular vein, submandibular gland and stylohyoid muscle
4 Hypoglossal nerve and lingual artery
5 Vagus nerve and internal jugular vein
6 Superior laryngeal artery
7 **External carotid artery,** thyrohyoid muscle, and superior thyroid artery
8 Common carotid artery and superior root of ansa cervicalis
9 Omohyoid and sternohyoid
10 Masseter and marginal mandibular branch of facial nerve
11 **Facial artery and vein**
12 Mandible and submental artery and vein
13 Mylohyoid nerve
14 Submandibular duct, sublingual gland, and anterior belly of digastric muscle
15 Mylohyoid (right side)
16 Left mylohyoid and anterior belly of left digastric muscle
17 Hyoglossus muscle and lingual artery
18 **Lingual nerve**
19 **Hypoglossal nerve**
20 Geniohyoid muscle
21 Anterior belly of right digastric muscle
22 Submandibular gland and duct



Oral cavity (internal aspect). Tongue and pharyngeal wall removed.

1 Medial pterygoid muscle
2 Sublingual papilla
3 **Submandibular duct**
4 **Sublingual gland**
5 **Lingual nerve**
6 Hypoglossal nerve
7 Mylohyoid muscle
8 Geniohyoid muscle
9 Anterior belly of digastric muscle
10 Inferior alveolar nerve
11 **Chorda tympani**
12 Internal carotid artery
13 Parotid gland
14 Sphenomandibular ligament
15 Vagus nerve
16 Glossopharyngeal nerve
17 Superficial temporal artery and ascending pharyngeal artery
18 Styloglossus muscle
19 Posterior belly of digastric muscle
20 **Facial artery**
21 Submandibular gland
22 **External carotid artery**
23 Lingual artery
24 Middle pharyngeal constrictor muscle
25 **Stylohyoid ligament**
26 Hyoglossus muscle
27 Deep lingual artery
28 Epiglottis
29 Hyoid bone
30 Buccinator muscle
31 Tongue
32 Mandible (divided)
33 **Parotid duct**
34 Masseter muscle
35 Right and left sublingual papilla



Dissection of major salivary glands. Left mandible and buccinator muscle partly removed to view the oral cavity (inferior lateral aspect).



Location of the major salivary glands in relation to the oral cavity.



Cervical spine (oblique lateral aspect).

1 Temporal bone
2 Head of mandible
3 Mandible
4 Occipital bone
5 Atlas
6 Axis
7 Third cervical vertebra
8 Spinous process of fourth cervical vertrebra
9 Transverse process of fifth cervical vertebra with groove for spinal nerve
10 Intervertebral foramen
11 Vertebra prominens (C_7)
12 First rib
13 Sternum (manubrium sterni)
14 Atlantooccipital joint
15 Lateral atlantoaxial joint
16 Body of axis
17 Body of fourth cervical vertebra
18 Body of fifth cervical vertebra
19 Body of sixth cervical vertebra
20 Body of seventh cervical vertebra



Cervical vertebra and the **organization of the neck.** (Schematic drawing.)

1 Sternohyoid and sternothyroid muscles
2 Omohyoid muscle
3 Thyroid gland and trachea
4 Sternocleidomastoid muscle
5 Recurrent laryngeal nerve
6 Internal jugular vein, common carotid artery and vagus
7 Longus colli and longus capitis muscles
8 Sympathetic trunk
9 Spinal nerve
10 Ventral and dorsal root of spinal nerve
11 True muscles of the neck
12 Trapezius muscle
13 Body of cervical vertebra
14 Anterior tubercle of transverse process and origin of scalenus anterior muscle
15 Vertebral artery and foramen transversarium
16 Posterior tubercle of transverse process and origin of scalenus medius and posterior muscles
17 Superior facet of articular process
18 Spinal cord
19 Spinous process



Median section through adult head and neck. Note the low position of the adult larynx when compared with that of the neonate (cf. with figure below).

1 Nasal septum
2 Uvula
3 Genioglossus muscle
4 Mandible
5 Geniohyoid muscle
6 Mylohyoid muscle
7 **Hyoid bone**
8 Thyroid cartilage
9 Manubrium sterni
10 Sphenoidal sinus
11 **Nasopharynx**
12 **Oropharynx**
13 **Epiglottis**
14 **Laryngopharynx**
15 Arytenoid muscle
16 **Vocal fold**
17 Cricoid cartilage
18 **Trachea**
19 Left brachiocephalic vein
20 Thymus
21 Esophagus
22 Occipital lobe
23 Cerebellum and 4th ventricle
24 Medulla oblongata
25 Dens of axis
26 Intervertebral discs
of cervical vertebral column



Median section through neonate head and neck. Note the high position of the larynx permitting the epiglottis nearly to reach the uvula (cf. with the figure above).



Sagittal section through the head. (MR-Scan.)



Muscles of the neck (anterior aspect).

Suprahyoid muscles

1 Anterior belly of digastric muscle
2 Mylohyoid muscle
3 Posterior belly of digastric muscle
4 Stylohyoid muscle

Infrahyoid muscles

5 Omohyoid muscle
6 Sternohyoid muscle
7 Thyrohyoid muscle
8 Sternothyroid muscle

Other structures

9 Sternocleidomastoid muscle
10 Scalenus muscles
11 Trapezius muscle
12 Clavicle
13 First rib
14 Scapula
15 Mandible
16 Hyoid bone
17 Larynx (thyroid cartilage)
18 Trachea
19 Subclavius muscle
20 Manubrium sterni
21 Mucous membrane of larynx (conus elasticus)
22 Cricoid cartilage
23 Inferior horn of thyroid cartilage
24 Esophagus
25 Body of cervical vertebra
26 Posterior root ganglion
27 Spinal cord
28 Spinous process
29 Internal jugular vein, common carotid artery, and vagus nerve
30 True muscles of the neck (semispinalis cervicis and capitis muscles)



Cross-section of the neck at the level of the intervertebral disc between the 5th and 6th cervical vertebra (inferior aspect).



1 Mandible
2 Masseter muscle and facial artery
3 **Hyoid bone**
4 Median thyrohyoid ligament
5 **Thyrohyoid muscle**
6 **Sternothyroid muscle**
7 Thyroid gland (pyramidal lobe)
8 Pectoralis major muscle
9 Second rib
10 Parotid gland
11 Anterior belly of **digastric muscle**
12 Submandibular gland (divided)
13 **Mylohyoid muscle** and mylohyoid raphe
14 External carotid artery and vagus nerve
15 **Omohyoid muscle**
16 Thyroid cartilage
17 Sternocleidomastoid muscle
18 **Sternohyoid muscle**
19 Clavicle
20 Subclavius
21 Jugular fossa or suprasternal notch

Muscles of the neck (anterior aspect). Sternocleidomastoid and sternohyoid muscles on the right have been divided and reflected.



Regions and triangles of the neck.

1	Trapezius	
2	Sternocleidomastoid	
3	Occipital triangle	**Posterior triangle**
4	Supraclavicular triangle	
5	Submandibular triangle	**Anterior triangle**
6	Submental triangle	
7	Carotid triangle	
8	Muscular triangle	
9	Jugular fossa	
10	Lesser supraclavicular fossa	



Cartilages of the larynx and the hyoid bone (anterior aspect).



Cartilages of the larynx and the hyoid bone (posterior aspect).

1 **Epiglottis**
2 Lesser cornu of hyoid bone
3 Greater cornu of hyoid bone
4 Lateral thyrohyoid ligament
5 Body of **hyoid bone**
6 Superior cornu of thyroid cartilage
7 Thyroepiglottic ligament
8 Conus elasticus
9 Cricothyroid ligament
10 **Thyroid cartilage**
11 **Cricoid cartilage**
12 Trachea
13 Corniculate cartilage
14 **Arytenoid cartilage**
15 Posterior cricoarytenoid ligament
16 **Cricothyroid joint**
17 **Cricoarytenoid joint**



Cartilages of the larynx (anterior aspect). Thyroid cartilage is indicated by the outline.



Cartilages and ligaments of the larynx (lateral aspect). (Schematic drawing.)

1 Hyoid bone
2 Epiglottis
3 Thyrohyoid membrane
4 **Thyroid cartilage**
5 **Vocal ligament**
6 Conus elasticus
7 Arytenoid cartilage
8 **Cricoid cartilage**
9 **Cricoarytenoid joint**
10 **Cricothyroid joint**
11 Tracheal cartilages
12 Corniculate cartilage
13 Muscular process of arytenoid cartilage
14 Vocal process of arytenoid cartilage
15 Lamina of cricoid cartilage
16 Arch of cricoid cartilage



Cartilages of the larynx (oblique-posterior aspect).



Cartilages of the larynx (oblique-posterior aspect).

1 **Vocal ligament** (red)
2 Lateral thyrohyoid ligament
3 Greater cornu of hyoid bone
4 **Epiglottis**
5 **Thyroid cartilage**
6 Corniculate cartilage
7 **Arytenoid cartilage**
8 **Cricoarytenoid joint**
9 **Cricothyroid joint**
10 **Cricoid cartilage**
11 Trachea



Thyroid cartilage (lateral aspect).



Thyroid cartilage (anterior aspect).

1 Superior cornu
2 Superior thyroid tubercle
3 Lamina of thyroid cartilage
4 Inferior thyroid tubercle
5 Inferior cornu
6 Superior thyroid notch



1 Atlas
2 Axis
3 Cervical vertebrae (C_2–C_7)
4 Mandible
5 **Hyoid bone**
6 **Thyroid cartilage**
7 Arytenoid cartilage
8 **Cricoid cartilage**
9 Epiglottis
10 **Tracheal cartilages**
11 First rib
12 Manubrium sterni

Position of the larynx in the neck (oblique lateral aspect). (Schematic drawing.)



Laryngeal muscles I (lateral aspect). Thyroid cartilage and thyroarytenoid muscle have been partly removed.



Laryngeal muscles II (lateral aspect). Half of the right side of the thyroid cartilage has been removed.

1	Epiglottis
2	Greater horn of hyoid bone
3	Corniculate cartilage
4	Transverse arytenoid muscle
5	Oblique arytenoid muscle
6	Lamina of cricoid cartilage
7	**Posterior cricoarytenoid muscle**
8	Aryepiglottic fold and muscle
9	Lamina of thyroid cartilage
10	Thyroepiglottic muscle
11	Thyroarytenoid muscle
12	**Lateral cricoarytenoid muscle**
13	Articular facet of thyroid cartilage
14	Cartilages of trachea
15	Membranous part of trachea
16	Lateral thyrohyoid ligament
17	Thyrohyoid membrane
18	Position of piriform recess
19	Arytenoid cartilage
20	Stem of epiglottis
21	Vestibular fold
22	Vocal folds and fissure of glottis
23	**Vocalis muscle**
24	Cricoarytenoid articulation
25	Arch of cricoid cartilage
26	Cricothyroid muscle
27	Cricoid cartilage
28	Piriform recess
29	Superior horn of thyroid cartilage
30	Vocal ligament



Laryngeal muscles, larynx (anterior aspect).



Laryngeal muscles, larynx (posterior aspect).



Action of internal muscles of the larynx. (Schematic drawing.)



Laryngeal cartilages (superior aspect).



Glottis in vivo (superior aspect).



Horizontal section through the larynx at the level of the vocal folds (superior aspect).



Sagittal section through the larynx.



Coronal section through larynx and trachea.

1 **Hyoid bone**
2 Epiglottis
3 **Thyroid cartilage**
4 **Cricoid cartilage**
5 **Vocal ligament**
6 Thyrohyoid ligament
7 **Arytenoid cartilage**
8 Corniculate cartilage
9 **Vocal fold**
10 **Vestibular fold**
11 Aryepiglottic fold
12 Interarytenoid notch
13 Mandible
14 Anterior belly of digastric muscle
15 Mylohyoid muscle
16 Pyramidal process of thyroid gland
17 Sternohyoid and sternothyroid muscles
18 Common carotid artery
19 Internal jugular vein
20 **Rima glottidis**
21 Sternocleidomastoid muscle
22 Transverse arytenoid muscle
23 Pharynx and inferior constrictor muscle
24 Ventricle of larynx
25 **Vocalis muscle**
26 Trachea
27 Superior cornu of thyroid cartilage
28 Root of tongue (lingual tonsil)
29 Piriform recess
30 Vocalis muscle
31 Lateral cricoarytenoid muscle
32 **Thyroid gland**



Larynx and its innervation (posterior aspect). Dissection of superior and inferior laryngeal nerves. Pharynx has been opened.



Innervation of the larynx. (Schematic diagram.)



Larynx and thoracic organs (anterior aspect). Dissection of vagus and recurrent laryngeal nerves.

1 Scalenus anterior muscle
2 Scalenus medius and posterior muscles
3 Right **recurrent laryngeal nerve**
4 Right subclavian artery
5 Brachiocephalic trunk
6 Aortic arch
7 Hyoid bone
8 **Internal branch of superior laryngeal nerve**
9 Thyrohyoid membrane
10 **External branch of superior laryngeal nerve**
11 **Vagus nerve**
12 Thyroid cartilage
13 Cricothyroid muscle
14 Trachea
15 **Left recurrent larnygeal nerve**
16 Esophagus
17 Left subclavian artery
18 Left common carotid artery
19 Second rib
20 Tongue
21 Superior cervical ganglion
22 Sympathetic trunk
23 Inferior constrictor muscle of pharynx
24 **Inferior thyroid artery**
25 Glossopharyngeal nerve
26 Superior laryngeal nerve
27 Epiglottis
28 Posterior cricoarytenoid muscle and cricoid cartilage
29 Inferior laryngeal branch of recurrent laryngeal nerve
30 **Thyroid gland**
31 Superior thyroid artery
32 **Thyrocervical trunk**
33 Internal thoracic artery
34 **Phrenic nerve**
35 Hypoglossal nerve
36 Transverse cervical artery
37 Middle cervical ganglion
38 Middle cervical cardiac nerves (branches of sympathetic trunk)
39 Ligamentum arteriosum



Larynx and oral cavity (posterior aspect). Mucous membrane on the right half of pharynx has been removed.

1 Midbrain (inferior colliculus)
2 Rhomboid fossa and medulla oblongata
3 Vestibulocochlear and facial nerve
4 Glossopharyngeal, vagus and accessory nerve
5 Occipital artery and posterior belly of digastric muscle
6 Superior cervical ganglion
7 **Internal carotid artery**
8 **Oral cavity** (tongue)
9 Aryepiglottic fold
10 Vagus nerve
11 **Piriform recess**
12 Thyroid gland and common carotid artery
13 Esophagus
14 Trochlear nerve
15 Occipital condyle
16 **Nasal cavity** (choana)
17 Accessory nerve
18 **Uvula** and soft palate
19 Palatopharyngeus muscle
20 External carotid artery
21 Epiglottis
22 **Internal branch of superior laryngeal nerve**
23 **Inferior laryngeal nerve**
24 Ansa cervicalis



Pharynx and parapharyngeal nerves in connection with brain stem (posterior aspect).

1 Inferior colliculus of midbrain
2 Facial colliculus in **floor of rhomboid fossa**
3 Vestibulocochlear and facial nerves
4 Glossopharyngeal nerve
5 Vagus nerve
6 Accessory nerve
7 Hypoglossal nerve
8 Pharyngobasilar fascia
9 Superior constrictor muscle of pharynx
10 **Sympathetic trunk** and **superior cervical ganglion** (medially displaced)
11 Middle constrictor muscle of pharynx
12 Greater cornu of hyoid bone
13 Inferior constrictor muscle of pharynx
14 Trochlear nerve
15 **Internal acoustic meatus** with facial and vestibulocochlear nerves
16 **Jugular foramen** with glossopharyngeal, vagus and assessory nerves
17 Occipital condyle
18 Occipital artery
19 Posterior belly of digastric muscle
20 **Accessory nerve** (extracranial part)
21 **Hypoglossal nerve** (extracranial part)
22 External carotid artery
23 Carotid sinus nerve
24 **Internal carotid artery**
25 **Carotid sinus and carotid body**
26 Vagus nerve
27 Thyroid gland
28 Esophagus
29 Choanae
30 Medial pterygoid plate
31 Foramen lacerum
32 **Pharyngeal tubercle**
33 Hard palate
34 Greater and lesser palatine foramen
35 Pterygoid hamulus
36 Lateral pterygoid plate
37 Pterygoid canal
38 Foramen ovale
39 Mandibular fossa
40 Carotid canal
41 Styloid process and stylomastoid foramen



Inferior aspect of the skull. Red line = outline of superior constrictor muscle in continuation with buccinator muscle and orbicularis oris muscle. (Semischematic drawing.)



Parapharyngeal nerves and vessels. Dorsal aspect of the pharynx.



Cross-section of head and neck at the level of the atlas (inferior aspect).

1 Ascending pharyngeal artery
2 Pharyngeal plexus
3 **Accessory nerve**
4 Superior cervical ganglion of sympathetic trunk
5 Superior laryngeal nerve
6 Carotid body and carotid sinus nerve
7 Left **vagus nerve**
8 Common carotid artery and cardiac branch of vagus nerve
9 **Glossopharyngeal nerve**
10 **Hypoglossal nerve**
11 **Facial nerve**
12 Posterior belly of digastric muscle
13 Middle constrictor muscle of pharynx
14 Right vagus nerve
15 **Sympathetic trunk**
16 **Internal jugular vein**
17 Inferior constrictor muscle of pharynx
18 Larynx
19 **Buccinator muscle**
20 Soft palate and palatine glands
21 Palatine tonsil
22 Uvula of palate
23 **Pharynx** (oral part)
24 Parotid gland
25 Longus capitis muscle
26 Medioatlantoaxial joint and anterior arch of atlas
27 **Dens of axis**
28 **Spinal cord**
29 Dura mater
30 Incisive papilla
31 **Oral vestibule**
32 Masseter muscle
33 Mandible
34 Mandibular canal with vessels and nerve
35 Medial pterygoid muscle
36 External carotid artery
37 Internal carotid artery
38 **Atlas**
39 **Vertebral artery**
40 Splenius capitis muscle
41 Semispinalis capitis muscle



Dissection of pharynx, supra- and infrahyoid muscles I. Mandible partly removed (lateral aspect).

1. Maxilla
2. Pterygomandibular raphe
3. Buccinator muscle
4. Mandible (divided)
5. Depressor anguli oris muscle
6. Mylohyoid muscle
7. Anterior belly of digastric muscle
8. Hyoid bone
9. Thyroid cartilage
10. Cricothyroid muscle
11. Styloid process
12. Medial pterygoid muscle (divided)
13. Posterior belly of digastric muscle
14. Styloglossus muscle
15. Stylohyoid muscle
16. **Thyropharyngeal part of inferior constrictor muscle of pharynx**
17. Thyrohyoid muscle
18. **Cricopharyngeal part of inferior constrictor muscle of pharynx**
19. Esophagus
20. Trachea
21. First molar of maxilla
22. Tongue
23. Inferior longitudinal muscle of tongue
24. Genioglossus muscle
25. **Superior constrictor muscle of pharynx**
26. Hypoglossal nerve
27. Hyoglossus muscle
28. Superior laryngeal nerve and superior laryngeal artery



Dissection of pharynx, supra- and infrahyoid muscles II. Oral cavity opened (lateral aspect).



Muscles of the pharynx (posterior aspect).

1 Sella turcica
2 Internal acoustic meatus and petrous part of temporal bone
3 Pharyngobasilar fascia
4 Fibrous raphe of pharynx
5 **Stylopharyngeus muscle**
6 **Superior constrictor muscle of pharynx**
7 Posterior belly of digastric muscle
8 Stylohyoid muscle
9 **Middle constrictor muscle of pharynx**
10 **Inferior constrictor muscle of pharynx**
11 Muscle-free area (Killian's triangle)
12 Esophagus
13 Trachea
14 Thyroid and parathyroid glands
15 Medial pterygoid muscle
16 Greater horn of hyoid bone
17 Internal jugular vein
18 Parotid gland
19 Accessory nerve
20 **Superior cervical ganglion** of sympathetic trunk
21 Vagus nerve
22 Laimer's triangle (area prone to developing diverticula)
23 Orbicularis oculi muscle
24 Nasalis muscle
25 Levator labii superioris and levator labii alaeque nasi muscles
26 Levator anguli oris muscle
27 Orbicularis oris muscle
28 **Buccinator muscle**
29 Depressor labii inferioris muscle
30 **Hyoglossus muscle**
31 Thyrohyoid muscle
32 Thyroid cartilage
33 Cricothyroid muscle
34 Pterygomandibular raphe
35 Tensor veli palatini muscle
36 Levator veli palatini muscle
37 Depressor anguli oris muscle
38 Mentalis muscle
39 Styloglossus muscle



Muscles of the pharynx. (Schematic drawing.)



Muscles of pharynx (lateral aspect). (Schematic drawing.)



Arteries of head and neck. Diagram of the main branches of external carotid and subclavian artery.

1 Frontal and parietal branches of superficial temporal artery
2 Superficial temporal artery
3 **Occipital artery**
4 **Maxillary artery**
5 **Vertebral artery**
6 **External carotid artery**
7 Internal carotid artery
8 Common carotid artery (divided)
9 Ascending cervical artery
10 Inferior thyroid artery
11 Transverse cervical artery with 2 branches (superficial cervical artery and descending scapular artery)
12 Suprascapular artery
13 **Thyrocervical trunk**
14 Costocervical trunk with 2 branches (deep cervical artery and superior intercostal artery)
15 Internal thoracic artery
16 **Axillary artery**
17 Supraorbital and supratrochlear arteries
18 Angular artery
19 Dorsal nasal artery
20 Transverse facial artery
21 **Facial artery**
22 Superior labial artery
23 Inferior labial artery
24 Submental artery
25 Lingual artery
26 Superior thyroid artery
27 Brachiocephalic trunk

to page 165 ▷

1 Galea aponeurotica
2 Frontal branch } of superficial
3 Parietal branch } temporal artery
4 Superior auricular muscle
5 **Superficial temporal artery and vein**
6 Middle temporal artery
7 Auriculotemporal nerve
8 Branches of facial nerve
9 Facial nerve
10 **External carotid artery** within the retromandibular fossa
11 Posterior belly of digastric muscle
12 Sternocleidomastoid artery
13 Sympathetic trunk and superior cervical ganglion
14 Sternocleidomastoid muscle (divided and reflected)
15 Clavicle (divided)
16 Transverse cervical artery
17 Ascending cervical artery and phrenic nerve
18 Scalenus anterior muscle
19 Suprascapular artery
20 Dorsal scapular artery
21 Brachial plexus and **axillary artery**
22 Thoracoacromial artery
23 Lateral thoracic artery
24 Median nerve (displaced) and pectoralis minor muscle (reflected)
25 Frontal belly of occipitofrontalis muscle
26 Orbital part of orbicularis oculi muscle
27 **Angular artery** and vein
28 **Facial artery**
29 Superior labial artery
30 Zygomaticus major muscle
31 Inferior labial artery
32 Parotid duct
33 Buccal fat pad
34 **Maxillary artery**
35 Masseter muscle
36 Facial artery and mandible
37 Submental artery
38 Anterior belly of digastric muscle


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53

Main branches of head and neck arteries (lateral aspect). Anterior thoracic wall and clavicle partly removed; pectoralis muscles have been reflected to display the subclavian and axillary arteries.

39	Hyoid bone	46	Thyroid gland (right lobe)
40	**Internal carotid artery**	47	**Vertebral artery**
41	**External carotid artery**	48	**Thyrocervical trunk**
42	Superior laryngeal artery	49	Vagus nerve
43	Superior thyroid artery	50	Ansa subclavia of sympathetic trunk
44	**Common carotid artery**	51	**Brachiocephalic trunk**
45	Thyroid ansa of sympathetic trunk and **inferior thyroid artery**	52	Superior vena cava (divided)
		53	Aortic arch



Arteries of head and neck (anterior-lateral aspect). Clavicle, sternocleidomastoid and veins have been partly removed, the arteries were colored.



Veins of head and neck. Sternocleidomastoid muscle and anterior thoracic wall partly removed. Note the venous connection with the superior vena cava.

1 Occipital vein
2 Superficial temporal vein
3 Sternocleidomastoid muscle
4 Trapezius muscle
5 **Internal jugular vein**
6 External jugular vein
7 **Subclavian vein**
8 Cephalic vein
9 Supraorbital veins
10 Angular vein
11 Superior labial vein
12 Inferior labial vein
13 **Facial vein**
14 Submental vein
15 Superior thyroid vein
16 Anterior jugular vein
17 Thoracic duct
18 Inferior thyroid vein
19 Superior vena cava
20 Occipital artery
21 **Internal carotid artery**
22 Cervical plexus
23 Supraclavicular nerve
24 Phrenic nerve and ascending cervical artery on scalenus anterior muscle
25 Superficial cervical artery
26 Suprascapular artery and nerve
27 Brachial plexus and anterior circumflex humeral artery
28 Lateral cord of brachial plexus
29 **Thoracoacromial artery**
30 Lateral thoracic artery
31 Superficial temporal artery
32 Transverse facial artery
33 Facial artery
34 External carotid artery
35 Superior thyroid artery
36 **Common carotid artery, vagus nerve** and thyroid gland
37 **Thyrocervical trunk**
38 **Subclavian artery** and scalenus anterior muscle
39 Parotid gland and facial nerve
40 Great auricular nerve
41 External jugular vein
42 Brachial plexus
43 Cephalic vein in deltopectoral groove
44 Axillary vein and artery
45 Right brachiocephalic vein
46 **Superior vena cava**
47 Right lung (reflected)
48 Superficial temporal artery and vein
49 Facial artery and vein
50 Cervical branch of facial nerve and submandibular gland
51 **Internal jugular vein,** common carotid artery and omohyoid muscle
52 Anterior jugular vein and thyroid gland
53 Jugular venous arch
54 Left brachiocephalic vein
55 Pericardium of heart (location of right atrium)
56 Transverse cervical artery



Veins of head and neck (anterior aspect). Part of the thoracic wall, clavicle and sternocleidomastoid muscle have been removed. Veins were colored blue, arteries red.

The **internal jugular vein** is the continuation of the sigmoid sinus which drains most of the venous blood from the brain together with the external cerebrospinal fluid. By joining the subclavian vein it forms the right brachiocephalic vein which continues on the right side directly into the superior vena cava. The common way to introduce the lead from a pacemaker device into the heart is by way of the cephalic vein. On the left side the thoracic duct joins the internal jugular vein at that point where the subclavian vein and the internal jugular vein form the left brachiocephalic vein. Note that the subclavian vein lies in front of the scalenus anterior muscle whereas the subclavian artery together with the plexus brachialis lies posterior to that muscle. The cephalic vein joins the axillary vein by passing into the deltopectoral triangle. The subclavian vein is strongly fixed to the first rib so that it can be punctured with a needle at that point (underneath the sternal end of clavicle) to introduce a catheter (subclavian line).



Lymph nodes and lymph vessels of the neck, left side oblique (lateral aspect). The sternocleidomastoid muscle and the left half of the thoracic wall have been removed. Lower part of the internal jugular vein has been cut and laterally displaced to show the thoracic duct.

1 **Superficial parotid lymph node**
2 Parotid gland
3 Great auricular nerve
4 Mandible
5 Facial vein
6 Anterior belly of digastric muscle
7 Submandibular gland
8 **Submental lymph nodes**
9 Superior thyroid artery
10 Thyroid cartilage
11 Omohyoid muscle
12 Sternohyoid muscle
13 Common carotid artery
14 **Supraclavicular lymph nodes**
15 Anterior jugular vein
16 Thoracic duct
17 Jugular venous arch
18 Left brachiocephalic vein
19 **Superior mediastinal lymph nodes**
20 Retroauricular lymph nodes
21 **Submandibular nodes**
22 **Superficial cervical lymph nodes**
23 **Jugulodigastric lymph nodes and jugular trunk**
24 **Internal jugular vein**
25 External jugular vein
26 **Jugulo-omohyoid lymph nodes**
27 Brachial plexus
28 Cephalic vein
29 Subclavian trunk
30 **Infraclavicular lymph nodes**
31 Subclavian vein
32 Lung
33 Internal thoracic artery and vein



Carotid triangle, left side (lateral aspect). Sternocleidomastoid muscle reflected.

1 Mylohyoid muscle and facial artery
2 Anterior belly of digastric muscle
3 Thyrohyoid
4 **External carotid artery,** superior thyroid artery and vein
5 Omohyoid muscle
6 Thyroid cartilage
7 **Ansa cervicalis**
8 Sternohyoid muscle and superior thyroid artery
9 Stylohyoid muscle
10 Posterior belly of digastric muscle
11 Sternocleidomastoid muscle (reflected)
12 **Superior cervical lymph nodes** and sternocleidomastoid artery
13 Hyoid bone and hypoglossal nerve (n. XII)
14 Splenius capitis and levator scapulae muscles
15 Superior laryngeal artery and internal branch of superior laryngeal nerve
16 **Accessory nerve**
17 Cervical plexus
18 **Internal jugular vein**
19 Facial vein
20 Submental nodes
21 **Thoracic duct**
22 Retroauricular nodes
23 Parotid nodes
24 Occipital nodes
25 **Submandibular nodes**
26 Jugulodigastric nodes } **deep cervical nodes**
27 Jugulo-omohyoid nodes }
28 Jugular trunk
29 Subclavian trunk
30 Infraclavicular nodes
31 External jugular vein



Lymph nodes and veins of head and neck. Dotted lines = border between irrigation areas; arrows: direction of lymph flow.



Neck (anterior aspect).
The superficial fascia has been removed.



Cross-section of the neck at the level of the thyroid gland.
Notice the postion of the three laminae of cervical fascia (23, 24, 25).

1 Mandible
2 **Facial artery and vein**
3 Anterior belly of digastric muscle
4 Mylohyoid muscle
5 Infrahyoid muscles (sternohyoid, sternothyroid and omohyoid)
6 **Anterior jugular veins**
7 **External jugular vein**
8 Sternocleidomastoid muscle
9 **Thyroid gland**
10 **Submandibular gland**
11 Cervical branch of facial nerve
12 Great auricular nerve
13 Transverse cervical nerves
14 Lateral supraclavicular nerves
15 Middle supraclavicular nerves
16 Medial supraclavicular nerves
} Cutaneous branches of cervical plexus
17 Clavicle
18 Platysma muscle
19 Prevertebral lamina of cervical fascia, covering longus colli muscle
20 Vertebral artery and vein
21 Scalenus muscles
22 Trapezius muscle
23 **Superficial lamina of cervical fascia**
24 **Pretracheal lamina of cervical fascia**
25 **Prevertebral lamina of cervical fascia** with sympathetic trunk
26 **Carotid sheath** with common carotid artery, internal jugular vein and vagus nerve
27 Cervical part of sympathetic trunk
28 Carotid sheath



Anterior triangle (anterior aspect). The pretracheal lamina of cervical fascia and left sternocleidomastoid muscle have been removed.



Supra- and infrahyoid muscles. (Schematic drawing.)

1 Mylohyoid muscle
2 Anterior belly of digastric muscle
3 **Facial artery**
4 **Submandibular gland**
5 Great auricular nerve
6 Internal jugular vein and common carotid artery
7 Transverse cervical nerve and omohyoid muscle
8 **Sternohyoid muscle** and **superior thyroid artery**
9 Sternocleidomastoid muscle (sternal head)
10 Left sternocleidomastoid muscle (reflected)
11 Sternocleidomastoid muscle (clavicular head) and lateral supraclavicular nerves
12 Middle **supraclavicular nerves**
13 Medial supraclavicular nerves
14 Mandible
15 **Hyoid bone**
16 Superficial cervical lymph nodes
17 Left superior thyroid artery and external carotid artery
18 **Thyroid cartilage**
19 **Omohyoid muscle** (superior belly)
20 **Internal jugular vein** and branches of ansa cervicalis
21 Thyroid gland and unpaired inferior thyroid vein
22 Posterior belly of digastric muscle
23 **Stylohyoid muscle**
24 **Sternohyoid muscle**
25 **Sternothyroid muscle**



Posterior and carotid triangles (lateral aspect). Superficial dissection.

1 **Parotid gland** and **great auricular nerve**
2 **Lesser occipital nerve**
3 Internal and external jugular veins
4 Retromandibular vein and external carotid artery
5 **Transverse cervical nerve** with communicating branch to cervical branch of facial nerve
6 Trapezius muscle and superficial lamina of cervical fascia
7 Lateral supraclavicular nerves
8 Middle **supraclavicular nerves**
9 Pectoralis major muscle
10 Buccal branch of facial nerve and masseter
11 **Facial artery and vein** and mandibular branch of facial nerve
12 Cervical branch of facial nerve and submandibular gland
13 Thyroid cartilage
14 Omohyoid muscle
15 Sternohyoid muscle
16 Sternocleidomastoid muscle
17 Medial supraclavicular nerves
18 Mandibular branch of facial nerve
19 Cervical branch of facial nerve with communicating branch to transverse cervical nerve



Cutaneous branches of cervical plexus. Erb's point is indicated by an arrowhead. (Schematic diagram.)



Posterior and carotid triangles (lateral aspect). Superficial dissection. The superficial lamina of cervical fascia has been removed to display the cutaneous branches of the cervical plexus and subcutaneous veins.

1 **Lesser occipital nerve**
2 **Internal jugular vein**
3 Splenius capitis muscle
4 **Great auricular nerve**
5 Submandibular nodes
6 Internal carotid artery and vagus nerve
7 **Accessory nerve**
8 Muscular branches of cervical plexus
9 External jugular vein
10 **Posterior supraclavicular nerves**
11 **Middle supraclavicular nerves**
12 Suprascapular artery
13 Pretracheal lamina of fascia of neck
14 Clavicle
15 Parotid gland
16 Mandible
17 Cervical branch of facial nerve
18 Submandibular gland
19 External carotid artery
20 Superior thyroid artery
21 Transverse cervical nerve
22 Superior root of ansa cervicalis
23 Anterior jugular vein
24 Omohyoid muscle
25 Sternohyoid muscle
26 Sternocleidomastoid muscle
27 Intermediate tendon of omohyoid muscle



Neck, superficial dissection (lateral aspect). Sternocleidomastoid muscle has been cut and reflected to display the pretracheal lamina of the cervical fascia.

1 Sternocleidomastoid muscle (reflected) and branch of accessory nerve
2 Facial artery
3 External carotid artery and superior thyroid artery
4 **Internal jugular vein**
5 **Deep cervical lymph nodes** and external jugular vein
6 Omohyoid muscle and **pretracheal lamina of cervical fascia**
7 Anterior jugular vein
8 Pectoralis major muscle
9 **Great auricular nerve**
10 **Lesser occipital nerve**
11 Splenius capitis and levator scapulae muscles
12 Trapezius muscle
13 Scalenus medius muscle and brachial plexus
14 Posterior **supraclavicular nerves**
15 Middle supraclavicular nerve
16 Clavicle and anterior supraclavicular nerves
17 Sternocleidomastoid muscle (reflected)



Neck, deep dissection (lateral aspect). The internal jugular vein has been reflected to expose the carotid artery and vagus nerve.

1 Stylohyoid muscle
2 Facial artery and mylohyoid muscle
3 Anterior belly of digastric muscle
4 **Internal jugular vein,** hypoglossal nerve, and superficial cervical lymph nodes
5 **Superior thyroid artery and vein** and inferior pharyngeal constrictor muscle
6 Thyroid cartilage and vagus nerve
7 **Ansa cervicalis,** omohyoid muscle, and common carotid artery
8 Right superior thyroid artery
9 Scalenus anterior muscle
10 Sternothyroid muscle and inferior thyroid artery
11 Muscular branches of ansa cervicalis to the infrahyoid muscles
12 Inferior thyroid vein
13 Posterior belly of digastric muscle
14 Sternocleidomastoid muscle and lesser occipital nerve
15 **Accessory nerve**
16 Splenius capitis muscle
17 **Cervical plexus**
18 Scalenus posterior muscle
19 Levator scapulae muscle
20 Posterior **supraclavicular nerves**
21 Phrenic nerve
22 Middle supraclavicular nerve
23 **Brachial plexus**
24 Anterior supraclavicular nerves
25 Sternocleidomastoid muscle



Neck, deeper dissection (lateral aspect). **Ansa cervicalis.** The cervical fascia and the clavicle are partly removed. Ansa cervicalis and infrahyoid muscles are displayed.

1 Masseter muscle
2 Mylohyoid muscle and facial artery
3 **External carotid artery** and anterior belly of digastric muscle
4 **Hypoglossal nerve**
5 Thyrohyoid muscle
6 Superior thyroid artery and vein and inferior pharyngeal constrictor muscle
7 Omohyoid muscle (superior belly)
8 **Ansa cervicalis,** thyroid gland and **internal jugular vein**
9 Sternothyroid muscle
10 Sternohyoid muscle
11 **Thoracic duct**
12 Pectoralis minor muscle
13 Pectoralis major muscle
14 Posterior belly of digastric muscle
15 Sternocleidomastoid muscle and lesser occipital nerve
16 Splenius capitis muscle
17 Superficial cervical lymph nodes and accessory nerve
18 **Cervical plexus**
19 Scalenus medius muscle
20 Levator scapulae muscle
21 Scalenus posterior muscle
22 Brachial plexus
23 Transverse cervical artery and clavicle
24 Subclavius muscle
25 **Subclavian artery and vein**
26 Thoracoacromial artery
27 Cephalic vein



1 **Facial artery** and mandible
2 Submental artery
3 Mylohyoid muscle and nerve
4 **Hypoglossal nerve** (lingual branches)
5 Thyrohyoid branch of hypoglossal nerve (n. XII)
6 Anterior belly of digastric muscle
7 Hyoid bone
8 Omohyoid branch of hypoglossal nerve (n. XII)
9 Omohyoid muscle and superior thyroid artery
10 **Ansa cervicalis**
11 Posterior belly of digastric muscle
12 **Hypoglossal nerve** (n. XII)
13 **Vagus nerve** (n. X)
14 Internal carotid artery
15 Superior root of ansa cervicalis
16 **External carotid artery**
17 Cervical plexus
18 Common carotid artery

Neck, submandibular region (lateral aspect). **Hypoglossal nerve** (n. XII). Mandible slightly elevated.



1 **Hypoglossal nerve** (n. XII)
2 Communication from the ventral ramus of the first cervical spinal nerve
3 Atlas
4 Axis
5 Third cervical vertebra
6 Superior root of ansa cervicalis
7 Thyrohyoid branch of hypoglossal nerve
8 Inferior root of ansa cervicalis
9 **Ansa cervicalis**
10 Internal jugular vein
11 Inferior belly of omohyoid muscle
12 Geniohyoid branch of hypoglossal nerve
13 Geniohyoid muscle
14 Hyoid bone
15 Thyrohyoid muscle
16 Superior belly of omohyoid muscle
17 Sternohyoid muscle
18 Sternothyroid muscle
19 Clavicle

Ansa cervicalis.
Innervation of infrahyoid muscles. Cervical plexus and its communication with the hypoglossal nerve. C_1–C_4 = ventral rami of cervical spinal nerves of the first four segments.



Neck, deep dissection (lateral aspect). Clavicle partly removed to show the slit between the scalenus muscles. Internal jugular vein removed.

1. Masseter muscle
2. Mylohyoid muscle and **facial artery**
3. Anterior belly of digastric muscle
4. **Hypoglossal nerve**
5. Sternohyoid muscle
6. Omohyoid muscle, superior thyroid artery and vein
7. Sternothyroid muscle, thyroid cartilage, and pyramidal lobe of thyroid gland
8. Common carotid artery and sympathetic trunk
9. **Ansa cervicalis**
10. **Phrenic nerve,** ascending cervical artery and anterior scalenus muscle
11. Inferior thyroid artery, vagus nerve and internal jugular vein (cut)
12. **Thyroid gland** and unpaired inferior thyroid venous plexus
13. Thoracic duct and left subclavian trunk
14. Subclavius muscle (reflected)
15. Sternocleidomastoid muscle (reflected)
16. Posterior belly of digastric muscle
17. **Superior cervical ganglion** and splenius muscle
18. **Lesser occipital nerve**
19. Internal carotid artery and branch of the glossopharyngeal nerve to the carotid body
20. **External carotid artery**
21. **Cervical plexus** and **accessory nerve**
22. Inferior root of ansa cervicalis
23. Supraclavicular nerve
24. Levator scapulae muscle
25. Scalenus medius muscle and clavicle
26. Transverse cervical artery, brachial plexus, and scalenus posterior muscle
27. **Subclavian artery and vein**
28. Thoracoacromial artery and pectoralis minor muscle
29. Pectoralis major muscle



Neck, deepest dissection (anterolateral aspect). Thyroid gland reflected to expose the esophagus and the recurrent laryngeal nerve.

1	**Superior cervical ganglion** of sympathetic trunk and posterior belly of digastric muscle
1'	Anterior belly of digastric muscle
2	**Facial artery** and common carotid artery (reflected anteriorly)
3	Ascending cervical artery and longus colli muscle
4	Omohyoid muscle and superior thyroid artery
5	**Sympathetic trunk** and sternohyoid muscle
6	Middle cervical ganglion and inferior pharyngeal constrictor muscle
7	Scalenus anterior muscle and phrenic nerve
8	**Thyroid gland** and **inferior thyroid artery**
9	Vagus nerve and esophagus
10	**Stellate ganglion**
11	**Recurrent laryngeal nerve** and trachea
12	Common carotid artery and cervical cardiac branch of vagus nerve
13	Sternocleidomastoid muscle and accessory nerve
14	Splenius capitis muscle
15	Lesser occipital nerve, longus capitis muscle and cervical plexus
16	**Phrenic nerve,** scalenus posterior muscle and levator scapulae muscle
17	Supraclavicular nerves and scalenus medius muscle
18	Brachial plexus and pectoralis major muscle (clavicular head)
19	Transverse cervical artery and clavicle
20	**Subclavian artery**
21	**Thoracoacromial artery** and pectoralis minor muscle
22	First rib, accessory phrenic nerve and subclavian vein
23	Internal jugular vein, thoracic duct and subclavius muscle



Neck and arm, deepest dissection (anterior-lateral aspect). Cervical and brachial plexus and their relation to the blood vessels are shown. Note the location and content of scalene triangle. Sternocleidomastoid muscle and clavicle have been removed; the internal jugular vein was divided to display the roots of cervical and brachial plexus.

1 Lesser occipital nerve
2 Great auricular nerve
3 Cutaneous branches of cervical plexus
4 Supraclavicular nerve
5 Suprascapular nerve and artery
6 **Brachial plexus**
7 **Median nerve** (with two roots) and musculocutaneous nerve
8 Axillary artery
9 Axillary vein
10 Medial brachial cutaneous nerve
11 **Ulnar nerve**
12 Thoracodorsal nerve
13 Parotid gland and facial nerve (cervical branch)
14 **Cervical plexus**
15 Submandibular gland
16 Superior thyroid artery
17 Common carotid artery dividing in internal and external carotid artery and superior root of ansa cervicalis
18 Omohyoid muscle and cervical branch of facial nerve joining the transverse cervical nerve (C_2, C_3)
19 Sternohyoid muscle
20 Transverse cervical nerve and sternothyroid muscle
21 **Common carotid artery** and **vagus nerve**
22 **Phrenic nerve** and scalenus anterior muscle
23 Internal jugular vein
24 Intercostobrachial nerves
25 Long thoracic nerve



◁ **Horizontal section through the neck** at the level of the fissure of glottis, viewed from above.

1 **Thyroid cartilage**
2 **Vocal fold** and **glottis** (rima glottidis)
3 Arytenoid cartilage
4 Common carotid artery
5 **Internal jugular vein**
6 Infrahyoid muscles
7 Lateral thyroarytenoid muscle
8 Sternocleidomastoid muscle
9 Transverse arytenoid muscle
10 Laryngopharynx and inferior constricor muscle of pharynx
11 Longus colli muscle
12 External jugular vein
13 Body of cervical vertebra (C$_5$)
14 **Spinal cord**
15 Vertebra arch
16 Deep muscles of neck (semispinalis cervicis muscle)
17 Trapezius muscle
18 Rima glottidis
19 Levator scapulae muscle
20 Lymph node
21 Semispinalis capitis muscle
22 Splenius capitis muscle



◁ **Section through the neck at the level of larynx.** (MR-Scan.)

1 Hyoid bone
2 Thyroid cartilage
3 **Cervical plexus** (C$_1$-C$_4$)
4 **Phrenic nerve** (C$_4$)
5 Sealenus anterior muscle
6 **Brachial plexus** (C$_5$-T$_1$)
7 Scalenus medius and posterior muscles
8 Subclavian artery
9 Subclavian vein
10 Superior vena cava
11 Cricoid cartilage
12 Thyroid gland
13 **Internal jugular vein**
14 **Common carotid artery**
15 Inferior thyroid vein
16 Ascending aorta
17 Descending aorta
18 Second rib



◁ **Scalene triangle, arrangements of blood vessels, and brachial plexus at the lower part of the neck.** (Schematic diagram.)



Median sagittal section through the vertebral column, head, and thorax of the adult.



Skeleton of the trunk, vertebral column, thorax, and pelvis (posterior aspect).

1 Atlas
2 Axis
3 Seventh cervical vertebra (vertebra prominens)
4 Vertebral canal
5 First rib
6 Clavicle
7 Manubrium sterni
8 Body of sternum
9 Costal arch
10 Acromion
11 Spine of scapula
12 Glenoid cavity (lateral angle of scapula)
13 Eleventh rib
14 Twelfth rib
15 Lumbar vertebrae
16 Sacral promontory
17 Hip bone
18 Symphysis pubis
19 Sacrum
20 Obturator foramen
21 Acetabulum
22 Scapula with coracoid process
23 Posterior superior iliac spine
24 Posterior inferior iliac spine
25 Ischial spine
26 Ischial tuberosity



1 Manubrium sterni
2 **Clavicle**
3 Acromion
4 Coracoid process
5 Glenoid cavity
6 Body of **sternum**
7 Costal cartilage
8 Body of the twelfth **thoracic vertebra**
9 Body of the first **lumbar vertebra**
10 Hip bone
11 Sacral promontory
12 **Sacrum**
13 Anterior superior iliac spine
14 Obturator foramen
15 Atlas
16 Seventh **cervical vertebra**
17 First rib
18 Xiphoid process
19 Twelfth rib
20 Body of the fifth lumbar vertebra
21 Iliac crest
22 **Coccyx**
23 Symphysis pubis

Skeleton of the trunk, vertebral column, pelvis, thorax, and shoulder girdle (anterior aspect).

The trunk is divided into segments best visible in the thoracic region, where each segment consists of a pair of ribs connected anteriorly by the sternum and posteriorly by a thoracic vertebra. In the lumbar part of the vertebral column only vestiges of ribs are present which form what appear to be the transverse processes. In cervical vertebrae, remnants of ribs are part of the transverse processes. Each segment also comprises muscles (e.g. intercostal muscles), nerves, and vessels. However, in the cervical and lumbar region the muscular segments fuse with each other forming large muscle plates, for example, the oblique muscles of the abdomen, while vessels and nerves still retain their segmental pattern.


1
2
C1
6
7
8
9
2
10
11
12
C 2
13
3
1
4
2
C
14
15
16
17
T h
18
2
19
20
16
3
L
2
21
19
16
5
22
S
23
24
25
26

Representative vertebrae from each region of the vertebral column (superior aspect). From top to bottom: atlas (C_1), axis (C_2), cervical vertebra (C), thoracic vertebra (Th), lumbar vertebra (L), and sacrum (S).


9
8
7
6
10
11
16
12

Atlas and axis


4
16
3
27
19
20
16
28
3
29
30
27

Typical cervical and thoracic vertebrae


19
21
16
38
31
3
30
19
26
5
22
24
33
32

Typical lumbar vertebra and sacrum

Representative vertebrae from each region of the vertebral column (lateral aspect, ventral surface on the right).


3
2
19
27
16
18
37
17
20

General organization of ribs and vertebrae. (Schematic diagram.)



General characteristics of the vertebrae. Typical cervical, thoracic, lumbar vertebrae and sacrum.



General characteristics of lumbar vertebrae and sacrum (posterior aspect).

1 Foramen transversarium
2 Vertebral foramen
3 Body of vertebra
4 Superior articular facet
5 Base of sacrum
6 Anterior tubercle of atlas
7 Superior articular facet of atlas
8 Transverse process
9 Posterior tubercle of atlas
10 Dens of axis
11 Superior articular surface
12 Transverse process
13 Arch of vertebra
14 Anterior tubercle of transverse process
15 Posterior tubercle of transverse process
16 Spinous process
17 Shaft of rib
18 Body of vertebra and head of rib articulating with each other (costovertebral joint)
19 Superior articular process
20 Transverse process and tubercle of rib articulating with each other (costotransverse joint)
21 Transverse process
22 Auricular surface
23 Lateral part of sacrum
24 Lateral sacral crest
25 Intermediate sacral crest
26 Median sacral crest
27 Inferior articular facet
28 Superior demifacet for head of rib
29 Inferior demifacet for head of rib
30 Inferior vertebral notch
31 Superior vertebral notch
32 Apex of the sacrum
33 Sacral cornu
34 Coccyx
35 Dorsal sacral foramina
36 Mamillary process
37 Pedicle
38 Inferior articular process

Green = Ribs or homologous processes
Red = Muscular processes (transverse and spinous processes)
Orange = Laminae and articular processes
Yellow = Articular facets



Skeleton of the thorax (anterior aspect).



Skeleton of the thorax (posterior aspect).



Costovertebral articulation (right lateral aspect).

1 Atlas
2 Axis
3 **Cervical vertebrae**
4 First thoracic vertebra
5 First rib
6 Facet for clavicle and clavicular notch
7 **Manubrium sterni**
8 Sternal angle
9 Body of sternum
10 Xiphoid process
11 Twelfth thoracic vertebra and rib
12 Jugular notch
13 Second rib
14 **Costal cartilages**
15 Infrasternal angle
16 **Costal arch**
17 Costotransverse joints between the transverse processes of thoracic vertebra and the tubercles of the ribs
18 Spinous processes
19 Costal angle
20 Transverse processes of lumbar vertebrae
21 Facet for articulation with rib
22 Tubercle of rib
23 Superior facet for articulation with head of rib
24 Articulation of head of rib with two vertebrae
25 Inferior facet for articulation with head of rib
26 Body of thoracic vertebra
27 Body or shaft of rib


1
2
14
3
4
4
5
6
17
7
8
9
10
11
12
16
13

Skeleton of the thorax (right lateral aspect).

1 Atlas
2 Axis
3 **Cervical vertebrae**
4 Seventh cervical vertebra (vertebra prominens)
5 First rib
6 Facet for clavicle
7 **Manubrium sterni**
8 Sternal angle
9 Body of sternum
10 Costal arch
11 Tenth rib
12 Eleventh rib
13 Twelfth rib
14 Spinous processes of cervical vertebrae
15 Spinous processes of thoracic vertebrae
16 Spinous processes of lumbar vertebrae
17 Costal angle
18 Intervertebral foramina
19 Intervertebral discs
20 **Cervical curvature**
21 **Thoracic curvature**
22 **Lumbar curvature**
23 Sacrum
24 Coccyx


1
2
3
20
4
T1
T6
15
21
18
19
T12
L1
16
22
19
L5
23
24

Vertebral column (right lateral aspect).



Disarticulated ribs. The twelve ribs arranged in a craniocaudal direction, first rib at top. I–XII = pairs of ribs; 1 = head of rib; 2 = neck of rib; 3 = tubercle of rib; 4 = body of rib.

The head of a typical rib articulates with the bodies of adjacent vertebrae and the intervening intervertebral disc. The first seven ribs are directly connected through the costal cartilages (not depicted) to the sternum (true ribs) while the remaining five ribs are only indirectly connected to the sternum (false ribs, ribs VIII to X) or end freely in the lateral wall of the trunk (floating ribs, ribs XI and XII).



Two **thoracic vertebrae** (left lateral aspect).



Ligaments of thoracic vertebrae and costovertebral joints (left anterolateral aspect).
In the upper joint, most of the radiate ligament and the anterior part of the head of the rib have been removed to expose the two joint cavities and the interposed intra-articular ligament.

1 Superior demifacet for head of rib
2 Body of vertebra
3 Inferior demifacet for head of rib
4 Intervertebral disc
5 Inferior vertebral notch
6 Superior articular facet and superior articular process
7 Pedicle
8 Transverse process and facet for tubercle of rib
9 Inferior articular process
10 Intervertebral foramen
11 Spinous process
12 Anterior longitudinal ligament
13 Intraarticular ligament
14 Radiate ligament
15 Superior costotransverse ligament
16 Body of rib
17 Intertransverse ligament



Location of costovertebral joints (superior aspect).



Costovertebral joints. Two thoracic vertebrae with an articulating rib (separated). Axis of movement indicated by dotted line. Blue = articular facets. (Schematic diagram.)

1 Superior articular process
2 Vertebral canal
3 Body of thoracic vertebra
4 Costovertebral joint (articular facets)
5 Tubercle of rib
6 Head of rib
7 Shaft or body of rib
8 Transverse process with articular facet
9 Spinous process
10 Costotransverse joint (articular facets)



Median-sagittal section of the bodies of the vertebrae showing the **intervertebral discs,** each of which consists of an outer laminated portion and an inner core.



Ligaments of the vertebral column (dorsal aspect).

1 Body of vertebra
2 **Intervertebral disc**
  a Outer portion (anulus fibrosus)
  b Inner core **(nucleus pulposus)**
3 Anterior longitudinal ligament
4 Posterior longitudinal ligament and spinal dura mater
5 Transverse process of lumbar vertebra
6 Sacrum
7 **Supraspinous ligament**
8 Interspinous ligament
9 **Intertransverse ligament**
10 Superior costotransverse ligament
11 Transverse process of thoracic vertebra
12 Rib
13 **Ligamentum flavum**
14 Spinous process
15 Intervertebral foramen



The two caudal lumbar vertebrae and the sacrum with their intervertebral discs (anterior aspect). Anterior longitudinal ligament removed.



Ligaments of the vertebral column, thoracic part (left lateral aspect).



Atlas and axis (from above).



Median atlantoaxial joint and transverse ligament of atlas (from above). Dens of axis partly severed.

1 Anterior arch of **atlas** with anterior tubercle
2 Superior articular facet of atlas
3 **Foramen transversarium** and transverse process
4 Posterior arch of atlas and vertebral artery
5 Posterior tubercle of atlas
6 **Dens of axis**
7 Superior articular surface of axis
8 Body of axis
9 Pedicle and lamina of axis
10 Spinous process
11 Inferior articular process
12 Transverse process and vertebrarterial foramen (foramen transversarium)
13 **Median atlantoaxial joint** (anterior part)
14 Articular capsule of **atlantooccipital joint**
15 Transverse ligament of atlas
16 Occipital bone
17 **Atlantooccipital joint**
18 **Lateral atlantoaxial joint**
19 Third cervical vertebra
20 Superior longitudinal band of cruciform ligament
21 Alar ligaments
22 Transverse ligament of atlas
23 Inferior longitudinal band of cruciform ligament
24 Spinous process of axis
25 Dura mater



Atlantooccipital and atlantoaxial joints (posterior aspect). Posterior part of occipital bone, posterior arch of atlas and axis have been removed to show the cruciform ligament.



Atlas and axis. Left oblique posterolateral aspect, demonstrating the articulation of the dens of axis with atlas (cf. arrows).



Occipital bone, atlas and axis (anterior aspect).



Occipital bone, atlas and axis (left lateral aspect).

1 External occipital protuberance
2 Foramen magnum
3 Atlantooccipital joint
4 Transverse process of atlas
5 Membrana tectoria
6 Posterior longitudinal ligament
7 Spinous process of third cervical vertebra
8 Occipital condyle
9 Lateral atlantoaxial joint
10 Occipital bone
11 Atlas
12 Axis
13 Dens of axis
14 Hypoglossal canal
15 Spinous processes of axis
16 Anterior longitudinal ligament



Cervical vertebral column and skull with ligaments (posterior aspect). Posterior arch of atlas and axis removed to show the membrana tectoria.



Cervical vertebral column and skull with ligaments (anterior aspect). Anterior part of occipital bone removed.



1 Axillary vein
2 Intercostobrachial nerves
3 Subscapularis muscle and thoracodorsal nerve
4 Long thoracic nerve, lateral thoracic artery and vein
5 Latissimus dorsi muscle
6 **External intercostal** muscles
7 **Serratus anterior** muscle
8 Lateral cutaneous branches of intercostal nerves
9 External abdominal oblique muscle
10 Clavicle (divided)
11 Second rib (costo-chondral junction)
12 **Internal intercostal muscles**
13 External intercostal membrane
14 Position of xiphoid process
15 Costal arch or margin
16 Anterior layer of rectus sheath

Muscles of the thorax, superficial layer (lateral aspect). Upper limb elevated. Pectoralis major and minor muscles have been removed.



Effect of intercostal muscles on the costovertebral and costotransverse joints. Axes of movement indicated by lines; direction of movements indicated by arrows.



A Action of internal intercostal muscles (expiration)
B Action of external intercostal muscles (inspiration)



Anterior thoracic wall (posterior aspect). Diaphragm partly removed, posterior layer of rectus sheath fenestrated on both sides.

1 Sternocleidomastoid muscle (divided)
2 Clavicle
3 Sternothyroid muscle
4 **Internal intercostal muscle**
5 **Transversus thoracis muscle**
6 Intercostal arteries and nerves
7 Musculophrenic artery
8 Superior epigastric artery and vein
9 Diaphragm (divided)
10 Rectus abdominis muscle

11 Subclavian artery and brachial plexus
12 First rib
13 Internal thoracic artery and vein
14 Sternum
15 Innermost intercostal muscle
16 Intercostal artery and vein
17 Xiphoid process
18 Linea alba and posterior layer of rectus sheath
19 **Transversus abdominis muscle**



Superficial muscles of the anterior thoracic and abdominal wall. The fascia of pectoralis major muscle and the abdominal wall have been removed; the anterior layer of the sheath of the rectus abdominis muscle is displayed.

1 Sternohyoid muscle
1 Sternocleidomastoid muscle
3 Supraclavicular nerves (branches of cervical plexus)
4 Deltoid muscle
5 **Pectoralis major muscle**
6 **Anterior cutaneous branches of intercostal nerves**
7 External abdominal oblique muscle
8 **Lateral cutaneous branches of intercostal nerves**
9 Umbilicus and umbilical ring
10 Clavicle
11 Cephalic vein
12 Serratus anterior muscle
13 Linea alba
14 **Sheath of rectus abdominis** muscle (anterior layer)
15 Inguinal ligament



Thoracic wall I (anterior aspect). Left pectoralis major muscle has been divided and reflected. Note the connection of the cephalic vein with the subclavian vein. Arrow: medial pectoral nerve.

1 Mandible
2 Facial artery
3 Submandibular gland
4 Hyoid bone
5 Thyroid cartilage and sternohyoid muscle
6 Clavicle
7 Subclavius muscle
8 Second rib
9 Anterior cutaneous branches of intercostal nerves
10 External intercostal membrane
11 Parotid gland
12 External carotid artery
13 Sternocleidomastoid muscle and cutaneous branches of cervical plexus
14 Supraclavicular nerves
15 Pectoralis major muscle and lateral pectoral nerves
16 Thoracoacromial artery and subclavian vein
17 **Pectoralis minor muscle**
18 **Median and ulnar nerve**
19 Thoracoepigastric vein
20 Cephalic vein and long head of biceps brachii muscle
21 **Lateral thoracic artery and long thoracic nerve**
22 Lateral cutaneous branches of intercostal nerve
23 Latissimus dorsi muscle
24 Median nerve
25 Axillary artery
26 Intercostobrachial nerves
27 **Thoracodorsal nerve**
28 Long thoracic nerve
29 Latissimus dorsi muscle
30 **Serratus anterior muscle**
31 Thoracoacromial artery
32 Clavicle
33 External intercostal muscle
34 Third rib
35 **Internal intercostal muscle**
36 Anterior intercostal artery and vein
37 Costal arch or margin



Thoracic wall (lateral aspect). Pectoralis major and minor muscles have been removed. A section of the 4th rib has been cut and removed to display the intercostal vessels and nerve.



1 Anterior perforating branches of intercostal nerve
2 Mammary gland
3 External abdominal oblique muscle
4 Rectus sheath (anterior layer)
5 Sternocleidomastoid muscle
6 Clavicle
7 Lateral thoracic artery and vein
8 Pectoralis major muscle
9 **Internal thoracic artery and vein**
10 Serratus anterior muscle
11 **Superior epigastric artery and vein**
12 Costal margin
13 Rectus abdominis muscle
14 Cut edge of the anterior layer of the rectus sheath
15 Subclavian artery
16 Highest intercostal artery
17 Internal thoracic artery
18 Musculophrenic artery
19 Superficial epigastric artery
20 Deep circumflex iliac artery
21 Superior epigastric artery
22 Inferior epigastric artery
23 Superficial circumflex iliac artery

Thoracic wall II (anterior aspect). Dissection of the **internal thoracic artery and vein.** Left pectoralis major muscle partly removed. Anterior lamina of the rectus sheath on the left side has been removed.



Main arteries of thoracic and abdominal wall.



1 Deltoid muscle
2 Cephalic vein
3 Pectoralis major muscle (divided)
4 **Internal intercostal muscle**
5 **Intercostal artery and vein** (intercostal space, fenestrated)
6 Serratus anterior muscle
7 **External abdominal oblique muscle**
8 **Anterior layer of rectus sheath**
9 Iliac crest
10 Superficial epigastric vein
11 Superficial circumflex iliac vein
12 Saphenous opening
13 Superficial inguinal lymph nodes
14 Superficial external pudendal veins
15 Great saphenous vein
16 Nipple
17 Costal margin
18 Subcutaneous fatty tissue
19 Umbilicus
20 Anterior layer of rectus sheath
21 Rectus abdominis muscle
22 Posterior layer of rectus sheath
23 **Internal abdominal oblique muscle**
24 **External abdominal oblique muscle**
25 **Transversus abdominis muscle**
26 Transversal fascia and peritoneum
27 Psoas major muscle
28 Body of lumbar vertebra (L_4)
29 Quadratus lumborum muscle
30 Medial tract of erector spinae muscle
31 Lateral tract of erector spinae muscle (longissimus and iliocostalis muscles)
32 Small intestine
33 Left ureter
34 **Abdominal aorta**
35 **Inferior vena cava**
36 Descending colon
37 Spinous process

Thoracic and abdominal wall I. Right pectoralis major and minor muscles are divided. Muscles of thoracic and abdominal wall on right side are displayed.



Horizontal section of the trunk at the level of the umbilicus, superior to arcuate line (inferior aspect).



Thoracic and abdominal wall II. Right pectoralis major and minor muscles and anterior layer of rectus sheath have been removed on the right side.



Horizontal section through the body at the level of 4th lumbar vertebra; seen from below. (CT-Scan.)

1	Deltoid muscle
2	Pectoralis major muscle (divided)
3	**Internal intercostal muscle**
4	Intercostal artery and vein
5	**Rectus abdominis muscle**
6	Tendinous intersections
7	**External abdominal oblique muscle**
8	Anterior superior iliac spine
9	Superficial circumflex iliac vein
10	Superficial epigastric vein
11	Great saphenous vein
12	Cephalic vein
13	**Pectoralis major muscle**
14	Anterior cutaneous branches of intercostal nerves
15	Nipple
16	Linea alba
17	**Anterior layer of rectus sheath**
18	Umbilicus
19	**Inguinal ligament**
20	Pyramidalis muscle
21	Superficial inguinal ring and spermatic cord
22	Suspensory ligament of penis
23	Longissimus and iliocostalis muscles
24	Multifidus muscle
25	Quadratus lumborum muscle
26	Latissimus dorsi muscle
27	Psoas major muscle
28	Spinous process
29	Body of 1st lumbar vertebra
30	**Transversus abdominis muscle**
31	**Internal abdominal oblique muscle**



1 Costal margin
2 **Rectus abdominis muscle**
3 External abdominal oblique muscle (reflected)
4 Thoracoabdominal (intercostal) nerves with accompanying vessels
5 Internal abdominal oblique muscle
6 **Arcuate line** (arrow)
7 **Inferior epigastric artery and vein**
8 Ilioinguinal nerve
9 Position of deep inguinal ring
10 Superficial inguinal lymph nodes
11 Great saphenous vein
12 Linea alba
13 Iliohypogastric nerve
14 **Pyramidalis** muscle
15 Spermatic cord
16 Fundiform ligament of penis

Thoracic and abdominal wall III. External abdominal oblique muscle has been divided and reflected on both sides. The right rectus muscle has been reflected medially to display the posterior layer of rectus sheath. Arrow: location of arcuate line.



Horizontal-section of the trunk superior to arcuate line. (Schematic drawing.)

1 Medial column of intrinsic muscles of the back
2 Lateral column of erector spinae muscle
3 Thoracolumbar fascia with superficial and deep layer
4 External oblique muscle
5 Internal oblique muscle
6 Transversus abdominis muscle
7 Transversalis fascia
8 Posterior layer of rectus sheath
9 Rectus abdominis muscle
10 Anterior layer of rectus sheath



1 **Rectus abdominis muscle** (reflected)
2 External abdominal oblique muscle (divided)
3 Posterior layer of rectus sheath
4 Umbilical ring
5 **Internal abdominal oblique muscle**
6 Arcuate line (arrow)
7 Inguinal ligament
8 **Inferior epigastric artery and vein** and rectus abdominis muscle (divided and reflected)
9 Costal margin
10 Linea alba
11 Tendinous intersection
12 Iliohypogastric nerve
13 **Ilioinguinal nerve**
14 **Pyramidalis** muscle
15 Spermatic cord

Thoracic and abdominal wall IV. External abdominal oblique muscle has been divided and reflected on both sides. The right rectus muscle has been cut and reflected to display the posterior layer of rectus sheath. Arrow: location of arcuate line.



1 Peritoneum
2 Transversalis fascia (green)
3 Transversus abdominis muscle
4 Internal abdominal oblique muscle
5 External abdominal oblique muscle
6 Fascia of external abdominal oblique muscle (green)
7 Skin
8 Linea alba
9 Rectus abdominis muscle

Transverse sections through the abdominal wall superior (a) and inferior (b) to arcuate line.



Thoracic and abdominal wall (schematic drawing). Note the segmental organization of the blood vessels and nerves. Right side: superficial layers; left side: deeper layers.



Horizontal section of the abdominal wall (from above) showing the location of the intercostal arteries (left side) and nerves (right side).

1 Sternocleidomastoid muscle
2 Deltoid muscle
3 Pectoralis major muscle
4 **Anterior cutaneous branches of intercostal nerves**
5 Cut edge of anterior layer of rectus sheath
6 **Rectus abdominis muscle**
7 Tendinous intersection
8 External abdominal oblique muscle
9 Lateral femoral cutaneous nerve
10 Femoral vein
11 Great saphenous vein
12 Medial supraclavicular nerves
13 Pectoralis minor muscle (reflected) and medial pectoral nerves
14 Axillary vein
15 Long thoracic nerve and lateral thoracic artery
16 Internal thoracic artery
17 **Intercostal nerves**
18 **Lateral cutaneous branches of intercostal nerves**
19 Superior epigastric artery
20 Thoracoabdominal (intercostal) nerves
21 Transversus abdominis muscle
22 Posterior layer of rectus sheath
23 **Inferior epigastric artery**
24 Lateral femoral cutaneous nerve
25 Inguinal ligament and ilioinguinal nerve
26 Femoral nerve
27 Femoral artery
28 Spermatic cord
29 Testis
30 **Posterior intercostal arteries**
31 Internal abdominal oblique muscle
32 Lateral cutaneous branch of intercostal nerve
33 Dorsal branch of spinal nerve
34 Latissimus dorsi muscle
35 Deep muscles of the back (medial and lateral tract)
36 Anterior layer of rectus sheath
37 Posterior layer of rectus sheath
38 Thoracolumbar fascia
39 Spinal cord
40 Aorta
41 Ventral root } of spinal
42 Dorsal root } nerve


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29

Thoracic wall and abdominal wall V. Right side: superficial layers; left side: deeper layers (anterior aspect). Pectoralis major and minor muscles, the external and internal intercostal muscles on the left side have been removed to display the intercostal nerves. The anterior layer of rectus sheath, the left rectus abdominis muscle and the external and internal abdominal oblique muscle have been removed to show the thoracoabdominal nerves within the abdominal wall.



Abdominal wall with vessels and nerves. The left rectus abdominis muscle has been divided and reflected to display the inferior epigastric vessels. The left internal abdominal oblique muscle has been removed to show the thoracoabdominal nerves.

1 **Rectus abdominis muscle**
2 Tendinous intersection
3 **Internal abdominal oblique muscle**
4 External abdominal oblique muscle (reflected)
5 Anterior superior iliac spine
6 Ilioinguinal nerve
7 Spermatic cord
8 Costal margin
9 Superior epigastric artery
10 **Thoracoabdominal** (intercostal) **nerves**
11 Posterior layer of rectus sheath
12 **Transversus abdominis muscle**
13 Semilunar line
14 Arcuate line
15 **Inferior epigastric artery**
16 Inguinal ligament



Arteries and nerves which supply the thoracic and abdominal wall. Note their segmental arrangement. (Schematic drawing.)

1 Internal thoracic artery
2 Intercostal artery
3 Superior epigastric artery
4 Musculophrenic artery
5 Gallbladder
6 Rectus abdominis muscle
7 External abdominal oblique muscle
8 Deep circumflex iliac artery
9 Superficial epigastric artery
10 Inferior epigastric artery
11 Superficial circumflex iliac artery
12 Femoral artery
13 Intercostal nerve
14 Thoracoabdominal nerve (T_{10})
15 Transversus abdominis muscle
16 Posterior layer of the rectus sheath
17 Iliohypogastric nerve (L_1)
18 Ilioinguinal nerve (L_1)
19 Spermatic cord
20 Genitofemoral nerve (L_1, L_2)
  a Femoral branch
  b Genital branch



Inguinal canal in the male I. Dissection of superficial layer, right side (anterior aspect).



Inguinal canal in the male II, right side (anterior aspect). The external abdominal oblique muscle has been divided to display the inguinal canal.



Regions and reference lines
for delineating surface projections.

Reference lines and regions

1 Median line
2 Lateral sternal line
3 Parasternal line
4 Left lateral or midclavicular line
5 Midaxillary line
6 Transpyloric plane
7 Transtubercular plane
8 Hypochondriac region
9 Epigastric region
10 Lumbar region
11 Umbilical region
12 Iliac region
13 Hypogastric region

1 Anterior superior iliac spine
2 Medial crus of inguinal ring
3 Inguinal ligament
4 Lateral crus of inguinal ring
5 Superficial epigastric vein
6 Saphenous opening
7 **Superficial inguinal lymph nodes**
8 **Great saphenous vein**
9 Anterior cutaneous branches of femoral nerve
10 **Anterior layer of rectus sheath**
11 Intercrural fibers
12 **Superficial inguinal ring**
13 Spermatic cord and genital branch of genitofemoral nerve
14 Penis
15 Aponeurosis of external abdominal oblique muscle (divided and reflected)
16 **Internal abdominal oblique muscle**
17 Ilioinguinal nerve
18 Anterior cutaneous branches of iliohypogastric nerve
19 Superficial external pudendal veins



Inguinal canal in the male III. Deep dissection (anterior aspect, right side). Spermatic cord with exception of ductus deferens (probe) has been divided and reflected.



General characteristics of lower part of anterior abdominal wall and inguinal canal. (Schematic drawing.)

1 Internal abdominal oblique muscle (reflected)
2 Transversus abdominis muscle
3 Inguinal ligament
4 **Spermatic cord** with the exception of the ductus deferens (divided and reflected)
5 **Ductus deferens** and interfoveolar ligament
6 Superficial circumflex iliac artery
7 **Femoral artery and vein**
8 Superficial inguinal lymph nodes and inguinal lymph vessel
9 **Inferior epigastric artery and vein**
10 Falx inguinalis or conjoint tendon (cut)
11 Pubic branch of inferior epigastric artery
12 Superficial inguinal ring
13 Penis
14 External abdominal oblique muscle
15 Anterior superior iliac spine
16 Intercrural fibers
17 Fascia lata and sartorius muscle
18 Saphenous opening and great saphenous vein
19 Deep inguinal ring
20 Skin of scrotum and dartos muscle
21 Cremaster muscle
22 Internal spermatic fascia
23 Ductus deferens
24 Epididymis
25 Peritoneum (blue)
26 Remnant of processus vaginalis
27 Tunica vaginalis testis
28 Rectus abdominis muscle
29 Spermatic cord with ductus deferens covered by external spermatic fascia
30 Anterior layer of rectus sheath
31 Suspensory ligament of penis
32 **Testis and epididymis**
33 Ductus deferens
34 Pampiniform venous plexus and testicular artery
35 Inferior epigastric artery
36 Lateral femoral cutaneous nerve
37 Ilioinguinal nerve
38 **Femoral nerve**
39 Sartorius muscle
40 Deep dorsal vein of penis

Inguinal hernias may either pass through the inguinal canal lateral to the inferior epigastric artery (indirect or lateral inguinal hernias, A and C) or directly penetrate the abdominal wall through the inguinal triangle located medial to the inferior epigastric artery (direct or medial inguinal hernias, B). The lateral hernias can be congenital if the vaginal process remains open (C) or acquired (A) if the hernia develops independently of a patent processus vaginalis.

Femoral hernias generally protrude through the femoral ring below the inguinal ligament. Proper assessment of the site of herniation requires the identification of both the inguinal ligament and the epigastric artery.


1
2
28
3
19
33
34
8
17
18
13
15
35
36
3
37
38
12
7
31
37
29
39
40
32

Inguinal and femoral region in the male (anterior aspect). On the right, the spermatic cord was dissected to display the ductus deferens and the accompanying vessels and nerves. The fascia lata on the left side has been removed.


2
1
14
19
28
20
21
22
23
26
9
25
30
13
29
27
32
A
B
III
II
I
C
III
II
I

Layers of spermatic cord and types of hernias. Left: Normal situation; middle: Location of acquired inguinal hernias; A = indirect; B = direct inguinal hernia. Right: congenital indirect inguinal hernia (C); the vaginal process remained open.

I = Median umbilical fold, containing urachus chord.
II = Medial umbilical fold with remnants of umbilical artery and vein.
III = Lateral umbilical fold with inferior epigastric artery and vein.



Inguinal region in the female (anterior aspect). Left side: superficial layer; right side: external and internal abdominal oblique muscle divided and reflected.

1 Aponeurosis of external abdominal oblique muscle
2 Internal abdominal oblique muscle (divided and reflected)
3 Transversus abdominis muscle
4 Superficial circumflex iliac artery and vein
5 Superficial inguinal ring with fat pad
6 Medial and lateral crural fibers
7 **Round ligament** (ligamentum teres uteri)
8 Labium majus pudendi
9 Anterior layer of rectus sheath
10 Superficial epigastric artery and vein
11 **Inguinal ligament**
12 Cutaneous branch of ilioinguinal nerve
13 Superficial inguinal lymph nodes
14 Entrance of round ligament into the labium majus
15 External pudendal artery and vein
16 Position of deep inguinal ring
17 **Ilioinguinal nerve**
18 Internal abdominal oblique muscle
19 Pubic branch of inferior epigastric artery
20 Genital branch of genitofemoral nerve
21 Fat pad of inguinal canal
22 Ilioinguinal nerve
23 Sheath of round ligament (inguinal canal)
24 Transversalis fascia



Inguinal canal of the female I (anterior aspect, right side). The external abdominal oblique muscle has been divided and reflected, to display the ilioinguinal nerve and the round ligament.



Inguinal canal of the female II (anterior aspect, right side). The external and internal abdominal oblique muscle have been divided and reflected to show the content of the inguinal canal.



1 Occipital belly of occipitofrontalis muscle
2 Splenius capitis muscle
3 Sternocleidomastoid muscle
4 **Trapezius muscle**
5 Deltoid muscle
6 Teres minor muscle
7 Medial margin of scapula
8 **Rhomboid major muscle**
9 Teres major muscle
10 **Latissimus dorsi muscle**
11 Thoracolumbar fascia
12 External abdominal oblique muscle
13 Iliac crest
14 **Gluteus maximus muscle**
15 Position of last coccygeal vertebra
16 Anus
17 Semispinalis capitis muscle
18 Splenius cervicis muscle
19 Levator scapulae muscle
20 Spine of scapula
21 Rhomboideus minor muscle
22 Infraspinatus muscle
23 Triceps brachii muscle
24 Serratus anterior muscle
25 **Iliocostalis muscle**
26 External intercostal muscle
27 **Serratus posterior inferior muscle**
28 Latissimus dorsi muscle (cut edge)
29 Fascia over gluteus medius muscle
30 Long head of biceps femoris muscle

Muscles of the back I. Superficial layer on the left, deeper layer on the right. Right latissimus dorsi and trapezius muscles are removed.



Muscles of the back II. Dissection of deep muscles. Erector spinae muscle.



Origin and insertion of iliocostalis and longissimus muscles. (Schematic drawing.)

1 Rectus capitis posterior minor muscle
2 Rectus capitis posterior major muscle
3 Obliquus capitis inferior muscle
4 Spinous process of axis
5 Semispinalis cervicis muscle
6 Spinous process of seventh vertebra
7 **Iliocostalis cervicis muscle**
8 External intercostal muscles
9 **Iliocostalis thoracis muscle**
10 **Longissimus thoracis muscle**
11 **Iliocostalis lumborum muscle**
12 Internal abdominal oblique muscle
13 Semispinalis capitis muscle (divided)
14 **Longissimus capitis muscle**
15 Levator scapulae muscle
16 **Longissimus cervicis muscle**
17 Rhomboid major muscle
18 **Spinalis thoracis muscle**
19 Serratus posterior inferior muscle (reflected)
20 Spinous process of second lumbar vertebra
21 Iliac crest
22 Mastoid process



Muscles of the back III. Transversospinal muscles, deepest layer on the right, where all parts of semispinalis and multifidus muscles have been removed.



Medial column of intrinsic muscles of the back. Transversospinal and intertransversal system. (Schematic drawing.)

1 Rectus capitis posterior minor muscle
2 Obliquus capitis superior muscle
3 Rectus capitis posterior major muscle
4 Obliquus capitis inferior muscle
5 Spinous process of axis
6 **Longissimus capitis muscle**
7 Trapezius muscle (reflected) and accessory nerve (n. XI)
8 Spinous processes
9 Rhomboid major muscle
10 Transverse processes of thoracic vertebrae
11 Teres major muscle
12 Intertransverse ligaments
13 **Levatores costarum muscles**
14 **Rotatores muscles**
15 Tendons of iliocostalis muscle
16 Intertransversarii lumborum muscle (lateral)
17 Iliac crest
18 Gluteus maximus muscle
19 Semispinalis capitis muscle
20 **Semispinalis cervicis muscle**
21 Semispinalis thoracis muscle
22 **External intercostal muscles**
23 **Multifidus muscle**
24 Intertransversarii posterior cervicis muscle
25 Spinalis thoracis muscle



Innervation of the back I. Superficial (left) and deeper (right) layers. Right trapezius and latissimus dorsi muscles removed.

1 Occipital belly of occipitofrontalis muscle
2 Splenius capitis muscle
3 **Trapezius muscle**
4 **Medial cutaneous branches of dorsal rami of spinal nerves**
5 Medial margin of scapula
6 Rhomboid major muscle
7 **Latissimus dorsi muscle**
8 **Lateral cutaneous branches of dorsal rami of spinal nerves**
9 Thoracolumbar fascia
10 External abdominal oblique muscle
11 Iliac crest
12 Last coccygeal vertebra
13 Anus
14 Greater occipital nerve
15 Third occipital nerve
16 Lesser occipital nerve
17 Cutaneous branches of cervical plexus
18 Levator scapulae muscle
19 Deltoid muscle
20 **Rhomboid major and minor muscles**
21 Upper lateral cutaneous nerve of arm (branch of axillary nerve)
22 **Teres major muscle**
23 Iliocostalis thoracis muscle
24 Serratus posterior inferior muscle
25 Superior cluneal nerves
26 Middle cluneal nerves
27 Inferior cluneal nerves
28 Posterior femoral cutaneous nerve

▷

To page 213:

1 **Trapezius muscle**
2 Infraspinatus muscle
3 Left **latissimus dorsi muscle**
4 Thoracolumbar fascia
5 Splenius cervicis muscle
6 Serratus posterior superior muscle
7 **Medial branches of dorsal rami of thoracic spinal nerves**
8 **Lateral branches of dorsal rami of thoracic spinal nerves**
9 Iliocostalis muscle
10 Serratus posterior inferior muscle
11 Latissimus dorsi muscle (reflected)



Innervation of the back II. Dissection of the dorsal branches of spinal nerves. On the right, longissimus thoracis muscle has been removed and iliocostalis muscle laterally reflected.



General characteristics of the innervation of the back. Distribution of dorsal branches of spinal nerves. Note the segmental arrangement of the innervation of the dorsal part of the trunk. (Schematic drawing.)



Position and branches of spinal nerves in one segment of thoracic wall. (Schematic drawing.)

1 Greater occipital nerve (C_2)
2 Suboccipital nerve (C_1)
3 **Medial branches of dorsal rami of spinal nerves**
4 **Lateral branches of dorsal rami of spinal nerves**
5 Superior cluneal nerves (L_1–L_3)
6 Middle cluneal nerves (S_1–S_3)
7 Inferior cluneal nerves (derived from branches of the sacral plexus, ventral rami)
8 Lesser occipital nerve
9 Great auricular nerve
10 Trapezius muscle
11 Deltoid muscle
12 Latissimus dorsi muscle
13 Gluteus maximus muscle
14 External intercostal muscle
15 Internal intercostal muscle
16 Innermost intercostal muscle
17 Dorsal ramus of spinal nerve
18 **Spinal nerve** and **spinal ganglion**
19 Sympathetic trunk with ganglion
20 Intercostal nerve
21 Lateral cutaneous branch } of **intercostal nerve**
22 Anterior cutaneous branch }



Innervation of the back III. Deeper layer (dorsal aspect).

1 Semispinalis capitis muscle
2 Left splenius capitis muscle (cut and reflected)
3 Left splenius cervicis muscle (cut and reflected)
4 Semispinalis thoracis muscle
5 **Spinalis thoracis muscle**
6 Latissimus dorsi muscle (reflected)
7 Iliac crest
8 Lesser occipital nerve
9 Splenius capitis muscle
10 Levator scapulae muscle
11 **Splenius cervicis muscle**
12 Serratus posterior superior muscle
13 Scapula
14 **Medial branches of dorsal rami of spinal nerves**
15 Rib and external intercostal muscle
16 Iliocostalis thoracis muscle
17 **Lateral branches of dorsal rami of spinal nerves**
18 Multifidus muscle
19 Superior cluneal nerves



Lumbar portion of spinal cord. Note the relation between the nervous and muscular segments.



Terminal part of spinal cord. Dura removed.



Innervation of the back IV. Spinal cord in the vertebral canal (opened). Longissimus dorsi muscle has been removed and iliocostal muscle reflected.

1 Cerebellomedullary cistern and cerebellum
2 Medulla oblongata
3 Greater occipital nerve (C_2)
4 Third cervical nerve (C_3)
5 Dorsal primary ramus
6 Dorsal roots
7 Spinal ganglion
8 Spinal dura mater
9 Spinal arachnoid mater
10 Filum terminale
11 Conus medullaris
12 Cauda equina
13 Lateral branches of dorsal rami of spinal nerves
14 Ventral ramus of spinal nerve (intercostal nerve)
15 Iliocostalis muscle



Thoracic portion of spinal cord (dorsal aspect). Vertebral canal and dura mater opened.

1 Arch of vertebra (divided)
2 Spinal nerve with meningeal coverings
3 Dorsal roots of thoracic spinal nerves
4 Spinal cord (thoracic portion)
5 Spinal ganglia with meningeal coverings
6 Pia mater with blood vessels
7 Dura mater (opened)
8 Denticulate ligament
9 Lateral branch of dorsal ramus
10 Dorsal ramus of spinal nerve (dividing into a medial and lateral branch)
11 Medial branch of dorsal ramus of spinal nerve
12 Spinal dura mater
13 Spinal nerves of sacral segments
14 Filum terminale



Terminal part of spinal cord with dura mater (dorsal aspect). Dorsal part of sacrum removed.



Horizontal section of the neck. Dissection of the second cervical spinal nerve. Posterior surface at top of figure.



Meningeal coverings of the spinal cord (anterior aspect). (Schematic drawing.)

1 Trapezius muscle
2 Semispinalis capitis muscle
3 **Dorsal ramus of spinal nerve**
4 Sternocleidomastoid muscle
5 Platysma muscle
6 **Dorsal and ventral roots of spinal nerves**
7 **Spinal ganglion**
8 Posterior belly of digastric muscle
9 **Ventral ramus of spinal nerve**
10 Vertebral artery
11 Great auricular nerve
12 Superficial temporal artery
13 Styloid process
14 Internal jugular vein and internal carotid artery
15 Rectus capitis posterior major muscle
16 Dura mater and subarachnoid space
17 Denticulate ligament
18 Vertebral artery
19 Parotid gland
20 Dens of axis (divided) and inferior articular facet of atlas
21 Longus capitis muscle
22 Pharyngeal cavity
23 Medial pterygoid muscle
24 Periosteum of vertebral canal
25 Posterior spinal arteries
26 Anterior spinal artery

Meningeal coverings

27 Dura mater
28 Subdural space
29 Extradural or epidural space with venous plexus and fatty tissue
30 Arachnoid (green)
31 Subarachnoid space
32 Pia mater (pink)
33 Nucleus pulposus
34 Crus of diaphragm
35 Intervertebral disc
36 Body of first lumbar vertebra
37 Spinal cord
38 Conus medullaris
39 Cauda equina
40 Filum terminale
41 Spinous process



Sagittal section through the vertebral canal, T_9–L_2. (MR-Scan.)



Sagittal section through vertebral canal, T_{12}–L_2. Notice red bone marrow (unfixed).


1
2
3
18
19
4
20
5
6
8
7
9
12
10
11
21
22
13
14
15
23
16
24
17
25

Median section of the head and trunk in the adult (female). The conus medullaris of the spinal cord is located at the level of L_1.


2
18
3
19
4
20
8
29
6
7
26
9
27
21
28
14
22
16
15
17
23
24

Median section of the head and trunk in the neonate. Note that in the neonate the conus medullaris of the spinal cord extends far more caudally than in the adult.

1	Cerebrum
2	Corpus callosum
3	Pons
4	Larynx
5	Trachea
6	Left atrium
7	**Right ventricle**
8	Esophagus
9	**Liver**
10	Stomach
11	Pancreas
12	Transverse colon
13	Umbilicus
14	Small intestine
15	Uterus
16	Urinary bladder
17	Pubic symphysis
18	Cerebellum
19	Medulla oblongata
20	**Spinal cord**
21	**Conus medullaris**
22	**Cauda equina**
23	Rectum
24	Vagina
25	Anus
26	Inferior vena cava
27	Aorta
28	Umbilical cord
29	Thymus



Dorsal aspect of the neck I. Superficial layer. Nuchal region and shoulder.

1	Sternocleidomastoid muscle	10	Occipital belly of occipitofrontalis muscle
2	**Lesser occipital nerve**	11	**Greater occipital nerve**
3	Descending fibers of trapezius muscle	12	Third occipital nerve
4	Spine of scapula	13	Splenius capitis muscle
5	**Medial cutaneous branches of dorsal rami of spinal nerves**	14	**Great auricular nerve**
6	Medial margin of scapula	15	Cutaneous nerves of cervical plexus
7	Rhomboid major muscle	16	Transverse fibers of trapezius muscle
8	Latissimus dorsi muscle	17	Ascending fibers of trapezius muscle
9	Galea aponeurotica	18	Teres major muscle



Dorsal aspect of neck II. Deeper layer. The left trapezius muscle has been divided and reflected. On the right, trapezius, rhomboid and splenius muscles have been divided. Right levator scapulae muscle has been slightly reflected.

1 Galea aponeurotica
2 Occipital belly of occipitofrontalis muscle
3 Occipital artery
4 **Greater occipital nerve** (C_2)
5 Semispinalis capitis muscle
6 Sternocleidomastoid muscle
7 Lesser occipital nerve
8 Left splenius capitis muscle
9 Third occipital nerve (C_3)
10 Spinous process of vertebra prominens (C_7)
11 Left trapezius muscle and **accessory nerve**
12 Levator scapulae muscle
13 Superficial branch of transverse cervical artery
14 Thomboid minor muscle
15 Rhomboid major muscle
16 Medial margin of scapula
17 **Medial branches of dorsal rami of spinal nerves**
18 Ligamentum nuchae
19 Splenius capitis muscle (divided)
20 Splenius cervicis muscle
21 Right **accessory nerve** and superficial branch of transverse cervical artery
22 Right levator scapulae muscle
23 Dorsal scapular nerve and deep branch of transverse cervical artery
24 Serratus posterior superior muscle
25 Right trapezius muscle (divided and reflected)
26 Right rhomboid major muscle (divided and reflected)



Dorsal aspect of neck III. Deepest layer. Nuchal region. Trapezius muscle and splenius capitis and cervicis muscles have been divided and partly removed or reflected.

1 Skin of scalp
2 Galea aponeurotica
3 Occipital belly of occipitofrontalis muscle
4 **Occipital artery**
5 **Greater occipital nerve**
6 Third occipital nerve
7 Semispinalis capitis muscle
8 Levator scapulae muscle
9 **Accessory nerve** (n. XI)
10 Superficial cervical artery
11 Trapezius muscle (reflected)
12 Longissimus cervicis muscle
13 **Medial cutaneous branches of dorsal rami of spinal nerves**
14 Medial margin of scapula
15 Splenius capitis muscle (divided)
16 Sternocleidomastoid muscle
17 **Lesser occipital nerve**
18 Great auricular nerve
19 Splenius cervicis muscle
20 Longissimus cervicis muscle
21 Spinous process of seventh cervical vertebra (vertebra prominens)
22 Rhomboid muscles (divided)
23 Iliocostalis thoracis muscle
24 Longissimus thoracis muscle



Dorsal aspect of neck IV. Deepest layer, suboccipital triangle; right semispinalis capitis muscle divited and reflected.

1 Semispinalis capitis muscle (divided)
2 External occipital protuberance
3 Obliquus capitis superior muscle
4 Rectus capitis posterior minor muscle
5 Rectus capitis posterior major muscle
6 Vertebral artery
7 Obliquus capitis inferior muscle
8 **Spinous process of axis**
9 Third cervical vertebra
10 Occipital belly of occipitofrontalis muscle
11 **Greater occipital nerve**
12 Suboccipital nerve (C_1)
13 Lesser occipital nerve
14 Third occipital nerve (C_3)
15 Mastoid process and splenius capitis muscle
16 Atlas
17 Axis
18 Spinous process of third cervical vertebra
19 Right semispinalis cervicis muscle
20 Deep cervical artery
21 Left splenius capitis muscle (divided)
22 Left sternocleidomastoid muscle
23 Great auricular nerve
24 Left **semispinalis capitis muscle**
25 Left longissimus cervicis muscle
26 Levator scapulae muscle
27 Muscular branch of vertebral artery
28 Left semispinalis cervicis muscle (divided)
29 **Medial branches of dorsal rami of spinal nerves**
30 **Occipital artery**
31 Dorsal scapular nerve



Suboccipital triangle and position of the vertebral artery. (Schematic drawing.)



Dorsal aspect of neck V. Nuchal region. Deepest layer. Dissection of suboccipital triangle on both sides.

1 Occipital belly of occipitofrontalis muscle
2 **Occipital artery**
3 Insertion of semispinalis capitis muscle (divided)
4 Lesser occipital nerve (from cervical plexus)
5 Suboccipital nerve (C_1)
6 **Greater occipital nerve** (C_2)
7 Splenius capitis muscle (reflected)
8 Splenius cervicis muscle
9 Levator scapulae muscle
10 Accessory nerve (n. XI), trapezius muscle
11 Longissimus cervicis muscle
12 Iliocostalis cervicis muscle
13 **Medial cutaneus branches of dorsal rami of spinal nerves** (C_7, C_8)
14 Longissimus thoracis muscle
15 Medial margin of scapula
16 **Rectus capitis posterior minor muscle**
17 **Obliquus capitis superior muscle**
18 **Rectus capitis posterior major muscle**
19 **Obliquus capitis inferior muscle**
20 Spinous process of axis
21 Semispinalis cervicis muscle
22 Semispinalis capitis muscle (divided and reflected)
23 Transverse cervical artery (superficial branch)
24 Serratus posterior superior muscle (divided and reflected)
25 Rhomboid minor muscle (divided and reflected)
26 Rhomboid major muscle (divided and reflected)



Neck, deepest layer. Spinal cord and medulla oblongata (dorsal aspect). Cranial cavity opened.

1	Vermis of the cerebellum
2	Medulla oblongata and posterior spinal artery
3	Vertebral artery
4	**Spinal ganglion**
5	Occipital artery
6	Cerebellum
7	**Cerebellomedullary cistern**
8	Atlas
9	Greater occipital nerve (C_2)
10	Levator scapulae muscle and intertransverse ligament
11	**Dorsal roots of spinal nerves**
12	Vertebral arch
13	**Denticulate ligament and arachnoid mater**
14	Area where pia mater has been removed
15	Dura mater
16	**Dorsal rami of spinal nerves**



Deeper layer of the dorsal neck (oblique lateral aspect). Trapezius and semispinalis capitis muscles have been divided and partly removed.

1 Great auricular nerve
2 Accessory nerve (n. XI)
3 Scalenus posterior muscle
4 Transverse cervical artery
5 Omohyoid muscle
6 Muscular branch of cervical plexus
7 Trapezius muscle
8 Occipital artery
9 Greater occipital nerve
10 Semispinalis capitis muscle
11 Longissimus capitis muscle
12 Splenius capitis muscle
13 Splenius cervicis muscle
14 Serratus posterior superior muscle
15 Deep cervical vein (variant)
16 Rhomboid minor muscle
17 Levator scapulae muscle
18 Sternocleidomastoid muscle



1 Thyroid gland
2 Internal jugular vein
3 Right common carotid artery
4 Right axillary vein
5 Right brachiocephalic vein
6 Superior lobe of right lung
7 Right atrium
8 Right coronary artery
9 Middle lobe of right lung
10 **Right ventricle**
11 Diaphragm
12 Liver (left lobe) and falciform ligament
13 Left internal jugular vein
14 **Trachea**
15 Left brachiocephalic vein
16 Superior lobe of left lung
17 Cut edge of pericardium
18 **Ascending aorta**
19 **Pulmonary trunk**
20 Inferior lobe of left lung
21 **Left ventricle**
22 Costal margin
23 Right pulmonary artery
24 Esophagus
25 Descending aorta
26 Pericardium
27 Aortic valve
28 Thymus
29 Diaphragm

Thoracic organs, heart and lungs in situ (ventral aspect). Anterior thoracic wall, parietal pleura and pericardium had been removed.



Sagittal section through thoracic cavity. The divisions of the mediastinum are indicated by colors.

Divisions of mediastinum	**Main content**
Superior mediastinum (yellow)	Trachea, brachiocephalic veins, thymus, aortic arch, esophagus, thoracic duct
Middle mediastinum (light blue)	Heart, ascending aorta, pulmonary trunk, pulmonary veins, phrenic nerves
Posterior mediastinum (red)	Esophagus with vagus nerves, descending aorta, thoracic duct, sympathetic trunks
Anterior mediastinum (pink)	Small vessels, connective and fatty tissue, and thymus in a child


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30

Positions of thoracic organs. The anterior thoracic wall has been removed. Arrow: horizontal fissure of right lung.

1 Cricothyroid muscle
2 Right internal jugular vein
3 Vagus nerve
4 Right common carotid artery
5 Right subclavian vein
6 Right brachiocephalic vein
7 Superior vena cava
8 Upper lobe of right lung
9 Right auricle
10 Middle lobe of right **lung**
11 Oblique fissure of right lung
12 Lower lobe of right lung
13 **Diaphragm**
14 Falciform ligament
15 Costal margin
16 Transverse colon
17 Thyroid gland
18 Trachea
19 Left internal jugular vein
20 Left cephalic vein
21 Left brachiocephalic vein
22 Pericardium (cut edge)
23 Upper lobe of left **lung**
24 **Right ventricle**
25 **Left ventricle**
26 Anterior interventricular sulcus
27 Lower lobe of left lung
28 Xiphoid process
29 **Liver**
30 **Stomach**
31 Pectoralis major muscle


32
31
9
10
43
45
46
47
12
48
39
40
41
42
34
23
44
36
37
38
27
49
50

Horizontal section through the thorax at the level of the 7th thoracic vertebra (from below).


51
21
52
53
54
55
56
57
29
58
30
59
60
61
62
63
64
65
36
35
37
66
13
67
68
69

Sagittal section through the left thorax, 2 cm lateral to the median plane.


52
33
70
24
29
30
61
23
65
36
35
27
71
30
72
73
58
68

Sagittal section through the left thorax, 3.5 cm lateral to the median plane.


4
32
33
25
29
64
65
48
66
35

Sagittal section through the thorax. MR-Scan.

32 Sternum
33 Pulmonary trunk
34 Left ventricle and bulb of aorta
35 Left atrium
36 Left main bronchus
37 **Esophagus**
38 Descending aorta
39 Serratus anterior muscle
40 Teres major muscle
41 Rib
42 Trapezius muscle
43 Right atrium
44 Left pulmonary vein
45 Right pulmonary vein
46 Right main bronchus
47 Azygos vein
48 Body of vertebra
49 Spinal cord
50 Scapula
51 Left common carotid artery
52 Sternoclavicular articulation with disc
53 Right pulmonary artery
54 Remnants of thymus
55 Aortic bulb
56 Right atrium
57 Entrance of inferior vena cava in right atrium
58 **Pancreas**
59 Left renal vein
60 **Duodenum**
61 Transverse colon (dilated)
62 Small intestine
63 Umbilicus
64 Left subclavian artery
65 Aortic arch
66 **Thoracic aorta**
67 Abdominal aorta
68 Intervertebral disc
69 Body of lumbar vertebra
70 Aortic valve
71 Cardia of stomach
72 Suprarenal gland
73 Splenic vein



Respiratory system. The lungs have been fixed in expiration and turned laterally. Head bisected and turned laterally.

1 Sphenoid sinus
2 Pharyngeal opening of auditory tube
3 Spinal cord
4 Dens of axis
5 **Oropharynx** (oropharyngeal isthmus)
6 Epiglottis
7 Entrance of larynx
8 Esophagus
9 Upper lobe of right lung
10 Azygos vein
11 Branches of pulmonary artery
12 **Right main bronchus**
13 **Bifurcation of trachea**
14 Tributaries of right pulmonary veins
15 Middle lobe of right lung
16 Lower lobe of right lung
17 Frontal sinus
18 Superior nasal concha
19 Middle nasal concha
20 Inferior nasal concha
21 Hard palate
22 Soft palate with uvula
23 Tongue
24 Vocal fold
25 Larynx
26 Trachea
27 Upper lobe of left lung
28 Left pulmonary artery
29 **Left main bronchus**
30 Left pulmonary veins
31 Lower lobe of left lung



Bronchial tree (ventral aspect). The lung tissue has been removed. The bronchopulmonary segments are numbered 1–10.

▷

To page 231:

1 Nasal cavity
2 Pharynx
3 Larynx (thyroid cartilage)
4 Trachea
5 Upper lobe of right lung
6 Bifurcation of trachea
7 Right main bronchus
8 Horizontal fissure of right lung
9 Middle lobe of right lung
10 Oblique fissures of lungs
11 Lower lobe of right lung
12 Clavicle
13 Upper lobe of left lung
14 Left main bronchus
15 Bronchi supplying bronchopulmonary segments
16 Lower lobe of left lung
17 Costal margin
18 Hyoid bone
19 Right superior lobe bronchus
20 Right middle lobe bronchus
21 Right inferior lobe bronchus
22 Left superior lobe bronchus
23 Left inferior lobe bronchus
24 Segmental bronchi
25 Branches of pulmonary arteries
26 Branches of pulmonary veins


18
3
4
7
19
6
14
22
20
23
21
24
24

Larynx, trachea and bronchial tree (anterior aspect).


1
2
3
4
12
5
13
6
14
7
15
8
9
10
10
16
11
17
17

Organization and positions of respiratory organs. (Schematic drawing.)


5
19
25
26
20
21
10
11
1
2
3
4
5
6
7
9
10
13
26
25
22
23
25
26
10
16
1-2
3
4
5
6
8
9
10

Mediastinal dissection of the bronchial tree, pulmonary veins, and pulmonary arteries of right lung (left) and left lung (right) (medial aspect). Segmental bronchi are numbered 1–10.


1
1
2
7
3
8
4
5
5
9
6
10
1
2
5
3
4
6
11
1
2
3
4
5
6
7
8
9
10
11

Surface projections of lungs and pleura on the thoracic wall. Left: anterior aspect; right: right-lateral aspect. Red = margins of the lung; blue = margins of pleura. The numbers indicate ribs.


12
7
5
6
9
13
7
9
14
2
3
4
5
6
7
8
9
10
11
1
2
3
4
5
6
7
8
9
10
11

Surface projections of lungs and pleura on thoracic wall. Left: posterior aspect; right: left-lateral aspect. Red = margins of lung; blue = margins of pleura. The number indicate ribs.

1 Apex of lung
2 Upper lobe of right lung
3 Horizontal fissure of right lung
4 Middle lobe of right lung
5 Oblique fissures of lungs
6 Lower lobe of right lung
7 Upper lobe of left lung
8 Cardiac notch of left lung
9 Lower lobe of left lung
10 Infrasternal angle
11 Costal margin
12 Spine of scapula
13 1st lumbar vertebra
14 Space between border of lung and pleura (costodiaphragmatic recess)



Right lung (lateral aspect).



Left lung (lateral aspect).



Right lung (medial aspect).



Left lung (medial aspect).

1 Apex of lung
2 Upper lobe of right lung
3 Horizontal fissure of right lung
4 Oblique fissure of right lung
5 Middle lobe of right lung
6 Lower lobe of right lung
7 Inferior border
8 Upper lobe of left lung
9 Impressions of ribs
10 Oblique fissure of left lung
11 Lower lobe of left lung
12 Groove of subclavian artery
13 Groove of azygos arch
14 Branches of right pulmonary artery
15 Bronchi
16 Right pulmonary veins
17 Pulmonary ligament
18 Diaphragmatic surface
19 Groove of aortic arch
20 Left pulmonary artery
21 Branches of left pulmonary veins
22 Left secondary bronchi
23 Groove of thoracic aorta
24 Groove of esophagus
25 Cardiac impression
26 Lingula



Right lung (medial aspect).


2
1
3
6
4
5
8
10
9

Left lung (medial aspect).



Right lung (lateral aspect).



Left lung (lateral aspect).

The bronchopulmonary segments of the lungs are differentiated by the various colors. Notice that there is no segment in the left lung that corresponds to the 7th segment of the right lung. Compare with the schematic drawing on the facing page.



Distribution of bronchopulmonary segments of the lungs and their relation to the bronchial tree (after J. F. Huber). The bronchopulmonary segments are morphologically and functionally separate independent respiratory units of the lung tissue. Each segment is surrounded by connective tissue which is continuous with the visceral pleura. The segmental bronchi in a segment are central, closely accompanied by branches of the pulmonary arteries whereas the tributaries of the pulmonary veins run **between** the segments. Thus, the veins serve two adjacent segments which drain for the most part into more than one vein. A bronchopulmonary segment is therefore not a complete vascular unit, but segmentation is the result of a specific architecture of the lung vasculature.

	Right lung	
1	Apical segment	Upper lobe bronchus
2	Posterior segment	
3	Anterior segment	
4	Lateral segment	Middle lobe bronchus
5	Medial segment	
6	Superior (apical) segment	Lower lobe bronchus
7	Medial basal segment	
8	Anterior basal segment	
9	Lateral basal segment	
10	Posterior basal segment	

	Left lung		
1+2	Apico-posterior segment	Superior division	Upper lobe bronchus
3	Anterior segment		
4	Superior lingular segment	Inferior division	
5	Inferior lingular segment		
6	Superior (apical) segment	Lower lobe bronchus	
7	Absent		
8	Anteromedial basal segment		
9	Lateral basal segment		
10	Posterior basal segment		



Heart of 30-year-old woman (anterior aspect).



Heart of 30-year-old woman (oblique posterior view).

1 Left subclavian artery
2 Left common carotid artery
3 Brachiocephalic trunk
4 Superior vena cava
5 Ascending aorta
6 Bulb of the aorta
7 Right auricle
8 **Right atrium**
9 Coronary sulcus
10 **Right ventricle**
11 Aortic arch
12 Ligamentum arteriosum
13 Left pulmonary veins
14 Left auricle
15 **Pulmonary trunk**
16 Sinus of pulmonary trunk
17 Anterior interventricular sulcus
18 **Left ventricle**
19 Apex of the heart
20 **Left atrium**
21 Epicardial fat overlying coronary sinus
22 Posterior interventricular sulcus
23 Right pulmonary artery
24 Right pulmonary veins
25 Inferior vena cava



Position of heart and its vessels within the thorax.
(Schematic drawing.)

1 Right brachiocephalic vein
2 Superior vena cava
3 Ascending aorta
4 Right atrium
5 Right ventricle
6 Inferior vena cava
7 Left internal jugular vein
8 Left common carotid artery
9 Left axillary artery and vein
10 Left brachiocephalic vein
11 Pulmonary trunk
12 Left auricle
13 Left ventricle
14 Descending aorta



Heart and related vessels in situ (anterior aspect). Anterior thoracic wall, pericardium and epicardium have been removed; trachea divided.

1 Larynx (thyroid cartilage)
2 Sternocleidomastoid muscle (divided)
3 Trachea (divided) and right internal jugular vein
4 Vagus nerve
5 Right common carotid artery and cephalic vein
6 Esophagus
7 Right axillary vein
8 Right and left brachiocephalic veins
9 **Superior vena cava**
10 Right auricle
11 Right **coronary artery**
12 **Right atrium**
13 Diaphragm
14 Pericardium (cut edges)
15 Costal margin
16 Omohyoid muscle
17 Left **common carotid artery**
18 Left internal jugular vein
19 Clavicle (divided)
20 Left recurrent laryngeal nerve
21 **Subclavian vein**
22 Pericardial reflection
23 **Pulmonary trunk**
24 **Ascending aorta**
25 Anterior interventricular sulcus and anterior interventricular branch of left coronary artery
26 **Right ventricle**
27 **Left ventricle**
28 Aortic valve
29 Tricuspid or right atrioventricular valve
30 Inferior vena cava
31 Pulmonary veins
32 Pulmonary valve
33 Left atrioventricular (bicuspid or mitral) valve



Heart in situ. Position of valves (anterior aspect). (Schematic drawing.)



Anterior aspect of the heart. The anterior walls of the ventricles and of the aorta and pulmonary trunk have been fenestrated to show the aortic valve.

1 Brachiocephalic trunk
2 Superior vena cava
3 Sulcus terminalis
4 Right auricle
5 Right atrium
6 **Aortic valve**
7 Conus arteriosus (interventricular septum)
8 **Right atrioventricular (tricuspid) valve**
9 **Anterior papillary muscle**
10 Myocardium of right ventricle
11 Left common carotid artery
12 Left subclavian artery
13 **Aortic arch**
14 Ligamentum arteriosum (remnant of ductus arteriosus)
15 Thoracic aorta (descending aorta)
16 **Ascending aorta**
17 Left pulmonary vein
18 **Pulmonary trunk**
19 Left auricle
20 Pulmonic valve
21 **Anterior papillary muscle** with chordae tendineae
22 Myocardium of left ventricle
23 Posterior papillary muscle
24 Interventricular septum
25 Right and left brachiocephalic veins
26 **Chordae tendineae**
27 Papillary muscles of right ventricle
28 Left atrium
29 Infundibulum
30 Anterior papillary muscle of left ventricle
31 Left atrioventricular (bicuspid or mitral) valve and chordae tendineae
32 Apex of heart



Circulation within the heart. (Schematic drawing.) The arrows indicate the direction of the blood flow through the heart. Blue = right heart; red = left heart.



Heart in situ. Myocardium and coronary arteries (anterior aspect).

1 Internal jugular vein
2 Common carotid artery
3 Brachiocephalic trunk
4 **Ascending aorta**
5 Right lung
6 Right auricle
7 **Right coronary artery**
8 **Myocardium of right ventricle**
9 Diaphragm
10 Costal margin
11 Thyroid gland and internal jugular vein
12 Trachea and left common carotid artery
13 Left brachiocephalic vein
14 Left lung
15 **Pericardium** (cut edge)
16 Pulmonary trunk
17 Anterior interventricular artery
18 **Myocardium of left ventricle**
19 **Muscular vortex** (right ventricle)
20 Posterior interventricular sulcus
21 Anterior interventricular sulcus
22 **Muscular vortex** (left ventricle)
23 Aortic arch
24 Left atrium
25 Coronary sinus
26 Superior vena cava
27 Right pulmonary vein
28 Right atrium
29 Inferior vena cava
30 Coronary sulcus
31 Myocardium of left ventricle
32 Left pulmonary artery
33 Left pulmonary vein
34 Apex of heart



Heart (posterior aspect). The myocardium of the left ventricle has been fenestrated to show the muscle fiber bundles of the deeper layer with their more circular course.



Vortex of cardiac muscle fibers (from below).



Right heart (anterior aspect). Anterior wall of right atrium and ventricle removed.

1 Superior vena cava
2 Crista terminalis
3 Fossa ovalis
4 Opening of inferior vena cava
5 Opening of coronary sinus
6 Right auricle
7 Right coronary artery and coronary sulcus
8 **Anterior cusp** of **tricuspid valve**
9 Chordae tendineae
10 **Anterior papillary muscle**
11 Myocardium
12 Pulmonary trunk
13 Ascending aorta
14 **Pulmonic valve**
15 Conus arteriosus (interventricular septum)
16 Septal papillary muscles
17 Septomarginal or moderator band
18 Apex of heart
19 Left auricle
20 **Aortic valve**
21 **Left ventricle**
22 Pulmonary veins
23 Position of fossa ovalis
24 **Left atrium**
25 **Left atrioventricular** (bicuspid or **mitral**) **valve**
26 Coronary sinus
27 Left coronary artery
28 Posterior papillary muscle
29 Left subclavian artery
30 Descending aorta
31 Left pulmonary artery



Left heart. Left atrium and ventricle opened. Aortic and mitral valve cut open.



Left heart. Aortic valve cut open. Left atrium and ventricle opened. The atrial wall was cut near the anulus fibrosus of the mitral valve.



Valves of heart (superior aspect). Left and right atrium removed. Dissection of coronary arteries. Above: anterior wall of the heart.

1 **Pulmonic valve**
2 Sinus of pulmonary trunk
3 **Left coronary artery**
4 Great cardiac vein
5 **Left atrioventricular (mitral) valve**
6 **Coronary sinus**
7 **Aortic valve**
8 **Right coronary artery**
9 **Right atrioventricular (tricuspid) valve**
10 Bulb of aorta
11 Anterior semilunar cusp of pulmonic valve
12 Left semilunar cusp of pulmonic valve
13 Right semilunar cusp of pulmonic valve
14 Left semilunar cusp of aortic valve
15 Right semilunar cusp of aortic valve
16 Posterior semilunar cusp of aortic valve
17 Right atrium
18 Anterior cusp of tricuspid valve
19 **Chordae tendineae**
20 Trabeculae carneae
21 Interventricular septum
22 Septal cusp of tricuspid valve
23 **Anterior papillary muscle**
24 Myocardium of right ventricle



Pulmonic and aortic valves (from above). Anterior wall of the heart at the top. Both valves are closed.



Right atrioventricular (tricuspid) valve (anterior aspect after removal of the anterior wall of the right ventricle).



Heart, fixed in **diastole** (anterior aspect). The ventricles are relaxed, atria contracted.

1 Ascending aorta
2 Superior vena cava
3 Right auricle
4 **Right atrium**
5 Coronary sulcus
6 **Right ventricle**
7 Pulmonary trunk
8 Left auricle
9 Anterior interventricular sulcus
10 **Left ventricle**
11 Right pulmonary artery
12 Sulcus terminalis with sinuatrial node
13 Line indicating plane of position of valves
14 Myocardium of right atrium
15 Inferior vena cava
16 Valve of pulmonary trunk
17 Tricuspid valve
18 Myocardium of right ventricle



Heart, fixed in **systole** (anterolateral aspect). The ventricles are contracted, atria dilated.



Morphological changes during heart movements. Note the changes in positon of the valves (arrows). Contracted portions of heart are indicated in red.

A. **Diastole,** muscles of the ventricles relaxed; atrioventricular valves open, semilunar valves closed.

B. **Systole,** muscles of ventricles contracted; atrioventricular valves closed, semilunar valves open.



Right ventricle, dissection of **atrioventricular node, atrioventricular bundle (bundle of His)** and right limb or bundle branch (probes).



Left ventricle, dissection of the left limb or bundle branch of conducting system (probes).

1 Superior vena cava
2 Sulcus terminalis
3 Bulb of aorta
4 Sinuatrial node (arrows)
5 Muscle fiber bundles of right atrium
6 Coronary sulcus (with right coronary artery)
7 Aortic sinus
8 Entrance to left coronary artery
9 Aortic valve
10 Branches of **left bundle branch**
11 Purkinje fibers
12 Left auricle
13 Interventricular septum
14 Papillary muscles
15 Ascending aorta
16 Right atrium
17 Opening of coronary sinus
18 **Atrioventricular node**
19 Septal cusp of tricuspid valve
20 Pulmonary trunk
21 **Atrioventricular bundle** (bundle of His)
22 Bifurcation of atrioventricular bundle
23 **Right bundle branch**
24 Inferior vena cava
25 Left atrium
26 Left bundle branch
27 Papillary muscles with Purkinje fibers



Right atrium, anterior wall, showing the location of the **sinuatrial node** (arrows).



Conducting system of the heart.
(Schematic drawing.)



Coronary arteries (anterior aspect). The epicardium and subepicardial fatty tissue have been removed. The arteries have been injected with red resin from the aorta.



Right coronary artery and veins of the heart (dorsal aspect). The epicardium and subepicardial fatty tissue have been removed.

1 Ascending aorta
2 Aortic bulb and (in the above specimen) sinuatrial branch of right coronary artery
3 Right auricle
4 **Right coronary artery**
5 Right atrium
6 Coronary sulcus
7 Right ventricle
8 Left auricle
9 Pulmonary trunk
10 Circumflex branch of left coronary artery
11 **Left coronary artery**
12 Diagonal branch of left artery
13 Great cardiac vein
14 Anterior interventricular artery
15 Anterior interventricular sulcus
16 Left ventricle
17 Apex of heart
18 Right pulmonary vein
19 Left atrium
20 Left pulmonary veins
21 Oblique vein of left atrium (Marshall's vein)
22 **Coronary sinus**
23 **Great cardiac vein**
24 Coronary sulcus (posterior portion)
25 Posterior vein of left ventricle
26 **Middle cardiac vein**
27 Left pulmonary artery
28 Inferior vena cava
29 Right atrium
30 Posterior interventricular branch of right coronary artery
31 Posterior interventricular sulcus
32 Superior vena cava
33 Right marginal branch
34 Branch of sinuatrial node
35 Minimal cardiac veins
36 **Small cardiac vein**



Vessels of the heart. Coronary arteries (red) and veins (blue) of the heart (anterior aspect).

1. Platysma muscle
2. Clavicle
3. Deltoid muscle
4. Pectoralis major muscle
5. Deltopectoral groove and cephalic vein
6. Latissimus dorsi muscle
7. Medial mamarian branches of intercostal nerves
8. Breast tissue
9. Areola
10. Nipple (papilla)
11. Costal margin
12. Pectoral fascia
13. Mammary gland
14. Serratus anterior muscle
15. Lactiferous sinus
16. Lactiferous ducts



Dissection of mammary gland (anterior aspect).



Mammary gland (sagittal section; pregnant female).



Galactogram of mammary gland (adult female). Notice multiple duct cysts.



Thoracic wall and organs (ventral aspect). The left clavicle and ribs have been partially removed, and the right intercostal spaces have been opened to show the internal thoracic vein and artery.

1 Right internal jugular vein
2 Omohyoid muscle
3 Sternohyoid muscle and external jugular vein
4 Clavicle
5 Thoracoacromial artery
6 Right **subclavian vein**
7 Pectoralis major muscle
8 External intercostal muscle
9 Pectoralis minor muscle
10 Body of sternum
11 Right internal thoracic artery and vein
12 Fascicles of transversus thoracis muscle
13 **Internal intercostal muscles**
14 Serratus anterior muscle
15 Costal margin
16 External abdominal oblique muscle
17 Anterior sheath of rectus abdominis muscle
18 Sternocleidomastoid muscle
19 Left internal jugular vein
20 Transverse cervical artery
21 Brachial plexus
22 Vagus nerve
23 Left axillary vein
24 Left **internal thoracic artery and vein**
25 Ribs and thoracic wall (cut)
26 Costal pleura
27 Xiphoid process
28 **Superior epigastric artery**
29 Diaphragm
30 Rectus abdominis muscle



Thoracic organs, anterior mediastinum and pleura. Ribs, clavicle and sternum have been partly removed. Red = arteries; blue = veins; green = lymph vessels and nodes.

1 Sternothyroid muscle and its nerve (a branch of the ansa cervicalis)
2 Right **internal jugular vein**
3 Right common carotid artery
4 Cephalic vein
5 Right **subclavian vein**
6 **Right brachiocephalic vein**
7 Pectoralis major muscle (divided)
8 Pectoralis minor muscle (divided)
9 Parasternal lymph nodes
10 Internal thoracic artery and vein
11 Anterior margin of costal pleura
12 **Pericardium**
13 5th and 6th ribs (divided) and serratus anterior muscle
14 **Costodiaphragmatic recess**
15 External abdominal oblique muscle
16 Rectus abdominis muscle
17 Larynx (thyroid cartilage)
18 Thyroid gland
19 Trachea
20 Left vagus nerve
21 Left brachiocephalic vein
22 Left **internal thoracic artery and vein**
23 Thymus
24 **Costal pleura**
25 Costal margin
26 **Superior epigastric artery**
27 Margin of costal pleura
28 **Diaphragm**
29 **Linea alba**
30 Cut edge of anterior sheath of rectus abdominis muscle



The **thymus** above the heart, showing its position and size.



Thoracic organs (ventral aspect). The internal thoracic vessels have been removed, and the anterior margins of the pleura and lungs have been slightly reflected to display the **anterior** and **middle mediastinum,** including the **heart** and **great vessels.**

1 Larynx (thyroid cartilage)
2 Thyroid gland
3 **Trachea**
4 Internal jugular vein
5 Brachial plexus
6 Right brachiocephalic vein and common carotid artery
7 Right phrenic nerve
8 **Ascending aorta**
9 Pectoralis minor muscle (divided)
10 Pulmonary trunk (covered by pericardium)
11 **Costal pleura**
12 Pericardium and **heart**
13 Serratus anterior muscle
14 Xiphoid process
15 Costal margin
16 External abdominal oblique muslce
17 Sternothyroid muscle (divided and reflected)
18 Vagus nerve
19 Left common carotid artery
20 Left sympathetic trunk
21 Left recurrent laryngeal nerve
22 Left internal thoracic artery and vein (divided)
23 Margin of costal pleura
24 Intercostal nerves and vessels
25 Superior epigastric artery
26 Rectus abdominis muscle
27 **Diaphragm**
28 Ansa cervicalis
29 Phrenic nerve and scalenus anterior muscle
30 External jugular vein (divided)
31 Right subclavian vein
32 Right brachiocephalic vein
33 Internal thoracic artery (divided)
34 Internal thoracic vein (divided)
35 Right lung
36 Cricothyroid muscle
37 Omohyoid muscle
38 **Thymus**
39 Left lung



Thoracic organs (ventral aspect). The pleura has been opened and the lungs exposed. Remnants of the thymus and pericardium are seen.

1	Right internal jugular vein	11	Middle lobe of right lung	20	Left common carotid artery and vagus nerve
2	Phrenic nerve and scalenus anterior muscle	12	Oblique fissure of right **lung**	21	**Left brachiocephalic vein**
3	Clavicle (divided)	13	Lower lobe of right lung	22	Internal thoracic artery and vein (divided)
4	Right subclavian artery and vein	14	Xiphoid process	23	**Ascending aorta** and aortic arch
5	Internal thoracic artery	15	**Diaphragm**	24	Upper lobe of left **lung**
6	**Right brachiocephalic vein**	16	**Thyroid gland**	25	**Pericardium**
7	Brachiocephalic trunk	17	Left internal jugular vein	26	Oblique fissure of left lung
8	Thymus (atrophic)	18	Brachial plexus	27	Lower lobe of left lung
9	Upper lobe of right **lung**	19	Left cephalic vein	28	Costal margin
10	Horizontal fissure of right lung (incomplete)				



Thoracic organs (ventral aspect). The thoracic wall, costal pleura, pericardium and diaphragm have been partly removed.

1 Internal jugular vein
2 External jugular vein (displaced medially)
3 Brachial plexus
4 Trachea
5 Right common carotid artery
6 Clavicle (divided)
7 Right brachiocephalic vein
8 Upper lobe of right lung
9 **Thymus** (atrophic)
10 Horizontal fissure of right lung
11 Middle lobe of right lung
12 Pericardium (cut edges)
13 Oblique fissure of lung
14 Lower lobe of right lung
15 **Diaphragm**
16 Falciform ligament
17 **Liver**
18 Location of larynx
19 Left internal jugular vein
20 Thyroid gland
21 Omohyoid muscle (divided)
22 Vagus nerve
23 Left subclavian vein
24 1st rib (divided)
25 Internal thoracic artery and vein
26 Pectoralis major and pectoralis minor muscles (cut edges)
27 **Upper lobe of left lung**
28 **Right ventricle**
29 Cardiac notch of left lung
30 Interventricular sulcus of heart
31 **Left ventricle**
32 Lingula
33 Lower lobe of left lung



Thoracic organs, position of the heart, middle mediastinum (ventral aspect). The anterior wall of the thorax, the costal pleura and the pericardium have been removed and the lungs slightly reflected.

1 Thyroid gland
2 Phrenic nerve and scalenus anterior muscle
3 Vagus nerve and internal jugular vein
4 Clavicle (divided)
5 Brachial plexus and subclavian artery
6 Subclavian vein
7 Internal thoracic artery
8 Brachiocephalic trunk and right brachiocephalic vein
9 **Superior vena cava** and thymic vein
10 **Right phrenic nerve**
11 Transverse pericardial sinus (probe)
12 Right auricle
13 Middle lobe of right lung
14 **Right ventricle**
15 Cut edge of pericardium
16 Diaphragm
17 Internal jugular vein
18 Trachea
19 Left recurrent laryngeal nerve
20 Left common carotid artery and vagus nerve
21 Left brachiocephalic vein and inferior thyroid vein
22 Left internal thoracic artery and vein (divided)
23 Upper margin of pericardial sac
24 **Ascending aorta**
25 Pulmonary trunk
26 **Left phrenic nerve** and left pericardiacophrenic artery and vein
27 Upper lobe of left lung
28 Left ventricle



Thoracic organs, position of heart, dissection of coronary vessels in situ (ventral aspect). The anterior wall of thorax, costal pleura and pericardium have been removed.

1 Intermediate supraclavicular nerve
2 Internal jugular vein
3 Right phrenic nerve
4 Right vagus nerve
5 Right common carotid artery
6 Right subclavian vein
7 Right brachiocephalic vein
8 Right internal thoracic artery
9 **Superior vena cava**
10 Ascending aorta
11 Right lung
12 Right atrium
13 **Right coronary artery** and small cardiac vein
14 **Right ventricle**
15 Cut edge of pericardium
17 Costal margin
18 Larynx (cricothyroid muscle and thyroid cartilage)
19 Thyroid gland
20 Left common carotid artery and left vagus nerve
21 Left recurrent laryngeal nerve
22 Trachea
23 Left internal thoracic artery and vein (divided)
24 Thymic veins
25 Margin of pericardial sac
26 Pulmonary trunk
27 Left lung
28 Left ventricle
29 Anterior interventricular artery and vein
30 Lingula
31 Liver



Thoracic organs, heart with valves in situ (ventral aspect). Anterior wall of thorax, pleura and anterior portion of pericardium have been removed. The right atrium and ventricle have been opened to show the right atrioventricular and pulmonary valves.

1 Omohyoid muscle
2 Pyramidal lobe of thyroid gland
3 Internal jugular vein
4 Thyroid gland
5 Right subclavian vein
6 Brachiocephalic trunk
7 **Right brachiocephalic vein**
8 Right internal thoracic artery
9 Right phrenic nerve
10 **Superior vena cava**
11 Pulmonary vein
12 Branches of pulmonary artery
13 Right auricle
14 **Right atrium**
15 **Right atrioventricular (tricuspid) valve**
16 Right lung
17 Posterior papillary muscle
18 Diaphragm
19 Left **vagus nerve**
20 Left **phrenic nerve**
21 Scalenus anterior muscle
22 Brachial plexus
23 Thyrocervical trunk
24 Left common carotid artery
25 Left subclavian artery
26 Left internal thoracic artery
27 Apex of left lung
28 Left recurrent laryngeal nerve
29 Cut edge of **pericardium**
30 Pulmonary trunk (fenestrated)
31 Pulmonic valve
32 Supraventricular crest
33 **Anterior papillary muscle**
34 **Left ventricle**



Thoracic organs, pericardium and **mediastinum** (ventral aspect). Anterior wall of thorax and heart have been removed and the lungs slightly reflected. Note probe within transverse pericardial sinus.

1 Right internal jugular vein and right vagus nerve
2 Right phrenic nerve and scalenus anterior muscle
3 Right common carotid artery
4 Brachial plexus
5 Right subclavian artery and vein
6 Right brachiocephalic vein
7 Right internal thoracic artery (divided)
8 **Brachiocephalic trunk**
9 Upper lobe of right lung
10 **Superior vena cava**
11 Transverse pericardial sinus (probe)
12 Right **phrenic nerve** and right pericardiacophrenic artery and vein
13 Right pulmonary veins
14 Oblique sinus of pericardium
15 **Inferior vena cava**
16 Diaphragmatic part of pericardium
17 Diaphragm
18 Costal margin
19 Thyroid gland
20 **Trachea**
21 Left recurrent laryngeal nerve and inferior thyroid vein
22 Left common carotid artery and left vagus nerve
23 Left internal thoracic artery and vein (divided)
24 **Vagus nerve** at aortic arch
25 Cut edge of pericardium
26 **Ascending aorta**
27 Pulmonary trunk (divided)
28 Left pulmonary veins
29 Left phrenic nerve and left pericardiacophrenic artery and vein
30 Contour of esophagus beneath pericardium
31 Contour of aorta beneath pericardium
32 **Pericardium** (cut edge)


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18

Pericardial sac (ventral aspect). The heart has been removed, and the posterior wall of the pericardium has been opened to show the adjacent esophagus and aorta.

1 Internal thoracic vein
2 Superior vena cava
3 Oblique sinus of pericardium
4 Right pulmonary veins
5 Esophagus
6 Branches of right vagus nerve
7 Mesocardium
8 Inferior vena cava
9 Middle lobe of right lung
10 Diaphragm
11 Upper lobe of left lung
12 Ascending aorta
13 **Pulmonary trunk**
14 Transverse pericardial sinus
15 Left pulmonary veins
16 Descending aorta and left vagus nerve
17 Left lung (adjacent to pericardium)
18 **Pericardium**
19 Left subclavian artery
20 Vagus nerve
21 Left recurrent laryngeal nerve
22 Descending aorta
23 Pulmonary artery
24 **Left atrium**
25 **Left ventricle**
26 Coronary sinus
27 Left common carotid artery
28 Brachiocephalic trunk
29 Azygos arch
30 **Right atrium**
31 **Right ventricle**
32 Aortic arch


19
20
21
22
23
14
3
15
24
25
26
27
28
2
29
20
23
18
4
30
7
8
31

Heart with epicardium (posterior aspect). Arrows: oblique sinus.


27
28
32
12
2
18
30
31
19
20
21
23
18
13
15
25

Heart with epicardium (anterior aspect). Arrow: pericardial reflection.



Mediastinal organs after removal of heart and pericardium (ventral aspect). Both lungs have been slightly reflected.

1	Supraclavicular nerves
2	Internal jugular vein
3	Omohyoid muscle
4	**Right vagus nerve**
5	Right common carotid artery
6	Right subclavian artery
7	Brachiocephalic trunk
8	Right brachiocephalic vein
9	Superior cervical cardiac branch of vagus nerve
10	Inferior cervical cardiac branches of vagus nerve
11	Azygos arch (divided)
12	Bifurcation of trachea
13	Right **pulmonary artery**
14	Right **pumonary veins**
15	Right lung
16	**Esophagus** and branches of right vagus nerve
17	Inferior vena cava
18	Pericardium
19	Larynx (thyroid cartilage, cricothyroid muscle)
20	Thyroid gland
21	Internal jugular vein
22	Esophagus and left recurrent laryngeal nerve
23	**Trachea**
24	**Left vagus nerve**
25	Left common carotid artery
26	Aortic arch
27	Left recurrent laryngeal nerve branching off from vagus nerve
28	Left pulmonary veins
29	**Thoracic aorta** and left vagus nerve
30	Left lung
31	Left phrenic nerve (divided)


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
1
3
4
5
4
9
8
1
3
2
3
4
5
8
9
8
10

Bronchial tree in situ (ventral aspect). Heart and pericardium have been removed; the bronchi of the bronchopulmonary segments are dissected. 1–10 = numbers of segments.

1 Internal jugular vein
2 Right vagus nerve
3 **Thyroid gland**
4 Right recurrent laryngeal nerve
5 Brachiocephalic trunk
6 Trachea
7 **Bifurcation of trachea**
8 **Right phrenic nerve**
9 Inferior vena cava
10 Diaphragm
11 Left subclavian artery
12 Left common carotid artery
13 Left **vagus nerve**
14 Aortic arch
15 **Esophagus**
16 Esophageal plexus
17 Thoracic aorta
18 **Left phrenic nerve**
19 Pericardium at the central tendon of diaphragm
20 Right pulmonary artery
21 Left pulmonary artery
22 Tracheal lymph nodes
23 Superior tracheobronchial lymph nodes
24 Bronchopulmonary lymph nodes


15
12
6
11
14
21
24
17
15
22
5
23
20
1
2
3
4
5
6
7
8
9
10
2
1
3
4
5
8
6
8
9
10

Relation of aorta, pulmonary trunk and esophagus to trachea and bronchial tree. (Schematic drawing.)
1–10 = number of segments (ef. p. 230 and 235).



Organs of posterior mediastinum (ventral aspect). The heart with the pericardium has been removed, and the lungs and aortic arch have been slightly reflected to show the vagus nerves and their branches.

1 Supraclavicular nerves
2 Right internal jugular vein with ansa cervicalis
3 Omohyoid muscle
4 **Right vagus nerve**
5 Clavicle
6 Right subclavian artery and recurrent laryngeal nerve
7 Right subclavian vein
8 Superior cervical cardiac branch of vagus nerve
9 Inferior cervical cardiac branch of vagus nerve
10 Azygos arch (divided)
11 **Right lung**
12 **Right pulmonary artery**
13 **Right pulmonary veins**
14 **Esophagus**
15 Esophageal plexus
16 Right phrenic nerve (divided)
17 Inferior vena cava
18 Pericardium covering the diaphragm
19 **Larynx (thyroid cartilage and cricothyroid muscle)**
20 Thyroid gland
21 Left internal jugular vein
22 Esophagus and left recurrent laryngeal nerve
23 Trachea
24 **Left vagus nerve**
25 Left common carotid artery
26 Aortic arch
27 Left recurrent laryngeal nerve
28 **Bifurcation of trachea**
29 **Left pulmonary artery**
30 Left primary bronchus
31 Descending aorta
32 Left pulmonary veins
33 Branch of left vagus nerve
34 **Left lung**
35 Left phrenic nerve (divided)



Mediastinal organs (ventral aspect). Heart and distal part of esophagus have been removed to display the vessels and nerves of the posterior mediastinum.

1 Thyroid gland
2 Right internal jugular vein
3 Right vagus nerve
4 Point, where right recurrent laryngeal nerve is branching off the vagus nerve
5 Right brachiocephalic vein
6 Trachea
7 Left brachiocephalic vein (reflected)
8 Esophagus
9 Right bronchial artery
10 Posterior intercostal artery
11 **Azygos vein**
12 **Thoracic duct**
13 Posterior intercostal artery and vein (in front of the vertebral column)
14 Right phrenic nerve
15 Inferior vena cava
16 Diaphragm
17 **Left vagus nerve**
18 Thyrocervical trunk
19 Left subclavian artery
20 Left common carotid artery
21 Brachiocephalic trunk
22 Left vagus nerve
23 **Aortic arch**
24 Left recurrent laryngeal nerve
25 Left bronchial artery
26 Lymph node
27 Thoracic aorta
28 Esophageal plexus
29 Left phrenic nerve



Diaphragm and organs of mediastinum (anterior aspect). Heart and lungs have been removed; the costal margin remains in place. Note the different courses of left and right vagus.



Organs of posterior mediastinum (ventral aspect). (Schematic drawing.) Three regions in which the esophagus is narrowed are shown:

A at the level of the cricoid cartilage;

B at the level of the aortic arch;

C at the level of the diaphragm.

1 Right subclavian artery
2 Right recurrent laryngeal nerve
3 Right brachiocephalic vein
4 Superior cervical cardiac nerve
5 Inferior cervical cardiac nerves and pulmonary branches
6 **Bifurcation of trachea**
7 **Esophagus** (thoracic part)
8 Bronchi of lateral and medial segments of middle lobe
9 Esophageal plexus and branches of right vagus nerve
10 Inferior vena cava and right phrenic nerve (cut)
11 Sternal part of diaphragm
12 Costal part of **diaphragm**
13 Falciform ligament of liver
14 Liver (quadrate lobe)
15 Left common carotid artery
16 Left recurrent laryngeal nerve
17 Esophageal branches of left vagus nerve and esophagus
18 **Trachea**
19 Aortic arch
20 Left vagus nerve
21 Left recurrent laryngeal nerve with inferior cardiac nerve
22 Left primary bronchus
23 Superior and inferior lingular bronchi
24 Esophageal plexus of left vagus nerve
25 **Descending aorta**
26 Central tendon of diaphragm covered with pericardium
27 Left phrenic nerve (divided)
28 Costal margin
29 **Liver,** left lobe
30 Pharynx
31 Secondary bronchi
32 Esophagus (abdominal part)
33 Diaphragm
34 Abdominal aorta



Organs of posterior mediastinum (anterior aspect).



Inferior segment of posterior mediastinum (anterior aspect).



Veins of the posterior wall of thoracic and abdominal cavity. (Schematic drawing.)

1 Right vagus nerve
2 Thyroid gland and trachea
3 Intercostal nerve
4 Aortic arch
5 **Azygos vein**
6 Posterior intercostal artery
7 **Greater splanchnic nerve**
8 Diaphragm
9 Liver
10 Proper hepatic artery and hepatic plexus
11 Left recurrent laryngeal nerve
12 Inferior cervical cardiac nerves
13 Left vagus nerve and left recurrent laryngeal nerve
14 Left primary bronchus
15 Thoracic aorta and left vagus nerve
16 Esophagus and esophageal plexus
17 **Thoracic duct**
18 Spleen
19 Anterior gastric plexus and stomach (divided)
20 Splenic artery and splenic plexus
21 **Celiac trunk** and **celiac plexus**
22 Pancreas
23 Ramus communicans
24 **Sympathetic trunk** and **sympathetic ganglion**
25 **Posterior intercostal vein** and **artery** and **intercostal nerve**
26 Right brachiocephalic vein
27 Superior vena cava
28 Ascending lumbar vein
29 Lumbar veins
30 Right external iliac vein
31 Trachea
32 Accessory hemiazygos vein
33 Posterior intercostal veins
34 Hemiazygos vein
35 Inferior vena cava
36 Median sacral vein
37 Internal iliac vein



Mediastinal organs (right lateral aspect). Right lung and pleura of right half of the thorax have been removed.

1 Posterior intercostal arteries
2 Ganglion of sympathetic trunk
3 **Sympathetic trunk**
4 Vessels and nerves of the intercostal space (from above: Posterior intercostal vein and artery and intercostal nerve)
5 Right primary bronchus
6 Ramus communicans of sympathetic trunk
7 Esophageal plexus (branches of right vagus nerve)
8 Pulmonary veins
9 Posterior intercostal vein
10 **Azygos vein**
11 Esophagus
12 Greater splanchnic nerve
13 **Right vagus nerve**
14 **Right phrenic nerve**
15 Inferior cervical cardiac branches of vagus nerve
16 **Aortic arch**
17 Superior vena cava
18 Right pulmonary artery
19 **Heart with pericardium**
20 Diaphragm



Organs of posterior and superior mediastinum (left lateral aspect).

1 Subclavian artery
2 Subclavian vein
3 Clavicle (divided)
4 **Left vagus nerve**
5 First rib (divided)
6 Left superior intercostal vein
7 **Left atrium with pericardium**
8 **Left phrenic nerve** and pericardiacophrenic artery and vein
9 Esophageal plexus (branches derived from left vagus nerve)
10 **Apex of heart with pericardium**
11 Brachial plexus
12 Scapula (divided)
13 Posterior intercostal arteries
14 Ramus communicans of sympathetic trunk
15 **Sympathetic trunk**
16 Aortic arch
17 Left vagus nerve and left recurrent laryngeal nerve
18 Left pulmonary artery
19 Left primary bronchus
20 **Thoracic aorta**
21 Pulmonary vein
22 Esophagus (thoracic part)
23 **Diaphragm**
24 Posterior intercostal artery and vein and intercostal nerve



1 Superior vena cava
2 Right atrium
3 Right ventricle
4 **Costal part of diaphragm**
5 Costal margin
6 Position of costodiaphragmatic recess
7 **Lateral arcuate ligament**
8 **Medial arcuate ligament**
9 Right crus of lumbar part of diaphragm
10 Quadratus lumborum muscle
11 Ascending aorta
12 Pulmonary trunk
13 Left ventricle
14 Pericardium, diaphragm
15 Esophageal hiatus and abdominal part of esophagus (cut)
16 **Lumbar part of diaphragm**
17 Aortic hiatus
18 Psoas major muscle
19 Lumbar vertebra

Diaphragm in situ (anterior aspect). Anterior walls of thoracic and abdominal cavities have been removed. Natural position of the heart above the central tendon on the diaphragm is shown.





Changes in the position of the diaphragm and thoracic cage during respiration. Left: lateral aspect; right: anterior aspect. During inspiration the diaphragm moves downwards and the lower part of the thoracic cage expands forward and laterally, causing the costodiaphragmatic recess (R) to enlarge (cf. dotted arrows).



Diaphragm. Paramedian section to the right of the median plane through thoracic and upper abdominal cavity. The plane passes through the superior and inferior vena cava just to the right of the vertebral bodies. Most of the heart remains in situ to the left of this plane (specimen is viewed from the right side).

1 Azygos venous arch
2 Right pulmonary artery
3 **Superior vena cava**
4 Right pulmonary vein
5 Fossa ovalis
6 Hepatic veins
7 Inferior vena cava
8 Right crus of lumbar part of **diaphragm**
9 Medial arcuate ligament
10 Psoas major muscle
11 Left brachiocephalic vein
12 Terminal crista
13 **Right atrium**
14 Right auricle
15 Central tendon of diaphragm
16 Esophagus
17 Celiac trunk and superior mesenteric artery
18 Aorta
19 Costal part of diaphragm
20 Costal margin
21 Transversus abdominis muscle



Diaphragm (superior aspect). The pleura and thoracic wall have been removed.

1 Sternocostal triangle
2 Central tendon (from above)
3 Esophagus
4 Aorta
5 Lumbar part of diaphragm
6 Sternum
7 Sternal part of diaphragm
8 Costal part of diaphragm
9 Entrance of hepatic veins
10 Inferior vena cava
11 Body of 9th thoracic vertebra
12 Spinal cord



Coronal section through the thorax at the level of ascending aorta (anterior aspect).



Coronal section through the thorax at the level of ascending aorta. (MR-Scan.)

1 Clavicle
2 Left brachiocephalic vein
3 Superior lobe of right lung
4 Aortic arch
5 Superior vena cava
6 Right atrium (entrance of inferior vena cava)
7 Coronary sinus
8 Liver
9 Second rib
10 Superior lobe of left lung
11 Pulmonary trunk
12 Ascending aorta and left coronary artery
13 Aortic valve
14 Pericardium
15 Myocardium of left ventricle
16 Lower lobe of left lung
17 Diaphragm
18 Colic flexures
19 Stomach
20 Brachiocephalic trunk



Coronal section through the thorax at the level of superior and inferior vena cava (anterior aspect).



Coronal section through the thorax at the level of superior vena cava. (MR-Scan.)

1 Trachea
2 Upper lobe of right lung
3 **Superior vena cava**
4 Right pulmonary veins
5 Inferior vena cava and right atrium
6 Liver
7 Left common carotid artery
8 Left subclavian vein
9 Upper lobe of left lung
10 Aortic arch
11 Left pulmonary artery
12 Left auricle
13 **Left atrium** with orifices of pulmonary veins
14 Left ventricle (myocardium)
15 Pericardium
16 Diaphragm
17 Left colic flexure
18 Stomach
19 Left subclavian artery



Horizontal section through the thorax at level 1 (from below).



Horizontal section through the thorax at level 1 (from below). (MR-Scan.)

1	Internal thoracic artery and vein	12	Pectoralis major and minor muscles
2	Right atrium	13	Conus arteriosus (right ventricle), pulmonic valve
3	Lung	14	Ascending aorta and left coronary artery (only in upper figure)
4	Pulmonary artery	15	**Left atrium**
5	Pulmonary vein	16	**Descending aorta**
6	Primary bronchus	17	Thoracic vertebra
7	Esophagus	18	Spinal cord
8	Serratus anterior muscle	19	Latissimus dorsi muscle
9	Scapula	20	Trapezius muscle
10	Longissimus thoracis muscle		
11	Sternum		


11
21
22
23
2
24
25
26
7
27
17
18
28
29
30
24
31
32
33
34
5
16
35
27
36
19
20

Horizontal section through the thorax at level 2 (from below).


11
2
3
7
21
31
15
16
3
18

Horizontal section through the thorax at level 2 (from below). (MR-Scan.)



Levels of sections.

21 **Right ventricle**
22 Right coronary artery
23 Right atrioventricular valve
24 Lung (upper lobe)
25 **Left atrium**
26 Pulmonary veins
27 Lung (lower lobe)
28 Erector muscle of spine
29 Third costal cartilage
30 Nipple
31 **Left ventricle**
32 Pericardium
33 Left atrioventricular valve
34 Left coronary artery and coronary sinus
35 Accessory hemiazygos vein
36 Serratus anterior muscle
37 Pulmonary trunk



Heart and right lung of the fetus (viewed from left side). The left lung has been removed. Note the ductus arteriosus (Botalli).



Heart of the fetus (anterior aspect). Right atrium and ventricle opened.

Shunts in the fetal circulation system		
1. Ductus venosus (of Arantius)	between umbilical vein and inferior vena cava	bypass of liver circulation
2. Foramen ovale	between right and left atrium	bypass of pulmonary circulation
3. Ductus arteriosus (Botalli)	between pulmonary trunk and aorta	

1 Right common carotid artery
2 Right brachiocephalic vein
3 Left brachiocephalic vein
4 Superior vena cava
5 **Ascending aorta**
6 Right auricle
7 **Pulmonary trunk**
8 Left primary bronchus
9 Left auricle
10 Right ventricle
11 Left ventricle
12 Left common carotid artery
13 Trachea
14 Superior lobe of right lung
15 Left subclavian artery
16 Aortic arch
17 **Ductus arteriosus (Botalli)**
18 Inferior lobe of right lung
19 Left pulmonary artery with branches to the left lung
20 **Descending aorta**
21 Left pulmonary veins
22 Inferior vena cava
23 **Foramen ovale**
24 Right atrium
25 Opening of inferior vena cava
26 Valve of inferior vena cava (Eustachian valve)
27 Opening of coronary sinus
28 Anterior papillary muscle of right ventricle



◁ **Heart of the fetus** (schematic drawing). Direction of blood flow indicated by arrows. Note the change in oxygenation of blood after ductus arteriosus entry into aorta.



Thoracic and abdominal organs in the newborn (anterior aspect). The right atrium has been opened to show the foramen ovale. The left lobe of the liver has been removed.

1 Internal jugular vein and right common carotid artery
2 Right and left brachiocephalic vein
3 Aortic arch
4 Superior vena cava
5 **Foramen ovale**
6 Inferior vena cava
7 **Ductus venosus**
8 Liver
9 **Umbilical vein**
10 Small intestine
11 **Umbilical artery**
12 Urachus
13 Trachea and left internal jugular vein
14 Left pulmonary artery
15 **Ductus arteriosus** (Botalli)
16 Right ventricle
17 Hepatic arteries (red) and portal vein (blue)
18 Stomach
19 Urinary bladder
20 Portal vein
21 Pulmonary veins
22 Descending aorta
23 Placenta



◁ **Fetal circulatory system.** (Schematic drawing.) The oxygen gradient is indicated by color.



Survey of upper portion of digestive system. Oral cavity, pharynx, esophagus, and stomach.



Organization of digestive system. Position of abdominal organs.

1 Hard palate
2 Soft palate with uvula
3 Vestibule of the mouth
4 Oral cavity proper
5 Tongue
6 Epiglottis
7 Vocal ligament and larynx
8 Trachea
9 Right lung
10 Superior part of duodenum
11 Pylorus
12 Pyloric antrum
13 Nasopharynx
14 Dens of axis
15 Oropharynx
16 Laryngopharynx
17 Esophagus (thoracic part)
18 Left primary bronchus
19 Left lung
20 Abdominal part of esophagus and cardia
21 Fundus of stomach
22 Body of stomach
23 Pancreas
24 Transverse colon (divided)
25 Descending colon
26 Jejunum
27 Sigmoid colon
28 Rectum
29 Liver
30 Gall bladder
31 Duodenum
32 Ascending colon
33 Ileum
34 Vermiform appendix



Abdominal organs in situ. The greater omentum has been partly removed or reflected.

1 Thyroid gland
2 Upper lobe of right lung
3 Middle lobe of right lung
4 Heart
5 Diaphragm
6 Round ligament of liver (ligamentum teres)
7 **Transverse colon**
8 Cecum
9 Small intestine (ileum)
10 Thymus
11 Upper lobe of left lung
12 Lower lobe of left lung
13 Pericardium (cut edge)
14 **Liver** (left lobe)
15 **Stomach**
16 Greater omentum
17 **Small intestine** (jejunum)
18 Sigmoid colon
19 Rectus abdominis muscle
20 Small intestine (section)
21 Rib
22 Common bile duct, duodenum and pancreas
23 Inferior vena cava
24 Liver
25 Body of second lumbar vertebra
26 Right kidney
27 Cauda equina and dura mater
28 Linea alba
29 Stomach and pylorus
30 Superior mesenteric artery and vein
31 Abdominal aorta
32 Left renal artery and vein
33 Left kidney
34 Psoas major muscle
35 Deep muscles of the back
36 Pancreas adjacent to lesser sac (bursa omentalis)
37 Falciform ligament with ligamentum teres



Transverse section through the abdominal cavity at the level of the second lumbar vertebra (from below).


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24

Midsagittal section through the trunk (female).


4
5
7
26
10
11
27
12
28
25
29
16
30
9
31
32
33
34
23

Midsagittal section through the tunk (female).
(Schematic drawing.)
Blue = omental bursa; red = peritoneum.

1 Sternum
2 Right ventricle of heart
3 Diaphragm
4 Liver
5 Stomach
6 Transverse mesocolon
7 Transverse colon
8 Umbilicus
9 Mesentery
10 Small intestine
11 Uterus
12 Urinary bladder
13 Pubic symphysis
14 Left atrium of heart
15 Caudate lobe of liver
16 Omental bursa or lesser sac
17 Conus medullaris
18 Pancreas
19 Cauda equina
20 Intervertebral discs (lumbar vertebral column)
21 Sacral promontory
22 Sigmoid colon
23 Anal canal
24 Anus
25 Lesser omentum
26 Greater omentum
27 Vesicouterine pouch
28 Urethra
29 Epiploic (omental) foramen
30 Duodenum
31 Rectum
32 Rectouterine pouch
33 Vaginal part of cervix of uterus
34 Vagina



Anterior abdominal wall with pelvic cavity and thigh (frontal section, male) (internal aspect).

1 Left ventricle with pericardium
2 Diaphragm
3 Remnant of liver
4 Ligamentum teres (free margin of falciform ligament)
5 Site of umbilicus
6 **Medial umbilical fold** (containing the obliterated umbilical artery)
7 **Lateral umbilical fold** (containing inferior epigastric artery and vein)
8 **Median umbilical fold** (containing remnant of urachus)
9 Head of femur and pelvic bone
10 Urinary bladder
11 Root of penis
12 Falciform ligament of liver
13 Rib (divided)
14 Iliac crest (divided)
15 Site of **deep inguinal ring** and lateral inguinal fossa
16 Iliopsoas muscle (divided)
17 Medial inguinal fossa
18 Supravesical fossa
19 Posterior layer of rectus sheath
20 Transversus abdominis muscle
21 Umbilicus and arcuate line
22 **Inferior epigastric artery**
23 Femoral nerve
24 Iliopsoas muscle
25 Remnant of umbilical artery
26 Femoral artery and vein
27 Tendinous intersection of rectus abdominis muscle
28 Rectus abdominis muscle
29 Interfoveolar ligament
30 Pubic symphysis (divided)
31 External iliac artery and vein



Anterior abdominal wall (male) (internal aspect). The peritoneum and parts of the posterior layer of rectus sheath have been removed. Dissection of inferior epigastric arteries and veins.



Stomach (ventral aspect).



Mucosa of posterior wall of stomach (ventral aspect).



Parasagittal section through upper part of left abdominal cavity 3.5 cm lateral to median plane.

1 Esophagus
2 Cardiac notch
3 **Cardiac part of stomach**
4 Lesser curvature of stomach
5 **Pyloric sphincter**
6 Angular notch (incisura angularis)
7 **Pyloric canal**
8 Pyloric antrum
9 Fundus of stomach
10 Greater curvature of stomach
11 Body of stomach
12 Folds of mucous membrane (gastric rugae)
13 **Gastric canal**
14 Right ventricle of heart
15 Diaphragm (cut edge)
16 Abdominal portion of esophagus
17 **Liver**
18 Cardiac part of stomach (cut edge)
19 Position of pyloric canal
20 Body of stomach
21 Transverse colon
22 Small intestine
23 Lung (cut edge)
24 Fundus of stomach (section)
25 Lumbar portion of diaphragm (cut edge)
26 Suprarenal gland
27 Splenic vein
28 Pancreas
29 Superior mesenteric artery and vein
30 Intervertebral disc



Muscular coat of stomach, outer layer (ventral aspect).



Muscular coat of stomach, middle layer (ventral aspect).



Muscular coat of stomach, inner layer (ventral aspect).

1 Esophagus (abdominal part)
2 Cardiac notch
3 Cardiac part of stomach
4 Longitudinal muscle layer at lesser curvature of stomach
5 Lesser curvature
6 Incisura angularis
7 Circular muscle layer of pyloric part of stomach
8 Pyloric sphincter muscle
9 Fundus of stomach
10 Circular muscle layer of fundus of stomach
11 Longitudinal muscle layer of greater curvature of stomach
12 Greater curvature of stomach
13 Longitudinal muscle layer (transition from body to pyloric part of stomach)
14 Pyloric part of stomach
15 Oblique muscle fibers



Pancreas with adjacent duodenum, spleen, liver and related arteries. The pancreatic ducts have been partly dissected. The duodenal papillae are indicated by probes. Left half of liver has been removed.



Pancreas, duodenum and extrahepatic bile ducts. (Schematic drawing.)

1 Liver
2 Left and right hepatic ducts
3 Common hepatic duct
4 **Cystic duct**
5 **Gall bladder**
6 **Pancreatic duct** and **head of pancreas**
7 Pylorus (cut)
8 Right gastro-omental (gastroepiploic) artery
9 Minor duodenal papilla (probe)
10 Major duodenal papilla (probe)
11 **Superior mesenteric artery and vein**
12 Inferior vena cava and iliocolic artery
13 **Portal vein,** lig. teres of liver and lig. venosum
14 Aorta
15 Common hepatic artery, left branch of hepatic artery proper, and right gastric artery
16 **Gastroduodenal artery** and right branch of hepatic artery proper
17 Spleen
18 Splenic artery and vein
19 **Tail of pancreas**
20 Left gastro-omental artery
21 Middle colic artery
22 Jejunum
23 Jejunal arteries
24 Aorta and inferior mesenteric artery
25 **Common bile duct**
26 Horizontal part of duodenum
27 Esophagus
28 Stomach
29 **Pancreatic duct**
30 Duodenojejunal flexure
31 Lumbal vertebrae



Radiograph of biliary ducts, gallbladder and pancreatic duct (anterior-posterior view).

1 Left hepatic duct
2 Right hepatic duct
3 Cystic duct
4 Neck of gallbladder
5 Body of gallbladder
6 Fundus of gallbladder
7 Common hepatic duct
8 **Common bile duct**
9 **Pancreatic duct**
10 **Greater duodenal papilla**
11 Second lumbar vertebra
12 Folds of mucous membrane of gallbladder
13 Muscular coat of gallbladder
14 Neck of gallbladder (opened)
15 Cystic duct with spiral fold
16 **Lesser duodenal papilla**
17 **Accessory pancreatic duct**
18 Uncinate process
19 Plica circularis of duodenum (Kerckrings's fold)
20 Head of pancreas
21 Body of pancreas
22 Tail of pancreas
23 Descending part of duodenum
24 Incisure of pancreas



Isolated gallbladder and cystic duct (anterior aspect).
The gallbladder has been opened to display the mucous membrane.



Pancreas with descending part of duodenum (posterior aspect). The duodenum was opened to display the duodenal papillae. Pancreatic duct has been dissected, the common bile duct has been divided. The sphincter of Oddi is shown.



Liver in situ (ventral aspect). Part of the diaphragm has been removed.



Liver in situ. Parasagittal section through the left side of the abdomen 2 cm lateral to median plane.

1 Ribs (cut edges)
2 Diaphragm
3 Diaphragmatic surface of liver
4 **Falciform ligament of liver**
5 Right lobe of liver
6 Fundus of gallbladder
7 Gastrocolic ligament
8 Greater omentum
9 Aorta
10 Esophagus
11 Left lobe of liver
12 Stomach
13 **Ligamentum teres**
14 Transverse colon
15 Right atrium of heart
16 Central tendon and sternal portion of diaphragm
17 Liver (cut edge)
18 Entrance to duodenum (pylorus)
19 Stomach
20 Duodenum
21 Transverse colon (divided, dilated)
22 Small intestine
23 Thoracic aorta (longitudinally divided)
24 Esophagus (longitudinally divided)
25 Esophageal hiatus of diaphragm
26 **Omental bursa** (lesser sac)
27 Splenic artery
28 Pancreas
29 Left renal vein
30 Intervertebral disc
31 Abdominal aorta (longitudinally divided)



Liver (inferior aspect). Dissection of porta hepatis. Gallbladder partly collapsed. Ventral margin of liver above.

1 Fundus of **gallbladder**
2 Peritoneum (cut edges)
3 Cystic artery
4 **Cystic duct**
5 **Right lobe of liver**
6 Inferior vena cava
7 Bare area of liver
8 Notch for ligamentum teres and falciform ligament
9 Ligamentum teres
10 Falciform ligament of liver
11 **Quadrate lobe of liver**
12 Common hepatic duct
13 **Left lobe of liver**
14 Hepatic artery proper
15 **Common bile duct** } Portal triad
16 **Portal vein**
17 **Caudate lobe of liver**
18 Ligamentum venosum
19 Ligament of inferior vena cava
20 Appendix fibrosa (left triangular ligament)
21 Coronary ligament of liver
22 Hepatic veins
23 Porta hepatis



Segmentation of the liver (anterior aspect). Liver segments indicated by roman numerals.



Liver (ventral aspect) (transparent drawing illustrating margins of peritoneal folds).

It should be noted that the anatomical left and right lobes of the liver do not reflect the internal distribution of the hepatic artery, portal vein, and biliary ducts. Using these structures as criteria the left lobe includes both the caudate and quadrate lobes and thus the line dividing the liver into left and right functional lobes passes through the gallbladder and inferior vena cava. The three main hepatic veins drain segments of the liver which have no visible external markings.



Location of the spleen in situ (left-lateral aspect). Intercostal spaces and diaphragm have been fenestrated.

1 Serratus anterior muscle
2 Left lung
3 Diaphragm
4 Spleen
5 External abdominal oblique muscle
6 Gastrosplenic ligament
7 **Splenic artery**
8 Pancreas tail
9 Superior margin of spleen
10 Anterior border of spleen
11 Inferior vena cava
12 **Hepatic veins**
13 Liver
14 **Portal vein**
15 Paraumbilical veins within falciform ligament
16 **Superior mesenteric vein**
17 Middle colic vein
18 Right colic vein
19 Ascending colon
20 Ileocolic vein
21 Vermiform appendix and appendicular vein
22 Spleen
23 Gastric and esophageal veins
24 **Splenic vein**
25 **Inferior mesenteric vein**
26 Right gastroepiploic vein
27 Ileal veins
28 Descending colon
29 Ileum
30 Sigmoid veins
31 Superior rectal veins



Spleen (visceral surface), hilum of spleen with vessels, nerves and ligaments.



Main tributaries of portal vein. (Schematic drawing of portal circulation.) X = sites of portocaval anastomoses.



Tributaries of portal vein and branches of superior mesenteric artery (injected with colored solutions). Blue = veins; red = arteries. One layer of peritoneum has been removed to display the vascular arcades of the intestine. Part of the head of the pancreas and the mesocolon have also been removed to show the deeper vessels.

1 Greater omentum (reflected)
2 Transverse colon (raised cranially)
3 Celiac trunk
4 **Portal vein**
5 Superior mesenteric vein
6 **Superior mesenteric artery**
7 Right colic vein
8 Iliocolic vein
9 Right colic artery
10 Iliocolic artery
11 Appendicular artery
12 Cecum
13 Transverse mesocolon
14 **Splenic artery and vein**
15 Pancreas (divided)
16 Renal artery and vein
17 Duodenojejunal flexure
18 Middle colic artery
19 Jejunum
20 Jejunal arteries
21 Arterial arcades to intestine
22 Jejunal veins
23 Ileal arteries
24 Ileal vein
25 Ileum with mesentery



Superior mesenteric artery in relation to pancreas and duodenum. Stomach and transverse colon has been removed and the liver elevated. Note the location of the spleen. A yellow probe is inserted through the omental foramen.



Main branches of superior and inferior mesenteric arteries. (Schematic drawing.)

1	Ligamentum teres
2	Liver
3	Caudate lobe of liver
4	Proper hepatic artery and portal vein
5	Gallbladder and common bile duct
6	Right gastric artery and pylorus
7	**Pancreas**
8	Ascending colon
9	Gastroduodenal artery
10	**Superior mesenteric artery**
11	Duodenum
12	**Iliocolic artery**
13	Terminal part of ileum
14	Mesenteric lymph nodes
15	Right common iliac artery
16	Cecum
17	Left lobe of liver
18	**Spleen**
19	Left gastro-omental (gastroepiploic) artery
20	Stomach
21	Left gastric artery
22	Left colic flexure (cut)
23	**Splenic artery**
24	Right gastro-omental (gastroepiploic) artery
25	Renal artery
26	**Ileal arteries**
27	Left kidney
28	Left colic artery
29	Middle colic artery
30	**Superior mesenteric vein**
31	Jejunum
32	**Jejunal arteries**
33	Inferior vena cava
34	Sigmoid colon
35	Right colic artery
36	Appendicular artery
37	**Inferior mesenteric artery**
38	Sigmoid arteries
39	Superior rectal artery
40	Fundus of gallbladder
41	Common bile duct
42	Portal vein
43	Beginning of jejunum
44	Duodenojejunal flexure
45	Ureter
46	Splenic artery
47	**Celiac trunk**
48	Renal vein
49	Abdominal aorta
50	Descending colon
51	Left common iliac artery
52	Transverse mesocolon



Vessels of abdominal organs; dissection of inferior mesenteric artery and celiac trunk (injected with colored solutions). Blue = veins; red = arteries. The small intestine including the duodenojejunal flexure has been reflected laterally and the stomach and liver have been raised. The peritoneum of the posterior abdominal wall has been removed to display the inferior mesenteric artery and its branches to the colon.

The **superior mesenteric artery** arises at the level of L_1 vertebra branching of the abdominal aorta. It supplies jejunum and ileum as the ascending and transverse colon. At the left colic flexure branches of the middle colic artery (from the superior mesenteric artery) and of the left colic artery (from the inferior mesenteric artery) anastomose (so-called **Riolani's anastomosis**). The arteries unite to form loops or arches called arterial arcades from which straight vessels (vasa recta) arise. The vasa recta do not anastomose within the mesentery. Thus occlusion of these vessels may lead to necrosis of the segment of bowel concerned and ileus. Within the wall of the intestine there are many anastomoses of blood vessels so that blockage of a single vessel is usually not dangerous. The arteries are paralleled by veins which convey blood to the portal vein. Closely related to the venous drainage are the lymph vessels which pass the mesenteric lymph nodes and finally enter the cisterna chyli.



Abdominal organs. The anterior thoracic and abdominal walls have been removed.

1	Middle lobe of right lung
2	Xiphoid process
3	Costal margin
4	Falciform ligament of liver
5	Quadrate lobe of liver
6	Greater omentum
7	Upper lobe of left lung
8	Heart
9	Diaphragm
10	Left lobe of liver
11	Ligamentum teres
12	Stomach
13	Gastrocolic ligament
14	Transverse colon
15	Taenia coli
16	Appendices epiploicae
17	Cecum
18	Taenia coli
19	Ileum
20	Transverse mesocolon
21	Jejunum
22	Sigmoid colon
23	Position of root of mesentery
24	Vermiform appendix
25	Duodenojejunal flexure
26	Mesentery



Abdominal organs. The greater omentum which is fixed to the transverse colon has been raised.



Abdominal organs (anterior aspect). The transverse colon has been reflected.

1 Diaphragm
2 Costal margin
3 Transverse colon
4 Ascending colon with haustra
5 Free taenia of cecum
6 **Ileum**
7 **Cecum**
8 **Falciform ligament of liver**
9 Liver
10 Stomach
11 Gastrocolic ligament
12 Jejunum
13 Sigmoid colon
14 **Vermiform appendix**
15 Terminal ileum
16 **Mesoappendix**
17 Mesentery



Abdominal organs in situ. The greater omentum has been removed.



Ascending colon, cecum and vermiform appendix (detail of the preceding figure).



Variations in the position of the vermiform appendix. a = retrocecal; b = paracolic; c = retroileal; d = preileal; e = subcecal.



Abdominal organs. Dissection of inferior mesenteric artery and autonomic plexus. The transverse colon with mesocolon has been raised and the small intestine reflected.

1	Liver
2	Gallbladder
3	**Middle colic artery**
4	Jejunal artery
5	**Inferior mesenteric artery**
6	Sympathetic nerves and ganglia
7	Right common iliac artery
8	Small intestine (ileum)
9	Transverse colon (reflected)
10	Transverse mesocolon
11	Anastomosis between middle and left colic artery
12	Spleen
13	**Abdominal aorta**
14	**Left colic artery**
15	Duodenojejunal flexure
16	Descending colon (free taenia of colon)
17	Inferior mesenteric vein
18	Superior hypogastric plexus
19	**Superior rectal artery**
20	Sigmoid arteries
21	Peritoneum (cut edge)
22	Sigmoid mesocolon
23	Sigmoid colon



1 Liver
2 Middle colic artery
3 Horizontal part of duodenum (extended)
4 **Superior mesenteric artery and vein**
5 **Right colic artery**
6 **Iliocolic artery**
7 Ascending colon
8 Cecum
9 Greater omentum (reflected)
10 Transverse colon
11 Transverse mesocolon
12 Duodenojejunal flexure
13 **Jejunal arteries**
14 Jejunum
15 **Ileal arteries**
16 **Mesenteric lymph nodes and lymph vessels**
17 Ileum
18 Abdominal aorta
19 Inferior vena cava
20 Stomach
21 Spleen
22 Splenic artery
23 Head of pancreas
24 Superior mesenteric artery

Abdominal organs. Superior mesenteric artery. Mesenteric lymph nodes. Transverse colon reflected.



Frontal section through the abdominal cavity. (MR-Scan: the intestinal tract and vessels are filled with a paramagnetic substance [Gadolinium]; courtesy of Dr. W. Rödl, Erlangen.)



Abdominal cavity. Mesenteries. The small intestine has been reflected laterally to demonstrate the mesentery.

1 Lung
2 Diaphragm
3 Falciform ligament of liver
4 Jejunum
5 Ileocecal fold
6 Mesoappendix
7 Vermiform appendix
8 **Ileocecal junction**
9 **Cecum**
10 Pericardial sac
11 Xiphoid process
12 Costal margin
13 Liver
14 Stomach
15 Transverse colon
16 **Duodenojejunal flexure**
17 Inferior duodenal fold
18 Mesentery
19 Position of left kidney
20 Descending colon
21 Position of left common iliac artery
22 Sacral promontory
23 Sigmoid mesocolon
24 Sigmoid colon
25 Rectum
26 Beginning of jejunum
27 Peritoneum of posterior abdominal wall
28 Transverse mesocolon
29 Superior duodenal fold
30 Superior duodenal recess
31 Retroduodenal recess
32 Free taenia of ascending colon
33 **Ileocecal valve**
34 Frenulum of ileocecal valve
35 Orifice of vermiform appendix (probe)
36 **Ileocolic artery**
37 Vermiform appendix with appendicular artery
38 Ascending colon



Duodenojejunal flexure (enlargement of preceding figure).



Ileocecal valve (ventral aspect). The cecum and terminal part of the ileum have been opened.



Upper abdominal organs. Thorax and anterior part of diaphragm have been removed and the liver raised to display the lesser omentum. A probe has been inserted into the epiploic foramen and lesser sac.

1 Falciform ligament and ligamentum teres
2 Liver
3 Gallbladder (fundus)
4 Hepatoduodenal ligament
5 **Epiploic foramen** (probe)
6 Pylorus
7 Descending part of duodenum
8 Right colic flexure
9 **Gastrocolic ligament**
10 Caudate lobe of liver (behind lesser omentum)
11 **Lesser omentum**
12 Stomach
13 Lesser curvature of stomach
14 Superior part of duodenum
15 Diaphragm
16 Greater curvature of stomach with gastroepiploic vessels
17 Twelfth thoracic vertebra
18 Right kidney
19 Right suprarenal gland
20 Inferior vena cava
21 Falciform ligament of liver
22 Abdominal aorta
23 Spleen
24 Lienorenal ligament
25 Gastrosplenic ligament
26 Pancreas
27 Lesser sac



Horizontal section through omental bursa above the level of epiploic foramen (black arrow). Viewed from above. Red arrows: routes of the arterial branches of celiac trunk to liver, stomach, duodenum, and pancreas. (Schematic drawing.)



Upper abdominal organs, lesser sac, omental bursa (anterior aspect). Lesser omentum partly removed, liver and stomach slightly reflected.

1 Falciform ligament and ligamentum teres
2 Liver
3 **Hepatoduodenal ligament**
4 Gallbladder
5 Probe within the epiploic foramen
6 Superior part of duodenum
7 Pylorus
8 Descending part of duodenum
9 Right colic flexure
10 Gastrocolic ligament
11 **Greater omentum**
12 Caudate lobe of liver
13 Fundus of stomach
14 Probe at the level of the vestibule of lesser sac
15 **Head of pancreas**
16 Lesser curvature of stomach
17 **Body of stomach**
18 Diaphragm
19 Greater curvature with gastroepiploic vessels
20 Head of pancreas and gastropancreatic fold
21 **Spleen**
22 **Tail of pancreas**
23 Left colic flexure
24 Root of transverse mesocolon
25 Transverse mesocolon
26 Gastrocolic ligament (cut edge)
27 **Transverse colon**
28 Umbilicus
29 Small intestine
30 Lesser omentum
31 Lesser sac (omental bursa)
32 Duodenum
33 Mesentery
34 Sigmoid colon


1
2
10
4
5
8
9
11
17
14
20
21
22
23
18
24
25
26
27

Upper abdominal organs, lesser sac, omental bursa (anterior aspect). The gastrocolic ligament has been divided and the whole stomach raised to display the posterior wall of the lesser sac.


2
17
25
27
11
28
29
30
31
15
32
33
34

Midsagittal section through abdominal cavity demonstrating the site of lesser sac (blue). (Schematic drawing.) The epiploic foramen, entrance to the lesser sac, is indicated by an arrow. Red = peritoneum.


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
1
7
21
20
21
22
23
24
25
26
27
28
29
30
31
32
33

Arteries of upper abdominal organs; dissection of celiac trunk. The lesser omentum has been removed and the lesser curvature of the stomach reflected to display the branches of the celiac trunk.


2
10
9
6
14
30
15
34
18
28
36
25
37
35
24
26
29

Branches of celiac trunk.
(Schematic drawing.)



Branches of celiac trunk; blood supply of liver, pancreas and spleen. The stomach, superior part of duodenum and celiac ganglion have been removed to reveal the anterior aspect of the posterior wall of the lesser sac (omental bursa) and the vessels and ducts of the hepatoduodenal ligament. The pancreas has been slightly reflected anteriorly.

1	Lung
2	Liver (visceral surface)
3	Lymph node
4	Inferior vena cava
5	Ligamentum teres (reflected)
6	Right branch of hepatic artery proper
7	Diaphragm
8	**Common hepatic duct** (dilated)
9	Cystic duct and artery
10	Gallbladder
11	Probe in epiploic foramen
12	Right lobe of liver
13	**Portal vein**
14	**Right gastric artery**
15	Duodenum
16	Pylorus
17	Right colic flexure
18	**Right gastro-omental** (gastroepiploic) **artery**
19	Transverse colon
20	Abdominal part of esophagus (cardiac part of stomach)
21	Fundus of stomach
22	Esophageal branches of left gastric artery
23	Lumbar part of diaphragm
24	Left gastric artery
25	**Celiac trunk**
26	**Splenic artery**
27	Pancreas
28	**Common hepatic artery**
29	Left gastro-omental (gastroepiploic) artery
30	**Gastroduodenal artery**
31	Pyloric part of stomach
32	Greater curvature of stomach
33	Gastrocolic ligament
34	Superior pancreaticoduodenal artery
35	Short gastric arteries
36	Aorta
37	Spleen
38	Caudate lobe of liver
39	Left branch of hepatic artery proper
40	Descending part of duodenum (cut)
41	Left inferior phrenic artery
42	Suprarenal gland
43	Kidney
44	Transverse mesocolon



Pancreas and extrahepatic bile ducts in situ (anterior aspect). The gastrocolic ligament has been divided, the transverse colon and the stomach were replaced to display pancreas and superior mesenteric vessels.

1 Stomach (pyloric part) and pylorus
2 Right gastro-omental (gastroepiploic) artery
3 **Fundus of gall bladder**
4 Liver, right lobe
5 Head of pancreas
6 **Superior mesenteric artery** and **vein**
7 Duodenum
8 Middle colic artery
9 Transverse colon
10 Greater curvature of stomach (remnants of gastrocolic ligament)
11 **Body of stomach**
12 **Body of pancreas**
13 Left gastro-omental (gastroepiploic) artery
14 **Splenic artery**
15 **Spleen**
16 Tail of pancreas
17 Left colic flexure
18 Jejunum
19 Lung (inferior lobe of right lung)
20 **Common hepatic duct** and caudate lobe of liver
21 Portal vein and hepatic artery proper
22 Cystic duct and right gastric artery
23 **Common bile duct** and gastroduodenal artery
24 Pylorus (cut)
25 Major and minor duodenal papillas (probes)
26 Duodenum (inferior part)
27 Right kidney, ureter and ovarian artery
28 Iliocolic artery and inferior vena cava
29 Right and left vagal trunk
30 **Esophagus**
31 Diaphragm
32 Cut edge of esophagus, left gastric artery with esophageal branch
33 Celiac trunk
34 Common hepatic artery, main pancreatic duct and **pancreas**
35 Renal vein
36 Duodenojejunal flexure
37 Left kidney
38 Jejunal arteries
39 Abdominal aorta and left ureter
40 Cystic artery
41 Hepatic proper artery
42 **Celiac trunk**
43 Right gastric artery
44 **Common hepatic artery**
45 Gastroduodenal artery
46 **Superior mesenteric artery**
47 Superior posterior pancreaticoduodenal artery
48 Superior anterior pancreaticoduodenal artery
49 Short gastric arteries
50 Left gastric artery
51 Posterior pancreatic branch of splenic artery
52 Inferior pancreaticoduodenal artery



Blood supply of upper abdominal organs (branches of the celiac trunk and superior mesenteric artery). (Schematic drawing.)


19
20
3
21
22
23
24
4
25
6
2
26
27
28
29
30
31
32
15
14
34
35
36
13
37
38
39

Pancreas, extrahepatic bile ducts, spleen and liver with their vessels in situ. The stomach has been removed, the liver elevated, and the descending part of duodenum opened to display the openings of pancreatic ducts. The pancreatic ducts were dissected. Note the location of superior mesenteric artery and vein between duodenum and pancreas. Arrow: probe within the epiploic foramen.


19
20
3
21
22
23
24
4
25
6
2
26
27
28
29
30
31
32
33
15
14
34
35
36
13
37
38
39

Schematic drawing of the specimen depicted above. Note the branching of the celiac trunk (partially covered by the body of the pancreas), and the main arterial supply of liver, spleen, pancreas, stomach, and duodenum.



Abdominal cavity after removal of stomach, jejunum, ileum and part of the transverse colon. Liver has been slightly raised.

1 Liver
2 Falciform ligament
3 Hepatoduodenal ligament
4 Pylorus (divided)
5 Gallbladder
6 Probe within the epiploic foramen
7 Duodenojejunal flexure (divided)
8 **Greater omentum**
9 Root of mesentery
10 Ascending colon
11 Free colic taenia
12 End of ileum (divided)
13 Vermiform appendix with mesoappendix
14 Cecum
15 Pancreas and site of lesser sac
16 Diaphragm
17 Spleen
18 Cardia (part of stomach, divided)
19 Head of pancreas
20 Body and tail of pancreas
21 **Transverse mesocolon**
22 Transverse colon (divided)
23 Descending colon
24 Cut edge of mesentery
25 Sigmoid colon
26 Rectum
27 Attachment of bare area of liver
28 Inferior vena cava
29 Kidney
30 Attachment of right colic flexure
31 Root of transverse mesocolon
32 Junction between descending and horizontal parts of duodenum
33 Bare surface for ascending colon
34 **Ileocecal recess**
35 **Retrocecal recess**
36 Root of mesoappendix
37 Superior recess
38 Isthmus (opening) } of **lesser sac (omental bursa)**
39 Splenic recess
40 **Superior duodenal recess**
41 **Inferior duodenal recess**
42 Bare surface for descending colon
43 **Paracolic recesses**
44 **Root of mesentery**
45 Root of mesosigmoid
46 **Intersigmoid recess**
47 Hepatic veins
48 Duodenojejunal flexure
49 Attachment of left colic flexure
50 Esophagus
51 Entrance to lesser sac through the epiploic foramen



Peritoneal reflections from organs and the position of root of mesentry and peritoneal recesses on the posterior abdominal wall. (Schematic drawing.)


16
47
28
27
6
4
29
32
31
33
34
36
18
37
17
38
39
20
31
48
29
49
44
42
45
46
26

Peritoneal recesses on the posterior abdominal wall. The liver, stomach, jejunum, ileum, and colon have been removed. The duodenum, pancreas, and spleen have been left in place.



Horizontal section through the abdominal cavity at level 1 (from below).





Horizontal section through the body. MR-Scan, corresponding to level 1. Arrow: stomach.

1 Rectus abdominis muscle
2 Falciform ligament
3 **Liver** (right lobe)
4 Inferior vena cava
5 Diaphragm
6 Intervertebral disc
7 Liver (left lobe)
8 Rib
9 Liver (caudate lobe)
10 Abdominal (descending) aorta
11 **Stomach**
12 **Spleen**
13 Spinal cord
14 Longissimus and iliocostalis muscles
15 Body of vertebra
16 Abdominal rectus muscle
17 External abdominal oblique muscle
18 Transverse colon
19 **Head of pancreas**
20 **Greater duodenal papilla**
21 Duodenum
22 Suprarenal gland and ureter
23 **Kidney**
24 Round ligament of liver
25 Superior mesenteric artery and vein
26 Psoas major muscle
27 Descending colon
28 Quadratus lumborum muscle
29 Cauda equina
30 Right renal vein
31 **Small intestine**
32 Iliacus muscle
33 Ilium
34 **Ileocecal valve**
35 Cecum
36 Common iliac artery and vein
37 Gluteus medius muscle
38 Vertebral canal and dura mater


16
17
18
19
20
21
3
22
23
15
14
24
31
25
31
10
4
26
27
23
28
29

Horizontal section through the abdominal cavity at the level of greater duodenal papilla (from below).


19
3
21
30
15
23
8
31
10
23
12
29

Horizontal section through the body. CT-Scan, corresponding to level 2.


34
35
36
37
38
14
31
27
26
32
33

Horizontal section through the abdominal cavity at level 3 (from below).



Posterior abdominal wall with duodenum, pancreas and spleen (anterior aspect). Dissection of pancreatic and common bile duct. The stomach has been removed, the liver raised and the duodenum anteriorly opened.

1 Ligamentum teres
2 Gallbladder and cystic artery
3 Common hepatic duct and portal vein
4 Cystic duct
5 Right gastric artery (pylorus with superior part of duodenum, cut and reflected)
6 Gastroduodenal artery
7 **Common bile duct**
8 Probe within the minor duodenal papilla
9 **Accessory pancreatic duct**
10 Probe within the major duodenal papilla
11 Descending part of duodenum (opened)
12 Middle colic artery and inferior pancreaticoduodenal artery
13 Horizontal part of duodenum (distended)
14 **Superior mesenteric artery**
15 Liver (left lobe)
16 Caudate lobe of liver and hepatic artery proper
17 Abdominal part of esophagus (cut)
18 Probe in epiploic foramen and lymph node
19 Left gastric artery
20 **Spleen**
21 Splenic vein and branches of splenic artery
22 **Pancreatic duct and head of pancreas**
23 Left colic flexure and tail of pancreas
24 Duodenojejunal flexure



Parasagittal section through the thoracic and abdominal cavities (right side, medial aspect).



Position of kidneys and urinary system (anterior view). The excursions of the kidneys with the respiratory movements of the diaphragm are indicated. (Schematic drawing.)



Parasagittal section through the abdominal cavity. (MR-Scan, courtesy of Prof. W. Rödl, Erlangen).

1	Right lung (superior and middle lobes)
2	Transverse colon
3	Jejunum
4	Abdominal wall
5	Fourth rib
6	Right lung (inferior lobe)
7	Diaphragm
8	**Liver**
9	Suprarenal gland
10	**Kidney**
11	Renal pelvis
12	Small intestine
13	Perirenal fat pad
14	Eleventh rib
15	Ureter (abdominal part)
16	Ureter (pelvic part)
17	**Urinary bladder**
18	Urethra
19	Colon



Horizontal section through the abdominal cavity at the level of the first lumbar vertebra (from below).

1	Pyloric antrum
2	Gastroduodenal artery
3	Descending part of duodenum
4	Vestibule of lesser sac
5	Inferior vena cava and liver
6	Body of first lumbar vertebra
7	Cauda equina
8	**Right kidney**
9	Latissimus dorsi muscle
10	Iliocostalis muscle
11	Rectus abdominis muscle
12	Stomach
13	Lesser sac
14	Splenic vein
15	Superior mesenteric artery
16	Pancreas
17	Aorta and left renal artery
18	Transverse colon
19	Renal artery and vein
20	Spleen
21	**Left kidney**
22	Psoas major muscle
23	Multifidus muscle
24	Margin of lung
25	Margin of pleura
26	Renal pelvis
27	**Left ureter**
28	Descending colon
29	Rectum
30	Right suprarenal gland
31	12th rib
32	Ascending colon
33	**Right ureter**
34	Cecum
35	Vermiform appendix
36	Urinary bladder
37	Liver
38	Anterior layer of renal fascia
39	Duodenum
40	Perirenal fatty tissue
41	Posterior layer of renal fascia
42	Abdominal cavity



Positions of urinary organs (posterior view). Notice that the upper part of the kidney reaches the level of the margin of pleura and lung.



Retroperitoneal tissue, location of the right kidney. (Schematic drawing.) Yellow = adipose capsule of kidney.



1 Scalenus anterior, medius and posterior muscles
2 Left subclavian artery
3 Left subclavian vein
4 Pulmonic valve
5 Arterial cone
6 Right ventricle of heart
7 Liver
8 Stomach
9 Transverse colon
10 Small intestine
11 Left lung
12 Left main bronchus
13 Branches of pulmonary vein
14 Left ventricle of heart
15 Spleen
16 Splenic artery and vein and pancreas
17 **Left kidney**
18 Psoas major muscle
19 Inferior vena cava
20 **Renal vein**
21 Body of 12th thoracic vertebra and vertebral canal
22 **Right kidney**
23 Superior mesenteric artery
24 Superior mesenteric vein
25 Pancreas
26 Abdominal aorta
27 Left psoas major and quadratus lumborum muscles
28 Anterior layer of renal fascia } of Gerota
29 Posterior layer of renal fascia }
30 Perirenal fatty tissue
31 Abdominal cavity
32 Descending and sigmoid colon

Parasagittal section through the thoracic and abdominal cavities at the level of the left kidney
(5.5 cm left of median plane).



Horizontal section through the retroperitoneal region at level of 12th thoracic vertebra. (CT-Scan, from below.)



Retroperitoneal tissue, position of left kidney. (Schematic drawing.)



Coronal section through right kidney and suprarenal gland (posterior view). The renal pelvis has been opened and the fatty tissue removed to display the renal vessels.

1 Renal vein
2 Renal artery
3 **Renal pelvis**
4 Abdominal part of ureter
5 **Major renal calyx**
6 Cribriform area of renal papilla
7 Cortex of suprarenal gland
8 Medulla of suprarenal gland
9 **Cortex of kidney**
10 **Medulla of kidney**
11 Renal papilla
12 **Minor renal calyx**
13 Renal sinus
14 Renal columns
15 **Fibrous capsule** of kidney



Right kidney (posterior view). Partial coronal section to expose internal aspect of the kidney.

Each kidney can be divided in five segments supplied by individual interlobar arteries considered as end arteries. Thus, obstruction leads to infarcts marking the trace of segment borders. The anterior kidney surface reveals four segments, the posterior only three (No. 1, 4 and 5).



Cast of renal pelvis and calices.
1–4 = Renal segments on anterior surface.



Left kidney and suprarenal gland in situ. The anterior cortical layer of the kidney has been removed to display the renal pelvis and papillae.

1 Hepatic vein
2 Anterior and posterior vagal trunk
3 Inferior vena cava
4 Lumbar part of diaphragm
5 Right greater and lesser splanchnic nerves
6 Celiac trunk
7 Celiac ganglion and plexus
8 Superior mesenteric artery
9 Left renal vein
10 Right sympathetic trunk and ganglion
11 Abdominal aorta
12 Left sympathetic trunk
13 Esophagus (cut),
left greater splanchnic nerve
14 **Left suprarenal gland**
15 Left renal artery
16 Renal pelvis
17 Renal papilla with minor calyx
18 Left testicular vein
19 Left ureter
20 Psoas major muscle
21 Quadratus lumborum muscle
22 **Glomerulus**
23 Afferent arteriole of glomerulus
24 **Glomeruli**
25 Radiating cortical artery
26 Subcortical or arcuate artey
27 Subcortical or arcuate vein
28 Interlobular vein
29 Interlobular artery
30 **Interlobar artery and vein**
31 Vessels of renal capsule
32 Efferent arteriole of glomerulus
33 **Vasa recta** of renal medulla
34 Spiral arteries of renal pelvis



Glomeruli (210×). Scanning electron micrograph showing glomeruli and associated arteries.



Architecture of vascular system of kidney. (Schematic drawing.)

1 Arteriolae rectae of renal medulla
2 Interlobar artery
3 Interlobular arteries
4 Cortical glomeruli
5 Juxtamedullary glomeruli
6 Body of first lumbar vertebra
7 Left renal artery
8 Abdominal aorta with catheter
9 Upper pole of kidney
10 Anterior branch
11 Posterior branch } of renal artery
12 Anterior inferior segmental artery
13 Lower pole of kidney
14 Celiac trunk
15 Superior mesenteric artery
16 Middle colic artery
17 Splenic artery



Resin cast of kidney arteries. (Scanning electron micrograph.)



Left kidney. (Arteriogram.)



Abdominal aorta. (Subtraction angiograph.)



Main branches of descending aorta. (Schematic drawing.)

1 Right common carotid artery
2 Right subclavian artery
3 **Brachiocephalic trunk**
4 Thoracic aorta
5 Diaphragm
6 **Celiac trunk**
7 Right **renal artery**
8 **Superior mesenteric artery**
9 Lumbar arteries
10 Right **common iliac artery**
11 Internal iliac artery
12 **External iliac artery**
13 Left common carotid artery
14 Left subclavian artery
15 Highest intercostal artery
16 Aortic arch
17 **Posterior intercostal arteries**
18 Left renal artery
19 Left testicular (or ovarian) artery
20 Inferior mesenteric artery
21 Median sacral artery
22 **Superior suprarenal artery**
23 Upper capsular artery
24 Anterior branch of renal artery
25 Perforating artery
26 Lower capsular artery
27 Ureter
28 Right inferior phrenic artery
29 Left inferior phrenic artery
30 **Middle suprarenal artery**
31 **Inferior suprarenal artery**
32 Posterior branch of renal artery



Arteries of kidney and suprarenal gland. (Schematic drawing.)



Ultrasound image of the right kidney (upper and lower border of the kidney marked by crosses. × = small cortical cyst).



Retroperitoneal organs, urinary system in the male (anterior view). The peritoneum has been removed.

1 Costal arch
2 Right renal vein
3 **Right kidney**
4 Inferior vena cava
5 Iliohypogastric nerve and quadratus lumborum
6 **Ureter** (abdominal part)
7 Psoas major muscle and genitofemoral nerve
8 Iliacus muscle
9 External iliac artery
10 **Ureter** (pelvic part)
11 Ductus deferens
12 Testis and epididymis
13 Celiac trunk
14 Superior mesenteric artery
15 **Left kidney**
16 Abdominal aorta
17 Inferior mesenteric artery
18 Common iliac artery
19 Iliac crest
20 Sacral promontory
21 Rectum (cut)
22 Medial umbilical ligament
23 **Urinary bladder**
24 Penis



Retroperitoneal organs, urinary system in situ (anterior view). The peritoneum has been removed. Red = arteries; blue = veins.

1 Diaphragm
2 Hepatic veins
3 **Inferior vena cava**
4 Common hepatic artery
5 Right suprarenal gland
6 Celiac trunk
7 **Right renal vein**
8 Right kidney
9 **Abdominal aorta**
10 Subcostal nerve
11 Iliohypogastric nerve
12 Quadratus lumborum muscle
13 Iliac crest
14 Iliacus muscle
15 Right lateral femoral cutaneous nerve
16 **External iliac artery**
17 Femoral nerve
18 Right inferior epigastric artery
19 Central tendon of diaphragm
20 Inferior phrenic artery
21 Cardiac part of stomach and esophageal branches of left gastric artery
22 Spleen
23 Splenic artery
24 Left suprarenal gland
25 **Left renal artery**
26 Left **kidney**
27 Superior mesenteric artery
28 Psoas major muscle
29 Inferior mesenteric artery
30 **Ureter**
31 Testicular artery and vein
32 Transversus abdominis muscle
33 Left common iliac artery
34 Left common iliac vein
35 Lateral femoral cutaneous nerve
36 Genitofemoral nerve
37 Rectum (cut)
38 Urinary bladder



1 Internal jugular vein
2 Right common carotid artery and right vagus nerve
3 Jugulo-omohyoid lymph node
4 Right lymphatic duct
5 Subclavian trunk
6 Right subclavian vein
7 Bronchomediastinal trunk
8 Azygos vein
9 Diaphragm
10 Right kidney
11 Right lumbar trunk
12 Right ureter
13 Common iliac lymph nodes
14 Right internal iliac artery
15 External iliac lymph nodes
16 Right external iliac artery
17 Left common carotid artery and left vagus nerve
18 Internal jugular vein
19 Deep cervical lymph nodes
20 Thoracic duct entering left jugular angle
21 Left subclavian vein
22 Left brachiocephalic vein
23 **Thoracic duct**
24 Mediastinal lymph nodes
25 Thoracic aorta
26 Left suprarenal gland
27 Left renal artery
28 Left kidney
29 Cisterna chyli
30 Lumbar lymph nodes
31 Abdominal aorta
32 Left ureter
33 Sacral lymph nodes
34 Rectum (cut edge)

Lymph vessels and lymph nodes of the posterior wall of thoracic and abdominal cavities (anterior aspect). Green = lymph vessels and nodes; blue = veins; red = arteries; white = nerves.



Vessels and nerves of posterior abdominal wall (anterior aspect). Part of the left psoas major muscle has been removed to display the lumbar plexus. Red = arteries, blue = veins.

1 Diaphragm
2 Hepatic veins
3 **Inferior vena cava**
4 Inferior phrenic artery
5 Right renal vein
6 **Iliohypogastric nerve**
7 Quadratus lumborum muscle
8 Subcostal nerve
9 Inferior mesenteric artery
10 Right genitofemoral nerve and psoas major muscle
11 Common iliac artery
12 Iliacus muscle
13 Right ureter (divided)
14 Lateral femoral cutaneous nerve
15 Internal iliac artery
16 **Femoral nerve**
17 **External iliac artery**
18 Inferior epigastric artery
19 Cardiac part of stomach and oesophageal branches of left gastric artery
20 Splenic artery
21 Celiac trunk
22 **Superior mesenteric artery**
23 Left renal artery
24 **Ilioinguinal nerve**
25 Sympathetic trunk
26 Transversus abdominis muscle
27 Iliac crest
28 Left **genitofemoral nerve**
29 Left **obturator nerve**
30 Median sacral artery
31 Psoas major muscle (divided) with supplying artery
32 Rectum (cut)
33 Urinary bladder


1
14
15
2
16
3
17
18
4
17
5
7
19
20
21
6
22
8
9
6
23
10
24
5
11
25
12
13
26

Posterior wall of thoracic and abdominal cavities with sympathetic trunk, vagus nerve and autonomic ganglia (anterior view). Thoracic and abdominal organs removed, except esophagus and aorta.


1
14
27
28
29
36
30
31
5
4
17
7
19
5
6
14
32
9
37
10
33
25
13
34
35
35
38

Organization of autonomic nervous system (after Mattuschka). (Schematic drawing.) Yellow = parasympathetic nerves; green = sympathetic nerves.



Ganglia and plexus of the autonomic nervous system within the retroperitoneal space (anterior view). The kidneys and the inferior vena cava with its tributaries have been removed (compare pp. 264 and 265).

1 **Right vagus nerve**
2 Right subclavian artery
3 Esophagus
4 Aortic arch
5 **Sympathetic trunk**
6 Greater splanchnic nerve
7 Intercostal nerve
8 Abdominal part of esophagus and vagal trunk
9 **Celiac trunk with celiac ganglion**
10 **Superior mesenteric artery and ganglion**
11 Psoas major muscle and genitofemoral nerve
12 Common iliac artery
13 **Superior hypogastric plexus and ganglion**
14 **Left vagus nerve**
15 Brachial plexus
16 Left subclavian artery
17 Left recurrent laryngeal nerve
18 Inferior cervical cardiac nerve
19 Thoracic aorta
20 Esophageal plexus
21 Azygos vein
22 Diaphragm
23 Splenic artery
24 Left renal artery and plexus
25 **Inferior mesenteric ganglion and artery**
26 Left external iliac artery
27 **Superior cervical ganglion** of sympathetic trunk
28 Superior cardiac branch of sympathetic trunk
29 Middle cervical ganglion of sympathetic trunk
30 **Inferior cervical ganglion** of sympathetic trunk
31 Right recurrent laryngeal nerve
32 Lesser splanchnic nerve
33 Lumbar splanchnic nerves
34 Sacral splanchnic nerves
35 **Inferior hypogastric ganglion and plexus**
36 Left recurrent laryngeal nerve
37 **Aorticorenal plexus** and renal artery
38 Ganglion impar
39 Esophagus with branches of vagus nerve
40 Hepatic veins
41 Right crus of diaphragm
42 Inferior phrenic artery
43 Right vagus nerve entering the celiac ganglion
44 Right lumbar lymph trunk
45 Lumbar part of right sympathetic trunk
46 Lumbar artery and vein
47 **Psoas major muscle**
48 Iliac crest
49 Inferior vena cava
50 **Iliacus muscle**
51 Ureter
52 Left vagus nerve forming the esophageal plexus
53 Left vagus nerve forming the gastric plexus
54 Esophagus continuing into the cardiac part of stomach
55 Lumbocostal triangle
56 Position of 12th rib
57 Left lumbar lymph trunk
58 Ganglion of sympathetic trunk
59 **Quadratus lumborum muscle**
60 Lumbar part of left sympathetic trunk
61 Iliac lymph vessels


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15

Male genital organs isolated (right lateral aspect).


1
2
16
3
17
18
6
10
12
19
13
14
8
9
15

Male genital organs in situ (right lateral aspect).


20
21
22
16
12
1
23
2
24
3
4
17
5
6
8
9
25
26
27
11
10
28
29
13
14
12
30
15

Positions of male genital organs (right lateral aspect).
(Schematic drawing.)

1 Ureter
2 **Seminal vesicle**
3 **Prostate gland**
4 Urogenital diaphragm and membranous part of urethra
5 Bulbourethral or Cowper's gland
6 Bulb of penis
7 Left and right crus penis
8 **Epididymis**
9 **Testis**
10 **Urinary bladder**
11 Apex of urinary bladder
12 **Ductus deferens**
13 **Corpus cavernosum of penis**
14 **Corpus spongiosum of penis**
15 Glans penis
16 Ampulla of rectum
17 Levator ani muscle
18 Anal canal and external anal sphincter muscle
19 Spermatic cord (cut)
20 Sacral promontory
21 Sigmoid colon
22 Peritoneum (cut edge)
23 **Rectovesical pouch**
24 Ejaculatory duct
25 Lateral umbilical fold
26 Medial umbilical fold
27 Deep inguinal ring and ductus deferens
28 Pubic symphysis
29 Prostatic part of urethra
30 Spongy urethra



Midsagittal section through the male pelvis.

1 Sigmoid colon
2 **Ampulla of rectum**
3 Ampulla of ductus deferens
4 External anal sphincter muscle
5 Internal anal sphincter muscle
6 **Anal canal**
7 Bulb of penis
8 **Testis** (cut surface)
9 Median umbilical ligament
10 **Urinary bladder**
11 Internal urethral orifice and sphincter muscle (sphincter vesicae)
12 Pubic symphysis
13 Prostatic part of urethra
14 **Prostate gland**
15 Membranous urethra and external urethral sphincter muscle
16 **Corpus cavernosum of penis**
17 **Spongy urethra**
18 Corpus spongiosum of penis
19 Foreskin or prepuce
20 Glans penis
21 Kidney
22 Renal pelvis
23 Abdominal part of ureter
24 Pelvic part of ureter
25 Seminal vesicle
26 Ejaculatory duct
27 Bulbourethral or Cowper's gland
28 **Ductus deferens**
29 **Epididymis**
30 Umbilicus
31 Trigone of bladder and ureteric orifice
32 Navicular fossa of urethra
33 External urethral orifice
34 **Testis**



Male urogenital system. (Schematic drawing.)

The **prostate** is located between bladder and urogenital diaphragm. The penis includes the **urethra** and thus serves for both ejaculation and micturition. The internal (involuntary) and external (voluntary) urethral sphincters are widely separated. The **ureter** having crossed the ductus deferens enters the urinary bladder at its base. The peritoneum is reflected off the posterior surface of the bladder onto the rectum thus forming the rectovesical pouch.



Male urogenital organs; isolated (anterior view). Urinary bladder, prostate and urethra have been opened. The urinary bladder is contracted.

1 Ureter
2 Ductus deferens
3 Interureteric fold
4 Ureteric orifice
5 Seminal vesicle
6 Trigone of bladder
7 Prostatic urethra with seminal colliculus and urethral crest
8 Deep transverse perineal muscle
9 Membranous urethra
10 **Spongy urethra**
11 Mucous membrane of **urinary bladder**
12 Internal urethral orifice and uvula of bladder
13 **Prostate**
14 Prostatic utricle
15 Right and left **corpus cavernosum of penis**
16 Ejaculatory duct
17 **Sphincter urethrae muscle**
18 **Median umbilical fold** with remnant of urachus
19 Medial umbilical fold with remnant of umbilical artery
20 **Urinary bladder**
21 Rectovesical pouch
22 Rectum
23 Sacrum
24 Deep iliac circumflex artery
25 Deep inguinal ring and ductus deferens
26 External iliac artery and vein
27 **Femoral nerve**
28 Obturator nerve
29 Ilium and sacrum
30 Inferior epigastric artery
31 Iliopsoas muscle



Pelvic cavity in the male (viewed from above).



Posterior half of male urethra and prostate in continuity with neck of bladder (anterior view).



1	Apex of urinary bladder with urachus
2	**Urinary bladder**
3	Ureter
4	**Ductus deferens**
5	Ampulla of ductus deferens
6	**Seminal vesicle**
7	**Prostate**
8	**Bulbourethral or Cowper's gland**
9	**Bulb of penis**
10	Crus penis
11	**Corpus spongiosum of penis**
12	**Corpus cavernosum of penis**
13	Testis and epididymis with coverings
14	Glans penis
15	Fundus of bladder
16	**Head of epididymis**
17	**Testis**
18	Mucous membrane of bladder
19	Trigone of bladder
20	Ureteric orifice
21	Internal urethral orifice
22	Seminal colliculus
23	Prostate
24	Prostatic urethra
25	Membranous urethra
26	Spongy (penile) urethra
27	Skin of penis
28	Deep dorsal vein of penis (unpaired)
29	Dorsal artery of penis (paired)
30	**Tunica albuginea of corpora cavernosa**
31	Septum of penis
32	Deep artery of penis
33	Tunica albuginea of corpus spongiosum
34	Deep fascia of penis

Male genital organs, isolated (posterior view).



Urinary bladder, urethra and penis (anterior view, open longitudinally).



Cross-section of penis (anterior view).

1 **Corpus cavernosum of penis**
2 **Corpus spongiosum of penis**
3 Corona of glans penis
4 **Glans penis**
5 Suspensory ligament of penis
6 Inferior pubic ramus
7 Crus penis
8 **Bulb of penis**
9 Deep dorsal vein of penis
10 Septum pectiniforme
11 Dorsal artery of penis
12 Bulbourethral or Cowper's gland
13 Urinary bladder
14 **Seminal vesicle**
15 Ampulla of ductus deferens
16 Ductus deferens
17 Membranous urethra
18 **Prostate**
19 Ureter



Male external genital organs (lateral view). The corpus spongiosum of the penis with the glans penis has been isolated and reflected.



Resin cast of erected penis.



Male external genital organs and accessory glands. (Schematic drawing.)



Testis and epididymis with investing layers (lateral view).



Testis and epididymis (lateral view). The tunica vaginalis has been opened.



Testis, epididymis and spermatic cord. Dissection of spermatic cord and ductus deferens (left side, posterolateral aspect).

1 Spermatic cord covered with cremasteric fascia
2 **Cremaster muscle**
3 Position of epididymis
4 Internal spermatic fascia
5 Position of testis
6 Internal spermatic fascia with adjacent investing layers of testis (cut surface)
7 **Head of epididymis**
8 **Testis with tunica vaginalis** (visceral layer)
9 Body of epididymis
10 Pampiniform venous plexus (anterior veins)
11 **Testicular artery**
12 Tunica vaginalis (parietal layer, cut edge)
13 Skin and dartos muscle (reflected)
14 **Ductus deferens**
15 Artery of ductus deferens
16 Posterior veins of pampiniform plexus
17 Tail of epididymis
18 Transition of epididymal duct to ductus deferens and venous plexus
19 Parietal layer of tunica vaginalis
20 Appendix of epididymis
21 Appendix of testis
22 Gubernaculum testis



Longitudinal section through testis and epididymis. The left figure shows the testicular septa after removal of the seminiferous tubules.

1 Spermatic cord (cut surface)
2 Head of epididymis (cut surface)
3 Septa of testis
4 Mediastinum testis
5 Tunica albuginea
6 Superior pole of testis
7 Convoluted seminiferous tubules
8 Inferior pole of testis



Accessory glands of male genital organs in situ. Coronal section through the pelvic cavity. Posterior aspect of urinary bladder, prostate and seminal vesicles.

1 Ureter
2 **Ductus deferens**
3 **Seminal vesicle**
4 **Ampulla of ductus deferens**
5 Ejaculatory duct (proximal portion)
6 **Prostate**
7 Membranous urethra
8 **Bulbourethral or Cowper's gland**
9 Bulb of penis
10 Penis
11 Glans penis
12 **Urinary bladder**
13 Levator ani muscle
14 Obturator internus muscle
15 Pelvic bone (cut edge)
16 Puboprostatic ligament
17 **Corpus spongiosum of penis**
18 Head of epididymis
19 Beginning of ductus deferens
20 Testis
21 Tail of epididymis
22 Corpus cavernosum of penis
23 Spermatic cord
24 Pectineus and adductor muscles
25 Pubic bone
26 **Prostatic part of urethra** (seminal colliculus)
27 Rectum
28 Sciatic nerve
29 Great saphenous vein
30 Sartorius muscle
31 Femoral artery and vein
32 Rectus femoris muscle
33 Tensor fasciae latae muscle
34 Pectineus muscle
35 Iliopsoas muscle
36 Vastus lateralis muscle
37 Obturator externus muscle
38 Femur
39 Ischial tuberosity
40 Gluteus maximus muscle



Horizontal section through pelvic cavity at level of prostate.



Coronal section through pelvic cavity at the level of prostate and hip joint (anterior aspect).

1 Acetabulum of hip joint
2 **Urinary bladder**
3 Head of femur
4 Internal urethral orifice
5 **Prostate**
6 **Seminal colliculus**
7 Obturator internus muscle
8 Ischiorectal fossa
9 Membranous urethra
10 Deep transverse perineus muscle
11 **Crus penis** and **ischiocavernosus muscle**
12 Prostatic part of urethra
13 Prostatic plexus
14 Levator ani muscle
15 Obturator externus muscle
16 **Bulb of penis**
17 Ampulla of rectum
18 **Anal canal**
19 Seminal vesicle
20 Internal anal sphincter muscle
21 External anal sphincter muscle
22 Anus
23 Psoas major muscle
24 Intervertebral disc
25 Ilium
26 Ligament of the head of the femur
27 Sacral promontory



Coronal section through pelvic cavity. (MR-Scan.)



Coronal section through anal canal.



Pelvic cavity in the male (right half of parasagittal section). The arteries have been injected with red resin. The parietal layer of peritoneum has been removed. The urinary bladder is filled to a great extent.

1 Left common iliac artery
2 Right common iliac artery
3 Right **ureter**
4 Right **internal iliac artery**
5 Right external iliac artery and vein
6 Right **obturator artery and nerve**
7 Umbilical artery
8 Sigmoid and superior vesical artery
9 Left ductus deferens
10 **Urinary bladder**
11 Pubic bone (cut)
12 **Prostate**
13 Vesicoprostatic venous plexus
14 Deep dorsal vein of penis and dorsal artery of penis
15 Penis and superficial dorsal vein
16 **Spermatic cord and testicular artery**
17 **Bulb of penis** and deep artery of penis
18 Cauda equina and dura mater (divided)
19 Intervertebral disc between fifth lumbar vertebra and sacrum
20 **Sacral promontory**
21 Mesosigmoid
22 Left ureter
23 Left internal pudendal artery
24 Ischial spine (cut), sacrospinal ligament, inferior gluteal artery
25 Left **inferior vesical artery**
26 **Seminal vesicle**
27 Levator ani muscle
28 Branches of inferior rectal artery
29 Perineal artery
30 Anus
31 Posterior scrotal branches
32 **Pudendal nerve** and sacrotuberal ligament



Vessels of pelvic cavity in the male (midsagittal section, right side, medial aspect). Urinary bladder and rectum have been partly removed; the hypogastric plexus is displayed.



Main branches of internal iliac artery in the male. (Schematic drawing.)

1 Intervertebral disc between 5th lumbar vertebra and sacrum
2 Right common iliac artery
3 Sacral promontory
4 Right **internal iliac artery**
5 Femoral nerve
6 Right external iliac artery
7 Psoas major muscle
8 Right external iliac vein
9 **Umbilical artery**
10 Medial umbilical ligament with obliterated umbilical artery
11 Obturator nerve
12 Superior hypogastric plexus
13 Sacral spinal nerve (of sacral plexus)
14 **Inferior hypogastric plexus**
15 Rectum
16 Iliolumbar artery
17 Lateral sacral artery
18 Superior gluteal artery and sacral spinal nerve
19 Pudendal and coccygeal plexus
20 Inferior gluteal artery
21 **Internal pudendal artery**
22 Coccygeus muscle overlying sacrospinous ligament
23 **Anal canal**
24 Middle rectal artery
25 **Superior vesical artery** and branch to the ductus deferens
26 Pubic bone (cut)
27 Bulbospongiosus muscle
28 Right ureter
29 Right ductus deferens
30 Left ureter
31 **Urinary bladder**
32 **Prostate**
33 Urogenital diaphragm
34 Deep artery of penis
35 Dorsal artery of penis
36 Penis
37 Testis
38 Left common iliac artery
39 **Obturator artery**
40 **Inferior vesical artery**
41 Levator ani muscle
42 Inferior rectal artery


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16

Male external genital organs with penis, testis, and spermatic cord, superficial layers (anterior view).


17
18
19
20
13
21
22
16
23
24
25
26
27
28
29
30
31
32
33
34
A

1 Femoral nerve
2 Femoral artery and vein
3 Femoral branch of genitofemoral nerve
4 **Spermatic cord** with genital branch of genitofemoral nerve
5 **Penis** with deep fascia
6 Great saphenous vein
7 Cremaster muscle
8 **Testis with cremaster muscle**
9 Superficial inguinal ring
10 Internal spermatic fascia (cut edge)
11 Ilioinguinal nerve
12 Left spermatic cord
13 Pampiniform venous plexus
14 External spermatic fascia
15 Superficial dorsal vein of penis
16 **Glans penis**


15
19
20
34
30
35
B

Vessels of male genital organs. (Schematic drawing.)
A = lateral aspect; B = cross-section of penis.



Male external genital organs with penis, testis and spermatic cord, deeper layers (ventral aspect). The deep fascia of the penis has been opened to display the dorsal nerves and vessels.



Male genital organs (lateral aspect). (Arteriogram.)

17	Testicular vein
18	Testicular artery
19	Deep dorsal vein of penis
20	**Dorsal artery of penis**
21	**Helicine arteries**
22	Prepuce
23	**Testis** with **tunica albuginea**
24	Ductus deferens
25	Ureter
26	Urinary bladder
27	**Seminal vesicle**
28	**Prostate**
29	Vesicoprostatic venous plexus
30	**Deep artery of penis**
31	Artery of bulb of penis
32	Internal pudendal artery
33	Corpus spongiosum of penis
34	Corpus cavernosum of penis
35	Urethra
36	Cremasteric fascia with cremaster muscle
37	Dorsal nerve of penis
38	**Epididymis**
39	**Tunica vaginalis** (visceral layer)
40	Tunica vaginalis (parietal layer)
41	Testis with vascular loops



1 Glans penis
2 **Corpus spongiosum of penis**
3 **Corpus cavernosum of penis**
4 Gracilis muscle
5 Adductor muscles
6 Ischiocavernosus muscle overlying crus of penis
7 Perineal body
8 Gluteus maximus muscle
9 Coccyx
10 **Bulbospongiosus** muscle
11 Deep transverse perineus muscle covered by inferior fascia of urogenital diaphragm
12 Superficial transverse perineus muscle
13 Anus
14 **External anal sphincter muscle**
15 **Levator ani muscle**
16 Anococcygeal ligament
17 Obturator internus muscle
18 Urethra
19 **Deep transverse perineus muscle**

Muscles of urogenital and pelvic diaphragms in the male (from below).



Muscles of urogenital and pelvic diaphragms in the male (from below). The penis has been divided. (Schematic drawing.)



Urogenital diaphragm and external genital organs in the male with vessels and nerves (from below). The testes have been reflected laterally.

1 Right testis (reflected laterally and upward)
2 Bulbospongiosus muscle
3 Ischiocavernosus muscle
4 Adductor magnus muscle
5 **Posterior scrotal nerves** and superficial perineal arteries
6 Posterior scrotal artery and vein
7 Right artery of bulb of penis
8 Perineal body
9 Perineal branches of pudendal nerve
10 **Pudendal nerve** and **internal pudendal artery**
11 **Inferior rectal arteries** and **nerves**
12 Inferior cluneal nerve
13 Coccyx (location)
14 Penis
15 Left testis (reflected laterally)
16 Left posterior scrotal artery
17 **Deep transverse perineal muscle**
18 Left artery of bulb of penis
19 **Posterior femoral cutaneous nerve**
20 External anal sphincter muscle
21 **Anus**
22 Gluteus maximus muscle
23 Anococcygeal nerves
24 Acetabulum (femur removed)
25 Ligament of femoral head
26 Body of ischium (cut)
27 Sciatic nerve
28 Coccygeus muscle
29 **Levator ani muscle**
   a iliococcygeus muscle
   b pubococcygeus muscle
   c puborectalis muscle
30 Prostatic venous plexus
31 Body of pubis
32 Testis



Pelvic diaphragm and external genital organs in the male. The right half of the pelvis including obturator internus muscle and femur had been removed to display the right half of levator ani muscle.



1 Right testis (reflected)
2 Posterior scrotal nerves
3 Left crus penis with ischiocavernosus muscle
4 **Anus**
5 Inferior cluneal nerves
6 **Penis**
7 Left testis (reflected)
8 Dorsal artery and nerve of penis
9 Urethra
10 **Deep transverse perineus muscle**
11 **Perineal branch of pudendal nerve**
12 Artery of bulb of penis (reflected)
13 Branch of posterior femoral cutaneous nerve
14 **Internal pudendal artery** and **pudendal nerve**
15 Inferior rectal arteries and nerves
16 Gluteus maximus muscle
17 Dorsal nerve of penis
18 Posterior femoral cutaneous nerve
19 Perineal branches of pudendal nerve
20 Inferior rectal nerves
21 **Bulbocavernosus muscle** (inside: dorsal artery of penis)
22 Perineal artery
23 **External anal sphincter muscle**
24 Inferior rectal artery and veins

Urogenital diaphragm and external genital organs in the male (from below).
The left crus penis has been isolated and reflected laterally together with the bulb of the penis. The urethra has been cut.



Urogenital and anal region in the male (from below). Right side: nerves; left side: arteries and veins.



1 Right testis (reflected)
2 **Corpus spongiosum of penis**
3 **Corpus cavernosum of penis**
4 Perineal branch of posterior femoral cutaneous nerve
5 Posterior scrotal arteries and nerves
6 Deep artery of penis
7 Deep transverse perineal muscle
8 Right **perineal nerves**
9 **Inferior rectal nerves**
10 Inferior cluneal nerve
11 Anococcygeal nerves
12 Left spermatic cord
13 Left testis (cut surface)
14 Dorsal artery and nerve of penis
15 Deep dorsal vein of penis
16 **Urethra** (cut)
17 Artery of bulb of penis
18 Superficial transverse perineus muscle
19 Left artery of bulb of penis
20 Perineal branch of pudendal nerve
21 **Anus**
22 **External anal sphincter muscle**
23 Gluteus maximus muscle
24 Internal pudendal artery and pudendal nerve
25 Sacrotuberous ligament
26 Coccyx
27 Urogenital diaphragm (deep transverse perineus muscle)
28 Tendinous center of perineum (perineal body)
29 **Levator ani muscle**
30 Anococcygeal ligament
31 Obturator internus muscle
32 Dorsal artery of penis

Anal and urogenital region in the male (from below). The root of penis has been cut. Dissection of the urogenital diaphragm.



Urogenital and pelvic diaphragms in the male (from below). The penis has been removed. The arrows indicate the course of vessels and nerves. (Schematic drawing.)



Coronal section through the female urinary bladder and urethra (anterior view).

1 Muscular coat of **urinary bladder**
2 Folds of mucous membrane of urinary bladder
3 Right ureteric orifice
4 Interureteric fold
5 Internal urethral orifice
6 Vesicouterine venous plexus
7 **Urethra**
8 Pubic bone (cut edge)
9 External urethral orifice
10 Vestibule of vagina
11 Left ureteric orifice
12 Trigone of bladder
13 Obturator internus muscle
14 Levator ani muscle
15 Bulb of the vestibule
16 Left labium minus
17 **Uterine tube**
18 Mesosalpinx
19 **Ovary**
20 Sigmoid colon
21 Saphenous opening
22 Urinary bladder
23 Vesicouterine pouch
24 **Fundus of uterus**
25 Rectouterine pouch (of Douglas)
26 Ampulla of rectum
27 Kidney
28 Abdominal part of ureter
29 Pelvic part of ureter
30 Anal canal
31 Perineum (perineal body)
32 Umbilicus
33 Infundibulum of uterine tube
34 Vaginal portion of cervix of uterus
35 Vagina
36 Pubic symphysis
37 Clitoris
38 Deep transverse perineus muscle



Femal internal genital organs. Pelvic cavity (from above).



Female urogenital system (midsagittal section). (Schematic drawing.)



Female internal genital organs. Pelvic cavity, seen from above. The uterus has been reflected to the right.



Regional relations of female internal genital organs (medial aspect). (Schematic drawing.)

1 Body of 5th lumbar vertebra
2 Sacral promontory
3 Left ureter
4 Peritoneum (cut edge)
5 Right ureter (divided)
6 **Recto-uterine pouch** (of Douglas)
7 Rectum
8 Umbilicus
9 Sigmoid colon
10 Median umbilical fold with urachus
11 Ampulla of uterine tube
12 Fimbriae of uterine tube
13 **Ovary**
14 **Uterine tube** (isthmus)
15 **Uterus**
16 **Vesico-uterine pouch**
17 Urinary bladder
18 Vagina
19 Pubic symphysis
20 Urethra
21 Clitoris
22 Labium minus
23 Insertion of uterine tube at fundus of uterus
24 Round ligament of uterus
25 Ligament of the ovary
26 Suspensory ligament of ovary
27 Right common iliac artery (covered by peritoneum)
28 Infundibulum of uterine tube



Female internal genital organs in situ. Right half of the pelvis and sacrum have been removed.

1 Body of 5th lumbar vertebra, **suspensory ligament of ovary** and sacral promontory
2 Ureter
3 Medial umbilical ligament (remnant of umbilical artery) (cut)
4 Infundibulum of uterine tube
5 Ampulla of uterine tube
6 **Ovary**
7 **Uterine artery**
8 **Uterine tube**
9 Rectum
10 Levator ani muscle (pelvic diaphragm – cut edge)
11 External anal sphincter muscle
12 Anus (probe)
13 Internal iliac artery
14 Remnant of urachus (median umbilical ligament)
15 **Uterus**
16 Round ligament of uterus
17 **Urinary bladder**
18 **Vagina**
19 **Clitoris**
20 Labium minus
21 External orifice of urethra (red probe)
22 Vaginal orifice (green probe)
23 Lateral umbilical ligament
24 Inferior epigastric artery
25 Obturator artery, vein and nerve
26 External iliac artery
27 **Recto-uterine pouch** (of Douglas)
28 Recto-uterine fold
29 Vesico-uterine pouch
30 Suspensory ligament of ovary
31 Greater vestibular gland and bulb of the vestibule



Female internal genital organs in situ (seen from above). The peritoneum at the left half of pelvic cavity has been removed to display uterine tube, vessels, and nerves.



Coronal section through the pelvic cavity of the female. (MR-Scan.)

1 Psoas major muscle
2 Ampulla of rectum
3 **Uterus**
4 **Urinary bladder**
5 Obturator internus muscle
6 Promontory
7 Sigmoid colon
8 **Uterine tube**
9 Head of femur
10 Urethra
11 Vagina
12 Labium minus
13 Umbilicus
14 Duodenum
15 Ascending part of duodenum
16 Root of mesentery
17 Mesentery
18 Vesico-uterine pouch
19 **Urinary bladder** (collapsed)
20 Pubic symphysis
21 Anterior fornix of vagina
22 Clitoris
23 Labium minus
24 Labium majus
25 Vertebral canal with cauda equina
26 Intervertebral disc
27 Body of 5th lumbar vertebra
28 Sacral promontory
29 Mesosigmoid
30 **Recto-uterine pouch** (of Douglas)
31 Posterior fornix of vagina
32 Cervix of uterus
33 External anal sphincter muscle
34 Anal canal
35 Internal anal sphincter muscle
36 Anus
37 Hymen
38 Small intestine
39 Rectus abdominis muscle



Midsagittal section through the female trunk. The urinary bladder is empty, the position and shape of the uterus are normal.



Female genital organs, isolated (anterior view). The anterior wall of the vagina has been opened to display the vaginal portion of the cervix.



Female internal genital organs. (Schematic drawing.)

1	**Ovary**
2	Mesovarium
3	**Fundus of uterus**
4	Vesico-uterine pouch
5	**Cervix of uterus**
6	Vaginal portion of cervix
7	**Vagina**
8	Crus of clitoris
9	Labium minus
10	Fimbriae of uterine tube
11	Infundibulum of uterine tube
12	Ligament of the ovary
13	Mesosalpinx
14	Uterine tube
15	Suspensory ligament of ovary (caudally displaced)
16	Broad ligament of uterus
17	Round ligament of uterus
18	Corpus cavernosum of clitoris
19	Glans of clitoris
20	**Hymen, vaginal orifice**
21	Promontory
22	Linea terminalis of pelvis
23	Pubic symphysis



Female internal genital organs, isolated (superior-posterior view).



Right ovary and uterine tube, isolated (superior-posterior view). The fimbriae of the uterine tube have been reflected to show the abdominal ostium.



Uterus and related organs (posterior view). The posterior wall of the uterus has been opened.

1 **Fundus of uterus**
2 Uterine tube
3 **Ligament of the ovary**
4 **Ovary**
5 Infundibulum of uterine tube
6 Fimbriae of uterine tube
7 **Ureter**
8 Rectum
9 Apex of urinary bladder and median umbilical ligament
10 Urinary bladder
11 Round ligament of uterus
12 **Mesosalpinx**
13 **Mesovarium**
14 **Rectouterine pouch** (of Douglas)
15 Suspensory ligament of ovary
16 Scarring of ovary (following ovulation)
17 Abdominal opening of uterine tube
18 Body of uterus
19 **Cervical canal**
20 Vaginal portion of cervix of uterus (congestion)
21 Vagina
22 Mucous membrane of uterus
23 Anterior fornix of vagina



Arteriogram of female genital organs (anterior-posterior view). Notice the helicine arteries supplying uterus and ovary.



Arteries of female genital organs. (Schematic drawing.)

1	Ovarian branch of uterine artery (anastomoses with ovarian artery)
2	Tubal branch of ovarian artery
3	Ovarian branch of ovarian artery
4	**Uterine artery**
5	Internal iliac artery
6	Inferior gluteal artery
7	**Internal pudendal artery**
8	Round ligament of uterus
9	**Ovarian artery**
10	Vaginal artery
11	Vaginal orifice
12	Infundibulum of uterine tube
13	Ovary
14	Fundus of uterus
15	Uterine tube
16	Vaginal portion of cervix of uterus
17	Vagina
18	Clitoris
19	Corpus cavernosum of clitoris
20	Bulb of vestibule
21	Greater vestibular gland
22	Suspensory ligament of ovary
23	Artery of round ligament



Full term uterus with placenta (anterior view). The anterior wall of the uterus has been removed to show the location of the placenta.



Main drainage routes of lymph vessels of uterus and its adnexa (indicated by arrows). (Schematic drawing.)
Red = arteries; black = lymph vessels and nodes; yellow = internal genital organs.



Pelvic vessels in the female (anterior-posterior view). (Arteriogram.)

1 Placenta
2 Amnion and chorion
3 Adnexa of uterus (uterine tube and ovaries)
4 Myometrium
5 Round ligament of uterus
6 Internal orifice of uterus
7 Cervix of uterus
8 **Umbilical cord**
9 Lumbar lymph nodes
10 External iliac lymph nodes
11 Inguinal lymph nodes
12 Abdominal aorta
13 Suspensory ligament of ovary
14 External iliac artery
15 Sacral lymph nodes
16 Internal iliac artery
17 Ovary
18 Uterine tube
19 Internal iliac lymph nodes
20 External genital organs
21 Superior gluteal artery
22 **Obturator artery**
23 Inferior gluteal artery
24 **Uterine artery**
25 **Internal pudendal artery**
26 Middle sacral artery
27 **Uterine cavity**
28 Femoral artery
29 Vessels of labium majus
30 Femur



External genital organs in the female (anterior aspect). Labia reflected.



Female external genital organs in relation to internal genital organs and urinary system (isolated, anterior aspect).

1 **Glans clitoris**
2 Labium majus
3 Vestibule of vagina
4 **Hymen**
5 Posterior labial commissure
6 **Body of clitoris**
7 Labium minus
8 **External orifice of urethra**
9 **Vaginal orifice**
10 Ureter
11 Adnexa of uterus
12 Prepuce of clitoris
13 Crus of clitoris
14 Greater vestibular glands
15 Anus and internal anal sphincter muscle
16 Median umbilical ligament containing urachus
17 **Urinary bladder**
18 Infundibulum of uterine tube
19 Ovary
20 Ampulla of uterine tube
21 Suspensory ligament of the ovary
22 Bulbospongiosus muscle and bulb of vestibule
23 Central tendon of perineum (perineal body)
24 External anal sphincter muscle



Cavernous tissue of female external genital organs, isolated (anterior aspect).



Urogenital and pelvic diaphragms (anterior aspect). (Schematic drawing.)
Blue = cavernous tissue of clitoris and bulb of vestibule.



Inguinal canal and round ligament of uterus in situ (right side, ventral aspect).

1	Body of clitoris
2	Crus of clitoris
3	Bulb of vestibule
4	Prepuce of clitoris
5	**Glans of clitoris**
6	Frenulum of clitoris
7	**Labium minus**
8	**Vaginal orifice**
9	**Greater vestibular gland**
10	Lateral crus of superficial inguinal ring
11	Ilioinguinal nerve
12	Intercrural fibers
13	Superficial inguinal ring
14	**Round ligament of uterus**
15	Medial crus of superficial inguinal ring
16	Aponeurosis of external abdominal oblique muscle
17	Deep transverse perineus muscle with fascia
18	Greater vestibular gland
19	Superficial transverse perineus muscle
20	Levator ani muscle
21	Gluteus maximus muscle
22	Suspensory ligament of clitoris
23	External orifice of urethra
24	Bulb of vestibule
25	Perineal body
26	External anal sphincter muscle
27	Anus



Female urogenital diaphragm and external genital organs, superficial layer (from below).



Muscles of pelvic and urogenital diaphragms (from below).
(Schematic drawing.)

1 Fatty tissue encasing round ligament
2 Position of pubic symphysis
3 Clitoris
4 Labium minus
5 Bulb of vestibule
6 Ischiocavernosus muscle
7 **Greater vestibular gland**
8 Perineal branches of pudendal nerve
9 Levator ani muscle
10 Inferior rectal nerves
11 External anal sphincter muscle
12 Gluteus maximus muscle
13 Coccyx
14 Fatty tissue of mons pubis
15 **External orifice of urethra**
16 Urogenital diaphragm with fascia of deep transverse perineus muscle
17 **Vaginal orifice**
18 Superficial transverse perineal muscle
19 **Anus**
20 Bulbospongiosus muscle
21 Obturator internus muscle



Urogenital diaphragm and external genital organs in the female, superficial layer (from below). On the right side the bulb of vestibule has been removed.



External female genital organs. Position of arteries and nerves; bulb of vestibule in blue. (Schematic drawing.)

1 **Prepuce of clitoris**
2 Labium minus
3 **Vaginal orifice**
4 Deep transverse perineus muscle
5 Dorsal nerve of clitoris
6 Posterior labial nerves
7 Great adductor muscle
8 Perineal branches of pudendal nerve
9 **Anus** and **external anal sphincter muscle**
10 Inferior cluneal nerves
11 Mons pubis
12 Crus of clitoris with ischiocavernosus muscle
13 Bulb of vestibule
14 Superficial transverse perineus muscle
15 **Pudendal nerve** and **internal pudendal artery**
16 Inferior rectal nerves
17 Levator ani muscle
18 Gluteus maximus muscle
19 Anococcygeal ligament
20 External urethral orifice
21 Glans of clitoris



External female genital organs (inferior aspect). The clitoris has been dissected and slightly reflected to the right. The prepuce of clitoris has been divided to display the glans.

1 Position of pubic symphysis
2 Body of clitoris
3 Prepuce of clitoris
4 Adductor longus and gracilis muscles
5 External orifice of vagina and labium minus
6 Posterior labial nerve
7 Perineal body
8 Deep artery of clitoris and dorsal nerve of clitoris
9 Adductor brevis muscle
10 **Glans of clitoris**
11 Crus of clitoris and ischiocavernosus muscle
12 **Bulb of vestibule** and bulbospongiosus muscle
13 Anterior branch of obturator nerve
14 Labium minus
15 **Vaginal orifice**
16 Posterior labial nerves
17 Branches of pudendal nerve
18 External sphincter of anus
19 **Anus**
20 Bulb of vestibule (divided)
21 Dorsal artery of clitoris
22 Superficial transverse perineus muscle
23 Perineal branch of posterior femoral cutaneous nerve
24 Levator ani muscle
25 **Pudendal nerve** and **internal pudendal artery**
26 Inferior rectal nerves
27 Gluteus maximus muscle
28 Anococcygeal ligament



Urogenital diaphragm and external genital organs in the female (lateral inferior view). The bulb of vestibule has partly been removed, the left labium minus was cut away.



Coronal section through the pelvic cavity of the female (cf. MR-Scan on page 335).



Horizontal section through pelvic cavity at level of uterus (from below). The uterus is retroverted to the left.



Horizontal section through the pelvic cavity at level of the urethral sphincter and vagina (from below).

1 Ilium
2 Rectum
3 Rectouterine fold
4 **Ovary**
5 **Uterine tube**
6 **Urinary bladder**
7 **Urethra**
8 Labium minus
9 Rectouterine pouch of Douglas
10 **Uterus** (uterovesical pouch)
11 Ligament of the head of the femur
12 Head of femur
13 Vestibule of vagina
14 Labium majus
15 Anal cleft
16 Coccyx
17 Rectum
18 Myometrium of uterus
19 Uterine cavity
20 Obturator internus muscle
21 Iliopsoas muscle
22 Sartorius muscle
23 Sciatic nerve and gluteus maximus muscle
24 Uterine venous plexus
25 Broad ligament
26 Small intestine
27 Femoral artery and vein
28 Femoral nerve
29 Pyramidalis muscle
30 Rectum (anal canal)
31 Vagina
32 Urethral sphincter muscle (base of urinary bladder)
33 Pubic symphysis
34 Levator ani muscle
35 Obturator externus muscle
36 Mons pubis
37 Pectineus muscle



A Pectoral girdle
B Arm
C Forearm
D Wrist
E Palm of hand
F Finger

Bones

1 Scapula
2 Clavicle
3 Sternum
4 Humerus
5 Radius
6 Ulna
7 Carpal bones
8 Metacarpal bones
9 Phalanges

Joints

10 Sternoclavicular joint
11 Acromioclavicular joint
12 Shoulder joint
13 Elbow joint
14 Radiocarpal joint
15 Midcarpal joint
16 Carpometacarpal joint
17 Metacarpophalangeal joint
18 Interphalangeal joints of fingers
19 Carpometacarpal joint of thumb

Organization of shoulder girdle and upper limb (superior aspect). The two positions of the forearm essential to manual skills in the human, supination (right arm) and pronation (left arm) are shown.



Bones of shoulder girdle articulated with the thorax (superior aspect).



Skeleton of shoulder girdle and thorax (anterior aspect). The cartilaginous parts of the ribs appear dark brown.

Vertebral column

1 Atlas
2 Axis
3 3rd-7th cervical vertebrae
4 1st thoracic vertebra
5 12th thoracic vertebra
6 1st lumbar vertebra

Ribs

7 1st–3rd ribs } True ribs
8 4th–7th ribs
9 8th–10th ribs } False ribs
10 11th and 12th ribs (floating ribs)

Clavicle

11 Sternal end
12 Articular facet for sternum
13 Acromial end
14 Articular facet for acromion
15 Impression for costoclavicular ligament
16 Conoid tubercle
17 Trapezoid line
18 Site of acromioclavicular joint
19 Site of sternoclavicular joint

Scapula

20 Acromion
21 Coracoid process
22 Glenoid cavity
23 Costal surface

Sternum

24 Manubrium
25 Body
26 Xiphoid process



Right clavicle (superior aspect).



Right clavicle (inferior aspect).

Because of his upright posture, man's upper limb has developed a high degree of mobility. The shoulder girdle is to a great extent movable in the thorax and is connected with the trunk only by the sternoclavicular joint. A further characteristic of man's forearm is the capacity for rotation (i.e., pronation and supination).



Skeleton of shoulder girdle and thorax (posterior view).



Skeleton of shoulder girdle and thorax (lateral view).

Vertebral column

1 Atlas
2 Axis
3 3rd–6th cervical vertebrae
4 7th vertebra (vertebra prominens)
5 1st thoracic vertebra
6 6th thoracic vertebra
7 12th thoracic vertebra
8 1st lumbar vertebra

Clavicle

9 Sternal end
10 Acromial end
11 Site of acromioclavicular joint

Scapula

12 Acromion
13 Spine of scapula
14 Lateral angle
15 Posterior surface
16 Inferior angle
17 Coracoid process
18 Supraglenoid tubercle
19 Glenoid cavity
20 Infraglenoid tubercle
21 Lateral margin

Thorax

22 Body of sternum
23 Costal arch
24 Angle of ribs
25 Free ribs



Right scapula (posterior aspect).



Right scapula (anterior aspect costal surface).



Right scapula (lateral view).

Scapula

A Superior border
B Medial border
C Lateral border
D Superior angle
E Inferior angle
F Lateral angle

1 Acromion
2 Coracoid process
3 Scapular notch
4 Glenoid cavity
5 Infraglenoid tubercle
6 Supraspinous fossa
7 Spine
8 Infraspinous fossa
9 Articular facet for acromion
10 Neck
11 Supraglenoid tubercle
12 Costal (anterior) surface
13 Base of coracoid process



Bones of shoulder joint (posterior aspect).

1 1st rib
2 Position of costotransverse joints
3 4th–7th ribs
4 **Clavicle**
5 Position of acromioclavicular joint
6 Acromion
7 Scapular notch
8 Spine of scapula
9 Head of humerus
10 Glenoid cavity
11 Surgical neck of humerus
12 Posterior surface of **scapula**
13 Coracoid process
14 Infraglenoid tubercle
15 Greater tubercle of **humerus**
16 Anatomical neck of humerus



Bones of shoulder joint (anterior aspect).


1
2
4
5
6
7
8
9
10
11
12
13
3
14
15
16
17
18
19

Right humerus (anterior aspect).


2
13
14
6
16
18

Right humerus (medial aspect).


13
14
6
20
18
21
19
1
22
23
11

Right humerus (posterior aspect).

Humerus

1 Greater tubercle
2 Lesser tubercle
3 Crest of lesser tubercle
4 Crest of greater tubercle
5 Intertubercular sulcus
6 Surgical neck
7 Deltoid tuberosity
8 Anterolateral surface
9 Lateral supracondylar ridge
10 Radial fossa
11 Lateral epicondyle
12 Capitulum
13 Head
14 Anatomical neck
15 Anteromedial surface
16 Medial supracondylar ridge
17 Coronoid fossa
18 Medial epicondyle
19 Trochlea
20 Posterior surface
21 Groove for ulnar nerve
22 Groove for radial nerve
23 Olecranon fossa



Bones of right forearm, radius and ulna (anterior aspect).



Bones of right forearm, radius and ulna (posterior aspect).

Radius

1 Head
2 Articular circumference
3 Neck
4 Radial tuberosity
5 Shaft
6 Anterior surface
7 Styloid process
8 Articular surface
9 Posterior surface
10 Ulnar notch

Ulna

11 Trochlear notch
12 Coronoid process
13 Radial notch
14 Ulnar tuberosity
15 Head
16 Articular circumference
17 Styloid process
18 Posterior surface
19 Olecranon



Bones of right elbow joint (lateral aspect).

Articulations at the right elbow

20 Site of humeroulnar joint
21 Site of humeroradial joint
22 Site of proximal radioulnar joint

A Humerus
B Radius
C Ulna


1
2
3
4
5
6
7
9
10
11
12
13
14
17
18
19
20
21
22
23
15
24
16
25
26

Skeleton of right forearm and hand in pronation.


1
2
3
4
5
7
6
8
10
23
15
11
16
12
13
14
17
18
19
21
22
24
25
26

Skeleton of right forearm and hand in supination.

1 Humerus
2 Trochlea of humerus
3 Capitulum of humerus
4 Articular circumference of radius
5 Radial tuberosity
6 Anterior surface of **ulna**
7 Posterior surface of **radius**
8 Anterior surface of radius
9 Articular circumference of ulna
10 **Carpal bones**

11 **Metacarpal bones**
12 Proximal phalanges
13 Middle phalanges
14 Distal phalanges
15 Metacarpal bone of thumb
16 Proximal phalanx of thumb

Sites of joints

17 Humeroradial joint
18 Humeroulnar joint
19 Proximal radioulnar joint
20 Distal radioulnar joint
21 Radiocarpal joint
22 Midcarpal joint
23 Carpometacarpal joint of thumb
24 Carpometacarpal joints
25 Metacarpophalangeal joints
26 Interphalangeal joints of fingers


1
2
3
4
5
6
7
8
9
24
11
12
13
14
15
16
17
18
19
10
20
21
22
23

Skeleton of right wrist and hand (dorsal aspect).


1
2
3
6
9
10
11
12
13
14
15
16
18
19
21
20
22

Skeleton of right wrist and hand (medial aspect).

1 **Radius**
2 **Ulna**
3 Styloid process of ulna
4 Lunate bone
5 Triquetral bone
6 Capitate bone
7 Hamate bone
} **Carpal bones** (4–7)

8 Base of third metacarpal bone
9 **Metacarpal bones**
10 Head of metacarpal bone
11 Proximal phalanges of hand
12 Middle phalanges of hand
13 Distal phalanges of hand
14 Styloid process of radius

15 Scaphoid bone
16 The trapezium
17 Trapezoid bone
} **Carpal bones** (15–17)
18 Metacarpal bone of thumb
19 Proximal phalanx of thumb
20 Distal phalanx of thumb
21 Base of second proximal phalanx

22 Head of second proximal phalanx
23 Tuberosity of distal phalanx
24 Body of third metacarpal bone



1	Radius	
2	Styloid process of radius	
3	Scaphoid bone	**Carpal bones**
4	Capitate bone	
5	Trapezium	
6	Trapezoid bone	
7	First metacarpal bone	
8	Second to fourth metacarpal bones	
9	Proximal phalanx of thumb	
10	Distal phalanx of thumb	
11	Base of second proximal phalanx	
12	Proximal phalanges	
13	Head of second proximal phalanx	
14	Middle phalanges	
15	Distal phalanx	
16	Ulna	
17	Styloid process of ulna	
18	Lunate bone	**Carpal bones**
19	Pisiform bone	
20	Triquetral bone	
21	Hamate bone	
22	Hamulus or hook of hamate bone	
23	Base of third metacarpal bone	
24	Head of metacarpal bone	
25	Tuberosity of distal phalanx	

Skeleton of right wrist and hand (palmar aspect).

The human hand is one of the most admirable structures of the human body. The carpometacarpal joint of the thumb, a saddle joint, enjoys wide mobility, so that the thumb can get in contact with all other fingers, thus enabling the hand to become an instrument for grasping and psychologic expression. During evolution these newly developed functions appeared after the erect posture of the human body was achieved. An inevitable prerequisite for the development of human cultures is not only the differentiation of the brain but also the development of an organ capable of realizing its ideas: the human hand.



Right sternoclavicular joint (anterior aspect). On the right side the joint has been opened by a coronal section. Note the articular disk.

1 Sternocleidomastoid muscle, cervical branch of facial nerve and anterior jugular vein
2 External jugular vein and transverse cervical nerve (inferior branch)
3 Clavicle
4 **Sternoclavicular joint** (opened) with articular disk
5 Pectoralis major muscle
6 Omohyoid muscle and external jugular vein
7 Jugular venous arch and sternohyoid muscle
8 Sternoclavicular joint (not opened)
9 Acromial end of clavicle
10 **Acromioclavicular joint**
11 Acromion
12 Tendon of supraspinatus muscle (attached to the articular capsule)
13 Coraco-acromial ligament
14 Tendon of long head of biceps brachii muscle
15 Tendon of subscapularis muscle (attached to the articular capsule)
16 Intertubercular sulcus
17 Articular capsule of shoulder joint
18 Humerus
19 Trapezoid ligament
20 Coracoid process
21 Glenoid labrum
22 **Shoulder joint** (joint cavity)
23 Scapula
24 Supraspinatus muscle
25 Cartilage of glenoid cavity
26 Tendon of long head of triceps brachii muscle
27 Head of humerus (articular cartilage)
28 Epiphyseal line



Right shoulder joint. The anterior part of the articular capsule has been removed and the head of the humerus has been slightly rotated outward to show the cavity of the joint.



Coronal section of the right shoulder joint (anterior aspect).

1 Humerus
2 Lateral epicondyle of humerus
3 Articular capsule
4 Annular ligament of proximal radioulnar joint
5 Radius
6 Tendon of biceps brachii muscle
7 Medial epicondyle of humerus
8 Ulnar collateral ligament
9 Oblique cord
10 Ulna
11 Interosseous membrane
12 Radial fossa
13 Capitulum of humerus
14 Head of radius
15 Radial collateral ligament
16 Coronoid fossa
17 Trochlea of humerus
18 Coronoid process of ulna
19 Olecranon
20 Radial tuberosity



Ligaments of elbow joint (anterior aspect).



Elbow joint with ligaments (anterior aspect). Articular capsule has been removed to show the annular ligament.



Elbow joint with collateral ligaments (medial aspect).



Ligaments of hand and wrist (dorsal aspect).



Ligaments of hand and wrist (palmar aspect).

1 Ulna
2 Exostosis (pathological)
3 Head of ulna
4 **Ulnar carpal collateral ligament**
5 Deep intercarpal ligaments
6 Dorsal carpometacarpal ligaments
7 Dorsal metacarpal ligaments
8 Interosseous membrane
9 Radius
10 Styloid process of radius
11 **Dorsal radiocarpal ligament**
12 Radial collateral ligament
13 Articular capsule and dorsal intercarpal ligaments
14 **Palmar radiocarpal ligament**
15 Tendon of flexor carpi radialis muscle (cut)
16 Radiating carpal ligament
17 Palmar carpometacarpal ligaments
18 1st metacarpal bone
19 Palmar ulnocarpal ligament
20 Tendon of flexor carpi ulnaris muscle (cut)
21 **Pisohamate ligament**
22 **Pisometacarpal ligament**
23 Palmar metacarpal ligaments
24 5th metacarpal bone

1 Radius
2 Styloid process of radius
3 Palmar radiocarpal ligament
4 Tendon of flexor carpi radialis muscle (cut)
5 Radiating carpal ligament
6 Articular capsule of **carpometacarpal joint of thumb**
7 Articular capsule of **metacarpophalangeal joint of thumb**
8 Palmar ligaments and articular capsule of metacarpophalangeal joints
9 Palmar ligaments and articular capsule of interphalangeal joints
10 Articular capsule
11 Interosseous membrane
12 Ulna
13 **Distal radioulnar joint**
14 Styloid process of ulna
15 Palmar ulnocarpal ligament
16 **Pisiform bone with tendon of flexor carpi ulnaris muscle**
17 Pisometacarpal ligament
18 Pisohamate ligament
19 Metacarpal bone
20 Deep transverse metacarpal ligament
21 Tendons of extensor muscles and articular capsule
22 Collateral ligament of **interphalangeal joint**
23 Collateral ligaments of **metacarpophalangeal joints**
24 Second metacarpal bone



Ligaments of right forearm, hand and fingers (palmar aspect). The arrow indicates the location of the carpal tunnel.



Ligaments of fingers (lateral aspect).



1 Descending fibers of **trapezius muscle**
2 Spinous processes of thoracic vertebrae
3 Ascending fibers of trapezius muscle
4 Rhomboid major muscle
5 Inferior angle of scapula
6 **Latissimus dorsi muscle**
7 Transverse fibers of trapezius muscle
8 Spine of scapula
9 Posterior fibers of **deltoid muscle**
10 Infraspinatus muscle and infraspinous fascia
11 Teres minor muscle and fascia
12 Long head of triceps brachii muscle
13 **Teres major muscle**
14 Lateral head of triceps brachii muscle
15 Medial head of triceps brachii muscle
16 Medial intermuscular septum
17 Ulnar nerve
18 Olecranon

Muscles of shoulder and arm, superficial layer (dorsal aspect).



1 Trapezius muscle (reflected)
2 Levator scapulae muscle
3 Supraspinatus muscle
4 Rhomboid minor muscle
5 Medial border of scapula
6 **Rhomboid major muscle**
7 **Infraspinatus muscle**
8 **Teres major muscle**
9 Inferior angle of scapula
10 Cut edge of trapezius muscle
11 Intrinsic muscles of back with fascia
12 **Latissimus dorsi muscle**
13 Acromion
14 Spine of scapula
15 **Deltoid muscle**
16 Teres minor
17 Long head of triceps brachii muscle
18 Lateral head of triceps brachii muscle
19 Medial head of triceps brachii muscle
20 Medial intermuscular septum
21 Tendon of triceps brachii muscle

Muscles of shoulder and arm, deeper layer (right side, dorsal aspect). The trapezius has been cut near its origin at the vertebral column and reflected upward.



1 **Splenius capitis muscle**
2 Sternocleidomastoideus muscle
3 Trapezius muscle (reflected)
4 **Lateral supraclavicular nerves**
5 Clavicle
6 Levator scapulae muscle
7 Supraspinatus muscle
8 Spine of scapula
9 Deltoid muscle (reflected)
10 Rhomboid minor muscle
11 **Rhomboid major muscle**
12 **Axillary nerve and posterior circumflex humeral artery**
13 **Infraspinatus muscle**
14 **Teres minor muscle**
15 Long head of triceps brachii muscle
16 **Teres major muscle**
17 Inferior angle of scapula
18 Triceps brachii muscle
19 **Latissimus dorsi muscle**

Muscles of shoulder and arm, deeper layer, right side (dorsal aspect). The trapezius and deltoid muscles have been divided and reflected.



Shoulder muscles, schematic diagram illustrating the course of the main muscles of the dorsal aspect of the shoulder.

1 Rhomboid minor muscle (red)
2 Rhomboid major muscle (red)
3 Levator scapulae muscle (red)
4 Supraspinatus muscle (blue)
5 Deltoid muscle (red)
6 Infraspinatus muscle (blue)
7 Teres minor muscle (red)
8 Teres major muscle (red)



Muscles of shoulder and arm, superficial layer (ventral aspect).

1 Trapezius muscle
2 Acromion
3 Deltopectoral triangle
4 Clavicular part of deltoid muscle (anterior fibers)
5 Acromial part of deltoid muscle (central fibers)
6 Clavicular part of pectoralis major muscle
7 Sternocostal part of pectoralis major muscle
8 Short head of biceps brachii muscle
9 Long head of biceps brachii muscle
10 Abdominal part of pectoralis major muscle
11 Brachialis muscle
12 Serratus anterior muscle
13 External abdominal oblique muscle
14 Sternocleidomastoid muscle
15 Infrahyoid muscles
16 Clavicle
17 Manubrium sterni
18 Body of sternum
19 Xiphoid process
20 Anterior layer of sheath of rectus abdominis muscle



Arrangement of pectoral and shoulder muscles (ventral aspect).
(Schematic drawing.)

1 Subclavius muscle (blue)
2 Pectoralis minor muscle (blue)
3 Pectoralis major muscle (red)
4 Subscapularis muscle (red)
5 Coracobrachialis muscle (light-blue)
6 Serratus anterior muscle (green)



Muscles of shoulder and arm, deep layer (ventral aspect).



1 Acromion
2 Clavicular part of deltoid muscle
3 Pectoralis major muscle (reflected)
4 Coracobrachialis muscle
5 Short head of biceps brachii muscle
6 Deltoid muscle (insertion on humerus)
7 Long head of biceps brachii muscle
8 Brachialis muscle
9 Sternocleidomastoid muscle
10 Clavicle
11 Subclavius muscle
12 Pectoralis minor muscle
13 Sternum
14 3rd rib
15 Pectoralis major muscle
16 Platysma muscle
17 Pectoralis major muscle forming the anterior axillary fold
18 Anterior cutaneous branches of intercostal nerves
19 Lateral cutaneous branches of intercostal nerves
20 Rectus abdominis muscle
21 Subscapularis muscle
22 **Latissimus dorsi muscle** forming the posterior axillary fold
23 **Serratus anterior muscle** forming the medial wall of the axilla
24 External abdominal oblique muscle

Axillary fossa and serratus anterior muscle
(left side, lateral aspect).


1
2
3
4
5
6
7
8
9
10
11

Muscles of right arm (lateral aspect).


12
6
7
13
14
8
15
9
16
10
17
18
19
20
3
21
22
23
24
25

Muscles of right arm (ventral aspect). The arm with the scapula and attached muscles has been removed from the trunk.


34
8
9
3
10
32
A
33

Diagram illustrating the position of the **flexor and extensor muscles of the arm** and their effect on the elbow joint. A = axis; arrows = direction of movements; red = flexion; black = extension.



Flexor muscles of right arm (ventral aspect). Part of the biceps brachii muscle has been removed. Arrow: tendon of long head of biceps brachii muscle.



Position and course of flexors of arm. (Schematic drawing.)

1 Subscapularis muscle (red)
2 Coracobrachialis muscle (blue)
3 Biceps brachii muscle (red)
4 Brachialis muscle (blue)

1 Acromial part of deltoid muscle (central fibers)
2 Scapular part of deltoid muscle (posterior fibers)
3 Triceps brachii muscle
4 Tendon of triceps brachii muscle
5 Olecranon
6 Clavicular part of deltoid muscle (anterior fibers)
7 Deltopectoral groove
8 **Biceps brachii muscle**
9 **Brachialis muscle**
10 **Brachioradialis muscle**
11 Extensor carpi radialis longus muscle
12 Clavicle (divided)
13 Pectoralis major muscle
14 Medial intermuscular septum with vessels and nerves
15 Lateral intermuscular septum
16 Tendon of biceps brachii muscle
17 Bicipital aponeurosis
18 Axillary artery
19 Rhomboid major muscle
20 **Subscapularis muscle**
21 Latissimus dorsi muscle (divided)
22 Medial intermuscular septum
23 Medial epicondyle of humerus
24 Brachial artery and median nerve
25 Pronator teres muscle
26 Tendon of short head of biceps brachii muscle
27 Coracobrachialis muscle
28 Distal part of biceps brachii muscle
29 Teres major muscle
30 Long head of triceps brachii muscle
31 Medial head of triceps brachii muscle
32 Radius
33 Ulna
34 Scapula


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
18
21
31
22
23
24
25

Forearm muscles, superficial layer (ventral aspect).


1
26
2
3
4
27
44
9
11
28
13
29
15
16
17
19
18
30
21
31
23
32
33
34
25

Forearm muscles, superficial layer (ventral aspect). The palmaris longus and flexor carpi ulnaris muscles have been removed.

1 Biceps brachii muscle
2 Bicipital aponeurosis
3 **Brachioradialis muscle**
4 **Flexor carpi radialis muscle**
5 Radial artery
6 **Flexor digitorum superficialis muscle**
7 Median nerve
8 Antebrachial fascia and tendon of palmaris longus muscle
9 Tendon of abductor pollicis longus muscle
10 Tendon of extensor pollicis brevis muscle
11 Abductor pollicis brevis muscle
12 **Palmar aponeurosis**
13 Superficial head of flexor pollicis brevis muscle
14 Tendon of flexor pollicis longus muscle
15 Medial intermuscular septum
16 Medial epicondyle of humerus
17 Humeral head of pronator teres muscle
18 **Palmaris longus muscle**
19 **Flexor carpi ulnaris muscle**
20 **Ulnar artery**
21 Tendon of flexor carpi ulnaris muscle
22 Palmaris brevis muscle



Forearm muscles, middle layer (ventral aspect). The palmaris longus, flexor carpi radialis and ulnaris muscles have been partly removed. The flexor retinaculum has been divided.



Position of flexors of fingers and hand. (Schematic drawing.)

A Deep layer
B Superficial layer
△
1 Flexor pollicis longus muscle (blue)
2 Flexor digitorum profundus muscle (red)
3 Pronator teres muscle (red)
4 Flexor carpi radialis muscle (red)
5 Flexor carpi ulnaris muscle (red)
6 Flexor digitorum superficialis muscle (blue)

23 Abductor digiti minimi muscle
24 Transverse fasciculi of palmar aponeurosis
25 Digital fibrous sheaths of tendons of flexor digitorum muscle
26 Brachialis muscle
27 Flexor pollicis longus muscle
28 Carpal tunnel (canalis carpi, probe)
29 Triceps brachii muscle
30 Flexor digitorum superficialis muscle
31 Pisiform bone
32 Opponens digiti minimi muscle
33 Flexor digiti minimi brevis muscle
34 Tendons of flexor digitorum superficialis muscle
35 Supinator muscle
36 Extensor carpi radialis brevis muscle
37 **Flexor pollicis longus muscle**
38 Tendon of flexor carpi radialis muscle
39 **Pronator teres muscle** (insertion of radius)
40 **Flexor digitorum profundus muscle**
41 **Lumbrical muscles**
42 Tendons of flexor digitorum profundus muscle
43 Tendons of flexor digitorum profundus muscle having passed through the divided tendons of the flexor digitorum superficialis muscle
44 Flexor retinaculum



Muscles of the forearm, deep layer (ventral aspect). All flexors have been removed to display the pronator quadratus and pronator teres muscles together with the interosseous membrane. Forearm in supination.

1. Biceps brachii muscle
2. Brachialis muscle
3. **Pronator teres muscle**
4. Brachioradialis muscle
5. **Radius**
6. Tendon of flexor carpi radialis muscle
7. Tendon of abductor pollicis longus muscle
8. Opponens pollicis muscle
9. Adductor pollicis muscle
10. Tendon of flexor pollicis longus muscle
11. Triceps brachii muscle
12. Medial intermuscular septum
13. Medial epicondyle of humerus
14. Common flexor mass (divided)
15. **Ulna**
16. **Interosseous membrane**
17. **Pronator quadratus muscle**
18. Tendon of flexor carpi ulnaris muscle
19. Pisiform bone
20. Abductor digiti minimi muscle
21. Flexor digiti minimi brevis muscle
22. Tendons of flexor digitorum profundus muscle
23. Tendons of flexor digitorum superficialis muscle
24. Flexor retinaculum
25. Hypothenar muscles
26. Thenar muscles
27. Common synovial sheath of flexor tendons
28. Synovial sheath of tendon of flexor pollicis longus muscle
29. Digital synovial sheaths of flexor tendons



Synovial sheaths of flexor tendons (palmar aspect of right hand). (Semischematic drawing.)

1 Humerus
2 Lateral epicondyle of humerus
3 Articular capsule
4 Position of capitulum of humerus
5 Deep branch of radial nerve
6 **Supinator muscle**
7 Entrance of deep branch of radial nerve to extensor muscles
8 Radius and insertion of pronator teres muscle
9 Interosseous membrane
10 Median nerve
11 Triceps brachii muscle
12 Trochlea of humerus
13 Tendon of biceps brachii muscle
14 Brachial artery
15 **Pronator teres muscle**
16 Tendon of pronator teres muscle
17 Ulna
18 **Pronator quadratus muscle**
19 Tendon of flexor carpi radialis muscle
20 Thenar muscles
21 Synovial sheath of tendon of flexor pollicis longus muscle
22 Fibrous sheath of flexor tendons
23 **Digital synovial sheath of flexor tendons**
24 Flexor digitorum superficialis muscle
25 Tendon of flexor carpi ulnaris muscle
26 **Common synovial sheath of flexor tendons**
27 Position of pisiform bone
28 Flexor retinaculum
29 Hypothenar muscles



Right supinator and elbow joint (anterior aspect). Forearm in pronation.



Synovial sheaths of flexor muscles (palmar aspect of right hand). Blue PVA-solution has been injected into the sheaths.



A Axis of flexion and extension
B Axis of rotation
Arrows:
S Supination
P Pronation

Diagram illustrating the two **axes of the elbow joint.**



Muscles of thumb and index finger (medial aspect). The tendons of the extensor muscles of the thumb and the insertion of the flexor tendons of the index finger are displayed.



Muscles of hand (palmar aspect). The tendons of the flexor muscles and parts of the thumb muscles have been removed. The carpal tunnel has been opened.

1 Tendons of extensor pollicis brevis and abductor pollicis longus muscle
2 Extensor retinaculum
3 Tendon of extensor pollicis longus muscle
4 Tendons of extensor carpi radialis longus and brevis muscles
5 First dorsal interosseous muscle
6 Tendon of extensor digitorum muscle for index finger
7 Location of metacarpophalangeal joint
8 Tendon of lumbrical muscle
9 Extensor expansion of index finger
10 Tendon of flexor carpi radialis muscle (cut)
11 **Anatomical snuffbox**
12 Tendon of abductor pollicis longus muscle
13 Tendon of extensor pollicis brevis muscle
14 Tendon of abductor pollicis brevis muscle
15 Extensor expansion of extensor of thumb
16 Vinculum longum
17 Tendons of flexor digitorum superficialis muscle dividing to allow passage of deep tendons
18 Vincula of flexor tendons
19 Tendon of flexor digitorum profundus muscle
20 Vinculum breve
21 Radial carpal eminence (cut edge of flexor retinaculum)
22 Opponens pollicis muscle
23 Deep head of flexor pollicis brevis muscle
24 Abductor pollicis brevis muscle (cut)
25 Superficial head of flexor pollicis brevis muscle (cut)
26 Oblique head of adductor pollicis muscle
27 Transverse head of adductor pollicis muscle
28 Tendon of flexor pollicis longus muscle (cut)
29 Lumbrical muscles (cut)
30 First dorsal interosseous muscle
31 **Position of carpal tunnel**
32 Tendon of flexor carpi ulnaris muscle
33 Location of pisiform bone
34 Hook of hamate bone
35 Abductor digiti minimi muscle
36 Flexor digiti minimi brevis muscle
37 Opponens digiti minimi muscle
38 2nd palmar interosseous muscle
39 3rd palmar interosseous muscle
40 4th dorsal interosseous muscle
41 3rd dorsal interosseous muscle
42 Tendon of flexor digitorum profundus muscle (cut)
43 Tendons of flexor digitorum superficialis muscle (cut)
44 Fibrous flexor sheaths



Muscles of right hand, deep layer (palmar aspect). The thenar and hypothenar muscles have been removed to display the interosseous muscles.



Actions of interosseous muscles in abduction and adduction of fingers (palmar aspect, schematic drawing). Arrow: carpal tunnel.
Red = **abduction**
(dorsal interosseous muscles, abductor digiti minimi and abductor pollicis brevis muscles).
Black = **adduction**
(palmar interosseous muscles, adductor pollicis muscle).



Transverse section through the right hand, showing the carpal tunnel (canalis carpi).

1 Pronator quadratus muscle
2 Tendon of flexor carpi radialis muscle
3 Abductor pollicis brevis muscle (divided)
4 Adductor pollicis muscle (divided)
5 Tendon of flexor pollicis longus muscle
6 Lumbrical muscles (cut)
7 Tendon of flexor carpi ulnaris muscle
8 Pisiform bone
9 Abductor digiti minimi muscle (divided)
10 **Dorsal interosseous muscles**
11 **Palmar interosseous muscles**
12 Radius
13 Ulna
14 **Flexor retinaculum**
15 Tendons of flexor digitorum profundus muscle
16 Tendons of flexor digitorum superficialis muscle
17 Capitate bone
18 Trapezium bone and trapezoid bone
19 Radial artery
20 Tendon of flexor muscles
21 First metacarpal bone
22 **Median nerve**
23 Thenar muscles
24 Hamate bone
25 Hypothenar muscles
26 Ulnar artery and nerve
27 **Carpal tunnel** (canalis carpi)



Extensor muscles of forearm and hand, superficial layer (dorsal aspect). Tunnels for extensor tendons indicated by probes.



Synovial sheaths of extensor tendons. The sheaths have been injected with blue gelatin.



Synovial sheaths of extensor tendons on the back of right wrist (indicated in blue). Notice the six tunnels for the passage of the extensor tendons beneath the extensor retinaculum. (Semischematic drawing.)

1 Lateral intermuscular septum
2 Tendon of triceps brachii muscle
3 Lateral epicondyle of humerus
4 Olecranon
5 Anconeus
6 Extensor carpi ulnaris muscle
7 Extensor digitorum muscle
8 Extensor digiti minimi muscle
9 Extensor retinaculum
10 Tendons of extensor digiti minimi muscle
11 Tendons of extensor digitorum muscle
12 Intertendinous connections
13 Brachioradialis muscle
14 Extensor carpi radialis longus muscle
15 Extensor carpi radialis brevis muscle
16 Abductor pollicis longus muscle
17 Extensor pollicis brevis muscle
18 Tendon of extensor pollicis longus muscle
19 Tendons of both extensor carpi radialis longus and extensor carpi radialis brevis muscles
20 Tendon of extensor indicis muscle
21 1st tunnel: Abductor pollicis longus muscle
Extensor pollicis brevis muscle
22 2nd tunnel: Extensor carpi radialis longus and brevis muscles
23 3rd tunnel: Extensor pollicis longus muscle
24 4th tunnel: Extensor digitorum muscle
Extensor indicis muscle
25 5th tunnel: Extensor digiti minimi muscle
26 6th tunnel: Extensor carpi ulnaris muscle



Extensor muscles of forearm and hand, deep layer (dorsal aspect).

1 Triceps brachii muscle
2 Lateral intermuscular septum
3 Lateral epicondyle of humerus
4 Anconeus muscle
5 Extensor digitorum and extensor digiti minimi muscles (cut)
6 Supinator muscle
7 Extensor carpi ulnaris muscle
8 Extensor retinaculum
9 3rd and 4th dorsal interosseous muscles
10 Tendons of extensor digitorum muscle (cut)
11 Biceps brachii muscle
12 Brachialis muscle
13 Brachioradialis muscle
14 Extensor carpi radialis longus muscle
15 Extensor carpi radialis brevis muscle
16 Abductor pollicis longus muscle
17 Extensor pollicis longus muscle
18 Extensor pollicis brevis muscle
19 Extensor indicis muscle
20 Tendons of the extensor carpi radialis longus and extensor carpi radialis brevis muscles
21 1st dorsal interosseous muscle



Position of extensor muscles of forearm and hand. (Semischematic drawing.)

A Extensors of thumb	B Extensors of fingers and hand
1 Abductor pollicis longus muscle (red)	5 Extensor carpi ulnaris muscle (blue)
2 Extensor pollicis brevis muscle (blue)	6 Extensor digitorum muscle (red)
3 Extensor pollicis longus muscle (red)	7 Extensor carpi radialis brevis muscle (blue)
4 Extensor indicis muscle (blue)	8 Extensor carpi radialis longus muscle (blue)



Main branches of right subclavian and axillary arteries (anterior aspect). Pectoralis muscles have been reflected, clavicle and anterior wall of thorax removed and right lung divided. Left lung with pleura and thyroid gland have been reflected laterally to display aortic arch and common carotid artery with their branches.

1 Pectoralis minor muscle (reflected)
2 Anterior circumflex humeral artery
3 Musculocutaneous nerve (divided)
4 **Axillary artery**
5 Posterior circumflex humeral artery
6 **Profunda brachii artery**
7 Median nerve (var.)
8 **Brachial artery**
9 Biceps brachii muscle
10 Thoracoacromial artery
11 Suprascapular artery
12 Descending scapular artery
13 Brachial plexus (middle trunk)
14 Transverse cervical artery
15 Scalenus anterior muscle and phrenic nerve
16 Right internal carotid artery
17 Right external carotid artery
18 Carotid sinus
19 Superior thyroid artery
20 Right common carotid artery
21 Ascending cervical artery
22 Thyroid gland
23 Inferior thyroid artery
24 Internal thoracic artery
25 Right subclavian artery
26 Brachiocephalic trunk
27 Left brachiocephalic vein (divided)
28 Left vagus nerve
29 Superior vena cava (divided)
30 **Ascending aorta**
31 Median nerve (divided)
32 Phrenic nerve
33 Right lung (divided) and pulmonary pleura
34 Thoracodorsal artery
35 Subscapular artery
36 Lateral mammary branches (variant)
37 Lateral thoracic artery
38 **Thyrocervical trunk**
39 Superior thoracic artery
40 Superior ulnar collateral artery
41 Inferior ulnar collateral artery
42 Middle collateral artery
43 Radial collateral artery
44 Radial recurrent artery
45 **Radial artery**
46 Anterior and posterior interosseous arteries
47 Princeps pollicis artery
48 **Deep palmar arch**
49 Common palmar digital arteries
50 Ulnar recurrent artery
51 Recurrent interosseous artery
52 Common interosseous artery
53 **Ulnar artery**
54 **Superficial palmar arch**
55 Median nerve and brachial artery
56 Biceps brachii muscle
57 Ulnar nerve
58 Flexor pollicis longus muscle
59 Palmar digital arteries
60 Anterior interosseous artery
61 Flexor carpi ulnaris muscle
62 Superficial palmar branch of radial artery


55
56
41
53
50
45
57
53
60
58
61
53
45
7
62
54
49
59

Dissection of the arteries of forearm and hand. The superficial flexor muscles have been removed, the carpal tunnel opened and the flexor retinaculum cut. The arteries have been filled with colored resin.


12
39
10
4
35
5
2
6
8
42
43
44
45
46
62
47
49
38
25
24
37
40
41
50
52
51
53
48
54

Arteries of the upper limb. (Schematic drawing.)



Veins of the head, neck and upper extremity and their connection with the heart (anterior-lateral aspect; anterior thoracic wall) has been opened).



Superficial veins of upper limb. (Semischematic drawing.)

1 Superficial temporal artery and vein
2 Occipital vein
3 Parotid gland
4 Great auricular nerve and sternocleidomastoid muscle
5 External jugular vein
6 **Internal jugular vein and common carotid artery**
7 Deltoid muscle
8 **Axillary vein**
9 Right **cephalic vein** within the deltopectoral groove
10 Right lung (middle lobe)
11 Serratus anterior muscle and lateral thoracic vein
12 Cephalic vein on forearm
13 **Venous network on dorsum of hand**
14 Dorsal metacarpal veins
15 **Facial artery and vein**
16 Submandibular gland
17 Anterior jugular vein, hyoid bone and omohyoid muscle
18 Jugular venous arch and thyroid gland
19 Right and left brachiocephalic veins
20 Retrosternal body (remnant of thymus gland)
21 Internal thoracic artery and vein
22 Heart with pericardium
23 Right venous angle
24 **Brachial vein**
25 Basilic vein
26 Median cubital vein
27 Digital veins



Main branches of radial nerve. (Schematic drawing.) Posterior divisions of trunks and posterior cord and its branches are indicated in green.



Main branches of musculocutaneous, median and ulnar nerves. (Schematic drawing.) Anterior divisions of the trunks and all the components arising from them are indicated in yellow.

1 Brachial plexus
2 Lateral cord of brachial plexus
3 Posterior cord of brachial plexus
4 Medial cord of brachial plexus
5 **Axillary nerve**
6 **Radial nerve**
7 Posterior cutaneous nerve of arm
8 Lower lateral cutaneous nerve of arm
9 Posterior cutaneous nerve of forearm
10 Superficial branch of radial nerve
11 Deep branch of radial nerve
12 Dorsal digital nerves

13 Roots of median nerve
14 Musculocutaneous nerve
15 **Median nerve**
16 **Ulnar nerve**
17 Medial cutaneous nerves of arm and forearm
18 Lateral cutaneous nerve of forearm
19 Anterior interosseous nerve
20 Palmar branch of median nerve
21 Dorsal branch of ulnar nerve
22 Deep branch of ulnar nerve
23 Common palmar digital nerves of median nerve
24 Superficial branch of ulnar nerve



Cutaneous nerves of right upper limb (ventral aspect).
(Semischematic drawing.)



Cutaneous nerves of the upper limb (dorsal aspect).
(Semischematic drawing.)

1 Medial supraclavicular nerve
2 Intermediate supraclavicular nerve
3 Upper lateral cutaneous nerve of arm
4 Terminal branches of intercostobrachial nerves
5 Lower lateral cutaneous nerve of arm
6 Lateral cutaneous nerve of forearm
7 Terminal branch of superficial branch of radial nerve
8 Palmar digital nerve of thumb (branch of median nerve)
9 Palmar digital branches of median nerve
10 Anterior cutaneous branches of intercostal nerves
11 Lateral cutaneous branches of intercostal nerves
12 Medial cutaneous nerve of forearm

13 Palmar cutaneous branch of ulnar nerve
14 Palmar branch of median nerve
15 Palmar digital branches of ulnar nerve
16 Cutaneous branches of dorsal rami of spinal nerves
17 Dorsal branch of ulnar nerve
18 Dorsal digital nerves
19 Posterior supraclavicular nerve
20 Posterior cutaneous nerve of arm
21 Posterior cutaneous nerve of forearm
22 Superficial branch
23 Dorsal digital branches
} from radial nerve



Dorsal region of shoulder, superficial layer. Note the segmental arrangement of the cutaneous nerves of the back.



Shoulder and arm (dorsal aspect). Dissection of the quadrangular and triangular spaces of the axillary region.

1 Trapezius muscle
2 Dorsal branches of posterior intercostal artery and vein (medial cutaneous branches)
3 Medial branches of dorsal rami of spinal nerves
4 Rhomboid major muscle
5 Lateral branches of dorsal rami of spinal nerves
6 Latissimus dorsi muscle
7 Posterior supraclavicular nerves
8 Spine of scapula
9 Deltoid muscle
10 Infraspinatus muscle
11 Teres minor muscle
12 **Triangular space** with circumflex scapular artery and vein
13 Upper lateral cutaneous nerve of arm with artery
14 Teres major muscle
15 Terminal branches of intercostobrachial nerve
16 Medial cutaneous nerve of arm
17 Tendon of triceps brachii muscle
18 Lateral cutaneous branches of intercostal nerves
19 Medial cutaneous nerve of forearm
20 Long head of triceps brachii muscle
21 **Quadrangular space** with axillary nerve and posterior humeral circumflex artery
22 Anastomosis between profunda brachii artery and posterior humeral circumflex artery
23 Course of radial nerve and profunda brachii artery
24 Lateral head of triceps brachii muscle
25 Course of descending scapular artery and dorsal scapular nerve
26 Course of suprascapular nerve, artery and vein



Course of vessels and nerves to shoulder and upper limb. (Schematic drawing.)



Scapular region, arm and shoulder, deep layer (dorsal aspect). Part of deltoid muscle has been cut and reflected to display the quadrangular and triangular spaces of the axillary region.



Scapular region and posterior brachial region; arm and shoulder, deep layer (dorsal aspect). The lateral head of the triceps brachii muscle has been cut to display the radial nerve and accompanying vessels.

1	Trapezius muscle
2	Spine of scapula
3	Infraspinatus muscle
4	Teres minor muscle
5	**Triangular space** containing circumflex scapular artery and vein
6	Teres major muscle
7	Latissimus dorsi muscle
8	Deltoid muscle (cut and reflected)
9	**Quadrangular space** containing axillary nerve and posterior circumflex humeral artery and vein
10	Long head of triceps brachii muscle
11	Cutaneous branch of axillary nerve
12	Lateral head of triceps brachii muscle
13	Terminal branches of intercostobrachial nerve
14	Lateral cutaneous branches of intercostal nerves
15	Medial cutaneous nerve of arm
16	Medial cutaneous nerve of forearm
17	Upper lateral cutaneous nerve of arm
18	Anastomosis between profunda brachii artery and posterior humeral circumflex artery
19	Humerus
20	**Profunda brachii artery**
21	**Radial nerve**
22	Radial collateral artery
23	Middle collateral artery
24	Lower lateral cutaneous nerve of arm
25	Posterior cutaneous nerve of forearm
26	Tendon of triceps brachii muscle



Dorsal regions of neck and shoulder (dorsal aspect). Left side: superficial layer. Right side: trapezius and latissimus dorsi muscles have been removed. Dissection of dorsal branches of spinal nerves.

1 **Greater occipital nerve**
2 Ligamentum nuchae
3 Splenius capitis muscle
4 Sternocleidomastoid muscle
5 Lesser occipital nerve
6 Splenius cervicis muscle
7 Descending and transverse fibers of trapezius muscle
8 **Medial cutaneous branches of dorsal rami of spinal nerves**
9 Ascending fibers of trapezius muscle
10 Latissimus dorsi muscle
11 Cutaneous branch of third occipital nerve
12 Great auricular nerve
13 Accessory nerve (n. XI)
14 Posterior supraclavicular nerve and levator scapulae muscle
15 Branches of suprascapular artery
16 Deltoid muscle
17 Rhomboid major muscle
18 Infraspinatus muscle
19 Teres minor muscle
20 Upper lateral cutaneous nerve of arm (branch of axillary nerve)
21 Teres major muscle
22 Medial margin of scapula
23 Long head of triceps muscle
24 Posterior cutaneous nerve of arm (branch of radial nerve)
25 Latissimus dorsi muscle (divided)
26 Ulnar nerve and brachial artery
27 **Lateral cutaneous branches of dorsal rami of spinal nerves** and iliocostalis thoracis muscle
28 External intercostal muscle and seventh rib
29 Serratus posterior inferior muscle

1	Clavicle
2	Deltoid muscle
3	**Suprascapular artery**
4	Suprascapular nerve
5	Superior transverse scapular ligament
6	Teres minor muscle
7	Axillary nerve and posterior circumflex humeral artery
8	Long head of triceps muscle
9	**Circumflex scapular artery**
10	Teres major muscle
11	Greater occipital nerve
12	Lesser occipital nerve
13	Great auricular nerve
14	Splenius capitis muscle
15	Accessory nerve (n. XI)
16	Third occipital nerve and levator scapulae muscle
17	Serratus posterior superior muscle
18	Spine of scapula
19	Descending scapular artery and dorsal scapular nerve
20	Rhomboid major muscle
21	Infraspinatus muscle and medial margin of scapula
22	Radial nerve and profunda brachii artery
23	Thoracodorsal artery
24	Thyrocervical trunk
25	Roots of brachial plexus



Dorsal region of shoulder; deepest layer. Rhomboid and scapular muscles fenestrated; posterior part of deltoid muscle reflected.



Collateral circulation of shoulder. Anastomosis of suprascapular and circumflex scapular arteries. (Semischematic drawing.)



Scapular region, arm and shoulder (dorsal aspect). Arteries of scapular region are injected. Trapezius, deltoid and infraspinatus muscles are partially removed or reflected.

1	Sternocleidomastoid muscle
2	Lesser occipital nerve
3	Splenius capitis muscle and third occipital nerve
4	**Accessory nerve** (N. XI)
5	Splenius cervicis muscle and transverse cervical artery (deep branch)
6	Levator of scapula muscle
7	**Transverse cervical artery** (superficial branch)
8	Spine of scapula and serratus posterior superior muscle
9	Rhomboid major muscle
10	Trapezius muscle
11	Latissimus dorsi muscle
12	Facial artery
13	Acromion
14	Deltoid muscle
15	**Suprascapular artery** and supraspinatus muscle (reflected)
16	**Axillary nerve,** posterior circumflex humeral artery and lateral head of triceps, brachii muscle
17	Teres minor muscle
18	Long head of triceps brachii muscle
19	**Circumflex scapular artery** and teres major
20	Infraspinatus muscle



Right shoulder and thoracic wall, superficial layer (anterior aspect). Dissection of the cutaneous nerves and veins.



Superficial veins of right arm have been injected with blue gelatin.

1 Trapezius muscle
2 Posterior supraclavicular nerve
3 Middle supraclavicular nerve
4 Deltopectoral triangle
5 Deltoid muscle
6 Cephalic vein within the deltopectoral groove
7 Upper lateral cutaneous nerve of arm (branch of axillary nerve)
8 Latissimus dorsi muscle
9 **Cephalic vein**
10 Biceps brachii muscle
11 Triceps brachii muscle
12 Lateral cutaneous branches of intercostal nerves
13 Transverse cervical nerve and external jugular vein
14 Sternocleidomastoid muscle
15 **Anterior jugular vein**
16 Anterior supraclavicular nerve
17 Clavicle
18 Clavicular part of pectoralis major muscle
19 Sternocostal part of pectoralis major muscle
20 Perforating branch of internal thoracic artery
21 **Anterior cutaneous branches of intercostal nerves**
22 Abdominal part of pectoralis major muscle
23 Accessory cephalic vein
24 **Basilic vein**
25 **Median cubital vein**
26 Median vein of forearm
27 Cephalic vein in the forearm



Right deltopectoral triangle, infraclavicular region (anterior aspect). The pectoralis major muscle has been cut and reflected.



Thoracic wall and shoulder, deep layer. **Right axillary region** (anterior aspect). The pectoralis major muscle has been cut and partly removed.

1 Accessory nerve
2 Trapezius muscle
3 Pectoralis major muscle (clavicular part)
4 Acromial branch of thoracoacromial artery
5 Pectoralis major muscle
6 **Lateral pectoral nerves**
7 Abdominal part of pectoralis major muscle
8 External jugular vein
9 Cutaneous branches of cervical plexus
10 Sternocleidomastoid muscle
11 Clavicle
12 Clavipectoral fascia
13 **Cephalic vein**
14 Subclavius muscle
15 Clavicular branch of thoracoacromial artery
16 **Subclavian vein**
17 **Thoracoacromial artery**
18 Pectoral branch of thoracoacromial artery
19 Medial pectoral nerve
20 2nd rib
21 Pectoralis minor muscle
22 3rd rib
23 Deltoid muscle
24 Pectoralis major muscle (reflected), **brachial artery and median nerve**
25 Short head of biceps brachii muscle
26 Thoracodorsal artery and nerve
27 Medial cutaneous nerve of arm
28 Intercostobrachial nerve (T_2)
29 Long head of biceps brachii muscle
30 Medial cutaneous nerve of forearm
31 Latissimus dorsi muscle
32 Lateral cutaneous branches of intercostal nerves (posterior branches)
33 Serratus anterior muscle
34 Medial pectoral nerve
35 **Long thoracic nerve and lateral thoracic artery**
36 Intercostobrachial nerve (T_3)
37 **Lateral cutaneous branches of intercostal nerves** (anterior branches)



Right axillary region (inferior aspect). **Dissection of superficial axillary nodes and lymphatic vessels.** The pectoralis major muscle has been slightly elevated.

1	Deltoid muscle	12	Thoracodorsal artery
2	Cephalic vein	13	Lateral cutaneous branch of intercostal nerve
3	Median nerve	14	Latissimus dorsi muscle
4	Brachial artery	15	Thoracoepigastric vein
5	Medial cutaneous nerves of arm and forearm	16	Serratus anterior muscle
6	Ulnar nerve	17	Musculocutaneous nerve
7	Basilic Vein	18	Radial nerve
8	Intercostobrachial nerves	19	Pectoralis major muscle
9	Circumflex scapular artery	20	Nipple
10	**Superficial axillary nodes**		
11	Lateral thoracic artery		



Axillary region (anterior aspect). Dissection of deep axillary nodes. Pectoralis major and minor divided and reflected. Shoulder girdle and arm elevated and reflected.

1 Deltoid muscle
2 Insertion of pectoralis major muscle
3 Coracobrachialis muscle
4 Roots of **median nerve, axillary artery**
5 Short head of biceps brachii muscle
6 **Ulnar nerve** and medial cutaneous nerve of forearm
7 Thoracoepigastric vein
8 Deep axillary node
9 Latissimus dorsi muscle
10 Serratus anterior muscle
11 Cephalic vein
12 Insertion of pectoralis minor muscle (coracoid process)
13 **Musculocutaneous nerve**
14 Subclavius muscle
15 Thoracoacromial artery
16 **Axillary vein**
17 Clavicle
18 Pectoralis major and minor muscles (reflected)
19 Nipple
20 Anterior cutaneous branches of intercostal nerves
21 Anterior layer of rectus sheaths



Right axillary region (anterior aspect). The pectoralis major and minor muscles have been cut and reflected to display the vessels and nerves of the axilla.

1 Sternocleidomastoid muscle (cut and reflected)
2 Cervical plexus
3 Trapezius muscle
4 Pectoralis minor muscle and medial pectoral nerve
5 Deltoid muscle
6 Pectoralis major muscle and lateral pectoral nerve
7 **Median nerve and brachial artery**
8 Circumflex scapular artery
9 Short head of biceps brachii muscle
10 **Thoracodorsal artery and nerve**
11 Long head of biceps brachii muscle
12 Latissimus dorsi muscle
13 Serratus anterior muscle
14 Internal jugular vein
15 **Scalenus anterior muscle**
16 Phrenic nerve and ascending cervical artery
17 Brachial plexus (at the levels of the trunks)
18 Clavicle
19 Subclavius muscle
20 **Thoracoacromial artery**
21 Subclavian vein (cut)
22 **Axillary artery**
23 Subscapular artery
24 Superior thoracic artery
25 **Lateral thoracic artery and long thoracic nerve**
26 External intercostal muscle
27 Insertion of pectoralis minor muscle
28 Intercostobrachial nerves
29 Lateral cutaneous branches of intercostal nerves
30 Insertion of pectoralis major muscle



Shoulder and arm. Axillary region with brachial plexus (anterior aspect). The pectoralis major and minor muscles have been partly removed. The clavicle has been cut.

1 Trapezius muscle and accessory nerve
2 Brachial plexus
3 Clavicle (cut)
4 Pectoralis minor muscle
5 **Axillary (subclavian) artery**
6 Deltoid muscle
7 **Musculocutaneous nerve**
8 **Axillary nerve**
9 **Radial nerve**
10 Medial and lateral roots of the median nerve
11 **Median nerve** and **brachial artery**
12 **Ulnar nerve**
13 Short head of biceps brachii muscle
14 Medial cutaneous nerves of arm and forearm
15 Long head of biceps brachii muscle
16 Latissimus dorsi muscle
17 Cephalic vein
18 Cervical plexus
19 **Phrenic nerve and scalenus anterior muscle**
20 Descending scapular artery
21 Suprascapular artery
22 Internal thoracic artery
23 Subclavian vein
24 Thoracoacromial artery
25 Superior thoracic artery
26 **Thoracodorsal artery and nerve**
27 **Lateral thoracic artery and long thoracic nerve**
28 Intercostobrachial nerves
29 Insertion of the pectoralis minor muscle into the 2nd–5th ribs
30 Lateral cutaneous branches of intercostal nerves
31 Abdominal part of pectoralis major muscle (cut)
32 Suprascapular nerve and artery



Brachial plexus (anterior aspect). Clavicle and the two pectoralis muscles have been partly removed.



Main branches of brachial plexus. Posterior cord in red, lateral cord in yellow and medial cord in purple. (Schematic drawing.)

1	Accessory nerve
2	Dorsal scapular artery
3	Suprascapular nerve
4	Clavicle and pectoralis minor muscle
5	**Lateral cord** of brachial plexus
6	Musculocutaneous nerve
7	Axillary nerve
8	Median nerve
9	Brachial artery
10	Radial nerve
11	Cervical plexus
12	Common carotid artery
13	Roots of brachial plexus (C_5–T_1)
14	Phrenic nerve
15	Dorsal scapular artery
16	Subclavian artery
17	**Posterior cord** of brachial plexus
18	**Medial cord** of brachial plexus
19	Subscapular artery
20	Long thoracic nerve
21	Ulnar nerve
22	Medial cutaneous nerve of forearm
23	Thoracodorsal nerve
24	Intercostobrachial nerve
25	Medial cutaneous nerves of arm and forearm
26	Scalenus anterior muscle
27	Scalenus medius muscle
28	Intercostal nerve (T_1)
29	Axillary artery



Right arm. Dissection of vessels and nerves (medial aspect). Shoulder girdle has been reflected slightly.

1 Radial artery and superficial branch of radial nerve
2 Lateral cutaneous nerve of forearm
3 Brachioradialis muscle
4 Ulnar artery
5 Tendon of biceps brachii muscle
6 Brachialis muscle
7 Pronator teres muscle
8 **Median nerve**
9 Medial epicondyle of humerus
10 Inferior ulnar collateral artery
11 **Ulnar nerve**
12 Medial cutaneous nerve of forearm
13 **Brachial artery**
14 Biceps brachii muscle
15 Intercostobrachial nerve (T_3)
16 Latissimus dorsi muscle
17 Thoracodorsal nerve and artery
18 Serratus anterior muscle
19 Subscapular artery
20 Pectoralis major muscle (reflected) and lateral pectoral nerve
21 Radial nerve and profunda brachii artery
22 Axillary nerve
23 Roots of the median nerve with axillary artery
24 **Musculocutaneous nerve**
25 Pectoralis minor muscle (reflected) and medial pectoral nerve
26 Posterior cord of brachial plexus
27 Clavicle (cut)
28 Lateral cord of brachial plexus
29 Medial cord of brachial plexus
30 Subclavian artery
31 Brachial vein



Right arm. Dissection of vessels and nerves, deeper layer. Biceps muscle has been reflected.



Superficial veins and cutaneous nerves of forearm and hand (anteromedial aspect).



Sagittal section through the forearm at the level of the humeroulnar articulation (MR-Scan, after A. Heuck, G. Luttke, and J. W. Rohen, 1994).

1	**Cephalic vein**
2	Brachioradialis muscle covered by its fascia
3	**Posterior cutaneous nerve of forearm** (branch of radialis nerve)
4	Cephalic vein of forearm
5	Extensor pollicis longus and brevis muscles covered by their fascia
6	**Median cubital vein**
7	Lateral cutaneous nerves of forearm (branch of musculocutaneous nerve)
8	Intermedian vein of forearm
9	Superficial branch of radial nerve
10	**Dorsal digital branches of radial nerve**
11	Triceps brachii muscle
12	Venous network on the dorsum of the hand
13	Olecranon
14	**Humeroulnar articulation**
15	Ulna
16	Radiocarpal articulation
17	Biceps brachii muscle
18	Trochlea of humerus
19	Flexor muscles of forearm
20	Carpal bones



Vessels and nerves of right forearm, superficial layer (dorsal aspect).



Vessels and nerves of right forearm, deep layer (dorsal aspect).

1 Tendon of triceps brachii muscle
2 Olecranon
3 Anconeus muscle
4 Extensor digitorum muscle
5 Extensor carpi ulnaris muscle
6 Deep branch of radial nerve
7 Posterior interosseous artery
8 Extensor pollicis longus muscle
9 Extensor indicis muscle
10 Tendon of extensor carpi ulnaris muscle
11 Extensor retinaculum
12 Dorsal branch of ulnar nerve
13 Biceps brachii muscle
14 Brachialis muscle
15 Brachioradialis muscle
16 Lateral epicondyle of humerus
17 Extensor carpi radialis longus muscle
18 Extensor carpi radialis brevis muscle
19 Abductor pollicis longus muscle
20 Tendons of extensor digitorum muscle
21 Extensor pollicis brevis muscle
22 Superficial branch of radial nerve
23 Radial artery
24 Posterior interosseous nerve
25 Posterior interosseous branch of radial nerve
26 Posterior branch of anterior interosseous artery
27 Supinator muscle



Cutaneous nerves and veins of forearm and hand (superficial layer, dorsal aspect).



Dorsal region of forearm and hand (deeper layer). Extensor digitorum muscle has been partly removed.



Innervation pattern of dorsal surfaces of hand

$2^1/_2$ digits by radial nerve, $2^1/_2$ digits by ulnar nerve. Note that the terminal branches to the dorsal surfaces of the distal phalanges are derived from the palmar digital nerves. The cutaneous distribution varies; often $3^1/_2$ digits are innervated by the radial and $1^1/_2$ digits by the ulnar nerve.

1 **Posterior cutaneous nerve of forearm** (branch of radial nerve)
2 Extensor digitorum muscle
3 Tendon of extensor carpi ulnaris muscle
4 Extensor retinaculum
5 **Ulnar nerve**
6 **Venous network of dorsum of hand**
7 Abductor pollicis longus muscle
8 Cephalic vein
9 Extensor pollicis brevis muscle
10 **Radial nerve,** superficial branch
11 **Radial artery**
12 Tendon of extensor pollicis longus muscle
13 Dorsal digital branches of radial nerve
14 Tendons of extensor digitorum muscle with intertendinous connections
15 Posterior interosseus nerve (branch of the deep radial nerve)
16 Posterior interosseous artery
17 Styloid process of ulna
18 Dorsal interosseus muscle IV
19 Dorsal carpal branch of radial artery
20 **Lateral cutaneous nerve of forearm** (branch of musculocutaneous nerve)
21 Dorsal metacarpal artery
22 Proper dorsal digital branches of ulnar nerve
23 Regions supplied by palmar digital nerves (ulnar nerve)
24 Regions supplied by palmar digital nerves (median nerve)
25 Communicating branch with ulnar nerve



Cubital region (anterior aspect), dissection of cutaneous nerves and veins.



Cubital region, superficial layer (anterior aspect). The fasciae of the muscles have been removed.

1 Biceps brachii muscle with fascia
2 **Cephalic vein**
3 **Median cubital vein**
4 Lateral cutaneous nerve of forearm
5 Tendon and aponeurosis of biceps brachii muscle (covered by the antebrachial fascia)
6 Brachioradialis muscle with fascia
7 Accessory cephalic vein
8 Median vein of forearm
9 Branches of lateral cutaneous nerve of forearm
10 Terminal branches of medial cutaneous nerve of arm
11 **Medial cutaneous nerve of forearm**
12 **Basilic vein**
13 Medial epicondyle of humerus
14 Terminal branches of medial cutaneous nerve of forearm
15 Biceps brachii muscle
16 Tendon of biceps brachii muscle
17 Radial nerve
18 Brachioradialis muscle
19 Radial recurrent artery
20 **Radial artery**
21 **Ulnar nerve**
22 Superior ulnar collateral artery
23 Medial intermuscular septum
24 **Brachial artery**
25 **Median nerve**
26 Pronator teres muscle
27 Bicipital aponeurosis
28 Ulnar artery
29 Palmaris longus muscle
30 Flexor carpi radialis muscle
31 Flexor digitorum superficialis muscle
32 Flexor carpi ulnaris muscle



Cubital region, middle layer (anterior aspect). The bicipital aponeurosis has been removed.



Cubital region, middle layer (anterior aspect). The pronator teres and brachioradialis muscles have been slightly reflected.

1	Median nerve
2	Biceps brachii muscle
3	Brachial artery
4	Lateral cutaneous nerve of forearm (terminal branch of **musculocutaneous nerve**)
5	Brachialis muscle
6	Tendon of biceps brachii muscle
7	Brachioradialis muscle
8	**Radial artery**
9	**Ulnar artery**
10	Superficial branch of radial nerve
11	Lateral cutaneous nerve of forearm
12	Medial cutaneous nerve of forearm
13	Triceps brachii muscle
14	**Ulnar nerve**
15	Inferior ulnar collateral artery
16	Anterior branch of medial cutaneous nerve of forearm
17	Medial epicondyle of humerus
18	**Median nerve** with branches to pronator teres muscle
19	Pronator teres muscle
20	Flexor carpi radialis muscle
21	Deep branch of radial nerve
22	Radial recurrent artery
23	Supinator muscle
24	Medial intermuscular septum of arm



Cubital region, deep layer (anterior aspect). The pronator teres and flexor carpi ulnaris muscles have been cut and reflected.



Cubital region, deepest layer (anterior aspect). The flexor digitorum superficialis and the ulnar head of the pronator teres have been cut and reflected.

1 Biceps brachii muscle
2 Brachialis muscle
3 Brachioradialis muscle
4 Superficial branch of radial nerve
5 Deep branch of radial nerve
6 Tendon of biceps brachii muscle
7 **Radial recurrent artery**
8 Supinator muscle
9 Insertion of pronator teres muscle
10 **Radial artery**
11 **Ulnar nerve**
12 Medial intermuscular septum of arm and superior ulnar collateral artery
13 **Brachial artery**
14 **Median nerve**
15 Medial epicondyle of humerus
16 Humeral head of pronator teres muscle
17 **Ulnar artery**
18 Ulnar head of pronator teres muscle
19 **Ulnar recurrent artery**
20 Anterior interosseous nerve
21 Common interosseous artery
22 Tendinous arch of flexor digitorum superficialis muscle
23 Anterior interosseous artery
24 Flexor digitorum superficialis muscle
25 Flexor digitorum profundus muscle
26 Flexor pollicis longus muscle


1
2
3
5
3
6
6
7
6
9
11
12
13
14
15
16
7
17
18
19
20
21
22
23
24
25
20
26
27
28
29
32
34

Vessels and nerves of right forearm and hand, superficial layer (palmar aspect).


1
2
3
4
5
6
7
6
8
9
10
11
12
13
14
15
16
7
17
18
20
22
23
13
24
25
13
20
26
27
30
31
33
34

Vessels and nerves of right forearm and hand, superficial layer (palmar aspect). The palmar aponeurosis of the hand and the bicipital aponeurosis have been removed.



Vessels and nerves of forearm and hand, deep layer (anterior aspect). The superficial layer of the flexor muscles has been removed.

1 Biceps brachii muscle
2 Brachialis muscle
3 Brachioradialis muscle
4 **Deep branch of radial nerve**
5 **Superficial branch of radial nerve**
6 **Radial artery**
7 **Median nerve**
8 Flexor retinaculum
9 Thenar muscles
10 Common palmar digital branches of median nerve
11 Common palmar digital arteries
12 Proper palmar digital nerves (median nerve)
13 **Ulnar nerve**
14 Medial intermuscular septum of arm
15 Superior ulnar collateral artery
16 Brachial artery
17 Medial epicondyle of humerus
18 Pronator teres muscle
19 Bicipital aponeurosis
20 **Ulnar artery**
21 Palmaris longus muscle
22 Flexor carpi radialis muscle
23 Flexor digitorum superficialis muscle
24 Flexor carpi ulnaris muscle
25 Tendon of palmaris longus muscle
26 Remnant of antebrachial fascia
27 Superficial branch of ulnar nerve
28 Palmaris brevis muscle
29 Palmar aponeurosis
30 Hypothenar muscles
31 **Superficial palmar arch**
32 Superficial transverse metacarpal ligament
33 Common palmar digital branch of ulnar nerve
34 Proper palmar digital branches of ulnar nerve
35 Anterior interosseous artery and nerve
36 Flexor digitorum profundus muscle
37 Common palmar digital arteries
38 Palmar branch of median nerve
39 Flexor pollicis longus muscle
40 Palmar branch of ulnar nerve



Cutaneous innervation of hand (palmar aspect). (Schematic drawing.)

Cutaneous innervation of palmar surface:
3½ digits by median nerve,
1½ digits by ulnar nerve.



Right hand, superficial layer, dissection of vessels and nerves (palmar aspect).



Right hand, superficial layer, dissection of vessels and nerves (palmar aspect). The palmar aponeurosis has been removed to display the superficial palmar arch.

1 Tendon of palmaris longus muscle
2 **Radial artery**
3 Tendon of flexor carpi radialis muscle and median nerve
4 Distal part of antebrachial fascia
5 Radial artery passing into the anatomical snuffbox
6 Abductor pollicis brevis muscle
7 Superficial head of flexor pollicis brevis muscle
8 Palmar digital artery of thumb
9 Common palmar digital arteries
10 Proper palmar digital nerves (median nerve)
11 **Ulmar nerve**
12 Tendon of flexor carpi ulnaris muscle
13 **Ulnar artery**
14 Superficial branch of ulnar nerve
15 Palmaris brevis muscle
16 Palmar aponeurosis
17 Palmar digital nerves (ulnar nerve)
18 Superficial transverse metacarpal ligament
19 Proper palmar digital arteries
20 Superficial palmar branch of radial artery (contributing to the superficial palmar arch)
21 Flexor retinaculum
22 **Median nerve**
23 Abductor digiti minimi muscle
24 Flexor digiti minimi brevis muscle
25 Opponens digiti minimi muscle
26 **Superficial palmar arch**
27 Tendons of flexor digitorum superficialis muscle
28 Common palmar digital branch of ulnar nerve
29 Common palmar digital branch of median nerve
30 Fibrous sheath of flexor tendons


1
2
3
4
5
6
4
7
8
9
10
11
12
13
12
14
15
16
17
18
19
20
21
22
23
24
25
11
13
14

Coronal section through the right hand (palmar aspect).


1
3
6
7
26
15
18
19
21
24
9
11
27
13
14

Coronal section through the right hand (palmar aspect) (MR-Scan, courtesy of Dr. A. Heuck, Munich).

1 Radius
2 **Radiocarpal articulation**
3 **Scaphoid** (navicular) **bone**
4 **Radial artery**
5 Trapezoid bone
6 **Trapezium bone**
7 First metacarpal bone
8 Metacarpophalangeal articulation of thumb
9 Interosseous muscles
10 Proximal phalanx of thumb
11 Proximal phalanx of fingers
12 Interphalangeal articulations
13 Middle phalanx
14 Distal phalanx
15 **Ulna**
16 Distal radioulnar articulation
17 Articular disk
18 **Lunate bone**
19 **Triangular bone**
20 **Capitate bone**
21 **Hamate bone**
22 Carpometacarpal articulations
23 Abductor digiti minimi muscle
24 Fifth metacarpal bone
25 Metacarpophalangeal articulation
26 Adductor pollicis muscle
27 Proper palmar digital arteries


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15

Horizontal section through shoulder joint (section 1; MR-Image; inferior aspect).



Upper extremity, location of sections 1–5 (MR-Scans, courtesy of Dr. A. Heuck, Munich).

1 Pectoralis major muscle
2 Greater tubercle and tendon of biceps muscle
3 Lesser tubercle
4 Head of humerus and articular cavity of shoulder joint
5 Deltoid muscle
6 Scapula
7 Infraspinatus muscle
8 Serratus anterior muscle
9 Sternum
10 Infrahyoid muscles
11 Trachea
12 Body of thoracic vertebra
13 Vertebral canal and spinal cord
14 Deep muscles of the back
15 Trapezius muscle
16 Brachialis muscle
17 Radial nerve and profunda brachii vessels


1
2
4
6
5
7
9
10
11
*
12
13
14
15

Horizontal section through the right shoulder at the level of T_1 (section 1; inferior aspect). * = Upper lobe of lung.


19
20
16
21
23
22
24
17
25
18

Axial section through the middle of the right arm (section 2; MR-Image, inferior aspect).


19
20
16
23
24
29
17
22
25
18
18

Axial section through the middle of the right arm (section 2; inferior aspect).



Axial section through the elbow joint (section 3; MR-Image; inferior aspect).



Axial section through the right elbow joint (section 3; inferior aspect).



Axial section through the middle of the forearm (section 4; MR-Image; inferior aspect).



Axial section through the right forearm (section 4; inferior aspect).

18 Triceps brachii muscle
19 Cephalic vein
20 Biceps brachii muscle
21 Musculocutaneous nerve
22 **Ulnar nerve**
23 **Medianus nerve**
24 Brachial artery and vein
25 Shaft of humerus
26 Brachioradialis muscle
27 **Radial nerve**
28 Olecranon and articular cavity of elbow joint
29 Basilic vein
30 Humerus
31 Pronator teres muscle
32 Extensor muscles of forearm
33 Ramus profundus of radialis nerve
34 Anterior interosseus vessels and nerve
35 Interosseous membrane
36 Ulna
37 Radius
38 Radial artery and superficial branch of radial nerve
39 Flexor pollicis longus muscle
40 Flexor digitorum superficialis and profundus muscles
41 Ulnar nerve, ulnar artery and vein
42 Flexor carpi ulnaris muscle
43 Radial artery
44 Metacarpal bones III and IV
45 **Carpal canal** with tendons of flexor digitorum muscles
46 Hypothenar muscle
47 Median nerve
48 Interosseus muscles
49 First metacarpal bone
50 Thenar muscles
51 Articular cavity of humeroradial joint
52 Median cubital vein



Axial section through the right hand (metacarpus; MR-Image; section 5; inferior aspect).



Axial section through the right hand at the level of the metacarpus (section 5; inferior aspect).


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27


1
4
3
32
19
8
31
12
14
34
16
43
18
30
23
25
27
35

Arteries and nerves of the right hand (palmar aspect). (Schematic drawing.)

◁

Right hand, superficial layer (palmar aspect). Dissection of the superficial palmar arch.


38
39
44
40
41
42

Longitudinal section through the hand at the level of the third finger


36
37
38
39
24
40
41
42

Longitudinal section through the hand at the level of the third finger (MR-Scan, courtesy of Dr. A. Heuck, Munich).



Right hand, middle layer (palmar aspect). The flexor retinaculum has been removed.



Arteriogram of the right hand (palmar aspect).

1 Superficial branch of radial nerve
2 Tendon of flexor carpi radialis muscle
3 **Radial artery**
4 **Median nerve**
5 Tendon of flexor digitorum superficialis muscle
6 Tendon of abductor pollicis longus muscle
7 Tendon of extensor pollicis brevis muscle
8 Superficial palmar branch of radial artery
9 Abductor pollicis brevis muscle
10 Superficial head of flexor pollicis brevis muscle
11 Terminal branches of superficial branch of radial nerve
12 Common palmar digital nerves (median nerve)
13 Proper palmar digital arteries of thumb
14 Proper palmar digital nerves (median nerve)
15 Tendon of flexor carpi ulnaris muscle
16 **Ulnar artery**
17 Position of pisiform bone
18 Superficial branch of ulnar nerve
19 Flexor retinaculum
20 Deep branch of ulnar nerve
21 Abductor digiti minimi muscle
22 Common palmar digital nerves (ulnar nerve)
23 **Superficial palmar arch**
24 Tendons of flexor digitorum muscles
25 Common palmar digital arteries
26 **Palmar digital nerves (ulnar nerve)**
27 **Proper palmar digital arteries**
28 **Carpal tunnel**
29 Fibrous sheaths for the tendons of flexor digitorum muscles
30 **Deep palmar arch**
31 Princeps pollicis artery
32 Palmar branch of median nerve
33 Common digital palmar artery
34 Ulnar nerve
35 Capillary network of finger
36 Radius
37 Carpal bones
38 Metacarpal bone
39 Interosseus muscles
40 Proximal phalanx
41 Middle phalanx
42 Distal phalanx
43 Dorsal branch of ulnar nerve
44 Tendons of flexor digitorum profundus (upper) and superficialis (lower) muscles



Right hand, deep layer (palmar aspect). The carpal tunnel has been opened, the tendons of the flexor muscles have been removed and the superficial palmar arch has been cut.



Right hand, deep layer (palmar aspect). Dissection of the deep palmar arch.

1 Tendon of flexor carpi radialis muscle
2 Radial artery
3 Tendon of abductor pollicis longus muscle
4 Abductor pollicis brevis muscle
5 Superficial and deep heads of flexor pollicis brevis muscle
6 Oblique and transverse heads of adductor pollicis muscle
7 Median nerve
8 Tendons of flexor digitorum superficialis and profundus muscles
9 Tendon of flexor pollicis longus muscle
10 Pronator quadratus muscle
11 Tendon of flexor carpi ulnaris muscle
12 Ulnar artery
13 Superficial branch of ulnar nerve
14 Deep branch of ulnar nerve
15 Abductor digiti minimi muscle
16 **Superficial palmar arch** (cut end)
17 Common palmar digital nerves (ulnar nerve)
18 Palmar metacarpal arteries of deep palmar arch
19 Palmar digital artery of the 5th finger
20 Fibrous sheaths of tendons of flexor muscles
21 Palmar interosseous muscles
22 Opponens pollicis muscle (cut)
23 **Deep palmar arch**
24 1st dorsal interosseous muscle
25 1st lumbrical muscle



Coronal section through pelvis and thighs (MR-Scan of the male, courtesy of Dr. A. Heuck, Munich).



Coronal section through the legs (MR-Scan, courtesy of Dr. A. Heuck, Munich).

1 Sacral promontory
2 Gluteus medius muscle
3 Small intestine and urinary bladder
4 Acetabulum
5 **Head of femur**
6 Greater trochanter of femur
7 Vastus lateralis muscle
8 **Femur**
9 Adductor muscles
10 **Knee joint** with menisci
11 **Tibia**
12 Soleus muscle
13 Tibialis anterior muscle
14 Distal tibiofibular articulation
15 **Talocrural articulation**
16 Fibula (lateral malleolus)

The lower limb (extremity) is specialized for support of the upright posture, locomotion and maintaining balance. In contrast to the upper limb, the lower limb is more restricted in its movements, and the joints are more tight and fixed by strong ligaments. The hip joint is a ball and socket type of synovial joint between head of femur and acetabulum. The knee joint is a hinge type of synovial joint that permits only limited rotation. The talocrural joint is a hinge joint between talus, fibula, and tibia only allowing movements of flexion and extension.
The long axis of the foot is at right angle to that of the leg, thus, forming an effective arch for the upright stance of man.

A	Pelvic girdle
B	Thigh
C	Leg
D	Foot
1	Right hip bone
2	Sacrum
3	Femur
4	Patella
5	Fibula
6	Tibia
7	Tarsal bones
8	Metatarsal bones
9	Phalanges
10	Sacroiliac joint
11	Pubic symphysis
12	Hip joint
13	Knee joint
14	Proximal tibiofibular joint
15	Distal tibiofibular joint
16	Talocrural joint
17	Talocalcaneonavicular joint
18	Tarsometatarsal joints
19	Metatarsophalangeal joints
20	Interphalangeal joints

The pelvic girdle is firmly connected to the vertebral column at the sacroiliac joint. Therefore the body can be kept upright more easily even if only one limb is used for support (as in walking). The mobility of the lower limb is more limited than that of the upper limb.



Skeleton of pelvic girdle and lower limb (anterior aspect). The talocrural joint has been dislocated.



Organization of pelvic girdle and lower limb.



Right hip bone (lateral aspect).



Right hip bone (medial aspect).



Sacrum and coccyx (lateral aspect).

A	Ilium
B	Ischium
C	Pubis
1	Posterior superior iliac spine
2	Posterior gluteal line
3	Posterior inferior iliac spine
4	Greater sciatic notch
5	Ischial spine
6	Lesser sciatic notch
7	Body of ischium
8	Ischial tuberosity
9	Obturator foramen
10	Iliac crest
11	Anterior gluteal line
12	Internal lip of iliac crest
13	External lip of iliac crest
14	Anterior superior iliac spine
15	Inferior gluteal line
16	Anterior inferior iliac spine
17	Lunate surface of acetabulum
18	Acetabular fossa
19	Acetabular notch
20	Pecten pubis
21	Pubic tubercle
22	Body of pubis
23	Iliac fossa
24	Arcuate line
25	Iliopubic eminence
26	Articular surface of pubis
27	Auricular surface of sacrum
28	Pelvic surface of sacrum
29	Superior articular process of sacrum
30	Dorsal sacral foramina
31	Sacral tuberosity
32	Lateral sacral crest
33	Median sacral crest
34	Obturator groove
35	Coccyx



Sacrum (posterior aspect).



Sacrum (anterior aspect).



Sacrum (superior aspect).



Diameters of pelvis (oblique superior aspect). (Schematic drawing.)

1 Superior articular process of sacrum
2 Dorsal sacral foramina
3 Sacral hiatus
4 Median sacral crest
5 Lateral sacral crest
6 Sacral tuberosity
7 Intermediate sacral crest
8 Coccyx
9 Base of sacrum
10 Sacral promontory
11 Anterior sacral foramina
12 Lateral part of sacrum (ala)
13 Transverse line of sacrum
14 Sacral canal
15 Linea terminalis
16 True conjugate
17 Diagonal conjugate
18 Transverse diameter
19 Oblique diameter
20 Inferior pelvic aperture or outlet


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
22
21
11
15

Female pelvis (superior aspect). Note the differences between the male and the female pelvis, predominantly in the form and dimensions of the sacrum, the superior and inferior apertures and the alae of the ilium.


2
17
3
4
5
6
11
12
13
14
15
1
18
19
20
21
22
11
15
16

Male pelvis (superior aspect). Compare with the female pelvis (depicted above).

1 Superior articular process of sacrum
2 Posterior superior iliac spine
3 Base of sacrum
4 Sacral promontory
5 Coccyx
6 Ischial spine
7 External lip } of iliac crest
8 Intermediate line } of iliac crest
9 Internal lip } of iliac crest
10 Arcuate line
11 Anterior superior iliac spine
12 Anterior inferior iliac spine
13 Iliopubic eminence
14 Pecten pubis
15 Pubic tubercle
16 Pubic symphysis
17 Sacral canal
18 Ala of sacrum
19 Position of sacroiliac joint
20 Iliac fossa
21 Linea terminalis
22 Iliac crest



Female pelvis (anterior aspect). Note the differences between the form and dimensions of the male and the female pelvis. The female pubic arch is wider than the male. The obturator foramen in the female pelvis is triangular, while that in the male pelvis is ovoid.



Male pelvis (anterior aspect). Compare with foregoing figure.

1 Anterior superior iliac spine
2 Iliac fossa
3 Position of sacroiliac joint
4 Iliopubic eminence
5 Lunate surface of acetabulum
6 Acetabular notch
7 Obturator foramen
8 Ischial tuberosity
9 Pubic arch
10 Anterior inferior iliac spine
11 Sacrum
12 Linea terminalis (at margin of superior aperture)
13 Pubic symphysis
14 Ischial spine
15 Coccyx



Female pelvis (posterior inferior aspect). Note the differences between the female and male pelvis, especially with respect to the inferior aperture, the shape of the sacrum, the two sciatic notches and the pubic arch.



Male pelvis (posterior inferior aspect). Compare with the female pelvis (depicted above).

1 Iliac crest
2 Sacral canal
3 Posterior gluteal line
4 Posterior superior iliac spine
5 Position of sacroiliac joint
6 Dorsal sacral foramina
7 Sacral hiatus
8 Obturator foramen
9 Ramus of ischium
10 Coccyx
11 Superior articular process of sacrum
12 Gluteal surface of ilium
13 Median sacral crest
14 Greater sciatic notch
15 Position of acetabulum
16 Ischial spine
17 Lesser sciatic notch
18 Ischial tuberosity



Bones of right hip joint (anterior aspect).



Bones of right hip joint (posterior aspect).

1 Iliac crest
2 Lateral part of sacrum (ala)
3 Position of sacroiliac joint
4 Anterior superior iliac spine
5 Linea terminalis
6 Iliopubic eminence
7 Bony margin of acetabulum
8 Head of femur
9 Greater trochanter
10 Neck of femur
11 Intertrochanteric line
12 Shaft of femur
13 5th lumbar vertebra
14 Imitation intervertebral disc between 5th lumbar vertebra and sacrum
15 Sacral promontory
16 Anterior sacral foramina
17 Pubic tubercle
18 Obturator foramen
19 Ramus of ischium
20 Lesser trochanter
21 Dorsal sacral foramina
22 Greater sciatic notch
23 Ischial spine
24 Pubic symphysis
25 Pubis
26 Ischial tuberosity
27 Intertrochanteric crest
28 Symphysial surface

Diameters of the pelvis

A True conjugate (11–11.5 cm) (Conjugata vera)
B Diagonal conjugate (12.5–13 cm)
C Largest diameter of pelvis
D Inferior pelvic aperture
E Pelvic inclination (60°)



Inclination and diameters of the female pelvis, right half (medial aspect).


7
8
1
2
9
10
3
4
5
11
6

Right femur (anterior aspect).


7
8
1
9
10
12
13
4
14
15
6
11
16

Right femur (medial aspect).


7
1
9
17
12
18
19
20
14
11
5
16
15
21

Right femur (posterior aspect).

1 Greater trochanter
2 Intertrochanteric line
3 Nutrient foramina
4 Shaft of femur (diaphysis)
5 Lateral epicondyle
6 Patellar surface
7 Head
8 Fovea of head
9 Neck
10 Lesser trochanter
11 Medial epicondyle
12 Pectineal line
13 Linea aspera
14 Popliteal surface
15 Lateral condyle
16 Medial condyle
17 Intertrochanteric crest
18 Third trochanter
19 Medial lip of linea aspera
20 Lateral lip of linea aspera
21 Intercondylar fossa

1 Lateral condyle of tibia
2 Position of tibiofibular joint
3 Head of fibula
4 Interosseous border of tibia
5 Shaft of fibula
6 Interosseous border of fibula
7 Lateral surface of fibula
8 Position of tibiofibular joint
9 Lateral malleolus
10 Medial condyle of tibia
11 Tuberosity of tibia
12 Shaft of tibia (diaphysis)
13 Anterior margin of tibia
14 Medial malleolus
15 Inferior articular surface of tibia
16 Intercondylar eminence
17 Soleal line
18 Medial border of tibia
19 Posterior surface of tibia
20 Malleolar sulcus of tibia
21 Malleolar articular surface of fibula
22 Apex of head of fibula
23 Posterior surface of fibula
24 Posterior border of fibula
25 Medial intercondylar tubercle
26 Posterior intercondylar area
27 Anterior intercondylar area
28 Lateral intercondylar tubercle



Bones of leg, right tibia and fibula (anterior aspect).



Bones of leg, right tibia and fibula (posterior aspect).



Upper end of right tibia with fibula (from above), anterior margin of tibia above. Superior articular surface of tibia.



Bones of right knee joint (anterior aspect).



Bones of right knee joint (posterior aspect).



Bones of right knee joint (lateral aspect).



Right patella (anterior aspect).



Right patella (posterior aspect).

1 **Femur**
2 Patellar surface of femur
3 Lateral epicondyle of femur
4 Intercondylar eminence of tibia
5 Lateral condyle of tibia
6 Position of tibiofibular joint
7 Head of fibula
8 Tuberosity of **tibia**
9 **Fibula**
10 Shaft of tibia
11 Popliteal surface of femur
12 Intercondylar fossa of femur
13 Lateral condyle of femur
14 **Patella**
15 Base of patella
16 Anterior surface of patella
17 Apex of patella
18 Articular surface of patella


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
27
32

Bones of right foot (dorsal aspect).


16
17
18
19
20
21
22
23
24
31
25
27
32
1
2
3
4
5
6
7
8
9
10
11
12
33

Bones of right foot (plantar aspect).


34
35
14
15
12
33
10
32
4
36
37
38
39
40
25
24
21

Bones of right foot together with tibia and fibula (posterior aspect).

1	Tuberosity of distal phalanx of great toe
2	Distal phalanx of great toe
3	Proximal phalanx of great toe
4	Head of first metatarsal bone
5	First metatarsal bone
6	Base of first metatarsal bone
7	Medial cuneiform bone
8	Intermediate cuneiform bone
9	Position of **cuneonavicular joint**
10	Navicular bone



Bones of right foot, tibia and fibula (lateral aspect).



Bones of right foot, tibia and fibula (medial aspect).

11 Position of **talocalcaneonavicular joint**
12 Head of talus
13 Neck of talus
14 Trochlea of talus
15 Posterior talar process
16 Distal phalanges
17 Middle phalanges
18 Position of **interphalangeal joints**
19 Proximal phalanges
20 Position of **metatarsophalangeal joints**
21 Metatarsal bones
22 Position of **tarsometatarsal joints**
23 Lateral cuneiform bone
24 Tuberosity of 5th metatarsal bone
25 Cuboid bone
26 Position of **calcaneocuboid joint**
27 Calcaneus
28 Tarsal sinus
29 Lateral malleolar surface of talus
30 Peroneal trochlea of calcaneus
31 Groove for tendon of peroneus longus
32 Calcaneal tuberosity
33 Sustentaculum tali
34 Tibia
35 Medial malleolus
36 Fibula
37 Position of tibiofibular syndesmosis
38 Position of **talocrural joint**
39 Lateral malleolus
40 Position of **subtalar joint**



Ligaments of pelvis and hip joint (anterior aspect).

1 **Iliolumbar ligament**
2 Iliac crest
3 Fifth lumbar vertebra
4 Sacral promontory
5 Anterior superior iliac spine
6 Inguinal ligament
7 Sacrospinous ligament
8 Greater trochanter
9 **Iliofemoral ligament** (vertical band)
10 Lesser trochanter
11 Forth lumbar vertebra
12 Iliolumbar and ventral sacroiliac ligaments
13 Sacrum
14 Iliopectineal arch
15 **Iliofemoral ligament** (horizontal band)
16 Obturator canal
17 Obturator membrane
18 **Greater sciatic foramen**
19 Sacrospinous ligament
20 Sacrotuberous ligament
21 **Lesser sciatic foramen**
22 Ischial tuberosity
23 **Ischiofemoral ligament**
24 Intertrochanteric crest
25 Femur
26 Articular capsule of hip joint
27 Dorsal sacroiliac ligaments
28 Coccyx with superficial dorsal sacrococcygeal ligament
29 Head of femur
30 Articular cartilage of head of femur
31 Articular cavity of hip joint
32 Acetabular lip
33 Spongy bone
34 Ligament of head of femur
35 Pubofemoral ligament
36 Zona orbicularis



Ligaments of pelvis and hip joint (left anterior aspect).



Coronal section of right hip joint (anterior view).



Right hip joint, opened (lateral anterior aspect). The ligament of the head of the femur has been divided and the femur has been posteriorly reflected.

1	Femur
2	Lesser trochanter
3	Neck of femur
4	Head of femur
5	Fovea of head with remnants of ligament of head
6	Lunate surface of acetabulum
7	Acetabular lip
8	Acetabular fossa
9	Transverse acetabular ligament
10	Inguinal ligament
11	Iliopectineal arch
12	Pubic symphysis
13	Pubic bone
14	Obturator canal
15	Ligament of head of femur
16	Obturator membrane
17	Ischium
18	Anterior longitudinal ligament (level of fifth lumbar vertebra)
19	Sacral promontory
20	Iliolumbar ligament
21	Iliac crest
22	Anterior superior iliac spine
23	Iliofemoral ligament (horizontal band)
24	Iliofemoral ligament (vertical band)
25	Greater trochanter
26	Pubofemoral ligament
27	Anterior inferior iliac spine
28	Ventral sacroiliac ligaments
29	**Sacrospinous ligament**
30	**Sacrotuberous ligament**
31	Intertrochanteric line
32	**Ischiofemoral ligament**
33	Zona orbicularis



Ligaments of the pelvis and hip joint (antero-lateral aspect).



Ligaments of hip joint (anterior aspect). (Schematic drawing.)



Ligaments of hip joints (posterior aspect). (Schematic drawing.)



Right knee joint (opened) **with ligaments** (anterior aspect). The patella and articular capsule have been removed and the femur slightly flexed.



Right knee joint with ligaments (posterior aspect). The joint is extended and the articular capsule has been removed.



Articular surface of right tibia, menisci, and cruciate ligaments (superior aspect). Anterior margin of tibia above.

1 Femur
2 Articular capsule with **suprapatellar bursa**
3 Patellar surface
4 Lateral condyle of femur
5 **Lateral meniscus of knee joint**
6 Fibular collateral ligament
7 Lateral condyle of tibia (superior articular surface)
8 Fibula
9 Medial condyle of femur
10 Tibial collateral ligament
11 **Anterior cruciate ligament**
12 **Medial meniscus of knee joint**
13 Transverse ligament of knee
14 Patellar ligament
15 Common tendon of sartorius, semitendinosus and gracilis muscles
16 Tibia
17 **Posterior cruciate ligament**
18 Medial condyle of tibia (superior articular surface)
19 Posterior meniscofemoral ligament
20 Head of fibula
21 Tendon of semimembranosus muscle
22 Posterior attachment of articular capsule of knee joint
23 Lateral epicondyle of femur



Right knee joint, opened (anterior aspect). Patellar ligament with patella reflected.



Right knee joint. Frontal section through the central part of the joint (posterior aspect, MR-Scan). (See also p. 10.)

1 Iliotibial tract
2 Articular muscle of knee
3 Patellar surface
4 Lateral condyle of femur
5 Articular capsule
6 Infrapatellar fat pad
7 **Patella** (articular surface)
8 **Suprapatellar bursa**
9 Quadriceps muscle of thigh (divided)
10 **Anterior cruciate ligament**
11 Medial condyle of femur
12 Fibular collateral ligament
13 **Posterior cruciate ligament**
14 Medial epicondyle of femur
15 Intercondylar fossa of femur
16 Tibial collateral ligament
17 **Medial meniscus** of knee joint
18 Medial intercondylar tubercle
19 Femur
20 Lateral epicondyle of femur
21 **Lateral meniscus** of knee joint
22 Epiphyseal line of tibia
23 Tibia



Sagittal section through the knee joint. Anterior surface to the left.

1 **Femur**
2 Quadriceps femoris muscle
3 Suprapatellar bursa and articular cavity
4 **Patella**
5 Patellar surface (articular cartilage)
6 Infrapatellar fat pad
7 Patellar ligament
8 **Tibia**
9 Tibial nerve
10 Adductor magnus muscle
11 Popliteal vein
12 Semitendinosus muscle
13 Semimembranosus muscle
14 **Popliteal artery**
15 Gastrocnemius muscle
16 Anterior cruciate ligament
17 Posterior cruciate ligament
18 Popliteus muscle
19 Soleus muscle
20 Deep flexor muscles of leg
21 Calcaneal tendon
22 Epiphyseal line of tibia
23 Calcaneus
24 **Talocrural joint**
25 Talus
26 Lateral meniscus
27 Epiphysial line



Talocrural joint. Sagittal section; anterior part to the left. (MR-Scan.)



Left knee joint. Anterior cruciate ligament (lateral aspect).



Ligaments of talocrural joint, right leg (posterior aspect).



Deep ligaments of the foot, right foot (plantar aspect). The toes have been removed.



Right knee joint and tibiofibular joint with ligaments. Note the position of the lateral meniscus.

1 Quadriceps femoris muscle
2 Femur
3 Patellar surface
4 Lateral epicondyle of femur
5 **Fibular collateral ligament**
6 Head of fibula
7 **Fibula**
8 **Patella**
9 Articular cavity of knee joint
10 Infrapatellar fat pad
11 **Patellar ligament**
12 **Lateral meniscus of knee joint**
13 Lateral condyle of tibia (superior articular facet)
14 **Tibiofibular joint**
15 Tibia
16 Trochlea of talus (superior surface)
17 Deltoid ligament of ankle (posterior tibiotalar part)
18 Talus
19 **Sustentaculum tali**
20 Navicular bone
21 1st metatarsal bone
22 **Posterior tibiofibular ligament**
23 Lateral malleolus
24 Posterior talofibular ligament
25 Calcaneofibular ligament
26 Calcaneal tuberosity
27 Plantar tarsometatarsal ligaments
28 **Long plantar ligament**
29 Plantar cuneonavicular ligaments



Ligaments of right foot (lateral aspect).



Ligaments of right foot (medial aspect).

1 Fibula
2 Tibia
3 Trochlea of talus and **talocrural joint**
4 Anterior tibiofibular ligament
5 Anterior talofibular ligament
6 Lateral malleolus
7 Calcaneofibular ligament
8 Lateral talocalcaneal ligament
9 **Subtalar joint**
10 Tuber calcanei
11 Interosseous talocalcaneal ligament
12 Bifurcate ligament
13 Long plantar ligament
14 **Calcaneocuboid joint**
15 Tuberosity of 5th metatarsal bone
16 Dorsal tarsometatarsal ligaments
17 Metatarsal bones
18 Head of talus and **talocalcaneonavicular joint**
19 Navicular bone
20 Dorsal cuneonavicular ligaments
21 Heads of metatarsal bones
22 Medial or deltoid ligament of ankle (tibionavicular part)
23 Medial or deltoid ligament of ankle (tibiocalcaneal part)
24 Dorsal cuneonavicular ligaments
25 Navicular bone
26 Plantar cuneonavicular ligament
27 1st metatarsal bone
28 Head of 1st metatarsal bone
29 Plantar tarsometatarsal ligaments
30 Plantar calcaneonavicular ligament
31 Sustentaculum tali
32 Calcaneus
33 Medial malleolus
34 Medial or deltoid ligament of ankle (posterior part)
35 Talus



Longitudinal section through the foot at the level of first phalanx.



Sagittal section through the foot
(MR-Scan after A. Heuck, G. Luttke and J. W. Rohen, 1994).



Talocalcaneonavicular joint.
The talus has been rotated to show the articular surfaces of the joint.

1 Tibia
2 Deep flexor muscles
3 Superficial flexor muscles
4 **Talocrural joint**
5 Interosseous talocalcaneal ligament
6 **Subtalar joint**
7 Calcaneal or Achilles tendon and bursa
8 Calcaneus
9 Vessels and nerves of foot
10 Talus
11 **Talocalcaneonavicular joint**
12 Navicular bone
13 **Cuneonavicular joint**
14 Intermediate cuneiform bone
15 **Tarsometatarsal joints**
16 Metatasal bones
17 **Metatarsophalangeal** and **interphalangeal joints**
18 Quadratus plantae muscle with flexor tendons
19 Flexor digitorum brevis muslce
20 Plantar aponeurosis
21 Articular capsules of interphalangeal joints
22 Articular capsules of metatarsophalangeal joints
23 Articular surface of navicular bone
24 Plantar calcaneonavicular ligament
25 Middle talar articular surface of calcaneus
26 Navicular articular surface of talus
27 Anterior and middle calcaneal surfaces of talus
28 Posterior calcaneal surface of talus
29 Dorsal tarsometatarsal ligaments
30 Talonavicular ligament
31 Bifurcate ligament
32 Anterior talar articular surface of calcaneus
33 Posterior talar articular surface of calcaneus
34 Axis for inversion and eversion
35 Tendon of tibialis posterior muscle
36 Tendon of flexor hallucis longus muscle
37 Flexor hallucis brevis muscle
38 Sesamoid bone
39 Cuboid bone



Extensor and adductor muscles of thigh, right thigh (anterior aspect).



Quadriceps muscle and superficial layer of adductor muscles, right thigh (anterior aspect). The sartorius muscle has been divided.



Course of extensor muscles of thigh and muscles inserting with common tendon on tibia.

1 Anterior superior iliac spine
2 Inguinal ligament
3 Iliopsoas muscle
4 Femoral artery
5 Tensor fasciae latae muscle
6 Sartorius muscle
7 **Rectus femoris muscle**
8 Iliotibial tract
9 Vastus lateralis muscle
10 Patella
11 Patellar ligament
12 Aponeurosis of external abdominal oblique muscle
13 Spermatic cord
14 Femoral vein

15 **Pectineus muscle**
16 **Adductor longus muscle**
17 Gracilis muscle
18 Vastus medialis muscle
19 Common tendon of sartorius, gracilis, and semitendinosus muscles (pes anserinus)
20 **Adductor brevis muscle**
21 Femoral artery
22 Femoral vein
23 Saphenous nerve
} entering the adductor canal
24 Fascia of adductor canal
25 Vastus intermedius muscle
26 Articularis genus muscle
27 Semitendinosus muscle



Deep layer of adductor muscles. Adductor magnus muscle (anterior aspect). Pectineus, adductor longus and brevis muscles have been divided.



Course of adductor muscles. (Schematic drawing.)

1 Pectineus muscle (blue)
2 Adductor minimus muscle (red)
3 Adductor brevis muscle (blue)
4 Adductor longus muscle (blue)
5 Adductor magnus muscle (red)
6 Gracilis muscle (blue)
7 Iliopsoas muscle (red/blue)



Iliopsoas and adductor muscles; deepest layer (anterior aspect). Pectineus, adductor longus and brevis, rectus femoris muscles have been divided.

1 Anterior superior iliac spine
2 Inguinal ligament
3 **Iliopsoas muscle**
4 Sartorius muscle
5 Obturator externus muscle
6 Tensor fasciae latae muscle
7 Rectus femoris muscle
8 Iliotibial tract
9 Adductor longus muscle (divided)
10 Vastus lateralis muscle
11 Vastus medialis muscle
12 Pectineus muscle (divided)
13 Adductor minimus muscle
14 Adductor brevis muscle (cut)
15 **Adductor magnus**
16 Gracilis muscle
17 Adductor hiatus
18 Vastoadductor membrane
19 Diaphragm
20 Quadratus lumborum muscle
21 **Iliacus muscle**
22 Vastus intermedius muscle
23 Aorta in aortic hiatus
24 Twelfth rib
25 **Psoas minor muscle**
26 **Psoas major muscle**
27 Iliopectineal arch


1
2
3
4
5
6
7
8
9
10
11

Gluteal muscles, superficial layer (posterior aspect).


7
8
18
12
10
13
14
15
16
10
19
6
10
17

Gluteal muscles, deeper layer (posterior aspect).


12
13
14
15
19
21
6
40
22
17
23



Course of gluteal muscles
(posterior aspect; schematic drawing).

◁

Course of gluteal muscles (deeper layer) **and of ischiocrural muscles** (posterior aspect).
Sartorius muscle is indicated by dotted line (schematic drawing).



Flexors of the right thigh, superficial layer (dorsal aspect).

1	Thoracolumbar fascia
2	Spinous processes of lumbar vertebrae
3	Coccyx
4	Anus
5	Adductor magnus muscle
6	Semitendinosus muscle
7	Iliac crest
8	**Gluteus medius muscle**
9	Greater trochanter
10	**Gluteus maximus muscle**
11	Iliotibial tract
12	Piriformis muscle
13	Superior gemellus muscle
14	Obturator internus muscle
15	Inferior gemellus muscle
16	Ischial tuberosity
17	**Biceps femoris muscle**
18	Tensor fasciae latae muscle
19	Quadratus femoris muscle
20	**Gluteus minimus muscle**
21	Sartorius muscle
22	Semimembranosus muscle
23	Tendon of gracilis muscle
24	Tibial nerve
25	Medial head of gastrocnemius muscle
26	Common peroneal nerve
27	Tendon of biceps femoris muscle
28	Lateral head of gastrocnemius muscle
29	Rectus femoris muscle
30	Vastus medialis muscle
31	Vastus intermedius muscle
32	Vastus lateralis muscle
33	Sciatic nerve
34	Gluteus maximus muscle (insertion)
35	Great saphenous vein
36	Femoral artery
37	Femoral vein
38	Adductor longus muscle
39	Femur
40	Gracilis muscle
41	Septum between semitendinosus and semimembranosus muscles



Cross section of right thigh (inferior aspect). Anterior side on top.



Dorsal muscles of right thigh (posterior aspect).
The gluteus maximus muscle has been cut and reflected.



Dorsal muscles of right thigh (posterior aspect).
The gluteus maximus muscle and the long head of biceps femoris muscle have been divided and displaced.

1	Gluteus maximus muscle (divided)
2	Position of coccyx
3	Piriformis muscle
4	Superior gemellus muscle
5	Obturator internus muscle
6	Inferior gemellus muscle
7	Ischial tuberosity
8	Quadratus femoris muscle
9	Semitendinosus muscle with intermediate tendon
10	Semimembranosus muscle
11	Medial head of gastrocnemius muscle
12	Gluteus medius muscle
13	Adductor minimus muscle
14	Adductor magnus muscle
15	Long head of biceps femoris muscle
16	Iliotibial tract
17	Short head of biceps femoris muscle
18	Popliteal surface of femur
19	Plantaris muscle
20	Tendon of biceps femoris muscle
21	Lateral head of gastrocnemius muscle
22	Membranous part of semimembranosus muscle



Flexor muscles of right leg (posterior aspect).



Flexor muscles of right leg (posterior aspect). Both heads of the gastrocnemius muscle have been cut and reflected.



Flexor muscles of the leg (right side).

1 Semitendinosus muscle
2 Semimembranosus muscle
3 Sartorius muscle
4 Tendon of gracilis muscle
5 **Medial head of gastrocnemius muscle**
6 Common tendon of gracilis, sartorius, and semitendinosus muscles
7 Calcaneal or Achilles tendon
8 Medial malleolus
9 Calcaneal tuberosity
10 Tibial nerve
11 Biceps femoris muscle
12 Plantaris muscle
13 Common peroneal nerve
14 **Lateral head of gastrocnemius muscle**
15 **Soleus muscle**
16 Peroneus longus and brevis muscles
17 Lateral malleolus
18 Popliteal fossa
19 Tibial nerve and posterior tibial artery
20 Popliteus muscle
21 Tendinous arch of soleus muscle
22 Femur
23 Fibula
24 Tibia



Muscles of right leg and foot (medial aspect).



Popliteal region with plantaris and soleus, right side (dorsal aspect). Notice the insertion of the tendon of semimembranosus.

1 Vastus medialis muscle
2 Patella
3 Patellar ligament
4 Tibial tuberosity
5 Tibia
6 Tendons of deep flexor muscles (from anterior to posterior: 1. tibialis posterior; 2. flexor digitorum longus; 3. flexor hallucis longus muscles)
7 Flexor retinaculum
8 Tendon of tibialis anterior muscle
9 Tendon of extensor hallucis longus muscle
10 Abductor hallucis muscle
11 Semimembranosus muscle
12 Sartorius muscle
13 Tendon gracilis muscle
14 Tendon of semitendinosus muscle
15 Common tendon of gracilis, semitendinosus and sartorius muscles
16 **Medial head of gastrocnemius muscle**
17 **Soleus muscle**
18 Calcaneal or Achilles tendon
19 Calcaneus muscle
20 Tendon of flexor hallucis longus muscle
21 Quadriceps femoris muscle (divided)
22 Tendon of adductor magnus muscle (divided)
23 Medial condyle of femur
24 Popliteal artery and vein, tibial nerve
25 Tibia
26 Femur
27 Lateral epicondyle of femur
28 Oblique popliteal ligament
29 Lateral (fibular) collateral ligament
30 **Plantaris muscle**
31 Tendon of biceps femoris muscle (divided)
32 Tendinous arch of soleus muscle



Muscles of right leg and foot (lateral aspect).



Right foot with synovial sheaths of extensor muscles (dorsal aspect). The synovial sheaths have been injected with blue solution.

1 Common peroneal nerve
2 Head of fibula
3 Lateral head of gastrocnemius muscle
4 Soleus muscle
5 Peroneus longus muscle
6 Peroneus brevis muscle
7 Calcaneal or Achilles tendon
8 Lateral malleolus muscle
9 Tendon of peroneus longus muscle
10 Extensor digitorum brevis muscle
11 Tendon of peroneus brevis muscle
12 Patella
13 Patellar ligament
14 Tuberosity of tibia
15 Tibialis anterior muscle
16 Extensor digitorum longus muscle
17 Superior extensor retinaculum
18 Inferior extensor retinaculum
19 Tendon of extensor hallucis longus muscle
20 Tendons of extensor digitorum longus muscle
21 Common synovial sheath of extensor digitorum longus muscle
22 Tendon of peroneus tertius muscle to the lateral margin of foot
23 Tendons of extensor digitorum brevis muscle
24 Medial malleolus
25 Synovial sheath of tendon of tibialis anterior muscle
26 Tendon of tibialis anterior muscle
27 Synovial sheath of tendon of extensor hallucis longus muscle



1 Medial condyle of femur
2 Popliteus muscle
3 Flexor digitorum longus muscle
4 Crosssing of tendons in leg
5 Tendon of tibialis posterior muscle
6 Tendon of flexor digitorum longus muscle
7 Medial malleolus
8 Lateral condyle of femur
9 Head of fibula
10 Tibialis posterior muscle
11 Flexor hallucis longus muscle
12 Peroneus longus muscle
13 Peroneus brevis muscle
14 Tendon of flexor hallucis longus muscle
15 Calcaneal tendon (divided)
16 Lateral malleolus

Deep flexor muscles of right leg (posterior aspect).



1 Popliteus muscle (blue)
2 Flexor digitorum longus muscle (blue)
3 Tibialis posterior muscle (red)
4 Crossing of tendons in leg
5 Flexor hallucis longus muscle (blue)
6 Crossing of tendons in sole

Course of deep flexor muscle of leg. (Schematic drawing.)

1 Medial condyle of femur
2 Tibia
3 Flexor digitorum longus muscle
4 Crossing of tendons in leg
5 Tendon of tibialis posterior muscle
6 Abductor hallucis muscle
7 Tendon of flexor hallucis longus muscle
8 Lateral condyle of femur
9 Head of fibula
10 Tibialis posterior muscle
11 Tendon of flexor digitorum longus muscle
12 Flexor retinaculum
13 Calcaneal tendon
14 Calcaneal tuberosity
15 Crossing of tendons in sole
16 Quadratus plantae muscle
17 Tendons of flexor digitorum longus muscle
18 Tendon of tibialis anterior muscle
19 Area of insertion of tibialis posterior muscle
20 Lumbrical muscles
21 Flexor hallucis longus muscle



Deep flexor muscles of right leg and foot (posterior oblique medial aspect). Felxor digitorum brevis and flexor hallucis longus muscles have been removed.



Sole of foot; tendons of long flexor muscles (oblique medial and inferior aspect).



Extensor muscles of right leg and foot (oblique anterolateral aspect).



Extensors of the right leg and foot (anterior aspect). Part of the tibialis anterior muscle has been removed.

1 Patella
2 Patellar ligament
3 Anterior margin of tibia
4 Tibialis anterior muscle
5 Extensor digitorum longus muscle
6 Superior extensor retinaculum
7 Inferior extensor retinaculum
8 Tendon of peroneus tertius muscle
9 Extensor digitorum brevis muscle
10 Tendons of extensor digitorum longus muscle
11 Soleus
12 Extensor hallucis longus muscle
13 Medial malleolus
14 Tendon of tibialis anterior muscle
15 Extensor hallucis brevis muscle
16 Tendon of extensor hallucis longus muscle
17 Common tendon of gracilis, semitendinosus and sartoris muscles
18 Tibia



Extensor muscles of the leg (right side).



Sole of foot, first layer of muscles (from below). The plantar aponeurosis and the fasciae of the superficial muscles have been removed.



Sole of foot, plantar aponeurosis (from below).



Course of abductor and adductor muscles of foot. (Schematic drawing.)
Red arrows = abduction.
Black arrows = adduction.

1 Longitudinal bands of plantar aponeurosis
2 Plantar aponeurosis
3 Position of tuberosity of 5th metatarsal bone
4 Muscles of 5th toe with fascia
5 Calcaneal tuberosity
6 Muscles of great toe with fascia
7 Tendons of flexor digitorum longus muscle
8 Tendons of flexor digitorum brevis muscle
9 Lumbrical muscle
10 Flexor digiti minimi brevis muscle
11 Flexor digitorum brevis muscle
12 Tendon of peroneus longus muscle
13 Abductor digiti minimi muscle
14 Tendon of flexor hallucis longus muscle
15 Flexor hallucis brevis muscle
16 Abductor hallucis muscle
17 Plantar aponeurosis (cut)
18 Peroneus longus muscle
19 Peroneus brevis muscle
20 Tibialis anterior muscle
21 Extensor hallucis longus muscle
22 Extensor digitorum longus muscle

1 Plantar interossei muscles (black)
2 Abductor digiti minimi muscles (red)
3 Dorsal interossei muscle (red)
4 Transverse head of adductor muscle (black)
5 Oblique head of adductor muscle (black)
6 Abductor hallucis muscle (red)



Muscles of sole of foot, second layer (from below). The flexor digitorum brevis muscle has been divided.



Muscles of sole of foot, second layer (from below). The tendons of the flexor muscles and the crossing of tendons are displayed. The flexor digitorum brevis muscle has been divided and reflected.

1 Tendons of flexor digitorum brevis muscle
2 Tendons of flexor digitorum longus muscle
3 Lumbrical muscles
4 Interossei muscles
5 Flexor digiti minimi brevis muscle
6 Abductor digiti minimi muscle
7 Quadratus plantae muscle
8 Calcaneal tuberosity
9 Tendon of flexor hallucis longus muscle
10 Flexor hallucis brevis muscle
11 Abductor hallucis muscle
12 Flexor digitorum brevis muscle (divided)
13 Tuberosity of 5th metatarsal bone
14 Tendon of peroneus longus muscle
15 Transverse head of adductor hallucis muscle
16 Crossing of tendons in sole of foot
17 Medial malleolus
18 Plantar aponeurosis (divided)



Muscles of sole of foot, third layer (from below). The flexor digitorum brevis muscle has been removed, and the quadratus plantae muscle and the abductor hallucis and digiti minimi muscles have been divided.



Muscles of sole of foot, fourth layer (from below). The interosseous muscles and the canal for the tendon of peroneus longus muscle are shown.

1 Tendons of flexor digitorum brevis muscle
2 Transverse head of adductor hallucis muscle
3 Abductor digiti minimi muscle
4 Interosseous muscles
5 Flexor digiti minimi brevis muscle
6 Opponens digiti minimi muscle
7 Tendon of peroneus longus muscle
8 Quadratus plantae muscle with tendon of flexor digitorum longus muscle
9 Calcaneal tuberosity
10 Tendons of flexor hallucis longus muscle (divided)
11 Tendon of flexor digitorum longus muscle
12 Flexor hallucis brevis muscle
13 Oblique head of adductor hallucis muscle
14 Abductor hallucis muscle (cut)
15 Tendon of tibialis posterior muscle
16 Dorsal interossei muscles
17 Plantar interossei muscles
18 Tuberosity of 5th metatarsal bone
19 Tendon of flexor digitorum longus muscle (crossing of plantar tendons)
20 Long plantar ligament


22
1
23
2
24
25
26
27
28
48
29
30
13
14
31
32
33
34
35
36
25
37
38

Main arteries and nerves of right thigh (anterior aspect). Sartorius muscle has been divided and reflected. The femoral vein has been partly removed to show the deep femoral artery. Notice: the vessels enter the adductor canal to reach the popliteal fossa.


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21

Main arteries of lower extremity, right side (ventral aspect). (Schematic drawing.)



Arteries of the right leg (posterior aspect).

1 **Femoral artery**
2 **Profunda femoris artery**
3 Ascending branch of lateral circumflex femoral artery
4 Descending branch of lateral circumflex femoral artery
5 Lateral superior genicular artery
6 Popliteal artery
7 Lateral inferior genicular artery
8 **Anterior tibial artery**
9 **Peroneal artery**
10 **Lateral plantar artery**
11 Arcuate artery with dorsal metatarsal arteries
12 **Plantar arch** with plantar metatarsal arteries
13 Medial circumflex femoral artery
14 Profunda femoris artery with perforating arteries
15 Descending genicular artery
16 Medial superior genicular artery
17 Middle genicular artery
18 Medial inferior genicular artery
19 **Posterior tibial artery**
20 **Dorsalis pedis artery**
21 **Medial plantar artery**
22 Superficial and deep circumflex iliac arteries
23 **Femoral nerve**
24 Lateral circumflex femoral artery
25 Sartorius muscle (cut and reflected)
26 Rectus femoris muscle
27 Vastus medialis muscle
28 Inguinal ligament
29 **Femoral vein** (cut)
30 External pudendal artery and vein
31 Adductor longus muscle
32 Great saphenous vein
33 Obturator artery and nerve
34 Gracilis muscle
35 Saphenous nerve
36 Tendinous wall of adductor canal
37 Anterior cutaneous branch of femoral nerve
38 Infrapatellar branch of saphenous nerve
39 Popliteal vein
40 **Tibial nerve**
41 Medial head of gastrocnemius muscle
42 Biceps femoris muscle
43 Common peroneal nerve
44 Lateral head of gastrocnemius muscle
45 Plantaris muscle
43 Soleus muscle
47 Flexor hallucis longus muscle
48 Spermatic cord



Superficial veins of lower limb, right side (medial anterior aspect). The veins have been injected with red solution.

Main veins of lower limb, right side (anterior aspect). (Schematic drawing.)



1 Superficial epigastric vein
2 Superficial circumflex iliac vein
3 Femoral vein
4 **Small saphenous vein**
5 External iliac vein
6 External pudendal vein
7 **Great saphenous vein**
8 Dorsal venous arch
9 Saphenous opening with femoral vein
10 Venous anastomoses of small saphenous vei with great saphenous vein
11 Patella
12 Penis
13 Medial malleolus
14 Popliteal fossa
15 Perforating veins
16 Lateral malleolus
17 Dorsal digital veins of foot
18 Dorsal venous arch of foot
19 Dorsal metatarsal veins of foot
20 Anterior tibial artery and veins
21 Tibia
22 **Posterior tibial artery and veins**
23 Fibula
24 Peroneal artery and vein
25 Deep layer of crural fascia
26 Superficial layer of crural fascia
27 Perforating veins I-III (of Cockett)
28 **Tibial nerve**
29 **Arcuate vein**
30 **Saphenous nerve**
31 Medial dorsal cutaneous nerve (branch of superficial peroneal nerve)
32 Posterior tibial vein



▷

Medial malleolar region. Dissection of tibial nerve, posterior tibial vessels, and great saphenous vein (veins injected with blue resin).



Superficial veins of leg (posterior aspect; injected with blue resin).


7
26
27
15
27
4
27
13

Superficial veins of leg. The perforating veins of Cockett have been dissected.


21
28
27
22
29
27
4
27
13

Veins of leg. The anastomoses between superficial and deeper veins are dissected.


7
16
13
18
19
17

Anastomoses between superficial and deep veins of the leg (after Aigner). (Schematic drawing.) Arrows: directions of blood flow. ▷

◁

Superficial veins on dorsum of foot (injected with blue resin).


20
23
26
24
21
25
4
7
22
15



1 Transversus abdominis muscle
2 Iliohypogastric nerve
3 Ilioinguinal nerve
4 **Femoral nerve**
5 Lateral femoral cutaneous nerve
6 Obturator nerve
7 Obturator internus muscle
8 Pubic bone (cut edge)
9 Levator ani muscle (remnant)
10 Dorsal nerve of penis
11 Posterior scrotal nerves
12 Adductor longus muscle
13 Gracilis muscle
14 Body of 4th lumbar vertebra
15 Cauda equina
16 Intervertebral disc
17 Sacral promontory
18 Sympathetic trunk
19 Sacrum
20 **Lumbosacral trunk**
21 **Sciatic plexus**
22 Coccyx
23 Sacrospinous ligament
24 **Pudendal nerve**
25 Inferior rectal nerves
26 Perineal nerves
27 Subcutaneous fat tissue of gluteal region

Lumbosacral plexus in situ, right side (medial aspect).
Pelvic organs with peritoneum and part of the levator ani muscle have been removed.



Nerves of lower limb, right side (lateral aspect). (Schematic drawing.)

1 Subcostal nerve
2 Iliohypogastric nerve
3 Ilioinguinal nerve
4 Lateral femoral cutaneous nerve
5 Genitofemoral nerve
6 **Pudendal nerve**
7 **Femoral nerve**
8 Obturator nerve
9 **Sciatic nerve**
10 Lumbar plexus (L_1–L_4) } lumbosacral plexus
11 Sacral plexus (L_4–S_4) } lumbosacral plexus
12 "Pudendal" plexus (S_2–S_4) } lumbosacral plexus
13 Inferior cluneal nerve
14 Posterior femoral cutaneous nerve
15 Common peroneal nerve
16 **Tibial nerve**
17 Lateral sural cutaneous nerve
18 Medial and lateral plantar nerves
19 Saphenous nerve
20 Infrapatellar branch of saphenous nerve
21 **Deep peroneal nerve**
22 **Superficial peroneal nerve**



Main branches of lumbosacral plexus (ventral aspect). (Schematic drawing.)



Spinal cord with intercostal nerves. Inferior thoracic region (anterior aspect). Anterior portion of thoracic vertebrae removed, dural sheath opened and spinal cord slightly reflected to the right to display the dorsal and ventral roots.

1	Dura mater	6	Eleventh rib	10	Anterior root filaments
2	**Spinal cord**	7	**Intercostal nerve**	11	Spinal (dorsal root) ganglion
3	Costotransverse ligament	8	Collateral branch of intercostal nerve	12	Posterior root filaments
4	Innermost intercostal muscle	9	Intercostal nerve (entering the intermuscular interval)	13	Arachnoid mater and denticulate ligament
5	Vertebral arches (cut surfaces)			14	Anterior spinal artery


1
2
3
4
5
6
7
6
8
9

Spinal cord and lumbar plexus in situ (anterior aspect).


C1
1
2
C4
4
C8
7
1
D2
D4
5
D7
7
D10
10
L1
L4
12
S2
1
4
C1–C8
D1–D12
L1–L5
S1–S5
Co

Organization of spinal cord segments in relation to the vertebral column (anterior aspect). C = cervical; D = thoracic; L = lumbar; S = sacral segments; Co = coccygeal bone.

1 Conus medullaris
2 Filum terminale
3 Subcostal nerve
4 Iliohypogastric nerve
5 Ilioinguinal nerve
6 Genitofemoral nerve
7 Lateral femoral cutaneous nerve
8 Femoral nerve
9 Obturator nerve


1
2
3
4
5
6
4
7
8
9
10
11
12
13
14
15
16
17
18

Cutaneous nerves and veins of thigh (anterior aspect).


6
11
3
14
8
21
18
17
19
22
20
23
29
24

Cutaneous nerves of lower limb (anterior aspect). (Schematic drawing.)

1 Inguinal ligament
2 Superficial circumflex iliac vein
3 Femoral branch of genitofemoral nerve
4 Superficial inguinal lymph nodes
5 Saphenous opening with femoral artery and vein
6 Lateral femoral cutaneous nerve
7 Great saphenous vein
8 Anterior cutaneous branches of femoral nerve
9 Patella
10 Terminal branches of subcostal nerve
11 Terminal branches of iliohypogastric nerve
12 Superficial inguinal ring
13 External pudendal vein
14 Spermatic cord with genital branch of genitofemoral nerve
15 Penis with superficial dorsal vein of penis
16 Testis and its coverings
17 Saphenous nerve
18 Infrapatellar branch of saphenous nerve
19 Lateral sural cutaneous nerves
20 Intermediate dorsal cutaneous branch of superficial peroneal nerve
21 Cutaneous branch of obturator nerve
22 Superficial peroneal nerve
23 Medial dorsal cutaneous branch of superficial peroneal nerve
24 Deep peroneal nerve
25 **Femoral nerve**
26 **Femoral artery**
27 Superficial epigastric vein
28 **Femoral vein**
29 Lateral dorsal cutaneous branch of sural nerve
30 **Inguinal nodes** (enlarged)
31 Lymphatic vessels
32 Sartorius muscle



Cutaneous nerves and veins of thigh (anterior aspect). The fascia lata and fasciae of the thigh muscles have been removed.



Inguinal nodes with lymphatic vessels (anterior aspect).



Anterior region of right thigh (anterior aspect).
The fascia lata has been removed, and the sartorius muscle has been slightly reflected.



Anterior region of right thigh (anterior aspect).
The fascia lata has been removed, and the sartorius muscle has been divided.

1 Anterior superior iliac spine
2 Inguinal ligament
3 **Deep circumflex iliac artery**
4 Iliopsoas muscle
5 Tensor fasciae latae muscle
6 **Femoral nerve**
7 **Lateral circumflex femoral artery**
8 Sartorius muscle
9 Rectus femoris muscle
10 Iliotibial tract
11 Vastus lateralis muscle
12 Anterior sheath of rectus abdominis muscle
13 Inferior epigastric artery
14 Spermatic cord
15 **Femoral artery**
16 Pectineus muscle
17 **Femoral vein**
18 Great saphenous vein (divided)
19 Adductor longus muscle
20 **Saphenous nerve**
21 Muscular branch of femoral nerve
22 Gracilis muscle
23 Vastus medialis muscle
24 Ascending branch of lateral circumflex femoral artery
25 Descending branch of lateral circumflex femoral artery
26 Medial circumflex femoral artery
27 Adductor longus muscle
28 Penis
29 Entrance to adductor canal
30 Vastoadductory lamina of fascia beneath sartorius muscle



Anterior region of right thigh (anterior aspect). The fascia lata has been removed. Sartorius muscle, pectineus muscle and femoral artery have been cut to display the deep femoral artery with its branches. The rectus femoris muscle has been slightly reflected.



Anterior region of right thigh (anterior aspect). The sartorius, pectineus, adductor longus and rectus femoris muscles have been divided and reflected. The greater part of the femoral artery has been removed.

1 Anterior superior iliac spine
2 Inguinal ligament
3 Tensor fasciae latae muscle
4 Deep circumflex iliac artery
5 Iliopsoas muscle
6 Sartorius muscle (cut)
7 **Femoral nerve**
8 **Lateral circumflex femoral artery**
9 Ascending branch of lateral circumflex femoral artery
10 Descending branch of lateral circumflex femoral artery
11 Rectus femoris muscle
12 Vastus medialis muscle
13 Vastus lateralis muscle
14 Femoral vein
15 Pectineus muscle (cut)
16 Femoral artery (cut)
17 **Obturator nerve**
18 **Profunda femoris artery**
19 Ascending branch of medial circumflex femoral artery
20 **Medial circumflex femoral artery**
21 Adductor longus muscle
22 Gracilis muscle
23 Saphenous nerve
24 Distal part of vastoadductory lamina
25 Rectus femoris muscle with muscular branch of femoral nerve
26 Adductor longus muscle (divided)
27 Posterior branch of obturator nerve
28 Anterior branch of obturator nerve
29 Point at which perforating artery branches off from profunda femoris artery
30 Muscular branch to vastus medialis muscle



1. Iliac crest
2. Gluteus maximus muscle
3. **Middle cluneal nerves**
4. Anococcygeal nerves
5. Perineal branch of posterior femoral cutaneous nerve
6. Adductor magnus muscle
7. **Superior cluneal nerves**
8. Position of greater trochanter
9. **Inferior cluneal nerves**
10. Semitendinosus muscle
11. Posterior femoral cutaneous nerve
12. Long head of biceps femoris muscle

Gluteal region, right side (posterior aspect).

A **Suprapiriform foramen** of greater sciatic foramen

Superior gluteal artery, vein and nerve

B **Infrapiriform foramen** of greater sciatic foramen

Sciatic nerve
Inferior gluteal artery, vein and nerve
Posterior femoral cutaneous nerve
Internal pudendal artery and vein
Pudendal nerve

C **Lesser sciatic foramen**

Pudendal nerve
Internal pudendal artery and vein



Gluteal region, right side (posterolateral aspect). Location of sciatic foramina in relation to the bones. (Schematic drawing.)

Red lines

1. **Spine-tuber line.** In the middle of this line the infrapiriform foramen is situated
2. **Spine-trochanter line.** In the upper third the suprapiriform foramen is located
3. **Tuber-trochanter line.** Between the middle and posterior third, the ischiadic nerve can be found

Other structures

4. Posterior superior iliac spine
5. Iliac crest
6. Greater trochanter
7. Ischial tuberosity
8. Sacrum



Gluteal region, right side (dorsal aspect). The gluteus maximus and gluteus medius muscles have been divided and reflected. Notice the position of the foramina above and below piriformis muscles and the lesser sciatic foramen.

1 Iliac crest
2 Gluteus maximus muscle (cut)
3 Inferior gluteal nerve
4 Piriformis muscle
5 Muscular branches of inferior gluteal artery
6 Pudendal nerve and internal pudendal artery within the **lesser sciatic foramen** (entrance to the pudendal canal)
7 Sacrotuberous ligament
8 Inferior cluneal nerve
9 Inferior rectal nerves
10 Inferior rectal arteries
11 Perforating cutaneous nerve
12 Long head of biceps femoris muscle

13 Gluteus medius muscle (cut)
14 Deep branch of superior gluteal artery
15 Gluteus minimus muscle
16 Superior gluteal nerve
17 **Suprapiriform foramen** } greater sciatic foramen
18 **Infrapiriform foramen** }
19 Tendon of obturator internus and superior gemellus muscles
20 Posterior femoral cutaneous nerve
21 Inferior gemellus muscle
22 **Sciatic nerve**
23 Quadratus femoris muscle
24 Tensor fasciae latae muscle



Cutaneous nerves of thigh (posterior aspect).
The fascia lata and the fasciae of muscles have been removed.

1 Middle cluneal nerves
2 Perineal branch of posterior femoral cutaneous nerve
3 **Posterior femoral cutaneous nerve**
4 Semimembranosus muscle
5 Semitendinosus muscle
6 **Tibial nerve**
7 Medial sural cutaneous nerve
8 **Small saphenous vein**
9 Medial head of gastrocnemius muscle
10 Gluteus maximus muscle
11 **Inferior cluneal nerve**
12 Cutaneous veins
13 Long head of biceps femoris muscle
14 Iliotibial tract
15 Short head of biceps femoris muscle
16 Popliteal fossa
17 Lateral sural cutaneous nerve
18 Lateral head of gastrocnemius muscle
19 **Common peroneal nerve**
20 Tendon of biceps femoris muscle
21 Inferior gluteal nerve
22 Sacrotuberous ligament
23 Inferior rectal branches of pudendal nerve
24 Anus
25 Gluteus medius muscle
26 Piriformis muscle
27 **Sciatic nerve**
28 Inferior gluteal artery
29 Gluteus maximus muscle (cut)
30 Quadratus femoris muscle
31 Sciatic nerve dividing into its two branches: the common peroneal nerve and the tibial nerve
32 Muscular branches of sciatic nerve to hamstring muscles
33 **Popliteal artery**
34 **Popliteal vein**
35 Small saphenous vein (cut)
36 Long head of biceps femoris muscle (cut)
37 **Superficial peroneal nerve**


25
21
26
27
28
22
29
30
23
2
3
24
13
14
5
31
4
6
19
18
9
7
17

Posterior femoral region and gluteal region, right side (posterior aspect). The gluteus maximus muscle has been divided and reflected.


25
21
26
27
22
28
30
23
29
3
14
32
36
5
31
33
4
34
19
6
35
37
9
17
7

Posterior femoral region and gluteal region, right side (posterior aspect). The gluteus maximus muscle and the long head of biceps femoris muscle have been divided and reflected.



Anterior region of right knee; cutaneous nerves and veins (anterior aspect).



Posterior region of right kneee; cutaneous nerves and veins (posterior aspect).

1 Fascia lata
2 Terminal branches of anterior cutaneous branches of femoral nerve
3 Venous network around knee
4 Position of head of fibula
5 Superficial crural fascia
6 **Great saphenous vein**
7 Patella
8 Position of medial epicondyle of femur
9 Saphenous nerve
10 **Infrapatellar branches of saphenous nerve**
11 Patellar ligament
12 Position of tuberosity of tibia

1 Cutaneous veins (tributaries of great saphenous vein)
2 **Great saphenous vein**
3 Cutaneous branch of femoral nerve
4 Position of medial epicondyle of femur
5 Position of small saphenous vein
6 Fascia lata
7 Terminal branches of **posterior femoral cutaneous nerve**
8 Cutaneous veins of popliteal fossa
9 Position of head of fibula
10 Superficial layer of fascia cruris
11 Lateral sural cutaneous nerve



Right leg, posterior crural region (posterior aspect). The gastrocnemius muscle has been divided and reflected.



Right leg, posterior crural region, deep layer (posterior aspect). The gastrocnemius and the soleus muscles have been divided and reflected.

1 Semitendinosus muscle
2 Gracilis muscle
3 Semimembranosus muscle
4 Sartorius muscle
5 Tendon of semitendinosus muscle
6 Position of medial condyle of femur
7 Muscular branches of tibial nerve
8 Sural arteries and veins
9 Tendon of semimembranosus muscle
10 Common tendon of gracilis, semitendinosus and sartorius muscles
11 Medial head of gastrocnemius muscle
12 Biceps femoris muscle
13 Muscular branch of popliteal artery
14 **Popliteal artery**
15 **Popliteal vein**
16 **Tibial nerve**
17 **Common peroneal nerve**
18 Lateral head of gastrocnemius muscle
19 Medial sural cutaneous nerve
20 Medial superior genicular artery
21 Medial head of gastrocnemius muscle (cut and reflected)
22 Medial inferior genicular artery
23 Soleus muscle
24 Tendon of plantaris muscle
25 Lateral superior genicular artery
26 Lateral inferior genicular artery
27 Plantaris muscle



Right leg, popliteal fossa, deep layer (posterior aspect). The muscles have been reflected to display the genicular arteries.



Right leg, popliteal fossa, deepest layer (posterior aspect). Tibial nerve and popliteal vein have been partly removed and a portion of the soleus muscle was cut away to display the anterior tibial artery.

1 Semitendinosus muscle
2 Semimembranosus muscle
3 Medial superior genicular artery
4 **Popliteal artery**
5 Medial head of gastrocnemius muscle
6 Middle genicular artery
7 Muscular branches
8 Medial inferior genicular artery
9 Tendon of plantaris muscle
10 **Tibial nerve** (cut)
11 Biceps femoris muscle
12 Popliteal vein (cut)
13 Lateral superior genicular artery
14 Lateral inferior genicular artery
15 Lateral head of gastrocnemius muscle
16 **Common peroneal nerve**
17 Head of fibula
18 Lateral sural cutaneous nerves
19 Soleus muscle
20 Medial sural cutaneous nerve
21 **Anterior tibial artery**
22 **Posterior tibial artery**
23 Lateral sural cutaneous nerve



Right leg. Cutaneous veins and nerves (posterior aspect).



Right leg. Cutaneous nerves and veins (posterior aspect). The superficial layer of the crural fascia has been removed.



Cutaneous veins and nerves of the right leg (anterior-medial aspect; veins are colored).

1 **Great saphenous vein**
2 Venous anastomosis between small and great saphenous veins
3 Medial malleolus
4 Popliteal fossa
5 Position of head of fibula
6 Lateral sural cutaneous nerve
7 **Small saphenous vein**
8 **Sural nerve**
9 Calcaneal tendon
10 Lateral malleolus
11 Semitendinosus muscle
12 Medial head of gastrocnemius muscle
13 Saphenous nerve
14 **Common peroneal nerve**
15 Medial sural cutaneous nerve
16 Perforating veins
17 Superficial peroneal nerve
18 Dorsal venous arch
19 Intermediate dorsal cutaneous nerve
20 **Infrapatellar branches of saphenous nerve**
21 Terminal branches of saphenous nerve
22 Medial dorsal cutaneous nerve


1
2
3
4
5
6
7
5
8
9
5
10
11
12
13
7
14
15
16
17
18
19
20

Right popliteal fossa, middle layer (posterior aspect). The cutaneous veins and nerves have been removed.


2
1
21
5
6
7
8
22
23
24
5
10
25
11
12
13
7
14
5
26
27
28
18
20

Right popliteal fossa, deep layer (posterior aspect). The medial head of gastrocnemius muscle has been divided and reflected.



Right leg, posterior crural region, deepest layer (posterior aspect). Triceps surae (gastrocnemius and soleus) and flexor hallucis longus muscles have been cut and reflected.

1 Semimembranosus muscle
2 Semitendinosus muscle
3 **Popliteal vein**
4 Popliteal artery
5 **Tibial nerve**
6 Small saphenous vein (cut)
7 Muscular branch of tibial nerve
8 Medial head of gastrocnemius muscle
9 Tendon of plantaris muscle
10 **Posterior tibial artery**
11 Medial malleolus
12 Biceps femoris muscle
13 Common peroneal nerve
14 **Sural arteries**
15 Plantaris muscle
16 Lateral head of gastrocnemius muscle
17 Soleus muscle
18 Calcaneal tendon
19 Lateral malleolus
20 Calcaneal tuberosity
21 Sartorius muscle
22 **Popliteal artery**
23 Tendinous arch of soleus muscle
24 Flexor digitorum longus muscle
25 Flexor retinaculum
26 **Peroneal artery**
27 Soleus muscle
28 Flexor hallucis longus muscle
29 **Anterior tibial artery**
30 Muscular branches of tibial nerve
31 Tibialis posterior muscle
32 Communicating branch of peroneal artery
33 Tendon of tibialis anterior muscle
34 Tibia
35 Tendon of extensor hallucis longus muscle
36 Tendons of extensor digitorum longus muscle
37 Anterior tibialis artery
38 Fibula
39 Tendons of peroneus longus and brevis muscles



Cross-section of the leg, superior to the malleoli (from below).



Right leg and foot, anterior crural region and dorsum of foot; cutaneous nerves and veins (anterior aspect).



Right leg and foot; cutaneous nerves and veins (medial aspect).

1 Superficial crural fascia
2 Medial cutaneous branch of superficial peroneal nerve
3 Lateral malleolus
4 Lateral cutaneous branch of superficial peroneal nerve
5 Cutaneous branch of sural nerve
6 Position of tuberosity of tibia
7 Anterior margin of tibia
8 **Great saphenous vein**
9 Medial malleolus
10 Deep peroneal nerve
11 **Venous arch of dorsum of foot**
12 Position of patella
13 **Infrapatellar branches of saphenous nerve**
14 Saphenous nerve
15 Small saphenous vein
16 Perforating vein
17 Calcaneal tendon



Right leg and dorsum of foot; cutaneous nerves and veins (lateral aspect).

1 Position of fibula
2 **Sural nerve**
3 **Small saphenous vein**
4 Calcaneal tendon
5 Lateral calcaneal branches of sural nerve
6 Venous network at lateral malleolus
7 Cutaneous branch of sural nerve
8 Tendon of peroneus brevis muscle
9 Tendons of extensor digitorum longus muscle

10 Fascia cruris
11 Superficial peroneal nerve
12 Position of tibia
13 Lateral cutaneous branch } of **superficial peroneal nerve**
14 Medial cutaneous branch } of **superficial peroneal nerve**
15 Lateral malleolus
16 Dorsal digital nerves
17 Dorsal venous arch
18 Deep peroneal nerve


1
11
2
3
12
13
14
4
5
15
16
6
7
17
18
19
8
20
21
9
22
10
23

Right leg and dorsum of foot, middle layer (anterior lateral aspect). The extensor digitorum longus muscle has been divided and reflected laterally.


1
11
2
3
12
24
13
14
25
5
26
4
16
27
7
18
28
17
8
19
20
22
21
9
10
23

Right leg, deep layer (anterior lateral aspect). The extensor digitorum longus and the peroneus longus muscle have been divided or removed. The common peroneal nerve has been elevated to show its course around the head of fibula.



Coronal section through the foot and talocrural joint (anterior aspect).



Coronal section through the foot (MR-Scan after A. Heuck, G. Luttke and J. W. Rohen, 1994).

1 Iliotibial tract
2 **Common peroneal nerve**
3 Position of head of fibula
4 Extensor digitorum longus muscle
5 Muscular branches of deep peroneal nerve
6 **Superficial peroneal nerve**
7 Tendon of extensor digitorum longus muscle
8 Lateral malleolus
9 Extensor digitorum brevis muscle
10 Tendons of extensor digitorum longus muscle
11 Patella
12 Patellar ligament
13 Anterior margin of tibia
14 **Anterior tibial artery**
15 Tibialis anterior muscle
16 Deep peroneal nerve
17 Extensor hallucis longus muscle
18 Tendon of tibialis anterior muscle
19 Extensor retinaculum
20 Dorsalis pedis artery
21 Extensor hallucis brevis muscle
22 Deep peroneal nerve (on dorsum of foot)
23 Dorsal digital nerves (terminal branches of deep peroneal nerve)
24 **Deep peroneal nerve**
25 Peroneus longus muscle (cut)
26 Superficial peroneal nerve (with peroneal muscles laterally reflected)
27 Peroneus brevis muscle
28 Lateral anterior malleolar artery
29 Fibula
30 Distal tibiofibular joint (syndesmosis)
31 Interosseous talocalcaneal ligament
32 Calcaneus
33 Tendon of peroneus brevis muscle
34 Cuboid bone
35 Lateral cuneiform bone
36 Metatarsal bones
37 Dorsal interosseous muscles
38 Tibia
39 **Talocrural joint**
40 Medial malleolus
41 Talus
42 **Talocalcaneonavicular joint**
43 Navicular bone
44 Medial cuneiform bone
45 Intermediate cuneiform bone
46 First metatarsal bone
47 Metatarsophalangeal joint of great toe
48 Proximal phalanx of great toe
49 Distal phalanx of great toe
50 Heads of metatarsal bones II-IV



Dorsum of the right foot, superficial layer (anterior aspect).



Dorsum of the right foot, superficial layer. The fascia of the dorsum has been removed.

1 **Superficial peroneal nerve**
2 Superior extensor retinaculum
3 Lateral malleolus
4 Venous network of lateral malleolus and tributaries of small saphenous vein
5 Lateral dorsal cutaneous nerve (branch of sural nerve)
6 Intermediate dorsal cutaneous nerve
7 Tendons of extensor digitorum longus muscle
8 Dorsal digital nerves
9 Tendon of tibialis anterior muscle
10 **Saphenous nerve**
11 Venous network of medial malleolus and tributaries of great saphenous vein
12 Medial malleolus
13 Medial dorsal cutaneous nerves
14 **Dorsal venous arch**
15 Dorsal digital nerve (of deep peroneal nerve)
16 Tendon of extensor hallucis longus muscle
17 Dorsal digital arteries
18 Peroneal muscles
19 Deep plantar branch of dorsalis pedis artery anastomosing with plantar arch
20 Extensor digitorum longus muscle
21 Extensor hallucis longus muscle
22 Inferior extensor retinaculum
23 Extensor hallucis brevis muscle



Dorsum of right foot, middle layer (anterior lateral aspect). The cutaneous nerves have been removed.

1 Extensor retinaculum
2 Lateral malleolus
3 Lateral anterior malleolar artery
4 Tendons of peroneal muscles
5 Tendon of peroneus tertius muscle
6 Extensor digitorum brevis muscle
7 Tendons of extensor digitorum longus muscle
8 Dorsal metatarsal arteries
9 Medial malleolus
10 Tendon of tibialis anterior muscle
11 **Dorsalis pedis artery**
12 Deep peroneal nerve (on dorsum of foot)
13 Extensor hallucis brevis muscle
14 Tendon of extensor hallucis longus muscle
15 Dorsalis pedis artery with deep plantar branch to the plantar arch
16 Dorsal digital nerves (terminal branches of deep peroneal nerve)
17 Lateral tarsal artery
18 Extensor digitorum brevis muscle (divided)
19 Arcuate artery
20 Dorsal interosseous muscles
21 **Deep peroneal nerve**
22 Medial cuneiform and 1st metatarsal bone
23 Tendon of peroneus longus muscle
24 Abductor hallucis and flexor hallucis brevis muscles
25 Medial plantar artery, vein and nerve
26 Fourth and fifth metatarsal bone
27 Adductor hallucis (oblique head)
28 Tendons of flexor digitorum longus muscle
29 Lateral plantar artery, vein and nerve
30 Flexor digitorum brevis muscle
31 Plantar aponeurosis



Dorsum of right foot, deep layer (anterior lateral aspect). The extensor digitorum and hallucis breves muscles have been removed.



Cross-section of the rigt foot at the level of the metatarsal bones (posterior aspect).


10
11
12
13
14
6
1
2
3
4
5
6
7
8
9

Axial section through the pelvis and the hip joints (section 1; MR-Image; inferior aspect).



Lower extremity, location of section 1–5. (MR-Images, courtesy of Dr. A. Heuck, Munich).

1 Sartorius muscle
2 **Femoral artery and vein**
3 Iliopsoas muscle
4 Pelvic bone
5 **Femoral head** with ligament of femoral head
6 Articular cavity
7 Rectum
8 **Sciatic nerve** and accompanying artery
9 Gluteus maximus muscle
10 Obturator vessels and obturator nerve
11 Rectus abdominis muscle
12 Pyramidalis muscle
13 Urinary bladder
14 Obturator internus muscle
15 Rectus femoris muscle
16 Vastus intermedius and vastus lateralis of quadriceps femoris muscle


2
3
4
5
6
8
7
66
2
10
6
14
20

Axial section through the pelvis and hip joints in the female (section 1, inferior aspect). (Arrows: uterus, myometrium with myoma).


15
16
17
18
8
27
21
22
23
25
26
63

Axial section through the middle of the thigh (section 2; MR-Image, inferior aspect).


16
17
19
27
62
15
21
23
22
26
25
63

Axial section through the middle of the right thigh (section 2, inferior aspect).



Axial section through the knee joint (section 3; MR-Image; inferior aspect).



Axial section through the right knee joint (section 3, inferior aspect).



Axial section through the middle of the leg (section 4, MR-Image, inferior aspect).



Axial section through the middle of the right leg (section 4, inferior aspect).



Axial section through the end of the right leg (section 5; MR-Image; inferior aspect).



Axial section through the end of the right leg (section 5; inferior aspect).

17 **Femur**
18 Perforating artery
19 Sciatic nerve
20 Gluteus maximus muscle (insertion)
21 Vastus medialis muscle
22 Sartorius muscle
23 Femoral artery and vein
24 Great saphenous vein
25 Gracilis muscle
26 Adductor muscles
27 Biceps femoris muscle
28 Patellar ligament
29 Lateral condyle of femur
30 Posterior cruciate ligament
31 **Tibialis nerve**
32 Popliteal artery and vein
33 Lateral head of gastrocnemius muscle
34 Medial condyle of femur
35 Medial head of gastrocnemius muscle
36 Tibialis anterior muscle
37 **Tibia**
38 Deep peroneal nerve, anterior tibial artery and vein
40 Peroneus longus and brevis muscles
41 **Fibula**
42 Soleus muscle
43 Flexor digitorum longus muscle
44 Tibialis posterior muscle
45 Posterior tibial artery and vein and tibial nerve
46 Peroneal artery
47 Small saphenous vein and sural nerve
48 Extensor hallucis longus muscle
49 Extensor digitorum longus muscle
50 Tendon of peroneus longus muscle
51 Lateral malleolus (fibula)
52 Peroneus brevis muscle
53 Tibialis anterior muscle (tendon)
54 Dorsalis pedis artery
55 Medial malleolus (tibia)
56 Tibialis posterior muscle (tendon)
57 Flexor digitorum longus muscle (tendon with synovial sheath)
58 Flexor hallucis longus muscle
59 Posterior tibial artery and vein
60 Lateral and medial plantar nerves
61 Calcaneal tendon
62 Semitendinosus muscle
63 Semimembranosus muscle
64 Anterior cruciate ligament
65 Plantaris muscle
66 Small intestine


1
2
3
4
5
6
7
8
9
10

Sole of the right foot, superficial layer (from below): dissection of cutaneous nerves and vessels.


1
7
1
8
2
11
6
5
4
12
13
14
6
15
7
1
16
8
17
19
18
9
20
21
22
23

Sole of the right foot, middle layer (from below). The plantar aponeurosis has been removed.



Sole of the right foot, middle layer (from below); dissection of vessels and nerves. The flexor digitorum brevis muscle has been divided and anteriorly reflected.

1 Proper plantar digital nerves
2 Common plantar digital nerves
3 Plantar aponeurosis
4 Superficial branch of lateral plantar nerve
5 Superficial branch of lateral plantar artery
6 Abductor digiti minimi
7 Proper plantar digital arteries
8 Common plantar digital arteries
9 Digital branch of medial plantar nerve to great toe
10 Medial calcaneal branches
11 Tendons of flexor digitorum brevis muscle
12 Flexor digitorum brevis muscle
13 **Superficial branch of lateral plantar nerve**
14 **Lateral plantar artery**
15 Plantar aponeurosis (remnant)
16 Digital synovial sheath
17 Lumbrical muscles
18 Tendon of flexor hallucis longus muscle
19 Flexor hallucis brevis muscle
20 **Medial plantar artery**
21 **Medial plantar nerve**
22 Abductor hallucis muscle
23 Calcaneal tuberosity
24 Tendons of flexor digitorum longus muscle
25 Quadratus plantae muscle
26 **Lateral plantar nerve**
27 Flexor digitorum brevis muscle (cut)
28 Synorial sheaths
29 Plantar arch



Sole of the right foot. Synovial sheaths of flexor tendons indicated in light blue. (Schematic drawing.)



1 Proper plantar digital arteries
2 Proper plantar digital nerves
3 Tendons of flexor digitorum brevis muscle
4 Tendons of flexor digitorum longus muscle
5 Superficial branch of lateral plantar artery
6 Deep branch of lateral plantar nerve
7 Superficial branch of lateral plantar nerve
8 **Lateral plantar nerve**
9 **Lateral plantar artery**
10 Abductor digiti minimi muscle
11 Calcaneal tuberosity
12 Common plantar digital arteries
13 Tendon of flexor hallucis longus muscle
14 Insertion of both heads of adductor hallucis muscle
15 Plantar metatarsal arteries
16 Medial plantar nerve of great toe
17 Deep plantar branch of dorsalis pedis artery (perforating branch)
18 **Plantar arch**
19 Oblique head of adductor hallucis muscle (cut)
20 **Medial plantar artery**
21 **Medial plantar nerve**
22 Crossing of tendons in sole of foot (flexor hallucis longus and flexor digitorum longus muscles)
23 Abductor hallucis muscle
24 Origin of flexor digitorum brevis muscle

Sole of the right foot, deep layer (from below); dissection of vessels and nerves. The flexor digitorum brevis muscle, the quadratus plantae muscle with the tendons of the flexor digitorum longus muscle and some branches of the medial plantar nerve have been removed. The flexor hallucis brevis and adductor hallucis muscles have been cut and portions removed to show the somewhat atypical course of the medial plantar artery and deep muscles of the foot.



CORY HERTER'S
"JOURNEY THROUGH THE AFTERLIFE"
300 NEAR DEATH EXPERIENCES, 1000+ HOURS ON THE OTHER SIDE
HOW WOULD YOU TELL THE WORLD WHAT YOU SAW?

CORY HERTER'S SACRED G E-BOOK

FREE SACRED G
NATURAL HEALING
PINEAL ACTIVATION
100+ HOURS OF VIDEO
LIVE INNER G CLASSES

Visit www.CoryHerter.com to Download Your Free Sacred G Technology, 100+ Page E-Course & Join Cory Every Tuesday & Wednesday Night for his Live Inner G Healing Webinars!

Version 1.1 – November, 2009
www.CoryHerter.com

Thank you for downloading Cory Herter's Sacred G E-Book. Please be aware that this e-book will continually be updated, edited and refined as new content is added to www.CoryHerter.com.

Why are the Sacred G Technologies, the seemingly unlimited amount of videos and this e-book available for Free Download? Has Cory lost his mind?

I was given an incredible vision, message and technology to spread to the world during my 300+ Near Death Experiences. I offer all of this and more as a service to the world in appreciation for the Visions that I was given. Sacred G technology restored my health and has given me a life beyond my dreams. I believe good health and an amazing life are something that every person on the planet deserves and I hope this information and technology will transform your life the way it has for mine.

If you have additional questions that are not answered on the website nor in this book, please email them to info@coryherter.com and the answers will be added to the future additions of this e-book and to the website. As the amount of email being received is more than I can handle, please do not expect an immediate reply. I assure you that I do read your stories and comments and really appreciate your feedback.

As this is the first version of this e-book, please excuse any grammatical errors, the content has been taken from the videos on the website. If you are having a real difficult time or frustrated by this, please edit it and send me the file for the next e-book update, that will be more helpful than any negative comments or feedback. Thank you, and remember, I am a Mathemagician, not an English Major!!

If you have questions about what you are experiencing as a result of using Sacred G, you can book a session with one of my specialists on the store. After you purchase a session, you will be contacted to setup an appointment.

If you are interested in making an order over the telephone, please send an email to order@coryherter.com and I will have a sales representative contact you ASAP.

Thank you for taking the time to try Sacred G, attend the Inner G Energy Training Classes and educate your self on what I feel is some of the most incredible information on the planet. If you have any comments, suggestions or topics that you would like me to teach about, please email me at info@coryherter.com.

With Love & Light, We shall all find the way!

Cory Herter

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Table of Contents

Introduction 8

1st and MOST IMPORTANT thing to do!! 9

SLEEP TEST 10

Water Purification Test 13

Water Purification Test Results 14

About Cory Herter – The Creator of Sacred G 15

Evolution of Vibrational Technologies into Sacred G 17

Pineal Activation through Sacred G Fusion Technology 20

Pineal Gland – DMT 20

Pineal Gland – Hormone Activation 21

Pineal Gland – Circadian Rhythms 22

Pineal Gland – The Natural Healing Mechanism… Sleep 23

Pineal Gland – Speed / Temperature 25

Pineal Gland – Conclusion 26

Sacred G Designs 27

Sacred G Spot 27

Transporter 29

Ascender 32

Trancendance 35

Simulator 36

Activator 38

Sacred G Fusion 41

Sacred G Fusion Case – The Tree of LOVE 43

Basic Instructions for Using Sacred G Technology 45

35 Ways To Boost Your Energy With Sacred G 46

Water 47

Food – Fridge, Freezer & Pantry 47

Fruit bowl and Bread Basket 48

Health supplements 48

Clothing 49

Jewelry 49

Cell Phone 50

Computer 50

Personal Hygiene Products 51

Hot Water Tank 51

Vehicle 52

Picture Frame 52

Air Ducts and Fuse Box 53

Directly on the Body 53

Couch Cushions 54

Vision Boards 54

Backpack 55

Massage Oils / Lotions, Shampoo & Conditioner, etc… 56

Crystals and Precious Stones 56

Meditation 57

Yoga mats 57

Extreme Performance Enhancement 58

Candles 58

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

- Contact Lenses / Glasses 59
- Kitchen Utensils 59
- Cleaning Products 60
- Animals Love Sacred G 60
- Improving Eyesight and Multi-Dimensional Vision 61
- Bath Tub 61
- Pictures & Photo Albums 62
- Business Cards 62
- Gardening 63
- Sacred G Food Test 64
- Sacred G Temperature Test 64
- Sacred G Full Body Energy Cleanse 65

What to expect when beginning Sacred G Technology 66
- **10 Most Common Forms of Cleansing 66**
- **3 Stage Development Process 68**

Research 73
- **Infrared Testing with Cell Phones 73**
- **Gas Discharge Visualization Camera 74**
- **Life Span of Flowers 75**
- **Food Preservation – Celery 76**

FAQ’s Regarding Sacred G 77

Video Library 84
- **2006 Video Series – 19 Hours 84**
  - 2006 - Introduction to Sacred G Technology – 2 Hours 84
  - 2006 – Creating the Council – 2 Hours 84
  - 2006 - Creating the Collective – 1 Hour 85
  - 2006 - Advanced Sacred Geometry - Part 1 – 2 Hours 85
  - 2006 - Advanced Sacred Geometry - Part 2 - Time & Space – 2 Hours 85
  - 2006 - Life After Death - Part 1 – 2 Hours 85
  - 2006 - Life After Death - Part 2 – 2 Hours 85
  - 2006 - Life After Death - Part 3 – 2 Hours 86
  - 2006 - Chironium Healing - Part 1 – 2 Hours 86
  - 2006 - Chironium Healing - Part 2 – 2 Hours 86
- **2012 ..... 86**
  - Oct 20, 09 Live Webinar – The Truth about 2012 87
  - The 2012 Enigma by David Wilcock 87
- **Ascension 87**
  - Merkabah – The Chariot of Ascension 87
- **Breath of LOVE 87**
  - LOVE Innerversity – Module 1 – The Breath of LOVE 87
  - #1 Reason For Every Health Problem 88
- **Cory Herter 88**
  - Cory Explains his 300 Near Death Experiences 88
  - Evolution Into Sacred G Technology 88
  - Cory Herter on Sacred G Fusion 88
  - Cory Herter’s Experience on Sacred G Fusion #2 89
  - Cory’s Sacred G Fusion Bed Set and Massive Sacred G Designs 89
- **Cory’s Video Series 89**

Sacred G Sleep Test – 5 Video Series 89
Pineal Gland Activation – Entire Series – 6 Parts 90
Benefits of each Sacred G Design – Entire Series + Bonus Video 90
Science of LOVE DVD – A 3 Hour Video Series on the Science behind Sacred G 90
Crazy Sacred G Fun 90
Cool Sacred G Video 90
Underground Sacred G Party 91
DMT 91
Pineal Gland & DMT by Cory Herter – Part 1 of 6 91
DMT: The Spirit Molecule, the Movie 91
DMT – The Spirit Molecule – Audio Interview with Film Maker Mitch Schultz 91
DMT, Dreams and Near Death Experiences 92
Joe Rogan Talks DMT on the Alex Jones Show 92
Joe Rogan Goes off about DMT 92
Fusion 92
New Sacred G Fusion Bed Set Video 93
Sacred G Fusion – ONLY $1.00 / Sheet 93
Sacred G Fusion Design – 7 of 7 93
Bonus: Secret of the Sacred G Fusion Case 93
Cory Herter on Sacred G Fusion 93
Cory Herter's Experience on Sacred G Fusion #2 93
The Collective & Sacred G Fusion 94
Cory's Sacred G Fusion Bed Set and Massive Sacred G Designs 94
Indigo Children 94
Indigo, Rainbow & Crystal Children and Sacred G Fusion 94
Akiane: child prodigy, artist, poet, "Indigo child" 95
Meditation 95
Sacred G Meditation Station 95
Sacred G Inspirational Video by Quantum Power 95
Sacred G Power Meditation by Quantum Power 96
Pineal Gland 96
Pineal Gland & DMT by Cory Herter – Part 1 of 6 96
Pineal Gland & Hormones by Cory Herter – Part 2 of 6 96
Pineal Gland & Circadian Rhythms by Cory Herter – Part 3 of 6 96
Pineal Gland & Sleep by Cory Herter – Part 4 of 6 97
Pineal Gland & Temperature by Cory Herter – Part 5 of 6 97
Pineal Gland – The Master Gland by Cory Herter – Part 6 of 6 97
THE PINEAL GLAND IS A STARGATE – 23 PART SERIES 97
Research 98
Research with Sacred G Technology 98
Sacred G Designs 98
Sacred G Spot Design – 1 of 7 98
Sacred G Transporter Design – 2 of 7 98
Sacred G Ascender Design – 3 of 7 98
Sacred G Trancendance Design – 4 of 7 99
Sacred G Simulator Design – 5 of 7 99
Sacred G Activator Design – 6 of 7 99
Sacred G Fusion Design – 7 of 7 99
Bonus: Secret of the Sacred G Fusion Case 100
Sacred G on MTV 100

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

The Full Sacred G Episode on MTV's Rob & Big 100
Rob Dyrdek & Steve Berra Share Their Views about Sacred G on MTV 100
Highlights from MTV's Hit Show Rob & Big Featuring Sacred G 100
Sacred G Uses & Tests 101
Simple Instructions and Tips for using Sacred G Technology 101
35 Uses & 5 Tests for Sacred G 101
Sacred G Water Taste Test 101
Sacred G Sleep Test – 5 Video Series 101
Sacred Geometry 102
The Secret of the Universe 102
Science of LOVE DVD 102
Science of LOVE Introduction 102
Science of LOVE DVD – A 3 Hour Video Series on the Science behind Sacred G 102
Sleep Test 103
Sacred G Sleep Test – Beta (Tossing and Tuning) – Part 1 of 5 103
Sacred G Sleep Test – Alpha (Emotional Dreams) – Part 2 of 5 103
Sacred G Sleep Test – Theta (Educational Dreams) – Part 3 of 5 103
Sacred G Sleep Test – Delta (Deep Sleep) – Part 4 of 5 104
Sacred G Sleep Test – Brain Wave Conclusion – Part 5 of 5 104
Tree of LOVE 104
Secret of the Sacred G Fusion Case 104
The Three Trees – The Tree of Life, Knowledge & LOVE 104
Secret to Perfect Health - 1 Problem, 1 Solution, 6 Layers & the Tree of LOVE 105
Video Testimonials 105
Carolanne & Theresa's Sacred G Experience 105
David Shore, Sacred G Life Saver 105
David Caddell Sacred G Testimonial 105
Druanna on Sacred G Technology 105
David Shore shares his testimonial of Sacred G 106
Pete Lewis's experience on Sacred G Technology 106
Loriel Hanon's Testimonial from Sleeping on 50 Cases of Sacred G Technology!! 106
Taylor Angelos's amazing testimonial from sleeping on a Fusion Bed Set!! 106
JoAnne Jablonski's LOVE Practioner Course Experience 107
Serena Carrico's experience of Sacred G Technology 107
Serena's Healing with Dog at the LOVE Practitioner Course – AMAZING!!! 107
Solei Hannahs testimonial about Sacred G and its powerful cleansing effects! 107
Loriel Hanon's experience of the LOVE Practitioner Course 108
Alysha Duran's experience on her Sacred G Fusion Bed Set 108
Allison Lee Clark – New Senses, Enhanced Meditation, Tons of Benefits!! 108
Kara's Sacred G Testimonial – Complete Life Transformation in 1 Year 108
Jayson's Testimonial of Sacred G Technology 108
Lee's Sacred G Testimonial – Kidney Transplant & Medication 109
Sacred G Testimonial from a Pediatrician's Office 109
Rob Dyrdek & Steve Berra Share Their Views about Sacred G on MTV 109
Highlights from MTV's Hit Show Rob & Big Featuring Sacred G 109
Webinar Archives 110
Aug 18, 09 Webinar – Sacred G and the Table of Elements 110
Aug 25, 09 Webinar – Cory shares insights on Sacred G Fusion and Q&A 110
Sept. 1, 09 – Channeling Higher Energy States 110
Sept. 8, 09 Webinar – Financial Abundance 110

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Sept. 15, 09 Webinar – Cleansing through Sacred G 111
Sept 22, 09 Webinar – Sound Healing + Q & A from Chat Room 111
Oct 6, 09 Webinar – Cory talks Energy and Introduces the new LOVE Innerversity ... 111
Oct 13, 09 Webinar – The Three Trees of Life, Knowledge & LOVE 111
Oct 20, 09 Live Webinar – The Truth about 2012 112
Oct 27, 2009 Webinar – Your Health, 1 Problem, 1 Solution, 6 Layers & The Tree of LOVE 112

Introduction

Welcome to Cory Herter's Journey Through the After Life. I am about to walk you through an incredible transformation to awaken your body, spirit and consciousness to a whole new level. I was given a message to share with you. This is no ordinary message, nor is it something I can tell you in a couple sentences. The message is something you must become; it is Sacred and can only be experienced to truly understand.

Sacred: Something that can only be experienced, something that can only be shared with those in the know.

This e-course is unlike anything you have ever seen. It is more than just a few pages of information designed to get you to buy some product. Ok, this isn't just an e-course, it is a table of contents for a massive website with so much video that people get lost. This guide is to walk you through an experiential process using Sacred G Technology, Massive Video Archives, Live Webinars, Group Chats, Experiential Energy Healing Courses, Live Seminars and so much more.
Here is just a quick sample of what you are receiving with this Free E-Book that never… ever… ends.

- A Two Year Live Energy Training Course Online with two classes every week!
- Every Sacred G Design (Except Fusion) for Free so that you can download and print as many as you want.
- Opportunity to purchase Sacred G Fusion for only $1.00 / Poster.
- Meditation Station for a daily stress relief exercise.
- 70+ Hours of Video Archives and growing every week.
- Community of 500+ amazing light workers to interact with.
- 3 Hour Science of Sacred Geometry Video Series.
- 6 Hour The science of Life After Death Seminar.
- 3 Hour Chironium Healing Energy Course (Pre-cursor to Module 1 – The Breath of LOVE Course)
- Sacred G Sleep Tests that reveal which Brain Wave States you are congested in and how to clear them.
- Deeper science behind the Law of Attraction behind the popular movie "The Secret".
- How to Create your own customized energized water shown on "What the Bleep".
- And so much more…

All you have to do is follow this outline and I will take you on a journey that you will never forget. You can jump around, follow the structure that I laid out for you, go through this as fast as you like or take as long as you like, but the most important thing you do is begin using the Sacred G Technology.

1st and MOST IMPORTANT thing to do!!



If you haven't downloaded your **Free Sacred G Technology** yet, here is the link to the store so you can sign up for them.

http://www.CoryHerterStore.com

These files are newer than before and a much higher quality, which means they will take a bit longer to download. Once you have the files, you will need to print them out. Each design is a separate file. Be sure to print at least one of each in color.
Here are some quick tips that you might have questions about when using your Sacred G Technology:

1. You can print on both sides of the paper for double the energy + you will also get the activation and grounding/integration effects.

2. Yes, you can laminate the designs to protect them. Remember, 1 Sacred G Fusion Poster costs only $1, less than it costs to laminate the one you printed out. Try laminating 2 or 3 sheets that you printed out for extra strength.

3. The activator is the only Sacred G Design you can cut, it is the only repeating pattern out of all the Sacred G Designs and is the actual mathematics behind the structure of space… it is designed to activate the cerebellum which you will learn more about soon. (get used to my crazy… way to much information answers, I do it all the time… lol.) Do not cut into the other designs. If you need to resize them… fold them instead. You can laminate them after folding them if you like.

4. Stacking the Sacred G Designs on top of each other makes them more powerful. If you do not notice a difference, print more and add them underneath your mattress. Some people's bodies are not as sensitive as others.

5. Yes, you can stack different designs on top of each other, have fun, play around and notice if you have different effects by stacking the Sacred G Technology differently.

OK… Now here is what you need to do with the Sacred G Designs that you printed out. Using them in this configuration is the closest thing to actually having the most advanced Sacred G Fusion design under your mattress.

SLEEP TEST

Place the Sacred G designs between your mattress and box spring in these specific locations:

G-Spot - Goes where you Head will be.
Transporter - Goes where your Chest will be.
Ascender - Goes where your Stomach will be.
Simulator - Goes where your Knees will be.
Activator - Goes where your Feet will be.

Place the Trancendance Design on your night table with a glass of water on it. Drink the water when you wake up in the morning to help eliminate any toxins that were cleared from your cells while you sleep.

When you wake up, make a mental note about any difference in your sleep. I am going to teach you about brain wave states and your sleep in the next section.

STOP HERE, PRINT OUT THE DESIGNS AND PLACE THEM IN-BETWEEN THE BOXSPRING AND MATTRESS!!!

Read the next section tomorrow to learn about what the Sacred G Sleep Test reveals about you.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Sleep Test Results

Welcome to Day 2 of your journey.

Today you are going to learn about the most important person on this Planet... You! Your sleep is the most important time of the day when it comes to your health. Without sleep, your body deteriorates extremely quickly. At nighttime while you sleep, your brain is processing all of your experiences and information that your brain absorbed throughout the day. This frees up all your energy so your body can run smoothly again the following day.

If your brain gets backed up, your energy slowly drops and your body begins to breakdown. If your brain gets too backed up, your body and brain dulls the senses as it resists external stimulation. Over the years, the body has no choice but to continue shutting down systems in the brain and body to the point where old age and disease sets in.

If you can increase the amount of information your brain can process at nighttime while you sleep, your body will heal itself more effectively. Overtime, the aging and breakdown of the physical body can be reversed while you are sleeping. Remember that sleep is the optimum time for healing and is a natural response when the body is sick. Increase the quality of sleep through Sacred G Technology and feel the health benefits for years to come.

How was your sleep last night?
Everyone has a unique experience when starting Sacred G Technology, luckily I found a pattern and it has to do with Brain Wave States. Last nights sleep was the first test to discovering more about yourself.

Click on the link below the statement that is the most true for your experience last night. This will take you to a video on the website where you can learn about which brain wave states have too much unprocessed energy, determine which Sacred G Design will unlock the most amount of energy for you and discover the transformational processes that Sacred G Fusion will initiate.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Sleep Test Results
Click on the link that most reflects your Sacred G sleep experience.

No Video for this one. **Simply add more Sacred G and come back to this tomorrow.**	**Didn't notice anything, I went to bed and woke up as usual.** This is simply because your body is not as sensitive and requires more Sacred G Technology to cross the threshold. Print out another set of the designs and add them under your mattress. Continue adding more until you notice a difference, then watch the videos when you notice the shift take place. Some bodies simply require a larger amount of Sacred G for the effects to take place.
Cory Herter's Journey Through The After Life	**I couldn't sleep; I was tossing and turning all night.** http://coryherter.com/?p=1002
Cory Herter's Journey Through The After Life	**I was dreaming all night long, and woke up emotionally triggered.** http://coryherter.com/?p=1000
Cory Herter's Journey Through The After Life	**I was dreaming all night long about old friends, learning new information or seeing patterns in my life.** http://coryherter.com/?p=998
Cory Herter's Journey Through The After Life	**My Head hit the pillow and I was out… Deep Deep Sleep.** http://coryherter.com/?p=996

Cory Herter's Journey Through The After Life

Sleep Test Conclusion: After you watched the above video corresponding with your sleep experience, watch this video to learn a little more about sleep. http://coryherter.com/?p=993

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Please share your experience of the Sacred G Sleep Test with everyone. Just click the link below and add your comments.

http://coryherter.com/?p=975

This is one last video called #1 Reason for every Health Problem and has to do with sleep. This will help you to understand how important Sleep is to your Health.

http://coryherter.com/?p=672

Here is your task for today:

1. Print out another set of the Sacred G designs and layer them on top of the designs you already put under your mattress. Increasing the amount of Sacred G that you use will increase the healing process!
2. Notice the difference in the morning and be sure to journal your experience. I hope you enjoyed the video and gained a deeper understanding of your body, brain and Sacred G.
3. Try the Water Purification Test!!

Water Purification Test

The water test is designed to show you how Sacred G Technology can clean water, and more importantly cleanse and energize your body from Sleeping on Sacred G. Use Tap Water for this test to notice the biggest difference in taste. Use purified water combined with Sacred G for the best health benefits.

Water Test Instructions:

1. Fill 2 glasses with tap water.
2. Put one glass on top of the TranceNDance design and the other glass at least 6 feet away.
3. Let sit for a minimum of 30 minutes, or leave overnight for even more profound results.
4. Taste the difference between the 2 glasses.

Over 80% of people surveyed noticed a difference in the water after using Sacred G.

"I haven't drank tap water for years…there was definitely a sweet taste." – Veronica

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

“The water was a totally different taste, this is amazing! We use well water as opposed to city water. The water however has a lot of sulpher in it. You can smell the sulpher it's so strong. I used a gallon ice cream tub filled with the water and let it rest on top of the "Sacred G" over night. The next morning I poured a glass of water just to see if there was a difference. (I also had a glass of water away from the "Sacred G" that I also let stand over night.) The glass of water still had the sulpher taste. The gallon of water however, I swear, tasted like distilled water. The pot of coffee I made with it was superb.” –Ira

“My body was completely energized after drinking the L.O.V.E. Water! Used it in all my plants, on myself, and it was sweet and delicious.” -Ameena

“The water was a totally different taste, this is amazing! It tasted fresh and I really noticed the difference....loved it!” – Linda

What did you notice?

Water Purification Test Results

Please visit the following link to share your experience and discover the Secret behind how Sacred G can change the taste of your water.

http://coryherter.com/?p=136

Try stacking every Sacred G Design on top of each other and then charging the water. What did you notice?

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Part 2 – Learning the Details

About Cory Herter – The Creator of Sacred G

http://coryherter.com/?p=495

Let me guess… you're wondering the exact same thing that everyone that comes to this website is wondering. How did Cory Herter have over 300 near-death experiences? How could you possibly spend over 1000 hours on the other side? I'm going to explain this to you. This actually has a lot to do with you and every single person because every single person faces death and every single person faces life. There is something really amazing inside of you. There is this connection. In my experience, I have been given this really amazing message and a really amazing technology.

So how did I have over 300 death experiences? It's actually really simple. In 1990, I was 10 years old I got involved in a really serious car accident. I suffered a very traumatic brain injury. My brain was bleeding, and I was actually very lucky to come out of the accident alive. And that was my very first near death experience. It wasn't anything magnificent. The next thing I knew, I was up and out of my body. I was up above the car, looking down at the car. I was kind of worried about what was happening. This person came and sat next to me in the air. It's kind of weird, "sitting next to me in the air" or that "this presence came and sat beside me in the air," whichever way you want to look at. He basically said, "Its going to be OK, you'll be back very shortly, just relax… its part of the process." The next thing I knew, I was in the hospital.

From that car accident, two major things happened. The first one was with the brain injury. I lost all my memory from before I was 10 years old, so my long- term memory was severely impaired with my short-term memory usually only lasting 3 to 5 days. After that, I couldn't recall my memories by myself, but if someone else brought them up, I could remember them. Now most people talk about being in the moment. Being in the moment, you don't have all that extra baggage weighing you down. I was actually a very happy-go-lucky person. I didn't have any worries or cares, fears or anything. I was just so in the moment then.

A few years later, after the accident around 1994, something very different started to happen. I started to find out the other side of the moment. Being in the moment in one way, you're happy, you're celebrating, you're just giving it all you got.

Then I found out there's this other moment where you don't recognize anything. You don't know who anybody is, and you're so in the moment but you don't have any information or any recollection. This is kind of the opposite of the moment. It's very shocking, and it would put my body into shock. It didn't matter where I was when this started to happen. I usually tried to remove myself from everybody and everything. I would be huddled in the corner. I wouldn't know where I was. My whole body would be in this state of shock, and I would always go over this same prayer: "Please god, please help me, please take me away from here. I don't know where I am, I don't know what I am doing." The next thing I knew, I would get this energy that would float through my body and everything would go peaceful.

Gradually, this process kept happening about every 5 days and over about 6 months time. The energy kept increasing every single time it happened, and I was about 14 going on 15 when all of sudden, something changed. This energy blew through so much that it literally picked me up and took me out of my body. I remembered that I was in that exact same place that I had when I had my first near death experience. I didn't actually know what was going on for quite a few years. Actually until about 2004, I still didn't understand the mechanics of this process that I was going through, so every 5 days for about 5 years, my body would go into shock and would trigger the release of this energy and it would literally send me into these near-death experiences. Each experience lasted anywhere from 4 to 12 hours. The longest one lasted in a peak state for about 4 days, and it took about 2 weeks to really be back here.

Through all of these experiences, I really grew. I learned some really neat things, and of course, that's where I was given technology to heal my brain as well. This happened approximately from 1995 to 2000. In 2004, I actually developed Sacred G to a point that started bringing my memories back. This is actually the Ascender design. The Transporter also started bringing back some of the memories. It's been a really incredible experience!

So that's kind of how I had over 300 near-death experiences, but what actually made this happened? There is a chemical inside your pineal gland called DMT. It stands for dimethyltryptamine. It's a hallucinogenic compound that's produced naturally in every single one of our brains. This chemical is also our connection to source, to who we are as a spirit, so when we start to increase the amount of this chemical in our brain, we increase the connection we have to source, and we feel like we are spiritually home now. Typically, this only releases twice in large doses in your lifetime, once when you are born and once when you die. At nighttime, when you sleep, it's this chemical that makes you dream.

The pineal gland is also referred to as the third eye. There are more videos on DMT, if you're interested in learning more about this compound. This is how I went through over 300 near-death experiences. It was because my brain injury started production of this compound, and it would shoot me into these near-death experiences every 5 days for over 5 years.

Evolution of Vibrational Technologies into Sacred G

http://coryherter.com/?p=668

A lot of people are curious about how I started working on Sacred G technology. Where did it come from? It didn't just start with Sacred G technology on this flat surface. I used to actually use a bunch of other vibrational technologies with vibration there is actually light, sound, magnetic fields, electromagnetic fields and also pressure, which most people aren't aware of, that can be used with vibration systems. I worked with every single one of them, and Sacred G is really that point that falls in between all of them. It's that capstone that holds them all together. With Sacred G, I can actually influence light waves, sound waves, magnetic fields, electromagnetic fields, not essentially with the fields themselves, but I can add energy to the underlying structure of them, so I can add in layers of density and depth almost like using sound or light as a carrier wave to pass on extra Sacred G information for me.

I used to build this bed called an enhancer bed. They were pretty amazing. There were 80 different color lights that would shine on your body when you were naked on this bed. Then there was a 120 essential oil blend that is now up to 137 blend that you would mist all over the body. There was a CD that I made with 40,000 minutes of music playing a 100 times a second that was a custom CD that my brother and I built. I would drape14 high-powered, high strength magnetic necklaces beyond most magnetic necklaces all over my body. There was Sacred G all around this design, and I was given a recipe to make this clay that would absorb all the toxins as I was cleansing them from going into this bed. I also had those Voyager glasses with little red lights that flicker on and off and make all these geometric patterns take place. All of this stuff was taking place at the same time. Instead of a sensory deprivation, this was like a sensory overload chamber, essentially to overload every single sense inside the body.

I'd go in there for about an hour and a half every single day and the types of experiences I would have there would be points where I would feel myself float right out of my body. I would go into this infinite plane. I would just expand outward and could feel this eternalness. It was actually very similar to what it would feel like when I would go into the tunnel and become immersed in the light during the near death experiences. It was nearly identical, so it was really neat that they taught me how to build a bed that you could actually experience what it was like to die and go into the tunnel and have those same sensations while you're still alive. After using the bed for about a year and a half, as much as I grew and opened up, having to take out an hour and half everyday, the bed almost became its own block. I could have an argument with my girlfriend at the time. I'd say "Let's go to the bed," so we'd go to the bed and we'd come out after 30 or 45 minutes, sometimes an hour later, completely calm, no charge whatsoever and we'd quickly figure out we were saying essentially the same thing. We just couldn't communicate properly.

Then I started throwing these 5-gallon jugs of water onto this bed and letting this water cook for days, and we'd start drinking this water. I could tell that this water was powerful, and all of a sudden I started getting these heart palpitations. It would just drop me to the ground, and it wasn't just me. It would drop my brother and my girlfriend too. This is where I was really humbled by vibration technology, because before then, everyone always said, "Oh, it's all vibrational energy, it's all positive, its all good." It was then that I started to realize, "Hey wait a second, vibrational energy is extremely powerful and there's a lot to it." I'm telling you this, so you understand that I've been through the process of what works and what doesn't work with vibrational technology. A lot of people, think that it's just vibrations, its just going to give you energy. There is a little more to it than that.

Vibration works just like chemistry, and it's basically a mathematical form of chemistry. So if you start getting too much of one vibration, it can throw your body off balance. That's what I was starting to find. How many different colors actually are there? How can you get this balanced spectrum of light or color? Another thing I was starting to find was that blue affects me in one way, but it can affect someone else a completely different way. Then I started to realize something, because of quantum physics, our bodies are internally wired so differently. One thing doesn't work for everybody. It's the way that the body is built.

I started thinking, "How do I know what vibration to use for people?" There was so much manual calculation trying to understand well which sound vibration does what type of effect to what type of organ in the body. One sound vibration will affect one organ in a person, but with a different person, it will affect a completely different organ. Because of they way we are all wired, we're all completely different. This is our own unique print. Like your fingerprint or eye print is customized just for you, your own internal vibrational wiring is also unique, so vibrationally everyone has their own individual code that needs to be cracked. What I started to look for was a type of vibration, a full spectrum vibration, which was perfectly balanced. In other words, it would resemble a perfect white light, which is a perfect balance of every color.

So that's what I started to look for with vibration and through that process, I studied a lot and built a lot of technology with electricity. I built technology that was actually similar to Stonehenge. It's a whole funny story. I'll make a video of it and hopefully build one so you guys can know how to build little mini Stonehenge water chargers for yourself. That was actually the starting blueprint for how to build some of the more advanced Sacred G technology on a flat surface, and eventually I came to this whole spectrum vibration. The only way that I could produce was actually on a flat surface using sacred geometry because with sacred geometry I could control the angles. With the angles, I could figure out which angles could produce what types of vibrations and actually build a mathematical model to understand this invisible force of energy that is governed through a mathematical system of vibration. If you want to learn more about this mathematical system, there is a 3 hour video series on coryherter.com where you can actually watch and learn some of the basics about the mathematics.

Eventually, I found this full spectrum vibration and it became this stabilizing agent, the one that's going to stabilize all the energy and integrate it. With Sacred G Fusion, it includes the full spectrum vibration, and it also directs that vibration to all the different regions of the brain and most importantly, the pineal gland, to really activate it.

A full spectrum vibration is essentially a freedom vibration. It opens us up to choice, so it forces us to open ourselves up to have choice. Once we have choice, the technology moves on to the next thing where we put ourselves into an internal prison or through judgment. That's essentially what Sacred G Fusion is. It goes inside and finds your settings that are locked down in one setting and says, "No, you can fluctuate. You can change. You can adapt." This full spectrum vibration is an integration type of vibration, and that's what makes Sacred G technology so powerful to use with every other modality. Every Healing modality focuses into specific areas of the brain for healing, Sacred G Fusion is great because it completes the rest of the regions of the brain that the modality missed and integrates those new programming changes into your life. When you use other healing modalities and various healing products and technologies, you are manually accelerating the natural healing process that typically occurs only at night while you are dreaming. The more healing you do, the more powerful Sacred G Fusion will become. If you are a health practitioner and wish to accelerate the results and really help your clients integrate their healing work into their life, get your clients on Sacred G Fusion.

So Sacred G literally came out of all of these vibrations. It came out of a search to find a really stable perfectly balanced vibration that you could continuously add more to in order to reach higher and higher states of consciousness. It would keep you stable, balanced, and of course, very spiritually pure. The whole intention with Sacred G was to ground and integrate this powerful spiritual energy for healing and activate higher levels of functionality in the human body.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Pineal Activation through Sacred G Fusion Technology

Pineal Gland – DMT

http://coryherter.com/?p=420

The pineal gland is absolutely incredible and does so many things, one of the most important is the role it plays in DMT production. DMT stands for **Dimethyltryptamine,** a hallucinogenic compound that regulates our experience of our connection with Source. DMT is a naturally occurring hallucinogenic in the human body, plants and animals. While you can extract DMT from grass clippings from your lawn and find it in every human brain, DMT is a completely illegal substance just like heroin or cocaine. Increase in DMT leads to increasing spiritual awareness as well as an increase in the activation of the body. Large amounts of DMT were released in me every 5 days for over 5 years shooting me into the near death experiences where I learned how to build the Sacred G technology. The purpose of what I experienced on the other side was to learn to overcome death and truly live, and the pineal gland is a crucial part of that.

The pineal gland is typically called the third eye because of its location in the center of the brain behind the forehead. In reptiles, this gland actually has a cornea, a retina and a lens and is literally a third eye. Something interesting about the pineal gland is that it begins to calcify as we get older, mostly caused by the fluoride in tap water. To offset this, it's important to not only use Sacred G to charge yourself up at night, but to also charge up your water and food to start activating your pineal gland, making it more alive so that it can overcome the suppression from the toxic environment that we all exist within.

In a human body, the pineal gland has essentially evolved to not only pick up visible light, but invisible light as well. The light we normally associate as being visible to us is a very tiny sliver of the electromagnetic spectrum. While most are not conscious that it's happening, the pineal gland is also able to pick up these invisible forms of light and vibration from our environment. These invisible forms of light and vibration picked up by pineal gland are what we experience as our spiritual senses.

We all have spiritual gifts and abilities. Some examples of those are what people call clairaudience, clairvoyance, or clairsentience. We have the ability to feel what other people are feeling, to talk to people on the other side, to channel, download new information or intuitive hits, psychic premonitions… all of these are all spiritual senses. When you truly understand spiritual senses, you realize that they reflect

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

that state of oneness that connects us. Our physical bodies give us the appearance of being separate individuals with our own separate space, but when we move into a spiritual state we all become one massive being. When we increase DMT production in the pineal gland, we move into that state of connectedness with our conscious awareness. We then experience life at this richer, deeper, more synchronized level.

Sacred G technology works by using mathematics to enhance and activate the pineal gland and increase the amount of DMT production. When you start increasing DMT production, what you are essentially doing is increasing your connection to Source and your conscious access to your spiritual abilities. Many people around the planet have been waking up and these new senses have been opening. For some people this can be a scary process, especially if they aren't stabilized as they are doing it. Sacred G technology enables us to increase DMT production, unlock these higher spiritual senses in a way that's stable and balanced.

Any person on the planet can experience the unlocking of the spiritual senses. We no longer need to wish our parents, children, husbands or wives could open up. Now with Sacred G technology, we can start opening more people up in a stable way all around the globe to these new senses, to these new abilities, and to this entirely new experience of reality.

As we become more conscious and activated, we are participating in a spiritual revolution on the planet. When we experience this wave of energy that's coming through everybody, opening and activating our bodies, what we're actually talking about is the activation of the pineal gland and the activation of this natural occurring compound called DMT.

Pineal Gland – Hormone Activation

http://coryherter.com/?p=418

Pineal gland is so crucial to who we are. It regulates actual hormone production in the body including testosterone and estrogen and affects our comfortability with being human, with being a male with being a female, masculinity and femininity. If our hormones are off we're not going to feel at home inside of our own bodies. We are going to feel uncomfortable, not want to move, have difficulty feeling confident, focused, and have a challenging time expressing what we want.

You may even be one of those people who feels so uncomfortable inside of his or her own body and felt that Earth isn't actually your home, that you don't actually belong here and you don't really feel welcome here. What you're really talking about in that situation is a hormonal imbalance caused by an inactive pineal gland. Sacred G Fusion is something that can support you in stabilizing your hormones, and help to make you feel comfortable in your body. Sacred G Fusion will also actually activate and enhance your hormones so that your body starts healing faster, you actually increase your performance, you start building muscle faster, women will develop more curves and be more visually in their femininity. You start stepping more into your sexuality and your sensuality and your skin starts to become more sensitive and alive. This is the richness of life, the intensity of touch and phenomenal feeling of living with awakened senses. When your senses are dull, life is dull. When your senses are shut down, life becomes boring but when senses are active, life starts opening up and possibilities start to awaken for you. When you're really sensitized and active, you feel comfortable, you feel great in your body, you want to move, you feel alive, you love who you are, you love being here on earth, you love being alive and of course the more you love being here your going to start to interact more and the more you interact with people and the better feel about yourself, the more people are going to want to be around you. You'll start doing better in business and having better relationships.

Your sexual experiences will also intensify, especially on a Sacred G Fusion bed set because your senses start to activate. The Sacred G Fusion pulls out the primal forces of energy and Kundalini energy that comes up through your body. When you start feeling alive and comfortable in your own body people recognize it and are instantly attracted and drawn to you. They want to do business with you, they want to make deals with you, they want to be friends, they want to laugh and all of a sudden you start to become so interactable with everyone else that life just seems to be flowing smoothly and life starts to unfold itself for you.

Pineal Gland – Circadian Rhythms

http://coryherter.com/?p=416

The third system associated with the pineal gland is circadian rhythms. Most people only talk about 24 hour cycles, but there are 28 day cycles, knows as a moon cycle for woman and for men, there are 3 month and 6 month cycles, 1 year cycles and 4 year cycles. These cycles and more are really related to our connection with the Earth, the sun, moon, solar system, galaxies and planets. Your circadian rhythm is actually what links all of us together, so if this system is suppressed in the pineal gland, you'll always feel out of sink. In other words, you'll show up late, you'll arrive late, you'll arrive way too early and you always seem to miss that moment, miss that spot. You're also always in the past or the future and have a hard time being in the moment where all the magic really happens.

You may also have difficulty if you're out at a party and aren't able to connect with everyone there. It feels like you're out of sink or out of vibe and what starts to happen is you'll start to isolate yourself into tiny little groups, not able to get out and to experience all the amazing people on the planet. In addition to being responsible for our connection with all the people outside of our self, circadian rhythms are also responsible for our connection with nature, animals and pets. It's amazing when you start activating the circadian rhythm. Things can seem as if everything just lands in front of you step by step as if life was serving you and you are a master over life. Synchronicities just kept happening and you feel so alive, so full, as if everything is here for you. That's something we should feel all the time because life is here for us, it's here to serve us. It's when we fall out of sink with life that we start to doubt ourselves and start to question our own power and our own integrity. We question our own actions yet when we really start to understand the pineal gland if we activate this region, the circadian rhythms in the pineal gland begin to put us into the flow more easily where we experience those synchronistic events continuously. I have figured out how to harness this system through mathematics and technology. While we have all experienced synchronicity on some level, I've found that very few of us have actually felt the alignment in circadian rhythm.

This third function of the pineal gland it is so important to our everyday functioning. When you start to activate this circadian rhythm system, you meet the right people at the right time who are going to move you in the right direction, you'll stop wasting your time with people who are wasting your time and don't have any actual information and don't have anywhere to take you. Those people are playing a part in somebody else's story not yours. For you to walk into a room with a 100 people and to know who to go to and who not to go to is an ability beyond logic. The pineal gland, your body, and the connection to the world around you through circadian rhythms can actually find those few right people in a room full of a 100 people to move you forward. This is just one little bit of what the pineal gland does and what Sacred G Fusion is actually built to do. To be able to harness this into a technology and be able to offer the power of synchronistic events in your life is an absolute honor.

Pineal Gland – The Natural Healing Mechanism… Sleep

http://coryherter.com/?p=414

To have eternal life is really the ultimate quest for a human being. The next function of the pineal gland is probably the most important part especially considering my mission of creating the ultimate anti-aging technology on the planet. Life really doesn't even begin until your actually living forever with a body that regenerates itself continuously. Most people don't think about how the body can live forever. We all die, but death is actually the biggest and greatest disease that humankind has ever faced. Most people don't look at death as an actual disease. By the age of 2 to 3 years old the body makes a calculation. It realizes that it's storing and utilizing more energy throughout the day than it's freeing up and generating at night. As soon as your brain realizes that it's losing energy by spending more throughout the day than it's generating at night when it sleeps it realizes it's going to die. When the body realizes its going to die it shuts itself down it puts itself into a survival-like state where the body no longer continues to open up new levels of awareness and new senses. In fact, it starts to do the opposite it starts to horde energy.

You can see this change in a child when they go from "here is my toy, do you want to play?" to not wanting to share his toys. This is so crucial because at the moment the calculation is made, that child's natural development processes instantly takes a major turn for the worst. The body automatically starts to look for more energy so that it can survive, so it starts to look outside for toys, then as the years go by, the body starts to look for relationships, other people, cars, houses and money. All these material things to try and give itself more energy except its looking in the wrong place. The energy the body is seeking is actually stored in the body in the form of memories and emotion.

Every single one of us can think back to a major event in our life and we can start to feel the emotion start to surface. This emotion is actually energy in motion in other words your brain is storing this emotion as energy. At one time your brain used this energy and your body used this energy to operate itself to run all its systems. Since that energy is back-logged or backed up in all of the unprocessed memories from your history, and you continue to take on more emotions and memories that you don't process daily, your body experiences a gradual decline of energy, forced to shut down more and more systems to the point where it can no longer survive and death happens. What is necessary is to increase the daily amount of energy, in other words, start conserving the amount of energy used up during the daytime and at night time amplify the amount of energy and healing and regeneration.

This is what Sacred G Fusion technology actually does. It's designed to enhance the body's natural sleep process or natural healing process while you're sleeping at night. All you have to do with this technology is sleep on it and it completely transforms your life with the amount of energy.

But where is this energy coming from? It's not coming from the technology, the energy is actually coming from inside of you, inside your own memories. The technology is providing waves, it's providing instructions, and it's teaching your brain how to process the energy, information, emotion, and memories more effectively. In other words, you're actually healing yourself as you clear out emotion. As you start dreaming more at nighttime you're processing more memories so you're freeing up extra energy. If you're sleeping on enough Sacred G Fusion, your body will actually make the calculation where it realizes, hey wait a second I am actually freeing up more energy at nighttime than what I'm storing during the daytime and the body starts doing this amazing thing. It starts unlocking itself it starts opening itself up and it starts coming out of this survival state. Your whole body and your whole experience of reality shifts at that moment because the body realizes that its constantly regenerating itself now and its going to live on in perpetual motion its going to keep regenerating more and more energy every single night you sleep on it.

Your body starts unlocking new senses that have been dormant or senses that you've never actually had access to throughout your life. Your experience of life becomes richer and deeper. All those little aches and pains start disappearing. You start to want to become more active. This is literally the number one most important thing about Sacred G Fusion is the fact that it helps your body produce enough energy to actually open up, shift out of survival state, activate, and start healing. That's where life takes a really big shift.

Pineal Gland – Speed / Temperature

http://coryherter.com/?p=412

The last system regarding the pineal gland contains the programming for both speed and temperature. The pineal gland is responsible for regulating temperature in the body but not only in the body. If you've ever done any type of energy work or energy healing, you've probably noticed you either feel a cool or hot sensation you'll also notice that by sticking your hand on or slightly above the Sacred G technology, you'll feel that same cool or hot breeze which shows that the temperature in the pineal gland is actually being affected. Your body is being affected by this vibration technology that's one of the very first indicators that Sacred G technology actually works. If you look at the infrared testing done on the Sacred G Micros used with cell phones, you'll notice that 4 Sacred G Micros on a cell phone will reduce heat by 87% which is incredible because it's actually the heat from the cell phone that starts to cook your brain and make it more vulnerable to the electromagnetic frequencies that are coming off your cell phone. This is one example of how Sacred G works.

Speed is regulated by this same system in the pineal gland. Speed refers to how fast you are traveling through life. If you can slow down and analyze your situation and gather more information when you need it and then speed back up and blast forward to really get the job done to make whatever you need to have happen. A lot of people get stuck in one speed. They're either too slowed down, trying to get momentum, trying to take action, or they're always taking action and they can't actually slow down to take a moment to think. If you can't slow down, you get caught up in unproductive loops and repetitive cycles in life. The activation and stabilization of both temperature and speed helps you to overcome things like coffee and helps you to stabilize and activate your adrenal glands. Adrenaline is a system that starts to be more activated and utilized more effectively by your body. Instead of just being activated through fight or flight, which are survival states, your body overcomes these survival states through sleeping on Sacred G Fusion bed sets. Adrenaline is then used when combined with DMT to unlock a whole new and unique type of spiritual experience.

When I talk about speed, I am also talking about weight, which means muscle mass versus fat having the optimum body weight and size having your body tweaked which means not only having muscle but having very dense muscle that has been activated that has been trained and refined again these are all parts of the pineal gland that are activated by the use of Sacred G Fusion.

Pineal Gland – Conclusion

http://coryherter.com/?p=409

As you can see the pineal gland is the ultimate gland of the entire body. It regulates your connection with Source, your connection with your body, your connection with other people, your environment, and with the Earth. It regulates sleep which is your body's natural healing mechanism. Try going without sleep for 3 days and see how well your body does. You just can't do it. Your body has to have sleep and not only sleep but extremely effective sleep and the pineal gland is responsible for regulating that. The pineal gland is also responsible for regulating speed and temperature which is how fast you are travelling through life, and being able to slow down or speed up your life when you need for ultimate productivity.

The pineal gland is the master gland and the literal third eye. When every single religion describes spiritual or euphoric experiences, they are referring to the activation of this third eye, this inner sight, this mind's eye. Some people refer to the third eye as the all-seeing eye, the eye of God, the eye of Rah. This eye is incredible and Sacred G Fusion is specifically built for this. All other Sacred G designs influence different regions of the brain. Sacred G Fusion can also influence all of those other regions as well, but the pineal gland essentially sits at the top of those other systems in the brain. If you'd like to learn about those, you can watch the videos on the other Sacred G designs and what parts of the brain they affect. Sacred G Fusion and the pineal gland is like the hub in the middle of the circle that pulls and ties everything together and makes everything work like magic. If you'd like to learn more about the pineal gland, you can search the internet. If you'd like to learn more about DMT, read "The Spirit Molecule" by Dr. Rick Strassman.

Remember to drink good water not tap water that has the poisons and toxins that calcify the pineal gland and remember to charge it with Sacred G Fusion. Get out and get some Sacred G Fusion and really activate your body and activate your life. Get yourself out of that survival state because there's a whole world and incredible spiritual abilities waiting to be unlocked.

Sacred G Designs

Thank you for downloading your free Sacred G technology. Sacred g is an incredible vibrational energy product designed to open up and maximize human potential. There is a series of processes that take place in your body as a result of using this technology. Each Sacred G design that you printed focuses into different aspects of the brain and each one has its own unique benefits. Sacred G Fusion is a conglomeration of them all and links and integrates them all together to really maximize the full potential of sacred geometry. What I am going to do is explain the process that you go through and explain what each Sacred G design is going to enhance. This way you can choose what type of energy and what type of growth and development you want to go through.

If you did not download your free Sacred G technology yet, click here:

www.coryherterstore.com

Sacred G Spot



http://coryherter.com/?p=557

The G-Spot design focuses into cleansing the cells in your body and is powerful for detoxing the body.

There is a 6-stage sequence for how sacred g technology works to boost energy and increase health. The sequence is very simple, first your cells absorb this vibration or this energy through a subsystem of DNA called epigenetics which essentially determines where your DNA splits for what types of proteins are going to be

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

produced in your cells. This has to do with the operation of the cell but it also has to do with how your cells are functioning.

One of the first things that takes place as a result of using Sacred G technology is a cleanse. Your cells will literally start detoxing and eliminate toxins that have built up over the years. If you've done a lot of drugs or pharmaceutical drugs you'll notice that those will start to detox or cleanse from you. You might start going to the bathroom a few extra times the first few days, you might get some headaches, you might experience some old pains that come back up as your cells are releasing their memory.

This process is actually what generates energy for you. This is what that saying that you actually heal yourself is talking about. You are actually healing yourself by going through this process. Sacred G doesn't give you energy it gives your cells instructions for how to function and those instructions tell your cells to cleanse their history or their memory. The toxins inside are inhibiting the cell's function their flow and their performance in other words inhibiting the amount of positive energy that you feel inside your body. This is how cells break down and age this is what Sacred G does and this is specifically the Sacred G spot that actually focuses into cleansing your cells.

The Sacred G Spot focuses into the hypothalamus in your brain and is a master gland that regulates all the chemistry inside your body. Using this technology can help you to activate your hypothalamus. When your hypothalamus lacks energy your body starts to run almost like a dictatorship it doesn't want you to grow it doesn't want to change it wants to put you into patterns so it doesn't have to change any of the body chemistry and it locks you into a prison. As you build up toxins the cells get so stagnate that they don't want to shift for you, typically your body is supposed to adapt to whatever situation you are doing in that moment. That's what makes us function effectively in any job your doing or any activity. When you're having fun or out partying and you can't adjust and get into that moment with your family or friends you can't really take part in the treasure that we call life.

This is the very first step that Sacred G is designed to do is to activate and to open up your hypothalamus and open up your body so you can start to change and adapt to any situation that you come across. What you'll also start to notice is a mass amount of energy because as your body clears out these toxins your body is just going to feel better a lot of things happens as a result of this first phase. A lot of people turn to vegetarian diets or if they're vegetarian a lot of people go raw, simply because they can feel the heaviness of heavy foods that aren't good for you which is why it is so important to charge all of your food your water and anything you put on, in or around your body.

During this first phase never use a product that has toxic chemicals in it, only use products that are green, organic and healthy for your body. Any lotion you put on your body you should also be able to eat it because your skin is actually going to eat it. It's going to go into your body. This is the first phase of what Sacred G technology is going to take you through and it's what the Sacred G spot really focuses into. So if you notice you have any kind of cleansing effects such as headaches or your getting old injuries, try putting the Sacred G spot on the spot where it hurts and you'll notice it will take away a lot of the pain.

You can charge your water and it will charge the water to help detoxify your body. So with any type of cleansing that you're doing you can literally charge any type of herb or supplement or food or drink to help your body detoxify just simply by charging it up with the Sacred G spot. This will bring your body into alignment and will help you feel better about whom you are making you feel more comfortable inside of your body again. This is the very first phase of how you are going to increase energy inside of your body. Sacred G is not a magical technology, it doesn't just give your energy from nowhere, and you actually have to generate that energy from inside your body. It is a karma principle, whatever you put in you have to be responsible for taking out.

Transporter



http://coryherter.com/?p=555

The Sacred G Transporter design focuses on the emotional clearing of past memories and current experiences as well.

The second place you are going to get energy from using Sacred G technology is from emotion stored in past memories. I used to do a seminar called the number one reason for every health problem is that our brain becomes congested with emotion from past memories and our brains can't keep up. Emotion stands for energy in motion, in other words its energy that the body used to be able to use to operate its systems and functionality and now that energy is caught up and trapped inside emotion. Your body no longer has access to that energy anymore.

When you're sleeping your brain is discharging your brain wave states processing your memories from the day and freeing up that energy. When you are opening and using more energy during the daytime than what your brain is freeing up during the night it doesn't take very long at all until your body realizes it is losing energy every single day. As soon as your brain makes that calculation it puts the body into a survival state and literally starts shutting down your senses and shutting down your body and it will not activate a lot of the future senses and abilities that the body is capable of, especially the more enhanced and activated spiritual abilities that we are all capable of. This usually happens at the age of two, three or four years of age. You can see it in a child when their brain makes this calculation when the child goes from "hey these are my toys, you want to share? Do you want to play?" to "its mine!" And as soon as they go "it's mine!" their brain just realized it's using more energy than its freeing up at night time.

When the body realizes it's going to die it wants more energy and it starts to horde. Hording the toys is the beginning of a survival state and we never recoup from this survival state. As we get older it changes to people; he's mine, she's mine, that job is mine, that car is mine. Hording material possessions and an endless need to have to own more things and own people and control and manipulate to try to get what we want is really our body saying I don't have enough energy and you're still not giving me the right type of energy. The energy your body wants is this internal energy so that it can heal itself, so how do we offer that? One, we have to increase the amount of healing that takes place why we are sleeping this is so important if you increase the amount of energy that is freed up at night time why you are sleeping in other words enhancing the natural healing process while you sleep. If you can increase that to a point where you are freeing up more energy at night time than you are using in the day your body will make another calculation it will say the body is no longer dying its now starting to regenerate its freeing up more energy every single day. Something happens inside, you come out of this survival state.

Instead of all these outward possessions becoming so important, you find this peace you find this calmness inside. You'll lose that edge you lose the rush of needing things outside of yourself you start to become very fulfilled. This is what we are all looking for, is this inner fulfillment this inner peace and the inner peace comes as we open up all this energy so that's one of the things that Sacred G technology is actually designed for is to help you to go inside at night time when you are sleeping and accelerate this natural healing process. The more Sacred G you use the more this will happen. So what exactly happens at nighttime while you are sleeping? First off when you first start sleeping on Sacred G you might get some tossing and turning the first few nights or even the first few weeks and if you get that it's essentially your beta brain wave state. you have a lot of extra energy and blocks built into it and you get into these anxiety states and typically it's because you just hate your life, you hate what you're doing you hate how you're serving, you hate how you have the same job for so many years, you're not happy with your situation and it starts to bring up all these emotions you have been suppressing all these years and it brings them up and puts them in your face and it makes you deal with them. All of sudden you can't handle it anymore and bam! You have to make some big changes in your life in order for your sleep to actually shift. This is part of Sacred G technology helping you to transform what is taking place in your life and to stop letting things go, stop letting your life go and start going for what you want instead of just settling for less. That is not what we are here for, we are here to have the life of our dreams.

The second thing that you can notice is more dream and nightmares taking place. This is all of your past memories and past emotions clearing out. Your brain takes all of your memories and cuts them into little snippets and links them all together. This is why your dreams are all scattered and all over the place, because its processing series of memories which all have to do with the same types of patterns and processing it all so you that you can release these patterns and step out of these zombie like states. This is where you start to become alive and animated and where all of your energy will come from. This is where you step back into your power and take your power back and you actually start living the life that you are looking for.

This part of the process actually has to do with the limbic system, which is responsible for storing all the emotion from your past. Now if you look back into any major memory and you focus on that memory for a little while, you'll actually feel the emotion come back up. That emotion is simply indicating to you that there is still a lot of unprocessed feelings and energy back in some memory that could 20, 30, or 40 years ago that is literally still holding you back. So when you start cutting those cords and clearing that emotional energy, not only do you let go of those attachments from the past so you can live more in the moment, but you also get new information and new understanding about who you are. You get new lessons and fears you have as result of traumas disappear and you stop putting yourself into a prison to protect yourself. This whole process is actually initiated from the Sacred G design called the Transporter that focuses literally into the limbic system for emotional processing.

Now that is a massive resource of energy, so once that emotion is processed the body can use that energy to start healing itself. Sacred G help to heal on you, the more emotion that is processed the more energy that is freed up so your body takes that energy and it says where can the body best use that energy to reactive it to heal it more effectively so the more memories you process the more energy you are going to generate the more health and healing you are going to attain.

As you really start to heal the body it's not just about healing the body, is literally only the first step. That's all about performance and opening yourself to a whole other way to experience reality so that is the second way that Sacred G frees up

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

energy inside of you and that energy is inside of you It's not from Sacred G it just puts you through the process and when you go through that process your doing the work to free up that energy. If you have a couple nightmares and you're not sure you want to sleep on this technology, let me tell you one thing; your limbic system is directly connected to your hypothalamus and regulates your body's chemistry. If you have extreme nightmares, that's extreme negative energy. When that emotional energy is converted to chemical energy from your limbic system to your hypothalamus, that negative energy is converted to chemical energy that energy is the stuff that actually kills you. In the end when you have that anxiety that is coming up and you can't handle sleeping on this technology at night, that's that energy that's saying I hate my life I don't even know why am here you lose your purpose you lose your point going through that helps you find who you are and your purpose.

Your point it helps you get back on track with your life cleansing emotionally can sometimes be a little difficult but stick with it go through it use the Sacred G meditation on the website attend some of the webinars get some of that energy moving get on a community get on a chat get some support from people who are using this technology if you are having a hard time go through the process this is your life this is your energy

Ascender



http://coryherter.com/?p=553

The Sacred G Ascender design helps you to resolve and internal information

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

conflicts and false belief systems. The Ascender also helps to gain focus and clarity in your life and identify your goals.

Sacred G doesn't just give you energy; Sacred G walks you through a process which generates more energy from within. This energy is your energy, the regulators, the vibrations and everything that is set with Sacred G is all customized specifically for you and your experience. It's your body that is actually running this energy and this development and healing process. There is a development system that every single body has built into it, which is have been walking you through this process but our experience of Sacred G is completely unique and all customized for us individually.

This next phase of Sacred G is built off of your belief systems. Belief systems are how you like things, your perceptions, do you like experiences in life to happen slow or fast? Are there certain aspects of your life you like to happen fast and others you like to happen slow? How do you set all your regulators for how you experience life? The next phase of Sacred G starts opening up belief systems that you have created throughout your life, some because of passion some because of trauma.

When you start focusing into these belief systems, you'll find that there are a lot of belief systems that are not really serving you anymore. In fact a lot of belief systems is our brain beating itself up and beating us up telling us that we can't do it or that we are not enough or that we are not smart enough. We have all these belief system inside and what are they there for? They are sitting there telling us these things so that we don't expend our energy.

Remember that when we are in a survival state it does not want to expend energy it wants to conserve it. As soon as you start to think of new ideas or new places to go or new things to do your body is like no we can just sit here, lets just sit here and watch TV or do something less strenuous. However when you start opening up your body, in this next phase and start clearing up all the energy from cleansing all the toxins and clearing out all the emotions from past memories, you start opening up energy and your body starts feeling better and starts coming out of this survival state.

All these belief systems and all these thoughts have to be reconfigured. There is a whole process you have to go through coming from "Oh I don't know maybe we shouldn't do that" to "Hey I'm open let's do it! I've never experienced that before lets give it a shot" and jumping in and actually immersing yourself into part of the game. This phase of Sacred G is the Ascender design, which will open up or unlock your belief systems.

If you have ever heard of post dramatic stress disorder or multiple personalities, what happens anytime the body is induced with massive amount of emotional energy especially if it is negative because your limbic system is directly connected with your frontal lobe which is what is responsible for organizing all your belief systems if you induce a massive amount of negative emotional energy it forces your frontal lobe all of your beliefs your personality your identity to actually split and when it splits it goes from one unified identity to two separate halves and they are in opposite polarities so those are things like bi polar depression and schizophrenia all that is actually induced by traumatic states or not properly wiring the brain as you are growing up through childhood. So one of the things that the ascender does is it starts taking all of these opposites and these two halves and as you clear out the negative emotion through sleeping it automatically forces your frontal lobe or your brain to start solving conflicts and when you take two pieces of conflicting information and you find a unifying piece of information you get this third piece up here which unifies these two you get out of this land of the opposites and we move into a unified state and this unified state all of sudden you have a new piece of information and with this new piece of information we have a new perception.

A lot times you'll start talking especially with the ascender and this phase of Sacred G technology a lot of times someone will ask you about something you'll start talking and you'll think "wow I've never really thought that way before." You are actually seeing some of the changes that are taking place internally but your actually seeing them in hindsight. This is one of the most amazing processes, especially for people who value information so much and have a massive amount of information and who are really in the game to figuring out how things work because the ascender will literally start solving pieces of information for people. What starts to happen if you have this identity and self over here and another identity and self over here and all of a sudden you eliminate all the things that cause separation between the two of them they come together into this bigger personality this bigger identity and this bigger identity contains more energy because you've got more active neural activity inside of your brain.

If you've had that experience before where you start making these internal connections and you finally get it and you get this rush of energy and you get tingle down your arms and legs your just vibrating with energy that is actually what has happened. Two different identities have solved conflict and have actually joined and integrated together. This is essentially kind of like putting humpty dumpty back together again. As you start to increase the size of your identities, confidence goes up with confidence comes more energy. You feel like you have more energy that's because you have more neural activity in your brain and more communication going on through your body. you can quickly make decisions you can take a lot more information in at once you can see larger patterns because you can see more information at once in other words you can download more information actively into the neurons in the brain so you can detect larger patterns.

The bigger the pattern you can see in life, you start to become aware of some of the major belief systems that drive all of your actions throughout your entire life so you can start to set yourself free from those. You start to see patterns in your business, in your job, in the way you spend money, and the way your relationships happen. You start to identify how to see more information at once but those all end up leading to creating smarter, wiser choices for you in the long run. This is one of the amazing things about the Ascender design is its ability to unlock new information to you. Unlock new perceptions and overcome conflicting belief systems and really open your mind to new information and new experiences and to let go of that overwhelmed feeling of where we are and the conscious understanding of who we are.

Trancendance



http://coryherter.com/?p=551

The Sacred G TranceNdance design assists in clearing emotion from past memories as well as solving internal information conflicts. TranceNdance is specifically designed to increase intuition and unlock new perceptions and strands of information.

The Sacred G Trancendance design is by far the most popular design. This design essentially helps to cleanse and detoxify the cells, process the emotional memory from our past and also what the ascender design does. So it's kind of a conglomeration of the past three; the g spot, the transporter and the ascender. This was crucial in order for me to step forward into the next one. Everyone loves the Sacred G Trancendance, it charges water, you can do everything with it. It's very powerful because it's combination of the last three. It's been designed to kick in some of the artificial intelligence or the ability to start downloading and streaming new information from cleansing cells, clearing out the emotion and then solving the information. Trancendance helps unlock these information systems even further.

A lot of the research has been done with Trancecendance. We have had celery last in the refrigerator for about a month compared to uncharged celery only lasting four days. Lettuce literally lasts in the refrigerator for three months, milk lasts for two or three months. We've had bread that doesn't mold, flowers lasting three to four weeks normally wilting up and dying after one week, contact lenses that are disposable that are only good for a week lasting three to four weeks because it stops the protein buildup. So many cool things have been done with Trancendance because we have passed around to so many to people freely and now that we have opened up all the designs there is so many cool types of research that we can do. I hope you are going to get involved with it and create research projects and do them and track the results and really being part of the Sacred G. This is a massive discovery for how to really open up the capabilities and the potential of life.

Simulator



http://coryherter.com/?p=549

The Sacred G Simulator design helps you to learn how to express what is inside. Speaking your heart and mind and being authentic with your own experience is a major part of the transformation induced by this Sacred G design. This design is also called the simulator as it bridges your internal reality with your external one to prepare you for taking action towards your dreams.

The next phase that Sacred G will take you through is the fourth phase. The first phase was clearing and detoxifying the cells. The second phase was clearing out the emotion from past memories. The third phase was reconstructing your neural network or how your brain is organized and how it organizes all your information, eliminating the conflicts and doing that to boost energy, boost confidence, and boost intelligence. The fourth phase has to do with expression. Expression is so important. Now if you watch my videos labeled 2006, you can see that the Simulator wasn't actually developed then. In fact, I only developed the Simulator

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

after those seminars, and you'll see the difference in my expression and my animation. Now after spending about 14 months on the Simulator, you'll see the difference in the way I express myself, and how much I've opened up my expression abilities.

Now there are actually three regions of the brain that the Simulator opens up, and those are the parietal, occipital, and temporal lobes. In other words, it opens up your ability to take your thoughts and convert them into language. You know that when you talk to somebody, you're actually hearing what you say and you're kind of getting a visual image of what you're saying as well. When your trying to figure something out, it's so much easier if you have someone to talk to because you start understanding it deeper because you are starting to convert it from an internal or a two-dimensional state to an external or a three- dimensional state.

A lot of people ask me, "How can you put these designs onto a flat piece of paper and expect them to do anything?" We live in a three-dimensional world but this layer of programming is actually what takes this energy and reconverts it back out into our three-dimensional reality. Before this, it was all just internal changes and changes that were happening inside of you. Now with the expression, the changes that are happening internally as a result of using Sacred G can really start to manifest through your expression.

So if you have ever heard of the spiritual ability of channeling or being able to download new information, what you are really doing is channeling information that the previous design, the Ascender, unlocked by solving conflicts in your own belief systems. As it is unlocking new information, your brain has to bring conscious awareness of that information. So what starts to happen is someone asks you a question and all of a sudden, boom, it comes through you. You're talking it, and you've never heard that information before but you talk like you've known it forever. You're like, "Oh yeah! That's how it works." and you're like "Whoa, cool!" It's cool when you get into this one. It's a really cool one.

It's called the Simulator because this one actually sets up simulations, so after you change your belief systems and you say, "OK, this is what I really want in my life," the body says, "OK, well, we need to just confirm that." So what the Simulator does is actually create a simulation in your life and give you an opportunity to actually choose that other choice that you want to get you out of that other pattern. What is really cool about the Simulator is that if you don't pass that little test to change your programming, it will create another one, only bigger, and it will create it even bigger so you have to pass the test to get what you are actually looking for. It almost becomes this mechanical game of the technology literally walking you through the process, helping you change all your perimeters and regulators inside of your brain so you can have the actual reality that you are looking for.

The Simulator also focuses into helping you to be able to actually express what is in your heart and not just what other people want to hear, but actually saying what you really feel, even if that means opening up to conflict. It means opening up to whatever possibility, but opening yourself up and opening your heart up and opening up who you really are inside. So it really forces you to start coming into integrity to who you truly are and what you're here for.

That's a really major change, and we actually had the Simulators on posters, which we called the Love Chargers, and a lot of people made some pretty major changes in their lives with relationships, with jobs, with careers. Usually people who were working in the same job for 10 years and didn't move up, just quit their job. They had all this anger and rage that came up at their job, at their boss. Why… because everyone else was growing, and they weren't. The company wasn't taking caring of them, so why are they there? They could be moving their life forward. They could be growing. They could be becoming more, but because they weren't expressing themselves, their needs weren't being met, so there was really nothing else to do besides go somewhere new and start actually growing and getting the life they are really looking for.

This is where this energy in Sacred G technology really starts to come out into your external life because after making all these internal changes you have to integrate them into your physical reality in order to make them real. So that's where Sacred G starts to set aside all of the other vibrational technologies because of these conversion systems to get your thoughts out here and start manifesting into reality. That's where people usually get caught up. They're always looking for ways to manifest and meditate more and open themselves spiritually more, so that they can get out here. The Simulator is really what starts that process. It's amazing!

There's so many people in the world looking for this technology, looking for the Simulator right now, and have no idea that is what actually will retrain their brain to get them into that state of mind so that they can manifest the life that they are looking for. It does so much! I learned so much about the new memory systems and about expressions and how to really get out here again. Watch my videos from 2006 and watch them now and see the difference in my animation and how much more alive and how much more energy I have from literally the result of the Simulator.

Activator

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.



http://coryherter.com/?p=547

The Sacred G Activator design is specifically built to activate your body. Focusing on movement, motion and space, the Activator is all about the value of getting out of your head and back into your body so you can create the life you have dreamed of.

The fifth phase of Sacred G technology is going to walk you through another region of your brain, and it actually has to do with your cerebellum. Now your cerebellum is located in the back of your skull, and your cerebellum is the very last place that you can use your brain to do any tweaks to this vibrational energy. The cerebellum has to do with motion movement. It means taking the first step, making it happen, taking baby steps, moving forward, moving your ideas forward, not just expressing what you want, but taking action steps to make it happen. So instead of talking to your mom or dad or your friends about doing something you want to do in your life, actually taking that step and talking to professionals who can actually move you in that direction for where you want to go. Since they're already doing it, they have the information you need.

So the cerebellum is really interesting, and the Sacred G Activator is the design that really activates the cerebellum. Of course, we call it the Activator simply because its designed to activate and physically activate the body. So this includes things like working out, getting in shape, taking action steps in your life. Enough talk! Let's go. Let's make it happen. Let's take those action steps! It also has to do with building your identity. What separates you? What sets you apart from everybody else? What is your uniqueness? What is your specialty? Who are you? Why are you different than everyone else? What is your value? This is the level where you really start to manifest and understand your own power because you start to understand your own value and what you are worth. When you understand that, you understand what you can offer. When you understand what you can offer, people know what to look for.

For instance, the process I went through was to understand that my real specialty is near-death experiences, Sacred G technology, anti-aging, and memory systems because I brought my memory back. I know my specialties for what I am good at, there's a lot of things I'm not good at, but those things don't matter. All I have to do is focus on my own personal specialties because that is what I am going to offer to the world. That is what the Activator is really designed for, to prep you, and get you ready to make you get out there and to get you in that flow. So it's the very last phase to restructuring your internal core so that you can get out into the world and really make your magic happen on the planet. You can be somebody who has discovered their own wealth and is available to serve humanity.

Now the cerebellum is really unique. This is where with the Activators we really started to understand the value of the Sacred G bed sets. Your cerebellum contains more than half the amount of neurons in your entire brain and compresses them into a region of only 10% of the space of your entire brain. That's how compact and compressed these neurons are. That is pretty dense energy. What we started to learn with the technology, when we add more, and stack them together, is that what it does is increase the density of the energy field. That density was required to activate the cerebellum. That's when we started coming out with the cases of the posters and the bed sets because it took that much energy to activate that region of the brain. So the difference between the Simulator and the Activator was that it really pulled out the need for the bed sets to really manifest and harness what Sacred G can really do. Another thing about the Activator is that besides just running a simulation like the Simulators, the Activators will not only run a simulation but it will actually walk you to that right space in the room to the right person. So the Simulator can express what you need because your thoughts have already been attuned from the Ascender. You say what you need, and all of sudden you're making these really amazing connections to move your life forward to where you want it to go. This is where the real magic starts to happen. It's not fully activated, but this is where it starts to happen. It's training you on a process for how to really manifest your dreams.

So that's all the synchronicities in your life. It's your connection with your external environment. Your cerebellum, because it has to do with motion and movement, is a three-dimensional mathematical equation. The Activator is a three-dimensional system, so it will influence the ways that you move. You start to feel pressure in yourself, in your movements, and other people. Your senses start to enhance. People that slept on the Activator bed sets noticed that all their senses started to open up, especially making love and expressing their sensuality. Because they are exposed to the technology through making love, they started to open up. The body is healing faster at nighttime from doing workouts and pushing your body to the extreme, especially with extreme sports.

So that’s all part of the Activator and something that is really crucial for unlocking our true potential and training our brain, our body, and ourselves on how to really be in the flow of energy in this external three-dimensional environment. Not only linking up our emotions, our thoughts, and our expressions, but also our physical movement, as in knowing where to go, when to leave, who to talk to and who not to talk to, as well as some people take up your time. So sometimes we get caught up, the Activator says, “I got to go… sorry, my body is just taking me.”

Each one of the Sacred G designs is focused into specific regions of the brain to activate it. Now what is really amazing about the Activators is that it completed this cycle of energy. When this cycle was completed, it would start another cycle, but you would increase the amount of energy units inside your pineal gland. That’s what it was, all for if you could continually increase the amount of energy flow in this cycle or the amount of inner chi in this cycle. If we can increase the amount of energy in this flow, what we start to do is actually activate the pineal gland and the pineal gland has all the magic in it, including the DMT, the connection to Source, the ability to regulate brain waves, and the ability to regulate and activate hormones for maximum growth potentiality, sexuality, and sensuality. It opens life up. The pineal gland is literally that point, that central region of the brain that we are all looking for that really identifies who we really are. It’s our connection to Source. It’s our spiritual self and our physical body. It’s our environment. It’s every level of us compacted into one single unit. It’s the singularity point.

So the more we can go through this flow of energy using all the Sacred G designs, the more the pineal gland starts to activate. It only took me a little bit longer of integrating, going through all the tests and the activations I had to go through with the Activator to reach the next level of technology.

Sacred G Fusion



http://coryherter.com/?p=545

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Sacred G Fusion – (Available only in Cases)
Sacred G Fusion is the ultimate Sacred G design that integrates every single Sacred G Design into one cohesive unit. This design enables you and your body to focus into whichever previous design at any time to clear and activate each system for maximum energy production. The Sacred G Fusion also has additional programming that focuses entirely on the pineal gland, activating your connection with God, your body, your environment, and the people in your environment.

Sacred G Fusion is not just another Sacred G Design, it's a highly advanced system that enables you to function on a whole new level that transcends any previous Sacred G Design. Instead of going into specific regions in your brain to increase flow to activate your pineal gland, Sacred G Fusion activates the pineal gland first and then it spreads out into the different regions of your brain. Because it is able to reach more regions of the brain at once, it eliminates a majority of the cleansing and the detoxing effects such as nightmares. You will still be detoxing and may have challenging effects from that but the process will be more smooth, fast and efficient. Each different Sacred G design prior to Fusion mainly affects one of five different areas of the brain. Sacred G Fusion is an incredible tool for activating human potential as it addresses all five areas, increasing the flow of energy to activate the pineal gland. This focus on the pineal gland allows Sacred G Fusion to bring about an experience of singularity, compressing down to the point of all creation. This leads to an intense experience of connection with Source and an unlocking of the spiritual senses, helping us to truly understand and know ourselves inside and out.

Sacred G Fusion has completely transformed my life in 4 months. I've been opening up in ways I haven't even dreamed of and the pineal activation is the key. That connection to Source has allowed me to channel all of these systems and be trained in them as I was taught how to build them. The Sacred G Fusion poster is a minimum of 40 X more powerful than the Activator and the Love Chargers. The power available in Sacred G Fusion deepens one's ability to go within and bring ourselves into complete alignment. What used to take me 2 to 3 weeks to process, now I can process in 2 to 3 days. Everything has been accelerated. I sometimes refer to Fusion as Sacred G 2.0 because it's a whole new type of inner network that you can experience. Here you tap into the magic, the flow, and the synchronicity. Every where I go, I'm always meeting people who just had someone pass over, who had near death experiences. The particular people that I meet are interested in vibrational energy, interested in sacred geometry. Literally every single place I go, I am meeting people who already know of Sacred G. The synchronicities are amazing and at a level that I've never experienced in my life.

Living daily consciously in the flow of synchronicity is something I want for you to experience. We have different Sacred G designs on the website available for free download. I encourage you to print them out and use them to tweak different areas of your life. When you're ready to amplify things and take your life, abilities, and world to a whole new level, I really encourage you to get on Sacred G Fusion. Due to the complexity of the mathematics and design, Sacred G Fusion is only available in poster size. The Fusion design is only available in cases and bed sets simply because I want you to have the full experience and that requires enough energy to actually activate some of the systems.

Sacred G Fusion Case – The Tree of LOVE



http://coryherter.com/?p=543

Sacred G Fusion comes in a specially designed case. Watch the bonus video to learn more about how the Sacred G Fusion works with the Sacred G Fusion case. The case illustrates the Tree of Love and provides a stabilizing container for the intensity of the 300 Fusion posters. On the Tree of Love, you'll notice twelve colored circles that stand for the 12 chakras. Since all vibration technology is at the top chakra, all Sacred G and energy technology falls in the arena of the blue chakra. This is also referred to as the Sacred G Spot and the area associated on the physical body is your head. The green chakra, associated with your chest and heart, is the limbic system and corresponds with the Transporter design. The yellow chakra relates to your identity and has to do with your frontal lobe and the Ascender design. The orange chakra here has to do with your expression that is the Simulator and relates to the knees. The red chakra essentially has to do with your cerebellum, motion movement and that of course is the Activator.

Sacred G Fusion contains the mathematics of the entire Tree of LOVE, walking you through the outer external chakras that have to do with your job, friends, discovering your true purpose and passion, your relationships, family, and the ways in which you give back to the planet. The orange is the friendship, the green is your relationship, the purple is your family, the red is your job, the yellow is about discovering your passion your purpose, and the blue is about serving the planet in a really big way. These chakras actually regulate and explain all the biological systems for unlocking the body. I encourage you to learn more about the Tree of Love through my videos and trainings. You'll come to learn about the double helix inside the geometry of the Tree and the genetic shifts that occur as you move through the chakras. Some of the advanced systems actually reveal the 23 different chromosomes that make up your entire genetic code. There are particularly amazing things to be found in the Tree of Love related to brain wave states: beta, theta, alpha, delta brain as well as the second beta that is the purple chakra.

There are many ways to interact with the Tree of Love and the Fusion case. For example, if you have a stomachache, you can put a glass of water on the case with all your Sacred G Fusion inside. Place the glass over the yellow chakra that represents your stomach. Leave the water there for about 10 minutes and then drink the water. You'll physically feel the difference in your stomach. You can charge up water, jewelry, food, anything you can physically put onto the chakras on the case and it will be energized with vibrations that will be absorbed into your body, particularly into that particular chakra. It's a way to actually direct where you want that energy to go and what you want to enhance in your life. We had great experiences with putting colored candles matching each different chakra on each corresponding chakra on the case. We lit the candles at night and not only was it beautiful to look at, it amplifies the energy in the space. This is powerful when doing crystal mediations and can support experiencing crystal grids.

Sacred G Fusion walks you through the internal and external systems represented in the Tree of Love. Sacred G Fusion combines all of these systems and moves you to the top point, the singularity point we are all one, we are all already perfect. This conversion system of energy exchange moves us forward to really manifest the type of life we want and that sense of perfect flow.

Click on the Category section for the Tree of LOVE to learn more about each Chakra.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Basic Instructions for Using Sacred G Technology

Select something that you eat or drink or anything you would like to charge and put it directly on the Sacred G design. If you want to charge a bottle of water, simply place it on top of the Sacred G. Keep the water on the design for at least an hour although it's great to experiment with the different lengths of time between one hour, several hours and overnight. Whichever Sacred G design you use, it will charge the water to target specific regions of the brain and body. For example, if you charge the water with the Sacred G Spot, then drink the water, that energy is going to focus on the hypothalamus and is going to help detoxify and cleanse your cells. If you charge it up with the Transporter, that water will help you purge and process negative emotions and emotions that are stored in past memories.

If you want to make Sacred G even more powerful, you can use more than one. Using a bottle of water for example, put one design on the bottom and one on the top of the bottle. This creates a pressure field that will enhance the charge of the water. To create an even more intense field, you can enclose the water on six sides. One way this can be done by taping 4 stickers together in a square and putting one on top and one on bottom of the water. This will supercharge your water, supplements or anything you decide to charge.

You can laminate the stickers, posters or print-outs it doesn't hurt at all. In fact, if you're going to laminate them I would suggest printing 3 or 4 sheets with the designs printed on both sides. If one-sided, put them back to back so you have the design facing out on both sides and then laminate several sheets. The more of them you use, the more energy generated which increases the amplitude of the wave or of the frequency Sacred G puts out. If you want to increase the energy, simply add more. Sacred G lasts forever if the designs aren't damaged. Don't cut any of the designs, the pressure systems and mathematics built into them will be affected and you'll have energy leaks. Print them in color not black and white. Put the Sacred G in your closets, on your shelves, in your refrigerator (best if laminated or you can tape them underneath your shelves so they don't get dirty).

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

35 Ways To Boost Your Energy With Sacred G

To see the Online Version, click… http://coryherter.com/?page_id=594
The following uses are listed in order of importance, go down the list and place Sacred G in every area of your environment to get the maximum benefits. I find it best to place them in ways where the technology will not get damaged. For instance, in the closet, you can tack the Sacred G to the wall behind your clothing. In your fridge, tape the Sacred G to the sides of fridge and underneath the shelves. Be creative, remember that Sacred G Fusion is by far the most powerful Sacred G Technology and is available for only $1.00 / sheet.

Mattress

Place the Sacred G technology between your mattress and box spring to encapsulate your self in the energy all night long. You can also place them directly on the floor. If you have cases you can also place the cases directly on the floor. Sacred G enhances anything that you are doing. While you are sleeping your body is working to heal itself and refill your energy. This is the optimum place to use Sacred G technology and enhanced energy and is the long-term solution for boosting energy permanently. Every night, your energy will continue to increase.
If you are looking to heal your body and activate the Law of Attraction in your life, continue adding Sacred G Fusion underneath your mattress. The more Sacred G you add, the more powerful your experience is going to become.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Water

You can create unlimited amounts of pure energized water using Sacred G. Programmed to a level that no other vibrational energy method can compare to, this water is extremely efficient in hydrating the body. Using large amounts of Sacred G love chargers can energize your water so much that you can use it as a dietary supplement to replace 1 meal a day. Take a big drink of sacred g water whenever you are hungry. Charging your water is vital to reducing any negative cleansing effects from releasing toxins. This also helps to hydrate the body increasing the amount of energy you will feel.

Food – Fridge, Freezer & Pantry

Placing the Sacred G Fusion posters or Sacred G stickers inside your fridge freezer and pantry will lengthen the lifespan of your food help you from over eating and help you lose weight. Use tape to attach the posters to the sides and back of the fridge or on the shelves to prevent damage and get the best results. Charging your food will increase the absorption rate reducing the amount of energy the body has to spend to digest. Cleansing the digestive system will be one the first things to happen when using Sacred G. This will free up your energy, reduce fat and enable your body to start eliminating toxins. Charging your food will help prevent additional toxins from entering in your body and prevent waste buildup in the intestines.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Fruit bowl and Bread Basket

Extend the life of your fruit vegetables and bread by sticking them on top of Sacred G technology increases taste energy and fills you up faster. Eat as many fruits and vegetables as possible for optimum levels of energy. Replace sugar with natural sugar from fruits this is especially a powerful practice for children and eliminates emotional outbursts, rage attacks and fighting with family and friends, simply from eliminating sugar from the diet and replacing it with fruit symptoms of ADD/ADHD, depression, bipolar, MPD and more have disappeared.

Health supplements

VITAMIN
200 I.U.
Dietary Supplement
10 Capsu

Supplements and nutritional shakes are being used by millions of people on a constant basis to improve health. Double or triple their effects by having Sacred G Fusion technology under your supplements all times use herbs to direct where in the body you want the Sacred G Fusion energy to go. This is a powerful method to really focus where in your body you want more energy and can be used for accelerated healing.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Clothing

Your clothing is the first line of defensive between you and your vibrational environment place Sacred G Fusion posters in your closet and drawers to keep your clothes boosted with energy this will keep you flying with energy all day long. Most laundry detergents are filled with chemicals that are no good for your body and rub into your skin this can add to the toxins that are put into your body and decrease energy. Find some natural and green laundry detergent to use this will help in a subtle way to keep your energy boosted. All of these green decisions add up to massive boosts of energy and overall health.

Jewelry

Magnetic and ionized bracelets are a popular tool to use to boost energy and are great for pain relief but they also cost hundreds of dollars and they don't have much style. With sacred g fusion technology you can super charge all of your jewelry to keep your energy boosted all day. Keep your energy boosted all day simply by charging all of your jewelry while you sleep with Sacred G. Charging your jewelry is a powerful technique to help with emotional stability.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Cell Phone

Place the sacred g micros on your cell phone to reduce the heat up to 87%and reduce the negative effects of emfs emitted by your cell phone at the same time.
To Learn more about Cell Phone use and to download your Free Cell Phone Sacred G Micros, visit http://www.freeshield.com

Computer

Place Sacred G under your computer monitor and under your keyboard this works great to reduce the brain drain feeling Sacred G can also help reduce the negative effects caused from emf's. Try placing some Sacred G posters around your desk area can increase work productivity by 300%. Stare at the Sacred G Meditation Station to physically and mentally give your self a break from work and energize yourself do this once or twice a day to accelerate the positive benefits of Sacred G.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Personal Hygiene Products

A lot of products that we put on our body everyday are filled with toxic chemicals that poison our body. The more toxic your body is the, more fat the body needs to neutralize and store these toxins. Search around for natural and green products to ensure your not accidently poisoning your own body. Energize all of your beauty products soaps lotions etc… to boost your energy. Charging your products with sacred g will also help the body with eliminating any chemicals that are not beneficial to your body. Remember your skin will digest anything that you put on it. So anything you put on it you should be able to put in your mouth.

Hot Water Tank

Try placing Sacred G Fusion technology around the hot water tank. This energizes your water and is great for bathing and showering as well as cleaning dishes and doing laundry. Notice how soft your skin becomes.

Vehicle

Place Sacred G under your seat when you are driving reduces pain and stiffness from long periods of sitting. This technology is priceless for truck drivers taxi drivers or anyone else who spends a lot of time in their vehicle. Try putting Sacred G stickers on your gas tank, gas tank lid and fuel filter for increase gas mileage.

Picture Frame



Place 1-20 Sacred G Fusion posters in one picture frame to create a massive blast of energy for your room or office place the picture frame for where you want the energy to go. Great for the office the practitioner room and of course the living room and bedroom for maximum energy and productivity. This will help to keep the energy in the air clear and Transcend negative emotions that can cause drama.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Air Ducts and Fuse Box

Use Sacred G Fusion posters in the air ducts in your home. This is a powerful tool to charge up all the air in your house and enable all of your family to benefit from the positive vibrations emitted from Sacred G. Place Sacred G in your fuse box to encode the electricity that enters your home with positive vibrations using more Sacred G fusion will give you stronger benefits and more noticeable differences use one Sacred G Fusion case for this if possible.

Directly on the Body

This technique is extremely for eliminating pain and focusing where you want the body to heal simply face the Sacred G design towards the area of the body you want to increase energy and eliminate pain sleeping on Sacred G Fusion has been known to eliminate chronic back pain within days.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Couch Cushions

Place Sacred G Fusion under couch cushions or directly underneath the couch. Boost your energy and enable you body to relax when you are watching tv, movies or playing video games. You will find that you can become more immersed in the shows you are watching and the emotional reactions will intensify and heighten your experience. This is a great tool for kids. Using Sacred G this way has actually been known to cut down on the amount of time spent sitting in front of the tv increasing the amount of physical activity of children.

Vision Boards


have everything I want.
I am infinitely abundant!
Life is incredible.
I have amazing friends!

Have you ever heard of a vision board? Simply cut out a bunch of pictures and words that you feel passionate about. This is a physical way of moving towards your goals that you want in your life and takes goal setting to the next level. Attach some Sacred G to your vision board to add extra energy to your intentions. This works great for accelerated manifestation if you sleep on Sacred G, place a vision board between your mattress and the Sacred G. This will program the energy to start building the life of your dreams. The energy will pass these instructions into your cells and start the materialization process.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Backpack

Place Sacred G Fusion (Folded Up) in your backpack to charge your lunch and books charging your books with Sacred G technology increases your ability to retain what you read by 300%. Use Sacred G as a bookmark to help you read and absorb the information more effectively.

Flowers and Plants

Help prolong the life of your flowers and plants by placing the Sacred G design underneath the vase. Try using different designs and see if you have different results then share your research with us. Place Sacred G designs under your plants to help them grow strong and come back to life if they are dying.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Massage Oils / Lotions, Shampoo & Conditioner, etc…

Charging massage oil can turn the oil into a powerful pain relief solution. Add some Fusion 137 Essential Oil to increase the Healing Benefits of products that you use everyday.

Crystals and Precious Stones

Certain stones that you hold after charging with Sacred G will generate a massive influx of energy and sensation in your body. Experiment with different types of stones and how each different type of crystal will create a unique feeling for you. Crystals pick up all kinds of vibrations from the environment so it is important to clear and activate them with Sacred G for maximum energy output.

Meditation

Use Sacred G for meditation by sitting or laying down on several Sacred G designs. You can charge up several crystals or rocks and place them on your body, listen to some nice music and let the energy take you for a ride. Burn Candles on top of the Sacred G to take you even deeper.

Yoga mats

Place the Sacred G designs or Sacred G Fusion posters underneath your yoga mat to instantly increase your strength and flexibility. Sleep on Sacred G Fusion to increase the healing at night reducing pain from physically training your body. Sacred G can be used to support physically demanding exercises and to accelerate healing as well.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Extreme Performance Enhancement

Michael Roth
MOUNTAIN MOTORSPORTS
CRUNK!!! ENERGY DRINK
sacredg
Galardi South Enterprises

Place the Sacred G on skateboards surfboards team uniforms or any gear or equipment you use. Watch as your performance is enhanced and your game is improved. Take your performance to the next level by using Sacred G in any and everywhere you can.

Candles

Charge your candles with Sacred G to fill the air in a room with positive vibes. Try this method during or after there has been a big argument in a room to help clear the air and watch as it helps solve the conflict more peacefully. Charging your candles helps boost your concentration helps clear your head and inspire new thoughts to come through. Using Candles with Sacred G is great when working on

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

any creative or artistic activities. Use Sacred G with candles to enhance meditation enabling you to access deeper states of mind. Natural and alternative health practitioners love this simple technique when working with clients as it keeps the energy moving and the room free of stagnant energy.

Contact Lenses / Glasses

Place Sacred G under your contact lenses and glasses and cleaning solutions to make them last longer. Some people have reported disposable lenses lasting 3 to 5 times longer. Using Sacred G stickers placed directly on your eyes for at least 15 minutes a day will awaken your ability to see energy and energetic fields that surround everything. There are layers upon layers in the reality that you exist within when you can amp up your energy enough your body will unveil new layers for you to see for yourself unlock these new layers of reality through Sacred G.

Kitchen Utensils

Charge all your dishes glasses and cutlery to help charge your food even more they will pass the chare onto your food and drink.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Cleaning Products

Activate your cleaning products with Sacred G so they do a better job. The emf's (electro magnetic fields) from power lines program the molecules of these substances to group together. Sacred G splits these clusters apart meaning that the cleaning products can penetrate deeper to enhance their natural cleaning properties. Most cleaners are filled with toxic chemicals try finding ones that are green and natural to help keep your body clean and your energy high

Animals Love Sacred G

Pets will notice the effect of Sacred G instantly. They will start sleeping on your pillow/bed. Cats will chew on the stickers trying to get into where the energy is coming from. Turtles will swim at hyper speed. Pets are one of the easiest ways to see how powerful Sacred G technology really is. Place sacred g under your pets food and water dishes as well as under the area where they sleep. Notice the youthfulness and the increased activity in your pet within days. Place the Sacred G Fusion posters behind the fish tank to keep the water clean 3x as long.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Improving Eyesight and Multi-Dimensional Vision

Lose track of time by staring into the design and wondering how it changed your life so quickly. Sacred G has been known to improve eyesight as well through regular practice of this technique (15 to 30 minutes a day) Sacred G Fusion will also produce some interesting multi-dimensional visuals along with heightened states.

Bath Tub

After a hard day or an extreme workout, the body needs to relax and unwind. Charging up the water in the bathtub by sticking some Sacred G stickers on the bottom will ensure that the water is helping the body heal and increase energy. Trying adding some bath salts to clear out lactic acid. Add some Sacred G 137 essential oils to help give your body that extra boost. Water charged with sacred g will make your skin silky smooth by breaking apart the clusters of water molecules apart enabling a deeper cleanse. Try charging a 5 gallon jug with your Sacred G Fusion and adding one gallon to your bath for an extremely powerful experience

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Pictures & Photo Albums

Have you ever had an experience when you were thinking or talking about someone and then they called? We have all had an invisible connection and we have all felt it. Harness this connection with Sacred G by pumping up other people with energy by placing their picture on some Sacred G. Try it out, the effects might freak you out when you see just how powerful Sacred G can be. This is a perfect tool for when you are having problems with someone and don't know how to solve or overcome it.

Business Cards

Direct the energy of Sacred G into your business by placing a business card face down to increase the growth and wealth. You may notice instant effects from this. This is the next level of simply having a positive intent. A physical action is always more powerful than just a thought. Be open to new ideas and direction in your company if you need to make more connections and build a team use, the simulator. If you are looking for new systems or new ideas to govern your company, use TranceNdance. If you wish to accelerate the momentum of your company use the Activator. If there is too much drama in your company, be sure to use the transporter. Add Sacred G Fusion to your life for an increased focus in wealth building.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Gardening

Charging your seeds before planting them. Your food will taste better last longer and fill you up faster. The amount of energy influences every generation so be sure to replant the new seeds. You can also keep your seed immersed in this field continuously by putting Sacred G stickers or minis that have been laminated directly into the dirt. Experiment and see what kinds of results you get and then let us know. Try placing Sacred G under your sprouts if you make them at home.

Positive Influence

Wish you could change the world in a really big way so people were happier and having more fun? Place pictures of authority figures on Sacred G to give them some positive vibes. Fill them with positive energy so they can make more positive decisions that will benefit all of us. Works great for corporate logos as well.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Sacred G Food Test

In the morning take an apple or a banana and place it in between two Sacred G designs both facing toward the piece of fruit. Leave the fruit sitting all morning, at lunchtime eat the fruit before your regular lunch and feel how full you become. This test will show you how charging your food with Sacred G will fill you up faster. Charging your food is a vital part of boosting your energy even higher. Using Sacred G to charge your food also helps with weight loss.

Sacred G Temperature Test

Place your hand on or a couple of inches above the Sacred G technology. Most people can feel a breeze of cool or warm air. After the temperature stabilizes you will feel tingles and sensations all over your arm and then your body temperature is the first system the technology will stabilize for optimum energy flow. Charging your clothing with Sacred G will help you remain at a comfortable temperature through out your day.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Sacred G Full Body Energy Cleanse

Stand with each foot on one sacred g design then place another Sacred G design on top of your head feel the energy trickle out of your fingertips as you are bathed in energy now add two more Sacred G designs between your hands feel the buzz. This test is a quick energy booster and cleanser as it builds up a pressure of energy throughout your entire body.

The more places you place Sacred G Technology, the more energy you are going to have and the better you are going to feel. Have fun, experiment and see what you can discover. Energy is a playful system that utilizes imagination to its full extent. The only limitation energy will ever have is the limitations that you put on it through a lack of imagination.

When you are ready, be sure to upgrade to a case of Sacred G Fusion for the maximum benefits of this incredible technology.

The following section will help you to understand the processes that take place when beginning your use with Sacred G Technology.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

What to expect when beginning Sacred G Technology

“Karma – Whatever you put in your body, you are responsible for cleaning out!”
~Humbled State of Consciousness

10 Most Common Forms of Cleansing

Cleansing – As the cells in your body dump these toxins out, you can get headaches, feel tired or woozy, your head can feel congested and foggy. These are all signs that Sacred G is working and clearing out the toxins from your cells… Keep Using the Sacred G to complete this process or try adding more to speed this process up further and cleanse even deeper.

1. Initial weight gain can happen if your organs are on toxic overload… your body will take the toxins and store them temporarily in fat cells while your organs are cleansed and strengthened. Then the body will begin releasing the toxins so your organs can properly cleanse and clear them out of the body. You will also notice that your body will continue to lose even more weight, as your organs will continue this purging of toxins eliminating the need for fat. Fat is designed as a safe place to neutralize and store dangerous toxins. The cleansing effects of Sacred G make this technology a powerful tool to add to your weight loss program.

2. Addictions to toxic substances such as drugs, illegal or pharmaceutical, sugar, coffee, yeast, fluoride in water, pesticides on your food and more are continually creating a toxic wasteland… Inside Your Body. Is it any wonder that it becomes difficult to feel good when practically everything in our world is full of processed chemicals that are toxic? Although Sacred G initiates the body to clear these toxins out of your cells, it is your responsibility to stop putting these toxins back into your body. You will notice that your tastes will change and eating organic and healthy will come easily and naturally if you are charging everything you put in, on and around your body with Sacred G. Please keep in mind, that this also means no more putting toxic substances on your body either.

3. Old injuries often come up from using Sacred G Technology. Although an injury heals, the healing is not 100%. As your cells regress back to their youth, anti-aging, they are physically releasing memory. These old injuries can even have physical bruises show back up, can be very painful and can also spur a lot of agitation as well. Stay with it and try using

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Sacred G Fusion Essential Oil on the injury to accelerate the Healing Process. This is a natural process of Sacred G clearing the cellular memory and restoring your cells back to 100% health.

4. If you had drug addictions or taken pharmaceutical drugs for a long period of time, these drugs will release out of your cells and you will feel their effects. You can have urges, withdrawals, mood swings, etc… that is because these drugs are coming out of your cells and hitting your blood stream. Stick with the process and drink lots of charged water.

5. Speed up this entire process by taking the initiative and doing some cleanses that you can pick up at your local health food store. Check the labels and educate yourself on what is healthy for your body and what is not. Don't put anything on your skin that you wouldn't eat. Do yourself a favor and get off the medications. If you feel the detox, stick with the Sacred G… this is Karma, what you put in, you have to take out. And remember to take a cheat day every once in a while, you are still human and need a chance to celebrate from time to time.

6. Nightmares can take place as your body purges the most extreme form of emotional energy from your past. You can wake up in wet sweats as your body simultaneously releases toxins while you are emotionally purging your system. You can also wake up triggered or even aware of patterns that you are playing out that are causing yourself and others a great deal of pain. All of these emotional triggers can be difficult to go through, yet peace is on the other side of this chaos and it is worth it to stick through it.

7. Pretty much every single person will go through a 1 – 3 week rage attack as they wake up and realize they have living their life for everyone else and not themselves. This is a process of re-activating a person's own personal power and is an amazing feeling and confidence booster once this process completes.

8. Deep anxiety can come up as well once you realize that you have been playing the same patterns in your life, your whole life and you have never really been happy. This usually ends up in dissolving old relationships, friendships or jobs that are not serving you. Although these changes can sometimes make for a difficult transition, sticking with them and going through the process is rewarding in itself when you are on track with your life, your heart and your purpose once again.

9. Little bursts of emotion can come out at anytime of the day for the first while on Sacred G Technology as memories are busy processing in the back ground of your brain. It seems as quick as they come, they go just as quickly too. These emotional surges are the body's way of completing the

last conscious processing step and are necessary for a complete release. The majority of the time you won't even know what the emotion is from.

10. If you have a lot of deep seated emotion come up from never expressing how you feel, the best thing to do is to lay on your Sacred G Fusion Bed Set as often as possible to help you purge this emotion and free up this energy.

Rewards from Cleansing– When you begin to open up your body and feel good again, you will remember that the body is literally the most important thing in your life. As the toxins disappear, your respect for your body and other people's body's increases. You will automatically treat others with more respect, love and appreciation boosting every relationship you have. Eliminating toxins automatically increases energy, health and gives a youthful appearance and is a powerful anti-aging tool. Your body is your temple and cleaning the toxins out of it is the first step. Ensure you charge everything you put in, on and around your body with Sacred G to generate the most amount of energy and to assist you in some of these life changing positive patterns.

Clearing the massive amount of emotion stored in past memories is an extremely powerful method in freeing up energy for your body to heal naturally. You will notice a major increase in energy as well as an overall boost in peace, joy, happiness and excitement as old feelings like resentment, anger and sadness are no longer there to weigh you down. As you clear the major emotional blockages, you will find that you will be able to pick up more subtle sensations in your body. This means you will be able to read and communicate with people more effectively as you will be able to sense and feel what is going on with them more clearly. Making love intensifies as your physical senses become more alive. Even being able to smell the fresh morning air after a rain becomes more exhilarating as your senses magnify. Clearing the emotions that have become congested in your brain and body not only boost your energy but enhance your entire experience of life by heightening your senses. This is your body, not just your body, but your very vessel that you experience life with, Unlock your body's full potential with the Sacred G Fusion Bed Set and discover what life can truly be like.

3 Stage Development Process

Sacred G technology has three major stages of development that it will move you through. Each of the stages has their own unique attributes. These development stages are all required to go through before you will truly stabilize from the increase of energy within your body. Once you stabilize, your growth and development will feel like it has slowed as you integrate your life into that new level of energy.

The first stage of development is a complete body cleansing and rejuvenation. This initial part entails that you clear personal memories and issues in your life that you are experiencing right now. These are some of the typical experiences that you will endure.

- Increase of energy – This will take place if your system is slowed down.

- Decrease of energy – This will occur if your system is too accelerated.

- Non-stop dreaming all night – This is the body's way of cleansing and adding programming through experiences.
  - You can feel tired after these nights or be bursting full of energy.
  - You can experience nightmares if you are spacey or lack focus.
  - You can experience powerful goals and realizations to get in touch with what you really want.

- Deep sleeps - You will have incredibly deep and long sleeps. This is the body working through some very deep issues and has decided that it is better for you to not get back into old memories.
  - You may feel really tired all the time and want to sleep, sleep, sleep.
  - Listen to your body and sleep as much as possible on Sacred G technology. The body needs its rest. The more you do so, the faster you will move past this initial stage.

- You can feel very tired or emotional as the body is trying to clear and reprogram new emotions to stabilize your internal system.
  - Lay on your bed when this occurs and you will notice that Sacred G technology will accelerate this process and rejuvenate you.
  - Make sure you are drinking lots of water that has been programmed.

- You can experience major bursts of energy that you will have no idea what to do with.
  - When you feel this much energy, use it how you would like, most people realize that they still cannot do anything with this energy.
  - Lay on your bed and let Sacred G technology stabilize this energy so that you can speed up the process of this stage of development.

- Old physical injuries or traumas can resurface as the body clears out the cellular memory.
  - Bruising, pain from scars, bone breaks, injured joints, etc… can resurface as the body clears.
  - Lay on the bed and let Sacred G technology accelerate you through this process.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

- Physical cleansing sensations may occur such as excessive need of the bathroom.
    - This is part of the physical cleansing process. As the energy of the body increases, pollutants and toxins need to be removed from your body to fulfill the vibrational instructions.
    - Drink lots of water and lay on your bed to speed up this process.

All of these effects may or may not take place depending on what your body needs. You just have to play it through and realize that most effects will only last 1 to 3 days. This first initial body cleansing period is the hardest part about using this technology. The more Sacred G technology you use, the longer it will take for this first stage to complete itself.

You have to think that you have a whole lifetime of memories and physical abuse that you have put your body through. This accelerated cleansing is set to clear as smooth as possible. Some major changes do have to be initiated in this stage though that is necessary to get you where you want to go. Sacred G is the ideal technology to use for this type of cleansing because they give the instructions to your body and let the body use its ability of quantum computing to know what needs to be cleared and when. It is the most efficient system of cleansing that I know of and far surpasses the standard body cleanses and psychological healing.

Once you finish this first initial stage of cleansing, you will notice that your life will dramatically calm down. You will feel powerful, strong and centered. Your body will feel stable and strong.

The second stage of development is vital to setting up new goals and getting in touch with where you want to go in your life. Your desires will be brought to the surface so you can set out a plan of action for yourself. This is the major rewiring and reprogramming part of Sacred G technology.

- Excessive vivid dreaming – Dreams are a way to help bring awareness of beliefs and ideals that you have inside of your head. Dreams are used to train your brain and awaken new ideas and concepts for what you want in your life.

- You will have motivation to get certain things done, yet you will have no energy for it. This is the second stage of getting in touch with what you want. Make notes and create a plan for your life.

- Your information, beliefs, likes and dislikes, attitude towards certain information, activities and people will start to be questioned. Those aspects not in alignment will feel like a waste of time.

- You will go through a level where you will feel like everything is pointless and not worth the effort. This is initially cleansing out everything that once had value and will eventually replace it with strong passions and desires about what you want. This eliminates the clutter of information that is not relevant to your true goals and aspirations.

- The void is introduced as the brain clears out all objectivity and rationality as you move through one reality into the next. Subtle depression and feeling lost can result in this stage. When in your blank stage, keep notes on what still makes you smile and you can have foresight into where you are going next. Lay on the bed with Sacred G technology so that you can accelerate yourself through this process.

- Connections will then be made once all information has been deemed irrelevant. This will construct a new plan and new ambitions for your self. This will clear your mind of all irrational thought and you will feel the precision in your choices. Construct a plan for what you really want to do in your life and prepare for it. Remember that you are alive and that you can do anything that you want.

The second stage of development can be difficult for some people and completely rejuvenating for others. This is essential for you to realize that everything in your life is irrelevant. This cleansing is what allows you to start functioning on the variable vibration program. Afterwards, you will be able to adjust your information system within so that you become more flexible and increase your adaptation skills. This is part of the training to initiate your ability to flow into the level of pure performance.

The third stage of development is where you will begin to implement the new changes in programming into your life. This can and will result in you completely restructuring your life. This can be a fun and exciting adventure, as well as a difficult one as major life changes are introduced. This level is where you will start to see the power of Sacred G technology as it shifts your external world to get you on track with where you want to go.

- Initial cleansing of relationships can begin.
    - This is to cleanse your external environment for what is working and what isn't working. This can be very difficult depending on the type of relationship changing. The easiest and fastest way to overcome this level is to meditate by laying down on your bed with Sacred G technology.
    - Old relationships that serve no real purpose block you from creating new ones. They take up time and energy.

  - Some old relationships can be strengthened and renewed with your new sense of purpose and direction. The body has major key changes that need to occur in your life to get you to where you are going. What needs to be there will be there stronger than ever.

- Business and Career Restructuring – These changes are a major part of your life. In order to reach the point where you want to be. Certain changes need to be made. When you feel like something is not right about a situation, take note and start preparing for a change to happen.
  - Everyone in the world wants to feel worthy and support the whole. 1/3 of our life is devoted to serving others. You need to make sure that you are serving in the ways that you want for optimum happiness and self satisfaction.
  - Remember to think ahead and do not make any major changes by impulse alone. Plan, prepare and then act at the right time to initiate change the smoothest. We will all learn this lesson the hard way at first. Sacred G technology is designed to train you to do this properly. Remember not to be hard on yourself; we learn by mistakes. Sacred G technology is very resourceful at making whatever connections are necessary to help you along the way.

- Physical Health – The body wants to increase your physical level of performance so that you can feel strong and confident with your actions. This may not take place until the end of this stage, as the body wants to complete some of the major life changes first.

- New directions and contacts will need to be made in order to accomplish your new objectives and goals.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Research

Infrared Testing with Cell Phones



Infrared Test with No Sacred G Micros
White = Highest Heat



Infrared Test with 4 Sacred G Micros
Red = Normal Tissue Temperature

After being exposed to cell phone radiation for fifteen minutes, the head on the left shows significant levels of heat radiation. Notice the areas of white, which represent the hottest temperature readings.

After fifteen minutes on the same cell phone with 4 Sacred G Micros installed, the head on the right shows far less heat. The red areas show cool, normal tissue temperatures.

After collecting data from numerous infrared thermography trials, there is now scientific proof that the Sacred G Micro Reduces Thermal Heat Radiation by up to 87%!

Now There's Scientific Proof That...
a) Cell phones "cook" your head.
b) Sacred G reduces this effect by up to 87%!

“Without the Sacred G Micro, my cell phone would always get hot, plus I could feel the heat in my head. Now that I put the Micro on my phone, I not longer feel the heat…”

~ Rochelle Coatney, California

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Gas Discharge Visualization Camera



Tap Water



Tap Water Charged with Sacred G

Many people are interested in structured water, which refers to the way in which water molecules align themselves, bond to each other, and interact with each other. Generally, it consists of small clusters of water as opposed to normal, larger clusters of the water molecule. These smaller clusters are thought to improve hydration. Because there are not many effective ways to measure structured water other than secondary effects, the Gas Discharge Visualization Camera (GDV), provides an important way to assess directly the effects of various treatments of water. The GDV Camera, Russian technology that measures photon emission of materials in response to a micro current.

Looking at the above images helps understand what placing a container of tap water on the Sacred G Technology does to the water. A GDV assessment of tap water (left photo) shows that the water has essentially no energy. However, the photo on the right shows that after the same water sat on the Sacred G for 9 hours there was a dramatic increase in the energetic responsiveness of the water. This image has a significantly increased bright corona discharge, a measure of energy. Also, the Charged water has pronounced flares, originating from a few action sites, indicating more highly structured water.

Independent Research Performed by,
Lisa Tulley
Phd. Pharmacology & Toxicology

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Life Span of Flowers



Flowers



Flowers Charged with Sacred G

This is a Fantastic display for the powerful influence Sacred G Technology can have on Flowers and the massive potential Sacred G can have for Anti-Aging.

The above flowers were purchased at the same time and were part of the same bouquet. Three of the flowers were taken out and put into 2 different vases. While the rest were placed in another vase with a Sacred G TranceNdance sticker under it.

These flowers are 12 days old and you can see the huge difference Sacred G can have on flowers. Just think what thousands of the Sacred G Posters could do for your body and mind!

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Food Preservation – Celery

Celery (4 Days Old)

Celery Charged with Sacred G (24 Days Old)

Notice how the celery that is only 4 days old is already starting to wilt and bend over. The celery that was Energized by the Sacred G is still bright, firm and crunchy.

We used to buy fruits and vegetables every week so they wouldn't go bad. Slowly after using the Sacred G our habit shifted and we started buying more Vegetables at one time. Now, we buy all of our groceries for the month, at the beginning of the month, including our fruits and vegetables.

I had bought celery at the beginning of the month; the date was March 4, 2005. It was the Easter weekend and we were having company so I had to pick up some extra food for the dinners we had planned. I picked up an extra stalk of celery from the store. This was on March 24, 2005. The first celery had charged up for 2 weeks. On March 18, 2005 I took the L.O.V.E. Chargers out of the fridge, I was cleaning out the fridge preparing for our move at the end of the month.

On March 28, 2005 we looked at the two celery stalks that we had bought. The one that was charged up for two weeks was in better condition than the one we bought 5 days ago. The one we bought at the beginning of the month still looked fresh and crisp; the leaves were still bright green. The ones we had bought 5 days before had already started to wilt; the leaves had turned a much darker brown and looked terrible compared to the other one.

Here are the pictures - the celery with more gone is the one that I bought at the beginning of the month. The full stalk of celery is the new one.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

FAQ's Regarding Sacred G

Q. How do I enhance the durability of my Sacred G?

A. Many people have found that laminating the Sacred G is the best way to increase its durability. This is a great solution, especially for using the Sacred G in your refrigerator, with your water, in or under your bed, and any other places where the Sacred G could be exposed to moisture or the possibility of rips and tears.

Q. Can I cut the Sacred G Fusion Posters?

A. No, it is not recommended that you cut the Fusion posters, but you can fold them up to custom fit places like the fridge, freezer, pantry, or any other areas.

Q. I just downloaded and printed out the digital version of the Sacred G, what do I do with it?

A. The best way to use the print out version of the Sacred G is beneath your pillow and/or beneath your water & food. Simply place the Sacred G, design side up, directly inside your pillowcase on the underside of your pillow. This will prevent the Sacred G from moving around too much at night. For a heightened experience with the printable Sacred G, print out as many as you can and layer them between your box spring & mattress beneath the entire length of your body. For your water and food, place the Sacred G design side up beneath your water bottle or glass, beneath your plate of food, in your refrigerator or under your fruit bowl.

Q. I just received a Sacred G Sticker Pack, how do I use them?

A. The Sacred G stickers, which are double sided for extra energy, are great to use to charge up anything you put in, on or around your body. You can either stack them ALL under your pillow for a big boost of energy or you can place just one design for the specific area of your life you want to enhance. You can also use the stickers to charge up your water, food, jewelry and more, click on the Sacred G link on the top bar of the website to learn a more detailed description of each design and over 35 Uses. If you purchased the Variety Pack, you are in for some fun. You can utilize all of the applications above, or use them like a mini tarot deck. Either read the descriptions of what each sticker is for and choose the one the most resonates with what you are going through and place it beneath your pillow, or, wave your hand slowly over each design with your eyes closed and choose the one that draws your attention most strongly. Then place it beneath your pillow, and enjoy!

Q. I just received a Sacred G Capsule containing the full sized 18" x 24" double-sided Sacred G Fusion plus a sticker pack, what do I do with them?

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

A. This package contains either 10 or 20 of the full-sized doubles-sided Sacred G Posters. Depending on what type of bed you have, the rule of thumb with this product is to place as many as you can beneath the full length of your body either under your bed or between your box spring and mattress. If you know that you do not move around a lot at night, the you can place them in three piles directly beneath where you sleep, vertically, so that the points of the stars are North/South. If you do move around a lot, then spread them out evenly throughout the entire length of the bed. TIP: Many people have noticed stronger effects when they physically sleep with their head to the North and feet to the South. For Variety Pack instructions, see above.

Q. What is the best way to charge my food and water?

A. Ideally, you want to be drinking water and eating food that has been charged on the same amount of Sacred G that you are sleeping on. When possible, only eat, drink or use products that carry the same level of charge as your body does. The easiest way to do this is to place your groceries and/or bottles of water directly on the bed for at least 30 minutes before putting them away. Then, make sure you have Sacred G in the fridge, freezer and pantry to help hold the charge. Always carry a few pocket chargers with you for when you eat or drink out. Place the Sacred G Technology under the shelves to protect them.

Q. What is the best way to charge my supplements, herbs, and medications?

A. Same as above; be sure to charge anything you put in, on or around your body with as much Sacred G as you are sleeping on. With herbs, supplements & medications, it is VERY IMPORTANT to remember that the Sacred G will amplify which can increase the effects of anything it charges. Listen to your body and decrease your dosages as your body tells you it is time to do so. Always consult a doctor first before altering any suggested dosages or instructions given by them.

Q. What is the best way to use the Sacred G on the body for aches and pains?

A. Whenever possible, place the Sacred G directly on the body. For example, for back pain, grab a stack of Mini Activators and hold directly against your back, or place between your back and your chair, or lay directly on them. For an even more powerful results, charge up the Fusion 137 Essential Oil Blend we offer and rub it on the agitated area. You can also mix the Fusion 137 Essential Oil in your other products to give it extra healing properties. And last, charge up a glass of water, and when you are drinking it, put all of your focus on the area of your body that requires relief directing the energy quickly to the source of the pain or discomfort.

Q. How do I combine my Sacred G with my vision board or goals list?

A. If you have a vision board, simply put the Sacred G beneath your pictures, inspirational quotes and personal goal list. Sacred G makes a GREAT background for any vision board. In addition, write out, in as much detail as possible, what you desire to manifest in your life, and place the list on top of the Sacred G beneath your body. The Sacred G will blast energy through your list and into your body feeding your body instructions for exactly what action steps to take to turn your desires into reality.

Q. How do I use Sacred G with my cell phone and other EMF emitting Devices?

A. Simply stick the Sacred G directly on the device. We have many different size stickers available for this purpose. The L.O.V.E. Micro is made specifically for cellular phones, but can be used on anything. Some examples include computers, microwaves, even the human body. Did you know that by sleeping on the Sacred G you are surrounding yourself in a shield that protects you from EMF's while you sleep?

Q. What is the best way to use my Sacred G for meditation?

A. Our favorite way to use the Sacred G for meditation is to light some candles on top of some Sacred G stickers, place some Sacred G charged crystals along the charkas, lay on the Sacred G bed and begin by following the G Breath on the Meditation Station at http://coryherter.com/Flash/Gspot/index.html

Q. When I travel, how much of my Sacred G should I take with me?

A. Of course, as much as possible, but due to the weight of the boxes, 25 of the regular sized double-sided "posters" should do the trick. The plastic capsule that the Sacred G comes in is perfect for traveling and fits into most suitcases. Frequently Asked Questions regarding the transformational process that Sacred G Technology initiates. IMPORTANT: Sacred G is an extremely powerful technology that can put your body through major processing to get you cleaned up from the toxins you have been putting in, on & around it over the years. Past events that are left open and have never dealt with will come to the surface to be cleared. Belief systems can be addressed and recognition will have to be made about the choices you are making in your life. In order to achieve higher states of consciousness, you will need to embrace the natural systems of the body and release the emotional baggage and physical toxins that are being stored.

Q. I tried sleeping on the Sacred G and I couldn't sleep. I was restless and tossed and turned all night long. I had to take them out to get some sleep. What should I do?

A. Sleeping on Sacred G will immediately begin processing the stress of your day to day life. If you toss and turn, this is the energy beginning to clear the anxiety and stress that has been suppressed. When you spend your time doing something that isn't taking you where you want to go, anxiety, resentment and frustration start to build up within the body. If you continue this pattern, you will begin suppressing all

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

of this emotion. Sacred G is built to get you back on track with your purpose so you are living your passion. Continue going through this process until it stops. Within days of overcoming this first phase, you are most likely going to make a big shift in your life. This stage usually only lasts a few days, but can last up to 6 weeks depending on the amount of time you have been playing this pattern out.

Q. As soon as I started using Sacred G, my energy skyrocketed. When I added more posters my energy plummeted, what is happening?

A. When you first started, your energy levels increased. After applying more posters, your energy state increased beyond your current state. Once this takes place you have opened up a new stage of growth and requires the body to purify itself. The drop in energy happened because your body went into the internalized cleansing and development stages, which is associated with your core. Study the Tree of L.O.V.E. to identify which Chakra you are blocked on and take the steps to move forward. In time, days or weeks, this phase will pass and your energy will shoot up again, and next time way beyond what you experienced at first.

Q. I have been feeling groggy and spacey the last few days, should I stop using my Sacred G?

A. The body will initiate the physical cleansing of cells in your body. As the toxins are released into the blood stream to be eliminated from the body, you may feel groggy or spacey. These toxins have been in your body for a long time and influence your choices daily. You are simply becoming aware of the chemicals that have been influencing your choices every day. To speed up this process, drink plenty of charged water to cut down on cleansing effects and be sure to keep charging your food. You can also try doing one of the cleanses mentioned on the Tree of L.O.V.E.

Q. My dog is acting like a puppy again and has started sleeping on my bed all the time. Can he feel this energy too?

A. Pets LOVE Sacred G and the results are instantaneous. Youthful playfulness and a calmer attitude towards people are the most common results.

Q. I am dreaming continuously every night, its like watching movies. Does it ever stop?

A. Dreams are the method the body uses to process and clear your internal information and emotions. Advanced levels of dreaming include being taught new information, running simulations for choices that you want to make and opening up some extremely powerful spiritual states. Be sure to have a pen and paper handy when you wake up with downloads for exactly what to do for the day and answers to questions you have been asking.

Q. Why do I need to use more than one Sacred G Poster?

A. Every Sacred G Poster will generate a certain amount of energy. To boost your energy levels higher, simply add more Sacred G. Wait until you see the states of experience you can access at higher quantities.

Q. Can I put the Sacred G directly on my body?

A. Yes. Placing the Sacred G directly on the body can help to eliminate pains, aches, headaches, cramps etc. Try charging up the Fusion 137 essential oil or massage oil with Sacred G and apply it to your body for Pain Relief.

Q. How long do I leave my water, food and supplements on top of the Sacred G?

A. The best way to use this technology is to put the Posters in the fridge, freezer, pantry, medicine cabinet, etc… and leave them there permanently. This ensures the most powerful charge; increase the number of posters to infuse everything you charge with even more Energy and leads to greater results.

Q. What exactly happens to my water and food when it is charged with the Sacred G?

A. There is a mathematical program embedded within Sacred G technology to enhance the cellular absorption strengthening the effects of the energy. When charging your food and water, this programming increases absorption into the cells filling you up faster and enabling you to eat less. This can be a very powerful tool for weight loss. Charging up your food also lengthens the shelf life from the full spectrum vibration that doubles as a stabilizing agent and a natural preservative.

Q. Can I use too Much Sacred G?

A. Sacred G uses a perfectly balanced full spectrum vibration that enables you to continue to increase the quantity as high as you desire. Four people have tested Sacred G at extreme quantities of up to 43,200 Posters for over a six month period. The results are neither incomprehensible nor explainable to someone that has not accessed extremely high states of consciousness, yet I would instantly recommend it to anyone that yearns to explore the consciousness of the universe. There is a safe guard in the mathematics that prevents anyone from opening higher states of energy before they are ready through a precise development system. This safe guard program also incorporates a coaching program to help you develop through this growth cycle when using enough Sacred G.

Q. I am starting to download information that I have never acquired before, where does this come from?

A. Welcome to the new way of learning…I call it the L.O.V.E. Innerversity. This new education system is a powerful Intelligence System built directly into the technology to help you achieve your goals and unlock the potential of the human body. Wait until you start downloading new forms of motion into your body and you watch yourself move. Another fun effect is the ability to speak without knowing what you are going to say and learning from yourself as you say it. This is really fun with jokes because you hear them the first time as you say them. Your body becomes an intelligent being that teaches and interacts with you. This is an Absolutely Phenomenal state of mind.

Q. My sensations are incredible; my love life is amazing…what is happening so I know how to do more of it?

A. Enhancing the senses literally means enhancing your sensations, as the Sacred G continues to boost you to new heights of self acceptance and enable you to open your heart; your senses will become much more intense. Wait until the Tantric energy starts to fill your being and you can feel your spirits merge… oh so many things to experience, I LOVE IT!!

Q. I have spent the last 15 years doing self-development and this technology seems to automate everything, do you think this takes away from people's individual accountability for the laws of cause and effect if they can have their body and mind cleared automatically?

A. The great thing about the technology is that it is not a free ride, you have to train with it and it teaches you to process memories faster, which includes clearing out the emotion, eliminating judgments and opening up to new perceptions. Although the process is automated, this does not mean that the clearing is instantaneous or that each person does not have to be accountable for their actions. In order to learn and develop, conscious recognition will be given to ensure the new programming is locked in which fulfills the laws of cause and effect. What you put into the body, you are also responsible for clearing out, even though it may be uncomfortable at times.

Q. Does the technology have the same effect from looking at it? Should I put it on my walls or on my ceiling above my bed?

A. You can put it anywhere you like… Yes Sacred G does have a powerful effect from staring at it. TIP: Placing Sacred G posters under your bed and on the ceiling above your bed will create a pressurized effect enhancing your results. Place the Posters on your headboard and footboard as well to create an even more powerful effect! I know this might sound strange, but, does the Sacred G answer prayers? I mean, at night I usually go over my affirmations in my head while I meditate, and it just seems like since I have been using the technology, that manifestation, or as I like to call it, my prayers being answered is, well, happening faster. When you override the massive amounts of vibrational influences contained within our environment, the body is able to create your goals more efficiently. Increasing the number of Posters essentially will increase the speed that your intentions or prayers are manifested.

Q. Does the effects and transformation induced by this technology stop or old patterns come back if I stop using the technology?

A. When you stop using the technology, your body will re-harmonize with your environment. This is the drop in energy that is experienced. In this way the technology is used to overcome the negative vibrations created from electricity With the additional mathematics in the technology, this energy has the ability to help you process the emotions from past memories and help solve conflicts in your information unlocking new information. All of these benefits stay with you, it is impossible to unlearn them.

The process that the technology uses is a natural occurring cycle in the body. The technology is only accelerating this growth cycle and helping to prevent you from becoming stuck. As you clear more of the blocks from the past, your spirit can shine through brighter than ever before. The technology gives the body an artificial boost of energy to take you to a higher state that you are not currently at.

The physical body is required to create this temporary energetic state into a solid reality, which initiates the development procedures that Sacred G will take you through. Over time, the level the technology boosts you up to become an integrated system, and you will never drop down in energy even if you stop using the technology. Increasing the amount of Sacred G takes you to a higher level and will speed up the development and integration process. Even though the technology is a shortcut, you are still required to go through the process of integration so you can become this higher state of consciousness. The beauty of the technology is that instead of struggling to grow, the extra energy initiates the growth making this transformational process easier which enables more people to step into their potential.

If you have a question that is not answered above, simply email us and we will answer it and then add it to our list of FAQ's. Please send your question(s) to info@coryherter.com.

Video Library

The Video Library is actually categorized in the www.CoryHerter.com website. Below is an outline of all the videos that are included and a brief synopsis for each video. There is a category link included at the beginning of each section as well as individual links to each video.

2006 Video Series – 19 Hours

http://coryherter.com/?cat=73

The 2006 Series are a live seminar series that I offered in Santa Monica, CA. These seminars were one of my tests that I needed to complete to pass the TranceNdance design and get the upgrade to the Sacred G Simulator (also known as the Love Charger). The Sacred G Simulator includes the mathematics for expression, you can see the before and after results in me from using the Sacred Simulator. The Perfect Wave Programmer talked about in this series of Videos is now called Sacred G TranceNdance. I hope you enjoy these videos, please leave a comment on the bottom of the videos to share with other people your experience.

2006 - Introduction to Sacred G Technology – 2 Hours

Cory explains Sacred G Technology back in 1996 when the technology was called Perfect Wave Programmers. This was before the simulators, activators and fusion designs were developed. The Perfect Wave Programmers were an early version of the Sacred G Trancendance design.

http://coryherter.com/?p=771

2006 – Creating the Council – 2 Hours

Cory explains the process for splitting apart your identity and growing up the fragments into your own internal council. This is a powerful tool for understanding how to unlock massive amounts of information in your brain. Sacred G Fusion has this system built into it and is a piece of what Cory refers to as the advanced memory systems, such as complex pattern recognition.

http://coryherter.com/?p=769

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

2006 - Creating the Collective – 1 Hour

The Collective is something that we must create within our own energy systems in order to gain access to the collective that exists in deeper layers of the human body. Cory takes creating the council to the next level in this incredible video. The collective is now a system completely integrated into Sacred G Fusion and activated by the Pineal Gland.

http://coryherter.com/?p=767

2006 - Advanced Sacred Geometry - Part 1 – 2 Hours

Cory shares some of the advanced Sacred Geometry science behind Sacred G Technology.

http://coryherter.com/?p=761

2006 - Advanced Sacred Geometry - Part 2 - Time & Space – 2 Hours

Cory shares some of the advanced Sacred Geometry science behind Sacred G Technology.

http://coryherter.com/?p=759

2006 - Life After Death - Part 1 – 2 Hours

Cory shares the Science behind Life After Death using Sacred Geometry. Watch the Science of LOVE Video Series first to gain a deeper understanding of the information given in these videos.

http://coryherter.com/?p=746

2006 - Life After Death - Part 2 – 2 Hours

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Cory shares the Science behind Life After Death using Sacred Geometry. Watch the Science of LOVE Video Series first to gain a deeper understanding of the information given in these videos.

http://coryherter.com/?p=744

2006 - Life After Death - Part 3 – 2 Hours

Cory shares the Science behind Life After Death using Sacred Geometry. Watch the Science of LOVE Video Series first to gain a deeper understanding of the information given in these videos.

http://coryherter.com/?p=742

2006 - Chironium Healing - Part 1 – 2 Hours

Chironium Healing is an energy healing technique developed by Cory Herter which utilizes breath and sacred geometry for healing physical injuries and psychological trauma. Chironium Healing is a pre-cursor to the Breath of LOVE Workshops that Cory now offers Live in Person. Check the events page to learn more.

http://coryherter.com/?p=740

2006 - Chironium Healing - Part 2 – 2 Hours

Chironium Healing is an energy healing technique developed by Cory Herter which utilizes breath and sacred geometry for healing physical injuries and psychological trauma. Chironium Healing is a pre-cursor to the Breath of LOVE Workshops that Cory now offers Live in Person. Check the events page to learn more.

http://coryherter.com/?p=738

I hope you enjoyed the 2006 Video Series. This 19 hour introduction into my work is a powerful way to open your mind to some of the more advanced concepts I will continue to teach.

2012

http://coryherter.com/?cat=95

Oct 20, 09 Live Webinar – The Truth about 2012

The Truth about 2012 – Evolution, Conspiracy, 9-11, Privacy Act, Natural Selection, Light Workers and more!
http://coryherter.com/?p=951

The 2012 Enigma by David Wilcock

2012: Tragedy, transcension or just another year? David Wilcock exposes many great secrets: DNA, consciousness science, wormholes, stargate travel, sacred geometry, three-dimensional time, the Mayan Calendar and much, much more!

http://coryherter.com/?p=637

Ascension

http://coryherter.com/?cat=99

Merkabah – The Chariot of Ascension

The Merkaba Field is a permanent and highly ordered Merkabic structure of inter-connected electro-magnetic counter-rotating energy spirals that exist as an integral part of ALL CREATION. The mathematics of the Merkabah are built into the New Sacred G Fusion Design to activate the Pineal Gland to Access Higher Consciousness Communication and Inter-Dimensional Travel.

http://coryherter.com/?p=817

Breath of LOVE

http://coryherter.com/?cat=105

LOVE Innerversity – Module 1 – The Breath of LOVE

Cory Shares about the Module 1 - Breath of LOVE course taught at his Live Workshops. Click the Events page to learn about upcoming events near you.

http://coryherter.com/?p=977

#1 Reason For Every Health Problem

Find out what this incredible breakthrough is and how knowing this 1 thing can change your life forever. Cory breaks down every single illness into a completely customized disease that every single one of us creates for ourselves as the result of 1 single problem.

http://coryherter.com/?p=672

Cory Herter

http://coryherter.com/?cat=10

Cory Explains his 300 Near Death Experiences

Introduction to Cory's Story and how he was triggered into over 300 near death experiences.

http://coryherter.com/?p=495

Evolution Into Sacred G Technology

Discover the evolutionary process through vibrational healing technologies Cory went through in order to create Sacred G.

http://coryherter.com/?p=668

Cory Herter on Sacred G Fusion

Cory Herter shares his initial experience with Sacred G Fusion. Video includes a quick overview of the New Sacred G Fusion.

http://coryherter.com/?p=422

Cory Herter's Experience on Sacred G Fusion #2

Cory Herter's experience using Sacred G Fusion Technology. Another addition to my video blog with what I am learning about Sacred G Fusion as I go through this incredible process of transformation.

http://coryherter.com/?p=498

Cory's Sacred G Fusion Bed Set and Massive Sacred G Designs

I am definitely the biggest fan of Sacred G Technology. As you can see, I have my pad here in Las Vegas loaded up with Sacred G everywhere. With this many cases under my bed, my 5 meal a day diet loaded with steak, chicken and fish to add weight for working out has now been reduced to 4 raw seaweed veggie wraps a day along with a glass or two of fresh juice!! I am still keeping my same weight, losing the outer layer of fat and getting totally cut up!! My dream is to have a massive warehouse with the floor and walls covered in Sacred G Fusion Cases, with my bed resting on top of a pyramid of Sacred G Fusion cases like the mayan temples!! I am curious how many cases it will take to reduce the food down to nothing but air... or if that is even possible.

http://coryherter.com/?p=736

Cory's Video Series

http://coryherter.com/?cat=103

Sacred G Sleep Test – 5 Video Series

Learn the different types of Sleep Effects that Sacred G will use to Increase Your ENERGY!!

http://coryherter.com/?p=975

Pineal Gland Activation – Entire Series – 6 Parts

Cory's Sacred G Pineal Gland Activation Video Series.

http://coryherter.com/?p=969

Benefits of each Sacred G Design – Entire Series + Bonus Video

Discover the Benefits and Science behind each Sacred G Design. This is a 7 Part Series with an extra bonus video at the end explaining the Tree of LOVE Case!!

http://coryherter.com/?p=559

Science of LOVE DVD – A 3 Hour Video Series on the Science behind Sacred G

Cory Herter gives an amazing presentation into the math and physics behind Sacred G Technology. L.O.V.E., which stands for the Laws Of Vibrational Energy is the engine that drives Sacred G Technology and is a natural law of the universe contained within Sacred Geometry. Discover the deeper meaning of the Flower of Life, The All Seeing Eye, DNA Activation and more...

http://coryherter.com/?p=399

Crazy Sacred G Fun

http://coryherter.com/?cat=17

Cool Sacred G Video

Cool Video Highlighting Sacred G Technology. Sacred G is a revolutionary new technology that increases DMT production in the Pineal Gland. Try this technology out for Free today!

http://coryherter.com/?p=264

Underground Sacred G Party

Check out the Highlights from a Massive Sacred G Underground Party with Fire Dancing, Break Dancers, Sacred Geometry Art Displays and More... The Peeps are Loving the Fusion 137 Essential Oil and are calling it the New *Vicks*.

http://coryherter.com/?p=268

DMT

http://coryherter.com/?cat=46

Pineal Gland & DMT by Cory Herter – Part 1 of 6

Discover the Power of the Pineal Gland and its relation to DMT. Unlock your Potential with Sacred G Fusion's Pineal Gland Activation!

http://coryherter.com/?p=420

DMT: The Spirit Molecule, the Movie

A series of interview clips from DMT: THE SPIRIT MOLECULE, the movie. http://www.thespiritmolecule.com/

http://coryherter.com/?p=617

DMT – The Spirit Molecule – Audio Interview with Film Maker Mitch Schultz

An audio interview with Mitch Schultz, maker of the film DMT, The Spirit Molecule. We'll be talking to Mitch about the film: who's in it, what he's learned along the way, and when you can expect it's release.

http://coryherter.com/?p=613

DMT, Dreams and Near Death Experiences

Does DMT play a role in near death experiences? Clip from an episode of the magical egypt series featuring Rick Strassman.

Endogenous DMT, produced in the human brain, is involved in certain psychological and neurological states. As DMT is naturally produced in small amounts in the brains and other tissues of humans, and other mammals, some believe it plays a role in promoting the visual effects of natural dreaming, and also near-death experiences and other mystical states.

http://coryherter.com/?p=389

Joe Rogan Talks DMT on the Alex Jones Show

Alex Jones welcomes to the show Joe Rogan to discuss the importance of Dimethyltryptamine or more commonly known as DMT. Anyone that has experianced a lucid dream or have done an extracted form of DMT knows just how important this subject is.

http://coryherter.com/?p=384

Joe Rogan Goes off about DMT

Joe Rogan Goes off about DMT - Joe Rogan recounting his experience with DMT and his ideas on humanity.

http://coryherter.com/?p=393

Fusion

http://coryherter.com/?cat=79

New Sacred G Fusion Bed Set Video

Cory Herter's Journey Through The After Life Sacred G Fusion Bed Set Video.

http://coryherter.com/?p=258

Sacred G Fusion – ONLY $1.00 / Sheet

Sacred G Fusion is now only $1.00 / sheet. Packs of 100 Available Now!! Boost your Energy and Experience the New Sacred G Fusion!

http://coryherter.com/?p=973

Sacred G Fusion Design – 7 of 7

Discover what each Sacred G Design can do for you!! Learn the process that Sacred G uses to unlock your true potential. Finally learn how Sacred G can boost your energy so much! Be sure to download your Free Sacred G Designs at www.CoryHerter.com!

http://coryherter.com/?p=545

Bonus: Secret of the Sacred G Fusion Case

Discover the secret behind the New Sacred G Fusion Case!!!

http://coryherter.com/?p=543

Cory Herter on Sacred G Fusion

Cory Herter's experience with using Sacred G Fusion Technology. A Quick Overview of the New Sacred G Fusion.

http://coryherter.com/?p=422

Cory Herter's Experience on Sacred G Fusion #2

Cory Herter's experience with using Sacred G Fusion Technology. Another addition to my video blog with what I am learning about Sacred G Fusion as I go through this incredible process of transformation.

http://coryherter.com/?p=498

The Collective & Sacred G Fusion

Access the Collective through your 3rd eye. Activate your Pineal Gland and Release DMT Now!!!

http://coryherter.com/?p=629

Cory's Sacred G Fusion Bed Set and Massive Sacred G Designs

I am definitely the biggest fan of Sacred G Technology. As you can see, I have my pad here in Las Vegas loaded up with Sacred G everywhere. With this many cases under my bed, my 5 meal a day diet loaded with steak, chicken and fish to add weight for working out has now been reduced to 4 raw seaweed veggie wraps a day along with a glass or two of fresh juice!! I am still keeping my same weight, losing the outer layer of fat and getting totally cut up!! My dream is to have a massive warehouse with the floor and walls covered in Sacred G Fusion Cases, with my bed resting on top of a pyramid of Sacred G Fusion cases like the mayan temples!! I am curious how many cases it will take to reduce the food down to nothing but air... or if that is even possible.

http://coryherter.com/?p=736

Indigo Children

http://coryherter.com/?cat=89

Indigo, Rainbow & Crystal Children and Sacred G Fusion

You have to watch this!! The Spiritual Revolution is here!! It is time to Awaken!!

http://coryherter.com/?p=625

Akiane: child prodigy, artist, poet, “Indigo child”

An internationally recognized 13-year-old prodigy, considered the only known child binary genius, in both realist painting and poetry. Selected as 1 of 20 most accomplished visual artists in the world by Tribute Entertainment (London) and ABI (United States). Kids Hall of Fame inductee. World Council for Gifted and Talented Children inductee. A best selling author of two books "Akiane: Her Life, Her Art, Her Poetry" and "My Dream is Bigger than I - Memories of Tomorrow"

http://coryherter.com/?p=634

Meditation

http://coryherter.com/?cat=36

Sacred G Meditation Station

Learn the mechanics behind the Famous Meditation Station. Cory explains each component and why the Meditation is so Powerful. Use this process daily to advance through the levels of this meditation and unlock deeper aspect of the self.

http://coryherter.com/?p=674

Go to the Meditation Station Now… http://coryherter.com/Flash/Gspot/index.html

Sacred G Inspirational Video by Quantum Power

Enjoy this amazing inspirational video created by Quatum Power using Sacred G and iTom Lab's Galactic Mantra.

http://coryherter.com/?p=903

Sacred G Power Meditation by Quantum Power

Enjoy the Sacred G Power Meditation created by Quantum Power using iTom Lab's Galactic Mantra!

http://coryherter.com/?p=906

Pineal Gland

http://coryherter.com/?cat=42

Pineal Gland & DMT by Cory Herter – Part 1 of 6

Discover the Power of the Pineal Gland and its relation to DMT. Unlock your Potential with Sacred G Fusion's Pineal Gland Activation!

http://coryherter.com/?p=420

Pineal Gland & Hormones by Cory Herter – Part 2 of 6

Pineal Gland & Hormones by Cory Herter - Part 2 of 6. Discover the Power of the Pineal Gland and its relation to Hormone Regulation. Unlock your Potential with Sacred G Fusion's Pineal Gland Activation!

http://coryherter.com/?p=418

Pineal Gland & Circadian Rhythms by Cory Herter – Part 3 of 6

Pineal Gland & Circadian Rhythms by Cory Herter - Part 3 of 6. Discover the Power of the Pineal Gland and its relation to CIrcadian Rhythms. Harness the Power of your brain to create synchronicities in your life. Unlock your Potential with Sacred G Fusion's Pineal Gland Activation!

http://coryherter.com/?p=416

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Pineal Gland & Sleep by Cory Herter – Part 4 of 6

Pineal Gland & Sleep by Cory Herter - Part 4 of 6. Discover the Power of the Pineal Gland and its relation to Sleep and Healing. Harness the Power of your Sleep to unlock massive amounts of energy in your life and accelerate the natural healing process every night while you sleep. Unlock your Potential with Sacred G Fusion's Pineal Gland Activation!

http://coryherter.com/?p=414

Pineal Gland & Temperature by Cory Herter – Part 5 of 6

Pineal Gland & Temperature by Cory Herter - Part 5 of 6. Discover the Power of the Pineal Gland and its relation to Temperature and Speed. Harness the Power of Temperature, Adrenaline, Metabolism and more for Total Human Performance by Activating your Pineal Gland with Sacred G Fusion.

http://coryherter.com/?p=412

Pineal Gland – The Master Gland by Cory Herter – Part 6 of 6

Pineal Gland - The Master Gland by Cory Herter - Part 6 of 6. The Pineal Gland is the Master Gland of the Human Body and Human Experience. The Pineal Gland is our direct link to source, our body, our environment, health and performance. Activate Your Pineal Gland Now with the New Sacred G Fusion Technology available at www.CoryHerter.com

http://coryherter.com/?p=409

THE PINEAL GLAND IS A STARGATE – 23 PART SERIES

THE PINEAL GLAND IS A STARGATE SERIES - This Video Player contains 23 videos done by incredible beings of Light and they all talk about the Pineal Gland. Sacred G Fusion is the mathematical coding to unlock the Pineal Gland. Learn more about the information behind the Pineal Activation, watch this Series on www.CoryHerter.com

http://coryherter.com/?p=395

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Research

http://coryherter.com/?cat=98

Research with Sacred G Technology

Learn about some of the cool research and contribute to some of the projects that are going on with Sacred G Technology.

http://coryherter.com/?p=734

Sacred G Designs

http://coryherter.com/?cat=12

Sacred G Spot Design – 1 of 7

Discover what each Sacred G Design can do for you!! Learn the process that Sacred G uses to unlock your true potential. Finally learn how Sacred G can boost your energy so much! Be sure to download your Free Sacred G Designs at www.CoryHerter.com!

http://coryherter.com/?p=557

Sacred G Transporter Design – 2 of 7

Discover what each Sacred G Design can do for you!! Learn the process that Sacred G uses to unlock your true potential. Finally learn how Sacred G can boost your energy so much! Be sure to download your Free Sacred G Designs at www.CoryHerter.com!

http://coryherter.com/?p=555

Sacred G Ascender Design – 3 of 7

Discover what each Sacred G Design can do for you!! Learn the process that Sacred G uses to unlock your true potential. Finally learn how Sacred G can boost your energy so much! Be sure to download your Free Sacred G Designs at www.CoryHerter.com!

http://coryherter.com/?p=553

Sacred G Trancendance Design – 4 of 7

Discover what each Sacred G Design can do for you!! Learn the process that Sacred G uses to unlock your true potential. Finally learn how Sacred G can boost your energy so much! Be sure to download your Free Sacred G Designs at www.CoryHerter.com!

http://coryherter.com/?p=551

Sacred G Simulator Design – 5 of 7

Discover what each Sacred G Design can do for you!! Learn the process that Sacred G uses to unlock your true potential. Finally learn how Sacred G can boost your energy so much! Be sure to download your Free Sacred G Designs at www.CoryHerter.com!

http://coryherter.com/?p=549

Sacred G Activator Design – 6 of 7

Discover what each Sacred G Design can do for you!! Learn the process that Sacred G uses to unlock your true potential. Finally learn how Sacred G can boost your energy so much! Be sure to download your Free Sacred G Designs at www.CoryHerter.com!

http://coryherter.com/?p=547

Sacred G Fusion Design – 7 of 7

Discover what each Sacred G Design can do for you!! Learn the process that Sacred G uses to unlock your true potential. Finally learn how Sacred G can boost your energy so much! Be sure to download your Free Sacred G Designs at www.CoryHerter.com!

http://coryherter.com/?p=545

Bonus: Secret of the Sacred G Fusion Case

Discover the secret behind the New Sacred G Fusion Case!!!

http://coryherter.com/?p=543

Sacred G on MTV

http://coryherter.com/?cat=107

The Full Sacred G Episode on MTV's Rob & Big

Watch the complete episode of Rob & Big Featuring Sacred G Technology as a Performance Enhancement Tool. Sacred G Enhances the Performance Levels of Athletes doing Extreme Sports by reducing the amount of Electro-magnetic interference from power lines, cell phone towers, satellite signals and radio waves. Neutralizing this Negative Electro-Magnetic Polloution enables the brain to process information faster, increasing reaction time. In extreme sports, 1/10 of a second in reaction time is a very long time and can easily determine whether or not you land your trick, score a goal or beat your opponent.

http://coryherter.com/?p=426

Rob Dyrdek & Steve Berra Share Their Views about Sacred G on MTV

Steve talks about Sacred G being like Steroids while Rob Dyrdek lands a Switch Laser, a Skateboarding Trick he has never landed before!

http://coryherter.com/?p=273

Highlights from MTV's Hit Show Rob & Big Featuring Sacred G

Watch the Highlights from MTV's Hit Show Rob & Big Featuring Sacred G.

http://coryherter.com/?p=270

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Sacred G Uses & Tests

http://coryherter.com/?cat=13

Simple Instructions and Tips for using Sacred G Technology

Cory explains simple instructions on how to use Sacred G Technology from his years of experience. You might even learn some cool tricks from this old dog.

http://coryherter.com/?p=670

35 Uses & 5 Tests for Sacred G

The incredible thing about **Sacred G** is that it can be used to charge absolutely everything you put ***IN, ON & AROUND Your Body*** with it. As you begin sleeping on your **Sacred G** as well as charging your food and water with it, your body will begin to tell you how else it wants it to be used. We have listed over 35 methods you can use **Sacred G** to enhance your life below.

http://coryherter.com/?p=84

Go to the Full Page of 35 Uses and 5 Tests here by clicking here…
http://coryherter.com/?page_id=594

Sacred G Water Taste Test

The Sacred G Water Taste Test demonstrates how Sacred G Technology can purify your body and mind. Get the explanation for how Sacred G can purify a glass of water right before your eyes.

http://coryherter.com/?p=136

Sacred G Sleep Test – 5 Video Series

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Learn the different types of Sleep Effects that Sacred G will use to Increase Your ENERGY!!

http://coryherter.com/?p=975

Sacred Geometry

http://coryherter.com/?cat=94

The Secret of the Universe

The Secret of the Universe is the name given to the ancient knowledge of the inner workings of the universe. This includes (but is not limited to) the method by which huge megaliths can be reduced in weight and lifted, something also known to the Freemasons and the builder of Coral Castle up to the mid 1900's.

http://coryherter.com/?p=641

Science of LOVE DVD

http://coryherter.com/?cat=37

Science of LOVE Introduction

.

The Science of LOVE Introduction - Learn the Science behind Sacred G Technology with this 3 Hour DVD Special... Available Online for a Limited Time Only!!!

http://coryherter.com/?p=282

Science of LOVE DVD – A 3 Hour Video Series on the Science behind Sacred G

Cory Herter gives an amazing presentation into the math and physics behind Sacred G Technology. L.O.V.E., which stands for the Laws Of Vibrational Energy is the engine that drives Sacred G Technology and is a natural law of the universe contained within Sacred Geometry. Discover the deeper meaning of the Flower of Life, The All Seeing Eye, DNA Activation and more...

http://coryherter.com/?p=399

Sleep Test

http://coryherter.com/?cat=106

Sacred G Sleep Test – Beta (Tossing and Tuning) – Part 1 of 5

The Sacred G Sleep Test reveals which brain wave states you have an excess amount of unprocessed energy. This energy is released from using Sacred G Technology by altering the types of sleep you have. This is the body's natural healing mechanism and is crucial for regenerating the body.

http://coryherter.com/?p=1002

Sacred G Sleep Test – Alpha (Emotional Dreams) – Part 2 of 5

The Sacred G Sleep Test reveals which brain wave states you have an excess amount of unprocessed energy. This energy is released from using Sacred G Technology by altering the types of sleep you have. This is the body's natural healing mechanism and is crucial for regenerating the body.

http://coryherter.com/?p=1000

.

Sacred G Sleep Test – Theta (Educational Dreams) – Part 3 of 5

The Sacred G Sleep Test reveals which brain wave states you have an excess amount of unprocessed energy. This energy is released from using Sacred G Technology by altering the types of sleep you have. This is the body's natural healing mechanism and is crucial for regenerating the body.

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

http://coryherter.com/?p=998

Sacred G Sleep Test – Delta (Deep Sleep) – Part 4 of 5

The Sacred G Sleep Test reveals which brain wave states you have an excess amount of unprocessed energy. This energy is released from using Sacred G Technology by altering the types of sleep you have. This is the body's natural healing mechanism and is crucial for regenerating the body.

http://coryherter.com/?p=996

Sacred G Sleep Test – Brain Wave Conclusion – Part 5 of 5

The Sacred G Sleep Test reveals which brain wave states you have an excess amount of unprocessed energy. This energy is released from using Sacred G Technology by altering the types of sleep you have. This is the body's natural healing mechanism and is crucial for regenerating the body.

http://coryherter.com/?p=993

Tree of LOVE

http://coryherter.com/?cat=87

Secret of the Sacred G Fusion Case

Discover the secret behind the New Sacred G Fusion Case!!!

http://coryherter.com/?p=543

The Three Trees – The Tree of Life, Knowledge & LOVE

Cory shares the science behind the Word of God through Sacred Geometry. The Tree of Life, Tree of Knowledge and the Tree of LOVE are explained in detail. Cory shows how the ascension is attained through understanding the Laws Of Vibrational Energy.

http://coryherter.com/?p=936

Secret to Perfect Health - 1 Problem, 1 Solution, 6 Layers & the Tree of LOVE

Oct 27, 09 - Your Health, 1 Problem - 1 Solution - 6 Layers - Tree of LOVE

http://coryherter.com/?p=962

Video Testimonials

http://coryherter.com/?cat=28

Carolanne & Theresa's Sacred G Experience

Carolanne and Theresa are natural health practitioners and host workshops. Get the scoop on their experience of Sacred G and how they are using it with their practice.

http://coryherter.com/?p=909

David Shore, Sacred G Life Saver

David shares how Sacred G Technology saved his life... Literally!

http://coryherter.com/?p=901

David Caddell Sacred G Testimonial

David shares his experience on Sacred G Technology!

http://coryherter.com/?p=899

Druanna on Sacred G Technology

I am so excited about how Sacred G has seriously Changed my life! I no longer have insomnia problems or Heart problems! My good friend Beau Manley from the METAL MULISHA CREW is having wonderful experiences on it as well!! HE CANT GET ENUFF! LOL Looking forward to the Sacred Fusion experience and G PILLS!!!

http://coryherter.com/?p=896

David Shore shares his testimonial of Sacred G

David's story is definitely one that will keep you smiling as he talks about how Sacred G has transformed his life.

http://coryherter.com/?p=859

Pete Lewis's experience on Sacred G Technology

Listen to Pete share about how Sacred G has helped him get off meds and cleared his cat of some emotional baggage.

http://coryherter.com/?p=857

Loriel Hanon's Testimonial from Sleeping on 50 Cases of Sacred G Technology!!

Listen to Loriel's incredible story about how Sacred G helped her clear the trauma of losing her son and restore the positive memories of his life.

http://coryherter.com/?p=844

Taylor Angelos's amazing testimonial from sleeping on a Fusion Bed Set!!

Within 2 weeks of Sleeping on Sacred G Fusion, Taylor is already downloading new information in her dreams. Her ability to recognize patterns in her life and make more conscious decisions has already made a major impact and she is just getting started. Taylor was so impressed with Sacred G that she flew out to Denver to check out the new LOVE Practitioner Course.

http://coryherter.com/?p=842

JoAnne Jablonski's LOVE Practioner Course Experience

Find out what JoAnne thought about Cory Herter's brand new LOVE Practioner course in Denver Colorado.

http://coryherter.com/?p=840

Serena Carrico's experience of Sacred G Technology

LIsten as Serena shares her very first experience of Sacred G Technology and how it has impacted her life.

http://coryherter.com/?p=838

Serena's Healing with Dog at the LOVE Practitioner Course – AMAZING!!!

Listen to this incredibly gifted healer as she talks about how she used the new LOVE Practitioner Techniques to significantly reduce the size of a tumor on a dog at Cory Herter's Love Practitioner course held in Denver.

http://coryherter.com/?p=836

Solei Hannahs testimonial about Sacred G and its powerful cleansing effects!

Doing Healing for over 12 years and eating Raw for over 4 years, Solei's body was pretty purified. Sleeping on the Sacred G Bed Set, Solei discovered the amazing benefits of Sacred G. Solei shares with us the power of Sacred G's ability to cleanse the body on a whole new level than ever before.

http://coryherter.com/?p=834

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Loriel Hanon’s experience of the LOVE Practitioner Course

Loriel hosted Cory in Denver for the very first LOVE Practitioner Certification Course... Get the scoop from her for how the event went!

http://coryherter.com/?p=831

Alysha Duran’s experience on her Sacred G Fusion Bed Set

Alysha's noticed a major difference in her ability to detect patterns that she is playing out in her life and being able to consciously shift her own internal programming to accelerate her growth.

http://coryherter.com/?p=829

Allison Lee Clark – New Senses, Enhanced Meditation, Tons of Benefits!!

Listen to Allison's Testimonial of Sacred G Technology!!

http://coryherter.com/?p=825

Kara’s Sacred G Testimonial – Complete Life Transformation in 1 Year

Discover the Power Sacred G has had in transforming Kara's life as a result of sleeping on a Sacred G Bed Set.

http://coryherter.com/?p=731

.

Jayson’s Testimonial of Sacred G Technology

Discover the power of Sacred G in Jayson's life and how it has helped him get everything he had on his dream board 2 years ago.

http://coryherter.com/?p=665

Lee's Sacred G Testimonial – Kidney Transplant & Medication

Listen to Lee's incredible story about how Sacred G has been helping him to reduce his medication necessary after his kidney transplant.

http://coryherter.com/?p=659

Sacred G Testimonial from a Pediatrician's Office

Watch the Testimonials from a Pediatrician's office about the Power of Sacred G on their patients. This is an incredible Testimonial for the Power of Sacred G!

http://coryherter.com/?p=277

Rob Dyrdek & Steve Berra Share Their Views about Sacred G on MTV

Steve talks about Sacred G being like Steroids while Rob Dyrdek lands a Switch Laser, a Skateboarding Trick he has never landed before!

http://coryherter.com/?p=273

Highlights from MTV's Hit Show Rob & Big Featuring Sacred G

Watch the Highlights from MTV's Hit Show Rob & Big Featuring Sacred G.

http://coryherter.com/?p=270

Webinar Archives

http://coryherter.com/?cat=100

Aug 18, 09 Webinar – Sacred G and the Table of Elements

Cory weaves Sacred G, Anti-Gravity and the Mathematics of the Coral Castle into the Table of Elements and unveils a deeper layer of the mechanics of Life!

http://coryherter.com/?p=846

Aug 25, 09 Webinar – Cory shares insights on Sacred G Fusion and Q&A

Cory talks about some of his near death experiences and how they are connected with Sacred G Fusion as well as answering a bunch of questions from Skype Chat!

http://coryherter.com/?p=848

Sept. 1, 09 – Channeling Higher Energy States

Cory talks about channeling energy, the flow of unlocking information and how we all have the energy and power within us to heal.

http://coryherter.com/?p=851

Sept. 8, 09 Webinar – Financial Abundance

Cory tackles the debate on finance and spirituality and kicks the **** out of it!! Enjoy as Cory shares how to increase your financial abundance and demonstrates there is no conflict at all. Using the Tree of LOVE, Cory illustrates the flow of energy from a spiritual source through the core and into our external reality using financial abundance to complete the creation process.

http://coryherter.com/?p=913

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Sept. 15, 09 Webinar – Cleansing through Sacred G

Cory shares with everyone how the cleansing effects work and why it is so important to clear out the negative energy stored in past memories. Cleansing can come up through physical, emotional, mental and spiritual releases that can be a bit uncomfortable at times but well worth it in the end. Cory shares some of his story's of processing on Sacred G.

http://coryherter.com/?p=915

Sept 22, 09 Webinar – Sound Healing + Q & A from Chat Room

Cory shares simple yet extremely powerful techniques to use Sound for boosting energy in water and other products for Healing. Cory spends the remainder of the webinar answering questions from the Sacred G Skype Chat Room.

http://coryherter.com/?p=919

Oct 6, 09 Webinar – Cory talks Energy and Introduces the new LOVE Innerversity

Cory talks about the New Online LOVE Innerversity School. This incredible announcement has rocked the world of energy healers and natural health practitioners around the world. Join Cory as he literally opens up a new energy healing modality every week.

http://coryherter.com/?p=938

Oct 13, 09 Webinar – The Three Trees of Life, Knowledge & LOVE

Cory shares the science behind the Word of God through Sacred Geometry. The Tree of Life, Tree of Knowledge and the Tree of LOVE are explained in detail. Cory shows how the ascension is attained through understanding the Laws Of Vibrational Energy.

http://coryherter.com/?p=936

Oct 20, 09 Live Webinar – The Truth about 2012

The Truth about 2012 – Evolution, Conspiracy, 9-11, Privacy Act, Natural Selection, Light Workers and more!

http://coryherter.com/?p=951

Oct 27, 2009 Webinar – Your Health, 1 Problem, 1 Solution, 6 Layers & The Tree of LOVE

Oct 27, 09 - Your Health, 1 Problem - 1 Solution - 6 Layers - Tree of LOVE

http://coryherter.com/?p=962

©2009 – Cory Herter - All Rights Reserved. Sacred G, Inner G, Tree of LOVE, L.O.V.E. and all Sacred G Designs are registered trademarks and copy writes of Cory Herter.

Everyone and Everything within the vicinity of Sacred G will get blasted with positive vibes that unlock energy and boost performance. Increasing the amount of Sacred G you use will increase the amount of energy you have.

Sacred G Stickers come in 6 unique designs:



The Sacred G Spot is designed to physically cleanse your cells, freeing up more energy for the body to run more efficiently.



The Sacred G Transporter is designed to free up usable energy trapped as emotion in your past memories. Each night that you sleep on Sacred G, more and more energy is released restoring you to your natural state of Peaceful Bliss.



The Sacred G Ascender is designed to boost energy and increase self confidence by solving conflicts within your thoughts and belief systems. This enables you to perceive more information at once increasing your level of focus and reaction time.



The Sacred G TranceNdance is a combination of the first three designs plus advanced memory systems that accelerate the learning and downloading of new information from the collective consciousness.



The Sacred G Simulator is designed to upgrade your friendships and relationships by attracting new productive ones while empowering you to let go of old ones that no longer serve you. This design will increase the number of synchronicities in your life and create an awakened sense of adventure and purpose.



The Sacred G L.O.V.E.™ Activator combines all of the designs with a new motion activation system that takes you beyond your limits to achieve your goals. The Activator is the Ultimate State-of-the-Art DNA Activation Technology.

Visit the website to learn about the most advanced Sacred G Design called "Fusion" which incorporates every design into One.

Sleep / Pillow Case

Place the Sacred G beneath your pillow or inside your pillowcase design side up.

Notice how the Sacred G alters your sleep and dream states. The body frees up the most amount of energy while you sleep. Sacred G enhances this process continually increasing the amount of energy you feel.

Energized Water

Super Charge your water with Energy by placing it on top of the Sacred G.

Test: Take two glasses of tap water, place one on top of the Sacred G, and the other at least six feet away. Allow the water to charge overnight, then taste the difference between the two glasses in the morning. This test shows how Sacred G Technology not only cleans your water, but is also instrumental in physically cleansing the toxins from your body increasing energy.

> "I will never ride a board that's not G'd out again!"
>
> *Rob Dyrdek*

X-treme Performance Enhancement: Place the Sacred G on skateboards, surfboards, team uniforms, or any gear and equipment that you use. Watch as your performance is enhanced and your game is improved.

Visit the website to learn over 35 ways to use Sacred G to boost your energy, plus 5 cool tests that you can do. Also, be sure to watch the Sacred G episode on MTV's Rob & Big show to see how Sacred G can boost your Performance.

Visit the website to download all of the Sacred G Designs for FREE! Bonus: Watch a 3 hour video on the science of Sacred Geometry!

www.CoryHerter.com

© 2008 - Cory Herter

SACRED G SPOT



WWW.CORYHERTER.COM

©2008 - CORY HERTER

Sacred G Transporter



www.CoryHerter.com

©2008 - Cory Herter

SACRED G ASCENDER



WWW.CORYHERTER.COM

©2008 - CORY HERTER

Sacred G TranceNdance



www.CoryHerter.com

©2008 - Cory Herter

SACRED G SIMULATOR



WWW.CORYHERTER.COM

©2008 - CORY HERTER

Sacred G Activator



www.CoryHerter.com

©2008 - Cory Herter

针灸

Claudia Focks

Atlas of Acupuncture



CHURCHILL
LIVINGSTONE
ELSEVIER

Dedication

To my parents Paula and Alfons Focks who have always supported my siblings and me in finding and pursuing our own paths, with love and gratitude

Commissioning Editor: Karen Morley, Claire Wilson
Development Editor: Kerry McGechie, Martin Mellor
Project Manager: Morven Dean
Designer: Stewart Larking
Photographs: Anja Messerschmidt
Graphics: Henriette Rintelen

CHURCHILL
LIVINGSTONE
ELSEVIER

CHURCHILL LIVINGSTONE
An imprint of Elsevier Limited

First and second edition published in German under the title *Atlas Akupunktur*
1. First edition 1998
2. Second edition 2006
© Elsevier GmbH, München

First edition published in English
© 2008, Elsevier Limited. All rights reserved.

The right of Claudia Focks to be identified as editor of this work has been asserted by her in accordance with the Copyright, Designs and Patents Act 1988

No part of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording or otherwise, without the prior permission of the Publishers. Permissions may be sought directly from Elsevier's Health Sciences Rights Department, 1600 John F. Kennedy Boulevard, Suite 1800, Philadelphia, PA 19103-2899, USA: phone: (+1) 215 239 3804; fax: (+1) 215 239 3805; or, e-mail: healthpermissions@elsevier.com. You may also complete your request on-line via the Elsevier homepage (http://www.elsevier.com), by selecting 'Support and contact' and then 'Copyright and Permission'.

First edition	**1998**
Second edition	**2006**
English edition	**2008**

ISBN-13: 9780443100284
ISBN-10: 0443100284

British Library Cataloguing in Publication Data
A catalogue record for this book is available from the British Library

Library of Congress Cataloging in Publication Data
A catalog record for this book is available from the Library of Congress

Notice

Neither the Publisher nor the Editor assumes any responsibility for any loss or injury and/or damage to persons or property arising out of or related to any use of the material contained in this book. It is the responsibility of the treating practitioner, relying on independent expertise and knowledge of the patient, to determine the best treatment and method of application for the patient.

The Publisher

ELSEVIER your source for books, journals and multimedia in the health sciences
www.elsevierhealth.com

Working together to grow
libraries in developing countries
www.elsevier.com | www.bookaid.org | www.sabre.org
ELSEVIER BOOK AID International Sabre Foundation

Printed in China

The Publisher's policy is to use **paper manufactured from sustainable forests**

Preface

'An acupuncture point is located where it is located' – like veins, arteries or nerves, the location of acupuncture points may vary. Consequently, locating and stimulating acupuncture points is an individual process in each patient, similar to locating veins or arteries for puncture. The goal of this atlas is therefore to help acupuncture students and therapists find the correct location of acupuncture points. Ultimately, the exact location of an 'acupuncture hole' will be where it can be palpated, addressed energetically in a safe way, and – most importantly – where it will be therapeutically effective.

Acupuncture therapy requires not only the knowledge to locate individual points but also an understanding of the context of these points. This atlas therefore includes both a description of the individual points as well as the central idea – the channel system.

The core chapters 4, 5 and 6 contain single page portraits of all the channel points as well as extra points used in body acupuncture. The clearly structured page layout, complemented by pictograms, allows for quick access to the clinically relevant information for the location and indication of individual points. Clear step-by-step instructions guide the reader through the surrounding surface anatomy to the correct location of the point. Figures with the relevant anatomical structures, as well as drawings showing channel pathways pertaining to the relevant region of the body, provide a further practical aid for correct point location. The text and the photo details also contain information regarding other points located in the vicinity or points in comparable locations in other parts of the body. This not only draws attention away from the individual points to the larger anatomical orientation, but also fosters an understanding of the context between the location and the action of a given point.

Chapter 7 presents the channel points according to the anatomical region – including illustrations of anatomical overview as well as text/picture details. This format will deepen the understanding of the anatomical relationship between the channel points and complete this academic concept. Chapter 2 'Location Methods and Cun Measurements' and Chapter 3 'Anatomical Orientation' provide further support in locating the individual points. The modified illustrations in these chapters are based on the well-known Sobotta Atlas.

Chinese medicine practitioners work with the Qi and its flow. In this context the individual 'acupuncture hole' has both an anatomical and an energetic component and is an intrinsic part of the channel and vessel network, which provides an exchange between the body's Exterior and Interior. In this way Chapter 1 describes the network of channels and vessels, and Chapter 8 the point categories and point combinations, explaining them in terms of their effects with relation to channel energetics, and presenting them in a clearly defined and visually organised manner. Chapter 9 contains up-to-date information and data about the scientifically proven effects or otherwise of individual points.

I hope the new edition of this atlas will provide a valuable help to students and therapists alike in studying acupuncture and applying the information in clinical practice. I look forward to hearing your constructive criticism and ideas.

Claudia Focks, March 2008

Acknowledgements

This Acupuncture Picture Atlas is a joint project of many very helpful contributors who have helped to complete it.

First of all my thanks go to the models and especially to the photographer Anja Messerschmidt. Her understanding and photographic skills provided the visual foundation for the Atlas to also be an artistic ‘feast for the eyes’.

I would like to thank the graphic designer Henriette Rintelen for the successful graphic design and converting my ideas into visual images.

Thanks go to my colleague Ulrich März for the succint arrangement and editing of the chapter on Anatomical Orientation as well as his contributions to the core chapters. I would like to thank my colleague Ingolf Hosbach for his contributions to the chapter on Research as well as his idea about the visually concise pictograms and for partially converting them by computer.

I want to thank all the staff at Elsevier involved in this project for their, once again, very productive co-operation. My thanks go particularly to Rolf Lenzen for agreeing to do the atlas, Christine Kosel for dealing with the gruelling organisation during production, as well as Petra Münzel-Kaiser and Christl Kiener for editing. My thanks extend particularly to Christl Kiener for her numerous ideas and fruitful exchange of concepts.

My heartfelt gratitude also includes my teachers who have sown the nourishing spark of enthusiasm for Chinese and energetic medicine. I thank my patients for their trust and for allowing me to learn from them.

I would also like to thank the strong women in my family and my circle of friends for their inspiration and being a source of vibrant female power. Thank you to my sister Annette Focks for her friendship and wonderful music, which helped me overcome some of the hurdles of this project. I extend particular thanks to Anneliese Solenski and Christa Skopp for their helpful support with my private affairs.

Above all I want to thank my inspirational husband Christoph Ranzinger and our wonderful children Tabea and Lasse for their love and generous tolerance, without which the Atlas would not have been possible.

For the English edition I would like to extend my thanks to the staff at Elsevier in London, particularly Karen Morley for accepting the atlas and to Kerry McGechie and Martin Mellor for the extensive editing work. Thank you also to Johanna Schuster who has translated the Atlas into English with great care and knowledge.

Claudia Focks, Rottweil, March 2008

About the editor and contributors

Dr med. Claudia Focks, Rottweil: anaesthesiologist, additional qualification in naturopathy and homeopathy; training in Chinese Medicine in China, Austria, and Germany, postgraduate training at the ETHNOMED Institut für Ethnomedizin e.V. (Institute for Ethnomedicine, registered charity) in Munich. Clinical focus on Chinese Medicine and energy therapies. Co-editor and co-author of *Leitfaden Chinesische Medizin* (*Chinese Medicine: An Introduction*), co-author of *Leitfaden Akupunktur* (*Acupuncture: An Introduction*), both published by Elsevier Munich. Lectures on Chinese Medicine, both in Germany and abroad.

Dr med. Ulrich März, Ulm: General practitioner with his own practice, focus on acupuncture and Traditional Chinese Medicine. Adjunct lecturer at the University of Ulm for acupuncture and TCM. Project manager for the postgraduate programme for acupuncture and TCM at the Akademie für Wissenschaft, Wirtschaft und Technik (Academy for Science, Economy and Technology) at the University of Ulm. Co-author of *Leitfaden Akupunktur* (*Acupuncture: An Introduction*), published by Elsevier Munich.

Dr med. Ingolf Hosbach, Bochum: Anaesthesiologist, additional qualification in palliative therapy. Employed at the University Clinic Bergmannsheil Bochum. Adjunct lecturer at the Universities of Witten/Herdecke and Bochum. Scientific publications and lectures on palliative therapy, acupuncture and TCM research. Webmaster of the homepage of the Department for Chinese Medicine at the University Witten/Herdecke and of the DWGTCM e.V. (www.dwgtcm.com).

Pictogrammes



Angle of insertion: The angle of insertion recommended for a particular point (see figure below) is shown in colour. (Note that occasionally more than one angle is possible – this is signified by colouring as appropriate).



Depth of insertion: Shallow: up to 0.5 cun, **Medium:** 0.5–1 cun, **Deep:** >1 cun. (In some cases more than one depth is possible depending on the angle of insertion – this is signified by colouring as appropriate).

Caution! Organs and structures such as the eyes, nerves, blood vessels, peritoneum (symbolised by intestinal tissue) etc. that might be injured by needling a particular point are shown by a symbol together with a blue exclamation mark. A lightning bolt signifies a point that is painful when needled.



Moxibustion: In principle all points can be treated with moxibustion. The following options are pointed out: **Blue colour below moxa cigar:** moxibustion particularly recommended, **Question mark next to moxa cigar:** moxibustion questionable (contraindicated according to some classical texts, but contradictory information), **Moxa cigar crossed out:** moxibustion contraindicated.



Bloodletting: In principle bloodletting may be applied to all points. **Neutral pictogramme:** bloodletting possible, **Blue droplet of blood:** bloodletting particularly recommended, **Blue question mark:** bloodletting questionable



Blue cup: Cupping particularly recommended.



Anatomical orientation: A blue hand signifies cases where anatomical structures are of particular importance for point location (for more detail → chapter 3).



Angle of insertion

a) Angle of insertion and layers of tissue: All needles are inserted to the same 'depth' (=the same proportion of the needle is inserted into the tissue), but reaching different levels of tissue.

b) Angle of insertion: transverse (subcutaneously): 5–15°; oblique: 15–45°; perpendicular: 90°.

Point hierarchy (Chapters 4–6)

In the introductions to the channels (chapters 4–6) the importance of points are marked with the following symbols:

■■: very important, universal point

■■: important point

This hierarchy is of course subjective and influenced by the authors' clinical experience but has proved very helpful for beginners.

1 *Jing luo* (Channel and Network Vessel System)

Claudia Focks

1.1 Introduction

1.1.1 Two Models of Qi Flow in the Channels – Historical Overview

There exist essentially two views about the direction of the Qi flow in the channels, which are based on different understandings of the Qi movement within the body (→ Pirog 1995, Manaka 1995/2004). For a better understanding of either model, imagine a person extending his/her arms towards the sky (→ Figs. 1.1 and 1.2).

Centripetal circulation model

The centre of classical Chinese cosmology, which describes humans as standing between heaven (Yang) and earth (Yin), includes the mutual relationship, influence, and dependence between cosmos and man. Accordingly, early records of the pathways (→ see appendix) depict the (11/12) channels as pathways that originate at the extremities, flow towards the centre of the body and terminate either on the head or the torso. This is the distinguishing feature of the **centripetal circulation model** (→ Fig. 1.1).



Fig. 1.1 Centripetal circulation model (modified according to Pirog 1996)

This model is also present in the theory of the five *shu*-Transporting points (→ 8.1.6). The macrocosmic Qi enters the body at the tips of the extremities and can be compared to the course of a river. It begins very dynamically as a well, spring and stream, expands to form a river and flows into the wide, deep sea at the elbows and the knees and then further to the internal organs via the channels.

According to this model, the functions of the channels can be compared to antennae, which receive the cosmic influence, transmitting it into the body. The Qi flow in the channels is always from distal (coming from the Exterior, entering at the tips of the extremities) to proximal (towards the centre, flowing towards the internal organs). Each channel connects man with a different part of the cosmos, which can be identified by a numerological structure. Thus a relationship was assumed between the eight extraordinary vessels and the eight trigrams of the *Yijing* (→ 1.7). The primary channels reflect the 12 earthly branches and the 10 heavenly branches. Since the early records only mention 11 channels (→ Appendix 2), they were counted as 10 channels on the arms and 12 channels on the legs. Later, the 12 primary channels were mainly associated with the 12 earthly branches – the 10 heavenly branches rather representing the Five Phases model (*note*: the earthly branches can be included in the latter as well).

Self-contained circulation model

In the course of the development of modern Chinese society, the idea of a close relationship between man and cosmos (as a heaven-earth-man model) became weaker. The channel system was now increasingly compared to phenomena created by man himself such as **canals** and **drainage ditches**. The importance of the original connection with the cosmos declined while that of relationships within society was on the rise. Chinese society became more complex, forming a self-contained unit. Similarly, the concept of the channels as a connection to the macrocosm was partially abandoned and the Qi flow is described as independent and self-contained (→ Fig. 1.2). According to this **self-contained circulation model**, Qi can flow forward as well as backward – from the outer extremities to the Interior of the body and from the Interior to the Exterior.



Fig. 1.2 Self-contained circulation model (modified according to Pirog 1996)

Thus the direction of the Qi flow in the primary channels can be from proximal to distal and vice versa, depending on the Yin/Yang polarity of the respective channel, as well as the respective extremity.

This second, probably more recent concept describes the Qi **as circulating continuously** through the body (➞ Appendix 2): from the thorax to the hand, to the head, to the foot and back to the thoracic region. These ideas reflect the development of the Chinese civilisation, its agriculture and in particular its **water control** and water **storage** in reservoirs, drainage canals, ditches, etc., which largely form the foundation of the theory of the **channels as water conduits** circulating Qi and Blood. The connections among the channels are considered to be anastomoses (➞ 1.2.2), which facilitate the ceaseless, circular flow of Qi from one channel to the next, allowing the exchange of the Qi flow with the Interior.

The self-contained circulation model can thus be described as follows:

- Hand Yin channels run from the thorax to the hand: **LU, HE, P**
- Hand Yang channels run from the hand to the head: **L.I., S.I., T.B.**
- Foot Yang channels run from the head to the foot: **ST, BL, G.B.**
- Foot Yin channels run from the foot to the thorax: **SP, KID, LIV**

More importance is attached to this model of Qi flow in the Western acupuncture tradition, which can in part explain the use of numbers in naming the acupuncture points, rather than names as in China.

However, the structure of this new circulatory model was probably also too rigid to sufficiently explain some of the effects of acupuncture. According to Pirog (1996), this might be the reason why the secondary channels, for example the sinew channels (➞ 1.4) and the divergent channels (➞ 1.3), with their rather primitive and natural pathways, were integrated into the channel and network vessel system (*jing luo*) in accordance with the **centripetal** circulation model.

Comparison of the two circulation models (modified according to Pirog 1996)

	Centripetal model	Self-contained model
Direction of Qi-flow	Always from distal to proximal	Either from proximal to distal or vice versa, depending on the polarity of the channel (Yin/Yang)
Origin of Qi	From outside the body. The distal end of the channel is open in order to receive cosmic Qi	Originates in the inside of the body. The distal end of the channels is connected to the channel that follows next.
Function of the channels	Transporting the Qi from the outer cosmos to the Interior of the body. Supporting the relationship between man and nature/ cosmos	Circulation of the Qi inside the body. Supporting man's relationship with himself

1.1.2 Overview of the Channel and Network Vessel System (*jing luo* System)

In *Ling Shu*, chapter 11, it says: 'Man lives, diseases occur … both the beginner and the experienced master always have to start with the channels and network vessels (*jing luo*).'

In Chinese Medicine, the *jing luo* are considered to be a network of channels and vessels in which the Qi and Blood (*xue*) flow. They are connected to the Organ systems (*zangfu*) and 'water' the whole organism, supplying the body with Qi and Blood (*xue*) on the surface (Exterior) and deep inside the body (Interior), above as well as below.

From a functional point of view, the channels and network vessels (*jing luo*) govern the distribution of Qi and Blood (*xue*), they regulate Yin and Yang and they protect the body. However, they also enable the spreading of diseases. Reactions to any disorders may therefore manifest along these channel pathways. These could be either disorders of the channels themselves, or external reflections of *zangfu* disorders. In clinical practice, the channels and network vessels (*jing luo*) can be utilised in order to send Qi to the diseased parts of the body (for an overview of the classification and nomenclature of the *jing luo* system ➞ Fig. 1.3).


a)
Jing luo (channel and network vessels)
Jing mai (channels)
12 *jing zheng* (primary channels)
shou (Hand)
3 *yin*
tai yin LU channel
shao yin HE channel
jue yin P channel
3 *yang*
tai yang S.I. channel
shao yang T.B. channel
yang ming L.I. channel
zu (Foot)
3 *yin*
tai yin SP channel
shao yin KID channel
jue yin LIV channel
3 *yang*
tai yang BL channel
shao yang G.B. channel
yang ming ST channel
12 *jing bie* (divergent channels)
12 *jing jin* (sinew channels)
8 *qi jing ba mai* (extraordinary vessels)
ren mai du mai
chong mai dai mai
yin qiao mai yang qiao mai
yin wei mai yang wei mai
Luo mai (*luo*-vessels)
12 *luo*-connecting vessels (begin at the extremities)
Spread from the primary channels
4 *luo*-connecting vessels (begin at the torso)
1 spreads from the SP primary channel (great *luo*-connecting vessel of the Spleen)
2 spread from the extraordinary vessels (*ren mai* and *du mai*)
1 spreads from a *fu*-Organ (great *luo*-connecting vessel of the Stomach)
Small *luo*-connecting vessels (superficial *luo*)
sun luo Vertical branches of the *luo mai*
fu luo Sub-branches of the *sun luo*
xue luo Horizontal branches of the *fu luo*
12 *pi bu* (cutaneous zones)
Superficial aspect of the *jing luo* system (channel and network vessel system), covering it towards the Exterior (outer layer)
b)
12 *jing zheng* (primary channels) = 6 *liu jing* (great channels)
3 *yin*
tai yin
shao yin
jue yin
3 *shou* (Hand)
tai yin LU channel
shao yin HE channel
jue yin P channel
3 *zu* (Foot)
tai yin SP channel
shao yin KID channel
jue yin LIV channel
3 *yang*
tai yang
shao yang
yang ming
3 *shou* (Hand)
tai yang S.I. channel
shao yang T.B. channel
yang ming L.I. channel
3 *zu* (Foot)
tai yang BL channel
shao yang G.B. channel
yang ming ST channel

Fig. 1.3 (a) Overview and classification of the *jing luo* system (channel and network vessel system); (b) the 12 primary channels and the six great channels *(liu jing)*

1.1.3 Distribution and Organisation of the Channel and Network Vessel (*jing luo*) System

According to the law of the Exterior–Interior (*biao-li*) the 'Exterior' communicates with the 'Interior'.

Exterior (*biao*) corresponds to the skin, the muscles and the pathways of the channel and network vessel superficial (*jing luo*) system. The deeper pathways of the channels and the Organ systems (*zangfu*) are attributed to the Interior (*li*). A particular organisational structure within the *jing luo* system is necessary to safeguard the circulation of Qi and the communication between the Exterior and the Interior. In this respect, the extraordinary vessels play a special role. While they play a major role in coordinating and regulating the primary channels and the *jing luo* system in general, they do not directly connect the Interior and the Exterior. There is also no direct connection between the extraordinary vessels and the *zangfu*-Organs (see → 1.7 and Chapter 5).

Depth organisation of the *jing luo* system

Differing ideas exist regarding the depth at which the various channels and vessels are located within the body. The table below and Fig. 1.4 show the ideas according to Solinas et al. (1998) and Deadman et al. (1998) in a modified way. While these authors regard the deep, Interior pathways of the primary and divergent channels as the deepest channel structures, other authors attribute this role to the eight extraordinary vessels (for the eight extraordinary vessels, see → 1.7).

Overview over the possible location with regard to depth of the *jing luo* system

Levels	Channel system
Superficial levels (skin and muscles)	• 12 cutaneous regions • Superficial *luo*-connecting vessels (*xue luo, fu luo, sun luo*) • 12 sinew channels (*jing jin*)
Mid-levels	• 15/16 *luo*-connecting vessels (*luo mai*) • External pathways of the 12 primary channels • External pathways of the 12 divergent channels (*jing bie*) • Eight extraordinary vessels
Deep levels (*zangfu*-Organs)	• Deep (internal) pathways of the 12 primary channels • Deep (internal) pathways of the 12 divergent channels


Superficial levels
Mid levels
Deep levels
Pi bu (cutaneous zones)
xue luo
fu luo
sun luo
xue luo
fu luo
sun luo
Yang sinew channels
Yin sinew channels
he-confluence
Longitudinal branch of the yang luo mai
Yang primary channel
External pathway
li
yuan-source point*
Transverse branches of the yin luo mai
Transverse branches of the yang luo mai
Yin primary channel
li
External pathway
Longitudinal branch of the yin luo mai
luo point
Deep (internal) pathway of the Yin primary channels
Deep (internal) pathway of the Yang primary channels
Yin divergent channel
Yang divergent channel
Yin
Yang
zangfu-Organs
* according to some authors to the yuan-source point of the Interiorly–Exteriorly paired channel

Fig. 1.4 Illustration of the possible organisation of the *jing luo* system (channel and network vessel system)

Channel systems

Each primary channel, together with its pertaining 'secondary channels', forms a complex, multi-layered organisational unit, a 'system'. These systems comprise the various relationships and connections among each other as well as with the eight extraordinary vessels (→ 1.7, → Chapter 5). They support the harmonious regulation within the body. There are 12 channel systems (hand *taiyin*, hand *yangming*, etc.), each of which includes the following:

- a **primary channel** (*jing zheng*) (→ 1.2) with an external and internal pathway, which enters its pertaining *zangfu*-Organ
- a **divergent channel** (*jing bie*) (→ 1.3)
- a **sinew channel** (*jing jin*) (→ 1.4)
- a great ***luo*-connecting vessel** (*luo mai*) (→ 1.5).

In turn, the **cutaneous zones** (*pi bu*) (→ 1.6) wrap around the whole channel system.

1.1.4 Qi Circulation and the Channel System

What moves with and within the channels?

The channel system represents the 'pathway of the Qi'. In acupuncture many schools of thought work with the **True Qi (*zhen qi*)**, which, according to Maciocia (1989), represents the final stage of a process of Qi refinement and transformation: the Gathering Qi (*zong qi*), acted upon by the Original Qi (*yuan qi*) as a catalyst, becomes True Qi (*zhen qi*), which manifests in its two aspects, the Defensive Qi (*wei qi*) and the Nutritive Qi (*ying qi*). According to Larre and Rochat de la Vallée (1986), the True Qi is regarded as the **sum of all Qi mechanisms and/or forms of Qi** in the body. In other words: if there is a balanced and harmonious flow in the channels, this can be called True Qi (*zhen qi*). It means that which circulates in the 'here and now'. The sum total of all forms of Qi in their correct alignment is called **Upright Qi (*zheng qi*)** and forms the counterpart to Evil Qi (*xie qi*), for example to pathogenic factors or counterflow Qi.

Forms of Qi

Essence (Qi) (*jing qi*)

The Essence (Qi) acts within the organism and, according to some authors, to some extent also in the extraordinary vessels (→ 1.7). It represents the combination of Early Heaven Essence inherited from the parents, which, according to many schools of thought, is stored in the Kidneys and has a relationship to the Life Gate (*mingmen*), and the Later Heaven Essence of the Middle Burner. They support and complement each other.

Original Qi (*yuan qi*)

The Original Qi (*yuan qi*) is often described as the **active form of Essence (*jing*)**, circulating in the channels and spreading to the whole organism with the help of the Triple Burner. Like a catalyst, it is the dynamic driving force which wakens and sustains the functional activity of all organs and structures. It has a pre- and a postnatal component. Therefore its proper functioning is dependent on the supply of acquired Qi derived from water and food supplied by the Middle Burner. The Original Qi can be directly accessed and influenced at the *yuan*-source points (→ 8.1.1) or at the points **Ren-17** (*danzhong/shanzhong*), **Ren-12** (*zhongwan*) and **Ren-6** (*qihai*).

Gathering Qi (*zong qi*)

According to Larre and Rochat de la Vallée (1986), the Gathering Qi (*zong qi*) is formed in the centre of the thorax when the essences derived from respiration (Great Qi, *da qi*) meet with the food (*shui gu*, from Grain Qi (*gu qi*) and water) and are set in motion through ancestral mechanisms by the first postnatal breath. Like an 'engine', it dictates the rhythm and circulation, it controls respiration and it regulates the heartbeat. It does not circulate itself, but is like a 'Sea of Qi' that 'collects' in the centre of the thorax behind **Ren-17** (*danzhong/shanzhong*). This sea contains the water from all the rivers (e.g. the vessels), resembling an inexhaustible reservoir that does not overflow but redistributes all its water supplies.

Defensive Qi (*wei qi*)

The *wei qi* is the body's **Defensive Qi**. Thus it defends the body at the level of the skin, the fascia and the muscles. In relation to the Nutritive Qi (*Ying qi*), it is a more slippery and less pure form of Qi that moves dynamically and quickly through the body like a **guard**. Its root lies in the **Lower Burner**, where it is produced by the ***mingmen***-Fire (Life Gate fire), so that it has a considerable genetic or constitutional component. Essence (*jing*) and Original Qi (*yuan qi*), which are stored in the Lower Burner (according to many schools in the Kidneys), are involved in the formation of Defensive Qi (*wei qi*), therefore also playing a role in the defence against Exterior pathogens. Additionally, the *wei qi* is constantly being replenished with pure essence, formed from food by the Spleen and Stomach in the **Middle Burner**. It is dispersed throughout the body by the **Upper Burner**. Proper functioning of the *wei qi* therefore depends on all three Burners.

Nutritive Qi (*ying qi*)

The Nutritive Qi (*ying qi*) is the result of a purification and/or distillation process of pure, clear origin. Compared to Defensive Qi (*wei qi*), it is more Yin in nature. It **nourishes** the whole body and is its '**building substance**', thus often translated as 'constructive Qi' or 'building energy'.

Circulation of Defensive Qi (*wei qi*) and Nutritive Qi (*ying qi*)

Circulation of Defensive Qi (*wei qi*)

In chapter 43 of the *Su Wen* the *wei qi* is described as flowing 'outside of the *mai*' (the channels and vessels). However, it circulates in part along the channel pathways, moving in the space between the skin and the muscles – the ***cou li***.

The *cou li* – often unsatisfactorily translated as ‘pores’ – are the striae or compartments between the skin and the muscles. They have the function of a gateway for the entry and exit of Qi and fluids and serve as protection against the invasion of Exterior pathogenic factors. According to Larre and Rochat de la Vallée (1986), the *cou li*, as the outermost of the wrappings of the Triple Burner, cover the whole body. They connect the surface of the body with its inner organs. This explains the effectiveness of acupuncture and other manual therapies for the treatment of internal disorders as well as showing up the presence of diseases of the inner organs on the Exterior of the body.

In the **superficial layers of the body**, the Defensive Qi (*wei qi*) circulates through the skin and the superficial musculature, warming, nourishing and strengthening them. Through these actions it supports the general defence against Exterior pathogenic factors, acting mainly in the realm of the sinew channels (*jing jin*) (→ 1.4). In the **deep layers of the body**, it plays an important role in the functioning of the ‘diaphragm’. According to Larre and Rochat de la Vallée (1986), this represents not only a membranous barrier between the thorax and the abdomen, but can be regarded as a ‘sac of membranes’, including and connecting the peritoneum, the pleura and the pericardium. Nielsen (1995) interprets this ‘network of caves’ as the **inner aspect of the Triple Burner**, which connects with its **outer aspect, the *cou li***. Following this interpretation, the Defensive Qi (*wei qi*) would also be involved with the **mesenteric defence** and the protection of the inner organs.

According to chapter 75 of the *Ling Shu*, the **circulation of the Defensive Qi (*wei qi*)** is cyclical, changing from day to night and vice versa. At dawn, when the Yin Qi is exhausted, the Yang Qi pours itself from the eyes and the eyes are opened. As a result, the *wei qi* rises from the heel via the (Yin) *qiao mai* upwards to the eye to **BL-1** (*jingming*) and flows into the whole body like a waterfall by following the six great Yang channels – ‘it moves 25 times in the Yang’. At dusk, when the Yang Qi is exhausted, the *wei qi* enters the Interior of the body and moves ‘25 times in the Yin’, following the controlling cycle (*ke* cycle → 8.2.5): from the Kidneys to the Heart, from the Heart to the Lungs, from the Lungs to the Liver, from the Liver to the Spleen, and back to the Kidneys. Therefore the *wei qi* has a relationship with the sleep–wake rhythm: during sleep it withdraws deeper into the body – during daytime it circulates in the outer layers of the body. The two extraordinary vessels, the *yin qiao mai* and the *yang qiao mai* (→ 1.7, → Chapter 5), play an important role in this respect. If their cycle is blocked, the circulation of the *wei qi* will be interrupted and disorders will arise. The *yin qiao mai* ascends, while the *yang qiao mai* descends, both meeting at the eyes at **BL-1** (*jingming*) and forming a cycle, similar to the small heavenly cycle of the *ren mai* and *du mai*. If there is an excess of Yang Qi, this will be drained from the channels into the *yang qiao mai*, ‘the eyes cannot close’ and insomnia will occur. If there is an excess of Yin Qi, this will be drained from the channels into the *yin qiao mai*, ‘the eyes cannot open’ and somnolence will occur. In both cases, a relative disharmony develops between the two opponents.

Circulation of the Nutritive Qi (*ying qi*)

The Nutritive Qi (*ying qi*) circulates in the *mai*. The *mai* include both the primary channels (*jing mai*) and the secondary channels such as the Connecting Vessels (*luo mai*, *sun luo*), the divergent channels (*jing bie*), the extraordinary vessels and the Blood Vessels. Wherever there are channels and vessels, the *ying qi* will circulate. According to chapter 16 and 18 of the *Ling Shu*, the *ying qi* circulates constantly and continuously.

First circulation of the *ying qi* (→ Fig. 1.5)

The first circulation of the *ying qi* encompasses the 12 primary channels. The cycle **starts** at the **primary LU channel** and **ends** at the **primary LIV channel**, which in turn connects with the primary LU channel, thus closing the cycle (→ Fig. 1.5). The **Middle Burner** provides and **distributes** the *ying qi* throughout the whole body. According to some of the classics, the Grain Qi (*gu qi*) derived from food is only transformed into Nutritive Qi (*ying qi*) in the Lungs, not already in the Middle Burner. Since the internal pathway of the primary Lung channel begins in the Middle Burner, these two statements do not contradict each other in principle.



Fig. 1.5 First circulation of the Nutritive Qi (*ying qi*)

The **changes in Yin/Yang polarisation** – the changes from a Yin channel to a Yang channel and vice versa – always take place in the hand or the foot (also → 1.2.2). For example, the Yang energy potential rises from the Yin channel to the Yang channel, and then descends again from the Yang channel to the Yin channel (→ Fig. 1.6).


yang
L.I.
ST
S.I.
BL
T.B.
G.B.
Yin/Yang connection
Polarisation zone
Yin/Yang connection
LU
SP
HE
KID
P
LIV
Yin
3^{00} 5^{00} 7^{00} 9^{00} 11^{00} 13^{00} 15^{00} 17^{00} 19^{00} 21^{00} 23^{00} 1^{00} 3^{00}

Fig. 1.6 Changes in Yin/Yang polarisation, shown as a sinus curve

First circulation of the Nutritive Qi (*ying qi*) and the Organ clock

The Nutritive Qi (*ying qi*) circulates in the 12 primary channels in a **circadian 24-hour rhythm** (→ Fig. 1.7) with each **Chinese hour**, named after one of the 'earthly branches', corresponding to two Western hours (→ expanded Organ clock, Fig. 1.8).

Each two-hour slot favours a particular channel, in other words: for two (Western) hours per day, **energy flow peaks** in a particular channel. During this period, the respective channel Qi increases, falling again during the following two hours. However, it will never fall below a particular level, so that there is always a certain portion of energy flowing continuously through the channels.

Example: The channel Qi of the primary Stomach channel will begin to appear more 'powerful', when the channel Qi of the Large Intestine is very strong. Therefore the 'high tide' of the Stomach channel takes place between 5–7 a.m., its peak is between 7–9 a.m. and its 'low tide' between 9–11 a.m. During the peak period of the Stomach channel, the channel on the opposite side of the Organ clock is at its lowest point (→ 8.3.7); while the Stomach channel is peaking, the Pericardium channel is at its lowest point.

In figure 1.8 the 'expanded Organ clock' with its 24-hour circulation through the 12 primary channels is shown in relation to the earthly branches and the hexagrams of the *Yijing*.


Midnight
23
1
3
5
7
9
11
13
15
17
19
21
Gall bladder
Liver
Lung
Large Intestine
Stomach
Spleen
Heart
Small Intestine
Bladder
Kidney
Pericardium
Triple Burner
Noon

Fig 1.7 Organ Clock


Noon
Time of day
11–13 hours
Earthly branches
9–11 hours
13–15 hours
Heaven
Wu
Si
Wei
Heart
Spleen
Small Intestine
7–9 hours
15–17 hours
Chen
Gou
Qian
Dun
Shen
Sto-mach
Guai
Hexa-gramm
Pi
Bladder
Earth
Da zhuang
Guan
5–7 hours
Mao
Large Intestine
Kidney
You
17–19 hours
Tai
Bo
Lung
Lin
Fu
Kun
Pericar-dium
Yin
Xu
Liver
Triple Burner
3–5 hours
Gall Bladder
19–21 hours
Chou
Hai
Zi
1–3 hours
21–23 hours
23–1 hours
Man
Midnight

Fig. 1.8 Expanded Organ clock

Second circulation of the Nutritive Qi (*ying qi*)

According to chapter 16 of the *Ling Shu*, the Nutritive Qi (*ying qi*), after having circulated through the 12 primary channels, takes a deep pathway of the primary Liver channel, which originates at **LIV-14** (*qimen*), passes the Lungs, the posterior aspect of the neck, the inner nasal passages and reaches **Du-20** (*baihui*), then follows along the *du mai* on the back and the *ren mai* along the midline of the abdomen. At the approximate level of **Ren-22** (*tiantu*) the *ying qi* again reaches the Lung channel, which traverses the supraclavicular fossa (near **ST-12**). Here, a new circulation of the *ying qi* through the 12 primary channels starts at the beginning of the primary LU channel.



Fig. 1.9 First and second circulation of the Nutritive Qi (*ying qi*) with the Middle Burner

1.2 The 12 Primary Channels (*jing zheng*)

1.2.1 Background Information

Synonyms: Meridians, regular channels. '*zheng*' can be translated as 'mainly' (primary channels), but also relates to terms such as 'straight' and 'direct'.

Chinese terms for the channels

Meanings (also → 1.2.4, the six great channels (*liu jing*)

Tai: means greater, highest. The polarised energy (Yang or Yin) develops and reaches the maximum extent of its activity in the *taiyang* and *taiyin* channels. Here, the maximum extent of their respective polarity is reached and begins to fall again.

Shao: means less or younger. The polarised energy (Yang or Yin) is less in the *shaoyang* and *shaoyin* channels than in the *taiyang* or *taiyin* channels.

Ming: means clear, bright, radiant, shining (for more detail see → 1.2.4, the six great channels).

Jue: means 'absolute', 'at the end', 'exhausted', and according to Wiseman also 'inverted'. The polarised energy (Yin) in the *jueyin* channel represents the terminal phase of the Yin; here polarity changes to Yang.

Composition of the channel names

In the Chinese language, the name for each channel comprises

- the nature or **polarity of the energy** (Yin or Yang) that flows in the channel
- the **quality** or **intensity** (*tai*, *shao*, *jue*, *ming*) of the Yin or Yang energy and
- the **extremity** at which the channel originates or terminates.

Thus the Yin or Yang channels that begin or terminate at the hand carry the name of the primary hand channels (***shou*** *jing zheng*). The Yin and Yang channels that terminate or begin at the feet carry the name of the foot primary channels (***zu*** *jing zheng*) (→ Fig. 1.2).

1.2.2 Communication and Connections

Principle of the primary channel system

The 12 primary channels cover the body **bilaterally**. Each channel has its **individual regular course** with a deep, **internal** and a more superficial **external** pathway.

One can distinguish between Yin and Yang channels, which are Interiorly/Exteriorly paired. While each channel is connected with its pertaining *zang* or *fu* Organ, it is also connected with the Organ of its Interiorly/Exteriorly coupled channel.

All hand Yin channels begin in the region of the thorax and flow to the hand. All hand Yang channels start at the hands and travel to the head, where they meet the foot Yang channels. These descend down to the toes, where they meet the foot Yin channels, which ascend to the thorax and there meet the hand Yin channels.

For a better understanding of this model, imagine a person standing with his/her hands raised to the sky. In this position, all **Yin channels are ascending** (a **Yang phenomenon**), while all **Yang channels are descending** (a **Yin phenomenon**) (→ Fig. 1.10).



Fig. 1.10 Ascending and descending primary channels (according to Pirog 1996)

Each channel is associated with its own specific pathological symptoms, which are an important diagnostic tool in clinical practice (for channel-specific pathologies see → chapter 4).

Communication between channels and *zangfu*-Organs

The **connections (anastomoses)** between the channels have the function of allowing communication within the channel system as well as between the channels and the Organ systems. This external/internal (*biao-li*) relationship comprises the following aspects:

Communication from the Interior to the Exterior

- The **internal pathways of the hand Yin channels** connect with their pertaining Organ as well as with their Yin/Yang-paired *fu*-Organ. They flow from the thoracic region to the Exterior and connect with their paired Yang channel at the finger tips or on the hand (→ Fig. 1.11 a).
- The **internal pathways of the foot Yang channels** connect with their pertaining *fu*-Organ as well as with their Yin/Yang-paired *zang*-Organ. They then flow from the centre of the body to its Exterior and connect with their paired Yin–channel at the foot (→ Fig. 1.11 b).

Communication from the Exterior to the Interior

- **Each hand Yang channel** begins on the hand, runs to the thoracic region, penetrates the thorax and connects in the Interior of the body with its pertaining *fu*-Organ and its Yin/Yang-paired *zang*-Organ (→ Fig. 1.11 c).
- **Each foot Yin channel** starts at the foot, penetrates the abdomen, reaches the Interior of the body and its pertaining *zang*-Organ as well as its Yin/Yang-paired *fu*-Organ (→ Fig. 1.11 d).



Fig. 1.11 Communication Interior → Exterior, hand-Yin channels (a). Communication Interior → Exterior, foot-Yang channels (b). Communication Exterior → Interior, hand-Yang channels (c). Communication Exterior → Interior, foot-Yin channels (d).

Channel circuits

Within the primary channel system we can distinguish three circuits, each circuit comprising four primary channels. The trajectories of two of the channels in one circuit are located on the Yin side of the body, the more anterior side (Interior), and two are found on the Yang side, the more posterior side of the body (Exterior). The Stomach channel (foot *yangming*, for more detail ➞ 1.2.3) presents the exception to this rule. Despite its major part running along the anterior side of the body, it is considered a Yang channel (➞ Fig. 1.12 and 1.3).


Head
taiyang
shaoyang
yangming
taiyang
shaoyang
yangming
Thorax
L.I.
T.B.
S.I.
LU
P
HE
Hand
taiyin
jueyin
shaoyin
Yang channels
Yin channels
ST
SP
G.B.
LIV
BL
KID
Foot

Fig. 1.12 Principle of the channel circuits

		First circuit			
Channel	**Time**	**Starts**	**Terminates**	**Hand/foot**	
LU	3–5 a.m.	Thorax	Finger tips	Hand (*shou*)	*taiyin*
L.I.	5–7 a.m.	Finger tips	Face	Hand (*shou*)	*yangming*
ST	7–9 a.m.	Face	Tips of the toes	Foot (*zu*)	*yangming*
SP	9–11 a.m.	Tips of the toes	Thorax (Heart)	Foot (*zu*)	*taiyin*
		Second circuit			
H	11 a.m.–1 p.m.	Thorax	Finger tips	Hand (*shou*)	*shaoyin*
S.I.	1–3 p.m.	Finger tips	Face	Hand (*shou*)	*taiyang*
BL	3–5 p.m.	Face	Tips of the toes	Foot (*zu*)	*taiyang*
KID	5–7 p.m	Tips of the toes	Thorax (Pericardium)	Foot (*zu*)	*shaoyin*
		Third circuit			
P	7–9 p.m.	Thorax	Finger tips	Hand (*shou*)	*jueyin*
T.B.	9–11 p.m.	Finger tips	Face	Hand (*shou*)	*shaoyang*
G.B.	11 p.m.–1 a.m.	Face	Tips of the toes	Foot (*zu*)	*shaoyang*
LIV	1–3 a.m.	Tips of the toes	Thorax (Lung)	Foot (*zu*)	*jueyin*



Fig. 1.13 Overview of the channel circuits

Connections among the primary channels

In order to ensure the continuous circulation (also see → 1.1.4) within the primary channel system, there need to be connections among the individual primary channels. Fig. 1.5 illustrates these in a schematic graphic overview.

According to some schools, the connections among the primary channels are facilitated by so-called entry/exit points. Various authors (for example Worsley, Jarrett, Pirog, Hicks et al., for more detail → 8.1.16) describe these as the shunting points between successive channels according to the Organ clock. The exit point marks the point on a channel from which the (internal) flow moves to a point (the entry point) on the channel that succeeds it on the Organ clock. There are some discrepancies regarding the location of the connections as described by the above authors and those described by Solinas et al. (1998), which are marked below as appropriate.

Yin–Yang connections

The connections – anastomoses – between the Yin and Yang channels are located on the hands and feet. The channels are most commonly connected at their respective final points, but sometimes also by branches separating from the main channel. These Yin–Yang connections are places where the Qi can change its polarity: Yin Qi becomes Yang Qi, and Yang Qi becomes Yin Qi. This creates a dynamic balance and allows for a better circulation of the Qi. The Yin–Yang connections follow the order of the basic structure of the circadian rhythm (24-hour cycle).

Hand Yin–Yang connections (→ Fig. 1.14)

The **hand Yin channels** are in most cases connected to the **hand Yang channels** at the tips of the fingers; sometimes they are connected on the hand by a branch that separates from the primary Yin channel and runs to the hand Yang channel:

First circuit

LU channel (*shou taiyin*) ➡ L.I. channel (*shou yangming*)
LU-7 (*lieque*) ➡ **L.I.-1** (*shangyang*)

A branch separates from the primary LU channel at → **LU-7** (*lieque*) and travels to the primary L.I. channel at → **L.I.-1** (*shangyang*).

Note: According to Hicks et al. (2004, → 8.1.16) **L.I.-4** (*hegu*) is considered to be an entry point.

Second circuit

HE channel (*shou shaoyin*) ➡ S.I. channel (*shou taiyang*)
HE-9 (*shaoyang*) ➡ **S.I.-1** (*shaoze*)

Third circuit

P channel (*shou jueyin*) ➡ T.B. channel (*shou shaoyang*)
P-8 (*laogong*) ➡ **T.B.-1** (*guanchong*)


LU-7
P-8
HE-9
T.B.-1
L.I.-1
S.I.-1
L.I.-4
LU-7
First circuit
L.I.-1
L.I.-4
(variant)
HE-9
Second circuit
S.I.-1
P-8
Third circuit
T.B.-1

Fig. 1.14 Hand Yin–Yang connections (primary channels)


ST-42
G.B.-41
BL-67
LIV-1
SP-1
KID-1
ST-42
First circuit
SP-1
BL-67
Second circuit
KID-1
G.B.-41
Third circuit
LIV-1

Fig. 1.15 Foot Yang–Yin connections (primary channels)

Foot Yang–Yin connections (→ Fig. 1.15)

The **foot Yang channels** are connected to the **foot Yin channels** at the toes by branches that separate from the primary Yang channels and run to the foot Yin channels (→ Fig. 1.15):

First circuit

ST channel (*zu yangming*) ➡ SP channel (*zu taiyin*)

ST-42 (*chongyang*) ➡ **SP-1** (*yinbai*)

At → **ST-42** a branch separates from the primary ST channel and travels to → **SP-1**.

Second circuit

BL channel (*zu taiyang*) ➡ KID channel (*zu shaoyin*)

BL-67 (*zhiyin*) ➡ **KID-1** (*yongquan*)

Third circuit

G.B. channel (*zu shaoyang*) ➡ LIV channel (*zu jueyin*)

G.B.-41 (*zulinqi*) ➡ **LIV-1** (*dadun*)

On the instep of the foot, at → **G.B.-41**, a branch separates from the G.B. channel and travels to → **LIV-1**

Yang–Yang connections (→ Fig. 1.16)

The Yang–Yang connections between the primary channels are located on the **head**. They are rather superficial and follow the order of the channels within the **circadian cycle** (according to the Organ clock → Fig. 1.7). These connections support the communication between the hand Yang and foot Yang primary channels in the cranial region, which convey Qi of the same nature and quality (*yangming*, *taiyang*, *shaoyang*). They also mark the connections between the Yang axes, also referred to as hand–foot pairing (→ 1.2.3), and serve as a link between **above** and **below**.

First circuit

L.I. channel (*shou yangming*) ➡ ST channel (*zu yangming*)

L.I.-20 (*yingxiang*) ➡ **ST-1** (*chengqi*)

Second circuit

S.I. channel (*shou taiyang*) ➡ BL channel (*zu taiyang*)

S.I.-18 (*quanliao*) ➡ **BL-1** (*yingming*)

Third circuit

T.B. channel (*shou shaoyang*) ➡ G.B. channel (*zu shaoyang*)

T.B.-23 (*sizhukong*) ➡ **G.B.-1** (*tongziliao*). Comment: according to Hicks et al. (2004, → entry/exit points, → 8.1.16) **T.B.-22** (*erheliao*) is considered an exit point.


T.B.-22
(variant)
T.B.-23 BL-1
G.B.-1
ST-1
S.I.-18 L.I.-20
L.I.-20
First circuit
(BL-1)
ST-1
S.I.-18
Second circuit
BL-1
T.B.-23
T.B.-22
(variant)
Third circuit
G.B.-1

Fig. 1.16 Yang–Yang connections of the primary channels

Yin–Yin connections

The Yin–Yin connections between the primary channels are located in the **thoracic region** (Fig. 1.17).

In contrast to the more superficial Yang–Yang connections, they are located deep inside the body (internal pathways of the channels).

There are two types of Yin–Yin connection:

- the Yin axes connections or hand–foot pairings (*taiyin*, *jueyin*, *shaoyin*), which are **non-circadian** (do not flow according to the Organ clock) and
- the (deep) Yin–Yin connections, whose Qi flow follows the circadian rhythm of the Organ clock.


Thorax
Yin
Yang
LU (*shou taiyin*)
Metal
L.I. (*shou yangming*)
First circuit
SP (*zu taiyin*)
Earth
ST (*zu yangming*)
HE (*shou shaoyin*)
Fire
S.I. (*shou taiyang*)
Second circuit
KID (*zu shaoyin*)
Water
BL (*zu taiyang*)
P (*shou jueyin*)
Fire
T.B. (*shou shaoyang*)
Third circuit
LIV (*zu jueyin*)
Wood
G.B. (*zu shaoyang*)
Yin axes connections/hand–foot pairings
Deep Yin–Yin connections
shou = hand
zu = foot

Fig. 1.17 Overview of the Yin–Yin connections (primary channels)

Connections of the Yin axes (hand–foot pairings)

These Yin–Yin connections support the communication between the hand Yin and the foot Yin channels, which convey Qi of the same quality (*taiyin*, *jueyin*, *shaoyin*) and serve as a link between **above** and **below**. Their Qi flow does **not follow the circadian rhythm** of the Organ clock (→ Fig. 1.17).

FIRST CIRCUIT

SP channel (*zu taiyin*) ➡ LU channel (*shou taiyin*)

SP-20 (*zhourong*) ➡ **LU-1** (*zhongfu*)

According to Solinas et al. (1998), a superficial branch separates from the primary SP channel at → **SP-20** and travels to the primary LU channel at → **LU-1**.

SECOND CIRCUIT

LIV channel (*zu jueyin*) ➡ P channel (*shou jueyin*)

LIV ➡ P

An internal branch ascends from the Liver, passes through the diaphragm, connects with the primary P channel below → **P-1** (*tianchi*).

THIRD CIRCUIT

KID channel (*zu shaoyin*) ➡ HE channel (*shou shaoyin*)

KID ➡ HE

An internal branch of the primary KID channel runs to the Liver, penetrates the diaphragm and spreads into the Lungs. From the

Lung a branch travels to the Heart, where it connects with the primary HE channel.

Many authors give **HE-1** (*jiquan*) as the site of connection.

Deep Yin–Yin connections

These Yin–Yin connections facilitate the **circadian cycle** according to the Organ clock and mark the transitions of the channel circuits. They are located deep in the thorax area on the level of the *zang*-Organs.

Connection of the first and second circuit

SP channel (*zu taiyin*) ➡ HE channel (*shou shaoyin*)

SP ➡ HE

An internal branch of the primary SP channel spreads in the Heart and connects with the HE channel. Note: according to Hicks et al. (2004, → entry/exit points, → 8.1.16) **SP-21** is considered to be the exit point of the SP channel and **HE-1** the entry point of the HE channel.

Connection of the second and third circuit

KID channel (*zu shaoyin*) ➡ P channel (*shou jueyin*)

KID ➡ P

An internal branch of the primary KID channel travels to the Kidneys, then to the Liver, penetrates the diaphragm and spreads into the Lung. From the Lung, an internal branch runs to the Heart, where it meets the primary P channel and also reaches → **Ren-17** (*shanzhong/danzhong*). Note: according to Hicks et al. (2004, → entry/exit points → 8.1.16) **KID-22** is considered to be the exit point of the KID channel and **P-1** the entry point of the P channel.

Connection of the third and first circuit

LIV channel (*zu jueyin*) ➡ LU channel (*shou taiyin*)

LIV ➡ P

An internal branch of the LIV channel originates in the Liver, passes the diaphragm, spreads in the Lungs and connects with the LU channel through a network of branches. Note: according to Hicks et al. (2004, → entry/exit points → 8.1.16) **LIV-14** is considered to be the exit point of the LIV channel and **LU-1** the entry point of the LU channel.

1.2.3 The Six Great Channels (*liu jing*)

Based on the Yang–Yang and Yin–Yin connections (→ 1.2.2, → Fig. 1.16, → Fig. 1.17), primary channels of the same nature and quality can be divided into **six great channels** (*liu jing*) or **hand–foot pairings (or axes).** They represent the three great Yang channels and the three great Yin channels.

Channels	**Trajectory**		**Amount of Qi and Blood**
Exterior			
Yang channels (hand–foot pairings)			
taiyang **(S.I., BL)**	Latero-posterior aspect of the four extremities, posterior aspect of the head and body	 Interior Yin Exterior Yang Anterior LU + SP *taiyin* L.I. + ST *yangming* Middle P + LIV *jueyin* T.B. + G.B. *shaoyang* Posterior HE + KID *shaoyin* S.I. + BL *taiyang* a	Less Qi, more Blood **Qi < Blood**
shaoyang **(T.B., G.B.)**	Lateral aspect of the four extremities and torso	 Interior Yin Exterior Yang Anterior LU + SP *taiyin* L.I. + ST *yangming* Middle P + LIV *jueyin* T.B. + G.B. *shaoyang* Posterior HE + KID *shaoyin* S.I. + BL *taiyang* b	More Qi, less Blood **Qi > Blood**

Fig. 1.18 Overview of the six great channels (*liu jing*)

Yang channels (hand–foot pairings)			
yangming **(ST, L.I.)**	Latero-anterior aspect of the four extremities, frontal aspect of the head (face, forehead), anterior aspect of the trunk	 Interior Yin Exterior Yang Anterior LU + SP taiyin L.I. + ST yangming Middle P + LIV jueyin T.B. + G.B. shaoyang Posterior HE + KID shaoyin S.I. + BL taiyang c	More Qi, more Blood **Qi = Blood**
Yin channels (hand–foot pairings)			
taiyin **(LU, SP)**	Medio-anterior aspect of the four extremities as well as the thorax and abdomen	 Interior Yin Exterior Yang Anterior LU + SP taiyin L.I. + ST yangming Middle P + LIV jueyin T.B. + G.B. shaoyang Posterior HE + KID shaoyin S.I. + BL taiyang d	More Qi, less Blood **Qi > Blood**
jueyin **(P, LIV)**	Middle of the medial aspect of the four extremities as well as the thorax and abdomen	 Interior Yin Exterior Yang Anterior LU + SP taiyin L.I. + ST yangming Middle P + LIV jueyin T.B. + G.B. shaoyang Posterior HE + KID shaoyin S.I. + BL taiyang e	Less Qi, more Blood **Qi < Blood**
shaoyin **(HE, KID)**	Medio-anterior aspect of the four extremities as well as the thorax and abdomen	 Interior Yin Exterior Yang Anterior LU + SP taiyin L.I. + ST yangming Middle P + LIV jueyin T.B. + G.B. shaoyang Posterior HE + KID shaoyin S.I. + BL taiyang f	More Qi, less Blood **Qi > Blood**
Interior			

Fig. 1.18 (cont'd) Overview of the six great channels (*liu jing*)

Names and functions of the six great channels (*liu jing*)

Tai means 'greater', 'highest'

The polarised energy (Yang or Yin) develops and reaches its maximum activity in the *taiyang* or *taiyin* channels. Here, **the maximum level of the respective polarity** is reached and begins to fall again. '*Taiyang* opens to the outside' means that it spreads to the Exterior (→ see comments below under *yangming*, also → Fig. 1.19).

Shao means 'less' or 'younger'

The polarised energy (Yang or Yin) is less in the *shaoyang* or *shaoyin* channels than in the *taiyang* or *taiyin* channels. This also manifests in their location: the *shaoyang* channels are located midway between the **inside** (or anterior aspect) and the **outside** (or posterior aspect) of the body, acting like a hinge. According to Larre and Rochat de la Vallée (1986), *shaoyang* should be translated as 'young Yang'. In their view it is positioned between the outside (the other two Yang channels) and the inside (the other three Yin channels).

Depending on the interpretation, the *shaoyin* channels are considered either to be located between the *taiyin* and the *jueyin* channels or to be the deepest of the six channels. Thus they are either seen as a hinge or as a fixed central point (for more detail see → Depth organisation of the channels).

Ming means 'clear', 'bright', 'radiant', 'shining'

'*Yangming* closes towards the inside – *yangming* contracts towards the inside.'

The *yangming* channel has some unique features. Based on its course alone, it is **not 'Yang'** like the other two Yang channels, but it develops as a Yang phenomenon within the Yin aspect of the body (partially anterior pathway of the ST channel).

The character for *ming* is composed of the radicals for the sun and the moon. The character for Yang also contains the sun radical. According to the *Su Wen*, the *yangming* is where the two Yang shine together. Thus, the two suns can be symbolically interpreted as a doubling of Yang energy. *Taiyang* and *shaoyang* are 'Yang' simply due to their physical location. *Yangming*, however, is 'Yang' due to the content of its stored energy. This raises the question as to why the *yangming* channel is so abundant, why it carries so much Qi and Blood. Pirog (1996) explains this fact based on embryonic development. The 'closing' of the *yangming*' can be equated with the image of a curled-up **embryo** (→ Fig. 1.19). Because of its contracting, 'closing' position, the energy of the *yangming* channel can be compared to the compressed energy in a pressure cooker. Thus the 'Yin' process of contracting towards the Interior results in producing Yang or, in other words, compression of the energy in the Interior. This naturally compressed energy is utilised in clinical practice. The *yangming* channels, but especially the ST channel, can be accessed, either by massage or by acupuncture, to supply the whole body with the energy stored and accumulated here. By the same token, the *yangming* channels can be needled in order to drain excess Heat – a procedure comparable to a controlled release of steam from a pressure cooker.

Jue means 'absolute', 'at the end', 'exhausted' (also, according to Wiseman, 'to revert')

The polarised energy (Yin) in the *jueyin* channel represents the terminal phase of the Yin; here polarity changes to Yang (→ see below for more detail).



Fig. 1.19 Embryonic development of the *yangming* and *taiyang* channels (according to Pirog 1996)

The six great channels (*liu jing*): relationships and depth organisation

The systemic division of the channels into six levels or stages is mainly associated with the *Shang Han Lun*, a herbal classic. But according to Pirog (1996), this system can also be used as a paradigm for acupuncture, since it provides fundamental ideas regarding the functions of the points and channels as well as the relationships among the channels. It focuses particularly on changes of characteristics of the channel Qi, depending on which level it is acting within the body. The channels can be described as being stacked one upon each other, similar to layered rocks in a quarry. The depth of a channel or a point will be indicative of its function and significance. The postulate is that the more deeply a channel is located in the body, the more deep-seated its functions are and the more deep-seated illnesses it will be able to treat. They are not static, however. Depending on their location in the human body, they are indeed living structures with specific activities such as openers, closers, hinges or pivots, reflected in the meaning of the Chinese names. Fig 1.20 illustrates the arrangement of the six great channels from the outside to the inside, resembling the layers of an onion (→ Fig. 1.20).

Nguyen Van Nghi (1996) compares the three Yin and three Yang channels to doors. The door (*taiyang* or *taiyin*) is closed to prevent the entry of unwelcome guests such as external pathogenic factors. But the door can also be opened to let in friends. Whether the door opens and closes well depends largely on the hinges (*shaoyang*, *shaoyin*). Only if the hinges function smoothly can the energy circulate adequately. The doorframe (or closing mechanism) (*yangming*, *jueyin*) closes towards the Interior; in other words, it protects and supports what is contained on the inside. (➞ Fig. 1.21).


Exterior
Yang channels
taiyang (S.I./BL)
shaoyang (T.B/G.B.)
yangming (L.I./ST)
taiyin (LU/SP)
jueyin (P/LIV)
shaoyin (HE/KID)
Interior
Yin channels
Yang channel
Yin channel
Deep Yin–Yin connection (Circadian)

Fig. 1.20 Relationships of the three Yin and three Yang channels (according to Nguyen Van Nghi, 1996)


Taiyang opens to the outside
Yangming closes towards the inside to the Yin channels
shaoyang (Hinge)
taiyang (Opener)
yangming (Closer)
shaoyang (Hinge)
a
Taiyin opens toward the outside to the Yang channels
Jueyin closes towards the inside to the Yin
shaoyin (Hinge/Pivot)
taiyin (Opener)
jueyin (Closer)
shaoyin (Hinge/Pivot)
b

Fig. 1.21 The six great channels as opener, hinge and frame of a door

The literature is somewhat contradictory about which are the deeper of the six great channels, the *shaoyin* or the *jueyin* channels. Pirog (1996) has contributed an interesting theory in suggesting that the *shaoyin* channels occupy the deepest position in the body. They are located in such a medial location (near the middle of the body) that, when a person is standing in a normal position, the *shaoyin* channels are covered and not directly visible. According to Pirog, the *shaoyin* does not function like a hinge, but rather like a fixed pivot, similar to the axis of a mill wheel, which itself is immobile, but is able to cause movement. When the Qi has reached the deepest point of the *shaoyin*, and the 'Yin of the *jueyin* is exhausted', it has to revert. In other words: it has to return to a more superficial level on the outside or it has to transform into Yang. In that sense, it is the P and LIV channels that again start the flow of the Qi towards the Yang, from the inside to the outside and from below to above (➞ Fig. 1.22).


Exterior
Yang channels
taiyang (S.I./BL)
Opener
shaoyang (T.B./G.B.)
Hinge
yangming (L.I./ST)
Closer
taiyin (LU/SP)
Opener
jueyin (P/LIV)
Closer
shaoyin (HE/KID)
Hinge/Pivot
Interior
Yin channels
Yang channel
Yin channel

Fig. 1.22 Depth organisation of the six great channels (according to Pirog, 1996)


LU-2
Jugulum
1 cun
Midline
LU 1
1cun
P-1
4. ICR
HE-1
BL-1
G.B.-1
Orbital margin
ST-1
(below
the pupil)

Fig. 1.23 Confluent points of the six great channels

Confluent or connecting points of the six great channels (*liu jing*)

The **primary Yin channels** (*liu jing*) connect in the **thoracic region** (see also ➞ Yin axes or hand–foot pairings ➞ 1.2.2, Fig. 1.17). In contrast, the **primary Yang channels** connect in the **cranial region** (see also ➞ Yang axes or hand–foot pairings ➞ 1.2.2, Fig. 1.16). Many schools of thought suggest the connections of the channels of the same nature and quality at the following **six confluent points**:

Yin channels	**LU-1** (*zhongfu*), **P-1** (*tianchi*), **H-1** (*jiquan*)
Yang channels	**BL-1** (*jingming*), **G.B.-1** (*tongziliao*), **ST-1** (*chengqi*)

Starting and end points of the six great channels (*liu jing*)

Fig. 1.24 shows the starting and end points of the six great channels on the feet or hands respectively.


L.I.-1
T.B.-1
S.I.-1
LU-11
P-9
HE-9
Great Yang channels
L.I.-1
T.B.-1
S.I.-1
ST-45
G.B.-44
BL-67
taiyang
shaoyang
yangming
Great Yin channels
P-9
HE-9
LU-11
SP-1
LIV-1
KID-1
shaoyin
jueyin
taiyin
ST-45
G.B.-44
BL-67
SP-1
LIV-1
KID-1

Fig. 1.24 Starting and end points of the *jiu jing*

Root points and binding points of the six great channels (*liu jing*)

According to Chapter 5 of the *Ling Shu*, each of the six great channels (*liu jing*) has a root point (*gen*) and a binding point (*jie*).

Root points (*gen*)

At the root point, the polarised energy (Yin/Yang) of a great channel is at its minimum – this point marks the end of the Yang or the beginning of the Yin. The root points are all located on the foot (→ Fig. 1.24).

Root points of the three Yang channels (→ Fig. 1.24)

These always represent the **terminal point** of each great **Yang** channel.

taiyang (S.I. → BL)	**BL-67** (*zhiyin*)
shaoyang (T.B. → G.B.)	**G.B.-44** (*zuqiaoyin*)
yangming (L.I. → ST)	**ST-45** (*lidui*)

Root points of the three Yin channels (→ Fig. 1.24)

These always represent the **first point** of each great **Yin** channel.

taiying (SP → LU)	**SP-1** (*yinbai*)
jueyin (LIV → P)	**LIV-1** (*dadun*)
shaoyin (KID → H)	**KID-1** (*yongquan*)

Binding points (*jie*)

The binding point is the point at which the polarised energy (Yin/Yang) of a great channel reaches its maximum level. It is at this point that the hand channel and the foot channel are connected.

Binding points of the three Yang channels

These are the **switching points** of the great Yang channels (hand to foot) and are located in the **cranial region**.

taiyang (BL ➡ S.I.)	**BL-1** (*jingming*)
shaoyang (G.B. ➡ T.B.)	**T.B.-21** (*ermen*)*
yangming (ST ➡ L.I.)	**ST-1** (*chengqi*)**

Binding points of the three Yin channels

These are the **switching points** of the great Yin channels (foot to hand) and are located in the **thoracic or abdominal region**.

taiying (SP ➡ LU)	**Ren-12** (*zhongwan*)
jueyin (LIV ➡ P)	**Ren-18** (*yutang*)
shaoyin (KID ➡ H)	**Ren-23** (*lianqian*)

1.3 Divergent Channels (*jing bie*)

Synonyms: Channel divergence (Wiseman), separate pathways (Larre and Rochat de la Vallée).
Character: *bie* means diverging, separating, branching off. In this sense, the 12 divergent channels can be seen as branches of the primary channels.

General pathways of the divergent channels (➞ Fig. 1.25)

The 12 bilateral divergent channels, which have no specific points of their own, are named after and are dependent on their corresponding primary channel.
They can be divided into **six great Yin and six great Yang pairs** and have their own system of six confluences (reunions): BL/KID, G.B./LIV, ST/SP, S.I./H, T.B./P, L.I./LU. According to Ramakers (course material, 2003) the divergent channels follow their own (non-cosmic) daily biorhythm:
BL ➡ G.B. ➡ ST ➡ S.I. ➡ T.B. ➡ L.I. ➡ KID ➡ LIV ➡ SP ➡ H ➡ P ➡ LU.
All divergent channels separate (*li*) from their corresponding primary channel on the extremities, except for the divergent T.B. channel, which branches off on the head. But many authors suspect that their pathways begin before the actual branching off. Based on this assumption, the divergent channels begin at the distal ends of the primary channels, running parallel to them, but as separate entities. The circulation in the divergent channels is of a centripetal nature (➞ 1.1.1); in other words, the flow is always from a distal in a proximal direction, towards the trunk and the head. After separating from the primary channels, they enter deeper (*ru*) into the body and, after completing their internal pathway, they re-emerge close to the surface of the body (*chu*). The divergent channel pairs (Yin/Yang) pass together through the Interior of the body to join (*he*) their pertaining primary Yang channel in the occipital or cranial region. It is this joining of the courses that is referred to as the six confluences (or reunions) (*liu he*).

Pathways of the divergent Yin channels

After separating from their primary channels, they connect with their pertaining *zang*-Organ, then with the Interiorly-Exteriorly paired *fu*-Organ. They continue their flow in the upper half of the body together with their paired divergent Yang channel to join the paired primary Yang channel. In contrast to the divergent Yang channels, the divergent Yin channels will not return to their pertaining primary Yin channel after having completed their internal pathway (➞ Fig. 1.25).

Pathways of the divergent Yang channels

After separating from their primary channels, the divergent Yang channels travel to their pertaining *fu*-Organ, then to the Interiorly-Exteriorly paired *zang*-Organ. They connect again with their pertaining primary channel and also with their Interiorly-Exteriorly paired divergent Yin channel in the upper half of the body (➞ Fig. 1.25).

The divergent channels and the Heart

All divergent channels pass the thoracic region and the Heart, except for the divergent channels of the LU, L.I. and KID. According to Shima and Chase (2001), this means that all divergent channels passing the thorax will communicate with the True Qi (*zhen qi*), representing the synthesis of the Gathering Qi (*zong qi*) and Original Qi (*yuan qi*) (➞ 1.1.4). They suggest that this hypothesis is in accordance with all the information available about the divergent channels, and explains furthermore why the divergent channels are so useful in the treatment of deep-seated Organ disorders as well as for disharmonies of the Defensive Qi (*wei qi*). It supports the image of a divergent channel as a fundamental axis between the Interior and the Exterior of the body. In the opinion of Shima and Chase (2001), the divergent channels are an invaluable connection to facilitate the return of the Defensive Qi (*wei qi*) to the Interior of the body and to transfer the fundamental inner Original Qi (*yuan qi*) to the periphery. In that respect the Original Yang (*yuan yang*) not only touches upon, but also strengthens the Defensive Yang (*wei-yang*).

---

* According to Nguyen Van Nghi (1996) and Solinas et al. (1998), this is G.B.-2 (*tinghui*)

** According to Nguyen Van Nghi (1996) and Solinas et al. (1998), this is ST-8 (*touwei*)



Fig. 1.25 Schematic illustration of the divergent channel pathways (according to Shima and Chase 2001)

Functions

The divergent channels reinforce the circulation of and communication between the primary channels in the Interior of the body. On the one hand, this is achieved due to their connection with the primary Yang channels (➞ pathways). But their organisational structure also supplements the primary channels in a functional way – for example they also control areas of the body not covered by the primary channels. Thus points on the primary Yin channels can affect the head and face, in spite of their 'external' pathways ending in the thoracic region. This effect can be explained by the fact that the Yin divergent channels, after branching off from their pertaining primary Yin channel, pour into the Yang divergent channels flowing to the head. A deeper understanding of the trajectory and functions of the divergent channels will in turn lead to a better understanding of the clinical application of some commonly used acupuncture points. Since their pathway passes the Heart and thorax, the divergent channels further strengthen the connection to the Heart (➞ explanations above). According to some schools, they can therefore also be used for the treatment of psychosomatic disorders. Many interpretations and variants exist regarding the pathways and clinical application of the divergent channels (for a good overview see ➞ Shima and Chase 2001).

1.4 The 12 Sinew Channels (*jing jin*)

Synonyms and translations: muscle channels, muscular meridians/the muscles in connection with the meridians (Larre and Rochat de la Vallée), muscle regions, channel sinews.

Principles of the sinew channel system

The sinew channels mainly represent the muscles, sinews and ligaments located along the pathways of the primary channels and their pertaining connecting vessels. They do not have their own specific points and also no direct connection to the *zangfu*-Organs. The 12 bilateral sinew channels are connected to and named after their pertaining primary channel. Each sinew channel has its own pathway, which generally follows the trajectory of its pertaining primary channel. However, in contrast to the primary channels, the sinew channels always begin at the extremities, mostly separating from the primary channels at the *jing*-well points (➞ 8.1.6) on the tips of the fingers and the toes. Their pathways always run from the extremities to the trunk or further to the head and face (➞ centripetal circulation ➞ 1.1.1). They cover a larger area than the primary channels, in the shape of a band and binding (*jie*) like a spindle at the joints and other areas of the body. This allows them to cover areas of the body which are not reached by the primary channels or the divergent channels. It further explains the actions of some of the points located on their pertaining primary channel. Under pathological conditions, the sinew channels will manifest as so-called *ashi*-points (*a shi xue*) or as trigger points.

Terms

Binding (*jie*) refers to spindle-shaped concentrations of the sinew channels, which tend to be located on the bigger muscles and joints (for more details on specific sinew channels see ➞ Chapter 4).

The term *ju* (point of confluence, gathering) is used to signify an area where two or more sinew channels are bundled together. In the larger muscles, the Qi disperses or spreads (*san*), so that they can be divided into smaller muscle groups. The sinew channels connect (*luo*) the muscles, sinews and ligaments with the joints in order to facilitate mobility.

Rhythm of Qi flow

According to Ramakers (course material, 2003) the sinew channels are subject to their own daily rhythm of Qi flow:

BL ➡ G.B. ➡ ST ➡ S.I. ➡ T.B. ➡ L.I. ➡ SP ➡ LU ➡ LIV ➡ P ➡ KID ➡ HE.

General pathways of the sinew channels (→ Fig. 1.26)

- The three hand Yang sinew channels (L.I./S.I./T.B.) flow from the finger tips towards the scapula, ascend to the ear and intersect with **G.B.-13** (*benshen*)
- The three foot Yang sinew channels (ST/BL/G.B.) run from the tips of the toes towards the head, join each other on the cheek and meet with **S.I.-18** (*quanliao*)
- The three hand Yin sinew channels (HE/P/LU) flow from the finger tips towards the thorax, joining within the thoracic musculature and meeting at **G.B.-22** (*yuanye*)
- The three foot Yin sinew channels (LIV/KID/SP) run from the tips of the feet towards the thorax, join each other in the genital region and, depending on the author, intersect in the area of **Ren-2** (*qugu*) or **Ren-3** (*zhongji*)



Fig. 1.26 Meeting points of the sinew channels

Functions

The main function of the sinew channels is to distribute Qi and Blood (*xue*) over the surface of the body as well as to integrate the muscles, sinews and ligaments with the joints. Generally, the sinew channels join groups of synergistic muscles, supporting their mobility and natural movement while also serving the function of integrating the surface of the body. At the same time they protect the bones and skeletal structure, linking the structures of the body.

Proper functioning of the muscles is dependent on the Spleen (*pi*) and the Liver (*gan*) and particularly on their Blood (*xue*). While the Yin (or material) aspect of the musculature, the 'flesh', is governed by the nourishing function of the Spleen, the functioning of the muscles and sinews is governed by the Liver. But the Liver is also connected to the mesenchymal structures of the body, especially those surrounding the organs. The sinew channels are not only composed of the muscular structures, but also of the mesenchymal formations, so that according to Larre and Rochat de la Vallée they are also involved in the structural aspect of the diaphragm as well as the thoracoabdominal serous membranes, in particular the pleura, peritoneum and pericardium. In the deeper parts of the body they act through the deep muscular fascia. One of the main functions of the sinew channels is that of a 'protective coat' that shields the body against attacks from the Exterior. In this respect the Defensive Qi (*wei qi*) is of particular importance ((→ 1.1.4): the muscle spindles are crossed by loose and diffuse flows of Qi, which also contain Defensive Qi (*wei qi*). Nutritive Qi (*ying qi*) is also present, particularly at the outer ends of the spindles (→ 1.1.4).

The sinew channels also have the task of barring access to the deeper channels. In other words, in a pathological situation, a deeper channel can only be reached if the resistance of the muscular layers can be broken. An important aim of Tuina therapy is to remove muscular tension. According to Larre and Rochat de la Vallée (1996), the sinew channels also play a role in psychosomatic disorders since they very effectively constitute the muscular carapace. The authors refer here to a bioenergetic interpretation of muscular tension.

Clinical and therapeutic importance

Disorders of the sinew channels will show the following symptoms along their pathway: muscular tension, pain, cramping, spasms, stiffness, but also paralyses, weakness and swellings of the muscles, tendons and ligaments. Any impairment of range of motion of the joints also indicates that the sinew channels are involved. In addition, each sinew channel also has its specific symptoms (→ chapter 4, individual channel descriptions).

The following factors can contribute to disorders of the sinew channels:

- *Bi* syndromes – external invasion of pathogenic Wind, Cold, Damp or Heat
- Traumatic injuries
- Muscle strain through over-use
- Muscle strain and contraction due to longstanding emotional and mental stress

While the sinew channels do not have their own specific points, they can easily be accessed by needling *ashi*-points, as well as through adjunctive therapies such as cupping, Tuina massage, plum blossom needling, moxibustion and *gua sha* (scraping technique). Distal points can also be used in treating disorders of the sinew channels.

For traumatic injuries with limited range of motion, needling of distal points with simultaneous movement of the affected joint has proven to be very effective. The distal points (→ 8.2.1) can be chosen by first determining the affected area, then needling points in the corresponding area on the contralateral side.

For example, for a knee injury, the exact location of the pain is determined, then the corresponding point or area on the contralateral elbow is needled or massaged. Fig. 1.27 illustrates the areas that have been found to be effective. These areas are also referred to as reciprocal areas (for more detail also see → 8.2, 8.3).



Fig. 1.27 Corresponding areas of the body

1.5 *Luo*-Connecting Vessels

Synonyms: secondary pathways (Larre and Rochat de la Vallée), network vessels, collaterals

Organisation

The *luo*-connecting vessels can be divided into 15/16 great *luo*-connecting vessels as well as into many smaller and more superficial *luo*-connecting vessels. Looking at the *luo*-connecting vessels altogether, they form a network that spans the entire body. And all *luo*-connecting vessels in turn connect with the great *luo*-connecting vessel of the Spleen (at → **SP-21**), which plays a major role within the network of the *luo*-connecting vessels (*Ling Shu*, Chapter 10). Together with the primary channel system, they form a network of vessels which distribute Qi and Blood not only within the body, but also to its surface (→ Fig. 1.3, 1.4).

The 16 great *luo*-connecting vessels

Traditionally there are 15 *luo*-connecting vessels, but if one includes the great *luo*-connecting vessel of the Stomach (*wei zhi da luo* or *xu li*), it raises the number to 16:

- 12 *luo*-connecting vessels (*luo mai*), related to the 12 primary channels and beginning at the extremities
- 4 *luo*-connecting vessels beginning at the thorax:
  - 2 *luo*-connecting vessels of the *ren mai* and *du mai*
  - 1 great *luo*-connecting vessel of the Spleen
  - 1 great *luo*-connecting vessel of the Stomach.

Except for the Great *luo*-connecting vessel of the Stomach (*xu li*) which originates in a *fu*-Organ, all other 15 *luo*-connecting vessels emerge at a specific point on their pertaining primary channel, the *luo*-connecting point (→ 8.1.2). 13 *luo*-connecting points are located on primary channels, two on extraordinary vessels (*ren mai* and *du mai*). The *luo*-connecting points are located on areas of the body, where the *luo*-connecting vessels that connect the Interiorly-Exteriorly pertaining channels with each other divide into smaller vessels. The 15/16 *luo*-connecting vessels thus fulfil a controlling function over all the other, smaller *luo*-connecting vessels. Each *luo*-connecting vessel has its own pathology according to its pertaining primary channel (→ introductions to the primary channels → Chapters 4 and 5).

Superficial *luo*-connecting vessels

The smaller superficial *luo*-connecting vessels are sub-branches of the 'great' *luo*-connecting vessels. They, in turn, are divided into the *sun luo*, vertical branches which are sometimes also referred to as tertiary branches or grandchild-vessels. The *sun luo* not only spread over the surface of the body, but also cover the internal Organs. The *sun luo* further divide into the more superficial *fu luo*. The *fu luo* again divide horizontally into small branches called the *xue luo* (blood vessel network).

Pathogenic factors tend to enter the body through the superficial *luo*-connecting vessels. By the same token, disorders such as Qi or Blood stagnation in a primary channel or an Organ may manifest in the *xue luo* as skin discolorations, spider veins, etc.

Clinical importance

The *luo*-connecting vessels can be accessed through superficial needling techniques as well as skin-sensitising techniques such as plum blossom needling, bloodletting, cupping, *gua sha* and moxibustion.

> New diseases are located in the primary channels; old (chronic) diseases lodge in the *luo*-connecting channels.

1.6 Cutaneous Regions (*pi bu*)

Characteristics

The cutaneous regions form the most superficial aspect or outer cover of the primary channel system (*pi* = skin). According to Ramakers (course material, 2003), they can be compared to a 'big bag that holds everything together' and – besides the extraordinary vessels – they represent the oldest tissue in the body, which developed from the ectoderm. The cutaneous zones are not channels *per se*, but rather areas of skin connected to and covering the network of superficial channels and vessels. They are named after the six great channels (*liu jing* ➞ 1.2.3) (Fig. 1.28).



Fig. 1.28 Cutaneous zones (anterior and posterior aspect)

Functions

The cutaneous zones circulate Blood and Qi, especially Defensive Qi (*wei qi*), to the surface of the body and regulate the skin and pores, thus strengthening the body's defences. Proper functioning depends on the Lung Qi, which governs the skin, and the Defensive Qi (*wei qi*) (➞ 1.1.4). Pathogenic factors can enter and exit the body through the cutaneous zones.

Clinical importance

Disorders of the primary channels and their pertaining *zangfu*-Organs may be reflected on the outside of the body by the cutaneous zones, for example pathological skin sensations, lesions or discolorations may occur. A bluish-greenish discoloration may indicate pain or obstructions, a reddish colour Heat and a pale-whitish colour deficiency or Cold. Therefore, the cutaneous zones can serve as a diagnostic tool for skin disorders or pain, specifically for chronic pain. Treatment techniques include superficial needling, plum blossom needling, cupping, massage, and *gua sha* (Chinese scraping technique). The author had good results in the treatment of chronic pain with the somatopic wrist/ankle acupuncture developed by Dr Zhang Xin Shu (➞ JCM, No. 37,11/1991, ➞ Focks and Hillenbrand 2003). The strictly subcutaneous needling used in this technique influences, of course, the cutaneous zones.

1.7 The Eight Extraordinary Vessels (*qi jing ba mai*)

Synonyms: Extraordinary meridians, Wondrous meridians
Meaning of *qi jing ba mai*:
Qi: extraordinary, strange, not paired, miraculous, wonderful
Jing: channels, meridians
Ba: eight (first differentiation)
Mai: vessels

The eight extraordinary vessels are not channels such as the *jing mai*, but they are – as the name implies – extraordinary. While they are often mentioned together with the primary channels (*jing mai* ➞ Fig. 1.3), they still play a special role.

1.7.1 Theories about the Origin of the Extraordinary Vessels

The eight extraordinary vessels are often considered to be the deepest and most original structures of the body and channel system, developing very early on during the embryonic phase. They are considered to 'cover all of human activity' (Larre et al 1986). They also initiate all secondary functions and always remain operative. Therefore, their pathologies manifest with complex symptoms and include pre- and postnatal Essence problems. The *Nanjing* (Unschuld's translation, 1986) is the first to describe the extraordinary vessels as a complete system. Earlier records only mention them individually in the context of their respective functions.

Origins of the extraordinary vessels

In order for the manifestations of life to develop, the body requires structures that keep the rhythm of the Qi and its related processes in harmony and balance. The *Nanjing* introduces the concept of an energetic centre in the human body, the 'moving Qi between the Kidneys', which is often seen as connected with the *mingmen* and *qihai dantian* and is subject to the influences of the cosmic as well as of the prenatal and postnatal Qi.

According to Matsumoto and Birch (1986), the 'moving Qi between the Kidneys' represents the *Taiji* of the body, the Great One, the origin of Yin and Yang. It is considered to be the root and origin of all human systems and structures and, according to some authors, it has a connection to the Original Qi (*yuan qi*) (→ 1.1.4). The *chong mai*, as the oldest vessel, is sometimes equated with the 'moving Qi'. The *ren mai* and *du mai* represent the basic division of the Yin and Yang in the body; in other words, they originate from the 'moving Qi' or *chong mai* as Yin and Yang branches. During the 'division', one movement ascends the front of the body (*ren mai*), the other movement the back (*du mai*).

Heaven and Earth have noon and midnight, the body has the *ren mai* and *du mai* as its polar axes. The *du mai*, *ren mai* and *chong mai* have different names, but in the end they are the same and have the same significance. The *chong mai* ensures the inseparability or unity of the *du mai* and *ren mai* – of Yin and Yang. If we tried to separate Yin and Yang, we would have to realise that they are an 'inseparable whole, a unit'.

Therefore, the extraordinary vessels function as a kind of matrix, which is the source of the energetic functioning and the cellular divisions in the body. This matrix is present from the moment of conception and organises the structuring of the embryonic development from the earliest stages.

Explanation of Fig. 1.29 (after Matsumoto and Birch)

In the beginning, there is the Great One, the *Taiji* (first level). At this level of 'no-form', the Great One begins to separate (second level) and becomes Yin and Yang (third level). At the fourth level, Yin and Yang separate twice (two branches):

- One branch **separates in a threefold way** to become the **Triple** Burner (*san jiao*) and its associated forms of Qi. Further separations lead to the formation of the **six** great channels (*liu jing* → 1.2), the **Five** Phases and **their source**, as well as the 12 primary channels.
- The other branch separates at the fourth level to form the **four** body areas (left, right, above, below) and then the **eight** extraordinary vessels.



Fig. 1.29 Origin of the channels

Scars of the first cell division

Matsumoto and Birch (1986) comment on the work of Manaka and others, who interpret the extraordinary vessels with regard to embryonic development, regarding them as scars or 'lines of separation of the first cell divisions'.

The *du mai* and *ren mai* are the result of the first division of the fertilised egg, while the *dai mai* develops during the second division. At this stage, the embryo is essentially a torso, while the extremities and the more 'peripheral' extraordinary vessels – the *yang qiao mai* and the *yin qiao mai* as well as the *yang wei mai* and the *yin wei mai* – only form during subsequent divisions.

The eight extraordinary vessels and body structure

- According to Manaka et al (1995), a close connection exists between the eight extraordinary vessels and **body** structure/symmetry.
- The ***du mai*** and the ***ren mai*** separate the body **vertically** into **left** and **right**: the *ren mai* marks the anterior midline, the *du mai* ascends the posterior midline.
- The ***dai mai*** circles the waist **horizontally,** forming a **horizontal axis**. It separates **above** from **below** (→ Fig. 1.30 a).

In a further development of this idea, Manaka describes the division of the body into **eight areas,** using the structure of a topological octahedron for illustration. (→ Fig. 1.30 b). In this model, the eight extraordinary vessels directly relate to the lines 'separating' the faces of the octahedron:

- Due to their location on the anterior/posterior midline, the ***ren mai*** and the ***du mai*** separate the body into its right and left section.
- The ***dai mai*** separates above and below.
- The **G.B. and T.B. channels** compare to the anterior and posterior dividing lines at the lateral edges of the Yang aspect of the body.

- The **P** and **SP channels** compare to the anterior and posterior dividing lines at the lateral edges of the Yin portion of the body.

The opening points of the extraordinary vessels, with the exception of **SP-4** (a point on the LIV channel would be more appropriate), represent this division:

- **P-6** and **T.B.-5** are the opening points of the *yin wei mai* and *yang wei mai* respectively
- **SP-4** and **G.B.-41** are the opening points of the *chong mai* and *dai mai* respectively.

These four channels divide the **anterior** and the **lateral** aspects of the body and connect the **upper** and **lower** parts, the four associated extraordinary vessels functioning accordingly. The *yin qiao mai* and the *yang qiao mai*, due to their connection to the KID and BL channels (opening points **KID-6** and **BL-62**) have a close relationship to the *ren mai* and *du mai*. Furthermore, the pathway of the KID channel is located close to the *ren mai* while the BL channel is close to the *du mai*.



Fig. 1.30 Development of the octahedral structure based on body symmetry

1.7.2 Principles and Functions

'The primary channels are the rivers, the extraordinary vessels are the lakes.'

In some of the classics, the extraordinary vessels are compared to reservoirs, which store excess Yang, Yin, Qi or Blood, releasing it into the primary channel system in times of need. With the exception of the *ren mai* and *du mai* they do not have their own points, but they can be accessed through and are connected by points on the primary channels (see pathways of the primary channels → Chapter 5). All extraordinary vessels (with the exception of the *dai mai* with its horizontal trajectory) begin at the lower extremities or in the lower part of the torso and travel to the head. They can be activated by needling their opening and coupled points (differential therapy → 8.1.8).

Reservoir and compensation function

'*…when the network vessels (the primary channels) are filled to overflowing, none of the… conduits could seize any of their contents, and it is only then that the surplus contents of these vessels flow into the single conduit vessels (the extraordinary vessels)*' (*Nanjing*, translation by Unschuld 1986).

The *Nanjing* compares the extraordinary vessels to reservoirs, which are able to absorb a surplus of Qi and Blood in the primary channels, releasing them again during periods of deficiency. For example, if pathogenic factors penetrate the primary channel system, this excess can be absorbed by the extraordinary vessels. This will ensure that the *zangfu*-Organs remain unaffected. In that sense, the extraordinary vessels have a regulating compensation function.

Reproduction and fertility

The *chong mai* and the *ren mai* in particular, but also the *du mai*, play an important role in reproduction and fertility.

Connecting the primary channels

- The *chong mai*, also known as the '**sea of the 12 primary channels**', connects the primary ST and KID channels. It also strengthens the connection between the *ren mai* and the *du mai*.
- The *ren mai* as the **sea of Yin** connects all Yin channels
- The *du mai* as the **sea of Yang** connects all Yang channels at **Du-14** (*dazhui*).
- The *dai mai* circles the body at the waist and binds the vertical trajectories of all 12 primary channels in general, but especially the *chong mai*, the *ren mai* and the KID, LIV and SP channels.
- The *yin wei mai* **dominates the Interior** of the body and connects the KID, SP and LIV channels and the *ren mai*.
- The *yang wei mai* **controls the Exterior** of the body and connects the BL, G.B., T.B., S.I. and ST channels and the *du mai*.
- The *yin qiao mai* connects the KID and BL channels and controls balance.
- The *yang qiao mai* connects the BL, G.B., S.I., L.I. and ST channels and controls activity.

In addition, the eight extraordinary vessels are regarded as **connecting channels for the extraordinary *fu***-Organs.

Protection of the body

The *chong mai*, *ren mai* and *du mai* circulate the Defensive Qi (*wei qi*) in the thorax, abdomen and the back, and thus help to protect the body against external pathogenic factors. Due to their origin, they are also directly linked to the Kidneys, the pre-Heaven Qi and to the constitutional forces.

1.7.3 Comparison of the Eight Extraordinary Vessels with the Primary Channels

	Primary channels	**Eight extraordinary vessels**
Points, trajectory	Specific, bilateral points	Only the *ren mai* and *du mai* have their own points (and internal pathways); all other extraordinary vessels 'borrow' points from the primary channels. The four central vessels are unilateral (except for the *chong mai*, which also has a pathway on the extremities); the four peripheral vessels are bilateral.
Circulation	Continuously circulate *Nutritive Qi* and Blood	Circulate Essence Qi, Nutritive Qi and Defensive Qi, but according to some authors they do not have a continuous flow of Qi
Depth	Superficial, external pathway and a deeper, internal pathway; directly connected to their pertaining *zangfu*-Organs	Compared to the internal pathways of the primary channels they are more superficial, compared to the external pathways of the primary channels they are deeper. They have **no direct connection** to the *zangfu*-Organs, but their origin – especially of the four central vessels – lies deep within the body.
Connections	They connect the Exterior and Interior (through internal/ external pathways and through Yin/Yang channels) as well as above and below (hand–foot pairing, axes)	They do not connect the Interior with the Exterior, nor do they connect Yin and Yang.
Functions	Guide excess to the eight extraordinary vessels or to other secondary channels	Reservoir function: excess of Qi and Blood in the primary channels flows to the eight vessels and are stored there. In times of deficiency they are transported back into the primary channels.
Diagnosis	Diagnosis based on channel theory (meridian therapy), in TCM according to the *ba gang* (*zangfu*, pulse and tongue)	Diagnosis is characterised by specific arrays of symptoms and specific pulses.

1.7.4 Pairing and Special Functions

The eight extraordinary vessels can be paired in several ways (→ Fig. 1.31):

- The central vessels and the peripheral vessels can be coupled to form Yin/Yang pairs
- Or a central vessel can be paired with a peripheral vessel. These pairs support particular regions and are very important in acupuncture therapy (→ Opening points 8.1.8).


du mai
ren mai
dai mai
a
yin qiao mai
ren mai
du mai
yang qiao mai
Yin vessels
Centre
Yang vessels
chong mai
dai mai
yin wei mai
yang wei mai
Centre ↔ periphery (Yin–Yin, Yang–Yang)
Periphery ↔ periphery (Yin–Yang)
Centre ↔ centre (Yin–Yang)
b

Fig. 1.31 Pairing of the extraordinary vessels (b, graphic overview modified according to Pirog 1996)

Pairing according to Yin/Yang polarity

Pairing of the extraordinary vessels according to Yin/Yang polarity

Yin vessels	Yang vessels	Functions of the Yin/Yang pair	General functions – Centre/periphery
Central vessels (pathways on the head and torso)			
ren mai	*du mai*	The *du mai* can be considered to be the first manifestation of the Qi and Yang, the *ren mai* the first manifestation of the Blood and Yin. This pair **stores the Yin Qi and Yang Qi**.	**Functions:** Storage and distribution (of Yin and Yang). Foundation of the eight extraordinary vessels, stores Essence Qi, is responsible for the support of the internal organs and extraordinary *fu* organs, as well as for the fundamental body structures
chong mai	*dai mai*	The *chong mai* is like a harmonious connection between Yin and Yang, it expresses vitality and sets impulses. The *dai mai* encircles; it is like a container and prepares the circulation of Yin and Yang. The pair **circulates the Essence (*jing*) and Qi between the Yin and Yang regions of the body**.	
Peripheral vessels (pathways from the lower extremities to the torso)			
yin qiao mai	*yang qiao mai*	This pair **creates balance between Yin and Yang** (for example balance between Essence (*jing*) and Qi, Blood and Qi, left and right, Nutritive Qi and Defensive Qi, also on the outside – between day and night), controls and regulates the ascending (*yin qiao mai*) and descending (*yang qiao mai*) movement in the body, is responsible for balance and rhythm between Yin and Yang.	**Functions:** Balance, circulation and connection (of the Yin and Yang aspects). Provides contact between the distal regions of the body and the torso and head.
yin wei mai	*yang wei mai*	The *yin wei mai* governs the Interior (*li*), it organises and creates connections within the *Yin* aspects of the body. The *yang wei mai* governs the Exterior (*biao*), it organises within the Yang aspects of the body. This pair **connects the Yin and Yang respectively.** 'That which moves and circulates between the *Yin* channels is called the *yin wei* – that which moves between the Yang channels is called the *yang wei*.'	

Central–peripheral pairing

Here, a central vessel is combined with a peripheral vessel. This pairing probably refers to regions of the body which are traversed and supplied by the pair.

Central–peripheral pairing of the extraordinary vessels

Pair	Vessel	Relationship	Opening point	Coupling point	Supported regions
Pair 1	*chong mai*	father	SP-4	P-6	Heart, thorax, Stomach
	yin wei mai	mother	P-6	SP-4	
Pair 2	*du mai*	husband	S.I.-3	BL-62	Inner canthus of the eye, occiput, shoulders and back, S.I. and BL channels
	ren mai	wife	BL-62	S.I.-3	
Pair 3	*dai mai*	man	G.B.-41	T.B.-5	Lateral eye and temple region, ears, cheeks, occiput and shoulders
	yang wei mai	woman	T.B.-5	G.B.-41	
Pair 4	*ren mai*	host	LU-7	KID-6	Face, throat, thorax, Lungs, diaphragm, abdomen
	yin qiao mai	guest	KID-6	LU-7	

2 Location Methods and Cun Measurements

Claudia Focks

One of the basic prerequisites for any successful acupuncture treatment, besides a differential Chinese Medicine diagnosis and the relevant point selection, is the correct point location.

2.1 Location Methods for Body Acupuncture

There are various methods for locating acupuncture points:

Anatomical approach: many acupuncture points are situated at clearly defined anatomical locations, for example in depressions, at muscle and tendon insertions, in grooves, at joint clefts, at bony prominences, etc. With some experience, the palpating finger will often automatically 'fall' into the right depressions and holes.

Various anatomical structures and zones form the basis for point location. These are described in more detail in Chapter 3. We can distinguish between the following:

- **Fixed markers** are not affected by the body position or by movement. These include bony landmarks such as depressions or prominences of the skeletal system, but also the finger- and toenails, the nipples, the umbilicus, etc. Most of the proportional cun measurements (→ 2.2) rely on fixed markers.
- **Movable markers** often become more clearly defined with a particular body posture or movement (→ 2.3.2). For example, by flexing the elbow, the cubital crease becomes much more clearly visible to locate **L.I.-11** precisely. Equally, the most distal palmar crease becomes much more visible when making a loose fist, in order to locate **S.I.-3**. Other parameters that might determine the location of a point include changed skin consistency, sensitivity to pressure, puffiness or a resistant sensation when palpating gently with a finger.

Proportional measurements: When trying to locate points not situated at any prominent structures, Chinese Medicine applies the proportional cun measurement (→ 2.2).

Electric tools: These measure the electric resistance of the skin in order to find the correct location of the points. Generally, electric resistance is lower in the immediate area around the point. This method is especially used in auricular acupuncture, but it has not proved to be a practical method for body acupuncture.

Very point technique (after Gleditsch 2005): The needle is held loosely and guided in a 'dancing' fashion over the skin. When the correct point – the 'very point' – is found, the needle will 'catch' on to it and penetrate the skin as if out of its own volition.

2.2 Cun Measurements of the Body

In Chinese medicine, distances on the body are traditionally measured in cun. In contrast to the official Chinese cun (1 cun = 2.5 cm), the cun used in a medical context is a **proportional unit of measurement** that takes the individual proportions of each body into account.

This relative unit of measurement is defined either by using the width of a particular finger or fingers (finger cun) or by the distances between clearly defined landmarks of the body (body cun).

In clinical practice, many points can be located by using **finger cun** measurements (→ Fig. 2.1). It is important, however, to use the **patient's fingers**, not the practitioner's fingers, for reference. If the fingers of both the practitioner and the patient have approximately the same width, the width of the practitioner's fingers can be applied for point location. Otherwise, measurements have to be adapted to correct minor deviations, for example by adjusting the spaces (narrow or wide) between the practitioner's fingers when using finger cun measurements.

The **body or proportional cun** is based on the proportions of particular sections of the body, which are divided into a specific number of units (→ Fig. 2.3). In clinical practice, the measurement of these divisions can be quite cumbersome. Therefore, the spreading hands technique is commonly applied (Koenig and Wancura 1979/1983). It allows the practitioner to quickly determine the midpoint of a given distance (→ 2.3.3) and, combined with finger cun measurements and palpation, is in most cases sufficient for correctly locating a point. For point location on the abdomen, a prepared elastic tape can be useful for measuring proportional cun (→ 2.3.1).

Finger cun


A
1
B
2
C
1
3
F
2
E
1.5
D

A:
1 cun:
thumb

B:
2 cun:
index finger

C:
1 cun:
middle finger

D:
1.5 cun:
finger-width

E:
2 cun:
finger-width

F:
3 cun:
finger-width

Fig 2.1

A	1 cun as thumb measure	The width of the interphalangeal joint of the thumb at its widest point
B	2 cun as index finger measure	The distance of the two distal phalanges of the index finger
C	1 cun as middle finger measure	With the tip of the middle finger placed on the thumb, the distance between the ends of the creases of the interphalangeal joints of the middle finger
D	1.5 cun as two-finger measure	The width of the index and middle finger when placed closely together, at the level of the distal interphalangeal joints
E	2 cun as index, middle and ring finger measure	The width of the index, middle and ring finger when placed closely together, at the level of the distal interphalangeal joints
F	3 cun as four finger measure	The width of the four fingers when placed closely together, at the level of the distal interphalangeal joints (=1 hand-breadth)

Body cun or proportional cun – the most commonly used proportional distances

Tip for locating the end of the axillary fold: The anterior or posterior axillary fold defines the end of the axilla, forming a fold in the skin (both anteriorly and posteriorly), where the arm joins the thorax. The axillary fold is the reference point for any cun measurements on the upper arm (→ Figs 2.2, 2.3, LU-3 and LU-4), which can be found by asking the patient to adduct his/her arm and to insert his/her flat hand into the axilla. The end of the axillary fold points in a superior direction, terminating at the lower border of the pectoralis major muscle, which in this area extends to its insertion in the humerus, below the deltoid muscle. The end of the axillary fold may vary considerably, depending on the individual proportions, positioning of the arm and flexing of the muscles. It should therefore be located with the patient's arms hanging down in a relaxed way.


9
9
12
3
3
Suprasternal fossa
9
8
End of the axillary fold
Sternocostal angle
9
8
Cubital crease
Centre of the umbilicus
12
5
Upper border of the pubic symphysis
Wrist joint space
Gluteal crease
18
19
14 cun
Highest prominence of the greater trochanter
Popliteal crease
Upper patellar border
Popliteal crease
Transition shaft/medial condyle of the tibia
13
16
Highest prominence of the medial malleolus
Highest prominence of the lateral malleolus
1 cun
3 cun
Highest prominence of the medial malleolus
Highest prominence of the lateral malleolus
Lower border of the heel

Fig. 2.2

Head		
Longitudinal	12 cun	From the anterior (→ 3.1.1) to the posterior hairline (→ 3.1.5)
	3 cun	From the midpoint of the eyebrows to the anterior hairline (→ 3.1.1)
	3 cun	From the lower border of the spinous process of C7 (→ 3.4.1) to the posterior hairline (→ 3.1.5)
	18 cun	From **Ex-HN-3 (*yintang*)** to **Du-14**
Horizontal	9 cun	The distance between the mastoid processes (→ 3.1.4)
	9 cun	From corner to corner on the forehead (**ST-8** to **ST-8**)
Thorax and abdomen		
Longitudinal	9 cun	From the suprasternal depression (**Ren-22**) to the sternocostal angle (→ 3.5, xiphosternal synchondrosis)
	8 cun	From the sternocostal angle (→ 3.5, xiphosternal synchondrosis) to the centre of the umbilicus
	5 cun	From the centre of the umbilicus to the upper border of the pubic symphysis (→ 3.5)
Horizontal	8 cun	The distance between the two nipples
Laterally longitudinal	12 cun	From the end of the axillary fold to the tip of the free end of the 11th rib (**LIV-13**)
Back and lumbar region		
Both the spinous processes and the intercostal spaces are used for orientation. Main reference points are: the spinous process of C7, the inferior angle of the scapula (level with T7), the iliac crest (level with the spinous process of L4), the posterior superior iliac spine (PSIS) (level with S2 or the 2nd sacral foramen). Please note: the position of the patient (standing, sitting, lying) as well as individual anatomy and spinal structure (kyphosis, lordosis etc.) all influence the level of the vertebrae, which consequently may vary considerably in relation to other anatomical structures. For more detail → Chapter 3.		
Longitudinal	30 cun	From the spinous process of the T1 to the tip of the coccyx
Horizontal	3 cun	From the medial border of the scapula to the posterior midline (spinous processes), with the shoulder relaxed and hanging arms
Upper extremity		
Lateral	9 cun	From the end of the anterior axillary fold to the transverse cubital crease
	12 cun	From the transverse cubital crease to the wrist joint space (→ 3.3.3, transverse wrist crease)
Lower extremity		
Lateral	19 cun	From the highest prominence of the greater trochanter (→ 3.6) to the popliteal crease
	16 cun	From the popliteal crease to the highest prominence of the lateral malleolus (→ 3.6.2)
	14 cun	From **G.B.-34** (anterior and inferior to the head of the fibula) to the highest prominence of the lateral malleolus (→ 3.6.2)
	3 cun	From the highest prominence of the lateral malleolus (→ 3.6.2) to the lower border of the heel
Medial	18 cun	From the upper border of the pubic symphysis (3.5) to the upper border of the patella (→ 3.6.1)
	15 cun	From the medial end of the popliteal crease to the highest prominence of the medial malleolus (→ 3.6.2)
	13 cun	From the medial condyle of the tibia (→ 3.6.1, junction of the head and the shaft of the tibia) to the highest prominence of the medial malleolus (→ 3.6.2)
Dorsal	14 cun	From the gluteal crease to the popliteal crease
Difference between the medial and lateral malleolus		
	1 cun	Difference between the level of the highest prominence of the lateral and medial malleolus respectively (→ 3.6.2)


8 cun
5 cun
8 cun
5 cun
8 cun
5 cun
8 cun
5 cun
8 cun
5 cun
8 cun
5 cun
16 cun

Fig. 2.3


Sternocostal angle
Umbilicus

Fig. 2.4

2.3 Tips for Point Location

2.3.1 Elastic Tape

A marked elastic tape has proven a very useful tool for simplifying cun measurements and facilitating correct point location. It is especially recommended for measurements on the abdomen, the shape of which can vary considerably from patient to patient (Kitzinger 1995). An elastic tape, 1–2 cm wide and approximately 40 cm long, is marked at regular intervals of 2 cm, which can optionally be numbered from 1–20. The tape is placed onto the distance to be measured, stretching it according to the correct number of cun for that particular distance. This method allows the use of proportional cun for each individual patient.
Examples:

- For locating points on the upper abdomen, stretch the tape so that eight units cover the distance between the sternocostal angle and the centre of the umbilicus (→ Fig. 2.4).
- For locating points on the lower abdomen, stretch the tape so that five units cover the distance between the upper border of the pubic symphysis and the centre of the umbilicus (→ Fig. 2.5).


Umbilicus
Upper border of the pubic symphysis

Fig. 2.5

2.3.2 Patient Positioning and Body Movements

To locate certain points, it can be very helpful to ask the patient to assume a particular position or to perform a specific movement.

Examples:

- For locating points on the **P** channel on the forearm, ask the patient to tightly press the thumb and little finger together. This will make the tendons more visible (→ Fig. 2.6)
- ‘Tiger mouth grip’ as location help for **LU-7** and **L.I.-6** (→ Fig. 2.7)
- For locating **L.I.-4**, ask the patient to press his/her thumb and index finger together. A muscle bulge will form; L.I.-4 is located on its highest point (→ Fig. 2.8).
- When turning the wrist joint from a pronated to a half-supinated position, the palpating finger will glide into a bony cleft just proximal to the styloid process of the ulna (**S.I.-6**, → fig 2.9).
- As the palpating finger glides along the skin, the skin bulge forming in front of it will ‘arrest’ the finger at the point to be located. This method is very useful for quick location of certain points such as **T.B.-5** or **P-6** (→ Fig. 2.10).


Pressing the thumb and little finger together for better presentation of the tendons
Tendon of the M. flexor carpi radialis
Tendon of the M. palmaris longus
P-7
Pisiform
Wrist joint space

Fig. 2.6



Fig. 2.7


Midpoint
Metacarpal II
L.I.-4
Highest point of the muscle bulge

Fig. 2.8


Initial position: pronation
Distal part of the styloid process of the ulna
Half-supination
Palpating finger slides into the bony cleft

Fig. 2.9



Fig. 2.10

2.3.3 Spreading Hands Technique According to König and Wancura

The spreading hands technique is particularly useful for quickly determining the midpoint of a given distance. For this purpose, the little fingers of each hand are placed on the endpoints of the distance to be measured. Both hands are then evenly spread over the distance. The thumbs are joined in the middle, indicating the midpoint of the distance.

Examples:

- To determine the midpoint of the 16 cun-distance between the popliteal crease and the prominence of the lateral malleolus, the little fingers are placed on both endpoints of this distance (→ Fig. 2.11)
- To locate **Du-20**, the hands are placed on the lateral aspects of the patient's head, with the little fingers touching the apices of the ears. The thumbs are then joined on the vertex of the head, and will be pointing to **Du-20** (→ Fig. 2.12).


Du-20
Little finger on the apex of the ear
Little finger on the apex of the ear
Midpoint

Fig. 2.12


ST-35 (Level of the popliteal crease/knee joint space)
8 cun
Midpoint
8 cun
Highest prominence of the lateral malleolus

Fig. 2.11

3 Anatomical Orientation

Ulrich März


Cranial
midline
('vertex')
Ex-HN-1
(*sishencong*)
Line connecting the
apices of the ears
Du-20

Fig. 3.1


Coronal suture
Parietal bone
Frontal
eminence
Du-20
Sagittal suture
Vertex
Occipital bone

Fig. 3.2

3.1 Head

3.1.1 Vertex, Forehead and Supraorbital Region

Vertex (➞ Figs 3.1, 3.2)

➞ **Du-20** (*baihui*) is located at the junction of the cranial midline and an imaginary line connecting the apices of the ears. This point is at a distance of 5 cun from the anterior hairline and 7 cun from the posterior hairline, marking the highest point of the cranium ('vertex').

Please note: When locating **Du-20**, the patient's head should be in an upright position. Spreading hands technique (after König and Wancura, ➞ Chapter 2): Place the hands on the lateral aspects of the patient's head, with the little fingers touching the apices of the ears. The thumbs are then joined at the cranial midline and will be pointing to ➞ **Du-20** (*baihui*).


5 cun
Du-20
Apex of
the ear
Apex of
the ear

Fig. 3.3

Anterior hairline (→ Fig. 3.4)

The anterior hairline forms the superior border of the forehead and can vary considerably from person to person. The original line of hair growth is generally considered as the anterior hairline.
In men especially, the hairline may begin to recede early in life due to progressive baldness, so that the existing hairline may not be identical with the original line, which will now be located in an area not covered by hair. In these cases ask the patient to frown: the original hairline will be located superior to the wrinkled forehead, at the junction of the still slightly creased skin with the completely smooth skin. Points in this area are → **Du-20** to **Du-24**, **BL-3** to **BL-7, G.B.-4** to **G.B.-7, G.B.-13** to **G.B.-15, ST-8.**


ST-8
G.B.-15
BL-3
G.B.-13
BL-4
Du-24
Anterior hair line

Fig. 3.4


Du-24
BL-4
0.5 cun
ST-8
Hairline
1.5 cun
1/3
2/3
Midline

Fig. 3.5


Du-24
G.B.-15
G.B.-13
0.5 cun
ST-8
Hairline
3 cun
2/3
1.5 cun
1/3
Midline

Fig. 3.6


Coronal suture
ST-8
Parietal bone
Frontal bone
Occipital bone
Temporal bone
Zygomatic arch
Zygomatic bone
Mandible

Fig. 3.7


ST-8
Temporalis
Sternocleidomastoid

Fig. 3.8

Temporalis muscle and temporal corner of the forehead (→ Figs 3.7–3.9)

By asking the patient to firmly clench and release his/her teeth, the temporalis muscle can be palpated on the lateral aspect of the forehead. The corner between the forehead and the temples is marked by the junction of the anterior hairline with the temporal hairline, which tends to become more pronounced with a receding hairline.

→ **ST-8** is located in the centre of this area, at the insertion point of the temporalis muscle and 0.5 cun within the natural hairline. Often, the coronal suture can be palpated here.


ST-8
Chewing still palpable
Temporalis

Fig. 3.9

Forehead (→ Figs 3.10, 3.11)

The more or less prominent bulge of the frontal eminences can be palpated on both sides of the forehead. → **G.B.-14** is located at their lower border, in a shallow depression at the junction of the eminences and the superciliary arches. With the patient looking straight ahead, G.B.-14 is located directly above the pupil, approximately 1 cun superior to the supraorbital margin.

Glabella, superciliary arches

The glabella is the central bony reference point on the forehead, forming a slightly convex, level area superior to the root of the nose and between the superciliary arches.
The extra point *yintang* (Ex-HN-3) is located at the centre of the glabella. Several points are located along the superciliary arches (from medial to lateral): → **BL-2,** ***yuyao*** (Ex-HN-4) and **T.B.-23.**
Please note: → **BL-2** is located superior to the inner canthus of the eye, in the area of the frontal (not the supraorbital) incisure, when this is present.


Frontal eminence
[tuber frontale]
G.B.-14
G.B.-14
Ex-HN-4
(*yuyao*)
Glabella
Ex-HN-3
(*yintang*)
T.B.-23
BL-2
Superciliary arch

Fig. 3.10


Ex-HN-3
(*yintang*)
Frontal squama
BL-2
Ex-HN-4
(*yuyao*)
G.B.-14
Ex-HN-4
(*yuyao*)
T.B.-23
Orbit
Zygomatic bone
Apertura piriformis

Fig. 3.11


Infraorbital foramen
Zygomatic bone (zygoma)
ST-2
S.I.-18
Maxilla (upper jaw)

Fig. 3.12


Frontal squama
Orbit
S.I.-18
Maxilla
ST-2
Apertura piriformis
Zygomatic bone
Infraorbital foramen

Fig. 3.13

3.1.2 Centre of the Face and Nasal Region

Cheek bones (→ Figs 3.12, 3.13)

Both the maxilla and the zygoma form the cheek bones below the eyes. Important anatomical landmarks are the infraorbital foramen, the lower border of the zygoma and the zygomatic arch of the temporal bone.

Infraorbital foramen (→ Figs 3.12, 3.13)

With the patient looking straight ahead, the infraorbital foramen with → **ST-2** is located on the maxilla, directly below the pupil. The foramen lies 1 finger-width below the infraorbital ridge. By palpating inferiorly from there, it can be felt below the maximal curvature of the ridge, in a small depression that is often sensitive to pressure.


Infraorbital margin
ST-2

Fig. 3.14

Zygoma (→ Figs 3.15, 3.16)

The bony structures below the lateral orbit are formed by the zygoma. → **S.I.-18** is located directly below the outer canthus of the eye at the lower border of the zygoma, at the junction of the zygoma and the maxilla, on the anterior border of the masseter muscle. (→ Lower face and chin).

Zygomatic arch (→ Figs 3.15, 3.16)

On the lateral aspect of the face, the temporal process of the zygoma articulates with the zygomatic process of the temporal bone to form the zygomatic arch. This is an approximately horizontal bony structure which can be palpated laterally to the ear. → **G.B.-3** and → **T.B.-22** are both located on the upper border of the zygomatic arch, while → **ST-7** and → **T.B.-21** are situated at its lower border.


Zygoma
Zygomatic arch
Temporomandibular joint
G.B.-3
T.B.-22
T.B.-21
ST-7

Fig. 3.15


Temporal bone
T.B.-22
G.B.-3
Occipital bone
T.B.-23
ST-7
Zygomatic arch
Mandibular angle

Fig. 3.16



Fig. 3.17


Mandibular incisure
Mandibular head
Articular disc
External acoustic meatus
Condyloid process
Ramus of the mandible
Coronoid process
SK

Fig. 3.18


Mandibular head
Articular disc
External acoustic meatus
Articular capsule
Ramus of the mandible
SK

Fig. 3.19


G.B.-3
Styloid process

Fig. 3.20

Temporomandibular joint (→ Figs 3.15, 3.18, 3.19)

The temporomandibular joint is located inferior to the zygomatic arch and anterior to the tragus of the ear. Its movement can easily be palpated by gently opening and closing the mouth. → **ST-7** is located in a depression anterior to the joint and directly inferior to the zygomatic arch. This depression is situated in the mandibular incisure, which is formed by the coronoid and condylar processes of the mandible. By opening the mouth, the palpating finger resting on → **ST-7** is 'lifted' out of the depression by the condyloid process sliding anteriorly.

Nasolabial groove (→ Fig. 3.21)

The nasolabial groove begins lateral to the nose and superior to the ala nasi, at the junction of the cartilage and the bone. From there it runs to the corners of the mouth. → **Ex-HN-8** (*shangyingxiang, bitong*) is located at its upper end, at the junction of the upper jaw and the nasal cavities. → **L.I.-20** is located slightly below *bitong*, between the lateral border of the side of the nose and the nasolabial groove.

3.1.3 Lower Face and Chin

Mandibular angle (→ Fig. 3.22)

The mandibular angle corresponds to the area where the lower jaw line changes its direction from horizontal to vertical. It is located markedly inferior and anterior to the ear lobe. This angle marks the location of → **ST-6** (1 finger-width anterior and superior to the mandibular angle) as well as of → **S.I.-17** and → **T.B.-16** (level with the mandibular angle).


Ex-HN-8
(*bitong*)
Nasolabial groove
L.I.-20
Maxilla
(upper
jaw)

Fig. 3.21


Masseter
Zygomatic bone
Man-
dibular
angle
S.I.-18
T.B.-16
ST-5
Sternocleidomastoid
ST-6
S.I.-17

Fig. 3.22


S.I.-18
ST-6
ST-5
Masseter

Fig. 3.23

Masseter muscle (→ Fig. 3.23)

By firmly clenching the jaw, the contours of the masseter muscle become well defined, stretching from the lateral aspect of the lower jaw to the zygomatic bone. It originates at the zygomatic arch (→ Fig. 3.15) and inserts at the mandibular angle (→ Fig. 3.22).

Mentolabial groove (→ Fig. 3.24)

This forms a transverse groove at the junction of the chin and the lower lip. → **Ren-24** is located in its centre.


Mentolabial groove
Ren-24

Fig. 3.24

3.1.4 Ear Region

Note: points used in auricular acupuncture are not discussed here.

Helix root (➞ Figs 3.25, 3.26)

The helix root borders the upper part of the ear. This is the location of ➞ **T.B.-22**.

Supratragic notch (➞ Figs 3.25, 3.26)

The supratragic notch forms an incisure within the cartilage of the ear, separating the helix root from the tragus. ➞ **T.B.-21** is located anterior to it.

Tragus (➞ Figs 3.25, 3.26)

➞ **S.I.-19** is located anterior to the midpoint of the tragus.

Intertragic notch (➞ Figs 3.25, 3.26)

The intertragic notch forms an incisure in the auricular cartilage, separating the tragus from the lobe and antitragus. ➞ **G.B.-2** is located anterior to this notch.

Ear lobe (➞ Figs 3.25, 3.26)

Inferior to the earlobe and the ear canal is a depression, which is bordered posteriorly by the mastoid process and anteriorly by the lower jaw. The lower border is formed by the transverse process of the 1st cervical vertebra (atlas). ➞ **T.B.-17** is located in this depression.

Border between the auricle and the face (➞ Fig. 3.26)

The border between the auricle and the temple/cheek generally forms a more or less vertical line, which will become more clearly defined by bending the auricle and tragus towards the anterior. Several points are located along this line (from top to bottom): ➞ **T.B.-22, T.B.-21, S.I.-19, G.B.-2.**

Mastoid process (➞ Figs 3.26, 3.27)

The mastoid process is a cone-shaped bony structure which can be palpated posterior to the ear. ➞ **G.B.-12** is located at its tip, while ➞ ***anmian*** (Ex-HN) can be found at the border of the mastoid process and the occiput. ➞ ***yiming*** (Ex-HN-14) is located somewhat more inferiorly.


Helix
Antihelix
Antitragus
Lobe
Helix root
Supratragic notch
Tragus
Intertragic notch

Fig. 3.25


Helix root
Supratragic notch
Tragus
Intertragic notch
T.B.-22
T.B.-21
S.I.-19
G.B.-2
T.B.-17
Transverse process of the atlas
Mastoid process
Ex-HN (*anmian*)
Ex-HN-14 (*yiming*)
G.B.-12
Sternocleidomastoid

Fig. 3.26


Mastoid process
Occipital bone
G.B.-12
Ex-HN-14 (*yiming*)
Ex-HN (*anmian*)

Fig. 3.27


Transverse process of the atlas
Axis, dens
Atlas
Axis

Fig. 3.28


Atlas
Du-16
G.B.-20
Occipital bone
Lower border of the occiput
G.B.-20
Axis
BL-10
Sterno-cleidomastoid
Du-15
1st palpable spinous process
Trapezius, superior fibres
Du-14

Fig. 3.29

Transverse process of the 1st cervical vertebra (atlas) (→ Fig. 3.28)

The transverse process of the atlas can be palpated inferior to the earlobe as a deep bony structure, which in most cases is very sensitive to pressure.

3.1.5 Occiput

Craniocervical transition (→ Figs 3.28–3.32)

The transition from the head to the neck is formed by the mastoid process, the adjacent dorsal musculature and the occiput. The following points are located in this area (from lateral to medial) → **G.B.-12,** ***yiming*** **(Ex-HN-14),** ***anmian*** **(Ex-HN), G.B.-20, BL-10, Du-15** and **Du-16.**

External occipital protuberance (→ Figs 3.32, 3.33)

The external occipital protuberance forms a flat projection on the posterior midline of the occiput, which can be palpated slightly superior to the craniocervical transition. It defines the location of → **Du-16, Du-17** and **BL-9.** Sometimes, and more frequently in women, the protuberance may be defined only poorly or not at all.

Posterior hairline (no figure)

The posterior hairline is used as a reference point for locating points on the occiput, but due to its variable position it is not a very reliable landmark.


Approximate level of the root of the ear
G.B.-11
1/3
G.B.-12
Mastoid process

Fig. 3.30


Occipital bone
G.B.-20
G.B.-20
Lower border of the occiput
Axis
BL-10
Du-15
Sternocleido-mastoid

Fig. 3.31


External occipital protuberance
Du-17
BL-9
Du-16
G.B.-20
BL-10
Transverse process of the atlas
C1

Fig. 3.32


Sagittal suture
Parietal bone
Lambdoid suture
BL-9
Du-17
BL-9
Mastoid process
Occipitomastoid suture
Du-16
Occipital bone
External occipital protuberance

Fig. 3.33

3.2 Neck

Laryngeal prominence (→ Figs 3.34, 3.35)

In men, the laryngeal prominence as the highest point of the larynx ('Adam's apple') tends to form a clearly palpable and visible structure. In women, visual identification is more difficult, so that palpation is necessary in order to locate the V-shaped incisure on the upper border of the thyroid cartilage on the laryngeal midline. Located at the level of the laryngeal prominence are → **ST-9, L.I.-18** and **S.I.-16**.


Hyoid bone
Superior thyroid notch
Laryngeal prominence
Thyroid cartilage
**
Tracheal cartilage

Fig. 3.34


ST-9
L.I.-18
S.I.-16
Laryngeal prominence
Clavicular head
Sternal head
Sternocleidomastoid

Fig. 3.35

Sternocleidomastoid (SCM) muscle (→ Figs 3.36, 3.37)

This muscle forms a distinct, easily identifiable structure on the anterior and lateral aspect of the neck, which becomes visible and palpable by rotating the neck in the opposite direction. This effect can be increased by rotating the head against resistance (by pushing against the chin for example). The more slender clavicular head originates from the anterior aspect of the manubrium, while the more flat clavicular head originates from the medial third of the clavicle, revealing a small triangle between the two heads near the sternoclavicular joint. This is the location of → **ST-11**. By palpating along the SCM muscle in a superior direction, the two heads can be distinguished for the major part of the muscle, before they merge to insert at the posterior part of the mastoid process and the lateral superior nuchal line of the occiput. Besides → **ST-11,** the following points are located alongside the muscle belly of the SCM: → **L.I.-17, L.I.-18, S.I.-16, ST-9, G.B-12** and ***anmian*** **(Ex-HN)**.


Ex-HN (*anmian*)
G.B.-12
ST-9
Sternocleido-mastoid
L.I.-18
S.I.-16
L.I.-17
Laryngeal prominence
ST-11
Sternal head
Clavicular head

Fig. 3.36


Great auricular nerve
Major occipital nerve
External jugular vein
Transverse cervical nerve
Sternocleidomastoid muscle

Fig. 3.37


Trapezius
(superior fibres)
G.B.-21
S.I.-13
S.I.-12
L.I.-16
T.B.-15
S.I.-10
Trapezius
(inferior fibres)

Fig. 3.38


Vertebral prominence,
spinous process
External occipital protuberance
Sternocleidomastoid
Splenius capitis
Trapezius
Scapular
spine
Deltoid
Acromion
Scapula,
inferior angle
Teres major
Latissimus dorsi

Fig. 3.39

3.3. Shoulder and Arm

3.3.1 Shoulder and Upper Arm

Trapezius muscle (→ Figs 3.38, 3.39)

This muscle covers the superior aspect of the shoulder, its superior portions extending from the cervical spine to the acromion at the lateral end of the scapula. Located at the midpoint of the superior border of the muscle are → **G.B.-21** and, slightly inferiorly, → **T.B.-15.**

Acromion (→ Figs 3.39, 3.42, 3.43)

When palpating the shoulder joint from a lateral direction, the acromion can be felt as a bony extension with a flat surface, slightly superior to the laterally protruding head of the humerus.

Scapular spine (→ Figs 3.39–3.44)

The scapular spine forms a bony ridge that originates at the acromion and runs in an oblique angle across the scapula, ending at its medial border in an upward opening curve. This is the location of → **S.I.-13**, → **L.I.-16** is located on the most lateral portion of the trapezius and supraspinatus muscles, in the angle between the acromial origin of the scapular spine and the acromioclavicular joint.

Head of the humerus, shoulder hollows (→ Figs 3.42, 3.44)

The head of the humerus is located inferior to the acromion and protrudes slightly on the lateral aspect of the shoulder. When abducting the arm horizontally, two hollows will form at the transition from the arm to the shoulder. The anterior hollow is the location of → **L.I.-15**, while → **T.B.-14** is located in the posterior one. The hollows mark the border between the clavicular and acromial portion and the border between the acromial and spinal portion of the deltoid muscle.


C7, spinous process
T1, spinous process
S.I.-13

Fig. 3.40


Clavicle
L.I.-16
AC joint
Acromion

Fig. 3.41


Acromion
Trapezius
Deltoid
Scapular spine
Triceps brachii, lateral head
Teres major
Triceps brachii, long head
Biceps brachii

Fig. 3.42


Facies articularis clavicularis
Acromion
Supraspinatus
Biceps brachii, tendon of the long head
Head of the humerus
Scapula
Biceps brachii, tendon of the long head
Humerus

Fig. 3.43


Coracoid process
Acromion
Scapula, superior angle
Supraspinous fossa
Scapular spine
Glenoid cavity
Medial border
Lateral border
Inferior angle

Fig. 3.44


Deltoid
S.I.-10
Border of the deltoid
S.I.-9
End of the axillary fold

Fig. 3.45


L.I.-15
T.B.-14
Anterior fibres
Lateral fibres
Posterior fibres

Fig. 3.46

Deltoid muscle (→ Figs 3.42, 3.45–3.51)

This muscle covers the anterior, posterior and lateral aspect of the head of the humerus. The following points are located either on the muscle or on its margins: → **S.I.-9, S.I.-10, T.B.-14, L.I.-15,** ***jianquan*** **(Ex-UE), LU-1, LU-2, LU-3, L.I.-14**.


Deltoid, posterior fibres
Scapular spine
Deltoid, lateral fibres
Acromio-clavicular joint
T.B.-14
L.I.-15
Clavicle
Anterior extremity of the acromion
Deltoid, anterior fibres
Abduct arm

Fig. 3.47


Trapezius
Acromion
Sternocleidomastoid
Clavicle
Scapular spine
Pectoralis major
Trapezius
Deltoid
Teres minor
Teres major
Triceps brachii, long head
Triceps brachii, lateral head
Latissimus dorsi
Biceps brachii
Triceps brachii, tendon
Brachialis

Fig. 3.48


Acromion
Trapezius
T.B.-14
Deltoid
Scapular spine
S.I.-10
S.I.-9
Triceps brachii, lateral head
Teres major
T.B.-13
Triceps brachii, long head
Biceps brachii
Triceps brachii, medial head

Fig. 3.49


Deltoid
LU-2
LU-1
Ex-UE (jianqian/ jianneiling)
LU-3
L.I.-14
Biceps

Fig. 3.50


Clavicle
L.I.-15
LU-2
Deltoid
Infraclavicular fossa
Ex-UE (jianqian/ jianneiling)
LU-1
Pectoralis major, clavicular head
LU-3
Triceps brachii
L.I.-14
Biceps brachii

Fig. 3.51


Biceps brachii
Tendon of the biceps brachii
Cubital crease
LU-5
P-3
HE-3

Fig. 3.52


Biceps brachii
Triceps brachii, medial head
Aponeurosis of the biceps brachii
P-3
HE-3
LU-5
Medial epicondyle
Tendon of the biceps brachii
Palmaris longus
Flexor carpi radialis
Brachioradialis
Flexor carpi ulnaris
Flexor digitorum superficialis

Fig. 3.53

3.3.2 Elbow

Elbow, tendon of the biceps muscle (→ Figs 3.52, 3.53)

The anterior aspect of the elbow is marked by the cubital crease, extending from the lateral to the medial epicondyle of the humerus. It is divided by the tendon of the biceps muscle. → **L.I.-11** and → **LU-5** are located lateral to the tendon while → **P-3** and → **HE-3** are located medial to it.

Lateral and medial epicondyles of the humerus (→ Figs 3.53, 3.55, 3.56)

The lateral and medial epicondyles of the humerus form the lateral aspects of the elbow. The olecranon is located between them, on the posterior aspect of the elbow. The medial epicondyle is the origin of the extensor muscles of the wrist joint, while the flexor muscles originate at the medial epicondyle.


90°
L.I.-11
Lateral epicondyle
Olecranon

Fig. 3.54

Olecranon (→ Figs 3.55, 3.56)

The olecranon forms the tip of the elbow. Located in the ulnar sulcus, between the medial epicondyle and the tip of the olecranon, is → **S.I.-8**, while → **T.B.-10** is located in a depression proximal to the olecranon.

3.3.3 Forearm and Hand

For locating points on the forearm, it is important to note whether the arm is in a pronated or supinated position, since this can have a considerable effect on the relative location of some points (see also location details of specific points). For example, in supination the line connecting → **L.I.-5** and → **L.I.-11** runs along the lateral border of the forearm, while in pronation it traverses the forearm.


Lateral epicondyle of the humerus
T.B.-10
S.I.-8
Medial epicondyle of the humerus
Olecranon

Fig. 3.55


Brachialis
Brachioradialis
Extensor carpi radialis longus
L.I.-11
Lateral epicondyle
Extensor digitorum
Triceps brachii, lateral head
Triceps brachii, medial head
Tendon of the triceps brachii
T.B.-10
Olecranon
Flexor carpi ulnaris
Extensor carpi ulnaris

Fig. 3.56


Radius
Ulna
Styloid process of the radius
Styloid process of the ulna
Scaphoid
Triquetrum
Hamatum

Fig. 3.57 Wrist joint, posterior view


Ulna
Distal radioulnar joint
Radius
Styloid process of the radius
Styloid process of the ulna
Lunate
Pisiform

Fig. 3.58 Wrist joint, anterior view

Styloid process of the radius (Figs 3.57, 3.58)

The styloid process forms a flat mound on the anterior and lateral aspect of the distal end of the radius. An oblique groove can be palpated at the transition from the process to the shaft of the radius. This is the location of LU-7. LU-8 is located slightly more distally and anteriorly, at the border of the process.

Styloid process of the ulna (Figs 3.57, 3.58)

The styloid process of the ulna is located at the distal end of the ulna, forming a distinct prominence. With the elbow flexed and the forearm in a supinated position, a small groove becomes palpable (sliding groove of the tendon of the extensor carpi ulnaris muscle). This is the location of S.I.-6.


Wrist joint space
Abductor pollicis longus
Brachioradialis
1,5 cun
Abductor pollicis longus
Radial artery
LU-8
1 cun
LU-9
Wrist joint space
Carpal bones
S.I.-6
Styloid process of the ulna

Fig. 3.59

Lumbosacral junction

Following orientation in the lumbar region with the help of the iliac crests (→ Iliac crest), the lumbosacral joint can be located by counting the spinous processes in an inferior direction. It can generally be felt as a marked 'kink' or depression, followed by the smaller spinous processes of the slightly convex median sacral crest directly below.

Caution: Note that (according to the literature in up to 15% of cases) there can be lumbarization of the 1st sacral vertebra or sacralization of L5. In these cases there will be either four or six lumbar vertebrae.

Posterior superior iliac spine (PSIS) (→ Figs 3.73, 3.74)

Another important landmark on the lower back is the posterior superior iliac spine (PSIS), which forms the posterior end of the iliac crest lateral to the upper sacral region. The PSIS can often be identified by two superficially visible dimples. It is best located by palpating from an inferior in a superior direction. If the dimples are not visible, they can be located by palpating 3 cun from the rima ani in a superior and lateral direction at an angle of 45°, until a marked bony ridge can be felt.

Generally, the PSIS is located at the level of the space between the 1st and 2nd sacral foramina, so that → **BL-27** is located directly medial or slightly superior and medial to the PSIS, while → **BL-28** is located just inferior and medial to the PSIS.



Fig. 3.73



Fig. 3.74


Median sacral crest
Sacral foramina
Sacral hiatus

Fig. 3.75


Sacral crest
BL-31
BL-32
BL-33
BL-34
Fingers on the 1st to 4th sacral foramina
Sacral hiatus

Fig. 3.76

3.4.4 Sacrum and Sacroiliac Joint

Sacrum (→ Figs 3.75, 3.76)

On the sacrum, landmarks for palpation are the median sacral crest and the sacral hiatus as well as the sacral foramina on its lateral aspects.

Sacral crest (→ Figs 3.74, 3.75)

The sacral crest is formed by the narrow, irregular spinous processes, which can be palpated on the sacral midline.

Sacral hiatus (→ Figs 3.75, 3.76)

The sacral hiatus can be palpated as a U-shaped depression at the inferior end of the sacral crest. → **Du-2** is located on the midline, just inferior to it. Both the sacral hiatus and the greater trochanter (→ Lower extremity) are reference points for locating → **G.B.-30.**

Sacral foramina (→ Figs 3.75, 3.76)

The sacral foramina are located between the lumbosacral joint and the sacral hiatus and can usually be palpated. They are in most cases evenly spaced and lie approximately 1 finger-width lateral to the midline, with the distance decreasing in a distal direction. The foramina are the location of → **BL-31–BL-34.**


Fingers on the 1st to 4th sacral foramina
Sacral hiatus
Du-2

Fig. 3.77


Highest prominence of the greater trochanter
Sacral hiatus
2/3
G.B.-30
1/3

Fig. 3.78

Iliosacral joint (→ Figs 3.80, 3.81)

The iliosacral joint can be palpated bilaterally as a shallow groove between the sacrum, the PSIS (see above) and more inferiorly located ilial structures. → **BL-26–BL-29** are located in this area.


Spinous process L3
Level of the iliac crests
Spinous process L4
Spinous process L5
BL-26
Midline
BL-27
1.5 cun
1
2
PSIS
BL-28
PSIS
1
2
BL-28
3
4
sacral foramina
BL-29
Midline

Fig. 3.79


Ilium
Iliosacral joints
PSIS
Sacrum

Fig. 3.80


Iliosacral joint
Ilium
Sacrum

Fig. 3.81

3.5 Anterior and Lateral Aspect of the Thorax and Abdomen

Clavicle (→ Figs 3.82, 3.86)

The clavicle forms the connection between the shoulder girdle and the thorax. It separates the major and minor supraclavicular fossae with → **ST-11, ST-12** and ***jingbi*** (Ex-HN) from the ribcage. Located on the lower border of the clavicle are → **ST-13** (at its midpoint) and → **KID-27** (2 cun lateral to the midline).

Suprasternal fossa (→ Fig. 3.82)

The suprasternal fossa forms a depression superior to the sternum between the sternoclavicular joints. It is the location of → **Ren-22**.

Ribs (→ Figs 3.83, 3.86)

For anatomical orientation of the ribs, the midsection of the clavicle is a good starting point. The first rib lies directly below the clavicle, forming a narrow bow. It articulates with the manubrium just inferior to the sternoclavicular joint.

Please note the following when palpating the ribs and intercostal spaces (ICS) and locating the respective acupuncture points:

- From their articulation with the sternum, the ribs run initially horizontally or in a gentle curve in an inferior direction, while at the lateral aspect of the thorax, they assume a superior direction towards the posterior aspect of the body.
- Inferior to the 4th/5th intercostal spaces, the medial sections of the ribs merge with the costal cartilage, so that the intercostal spaces do not extend very far medially. Therefore it is necessary to palpate somewhat more laterally.


Minor supraclavicular fossa
Suprasternal fossa
Major supraclavicular fossa
Cavicle
ST-12
Ren-22
ST-11

Fig. 3.82


Manubrio-sternal synchondrosis
Ren-21
Ren-17
4th ICS
Sternocostal angle
ST-18

Fig. 3.83


Ex-HN (jingbi)
1 cun

Fig. 3.84A


KID-27
KID-26
1st rib

Fig. 3.84C



Fig. 3.84B


Suprasternal fossa
Ren-22

Fig. 3.84D

1st rib, 1st intercostal space (→ Fig. 3.86)

By palpating parasternally in an inferior direction, the first rib can generally be felt directly below the clavicle. Here, → **KID-27** is located 2 cun lateral to the anterior midline. Below follows the first intercostal space, then the second rib and so on. → **Ren-20** is located on the anterior midline, at the level of the first intercostal space, → **Ren-21** is located slightly superior to it.

2nd rib, manubriosternal synchondrosis (manubriosternal junction) (→ Figs 3.83, 3.86)

The synchondrosis is usually a clearly defined transverse bony structure on the superior section of the sternum, level with the articulation of the second rib. Directly below the synchondrosis is the 2nd intercostal space from where subsequent ribs and intercostal spaces can be counted by palpation.

Laterosuperior aspect of the thorax and coracoid process (→ Fig. 3.87)

The laterosuperior aspect of the thorax is bordered by the clavicle and the deltoid muscle with the coracoid process deep to the latter. The deltopectoral triangle can be located by palpating from the end of the anterior axillary fold along the border of the deltoid muscle towards the shoulder and the lower border of the clavicle. Here, in the centre of the triangle, lies → **LU-2**. Laterally, the triangle is bordered by a clearly palpable bony structure, the coracoid process. In order to distinguish the process from the lesser tubercle of the humerus, the arm is rotated externally with the elbow flexed at the same time. While the process will remain fixed, the tubercle will follow the movement. → **LU-1** is located slightly superior and lateral to → **LU-2** and medial to the lower border of the coracoid process. The contours of the deltoid muscle and the deltopectoral triangle can be emphasised through muscle flexion, for example by pressing the hands against each other in front of the chest.


KID-27
KID-26
1st rib
Ren-21
Ren-20
Ren-21
Ren-20

Fig. 3.85


C6
T1
Coracoid process
Glenoid cavity
Clavicle
Acromion
1st rib
2nd rib
3rd rib
Scapula
4th rib
Sternum
6th rib
7th rib
8th rib
10th rib
11th rib
T12
12th rib
L1

Fig. 3.86


Minor tubercle
of the humerus
Coracoid
process
Deltopectoral
triangle
LU-2
Clavicle
LU-1

Fig. 3.87



Fig. 3.88



Fig. 3.89



Fig. 3.90

Midclavicular line (→ Fig. 3.88)

The midclavicular line provides a further tool for reference on the upper thorax. It is an imaginary line that runs from the midpoint of the clavicle to the nipple. Since in most cases the nipple lies somewhat more laterally than the clavicular midpoint, the line tends to have a slightly oblique pathway. → **ST-13** to **ST-16** are all located on the line.

Nipple (→ Fig. 3.88)

In men, the nipple is located in the 4th intercostal space, lateral to the midline, while in women, the location can vary depending on the shape of the breast. → **ST-17** is located on the nipple.

Mamillary line (→ Fig. 3.88)

The mamillary line is an imaginary line for orientation on the mediolateral thorax and abdomen. It runs vertically from the nipple in an inferior direction. The points → **ST-18, LIV-14** and **G.B.-24** are all located on this line.

Sternocostal angle, xiphoid process and umbilicus (→ Figs 89, 3.91)

The lower borders of the ribcage unite at the lower sternal border, forming the sternocostal angle. This angle and the umbilicus are the two major anatomical landmarks for point location on the upper abdomen.

Caution: It is important not to mistake the sternocostal angle for the tip of the xiphoid process. The latter is attached to the sternum at the sternocostal angle, projecting inferiorly towards the abdomen. For definite identification, palpate along the costal cartilage in a superior direction to where it meets the sternocostal angle. This is the location of → **Ren-16**.

Axillary line (→ Fig. 3.92)

The axillary line is an imaginary line for orientation on the lateral aspect of the thorax and abdomen. It runs vertically from the middle of the axilla in an inferior direction. Both → **G.B.-22** and **SP-21** are located on this line.

Free end of the 11th rib (→ Figs 3.91, 3.92)

The free end of the 11th rib can be palpated below the costal cartilage, at the transitional zone from the thorax to the abdomen. Location tip: the patient places his/her flexed elbow (90° angle) alongside his/her thorax. The tip of the olecranon will then usually be close to the free end of the 11th rib. → **LIV-13** is located below its anterior lower border.


Manubriosternal synchondrosis
Coracoid process
2nd rib
Sternocostal angle
Xiphoid process
11th rib
Free end of the 12th rib
Free end of the 11th rib

Fig. 3.91


G.B.-22
4th ICS
5th ICS
6th ICS
SP-21
Axillary line
11th rib
LIV-13

Fig. 3.92

Anterior superior iliac spine (ASIS) (→ Figs 3.93–3.95)

By palpating along the iliac crest in an anterior and inferior direction, the anterior superior iliac spine (ASIS) is reached at the lateral end of the inguinal groove. The ASIS is felt as a distinct bony ridge. → **G.B.-27** is located anterior to it, while → **G.B.-28** is located slightly more inferiorly and medially.


Umbilicus
(Ren-8)
ASIS
KID-15
Ren-6
G.B.-27
ST-28
Ren-2
ST-30
SP-12
Symphysis

Fig. 3.93


G.B.-27
Anterior superior iliac spine
0.5 cun
G.B.-28

Fig. 3.96


Anterior superior iliac spine

Fig. 3.94


Posterior superior iliac spine
Anterior superior iliac spine

Fig. 3.95

Pubic symphysis, umbilicus (→ Fig. 3.98)

The upper border of the pubic symphysis is an important orientation point for point location on the lower abdomen. The distance between the centre of the umbilicus and the upper border of the symphysis can be divided into 5 proportional cun, which can differ significantly from the patient's finger cun (→ Chapter 2). → **Ren-2** is located on the anterior midline and on the upper border of the pubic symphysis.

3.6 Lower Extremity

Greater trochanter (→ Fig. 3.99)

The greater trochanter forms a distinct, projecting bony structure on the hip area. It is one of the endpoints on an imaginary line connecting it with the sacral hiatus. Located on this line is → **G.B.-30**, a third of the distance from the greater trochanter. Another line connecting the greater trochanter and the anterior superior iliac spine (ASIS) is used for locating → **G.B.-29**.


Ren-2
Symphysis

Fig. 3.97


L4
Anterior superior iliac spine (ASIS)
Sacroiliac joint
Greater trochanter
Symphysis pubis, interpubic disc

Fig. 3.98


Anterior superior iliac spine (ASIS)
G.B.-29
Greater trochanter
G.B.-30

Fig. 3.99


ST-34
'Eyes of the knee'
Patellar tendon
Head of the fibula
G.B.-34
SP-9
Ex-LE-4 (*neixiyan*)
ST-35
Medial condyle of the tibia

Fig. 3.100


Vastus lateralis
Vastus medialis
Patella
Medial condyle of the femur
'Eye of the knee'
Head of the fibula
'Eye of the knee'
Patellar ligament

Fig. 3.101

3.6.1 Knee Region

For locating and needling points in the knee region, the patient should be in a relaxed supine position, with the knees slightly flexed and supported by pillows. This opens up the knee joint and allows for better palpation of the eyes of the knees. A prone position with a support below the feet and ankles is recommended for treating points in the popliteal crease.

Patella (→ Figs 3.100, 3.101)

The upper patellar border marks the location of → **SP-10** as well as of → **ST-32** to **ST-34**.

Eyes of the knee (→ Figs 3.100, 3.101)

The eyes of the knee are formed by the depressions on either side of the patellar tendon at the level of the lower patellar border. The lateral eye corresponds to the location of → **ST-35**, the medial eye is the location of the extra point → **Ex-LE-4** (*neixiyan*).

Head of the fibula (→ Figs 3.100, 3.101)

The head of the fibula forms a further important reference point inferior to the lateral aspect of the knee joint. For locating → **G.B.-34**, find the head of the fibula (approximately where the seam of a pair of trousers would be) and hold it with two fingers. By sliding downward, the anterior finger will 'drop' into the depression anterior and inferior to the head of the fibula, which marks the location of → **G.B.-34**.


2 cun
2 cun
SP-10
ST-32
3 cun
ST-33
6 cun
3 cun
Upper patellar border
ST-33
6 cun
3 cun
Upper patellar border

Fig. 3.102

Tibial shaft and medial condyle of the tibia (→ Fig. 3.103)

Below the medial aspect of the knee joint, the transition from the medial condyle of the tibia to the tibial shaft marks the location of → **SP-9**. This transition is best located by palpating in a superior direction along the posterior border of the medial aspect of the tibia. When using a knee roll, be aware that the soft tissue around this area may be pushed anteriorly, hindering palpation.


Femur
Tibia
SP-9

Fig. 3.103


Pes anserinus
Medial condyle of the tibia
Gastrocnemius
SP-9

At the junction of the shaft and medial condyle of the tibia

Fig. 3.104


KID-7
Highest prominence of the medial malleolus
Achilles tendon
KID-3
SP-5
KID-4
KID-6

Fig. 3.105


Tibia
Fibula
Medial malleolus
Lateral malleolus
Talus
Achilles tendon
Calcaneus

Fig. 3.106

3.6.2 Ankle and Foot

Highest prominence of the medial/lateral malleolus (→ Figs 3.105, 3.106)

Please note: The highest prominence of the malleolus does not refer to its lower border, but literally to its most protruding tip. The prominences are important reference points for the lower leg and ankle. → **Ex-LE-8** (*neihuajian*) is located on the highest prominence of the lateral malleolus, while → **Ex-LE-9** (*waihuajian*) is its medial counterpart.

Please also note: Contrary to some textbooks, the lateral and medial prominences are anatomically not located at the same level. There is approximately a 1 cun (→ Chapter 1, Fig. 1.2) difference in level. Thus, → **BL-60** and → **KID-3** are not located directly opposite each other, but rather occupy a comparable position.


Highest prominence of the medial malleolus
Ex-LE-8
Highest prominence of the lateral malleolus
Ex-LE-9
BL-60

Fig. 3.107

Joint space on the anterior ankle (→ Figs 3.108, 3.109)

The joint space on the anterior aspect of the ankle (between the malleoli) is best palpated by passively flexing and extending the foot. → **LIV-4** and → **ST-41** are both located here.


Tendon of the tibialis anterior
Ankle joint space
ST-41
LIV-4

Fig. 3.108


Tibia
Fibula
Trochlea tali
Talocrural joint
Medial malleolus
Subtalar joint
Lateral malleolus

Fig. 3.109


Tendon of the gastrocnemius
Medial malleolus
Calcaneal tendon (Achilles tendon)
Calcaneal tuberosity
Lateral malleolus

Fig. 3.110


Achilles tendon
Highest prominence of the lateral malleolus
Tuberosity of the 5th metatarsal bone
BL-59
BL-62
BL-60
BL-64
BL-63

Fig. 3.111


Talus
Navicular
Intermediate cuneiform
Lateral cuneiform
Metatarsal bones
Phalanges
Calcaneus
Cuboid
BL-63
BL-64
Tuberosity of the 5th metatarsal bone

Fig. 3.112

Achilles tendon (→ Fig. 3.110)

On the distal aspect of the lower leg and on the heel, the Achilles tendon defines the location of → **KID-3, KID-4**, and **KID-7** on its medial aspect and of → **BL-59** and **BL-60** on its lateral aspect.

Tuberosity of the 5th metatarsal bone (→ Figs 3.111, 3.112)

The tuberosity at the proximal end of the 5th metatarsal bone is the most palpable orientation point on the lateral aspect of the midfoot. → **BL-63** is located in the depression proximal to the tuberosity, while → **BL-64** is located in the depression distal to it, at the junction of the head and the shaft.


Highest prominence of the lateral malleolus
KID-3
Achilles tendon
Highest prominence of the lateral malleolus
KID-3
KID-4
KID-5
0.5 cun
KID-7
2 cun

Fig. 3.113

Base of the 1st metatarsal bone (→ Figs 3.114, 3.115)

When palpating along the medial aspect of the midfoot in a proximal direction, the proximal end (base) of the 1st metatarsal bone forms the first distinct prominence. → **SP-4** is located distal to this bony orientation point, at the junction of the shaft and the base.


Navicular tuberosity
Base of the 1st metatarsal bone
SP-4
KID-2

Fig. 3.114

Navicular tuberosity (→ Fig. 3.115)

When palpating along the medial side of the foot, past → **SP-4** and the base of the 1st metatarsal bone, a further bony structure can be clearly felt. This is the navicular tuberosity, where → **KID-2** is located.


Navicular
Medial cuneiform
Metatarsal bones
Proximal phalanges
Distal phalanges
Medial phalanges
Base of the 1st metatarsal bone
Navicular tuberosity
Calcaneus

Fig. 3.115

4 Acupuncture Points of the Twelve Primary Channels

Claudia Focks, Ulrich März

4.1 The Lung Channel System – Hand-*taiyin* (*shou tai yin jing luo*)

4.1.1 The Lung Primary Channel (*shou tai yin jing*)


LU-7
L.I.-1
LU-1
3
4
5
6
7
LU-11

Pathway

The internal section of the Lung primary channel originates in the Middle Burner in the region of the Stomach (*wei*)

- ➡ descends to connect with the Large Intestine (*dachang*), its paired *fu*-Organ
- ➡ curves upwards again to the Stomach (*wei*)
- ➡ penetrates the diaphragm
- ➡ enters the Lung (*fei*), its pertaining *zang*-Organ
- ➡ ascends to the throat region
- ➡ and curves towards the lateral thoracic region.


Anterior midline
LU-2
6 Cun
LU-1
Axillary fold
1
2
3
4
5
6
7
8
LU-3
LU-4
Cubital crease 9
Cun
LU-5
1
2
3
4
5
6
7
8
9
10
11
LU-6
Wrist crease 12
Cun
LU-7
LU-8
LU-9


LU-11
LU-10
LU-7
LU-8
LU-9

The Lung primary channel emerges at LU-1 (*zhongfu*) on the lateral thoracic wall at the level of the first intercostal space

- ➡ travels along the anterolateral aspect of the upper arm and forearm
- ➡ ends at LU-11 (*shaoshang*) on the thumb, at the radial aspect of the corner of the nail.

A branch separates from the primary channel at LU-7 (at the styloid process of the radius) and travels along the radial side of the index finger to its tip, where it connects with → **L.I.-1** (*shangyang*) (hand Yin–Yang connection of the first great circuit).

Clinical importance (→ 1.2)

Exterior (***biao***) signs and symptoms: Fever, aversion to cold, nasal blockage, headache, pain in the region of the thorax, shoulder and back, pain with cold sensations along the channel
Interior (***li***) or *zangfu*-Organ signs and symptoms: Cough, asthma, wheezing, dyspnoea, shortness of breath, fullness and tightness of the chest, expectoration of phlegm, dry throat, changed colour of the urine, irritability, heat sensation in the palms, abdominal fullness and distension, diarrhoea
Excess (***shi***): Shoulder and back pain, Wind-Cold attack with spontaneous sweating, frequent urination, yawning
Deficiency (***xu***): Shoulder and back pain with aversion to cold, shortness of breath, changed colour of urine

Connections of the Lung primary channel (→ 1.2)

Connections with other channels

Large Intestine primary channel (*shou yang ming jing*)

Connection: Hand Yin–Yang connection of the first great circuit
Location: LU-7 → L.I.-1 (on the hand). A branch of the Lung primary channel separates at **LU-7** (*lieque*) and connects with the Large Intestine primary channel at **L.I.-1** (*shangyang*), according to some authors also with → **L.I.-4** (*hegu*).
Circulation: Circadian (according to the Organ clock)
Importance: Interior–Exterior relationship

Spleen primary channel (*zu tai yin jing*)

Connection: Paired according to the six channel theory (hand–foot pairing): *tai yin* (Yin axes of the first great circuit)
Location: SP-20 → LU-1 (on the thorax). A branch of the Spleen primary channel separates at → **SP-20** (*zhourong*) and connects with the Lung primary channel at → **LU-1** (*zhongfu*).
Circulation: Non-circadian (not according to the Organ clock)
Importance: Above–below relationship

Liver primary channel (*zu jue yin jing*)

Connection: Deep Yin–Yin connection
Location: LIV → LU (on the thorax). An internal branch of the Liver primary channel emerges at the Liver, passes the diaphragm and spreads inside the Lung (*fei*), forming a network with the Lung primary channel.
Circulation: Circadian (according to the Organ clock)
Importance: Closes the circle of the first great circuit of the Nutritive Qi (*ying qi*, → 1.1.4)

Ren mai

Connection: *Ren mai* → Lung primary channel
Importance: Closes the circle of the second circuit of the Nutritive Qi (*ying qi*, → 1.1.4). The Lung primary channel as well as the great circuit (circulation through the 12 primary channels) receives Qi from the small circuit (*ren mai – du mai*).

Connections to the *zangfu*-Organ systems

Lung (*fei*), **Large Intestine (*dachang*)**, Stomach (*wei*)

4.1.2 The Lung Divergent Channel (*shou tai yin jing bie*)



Pathway

The Lung divergent channel separates from the Lung primary channel in the axillary region

- travels anteriorly to → **G.B.-22** (*yuanye*) on the midaxillary line, 3 cun inferior to the axilla
- enters the thoracic region
- disperses in the Lung (*fei*), its pertaining *zang*-Organ
- descends to the Large Intestine (*dachang*), its paired *fu*-Organ
- ascends again and emerges in the region of the supraclavicular fossa at → **ST-12** (*quepen*)
- traverses the neck in a cranial direction and connects with the Large Intestine primary channel at → **L.I.-18** (*futu*) at one of the six *he*-confluences* (L.I./LU as 6th confluence. → 1.3).

There exist variations regarding the channel pathway due to differing interpretations of the *Ling Shu* (→ Solinas et al. 1998).

---

* According to some authors the 6th confluence is localised at → **ST-12** (*quepen*).

Clinical importance

- Strengthens the connection between the Lung and the Large Intestine (*zangfu*-Organ systems). Points on the Large Intestine primary channel can therefore be used for disorders of the Lung, and vice versa points on the Lung primary channel can treat disorders of the Large Intestine.
- Creates a network between the Lung primary channel and the neck region at the confluent point ➞ **L.I.-18**: thus LU points such as ➞ **LU-10** or ➞ **LU-11** may be used to treat the neck region.

4.1.3 The Lung Sinew Channel (*shou tai yin jing jin*)



Pathway

The Lung sinew channel

➡ begins on the thumb at **LU-11** (*shaoshang*), at the radial aspect of the corner of the nail

➡ spreads along the radial aspect of the thumb and the 1st metacarpal bone as well as the thenar eminence

➡ meets **LU-9** (*taiyuan*) and binds (*jie*) at the radial wrist joint space

➡ travels proximally along the anterolateral aspect of the forearm

➡ reaches the elbow at **LU-5** (*chize*) and binds (*jie*) at the biceps tendon

➡ follows the biceps brachii muscle and the lateral portion of the deltoid muscle

➡ binds (*jie*) at the anterior shoulder region near the acromioclavicular joint

➡ continues to the axilla and meets the other hand Yin sinew channels (P, HE) at ➞ **G.B.-22** (*yuanye*) and binds (*jie*) there

➡ continues deep to the pectoralis major muscle and enters the supraclavicular fossa at ➞ **ST-12** (*quepen*)

➡ courses to ➞ **L.I.-15** (*jianyu*) and returns to ➞ **ST-12** (*quepen*)

➡ penetrates the supraclavicular fossa and disperses in the thoracic and hypochondriac region and the diaphragm (➞ Fig.)

Clinical importance

Pathology: Stiffness, cramps and pain along the sinew channel. *Xi fen*: spasms and pain in the thorax and hypochondriac region. In severe cases formation of nodules below the right lateral costal region and distension along the lateral costal region.

Indication: Mainly for *bi*-syndromes (painful obstruction syndrome) along the LU channel.

The area covered by the Lung sinew channel is larger than that covered by the Lung primary channel. This explains why the indications of points on the Lung primary channel include disorders and diseases of the thoracic and hypochondriac region.

4.1.4 The Lung *luo*-Connecting Vessel System (*shou tai yin luo mai*)



Pathway

The Lung *luo*-connecting channel system separates from the Lung primary channel at **LU-7** (*lieque*) (➞ 8.1.2) and forms a three-dimensional reticular network, dividing into multiple branches and sub-branches (*sun luo*, *fu luo*, *xue luo* ➞ 1.5) within the surrounding tissue.

➡ Horizontal divisions course to the Interiorly–Exteriorly paired Large Intestine primary channel; according to some schools (for example Van Nghi, ➞ Appendix) they travel as a transverse Lung *luo* vessel to the *yuan*-source point ➞ **L.I.-4** (*hegu*).

➡ A longitudinally orientated division spreads on the palm and thenar eminence.

Clinical importance (→ 8.1.2)

Pathology

- **Excess (*shi*)**: Hot and burning sensations in the palms and the wrist joints
- **Deficiency (*xu*)**: Yawning, shortness of breath, frequent urination, enuresis

4.1.5 Cutaneous Region (*tai yin pi bu*)

See description and figures → 1.6.

4.1.6 Points of the Lung Primary Channel (Overview)

Specific points according to function

- ***Yuan*-source point (→ 8.1.1): LU-9** (*taiyuan*) 🟦🟦
- ***Luo*-connecting point (→ 8.1.2.): LU-7** (*lieque*) 🟦🟦
- ***Xi*-cleft point (→ 8.1.3): LU-6** (*kongzui*)
- **Pertaining Back-*shu* point (→ 8.1.4): BL-13** (*feishu*) 🟦■
- **Pertaining Front-*mu* point (→ 8.1.5): LU-1** (*zhongfu*) 🟦■
- **Five *shu*-transporting points (→ 8.1.6):**
  jing-well point (Wood): **LU-11** (*shaoshang*) 🟦■
  ying-spring point (Fire): **LU-10** (*yuji*)
  shu-stream point (Earth), tonification point: **LU-9** (*taiyuan*) 🟦🟦
  jing-river point (Metal), *ben* point: **LU-8** (*jingqu*) 🟦■
  he-sea point (Water), sedation point: **LU-5** (*chize*) 🟦■
- **Influential *hui*-meeting point (→ 8.1.7) of the vessels: LU-9** (*taiyuan*) 🟦🟦
- **Opening point (→ 8.1.8) of the *ren mai*: LU-7** (*lieque*) 🟦🟦
- ***Jiaohui*-meeting points (→ 8.1.10):**
  - with the SP primary channel: **LU-1** (*zhongfu*) 🟦■
  - of other channels with the LU channel: –
- **Gao Wu Command point (→ 8.1.11) for the occiput and nape: LU-7** (*lieque*) 🟦🟦
- **Window of Heaven point (→ 8.1.12): LU-3** (*tianfu*)
- **Ma Dan Yang Heavenly Star points (→ 8.1.14): LU-7** (*lieque*) 🟦🟦
- **Sun Si Miao Ghost point (→ 8.1.15): LU-11** (*shaoshang*) 🟦■

Points according to region

- **Local points (→ 8.2.1):** Lung – **LU-1** (*zhongfu*) 🟦■; elbow – **LU-5** (*chize*) 🟦■; wrist – **LU-7** (*lieque*) 🟦🟦
- **Adjacent points (→ 8.2.1):** hands – **LU-7** (*lieque*) 🟦🟦
- **Distal points (→ 8.2.1):** occiput – **LU-7** (*lieque* 🟦🟦); throat – **LU-10** (*yuji*) – **LU-11** (*shaoshang*); Lung – **LU-5** (*chize*) 🟦■, **LU-7** (*lieque*) 🟦🟦; shoulder – **LU-7** (*lieque*) 🟦🟦

Specific points according to the course of the channel (in numeric order)

- **LU-1** (*zhongfu* 🟦■): associated Front-*mu* point (→ 8.1.5), *jiaohui*-meeting point with the SP channel (→ 8.1.10)
- **LU-3** (*tianfu*): Window of Heaven point (→ 8.1.2)
- **LU-5** (*chize*) 🟦■: *he*-sea point (Water) (→ 8.1.6); sedation point; distal point of the Lung (→ 8.2.1)
- **LU-6** (*kongzui*): *xi*-cleft point (→ 8.13)
- **LU-7** (*lieque*) 🟦🟦: *luo*-connecting point (→ 8.1.2); opening point (→ 8.1.8) of the *ren mai*; Gao Wu Command point (→ 8.1.11) of the nape and occiput; Ma Dan Yang Heavenly Star point (→ 8.1.14); distal point for the occiput, shoulder and Lungs (→ 8.2.1); adjacent point for the hands (→ 8.2.1)
- **LU-8** (*jingqu*): *jing*-river point (Metal) (→ 8.1.6); *ben* point (Five Phase point)
- **LU-9** (*taiyuan*) 🟦🟦: *yuan*-source point (→ 8.1.1), hui-meeting point (→ 8.1.7) of the vessels; *shu*-stream point (Earth) (→ 8.1.6); tonification point
- **LU-10** (*yuji*): *ying*-spring point (Fire) (→ 8.1.6); distal point for the neck (→ 8.2.1)
- **LU-11** (*shaoshang*) 🟦■: Sun Si Miao Ghost point (→ 8.1.15); *jing*-well point (Wood) (→ 8.1.6); distal point for the neck

Central Residence ZHONGFU LU-1


Minor tubercle of the humerus
Coracoid process
Deltopectoral triangle
LU-2
Suprasternal notch
1 cun
Midline
6 cun
LU-1


Midline
Clavicle
1 cun
LU-1


ST-9
12
Ren-22
KID-27
14
26
20
SP-20
25
19
19
16
24
18
17

Location

6 cun lateral of the anterior midline and approximately 1 cun below → **LU-2,** slightly medial to the lower border of the coracoid process.

How to find

First, locate → **LU-2** in the deltopectoral triangle, which is bordered superiorly by the clavicle and laterally by the coracoid process (within the deltoid muscle). From there, palpate along the border of the deltoid for 1 cun and there locate **LU-1** slightly medial to the lower border of the deltoid on the thoracic wall, approximately 6 cun lateral to the midline. For orientation: when externally rotating the arm with the elbow flexed at the same time, the coracoid process will remain static, while the minor tuberculum of the humerus will follow the movement. → **SP-20** is also located 6 cun lateral to the midline on the level of the 2nd intercostal space. Located approximately on the same level are → **Ren-20,** → **KID-26** and → **ST-14**.

Needling

0.5–1 cun obliquely in a cranial (approximately 45°) and lateral direction towards the coracoid process.

Actions/Indications

- Regulates and descends the Lung Qi
- Clears Heat in the Upper Burner, transforms Phlegm
- Regulates the water passages
- Moves Qi locally and in the sinew channel

Special features

Front-*mu* point of the Lung, meeting point with the Spleen channel, entry point. Important point for disorders of the Lung.


Clavicle
L.I.-15
LU-2
Deltoid
Infraclavicular fossa
Jianqian
LU-1
Pectoralis major, clavicular portion
LU-3


Ren-21
Ren-20

LU-2 *Cloud Gate* YUNMEN

Location

6 cun lateral to the anterior midline, below the clavicle, in the centre of the deltopectoral triangle.

How to find

Find the angle formed by the lateral lower border of the clavicle and the coracoid process (within the deltoid muscle). Locate **LU-2** at the junction of the clavicular insertions of the deltoid and pectoralis muscles (deltopectoral triangle), in the centre of a clearly palpable depression in the thoracic wall, 6 cun lateral to the anterior midline.

→ **ST-13** is also located at the lower border of the clavicle, 4 cun lateral to the anterior midline or at the midpoint of the clavicle. Also located on approximately the same level are → **KID-27** (2 cun lateral to the midline) and → **Ren-21** (on the midline). → **LU-1** is located 1 cun below and in most cases slightly lateral to **LU-2**.

Needling

Obliquely to a maximal depth of 0.8 cun. No needling in a medial direction! Risk of pneumothorax!

Actions/Indications

- Clears Lung Heat, decends the Lung Qi
- Opens the channel and sinew channel
- Clears Heat from the extremities


Minor tubercle of the humerus
Coracoid process
Deltopectoral triangle
LU-2
Suprasternal fossa
1 cun
Midline
6 cun
LU-1




Ren-21
Ren-20


KID-27
KID-26
1st rib


ST-9
12
Ren-22
KID-27
14 26
20
SP-20
25
19
19
16
24
18
17


Clavicle
L.I.-15
LU-2
Deltoid
Infraclavicular fossa
Jianqian
LU-1
Pectoralis major, clavicular portion
LU-3

Heavenly Residence TIANFU **LU-3**


Anterior end of the axillary fold
3 cun
Lateral border
of the biceps muscle
LU-3


LU-2
LU-1
HE-1
P-1
P-2
LU-3
LU-4
HE-2
LU-5
P-3
HE-3
1
2
3
4
5
6
7
8
9
cun
1
2
3


Lateral border of
the biceps muscle
LU-4


2 cun
Axillary fold
P-2

Location

On the medial aspect of the upper arm, 3 cun distal to the end of the anterior axillary fold, in the groove on the lateral border of biceps brachii.

How to find

Ask the patient to flex the biceps muscle against resistance. Locate **LU-3** 3 cun below the anterior end of the axillary fold (→ 2.2) in a groove on the lateral border of biceps brachii. Sometimes, you can feel the pulse of the brachial artery here.
Or: Divide the distance of 9 cun (→ 2.2) between the end of the axillary fold and the cubital crease (→ **LU-5**) into thirds and locate **LU-3** a third of the distance from the axillary fold.
→ **LU-4** is located in the sulcus, 1 cun distal to **LU-3**. → **P-2** is located 2 cun below the axillary fold, between the two heads of the biceps brachii muscle.

Needling

Vertically 0.5–1 cun. Moxibustion is contraindicated according to some classics.

Actions/Indications

- Regulates and descends the Lung Qi
- Clears Lung Heat
- Cools the Blood and stops bleeding
- Calms the *po* (corporeal soul)
- Opens the channel and alleviates pain

Special features

Window of Heaven point

LU-4 *Clasping the White* XIABAI

Location

On the medial aspect of the upper arm, 4 cun distal to the end of the anterior axillary fold, in the depression on the lateral border of sulcus bicipitalis lateralis.

How to find

Ask the patient to flex their biceps muscle against resistance. Locate **LU-4** 4 cun below the anterior end of the axillary fold (→ 2.2) in the depression on the lateral border of the sulcus bicipitalis muscle. Sometimes you can feel the pulse of the brachial artery here. **Or quick method:** Spreading hands technique (→ 2.3.3): place the little fingers on the axillary fold and the cubital crease (at → **LU-5**) respectively (this distance corresponds to 9 proportional cun → 2.2) and determine the midpoint of this distance by joining the thumbs. Locate **LU-4** 0.5 proximal to the midpoint in the sulcus on the lateral border of the biceps muscle. → **LU-3** is also located in the sulcus, 1 cun proximal to **LU-4**.

Needling

Vertically 0.5–1 cun

Actions/Indications

- Regulates and moves Qi and Blood in the chest
- Descends the Lung Qi
- Opens the channel and alleviates pain


Anterior end of the axillary fold
4 cun
Lateral border of the biceps muscle
LU-4


LU-2
LU-1
1
2
3
4
5
6
7
8
9
cun
HE-1
P-1
P-2
LU-3
LU-4
HE-2
1
2
3
LU-5
P-3
HE-3


Lateral border of the biceps muscle
LU-3

Cubit Marsh CHIZE LU-5


Biceps tendon
LU-5

Right arm

Location

In the cubital crease, on the radial aspect of the tendon of the biceps.

How to find

By slightly flexing the forearm, the biceps tendon becomes more visible. **LU-5** is located on its radial aspect in the cubital crease. Also located in the area of the cubital crease are → **P-3** (ulnar to the tendon), → **HE-3** (at the ulnar end of the cubital crease) and → **L.I.-11** (between the radial end of the cubital crease and the lateral epicondyle).

Needling

Vertically 0.5–1 cun. Needle with the arm slightly flexed. Use bloodletting for Heat disorders. Caution: Avoid cubital vein.

Actions/Indications

- Clears Heat in the Upper Burner
- Descends the Lung Qi
- Regulates the water passages
- Opens the channel and *luo*-connecting vessels, alleviates pain

Special features

He-sea point, Water point, sedation point, distal point for the Lung, local point for the elbow. Use bloodletting for disorders of the skin and Lung due to excess and/or Heat.


Biceps brachii
Triceps brachii, medial head
Aponeurosis of the biceps brachii
P-3
HE-3
Medial epicondyle
LU-5
Tendon of the biceps brachii
Palmaris longus

Left arm, anterior aspect


Biceps tendon
Cubital crease
LU-5
P-3
HE-3


90°
L.I.-11
Lateral epicondyle
Olecranon

LU-6 *Biggest Hole* KONGZUI

Location

On the line connecting → **LU-5** (in the cubital crease) and → **LU-9** (on the wrist crease/joint space), 5 cun distal to → **LU-5** or 7 cun proximal to → **LU-9**.


LU-5
(cubital crease,
radial to the
biceps tendon)
1/2
Midpoint of the
distance
1 cun
1/2
LU-6
LU-9
(joint space, radial
to the radial artery)

How to find

The biceps tendon becomes more visible with the arm flexed. First, locate → **LU-5** radial to the biceps tendon in the cubital crease and → **LU-9** radial to the radial artery on the wrist joint space (→ 3.3.3) between the proximal row of carpals and the radius/ulna. By moving the hand, the joint space becomes more easily palpable. Next, find the midpoint of the distance between → **LU-5** and → **LU-9** using the spreading hands technique (→ 2.3.3). **LU-6** is located 1 cun proximal to the midpoint of this distance.

→ **P-4** is located more medially (between the tendons) and distally (1 cun distal to the midpoint of the distance).

Needling

Vertically 0.5–1 cun


8
9
cun
1
2
3
4
5
6
7
8
9
10
11
12
cun
HE-2
LU-5
P-3
HE-3
LU-6
P-4
P-5
LU-7
P-6
LU-8
LU-9
P-7
HE-4
HE-5
HE-6
HE-7
LU-10
P-8
HE-8
LU-11
HE-9
P-9

Actions/Indications

- Descends the Lung Qi
- Clears Lung Heat
- Cools Blood Heat, stops bleeding
- Expels Exterior pathogenic factors
- Opens the channel

Special features

Xi-cleft point


Biceps tendon
LU-5


Abductor
pollicis longus
Radial artery
LU-8
1 cun
LU-9
Joint space
Carpal bones


P-4
Tendon of the
flexor muscle
5 cun

Broken Sequence LIEQUE **LU-7**

Location

On the radial aspect of the forearm, directly above the styloid process of the radius, approximately 1.5 cun proximal to the wrist joint space (wrist crease) in a V-shaped groove.

How to find

Place the palpating forefinger on the anatomical snuffbox (→ **L.I.-5**). From there, glide proximally over the styloid process of the radius and locate **LU-7** where the finger can palpate a cleft between two tendons (brachioradialis/abductor pollicis longus). **Or:** 'Tiger mouth grip' (→ Fig. 2.6): spread the thumb and forefinger of both hands, crossing them so that the forefinger of one hand comes to rest on the styloid process of the other, but avoiding bending the wrist. **LU-7** is located directly below the tip of the forefinger in a V-shaped groove

Needling

Lift the skin above the styloid process by pinching it. Insert the needle 0.5–1 cun obliquely and proximally (reducing) or distally (tonifying). Caution: Cephalic vein.

Actions/Indications

- Supports the occiput and head
- Releases the Exterior, expels Wind, descends the Lung Qi
- Opens and regulates the *ren mai*
- Regulates the water passages
- Opens the channel and *luo*-connecting channel, alleviates pain

Special features

Luo-connecting point, opening point of the *ren mai*, Ma Dan Yang Heavenly Star point, Gao Wu command point of the occiput, exit point.


Wrist joint space
Abductor pollicis longus
1.5 cun
Brachioradialis


Styloid process of the radius


Radius
Ulna
Styloid process of the radius
Styloid process of the ulna
Scaphoid
Triquetrum
Hamate

Left hand, dorsal aspect


Tendon of extensor pollicis longus
Styloid process of the radius
L.I.-5
LU-7
Tendon of extensor pollicis brevis

Ch04.1-F10028.qxd 2/23/08 7:03 PM Page 90

LU-8 Channel Gutter JINGQU

Location

Lateral to the radial artery, 1 cun proximal to the ventral wrist joint space (most distal wrist crease).

How to find

As the location of the wrist crease varies, use the joint space (➞ 3.3.3) between the proximal row of carpals and the radius/ulna for orientation. By loosely moving the hand, the joint space is easily palpable. This is the level for palpating the radial pulse (using the finger tips, not the finger pads). ➞ **LU-9** is located on the radial side of the artery, while **LU-8** is located 1 cun proximal to ➞ **LU-9**.
➞ **L.I.-5** is located close to **LU-8**, but on the dorsal aspect of the wrist joint in the anatomical snuffbox.

Needling

0.3–0.5 cun proximally or vertically. Avoid the radial artery by gently pushing it to the side when palpating for the point. Moxibustion is contraindicated according to some classics.

Actions/Indications

- Descends the Lung Qi, alleviates cough and wheezing
- Opens the pores and expels Wind in particular
- Opens the channel, especially locally

Special features

Jing-river point, Metal point, *ben* point (Five Phases).


Abductor pollicis longus
Radial artery
LU-8
1 cun
LU-9
Joint space
Carpal bones
Radius
HE-7
Ulna
Pisiform
Styloid process of the radius


10
11
12 cun
P-5
P-6
LU-7
LU-8
LU-9
HE-4
HE-5
HE-6
HE-7
P-7
LU-10
LU-11
P-8
HE-8
HE-9
P-9


Ulna
Distal radioulnar joint
Radius
Styloid process of the radius
Styloid process of the ulna
Lunate
Pisiform

Left hand, palmar aspect


L.I.-5
Extensor tendon

Supreme Abyss TAIYUAN LU-9


Abductor pollicis longus
Radial artery
LU-8
1 cun
LU-9
Joint space
Carpal bones
HE-7
Pisiform
Radius
Ulna
Styloid process of the radius


Tendon of the flexor carpi ulnaris
Tendon sheath of the flexor carpi radialis
Abductor digiti minimi
Opponens pollicis
Flexor pollicis brevis
Abductor pollicis brevis

Left hand, palmar aspect


Tendon of the flexor carpi ulnaris
Wrist joint space
Pisiform
HE-7
P-7
LU-9

Location

On the ventral aspect of the wrist, at the level of the wrist joint space (most distal wrist crease), on the radial aspect of the radial artery and ulnar to the tendon of the abductor pollicis longus muscle.

How to find

As the location of the wrist crease varies, the ventral joint space (→ 3.3.3) between the proximal row of carpals and the radius/ulna is a more reliable landmark for orientation. By loosely moving the hand, the joint space is easily palpable. Palpate the radial artery (pulsation) on the radial side and locate **LU-9** on its radial aspect. Located on the same level are → **P-7** (between two tendons) and → **HE-7** (radial to the insertion of the tendon of the flexor carpi ulnaris on the pisiform bone).

Needling

Vertically 0.2–0.5 cun. Caution: Avoid radial artery. If the needle is pulsating (desired effect), no additional stimulation!

Actions/Indications

- Strengthens the Lung, transforms Phlegm, descends the Lung Qi
- Regulates and harmonises the vessels (relationship between *zong qi* and Blood circulation)
- Opens the channel, alleviates pain

Special features

Yuan-source point, *shu*-stream point, Earth point, tonification point, *hui*-meeting point of the vessels. Important point for tonifying the Lung Qi and Yin, especially with chronic disorders.

LU-10 *Fish Border* **YUJI**

Location

At the midpoint of the palmar border of the 1st metacarpal bone.

How to find

With the thumb relaxed, palpate the ‘belly’ of the thenar eminence from palmar to lateral (radial), then palpate the first metacarpal bone. **LU-10** is located at the midpoint of its palmar ‘border’.

→ **L.I.-4** is located on the dorsal aspect of the hand, close to the 2nd metacarpal bone.

Needling

Vertically 0.5–1 cun. Caution: Painful!

Actions/Indications

- Regulates the Lung Qi
- Cools Blood Heat
- Expels pathogenic factors from the throat
- Descends rebellious Qi
- Harmonises the Stomach and Heart

Special features

Ying-spring point, Fire point, important distal point for sore throat caused by Wind-Heat.


Metacarpal I
Mid point
LU-10


12 cun
LU-7
P-6
LU-8
LU-9
HE-4
HE-5
P-7
HE-6
HE-7
LU-10
P-8
LU-11
HE-8
HE-9
P-9


Midpoint
Metacarpal II
L.I.-4

Lesser Shang SHAOSHANG LU-11



Location

On the thumb, 0.1 cun from the radial corner of the nail.

How to find

The point is located at the junction of two tangents running along the proximal and radial border of the thumb nail, approximately 0.1 cun from the actual border of the nail.

Needling

0.1–0.2 cun vertically or obliquely in a proximal direction or prick to bleed. Avoid needling the perionychium.

Actions/Indications

- Frees the senses
- Regulates the Lung Qi
- Clears Heat (especially from the throat)
- Opens the channel

Special features

Jing-well point, Wood point, Sun Si Miao Ghost point, important distal point for sore throat caused by Wind-Heat.

4.2 The Large Intestine Channel System – Hand *yangming* (*shou yang ming jing luo*)

4.2.1 The Large Intestine Primary Channel (*shou yang ming jing*)


L.I.-1
L.I.-2
L.I.-3
L.I.-4
L.I.-5


L.I.-20
L.I.-19
Du-26
ST-4
S.I.-12
Du-14
ST-12
17
15
14
13
12
11
10
9
8
7
6
5
4
L.I.-1

To ST-37 (lower *he*-Sea point of the Large Intestine)


L.I.-16
Axillary fold
1
2
3
4
5
6
7
8
9
cun
Cubital crease
L.I.-14
L.I.-13
L.I.-12
L.I.-11
L.I.-10
L.I.-9
L.I.-8
L.I.-7
L.I.-6
L.I.-5
1
2
3
4
5
6
7
8
9
10
11
12
cun
Wrist crease
2 cun
1 cun
1 cun
3 cun
2 cun
3 cun

Pathway

The **external** part of the Large Intestine primary channel begins on the index finger at → **L.I.-1** (*shangyang*, at the radial aspect of the corner of the nail). This point is reached by a branch which separates from the Lung primary channel at → **LU-7** (*lieque*; hand Yin–Yang connection of the first great circuit). The Large Intestine primary channel runs between the first and second metacarpal bones,

- ➡ then runs proximally along the radial aspect of the forearm towards the lateral aspect of the elbow
- ➡ travels in a proximal direction along the lateral aspect of the upper arm towards the shoulder
- ➡ crosses the Small Intestine primary channel at → **S.I.-12** (*bingfeng*) in the centre of the suprascapular fossa
- ➡ continues to → **Du-14** (*dazhui*) inferior to the spinous process of the 7th cervical vertebra, where it meets with the other five Yang primary channels
- ➡ crosses the neck and enters the supraclavicular fossa at → **ST-12** (*quepen*).

Here the **internal** pathway branches off and connects with the Lung (*fei*), its paired *zang*-Organ, penetrates the diaphragm and enters the Large Intestine (*dachang*), its pertaining *fu*-Organ. From the Large Intestine (according to some authors: the Large Intestine primary channel) an **internal** branch runs in an inferior direction to → **ST-37** (*shangjuxu*) on the lateral aspect of the lower leg, the lower *he*-sea point of the Large Intestine.

Ch04.2-F10028.qxd 2/23/08 7:05 PM Page 96


L.I.-20
Cross-over to the contra-lateral side
L.I.-19
sternocleidomastoid
Level of the laryngeal prominence
3 cun
L.I.-18
1 cun
L.I.-17

The **external** branch ascends from the supraclavicular fossa, travels along the lateral aspect of the neck and traverses the cheek.

- ➡ From here another **internal** branch enters the lower gums, where it extends further.
- ➡ The **external** course of the primary channel passes → **ST-4** (*dicang*) and curves around the mouth to the upper lip, crossing to the contralateral side of the body at → **Du-26** (*renzhong*), located at the philtrum. On the contralateral side of the body, it reaches → **L.I.-19** (*kouheliao*) and terminates **contralaterally** at → **L.I.-20** (*yingxiang*) on the side of the nose.

Note: Deadman et al. (1998) mention → **Ren-24** (*chengjiang*) as additional meeting point (variant → figure). They also mention → **G.B.-5** (*xuanlu*), → **G.B.-6** (*xuanli*) and → **G.B.-14** (*yangbai*) as classic meeting points with the Large Intestine channel but these are not normally shown in illustrations of the channel.

Clinical importance (→ 1.2)

Exterior (*biao*) signs and symptoms: Fever, dryness of the mouth, thirst, a sore and swollen throat, nosebleed, toothache, red, painful eyes, stiff fingers, painful cold or painful hot swellings of the upper arm and shoulder

Interior (*li*) or *zangfu*-Organ signs and symptoms: Pain in the lower abdomen, borborygmus, diarrhoea or yellow stools with mucus, shortness of breath, dyspnoea

Excess (*shi*): Heat sensations along the channel

Deficiency (*xu*): Cold sensations and chills along the channel

Connections of the Large Intestine primary channel (→ 1.2)

With other channels

Lung primary channel (*shou tai yin jing*)

Connection: Hand Yin–Yang connection of the first great circuit
Location: LU-7 → L.I.-1 (on the hand). A branch of the Lung primary channel connects with the Large Intestine primary channel at **L.I.-1** (*shangyang*)
Circulation: Circadian (according to the Organ clock)
Importance: Exterior–Interior relationship

Stomach primary channel (*zu yang ming jing*)

Connection: Paired according to the six channel theory (hand–foot pairing): *yangming* (Yang axes of the first great circuit)
Location: L.I.-20 → (BL-1) → ST-1 (on the head)
Circulation: Circadian (according to the Organ clock)
Importance: Above–below relationship

With the *zangfu*-Organ systems

Lung (*fei*), **Large Intestine (*dachang*)**, Stomach (*wei*)

4.2.2 The Large Intestine Divergent Channel (*shou yang ming jing bie*)



Pathway

The Large Intestine divergent channel separates from the Large Intestine primary channel on the hand,

- ➡ travels along the arm to the shoulder to → **L.I.-15** (*jianyu*)
- ➡ from **L.I.-15** a **branch** runs to the thorax and branches out into the breasts
- ➡ **another branch** runs to the cervical spine at the 7th cervical vertebra, returns from there to the supraclavicular fossa, descends to the Large Intestine (*dachang*), ascends to the Lung (*fei*) and **emerges** to the Exterior at → **ST-12** (*quepen*).*

It then travels along the anterolateral aspect of the neck and connects with the Large Intestine primary channel and the Lung divergent channel at → **L.I.-18** (*futu*) at one of the six *he*-confluences[†] (here: L.I./LU as 6th confluence → 1.3).

Clinical importance

- Strengthens the connection between the Lung and the Large Intestine (*zangfu*-Organs). Points on the Large Intestine primary channel can therefore be used for disorders of the Lung, and vice versa points on the Lung primary channel can treat disorders of the Large Intestine.
- A branch of the Large Intestine divergent channel spreads (from → **L.I.-15**) across the thorax and the breasts, thus extending the actions of the points on the Large Intestine primary channel to these regions, for example for the treatment of mastitis, myalgias and thoracic pain.

---

* Some authors describe the divergent channel as travelling directly from the spine to the Large Intestine, without meeting → **ST-12** (variant → Fig.).

[†] According to some authors the 6th *he*-Confluence is located at → **ST-12** (*quepen*).

4.2.3 The Large Intestine Sinew Channel (*shou yang ming jing jin*)





Pathway

The Large Intestine sinew channel

- begins on the index finger at → **L.I.-1** (*shangyang*)
- runs along the index finger and the 2nd metacarpal bone towards the wrist, where it binds (*jie*) at → **L.I.-5** (*yangxi*)
- travels along the posterolateral aspect of the forearm
- reaches the elbow and binds (*jie*) at → **L.I.-11** (*quchi*)
- continues along the lateral aspect of the upper arm and the deltoid muscle to the shoulder, where it binds (*jie*) again at → **L.I.-15** (*jianyu*)
- from **L.I.-15** a branch spreads across the scapula and then attaches to the spine between the 7th cervical vertebra and the 5th thoracic vertebra (or between → **Du-14** (*dazhui*) and → **Du-11** (*shendao*).
- The **main branch** ascends from **L.I.-15**, crosses the supraclavicular fossa and continues from there along the lateral aspect of the neck towards the angle of the jaw where it binds (*jie*).

Here it forks into two branches:

- **One branch** runs across the zygomatic bone towards the lateral side of the nose
- **The other branch** ascends the lateral aspect of the face and anterior to the Small Intestine sinew channel, connects at → **G.B.-13** (*benshen*) with the other sinew Yang channels, crosses over the head and ends at the lower jaw on the opposite side.

Note: According to some schools of thought, the sinew channel only ends at → **L.I.-17** (*tianding*; Solinas et al. 1998).

Clinical importance

Pathology: cramps, pain, tension and stiffness along the Large Intestine sinew channel. Limited range of motion of the upper limbs and shoulders. Occipital pain, stiffness and limited range of motion.

Indication: Mainly for *bi*-syndrome (painful obstruction syndrome) along the Large Intestine channel. The area covered by the Large Intestine sinew channel is larger than that covered by the Large Intestine primary channel. This explains why the indications of points on the Large Intestine primary channel include disorders and diseases of the upper neck and thoracic region as well as of the whole face (for example frontal and temporal headaches).

4.2.4 The Large Intestine *luo*-Connecting Vessel System (*shou yang ming luo mai*)



Pathway

The **Large Intestine** *luo*-connecting channel system begins at the *luo*-connecting point → **L.I.-6** (*pianli*) (→ 8.1.2), where it branches off from the primary channel and forms a three-dimensional reticular network, dividing into numerous branches and sub-branches (*sun luo*, *fu luo*, *xue luo* → 1.5) within the surrounding tissue.

- ➡ Horizontal divisions course to the Interiorly–Exteriorly paired Lung primary channel; according to some schools (for example, Van Nghi → Appendix) they travel as a **transverse** LU *luo*-connecting vessel to the *yuan*-source point → **LU-9** (*taiyuan*).
- ➡ A **longitudinally** orientated division follows the Large Intestine primary channel to **L.I.-15** (*jianyu*), continues via the supraclavicular fossa to → **ST-12** (*quepen*) and along the neck to the mandibular angle, where it spreads. One branch runs to the teeth; another branch reaches the ear, where it communicates with all channels reaching the ear.

Clinical importance (→ 8.1.2)

Pathology

- **Excess (*shi*):** Disorders of the teeth and gums, disorders of the ears
- **Deficiency (*xu*):** Sensitive teeth and gums (such as sensitivity to cold), sensation of tightness in the chest and diaphragm

4.2.5 Cutaneous Region (*yang ming pi bu*)

See description and figures → 1.6

4.2.6 Points of the Large Intestine Primary Channel (Overview)

Specific points according to their function

- ***Yuan*-source point (→ 8.1.1): L.I.-4** (*hegu*) 🟦🟦
- ***Luo*-Connecting point (→ 8.1.2.): L.I.-6** (*pianli*) 🟦⬛
- ***Xi*-cleft point (→ 8.1.3): L.I.-7** (*wenliu*)
- **Associated Back-*shu* point (→ 8.1.4): BL-25** (*dachangshu*) 🟦⬛
- **Associated Front-*mu* point (→ 8.1.5): ST-25** (*tianshu*)
- **Five *shu*-transport point (→ 8.1.6):**
  jing-well point (Metal), *ben* point:. **L.-I.1** (*shangyang*)
  ying-spring point (Water), sedation point: **L.I.-2** (*erjian*)
  shu-stream point (Wood): **L.I.-3** (*sanjian*)
  jing-river point (Fire): **L.I.-5** (*yangxi*)
  he-sea point (Earth), tonification point: **L.I.-11** (*quchi*) 🟦🟦
- ***Hui*-meeting point (→ 8.1.7): –**
- **Opening point (→ 8.1.8): –**
- **Lower *he*-sea point (→ 8.1.9): –**
- ***Jiaohui*-meeting points (→ 8.1.10):**
  - with the Small Intestine primary and BL channel, *yang wei mai*: **L.I.-14** (*binao*)*
  - with the *yang qiao mai*: **L.I.-15** (*jianyu*) 🟦⬛, **L.I.-16** (*jugu*)
  - with the primary ST channel: **L.I.-20** (*yingjiang*) 🟦⬛
  - of other channels with the L.I. channel: **ST-4, ST-12, S.I.-12, Du-14, Du-26, Ren-24***; according to some classics: **G.B.-5, G.B.-6, G.B.-14**
- **Gao Wu command point (→ 8.1.11) for the face and mouth: L.I.-4** (*hegu*) 🟦🟦
- **Window of Heaven point (→ 8.1.12): L.I.-18** (*futu*)
- **Point of the Four Seas (→ 8.1.13): –**
- **Ma Dan Yang Heavenly Star points (→ 8.1.14): L.I.-4** (*hegu*) 🟦🟦, **L.I.-11** (*quchi*) 🟦🟦
- **Sun Si Miao Ghost point (→ 8.1.15): L.I.-11** (*quchi*) 🟦🟦

---

* Mentioned by only some authors

Points according to region

- **Local points (→ 8.2.1):** nose – **L.I.-20** (*yingxiang*) 🟦■; shoulder – **L.I.-15** (*jianyu*) 🟦■; elbow – **L.I.-11** (*quchi*) 🟦🟦; hand – **L.I.-5** (*yangxi*); hand and fingers – **L.I.-4** (*hegu*) 🟦🟦; fingers (numbness and pain) – **L.I.-3** (*sanjian*)
- **Regional points (→ 8.2.1):** elbow – **L.I.-10** (*shousanli*), **L.I.-13** (*shouwuli*); shoulder and elbow – **L.I.-14** (*binao*)
- **Distal points (→ 8.2.1):** forehead, eyes, mouth/teeth – **L.I.-4** (*hegu*) 🟦🟦; nose – **L.I.-3** (*sanjian*), **L.I.-4** (*hegu*) 🟦🟦; neck – **L.I.-4** (*hegu*) 🟦🟦, **L.I.-11** (*quchi*) 🟦🟦; mouth/teeth – **L.I.-2** (*erjian*), **L.I.-4** (*hegu*) 🟦🟦; shoulder, elbow, hand, fingers – **L.I.-4** (*hegu*) 🟦🟦, **L.I.-1** (*shangyang*); knee and foot – **L.I.-5** (*yangxi*); foot – **L.I.-2** (*erjian*), **L.I.-3** (*sanjian*); toes – **L.I.-4** (*hegu*) 🟦🟦

Specific points according to the course of the channel (in numerical order)

- **L.I.-1** (*shangyang*): *jing*-well point (Metal) (→ 8.1.6); *ben* point (Five Phase point); distal point for the elbow and the hand (→ 8.2.1)
- **L.I.-2** (*erjian*): *ying*-spring point (Water) (→ 8.1.6); sedation point; distal point for the mouth/teeth (→ 8.2.1); distal point for the foot (→ 8.2.1)
- **L.I.-3** (*sanjian*): *shu*-stream point (Wood) (→ 8.1.6); local point for the fingers (numbness and pain) (→ 8.2.1); distal point for the nose (→ 8.2.1); distal point for the feet (→ 8.2.1)
- **L.I.-4** (*hegu*) 🟦🟦: *yuan*-source point (→ 8.1.1); Ma Dan Yang Heavenly Star point (→ 8.1.14); Gao Wu command point (→ 8.1.11) for the face and mouth; important point for acupuncture anaesthesia; distal point for the forehead, eyes, nose, mouth/teeth, jaw, shoulder, elbow, hand, fingers (→ 8.2.1); local point for the hand and fingers (stiffness) (→ 8.2.1)
- **L.I.-5** (*yangxi*): *shu*-stream point (Fire) (→ 8.1.6); local point for the hand (→ 8.2.1); distal point for the knees and feet (→ 8.2.1)
- **L.I.-6** (*pianli*): *luo*-connecting point (→ 8.1.2)
- **L.I.-7** (*wenliu*): *xi*-cleft point (→ 8.1.3)
- **L.I.-10** (*shousanli*): adjacent point for the elbow (→ 8.2.1)
- **L.I.-11** (*qichi*) 🟦🟦: Sun Si Miao Ghost point (→ 8.1.15); *he*-sea point (Earth) (→ 8.1.6); tonification point; Ma Dan Yang Heavenly Star point; distal point for the neck (→ 8.2.1); local point for the elbow (→ 8.2.1)
- **L.I.-13** (*shouwuli*): regional point for the elbow (→ 8.2.1)
- **L.I.-14** (*binao*)*: *jiaohui*-meeting point with the S.I. and BL channel and the *yang wei mai** (→ 8.1.10); regional point for the shoulder and elbow (→ 8.2.1)
- **L.I.-15** (*jianyu*) 🟦■: *jiaohui*-meeting point with the *yang qiao mai* (→ 8.1.10); local point for the shoulder (→ 8.2.1)
- **L.I.-16** (*jugu*): *jiaohui*-meeting point with the *yang qiao mai* (→ 8.1.10)
- **L.I.-18** (*futu*): Window of Heaven point (→ 8.1.12)
- **L.I.-20** (*yingxiang*) 🟦■: local point for disorders of the nose (→ 8.2.1); *jiaohui*-meeting point with the ST channel (→ 8.1.10)

General location help

- The course of the line connecting **L.I.-5** and **L.I.-11** (12 cun) changes depending on whether the forearm is in a supinated or a pronated position. For location purposes the forearm should be in a midposition with the elbow slightly flexed.
- Since the L.I. channel crosses to the opposite side of the body at **Du-26** (nasolabial groove), locate **L.I.-19** and **L.I.-20** contralaterally.

---

* Mentioned by only a few authors

Ch04.2-F10028.qxd 2/23/08 7:05 PM Page 101

Shang Yang SHANGYANG L.I.-1



Location

On the index finger, 0.1 cun from the radial corner of the nail.

How to find

This point is located where two tangents bordering the nail of the index finger medially and proximally cross, approximately 0.1 cun from the corner of the nail.

Needling

0.2–0.3 cun vertically or obliquely in a proximal direction. Avoid needling the perionychium. For acute disorders (pain, inflammation), prick to bleed with needle, lancet or three-edged needle.

Actions/Indications

- Expels pathogenic factors and opens the channel
- Frees the senses

Special features

Jing-well point, Metal point, *ben* point (Five Phases), entry point according to some authors.





L.I.-2 *Second Space* ERJIAN

Location

On the radial aspect of the index finger, distal to the metacarpophalangeal joint, at the junction of the shaft and the basis of the proximal phalanx.

How to find

With the hand relaxed, palpate the border between the 'red to white' skin along the shaft of the second proximal phalangeal bone towards the metacarpo-phalangeal joint until the angle between the base and the shaft of the bone can be clearly felt. **L.I.-2** is located at the junction of the shaft and the base and slightly below (palmar to) the most external curvature of the bone.

→ **S.I.-2** is located in a similar position at the proximal phalanx of the little finger.

Needling

0.2–0.5 cun obliquely in a proximal direction or distal in a slightly palmar direction.

Actions/Indications

- Clears Heat and expels Wind

Special features

Ying-spring point, Water point, sedation point, distal point for the mouth and teeth







Third Space SANJIAN L.I.-3


Metacarpal II
Proximal phalanx II
L.I.-3


S.I.-2
S.I.-3
Most distal palmar crease
Junction

Location

On the radial aspect of the index finger, proximal to the metacarpo-phalangeal joint, at the junction of the shaft and the head of the 2nd metacarpal bone.

How to find

With the hand relaxed, palpate along the radial aspect of the 2nd metacarpal bone in a distal direction until the angle formed between the head and the shaft can be clearly felt. **L.I-3** is located at the junction of the shaft and the head and slightly below (palmar to) its most external curvature. → **S.I.-3** is located in a comparable position on the ulnar aspect of the 5th metacarpal bone (on the ulnar border of the hand). Located in a comparable location on the feet are → **SP-3** and → **BL-65**.

Needling

With the hand relaxed, 0.3–1 cun vertically directly below the lower border of the metacarpal bone towards → **S.I.-3**.

Actions/Indications

- Clears Heat and expels Wind
- Benefits the throat and teeth
- Alleviates pain

Special features

Shu-stream point, Wood point. Important point for pain in the fingers and the metacarpus.


S.I.-1
Ex-UE-9
(*baxie*)
L.I.-2
L.I.-3
Ex-UE-8
T.B.-2
S.I.-2
Ex-UE-9
(*baxie*)
L.I.-4
T.B.-3
S.I.-3
Ex-UE-7
Ex-UE-7
S.I.-4
L.I.-5
S.I.-5




BL-66
BL-65
BL-64

L.I.-4 *Joining Valley* HEGU

Location

On the radial aspect of the hand, between the 1st and 2nd metacarpal bones, closer to the 2nd metacarpal bone and approximately at its midpoint.

How to find

When pressing the thumb and index finger together, the adductor pollicis and the interosseus dorsalis muscles will form a bulge. Needle **L.I.-4** at the highest point of the bulge and push it further towards the inferior aspect of the second metacarpal bone. **Or**: Spread the thumb and forefinger and place the distal phalanx of the thumb of the other hand on the webbed border. When flexing the thumb, its tip will point to **L.I.-4. Or**: Insertion on the angle bisector between the 1st and 2nd metacarpal bones, needling in the direction of the midpoint of the second metacarpal bone.

Needling

0.5–1 cun vertically or slightly obliquely towards the palmar aspect of the hand. Caution: Reducing needle techniques are contraindicated during pregnancy; exception: to induce labour.

Actions/Indications

- Releases the Exterior (main point!)
- Regulates the face and head
- Regulates the Defensive Qi (*wei qi*) and sweating
- Opens the channel and *luo*-connecting vessels
- Alleviates pain
- Promotes labour

Special features

Yuan-source point, Gao Wu command point for the head and mouth, Ma Dan Yang Heavenly Star point, entry point according to some authors. Most important analgesic point for the whole body. Most important single distal point for disorders of the face and sensory organs. It is the most commonly used point in clinical practice. The combined bilateral needling of **L.I.-4** and → **LIV-3** (between the 2nd and 3rd metatarsal bones) is known as *si guan* (Four Gates): they strongly regulate the Qi and Blood, stop pain and relieve spasms.


midpoint
Meta-
carpal II
L.I.-4
Highest point
of the muscle bulge


Meta-
carpal II
Extended
thumb


Internal location
midpoint
Meta-
carpal II
Meta-
carpal I
Insertion on the
angle bisector


S.I.-1
Ex-UE-9
(baxie)
L.I.-2
L.I.-3
T.B.-2
S.I.-2
Ex-UE-8
Ex-UE-9
(baxie)
L.I.-4
T.B.-3
S.I.-3
Ex-UE-7
Ex-UE-7
S.I.-4
L.I.-5
S.I.-5


LIV-3
LIV-2
1.5–2 cun
Interdigital fold

Yang Stream YANGXI L.I.-5


Tendon of the extensor pollicis longus
Styloid process of the radius
L.I.-5
Tendon of the extensor pollicis brevis


T.B.-10
L.I.-11
S.I.-8
L.I.-10
T.B.-9
L.I.-7
S.I.-7
L.I.-6
T.B.-6
T.B.-5
S.I.-6
T.B.-4
L.I.-5
1
2
3
4
5
6
7
8
9
10
11
12
cun


Abductor pollicis longus
Radial artery
Lu-8
1cun
Lu-9
Joint space
Carpal bones

Location

With the thumb abducted, in a depression between the tendons of the extensor pollicis longus and brevis muscles ('anatomical snuffbox'), on the radial aspect of the wrist.

How to find

The anatomical snuffbox is a depression on the radial aspect of the wrist formed when abducting the thumb. Holding the hand in a horizontal position, it opens towards the body. **L.I.-5** is located on the wrist joint space, which becomes palpable by moving the wrist. → **LU-9** is also located on the wrist joint space and can be found by moving anteriorly from **L.I.-5** across the short tendon of the extensor pollicis muscle.

Needling

Vertically 0.5–1 cun. Caution: Avoid the superficial cephalic vein.

Actions/Indications

- Supports the wrist joint
- Clears Fire and expels Wind
- Clears Fire from the *yangming* (L.I., ST) and calms the *shen*

Special features

Jing-river point, Fire point. Important local point for disorders of the wrist, together with **T.B.-4, S.I.-5, HE-7, P-7** and **LU-9**.

L.I.-6 *Veering Passage* PIANLI

Location

3 cun proximal to → **L.I.-5** (in the centre of the anatomical snuffbox), on the line connecting → **L.I.-5** and → **L.I.-11**, between the abductor pollicis longus and the extensor pollicis brevis muscles, at the level of the junction between the tendon and the muscle.

How to find

Please note: The course of the line connecting → **L.I.-5** and → **L.I.-11** depends on the position of the forearm. For location purposes, a midposition of the forearm with flexed elbow is recommended. To locate **L.I.-6**, measure 3 cun (1 handsbreath) from → **L.I.-5** (centre of the anatomical snuffbox) on the connecting line. **Or**: 'Tiger mouth grip' (→ Fig. 2.6): Spread thumb and index finger of both hands, crossing them so that the forefinger of one hand comes to rest on the styloid process of the other, but avoiding bending the wrist. Place the middle finger against the forefinger: **L.I.-6** is located directly below the tip of the middle finger.

Located at the same level (3 cun proximal to the wrist joint space) on the dorsal side of the forearm are → **T.B.-6** (in the depression between the radius and the muscle) and → **T.B.-7** (in the depression between the ulna and the muscle) as well as → **P-5** (on the ventral side of the forearm between the tendons).

Needling

Obliquely or transversely (subcutaneously) 0.5–1 cun

Actions/Indications

- Expels Wind, clears Heat
- Regulates and opens the water passages
- Opens the channel and *luo* vessels

Special features

Luo-connecting point. Major point of the L.I. channel for regulating the water passages.













Warm Flow WENLIU L.I.-7


7 cun
5 cun
L.I.-11
L.I.-7
L.I.-5


T.B.-10
L.I.-11
S.I.-8
L.I.-10
1
2
3
4
5
6
7
8
9
10
11
12
cun
T.B.-9
L.I.-7
S.I.-7
L.I.-6
T.B.-6
T.B.-5
S.I.-6
T.B.-4
L.I.-5




L.I.-5
Extensor tendon


90°
L.I.-11
Lateral epicondyle
Olecranon

Location

5 cun proximal to the anatomical snuffbox in the direction of the lateral end of the elbow crease or 1 cun distal to the midpoint of the line connecting → **L.I.-5** and → **L.I.-11**.

How to find

Please note: With the hand supinated, the line connecting → **L.I.-5** and → **L.I.-11** runs alongside the radial margin of the forearm. However, with the arm pronated, it transverses the forearm. **L.I.-7** lies on the dorso-lateral aspect of the radius and is best located with the forearm in midposition and the elbow flexed. Spreading hands technique: Place the little fingers on → **L.I.-5** and → **L.I.-11** and span the hands evenly so that the thumbs join at the midpoint of the line. From there, measure 1 cun distally. → **T.B.-8** is located 4 cun proximal to the wrist crease between the radius and the ulna in the centre of the dorsal forearm or 1 cun distal to **L.I.-7**.

Needling

Vertically 0.5–1 cun

Actions/Indications

- Treats acute disorders
- Clears Heat and toxic Heat
- Regulates the Stomach and Large Intestine

Special features

Xi-cleft point

L.I.-8 *Lower Angle* XIALIAN

Location

4 cun distal to the lateral end of the elbow crease in the direction of the anatomical snuffbox and on a line connecting ➞ **L.I.-5** and ➞ **L.I.-11**.

How to find

Please note: In supination, the line connecting ➞ **L.I.-5** and ➞ **L.I.-11** runs along the radial margin of the forearm; in pronation, it transverses the forearm. **L.I.-8** lies on the dorsal aspect of the radius and is best located with the forearm in mid-position and the elbow flexed. **L.I.-8** can be found either 4 cun distal to ➞ **L.I.-11** or 2 cun proximal to the midpoint of the line connecting ➞ **L.I.-5** and ➞ **L.I.-11** (spreading hands technique, ➞ 2.3.3).

➞ **T.B.-9** is 5 cun distal to the olecranon between the radius and the ulna, about 1 cun distal to **L.I.-8** in the middle of the dorsal forearm.

Needling

Vertically or obliquely 0.5–1 cun

Actions/Indications:

- Opens the channel
- Cools and expels Wind
- Harmonises the Small Intestine


4 cun
8 cun
L.I.-11
L.I.-8
L.I.-5


T.B.-10
L.I.-11
S.I.-8
L.I.-10
T.B.-9
L.I.-7
S.I.-7
L.I.-6
T.B.-6
T.B.-5
S.I.-6
T.B.-4
L.I.-5
1
2
3
4
5
6
7
8
9
10
11
12
cun


Lateral epicondyle
5 cun
T.B.-9
7 cun
Midpoint of the wrist

Upper Angle SHANGLIAN L.I.-9







Location

3 cun distal to the lateral end of the elbow crease in the direction of the anatomical snuffbox, on the line connecting → **L.I.-5** and → **L.I.-11**.

How to find

Please note: With the hand supinated, the line connecting → **L.I.-5** and → **L.I.-11** runs along the radial margin of the forearm. However, with the arm pronated, it transverses the forearm. **L.I.-9** lies on the dorsal aspect of the radius and is best located with the forearm in midposition and the elbow flexed. From → **L.I.-11**, measure 3 cun distally. The point is located in an easily palpable depression between two muscle bellies and is often tender with pressure.

Needling

Vertically or obliquely 0.5–1 cun

Actions/Indications

- Opens the channel, cools and expels Wind
- Harmonises the Large Intestine

L.I.-10 *Arm Three Miles* SHOUSANLI

Location

2 cun distal to → **L.I.-11**, on the line connecting → **L.I.-5** and → **L.I.-11**, on the extensor carpi radialis longus muscle; a deeper insertion will reach the supinator muscle.

How to find

Please note: With the hand supinated, the line connecting → **L.I.-5** and → **L.I.-11** runs along the radial margin of the forearm. However, with the arm pronated, it transverses the forearm. **L.I.-10** lies on the dorsal aspect of the radius and is best located with the forearm in midposition and with the elbow flexed. First, palpate → **L.I.-11** in the depression lateral to the radial end of the cubital crease. **L.I.-10**, usually sensitive to pressure, is found by measuring 2 cun distally from → **L.I.-11** on the connecting line.

Needling

Vertically 1–2 cun

Actions/Indications

- Regulates the Qi and Blood (in the upper extremity), opens the channel and *luo* vessels, alleviates pain
- Regulates the Stomach and Intestines

Special features

Important local point, often used in chain-and-lock method with other channel points


Cubital crease
Extensor carpi radialis longus
Anatomical snuffbox
L.I.-11
L.I.-10
L.I.-5
2 cun


90°
L.I.-10
L.I.-11


L.I.-14
T.B.-12
L.I.-13
T.B.-10
L.I.-11
S.I.-8
L.I.-10
T.B.-9
L.I.-7
S.I.-7
L.I.-6
T.B.-6
T.B.-5
3
4
5
6
7
8
9
1
2
3
4
5
6
7
8
9
10
11
12


L.I.-5
Extensor tendon

Pool at the Crook QUCHI L.I.-11


Cubital crease
90°
L.I.-11
Lateral epicondyle
Olecranon

Location

With the elbow flexed, on the lateral end of the elbow crease, in a depression between the end of the crease and the lateral epicondyle of the humerus, on the extensor carpi radialis longus muscle.

How to find

First, with the elbow completely flexed, locate the lateral end of the elbow crease. Next, with the elbow flexed at approximately 90°, palpate for a pressure-sensitive depression in this area on the extensor carpi radialis longus muscle. **L.I.-11** is located close to the border of the proximal aspect of the ulna.

Also located at the level of the elbow crease are → **LU-5,** → **P-3** (radial/ulnar of the tendon of the biceps) and → **HE-3** (with the elbow completely flexed at the medial end of the cubital crease).

Needling

Vertically 1–1.5 cun

Actions/Indications

- Clears Heat, expels Wind
- Clears *yangming* – Fire
- Cools the Blood, drains Dampness, alleviates itching
- Opens the channel

Special features

He-sea point, Earth point, tonification point, Sun Si Miao Ghost point, Ma Dan Yang Heavenly Star point. Important point for Heat conditions and disorders of the upper extremity.


Biceps brachii
Medial head of the triceps brachii
Aponeurosis of the biceps brachii
P-3
HE-3
LU-5
Medial epicondyle
Tendon of the biceps brachii
Palmaris longus
Flexor carpi radialis

Left arm, anterior aspect


Brachialis
Lateral head of the triceps brachii
Brachioradialis
Medial head of the triceps brachii
Extensor carpi radialis longus
Tendon of the triceps brachii
T.B.-10
L.I.-11
Olecranon
Lateral epicondyle
Flexor carpi ulnaris

Left arm, posterior aspect


Biceps
Biceps tendon
Cubital crease
P-3
Lu-5
He-3

Right arm, anterior aspect

L.I.-12 *Elbow Crevice* ZHOULIAO

Location

1 cun proximal to the lateral end of the elbow crease (→ **L.I.-11**), on the anterior border of the humerus.

How to find

L.I.-12 is best located with the elbow flexed at 90°. From → **L.I.-11** (on the lateral end of the elbow crease), palpate 1 cun towards proximal. There, palpate for the anterior border of the humerus. **L.I.-12** is located at the junction of the shaft with the lateral epicondyle of the humerus and in front of the anterior border of the bone.

Needling

Vertically 0.5–1 cun, needle insertion between the border of the humerus and the flexor muscles in a medial direction.

Actions/Indications

- Opens the channel


1 cun
L.I.-12
L.I.-11


T.B.-13
S.I.-9
L.I.-14
T.B.-12
L.I.-13
L.I.-11
T.B.-10
S.I.-8
L.I.-10
T.B.-9
S.I.-7
L.I.-7
L.I.-6
T.B.-6
T.B.-5
S.I.-6
T.B.-4
L.I.-5
1
2
3
4
5
6
7
8
9
1
2
3
4
5
6
7
8
9
10
11
12
cun


90°
L.I.-11
Lateral epicondyle
Olecranon

Arm Five Miles SHOUWULI L.I.-13


L.I.-15
Lateral border of the biceps
L.I.-13
3 cun
L.I.-11


Acromio-clavicular joint
T.B.-14
L.I.-15

Location

On the lateral aspect of the upper arm, 3 cun proximal to the lateral end of the elbow crease (→ **L.I.-11**), in the direction of the head of the humerus.

How to find

This point is located on a line connecting → **L.I.-11** (lateral end of the elbow crease) and → **L.I.-15** (in a depression anterior and inferior to the acromion), on the lateral border of the biceps, in a groove between the biceps and the brachialis muscles. With the elbow flexed at 90°, measure 3 cun from → **L.I.-11** towards proximal. Ask the patient to flex their biceps.

Needling

Vertically 0.5–1 cun, alongside the anterior border of the humerus.

Actions/Indications

- Opens the channel

L.I.-14 *Upper Arm* BINAO

Location

On the lateral aspect of the upper arm, on a line connecting → **L.I.-11** and → **L.I.-15**, 7 cun proximal to → **L.I.-11** and slightly superior to the pointed insertion of the deltoid muscle.

How to find

This point is best located with the elbow flexed and the deltoid muscle flexed against resistance, making the lateral border of the muscle belly more visible. **L.I.-14** is located in a depression on the lower pointed insertion area of the deltoid. 'By moving the upper arm towards the tip of the nose, the patient will touch the approximate location of this point.' **For orientation:** This point lies approximately 2 cun inferior to the anterior end of the axillary fold (→ 2.2).

Needling

Vertically 0.5–1 cun; also obliquely towards the shoulder for disorders of the eyes.

Actions/Indications

- Opens the channel and *luo* vessels, alleviates pain
- Benefits the eyes

Special features

Important local point. According to some authors, meeting point with the *yang wei mai* and the S.I. and BL channels.


Deltoid
L.I.-14
Flexion of the deltoid
L.I.-11
Cubital crease


S.I.-12
S.I.-10
T.B.-14
T.B.-13
S.I.-9
1
2
L.I.-14
3
4
T.B.-12
5
6
7
L.I.-13
8
9
T.B.-10
L.I.-11
1
S.I.-8
L.I.-10
2
3
4


Clavicle
L.I.-15
LU-2
Deltoid
Infraclavicular fossa
Ex-UE (jianqian/ jianneiling)
LU-1
Pectoralis major, clavicular head
LU-3
Triceps brachii
L.I.-14


90°
L.I.-11
Lateral epicondyle
Olecranon

Shoulder Bone JIANYU L.I.-15


Deltoid, posterior fibres
Scapular spine
Deltoid, lateral fibres
Acromio-clavicular joint
T.B.-14
L.I.-15
Clavicle
Anterior extremity of the acromion
Abduct arm
Deltoid, anterior fibres


Acromion
Trapezius
Deltoid
Scapular spine
Triceps brachii, lateral head
Teres major
Triceps brachii, long head
Biceps brachii

Location

In the depression distal and anterior to the acromion, between the clavicular and acromial portions of the deltoid muscle.

How to find

Ask the patient to abduct their arm. With the arm in a horizontal position, two depressions will form in the insertion area of the deltoid, distally to the acromion. By placing the thumb and index finger in those depressions in a pincer-like grip (with thumb and finger 1 thumb's breadth apart), the anterior finger will be in the anterior depression, where **L.I.-15** is located.
→ **T.B.-14** is located under the posterior finger in the dorsal depression.

Needling

With the arm slightly adducted, 1–1.5 cun obliquely in the bony cleft and in a posterior direction; with the arm abducted, 0.5–1 cun vertically. Caution: Shoulder joint.

Actions/Indications

- Expels Wind-Damp, opens the channel, alleviates pain, supports the shoulder joint
- Expels Wind
- Regulates the Qi, resolves Phlegm

Special features

Meeting point with the *yang qiao mai*. Important local point for disorders of the shoulder, often used with chain-and-lock method (→ 8.3.6) with other channel points of the upper extremity.

L.I.-16 *Great Bone* JUGU

Location

In a depression between the acromial extremity of the clavicle and the junction of the scapular spine and the acromion.

How to find

This point is located on the shoulder, at the angle between the acromio-clavicular joint and the junction of the scapular spine and the acromion (→ 3.3.1), above the most lateral portion of the trapezius and supraspinatus muscles. At this point, the tendon of the supraspinatus delves below the acromion, where it often causes problems owing to the cramped anatomical structure (for example, impingement syndrome).

Needling

Vertically 0.5–1 cun

Actions/Indications

- Opens the channel, supports the shoulder joint

Special features

Meeting point with the *yang qiao mai*


Scapular spine
Clavicle
L.I.-16
AC joint
Acromion


Acromion
Trapezius
Deltoid
Scapular spine
Triceps brachii, lateral head
Teres major
Triceps brachii, long head
Biceps brachii


Trapezius (superior fibres)
G.B.-21
S.I.-13
S.I.-12
T.B.-15
L.I.-16
S.I.-10

Heaven's Tripod TIANDING L.I.-17


L.I.-18
Laryngeal prominence
1 cun
L.I.-17
Clavicular head
Sternal head
Sternocleidomastoid

Location

On the posterior border of the sternocleidomastoid muscle, 1 cun below the laryngeal prominence (→ 3.2).

How to find

This point is located on the lateral musculature of the neck, directly posterior to the sternocleidomastoid muscle. By rotating the patient's head to the opposite side, this muscle will become more visible and palpable. → **L.I.-18** is located 1 cun superior to **L.I.-17**, between the two heads of the sternocleidomastoid.

Needling

Rotate the head back to its normal position before needle insertion. Vertically 0.3–0.5 cun or obliquely up to 0.8 cun. Caution: Carotid artery, jugular vein.

Actions/Indications

- Benefits the throat and larynx


G.B.-20
T.B.-17
G.B.-12
Ex-HN (*anmian*)
ST-5
ST-6
S.I.-17
T.B.-16
Ren-23
ST-9
L.I.-18
S.I.-16
L.I.-17
ST-12
ST-11


Ex-HN (*anmian*)
G.B.-12
ST-9
Sternocleido-mastoid
L.I.-18
S.I.-16
Laryngeal prominence
L.I.-17
ST-11
Sternal head
Clavicular head


External jugular vein
Transverse cervical nerve

L.I.-18 *Support the Prominence* FUTU

Location

On the lateral aspect of the neck, at the level of the laryngeal prominence, between the two heads of the sternocleidomastoid muscle (→ 3.2).

How to find

From the laryngeal prominence (tip of the Adam's apple), draw a line across the sternocleidomastoid muscle to its posterior border. **L.I.-18** is located between the two heads of this muscle, which becomes more visible and palpable by rotating the head to the opposite side.

Located on the same level are → **ST-9** on the anterior border and → **S.I.-16** on the posterior border of the sternocleidomastoid muscle.

Needling

Rotate the head back to its normal position before inserting the needle. Vertically 0.3–0.5 cun or obliquely up to 0.8 cun. Caution: Carotid artery, jugular vein.

Actions/Indications

- Benefits the throat and larynx

Special features

Window of Heaven point. Often used when swallowing is difficult, for example after a stroke.


Hyoid bone
Superior thyroid notch
Laryngeal prominence
Thyroid cartilage
**
Tracheal cartilage


ST-9
L.I.-18
S.I.-16
Laryngeal prominence
Clavicular head
Sternal head
Sternocleidomastoid


S.I.-18
ST-
G.B.-2
G.B.-20
T.B.-17
G.B.-12
Ex-HN (*anmian*)
ST- 5
ST- 6
S.I.-17
T.B.-16
Ren-23
ST- 9
L.I.-18
S.I.-16
L.I.-17
ST-12
ST-11


External jugular vein
Transverse cervical nerve

Mouth Grain Crevice KOUHELIAO L.I.-19


L.I.-19
Du-26
0.5 cun


Ex-HN-7
ST-1
ST-2
ST-7
G.B.-2
Ex-HN-8
L.I.-20
S.I.-18
L.I.-19
D.U.- 26
ST-4
ST-5
Ex-HN
Ren-24


L.I.-19
Du-26
0.5 cun

Location

On the maxilla, slightly below the lateral margin of the nostril.

How to find

By dividing the distance between the margin of the nostril and the margin of the upper lip into three sections, **L.I.-19** is located at the junction of the upper and the middle third.
→ **Du-26** is located on the same level, on the anterior midline and at a distance of approximately 0.5 cun.

Needling

Obliquely 0.3–0.5 cun. Painful point! According to some classics, moxibustion is contraindicated.

Actions/Indications

- Expels Wind and opens the nasal passages

L.I.-20 *Welcome Fragrance* YINGXIANG

Location

In the nasolabial groove, on the level of the midpoint of the lateral border of the ala nasi.

How to find

L.I.-20 is located by finding the midpoint of the lateral border of the ala nasi (→ 3.1.2) and following it to the nasolabial groove. Tip: The nasolabial groove becomes more pronounced if you ask the patient to smile.

Needling

0.3–0.5 cun vertically, obliquely or transversely (subcutaneously) in a medial and superior direction towards the extra point → **EX-HN-8** (*shangyingxiang* or *bitong*: at the upper end of the nasolabial groove, at the transition between the nasal bone and the cartilage). According to some authors, moxibustion is contraindicated.

Actions/Indications

- Opens the nasal passages, expels Wind, clears Heat

Special features

Meeting point with the ST channel, exit point. Most important local point for disorders of the nose.


Midpoint of the lateral border of the ala nasi
L.I.-20
Nasolabial groove


Ex-HN-7
ST-1
ST-2
Ex-HN-8
G.B.-2
ST-7
L.I.-20
S.I.-18
L.I.-19
D.U.-26
ST-4
ST-5
Ex-HN
Ren-24


Ex-HN-8
(*bitong*)
L.I.-20
Nasolabial groove
Maxilla
(upper
jaw)

4.3 The Stomach Channel System – Foot *yangming* (*zu yang ming jing luo*)

4.3.1 The Stomach Primary Channel (*zu yang ming jing*)


G.B.-4
G.B.-5
G.B.-6
G.B.-3
S.I.-14
ST- 8
S.I.-24
L.I.-20 → (BL-1) → ST-1
S.I.-26
Ren-24
ST-12
19
Ren-13
Ren-12
Ren-10
31
32
33
34
35
ST-36
Lower *he*-Sea point of the Stomach
41
ST-45
SP-1


Mamillary line
ST-10
ST-11
ST-12
ST-13
ST-14
ST-15
ST-16
ST-17
ST-18
8 cun
Junction: xiphoid process/sternum
1
2
3
4
5
6
7
8
9
ST-19
ST-20
ST-21
ST-22
ST-23
ST-24
ST-25
2 cun
Ren-12
2 cun
Ren-8
(In the umbilicus)
1
2
3
4
5
6
7
8
ST-26
ST-27
ST-28
ST-29
ST-30
2 cun
Upper border of the pubic symphysis
1
2
3
4
5
cun


Highest prominence of the greater trochanter
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
cun
ST-31
ST-32
4 cun
ST-33
ST-34
2 cun
Upper patellar border
Knee joint space (lower patellar border)
ST-35
3 cun
ST-36
3 cun
ST-37
2 cun
ST-38
1 cun
ST-39
ST-40
8 cun
Midpoint
8 cun
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
cun
Highest prominence of the lateral malleolus
ST-41



Pathway

The Stomach primary channel begins with an **internal** branch at the Yang axes connection of the first great circuit (*yangming*, hand–foot pairing) at → **LI-20** (*yingxiang*) lateral to the ala nasi

- travels **internally** to → **BL-1** (*jingming*) at the inner canthus of the eye
- emerges at the infraorbital ridge at **ST-1** (*chengqi*), the beginning of the external part of the primary channel
- descends laterally along the nose and **enters** the gums of the upper jaw
- meets the contralateral Stomach primary channel and the *du mai* at → **Du-26** (*renzhong*) and emerges again
- curves around the lips to meet the *ren mai* and again the contralateral Stomach channel at → **Ren-24** (*chengjiang*)
- traverses the lower cheek and winds around the lower angle of the mandible.

Here, at → **ST-5** (*daying*), the external channel **divides into two branches**:

- **One branch** ascends anterior to the ear, travels via → **G.B.-3** (*shangguan*), → **G.B.-6** (*xuanli*), → **G.B.-5** (*xuanlu*) and → **G.B.-4** (*hanyan*) to the temporal region to → **ST-8** (*touwei*) and continues to the forehead to meet → **Du-24** (*shenting*), where it terminates.
- The **other external branch** descends along the lateral aspect of the neck to the supraclavicular fossa and travels posteriorly over the back of the neck to → **Du-14** (*dazhui*) below the spinous process of the 7th cervical vertebra, where it meets the other five Yang primary channels.

An internal branch descends from the supraclavicular fossa, passes the diaphragm, enters first its pertaining *fu*-Organ, the Stomach (*wei*) and then connects with its paired *zang*-Organ, the Spleen (*pi*). Minor branches of the **internal** channel intersect with → **Ren-13** (*shangwan*), → **Ren-12** (*zhongwan*) and → **Ren-10** (*xiawan*). The internal branch then descends towards the inguinal region where it emerges slightly superior to **ST-30** (*qichong*) and reconnects with the **external** branch.

- The **external** channel descends from the supraclavicular fossa, crosses the nipple and laterally passes the umbilicus, travels in a curve to the leg and knee, continues along the anterior crest of the tibia and the dorsum of the foot and terminates on the second toe at → **ST-45** (*lidui*) at the lateral corner of the nail.
- An **internal** branch originates below the knee area at → **ST-36** (*zusanli*) and travels to the lateral aspect of the middle toe.
- A further branch separates from the primary channel at → **ST-42** (*chongyang*) on the dorsum of the foot and connects at → **SP-1** (*yinbai*) with its paired SP channel on the medial aspect of the big toe (foot Yin–Yang connection of the first great circuit).

Clinical importance (→ 1.2)

Exterior (*biao*) signs and symptoms: High fever, malaria, flushed face, sweating, confused mental state, aversion to cold, eye pain, dry nasal passages, nosebleeds, dry lips and mouth, lesions of the lips and mouth, sore and swollen throat, thoracic pain, red and swollen legs

Interior (*li*) or *zangfu*-Organ signs and symptoms: Abdominal distension, sensation of fullness, oedema, irritability during work and rest, mania and epilepsy, hyperpepsinia, constant hunger, yellow urine

Excess (*shi*): Heat sensations on the anterior aspect of the body, constant hunger, yellow urine

Deficiency (*xu*): Cold sensations on the anterior aspect of the body, chills, Stomach Cold with distension and fullness

Connections and meeting points of the Stomach primary channel (→ 1.2)

Connections with other channels

Spleen primary channel (*zu tai yin jing*)

Connection: Foot Yin–Yang connection of the first great circuit
Location: ST-42 → SP-1 (on the foot).
Circulation: Circadian (according to the Organ clock)
Importance: Exterior–Interior relationship

Large Intestine primary channel (*shou yang ming jing*)

Connection: Paired according to the six channel theory (hand–foot pairing): *yang ming* (Yang axes of the first great circuit)
Location: L.I.-20 → (BL-1) → ST-1 (on the head)
Circulation: Circadian (according to the Organ clock)
Importance: Above–below relationship

Connections with other *zangfu*-Organ systems

Stomach (*wei*), Spleen (*pi*)

4.3.2 The Stomach Divergent Channel (*zu yang ming jing bie*)



Pathway

The Stomach divergent Channel separates from the Stomach primary channel at → **ST-31** (*biguan*) on the antero-lateral aspect of the thigh

- ➡ penetrates the body at the inguinal region at **ST-30** (*qichong*)
- ➡ continues to the Stomach (*wei*) and disperses in the Spleen (*pi*)
- ➡ ascends and penetrates the Heart (*xin*)
- ➡ ascends along the oesophagus to the suprasternal fossa and travels laterally to the supraclavicular fossa at **ST-12** (*quepen*).

From there it rises along the anterior border of the sternocleidomastoid muscle and meets its primary channel as well as the divergent Spleen channel at **ST-9** (*renying*) at one of the six *he*-confluences (here: ST/SP as third confluence → 1.3).

It then **emerges** at the mouth, ascends along the nose, reaches the inner canthus of the eye and connects with the eye, circles the eye region and meets the Stomach primary channel at **ST-1** (*chengqi*) where it terminates (→ fig.).

According to some authors, the Stomach divergent channel connects with the Stomach primary channel at **BL-1** (→ variant, fig.). After intersecting with **BL-1**, the divergent channel could enter the head, disperse in the brain and re-emerge at **ST-1.**

Clinical importance

- Strengthens the relationship between the Stomach and the Spleen (*zangfu*-Organs). Points on the Stomach primary channel can therefore be used for disorders of the Spleen, and vice versa points on the Spleen primary channel can treat disorders of the Stomach.
- Spreads Qi to the face and sensory organs: many points on the ST channel treat disorders of the head and face.
- Strengthens the relationship between the Stomach and the eyes: Heat and excess in this region can be directed downward by using points on the ST channel.

Ch04.3-F10028.qxd 2/22/08 8:41 PM Page 124

4.3.3 The Stomach Sinew Channel (*zu yang ming jing jin*)



Pathway

The Stomach sinew channel begins as a wider band, encompassing the second, third and fourth toe, traverses the dorsum of the foot, binds (*jie*) at the tibial depression and divides into two branches:

- **One branch** obliquely ascends the **anterolateral aspect** of the leg and binds (*jie*) at the lateral aspect of the knee. It then ascends the anterolateral aspect of the thigh and binds (*jie*) at the anterior hip region. From there it sends **a branch** to → **G.B.-30** (*huantiao*) in the direction of the greater trochanter. The sinew channel travels from the anterior hip region across the lateral abdomen and spreads across the lower ribcage posteriorly to the spine.
- **Another branch** follows the tibia on the **anterior aspect** of the lower leg and binds (*jie*) at the level of the patella. From there a branch runs to the head of the fibula where it meets the G.B. sinew channel at → **G.B.-34** (*yanglingquan*).
- From the patella the channel ascends along the anterior aspect of the thigh, binds (*jie*) in the inguinal region, passes → **Ren-2** (*qugu*) and binds (*jie*) at → **Ren-3** (*zhongji*). It then ascends across the abdominal and thoracic region and reaches the supraclavicular fossa to bind (*jie*) at **ST-12** (*quepen*). It then continues along the anterolateral aspect of the neck and binds (*jie*) at the angle of the mandible.

At the angle of the mandible the channel divides into three branches:

- **One branch** terminates anterior to the ear.
- **A further branch** ascends to the zygomatic bone where it meets the other Yang sinew channels at → **S.I.-18** (*quanliao*).
- **The third branch** circles the mouth, ascends to the upper nose region, there connects with the Bladder sinew channel and then spreads along the lower eyelid. The Bladder sinew channel spreads along the upper eyelid, so that the two channels together form a network around the eyes.

Clinical importance

Pathology: Stiffness and aching of the toes, leg cramps (gastrocnemius and quadriceps muscles), stiffness and pain on the dorsum of the foot (at **ST-41**), swelling and tension in the inguinal region, *shan*-disorders, cramping in the abdomen as well as in the supraclavicular fossa and the face, facial paralysis, weakness and paralysis of the superior rectus muscle.

Indication: Mainly used for *bi*-syndromes (painful obstruction syndromes) along the Stomach channel. The area covered by the Stomach sinew channel is larger than that covered by the Stomach primary channel. This explains why the indications of points on the Stomach primary channel include disorders and diseases of the external genitalia (for example urinary tract disorders such as cystitis, hernia and orchitis, which are often treated in combination with LIV points) as well as disorders of the eyelids and of all sensory organs.

4.3.4 The Stomach *luo*-Connecting Vessel System (*zu yang ming luo mai*)



Pathway

The ST *luo*-connecting vessel separates from the Stomach primary channel at its *luo*-connecting point **ST-40** (*fenglong*) (→ 8.1.2). It forms a three-dimensional reticular network, dividing into multiple branches and sub-branches *(sun luo, fu luo, xue luo* → 1.5) within the surrounding tissue.

➡ Horizontal divisions run to the Interiorly–Exteriorly paired primary SP channel; according to some schools of thought (for example Van Nghi, → Appendix) they travel as a **transverse** Stomach *luo*-connecting vessel to the *yuan* point → **SP-3** (*taibai*).

➡ A **longitudinal** division ascends along the anterolateral aspect of the leg to the torso and reaches the lateral aspect of the neck at → **ST-12**, where it divides into two branches: **one branch** traverses the neck, the **other branch** runs to the occiput and ascends the head to reach → **Du-20** (*baihui*).

Clinical importance (→ 8.1.2)

Pathology

- **Counterflow Qi:** Swelling and pain of the throat, sudden loss of voice, sensation of tightness in the throat
- **Excess (*shi*):** Psychological disorders, also epilepsy and mania
- **Deficiency (*xu*):** *Wei*-syndrome of the legs (atrophy syndrome with muscle weakness and paralysis)

The great *luo*-connecting vessel of the Stomach (*wei zhi dao luo* or *xu li*)

Pathway

The great Stomach *luo*-connecting vessel begins at the Stomach (*wei*), passes through the diaphragm, intersects with → **Ren-17** (*shanzhong*) and spreads in the Lungs (*fei*), trachea and larynx. From the Lung it travels to the Heart (*xin*) and emerges on the left aspect of the thorax near → **ST-18** (*rugen*) which is located where the heartbeat is visible (→ 8.1.2).

Clinical importance (→ 8.1.2)

Pathology

- **Excess (*shi*):** Dyspnoea
- **Deficiency (*xu*):** Chest tightness, for example with asthma, coughing, angina pectoris, etc.

4.3.5 Cutaneous Region (*yang ming pi bu*)

See description and figures → 1.6

4.3.6 Points of the Stomach Primary Channel (Overview)

Specific points according to their function (→ 8.1)

- ***Yuan*-source point (→ 8.1.1): ST-42** (*chongyang*) 🟦■
- ***Luo*-connecting point** (→ **8.1.2.): ST-40** (*fenglong*) 🟦🟦
- ***Xi*-cleft point (→ 8.1.3): ST-34** (*liangqiu*) 🟦■
- **Associated Back-*shu* point (→ 8.1.4): BL-21** (*weishu*) 🟦■
- **Associated Front-*mu* point (→ 8.1.5): Ren-12** (*zhongwan*) 🟦■
- **Five *shu*-transporting points (→ 8.1.6):**
  jing-well point (Metal), sedation point: **ST-45** (*lidui*) 🟦■
  ying-spring point (Water): **ST-44** (*neiting*) 🟦■
  shu-stream point (Wood): **ST-43** (*xiangu*) 🟦■
  jing-river point (Fire), tonification point: **ST-41** (*jiexi*) 🟦■
  he-sea point (Earth), *ben* point: **ST-36** (*zusanli*) 🟦🟦
- ***Hui*-meeting point (→ 8.1.7): –**
- **Opening point (→ 8.1.8): –**
- **Lower *he*-sea points (→ 8.1.9):**
  of the Stomach: **ST-36** (*zusanli*) 🟦🟦
  of the Large Intestine: **ST-37** (*shangjuxu*) 🟦■
  of the Small Intestine: **ST-39** (*xiajushu*) 🟦■
- ***jiaohui*-meeting points (→ 8.1.10):**

  - with the *ren mai, yang qiao mai, du mai**: **ST-1** (*chengqi*) 🟦⬛
  - with the *yang qiao mai**: **ST-2** (*sibai*) 🟦⬛
  - with the *yang qiao mai*: **ST-3** (*juliao*)
  - with the primary L.I. channel, *yang qiao mai, du mai*, ren mai*:* **ST-4** (*dicang*)
  - with the G.B. channel*: **ST-5** (*daying*), **ST-6** (*jiache*)
  - with the G.B. channel: **ST-7** (*xiaguan*) 🟦⬛**, ST-9** (*renying*)
  - with the G.B. channel, *yang wei mai*: **ST-8** (*touwei*) 🟦⬛
  - with the primary L.I., S.I., T.B., G.B. channels: **ST-12** (*quepen*)
  - with the *chong mai*, G.B. channel*: **ST-30** (*qichong*) 🟦⬛
  - other channels with the ST channel: **L.I.-20, BL-1, G.B.-3, G.B.-4, G.B.-5, G.B.-6; Du-14, Du-24; Du-26, Du-28*; Ren-10*, Ren-12, Ren-13**, **Ren-24; G.B.-14*, G.B.-21***
- **Gao Wu command point** (**→ 8.1.11**) **for the abdomen: ST-36** (*zusanli*) ⬛⬛
- **Window of Heaven point** (**→ 8.1.12**)**: ST-9** (*renying*)
- **Points of the Four Seas** (**→ 8.1.13**)**:**
  Sea of Qi point: **ST-9** (*renying*)
  Sea of Grain: **ST-30** (*qichong*) 🟦⬛, **ST-36** (*zusanli*) 🟦🟦
  Sea of Blood: **ST-37** (*shangjuxu*) 🟦⬛, **ST-39** (*xiajushu*) 🟦⬛
- **Ma Dan Yang Heavenly Star points** (**→ 8.1.14**)**: ST-36** (*zusanli*) 🟦🟦, **ST-44** (*neiting*) 🟦🟦
- **Sun Si Miao Ghost point** (**→ 8.1.15**)**: ST-6** (*jiache*) 🟦⬛
- **Other functional points:**
  - Front-*mu* point of the Large Intestine: **ST-25** (*tianshu*) 🟦🟦
  - most important acupuncture 'Phlegm'-point: **ST-40** (*fenglong*) 🟦🟦
- Points according to region
- **Local points** (**→ 8.2.1**)**:** eyes – **ST-1** (*chengqi*) 🟦⬛; mouth and teeth – **ST-4** (*dicang*), **ST-6** (*jiache*) 🟦⬛; jaw – **ST-7** (*xiaguan*) 🟦⬛; Large Intestine – **ST-25** (*tianshu*) 🟦🟦; Small Intestine and Bladder – **ST-28** (*shuidao*); urogenital region – **ST-30** (*qichong*) 🟦⬛; knee – **ST-34** (*liangqiu*) 🟦⬛, **ST-35** (*dubi*) 🟦⬛, **ST-36** (*zusanli*) 🟦🟦; foot – **ST-41** (*jiexi*) 🟦⬛
- **Adjacent points** (**→ 8.2.1**)**:** forehead – **ST-8** (*touwei*) 🟦⬛; eyes – **ST-2** (*sibai*) 🟦⬛; mouth/teeth – **ST-7** (*xiaguan*) 🟦⬛; throat – **ST-10** (*shuitu*); Spleen, Stomach, Gall Bladder – **ST-21** (*liangmen*); Kidney – **ST-29** (*guilai*); abdominal region – **ST-25** (*tianshu*) 🟦🟦, **ST-26** (*wailing*), **ST-30** (*qichong*) 🟦⬛; foot – **ST-34** (*liangqiu*) 🟦⬛, **ST-36** (*zusanli*) 🟦🟦; toes – **ST-41** (*jiexi*) 🟦⬛
- **Distal points** (**→ 8.2.1**)**:** frontal headaches – **ST-44** (*neiting*) 🟦⬛; nose – **ST-44** (*neiting*) 🟦⬛; mouth/teeth – **ST-44** (*neiting*) 🟦⬛; throat – **ST-44** (*neiting*) 🟦⬛; shoulder region – **ST-38** (*tiakou*) 🟦⬛; Lung – **ST-40** (*fenglong*) 🟦🟦; Spleen/Stomach – **ST-36** (*zusanli*) 🟦🟦; Large Intestine – **ST-37** (*shangjuxu*) 🟦⬛; Small Intestine – **ST-39** (*xiajushu*) 🟦⬛; epigastrium – **ST-36** (*zusanli*) 🟦🟦; shoulder – **ST-36** (*zusanli*) 🟦🟦, **ST-38** (*tiakou*) 🟦⬛

Specific points according to the channel pathway (in numerical order)

- **ST-1** (*chengqi*) 🟦⬛: meeting point with the *ren mai, yang qiao mai*, du mai* (→ 8.1.10); local point for the eyes (→ 8.2.1)
- **ST-2** (*sibai*) 🟦⬛: meeting point with the *yang qiao mai** (→ 8.1.10); adjacent point for the eyes (→ 8.2.1)
- **ST-3** (*juliao*): meeting point with the *yang qiao mai* (→ 8.1.10)
- **ST-4** (*dicang*): meeting point with the Large Intestine channel, *yang qiao mai, du mai*, ren mai** (→ 8.1.10); local point for the mouth/teeth (→ 8.2.1)
- **ST-5** (*daying*): meeting point with the Gall Bladder channel
- **ST-6** (*jiache*) 🟦⬛*:* Sun Si Miao Ghost point (→ 8.1.15); meeting point with the Gall Bladder channel* (→ 8.1.10); local point for the mouth/teeth (→ 8.2.1)
- **ST-7** (*xiaguan*) 🟦⬛: meeting point with the Gall Bladder channel (→ 8.1.10); adjacent point for the teeth and jaw (8.2.1); local point for the jaw (→ 8.2.1)
- **ST-8** (*touwei*) 🟦⬛: meeting point with the Gall Bladder channel, *yang wei mai* (→ 8.1.10); adjacent point for frontal headaches (→ 8.2.1)
- **ST-9** (*renying*): meeting point with the Gall Bladder channel (→ 8.1.10); Sea of Qi point (→ 8.1.13); Window of Heaven point (→ 8.1.12)
- **ST-10** (*shuitu*): adjacent point for the neck (→ 8.2.1)
- **ST-12** (*quepen*): meeting point with the L.I., S.I., T.B. and G.B. channels (→ 8.1.10)
- **ST-21** (*liangmen*): adjacent point for the Spleen, Stomach and Gall Bladder (→ 8.2.1)
- **ST-25** (*tianshu*) 🟦🟦: Front-*mu* point of the Large Intestine (→ 8.1.5); adjacent point for the abdominal region (→ 8.2.1)
- **ST-26** (*wailing*): adjacent point for the abdominal region (→ 8.2.1)
- **ST-28** (*shuidao*): local point for the Small Intestine and Bladder (→ 8.2.1)
- **ST-29** (*guilai*): local point for the urogenital region (→ 8.2.1)
- **ST-30** (*qichong*) 🟦⬛: meeting point with the *chong mai*, G.B. channel* (→ 8.1.10); Sea of Water and Grain point (→ 8.1.13); local point for the urogenital region (8.2.1); adjacent point for the abdominal region (→ 8.2.1)
- **ST-34** (*liangqiu*) 🟦⬛: *xi*-cleft point, important adjacent point for disorders of the knee (→ 8.2.1)
- **ST-35** (*dubi*) 🟦⬛: local point for the knee region (→ 8.2.1)
- **ST-36** (*zusanli*) 🟦🟦: *he*-sea point (Earth) (→ 8.1.6), *ben*-point (Five Phase point); Lower *he*-sea point of the Stomach (→ 8.1.9); *Gao Wu* command point (→ 8.1.11) for the abdomen; Sea of Water and Grain point (→ 8.1.13); *Ma Dan Yang* Heavenly Star point (→ 8.1.14); distal point for the Spleen/Stomach and epigastrium (→ 8.2.1); local point for the knee (→ 8.2.1); distal point for the shoulder (→ 8.2.1); adjacent point for the foot (→ 8.2.1)

---

* Mentioned by only some authors.

- **ST-37** (*shangjuxu*) 🟦⬛: Lower *he*-sea point of the Large Intestine (→ 8.1.9); Sea of Blood point (→ 8.1.13); distal point for the Large Intestine (→ 8.2.1)
- **ST-38** (*tiakou*) 🟦⬛: distal point for the shoulder region (→ 8.2.1)
- **ST-39** (*xiajushu*) 🟦⬛: Lower *he*-sea point of the Small Intestine (→ 8.1.9); Sea of Blood point (→ 8.1.13); distal point for the Small Intestine (→ 8.2.1)
- **ST-40** (*fenglong*) 🟦⬛: *luo*-connecting point (→ 8.1.2); main 'Phlegm'-point; distal point for the Lung (→ 8.2.1)
- **ST-41** (*jiexi*) 🟦⬛: *jing*-river point (Fire) (→ 8.1.6); tonification point; local point for the foot (8.2.1); adjacent point for the toes (→ 8.2.1)
- **ST-42** (*chongyang*) 🟦⬛: *yuan*-source point (→ 8.1.1)
- **ST-43** (*xiangu*) 🟦⬛: *shu*-stream point (Wood) (→ 8.1.6)
- **ST-44** (*neiting*) 🟦🟦: *ying*-spring point (Water) (→ 8.1.6); distal point for frontal headaches, as well as for the nose, mouth/teeth and throat (→ 8.2.1); Ma Dan Yang Heavenly Star point (→ 8.1.14)
- **ST-45** (*lidui*) 🟦⬛: *jing*-well point (Metal) (→ 8.1.6); sedation point.

General location help

- **ST-1** to **ST-4**: with the patient looking straight ahead, these points are located on the vertical pupil line
- **ST12** to **ST-18** are all located on the midclavicular/mamillary line, 4 cun lateral to the anterior midline
  - **ST-12**: in the supraclavicular fossa
  - **ST-13**: on the lower border of the clavicle
  - **ST-14** to **ST-18**: in the first to fifth intercostal spaces
- **ST-19** to **ST-30** are all located on a vertical line midway between the mamillary line and the anterior midline, 2 cun lateral to the anterior midline:
  - **ST-19** to **ST-25** are located on the 8 cun section (→ 2.2) between the sternocostal angle and the umbilicus (**ST-19** to **ST-25** are evenly spread on this line, from 6 cun above the umbilicus to the same level as the umbilicus)
  - **ST-26** to **ST-30** are located on the 5 cun section (→ 2.2) between the umbilicus and the upper border of the pubic symphysis (1 cun steps from 4 cun superior to the upper border of the pubic symphysis to its upper border).

Container of Tears CHENGQI ST-1


Orbital margin
ST-1 (below the pupil)

Location

With the eyes looking straight ahead, directly below the centre of the pupil, between the eyeball and the infraorbital ridge.

How to find

With the patient looking straight ahead, the first four points of the ST channel are located on a vertical line drawn through the centre of the pupil. Within the area of the lower eyelid, the infraorbital ridge presents itself as a distinct bony structure. **ST-1** is located on the pupil line, directly superior to the infraorbital ridge.

Needling

Ask the patient to look upward, gently push the eyeball upwards and insert the needle vertically along the orbital ridge in a dorsal direction. Caution: Venous plexus and arteries, avoid injuring the eyeball and periost! Needling recommended only by experienced practitioners! Pay attention to needling pain! No needle manipulation! After removing the needle, press firmly on the insertion site for about one minute to prevent haematoma. Inform the patient that it may still be possible for a haematoma to develop. Moxibustion is contraindicated! Points for disorders of the eyes with less risk of complications include **BL-2**, **T.B.-21**, **G.B.-1**, **ST-2**, **Ex-HN-5** (*taiyang*), **EX-HN-4** (*yuyao*).

Actions/Indications

- Expels Wind and Heat, clears and benefits the eyes

Special features

Meeting point with the *yang qiao mai* and *ren mai*, also with the *du mai* according to some authors, important point for the eyes, entry point.


G.B.-14
Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
Ex-HN-7
ST-1
ST-2
G.B.-2
ST-7
Ex-HN-8
L.I.-20
S.I.-18




Infraorbital margin
ST-2


G.B.-14
G.B.-14
Ex-HN-4 (*yuyao*)
Glabella
Ex-HN-3 (*yintang*)
T.B.-23
B.L.-2
Superciliary arch

ST-2 *Four Whites* SIBAI

Location

With the eyes looking straight ahead, directly below the centre of the pupil, in the depression at the infraorbital foramen.

How to find

With the patient looking straight ahead, the first four points of the ST channel are located on a vertical line drawn through the centre of the pupil. Within the area of the lower eyelid, the infraorbital ridge presents itself as a distinct bony structure. Starting at the infraorbital ridge (→ 3.1.2), palpate inferiorly until you can feel the depression of the infraorbital foramen (this is often located slightly medial to the pupil line), where **ST-2** is located.

Needling

0.3–0.5 cun vertically or transversely (subcutaneously) towards → **S.I.-18** or → **L.I.-20** (for example, in cases of facial paralysis). Deep needling (in an oblique cranial direction) is contraindicated. Caution: Infraorbital nerve, eye injury. According to some classic texts, moxibustion is contraindicated.

Actions/Indications

- Benefits the eyes, clears Heat, eliminates Wind

Special features

Important local point for disorders of the eyes, pain and paralysis of the face; meeting point with the *yang qiao mai* according to some authors. A less risky substitute for → **ST-1**.





Great Crevice JULIAO ST-3




G.B.-14
Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
Ex-HN-7
ST-1
ST-2
Ex-HN-8
G.B.-2
ST-7
L.I.-20
S.I.-18


Zygomatic bone
(zygoma)
Infraorbital foramen
ST-2
S.I.-18


Midpoint of the lateral border
of the ala nasi
L.I.-20
Nasolabial groove

Location

With the patient looking straight ahead, directly below the centre of the pupil, on the level of the lower border of the ala nasi.

How to find

With the patient looking straight ahead, the first four points of the ST channel are located on a vertical line drawn through the centre of the pupil (pupil line). **ST-3** is located at the crossing point of the pupil line and a horizontal line on the level of the lower border of the ala nasi.

Needling

Vertically or obliquely 0.3–0.5 cun or penetration method: transversely (subcutaneously) towards → **ST-4,** → **S.I.-18**, etc, for example, in cases of peripheral facial paralysis.

Actions/Indications

- Expels Wind, opens the channel, disperses accumulations

Special features

Meeting point with the *yang qiao mai*

ST-4 *Earth Granary* DICANG

Location

With the patient looking straight ahead, directly below the centre of the pupil and approximately 0.4 cun lateral to the corner of the mouth.

How to find

With the patient looking straight ahead, the first four points of the ST channel are located on a vertical line drawn through the centre of the pupil (pupil line). **ST-4** is located at the crossing point of the pupil line and a horizontal line originating at the corner of the mouth. The point is located in the nasolabial groove (➞ 3.1.2), approximately 0.4 cun lateral to the corner of the mouth. Ask the patient to smile in order to make the line more clearly visible.

Needling

Obliquely in a lateral direction or vertically 0.3–0.5 cun or penetration method: transversely (subcutaneously) approximately 1.5–2 cun in cases of facial paralysis towards ➞ **ST-6**, for trigeminal neuralgia towards ➞ **L.I.-20**. Caution: Facial artery/vein.

Actions/Indications

- Expels Wind (from the face), opens the channel, alleviates pain, relaxes the facial musculature
- Sometimes as distal point for disorders of the leg

Special features

Meeting point with the L.I. channel, the *ren mai* and *yang qiao mai* (also with the *du mai* according to some authors). Important local point for neuralgias and pareses affecting the mouth and cheeks.







Great Welcome DAYING ST-5


Masseter
ST-6
ST-5

Location

On the lateral mandible, anterior to the masseter muscle.

How to find

By asking the patient to clench their teeth, the anterior border of the masseter muscle becomes clearly palpable. **ST-5** is located directly anterior to the border of the muscle, in a shallow depression on the mandible and slightly above the angle of the jaw. Here, the facial artery can be palpated.

Needling

0.3–0.5 cun obliquely or transversely (subcutaneously) in the direction of → **ST-6**. Caution: Facial artery/vein.

Actions/Indications

- Expels Wind, opens the channels

Special features

Meeting point with the G.B. channel according to some authors


Ex-HN-5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
ST-7
G.B.-2
S.I.-18
T.B.-17
G.B.-20
G.B.-12
Ex-HN
(*anmian*)
ST-5
ST-6
S.I.-17
T.B.-16
Ren-23
L.I.-18
S.I.-16
ST-9
L.I.-17


Ex-HN-8
(*bitong*)
Nasolabial groove
L.I.-20
Maxilla
(upper
jaw)


S.I.-18
ST-6
ST-5
Masseter


Masseter
Zygomatic
bone
Mandibular
angle
S.I.-18
T.B.-16
ST-5
Sternocleidomastoid
ST-6
S.I.-17

ST-6 *Jaw Bone* JIACHE

Location

With the teeth clenched, on the highest prominence of the masseter muscle, approximately one finger-width (middle finger) anterior and superior to the angle of the jaw.

How to find

Ask the patient to clench their teeth, which will allow the muscle belly of the masseter muscle to bulge. **ST-6** is located on its prominence, a little anterior and superior to the angle of the jaw (mandibular angle → 3.1.3). With chewing movements of the jaw ('biting and relaxing'), the palpating finger will naturally fall into the right depression when the muscle is relaxed.

→ **ST-5** is located more medially in the depression at the anterior border of the masseter muscle.

Needling

Insertion with the patient's mouth slightly opened (relaxed masseter muscle). Vertically 0.3–0.5 cun or obliquely or transversely (subcutaneously) 1–1.5 cun in the direction of → **ST-4**, **ST-5**, **ST-7**, for example, in cases of facial paralysis.

Actions/Indications

- Eliminates Wind, benefits the jaw and teeth, opens the channel and *luo* vessels, alleviates pain

Special features

Sun Si Miao Ghost point. Important local point for the jaw region. Its location corresponds to a commonly used trigger point on the masseter muscle. According to some authors, **ST-6** is a meeting point with the G.B. channel.


Masseter
Zygomatic bone
S.I.-18
Mandibular angle
T.B.-16
ST-5
ST-6
S.I.-17
Sternocleidomastoid


Masseter
ST-6
ST-5


G.B.-19
T.B.-21
S.I.-19
ST-7
G.B.-2
S.I.-18
G.B.-20
T.B.-17
G.B.-12
Ex-HN (*anmian*)
ST-5
ST-6
S.I.-17
T.B.-16
Ren-23
L.I.-18
S.I.-16
ST-9


S.I.-18
ST-6
ST-5
Masseter

Below the Joint XIAGUAN ST-7

Location

With the mouth closed, at the lower border of the zygomatic arch (→ 3.1.2) in the centre of the depression of the mandibular fossa, between the coronoid process and the condyloid process of the mandible.

How to find

Palpate along the lower border of the zygomatic arch (→ 3.1.2) towards the ear. **ST-7** is located in a clearly palpable depression just before the temporomandibular joint and at the posterior border of the masseter muscle (clench teeth). To confirm: When the patient's mouth is fully opened, the condyloid process of the lower jaw slides anteriorly and the depression disappears (figure modified after Deadman et al).

→ **G.B.-3** is located directly superior to **ST-7**, on the upper border of the zygomatic arch.

Needling

Insert the needle with the patient's mouth closed. 0.3–0.5 cun vertically or 1–1.5 cun transversely (subcutaneously) in the direction of → **ST-6**, → **S.I.-19**, → **S.I.-18**.

Actions/Indications

- Opens the channel, benefits the jaw and teeth, alleviates pain
- Benefits the ears

Special features

Meeting point with the G.B. channel. Important local point and frequently used trigger point.


Coronoid process of the mandible
Zygomatic arch
ST-7 in the mandibular incisure
G.B.-3
Condyloid process of the mandible
Styloid process
Mouth closed
Posterior border of the masseter
Location of ST-7 with the mouth open*


T.B.-23
T.B.-20
Ex-HN-5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
S.I.-18
ST-7
G.B.-2
G.B.-20
T.B.-17
G.B.-12
Ex-HN (anmian)
ST-5
ST-6
S.I.-17
T.B.-16
Ren-23


Occipital bone
T.B.-23
ST-7
Zygomatic arch
Mandibular angle


Mandibular notch
Head of the mandible
Articular disc
External auditory meatus
Condyloid process
Ramus of the mandible
Coronoid process

---

* According to Deadman et al 1998.

ST-8 *Head's Binding* TOUWEI

Location

At the temporal corner of the forehead, on the border of the temporalis muscle and 0.5 cun within the anterior hairline or 4.5 cun lateral to the anterior midline (→ **Du-24**).

How to find

First, find the anterior hairline (→ 3.1.1). Then locate **ST-8** at the temporal corner of the forehead 0.5 cun within the hairline. Chewing movements of the temporalis muscle will still be palpable here.

Also located 0.5 cun superior to the anterior hairline are → **Du-24/BL-3/BL-4/G.B.-15/G.B.-13** (anterior midline/superior to the inner canthus of the eye/1.5 cun lateral to the anterior midline/3 cun lateral to the anterior midline). These distances refer to the distance between → **Du-24** and **ST-8** (=4.5 cun, → 2.2). **ST-8** and → **G.B.-7** (a depression on the level of the apex of the ear, within the temporal hairline) mark the endpoints of a curved line, on which **ST-8 and** → **G.B.-4–7** are located at regular intervals (by dividing the line into five parts).

Needling

0.5–1 cun transversely (subcutaneously) or obliquely in the direction of the disorder. Moxibustion possible (contraindicated according to some classical texts).

Actions/Indications

- Eliminates Wind from the head and eyes, benefits the eyes, alleviates pain

Special features

Meeting point with the *yang wei mai* and the G.B. channel. Important local point for headaches and disorders of the eyes.


BL-5
Du-23
G.B.-15
BL-4
Du-24
ST-8
G.B.-13
BL-3
G.B.-14
Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
Ex-HN-7
ST-1
ST-2


G.B.-7
T.B.-20
Circumauricular
hairline




ST-8
Chewing movement
still palpable
Temporalis


Original hairline
ST-8

Man's Welcome RENYING **ST-9**


ST-9
L.I.-18
S.I.-16
Laryngeal prominence
Clavicular head
Sternal head
Sternocleidomastoid


S.I.-18
ST-7
G.B.-2
T.B.-17
G.B.-20
G.B.-12
Ex-HN (*anmian*)
ST-5
ST-6
S.I.-17
T.B.-16
Ren-23
L.I.-18
S.I.-16
ST-9
L.I.-17
ST-12
ST-11


Hyoid bone
Superior thyroid notch
Laryngeal prominence
Thyroid cartilage
**
Tracheal cartilage

Location

1.5 cun lateral to the anterior midline, on the level of the laryngeal prominence and at the anterior border of the sternocleidomastoid muscle.

How to find

From the laryngeal prominence, palpate posteriorly to the anterior border of the sternocleidomastoid muscle (→ 3.2). **ST-9** is located at the anterior border of the muscle, which becomes more clearly visible and palpable if the patient's head is turned in the opposite direction.

Located on the same level are → **S.I.-16** on the posterior border of the sternocleidomastoid muscle and **L.I.-18** between the two heads of the sternocleidomastoid muscle.

Needling

If necessary, move the head to its normal position before needling. Caution: Carotid artery, carotid sinus, jugular veins. The carotid artery is located directly at the anterior border of the sternocleidomastoid muscle. The needle should be inserted anterior to where you can feel the pulsating of the carotid artery. Vertically 0.5–1 cun between the artery and the thyroid cartilage. For reasons of safety, the artery should be held in a lateral position with one finger of the palpating hand above and one finger below the insertion site. Irritation of the carotid sinus can lead to a lowering of the blood pressure and fainting!

Actions/Indications

- Regulates the Qi
- Opens the channel
- Harmonises excess or deficiency in the thorax

Special features

Window of Heaven point, Sea of Qi point, meeting point with the G.B. channel.


External jugular vein
Transverse cervical nerve

ST-10 *Water Prominence* SHUITU

Location

On the anterior border of the sternocleidomastoid muscle, at the midpoint of a line connecting ➞ **ST-9** and **ST-11**.

How to find

➞ **ST-9** and **ST-10** are both located on the anterior border of the sternocleidomastoid muscle (➞ 3.2). ➞ **ST-11** is located posterior to the sternal head. Place the middle finger of the left hand onto ➞ **ST-9** on the level of the laryngeal prominence and the thumb on ➞ **ST-11** posterior to the sternal insertion. **ST-10** is located at the midpoint between the two fingers. With the patient's head rotated in the opposite direction, the muscle will be more visible and can be more easily palpated.

Needling

0.5–1 cun obliquely in a medial direction, away from the artery. Caution: Carotid artery, jugular veins. If necessary, rotate the head back to a middle position before needling.

Actions/Indications

- Regulates the Lung Qi
- Benefits the throat


Laryngeal prominence
ST-9
1/2
ST-10
1/2
ST-11


S.I.-18
ST-7
G.B.-2
G.B.-20
T.B.-17
G.B.-12
Ex-HN
(*anmian*)
ST-5
ST-6
S.I.-17
T.B.-16
Ren-23
L.I.-18
ST-9
S.I.-16
L.I.-17
ST-12
ST-11


ST-9
Sternocleido-
mastoid
L.I.-18
S.I.-16
L.I.-17
Laryngeal
prominence
ST-11
Sternal
head
Clavicular
head

Qi Abode QISHE ST-11


Laryngeal prominence
ST-9
1/2
ST-10
1/2
ST-11

Location

On the upper border of the clavicle, between the tendons of the sternal and clavicular heads of the sternocleidomastoid muscle.

How to find

By rotating the patient's head in the opposite direction (especially against resistance), the ropey sternal insertion of the sternocleidomastoid muscle (→ 3.2) becomes clearly visible. **ST-11** is located in a shallow depression, the minor supraclavicular fossa, between the sternal insertion and the more extended insertion of the clavicular head.

Needling

Vertically 0.3–0.5 cun. Caution: Pneumothorax, jugular veins.

Actions/Indications

- Benefits the throat and neck
- Regulates counterflow Qi


External jugular vein
Transverse cervical nerve


Minor supraclavicular fossa
Suprasternal fossa
Major supraclavicular fossa
Clavicle
ST-12
Ren-22
ST-11

ST-12 *Empty Basin* QUEPEN



Location

In the supraclavicular fossa, superior to the midpoint of the clavicle, approximately 4 cun lateral to the anterior midline.

How to find

From the anterior midline, palpate to the midpoint of the clavicle (=4 cun in a lateral direction). There, an imaginary vertical line marks the midclavicular line. **ST-12** is located on the midclavicular line, at the upper border of the clavicle, in the supraclavicular fossa, lateral to the clavicular head of the sternocleidomastoid muscle.

Needling

Vertically 0.3–0.5 cun. The needle should be guided along the posterior border of the clavicle. Caution: Pneumothorax, especially with emphysema; superficial and deep cervical arteries. According to some authors, this point is contraindicated during pregnancy.

Actions/Indications

- Opens the channel
- Disperses and descends the Lung Qi
- Clears Heat in the throat

Special features

Meeting point with the L.I., S.I., G.B. and T.B. channel


S.I.-18
ST-7
G.B.-2
G.B.-20
T.B.-17
G.B.-12
Ex-HN
(*anmian*)
ST-5
ST-6
S.I.-17
T.B.-16
Ren-23
L.I.-18
S.I.-16
ST-9
L.I.-17
ST-12
ST-11


Minor supraclavicular fossa
Suprasternal fossa
Major supraclavicular fossa
Clavicle
ST-12
ST-11
Ren-22

Qi Door QIHU ST-13











Location

At the midpoint of the clavicle and on its inferior border, 4 cun lateral to the anterior midline.

How to find

On the upper thorax region, the midclavicular line (4 cun lateral to the anterior midline) runs slightly obliquely from the clavicular midpoint to the generally more lateral nipple. Find the midpoint of the clavicle (or measure 4 cun lateral to the midline) and locate **ST-13** at the lower border of the clavicle. Since the 1st rib curves posteriorly in a short bow, **ST-13** is generally situated lateral to the 1st rib.

→ **KID-27** is located medial to **ST-13**, but inferior to the lower border of the clavicle and 2 cun lateral to the anterior midline. → **Ren-21** is located on the midline. → **ST-14** is located only slightly inferior to **ST-13** in the 1st intercostal space.

Needling

0.3–0.5 cun obliquely in a lateral or medial direction or transversely (subcutaneously) along the channel pathway. Caution: Pneumothorax, subclavicular artery/vein.

Actions/Indications

- Descends counterflow Qi
- Clears Heat
- Unbinds the chest

ST-14 *Store House* KUFANG

Location

On the midclavicular line, in the first intercostal space, 4 cun lateral to the anterior midline.

How to find

On the upper thorax, the midclavicular line (4 cun lateral to the anterior midline) runs slightly obliquely from the clavicular midpoint to the generally more lateral nipple. By palpating across the clavicle from superior to inferior, the first rib will generally be felt directly below the clavicle, although, in some cases, the 1st rib might be completely hidden under the clavicle. The 1st intercostal space follows directly inferior to the 1st rib, where **ST-14** is located.

→ **ST-13** is located only slightly superior to **ST-14** at the lower border of the clavicle. Also located on the level of the first intercostal space are → **Ren-20** (anterior midline), → **KID-26** (2 cun lateral to the anterior midline) and → **LU-1** (6 cun lateral to the midline). For more detail about orientation regarding intercostal spaces → 3.5.

Needling

0.5–0.8 cun obliquely or transversely (subcutaneously), parallel to the course of the intercostal space or with or against the channel pathway. Caution: Pneumothorax.

Actions/Indications

- Regulates the Qi
- Unbinds the chest
- Benefits the breasts


LU-2
Suprasternal fossa
1 cun
Midline
LU-1


ST-13
1st intercostal space
ST-14
2nd intercostal space
ST-15
3rd intercostal space
ST-16
4th intercostal space
ST-17


ST- 9
12
Ren-22
KID-27
14 26
20
SP-20
25
19
19
16
24
18
17


Ren-21
Ren-20


KID-27
KID-26
1st intercostal space

Room Screen WUYI ST-15


ST-13
1st intercostal space
ST-14
2nd intercostal space
ST-15
3rd intercostal space
ST-16
4th intercostal space
ST-17


Ren-21
Ren-20
2nd intercostal space
Ren-19


KID-25
2nd intercostal space
KID-24
KID-23
Ren-17


LU-1
SP-20
1st intercostal space
SP-19
2nd intercostal space
3rd intercostal space

Location

In the 2nd intercostal space, on the midclavicular line, 4 cun lateral to the anterior midline.

How to find

On the upper thorax, the midclavicular line (4 cun lateral to the anterior midline) runs slightly obliquely from the clavicular midpoint to the generally more lateral nipple. Locate the 2nd intercostal space by palpating downward from the clavicle or by palpating from the manubriosternal synchondrosis (second rib) (→ 3.5). Then palpate along its course to the midclavicular line, where **ST-15** is located. Note the ascending course of the intercostal space! Located on the same level are → **Ren-19** (anterior midline), → **KID-25** (2 cun lateral to the anterior midline) and → **SP-20** (6 cun lateral to the midline).

Needling

0.5–0.8 cun obliquely or transversely (subcutaneously), parallel to the course of the intercostal space or with or against the channel pathway. Caution: pneumothorax.

Actions/Indications

- Regulates the Lung Qi
- Unbinds the chest
- Benefits the breasts and clears Heat

ST-16 *Breast Window* YINGCHUANG


ST-13
1st intercostal space
ST-14
2nd intercostal space
ST-15
3rd intercostal space
ST-16
4th intercostal space
ST-17

Location

In the 3rd intercostal space, on the midclavicular line, 4 cun lateral to the anterior midline.

How to find

On the upper thorax, the midclavicular line (4 cun lateral to the anterior midline) runs slightly obliquely from the clavicular midpoint to the generally more lateral nipple. Locate the 3rd intercostal space by palpating downward from the clavicle or by palpating from the manubriosternal synchondrosis (second rib) (➞ 3.5). Then palpate along its course to the midclavicular line, where **ST-16** is located. Note the ascending course of the intercostal space! In male patients, this point can also be located by counting one intercostal space upward from the level of the nipple.

Located on the same level are ➞ **Ren-18** (anterior midline), ➞ **KID-24** (2 cun lateral to the anterior midline) and ➞ **SP-19** (6 cun lateral to the midline).

Needling

0.5–0.8 cun obliquely or transversely (subcutaneously), along the course of the intercostal space or with or against the flow of the channel. Caution: pneumothorax.

Actions/Indications

- Regulates the Qi
- Unbinds the chest
- Benefits the breasts


LU-1
SP-20
SP-19
1st intercostal space
2nd intercostal space
3rd intercostal space


ST-9
12
Ren-22
KID-27
14
26
20
SP-20
25
19
19
16
24
18
17


Ren-19
3rd intercostal space
Ren-18
Ren-17
Ren-16


KID-24
3rd intercostal space
KID-23
Ren-17
KID-22

Breast Centre RUZHONG ST-17


ST-13
1st intercostal space
ST-14
2nd intercostal space
ST-15
3rd intercostal space
ST-16
4th intercostal space
ST-17


ST-13
Clavicle
Midclavicular line
ST-17
ST-18
LIV-14
G.B.-24


Level of the nipples
4th intercostal space
Ren-17


KID-24
4th intercostal space
KID-23
Ren-17
KID-22

Location

In the centre of the nipple.

How to find

In the centre of the nipple. In men, this is usually located 4 cun lateral to the anterior midline, at the level of the 4th intercostal space and is also used for reference.
In men, also located on the same level are → **Ren-17** (anterior midline), → **KID-23** (2 cun lateral to the anterior midline), → **SP-18** (6 cun lateral to the midline), → **P-1** (1 cun lateral to the nipple), → **G.B.-22** and → **G.B.-23**. In women, the location of the nipples varies considerably and should therefore not be used for reference.

Needling

No therapy; this point is for reference only.


SP-18
4th intercostal space
6 cun


1cun
P-1
4th intercostal space


G.B.-23
4th intercostal space
G.B.-22
1 cun

ST-18 *Breast Root* RUGEN

Location

In the 5th intercostal space, on the mamillary line, 4 cun lateral to the anterior midline.

How to find

The mamillary line, a vertical line used for reference, is located 4 cun lateral to the anterior midline (➞ 3.5). In men, the nipple is generally located on the level of the 4th intercostal space, and **ST-18** is located in the intercostal space directly below. The point is often located at the lower border of the pectoralis major muscle; in women, it is often found at the root of the breast. Location help in women: Find the 5th intercostal space by palpating downward from the clavicle or from the manubriosternal synchondrosis (second rib) (➞ 3.5). Then follow the course of the intercostal space laterally to the mamillary line and there locate **ST-18**. Note the ascending course of the intercostal spaces!

Located on the same level are ➞ **Ren-16** (anterior midline), ➞ **KID-22** (2 cun lateral to the anterior midline) and ➞ **SP-17** (6 cun lateral to the midline).

Needling

0.5–0.8 cun obliquely or transversely (subcutaneously), parallel to the course of the intercostal space or with or against the channel pathway. Caution: Pneumothorax.

Actions/Indications

- Benefits the breasts, moves the Blood
- Unbinds the chest
- Regulates the Lung Qi

Special features

Important local point


Sternocostal
angle
ST-18
2 cun


SP-20
25
19
19
16
24
18
17
17
18
22
15
LIV-14
G.B.-24
Sternocostal
8 angle
7
6
5


Sterno-
costal
angle
Ren-16


KID-24
KID-23
KID-22
Ren-17
5th intercostal space


5th intercostal
space
SP-17
6 cun

Not Contained BURONG ST-19









Location

2 cun below the sternocostal angle and 2 cun lateral to the anterior midline.

How to find

The distance between the sternocostal angle and the centre of the umbilicus is divided into 8 cun, which can vary considerably from the patient's finger cun; therefore, only proportional cun measurements should be used (helpful tool: elastic tape → 2.3.1). First, measure 2 cun down from the sternocostal angle. **Or:** Measure the midpoint of the upper half of the distance between the umbilicus and the subcostal angle (→ **Ren-12**: spreading hands technique → 2.3.3). From there, measure 2 cun in a lateral direction to locate **ST-19**. As its location depends on the shape of the thorax, it might be located either on the rib or on the abdomen. Located on the same level are → **Ren-14** (anterior midline), → **KID-21** (0.5 cun lateral to the anterior midline) and → **LIV-14** (on the mamillary line and in the 6th intercostal space). Please note: From **ST-19** onwards, the ST channel is located only 2 cun lateral to the anterior midline.

Needling

Vertically 0.5–1 cun. If the correct location projects this point on the lower ribcage, needle transversely on the rib or locate the point more medially (or choose an alternative point) Caution: Peritoneum, pericardium.

Actions/Indications

- Regulates the Stomach, Intestines and Middle Burner
- Regulates the Lung Qi

ST-20 *Supporting Fullness* CHENGMAN

Location

3 cun below the sternocostal angle (or 5 cun above the umbilicus) and 2 cun lateral to the anterior midline.

How to find

The distance between the sternocostal angle and the centre of the umbilicus is divided into 8 cun, which can vary considerably from the patient's finger cun; therefore, only proportional cun measurements should be used (helpful tool: elastic tape → 2.3.1). First, measure 3 cun down from the sternocostal angle. **Or:** Measure 1 cun up from the midpoint of the distance between the umbilicus and the sternocostal angle (→ **Ren-12**: spreading hands technique → 2.3.3). From there, measure 2 cun in a lateral direction to locate **ST-20**. Depending on the shape of the thorax, **ST-20** might be located on the lower border of the ribcage in some cases (narrow subcostal angle).

Located on the same level are → **Ren-13** (anterior midline) and → **KID-20** (0.5 cun lateral to the anterior midline) and → **G.B.-24** (on the mamillary line, in the 7th intercostal space).

Needling

Vertically 0.5–1 cun. If the correct location projects this point on the lower ribcage, needle transversely on the rib or locate the point more medially (or choose an alternative point). Caution: Peritoneum.

Actions/Indications

- Regulates the Middle Burner and the Stomach Qi
- Regulates the Lung Qi


Sternocostal angle
3 cun
ST-19
ST-20
2 cun


17
18
22
15
LIV-14
G.B.-24
12
16
22
18
LIV-13
15
25
16
8
14
Sterno-costal angle
8
7
6
5
4
3
2
1
Umbilicus
1


3 cun
Ren-13
8 cun


KID-20
KID-19
KID-18
KID-17
Ren-13
Ren-12
Ren-11
Ren-10
5 cun
8 cun


6
7
G.B.-24
in 7th intercostal space

Beam Gate LIANGMEN ST-21


Midline
Mamillary line
Sterno-costal angle
2 cun
2 cun
1/2
ST-21
Ren-12
1/2
Umbilicus


Needle in Ren-12
ST-21




KID-19
KID-18
KID-17
Ren-12
Ren-11
Ren-10
8 cun
4 cun

Location

2 cun lateral to the anterior midline, 4 cun above the umbilicus (or 4 cun below the subcostal angle).

How to find

The distance between the sternocostal angle and the centre of the umbilicus can be divided into 8 cun, which can vary considerably from the patient's finger cun; therefore, only proportional cun measurements should be used (helpful tool: elastic tape → 2.3.1). **Quick method:** Find the midpoint between the umbilicus and the sternocostal angle (→ **Ren-12**) by using the spreading hands technique (→ 2.3.3), then measure 2 cun in a lateral direction to locate **ST-21**. Depending on the shape of the thorax, this can be located on the lower rib cage.
Located on the same level are → **Ren-12** (anterior midline) and → **KID-19** (0.5 cun lateral to the anterior midline).

Needling

Vertically 0.5–1 cun. If the correct location projects this point on the lower ribcage, needle transversely on the rib or locate the point more medially (or choose an alternative point). Caution: Peritoneum, enlarged liver (on the right), pregnancy.

Actions/Indications

- Regulates the Qi, harmonises the Middle Burner, eliminates stagnation, raises the Qi and stops diarrhoea

Special features

Important local point for distension and pain in the epigastrium and the lateral abdomen

ST-22 *Pass Gate* GUANMEN

Location

3 cun above the umbilicus (or 5 cun inferior to the sternocostal angle) and 2 cun lateral to the anterior midline.

How to find

The distance between the sternocostal angle and the centre of the umbilicus can be divided into 8 cun, which can vary considerably from the patient's finger cun; therefore, only proportional cun measurements should be used (helpful tool: elastic tape → 2.3.1). First, measure 3 cun up from the umbilicus. **Or:** Measure 1 cun downward from the midpoint of the distance between the umbilicus and the sternocostal angle (→ **Ren-12**: spreading hands technique → 2.3.3). **ST-22** is located 2 cun lateral from here. Located on the same level are → **Ren-11** (anterior midline), → **KID-18** (0.5 cun lateral to the anterior midline) and → **SP-16** (4 cun lateral to the midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Regulates the Stomach and Intestines
- Regulates the water passages


2 cun
ST-22
3 cun


4 cun
SP-16
3 cun
SP-15


17
18
22
15
LIV-14
G.B.- 24
12
16
22
18
LIV-13
15
25
16
8
14
8
Sterno-
costal
angle
7
6
5
4
3
2
1
Umbilicus
1


Ren-11
3 cun
Umbilicus


KID-18
Ren-11
KID-17
Ren-10
2 cun
0.5 cun
Umbilicus

Supreme Unity TAIYI ST-23



Location

2 cun above the umbilicus and 2 cun lateral to the anterior midline.

How to find

The distance between the sternocostal angle and the centre of the umbilicus is divided into 8 cun, which can vary considerably from the patient's finger cun; therefore, only proportional cun measurements should be used (helpful tool: elastic tape → 2.3.1). First, measure 2 cun up from the umbilicus. **Or:** Measure the midpoint of the lower half of the distance between the umbilicus and the subcostal angle (→ **Ren-12**: spreading hands technique → 2.3.3). **ST-23** is located 2 cun lateral from here.

Located on the same level are → **Ren-10** (anterior midline), → **KID-17** (0.5 cun lateral to the anterior midline) and → **Ex-CA** (*weishang*; 4 cun lateral to the midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Harmonises the Middle Burner, strengthens the Spleen
- Benefits the Heart and calms the *shen*







ST-24 *Slippery Flesh Gate* HUAROUMEN

Location

1 cun above the umbilicus and 2 cun lateral to the anterior midline.

How to find

The distance between the sternocostal angle and the centre of the umbilicus is divided into 8 cun, which can vary considerably from the patient's finger cun; therefore, only proportional cun measurements should be used (helpful tool: elastic tape → 2.3.1). **ST-24** is located 1 cun above the umbilicus and 2 cun lateral to the anterior midline.
Located on the same level is → **Ren-19** (anterior midline); often, also → **LIV-13** (at the free end of the 11th rib) will be located at this level.

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Regulates the Stomach
- Transforms Phlegm and calms the *shen*


2 cun
ST-24
1 cun


17
18
22
15
LIV-14
G.B.-24
12
16
22
18
LIV-13
15
25
16
8
14
Sterno-costal angle
8
7
6
5
4
3
2
1
Umbilicus
1


Umbilicus
1 cun
Ren-9
Ren-8


11th rib
LIV-13

Heaven's Pivot TIANSHU ST-25



Location

2 cun lateral to the umbilicus.

How to find

Measure 2 cun lateral from the centre of the umbilicus. **For reference:** On the abdomen, 2 cun lateral corresponds to the midpoint between the anterior midline and the mamillary line (→ 3.5). Located on the same level are → **Ren-8/KID-16/SP-15/G.B.-26** (umbilicus/0.5 cun lateral to the umbilicus/mamillary line or 4 cun lateral to the umbilicus/at the level of the umbilicus and directly inferior to the free end of the 11th rib).

Needling

Vertically 0.5–1.5 cun. For gynaecological disorders, obliquely in an inferior direction towards the uterus. Caution: Peritoneum, pregnancy. The needle may reach the aponeuroses of the oblique abdominal musculature at the transition to the sheath of the rectus abdominis muscle.

Actions/Indications

- Regulates the Spleen, Stomach and Intestines, eliminates Dampness and clears Damp-Heat
- Eliminates stagnation

Special features

Front-*mu* point of the Large Intestine. Important point for disorders of the gastrointestinal tract.











ST-26 *Outer Mound* WAILING

Location

1 cun below the umbilicus and 2 cun lateral to the anterior midline.

How to find

The distance between the umbilicus and the upper border of the pubic symphysis is divided into 5 proportional cun, which can vary considerably from the patient's finger cun; therefore, only proportional cun measurements should be used (helpful tool: elastic tape ➞ 2.3.1). From the umbilicus, measure 1 cun down: **ST-26** is located 2 cun laterally from there.
Located on the same level are ➞ **Ren-7** (anterior midline) and ➞ **KID-15** (0.5 cun lateral to the anterior midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Regulates the Qi, alleviates pain and Cold


2 cun
ST-25
1 cun
ST-26
Upper border of the pubic symphysis


LIV-13
15
25
16
8
14
6
27
14
4
29
12
13
SP-12
ST-30
KID-11
Ren-2
2
1
Umbilicus
1
2
3
4
Upper border of the pubic symphysis


Ren-8
Umbilicus
1 cun
Ren-7


KID-16
Umbilicus
Ren-08
KID-15
Ren-07
Ren-06

The Great DAJU **ST-27**







Location

2 cun below the umbilicus and 2 cun lateral to the anterior midline.

How to find

The distance between the umbilicus and the upper border of the pubic symphysis is divided into 5 proportional cun, which can vary considerably from the patient's finger cun; therefore, only proportional cun measurements should be used (helpful tool: elastic tape → 2.3.1). From the umbilicus, measure 2 cun down and 2 cun laterally, where **ST-27** is located.
Located on the same level are → **Ren-5** (anterior midline) and → **KID-14** (0.5 cun lateral to the anterior midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Regulates and strengthens the Qi
- Benefits the Kidneys and promotes diuresis, strengthens the Yang and Essence (*jing*)

ST-28 *Water Passage* SHUIDAO

Location

3 cun below the umbilicus or 2 cun above the upper border of the pubic symphysis and 2 cun lateral to the anterior midline.

How to find

The distance between the umbilicus and the upper border of the pubic symphysis is divided into 5 proportional cun, which can vary considerably from the patient's finger cun; therefore, only proportional cun measurements should be used (helpful tool: elastic tape → 2.3.1). From the upper border of the pubic symphysis, measure 2 cun up or measure 3 cun down from the umbilicus. **ST-28** is located 2 cun laterally from there.

Located on the same level are → **Ren-4** (anterior midline), → **KID-13** (0.5 cun lateral to the anterior midline) and → **Ex-CA** (*tituo/quimen/yijing*; 4/3/1 cun lateral to the anterior midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, urinary bladder, pregnancy.

Actions/Indications

- Clears Damp-Heat, benefits the Lower Burner and eliminates stagnation

Special features

Important local point for the urogenital tract


2 cun
3 cun
ST-28
2 cun
Upper border of the pubic symphysis


tituo
qimen
yijing
Ren-4
1 cun
2 cun
3 cun
Ren-2
4 cun
Midline
Upper border of the pubic symphysis


LIV-13
15
25
16
8
14
27
6
14
4
29
12
13
SP-12
ST-30
KID-11
Ren-2
2
1
Umbilicus
1
2
3
4
Upper border of the pubic symphysis


Ren-4
2 cun
Ren-2


5 cun
KID-13
Ren-04
KID-12
Ren-03

Return GUILAI ST-29


2 cun
ST-29
1 cun
ST-30
Upper border of the
pubic symphysis


Ren-3
Ren-2
1 cun


KID-12
Ren-03
KID-11
Ren-02
Upper border
of the pubic
symphysis


Ex-CA-1
(*zigong*)
3 cun
Ren-3
Ren-2
1 cun

Location

1 cun above the upper border of the pubic symphysis or 4 cun below the umbilicus and 2 cun lateral to the anterior midline.

How to find

The distance between the umbilicus and the upper border of the pubic symphysis is divided into 5 proportional cun, which can vary considerably from the patient's finger cun; therefore, only proportional cun measurements should be used (helpful tool: elastic tape ➞ 2.3.1). From the upper border of the pubic symphysis, measure 1 cun up and 2 cun lateral to **ST-29**.
Located on the same level are ➞ **Ren-3** (anterior midline), ➞ **KID-12** (0.5 cun lateral to the anterior midline) and ➞ **Ex-CA** (*zigong*; 3 cun lateral to the anterior midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, urinary bladder, pregnancy.

Actions/Indications

- Warms and regulates the Lower Burner and menstruation

Special features

Commonly treated with moxibustion, the combination of acupuncture and moxibustion being particularly beneficial. Important local point for the urogenital tract.

ST-30 *Rushing Qi* QICHONG

Location

2 cun lateral to the upper border of the pubic symphysis and medial to the femoral artery and vein, approximately 1 cun superior to the inguinal groove.

How to find

First, locate the upper border of the pubic symphysis (location of → **Ren-2**). Then locate **ST-30** 2 cun lateral from there (on the vertical line halfway between the anterior midline and the mamillary line). This often corresponds with a location 1 cun superior to the inguinal groove and medial to the femoral artery/vein.
Located on the same level are → **Ren-2/KID-11/SP-12** (anterior midline/0.5 cun lateral to the anterior midline/3.5 cun lateral to the anterior midline). → **LIV-12** is located in the inguinal groove, 1 cun inferior and 0.5 cun lateral to **ST-30**.

Needling

0.5–1 cun vertically or 1.5 cun slightly obliquely towards the external genitalia for disorders of the urogenital tract. Caution: Femoral artery, urinary bladder (quite superficial in a superior direction); in men, the spermatic ducts (quite superficial in an inferior direction), pregnancy. Ask the patient to empty their bladder before needling this point.

Actions/Indications

- Regulates the Qi in the Lower Burner
- Strengthens the Sea of Grain (later Heaven Qi)

Special features

Meeting point with the *chong mai* (according to some authors, also with the G.B. channel), Sea of Grain point. Wide usage for disorders of the Lower Burner.


Umbilicus
(Ren-8)
Anterior superior
iliac spine
KID-15
Ren-6
G.B.-27
ST-28
Ren-2
Symphysis
ST-30
SP-12


Femoral-
nerve
artery
vein
SP-13
0.7 cun
ST-30
Upper border
of the pubic
symphysis
SP-12
Symphysis
2 cun




LIV-13
2
1
15
25
16
8
Umbilicus
14
1
6
27
14
2
4
3
29
12
4
13
SP-12
ST-30
KID-11
Ren-2
Upper border
of the pubic
symphysis


KID-12
Ren-03
KID-11
Ren-02
Upper border
of the pubic
symphysis


Ren-2
Upper border
of the pubic
symphysis
1 cun
LIV-12

Thigh Gate BIGUAN ST-31


Anterior superior iliac spine
ST-31
Upper border of the pubic symphysis
Sartorius
Upper patellar border
Lateral patellar border


Ren-3
ST-30
Ren-2
SP-12
ST-31
KID-11
Upper border of the pubic symphysis
Highest prominence of the greater trochanter
LIV-11
LIV-10
19 cun
SP-11
ST-32
ST-33
Ex-LE-3
LIV-9
ST-34
SP-10
Ex-LE-2
Ex-LE-1
Upper border of the patella
Popliteal crease
ST-35
Ex-LE-4
LIV-8
G.B.-34
SP-9
ST-36
ST-37
8 cun
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 cun
1 2 3 4 5 6 7

Location

Inferior to the anterior superior iliac spine and lateral to the sartorius muscle, at the level of the lower border of the pubic symphysis.

How to find

The sartorius muscle originates at the anterior superior iliac spine (ASIS) and crosses the thigh towards the medial aspect of the knee. With the knee and hip slightly flexed and with active lateral rotation, it can be isolated easily. **ST-31** is located on the lateral border of the muscle, at the crossing point of a vertical line connecting the ASIS and the lateral upper border of the patella and a horizontal line at the level of the lower border of the pubic symphysis.

Needling

Vertically 0.5–2 cun

Actions/Indications

- Opens the channel, warms and expels pathogenic factors

Special features

Particularly useful for Cold *bi*-syndrome, disorders of the knees and lower back. The chain-and-lock method in combination (→ 8) with → **ST-36** and → **ST-41** is often used for paraesthesia and pain in the hip and leg radiating along the channel.

ST-32 *Crouching Rabbit* FUTU

Location

On the thigh, on a line connecting the lateral patellar border and the anterior superior iliac spine, 6 cun superior to the upper, lateral border of the patella.

How to find

Divide the distance between the tip of the greater trochanter and the lateral upper border of the patella into three sections. **ST-32** is located at the junction of the lower and the middle third of the thigh in a depression on the quadriceps muscle.

Needling

Vertically 0.5–2 cun

Actions/Indications

- Opens the channel and expels Wind, Dampness and Cold


Anterior superior iliac spine
ST-31
Upper border of the pubic symphysis
Sartorius
ST-32
3 cun
6 cun
ST-33
3 cun
Upper patellar border
Lateral patellar border


Ren-3
ST-30
Ren-2
SP-12
KID-11
ST-31
Highest prominence of the greater trochanter
Upper border of the pubic symphysis
LIV-11
LIV-10
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
cun
19 cun
SP-11
ST-32
ST-33
ST-34
Ex-LE-3
LIV-9
SP-10
Ex-LE-2
Upper border of the patella
Ex-LE-1
Popliteal crease
ST-35
Ex-LE-4
LIV-8
G.B.-34
SP-9
ST-36
ST-37
1
2
3
4
5
6
7
8 cun

Yin Market YINSHI ST-33


Anterior superior iliac spine
Upper border of the pubic symphysis
Sartorius
ST-32
3 cun
ST-33
6 cun
3 cun
Upper patellar border
Lateral patellar border


Vastus lateralis
Vastus medialis
Patella
Medial condyle of the femur
'Eye of the knee'
Head of the fibula
'Eye of the knee'
Patellar ligament

Location

On a line joining the lateral patellar border and the anterior superior iliac spine, 3 cun superior to the upper lateral border of the patella.

How to find

Measure 3 cun up from the upper lateral border of the patella, on the connecting line to the anterior superior iliac spine. **ST-33** is located in a groove at the junction of the rectus femoris and vastus lateralis muscles.

Needling

Vertically 0.5–1.5 cun

Actions/Indications

- Opens the channel and expels pathogenic factors

ST-34 *Ridge Mound* LIANGQIU

Location

On a line joining the lateral patellar border and the anterior superior iliac spine, 2 cun proximal to the upper lateral border of the patella, in a groove of the vastus lateralis muscle.

How to find

Locate the lateral upper border of the patella and from there measure 2 cun proximally. **ST-34** is located in a palpable groove on the vastus lateralis muscle of the quadriceps femoris group. This point projects on the line joining the lateral upper border of the patella and the anterior superior iliac spine (ASIS → 3.5).
Located on the same level are the points → **Ex-LE-1** (each 1.5 cun lateral and medial to **ST-34**). → **SP-10** is located in a comparable position on the medial aspect of the thigh (2 cun proximal to the medial upper border of the patella and in a groove on the vastus medialis muscle).

Needling

Vertically or obliquely 1–1.5 cun

Actions/Indications

- Regulates the Stomach Qi, alleviates acute conditions
- Opens the channel and alleviates pain

Special features

Xi-cleft point. Important local point for disorders of the knee. Modern application for acute epigastric pain – strongly reducing needling techniques have an immediate and calming effect on gastrointestinal peristalsis.


ST-34
Quadriceps femoris
2 cun
Upper border of the patella




ST-34
Upper border of the patella


2 cun
2 cun
SP-10


19 cun
SP-11
ST-32
ST-33
ST-34
Ex-LE-3
LIV-9
SP-10
Ex-LE-2
Ex-LE-1
Popliteal crease
ST-35
Ex-LE-4
LIV-8
G.B.-34
SP-9
ST-36
9
10
11
12
13
14
15
16
17
18
19
20 cun
1
2
3
4
Upper border of the patella
8 cun

Calf's Nose DUBI ST-35


Level of the lower patellar border
Ex-LE-4
Patellar ligament

Location

With the knee flexed, in the depression inferior to the patella and lateral to the patellar ligament.

How to find

This point is best located and needled with the knee slightly flexed (use knee support). **ST-35** is located in a depression on the lower lateral border of the patella, in a groove lateral to the patellar ligament. It projects onto the level of the knee joint space and more or less corresponds with the arthroscopic access to the joint. **ST-35** is also known as 'lateral eye of the knee' and is part of the extra point → **Ex-LE-5** (*xiyan*).

Needling

0.5–1 cun slightly obliquely in a medial direction, towards the medial eye of the knee → **Ex-LE-4** (*neixiyan*). Caution: Knee joint (the location of this point corresponds approximately with the arthroscopic access to this joint!).

Actions/Indications

- Expels Wind and Dampness, reduces swellings, opens the channel, alleviates pain

Special features

Important local point for all disorders of the knee


Lateral eye of the knee
Patellar ligament


Corresponds to ST-35
Level of the lower patellar border
Ex-LE-5 (*xiyan*)


ST-35
Ex-LE-4
Level of the lower patellar border


Patella
Medial condyle of the femur
'Eye of the knee'
Head of the fibula
'Eye of the knee'
Patellar ligament

ST-36 *Leg Three Miles* ZUSANLI

Location

3 cun distal to → **ST-35** ('lateral eye of the knee') and 1 fingerbreadth lateral to the anterior crest of the tibia, on the tibialis anterior muscle.

How to find

First, locate → **ST-35** ('lateral eye of the knee', at the level of the knee joint space). From → **ST-35**, palpate 3 cun (1 handbreadth) down and 1 fingerbreadth towards lateral by placing the middle finger adjacent to the tibial crest. There, **ST-36** is located in a depression, which can be palpated 'dynamically' (choose the point according to pressure sensitivity). **Or:** Palpate the lower border of the tibial tuberosity and 'dynamically' locate **ST-36** 1 fingerbreadth lateral to it.

Needling

Vertically 1–1.5 cun. Moxibustion is often used on this point.

Actions/Indications

- Regulates the Stomach, strengthens the Spleen, transforms Dampness
- Tonifies Qi and Yang, nourishes the Blood and Yin
- Calms the *shen*
- Opens the channel

Special features

He-sea point, Earth point, *ben* point (Five Phases point), lower *he*-sea point of the Stomach, *Gao Wu* command point for disorders of the abdomen, Ma Dan Yang point, Sea of Water and Grain point. Main point to tonify Qi and Blood for general weakness. Very important point.


ST-35
3 cun
ST-36
1 finger-width
Crest of the tibia
13 cun
Highest prominence of the lateral malleolus


ST-33
ST-34
Ex-LE-3
LIV-9
SP-10
Ex-LE-2
Ex-LE-1
Popliteal crease
ST-35
Ex-LE-4
LIV-8
G.B.-34
SP-9
ST-36
ST-37
ST-38
ST-40
ST-39
14
15
16
17
18
19
20
cun
Upper border of the patella
1
2
3
4
5
6
7
8
9
10
11
8 Cun
Midpoint


ST-35
Level of the lower patellar border


ST-35
Level of the lower patellar border
ST-36

Upper Great Emptiness SHANGJUXU ST-37


ST-35
3 cun
ST-36
3 cun
ST-37
1 finger-width
Crest of the tibia
10 cun
Highest prominence
of the lateral malleolus

Location

6 cun distal to → **ST-35** (at the knee joint space) or 3 cun distal to → **ST-36** and 1 fingerbreadth lateral to the anterior crest of the tibia.

How to find

First, find → **ST-35** ('lateral eye of the knee', level with the knee joint space). From → **ST-35**, measure 6 cun (2 handbreadths) in a distal direction and, at that level, 1 fingerbreadth towards lateral (place the middle finger onto the anterior crest of the tibia). There, **ST-37** is located in a depression, which can be 'dynamically' palpated (choose the point according to pressure sensitivity). **Or:** Find the midpoint of the line joining → **ST-35** and → **ST-41** (in the depression between the tendons of the extensor digitorum longus and the hallucis longus, level with the highest prominence of the lateral malleolus) by using the spreading hands technique (→ 2.3.3). **ST-37** is located 2 cun proximal and 1 fingerbreadth lateral to this point.

Needling

Vertically or obliquely 1–1.5 cun

Actions/Indications

- Regulates the Spleen, Stomach and Intestines, eliminates stagnation, clears Damp-Heat
- Opens the channel, alleviates pain

Special features

Lower *he*-sea point of the Large Intestine, Sea of Blood point.


ST-35
Upper
border of
the patella
ST-37


Level of the highest
prominence of the
lateral malleolus
ST-41
Talocrural joint
(ankle joint)
Tendon of the
extensor hallucis
longus

ST-38 *Lines Opening* TIAOKOU

Location

At the midpoint of the line joining → **ST-35** and → **ST-41** and 1 fingerbreadth lateral to the anterior crest of the tibia.

How to find

Quick method: Spreading-hands technique (→ 2.3.3): place the small fingers on → **ST-35** ('lateral eye of the knee', level with the knee joint space) and → **ST-41** (in the depression between the tendons of the extensor digitorum longus and the hallucis longus, level with the highest prominence of the lateral malleolus) and determine the midpoint of this line, using the thumbs. **ST-38** is located in a depression 1 fingerbreadth (middle fingerbreadth, measured from the anterior crest of the tibia) lateral to the midpoint. **ST-38** may be palpated 'dynamically' (according to pressure sensitivity). **Or:** From → **ST-35**, measure 8 cun (→ 2 handbreadths and 3 fingerbreadths) distally and 1 fingerbreadth laterally.

Located on the same level are → **ST-40** (1 fingerbreadth more laterally) and → **BL-57** (dorsal aspect of the lower leg, on the midpoint of the line joining → **BL-40** and → **BL-60**).

Needling

Vertically or obliquely 1–1.5 cun

Actions/Indications

- Expels Wind-Damp, opens the channel, alleviates pain, benefits the shoulder

Special features

Very effective distal point for disorders of the shoulder. For limited range of motion of the shoulder joint: apply strong reducing needling techniques while the patient moves their shoulder joint.


ST-35
8 cun
ST-38 on the tibialis anterior muscle
Crest of the tibia
1 finger-width
8 cun
Highest prominence of the lateral malleolus


ST-33
ST-34
Ex-LE-3
LIV-9
SP-10
Ex-LE-2
Ex-LE-1
Popliteal crease
ST-35
Ex-LE-4
LIV-8
G.B.-34
SP-9
ST-36
ST-37
ST-38
ST-40
ST-39
14
15
16
17
18
19
20
cun
Upper border of the patella
1
2
3
4
5
6
7
8
9
10
8 cun
Midpoint


ST-38
ST-40
Crest of the tibia





Lower Great Void XIAJUXU **ST-39**


ST-35
8 cun
ST-38
ST-39
1 cun
Crest of the tibia
1 finger-width
7 cun
Highest prominence of the lateral malleolus

Location

1 cun distal to → **ST-38** (midpoint of the line joining → **ST-35** and → **ST-41**) and 1 fingerbreadth lateral to the anterior crest of the tibia.

How to find

Quick method: Spreading-hands technique (→ 2.3.3): Place the little fingers on → **ST-35** (‘lateral eye of the knee’, level with the knee joint space) and → **ST-41** (in the depression between the tendons of the extensor digitorum longus and the hallucis longus, level with the highest prominence of the lateral malleolus) and determine the midpoint of this line (level with → **ST-38**), using the thumbs. **ST-39** is located in a depression 1 cun distal and 1 fingerbreadth (middle fingerbreadth, measured from the anterior crest of the tibia) lateral to this point. **ST-39** may be palpated ‘dynamically’ (according to pressure sensitivity).

Located on the same level (7 cun proximal to the lateral malleolus) are → **G.B.-35** (on the posterior border of the fibula), → **G.B.-36** (on the anterior border of the fibula) and → **BL-58** (on the lateral border of the gastrocnemius muscle).

Needling

Vertically or obliquely 1–1.5 cun

Actions/Indications

- Moves the Small Intestine Qi, eliminates stagnation, clears Damp-Heat
- Opens the channel, alleviates pain

Special features

Lower *he*-sea point of the Small Intestine, Sea of Blood point.


ST-35
Crest of the tibia
Level of ST-41








BL-57
1 cun
BL-58

ST-40 *Abundant Bulge* FENGLONG

Location

At the midpoint of the line joining → **ST-35** and → **ST-41** and 2 fingerbreadths lateral to the anterior crest of the tibia or 1 fingerbreadth lateral to → **ST-38**, between the extensor digitorum longus and peroneus brevis muscles.

How to find

Quick method: Spreading-hands technique (→ 2.3.3): Place the little fingers on → **ST-35** ('lateral eye of the knee', level with the knee joint space) and → **ST-41** (in the depression between the tendons of the extensor digitorum longus and the hallucis longus, level with the highest prominence of the lateral malleolus) and determine the midpoint of this line, using the thumb. **ST-40** is located in a depression 2 fingerbreadths (2 middle fingerbreadths, measured from the anterior crest of the tibia) lateral to this point. **ST-40** may be palpated 'dynamically' (according to pressure sensitivity). Located on the same level (8 cun proximal to the highest prominence of the lateral malleolus) are → **ST-38** (1 fingerbreadth lateral to the tibia) and → **BL-57** (on the dorsal aspect of the lower leg, halfway between → **BL-40** and → **BL-60**).


ST-35
8 cun
ST-38
ST-40
Crest of the tibia
1 finger-width
8 cun
Highest prominence of the lateral malleolus

Needling

Vertically or obliquely 1–1.5 cun

Actions/Indications

- Transforms Dampness and Phlegm, clears Phlegm in the Lung and Heart, calms the *shen*

Special features

Luo-connecting point. Main acupuncture point for eliminating Phlegm.


ST-33
ST-34
Ex-LE-3
LIV-9
SP-10
Ex-LE-2
Ex-LE-1
Popliteal crease
ST-35
Ex-LE-4
LIV-8
G.B.-34
SP-9
ST-36
ST-37
ST-38
ST-40
ST-39
14
15
16
17
18
19
20
cun
Upper border of the patella
1
2
3
4
5
6
7
8
9
10
8 cun
Midpoint


ST-35
Crest of the tibia
Level of ST-41


ST-38 on the tibialis anterior muscle
Crest of the tibia
1 fingerbreadth



Stream Divide **JIEXI** **ST-41**


Level of the highest prominence of the lateral malleolus
ST-41
Talocrural joint (ankle joint)
Tendon of the extensor hallucis longus

Location

On the ankle, on the level of the highest prominence of the lateral malleolus, in the depression between the tendons of the extensor digitorum and the extensor hallucis longus.

How to find

With the patient extending their big toe against resistance, the tendon of the extensor hallucis longus muscle will become more distinct. **ST-41** is located lateral to this tendon, in an obvious depression on the level of the highest prominence of the lateral malleolus (→ 3.6.2) and ankle joint space.

Located on the same level is → **LIV-4** (medial to the tendon, halfway between → **SP-5** and **ST-41**).

Needling

0.5–1 cun vertically or obliquely deep to the tendons in a medial direction towards → **SP-5** or in a lateral direction towards → **G.B.-40**. Caution: Tibial artery/vein/nerve lie deep to this point.

Actions/Indications

- Clears Heat from the Stomach and Stomach channel
- Calms the *shen*
- Opens the channel and *luo* vessels, alleviates pain

Special features

Jing-river point, Fire point, tonification point. Important local point for disorders of the ankle joint. Important distal point for frontal headaches caused by Stomach Heat or Stomach Fire.


BL-63
G.B.-40
ST-41
LIV-4
SP-5
BL-64
ST-42
G.B.-41
SP-4
BL-65
G.B.-42
LIV-3
G.B.-43
ST-43
BL-66
SP-3
BL-67
ST-44
SP-2
G.B.-44
Ex-LE-10 (*bafeng*)
LIV-1
SP-1
ST-45


Trochlea tali
Medial malleolus
Lateral malleolus
Talocrural joint
Subtalar joint


Ankle joint space
Tendon of the tibialis anterior
ST-41
LIV-4

ST-42 *Rushing Yang* CHONGYANG

Location

On the highest point of the dorsum of the foot, between the tendons of the extensor hallucis longus and the extensor digitorum longus, directly lateral to the point where the dorsalis pedis artery may be palpated. The point is bordered proximally by the 2nd and 3rd metatarsal bones and distally by the 2nd and 3rd cuneiform bones. **Alternative location:** Sometimes, this point may be located lateral to the medial portion of the extensor digitorum longus tendon (joining the 2nd toe).


Talocrural joint
(ankle joint)
ST-41
ST-42
Dorsalis pedis
artery

How to find

With the palpating finger, glide from → **ST-43** (in the depression between the base of the 2nd and 3rd metatarsal bones) proximally towards → **ST-41** (in the depression between the tendons of extensor digitorum longus and hallucis longus). Locate **ST-42** at the highest point of the dorsum of the foot, in a depression lateral to the pulse. In most cases, **ST-42** is located lateral to the tendon of the extensor hallucis longus, which becomes more distinct by extending the big toe.


Level of the highest
prominence of the
lateral malleolus
ST-41
Talocrural joint
(ankle joint)
Tendon of the
extensor hallucis
longus

Needling

Vertically 0.2–0.5 cun. Caution: Dorsalis pedis artery.

Actions/Indications

- Clears Heat from the Stomach channel, regulates the Stomach
- Calms the *shen*
- Opens the channel and *luo* vessels

Special features

Yuan-source point, exit point.

Sunken Valley XIANGU ST-43


Metatarsal III
Metatarsal II
ST-43

Location

On the dorsum of the foot, in the depression between the 2nd and 3rd metatarsal bones, at the level of the junction of the shafts and the heads of these metatarsal bones.

How to find

Palpate from distal (toes) towards proximal (ankle) between the 2nd and 3rd metatarsal bones, until the finger glides into a depression distal to the metatarsophalangeal joint, where **ST-43** is located. It is approximately on the same level as the junction of the shafts and the heads of the two metatarsal bones.

Needling

Vertically or obliquely 0.5–1 cun

Actions/Indications

- Regulates the Spleen, Stomach and Intestines, reduces oedema

Special features

Shu-stream point, Wood point, generally used for 'inflammatory' joint disorders (*bi*-syndromes).


BL-63
G.B.-40
ST-41
SP-5
LIV-4
BL-64
ST-42
G.B.-41
SP-4
BL-65
LIV-3
G.B.-42
G.B.-43
ST-43
SP-3
BL-66
BL-67
ST-44
SP-2
G.B.-44
Ex-LE-10
(*bafeng*)
LIV-1
SP-1
ST-45

ST-44 *Inner Court* NEITING

Location

Between the 2nd and the 3rd toes, proximal to the interdigital fold.

How to find

Locate **ST-44** just proximal to the interdigital fold between the 2nd and the 3rd toes.

Needling

0.5–1 cun vertically or obliquely in a proximal direction

Actions/Indications

- Opens the channel, expels Wind and clears Heat, alleviates pain
- Regulates the Intestines, clears Damp-Heat
- Calms the *shen*

Special features

Ying-spring point, Water point, Ma Dan Yang Heavenly Star point. Major point for clearing Heat from the head and face.




BL-63
G.B.-40
ST-41
LIV-4
SP-5
BL-64
ST-42
G.B.-41
SP-4
BL-65
G.B.-42
LIV-3
G.B.-43
ST-43
BL-66
SP-3
ST-44
SP-2
BL-67
G.B.-44
Ex-LE-10
(*bafeng*)
LIV-1
SP-1
ST-45

Strict Exchange LIDUI **ST-45**



Location

On the 2nd toe, 0.1 cun from the lateral corner of the nail.

How to find

ST-45 is located at the junction of two tangents drawn along the lateral and proximal border of the nail of the 2nd toe, approximately 0.1 cun from the margin of the nail.

Needling

0.1 cun vertically or obliquely in a proximal direction or prick to bleed.

Actions/Indications

- Opens the channel and clears Heat from the *yangming* channels (L.I./ST)
- Calms and regulates the *shen*

Special features

Jing-well point, Metal point, sedation point, important distal point for all Heat disorders affecting the head. For severe insomnia due to Fire or Phlegm-Heat, apply moxibustion ('small Fire attracting big Fire' technique).

4.4 The Spleen Channel System – Foot *taiyin* (*zu tai yin jing luo*)

4.4.1 The Spleen Primary Channel (*zu tai yin jing*)


Highest prominence of the medial malleolus
Base of the 1st metatarsal bone
Head of the 1st metatarsal bone
SP-5
SP-1
SP-2
SP-3
SP-4


LU-1
20
SP-21
LIV-14
G.B.-24
17
Ren-10
15
Ren-4
Ren-3
13
12
11
10
9
8
7
6
5
SP-1


SP-11
6
SP-10
2
cun
SP-9
3
SP-8
4
SP-7
3
SP-6
3
Highest point of the medial malleolus
SP-5
cun


SP-20
SP-19
SP-18
8 cun
SP-17
Mamillary line
8
SP-16
3
4 cun
SP-15
Ren-8
1,3
SP-14
5
SP-13
0,7
SP-12
cun

Pathway

The **external pathway** of the Spleen primary channel begins at **SP-1** (*yinbai*) on the big toe at the medial corner of the nail. This point is reached by a branch that separates from the Stomach primary channel at → **ST-42** (*chongyang*) (foot Yin–Yang connection of the first great circuit).

➡ From **SP-1** the channel courses along the medial aspect of the foot



Mid-axillary line

- ➡ ascends anterior to the medial malleolus and continues along the posterior border of the medial crest of the tibia
- ➡ passes the anteromedial region of the knee and thigh
- ➡ ascends the abdomen lateral to the midline to the second intercostal space, passing on its way ➞ **Ren-3** (*zhongji*), ➞ **Ren-4** (*guanyuan*), ➞ **Ren-10** (*xiawan*), ➞ **G.B.-24** (*riyue*) and ➞ **LIV-14** (*qimen*)
- ➡ curves downward again and terminates 6 cun inferior to the axilla on the midaxillary line at **SP-21** (*dabao*).

According to Solinas et al (1998), its **inner pathway** branches off at ➞ **Ren-10** (*xiawan*) and enters the Spleen (*pi*), its pertaining *zang*-Organ, and connects with the Stomach (*wei*), its paired *fu*-Organ. From the Stomach (*wei*), an **Interior branch** passes the diaphragm, ascends part of the oesophagus and enters the Heart (*xin*), where it connects with the Heart primary channel (*shou shao yin jing*) (deep Yin–Yin connection ➞ 1.2). From **SP-20** (*zhourong*), a **further branch** ascends to ➞ **LU-1** *(zhongfu)* at the level of the first intercostal space to form the hand–foot pairing (Yin axes of the first great circuit, *taiyin*). The branch ascends further to the tongue, reaches the root of the tongue and disperses on its lower surface.

Clinical importance (→ 1.2)

Exterior (*biao*) signs and symptoms: Heavy sensations of the head and body, sensation of weakness in the legs, general fever, pain in the lower cheek, muscular atrophy and weakness of the legs and medial hip region, cold knees, feet and legs, oedema

Interior (*li*) or *zangfu*-Organ signs and symptoms: Abdominal pain, diarrhoea or loose stools with undigested food, borborygmus, belching and dizziness, abdominal masses, loss of appetite, a sallow complexion, retention of urine

Excess (*shi*) ➞ Spasms, foot pain

Deficiency (*xu*) ➞ Abdominal fullness, borborygmus, diarrhoea with undigested food

Connections and meeting points of the Spleen primary channel (→ 1.2)

Connections with other channels

Stomach primary channel (*zu yang ming jing*)

Connection: Foot Yin–Yang connection of the first great circuit
Location: ST-42 SP-1 (on the foot).
Circulation: Circadian (according to the Organ clock)
Importance: Interior–Exterior relationship

Lung primary channel (*shou tai yin jing*)

Connection: Paired according to the six channel theory (hand–foot pairing) ➞ *tai yin* (Yin axes of the first great circuit)
Location: SP-20 ➞ **LU-1** (on the thorax). A branch of the Spleen primary channel ascends from **SP-20** (*zhourong*) to **LU-1** (*zhongfu*)
Circulation: Non-circadian (**not** according to the Organ clock)
Importance: Above–below relationship

Heart primary channel (*shou shao yin jing*)

Connection: Deep Yin–*Yin* connection
Location: SP ➞ **HE** (on the thorax). An internal branch of the Spleen primary channel spreads inside the Heart (*xin*) and connects with the Heart primary channel.
Circulation: Circadian (according to the Organ clock)
Importance: The Heart primary channel receives Nutritive Qi (*ying qi*) from the Spleen primary channel (first circulation of the *ying qi* ➞ 1.1.4)

Connections with other *zangfu*-Organs

Spleen (*pi*), Stomach (*wei*), Heart (*xin*)

4.4.2 The Spleen Divergent Channel (*zu tai yin jing bie*)



Pathway

The Spleen divergent channel separates from the Spleen primary channel near **SP-11** (*jimen*) on the anteromedial aspect of the thigh, at the medial border of the sartorius muscle. It

➡ penetrates the abdomen in the inguinal region at → **ST-30** (*qichong*)

➡ connects with the Stomach (*wei*), Spleen (*pi*) and Heart (*xin*)

➡ ascends along the oesophagus to the suprasternal fossa and travels laterally to → **ST-12** (*quepen*) in the supraclavicular fossa

➡ crosses the Stomach primary channel and the Stomach divergent channel at → **ST-9** (*renying*) where they meet to connect at one of the six *he*-confluences (here: ST/SP as third confluence → 1.3).

Clinical importance

- Strengthens the relationship between the Spleen and the Stomach (*zangfu*-Organs). Points on the Spleen primary channel can therefore be used for disorders of the Stomach, and vice versa points on the Stomach primary channel can treat disorders of the Spleen. In clinical practice, Spleen points are used for the whole gastrointestinal tract.
- Meets the Stomach primary channel at → **ST-30**; this is also a Sea of Water and Grain point, which can be used for many digestive disorders.
- Links the Spleen primary channel with the Heart; in combination with other points, SP points can be used for Qi and Blood deficiency as well as for psycho-emotional disorders.
- Connects the Spleen primary channel and the neck region and can therefore be used for chronic disorders of the neck and thyroid caused by retention of Phlegm (for example **SP-3** with **ST-40**, **P-5**).
- Connects the Spleen primary channel with the mouth and tongue and can therefore be used for disorders/ulcers of the tongue and mouth caused by retention of Phlegm (for example **SP-2, SP-3, SP-6**).

4.4.3 The Spleen Sinew Channel (*zu tai yin jing jin*)



Pathway

The Spleen sinew channel begins on the medial aspect of the big toe at **SP-1** (*yinbai*)

- ➡ runs along the medial border of the foot
- ➡ binds (*jie*) anterior to the medial malleolus at **SP-5** (*shangqiu*)
- ➡ ascends along the medial aspect of the tibia to **SP-9** (*yinlingquan*) and binds (*jie*) anterior to the medial head of the tibia
- ➡ runs along the medial aspect of the thigh and binds (*jie*) on the medial aspect of the inguinal region
- ➡ continues to → **Ren-3** (*zhongji*) where it meets the other sinew channels of the foot Yin channels

At → **Ren-3** the sinew channel separates into three branches:

- **One branch** runs to the genital region
- **A further branch** ascends along the anterior midline, covering the *ren mai* and binding (*jie*) at the umbilical region. It penetrates the abdomen and spreads in the costal and thoracic region.
- **A third branch** penetrates deeper into the body and ends at the spinal region at → **BL-20** (*pishu*).

Clinical importance

- **Pathology:** Distending pain of the big toe, pain at the medial malleolus, cramps and pain in the calves, pain of the medial aspect of the knees and thighs, pain in the inguinal and genital region (radiating to the umbilicus, thorax and back).
- **Indication:** Mainly for *bi*-syndromes (Painful Obstruction Syndrome) and *wei*-syndrome (atrophy syndrome) along the Spleen channel, especially along the medial aspect of the leg. The area covered by the Spleen sinew channel is larger than that covered by the Spleen primary channel. This explains why Spleen primary channel points can also be used for disorders and diseases of the external genitalia and the umbilical region.

4.4.4 The Spleen *luo*-Connecting Vessel System (*zu tai yin luo mai*)



Pathway

The Spleen *luo*-connecting channel separates from the Spleen primary channel at its *luo*-connecting point **SP-4** (*gongsun*) (→ 8.1.2). It forms a three-dimensional reticulate network, dividing into multiple branches and sub-branches (*sun luo, fu luo, xue luo* → 1.5) within the surrounding tissue.

- ➡ Horizontal divisions run to the Interiorly–Exteriorly paired Stomach primary channel, according to some schools of thought

Ch04.4-F10028.qxd 2/23/08 7:08 PM Page 179

(for example Ngyen Van Nghi ➞ Appendix) they travel as a **transverse** Spleen *luo*-connecting vessel to the *yuan*-source point ➞ **ST-42** (*chongyang*).

- A **longitudinal** division follows the pathway of the Spleen primary channel, enters the abdomen in the inguinal region and connects with the Large Intestine (*dachang*) and the Stomach (*wei*).

Clinical importance (➞ 8.1.2)

Pathology

- **Excess (*shi*)**: Colicky pain in the Stomach and Large Intestine
- **Deficiency (*xu*)** ➞ *Gu zhang* (drum-like abdominal distension) such as digestive disorders in children, abdominal fullness and distension, ascites
- **Counterflow Qi:** Acute vomiting, diarrhoea, severe abdominal pain

The great *luo*-connecting vessel of the Spleen (*zu tai yin luo mai*)

Pathway

The great *luo*-connecting vessel of the Spleen begins on the lateral aspect of the thorax at ➞ **SP-21** (*dabao*). It contains the Blood of the *luo*-connecting vessel and disperses to the vessels of the whole body, covering them in a net-like fashion (➞ 1.5, ➞ 8.1.2).

Clinical importance (➞ 8.1.2)

- **Excess (*shi*)**: Pain in the whole body, polyarthritis, *bi*-Syndrome (Painful Obstruction Syndrome)
- **Deficiency (*xu*)**: Muscular atrophy and weakness, weakness of the joints, weakness in the whole body.

4.4.5 Cutaneous Region (*tai yin pi bu*)

See description and figures ➞ 1.6

4.4.6 Points of the Spleen Primary Channel (Overview)

Specific points according to their function

- ***Yuan*-source point (➞ 8.1.1): SP-3** (*taibai*) 🟦■
- ***Luo*-connecting point (➞ 8.1.2.): SP-4** (*gongsun*) 🟦■/ SP-21 (*dabao*) 🟦🟦
- ***Xi*-cleft point (➞ 8.1.3): SP-8** (*diji*) 🟦■
- **Associated Back-*shu* point (➞ 8.1.4): BL-20** (*pishu*) 🟦🟦
- **Associated Front-*mu* point (➞ 8.1.5): LIV-13** (*zhangmen*) 🟦🟦
- **Five *shu*-transporting points (➞ 8.1.6):**
  jing-well point (Wood): **SP-1** (*yinbai*) 🟦■
  ying-spring point (Fire), tonification point: **SP-2** (*dadu*)
  shu-stream point (Earth), *ben* point: **SP-3** (*taibai*) 🟦■
  jing-river point (Metal), sedation point: **SP-5** (*shangqiu*) 🟦■
  he-sea point (Water): **SP-9** (*yinlingquan*) 🟦🟦
- ***Hui*-meeting point (➞ 8.1.7): –**
- **Opening point (➞ 8.1.8) of the *chong mai*: SP-4** (*gongsun*) 🟦■
- **Lower *he*-sea points (➞ 8.1.9): –**
- ***Jiaohui*-meeting points (➞ 8.1.10):**
  - with the Kidney and Liver primary channels (meeting point of the three foot *Yin* channels and the *yin qiao mai**: **SP-6** (*sanyinjiao*) 🟦🟦
  - with the LIV and T.B.* channels and the *yin wei mai:* **SP-12** (*chongmen*)
  - with the LIV channel and the *yin wei mai*: **SP-13** (*fushe*)
  - with the *yin wei mai*: **SP-15** (*daheng*), **SP-16** (*fuai*)
  - of other channels with the SP channel: **LU-1**, **G.B.-24**, **LIV-14**, **Ren-3**, **Ren-4**, **Ren-10**, **Ren-17***
- **Gao Wu command point (➞ 8.1.11):** –
- **Window of Heaven point (➞ 8.1.12):** –
- **Points of the Four Seas (➞ 8.1.13):** –
- **Ma Dan Yang Heavenly Star point(➞ 8.1.14):** –
- **Sun Si Miao Ghost point (➞ 8.1.15): SP-1** (*yinbai*) 🟦■
- **Other functional points:**
  – important point for diarrhoea: **SP-4** (*gongsun*) 🟦■
  – important point for Damp *bi*-syndrome: **SP-5** (*shangqiu*) 🟦■
  – important point for eliminating Dampness: **SP-9** (*yinlingquan*) 🟦🟦
  – important point for regulating the Blood: **SP-10** (*xuehai*) 🟦■
  – important point for general pain: **SP-21** (*dabao*) 🟦🟦

Points according to region

- **Local points (➞ 8.2.1):** knee region – **SP-9** (*yinlingquan*) 🟦🟦; Large Intestine – **SP-15** (daheng) 🟦■; knee – **SP-9** (*yinlingquan*) 🟦🟦; foot – **SP-5** (*shangqiu*) 🟦■; toes – **SP-3** (*taibai*) 🟦■
- **Adjacent points (➞ 8.2.1):** Spleen/Stomach – **SP-15** (*daheng*) 🟦■; hypochondrium – **SP-21** (*dabao*) 🟦🟦; knee – **SP-10** (*xuehai*) 🟦■; toes – **SP-4** (*gongsun*) 🟦■, **SP-5** (*shangqiu*) 🟦■, **SP-9** (*yinlingquan*) 🟦🟦
- **Distal points (➞ 8.2.1):** for the Spleen/Stomach, upper abdominal region – **SP-4** (*gongsun*) 🟦■; for the female genital organs, urogenital region – **SP-6** (*sanyinjiao*) 🟦🟦; lower abdomen – **SP-1** (*yinbai*) 🟦■; for the hand and knee – **SP-5** (*shangqiu*) 🟦■

Specific points according to the channel pathway (in numerical order):

- **SP-1** (*yinbai*) 🟦■: Sun Si Miao Ghost point (➞ 8.1.15); distal point for the lower abdomen (➞ 8.2.1); *jing*-well point (Wood) (➞ 8.1.6)
- **SP-2** (*dadu*): *ying*-spring point (Fire) (➞ 8.1.6), tonification point
- **SP-3** (*taibai*) 🟦■: *yuan*-source point (➞ 8.1.1), *shu*-stream point (➞ 8.1.6), *ben* point (Five Phase point) (➞ 8.1.6)

---

* Mentioned by only some authors.

- **SP-4** (*gongsun*) 🟦⬛: *luo*-connecting point of the Spleen (→ 8.1.2); opening point of the *chong mai* (→ 8.1.8); distal point for the Spleen/Stomach, upper abdomen (→ 8.2.1); important point for diarrhoea; adjacent point for the toes (→ 8.2.1)
- **SP-5** (*shangqiu*) 🟦⬛: *jing*-river point (Metal) (→ 8.1.6); Sedation point; important point for Damp *bi*-syndrome; local point for the foot (→ 8.2.1); distal point for the hand and knee (→ 8.2.1)
- **SP-6** (*sanyinjiao*) 🟦🟦: *jiaohui*-meeting point with the KID and LIV channels and the *yin qiao mai* (→ 8.1.10) (meeting point of the three foot Yin channels); distal point for the female genital system, the urogenital region (→ 8.2.1)
- **SP-8** (*diji*) 🟦⬛: *xi*-cleft point (→ 8.1.3)
- **SP-9** (*yinlingquan*) 🟦🟦: *he*-sea point (Water) (→ 8.1.6); important point for eliminating Dampness; local point for the knee region (→ 8.2.1); local point for the knees (→ 8.2.1)
- **SP-10** (*xuehai*) 🟦⬛: important point for regulating the Blood; adjacent point for the knees (→ 8.2.1)
- **SP-12** (*chongmen*): *jiaohui*-meeting point with the LIV and T.B.* channels and the *yin wei mai* (→ 8.1.10)
- **SP-13** (*fushe*): *jiaohui*-meeting point with the LIV channel and the *yin wei mai* (→ 8.1.10)
- **SP-15** (*daheng*) 🟦⬛: local point for the Large Intestine (→ 8.2.1); adjacent point for the Spleen/Stomach (→ 8.2.1); *jiaohui*-meeting point with the *yin wei mai* (→ 8.1.10)
- **SP-16** (*fuai*): *jiaohui*-meeting point with the *yin wei mai* (→ 8.1.10)
- **SP-21** (*dabao*) 🟦🟦: adjacent point for the hypochondrium (→ 8.2.1); Main-*luo*-connecting point of the Spleen (→ 8.1.2); important point for generalised pain

General location help

- **SP-13 – SP-16**: these points are all located 4 cun lateral to the anterior midline (= mamillary line) → **SP-13**: 0.7 cun superior to **SP-12; SP-14**: 1.3 cun inferior to the umbilicus; **SP-15**: at the level of the umbilicus; **SP-16**: 3 cun superior to the umbilicus.
- **SP-17 – SP-20**: these points are all located 6 cun lateral to the anterior midline in the fifth to second intercostal spaces.

---

*Mentioned by only some authors.

Hidden White YINBAI SP-1



Location

On the big toe, 0.1 cun from the medial corner of the nail.

How to find

SP-1 is located at the junction of two tangents drawn along the medial and proximal border of the nail of the big toe, approximately 0.1 cun from the margin of the nail.

Needling

0.1–0.2 cun vertically or obliquely in a proximal direction or prick to bleed with a needle, lancet or three-edged needle.

Actions/Indications

- Regulates the Blood
- Regulates the Spleen
- Unbinds the chest
- Calms the *shen*
- Revives consciousness

Special features

Jing-well point, Wood point, Sun Si Miao Ghost point, entry point, important distal point for the lower abdomen.


SP-6
KID-7
KID-8
LIV-4
KID-3
KID-4
SP-5
KID-6
KID-5
SP-1
SP-4
KID-2
SP-2
SP-3


G.B.-40
BL-63
ST-41
SP-5
LIV-4
BL-64
ST-42
G.B.-41
SP-4
BL-65
G.B.-42
LIV-3
G.B.-43
ST-43
BL-66
SP-3
BL-67
ST-44
SP-2
G.B.-44
Ex-LE-10
(*bafeng*)
LIV-1
SP-1
ST-45

SP-2 Great Metropolis DADU



Location

On the medial aspect of the big toe, at the junction of the shaft and the base of the proximal phalanx, distal to the 1st metatarsophalangeal joint.

How to find

On the medial aspect of the big toe, palpate from distal to proximal towards the metatarsophalangeal joint, until you can feel the junction of the shaft with the base of the proximal phalanx. **SP-2** is located distally to the base of the bone, which forms a distinct step, and slightly inferiorly to its outer curvature, at the border of the red and white skin (sole/dorsum of the foot).
Located in comparable positions are → **BL-66** on the lateral border of the foot, → **L.I.-2** on radial aspect and → **S.I.-2** on the ulnar aspect of the hand.

Needling

0.2–0.5 cun vertically or obliquely, just below the lower border of the bone. Caution: Painful point.

Actions/Indications

- Regulates and supports the Spleen, harmonises the Lower Burner and clears Heat

Special features

Ying-spring point, Fire point, tonification point.


BL-63
G.B.-40
ST-41
SP-5
LIV-4
BL-64
ST-42
G.B.-41
SP-4
BL-65
G.B.-42
LIV-3
G.B.-43
ST-43
BL-66
SP-3
BL-67
ST-44
SP-2
G.B.-44
Ex-LE-10
(*bafeng*)
LIV-1
SP-1
ST-45


SP-6
KID-7
KID-8
LIV-4
KID-3
SP-5
KID-4
KID-6
KID-5
SP-1
KID-2
SP-4
SP-2
SP-3


Proximal phalanx II
Metacarpal II
L.I.-2

Supreme White TAIBAI SP-3


SP-3
Border 'red/white skin'
Head of metatarsal I


Border 'red/white skin'

Location

On the medial aspect of the foot, in the depression proximal to the head of the 1st metatarsal bone, at the border of the red and white skin.

How to find

When palpating along the border of the red and white skin on the medial aspect of the foot from distal (toes) to proximal (ankle), the metatarsophalangeal joint forms a prominent landmark. **SP-3** is located just proximal to this joint in a clearly palpable depression, which marks the junction of the head and the shaft of the 1st metatarsal bone.

Located in a comparable position is → **BL-65** (proximal to the head of the 5th metatarsal bone) on the lateral border of the foot. In comparable locations on the borders of the hand are → **L.I.-3** on the radial aspect and → **S.I.-3** on the ulnar aspect of the hand.

Needling

0.5–1 cun vertically or obliquely from medial towards lateral. Caution: Needling this point tends to be painful.

Actions/Indications

- Tonifies the Spleen, harmonises the Lower Burner
- Eliminates Dampness and Damp-Heat
- Regulates Qi locally

Special features

Yuan-source point, *shu*-stream point, Earth point, *ben* point (Five Phases). Important point for tonifying the Spleen.


BL-66
BL-65
BL-64


S.I.-2
S.I.-3
Junction
Most distal transverse crease


Metacarpal II
Proximal phalanx II
L.I.-3


Navicular
Medial cuneiform
Metatarsal bones
Proximal phalanges
Distal phalanges
Medial phalanges
Base of the 1st metatarsal bone
Navicular tuberosity
Calcaneus

SP-4 *Grandfather Grandson* GONGSUN

Location

In the depression distal to the base of the 1st metatarsal bone, on the border of the red and white skin.

How to find

When palpating along the border of the red and white skin (sole/dorsum of the foot) on the medial aspect of the midfoot from proximal towards medial, the base of the 1st metatarsal bone (→ 2.6.2) forms a distinct bony prominence. **SP-4** is located in the depression distal to this prominence, at the junction of the shaft and the base of the bone.

→ **SP-3** is located slightly more distally at the junction of the head and the shaft of the 1st metatarsal bone. → **BL-64** is located in a comparable position on the lateral aspect of the midsection of the foot (at the junction of the shaft and the base of the 5th metatarsal bone).

Needling

0.5–1 cun vertically or obliquely from medial towards lateral. Caution: Needling may be painful.

Actions/Indications

- Strengthens and regulates the Spleen Qi, eliminates Dampness
- Calms the *shen*
- Benefits the Heart and chest
- Regulates the *chong mai*
- Local point, for example for metatarsalgia

Special features

Luo-connecting point, opening (master) point of the *chong mai*. Important point for distension and pain in the upper and lower abdomen caused by Qi stagnation, Blood stasis or obstruction due to Dampness.


Tibialis anterior
Base of metatarsal I
SP-3
SP-4
Border 'red/white skin'


14
15 cun
Highest prominence of the medial malleolus
KID-3
SP-5
SP-1
SP-4
KID-2


Navicular
Medial cuneiform
Metatarsal bones
Proximal phalanges
Distal phalanges
Medial phalanges
Base of the 1st metatarsal bone
Navicular tuberosity
Calcaneus




BL-63
G.B.-40
ST-41
SP-5
LIV-4
BL-64
ST-42
G.B.-41
SP-4
BL-65
LIV-3
G.B.-42
G.B.-43
ST-43
BL-66
SP-3
BL-67
ST-44
SP-2
G.B.-44
Ex-LE-10 (*bafeng*)
LIV-1
SP-1
ST-45

Shang Mound SHANGQIU SP-5


Highest prominence
of the medial malleolus
SP-5
Navicular tubercle


LIV-4
KID-3
KID-4
SP-5
KID-6
KID-5
SP-1
SP-4
KID-2
SP-2
SP-3


Ankle joint space
Tendon of the
tibialis anterior
LIV-4
ST-41


Inferior border
of the lateral
malleolus
G.B.-40

Location

In the depression at the junction of a vertical line drawn along the anterior border and a horizontal line drawn along the lower border of the medial malleolus. **Or**: In the depression halfway between the highest prominence of the medial malleolus and the tubercle of the navicular bone.

How to find

SP-5 is located in a depression anterior and inferior to the medial malleolus, at the junction of a vertical line drawn along the anterior border and a horizontal line drawn along the inferior border of the medial malleolus. **SP-5** is located distal to the tendon of the tibialis anterior muscle.

Located in a comparable position on the lateral aspect of the foot is → **G.B.-40** (in a depression at the junction of a vertical line drawn along the anterior border and a horizontal line drawn along the inferior border of the lateral malleolus).

Needling

0.3–0.6 cun vertically, obliquely or transversely (subcutaneously) deep to the tendons towards → **ST-41**.

Actions/Indications

- Tonifies the Spleen, eliminates Dampness, benefits the tendons and bones
- Moves Qi locally
- Calms the *shen*

Special features

Jing-river point, Metal point, sedation point. Important point for treating Damp *bi*-syndrome.

SP-6 *Three Yin Intersection* SANYINJIAO

Location

3 cun proximal to the highest prominence of the medial malleolus, on the posterior border of the medial crest of the tibia.

How to find

From the highest prominence of the medial malleolus (→ 3.6.2), measure 3 cun (1 handbreadth) in a superior direction, where **SP-6** is located in a depression at the posterior border of the medial crest of the tibia. This point is often sensitive to pressure. Sometimes, this depression is located more anteriorly, and locating **SP-6** should be based on pressure-sensitivity.

Located in a comparable position is → **G.B.-39** (3 cun proximal to the prominence of the lateral malleolus, on the anterior border of the fibula, intersecting point of the three foot Yang channels).

Needling

Vertically or obliquely 1–2 cun. Caution: Contraindicated during pregnancy, particularly with reducing needle techniques; exception: to promote labour.

Actions/Indications

- Tonifies the Spleen and the Stomach, eliminates Dampness
- Nourishes the Blood and Yin, regulates menstruation, promotes labour
- Regulates urination, benefits the genitals, harmonises the Lower Burner
- Calms the *shen*

Special features

Meeting point with the Liver and Kidney channels (group *luo*-connecting point) and the *yin qiao mai*. Very important point for disorders of the Lower Burner (especially for gynaecological disorders, birth and urinary disorders), as well as for many digestive disorders and psychological disorders (caused by Blood and Yin deficiency).


Posterior border of the tibia
SP-6
3 cun
Highest prominence of the medial malleolus


SP-6
Highest prominence of the medial malleolus


SP-6
KID-7
KID-8
LIV-4
KID-3
KID-4
SP-5
KID-6
KID-5
SP-1
KID-2
SP-4
SP-3
SP-2


G.B.-39
3 cun
Highest prominence of the medial malleolus


SP-6
KID-8
KID-7
KID-3
SP-5
SP-1
SP-4
KID-2
11
12
13
14
15 cun
Highest prominence of the medial malleolus

Dripping Valley LOUGU SP-7


SP-7
3 cun
6 cun
SP-6
3 cun
Highest prominence of the medial malleolus




Medial condyle of the tibia
Gastrocnemius
SP-9
At the junction of the shaft and medial condyle of the tibia

Location

6 cun proximal to the highest prominence of the medial malleolus, on the posterior border of the medial crest of the tibia.

How to find

From the highest prominence of the medial malleolus, measure 6 cun in a superior direction, where **SP-7** is located at the posterior border of the medial crest of the tibia. **Or**: Spreading hands technique (→ 2.3.3): **SP-7** is located 0.5 cun distal to the midpoint of a line connecting → **SP-9** (distal to the tibial condyle) and the highest prominence of the medial malleolus.

→ **SP-6** is located midway between the tip of the malleolus and **SP-7** (3 cun superior/inferior respectively).

Needling

Vertically 1–1.5 cun

Actions/Indications

- Strengthens the Spleen, drains Dampness, opens the channel
- Promotes urination


KID-10
Popliteal crease
LIV-8
1
Junction tibial shaft/medial condyle of the tibia
SP-9
2
LIV-7
3
4
SP-8
5
6
7
LIV-6
8
9
SP-7
10
LIV-5
KID-9
11
SP-6
12
13
KID-7
KID-8
14
KID-3
15 cun
Highest prominence of the medial malleolus
SP-5
SP-1
SP-4
KID-2

SP-8 *Earth Pivot* DIJI

Location

3 cun distal to the junction of the shaft and the medial condyle of the tibia (➞ **SP-9**), at the posterior border of the medial crest of the tibia.

How to find

Measure 1 handbreadth directly inferior to the medial condyle of the tibia (➞ **SP-9**). **SP-8** is located 3 cun distal to ➞ **SP-9** on the posterior border of the medial crest of the tibia, on a line connecting ➞ **SP-9** and the highest prominence of the medial malleolus.

Needling

Vertically 1–1.5 cun

Actions/Indications

- Regulates the uterus and the Blood
- Regulates the Spleen and eliminates Dampness

Special features

Xi-cleft point. Important point for acute dysmenorrhoea, often used in combination with ➞ **L.I.-4**.


Pes anserinus
Medial condyle of the tibia
3 cun
SP-9
At the junction of the shaft and medial condyle of the tibia
SP-8


KID-10
Popliteal crease
LIV-8
1
Junction tibial shaft/medial condyle of the tibia
SP-9
2
LIV-7
3
4
SP-8
5
6
7
LIV-6
8
9
SP-7
LIV-5
10
KID-9
11
SP-6
12
KID-7
13
KID-8
14
KID-3
15 cun
Highest prominence of the medial malleolus
SP-5
SP-1
SP-4
KID-2

Yin Mound Spring YINLINGQUAN SP-9

Location

With the knee flexed, this point is located in a depression distal to the medial condyle of the tibia, at the junction of the shaft and the medial condyle.

How to find

Patient's position: Preferably locate and needle **SP-9** with the knee bent and the hip slightly externally rotated, so that the knee slightly lifts from the surface, or rest the knee in an externally rotated position on a knee support. **Location**: Palpate along the posterior border of the medial crest of the tibia towards the head of the tibia to locate **SP-9** in a pressure-sensitive depression at the junction of the shaft and the head of the tibia. This depression is located between the pes anserinus superficialis and the belly of the gastrocnemius muscle (→ 3.6.1).

Located on the same level but 1 cun posterior to **SP-9** is → **LIV-7**.

Located on the lateral aspect of the lower leg is → **G.B.-34** (anterior and inferior to the head of the fibula).

Needling

1–1.5 cun vertically, along the posterior border of the tibia.

Actions/Indications

- Regulates the Spleen, transforms Dampness, regulates the water passages, benefits the Lower Burner
- As local point for disorders of the knee, especially if there are swellings

Special features

He-sea point, Water point. One of the major points for eliminating Dampness anywhere in the body. Important local point for disorders of the knee. **SP-9** is located approximately on the same level as → **G.B.-34**. If indicated, this point tends to be very tender upon pressure.


Pes anserinus
Medial condyle of the tibia
SP-9
At the junction of the shaft and medial condyle of the tibia
Gastrocnemius


19 cun
SP-11
ST-32
ST-33
ST-34
Ex-LE-3
LIV-9
SP-10
Ex-LE-2
Ex-LE-1
Popliteal crease
ST-35
Ex-LE-4
LIV-8
G.B.-34
SP-9
ST-36
ST-37
9
10
11
12
13
14
15
16
17
18
19
20 cun
1
2
3
4
5
6
Upper border of the patella
8 cun


1 cun
SP-9
LIV-7


G.B.-34
Head of the fibula


Femur
Tibia
SP-9

SP-10 *Sea of Blood* XUEHAI

Location

With the knee flexed, **SP-10** is located 2 cun proximal and slightly medial to the medial superior border of the patella, in a depression on the vastus medialis muscle.

How to find

Measure 2 cun proximal to the medial superior border of the patella and locate **SP-10** by palpating slightly medially for a soft depression. **Or**: The practitioner places their left hand on the patient's right patella, with the heel of the palm level with the inferior patellar border and the extended fingers pointing in a superior direction. With the thumb and index finger forming an angle of 45°, the tip of the thumb will point to **SP-10**.

Needling

Vertically or obliquely 1–1.5 cun

Actions/Indications

- Strengthens the Blood, dispels Blood stasis, cools the Blood, stops bleeding, regulates menstruation, benefits the skin
- Local point for disorders of the knee

Special features

Important point for regulating the Blood









Winnowing Gate JIMEN **SP-11**


Upper border
of the pubic
symphysis
SP-12
Symphysis
1/2
Sartorius
SP-11
6 cun
8 cun
SP-10
1/2
Patella
Knee joint space


19 cun
SP-11
10
11
ST-32
12
13
ST-33
14
Ex-LE-3
LIV-9
15
ST-34
16
SP-10
17
Ex-LE-2
18
Upper border of the patella
Ex-LE-1
19
Popliteal crease
20 cun
ST-35
LIV-8
Ex-LE-4
1
G.B.-34
SP-9
2
ST-36
3
4
8 cun
5

Location

6 cun proximal to ➞ **SP-10** or 8 cun proximal to the medial upper border of the patella, at the midpoint of the femur between the sartorius and vastus lateralis muscles.

How to find

First, locate ➞ **SP-10** by measuring 2 cun proximal and 1 cun medial from the medial upper border of the patella. From there, measure 6 cun vertically in a proximal direction to locate **SP-11** in a depression on the lateral border of the sartorius muscle. **Or**: Spreading hands technique (➞ 2.3.3): **SP-11** is located midway between the knee joint space and ➞ **SP-12** (2 cun lateral to the anterior midline, on a level with the upper border of the pubic symphysis).

Needling

Vertically 0.5–1 cun. Caution: Femoral artery/vein.

Actions/Indications

- Regulates the Lower Burner and urination, drains Dampness, clears Heat


Medial leg
Upper border of the pubic symphysis
18 cun
LIV-10
SP-11
8 cun
LIV-9
SP-10
2 cun
Upper border of the patella
KID-10
Popliteal crease
LIV-8
1
Junction tibal shaft/medial condyle of the tibia
SP-9
2
LIV-7
3
4
SP-8
5


Upper border
of the pubic
symphysis
SP-12
Symphysis
3.5 cun

SP-12 *Rushing Gate* CHONGMEN

Location

3.5 cun lateral to the midline, at the level of the upper border of the pubic symphysis, lateral to the femoral artery.

How to find

From the upper border of the pubic symphysis (➞ **Ren-2**), measure 3.5 cun in a lateral direction. There, you can feel the pulsation of the femoral artery. **SP-12** is located in a depression immediately lateral to the artery.

Located on the same level are **Ren-2** (on the midline), ➞ **KID-11** (0.5 cun lateral to the midline) and ➞ **ST-30** (2 cun lateral to the midline). ➞ **LIV-12** is located 2.5 cun lateral to the midline, but 1 cun inferior to the upper border of the pubic symphysis.

Needling

Vertically 0.5–1 cun. Caution: Needling in a medial direction may puncture the artery; needling in a lateral direction may injure the femoral nerve.

Actions/Indications

- Regulates Qi and Blood in the Lower Burner
- Descends rising fetal Qi
- Clears Heat and drains Dampness

Special features

Meeting point with the LIV and T.B.* channels and the *yin wei mai*


Femoral-
Nerve
Artery
Vein
Upper border of the pubic symphysis
SP-12
Symphysis
3,5 cun


15
25
16
8
14
6
27
14
4
29
12
13
SP-12
ST-30
KID-11
Ren-2
Umbilicus
1
2
3
4
Upper border of the pubic symphysis


KID-12
Ren-03
KID-11
Ren-02
Upper border of the pubic symphysis


Ren-2
Upper border of the pubic symphysis
1 cun
LIV-12


SP-13
0.7 cun
ST-30
Upper border of the pubic symphysis
SP-12
Symphysis

---

* According to some authors

Abode of the Fu FUSHE SP-13


Femoral-
Nerve
Artery
Vein
SP-13
Upper border of the pubic symphysis
0.7 cun
SP-12
Symphysis
0.5 cun
3.5 cun


ST-25
KID-16
SP-15
Ren-8
SP-14
ST-28
Ren-4
Ren-3
SP-13
ST-30
SP-12
Ren-2
Upper border of the pubic symphysis
Highest prominence of the greater trochanter
ST-31
SP-11
LIV-11
LIV-10
1
2
3
4
5
6
7
8
9
10
11
19 cun
SP-11

Location

4 cun lateral to the anterior midline and 0.7 cun superior to the upper border of the pubic symphysis.

How to find

First, measure 4 cun in a lateral direction from the upper border of the pubic symphysis and from there 0.7 cun in a superior direction to locate **SP-13** in a depression in the inguinal groove. **SP-13** is located 0.5 cun lateral and 0.7 cun superior to → **SP-12** (→ 3.5 cun lateral to the upper border of the pubic symphysis).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum.

Actions/Indications

- Disperses accumulations
- Regulates the Qi

Special features

Meeting point with the *yin wei mai* and the Liver channel

SP-14 *Abdomen Knot* FUJIE

Location

4 cun lateral to the anterior midline, on the mamillary line, 3 cun superior to ➞ **SP-13** or 1.3 cun inferior to ➞ **SP-15**.

How to find

First, measure 4 cun from the umbilicus in a lateral direction in order to locate the mamillary line. This is the point ➞ **SP-15**. From there, measure 1.3 cun in an inferior direction to locate **SP-14**.

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Moves Qi and Blood, warms the middle, dispels Cold
- Regulates the Lower Burner and descends counterflow Qi

Special features

Sensitive to pressure with appendicitis


Midline
Mamillary line
4 cun
SP-15
1.3 cun
SP-14


ST-25
SP-16
SP-15
Ren-8
SP-14
ST-28
Ren-4
Ren-3
ST-30
Ren-2
SP-12
Highest prominence of the greater trochanter
ST-31
KID-11
Upper border of the pubic symphysis
LIV-11
LIV-10
19 cun
SP-11
1
2
3
4
5
6
7
8
9
10
11


SP-13
Upper border of the pubic symphysis
0.7 cun
SP-12
Symphysis
0.5 cun
3.5 cun

Great Horizontal DAHENG SP-15

Location

4 cun lateral to the centre of the umbilicus, on the mamillary line.

How to find

Locate **SP-15** 4 cun lateral to the umbilicus, using the mamillary line for reference, especially in male patients.
Located on the same level are → **Ren-8/KID-16/ST-25/G.B.-26** (umbilicus/0.5 cun lateral to the umbilicus/2 cun lateral to the umbilicus/below the free end of the 11th rib at the level of the umbilicus).

Needling

Vertically 1–1.5 cun. Caution: Peritoneum, pregnancy. Deep needling may reach the aponeuroses of the transverse abdominal musculature.

Actions/Indications

- Regulates and moves Qi in the Intestines (promotes bowel movement by stimulating peristalsis)

Special features

Meeting point with the *yin wei mai*. Important point for regulating the Large Intestine Qi.


Mamillary line
2 cun
4 cun
ST-25
SP-15


Umbilicus
SP-15




0.5
KID-16
Umbilicus
Ren-08


11th rib
G.B.-26



SP-16 *Abdomen Sorrow* FUAI

Location

3 cun above the centre of the umbilicus and 4 cun lateral to the anterior midline, on the mamillary line.

How to find

The distance between the sternocostal angle and the centre of the umbilicus can be divided into 8 proportional cun, which can differ considerably from the patient's finger cun; therefore, only proportional cun measurements should be applied (elastic tape → 2.3.1). First, measure 3 cun from the umbilicus in a superior direction, then 4 cun in a lateral direction, where **SP-16** is located on the mamillary line. Depending on the shape of the thorax, this point will either be located on the abdomen or it will project onto the lower border of the ribcage.

Located on the same level are → **Ren-11** (anterior midline), → **KID-18** (0.5 cun lateral to the anterior midline) and → **ST-22** (2 cun lateral to the anterior midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy. Depending on the shape of the thorax, the correct location of this point might be on the costal cartilage. In this case, either transverse (subcutaneous) needling or locate the point more medially (or choose an alternative point).

Actions/Indications

- Regulates Qi in the Intestines
- Drains Dampness

Special features

Meeting point with the *yin wei mai*


Midline
Mamillary line
4 cun
SP-16
3 cun
SP-15


17
18
22
15
LIV-14
G.B.-24
12
16
22
18
LIV-13
15
25
16
8
14
6
8
Sterno-costal angle
7
6
5
4
3
2
1
Umbilicus
1


Ren-11
3 cun
Umbilicus


KID-18
Ren-11
KID-17
Ren-10
2 cun
0.5 cun
Umbilicus



Ch04.4-F10028.qxd 2/23/08 7:09 PM Page 197

Food Cavity SHIDOU SP-17


4th intercostal space
SP-17
5th intercostal space
6 cun
Midline


Sternocostal angle
Ren-16


KID-24
KID-23
Ren-17
KID-22
5th intercostal space


Sternocostal angle
ST-18

Location

In the 5th intercostal space, 6 cun lateral to the anterior midline (in male patients, 2 cun lateral to the nipple).

How to find

In men, the nipple is generally located on the level of the 4th intercostal space, while in women, when in a supine position, it is not always at this level. Locate **SP-17** in the 5th intercostal space, 2 cun lateral to the mamillary line (note that the intercostal space laterally curves upward). Both the clavicle and the manubriosternal synchondrosis are good reference points for locating the 5th intercostal space. **SP-17** can be located by following the course of the intercostal space in a lateral direction and measuring 2 cun lateral to the mamillary line.

Also located on the level of the 5th intercostal space are ➞ **Ren-16** (anterior midline), ➞ **KID-22** (2 cun lateral to the anterior midline) and ➞ **ST-18** (4 cun lateral to the anterior midline).

Needling

0.5–0.8 cun obliquely or transversely (subcutaneously), parallel to the intercostal space or with or against the channel pathway. Caution: Pneumothorax.

Actions/Indications

- Regulates the Qi
- Harmonises the Stomach and eliminates stagnation
- Drains Dampness

SP-18 *Heavenly Stream* TIANXI

Location

In the 4th intercostal space, 6 cun lateral to the anterior midline or 2 cun lateral to the midclavicular line.

How to find

In men, the nipple is generally located on the level of the 4th intercostal space, while in women, when in a supine position, it is not always at this level. Follow the course of the 4th intercostal space in a lateral direction and locate **SP-18** 2 cun lateral to the nipple (note that the intercostal space laterally curves upward). In women, either the clavicle or the manubriosternal synchondrosis are good reference points for locating the 4th intercostal space (→ 3.5). **SP-18** can be located by following the course of the intercostal space in a lateral direction while measuring 6 cun laterally from the anterior midline or 2 cun laterally from the nipple.

Also located on the level of the 4th intercostal space are → **Ren-17** (anterior midline), → **KID-23** (2 cun lateral to the anterior midline), → **ST-17** (nipple), → **P-1** (1 cun lateral to the nipple) and → **G.B.-23** (1 cun anterior to **G.B.-22**).

Needling

0.5–0.8 cun obliquely or transversely (subcutaneously), parallel to the intercostal space or with or against the channel pathway. Caution: Pneumothorax.

Actions/Indications:

- Unbinds the chest
- Descends the Qi
- Benefits the breasts


SP-18
4th intercostal space
6 cun


KID-24
KID-23
KID-22
4th intercostal space
Ren-17


3rd intercostal space
4th intercostal space


1 cun
P-1
4. ICR


G.B.-23
4th intercostal space
G.B.-22
1 cun


12
Ren-22
KID-27
14
26
20
SP-20
25
19
19
16
24
18
17
17
18
22
15
LIV-14
G.B.-24
12
16
22
18
Sterno-costal angle
8
7
6
5
4
3


Level of the nipple
4th intercostal space
Ren-17

Chest Village XIONGXIANG **SP-19**


6 cun
LU-1
SP-20
SP-19
1st intercostal space
2nd intercostal space
3rd intercostal space

Location

In the 3rd intercostal space, 6 cun lateral to the anterior midline or 2 cun lateral to the midclavicular line.

How to find

Locate the 3rd intercostal space by counting parasternally from the clavicle or from the manubriosternal synchondrosis (→ 3.5). Follow the course of the intercostal space in a lateral direction and locate **SP-19** 6 cun lateral to the anterior midline or 2 cun lateral to the midclavicular line (note: the intercostal space laterally curves upward).

Located on the same level (note: course of the intercostal space) are → **Ren-18** (anterior midline), → **KID-24** (2 cun lateral to the midline) and → **ST-16** (4 cun lateral to the midline).


Ren-19
3rd intercostal space
Ren-18
Ren-17
Ren-16


KID-24
3rd intercostal space
KID-23
Ren-17
KID-22


2nd intercostal space
ST-16
3rd intercostal space
4th intercostal space

Needling

0.5–0.8 cun obliquely or transversely (subcutaneously), parallel to the intercostal space, or with or against the channel pathway. Caution: Pneumothorax.

Actions/Indications

- Disperses and descends the Lung Qi
- Unbinds the chest

SP-20 *Encircling Glory* ZHOURONG

Location

In the 2nd intercostal space, 6 cun lateral to the anterior midline or 2 cun lateral to the midclavicular line.

How to find

Locate the 2nd intercostal space by counting parasternally from the clavicle or from the manubriosternal synchondrosis (→ 3.5). Follow the course of the intercostal space in a lateral direction and locate **SP-20** 6 cun lateral to the anterior midline or 2 cun lateral to the midclavicular line (note: the intercostal space laterally curves upward). **SP-20** is located 1 cun inferior to → **LU-1**. Located on the same level (note: course of the intercostal space) are → **Ren-19** (anterior midline), → **KID-25** (2 cun lateral to the midline) and → **ST-15** (4 cun lateral to the midline).

Needling

0.5–0.8 cun obliquely or transversely (subcutaneously), parallel to the intercostal space or with or against the channel pathway. Caution: Pneumothorax.

Actions/Indications

- Unbinds the chest
- Regulates the Lung Qi


6 cun
Lu-1
SP-20
SP-19
1st intercostal space
2nd intercostal space
3rd intercostal space


Ren-21
Ren-20
2nd intercostal space
Ren-19


KID-25
2nd intercostal space
KID-24
KID-23
Ren-17


ST-14
1st intercostal space
ST-15
2nd intercostal space


ST-9
12
Ren-22
KID-27
14
26
20
SP-20
25
19
19
16
24
18
17
17
18
22
15
LIV-14
G.B.-24
12
16
22
18
Sterno-costal angle
8
7
6
5
4
3
2

Great Wrapping DABAO **SP-21**


4th intercostal space
5th intercostal space
6th intercostal space
SP-21
Mid-axillary line

Location

On the midaxillary line, in the 6th intercostal space. Note: According to some texts, this point is located in the 7th intercostal space.

How to find

Locate the 6th intercostal space by counting parasternally from the clavicle or from the manubriosternal synchondrosis (→ 3.5). Follow the course of the intercostal space in a lateral direction and locate **SP-21** on the axillary midline (note: the intercostal space laterally curves upward). **SP-21** is often sensitive to pressure. Or: Locate **SP-21** on the midaxillary line, midway between the axilla and the end of the 11th rib.

Needling

0.5–0.8 cun obliquely or transversely (subcutaneously), parallel to the intercostal space or with or against the channel pathway. Caution: Pneumothorax.

Actions/Indications

- Regulates Qi and Blood, governs and wraps all the *luo*-connecting vessels of the body
- Unbinds the chest

Special features

Great *luo*-connecting point of the spleen (→ 8.1.2), exit point.


SP-20
SP-21
Mid-axillary line


G.B.-22
4th intercostal space
5th intercostal space
6th intercostal space
SP-21
Mid-axillary line
11th rib
LIV-13

4.5 The Heart Channel System – Hand *shaoyin* (*shou shao yin jing luo*)

4.5.1 The Heart Primary Channel (*shou shao yin jing*)


HE-1
2
3
4
7
8
HE-9


1
2
3
4
5
6
7
8
Cubital crease 9 cun
1
2
3
4
5
6
7
8
9
10
11
12
Wrist joint space
cun
HE-1
HE-2
HE-3
HE-4
5
6
HE-7
Palm
HE-8
Pisiform
0.5 cun
0.5 cun
0.5 cun
Tendon of the flexor carpi ulnaris
Flexor carpi ulnaris
HE-7
HE-6
HE-5
HE-4
Wrist crease
Right hand


Tendon of the flexor carpi ulnaris
HE-7
Radius
Ulna


HE-9
HE-9
HE-8
Palm
HE-7
Right hand

Pathway

The **internal** pathway of the Heart primary channel originates in its related *zang*-Organ, the Heart (*xin*). An **internal branch** of the Spleen primary channel reaches the Heart and connects with the Heart primary channel (deep Yin–Yin connection ➞ 1.2).

The **internal pathway** of the Heart primary channel splits into three branches:

- **the first branch** penetrates the diaphragm and connects with the internally–externally related *fu*-Organ, the Small Intestine (*xiaochang*)
- **the second branch** ascends along the oesophagus and the neck region, disperses in the tissues around the eyes and, according to some authors, also spreads inside the brain.
- **the main branch** runs from the Heart to the Lung (*fei*) and descends again to emerge in the centre of the axilla at ➞ **HE-1** (*jiquan*) (beginning of the external pathway).

From here the **external pathway** runs along the anteromedial aspect of the upper arm and forearm, traverses the palm between the fourth and fifth metacarpal bones, continues along the radial aspect of the little finger and ends at the radial corner of its nail at **HE-9** (*shaoyang*).

From **HE-9** (*shaoyang*) a branch crosses to the ulnar border of the little finger's nail to ➞ **S.I.-1** (*shaoze*) (hand Yin–Yang connection of the second great circuit).

Clinical importance (➞ 1.2)

Exterior (*biao*) signs and symptoms: General fever, headaches, pain in the thorax and back, thirst with a desire to drink, Heat sensation in the palms, Cold invasion in the extremities, pain in the shoulder and the medial aspect of the upper arm

Interior (*li*) or *zangfu*-Organ signs and symptoms: Heart pain, pain and fullness in the thorax and lateral costal region, hypochondriac pain, irritability, shortness of breath, restlessness, dizziness, mental confusion

Connections of the Heart primary channel (→ 1.2)

Connections with other channels

Small Intestine primary channel (*shou tai yang jing*)

Connection: Hand Yin–Yang connection of the second great circuit
Location: H-9 → S.I.-1 (on the hand).
Circulation: Circadian (according to the Organ clock)
Importance: Exterior–Interior relationship

Kidney primary channel (zu shao yin jing)

Connection: Paired according to the six channel theory (hand–foot pairing): *shao yin* (Yin axes of the second great circuit)
Location: KID → HE (on the thorax). An internal branch of the Kidney primary channel travels to the Liver (*gan*), penetrates the diaphragm and spreads in the Lung (*fei*). From the Lung a branch runs to Heart (*xin*) and there connects with the Heart primary channel.
Circulation: Non-circadian (**not** according to the Organ clock)
Importance: Above–below relationship

Spleen primary channel (*zu tai yin jing*)

Connection: Deep Yin–Yin connection
Location: SP → HE (on the thorax). An **internal** branch of the Spleen primary channel spreads in the Heart (*xin*) and connects with the Heart primary channel.
Circulation: Circadian (according to the Organ clock)
Importance: The Heart primary channel receives Nutritive Qi (*ying qi*) from the Spleen primary channel (first circulation of the *ying qi* → 1.1.4)

Connections with other *zangfu*-Organ systems

Small Intestine (*xiaochang*), Heart (*xin*), Lung (*fei*)

4.5.2 The Heart Divergent Channel (*zu shao yin jing bie*)



Pathway

The Heart divergent channel separates from the Heart primary channel at **HE-1** (*jiquan*) in the axilla

- penetrates the thorax at → **G.B.-22** (*yuanyue*) on the mid-axillary line and 3 cun distal to the axilla
- and reaches the Heart (*xin*) (see commentary below).
- It then ascends to the neck and crosses → **Ren-23** (*lianquan*)
- disperses in the cheek and reaches the medial canthus of the eye at → **BL-1** (*jingming*), where, according to most authors, it connects with a small branch coming from → **S.I.-18** (*quanliao*) to form one of the six he-confluences (here: S.I./BL as fourth confluence → 1.3).

Commentary: according to Solinas et al (1998) the Heart divergent channel meets the Small Intestine divergent channel and the Small Intestine primary channel at the Heart (*xin*) in order to bind with one of the six he-confluences.

Clinical importance

- Strengthens the relationship between the Heart and the thoracic region. Points on the Heart primary channel mainly treat disorders of the Heart and the thorax. There is no connection with the Small Intestine (*xiaochang*).

- Connects the Heart primary channel with the neck. Points on the Heart primary channel can be used to treat disorders of the throat and vocal chords such as laryngitis, pharyngitis, etc. Use points such as **HE-5, HE-8**.
- Strengthens the connection between the Heart and the inner canthus of the eye. Heart points can thus be used for disorders of the eyes.

4.5.3 The Heart Sinew Channel (*shou shao yin jing jin*)


G.B.-22 (Meeting point of the three hand Yin sinew channels)
HE-3
HE-7

Pathway

The Heart sinew channel begins on the radial aspect of the little finger

- ➡ continues along the anterior and radial aspect of the little finger and the hand
- ➡ binds (*jie*) at the pisiform bone at **HE-7** (*shenmen*)
- ➡ ascends the anterior and ulnar aspect of the forearm, binds (*jie*) at the medial epicondyle at **HE-3** (*shaohai*) and continues to the axillary region, where it meets the Lung sinew channel, binds (*jie*) in the axilla and meets the other hand Yin sinew channels near → **G.B.-22** (*yuanye*)
- ➡ from here it continues at a deeper level, crosses the thoracic region, binds (*jie*) at → **Ren-17** (*shanzhong*), descends to the upper cardiac orifice, penetrates the diaphragm and terminates in the umbilical region.

Clinical importance

Pathology: Stiffness, cramps and pain along the pathway of the Heart sinew channel. Internal cramping in the cardiac region, for example disorders with angina-like pain due to stress, hiatal hernia and disorders of the stomach.

Indication: Mainly for *bi*-syndromes (painful obstruction syndrome) along the pathway of the Heart channel. The area covered by the Heart sinew channel is larger than that covered by the Heart primary channel. This explains why Heart primary channel points can also be used for disorders and diseases of the thorax and the chest, for example pain and tightness in the chest, mastitis and mastopathy. Since the Heart sinew channel also penetrates the diaphragm, it is also indicated for disorders such as hiccups, acid reflux and oesophagitis. Due to its connection with the umbilical region, the Heart sinew channel has a direct link to the Original Qi (*yuan qi*): if the Heart (*shen*) has suffered a shock, for example due to fainting or collapse, direct moxibustion at **Ren-8** can be very helpful.

4.5.4 The Heart *luo*-Connecting Vessel System (*shou shao yin luo mai*)



Pathway

The HE *luo*-connecting vessel separates from the Heart primary channel at its *luo*-connecting point **HE-5** (*tongli*) (→ 8.1.2). It forms a three-dimensional reticulate network, dividing into multiple branches and sub-branches (*sun luo, fu luo, xue luo* → 1.5) within the surrounding tissue.

- Horizontal divisions run to the Interiorly–Exteriorly paired Small Intestine primary channel; according to some schools of thought (for example Ngyen Van Nghi → Appendix) they travel as a **transverse** HE *luo*-connecting vessel to the *yuan*-source point → **S.I.-4** (*wangu*).
- A **longitudinal** division follows the pathway of the Heart primary channel along the anteromedial aspect of the arm, ascends to the axilla, reaches the Heart, ascends to the root of the tongue and terminates in the eye while further branches penetrate the brain.

Clinical importance (→ 8.1.2)

Pathology

- **Excess (*shi*)**: Distension and fullness of the thorax and diaphragm
- **Deficiency (*xu*)**: Aphasia, disorders of the vocal cords

4.5.5 Cutaneous Region (*shao yin pi bu*)

See description and figures → 1.6.

4.5.6 Points of the Heart Primary Channel (Overview)

Specific points according to their function

- ***Yuan*-source point (→ 8.1.1): HE-7** (*shenmen*) 🟦🟦
- ***Luo*-connecting point (→ 8.1.2.): HE-5** (*tongli*) 🟦■
- ***Xi*-cleft point (→ 8.1.3): HE-6 (*yinxi*)** 🟦■
- **Associated Back-*shu* point (→ 8.1.4): BL-15** (*xinshu*) 🟦■
- **Associated Front-*mu* point (→ 8.1.5): Ren-14** (*juque*) 🟦■
- **Five *shu*-transporting points (→ 8.1.6):**
  jing-well point (Wood): **HE-9** (*shaochong*) 🟦■
  ying-spring point (Fire), *ben* point (Five Phases): **HE-8** (*shaofu*) 🟦■
  shu-stream point (Earth), sedation point: **HE-7** (*shenmen*) 🟦🟦
  jing-river point (Metal): **HE-4** (*lingdao*)
  he-sea point (Water): **HE-3** (*shaohai*) 🟦■
- ***Hui*-meeting point (→ 8.1.7): –**
- **Opening point (→ 8.1.8): –**
- **Lower *he*-sea points (→ 8.1.9): –**
- ***Jiaohui*-meeting points (→ 8.1.10): –**
- **Gao Wu command point (→ 8.1.11): –**
- **Window of Heaven point (→ 8.1.12): –**
- **Points of the Four Seas (→ 8.1.13): –**
- **Ma Dan Yang Heavenly Star point (→ 8.1.14): HE-5** (*tongli*) 🟦■
- **Sun Si Miao Ghost point (→ 8.1.15): –**
- **Other functional points: –**

Points according to region

- **Local point (→ 8.2.1):** elbow – **HE-3** (*shaohai*) 🟦■
- **Distal points (→ 8.2.1):** tongue – **HE-5** (*tongli*) 🟦■; Heart – **HE-7** (*shenmen*) 🟦🟦, **HE-5** (*tongli*) 🟦■, **HE-3** (*shaohai*) 🟦■

Specific points according to the channel pathway (in numeric order)

- **HE-3** (*shaohai*) 🟦■: *he*-sea point (Water); local point for the elbow (→ 8.2.1); distal point for the Heart (→ 8.2.1)
- **HE-4** (*lingdao*): *jing*-river point (Metal)
- **HE-5** (*tongli*) 🟦■: *luo*-connecting point (→ 8.1.2); Ma Dan Yang Heavenly Star point (→ 8.1.14); distal point for the tongue and Heart (→ 8.2.1)
- **HE-6** (*yinxi*) 🟦■: *xi*-cleft point (→ 8.1.3)
- **HE-7** (*shenmen*) 🟦🟦: *yuan*-source point (→ 8.1.1); distal point for the Heart (→ 8.2.1); *shu*-stream point (Earth), sedation point
- **HE-8** (*shaofu*) 🟦■: *ying*-spring point (Fire); *ben* point (Five Phases)
- **HE-9** (*shaochong*) 🟦■: *jing*-well point (Wood), tonification point

Summit Spring JIQUAN HE-1



Location

With the arm abducted, in the centre of the axilla, medial to the axillary artery.

How to find

With the arm abducted, palpate along the thoracic wall in a superior direction towards the centre of the axilla until you reach the highest point.

Needling

Palpate for the artery before needling! 0.5–1 cun vertically in the direction of → **G.B.-21** (border of the trapezius, middle of the shoulder). Caution: Axillary plexus and artery. Needling in a medial direction may puncture the lung!

Actions/Indications

- Unbinds the chest
- Opens the channel
- Nourishes the Heart Yin

Special features

Entry point. Important point in Qigong practice: During practice (and in everyday life), the axillary region should always be slightly open to allow for the free circulation of Qi and Blood to and from the upper extremity.





HE-2 *Green Spirit* QINGLING

Location

3 cun proximal to the cubital crease, on the medial border of the biceps brachii muscle.

How to find

With the elbow flexed, measure 3 cun from the ulnar end of the cubital crease (→ **HE-3**) towards the axilla. **HE-2** is located in a groove on the medial border of the biceps brachii muscle. Ask the patient to flex this muscle for easier location.

Needling

Vertically or obliquely 0.5–1 cun. Caution: Brachial artery! According to classic texts, needling is contraindicated, only moxibustion is permitted.

Actions/Indications

- Opens the channel


Medial end of the cubital crease
He-2
Biceps
3 cun


LU-2
LU-1
HE-1
P-1
P-2
LU-3
LU-4
HE-2
LU-5
P-3
HE-3
1
2
3
4
5
6
7
8
9
cun
1
2
3
4
5

Lesser Sea SHAOHAI **HE-3**


Cubital crease
1/2
1/2
P-3
HE-3
Medial epicondyle of the humerus


Biceps brachii
Medial head of the triceps brachii
Aponeurosis of the biceps brachii
P-3
HE-3
LU-5
Medial epicondyle
Tendon of the biceps brachii
Palmaris longus

Right arm anterior aspect


Biceps tendon
Cubital crease
P-3
LU-5
HE-3

Right arm

Location

With the elbow flexed, this point is in a depression between the ulnar end of the transverse cubital crease and the medial epicondyle of the humerus.

How to find

This point should be located with the elbow slightly flexed and the forearm in a supinated position. Find the ulnar end of the transverse cubital crease and palpate towards the medial epicondyle of the humerus (→ 3.2.2). **HE-3** is located in a depression approximately midway between → **P-3** and the medial epicondyle. **Or**: With the elbow fully flexed, **HE-3** is located directly at the medial end of the transverse crease.

Located on the same level are → **P-3** (ulnar to the tendon of the biceps muscle), → **LU-5** (radial to the tendon of the biceps muscle) and → **L.I.-11** (at the radial end of the crease).

Needling

0.5–1.5 cun obliquely in a distal or proximal direction or vertically towards → **L.I.-11**.

Actions/Indications

- Transforms Phlegm, clears Heat (from the heart), calms the *shen*
- Opens the channel and *luo*-vessels

Special features

He-sea point, Water point. Important local point, important calming point.


90°
L.I.-11
Lateral epicondyle
Olecranon

HE-4 *Spirit Path* LINGDAO

Location

1.5 cun proximal to the transverse wrist crease, on the radial side of the tendon of the flexor carpi ulnaris muscle.

How to find

The flexor carpi radialis muscle has a distinct tendon which can be easily palpated ulnar and proximal to the wrist crease. It attaches to the pisiform bone (→ 3.3.3). **HE-4** is located directly on the radial side of the tendon.

→ **HE-5**, → **HE-6** and → **HE-7** are located at 0.5 cun intervals distal to **HE-4**. → **LU-7** is located approximately 1.5 cun proximal to the wrist crease on the radial aspect of the forearm.

Needling

0.3–1 cun vertically or obliquely in a proximal or distal direction.

Actions/Indications

- Opens the channel
- Nourishes the Heart, calms the *shen*
- Strengthens the voice

Special features

Jing-river point, Metal point.


1.5 cun
HE-7
HE-4
Pisiform
Tendon of the flexor carpi ulnaris


9
10
11
12 cun
P-4
P-5
P-6
LU-7
LU-8
LU-9
P-7
HE-4
HE-5
HE-6
HE-7
LU-10
LU-11
P-8
HE-8
HE-9
P-9


Tendon of the flexor carpi ulnaris
Pisiform
HE-7
Joint space


Wrist joint space
Abductor pollicis longus
Brachioradialis
1.5 cun
LU-7


Tendon of the flexor carpi ulnaris
Tendon sheath of the flexor carpi radialis
Abductor digiti minimi
Opponens pollicis
Flexor pollicis brevis
Abductor pollicis brevis

Penetrating the Interior TONGLI **HE-5**


Flexor
carpi ulnaris
HE-5
Tendon of
the flexor
carpi ulnaris
1 cun
Joint space
Pisiform
HE-7


HE-5
Wrist joint space


Abductor
pollicis longus
Radial artery
LU-8
1 cun
LU-9
Joint space
Carpal bones

Location

1 cun proximal to the ventral wrist joint space (‘most distal transverse wrist crease’), on the radial side of the tendon of the flexor carpi ulnaris muscle.

How to find

Position the forearm in a relaxed fashion. The location of the ventral wrist crease is variable; therefore, the proximal border of the pisiform bone (→ 3.3.2) provides a more reliable landmark. → **HE-7** is located on the wrist joint space, radial to the distinct tendon of the flexor carpi ulnaris muscle. Locate **HE-5** 1 cun proximal to → **HE-7**, also on the radial side of the tendon.

Located along a line on the radial aspect of the tendon are → **HE-6** (0.5 cun proximal to → **HE-7**) and → **HE-4** (1.5 cun proximal to **HE-7**). → **LU-8** is also located 1 cun proximal to the ventral wrist joint space, but on the radial aspect of the forearm.

Needling

Vertically 0.3–0.5 cun or obliquely 0.5–1 cun in a proximal or distal direction. Caution: Needling may be painful.

Actions/Indications

- Regulates and strengthens the Heart Qi (main point!) and the Heart rhythm
- Calms the *shen*
- Benefits the tongue
- Benefits the Bladder (via the *taiyang* channel)
- Opens the channel and *luo*-connecting vessels

Special features

Luo-connecting point, Ma Dan Yang Heavenly Star point. Main point for regulating and strengthening the Heart Qi.

HE-6 *Yin Cleft* YINXI

Location

0.5 cun proximal to the transverse wrist crease, on the radial side of the tendon of the flexor carpi ulnaris muscle.

How to find

The flexor carpi ulnaris muscle has a distinct tendon on the ventral aspect of the forearm that can be easily palpated ulnar and proximal to the wrist. **HE-6** is located on the radial aspect of the tendon, 0.5 cun proximal to → **HE-7** (located on the joint space).

→ **HE-5** and → **HE-4** are located proximally on the same line at 0.5 cun intervals.

Needling

0.3–1 cun vertically or obliquely in a proximal or distal direction. Caution: Ulnar artery/nerve. Painful point!

Actions/Indications

- Tonifies and regulates the Heart Yin and Blood, clears empty Heat in the Heart, calms the *shen*

Special features

Xi-cleft point


Tendon of the flexor carpi radialis
Tendon of the palmaris longus
Tendon of the flexor carpi ulnaris
Wrist joint space
Pisiform
HE-7
P-7
LU-9


0,5 cun
HE-7
HE-6
Pisiform
Tendon of the flexor carpi ulnaris


11
12 cun
P-5
LU-7
P-6
LU-8
HE-4
LU-9
HE-5
P-7
HE-6
LU-10
HE-7
P-8
HE-8
LU-11
HE-9
P-9


Tendon of the flexor carpi ulnaris
Tendon sheath of the flexor carpi radialis
Opponens pollicis
Abductor digiti minimi
Flexor pollicis brevis
Abductor pollicis brevis

Spirit Gate SHENMEN HE-7


Flexor carpi ulnaris
Tendon of the flexor carpi ulnaris
Pisiform
HE-7
Joint space




0.5 cun
HE-7
HE-6

Location

On the ventral aspect of the wrist joint space ('most distal wrist crease'), radial to the insertion of the tendon of the flexor carpi ulnaris muscle.

How to find

Position the forearm in a relaxed supinated position. As the location of the wrist crease can vary, the proximal border of the pisiform bone (➞ 3.3.3) should be used for reference instead. **HE-7** is located radial to the insertion of the tendon of the flexor carpi ulnaris muscle, in a depression proximal to the pisiform bone.

➞ **HE-6**, ➞ **HE-5** and ➞ **HE-4** are all located on a line on the radial aspect of the tendon at 0.5 cun intervals. Also located on the wrist crease are ➞ **P-7** (between the tendons of the palmaris longus and the flexor carpi radialis muscles) and ➞ **LU-9** (on the radial aspect, lateral to the radial artery).

Needling

0.3–0.5 cun vertically or transversely deep to the tendon (parallel to the wrist crease 0.5–0.8 cun). Caution: Ulnar artery/nerve. Painful point!

Actions/Indications

- Regulates and strengthens the Heart (Blood and Yin), calms the *shen*
- Clears Heat from the Heart channel
- Moves Qi locally for disorders of the wrist

Special features

Yuan-source point, *shu*-stream point, Earth point, sedation point. Major point for calming the *shen*.


Tendon of the flexor carpi ulnaris
HE-7
Radius
Ulna

HE-8 *Lesser Palace* SHAOFU

Location

On the palm, between the 4th and 5th metacarpal bones.

How to find

When making a fist, **HE-8** is generally located below the tip of the little finger, in the depression between the 4th and 5th metacarpal bones. **HE-8** often lies between the two transverse palmar creases. It is often sensitive to pressure.

→ **P-8** is also located on the palm, generally below the tip of the middle finger when making a fist (between the 2nd and 3rd metacarpal bones).

Needling

Vertically 0.5–1 cun. Caution: Needling this point may be painful. Provide a competitive stimulus by pressing the palm with the fingernail close to the point before inserting the needle. Ask the patient to breathe out during needle insertion.

Actions/Indications

- Clears Heat in the Heart and Small Intestine
- Regulates the Heart Qi for Liver Qi stagnation
- Calms the *shen* and strengthens the Heart Qi
- Opens the channel, especially for contractures of the fingers

Special features

Ying-spring point, Fire point, *ben* point (Five Phases).







Lesser Rushing SHAOCHONG **HE-9**





Location

On the little finger, 0.1 cun lateral to the radial corner of the nail.

How to find

This point is located at the junction of two tangents that border the radial and proximal aspect of the nail, approximately 0.1 cun from the actual corner of the nail. → **S.I.-1** is located on the opposite (ulnar) aspect of the nail.

Needling

0.2–0.3 cun vertically or obliquely in a proximal direction. For acute disorders (pain, inflammation), prick to bleed with a needle, lancet or three-edged needle. Caution: Painful point!

Actions/Indications

- Revives consciousness
- Clears Heat from the opposite end of the channel
- Regulates Qi in the chest and clears Heat in the Heart
- Opens the channel

Special features

Jing-well point, Wood point, tonification point, exit point.

4.6 The Small Intestine Channel System – Hand *taiyang* (*shou tai yang jing luo*)

4.6.1 The Small Intestine Primary Channel (*shou tai yang jing*)


(T.B.-20)* T.B.-22
G.B.-21
BL-1
S.I.-19
(G-B.-11)*
Du-14
BL-11
BL-41
16
S.I.-15
ST-12
S.I.-13
Ren-17
L.I.-14*
(Variant according to Deadman)
Ren-13
Ren-12
S.I.-8
S.I.-1
*meeting points only mentioned by some authors
To ST-39
Lower *he*-Sea point of the Small Intestine


S.I.-12
S.I.-10
S.I.-11
S.I.-9
1
2
3
4
5
6
7
8
9
cun
S.I.-8
1
2
3
4
5
6
7
8
9
10
11
12
cun
S.I.-7
S.I.-6


S.I.-1
S.I.-2
S.I.-3
Hamate
S.I.-4
Triquetrum
S.I.-5
Styloid process of the ulna
S.I.-6


Levator scapulae
Supraspinatus
Scapular spine
S.I.-15
S.I.-14
Teres minor
S.I.-12
S.I.-10
S.I.-13
Spinous process
1/3
T4
T5
S.I.-11
S.I.-9
2/3
Inferior angle of the scapula
Infraspinatus
Teres major


S.I.-19
S.I.-18
L.I.-20
Lower border of the zygomatic arch
S.I.-17
Masseter
S.I.-16
Sternocleidomastoid

Pathway

The **external** pathway of the Small Intestine primary channel begins on the little finger, on the ulnar corner of the nail, at **S.I.-1** (*shaoze*). This point is reached by a branch that separates from the Heart primary channel at → **HE-9** (*shaochong*) (hand Yin–Yang connection of the second great circuit).

The channel runs along the ulnar border of the hand, passes the wrist and continues along the ulna to the medial aspects of the elbow.

- ➡ passes between the olecranon and the medial epicondyle, ascends the posterior aspect of the humerus to the shoulder joint and, according to some authors, meets → **L.I.-14**
- ➡ zig-zags across the scapula, passes → **BL-41** (*fufen*) and → **BL-11** (*dazhu*) and meets the extraordinary vessel *du mai* and the other Yang primary channels at → **Du-14** (*dazhui*), below the spinous process of C7
- ➡ continues anteriorly to the supraclavicular fossa to → **ST-12** (*quepen*).

An **internal** branch originates at → **ST-12** and runs inferiorly to the Heart (*xin*), the paired *zang*-Organ, continues to → **Ren-17** and descends along the oesophagus, penetrates the diaphragm and continues to the Stomach (*wei*). Here it crosses → **Ren-13** (*shangwan*) and → **Ren-12** (*zhongwan*), further descends and spreads in its pertaining *fu*-Organ, the Small Intestine (*xiaochang*).

According to the *Neijing Ling Shu*, an **internal** branch courses from the Small Intestine (according to some authors from the Small Intestine primary channel) to → **ST-39** (*xiajuxu*), the lower *he*-sea point of the Small Intestine.

The **external** pathway of the Small Intestine primary channel continues from the supraclavicular fossa along the neck and ascends to the cheek to **S.I.-18** (*quanliao*).

From **S.I.-18**

- ➡ **a branch** courses to → **BL-1** (*jingming*) at the inner canthus of the eye, where it connects with the Bladder primary channel (six channel theory, Yang axes: *taiyang*)
- ➡ **a further branch** travels to the outer canthus of the eye, intersects with → **G.B.-1** (*tongziliao*), according to some authors also with → **T.B.-20** and → **G.B.-11**, continues to → **T.B-22** (*erheliao*) anterior to the ear and terminates anterior to the ear deep to **S.I.-19** (*tinggong*)

Clinical importance (➡ 1.2)

Exterior (*biao*) signs and symptoms: Mouth and tongue ulcers, cheek pain, neck pain, occipital stiffness, pain on the lateral aspect of the shoulder and the upper arm

Interior (*li*) or *zangfu*-Organ signs and symptoms: Pain and distension of the upper abdomen, radiating to the genital region, diarrhoea, epigastric pain with constipation

Connections of the Small Intestine primary channel

Connections with other channels

Heart primary channel (*shou shao yin jing*)

Connection: Hand Yin–Yang connection of the second great circuit
Location: **H-9** → **S.I.-1** (on the hand)
Circulation: Circadian (according to the Organ clock)
Importance: Exterior–Interior relationship

Bladder primary channel (*zu tai yang jing*)

Connection: Paired according to the six channel theory (hand–foot pairing): *tai yang* (Yang axes of the second great circuit)
Location: **S.I.-18** → **BL-1** (on the head)
Circulation: Circadian (according to the Organ clock)
Importance: Above–below relationship

Connections with other *zangfu*-Organ systems

Heart (*xin*), Stomach (*wei*), **Small Intestine (*xiaochang*)**

4.6.2 The Small Intestine Divergent Channel (*shou tai yang jing bie*)



Pathway

The Small Intestine divergent channel separates from the Small Intestine primary channel at the shoulder, depending on the school of thought in the area of → **S.I.-12** (*bingfeng*) or in the area of → **S.I.-10** (*naoshu*)

- ➡ descends towards the axilla and continues to → **G.B.-22** (*yuanye*)
- ➡ penetrates the thorax and spreads in the Heart (*xin*) where, according to most authors, it forms the fourth confluence
- ➡ penetrates the diaphragm to connect with its pertaining *fu*-Organ, the Small Intestine

Clinical importance

- Strengthens the relationship between the Heart and the Small Intestine (*zangfu*-Organ system). It provides an explanation for the pattern of Heart Fire transferring to the Small Intestine and the Bladder.

4.6.3 The Small Intestine Sinew Channel (*shou tai yang yin jing jin*)


G.B.-13 (Meeting point of the three hand Yin sinew channels)
a
b
S.I.-9
c

Pathway

The Small Intestine sinew channel begins on the ulnar aspect of the little finger at ➞ **S.I.-1** (*shaoze*)

- ➡ continues along the ulnar aspect of the little finger and the ulnar border of the hand
- ➡ runs to **S.I.-5** (*yanggu*) distal to the styloid process of the ulna and binds (*jie*) at the wrist
- ➡ travels along the ulnar aspect of the forearm to the elbow, continues to the axilla, binding at **S.I.-8** (*xiaohai*) and the posterior aspect of the axilla.

From here a branch courses into the axilla where it binds (*jie*). Another branch spreads across the scapula and ascends anterior to the Bladder and Gall Bladder sinew channels and posterior to the Stomach sinew channel to the lateral aspect of the neck, where it meets the Triple Burner sinew channel.

At the neck it divides into **two branches:**

- ➡ the **anterior branch** runs to the mandibular angle where it binds (*jie*), continues along the mandible to the ear and the zygomatic bone to bind (*jie*) at the lateral aspect of the orbit
- ➡ the **posterior branch** binds (*jie*) at the mastoid process (from here a small branch runs to the ear). The branch curves around the ear, descends to the cheek and binds (*jie*) at the insertion of the masseter muscle on the mandible, continues to the lateral aspect of the orbit and reaches ➞ **G.B.-13** (*benshen*) on the frontoparietal aspect of the head, where it meets the other hand Yang sinew channels.

Clinical importance

Pathology: Distending sensations, stiffness and pain of the little finger, impaired range of motion of the upper extremity and shoulder. Pain, stiffness and impaired range of motion of the cervical spine and occiput. Tinnitus and ear pain radiating to the mandible.

Indication: Mainly for *bi*-syndromes (painful obstruction syndrome) along the pathway of the S.I. channel. The area covered by the Small Intestine sinew channel is larger than that covered by the Small Intestine primary channel. This explains why Small Intestine primary channel points can also be used for disorders and diseases of the cervical and thoracic spine and the whole face (for example frontal and lateral headaches).

4.6.4 The Small Intestine *luo*-Connecting Vessel System (*shou tai yang luo mai*)



Pathway

The S.I. *luo*-connecting vessel separates from the Small Intestine primary channel at its *luo*-connecting point **S.I.-7** (*zhizheng*) (→ 8.1.2). It forms a three-dimensional reticular network, dividing into multiple branches and sub-branches (*sun luo*, *fu luo*, *xue luo* → 1.5) within the surrounding tissue.

- Horizontal divisions run to the Interiorly–Exteriorly paired Heart primary channel, according to some schools of thought (for example Ngyen Van Nghi → Appendix) they travel as a **transverse** S.I. *luo*-connecting vessel to the *yuan*-source point → **HE-7** (*shenmen*).
- A **longitudinal** division runs to the medial condyle of the humerus, ascends to the shoulder to → **L.I.-15** (*jianyu*). According to some schools of thought the vessel spreads and terminates here, while according to other schools it traverses the acromion, continues to → **ST-12** (*quepen*) in the supraclavicular fossa, penetrating the thorax in order to connect with the Heart.

Clinical importance (➡ 8.1.2)

Pathology

- **Excess** (***shi***): Weak and unstable joints, weakness and paralysis of the elbow and the arm
- **Deficiency** (***xu***): Warts

4.6.5 Cutaneous Region (*tai yang pi bu*)

See description and figures → 1.6.

4.6.6 Points of the Small Intestine Primary Channel (Overview)

Specific points according to their function

- ***Yuan*-source point (→ 8.1.1): S.I.-4** (*wangu*)
- ***Luo*-connecting point (→ 8.1.2.): S.I.-7** (*zhizheng*)
- ***Xi*-cleft point (→ 8.1.3): S.I.-6** (*yanglao*) 🟦■
- **Associated Back-*shu* point (→ 8.1.4): BL-27** (*xiaochangshu*) 🟦■
- **Associated Front-*mu* point (→ 8.1.5): Ren-4** (*guanyuan*) 🟦🟦
- **Five *shu*-transporting point (→ 8.1.6):**
  jing-well point (Metal): **S.I.-1** (*shaoze*)
  ying-spring point (Water): **S.I.-2** (*qiangu*)
  shu-stream point (Wood), tonification point: **S.I.-3** (*houxi*) 🟦■
  jing-river point (Fire), *ben* point: **S.I.-5** (*yanggu*)
  he-sea point (Earth), tonification point: **S.I.-8** (*xiaohai*)
- ***Hui*-meeting point (→ 8.1.7): –**
- **Opening point (→ 8.1.8) of the *du mai*: S.I.-3** (*houxi*) 🟦🟦
- **Lower *he*-sea points (→ 8.1.9): –**
- ***Jiaohui*-meeting points (→ 8.1.10):**
  – with the BL channel, the *yang wei mai, yang qiao mai*: **S.I.-10** (*naoshu*)
  – with the L.I., T.B., G.B. channels: **S.I.-12** (*bingfeng*)
  – with the T.B. channel: **S.I.-18** (*quanlao*) 🟦■
  – with the T.B., G.B.: **S.I.-19** (*tinggong*) 🟦■
  – of other channels with the S.I. channel: **L.I.-14*, Du-14, BL-41, BL-11, ST-12, Ren-17*, Ren-13, Ren-12, G.B.-1, G.B.-11*, T.B.-20*, T.B.-22, BL-1**
- **Gao Wu command point (→ 8.1.11): –**
- **Window of Heaven point (→ 8.1.12): S.I.-16** (*tianchuang*), **S.I.-17** (*tianrong*) 🟦■
- **Points of the Four Seas (→ 8.1.13): –**
- **Ma Dan Yang Heavenly Star point (→ 8.1.14): –**
- **Sun Si Miao Ghost point (→ 8.1.15): –**

Points according to region

- **Local points (→ 8.2.1):** face and cheek – **S.I.-18** (*quanlao*) 🟦■; jaw – **S.I.-19** (*tinggong*) 🟦■; neck – **S.I.-17** (*tianrong*) 🟦■; ears – **S.I.-19** (*tinggong*) 🟦■; shoulder – **S.I.-9** (*jianzhen*), **S.I.-10** (*naoshu*), **S.I.-11** (*tianzong*), **S.I.-12** (*bingfeng*) ■■, **S.I.-13** (*quyuan*), **S.I.-14** (*jianwaishu*) 🟦■; elbow – **S.I.-8** (*xiaohai*); hand – **S.I.-4** (*wangu*), **S.I.-5** (*yanggu*); finger (numbness and pain) – **S.I.-3** (*houxi*) 🟦■; finger (stiffness) – **S.I.-3** (*houxi*) 🟦■, **S.I.-5** (*yanggu*)
- **Adjacent points (→ 8.2.1):** shoulder – **S.I.-9–S.I.-15**; finger – **S.I.-5** (*yanggu*)
- **Distal points (→ 8.2.1):** for the occiput – **S.I.-3** (*houxi*) 🟦■; for the eyes – **S.I.-6** (*yanglao*) 🟦■; for the cervical and thoracic spine – **S.I.-3** (*houxi*) 🟦■; for the thoracic spine – **S.I.-6** (*yanglao*) 🟦■; for the lumbar region – **S.I.-3** (*houxi*) 🟦■, **S.I.-6** (*yanglao*) 🟦■

Specific points according to the channel pathway (in numerical order)

- **S.I.-1** (*shaoze*): *jing*-well point (Metal)
- **S.I.-2** (*qiangu*): *ying*-spring point (Water)
- **S.I.-3** (*houxi*) 🟦■: *shu*-stream point (Wood), tonification point, opening point (→ 8.1.8) of the *du mai*, distal point for the occiput and the lumbar region (→ 8.2.1); local point for the fingers (→ 8.2.1); distal point for the cervical and thoracic spine (→ 8.2.1)
- **S.I.-4** (*wangu*): *yuan*-source point (→ 8.1.1); local point for the hand (→ 8.2.1)
- **S.I.-5** (*yanggu*): *jing*-river point (Fire), *ben* point (Five Phases); local point for the hand and fingers (stiffness) (→ 8.2.1); regional point for the fingers (→ 8.2.1)
- **S.I.-6** (*yanglao*) 🟦■: *xi*-cleft point (→ 8.1.3); distal point for the eyes, the thoracic and lumbar spine (→ 8.2.1)
- **S.I.-7** (*zhizheng*): *luo*-connecting point (→ 8.1.2)
- **S.I.-8** (*xiaohai*): *he*-sea point (Earth), sedation point; local point for the elbow (→ 8.2.1)
- **S.I.-9** *(jianzhen):* local point for the shoulder (often sensitive to pressure) (→ 8.2.1)
- **S.I.-9 – S.I.-15**: adjacent points for the shoulder (often sensitive to pressure) (→ 8.2.1)

---

* According to Deadman et al 1998.

Ch04.6-F10028.qxd 2/22/08 9:47 PM Page 221

- **S.I.-10** (*naoshu*): *jiaohui*-meeting point with the BL channel, the *yang wei mai, yang qiao mai* (→ 8.1.10); local point for the shoulder (often sensitive to pressure) (→ 8.2.1)
- **S.I.-11** (*tianzong*) 🟦⬛: local point for the shoulder (often sensitive to pressure) (→ 8.2.1)
- **S.I.-12** (*bingfeng*): *jiaohui*-meeting point with the L.I., T.B. and G.B. channels (→ 8.1.10); local point for the shoulder (often sensitive to pressure) (→ 8.2.1)
- **S.I.-13** (*quyuan*): local point for the shoulder (often sensitive to pressure) (→ 8.2.1)
- **S.I.-14** (*jianwaishu*) 🟦⬛: local point for the shoulder (often sensitive to pressure) (→ 8.2.1)
- **S.I.-16** (*tianchuang*): Window of Heaven point (→ 8.1.12)
- **S.I.-17** (*tianrong*) 🟦⬛: Window of Heaven point (→ 8.1.12); local point for the neck (→ 8.2.1)
- **S.I.-18** (*quanlao*) 🟦⬛: local point for the face and cheek (→ 8.2.1); *jiaohui*-meeting point with the T.B. channel (→ 8.1.10)
- **S.I.-19** (*tinggong*) 🟦⬛: *jiaohui*-meeting point with the T.B., G.B. channels (→ 8.1.10); local point for disorders of the ear and jaw (→ 8.2.1)

Lesser Marsh SHAOZE S.I.-1



Location

On the little finger, 0.1 cun from the ulnar corner of the nail.

How to find

This point is located at the junction of two tangents drawn along the lateral and proximal borders of the nail, approximately 0.1 cun from the actual corner of the nail. → **HE-9** is located at the radial corner of the nail.

Needling

0.1–0.2 cun vertically or obliquely in a proximal direction or prick to bleed with a needle, lancet or three-edged needle. Caution: Painful point.

Actions/Indications

- Expels Wind and Heat
- Opens the orifices
- Revives consciousness
- Opens the channel
- Benefits the breasts

Special features

Jing-well point, Metal point, entry point.


L.I.-1
T.B.-1
L.I.-1
Ex-UE-9
(*baxie*)
L.I.-2
L.I.-3
Ex-UE-8
T.B.-2
L.I.-2
Ex-UE-9
(*baxie*)
L.I.-4
T.B.-3
L.I.-3
Ex-UE-7
Ex-UE-7
L.I.4
L.I.-5
L.I.-5
T.B.-4
L.I.-6
T.B.-5



S.I.-2 *Front Valley* QIANGU

Location

On the ulnar aspect of the little finger, distal to the metacarpophalangeal joint, at the junction of the shaft and the base of the proximal phalanx.



How to find

On the ulnar aspect of the little finger, palpate along the border of the 'red and white' skin in the direction of the metacarpophalangeal joint, until you can clearly feel the junction between the shaft and the base. **S.I.-2** is located at the junction of the shaft and the base and slightly inferior (palmar) to the exterior curvature of the bone. → **L.I.-2** is located in a comparable position on the proximal phalanx of the index finger. In a comparable location on the foot are → **BL-66** (on the lateral aspect) and → **SP-2** (on the medial aspect).

Needling

0.2–0.5 cun obliquely in a proximal or distal direction and slightly towards the palm. Caution: Painful point.

Actions/Indications

- Drains Heat, expels Wind
- Disperses accumulations

Special features

Ying-spring point, Water point.


Proximal phalanx II
Metacarpal II
L.I.- 2




BL-66
BL-65
BL-64


L.I.-1
T.B.-1
L.I.-1
Ex-UE-9
(*baxie*)
L.I.-2
L.I.-3
Ex-UE-8
T.B.-2
L.I.-2
Ex-UE-9
(*baxie*)
L.I.-4
T.B.-3
L.I.-3
Ex-UE-7
Ex-UE-7
L.I.4
L.I.-5
L.I.-5
T.B.-4
L.I.-6
T.B.-5

Back Stream HOUXI S.I.-3









Location

On the ulnar border of the hand, in the depression proximal to the metacarpophalangeal joint, at the border of the ‘red and white’ skin.

How to find

Quick method: Slide from proximal (wrist) to distal (little finger) along the ulnar border of the hand, until the palpating finger comes to rest at the junction between the base and the head of the 5th metacarpal bone proximal to the metacarpophalangeal joint. Here, locate **S.I.-3. Or:** Locate, with the patient making a loose fist. Locate **S.I.-3** at the end of the most distal transverse crease (this often originates between the index and middle fingers and runs to the little finger). When making a fist, a small bulge forms at the end of the crease. There, locate **S.I.-3** in a palpable depression slightly proximal and dorsal to the bulge.
→ **L.I.-3** is located in a comparable position on the radial border of the hand. Located in a comparable position on the foot are → **SP-3** (on the medial aspect) and → **BL-65** (on the lateral aspect).

Needling

0.5–1 cun horizontally below the bone – that is, vertically to the skin towards the palm – or 0.2–0.3 cun obliquely in a distal direction. Caution: Painful point.

Actions/Indications

- Eliminates Wind and Heat from the *taiyang* (S.I., BL)
- Opens the channel and the *luo* vessels
- Clears Heat and benefits the orifices
- Regulates the *du mai*, calms the *shen*

Special features

Shu-stream point, Wood point, tonification point, opening (master) point of the *du mai*. Important distal point for pain, stiffness and contractures along the course of the channel and for disorders of the cervical spine.

S.I.-4 *Wrist Bone* WANGU

Location

On the ulnar border of the hand, between the 5th metacarpal bone and the carpal bones, on the border of the red and white skin.

How to find

On the ulnar aspect of the hand, palpate along the shaft of the 5th metacarpal bone in a proximal direction, until the finger glides over the curvature of the base and into the cleft between the metacarpal and carpal bones.

→ **S.I.-5** is located on the same line, proximal to the pisiform bone and at the level of the wrist crease.

Needling

Vertically 0.3–0.5 cun. Caution: Painful point.

Actions/Indications

- Clears pathogenic factors from the *taiyang* channel
- Clears Damp-Heat in the Small Intestine

Special features

Yuan-source point


Metacarpal V
S.I.-4
Pisiform
S.I.-5
Ulna


L.I.-1
T.B.-1
L.I.-1
Ex-UE-9
(*baxie*)
L.I.-2
L.I.-3
Ex-UE-8
T.B.-2
L.I.-2
Ex-UE-9
(*baxie*)
L.I.-4
T.B.-3
L.I.-3
Ex-UE-7
Ex-UE-7
L.I.4
L.I.-5
L.I.-5
T.B.-4
L.I.-6
T.B.-5

Yang Valley YANGGU S.I.-5


S.I.-4
S.I.-5
Metacarpal V
Pisiform
Wrist joint space
Ulna

Location

On the ulnar aspect of the wrist, at the level of the lateral joint space.

How to find

By moving the wrist in a relaxed way, the wrist joint space can be palpated on the ulnar side. **S.I.-5** is located directly distal to the styloid process of the ulna (→ 3.3.3), on a line running along the ulnar border of the hand and continuing to the wrist. Located on the same line and distal to the prominence of the pisiform bone is → **S.I.-4**.

Needling

Vertically 0.3–0.5 cun

Actions/Indications

- Clears Heat and reduces swellings

Special features

Jing-river point, Fire point, *ben* point (Five Phases point).


Ulna
Distal radioulnar joint
Styloid process of the ulna
Pisiform
Radius
Styloid process of the radius
Lunate

S.I.-6 *Support the Aged* YANGLAO

Location

In the depression radial and proximal to the styloid process of the ulna, which forms when the hand is turned from a pronated to a supinated position.

How to find

This point is best located with the elbow slightly flexed. Place the palpating finger on the distal portion of the styloid process of the ulna (→ 3.3.3). When turning the hand from a pronated to a supinated position (mnemonic: cut **br**ead and eat **soup**), the palpating finger will glide into a bony cleft at the proximal aspect of the styloid process (the tendon of the extensor carpi ulnari muscle runs along this groove). This cleft also becomes palpable when the patient rests the hand on the chest (half-supinated position). Locate **S.I.-6** in this bony groove.

Needling

0.3–0.8 cun vertically or slightly obliquely in a proximal direction towards → **P-6** or along the tendon towards the elbow joint.

Actions/Indications

- Opens the channel, alleviates pain, benefits the shoulder and arm, alleviates acute conditions
- Benefits the eyes

Special features

Xi-cleft point. Important distal point for pain and limited range of motion of the occiput and shoulder (for example, acute torticollis) and the lumbar region (for example, acute sciatica). For acute and painful impairment of motion, use strong reducing needling technique while the patient gently moves the affected region.


Half-
supi
nation
S.I.-6
Pronation
(initial position)
S.I.-6
Styloid
process
of the ulna


Initial position:
pronation
Proximal part of the styloid
process of the ulna


Half-
supination
Palpating finger
slides into the cleft
of the tendon

Branch of the Upright ZHIZHENG **S.I.-7**


S.I.-5
Wrist joint space
Ulna
Medial epicondyle of the humerus
5 cun
S.I.-7
7 cun
Olecranon
S.I.-8

Location

5 cun proximal to the wrist joint, on the line connecting the ulnar wrist joint space with the ulnar sulcus of the elbow (→ **S.I.-5** to → **S.I.-8**) or 1 cun distal to the midpoint of this line.

How to find

Find the midpoint of the distance between → **S.I.-5** and → **S.I.-8** by using the spreading hands technique (→ 2.3.3): Place the little fingers on → **S.I.-5** and → **S.I.-8** respectively and span the hands evenly, with the thumbs joining at the midpoint. From the midpoint, measure 1 cun in a distal direction. The point lies between the palpable border of the ulna and the more anteriorly located flexor carpi ulnaris muscle.

Needling

Vertically 0.5–1 cun

Actions/Indications

- Opens the channel
- Releases the Exterior
- Calms the *shen*

Special features

Luo-connecting point


T.B.-10
L.I.-11
S.I.-8
L.I.-10
1
2
3
4
5
6
7
8
9
10
11
12
cun
T.B.-9
L.I.-7
S.I.-7
L.I.-6
T.B.-6
T.B.-5
S.I.-6
T.B.-4
L.I.-5


5th metacarpal
S.I.-4
Pisiform
S.I.-5
Wrist joint space


Brachialis
Triceps brachii, lateral head
Brachioradialis
Triceps brachii, medial head
Extensor carpi radialis longus
Tendon of the triceps brachii
T.B.-10
L.I.-11
Olecranon
Lateral epicondyle
Flexor carpi ulnaris
Extensor digitorum
Extensor carpi ulnaris


Olecranon
Medial epicondyle of the humerus
S.I.-8

S.I.-8 *Small Sea* XIAOHAI

Location

With the elbow flexed, in the depression between the olecranon process of the ulna and the medial epicondyle of the humerus.

How to find

S.I.-8 is located on a line connecting the tip of the olecranon and the tip of the medial epicondyle, at the deepest point of the groove between those two bony protrusions.

Needling

0.3–0.5 cun vertically or obliquely with or against the flow of the channel. Caution: The ulnar nerve is located in this groove.

Actions/Indications

- Opens the channel

Special features

He-sea point, Earth point, sedation point.


Olecranon
S.I.-8
Medial epicondyle of the humerus


Lateral epicondyle of the humerus
T.B.-10
S.I.-8
Medial epicondyle of the humerus
Olecranon


T.B.-10
L.I.-11
S.I.-8
L.I.-10
1
2
3
4
5
6
7
8
9
10
11
12
cun
S.I.-9
L.I.-7
S.I.-7
L.I.-6
T.B.-6
T.B.-5
S.I.-6
T.B.-4
L.I.-5


Brachialis
Brachioradialis
Extensor carpi radialis longus
L.I.-11
Lateral epicondyle
Triceps brachii, lateral head
Triceps brachii, medial head
Tendon of the triceps brachii
T.B.-10
Olecranon
Flexor carpi ulnaris

True Shoulder JIANZHEN S.I.-9


Deltoid
S.I.-10
Border of the deltoid
ca. 1 cun
S.I.-9
Anterior end of the axillary fold

Location

With the arm adducted, 1 cun superior to the posterior axillary fold, on the lower border of the deltoid muscle.

How to find

With the patient sitting upright, palpate upward from the end of the posterior axillary fold, until you can feel the lower border of the deltoid muscle. If in doubt, ask the patient to flex their muscle. **S.I.-9** is located on its lower border.

Needling

Vertically 1–1.5 cun

Actions/Indications

- Opens the channel, expels Wind and benefits the shoulder

Special features

S.I.-9 corresponds to a trigger point that is often sensitive to pressure.


Acromion
Trapezius
T.B.-14
Deltoid
Scapular spine
S.I.-10
S.I.-9
Triceps brachii, lateral head
Teres major
T.B.-13
Triceps brachii, long head
Biceps brachii
Triceps brachii, medial head


S.I.-15
S.I.-14
G.B.-21
S.I.-12
T.B.-15
14
1
11
13
2
3
T.B.-14
S.I.-10
42
13
12
4
S.I.-13
5
S.I.-11
T.B.-13
S.I.-9
44
15
11
6
7
1
2
L.I.-14

S.I.-10 *Upper Arm* **Shu** NAOSHU

Location

With the arm adducted, on an imaginary line extending in a superior direction from the posterior axillary fold, on the lower border of the scapular spine.

How to find

With the patient sitting upright, palpate from the posterior axillary fold upward, past the lower border of the deltoid muscle (→ **S.I.-9**) to the bony resistance of the scapular spine and acromion, which here form a curve that opens towards the inferior. **S.I.-10** is located below its bony border.

Needling

Vertically 0.5–1.5 cun

Actions/Indications

- Opens the channel and relaxes the sinews

Special features

Meeting point of the *yang wei mai* and the *yang qiao mai*. S.I.10 corresponds to a trigger point that is often sensitive to pressure. It also corresponds to the posterior access for puncturing the shoulder joint.


Deltoid
S.I.-10
Border of the deltoid
ca. 1 cun
S.I.-9
Anterior end of the axillary fold


Trapezius
Acromion
T.B.-14
Deltoid
Scapular spine
S.I.-10
S.I.-9
Triceps brachii, lateral head
Teres major
T.B.-13
Triceps brachii, long head
Biceps brachii
Triceps brachii, medial head


S.I.-15
S.I.-14
G.B.-21
S.I.-12
T.B.-15
14
1
11
13
2
S.I.-10
T.B.-14
3
42
13
12
4
S.I.-13
5
S.I.-11
T.B.-13
S.I.-9
44
15
11
6
7
1
2
L.I.-14
3

Heavenly Gathering TIANZONG S.I.-11


Scapular spine
Spinous process C7
1/2
1/2
Spinous process T4
Spinous process T5
S.I.-11
1/3
2/3
Infraspinatus
Inferior angle of the scapula

Location

On the scapula, in a depression on the infraspinatus muscle, one third of the distance from the midpoint of the scapular spine and the inferior angle of the scapula.

How to find

Patient's position: Prone position or better seated with relaxed shoulders. Draw an imaginary line from the midpoint of the scapular spine (→ 3.3.1) to the inferior angle of the scapula. **S.I.-11** is located at the junction of the upper and middle third of this line, in a depression on the infraspinatus muscle, which is often sensitive to pressure. In a seated or standing position with the arms hanging down, it will generally be level with the spinous process of the 4th thoracic vertebra or the body of the 5th thoracic vertebra.

→ **S.I.-12** is located directly above **S.I.-11**, in the centre of the supraspinous fossa.

Needling

0.5–1.5 cun vertically or obliquely into the muscle tissue

Actions/Indications

- Opens the channel, alleviates pain, moves Qi locally, unbinds the chest and lateral costal region
- Benefits the breasts

Special features

S.I.-11 is often a trigger point on the infraspinatus muscle.


S.I.-12
S.I.-10
T.B.-14
T.B.-13
S.I.-9
1
2
L.I-14
3
4
T.B.-12
5
6
L.I.-13
7
8
T.B.-10
L.I.-11
1
S.I.-8
L.I.-10
2
3
4
5
6
T.B.-9
7
L.I.-7
8


Spinous process C7
S.I.-12 (Supraspinatus)
Spinous process T4
S.I.-11
1/3

S.I.-12 *Grasping the Wind* BINGFENG

Location

Directly above → **S.I.-11**, in the centre of the supraspinous fossa.

How to find

Patient's position: Prone position or better seated with relaxed shoulders. First, locate → **S.I.-11** (one third of the distance between the midpoint of the scapular spine and the inferior angle of the scapula). **S.I.-12** is located directly above → **S.I.-11** in the centre of the supraspinous fossa.

Needling

0.5–1 cun vertically or obliquely into the supraspinatus muscle in the direction of the shoulder. Caution: Pneumothorax.

Actions/Indications

- Eliminates Wind, benefits the shoulder and scapula, opens the channel and the *luo* vessels

Special features

Meeting point with the Gall Bladder, Triple Burner and Large Intestine channels. **S.I.-12** is often a trigger point in the supraspinatus muscle.


Supraspinous fossa
S.I.-12 (Supraspinatus)
Spinous process C7
Spinous process T5
S.I.-11
1/3
2/3


S.I.-15
S.I.-14
G.B.-21
S.I.-12
T.B.-15
14
1
11
13
2
3
S.I.-10
T.B.-14
42
13
12
4
S.I.-13
5
S.I.-11
T.B.-13
S.I.-9
44
15
11
6
7
1
2
3
L.I.-14


Spinous process T4
Spinous process T5
S.I.-11
1/3

Crooked Wall QUYUAN S.I.-13


Spinous process C7
Spinous process C1
Spinous process T4
S.I.-13
S.I.-11

Location

At the medial end of the supraspinous fossa.

How to find

At its medial end, the scapular spine fans out in a deltoid shape, curving round in a superior direction. When palpating, this feels like a ‘crooked wall’, hence its name. **S.I.-13** is located on the scapula, in the slightly concave bend, at the medial origin of the supraspinatus muscle.

Needling

0.5–1 cun vertically or obliquely in a lateral direction. No danger of puncturing the pleura if located correctly.

Actions/Indications

- Opens the channel


Trapezius (superior fibres)
G.B.-21
S.I.-13
S.I.-12
L.I.-16
T.B.-15
S.I.-10
Trapezius (inferior fibres)


Trapezius
Scapular spine
Deltoid
Triceps brachii, lateral head
Teres major
Triceps brachii, long head
Biceps brachii

S.I.-14 *Outer Shoulder Shu* JIANWAISHU

Location

3 cun lateral to the lower border of the spinous process of the 1st thoracic vertebra, at the insertion of the levator scapulae muscle.

How to find

The levator scapulae muscle originates on the upper aspect of the medial border and the superior angle of the scapula. In this area, it is often myogelotic and therefore well defined and often sensitive to pressure (trigger point). **S.I.-14** is located just superior to the actual muscle insertion; in contrast to → **S.I.-13**, it is not located on the scapula.

Located on approximately the same level are → **Du-13** (below the spinous process of the 1st thoracic vertebra) and → **BL-11** (1.5 cun distal to the posterior midline).

Needling

0.5–1 cun vertically or obliquely in a medial direction. Caution: Pneumothorax.

Actions/Indications

- Opens the channel
- Expels Wind-Cold

Special features

Trigger point on the levator scapulae muscle


Levator scapulae
Spinous process C17
Spinous process T5
S.I.-14
S.I.-13
Du 13
BL 11
Spinous process T4


S.I.-15
14
1
S.I.-12
11
13
2
3
42
13
12
4
5
44
15
11
6
7
46
17
9
8


Spinous process C7
Spinous process T1
S.I.-13


BL 11
Medial border of the scapula
Base of the scapular spine
Spinous process C7
Spinous process T1

***Middle Shoulder* Shu JIANZHONGSHU S.I.-15**


Spinous process C7
Du 14
S.I.-15
2 cun

Location

2 cun lateral to the lower border of the spinous process of the 7th thoracic vertebra.

How to find

For locating the 7th cervical vertebra, see → 3.4.
Located on the same level is → **Du-14** below the spinous process of the 7th cervical vertebra. Locate **S.I.-15** by measuring 2 cun in a lateral direction.

Needling

0.5–1 cun vertically or obliquely in a medial direction. Caution: Pneumothorax.

Actions/Indications

- Opens the channel

Special features

Trigger point on the levator scapulae muscle, effective point for disorders of the cervicodorsal area.


Spinous process C7
Du-14
Base of the
scapular spine


S.I.-15
S.I.-14
G.B.-21
S.I.-12
T.B.-15
14
11
13
S.I.-10
T.B.-14
42
13
12
S.I.-13
S.I.-11
T.B.-13
1
2
S.I.-9
44
15
11
L.I.-14
3
4


Extension and
flexion of the head
Two fingers on the spinous
processes of C6 and 7
G.B.-21
S.I.-15
Du-14

S.I.-16 *Heavenly Window* TIANCHUANG

Location

Approximately 3.5 cun lateral to the anterior midline, at the level of the laryngeal prominence, on the posterior border of the sternocleidomastoid muscle.

How to find

From the laryngeal prominence (→ 3.2), draw a line to the posterior border of the sternocleidomastoid muscle. **S.I.-16** is located directly at its posterior border, which can be made more clearly visible and palpable by rotating the patient's head in the opposite direction.

Located on the same level are → **ST-9** (on the anterior border of the sternocleidomastoid muscle) and → **L.I.-18** (between the two heads of the SCM muscle).

Needling

Vertically 0.5–1 cun. If necessary, rotate the patient's head back to its normal position before needle insertion.

Actions/Indications

- Expels Wind and Heat, benefits the throat, ears and voice
- Opens the channel

Special features

Window of Heaven point


ST-9
L.I.-18
S.I.-16
Laryngeal prominence
Clavicular head
Sternal head
Sternocleidomastoid


Hyoid bone
Superior thyroid notch
Thyroid cartilage
Laryngeal prominence
**
Tracheal cartilage


Ex-HN (*anmian*)
G.B.-12
ST-9
Sternocleidomastoid
L.I.-18
S.I.-16
L.I.-17
Laryngeal prominence
ST-11
Sternal head
Clavicular head

Heavenly Appearance TIANRONG S.I.-17


Mandibular angle
S.I.-17
Sternocleidomastoid


S.I.-18
Ma 7
G.B.-2
G.B.-20
T.B.-17
G.B.-12
Ex-HN
(*anmian*)
ST-5
ST-6
S.I.-17
T.B.-16
Ren 23
L.I.-18
ST-9
S.I-16
L.I.-17
ST-12
ST-11


Masseter
Zygoma
Mandi-
bular
angle
S.I.-18
T.B.-16
ST-5
Sternocleidomastoid
ST-6
S.I.-17

Location

Posterior to the mandibular angle, on the anterior border of the sternocleidomastoid muscle.

How to find

By rotating the patient's head in the opposite direction, the border of the sternocleidomastoid muscle becomes more pronounced. **S.I.-17** is located halfway between the angle of the mandible and the anterior border of the sternocleidomastoid muscle.

Needling

Vertically 0.5–1 cun. Caution: Internal carotid artery, internal and external jugular veins.

Actions/Indications

- Expels Wind, opens the channel, disperses accumulations, benefits the ears and throat

Special features

Window of Heaven point

S.I.-18 *Cheekbone Crevice* QUANLIAO

Location

At the intersection of a vertical line through the outer canthus of the eye with the lower border of the zygomatic bone, on the anterior border of the masseter muscle.

How to find

Draw an imaginary vertical line from the outer canthus of the eye to the lower border of the zygomatic bone. **S.I.-18** is located in a depression on the anterior border of the masseter muscle, approximately on the level of the lateral border of the ala nasi (→ **L.I.-20**). By making chewing movements, the anterior border of the masseter muscle becomes easily palpable.

Needling

0.3–0.5 cun vertically or 1–1.5 cun transversely (subcutaneously) in the direction of → **ST-4,** → **ST-7** and → **L.I.-20**. According to some texts, moxibustion is contraindicated.

Actions/Indications

- Eliminates Wind, alleviates pain, clears Heat, reduces swellings

Special features

Meeting point with the Triple Burner channel. Important local point for disorders of the face (caused by internal or external Wind).


Lateral margin
of the orbit
Lower border
of the zygomatic
arch
S.I.-18
Anterior border
of the masseter


Orbit
S.I.-18
Upper jaw
ST-2
Anterior bony aperture of the nose
Zygomatic
bone
Infraorbital
foramen


G.B.-15
BL-5
Du-23
ST-8
G.B.-13
BL-4
Du-24
BL 3
G.B.-14
Ex-HN 4
T.B.-23
BL-2
BL-1
Ex-HN 3
G.B.-1
ST-1
Ex-HN-7
ST-2
Ex-HN 8
G.B.-2
ST-7
L.I.-20
S.I.-18
L.I.-19
Du-26
ST-4
ST-5
Ex-HN Ren 24



Palace of Hearing TINGGONG S.I.-19


Condyloid process
of the mandible
Styloid
process
Needle insertion
with the mouth
slightly open
T.B.-21
S.I.-19
Tragus
G.B.-2
Mouth closed*
Mouth open*


Du-20
G.B.-18
G.B.-13
ST 8
G.B.-14
G.B.-8
T.B.-20
T.B.-23
Ex-HN 5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
G.B.-2
S.I.-18
Ma
G.B.-20
T.B.-17
G.B.-12
Ex-HN
(anmian)


Helix
Helix root
Antihelix
Supratragic
notch
Tragus
Antitragus
Lobe
Intertragic
notch

Location

Anterior to the ear, with the mouth open at the level of the middle of the tragus, in a depression between the tragus and condyloid process of the mandible.

How to find

Locate and needle this point with the mouth open. This allows the condyloid process of the mandible to slide anteriorly and reveals the depression. Locate the vertical sulcus at the junction between the ear and the cheek (this is not always very pronounced). Then locate **S.I.-19** on the level of the tragus on the sulcus. If you cannot clearly define the sulcus (it becomes more pronounced with increasing age), an (ear) point locator can be used to locate the point (the patient should have their mouth open in order to reveal the depression).

S.I.-19 is the centre point of three points located anteriorly to the ear (→ **T.B.-21** is located proximal and → **G.B.-2** is located distal to **S.I.-19**).

Needling

0.5–1 cun vertically or slightly obliquely in an inferior direction. Needle with the mouth open (to avoid intra-articular needling). Caution: This point is located close to the superficial temporal artery and the auriculotemporal nerve (as are → **T.B.-21** and → **G.B.-2**).

Actions/Indications

- Benefits the ears
- Calms the *shen*

Special features

Meeting point with the Gall Bladder and Triple Burner channels, exit point. Important local point for disorders of the ears. For temporomandibular joint dysfunction and pain, rather use → **G.B.-2** as a local point.


Helix
Supratragic notch
Tragus
Intertragic notch
T.B.-22
T.B.-21
S.I.-19
G.B.-2
SJ 17
Transverse process
of the atlas
Mastoid process
Ex-HN
(anmian)
Ex-HN 14
(yiming)
G.B.-12
Sternocleidomastoid

---

* According to Deadman et al 1998.

4.7 The Bladder Channel System – Foot *taiyang* (*zu tai yang jing luo*)

4.7.1 The Bladder Primary Channel (*zu tai yang jing*)


Meeting points
G.B.-7, G.B.-8,
G.B.-9, G.B.-10,
G.B.-11, G.B.-12
BL-7
Du-20
G.B.-15
(S.I.-18)
Du-24
BL-1
10
Du-17
Du-14
Du-13
41
12
46
23
31
G.B.-30
30
36
39
40
57
58


1,5 Cun
BL-5
Du-23
BL-4
BL-3
BL-2
BL-1


Du-17
BL-8
Du-20
BL-7
BL-6
BL-5
Du-23
BL-4
BL-3

Pathway

The **external** pathway of the Bladder primary channel begins at the inner canthus of the eye at → **BL-1** (*jingming*). This point is reached by a branch that separates from the Small Intestine primary channel at → **S.I.-18** (*quanliao*) (hand–foot pairing of the second great circuit, Yang axes: *taiyang*).

The **external** pathway ascends the forehead, there intersects with → **Du-24** (*shenting*) and → **G.B.-15** (*toulinqi*), continues to the vertex and there connects with the *du mai* at → **Du-20** (*baihui*).

At → **Du-20 two branches** separate from the primary channel:

- ➡ **one branch** travels to the temporal region and intersects the Gall Bladder primary channel at **G.B.-8** (*shuaigu*), **G.B.-7** (*qubin*), **G.B.-9** (*tianchong*), **G.B.-10** (*fubai*), **G.B.-11** (*touqiaoyin*) and **G.B.-12** (*wangu*)
- ➡ the **other branch** penetrates deeper into the brain and re-emerges at → **Du-17** (*naohu*) or, according to some authors, at **BL-8** (*luoque*).

From → **Du-20**, the **external pathway** runs to **BL-8** (*luoque*) and **BL-9** (*yuzhen*), passes → **Du-17** (*naohu*) and continues to **BL-10** (*tianzhu*) in the occipital region. Here, the **external pathway** of the channel separates into **two branches**:

- ➡ the **medial** branch runs to → **Du-14** (*dazhui*) below the spinal process of C7 where it meets the other Yang primary channels, then continues to → **Du-13** (*taodao*). From T1 it runs parallel to the posterior midline, 1.5 cun lateral to it.


1.5 cun
1.5
1.5
1.5
BL-3
BL-6
BL-7
BL-8
BL-5
BL-4
1.3 cun
BL-9
2.5 cun
BL-10


BL-41
BL-43
BL-44
BL-46
3 cun
3 cun
BL-48
BL-50
BL-52
BL-53
BL-54
1
2
3
4
5
6
7
8
9
10
11
12
1
2
3
4
5


Occiput
G.B.-20
Du-16
G.B.-20
Atlas
C1
Sternocleido-
mastoid
BL-10
Du-15
BL-10
Axis
Splenius
capitis
1st palpable
spinous
process
Trapezius,
superior
fibres
Du-14


Scapular spine
1
2
3
4
5
6
7
BL-11
BL-12
BL-15
Base of the scapular spine at the medial border of the scapula → level with the spinous process of T3 or T4
BL-17
Inferior angle of the scapula → level with the spinous process of T7 or T8
1.5
1.5
cun
10
11
12
1
2
3
4
5
BL-18
BL-19
BL-20
BL-21
BL-22
BL-23
Upper border of the iliac crest → L4
BL-25
BL-26
BL-27
BL-28
BL-30
31
32
33
35
BL-36


BL-36
6
BL-37
7
BL-38
1
Popliteal
crease
BL-40
BL-39
2
BL-55
1/2
1/2
BL-56
1/2
BL-57
BL-58
1
1/2
BL-59
3
BL-60
1.5
cun
BL-61


Long head of the
biceps femoris
BL-38
BL-40
Popliteal
crease
BL-39
BL-55
1
2
3
4
BL-56
5
Gastro-
cnemius
6
7
BL-57
8
BL-58
9
10
11
12
BL-59
13
14
15
BL-60
16
Lateral
malleolus


BL-60
BL-62
1.5 cun
BL-61
BL-63
BL-67
BL-66
BL-65
BL-64

At the level of L2, it **enters** the abdomen and reaches its paired *zang*-Organ, the Kidney (*shen*) and its pertaining *fu*-Organ, the Bladder (*pangguang*). The **external** branch runs through the gluteal region and the thigh to the popliteal fossa (**BL-40**), where it re-unites with the lateral external branch.

- the **lateral branch** runs from **BL-10** (*tianzhu*) to **BL-41** (*fufen*) at the level of T2, from where it descends down the back, 3 cun lateral to the midline to the level of the fourth sacral foramen. From there it traverses the gluteal region to → **G.B.-30** (*huantiao*), continues along the posterolateral aspect of the thigh and meets the medial external branch at the popliteal fossa.

From the popliteal fossa (**BL-40**) the channel descends along the posterolateral aspect of the foreleg to the foot

- passes the lateral malleolus
- travels along the lateral border of the foot to the lateral corner of the little toenail to **BL-67** (*zhiyin*). From here, a branch travels to → **KID-1** (*yongquan*) located on the Interiorly–Exteriorly paired Kidney primary channel (foot Yin–Yang pairing of the second great circuit).

Clinical importance (→ 1.2)

Exterior (*biao*) signs and symptoms: Chills and fever, headaches, occipital stiffness, pain in the lumbar region, obstruction of the nasal passages, eye pain with tearing, pain along the posterior aspect of the hip, knee and foreleg, foot pain

Interior (*li*) or *zangfu*-Organ signs and symptoms: Pain and tension in the lower abdomen, retention of urine, enuresis, psycho-emotional disorders, opisthotonus

Connections and meeting points of the Bladder primary channel (→ 1.2)

Connections with other channels

Kidney primary channel (*zu shao yin jing*)

Connection: Foot Yin–Yang pairing of the second great circuit
Location: BL-67 → KID-1 (on the foot).
Circulation: Circadian (according to the Organ clock)
Importance: Exterior–Interior relationship

Small Intestine primary channel (*shou tai yang jing*)

Connection: Paired according to the six channel theory (hand–foot pairing): *tai yang* (Yang axes of the second great circuit)
Location: S.I.-18 → BL-1 (on the head).
Circulation: Circadian (according to the Organ clock)
Importance: Above–below relationship

Connections with other *zangfu*-Organ systems

Kidney (*shen*), Bladder (*pangguang*)

4.7.2 The Bladder Divergent Channel (*zu tai yang jing bie*)



Pathway

The Bladder divergent channel separates from the Bladder primary channel in the popliteal fossa at **BL-40** (*weizhong*)

- ascends to the centre of the gluteal crease at **BL-36** (*chengfu*)
- ascends further and penetrates the anus, continues to the Bladder (*pangguang*), its pertaining *fu*-Organ, and the Kidney (*shen*), its paired *zang*-Organ
- rises along the spine and spreads in the Heart (*xin*)

➡ from here it ascends to the occiput, where it unites at **BL-10** (*tianzhu*) with the Kidney divergent channel and the Bladder primary channel to form one of the six *he*-confluences (here: KID/BL as first confluence → 1.3)

Clinical importance

- Strengthens the relationship between the Bladder and the Kidney (*zangfu*-Organs). Points on the Bladder primary channel can therefore be used for disorders of the Kidney, and vice versa points on the Kidney primary channel can treat disorders of the Bladder.
- Supports the connection between the Bladder primary channel and the Heart
- Supports the connection between the Bladder primary channel and the anus
- Creates a connection between the popliteal region (**BL-40**) and the sacral region (**BL-32**, **BL-31**) as well as with the occipital region (**BL-10**).

4.7.3 The Bladder Sinew Channel (*zu tai yang jing jin*)



Pathway

The Bladder sinew channel begins on the lateral aspect of the little toe and travels along the lateral border of the foot to the lateral malleolus, where it binds (*jie*).

At the lateral malleolus **three branches** separate from the sinew channel:

➡ **one branch** runs to the calcaneus where it binds (*jie*) and disperses over the heel

➡ **a further branch** ascends the lateral aspect of the lower leg and binds (*jie*) at the head of the fibula, where it also meets the Gall Bladder and Stmach sinew channels at → **G.B.-34** (*yanglingquan*)

➡ **the main branch** travels to the Achilles tendon, binds (*jie*) in the area of the two heads of the gastrocnemius muscle, ascends the posterior aspect of the leg along the gastrocnemius and soleus muscles and binds (*jie*) on either side of the popliteal crease, ascends the posterior aspect of the thigh and binds (*jie*) at the centre of the gluteal crease, ascends as a broad band along the spine and binds (*jie*) at **BL-10** (*tianzhu*).

Two branches separate from the main branch in the thoracic region at the level of the axilla:

- ➡ **one branch** ascends to the shoulder and reaches ➞ **L.I.-15** (*jianyu*)
- ➡ **the other branch** penetrates the axilla, ascends the thorax and runs to the supraclavicular fossa, where again **two sub-branches** separate:
  - **one sub-branch** ascends to the mastoid process to ➞ **G.B.-12** (*wangu*)
  - **the other sub-branch** crosses the cheek to ➞ **S.I.-18** (*quanliao*) where it meets with the other foot Yang sinew channels

The **main branch** divides at **BL-10** (*tianzhu*) into **two branches:**

- ➡ **one branch** penetrates deeper to the root of the tongue
- ➡ **the other branch** crosses the head lateral to the midline, reaches the inner canthus of the eye and separates into **two branches:**
  - **one branch** binds (*jie*) lateral to the nose and descends the cheek
  - **the other branch** crosses the upper eyelid and connects with the Stomach sinew channel, together forming a network around the eye. It then penetrates deeper into the upper orbital region and ends at the roof of the mouth.

Clinical importance

Pathology: Muscular cramping in the region of the little toe. Tension and pain in the heel. Stiffness and limited range of motion of the joints. Tension and stiffness in the back and along the spine, and difficulty when bending forward. Inability to lift the arms above the shoulder region. Stiffness or distending pain in the axillary region. Pain and tense musculature in the supraclavicular fossa. Limited range of motion of the cervical spine.

Indication: Mainly with *bi*-syndromes (painful obstruction syndrome) along the Bladder channel. The area covered by the Bladder sinew channel is larger than that covered by the Bladder primary channel. This explains why Bladder primary channel points can also be used for disorders of the scapula and the shoulder region as well as for disorders of the lower eyelid and the nasal region.

4.7.4 The Bladder *luo*-Connecting Vessel System (*zu tai yang luo mai*)



Pathway

The Bladder *luo*-connecting channel separates from the Bladder primary channel at **BL-58** (*feiyang*) (➞ 8.1.2). It forms a three-dimensional reticular network, dividing into multiple branches and sub-branches (*sun luo*, *fu luo*, *xue luo* ➞ 1.5) within the surrounding tissue.

- Horizontal divisions run to the Interiorly–Exteriorly paired Kidney primary channel; according to some schools of thought (for example Nguyen Van Nghi ➞ Appendix) they travel as a **transverse** BL *luo*-connecting vessel to the *yuan*-source point ➞ **KID-3** (*taixi*).

- Solinas et al. (1998, variant → fig.) describe a **longitudinal** division following the pathway of the Bladder primary channel, reaching the head and penetrating the nose. While this division is not mentioned in the classics, according to Solinas et al it becomes evident based on the classic descriptions of the pathologies of the *luo*-connecting vessels.

Clinical importance (→ 8.1.2)

Pathology

- **Excess (*shi*):** Obstruction of the nasal passages, clear watery nasal discharge, headaches, back pain
- **Deficiency (*xu*):** Nosebleeds, chronic clear nasal discharge, sinusitis

4.7.5 Cutaneous Region (*tai yang pi bu*)

See description and figures → 1.6.

4.7.6 Points of the Bladder Primary Channel (Overview)

Specific points according to their function

- ***Yuan*-source point (→ 8.1.1): BL-64** (*jinggu*)
- ***Luo*-connecting point (→ 8.1.2): BL-58** (*feiyang*)
- ***Xi*-cleft point (→ 8.1.3): BL-63** (*jinmen*)
- ***Xi*-cleft point of the *yang qiao mai*: BL-59** (*fuyang*)
- **Associated Back-*shu* point (→ 8.1.4): BL-28** (*pangguangshu*) 🟦🟦
  - Back-*shu* point of the Lung: **BL-13** (*feishu*) 🟦🟦
  - Back-*shu* point of the Pericardium: **BL-14** (*jueyinshu*)
  - Back-*shu* point of the Heart: **BL-15** (*xinshu*) 🟦🟦
  - Back-*shu* point of the *du mai*: **BL-16** (*dushu*)
  - Back-*shu* point of the diaphragm: **BL-17** (*geshu*) 🟦🟦
  - Back-*shu* point of the Liver: **BL-18** (*ganshu*) 🟦🟦
  - Back-*shu* point of the Gall Bladder: **BL-19** (*danshu*) 🟦■
  - Back-*shu* point of the Spleen: **BL-20** (*pishu*) 🟦🟦
  - Back-*shu* point of the Stomach: **BL-21** (*weishu*) 🟦🟦
  - Back-*shu* point of the Triple Burner: **BL-22** (*sanjiaoshu*) 🟦■
  - Back-*shu* point of the Kidneys: **BL-23** (*shenshu*) 🟦🟦
  - Back-*shu* point of the Large Intestine: **BL-25** (*dachangshu*) 🟦■
  - Back-*shu* point of the Small Intestine: **BL-27** (*xiaochangshu*)
  - Back-*shu* point of the Bladder: **BL-28** (*pangguangshu*) 🟦🟦
- **Associated Front-*mu* point (→ 8.1.5): Ren-3** (*zhongji*) 🟦🟦
- **Five *shu*-transporting points (→ 8.1.6):**
  jing-well point (Metal), tonification point: **BL-67** (*zhiyin*) 🟦■
  ying-spring point (Water), *ben* point (Five Phases): **BL-66** (*zutonggu*)
  shu-stream point (Wood), sedation point: **BL-65** (*shugu*)
  jing-river point (Fire): **BL-60** (*kunlun*) 🟦🟦
  he-sea point (Earth): **BL-40** (*weizhong*) 🟦🟦
- ***Hui*-meeting point (→ 8.1.7):**
  - of the Blood: **BL-17** (*geshu*) 🟦🟦
  - of the Bones: **BL-11** (*dazhu*) 🟦■
- **Opening point (→ 8.1.8) of the *yang qiao mai*: BL-62** (*shenmai*) 🟦🟦
- **Lower *he*-sea points (→ 8.1.9):**
  of the Triple Burner: **BL-39** (*weiyang*) 🟦■
  of the Bladder: **BL-40** (*weizhong*) 🟦🟦
- ***Jiaohui*-meeting points (→ 8.1.10):**
  - with the ST, T.B.* channels, the *yin qiao mai*, *yang qiao mai*, S.I., G.B.* channels, *du mai*: **BL-1** (*jingming*) 🟦■
  - with the S.I. channel, (T.B., G.B. channels, *du mai**): **BL-11** (*dazhu*) 🟦■
  - with the *du mai*: **BL-12** (*fengmen*) 🟦■
  - with the *du mai**: **BL-23** (*shenshu*) 🟦🟦
  - with the G.B. channel: **BL-31–BL-34** 🟦■
  - with the S.I. channel: **BL-41** (*fufen*)
  - with the *yang qiao mai*: (**BL-59** (*fuyang*)*), **BL-61** (*pucan*), **BL-62*** (*shenmai*) 🟦🟦
  - with the *yang wei mai*: **BL-63** (*jinmen*)
  - of other channels with the Bladder channel: **Du-24, G.B.-15, Du-20, (G.B.-6*), G.B.-7, G.B.-8, G.B.-9, G.B.-10, G.B.-11, G.B.-12, Du-17, Du-16*, Du-14, Du-13, G.B.-30**
- **Gao Wu command point (→ 8.1.11) for the Back and lumbar region: BL-40** (*weizhong*) 🟦🟦
- **Window of Heaven point (→ 8.1.12): BL-10** (*tianzhu*) 🟦🟦
- **Points of the Four Seas (→ 8.1.13):**
  - Sea of Blood point: **BL-11** (*dazhu*) 🟦■
- **Ma Dan Yang Heavenly Star points (→ 8.1.14): BL-40** (*weizhong*) 🟦🟦, **BL-57** (*chengshan*) 🟦■, **BL-60** (*kunlun*) 🟦🟦
- **Sun Si Miao Ghost point (→ 8.1.15): BL-62** (*shenmai*) 🟦🟦
- **Other functional points:**
  - *xi*-cleft point of the *yang qiao mai*: **BL-59** (*fuyang*)

Points according to region

- **Local points (→ 8.2.1):** occiput – **BL-10** (*tianzhu*) 🟦🟦; eyes – **BL-1** (*jingming*) 🟦■; Stomach/Spleen – **BL-20** (*pishu*) 🟦🟦, **BL-21** (*weishu*) 🟦🟦; Kidney – **BL-23** (*shenshu*) 🟦🟦, **BL-62** (*shenmai*) 🟦🟦; rectum – **BL-35** (*huiyang*); cervical spine – **BL-10** (*tianzhu*) 🟦🟦; thoracic spine – **BL-17** – **BL-23**; lumbar spine – **BL-23** – **BL-26**, **BL-52** (*zhishi*); iliosacral region – **BL-27** (*xiaochangshu*), **BL-28** (*pangguangshu*); hip – **BL-49** (*yishe*), **BL-50** (*weicang*), **BL-54** (*zhibian*); knee – **BL-40** (*weizhong*) 🟦🟦; foot – **BL-60** (*kunlun*) 🟦🟦, **BL-62** (*shenmai*) 🟦🟦
- **Adjacent points (→ 8.2.1):** eyes – **BL-2** (*zanzhu*) 🟦■; nose – **BL-7** (*tongtian*); Lung – **BL-13** (*feishu*) 🟦🟦, **BL-43** (*gaohuang*); Heart – **BL-14** (*jueyinshu*), **BL-15** (*xinshu*) 🟦🟦; Liver – **BL-18** (*ganshu*) 🟦🟦, **BL-20** (*pishu*) 🟦🟦; Gall Bladder – **BL-19** (*danshu*) 🟦■; Large Intestine – **BL-25** (*dachangshu*) 🟦🟦; Small Intestine – **BL-27** (*xiaochangshu*) 🟦■; rectum – **BL-30** (*baihuanshu*), **BL-34** (*xialiao*) 🟦■; Bladder – **BL-28** (*pangguangshu*) 🟦🟦, **BL-23** (*shenshu*) 🟦🟦; urogenital region – **BL-23** (*shenshu*) 🟦🟦, **BL-32** (*ciliao*); cervical spine – **BL-11** (*dazhu*) 🟦■;

---

* Mentioned by only some authors

Ch04.7a-F10028.qxd 2/23/08 3:53 PM Page 249

iliosacral region – **BL-23** (*shenshu*) 🟦🟦; thoracic spine – **BL-38** – **BL-47**; toes – **BL-60** (*kunlun*) 🟦🟦, **BL-65** (*shugu*)

- **Distal points (→ 8.2.1):** occipital region – **BL-65** (*shugu*), **BL-60** (*kunlun*); rectum – **BL-57** (*chengshan*) 🟦🟦; thoracic spine – **BL-57** (*chengshan*) 🟦■; cervical, thoracic, lumbar spine – **BL-60** (*kunlun*) 🟦🟦; shoulder and iliosacral region – **BL-58** (*feiyang*); for the thoracic spine, lumbar spine and iliosacral region – **BL-40** (*weizhong*) 🟦🟦; lumbar spine – **BL-40** (*weizhong*) 🟦🟦, **BL-59** (*fuyang*), **BL-60** (*kunlun*) 🟦🟦; lumbar spine and hip – **BL-62** (*shenmai*) 🟦🟦

Specific points according to the channel pathway (in numerical order):

- **BL-1** (*jingming*) 🟦■: *jiaohui*-meeting point with the ST, T.B.* channels, the *yin qiao mai, yang qiao mai*, S.I., G.B.* channels, *du mai* (→ 8.1.10): local point for the eyes (→ 8.2.1)
- **BL-2** (*zanzhu*) 🟦■: adjacent point for the eyes (→ 8.2.1)
- **BL-7** (*tongtian*): adjacent point for the nose (→ 8.2.1)
- **BL-10** (*tianzhu*) 🟦🟦: Window of Heaven point (→ 8.1.12); important point for eliminating Wind; local point for the occiput and the cervical spine (→ 8.2.1)
- **BL-11** (*dazhu*) 🟦■: *hui*-meeting point (→ 8.1.7) of the bones; Sea of Blood point (→ 8.1.13); *jiaohui*-meeting point with the S.I. channel (T.B., G.B. channels, *du mai**) (→ 8.1.10); adjacent point for the cervical spine (→ 8.1.10)
- **BL-12** (*fengmen*) 🟦■: *jiaohui*-meeting point with the *du mai* (→ 8.1.10)
- **BL-13** (*feishu*) 🟦🟦: Back-*shu* point of the Lung (→ 8.1.4); adjacent point for the Lung (→ 8.2.1)
- **BL-14** (*jueyinshu*): Back-*shu* point of the Pericardium (→ 8.1.4); adjacent point for the Heart (→ 8.2.1)
- **BL-15** (*xinshu*) 🟦🟦: Back-*shu* point of the Heart (→ 8.1.4); adjacent point for the Heart (→ 8.2.1)
- **BL-16** (*dushu*): Back-*shu* point of the *du mai* (→ 8.1.4);
- **BL-17** (*geshu*) 🟦🟦: Back-*shu* point of the diaphragm (→ 8.1.4); *hui*-meeting point of the Blood (→ 8.1.7)
- **BL-17 to BL-23**: local points for the thoracic spine (→ 8.2.1)
- **BL-18** (*ganshu*) 🟦🟦: Back-*shu* point of the Liver (→ 8.1.4); adjacent point for the Liver (→ 8.2.1)
- **BL-19** (*danshu*) 🟦■: Back-*shu* point of the Gall Bladder (→ 8.1.4); adjacent point for the Gall Bladder (→ 8.2.1)
- **BL-20** (*pishu*) 🟦🟦: Back-*shu* point of the Spleen (→ 8.1.4); adjacent point for the Liver (→ 8.2.1)
- **BL-21** (*weishu*) 🟦🟦: local point for the Stomach (→ 8.2.1); Back-*shu* point of the Stomach (→ 8.1.4)
- **BL-22** (*sanjiaoshu*) 🟦■: Back-*shu* point of the Triple Burner (→ 8.1.4)
- **BL-23** (*shenshu*) 🟦🟦: *jiaohui*-meeting point with the *du mai** (→ 8.1.10); local point for the Kidneys and lumbar region (→ 8.2.1); adjacent point for the Bladder, urogenital region and iliosacral region (→ 8.2.1); Back-*shu* point of the Kidney (→ 8.1.4)
- **BL-24** (*qihaishu*): local point for the lumbar spine (→ 8.2.1)
- **BL-25** (*dachangshu*) 🟦🟦: Back-*shu* point of the Large Intestine (→ 8.1.4); adjacent point for the lumbar spine (→ 8.2.1)
- **BL-26** (*guanyuanshu*): local point for the lumbar spine (→ 8.2.1)
- **BL-27** (*xiaochangshu*) 🟦■: Back-*shu* point of the Small Intestine (→ 8.1.4); adjacent point for the Small Intestine (→ 8.2.1); local point for the iliosacral region (→ 8.2.1)
- **BL-28** (*pangguangshu*) 🟦🟦: Back-*shu* point of the Bladder (→ 8.1.4); adjacent point for the Bladder (→ 8.2.1); local point for the iliosacral region (→ 8.2.1)
- **BL-30** (*baihuanshu*): regional point for the rectum (→ 8.2.1)
- **BL-31** – **BL-34**: *jiaohui*-meeting points with the G.B. channel (→ 8.1.10)
- **BL-32** (*ciliao*): regional point for the urogenital region (→ 8.2.1); local point for the iliosacral region (→ 8.2.1)
- **BL-34** (*xiaoliao*): regional point for the rectum (→ 8.2.1)
- **BL-35** (*huiyang*): local point for the rectum (→ 8.2.1)
- **BL-38** – **BL-47**: adjacent points for the thoracic spine (→ 8.2.1)
- **BL-39** (*weiyang*) 🟦■: lower *he*-sea point of the Triple Burner (→ 8.1.9)
- **BL-40** (*weizhong*) 🟦🟦: *he*-sea point (Earth); lower *he*-sea point of the Bladder (→ 8.1.9); Gao Wu command point (→ 8.1.11) of the back and lumbar region; Ma Dan Yang Heavenly Star point (→ 8.1.14); distal point for the thoracic and lumbar spine as well as for the iliosacral region (→ 8.2.1); local point for the knee (→ 8.2.1)
- **BL-41** (*fufen*): *jiaohui*-meeting point with the S.I. channel (→ 8.1.10)
- **BL-43** (*gaohuang*): adjacent point for the Lung (→ 8.2.1)
- **BL-49** (*yishe*): local point for the hip (→ 8.2.1)
- **BL-50** (*weicang*): local point for the hip (→ 8.2.1)
- **BL-52** (*zhishi*): local point for the lumbar region (→ 8.2.1)
- **BL-54** (*zhibian*): local point for the hip (→ 8.2.1)
- **BL-57** (*chengshan*) 🟦■: Ma Dan Yang Heavenly Star point (→ 8.1.14); distal point for the rectum (→ 8.2.1); distal point for the thoracic spine (→ 8.2.1)
- **BL-58** (*feiyang*): *luo*-connecting point (→ 8.1.2); distal point for the shoulder and iliosacral region (→ 8.2.1)
- **BL-59** (*fuyang*): *xi*-cleft point of the *yang qiao mai; jiaohui*-meeting point with the *yang qiao mai* (→ 8.1.10)*; distal point for the lumbar spine (→ 8.2.1)
- **BL-60** (*kunlun*) 🟦🟦: *jing*-river point (Fire); Ma Dan Yang Heavenly Star point (→ 8.1.14); distal point for the cervical, thoracic and lumbar spine (→ 8.2.1); distal point for the occipital and lumbar region (→ 8.2.1); local point for the foot (→ 8.2.1); regional point for the toes (→ 8.2.1)
- **BL-61** (*pucan*): *jiaohui*-meeting point with the *yang qiao mai* (→ 8.1.10)
- **BL-62** (*shenmai*) 🟦🟦:Opening point of the *yang qiao mai* (→ 8.1.8); Sun Si Miao Ghost point (→ 8.1.15); *jiaohui*-meeting point with the *yang qiao mai* (→ 8.1.10); local point

---

* Mentioned by only some authors

for the Kidney (→ 8.2.1); local point for the foot (→ 8.2.1); distal point for the lumbar spine and hip (→ 8.2.1)

- **BL-63** (*jinmen*): *xi*-cleft point (→ 8.1.3); *jiaohui*-meeting point with the *yang wei mai* (→ 8.1.10)
- **BL-64** (*jinggu*): *yuan*-source point (→ 8.1.1)
- **BL-65** (*shugu*): *shu*-stream point (Wood); sedation point; distal point for the occiput (→ 8.2.1); adjacent point for the toes (→ 8.2.1)
- **BL-66** (*zutongu*): *ying*-spring point (Water); *ben* point (Five Phases point)
- **BL-67** (*zhiyin*) 🟦■: *jing*-well point; tonification point

General location help

- **The medial branch of the Bladder channel** runs from **BL-11** (below the spinal process of the T1) to **BL-30** (level with the fourth sacral foramen), 1.5 cun lateral to the midline

Memorisation help for the medial branch of the BL channel:

- **BL11 to BL-17**: the second digit of the point number corresponds to the level of the respective thoracic vertebra. Example: **BL-13** is located below the spinal process of T3.
- **BL-18 to BL-21**: second digit of the point number + 1. *Example*: **BL-19** (9 + 1) is located below the spinal process of the T10.

The outer branch of the Bladder channel runs from **BL-41** (below the spinal process of the T2) to **BL-54** (below the spinal process of S4/level with the 4th sacral foramen) 3 cun lateral to the midline.

Memorisation help for the lateral branch of the BL channel:

- **BL41 to BL-46**: second digit of the point number + 1. *Example*: **BL-42** (2 + 1) corresponds to T3
- **BL-47 to BL-49**: second digit of the point number + 2. *Example*: **BL-47** (7 + 2) corresponds to the level of T9.
- **BL-50**: second digit of the point number + 12.

Needling: The Back-*shu* points are also commonly needled transversely (subcutaneously) towards the spine. This allows the patient to lie in a supine position during needle retention (the needles can be secured with tape).

Bright Eyes **JINGMING** **BL-1**



Location

0.1 cun superior and medial to the inner canthus of the eye, in a depression.

How to find

BL-1 is located in a small depression near the inner canthus of the eye, superior to the insertion of the upper eyelid. Medially, it is bordered by the bony root of the nose. → **BL-2** is located directly above **BL-1** in a depression at the medial end of the eyebrow. → **ST-1** is located on the pupil line between the eyeball and the border of the infraorbital ridge, → **G.B.-1** and → **T.B.-23** are located on the outer canthus of the eye.


Inner canthus of the eye
Needle in BL-1

Needling

Ask the patient to look downward and outward, with their eyes closed. Gently push the eyeball downward and outward from above. Needle perpendicularly along the supraorbital ridge in a posterior direction. Caution: Angular artery and vein, eyeball, periosteum. This point should only be needled by experienced practitioners. After removing the needle, press on the insertion site for 10 minutes. Despite this precaution, a bruise may still form (inform the patient). **No** needle stimulation! Moxibustion is contraindicated. Alternative point: → **BL-2** or transverse (subcutaneous) insertion at **BL-1** in the direction of → **BL-2**.

Actions/Indications

- Expels Wind and clears Heat, benefits the eyes

Special features

Meeting point with the *du mai*, *yin qiao mai*, *yang qiao mai* as well as the ST, S.I., G.B. channels and, according to some authors, also the T.B. channel. Entry point.


G.B.-15
BL-5
Du-23
ST-8
G.B.-13
BL-4
Du-24
BL-3
G.B.-14
Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
Ex-HN-7
ST-1
ST-2
Ex-HN-8
G.B.-2
ST-7
L.I.-20
S.I.-18
L.I.-19


G.B.-14
G.B.-14
Ex-HN-4
(yuyao)
Glabella
Ex-HN-3
(yintang)
T.B.-23
BL-2
Superciliary arch


Orbital margin
ST-1
(below the
pupil)

BL-2

Gathered Bamboo ZANZHU

Location

In a depression at the medial end of the eyebrow, directly above the inner canthus of the eye.

How to find

As the location of the eyebrow can vary, the medial canthus of the eye should be used for reference (→ **BL-1**). Palpate for a generally pressure-sensitive depression in this area of the orbital ridge. Caution: According to Sobotta, except in rare cases, **BL-2** is not located on the supraorbital foramen (mainly located more laterally), but in the area where the supratrochlear artery and the supraorbital nerve emerge (frontal notch).

→ **BL-1** is located inferior to **BL-2**.

Needling

0.3–0.5 cun obliquely from lateral to medial or transversely (subcutaneously) in the direction of the disorder. Caution: Branches of the frontal nerve, facial nerve, blood vessels! According to the majority of authors, moxibustion is contraindicted. Considered a less risky alternative to → **BL-1**.

Actions/Indications

- Benefits the eyes
- Expels external pathogenic factors such as Wind, clears Heat
- Clears the head
- Moves Qi in the Bladder divergent channel (for example, for painful haemorrhoids)

Special features

Important and frequently used local point for the eye region. Good point for excess and Heat syndromes of the eye region: prick to bleed (puncture the point and let it bleed), but avoid facial haematoma.









Eyebrows' Pouring MEICHONG BL-3

Location

0.5 cun within the anterior hairline, vertically above the medial canthus of the eye.

How to find

BL-3 is located directly above the medial canthus of the eye (➞ **BL-1**) and 0.5 cun within the anterior hairline (➞ 3.1.1). Located on the same level (0.5 cun within the anterior hairline) are ➞ **Du-24** (on the midline), ➞ **G.B.-15** (on the pupil line), ➞ **G.B.-13** (3 cun lateral to the midline) and ➞ **ST-8** (on the corner of the forehead).

Needling

0.5–1 cun obliquely in a dorsal direction or transversely (subcutaneously). According to some classic texts, moxibustion is contraindicated.

Actions/Indications

- Expels Wind and clears Heat from the head and forehead


0,5 cun
Hairline
BL-3
BL-2
Inner canthus of the eye
BL-1
Midline


BL-3
BL-2
BL-1
Inner canthus of the eye




BL-8
Du-20
G.B.-18
BL-7
Du-21
G.B.-17
BL-6
Du-22
G.B.-16
BL-5
Du-23
BL-3
G.B.-15
BL-4
Du-24
Hairline

BL-4 *Crooked Curve* QUCHA

Location

0.5 cun superior to the anterior hairline and 1.5 cun lateral to the midline (or one third of the distance between ➞ **Du-24** and ➞ **ST-8**).

How to find

While ➞ **BL-3** is still located on a vertical line through the inner canthus of the eye, **BL-4** is located slightly more laterally (hence its name). The distance of 1.5 cun from the midline refers to the proportional cun measurements along the anterior hairline (➞ 3.1.1): the distance between ➞ **Du-24** (on the midline) and ➞ **ST-8** (on the corner of the forehead) is 4.5 proportional cun; therefore, the distance between **BL-4** and the midline is one third of this distance.

Located on the same level (0.5 cun within the anterior hairline) are ➞ **Du-24** (on the midline), ➞ **BL-3** (superior to the inner canthus of the eye), ➞ **G.B.-15** (on the pupil line), ➞ **G.B.-13** (3 cun lateral to the midline) and ➞ **ST-8** (on the corner of the forehead).


Du-24
BL-4
0.5 cun
ST-8
Hairline
1.5 cun
1/3
2/3
Midline

Needling

Transversely (subcutaneously) 0.5–1 cun

Actions/Indications

- Expels Wind and Wind-Heat, especially from the eyes and the nose
- Clears the head, opens the orifices, alleviates pain


G.B.-15
BL-5
Du-23
ST-8
G.B.-13
BL-4
Du-24
BL-3
G.B.-14
Ex-HN-4
T.B. -23
BL-2
BL-1
Ex-HN-3
G.B.-1
Ex-HN-7
ST-1
ST-2


Original hairline
ST-8



Fifth Place WUCHU BL-5


Du-24
Du-23
BL-5
1 cun
ST-8
Hairline
1.5 cun
1/3
2/3
Midline

Location

1 cun superior to the anterior hairline and 1.5 cun lateral to the midline or one third of the distance between ➞ **Du-24** and ➞ **ST-8**.

How to find

The distance of 1.5 cun refers to the proportional cun measurement for the distance of 4.5 cun between ➞ **Du-24** (midline, 0.5 cun superior to the anterior hairline) and ➞ **ST-8** (corner of the forehead), (➞ 2.2). By dividing this distance into thirds, **BL-5** can be located one third of the distance from ➞ **Du-24** and 1 cun superior to the anterior hairline.
Located on the same level is ➞ **Du-23** (on the midline).

Needling

Transversely (subcutaneously) 0.5–1 cun. Moxibustion is contraindicated according to some texts.

Actions/Indications

- Releases the Exterior, expels Wind and Heat from the head and eyes
- Opens the channel and the *luo* vessels
- Opens the orifices (especially the eyes) and revives consciousness


Hairline
1 cun
Du-23


BL-8
Du-20
G.B.-18
BL-7
Du-21
G.B.-17
BL-6
Du-22
G.B.-16
BL-5
Du-23
G.B.-15
BL-3
BL-4
Du-24
Hairline

BL-6 *Receiving Light* CHENGGUAN

Location

2.5 cun superior to the anterior hairline and 1.5 cun lateral to the midline or one third of the distance between → **Du-24** and → **ST-8**.

How to find

Spreading hands technique (→ 2.3.3): First, locate the anterior midline at the level of the anterior hairline (→ 3.1.1) as well as → **Du-20** (5 cun superior to the anterior hairline, on the vertex, at the junction of the midline with a line connecting the apices of the ears). Next, determine the midpoint between those two reference points (→ 2.5 cun superior to the anterior hairline). From this point, measure 1.5 cun laterally (or one third of the distance between → **Du-24** and → **ST-8**) to locate **BL-6**.

Located on the same level (→ 2.5 cun superior to the anterior hairline), but more laterally (pupil line), is → **G.B.-17**.

Needling

Transversely (subcutaneously) 0.5–1 cun. Moxibustion only following careful diagnosis.

Actions/Indications

- Expels Wind, especially from the head and eyes
- Clears Heat from the head, especially from the eyes and nose


Hairline
2.5 cun
1/2
BL-6
Apex of the ear
Apex of the ear
1.5 cun
1/2
Du-20
Midline


5 cun
Du-20
Apex of the ear
Apex of the ear




G.B.-17
2.25 cun
Apex of the ear
2.5 cun
Apex of the ear
Du-20


BL-8
Du-20
G.B.-18
BL-7
Du-21
G.B.-17
BL-6
Du-22
G.B.-16
BL-5
Du-23
BL-3
G.B.-15
BL-4
Du-24
Hairline

Heavenly Connection TONGTIAN BL-7

Location

1.5 cun lateral to the midline and 4 cun superior to the anterior hairline or 1 cun anterior to → **Du-20**.

How to find

BL-7 is best located by using → **Du-20** (5 cun superior to the anterior hairline, on the vertex, at the junction of the midline with a line connecting the apices of the ears) as a reference point. Measure 1 cun anterior from → **Du-20** and 1.5 cun lateral to the midline (or one third of the distance between → **Du-24** and **ST-8,** → 2.2) to locate **BL-7**. Located on the same level (4 cun superior to the anterior hairline), but more laterally (pupil line), is → **G.B.-18**. → **Du-21** is located on the midline, 1.5 cun anterior to → **Du-20**.

Needling

Transversely (subcutaneously) 0.5–1 cun

Actions/Indications

- Clears the head, benefits especially the nose

Special features

Important point for treating disorders of the nose


Hairline
4 cun
1.5 cun
Apex of the ear
Apex of the ear
1 cun
BL-7
Du-20
Midline


Original hairline
ST-8


Apex of the ear
Apex of the ear
G.B.-18
2.25 cun
1 cun
Du-20


Apex of the ear
Du-21
Apex of the ear
1.5 cun

BL-8 *Declining Connection* LUOQUE

Location

1.5 cun lateral to the midline and 5.5 cun superior to the anterior hairline or 0.5 cun posterior to → **Du-20**.

How to find

BL-8 is best located by using → **Du-20** as a reference point. → **Du-20** is located at the junction of the vertical midline with a line connecting the apices of the ears, 5 cun superior to the anterior hairline (→ 3.1.1). To locate **BL-8**, measure 0.5 cun from → **Du-20** in a posterior direction and 1.5 cun in a lateral direction.

Needling

Transversely (subcutaneously) 0.5–1 cun. Moxibustion possible.

Actions/Indications

- Opens the orifices
- Subdues Wind
- Transforms Phlegm
- Calms the *shen*


Apex of the ear
Apex of the ear
Du-20
0.5 cun
BL-8
1.5 cun
Midline


5 cun
Du-20
Apex of the ear
Apex of the ear


BL-8
Du-20
G.B.-18
BL-7
Du-21
G.B.-17
BL-6
Du-22
G.B.-16
BL-5
Du-23
BL-3
G.B.-15
BL-4
Du-24
Hairline

Jade Pillow YUZHEN BL-9


Midline
1.3 cun
External occipital protuberance
Du-17
BL-9
ca. 2.5 cun
Du-16
C1
≙(atlas)
BL-10
Hairline


G.B.-19
BL-9
Du-17
Du-16
G.B.-20
G.B.-12
BL-10
Du-15


BL-9
Du-17
BL-9
Mastoid process
Occipitomastoid suture
Du-16
Occipital bone
External occipital protuberance


External occipital protuberance
2.25 cun
Du-17
G.B.-19
1,5 cun

Location

2.5 cun superior to the posterior hairline and 1.3 cun lateral to the midline or → **Du-17** (directly superior to the external occipital protuberance).

How to find

To locate **BL-9,** → **Du-17** is a good reference point, located on the midline, in the depression directly superior to the upper border of the external occipital protuberance (→ 3.1.5). From there, measure 1.3 cun in a lateral direction to locate **BL-9**, which is generally located on an imaginary vertical line through → **BL-10.**
Or: Locate the posterior hairline (often not very accurate → 3.1.5) and, on the midline, measure 2.5 cun in a superior direction, then 1.3 cun towards lateral.
Located on the same level are → **Du-17** (midline, in the depression at the upper border of the external occipital protuberance) and → **G.B.-19** (more laterally, on a vertical line through → **G.B.-20**).

Needling

Transversely (subcutaneously) 0.5–1 cun. Moxibustion possible.

Actions/Indications

- Expels Wind and Cold
- Opens the channel and *luo* vessels, alleviates pain
- Benefits the eyes and nose

Special features

In Qigong practice, **BL-9** plays an important role as one of the three gates (*san guan*).

BL-10 *Heavenly Pillar* TIANZHU

Location

Approximately 1.3 cun lateral to ➞ **Du-15**, where the trapezius muscle inserts on the lower border of the occiput, close to where the major occipital nerve emerges.

How to find

With the patient's head in an upright and relaxed position, first locate ➞ **G.B.-20** below the lower border of the occiput and between the insertions of the sternocleidomastoid and trapezius muscles. From there, palpate in a medial and inferior direction at a 45° angle, until the finger comes to a halt against the bulge of the trapezius muscle. This is the location of **BL-10**. For reference: If the practitioner places their left middle finger on ➞ **G.B.-20**, the (shorter) index finger will be pointing to **BL-10**. Located on the same level is ➞ **Du-15** (approximately 1.3 cun lateral to the midline and superior to the axis (first palpable spinous process)).

Needling

0.5–1 cun vertically or slightly obliquely in a dorsal direction. Caution: Do not needle in a superior direction.

Actions/Indications

- Regulates the Qi, calms Wind and the *shen*, benefits the head and sensory orifices
- Opens the channel
- Strengthens the lower back
- Expels Wind

Special features

Window of Heaven point. Important point for expelling (internal and external) Wind. In contrast to ➞ **G.B.-20**, **BL-10** is used in clinical practice mainly for pacifiying internal Wind.


Atlas
Du-16
G.B.-20
Occipital bone
Lower border of the occiput
G.B.-20
Axis
BL-10
Sternocleido-mastoid
Du-15
1st palpable transverse process
Trapezius, superior fibres
Du-14




Vertebral prominence, spinous process
External occipital protuberance
Sternocleidomastoid
Splenius capitis
Trapezius
Scapular spine


G.B.-19
BL-9
Du-17
Du-16
G.B.-20
G.B.-12
BL-10
Du-15

Great Shuttle DAZHU BL-11


BL-11
Medial border of the scapula
Base of the scapular spine
Spinous process C7
Spinous process T1
Spinous process T3
Spinous process T7
Inferior angle of the scapula
1.5 cun
1.5 cun
Spinous process T12
Bladder channel, lateral branch
Bladder channel, medial branch
Midline


S.I.-15
14
S.I.-12
11
13
S.I.-10
42
13
12
44
15
11


Extension and flexion of the head
Finger on the spinous processes of C6 and 7
G.B.-21
S.I.-15
Du-14


Base of the scapular spine
Spinous process C7
Spinous process T1
Du-13


Levator scapulae
Spinous process C7
Spinous process T1
S.I.-14
S.I.-13

Location

1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 1st thoracic vertebra (T1, with hanging shoulders on the level of the acromion).

How to find

First, locate the spinous process of C7 (→ 3.4.1). The next spinous process inferior to this belongs to the T1. Locate **BL-11** 1.5 cun lateral to the lower border of T1, at the highest point of the paraspinal musculature.

Located on the same level are → **Du-13** (on the midline), a point of → **Ex-B-2** (0.5 cun lateral to the midline) and → **S.I.-14** (3 cun lateral to the midline).

Needling

0.5–1 cun obliquely towards the spine or transversely (subcutaneously). Caution: Pneumothorax.

Actions/Indications

- Expels pathogenic factors (Wind-Heat)
- Regulates the Lung Qi
- Opens the channel, benefits the bones and joints

Special features

Hui-meeting point with the bones; meeting point with the S.I. channel, according to some authors also with the T.B., G.B. channels and the *du mai*; Sea of Blood point.

BL-12 *Wind Gate* FENGMEN

Location

1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 2nd thoracic vertebra (T2).

How to find

First, locate the spinous process of C7 (→ 3.4.1). From there, count down two spinous processes to the lower border of the spinous process of T2. Measure 1.5 cun laterally to locate **BL-12** on the highest point of the paraspinal musculature.

Located on the same level are a point of → **Ex-B-2** (0.5 cun lateral to the midline), → **BL-41** (3 cun lateral to the midline) and → **S.I.-13** (on the scapula, on the medial end of the scapular spine).

Needling

0.5–1 cun obliquely towards the spine. In clinical practice, this point is often needled transversely (subcutaneously) towards the spine. This allows the patient to lie in a supine position during needle retention (the needles can be secured with tape). Caution: Pneumothorax. For acute febrile colds, use reducing needling techniques or cupping. For susceptibility to catching colds, use tonifying needling techniques and/or moxibustion.

Actions/Indications

- Expels (external) Wind and releases the Exterior
- Spreads and descends the Lung Qi
- Tonifies the defensive Qi (*wei qi*), stabilises the Exterior
- Benefits the nose
- Opens the channel

Special features

Meeting point with the *du mai*. Important point for expelling pathogenic factors, especially Wind.


Spinous process C7
Medial border of the scapula
Base of the scapular spine
Spinous process T2
Spinous process T3
BL-12
Spinous process T7
Inferior angle
1.5 cun
1.5 cun
Spinous process T12
Bladder channel, lateral branch
Bladder channel, medial branch
Midline


Spinous process C7
Medi
scap
Scapular spine
Spinous process T2
BL-41
Spinous process T3


Lower border of the spinous process of T3
BL-12


Spinous process C7
Spinous process T1
S.I.-13


S.I.-15
S.I.-12
S.I.-10
14
11
13
42
13
12
44
15
11


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2 (parts)

Lung Shu FEISHU BL-13


Medial border of the scapula
Base of the scapular spine
Spinous process C7
Spinous process T3
BL-13
Spinous process T7
Inferior angle
1.5 cun
1.5 cun
Spinous process T12
Bladder channel, lateral branch
Bladder channel, medial branch
Midline


Lower border of the spinous process (BSP) of T3
BL-13


Extension and flexion of the head
2 fingers on the spinous processes of C6 and 7
G.B.-21
S.I.-15
Du-14

Location

1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 3rd thoracic vertebra (T3).

How to find

First, locate the spinous process of C7 (→ 3.4.1). From there, count down three spinous processes to the lower border of the spinous process of the T3. Measure 1.5 cun laterally to locate **BL-13** on the highest point of the paraspinal musculature. **Or:** With the patient seated and their arms hanging down, the spinous process of the T3 is generally on the level of the medial end of the scapular spine (→ 3.4.2). Locate **BL-13** 1.5 cun lateral to the midline.

Located on the same level are → **Du-12** (on the midline), a point of → **Ex-B-2** (0.5 cun lateral to the midline) and **BL-42** (3 cun lateral to the midline).

Needling

0.5–1 cun obliquely towards the spine. In clinical practice, this point is often needled transversely (subcutaneously) towards the spine. This allows the patient to lie in a supine position during needle retention (the needles can be secured with tape). Caution: Pneumothorax. For chronic Lung Qi deficiency without Heat signs, use moxibustion.

Actions/Indications

- Tonifies, spreads and descends the Lung Qi, nourishes the Lung Yin
- Clears Heat from the Lung
- Releases the Exterior
- Opens the channel, alleviates pain

Special features

Back-*shu* point of the lung. Major point for all disorders of the Lung (Lung deficiency and excess patterns).


Spinous process C7
Spinous process T3
Du-12


Spinous process C7
Medial scapula
Scapular spine
Spinous process T3
BL-42

BL-14 Jueyin Shu JUEYINSHU

Location

1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 4th thoracic vertebra (T4).

How to find

First, locate the spinous process of C7 (→ 3.4.1). From there, count down four spinous processes to the lower border of the spinous process of T4. Measure 1.5 cun laterally to locate **BL-14** on the highest point of the paraspinal musculature. **Or:** With the patient seated and their arms hanging down, the spinous process of T3 is generally on the level of the medial end of the scapular spine (→ 3.4.2). The next spinous process in an inferior direction belongs to the T4. Locate **BL-14** 1.5 cun lateral to the midline. Located on the same level are a point of → **Ex-B-2** (0.5 cun lateral to the midline) and → **BL-43** (3 cun lateral to the midline).

Needling

0.5–1 cun obliquely towards the spine or transversely (subcutaneously). Caution: Pneumothorax.

Actions/Indications

- Regulates and tonifies the Heart
- Unbinds the chest, regulates the Qi
- Calms the *shen*

Special features

Back-*shu* point of the Pericardium


Spinous process C7
Medial border of the scapula
Base of the scapular spine
Spinous process T3
Spinous process T4
BL-14
Spinous process T7
Inferior angle
1.5 cun
1.5 cun
Spinous process T12
Bladder channel, lateral branch
Bladder channel, medial branch
Midline


S.I.-15
14
S.I.-12
11
13
S.I.-10
42
13
12
44
15
11
46
17
9
Ex-B-3


Spinous process C7
Medial scapula
Scapular spine
Spinous process T3
Spinous process T4
BL-43


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2 (parts)

Heart Shu XINSHU BL-15


Spinous process C7
Medial border of the scapula
Base of the scapular spine
Spinous process T3
Spinous process T5
BL-15
Spinous process T7
Inferior angle
1.5 cun
1.5 cun
Spinous process T12
Bladder channel, lateral branch
Midline
Bladder channel, medial branch


Lower border of the spinous process (BSP) of T5
BL-15


Extension and flexion of the head
2 fingers on the spinous processes of C6 and 7
G.B.-21
S.I.-15
Du-14

Location

1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 5th thoracic vertebra (T5).

How to find

First, locate the spinous process of C7 (➞ 3.4.1). From there, count down five spinous processes to the lower border of the spinous process of T5. Measure 1.5 cun laterally to locate **BL-15** on the highest point of the paraspinal musculature. **Or:** With the patient seated and their arms hanging down, the spinous process of the T3 is generally on the level of the easily palpable medial end of the scapular spine (➞ 3.4.2). From there, count down two spinous processes in an inferior direction to the T5. Locate **BL-15** 1.5 cun lateral to the midline.

Located on the same level are ➞ **Du-11** (on the midline), a point of ➞ **Ex-B-2** (0.5 cun lateral to the midline) and ➞ **BL-44** (3 cun lateral to the midline).

Needling

0.5–1 cun obliquely towards the spine. In clinical practice, this point is often needled transversely (subcutaneously) towards the spine. This allows the patient to lie in a supine position during needle retention (the needles can be secured with tape). Caution: Pneumothorax.

Actions/Indications

- Tonifies and nourishes the Heart, regulates the Heart Qi, unbinds the chest and removes Blood stasis, calms the *shen*, clears Fire, moves Qi locally and along the channel pathway: for example, for disorders of the thoracic spine and intercostal region

Special features

Back-*shu* point of the Heart


Spinous process T5
Du-11
Spinous process T7
Inferior angle


Spinous process T5
BL-44
Spinous process T7
Inferior angle

BL-16 *Governing* Shu DUSHU

Location

1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 6th thoracic vertebra (T6).


Spinous process C7
Medial border of the scapula
Base of the scapular spine
Spinous process T3
Spinous process T6
Spinous process T7
BL-16
Inferior angle
1.5 cun
1.5 cun
Spinous process T12
Bladder channel, lateral branch
Bladder channel, medial branch
Midline

How to find

First, locate the spinous process of the C7 (→ 3.4.1). From there, count down six spinous processes to the lower border of the spinous process of T6. Measure 1.5 cun laterally to locate **BL-16** on the highest point of the paraspinal musculature. **Or:** With the patient standing and their arms hanging down, the spinous process of T7 is level with the inferior angle of the scapula (→ 3.4.2). The next spinous process in a superior direction belongs to T6. Locate **BL-16** 1.5 cun lateral to the midline.

Located on the same level are → **Du-10** (on the midline), a point of → **Ex-B-2** (0.5 cun lateral to the midline) and → **BL-45** (3 cun lateral to the midline).


S.I.-15
S.I.-12
S.I.-10
14
11
13
42
13
12
44
15
11
46
17
9
Ex-B-3
1
2
3
4
5
6
7
8
9

Needling

0.5–1 cun obliquely towards the spine or transversely (subcutaneously). Caution: Pneumothorax.


Spinous process T7
Du-10
Inferior angle

Actions/Indications

- Unbinds the chest and regulates the Qi movement in the thorax and the abdomen


Spinous process T6
Spinous process T7
BL-45
Inferior angle
3 cun

Special features

Despite its designation as Back-*shu* point of the *du mai*, this point is hardly mentioned in classical or modern texts.


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2 (parts)

Diaphragm Shu GESHU BL-17


Spinous process C7
Spinous process T3
Spinous process T7
Spinous process T12
Midline
Medial border of the scapula
Base of the scapular spine
BL-17
Inferior angle
1.5 cun
1.5 cun
Bladder channel, lateral branch
Bladder channel, medial branch


Lower border of the spinous process (BSP) of T7
BL-17


Extension and flexion of the head
2 fingers on the spinous processes of C6 and 7
G.B.-21
S.I.-15
Du-14

Location

1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 7th thoracic vertebra (T7).

How to find

The spinous process of the T7 is approximately on the level of the inferior angle of the scapula (→ 3.4.2). **BL-17** is located on the level of the lower border of its spinous process and 1.5 cun lateral to the midline at the highest point of the paraspinal musculature. **Or:** Use the spinous process of the T3 for reference (generally on the level of the medial end of the scapular spine) (→ 3.4.2). **Or:** Use C7 as a reference point (→ 3.4.1).
Located on the same level are → **Du-9** (on the midline), a point of → **Ex-B-2** (0.5 cun lateral to the midline) and → **BL-46** (3 cun lateral to the midline).

Needling

0.5–1 cun obliquely towards the spine. In clinical practice, this point is often needled transversely (subcutaneously) towards the spine. This allows the patient to lie in a supine position during needle retention (the needles can be secured with tape). Caution: Pneumothorax.

Actions/Indications

- Cools Blood-Heat, stops bleeding, removes Blood stasis, nourishes and harmonises Blood (and Yin)
- Regulates the diaphragm, descends counterflow Qi
- Moves Qi locally and along the channel pathway

Special features

Back-*shu* point of the Diaphragm, *hui*-meeting point of the Blood.




Spinous process T7
BL-46
Inferior angle
3 cun

BL-18 *Liver* Shu GANSHU


Spinous process C7
Medial border of the scapula
Base of the scapular spine
Spinous process T3
1.5 cun
1.5 cun
Spinous process T7
Inferior angle
Spinous process T9
BL-18
Spinous process T12
Bladder channel, lateral branch
Midline
Bladder channel, medial branch

Location

1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 9th thoracic vertebra (T9).

How to find

In a standing position with the arms hanging down, the spinous process of T7 is approximately on the level of the inferior angle of the scapula (→ 3.4.2). From there, count down two spinous processes to the spinous process of T9. **BL-18** is located on the level of the lower border of its spinous process and 1.5 cun lateral to the midline at the highest point of the paraspinal musculature. **Or:** Use the C7 as a reference point (→ 3.4.1). From there, count down nine spinous processes to T9 and locate **BL-18** 1.5 cun lateral to the lower border of its spinous process.

Located on the same level are → **Du-8** (on the midline), a point of → **Ex-B-2** (0.5 cun lateral to the midline) and → **BL-47** (3 cun lateral to the midline).


Lower border of the spinous process (BSP) of T9
BL-18

Needling

0.5–1 cun obliquely towards the spine. In clinical practice, this point is often needled transversely (subcutaneously) towards the spine. This allows the patient to lie in a supine position during needle retention (the needles can be secured with tape). Caution: Pneumothorax.

Actions/Indications

- Spreads Liver Qi, cools Fire, clears Damp-Heat, regulates and nourishes Liver Blood, subdues (internal) Wind
- Benefits the eyes
- Benefits the sinews

Special features

Back-*shu* point of the Liver


Spinous process T7
Inferior angle
Spinous process T9
BL-47


Spinous process T9
Spinous process T10
Du-8


46
17
9
Ex-B-3
47
18
8
10
11
12
49
20
6
Ex-B-4
52
23
4
Ex-B-5
Ex-B-5
Ex-B-7
25
3
Ex-B-6

Gall Bladder Shu DANSHU BL-19


Spinous process C7
Medial border of the scapula
Base of the scapular spine
Spinous process T3
1.5 cun
1.5 cun
Spinous process T7
Inferior angle
Spinous process T10
BL-19
Spinous process T12
Bladder channel, lateral branch
Bladder channel, medial branch
Midline


Lower border of the spinous process (BSP) of T10
BL-19


BL-23
Du-4
BL-52
Spinous process L4
Level of the iliac crests
Tuffier's line
Du-3


Spinous process T10
Du-7
Spinous process T11

Location

1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 10th thoracic vertebra (T10).

How to find

In a standing position with the patient's arms hanging down, the spinous process of T7 is approximately on the level of the inferior angle of the scapula (→ 3.4.2). From there, count down three spinous processes to the spinous process of T10. **BL-19** is located on the level of the lower border of its spinous process and 1.5 cun lateral to the midline at the highest point of the paraspinal musculature. **Or:** Use C7 as a reference point (→ 3.4.1). From there, count down 10 spinous processes to T10 and locate **BL-19** 1.5 cun lateral to the lower border of its spinous process. **Or:** Use the lumbar spine as a reference point (→ 3.4.3).

Located on the same level are → **Du-7** (on the midline), a point of → **Ex-B-2** (0.5 cun lateral to the midline) and → **BL-48** (3 cun lateral to the midline).

Needling

0.5–1 cun obliquely towards the spine. In clinical practice, this point is often needled transversely (subcutaneously) towards the spine. This allows the patient to lie in a supine position during needle retention (the needles can be secured with tape). Caution: Pneumothorax.

Actions/Indications

- Clears Damp-Heat from the Liver and Gall Bladder
- Expels pathogenic factors from the *shaoyang*
- Tonifies and regulates the Gall Bladder Qi
- Unbinds the chest and relaxes the pathway of the channel

Special features

Back-*shu* point of the Gall Bladder. Important point for clearing Damp-Heat from the Liver and Gall Bladder.


Extension and flexion of the head
2 fingers on the spinous processes of C6 and 7
G.B.-21
S.I.-15
Du-14


inferior
Spinous process T10
BL-48

BL-20 *Spleen* Shu PISHU

Location

1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 11th thoracic vertebra (T11).

How to find

In a seated position with the arms hanging down, the spinous process of T7 is approximately on the level of the inferior angle of the scapula (→ 3.4.2). From there, count down four spinous processes to the spinous process of T11. **BL-20** is located on the level of the lower border of its spinous process and 1.5 cun lateral to the midline at the highest point of the paraspinal musculature. **Or:** Locate the articulation of the most inferior rib (T12) and palpate in a superior direction to T11. **Or:** Use the lumbar spine for reference (→ 3.4.3).

Located on the same level are → **Du-6** (on the midline), a point of → **Ex-B-2** (0.5 cun lateral to the midline) and **BL-49** (3 cun lateral to the midline).

Needling

0.5–1 cun obliquely towards the spine. In clinical practice, this point is often needled transversely (subcutaneously) towards the spine. This allows the patient to lie in a supine position during needle retention (the needles can be secured with tape). Caution: Pneumothorax.

Actions/Indications

- Tonifies the Spleen Qi and Yang, regulates Qi in the Middle, raises Qi
- Transforms Dampness
- Holds and nourishes Blood

Special features

Back-*shu* point of the spleen. Major point for tonifying the Middle, especially for Spleen deficiency syndromes. Use moxibustion or tonifying needle techniques for nourishing the Blood.


Extension and flexion of the head
2 fingers on the spinous processes of C6 and 7
G.B.-21
S.I.-15
Du-14


Spinous process T11
Spinous process T12
BL-49


Spinous process C7
Medial border of the scapula
Base of the scapular spine
Spinous process T3
1.5 cun
1.5 cun
Spinous process T7
Inferior angle
Spinous process T12
Spinous process T12
BL-20
Bladder channel, lateral branch
Bladder channel, medial branch
Midline


Lower border of the spinous process (BSP) of T11
BL-20


46
17
9
Ex-B-3
9
47
18
8
10
11
49
20
6
12
1
Ex-B-4
2
52
23
4
3
Ex-B-5
Ex-B-5
4
Ex-B-7
25
3
Ex-B-6
5


Spinous process T11
Du-6
Spinous process T12


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2 (parts)

Stomach Shu WEISHU BL-21


Medial border of the scapula
Base of the scapular spine
Spinous process C7
Spinous process T3
1.5 cun
1.5 cun
Spinous process T7
Inferior angle
Spinous process T12
BL-50
BL-21
Bladder channel, lateral branch
Midline
Bladder channel, medial branch


Lower border of the spinous process
T11
T12
BL-20
BL-21


Spinous process T11
Spinous process T12
BL-21
Spinous process L1
Spinous process L2
Spinous process L3
Spinous process L4
Level of the iliac crests
Spinous process L5
1.5 cun


BL-23
Du-4
BL-52
Spinous process L4
Level of the iliac crests
Tuffier's line
Du-3

Location

1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 12th thoracic vertebra (T12).

How to find

In a seated position with the arms hanging down, the spinous process of T7 is approximately on the level of the inferior angle of the scapula (→ 3.4.2). From there, count down five spinous processes to the spinous process of T12. **BL-21** is located on the level of the lower border of its spinous process and 1.5 cun lateral to the midline at the highest point of the paraspinal musculature. **Or:** Palpate for the articulation of the most inferior rib with T12 and locate **BL-21** 1.5 cun lateral to the lower border of its spinous process. **Or:** Use the lumbar spine for reference (→ 3.4.3). Located on the same level are a point of → **Ex-B-2** (0.5 cun lateral to the midline) and → **BL-50** (3 cun lateral to the midline).

Needling

0.5–1 cun obliquely towards the spine. In clinical practice, this point is often needled transversely (subcutaneously) towards the spine. This allows the patient to lie in a supine position during needle retention (the needles can be secured with tape). Caution: Pneumothorax.

Actions/Indications

- Regulates the Stomach, descends counterflow Qi, harmonises the Middle Burner, eliminates Dampness and food stagnation
- Opens the channel

Special features

Back-*shu* point of the Stomach, main point for regulating any dysfunction of the Stomach.

BL-22 San Jiao Shu SANJIAOSHU

Location

1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 1st lumbar vertebra (L1).

How to find

For orientation in the lumbar region (→ 3.4.3), first, determine the Tuffier's line (a line connecting the highest points of the iliac crests), which in most cases intersects with the spinous process of L4 (note: this varies depending on the patient's position → 3.4.3). From there, count upward to the lower border of the spinous process of L1 and, on this level, locate **BL-22** 1.5 cun in a lateral direction, on the highest point of the paraspinal musculature.

Located on the same level are → **Du-5** (on the midline), a point of → **Ex-B-2/BL-51/Ex-B-4** (0.5 cun/3 cun/3.5cun lateral of the midline).

Needling

Obliquely 0.5–1.5 cun. Caution: Kidneys.

Actions/Indications

- Regulates the Triple Burner
- Opens the water passages and promotes urination
- Has an effect on the *shaoyang*

Special features

Back-*shu* point of the Triple Burner. Especially regulates the relationship between the Middle and Lower Burner.


Spinous process L1
Spinous process L2
BL-51


Spinous process L1
Ex-B-4


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2
(parts)


Spinous process L1
BL-22
Spinous process L2
Spinous process L3
Spinous process L4
Level of the
iliac crests
Spinous process L5
1.5
cun


Level of spinous process C4
Level of the iliac crests
(dependent on patient position)


46
17
9
Ex-B-3
9
47
18
8
10
11
49
20
6
12
1
Ex-B-4
2
52
23
4
3
Ex-B-5
Ex-B-5
4
Ex-B-7
25
3
Ex-B-6
5


BL-23
Du-4
BL-52
Spinous process L4
Level of
the iliac
crests
Tuffier's line
Du-3


Spinous process L1
Du-5
Spinous process L2
Spinous process L3

Ch04.7a-F10028.qxd 2/23/08 3:54 PM Page 273

Kidney Shu SHENSHU BL-23

Location

1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 2nd lumbar vertebra (L2).

How to find

For orientation in the lumbar region (→ 3.4.3), first, determine the Tuffier's line (a line connecting the highest points of the iliac crests), which in most cases intersects with the spinous process of L4 (note: this varies depending on the patient's position → 3.4.3). From there, count upward to the lower border of the spinous process of L2 and, on this level, locate **BL-23** 1.5 cun in a lateral direction, on the highest point of the paraspinal musculature. Located on the same level are → **Du-4** (on the midline), a point of → **Ex-B-2/BL-52** (0.5 cun/3 cun lateral of the midline).

Needling

Vertically or obliquely 0.5–1.5 cun. Caution: Kidneys.

Actions/Indications

- Strengthens the Kidneys, tonifies the Kidney Qi and Yang, benefits the Essence (*jing*), nourishes the Kidney Yin
- Regulates the Lower Burner, benefits the uterus
- Benefits the bones and the marrow
- Benefits the eyes and ears
- Strengthens the lower back

Special features

Back-*shu* point of the Kidneys, according to some authors, meeting point with the *du mai*. Major point for tonifying the Kidneys. Use tonifying needle techniques for all Kidney deficiency syndromes. Moxibustion tonifies especially the Kidney Yang. **Caution**: Moxibustion is contraindicated for Kidney Yin deficiency with empty Heat (Heat in the Five Hearts (Heat in the thorax, the palms and the soles of the feet), night sweats, restlessness, often a red tongue).


1,5 cun
Spinous process L1
Spinous process L2
Spinous process L3
Spinous process L4
BL-22
BL-23
BL-24
Level of the iliac crests (dependent on patient position)
Midline


Level of spinous process L4
Level of the iliac crests (dependent on patient position)


Lower border of the spinous process (BSP) of L2
BL-23


Level of the iliac crests (dependent on patient position)
Spinous process L2
Spinous process L3
Du-4
Spinous process C4


Spinous process L1
Spinous process L2
Spinous process L3
BL-52

BL-24 *Sea of Qi* QIHAISHU

Location

1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 3rd lumbar vertebra (L3).

How to find

For orientation in the lumbar region (→ 3.4.3), first, determine the Tuffier's line. Place both hands directly superior or lateral to the highest points of the iliac crests, joining the thumbs on the midline at the lumbar spine. In most cases, this line intersects with the spinous process of L4 (note: this varies depending on the patient's position → 3.4.3). From there, count upward to the lower border of the spinous process of L3 and, on this level, locate **BL-24** 1.5 cun in a lateral direction.

Located on the same level are a point of → **Ex-B-2** (0.5 cun lateral to the midline) and → **Ex-B-5** (*xiazhishi*; 3 cun lateral to the midline according to the WHO location notes).

Needling

Vertically 0.5–1.5 cun

Actions/Indications

- Benefits the back and strengthens the knees
- Regulates and tonifies Qi and Blood of the Lower Burner


1.5 cun
Spinous process C3
BL-24
Level of the iliac crests
Spinous process C4
Midline


Level of the iliac crests
Ex-B-5
3 cun


Level of spinous process L4
Level of the iliac crests (dependent on patient position)


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2 (parts)


46
17
9
Ex-B-3
9
47
18
8
10
11
49
20
6
12
1
Ex-B-4
2
52
23
4
3
Ex-B-5
Ex-B-5
4
Ex-B-7
25
3
Ex-B-6
5

Large Intestine Shu DACHANGSHU BL-25


1.5 cun
Spinous process C3
Spinous process C4
Level of the iliac crests ≙ C4 (dependent on patient position)
BL-25
Midline


Level of spinous process L4
Level of the iliac crests (dependent on patient position)


Lower border of the spinous process (BSP) of L4
BL-25


Level of the iliac crests
Spinous process L4
Spinous process L5
Du-3


Level of the iliac crests
Level of spinous process L4
Ex-B-6

Location

1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 4th lumbar vertebra (L4).

How to find

For orientation in the lumbar region (→ 3.4.3), first, determine the Tuffier's line. Place both hands directly superior or lateral to the highest points of the iliac crests, joining the thumbs on the midline at the lumbar spine. In most cases, this line intersects with the spinous process of L4 (note: this varies depending on the patient's position → 3.4.3). On this level, locate **BL-25** 1.5 cun in a lateral direction.

Located on the same level are → **Du-3** (on the midline), a point of → **Ex-B-2** (0.5 cun lateral to the midline), → **Ex-B-6** (3 cun lateral to the midline) and → **Ex-B-7** (3.5 cun lateral to the midline).

Needling

Vertically 1–1.5 cun

Actions/Indications

- Regulates the intestines and promotes the Qi flow
- Strengthens the lower back

Special features

Back-*shu* point of the Large Intestine. Important point for regulating the Large Intestine Qi. Important local point for acute and chronic lumbar disorders.


Level of the iliac crests
Spinous process L3
Spinous process L4
Ex-B-7

BL-26 *Gate of Origin* Shu GUANYUANSHU

Location

1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 5th lumbar vertebra (L5).

How to find

For orientation in the lumbar region (→ 3.4.3), first, determine the Tuffier's line. Place both hands directly superior or lateral to the highest points of the iliac crests, joining the thumbs on the midline at the lumbar spine. In most cases, this line intersects with the spinous process of L4 (note: this varies depending on the patient's position; for more detail on orientation in the lumbar/sacral region → 3.4.3, 3.4.4). Next, locate the lower border of the spinous process of L5 and, on this level, locate **BL-26** 1.5 cun in a lateral direction.

Located on the same level are → **Ex-B-8** (on the midline) and a point of → **Ex-B-2** (0.5 cun lateral to the midline).

Needling

Vertically 0.5–1.5 cun

Actions/Indications

- Strengthens the back, especially for Kidney deficiency syndromes
- Regulates the Lower Burner


1.5 cun
Spinous process L3
Level of the iliac crests
Spinous process L4
Spinous process L5
BL-26
Midline


Level of the iliac crests
Spinous process L4
Spinous process L5
Ex-B-8


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2 (parts)


52
23
4
Ex-B-5
Ex-B-5
Ex-B-7
25
3
Ex-B-6
Ex-B-8
54
30
Ex-B-11
36
Bladder channel, lateral branch
Du mai
Bladder channel, medial branch


L4
Tuffier's line
Iliac crest
L5
PSIS
Lumbosacral junction
Sacrum


Iliosacral joints
Ilium
Sacrum

Ch04.7a-F10028.qxd 2/23/08 3:54 PM Page 277

Small Intestine Shu XIAOCHANGSHU BL-27

Location

1.5 cun lateral to the posterior midline, on the level of the first sacral foramen.

How to find

Quick method: Locate the posterior superior iliac spine (PSIS → 3.4.3): from the rima ani, palpate 3 cun (1 handbreadth) in a superior and lateral direction at a 45° angle, until you can feel a distinct bony ridge (often superficially visible by a dimple). **BL-27** is located slightly superiorly and medially to the PSIS, 1.5 cun lateral to the midline, on the level of the first sacral foramen. For more detail on orientation in the lumbar and sacral region → 3.4.3, 3.4.4.

Located on the same level are → **BL-31** (over the 1st sacral foramen) and → **BL-28** (slightly below and medial to the PSIS at the level of the 2nd sacral foramen).

Needling

Vertically 0.5–1 cun

Actions/Indications

- Tonifies the Small Intestine Qi
- Drains Dampness and Damp-Heat
- Regulates the water passages

Special features

Back-*shu* point of the Small Intestine


Sacral foramen
BL-27
1.5 cun
1
2
3
4
Posterior superior iliac spine
BL-28
Midline


Posterior superior iliac spine
1.5 cun
BL-27
45°
3 cun
BL-28
Superior end of the rima ani


Ilium
Iliosacral joints
PSIS
Sacrum


Posterior superior finger on the PSIS
BL-27
BL-28

Ch04.7a-F10028.qxd 2/23/08 3:54 PM Page 278

BL-28 *Bladder* Shu PANGGUANGSHU

Location

1.5 cun lateral to the posterior midline, on the level of the second sacral foramen.

How to find

Quick method: Locate the posterior superior iliac spine (PSIS → 3.4.3): from the rima ani, palpate 3 cun (1 handbreadth) in a superior and lateral direction at a 45° angle, until you can feel a distinct bony ridge (often superficially visible by a dimple). **BL-28** is located slightly inferiorly and medially to the PSIS, 1.5 cun lateral to the midline on the level of the 2nd sacral foramen. For more detail on orientation in the lumbar and sacral region → 3.4.3, 3.4.4.

Located on the same level are → **BL-32** (over the 2nd sacral foramen) and → **BL-53** (3 cun lateral to the midline). → **BL-27** is located slightly superiorly and medially to the PSIS on the level of the 1st sacral foramen.

Needling

Vertically 0.5–1.5 cun. For local disorders, slightly oblique insertion towards the iliosacral joint.

Actions/Indications

- Regulates the Bladder and the Lower Burner, clears Damp-Heat from the Lower Burner, removes stagnation and transforms masses
- Benefits the lumbar region and the legs

Special features

Back-*shu* point of the Bladder


Fingers on the PSIS
BL-27
BL-28


Sacral foramen
1.5 cun
Posterior superior iliac spine
1
2
3
4
BL-28
Midline


Posterior superior iliac spine
1.5 cun
BL-27
45°
3 cun
BL-28
Superior end of the rima ani


Ilium
Iliosacral joints
PSIS
Sacrum

Mid Spine Shu ZHONGLÜSHU BL-29


1.5 cun
Level of the iliac crests
Spinous process L4
Spinous process L5
Sacral foramina
BL-29
Midline


L4
Tuffier's line
Iliac crest
L5
PSIS
Lumbosacral junction
Sacrum


Iliosacral joints
Ilium
Sacrum


Sacral foramen 1
2
3
4
BL-31
BL-32
BL-33
BL-34

Location

1.5 cun lateral to the posterior midline, on the level of the 3rd sacral foramen.

How to find

For more detail on orientation in the lumbar and sacral region, see → 3.4.3, 3.4.4. First of all find L5. The next palpable structure in an inferior direction is the most superior sacral spinous process. Palpate in an inferior direction for two further sacral processes and locate the 3rd sacral foramen in a depression less than 1 cun lateral to the 3rd process. **BL-29** is located on the same level (3rd sacral foramen) and 1.5 cun lateral to the midline. Also located on this level is → **BL-33** (over the 3rd sacral foramen).

Needling

Vertically 0.5–1.5 cun

Actions/Indications

- Strengthens the lower back and the Kidneys
- Expels Cold
- Regulates the Lower Burner and stops diarrhoea


52
23
4
Ex-B-5
Ex-B-5
Ex-B-7
25
3
Ex-B-6
Ex-B-8
54
30
Ex-B-11
36
Du mai
Bladder channel, lateral branch
Bladder channel, medial branch

BL-30 *White Ring* Shu BAI HUAN SHU

Location

1.5 cun lateral to the posterior midline, on the level of the 4th sacral foramen.

How to find

For more detail on orientation in the lumbar and sacral region, see → 3.4.3, 3.4.4. First, find L5. The next palpable structure in an inferior direction is the most superior sacral spinous process. Palpate in an inferior direction for three further sacral processes and locate the 4th sacral foramen in a depression less than 1 cun lateral to the 4th process. **BL-30** is located on the level of the 4th foramen, 1.5 cun lateral to the midline.

Located on the same level are → **BL-34** (over the 4th sacral foramen) and → **BL-54** (3 cun lateral to the midline).

Needling

Vertically 0.5–1.5 cun

Actions/Indications

- Strengthens the lower back and the knees
- Eliminates Damp-Heat from the Lower Burner
- Regulates menstruation


1.5 cun
Level of the iliac crests
Spinous process L4
Spinous process L5
Sacral foramina
BL-30
Midline


52
23
4
Ex-B-5
Ex-B-5
Ex-B-7
Ex-B-6
25
3
Ex-B-8
54
30
Ex-B-11
36
Du mai
Bladder channel, lateral branch
Bladder channel, medial branch


Sacral foramen 1
Sacral foramen 2
Sacral foramen 3
Sacral foramen 4


Ilium
Iliosacral joints
PSIS
Sacrum


Sacral foramina
BL-54
Midline

Eight Liao BALIAO BL 31 – BL 34



These points are described together because of their similar actions and indications.

BL-31 (*shangliao*) 'Upper Crevice', 1st sacral foramen
BL-32 (*ciliao*) 'Second Crevice', 2nd sacral foramen
BL-33 (*zhongliao*) 'Middle Crevice', 3rd sacral foramen
BL-34 (*xialiao*) 'Lower Crevice', 4th sacral foramen

Location

BL-31: Over the 1st sacral foramen
BL-32: Over the 2nd sacral foramen
BL-33: Over the 3rd sacral foramen
BL-34: Over the 4th sacral foramen

How to find

For more detail on orientation in the lumbar and sacral region, → 3.4.3, 3.4.4. First, locate L5. The next palpable structure in an inferior direction is the most superior sacral spinous process. Palpate in a lateral direction on the level of the sacral processes for the depressions of the sacral foramina. **Or:** Locate the 4th sacral foramen on the level of the superior end of the rima ani (sometimes a bit more superiorly or inferiorly). Place the little finger on the 4th foramen, then the ring, middle and index fingers on a slightly V-shaped line in a superior direction, palpating for the depressions of the sacral foramina. With the fingers in this position, the index finger will be resting on the 1st foramen (**BL-31**), the middle finger on the 2nd foramen (**BL-32**), the ring finger on the 3rd foramen (**BL-33**) and the little finger on the 4th foramen (**BL-34**). Located on the same level as **BL-31–BL-34** are the points → **BL-27–BL-30** on the inner branch of the BL channel (1.5 cun lateral to the midline) as well as → **BL-53** (on the level of **BL-32**) and → **BL-54** (on the level of **BL-34**), both 3 cun lateral to the midline. Also on the level of **BL-34** is → **Ex-B-11** (3.5 cun lateral to the midline).

Needling

Vertically 0.7–1.5 cun. Caution: Pregnancy (especially reducing needling techniques are contraindicated); exception: to promote labour.

Actions/Indications

- Regulates the Lower Burner, promotes urination (all eight points) (**BL-32** and **BL-33** have the strongest action in cases of urinary disorders, while **BL-34** has the strongest action in cases of genital disorders)
- Strengthens the Kidneys and Essence (*jing*)
- Benefits the Intestines (**BL-34** has the strongest action in cases of intestinal disorders)
- Promotes labour (for example, use **BL-32** with electro-acupuncture)
- Benefits the lumbar region (**BL-32** and **BL-33** have the strongest action)

Special features

According to some authors, meeting point with the G.B. channel. Clinically, **BL-32** is the most commonly used point owing to its widest range of indications. Electro-acupuncture at **BL-32** is useful for alleviating pain during labour: after needling this point, bend the handle of the needle in a superior direction at a 90° angle and tape it to the skin. Now attach the electro-stimulation. This method allows the woman to lie down if desired.
Moxibustion of the *baliao* is indicated for difficult urination or defaecation due to Kidney deficiency in elderly people.

BL-35 *Meeting of Yang* HUIYANG

Location

0.5 cun lateral to the posterior midline, on the level of the tip of the coccyx.

How to find

Locate the coccyx superior to the anus. In contrast to the sacrum, the coccyx is movable. **BL-35** is located 0.5 cun lateral to the midline on the level of the tip of the coccyx.
→ **Du-2** is located on the midline, on the level of the sacral hiatus (→ 3.4.4) and superior to **BL-35** and the tip of the coccyx.

Needling

Vertically 1–1.5 cun

Actions/Indications

- Clears Damp-Heat from the Lower Burner
- Treats haemorrhoids and rectal prolapse
- Benefits the coccyx

Special features

Especially in patients with a weakened immune system, this point should be needled only if strictly necessary and after using a disinfecting wipe three times.


Midline
Anus
0.5 cun
Level of the tip of the coccyx
Coccyx
BL-35


52
23
4
Ex-B-5
Ex-B-5
Ex-B-7
25
3
Ex-B-6
Ex-B-8
54
30
Ex-B-11
2
1
36
Du mai
Bladder channel, lateral branch
Bladder channel, medial branch


Fingers on the 1st to 4th sacral foramina
Sacral hiatus
Du-2

Hold and Support CHENGFU BL-36


BL-36
BL-40
Centre of the popliteal crease

Location

In the gluteal crease, superior to the midpoint of the popliteal crease (→ **BL-40**).

How to find

Locate the midpoint of the popliteal crease (in obese patients, use bony/muscular structures to find the midpoint). **BL-36** is located directly vertically above the midpoint of the popliteal crease, in the gluteal crease at the transition between the buttocks and the posterior aspect of the thigh (palpate for a depression).

Needling

Vertically 1–2 cun

Actions/Indications

- Opens the channel, alleviates pain
- Relaxes the tendons
- Regulates the Lower Burner and treats haemorrhoids


Highest prominence of the greater trochanter
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
cun
G.B.-30
BL-36
6 cun
BL-37
G.B.-31
G.B.-32
G.B.-33
BL-40
BL-39
BL-55
G.B.34
Centre of the popliteal crease
1
2

BL-37 *Gate of Abundance* YINMEN

Location

6 cun distal to → **BL-36** (gluteal crease), on a line connecting → **BL-36** and → **BL-40** (in the popliteal crease), in a gap in the musculature.

How to find

First, locate → **BL-36** in the centre of the gluteal crease and, from there, palpate 6 cun along the posterior aspect of the thigh in an inferior direction towards the centre of the popliteal crease (→ **BL-40**). This is the location of **BL-37**, which in slim patients can be located where the long head of the biceps femoris muscle and the semitendinosus muscle converge (usually 8 cun superior to the centre of the popliteal crease. **Or:** Spreading hands technique (→ 2.3.3 or elastic tape): Place the little fingers on the centre of the popliteal crease (→ **BL-40**) and the centre of the gluteal crease (→ **BL-36**). Locate **BL-37** 1–2 cun proximal to the midpoint of the distance, in a depression between the two muscle bellies.

Needling

Vertically 0.5–2 cun

Actions/Indications

- Relaxes the tendons
- Opens the channel and *luo* vessels
- Benefits the lower back


BL-36
Biceps femoris
BL-37
Semi-tendinosus
6 cun
ca. 8 cun
BL-40
Centre of the popliteal crease




Popliteal crease
BL-40


Highest prominence of the greater trochanter
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
cun
G.B-30
BL-36
6 cun
BL-37
G.B.-31
G.B.-32
G.B.-33
BL-40
BL-39
BL-55
G.B.34
Centre of the popliteal crease
1
2

Floating Cleft FUXI BL-38





Location

On the laterodorsal aspect of the knee, 1 cun superior and lateral to the centre of the popliteal crease (→ **BL-40**), medial to the biceps femoris muscle, or 1 cun proximal to → **BL-39**.

How to find

To locate the popliteal crease, ask the patient to flex their knee slightly and palpate for the knee joint space. By flexing the knee against resistance, the tendon of the biceps femoris muscle will become more pronounced and visible. Locate **BL-38** 1 cun superior to the knee joint on the medial border of the tendon.
→ **BL-39** is located 1 cun distal to **BL-38** on the level of the popliteal crease.

Needling

Vertically 1–2 cun

Actions/Indications

- Relaxes the muscles and tendons
- Opens the channel and *luo* vessels
- Clears Heat (from the Small Intestine)

BL-39 *Outside of the Crook* WEIYANG

Location

At the lateral end of the popliteal crease, on the medial side of the tendon of the long head of the biceps femoris muscle, 1 cun lateral to → **BL-40** (in the centre of the popliteal crease).

How to find

This point is best located with the patient's knee slightly flexed. Find the midpoint of the popliteal crease (→ **BL-40**) and locate **BL-39** approximately 1 cun lateral in a depression medial to the tendon of the long head of the biceps femoris muscle. Located on the same level is → **BL-40** at the centre of the popliteal crease.

Needling

Vertically 0.5–1.5 cun. Caution: N. fibularis communis.

Actions/Indications

- Harmonises the Triple Burner and regulates the water passages
- Opens the channel and the *luo* vessels, alleviates pain

Special features

Lower *he*-sea point of the Triple Burner


1 cun
Popliteal crease
BL-40
BL-39


Highest prominence of the greater trochanter
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
cun
G.B.-30
BL-36
6 cun
BL-37
G.B.-31
G.B.-32
G.B.-33
Bl 39
Bl-40
Popliteal crease
1
2
BL-55
G.B.-34



Middle of the Crook WEIZHONG BL-40







Location

In the centre of the popliteal crease, between the tendons of the biceps femoris and semitendinosus muscles.

How to find

This point is best located with the patient's knee slightly flexed. Locate the centre of the popliteal crease (a pulse may be palpable) and there locate **BL-40**.
Located on the same level are → **BL-39** (1 cun laterally), → **KID-10** (more medially, between the tendons of the semimembranosus and semitendinosus muscles) and → **LIV-8** (more medially, anterior to the tendons of the semimembranosus and semitendinosus muscles).

Needling

Vertically 0.5–1.5 cun. Caution: Popliteal nerve, artery and vein lie deep to this point. Use moxibustion with caution (contraindicated according to some authors). To clear Heat and eliminate stasis: bleed the superficial veins, possibly followed by brief cupping. Caution: Only use for excess conditions and in constitutionally robust patients. **BL-40** is also indicated as a distal point for the lower back: needle with the patient standing (for safety and balance, use a treatment couch or chair as a support for the hands) and ask them to move their lower back gently while manipulating the needle (only short needle retention). When needling this point with the patient in a prone position, place a supporting roll or pillow under the ankles to relax the popliteal crease.

Actions/Indications

- Clears (summer) Heat, stops vomiting and diarrhoea
- Cools the Blood
- Benefits the lower back and knees, opens the channel and *luo* vessels, alleviates pain

Special features

He-sea point, Earth point, lower *he*-sea point of the Bladder, Ma Dan Yang Heavenly Star point, Gao Wu command point of the lumbar region. Important distal point for the lower back, point with a wide range of indications.

BL-41 Attached Branch FUFEN

Location

3 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 2nd thoracic vertebra (T2).

How to find

After locating the spinous process of C7 (➞ 3.4.1), count down 2 spinous processes to the lower border of the spinous process of T2. Locate **BL-41** 3 cun lateral from the midline (with the shoulders relaxed and the arms hanging loosely down, 3 cun corresponds on this level to the distance from the midline to the medial border of the scapula). Note: From **BL-41** to ➞ **BL-54**, all points on the BL channel are located on its outer branch.

Located on the same level are a point of ➞ **Ex-B-2** (0.5 cun lateral to the midline), ➞ **BL-12** (1.5 cun lateral to the midline) and ➞ **S.I.-13** (more laterally, on the scapula).

Needling

Obliquely 0.3–0.5 cun. Caution: Pneumothorax.

Actions/Indications

- Expels pathogenic factors such as Wind and Cold
- Opens the channel and the *luo* vessels, alleviates pain

Special features

Meeting point with the S.I. channel


Spinous process C7
Medial border of the scapula
Base of the scapular spine
Spinous process T3
BL-41
Spinous process T3
Spinous process T7
Inferior angle
3 cun
Spinous process T12
Bladder channel, lateral branch
Midline


S.I.-15
14
S.I.-12
11
13
S.I.-10
42
13
12
44
15
11
46
17
9
Ex B 3
47
18
8


Spinous process T2
Spinous process T3
BL-12


Spinous process C7
Spinous process C1
S.I-13


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2 (parts)

Door of the Corporeal Soul POHU BL-42


Spinous process C7
Medial border of the scapula
Base of the scapular spine
Spinous process T3
BL-42
Spinous process T7
Inferior angle
3 cun
Spinous process T12
Bladder channel, lateral branch
Midline


Extension and flexion of the head
2 fingers on the spinous processes of C6 and 7
G.B.-21
S.I.-15
Du-14


Spinous process C7
Spinous process T3
Du-12


Spinous process T3
BL-13

Location

3 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 3rd thoracic vertebra (T3).

How to find

After locating the spinous process of C7 (→ 3.4.1), count down 3 spinous processes to the lower border of the spinous process of T3. Located on this level and 3 cun lateral to the midline is **BL-42.**
Or: With the patient seated and their shoulders in a relaxed position, the spinous process of T3 is generally on the level of the medial end of the scapular spine, an easily palpable structure (→ 3.4.2). Locate **BL-42** on the level of the lower border of the spinous process of T3, 3 cun lateral to the midline. With the patient's shoulders relaxed, 3 cun corresponds on this level to the distance from the midline to the medial border of the scapula.
Located on the same level are → **Du-12** (on the midline), a point of → **Ex-B-2** (0.5 cun lateral to the midline) and → **BL-13** (1.5 cun lateral to the midline).

Needling

Obliquely 0.3–0.5 cun. Caution: Pneumothorax.

Actions/Indications

- Tonifies and nourishes the Lung
- Alleviates wheezing and coughing, calms the corporeal soul (*po*)
- Opens the channel and alleviates pain
- Clears Heat from the Lung

BL-43 *Vital Region* Shu GAOHUANG

Location

3 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 4th thoracic vertebra (T4).

How to find

After locating the spinous process of C7 (→ 3.4.1), count down 4 spinous processes to the lower border of the spinous process of T4. Located on this level and 3 cun lateral to the midline is **BL-43. Or:** Locate **BL-43** by using the spinous process of T3 (generally, on the level of the easily palpable medial end of the scapular spine, 3.4.2) as a reference point.

Located on the same level are a point of → **Ex-B-2** (0.5 cun lateral to the midline) and → **BL-14** (1.5 cun lateral to the midline).

Needling

Obliquely 0.3–0.5 cun. Moxibustion is often used on this point. Caution: Pneumothorax.

Actions/Indications

- Tonifies and nourishes the five *zang*-Organs: Lung, Heart, Kidneys, Stomach and Spleen
- Nourishes Yin, clears Heat
- Calms the *shen*
- Strengthens the Original Qi (*yuan qi*)
- Eliminates Phlegm

Special features

Important point for deficiency syndromes (classic indication)


Spinous process C7
Spinous process T3
Spinous process T4
BL-43
Medial border of the scapula
Base of the scapular spine
Spinous process T7
Inferior angle
3 cun
Spinous process T12
Bladder channel, lateral branch
Midline


S.I.-15
14
S.I.-12
11
13
S.I.-10
42
13
12
44
15
11
46
17
9
Ex B-3
47
18
8


Spinous process T3
Spinous process T4
BL-14


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2 (parts)

Spirit Hall SHENTANG BL-44


Spinous process C7
Medial border of the scapula
Base of the scapular spine
Spinous process T3
Spinous process T5
BL-44
Spinous process T7
Inferior angle
3 cun
Spinous process T12
Bladder channel, lateral branch
Midline


Extension and flexion of the head
2 fingers on the spinous processes of C6 and 7
G.B.-21
S.I.-15
Du-14


Spinous process T5
Du-11
Spinous process T7
Inferior angle


Spinous process T3
Spinous process T5
BL-15

Location

3 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 5th thoracic vertebra (T5).

How to find

After locating the spinous process of C7 (→ 3.4.1), count down 5 spinous processes to the lower border of the spinous process of T5. Located on this level and 3 cun lateral to the midline is **BL-44. Or:** With the patient seated and their shoulders in a relaxed position, the spinous process of T3 is generally on the level of the medial end of the scapular spine, an easily palpable structure (→ 3.4.2). Locate **BL-44** by counting down to the level of the lower border of the spinous process of T5 and measure 3 cun lateral to the midline.

Located on the same level are → **Du-11** (on the midline), a point of → **Ex-B-2** (0.5 cun lateral to the midline) and → **BL-15** (1.5 cun lateral to the midline).

Needling

Obliquely 0.3–0.8 cun. Caution: Pneumothorax.

Actions/Indications

- Regulates the Upper Burner, unbinds the chest
- Opens the channel and alleviates pain

BL-45 *Cry of Pain* YIXI

Location

3 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 6th thoracic vertebra (T6).

How to find

After locating the spinous process of C7 (→ 3.4.1), count down 6 spinous processes to the lower border of the spinous process of T6. Located on this level and 3 cun lateral to the midline is **BL-45. Or:** With the patient seated and their shoulders in a relaxed position, the spinous process of T7 is generally on the level of the inferior angle of the scapula (→ 3.4.2). Locate **BL-45** on the level of the spinous process of T6, 3 cun lateral to the midline. Located on the same level are → **Du-10** (on the midline), a point of → **Ex-B-2** (0.5 cun lateral to the midline) and → **BL-16** (1.5 cun lateral to the midline).

Needling

Obliquely 0.3–0.8 cun. Caution: Pneumothorax.

Actions/Indications

- Expels pathogenic factors, especially Wind and Heat
- Descends the Lung Qi and unbinds the chest
- Strengthens the Qi and Blood and alleviates pain


Spinous process C7
Spinous process T3
Medial border of the scapula
Base of the scapular spine
Spinous process T6
BL-45
Spinous process T7
Inferior angle
3 cun
Spinous process T12
Bladder channel, lateral branch
Midline


S.I.-15
14
S.I.-12
11
13
S.I.-10
42
13
12
44
15
11
6
46
17
9
Ex B 3
47
18
8


Du-10
Spinous process T7
Inferior angle


Spinous process T6
Spinous process T7
BL-16
Inferior angle


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2 (parts)

Diaphragm's Gate GEGUAN BL-46


Spinous process C7
Medial border of the scapula
Base of the scapular spine
Spinous process T3
Spinous process T7
BL-46
Inferior angle
3 cun
Spinous process T12
Bladder channel, lateral branch
Midline


Extension and flexion of the head
2 fingers on the spinous processes of C6 and 7
G.B.-21
S.I.-15
Du-14


Spinous process T7
Du-9


Spinous process T7
BL-17
Inferior angle

Location

3 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 7th thoracic vertebra (T7).

How to find

With the patient standing and their shoulders in a relaxed position, the spinous process of T7 is generally on the level of the inferior angle of the scapula (→ 3.4.2). Locate **BL-46** on the level of the spinous process of T7, 3 cun lateral to the midline. **Or:** With the patient seated, the spinous process of T3 is generally on the level of the medial end of the scapular spine, an easily palpable bony protrusion at the medial border of the scapula (→ 3.4.2). From there, count down 4 spinous processes to the spinous process of T7. Locate **BL-46** on this level, 3 cun lateral to the midline. **Or:** Find the spinous process of C7 (→ 3.4.1). From there, count down 7 spinous processes in an inferior direction to the spinous process of T7. Locate **BL-46** on this level, 3 cun lateral to the midline.

Located on the same level are → **Du-9** (on the midline), a point of → **Ex-B-2** (0.5 cun lateral to the midline) and → **BL-17** (1.5 cun lateral to the midline).

Needling

Obliquely 0.3–0.8 cun. Caution: Pneumothorax.

Actions/Indications

- Regulates the diaphragm and descends counterflow Qi
- Harmonises the Middle Burner
- Opens the channel and alleviates pain

BL-47 *Gate of the Ethereal Soul* HUNMEN

Location

3 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 9th thoracic vertebra (T9).

How to find

In a sitting position with the arms hanging down, the spinous process of T7 is generally on the level of the inferior angle of the scapula (➞ 3.4.2). From there, count down 2 processes to the lower border of the spinous process of T9. **BL-47** is located 3 cun lateral to this point. **Or:** Locate the spinous process of C7 (➞ 3.4.1). From there, count down 9 processes to the lower border of the spinous process of T9 and locate **BL-47** 3 cun lateral to it. Located on the same level are ➞ **Du-8** (on the midline), a point of ➞ **Ex-B-2** (0.5 cun lateral to the midline) and ➞ **BL-18** (1.5 cun lateral to the midline).

Needling

Obliquely 0.3–0.5 cun. Caution: Pneumothorax.

Actions/Indications

- Spreads the Liver Qi
- Harmonises the Spleen and the Stomach
- Relaxes the tendons


Spinous process C7
Medial border of the scapula
Base of the scapular spine
Spinous process T3
3 cun
Spinous process T7
Inferior angle
Spinous process T9
BL-47
Spinous process T12
Bladder channel, lateral branch
Midline


S.I.-15
14
S.I.-12
11
13
S.I.-10
42
13
12
44
15
11
46
17
9
Ex B-3
47
18
8


Spinous process T9
Spinous process T10
Du-8


Spinous process T7
Inferior angle
Spinous process T9
BL-18


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2 (parts)


Extension and flexion of the head
2 fingers on the spinous processes of C6 and 7
G.B.-21
S.I.-15
Du-14

Yang's Key Link YANGGANG BL-48


Spinous process C7
Medial border of the scapula
Base of the scapular spine
Spinous process T3
3 cun
Spinous process T7
Inferior angle
Spinous process T10
BL-48
Spinous process T12
Bladder channel, lateral branch
Midline


BL-23
Du-4
BL-52
Spinous process L 4
Level of the iliac crests
Tuffier's line
Du-3


Spinous process T10
Spinous process T11
Du-7


1.5 cun
1.5 cun
Inferior angle
Spinous process T7
Spinous process T10
BL-19

Location

3 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 10th thoracic vertebra (T10).

How to find

In a sitting position with the arms hanging down, the spinous process of T7 is generally on the level of the inferior angle of the scapula (→ 3.4.2). From there, count down 3 processes to the lower border of the spinous process of T10. **BL-48** is located 3 cun lateral to this point. **Or:** Locate the spinous process of C7 (→ 3.4.1). From there, count down 10 processes to the lower border of the spinous process of T10 and locate **BL-48** 3 cun lateral to it.

Located on the same level are → **Du-7** (on the midline), a point of → **Ex-B-2** (0.5 cun lateral to the midline) and → **BL-19** (1.5 cun lateral to the midline).

Needling

Obliquely 0.3–0.8 cun. Caution: Pneumothorax.

Actions/Indications

- Regulates the Gall Bladder
- Clears Damp-Heat
- Harmonises the Middle Burner

BL-49 *Abode of Thought* YISHE

Location

3 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 11th thoracic vertebra (T11).

How to find

In a sitting position with the arms hanging down, the spinous process of T7 is generally on the level of the inferior angle of the scapula (→ 3.4.2). From there, count down 4 spinous processes to the lower border of the spinous process of T11 and locate **BL-49** 3 cun lateral to this point. **Or:** From the articulation of the most inferior rib, palpate in a superior direction to T11. **Or:** Use the lumbar spine for reference (→ 3.4.3).

Located on the same level are → **Du-6** (on the midline), a point of → **Ex-B-2** (0.5 cun lateral to the midline) and → **BL-20** (1.5 cun lateral to the midline).

Needling

Obliquely 0.3–0.8 cun. Caution: Pneumothorax.

Actions/Indications

- Clears Damp-Heat
- Harmonises the Spleen and the Stomach


Spinous process C7
Medial border of the scapula
Base of the scapular spine
Spinous process T3
3 cun
Spinous process T7
Inferior angle
BL-49
Spinous process T11
Spinous process T12
Bladder channel, lateral branch
Midline


46
17
9
Ex B-3
47
18
8
49
20
6
Ex B-4
52
23
4
Ex B-5
Ex B-5
Ex B-7
25
3
Ex B-6


Spinous process T11
Spinous process T12
Du-6


Spinous process T11
Spinous process T12
BL-20
Bladder channel


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2 (parts)

Stomach Granary WEICANG **BL-50**


Spinous process C7
Medial border of the scapula
Base of the scapular spine
Spinous process T3
3 cun
Spinous process T7
Inferior angle
Spinous process T12
BL-50
Bladder channel, lateral branch
Midline


Extension and flexion of the head
2 fingers on the spinous processes of C6 and 7
G.B.-21
S.I.-15
Du-14


BL-23
Du-4
BL-52
Spinous process L 4
Level of the iliac crests
Tuffier's line
Du-3


Spinous process T12
BL-21
Bladder channel, lateral branch

Location

3 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 12th thoracic vertebra (T12).

How to find

In a sitting position with the arms hanging down, the spinous process of T7 is generally on the level of the inferior angle of the scapula (→ 3.4.2). From there, count down 5 spinous processes to the lower border of the spinous process of the T12 and locate **BL-50** 3 cun lateral to this point. **Or:** Locate the articulation of the most inferior rib with T12 and palpate 3 cun in a lateral direction for **BL-50. Or:** Orientation from the lumbar spine (→ 3.4.3). Located on the same level are a point of → **Ex-B-2** (0.5 cun lateral to the midline) and → **BL-21** (1.5 cun lateral to the midline).

Needling

Obliquely 0.3–0.8 cun. Caution: Pneumothorax, especially with asthenic patients or patients with emphysema.

Actions/Indications

- Harmonises the Middle Burner
- Opens the channel

BL-51 *Vitals Gate* HUANGMEN

Location

3 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 1st lumbar vertebra (L1).

How to find

For orientation in the lumbar region (→ 3.4.3), first, the Tuffier's line: place both hands superior or lateral to the highest points of the iliac crest, joining the thumbs in the middle above the spine. In most cases, this line intersects with the spinous process of L4 (note: this varies depending on the patient's position → 3.4.). From there, count upward to the lower border of the spinous process of L1 and, on this level, locate **BL-51** 3 cun in a lateral direction. **Or:** With the patient seated and their arms hanging down in a relaxed way, the spinous process of T7 is generally on the level of the inferior angle of the scapula (→ 3.4.2). From there, count down six spinous processes and locate **BL-51** 3 cun lateral to the spinous process of L1.

Located on the same level are → **Du-5** (on the midline), a point of → **Ex-B-2** (0.5 cun lateral to the midline), → **BL-22** (1.5 cun lateral to the midline) and → **Ex-B-4** (→ 3.5 cun lateral to the midline).

Needling

Vertically or obliquely 0.5–1 cun. Caution: Kidneys.

Actions/Indications

- Moves the Qi and resolves stagnation
- Benefits the breasts

Special features

Distal point for disorders of the breasts


Medial border of the scapula
Spinous process L1
BL-51
Spinous process L2
Spinous process L3
Level of the iliac crests
Spinous process L4
Spinous process L5
3 cun


46
17
9
8
Ex B-3
9
47
18
8
10
11
49
20
6
12
Ex-B-4
52
23
4
Ex-B-5
Ex-B-5
Ex-B-7
25
3
Ex-B-6


Spinous process L1
Ex-B-4


Spinous process L1
Du-5
Spinous process L2
Spinous process L3


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2
(parts)


Spinous process L1
BL-22
Spinous process L2

Residence of the Will ZHISHI BL-52


Medial border of the scapula
Spinous process L1
Spinous process L2
BL-52
Spinous process L3
Level of the iliac crests
Spinous process L4
Spinous process L5
3 cun


BL-23
Du-4
BL-52
Spinous process L4
Level of the iliac crests
Tuffier's line
Du-3


Spinous process L2
Du-4
Spinous process L3
Level of the iliac crests (dependent on patient position)
Spinous process L4


Spinous process L1
BL-22
Spinous process L2
BL-23
Spinous process L3
BL-24
Level of the iliac crests
Spinous process L4

Location

3 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 2nd lumbar vertebra (L2).

How to find

For orientation in the lumbar region (→ 3.4.3), first, locate the Tuffier's line: place both hands superior or lateral to the highest points of the iliac crest, joining the thumbs in the middle above the spine. In most cases, this line intersects with the spinous process of L4 (note: this varies depending on the patient's position → 3.4.). From there, count upward to the lower border of the spinous process of L2 and, on this level, locate **BL-52** 3 cun in a lateral direction.

Located on the same level are → **Du-4** (on the midline), a point of → **Ex-B-2** (0.5 cun lateral to the midline) and → **BL-23** (1.5 cun lateral to the midline).

Needling

Vertically or obliquely 0.5–1 cun. Caution: Kidneys.

Actions/Indications

- Tonifies the Kidneys and Essence (*jing*), regulates urination
- Benefits the lumbar region

BL-53 *Bladder Vitals* BAOHUANG

Location

3 cun lateral to the posterior midline, on the level of the 2nd sacral foramen.

How to find

For details on orientation in the lumbar and sacral region, → 3.4.3, 3.4.4. First, locate L5. The next palpable bony structure inferior to L5 is the highest process of the medial sacral crest. Palpate inferiorly for the 2nd process and locate the 2nd sacral foramen slightly less than 1 cun lateral to the process. Next, locate **BL-53** 3 cun lateral to the midline on the level of the 2nd foramen. **Or:** Use the sacral foramina as a reference point (→ 3.4.4). **BL-53** is located on the level of the 2nd foramen, 3 cun lateral to the midline.

Located on the same level are → **BL-32** (over the 2nd sacral foramen) and → **BL-28** (1.5 cun lateral to the midline).

Needling

Vertically or obliquely 1–1.5 cun

Actions/Indications

- Benefits the lumbar region, opens the channel and alleviates pain
- Regulates the Lower Burner


3 cun
Level of the iliac crests
Spinous process L4
Spinous process L5
Sacral foramina
2
BL-53
Midline


46
17
9
Ex-B-3
47
18
8
10
11
49
20
6
12
Ex-B-4
52
23
4
Ex-B-5
Ex-B-5
Ex-B-7
25
3
Ex-B-6


Sacral foramen 1
2
3
4
BL-31
BL-32
BL-33
BL-34


Posterior superior iliac spine
BL-28
1
2
3
4

Order's Limit ZHIBIAN **BL-54**


3 cun
Level of the iliac crests
Spinous process L4
Spinous process L5
Sacral foramina
BL-54
Midline


BL-23
Du-4
BL-52
Level of the iliac crests
Spinous process L4
Tuffier's line
Du-3


Sacral foramen 1
2
3
4
BL-31
BL-32
BL-33
BL-34


Sacral foramina
BL-30

Location

3 cun lateral to the posterior midline, on the level of the 4th sacral foramen, approximately at the centre of the buttock.

How to find

For details on orientation in the lumbar and sacral region, see → 3.4.3, 3.4.4. First, locate L5. Inferior to it, the next palpable bony structure is the highest point on the medial sacral crest (= sacral spinous processes). Palpate downward for 3 more bony elevations and locate the depression of the 4th sacral foramen less than 1 cun lateral to it. This is on the level of **BL-54**, located 3 cun lateral to the midline. For further reference: The 4th sacral foramen is mostly level with the superior end of the rima ani. Located on the same level are → **BL-34** (over the 4th sacral foramen) and → **BL-30** (1.5 cun lateral to the midline).

Needling

Vertically 1.5–2 cun or 2–3 cun in the direction of the anus or the genital region, depending on the indication.

Actions/Indications

- Opens the channel and *luo* vessels, eliminates stagnation
- Regulates urination
- Eliminates haemorrhoids

Special features

Important local point

BL-55 *Confluence of Yang* **HEYANG**

Location

2 cun inferior to the midpoint of the popliteal crease, in a depression between the two bellies of the gastrocnemius muscle.

How to find

Locate the popliteal crease by flexing the knee. In slim patients, palpate for the joint space. From the centre of the popliteal crease, palpate 2 cun in an inferior direction and locate **BL-55** in a depression between the two bellies of the gastrocnemius muscle.

Needling

Vertically or obliquely 1–1.5 cun

Actions/Indications

- Opens the channel, alleviates pain (also in the urogenital region)
- Stops uterine bleeding


Vertical line through the centre of the popliteal crease
BL-40
2 cun
BL-55
Muscle bellies of the gastrocnemius


BL-36
6
BL-37
7
BL-38
1
Popliteal crease
BL-40
BL-39
2
BL-55
1/2
1/2
1/2
BL-56
BL-57
BL-58
1
1/2
BL-59
3
BL-60
1,5
BL-61
cun
Gastro-cnemius
Long head of the biceps femoris
BL-38
BL-40
BL-39
BL-55
Popliteal crease
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
BL-56
BL-57
BL-58
BL-59
BL-60
Lateral malleolus


Popliteal crease
BL-40

Support the Sinews CHENGJIN BL-56


Popliteal crease
BL-40
5 cun
BL-56
3 cun
BL-57
8 cun
Highest prominence of the lateral malleolus



Location

5 cun inferior to the midpoint of the popliteal crease, between the two bellies of the gastrocnemius muscle.

How to find

Locate the popliteal crease by flexing the knee. In slim patients, palpate for the joint space. **BL-56** is located 5 cun distal to the popliteal crease, in a depression between the two bellies of the gastrocnemius muscle.

Needling

Vertically or obliquely 1–1.5 cun

Actions/Indications

- Relaxes the muscles and tendons
- Opens the channel
- Eliminates haemorrhoids

BL-57 *Supporting Mountain* CHENGSHAN

Location

In the middle of the calf, between the two heads of the gastrocnemius muscle, on a line connecting → **BL-40** and → **BL-60**, approximately 8 cun distal to → **BL-40**.

How to find

Slide along the dorsal aspect of the Achilles tendon in a superior direction until you can feel the depression between the two bellies of the gastrocnemius muscle. This will become more defined when the patient's muscles are flexed. **Or:** Spreading hands technique (→ 2.3.3): Place the little fingers on → **BL-40** (centre of the popliteal crease) and → **BL-60** (depression between the Achilles tendon and the highest prominence of the lateral malleolus). The midpoint of this distance, where the thumbs meet, marks the location of **BL-57**.

Located on the same level on the anterolateral aspect of the lower leg are → **ST-38** (1 finger-width lateral to the tibia) and → **ST-40** (2 fingerbreadths lateral to the tibia).

Needling

Vertically or obliquely 1–1.5 cun

Actions/Indications

- Relaxes the muscles and tendons, opens the channel
- Eliminates haemorrhoids (pathway of the Bladder divergent channel)

Special features

Ma Dan Yang Heavenly Star point. Important local point with distal effect on the lumbar and anal region.


BL-40
Gastro-
cnemius
8 cun
BL-57
8 cun
BL-60
Standing on
tiptoes


17
18
19
cun
G.B.-33
BL-40
BL-39
Popliteal
crease
BL-55
G.B.-34
1
2
3
4
BL-56
5
6
7
8
G.B.-35
BL-57
G.B.-36
9
BL-58
10
G.B.-37
11
G.B.-38
12
G.B.-39
13
BL-59
14
15
16
cun
Highest
prominence
of the lateral
malleolus
BL-60
G.B.-40
G.B.-42
G.B.-44


BL-40
BL-57
BL-60

Soaring Upward FEIYANG **BL-58**


BL-40
8 cun
1 cun
1 cun
BL-57
BL-58
8 cun
BL-60
Highest prominence of the medial malleolus

Location

1 cun distal and 1 cun lateral to ➞ **BL-57** or 7 cun proximal to ➞ **BL-60**, at the posterior border of the fibula and at the lower border of the gastrocnemius muscle.

How to find

First, locate ➞ **BL-57** (in the centre of the calf, between the two bellies of the gastrocnemius muscle). From ➞ **BL-57**, palpate 1 cun in a distal direction and 1 cun in a lateral direction. There, locate **BL-58** on the lower border of the gastrocnemius muscle. Located on the same level (7 cun superior to the highest prominence of the lateral malleolus) are ➞ **G.B.-35** (at the posterior border of the fibula), ➞ **G.B.-36** (at the anterior border of the fibula) and ➞ **ST-39** (1 cun distal to the midpoint of the line connecting ➞ **ST-35** and ➞ **ST-41** and 1 fingerbreadth lateral to the anterior crest of the tibia).

Needling

Vertically or obliquely 1–1.5 cun

Actions/Indications

- Opens the channel and *luo* vessels, alleviates pain
- Expels pathogenic factors from the *taiyang* channels (S.I., BL)
- Harmonises above and below
- Treats haemorrhoids

Special features

Luo-connecting point








ST-38
ST-39
1 cun
Crest of the tibia



BL-59 *Instep Yang* FUYANG

Location

On the lateral aspect of the lower leg, 3 cun superior to → **BL-60** (in the depression between the highest prominence of the lateral malleolus and the Achilles tendon).

How to find

First, locate → **BL-60** in the depression between the highest prominence of the lateral malleolus and the Achilles tendon. With oedema of the lower leg, this point is not visible but palpable. From → **BL-60**, measure 3 cun (1 handbreadth) in a superior direction. There, locate **BL-59** in a depression between the Achilles tendon and the tendons of the peroneous longus and brevis muscles.

Located on the same level is → **G.B.-39**, 3 cun directly above the prominence of the lateral malleolus.

Needling

Vertically or obliquely 1–1.5 cun

Actions/Indications

- Opens the channel and *luo* vessels
- Benefits the lower back
- Benefits the head, activates the *yang qiao mai*

Special features

Xi-cleft point of the *yang qiao mai*, meeting point with the *yang qiao mai* according to some authors.


BL-59
Highest prominence of the lateral malleolus
3 cun
Anterior border of the Achilles tendon
BL-60


7
8
9
10
11
12
13
14
15
16
cun
G.B.-35
BL-57
G.B.-36
BL-58
G.B.-37
G.B.-38
G.B.-39
BL-59
BL-60
Highest prominence of the lateral malleolus
G.B.-40
G.B.-42
G.B.-44


Tendon of the gastrocnemius
Medial malleolus
Calcaneal tendon (Achilles tendon)
Lateral malleolus
Calcaneal tuberosity

Kunlun Mountains **KUNLUN** **BL-60**


Achilles tendon
Highest prominence
of the lateral malleolus
BL-60


BL-60
G.B.-40
BL-62
G.B.-41
G.B.-42
G.B.-43
G.B.-44
BL-61
BL-63
BL-64
BL-67
BL-66
BL-65


Tibia
Fibula
Medial
malleolus
Lateral
malleolus
Talus
Achilles tendon
Calcaneus

Location

In the depression on the line connecting the Achilles tendon and the highest prominence of the lateral malleolus.

How to find

Locate the highest prominence of the lateral malleolus (→ 3.6.2). From there, palpate horizontally towards the Achilles tendon and locate **BL-60** in a depression anterior to the tendon.

Needling

Vertically 0.5–1 cun. Caution: Reducing needle techniques contraindicated during pregnancy. Exception: A supportive point during labour. If the patient has cold feet, the therapeutic effect can be increased by using a heatlamp or a hot cherry-pit bag under the soles of the feet.

Actions/Indications

- Clears Heat, subdues Yang and Wind and eliminates excess, especially in the head
- Opens the channel, alleviates pain, relaxes the tendons, strengthens the lumbar region
- Promotes labour

Special features

Jing-river point, Fire point, Ma Dan Yang Heavenly Star point. Important distal point for the cervical, thoracic and lumbar spine, especially for chronic cases.

BL-61 *Servant's Respect* PUCAN

Location

On the lateral aspect of the heel, 1.5 cun inferior to → **BL-60** (in the depression between the highest prominence of the lateral malleolus and the Achilles tendon), in a depression on the calcaneus.

How to find

First, locate → **BL-60** in the depression between the highest prominence of the lateral malleolus and the Achilles tendon. With oedema of the lower leg, the depression is not visible but palpable. From → **BL-60**, measure 1.5 cun in a distal direction. There, locate **BL-61** in a depression on the calcaneus, approximately on the midpoint of a line connecting the sole of the foot and → **BL-60**.

Needling

Vertically or obliquely 0.3–0.5 cun

Actions/Indications

- Relaxes the tendons
- Opens the channel, alleviates pain

Special features

Meeting point with the *yang qiao mai*


Highest prominence
of the lateral malleolus
BL-60
Anterior border
of the Achilles
tendon
1.5 cun
BL-61


BL-60
G.B.-40
BL-62
G.B.-41
G.B.-42
G.B.-43
G.B.-44
BL-61
BL-63
BL-64
BL-67
BL-66
BL-65



Extending Vessel SHENMAI **BL-62**


Lower border of the
lateral malleolus
BL-62


Talus
Navicular
Intermediate cuneiform
Lateral cuneiform
Metatarsal bones
Phalanges
Cuboid
Calcaneus
BL-63
BL-64
Tuberosity of the 5th metatarsal bone

Location

In a depression directly inferior to the highest prominence of the lateral malleolus, above the joint space between the talus and calcaneus.

How to find

First, locate the highest prominence of the lateral malleolus (→ 3.6.2). **BL-62** is located directly below it, in a depression inferior to the lower border of the malleolus and superior to the tendons of the peroneus muscle, in the joint space between the talus and calcaneus.

Needling

Vertically or obliquely 0.3–0.5 cun. The needle may reach the calcaneofibular ligaments superior to the tendons of the peroneus longus and brevis muscles, possibly also the joint space.

Actions/Indications

- Subdues (internal) Wind, clears Heat from the head, calms the *shen*, benefits the head and eyes
- Expels external Wind
- Opens and regulates the *yang qiao mai*
- Opens the channel, alleviates pain
- Moves the Qi in the Bladder sinew channel

Special features

Opening (master) point of the *yang qiao mai*, Sun Si Miao Ghost point.

BL-63 Golden Gate JINMEN

Location

On the lateral aspect of the foot, proximal to the tuberosity of the 5th metatarsal bone, in a depression anterior and inferior to ➞ **BL-62** between the calcaneus and the cuboid bone. Note: Some authors locate **BL-63** between the cuboid bone and the tuberosity of the 5th metatarsal bone (see figure on **p. 311**); the more tender point should be selected.

How to find

When palpating along the lateral aspect of the foot on the level of the border of the 'red and white' skin, a bony structure can be felt approximately at the midpoint of the foot. This is the tuberosity of the 5th metatarsal point (➞ 3.6.2). Slightly proximal to it (towards the heel), you can palpate a depression between the calcaneus and the cuboid bone. There, locate **BL-63**.

➞ **BL-64** is located distal (towards the toes) to the tuberosity of the 5th metatarsal bone.

Needling

Vertically 0.3–0.5 cun

Actions/Indications

- Opens the channel, alleviates pain and eliminates stagnation (*xi*-cleft point)
- Subdues internal Wind and calms the *shen*

Special features

Xi-cleft point, meeting point with the *yang wei mai*.


Lower border of the lateral malleolus
BL-62


Tuberosity of the 5th metatarsal
BL-62
BL-63
Cuboid
Calcaneus


BL-63
G.B.-40
ST-41
LIV-4
SP-5
BL-64
ST-42
G.B.-41
SP-4
BL-65
G.B.-42
LIV-3
G.B.-43
ST-43
BL-66
SP-3
BL-67
ST-44
SP-2
G.B.-44
Ex-LE-10
(*bafeng*)
LIV-1
SP-1
ST-45

Capital Bone JINGGU BL-64


Tuberosity of the 5th metatarsal
BL-64
BL-63


BL-60
G.B.-40
BL-62
G.B.-41
G.B.-42
G.B.-43
G.B.-44
BL-61
BL-63
BL-64
BL-67
BL-66
BL-65


Talus
Navicular
Intermediate cuneiform
Lateral cuneiform
Metatarsal bones
Phalanges
Cuboid
Calcaneus
BL-63
BL-64
Tuberosity of the 5th metatarsal bone

Location

On the lateral aspect of the foot, distal to the tuberosity of the 5th metatarsal bone.

How to find

When palpating along the lateral aspect of the foot on the level of the border of the 'red and white' skin, a bony structure can be felt approximately at the midpoint of the foot. This is the tuberosity of the 5th metatarsal bone (→ 3.6.2). **BL-64** is located directly distal to it (towards the toes), at the junction between the base and the shaft of the 5th metatarsal bone.

→ **BL-63** is located proximal to the tuberosity of the 5th metatarsal bone, in a depression between the calcaneus and cuboid bone (or between the tuberosity and the cuboid bone). → **SP-4** is located in a comparable position on the medial aspect of the foot, in a depression distal to the base of the 1st metatarsal bone.

Needling

Vertically 0.3–0.5 cun

Actions/Indications

- Clears Wind and Heat from the head and eyes
- Calms the *shen*
- Opens the channel

Special features

Yuan-source point

BL-65 *Restraining Bone* **SHUGU**

Location

On the lateral aspect of the foot, in the depression proximal to the head of the 5th metatarsal bone.

How to find

When palpating along the bony structures on the lateral aspect of the foot, a prominent bony landmark can be felt approximately at the midpoint of the foot. This is the tuberosity of the 5th metatarsal bone. Distal to it (towards the toes), you can feel a further bony structure, the head of the 5th metatarsal bone. Directly proximal to it, at the border of the 'red and white' skin (border dorsum/sole of the foot), **BL-65** can be palpated in a depression. → **BL-66** is located in a depression distal to the head of the 5th metatarsal bone (distal to the metatarsophalangeal joint), at the junction of the base and the shaft of the proximal phalanx of the little toe.

→ **SP-3** is located in a comparable position on the medial aspect of the foot (proximal to the head of the 1st metatarsal bone). → **S.I.-3** and → **L.I.-3** are located in comparable positions at the ulnar/lateral border of the hand.

Needling

Vertically 0.3–0.5 cun. Caution: Painful point.

Actions/Indications

- Expels pathogenic factors (especially from the head)
- Clears Heat
- Opens the channel and *luo* vessels, alleviates pain
- Calms the *shen*

Special features

Shu-stream point, Wood point, sedation point.




Tuberosity of the 5th metatarsal
Head of the 5th metatarsal
BL-66
BL-65
BL-64


G.B.-41
SP-4
BL-65
G.B.-42
alus
LIV-3
G.B.-43
ST-43
BL-66
SP-3
BL-67
ST-44
SP-2
G.B.-44
Ex-LE-10
(bafeng)
LIV-1
SP-1
ST-45


S.I.-2
S.I.-3
Junction
Most distal palmar crease


Metacarpal II
Proximal phalanx II
L.I.-3

Foot Connecting Valley ZUTONGGU **BL-66**


Tuberosity of the 5th metatarsal
BL-66
BL-65
BL-64


BL-60
G.B.-40
BL-62
G.B.-41
G.B.-42
G.B.-43
G.B.-44
BL-61
BL-63
BL-64
BL-67
BL-66
BL-65






Proximal phalanx II
Metacarpal II
L.I.-2

Location

At the lateral border of the foot, in the depression distal to the metatarsophalangeal joint of the little toe.

How to find

When palpating along the border of the 'red and white' skin on the lateral aspect of the foot, at approximately the midpoint of the length of the foot, a clearly defined bony structure can be felt. This is the tuberosity of the 5th metatarsal bone. Distal to it (towards the toes), you can feel a further prominent bony structure, the head of the 5th metatarsal bone (or the 5th metatarsophalangeal joint). **BL-66** is located directly distal to it, in a depression at the junction of the base and the shaft of the proximal phalanx of the little toe.
→ **BL-65** is located proximal to the head of the 5th metatarsal bone. → **SP-2** is located in a comparable position on the medial aspect of the foot. Located in comparable positions on the hand are → **S.I.-2** (on the ulnar aspect) and → **L.I.-2** (on the radial aspect).

Needling

Vertically 0.3–0.5 cun. Caution: Painful point.

Actions/Indications

- Clears the head
- Descends the Lung and Stomach Qi
- Calms the *shen*

Special features

Ying-spring point, Water point, *ben* point (Five Phases point).

BL-67 *Reaching Yin* ZHIYIN

Location

On the dorsal aspect of the little toe, 0.1 cun from the lateral corner of the nail.

How to find

This point is located at the junction of two tangents that border the nail of the little toe laterally and proximally, approximately 0.1 cun from the actual corner of the nail.

Needling

Vertically 0.1 cun or obliquely 0.2 cun in the direction of the foot. Prick to bleed. Caution: Painful point.

Actions/Indications

- Scientifically established: conversion of breech presentations prior to birth: moxibustion and electro-acupuncture at this point seem to be most effective (approximately 70–80%)
- Facilitates labour
- Expels pathogenic factors from the opposite end of the channel
- Regulates Yin and Yang of the Water element

Special features

Jing-Well point, Metal point, tonification point, exit point. An isolated case has been reported regarding a pregnant woman who was treated with moxibustion at **BL-67**. This resulted in a fetomaternal transfusion of 300 ml of blood, endangering the fetus. For this reason, treatments should be controlled by cardiotocography.


BL-67
Wrong
Correct
BL-67


BL-66
G.B.-43
ST-43
SP-3
BL-67
ST-44
SP-2
G.B.-44
Ex-LE-10
(*bafeng*)
LIV-1
SP-1
ST-45


BL-60
G.B.-40
BL-62
G.B.-41
G.B.-42
G.B.-43
G.B.-44
BL-61
BL-63
BL-64
BL-67
BL-66
BL-65

4.8 The Kidney Channel System – Foot *shaoyin* (*zu shao yin jing luo*)

4.8.1 The Kidney Primary Channel (*zu shao yin jing*)


KID-27
21
Ren-7*
Ren-4
Ren-3
Du-1
11
SP-6
7
KID-1
Ren-4
Ren-3
Du-1

* According to Deadman et al 1998.


KID-7
KID-8
2 cun
Highest prominence of the medial malleolus
KID-3
KID-4
1 cun
Talus
KID-6
KID-5
Achilles tendon
Calcaneus
KID-2


KID-10
Junction tibial shaft of the medial condyle of the tibia
1
2
3
4
5
6
7
8
9
10
11
12
cun
KID-9
SP-6
KID-8
KID-7
5 cun
2 cun
KID-3
Highest prominence of the medial malleolus
KID-4
1 cun
KID-2
KID-6
KID-5

Pathway

The Kidney primary channel begins beneath the little toe, which is reached by **a branch** separating from the Bladder primary channel at its endpoint at → **BL-67** (*zhiyin*) (foot Yin–Yang connection of the second great circuit).

The Kidney primary channel diagonally crosses the sole of the foot to **KID-1** (*yongquan*) and to **KID-2** (*rangu*) below the navicular tuberosity, continues to the posterior aspect of the medial malleolus and descends to enter the heel. From here it ascends the medial aspect of the lower leg, intersecting with → **SP-6** (*yinlingquan*) and continuing to ascend the postero-medial aspect of the thigh towards the perineum.

In the perineal region the primary channel divides into **two branches**:

- the **deep, internal** branch travels to → **Du-1** (*changqiang*) and ascends alongside the spine to connect with its pertaining *zang*-Organ, the Kidneys (*shen*), and its paired *fu*-Organ, the Bladder (*pangguang*). Here it divides into smaller branches which connect with → **Ren-4** (*guanyuan*) and → **Ren-3** (*zhongji*), and, according to some authors, also with → **Ren-7** (*yinjiao*). From the Kidney (*shen*) a branch ascends to the Liver (*gan*), runs to and spreads in the Lung (*fei*), continues to the trachea and terminates at the root of the tongue. From the Lung (*fei*), an **inner branch** travels to the Heart (*xin*), where it meets the Pericardium primary channel (deep Yin–Yin connection). It then disperses in the chest and reaches → **Ren-17** (*shanzhong*).
- the **external** branch separates in the perineal region and runs to the lower abdomen at **KID-11** (*henggu*). From the pubic



bone it ascends initially 0.5 cun lateral to the anterior midline, from the 5th intercostal space (**KID-22**) 2 cun lateral to the midline to the infraclavicular fossa.

Clinical importance (→ 1.2)

Exterior (*biao*) **signs and symptoms:** Pain in the lumbar region, counterflow Cold or weakness of the legs, dry mouth, sore throat, pain in the lateral gluteal region and on the posterior thigh, pain on the soles of the feet.

Interior (*li*) **or** ***zangfu*****-Organ signs and symptoms:** Pain, facial oedema, dark rings under the eyes, shortness of breath, somnolence, restlessness, diarrhoea, thin or dry stools, abdominal distension, nausea and vomiting, impotence.

Connections of the Kidney primary channel

Connections with other channels

Bladder primary channel (*zu tai yang jing*)

Connection: Foot Yin–Yang connection of the second great circuit
Location: BL-67 → KID-1 (on the foot)
Circulation: Circadian (according to the Organ clock)
Importance: Exterior–Interior relationship

Heart primary channel (*shou shao yin jing*)

Connection: Paired according to the Six-Channel theory (hand–foot pairing): *shao yin* (Yin axes of the second great circuit)
Location: KID → HE (on the thorax). A branch of the internal pathway of the Kidney primary channel travels from the Kidney to the Liver, penetrates the diaphragm and spreads in the Lung (*fei*). From the Lung a branch runs to the Heart (*xin*), there connecting with the Heart primary channel.
Circulation: Non-circadian (**not** according to the Organ clock)
Importance: Above–below relationship

Pericardium primary channel (*shou jue yin jing*)

Connection: Deep Yin–Yin connection
Location: KID → P. A branch of the internal pathway of the Kidney primary channel travels from the Kidney to the Liver, penetrates the diaphragm and spreads in the Lung (*fei*). From the Lung an internal branch courses to the Heart (*xin*), where it joins the Pericardium primary channel (deep Yin–Yin connection) and also reaches → **Ren-17** (*shanzhong*).
Circulation: Circadian (according to the Organ clock)
Importance: The Pericardium primary channel receives Nutritive Qi (*ying qi*) from the Kidney primary channel (first circulation of the *ying qi* → 1.1.4).

Connections with other *zangfu*-Organ systems

Kidney (***shen***), **Bladder** (***pangguang***), Liver (*gan*), Lung (*fei*), Pericardium (*xin bao*), Heart (*xin*)

4.8.2 The Kidney Divergent Channel (*zu shao yin jing bie*)



Pathway

The Kidney divergent channel separates from the Kidney primary channel in the popliteal fossa at → **KID-10** (*yinggu*). It

➡ meets → **BL-40** (*weizhong*) in the popliteal fossa

➡ ascends to → **BL-36** (*chengfu*) in the centre of the gluteal crease

➡ penetrates the anus and reaches the Kidney (*shen*) and the Bladder (*pangguang*)

➡ ascends to → **BL-23** (*shenshu*) at the level of the lower border of the spinous process of L2, where it also meets the *dai mai*, following it round the waist to the abdomen

➡ ascends lateral to the midline to the infraclavicular fossa

➡ reaches the neck at → **Ren-23** (*liangquan*)

➡ emerges at the nape of the neck at → **BL-10** (*tianzhu*) and converges with the Bladder primary channel and the Bladder divergent channel to form one of the 6 *he*-confluences (here: BL/KID as first confluence → 1.3).

Clinical importance

- Strengthens the relationship between the Kidneys and the Bladder (*zangfu*-Organ systems). Points on the Kidney primary channel can therefore be used for disorders of the Bladder, and vice versa points on the Bladder primary channel can treat disorders of the Kidneys.
- Through the connection with the *dai m*ai, KID points can be used for disorders of the *dai mai*.
- Kidney Qi and Essence (*jing*) are sent to the Brain through the Kidney divergent channel via the spinal canal, thus strengthening the connection between the Kidneys, the Marrow and the Brain.
- Supports the connection to the tongue.

4.8.3 The Kidney Sinew Channel (*zu shao yin jing jin*)





Pathway

The Kidney sinew channel originates beneath the little toe

- diagonally crosses the sole of the foot, meets the Spleen sinew channel and continues to the medial malleolus where it binds (*jie*). From here a **minor branch** travels to the medial portion of the calcaneus. The **main branch** ascends the posteromedial aspect of the leg, binds (*jie*) at the medial condyle of the femur, crosses the Bladder sinew channel, ascends the posteromedial aspect of the thigh to the genital region to ➞ **Ren-3** (*zhongji*) and ➞ **Ren-2** (➞ 1.3), where it meets the other Yin sinew channels. It then penetrates the abdomen, runs along the spine to the nape of the neck and there meets the Bladder sinew channel.

From the genital region **an internal branch** traverses the gluteal region and follows the deep musculature along the spine to the occiput, where it meets the Bladder sinew channel.

Clinical importance

Pathology: Spasms on the sole of the foot, pain or spasms along the posteromedial aspect of the lower extremity, the back and the occiput. Chronic *bi*-syndromes. Epileptic seizures, limited range of motion with spinal flexion and extension. Degenerative disorders of the bones and joints, spondylosis, osteoarthritis.

Indication: Mainly for chronic pain, spasms and Cold sensations of the lower back and spine, accompanied by limited range of motion.

4.8.4 The Kidney *luo*-Connecting Vessel System (*zu shao yin luo mai*)



Pathway

The Kidney *luo*-connecting channel separates from the Kidney primary channel at **KID-4** (*dazhong*). It forms a three-dimensional reticular network, dividing into multiple branches and sub-branches (*sun luo*, *fu luo*, *xue luo* → 1.5) within the surrounding tissue.

➡ Horizontal divisions run to the Interiorly–Exteriorly paired Bladder primary channel; according to some schools of thought (for example Ngyen Van Nghi → Appendix) they travel as a **transverse** KID *luo*-connecting vessel to the *yuan*-source point **BL-64** (*jinggu*).

➡ A **longitudinal** division follows the Kidney primary channel to → **Ren-17** (*shanzhong*), penetrates the thorax and reaches the spine in the lumbar region.

Clinical importance (→ 8.1.2)

Pathology
Excess (*shi*): Retention of urine
Deficiency (*xu*): Pain in the lumbar region
Counterflow Qi: Restlessness, anxiety, fear, depression, fullness in the chest and epigastrium.

4.8.5 Cutaneous Region (*shao yin pi bu*)

See description and figures → 1.6.

4.8.6 Points of the Kidney Primary Channel (Overview)

Specific points according to their functions

- ***Yuan*-source point (→ 8.1.1): KID-3** (*taixi*) 🟦🟦
- ***Luo*-connecting point (→ 8.1.2.): KID-4** (*dazhong*)
- ***Xi*-cleft point (→ 8.1.3): KID-5** (*shuiquan*)
- **Associated Back-*shu* point (→ 8.1.4): BL-23** (*shenshu*) 🟦🟦
- **Associated Front-*mu* point (→ 8.1.5): G.B.-25** (*jingmen*) ■■
- **Five *shu*-transporting point (→ 8.1.6):**
  jing-well point (Wood), sedation point: **KID-1** (*yongquan*)
  ying-spring point (Fire): **KID-2** (*rangu*)
  shu-stream point (Earth): **KID-3** (*taixi*) 🟦■
  jing-river point (Metal), tonification point: **KID-7** (*fuliu*) 🟦■
  he-sea point (Water), *ben* point (Five Phases): **KID-10** (*yingu*) 🟦■
- *Hui*-meeting point (→ 8.1.7): –
- Opening point (→ 8.1.8) of the *yin qiao mai*: **KID-6** (*zhaohai*) 🟦■
- Lower *he*-sea points (→ 8.1.9): –
- *Jiaohui*-meeting points (→ 8.1.10):
  - with the *yin qiao mai*: **KID-2** (*rangu*)*, (**KID-6** (*zhaohai*)*, **KID-8** (*jiaoxin*)*)
  - with the *yin wei mai*: **KID-9** (*zhubin*)
  - with the *chong mai*: **KID-11–KID-21**
  - of other channels with the Kidney channel: **SP-6**, **Du-1**, **Ren-4**, **Ren-3**, **Ren-7***, **Ren-17**
- **Gao Wu command point (→ 8.1.11): –**
- **Window of Heaven point (→ 8.1.12): –**
- **Points of the Four Seas (→ 8.1.13): –**

---

* Mentioned by only some authors

- **Ma Dan Yang Heavenly Star point (→ 8.1.14): –**
- **Sun Si Miao Ghost point (→ 8.1.15): –**
- **Other functional points:**
  - *xi*-cleft point of the *yin qiao mai*: **KID-8** (*jiaoxin*)
  - *xi*-cleft point of the *yin wei mai*: **KID-9** (*zhubin*)

Points according to region

- **Local points** (→ 8.2.1): foot – **KID-6** (*zhaohai*) 🟦🟦; knee – **KID-10** (*yingu*) 🟦■
- **Adjacent points** (→ 8.2.1): foot – **KID-7** (*fuliu*) 🟦■; toes – **KID-6** (*zhaohai*) 🟦🟦
- **Distal points** (→ 8.2.1): for the throat – **KID-6** (*zhaohai*) 🟦🟦; for the tongue – **KID-6** (*zhaohai*) 🟦🟦; for the Kidneys and the Bladder – **KID-3** (*taixi*) 🟦■, **KID-7** (*fuliu*) 🟦🟦; for the genito-urinary region – **KID-3** (*taixi*) 🟦🟦

Specific points according to the channel pathway (in numerical order)

- **KID-1** (*yongquan*) 🟦■: *jing*-well point (Wood); sedation point
- **KID-2** (*rangu*): *ying*-spring point (Fire); *jiaohui*-meeting point with the *yin qiao mai* (→ 8.1.10)
- **KID-3** (*taixi*) 🟦🟦: *shu*-stream point (Earth); distal point for the Kidneys, Bladder, urogenital region (→ 8.2.1); *yuan*-source point (→ 8.1.1)
- **KID-4** (*dazhong*): *luo*-connecting point (→ 8.1.2)
- **KID-5** (*shuiquan*): *xi*-cleft point (→ 8.1.3)
- **KID-6** (*zhaohai*) 🟦🟦: opening point (→ 8.1.8) of the *yin qiao mai*; distal point for the tongue and throat (→ 8.2.1); *jiaohui*-meeting point with the *yin qiao mai** (→ 8.1.10); local point for the foot (→ 8.2.1)
- **KID-7** (*fuliu*) 🟦■: distal point for the Kidneys and the Bladder (→ 8.2.1); *jing*-river point (Metal); tonification point; regional point for the foot (→ 8.2.1)
- **KID-8** (*jiaoxin*): *xi*-cleft point of the *yin qiao mai*; *jiaohui*-meeting point with the *yin qiao mai** (→ 8.1.10)
- **KID-9** (*zhubin*): *xi*-cleft point of the *yin wei mai*; *jiaohui*-meeting point with the *yin wei mai** (→ 8.1.10)
- **KID-10** (*yingu*) 🟦■: *he*-sea point (Water), *ben* point (Five Phases); local point for the knee (→ 8.2.1)
- **KID-11** to **KID-21**: *jiaohui*-meeting points with the *chong mai* (→ 8.1.10)

General location help

- **KID-11** to **KID-21** are all located 0.5 cun lateral to the midline
  - **KID-11** to **KID-15** are spread on the 5 cun distance (→ 1.2) between the upper border of the pubic symphysis and the umbilicus (they are spaced at 1 cun intervals from the upper border of the pubic symphysis to 4 cun above it)
  - **KID-16** to **KID-21** are spread on the 8 cun distance (→ 1.2) between the umbilicus and the sternocostal angle (they are spaced at 1 cun intervals from the level of the umbilicus to 6 cun superior to it).
- **KID-22** to **KID-27** are all located 2 cun lateral to the midline
  - **KID-22** to **KID-26** are located in the 5th to 1st intercostal spaces
  - **KID-27** is located on the lower border of the sternoclavicular joint

---

* Mentioned by only some authors

Gushing Spring YONGQUAN KID-1





Location

On the sole of the foot, in a depression between the 2nd and 3rd metatarsal bones, at the junction of the anterior third and the posterior two-thirds of the sole.

How to find

Measure one third from the anterior border of the sole of the foot. Palpate for a pressure-sensitive point dorsal to the balls of the foot, at the midpoint of the width of the foot.

Needling

Needling this point is very painful and is therefore only recommended for severe disorders or in an emergency. Acupressure is commonly used instead; moxibustion is possible. For the treatment of collapse, unconsciousness, shock or a severe excess condition, this point should be strongly stimulated; in pronounced deficiency conditions, stimulation should be applied more cautiously.

Actions/Indications

- Revives collapsed Yang
- Clears excess, Heat and Wind from the head, lowers Yang
- Calms the *shen*

Special features

Jing-well point, Wood point, sedation point, entry point. **KID-1** is the lowest acupuncture point on the body and the only point on the sole of the foot. For this reason, it plays an important role in Qigong, forming a grounding point in the centre of the foot, where the energies of the Earth and Man unite. During practice, the centre of gravity should be above this point.

KID-2 *Blazing Valley* RANGU

Location

At the medial border of the foot, in a depression at the anterior border of the navicular bone, at the border of the 'red and white' skin.

How to find

Palpate from distal to proximal along the tarsal section of the medial aspect of the foot, past the shaft and the head of the 1st metatarsal bone (→ **SP-4**) and the medial cuneiform bone, finally reaching the prominent navicular bone. Locate **KID-2** anterior to the navicular bone, at the inferior angle of the joint between the medial cuneiform bone and the navicular bone.

Needling

From the medial aspect of the foot, 0.5–1 cun vertically below the border of the bone. Use reducing needling techniques for empty Heat. Use tonifying techniques for Kidney Yang/Qi deficiency.

Actions/Indications

- Clears empty Heat
- Regulates the Lower Burner and the Kidneys
- Local point

Special features

Ying-spring point, Fire point, meeting point with the *yin qiao mai*.




Navicular
Medial cuneiform
Metatarsal bones
Proximal phalanges
Distal phalanges
Medial phalanges
Base of the 1st metatarsal bone
Navicular tuberosity
Calcaneus



Supreme Stream TAIXI KID-3


Highest prominence
of the medial malleolus
KID-3

Location

In the depression between the highest prominence of the medial malleolus and the Achilles tendon.

How to find

Locate the highest prominence of the medial malleolus (→ 3.6.2). From there, palpate horizontally towards the Achilles tendon. **KID-3** is located in a depression that can be palpated anterior to the tendon.

Needling

Vertically 0.3–1 cun

Actions/Indications

- Nourishes Kidney Yin and clears deficiency Heat, tonifies Kidney Yang, stabilises the Kidney Qi and the Lungs (helping the Kidneys absorb the Qi), regulates menstruation
- Strengthens the lower back, local point

Special features

Yuan-source point, *shu*-stream point, Earth point. Important point for tonifying the Kidneys (especially Kidney Yin).


SP-6
KID-7
KID-8
LIV-4
KID-3
KID-4
SP-5
KID-6
KID-5
SP-1
KID-2
SP-4
SP-2
SP-3


Tibia
Fibula
Medial
malleolus
Lateral
malleolus
Talus
Achilles tendon
Calcaneus


Tendon of the
gastrocnemius
Medial
malleolus
Calcaneal tendon
(Achilles tendon)
Lateral
malleolus
Calcaneal tuberosity

KID-4 *Great Bell* DAZHONG

Location

Anterior to the medial border of the Achilles tendon, superior to its insertion at the calcaneus.

How to find

From the highest prominence of the medial malleolus, draw a horizontal line to the medial border of the Achilles tendon. From there, measure 0.5 cun in a distal direction. **KID-4** is located in a depression anterior to the Achilles tendon, slightly superior to its insertion at the calcaneus. **Or: KID-4** is located posterior to the midpoint of a line connecting → **KID-3** and → **KID-5** anterior to the Achilles tendon.

Needling

Vertically 0.3–0.5 cun. Avoid puncturing the tendon.

Actions/Indications

- Firms the Kidney Qi (helping the Kidneys absorb the Qi) and supports the Lungs
- Strengthens the Kidneys and cools empty Heat
- Strengthens the will, dispels fear
- Local point

Special features

Luo-connecting point


Highest prominence
of the medial malleolus
KID-3
KID-4
KID-5
0.5 cun


Tendon of the
gastrocnemius
Medial
malleolus
Calcaneal tendon
(Achilles tendon)
Calcaneal tuberosity
Lateral
malleolus


Highest prominence
of the medial malleolus
KID-3
Achilles
tendon

Ch04.8-F10028.qxd 2/22/08 6:14 PM Page 325

Water Spring SHUIQUAN KID-5


Highest prominence
of the medial malleolus
KID-3
1 cun
KID-5




SP-6
KID-7
KID-8
LIV-4
KID-3
KID-4
SP-5
KID-6
KID-5
SP-1
KID-2
SP-4
SP-2
SP-3

Location

1 cun distal to → **KID-3**, in a depression over the joint space between the talus and calcaneus.

How to find

First, locate → **KID-3** on the level of the highest prominence of the medial malleolus (→ 3.6.2), in a depression between the malleolus and the Achilles tendon. From **KID-3**, palpate 1 cun in an inferior direction to a palpable depression over the joint space between the talus and calcaneus. This is the location of **KID-5**.

Needling

0.3–0.5 cun obliquely to vertically superior to the margin of the bone.

Actions/Indications

- Regulates the *chong mai* and *ren mai*, benefits menstruation and urination

Special features

Xi-cleft point. Especially indicated for acute disorders and painful conditions.

Ch04.8-F10028.qxd 2/22/08 6:14 PM Page 326

KID-6 *Shining Sea* ZHAOHAI

Location

Approximately 1 cun inferior to the highest prominence of the medial malleolus, over the joint space between the talus and the calcaneus.


Highest prominence of the medial malleolus
KID-6
Approxi-mately 1 cun
Joint space between the talus and calcaneus
Sustentaculum tali

How to find

From the highest prominence of the medial malleolus (→ 3.6.2), palpate distally, until the palpating finger can feel the depression of the joint space between the talus and the calcaneus. (**KID-6** is often located between the tendons of the tibialis and flexor digitorum longus muscles.) Directly distal to this point, you can palpate a small bony prominence, the sustentaculum tali. With the patient's foot in a supinated position, a visible skin crease forms on the level of the point. Note: There are several variations regarding the exact location of this point. However, the determining aspect for its location is not the cun measurement but the joint space below the prominence.


Highest prominence of the medial malleolus
KID-6

Needling

0.3–0.5 cun vertically or obliquely in a proximal direction. The needle may reach the deltoid ligament.

Actions/Indications

- Nourishes Kidney Yin, clears empty Heat, benefits the throat, regulates the Lower Burner
- Calms the *shen*
- Moves Qi locally

Special features

Opening (master) point of the *yin qiao mai*. Important point, especially for strengthening the Kidney Yin.


SP-6
KID-7
KID-8
LIV-4
KID-3
KID-4
SP-5
KID-6
KID-5
SP-1
KID-2
SP-4
SP-3
SP-2


11
12
13
14
15 cun
SP-6
KID-8
KID-7
KID-3
SP-5
SP-1
KID-2
SP-4
Highest prominence of the medial malleolus


Highest prominence of the medial malleolus
KID-3
Achilles tendon

Returning Current FULIU **KID-7**


KID-7
2 cun
Highest prominence
of the medial malleolus
KID-3
Achilles
tendon




Medial
malleolus
Calcaneal tendon
(Achilles tendon)
Calcaneal tuberosity
Lateral
malleolus


KID-8
KID-7
KID-3
2 cun

Location

2 cun proximal to → **KID-3**, at the anterior border of the Achilles tendon.

How to find

First, locate → **KID-3** on the level of the higest prominence of the medial malleolus (→ 3.6.2), in the depression between the malleolus and the Achilles tendon. From → **KID-3**, measure 2 cun in a proximal direction (towards the knee joint) and locate **KID-7** in a depression at the anterior border of the Achilles tendon.

Located on the same level, but more medially, is → **KID-8** (2 cun directly proximal to the medial malleolus).

Needling

Vertically 0.5–1 cun

Actions/Indications

- Regulates the water passages and treats oedema, strengthens the Kidneys (especially Kidney Yang), drains Dampness and clears Damp-Heat
- For disorders of the Intestines due to Damp-Heat
- Strengthens the lumbar region

Special features

Jing-river point, Metal point, tonification point

KID-8 *Exchange Belief* JIAOXIN

Location

2 cun proximal to the highest prominence of the medial malleolus, posterior to the medial border of the tibia.

How to find

KID-8 is located on the same level as → **KID-7**, but slightly closer to the border of the tibia (approximately 0.5 cun).

Needling

Vertically 0.5–1 cun

Actions/Indications

- Regulates menstruation, regulates the *ren mai* and *chong mai*
- Clears Heat and eliminates Dampness from the Lower Burner
- Treats blockages of the *yin qiao mai*

Special features

Xi-cleft point of the *yin qiao mai*


LIV-5
KID-7
KID-8
2 cun
KID-3
0.5 cun


SP-6
KID-7
KID-8
LIV-4
KID-3
KID-4
SP-5
KID-6
KID-5
SP-1
KID-2
SP-4
SP-2
SP-3



Ch04.8-F10028.qxd 2/22/08 6:14 PM Page 329

Guesthouse ZHUBIN KID-9


LIV-5
KID-9
KID-7
5 cun
KID-3


6
7
8
9
10
11
12
13
14
15
cun
LIV-6
SP-7
LIV-5
KID-9
SP-6
KID-8
KID-7
KID-3
SP-5
SP-1
SP-4
KID-2
Highest prominence of the medial malleolus


LIV-5
1/3
5 cun


Highest prominence of the medial malleolus
KID-3
Achilles tendon


Tendon of the semitendinosus (most prominent tendon)
KID-10

Location

5 cun proximal to the highest prominence of the medial malleolus, 2 cun posterior to the medial border of the tibia.

How to find

On a line connecting → **KID-3** (posterior to the medial malleolus) and → **KID-10** (medial aspect of the popliteal crease), measure 5 cun from the level of the prominence of the medial malleolus. Here, **KID-9** is located 2 cun posterior to the medial border of the tibia.

Located on the same level, but directly posterior to the medial border of the tibia, is → **LIV-5**.

Needling

Vertically 1–1.5 cun

Actions/Indications

- Clears the Heart and transforms Phlegm
- Regulates the Qi and alleviates pain

Special features

Xi-cleft point of the *yin wei mai*

KID-10 *Yin Valley* YINGU

Location

At the medial end of the popliteal crease, between the tendons of the semimembranosus and semitendinosus muscles, on the level of the knee joint space.

How to find

With the knee flexed less than 90°, ask the patient to press their heel against the treatment couch so that the two tendons will become more pronounced in the popliteal crease. From a medial direction, **KID-10** is located in a small gap anterior to the more prominent tendon of the semitendinosus muscle and posterior to the less well-defined tendon of the semimembranosus muscle.
→ **BL-40** is located on the same level, in the centre of the popliteal crease.

Needling

Needle 1–1.5 cun vertically from a dorsomedial aspect towards the tibial tuberosity. Avoid puncturing the tendon.

Actions/Indications

- Drains Damp-Heat from the Lower Burner and benefits the Kidneys
- Opens the channel

Special features

He-sea point, *ben* point (Five Phases point); for recurring urinary disorders with Kidney Yin deficiency.


Tendon of the semimembranosus
Tendon of the semitendinosus (most prominent tendon)
KID-10
medial
lateral


Upper border of the patella
KID-10
Popliteal crease
LIV-8
1
Junction of the tibial shaft with the medial condyle of the tibia
SP-9
2
LIV-7
3
4
SP-8
5
6
7
LIV-6
8
9
SP-7
LIV-5
10
KID-9
SP-6
11
12




Popliteal crease
BL-40

Pubic Bone HENGGU KID-11


Midline
0.5 cun
KID-16
Ren-08
Umbilicus
KID-15
Ren-07
Ren-06
KID-14
Ren-05
5 cun
KID-13
Ren-04
KID-12
Ren-03
KID-11
Ren-02
Upper border
of the pubic
symphysis

Location

At the upper border of the pubic symphysis, 0.5 cun lateral to the anterior midline.

How to find

Close to the midline, the upper border of the pubic symphysis is generally easily palpable. **KID-11** is located directly superior to its bony margin and 0.5 cun lateral to the midline.

Located on the same level are → **Ren-2** (on the midline), → **ST-30** (2 cun lateral to the midline) and → **SP-12** (3.5 cun lateral to the midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, full bladder, pregnancy.

Actions/Indications

- Regulates the Lower Burner and the water passages, strengthens the Kidneys

Special features

Meeting point with the *chong mai*


15
25
16
8
14
6
27
14
4
29
12
13
SP-12
ST-30
KID-11
Ren-2
Umbilicus
1
2
3
4
Upper border
of the pubic
symphysis


Umbilicus
(Ren-8)
Anterior superior
iliac spine
KID-15
Ren-6
G.B.-27
ST-28
Ren-2
ST-30
SP-12
Symphysis


SP-13
Upper border
of the pubic
symphysis
0.7 cun
SP-12
Symphysis
0.5 cun
3.5 cun

KID-12 *Great Luminance* DAHE

Location

1 cun superior to the upper border of the pubic symphysis, 0.5 cun lateral to the anterior midline.

How to find

The distance between the centre of the umbilicus and the upper border of the pubic symphysis is divided into 5 proportional cun. As these can vary considerably from finger cun measurements, only proportional cun measurements should be applied (elastic tape → 2.3.1). From the upper border of the pubic symphysis, measure 1 cun in a superior direction and on this level locate **KID-12** 0.5 cun lateral to the midline. Located on the same level are → **Ren-3** (on the midline), → **ST-29** (2 cun lateral to the midline) and → **Ex-CA-1** (*zigong*; 3 cun lateral to the midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, full bladder, pregnancy.

Actions/Indications

- Regulates the Lower Burner, strengthens the Kidneys and the Essence (*jing*)

Special features

Meeting point with the *chong mai*


Ex-CA-1
(zigong)
3 cun
Ren-3
Ren-2
1 cun


Midline
0.5 cun
KID-16
Ren-08
Umbilicus
KID-15
Ren-07
Ren-06
KID-14
Ren-05
5 cun
KID-13
Ren-04
KID-12
Ren-03
KID-11
Ren-02
Upper border
of the pubic
symphysis


15
25
16
8
Umbilicus
1
14
6
27
14
2
BR09-01
4
3
29
12
4
13
SP-12
ST-30
KID-11
Ren-2
Upper border
of the pubic
symphysis


Ren-3
Ren-2
1 cun


ST-29
1 cun
ST-30
Upper border of
the pubic symphysis

Qi Cave QIXUE **KID-13**


Midline
0.5 cun
KID-16
Ren-08
Umbilicus
KID-15
Ren-07
Ren-06
KID-14
Ren-05
5 cun
KID-13
Ren-04
KID-12
Ren-03
KID-11
Ren-02
Upper border of the pubic symphysis

Location

2 cun superior to the upper border of the pubic symphysis, 0.5 cun lateral to the anterior midline.

How to find

The distance between the centre of the umbilicus and the upper border of the pubic symphysis is divided into 5 proportional cun. As these can vary considerably from finger cun measurements, only proportional cun measurements should be applied (elastic tape ➞ 2.3.1). From the upper border of the pubic symphysis, measure 2 cun in a superior direction and on this level locate **KID-13** 0.5 cun lateral to the midline.

Located on the same level are ➞ **Ren-4** (on the midline), ➞ **ST-28** (2 cun lateral to the midline), ➞ **Ex-CA** (*tituo*/*qimen*/*yijing*: 4/3/1 cun lateral to the midline) and ➞ **G.B.-27** (anterior and medial to the ASIS).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, full bladder, pregnancy.

Actions/Indications

- Regulates the Lower Burner, regulates the *chong mai* and *ren mai*, strengthens the Kidneys and the essence (*jing*)

Special features

Meeting point with the *chong mai*


tituo
qimen
yijing
Ren-4
1 cun
2 cun
3 cun
Ren-2


Ren-4
2 cun
Ren-2




G.B.-27
Anterior superior iliac spine
0.5 cun
G.B.-28

KID-14 *Four Fullnesses* SIMAN

Location

2 cun inferior to the umbilicus, 0.5 cun lateral to the anterior midline.

How to find

The distance between the centre of the umbilicus and the upper border of the pubic symphysis is divided into 5 proportional cun. As these can vary considerably from finger cun measurements, only proportional cun measurements should be applied (elastic tape → 2.3.1). From the centre of the umbilicus, measure 2 cun in an inferior direction and on this level locate **KID-14** 0.5 cun lateral to the midline.

Located on the same level are → **Ren-5** (on the midline) and → **ST-27** (2 cun lateral to the midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Regulates the Lower Burner and benefits the Kidneys
- Regulates the water passages
- Regulates the Qi and moves Blood stasis

Special features

Meeting point with the *chong mai*


Midline
0.5 cun
KID-16
Ren-08
Umbilicus
KID-15
Ren-07
Ren-06
KID-14
Ren-05
5 cun
KID-13
Ren-04
KID-12
Ren-03
KID-11
Ren-02
Upper border of the pubic symphysis


15
25
16
8
14
6
27
14
4
29
12
13
SP-12
ST-30
KID-11
Ren-2
Umbilicus
1
2
3
4
Upper border of the pubic symphysis





Middle Flow ZHONGZHU KID-15


Midline
0.5 cun
KID-16
Ren-08
Umbilicus
KID-15
Ren-07
Ren-06
KID-14
Ren-05
5 cun
KID-13
Ren-04
KID-12
Ren-03
KID-11
Ren-02
Upper border of the pubic symphysis

Location

1 cun inferior to the umbilicus, 0.5 cun lateral to the anterior midline.

How to find

The distance between the centre of the umbilicus and the upper border of the pubic symphysis is divided into 5 proportional cun. As these can vary considerably from finger cun measurements, only proportional cun measurements should be applied (elastic tape → 2.3.1). From the centre of the umbilicus, measure 1 cun in an inferior direction and on this level locate **KID-15** 0.5 cun lateral to the midline.

Located on the same level are → **Ren-7** (on the midline) and → **ST-26** (2 cun lateral to the midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Regulates the Intestines
- Regulates the Lower Burner

Special features

Meeting point with the *chong mai*


Umbilicus
Upper border of the pubic symphysis


Ren-8
Umbilicus
1 cun
Ren-7


2 cun
ST-25
1 cun
ST-26

KID-16 *Vitals* Shu HUANGSHU

Location

0.5 cun lateral to the centre of the umbilicus.

How to find

From the centre of the umbilicus, measure 0.5 cun in a lateral direction. Located on the same level are → **Ren-8** (in the centre of the umbilicus), → **ST-25** (2 cun lateral to the midline), → **SP-15** (4 cun lateral to the midline) and → **G.B.-26** (on the level of umbilicus, on a vertical line drawn through the free end of the 11th rib).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy. Avoid the umbilicus.

Actions/Indications

- Regulates the Qi, regulates and warms the Stomach and Intestines

Special features

Meeting point with the *chong mai*


Midline
0.5 cun
KID-16
Umbilicus
Ren-08




11th rib
G.B.-26


LIV-14
G.B.-24
12
16
22
18
LIV-13
15
25
16
8
14
6
27
14
6
5
4
3
2
1
Umbilicus
1
2




2 cun
4 cun
ST-25
SP-15

Shang Bend SHANGQU KID-17

Location

2 cun superior to the umbilicus, 0.5 cun lateral to the anterior midline.

How to find

The distance between the sternocostal angle (→ 3.5) and the centre of the umbilicus is divided into 8 proportional cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun should be used (elastic tape → 2.3.1). From the centre of the umbilicus, measure 2 cun in a superior direction and on this level locate **KID-17** 0.5 cun lateral to the midline.
Located on the same level are → **Ren-10** (on the midline), → **ST-23** (2 cun lateral to the midline) and **Ex-CA** (*weishang*, 4 cun lateral to the midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Regulates the Stomach and Intestines, eliminates stagnation

Special features

Meeting point with the *chong mai*


Sternocostal angle
KID-21
Ren-14
KID-20
Ren-13
KID-19
Ren-12
8 cun
KID-18
Ren-11
KID-17
Ren-10
2 cun
0.5 cun
Umbilicus


Ren-10
2 cun
Umbilicus




Sternocostal angle
Umbilicus


Ren-10
weishang
2 cun
SP-15

KID-18 *Stone Gate* SHIGUAN

Location

3 cun superior to the umbilicus, 0.5 cun lateral to the anterior midline.

How to find

The distance between the sternocostal angle (→ 3.5) and the centre of the umbilicus is divided into 8 proportional cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun measurements should be used (elastic tape → 2.3.1). From the centre of the umbilicus measure 3 cun in a superior direction and on this level locate **KID-18** 0.5 cun lateral to the midline.

Located on the same level are → **Ren-11** (on the midline), → **ST-22** (2 cun lateral to the midline) and → **SP-16** (on the mamillary line).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Strengthens the Middle, regulates the Stomach and Intestines, removes Blood stagnation

Special features

Meeting point with the *chong mai*


Sternocostal angle
KID-21
Ren-14
KID-20
Ren-13
KID-19
Ren-12
KID-18
Ren-11
KID-17
Ren-10
8 cun
3 cun
0.5 cun
Umbilicus


LIV-14
G.B.-24
12
16
22
18
LIV-13
15
25
16
8
14
6
27
14
6
5
4
3
2
1
Umbilicus
1
2


Ren-11
3 cun
Umbilicus




4 cun
SP-16
3 cun
SP-15

Yin Metropolis YINDU **KID-19**


Sternocostal angle
KID-21
Ren-14
KID-20
Ren-13
KID-19
Ren-12
8 cun
KID-18
Ren-11
KID-17
Ren-10
4 cun
0.5 cun
Umbilicus


Sternocostal angle
Umbilicus

Location

Midway between the sternocostal angle and the centre of the umbilicus, 0.5 cun lateral to the anterior midline.

How to find

The distance between the sternocostal angle (→ 3.5) and the centre of the umbilicus is divided into 8 proportional cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun should be used (elastic tape → 2.3.1). Spreading hands technique (→ 2.3.3): Place the little fingers on the centre of the umbilicus and the sternocostal angle respectively and join the thumbs at the midpoint of this distance by evenly spreading both hands. **KID-19** is located on this level, 0.5 cun lateral to the midline.

Located on the same level are → **Ren-12** (on the midline) and → **ST-21** (2 cun lateral to the midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Regulates the Qi, regulates the Stomach and Intestines
- Regulates counterflow Qi

Special features

Meeting point with the *chong mai*




1/2
ST-21
Ren-12

KID-20 *Abdomen Connecting Valley* FUTONGGU

Location

5 cun superior to the umbilicus or 3 cun inferior to the sternocostal angle, 0.5 cun lateral to the anterior midline.

How to find

The distance between the sternocostal angle (→ 3.5) and the centre of the umbilicus is divided into 8 proportional cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun measurements should be used (elastic tape → 2.3.1). From the sternocostal angle, measure 3 cun in an inferior direction and on this level locate **KID-20** 0.5 cun lateral to the midline.

Located on the same level are → **Ren-13** (on the midline), → **ST-20** (2 cun lateral to the midline) and → **G.B.-24** (on the mamillary line, in the 7th intercostal space).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Strengthens the Spleen, harmonises the Stomach and Intestines, regulates counterflow Qi

Special features

Meeting point with the *chong mai*


Sternocostal angle
KID-21
Ren-14
KID-20
Ren-13
KID-19
Ren-12
KID-18
Ren-11
KID-17
Ren-10
3 cun
8 cun
5 cun
0.5 cun
Umbilicus


6
7
G.B.-24 in the
7th intercostal space


LIV-14
G.B.-24
16
22
18
12
LIV-13
15
25
16
8
14
6
27
14
6
5
4
3
2
1
Umbilicus
1
2


3 cun
8 cun
Ren-13


3 cun
ST-19
ST-20

Hidden Gate YOUMEN KID-21


Sternocostal angle
KID-21
Ren-14
3 cun
KID-20
Ren-13
KID-19
Ren-12
8 cun
KID-18
Ren-11
KID-17
Ren-10
5 cun
0.5 cun
Umbilicus


Sternocostal angle
Umbilicus

Location

2 cun inferior to the sternocostal angle, 0.5 cun lateral to the anterior midline.

How to find

The distance between the sternocostal angle (→ 3.5) and the centre of the umbilicus is divided into 8 proportional cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun should be used (elastic tape → 2.3.1). From the sternocostal angle, measure 2 cun in an inferior direction and on this level locate **KID-21** 0.5 cun lateral to the midline.
Located on the same level are → **Ren-14** (on the midline), → **ST-19** (2 cun lateral to the midline) and → **LIV-14** (on the mamillary line, in the 6th intercostal space).

Needling

Vertically 0.5–1 cun. Caution: The liver is located on the right, the peritoneum on the left. Caution during pregnancy.

Actions/Indications

- Harmonises the Stomach, regulates counterflow Qi

Special features

Meeting point with the *chong mai*. Last point of the *chong mai* located on the Kidney channel.




Sternocostal angle
ST-18
2 cun
ST-19


5th intercostal space
6th intercostal space
LIV-14

KID-22 *Walking Corridor* BULANG

Location

In the 5th intercostal space (ICS), 2 cun lateral to the anterior midline.

How to find

Locate the 5th ICS either by counting parasternally from the clavicle or from the manubriosternal synchondrosis (➞ 2nd rib) (➞ 3.5), then locate **KID-22** 2 cun lateral to the anterior midline. Located on the same level (5th ICS) are ➞ **Ren-16** (on the midline), ➞ **ST-18** (on the mamillary line) and ➞ **SP-17** (6 cun lateral to the midline).

Needling

0.5–0.8 cun obliquely or transversely (subcutaneously) with or against the channel pathway. Caution: Avoid injuring the liver (on the right side), the heart (on the left side) and the pleura.

Actions/Indications

- Regulates the Lung Qi and counterflow Qi, unbinds the chest

Special features

Exit point. The *Su Wen* describes points **KID-22** to **KID-27** as *shu* points of the chest, indicated for difficult breathing and disorders of the thorax. They are particularly indicated for breathing difficulties due to 'excess above, deficiency below', which refers to the inability of the Kidneys to absorb the Qi that has descended from the Lung.


KID-27
KID-26
KID- 25
KID-24
KID-23
Ren-17
KID-22
5th intercostal space
2 cun


Sternocostal angle
Ren-16


Sternocostal angle
ST-18


5th intercostal space
SP-17
6 cun


Ma 9
12
Ren 22
Ni 27
14 26
20
Mi 20
25
19
19
16
24
18
17
17
18
22
15
LIV-14
G.B.-24
12
16
22
18
LIV-13
15
25
16
8
Sternocostal angle
8
7
6
5
4
3
2
1
Umbilicus

Spirit Seal SHENFENG KID-23


KID-27
KID-26
KID-25
KID-24
KID-23
KID-22
4th intercostal space
Ren-17
2 cun


Level of the nipples
4th intercostal space
Ren-17


3rd intercostal space
ST-16
4th intercostal space


SP-18
4th intercostal space
6 cun


1 cun
P-1
4th intercostal space


G.B.-23
4th intercostal space
G.B.-22
1 cun

Location

In the 4th intercostal space (ICS), 2 cun lateral to the anterior midline.

How to find

Locate the 4th ICS either by palpating parasternally from the clavicle or by counting from the manubriosternal synchondrosis (→ 2nd rib) (→ 3.5), then locate **KID-23** 2 cun lateral to the anterior midline.

Located on the same level (4th ICS) are → **Ren-17** (on the midline), → **ST-17** (on the nipple), → **SP-18** (6 cun lateral to the midline), → **P-1** (1 cun lateral to the nipple) and → **G.B.-22** (3 cun inferior to the axilla) as well as → **G.B.-23** (1 cun anterior to **G.B.-22**).

Needling

0.5–0.8 cun obliquely or transversely (subcutaneously) along the course of the ICS or with or against the channel pathway. Caution: Heart, pneumothorax.

Actions/Indications

- Regulates the Lung Qi and counterflow Qi, unbinds the chest
- Harmonises the Stomach
- Benefits the breasts

Special features

The *Su Wen* describes points **KID-22** to **KID-27** as *shu* points of the chest, indicated for difficult breathing and disorders of the thorax. They are particularly indicated for breathing difficulties due to 'excess above, deficiency below', which refers to the inability of the Kidneys to absorb the Qi that has descended from the Lung.

KID-24 *Spirit Ruin* LINGXU

Location

In the 3rd intercostal space (ICS), 2 cun lateral to the anterior midline.

How to find

Locate the 3rd ICS by palpating parasternally from the clavicle or by counting from the manubriosternal synchondrosis (→ 2nd rib) (→ 3.5), then locate **KID-24** 2 cun lateral to the anterior midline. Located on the same level (→ 3rd ICS) are → **Ren-18** (on the midline), → **ST-16** (4 cun lateral to the midline) and → **SP-19** (6 cun lateral to the midline).

Needling

0.5–0.8 cun obliquely or transversely (subcutaneously) along the course of the ICS or with or against the channel pathway. Caution: Pneumothorax.

Actions/Indications

- Regulates the Lung and Stomach Qi
- Unbinds the chest
- Benefits the breasts

Special features

The *Su Wen* describes points **KID-22** to **KID-27** as *shu* points of the chest, indicated for difficult breathing and disorders of the thorax. They are particularly indicated for breathing difficulties due to 'excess above, deficiency below', which refers to the inability of the Kidneys to absorb the Qi that has descended from the Lung.


KID-27
KID-26
KID-25
KID-24
3rd intercostal space
KID-23
Ren-17
KID-22
2 cun


Ren-19
3rd intercostal space
Ren-18
Ren-17
Ren-16


2nd intercostal space
ST-16
3rd intercostal space
4th intercostal space


LU-1
SP-20
1st intercostal space
SP-19
2nd intercostal space
3rd intercostal space


ST-9
12
Ren 22
Ni 27
14 26
20
SP- 20
25
19
19
16
24
18
17
17
18
22
15
Le 14
G.B.-24
12
16
22
18
LIV-13
15
25
16
8
14
Sterno-costal angle
7
6
5
4
3
2
1
Umbilicus
1

Spirit Storehouse SHENCANG KID-25


KID-27
KID-26
KID-25
2nd intercostal space
KID-24
KID-23
Ren-17
KID-22
2 cun


Ren-21
Ren-20
2nd intercostal space
Ren-19


1st intercostal space
ST-14
2nd intercostal space
ST-15


LU-1
SP-20
1st intercostal space
SP-19
2nd intercostal space
3rd intercostal space

Location

In the 2nd intercostal space (ICS), 2 cun lateral to the anterior midline.

How to find

Locate the 2nd ICS by palpating parasternally from the clavicle or by counting from the manubriosternal synchondrosis (➞ 2nd rib) (➞ 3.5), then locate **KID-24** 2 cun lateral to the anterior midline. Located on the same level (➞ 2nd ICS) are ➞ **Ren-19** (on the midline), ➞ **ST-15** (4 cun lateral to the midline) and ➞ **SP-20** (6 cun lateral to the midline).

Needling

0.5–0.8 cun obliquely or transversely (subcutaneously) along the course of the ICS or with or against the channel pathway. Caution: Pneumothorax.

Actions/Indications

- Regulates the Lung Qi
- Unbinds the chest

Special features

The *Su Wen* describes points **KID-22** to **KID-27** as *shu* points of the chest, indicated for difficult breathing and disorders of the thorax. They are particularly indicated for breathing difficulties due to 'excess above, deficiency below', which refers to the inability of the Kidneys to absorb the Qi that has descended from the Lung.

KID-26 *Comfortable Chest* YUZHONG

Location

In the 1st intercostal space (ICS), 2 cun lateral to the anterior midline.

How to find

Palpating parasternally from superior to inferior, the 1st rib can be palpated directly below the clavicle; in some cases, it can be completely hidden under the clavicle. Locate **KID-26** below the 1st rib in the 1st ICS, 2 cun lateral to the midline. Located on the same level (1st ICS) are → **Ren-20** (on the midline), → **ST-14** (4 cun lateral to the midline) and → **LU-1** (6 cun lateral to the midline).

Needling

0.5–0.8 cun obliquely or transversely (subcutaneously) along the course of the ICS or with or against the channel pathway. Caution: Pneumothorax.

Actions/Indications

- Regulates the Lung Qi and transforms Phlegm
- Unbinds the chest
- Benefits the breasts

Special features

The *Su Wen* describes points **KID-22** to **KID-27** as *shu* points of the chest, indicated for difficult breathing and disorders of the thorax. They are particularly indicated for breathing difficulties due to 'excess above, deficiency below', which refers to the inability of the Kidneys to absorb the Qi that has descended from the Lung.


KID-27
KID-26
KID-25
KID-24
KID-23
KID-22
1st intercostal space
Ren-17
2 cun


Ren-21
Ren-20


ST-13
1st intercostal space
ST-14


LU-2
Midline
1 cun
Midline
LU-1


ST-9
12
Ren 22
Ni 27
14 26
20
SP- 20
25
19
19
16
24
18
17
17
18
22
15
Le 14
G.B.-24
12
16
22
18
LIV-13
15
25
16
14
Sterno-costal angle
7
6
5
4
3
2
1
Umbilicus
1

Shu *Mansion* SHUFU KID-27


KID-27
KID-26
KID-25
KID-24
KID-23
KID-22
1st rib
Ren-17
2 cun

Location

At the lower border of the clavicle, 2 cun lateral to the anterior midline

How to find

When palpating parasternally from superior to inferior, the 1st rib can be felt directly below the clavicle; in some cases, it can be completely hidden under the clavicle. Therefore, **KID-27** will be located either on the 1st rib or, in some cases, at its lower border. → **ST-13** is located lateral to the short curvature of the 1st rib, below the midpoint of the clavicle.

Located on approximately the same level are → **Ren-21** (on the midline) and → **LU-2** (6 cun lateral to the midline).

Needling

0.5–0.8 cun obliquely or transversely (subcutaneously) along the course of the ICS or with or against the channel pathway. Caution: Pneumothorax.

Actions/Indications

- Regulates the Lung Qi and transforms Phlegm
- Unbinds the chest


C6
T1
Coracoid process
Glenoid cavity
Clavicle
Acromion
1st rib
2nd rib
3rd rib
Scapula
4th rib
Sternum
6th rib
7th rib
8th rib
10th rib
11th rib
T12
12th rib
L1


Ren-21
Ren-20




LU-2
Midline
1 cun
Midline

4.9 The Pericardium Channel System – Hand *jueyin* (*shou jue yin jing luo*)

4.9.1 Primary Pericardium Channel (*shou jue yin jing*)




Axillary fold
1
2
3
4
5
6
7
8
9
cun
P-1
P-2
1 cun lateral to the nipple
Biceps brachii
P-3
Cubital crease
1
2
3
4
5
6
7
8
9
10
11
12
cun
Brachioradialis
P-4
P-5
P-6
Tendon of the flexor carpi radialis
Tendon of the palmaris longus
Pisiform
P-7
Wrist crease


P-9
Palmar aspect
P-8
Pisiform
P-7
Wrist crease

Pathway

The Pericardium primary channel begins in the centre of the thorax on the level of → **Ren-17** (*shanzhong*), where an internal branch of the Kidney primary channel ends, having also connected with the Liver, Lung and Heart (deep Yin–Yin connection).

The Pericardium primary channel then divides into two branches:

- The **first branch** penetrates the diaphragm, descends to the abdomen and connects with the Upper, Middle and Lower Burner.
- A **further internal branch** also originates in the thoracic region, continues to the breast and emerges approximately 1 cun lateral to the nipple in the 4th intercostal space at **P-1** (*tianchi*). Beneath **P-1**, an internal branch of the Liver primary channel emerges from the Liver and joins the Pericardium primary channel (Yin axes of the third great circuit: *jueyin*).

The **external** pathway ascends to the axilla, follows the medial aspect of the upper arm between the Lung and Heart primary channels, passes the elbow and continues along the forearm between the tendons of the palmaris longus and flexor carpi ulnaris muscles, ending at the tip of the middle finger.

Another **internal** branch originates in the centre of the palm at **P-8** (*laogong*), runs along the ring finger and connects at its tip with the Triple Burner primary channel (hand Yin–Yang connection of the third circuit).

Clinical importance (→ 1.2)

Exterior *(biao)* signs and symptoms: Occipital stiffness, leg cramps, red complexion, eye pain, swellings in the subaxillary region, hypertonic musculature with limited range of motion of the arm and elbow, Heat sensations in the palms

Interior (*li*) or *zangfu*-Organ signs and symptoms: Delirious speech, confusion, irritability, fullness and distension in the thorax and lateral costal region, aphasia, palpitations

Connections of the Pericardium primary channel (→ 1.2)

Connections with other channels

Triple Burner primary channel (*shou shao yang jing*)

Connection: Hand Yin–Yang pairing of the third great circuit
Location: P-8 → T.B.-1 (on the hand)
Circulation: Circadian (according to the Organ clock)
Importance: Exterior–Interior relationship

Liver primary channel (*zu jue yin jing*)

Connection: Six-channel pairing of the third great circuit (Yin axes): *jue yin*
Location: LIV → P. An internal branch of the Liver primary channel emerges at the Liver, penetrates the diaphragm and connects with the Pericardium primary channel beneath **P-1** (*tianchi*).
Circulation: Non-circadian (**not** according to the Organ clock)
Importance: Above–below relationship

Kidney primary channel (*zu shao yin jing*)

Connection: Deep Yin–Yin connection
Location: KID → P (on the thorax). A branch of the internal pathway of the Kidney primary channel travels from the Kidney to the Liver, penetrates the diaphragm and spreads in the Lung (*fei*). From the Lung, an internal branch runs to the Heart (*xin*), where it joins the Pericardium primary channel (deep Yin–Yin connection) and further reaches → **Ren-17** (*shanzhong*).
Circulation: Circadian (according to the Organ clock)
Importance: The Pericardium primary channel receives Nutritive Qi (*ying qi*) from the Kidney primary channel (first circulation of the *ying qi* → 1.1.4).

Connections with *zangfu*-Organ systems

Pericardium (*xin bao*), Triple Burner (*san jiao*)

4.9.2 The Pericardium Divergent Channel (*shou jue yin jing bie*)



Pathway

The Pericardium divergent channel separates from the Pericardium primary channel near **P-1** (*tianchi*), 1 cun lateral to the nipple on the level of the 4th intercostal space. It

➡ runs in a lateral direction to → **G.B.-22** (*yuanye*)

➡ penetrates the thorax, continues to the Heart (*xin*) and divides into **two branches:**

- **one branch** connects with the Upper, Middle and Lower Burner
- the **other branch** ascends to the neck to → **Ren-23** (*lianquan*) and continues to the lateral aspect of the neck, emerges at → **T.B.-16** (*tianyou*) on the posterior border of the sternocleidomastoid muscle on the level of the mandibular angle, connecting with the Triple Burner primary channel and the Triple Burner divergent channel to form one of the 6 *he*-confluences (here: P/T.B. as 5th Confluence → 1.3)

Clinical importance

- Strengthens the relationship between the Pericardium and the Triple Burner (*zangfu*-Organ systems). Points on the Pericardium primary channel can therefore be used for disorders of the Triple Burner; vice versa, points on the Triple Burner primary channel can treat disorders of the Pericardium.

- In contrast to the Pericardium primary channel, the Pericardium divergent channel reaches the occiput and the neck. This explains why several points on the P channel can be used for disorders of the neck and ears, chronic throat pain, etc.
- By reaching the thorax, breast and hypochondrium, the Pericardium divergent channel supports the relationship between the Pericardium primary channel and these regions.

4.9.3 The Pericardium Sinew Channel (*shou jue yin jing jin*)



Pathway

The Pericardium sinew channel begins at the tip of the middle finger

- ➡ runs along the anterior aspect of the middle finger and along the 3rd metacarpal bone
- ➡ spreads in the centre of the palm and meets the Lung sinew channel
- ➡ binds (*jie*) in the centre of the wrist
- ➡ ascends the anterior aspect of the forearm as well as the anteromedial aspect of the upper arm to the axilla, binding (*jie*) at **P-3** (*quze*) on the elbow and at → **G.B.-22** (*yuanye*), where it meets the other hand Yin sinew channels.

At → **G.B.-22**, the channel separates into two branches:

- **one branch** disperses on the anterior, lateral and posterior aspects of the costal region
- **the other branch** penetrates the thorax below the axilla and reaches the midthoracic region on the level of → **Ren-17** (*shanzhong*), from where it spreads in the thoracic cavity to bind (*jie*) at the diaphragm.

Clinical importance

Pathology: Stiffness, pain, spasms and distending sensations along the pathway of the Pericardium sinew channel. Thoracic pain and tightness, *xi fen* syndrome (one of the five *ji*-syndromes, an ‘accumulation syndrome’) due to Lung Qi stagnation with accumulation of Phlegm and Heat manifesting with symptoms such as masses in the right hypochondriac region, possibly accompanied by thoracic or back pain, haemoptysis, chills and fever, shortness of breath and dyspnoea, etc.

Indication: Mainly for pain, spasms and distending sensations along the pathway of the sinew channel, limited range of motion along the medial aspect of the arm and elbow, swellings and pain in the axilla and the breast.

4.9.4 The Pericardium *luo*-Connecting Vessel System (*shou jue yin luo mai*)



Pathway

The *luo*-connecting Pericardium vessel system separates from the Pericardium primary channel at its associated *luo*-connecting point **P-6** (*neiguan*) (→ 8.1.2). It forms a three-dimensional reticular network, dividing into multiple branches and sub-branches (*sun luo, fu luo, xue luo* → 1.5) within the surrounding tissue.

- Horizontal divisions run to the Interiorly–Exteriorly paired Triple Burner primary channel; according to some schools of thought (for example, Ngyen Van Nghi → Appendix), they travel as a **transverse** Pericardium *luo*-connecting vessel to the *yuan*-source point → **T.B.-4** (*yangchi*).
- **A longitudinal division** follows the Pericardium primary channel along the anterior aspect of the arm, crosses → **Ren-17** (*shanzhong*) on the midline on the level of the 4th intercostal space, penetrates the thorax and terminates at the Pericardium (*xin bao*) and the Heart (*xin*).

Clinical importance (→ 8.1.2)

Pathology

Excess (*shi*): Heart pain, angina pain, thoracic pain
Deficiency (*xu*): Restlessness, irritability

4.9.5 Cutaneous Region (*jue yin pi bu*)

See description and figures → 1.6.

4.9.6 Points of the Primary Pericardium Channel (Overview)

Specific points according to their function

- ***Yuan*-source point (→ 8.1.1): P-7** (*daling*) 🟦■
- ***Luo*-connecting point (→ 8.1.2.): P-6** (*neiguan*) 🟦🟦
- ***Xi*-cleft point (→ 8.1.3): P-4** (*ximen*) 🟦■
- **Associated Back-*shu* point (→ 8.1.4): BL-14** (*jueyinshu*)
- **Associated Front-*mu* point (→ 8.1.5): Ren-17** (*shanzhong*) 🟦🟦
- **Five *shu*-transporting points (→ 8.1.6):**
  jing-well point (Wood), tonification point: **P-9** (*zhongchong*) 🟦■
  ying-spring point (Fire), *ben* point (Five Phases): **P-8** (*laogong*) 🟦■
  shu-stream point (Earth), sedation point: **P-7** (*daling*) 🟦■
  jing-river point (Metal): **P-5** (*jianshi*) 🟦■
  he-sea point (Water): **P-3** (*quze*) 🟦■
- ***Hui*-meeting point (→ 8.1.7): –**
- **Opening point (→ 8.1.8) of the *yin wei mai:* P-6** (*neiguan*) 🟦🟦
- **Lower *he*-sea point (→ 8.1.9): –**
- ***Jiaohui*-meeting points (→ 8.1.10):**
  – with the LIV, T.B., G.B.* channels: **P-1** (*tianchi*)
  – of other channels with the Pericardium channel: –
- **Gao Wu command point (→ 8.1.11) for the thoracic region: P-6** (*neiguan*) 🟦🟦
- **Window of Heaven point (→ 8.1.12): P-1** (*tianchi*)
- **Points of the Four Seas (→ 8.1.13): –**
- **Ma Dan Yang Heavenly Star point (→ 8.1.14): –**
- **Sun Si Miao Ghost point (→ 8.1.15): P-7** (*daling*) 🟦■, **P-8** (*laogong*) 🟦■
- **Other functional points:**
  – important point for eliminating Phlegm misting the orifices: **P-5** (*jianshi*) 🟦■
  – important point for calming the *shen*: **P-6** (*neiguan*) 🟦🟦

Points according to region

- **Local points (→ 8.2.1):** hand – **P-7** (*daling*) 🟦■
- **Adjacent points (→ 8.2.1): –**
- **Distal points (→ 8.2.1):** tongue – **P-8** (*laogong*) 🟦■; Lung – **P-6** (*neiguan*) 🟦🟦; Heart – **P-4** (*ximen*) 🟦■; **P-6** (*neiguan*) 🟦🟦; Spleen – **P-6** (*neiguan*) 🟦🟦; thorax and epigastrium – **P-6** (*neiguan*) 🟦🟦; foot – **P-7** (*daling*) 🟦■

Specific points according to the channel pathway (in numeric order)

- **P-1** (*tianchi*) 🟦■: *jiaohui*-meeting point with the LIV, T.B., G.B.* channels (→ 8.1.10); Window of Heaven point (→ 8.1.12)
- **P-3** (*quze*) 🟦■: lower *he*-sea point (Water) (→ 8.1.6)
- **P-4** (*ximen*) 🟦■: *xi*-cleft point (→ 8.1.3); distal point for the Heart (→ 8.2.1)
- **P-5** (*jianshi*) 🟦■: *jing*-river point (Metal) (→ 8.1.6); important point for eliminating Phlegm misting the orifices
- **P-6** (*neiguan*) 🟦🟦: *luo*-connecting point (→ 8.1.2); Gao Wu command point (→ 8.1.11) for the thorax; Opening point (→ 8.1.8) of the *yin wei mai*; distal point for the Heart, Spleen, thorax and epigastrium (→ 8.2.1); important point for calming the *shen*
- **P-7** (*daling*) 🟦■: *yuan*-source point (→ 8.1.1); *shu*-stream point (Earth) (→ 8.1.6); sedation point; Sun Si Miao Ghost point (→ 8.1.15); local point for the hand (→ 8.2.1); distal point for the foot (→ 8.2.1)
- **P-8** (*laogong*) 🟦■: *ying*-spring point (Fire) (→ 8.1.6); *ben* point (Five Phases); Sun Si Miao Ghost point (→ 8.1.15); distal point for the tongue (→ 8.2.1)
- **P-9** (*zhongchong*) 🟦■: *jing*-well point (Wood) (→ 8.1.6); tonification point

---

* Mentioned by only some authors

Ch04.9-F10028.qxd 2/23/08 3:57 PM Page 353

Heavenly Pool TIANCHI P-1


1cun
P-1
4th intercostal space
5th intercostal space
6th intercostal space

Location

In the 4th intercostal space (ICS), 1 cun lateral to the nipple.

How to find

Quick method, especially in male patients: The 4th ICS is located on the same level as the nipple. Locate **P-1** 1 cun lateral to the nipple in the 4th ICS (note: ascending course of the ICS towards lateral). **Or:** For better orientation in the intercostal region, first, locate the manubriosternal synchondrosis (→ 3.4.2.). This is on the level of the costal cartilage of the 2nd rib, followed by the 2nd ICS below it. Count down to ICS to the 4th ICS and measure 5 cun in a lateral direction. There, locate **P-1**.

Located on the same level (4th ICS) are → **Ren-17** (on the midline), → **KID-23/ST-17/SP-18** (2/4/6 cun lateral to the midline), as well as → **G.B.-22** and → **G.B.-23**.

Needling

0.5–1 cun transversely (subcutaneously) along the course of the ICS. Especially in women, transverse needling only, avoid puncturing the mamillary tissue. Caution: Pneumothorax.

Actions/Indications

- Descends counterflow Qi
- Eliminates excess (especially Heat and Phlegm) from the thorax
- Promotes lactation and eliminates local Qi stagnation

Special features

Meeting point with the LIV and T.B. channels, also with the G.B. channel according to some authors. Window of Heaven point, entry point.


ST-9
12
Ren 22
KID-27
14
26
20
SP- 20
25
19
19
16
24
18
17
17
18
22
15
LIV-14
G.B.-24
16
22
18
LIV-13
15
25
16
8
Sterno-costal angle
7
6
5
4
3
2
1
Umbilicus


Level of the nipple
4th intercostal space
Ren-17


KID-24
KID-23
KID-22
4th intercostal space
Ren-17


ST-13
Clavicle
Midclavicular line
ST-17
ST-18
LIV-14
G-B.-24
Mamillary line
ca. 4 cun

P-2 *Heavenly Spring* TIANQUAN

Location

Between the two heads of the biceps brachii muscle, 2 cun inferior to the axillary fold.

How to find

Locate the biceps brachii muscle through slight external rotation; in patients with less muscle definition, ask the patient to flex their elbow against resistance. **P-2** is located between the two heads of the biceps brachii muscle, 2 cun inferior to the upper end of the anterior axillary fold (➞ 2.2).

➞ **LU-3** is located radial to **P-2,** on the lateral aspect of the biceps brachii muscle and 1 cun more distally.

Needling

1–1.5 cun obliquely in a proximal or lateral direction.

Actions/Indications

- Unbinds the chest.
- Nourishes and invigorates the Blood
- Calms the *shen*


Anterior end of the axillary fold
2 cun
P-2
7 cun
Cubital crease
P-3


LU-2
LU-1
HE-1
P-1
P-2
LU-3
LU-4
HE-2
LU-5
P-3
HE-3
1
2
3
4
5
6
7
8
9
cun
1
2
3


Lateral border of the biceps muscle
LU-3

Marsh at the Crook QUZE P-3

Location

On the cubital crease, on the ulnar side of the biceps tendon, between the tendon and the brachial artery.

How to find

Place the patient's arm in a relaxed supinated position. This point is best located with the elbow bent and the biceps flexed in order to make the tendon and elbow crease more clearly visible and palpable. **P-3** is located on the cubital crease, on the ulnar aspect of the tendon.
Also located in the area of the cubital crease are → **LU-5** (on the radial side of the tendon), → **L.I.-11** (between the radial end of the crease and the lateral epicondyle of the humerus) and → **HE-3** (with the elbow fully flexed, at the ulnar end of the cubital crease).

Needling

0.5–1 cun vertically or prick to cause bleeding of the vein. Caution: Brachial artery/vein. Palpate for the pulse before needling.

Actions/Indications

- Clears Heat, drains Fire
- Harmonises the Stomach and Intestines, stops vomiting
- Opens the channel, alleviates pain

Special features

He-sea point, Water point. Important local point and important point to drain Heat. For Heat conditions, apply bloodletting.


Contraction of the biceps tendon
Biceps tendon
P-3
Cubital crease


Biceps
Biceps tendon
P-3
Cubital crease
LU-5
HE-3


90°
L.I.-11
Lateral epicondyle
Olecranon

P-4 Xi *Cleft Gate* XIMEN

Location

5 cun proximal to the anterior space of the wrist joint (most distal wrist crease), between the tendons of the palmaris longus and flexor carpi radialis muscles.

How to find

Spreading hands technique (➞ 2.3.3): Place the little fingers in the centre of the anterior wrist joint space (➞ 3.3.3, ➞ **P-7**) and the cubital crease respectively (➞ **P-3**). From the midpoint of this distance, measure 1 cun in a distal direction. On this level, locate **P-4** between the two tendons, which become more pronounced when the fingertips are pressed together. If only one tendon is visible, this will be the tendon of the flexor carpi radialis muscle. **P-4** is located on its ulnar aspect.

Needling

0.5–1 cun vertically or 1–1.5 cun obliquely in a proximal direction.

Actions/Indications

- Tonifies the Blood, dispels Blood stasis
- Calms the *shen*
- Cools the Blood
- Opens the channel

Special features

Xi-cleft point. Major point for acute, painful Blood stasis in the region of the thorax and the Heart


P-3
Cubital crease
7 cun
Tendon of the palmaris longus
P-4
Tendon of the flexor carpi radialis
5 cun
Wrist joint space
P-7
Pisiform


1
2
3
4
5
6
7
8
9
10
11
12 cun
LU-5
P-3
HE-3
LU-6
P-4
P-5
P-6
LU-7
LU-8
LU-9
HE-4
HE-5
HE-6
HE-7
P-7
LU-10
P-8
HE-8
LU-11
HE-9
P-9


Biceps tendon
P-3
Cubital crease

Intermediary Messenger JIANSHI P-5


Pressing the thumb and little finger together for better presentation of the tendons
Tendon of the flexor carpi radialis
Tendon of the palmaris longus
P-7
P-5
3 cun
Pisiform
Wrist joint space




Brachialis
Triceps brachii, lateral head
Brachioradialis
Triceps brachii, medial head
Extensor carpi radialis longus
Tendon of the triceps brachii
T.B.-10
L.I.-11
Olecranon
Lateral epicondyle
Flexor carpi ulnaris
Extensor digitorum
Extensor carpi ulnaris

Location

3 cun proximal to the anterior wrist joint space (‘most distal wrist crease’), between the tendons of the palmaris longus and flexor carpi radialis muscles.

How to find

As the location of the wrist crease varies, the wrist joint space is a more reliable reference point (→ 3.3.3). It can easily be palpated by moving the patient’s hand in a relaxed way. From the centre of the joint space (→ **P-7**), measure 3 cun in a proximal direction and locate **P-5** between the two tendons, which become more pronounced when the fingertips are pressed together. If only one tendon is visible, this will be the tendon of the flexor carpi radialis muscle. **P-5** is located at its ulnar aspect.

Needling

0.5–1 cun vertically or obliquely in a proximal direction. Caution: The median nerve here is only covered by the radial head of the flexor digitorum superficialis. Vertical needling should not exceed 0.5 cun; no strong needle stimulation.

Actions/Indications

- Calms the *shen* and the Heart
- Harmonises the Middle Burner
- Clears Heart Fire
- Unbinds the chest
- Transforms invisible Phlegm

Special features

Jing-river point, Metal point. Important point for transforming Phlegm blocking the orifices.

P-6 *Inner Gate* NEIGUAN

Location

2 cun proximal to the anterior wrist joint space ('most distal wrist crease'), between the tendons of the palmaris longus and flexor carpi radialis muscles.

How to find

As the location of the wrist crease varies, the wrist joint space is a more reliable reference point (→ 3.3.3). It can easily be palpated by moving the patient's hand in a relaxed way. From the centre of the wrist joint space (→ **P-7**), measure 2 cun in a proximal direction and locate **P-6** between the two tendons, which become more pronounced when the fingertips are pressed together. If only one tendon is visible, this will be the tendon of the flexor carpi radialis muscle. **P-6** is located on its ulnar aspect.

Or quick method: From the centre of the wrist joint space, glide in a proximal direction between the two tendons. The skin will begin to form a bulge in front of the sliding finger, which will come to a halt at **P-6.**

→ **T.B.-5** (2 cun proximal to the dorsal wrist joint space) is located opposite **P-6**.

Needling

0.5–1 cun vertically or obliquely in a proximal or lateral direction. Caution: The median nerve is located directly below this point.

Actions/Indications

- Calms the *shen*
- Unbinds the chest
- Harmonises the Stomach
- Opens the channel

Special features

Luo-connecting point, opening (master) point of the *yin wei mai*, Gao Wu command point for the thorax. Main point for nausea and vomiting. Very important point.


Pressing the thumb and little finger together for better presentation of the tendons
Tendon of the flexor carpi radialis
Tendon of the palmaris longus
2 cun
P-7
P-6
Pisiform
Wrist joint space






T.B.-5
Joint space
T.B.-4


1
2
3
4
5
6
7
8
9
10
11
12
cun
LU-5
P-3
HE-3
LU-6
P-4
P-5
LU-7
P-6
LU-8
LU-9
P-7
HE-4
HE-5
HE-6
HE-7
LU-10
LU-11
P-8
HE-8
HE-9
P-9

Great Mound DALING **P-7**


Pressing the thumb and little finger together for better presentation of the tendons
Tendon of the flexor carpi radialis
Tendon of the palmaris longus
P-7
Pisiform
Wrist joint space


Tendon of the flexor carpi ulnaris
Tendon sheath of the flexor carpi radialis
Abductor digiti minimi
Opponens pollicis
Flexor pollicis brevis
Abductor pollicis brevis


Tendon of the flexor carpi radialis
Tendon of the palmaris longus
Tendon of the flexor carpi ulnaris
Wrist joint space
Pisiform
HE-7
P-7
LU-9

Location

On the anterior aspect of the wrist joint space ('most distal wrist crease'), between the tendons of the palmaris longus and flexor carpi radialis muscles.

How to find

As the location of the wrist crease varies, the wrist joint space is a more reliable reference point (→ 3.3.3). By moving the patient's hand in a relaxed way, it can easily be palpated. Locate **P-7** on this level between the two tendons, which become more pronounced when the fingertips are pressed together. If only one tendon is visible, this will be the tendon of the flexor carpi radialis muscle. **P-7** is located on its ulnar aspect.

Located on the same level are → **HE-7** (on the ulnar aspect of the wrist joint, radial to the tendon of the flexor carpi ulnaris muscle) and → **LU-9** (on the radial aspect of the wrist joint, lateral to the radial artery.

Needling

Vertically 0.3–0.5 cun, for carpal tunnel syndrome also 0.5–1 cun obliquely in a lateral direction along the tunnel. Caution: The median nerve is located directly under this point, thus needling can cause a significant electric sensation; in this case, no further needle manipulation to avoid possible injury.

Actions/Indications

- Clears Heat from the Heart, calms the *shen*
- Harmonises the Stomach and Intestines
- Cools Heart Fire affecting the Bladder
- Unbinds the chest
- Cools the Blood
- Opens the channel, alleviates pain

Special features

Yuan-source point, *shu*-stream point, Earth point, sedation point, Sun Si Miao Ghost point. Important point for calming, main point for carpal tunnel syndrome.

P-8 *Palace of Toil* LAOGONG

Location

In the centre of the palm, between the 2nd and 3rd metacarpal bones, slightly closer to the 3rd metacarpal bone.

How to find

When making a loose fist, the tip of the middle finger will rest on **P-8,** between the 2nd and 3rd metacarpal bones, slightly closer to the 3rd metacarpal bone.

→ **HE-8** is located more radially, between the 4th and 5th metacarpal bones.

Needling

Vertically 0.3–0.5 cun. Thinner needles should be used as needling this point can be painful.

Actions/Indications

- Clears Heart Fire and calms the *shen*
- Harmonises the Middle Burner
- Clears the *ying*-nutritive level and cools the Blood

Special features

Ying-spring point, Fire point, *ben* point (Five Phases), Sun Si Miao Ghost point, exit point.







Middle Rushing ZHONGCHONG P-9



Location

On the most distal point of the middle finger.

How to find

Find the most distal point on the tip of the middle finger and there locate **P-9**.

Needling

Vertically 0.1–0.2 cun or prick to bleed. Caution: Painful point.

Actions/Indications

- Clears Heat, especially from the Heart and Pericardium
- Strengthens collapsed Yang
- Expels internal Wind

Special features

Jing-well point, Wood point, tonification point.

4.10 The Triple Burner Channel System – Hand *shaoyang* (*shou shao yang jing luo*)

4.10.1 Triple Burner Primary Channel (*shou shao yang jing*)



Pathway

The **external pathway** of the Triple Burner primary channel begins on the ring finger, at the ulnar corner of the nail at **T.B.-1** (*guanchong*). **T.B.-1** is reached by a branch of the Pericardium primary channel that separates on the palm of the hand at → **P-8** (*laogong*) (hand Yin–Yang connection of the third great circuit). The channel runs along the ulnar side of the ring finger

- continues between the 4th and 5th metacarpal bones
- travels along the posterior aspect of the forearm between the radius and the ulna towards the lateral aspect of the arm
- passes the olecranon and continues along the upper arm to the shoulder
- traverses the shoulder, intersects with → **S.I.-12** (*bingfeng*) and meets the other Yang primary channels at → **Du-14** (*dazhu*)
- runs to the anterior aspect of the body, crossing → **G.B.-21** (*jianjing*) and → **ST-12** (*quepen*), the latter in the supraclavicular fossa.

At **ST-12,** the channel enters the body to begin its **internal** section. It meets the Pericardium (*xin bao*) at → **Ren-17** (*shanzhong*), penetrates the diaphragm and enters the abdomen, connecting with the Upper, Middle and Lower Burners.

From the Lower Burner, an **internal branch** (according to some authors, the T.B. channel) descends to the popliteal fossa to → **BL-39** (*weiyang*), the lower *he*-sea point of the Triple Burner.

A further **inner branch** originates in the thorax at → **Ren-17** (*shanzhong*), emerges at the supraclavicular fossa and ascends to the posterior border of the sternocleidomastoid muscle to **T.B.-16**, follows via **T.B.-17, T.B.-18, T.B.-19** the temporal bone along its border behind the ear and reaches **T.B.-20** (*jiasun*) above the apex of the ear. It crosses the Gall Bladder primary channel at **G.B.-6** (*xuanli*), **G.B.-5** (*xuanlu*) and **G.B.-4** (*hanyan*), according to Deadman et al 1998) also at **G.B.-11** (*touqiaoyin*) and **G.B.-14** (*yangbai*), descends the cheek to the lower jaw and ascends again to intersect with → **S.I.-18** (*quanliao*) on the lower border of the zygomatic arch and continues to the infraorbital region.

From **T.B.-17** (*yifeng*), a branch penetrates the ear, emerges to the **Exterior** anterior to the tragus, intersects with → **S.I.-19** (*tinggong*), continues past **T.B.-21** (*ermen*) and **T.B.-22** (*erheliao*), meets → **G.B.-3** (*shangguan*), crosses its own cheek branch and ends at **T.B.-23** (*sizhukong*) on the frontozygomatic suture.

From **T.B.-23**, or, according to some authors from **T.B.-22**, a small branch runs to → **G.B.-1** (*tongziliao*) at the lateral canthus of the eye (Yang axes of the third great circuit: *shao yang*).

Clinical importance (→ 1.2)

Exterior (*biao*) signs and symptoms: Neck pain, cheek pain, red and painful eyes, deafness, pain behind the ears, pain on the posterior aspect of the shoulder and the upper arm

Interior (*li*) or *zangfu*-Organ signs and symptoms: Abdominal fullness and distension, difficult urination, skin oedema and skin swellings, enuresis

Connections of the Triple Burner primary channel (→ 1.2)

Connections with other channels

Pericardium primary channel (*shou jue yin jing*)

Connection: Hand Yin–Yang pairing of the third great circuit
Location: P-8 → **T.B.-1** (on the hand).
Circulation: Circadian (according to the Organ clock)
Importance: Exterior–Interior relationship

Gall Bladder primary channel (*zu shao yang jing*)

Connection: Paired according to the six-channel theory (hand–foot pairing): *shao yang* (Yang axes of the third great circuit)
Location: T.B.-23 (or **T.B.-22**) → **G.B.-1** (on the head).
Circulation: Circadian (according to the Organ clock)
Importance: Above–below relationship

Connections with *zangfu*-Organ systems
Pericardium (*xin bao*), Triple Burner (*san jiao*)



4.10.2 The Triple Burner Divergent Channel (*shou shao yang jing bie*)

Pathway

The Triple Burner divergent channel separates from the Triple Burner primary channel near **T.B.-20** (*jioasun*)

- ➡ ascends to → **Du-20** (*baihui*)
- ➡ descends along the posterior aspect of the ear to the neck to **T.B.-16** (*tianyou*) on the posterior border of the sternocleidomastoid muscle, where it connects with the Triple Burner primary channel and the Pericardium primary channel to form one of the six *he*-confluences (here: P/T.B. as fifth confluence → 1.3)
- ➡ The Triple Burner divergent channel further descends to → **ST-12** (*quepen*) in the supraclavicular fossa, penetrates the thorax, disperses in the Pericardium (*xin bao*) and reaches the Upper, Middle and Lower Burners.

Clinical importance

- Strengthens the relationship between the Upper, Middle and Lower Burners. T.B. points can be used for disorders affecting these areas and Organs.
- The Triple Burner divergent channel reaches the vertex at → **Du-20**. Therefore, T.B. points can be used for headaches, dizziness, etc, but also to raise the Yang Qi for prolapse, etc.
- The Triple Burner divergent channel spreads in the thorax, so that T.B. points can be used to support the treatment of thoracic problems such as pain, coughing etc.



4.10.3 The Triple Burner Sinew Channel (*shou shao yang jing jin*)

Pathway

The Triple Burner sinew channel begins on the ring finger, at the ulnar corner of the nail at **T.B.-1** (*guanchong*)

- ➡ travels between the 4th and 5th metacarpal bones to the wrist
- ➡ binds (*jie*) at **T.B.-4** (*yangchi*)
- ➡ continues along the posterior aspect of the forearm between the Small Intestine and Large Intestine sinew channels, binds (*jie*) at the olecranon, ascends the posterior aspect of the upper arm to bind (*jie*) at the posterior corner of the acromion, traverses the posterior aspect of the shoulder and the lateral aspect of the occiput and there meets the Small Intestine sinew channel. It then reaches the mandibular angle, where it divides into **two branches**:
- ➡ **One branch** enters internally and penetrates the root of the tongue

➡ **The other branch** ascends in front of the ear, binds (*jie*) at the outer canthus of the eye, crosses the temple and terminates at → **G.B.-13** (*benshen*) in the frontoparietal region. There, it also meets the other hand Yang sinew channels.

Clinical importance

Pathology: Stiffness, swellings and distending sensations along the course of the sinew channel. Curling or contraction of the tongue.

Indication: Predominantly for pain, stiffness, spasms, tension and distending sensations along the course of the channel, including the lateral aspects of the head and the body as well as the lateral sections of the extremities. T.B. points can also be used for muscle tension caused by emotional disorders. Owing to the connection of the sinew channel with the tongue, some T.B. points are also indicated for motor disorders of the tongue.



4.10.4 The Triple Burner *luo*-Connecting Vessel System (*shou shao yang luo mai*)

Pathway

The Triple Burner *luo*-connecting vessel system separates from the Triple Burner primary channel at its associated *luo*-connecting point **T.B.-5** (*waiguan*) (→ 8.1.2). It forms a three-dimensional reticulate network, dividing into multiple branches and sub-branches (*sun luo, fu luo, xue luo* → 1.5) within the surrounding tissue.

➡ Horizontal divisions run to the Interiorly–Exteriorly paired Pericardium primary channel; according to some schools of thought (for example Ngyen Van Nghi → Appendix), they travel as a **transverse** Triple Burner *luo*-connecting vessel to the *yuan*-source point **P-7** (*daling*).

➡ **A longitudinal division** follows the posterior aspect of the arm, crosses the posterior shoulder region, continues to the front of the body and, according to some authors (for example, Solinas et al 1998), reaches → **ST-12** (*quepen*) in the supraclavicular fossa, penetrates the thorax and reaches the Pericardium primary channel, both dispersing in the Upper, Middle and Lower Burners.

Clinical importance

Pathology

Excess (*shi*): Tension of the elbow joint

Deficiency (*xu*): Muscle weakness in the arm, difficulty flexing the elbow

4.10.5 Cutaneous Region (*shao yang pi bu*)

See description and figures → 1.6.

4.10.6 Points of the Triple Burner Primary Channel (Overview)

Specific points according to their function

- ***Yuan*-source point** (→ **8.1.1): T.B.-4** (*yangchi*)
- ***Luo*-connecting point** (→ **8.1.2.): T.B.-5** (*waiguan*) 🟦🟦
- ***Xi*-cleft point** (→ **8.1.3): T.B.-7** (*huizong*)
- **Associated Back-*shu* point** (→ **8.1.4): BL-22** (*sanjiaoshu*)
- **Associated Front-*mu* point** (→ **8.1.5): Ren-5** (*shimen*)
- **Five *shu*-transporting points** (→ **8.1.6):**
  jing-well point (Metal): **T.B.-1** (*guanchong*)
  ying-spring point (Water): **T.B.-2** (*yemen*)
  shu-stream point (Wood), tonification point: **T.B.-3** (*zhongzhu*)
  jing-river point (Fire), *ben point* (Five Phases): **T.B.-6** (*zhigou*)
  he-sea point (Earth), sedation point: **T.B.-10** (*tianjing*)
- ***Hui*-meeting point** (→ **8.1.7): –**
- **Opening point** (→ **8.1.8) of the *yin wei mai*: T.B.-5** (*waiguan*) 🟦🟦
- **Lower *xiahe*-sea points** (→ **8.1.9): –**
- ***Jiaohui*-meeting points** (→ **8.1.10):**
  – with the *yang wei mai* and the G.B. channel: **T.B.-13*** (*naohui*)
  – with the *yang wei mai* and the G.B. channel: **T.B.-15** (*tianliao*) 🟦■
  – with the G.B. channel: **T.B.-17** (*yifeng*) 🟦■
  – with the S.I.* and G.B. channel: **T.B.-20** (*jiaosun*)
  – with the S.I. and G.B. channels: **T.B.-22** (*erheliao*)

---

* Mentioned by only some authors

  - of other channels with the T.B. channel: **S.I.-12, BL-11, (S.I.-18, S.I.-19*), Du-14, Ren-12, Ren-17, ST-12, G.B.-21, G.B.-14, G.B.-11, G.B.-6, G.B.-5, G.B.-4, G.B.-3, G.B.-1, (S.I.-9*)**
- **Gao Wu command point (→ 8.1.11): –**
- **Window of Heaven point (→ 8.1.12): T.B.-16** (*tianyou*)
- **Points of the Four Seas (→ 8.1.13): –**
- **Ma Dan Yang Heavenly Star point (→ 8.1.14): –**
- **Sun Si Miao Ghost point (→ 8.1.15): –**
- **Other functional points: –**

Points according to region

- **Local points (→ 8.2.1):** ears – **T.B.-21** (*ermen*) 🟦■; shoulder – **T.B.-14** (*jianliao*) 🟦■, **T.B.-15** (*tianliao*) 🟦■
- **Adjacent points (→ 8.2.1):** temporal aspect of the head – **T.B.-17** (*yifeng*) 🟦■; eyes – **T.B.-23** (*sizhukong*) 🟦■; ears – **T.B.-17** (*yifeng*) 🟦■; jaw – **T.B.-17** (*yifeng*) 🟦■; shoulder – **T.B.-13** (*naohui*), **T.B.-15** (*tianliao*) 🟦■
- **Distal points (→ 8.2.1):** temporal aspect of the head – **T.B.-3** (*zhongzhu*) 🟦■, **T.B.-5** (*waiguan*) 🟦🟦; ears – especially **T.B.-3** (*zhongzhu*), **T.B.-5** (*waiguan*) 🟦🟦; hypochondrium – **T.B.-5** (*waiguan*) 🟦🟦, **T.B.-6** (*zhigou*); cervical spine – **T.B.-8** (*sanyangluo*); cervical spine and shoulder – **T.B.-5** (*waiguan*) 🟦🟦; shoulder – **T.B.-1** (*guanchong*)

Specific points according to the channel pathway (in numeric order)

- **T.B.-1** (*guanchong*): *jing*-well point (Metal) (→ 8.1.6); distal point for the shoulder (→ 8.2.1)
- **T.B.-2** (*yemen*): *ying*-spring point (Water) (→ 8.1.6)
- **T.B.-3** (*zhongzhu*): *shu*-stream point (Wood) (→ 8.1.6); tonification point; distal point for the temporal region and the ears (→ 8.2.1); local point for the fingers (numbness and pain) (→ 8.2.1)
- **T.B.-4** (*yangchi*): *yuan*-source point (→ 8.1.1); local point for the hand (→ 8.2.1)
- **T.B.-5** (*waiguan*) 🟦🟦: *luo*-connecting point (→ 8.1.2); Opening point (→ 8.1.8) of the *yang wei mai*; distal point for the temporal region, the ears, the cervical spine, the shoulder, the elbow and the hypochondrium (→ 8.2.1); regional point for the hand and fingers (→ 8.2.1)
- **T.B.-6** (*zhigou*): *jing*-river point (Fire) (→ 8.1.6); *ben* point (Five Phases); distal point for the hypochondrium (→ 8.2.1)
- **T.B.-7** (*huizong*): *xi*-cleft point (→ 8.1.3)
- **T.B.-8** (*sanyangliao*): distal point for the cervical spine (→ 8.2.1)
- **T.B.-10** (*tianjing*): *he*-sea point (Earth) (→ 8.1.6); sedation point; local point for the elbow (→ 8.2.1)
- **T.B.-13** (*naohui*): *jiaohui*-meeting point (→ 8.1.10) of the *yang wei mai** and the G.B. channel*; adjacent point for the shoulder (→ 8.2.1)
- **T.B.-14** (*jianliao*) 🟦■: local point for the shoulder (→ 8.2.1)
- **T.B.-15** (*tianliao*) 🟦■: *jiaohui*-meeting point of the *yang wei mai* and the G.B. channel; local point for the shoulder (→ 8.2.1)
- **T.B.-16** (*tianyou*): Window of Heaven point (→ 8.1.12)
- **T.B.-17** (*yifeng*) 🟦■: *jiaohui*-meeting point of the G.B. channel; adjacent point for the temporal region, the ears and the jaw (→ 8.2.1)
- **T.B.-20** (*jiaosun*): *jiaohui*-meeting point of the S.I.* and G.B. channels
- **T.B.-21** (*ermen*) 🟦■: local point for the ears (→ 8.2.1)
- **T.B.-22** (*erheliao*): *jiaohui*-meeting point with the S.I. and G.B. channels
- **T.B.-23** (*sizhukong*) 🟦■: adjacent point for the eyes (→ 8.2.1)

---

*Mentioned only by some authors

Rushing Pass **GUANCHONG** **T.B.-1**



Location

On the ring finger, 0.1 cun from the ulnar corner of the nail.

How to find

This point is located at the junction of two tangents bordering the ulnar and proximal margins of the nail, approximately 0.1 cun from the corner of the actual nail.

Needling

Approximately 0.2 cun vertically or obliquely in a proximal direction or prick to bleed. Caution: Avoid needling too close to the nail; painful point.

Actions/Indications

- Clears Heat from the Upper Burner
- Benefits the ears and tongue
- Opens the channel and alleviates pain

Special features

Jing-well point, Metal point, entry point. Especially indicated for acute disorders.



T.B.-2 *Fluid Gate* YEMEN

Location

Between the little finger and ring finger, proximal to the margin of the web.

How to find

This point is best located when making a loose fist. Locate the web between the little finger and ring finger (4th and 5th fingers) and locate **T.B.-2** proximal to its margin. **T.B.-2** is part of → **Ex-UE-9** (*baxie*: proximal to the webs between the fingers). Located in a comparable position on the foot is → **G.B.-43** (on the web between the 4th and 5th toes), which is also part of → **Ex-LE-10** (*bafeng*).

Needling

Vertically up to 0.5 cun

Actions/Indications

- Clears Heat from the Upper Burner
- Benefits the ears and calms the *shen*
- Opens the channel and alleviates pain

Special features

Ying-spring point, Water point. Especially indicated for psycho-neurological disorders caused by Heat and local channel problems.


T.B.-2
Proximal to the interdigital fold


L.I.-1
T.B.-1
S.I.-1
Ex-UE-
(baxie)
L.I.-2
L.I.-3
Ex-UE-8
T.B.-2
S.I.-2
Ex-UE-9
(baxie)
L.I.-4
T.B.-3
S.I.-3






Proximal to the interdigital fold
G.B.-43

Central Islet ZHONGZHU T.B.-3



Location

On the dorsum of the hand, in a depression between the 4th and 5th metacarpal bones, proximal to the metacarpophalangeal joints. **T.B.-3** is located at the junction between the heads and shafts of the two metacarpal bones.

How to find

The hand should be relaxed or a loose fist should be made. Palpate from the metacarpophalangeal joints along the groove between the 4th and 5th metacarpal bones towards proximal. **T.B.-3** is located at the widest/deepest point of the groove, slightly distal to the carpometacarpal joints.

Located in comparable positions are → **Ex-UE-8** (*wailaogong*: between the 2nd and 3rd metacarpal bones), → **S.I.-3** (on the ulnar aspect of the 5th metacarpal bone) and → **L.I.-3** (on the radial aspect of the 2nd metacarpal bone).

Needling

0.5–1 cun vertically or obliquely in a proximal direction.

Actions/Indications

- Benefits the ears, clears Heat (and drains Fire), clears the head and the eyes
- Opens the channel and *luo*-connecting vessels, alleviates pain

Special features

Shu-stream point, Wood point, tonification point. One of the most important distal points for any disorder of the ears.







T.B.-4 *Yang Pool* YANGCHI


Tendons of the extensor digitorum
Ex-UE-3 (*zhongquan*)
T.B.-4
Wrist joint space
Tendon of the extensor digiti minimi
Moving the fingers for better presentation of the tendons

Location

On the dorsum of the wrist (above the wrist joint space, 'dorsal wrist crease'), in the gap between the tendons of the extensor digitorum (on the ulnar aspect) and the extensor digiti minimi muscles (on the radial aspect).

How to find

As the location of the dorsal wrist crease varies, the wrist joint space should be used for orientation instead (➞ 3.3.3). By moving the patient's wrist in a relaxed way, the joint space becomes well defined. **T.B.-4** is located slightly laterally to the midpoint of the joint space, in the depression between the tendons of the extensor digiti minimi muscle (continuing to the little finger) on its radial aspect and the tendon of the extensor digitorum muscle on its ulnar aspect. The tendons of the extensor digitorum muscle will become more pronounced by moving the three middle fingers.

Located on the same level but radial to the tendons of the extensor digitorum muscle is ➞ **Ex-UE-3** (*zhongquan*).

Needling

0.3–0.5 cun vertically or slightly obliquely in a proximal direction or transversely (subcutaneously) deep to the tendons towards the radial aspect of the wrist.

Actions/Indications

- Clears Heat, opens the channel, relaxes the tendons. In Japanese acupuncture tradition, **T.B.-4**, in its function as *yuan*-source point, is used for deficiency syndromes.

Special features

Yuan-source point


L.I.-3
Ex-UE-8
T.B.-2
S.I.-2
Ex-UE-9
(*baxie*)
L.I.-4
T.B.-3
S.I.-3
Ex-UE-7
Ex-UE-7
S.I.-4
L.I.-5
S.I.-5
T.B.-4
S.I.-6
T.B.-5


Tendons of the extensor digitorum
Ex-UE-3 (*zhongquan*)
T.B.-4
Wrist joint space

Outer Pass WAIGUAN T.B.-5







Location

2 cun proximal to the dorsal wrist joint space (‘dorsal wrist crease’), between the radius and the ulna.

How to find

As the location of the dorsal wrist crease varies, the wrist joint space should be used for orientation instead (➞ 3.3.3). By moving the patient’s wrist in a relaxed way, the joint space becomes more easily palpable. **T.B.-5** is located 2 cun proximal to the midpoint of the joint space, in the depression midway between the radius and the ulna. **Or quick method:** With the palpating finger, slide with slight pressure from the dorsal aspect of the wrist joint in a proximal direction between the radius and the ulna, until the finger is brought to rest at **T.B.-5** by the increasing skin bulge building up in front of it.

➞ **P-6** is located opposite **T.B.-5,** on the anterior aspect of the forearm.

Needling

Vertically or obliquely 0.5–1.5 cun. Caution: Movement of the hand/arm during needle retention may cause bending of the needle.

Actions/Indications

- Expels Wind and benefits the head and ears, clears Heat, opens and regulates the *yang wei mai*
- Opens the channel and alleviates pain

Special features

Luo-connecting point, opening (master) point of the *yang wei mai*. Major point for expelling Wind-Heat, analgesic point for the upper extremity.



T.B.-6 *Branching Ditch* ZHIGOU

Location

3 cun proximal to the dorsal wrist joint space (‘dorsal wrist crease’), in a depression between the radius and the ulna, radial to the tendon of the extensor digitorum communis muscle.

How to find

As the location of the dorsal wrist crease varies, the wrist joint space should be used for orientation instead (→ 3.3.3). By moving the patient’s wrist in a relaxed way, the joint space becomes more easily palpable. From the joint space, measure 3 cun in a proximal direction. At this point, the extensor digitorum communis muscle will often lie midway between the ulna and the radius. **T.B.-6** is located in a depression close to the border of the radius, on the radial side of the muscle.

Located on the same level is → **T.B.-7,** in a depression between the ulna and the extensor digitorum communis muscle. → **P-5** is also located on this level, but on the anterior aspect of the forearm.

Needling

0.5–1.5 cun slightly obliquely towards the ulna or obliquely in a proximal (elbow) or distal (wrist) direction. Or through-needling to **P-5** (*jianshi*). Caution: Movement of the hand/arm during needle retention may cause bending of the needle.

Actions/Indications

- Regulates the Qi, clears Heat in the Triple Burner, benefits the lateral costal region, promotes bowel movements
- Benefits the voice
- Opens the channel

Special features

Jing-river point, Fire point, *ben* point (Five Phases).







Ancestral Meeting HUIZONG T.B.-7





Location

3 cun proximal to the dorsal wrist joint space (‘dorsal wrist crease’) and 0.5 cun ulnar to the centre of the forearm.

How to find

As the location of the dorsal wrist crease varies, the wrist joint space should be used for orientation instead (→ 3.3.3). By moving the patient’s wrist in a relaxed way, the joint space becomes more easily palpable. From the joint space, measure 3 cun in a proximal direction and locate **T.B.-7** in a depression between the ulna and the extensor digitorum communis muscle. **Or:** Spreading hands technique (→ 2.3.3): Place the little fingers on the elbow crease and the wrist joint space respectively (this distance corresponds to 12 cun). Divide this distance into quarters and locate **T.B.-7** one quarter of the distance from the wrist joint and 0.5 cun ulnar to the centre of the forearm (where → **T.B.-6** is located) on the border of the ulna.

Located on the same level is → **T.B.-6** (0.5 cun towards the radius).

Needling

Vertically or obliquely up to 1.5 cun

Actions/Indications

- Opens the channel and alleviates pain
- Benefits the ears

Special features

Xi-cleft point

T.B.-8 *Three Yang Connection* SANYANGLUO

Location

4 cun proximal to the dorsal wrist joint space (‘dorsal wrist crease’), between the radius and the ulna, radial to the tendon of the extensor digitorum communis muscle.

How to find

As the location of the dorsal wrist crease varies, the wrist joint space should be used for orientation instead (➞ 3.3.3). By moving the patient’s wrist in a relaxed way, the joint space becomes more easily palpable. From the joint space, measure 4 cun in a proximal direction and locate **T.B.-8** in a depression between the ulna and radial to the extensor digitorum communis muscle. **Or:** Spreading hands technique (➞ 2.3.3): Divide the distance between the elbow crease and the wrist joint space (=12 cun) into thirds and locate **T.B.-8** one third of the distance from the wrist joint between the radius and the ulna.

Needling

Vertically or obliquely up to 1.5 cun

Actions/Indications

- Benefits the ears and the voice
- Opens the channel and the *luo*-connecting vessels, alleviates pain





Four Rivers SIDU T.B.-9



Location

7 cun proximal to the dorsal wrist joint space ('dorsal wrist crease'), between the radius and the ulna.

How to find

From the wrist joint space (→ 3.3.3, more accurate reference point than the variable dorsal wrist crease), measure 7 cun in a proximal direction and locate **T.B.-9** in a depression between the extensor digitorum communis muscle and the extensor carpi ulnaris muscle. Alternatively, measure 5 cun distally from the lateral epicondyle of the humerus. **T.B.-9** is located on a line connecting the midpoint of the dorsal wrist joint space and the lateral epicondyle of the humerus. **Or:** Spreading hands technique (→ 2.3.3): Place the little fingers on the cubital crease and the wrist joint space (→ 2.2) respectively and join the thumbs at the midpoint of this distance (=12 cun). From the midpoint of this line, measure 1 cun in a proximal direction and there locate **T.B.-9** between the radius and the ulna.

Needling

Vertically or obliquely up to 2 cun

Actions/Indications

- Opens the channel and *luo*-connecting vessels
- Benefits the ears and throat

T.B.-10 *Heavenly Well* TIANJING

Location

On the lateral aspect of the upper arm, with the elbow flexed in a depression approximately 1 cun proximal to the olecranon.

How to find

This point is best located with the patient's elbow flexed to 90°, which will reveal an easily palpable depression 1 cun superior to the olecranon. **T.B.-10** is located in this depression, on the tendon of the triceps brachii muscle.

Needling

Up to 1 cun vertically or obliquely in a proximal direction.

Actions/Indications

- Transforms Phlegm and disperses accumulations
- Regulates and descends the Qi
- Calms the *shen*
- Clears Heat from the channel
- Opens the channel and *luo*-connecting vessels, alleviates pain

Special features

He-sea point, Earth point, sedation point.


Elbow flexed to 90°
T.B.-10
ca. 1 cun
Olecranon


Brachialis
Brachioradialis
Extensor carpi radialis longus
L.I.-11
Lateral epicondyle
Triceps brachii, lateral head
Triceps brachii, medial head
Tendon of the triceps brachii
T.B.-10
Olecranon
Flexor carpi ulnaris


S.I.-12
T.B.-14
10
T.B.-13
S.I.-9
1
2
L.I.-14
3
4
T.B.-12
5
6
L.I.-13
7
8
9
T.B.-10
L.I.-11
S.I.-8
1
L.I.-10
2
3
4
5
6
T.B.-9
7

Clear Cold Abyss QINGLENGYUAN T.B.-11


T.B.-11
T.B.-10 (in the depression approximately 1 cun superior to the olecranon)
2 cun
Olecranon

Location

On the lateral aspect of the upper arm, with the elbow flexed 1 cun proximal to → **T.B.-10** or 2 cun proximal to the olecranon, on the triceps brachii muscle.

How to find

This point is best located with the patient's elbow flexed to 90°, using → **T.B.-10** as a reference point. This is located in an easily palpable depression 1 cun superior to the olecranon. From → **T.B.-10**, palpate approximately 1 cun in a proximal direction and locate **T.B.-11** in a depression on the triceps brachii muscle.

Needling

Vertically up to 1 cun

Actions/Indications

- Dispels Wind-Damp
- Opens the channel and the *luo*-connecting vessels
- Clears Damp-Heat


Lateral epicondyle of the humerus
T.B.-10
S.I.-8
Medial epicondyle of the humerus
Olecranon

T.B.-12 *Dispersing Luo River* XIAOLUO

Location

4 cun proximal to ➞ **T.B.-10** (with the elbow flexed in a depression superior to the olecranon) or 5 cun proximal to the olecranon on a line connecting the olecranon and the lateral extremity of the acromion (location of ➞ **T.B.-14**).

How to find

First, locate the acromion (➞ 3.3.1). When the patient's arm is in abduction, two depressions will form below the acromion, in the area of origin of the deltoid muscle. ➞ **T.B.-14** is located in the posterior depression, below the posterior aspect of the lateral extremity of the acromion. Next, on a line connecting ➞ **T.B.-14** and the olecranon, measure 4 cun from ➞ **T.B.-10** (1 cun proximal to the olecranon, in the depression that forms when the elbow is flexed) in a proximal direction and there locate **T.B.-12**. **Or quick method:** Spreading hands technique (➞ 2.3.3): Place the little fingers on ➞ **T.B.-14** and ➞ **T.B.-10** respectively and determine the midpoint of this distance with the thumbs. From the midpoint, measure 1 cun in a distal direction and there locate **T.B.-12. For orientation: T.B.-12** is midway between ➞ **T.B.-11** (1 cun proximal to **T.B.-10** or 2 cun proximal to the olecranon) and ➞ **T.B.-13** (3 cun distal to ➞ **T.B.-14**, on the margin of the deltoid muscle).

Needling

Vertically or obliquely up to 2 cun

Actions/Indications

- Opens the channel and alleviates pain

Special features

T.B.-12 represents an area extending from 5–7 cun proximal to the tip of the elbow rather than a discrete acupuncture point. Determine the exact location by tenderness.


Facies
articularis
clavicularis
T.B.-14
L.I.-15


T.B.-10
Ca
1 cun
Olecranon


Posterior extremity
of the acromion
T.B.-14
1/2
6 cun
midpoint
1 cun
T.B.-12
1/2
4 cun
T.B.-10
Olecranon


S.I.-12
S.I.-10
T.B.-14
T.B.-13
S.I.-9
1
2
L.I.-14
3
4
T.B.-12
5
6
L.I.-13
7
8
9
L.I.-11
T.B.-10
1
S.I.-8
2
L.I.-10
3
4
5
6
T.B.-9
7

Upper Arm Meeting NAOHUI T.B.-13


Posterior extremity of the acromion
T.B.-14
3 cun
Deltoid
T.B.-13
Olecranon


Acromion
Trapezius
T.B.-14
Deltoid
Scapular spine
S.I.-10
S.I.-9
Triceps brachii, lateral head
Teres major
T.B.-13
Triceps brachii, long head
Biceps brachii
Triceps brachii, medial head


T.B.-11
(In the depression approximately 1 cun superior to the olecranon)
2 cun
Olecranon

Location

3 cun distal to the lateral extremity of the acromion (location of → **T.B.-14**), on a line connecting → **T.B.-14** and the olecranon, at the junction of this line with the margin of the deltoid muscle.

How to find

First, locate the acromion (→ 3.3.1). When the patient's arm is in abduction, two depressions will form inferior to the acromion, in the area of origin of the deltoid muscle. → **T.B.-14** is located in the posterior depression, below the dorsal aspect of the lateral extremity of the acromion. Next, locate **T.B.-13** 3 cun distal to → **T.B.-14**, on a line connecting → **T.B.-14** and the olecranon. **T.B.-13** is located at the junction of this line with the margin of the deltoid muscle, approximately on the level of the end of the posterior axillary fold.

Needling

Vertically or obliquely up to 2 cun

Actions/Indications

- Opens the channel and the *luo*-connecting vessels, alleviates pain
- Regulates the Qi flow and transforms Phlegm

Special features

According to some authors, meeting point with the *yang wei mai* and the G.B. channel

T.B.-14 *Shoulder Crevice* JIANLIAO

Location

Inferior to the lateral extremity of the acromion between the acromial and spinal portions of the deltoid muscle or, with the arm abducted, in the posterior of the two depressions on the shoulder joint.

How to find

Ask the patient to abduct their arm to a 90° angle, which will reveal two depressions anterior and posterior to the acromion. **T.B.-14** is located in the posterior depression, directly below the dorsal aspect of the lateral extremity of the acromion, between the acromial and spinal fibres of the deltoid muscle. The dorsal aspect of the lateral extremity of the acromion becomes more easily palpable when the upper arm is gently pulled (extension of the upper arm), allowing the head of the humerus to glide anteriorly.

→ **L.I.-15** is located in the depression anterior to **T.B.-14.**

Needling

With the arm adducted, 0.5–1 cun perpendicularly towards the centre of the axilla or 1–2 cun transversally to obliquely towards the elbow.

Actions/Indications

- Disperses Wind and Dampness, benefits the shoulder joint, opens the channel and the *luo*-connecting vessels, alleviates pain

Special features

Important local point for shoulder pain, especially for the dorsal aspect of the shouler


Acromion
Trapezius
T.B.-14
Deltoid
Scapular spine
S.I.-10
S.I.-9
Triceps brachii, lateral head
Teres major
T.B.-13
Triceps brachii, long head
Biceps brachii
Triceps brachii, medial head


Deltoid, posterior fibres
Scapular spine
Deltoid, lateral fibres
Acromio-clavicular joint
T.B.-14
L.I.-15
Clavicle
Anterior extremity of the acromion
Abduct arm
Deltoid, anterior fibres


S.I.-12
S.I.-10
T.B.-14
T.B.-13
S.I.-9
1
2
L.I.-14
3
4
T.B.-12
5
6
L.I.-13
7
8
9
L.I.-11
T.B.-10
1
S.I.-8
L.I.-10
2
3
4
5
6
T.B.-9
7


Acromio-clavicular joint
T.B.-14
L.I.-15

Heavenly Crevice TIANLIAO **T.B.-15**


Spinous process C-7
G.B.-21
1/2
T.B.-15
1/2
S.I.-13
Tip of the acromion
Spinous process T-4

Location

At the midpoint of an imaginary line between the spinous process of the 7th cervical vertebra (C7) and the tip of the acromion (lateral extremity of the acromion).

How to find

First, locate C7 (→ 3.4.1) and the acromion (→ 3.3.1), which represents the lateral extension of the scapular spine (→ 3.3.1) and, at its most lateral end, forms a flat surface superior to the head of the humerus (acromial angle). Using, for example, the spreading hands technique (→ 2.3.3), determine the midpoint between C7 and the acromial angle. Located at the highest point of the shoulder is → **G.B.-21. T.B.-15** is located approximately 1 cun inferior to → **G.B.-21**, on the superior angle of the scapula.
→ **S.I.-13** is located inferior to **T.B.-15**, directly superior to the medial end of the scapular spine.

Needling

0.5–1 cun vertically or obliquely towards the neck or shoulder. Caution: Pneumothorax.

Actions/Indications

- Opens the channel and alleviates pain
- Dispels especially Wind-Damp, unbinds the chest

Special features

Meeting point with the *yang wei mai* and the G.B. channel


Trapezius (superior fibres)
G.B.-21
S.I.-13
S.I.-12
L.I.-16
T.B.-15
S.I.-10
Trapezius (inferior fibres)


Vertebral prominence, spinous process
External occipital protuberance
Sternocleidomastoid
Splenius capitis
Trapezius
Scapular spine
Deltoid
Acromion
Scapula, inferior angle
Teres major
Latissimus dorsi

T.B.-16 *Window of Heaven* TIANYOU

Location

At the posterior border of the sternocleidomastoid muscle, directly inferior to the mastoid process, on the level of the mandibular angle.

How to find

For a better definition of the sternocleidomastoid muscle, ask the patient to rotate their head against resistance towards the side to be needled. **T.B.-16** is located on the level of the mandibular angle, on the dorsal aspect of the sternocleidomastoid muscle. This point is located inferior to the posterior border of the mastoid (→ 3.1.4). → **G.B.-12** is located directly posterior and inferior to the mastoid; → **S.I.-17** is also located on the level of the mandibular angle, but on the anterior border of the sternocleidomastoid muscle.

Needling

Vertically 0.5–1 cun. Caution: Carotid artery.

Actions/Indications

- Benefits the head and sensory organs
- Descends the Qi, expels Wind
- Opens the channel and alleviates pain

Special features

Window of Heaven point


Helix root
Supratragic notch
Tragus
Intertragic notch
T.B.-22
T.B.-21
S.I.-19
G.B.-2
T.B.-
Transverse process of the atlas
Mastoid process
Ex-HN (anmian)
Ex-HN 14 (yiming)
G.B.-12


Mastoid process
Mandibular angle
T.B.-16
Sternocleidomastoid
S.I.-17


T.B.-21
S.I.-19
G.B.-2
S.I.-18
ST-7
T.B.-17
G.B.-20
G.B.-12
Ex-HN (anmian)
ST-5
S.I.-17
T.B.-16
Ren-23
ST-9
L.I.18
S.I.-16
L.I.-17
ST-12
ST-11


S.I.-18
Mandibular angle
T.B.-16
ST-5
Sternocleidomastoid
ST-6
S.I.-17


Approximate level of the root of the ear
G.B.-11
1/3
Mastoid process
G.B.-12

Wind Screen YIFENG T.B.-17


T.B.-17
Mastoid process
Transverse process of the atlas


T.B.17
Posterior to the earlobe

Location

With the patient's mouth open, in the depression behind the earlobe, between the mastoid process and the mandible.

How to find

This point should be located with the patient's mouth open. **Quick method:** When pressing onto the ear lobe, it will touch **T.B.-17**. **Or:** Gently fold the earlobe anteriorly. **T.B.-17** is located posterior to the lobe, in a pressure-sensitive depression which can be palpated between the mandible and the mastoid process. The tip of the needle will get close to the transverse process of the 1st cervical vertebra (transverse process of the atlas, → 3.1.4), which, below the earlobe, can be palpated as a deep bony structure often sensitive to pressure.

Needling

This point should be needled with the patient's mouth slightly open. Caution: This point is close to the facial nerve, therefore no deep needling. Superior to the transverse process, the vertebral artery curves round posteriorly, therefore strictly needle 0.5–1 cun in an anterior direction.

Actions/Indications

- Expels (external) Wind, benefits the ears, clears Heat, opens the channel and *luo*-connecting vessels, alleviates pain

Special features

Meeting point with the G.B. channel. Important local point for disorders of the ears and the temporomandibular joint.


Helix
Antihelix
Antitragus
Lobe
Helix root
Supratragic notch
Tragus
Intertragic notch

Ch04.10-F10028.qxd 2/23/08 2:27 PM Page 384

T.B.-18 *Spasm Vessel* QIMAI

Location

Posterior to the ear, in a well-defined depression in the centre of the mastoid.

How to find

On an imaginary clock face superimposed over the auricle (12 o'clock = apex of the ear, 6 o'clock = earlobe), you can find an easily palpable depression at 8 o'clock (on the right side) and at 4 o'clock (on the left side). It is located directly behind the margin of the auricle and is the location of **T.B.-18**.

→ **G.B.-11** is located slightly superior to **T.B.-18** and approximately 0.3 cun from the ear; → **G.B.-12** is located inferior to **T.B.-18**, directly posterior to the mastoid.

Needling

0.5 cun transversely (subcutaneously) in an inferior direction or prick to bleed.

Actions/Indications

- Dispels Wind
- Opens the channel, alleviates pain
- Benefits the ears


12
9
3
4
T.B.-18
6


12
9
3
8
T.B.-18
6


T.B.-20
T.B.-23
Ex-HN-5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
G.B.-2
ST-7
S.I.-18
G.B.-20
T.B.-17
G.B.-12
Ex-HN
(*anmian*)


Helix root
Supratragic notch
Tragus
Intertragic notch
T.B.-22
T.B.-21
S.I.-19
G.B.-2
T.B.-1
Transverse process
of the atlas
Mastoid process
Ex-HN
(*anmian*)
Ex-HN 14
(*yiming*)
G.B.-12


Approximate
level of the root
of the ear
G.B.-11
1/3
Mastoid
process
G.B.-12

Skull's Rest LUXI T.B.-19







Location

Posterior to the ear, in a well-defined depression superior to the centre of the ear.

How to find

On an imaginary clock face superimposed over the auricle (12 o'clock = apex of the ear, 6 o'clock = earlobe), you can find an easily palpable depression at approximately 10 o'clock (on the right side) and at 2 o'clock (on the left side). It is located directly behind the margin of the auricle and is the location of **T.B.-19**.
→ **G.B.-11** is located slightly inferior to **T.B.-19** and approximately 0.3 cun from the margin of the ear.

Needling

Up to 0.5 cun transversely (subcutaneously) in an inferior direction or prick to bleed.

Actions/Indications

- Dispels Wind
- Opens the channel
- Benefits the ear, clears Heat

Ch04.10-F10028.qxd 2/23/08 2:27 PM Page 386

T.B.-20 *Minute Angle* JIAOSUN

Location

Directly superior to the apex of the ear.

How to find

Directly superior to the apex of the ear. → **G.B.-7** is also located on the apex of the ear, but anterior to it, within the circumauricular hairline. → **G.B.-8** is located 1.5 cun superior to the apex of the ear.

Needling

Up to 1.5 cun transversely (subcutaneously) in the direction of the disorder.

Actions/Indications

- Benefits the ears and the eyes
- Clears Heat, especially from the mouth

Special features

Meeting point with the G.B. channel, also with the S.I. channel according to some authors.




T.B.-23
Ex-HN-5
G.B.-1
T.B.-21
S.I.-19
G.B.-2
S.I.-18
ST-7
T.B.-17
G.B.-11
G.B.-19
G.B.-20
G.B.-12
Ex-HN
(*anmian*)


Helix
Antitragus
Antitragus
Lobe
Helix root
Supratragic notch
Tragus
Intertragic notch




G.B.-7
T.B.-20
Circumauricular hairline

Ear Gate ERMEN **T.B.-21**


Condyloid process
of the mandible
Styloid
process
Needle insertion
with the mouth
slightly open
T.B.-21
S.I.-19
Tragus
G.B.-2
Mouth closed*
Mouth open*




Helix root
Supratragic notch
Tragus
Intertragic notch
T.B.-22
T.B.-21
S.I.-19
G.B.-2
T.B.-17
Transverse process
of the atlas
Mastoid process
Ex-HN
(*anmian*)
Ex-HN 14
(*yiming*)
G.B.-12

Location

Anterior to the ear, with the patient's mouth open in the depression on the level of the supratragic notch and slightly superior to the condyloid process of the mandible.

How to find

This point should be both located and needled with the patient's mouth open. This allows the condyloid process of the mandible to slide anteriorly to reveal the depression where **T.B.-21** is located. Locate the sulcus between the auricle and the cheek anterior to the tragus (this can be more or less well defined). Then locate **T.B.-21** on the level of the supratragic notch on the sulcus. If the latter cannot be clearly identified (it becomes more pronounced with increasing age), the depression can be located with an (ear) point locator when the patient's mouth is opened. **T.B.-21** is the most superior of three points located anterior to the ear (→ **S.I.-19** and → **G.B.-2** are located more distally).

Needling

0.5–1 cun vertically or slightly obliquely in an inferior direction. Needle with the patient's mouth open (to avoid intra-articular insertion). After insertion, patients can close their mouth again. Caution: Like S.I.-19 and G.B.-2, this point is close to the superficial temporal artery and the auriculotemporal nerve.

Actions/Indications

- Clears Heat, benefits the ears

Special features

Important local point for disorders of the ears

---

* Accoring to Deadman et al 1998.

T.B.-22 *Ear Harmony Crevice* ERHELIAO

Location

In a depression at the border of the circumauricular temporal hairline, anterior to and on the level of the root of the auricle.

How to find

First, locate the anterior aspect of the root of the ear. From there, palpate approximately the breadth of the little finger in the direction of the eye. There, **T.B.-22** is located superior to the zygomatic arch (→ 3.1.2), which forms a bony ridge when sliding inferiorly from **T.B.-22**.
Located inferior to the zygomatic arch is → **T.B.-21**.

Needling

Transversely (subcutaneously) 0.5 cun. Caution: Superficial temporal artery.

Actions/Indications

- Dispels Wind
- Opens the channel and the *luo*-connecting vessels

Special features

Meeting point with the S.I. and G.B. channels, exit point according to some authors.


Zygomatic arch
Temporomandibular joint
G.B.-3
T.B.-22
T.B.-21
ST-7


Depression
Circumauricular hairline
Upper border of the root of the ear
T.B.-22
ca. 0.5 cun


T.B.-23
Ex-HN-5
G.B.-1
T.B.-21
S.I.-19
G.B.-2
S.I.-18
ST-7
G.B.-11
G.B.-19
G.B.-20
T.B.-17
G.B.-12
Ex-HN
(*anmian*)


Occipital bone
T.B.-23
ST-7
Zygomatic arch
Mandibular angle


Helix root
Supratragic notch
Tragus
Intertragic notch
T.B.-22
T.B.-21
S.I.-19
G.B.-2
T.B.-17
Transverse process of the atlas
Mastoid process
Ex-HN
(*anmian*)

Silken Bamboo Hollow SIZHUKONG T.B.-23


T.B.-23
over the
frontozygomatic suture
G.B.-1


G.B.-14
Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
Ex-HN-7
ST-1
ST-2


Orbit
Zygomatic
bone

Location

On the lateral end of the eyebrow, in the bony depression of the frontozygomatic suture, between the frontal and zygomatic bones.

How to find

The frontozygomatic suture (between the zygoma and the frontal bone) is generally located at the lateral end of the eyebrow. As the position of the latter can vary considerably, the suture is a more suitable reference point. In order to locate it, palpate from the outer canthus of the eye superiorly along the orbital margin, from its zygomatic to the frontal section, until you can feel a bony depression in the area of the suture. Locate **T.B.-23** in this mainly pressure-sensitive depression.

Needling

0.5–1 cun obliquely or transversely (subcutaneously) in a posterior direction towards **Ex-HN-5** (*taiyang*). In China, this point is also needled along the eyebrow to **Ex-HN-4** (*yuyao*: in the centre of the eyebrow). Moxibustion is contraindicated according to some classic texts.

Actions/Indications

- Benefits the eyes, alleviates pain, eliminates Wind

Special features

Important local point for headaches and disorders of the eyes


G.B.-14
G.B.-14
Ex-HN-4
(yuyao)
Glabella
Ex-HN-3
(yintang)
T.B.-23
BL-2
Superciliary arch



4.11 Gall Bladder Channel System – Foot *shaoyang* (*zu shao yang jing luo*)

4.11.1 The Gall Bladder Primary Channel (*zu shao yang jing*)


T.B.-22
T.B.-20
S.I.-19
T.B.-17
G.B.-21
Du-14
ST-15*
S.I.-12
ST-8
(T.B.-23)
G.B.-1
ST-7
ST-5
ST-6
ST-9
ST-12
G.B.-21
25
LIV-13
BL-31*
BL-32*
BL-33*
BL-34*
30
ST-30
Du-1*
35
(LIV-1)
G.B-44

* According to Deadman et al 1998.


ST-8
1/4
G.B.-4
1/4
1/4
5
1/4
6
7
G.B.-8
G.B.-9
T.B.-20
10
G.B.-1
G.B.-3
G.B.-2
11
G.B.-12
Mastoid process
Transverse process of the atlas


G.B.-16
G.B.-17
G.B.-18
G.B.-15
G.B.-13
G.B.-14
4
7
10
1
11
G.B.-19
G.B.-20
G.B.-12
G.B.-21


Semispinalis capitis
Occiput
G.B.-20
Du-16
G.B.-20
Atlas
C1
Sternocleido-mastoid
Axis
BL-10
Du-15
BL-10
Splenius capitis
1st palpable spinous process
Trapezius, superior fibres
Du-14

Pathway

The Gall Bladder primary channel begins at **G.B.-1** (*tongziliao*) at the outer canthus of the eye. This point is reached by a **small branch** which separates from the Triple Burner primary channel at → **T.B.-23** (*sizhukong*) on the frontozygomatic suture, according to some authors at → **T.B.-22** (hand–foot pairing of the third great circuit, Yang axes: *shaoyang*).

From **G.B.-1**, the **external pathway** runs to **G.B.-2** (*tinghui*) in front of the ear

- ➡ ascends to the forehead and **ST-8** (*touwei*)
- ➡ traverses the temporal region in a slight curve, passing


G.B.-21
Level of the nipples
G.B.-23
G.B.-22
G.B.-24
LIV-13
G.B.-25
Level of the umbilicus
G.B.-26
Ren-4
G.B.-27
G.B.-28
G.B.-29
Upper border of the pubic symphysis
G.B.-30


1/2
1/2
G.B.-21
Spinous process of C7
Du-14
T1
Acromion


Manubrium
Manubriosternal synchondrosis
Sternum
Mamillary line
ST-18
6th intercostal space
LIV-14
7th intercostal space
G.B.-24
LIV-13


G.B.-29
G.B.-30
12 cun
G.B.-31
2 cun
G.B.-32
5 cun
G.B.-33
Lateral popliteal crease
G.B.-34
9 Cun
G.B.-36
G.B.-35
7
6
5
4
3
2
1
G.B.-37
G.B.-38
G.B.-39
Highest prominence of the lateral malleolus
cun
G.B.-40


Sacral hiatus
Gemellus superior
Piriformis
2/3
G.B.-30
1/3
Obturatorius internus
Gemellus minor
Prominence of the greater trochanter


Popliteal crease
Head of the fibula
G.B.-34
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
Cun
Peroneus longus
Extensor digitorum longus
Tibialis anterior
G.B.-36
G.B.-35
G.B.-37
G.B.-38
G.B.-39
Highest prominence of the lateral malleolus
Talus
G.B.-40
Calcaneus
Tendon of peroneus longus
Tendon of peroneus brevis
Cuboid


Calcaneus
Talus
Tendon of peroneus brevis
G.B.-40
Tendons of the extensor digitorum longus
Base of the 5th metatarsal bone
Cuboid
G.B.-41
G.B.-42
G.B.-43
G.B.-44

G.B.-4 to **G.B.-7**, and continues to → **T.B.-22** (*erheliao*) anterior to the root of the ear

➡ passes → **T.B.-20** (*jiaosun*) superior to the apex of the ear and curves posterior to the ear from **G.B.-8** to **G.B.-12**

➡ traverses the lateral aspect of the head to **G.B.-13** (*benshen*) and **G.B.-14** (*yangbai*) on the forehead

➡ again traverses the side of the head to **G.B.-20** (*fengchi*)

➡ crosses the superior aspect of the shoulder and passes **G.B.-21** (*jianjing*) and → **T.B.-15** (*tianliao*) to reach → **Du-14** (*dazhu*), where it meets the other Yang primary channels

➡ continues to **S.I.-12** (*bingfeng*), according to some authors (Deadman et al 1998) previously passing → **BL-11** (*dashu*) and **ST-12** (*quepen*) in the supraclavicular fossa.

One branch runs from **G.B.-20** to → **T.B.-17** (*yifeng*), enters the ear and travels to → **S.I.-19** (*tinggong*), passes → **ST-7** (*xiaguan*) and continues to **G.B.-1** (*tongziliao*) at the lateral canthus of the eye, descends to → **ST-5** (*daying*), again ascends to the infraorbital region, where it meets the Triple Burner primary channel; then descends to → **ST-6** (*jiache*) on the lower jaw, traverses the lateral aspect of the neck, passing → **ST-9** (*renying*) at the sternocleidomastoid, and meets the main branch again at

→ **ST-12** (*quepen*) in the supraclavicular fossa, where the latter divides into **2 branches**:

- ➡ **The inner branch** enters the thorax, meets the Pericardium primary channel at → **P-1** (*tianchi*), runs across the diaphragm, connects with the Liver (*gan*) and the Gall Bladder (*dan*), traverses the hypochondrium and continues to the lower abdomen, enters the lumbar region near the femoral artery, according to Solinas et al (1998) via → **ST-30** (*qichong*), and continues along the pubic hairline to the hip.
- ➡ **The outer branch** descends superficially from the supraclavicular fossa, crosses the midaxillary line and continues along the lateral thoracic wall, passing → **LIV-13** (*zhangmen*) at the free end of the 11th rib and continuing to the hip to **G.B.-29** (*juliao*). It then traverses the sacral region, passing → **BL-31** (*shangliao*), → **BL-32** (*ciliao*), → **BL-33** (*zhongliao*) and → **BL-34** (*xialiao*) over the sacral foramina and continues to → **Du-1** (*changqiang*). From there, it travels laterally to **G.B.-30** (*huantiao*), where it reconnects with the main branch (→ see comment below*).

The **external pathway** descends along the lateral aspect of the thigh to the knee and further along the anterior/posterior border of the fibula, passing the anterior aspect of the lateral malleolus and ending at the ulnar corner of the nail of the fourth toe.

A further branch originates at **G.B.-41** (*zulinqi*) on the dorsum of the foot and travels between the 1st and 2nd metatarsal bones to the tip of the big toe and **LIV-1** (*dadun*), where it joins the LIV channel.

Clinical importance (→ 1.2)

Exterior (*biao*) signs and symptoms: Alternating fevers and chills, headaches, eye pain, pain in the cheek and on the chin, subaxillary swellings, deafness, lateral knee and leg pain

Interior (*li*) or *zangfu*-Organ signs and symptoms: Pain in the lateral costal region, vomiting, bitter taste in the mouth, thoracic pain

Connections of the Gall Bladder primary channel (→ 1.2)

Connections with other channels (→ 1.2)

Liver primary channel (*zu jue yin jing*)

Connection: Foot Yin–Yang pair of the third great circuit
Location: G.B.-41 → LIV-1 (on the foot)
Circulation: Circadian (according to the Organ clock)
Importance: Exterior–Interior relationship

Triple Burner primary channel (*shou shao yang jing*)

Connection: Hand–foot pairing of the third great circuit: *shaoyang* (Yang axes)
Location: T.B.-23 (or **T.B.-22**, according to some authors) → **G.B.-1** (on the head)
Circulation: Circadian (according to the Organ clock)
Importance: Above–below relationship

Connections with *zangfu*-Organ systems

Liver (*gan*), Gall Bladder (*dan*)

4.11.2 The Gall Bladder Divergent Channel (*zu shao yang jing bie*)



Pathway

The Gall Bladder Divergent channel separates from the Gall Bladder primary channel near **G.B.-30** (*huantiao*); according to some authors, it separates on the thigh (→ variant in the illustration)

- ➡ traverses the hip region to the anterior aspect of the body
- ➡ reaches the inguinal region and crosses the Liver divergent channel at → **Ren-2** (*qugu*)
- ➡ ascends the abdomen to **LIV-13** (*zhangmen*) below the free end of the 11th rib
- ➡ continues internally along the thoracic wall
- ➡ connects with the Gall Bladder (*dan*) and the Liver (*gan*) and passes the Heart (*xin*)
- ➡ ascends to the neck
- ➡ emerges on the lower jaw

---

* Not all authors describe the pathway of the G.B. channel as passing the points **BL-31** to **BL-34** and **Du-1** (see figure for variant pathway).

➡ disperses on the face

➡ connects with the Gall Bladder primary channel and the Liver divergent channel to form one of the six *he*-confluences (here: G.B./LIV as 2nd confluence → 1.3)

➡ continues to the eye system and ends in the Brain.

Clinical importance

- Strengthens the relationship between the Gall Bladder and the Liver (*zangfu*-Organ systems). Points on the Gall Bladder primary channel can therefore be used to treat disorders of the Liver and vice versa.
- Supports the relationship between the oesophagus and the Heart.
- The Gall Bladder Divergent channel covers the area around the eyes, thus supporting the action of some G.B. points for disorders of the eyes.

4.11.3 The Gall Bladder Sinew Channel (*zu shao yang jing jin*)



Pathway

The Gall Bladder sinew channel begins at the 4th toe, binds (*jie*) anterior and inferior to the lateral malleolus in the area of **G.B.-40** (*qiuxu*), follows the lateral aspect of the leg, binds (*jie*) at the fibula and the lateral aspect of the knee.

From the fibula, it continues to ascend the lateral aspect of the thigh

➡ while a **branch** runs obliquely to → **ST-32** (*futu*), where it binds (*jie*).

The main branch further ascends the leg to bind (*jie*) at the greater trochanter. Here, a **branch** separates and disperses over the gluteal and sacral regions.

From the hip, the channel continues to ascend the flanks to the lower costal region, where it divides into **two branches**:

➡ **one branch** traverses the lateral aspect of the thorax and ascends to bind (*jie*) at → **ST-12** (*quepen*)

➡ **the other branch** follows the midaxillary line to the thorax, meeting the other branch in the supraclavicular fossa.

From **ST-12**, the channel ascends the lateral aspect of the neck

➡ curves around the ear

➡ a branch continues to the apex of the ear and to → **Du-20** (*baihui*)

➡ from the temporal region, **a branch** descends and traverses the cheek to the lower jaw

➡ crosses the zygomatic arch to reach **S.I.-18** (*quanliao*), where it meets the other foot Yang sinew channels and divides into **two branches**. One branch travels laterally to the root of the nose, the other to the outer canthus of the eye.

Clinical importance

Pathology: Stiffness and distending sensations in the area of the 4th toe as well as on the lateral aspect of the knee. Limited range of motion of the knee joint. Pain, tension and distending sensations in the popliteal crease radiating to the thigh and the sacral region and vice versa. Pain and distending sensations in the sacral region radiating to the hypochondrium and vice versa. Pain and tension in the supraclavicular fossa, thorax, breast and neck region. Pain along the left side of the channel and inability to open the right eye and vice versa.

Indication: Predominantly for pain, muscle tension, stiff joints and distending sensations on the lateral aspect of the body. Used for disorders of the anterior, lateral and posterior aspects of the legs, especially those affecting the knees and the thighs. The Gall Bladder Sinew channel spreads in the thorax and the breasts so that points on the G.B. channel can be used for disorders in those areas. Also for headaches on the vertex and temporal regions. The channel also reaches the lateral aspect of the nose, which supports the relationship with the nose. Therefore, G.B. points can be used for chronic nasal disorders, chronic sinusitis, etc.

4.11.4 The Gall Bladder *luo*-Connecting Channel (*zu shao yang luo mai*)



Pathway

The Gall Bladder *luo*-connecting channel separates from the Gall Bladder primary channel at its *luo*-connecting point **G.B.-37** (*guangming*) (→ 8.1.2). It forms a three-dimensional reticulate network, dividing into multiple branches and sub-branches (*sun luo, fu luo, xue luo* → 1.5) within the surrounding tissue.

- Horizontal divisions run to the Interiorly–Exteriorly paired Liver primary channel; according to some schools of thought (for example, Ngyen Van Nghi → Appendix), they travel as a **transverse** G.B. *luo* vessel to the *yuan*-source point **LIV-3** (*taichong*).
- A **longitudinal** division descends to the dorsum of the foot and spreads to the 3rd, 4th and 5th toes.

Clinical importance (→ 8.1.2)

Pathology

Excess (*shi*): Cold sensations in the feet

Deficiency (*xu*): Weakness, weak musculature of the foot, including difficulty in standing, paralysis of the lower extremity

4.11.5 Cutaneous Region (*shao yang pi bu*)

See description and figures → 1.6.

4.11.6 Points of the Gall Bladder Primary Channel (Overview)

Specific points according to their function

- ***Yuan*-source point (→ 8.1.1): G.B.-40** (*qiuxu*) 🟦⬛
- ***Luo*-connecting point (→ 8.1.2.): G.B.-37** (*guangming*) 🟦⬛
- ***Xi*-cleft point (→ 8.1.3): G.B.-36** (*waiqiu*)
- **Associated Back-*shu* point (→ 8.1.4): BL-19** (*danshu*) 🟦⬛
- **Associated Front-*mu* point (→ 8.1.5): G.B.-24** (*riyue*) 🟦⬛
- **Five *shu*-transporting points (→ 8.1.6):**
  jing-well point (Metal): **G.B.-44** (*zuqiaoyin*) 🟦⬛
  ying-spring point (Water), tonification point: **G.B.-43** (*xiaxi*)
  shu-stream point (Wood), *ben* point (Five Phases): **G.B.-41** (*zulinqi*) 🟦⬛
  jing-river point (Fire), sedation point: **G.B.-38** (*yangfu*)
  he-sea point (Earth): **G.B.-34** (*yanglingquan*) 🟦🟦
- ***Hui*-meeting point (→ 8.1.7)**
  – with the sinews: **G.B.-34** (*yanglingquan*) 🟦🟦
  – with the Marrow: **G.B.-39** (*xuanzhong*) 🟦⬛
- **Opening point (→ 8.1.8) of the *dai mai:* G.B.-41** (*zulinqi*) 🟦⬛
- **Lower *he*-sea point (→ 8.1.9) of the Gall Bladder: G.B.-34** (*yanglingquan*) 🟦🟦
- ***Jiaohui*-meeting points (→ 8.1.10):**
  – with the S.I. and T.B. channels: **G.B.-1** (*tongziliao*)
  – with the T.B. and ST channels: **G.B.-3** (*shangguan*), **G.B.-4** (*hanyan*)
  – with the T.B., L.I. and ST channels: **G.B.-5** (*xuanlu*), **G.B.-6** (*xuanli*)
  – with the BL channel: **G.B.-7** (*qubin*); **G.B.-8** (*shuaigu*) 🟦⬛, **G.B.-9** (*tianchong*), **G.B.-10** (*fubai*)
  – with the BL, (S.I., T.B.*) channels: **G.B.-11** (*touqiaoyin*)
  – with the BL channel: **G.B.-12** (*wangu*) 🟦⬛
  – with the *yang wei mai*: **G.B.-13** (*benshen*) 🟦⬛
  – with the *yang wei mai*, (T.B., ST, L.I. channels*): **G.B.-14** (*yangbai*) 🟦⬛
  – with the *yang wei mai* and the BL channel: **G.B.-15** (*toulinqi*)
  – with the *yang wei mai*: **G.B.-16** (*muchuang*). **G.B.-17** (*zhengying*), **G.B.-18** (*chengling*), **G.B.-19** (*naokong*)
  – with the *yang wei mai, yang qiao mai* and (T.B. channel*): **G.B.-20** (*fengchi*) 🟦🟦
  – with the *yang wei mai*, T.B. and (ST*) channels: **G.B.-21** (*jianjing*) 🟦⬛
  – with the BL channel*: **G.B.-23** (*zhejin*)
  – with the SP channel and (*yang wei mai**): **G.B.-24** (*riyue*) 🟦⬛
  – with the *dai mai*: **G.B.-26** (*daimai*), **G.B.-27** (*wushu*), **G.B.-28** (*weidao*)
  – with the *yang qiao mai* and (*dai mai**): **G.B.-29** (*juliao*)
  – with the BL channel: **G.B.-30** (*huantiao*) 🟦⬛
  – with the *yang wei mai**: **G.B.-35** (*yangjiao*)
  – of other channels with the G.B. channel: **ST-7, ST-8, ST-9, ST-12, S.I.12, S.I.-19, (BL-1, BL-11*), BL-31–34, P-1, (T.B.-15*), T.B-17, T.B.-20, T.B.-22, LIV-13, Du-1, Du-14, (Du-20, ST-5, ST-6, ST-30*)**
- **Gao Wu command point (→ 8.1.11): –**
- **Window of Heaven point (→ 8.1.12): G.B.-9** (*tianchong*)
- **Points of the Four Seas (→ 8.1.13): –**
- **Ma Dan Yang Heavenly Star points (→ 8.1.14): G.B.-30** (*huantiao*) 🟦⬛, **G.B.-34** (*yanglingquan*) 🟦🟦

---

* Mentioned by only some authors.

- **Sun Si Miao Ghost point (→ 8.1.15): –**
- **Other functional points:**
  - – main point for all disorders of the head, sensory organs, Brain: **G.B.-20** (*fengchi*) 🟦🟦
  - – front-*mu* point of the Kidneys (→ 8.1.5): **G.B.-25** (*jingmen*) 🟦■
  - – *xi*-cleft point (→ 8.1.3) of the *yang wei mai:* **G.B.-35** (*yangjiao*)

Points according to region

- **Local points (→ 8.2.1):** forehead – **G.B.-14** (*yangbai*) 🟦■; head, temporal region – **G.B.-8** (*shuaigu*) 🟦■; head, occipital region – **G.B.-20** (*fengchi*) 🟦🟦; ears – **G.B.-2** (*tingshui*) 🟦■; cervical spine – **G.B.-20** (*fengchi*) 🟦🟦; neck and shoulder region – **G.B.-20** (*fengchi*) 🟦■, **G.B.-21** (*jianjing*) 🟦■; Gall Bladder – **G.B.-24** (*riyue*) 🟦■; hypochondrium – **G.B.-25** (*jingmen*) 🟦■, **G.B.-26** (*daimai*), **G.B.-27** (*wushu*); hip – **G.B.-29** (*juliao*), **G.B.-30** (*huantiao*) 🟦■; knee – **G.B.-34** (*yanglingquan*) 🟦🟦, **G.B.-35** (*yangjiao*); foot – **G.B.-40** (*qiuxu*) 🟦■
- **Adjacent points (→ 8.2.1):** head, temporal region – **G.B.-20** (*fengchi*) 🟦🟦; ears – **G.B.-8** (*shuaigu*) 🟦■, **G.B.-20** (*fengchi*) 🟦🟦; cervical spine and shoulders – **G.B.-21** (*jianjing*) 🟦■; lumbar region – **G.B.-25** (*jingmen*) 🟦■, **G.B.-30** (*huantiao*) 🟦■; hip – **G.B.-31** (*fengshi*); knee – **G.B.-33** (*xiyangguan*); foot – **G.B.-34** (*yanglingquan*) 🟦🟦; toes – **G.B.-38** (*yangfu*)
- **Distal points (→ 8.2.1):** head, temporal region – **G.B.-43** (*xiaxi*), **G.B.-41** (*zulinqi*) 🟦■; eyes – **G.B.-37** (*guangming*) 🟦■; ears – **G.B.-41** (*zulinqi*) 🟦■; Liver – **G.B.-34** (*yanglingquan*) 🟦🟦; Gall Bladder – **G.B.-34** (*yanglingquan*) 🟦🟦, **G.B.-40** (*qiuxu*) 🟦■; hypochondrium – **G.B.-38** (*yangfu*), **G.B.-34** (*yanglingquan*) 🟦🟦, **G.B.-43** (*xiaxi*); cervical spine and hip – **G.B.-39** (*xuanzhong*) 🟦■; hip – **G.B.-41** (*zulinqi*) 🟦■

Specific points according to the channel pathway (in numeric order)

- **G.B.-1** (*tongziliao*): *jiaohui*-meeting point with the S.I. and T.B. channels (→ 8.1.10)
- **G.B.-2** (*tinghui*) 🟦■: local point for the ears (→ 8.2.1)
- **G.B.-3** (*shangguan*): *jiaohui*-meeting point with the T.B. and ST channels (→ 8.1.10)
- **G.B.-4** (*hanyan*): *jiaohui*-meeting point with the T.B. and ST channels (→ 8.1.10)
- **G.B.-5** (*xuanlu*): *jiaohui*-meeting point with the T.B., L.I. and ST channels (→ 8.1.10)
- **G.B.-6** (*xuanli*):): *jiaohui*-meeting point with the T.B., L.I. and ST channels (→ 8.1.10)
- **G.B.-7** (*qubin*):): *jiaohui*-meeting point with the BL channel (→ 8.1.10)
- **G.B.-8** (*shuaigu*) 🟦■: *jiaohui*-meeting point with the BL channel (→ 8.1.10); local point for the lateral aspect of the head (→ 8.2.1); adjacent point for the ears (→ 8.2.1)
- **G.B.-9** (*tianchong*): *jiaohui*-meeting point with the BL channel (→ 8.1.10)*; Window of Heaven point (→ 8.1.12)*
- **G.B.-10** (*fubai*): *jiaohui*-meeting point with the BL channel (→ 8.1.10)
- **G.B.-11** (*touqiaoyin*): *jiaohui*-meeting point with the BL, (S.I., T.B.)* channels (→ 8.1.10)
- **G.B.-12** (*wangu*): *jiaohui*-meeting point with the BL channel (→ 8.1.10)
- **G.B.-13** (*benshen*) 🟦■: *jiaohui*-meeting point with the *yang wei mai* (→ 8.1.10)
- **G.B.-14** (*yangbai*) 🟦■: *jiaohui*-meeting point with the *yang wei mai* and (T.B., ST, L.I.*) channels (→ 8.1.10); local point for the forehead (→ 8.2.1)
- **G.B.-15** (*toulinqi*): *jiaohui*-meeting point with the *yang wei mai* and BL channel (→ 8.1.10)
- **G.B.-16** (*muchuang*): *jiaohui*-meeting point with the *yang wei mai* (→ 8.1.10)
- **G.B.-17** (*zhengying*): *jiaohui*-meeting point with the *yang wei mai* (→ 8.1.10)
- **G.B.-18** (*chengling*): *jiaohui*-meeting point with the *yang wei mai* (→ 8.1.10)
- **G.B.-19** (*naokong*): *jiaohui*-meeting point with the *yang wei mai* (→ 8.1.10)
- **G.B.-20** (*fengchi*) 🟦🟦: *jiaohui*-meeting point with the *yang wei mai, yang qiao mai* and (T.B. channel*) (→ 8.1.10); local point for the occiput (→ 8.2.1); local point for the neck and shoulders (→ 8.2.1); local point for all disorders of the head, sensory organs, Brain; adjacent point for the lateral aspect of the head and the ears (→ 8.2.1)
- **G.B.-21** (*jianjing*) 🟦■: *jiaohui*-meeting point with the *yang wei mai*, T.B. and (ST*) channels (→ 8.1.10); adjacent point for the neck and shoulders (→ 8.2.1)
- **G.B.-23** (*zhejin*): *jiaohui*-meeting point with the BL channel (→ 8.1.10)
- **G.B.-24** (*riyue*) 🟦■: associated Front-*mu* point (→ 8.1.5); *jiaohui*-meeting point with the SP channel and (*yang wei mai**) (→ 8.1.10); local point for the Gall Bladder (→ 8.2.1)
- **G.B.-25** (*jingmen*) 🟦■: Front-*mu* point of the Kidneys (→ 8.1.5); local point for the hypochondrium (→ 8.2.1); adjacent point for the lumbar region (→ 8.2.1)
- **G.B.-26** (*daimai*): *jiaohui*-meeting point with the *dai mai* (→ 8.1.10); local point for the hypochondrium (→ 8.2.1)
- **G.B.-27** (*wushu*): *jiaohui*-meeting point with the *dai mai* (→ 8.1.10); local point for the hypochondrium (→ 8.2.1)
- **G.B.-28** (*weidao*): *jiaohui*-meeting point with the *dai mai* (→ 8.1.10);
- **G.B.-29** (*juliao*): *jiaohui*-meeting point with the *yang qiao mai* and (*dai mai**) (→ 8.1.10); local point for the hip (→ 8.2.1)
- **G.B.-30** (*huantiao*) 🟦■: *jiaohui*-meeting point with the BL channel (→ 8.1.10); Ma Dan Yang Heavenly Star point (→ 8.1.14); adjacent point for the lumbar region and the hip (→ 8.2.1); local point for the hip (→ 8.2.1)
- **G.B.-31** (*fengshi*): adjacent point for the hip (→ 8.2.1)
- **G.B.-33** (*xiyangguan*): adjacent point for the knee (→ 8.2.1)

- **G.B.-34** (*yanglingquan*) 🟦🟦: *he*-sea point (Earth) (→ 8.1.6); *hui*-meeting point with the sinews (→ 8.1.7); lower *he*-sea point of the Gall Bladder (→ 8.1.9); Ma Dan Yang Heavenly Star point (→ 8.1.14); distal point for the Liver, Gall Bladder and hypochondrium (→ 8.2.1); local point for the knee (→ 8.2.1); adjacent point for the foot (→ 8.2.1)
- **G.B.-35** (*yangjiao*): *xi*-cleft point of the *yang wei mai* (→ 8.1.3); *jiaohui*-meeting point with the *yang wei mai** (→ 8.1.10); local point for the knee (→ 8.2.1)
- **G.B.-36** (*waiqiu*): *xi*-cleft point (→ 8.1.3)
- **G.B.-37** (*guangming*) 🟦■: *luo*-connecting point (→ 8.1.2); distal point for the eyes (→ 8.2.1)
- **G.B.-38** (*yangfu*): *jing*-river point (Fire) (→ 8.1.6); sedation point; distal point for the hypochondrium (→ 8.2.1)
- **G.B.-39** (*xuanzhong*) 🟦■: *hui*-meeting point with the Marrow (→ 8.1.7); distal point for the cervical spine and the hip (→ 8.2.1)
- **G.B.-40** (*qiuxu*) 🟦■: *yuan*-source point (→ 8.1.1); local point for the foot (→ 8.2.1); distal point for the Gall Bladder (→ 8.2.1)
- **G.B.-41** (*zulinqi*) 🟦■: *shu*-stream point (Wood); *ben* point (Five phases) (→ 8.1.6); Opening point (→ 8.1.8) of the *dai mai*; distal point for the temporal region and the ears (→ 8.2.1); distal point for the hip (→ 8.2.1)
- **G.B.-43** (*xiaxi*): *ying*-spring point (Water) (→ 8.1.6); tonification point; distal point for the lateral aspect of the head and the hypochondrium (→ 8.2.1)
- **G.B.-44** (*zuqiaoyin*) 🟦■: *jing*-well point (Metal) (→ 8.1.6)

Pupil Crevice TONGZILIAO G.B.-1


Lateral margin
of the orbit
G.B.-1


G.B.-14
Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
Ex-HN-7
ST-1
ST-2
Ex-HN-8
G.B.-2
ST-7


G.B.-8
G.B.-14
T.B.-20
T.B.-23
Ex-HN-5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
G.B.-2
S.I.-18
G.B.-20
T.B.-17
G.B.-12
Ex-HN
(anmian)


G.B.-14
G.B.-14
Ex-HN-4
(yuyao)
Glabella
Ex-HN-3
(yintang)
T.B.-23
BL-2

Location

In a bony depression on the lateral aspect of the orbital margin, on the level of the outer canthus of the eye.

How to find

From the outer canthus of the eye, palpate in a lateral direction. Locate **G.B.-1** on the outer aspect of the orbit (diagonally inferior to the temple), where a bony depression can be palpated. → **T.B.-23** is located more superiorly on the lateral end of the eyebrow, in a depression on the frontozygomatic suture. → **BL-1** is located at the inner canthus of the eye.

Needling

0.2–0.3 cun obliquely in a posterior direction or up to 1 cun transversely (subcutaneously) towards → **Ex-HN-5** (*taiyang*). According to some texts, moxibustion is contraindicated.

Actions/Indications

- Expels Wind and Heat from the eyes

Special features

Meeting point with the S.I. and T.B. channels, entry point.



G.B.-2 *Meeting of Hearing* TINGHUI

Location

Anterior to the ear, with the patient's mouth open in the depression on the level of the intertragic notch, on the lower border of the condyloid process of the mandible.

How to find

Locate and needle with the patient's mouth open as this allows the condyloid process of the mandible to slide towards the anterior, revealing the depression where **G.B.-2** is located. Find the vertical sulcus anterior to the ear (at the ear/cheek junction), which may be more or less pronounced. Then locate **G.B.-2** on the sulcus, on the level of the intertragic notch. If the sulcus is not clearly defined (it becomes more clearly visible with increasing age), the depression can be located by using an (ear) point locator. **G.B.-2** is the most distal of three points located anterior to the ear (→ **S.I.-19** and → **T.B.-21** are both located more superiorly).



Condyloid process of the mandible
Styloid process
Needle insertion with the mouth slightly open
T.B.-21
S.I.-19
Tragus
G.B.-2
Mouth closed *
Mouth open*

Needling

0.5–1 cun vertically or slightly obliquely in an inferior direction. Needle with the patient's mouth open to avoid intra-articular insertion. Caution: Like **T.B.-21** and **S.I.-19**, this point is located close to the superficial temporal artery and the auriculotemporal nerve.

Actions/Indications

- Eliminates Wind, clears Heat, benefits the ears and the temporomandibular joint
- Opens the channel and the *luo*-connecting vessel, alleviates pain



G.B.-14
Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
ST-1
Ex-HN-7
ST-2
Ex-HN-8
G.B.-2
ST-7
L.I.-20
S.I.-18
L.I.-19
Du-26

Special features

Important local point for disorders of the ears and the jaw. This point is often used alternately with **T.B.-21** and **S.I.-19**.



Helix
Helix root
Antihelix
Supratragic notch
Tragus
Antitragus
Lobe
Intertragic notch



Helix root
Supratragic notch
Tragus
Intertragic notch
T.B.-22
T.B.-21
S.I.-19
G.B.-2
T.B.-17
Antitragus

---

* According to Deadman et al 1998.

Above the Joint SHANGGUAN G.B.-3


Condyloid process of the mandible
Zygomatic arch
ST-7 in the mandibular incisure
G.B.-3
Mouth closed
Posterior border of the masseter
Condyloid process of the mandible


G.B.-14
G.B.-8
T.B.-20
T.B.-23
Ex-HN-5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
G.B.-2
S.I.-18
Ma
G.B.-20
T.B.-17
G.B.-12
Ex-HN (*anmian*)


T.B.-22
G.B.-3
Occipital bone
T.B.-23
ST-7
Zygomatic arch
Mandibular angle

Location

In a depression on the upper border of the zygomatic arch, approximately 1 cun anterior to the root of the ear, superior to → **ST-7**.

How to find

Locate the zygomatic arch (→ 3.1.2) by palpating from the root of the ear (root of the helix) approximately 1 cun towards the orbit. Follow its course by placing one finger above and the other finger below the arch. As soon as the lower finger has reached a clearly palpable depression anterior to the temporomandibular joint and posterior to the masseter muscle (→ **ST-7**), the upper finger will be resting on **G.B.-3**, which is located directly superior to → **ST-7** in a shallow depression on the superior border of the zygomatic arch.

Needling

Vertically 0.3–0.5 cun, no strong stimulation. Caution: Branches of the temporal, transverse facial and masseteric arteries! Traditionally, deep needling is prohibited.

Actions/Indications

- Opens the channel, alleviates pain
- Eliminates Wind
- Benefits the ears

Special features

Meeting point with the T.B. and ST channels


Zygomatic arch
Temporo-mandibular joint
G.B.-3
T.B.-22
T.B.-21
ST-7

G.B.-4 *Jaw Serenity* HANYAN

Location

At the junction of the upper quarter and the second quarter of a line connecting ➞ **ST-8** and ➞ **G.B.-7**.

How to find

First, locate the two reference points: ➞ **ST-8** (4.5 cun lateral to the midline and 0.5 cun within the anterior hairline, at the corner of the forehead) and ➞ **G.B.-7** (in the depression on the level of the apex of the ear, within the circumauricular temporal hairline). Then divide the slightly curved line between these two points into quarters and locate **G.B.-4** at the junction of the upper quarter with the lower three quarters. Generally, **G.B.-4** is located on the temporal hairline and the anterior portion of the temporalis muscle, which can be felt when chewing.

Needling

0.3–1.5 cun transversely (subcutaneously), tangentially along the skull, in the direction of the occiput or towards the disorder/pain.

Actions/Indications

- Eliminates Wind and Heat
- Opens the channel

Special features

Meeting point with the T.B. and ST channel


ST-8
1/4
G.B.-4
1/4
At the level of the apex, on the circumauricular hairline
1/2
G.B.-7
T.B.-20


Du-20
G.B.-18
G.B.-13
ST-8
G.B.-8
G.B.-14
T.B.-20
T.B.-23
Ex-HN-5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
Ma 7
G.B.-2
S.I.-18
G.B.-20
T.B.-17
G.B.-12
Ex-HN (anmian)



Suspended Skull XUANLU G.B.-5


ST-8
1/4
G.B.-4
1/4
At the level of the apex, on the circumauricular hairline
1/2
G.B.-7
T.B.-20


G.B.-7
T.B.-20
Circumauricular hairline


Coronal suture
ST-8
Parietal bone
Frontal bone
Occipital bone
Temporal bone
Zygomatic arch
Zygomatic bone
Mandible

Location

At the junction of the 2nd and 3rd quarter of an imaginary line connecting → **ST-8** and → **G.B.-7**.

How to find

First, locate the two reference points: → **ST-8** (4.5 cun lateral to the midline and 0.5 cun within the anterior hairline, at the corner of the forehead) and → **G.B.-7** (in the depression on the level of the apex of the ear, within the circumauricular temporal hairline). Then divide the slightly curved line between these two points into quarters and locate **G.B.-5** at the junction of the upper two quarters with the lower two quarters. Generally, this point is located on the level of the parietal suture, just within the hairline.

Needling

0.3–1.5 cun transversely (subcutaneously), tangentially along the skull, in the direction of the occiput or towards the disorder/pain.

Actions/Indications

- Expels Wind and Heat
- Opens the channel

Special features

Meeting point with the T.B., L.I. and ST channels

G.B.-6 *Suspended Hair* XUANLI

Location

At the junction of the lower quarter and the upper three quarters of a line connecting ➞ **ST-8** and ➞ **G.B.-7**.

How to find

First, locate the two reference points: ➞ **ST-8** (4.5 cun lateral to the midline and 0.5 cun within the anterior hairline, at the corner of the forehead) and ➞ **G.B.-7** (in the depression on the level of the apex of the ear, within the circumauricular temporal hairline). Then divide the slightly curved line between these two points into quarters and locate **G.B.-6** at the junction of the upper three quarters with the lower quarter.

Needling

0.3–1.5 cun transversely (subcutaneously) in the direction of the occiput or towards the disorder/pain.

Actions/Indications

- Expels Wind and Heat
- Opens the channel

Special features

Meeting point with the L.I., ST and T.B. channels


ST-8
1/2
1/4
1/4
G.B.-6
G.B.-7
T.B.-20
At the level of the apex, on the circumauricular hairline


Du-20
G.B.-18
G.B.-13
ST-8
G.B.-8
G.B.-14
T.B.-20
T.B.-23
Ex-HN-5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
Ma 7
G.B.-2
S.I.-18
G.B.-20
T.B.-17
G.B.-12
Ex-HN (*anmian*)



Crook of the Temple QUBIN G.B.-7





Location

In a depression on the level of the apex of the ear, within the circumauricular temporal hairline, approximately at the junction of a horizontal line through the apex of the ear and a vertical line along the posterior border of the temple anterior to the ear.

How to find

Locate **G.B.-7** by palpating for a small depression anterior to the apex of the ear at the circumauricular temporal hairline. The point is located approximately at a junction between a horizontal line through the apex of the ear and a vertical line along the posterior border of the temple anterior to the ear.
For orientation: → **T.B.-20** is located directly superior to the apex of the ear.

Needling

0.3–1.5 cun transversely (subcutaneously) in the direction of the occiput or towards the site of the disorder/pain.

Actions/Indications

- Expels Wind
- Benefits the mouth and jaw

Special features

Meeting point with the BL channel

G.B.-8 *Leading Valley* SHUAIGU

Location

1.5 cun directly superior to the apex of the ear, in a depression on the upper border of the temporalis muscle.

How to find

Locate the apex of the ear, which becomes more clearly defined by folding the auricle towards the anterior so that the posterior part of the upper helix covers its anterior part. From the apex of the ear, measure 1.5 cun (2 fingerbreadths) in a superior direction. There, the palpating finger will glide into a bony depression (**G.B.-8**) which is often sensitive to pressure. For orientation: When a chewing movement is made, this can just about be felt at this point.
→ **G.B.-9** is located on the same level, 0.5 cun dorsal to **G.B.-8**.

Needling

0.3–1.5 cun transversely (subcutaneously), mostly from anterior to posterior or towards the site of the pain.

Actions/Indications

- Expels Wind, benefits the head and ears, alleviates pain, harmonises the diaphragm and Stomach

Special features

Meeting point with the BL channel. Important local point for parietal and temporal headaches.


T.B.-20
Approximately level with the apex
G.B.-10
1/3
Approximately level with the helix root
G.B.-11


G.B.-8
1.5 cun
Apex of the ear




Du-18
G.B.-8
G.B.-19
BL-9
Du-17
Du-16
G.B.-20
G.B.-12
BL-10
Du-15

Heavenly Rushing TIANCHONG G.B.-9


0.5 cun
G.B.-8
G.B.-9
1.5 cun
1/3
T.B.-20
Approximately level with the apex
G.B.-10
1/3
Approximately level with the helix root
G.B.-11
1/3
Mastoid process
G.B.-12


G.B.-14
G.B.-8
T.B.-23
T.B.-20
Ex-HN-5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
G.B.-2
S.I.-18
Ma-7
G.B.-20
T.B.-17
G.B.-12
Ex-HN (*anmian*)


Helix root
Supratragic notch
Tragus
Intertragic notch
T.B.-22
T.B.-21
S.I.-19
G.B.-2
T.B.-17
Transverse process of the atlas


T.B.-20
Approximately level with the apex
G.B.-10
1/3
Approximately level with the helix root
G.B.-11


with the apex
1/3
Approximately level with the helix root
G.B.-11
1/3

Location

1.5 cun directly superior to the apex of the ear (→ **T.B.-20**) and 0.5 cun posterior to → **G.B.-8**. The point is approximately superior to the posterior margin of the ear.

How to find

First, locate → **G.B.-8** 1.5 cun superior to the apex of the ear. The latter becomes more clearly defined by folding the auricle towards the anterior so that the posterior part of the upper helix covers its anterior part. From → **G.B.-8**, measure 0.5 cun in a posterior direction and there locate **G.B.-9**. Similar to → **G.B.-8**, **G.B.-9** is located in a slight 'dip' in the bone.

Both **G.B.-9** and → **G.B.-12** (in the depression posterior and inferior to the mastoid process) are reference points for a curved line that runs approximately parallel to the posterior margin of the ear within the hairline. When dividing this line into thirds, → **G.B.-10** and → **G.B.-11** are located at the junctions of the thirds.

Needling

0.5–1.5 cun transversely (subcutaneously) towards the occiput or the site of the pain.

Actions/Indications

- Expels Wind and Heat
- Opens the *luo*-connecting vessels
- Calms the *shen*

Special features

Meeting point with the BL channel; Window of Heaven point according to some authors.

G.B.-10 *Floating White* FUBAI

Location

Posterior to the ear, at the junction of the upper third with the two lower thirds of the curved line connecting → **G.B.-9** and → **G.B.-12**.

How to find

First, locate → **G.B.-9** (1.5 cun superior to the apex of the ear and 0.5 cun in a posterior direction). Then locate → **G.B.-12** in a depression posterior and inferior to the mastoid process (→ 3.1.4). These two points are the endpoints of a curved line that runs approximately parallel to the posterior margin of the ear within the hairline. Divide this line into thirds and locate **G.B.-10** at the junction of the upper and the middle third, where often a small ‘dip’ can be felt on the bone. **G.B.-10** tends to be on the level of the apex of the ear.

→ **T.B.-20** is located directly above the apex of the ear.

Needling

Transversely (subcutaneously) 0.5–0.8 cun

Actions/Indications

- Expels Wind
- Opens the *luo*-connecting vessels

Special features

Meeting point with the BL channel


0.5 cun
G.B.-8
G.B.-9
1.5 cun
1/3
Approximately level with the apex
T.B.-20
G.B.-10
1/3
Approximately level with the helix root
G.B.-11
1/3
G.B.-12
Mastoid process


Approximately level with the helix root
G.B.-11
1/3
Mastoid process
G.B.-12




G.B.-8
G.B.-9
1.5 cun
1/3
Approximately level with the apex
T.B.-20
G.B.-10

Ch04.11-F10028.qxd 2/23/08 11:24 AM Page 409

Head Portal Yin TOUQIAOYIN G.B.-11


0.5 cun
G.B.-8
G.B.-9
1.5 cun
1/3
T.B.-20
Approximately level with the apex
G.B.-10
1/3
Approximately level with the helix root
G.B.-11
1/3
Mastoid process
G.B.-12


G.B.-8
G.B.-14
T.B.-20
T.B.-23
Ex-HN-5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
Ma 7
S.I.-18
G.B.-2
G.B.-20
T.B.-17
G.B.-12
Ex-HN (*anmian*)



Location

Posterior to the ear, at the junction of the lower third with the two upper thirds of the curved line connecting → **G.B.-9** and → **G.B.-12**.

How to find

First, locate → **G.B.-9** (1.5 cun superior to the apex of the ear and 0.5 cun in a posterior direction). Then locate → **G.B.-12** in a depression posterior and inferior to the mastoid process (→ 3.1.4). These two points are the endpoints of a curved line that runs approximately parallel to the posterior margin of the ear within the hairline. Divide this line into thirds and locate **G.B.-11** at the junction of the middle and the lower third. At this point, a small 'dip' often can be felt in the bone. For reference: **G.B.-11** is located at the midpoint between a line connecting → **G.B.-10** and → **G.B.-12** and is generally on the level of the root of the helix.

→ **T.B.-19** is located on the same level, directly posterior to the helix.

Needling

Transversely (subcutaneously) 0.5–0.8 cun

Actions/Indications

- Expels Wind and Damp-Heat
- Opens the ears and the eyes
- Moves the (Liver) Qi and Blood

Special features

Meeting point with the BL channel, also with the S.I. and T.B. channels according to some authors.

G.B.-12 *Mastoid Process* WANGU

Location

In a depression directly posterior and inferior to the mastoid process.

How to find

First, locate the mastoid process posterior to the ear (→ 3.1.4). This can be palpated at the junction of the cranium and the neck as a cone-shaped, bony structure. With the palpating finger, find the inferior aspect of the mastoid process and locate **G.B.-12** on its lower border posterior to the tip of the process.

→ **T.B.-17** is located more anteriorly, in the depression posterior to the earlobe, between the mastoid process and the mandible.

Needling

0.5–1 cun obliquely in an inferior direction.

Actions/Indications

- Expels Wind, Heat and Dampness/Phlegm
- Opens the ears
- Calms the *shen*

Special features

Meeting point with the BL channel


0.5 cun
G.B.-8
G.B.-9
1.5 cun
1/3
Approximately level with the apex
T.B.-20
G.B.-10
1/3
Approximately level with the helix root
G.B.-11
1/3
G.B.-12
Mastoid process


Du-18
G.B.-8
G.B.-19
BL-9
Du-17
G.B.-20
Du-16
G.B.-12
BL-10
Du-15


Great auricular nerve
Major occipital nerve
External jugular vein
Transverse cervical nerve


Mastoid process
Occipital bone
G.B.-12
Ex-HN-14 (yiming)
Ex-HN (anmian)

Spirit Root BENSHEN G.B.-13


Du-24
G.B.-15
G.B.-13
0.5 cun
ST-8
Hairline
3 cun
2/3
1,5 cun
1/3
Midline

Location

3 cun lateral to → **Du-24** (on the midline, 0.5 cun superior to the anterior hairline).

How to find

First, locate the anterior hairline (→ 3.1.1, with hairloss: when the patient frowns, the anterior hairline is marked by the border between the creased forehead and the smooth skin above) and there locate → **Du-24** on the midline and 0.5 cun within the hairline. **G.B.-13** is located on the same level, 3 cun lateral to the midline, measured in proportional cun based on the distance → **ST-8** to → **Du-24** (=4.5 cun, 2.2). Divide this distance into thirds and locate **G.B.-13** one third of the distance from **ST-8**. Located at the same level (0.5 cun within the anterior hairline) are → **Du-24/BL-3/BL-4/G.B.-15/ST-8** (on the midline/superior to the inner canthus of the eye/1.5 cun lateral to the midline/on the pupil line or 2.25 cun lateral to the midline/on the corner of the forehead).

Needling

0.5–0.8 cun transversely (subcutaneously) towards the occiput.

Actions/Indications

- Expels Wind
- Calms the *shen*
- Benefits the eyes

Special features

Meeting point with the *yang wei mai*


ST-8
Chewing movement
still palpable
Temporalis


G.B.-15
BL-5
Du-23
ST-8
G.B.-13
BL-4
Du-24
BL-3
G.B.-14
Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1


Du-20
G.B.-18
G.B.-13
ST-8
G.B.-8
G.B.-14
T.B.-20
T.B.-23
Ex-HN-5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
G.B.-2
S.I.-18
Ma
G.B.-20

G.B.-14 *Yang White* YANGBAI

Location

With the patient looking straight ahead, on the pupil line, approximately 1 cun superior to the midpoint of the eyebrow, at the junction of the frontal eminence and the superciliary arch.

How to find

On the pupil line, palpate from the anterior hairline in an inferior direction, past the frontal eminence, and locate **G.B.-14** at the deepest point between the frontal eminence and the superciliary arch. The distance between the midpoint of the eyebrow and the anterior hairline (→ 3.1.1) is 3 proportional cun (→ 2.2). **G.B.-14** is located one third of the distance or 1 cun superior to the midpoint of the eyebrow. With the patient looking straight ahead, **G.B.-14** is located on the pupil line.

Needling

0.3–1 cun transversely (subcutaneously) towards the centre of the eyebrow or towards the site of the pain. The pinching-skin method might be used for needling: pinch the skin between the thumb and index finger so that a skin fold forms. Insert the needle subcutaneously into this fold, directing it towards the site of the pain.

Actions/Indications

- Expels (internal and external) Wind and Wind-Heat, benefits the head, alleviates pain
- Benefits the eyes

Special features

Meeting point with the *yang wei mai*, also with the T.B., L.I. and ST channels according to some authors. Important local point for frontal headache regardless of the pathology.


Hairline
2/3
G.B.-14
1 cun
1/3




Du-20
G.B.-18
G.B.-13
ST-8
G.B.-8
G.B.-14
T.B.-20
T.B.-23
Ex-HN-5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
G.B.-2
S.I.-18
Ma
T.B.-17
G.B.-20


G.B.-15
BL-5
Du-23
BL-4
Du-24
ST-8
G.B.-13
BL-3
G.B.-14
Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
Ex-HN-7
ST-1
ST-2
Ex-HN-8

Head Governor of Tears TOULINQI G.B.-15


Du-24
G.B.-15
G.B.-13
ST-8
0.5 cun
Hairline
2.25 cun
$^1/_2$
2.25 cun
$^1/_2$
Pupil line
Midline


BL-8
Du-20
G.B.-18
BL-7
Du-21
G.B.-17
BL-6
Du-22
G.B.-16
BL-5
Du-23
BL-3
G.B.-15
BL-4
Du-24
Hairline

Location

With the patient looking straight ahead, directly superior to the pupil and 0.5 cun superior to the anterior hairline.

How to find

First, locate the anterior hairline (→ 3.1.1, with hairloss: when the patient frowns, the anterior hairline is marked by the border between the creased forehead and the smooth skin above). With the patient looking straight ahead, **G.B.-15** is located 0.5 cun superior to the anterior hairline and directly superior to the pupil. **G.B.-15** can also be described as being located midway between → **Du-24** (on the midline) and → **ST-8** (4.5 cun lateral to the midline, on the corner of the forehead).

Located on the same level (0.5 cun within the anterior hairline) are → **Du-24/BL-3/BL-4/G.B.-13/ST-8** (on the midline/superior to the inner canthus of the eye/1.5 cun lateral to the midline/3 cun lateral to the midline or one third of the distance from → **ST-8** (on the corner of the forehead) to → **Du-24**.

Needling

Transversely (subcutaneously) 0.3–0.5 cun

Actions/Indications

- Expels Wind
- Opens the eyes and nasal passages
- Calms the *shen*

Special features

Meeting point with the *yang wei mai*, also with the BL channel according to some authors.


ST-8
Chewing movement still palpable
Temporalis

G.B.-16 *Window of the Eye* MUCHUANG

Location

1.5 cun superior to the anterior hairline, on the pupil line or 2.25 cun lateral to the midline (midway between ➞ **Du-24** and ➞ **ST-8**).

How to find

Locate the anterior hairline (➞ 3.1.1, with hairloss: when the patient frowns, the anterior hairline is marked by the border between the creased forehead and the smooth skin above). With the patient looking straight ahead, **G.B.-16** is located 1.5 cun superior to the anterior hairline, on a vertical line through the centre of the pupil. This line is located 2.25 cun lateral to the midline (this corresponds to the midpoint of the distance between ➞ **Du-24** and ➞ **ST-8**). For further orientation: The distance between the anterior hairline and ➞ **Du-20** (at the junction of the vertical midline and a line connecting the apices of the ears) is 5 cun. ➞ **G.B.-16** is located 3.5 cun anterior to ➞ **Du-20**, on the curved line connecting ➞ **G.B.-15** and ➞ **G.B.-20**.
➞ **G.B.-15** is located on the same vertical line, but 0.5 cun superior to the anterior hairline.

Needling

0.3–1.5 cun transversely (subcutaneously) towards the occiput or the site of the disorder/pain.

Actions/Indications

- Expels pathogenic factors (especially Wind) from the head and eyes
- Opens the *luo*-connecting vessels

Special features

Meeting point with the *yang wei mai*


Occiput
G.B.-20
Lower border of the occiput
G.B.-20
Axis
BL-10
Sternocleido-mastoid


Pupil line
Anterior hairline
1.5 cun
G.B.-16
2.25 cun
Apex of the ear
3.5 cun
Apex of the ear
Du-20
Midline


BL-8
Du-20
G.B.-18
BL-7
Du-21
G.B.-17
BL-6
Du-22
G.B.-16
BL-5
Du-23
BL-3
G.B.-15
BL-4
Du-24
Hairline

Upright Nutrition ZHENGYING G.B.-17

Location

2.5 cun superior to the anterior hairline and 2.25 cun lateral to the midline.

How to find

First, on the midline, locate the anterior hairline (➞ 3.1.1, with hairloss: when the patient frowns, the anterior hairline is marked by the border between the creased forehead and the smooth skin above) and ➞ **Du-20** (at the junction of the vertical midline and a line connecting the apices of the ears). The distance between these two points is 5 proportional cun (➞ 2.2). Locate the midpoint (for example by using the spreading hands technique ➞ 2.3.3). **G.B.-17** is located on the curved line connecting ➞ **G.B.-15** and ➞ **G.B.-20** (an extension of the pupil line, 2.25 cun lateral to the midline).

➞ **BL-6** is also located 2.5 cun anterior to ➞ **Du-20**, but 1.5 cun lateral to the midline.

Needling

0.3–1.5 cun transversely (subcutaneously) towards the occiput or the site of the disorder/pain.

Actions/Indications

- Expels Wind
- Opens the *luo*-connecting vessels
- Descends counterflow Stomach Qi

Special features

Meeting point with the *yang wei mai*


Pupil line
Anterior hairline
2.5 cun
G.B.-17
2.25 cun
Apex of the ear
Apex of the ear
2.5 cun
Du-20
Midline


ST-8
Chewing movement still palpable
Temporalis


5 cun
Du-20
Apex of the ear
Apex of the ear

G.B.-18 *Support Spirit* CHENGLING

Location

4 cun superior to the anterior hairline or 1 cun anterior to → **Du-20** and 2.25 cun lateral to the midline.

How to find

First, locate → **Du-20** (at the junction of the vertical midline and a line connecting the apices of the ears, distance to the anterior hairline = 5 cun). Next, locate **G.B.-18** 1 cun anterior to → **Du-20** on the curved line connecting → **G.B.-15** and → **G.B.-20** (= extension of the pupil line, midway between → **ST-8** and → **Du-24**).
→ **BL-7** is located on the same level (1 cun anterior to → **Du-20**), but 1.5 cun lateral to the midline.

Needling

0.3–1.5 cun transversely (subcutaneously) towards the occiput or the site of the disorder/pain.

Actions/Indications

- Expels Wind, especially from the nose

Special features

Meeting point with the *yang wei mai*


Pupil line
Anterior hairline
4 cun
Apex of the ear
Apex of the ear
G.B.-18
2.25 cun
1 cun
DU-20
Midline


5 cun
Du-20
Apex of the ear
Apex of the ear


Occiput
Du 16
G.B-20
Lower border of the occiput
G.B.-20
Axis
BL-10
Sterno-cleidomastoid


BL-8
Du-20
G.B.-18
BL-7
Du-21
G.B.-17
BL-6
Du-22
G.B.-16
BL-5
Du-23
Bl3
G.B.-15
BL-4
Du-24
Hairline

Brain Hollow NAOKONG G.B.-19


Pupil line
2.25 cun
External occipital protuberance
Du-17
G.B.-19
1.5 cun
Du-16
G.B.-20


Du-20
BL-8
Du-19
Du-18
G.B.-8
G.B.-19
BL-9
Du-17
Du-16
G.B.-20
G.B.-12
BL-10
Du-15


External occipital protuberance
Du-17
Du-16
1.5 cun

Location

On the posterior aspect of the head, at the upper border of the external occipital protuberance (→ **Du-17**) and 2.25 cun lateral to the midline.

How to find

First, locate the external occipital protuberance (→ 3.1.5), which can be palpated as a flat protruding area on the midline. Next, find → **Du-17** in the depressoin just superior to the protuberance. From there, measure 2.25 cun in a lateral direction and locate **G.B.-19** on the curved line connecting → **G.B.-15** and → **G.B.-20**, an extension of the pupil line (→ 2.25 cun lateral to the midline or midway between → **Du-24** and → **ST-8**). **For orientation: G.B.-19** is located approximately 2.5 cun superior to the posterior hairline (→ 3.1.5) and approximately 1.5 cun superior to → **G.B.-20** (on the lower border of the occiput, between the origins of the sternocleidomastoid and trapezius muscles).

Needling

0.3–1.5 cun transversely (subcutaneously) towards the occiput or the site of the disorder/pain.

Actions/Indications

- Expels Wind
- Clears the sensory orifices
- Opens the *luo*-connecting vessels

Special features

Meeting point with the *yang wei mai*


ST-8
Chewing movement still palpable
Temporalis

G.B.-20 *Wind Pool* FENGCHI

Location

At the lower border of the occipital bone, in the depression between the origins of the sternocleidomastoid and trapezius muscles.

How to find

Patient's position: Prone, sitting or supine (supported by a pillow, so that the occipital region is accessible). Starting at the midline, glide with the palpating finger along the lower border of the occiput, crossing the bulge of the origin of the trapezius muscle, until you reach a depression the size of a finger pad. Locate **G.B.-20** in its centre.

Located on the same level is → **Du-16**. → **BL-10** is located more medially and inferiorly.

Needling

Needle with the patient's head bent forward and the tip of the needle pointing inferiorly. Depending on the position of the head, insertion towards the tip of the nose or the contralateral orbit, 0.5–1.2 cun. Caution: In slim patients, do not needle deeper than 2 cm (the vertebral artery is located at a depth of approximately 4 cm).

Actions/Indications

- Eliminates Wind, benefits the head, clears the sensory organs
- Opens the channel
- With tonifying needle technique: strengthens the Marrow and the Brain (according to Maciocia)

Special features

Meeting point with the T.B. channel*, *yang wei mai, yang qiao mai*. Major point for all 'Wind disorders', very important point for disorders of the head and eyes.


External occipital protuberance
Sternocleidomastoid
Splenius capitis
Trapezius


Atlas
Du-16
G.B.-20
Occipital bone
G.B.-20
Lower border of the occiput
Axis
BL-10
Du-15
Sternocleido-mastoid
1st palpable spinous process
Trapezius, superior fibres
Du-14


G.B.-14
G.B.-8
T.B.-20
T.B.-23
Ex-HN-5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
G.B.-2
Ma 7
S.I.-18
G.B.-20
T.B.-17
G.B.-12
Ex-HN (*anmian*)
ST-5
ST-6
S.I.-17
T.B.-16
Ren-23
ST-9
S.I.-18
S.I.-16


Du-20
BL-8
Du-19
Du-18
G.B.-8
G.B.-19
BL-9
Du-17
Du-16
G.B.-20
G.B.-12
BL-10
Du-15

---

*According to Deadman et al 1998.

Shoulder Well JIANJING G.B.-21



Location

At the highest point of the shoulder, at the midpoint of a line connecting the 7th cervical vertebra (C7) and the lateral extremity of the acromion.

How to find

First, locate C7 (→ 3.4.1) and the lateral extremity of the acromion (→ 3.3.1). Next, locate **G.B.-21** at the midpoint of a line connecting these two reference points, on the highest point of the trapezius muscle on the sagittal plane.
→ **T.B.-15** is located 1 cun inferior to **G.B.-21**, midway between **G.B.-21** and → **S.I.-13** (medial to the supraspinous fossa).

Needling

Vertically approximately 0.3–0.5 cun (lift the muscle). An alternative, safer method: Lift the muscle and insert the needle approximately 1 cun anteriorly or posteriorly into the muscle belly. Caution: Contraindicated during pregnancy! Pneumothorax.

Actions/Indications

- Opens the channel
- Descends the Qi
- Regulates the Qi flow, transforms Phlegm, dissipates nodules
- Promotes labour, benefits the breasts

Special features

Meeting point with the *yang wei mai* and the T.B. and ST* channels. Important local point. Trigger point for the shoulder with a distal effect on the Uterus.





---

*According to Deadman et al 1998.

G.B.-22 *Armpit Abyss* YUANYE

Location

On the midaxillary line, with the arm abducted approximately 3 cun inferior to the apex of the axilla, in the 4th intercostal space (according to some authors, in the 5th intercostal space).

How to find

With the patient's arm slightly abducted, locate the apex of the axilla. Locate **G.B.-22** 3 cun inferior to it in the 4th intercostal space. **For orientation:** In men, the nipple is located in the 4th intercostal space; in women, in a supine position, its location may vary. Therefore, in women, the manubriosternal synchondrosis (→ 3.5) is a more reliable reference point for the costal region. Note: The intercostal space curves in a superior direction towards lateral.

Also located on the level of or in the 4th intercostal space, but more medially, are → **Ren-17/KID-23/ST-17/P-1/SP-18/G.B.-23** (on the midline/2 cun lateral to the midline/in the centre of the nipple or 4 cun lateral to the midline/1 cun lateral to the nipple or 5 cun lateral to the midline/6 cun lateral to the midline/1 cun anterior to **G.B.-22**).

Needling

0.5–1 cun obliquely or transversely (subcutaneously) along the intercostal space. Caution: Pneumothorax.

Actions/Indications

- Regulates the Qi in the Upper Burner
- Opens the *luo*-connecting vessels of the axilla


1cun
P-1
4th intercostal space


Level of
the nipple
4th intercostal space
Ren-17


Apex of the
axilla
3 cun
G.B.-23
4th intercostal space
1 cun
G.B.-22
5th intercostal space
6th intercostal space
Midaxillary line


SP-20
25
19
19
16
24
18
17
17
18
22
15
LIV-14
G.B.-24
Sternocostal
angle
8
7
6
5
4

Flank Sinews ZHEJIN G.B.-23


Apex of the axilla
3 cun
G.B.-23
4th intercostal space
1 cun
G.B.-22
5th intercostal space
6th intercostal space
Midaxillary line

Location

1 cun anterior to → **G.B.-22** (on the midaxillary line, 3 cun inferior to the apex of the axilla in the 4th intercostal space).

How to find

With the patient's arm slightly abducted, locate the apex of the axilla. First, locate → **G.B.-22** 3 cun inferior to it in the 4th intercostal space, then locate **G.B.-23** 1 cun anterior to → **G.B.-22** and also in the 4th intercostal space. **For orientation:** In men, the nipple is located in the 4th intercostal space; in women, in a supine position, its location may vary. Therefore, in women, the manubriosternal synchondrosis (→ 3.5) is a more reliable reference point for the costal region. Note: The intercostal space curves in a superior direction towards lateral.

Also located on the level of or in the 4th intercostal space, but more medially, are → **Ren-17/KID-23/ST-17/P-1/SP-18** (on the midline/2 cun lateral to the midline/in the centre of the nipple or 4 cun lateral to the midline/1 cun lateral to the nipple or 5 cun lateral to the midline/6 cun lateral to the midline).

Needling

0.5–1 cun obliquely or transversely (subcutaneously) along the 4th intercostal space. Caution: Pneumothorax.

Actions/Indications

- Regulates the Qi between the Upper and Middle Burners
- Opens the channel

Special features

Meeting point with the BL channel according to some authors


KID-24
KID-23
KID-22
4th intercostal space
Ren-17


3rd intercostal space
ST-1
4th intercostal space


SP-18
4th intercostal space
6 cun

G.B.-24 *Sun and Moon* RIYUE

Location

In the 7th intercostal space, on the mamillary line (4 cun lateral to the anterior midline).

How to find

The mamillary line, a vertical line 4 cun lateral to the midline, is used for reference in the thoracic region (→ 3.5). **Quick method, especially in men:** In men, the nipple is usually located on the level of the 4th intercostal space. From the nipple, count downward to the 7th intercostal space. **Or:** A more reliable reference, especially in women, is the manubriosternal synchondrosis, a horizontal bony structure on the sternum. The costal cartilage of the second rib is lateral to the synchondrosis, with the 2nd intercostal space below. From there, count downward to the 7th intercostal space and locate **G.B.-24** on the mamillary line. → **LIV-14** is located directly superior to **G.B.-24** in the 6th intercostal space.

Located approximately on the same level (1 cun inferior to the sternocostal angle) are → **Ren-13/KID-20/ST-20** (on the midline/0.5 cun lateral to the midline/2 cun lateral to the midline).

Needling

0.3–0.8 cun obliquely in a lateral direction along the intercostal space. Caution: Pneumothorax.

Actions/Indications

- Benefits the Gall Bladder, eliminates Damp-Heat, regulates and spreads Liver Qi, descends counterflow Qi, harmonises the Middle Burner

Special features

Front-*mu* point of the Gall Bladder, meeting point with the SP channel, also with the *yang wei mai* according to some authors. Major point for disorders of the Gall Bladder.


Manubriosternal synchondrosis
2nd rib
1
2
3
4
5
6
7
Mamillary line
G.B.-24 in the 7th intercostal space


2nd rib
Manubriosternal synchondrosis
2nd intercostal space
3
4
5
6


G.B.-21
G.B.-23
Level of the nipples
G.B.-22
G.B.-24
LIV-13
G.B.-25
Level of the umbilicus
G.B.-26
Ren-4
G.B.-27
G.B.-28
G.B.-29
Upper border of the pubic symphysis
G.B.-30


SP-20
25
19
19
16
24
18
17
17
18
22
15
LIV-14
G.B-24
12
Sternocostal angle
8
7
6
5
4

Capital Gate JINGMEN **G.B.-25**



Location

On the lateral aspect of the ribcage, at the lower border of the free end of the 12th rib.

How to find

Place the hand on the upper abdomen and, with gentle pressure, glide along the lower border of the ribcage until you can feel the free end of the 11th rib (→ **LIV-13**) slightly superior to the umbilicus. By continuing to palpate along the lower border of the ribcage, you will feel the free end of the 12th rib on the lateral aspect of the waist. Locate **G.B.-25** on its lower border. **For orientation:** When pressing the flexed elbow onto the thorax, the tip of the olecranon will rest on the area around the free end of the 11th rib (→ **LIV-13**).

Needling

Vertically or obliquely 0.3–1 cun. Caution: Peritoneum; the needle should be inserted into the obliquus externus or internus muscles.

Actions/Indications

- Tonifies the Kidneys and regulates the water passages
- Strengthens the Spleen, regulates the Intestines
- Benefits the lumbar region

Special features

Front-*mu* point of the Kidneys







G.B.-26 *Girdling Vessel* DAIMAI

Location

On the lateral aspect of the waist, at the junction of a vertical line through the free end of the 11th rib and a horizontal line through the umbilicus, approximately 1.8 cun inferior to ➞ **LIV-13**.

How to find

First, palpate the lower border of the ribcage to locate the free end of the 11th rib (➞ **LIV-13**). Next, locate **G.B.-26** inferior to the free end of the 11th rib, level with the umbilicus. **Quick method for locating ➞ LIV-13:** When pressing the flexed elbow onto the thorax, the tip of the olecranon will rest on the area around the free end of the 11th rib (➞ **LIV-13**).

Located on the same level are ➞ **Ren-8** (in the centre of the umbilicus), ➞ **KID-16/ST-25/SP-15** (0.5/2/4 cun lateral to the midline).

Needling

Vertically 0.5–1 cun. Caution: Be careful with slim patients.

Actions/Indications

- Regulates the *dai mai*
- Regulates the Uterus
- Drains Damp-Heat

Special features

Meeting point with the *dai mai*


Tip of the olecranon resting on the free end of the 11th rib
Umbilicus
11th rib
G.B.-26


17
17
18
22
15
LIV-14
G.B-24
12
16
22
18
Le 13
15
25
16
8
Sternocostal
8 angle
7
6
5
4
3
2
1
Umbilicus


0.5
KID-16
Ren-08
Umbilicus


11th rib
LIV-13


2 cun
4 cun
ST-25
SP-15



Fifth Pivot WUSHU G.B.-27


Umbilicus
3 cun
Iliac crest
G.B.-27
Anterior superior iliac spine
0.5 cun
G.B.-28



Location

In the depression medial to the anterior superior iliac spine (ASIS), approximately 3 cun inferior to the umbilicus.

How to find

First, locate the anterior superior iliac spine (ASIS → 3.5) by palpating along the upper border of the iliac crest in an anterior and inferior direction. At its anterior end, the ASIS can be palpated as a bony ridge on the lateral aspect of the lower abdomen. Locate **G.B.-27** in a depression anterior and medial to the ASIS.
→ **G.B.-28** is located approximately 0.5 cun inferior and medial to **G.B.-27**.
Located approximately on the same level (3 cun inferior to the umbilicus) are → **Ren-4/KID-13/ST-28** (on the midline/0.5 cun lateral to the midline/2 cun lateral to the midline).

Needling

Vertically 1–1.5 cun. Caution during pregnancy.

Actions/Indications

- Strengthens the Kidneys
- Regulates the *dai mai*
- Regulates the Triple Burner

Special features

Meeting point with the *dai mai*


Anterior superior iliac spine


G.B.-27
Anterior superior iliac spine
0.5 cun
G.B.-28


G.B.-27
G.B.-28
G.B.-29
Highest prominence of the greater trochanter
G.B.-30
BL-36
6 cun
BL-37
G.B.-31
G.B.-32
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15

G.B.-28 *Linking Path* WEIDAO

Location

On the lateral aspect of the abdomen, anterior and inferior to the anterior superior iliac spine (ASIS), approximately 0.5 cun anterior and inferior to → **G.B.-27**.

How to find

First, locate the ASIS (→ 3.5) by palpating along the upper border of the iliac crest in an anterior and inferior direction. On its anterior border, the ASIS can be palpated as a bony ridge on the lateral aspect of the lower abdomen, with → **G.B.-27** located in a depression anterior and medial to the ASIS. Locate **G.B.-28** approximately 0.5 cun anterior and inferior to → **G.B.-27**.

Needling

Vertically 1–1.5 cun. Caution during pregnancy.

Actions/Indications

- Regulates the *dai mai*
- Regulates the Triple Burner
- Eliminates Dampness

Special features

Meeting point with the *dai mai*


Umbilicus
3 cun
Iliac crest
G.B.-27
Anterior superior iliac spine
0.5 cun
G.B.-28


Anterior superior iliac spine

G.B.-27
Anterior superior iliac spine
0.5 cun
G.B.-28

Stationary Crevice JULIAO G.B.-29


Anterior
iliac spine
1/2
G.B.-29
1/2
Greater
trochanter

Location

At the midpoint of a line connecting the anterior superior iliac spine (ASIS) and the greater trochanter, at the anterior border of the iliac crest.

How to find

First, locate the ASIS (→ 3.5), the highest point on the anterior aspect of the iliac crest, by palpating along the upper border of the iliac crest in an anterior and inferior direction. At its anterior end, the ASIS can be palpated as a bony ridge on the lateral aspect of the lower abdomen. With the patient lying on their side and their leg slightly flexed, locate the greater trochanter (→ 3.6), a clearly marked bony structure in the region of the hip joint. **G.B.-29** is located at the midpoint of a line connecting these two reference points.

Needling

Vertically 1–2 cun

Actions/Indications

- Expels Cold, Dampness and Wind, opens the channel

Special features

Meeting point with the *yang qiao mai*, also with the *dai mai* according to some authors.


G.B.-7
G.B.-28
G.B.-29
Highest
prominence of the
greater trochanter
G.B.-30
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
BL-36
6 cun
BL-37
G.B.-31
G.B.-32


Anterior
superior
iliac spine
ASIS
G.B.-29
Greater
trochanter
G.B.-30

Ch04.11-F10028.qxd 2/23/08 11:25 AM Page 428

G.B.-30 *Jumping Circle* HUANTIAO

Location

With the patient lying on their side, the point is at the junction between the medial two-thirds and the lateral third of a line connecting the greater trochanter and the sacral hiatus.

How to find

Patient's position: Supine or, better, lying on their side, preferably with the hip and knee joints of the side to be needled flexed and the lower leg straight. Use pillows, etc, for a comfortable position. Reference points: the sacral hiatus (→ 3.4.4) and the lateral prominence of the greater trochanter (→ 3.6). **G.B.-30** is located on a line connecting these two points, one third of the distance from the greater trochanter.



Needling

1.5–3 cun vertically towards the genital region. The needle may reach the fascia of the obturator internus muscle as well as intermuscular connective tissue. Long 3 cun needles (50mm) should be used. Caution: Needling is often painful. Needling can result in an electric *de qi* sensation radiating to the toes. This sensation is particularly common with sciatic disorders and if **G.B.-30** is needled 1 cun inferior to its normal location.

Actions/Indications

- Opens the channel and the *luo*-connecting vessels, alleviates pain, benefits the hip and legs, eliminates Wind-Damp.



Special features

Meeting point with the BL channel, Ma Dan Yang Heavenly Star point. Important point for disorders of the hips.

Wind Market FENGSHI G.B.-31



Location

On the lateral aspect of the thigh, inferior to the greater trochanter, approximately 7 cun proximal to the popliteal crease.

How to find

Ask the patient to place their hands on the imaginary seam of their trousers (this is best done with the patient standing). **G.B.-31** is located where the middle finger touches the lateral aspect of the thigh. **Or:** The distance between the highest prominence of the greater trochanter (→ 3.6) to the popliteal crease is 19 cun (→ 2.2). Divide this distance into thirds and locate **G.B.-31** 1 cun proximal to a third of the distance from the popliteal crease. Sensitivity to pressure should help determine the location of this point.

Needling

Vertically 1–2 cun

Actions/Indications

- Eliminates Wind, Dampness and Heat
- Opens the channel and alleviates pain


Highest prominence of the greater trochanter
G.B.-27
G.B.-28
G.B.-29
G.B.-30
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
cun
BL-36
6 cun
BL-37
G.B.-31
G.B.-32
G.B.-33
BL-40
BL-39
Popliteal crease
BL-55
G.B.- 34
1
2
3


Median sacral crest
Sacral foramina
Sacral hiatus

G.B.-32 *Middle Ditch* ZHONGDU

Location

On the lateral aspect of the thigh, 5 cun proximal to the popliteal crease, between the vastus lateralis and biceps femoris muscles.

How to find

First, ask the patient to place their hands on the imaginary seam of their trousers (this is best done with the patient standing) and locate → **G.B.-31** where the middle finger touches the thigh. **G.B.-32** can now be located 2 cun distal to → **G.B.-31. Or:** The distance between the highest prominence of the greater trochanter (→ 3.6) to the popliteal crease is 19 cun (→ 2.2). Divide this distance into quarters (use an elastic tape or the spreading hands technique) and locate **G.B.-32** slightly proximal to a quarter of the distance from the popliteal crease. Sensitivity to pressure should help determine the location of this point.

Needling

Vertically 1–2 cun

Actions/Indications

- Eliminates Wind, Dampness and Cold, opens the channel


2 cun
G.B.-31
G.B.-32


G.B.-27
G.B.-28
G.B.-29
Highest prominence of the greater trochanter
G.B.-30
BL-36
6 cun
BL-37
G.B.-31
G.B.-32
G.B.-33
BL-40
BL-39
Popliteal crease
BL-55
G.B.-34
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
cun
1
2
3



Knee Yang Gate XIYANGGUAN G.B.-33







Location

On the lateral aspect of the knee. With the knee flexed, in the depression between the shaft and the lateral epicondyle and the tendon of the biceps femoris muscle, approximately 3 cun proximal to ➞ **G.B.-34**.

How to find

This point is best located with the patient's knee flexed. On the level of the lateral upper border of the patella, palpate in a lateral direction towards the thigh and palpate for the distal end of the lateral epicondyle of the femur. Then locate **G.B.-33** in a clearly palpable depression between the epicondyle and the tendon of the biceps femoris muscle. The latter runs along the lateral aspect of the leg (along the line of an imaginary trouser seam) and attaches inferior to the knee joint at the head of the fibula. ➞ **G.B.-34** is located 3 cun more distal, ➞ **ST-34** is located 2 cun proximal to the lateral upper border of the patella.

Needling

Vertically 1–2 cun

Actions/Indications

- Opens the channel
- Relaxes the tendons

G.B.-34 *Yang Mound Spring* YANGLINGQUAN

Location

In the depression anterior and inferior to the head of the fibula, between the peroneus longus and extensor digitorum longus muscles.

How to find

This point is best located with the patient's knee flexed (use knee support). Palpate for the head of the fibula on the lateral aspect of the leg and hold it with the index and middle fingers in a tweezer-like way. Gliding distally with both fingers, the more medial finger will drop into a depression directly anterior and inferior to the head of the fibula, the location of **G.B.-34**.

Located on the same level but on the medial aspect of the lower leg is → **SP-9** (at the junction of the shaft and the medial condyle of the tibia).

Needling

1–1.5 cun vertical insertion between the tibia and fibula towards the interosseous membrane. Caution: Deep peroneal nerve with deep needling, in some cases also common peroneal nerve. The needle may reach the interosseous membrane as well as the epineural tissue of the peroneal nerve.

Actions/Indications

- Benefits the tendons and joints
- Opens the channel, alleviates pain, benefits the lateral costal region
- Clears Damp-Heat from the Liver and Gall Bladder
- Spreads Liver Qi

Special features

He-sea point, Earth point, *hui*-meeting point of the tendons (coordination/movement), lower *he*-sea point of the Gall Bladder, Ma Dan Yang Heavenly Star point. Major point for disorders of the tendons and musculature.


G.B.-34
Head of the fibula


ST-33
ST-34
Ex-LIV-3
LIV-9
SP-10
Ex-LIV-2
Ex-LIV-1
Popliteal crease
ST-35
Ex-LIV-4
LIV-8
G.B.-34
SP-9
ST-36
ST-37
ST-38
ST-40
ST-39
14
15
16
17
18
19
20
cun
Upper patellar border
1
2
3
4
5
6
7
8
9
10
11
8 cun
Midpoint


Medial condyle of the tibia
SP-9
At the junction of the shaft and medial condyle of the tibia
Gastrocnemius


Vastus lateralis
Vastus medialis
Patella
Medial condyle of the femur
Eye of the knee
Eye of the knee
Head of the fibula
Patellar ligament

Yang Intersection YANGJIAO G.B.-35


Popliteal crease
G.B.-34
7 cun
1/2
Fibula
G.B.-35
7 cun
1/2
Highest prominence of the lateral malleolus


14
15
16
17
18
19
cun
G.B.-32
G.B.-33
BL-39
BL-40
Popliteal crease
BL-55
G.B.-34
1
2
3
4
BL-56
5
6
7
8
G.B.-35
BL-57
G.B.-36
9
BL-58




BL-57
1 cun
BL-58

Location

7 cun proximal to the highest prominence of the lateral malleolus, on the **posterior** border of the fibula.

How to find

Quick method: Spreading hands technique (→ 2.3.3): Locate **G.B.-35** at the midpoint of a line connecting → **G.B.-34** (in the depression anterior and inferior to the head of the fibula) and the highest prominence of the lateral malleolus (→ 3.6.2), on the **posterior** border of the fibula (distance = 14 cun). **G.B.-35** is located 7 cun proximal to the prominence of the lateral malleolus. **Or:** Spreading hands technique (→ 2.3.3): Locate **G.B.-35** 1 cun distal to the midpoint of a line connecting the popliteal crease and the highest prominence of the lateral malleolus, on the **posterior** border of the fibula (distance = 16 cun, → 2.2). **For orientation:** The borders of the fibula are deep to the peroneus brevis muscle and are often not easily palpable. For this reason, it is suggested to palpate the posterior border of the fibula just superior to the lateral malleolus and then locate the point on an imaginary line running to the head of the fibula.
Located on the same level are → **G.B.-36** (on the **anterior** border of the fibula) and → **BL-58** (7 cun proximal to → **BL-60**).

Needling

Vertically 0.5–1.5 cun

Actions/Indications

- Clears Heat, opens the channel, relaxes the tendons
- Regulates Qi of the Gall Bladder
- Calms the *shen*

Special features

Xi-cleft point of the *yang wei mai*, meeting point with the *yang wei mai* according to some authors.

G.B.-36 *Outer Mound* WAIQIU

Location

7 cun proximal to the highest prominence of the lateral malleolus, on the **anterior** border of the fibula.

How to find

Quick method: Spreading hands technique (→ 2.3.3): Locate → **G.B.-35** at the midpoint of a line connecting → **G.B.-34** (in the depression anterior and inferior to the head of the fibula) and the highest prominence of the lateral malleolus (→ 3.6.2), on the **anterior** border of the fibula (distance = 14 cun). **G.B.-36** is located 7 cun proximal to the prominence of the lateral malleolus. **Or:** Spreading hands technique (→ 2.3.3): locate **G.B.-36** 1 cun distal to the midpoint of a line connecting the popliteal crease and the highest prominence of the lateral malleolus, on the **anterior** border of the fibula (distance = 16 cun, → 2.2).
For orientation: The borders of the fibula are deep to the peroneus brevis muscle and are often not easily palpable. For this reason, it is suggested to palpate the anterior border of the fibula just superior to the ankle and then locate the point on an imaginary line running to the head of the fibula.
Located on the same level are → **G.B.-35** (on the **posterior** border of the fibula) and → **BL-58** (7 cun proximal to → **BL-60**).



Needling

Vertically 0.5–1.5 cun

Actions/Indications

- Regulates Gall Bladder and Liver Qi
- Drains Damp-Heat
- Relaxes the tendons and muscles
- Calms the *shen*

Special features

Xi-cleft point



Bright Light **GUANGMING** **G.B.-37**


Popliteal crease
G.B.-34
1/2
9 cun
2 cun
G.B.-37
1/2
5 cun
G.B.-39
Highest prominence of the lateral malleolus

Location

5 cun proximal to the highest prominence of the lateral malleolus, on the anterior border of the fibula, between the peroneus longus and extensor digitorum longus muscles.

How to find

Quick method: Spreading hands technique (➞ 2.3.3): Place the little fingers on ➞ **G.B.-34** (in the depression anterior and inferior to the head of the fibula) and the highest prominence of the lateral malleolus (➞ 3.6.2). This distance is 14 cun. From the midpoint of this distance, measure 2 cun in a distal direction and locate **G.B.-37** on this level in a depression on the **anterior** border of the fibula. This depression is located 5 cun proximal to the prominence of the lateral malleolus (the width of 1 hand and 2 thumbs). **For orientation:** The borders of the fibula are deep to the peroneus brevis muscle and are often not easily palpable. For this reason, it is suggested to palpate the anterior border of the fibula just superior to the ankle and then locate the point on an imaginary line running to the head of the fibula.

Needling

Vertically 0.5–1.5 cun

Actions/Indications

- Benefits the eyes
- Eliminates Wind-Damp, opens the channel, alleviates pain

Special features

Luo-connecting point. Important distal point for disorders of the eyes.


G.B.-34
Midpoint
Highest prominence of the lateral malleolus


Midpoint
G.B.-37


G.B.-35
G.B.-36
BL- 57
BL- 58
8
9
10
11
12
13
14
15
16
cun
G.B.-37
G.B.-38
G.B.-39
BL-59
BL-60
G.B.-40
G.B.-44
Highest prominence of the lateral malleolus


G.B.-37
3 cun
Highest prominence of the lateral malleolus


G.B.-37
2 cun
3 cun
Highest prominence of the lateral malleolus

G.B.-38 *Yang Assistance* YANGFU

Location

4 cun proximal to the highest prominence of the lateral malleolus, on the **anterior** border of the fibula.

How to find

First, locate the prominence of the lateral malleolus (→ 3.6.2) and, from there, measure 4 cun in a proximal direction. There, locate **G.B.-38** on the **anterior** border of the fibula. **Or:** On the lateral aspect of the lower leg, the distance between the prominence of the lateral malleolus (→ 3.6.2) and the popliteal crease is 16 cun (→ 2.2). Divide this distance into quarters and locate **G.B.-38** one quarter of the distance from the lateral malleolus (aid: spreading hands technique or elastic tape → 2). **For orientation:** The borders of the fibula are deep to the peroneus brevis muscle and are often not easily palpable. For this reason, it is suggested to palpate the anterior border of the fibula just superior to the ankle and then locate the point on an imaginary line running to the head of the fibula.


Popliteal crease
Fibula
12 cun
3/4
G.B.-38
4 cun
1/4
Highest prominence of the lateral malleolus

Needling

Vertically 0.5–1.5 cun

Actions/Indications

- Opens the channel
- Clears Wind and Heat

Special features

Jing-river point, Fire point, sedation point.


G.B.-35
BL-57
G.B.-36
BL-58
G.B.-37
G.B.-38
G.B.-39
BL-59
BL-60
G.B.-40
G.B.-42
G.B.-44
8
9
10
11
12
13
14
15
16
cun
Highest prominence of the lateral malleolus

Hanging Bell XUANZHONG G.B.-39


G.B.-39
3 cun
Highest prominence of the lateral malleolus


G.B.-39
Highest prominence of the lateral malleolus


BL-59
Highest prominence of the lateral malleolus
3 cun
Anterior border of the Achilles tendon



Location

3 cun proximal to the highest prominence of the lateral malleolus, on the **anterior** border of the fibula.

How to find

From the highest prominence of the lateral malleolus (→ 3.6.2), measure 3 cun (1 handbreadth) in a proximal direction and locate **G.B.-39** in a depression on the **anterior** border of the fibula. According to some authors, it is located between the posterior border of the fibula and the tendons of the peroneus longus and brevis musles. When in doubt, choose the more pressure-sensitive point.

Located on the same level but 3 cun proximal to → **BL-60** (depression between the malleolus and the Achilles tendon) is → **BL-59**. In a comparable position but on the medial aspect of the leg is → **SP-6** (3 cun proximal to the highest prominence of the medial malleolus, meeting point of the three leg Yin channels).

Needling

Vertically 1–1.5 cun

Actions/Indications

- Opens the channel, benefits the tendons and bones
- Benefits the Marrow, clears Wind-Dampness
- Clears Heat from the Gall Bladder

Special features

Hui-meeting point of the Marrow. Important distal point for disorders of the cervical spine.

G.B.-40 *Mound of Ruins* QIUXU

Location

In the depression anterior and inferior to the lateral malleolus, lateral to the tendons of the extensor digitorum longus muscle.

How to find

For easier location, ask the patient to flex their ankle at a 90° angle. From the lateral malleolus (→ 3.6.2), let the palpating finger glide into a well-defined depression anterior and inferior to the malleolus. By lifting the toes, the tendons of the extensor digitorum longus muscle as well as the depression (**G.B.-40**) will become more pronounced. **For orientation: G.B.-40** is located at the junction of a vertical line along the anterior border of the lateral malleolus and a horizontal line along its lower border.

→ **SP-5** is located in a comparable position but on the medial aspect of the ankle (in the depression anterior and inferior to the medial malleolus). On a line connecting → **SP-5** and **G.B.-40**, → **LIV-4** is located medial to and → **ST-41** is located lateral to the tendon of the extensor hallucis longus muscle, which runs to the big toe.

Needling

0.5–1.5 cun vertically or slightly obliquely in the area of the fibulotarsal ligaments towards the medial arch of the foot.

Actions/Indications

- Opens the channel, benefits the joints
- Spreads Liver Qi, clears Heat and Dampness from the Gall Bladder

Special features

Yuan-source point


Ankle joint space
Tendon of tibialis anterior
LIV-4
ST-41


Anterior border of the lateral malleolus
Inferior border of the lateral malleolus
G.B.-40


G.B.-40
Tendons of the extensor digitorum longus


G.B.-35
G.B.-36
G.B.-37
G.B.-38
G.B.-39
G.B.-40
G.B.-42
G.B.-44
BL-57
BL-58
BL-59
BL-60
8
9
10
11
12
13
14
15
16
cun
Highest prominence of the lateral malleolus


Highest prominence of the medial malleolus
SP-5

Foot Governor of Tears ZULINQI G.B.-41


Base of the 5th metatarsal bone
G.B.-41
G.B.-42
Tendons of the extensor digitorum


Middle finger on the base of the 5th metatarsal
G.B.-41


G.B.-41
G.B.-42
Tendons

Location

In the depression at the junction of the shafts and the bases of the 4th and 5th metatarsal bones, lateral to the tendon of the extensor digitorum longus muscle.

How to find

Palpate for the distinct tuberosity of the 5th metatarsal bone (→ 3.6.2) on the lateral aspect of the midfoot. With the palpating finger, glide on from the tuberosity to the dorsum of the foot, into the groove between the 4th and 5th metatarsal bones. There, palpate in a distal direction. **G.B.-41** is located at the junction of the heads and the shafts of the two bones. **Or:** Ask the patient to abduct their toes so that the branch of the tendon of the extensor digitorum longus muscle extending to the little toe becomes more pronounced. Then palpate in the groove between the 4th and 5th metatarsal bones from distal to proximal to where the tendon crosses the groove. → **G.B.-42** is located medial (or anterior) to it, while **G.B.-41** is located in the depression lateral (or posterior) to the tendon.

Needling

Perpendicularly or obliquely approximately 0.3–0.8 cun

Actions/Indications

- Spreads Liver Qi, benefits the thorax and the lateral costal region, transforms Phlegm, dissipates nodules, benefits the breasts
- Clears the head, benefits the eyes

Special features

Shu-stream point, Wood point, opening point of the *dai mai*, *ben* point (Five Phases), exit point.


BL- 60
G.B.- 40
BL- 62
G.B.- 41
G.B.- 42
G.B.- 43
G.B.- 44
BL- 63
BL- 61
BL- 64
BL- 67
BL- 66
BL- 65

G.B.-42 *Earth Five Meetings* DIWUHUI

Location

Between the 4th and 5th metatarsal bones, proximal to the metatarsophalangeal joints and medial to the tendon of the extensor digitorum longus muscle.

How to find

From the space between the 4th and 5th toes, palpate towards the ankle. Locate **G.B.-42** in the groove between the two bones, proximal to the metatarsophalangeal joints (and proximal to the heads of the two metatarsal bones). **Or:** Ask the patient to abduct their toes so that the branch of the tendon of the extensor digitorum longus muscle extending to the little toe becomes more pronounced. Then palpate from the space between the toes along the groove between the 4th and 5th metatarsal bones from distal to proximal to where the tendon crosses the groove. **G.B.-42** is located medial (or anterior) to the tendon.

→ **G.B.-41** is located lateral (or posterior) to the tendon when continuing to palpate along the groove. → **BL-65** is located approximately on the same level on the lateral border of the foot, proximal to the head of the 5th metatarsal bone.

Needling

Vertically or obliquely 0.3–0.8 cun

Actions/Indications

- Moves Liver Qi
- Clears Heat from the Gall Bladder


Base of the 5th metatarsal bone
G.B.-41
G.B.-42
Tendons of the extensor digitorum longus





Clamped Stream JIAXI/XIAXI G.B.-43


Proximal to the interdigital fold
G.B.-43

Location

Between the 4th and 5th toes, proximal to the margin of the interdigital web.

How to find

Locate the interdigital web between the 4th and 5th toes. Then locate **G.B.-43** slightly proximal to the margin of the web. **G.B.-43** as well as → **LIV-2** and → **ST-44** are part of → **Ex-UE-10** (*bafeng*: proximal to the margins of the webs between the toes). → **T.B.-2** is located in a comparable position on the hand, between the ring finger and little finger. It is also part of → **Ex-UE-9** (*baxie*).

Needling

Up to 0.5 cun vertically or 1 cun obliquely in a proximal direction.

Actions/Indications

- Clears Heat, Damp-Heat and Wind, especially from the opposite end of the channel
- Calms Liver Yang

Special features

Ying-spring point, Water point, tonification point.


BL- 60
G.B.- 40
BL- 62
G.B.- 41
G.B.- 42
G.B.- 43
G.B.- 44
BL- 61
BL- 63
BL- 64
BL- 67
BL- 66
BL- 65


T.B.-2
Proximal to the interdigital fold




BL- 63
G.B.-40
ST-41
Mi-5
LIV-4
BL-64
ST-42
G.B.-41
Mi-4
BL-65
LIV-3
G.B.-42
G.B.-43
ST-43
BL-66
Mi-3
BL-67
ST-44
G.B.-44
Ex-LIV-10
(bafeng)
LIV-1
Mi-1
ST-45

G.B.-44 *Foot Portal Yin* ZUQIAOYIN

Location

On the 4th toe, 0.1 cun from the lateral corner of the nail.

How to find

G.B.-44 is located at the junction of two tangents along the proximal and lateral borders of the 4th toe.

→ **BL-67** is located at the lateral corner of the little toe.

Needling

0.1 cun vertically or 0.2 cun obliquely in a proximal direction or prick to bleed. Caution: Painful point.

Actions/Indications

- Clears Wind, Heat and Fire
- Harmonises the Liver and Gall Bladder
- Calms the *shen*

Special features

Jing-well point, Metal point


Correct
Wrong
G.B.-44
G.B.-44


G.B.- 41
BL- 65
G.B.-42
G.B.-43
BL- 66
BL- 67
G.B.-44
Ex-LIV- 10
(*bafeng*)
ST- 43
ST- 44
ST- 45
LIV-3
LIV-1
SP-4
SP-3
SP-2
SP-1


BL-60
G.B.-40
BL-62
G.B.-41
G.B.-42
G.B.-43
G.B.-44
BL-61
BL-63
BL-64
BL-67
BL-66
BL-65

4.12 The Liver Channel System – Foot *jueyin* (*zu jue yin jing luo*)

4.12.1 The Liver Primary Channel (*zu jue yin jing*)


Du-20
Lu-1
P-1
LIV-14
Ren-4
Ren-3
Ren-2
SP-13
SP-12
LIV-10
SP- 6
G.B.-41
LIV-1


LIV-1
LIV-2
LIV-3
LIV-4


2 cun
1 cun
LIV-12
LIV-11
LIV-10
Sartorius
Gracilis
Semimembranosus
Semitendinosus
Medial condyle
of the femur
KID-10
LIV-8
LIV-9
Pes anserinus
superficialis
4 cun
Medial
condyle of
the femur
LIV-8
Junction of the
shaft and medial
condyle of the tibia
LIV-7
LIV-6
LIV-5
2
5
Highest prominence
of the medial
malleolus
LIV-4
cun
13 cun

Pathway

The Liver primary channel begins at **LIV-1** (*dadun*) on the lateral corner of the nail of the big toe. This point is reached by a small branch of the G.B. channel, which separates from the Gall Bladder primary channel on the dorsum of the foot at → **G.B.-41** (*zulinqi*) (foot Yin–Yang connection of the third great circuit).





The **external pathway** runs proximally between the 1st and 2nd metatarsal bones

- ascends anterior to the medial malleolus
- crosses the SP channel at → **SP-6** (*yinlingquan*) on the medial aspect of the lower leg
- ascends the medial aspect of the leg towards the knee anterior to the SP channel
- continues along the medial aspect of the thigh to the pubic region, where it passes → **SP-12** (*chongmen*) and → **SP-13** (*fushe*)
- circles the external genitalia
- ascends the lower abdomen, passing → **Ren-2** (*qugu*), → **Ren-3** (*zhongji*) and → **Ren-4** (*guanyuan*)
- obliquely traverses the abdomen to **LIV-13** (*zhangmen*) at the free end of the 11th rib and to **LIV-14** (*qimen*), where the **external pathway** terminates.

At **LIV-13**, the channel enters the abdomen, marking the beginning of the **internal pathway**. It

- circles the Stomach (*wei*)
- connects with its pertaining *zang*-Organ, the Liver (*gan*) and its paired *fu*-Organ, the Gall Bladder (*dan*)
- penetrates the diaphragm
- spreads in the lateral hypochondrium and thoracic region.

The channel then ascends along the posterior aspect of the trachea to the throat and nasopharynx and connects with the eye system and the brain. It crosses the forehead and ascends to the vertex, where it connects with the extraordinary vessel *du mai* at → **Du-20** (*baihui*).

An **internal branch** descends from the maxillary sinus to the cheek and circles the **inner surface** of the lips.

An **internal branch** emerges from the Liver, penetrates the diaphragm, disperses in the Lung (*fei*) and meets the Lung primary channel (deep Yin–Yin connection), closing the first circuit of the Nutritive Qi (*ying qi*) (→ 1.1.4). This branch further connects with the Pericardium primary channel beneath → **P-1** (*tianchi*) (hand–foot pairing of the third great circuit: Yin axes, *jue yin*).

Clinical importance (→ 1.2)

Exterior (*biao*) signs and symptoms: Headaches, dizziness, blurred vision, tinnitus, fever, spastic extremities

Interior (*li*) or *zangfu*-Organ signs and symptoms: Distension, fullness and pain in the costal region, tightness and fullness in the chest, abdominal pain, vomiting, jaundice, diarrhoea, *shan* disorder, enuresis, urinary retention, yellow urine

Connections of the Liver primary channel (→ 1.2)

Connections with other channels

Gall Bladder primary channel (*zu shao yang jing*)

Connection: Foot Yin–Yang pairing of the third great circuit
Location: G.B.-41 → LIV-1 (on the foot)
Circulation: Circadian (according to the Organ clock)
Importance: Exterior–Interior relationship

Pericardium primary channel (*shou jue yin jing*)

Connection: Paired according to the six-channel theory (hand–foot pairing): *jue yin* (Yin axes of the third great circuit)
Location: LIV → P. An internal branch originating in the Liver penetrates the diaphragm and connects with the Pericardium primary channel beneath → P-1.
Circulation: Non-circadian (not according to the Organ clock)
Importance: Above–below relationship

Lung primary channel (*shou tai yin jing*)

Connection: Deep Yin–Yin connection
Location: LIV → LU (in the thorax). An internal branch originating in the Liver penetrates the diaphragm and disperses in the Lung to connect with the Lung primary channel.
Circulation: Circadian (according to the Organ clock)
Importance: The Lung primary channel receives part of its Nutritive Qi (*ying qi*) from the Liver primary channel (first circulation of the *ying qi* → 1.1.4).

Connections with zangfu-Organ systems

Stomach (*wei*), **Liver (*gan*)**, **Gall Bladder (*dan*)**, Lung (*fei*)

4.12.2 The Liver Divergent Channel (*zu jue yin jing bie*)



Pathway

The Liver divergent channel separates from the Liver primary channel on the dorsum of the foot

- ➡ ascends the medial aspect of the leg to the inguinal region
- ➡ meets the Gall Bladder divergent channel near → **Ren-2** (*qugu*)
- ➡ traverses the abdomen and enters internally at **LIV-13** (*zhangmen*)
- ➡ continues inside the thoracic cavity, spreads in the Liver (*gan*), connects with the Gall Bladder (*dan*) and runs to the Heart (*xin*)
- ➡ ascends to the neck
- ➡ emerges at the mandibular angle and disperses over the face
- ➡ connects with the Gall Bladder primary channel and the Gall Bladder divergent channel at → **G.B.-1** (*tongziliao*) on the outer canthus of the eye to form one of the six *he*-confluences (here: G.B./LIV as 2nd confluence → 1.3)
- ➡ continues to the eye system and ends in the Brain.

Clinical importance

- Strengthens the relationship between the Liver and the Gall Bladder (*zangfu*-Organ systems). Points on the Liver primary channel can therefore be used to treat disorders of the Gall Bladder and vice versa.
- Based on the pathways of the Gall Bladder and Liver divergent channels, points on both channels can be used for disorders of the hips and the lower extremities as well as for disorders of the eye system.

4.12.3 The Liver Sinew Channel (*zu jue yin jing jin*)



Pathway

The Liver sinew channel begins on the dorsum of the big toe

- ➡ follows the dorsolateral aspect of the big toe to the anterior aspect of the medial malleolus, where it binds (*jie*)
- ➡ ascends the medial aspect of the tibia and binds (*jie*) at the medial aspect of the knee
- ➡ further ascends the medial aspect of the thigh between the Kidney and Spleen sinew channels
- ➡ reaches the inguinal region, meeting the other foot Yin sinew channels at → **Ren-3** (*zhongji*) and continues to the genitalia.

Clinical importance

Pathology: Stiffness, tension and distending sensations along the big toe. Pain around the medial malleolus and medial aspect of the knee. Pain and muscular tension along the medial aspect of the thigh. Disorders of the genital region.

Indication: Pain, tension, muscle contractions and distending sensations along the pathway of the channel. Disorders of the genital region.

4.12.4 The Liver *luo*-Connecting Vessel System (*zu jue yin luo mai*)



Pathway

The Liver *luo*-connecting vessel system separates from the Liver primary channel at its *luo* point **LIV-5** (*ligou*) (→ 8.1.2). It forms a three-dimensional reticular network, dividing into multiple branches and sub-branches (*sun luo, fu luo, xue luo* → 1.5) within the surrounding tissue.

- Horizontal divisions run to the Interiorly–Exteriorly paired Gall Bladder primary channel; according to some schools of thought (for example, Ngyen Van Nghi → Appendix), they travel as a **transverse** Liver *luo*-connecting vessel to the *yuan*-source point → **G.B.-40** (*qiuxu*).
- **A longitudinal division** ascends the medial aspect of the leg to the genital region, where it branches out.

Clinical importance (→ 8.1.2)

Pathology

Counterflow Qi: Swellings and pain of the testicles and scrotum, hernia
Excess (*shi*): Priapism
Deficiency (*xu*): Itching of the external genitalia

4.12.5 Cutaneous Region (*jue yin pi bu*)

See description and figures → 1.6.

4.12.6 Points of the Liver Primary Channel (Overview)

Specific points according to their function

- ***Yuan*-source point (→ 8.1.1): LIV-3** (*taichong*) 🟦🟦
- ***Luo*-connecting point (→ 8.1.2.): LIV-5** (*ligou*) 🟦⬛
- ***Xi*-cleft point (→ 8.1.3): LIV-6** (*zhongdu*) 🟦⬛
- **Associated Back-*shu* point (→ 8.1.4): BL-18** (*ganshu*) 🟦⬛
- **Associated Front-*mu* point (→ 8.1.5): LIV-14** (*qimen*) 🟦⬛
- **Five *shu*-transporting points (→ 8.1.6):**
  jing-well point (Wood): **LIV-1** (*dadun*) 🟦⬛, *ben* point (Five Phases)
  ying-spring point (Fire): **LIV-2** (*xingjian*) 🟦🟦
  shu-stream point (Earth): **LIV-3** (*taichong*) 🟦🟦
  jing-river point (Metal): **LIV-4** (*zhongfeng*)
  he-sea point (Water): **LIV-8** (*ququan*) 🟦⬛, tonification point
- ***Hui*-meeting point (→ 8.1.7) of the *zang*-Organs: LIV-13** (*zhangmen*) 🟦🟦
- **Opening point (→ 8.1.8): –**
- **Lower *he*-sea point (→ 8.1.9): –**
- ***Jiaohui*-meeting points (→ 8.1.10):**
  – with the G.B. channel and the *dai mai**: **LIV-13** (*zhangmen*) 🟦🟦

---

*Mentioned by only some authors

Ch04.12-F10028.qxd 2/23/08 11:31 AM Page 448

  - – with the *yin wei mai* and the ST channel: **LIV-14** (*qimen*) 🟦⬛
  - – of other channels with the LIV channel: **SP-6, SP-12, SP-13, Ren-2, Ren-3, Ren-4, P-1, (Du-20*)**
- **Gao Wu command point (→ 8.1.11): –**
- **Window of Heaven point (→ 8.1.12): –**
- **Points of the Four Seas (→ 8.1.13): –**
- **Ma Dan Yang Heavenly Star point (→ 8.1.14): LIV-3** (*taichong*) 🟦🟦
- **Sun Si Miao Ghost point (→ 8.1.15): –**
- **Other functional points:**
  - – Front-*mu* point of the Spleen: **LIV-13** (*zhangmen*) 🟦🟦

Points according to region

- **Local points** (→ 8.2.1): Liver – **LIV-13** (*zhangmen*) 🟦🟦; knee – **LIV-7** (*xiguan*), **LIV-8** (*ququan*) 🟦⬛; foot – **LIV-4** (*zhongfeng*)
- **Adjacent points (→ 8.2.1):** Stomach/Spleen – **LIV-13** (*zhangmen*) 🟦🟦; hypochondrium – **LIV-13** (*zhangmen*) 🟦🟦, **LIV-14** (*qimen*)
- **Distal points** (→ 8.2.1): vertex – **LIV-3** (*taichong*) 🟦🟦; eyes – **LIV-2** (*xingjian*) 🟦🟦, **LIV-3** (*taichong*) 🟦🟦; Liver – **LIV-3** (*taichong*) 🟦🟦; Gall Bladder – **LIV-3** (*taichong*) 🟦🟦; urogenital region – **LIV-3** (*taichong*) 🟦🟦; genital region – **LIV-5** (*ligou*) 🟦⬛; lower abdomen – **LIV-8** (*ququan*) 🟦⬛

Specific points according to the channel pathway (in numeric order)

- **LIV-1** (*dadun*) 🟦⬛: *jing*-well point (Wood), *ben* point (Five Phases) (→ 8.1.6)
- **LIV-2** (*xingjian*) 🟦🟦: *ying*-spring point (Fire) (→ 8.1.6), sedation point; distal point for the eyes (→ 8.2.1)
- **LIV-3** (*taichong*) 🟦🟦: *yuan*-source point (→ 8.1.1); *shu*-stream point (Earth) (→ 8.1.6); Ma Dan Yang Heavenly Star point (→ 8.1.4); distal point for the vertex, eyes, Liver, Gall Bladder and urogenital region (→ 8.2.1)
- **LIV-4** (*zhongfeng*): *jing*-river point (Metal) (→ 8.1.6); local point for the foot (→ 8.2.1)
- **LIV-5** (*ligou*) 🟦⬛: *luo*-connecting point (→ 8.1.2); distal point for the genital region (→ 8.2.1)
- **LIV-6** (*zhongdu*) 🟦⬛: *xi*-cleft point (→ 8.1.3)
- **LIV-7** (*xiguan*): local point for the knee (→ 8.2.1)
- **LIV-8** (*ququan*) 🟦⬛: *he*-sea point (Water) (→ 8.1.6); tonification point; distal point for the abdomen (→ 8.2.1); local point for the knee (→ 8.2.1)
- **LIV-13** (*zhangmen*) 🟦🟦: Front-*mu* point of the Spleen (→ 8.1.5); *hui*-meeting point of the *zang*-Organs (→ 8.1.7); *jiaohui*-meeting point with the G.B. channel and the (*dai mai**) (→ 8.1.10); adjacent point for the Spleen/Stomach and the hypochondrium (→ 8.2.1)
- **LIV-14** (*qimen*) 🟦⬛: associated Front-*mu* point(→ 8.1.5); *jiaohui*-meeting point with the *yin wei mai* and the SP channel (→ 8.1.10); regional point for the hypochondrium (→ 8.2.1)

---

* Mentioned by only some authors

Big Mound DADUN LIV-1



Location

On the lateral aspect of the big toe, 0.1 cun proximal and lateral to the corner of the nail.

How to find

LIV-1 is located at the junction of two tangents along the proximal and lateral borders of the big toe, 0.1 cun from the actual margin of the nail. → **SP-1** is located at the medial corner of the big toe.

Needling

Vertically or obliquely 0.1–0.2 cun. Avoid needling into the perionychium. For excess conditions, prick to bleed. Caution: Painful point.

Actions/Indications

- Regulates the Lower Burner, the genitals and Liver Qi
- Eliminates Dampness
- Opens the sensory orifices

Special features

Jing-well point, Wood point, *ben* point (Five Phases), entry point.


G.B.-41
SP-4
BL-65
G.B.-42
LIV-3
G.B.-43
ST-43
BL-66
SP-3
BL-67
ST-44
SP-2
G.B.-44
Ex-LE-10
(*bafeng*)
LIV-1
SP-1
ST-45



LIV-2 *Moving Between* XINGJIAN

Location

Between the 1st and 2nd toes, proximal to the margin of the interdigital web.

How to find

Locate **LIV-2** slightly proximal to the margin of the interdigital web between the 1st and 2nd toes.
Located in comparable positions are → **ST-44** (between the 2nd/3rd toes) and → **G.B.-43** (between the 4th/5th toes). → **LIV-2,** → **ST-44** and → **G.B.-43** are all part of the extra point → **Ex-LE-10** (*bafeng*). Its counterpart on the hand is the extra point → **Ex-UE-9** (*baxie*).

Needling

0.3–0.5 cun obliquely towards the heel or vertically.

Actions/Indications

- Clears Liver Fire, spreads Liver Qi, calms (internal) Liver Wind, clears Heat and Blood Heat, stops bleeding, benefits the Lower Burner

Special features

Ying-spring point, Fire point, sedation point. Major point for excess syndromes of the Liver (especially Liver Fire).







Great Rushing TAICHONG **LIV-3**


2nd metatarsal bone
LIV-3
1st metatarsal bone
LIV-2
1.5–2 cun
Interdigital fold


Depression at LIV-3


Carpal II
L.I.-4

Location

On the dorsum of the foot, between the 1st and 2nd metatarsal bones, in the depression proximal to the metatarsophalangeal joints and the proximal angle between the two bones.

How to find

From the web between the 1st and 2nd toes, palpate proximally past the metatarsophalangeal joints and along the groove between the 1st and 2nd metatarsal bones, until you reach the widest and deepest part of the groove. There, locate **LIV-3**, which is often sensitive to pressure. To double-check: When continuing to palpate along the groove, it will become more narrow and shallow again.

Located in a similar position on the hand is → **L.I.-4** (between the 1st and 2nd metacarpal bones).

Needling

Vertically or slightly obliquely 0.5–1 cun. Caution during pregnancy.

Actions/Indications

- Spreads Liver Qi, clears the head, benefits the eyes, nourishes Liver Blood and Liver Yin, calms spasms, alleviates pain, regulates menstruation and the Lower Burner
- Eliminates (internal) Wind, pacifies Liver Yang

Special features

Yuan-source point, *shu*-stream point, Earth point, Ma Dan Yang Heavenly Star point (later added by Xu Feng). Major point for spreading Liver Qi.


G.B.-41
SP-4
BL-65
G.B.-42
LIV-3
G.B.-43
ST-43
BL-66
SP-3
BL-67
ST-44
SP-2
G.B.-44
Ex-LE-10
(*bafeng*)
LIV-1
SP-1
ST-45

LIV-4 *Middle Seal* ZHONGFENG

Location

1 cun anterior to the prominence of the medial malleolus, medial to the tendon of the tibialis anterior muscle.

How to find

Even with slight dorsiflexion of the ankle, the tendon of the tibialis anterior muscle will become more pronounced on the medial aspect of the ankle. **LIV-4** is located between the tendon and the prominence of the medial malleolus, in a depression over the palpable joint space.

→ **ST-41** is also located over the joint space (on the midpoint of its anterior aspect); → **SP-5** lies only slightly distal to → **LIV-4** at the junction of a vertical line along the anterior border and a horizontal line along the lower border of the medial malleolus.

Needling

Vertically 0.3–0.5 cun

Actions/Indications

- Opens the channel, promotes the flow of Liver Qi, regulates the Lower Burner

Special features

Jing-river point, Metal point.


Tendon of the
extensor pollicis longus
and
tibialis anterior
LIV-4
SP-5
Prominence of the
medial malleolus


SP-6
KID-7
KID-8
LIV-4
KID-3
KID-4
SP-5
KID-6
KID-5
SP-1
KID-2
SP-4
SP-3
SP-2


BL- 63
G.B.-40
ST-41
LIV-4
Mi-5
BL-64
ST-42
G.B.-41
Mi-4
BL-65
G.B.-42
LIV-3
G.B.-43
ST-43
BL-66
Mi-3
BL-67
ST-44
Mi-2
G.B.-44
Ex-LIV-10
(*bafeng*)
LIV-1
Mi-1
ST-45


Tibia
Fibula
Trochlea tali
Talocrural joint
Medial malleolus
Subtalar joint
Lateral malleolus

Woodworm Canal LIGOU LIV-5







Location

On the medial aspect of the lower leg, 5 cun proximal to the highest prominence of the medial malleolus, just posterior to the medial crest of the tibia, between the crest of the tibia and the gastrocnemius muscle.

How to find

First, locate the highest prominence of the medial malleolus (→ 3.6.2). From there, palpate 5 cun in a proximal direction and there locate **LIV-5** in a depression directly posterior to the medial crest of the tibia. **Or quick method:** Divide the distance between the medial end of the popliteal crease and the highest prominence of the medial malleolus (=approximately 15 cun, → 2.2) into thirds and locate **LIV-5** a third of the distance from the medial malleolus. Note: Some texts locate **LIV-5 on** the tibia, others on the **posterior** border of the tibia; sensitivity to pressure should be the determining factor. → **KID-9** is located on the same level but directly superior to → **KID-3** (between the medial malleolus and the Achilles tendon).

Needling

0.5–1 cun vertically or obliquely in a posterior direction towards the fibula or transversely (subcutaneously) along the tibia towards the abdomen.

Actions/Indications

- Regulates Liver Qi, benefits the genitals, clears Damp-Heat from the Lower Burner, regulates menstruation
- Eliminates ‘plum-pit’ Qi
- Moves Qi locally

Special features

Luo-connecting point. Important distal point for the urogenital region (especially with Liver Qi stagnation and Damp-Heat).



LIV-6 *Central Capital* ZHONGDU

Location

7 cun proximal to the highest prominence of the medial malleolus, just posterior to the medial crest of the tibia.

How to find

First, locate the highest prominence of the medial malleolus (→ 3.6.2). From there, palpate 7 cun (= the width of 2 hands and 1 thumb) in a proximal direction and there locate **LIV-6** in a depression directly posterior to the medial crest of the tibia. **Or quick method:** Spreading hands technique (→ 2.3.3): Place the little fingers on the medial end of the popliteal crease and the highest prominence of the medial malleolus respectively and join the thumbs on the posterior border of the tibia at the mid-point of this distance (= approximately 15 cun, 2.2). From there, measure 0.5 cun in a distal direction and here locate **LIV-6** posterior to the medial crest of the tibia. Note: Some texts locate **LIV-6 on** the tibia, others on the **posterior** border of the tibia; sensitivity to pressure should be the determining factor.



Needling

0.5–1 cun vertically or obliquely in a posterior direction towards the fibula or transversely (subcutaneously) in a proximal direction along the tibia.

Actions/Indications

- Spreads Liver Qi, regulates the Lower Burner, regulates Blood, eliminates Dampness

Special features

Xi-cleft point





Knee Joint XIGUAN **LIV-7**


1 cun
SP-9
LIV-7

Location

At the junction of the shaft and the medial condyle of the tibia, 1 cun posterior to ➞ **SP-9**.

How to find

The junction of the shaft and the medial condyle of the tibia can be easily palpated. There, locate ➞ **SP-9** and **LIV-7** 1 cun posterior to it. Both points tend to be sensitive to pressure if indicated.

Needling

Vertically 1–2 cun

Actions/Indications

- Opens the channel
- Expels Wind and Dampness


Medial condyle of the tibia
SP-9
Junction of the shaft and medial condyle of the tibia
Gastrocnemius


KID-10
Popliteal crease
LIV-8
1
Junction of the shaft and medial condyle of the tibia
SP-9
2
LIV7
3
4
SP-8
5
6
7
LIV-6
8
9
SP-7
LIV-5
10
KID-9
11
SP-6
12
KID-8
KID-7
13
14
KID-3
15 cun
Highest prominence of the medial malleolus
SP-5
SP-1
SP-4
KID-2

LIV-8 *Spring at the Crook* QUQUAN

Location

With the knee flexed, **LIV-8** is located directly proximal to the medial end of the popliteal crease, in a depression anterior to the tendons of the semitendinosus and semimembranosus muscles.

How to find

LIV-8 is best located with the patient's knee flexed and slight external rotation of the hip. First, palpate the prominent, ropey tendon of the semitendinosus muscle, which becomes more pronounced with the knee flexed. The tendon of the semimembranosus muscle lies deep to the semitendinosus and is often more difficult to isolate. With the palpating finger, glide from the tendon of the semitendinosus towards the patella. Approximately after 1 cun, you can feel a depression between the muscle bellies. **LIV-8** is located anterior to both tendons. Some authors locate **LIV-8** 1 cun superior and anterior to → **KID-10**. Sensitivity to pressure should determine the location.

→ **KID-10** is located approximately 1 cun in the direction of the popliteal crease and, from a medial perspective, posterior to the tendon of the semimembranosus and anterior to the tendon of the semitendinosus.

Needling

Vertically 0.5–1.5 cun

Actions/Indications

- Clears and eliminates Dampness and Damp-Heat from the Lower Burner (major action), benefits the genitals and the Uterus
- Nourishes Blood and Yin
- Moves Qi locally

Special features

he-sea point, Water point, tonification point.





Yin Wrapping YINBAO LIV-9


Sartorius
LIV-9
4 cun
LIV-8

Location

4 cun proximal to the medial condyle of the femur, between the sartorius and vastus medialis muscles. Alternative locations: 4 cun proximal to → **LIV-8** (for example, Deadman et al 1998, → photo), 4 cun proximal to the junction of the shaft and the condyle of the femur (for example, Hecker et al → see line drawing) or 4 cun proximal to the midpoint of the condyle of the femur (for example, Ogal and Stör 1999, → illustration on p. 443).

How to find

From → **LIV-8**, measure 4 cun in a proximal direction. There, locate **LIV-9** on the border between the more medial, narrow sartorius muscle and the anteromedial vastus medialis muscle. Sensitivity to pressure should determine the location of this point.

Needling

Vertically 1–2 cun

Actions/Indications

- Benefits the Lower Burner
- Opens the channel


Upper border of the pubic symphysis
18 cun
LIV-10
8 cun
SP-11
LIV-9
SP-10
2 cun
Upper border of the patella
KID-10
Popliteal crease
LIV-8
1
Junction tibial shaft/medial condyle of the tibia
SP-9
2
LIV-7
3
4

LIV-10 *Leg Five Miles* ZUWULI

Location

On the anterior aspect of the thigh, 3 cun inferior to the upper border of the symphysis, on the lateral border of the adductor longus muscle.

How to find

Ask the patient to flex their adductors by pressing their feet against each other. **LIV-10** is located in a groove on the medial border of the adductor longus muscle, where it forms an angle with the sartorius muscle.

Needling

Vertically 0.5–1.5 cun. Caution: Great saphenous vein, femoral artery/nerve.

Actions/Indications

- Relaxes the tendons and muscles
- Clears Damp-Heat from the Lower Burner
- Regulates the water passages


Midline
Upper border of the pubic symphysis
2 cun
3 cun
LIV-11
LIV-10
Sartorius


Upper border of the pubic symphysis
18 cun
LIV-10
8 cun
SP-11
LIV-9
2 cun
SP-10
Upper border of the patella
KID-10
Popliteal crease
LIV-8
1
2
SP-9
LIV-7
Junction tibial shaft/medial condyle of the tibia
3
4

Yin Corner YINLIAN LIV-11


Midline
Upper border of the pubic symphysis
2 cun
3 cun
LIV-11
LIV-10

Location

On the anterior aspect of the thigh, 2 cun inferior to the upper border of the symphysis and on the lateral border of the adductor longus muscle.

How to find

Ask the patient to flex their adductors by pressing their feet against each other. **LIV-11** is located 2 cun inferior to the upper border of the pubic symphysis, in a groove on the medial border of the adductor longus muscle.

LIV-11 is located approximately 1 cun inferior to where the femoral artery passes under the inguinal ligament.

Needling

Vertically 0.5–1.5 cun. Caution: Great saphenous vein, femoral artery/vein/nerve. Classical texts recommend moxibustion for female sterility.

Actions/Indications

- Relaxes the tendons
- Benefits the Uterus and regulates menstruation
- For disorders of the lumbar spine


ST-25
KID-16
SP-15
Ren-8
SP-14
ST-28
Ren-4
Ren-3
ST-30
SP-12
Ren-2
ST-31
KID-11
Highest prominence of the greater trochanter
Upper border of the pubic symphysis
1
2
LIV-11
3
LIV-10
4
5
6
7
8
9
10
19 cun
SP-11
11
ST-32
12
13

Ch04.12-F10028.qxd 2/23/08 11:32 AM Page 460

LIV-12 *Urgent Pulse* JIMAI

Location

In the inguinal groove, 2.5 cun lateral to the anterior midline and 1 cun inferior to the upper border of the symphysis.

How to find

From the upper border of the pubic symphysis, measure 2.5 cun in a lateral and 1 cun in an inferior direction. In this area, you can palpate the pulse of the femoral artery. **LIV-12** is located medial to the pulsating of the artery. As the femoral vein also runs medial to the artery, **LIV-12** should be needled in a medial direction, at least 1 fingerbreadth from the artery.

→ **ST-30** is located 1 cun superior and 0.5 cun medial to **LIV-12**.

Needling

Slightly obliquely 0.5–0.8 cun. Caution: Femoral artery/vein. The femoral vein is located medial to the artery and is approximately the breadth of a finger. To avoid injury to the vein, **LIV-12** should not be needled medial to the artery. Owing to its tricky location, classical texts recommend moxibustion only, while in modern texts moxibustion is contraindicated for the same reason.

Actions/Indications

- Dispels Cold from the Liver channel and benefits the Lower Burner


Midline
2 cun
Ren-2
Upper border of
the pubic symphysis
1 cun
LIV-12


ST-25
KID-16
SP-15
Ren-8
SP-14
ST-28
Ren-4
Ren-3
ST-30
SP-12
Ren-2
Highest
prominence
of the greater
trochanter
ST-31
KID-11
Upper border
of the pubic
symphysis
LIV-11
LIV-10
19 cun
SP-11
ST-32
1
2
3
4
5
6
7
8
9
10
11
12
13


Anterior superior
iliac spine
(ASIS)
Umbilicus
(Ren-8)
KID-15
Ren-6
G.B.-27
ST-28
Ren-2
Symphysis
ST-30
SP-12

Completion Gate ZHANGMEN LIV-13


Tip of the olecranon
resting on the free
end of the 11th rib
11th rib
LIV-13


Tip of the olecranon
resting on the free
end of the 11th rib


Umbilicus
1 cun
Ren-9
Ren-8

Location

Anterior and inferior to the free end of the 11th rib, approximately 1 cun superior to the umbilicus.

How to find

Quick method: Ask the patient to press their flexed elbow (90°) against the lateral aspect of the thorax and the tip of the olecranon will be pointing to the free end of the 11th rib. **LIV-13** can then be located on its anterior and inferior border. **Or:** Place the hand on the upper abdomen and, with gentle pressure, palpate along the lower border of the rib cage until you can feel the free end of the 11th rib just superior to the umbilicus. Locate **LIV-13** on its anterior and inferior border.

Located on approximately the same level (1 cun superior to the umbilicus) are ➞ **Ren-9** (on the midline) and ➞ **ST-24** (2 cun lateral to the midline). ➞ **G.B.-25** is located more laterally and inferiorly, at the free end of the 12th rib.

Needling

0.5–1 cun vertically or better obliquely in a lateral direction. Caution: Peritoneum, hypertrophied organs (right: liver, left: spleen).

Actions/Indications

- Harmonises the Liver and the Spleen, regulates Liver Qi (especially in the Middle and Lower Burner), strengthens the Spleen
- Opens the channel

Special features

Front-*mu* point of the Spleen, meeting point with the *dai mai* and the G.B. channel. *Hui*-meeting point of the *zang*-Organs.


16
24
18
17
17
18
22
15
LIV-14
G.B-24
12
16
22
18
Le 13
15
25
16
8
14
Sternocostal
8 angle
7
6
5
4
3
2
1
Umbilicus
1

LIV-14 *Cycle Gate* QIMEN

Location

In the 6th intercostal space, on the mamillary line or 4 cun lateral to the midline.

How to find

Quick method, especially in men: The nipple is generally located on the level of the 4th intercostal space. From there, palpate downward 2 intercostal spaces and locate **LIV-14** in the 6th intercostal space. **Or:** For more precise orientation on the ribcage (→ 3.5), palpate for the manubriosternal synchondrosis, a well-defined horizontal bony structure on the sternum. Lateral to it, locate the 2nd rib and below it the 2nd intercostal space. From there, count downward 4 intercostal spaces to the 6th intercostal space and there locate **LIV-14** on the mamillary line (4 cun lateral to the midline).

→ **G.B.-24** is located in the 7th intercostal space. Located on the same level (2 cun inferior to the sternocostal angle → 3.5) are → **Ren-14** (on the midline), → **KID-21** (0.5 cun lateral to the midline) and → **ST-19** (2 cun lateral to the midline).

Needling

0.5–1 cun obliquely, either in a lateral or medial (along the course of the ICS) direction. The latter is recommended for disorders of the breasts. Caution: Pneumothorax.

Actions/Indications

- Regulates Liver Qi and Liver Blood (especially in the Upper and Middle Burner), cools the Blood, disperses accumulations, harmonises the Liver and the Stomach

Special features

Front-*mu* point of the Liver, meeting point with the *yin wei mai* and the Spleen channel, exit point.


Manubriosternal synchondrosis
2nd rib
Mamillary line
2nd intercostal space
3rd intercostal space
4th intercostal space
5th intercostal space
6th intercostal space
LIV-14


Manubriosternal synchondrosis
2nd rib
2nd intercostal space
3
4
5
6


24
17
17
18
22
15
LIV-14
G.B-24
12
16
22
18
Le 13
15
25
16
8
14
Sternocostal angle
8
7
6
5
4
3
2
1
Umbilicus
1


6
7
G.B.-24 in the 7th intercostal space



5 The Eight Extraordinary Vessels (*qi jing ba mai*) with Points

Claudia Focks, Ulrich März

For an overview of the theoretical background of the eight extraordinary vessels → 1.7.

5.1 *Chong mai*

Synonym: Penetrating Vessel

Relationships (→ 1.7.3)

- **Yin/Yang:** *chong mai*/*dai mai*
- **Central/peripheral:** *chong mai*/*yin wei mai*. Regions supported by this pairing: Heart, thorax, Stomach. Opening point: SP-4 (*gongsun*), coupled point: P-6 (*neiguan*)

Pathway

The extraordinary vessel *chong mai* originates like the *du mai* and *ren mai* in the lower abdomen at *bao zhong* (in women in the Uterus) or, according to some authors, at the Kidneys. It crosses the genital area and divides into two branches:

➡ A **deep branch** reaches the perineum at → **Ren-1** (*huiyin*), travels to the spine, penetrates the spinal canal and ascends to the level of T1 and T2. (According to some authors the vessel ascends the anterior aspect of the spine.)

➡ The **other branch** emerges at → **ST-30** (*qichong*) to the surface of the body and divides into **two external branches**, one descending and one ascending branch:

- the **ascending** branch reaches → **KID-11** (*henggu*) 0.5 cun lateral to the midline at the level of the pubic symphysis and from there follows the KID channel to → **KID-21** (*youmen*). The KID channel initially ascends the abdomen at a distance of 0.5 cun from the midline, passing → **KID-12** (*dahe*), → **KID-13** (*qixue*), → **KID-14** (*siman*) and → **KID-15** (*zhongzhu*), runs to the midline, meeting → **Ren-7** (*yinjiao*) 1 cun inferior to the umbilicus, and again returns to its pathway 0.5 cun lateral to the midline, passing → **KID-16** (*huangshu*), → **KID-17** (*shangqu*), → **KID-18** (*shiguan*), → **KID-19** (*yindu*), → **KID-20** (*futonggu*) and → **KID-21** (*youmen*). The vessel then disperses into the intercostal spaces, ascends the neck, circles the inner surface of the lips and spreads in the upper pharynx and the nasal cavities.



- the **descending branch** meets the Kidney primary channel and descends the medial aspect of the thigh (according to the *Ling Shu* it divides into the three foot Yin channels), penetrates the popliteal fossa, follows the medial border of the tibia and emerges posterior to the medial malleolus, where it divides into two sub-branches: one branch travels along the anteromedial aspect of the foot to the big toe, the other branch reaches the sole of the foot.



Ren-1 (*huiyin*): In the centre of the perineum.


SP-13
Upper border of the pubic symphysis
0.7 cun
ST-30
SP-12
Symphysis

ST-30 (*qichong*): 2 cun lateral to the upper border of the pubic symphysis, medial to the femoral artery; at the level of Ren-2


KID-12
Ren-03
KID-11
Ren-02
Upper border of the pubic symphysis

KID-11 (*henggu*): On the upper border of the pubic symphysis, 0.5 cun lateral to the anterior midline


KID-12
Ren-03
KID-11
Ren-02
Upper border of the pubic symphysis

KID-12 (*dahe*): 1 cun superior to the upper border of the pubic symphysis, 0.5 cun lateral to the anterior midline


5 cun
KID-13
Ren-04
KID-12
Ren-03

KID-13 (*qixue*): 2 cun superior to the upper border of the pubic symphysis, 0.5 cun lateral to the anterior midline


KID-14
Ren-05
5 cun
KID-13
Ren-04

KID-14 (*siman*): 2 cun inferior to the umbilicus, 0.5 cun lateral to the anterior midline


KID-16
Umbilicus
Ren-08
KID-15
Ren-07
Ren-06

KID-15 (*zhongzhu*): 1 cun inferior to the umbilicus, 0.5 cun lateral to the anterior midline


Ren-8
Umbilicus
1 cun
Ren-7

Ren-7 (*yinjiao*): On the anterior midline, 1 cun inferior to the umbilicus


0.5
KID-16
Umbilicus
Ren-08

KID-16 (*huangshu*): 0.5 cun lateral to the centre of the umbilicus


KID-18
Ren-11
KID-17
Ren-10
2 cun
0,5 cun
Umbilicus

KID-17 (*shangqu*): 2 cun superior to the umbilicus, 0.5 cun lateral to the anterior midline


KID-18
Ren-11
KID-17
Ren-10
3 cun
0.5 cun
Umbilicus

KID-18 (*shiguan*): 3 cun superior to the umbilicus, 0.5 cun lateral to the anterior midline


KID-19
Ren-12
8 cun
KID-18
Ren-11
KID-17
Ren-10
4 cun

KID-19 (*yindu*): Midway between the sternocostal angle and the centre of the umbilicus, 0.5 cun lateral to the anterior midline



KID-20 (*futonggu*): 5 cun superior to the umbilicus or 3 cun inferior to the sternocostal angle, 0.5 cun lateral to the anterior midline



KID-21 (*youmen*): 2 cun inferior to the sternocostal angle, 0.5 cun lateral to the anterior midline

Connections with other channels and organs

- Kidney primary channel, *ren mai*, *du mai*, Stomach and Liver primary channels
- Kidney, Uterus

Clinical importance (→ 1.7.2, 1.7.3)

- **Sea of Blood**, strong connection to the various functions of the Blood
- Strong relationship to the Uterus, regulates the menses
- Regulates the 12 primary channels, effectively regulates the circulation of the Blood (*xue*) in the whole body
- Regulates counterflow Qi
- Connects the Stomach and Kidney primary channels and strengthens the relationship between the *ren mai* and *du mai*

5.2 *Ren mai*

Synonym: Conception Vessel

Relationships (→ 1.7.3)

- **Yin/Yang:** *ren mai*/*du mai*
- **Central/peripheral:** *ren mai*/*yin qiao mai*. Regions supported by this pairing: face, throat, thorax, Lungs, diaphragm, abdomen. Opening point: **LU-7** (*lieque*); coupled point: **KID-6** (*zhaohai*)

Pathway

The extraordinary vessel *ren mai* originates like the *chong mai* and *du mai* in the lower abdomen (*bao zhong*) or, according to some authors, at the Kidneys, connects with the urogenital area and emerges at the perineum at **Ren-1** (*huiyin*). From there the **external** pathway ascends the anterior midline, passing the abdomen, the chest, and the throat. It terminates on the chin in the mentolabial groove at **Ren-24** (*chengjiang*), where it meets the Stomach primary channel and the extraordinary vessel *du mai*. From here the vessel continues internally, encircles the inner surface of the lips and connects with the *du mai* at → **Du-28** (*yinjiao*) beneath the upper frenulum. It divides into **two branches**, which both reach the infraorbital ridge at → **ST-1** (*chengqi*), where they cross the Stomach primary channel as well as the extraordinary vessel *yin qiao mai*, and terminate near the eyes.

- **An internal branch** runs from the perineum to the spine, penetrates the spinal canal at **Du-1** (*changqiang*) and ascends in the spine.



Meeting Points of other channels with the *ren mai*



Du-28 (*yinjiao*): On the inside of the upper lip, at the junction of the frenulum and the upper gum



ST-1 (*chengqi*): With the eyes looking straight ahead, directly below the centre of the pupil, between the eyeball and the infraorbital ridge



Du-1 (*changqiang*): On the midline, midway between the tip of the coccyx and the anus

Connections with other channels and organ systems

- *Du mai*, *chong mai*, Kidney and Stomach primary channels
- Uterus, Kidney

Clinical importance (→ 1.7.2, 1.7.3)

- **Sea of the Yin Qi**, regulates and circulates the Yin Qi (including the Blood, Essence (*jing*) and body fluids) in order to nourish and moisten the body
- Connects all Yin channels, especially those of the lower abdomen
- Controls the anterior thoracic region and the abdomen
- Close relationship to the functions of the abdominal organs, particularly the Kidney, Bladder, Uterus and Lung
- Regulates reproduction
- Stores the Essence Qi (*jing qi*) overflowing from the Yin channels
- Absorbs excess from the Yin channels, especially stagnant Qi and Blood

Notes about the *ren mai*

Both the *ren mai* and *du mai* have a unique position among the eight extraordinary vessels. They are the only two extraordinary vessels with their own specific points – all other extraordinary vessels can only be accessed through points on the primary channels. For this reason the *ren mai* and the *du mai* together with the primary channels are often categorised as 14 channels. However, from the point of view of channel energetics this is not correct, since the extraordinarily vessels occupy a special position, both evolutionary as well as functionally (→ 1.7).

The pathway of the *ren mai*, like that of the *du mai*, is limited to the torso and the head. While it does not course along the extremities and does not have any points on the limbs (neither general points nor specific points such as the five *shu*-transporting points, *yuan*-source point, etc.) it does have an opening point (or Master point) (→ 8.1.8). The *ren mai* is also referred to as the Sea of Yin and governs the Yin in the whole body. Along its pathway are located the anterior aspects of the energy centres (or chakras according to Yogi tradition). Daoist tradition describes three energy centres, the three cinnabar fields (*dantian*) on the anterior aspect of the body, which play an important role in *Qigong* practice as centres where the Qi pools and originates. While all three centres are located on the pathway of the *ren mai*, they do not correspond to specific points but rather to certain areas.

The *ren mai* runs along the Yin side of the body. It contains not only several Front-*mu* points acting directly on the *zangfu*-Organs, but also multiple meeting points with other channels. This clearly denotes the outstanding importance of the *ren mai*.

Specific points according to their function

- ***Yuan*-Source point (→ 8.1.1): –**
- ***Luo*-Connecting point (→ 8.1.2.): Ren-15** (*jiuwei*) 🟦■
- ***Xi*-Cleft point (→ 8.1.3): –**
- **Associated Back-*shu* point (→ 8.1.4): –**
- **Associated Front-*mu* point (→ 8.1.5): –**
- **Five *shu*-transporting points (→ 8.1.6): –**
- **Hui-meeting point (→ 8.1.7)**
  - of the Qi: **Ren-17** (*danzhong*) 🟦🟦
  - of the *fu*-Organs: **Ren-12** (*zhongwan*) 🟦■
- **Pertaining opening point (→ 8.1.8): LU-7** (*lieque*)
- **Pertaining coupled point (→ 8.1.8): KID-6** (*zhaohai*)
- **Lower *he*-Sea point (→ 8.1.9): –**
- ***Jiaohui*-meeting points (→ 8.1.10):**
  - with the *chong mai* and the *du mai*: **Ren-1** (*huiyin*)
  - with the LIV channel: **Ren-2** (*qugu*) 🟦■
  - with the SP, LIV, KID channels: **Ren-3** (*zhongji*) 🟦🟦, **Ren-4** (*guanyuan*) 🟦🟦
  - with the *chong mai* and the KID channel*: **Ren-7** (*yinjiao*)
  - with the SP and ST* channels: **Ren-10** (*xiawan*)
  - with the S.I., T.B.* and ST channels: **Ren-12** (*zhongwan*) 🟦🟦
  - with the ST and S.I. channels: **Ren-13** (*shangwan*)
  - with the SP*, KID, S.I.* and T.B. channels: **Ren-17** (*danzhong*) 🟦🟦
  - with the *yin wei mai*: **Ren-22** (*tiantu*) 🟦🟦, **Ren-23** (*lianquan*)

---

* Mentioned by only some authors

–468 with the *du mai*, the L.I. and ST channels: **Ren-24** (*chengjiang*) 🟦■
  - of other channels with the *ren mai*: **Du-28, ST-1, Du-1**
- **Gao Wu command point (→ 8.1.11):** –
- **Window of Heaven point (→ 8.1.12): Ren-22** (*tiantu*) 🟦🟦
- **Points of the Four Seas (→ 8.1.13) Qi: Ren-17** (*danzhong*) 🟦🟦
- **Ma Dan Yang Heavenly Star point (→ 8.1.14):** –
- **Sun Si Miao Ghost points (→ 8.1.15): Ren-1** (*huiyin*), **Ren-24** (*chengjiang*) 🟦■
- **Other functional points:**
  - Front-*mu* point of the Bladder: **Ren-3** (*zhongji*) 🟦🟦
  - Front-*mu* point of the Small Intestine: **Ren-4** (*guanyuan*) 🟦🟦
  - Front-*mu* point of the Triple Burner: **Ren-5** (*shimen*)
  - important, general tonification point: **Ren-6** (*qihai*) 🟦🟦
  - Front-*mu* point of the Stomach: **Ren-12** (*zhongwan*) 🟦🟦
  - Front-*mu* point of the Heart: **Ren-14** (*juque*) 🟦🟦
  - important calming point: **Ren-15** (*jiuwei*) 🟦■
  - Front-*mu* point of the Pericardium, point of the Sea of Qi: **Ren-17** (*danzhong*) 🟦🟦

Points according to region

- **Local points (→ 8.2.1):** throat – **Ren-23** (*lianquan*); Lungs – **Ren-22** (*tiantu*) 🟦🟦, **Ren-17** (*danzhong*) 🟦🟦; Heart – **Ren-17** (*danzhong*) 🟦🟦; Spleen/Stomach – **Ren-12** (*zhongwan*) 🟦🟦; Small Intestine – **Ren-4** (*guanyuan*) 🟦🟦, **Ren-9** (*shuifen*); Bladder – **Ren-3** (*zhongji*) 🟦🟦; urogenital region – **Ren-3** (*zhongji*), **Ren-4** (*guanyuan*) 🟦🟦; epigastrium – **Ren-12** (*zhongwan*) 🟦🟦, **Ren-13** (*shangwan*); abdomen – **Ren-3** (*zhongji*) 🟦🟦, **Ren-4** (*guanyuan*) 🟦🟦, **Ren-6** (*qihai*) 🟦🟦
- **Adjacent points (→ 8.2.1):** throat – **Ren-22** (*tiantu*) 🟦🟦; tongue – **Ren-23** (*lianquan*); Heart – **Ren-14** (*juque*) 🟦🟦; Gall Bladder – **Ren-11** (*jianli*); Kidney – **Ren-4** (*guanyuan*) 🟦🟦; epigastrium – **Ren-8** (*shenque*)
- **Distal points (→ 8.2.1):** –

Specific points according to the vessel pathway (in numerical order)

- **Ren-1** (*huiyin*): *jiaohui*-meeting point with the *chong mai* and *du mai* (→ 8.1.10); Sun Si Miao Ghost point (→ 8.1.15)
- **Ren-2** (*qugu*) 🟦■: *jiaohui*-meeting point with the LIV channel (→ 8.1.10)
- **Ren-3** (*zhongji*) 🟦🟦: *jiaohui*-meeting point with the SP, LIV, KID channels (→ 8.1.10); Front-*mu* point of the Bladder; local point for the Bladder, urogenital region and lower abdomen (→ 8.2.1)
- **Ren-4** (*guanyuan*) 🟦🟦: Front-*mu* point of the Small Intestine (→ 8.1.5); *jiaohui*-meeting point with the SP, LIV, KID channels (→ 8.1.10); local point for the Small Intestine, urogenital region and lower abdomen (→ 8.2.1); adjacent point for the Kidneys
- **Ren-5** (*shimen*): Front-*mu* point of the Triple Burner
- **Ren-6** (*qihai*) 🟦🟦: important general tonification point; local point for the lower abdomen (→ 8.2.1); adjacent point for the Lung (→ 8.2.1)
- **Ren-7** (*yinjiao*): *jiaohui*-meeting point with the *chong mai* and the KID channel (→ 8.1.10)
- **Ren-8** (*shenque*): adjacent point for the epigastrium (→ 8.2.1)
- **Ren-9** (*shuifen*): local point for the Small Intestine (→ 8.2.1)
- **Ren-10** (*xiawan*): *jiaohui*-meeting point with the SP and ST* channels (→ 8.1.10)
- **Ren-11** (*jianli*): adjacent point for the Gall Bladder (→ 8.2.1)
- **Ren-12** (*zhongwan*) 🟦🟦: *hui*-meeting point (→ 8.1.7) of the *fu*-Organs; *jiaohui*-meeting point with the S.I., T.B.* and ST channels (→ 8.1.10); Front-*mu* point of the Stomach (→ 8.1.5); local point for the SP/ST and the epigastrium (→ 8.2.1)
- **Ren-13** (*shangwan*): *jiaohui*-meeting point with the ST and S.I. channels (→ 8.1.10); local point for the epigastrium (→ 8.2.1)
- **Ren-14** (*juque*) 🟦🟦: Front-*mu* point of the Heart (→ 8.1.5); adjacent point for the Heart
- **Ren-15** (*jiuwei*) 🟦■: *luo*-connecting point (→ 8.1.2); important point for calming
- **Ren-17** (*danzhong*) 🟦🟦: *hui*-meeting point (→ 8.1.7) of the Qi; *jiaohui*-meeting point with the SP, KID, S.I. and T.B. channels (→ 8.1.10); Front-*mu* point of the Pericardium, point of the Sea of Qi; local point for the Lung and Heart (→ 8.2.1)
- **Ren-22** (*tiantu*) 🟦🟦: *jiaohui*-meeting point with the *yin wei mai* (→ 8.1.10); Window of Heaven point (→ 8.1.12); local point for the Lungs (→ 8.2.1); adjacent point for the throat (→ 8.2.1)
- **Ren-23** (*lianquan*): *jiaohui*-meeting point with the *yin wei mai* (→ 8.1.10); local point for the throat (→ 8.2.1); adjacent point for the tongue (→ 8.2.1)
- **Ren-24** (*chengjiang*) 🟦■: *jiaohui*-meeting point with the *du mai*, the L.I. and ST channels (→ 8.1.10); Sun Si Miao Ghost point

---

* Mentioned by only some authors



Luo-Connecting Vessel of the *Ren Mai* (→ 1.6)

Pathway

The *luo*-connecting vessel of the *ren mai* originates at **Ren-15** (*jiuwei*), below the xiphoid process (→ 3) and disperses over the skin of the abdomen.

Clinical importance

Pathology

Excess (*shi*): pain of the abdominal skin
Deficiency (*xu*): itching of the abdominal skin

Meeting of the Yin HUIYIN Ren-1





Location

In the centre of the perineum.

How to find

In women: midway between the anus and the posterior labial commissure. In men: midway between the anus and the scrotum.

Needling

Vertically 0.5–1 cun. Caution: Contraindicated during pregnancy. Some classic texts prohibit needling this point. Particular attention should be paid to the prevention of infection.

Actions/Indications

- Clears Heat, strengthens the Kidneys and drains Dampness
- Regulates menstruation

Special features

Meeting point with the *du mai* and the *chong mai*. As a Sun Si Miao Ghost point, **Ren-1** is traditionally indicated for treating epilepsy and psychoses.

Ren-2 *Curved Bone* QUGU

Location

On the anterior midline, on the upper border of the pubic symphysis.

How to find

In the pubic area, locate the upper border of the pubic symphysis. **Ren-2** is located directly superior to its upper border, on the anterior midline.

Located on the same level are → **KID-11** (0.5 cun lateral to the midline), → **ST-30** (2 cun lateral to the midline) and → **SP-12** (3.5 cun lateral to the midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum. Also caution with a full bladder and during pregnancy.

Actions/Indications

- Benefits urination, warms the Yang and strengthens the Kidneys
- Regulates the Lower Burner

Special features

Meeting point with the LIV channel


Midline
Ren-2
Upper border of the pubic symphysis


Anterior superior iliac spine (ASIS)
Umbilicus (Ren-8)
KID-15
Ren-6
G.B.-27
ST-28
Ren-2
Symphysis
ST-30
SP-12


L4
Anterior superior iliac spine (ASIS)
Sacroiliac joint
Greater trochanter
Symphysis pubis, interpubic disc


KID-12
Ren-03
KID-11
Ren-02
Upper border of the pubic symphysis

Middle Pole ZHONGJI **Ren-3**


Ren-8
Umbilicus
4 cun
Ren-3
Ren-2
1 cun
Upper border of
the pubic symphysis


Ren-3
Upper border
of the pubic
symphysis


15
25
16
8
14
6
27
14
4
29
12
13
SP-12
ST-30
KID-11
Ren-2
Umbilicus
1
2
3
4
Upper border
of the pubic
symphysis

Location

On the anterior midline, 1 cun superior to the upper border of the pubic symphysis or 4 cun inferior to the umbilicus.

How to find

The distance between the centre of the umbilicus and the upper border of the pubic symphysis is divided into 5 cun. As these can vary considerably from the patient's finger cun, only proportional cun measurements should be used here (helpful device: elastic tape → 2.3.1). Locate **Ren-3** on the midline, 1 cun superior to the midpoint of the upper border of the pubic symphysis.

Located on the same level are → **KID-12** (0.5 cun lateral to the midline) and → **ST-29** (2 cun lateral to the midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, bladder. Contraindicated during pregnancy. Ask the patient to void their bladder before needling.

Actions/Indications

- Benefits the Bladder, drains Dampness and Damp-Heat, dispels stagnation, benefits the Lower Burner
- Regulates menstruation
- Strengthens the Kidneys (→ **Ren-4** is more commonly used for this purpose)

Special features

Front-*mu* point of the Bladder, meeting point with the LIV, KID and SP channels. Important point for disorders of the urogenital tract, with its main action on the Bladder (especially for acute cases).


KID-12
Ren-03
KID-11
Ren-02
Upper border
of the pubic
symphysis


ST-29
1 cun
ST-30
Upper border of the
pubic symphysis

Ren-4 *Gate of the Source* GUANYUAN

Location

On the anterior midline, 2 cun superior to the upper border of the pubic symphysis or 3 cun inferior to the umbilicus.

How to find

The distance between the centre of the umbilicus and the upper border of the pubic symphysis is divided into 5 cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun measurements should be used here (helpful device: elastic tape → 2.3.1). **Ren-4** is located on the midline, either 2 cun superior to the midpoint of the upper border of the pubic symphysis or 3 cun inferior to the umbilicus.

Located on the same level are → **KID-13** (0.5 cun lateral to the midline), → **ST-28** (2 cun lateral to the midline) and three extra points → **Ex-CA** (*yijing*: 1 cun lateral to the midline; *qimen*: 3 cun lateral to the midline; *tituo*: 4 cun lateral to the midline). Also located on approximately this level is → **G.B.-27** (medial to the ASIS).

Needling

Vertically 0.5–1.2 cun. Caution: Peritoneum. Needling contraindicated during pregnancy.

Actions/Indications

- Tonifies the Original Qi (*yuan qi*), benefits the Essence (*jing*), strengthens and nourishes the Kidneys as well as the Blood and Yin
- Eliminates Cold and Dampness from the Lower Burner (especially with moxibustion)

Special features

Front-*mu* point of the Small Intestine, meeting point with the SP, KID and LIV channels. Important point for tonification. Major point for urogenital disorders (especially gynaecological disorders).


Ren-8
Umbilicus
3 cun
Ren-4
2 cun
Ren-2
Upper border of the pubic symphysis


5 cun
KID-13
Ren-04
KID-12
Ren-03


tituo
qimen
yijing
Ren-4
1 cun
2 cun
3 cun
Ren-2


Anterior superior iliac spine (ASIS)
Umbilicus (Ren-8)
KID-15
Ren-6
G.B.-27
ST-28
Ren-2
ST-30
SP-12
Symphysis

Stone Gate SHIMEN Ren-5


Ren-8
Umbilicus
2 cun
Ren-5
3 cun
Ren-2
Upper border of the pubic symphysis


Umbilicus
Upper border of the pubic symphysis


15
25
16
8
14
6
27
14
4
29
12
13
SP-12
ST-30
KID-11
Ren-2
Umbilicus
1
2
3
4
Upper border of the pubic symphysis

Location

On the anterior midline, 2 cun inferior to the umbilicus or 3 cun superior to the upper border of the pubic symphysis.

How to find

The distance between the centre of the umbilicus and the upper border of the pubic symphysis is divided into 5 cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun measurements should be used here (helpful device: elastic tape ➞ 2.3.1). **Ren-5** is located on the midline, 2 cun inferior to the umbilicus. Located on the same level are ➞ **KID-14** (0.5 cun lateral to the midline) and ➞ **ST-27** (2 cun lateral to the midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Moves and benefits the water passages
- Regulates the Qi and Blood in the Lower Burner
- Regulates the Uterus

Special features

Front-*mu* point of the Triple Burner. Some classic texts warn that needling this point in women can lead to infertility (hence the name: infertile women were referred to as 'stone women'). There are no such warnings in modern texts.


KID-14
Ren-05
5 cun
KID-13
Ren-04



Ren-6 *Sea of Qi* QIHAI

Location

On the anterior midline, 1.5 cun inferior to the umbilicus or 3.5 cun superior to the upper border of the pubic symphysis.

How to find

The distance between the centre of the umbilicus and the upper border of the pubic symphysis is divided into 5 cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun measurements should be used here (helpful device: elastic tape → 2.3.1). **Ren-6** is located on the midline, 1.5 cun inferior to the umbilicus or 3.5 cun superior to the upper border of the pubic symphysis.

Needling

Vertically 0.8–1.5 cun. Caution: Peritoneum, pregnancy. According to some authors, this point should never be needled with strong reducing techniques owing to its strong Qi tonifying action. Moxibustion and cupping are recommended for this point.

Actions/Indications

- Tonifies the Original Qi (*yuan qi*) as well as Qi in general, strengthens the Kidneys (especially Kidney Yang), regulates Qi, harmonises Blood and eliminates Dampness

Special features

Important tonification point for mental and physical exhaustion, strengthens especially the Qi and Yang with moxibustion. One of the most important acupuncture points.


Ren-8
Umbilicus
1.5 cun
Ren-6
3.5 cun
Ren-2
Upper border of the pubic symphysis


Ren-6
Upper border of the pubic symphysis


15
25
16
8
14
6
27
14
4
29
12
13
SP-12
ST-30
KID-11
Ren-2
Umbilicus
1
2
3
4
Upper border of the pubic symphysis

Yin Intersection YINJIAO **Ren-7**

Location

On the anterior midline, 1 cun inferior to the umbilicus.

How to find

The distance between the centre of the umbilicus and the upper border of the pubic symphysis is divided into 5 cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun measurements should be used here (helpful device: elastic tape → 2.3.1). **Ren-7** is located on the midline, 1 cun inferior to the umbilicus.

Located on the same level are → **KID-15** (0.5 cun lateral to the midline) and → **ST-26** (2 cun lateral to the midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Regulates menstruation
- Regulates the Qi flow in the abdomen and the genital area

Special features

Meeting point with the *chong mai* and the KID channel


Ren-8
Umbilicus
1 cun
Ren-7
5 cun
Ren-2
Upper border of the pubic symphysis


Umbilicus
Upper border of the pubic symphysis


KID-16
Umbilicus
Ren-08
KID-15
Ren-07
Ren-06


2 cun
ST-25
1 cun
ST-26

Ren-8 *Spirit Gateway* SHENQUE



Location

In the centre of the umbilicus.

How to find

Located on the same level are → **KID-16** (0.5 cun lateral to the midline), → **ST-25** (2 cun lateral to the midline), → **SP-15** (4 cun lateral to the midline) as well as → **G.B.-26** (on a vertical line through the free end of the 11th rib).

Needling

Needling contraindicated. Only indirect moxibustion (on salt or ginger, moxa pole, moxa box).

Actions/Indications

- Warms and stabilises the Yang and the Intestines


2 cun
4 cun
ST-25
SP-15


11th rib
G.B.-26


15
25
16
8
14
6
27
14
4
29
12
13
SP-12
ST-30
KID-11
Ren-2
Umbilicus
1
2
3
4
Upper border of the pubic symphysis


0.5
KID-16
Ren-08
Umbilicus



Water Separation SHUIFEN Ren-9


Sterno-
costal
angle
8 cun
1 cun
Ren-9
Umbilicus
Ren-8

Location

On the anterior midline, 1 cun superior to the umbilicus.

How to find

The distance between the sternocostal angle (→ 3.5) and the centre of the umbilicus is divided into 8 cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun measurements should be applied here (helpful device: elastic tape → 2.3.1). From the centre of the umbilicus, measure 1 cun in a superior direction and there locate **Ren-9** on the anterior midline.

Located on the same level is → **ST-24** (2 cun lateral to the midline). → **LIV-13** is also located on approximately this level (at the free end of the 11th rib).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy

Actions/Indications

- Eliminates water accumulations, drains Dampness and controls the water passages Regulates the Intestines and disperses accumulations
- Delayed closure of the fontanelles


Sternocostal
angle
Umbilicus


19
16
24
18
17
17
18
22
15
LIV-14
G.B.-24
12
16
22
18
LIV-13
15
25
16
8
8
Sterno-
costal
angle
7
6
5
4
3
2
1
Umbilicus
1



Ch05a-F10028.qxd 2/22/08 9:44 PM Page 480

Ren-10 *Lower Cavity* XIAWAN


Sterno-
costal
angle
8 cun
Ren-10
2 cun
Umbilicus

Location

On the anterior midline, 2 cun superior to the centre of the umbilicus.

How to find

The distance between the sternocostal angle (→ 3.5) and the centre of the umbilicus is divided into 8 cun, which can vary considerably from the patient's finger cun. Therefore only proportional cun measurements should be applied here (helpful device: elastic tape → 2.3.1). From the centre of the umbilicus, measure 2 cun in a superior direction and there locate **Ren-10** on the anterior midline.

Located on the same level are → **KID-17** (0.5 cun lateral to the midline), → **ST-23** (2 cun lateral to the midline) and **Ex-CA** (*weishang*; 4 cun lateral to the midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Tonifies and regulates the Spleen and Stomach Qi, dispels food stagnation

Special features

Meeting point with the SP channel and according to some authors with the ST channel. According to some classical texts, this point is contraindicated during pregnancy (for both needling and moxibustion).


weishang
Ren-10
2 cun
SP-15


19
16
24
18
17
17
18
22
15
LIV-14
G.B.-24
12
16
22
18
LIV-13
15
25
16
8
Sterno-
costal
angle
8
7
6
5
4
3
2
1
Umbilicus
1


KID-18
Ren-11
KID-17
Ren-10
3 cun
0.5 cun
Umbilicus



Interior Strengthening JIANLI **Ren-11**


Sterno-
costal
angle
8 cun
Ren-11
3 cun
Umbilicus


Sternocostal
angle
Umbilicus

Location

On the anterior midline, 3 cun superior to the umbilicus.

How to find

The distance between the sternocostal angle (→ 3.5) and the centre of the umbilicus is divided into 8 cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun measurements should be applied here (helpful device: elastic tape → 2.3.1). From the centre of the umbilicus, measure 3 cun in a superior direction and there locate **Ren-11** on the anterior midline. Located on the same level are → **KID-18** (0.5 cun lateral to the midline), → **ST-22** (2 cun lateral to the midline) and → **SP-16** (4 cun lateral to the midline).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Harmonises the Middle Burner, regulates the Qi flow


KID-18
KID-17
Ren-11
Ren-10
3 cun
0.5 cun
Umbilicus




SP-16
4 cun
3 cun
SP-15

Ren-12 *Middle Cavity* ZHONGWAN

Location

On the anterior midline, 4 cun superior to the umbilicus or 4 cun inferior to the sternocostal angle.

How to find

The distance between the sternocostal angle (➞ 3.5) and the centre of the umbilicus can be divided into 8 cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun measurements should be applied here (helpful device: elastic tape ➞ 2.3.1). From the centre of the umbilicus, measure either 4 cun in a superior direction or from the sternocostal angle 4 cun in an inferior direction. There, locate **Ren-12** on the anterior midline. **Or:** Spreading hands technique (➞ 2.3.3): Place the little fingers on the sternocostal angle and the centre of the umbilicus respectively and determine the midpoint (=**Ren-12**) of this distance by joining the index fingers. Located on the same level are ➞ **KID-19** (0.5 cun lateral to the midline) and ➞ **ST-21** (2 cun lateral to the midline).

Needling

0.8–1.5 cun vertically or obliquely towards surrounding points (➞ **ST-21**, **Ren-10**, **Ren-15**). Caution: Peritoneum, pregnancy. If indicated, moxa is recommended.

Actions/Indications

- Harmonises and tonifies the Middle Burner, descends counterflow Qi, regulates the Qi flow and alleviates pain, transforms Dampness

Special features

Front-*mu* point of the stomach, meeting point with the S.I., T.B.* and ST channels, *hui*-meeting point of the *fu*-Organs. Major point for (functional) stomach disorders.


Sternocostal angle
4 cun
Ren-12
4 cun


19
16
24
18
17
17
18
22
15
LIV-14
G.B.-24
12
16
22
18
LIV-13
15
25
16
8
Sterno-costal angle
8
7
6
5
4
3
2
1
Umbilicus
1


Sternocostal angle
Ren-12


Sternocostal angle
Ren-12
Umbilicus


KID-19
Ren-12
8 cun
KID-18
Ren-11
KID-17
Ren-10
4 cun


1/2
ST-21
Ren-12

---

* Mentioned by only some authors

Upper Cavity SHANGWAN **Ren-13**


Sterno-
costal
angle
3 cun
Ren-13
8 cun
Umbilicus

Location

On the anterior midline, 3 cun inferior to the sternocostal angle.

How to find

The distance between the sternocostal angle (➞ 3.5) and the centre of the umbilicus is divided into 8 cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun measurements should be applied here (helpful device: elastic tape ➞ 2.3.1). From the sternocostal angle, measure 3 cun in an inferior direction and there locate **Ren-13** on the anterior midline.

Located on the same level are ➞ **KID-20** (0.5 cun lateral to the midline), ➞ **ST-20** (2 cun lateral to the midline) and ➞ **G.B.-24** (approximately on this level, in the 7th intercostal space, on the mamillary line).

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Regulates the Stomach and counterflow Qi
- Regulates the Heart

Special features

Meeting point with the ST and S.I. channel


Sternocostal
angle
Umbilicus


KID-20
KID-19
KID-18
KID-17
Ren-13
Ren-12
Ren-11
Ren-10
5 cun
8 cun


3 cun
ST-19
ST-20


6
7
G.B.-24
in the 7th
intercostal space

Ren-14 *Great Gateway* JUQUE

Location

On the anterior midline, 2 cun inferior to the sternocostal angle or 6 cun superior to the umbilicus.

How to find

The distance between the sternocostal angle (→ 3.5) and the centre of the umbilicus is divided into 8 cun (note: these are proportional cun → 2.2). **Ren-14** is located on the midline, 2 cun inferior to the sternocostal angle or 6 cun superior to the umbilicus. **Or:** Use spreading hands technique (→ Chapter 2): Place the little fingers on the sternocostal angle and the umbilicus respectively and determine the midpoint of this distance (→ **Ren-12**). Then locate **Ren-14** on the midpoint of the distance between → **Ren-12** and the sternocostal angle.
Located on the same level are → **KID-21** (0.5 cun lateral to the midline), → **ST-19** (2 cun lateral to the midline) and → **LIV-14** (approximately on this level, in the 6th intercostal space, on the mamillary line).

Needling

0.3–0.8 cun vertically or often obliquely in an inferior direction or up to 1.5 cun transversely (subcutaneously). Depending on individual anatomy, this point can be located on the xiphoid process. Caution: Peritoneum, injury to hypertrophied organs (left: heart, right: liver) depending on the thickness of the abdominal wall.

Actions/Indications

- Regulates the Heart, disperses stagnant Phlegm, alleviates pain, unbinds the thorax, descends the Qi
- Harmonises the Stomach, descends Stomach Qi
- Transforms Phlegm, calms the *shen*

Special features

Front-*mu* point of the Heart. Major local point for thoracic pain caused by Blood stasis or Phlegm blockages.


Sternocostal angle
2 cun
Ren-14
6 cun


Sternocostal angle
Ren-14


19
16
24
18
17
17
18
22
15
LIV-14
G.B.-24
12
16
22
18
LIV-13
15
25
16
8
Sterno-costal angle
8
7
6
5
4
3
2
1
Umbilicus
1


2 cun
KID-21
Ren-14

Turtledove Tail JIUWEI **Ren-15**


Sternocostal angle
1 cun
Ren-15
7 cun


Sternocostal angle
Ren-15

Location

On the anterior midline, 1 cun inferior to the sternocostal angle or 7 cun superior to the umbilicus.

How to find

The distance between the sternocostal angle (→ 3.5) and the centre of the umbilicus is divided into 8 cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun measurements should be applied here (helpful device: elastic tape → 2.3.1). From the sternocostal angle, measure 1 cun in an inferior direction and there locate **Ren-15** on the anterior midline. It is often located directly below or, depending on individual anatomy, on the xiphoid process.

Needling

0.5–1 cun obliquely in an inferior direction. The patient should be in an extended position. Caution: Possible injury to organs with deep needling or oblique insertion in a superior direction, especially in patients with hypertrophied organs (left: Liver, right: Heart). According to some classical texts, moxibustion is contraindicated.

Actions/Indications

- Regulates the Heart, calms the *shen*
- Descends counterflow lung and stomach Qi, unbinds the chest
- Regulates the *luo*-connecting vessel of the *ren mai*

Special features

Luo-connecting point of the *ren mai*. Important point for calming.


Manubriosternal synchondrosis
Coracoid process
2nd rib
Sternocostal angle
Xiphoid process
11th rib
Free end of the 12th rib
Free end of the 11th rib

Ren-16 *Central Courtyard* ZHONGTING

Location

On the anterior midline, on the level of the sternocostal angle.

How to find

Ren-16 is located on the level of the sternocostal angle, where the two lower borders of the ribcage (→ 3.5) meet. To locate this point, palpate upward along the lower borders of the ribcage with one hand on either side until the palpating fingers meet at the sternocostal angle. Here, locate **Ren-16** in a shallow depression between the sternum and the xiphoid process.

Located on the same level (approximately the 5th intercostal space) are → **KID-22** (2 cun lateral to the midline), → **ST-18** (4 cun lateral to the midline) and → **SP-17** (6 cun lateral to the midline).

Needling

0.5 cun transversely (subcutaneously) in a superior or inferior direction. Caution: Danger of heart injury in patients with a split xiphoid process or a sternal foramen. Therefore, only transverse needling is recommended.

Actions/Indications

- Unbinds the chest
- Regulates the Stomach and counterflow Stomach Qi


Sterno-
costal
angle
Ren-16


Manubriosternal synchondrosis
2nd rib
Coracoid process
Sternocostal angle
Xiphoid process
11th rib
Free end of the 12th rib
Free end of the 11th rib


19
16
24
18
17
17
18
22
15
LIV-14
G.B.-24
12
16
22
18
LIV-13
15
25
16
8
Sterno-
costal
angle
8
7
6
5
4
3
2
1
Umbilicus
1


Sternocostal angle
ST-18


KID-24
KID-23
KID-22
Ren-17
5th intercostal space


5th intercostal space
SP-17
6 cun

Chest Centre DANZHONG Ren-17


1st intercostal space
2nd intercostal space
3rd intercostal space
Level of
the nipples
4th intercostal space
Ren-17
Level of
4th intercostal space
1/2
1/2


3rd intercostal space
4th intercostal space


1 cun
P-1
4th intercostal space


SP-18
4th intercostal space


KID-24
4th intercostal space
KID-23
Ren-17
KID-22


G.B.-23
4th intercostal space
G.B.-22
1 cun

Location

On the anterior midline, on the level of the 4th intercostal space.

How to find

Quick method, especially in men: Locate **Ren-17** on the sternum, between the two nipples. For more detailed orientation on the intercostal region (→ 3.5), first, locate the manubriosternal synchondrosis, which can be felt on the sternum as a well-defined horizontal bony structure on the level of the costal cartilage of the 2nd rib. The 2nd intercostal space is below it. From there, count in an inferior direction to the 4th intercostal space. Locate **Ren-17** on this level on the midline of the sternum. Located on the same level in the 4th intercostal space are **→ KID-23/ST-17/P-1/SP-18/G.B.-22/G.B.-23** (2 cun lateral to the midline/on the nipple/1 cun lateral to the nipple/6 cun lateral to the midline/on the axillary line/1 cun anterior to **→ G.B.-22**).

Needling

Depending on the indication, 0.5–1 cun transversely (subcutaneously) in a superior or inferior direction or towards the nipples (for mamillary disorders). Caution: Intracardiac needling, pneumothorax. The sternum can be very thin in this area owing to embryonic ossification disorders! Moxibustion is recommended in order to tonify the Qi, but caution with asthmatic patients.

Actions/Indications

- Regulates and benefits the Qi, unbinds the chest, descends counterflow Lung and Stomach Qi
- Benefits the breasts

Special features

Front-*mu* point of the Pericardium, meeting point with the SP, KID, S.I. and T.B. channels. *Hui*-meeting point of the Qi. Sea of Qi. Important point for respiratory disorders.

Ren-18 *Jade Hall* YUTANG

Location

On the anterior midline, on the level of the 3rd intercostal space.

How to find

Locate the 3rd intercostal space either by parasternal palpation starting at the clavicle or by counting downward from the manubriosternal synchondrosis (→ 2nd rib) (→ 3.5).
Located on the same level (→ 3rd intercostal space) are → **KID-24/ST-16/SP-19** (2/4/6 cun lateral to the midline).

Needling

0.5–1 cun transversely (subcutaneously) in a superior or inferior direction. Caution: Danger of injury to the heart or the pleura in patients with a sternal foramen, therefore only transverse needling with or against the flow of the channel.

Actions/Indications

- Unbinds the chest, regulates and descends the Qi


KID-24
3rd intercostal space
KID-23
Ren-17
KID-22


LU-1
SP-20
1st intercostal space
SP-19
2nd intercostal space
3rd intercostal space


2nd intercostal space
ST-16
3rd intercostal space
4th intercostal space


Ren-21
Ren-20
Ren-19
Ren-18
3rd intercostal space
Ren-17
Sterno-
costal
angle
Ren-16


19
16
24
18
17
17
18
22
15
LIV-14
G.B.-24
12
16
22
18
LIV-13
15
25
16
8
Sterno-
costal
angle
8
7
6
5
4
3
2
1
Umbilicus
1

Purple Palace ZIGONG **Ren-19**

Location

On the anterior midline, on the level of the 2nd intercostal space.

How to find

Locate the 2nd intercostal space by parasternal palpation starting at the clavicle or by palpating from the manubriosternal synchondrosis (→ 2nd rib) (→ 3.5).

Located at the same level (2nd intercostal space) are → **KID-25/ST-15/SP-20** (2/4/6 cun lateral to the midline).

Needling

0.5 cun transversely in a superior or inferior direction. Caution: In patients with a sternal foramen, danger of injury to the pleura or the mediastinum, therefore only transverse needling with or against the flow of the channel.

Actions/Indications

- Unbinds the chest
- Regulates and descends the Qi


Ren-21
Ren-20
2nd inter-
costal space
Ren-19
Ren-18
Sterno-
costal
angle
Ren-16


KID-25
2nd intercostal space
KID-24
KID-23
Ren-17


LU-1
SP-20
1st intercostal space
SP-19
2nd intercostal space
3rd intercostal space


ST-14
1st intercostal space
ST-15
2nd intercostal space


Manubriosternal
synchondrosis
Coracoid process
2nd rib
Sternocostal
angle
Xiphoid
process
11th rib
Free end of
the 12th rib
Free end of
the 11th rib

Ren-20 *Magnificent Canopy* HUAGAI

Location

On the anterior midline, on the lower part of the manubrium sterni, on the level of the 1st intercostal space.

How to find

The manubriosternal synchondrosis generally forms a distinct horizontal bony structure on the upper part of the sternum. Locate **Ren-20** slightly superior to the synchondrosis, on the midline and on the level of the 1st intercostal space.

Located at the same level (1st intercostal space) are → **KID-26/ST-14/LU-1** (2/4/6 cun lateral to the midline).

Needling

0.5 cun transversely in a superior or inferior direction. Caution: In patients with a sternal foramen, danger of injury to the pleura or the mediastinum, therefore only transverse needling with or against the flow of the channel.

Actions/Indications

- Unbinds the chest
- Regulates and descends the Qi


Ren-21
Ren-20
Ren-19
Ren-18
Sterno-costal angle
Ren-16


KID-27
KID-26
1st intercostal space


ST-13
ST-14
1st intercostal space


LU-2
Suprasternal fossa
1 cun
LU-1
Midline


ST-9
12
Ren-22
KID-27
14
26
20
SP-20
25
19
19
16
24
18
17
17
18
22
15
LIV-14
G.B.-24
12
16
22
18
LIV-13
15
25
16
8
Sterno-costal angle
8
7
6
5
4
3
2
1
Umbilicus

Jade Pivot XUANJI **Ren-21**


Ren-21
Ren-20
Ren-19
Ren-18
Ren-16
Sterno-costal angle

Location

On the anterior midline, below the upper border of the manubrium sterni.

How to find

The upper border of the manubrium sterni forms the lower border of the suprasternal fossa. Locate **Ren-21** on the midline, inferior to the bony margin of the sternum.
Located on approximately the same level (below the clavicle) are ➞ **KID-27/ST-13/LU-2** (2/4/6 cun lateral to the midline).

Needling

0.5 cun transversely in a superior or inferior direction. Caution: In patients with a sternal foramen, danger of injury to the pleura or the mediastinum, therefore only transverse needling with or against the flow of the channel.

Actions/Indications

- Unbinds the chest
- Benefits the throat
- Descends counterflow Qi


C6
T1
Coracoid process
Glenoid cavity
Clavicle
Acromion
1st rib
2nd rib
3rd rib
Scapula
4th rib
Sternum
6th rib
7th rib
8th rib
10th rib
11th rib
T12
12th rib
L1


KID-27
KID-26
1st rib




LU-2
Suprasternal fossa
1 cun
Midline

Ren-22 *Heavenly Prominence* TIANTU

Location

0.5 cun superior to the sternum, in the centre of the suprasternal fossa.

How to find

This point is best located with the patient in a supine position and a pillow under the shoulders or seated with a comfortable and safe head support. Locate the centre of the suprasternal fossa, approximately 0.5 cun superior to the sternum and there locate **Ren-22**.

Needling

Initial vertical insertion 0.2 cun (in order to penetrate the skin), then direct the tip of the needle inferiorly and continue to insert the needle parallel to the posterior aspect of the sternum up to 0.5–1 cun. Caution: Dangerous point. Wrong insertion technique (for example, vertical or oblique retrosternal needling) may lead to injury of the big vessels and organs inside the mediastinum. This point should only be needled by experienced practitioners.

Actions/Indications

- Descends counterflow Lung Qi, alleviates coughing and dyspnoea, benefits the throat

Special features

Meeting point with the *yin wei mai*, Window of Heaven point. Important emergency point for acute asthma attacks.


Suprasternal fossa
Ren-22


C6
T1
Coracoid process
Glenoid cavity
Clavicle
Acromion
1st rib
2nd rib
3rd rib
Scapula
4th rib
Sternum
6th rib
7th rib
8th rib
10th rib
11th rib
T12
12th rib
L1

Corner Spring LIANQUAN **Ren-23**


Ren-23
Hyoid bone
Laryngeal cartilage


T.B.-17
G.B.-12
Ex-HN
(*anmian*)
ST-5
ST-6
S.I.-17
T.B.-16
Ren-23
L.I.-18
S.I.-16
ST- 9
L.I.-17
ST-12
ST-11

Location

On the anterior midline, superior to the upper border of the hyoid bone.

How to find

The hyoid bone can be palpated as a delicate bony structure slightly superior to the upper border of the laryngeal prominence. The patient should not recline their head too much, as this will cause the soft tissue to become stretched, making palpation of the bone difficult. **Ren-23** is located on the midline, on the upper border of the hyoid bone and at the junction of the vertical aspect of the neck to the horizontal floor of the mouth (with normal tissue distribution).

Needling

0.3–1 cun obliquely in a superior direction towards the vertex (→ **Du-20**). Moxibustion is contraindicated according to some texts.

Actions/Indications

- Benefits the tongue
- Benefits the throat, eliminates Phlegm and Heat
- Strengthens the voice

Special features

Meeting point with the *yin wei mai*

Ren-24 *Container of Fluids* CHENGJIANG

Location

On the anterior midline, below the lower lip, in the mentolabial groove.

How to find

On the chin, locate the mentolabial groove (→ 3.1.3), which forms a horizontal depression at the transition from the chin to the lower lip. Locate **Ren-24** in this groove, on the midline.

Needling

0.2–0.3 cun obliquely in a superior direction.

Actions/Indications

- Eliminates (external) Wind, opens the *luo*-connecting vessels, alleviates pain and swellings, regulates the *ren mai*
- As Sun Si Miao Ghost point for epilepsy and mania

Special features

Meeting point with the *du mai*, ST and L.I. channels, Sun Si Miao Ghost point. Important local point.





5.3 *Du mai*

Synonym: Governing Vessel

Relationships (→ 1.7.3)

- **Yin/Yang:** *ren mai*/*du mai*
- **Central/peripheral:** *du mai*/*yang qiao mai*. Regions supported by this pairing: inner canthus of the eye, occiput, shoulders, back, S.I. and BL channels, opening point: **S.I.-3** (*houxi*), coupled point: **BL-62** (*shenmai*)

Pathway

The extraordinary vessel *du mai* originates like the *chong mai* and *ren mai* in the lower abdomen (*bao zhong*), according to some authors at the Kidneys, emerges at the perineum and divides into several branches:

- ➡ The **main pathway** of the *du mai* begins at → **Ren-1** (*huiyin*) at the perineum, reaches **Du-1** (*changqiang*) between the anus and the coccyx and ascends the posterior midline along the spine. At **Du-12** (*shenzhu*), below the spinous process of T3, a branch separates on either side to reach → **BL-12** (*fengmen*), rejoining the main branch at **Du-13** (*taodao*) below the spinous process of T1. It then continues to **Du-16** (*fengfu*) on the lower border of the occipital bone. Here, an **internal branch** enters the Brain. The external pathway continues to ascend the head to **Du-20** (*baihui*), from there beginning its descent along the midline to the forehead and the nose to **Du-26** (*renzhong*) where it crosses the ST and L.I. channels. It terminates inside the mouth below the frenulum at **Du-28** (*yinjiao*) where it meets the ST channel and the extraordinary vessel *ren mai*.
- ➡ **one branch** of the *du mai* (the spinal branch) originates at → **Ren-1** (*huiyin*), courses to the tip of the coccyx where it meets the Kidney primary channel, ascends **within** the spinal canal to the space between L2 and L3 and enters the Kidneys.
- ➡ **The second branch** of the *du mai* (the abdominal branch) also originates at → **Ren-1** (*huiyin*), encircles the external genitalia and ascends to the umbilicus, passes through the Heart (*xin*), continues to the throat, circles the lips, travels to the cheek, passes → **ST-1** (*chengqi*) at the infraorbital ridge and reaches → **BL-1** (*jingming*).
- ➡ **The third branch** of the *du mai* travels bilaterally alongside the BL channel from → **BL-1** (*jingming*) to the vertex. From here, it branches out **internally** into the Brain. The **external** pathway follows the medial branches of the BL channel in an inferior direction and enters the body at the level of the lower border of the spinous process of L2 at → **BL-23** (*shenshu*) to terminate at the Kidneys (*shen*).







Meeting points of other channels with the *du mai*



Ren-1 (*huiyin*): In the centre of the perineum



BL-12 (*fengmen*): 1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 2nd thoracic vertebra (T2)



ST-1 (*chengqi*): With the eyes looking straight ahead, directly below the centre of the pupil, between the eyeball and the infraorbital ridge



BL-1 (*jingming*): 0.1 cun superior and medial to the inner canthus of the eye, in a depression



BL-23 (*shenshu*): 1.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 2nd lumbar vertebra (L2)

Connections with other channels/Organs

- *Ren mai*, *chong mai*, Bladder and Kidney primary channels
- Uterus, Kidneys, Brain

Clinical importance (→ 1.7.2, 1.7.3)

- **Sea of the Yang Qi**, supplies Yang Qi in order to warm the Organs and channels
- Supports and regulates all Yang channels, especially those of the upper back and head
- Influences and strengthens the functions of the Brain, Marrow and sensory organs
- Strengthens the body constitutionally and supports the immune system (circulation of the Defensive Qi (*wei qi*))
- Stores the Essence Qi (*jing qi*) overflowing from the Yang channels
- Absorbs excess from the Yang channels, especially excess Heat and internal Wind

Notes about the *du mai*

Both the *du mai* and *ren mai* have a unique position among the eight extraordinary vessels. They are the only two extraordinary vessels with their own specific points – all the other extraordinary vessels can only be accessed through points on the primary channels. For this reason the *ren mai* and the *du mai*, together with the primary channels, are often categorised as 14 channels. However, from the point of view of channel energetics this is not correct, since the extraordinary vessels occupy a special position, both evolutionarily and functionally (→ 1.7).

The pathway of the *du mai*, like that of the *ren mai*, is limited to the torso and the head. While it does not course along the extremities and does not have any points on the limbs (neither general points nor specific points such as the five *shu*-transporting points, *yuan*-source points, etc.) it does have a pertaining opening point (or master point) (→ 8.1.8).

The *du mai* is also referred to as the Sea of Yang and governs the Yang in the whole body. Located along its pathway are the posterior aspects of the energy centres (or chakras according to Yogi tradition) while their anterior aspects are located along the pathway of the *ren mai*. In Daoist tradition the *du mai* plays an important role in the cultivation of Qi. This concerns the development of a 'spirit child', which can be influenced by opening and activating energy centres located along the spine.

Furthermore, the *du mai* contains many meeting points with other channels. This clearly denotes the outstanding importance of the *du mai*.

Specific points according to their function

- ***Yuan*-source point (→ 8.1.1): –**
- ***Luo*-Connecting point (→ 8.1.2.): Du-1** (*changqiang*)
- ***Xi*-cleft point (→ 8.1.3): –**
- **Back-*shu* point (→ 8.1.4): –**
- **Front-*mu* point (→ 8.1.5): –**
- **Five *shu*-transporting points (→ 8.1.6): –**
- ***Hui*-meeting point (→ 8.1.7): –**
- **Pertaining opening point (→ 8.1.8): S.I.-3** (*houxi*)
- **Pertaining coupled point (→ 8.1.8): BL-62** (*shenmai*)
- **Lower *he*-Sea point (→ 8.1.9): –**
- ***Jiaohui*-meeting points (→ 8.1.10):**

- with the G.B. and KID channels and the *ren mai*: **Du-1** (*changqiang*)
- with the BL channel: **Du-13** (*taodao*)
- with all Yang channels: **Du-14** (*dazhui*) 🟦🟦
- with the *yang wei mai*: **Du-15** (*yamen*) 🟦■
- with the *yang wei mai* and the *yang qiao mai**: **Du-16** (*fengfu*) 🟦🟦
- with the BL channel: **Du-17** (*naohu*)
- with the BL, G.B., T.B. and LIV channels: **Du-20** (*baihui*) 🟦🟦
- with the BL and ST channels: **Du-24** (*shenting*) 🟦■
- with the L.I. and ST channels: **Du-26** (*renzhong*) 🟦🟦
- with the *ren mai* and ST channel*: **Du-28** (*yinjiao*)
- of other channels with the *du mai*: **Ren-1, BL-12**, **ST-1, BL-1, BL-23**

- **Gao Wu command point (→ 8.1.11): –**
- **Window of Heaven point (→ 8.1.12): Du-16** (*fengfu*) 🟦🟦
- **Points of the Four Seas (→ 8.1.13):**
  - Sea of Qi: **Du-14** (*dazhui*) 🟦🟦, **Du-15** (*yamen*) 🟦■
  - Sea of Marrow: **Du-16** (*fengfu*) 🟦🟦; **Du-20** (*baihui*) 🟦🟦
- **Ma Dan Yang Heavenly Star point (→ 8.1.14):**
- **Sun Si Miao Ghost point (→ 8.1.15): Du-16** (*fengfu*) 🟦🟦, **Du-26** (*renzhong*) 🟦🟦
- **Other functional points:**
  - very important point for strengthening the Yang (with moxibustion): **Du-4** (*mingmen*) 🟦🟦
  - important emergency point: **Du-26** (*renzhong*) 🟦🟦

Points according to region

- **Local points (→ 8.2.1):** Temporal region – **Du-20** (*baihui*) 🟦🟦; nose – **Du-25** (*suliao*); rectum – **Du-1** (*changqiang*); lumbar spine – **Du-3** (*yaoyangguan*), **Du-4** (*mingmen*) 🟦🟦
- **Adjacent points (→ 8.2.1):** occipital region – **Du-14** (*dazhui*) 🟦🟦; temporal region, eyes – **Du-23** (*shangxing*); nose – **Du-23** (*shangxing*), **Du-24** (*shenting*); Lungs – **Du-14** (*dazhui*) 🟦🟦; Heart – **Du-11** (*shendao*); cervical spine – **Du-14** (*dazhui*) 🟦🟦
- **Distal points (→ 8.2.1):** tongue – **Du-15** (*yamen*) 🟦■; rectum – **Du-20** (*baihui*) 🟦🟦; lumbar spine – **Du-12** (*shenzhu*), – **Du-26** (*renzhong*) 🟦🟦

Specific points according to the vessel pathway (in numerical order)

- **Du-1** (*changqiang*): *luo*-connecting point (→ 8.1.2); *jiaohui*-meeting point with the G.B., KID channels and the *ren mai* (→ 8.1.10); local point for the rectum (→ 8.2.1)
- **Du-3** (*yaoyangguan*): local point for the lumbar spine (→ 8.2.1)
- **Du-4** (*mingmen*) 🟦🟦: very important point for strengthening the Yang (with moxibustion)
- **Du-11** (*shendao*): adjacent point for the Heart (→ 8.2.1)
- **Du-12** (*shenzhu*): distal point for the lumbar spine (→ 8.2.1)
- **Du-13** (taodao): *jiaohui*-meeting point with the BL channel (→ 8.1.10)
- **Du-14** (*dazhui*) 🟦🟦: *jiaohui*-meeting point with all Yang channels (→ 8.1.10); point of the Sea of Qi (→ 8.1.13); adjacent point for the occiput and Lung (→ 8.2.1); adjacent point for the cervical spine (→ 8.2.1)
- **Du-15** (*yamen*) 🟦■: *jiaohui*-meeting point with the *yang wei mai* (→ 8.1.10); Sea of Qi point (→ 8.1.13); distal point for the tongue (→ 8.2.1)
- **Du-16** (*fengfu*) 🟦🟦: point of the Sea of Marrow (→ 8.1.13); Window of Heaven point (→ 8.1.12); Sun Si Miao Ghost point (→ 8.1.15); *jiaohui*-meeting point with the *yang wei mai* and the *yang qiao mai** (→ 8.1.10)
- **Du-17** (*naohu*): *jiaohui*-meeting point with the BL channel (→ 8.1.10)
- **Du-20** (*baihui*) 🟦🟦 *jiaohui*-meeting point with the BL, G.B., T.B. and LIV channels (→ 8.1.10); point of the Sea of Marrow (→ 8.1.13); local point for the temporal aspect of the head (→ 4.2.1); distal point for the rectum (→ 8.2.1)
- **Du-23** (*shangxing*): regional point for the temporal region, the eyes and the nose (→ 8.2.1)
- **Du-24** (*shenting*) 🟦■: *jiaohui*-meeting point with the BL and ST channels (→ 4.1.10); adjacent point for the nose (→ 8.2.1)
- **Du-25** (*suliao*): local point for the nose (→ 4.2.1)
- **Du-26** (*renzhong*) 🟦🟦: *jiaohui*-meeting point with the L.I. and ST channels (→ 8.1.10); Sun Si Miao Ghost point (→ 8.1.15); distal point for the lumbar spine (→ 8.2.1); important emergency point
- **Du-28** (*yinjiao*): *jiaohui*-meeting point with the *ren mai* and ST channel (→ 8.1.10)

---

* Mentioned by only some authors

luo-Connecting Vessel of the *Du Mai*

Pathway

The *luo*-connecting vessel of the *du mai* originates at **Du-1** (*changqiang*) between the anus and the tip of the coccyx, bilaterally ascends the spine to the neck and disperses in the occipital region, where it connects with the Bladder primary channel. Both course together to the shoulder region. There the *luo*-connecting vessel enters deeper into the body at the level of the scapula and spreads in the paravertebral musculature.



Clinical importance

Pathology

Excess (***shi***): limited range of motion and stiffness of the spine
Deficiency (***xu***): heavy sensations of the head, dizziness, balance disorders

Long Strong CHANGQIANG Du-1


Anus
Du-1
Coccyx
Tip of the coccyx


Ex-B-5
Ex-B-5
Ex-B-7
25
3
4
Ex-B-6
Ex-B-8
54
30
Ex-B-11
2
1
36
Bladder channel, outer branch
Du mai
Bladder channel, inner branch




Anus
0.5 cun
Tip of the coccyx
Coccyx
BL-35

Location

On the midline, midway between the tip of the coccyx and the anus.

How to find

First, locate the coccyx superior to the anus, then palpate for its tip. From the tip of the coccyx, palpate with pressure towards the anus. **Du-1** can often be located based on a strong *de* Qi sensation.

→ **Ren-1** is located anterior to the anus, posterior to the genitals.

→ **BL-35** is located 0.5 cun lateral to the midline, at the level of the tip of the coccyx.

Needling

After thorough disinfection, vertically 0.5–1 cun. Avoid puncturing the rectum.

Actions/Indications

- Clears Damp-Heat, lifts the Qi
- Opens the channel and alleviates pain
- Calms the *shen*

Special features

Luo-connecting point, meeting point with the *ren mai*, G.B. and KID channels.

Du-2 *Lumbar Shu* YAOSHU

Location

On the midline, in the sacral hiatus.

How to find

Palpate for the sacral hiatus (→ 3.4.4) from the sacrum. It can be felt at the inferior end of the iliac median crest as a U-shaped depression opening towards the inferior. **Du-2** is located on the midline, directly below the hiatus.

→ **BL-35** is located slightly more inferiorly, 0.5 cun lateral to the midline, on the level of the tip of the coccyx.

Needling

Up to 1 cun vertically or obliquely in a superior direction.

Actions/Indications

- Strengthens the lumbar region and the legs
- Dispels Wind-Dampness
- Warms the Lower Burner


Median sacral crest
Fingers on the 1st to 4th sacral foramina
Sacral hiatus
Du-2


Anus
0.5 cun
Tip of the coccyx
Coccyx
BL-35


Ex-B-5
Ex-B-5
Ex-B-7
25
3
Ex-B-6
Ex-B-8
54
30
Ex-B-11
2
1
36
Bladder channel, outer branch
Du mai
Bladder channel, inner branch


Median sacral crest
Sacral foramina
Sacral hiatus

Ch05b-F10028.qxd 2/22/08 9:55 PM Page 501

Lumbar Yang Gate YAOYANGGUAN Du-3


Spinous process C1
Spinous process C2
Spinous process C3
Level of the iliac crests
Spinous process C4
Du-3
Spinous process C5


Level of L4
Level of the iliac crests


BL-23
Du-4
BL-52
Spinous process L4
Level of the iliac crests
Tuffier's line
Du-3

Location

On the midline, below the spinous process of the 4th lumbar vertebra (L4).

How to find

For orientation in the lumbar region (→ 3.4.3), first, locate the Tuffier's line (a line connecting the two most superior points on the iliac crest), which generally intersects with the spinous process of L4. (Note: Point location in the lumbar region is dependent on the patient's position; for more detail on orientation → 3.4). Locate **Du-3** on the midline, below the spinous process of L4.

Located on the same level are a point of → **Ex-B-2/BL-25/Ex-B-6/Ex-B-7** (0.5/1.5/3/3.5 cun lateral to the midline).

Needling

0.5–1 cun strictly vertically to the skin or obliquely in an inferior direction (generally, there is only danger of accidental puncture of the spinal canal from the level of L2 in a cranial direction).

Actions/Indications

- Dispels Wind, Cold and Dampness
- Regulates Qi in the Lower Burner, strengthens the Original Qi (*yuan qi*)

Special features

Important local point for combined back and leg pain


Spinous process L1
Spinous process L2
Level of the iliac crests ≙ L4 (dependent on patient position)
BL-25
Midline


Spinous process L4
Level of the iliac crests
Ex-B-6


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2 (parts)


Spinous process L3
Spinous process L4
Level of the iliac crests
Ex-B-7

Du-4 *Gate of Life* MINGMEN

Location

On the posterior midline, below the spinous process of the 2nd lumbar vertebra (L2).

How to find

For orientation in the lumbar region (→ 3.4.3), first, locate the Tuffier's line by placing both hands directly superior and lateral to the two highest points on the iliac crest, joining the thumbs on the midline. The line will generally intersect with the spinous process of L4. (Note: Orientation on the lumbar region depends on the patient's position; for more detail on differential orientation → 3.4). From there, count up to the spinous process of L2 and locate **Du-4** on the midline, below the spinous process. Located on the same level are a point of → **Ex-B-2/BL-23/BL-52** (0.5/1.5/3 cun lateral to the midline).

Needling

0.5–1 cun vertically to slightly obliquely in an inferior direction, with the patient's back straight or flexed. The spinal cord generally ends between the 1st and 2nd lumbar vertebrae; still, there is hardly any mention in the literature of spinal punctures with deep needling and/or insertions in a superior direction.

Actions/Indications

- Tonifies Kidney Yang (especially with moxibustion), warms the *mingmen*, strengthens the Kidneys, regulates the *du mai*, benefits the lumbar region
- Pacifies Wind in the *du mai*

Special features

Major point for tonifying Yang, especially Kidney Yang


Spinous process L2
Du-4
Spinous process L3
Level of the iliac crests
Spinous process L4
Spinous process L4
(dependent on patient position)


Level of L4
Level of the iliac crests


Spinous process L1
Spinous process L2
Spinous process L3
Spinous process L4
Level of the iliac crests
BL-22
BL-23
BL-24


Spinous process L1
Spinous process L2
Spinous process L3
BL-52


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2
(parts)


11
12
1
49
20
6
Ex-B-4
2
52
23
4
3
Ex-B-5
Ex-B-5
4
Ex-B-7
25
3
Ex-B-6
5
Ex-B-8

Suspended Pivot XUANSHU Du-5


Spinous process L1
Du-5
Spinous process L2
Spinous process L3
Level of the iliac crests
Spinous process L4
Spinous process L5


BL-23
Du-4
BL-5
Spinous process L4
Level of the iliac crests
Tuffier's line
Du-3


Spinous process L1
BL-22
Spinous process L2


Spinous process L1
BL-51
Spinous process L2


Spinous process L1
Ex-B-4

Location

On the midline, below the spinous process of the 1st lumbar vertebra (L1).

How to find

For orientation in the lumbar region (➞ 3.4.3), first, locate the Tuffier's line by placing both hands directly superior and lateral to the two highest points on the iliac crest, joining the thumbs on the midline. The Tuffier's line generally intersects with the spinous process of L4. (Note: Anatomical orientation in the lumbar region is dependent on the patient's position; for more detail on differential orientation ➞ 3.4.) From there, count up to the spinous process of L1 and locate **Du-5** on the midline, below its spinous process. **Or:** Use the spinous process of T7 (inferior angle of the scapula ➞ 3.4.2) for reference.

Located on the same level are a point of ➞ **Ex-B-2/BL-22/ BL-51/Ex-B-4** (0.5/1.5/3/3.5 cun lateral to the midline).

Needling

0.5–1 cun strictly vertically to the skin or obliquely in an inferior direction, with the patient's back straight or flexed in order to avoid puncturing the spinal canal. Oblique insertions should only be carried out by experienced practitioners, as in small persons (irrespective of their body weight), the spinal canal may be reached after only 1.25 cun.

Actions/Indications

- Opens the channel
- Regulates Qi in the Lower Burner

Du-6 *Centre of the Spine* JIZHONG

Location

On the midline, below the spinous process of the 11th thoracic vertebra (T11).

How to find

Locate T7 (→ 3.4.2) and, from there, count down 4 spinous processes to T11. Locate **Du-6** on the midline, below its spinous process. **Or:** Use the Tuffier's line for reference (→ 3.4.3). Locate T11 by counting up 5 spinous processes from L4 and there locate **Du-6** on the midline, below the spinous process.
Located on the same level are a point of → **Ex-B-2/BL-20/BL-49** (0.5/1.5/3 cun lateral to the midline).

Needling

0.5–1 cun strictly vertically to the skin or obliquely in an inferior direction, with the patient's back straight or flexed in order to avoid puncturing the spinal canal. Oblique insertions should only be carried out by experienced practitioners, as in small persons (irrespective of their body weight), the spinal canal may be reached after only 1.25 cun.

Actions/Indications

- Strengthens the Spleen and its function of transforming Dampness
- Benefits the spine


Spinous process T11
Spinous process T12
BL-20
Bladder channel


Spinous process T11
Spinous process T12
BL-49


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2
(parts)


Spinous process C7
Base of the scapular spine
Spinous process T3
Spinous process T7
Inferior angle
Spinous process T11
Du-6
Spinous process T12
Midline


S.I.-15
S.I.-12
S.I.-10
14
11
13
1
2
3
42
13
12
4
5
44
15
11
6
7
8
46
17
9
Ex-B-3
9
47
18
8
10
11
49
20
6
12


BL-23
Du-4
BL-52
Spinous process L4
Level of the iliac crests
Tuffier's line
Du-3

Central Pivot ZHONGSHU **Du-7**


Spinous process C7
Base of the scapular spine
Spinous process T3
Spinous process T7
Inferior angle
Spinous process T10
Du-7
Spinous process T11
Midline


Extension and flexion of the head
2 fingers on the spinous processes of C6 and C7
G.B.-21
S.I.-15
Du-14


cun
cun
Spinous process T7
Inferior angle
Spinous process T10
BL-19


inferior
Spinous process T10
BL-48

Location

On the midline, below the spinous process of the 10th thoracic vertebra (T10).

How to find

Locate T7 (➞ 3.4.2) and, from there, count down 3 spinous processes to T10. Locate **Du-7** on the midline, below its spinous process. **Or:** Use the Tuffier's line for reference (➞ 3.4.3). Locate T11 by counting up 5 spinous processes from L4 and there locate **Du-7** on the midline, below the spinous process.

Located on the same level are a point of ➞ **Ex-B-2/BL-19/BL-48** (0.5/1.5/3 cun lateral to the midline).

Needling

0.5–1 cun strictly vertically to the skin or obliquely in an inferior direction, with the patient's back straight or flexed in order to avoid puncturing the spinal canal. Oblique insertions should only be carried out by experienced practitioners, as in small persons (irrespective of their body weight), the spinal canal may be reached after only 1.25 cun.

Actions/Indications

- Tonifies the Middle Burner
- Benefits the spine

Ch05b-F10028.qxd 2/22/08 9:55 PM Page 506

Du-8 *Sinew Contraction* JINSUO

Location

On the midline, below the spinous process of the 9th thoracic vertebra (T9).

How to find

Locate T7 (➞ 3.4.2) and, from there, count down 2 spinous processes to T9. Locate **Du-8** on the midline, below its spinous process. **Or:** Use the Tuffier's line for reference (➞ 3.4.3). Locate T9 by counting up from L4 and there locate **Du-8** on the midline, below the spinous process.

Located on the same level are a point of ➞ **Ex-B-2/BL-18/BL-47** (0.5/1.5/3 cun lateral to the midline).

Needling

0.5–1 cun strictly vertically to the skin or obliquely in an inferior direction, with the patient's back straight or flexed in order to avoid puncturing the spinal canal. Oblique insertions should only be carried out by experienced practitioners, as in small persons (irrespective of their body weight), the spinal canal may be reached after only 1.25 cun.

Actions/Indications

- Soothes the Liver
- Dispels Wind
- Calms the *shen*


Spinous process C7
Base of the scapular spine
Spinous process T3
Spinous process T7
Inferior angle
Spinous process T9
Du-8
Spinous process T10
Midline


S.I.-15
S.I.-12
S.I.-10
14
11
13
42
13
12
44
15
11
46
17
9
Ex-B-3
47
18
8
49
20
6


Spinous process T7
Inferior angle
Spinous process T9
BL-18


Spinous process T7
Inferior angle
Spinous process T9
BL-47


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2 (parts)

Reaching Yang ZHIYANG Du-9


Spinous process C7
Base of the scapular spine
Spinous process T3
Spinous process T7
Du-9
Inferior angle
Midline


Extension and flexion of the head
2 fingers on the spinous processes of C6 and C7
G.B.-21
S.I.-15
Du-14


Spinous process T7
BL-17
Inferior angle


Spinous process T7
BL-46
Inferior angle
3 cun

Location

On the midline, below the spinous process of the 7th thoracic vertebra (T7).

How to find

Find T7 (→ 3.4.2) and locate **Du-9** on the midline, below its spinous process. **Or:** Use the Tuffier's line for reference (→ 3.4.3). Locate T7 by counting up from L4 and there locate **Du-9** on the midline, below the spinous process.
Located on the same level are a point of → **Ex-B-2/BL-17/BL-46** (0.5/1.5/3 cun lateral to the midline).

Needling

0.5–1 cun strictly vertically to the skin or obliquely in an inferior direction, with the patient's back straight or flexed in order to avoid puncturing the spinal canal. Oblique insertions should only be carried out by experienced practitioners, as in small persons (irrespective of their body weight), the spinal canal may be reached after only 1.25 cun.

Actions/Indications

- Strengthens the Spleen and eliminates Dampness
- Clears Damp-Heat from the Middle Burner
- Harmonises the Upper Burner

Du-10 *Spirit Tower* LINGTAI

Location

On the midline, below the spinous process of the 6th thoracic vertebra (T6).

How to find

Locate T7 (→ 3.4.2). **Du-10** is located on the midline, below the spinous process of the T6. **Or:** Locate C7 (→ 3.4.1). **Du-10** can then be located by counting down 6 spinous processes (T1–T6). Located on the same level are a point of → **Ex-B-2/BL-16/BL-45** (0.5/1.5/3 cun lateral to the midline).

Needling

0.5–1 cun strictly vertically to the skin or obliquely in an inferior direction, with the patient's back straight or flexed in order to avoid puncturing the spinal canal. Oblique insertions should only be carried out by experienced practitioners, as in small persons (irrespective of their body weight), the spinal canal may be reached after only 1.25 cun.

Actions/Indications

- Harmonises the Upper Burner
- Clears Heat and Fire toxins


Spinous process C7
Base of the scapular spine
Spinous process T3
Spinous process T6
Du-10
Spinous process T7
Inferior angle
Midline


S.I.-15
14
1
S.I.-12
11
13
2
S.I.-10
3
42
13
12
4
5
44
15
11
6
7
8
46
17
9
Ex-B-3
9
47
18
8
10
11
49
20
6
12


Spinous process T6
Spinous process T7
BL-16
Inferior angle


Spinous process T6
Spinous process T7
BL-45
Inferior angle
3 cun

Spirit Pathway SHENDAO Du-11


Spinous process C7
Base of the scapular spine
Spinous process T3
Spinous process T5
Du-11
Spinous process T7
Inferior angle
Midline


Extension and flexion of the head
2 fingers on the spinous processes of C6 and 7
G.B.-21
S.I.-15
Du-14


Spinous process T3
Spinous process T5
BL-15


Spinous process T5
BL-44
Spinous process T7
Inferior angle

Location

On the midline, below the spinous process of the 5th thoracic vertebra (T5).

How to find

Locate T7 (→ 3.4.2). From there, count up 2 spinous processes and find **Du-11** on the midline, below the spinous process of T5.
Or: Locate C7 (→ 3.4.1). **Du-11** can then be located by counting down 5 spinous processes (T1–T5).
Located on the same level are a point of → **Ex-B-2/BL-15/BL-44** (0.5/1.5/3 cun lateral to the midline).

Needling

0.5–1 cun strictly vertically to the skin or obliquely in an inferior direction, with the patient's back straight or flexed in order to avoid puncturing the spinal canal. Oblique insertions should only be carried out by experienced practitioners, as in small persons (irrespective of their body weight), the spinal canal may be reached after only 1.25 cun.

Actions/Indications

- Tonifies the Heart and the Lungs
- Calms the *shen*
- Dispels Wind and Heat

Du-12 *Body Pillar* SHENZHU

Location

On the midline, below the spinous process of the 3rd thoracic vertebra (T3).

How to find

Locate T7 (➞ 3.4.2). From there, count up 4 spinous processes and locate **Du-12** on the midline, below the spinous process of T3. **Or:** Locate C7 (➞ 3.4.1). **Du-12** can then be located by counting down 3 spinous processes (T1–T3).
Located on the same level are a point of ➞ **Ex-B-2/BL-13/BL-42** (0.5/1.5/3 cun lateral to the midline).

Needling

0.3–1 cun strictly vertically to the skin or obliquely in an inferior direction, with the patient's back straight or flexed in order to avoid puncturing the spinal canal. Oblique insertions should only be carried out by experienced practitioners, as in small persons (irrespective of their body weight), the spinal canal may be reached after only 1.25 cun.

Actions/Indications

- Dispels internal and external Wind
- Calms the *shen*
- Tonifies the Lungs

Special features

Meeting point with the BL channel


Base of the scapular spine
Spinous process C7
Spinous process T3
Du-12
Spinous process T7
Inferior angle
Midline


S.I.-15
S.I.-12
S.I.-10
14
11
13
42
13
12
44
15
11
46
17
9
Ex-B-3
47
18
8
49
20
6
1
2
3
4
5
6
7
8
9
10
11
12


Spinous process T3
BL-13


Spinous process C7
Medi
scapula
Scapular spine
Spinous process T3
BL-42

Way of Happiness TAODAO Du-13


Medial base of scapular spine
Spinous process C7
Spinous process T1
Du-13
Spinous process T3
Spinous process T7
Inferior angle
Midline


Extension and flexion of the head
2 fingers on the spinous processes of C6 and 7
G.B.-21
S.I.-15
Du-14


BL-11
Medial border of the scapula
Medial base of scapular spine
Spinous process C7
Spinous process T1

Location

On the midline, below the spinous process of the 1st thoracic vertebra (T1).

How to find

Locate C7 (→ 3.4.2). Palpate downward to the next spinous process (T1) and locate **Du-13** on the midline, below its spinous process.

Located on the same level are a point of → **Ex-B-2/BL-11/S.I.-14** (0.5/1.5/3 cun lateral to the midline).

Needling

0.3–1 cun strictly perpendicularly to the skin or obliquely in an inferior direction, with the patient's back straight or flexed in order to avoid puncturing the spinal canal. Oblique insertions should only be carried out by experienced practitioners, as in small persons (irrespective of their body weight), the spinal canal may be reached after only 1.25 cun.

Actions/Indications

- Dispels pathogenic factors
- Opens the channel and *luo*-connecting vessels

Special features

Meeting point with the BL channel


Levator scapulae
Spinous process T7
Spinous process C1
S.I.-14
S.I.-13
Du-13
BL-11
Spinous process C4

Du-14 *Great Vertebra* DAZHUI

Location

On the midline, below the spinous process of the 7th cervical vertebra (C7).

How to find

First, identify C7 (→ 3.4.1): Place 2 fingers on the spinous processes believed to belong to C6 and C7 and ask the patient to flex and extend their head. In a fully functional spine and with correct finger placement, C6 will glide anteriorly with neck extension, while C7 will remain fixed. However, if the vertebra below the upper finger does not move with neck extension, the fingers will most probably have been placed on C7 and T1. Locate **Du-14** below the spinous process of C7.

Located on the same level are → **Ex-B-1** (*dingchuan*)/ **S.I.-15/Ex-B** (*jiehexue*) (0.5/2/3.5 cun lateral to **Du-14**).

Needling

0.3–1 cun strictly vertically to the skin or obliquely in an inferior direction, with the patient's back straight or flexed in order to avoid puncturing the spinal canal. Oblique insertions should only be carried out by experienced practitioners, as in small persons (irrespective of their body weight), the spinal canal may be reached after only 1.25 cun. For persistent epistaxis, place a cold metal object (for example, a spoon) or a cold cloth on **Du-14**. Cupping on this point for acute colds.

Actions/Indications

- Clears Wind, firms and regulates the surface, dispels pathogenic factors
- Clears Heat
- Calms (internal) Wind and the *shen*
- Strengthens Qi and Yang in deficiency conditions
- Benefits the spine, especially the cervical spine

Special features

Meeting point with all Yang channels, Sea of Qi point.


Medial base of scapular spine
Spinous process C7
Du-14
Spinous process T3
Spinous process T7
Inferior angle
Midline


Extension and flexion of the head
Spinous processes of C6 and 7


0.5 cun
Medial base of scapular spine
Spinous process C7
Ex-B-1


3.5 cun
Ex-B-10 (*jiehexue*)
Spinous process C7
Medial base of scapular spine
Du-14


S.I.-15
S.I.-12
S.I.-10
14
1
11
13
2
3
42
13
12
4
5
44
15
11
6
7
8
46
17
9
Ex B-3
9
47
18
8
10
11
49
20
6
12

Gate of Muteness YAMEN **Du-15**


External occipital protuberance
Atlas
Du-16
Occipital bone
G.B.-20
Lower border of the occiput
G.B.-20
Axis
BL-10
Sternocleido-mastoid
Du-15
1st palpable spinous process
Trapezius, superior fibres
Du-14


Sagittal suture
Parietal bone
Lambdoid suture
BL-9
Du-17
BL-9
Mastoid process
Occipitomastoid suture
Du-16
Occipital bone
External occipital protuberance


Extension and flexion of the head
2 fingers on the spinous processes of C6 and 7
G.B.-21
S.I.-15
Du-14

Location

On the occiput, on the posterior midline, in the depression between the 1st (atlas) and 2nd (axis) cervical vertebrae, approximately 0.5 cun inferior to ➞ **Du-16** (directly below the external occipital protuberance).

How to find

The external occipital protuberance (➞ 3.1.5) is a hump-shaped projection on the posterior surface of the occipital bone, on the midline and slightly superior to the craniocervical junction (➞ 3.1.5). ➞ **Du-16** is located in a depression on the posterior midline that you can palpate directly inferior to the protuberance. From there, glide 0.5 cun in an inferior direction and locate **Du-15** superior to the first palpable spinous process (belonging to the axis; the atlas has no spinous process) and approximately 0.5 cun superior to the posteror hairline.

Located on the same level is ➞ **BL-10** (on the lateral aspect of the trapezius muscle).

Needling

0.5–1 cun strictly perpendicularly in an inferior direction. Caution: Injury to the cervical marrow. According to classic texts, moxibustion is contraindicated.

Actions/Indications

- Benefits the tongue, ears, neck and spine
- Dispels Wind
- Clears Yang Heat/excess

Special features

Meeting point with the *yang wei mai*. Sea of Qi point.


G.B.-19
BL-9
Du-17
G.B.-20
Du-16
G.B.-12
BL-10
Du-15
G.B.-21
Du-14

Du-16 *Palace of Wind* FENGFU

Location

On the posterior midline, directly below the external occipital protuberance, in the depression between the origins of the trapezius muscle.

How to find

The external occipital protuberance (→ 3.1.5) is a hump-shaped projection on the posterior surface of the occipital bone, on the midline and slightly superior to the craniocervical junction (→ 3.1.5). Locate **Du-16** in a depression on the posterior midline that can be palpated directly inferior to the protuberance and between the two origins of the trapezius muscle. Generally, **Du-16** is located approximately 1 cun superior to the posterior hairline. → **G.B.-20** is located on the same level below the occiput, in a depression between the origins of the trapezius and sternocleidomastoid muscles.

Needling

0.5–1 cun slightly obliquely in an inferior direction. Bend the patient's head slightly forward when needling. Caution: Dangerous point with deep needling! No stimulation. Strictly no needling in a superior direction, danger of puncturing the cerebellomedullary cistern (also site for suboccipital puncture). The needle should be inserted into the nuchal ligament. According to some authors, moxibustion is contraindicated.

Actions/Indications

- Dispels (external) Wind
- Calms internal Wind and the *shen*
- Nourishes the Sea of Marrow, lightens the *shen*

Special features

Meeting point with the *yang wei mai* and, according to some authors, the *yang qiao mai*. Sea of Marrow point, Window of Heaven point, Sun Si Miao Ghost point. Used for all disorders which are caused by 'external or internal' Wind and which are characterised by sudden onset, changing location and/or intensity of the disorder, involuntary movements.


Atlas
External occipital protuberance
Du-16
Occipital bone
G.B.-20
Lower border of the occiput
G.B.-20
Axis
BL-10
Sternocleido-mastoid
Du-15
1st palpable spinous process
Trapezius, superior fibres
Du-14


G.B.-19
BL-9
Du-17
Du-16
G.B.-20
G.B.-12
BL-10
Du-15
G.B.-21
Du-14


Occipital bone
G.B.-20
Lower border of the occiput
G.B.-20
Axis
BL-10
Sternocleido-mastoid

Brain's Door NAOHU Du-17


External
occipital
protuberance
Du-17
Du-16
1.5 cun
C1
≙(atlas)
Hairline


Sagittal suture
Parietal bone
Lambdoid suture
BL-9
Du-17
BL-9
Mastoid
process
Occipitomastoid
suture
Du-16
Occipital bone
External occipital
protuberance


External
occipital
protuberance
M
1.3 cun
Du-17
BL-9
Du-16
ca.
2.5 cun

Location

In a depression superior to the external occipital protuberance, approximately 2.5 cun superior to the posterior hairline or 1.5 cun superior to ➞ **Du-16**.

How to find

First, locate the external occipital protuberance (➞ 3.1.5), which forms a hump-shaped projection on the posterior surface of the occipital bone. Next, locate **Du-17** on the posterior midline, in a depression directly superior to the protuberance. This corresponds to a distance of approximately 2.5 cun superior to the posterior hairline (➞ 3.1.5).

➞ **Du-16** is located directly inferior to the protuberance, whereas ➞ **BL-9** is located 1.3 cun lateral to **Du-17**.

Needling

0.5–1 cun transversely (subcutaneously) in an inferior or superior direction. Moxibustion controversial.

Actions/Indications

- Dispels Wind
- Opens the channel
- Benefits the eyes
- Calms the *shen*

Special features

Meeting point with the BL channel

Du-18 *Unyielding Space* QIANGJIAN

Location

On the posterior midline, 1.5 cun superior to **Du-17** (directly superior to the external occipital protuberance) or 3 cun inferior to → **Du-20** (on the vertex).

How to find

First, locate → **Du-17** in a depression directly superior to the external occipital protuberance (→ 3.1.5), which forms a hump-shaped projection on the posterior surface of the occipital bone. From there, palpate 1.5 cun in a superior direction and there locate **Du-18** on the posterior midline.
→ **Du-20** is located 3 cun in a superior direction, on the vertex.

Needling

Transversely (subcutaneously) 0.5–1 cun

Actions/Indications

- Dispels Wind, especially internal Wind
- Opens the channel
- Calms the *shen*


3 cun
To Du-20
Du-18
1.5 cun
External
occipital
protuberance
Du-17
Midline


Sagittal suture
Parietal bone
Lambdoid suture
BL-9
Du-17
BL-9
Mastoid
process
Occipitomastoid
suture
Du-16
Occipital bone
External occipital
protuberance


Du-20
BL-8
Du-19
Du-18
G.B.-8
G.B.-19
BL-9
Du-17
Du-16
G.B.-20
G.B.-12
BL-10
Du-15


External
occipital
protuberance
Du-17
1.5 cun
Du-16

Behind the Crown HOUDING Du-19


Hairline
5 cun
Apex of the ear
Apex of the ear
Du-20
1.5 cun
Du-19
3 cun to Du-17 and 5.5 cun to hairline
Midline


5 cun
Du-20
Apex of the ear
Apex of the ear

Location

On the midline, 3 cun superior to → **Du-17** (directly superior to the external occipital protuberance) or 1.5 cun posterior to → **Du-20**.

How to find

This point is best located by using → **Du-20** as a reference point (at the junction of the vertical midline and a line connecting the apices of the ears). **Du-19** can then be located by palpating 1.5 cun in a posterior direction from → **Du-20**. **Or:** First, locate → **Du-17** superior the external occipital protuberance (→ 3.1.5), then locate **Du-19** on the midline, 3 cun superior to → **Du-17**.

Needling

Transversely (subcutaneously) 0.5–1 cun.

Actions/Indications

- Dispels Wind
- Opens the channel
- Calms the *shen*

Du-20 *Hundred Meetings* BAIHUI

Location

At the junction of a line connecting the apices of the ears and the midline, 5 cun from the anterior or 7 cun from the posterior hairline respectively.

How to find

Spreading hands technique (→ 2.3.3): Place the hands on both sides of the head, with the little fingers touching the apices of the ears. Join the thumbs on the midline and locate **Du-20** in shallow depression on the vertex of the head (alternative location method: use an elastic tape, with the midpoint marked on it). The symbolic counterpart to **Du-20** (as the highest point on the body and in contact with heaven) is → **KID-1**, the lowest part of the body and in contact with the earth.

Needling

0.5–1 cun transversely (subcutaneously) towards the posterior (reducing effect) or the anterior (tonifying effect). Caution: Apply pressure to head points after needle removal to avoid bleeding. Remember to remove the needle after treatment.

Actions/Indications

- Calms Wind, pacifies Yang, benefits the Brain and sensory organs, calms the *shen*
- Nourishes the Sea of Marrow; applying moxibustion raises the Yang

Special features

Meeting point with the BL, G.B., T.B. and LIV channels; Sea of Marrow point. Important point for descending the Yang (reducing needle techniques) or raising the Yang (tonifying needle techniques, moxibustion).


Little fingers on the apices of the ear
Du-20
Little fingers on the apices of the ear


5 cun
7 cun
Anterior hairline
5 cun
Du-20
Apex of the ear
Apex of the ear
7 cun to posterior hairline


Midline
Apex of the ear
Apex of the ear
Du-20



In Front of the Crown QIANDING **Du-21**


Hairline
3.5 cun
Apex of the ear
Du-21
Apex of the ear
1.5 cun
Du-20
Midline

Location

On the midline, 3.5 cun superior to the anterior hairline or 1.5 cun anterior to → **Du-20**.

How to find

First, locate → **Du-20** (at the junction of the vertical midline and a line connecting the apices of the ears) and, from there, measure 1.5 cun in an anterior direction. **Or:** Locate the anterior hairline (→ 3.1.1; the distance from the anterior hairline to → **Du-20** is 5 cun) and palpate 3.5 cun in a superior/posterior direction. There, locate **Du-21** on the midline.

Needling

Transversely (subcutaneously) 0.5–1 cun. Caution with infants whose fontanelle has not yet closed. Moxibustion possible.

Actions/Indications

- Dispels Wind and Dampness
- Opens the channel
- Calms the *shen*


BL-8
Du-20
G.B.-18
BL-7
Du-21
G.B.-17
BL-6
Du-22
G.B.-16
BL-5
Du-23
BL-3
G.B.-15
BL-4
Du-24
Hairline


Coronal suture
Frontal eminence
Parietal bone
Du-20
Sagittal suture
Vertex
Occipital bone

Ch05b-F10028.qxd 2/22/08 9:56 PM Page 520

Du-22 *Fontanelle Meeting* XINHUI

Location

On the midline, 2 cun superior to the anterior hairline.

How to find

First, locate the anterior hairline (➞ 3.1.1) and, from there, palpate 2 cun in a superior direction. There, locate **Du-22** on the midline. For reference: The distance from the anterior hairline to ➞ **Du-20** is 5 cun. **Or:** From ➞ **Du-20** (at the junction of the vertical midline and a line connecting the apices of the ears), measure 3 cun in an anterior direction and there locate **Du-22** on the midline.

Needling

Transversely (subcutaneously) 0.5–1 cun. Caution with infants whose fontanelle has not yet closed (**Du-22** is located on the anterior border of the fontanelle). Moxibustion possible.

Actions/Indications

- Dispels Wind
- Calms the *shen*


Hairline
2 cun
Du-22
3 cun
Apex of the ear
Apex of the ear
Du-20
Midline


5 cun
Du-20
Apex of the ear
Apex of the ear


BL-8
Du-20
G.B.-18
BL-7
Du-21
G.B.-17
BL-6
Du-22
G.B.-16
BL-5
Du-23
BL-3
G.B.-15
BL-4
Du-24
Hairline

Upper Star **SHANGXING** **Du-23**


Hairline
1 cun
Du- 23
4 cun
Apex of the ear
Apex of the ear
Du-20
Midline


G.B.-15
BL-5
Du-23
ST-8
G.B.-13
BL-4
Du-24
BL-3
G.B.-14
Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
Ex-HN-7
ST-1


BL-5
1 cun
ST-8

Location

On the midline, 1 cun superior to the anterior hairline or 4 cun anterior to → **Du-20**.

How to find

First, locate the anterior hairline (→ 3.1.1) and, from there, palpate 1 cun in a superior direction. There, locate **Du-23** on the midline. For reference: The distance from the anterior hairline to → **Du-20** is 5 cun.

Located on the same level is → **BL-5** (1.5 cun lateral to the midline).

Needling

Transversely (subcutaneously) 0.3–0.5 cun. Moxibustion possible.

Actions/Indications

- Dispels pathogenic factors (especially Wind and Heat) from the nose
- Dispels pathogenic factors (especially Heat) from the face
- Calms the *shen*

Ch05b-F10028.qxd 2/22/08 9:56 PM Page 522

Du-24 *Courtyard of the Spirit* SHENTING

Location

On the midline, 0.5 cun superior to the anterior hairline or 4.5 cun anterior to ➞ **Du-20**.

How to find

First, locate the anterior hairline (➞ 3.1.1) and, from there, palpate 0.5 cun in a superior direction. There, locate **Du-24** on the midline. For reference: The distance from the anterior hairline to ➞ **Du-20** (at the junction of the vertical midline and a line connecting the apices of the ears) is 5 cun.
Located on the same level (0.5 cun superior to the anterior hairline) are ➞ **BL-3/BL-4/G.B.-15/G.B.-13** (superior to the inner canthus of the eye/1.5 cun lateral to the midline/on the pupil line or 2.25 cun lateral to the midline/3 cun lateral to the midline). These distances refer to the proportional cun distance (➞ 2.2) between **Du-24** and ➞ **ST-8** (on the corner of the forehead), which equals 4.5 cun (1.5 cun lateral to the midline).

Needling

Transversely (subcutaneously) 0.3–0.5 cun. Moxibustion possible.

Actions/Indications

- Calms the *shen*
- Dispels (internal) Wind
- Clears pathogenic factors from the eyes and nose

Special features

Meeting point with the BL and ST channels. One of the major points for calming the *shen*.




Du-24
0.5 cun
Hairline
Midline


BL-8
Du-20
G.B.-18
BL-7
Du-21
G.B.-17
BL-6
Du-22
G.B.-16
BL-5
Du-23
BL-3
G.B.-15
BL-4
Du-24
Hairline


5 cun
Du-20
Apex of the ear
Apex of the ear

Ch05b-F10028.qxd 2/22/08 9:56 PM Page 523

White Crevice SULIAO Du-25




ST-8
Chewing still palpable
Temporalis


Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
Ex-HN-7
ST-1
ST-2
ST-7
G.B.-2
Ex-HN-8
L.I.-20
S.I.-18
L.I.-19
Du-26
ST-4

Location

In a depression on the tip of the nose.

How to find

As the name implies, **Du-25** can be located in a depression on the tip of the nose, which generally can be easily palpated.

Needling

0.2 cun vertically or transversely (subcutaneously) in a superior direction up to 1 cun. Or prick to bleed. Moxibustion controversial.

Actions/Indications

- Benefits the nose

Du-26 *Man's Middle* RENZHONG

Location

Below the nose, on the upper third of the philtrum. Note: *shuigou* (Water Grave) is an alternative name for this point.

How to find

Locate the philtrum, which forms a distinct groove on the midline between the root of the nose and the margin of the upper lip. Locate **Du-26** sligthly superior to the midpoint of the philtrum. → **L.I.-19** is located on the same level, 0.5 cun lateral to the midline.

Needling

0.3–0.5 cun obliquely in a superior direction. Caution: Needling this point may be painful.

Actions/Indications

- Revives consciousness
- Benefits the face and nose, eliminates (external) Wind
- Benefits the spine

Special features

Meeting point with the L.I. and ST channels; Sun Si Miao Ghost point. Major point for acute emergencies: Needle with strongly reducing technique. If no acupuncture needle is available, use a syringe or perform strong acupressure with the nail of the thumb or index finger, supporting the patient's chin with the same hand. Can be used in cases of needle collapse – first remove all other needles.







Extremity of the Mouth DUIDUAN **Du-27**



Location

On the midline, on the margin of the upper lip and the philtrum.

How to find

Location help: As the name implies, **Du-27** is located on the midline, at the junction of the upper lip and the philtrum.

Needling

Up to 0.3 cun obliquely in a superior direction. No moxibustion.

Actions/Indications

- Clears Heat
- Moistens the body
- Local point for the mouth
- Calms the *shen*

Du-28 *Gum Intersection* YINJIAO



Location

On the inside of the upper lip, at the junction of the frenulum and the upper gum.

How to find

Hold the upper lip in a raised position in order to reveal the frenulum and the upper gum. Locate **Du-28** on the midline, at the junction of the frenulum with the upper gum.

Needling

0.1–0.2 cun obliquely in a superior direction or prick to bleed. Do not puncture the frenulum.

Actions/Indications

- Clears Heat (especially from the eyes and the mouth)

Special features

As the name implies, meeting point with the *ren mai* and the ST channel

5.4 *Dai mai*

Synonym: Girdling Vessel

The extraordinary vessel *dai mai* is the only vessel (or channel) with a horizontal pathway (except for *luo*-connecting vessels).

Relationships (→ 1.7.3)

- **Yin/Yang:** *chong mai/dai mai*
- **Central/peripheral:** *dai mai/yang wei mai*. Regions supported by this pairing: lateral eye region as well as temporal region, ears, cheeks, occiput and shoulders. Opening point: **G.B.-41** (*zulinqi*), coupled point: **T.B.-5** (*waiguan*).

Pathway

The extraordinary vessel *dai mai* originates in the hypochondrium at the level of L2; according to many other authors it originates at → **LIV-13** (*zhangmen*) at the free end of the 11th rib. It encircles the waist of the body like a belt. As it does so it passes → **G.B.-26** (*dai mai*) at the level of the umbilicus and below the free end of the 11th rib, → **G.B.-27** (*wushu*) and → **G.B.-28** (*weidao*).



Meeting points with other channels



LIV-13 (*zhangmen*): Anterior and inferior to the free end of the 11th rib



G.B.-26 (*daimai*): On the lateral aspect of the waist, at the junction of a vertical line through the free end of the 11th rib and a horizontal line through the umbilicus, approximately 1.8 cun inferior to → **LIV-13**



G.B.-27 (*wushu*): In the depression medial to the anterior superior iliac spine, approximately level with Ren-4



G.B.-28 (*weidao*): Anterior and inferior to the anterior superior iliac spine, 0.5 cun anterior and inferior to G.B.-27

Connections with other channels/Organs

- Gall Bladder and Liver primary channels, Kidney divergent channel
- Kidney, Uterus

Clinical importance (→ 1.7.2, 1.7.3)

- **Controls** and **encircles** the horizontal channels like a belt
- **Connects** the upper and lower halves of the body at the waist
- **Regulates** vaginal discharge
- **Eliminates** Damp-Heat from the Lower Burner, especially from the genitalia
- **Controls** the *shaoyang* channels, especially the G.B. channel

5.5 *Yin wei mai*

Synonym: Yin Motility Vessel (Deadman), **Yin Heel Vessel** (Maciocia)

Relationships (→ 1.7.3)

- **Yin/Yang:** *yin wei mai*/*yang wei mai*
- **Central/peripheral:** *chong mai*/*yin wei mai*. Regions supported by this pairing: Heart, thorax, Stomach. Opening point: **P-6** (*neiguan*), coupled point: **SP-4** (*gongsun*).

Pathway

The extraordinary vessel *yin wei mai* originates in the hypochondrium at → **KID-9** (*zhubin*), 5 cun proximal to the prominence of the medial malleolus, ascends the medial aspect of the leg to the inguinal region, follows the Spleen and Liver primary channels, passing the points → **SP-12** (*chongmen*) and → **SP-13** (*fushe*). It then passes → **SP-15** (*daheng*) and → **SP-16** (*fuai*) and again meets with the Spleen and Liver primary channels at → **LIV-14** (*qimen*). The vessel then traverses the thoracic region, passes → **Ren-22** (*tiantu*) in the suprasternal fossa and follows the extraordinary vessel *ren mai* to → **Ren-23** (*lianqiao*) where it terminates.


Ren-23
Ren-22
Heart
LIV-14
SP-16
SP-15
SP-13
SP-12
KID-9

Meeting points with other channels


LIV-5
KID-9
KID-7
5 cun
KID-3

KID-9 (*zhubin*): 5 cun proximal to KID-3 and 2 cun posterior to the medial border of the tibia


Upper border of the pubic symphysis
SP-12
Symphysis
3.5 cun

SP-12 (*chongmen*): 3.5 cun lateral to the midline, level with the upper border of the pubic symphysis, lateral to the femoral artery


SP-13
Upper border of the pubic symphysis
0.7 cun
SP-12
Symphysis
0.5 cun
3.5 cun

SP-13 (*fushe*): 4 cun lateral to the anterior midline (mamillary line) and 0.7 cun superior to the upper border of the pubic symphysis


2 cun
4 cun
ST-25
SP-15

SP-15 (*daheng*): 4 cun lateral to the centre of the umbilicus


4 cun
SP-16
3 cun
SP-15

SP-16 (*fuai*): 3 cun superior to the centre of the umbilicus and 4 cun lateral to the anterior midline, on the mamillary line


5th intercostal space
6th intercostal space
LIV-14

LIV-14 (*qimen*): In the 6th intercostal space, on the mamillary line, 4 cun lateral to the midline.


Suprasternal fossa
Ren-22

Ren-22 (*tiantu*): 0.5 cun superior to the sternum, in the centre of the suprasternal fossa


Ren-23
Hyoid

Ren-23 (*lianquan*): On the anterior midline, superior to the upper border of the hyoid bone

Connections with other channels/organs

- Kidney, Spleen and Liver primary channels, *ren mai*
- Internal organs

Clinical importance (→ 1.7.2, 1.7.3)

- **Connects** and **regulates** all **Yin channels** of the body. It connects the KID, SP and LIV channels and the *ren mai* and dominates the **Interior** of the body (the internal organs).
- **Strengthens** Yin and Heart-Blood, especially in women
- **Balances** the emotions

5.6 *Yang wei mai*

Synonym: Yang Motility Vessel (Deadman), **Yang Heel Vessel** (Maciocia)

Relationships (→ 1.7.3)

Yin/Yang: *yin wei mai*/*yang wei mai*
Central/peripheral: *dai mai*/*yang wei mai*. Regions supported by this pairing: Lateral eye region, temporal region, ears, cheeks, neck and shoulders. Opening point: **T.B.-5** (*waiguan*), coupled point: **G.B.-41** (*zulinqi*).

Pathway

The extraordinary vessel *yang wei mai* originates at → **BL-63** (*jinmen*) in the depression posterior to the tuberosity of the 5th metatarsal bone, runs anterior to the lateral malleolus, passes → **G.B.-35** (*yangjiao*), ascends the lateral aspect of the leg, passes the hip, ascends the posterior aspect of the costal region to the shoulder, passes → **S.I.-10** (*naoshu*), → **T.B.-15** (*tianliao*), → **G.B.-21** (*jianjing*) and ascends the neck. The vessel then ascends anterior to the ear (according to some authors, for example Solinas et al. (1998), posterior to the ear) to the forehead, passing → **ST-8** (*touwei*), → **G.B.-13** (*benshen*) and → **G.B.-14** (*yangbai*). It then runs with the G.B. channel from **G.B.-15** to **G.B.-20** on the occiput, passing → **G.B.-15** (*toulinqi*), → **G.B.-16** (*muchuang*), → **G.B.-17** (*zhengying*), → **G.B.-18** (*chengling*), → **G.B.-19** (*naokong*) and → **G.B.-20** (*fengchi*). The vessel then continues from **G.B.-20** to the posterior midline, passing → **Du-16** (*fengfu*) and → **Du-15** (*yamen*), where the vessel terminates.



Meeting points with other channels



BL-63 (*jinmen*): In a depression anterior and inferior to → **BL-62** between the calcaneus and the cuboid bone, proximal to the tuberosity of the 5th metatarsal bone



G.B.-35 (*yangjiao*): 7 cun proximal to the highest prominence of the lateral malleolus, on the posterior border of the fibula


S.I.-10
Border of the deltoid

S.I.-10 (*naoshu*): With the arm adducted on a line extending in a superior direction from the posterior axillary fold, on the lower border of the scapular spine


Spinous process C7
G.B.-21
T.B.-15
1/2
1/2

T.B.-15 (*tianliao*): At the midpoint of an imaginary line between the spinous process of the C7 and the lateral extremity of the acromion


Spinous process C7
G.B.-21
1/2
T.B.-15

G.B.-21 (*jianjing*): At the highest point of the shoulder, midway between the lower border of the spinous process of C7 and the lateral extremity of the acromion



ST-8 (*touwei*): At the temporal corner of the forehead, on the border of the temporalis muscle and 0.5 cun within the anterior hair line or 4.5 cun lateral to the anterior midline (Du-24)


0.5 cun
ST-8
Hairline
G.B.-13

G.B.-13 (*benshen*): 3 cun lateral to → **Du-24** (on the midline, 0.5 cun superior to the anterior hairline)


G.B.-14
1 cun
1/3

G.B.-14 (*yangbai*): When looking straight ahead on the pupil line, approximately 1 cun superior to the midpoint of the eyebrow, at the junction of the eminence and the superciliary arch


0.5 cun
ST-8
G.B.-15
Hairline

G.B.-15 (*toulinqi*): When looking straight ahead superior to the pupil, 0.5 cun superior to the anterior hairline


G.B.-16
2.25 cun
Apex of the ear
3.5 cun
Apex of the ear

G.B.-16 (*muchuang*): 1.5 cun superior to the anterior hairline, on the pupil line, or 2.25 cun lateral to the midline (= midway between → **Du-24** and → **ST-8**)


G.B.-17
2.25 cun
Apex of the ear
Apex of the ear
2.5 cun
Du-20

G.B.-17 (*zhengying*): 2.5 cun superior to the anterior hairline and 2.25 cun lateral to the midline


Apex of the ear
Apex of the ear
G.B.-18
2.25 cun
1 cun
Du-20

G.B.-18 (*chengling*): 4 cun superior to the anterior hairline or 1 cun anterior to → **Du-20**, 2.25 cun lateral to the midline


External occipital protuberance
2.25 cun
Du-17
G.B.-19
1.5 cun

G.B.-19 (*naokong*): On the occiput, level with the upper border of the external occipital protuberance (→ **Du-17**), 2.25 cun lateral to the midline


Occipital bone
G.B.-20
Lower border of the occiput
G.B.-20
Axis
BL-10
Sternocleido-mastoid

G.B.-20 (*fengchi*): On the lower border of the occipital bone, in the depression between the origins of the sternocleidomastoid and trapezius


Atlas
External occipital protuberance
Du-16
Occipital bone
G.B.-20
Lower border of the occiput
G.B.-20

Du-16 (*fengfu*): On the posterior midline, directly below the external occipital protuberance, in the depression between the origins of the trapezius


Occipital bone
G.B.-20
Lower border of the occiput
G.B.-20
Axis
BL-10
Sternocleido-mastoid
Du-15

Du-15 (*yamen*): On the occiput, on the posterior midline, in the depression between the 1st (atlas) and 2nd cervical vertebrae, approximately 0.5 cun below → **Du-16**

Connections with other channels/Organs

- BL, G.B., ST, S.I., T.B. and L.I. primary channels, *du mai*

Clinical importance

- **Connects** and **regulates** all **Yang channels** of the body. It connects the BL, G.B., ST, S.I., T.B. and L.I. channels as well as the *du mai* and controls the Exterior of the whole body (especially the *taiyang* and *shaoyang* channels)
- Harmonises the Nutritive Qi (*ying qi*) and the Defensive Qi (*wei qi*)
- Expels Exterior Wind-Cold, especially with *shaoyang*-syndrome.

5.7 *Yin qiao mai*

Synonym: Yin Motility Vessel (Deadman), **Yin Heel Vessel** (Maciocia)

Relationships (→ 1.7.2, 1.7.3)

- **Yin/Yang:** *yin qiao mai*/*yang qiao mai*
- **Central/peripheral:** *ren mai*/*yin qiao mai*. Regions supported by this pairing: Face, throat, thorax, Lung, diaphragm, abdomen. Opening point: **KID-6** (*zhaohai*), coupled point: **LU-7** (*lieque*).

Pathway

The extraordinary vessel *yin qiao mai* originates at → **KID-2** (*rangu*) inferior to the navicular tuberosity (according to some authors it only begins at → **KID-6**), runs to → **KID-6** (*zhaohai*) and → **KID-8** (*jiaoxin*), ascends the posteromedial aspect of the leg to the external genital region, ascends the abdomen to the thorax, crosses the supraclavicular fossa and continues to the throat and face. It then runs to the inner canthus of the eye where it connects with the Bladder primary channel and the *yang qiao mai* at → **BL-1** (*jingming*). It then ascends to enter the Brain.



Meeting points with other channels



KID-2 (*rangu*): In a depression at the anterior/inferior border of the navicular bone, at the border of the 'red and white' skin



KID-6 (*zhaohai*): In the depression inferior to the highest prominence of the medial malleolus, over the joint space between the talus and calcaneus



KID-8 (*jiaoxin*): 2 cun proximal to the highest prominence of the medial malleolus, posterior to the border of the tibia



BL-1 (*jingming*): In a depression 0.1 cun superior and medial to the inner canthus of the eye

Connections with other channels/Organs

- Kidney and Bladder primary channels
- Brain

Clinical importance (→ 1.7.2, 1.7.3)

- Together with the *yang qiao mai* controls the musculature of the lower extremities
- Together with the *yang qiao mai* regulates the opening and closing of the eyes
- Regulates the functioning of the Brain
- Removes stagnation (of Qi, Blood or Dampness) in the Lower Burner, especially in the Uterus in women

5.8 *Yang qiao mai*

Synonym: Yang Motility Vessel (Deadman), **Yang Heel Vessel** (Maciocia)

Relationships (→ 1.7.3)

- **Yin/Yang:** *yin qiao mai/yang qiao mai*
- **Central/peripheral:** *du mai/yin qiao mai*. Regions supported by this pairing: Inner canthus of the eye, occiput, shoulders and back. Opening point: **BL-62** (*shenmai*), coupled point: **S.I.3** (*houxi*)).

Pathway

The extraordinary vessel *yang qiao mai* originates at → **BL-62** (*shenmai*) below the prominence of the lateral malleolus, curves briefly around the malleolus to → **BL-61** (*pucan*) and ascends anterior to the Achilles tendon to → **BL-59** (*fuyang*), travels up the lateral aspect of the leg, crosses the hip, passing → **G.B.-29** (*juliao*), ascends the flanks and the posterior aspect of the shoulders, passes → **S.I.10** (*naoshu*), continues to → **L.I.-15** (*jianyu*) and runs in a curve to → **L.I.-16** (*jugu*), crosses the supraclavicular fossa, ascends the throat, according to some authors passing → **ST-9** (*renying*), and reaches the face. Here the vessel passes the points → **ST-4** (*dicang*) and → **ST-3** (*juliao*); according to some authors also → **ST-2** (*sibai*) and → **ST-1** (*chengqi*) in the infraorbital region. It then reaches → **BL-1** (*jingming*), where it meets the extraordinary vessel *yin qiao mai*, ascends the forehead to the vertex and descends posteriorly to → **G.B.-20** (*fengchi*); according to the *Nan Jing* and the *Nei Jing* it also reaches → **Du-16** (*fengfu*), where it enters the Brain.



* According to Deadman et al 1998.

Intersection points with other channels



BL-62 (*shenmai*): In a depression directly inferior to the highest prominence of the lateral malleolus, over the joint space between the talus and calcaneus



BL-61 (*pucan*): In a depression on the calcaneus, approximately 1.5 cun inferior to → **BL-60**


BL-59
Highest prominence of the lateral malleolus
3 cun
Anterior border of the Achilles tendon

BL-59 (*fuyang*): 3 cun superior to → BL-60 (in the depression between the highest prominence of the lateral malleolus and the Achilles tendon)


G.B.-29
1/2
Greater trochanter

G.B.-29 (*juliao*): At the midpoint of a line connecting the anterior superior iliac spine and the greater trochanter, at the anterior border of the iliac crest


S.I.-10
Border of the deltoid

S.I.-10 (*naoshu*): With the arm adducted on a line extending in a superior direction from the posterior axillary fold, on the lower border of the scapular spine


Acromioclavicular joint
T.B.-14
L.I.-15

L.I.-15 (*jianyu*): In the depression distal and anterior to the acromion, between the clavicular and acromial portions of the deltoid muscle


Clavicle
L.I.-16
AC joint
Acromion

L.I.-16 (*jugu*): In a depression between the acromial extremity of the clavicle and the junction of the scapular spine and the acromion


ST-9
L.I.-18
S.I.-16
Laryngeal prominence

ST-9 (*renying*): Approximately 1.5 cun lateral to the anterior midline, level with the laryngeal prominence, at the anterior border of the sternocleidomastoid



ST-4 (*dicang*): When looking straight ahead on the pupil line, approximately 0.4 cun lateral to the corner of the mouth



ST-3 (*juliao*): When looking straight ahead, directly below the centre of the pupil, level with the lower border of the ala nasi


Infraorbital margin
ST-2

ST-2 (*sibai*): When looking straight ahead, directly below the centre of the pupil, in the depression at the infraorbital foramen


Orbital margin
ST-1 (below the pupil)

ST-1 (*chengqi*): With the eyes looking straight forward, directly below the centre of the pupil, between the eyeball and the infraorbital ridge



BL-1 (*jingming*): In a depression 0.1 cun superior and medial to the inner canthus of the eye


Occipital bone
G.B.-20
G.B.-20
Lower border of the occiput
Axis
BL-10
Sternocleido-mastoid

G.B.-20 (*fengchi*): On the lower border of the occipital bone, in the depression between the origins of the sternocleidomastoid and trapezius


Atlas
Du-16
External occipital protuberance
Occipital bone
G.B.-20
G.B.-20
Lower border of the occiput

Du-16 (*fengfu*): On the posterior midline, directly below the external occipital protuberance, in the depression between the origins of the trapezius

Connections with other channels/Organs

- Kidney, Bladder, Gall Bladder, Stomach, Large Intestine and Small Intestine primary channels
- Brain

Clinical importance (→ 1.7.2, 1.7.3)

- Together with the *yin qiao mai* controls the musculature of the lower extremities
- Together with the *yang qiao mai* regulates the opening and closing of the eyes
- Regulates the functioning of the Brain, eliminates internal and external Wind from the head
- Removes obstructions and stagnation from the spine, especially after traumatic injuries

6 Extra Points

Claudia Focks, Ulrich März

Besides the 361 classic acupuncture points located on the channels there are a number of **Ex**tra Points (**Ex**), located with a few exceptions outside the pathways of the primary channels. In 1991, a new nomenclature for these extra points was confirmed in the People's Republic of China, listing 48 points (*The Location of Acupoints, State Standard of the People's Republic of China*, Foreign Languages Press, Beijing, 1990).

In the past, authors have developed ways of identifying the extra points by names or numbers:

- Nguyen Van Nghi; König and Wancura: '**P**unkte **a**ußerhalb der **M**eridiane' (points not on meridians) (PaM) and '**N**eu-**P**unkte' (new points) (NP); Schnorrenberger (wall charts translated from the Chinese language) uses the same numbering system as Nguyen Van Nghi but refers to the **PaM** as '**Z**usatz**p**unkte' (additional points) (ZP) and also as '**N**eu-**P**unkte' (NP)
- Shanghai College for Traditional Medicine (*Acupuncture – a Comprehensive Text*, English translation by O'Connor J, Bensky D, which also forms the foundation for Deadman et al. 1998 and Ellis and Wiseman 1991): **M**iscellaneous (M) and **N**ew (N) Points
- Hempen 1995: '**E**xtrapunkte' (extra points) (Ex).

The following tables give an overview of the most commonly used extra points also listed in this atlas.

6.1 Extra Points: Head and Neck (EX-HN)


Ex-HN-2 (*dangyang*)
Ex-HN-3 (*yintang*)
Ex-HN-4 (*yuyao*)
Ex-HN (*shangming*)
Ex-HN-7 (*qiuhou*)
Ex-HN-8 (*shangyingxiang*)
Ex-HN (*jiachengjiang*)
Ex-HN (*keliao*)


Ex-HN-6 (*erjian*)
T.B.-23
Ex-HN-5 (*taiyang*)
G.B.-1
Ex-HN-8 (*shangyingxiang*)
Ex-HN (*jiachengjiang*)
Ex-HN (*keliao*)
T.B.-17
G.B.-20
Ex-HN (*anmian 2*)
Ex-HN (*anmian 1*)
Ex-HN-14 (*yiming*)

English abbreviation (standard)	***Pinyin* name**	**Nguyen Van Nghi, König and Wancura, Schnorrenberger**	**Shanghai College**	**Ex (Hempen)**
Ex-HN-1	*sishencong*	PaM or ZP1	M-HN-1	Ex6
Ex-HN-2	*dangyang*		M-HN	
Ex-HN-3	*yintang*	PaM or ZP3	M-HN-3	Ex1
Ex-HN-4	*yuyao*	PaM or ZP6	M-HN-6	
Ex-HN-5	*taiyang*	PaM or ZP9	M-HN-9	Ex2
Ex-HN-6	*erjian*	PaM or ZP10	M-HN-10	
Ex-HN-7	*qiuhou*	PaM or ZP8	M-HN-8	
Ex-HN-8	*shangyingxiang/bitong*	NP12 (PaM or ZP14*)	M-HN-14	Ex3
Ex-HN-9	*neiyingxiang*		M-HN-35	
Ex-HN-10	*juquan*		M-HN-36	
Ex-HN-11	*haiquan*		M-HN-37	
Ex-HN-12	*jinjin*[†]	PaM or ZP20	M-HN-20	
Ex-HN-13	*yuye*[†]	PaM or ZP20	M-HN-20	
Ex-HN-14	*yiming*	PaM or ZP13	M-HN-13	Ex4
Ex-HN-15	*jing(bailao)*	PaM or ZP30	M-HN-30	
Further extra points				
Ex-HN	*shangming*		N-HN-4	
Ex-HN	*anmian*[‡]	NP27 and 28 (*anmian*[‡]1 und 2)	N-HN-54 M-HN-54 (Deadman)	Ex5
Ex-HN	*jiabi*	PaM or ZP15		
Ex-HN	*jiachengjiang*	PaM or ZP18 (*heliao/keliao*)	M-HN-18	Ex7
Ex-HN	*chonggu/zhuidong*	PaM or ZP31	M-HN-31	
Ex-HN	*jingbi*		M-HN-41	

---

[*] Nguyen Van Nghi and Schnorrenberger describe a different location for the point with this *pinyin* name (location: 0.5 cun inferior to the inner canthus of the eye); the 'standard' location is described under NP12 as '*bitong*' or '*bicong*'.

[†] The Shanghai nomenclature and also Nguyen Van Nghi, König and Wancura and Schnorrenberger describe the extra points *jinjin* and *yuye* as a pair of points.

[‡] There exists differing information regarding the extra point *anmian*; for example the Shanghai College (and Wiseman) describe *anmian* as N-HN-54 (in Deadman: M-HN-54) with the following location: midway between G.B.-20 and T.B.-17; Nguyen Van Nghi and Schnorrenberger describe *anmian* as two new points with the following locations: *anmian* 1 is located midway between T.B.-17 and *yiming* (PaM13 or Ex-HN-14), *anmian* 2 midway between G.B.-20 and *yiming* (*anmian* according to the Shanghai College is shown on the point page; the location of *anmian* 1 and 2 according to Nguyen and Schnorrenberger in figure 6.1).

Ch06a-F10028.qxd 2/23/08 1:24 PM Page 539

Four Alert Spirit SISHENCONG Ex-HN-1


Ex-HN-1
(*sishencong*)
Du-20

Location

A group of four points, each located 1 cun from → **Du-20** (anterior, posterior and lateral) (→ 3.1.1).

How to find

First, locate → **Du-20** on the highest point of the head, at the junction of a line connecting the apices of the ears and the vertical midline. Alternative location method: Locate → **Du-20** 5 cun superior to the anterior and 7 cun superior to the posterior hairline. **Ex-HN-1** (*sishencong*) forms a star-shaped group of points around → **Du-20**: two points are located at a distance of 1 cun each on the *du mai*, whereas the other two are located 1 cun each from → **Du-20** in a lateral direction.

Needling

0.5–1 cun obliquely towards → **Du-20**

Actions/Indications

- Calm the *shen*
- Alleviate pain
- Calm Wind
- Benefit the eyes and ears


5 cun
7 cun
Anterior hairline
5 cun
Du-20
Apex of the ear
Apex of the ear
7 cun to the posterior hairline

Ex-HN-2 *Above the Yang* DANGYANG

Location

With the patient looking straight ahead, vertically above the pupil, 1 cun above the anterior hairline.

How to find

In patients with a receding hairline, the original hairline can often be recognized by a change in skin texture. Location help (➞ 3.1.1): Ask the patient to frown, as this often reveals the site of the original hairline. Ask the patient to look straight ahead, then locate **Ex-HN-2** by measuring 1 cun from the hairline, on a vertical line through the pupil.
➞ **G.B.-14** is also located on the pupil line (on the lower border of the frontal eminence). Located on the same level (1 cun above the hairline) are ➞ **BL-5** (more medial, 1.5 cun from the anterior midline) and ➞ **Du-23** (on the anterior midline).

Needling

0.5 cun transversely (subcutaneously) towards the site of the disorder/pain.

Actions/Indications

- Dispels Wind and Heat, alleviates pain


1 cun
Ex-HN-2 (*Dangyang*)
GB.-14


Ex-HN-3
(*yintang*)
Frontal
squama
BL-2
Ex-HN-4
(*yuyao*)
G.B.-14
Ex-HN-4
(*yuyao*)
T.B.-23


ST-8
G.B.-15
BL-3
G.B.-13
BL-4
Du-24
Anterior
hairline


1 cun
1/3
G.B.-14


Du-24
BL-5
1 cun
ST-8

Hall of Impression YINTANG **Ex-HN-3**


Ex-HN-3
(*yintang*)

Location

On the anterior midline (*du mai*), between the eyebrows.

How to find

Locate the glabella (→ 3.1.1), a smooth surface on the frontal bone, directly above the root of the nose, between the superciliary arches. Then locate **Ex-HN-3** (*yintang*) in its centre, on the midline and between the medial extremities of the eyebrows. Located along the superciliary arches (from medial to lateral) are → **BL-2,** → **Ex-HN-4** (*yuyao*) and → **T.B.-23**.

Needling

Pinching-skin method: With the thumb and index finger, form a skin fold above the point and insert the needle 0.3–0.5 cun transversely from superior to inferior into the fold, towards the root of the nose. Alternative methods: Oblique or transverse (subcutaneous) insertion towards the eyebrows (→ **BL-2**) or prick to bleed.

Actions/Indications

- Calms the *shen*
- Benefits the nose
- Eliminates (internal) Wind
- Opens the channel, alleviates pain

Special features

Commonly used extra point with a harmonising effect




G.B.-14
Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
ST-1
Ex-HN-7
ST-2
ST-7
G.B.-2
Ex-HN-8
L.I.-20
S.I.-18


G.B.-14
G.B.-14
Ex-HN-4
(*yuyao*)
Glabella
Ex-HN-3
(*yintang*)
T.B.-23
BL-2

Ex-HN-4 *Fish Waist* **YUYAO**

Location

In the centre of the eyebrow, with the eyes looking straight ahead directly above the pupil.

How to find

With the patient looking straight ahead, palpate the eyebrow directly above the pupil, superior to the supraorbital ridge. There, locate **Ex-HN-4** (*yuyao*) in a small depression on the superciliary arch.

Needling

0.3–0.5 cun vertically or obliquely towards the eye.

Actions/Indications

- Benefits the eyes
- Dispels pain


Pupil line
Orbital margin
Ex-HN-4 (*yuyao*)
Ex-HN (*shangming*)


G.B.-14
G.B.-14
Ex-HN-3 (*yintang*)
Ex-HN-4 (*yuyao*)
Glabella
T.B.-23
BL-2


G.B.-14
Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
ST-1
Ex-HN-7
ST-2
ST-7
Ex-HN-8
G.B.-2
L.I.-20
S.I.-18


Ex-HN-3 (*yintang*)
Frontal squama
BL-2
Ex-HN-4 (*yuyao*)
G.B.-14
Ex-HN-4 (*yuyao*)
T.B.-23

Supreme Yang TAIYANG **Ex-HN-5**


Lateral eyebrow
1 cun
Ex-HN-5
Lateral canthus of the eye




G.B.-14
G.B.-8
T.B.-20
T.B.-23
Ex-HN-5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
Ma 7
G.B.-2
S.I.-18
G.B.-20
T.B.-17
G.B.-12
Ex-HN (*anmian*)



Location

On the temple, in a depression approximately 1 cun lateral to the midpoint of a line connecting the lateral extremity of the eyebrow and the outer canthus of the eye.

How to find

On the temple, first, draw a line between the lateral extremity of the eyebrow and the outer canthus of the eye. Next, palpate from the midpoint of this line in a lateral direction, until you can feel a distinct depression in the temporal bone. **Ex-HN-5** (*taiyang*) is located in the centre of this depression. This point tends to be pressure-sensitive, especially with temporal headaches. Patients often get relief by using acupressure on this point.

Needling

0.5–0.6 cun vertical insertion into the temporal muscle or obliquely in a lateral direction or transversely (subcutaneously) towards → **G.B.-8.** This point often bleeds when needled. Prick to bleed to drain Heat.

Actions/Indications

- Eliminates Wind, clears Heat, reduces swellings, opens the channel, alleviates pain

Special features

One of the most important and most commonly used extra points, especially with headaches

Ex-HN-6 *Tip of the Ear* ERJIAN

Location

On the apex of the ear, on the helix.

How to find

Fold the ear anteriorly, so that the posterior portion of the upper helix covers its anterior part. The point is located at the highest point of the fold. This is also the location of the auricular point **78**.

Needling

Vertically 0.1–0.2 cun. Some authors advise to bleed this point for Heat conditions, but this is not recommended owing to the danger of causing an otic haematoma. Indirect moxibustion for vision disorders.

Actions/Indications

- Clears Heat, alleviates pain, benefits the eyes and the throat



Behind the Ball QIUHOU Ex-HN-7


Orbital margin
Ex-HN-7
(*qiuhou*)
1/4
1/4
1/2


BL-3
G.B.-14
Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
ST-1
Ex-HN-7
ST-2
ST-7
G.B.-2
Ex-HN-8
L.I.-20


G.B.-14
G.B.-14
Ex-HN-3
(*yintang*)
Ex-HN-4
(*yuyao*)
Glabella
T.B.-23
BL-2

Location

On the lower border of the orbit, at the junction of the lateral quarter and the medial three quarters.

How to find

Divide the horizontal extension of the diameter of the orbit in quarters. Then locate the point at the junction of the first and second lateral quarters, slightly superior to the border of the orbit.

Needling

Ask the patient to look upward and gently push the eyeball upward, away from the lower eyelid. Slowly insert the needle 0.5–1 cun into the fatty tissue immediately above the bone (orbit). Caution: Do not injure the eyeball and the periosteum. Avoid the venous plexus and arteries! Pay attention to any pain from needling. No needle manipulation! After removal of the needle, compress the site for 10 minutes. Haematomas may still occur (inform the patient prior to needling). Moxibustion is contraindicated. Alternative, less difficult points for eye disorders: **BL-2, T.B.-23**, **G.B.-1**, **ST-2, Ex-HN-5** (*taiyang*), **Ex-HN-4** (*yuyao*).

Actions/Indications

- Disorders of the eyes

Ex-HN-8 *Upper* Yingxiang SHANGYINGXIANG

Location

At the upper end of the nasiolabial groove, at the junction of the maxilla and the nasal cavity. Note: *bitong* (Clear Nose) is an alternative name for this point.

How to find

At the upper end of the nasiolabial groove, palpate for the bony margin of the nasal cavity. Here, **Ex-HN-8** (*shangyingxiang* or *bitong*) is located at the junction of the nose and the cheek.

Needling

0.3–0.5 cun vertically towards the centre of the nasal cavity.

Actions/Indications

- Clears Heat, opens the nasal passages


Ex-HN-8 (*bitong*)
Nasolabial groove


Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
ST-1
Ex-HN-7
ST-2
ST-7
Ex-HN-8
G.B.-2
L.I.-20
S.I.-18
L.I.-19
Du-26


Ex-HN-8
(*bitong*)
Nasolabial groove
L.I.-20
Maxilla
(upper
jaw)

Inner Yingxiang NEIYINGXIANG Ex-HN-9


Ex-HN-9 *(neiyingxiang)*
(inside the nose)
Nasolabial groove


Ex-HN-8 *(bitong)*
Nasolabial groove

Location

In the nasal cavity, at the junction of the nasal bone and the nasal cartilage.

How to find

This point lies 'opposite' the external point → **Ex-HN-8** (*shangyingxiang* or *bitong*), which is located at the upper end of the nasolabial groove.

Needling

Prick to bleed with a needle, lancet or three-edged needle. Caution: Contraindicated in patients with bleeding disorders (or taking anticoagulants). Needling may be painful!

Actions/Indications

- Clears Heat, drains Fire

Ex-HN-10 *Gathering Spring* JUQUAN

Location

With maximal extension of the tongue, in the centre of the tongue body.

How to find

With maximal extension of the tongue in the centre of the tongue body.

Needling

Vertically 0.2 cun. Needling may be painful!

Actions/Indications

- Deviation of the tongue, impaired mobility or atrophy of the musculature of the tongue: for example, after a stroke or with loss of sense of taste



Sea Spring HAIQUAN Ex-HN-11


Ex-HN-11
(haiquan)

Location

Below the tongue, in the centre of the frenulum, between the points → **Ex-HN-12** (*jinjin*) and → **Ex-HN-13** (*yuye*).

How to find

Ask the patient to roll their tongue upward to reveal the frenulum. To avoid injury to the frenulum, this point should be located at the base of the frenulum.

Needling

Vertically 0.2 cun. Remove needle immediately after short stimulation. Needling may be painful!

Actions/Indications

- Mouth and tongue ulcers, hiccups


Ex-HN-12
(jinjin)
Ex-HN-13
(yuye)


Ex-HN-12
(jinjin)
Ex-HN-13
(yuye)

Ex-HN-12 *Golden Liquid* JINJIN



Location

On the underside of the tongue, on the lingual vein to the left of the frenulum.

How to find

Ask the patient to roll their tongue upward to reveal the lingual veins.

Needling

Prick to bleed: Briefly puncture with a needle, lancet or three-edged needle and let bleed. Often used together with → **Ex-HN-13** (*yuye*). Caution: Contraindicated with bleeding disorders or in patients taking anticoagulant medication.

Actions/Indications

- Dispels Heat and Wind

Jade Fluid YUYE **Ex-HN-13**



Location

On the underside of the tongue, on the great lingual vein to the right of the frenulum.

How to find

Ask the patient to roll their tongue upward to reveal the lingual veins.

Needling

Prick to bleed: Briefly puncture with a needle, lancet or three-edged needle and let bleed. Often used together with → **Ex-HN-12** (*jinjin*). Caution: Contraindicated with bleeding disorders or in patients taking anticoagulant medication.

Actions/Indications

- Dispels Heat and Wind

Ex-HN-14 *Eye Brightening* YIMING

Location

At the junction of the head and the occiput, posterior to the mastoid bone.

How to find

Ex-HN-14 (*yiming*) is located on a line connecting → **T.B.-17** (below the earlobe, between the maxilla and the mastoid) and → **G.B.-20** (at the junction of the occiput and the neck, in the centre of the dorsolateral depression). From → **T.B.-17**, measure 1 cun towards the posterior and there locate *yiming* posterior to the mastoid.

Located slightly superior and posterior to *yiming* is → **Ex-HN** (*anmian*), in the corner between the mastoid and the occiput.

Needling

Vertically 0.5–1 cun

Actions/Indications

- Disorders of the eyes and ears, dizziness, insomnia


1 cun
G.B.-20
T.B.-17
Ex-HN-14
(yiming)


Supratragic notch
Tragus
Intertragic notch
T.B.-22
T.B.-21
S.I.-19
G.B.-2
T.B.-17
Transverse process of the atlas
Mastoid process
Ex-HN
(anmian)
Ex-HN-14
(yiming)
G.B.-12


Du-18
G.B.-8
G.B.-19
BL-9
Du-17
G.B.-20
Du-16
G.B.-12
BL-10
Du-15


Occipital bone
G.B.-20
Lower border of the occiput
G.B.-20
Axis
BL-10
Sternocleido-mastoid


Mastoid process
Occipital bone
anmian
G.B.-12
Ex-HN-14
(yiming)

Hundred Taxations JINGBAILAO/BAILAO **Ex-HN-15**


1 cun
Ex-HN-15 (*jingbailao*)
C6
2 cun
C7
T1
Du-14

Location

2 cun superior to the lower border of the spinous process of the 7th cervical vertebra (C7) and 1 cun lateral to the midline.

How to find

For locating C7, see → 3.4.1. → **Du-14** (*dazhui*) is located below the spinous process of C7. From there, measure 2 cun in a superior and 1 cun in a lateral direction.

Needling

Vertically 0.5–0.8 cun

Actions/Indications

- Dispels Wind and Dampness
- Opens the channel


Extension and
flexion of the head
2 fingers on the
spinous processes
of C6 and 7
G.B.-21
S.I.-15
Du-14


Spinous process C7
Du-14
Medial base of
scapular spine

Ex-HN *Upper Brightness* SHANGMING

Location

Directly superior to the pupil, below the margin of the orbit.

How to find

With the patient looking straight ahead, palpate for the margin of the orbit directly above the pupil. **Ex-HN** (*shangming*) is located between the upper margin of the orbit and the eyeball.

Needling

Gently push the eyeball downward. Slowly insert the needle 0.5–1 cun vertically into the fatty tissue immediately below the bone (orbit). Caution: Pay attention to any pain from needling. No manipulation! After removal of the needle, compress the site for 10 minutes. Haematomas may still occur (inform the patient prior to needling). Alternative points with less risk of complications are **BL-2, T.B.-23**, **G.B.-1, ST-2, Ex-HN-5** (*taiyang*), **Ex-HN-4** (*yuyao*).

Actions/Indications

- Disorders of the eyes


G.B.-14
Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
ST-1
Ex-HN-7
ST-2
ST-7
Ex-HN-8
G.B.-2
L.I.-20
S.I.-18


Pupil line
Orbital margin
Ex-HN-4 (yuyao)
Ex-HN (shangming)


G.B.-14
G.B.-14
Ex-HN-4 (yuyao)
Glabella
Ex-HN-3 (yintang)
T.B.-23
BL-2




Eyebrow
1 cun
Ex-HN-5
Lateral canthus of the eye


Orbital margin
ST-2

Peaceful Sleep ANMIAN Ex-HN


T.B.-17
Transverse process of the atlas
Mastoid process
Ex-HN (*anmian*)
Ex-HN-14 (*yiming*)
G.B.-12
Sternocleidomastoid


T.B.-23
Ex-HN-5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
ST-7
G.B.-2
S.I.-18
G.B.-20
T.B.-17
G.B.-12
Ex-HN (*anmian*)
ST-5
ST-6
S.I.-17
T.B.-16
Ren-23
L.I.-18
S.I.-16
ST-9
L.I.-17


Mastoid process
Occipital bone
anmian
G.B.-12
Ex-HN-14 (*yiming*)

Location

Posterior to the ear, between → **T.B.-17** and → **G.B.-20**, posterior to the mastoid process.

How to find

First, locate → **T.B.-17** (directly below the earlobe, in the depression between the lower jaw and the mastoid process (→ 3.1) that forms when the mouth is open). Next, locate → **G.B.-20** on the lower border of the occiput, in the depression between the origins of the sternocleidomastoid and trapezius muscles. Locate **Ex-HN** (*anmian*) approximately midway between these two points, slightly posterior to the mastoid bone and superior to → **G.B.-12**, in a depression on the lower border of the occiput.

Needling

0.5–1 cun vertically or obliquely towards → **T.B.-17** (*yifeng*) or → **G.B.-20** (*fengchi*).

Actions/Indications

- Calms the *shen*

Special features

Important calming point for sleeping disorders. This extra point is not part of the WHO classification of extra points.


Great auricular nerve
Major occipital nerve
External jugular vein
Transverse cervical nerve

Ex-HN *Cheek Centre* JIALI



Location

Inside the mouth, on the mucosa of the cheek, 1 cun posterior to the corner of the mouth.

How to find

Locate this point on the mucosa of the cheek, 1 cun posterior to the corner of the mouth.

Needling

0.3–0.5 cun obliquely in a posterior direction, prick to bleed.

Actions/Indications

- Clears Heat
- For inflammations of the mouth and throat, for gastritis

Adjacent to Container of Fluids JIACHENGJIANG Ex-HN


Ex-HN (*jiachengjiang*)
Ren-24
1 cun
Mentolabial groove


L.I.-19
Du-26
ST-4
ST-5
Ex-HN
Ren-4

Location

1 cun lateral to the centre of the mentolabial groove.

How to find

This point is located on the mental foramen. → **Ren-24** (*chengjiang*) is located in the centre of the mentolabial groove.

Needling

0.3–0.5 cun vertically or up to 1 cun obliquely towards the mental foramen.

Actions/Indications

- Dispels Wind, opens the channel

Ex-HN

Prominent Bone CHONGGU ZHUIDONG

Location

Below the spinous process of the 6th cervical vertebra (C6).

How to find

This point is located on the posterior midline and thus on the *du mai*. In fact, the ‘prominent bone’ (vertebra prominens) inferior to *chonggu zhuidong* is the spinous process of either C7 or T1. → **Du-14** is located between the two. For the correct method of locating C6 and C7 → 3.4.1.

Needling

0.5–1 cun obliquely in a superior direction.

Actions/Indications

- Dispels external pathogenic factors
- Harmonises the *shen*


Ex-HN (*chonggu zhuidong*)
C6
C7
Du-14
T1


Extension and flexion of the head
2 fingers on the spinous processes of C6 and 7
G.B.-21
S.I.-15
Du-14

Upper Arm JINGBI **Ex-HN**


Ex-HN (*jingbi*)
1 cun
1/3
1/3
1/3

Location

1 cun superior to the junction of the proximal and middle third of the clavicle.

How to find

Measure a third of the clavicle from its medial end, then measure 1 cun in a superior direction and there locate *jingbi* in the supraclavicular fossa. The point is located above the brachial plexus. → **ST-12** is very close to this point, directly superior to the midpoint of the clavicle.

Needling

Vertically 0.3–0.5 cun. During insertion or stimulation, a tingling or warm sensation should be felt radiating to the fingers. Caution: Pneumothorax.

Actions/Indications

- Paraesthesia and paralysis of the upper extremity


Minor supraclavicular fossa
Suprasternal fossa
Major supraclavicular fossa
Clavicle
ST-12
ST-11
Ren-22

6.2 Extra Points: Chest and Abdomen (EX-CA)


Ex-HN
(jingbi)
1
2
3
4
5
6
7
8
9
8 cun
1
2
3
4
5
6
7
8
Ex-CA (weishang)
Ex-CA
(qizhongsibian)
4 cun
1
Ex-CA (zhixie)
2
Ex-CA
(qimen)
Ren-4 (guanyuan)
1 cun
3
3 cun
Ex-CA
(tituo)
4
5
cun
Ex-CA (yijing)
Ren-3 (zhongji)
Ex-CA-1 (zigong)


Ex-CA-1
(zigong)
3 cun
Ren-3
Ren-2
1 cun


weishang
Ren-10
2 cun
SP-15


corresponds to
Ren-9
qizhongsibian
(4 point)
corresponds to
Ren-7


tituo
qimen
yijing
Ren-4
1 cun
2 cun
3 cun
Ren-2


tituo
qimen
yijing
Ren-4
1 cun
2 cun
3 cun
Ren-2


tituo
qimen
yijing
Ren-4
1 cun
2 cun
3 cun
Ren-2

English abbreviation (standard)	***Pinyin* name**	**Nguyen Van Nghi, König and Wancura, Schnorrenberger**	**Shanghai College**	**Ex (Hempen)**
Ex-CA-1	*zigong*	PaM or ZP49	M-CA-18	Ex9
Further extra points				
Ex-CA	*weishang*			
Ex-CA	*qizhongsibian*			
Ex-CA	*yijing*	PaM or ZP45		
Ex-CA	*qimen*	PaM or ZP46		
Ex-CA	*tituo*	NP39	M-CA-4	
Ex-CA	*zhixie*	NP38	N-CA31	

Ch06a-F10028.qxd 2/23/08 1:25 PM Page 563

Palace of the Child ZIGONG Ex-CA-1


Ex-CA-1
(*zigong*)
3 cun
Ren-3
Ren-2
1 cun
Midline
Upper border of the pubic symphysis

Location

3 cun lateral to the anterior midline and 1 cun superior to the upper border of the pubic symphysis.

How to find

The distance between the centre of the umbilicus and the upper border of the pubic symphysis is divided into 5 proportional cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun measurements should be used (helpful device: elastic tape → 2.3.1). From the upper border of the pubic symphysis, measure 1 cun in a superior direction – this is the location of → **Ren-3**. From there, measure 3 cun in a lateral direction to locate *zigong*.

Located on the same level are → **KID-12** (0.5 cun from the midline) and → **ST-29** (2 cun lateral to the midline).

Needling

0.5–1 cun vertically or 1–2 cun obliquely towards the upper border of the pubic symphysis. Caution: Peritoneum, pregnancy, full bladder.

Actions/Indications

- Strengthens and raises Qi
- Regulates menstruation
- Alleviates pain in the abdomen and the lumbar region


15
25
16
8
14
6
27
14
4
29
12
13
SP-12
ST-30
KID-11
Ren-2
Umbilicus
1
2
3
4
Upper border of the pubic symphysis


Umbilicus
Upper border of the pubic symphysis


Ren-3
Ren-2
1 cun


KID-12
Ren-03
KID-11
Ren-02
Upper border of the pubic symphysis


ST-29
1 cun
ST-30
Upper border of the pubic symphysis

Ex-CA *Lifting the Stomach* WEISHANG

Location

On the Spleen channel, 4 cun lateral and 2 cun superior to the umbilicus.

How to find

The distance between the sternocostal angle and the centre of the umbilicus is divided into 8 proportional cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun measurements should be used (helpful device: elastic tape ➞ 2.3.1). From the centre of the umbilicus, measure 2 cun in a superior direction (location of ➞ **Ren-10**) and then locate *weishang* 4 cun lateral to the midline. 1 cun superior to ➞ **Ex-CA** (*weishang*) is ➞ **SP-16**.

Located on the same level are ➞ **Ren-10/KID-17/ST-23** (on the midline/0.5 cun lateral to the midline/2 cun lateral to the midline).

Needling

2–3 cun obliquely in the direction of the umbilicus. Caution: Peritoneum, pregnancy.

Actions/Indications

- Gastroptosis, abdominal pain


4 cun
SP-16
Ren-10
weishang
2 cun
SP-15
Spleen
Midline


Sterno-
costal
angle
Umbilicus


GB-24
12
16
22
18
LIV-13
15
25
16
8
14
6
27
14
5
4
3
2
1
Umbilicus
1
2


Ren-10
2 cun
Umbilicus


KID-18
Ren-11
KID-17
Ren-10
2 cun
0.5 cun
Umbilicus



Four Points Around the Umbilicus QIZHONGSIBIAN Ex-CA


corresponds to
Ren-9
qizhongsibian
(4 points)
corresponds to
Ren-7

Location

Four points, 1 cun lateral, superior and inferior to the umbilicus.

How to find

These four points are arranged in a star shape around the umbilicus.

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Distension, diarrhoea, dyspepsia, dysmenorrhoea


Umbilicus
Upper border of
the pubic symphysis


Sterno-
costal
angle
Umbilicus

Ex-CA

Loss of Semen YIJING

Location

1 cun lateral to the anterior midline and 2 cun superior to the upper border of the pubic symphysis.

How to find

The distance between the centre of the umbilicus and the upper border of the pubic symphysis is divided into 5 proportional cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun measurements should be used (helpful device: elastic tape → 2.3.1). From the upper border of the pubic symphysis, measure 2 cun in a cranial direction (→ **Ren-4**) and, from there, measure 1 cun in a lateral direction. There, locate *yijing*.

Located on the same level are → **KID-13** (0.5 cun lateral to the midline), **Ex-CA** (*qimen*, 3 cun lateral to the midline), → **ST-28** (2 cun lateral to the midline) and **Ex-CA** (*tituo*, 4 cun lateral to the midline). → **G.B.-27** is located medial to the ASIS, approximately on the same level.

Needling

0.5–1 cun. Caution: Peritoneum, full bladder, pregnancy.

Actions/Indications

Ejaculation disorders, impotence, scrotal eczema


tituo
qimen
yijing
Ren-4
1 cun
2 cun
3 cun
Ren-2
4 cun
Midline
Upper border of the pubic symphysis


15
25
16
8
Umbilicus
14
6
1
27
14
2
4
3
29
12
4
13
SP-12
ST-30
KID-11
Ren-2
Upper border of the pubic symphysis


Ren-4
2 cun
Ren-2


tituo
qimen
yijing
Ren-4
1 cun
2 cun
3 cun
Ren-2


Umbilicus
Upper border of the pubic symphysis


5 cun
KID-13
Ren-04
KID-12
Ren-03

Qi Gate QIMEN Ex-CA


tituo
qimen
yijing
Ren-4
1 cun
2 cun
3 cun
Ren-2
4 cun
Midline
Upper border of the pubic symphysis


15
25
16
8
14
6
27
14
4
29
12
13
SP-12
ST-30
KID-11
Ren-2
Umbilicus
1
2
3
4
Upper border of the pubic symphysis


Umbilicus
Upper border of the pubic symphysis

Location

3 cun lateral to the anterior midline and 2 cun superior to the upper border of the pubic symphysis.

How to find

The distance between the centre of the umbilicus and the upper border of the pubic symphysis is divided into 5 proportional cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun measurements should be used (helpful device: elastic tape → 2.3.1). From the upper border of the pubic symphysis, measure 2 cun in a cranial direction (→ **Ren-4**) and, from there, measure 3 cun in a lateral direction. There, locate *qimen*.

Located on the same level are → **KID-13** (0.5 cun lateral to the midline), **Ex-CA** (*yijing*, 1 cun lateral to the midline), → **ST-28** (2 cun lateral to the midline) and **Ex-CA** (*tituo*, 4 cun lateral to the midline). → **G.B.-27** is located medial to the ASIS, approximately on the same level.

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Metrorrhagia, female infertility, orchitis, urinary tract infections, persistent lochial discharge


Ren-4
2 cun
Ren-2




G.B.-27
0.5 cun
Anterior superior iliac spine
G.B.-28

Ex-CA *Lift and Support* TITUO

Location

4 cun lateral to the anterior midline and 2 cun superior to the upper border of the pubic symphysis.

How to find

The distance between the centre of the umbilicus and the upper border of the pubic symphysis is divided into 5 proportional cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun measurements should be used (helpful device: elastic tape → 2.3.1). From the upper border of the pubic symphysis, measure 2 cun in a cranial direction (→ **Ren-4**) and from there measure 4 cun in a lateral direction. There, medial to the ASIS, locate *tituo*.

Located on the same level are → **KID-13** (0.5 cun lateral to the midline), → **Ex-CA** (*yijing*, 1 cun lateral to the midline), → **ST-28** (2 cun lateral to the midline) and → **Ex-CA** (*qimen*, 3 cun lateral to the midline). → **G.B.-27** is located medial to the ASIS, approximately on the same level.

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, pregnancy.

Actions/Indications

- Strengthens the rising Qi and alleviates organ prolapse

Special features

In modern TCM, *tituo* is considered one of the most important points for prolapse of the uterus.


tituo
qimen
yijing
Ren-4
1 cun
2 cun
3 cun
Ren-2
4 cun
Midline
Upper border of the pubic symphysis


15
25
16
8
14
6
27
14
4
29
12
13
SP-12
ST-30
KID-11
Ren-2
Umbilicus
1
2
3
4
Upper border of the pubic symphysis


5 cun
KID-13
Ren-04
KID-12
Ren-03


Umbilicus
Upper border of the pubic symphysis




G.B.-27
0.5 cun
Anterior superior iliac spine
G.B.-28


Ren-4
2 cun
Ren-2

End Diarrhoea ZHIXIE Ex-CA



Location

On the anterior midline, 2.5 cun inferior to the umbilicus.

How to find

The distance between the centre of the umbilicus and the upper border of the pubic symphysis is divided into 5 proportional cun, which can vary considerably from the patient's finger cun. Therefore, only proportional cun measurements should be used (helpful device: elastic tape ➞ 2.3.1). *Zhixie* is located at the midpoint of this distance, between ➞ **Ren-4** (2 cun superior to the upper border of the pubic symphysis) and ➞ **Ren-5** (2 cun inferior to the umbilicus). **Or:** Spreading hands technique (➞ 2.3.3): Place the little fingers on the umbilicus and the upper border of the pubic symphysis respectively and spread the hands evenly, joining the thumbs at the midpoint of this distance.

Needling

Vertically 0.5–1 cun. Caution: Peritoneum, full bladder, pregnancy.

Actions/Indications

- Stops diarrhoea







Ex-CA *Triangle Moxibustion* SANJIAOJIU

Location

These three points are located on the corners of an equilateral triangle, the apex of which is formed by the umbilicus, while the base forms a horizontal line on the abdomen. The sides are equal to the patient's smile.

How to find

It is helpful to explain the location of this point to the patient. Invariably, this will make them smile, allowing the practitioner to determine the length of the sides of the triangle.

Needling

Moxibustion only, no needling.

Actions/Indications

- Regulate Qi and stop diarrhoea.



6.3 Extra Points: Back (EX-B)


Ex-B2 (*jiaji/huatuojiaji*)
Disorder of the upper extremities
Disorder of the thorax
Disorder of the abdominal region
Disorder of the lower extremities
Ex-HN-15 (*jingbailao*)
Ex-HN (*chonggu*)
Ex-B-1 (*dingchuan*)
Ex-B (*jiehexue*)
Ex-B-3 (*weiwanxiashu*)
Ex-B-4 (*pigen*)
Ex-B (*xiazhishi*)
Ex-B-5 (*xiajishu*)
Ex-B-7 (*yaoyan*)
Ex-B-6 (*yaoyi*)
Ex-B-8 (*shiqizhui*)
Ex-B (*tunzhong*)
Ex-B-9 (*yaoqi*)
Ex-LE (*huanzhong*)

English abbreviation (standard)	*Pinyin* name	Nguyen Van Nghi, König and Wancura, Schnorrenberger	Shanghai College	Ex (Hempen)
Ex-B-1	*dingchuan*	NP45	M-BW-1	Ex10
Ex-B-2	*huatuojiaji/jiaji*	PaM or ZP85	M-BW-35	Ex12
Ex-B-3	*weiwanxiashu/* *waiguanxiashu/* *bashu* or *yishu*	PaM or ZP62	M-BW-12	
Ex-B-4	*pigen*	PaM or ZP66	M-BW-16	
Ex-B-5	*xiajishu*	PaM or ZP71	M-BW-21	
Ex-B-6	*yaoyi*	PaM or ZP73	M-BW-23	
Ex-B-7	*yaoyan*	PaM or ZP74	M-BW-24	
Ex-B-8	*shiqizhui/shiqizhuixia*	PaM or ZP75	M-BW-25	Ex11
Ex-B-9	*yaoqi*	PaM or ZP79	M-BW-29	
Further extra points				
Ex-B	*jiehexue*	NP47	N-BW-6	
Ex-B	*tunzhong*	PaM or ZP83	M-BW-33	

Calm Dyspnoea DINGCHUAN Ex-B-1

Location

0.5 cun lateral to the lower border of the spinous process of the 7th cervical vertebra (C7).

How to find

First, identify C7 (→ 3.4.1). Next, measure 0.5 cun from the lower border of its spinous process in a lateral direction and there locate **Ex-B-1.**

Located on the same level are → **Du-14** (on the midline), → **S.I.-15** (2 cun lateral to the midline) and **Ex-B** (*jiehexue*, 3.5 cun lateral to the midline).

Needling

0.5–1 cun in a medial direction.

Actions/Indications

- Harmonises Lung Qi
- Local point for the neck and shoulders

Special features

Modern main point for dyspnoea


0.5 cun
Medial base of scapular spine
Spinous process C7
Ex-B-1
Du-14
Spinous process T3
Spinous process T7
Inferior angle
Midline


S.I.-15
S.I.-12
S.I.-10
14
11
13
42
13
12
44
15
11
46
17
9
Ex-B-3


Extension and flexion of the head
2 fingers on the spinous processes of C6 and 7
G.B.-21
S.I.-15
Du-14


Spinous process C7
Du-14
S.I.-15


3,5 cun
Ex-B-10 (*jiehexue*)
Spinous process C7
Medial base of scapular spine
Du-14

Ch06a-F10028.qxd 2/23/08 1:26 PM Page 574

Ex-B-2 *Hua Tuo's Paravertebral Points* HUATUOJIAJI

Location

17 point pairs, 0.5 cun lateral to the lower borders of the spinous processes, close to the spinal facet joints:

- 12 thoracic point pairs (*xiongjiaji*): between T1 and T12
- 5 lumbar point pairs (*yaojiaji*): between L1 and L5, Depending on the school of thought, corresponding points lateral to the cervical spine are described as 'additional *huatuojiaji*'.

How to find

Select points of **Ex-B-2** depending on the disorder. Determine the relevant spinous process and locate the point pairs 0.5 cun lateral to its lower border.

Needling

0.5–1 cun vertically or better obliquely in a medial direction towards the spine, up to 1.5 cun in the lumbar region. The purpose of needling these points is to stimulate the local nerve roots. This means that the insertion angle has to be adapted to the patient's anatomy. Never needle in a lateral direction. Once *deqi* is obtained, do not further stimulate the needle; it is possible to apply electrostimulation.

Actions/Indications

- Regulate and harmonise the five *zang* and six *fu* Organs, depending on the points selected

Special features

With disorders of the facet joints of the cervical spine, there are often tender points 0.5 cun lateral to the lower borders of the spinous processes. In China, these are needled for chronic disorders of the cervical spine. If oblique insertions (approximately 45°) in a medial direction are used for points on the inner branch of the Bladder channel, the tip of the needle will reach the area of the *huatuojiaji* points. This enhances the therapeutic effect.


0.5 cun
Disorders of the upper extremities
Spinous process C1
Spinous process T3
Disorders of the thorax
Spinous process T7
Disorders of the abdominal region
Disorders of the lower extremities
Spinous process L4
Level of the iliac crests ≙ spinous process L4 (depending on patient's position)
Ex-B-2 point pairs


Spinous process L1
Spinous process L2
Spinous process L3
Spinous process L4
Spinous process L5
Ex-B-2 (parts)
Level of the iliac crests Spinous process L4 (depending on patient's position)
0.5 cun


0,5 cun
C7
Ex-B-1
Spinous process T1
Spinous process T2
Spinous process T3
Ex-B-2 (parts)
Spinous process T4
Spinous process T5
Spinous process T6
Lower border of scapula
Spinous process T7
(depending on patient's position)

Stomach Controller Lower Shu WEIWANXIASHU Ex-B-3


Medial border of the scapula
Medial base of scapular spine
Spinous process C7
Spinous process T3
Spinous process T7
Spinous process T8
Ex-B-3
Inferior angle
1.5 cun
1.5 cun
Spinous process T12
BI channel, medial branch
Midline

Location

1.5 cun lateral to the lower border of the spinous process of the 8th thoracic vertebra (T8).

How to find

Locate T7 (→ 3.4.2). From there, count down one spinous process (to T8) and locate **Ex-B-3** 1.5 cun lateral from the midline. Use the Tuffier's line (L4, 3.4.3) to confirm the location of this point: from L4, count up the spinous processes of L3 to L1 and of T12 to T8.
Located on the same level is a point of → **Ex-B-2** (0.5 cun lateral to the midline).

Needling

0.5–1 cun vertically or up to 1.5 cun obliquely in a medial direction. Do not needle in a lateral direction. Caution: Pneumothorax.

Actions/Indications

- Opens the channel locally
- Moistens the body and clears Heat


S.I.-15
S.I.-12
S.I.-10
14
13
11
42
13
12
44
15
11
46
17
9
Ex-B-3
47
18
8
49
20
6
Ex-B-4
52
23
4
Ex-B-5
Ex-B-5
Ex-B-7
25
3
Ex-B-6
Ex-B-8
54
30
Ex-B-11


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2 (parts)

Ex-B-4 *Fullness Root* PIGEN

Location

3.5 cun lateral to the posterior midline, on the level of the lower border of the spinous process of the 1st lumbar vertebra (L1).

How to find

Locate the T7 (➞ 3.4.2) and count down 6 spinous processes to L1. Locate **Ex-B-4** on the level of the lower border of its spinous process, 3.5 cun lateral to the midline. Use the Tuffier's line (L4, ➞ 3.4.3) to confirm the location of this point: from L4, count up the spinous processes of L3 to L1.

Located on the same level are ➞ **Du-5** (on the midline), a point of ➞ **Ex-B-2/BL-22/BL-51** (0.5/1.5/3 cun lateral to the midline) as well as ➞ **G.B.-25** (on the lower border of the free end of the 12th rib).

Needling

0.8–1 cun obliquely in a medial direction. Caution: Injury to the kidneys!

Actions/Indications

- Improves the Qi flow between the Upper and Middle Burner
- Eliminates local Qi and Blood stagnation


Spinous process L1
Ex-B-4
Spinous process L2
Level of the iliac crests
3.5 cun


Ex-B-4
52
23
4
Ex-B-5
Ex-B-5
Ex-B-7
25
3
Ex-B-6
Ex-B-8
54
30
Ex-B-11
2
1
36
Bladder channel, lateral branch
Du mai
Bladder channel, medial branch


Spinous process L1
BL-22
Spinous process L2


Spinous process L1
BL-51
Spinous process L2


12th rib
G.B.-25


Spinous process L1
Du-5
Spinous process L2
Spinous process L3

Lower Shu Point XIAJISHU **Ex-B-5**


Medial border of the scapula
Spinous process L1
Spinous process L3
Level of the iliac crests
Ex-B-5
3 cun


BL-23
Du-4
BL-52
Spinous process L4
Level of the iliac crests
Tuffier's line
Du-3


1.5 cun
Spinous process L3
BL-24
Level of the iliac crests
Spinous process L4


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2 (parts)

Location

Some authors consider **Ex-B-5** (*xiajishu*) to comprise three points: one point on the midline below the spinous process of the 3rd lumbar vertebra (L3) (this is the more common and single location of this extra point), complemented by two lateral points 3 cun lateral to the centre point on the midline.

How to find

Locate the Tuffier's line and L4 (➞ 3.4.3). Locate **Ex-B-5** on the midline, on the lower border of the spinous process of L3. Then measure 3 cun in a lateral direction and there locate the two lateral points of **Ex-B-5.**

Located on the same level are a point of ➞ **Ex-B-2/BL-24** (0.5/1.5 cun lateral to the midline).

Needling

0.5–0.8 cun vertically to the skin or obliquely in an inferior direction. The patient's back should be straight or overextended to avoid a spinal puncture. Oblique insertions in a superior direction should only be carried out by experienced practitioners, as in small persons (regardless of their weight), the spinal canal can be reached after only 1.25 cun. Caution: In pregnant women about to go into labour, this point might have a labour-promoting effect.

Actions/Indications

- Tonifies Kidney Yang
- Opens the channel locally

Special features

Strictly speaking, this extra point should be considered as a single point and a pair of points with differing indications: depending on the school of thought and the clinical requirements, the lateral points are used for localised Qi and Blood stagnation, whereas the central point is indicated for Kidney Yang deficiency.

Ex-B-6 Back Pain Point YAOYI

Location

3 cun lateral to the midline, on the level of the lower border of the spinous process of the 4th lumbar vertebra (L4).

How to find

Locate the Tuffier's line and L4 (→ 3.4.3). On the level of the lower border of the spinous process of L4, measure 3 cun in a lateral direction and there locate **Ex-B-6.** Located on the same level are → **Du-3** (on the midline), a point of → **Ex-B-2/BL-25/Ex-B-7** (0.5/1.5/3.5 cun lateral to the midline).

Needling

Vertically 0.5–0.8 cun

Actions/Indications

- Opens the channel and *luo* vessels


Medial border of the scapula
Spinous process L1
Spinous process L4
Level of the iliac crests
Ex-B-6
3 cun


Ex-B-4
52
23
4
Ex-B-5
Ex-B-5
Ex-B-7
25
3
Ex-B-6
Ex-B-8
54
30
Ex-B-11
2
1
36
Bladder channel, lateral branch
Du mai
Bladder channel, medial branch


Level of the iliac crests
Spinous process L4
Spinous process L5
Du-3


Spinous process L3
Spinous process L4
Level of the iliac crests ≙ L4 (dependent on patient position)
BL-25
Midline

Lumbar Eyes YAOYAN **Ex-B-7**


Spinous process L1
Spinous process L3
Spinous process L4
Level of the iliac crests
Ex-B-7
3.5 cun


BL-23
Du-4
BL-52
Spinous process L4
Level of the iliac crests
Tuffier's line
Du-3


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2 (parts)

Location

3.5 cun lateral to the midline, on the level of the lower border of the spinous process of the 4th lumbar vertebra (L4).

How to find

Locate the Tuffier's line and L4 (➞ 3.4.3). **Ex-B-7** is located 3.5 cun lateral to it. Located on the same level are ➞ **Du-3** (on the midline), a point of ➞ **Ex-B-2/BL-25/Ex-B-6** (0.5/1.5/3 cun lateral to the midline).

Needling

Vertically 0.5–0.8 cun

Actions/Indications

- Opens the channel locally
- Tonifies the Kidneys

Ex-B-8 *Below the 17th Vertebra* SHIQIZHUI/SHIQIZHUIXIA

Location

On the midline, below the spinous process of the 5th lumbar vertebra (L5).

How to find

Locate the Tuffier's line and L4 (→ 3.4.3). Next, palpate in an inferior direction to the next vertebra (L5) and locate **Ex-B-8** below the border of its spinous process, at the lumbosacral joint. Located on the same level are a point of → **Ex-B-2/BL-26** (0.5/1.5 cun lateral to the midline).


Spinous process L1
Level of the iliac crests
Spinous process L4
Spinous process L5
Ex-B-8

Needling

0.5–1 cun vertically to the skin or obliquely in an inferior direction. The patient's back should be straight or slightly flexed to avoid a spinal puncture. Oblique insertions in a superior direction should only be carried out by experienced practitioners, as in small persons (regardless of their weight), the spinal canal can be reached after only 1.25 cun. Caution: In pregnant women about to go into labour, this point might have a labour-promoting effect.

Actions/Indications

- Tonifies the Kidneys
- Opens the channel locally


Ex-B-4
52
23
4
Ex-B-5
Ex-B-5
Ex-B-7
25
3
Ex-B-6
Ex-B-8
54
Ex-B-11
30
2
1
36
Du mai
Bladder channel, outer branch
Bladder channel, inner branch


Spinous process L3
Level of the iliac crests
Spinous process L4
Spinous process L5
BL-26
Midline


Spinous process L1
Spinous process L2
Spinous process L3
Ex-B-2 (parts)


BL-23
Du-4
BL-52
Spinous process L4
Level of the iliac crests
Tuffier's line
Du-3

Miraculous Lumbar Point YAOQI Ex-B-9



Location

2 cun superior to the tip (inferior end) of the coccyx.

How to find

Locate the tip of the coccyx superior to the anus and palpate for the sacral hiatus. From there, palpate 2 cun in a superior direction and locate **Ex-B-9** in a depression between the sacral processes.
→ **Du-1** is located on the midline, between the tip of the coccyx and the anus.

Needling

Up to 1.5 cun obliquely in a superior direction.

Actions/Indications

- Calms the *shen*

Ex-B-10 *Tuberculosis Point* JIEHEXUE

Location

3.5 cun lateral to the lower border of the spinous process of the 7th cervical vertebra (C7).

How to find

Locate the spinous process of C7 and, on this level, palpate 3.5 cun in a lateral direction. There, locate **Ex-B** (*jiehexue*).
Located on the same level are → **Du-14** (on the midline), → **Ex-B-2/S.I.-15** (0.5/2 cun lateral to the midline).

Needling

Vertically 0.5–0.8 cun. Caution: Pneumothorax.

Actions/Indications

- Tonifies the Lung
- Opens the channel locally

Special features

This is an unofficial extra point.


3.5 cun
Ex-B-10 (*jiehexue*)
Spinous process C7
Medial base of scapular spine
Du-14
Spinous process T3
Midline


S.I.-15
14
S.I.-12
11
13
S.I.-10
42
13
12
44
15
11
6
46
17
9
Ex-B-3


Extension and flexion of the head
2 fingers on the spinous processes of C6 and 7
G.B.-21
S.I.-15
Du-14


Spinous process C7
Du-14
Medial base of scapular spine


Spinous process C7
Du-14
S.I.-15

Buttock Centre TUNZHONG Ex-B

Location

At the centre of the buttock, 3.5 cun lateral to the posterior midline, on the level of the 4th sacral foramen.

How to find

Locate the lumbosacral joint, which often forms an easily palpable 'kink' between the L5 and the sacrum. Alternatively, locate the Tuffier's line (→ 3.4.3) for reference. Then palpate the inferior aspect of the sacrum for the sacral hiatus (→ 3.4.4). Between these two reference points, the four pairs of sacral foramina are arranged on either side of the midline in a slight V-shaped form and can be palpated as shallow depressions. **Ex-B** (*tunzhong*) is located 3.5 cun lateral to the lowest depression (=4th foramen), approximately at the centre of the buttock.

Located on the same level are → **BL-34/BL-30/BL-54** (over the 4th foramen/1.5/3 cun lateral to the midline).

Needling

Vertically 2–3 cun

Actions/Indications

- Opens the channel and *luo* vessels locally

Special features

This is an unofficial extra point.


Midline
3.5 cun
3 cun
Level of the iliac crests
Spinous process L4
Spinous process L5
Sacral foramina
4
BL-54
tunzhong


Sacral crest
BL-31
BL-32
BL-33
BL-34
Fingers on the 1st to 4th sacral foramina
Sacral hiatus


Sacral foramina
BL-54
Midline


Sacral foramina
BL-30
Midline

6.4 Extra Points: Upper Extremities (EX-UE)


Ex-UE-11 (*shixuan*)
Ex-UE-9
(*baxie*)
Ex-UE-5
(*dagukong*)
Ex-UE-4 (*zhongkui*)
Ex-UE-6 (*xiaogukong*)
Ex-UE-8 (*wailaogong*)
Ex-UE-7 (*yaotongdian*)
Ex-UE-3 (*zhongquan*)


1
2
3
4
5
6
7
8
9 cun
1
2
3
4
5
6
7
8
9
10
11
12
cun
Ex-UE (*bizhong*)
Ex-UE-2 (*erbai*)


Ex-UE-11 (*shixuan*)
Ex-UE-10
(*sifeng*)

English abbreviation (standard)	*Pinyin* name	Nguyen Van Nghi, König and Wancura, Schnorrenberger	Shanghai College	Ex (Hempen)
Ex-UE-1	*zhoujian*		M-UE-46	
Ex-UE-2	*erbai*	PaM or ZP114	M-UE-29	
Ex-UE-3	*zhongquan*	PaM or ZP118	M-UE-33	
Ex-UE-4	*zhongkui*	PaM101	M-UE-16	
Ex-UE-5	*dagukong*	PaM or ZP100	M-UE-15	
Ex-UE-6	*xiaogukong*	PaM or ZP102	M-UE-17	
Ex-UE-7	*yaotongxue/yaotongdian*	Handpoint 2 PaM or ZP110/111[*]	M-UE	Ex18
Ex-UE-8	*wailaogong*[†]*/luozhen*	PaM or ZP108[†]	M-UE-24	Ex17
Ex-UE-9	*baxie*	PaM or ZP107	M-UE-22	Ex14
Ex-UE-10	*sifeng*		M-UE-9	Ex13
Ex-UE-11	*shixuan*	PaM or ZP86	M-UE-1	Ex15
Further Extra points				
Ex-UE	*jianqian/jianneiling*	Part of NP74[‡] (*sanjian*): *jianyu* (L.I.-15), *jianqian*, *jianhou*	M-UE-48[§]	Ex16
Ex-UE	*bizhong*	PaM or ZP115	M-UE-30	

---

[*] The 'standard' point Ex-UE-7 (*yaotongdian* or *yaotongxue*) is described by Nguyen Van Nghi and Schnorrenberger as two separate points with different *pinyin* names: PaM or ZP110 (*weiling*) and 111 (*jingling*). Their location also corresponds to handpoint 2.

[†] Nguyen Van Nghi and Schnorrenberger distinguish between *luozhen* (PaM or ZP108) and *wailaogong* (PaM or ZP109). They describe the location of *luozhen* as identical with the 'standard' location of Ex-UE-8 (*wailaogong*): on the dorsum of the hand, between the 2nd and 3rd metacarpal bones, approximately 0.5 cun proximal to the metacarpophalangeal joint. 'Their' *wailaogong* is located at the midpoint of a line connecting the wrist and the head of the 3rd metacarpal bone, between the metacarpals, directly opposite to the point *laogong* (P-8) – hence the name *wailaogong* ('outer' *laogong*).

[‡] **NP74** (*jiansanzhen*/Three pinpricks at the Shoulder) according to Schnorrenberger: a set of three points: the first is identical with **L.I.-15** (*jianyu*), the second (*jianquan*/ Anterior to the Shoulder) is located 1 cun superior to the end of the anterior axillary fold, and the third (*jianhou*/Posterior to the Shoulder) is located 1 cun superior to the end of the posterior axillary fold.

[§] According to Deadman et al. (1998), **M-UE-48** (*jianqian*) is located midway between the end of the anterior axillary fold and **L.I.-15** (this point is not mentioned by the Shanghai College). See the point page for the location of this point.

Elbow Tip ZHOUJIAN Ex-UE-1


Ex-UE-1
Olecranon


T.B.-10
Lateral epicondyle of the humerus
S.I.-8
Medial epicondyle of the humerus
Olecranon

Location

On the tip of the olecranon.

How to find

On the tip of the olecranon. This point is best located with the elbow flexed.

Needling

Moxibustion only!

Actions/Indications

- Opens the channel and *luo* vessels locally
- Disperses Phlegm locally

Ex-UE-2 *Two Whites* ERBAI

Location

A pair of points on the palmar aspect of the forearm, 4 cun proximal to the wrist joint space (most distal wrist crease), on either side of the tendon of the flexor carpi radialis muscle.

How to find

Place the patient's arm in a relaxed supinated position. As the location of the wrist crease can vary, the wrist joint space provides a more reliable point of reference (→ 3.3.3). From the centre of the wrist joint space, measure 4 cun in a proximal direction and, on this level, locate one of the points lateral to and the other point medial to the tendon of the flexor carpi radialis muscle. **Or:** Divide the distance between the cubital crease (at → **P-3**) and the wrist joint space (at → **P-7**) into thirds, then locate → **Ex-UE-2** one third of the distance from the wrist joint (helpful tool: elastic tape → 2).

Needling

Up to 1 cun vertically or up to 1.5 cun obliquely towards proximal.

Actions/Indications

- Raises Qi to treat prolapse of the rectum and haemorrhoids


Cubital crease
P-3
8 cun
(2/3)
Tendon of the
palmaris longus
Ex-UE-2
Tendon of
the flexor
carpi radialis
4 cun
(1/3)
Wrist joint space
P-7
Pisiform


Biceps tendon
P-3
Cubital crease


1
2
3
4
5
6
7
8
9
10
11
12
cun
LU-5
P-3
HE-3
LU-6
P-4
P-5
LU-7
P-6
LU-8
HE-4
LU-9
HE-5
P-7
HE-6
HE-7
LU-10
P-8
HE-8
LU-11
HE-9
P-9



Posterior Spring ZHONGQUAN **Ex-UE-3**


Tendons of the extensor digitorum
Ex-UE-3 (*zhongquan*)
T.B.-4
Wrist joint space
Tendon of the extensor digiti minimi
Moving the fingers for better presentation of the tendons


Brachialis
Brachioradialis
Extensor carpi radialis longus
L.I.-11
Lateral epicondyle
Extensor digitorum
Triceps brachii, lateral head
Triceps brachii, medial head
Tendon of the triceps brachii
T.B.-10
Olecranon
Flexor carpi ulnaris
Extensor carpi ulnaris

Location

On the dorsal aspect of the wrist joint space (dorsal wrist crease), radial to the tendon of the extensor digitorum communis muscle.

How to find

Place the patient's arm in a relaxed pronated position. As the location of the dorsal wrist crease can vary, the joint space between the proximal row of carpals and the radius/ulna provides a more reliable point of reference (→ 3.3.3). By moving the wrist in a relaxed way, you can easily palpate the joint space. Locate **Ex-UE-3** in the joint space, radial to the tendon of the extensor digitorum communis muscle. The tendons become more pronounced by moving and overextending the three medial fingers. → **T.B.-4** is located on the same level, ulnar to the tendon of the extensor digitorum communis muscle.

Needling

Vertically 0.3–0.5 cun

Actions/Indications

- Harmonises the Qi flow between the Upper and Middle Burner


Tendons of the extensor digitorum
Ex-UE-3 (zhongquan)
T.B.-4
Wrist joint space
Tendon of the

Ex-UE-4 *Back of the Middle Finger* ZHONGKUI

Location

As the name implies, on the dorsal aspect of the middle finger, in the centre of the transverse creases of the proximal interphalangeal joint (PIP).

How to find

Slightly bend the PIP of the middle finger. The point is located at the vertex of the flexed joint.

Located in a comparable position on the little finger is → **Ex-UE-6** (*xiaokugong*, in the centre of the proximal PIP of the little finger).

Also located in a comparable position is → **Ex-UE-10** (*sifeng*, four points on the palmar aspect of the fingers of each hand, in the centre of the creases of the PIP joints of the 2nd to 5th fingers).

Needling

Prick to bleed or moxibustion.

Actions/Indications

- Descends Stomach Qi
- Clears Heat







Thumb Joint DAGUKONG **Ex-UE-5**



Location

As the name implies, on the dorsal aspect of the thumb, in the centre of the transverse creases of the interphalangeal joint.

How to find

Ask the patient to slightly flex the interphalangeal joint of the thumb. The point is located at the vertex of the bent joint.

Needling

Prick to bleed or moxibustion.

Actions/Indications

- Clears Heat
- Harmonises the Middle Burner

Ex-UE-6 *Little Finger Joint* XIAOGUKONG

Location

As the name implies, on the dorsal aspect of the little finger, in the centre of the transverse creases of the proximal interphalangeal joint (PIP).

How to find

Slightly bend the PIP of the little finger. The point is located at the vertex of the flexed joint.

Located in a comparable position on the middle finger are → **Ex-UE-4** (in the centre of the proximal PIP of the middle finger) and, on the palmar aspect of the little finger, → **Ex-UE-10** (four points on the palmar aspect of the fingers of each hand, in the centre of the creases of the PIP joints of the 2nd to 5th fingers).

Needling

Prick to bleed

Actions/Indications

- Clears Heat







Lumbar Pair Point YAOTONGDIAN Ex-UE-7


Metacarpal IV
Metacarpal III
Metacarpal II
Ex-UE-7
Metacarpal V
Ex-UE-8

Location

Two points on the dorsal aspect of the hand, between the 2nd/3rd and 4th/5th metacarpal bones, on the level of the junctions of the shaft and the base of the respective metacarpal bones.

How to find

On the dorsal aspect of the hand, glide with the palpating fingers in the grooves between the 2nd and 3rd as well as between the 4th and 5th metacarpal bones towards the wrist joint, until the fingers come to rest in the depressions just distal to the bases of the metacarpal bones. Here, locate the points of **Ex-UE-7** (*yaotongdian* or *yaotongxue*).

Needling

0.5–0.8 cun vertically or slightly obliquely towards the centre of a loose fist. Caution: Painful point! Do not stimulate these distal points in patients with a weak constitution: danger of needle collapse!

Actions/Indications

- Strengthen the Qi and Blood in the lumbar region, alleviate pain

Special features

Very effective distal point for acute disorders of the lumbar spine


L.I.-1
T.B.-1
S.I.-1
Ex-UE-9
(baxie)
L.I.-2
L.I.-3
T.B.-2
S.I.-2
Ex-UE-8
Ex-UE-9
(baxie)
L.I.-4
T.B.-3
S.I.-3
Ex-UE-7
Ex-UE-7
S.I.-4
L.I.-5
S.I.-5
T.B.-4
S.I.-6
T.B.-5

Ch06b-F10028.qxd 2/22/08 10:04 PM Page 594

Ex-UE-8 *Stiff Neck* WAILAOGONG/LUOZHEN/XIANQIANG

Location

On the dorsal aspect of the hand, between the 2nd and 3rd metacarpal bones, proximal to the metacarpophalangeal joints, at the junction of the heads and the shafts of the metacarpal bones.

How to find

This point is best located with the patient making a loose fist. With the palpating finger, glide in the groove between the 2nd and 3rd metacarpal bones from the wrist joint towards the fingers until the finger comes to rest in the depression just proximal to the heads of the two metacarpal bones. Here, locate **Ex-UE-8** (*wailaogong*). Located in a comparable position between the 4th and 5th metacarpal bones is → **T.B.-3**.

Needling

0.5–1 cun vertically or slightly obliquely. Caution: Painful point! Do not stimulate this point in patients with a weak constitution: danger of needle collapse!

Actions/Indications

- Strengthens the Qi and Blood of the neck and alleviates pain

Special features

Very effective distal point for acute disorders of the cervical spine. Use strongly reducing needling techniques (for 1–2 minutes) on the affected or contralateral side while asking the patient to gently move their neck/cervical spine. The practitioner should keep the patient's hand in a fixed position and ensure that the hand and forearm are sufficiently supported.




Metacarpal IV
Metacarpal III
Metacarpal II
Ex-UE-7
Metacarpal V
Ex-UE-8


L.I.-1
T.B.-1
S.I.-1
Ex-UE-9
(baxie)
L.I.-2
L.I.-3
T.B.-2
S.I.-2
Ex-UE-8
Ex-UE-9
(baxie)
L.I.-4
T.B.-3
S.I.-3
Ex-UE-7
Ex-UE-7
S.I.-4
L.I.-5
S.I.-5
T.B.-4
S.I.-6
T.B.-5

Eight Pathogens BAXIE Ex-UE-9







Location

Slightly proximal to the margins of the webs between the fingers, on the border of the red and white skin.

How to find

These points are best located when a loose fist is made. Locate the points on the border between the red and white skin. → **T.B.-2** (between the 4th and 5th fingers) is a point of **Ex-UE-9** (*baxie*). The points of → **Ex-LE-10** (*bafeng*) are located in a comparable position on the foot (proximal to the margins of the webs between the toes). → **LIV-2,** → **ST-44** and → **G.B.-43** are all part of → **Ex-LE-10**.

Needling

Up to 1 cun parallel to the metacarpal bones.

Actions/Indications

- Clears Heat
- Expels Cold and Dampness

Ex-UE-10 *Four Seams* SIFENG

Location

On the palmar aspect of the 2nd to 5th fingers, at the midpoint of the transverse creases of the proximal interphalangeal joints (PIP).

How to find

Locate these points on the palmar aspect of the 2nd to 5th fingers, at the midpoint of the transverse creases of the proximal interphalangeal joints (PIP).

Located in a similar position on the dorsal aspect of the little and middle fingers are → **Ex-UE-6** and → **Ex-UE-4** respectively.

Needling

Prick to bleed

Actions/Indications

- Harmonises the Qi flow between the Upper and Middle Burner







Ten Diffusions SHIXUAN **Ex-UE-11**





Location

On the tips of the 10 fingers.

How to find

These 10 points are located on the tips of the 10 fingers, approximately 0.1 cun from the free margin of the fingernail.
Located in a comparable position on the foot are the points of → **Ex-LE-12** (*qiduan*, on the tips of the 10 toes).

Needling

Prick to bleed

Actions/Indications

- Expels pathogenic factors

Ex-UE

Front of the Shoulder JIANQIAN/JIANNEILING

Location

On the midpoint of a line connecting the end of the anterior axillary fold and → **L.I.-15**.

How to find

To locate → **L.I.-15**: Ask the patient to actively abduct their arm and locate **L.I.-15** in the depression anterior and inferior to the acromion (=ventrolateral extremity of the acromion). The end of the anterior axillary fold is formed by the easily palpable lower border of the pectoralis major muscle. *Jianqian* is located on the anterior aspect of the shoulder joint, midway between these two reference points.

Needling

Vertically up to 1.5 cun

Actions/Indications

- Opens the channel and *luo* vessels locally

Addendum: For more details, → Table 6.4


L.I.-15
1/2
jianqian
1/2
Anterior end of the axillary fold


Clavicle
L.I.-15
LU-2
Deltoid
Infraclavicular fossa
jianquan
LU-1
Pectoralis major, clavicular head
LU-3
Triceps brachii
L.I.-14


Acromio-clavicular joint
T.B.-14
L.I.-15

Arm Centre BIZHONG **Ex-UE**


Cubital crease
6 cun
(1/2)
Ex-UE
(*bizhong*)
Ulna
Radius
6 cun
(1/2)
Wrist joint
space
Pisiform


P-4
Tendon of the
flexor
5 cun


Biceps tendon
P-3
Cubital crease



Location

On the palmar aspect of the forearm, midway between the cubital crease and the wrist joint space ('most distal wrist crease').

How to find

Place the patient's forearm in a relaxed supinated position. As the location of the wrist crease may vary, the wrist joint space presents a more reliable reference point (→ 3.3.3). The spreading hands technique is the best method for locating this point (→ 2.3.3): Place the little fingers on the centre of the wrist joint (→ **P-7**) and the cubital crease (→ **P-3**) respectively and determine the midpoint of this distance by joining the thumbs. Locate **Ex-UE** (*bizhong*) on this level between the radius and the ulna.

→ **P-4** is located 1 cun distal to the midpoint of the distance between → **P-3** and → **P-7** or 5 cun proximal to → **P-7**.

Needling

Vertically 1–1.5 cun

Actions/Indications

- Opens the channel and the *luo* vessels locally


1
2
3
4
5
6
7
8
9
10
11
12
cun
LU-5
P-3
HE-3
LU-6
P-4
P-5
P-6
LU-7
LU-8
LU-9
P-7
HE-4
HE-5
HE-6
HE-7
LU-10
LU-11
P-8
HE-8
HE-9
P-9

Ch06b-F10028.qxd 2/22/08 10:04 PM Page 601

6.5 Extra Points: Lower Extremities (EX-LE)


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
cun
ST-34
Ex-LE (*siqiang*)
Ex-LE-3 (*baichongwo*)
Ex-LE-2 (*heding*)
Ex-LE-1 (*kuangu*)
Ex-LE-4 (*neixiyan*)
ST-35 (*dubi*)
Ex-LE-5 (*xiyan*)
Ex-LE-6 (*dannang*)
Ex-LE-7 (*lanwei*)
Ex-LE-9 (*waihuaijian*)
Ex-LE-8 (*neihuaijian*)
Ex-LE-10 (*bafeng*)
Ex-LE-12 (*qiduan*)

English abbreviation (standard)	***Pinyin* name**	**Nguyen Van Nghi, König and Wancura, Schnorrenberger**	**Shanghai College**	**Ex (Hempen)**
Ex-LE-1	*kuangu*	PaM or ZP165 (*changgu*)	M-LE-28	
Ex-LE-2	*heding/xiding*	PaM or ZP156	M-LE-27	
Ex-LE-3	*baichongwo*	PaM or ZP163	M-LE-34	Ex21
Ex-LE-4	*neixiyan*	(PaM or ZP145)	M-LE	(Ex23)
Ex-LE-5	*xiyan*	PaM or ZP145	M-LE	Ex23
Ex-LE-6	*dannangxue*	PaM or ZP152	M-LE-23	
Ex-LE-7	*lanweixue*	PaM or ZP142	M-LE-13	Ex22
Ex-LE-8	*neihuaijian*	PaM or ZP146	M-LE-17	
Ex-LE-9	*waihuaijian*	PaM or ZP151	M-LE-22	
Ex-LE-10	*bafeng*	PaM or ZP137	M-LE-8	Ex19
Ex-LE-11	*duyin*		M-LE	
Ex-LE-12	*qiduan*		M-LE-6	
Further extra points				
Ex-LE	*huanzhong*	PaM or ZP84	M-**BW-34**	Ex20
Ex-LE	*siqiang*	NP94	**N**-LE-19	
Ex-LE	*lineiting*	PaM or ZP130	M-LE-1	

Hip Bone KUANGU Ex-LE-1


ST-34
1.5 cun
1.5 cun
Ex-LE-1

Location

A pair of points 2 cun superior to the patella and 1.5 cun lateral and medial to ➞ **ST-34** (*liangqiu*).

How to find

First, locate ➞ **ST-34**: measure 2 cun superiorly from the lateral upper border of the patella and there locate ➞ **ST-34** in a depression on the vastus lateralis muscle. Then locate **Ex-LE-1** 1.5 cun lateral and medial to ➞ **ST-34**.

Needling

Vertically 1–1.5 cun

Actions/Indications

- Alleviate pain


ST-32
ST- 33
ST-34
Ex-LE-3
LIV-9
SP-10
Ex-LE-2
Ex-LE-1
Popliteal crease
ST-35
Ex-LE-4
LIV-8
G.B.-34
SP-9
ST-36
12
13
14
15
16
17
18
19
20
cun
Upper patellar border
1
2
3
4
8 cun


ST-34
Quadriceps femoris
2 cun
Upper border of the patella

Ex-LE-2 *Crane's Summit* HEDING/XIDING

Location

In the centre of the upper border of the patella.

How to find

This point is best located and needled with the patient's knee slightly flexed (knee support). Locate the midpoint of the upper patellar border and there locate **Ex-LE-2** (*heding*).

Needling

Vertically 0.5–0.8 cun

Actions/Indications

- Benefits the knee joint




ST-32
ST- 33
ST-34
Ex-LE-3
LIV-9
SP-10
Ex-LE-2
Ex-LE-1
Popliteal crease
ST-35
Ex-LE-4
LIV-8
G.B.-34
SP-9
ST-36
12
13
14
15
16
17
18
19
20 cun
Upper patellar border
1
2
3
4
8 cun

Hundred Insect Burrow BAICHONGWO Ex-LE-3





Location

3 cun superior and 1 cun medial to the upper medial border of the patella, in a small depression on the vastus medialis muscle or 1 cun superior to → **SP-10**.

How to find

The patient should be in a supine or preferably in a seated position, with their knee flexed. Locate the upper medial border of the patella and, from there, measure 3 cun (1 handsbreadth) towards proximal. There, locate **Ex-LE-3** in a small depression on the vastus lateralis muscle.

Needling

Vertically 1–2 cun

Actions/Indications

- Cools Blood-Heat, eliminates Wind, drains Dampness

Ex-LE-4 *Inner Eye of the Knee* NEIXIYAN

Location

With the knee flexed, inferior to the patella, in a depression medial to the patellar ligament.

How to find

This point is best located with the patient's knee flexed (use knee support). The medial eye of the knee can be located in a distinct depression on the level of the lower border of the patella, medial to the patellar ligament. The lateral eye of the knee corresponds to → **ST-35** (*dubi*). Together, these two points form the extra point → **Ex-LE-5** (*xiyan*).

Needling

0.5–1 cun vertically or obliquely towards the lateral eye of the knee. Caution: Knee joint.

Actions/Indications

- Disorders of the knee joint

Special features

Important local point


ST-35
Ex-LE-4
Level of the lower patellar border
Patellar ligament


Vastus lateralis
Vastus medialis
Patella
Medial condyle of the femur
'Eye of the knee'
Head of the fibula
'Eye of the knee'
Patellar ligament


ST-32
ST-33
ST-34
Ex-LE-3
LIV-9
SP-10
Ex-LE-2
Ex-LE-1
Popliteal crease
ST-35
Ex-LE-4
LIV-8
G.B.-34
SP-9
ST-36
12
13
14
15
16
17
18
19
20
cun
Upper patellar border
1
2
3
4
8 cun

Eyes of the Knee XIYAN Ex-LE-5





Location

With the knee flexed, this pair of points is located inferior to the patella, medial and lateral to the patellar ligament. **Ex-LE-5** (*xiyan*) includes two points: the medial eye of the knee corresponds to → **Ex-LE-4** (*neixiyan*), the lateral eye of the knee to **ST-35** (*dubi*).

How to find

This point is best located with the patient's knee flexed (use knee support). The eyes of the knee can be located on the level of the lower border of the patella, lateral and medial to the patellar ligament. The lateral eye of the knee corresponds to → **ST-35** (*dubi*), the medial eye of the knee to → **Ex-LE-4** (*neixiyan*). Together, these two points form the extra point **Ex-LE-5** (*xiyan*).

Needling

Medial eye of the knee: 0.5–1 cun vertically or obliquely towards the lateral eye of the knee; lateral eye of the knee: 0.5–1 cun vertically or obliquely towards the medial eye of the knee. Caution: Do not needle too deeply to avoid intra-articular puncture (these points correspond to the incision sites for knee arthroscopy).

Actions/Indications

- Eliminate Wind-Dampness, reduce swellings and alleviate pain

Special features

Important local points for disorders of the knee

Ex-LE-6 *Gall Bladder Point* DANNANG/DANNANGXUE/DANNANGDIAN

Location

On the G.B. channel of the **right** leg, approximately 1–2 cun distal to → **G.B.-34**, palpate for the most tender point.

How to find

First, locate → **G.B.-34** on the right leg: locate the head of the fibula on the lateral aspect of the leg (where the seam of the trousers would be) and hold it with the index and middle fingers (as with tweezers). By gliding distally with both fingers, the index finger will come to rest in a depression directly inferior and anterior to the head of the fibula (→ **G.B.-34**). From there, continue to palpate slowly along the G.B. channel, until you find the most tender point approximately 1–2 cun inferior to → **G.B.-34**. This is the location of **Ex-LE-6** (*dannangxue*).

Needling

Vertically 1–1.5 cun

Actions/Indications

- Clears Heat and drains Dampness for acute and chronic disorders of the Gall Blader such as cholecystitis and cholelithiasis (tenderness on this point is diagnostically significant).





Appendix Point LANWEI/LANWEIXUE Ex-LE-7


ST-35
3 cun
ST-36
2 cun
1 fingerbreadth
Ex-LE-7
Crest of the tibia
11 cun
Highest prominence
of the lateral malleolus


ST-35
3 cun
ST-36

Location

On the ST channel of the **right** leg, the most tender point approximately 2 cun distal to ➞ **ST-36**.

How to find

Locate this point on the right leg only (this corresponds to the unilateral location of the appendix on the abdomen). First, locate ➞ **ST-36** 3 cun inferior to the knee joint space (➞ **ST-35**) and 1 cun lateral to the anterior crest of the tibia. Then continue to palpate along the ST channel for approximately 2 cun (towards ➞ **ST-37**, 3 cun inferior to ➞ **ST-36**) and locate **Ex-LE-7** (*lanweixue*) on the most tender point.

Needling

Vertically 1–1.5 cun

Actions/Indications

- Activates the Qi and Blood flow in the Large Intestine, clears Heat and Heat toxins from the Large Intestine


ST-33
ST-34
Ex-LE-3
LIV-9
SP-10
Ex-LE-2
Ex-LE-1
Popliteal
crease
ST-35
Ex-LE-4
LIV-8
G.B.-34
SP-9
ST-36
ST-37
ST-38
ST-40
ST-39
Highest prominence
of the lateral malleolus
ST-41
14
15
16
17
18
19
20
cun
Upper patellar
border
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
cun
8 cun
Midpoint
8 cun

Ex-LE-8 *Medial Malleolus Tip* NEIHUAIJIAN


Highest prominence
of the medial malleolus
Ex-LE-8

Location

On the highest point of the medial malleolus.

How to find

Find the highest prominence of the medial malleolus and there locate **Ex-LE-8** (*neihuaijian*). Located in a comparable position but on the lateral malleolus is → **Ex-LE-9** (*waihuaijian*).

Needling

0.1 cun transversely (subcutaneously) or prick to bleed.

Actions/Indications

- Pain in the medial ankle region


Tibia
Fibula
Medial
malleolus
Lateral
malleolus
Talus
Achilles tendon
Calcaneus

Outer Malleolus Tip WAIHUAIJIAN Ex-LE-9



Location

On the highest prominence of the lateral malleolus

How to find

Find the highest prominence of the lateral malleolus and there locate **Ex-LE-9** (*waihuaijian*). Located in a comparable position but on the medial malleolus is → **Ex-LE-8** (*neihuaijian*).

Needling

0.1 cun transversely (subcutaneously) or prick to bleed.

Actions/Indications

- Pain in the lateral ankle region

Ex-LE-10 *Eight Winds* BAFENG

Location

Eight points located on the dorsum of the foot, slightly proximal to the margins of the interdigital webs.

How to find

Locate the points of **Ex-LE-10** (*bafeng*) on the dorsum of the foot, proximal to the margins of the webs between the toes, on the border of the red and white skin. ➞ **LIV-2** (*xingjian*), ➞ **ST-44** (*neiting*) and ➞ **G.B.-43** (*xiabai*) are all part of the *bafeng* points. The extra points ➞ **Ex-UE-9** (*baxie*) are located in a comparable position on the dorsum of the hand, proximal to the margins of the webs between the fingers (➞ **T.B.-2** is part of the ➞ **Ex-UE-9**).

Needling

0.3–1 cun obliquely in a proximal direction or prick to bleed.

Actions/Indications

- Clears Heat and reduces swelling


Ex-LE-10
Interdigital fold




LIV-2
Interdigital fold between the 1st and 2nd toe




Proximal to the interdigital fold
G.B.-43


BL-63
G.B.-40
ST-41
LIV-4
SP-5
Bl 64
ST-42
G.B.-41
SP-4
BL-65
G.B.-42
LIV-3
G.B.-43
ST-43
BL-66
SP-3
BL-67
ST-44
SP-2
G.B.-44
Ex-LE-10 (*bafeng*)
LIV-1
SP-1
ST-45

Solitary Yin DUYIN Ex-LE-11



Location

On the plantar aspect of the 2nd toe, at the midpoint of the transverse crease of the distal interphalangeal joint.

How to find

Locate the plantar aspect of the 2nd toe. There, locate **Ex-LE-11** (*duyin*) at the midpoint of the transverse crease of the distal interphalangeal joint.

Needling

0.2–0.3 cun vertically or transversely (subcutaneously) or prick to bleed or moxibustion.

Actions/Indications

- Acute angina, thoracic and hypochondriac pain, nausea, vomiting, retention of the lochia, irregular menstruation, inguinal hernia

Ex-LE-12 *End of Qi* QIDUAN

Location

On the tips of the 10 toes.

How to find

Locate the points of **Ex-LE-12** (*qiduan*) on the tips of the 10 toes, 0.1 cun from the free margin of the nail.

The points of → **Ex-UE-11** (*shixuan*) are located in a comparable position on the hand, on the tips of the 10 fingers.

Needling

Prick to bleed

Actions/Indications

- Syncope, oedema of the feet, acute abdominal pain





Circle Centre HUANZHONG **Ex-LE**


Highest prominence of the greater trochanter
Ex-LE (*huanzhong*)
Sacral hiatus
2/3
G.B.-30
Du-2
1/2
1/2
1/3


Sacral hiatus
2/3
G.B.-30
1/3


Fingers on the 1st to 4th sacral foramina
Sacral hiatus
Du-2

Location

Midway between → **G.B.-30** (*huantiao*) and → **Du-2** (*yaoshu*).

How to find

First, locate → **G.B.-30**: divide the distance between the prominence of the greater trochanter and the sacral hiatus into thirds (→ 3.4.4) and locate → **G.B.-30** a third of the distance from the greater trochanter. Then locate → **Du-2** directly below the sacral hiatus. Next, locate **Ex-LE** (*huanzhong*) midway between these two points.

Needling

Vertically 2–2.5 cun

Actions/Indications

- Sciatica, urinary tract infection, haemorrhoids, paralysis of the lower extremities

Special features

- This point is not part of the WHO classification of extra points.

Ex-LE *Four Muscles Strengthening Point* SIQIANG

Location

4.5 cun superior to the centre of the upper patellar border.

How to find

Find the centre of the upper patellar border. From there, measure 4.5 cun (1 handbreadth and 2 fingerbreadths) in a superior direction. **Or:** The distance between the upper border of the pubic symphysis and the upper border of the patella is 18 cun (➞ 2.2). Divide this distance into quarters (spreading hands technique, elastic tape ➞ Chapter 2) and **Ex-LE** (*siqiang*) is located on the centre of the thigh, one quarter of the distance from the upper patellar border.

Needling

Vertically 1–2 cun

Actions/Indications

- Paralysis and atrophy of the muscles of the lower extremities, especially of the quadriceps femoris muscle

Special features

‘Four muscles’ refers to the four portions of the quadriceps femoris muscle. This point is not part of the WHO classification of extra points.


Sartorius
Ex-LE *siqiang*
4.5 cun
Upper patellar border
1/2
1/2
Lateral patellar border
Medial patellar border

Plantar Inner Space LINEITING **Ex-LE**





Location

On the plantar aspect of the foot, between the 2nd and 3rd metatarsal bones, opposite → **ST-44** (*neiting*).

How to find

Locate the space between the 2nd and 3rd toes on the plantar aspect of the foot. The extra point *lineiting* lies opposite → **ST-44** (on the dorsal aspect of the foot, proximal to the margin of the web between the 2nd and 3rd toe).

Needling

0.2–0.3 cun vertically towards → **ST-44**. Caution: Painful point.

Actions/Indications

- Acute epigastric pain, local pain, epilepsy, restlessness

Special features

This point is not part of the WHO classification of extra points.

7 Important Points According to Region

Claudia Focks

7.1 Anterior Aspect of the Head


ST-8
G.B.-15
G.B.-13
BL-5
BL-4
Du-23
Du-24
BL-3
G.B.-14
Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
Ex-HN-7
ST-1
ST-2
G.B.-2
ST-7
Ex-HN-8
S.I.-18
L.I.-20
L.I.-19
Du-26
ST-4
ST-5
Ex-HN
Ren-24


BL-5
1 cun
ST-8

BL-5 (*wuchu*) 'Fifth Place' 1 cun superior to the anterior hairline and 1.5 cun lateral to the midline (directly above **BL-4**, level with **Du-23**)


Hairline
1 cun
Du-23

Du-23 (*shangxing*) 'Upper Star' On the midline, 1 cun superior to the anterior hairline



ST-8 (*touwei*) 'Head's Binding' At the temporal corner of the forehead, on the border of the temporalis muscle and 0.5 cun within the anterior hair line or 4.5 cun lateral to the anterior midline (**Du-24**)


0.5 cun
ST-8
Hairline
G.B.-13

G.B.-13 (*benshen*) 'Root of the Spirit' 0.5 cun superior to the anterior hairline and 3 cun lateral to the midline, on the line between **Du-24** and **ST-8** (= 4.5 cun) at the junction of the lateral and medial third


0.5 cun
ST-8
G.B.-15
Hairline

G.B.-15 (*toulinqi*) 'Head Governor of Tears' On the pupil line when looking straight ahead, 0.5 cun superior to the anterior hairline, at the midpoint of the line between **Du-24** and **ST-8** (= 4.5 cun)


G.B.-15
BL-5
Du-23
ST-8
G.B.-13
BL-4
Du-24
BL-3
G.B.-14
Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
ST-1
Ex-HN-7
ST-2
ST-7
Ex-HN-8
G.B.-2
L.I.-20
S.I.-18
L.I.-19
Du-26
ST-4
ST-5
Ex-HN
Ren-24


BL-4
0.5 cun
ST-8
Hairline
1.5 cun

BL-4 (*qucha*) 'Crooked Curve' 0.5 cun superior to the anterior hairline and 1.5 cun lateral to the midline, or one third of the distance between **Du-24** and **ST-8** (= 4.5 cun)


0.5 cun
Hairline
BL-3

BL-3 (*meichong*) 'Eyebrows' Pouring' 0.5 cun within the anterior hairline, superior to the medial canthus of the eye (**BL-1**)


Du-24
0.5 cun
Hairline

Du-24 (*shenting*) 'Courtyard of the Spirit' On the midline, 0.5 cun superior to the anterior hairline


1 cun
1/3
G.B.-14

G.B.-14 (*yangbai*) 'Yang White' When looking straight ahead on the pupil line, approximately 1 cun superior to the midpoint of the eyebrow (centre of the eyebrow to anterior hairline = 3 cun)


Ex-HN-4 (yuyao)
Orbital margin
Ex-HN (shangming)

Ex-HN-4 (*yuyao*) 'Fish Waist' In the centre of the eyebrow, with the eyes looking straight ahead directly above the pupil


T.B.-23: over the frontozygomatic suture
G.B.-1

T.B.-23 (*sizhukong*) 'Silken Bamboo Hollow' In the depression (frontozygomatic suture) at the lateral end of the eyebrow



BL-2 (*zanzhu*) 'Gathered Bamboo' In a depression at the medial end of the eyebrow, directly superior to the inner canthus of the eye


Ex-HN-3
(yintang)

Ex-HN-3 (*yintang*) 'Hall of Impression' On the anterior midline between the eyebrows



BL-1 (*jingming*) 'Bright Eyes' 0.1 cun superior to the inner canthus of the eye, where spectacles tend to rest



G.B.-1 (*tongziliao*) 'Pupil Crevice' 0.5 cun lateral to the outer canthus of the eye



Ex-HN-7 (*qiuhou*) 'Behind the Ball' On the lower border of the orbit, at the junction of the lateral quarter and the medial three-quarters of the orbital margin



ST-1 (*chengqi*) 'Container of Tears' With the eyes looking straight forward, directly below the centre of the pupil, between the eyeball and the infraorbital ridge



ST-2 (*sibai*) 'Four Whites' When looking straight ahead, directly below the centre of the pupil, in the depression at the infraorbital foramen



Ex-HN-8 (*shangyingxiang or bitong*) 'Upper Yingxiang' or 'Free Nose' At the upper end of the nasolabial groove, at the junction of the maxilla and the nasal cavity (at the border between the nasal bone and cartilage)



ST-7 (*xiaguan*) 'Below the Joint' With the mouth closed in the depression of the mandibular incisure, between the coronoid and condyloid process of the mandible



G.B.-2 (*tinghui*) 'Meeting of Hearing' Anterior to the ear, with the mouth open in the depression at the level of the intertragic notch, on the lower border of the condyloid process of the mandible.



S.I.-18 (*quanliao*) 'Cheek Bone Crevice' In a depression at the intersection of a vertical line through the outer canthus of the eye with the lower border of the zygomatic bone



ST-3 (*juliao*) 'Great Crevice' When looking straight ahead, directly below the centre of the pupil, level with of lower border of the ala nasi.


G.B.-15
BL-5
Du-23
ST-8
G.B.-13
BL-4
Du-24
BL-3
G.B.-14
Ex-HN-4
T.B.-23
BL-2
BL-1
Ex-HN-3
G.B.-1
ST-1
Ex-HN-7
ST-2
Ex-HN-8
G.B.-2
ST-7
L.I.-20
S.I.-18
L.I.-19
Du-26
ST-4
ST-5
Ex-HN
Ren-24


Midpoint of the lateral border of the ala nasi
L.I.-20
Nasolabial groove

L.I.-20 (*yingxiang*) 'Welcome Fragrance' In the nasolabial groove, at the level of the midpoint of the lateral border of the ala nasi.


L.I.-19
Du-26
0.5 cun

L.I.-19 (*kouheliao*) 'Mouth Grain Crevice' Directly inferior to the lateral margin of the nostril, level with **Du-26**, which is located slightly superior to the midpoint of the philtrum (meeting point of the L.I. channel)


L.I.-19
Du-26
0.5 cun

Du-26 (*renzhong* or *shuigou*) 'Man's Middle' Below the nose, on the midline, at the junction of the upper and middle third of the philtrum



ST-4 (*dicang*) 'Earth Granary' When looking straight ahead on the pupil line, approximately 0.4 cun lateral to the corner of the mouth



ST-5 (*daying*) 'Great Welcome' On the lateral mandible, anterior to the masseter (ask the patient to clench the teeth); a branch of the facial artery is palpable here


Ex-HN *jiachengjiang*
Ren-24

Ex-HN (*jiachengjiang*) 'Adjacent to Container of Fluids' At the same level and 1 cun lateral to **Ren-24** (chengjiang)



Ren-24 (*chengjiang*) 'Container of Fluids' On the midline, in the mentolabial groove below the lower lip

7.2 Head and Lateral Aspect of the Neck


Du-20
G.B.-18
G.B.-13
ST-8
G.B.-14
G.B.-8
T.B.-20
T.B.-23
Ex-HN-5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
ST-7
G.B.-2
S.I.-18
T.B.-17
G.B.-20
G.B.-12
Ex-HN
(*anmian*)
ST-5
ST-6
S.I.-17
T.B.-16
Ren-23
ST-9
L.I.-18
S.I.-16
L.I.-17
ST-12
ST-11


Apex of the ear
Apex of the ear
G.B.-18
2.25 cun
1 cun
Du-20

G.B.-18 (*chengling*) 'Support Spirit' 4 cun superior to the anterior hairline or 1 cun anterior to **Du-20**, on the line connecting **G.B.-15** and **G.B.-20**, or 2.25 cun lateral to the midline (midpoint of the line connecting **ST-8** and **Du-24**)


0.5 cun
ST-8
Hairline
G.B.-13

G.B.-13 (*benshen*) 'Root of the Spirit' 0.5 cun superior to the anterior hairline and 3 cun lateral to the midline, on the line between **Du-24** and **ST-8** (= 4.5 cun) at the junction of the lateral and medial third



ST-8 (*touwei*) 'Head's Binding' At the temporal corner of the forehead, on the border of the temporalis muscle and 0.5 cun within the anterior hair line or 4.5 cun lateral to the anterior midline (**Du-24**)


G.B.-14
1 cun
1/3

G.B.-14 (*yangbai*) 'Yang White' When looking straight ahead on the pupil line, approximately 1 cun superior to the midpoint of the eyebrow (centre of the eyebrow to the anterior hairline = 3 cun)



G.B.-8 (*shuaigu*) 'Leading Valley' 1.5 cun directly superior to the apex of the ear


G.B.-8
G.B.-9
1.5 cun
1/3
T.B.-20
G.B.-10
Approximately
level with the apex

G.B.-9 (*tianchong*) 'Heavenly Rushing' 1.5 cun superior and 0.5 cun posterior to the apex of the ear or 0.5 cun posterior to **G.B.-8**



T.B.-20 (*jiaosun*) 'Minute Angle' Directly superior to the apex of the ear


Du-20
G.B.-18
G.B.-13
ST-8
G.B.-14
G.B.-8
T.B.-20
T.B.-23
Ex-HN-5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
ST-7
G.B.-2
S.I.-18
T.B.-17
G.B.-20
G.B.-12
Ex-HN
(anmian)
ST-5
ST-6
S.I.-17
T.B.-16
Ren-23
L.I.-18
S.I.-16
ST-9
L.I.-17
ST-12
ST-11


T.B.-23:
over the fronto-
zygomatic suture
G.B.-1

T.B.-23 (*sizhukong*) 'Silken Bamboo Hollow' In the depression (frontozygomatic suture) at the lateral end of the eyebrow


Approximately level
with the apex
T.B.-20
G.B.-10
1/3
Approximately level
with the helix root
G.B.-11

G.B.-10 (*fubai*) 'Floating White' At the junction of the upper third with the lower two-thirds of the curved line connecting **G.B.-9** and **G.B.-12**


Eyebrows
Lateral
canthus of the eye
1 cun
Ex-HN-5

Ex-HN-5 (*taiyang*) 'Supreme Yang' In the depression approximately 1 cun posterior to the midpoint between the lateral end of the eyebrow and the outer canthus of the eye



G.B.-1 (*tongziliao*) 'Pupil Crevice' 0.5 cun lateral to the outer canthus of the eye


Mandibular
notch
G.B.-3

G.B.-3 (*shangguan*) 'Above the Joint' In a depression on the upper border of the zygomatic arch, approximately 1 cun anterior to the root of the ear, directly superior to **ST-7** (lower border of the zygomatic arch)


Needle insertion
with the mouth
slightly open
T.B.-21
S.I.-19

T.B.-21 (*ermen*) 'Ear Gate' Anterior to the ear, with the mouth open in the depression at the level of the supratragic notch, slightly superior to the condyloid process of the mandible


Apex of the ear
1/3
Approximately
level with the
helix root
G.B.-11
1/3

G.B.-11 (*touqiaoyin*) 'Yin Portals of the Head' At the junction of the lower third with the upper two-thirds of the curved line connecting **G.B.-9** and **G.B.-12**


S.I.-19
Tragus
Mouth closed*

S.I.-19 (*tinggong*) 'Palace of Hearing' Anterior to the ear with the mouth open, at the level of the middle of the tragus, in a depression between the tragus and condyloid process of the mandible

---

* According to Deadman et al 1998.


ST-7
G.B.-3
Styloid process

ST-7 (*xiaguan*) 'Below the Joint' With the mouth closed in the depression of the mandibular notch, between the coronoid and condyloid process of the mandible


S.I.-19
Tragus
G.B.-2
Mouth closed

G.B.-2 (*tinghui*) 'Meeting of Hearing' Anterior to the ear with the mouth open, in the depression at the level of the intertragic notch, on the lower border of the condyloid process of the mandible



S.I.-18 (*quanliao*) 'Cheek Bone Crevice' In a depression at the intersection of a vertical line through the outer canthus of the eye with the lower border of the zygomatic bone


T.B.-17
Mastoid process
Process

T.B.-17 (*yifeng*) 'Wind Screen' With the mouth open in the depression behind the earlobe, between the mastoid process and the mandible


1 cun
G.B.-20
T.B.-17
Ex-HN-14
(*yiming*)

Ex-HN-14 (*yiming*) 'Eye Brightening' On the occiput, 1 cun posterior to **T.B.-17**, on a line connecting **T.B.-17** and **G.B.-20**


T.B.-17
Transverse process of the atlas
Ex-HN
(*anmian*)
Mastoid process

Ex-HN (*anmian*) 'Peaceful Sleep' Posterior to the ear, midway between **T.B.-17** and **G.B.-20**, posterior to the mastoid process


Occiput
G.B.-20
Lower border of the occiput
G.B.-20
Axis
BL-10
Sternocleido-mastoid

G.B.-20 (*fengchi*) 'Wind Pool' On the lower border of the occipital bone, in the depression between the origins of the sternocleidomastoid and trapezius


Approximately level with the helix root
G.B.-11
1/3
Mastoid process
G.B.-12

G.B.-12 (*wangu*) 'Mastoid Process' In a depression posterior and inferior to the mastoid process



ST-6 (*jiache*) 'Jaw Bone' With the teeth clenched, on the highest prominence of the masseter, approximately one fingerbreadth anterior and superior to the mandibular angle



ST-5 (*daying*) 'Great Welcome' On the lateral mandible, anterior to the masseter (ask the patient to clench the teeth); a branch of the facial artery is palpable here


Du-20
G.B.-18
G.B.-13
ST-8
G.B.-14
G.B.-8
T.B.-20
T.B.-23
Ex-HN-5
G.B.-1
G.B.-11
G.B.-19
T.B.-21
S.I.-19
ST-7
G.B.-2
S.I.-18
T.B.-17
G.B.-20
G.B.-12
Ex-HN
(anmian)
ST-5
ST-6
S.I.-17
T.B.-16
Ren-23
ST-9
L.I.-18
S.I.-16
L.I.-17
ST-12
ST-11


angle
S.I.-17
Sternocleidomastoid

S.I.-17 (*tianrong*) 'Heavenly Appearance' Level with and posterior to the mandibular angle, on the anterior border of the sternocleidomastoid


angle
T.B.-16
S.I.-17
Sternocleidomastoid

T.B.-16 (*tianyou*) 'Window of Heaven' posterior and inferior to the mastoid process, on the posterior border of the sternocleidomastoid, directly level with the mandibular angle


Ren-23
Hyoid bone

Ren-23 (*lianquan*) 'Corner Spring' On the anterior midline, superior to the upper border of the hyoid bone


ST-9
L.I.-18
S.I.-16
Laryngeal prominence

ST-9 (*renying*) Man's Welcome' Approximately 1.5 cun lateral to the anterior midline, level with the laryngeal prominence, at the anterior border of the sternocleidomastoid


ST-9
L.I.-18
S.I.-16
Laryngeal prominence

L.I.-18 (*futu*) 'Support the Prominence' At the level of the laryngeal prominence, between the sternal and clavicular heads of the sternocleidomastoid muscle


ST-9
L.I.-18
S.I.-16
Laryngeal prominence

S.I.-16 (*tianchuang*) 'Heavenly Window' Approximately 3.5 cun lateral to the anterior midline, level with the laryngeal prominence, on the posterior border of the sternocleidomastoid


Laryngeal prominence
ST-9
1/2
ST-10

ST-10 (*shuitu*) 'Water Prominence' On the anterior border of the sternocleidomastoid, at the midpoint of a line connecting **ST-9** and **ST-11**


L.I.-18
Laryngeal prominence
L.I.-17
1 cun

L.I.-17 (*tianding*) 'Heaven's Tripod' 1 cun inferior to the laryngeal prominence, on the posterior border of the sternocleidomastoid


1/2
ST-10
1/2
ST-11

ST-11 (*qishe*) 'Abode of Qi' On the upper border of the clavicle, between the tendons of the sternal and clavicular heads of the sternocleidomastoid



ST-12 (*quepen*) 'Empty Basin' In the supraclavicular fossa, superior to the midpoint of the clavicle, approximately 4 cun lateral to the midline

7.3 Occipital Region


Du-20
BL-8
Du-19
Du-18
G.B.-8
G.B.-19
BL-9
Du-17
Du-16
G.B.-20
G.B.-12
Du-15
BL-10
G.B.-21
Du-14


5 cun
Du-20
Apex of the ear
Apex of the ear

Du-20 (*baihui*) 'Hundred Meetings' At the junction of a line connecting the apices of the ears and the midline, 5 cun from the anterior or 7 cun from the posterior hairline respectively


Apex of the ear
Apex of the ear
Du-20
0.5 cun
BL-8

BL-8 (*luoque*) 'Declining Connection' 1.5 cun lateral to the midline and 5.5 cun superior to the anterior hairline, or 0.5 cun posterior to **Du-20**


Du-20
BL-8
Du-19
Du-18
G.B.-8
G.B.-19
BL-9
Du-17
Du-16
G.B.-20
G.B.-12
BL-10
Du-15
G.B.-21
Du-14


1.5 cun
Du-20
Du-19

Du-19 (*houding*) 'Behind the Crown' On the midline, 1.5 cun posterior to **Du-20** or 3 cun superior to **Du-17**


Du-18
1.5 cun
External occipital protuberance
Du-17

Du-18 (*qiangjian*) 'Unyielding Space' On the posterior midline, 1.5 cun superior to **Du-17** or 3 cun posterior to **Du-20**



G.B.-8 (*shuaigu*) 'Leading Valley' 1.5 cun directly superior to the apex of the ear


2.25 cun
External occipital protuberance
Du-17
G.B.-19
1.5 cun

G.B.-19 (*naokong*) 'Brain Hollow' Level with the upper border of the external occipital protuberance (**Du-17**), on the line connecting **G.B.-15** and **G.B.-20**, and 2.25 cun lateral to the midline


M
1.3 cun
External occipital protuberance
Du-17
BL-9
Du-16
approximately 2.5 cun

BL-9 (*yuzhen*) 'Jade Pillow' 2.5 cun superior to the posterior hairline and 1.3 cun lateral to the midline or **Du-17** (directly superior to the external occipital protuberance)


External occipital protuberance
Du-17
Du-16
1.5 cun

Du-17 (*naohu*) 'Brain's Door' On the midline, in a depression superior to the external occipital protuberance, approximately 2.5 cun superior to the posterior hairline, 1.5 cun superior to **Du-16**


Approximately level with the helix root
G.B.-11
1/3
Mastoid process
G.B.-12

G.B.-12 (*wangu*) 'Mastoid Process' In a depression posterior and inferior to the mastoid process


Occiput
G.B.-20
Lower border of the occiput
G.B.-20
Axis
BL-10
Sternocleido-mastoid

G.B.-20 (*fengchi*) 'Wind Pool' On the lower border of the occipital bone, in the depression between the origins of the sternocleidomastoid and trapezius


Atlas
Du-16
External occipital protuberance
G.B.-20
Occiput
Lower border of the occiput
G.B.-20

Du-16 (*fengfu*) 'Palace of Wind' On the posterior midline, directly below the external occipital protuberance, in the depression between the origins of the trapezius


Du-16
Occiput
G.B.-20
Lower border of the occiput
G.B.-20
Sternocleido-mastoid
Axis
BL-10

BL-10 (*tianzhu*) 'Celestial Pillar' Below the lower border of the occiput, approximately 1.3 cun lateral to the midline (**Du-15**), at the insertion of the trapezius


Occiput
G.B.-20
Lower border of the occiput
G.B.-20
Axis
BL-10
Sternocleido-mastoid
Du-15

Du-15 (*yamen*) 'Gate of Muteness' On the posterior midline, in the depression between the 1st (atlas) and 2nd cervical vertebrae (axis = first palpable spinous process), approximately 0.5 cun below **Du-16**


G.B.-21
Spinous process C7
1/2
T.B.-15

G.B.-21 (*jianjing*) 'Shoulder Well' At the highest point of the shoulder, midway between the lower border of the spinous process of C7 and the lateral extremity of the acromion


Base of the scapular spine
Spinous process C7
Du-14

Du-14 (*dazhui*) 'Great Vertebra' Below the spinous process of C7

7.4 Vertex


BL-8
Du-20
G.B.-18
BL-7
Du-21
G.B.-17
BL-6
Du-22
G.B.-16
BL-5
Du-23
BL-3
G.B.-15
BL-4
Du-24
Hairline


Apex of the ear
Apex of the ear
Du-20
0.5 cun
BL-8

BL-8 (*luoque*) 'Declining Connection' 1.5 cun lateral to the midline and 5.5 cun superior to the anterior hairline, or 0.5 cun posterior to **Du-20**


5 cun
Du-20
Apex of the ear
Apex of the ear

Du-20 (*baihui*) 'Hundred Meetings' At the junction of a line connecting the apices of the ears and the midline, 5 cun from the anterior or 7 cun from the posterior hairline respectively


BL-8
Du-20
G.B.-18
BL-7
Du-21
G.B.-17
BL-6
Du-22
G.B.-16
BL-5
Du-23
BL-3
G.B.-15
BL-4
Du-24
Hairline


Apex of the ear
Apex of the ear
G.B.-18
2.25 cun
1 cun
Du-20

G.B.-18 (*chengling*) 'Support Spirit' 4 cun superior to the anterior hairline or 1 cun anterior to **Du-20**, on the line connecting **G.B.-15** with **G.B.-20**, or 2.25 cun lateral to the midline (midpoint of the line connecting **ST-8** and **Du-24**)


4 cun
1.5 cun
Apex of the ear
Apex of the ear
1 cun
BL-7
Du-20

BL-7 (*tongtian*) 'Heavenly Connection' 1.5 cun lateral to the midline and 4 cun superior to the anterior hairline or 1 cun anterior to **Du-20**


Apex of the ear
Apex of the ear
Du-21
1.5 cun

Du-21 (*qianding*) 'In Front of the Crown' On the midline, 1.5 cun anterior to **Du-20** or 3.5 cun above the anterior hairline


GB-17
2.25 cun
Apex of the ear
2.5 cun
Apex of the ear
Du-20

G.B.-17 (*zhengying*) 'Upright Nutrition' 2.5 cun superior to the anterior hairline, on the pupil line, on the line connecting **G.B.-15** and **G.B.-20** (= 2.25 cun lateral to the midline or midway between **Du-23** and **ST-8**)


2.5 cun
1/2
BL-6
Apex of the ear
Apex of the ear
1.5 cun
1/2
Du-20

BL-6 (*chengguang*) 'Receiving Light' 2.5 cun superior to the anterior hairline and 1.5 cun lateral to the midline, or one-third of the distance between **Du-24** and **ST-8**


Du-22
Apex of the ear
3 cun
Apex of the ear

Du-22 (*xinhui*) 'Fontanelle Meeting' On the midline, 2 cun superior to the anterior hairline or 3 cun anterior to **Du-20**


G.B.-16
2.25 cun
Apex of the ear
3.5 cun
Apex of the ear

G.B.-16 (*muchuang*) 'Window of the Eye' 1.5 cun superior to the anterior hairline, on the pupil line, on the line connecting **G.B.-15** and **G.B.-20** (= 2.25 cun lateral to the midline or midway between **Du-24** and **ST-8**)


BL-5
1 cun
ST-8

BL-5 (*wuchu*) 'Fifth Place' 1 cun superior to the anterior hairline and 1.5 cun lateral to the midline (directly above **BL-4**, level with **Du-23**)


Hairline
1 cun
Du-23

Du-23 (*shangxing*) 'Upper Star' On the midline, 1 cun superior to the anterior hairline


0.5 cun
ST-8
GB-15
Hairline

G.B.-15 (*toulinqi*) 'Head Governor of Tears' On the pupil line when looking straight ahead, 0.5 cun superior to the anterior hairline, at the midpoint of the line between **Du-24** and **ST-8** (= 4.5 cun)


BL-4
0.5 cun
ST-8
Hairline
1.5 cun

BL-4 (*qucha*) 'Crooked Curve' 0.5 cun superior to the anterior hairline and 1.5 cun lateral to the midline, or one-third of the distance between **Du-24** and **ST-8** (= 4.5 cun)


0.5 cun
Hairline
BL-3

BL-3 (*meichong*) 'Eyebrows' Pouring' 0.5 cun within the anterior hairline, superior to the medial canthus of the eye (**BL-1**)


0.5 cun
Hairline
Du-24

Du-24 (*shenting*) 'Courtyard of the Spirit' On the midline, 0.5 cun superior to the anterior hairline

7.5 Back


S.I.-15
S.I.-12
S.I.-10
14
11
13
42
13
12
44
15
11
46
17
9
Ex-B-3
47
18
8
49
20
6
Ex-B-4
52
23
4
Ex-B-5
Ex-B-5
Ex-B-7
25
3
Ex-B-6
Ex-B-8
54
30
Ex-B-11
2
1
36
Du mai
Bladder channel, lateral branch
Bladder channel, medial branch


Spinous process C7
Spinous process T1
Spinous process T3
Spinous process T7
Spinous process T12
Du-14
13
12
11
10
9
8
7
Du-6
BL-11
12
13
14
15
16
17
18
19
20
BL-21
BL-41
42
43
44
45
46
47
48
49
BL-50


Spinous process L1
Spinous process L2
Spinous process L3
Spinous process L4
Spinous process L5
Level of the iliac crests
Du-5
Du-4
Ex-B-5
Du-3
Ex-B8
BL-22
BL-23
BL-24
BL-25
BL-26
BL-27
BL-28
BL-29
BL-30
BL-51
BL-52
BL-53
BL-54
BL-31
BL-32
BL-33
BL-34
BL-35
Du-1

Vertebra	**Below the spinous process or in the sacral foramen**	**0.5 cun lateral to the midline, level with the lower border of the spinous process or sacral foramen**	**1.5 cun lateral to the midline, level with the lower border of the spinous process or sacral foramen**	**3 cun lateral to the midline, level with the lower border of the spinous process or sacral foramen**
C7	Du-14	Ex-B-1 *(dingchuan)*	**2 cun lateral** S.I.-15	**3.5 cun lateral** Ex-B (*jiehexue*)
T1	Du-13	A point of Ex-B-2 (*huatuojiaji*)	BL-11	S.I.-14
T2		A point of Ex-B-2 (*huatuojiaji*)	BL-12	BL-41
T3	Du-12	A point of Ex-B-2 (*huatuojiaji*)	BL-13	BL-42
T4		A point of Ex-B-2 (*huatuojiaji*)	BL-14	BL-43
T5	Du-11	A point of Ex-B-2 (*huatuojiaji*)	BL-15	BL-44
T6	Du-10	A point of Ex-B-2 (*huatuojiaji*)	BL-16	BL-45
T7	Du-9	A point of Ex-B-2 (*huatuojiaji*)	BL-17	BL-46
T8		A point of Ex-B-2 (*huatuojiaji*)	Ex-B-3 (*weiwanxiashu*)	
T9	Du-8	A point of Ex-B-2 (*huatuojiaji*)	BL-18	BL-47
T10	Du-7	A point of Ex-B-2 (*huatuojiaji*)	BL-19	BL-48
T11	Du-6	A point of Ex-B-2 (*huatuojiaji*)	BL-20	BL-49
T12		A point of Ex-B-2 (*huatuojiaji*)	BL-21	BL-50
L1	Du-5	A point of Ex-B-2 (*huatuojiaji*)	BL-22	BL-51/ Ex-B-4 (**3.5 cun lateral**)
L2	Du-4	A point of Ex-B-2 (*huatuojiaji*)	BL-23	BL-52
L3	Ex-B-5 (*xiajishu*)	A point of Ex-B-2 (*huatuojiaji*)	BL-24	Ex-B-5 (according to WHO a set of 3 points)
L4	Du-3	A point of Ex-B-2 (*huatuojiaji*)	BL-25	Ex-B-6/Ex-B-7 (**3.5 cun lateral**)
L5	Ex-B-8	A point of Ex-B-2 (*huatuojiaji*)	BL-26	
1st sacral foramen	BL-31		BL 27	
2nd sacral foramen	BL-32		BL 28	BL-53
3rd sacral foramen	BL-33		BL 29	
4th sacral foramen	BL-34		BL 30	BL-54/Ex-B-11 (3.5 cun lateral)
Sacral hiatus	Du- 2			
		BL-35 (0.5 cun lateral and inferior to Du-2)		
Between the coccyx and the anus	Du-1			

7.6 Frontal and Lateral Thorax and Abdomen


ST-9
12
Ren-22
KID-27
14 26
20
SP-20
25
19
19
16
24
18
17
17
18
22
15
LIV-14
G.B.-24
12
16
22
18
LIV-13
15
25
16
8
14
6
27
14
4
29
12
13
KID-11
SP-12
ST-30
Ren-2
8
7
6
5
4
3
2
1
Sterno-costal angle
Umbilicus
1
2
3
4
Upper border of the pubic symphysis


ST-12
ST-13
27
14
26
SP-20
15
25
SP-19
16
24
SP-18
17
23
SP-17
ST-18
KID-22
ST-19
21
ST-20
20
ST-21
19
SP-16
ST-22
18
ST-23
17
ST-24
SP-15
ST-25
16
Ren-22
Ren-21
Ren-20
Ren-19
Ren-18
Ren-17
Ren-16
Ren-15
Ren-14
Ren-13
Ren-12
Ren-11
Ren-10
Ren-9
Ren-8


SP-15
ST-25
KID-16
Ren-08
ST-26
KID-15
Ren-07
SP-14
Ren-06
ST-27
KID-14
Ren-05
ST-28
KID-13
Ren-04
ST-29
KID-12
Ren-03
SP-13
SP-12
ST-30
KID-11
Ren-02

Anatomical level	***Ren Mai* (midline)**	**KID channel (2 cun lateral to the midline)**	**ST channel (4 cun lateral to the midline)**	**Other (6 cun lateral to the midline)**
Below the clavicle	≈ Ren-21	KID-27	ST-13	LU-2
1st ICS	Ren-20	KID-26	ST-14	LU-1
2nd ICS	Ren-19	KID-25	ST-15	SP-20
3rd ICS	Ren-18	KID-24	ST-16	SP-19
4th ICS	Ren-17	KID-23	ST-17 (nipple)	SP-18/P-1 (1 cun lateral to the nipple)/G.B.-22 (3 cun inferior to the apex of the axilla)/G.B.-23 (1 cun anterior to G.B.-22)
5th ICS	Ren 16	KID-22	ST-18	SP-17
Anatomical level	***Ren mai* (midline)**	**KID-channel (0.5 cun lateral to the midline)**	**ST channel (2 cun lateral to the midline)**	**Other (4 cun lateral to the midline)**
6 cun superior/6th ICS	Ren-14	KID-21	ST-19	LIV-14 (6th ICS)
5 cun superior/7th ICS	Ren-13	KID-20	ST-20	G.B.-24 (7th ICS)
4 cun superior	Ren-12	KID-19	ST-21	
3 cun superior	Ren-11	KID-18	ST-22	SP-16
2 cun superior	Ren-10	KID-17	ST-23	Ex-CA (*weishang*)
1 cun superior	Ren-9		ST-24	≈ LIV-13 (free end of the 11th rib)
Level of umbilicus	Ren-8	KID-16	ST-25	SP-15, G.B.-26 (inferior to the free end of the 12th rib, level with the umbilicus)
1 cun inferior	Ren-7	KID-15	ST-26	
(1.5 cun inferior)	Ren-6			
2 cun inferior	Ren-5	KID-14	ST-27	
(2.5 cun inferior)	Ex-CA (*zhishi*)			
3 cun inferior	Ren-4	KID-13	ST-28	Ex-CA (*tituo*)/Ex-CA (*qimen*)/ Ex-CA (*yijing*)/(4/3/1 cun lateral to the midline)/≈ G.B.-27 (anterior and medical to the ASIS → 3)
4 cun inferior	Ren-3	KID-12	ST-29	Ex-CA (*zigong*), 3 cun lateral to the midline
5 cun inferior **symphysis**	Ren-2	KID-11	ST-30	SP-12 (3.5 cun lateral to the midline)

Note: The intercostal spaces and the ribs curve upwards laterally!

7.7 Posterior Shoulder and Arm


S.I.-15
S.I.-14
G.B.-21
S.I.-12
T.B.-15
T.B.-14
S.I.-10
S.I.-13
S.I.-11
T.B.-13
S.I.-9
L.I.-14
T.B.-12
L.I.-13
T.B.-10
L.I.-11
S.I.-8
L.I.-10
T.B.-9
L.I.-7
S.I.-7
L.I.-6
T.B.-6
T.B.-5
S.I.-6
T.B.-4
L.I.-5
14
11
13
42
13
12
44
15
11
46
17
9
47
18
8
1
2
3
4
5
6
7
8
9
10
11
1
2
3
4
5
6
7
8
9
1
2
3
4
5
6
7
8
9
10
11
12
cun
Bladder channel, outer branch
Bladder channel, inner branch
Du mai


Spinous process C7
G.B.-21
1/2
T.B.-15

G.B.-21 (*jianjing*) 'Shoulder Well' At the highest point of the shoulder, midway between the lower border of the spinous process of C7 and the lateral extremity of the acromion


Spinous process C7
Du-14
S.I.-15

S.I.-15 (*jianzhongshu*) 'Middle Shoulder Shu' 2 cun lateral to the lower border of the spinous process of the T7 (**Du-14**)


Levator
scapulae
Spinous process C7
Spinous process T1
S.I.-14
S.I.-13
Du-13
BL-11

S.I.-14 (*jianwaishu*) 'Outer Shoulder Shu' 3 cun lateral to the lower border of the spinous process of the T1 (**Du-13**), at the insertion of the levator scapulae


Spinous process C7
G.B.-21
1/2
T.B.-15
1/2

T.B.-15 (*tianliao*) 'Heavenly Crevice' At the midpoint of an imaginary line between the spinous process of the C7 and the lateral extremity of the acromion


Spinous process C7
S.I.-12
(on the
supraspinatus)

S.I.-12 (*bingfeng*) 'Grasping the Wind' Directly superior to **S.I.-11**, in the centre of the supraspinous fossa


S.I.-10
Border of
the deltoid

S.I.-10 (*naoshu*) 'Upper Arm Shu' With the arm adducted on a line extending in a superior direction from the posterior axillary fold, on the lower border of the scapular spine


Acromio-
clavicular
joint
T.B.-14
L.I.-15

T.B.-14 (*jianliao*) 'Shoulder Crevice' Inferior to the lateral extremity of the acromion between the acromial and spinal portions of the deltoid, or with the arm abducted in the posterior of the two depressions on the shoulder joint


Spinous process C7
Spinous process T1
S.I.-13

S.I.-13 (*quyuan*) 'Crooked Wall' At the medial end of the supraspinous fossa


Spinous process T4
Spinous process T5
S.I.-11
1/3

S.I.-11 (*tianzong*) 'Heavenly Gathering' On the scapula, in a depression on the infraspinatus, one third of the distance from the midpoint of the scapular spine and the inferior angle of the scapula



T.B.-13 (*naohui*) 'Upper Arm Meeting' 3 cun distal to the lateral extremity of the acromion (location of **T.B.-14**), on a line connecting **T.B.-14** and the olecranon, at the junction of this line with the margin of the deltoid


Border of
the deltoid
approximately
1 cun
S.I.-9

S.I.-9 (*jianzhen*) 'True Shoulder' With the arm adducted on a line extending in a superior direction from the posterior axillary fold, on the lower border of the deltoid, 1 cun superior to the posterior axillary fold


Deltoid
L.I.-14

L.I.-14 (*binao*) 'Upper Arm' 7 cun proximal to **L.I.-11**, at the distal end of the deltoid, on a line connecting **L.I.-11** and **L.I.-15**


Midpoint
1 cun
T.B.-12

T.B.-12 (*xiaoluo*) 'Dispersing Luo River' 4 cun proximal to **T.B.-10** on a line connecting the olecranon and the lateral extremity of the acromion (location of **T.B.-14**)


Lateral border
of the biceps
L.I.-13
3 cun

L.I.-13 (*shouwuli*) 'Arm Five Miles' On the lateral aspect of the upper arm, 3 cun proximal to **L.I.-11**


T.B.-10
Olecranon
approximately
1 cun

T.B.-10 (*tianjing*) 'Heavenly Well' With the elbow flexed in a depression approximately 1 cun proximal to the olecranon


90°
L.I.-11
Lateral epicondyle
Olecranon

L.I.-11 (*quchi*) 'Pool at the Crook' With the elbow flexed, on the lateral end of the elbow crease, in a depression between the end of the crease and the lateral epicondyle of the humerus, on the extensor carpi radialis longus muscle


S.I.-15
S.I.-14
G.B.-21
S.I.-12
T.B.-15
T.B.-14
S.I.-10
S.I.-13
S.I.-11
T.B.-13
S.I.-9
L.I.-14
T.B.-12
L.I.-13
T.B.-10
L.I.-11
S.I.-8
L.I.-10
T.B.-9
L.I.-7
S.I.-7
L.I.-6
T.B.-6
T.B.-5
S.I.-6
T.B.-4
L.I.-5
14
13
12
11
9
8
11
13
15
17
18
42
44
46
47
1
2
3
4
5
6
7
8
9
10
11
12
cun
Bladder channel, outer branch
Bladder channel, inner branch
Du mai


Olecranon
Medial epicondyle of the humerus
S.I.-8

S.I.-8 (*xiaohai*) 'Small Sea' With the elbow flexed in the depression between the olecranon process of the ulna and the medial epicondyle of the humerus


Extensor carpi radialis longus
Anatomical snuffbox
L.I.-11
L.I.-10
L.I.-5
2 cun

L.I.-10 (*shousanli*) 'Arm Three Miles' 2 cun distal to **L.I.-11**, on the line connecting **L.I.-5** and **L.I.-11**


L.I.-11
L.I.-9
L.I.-5

L.I.-9 (*shanglian*) 'Upper Angle' 3 cun distal to **L.I.-11**, on the line connecting **L.I.-5** and **L.I.-11**


L.I.-11
L.I.-8
L.I.-5

L.I.-8 (*xialian*) 'Lower Angle' 4 cun distal L.I.-11, on the line connecting **L.I.-5** and **L.I.-11**


lateral
5 cun
T.B.-9
7 cun
Midpoint of the wrist

T.B.-9 (*sidu*) 'Four Rivers' 5 cun distal to the olecranon or 7 cun proximal to **T.B.-4**, between the radius and the ulna


Ulna
Medial epicondyle of the humerus
5 cun
S.I.-7

S.I.-7 (*zhizheng*) 'Branch of the Upright' 5 cun proximal to the wrist joint space, on the line connecting **S.I.-5** and **S.I.-8**


L.I.-11
L.I.-7
L.I.-5

L.I.-7 (*wenliu*) 'Warm Flow' 5 cun proximal to **L.I.-5** or midway between **L.I.-5** and **L.I.-11**


T.B.-6
3 cun
T.B.-7

T.B.-7 (*huizhong*) 'Ancestral Meeting' 3 cun proximal to **T.B.-4**, between radius and ulna, ulnar to extensor digitorum communis



T.B.-6 (*zhigou*) 'Branch Ditch' 3 cun proximal to **T.B.-4**, between radius and ulna, radial to the tendon of extensor digitorum communis


Cubital crease
L.I.-11
L.I.-6
L.I.-5

L.I.-6 (*pianli*) 'Veering Passage' 3 cun proximal to **L.I.-5**, on the line connecting **L.I.-5** and **L.I.-11**


T.B.-5
Joint space
T.B.-4

T.B.-5 (*waiguan*) 'Outer Pass' 2 cun proximal to **T.B.-4** (on the dorsal wrist joint space, between radius and ulna.


S.I.-6
Styloid process
of the ulna

S.I.-6 (*yanglao*) 'Support the Aged' In the depression radial and proximal to the styloid process of the ulna that forms when turning the hand from a pronated to a supinated position.


Tendons of
extensor
digitorum
Ex-UE-3
(zhongquan)
T.B.-4
Wrist joint space
Tendon of the

T.B.-4 (*yangchi*) 'Yang Pool' On the dorsum of the wrist, in the gap ulnar to the tendons of the extensor digitorum


L.I.-5
Extensor tendon

L.I.-5 (*yangxi*) 'Yang Stream' With the thumb abducted in the depression between the tendons of the extensor pollicis longus and brevis muscles ('anatomical snuff box')

7.8 Anterior Shoulder and Arm


LU-2
LU-1
HE-1
P-1
P-2
LU-3
LU-4
HE-2
LU-5
P-3
HE-3
LU-6
P-4
P-5
P-6
LU-7
LU-8
LU-9
P-7
HE-4
HE-5
HE-6
HE-7
LU-10
LU-11
P-8
HE-8
HE-9
P-9
1
2
3
4
5
6
7
8
9
cun
1
2
3
4
5
6
7
8
9
10
11
12
cun


LU-2
Suprasternal notch
1 cun
Midline

LU-2 (*yunmen*) 'Cloud Gate' 6 cun lateral to the anterior midline, below the clavicle, in the centre of the deltopectoral triangle.


LU-2
Suprasternal notch
1 cun
LU-1
Midline

LU-1 (*zhongfu*) 'Middle Palace' 6 cun lateral to the anterior midline and approximately 1 cun inferior to **LU-2**, slightly medial to the lower border of the coracoid process



HE-1 (*jiquan*) 'Summit Spring' With the arm abducted, in the centre of the axilla, medial to the axillary artery


1 cun
P-1
4th intercostal space

P-1 (*tianchi*) 'Heavenly Pool' In the 4th ICS, 1 cun lateral to the nipple


2 cun
Axillary fold
P-2

P-2 (*tianquan*) 'Heavenly Spring' Between the two heads of the biceps brachii muscle, 2 cun inferior to the axillary fold.


Lateral border of the biceps muscle
LU-3

LU-3 (*tianfu*) 'Palace of Heaven' 3 cun distal to the end of the anterior axillary fold, on the medial aspect of the upper arm, radial to the biceps brachialis


Lateral border of the biceps muscle
LU-4

LU-4 (*xiabai*) 'Clasping the White' 4 cun distal to the end of the anterior axillary fold, on the medial aspect of the upper arm, radial to the biceps brachii


Medial end of the cubital crease
HE-2
Biceps

HE-2 (*qingling*) 'Green Spirit' 3 cun proximal to the cubital crease, on the medial border of the biceps brachii


Biceps tendon
LU-5

LU-5 (*chize*) 'Cubit Marsh' In the cubital crease, radial to the tendon of the biceps brachii


Biceps tendon
P-3
Cubital crease

P-3 (*quze*) 'Marsh at the Crook' In the cubital crease, ulnar to the biceps tendon



HE-3 (*shaohai*) 'Lesser Sea' With the elbow flexed, in the depression between the ulnar end of the cubital crease and the medial epicondyle of the humerus


LU-5 (cubital crease, radial to the biceps tendon)
1/2
Midpoint of the distance
1 cun
1/2
LU-6
LU-9

LU-6 (*kongzui*) 'Maximum Opening' 5 cun distal to **LU-5** or 7 cun proximal to the wrist joint space, on a line connecting **LU-5** and **LU-9**


P-4
Tendon of the flexor
5 cun

P-4 (*ximen*) 'Xi-Cleft Gate' 5 cun proximal to the palmar wrist joint space, between the tendons of palmaris longus and flexor carpi radialis, or 1 cun distal to the midpoint of the line connecting **P-3** and **P-7**



P-5 (*jianshi*) 'Intermediate Messenger' 3 cun proximal to the palmar wrist joint space, between the tendons of palmaris longus and flexor carpi radialis



P-6 (*neiguan*) 'Inner Pass' 2 cun proximal to the palmar wrist joint space, between the tendons of palmaris longus and flexor carpi radialis


Wrist crease
Abductor pollicis longus
Brachioradialis
1.5 cun

LU-7 (*lieque*) 'Broken Sequence' On the radial aspect of the forearm, immediately above the styloid process of the radius, approximately 1.5 cun proximal to the wrist joint space in a V-shaped groove


LU-2
LU-1
HE-1
P-1
P-2
LU-3
LU-4
HE-2
LU-5
P-3
HE-3
LU-6
P-4
P-5
P-6
LU-7
LU-8
LU-9
P-7
HE-4
HE-5
HE-6
HE-7
LU-10
LU-11
P-8
HE-8
HE-9
P-9
1
2
3
4
5
6
7
8
9
cun
1
2
3
4
5
6
7
8
9
10
11
12
cun


1.5 cun
HE-7
HE-4

HE-4 (*lingdao*) 'Spirit Path' 1.5 cun proximal to the palmar wrist joint space, radial to the flexor carpi ulnaris tendon


Abductor pollicis longus
Radialis
LU- 8
1 cun
LU-9
Joint space
Carpal bones

LU-8 (*jingqu*) 'Channel Gutter' 1 cun proximal to the palmar wrist joint space (**LU-9**), lateral to the radial artery


HE-5
Tendon of flexor carpi ulnaris
1 cun
Joint space
Pisiform
HE-7

HE-5 (*tongli*) 'Penetrating the Interior' 1 cun proximal to the palmar wrist joint space, on the radial side of the flexor carpi ulnaris tendon


Abductor pollicis longus
Radialis
LU-8
1 cun
LU-9
Joint space
Carpal bones

LU-9 (*taiyuan*) 'Supreme Abyss' On the wrist joint space, lateral to the radial artery and ulnar to the tendon of abductor pollicis longus



P-7 (*daling*) 'Great Mound' In the centre of the palmar aspect of the wrist joint space ('most distal wrist crease'), between the tendons of palmaris longus and flexor carpi radialis


0.5 cun
HE-7
HE-6

HE-6 (*yinxi*) 'Yin Cleft' 0.5 cun proximal to the palmar wrist joint space, radial to the flexor carpi ulnaris tendon


Tendon of flexor carpi ulnaris
Pisiform
HE- 7
Joint space

HE-7 (*shenmen*) 'Spirit Gate' On the palmar aspect of the wrist joint space ('most distal wrist crease'), in the depression radial to the insertion of the flexor carpi ulnaris tendon


Metacarpal I
Mid-point
LU-10

LU-10 (*yuji*) 'Fish Border' At the midpoint of the palmar border of the 1st metacarpal bone



P-8 (*laogong*) 'Palace of Toil' In the centre of the palm, between the 2nd and 3rd metacarpal bones, slightly closer to the 3rd metacarpal bone. When a fist is made, the point is located beneath the tip of the middle finger



HE-8 (*shaofu*) 'Lesser Palace' When a fist is made, beneath the tip of the little finger, on the palm, between the 4th and 5th metacarpal bones



LU-11 (*shaoshang*) 'Lesser Shang' 0.1 cun from the radial corner of the thumb nail



HE-9 (*shaochong*) 'Lesser Rushing' 0.1 cun lateral to the radial corner of the nail of the little finger



P-9 (*zhongchong*) 'Middle Rushing' On the most distal point of the middle finger

7.9 Dorsum of the Hand


L.I.-1
T.B.-1
S.I.-1
Ex-UE-9
(*baxie*)
L.I.-2
L.I.-3
T.B.-2
S.I.-2
Ex-UE-8
Ex-UE-9
(*baxie*)
T.B.-3
S.I.-3
L.I.-4
Ex-UE-7
Ex-UE-7
S.I.-4
L.I.-5
S.I.-5
T.B.-4
S.I.-6
T.B.-5



L.I.-1 (*shangyang*) 'Shang Yang' On the index finger, 0.1 cun from the radial corner of the nail



T.B.-1 (*guanchong*) 'Rushing Pass' On the ring finger (4th finger), 0.1 cun from the ulnar corner of the nail



S.I.-1 (*shaoze*) 'Lesser Marsh' On the little finger, 0.1 cun from the ulnar corner of the nail


Proximal phalanx II
Metacarpal II
L.I.-2

L.I.-2 (*erjian*) 'Second Space' On the radial aspect of the index finger, distal to the metacarpophalangeal joint at the junction of the shaft and the basis of the proximal phalanx


T.B.-2
Proximal to the interdigital fold

T.B.-2 (*yemen*) 'Fluid Gate' Between the little finger and ring finger, proximal to the margin of the web; locate with the patient making a fist



S.I.-2 (*qiangu*) 'Front Valley' On the ulnar aspect of the little finger, at the junction of the shaft and the base of the proximal phalanx


Metacarpal II
Proximal phalanx II
L.I.-3

L.I.-3 (*sanjian*) 'Third Space' On the radial aspect of the index finger, proximal to the metacarpophalangeal joint at the junction of the shaft and the head of the 2nd metacarpal bone



Ex-UE-8 (*wailaogong/luozhen/xianqiang*) 'Stiff Neck' On the dorsum of the hand, between the 2nd and 3rd metacarpal bones, approximately 0.5 cun proximal to the metacarpophalangeal joints



T.B.-3 (*zhongzhu*) 'Central Islet' On the dorsum of the hand, in the depression between the 4th and 5th metacarpal bones, proximal to the metacarpophalangeal joints. **T.B.-3** is located at the junction between the heads and shafts of the two metacarpals


S.I.-2
S.I.-3
Most distal transverse crease
Junction shaft

S.I.-3 (*houxi*) 'Back Stream' On the ulnar border of the hand, in the depression proximal to the metacarpophalangeal joint, at the junction between the head and shaft of the 5th metacarpal


Metacarpal II
L.I.-4

L.I.-4 (*hegu*) 'Joining Valley' On the radial aspect of the hand, between the 1st and 2nd metacarpal bone, closer to the 2nd metacarpal bone and approximately at its midpoint


Metacarpal II
Ex-UE-7
Metacarpal V

Ex-UE-7 (*yaotongdian/yaotongxue*) 'Lumbar Pair Point' Two points on the dorsum of the hand, between the 2nd/3rd and 4th/5th metacarpal bones


Metacarpal V
S.I.-4
Pisiform
S.I.-5

S.I.-4 (*wangu*) 'Wrist Bone' On the ulnar border of the hand, between the 5th metacarpal and the carpal bones, at the border of the red and white skin


L.I.-5
Extensor tendon

L.I.-5 (*yangxi*) 'Yang Stream' With the thumb abducted in the depression between the tendons of the extensor pollicis longus and brevis muscles ('anatomical snuff box')


Tendons of extensor digitorum
Ex-UE-3 (zhongquan)
T.B.-4
Wrist joint space

T.B.-4 (*yangchi*) 'Yang Pool' On the dorsum of the wrist, in the gap ulnar to the tendons of extensor digitorum


Metacarpal V
S.I.-4
Pisiform
S.I.-5
Wrist joint space

S.I.-5 (*yanggu*) 'Yang Valley' On the ulnar aspect of the wrist, at the level of the lateral joint space


L.I.-1
T.B.-1
S.I.-1
Ex-UE-9
(*baxie*)
L.I.-2
L.I.-3
Ex-UE-8
T.B.-2
S.I.-2
Ex-UE-9
(*baxie*)
L.I.-4
T.B.-3
S.I.-3
Ex-UE-7
Ex-UE-7
S.I.-4
L.I.-5
S.I.-5
T.B.-4
S.I.-6
T.B.-5


S.I.-6
Styloid process
of the ulna

S.I.-6 (*yanglao*) 'Nourishing the Old' In the depression radial and proximal to the styloid process of the ulna that forms when the hand is turned from a pronated to a supinated position


T.B.-5
Joint space
T.B.-4

T.B.-5 (*waiguan*) 'Outer Pass' 2 cun proximal to **T.B.-4** (on the dorsal wrist joint space, between radius and ulna)

7.10 Anterior Leg


ST-25
KID-16
SP-15
Ren-8
SP-14
ST-28
Ren-4
Ren-3
Upper border
of the pubic
symphysis
ST-30
SP-12
Ren-2
ST-31
KID-11
Highest
prominence
of the greater
trochanter
LIV-11
LIV-10
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
cun
19 cun
SP-11
ST-32
ST-33
ST-34
Ex-LE-3
LIV-9
SP-10
Ex-LE-2
Upper patellar
border
Ex-LE-1
Popliteal
crease
ST-35
Ex-LE-4
LIV-8
SP-9
G.B.-34
ST-36
8 cun
ST-37
ST-38
Midpoint
ST-40
ST-39
8 cun
Highest prominence
of the lateral malleolus
ST-41
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
cun


2 cun
4 cun
ST-25
SP-15

SP-15 (*daheng*) 'Great Horizontal' 4 cun lateral to the centre of the umbilicus, on the mamillary line


4 cun
SP-15
1.3 cun
SP-14

SP-14 (*fujie*) 'Abdomen Knot' 4 cun lateral to the anterior midline (mamillary line), 3 cun superior to **SP-13** or 1.3 cun inferior to **SP-15**


SP-13
Upper border
of the pubic
symphysis
0.7 cun
SP-12
Symphysis
0.5 cun
3.5 cun

SP-13 (*fushe*) 'Meeting of the Fu Organs' 4 cun lateral to the anterior midline (mamillary line) and 0.7 cun superior to the upper border of the pubic symphysis


Upper border
of the pubic
symphysis
SP-12
Symphysis
3.5 cun

SP-12 (*chongmen*) 'Rushing Gate' 3.5 cun lateral to the midline, level with the upper border of the pubic symphysis, lateral to the femoral artery


SP-13
Upper border
of the pubic
symphysis
0.7 cun
ST-30
SP-12
Symphysis

ST-30 (*qichong*) 'Rushing Qi' 2 cun lateral to the upper border of the pubic symphysis, medial to the femoral artery; at the level of **Ren-2**


Upper border
of the pubic
symphysis
ST-31

ST-31 (*biguan*) 'Thigh Gate' With the hip joint flexed, in the depression below the anterior superior iliac spine, lateral to the sartorius


Upper border
of the pubic
symphysis
Ren-2
1 cun
LIV-12

LIV-12 (*jimai*) 'Urgent Pulse' In the inguinal groove, 2.5 cun lateral to the midline and 1 cun inferior to the upper border of the symphysis, inferior to **ST-30** and medial to the femoral artery


2 cun
3 cun
LIV-11
LIV-10

LIV-11 (*yinlian*) 'Yin Corner' 2 cun inferior to **ST-30** (level with the upper border of the pubic symphysis), on the lateral border of the adductor longus muscle or approximately 1 cun inferior to where the femoral artery passes the inguinal ligament


2 cun
3 cun
LIV-11
LIV-10

LIV-10 (*zuwuli*) 'Leg Five Miles' On the anterior aspect of the thigh, 3 cun inferior to the upper border of the symphysis, on the lateral border of adductor longus


Sartorius
SP-11

SP-11 (*jimen*) 'Winnowing Gate' 6 cun proximal to **SP-10** at the midpoint of the femur, in the depression between the sartorius and vastus lateralis


ST-32
3 cun
ST-33
6 cun
3 cun
Upper patellar
border

ST-32 (*futu*) 'Crouching Rabbit' 6 cun proximal to the lateral upper border of the patella, on a line connecting with the anterior superior iliac spine


ST-25
KID-16
SP-15
Ren-8
SP-14
ST-28
Ren-4
Ren-3
Upper border of the pubic symphysis
ST-30
Ren-2
Highest prominence of the greater trochanter
ST-31
SP-12
KID-11
LIV-11
LIV-10
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20 cun
19 cun
SP-11
ST-32
ST-33
Ex-LE-3
LIV-9
ST-34
SP-10
Upper patellar border
Ex-LE-2
Ex-LE-1
Popliteal crease
ST-35
Ex-LE-4
LIV-8
G.B.-34
SP-9
ST-36
8 cun
ST-37
ST-38
Midpoint
ST-40
ST-39
8 cun
Highest prominence of the lateral malleolus
ST-41
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16 cun


ST-33
6 cun
3 cun
Upper patellar border

ST-33 (*yinshi*) 'Yin Market' 3 cun superior to the upper lateral border of the patella


Ex-LE-3
1 cun
SP-10
2 cun
Ex-LE-2

Ex-LE-3 (*baichongwo*) 'Hundred Insect Burrow' 3 cun superior and 1 cun medial to the upper medial border of the patella, in a small depression on the vastus medialis muscle or 1 cun superior to **SP-10**



Ex-LE-1 (*kuangu*) 'Hip Bone' A pair of points 2 cun superior to the patella and 1.5 cun lateral and medial to **ST-34**


ST-34
Quadriceps femoris
Upper patellar border
2 cun

ST-34 (*liangqiu*) 'Ridge Mound' 2 cun proximal to the upper lateral border of the patella, in a depression on vastus lateralis


SP-10
2 cun
2 cun

SP-10 (*xuehai*) 'Sea of Blood' With the knee flexed, 2 cun proximal to the medial superior border of the patella. To find: place the right palm on the patient's left patella and locate the point at the tip of the thumb



Ex-LE-2 (*heding/xiding*) 'Crane's Summit' With the knee flexed, at the midpoint of the upper patellar border


Level of the lower patellar border
ST-35

ST-35 (*dubi*) 'Calf's Nose' With the knee flexed, in the depression inferior to the patella and lateral to the patellar ligament; corresponds to the lateral eye of the knee; **Ex-LE-5** (*xiyan*) is the combination of this point and **Ex-LE-4**


Level of the lower patellar border
ST-35
Ex-LE-4

Ex-LE-4 (*neixiyan*) 'Inner Eye of the Knee' Inferior to the patella, in a depression medial to the patellar ligament; **Ex-LE-5** (*xiyan*) is the combination of this point and **ST-35**


G.B.-34
Head of the fibula

G.B.-34 (*yanglingquan*) 'Yang Mound Spring' In the depression anterior and inferior to the head of the fibula


Medial condyle of the tibia
SP-9
Junction of the shaft and medial condyle of the tibia
Gastrocnemius

SP-9 (*yinlingquan*) 'Yin Mound Spring' With the knee flexed in a depression distal to the medial condyle of the tibia. To find: palpate from the medial posterior border of the tibia towards proximal, at roughly the same level as **G.B.-34**


ST-35
3 cun
ST-36

ST-36 (*zusanli*) 'Leg Three Miles' one fingerbreadth (middle finger) lateral to the anterior crest of the tibia, 3 cun distal to **ST-35**


ST-36
3 cun
ST-37

ST-37 (*shangjuxu*) 'Upper Great Void' 1 fingerbreadth lateral to the anterior crest of the tibia, 6 cun distal to **ST-35** or 3 cun distal to **ST-36**


ST-38
ST-40
Crest of the tibia

ST-40 (*fenglong*) 'Abundant Bulge' 2 fingerbreadths lateral to the anterior crest of the tibia, at the midpoint of the line joining **ST-35** ('lateral eye of the knee', level with the knee joint space) and the highest prominence of the lateral malleolus


ST-38 on the tibialis anterior muscle
Crest of the tibia
1 fingerbreadth

ST-38 (*tiaokou*) 'Lines Opening' 1 fingerbreadth lateral to the anterior crest of the tibia, at the midpoint of the line joining **ST-35** ('lateral eye of the knee', level with the knee joint space) and the highest prominence of the lateral malleolus


ST-38
ST-39
1 cun
Crest of the tibia

ST-39 (*xiajuxu*) 'Lower Great Void' 1 cun distal to **ST-38**


Level of the highest prominence of the lateral malleolus
ST-41
Talocrural joint (ankle joint)
Tendon of extensor hallucis longus

ST-41 (*jiexi*) 'Stream Divide' On the ankle, between the tendons of the extensor digitorum and the extensor hallucis longus, at the level of the highest prominence of the lateral malleolus

7.11 Medial Leg


Upper border of the pubic symphysis
18 cun
LIV-10
8 cun
SP-11
LIV-9
2 cun
SP-10
Upper patellar border
Popliteal crease
KID-10
LIV-8
1 Junction of the shaft and medial condyle of the tibia
2
3
4
5
6
7
8
9
10
11
12
13
14
15 cun
Highest prominence of the medial malleolus
SP-9
LIV-7
SP-8
LIV-6
SP-7
LIV-5
KID-9
SP-6
KID-8
KID-7
KID-3
SP-5
SP-1
SP-4
KID-2


2 cun
3 cun
LIV-11
LIV-10

LIV-10 (*zuwuli*) 'Leg Five Miles' On the anterior aspect of the thigh, 3 cun inferior to the upper border of the symphysis, on the lateral border of the adductor longus


Sartorius
SP-11

SP-11 (*jimen*) 'Winnowing Gate' 6 cun proximal to **SP-10** at the midpoint of the femur, in the depression between the sartorius and vastus lateralis



LIV-9 (*yinbao*) 'Yin Wrapping' 4 cun proximal to the medial condyle of the femur, between the sartorius and vastus medialis


2 cun
SP-10
2 cun

SP-10 (*xuehai*) 'Sea of Blood' With the knee flexed, 2 cun proximal to the medial superior border of the patella. To find: place the right palm on the patient's left patella and locate the point at the tip of the thumb



LIV-8 (*ququan*) 'Spring at the Crook' With the knee flexed, at the medial end of the popliteal crease, in the depression anterior to the tendons of semitendinosus and semimembranosus


Tendon of semitendinosus (most prominent tendon)
KID-10

KID-10 (*yingu*) 'Yin Valley' At the medial end of the popliteal crease, between the tendons of semimembranosus and semitendinosus, at the level of the knee joint space


Medial condyle of the tibia
Gastrocnemius
SP-9
Junction of the shaft and medial condyle of the tibia

SP-9 (*yinlingquan*) 'Yin Mound Spring' With the knee flexed, in a depression distal to the medial condyle of the tibia. To find: palpate from the medial posterior border of the tibia towards proximal, at roughly the same level as **G.B.-34**


1 cun
SP-9
LIV-7

LIV-7 (*xiguan*) 'Knee Joint' At the junction of the shaft and the medial condyle of the tibia, 1 cun posterior to **SP-9**


Medial condyle of the tibia
3 cun
SP-9
Junction of the shaft and medial condyle of the tibia
SP-8

SP-8 (*diji*) 'Earth Pivot' 3 cun distal to **SP-9** (at the junction of the shaft and the medial condyle of the tibia) on the posterior border of the tibia


15 cun
0.5 cun
LIV-6
LIV-5
7 cun

LIV-6 (*zhongdu*) 'Central Capital' 7 cun proximal to the highest prominence of the medial malleolus, just posterior to the medial crest of the tibia


SP-7
3 cun
6 cun
SP-6
3 cun

SP-7 (*lougu*) 'Dripping Valley' 6 cun proximal to the highest prominence of the medial malleolus or 3 cun proximal to **SP-6**, on the medial posterior border of the tibia


LIV-5
1/3
5 cun

LIV-5 (*ligou*) 'Woodworm Canal' 5 cun proximal to the highest prominence of the medial malleolus, just posterior to the medial crest of the tibia


LIV-5
KID-9
KID-7
5 cun
KID-3

KID-9 (*zhubin*) 'Guest House' 5 cun proximal to KID-3 and 2 cun posterior to the medial border of the tibia



SP-6 (*sanyinjiao*) 'Three Yin Intersection' 3 cun proximal to the highest prominence of the medial malleolus, posterior border to the medial border of the tibia


KID-8
KID-7
2 cun
KID-3
0.5 cun

KID-8 (*jiaoxin*) 'Exchange Belief' 2 cun proximal to the highest prominence of the medial malleolus, posterior to the medial border of the tibia



KID-7 (*fuliu*) 'Returning Current' 2 cun proximal to KID-3, in a depression on the anterior border of the Achilles tendon


Upper border of the pubic symphysis
18 cun
LIV-10
SP-11
8 cun
LIV-9
SP-10
2 cun
Upper patellar border
Popliteal crease
KID-10
LIV-8
1
Junction of the shaft and medial condyle of the tibia
SP-9
2
LIV-7
3
4
SP-8
5
6
7
LIV-6
8
9
SP-7
LIV-5
10
KID-9
11
SP-6
12
KID-8
KID-7
13
14
KID-3
15 cun
Highest prominence of the medial malleolus
SP-5
SP-1
KID-2
SP-4


Highest prominence of the medial malleolus
KID-3
Achilles tendon

KID-3 (*taixi*) 'Supreme Stream' In the depression between the highest prominence of the medial malleolus and the Achilles tendon


Highest prominence of the medial malleolus
SP-5

SP-5 (*shangqiu*) 'Shang Mound' In the depression at the junction of a vertical line along the anterior border and a horizontal line along the lower border of the medial malleolus. Or: in the depression halfway between the highest prominence of the medial malleolus and the navicular tuberosity



KID-2 (*rangu*) 'Blazing Valley' In a depression at the anterior inferior border of the navicular bone, at the border of the red and white skin



SP-4 (*gongsun*) 'Grandfather Grandson' In a depression distal and inferior to the base of the 1st metatarsal bone, at the border of the red and white skin



SP-1 (*yinbai*) 'Hidden White' On the big toe, 0.1 cun from the medial corner of the nail

7.12 Lateral Leg


G.B.-27
G.B.-28
G.B.-29
G.B.-30
Highest prominence of the greater trochanter
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
cun
BL-36
6 cun
BL-37
G.B.-31
G.B.-32
G.B.-33
BL-40
BL-39
Popliteal crease
G.B.-34
BL-55
BL-56
G.B.-35
G.B.-36
BL-57
BL-58
G.B.-37
G.B.-38
G.B.-39
BL-59
BL-60
G.B.-40
G.B.-42
G.B.-44
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
cun
Highest prominence of the lateral malleolus


G.B.-27
Anterior superior iliac spine
0.5 cun
G.B.-28

G.B.-27 (*wushu*) 'Five Pivots' In the depression medial to the anterior superior iliac spine, approximately level with **Ren-4**


G.B.-27
Anterior superior iliac spine
0.5 cun
G.B.-28

G.B.-28 (*weidao*) 'Linking Path' Anterior and inferior to the anterior superior iliac spine, 0.5 cun anterior and inferior to **G.B.-27**


G.B.-29
1/2
Greater trochanter

G.B.-29 (*juliao*) 'Stationary Crevice' At the midpoint of a line connecting the anterior superior iliac spine and the greater trochanter, at the anterior border of the iliac crest


Sacral hiatus
2/3
G.B.-30
1/3

G.B.-30 (*huantiao*) 'Jumping Circle' With the patient lying on his/her side, at the junction between the medial two-thirds and the lateral third on a line connecting the greater trochanter and the sacral hiatus



BL-36 (*chengfu*) 'Hold and Support' In the gluteal crease, superior to the midpoint of the popliteal crease


BL-37
Semitendinosus

BL-37 (*yinmen*) 'Gate of Abundance' 6 cun distal to **BL-36** (gluteal crease), on a line connecting BL-36 and BL-40 (centre of the popliteal crease), in a gap in the musculature


G.B.-27
G.B.-28
G.B.-29
G.B.-30
Highest prominence of the greater trochanter
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
cun
BL-36
6 cun
BL-37
G.B.-31
G.B.-32
G.B.-33
BL-40
BL-39
Popliteal crease
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
cun
BL-55
G.B.-34
BL-56
G.B.-35
G.B.-36
BL-57
BL-58
G.B.-37
G.B.-38
G.B.-39
BL-59
Highest prominence of the lateral malleolus
BL-60
G.B.-40
G.B.-42
G.B.-44



G.B.-31 (*fengshi*) 'Wind Market' On the lateral aspect of the thigh, approximately 7 cun proximal to the popliteal crease. With the patient standing upright, the point is where the patient's middle fingertip touches the thigh


G.B.-31
2 cun
G.B.-32

G.B.-32 (*zhongdu*) 'Middle Ditch' On the lateral aspect of the thigh, 2 cun inferior to **G.B.-31** or 5 cun superior to the popliteal crease, between vastus lateralis and biceps femoris



G.B.-33 (*xiyangguan*) 'Knee Yang Gate' On the lateral aspect of the knee, with the knee flexed, in the depression between the lateral epicondyle of the femur and the tendon of biceps femoris, approximately 3 cun proximal to **G.B.-34**


1 cun
Popliteal crease
B.L.-40
B.L.-39

BL-39 (*weiyang*) 'Outside of the Crook' At the lateral end of the popliteal crease, on the medial side of the tendon of the long head of the biceps femoris, 1 cun lateral to **BL-40** (in the centre of the popliteal crease).


Popliteal crease
B.L.-40

BL-40 (*weizhong*) 'Middle of the Crook' In the centre of the popliteal crease, between the tendons of the biceps femoris and semitendinosus.


G.B.-34
Head of the fibula

G.B.-34 (*yanglingquan*) 'Yang Mound Spring' In the depression anterior and inferior to the head of the fibula



BL-57 (*chengshan*) 'Support of the Mountain' In the middle of the calf, between the two heads of the gastrocnemius, on a line connecting **BL-40** and **BL-60**, approximately 8 cun distal to **BL-40** (spreading hands technique → 2)



G.B.-36 (*waiqiu*) 'Outer Hill' 7 cun proximal to the highest prominence of the lateral malleolus, on the anterior border of the fibula



G.B.-35 (*yangjiao*) 'Yang Intersection' 7 cun proximal to the highest prominence of the lateral malleolus, on the posterior border of the fibula


cun
1 cun
B.L.-57
B.L.-58

BL-58 (*feiyang*) 'Soaring Upwards' 1 cun distal and 1 cun lateral to **BL-57** or 7 cun proximal to **BL-60**, at the posterior border of the fibula and on the lower border of the gastrocnemius


G.B.-39
3 cun
Highest prominence
of the lateral malleolus

G.B.-39 (*xuanzhong*) 'Suspended Bell' 3 cun proximal to the highest prominence of the lateral malleolus, on the anterior border of the fibula


B.L.-59
3 cun
Highest prominence
of the lateral malleolus
Anterior border
of the Achilles
tendon

BL-59 (*fuyang*) 'Instep Yang' 3 cun superior to **BL-60** (in the depression between the highest prominence of the lateral malleolus and the Achilles tendon)



BL-60 (*kunlun*) 'Kunlun Mountains' In the depression between the Achilles tendon and the highest prominence of the lateral malleolus


Inferior border
of the medial
malleolus
G.B.-40

G.B.-40 (*qiuxu*) 'Large Mound' In the depression anterior and inferior to the lateral malleolus, lateral to the tendons of the extensor digitorum longus muscle.


G.B.-41
G.B.-42
Tendons of
extensor digitorum

G.B.-42 (*diwuhui*) 'Earth Five Meetings' Between the 4th and 5th metatarsal bones, proximal to the metatarsophalangeal joints and medial to the tendon of extensor digitorum longus


Proximal to the
interdigital fold
G.B.-43

G.B.-43 (*jiaxi/xiaxi*) 'Clamped Stream' Between the 4th and the 5th toes, proximal to the margin of the interdigital web



G.B.-44 (*zuqiaoyin*) 'Yin Portals of the Foot' On the 4th toe, 0.1 cun from the lateral corner of the nail

7.13 Dorsum of the Foot


G.B.-40
BL-63
ST-41
SP-5
LIV-4
BL-64
ST-42
G.B.-41
SP-4
BL-65
G.B.-42
LIV-3
BL-66
G.B.-43
ST-43
SP-3
BL-67
ST-44
SP-2
G.B.-44
Ex-LE-10
(*bafeng*)
LIV-1
SP-1
ST-45



BL-63 (*jinmen*) 'Golden Gate' In a depression anterior and inferior to **BL-62** between the calcaneus and the cuboid bone, proximal to the tuberosity of the 5th metatarsal bone


Highest prominence
of the medial malleolus
SP-5

SP-5 (*shangqiu*) 'Shang Mound' In the depression at the junction of a vertical line along the anterior border and a horizontal line along the lower border of the medial malleolus. Or: in the depression halfway between the highest prominence of the medial malleolus and the navicular tuberosity


Inferior border
of the lateral
malleolus
G.B.-40

G.B.-40 (*qiuxu*) 'Large Mound' In the depression anterior and inferior to the lateral malleolus, lateral to the tendons of extensor digitorum longus muscle.


Level of the
highest prominence
of the lateral
malleolus
ST-41
Talocrural joint
[ankle joint]
Tendon of extensor
hallucis longus

ST-41 (*jiexi*) 'Stream Divide' On the ankle, between the tendons of extensor digitorum and extensor hallucis longus, at the level of the highest prominence of the lateral malleolus


Tendon of extensor
hallucis longus
Tibialis anterior
LIV-4

LIV-4 (*zhongfeng*) 'Middle Seal' 1 cun anterior to the prominence of the medial malleolus, medial to the tendon of the tibialis anterior



BL-64 (*jinggu*) 'Capital Bone' Distal to the tuberosity of the 5th metatarsal bone, at the border of the red and white skin


ST-41
Talocrural joint
(ankle joint)
ST-42
Dorsalis pedis

ST-42 (*chongyang*) 'Rushing Yang' On the highest point of the dorsum of the foot, between the tendons of extensor hallucis longus and extensor digitorum longus, directly lateral to where the dorsalis pedis artery may be palpated. The point is bordered proximally by the second and third metatarsal bones and distally by the second and third cuneiform bones. **Alternative location:** sometimes this point may be located lateral to the medial portion of the extensor digitorum longus tendon (joining the second toe)



G.B.-41 (*zulinqi*) 'Foot Governor of Tears' In the depression at the junction of the shafts and the bases of the 4th and 5th metatarsal bones, lateral to the branch of the extensor digitorum longus tendon running to the little toe



SP-4 (*gongsun*) 'Grandfather Grandson' In a depression distal and inferior to the base of the 1st metatarsal bone, at the border of the red and white skin


BL-63
G.B.-40
ST-41
LIV-4
SP-5
BL-64
ST-42
G.B.-41
SP-4
BL-65
G.B.-42
LIV-3
BL-66
G.B.-43
ST-43
SP-3
BL-67
ST-44
SP-2
G.B.-44
Ex-LE-10
(*bafeng*)
LIV-1
SP-1
ST-45


BL-66
BL-65
BL-64

BL-65 (*shugu*) 'Restraining Bone' In the depression proximal to the head of the 5th metatarsal bone, at the border of the red and white skin


Tendons of extensor digitorum
G.B.-41
G.B.-42

G.B.-42 (*diwuhui*) 'Earth Five Meetings' Between the 4th and 5th metatarsal bones, proximal to the metatarsophalangeal joints and medial to the tendon of the extensor digitorum longus


LIV-3
LIV-2
1.5–2 cun
Interdigital fold

LIV-3 (*taichong*) 'Great Rushing' On the dorsum of the foot, in the depression between the 1st and 2nd metatarsal bones, approximately 1.5–2 cun proximal to the interdigital web


Metatarsal III
Metatarsal II
ST-43

ST-43 (*xiangu*) 'Sunken Valley' In the depression between the second and third metatarsal bones, at the junction of the shafts and the heads of these metatarsal bones


Proximal to the interdigital fold
G.B.-43

G.B.-43 (*xiaxi*) 'Clamped Stream' Between the 4th and the 5th toes, proximal to the margin of the interdigital web


BL-66
BL-65
BL-64

BL-66 (*zutonggu*) 'Foot Connecting Valley' In a depression distal to the metatarsophalangeal joint of the little toe



SP-3 (*taibai*) 'Supreme White' In the depression proximal to the head of the 1st metatarsal bone, at the border of the red and white skin



BL-67 (*zhiyin*) 'Reaching Yin' On the little toe, 0.1 cun from the lateral corner of the nail



LIV-2 (*xingjian*) 'Moving Between' Between the 1st and 2nd toe, proximal to the margin of the interdigital web



SP-2 (*dadu*) 'Great Metropolis' On the medial aspect of the big toe, in the depression distal to the first metatarsophalangeal joint, on the border of the red and white skin



ST-44 (*neiting*) 'Inner Court' Between the 2nd and the 3rd toe, proximal to the interdigital fold



G.B.-44 (*zuqiaoyin*) 'Yin Portals of the Foot' On the 4th toe, 0.1 cun from the lateral corner of the nail



LIV-1 (*dadun*) 'Big Mound' On the lateral aspect of the big toe, 0.1 cun proximal and lateral to the corner of the nail



SP-1 (*yinbai*) 'Hidden White' On the big toe, 0.1 cun from the medial corner of the nail



ST-45 (*lidui*) 'Strict Exchange' On the 2nd toe, 0.1 cun from the lateral corner of the nail

7.14 Medial Foot


SP-6
KID-7
KID-8
LIV-4
KID-3
KID-4
SP-5
KID-6
KID-5
SP-1
SP-4
KID-2
SP-3
SP-2



SP-6 (*sanyinjiao*) 'Three Yin Intersection' 3 cun proximal to the highest prominence of the medial malleolus, on the posterior border of the medial crest of the tibia


KID- 8
KID- 7
KID- 3
2 cun

KID-8 (*jiaoxin*) 'Exchange Belief' 2 cun proximal to the highest prominence of the medial malleolus, posterior to the medial border of the tibia.



KID-7 (*fuliu*) 'Returning Current' 2 cun proximal to **KID-3**, in a depression on the anterior border of the Achilles tendon


Tendon of
extensor
pollicis longus
LIV-4

LIV-4 (*zhongfeng*) 'Middle Seal' 1 cun anterior to the prominence of the medial malleolus, medial to the tendon of tibialis anterior


Highest prominence
of the medial malleolus
tendon
KID-3

KID-3 (*taixi*) 'Supreme Stream' In the depression between the highest prominence of the medial malleolus and the Achilles tendon


Highest prominence
of the medial malleolus
SP-5

SP-5 (*shangqiu*) 'Shang Mound' In the depression at the junction of a vertical line along the anterior border and a horizontal line along the lower border of the medial malleolus. Or: in the depression halfway between the highest prominence of the medial malleolus and the navicular tuberosity


Highest prominence
of the medial malleolus
KID-3
KID-4
0.5 cun
KID-5

KID-4 (*dazhong*) 'Great Bell' Anterior to the medial border of the Achilles tendon, superior to its insertion at the calcaneus


KID-6
ca. 1 cun

KID-6 (*zhaohai*) 'Shining Sea' In the depression inferior to the highest prominence of the medial malleolus, over the joint space between the talus and the calcaneus



KID-5 (*shuiquan*) 'Water Spring' 1 cun distal to **KID-3**, in a depression over the joint space between the talus and calcaneus



KID-2 (*rangu*) 'Blazing Valley' In a depression at the anterior inferior border of the navicular bone, at the border of the red and white skin



SP-4 (*gongsun*) 'Grandfather Grandson' In a depression distal and inferior to the base of the 1st metatarsal bone, at the border of the red and white skin



SP-1 (*yinbai*) 'Hidden White' On the big toe, 0.1 cun from the medial corner of the nail



SP-3 (*taibai*) 'Supreme White' In the depression proximal to the head of the 1st metatarsal bone, at the border of the red and white skin



SP-2 (*dadu*) 'Great Metropolis' On the medial aspect of the big toe, in the depression distal to the first metatarsophalangeal joint, on the border of the red and white skin

7.15 Lateral Foot


BL- 60
G.B.- 40
BL- 62
G.B.- 41
G.B.- 42
G.B.- 43
G.B.- 44
BL- 61
BL- 63
BL- 64
BL- 67
BL- 66
BL- 65



BL-60 (*kunlun*) 'Kunlun Mountains' In the depression between the Achilles tendon and the highest prominence of the lateral malleolus


Inferior border of the lateral malleolus
G.B.-40

G.B.-40 (*qiuxu*) 'Large Mound' In the depression anterior and inferior to the medial malleolus, lateral to the tendons of extensor digitorum longus muscle.


Inferior border of the lateral malleolus
BL-62

BL-62 (*shenmai*) 'Extending Vessel' In a depression directly inferior to the highest prominence of the lateral malleolus, over the joint space between the talus and calcaneus



G.B.-41 (*zulinqi*) 'Foot Governor of Tears' In the depression at the junction of the shafts and the bases of the 4th and 5th metatarsal bones, lateral to the branch of the extensor digitorum longus tendon running to the little toe


G.B.-41
Tendons of extensor digitorum
G.B.-42

G.B.-42 (*diwuhui*) 'Earth Five Meetings' Between the 4th and 5th metatarsal bones, proximal to the metatarsophalangeal joints and medial to the tendon of extensor digitorum longus



BL-61 (*pucan*) 'Servant's Respect' In a depression on the calcaneus, approximately 1.5 cun inferior to **BL-60**


Proximal to the interdigital fold
G.B.-43

G.B.-43 (*xiaxi*) 'Clamped Stream' Between the 4th and the 5th toes, proximal to the margin of the interdigital web



BL-63 (*jinmen*) 'Golden Gate' On the lateral aspect of the foot, proximal to the tuberosity of the 5th metatarsal bone, in a depression anterior and inferior to **BL-62** between the calcaneus and the cuboid bone



G.B.-44 (*zuqiaoyin*) 'Yin Portals of the Foot' On the 4th toe, 0.1 cun from the lateral corner of the nail



BL-67 (*zhiyin*) 'Reaching Yin' On the little toe, 0.1 cun from the lateral corner of the nail



BL-65 (*shugu*) 'Restraining Bone' In the depression proximal to the head of the 5th metatarsal bone, at the border of the red and white skin



BL-64 (*jinggu*) 'Capital Bone' Distal to the tuberosity of the 5th metatarsal bone, at the border of the red and white skin



BL-66 (*zutonggu*) 'Foot Connecting Valley' In a depression distal to the metatarsophalangeal joint of the little toe

8 Point Categories and Point Selection

Claudia Focks

There are a total of 361 acupuncture points located on the channels (→ Chapter 1). Translated literally from the Chinese language, the meaning of the word for 'point' is rather 'opening' or 'hole'. Stimulation of the points can be achieved through massage (in acupressure) or through the insertion of needles (in acupuncture). Besides the regular acupuncture points, there exist a wide variety of so-called extra points, located outside the pathways of the channels. The most commonly used of these extra points are described in Chapter 6, as classified by the WHO.

The acupuncture points are effective

- **locally** (for example, points on the elbow treat disorders of the elbow)
- **regionally** (the channel pathway – for example, points on the arm treat disorders of the upper extremity)
- some points have an effect on their **pertaining *zangfu*-**Organ
- some points have **additional actions** such as calming the *shen* or eliminating Heat.

The following table provides an overview for the general indications of the channel points (modified after Ellis and Wiseman 1991)

Indications of the channel points

Channel	Indications		
Hand-Yin channels			
LU	Lungs, throat		Disorders of the thoracic region
P	Heart, Stomach	Spirit (*shen*) disorders	
HE	Heart		
Hand-Yang channels			
L.I.	Face, mouth, occiput, teeth, nose		Eyes, disorders of the throat, febrile diseases
T.B.	Head/lateral costal region	Disorders of the ears	
S.I.	Occipital region, shoulder, scapula, *shen* disorders		
Foot-Yin channels			
SP	Spleen, Stomach, intestines		Urogenital disorders, menstrual disorders, vaginal discharge, spirit (*shen*) disorders
LIV	Liver, genitalia		
KID	Kidneys, Lungs, throat		
Foot-Yang channels			
ST	Frontal aspect of the head, face, mouth, teeth, throat, Stomach, intestines		Psychoemotional disorders (*shen* disorders), febrile colds
G.B.	Lateral aspect of the head, ears, lateral costal region	Disorders of the eyes	
BL	Posterior aspect of the head, lower back		

8.1 Point Categories

Certain acupuncture points or groups of points are categorised according to their actions or location on their respective channels. (For an overview of these points and point groups → inside back cover.)

8.1.1 *Yuan*-Source Points

At the *yuan*-source points, the Original *Qi* (*yuan qi* → 1.1.4) of the respective Organ system emerges to the surface of the body.

Location: near the hand or ankle.



Points

Yuan-source points of the Yin channels

LU-9 (*taiyuan*)	**SP-3** (*taibai*)	**HE-7** (*shenmen*)
KID-3 (*taixi*)	**P-7** (*daling*)	**LIV-3** (*taichong*)

- On the Yin channels the *yuan*-source point is always the **3rd point** from the distal end of the channel
- They are identical with the *shu*-stream points and the Earth point of the channel

Function

- They tonify deficiency or weakness of their pertaining *zang*-Organ
- They regulate the Yin/Yang balance, restoring homeostasis
- As Earth points they have a ‘grounding’ effect on the body, the emotions and the mind.

Yuan-source points of the Yang channels

L.I.-4 (*hegu*)	**ST-42** (*chongyang*)	**S.I.-4** (*wangu*)
BL-64 (*jinggu*)	**T.B.-4** (*yangchi*)	**G.B.-40** (*qiuxu*)

- On the Yang channels the *yuan*-source point is always the **4th point** from the distal end of the channel, except for the G.B. channel (5th point)
- Regarding the energetics of the channel, they are all located between the *shu*-stream point and the *jing*-river point.

Function

- Their main function is to expel pathogenic factors in excess syndromes
- They tonify their pertaining *fu*-Organ.

Clinical application

Diagnosis

Disorders of a particular channel or its pertaining *zangfu*-Organ will often manifest themselves with tenderness, skin changes such as discolorations, swellings, redness, etc. in the area of the respective *yuan*-source point.

Therapy

- For deficiency of the relevant channel or Organ, use tonifying needling techniques; for excess, use reducing techniques
- Combine with the *luo*-connecting point of its Interiorly–Exteriorly paired channel (→ 1.2.2) in order to increase the therapeutic effect and to balance Yin and Yang (→ 8.3.3)
- Combine with the respective Back-*shu* point (→ 8.1.4) for disorders of the *zangfu*-Organs

8.1.2 *Luo*-Connecting Points

The *luo*-connecting points are located in those regions of the body where the *luo*-network vessels (→ 1.5) branch out, connecting the Interiorly–Exteriorly paired Yin and Yang channels (→ 1.2.2).





Points

The 12 *luo*-connecting points of the primary channels are located between the fingers and the elbow on the upper extremity and between the toes and the knee on the lower extremity.

- *Luo*-connecting points of the primary Yin channels
  - hand Yin channels: **LU-7** (*lieque*), **P-6** (*neiguan*), **HE-5** (*tongli*)
  - foot Yin channels: **SP-4** (*gongsun*), **LIV-5** (*ligou*), **KID-4** (*dazhong*)
- *Luo*-connecting points of the primary Yang channels
  - hand Yang channels: **L.I.-6** (*pianli*), **T.B.-5** (*waiguan*), **S.I.-7** (*zhizheng*)
  - foot Yang channels: **ST-40** (*fenglong*), **G.B.-37** (*guangming*), **BL-58** (*feiyang*)
- *Luo*-connecting points of the *ren mai:* **Ren-15** (*jiuwei*); action: regulates the *luo*-connecting vessels of the Yin channels; indication: abdominal diseases and disorders
- *Luo*-connecting points of the *du mai:* **Du-1** (*changqiang*); action: regulates the *luo*-connecting vessels of the Yang channels; indication: disorders of the back
- Great *luo*-connecting point of the Spleen: **SP-21** (*dabao*); action: connects with all *luo*-vessels and governs all *luo* and Blood vessels of the body; indication: disorders of the joint, general weakness and pain
- Great *luo*-connecting point of the Stomach: ***xu li****, near the left **ST-18**; moxibustion is contraindicated, only superficial needling is recommended. Indication: breathing and heart disorders such as asthma, dyspnoea, emphysema and bradycardia, also for shortness of breath due to anxiety attacks.

Clinical application

Diagnosis

- In excess syndromes the *luo* vessels often become visible near the *luo*-connecting points, for example skin discolorations and swellings may occur. With pain due to Cold the predominant colour may be bluish to greenish, with Heat syndromes reddish, with chronic stagnation and stasis dark to dark purple.
- In deficiency syndromes there are often no colour changes. However, in severe chronic cases (for example severe Qi deficiency) there will more likely be distinct muscular flaccidity, presenting as a dip or depression in the area of the point.

Therapy

- For disorders of the pertaining *zangfu*-Organ or channel
- For diseases of the Interiorly–Exteriorly paired Organ or channel
- For disorders due to the accumulation of pathogenic factors or substances, for example Qi stagnation, Blood stasis, retention of Dampness or Phlegm
- For psychoemotional problems, especially *luo*-connecting points of the Yin channels, for example classically **P-6** (*neiguan*) and **HE-5** (*tongli*)
- Bloodletting (three-edged needle, lancet or plum-blossom needle) on the *luo*-connecting point of the affected channel: this is particularly indicated for excess syndromes with Qi stagnation and Blood stasis. For more details on point selection ➞ 8.3.3

8.1.3 *Xi*-Cleft Points

Synonyms: Accumulation points (Maciocia)
The *xi*-cleft points are all located between the fingers and the elbow on the upper extremity and between the toes and the knee on the lower extremity. Only **ST-34** is located more proximally on the thigh.

---

* *Xu li* is only rarely mentioned in Western literature. The location and significance of this point is based on *Su Wen*, chapter 18: 'The geat *luo* vessel of the Stomach is called *xu li* and emerges at **ST-18** under the left breast, passes through the diaphragm and ascends to connect with the Lung. One can feel its pulsation with the hand. It is the place where the *zong qi* (➞ 1.1.4) of the channels resides.' (Ngyen Van Nghi, 1989). *Xu li* is the only *luo*-connecting vessel to directly emerge from a *fu*-Organ. It plays an important role in Korean acupuncture.


Yin
Yang
LU-6
P-4
HE-6
L.I.-7
T.B.-7
S.I.-6
ST-34
SP-8
KID-9
LIV-6
KID-8
KID-5
BL-59
G.B.-36
G.B.-35
BL-63

Points

Xi-cleft points of the primary Yin channels

Hand Yin channels

LU-6 (*kongzui*)
HE-6 (*yinxi*)
P-4 (*ximen*)

Foot Yin channels

SP-8 (*diji*)
KID-5 (*shuiquan*)
LIV-6 (*zhongdu*)

Xi-cleft points of the primary Yang channels

Hand Yang channels

L.I.-7 (*wenliu*)
S.I.-6 (*yanglao*)
T.B.-7 (*huizhong*)

Foot Yang channels

ST-34 (*liangqiu*)
BL-63 (*jinmen*)
G.B.-36 (*waiqiu*)

Xi-cleft points of the extraordinary vessels (point names printed in blue)

- *Xi*-cleft point of the *yang qiao mai*: **BL-59** (*fuyang*)
- *Xi*-cleft point of the *yin qiao mai*: **KID-8** (*jiaoxin*)
- *Xi*-cleft point of the *yang wei mai*: **G.B.-35** (*yangjiao*)
- *Xi*-cleft point of the *yin wei mai*: **KID-9** (*zhubin*)

Clinical application

Diagnosis

- They provide information about disorders affecting their pertaining channel or *zangfu*-Organ
  - Excess: acute, intense pain upon pressure or redness and swelling in the area of the point
  - Deficiency: dull, mild pain upon pressure or presence of a depression in the area of the point

Therapy

- Mainly used for acute and/or therapy-resistant disorders, especially for excess conditions and pain of the affected channel and/or pertaining *zangfu*-Organ. In patients with a robust constitution use reducing needling techniques.
- Add the *xi*-cleft points of the Yin channels for disorders of the Blood.
- In order to increase the therapeutic effect, the *xi*-cleft point may be combined with a relevant *hui*-meeting point (→ 8.1.7).

8.1.4 Back-*Shu* Points

Synonym: Back-transporting points

The Back-*shu* points are located on the inner branch of the BL channel at the level of their pertaining *zangfu*-Organ. They are mostly at the same level as the corresponding Front-*mu* point (→ 8.1.5).


Lung BL-13
Pericardium BL-14
Heart BL-15
Liver BL-18
Gall Bladder BL-19
Spleen BL-20
Stomach BL-21
Triple Burner BL-22
Kidney BL-23
Large Intestine BL-25
Small Intestine BL-27
Bladder BL-28

Points

Organ	Back-*shu* point
Lung	**BL-13** (*feishu*)
Large Intestine	**BL-25** (*dachangshu*)
Stomach	**BL-21** (*weishu*)
Spleen	**BL-20** (*pishu*)
Heart	**BL-15** (*xinshu*)
Small Intestine	**BL-27** (*xiaochangshu*)
Bladder	**BL-28** (*pangguangshu*)
Kidney	**BL-23** (*shenshu*)
Pericardium	**BL-14** (*jueyinshu*)
Triple Burner	**BL-22** (*sanjiaoshu*)
Gall Bladder	**BL-19** (*danshu*)
Liver	**BL-18** (*ganshu*)

Clinical application

Diagnosis

- Often spontaneously tender and/or sensitive upon pressure in disorders of the pertaining *zangfu*-Organ

Therapy

- Mainly used for disorders of the corresponding *zangfu*-Organ. These points have a tonifying effect for chronic disorders and deficiency syndromes, but can also be used for acute disorders of their pertaining *zangfu*-Organ.
- For disorders of the sensory organs, use the Back-*shu* point of the pertaining *zangfu*-Organ.
  Example: for disorders of the eyes, needle the Back-*shu* point of the Liver **BL-18** (*ganshu*).

For excess syndromes, the Back-*shu* points can be needled with reducing needling techniques; for deficiency syndromes, tonifying needling techniques should be applied. When Cold signs are present, moxibustion can also be used. The needles should not be retained longer than 10 minutes – longer needle retention can have a sedating effect and lead to tiredness.

8.1.5 Front-*Mu* Points

Synonym: Alarm points
The Front-*mu* points are located on the thorax and abdomen in the area of their pertaining *zangfu*-Organs.



Points

Organ	Back-*shu* point
Lung	**LU-1** (*zhongfu*)
Large Intestine	**ST-25** (*tianshu*)
Stomach	**Ren-12** (*zhongwan*)
Spleen	**LIV-13** (*zhangmen*)
Heart	**Ren-14** (*juque*)
Small Intestine	**Ren-4** (*guanyuan*)
Bladder	**Ren-3** (*zhongji*)
Kidney	**G.B.-25** (*jingmen*)
Pericardium	**Ren-17** (*danzhong*)
Triple Burner	**Ren-5** (*shimen*)
Gall Bladder	**G.B.-24** (*riyue*)
Liver	**LIV-14** (*qimen*)

Clinical application

Diagnosis

- Often spontaneously tender or sensitive upon pressure in disorders of the pertaining *zangfu*-Organ

Therapy

- Used to regulate the pertaining *zangfu*-Organ. For excess syndromes use reducing needling techniques; for deficiency syndromes use tonifying methods.
- Commonly used point combinations:
  – *Shu–mu* method (➞ 8.3.2)
  – For disorders of the *fu*-Organs: simultaneous needling of the lower *he*-sea point (➞ 8.1.9) and the Front-*mu* point of the affected *fu*-Organ.

8.1.6 The Five *Shu*-Transporting Points

The five *shu*-transporting points are located **between the fingers and the elbow on the upper extremity, between the toes and the knee on the lower extremity**. The classification and application of these points is based on two theories: on the one hand they are applied according to the Qi flow in the channel from distal to proximal, on the other hand they are used according to the Five Phases (→ 8.2.5).

While the location of the five *shu*-transporting points is identical to the Five Phase points, their dynamics and range of application based on the Qi flow in the channels differs from or is even contrary to their actions as Five Phase points. The theoretical foundations of the Qi flow in the channels as applied in the instance of the *shu*-transporting point are based on a rather earlier circulatory concept (→ 1.1.1).

The therapeutic application of the Five Phase points will be explained in more detail in → 8.2.5, while the clinical application according to channel flow is described below.



Theoretical background of the Qi circulation in the channels

According to the more original centripetal model (→ 1.1.1), the Qi flows from the peripheral parts of the body to the elbows and knees, similar to a river coursing from its spring to its estuary and finally into the sea:

- The Qi flow begins at the anastomosis at the *jing*-well point. Here the water surfaces, it is dynamic and unstable (change of polarity from Yin to Yang)
- The water course then changes to a spring (*ying*) and a stream (*shu*) – both are at this point still quite dynamic features, the water flowing rapidly and superficially.
- The water then becomes increasingly deeper and slower, taking on the characteristics of a river (*jing*).
- Eventually it flows as a big river into the sea (*he*).

This image of a river system is often used to explain disorders caused by pathogenic factors (*xie qi*). Due to the superficial position of these points on the extremities, pathogens can here easily penetrate the body. By the same token, they can be removed again with relatively little effort. Barbara Kirschbaum (course material 1999) provides a useful visual image: she suggests imagining a ship carrying a cargo of pathogens that begins its journey at the tips of the extremities. The further a point is located peripherally in the body, the easier it is for the ship to get rid of its dangerous cargo (or to expel the pathogen according to the dynamics of the Qi flow). However, once the ship has reached the *he*-sea point, the ship and its cargo will disappear in the big, wide sea, having the potential to injure the internal *zangfu*-Organ. Thus it is the therapeutic goal to eliminate pathogens from the body as soon as possible.

Overview: *shu*-transporting points

***Shu*-transporting points of the Yin channels**

Phase/ channel	Wood point	Fire point	Earth point	Metal point	Water point
LU	LU-11	LU-10	LU-9 +	LU-8	LU-5 −
SP	SP-1	SP-2 +	SP-3	SP-5 −	SP-9
HE	HE-9 +	HE-8	HE-7 −	HE-4	HE-3
KID	KID-1 −	KID-2	KID-3	KID-7 +	KID-10
P	P-9 +	P-8	P-7 −	P-5	P-3
LIV	LIV-1	LIV-2 −	LIV-3	LIV-4	LIV-8 +
Channel Qi flow	*Jing*-well point	*Ying*-spring point	*Shu*-stream point	*Jing*-river point	*He*-sea point

***Shu*-transporting points of the Yang channels**

Phase/ channel	Metal point	Water point	Wood point	Fire point	Earth point
L.I.	L.I.-1	L.I.-2 −	L.I.-3	L.I.-5	L.I.-11 +
ST	ST-45 −	ST-44	ST-43	ST-41+	ST-36
S.I.	S.I.-1	S.I.-2	S.I.-3 +	S.I.-5	S.I.-8 −
BL	BL-67 +	BL-66	BL-65 −	BL-60	BL-40
T.B.	T.B.-1	T.B.-2	T.B.-3 +	T.B.-6	T.B.-10 −
G.B.	G.B.-44	G.B.-43+	G.B.-41	G.B.-38 −	G.B.-34
Channel Qi flow	*Jing*-well point	*Ying*-spring point	*Shu*-stream point	*Jing*-river point	*He*-sea point

+, tonification point; − , sedation point

Clinical application of the *shu*-transporting points

Jing-well points (*jing xue*)

***Shu*-transporting Points of the Yin channels**

Phase/ channel	Wood point	Fire point	Earth point	Metal point	Water point
LU	LU-11	LU-10	LU-9 +	LU-8	LU-5 −
SP	SP-1	SP-2 +	SP-3	SP-5 −	SP-9
HE	HE-9 +	HE-8	HE-7 −	HE-4	HE-3
KID	KID-1 −	KID-2	KID-3	KID-7 +	KID-10
P	P-9 +	P-8	P-7 −	P-5	P-3
LIV	LIV-1	LIV-2 −	LIV-3	LIV-4	LIV-8 +
Channel Qi flow	*Jing*-well point	*Ying*-spring point	*Shu*-stream point	*Jing*-river point	*He*-sea point

***Shu*-transporting points of the Yang channels**

Phase/ channel	Metal point	Water point	Wood point	Fire point	Earth point
L.I.	L.I.-1	L.I.-2 −	L.I.-3	L.I.-5	L.I.-11 +
ST	ST-45 −	ST-44	ST-43	ST-41 +	ST-36
S.I.	S.I.-1	S.I.-2	S.I.-3 +	S.I.-5	S.I.-8 −
BL	BL-67 +	BL-66	BL-65 −	BL-60	BL-40
T.B.	T.B.-1	T.B.-2	T.B.-3 +	T.B.-6	T.B.-10 −
G.B.	G.B.-44	G.B.-43+	G.B.-41	G.B.-38 −	G.B.-34
Channel Qi flow	*Jing*-well point	*Ying*-spring point	*Shu*-stream point	*Jing*-river point	*He*-sea point

+, tonification point; − , sedation point

According to the Five Phases (→ 8.2.5) the *jing*-well points of the **Yin channels** correspond to the **Wood points**, while those of the **Yang channels** correspond to the **Metal points**.

Location: as the **last or first point of each channel**, they are located on the **tips of the fingers or the toes** (exception: **KID-1** of the sole of the foot). The course of the channel is here at its **most superficial**. It is also here that a change of polarity is taking place in the energy: from Yin to Yang or vice versa. **Caution**: needling these points can be quite intense and painful, presenting a strong stimulus to the body.

Actions

- Clear Heat, restore consciousness, eliminate Heat and excess from the upper end of the channel: commonly pricked to bleed.
- Treat fullness and Cold below the Heart
- Treat disorders of the spirit (*shen*) for psychological disorders

Indications

- For acute conditions and emergencies: the *jing*-well points can quickly expel Exterior pathogenic factors (*xie qi*), especially Heat. They have a strong effect on the psyche, for example for coma, collapse and shock as well as for severe irritability and restlessness.
- The points on the Yin channels also have an effect on their pertaining *zang*-Organs and can eliminate internal Wind.

Ch08-F10028.qxd 2/23/08 4:40 PM Page 672

Examples

- **LU-11**: prick to bleed for acute sore throat
- **KID-1**: for spasms and unconsciousness
- **HE-9**: for collapse
- **SP-1**: for uterine bleeding

For psychological disorders:

- **KID-1**: for severe restlessness
- **P-9** and **HE-9**: for extreme restlessness and insomnia

























Ying-spring points (*ying xue*)

***Shu*-transporting points of the Yin channels**					
Phase/ channel	Wood point	Fire point	Earth point	Metal point	Water point
LU	LU-11	LU-10	LU-9 +	LU-8	LU-5 –
SP	SP-1	SP-2 +	SP-3	SP-5 –	SP-9
HE	HE-9 +	HE-8	HE-7 –	HE-4	HE-3
KID	KID-1 –	KID-2	KID-3	KID-7 +	KID-10
P	P-9 +	P-8	P-7 –	P-5	P-3
LIV	LIV-1	LIV-2 –	LIV-3	LIV-4	LIV-8 +
Channel Qi flow	*Jing*-well point	*Ying*-spring point	*Shu*-stream point	*Jing*-river point	*He*-sea point

***Shu*-transporting points of the Yang channels**					
Phase/ channel	Metal point	Water point	Wood point	Fire point	Earth point
L.I.	L.I.-1	L.I.-2 –	L.I.-3	L.I.-5	L.I.-11 +
ST	ST-45 –	ST-44	ST-43	ST-41 +	ST-36
S.I.	S.I.-1	S.I.-2	S.I.-3 +	S.I.-5	S.I.-8 –
BL	BL-67 +	BL-66	BL-65 –	BL-60	BL-40
T.B.	T.B.-1	T.B.-2	T.B.-3 +	T.B.-6	T.B.-10 –
G.B.	G.B.-44	G.B.-43 +	G.B.-41	G.B.-38 –	G.B.-34
Channel Qi flow	*Jing*-well point	*Ying*-spring point	*Shu*-stream point	*Jing*-river point	*He*-sea point

+, tonification point; –, sedation point

According to the Five Phases (→ 8.2.5) the *ying*-spring points of the Yin channels correspond to the Fire points, while those on the Yang channels correspond to the Water points. **Caution**: needling some of these points can be painful, for example **LU-10, P-8, HE-8**.

Location: as the second most distal point of each channel, they are located on the upper extremity between the phalanges and metacarpal bones and on the lower extremity between the phalanges with the exception of KID-2.

Actions

- They are very dynamic points that eliminate both external and internal pathogenic factors.
- They clear Heat from their pertaining *zangfu*-Organ and channel, especially in the upper half of the body.

Indications

- For example for febrile diseases: Exterior Heat syndromes are mainly treated using points on the Yang channels while Interior Heat or deficient Heat syndromes are treated with points on the Yin channels.

Examples

- **LU-10:** for acute inflammations of the throat
- **ST-44:** for acute frontal headaches or acute inflammations affecting the face
- **LIV-2:** for severe temporal headaches, for example due to blazing Liver Fire




















BL-66
BL-65
BL-64


T.B.-2
Proximal to the interdigital fold


Proximal to the interdigital fold
G.B.-43

Shu-stream points (*shu xue*)

***Shu*-transporting points of the Yin channels**

Phase/ channel	Wood point	Fire point	Earth point	Metal point	Water point
LU	LU-11	LU-10	LU-9 +	LU-8	LU-5 −
SP	SP-1	SP-2 +	SP-3	SP-5 −	SP-9
HE	HE-9 +	HE-8	HE-7 −	HE-4	HE-3
KID	KID-1 −	KID-2	KID-3	KID-7 +	KID-10
P	P-9 +	P-8	P-7 −	P-5	P-3
LIV	LIV-1	LIV-2−	LIV-3	LIV-4	LIV-8 +
Channel Qi flow	*Jing*-well point	*Ying*-spring point	*Shu*-stream point	*Jing*-river point	*He*-sea point

***Shu*-transporting points of the Yang channels**

Phase/ channel	Metal point	Water point	Wood point	Fire point	Earth point
L.I.	L.I.-1	L.I.-2 −	L.I.-3	L.I.-5	L.I.-11+
ST	ST-45 −	ST-44	ST-43	ST-41+	ST-36
S.I.	S.I.-1	S.I.-2	S.I.-3 +	S.I.-5	S.I.-8 −
BL	BL-67 +	BL-66	BL-65 −	BL-60	BL-40
T.B.	T.B.-1	T.B.-2	T.B.-3 +	T.B.-6	T.B.-10 −
G.B.	G.B.-44	G.B.-43+	G.B.-41	G.B.-38−	G.B.-34
Channel Qi flow	*Jing*-well point	*Ying*-spring point	*Shu*-stream point	*Jing*-river point	*He*-sea point

+, tonification point; −, sedation point

According to the Five Phases (→ 8.2.5) the *shu*-stream points of the **Yin channels** correspond to the **Earth points** and ***yuan*-Source points** (→ 8.1.1), while those on the **Yang channels** correspond to the **Wood points**.

Location: counting from the periphery, they are the **third point of each channel**, the only exception being the G.B. channel (4th point on the channel). They are located proximal to the metacarpophalangeal or metatarsophalangeal joints, except for **KID-3** (posterior to the medial malleolus), **LIV-3** and **SP-3** (both located at the distal ends of the metatarsal bones) as well as **LU-9, HE-7** and **P-7** (all located on the wrist joint space).

Actions

They are considered to be the entry points for pathogenic factors; needling these points can strengthen the Defensive Qi (*wei qi*) (→ 1.1.4) and eliminate pathogenic factors from the respective channel. At the *shu*-stream points, the Qi flow is already somewhat deeper: the bed of the river is widening and deepening.

Indications

For *bi*-syndromes of the joints, especially due to Damp or pathogenic Wind. They are generally used for heaviness of the body as well as for *shaoyang* syndrome with intermittent symptoms.

- Points on the Yang channels are predominantly used for Exterior syndromes: they have a specific action on their respective channel.
- Points on the Yin channels are more commonly used for Interior syndromes; they strengthen and harmonise their respective *zang*-Organs (this is in part due to these points also being the *yuan*-source points).


Abductor pollicis longus
Radial artery
LU-8
1 cun
LU-9
Joint space
Carpal bones




Tendon of the flexor carpi ulnaris
Joint space
Pisiform
HE-7


Highest prominence of the medial malleolus
Achilles tendon
KID-3




LIV-3
LIV-2
1,5–2 cun
Interdigital fold













Jing-river points (*jing xue*)

***Shu*-transporting points of the Yin channels**					
Phase/ channel	Wood point	Fire point	Earth point	Metal point	Water point
LU	LU-11	LU-10	LU-9 +	LU-8	LU-5 −
SP	SP-1	SP-2 +	SP-3	SP-5 −	SP-9
HE	HE-9 +	HE-8	HE-7 −	HE-4	HE-3
KID	KID-1 −	KID-2	KID-3	KID-7 +	KID-10
P	P-9 +	P-8	P-7−	P-5	P-3
LIV	LIV-1	LIV-2 −	LIV-3	LIV-4	LIV-8 +
Channel Qi flow	*Jing*-well point	*Ying*-spring point	*Shu*-stream point	*Jing*-river point	*He*-sea point

***Shu*-transporting points of the Yang channels**					
Phase/ channel	Metal point	Water point	Wood point	Fire point	Earth point
L.I.	L.I.-1	L.I.-2 −	L.I.-3	L.I.-5	L.I.-11 +
ST	ST-45 −	ST-44	ST-43	ST-41 +	ST-36
S.I.	S.I.-1	S.I.-2	S.I.-3 +	S.I.-5	S.I.-8 −
BL	BL-67 +	BL-66	BL-65 −	BL-60	BL-40
T.B.	T.B.-1	T.B.-2	T.B.-3 +	T.B.-6	T.B.-10 −
G.B.	G.B.-44	G.B.-43+	G.B.-41	G.B.-38 −	G.B.-34
Channel Qi flow	*Jing*-well point	*Ying*-spring point	*Shu*-stream point	*Jing*-river point	*He*-sea point

+, tonification point; − , sedation point

According to the Five Phases (→ 8.2.5), the *jing*-river points of the **Yin channels** correspond to the **Metal points**, while those on the **Yang channels** correspond to the **Fire points**.

Location: they are located **between** the ***shu*-stream points** and the ***he*-sea points**. On the upper extremity, they are located either at, or distal or proximal to the wrist, while on the lower extremity they are located either at, or distal or proximal to the ankle (see figure on p. 676).

Actions

They divert external pathogenic factors away from joints, bones and tendons towards the Exterior. At the *jing*-river points the Qi flow becomes increasingly wider, slower, deeper and larger – thus the actions of these points are also less dynamic compared to the first three, more peripheral, *shu*-transporting points. At the *jing*-river points external pathogens have already penetrated deeper into the body, especially into the joints, bones and tendons.

Indications

- Dyspnoea, disorders of the throat such as inflammations, cough, disorders manifesting in the voice.
- Alternating fever and chills (especially points on the Yin channels)
- Also for *bi*-syndromes such as painful joint and tendon disorders.


Abductor pollicis longus
Radial artery
LU-8
1 cun
LU-9
Joint space
Carpal bones


Highest prominence of the medial malleolus
SP-5


1.5 cun
HE-7
HE-4






Tendon of the extensor pollicis longus and tibialis anterior
LIV-4


L.I.-5
Extensor tendon


Level of the highest prominence of the lateral malleolus
ST-41
Talocrural joint (ankle joint)
Tendon of the extensor hallucis longus


S.I.-4
S.I.-5
Metacarpal V
Pisiform
Wrist joint space






G.B.-38
4 cun
1/4
Highest prominence

He-sea points (*he xue*)

***Shu*-transporting points of the Yin channels**

Phase/ channel	Wood point	Fire point	Earth point	Metal point	Water point
LU	LU-11	LU-10	LU-9 +	LU-8	LU-5 –
SP	SP-1	SP-2 +	SP-3	SP-5 –	SP-9
HE	HE-9 +	HE-8	HE-7–	HE-4	HE-3
KID	KID-1 –	KID-2	KID-3	KID-7 +	KID-10
P	P-9+	P-8	P-7–	P-5	P-3
LIV	LIV-1	LIV-2 –	LIV-3	LIV-4	LIV-8 +
Channel Qi flow	*Jing*-well point	*Ying*-spring point	*Shu*-stream point	*Jing*-river point	*He*-sea point

***Shu*-transporting points of the Yang channels**

Phase/ Channel	Metal point	Water point	Wood point	Fire point	Earth point
L.I.	L.I.-1	L.I.-2 –	L.I.-3	L.I.-5	L.I.-11 +
ST	ST-45 –	ST-44	ST-43	ST-41 +	ST-36
S.I.	S.I.-1	S.I.-2	S.I.-3 +	S.I.-5	S.I.-8 –
BL	BL-67 +	BL-66	BL-65 –	BL-60	BL-40
T.B.	T.B.-1	T.B.-2	T.B.-3 +	T.B.-6	T.B.-10 –
G.B.	G.B.-44	G.B.-43+	G.B.-41	G.B.-38–	G.B.-34
Channel Qi flow	*Jing*-well point	*Ying*-spring point	*Shu*-stream point	*Jing*-river point	*He*-sea point

+, tonification point; – , sedation point

According to the Five Phases (→ 8.2.5) the *he*-sea points of the **Yin channels** correspond to the **Water points**, while those on the **Yang channels** correspond to the **Earth points**.

Location: on the upper extremity these points are located near the **elbow**, on the lower extremity near the **knee**.

Actions

- They descend counterflow Qi and stop diarrhoea. At the *he*-sea points the Qi flow is very wide, deep and slow, 'terminating in the deep sea' where the 'toxic cargo' can 'disappear' into the body unless treated adequately. External pathogens (*xie qi*) which have not been eliminated from the channel beforehand can here penetrate the Interior of the body and injure the *zangfu*-Organs.
- Diseases of the *fu*-Organs (here especially points on the lower extremities are indicated).

Indications

- Disorders of the *fu*-Organs, especially gastro-intestinal disorders with symptoms such as vomiting and diarrhoea
- Some *he*-sea points are also indicated for skin diseases, for example **LI-11, BL-40**.


Biceps tendon
LU-5


Medial condyle of the tibia
SP-9
Junction of the shaft and medial condyle of the tibia
Gastrocnemius




Tendon of the semitendinosus (most prominent tendon)
KID-10


Biceps tendon
P-3
Cubital crease




90°
L.I.-11
Lateral epicondyle
Olecranon


ST-35
3 cun
ST-36


Olecranon
Medial epicondyle of the humerus
S.I.-8


Popliteal crease
BL-40


T.B.-10
approximately 1 cun
Olecranon


G.B.-34
Head of the fibula

8.1.7 The Eight *Hui*-Meeting Points

Synonym: Gathering Points (Maciocia)

The Qi of a particular tissue, Organ system or substance gathers at the *hui*-meeting points and can be influenced through these points.

Ch08-F10028.qxd 2/23/08 4:40 PM Page 678

Points and clinical application


BL-11
BL-17
Ren-17
Ren-12
LIV-13
LU-9
G.B.-34
G.B.-39

The Eight *hui*-Meeting Points		
Point	Tissue/organ system/substance	Indications
LIV-13 (*zhangmen*)	*zang*-Organs	Disorders of the *zang*-Organs (tonifies the Spleen and indirectly all *zang*-Organs)
Ren-12 (*zhongwan*)	*fu*-Organs	Disorders of the *fu*-Organs, for example of the gastro-intestinal tract
Ren-17 (*danzhong or shanzhong*)	Qi, has a strong effect on the *zong qi*	Respiratory diseases and disorders of the Qi flow such as hiccups; controls the *zong qi* and therefore functioning of the Lungs and Heart
BL-17 (*geshu*)	Blood (*xue*)	Disorders of the Blood such as anaemia, Blood stasis, haemorrhagia and gynaecological disorders
G.B.-34 (*yangling-quan*)	Sinews	Disorders of the joints, sinews and muscles
LU-9 (*taiyuan*)	Blood vessels	Stimulates the peripheral Blood circulation for disorders of the blood vessels such as vasculitis and arteriosclerosis
BL-11 (*dazhu*)	Bones	Disorders of the Bones such as shoulder and spine problems, joint and bone pain
G.B.-39 (*xuanzhong*)	Marrow	Disorders of the Bones, the Marrow and Brain (nerves)

8.1.8 Opening Points of the Eight Extraordinary Vessels

Synonyms: Confluent points (Deadman et al 1998), Master points (Pirog 1996)

The table below shows the opening points of the eight extraordinary vessels. For more detail on their origin and pathways → 1.7, Chapter 5.


Yin
Yang
P-6
LU-7
T.B.-5
S.I.-3
BL-62
G.B.-41
KID-6
SP-4


yin qiao mai
KID-6 LU-7
yang qiao mai
BL-62 S.I.-3
ren mai
LU-7 KID-6
du mai
S.I.-3 BL-62
Yin-Vessels
Central
Yang-Vessels
chong mai
SP-4 P-6
dai mai
G.B.-41 T.B.-5
yin wei mai
P-6 SP-4
yang wei mai
T.B.-5 G.B.-41
black Opening point
blue Coupled point
Central ↔ Peripheral (Yin–Yin, Yang–Yang)
Peripheral ↔ Peripheral (Yin–Yang)
Central ↔ Central (Yin–Yang)

Points

Pairs	Extraordinary Vessel	Opening point	Coupled point (opening point of the paired vessel)	Supported body regions
Pair 1	*chong mai*	**SP-4** (*gongsun*)	**P-6** (*neiguan*)	Heart, chest, Stomach
	yin wei mai	**P-6** (*neiguan*)	**SP-4** (*gongsun*)	
Pair 2	*du mai*	**S.I.-3** (*houxi*)	**BL-62** (*shenmai*)	Occiput, shoulder, back
	yang qiao mai	**BL-62** (*shenmai*)	**S.I.-3** (*houxi*)	
Pair 3	*dai mai*	**G.B.-41** (*zulinqi*)	**T.B.-5** (*waiguan*)	Temples, ears, lateral aspects of the body
	yang wei mai	**T.B.-5** (*waiguan*)	**G.B.-41** (*zulinqi*)	
Pair 4	*ren mai*	**LU-7** (*lieque*)	**KID-6** (*zhaohai*)	Face, throat, chest, Lungs, abdomen
	yin qiao mai	**KID-6** (*zhaohai*)	**LU-7** (*lieque*)	

Clinical application

Various approaches exist for needling the opening/coupled points of the extraordinary vessels. The following method **for 'opening' or regulating the extraordinary vessels** has been used with good therapeutic results in clinical practice:

- Needle the **opening point** of the relevant channel first, then needle the **contralateral coupled point** (opening point of the paired extraordinary vessel). This will mobilise and regulate the Qi of the extraordinary vessel, making it more dynamic.
- During a subsequent session, needle **either the *xi*-cleft point** of the previously treated extraordinary vessel (→ 8.1.3) or add **other channel points of the vessel** (see channel pathways, chapter 5) during the same or subsequent session. This will further support the dynamics of the Qi flow in the vessel.

In addition Maciocia (1989) and Kirschbaum (1995) suggest the following procedure for 'opening' the extraordinary vessels:

- **In women:** First needle the opening point on the *right* side with even method, then the coupled point on the *left* side with even method. Afterwards other points on the respective vessel may be added.
- **In men:** First needle the opening point on the *left* side with even method, then the coupled point on the *right* side with even method. Afterwards other points on the respective vessel may be added.
- **Needle retention:** the needles should be retained for 20–25 minutes and should be removed in the opposite order.

8.1.9 Lower *He*-Sea Points

The lower *he*-sea points are used as the main points for disorders of their pertaining *fu*-Organ.

Points and clinical application



- **ST-36** (*zusanli*): Lower *he*-sea point of the Stomach; indication: loss of appetite, epigastric pain and fullness, acid reflux, abdominal pain, constipation, diarrhoea
- **ST-37** (*shangjuxu*): Lower *he*-sea point of the Large Intestine; indication: appendicitis, diarrhoea
- **ST-39** (*xiajuxu*): Lower *he*-sea point of the Small Intestine; indication: diarrhoea, abdominal pain
- **G.B.-34** (*yanglingquan*): Lower *he*-sea point of the Gall Bladder; indication: cholecystitis, vomiting
- **BL-40** (*weizhong*): Lower *he*-sea point of the Bladder; indication: urinary incontinence, urinary retention
- **BL-39** (*weiyang*): Lower *he*-sea point of the Triple Burner; indication: urinary incontinence, urinary retention

8.1.10 Meeting Points (*Jiaohui* Points)

Synonym: Intersecting points (Practical Dictionary)
Meeting points (*jiaohui* points) represent intersections between channels and vessels. Needling them allows more than one channel to be influenced and widens the range of actions of a given point. By the same token, the number of needles may be reduced while maintaining a good therapeutic effect.

	Lung	Large Intestine	Stomach	Spleen	Heart	Small Intestine	Bladder	Kidney	Pericardium	Triple Burner	Gall Bladder	Liver	*Du mai*	*Ren mai*	*Yang wei mai*	*Yin wei mai*	*Yang qiao mai*	*Yin qiao mai*	*Chong mai*	*Dai mai*
LU 1	▒			■																
L.I. 14		░				▨	▨								▨					
L.I. 15		░															■			
L.I. 16		░															■			
L.I. 20		░	■																	
ST 1			░										▨	■			■			
ST 2			░														▨			
ST 3			░														■			
ST 4		■	░										▨	▨			■			
ST 5			░								▨									
ST 6			░								▨									
ST 7			░								■									
ST 8			░								■				■					
ST 9			░								■									
ST 12		■	░			■				■	■									
ST 30			░								▨								■	
SP 6				▒				■				■						▨		
SP 12				▒						▨		■				■				
SP 13				▒								■				■				
SP 15				▒												■				
SP 16				▒												■				
S.I. 10						░	■								■		■			
S.I. 12		■				░				■	■									
S.I. 18						░				■										
S.I. 19						░				■	■									
BL 1			■			■	░			▨	▨		■				■	■		
BL 11						■	░			▨	▨		▨							
BL 12							░						■							
BL 23							░						▨							
BL 31							░				■									
BL 32							░				■									
BL 33							░				■									
BL 34							░				■									
BL 41						■	░													
BL 59							░										▨			
BL 61							░										■			
BL 62							░										▨			
BL 63							░								■					
KID 2								▒										▨		
KID 6								▒										▨		
KID 8								▒										▨		
KID 9								▒								■				
KID 11								▒											■	
KID 12								▒											■	
KID 13								▒											■	
KID 14								▒											■	
KID 15								▒											■	
KID 16								▒											■	
KID 17								▒											■	
KID 18								▒											■	

	Lung	Large Intestine	Stomach	Spleen	Heart	Small Intestine	Bladder	Kidney	Pericardium	Triple Burner	Gall Bladder	Liver	*Du mai*	*Ren mai*	*Yang wei mai*	*Yin wei mai*	*Yang qiao mai*	*Yin qiao mai*	*Chong mai*	*Dai mai*
KID 19								▒											■	
KID 20								▒											■	
KID 21								▒											■	
P 1									▒	▨	■	■								
T.B. 13										░					▨					
T.B. 15										░	■				■					
T.B. 17										░	■									
T.B. 20						▨				░	■									
T.B. 22						■				░	■									
G.B. 1						■				■	░									
G.B. 3			■							■	░									
G.B. 4			■							■	░									
G.B. 5		■	■							■	░									
G.B. 6		■	■							■	░									
G.B. 7							■				░									
G.B. 8							■				░									
G.B. 9							■				░									
G.B. 10							■				░									
G.B. 11						▨	■			▨	░									
G.B. 12							■				░									
G.B. 13											░				■					
G.B. 14		▨	▨							▨	░				■					
G.B. 15							■				░				■					
G.B. 16											░				■					
G.B. 17											░				■					
G.B. 18											░				■					
G.B. 19											░				■					
G.B. 20										▨	░				■		■			
G.B. 21			▨							■	░				■					
G.B. 23							▨				░									
G.B. 24				■							░				▨					
G.B. 26											░									■
G.B. 27											░									■
G.B. 28											░									■
G.B. 29											░						■			▨
G.B. 30							■				░									
G.B. 35											░						▨			
LIV 13											■	▒								▨
LIV 14				■								▒				■				
Du 1								■			■		░	■						
Du 13							■						░							
Du 14		■	■			■	■			■	■		░							
Du 15													░		■					
Du 16													░		■		▨			
Du 17							■						░							
Du 20							■			■	■	■	░							
Du 24			■				■						░							
Du 26		■	■										░							
Du 28			▨										░	■						
Ren 1													■	▒					■	

	Lung	Large Intestine	Stomach	Spleen	Heart	Small Intestine	Bladder	Kidney	Pericardium	Triple Burner	Gall Bladder	Liver	*Du mai*	*Ren mai*	*Yang wei mai*	*Yin wei mai*	*Yang qiao mai*	*Yin qiao mai*	*Chong mai*	*Dai mai*
Ren 2												■		░						
Ren 3				■				■				■		░						
Ren 4				■				■				■		░						
Ren 7								▨						░					■	
Ren 10			▨	■										░						
Ren 12			■			■				▨				░						
Ren 13			■			■								░						
Ren 17				■		■		■		■				░						
Ren 22														░		■				
Ren 23														░		■				
Ren 24		■	■										■	░						

▨ only mentioned by some authors

8.1.11 The Gao Wu Command Points

Synonym: none known

These points have the ability to affect certain regions of the body. By combining these points with local and other specific points they can increase the therapeutic effect in a particular area of the body.



Points and clinical application

- **ST-36** (*zusanli*): for all disorders of the abdomen
- **L.I.-4** (*hegu*): for disorders of the face and mouth
- **LU-7** (*lieque*): for disorders of the occiput
- **BL-40** (*weizhong*): for disorders of the back and lumbar region
- **P-6** (*neiguan*): for disorders of the thorax
- **Du-26** (*renzhong*): for restoring consciousness (The last two points were added later, → Deadman et al 1998)

8.1.12 The Window of Heaven Points

In Chinese classical literature there are only a few references to these points. In modern times, both Ross (1995) and Deadman et al (1998) mention this group of points.

Points

LU-3 (*tianfu*)	**L.I.-18** (*futu*)	**P-1** (*tianchi*)
T.B.-16 (*tianyou*)	**S.I.-16** (*tianchuang*)	**S.I.-17** (*tianrong*)
ST-9 (*renying*)	**BL-10** (*tianzhu*)	**Ren-22** (*tiantu*)
Du-16 (*fengfu*)		

Location: Eight of the Window of Heaven points are located in the neck region (exceptions are **LU-3** on the upper arm and **P-1** on the thorax). This might provide a clue about the action of these points in regulating the Qi flow between the head and the body.

Comment: According to Deadman, the Ming dynasty physician Ma Shi remarked that **S.I.-17** should be replaced by **G.B.-9** (*tianchong*). If that was the case all six Yang channels running to the head would be represented by a Window of Heaven point.



Clinical application

- For disorders of the Qi flow:
  - **LU-3, L.I.-18, Ren-22** for counterflow Qi causing cough, wheezing, etc.
  - **P-1** for counterflow Lung Qi with copious Phlegm
  - **ST-9** for counterflow Lung and Stomach Qi
  - **BL-10** treats dizziness, headaches and stiffness of the occiput, etc.
  - **Du-16** for internal Liver Wind

- For goitre, swellings, pain and Qi stagnation in the occiput and neck: especially indicated if these occur locally
- For disorders with an acute onset, for example
  - **L.I.-18** for acute aphonia
  - **ST-9** for acute diarrhoea
  - **S.I.-16** for acute aphonia, for example following a stroke
  - **BL-10** for epilepsy
  - **T.B.-16** for acute hearing loss
  - **Ren-22** for acute dyspnoea
  - **Du-16** for acute aphasia following a stroke
- For psychological disorders:
  - **LU-3** for somnolence, grief, disorientation, forgetfulness, insomnia
  - **S.I.-16** for manic agitation and bipolar disorder
  - **BL-10** for mania, hallucinations, epilepsy, childhood convulsions
  - **T.B.-16** for vivid dreaming
  - **Du-16** for mania, grief, anxiety with anxiety-induced palpitations
- For disorders of the sensory organs:
  - **LU-3** for nose bleeding, blurry vision, myopia
  - **ST-9** for blurry vision
  - **S.I.-16** for deafness, tinnitus, ear pain
  - **S.I.-17** for tinnitus and deafness
  - **BL-10** for eye pain, blurry vision, excessive tearing, speech disorders, blocked nasal passages, loss of sense of smell
  - **T.B.-16** for hearing disorders, visual disorders, eye pain, excessive tearing, loss of sense of smell, blocked nasal passages
  - **Du-16** for speech disorders (for example following a stroke), blurry vision, nosebleeds
  - **Ren-22** for speech disorders

8.1.13 Points of the Four Seas

These points have a particular, supportive effect on their respective 'Sea'.



Sea of Qi	**ST-9** (*renying*), **Ren-17** (*danzhong or shanzhong*), **Du-15** (*yamen*), **Du-14** (*dazhui*)
*Ling Shu**: 'When the Sea of Qi is in excess there is fullness in the chest, urgent breathing and a red complexion. When the Sea of Qi is insufficient, there is scanty energy, insufficient for speech.'	
Sea of Blood	**BL-11** (*dazhu*), **ST-37** (*shangjuxu*), **ST-39** (*xiajuxu*)
*Ling Shu**: 'The Penetrating vessel is the sea of the twelve channels. In the upper it is conveyed to BL-11 (*dazhu*), and in the lower it emerges at both the ST-37 (*shangjuxu*) and ST-39 (*xiajuxu*) …When the Sea of Blood is in excess, then one has a sensation of the body being big; one feels disquiet, but does not know what the illness is; when the Sea of Blood is insufficient, one has the sensation of one's body being small; one feels reduced but does not know what the illness is.'	
Sea of Water and Grain	**ST-30** (*qichong*) as upper point, **ST-36** (*zusanli*) as lower point
*Ling Shu**: 'When the Sea of Water and Grain is in excess, there is abdominal fullness, and when it is deficient, there is hunger with inability to eat.'.	
Sea of Marrow	**Du-20** (*baihui*), **Du-16** (*fengfu*)
*Ling Shu**: 'When the Sea of Marrow is in excess, there is lightness of the body and much strength, and a person's feeling of 'self' exceeds the normal level; when the Sea of Marrow is insufficient there is a whirling sensation of the brain, dizziness, tinnitus, pain of the lower legs, impairment of vision, indolence and desire to sleep.'	

---

* Quotes from the *Ling Shu* according to Deadman et al. (1998).

8.1.14 The 12 Heavenly Star Points of Ma Dan Yang

Ma Dan Yang, a famous physician of the Jin dynasty, considered these initial 11 points as the most important acupuncture points. It was the physician Xu Feng who later added **LIV-3** as the 12th point.



LU-7 (*lieque*)	**L.I.-4** (*hegu*)	**L.I.-11** (*quchi*)
ST-36 (*zusanli*)	**ST-44** (*neiting*)	**HE-5** (*tongli*)
BL-40 (*weizhong*)	**BL-57** (*chengshan*)	**BL-60** (*kunlun*)
G.B.-30 (*huantiao*)	**G.B.-34** (*yanglingquan*)	**LIV-3** (*taichong*)

8.1.15 The 13 Ghost Points of Sun Si Miao

Sun Si Miao, a famous physician of the Tang Dynasty, applied these 13 points (also called demon points) for treating disorders that today would be considered severe, manic, psychological disorders and/or epilepsy. Each *Sun Si Miao* Ghost point has an alternative Chinese name containing the component 'demon' or 'ghost' (see list according to Deadman et al. 2000). According to Deadman et al., some authors assumed that *guixin* is **LU-9** (*taiyuan*) rather than **P-7** (*daling*), while *guilu* is believed to be **P-5** (*jianshi*) or **P-8** (*laogong*) rather than **BL-62** (*shenmai*). There also exist different versions of this list of points; for example the physician Gao Wu omitted **BL-62, Du-23, Ren-1*** (in the original text of *Sun Si Miao: yumentou/yinxiafeng*) and **L.I.-11**, adding **Du-24, ST-17, LIV-2 and G.B.-34** instead.

	Name	Alternative name	Translation
Du-26	*renzhong*	*guigong*	Ghost Palace
Du-16	*fengfu*	*guizhen*	Ghost Pillow
Du-23	*shangxing*	*guitang*	Ghost Hall
Ren-24	*chengjiang*	*guishi*	Ghost Market
LU-11	*shaoshang*	*guixin*	Ghost Faith
L.I.-11	*quchi*	*guitui*	Ghost Leg
ST-6	*jiache*	*guichuang*	Ghost's Bed
SP-1	*yinbai*	*guilei*	Ghost Fortress
P-7	*daling*	*guixin*	Ghost Heart
P-8	*laogong*	*guicu*	Ghost Cave
BL-62	*shenmai*	*guilu*	Ghost Path
Ex-HN-11	*haiquan*	*guifeng*	Ghost Seal
Ren-1*	*huiyin*	*guicang*	Ghost Store



---

* *Yumentou* (in women) and *yinxiafeng* (in men): these two extra points approximately correspond to Ren-1 (*huiyin*/*guicang*) (Ghost Store).

8.1.16 Entry/Exit Points

While in modern Chinese literature entry/exit points are not mentioned as a separate point category, they are listed as such in some Western literature (for example Jarrett 2003, Hicks et al. 2004, Pirog 1996). However, Hicks et al. (→ 2004, p. 250) postulate that original Chinese sources exist for these points. The concept of entry/exit points is based on a continuous flow of Qi from one channel to the next, the sequence corresponding to the Organ clock (→ 1.1.4). Shunts are suggested in order to facilitate the flow of Qi from the end of one channel to the beginning of the next. At an entry point the Qi therefore flows from the preceding channel into the following one, while at the exit points it leaves the current channel in order to enter the next one. However, it should be noted that the entry/exit points do not always correspond to the first or last point on a channel. In the following table these points are marked by grey shading.

Channel (sequence according to Organ clock)	Time of maximum Qi flow		Entry/exit points in sequential order		
LU (LU-1–LU-11)	3–5am		LU-1 (*zhongfu*)	➡	LU-7 (*lieque*)
					⬇
L.I. (L.I.-1–L.I.-20)	5–7am		L.I.-20 (*yingxiang*)	⬅	L.I.-4 (*hegxu*)
			⬇		
ST (ST-1–ST-45)	7–9am		ST-1 (*chengqi*)	➡	ST-42 (*chongyang*)
					⬇
SP (SP-1–SP-21)	9–11am		SP-21 (*dabao*)	⬅	SP-1 (*yinbai*)
			⬇		
HE (HE-1–HE-9)	11am–1pm		HE-1 (*jiquan*)	➡	HE-9 (*shaochong*)
					⬇
S.I. (S.I.-1–S.I.-19)	1–3pm		S.I.-19 (*tinggong*)	⬅	S.I.-1 (*shaoze*)
			⬇		
BL (BL-1–BL-67)	3–5pm		BL-1 (*jingming*)	➡	BL-67 (*zhiyin*)
					⬇
KID (KID-1–KID-27)	5–7pm		KID-22 (*bulang*)	⬅	KID-1 (*yongquan*)
			⬇		
P (P-1–P-9)	7–9pm		P-1 (*tianchi*)*	➡	P-8 (*laogong*)*
					⬇
T.B. (T.B.-1–T.B.-23)	9–11pm		T.B.-22 (*erheliao*)	⬅	T.B.-1 (*guanchong*)
			⬇		
G.B. (G.B.-1–G.B.-44)	11pm–1am		G.B.-1 (*tongziliao*)	➡	G.B.-41 (*zulinqi*)
					⬇
LIV (LIV-1–LIV-14)	1–3am		LIV-14 (*qimen*)	⬅	LIV-1 (*dadun*)

---

* In women P-2 is often substituted for P-1 due to its anatomical location close to the breast.


BL-1
ST-1
G.B.-1
T.B.-22
S.I.-19
L.I.-20
LU-1
HE-1
P-1
KID-22
SP-21
LIV-14
LU-7
P-8
HE-9
L.I.-4
S.I.-1
T.B.-1
KID-1
ST-42
LIV-1
SP-1
G.B.-41
BL-67


G.B.-41
LIV-1
1
LIV-14
LU-1
3
LU-7
L.I.-4
5
L.I.-20
ST-1
7
ST-42
SP-1
9
SP-21
HE-1
11
HE-9
S.I.-1
13
S.I.-19
BL-1
15
BL-67
KID-1
17
KID-22
P-1
19
P-8
T.B.-1
21
T.B.-22
G.B.-1
23
Gall Bladder
Liver
Lung
Large Intestine
Stomach
Spleen
Heart
Small Intestine
Bladder
Kidney
Peri-cardium
Triple Burner

Entry/exit block and therapy

Pulse diagnosis can reveal the partial or complete block between entry and exit points. An entry/exit block will inhibit the Qi flow from one channel to the next. In order to restore the blocked flow, the exit point of the blocked channel and the entry point of the following channel are needled at the same time. According to Hicks et al. (2004), further exit and entry points preceding or following the affected channel can be added in order to regulate the Qi flow over a greater distance. Needling should always be **bilateral**, even if the disorder occurs only on one side of the body. If it is not only the shunt between two channels, but the circulation in a channel as a whole that is affected, the flow in the whole channel can be strengthened and stimulated by simultaneous needling of both its entry point and its exit point.

Pirog (1996) compares the entry/exit points to input and output valves regulating the flow in a series of pipes (the channels) by 'opening' or 'closing' them.

- Tonifying needling techniques at the entry point (opening the input valve) will increase the flow into the channel. For example: tonifying **LU-1** opens the input valve. This will increase Qi flow in the LU channel for deficiency in this channel.
- Tonifying needling techniques at the exit point (opening the output valve) will decrease the flow in the channel. For example: Tonifying **LIV-14** opens the output valve: excess in the LIV channel will be drained.
- Reducing needling techniques at the entry point (closing the input valve) will reduce the flow into the channel. For example: Reducing **LU-1** closes the input valve and reduces the flow from the LIV channel into the LU channel, for example if there is pre-existing excess in the LU channel.
- Reducing needling techniques at the exit point (closing the output valve) will strengthen the flow in the channel. For example: Reducing **LIV-14** closes the output valve and prevents a further loss of Qi if there is a pre-existing deficiency in the LIV channel.

8.2 Strategies for Point Selection

8.2.1 Local, Adjacent and Distal Points

Local points

Local points are located in the immediate vicinity of the affected region. Each point that is tender with pressure (*ashi* point) can be considered to be a local point.

Adjacent points

Adjacent points are located near the affected or painful region.

Distal points

Distal points, despite being located at a distance from the affected area, still have a therapeutic effect, either directly or by being connected to the affected area by a channel (→ 1, also → 8.2.2, selection of distal points). The most effective and dynamic distal points are located distal to the knee (for the leg) or the elbow (for the arm). Generally the distal points of the foot channels tend to be more dynamic and effective than those on the arm channels.

Needling technique: In acute conditions or with severe pain the distal points should be needled with a reducing technique in order to activate the Qi flow more strongly in the blocked channels.

Stimulation of distal points: For a limited range of motion accompanied by pain the relevant distal point is strongly stimulated with a reducing technique while the patient moves the affected joint.

Enhancing the therapeutic effect: The therapeutic effect can be enhanced by combining distal points on the hand channels with those on the foot channels or by combining distal points with relevant local and adjacent points (→ 8.3.1).

8.2.2 Point Selection According to Affected Channel

Here the method of selecting points is based on the channel system (→ 1):

- Selecting points on the channel which **traverses the affected area**
- Selecting points on the channel that is **Interiorly–Exteriorly pertaining** (→ 1.2) to the affected channel
- Selecting points from the channel which is connected to the affected channel by **hand–foot pairing** (for example, *taiyang* axis, etc. → 1.2.3)

Differential selection of distal points

The following possibilities for selecting distal points are, among others, based on course material about the 'one point therapy' by R. Thambirajah (1990, 1991), R. Tan (2003) and my own clinical experience.

Selection of distal points according to corresponding areas

The distal points can be selected according to corresponding areas. The affected area is carefully examined, then the corresponding area is needled contralaterally (→ Fig.).



Selection of distal points according to Interiorly–Exteriorly connected channels

Here points are selected on the Interiorly–Exteriorly connected channel (Yin/Yang). The affected area is carefully located, then the corresponding point (mirror point) is needled with reducing technique on the contralateral side on the Interiorly–Exteriorly pertaining channel. Another specific example for this method of point selection is the *yuan–luo* combination (→ 8.3.3).

Example: For a disorder affecting the ST channel (foot *yangming*) select a point on the Interiorly–Exteriorly pertaining SP channel (foot *taiyin*). For example, for knee pain at **ST-35**, needle **SP-9** contralaterally (→ Fig.).



Selection of distal points according to the six great channels (*liu jing*, hand–foot pairing, → 1.2.3)

The point selection with this method is based on the six great channels (hand–foot pairing: *taiyin, taiyang*, etc., → 1.2.3). Disorders affecting the area of the hand channel are therefore treated with points on the corresponding foot channel and vice versa.

Example: Disorders in the area of the hand *taiyin* channel (LU channel) can be balanced by contralateral needling of points on the foot *taiyin* channel (SP channel). For example, shoulder pain with limited range of motion and maximum pain near **LU-1** (*zhongfu*) can be improved by contralateral needling of **SP-9** (*yinlingquan*) with reducing technique.



b

Selection of distal points according to the Organ clock (→ 1.4)

Distal points are selected on the channel that lies chronologically opposite to the affected channel on the Organ clock (→ 1.4). With this method, hand channels will treat disorders affecting the foot channels and vice versa.

Example: For a disorder affecting the G.B. channel (foot *shaoyang*), needle a point on the HE channel (hand *shaoyin*) located opposite the G.B. channel on the Organ clock. Needling can be contralateral or ipsilateral.



c

8.2.3 Point Selection Based on Symptoms

Points can also be selected based on traditional or empirical therapeutic experiences. While this method cannot replace a root treatment based on a differential diagnosis, it can be very helpful in situations where quick action is required.

Examples:

- **Du-14** or **L.I.-11** for fever
- **ST-36, Ren-12** for acute gastrointestinal disorders

8.2.4 Point Selection Based on the Qi Flow of the Organs

Descend counterflow Qi:

- Stomach: **Ren-10, Ren-13, ST-34, ST-44, ST-45, L.I.-4**
- Lung: **LU-1, LU-5, LU-7**
- Heart: **HE-5, HE-8, Ren-15**
- Kidney: **KID-1, KID-7, Ren-4**
- Liver: **LIV-2, LIV-3, LIV-1, LIV-14**

Raise Qi:

Spleen: **Ren-6, Ren-12, Du-20, BL-20**

8.2.5 Point Selection According to the Five Phases (Elements)

While the Five Phase points are identical to the *shu*-transporting points in location, their function and application differ from the latter (for more detail ➞ 8.1.6). There exist various very specific methods regarding diagnosis, point selection and therapy based on the Five Phases, which are practised by several different schools of thought. Within the framework of this Atlas, only a simplified overview of the possible clinical applications is listed below.

***Shu*-transporting points of the Yin channels**					
Phase/ channel	Wood point	Fire point	Earth point	Metal point	Water point
LU	LU-11	LU-10	LU-9 +	LU-8	LU-5 –
SP	SP-1	SP-2 +	SP-3	SP-5 –	SP-9
HE	HE-9 +	HE-8	HE-7 –	HE-4	HE-3
KID	KID-1 –	KID-2	KID-3	KID-7 +	KID-10
P	P-9 +	P-8	P-7 –	P-5	P-3
LIV	LIV-1	LIV-2 –	LIV-3	LIV-4	LIV-8 +
Channel Qi flow	*Jing*-well point	*Ying*-spring point	*Shu*-stream point	*Jing*-river point	*He*-sea point

***Shu*-transporting points of the Yang channels**					
Phase/ channel	Metal point	Water point	Wood point	Fire point	Earth point
L.I.	L.I.-1	L.I.-2 –	L.I.-3	L.I.-5	L.I.-11 +
ST	ST-45 –	ST-44	ST-43	ST-41 +	ST-36
S.I.	S.I.-1	S.I.-2	S.I.-3 +	S.I.-5	S.I.-8 –
BL	BL-67 +	BL-66	BL-65 –	BL-60	BL-40
T.B.	T.B.-1	T.B.-2	T.B.-3 +	T.B.-6	T.B.-10 –
G.B.	G.B.-44	G.B.-43 +	G.B.-41	G.B.-38 –	G.B.-34
Channel Qi flow	*Jing*-well point	*Ying*-spring point	*Shu*-stream point	*Jing*-river point	*He*-sea point

+, tonification point; – , sedation point

Cycles

The Five Phases influence each other both physiologically (*sheng* and *ke* cycle) as well as pathologically (*cheng*, *wu* and to some extent also *sheng* cycle). If the balance between the Five Phases is disturbed, pathological syndromes will appear.

- *Sheng* cycle (generating cycle, mother–son cycle): a phase generates and nourishes the following phase. Each phase nourishes (as mother) and is nourished (as son) at the same time. Fire nourishes Earth, Earth nourishes Metal, Metal nourishes Water, Water nourishes Wood, and Wood nourishes Fire. In a pathological condition either the mother is too weak to nourish the son sufficiently or the son is too strong, draining his mother and weakening her.
- *Ke* cycle (controlling cycle): one phase controls another and is itself controlled by yet another phase.
- *Cheng* cycle (overacting cycle): The controlled phase is pathologically suppressed or weakened.
- *Wu* cycle (insulting cycle): A phase is pathologically stronger than its controlling phase.



Simple point selection according to the *sheng* cycle


Yin
Yang
LU-5 –
LU-9 +
P-7 –
P-9 +
HE-7 –
HE-9 +
L.I.-11 +
L.I.-2 –
SJ 10 –
SJ 3 +
S.I.-8 –
S.I.-3 +
LIV-8 +
LIV-2 –
KID-1 –
KID-7 +
SP-5 –
SP-2 +
G.B.-38 –
G.B.-43 +
ST-41 +
ST-45 –
BL-65 –
BL-67 +

Treatment principle: For deficiency tonify the mother, for excess drain (sedate) the son. Mother–son points are identical to the tonification and sedation points of a channel. The correct needling technique is important in order to obtain the desired result:

- tonifying method for tonification points
- reducing method for sedation points

Example for the clinical application of the *sheng* cycle

For deficiency: In cases of deficiency of a particular channel/Organ, tonify that point on the affected channel that corresponds to the phase of the mother.

Example: Earth is the mother of Metal. If the Lung (Metal) is deficient, needle the Earth point (**LU-9**) on the Lung channel with tonifying technique.


Fire
HE
S.I.
P
T.B.
Earth
SP
ST
Metal
LU
L.I.
Water
KID
BL
Wood
LIV
G.B.
LU-9
Earth point on
the LU channel

For excess: If there is excess in a particular channel/Organ, select that point on the channel which corresponds to the phase of the son and needle it with reducing technique.

Example: Water is the son of Metal. If the Lung (Metal) is in excess, needle the Water point (LU-5) on the Lung channel with reducing technique.


Fire
HE
S.I.
P
T.B.
Earth
SP
ST
Metal
LU
L.I.
Water
KID
BL
Wood
LIV
G.B.
LU-5
Water point on
the LU channel

***Addendum*:** The terms tonification/sedation points are somewhat controversial, since the properties of a point can often be overshadowed by its other features. For example, according to the Five Phase theory, **P-9** and **HE-9** are considered tonification points, since they correspond to the phase of the mother. However, in clinical practice they are much more frequently used as *jing*-well points for acute situations – thus they are considered from the point of view of the Qi flow in the channels, especially in order to drain Heat.

Application of the Five Phase points for the elimination of external pathogenic factors

A connection exists between the Five Phases and pathogenic factors (Maciocia 1994; according to Ross 1998, however, these points should only be used for internal disorders):

- Wood corresponds to Wind
- Fire corresponds to Heat
- Earth corresponds to Dampness
- Metal corresponds to Dryness. According to Maciocia this correlation presents an exception: the Metal point should not be needled to treat Dryness; a moistening treatment is here the preferred choice.
- Water corresponds to Cold.

In accordance with these interrelations, Five Phase points can be applied to eliminate pathogenic factors.

Example: Acute sore throat with fever, redness and swelling of the throat due to Wind-Heat

Affected phases: Wood (Wind), Fire (Heat)

Affected Organ/channel: Lungs

Therapy: Needling of the Wood point on the LU channel (**LU-11**) and the Fire point on the LU channel (**LU-10**).



The application of the ***ke* cycle (controlling cycle)** allows a more differentiated approach in the therapy and elimination of pathogenic factors:

- On the Yin channel, needle the point corresponding to the pathogenic factor with reducing technique (for example, for Heat needle the Fire point)
- In addition, needle the point which corresponds to the controlling phase (according to the *ke* cycle/controlling cycle → 8.2.5) of the pathogenic factor on the paired Yang channel with tonifying technique.

Ben points

***Shu*-transporting points of the Yin channels**

Phase/ channel	Wood point	Fire point	Earth point	Metal point	Water point
LU	LU-11	LU-10	LU-9 +	LU-8	LU-5 –
SP	SP-1	SP-2 +	SP-3	SP-5 –	SP-9
HE	HE-9 +	HE-8	HE-7 –	HE-4	HE-3
KID	KID-1 –	KID-2	KID-3	KID-7 +	KID-10
P	P-9+	P-8	P-7 –	P-5	P-3
LIV	LIV-1	LIV-2–	LIV-3	LIV-4	LIV-8 +
Channel Qi flow	*Jing*-well point	*Ying*-spring point	*Shu*-stream point	*Jing*-river point	*He*-sea point

***Shu*-transporting points of the Yang channels**

Phase/ channel	Metal point	Water point	Wood point	Fire point	Earth point
L.I.	L.I.-1	L.I.-2 –	L.I.-3	L.I.-5	L.I.-11 +
ST	ST-45 –	ST-44	ST-43	ST-41 +	ST-36
S.I.	S.I.-1	S.I.-2	S.I.-3 +	S.I.-5	S.I.-8 –
BL	BL-67 +	BL-66	BL-65 –	BL-60	BL-40
T.B.	T.B.-1	T.B.-2	T.B.-3 +	T.B.-6	T.B.-10 –
G.B.	G.B.-44	G.B.-43+	G.B.-41	G.B.-38–	G.B.-34
Channel Qi flow	*Jing*-well point	*Ying*-spring point	*Shu*-stream point	*Jing*-river point	*He*-sea point

+, tonification point; – , sedation point

Ben points (root points, element points) represent the same phase as its pertaining channel. **Example:** The Spleen corresponds to Earth; thus the Earth point on the Spleen channel is its *ben* point.



Clinical application

- **For deficiency conditions:** needling the *ben* point with tonifying technique will tonify its corresponding Organ or channel
- **For excess conditions:** needling the *ben* point with reducing technique will drain the excess from its corresponding Organ or channel
- **Spiritual aspect:** the *ben* points on the Yin channels also affect the spiritual aspect of their corresponding phases. Thus the LU *ben* point **LU-8** allows the *po* (corporeal soul) to unfold its potential. Similarly the HE *ben* point **HE-8** will empower the *shen* (spirit), the SP *ben* point **SP-3** the *yi* (thinking), the LIV *ben* point **LIV-1** the *hun* (ethereal soul) and the KID *ben* point **KID-10** the *zhi* (will).

8.3 Point Combinations

8.3.1 Combining Local and Distal Points

Point selection and combination can be carried out according to affected areas and channels (→ 8.2.1, → 8.2.2).

For disorders affecting the channel: For example, for *bi*-syndromes affecting the sinews and joints, distal points can be stimulated first. Then local and adjacent points can be selected based on tenderness. These are needled and/or subsequently cupped.

For disorders of the *zangfu*-Organs: Generally, only distal points are applied in acute conditions. Once the condition (for example, acute pain) has improved, local points can be selected. In chronic conditions the combination of local and distal points – and especially Back-*shu* and Front-*mu* points as adjacent points (→ 8.3.2) – is commonly used. Another possibility is the combination of the opening point of an extraordinary vessel (→ 8.1.8) with local points in the affected area.



8.3.2 Combining Points on the Front and Back of the Body

Here, points on the anterior and posterior aspect of the body are combined:

- **Anterior points**: mainly located on the thorax and abdomen
- **Posterior points**: mainly located on the back and lumbar region

Back-*shu*/Front-*mu* method

The combination of the Back-*shu* point (→ 8.1.4) and the Front-*mu* point (→ 8.1.5) of the affected Organ is the most important way of combining points on the front and the back of the body. The Back-*shu*/Front-*mu* method enhances and extends the therapeutic effect, compared to using either of those points only. It has a strong Yin/Yang balancing effect and it is particularly beneficial for chronic disorders of the *zangfu*-Organs.


LU-1 Lung BL-13
Ren-17 Pericardium BL-14
Ren-14 Heart BL-15
LIV-14 Liver BL-18
G.B.-24 Gall Bladder BL-19
LIV-13 Spleen BL-20
Ren-12 Stomach BL-21
G.B.-25 Kidney BL-23
Ren-5 Triple Burner BL-22
ST-25 Large Intestine BL-25
Ren-4 Small Intestine BL-27
Ren-3 Bladder BL-28

Clinical application of the Back-*shu*/Front-*mu* method

- Needling of the Back-*shu* and Front-*mu* points during one session
- For repeated treatments within a short period of time, alternate needling of the Back-*shu* and Front-*mu* points (for example, during the first treatment select the relevant Back-*shu* point, in the next treatment select the corresponding Front-*mu* point, etc.)
- The Back-*shu*/Front-*mu* combination can also be applied to balance an incorrect treatment. For example, if the needles have been retained too long in the Back-*shu* points and the patient is tired, Front-mu points can be needled to restore balance.

Balancing the *du mai* and the *ren mai*

The points on the *ren mai* are located on the anterior aspect of the body, while those of the *du mai* are predominantly located on the posterior aspect. Combining points on the *ren mai* and *du mai* has a balancing affect on the Yin and Yang and can regulate the ascending and descending flow of Qi. This combination therefore not only balances the front and the back of the body, but also the Yin and the Yang. Furthermore, it has a strong effect on the psyche and, depending on the needling technique and point selection, will have a calming or stimulating effect (figure modified according to Ross 1998).



8.3.3 Yin–Yang Combination

Synonym: Interior/Exterior combination
The Yin–Yang combination balances the flow of Yin and Yang in the channels. It is based on the concepts of channel energetics (→ channel circuits, Fig. 1.12).

> Needling too many points on the Yang channels can make the patient nervous and restless. In this case, needling points on the Yin channels can restore balance and have a calming effect.
> Needling too many points on the Yin channels can lead to tiredness. In this case, needling points on the Yang channels has a balancing, stimulating effect.

Balancing Yin and Yang in paired channels

- Points on the Interiorly–Exteriorly paired channels are combined in order to balance Yin and Yang. For example the LU and L.I. channels are the Interiorly–Exteriorly paired channels of the hand, while the ST and SP channels are the Interiorly–Exteriorly paired channels of the foot of the first circuit.
- This method increases the therapeutic effect compared to using only Yin or only Yang points.

Yuan/luo combination

Most important Yin–Yang combination (Synonym: host–guest combination): The *yuan*-source point (host) of the primarily affected channel/Organ is combined with the *luo*-connecting point of the Interiorly–Exteriorly paired channel.

Important *yuan/luo* combinations

- **L.I.-4** (*hegu*) and **LU-7** (*lieque*) support the descending function of the Lung Qi, expel pathogenic factors, tonify the Defensive Qi (*wei qi*) and calm the *shen*
- **SP-3** (*taibai*) and **ST-40** (*fenglong*) tonify the Spleen and transform Phlegm
- **LIV-3** (*taichong*) and **G.B.-37** (*guangming*) benefit the eyes for Liver syndromes
- **T.B.-4** (*yangchi*) and **P-6** (*neiguan*) regulate the Triple Burner, move Liver Qi, calm the *shen*, relax the muscles in the occiput and shoulders.



Further methods of combining points of Interiorly–Exteriorly paired channels and modified *yuan/luo* combinations

a Combining the *luo*-connecting points of Interiorly–Exteriorly paired channels tends to enhance the therapeutic effect; for example combine **ST-40** and **SP-4** for abdominal pain

b For chronic disorders, combine the *yuan*-source point and the *luo*-connecting point of the same Yin channel in order to increase the therapeutic effect; for example needle **LU-9** and **LU-7** for chronic cough.

c For disorders affecting a Yin channel, only needle the *yuan*-source point of the Interiorly–Exteriorly paired Yang channel. For example for an acute cold (a Lung syndrome), needle only **L.I.-4** (*yuan*-source point).

d For unilateral musculoskeletal disorders affecting a Yang channel: in addition to local and adjacent points on the affected channel, needle the contralateral *luo*-connecting point of the Interiorly–Exteriorly paired Yin channel. This method, which promotes balance between Yin and Yang, is mainly used for channel-pertaining disorders. For example: for unilateral arm or shoulder pain along the L.I. channel, needle points on the L.I. channel on the affected side as well as **LU-7** on the opposite side of the body.



Yin–Yang balance for unpaired channels

Examples:

ST-36 + P-6	Harmonises the Middle Burner and descends counterflow Qi
L.I.-4 + LIV-3	Most important combination for regulating the Qi flow in the whole body

8.3.4 Combining Points from Above and Below



- A balance between the **upper and lower** half of the body is achieved by selecting points that are evenly distributed. For headaches, therefore, **L.I.-4** on the upper extremity is combined with **ST-44** on the lower extremity.
- Combining points above with points below **promotes the smooth flow of Qi**. For example: combining the opening point and coupled point of an extraordinary vessel (→ 8.1.8).

When points from above and below should not be combined

- for acute disorders of the joints and the back – here only distal points should be needled with the reducing method.
- if there is a pre-existing energetic disharmony between above and below. For example: for Heat sensations of the head (for example due to Kidney Yin deficiency with Empty Fire) needle **KID-1** in order to cause the Qi to descend. On the other hand, for a uterine prolapse use moxibustion **on Du-20** in order to raise the Qi.

8.3.5 Left–Right Combination

Often the balance between the right and left half of the body can be restored through bilateral needling of the relevant points. This will increase the therapeutic effect as opposed to unilateral needling.

Clinical application for Interiorly–Exteriorly paired channels (→ 1.2.3)

- For acute unilateral channel disorders caused by the invasion of pathogenic factors, combine **local points** on the affected side with the ***luo*-connecting point** on the contralateral side.
- For chronic unilateral channel disorders caused by the invasion of pathogenic factors, combine **local points** on the affected side with the *luo*-**connecting point** of the **Interiorly–Exteriorly paired channel** on the **contralateral** side (with tonifying technique).

Indications for unilateral and/or contralateral needling

- **For acute, painful disorders:** contralateral or diagonal needling (corresponding hand and foot channel, also see → 8.2.1 and → 8.2.2)
- **For chronic joint disorders:** ipsilateral needling of several points balanced by needling of contralateral points.
- **In paediatric acupuncture** (use fewer needles)
- **For ongoing treatment sessions:** occasional balancing contralateral needling of the healthy side of the body

8.3.6 Chain and Lock Point Association Method

Two, three or more points on the same channel are selected and needled one after the other (in a row). This method is predominantly applied for disorders of the musculoskeletal system or the nervous system.



8.3.7 Point Selection According to the Organ Clock

Within a 24-hour cycle each channel experiences a two-hour period of maximum Qi flow (→ Fig. 1.17, Chinese Organ clock). Some modern (Western) schools extrapolate the circadian Qi flow to the Organs (internal channel pathways and divergent channels). If one Organ is at its maximum period, the Organ on the opposite side of the clock will be at its minimum period, in other words the Qi flow will at that time be at its lowest. Symptoms of a disorder occurring at a particular time may provide a hint about the Organ affected, which at that time will be during its **maximal period in excess syndromes** or during its **minimal period in deficiency syndromes**.

For example: Always waking up between 1 and 3 am can be a sign of a Liver syndrome. Thus the tonification point and/or *luo*-connecting point of the channel opposite to the Liver on the Organ clock could be selected, in this example **S.I.-3** (*houxi*, tonification point) or **S.I.-7** (*zhizheng*, *luo*-connecting point).







Addendum: There are some very specific methods for chrono-acupuncture, for exampel the *zi wu liu zhu* method and the *ling gui ba fa* method, where points are needled at specific times (→ Kubiena and Ramakers 2002).

8.3.8 Clinical Application

The following illustration shows the clinical application of several point selection methods (8.3.1 – 8.3.5) for the treatment of dysmenorrhoea.



Possible point combinations for the treatment of dysmenorrhoea:

a. combining local and distal points (→ 8.3.1)
b. combining points on the front and the back of the body (→ 8.3.2) and Yin–Yang (→ 8.3.3)
c. Yin–Yang combination (→ 8.3.3) and above–below (→ 8.3.4)
d. Combination of all of the above methods (→ 8.3.1–8.3.4)
e. Additionally combining points on the left and right side of the body (→ 8.3.5)

9 Scientific Research

Ingolf Hosbach

9.1 Introduction

The aim of this chapter is to give a comprehensive overview about the scientifically proven or disproved effectiveness of certain points. It is not the aim of this chapter to prove the effectiveness of acupuncture as such. Based on the latest research, and 1000 recent human studies with mostly positive results, it is assumed that acupuncture is effective, despite criticism. If applied properly it is a well-established, low-risk method with minimal side effects.

Accordingly, the scope of acupuncture research has developed from simple questions, such as whether acupuncture works, to more specific questions such as which acupuncture points can be used for which conditions and with which stimulation methods. Furthermore, studies are increasingly designed for precise diagnoses and treatments based on the principles of Traditional Chinese Medicine. By the same token, the quality of the biomathematical methods used for the design and analysis of the studies is increasing. The number of randomised, controlled studies (RCTs) is also on the rise (Fig. 1).



Fig. 1: Number of all publications and RCTs per year between 1954 and 2005. (Source: PubMed, US National Library of Medicine, Bethesda, Maryland)

The percentage of RCTs of all publications is nearly 7%, a figure that compares well with most conventional forms of therapy (for example: arthroscopy 5%, beta-blockers 7%, pain medication 7%, lowering cholesterol medication 8–11%).

Fundamental principles for scientific assessment

One of the prerequisites for including a study in this chapter was the mention of specific acupuncture points in the abstract. Out of 1092 studies listed in PubMed until May 2006 under the keyword 'acupuncture', 259 were therefore chosen for this chapter. In some exceptional cases, studies based on animal experiments were also considered. Regarding the presentation of the results, particular emphasis was placed on the role of biomathematical methods as a parameter for reliability. The terms which allow assessment of a study in terms of its biomathematical quality are explained below:

Case study: Usually a retrospective (=in hindsight) summary of results of a particular treatment method in patients with a particular disorder; no control group or control therapy. Most basic form of clinical trial.

Controlled study: Usually a prospective (=planned in advance) scientific comparison of a treatment method with a group of untreated patients or of patients treated with a placebo or conventional therapy.

Placebo: A form of 'mock' or sham therapy. This can take the form of a pill containing no active ingredient or a therapy without any authentic foundation. The administration of a placebo tries to eliminate the non-specific improvement of the researched disorder (such as the therapist's care of the patient and expectations of the patient) compared to the study group receiving authentic treatment. While the possibilities for placebo-acupuncture are plentiful, none is free of disadvantages. The effectiveness of acupuncture as a holistic therapy can be seen as the sum of many psychological as well as non-specific and specific physiological effects. Depending on the choice of the acupuncture placebo, certain effects can be excluded. Based on the concept of the sinew channels, however, there is an ongoing debate whether non-acupuncture points exist at all. The highest level of placebo acupuncture is the so-called 'sham acupuncture' where actual deep needling takes place at non-acupuncture points. The value of a study increases considerably if it is controlled by a placebo therapy.

Randomisation: The random assignment of a patient to a treatment group, without any influence of either the patient or the therapist. Randomisation significantly increases the value of a study.

Waitlist: A control group formed by patients receiving no treatment as a form of control. While a patient is waiting for his/her treatment, all his/her data relevant to the treatment are collected and later compared to those data obtained during treatment. Since there is neither randomisation nor a placebo treatment, the value of a waitlist group as a control group is very low.

Cross-over study: A particular design of controlled study. Each patient will participate in two different courses of treatment (for example treatment 1: medication; treatment 2: acupuncture). The order in which the treatments are administered can differ from patient to patient and be random (=randomised cross-over study). However, any long-term effect of the first form of treatment poses a problem for the final result. Therefore so-called washout phases during which patients receive no treatments at all are implemented to eliminate these effects and prevent a distortion of the data to be collected during the second phase. Since the effects of some acupuncture treatments have been shown to last for up to a year, cross-over studies are not very suitable for acupuncture research and particularly non-significant results should be questioned.

The ‘n of 1’ study is another form of research: a patient will receive various different treatments in order to find out which form of treatment led to the best improvement for the relevant disorder. However, the same limitations as discussed above will affect this type of study.

Significance: In simple terms, the significance of a study indicates if the difference of a particular parameter which has been observed between two groups is caused by the treatment (and is therefore a true difference) or whether the difference is the result of random deviation. For example, if in a large number of treated patients the observed data differ ‘significantly’ from a group of untreated patients, it is **highly probable** that this difference is not due to a random deviation. This probability can be expressed mathematically. If, for example, the significance is expressed as $p = 0.03$ this means that, considering a random error of 3%, the difference noted between the two groups is statistically significant. The convention is to accept a random error of up to 5% as acceptable. The significance of a study is based on the number of patients treated and the extent of the difference in the treatment result (for example by assuming the same random error, the difference in treatment results has to be much larger in a group of 10 patients ($n = 10$) than if the same study was carried out with 100 patients ($n = 100$)). Only differences classified as ‘significant’ are accepted for research studies.

Power of the study: This refers to the ability of a study to be statistically significant. The higher the number of participants, the higher the power of the study. By international standards, 80% is an acceptable level of power. Depending on the difference between the two study groups, the number of patients required can therefore easily be in the 100s or 1000s.

Experimental studies: Through standardising and controlling conditions of the experiment strictly, every attempt is made to avoid random results, often leading to just a small number of participants. Generally these tend to be healthy volunteers, who are subjected to a clearly defined stimulus. In this case acupuncture as a form of therapy will achieve a high level of validity. More questionable are studies of healthy subjects without a well-defined stimulus, since in that case acupuncture as a balancing form of treatment is not used according to its principles (for example changes in peristalsis caused by acupuncture in healthy subjects).

Blinding: The gold standard of clinical trials are the so-called double blind studies in which both the patient and the therapist remain ignorant as to which treatment (for example the tablet with or without the active ingredient) is administered to the patient. However, blinding of an acupuncturist is not possible. Even in a single blind study (only the patient is ‘blinded’), his/her behaviour will distort the result of the trial. This effect can be counterbalanced to some extent by blinding the assessor of the treatment results (for example changes in the range of motion) so that he/she does not know which treatment (authentic or sham acupuncture) was received by the patient.

Standardisation: In pharmaceutical trials the amount of the active ingredient per tablet can easily be stated (for example standardisation of a 10 mg tablet). However, acupuncture cannot be standardised. The acupuncturist’s point selection will largely be influenced by experience, prior knowledge, specialisation and cultural background. Strictly speaking, acupuncture trials therefore do not investigate acupuncture per se but acupuncture as performed by an acupuncturist or a group of acupuncturists.

The fact that acupuncture is to a large extent centred on the therapist has in the past led to a paradoxical situation: experienced Chinese acupuncturists performing the ‘best’ acupuncture produced biomathematically ‘bad’ trials due to their lack of training, while ‘bad’ Western acupuncturists produced ‘good’ trials from a biomathematical point of view. ‘Importing’ Chinese acupuncturists into Western trials did not solve the problem either, since the Chinese clinicians were now treating Europeans with diseases not common in China and which reacted differently to acupuncture. Only as experience grows on both sides – which would have to be evaluated individually for each trial – will the value of acupuncture as a researched form of therapy increase accordingly.

9.2 Scientific Research According to Channels

Lung Channel

LU-5 ➞ Ren-23; L.I.-10



LU-6 192 patients with bronchial asthma were treated with **LU-6** and **LU-10**. 98.9% of the patients experienced an immediate improvement; the rate of clinical remission plus marked improvement was 76.5%. Best therapeutic results were achieved for allergic asthma according to Western medicine (asthma due to Cold according to TCM) and with longer needle retention (approximately 40 minutes). The lack of blinding and control groups reduce the value of this precise therapeutic case study. **Zang, J Tradit Chin Med 1990**

LU-7 ➞ ST-8

LU-10 ➞ LU-6

A Chinese prospective, randomised, controlled, non-blinded trial investigated the effect of bilateral bloodletting at **LU-10**, **P-8**, **HE-8**, **L.I.-2**, **T.B.-2** and **S.I.-3** on heart rate and consciousness in patients with **apoplexy** that had occurred within 3 days. Only patients with mild injuries showed improved consciousness while the heart rated increased independently of the size of injury. **Yi et al**, **J Tradit Chin Med 2005**



LU-11 Three Russian animal trials demonstrated the antipyretic action of **LU-11**. LU-11 can also strengthen the effect of hypothermic substances, suggesting a combination with antipyretic Chinese herbs. **Nezhenzev et al**, **Biull Eksp Bio Med 1992, and Fizion Zh SSSR Im I M Sechenova 1991**

A Taiwanese prospective, randomised, non-blinded, controlled trial ($n = 76$) investigated whether bloodletting at **LU-11** and **L.I.-1** can prevent or treat the occurrence of **laryngospasm** after tracheal extubation in children. The incidence of laryngospasm was significantly less in the bloodletting group (5% vs 24%). If laryngospasm developed, this could be relieved with the treatment of LU-11 or L.I.-1 within one minute in all patients. **Lee et al, Anaesthesia 1998**

Large Intestine Channel

L.I.-1 ➞ LU-11

L.I.-2 ➞ LU-10



L.I.-3 A Chinese prospective, randomised, controlled study ($n = 210$) reports the significantly better effects of needling **L.I.-3** and ***lingxia*** in the treatment of **periarthritis of the humerus** compared to the control group treated with local points. Of interest is the application of *lingxia*, an unofficial extra point 2 cun inferior to G.B.-34. **Feng, J Tradit Chin Med 2003**



L.I.-4 ➞ ST-36; P-5, P-6; ST-8; G.B.-43; Du-20; LIV-3; S.I.-18; SP-9; L.I.-11; ST-2

A Turkish prospective, controlled, non-blinded, group-comparison trial ($n = 55$) investigated the effect of electro-acupuncture (EA) at **L.I.-4**, **L.I.-11**, **ST-25**, **ST-36**, **ST-44** and **LIV-3** (combined with auricular points *shenmen* and *sanjiao*) on **obesity in women**. Treatments were given daily for 20 days. One control group received a 1425 kcal diet for 20 days while the other control group received no treatment. There was a 4.8% weight reduction in the EA group, whereas women on the restricted diet had a 2.5% weight loss. Both groups showed a significant reduction in total cholesterol and triglyceride levels. In the EA group only, LDL levels were also reduced significantly. **Cabioglu et Ergene**, **Am J Chin Med 2005**

A Chinese (Hong Kong) prospective, randomised, controlled, non-blinded study ($n = 29$) investigated the effect of **L.I.-4** and **P-6** on the heart rate variability (HRV) in normal subjects in **fatigue** and **non-fatigue states** respectively. Only fatigued subjects showed a significant change in HRV. The authors concluded that the effect of acupuncture depends not only on the points selected but also on the functional state of the subject, one of the principles of Chinese Medicine. **Li et al, Eur J Appl Physiol 2005**

An unusual veterinary case study investigated the effects of acupuncture on the **immune system**. According to the authors, immunostimulant points **include LI-4**, **LI-11**, **ST-36**, **GB-39**, **SP-6**, **GV-14**, **BL-11**, **BL-20**, **BL-23**, **BL-24**, **BL-25**, **BL-26**, **BL-27**, **BL-28,** and **Ren-12**. **BL-47** is considered to be immunosuppressive. Anti-febrile points include **ST-36** and **Du-14**. **Rogers et al, Probl Vet Med 1992**

A Chinese prospective, randomised, single-blinded, experimental trial ($n = 20$) compared the effect of transcutaneous electric nerve stimulation (TENS) at **L.I.-4** on the **heat pain threshold** and **vibration threshold** in humans with a placebo control point. In the study group, after TENS at **L.I.-4**, the pain threshold for heat was higher for up to half an hour compared to the control group. There was no effect on the threshold for feeling vibration. **Wang et al, Chin Med J (Engl) 2003**

A Korean prospective, randomised, placebo-controlled trial ($n = 35$) evaluated the efficacy of electro-acupuncture (EA) and moxibustion on **L.I.-4**, **L.I.-10**, **L.I.-11** and **T.B.-5** on **spasticity due to stroke**. The control group was treated with routine acupuncture. Only the EA group experienced a significant, immediate and lasting reduction in spasticity (using a modified Ashworth scale). **Moon et al, Am J Chin Med 2003**

A German prospective, randomised, controlled, non-blinded trial ($n = 29$) investigated if acupuncture at **L.I.-4**, **T.B.-5**, **ST-36**, **P-6**, **Du-20** and **Ex-UE-9** (*baxie*) had a vasospasmolytic effect on patients with **Raynaud's syndrome** during the winter season. There was no significant difference regarding the number and intensity of episodes, nor was there a significant effect on skin microcirculation between the acupuncture group and the placebo group before and after treatment. **Hahn et al, J Dtsch Dermatol Ges 2004**

A Japanese prospective, randomised, controlled study ($n = 21$) investigated the effect of **L.I.-4**, **ST-36 and SP-6** on objective and subjective parameters regarding **exhaustion** in elite female soccer players during a competition period. Only the subjects treated with acupuncture experienced a better rating for both subjective and objective parameters. **Akimoto et al, Med Sci Sports Exerc 2003**

A Chinese prospective, randomised, controlled trial ($n = 89$) researched the effect of **L.I.-4**, **ST-36**, **BL-18** and **BL-23** combined with CT positioning scalp circum-needling (SCN) and herbal therapy in patients with **poly-infarctional vascular dementia**. The control group received herbal treatment only. The treated group had a significantly better short-term result (96.5%) than the control group (75%) regarding changes of clinical symptoms, intelligence and haemorrheological characteristics. **Lun et al, Zhongguo Zhong Xi Yi Jie He Za Zhi 2003**

A Chinese prospective, randomised, controlled experimental trial ($n = 11$) investigated the changes in **brain activation patterns** evoked by stimulating **L.I.-4** manually versus stimulation with electro-acupuncture (EA). These were assessed by functional magnetic resonance imaging (fMRI). Results showed that EA mainly produced fMRI signal increases in precentral gyrus, postcentral gyrus/inferior parietal lobule and putamen/insula; in contrast, manual needle manipulation produced prominent decreases of fMRI signals in posterior cingulate, superior temporal gyrus, putamen/insula. These results suggest that different brain mechanisms may be recruited during manual and EA. **Kong et al, J Altern Complement Med 2002**

An American prospective, randomised, controlled, non-blinded experimental trial ($n = 13$) evaluated the effect of transcutaneous electric acupoint stimulation (TEAS) on **L.I.-4** and **P-6** on **tonic pain** induced with the cold-pressor test. While TEAS alone had a significant analgesic effect, this could be increased by combining TEAS analgesia with low-dose morphine. **Yuan et al, J Clin Pharmacol 2002**

A Taiwanese prospective, randomised, placebo-controlled experimental study ($n = 13$) investigated the effect of manual acupuncture as well as transcutaneous electrical nerve stimulation (TENS) with 2 Hz and 100 Hz respectively at **L.I.-4** on the spinal cord by measuring the **H-reflex**. While the application of TENS with both 2 Hz and 100 Hz changed the amplitude of the H-reflex, it was retained longer with the 100 Hz stimulation. These findings suggest that TENS enhances the excitability of the motoneuron pool in the spinal cord. **Chang et al, Acupunct Electrother Res 2001**

An Austrian prospective, randomised, controlled study ($n = 45$) evaluated whether acupuncture at **L.I.-4** and **SP-6** at term can influence cervical ripening, **induce labour** and thus reduce the need for postdate induction. Compared to the control group, the study group showed a significantly shorter time span (three days) between estimated date of confinement (EDC) and actual time of delivery. Medical induction of labour 10 days after EDC was also significantly lower in the acupuncture group (20%) than in the control group (35%). **Rabl et al, Wien Klin Wochenschr 2001**

An Israeli prospective, randomised, double-blinded controlled trial ($n = 25$) investigated the effect of acupuncture in the treatment of **irritable bowel syndrome**. True acupuncture was performed at **LI-4** and sham acupuncture at **BL-60** during a total of two sessions. There was no significant difference between the two groups. However, the choice of acupuncture points seems somewhat peculiar. While both points are Ma Dan Yang points (the 12 most important points), they have no specific action for intestinal disorders. Obviously the authors chose the points according to the channel (Large Intestine). Furthermore, only two treatments does not seem sufficient. **Fireman et al, Digestion 2000**

A British prospective experimental trial ($n = 14$) investigated the effect of acupuncture at **L.I.-4** on the **resting EEG** of healthy subjects. Acupuncture did not induce any changes in the resting EEG. **Rosted et al, Complement Ther Med 2001**

An Irish prospective, randomised, controlled trial ($n = 30$) applied transcutaneous electric nerve stimulation (TENS) either at **L.I.-4** or over the median nerve, in order to investigate **cutaneous blood flow**. The control group received no treatment. Only TENS over the median nerve showed a significant increase in cutaneous blood flow. **Cramp et al, Acupunct Electrother Res 2001**

A Japanese prospective, randomised, controlled, non-blinded trial ($n = 22$) investigated the effect of acupuncture at **L.I.-4**, **ST-6** and **ST-7** on pain after mandibular **wisdom tooth extraction**. Compared to the control group there was a significant reduction in pain in the treatment group. **Kitade et al, Acupunct Electrother Res 2000**

A Swedish prospective, randomised, controlled experimental trial ($n = 12$) investigated if acupuncture at **L.I.-4** induced **changes in the sympathetic and/or parasympathetic nervous system** in healthy subjects. For this purpose, regular and superficial needling of **L.I.-4** was compared. Changes were measured by using power spectral analysis and heart rate frequency analysis. Only deeper needling at L.I.-4 led to a significant activation of the sympathetic and parasympathetic nervous system during and after treatment as well as to a significant reduction of the heart rate frequency. **Haker et al, J Auton Nerv Syst 2000**

A US prospective, randomised, sham-controlled, single-blinded trial ($n = 101$) assessed the effect of varying intensities of transcutaneous electric acupoint stimulation (TEAS) at **L.I.-4** on the **postoperative patient-controlled analgesia** (PCA) requirement for **hydromorphine** (HM), the incidence of opioid-related side effects, and the recovery profile after lower abdominal surgery in women. In the sham-TEAS group HM-requirement was reduced by 23%, low-intensity TEAS produced a 34% decrease in the HM requirement while the high-intensity TEAS reduced requirement significantly by 65%, accompanied by a reduction in the occurrence of dizziness, nausea and pruritus. **Wang et al, Anesth Analg 1997**

A Chinese prospective, randomised, controlled trial ($n = 110$) investigated the effect of transcutaneous electric acupoint stimulation TEAS) at **L.I.-4**, **Ex-HN-4** ***(yuyao)*** and **G.B.-31** during enflurane anaesthesia in patients undergoing craniotomy. In comparison to the control group (anaesthesia maintained with enflurane only) the **minimum alveolar concentration** (MAC) of enflurane decreased in the TEAS-supplemented group by 38–47%. If anaesthesia was supplemented by TEAS plus scalp infiltration with procaine, there was an even higher reduction of 42–66%. The haemodynamic balance was also more stable during the operation, and postoperative recovery was faster. **Wang et al, Zhongguo Zhong Xi Yi Jie He Za Zhi 1994**

A German prospective, waitlist-controlled trial ($n = 6$) investigated the effect of electro-acupuncture at **L.I.-4**, **ST-25**, **LIV-3** and **BL-25** on stool frequency and colonic transit time in **chronic constipation**. There were no significant differences in all the parameters between the control group and the waitlist group. **Klauser et al, Z Gastroenterol 1993**

A Japanese experimental trial researched the influence of **L.I.-4 on vibration induced finger flexion reflex**. Unilateral acupuncture at L.I.-4 suppressed the reflex in both hands. **Takakura et al, Am J Chin Med 1992**

A Chinese prospective, randomised, matched controlled trial ($n = 12$) investigated the analgesic effect of aqueous acupuncture (injection of glucose solution) at **L.I.-4** and **G.B.-34** in **postoperative pain control**. In comparison to the control group, the intensity of postoperative pain as well as the requirement for analgesic medication were significantly lower in the study group. **Chen et al, Gaoxiong Yi Xue Ke Xue Za Zhi 1991**

A German prospective, non-randomised, sham-controlled trial ($n = 36$) investigated the **analgesic effect** of acupuncture at **L.I.-4**, **P-6**, **ST-36** and **SP-4** prior to a **colonoscopy**. The pain experienced by the acupuncture patients was significantly lower compared to the group receiving sham acupuncture. The analgesics and sedatives required were also significantly less. **Li et al, Dtsch Med Wochenschr 1991**

A prospective, randomised, single-blinded experimental study ($n = 39$) investigated the effect of acupuncture and laser acupuncture at **L.I.-4** and **Ex-UE** ***jianqian*** on the **pain threshold**. Compared to laser acupuncture, acupuncture significantly increased the pain threshold. **Brockhaus et al, Pain 1990**

A British prospective, controlled experimental cross-over study investigated the effectiveness of electro-acupuncture at **L.I.-4** on experimental **tooth pain**. After 30 minutes of electric stimulation the pain threshold increased by 27%. This increase could be partially blocked by naloxone. **Ernst et al, Acupunct Electrother Res 1987**

A British prospective, randomised, placebo-controlled study ($n = 51$) investigated the effect of acupuncture at **L.I.-4** as an **analgesic for operative dentistry**. There were no significant differences between the treatment group and the placebo group. **Taub et al, Oral Surg Oral Med Oral Pathol 1979**

A prospective non-randomised, placebo-controlled experimental trial ($n = 40$) investigated the effect of acupuncture at **L.I.-4** on the **pain threshold of postoperative dental pain** compared to codeine. Both **L.I.-4** and codeine had a significantly better effect than the placebo. The combination of both had the strongest effect. **Sung et al, Anesth Analg 1977**

An Austrian prospective, sham-controlled, single-blinded experimental trial ($n = 12$) measured the effect of **L.I.-4** and **P-6** on **pain threshold and pain tolerance**. In contrast to sham acupuncture, true acupuncture significantly raised the pain threshold. **Stacher et al, Am J Chin Med 1975**

L.I.-5 → P-5
L.I.-6 → P-5
L.I.-7 → P-5



L.I.-10 → L.I.-4; Du-12; ST-36

A Swedish prospective, randomised, controlled, double-blinded trial ($n = 49$) investigated the effect of laser acupuncture on **L.I.-10**, **L.I.-11**, **L.I.-12**, **LU-5** and **T.B.-5** on **lateral humeral epicondalgia (tennis elbow)**. No significant difference occurred at a dose of 0.36 J/point. **Haker et al, Pain 1990**



L.I.-11 → L.I.-4; ST-36; LIV-3; L.I.-10; L.I.-15

A Taiwanese prospective, randomised, placebo-controlled, single-blinded trial ($n = 40$) investigated the effect of acupuncture at **L.I.-11** on **uraemic pruritus**. The results of the pruritus score questionnaires demonstrated that only true acupuncture at **L.I.-11** resulted in a significantly reduced pruritus lasting for a period of three months. Uraemia levels remained unchanged. **Che-yi et al, Nephro Dial Transplant 2005**

A German prospective, randomised, placebo-controlled, single-blinded experimental trial (*n* = 22) investigated the effect of **L.I.-11** on the **phagocytic immune system**. Based on laboratory parameters, the **activity of neutrophils** was significantly higher in the study group. **Karst et al, Complement Ther Med 2003**

A Swedish prospective, non-randomised, placebo-controlled, single-blinded experimental longitudinal trial investigated the influence of electro-acupuncture at **L.I.-11** and **L.I.-4** on sympathetic nerve activity and the pain threshold. Only electro-acupuncture at L.I.-11 and L.I.-4 increased the pain threshold in combination with increased sympathetic nerve activity. **Knardahl et al, Pain 1998**

A Swedish prospective, randomised, placebo-controlled, single-blinded trial (*n* = 58) investigated the effect of laser acupuncture at **L.I.-11** and **L.I.-12** for **lateral humeral epicondalgia (tennis elbow)** compared to laser application on the painful area. There were no significant differences between the laser and placebo treatments after the treatment period. **Haker et al, Arch Phys Med Rehabil 1991**



L.I.-12 → L.I.-11; L.I.-10

A Chinese prospective, randomised, controlled trial (*n* = 64) investigated the effect of electro-acupuncture at **L.I.-12**, **T.B.-5**, **G.B.-30** and **ST-36** accompanied by medication for **acute cerebral infarction** with regard to the plasma and CSF somatostatin levels. The control group received medication only. Both plasma and CSF somatostatin levels increased significantly in the acupuncture group. **Zhang et al, J Tradit Chin Med 1999**

A Chinese prospective, randomised, controlled trial (*n* = 64) investigated the effect of electro-acupuncture at **L.I.-12**, **T.B.-5**, **G.B.-30** and **ST-36** on the plasma and CSF levels of VIP (vasoactive intestinal peptide), somatostatin and pancreatic polypeptide in patients with **acute cerebral infarction**. The CSF VIP level dropped significantly while the plasma pancreatic polypeptide level increased significantly. In patients with a good response both plasma and CSF somatostatin levels increased significantly after acupuncture. **Zhang et al, Zhen Ci Yan Jiu 1996**



L.I.-15 A Taiwanese prospective, randomised, controlled, non-blinded trial (*n* = 150) investigated the effect of electro-acupuncture at **L.I.-15**, **G.B.-21** and **Ex-UE *jianneiling*** with or without regional nerve block (RNB) (stellate ganglion and suprascapular plexus) for **'frozen shoulder' (adhesive capsulitis)**. This was compared to RNB treatment alone. The combination of electro-acupuncture and RNB produced the most significant reduction of pain and duration of pain relief as well as improvement of range of motion. **Lin et al, Acta Anaesthesiol Sin 1994**

A Chinese prospective, randomised, controlled, non-blinded trial (*n* = 63) investigated the effect of acupuncture at **L.I.-15**, **L.I.-11**, **L.I.-4**, **G.B.-30**, **G.B.-34**, **G.B.-37**, **LIV-3**, **G.B.-20**, **ST-25**, **ST-40**, **ST-36**, **SP-6** and **KID-3** on symptoms of **cerebral infarction** compared to the treatment with the calcium channel blocker verapamil. The effectiveness in the acupuncture group was 94%, in the verapamil group 84%. This difference is statistically significant. However, the choice of a calcium channel blocker seems unusual for this indication. **Zou et al, Zhong Xi Yi Jie He Za Zhi 1990**



L.I.-20 → G.B.-14

A British prospective, randomised, controlled trial (*n* = 20) investigated the effect of a 30 second massage at **L.I.-20** on **nasal airflow** compared to an untreated control group. Symptoms improved significantly in the massage group. **Takeuchi et al, Am J Rhinol 1999**

Stomach channel



ST-2 → G.B.-14

A prospective, non-randomised experimental trial (*n* = 33) investigated the effect of acupuncture and electro-acupuncture at **ST-2**, **L.I.-4** and **ST-44** on experimentally induced **tooth pain**.

While both procedures increased the pain threshold, the increase was not sufficient to justify acupuncture as a means of pain control in conservative dentistry. **Bakke, Scand J Dent Res 1976**

ST-4 → G.B.-14

ST-6 → G.B.-14; L.I.-4

ST-7 → L.I.-4



ST-8 A large prospective, randomised, multi-centre, group-comparison trial ($n = 120$) in patients suffering from **migraine without aura** demonstrated that acupuncture at **ST-8**, **G.B.-5**, **G.B.-20**, **Du-14** and **LU-7** was significantly more effective than conventional drug therapy, regarding both frequency and duration of the migraine attacks as well as number of sick days. The authors calculated that by treating migraine with acupuncture the Italian health system could save approximately 0.5 billion Euros per year. **Liguori et al., J Tradit Chin Med 2000**

A Bulgarian case study ($n = 35$) reports the successful treatment of headaches following caesarian sections with spinal anaesthesia with acupuncture at ST-8, L.I.-4, G.B.-11, G.B.-14, BL-10, Du-14 and Du-20 during 1–3 treatments. **Tsenov, Akush Ginekol (Sofia) 1996**

A Swedish prospective, placebo-controlled trial investigated the effect of intrasegmental (**ST-8**) and extrasegmental (**L.I.-4**) electro-acupuncture on sensory thresholds. Only the pain threshold could be increased, and this only with intrasegmental acupuncture at ST-8. **Lundeberg et al, Am J Chin Med 1989**

ST-18 → G.B.-14; Du-1

ST-20 → T.B.-8

ST-21 → Du-20



ST-25 → Du-1; Du-20; L.I.-4; L.I.-15

A Chinese prospective, randomised, controlled trial ($n = 62$) investigated the effect of acupuncture and moxibustion at ST-25 and Ren-4 for chronic colitis. This was compared to modern drug therapy. The acupuncture group showed the same therapeutic results but with fewer side effects. **Yang et al, J Tradit Chin Med 1999**



ST-32 → G.B.-31

ST-34 → ST-36; SP-9

ST-35 A Chinese prospective, randomised, single-blinded, controlled, long-term trial ($n = 24$) investigated the effect of electro-acupuncture (EA) and transcutaneous electrical nerve stimulation (TENS) at **ST-35** and **Ex-LE-4** (eight treatments over a period of two weeks) in older patients (average age: 85 years) suffering from **painful osteoarthritic knees**. This was compared to conventional therapy for this disorder. Both TENS and EA significantly reduced the knee pain. EA also had an effect on range of motion. **Ng et al, Altern Complement Med 2003**



ST-36 → L.I.-4; BL-27; P-6; T.B.-8; G.B.-26; G.B.-31; Du-1, Ex-B-3; Du-4; Du-20; LIV-3; SP-9; BL-60; L.I.-12; L.I.-15; Ren-17

An Iranian prospective, randomised, placebo-controlled, single-blinded trial ($n = 51$) investigated the effect of transcutaneous electric nerve stimulation (TENS) at **ST-36** and **ST-38** on nitroglycerin-induced **hypotension under general anaesthesia with halothane**. With true acupuncture at the above points, the mean arterial blood pressure (MAP) was significantly lower (60 vs 66 mmHg). The effect of acupuncture was significantly greater with lower dosages of nitroglycerin compared with higher dosage. In addition, the time to reach steady state MAP was significantly shorter (10 vs 15.8 minutes) and the quality of operative ischaemia was excellent in 83.3% subjects compared to 25% in the sham group. **Saghaei M. et al, Acta Anaesthesiol Taiwan 2005**

A US prospective non-blinded experimental trial investigated the response to acupuncture at **ST-36** as evidenced by **fMRI**. The limbic and paralimbic structures of the cortical and subcortical regions in the telencephalon, diencephalon, brainstem and cerebellum were activated in response to acupuncture. **Hui et al, Neuroimage 2005**

A prospective, randomised placebo-controlled single-blinded trial ($n = 13$) investigated the effect of electro-acupuncture at **ST-36** on the **heart rate variability** (HRV) in healthy subjects. There was no acupuncture-specific effect on HRV. **Chang et al, Am J Chin Med 2005**

A German prospective randomised placebo-controlled single-blinded experimental crossover study ($n = 10$) investigated the effect of acupuncture at **ST-36**, **L.I.-11**, **SP-10 and Du-14** on

leukocyte circulation in healthy young subjects. There was a significant decrease in leukocyte and lymphocyte values in the acupuncture group while cortisol and norepinephrine plasma levels remained unchanged. **Kou et al, Brain Behav Immun 2005**

A US prospective, non-randomised, placebo-controlled, single-blinded trial (*n* = 7) investigated if electro-acupuncture at **ST-36, SP-6**, **ST-34** and **L.I.-4** before and during induction of general anaesthesia (desflurane) influenced the **anaesthetic requirement** compared to a control group. There was no reduction in pain in the treatment group. **Chernyak et al Anesth Analg 2005**

A Taiwanese prospective, randomised, placebo-controlled, single-blinded experimental cross-over study (*n* = 15) investigated if electro-acupuncture (EA) at **ST-36** can normalise **atropine-induced gastric dysrhythmia**. While there was a significant increase in the percentage of normal frequency, atropine-induced gastric dysrhythmia was not normalised by EA (no significant differences in the EGG). **Chang et al, Dig Dis Sci 2002**

A Taiwanese prospective, randomised, controlled experimental trial (*n* = 15) investigated the effect of **ST-36** on **gastric myoelectrical regularity**. There was a significant decrease in the tachygastric and bradygastric rhythm during electro-acupuncture on ST-36. **Chang et al, Digestion 2002**

A Taiwanese prospective, randomised, sham-controlled trial (*n* = 100) investigated the effect of electro-acupuncture at **ST-36** on **postoperative pain and opioid-related side effects**. The postoperative pain, the requirement for morphine (via PCA) and the incidence of nausea and dizziness were all significantly reduced. **Lin et al, Pain 2002**

A US prospective, randomised, double-blinded, sham-controlled experimental trial (*n* = 14) investigated if electro-acupuncture at **ST-36**, **G.B.-34** and **BL-60** could reduce the anaesthetic requirement (desflurane) for **experimental pain stimuli**. Electro-stimulation of these points did not reduce desflurane requirements compared to the control group. **Morioka et al, Anesth Analg 2002**

A Taiwanese prospective case study (*n* = 15) investigated the effect of bilateral electro-acupuncture **at ST-36** on gastric slow waves in **diabetic patients** with symptoms suggesting **gastric motor dysfunction**. Changes of gastric activity were measured by EGG. During and after acupuncture there was a significant increase in the percentages of normal frequency. In addition the percentage of tachygastric frequency was decreased significantly during and after acupuncture. **Chang et al, Digestion 2001**

A Chinese case study (*n* = 104) reports the successful injection-acupuncture at **ST-36** for **chemotherapy-induced leukopenia**. **Yin et al, J Tradit Chin Med 2001**

A Chinese prospective, randomised, controlled, non-blinded trial (*n* = 26) investigated the effect of acupuncture at **ST-36** plus auricular plaster therapy on **peristalsis** for postoperative recovery of intestinal function after abdominal surgery. 92% of patients in the treatment group showed recovery of normal peristalsis within 72 hours, while in the control group only 46% patients recovered within the same time-period. **Wan et al, J Tradit Chin Med, 2000**

A US prospective, randomised, controlled pilot study (*n* = 17) investigated the effect of acupressure at **ST-36** and **P-6** on the intensity and frequency of **nausea** in patients undergoing **chemotherapy due to breast cancer**. Both the frequency and intensity of the nausea was significantly lower in the treatment group than in the control group. **Dibble et al, Oncol Nurs Forum 2000**

An Italian prospective, randomised, controlled experimental trial (*n* = 120) investigated the effect of acupuncture at **ST-36** and **L.I.-4** regarding changes in the levels of beta-endorphins and other parameters (VIP, lymphocyte subsets, NK cells and monocyte phagocytosis) in patients suffering from various painful disorders. These changes were compared to an untreated control group. Only in the acupuncture group were the endorphin levels, the CD3 and CD4 values and monocyte phagocytosis increased for at least 24 hours after treatment. At the same time there was an increase of the CD8 values. **Petti et al, J Tradit Chin Med 1998**

A Chinese retrospective case study reports good results in treating **leukopenia** with acupuncture at **ST-36**. **Wei, J Tradit Chin Med 1998**

A Taiwanese prospective, randomised, sham-controlled experimental trial (*n* = 18) investigated the effect of acupuncture at **ST-36** and **L.I.-4** on central nervous system pathways with functional MR imaging of the brain. Besides a significant reduction of the heart rate frequency, acupuncture at both points resulted in activation of the hypothalamus and nucleus accumbens (structures of the descending antinociceptive pathway) and deactivation of the rostral part of the anterior cingulate cortex, amygdala formation, and hippocampal complex (limbic areas of pain recognition). Therefore this study provides explanations for the **pain-reducing effect** of acupuncture. **Wu et al, Radiology 1999**

A prospective, sham-controlled, single-blinded experimental longitudinal trial (*n* = 13) investigated the effect of acupuncture at ST-36 only, compared to acupuncture at **ST-36 plus L.I.-10** on **auditory endogenous potentials** (P300). The effect of the different forms of acupuncture was identical. In contrast to the sham group, it led to a decrease of P300 amplitude in the acupuncture group. **Hsieh et al, Am J Chin Med 1998**

A US prospective, randomised, sham-controlled, single-blinded trial (*n* = 100) investigated the effect of transcutaneous electric nerve stimulation (TENS) at **ST-36** on **opioid analgesic requirement** by PCA following hysterectomy or myomectomy compared to peri-incisional dermatomal stimulation by TENS. TENS applied at the dermatomal level of the incision is as effective as stimulation at ST-36, and both were more effective than stimulation at a sham location. **Chen et al, Anesth Analg 1998**

A Chinese prospective, randomised, controlled trial (*n* = 69) compared the so-called immunotherapy at **ST-36** to conventional desensitisation therapy in patients suffering from **anaphylactic asthma**. Results in the acupuncture group were significantly better, regarding both clinical and immunohistochemical parameters. **Chen et al, Zhongguo Zhong Xi Yi Jie He Za Zhi 1996**

A Mongolian prospective, randomised, controlled study ($n = 48$) compared the effect of acupuncture at **ST-36** and **P-6** combined with epidural anaesthesia to simple epidural anaesthesia for subtotal gastrectomies. The acupuncture group, while requiring a lower dosage of anaesthetic, experienced a stronger analgesic effect, the abdominal muscles were more relaxed and the haemodynamic disturbances were smaller. **Sun, Zhen Ci Yan Jiu 1996**

A US prospective, randomised, controlled, experimental trial ($n = 11$) researched the effect of transcutaneous electric nerve stimulation (TENS) at **ST-36** and **ST-37** on **peripheral blood circulation** and **haemodynamics**. Twenty minutes of TENS on healthy subjects did not produce a significant change in the measured parameters. **Balogun et al, Disabil Rehabil 1996**

A Taiwanese prospective, randomised, placebo-controlled, single-blinded trial investigated the influence of acupuncture at **ST-36** on the **pulse spectrum**. The results indicated that acupuncture at ST-36 has a specific effect on the Fourier components of the pulse: C2 and C4 decreased while C5, C6, C8 and C9 increased. This specific frequency effect was not found when acupuncture was applied on a non-acupuncture point. **Wang et al, Am J Chin Med 1995**

A Chinese prospective, randomised, controlled trial ($n = 45$) investigated the effect of **ST-36**, **L.I.-11** and **KID-6** on the immunoactivity of natural killer cells and the interleukin-2 level in **malignant tumour** patients. After receiving one treatment of 30 minutes daily for 10 days, parameters in the treatment group had increased significantly compared to the control group. **Wu et al, Zhongguo Zhong Xi Yi Jie He Za Zhi 1994**

A Chinese prospective, randomised, controlled trial ($n = 80$) compared **anaesthesia with electro-acupuncture** at **ST-36** and **L.I.-4** to epidural anaesthesia in **appendectomies**. The operations were equally successful in both groups, without any significant differences regarding the success rate. **Sun et al, Zhen Ci Yan Jiu 1992**

A Chinese prospective, randomised, controlled trial ($n = 39$) investigated the effect of acupuncture at **ST-36** and **SP-6** on **bowel movements following abdominal surgery**. In the acupuncture group the first postoperative bowel movement occurred after approximately 58 hours, but only after 86 hours in the untreated control group. **Liu et al, Zhong Xi Yi Jie He Za Zhi 1991**

ST-37 → ST-36

ST-38 → G.B.-34; ST-36

ST-40 → L.I.-15

ST-44 → L.I.-4; ST-2

Spleen channel

SP-1 A US prospective experimental trial ($n = 13$) investigated the effect of electro-acupuncture (EA) at **SP-1** and **LIV-1** on **thermal pain thresholds**. The pain threshold increased significantly 30 seconds after onset of EA. The authors postulate that EA at the above points has an inhibitory effect on the C-fibre afferents; the analgesic benefit observed is most probably A-delta afferent mediated. **Leung et al, J Altern Complement Med 2005**

SP-4 → Du-4; P-6; L.I.-4



SP-6 → ST-36; L.I.-4; P-6; G.B.-26; Du-4; Du-20; LIV-3; L.I.-15

In a prospective, randomised, double-blinded group-comparison trial ($n = 56$) patients suffering from **interstitial cystitis** performed daily laser therapy on SP-6 at home for 30 seconds over a period of 12 weeks. There were no significant differences between the treatment and control cohorts. **O'Reilly et al, J Urol 2004**

An Australian prospective, randomised, placebo-controlled trial ($n = 20$) investigated the effect of transcutaneous electrical stimulation (TENS) at **SP-6** and **LIV-3** on **uterine contractions** in post-date pregnant women. A significant increase in frequency and strength of contractions was found in the TENS group compared with the placebo group. **Dunn et al, Obstet Gynecol 1989**


Medial condyle of the tibia
SP-9
Junction of the shaft and medial condyle of the tibia
Gastrocnemius

SP-9 A British prospective, randomised, controlled, assessor-blinded trial ($n = 44$) investigated the influence of **SP-9**, **SP-10**, **ST-34**, **ST-36** and **L.I.-4** on unilateral versus bilateral acupuncture in patients with **advanced osteoarthritis of the knee**. The symptoms improved significantly in both groups. This improvement was sustained for six months. There was no statistically significant difference between the groups. **Tillu et al, Acupunct Med 2001**



SP-10 → SP-9; ST-36; Ren-17

A Chinese prospective, randomised, controlled trial ($n = 62$) investigated the effect of Q-wave millimetre microwave application at **SP-10** and **BL-17** on **chemotherapy-induced leukopenia in gastrointestinal cancer patients**. One group received irradiation before the start of chemotherapy, the other group only after the onset of the chemotherapy-induced leukopenia. Beginning the irradiation before starting chemotherapy produced a significantly better result (86% versus 73% with later application). **Wu et al, Zhongguo Zhong Xi Yi Jie He za Zhi 1997**

SP-12 → Du-4

Heart channel

HE-3 → P-6
HE-5 → P-6



HE-7 → G.B.-26; Du-4; Du-20; S.I.-3; P-6

A German prospective, randomised, placebo-controlled, single-blinded trial ($n = 36$) investigated the effect of **H-7**, **P-6**, **Du-20**, **BL-62** and **Ex-HN-6** ***erjian*** on the cardiac autonomous nervous system in patients with **minor depression and anxiety disorders**. Only the acupuncture group demonstrated a relative increase of cardiovagal modulation of heart rate. **Agelink et al, Fortschr Neurol Psychiatr 2003**

A British pilot study ($n = 17$) investigated the effect of **HE-7** on certain **stress parameters**. There was an average decrease of 44% (based on the Edinburgh Postnatal Depression Scale (EPDS). **Chan et al, Acupunct Med 2002**

HE-8 → LU-10
HE-9 → Du-4

Small Intestine channel



S.I.-3 → LU-10; Du-12

A larger-scale Taiwanese prospective, controlled, randomised trial ($n = 100$) demonstrated a significant improvement of neurological functioning in patients with **severe spinal cord injuries** (ASIA status A and B) after electro-acupuncture at **S.I.-3** and **BL-62** plus auricular acupuncture versus the control group (conventional and rehabilitation therapy only). **Wong et al, Am J Phys Med Rehabil 2003**

A non-controlled pilot study ($n = 18$) found that the treatment of **acute torticollis** with a single treatment of ipsilateral acupuncture at **S.I.-3** and **M-UE-8** resulted in a mean improvement of lateral head rotation of 53%. **Samuels N, Am J Chin Med 2003**

A Chinese prospective, randomised, controlled trial ($n = 62$) investigated the effect of acupuncture at **S.I.-3** and **HE-7** in patients with **cerebral traumatic dementia** compared to conventional physiotherapy. There were significant changes of MMSE scores and auditory P300 values in the acupuncture group only. **Zhang et al, Zhen Ci Yan Jiu 1996** and **Zhang et al, Zhongguo Zhong Xi Yi Jie He Za Zhi 1995**



S.I.-18 A Chinese prospective, randomised, controlled, single-blinded trial ($n = 42$) investigated the effect of electro-acupuncture at **S.I.-18**, **Ex-HN-04**, **G.B.-20** and **L.I.-4** on controlled hypotension induced by isoflurane during a cerebral operation in order to avoid blood loss. The concentration of isoflurane necessary to achieve controlled hypotension was significantly reduced by 31–42% compared to the control group. **Wang et al, Zhongguo Zhong Xi Yi Jie He Za Zhi 2000**

Bladder channel



BL-1 → G.B.-14

A non-randomised group-comparison trial ($n = 34$) investigated the effect of warmed needle acupuncture at **BL-1** in patients suffering from **epiphora** due to dysfunction of the lacrimal duct. The effect in the treatment group was significantly better in comparison to the control group treated with lacrimal duct irrigation and norfloxacin eye drops (92% vs 54%). **Ni et al, J Tradit Chin Med 2002**

A Chinese case study reports the treatment of **epiphora** due to **insufficiency of lacrimal passage** with acupuncture at **BL-1**. Of the 68 eyes treated in 42 patients, 28 eyes were cured and 35 improved. 34 eyes improved after only one course of treatment. **Ni Y et al, J Tradit Chin Med 1999**



BL-7 A Chinese experimental trial carried out in 1988 was the first to discuss the possible effect of **BL-7**, **G.B.-6** and **Ex-HN-1** on **hemiplegia** through changes of the micro-circulation in the nail bed. **Shun et al, Zhen Ci Yan Jiu 1988**



BL-10 → ST-8

A placebo-controlled, non-blinded group-comparison trial ($n = 65$) investigated the effect of treating children with an acu-plaster at **BL-10**, **BL-11** and **G.B.-34** the night before undergoing **strabismus surgery,** for the prevention of **post-operative nausea and emesis**. Nausea and emesis were reduced by 50% during the early and later postoperative stage compared to the placebo-group. The well-researched point P-6 often failed to prevent nausea in this type of surgery. **Chu et al, Acta Anaesthesiol sin 1998**

BL-11 → Du-12; BL-10; L.I.-4; Ex-B-1

BL-12 → Ex-B-1

BL-13 → Ex-B-1; Du-14



BL-15 → Ex-B-1; P-6

In an animal experiment, moxibustion at **BL-27** was able to reduce the renal excretion of Na^+ while at the same time decreasing urinary volume. Systolic blood pressure remained unchanged while plasma levels of aldosterone and ANP (atrial natriuretic peptide) decreased. In contrast, moxibustion at BL-15 increased urinary volume while reducing excretion of Na^+ and decreasing systolic blood pressure. Plasma levels of aldosterone and ANP decreased. These results suggest that BL-15 and BL-27 might be applied for certain forms of **hypertension**. **Lee et al, Am J Chin Med 1997**

BL-17 → SP-10



BL-18 → BL-23

A Japanese prospective, randomised, placebo-controlled, double-blinded trial ($n = 189$) investigated the effect of Japanese intradermal acupuncture at **BL-18**, **BL-19**, **BL-20**, **BL-21**, **BL-22**, **BL-23**, **BL-24**, **BL-25** and **BL-26** on **analgesic requirement, nausea and emesis** as well as stress markers after **abdominal surgery**. Starting from the recovery room and including the second postoperative day incisional pain at rest and during coughing was significantly lower in the verum group than in the control group. The requirement for epidural morphine was also significantly lower (only 50%). Nausea and emesis were also significantly lower (20–30%). Plasma cortisol and epinephrine concentrations were reduced by 30–50% in the acupuncture group during recovery and on the first postoperative day. This is one of the most valuable trials due to its excellent methodology and design. **Kotani et al, Anesthesiology 2001**

BL-19 → BL-18

BL-20 → L.I.-4; Du-1; BL-18; Du-14; P-6

BL-21 → BL-18

BL-22 → BL-18; Ex-B-2

BL-23 → L.I.-4; Du-4; Du-20; BL-18; Du-14

BL-24 → L.I.-4; BL-18

BL-25 → L.I.-4; BL-18; Ex-B-2

BL-26 → L.I.-4; BL-18



BL-27 → L.I.-4; BL-15

A German randomised, placebo-controlled experimental trial ($n = 42$) compared the effect of acupuncture at **BL-27** on pain reduction with a point of the Yamamoto New Scalp Acupuncture (YNSA). Experimental pain stimuli were set on the **upper calcaneus edge**. The difference in pain reduction between the acupuncture group and the scalp acupuncture group was highly significant. There are also highly significant differences concerning the verum and the placebo treatment. BL-27 could therefore be a useful point for treating calcaneal pain. **Ogal et al, Anasthesiol Intensivmed Notfallmed Schmerzther 2002**

An animal experiment in 15 healthy dogs investigated the effect of acupuncture on intestinal (duodenum) motility. Electro-acupuncture at BL-27 decreased the frequency of intestinal motility by 31% during stimulation, while showing an increase of 18% after stimulation. Electro-stimulation of ST-36 led to the opposite result: a 20% increase during stimulation followed by a decrease of 7% after stimulation. Based on this result, BL-27 could be applied for **paralytic ileus** or **constipation** while ST-36 could be used for treating **bloating, tenesmus and diarrhoea**. **Choi et al, J Vet Sci 2001**

BL-28 → L.I.-4; Du-4



BL-29 There exists only a small case study describing **various disorders**. This is of educational value rather than anything else. **Chen Y., J Tradit Chin Med 2002**


Sacral foramina
1
2
3
4
BL-31
BL-32
BL-33
BL-34

BL-32 → Du-4; Ren-3
A medium-scale Chinese case study ($n = 30$) reports the successful treatment of **urinary and faecal incontinence** due to nerve damage with electro-acupuncture at **BL-35** and **BL-32**. **Yang et al, J Tradit Chin Med 2003**


Sacral foramina
1
2
3
4
BL-31
BL-32
BL-33
BL-34

BL-33 A Japanese case study ($n = 10$) documents a significant reduction of pain for **chronic pelvic pain syndrome** with **intrapelvic venous congestion** by weekly treatments with bilateral acupuncture at **BL-33** (needle retention 10 minutes, manual rotation). **Honjo et al, Int J Urol 2004**
A Japanese prospective case study ($n = 13$) investigated the effect of bilateral acupuncture at **BL-33** on cystometry and **incontinence** in **spinal-cord-injured patients**. Incontinence completely disappeared in 15% of cases and decreased to 50% or less compared to baseline in a further 46% of patients. Maximum cystometric bladder capacity increased significantly from 75 ml to 148 ml. When cystometry was repeated in six patients one month after the last acupuncture treatment, bladder capacity showed a further average increase to 187 ml. **Honjo et al, Urol Int 2000**


Anus
0.5 cun
Level of the tip
of the coccyx
Coccyx
BL-35

BL-35 → BL-29; BL-32
A larger-scale Chinese case study ($n = 103$) reports the successful treatment of **post-partum urinary retention** with classic acupuncture at **BL-35**. **Li et al, J Tradit Chin Med 1996**
BL-47 → L.I.-4


Sacral
foramina
BL-54
Midline

BL-54 → Du-3
A larger-scale Chinese case study ($n = 100$) reports the successful treatment of **lumbar pain** with acupuncture at **BL-54**. **Cui, J Tradit Chin Med 1992**


BL-59
Highest prominence
of the lateral malleolus
3 cun
Anterior border
of the Achilles
tendon

BL-59 A smaller-scale Chinese case study reports the treatment of **acute lumbar pain** with acupuncture at **BL-59**. **Hu, J Tradit Chin Med 1993**



BL-60 → Du-3; ST-36; L.I.-4
A US prospective case study ($n = 7$) reports the positive subjective (questionnaire) and objective (tibial H-reflex) effect of non-invasive electro-acupuncture at **BL-60**, **ST-36**, **KID-1** and **LIV-3** on **HIV-related neuropathy**. Results showed a significant overall improvement in functional activities. **Galantino et al, J Altern Complement Med 1999**
BL-62 → S.I.-3; HE-7; Du-20



BL-64 An animal experiment demonstrated that electro-acupuncture at BL-64 and BL-65 increased the activity of nitric oxide synthase in the brain stem nuclei (nucleus gracilis). **Ma at al, Acupunct Electrother Res 2002**
BL-65 → BL-64



BL-66 An experimental study in rats investigated the antipyretic effect of manual acupuncture at **BL-66** on lipopolysaccharide-induced **fever**. Acupuncture at this point reduced the fever and also reduced the production of the pro-inflammatory cytokines interleukin-1 beta and interleukin-6 in the hypothalamus of the treated rats. **Son et al, Neurosci Lett 2002**



BL-67 An Italian prospective, randomised, controlled, single-blinded trial (*n* = 123) investigated the effect of moxibustion at **BL-67** on the conversion rate in **breech presentations**. The trial had to be terminated prematurely due to a high drop-out rate of participants. At that time, there were no significant differences between the moxibustion group and the control group. The authors conclude that there is too little acceptance for moxibustion treatment in non-Asian cultures. **Cardini et al, Br J Obstet Gynaecol 2005**

A randomised, controlled, prospective larger-scale trial (*n* = 67) demonstrated a higher rate of conversion of fetal **breech presentations** in a group treated with 30 minutes of manual acupuncture at **BL-67** (76.4%) compared to an untreated control group (45.4%). **Habek et al, Fetal Diagn Ther 2003**

A large-scale (*n* = 260), randomised, controlled, prospective trial demonstrated a higher rate of conversion of fetal **breech presentations** in women treated with moxibustion at **BL-67** for 7–14 days (75.4%) than the conventionally treated control group (47.7%). **Cardini et al, JAMA 1998**

A medium-scale case study (*n* = 48) with retrospective control groups demonstrated that electro-acupuncture at **BL-67** for the conversion of fetal **breech presentations** had a 81.3% success rate. **Li et al, J Tradit Chin Med 1996**

Acupuncture at **BL-67** resulted in a significant increase in the number of **c-Fos-positive cells in the primary visual cortex** of binocularly deprived rat pups to levels suggesting that BL-67 has an influence on the activity of the primary visual cortex. **Lee et al, Am J Chin Med 2002**

A recent Italian prospective, randomised trial investigated the effect of acupuncture and moxibustion at **BL-67** on the conversion of **breech presentations** in 240 pregnant women. At delivery, breech presentation was significantly lower in the active-treatment group (37%) than in the observation group (54%). Therefore the proportion of caesarean sections indicated for breech presentation was also significantly lower in the treatment group than in the observation group (52% vs 67%). **Neri et al, J Matern Neonatal Med 2004**

A Croatian prospective, randomised, controlled, non-blinded group-comparison trial (*n* = 67) assessed the value of acupuncture at **BL-67** for 30 minutes in the conversion of **breech presentation**. The success rate of the acupuncture correction of the breech presentation was 76% while the rate in the untreated control group was only 45%. This is a highly significant difference. **Habek et al, Fetal Diagn Ther 2003**

An Austrian prospective, randomised, placebo-controlled experimental trial (*n* = 10) investigated the effect of laser acupuncture at **BL-67** on the visual cortex using fMRI to monitor **neuroradiological changes**. Only verum acupuncture resulted in an activation in the cuneus (Brodmann Area BA 18) and the medial occipital gyrus (BA 19). These results confirm the traditional application of this point for ophthalmic disorders. **Siedentopf et al, Neurosci Lett 2002**

An Italian prospective, non-randomised, sham-controlled, single-blinded trial (*n* = 12 pregnant women with **breech presentation**) demonstrated that acupuncture at **BL-67** significantly reduced the fetal heart rate while increasing fetal movement and producing more accelerations. **Neri et al, J Soc Gynecol Invest 2002**

Kidney channel



KID-1 → BL-60

A Chinese prospective, randomised, controlled, non-blinded trial (*n* = 150) investigated the effect of acupuncture at **KID-1** in the treatment of **children with bronchial asthma** compared to a control group treated with conventional drugs. The clinical effectiveness of acupuncture at KID-1 was significantly higher than treatment with drugs (89% vs 64%). In addition, in the acupuncture group the level of eosinophils and IgE was highly significant and significantly lower respectively than in the control group. **Gao et Zhu, Zhongguo Zhong Xi Yi Jie He Za Zhi 2005**

A Chinese retrospective case study reports the successful local stimulation of **KID-1** by applying a paste in the treatment of **essential hypertension**. **Gong et al, J Tradit Chin Med 1995**



KID-3 → Du-4; L.I.-15

A Taiwanese prospective, randomised, controlled experimental trial (*n* = 157) compared the absorption of Tc-99 m (a radioactive technetium marker) at **KID-3** with non-acupuncture points. Absorption at KID-3 was significantly better than at non-acupuncture points. **Wu et al, Am J Chin Med 1994**

KID-4 → P-6
KID-5 → Du-4
KID-6 → ST-36

Pericardium channel



P-2 A Chinese experimental trial (*n* = 100) examined cardiac function before and during acupuncture at **P-2**, **P-3**, **P-4** and **P-6** as well as at control points (some arbitrary points and **G.B.-37**) in patients with **coronary heart disease**. In contrast to the control points the verum points had an effect – even if only a minor one – on the measured parameters (PEP, LVET, P/L, HI, SV, CO, ST segment and T wave of ECG). **You et al, Zhen Ci Yan Jiu 1993**
P-3 → P-2
P-4 → P-2



P-5 An earlier Chinese trial interpreted the synchronising effect of electro-acupuncture at **P-5** on EEG activity as having a **homeostatic effect on the whole body**. **Huang et al, Zhen Ci Yan Jiu 1990**
Electro-acupuncture at **P-5** improved the ST segment of ECG in rabbits with induced **acute myocardial infarction**. **Cao et al, Zhen Ci Yan Jiu 1990**
An earlier Chinese experimental trial (*n* = 10) found that electro-acupuncture at **P-5** and **P-6** shortened sino-atrial conduction in healthy subjects and increased frequency at the sinus node (**positive chronotropic and bathmotropic effect**). **Xi et al, Zhongguo Zhong Xi Yi Jie He Za Zhi 1993**
Previous work of the team led by Li and Tjen-A-Looi suggests that the inhibitory effect of electro-acupuncture (EA) on the pressor reflex induced by bradykinin (BK) applied to the gallbladder is in part due to the activation of opioid receptors most likely located in the rostral ventrolateral medulla (rVLM). This trial investigated the specific opioid receptor subtypes and neurotransmitters responsible for this inhibition. Therefore BK was applied to the gallbladder of anaesthetised cats to induce an increase of arterial blood pressure. It was found that applying EA at P-5 and P-6 activated the mu and delta opioid receptors located in the rVLM, thus preventing a rise of the arterial blood pressure for a longer period of time through the activating influence of the splanchnic nerve (for example due to stretching of the gallbladder or stomach). This experiment substantiated the positive effect of EA at P-5 and P-6, especially for myocardial ischaemia due to **coronary heart disease**. **Li et al, Auton Neurosci 2001; Li et al, Am J Physiol Regul Integr Comp Physiol 2002; Tjen-A-Looi et al, Auton Neurosci 2003**
In a US study 17 healthy subjects were subjected to weekly bicycle training for 3–4 weeks. Subjects were asked to perform the training with and without electro-acupuncture (EA) at **P-5**, **P-6**, **L.I.-4**, **L.I.-5**, **L.I.-6**, **L.I.-7**, **G.B.-37**, **G.B.-38** and **G.B.-39**. In 70% of subjects, EA at points on the Pericardium and Large Intestine channels led to an increase in maximal workload with decreased blood pressure. Points on the Gall Bladder channel had no effect. Further trials may investigate the application of these points in the treatment of hypertension induced by exercise stress. **Li et al, Clin Auton Res 2004**



P-6 → P-2; P-5; Du-20; Du-14; HE-7; LIV-3; L.I.-4; ST-36
A Taiwanese prospective, randomised, placebo-controlled, double-blinded trial (*n* = 110) investigated the effect of acupressure bands at **P-6** on **nausea and vomiting during spinal anaesthesia for caesarean delivery**. The reduction and occurrence of nausea (64% vs 71%) and vomiting (22% vs 27%) was not significant. **Ho et al, Anesth Analg 2006**
A US prospective, randomised, placebo-controlled, single-blinded trial (*n* = 94) investigated the effect of acupressure bands at **P-6** on the occurrence of **nausea and vomiting during caesarean delivery under spinal anaesthesia**. There was no statistically significant difference between the active and sham control groups in the incidence of intraoperative nausea (30% vs 43%), postoperative nausea (23% vs 41%), intraoperative vomiting (13% vs 9%), postoperative vomiting (26% vs 34%), intraoperative antiemetic requirement (23% vs 18%), postoperative antiemetic requirement (34% vs 39%), complete intraoperative response (55% vs 57%) or complete postoperative response (51% vs 34%). These results did not reach the selected level of significance. There were also no significant differences between the groups in nausea scores, number of vomiting episodes and patient satisfaction. **Habib et al, Anesth. Analg 2006**
A Swedish prospective, randomised placebo-controlled experimental double-blinded trial (*n* = 60) investigated the effect of acupressure at **P-6** on **nausea induced by eccentric rotation**. Mean time to nausea was significantly the longest in the P-6 group (352 seconds), compared to the placebo-acupressure group (280 seconds) and the untreated control group (151 seconds). **Alkaissi et al, Can J Anaesth 2005.**
A Turkish prospective randomised controlled non-blinded trial (*n* = 90) investigated the effect of transcutaneous electrical acupoint stimulation (TEAS) at **P-6** and **Ren-13** compared to ondansetron on **postoperative nausea following paediatric**

tonsillectomy. There was the same incidence of nausea episodes in the TEAS group and in the ondansetron group, but significantly fewer episodes than in the untreated control group. Side-effects were significantly higher in the ondansetron group. **Kabalak et al, J Altern Complement Med 2005**

An Indian prospective, randomised, placebo-controlled, double-blinded trial (*n* = 120) investigated the effect of capsicum-plasters on **P-6** on **postoperative nausea and vomiting** (PONV) compared to conventional treatment with ondansetron. For the duration of the plaster application (6 hours after the operation) the incidence of PONV and the requirement for antiemetics were significantly lower in both groups. **Misra et al, Can J Anaesth 2005**

A Turkish prospective, randomised, placebo-controlled, single-blinded trial (*n* = 127) investigated the effect of transcutaneous electric nerve stimulation (TENS) at **P-6** on the incidence and severity of **nausea and gagging during gastroscopies**. There were no significant differences between the treatment group and placebo group. **Tarcin et al, Turk J Gastroenterol 2004**

A Chinese prospective, non-blinded, randomised, group-comparison trial (*n* = 30) investigated the effect of acupuncture at **P-6** plus mexiletin on **intermittent ventricular extrasystole**. The treatment group had a total effective rate of 90% compared with the control group, who was administered mexiletin only (80% total effective rate). Only the acupuncture group showed no increase in extrasystole. **Zhang et al, J Tradit Chin Med 2004.**

A Chinese group-comparison trial investigated the effect of acupuncture at **P-6** in the treatment of patients with angina pectoris and **acute myocardial infarct**. The effectiveness of acupuncture was significantly better (91%) than conventional treatment with isosorbide dinitrate and nifedipine. **Meng et al, J Tradit Chin Med 2004**

A US prospective, controlled, group-comparison trial (*n* = 77) investigated the effect of stimulation at **P-6** on the symptoms of **motion sickness** during exposure to optokinetic drum rotation. Despite the extreme test conditions, stimulating P-6 delayed the onset of symptoms considerably. **Miller et al, Aviat Space Environ Med 2004**

A Croatian prospective, single-blinded group-comparison trial (*n* = 36) investigated the efficiency of acupuncture at **P-6** in the treatment of **hyperemesis gravidarum**. Treatment results were measured by the requirement for anti-emetic medication. Acupuncture at P-6 had an efficiency rate of 90%, acupressure at P-6 64%, placebo acupuncture 12.5% and placebo acupressure 0%. **Habek et al, Forsch Komplementarmed Klass Naturheilkd 2004**

In a German prospective, randomised, placebo-controlled double-blinded group-comparison trial acupuncture at **P-6** significantly reduced the incidence of **emesis after gynaecological and breast surgery** (40% placebo, 25% P-6). Postoperative emesis was only reduced for gynaecological surgery, not for breast surgery. **Streitberger et al, Anaesthesia 2004**

A Chinese prospective, randomised, single-blinded, placebo-controlled group-comparison trial (*n* = 41) investigated the effect of twice daily acupressure at **P-6**, **ST-36** and **SP-6** on **gastrointestinal motility following trans-abdominal hysterectomy**. In comparison to the control group receiving acupressure on sham points, gastrointestinal motility (measured with a multifunctional stethoscope) increased significantly in the acupressure group. **Chen et al, Am J Chin Med 2003**

A German prospective, randomised, placebo-controlled, single-blinded trial (*n* = 80) investigated the anti-emetic effect of acupuncture at **P-6** in addition to administration of ondansetron in patients with **chemotherapy-related nausea**. There was no significant difference between the treatment and control group. **Streitberger et al, Clin Cancer Res 2003**

A US prospective, randomised, placebo-controlled, double-blinded trial (*n* = 230) investigated the effect of TENS at **P-6** for the relief of **nausea and vomiting in pregnancy**. Based on the Rhodes Index, results in the verum group were significantly better than in the control group. **Rosen et al, Obstet Gynecol 2003**

A British prospective, partially randomised, partially blinded, placebo-controlled trial (*n* = 301 patients with **acute myocardial infarction**, 125 of whom acted as a non-randomised control group) compared the effect of wristband-acupressure at **P-6** with placebo-acupressure. P-6 led to a significant reduction in **nausea and vomiting** during the last 20 hours of the 24-hour study phase (18%), compared with the placebo group (32%) and the control group (43%). **Dent et al, Complement Ther Med 2003**

A Swedish prospective case study (*n* = 39) investigated the effect of **P-6** combined with ondansetron for **nausea and vomiting** associated with **cyclophosphamide chemotherapy**. The authors stated that, compared with ondansetron treatment alone, the combined acupuncture-ondansetron treatment was significantly more effective, but they do not mention a control group. **Josefson et al, Rheumatology (Oxford) 2003**

In a US prospective, randomised, single-blinded trial (*n* = 53) the application of 'minute sphere' acupressure at **P-6**, **ST-36**, **SP-6** and **SP-4** showed no decrease of **postoperative pain and morphine requirement after abdominal surgery**. **Sakurai et al**, **Anesth Analg 2003**

A Swedish prospective, randomised, placebo-controlled, double-blinded, multi-centre trial (*n* = 410) investigated the effect of **P-6** for the treatment of **postoperative nausea and vomiting after gynaecological surgery**. The incidence of nausea and vomiting was significantly lower in the acupuncture group (33%) than in the control group (46%). **Alkaissi et al, Can J Anaesth 2002**

A US prospective, randomised, placebo- and sham-controlled, double-blinded trial (*n* = 120) investigated the effect of the prophylactic application of a 'ReliefBand' at **P-6** on the incidence of **nausea and vomiting after plastic surgery,** compared to the application of the ReliefBand in addition to 4 mg ondansetron. The occurrence of nausea and vomiting as well as the need for antiemetic 'rescue' medication was significantly the lowest in the P-6 plus ondansetron group. **White et al, Anesthesiology 2002**

A Korean prospective, randomised, placebo-controlled, double-blinded trial (*n* = 160) investigated among other parameters the effect of a capsicum plaster applied at **P-6** on **postoperative nausea and vomiting**. The incidence of nausea and vomiting was significantly less (P-6: 26% within 24 hours, placebo: 57%). **Kim et al, Anesth Analg 2002**

A Japanese case study investigated the effect of different stimulation techniques at **P-6** on the coronary arteries in patients with **coronary heart disease**. The mean coronary dilation with acupuncture was 69% of that caused by isosorbide dinitrate. **Kurono et al, Am J Chin Med 2002**

A US prospective, randomised, sham-controlled, single-blinded trial ($n = 187$) investigated the effect of **P-6** on the incidence of **postoperative nausea and vomiting** in children. P-6 produced significantly better results than the sham points and was equally effective as administration of droperidol, but without the sedative, hypotensive side effects. **Wang et al, Anesthesiology 2002**

A US prospective, randomised, sham-controlled, single-blinded trial ($n = 27$) investigated the effect of **P-6** on the incidence of **nausea and vomiting during chemotherapy**. Compared to the control group, the anti-emetic requirement was significantly lower in the P-6 group. **Roscoe et al, Altern Ther Health Med 2002**

An Austrian prospective, randomised, placebo-controlled, experimental cross-over study ($n = 51$) investigated the effect of acupuncture at **P-6** on the **skin blood perfusion** measured by laser Doppler perfusion imaging. This was compared to needling a sham point. Changes in the skin blood perfusion occurred significantly earlier in the acupuncture group than in the sham group, with a basically more pronounced reduction in skin blood perfusion at the verum point. **Litscher et al, Lasers Med Sci 2002**

A large-scale Australian prospective, randomised, sham-controlled trial ($n = 593$) investigated the effect of acupuncture at **P-6** on the incidence **of nausea and vomiting in early pregnancy**. Women receiving traditional acupuncture reported significantly less nausea after the second treatment and significantly less dry retching after the third week compared with women in the control group. Women treated with sham acupuncture showed significantly less nausea and retching after the third treatment compared with untreated women. Individualised acupuncture resulted in significantly less nausea and retching already after the first treatment. In this study none of the treatments had a significant influence on the frequency of vomiting. **Smith et al, Birth 2002**

A US prospective, randomised, sham-controlled trial ($n = 120$) investigated the influence of electro-acupuncture (EA) at **P-6** on postoperative **nausea and vomiting** in paediatric patients who had undergone **ENT surgery** and were awake. EA at P-6 significantly decreased the incidence of nausea (P-6: 60%, sham: 85%, control group: 93%). While vomiting had the lowest incidence in the P-6 group, the difference from the other groups was not significant. **Rusy et al, Anesthesiology 2002**

A Swedish prospective, randomised, placebo-controlled pilot study ($n = 60$) investigated the effect of tuina (acupressure) at **P-6** on **pregnancy-related nausea and vomiting**. The frequency of both nausea and vomiting was significantly lower in the acupressure group compared to the sham acupressure group and untreated control group. **Werntoft et al, J Reprod Med 2001**

A US prospective, randomised, controlled trial ($n = 25$) investigated the effect of an acupressure wrist band at **P-6** on **motion sickness**. Both the symptoms of motion sickness and abnormal gastric activity as recorded via EEG were significantly lower in the group treated with wristbands at P-6. **Stern et al, Altern Ther Health Med 2001**

A US prospective, randomised, placebo-controlled, single-blinded trial investigated the effect of ‘sea-bands’ (acupressure wristbands) at **P-6** on the incidence of **postoperative nausea and vomiting**. There were no significant differences. **Windle et al, J Perianesth Nurs 2001**

A Swedish prospective, randomised, sham-controlled, single-blinded cross-over study ($n = 33$) investigated the effect of acupuncture at **P-6** on pregnant women with **hyperemesis gravidarum** (vomiting in pregnancy). The verum group showed a significantly faster reduction of the nausea, and also a higher number of the patients experienced no vomiting. **Carlsson et al, J Pain Symptom Manage 2000**

A Chinese prospective, controlled, randomised, group-comparison study ($n = 181$) and a Chinese case study ($n = 33$) demonstrated that electro-acupuncture at **P-6** and **P-8** as well as at **L.I.-4**, **T.B.-5**, **ST-36** and **SP-6** with de-escalating treatment frequency from four times daily to once weekly for a period of 15 and 28 days had a significant effect on the **withdrawal symptoms of heroin addicts**. **Zhang et al, Zhongguo Zhong Xi Yi Jie He Za Zhi 2000; Wu et al, Zhongguo Zhong Xi Yi Jie He Za Zhi 2000**

A Taiwanese prospective, non-randomised, placebo-controlled, single-blinded experimental cross-over study ($n = 44$) investigated the effect of acupuncture at **P-6** on the left ventricular ejection fraction (LVEF) in 22 healthy subjects and 22 patients with **coronary artery disease** (CAD). There was no change of LVEF in the healthy subjects while LVEF significantly increased in the CAD patients. **Ho et al, Am J Chin Med 1999**

A US prospective, randomised, placebo-controlled, single-blinded trial ($n = 100$) investigated the effect of pre-operative acupressure (verum group) and intra-operative acupuncture (verum and control group) at **P-6** on **postoperative nausea and vomiting** after **tonsillectomy** in children. There were no significant differences. **Shenkman et al, Anesthesiology 1999**

A Swedish prospective, randomised, placebo-controlled, double-blinded trial ($n = 60$) investigated the effect of acupressure at **P-6** on **nausea and vomiting** after **minor gynaecological surgery**. Only the group receiving acupressure at P-6 experienced no vomiting and also required no anti-emetic medication. **Alkaissi et al, Acta Anaesthesiol Scand 1999**

An Austrian prospective, randomised, placebo-controlled, double-blinded trial investigated the effect of laser acupuncture at **P-6** on **nausea and vomiting in children undergoing strabismus surgery**. The laser acupuncture was administered 15 minutes before induction of anaesthesia and 15 min after arriving in the recovery room. In the laser stimulation group, the incidence of vomiting was significantly lower (25%) than that in the placebo group (85%). **Schlager et al, Br J Anaesth 1998**

A Chinese prospective, randomised, placebo-controlled, double-blinded trial ($n = 163$) investigated the effect of acupoint stickers at **P-6**, **Ren-8** and **T.B.-18** on **motion sickness**. All tested acupuncture points showed a significantly better result than the active control points (scopolamine plaster) and the placebo control (lactose plaster). T.B.-18 was the most effective point (symptoms 100% reduced), followed by Ren-8 (81%) and P-6 (46%). **Pei et al, Zhongguo Zhong Xi Yi Jie He Za Zhi 1998**

A Chinese prospective, randomised, controlled trial ($n = 50$) compared two forms of anaesthesia for the **anterior approach cervical discectomy**: local anaesthesia plus intravenous anaesthesia (IVA) in the control group and electro-acupuncture at **P-6** and **L.I.-4** plus IVA. The effect of the anaesthesia was the same in both groups. The authors therefore recommend electro-acupuncture at P-6 and L.I.-4 as a less risky alternative. **Li et al, Zhongguo Zhong Xi Yi Jie He Za Zhi 1997**

A British prospective, randomised, placebo-controlled, double-blinded trial ($n = 81$) investigated the effect of intra-operative acupuncture at **P-6** in the prevention of **postoperative nausea and vomiting** in patients undergoing **gynaecological laparoscopic surgery**. The use of acupuncture significantly reduced the incidence of postoperative nausea and vomiting by 30–38% compared with placebo. **Al-Sadi et al, Anaesthesia 1997**

A US prospective, randomised, placebo- and sham-controlled, double-blinded trial ($n = 75$) investigated the effect of acupressure at **P-6** on **nausea and vomiting during caesarean section under spinal anaesthesia** compared with administration of 10 mg metoclopramide. Acupressure at P-6 is as effective as 10 mg metoclopramide. **Stein et al, Anesth Analg 1997**

An Australian prospective, randomised, placebo-controlled, double-blinded trial ($n = 84$) investigated the effect of TENS at **P-6** and **L.I.-4** on **postoperative nausea and vomiting** in **paediatric patients** undergoing **minor urological surgery**. The differences between the treatment and control group were not statistically significant. **Schwager et al, Anaesth Intensive Care 1996**

A Taiwanese prospective, randomised, sham-controlled, single-blinded experimental trial ($n = 48$) evaluated the relationship between electro-acupuncture at **P-6** and **ST-36** and cardiopulmonary function in healthy subjects. In the P-6/ST-36 group **resting heart rate**, **carbon dioxide production** and **oxygen requirement** were significantly decreased, indicating that acupuncture can lower the metabolic rate. **Lin et al, Chin Med J (Engl) 1996**

A Taiwanese prospective, randomised, placebo-controlled, double-blinded trial ($n = 60$) investigated the effect of acupressure wristbands at **P-6** on the incidence of **nausea and vomiting after epidural morphine for post-caesarean section pain relief**. Compared to the control group, the incidence of nausea significantly decreased from 43% to 3%, vomiting significantly decreased from 27% to 0%. **Ho et al, Acta Anaesthesiol Scand 1996**

A US prospective, randomised, placebo-controlled, single-blinded cross-over study ($n = 9$) investigated the effect of acupressure wristbands at **P-6** on nausea and vomiting for **seasickness**. Depending on the time of application (earlier or later during the trip) subjects were either symptom-free or complained about nausea and vomiting. The difference was highly significant. **Bertolucci et al, Aviat Space Environ Med 1995**

A US prospective, randomised, placebo- and sham-controlled, single-blinded experimental trial ($n = 9$) investigated the effect of acupressure at **P-6** on the incidence of visually-induced **motion sickness**. Acupressure at P-6 significantly reduced the incidence of nausea and abnormal gastric myoelectric activity. **Hu et al, Aviat Space Environ Med 1995**

A Chinese prospective, randomised, controlled trial ($n = 40$) investigated the effect of acupuncture on **P-6**, **L.I.-4**, **ST-36** and **KID-4** on the regulation of cellular immune function in patients with **malignant tumours**. There was a highly significant increase of the CD3+ and CD4+ levels, an increase in the CD4+/CD8+ ratio, a higher endorphin level and a decreased level of soluble interleukin-2 receptor (SIL-2R). **Wu, Zhen Ci Yan Jiu 1995**

A British prospective, randomised, controlled trial ($n = 46$) investigated the effect of acupressure at **P-6** on **nausea and vomiting** following **laparoscopy** for **gynaecological surgery** and the requirement for anti-emetic therapy. There was a significant reduction in the requests for anti-emetic therapy in the P-6-acupuncture group. **Allen et al, Anaesth Intensive Care 1994**

A Chinese prospective paired trial ($n = 40$) investigated the effect of electro-acupuncture (EA) at **P-6** during different times of the day (*chen*-time: 7–9am, *xu*-time: 7–9pm) on left ventricular function (LVF) in patients with **coronary heart disease**. EA performed at *chen*-time improved LVF, while EA administered under the same conditions during *xu*-time led to an impairment of LVF. **Li et al, J Tradit Chin Med 1994**

A British prospective case study ($n = 27$) reports that wearing a special wrist band decreased **pregnancy-related nausea and vomiting** more than 50%. **Stainton et al, Health Care Women Int 1994**

A US prospective, randomised, sham-controlled, single-blinded trial ($n = 60$) investigated the effect of acupressure at **P-6** on **pregnancy-related nausea and vomiting**. There was a significant decrease of nausea in the P-6 acupressure group. The incidence of vomiting did not differ from the sham control group. **Belluomini et al, Obstet Gynecol 1994**

A German prospective, randomised, placebo-controlled, single-blinded trial ($n = 60$) investigated the effect of acupressure at **P-6** on **nausea** in patients undergoing **gynaecological operations of longer duration** (6–8 h). Nausea was reduced from 53% in the placebo group to 23% in the acupressure group. **Gieron et al, Anaesthesist 1993**

A Chinese prospective, randomised, placebo-controlled, single-blinded trial ($n = 15$) investigated the effect of acupuncture at **P-6**, **HE-7** and **HE-3** on the frequency and duration of **angina pectoris** during exercise. The control groups received either sham acupuncture or no treatment at all. In the verum group, the anginal attack occurred significantly later and the duration of the attack after stopping the exercise was significantly shorter than in the control groups. **Zhou et al, Zhongguo Zhong Xi Yi Jie He Za Zhi 1993**

A Taiwanese prospective, randomised, controlled trial (*n* = 120) investigated the effect of **P-6** acupoint injection with 0.2 ml 50% glucose in water compared to intravenous injection of 20 micrograms/kg droperidol for the prevention of **vomiting after gynaecological laparoscopy**. A non-controlled comparison-group received no treatment at all. The incidence of vomiting significantly decreased in both the P-6 group and the droperidol group. **Yang et al, Acta Anaesthesiol Scand 1993**

An Italian prospective, randomised, placebo-controlled, double-blinded cross-over study (*n* = 60) investigated the effect of unilateral and bilateral acupressure at **P-6** for the treatment of **morning sickness** compared to acupressure at a sham point. Compared to the placebo group both unilateral and bilateral acupressure at P-6 significantly reduced the frequency of morning sickness from 60% to 30%. **De Aloysio et al, Obstet Gynecol 1992**

A US 'n of 1' trial investigated the effect of **P-6** wristbands on **nausea and vomiting in hospice patients** (*n* = 6). There were no significant differences between the verum group, the placebo group and the group without wristbands. **Brown et al, Am J Hosp Palliat Care 1992**

A Canadian prospective, randomised, controlled, double-blinded trial (*n* = 90) investigated the effect of acupuncture at **P-6**, administered after induction of anaesthesia, on the frequency of **nausea and vomiting after strabismus surgery in children**. The control group received droperidol. There was no significant difference between the two groups. **Yentis et al, Can J Anaesth 1992**

A Canadian prospective, randomised, controlled, single-blinded trial (*n* = 45) investigated the effect of acupuncture at **P-6** administered after induction of anaesthesia on the frequency of **nausea and vomiting after tonsillectomy in children**. There was no significant difference between the verum group and the untreated control group. **Yentis et al, Br J Anaesth 1991**

A US prospective, randomised, controlled, double-blinded trial (*n* = 66) investigated the effect of acupuncture at **P-6** administered after induction of anaesthesia on the frequency of **nausea and vomiting after strabismus surgery in children**. There was no significant difference between the treatment group and placebo group. **Lewis et al, Br J Anaesth 1991**

An Irish case study (*n* = 100) reports that TENS at **P-6** reduced **chemotherapy-induced nausea** by 75%. **Dundee et al, J R Soc Med 1991**

A Swedish prospective, randomised, controlled cross-over study (*n* = 21) investigated the effect of acupuncture at **P-6**, **HE-5**, **BL-15**, **BL-20** and **ST-36** on the frequency of **angina pectoris** (AP) and the performance before onset of pain during exercise in patients suffering from coronary heart disease. The frequency of AP attacks decreased significantly from 11 to 6 attacks per week. Accordingly, the performance before onset of pain during exercise increased significantly from 82 W to 94 W. **Richter et al, Eur Heart J 1991**

A Chinese prospective, randomised, non-blinded, controlled trial (*n* = 64) investigated the effect of a 3 ml normal saline injection into **P-6** on the incidence of **postoperative vomiting**. Compared to the control group, vomiting was significantly reduced (2 vs 10 patients) in the treatment group. **Shyr et al, Ma Zui Xue Za Zhi 1990**

A British prospective, randomised, controlled experimental trial (*n* = 18) compared the effectiveness of acupressure bands at **P-6** on **motion sickness** to a placebo and 0.6 mg scopolamine. Only the subjects taking scopolamine showed a significant increase in tolerance to a laboratory nauseogenic cross-coupled motion challenge. **Bruce et al, Aviat Space Environ Med 1990**

A Taiwanese prospective, randomised, controlled trial (*n* = 100) compared the effect of electro-acupuncture (EA) and TENS at **P-6** on **nausea and vomiting after laparoscopy**. Compared to the control group (44%), nausea was significantly reduced in the EA and perchlorperazine group (12% each), but not in the TENS group (36%). **Ho et al, Anaesthesia 1990**

A British prospective, randomised, controlled trial (*n* = 162) compared the effect of acupressure wristbands at **P-6** on **postoperative nausea and vomiting** in the recovery room with conventional anti-emetic treatment. Acupressure at P-6 significantly reduced the intensity of the nausea. The reduced anti-emetic requirement and the reduced incidence of vomiting were not statistically significant. **Barsoum et al, J R Soc Med 1990**

A Chinese prospective, randomised, controlled trial (*n* = 40) compared the effect of electro-acupuncture (EA) at **L.I.-4** and **P-6** on intra-operative **analgesia** in patients undergoing **thyroidectomy** with superficial cervical plexus block. There was no significant difference between the two groups. **Ouyang et al, Zhen Ci Yan Jiu 1990**

An Irish prospective, randomised, sham-controlled, single-blinded trial investigated the effect of pre-operative electro-acupuncture and acupuncture at **P-6** on the frequency of **nausea and vomiting after minor gynaecological surgery** compared to sham acupuncture. The frequency of nausea and vomiting was significantly reduced in the P-6-group only. **Dundee et al, Br J Anaesth 1989**

A US prospective, randomised, controlled cross-over study (*n* = 16) investigated the efficacy of acupressure wristbands at **P-6** on **morning sickness**. Use of the acupressure wristbands significantly relieved morning sickness and also significantly reduced anxiety, depression and behavioural dysfunction. **Hyde, J Nurse Midwifery 1989**

An Irish prospective, randomised, sham-controlled cross-over study (*n* = 10) investigated the effect of electro-acupuncture on **P-6** on **chemotherapy-induced nausea**. In the verum group sickness was either completely absent or reduced considerably in 97% of patients and no side effects were encountered. The same research team confirmed these results in a larger-scale case study (*n* = 105). **Dundee et al, J R Soc Med 1988**

An Irish prospective, randomised, sham-controlled trial (*n* = 350) compared the effect of acupressure at P-6 on **morning sickness** to sham acupressure and a control group. Only acupressure at P-6 significantly relieved the symptoms of morning sickness. **Dundee et al, J R Soc Med 1988**

A prospective, randomised, placebo-controlled trial ($n = 75$) investigated the effect of acupuncture at **P-6** on **nausea and vomiting after minor gynaecological surgery**. Acupuncture at P-6 significantly reduced both nausea and vomiting. **Dundee et al, Br Med J (Clin Res Ed) 1986**

P-8 → P-6; LU-10



P-9 A larger-scale Chinese case study ($n = 100$) describes the positive effect of **P-9** on **infantile morbid night crying** in otherwise healthy children. **Zhao, J Tradit Chin Med 2002**

Triple Burner channel

T.B.-5 → P-6; L.I.-4; L.I.-12; L.I.-10



T.B.-8 Acupuncture at **T.B.-8** and **Du-15** activates areas important for **word generation** in the right inferior frontal gyrus, but not in the left inferior frontal gyrus. **Li et al, Hum Brain Mapp 2003**

A Russian case study reports the positive effects of acupuncture at **T.B.-8**, **T.B.-9**, **ST-20**, **ST-36**, **G.B.-14** and **Du-20** in 66 patients with **duodenal ulcer** accompanied by apparent shifts in psychovegetative correlations. **Kravtsova et al, Vopr Kurortol Fizioter Lech Fiz Kult 1994**

T.B.-9 → T.B.-8

T.B.-18 → P-6

Gall Bladder channel



G.B.-1 An earlier Italian case study reports the successful application of **G.B.-1** for **heroin withdrawal** in nine male heroin addicts. After six months, 66% of these patients were classified as abstinent. Besides reservations regarding methodology of such a small-scale trial, the accompanying medication also poses problems in evaluating the effect of the acupuncture treatments. **Cocchi et al, Minerva Med 1979**



G.B.-3 A US prospective, randomised, double-blinded, experimental cross-over study ($n = 20$) investigated the effect of TENS at **G.B.-3** on the **anaesthetic requirement** (desflurane) to prevent purposeful movement of the extremities in response to noxious electrical stimulation. In comparison with the placebo group, bilateral application of TENS at G.B.-3 significantly reduced the desflurane requirement by 11%. **Greif et al, Anesthesiology 2002**



G.B.-4 Following the induction of an **ischaemic cerebral infarction** by occlusion of the middle cerebral artery in rats, animals treated with electro-acupuncture (EA) at **G.B.-4**, **G.B.-5**, **G.B.-6** and **G.B.-7** showed a significantly faster recovery than animals in the untreated control group or in the group treated with EA at **Du-20** and **Du-26**. Infarct volume was significantly reduced in the EA-treated groups. The authors discuss the acupuncture-induced production of vascular endothelial growth factor (VEGF) in astrocytes of the peri-infarct area as a causative factor. **Wang et al, Neurol Res 2003**



G.B.-5 → G.B.-4; ST-8

A Chinese case study recommends a particular needling technique (from **G.B.-5** or **Ex-HN-5** to **G.B.-8**) for the treatment of **migraine**. **Gan et al, J Tradit Chin Med 1986**

G.B.-6 → BL-7; G.B.-4



G.B.-7 → G.B.-4
A large-scale Chinese case study ($n = 500$) reports the successful application of acupuncture at **G.B.-7** in the treatment of **hemiplegia** after apoplexy. **Sun et al, J Tradit Chin Med 1985**

G.B.-8 → G.B.-5

G.B.-11 → ST-8



G.B.-14 → T.B.-8; ST-8; LIV-3
A case study reports that 63 patients with **facial paralysis** were treated with acupuncture at **G.B.-14**, **BL-1**, **ST-2**, **L.I.-20**, **ST-4**, **ST-6** and **ST-18** plus auxiliary points according to the underlying TCM pattern. Just over half of the patients were cured and all except one patient showed a marked improvement. **Liu et al, Zhen Ci Yan Jiu 1992**



G.B.-15 An uncontrolled, non-randomised, group-comparison trial investigated the effect of acupuncture on **childhood diarrhoea**. Group I received scalp acupuncture (after Yamamoto) with points on line 3 starting at **G.B.-15**; Group II received body acupuncture; and Group III was treated with antibiotics. Group I showed the best results, followed by Group II and Group III, with results in Group I and II significantly better than in Group III. However, besides some methodological shortcomings, the authors did not seem to have a very firm grasp of their subject matter: while using the correct points for the correct indication, they refer to line 3 as line 2 and to G.B.-15 as BL-15! **Lin et al, J Tradit Chin Med 1993**

G.B.-20 → ST-8; LIV-3; S.I.-18; L.I.-15



G.B.-21 → L.I.-15
A Chinese case study reports the successful treatment of **achalasia of the cardia** with acupuncture at **G.B.-21**. **Shi et al, J Tradit Chin Med 1994**

G.B.-24 → LIV-14



G.B.-26 An earlier prospective group-comparison trial investigated the **analgesic effect** of electro-acupuncture (EA) at **G.B.-26**, **ST-36**, **SP-6** and **HE-7** in patients who underwent hysterectomy by subumbilical midline incision. EA for 40 minutes had the same analgesic effect as 30 mg pentazocine. However, in contrast to pentazocine; EA also improved the vital capacity of the lung for 3–4 hours after the treatment. **Facco et al, Am J Chin Med 1981**

G.B.-30 → L.I.-12; L.I.-15



G.B.-31 → L.I.-4
Three publications by a Canadian research team led by Romita demonstrated that electro-acupuncture (EA) at **G.B.-31**, **ST-32** and **ST-36** resulted in a more pronounced inhibition of the **nociceptive tail withdrawal reflex** than classical acupuncture in slightly anaesthetised rats. **Romita et al, Brain Res 1997, Romita et al, Brain Res Bull 1997, Romita et al, Brain Res 1996**



G.B.-34 → BL-10; Du-20; ST-36; L.I.-4; L.I.-15
A Korean prospective randomised placebo-controlled experimental trial ($n = 10$) investigated the effect of acupuncture at **G.B.-34** on motor cortex activities as evidenced by **fMRI**. Bilateral sensorimotor areas BA 3, 4, 6 and 7 were activated during acupuncture, providing a basis for future investigations regarding therapeutic interventions in **stroke** patients. **Jeun et al, Am J Chin Med 2005**

A Chinese prospective, randomised, controlled trial ($n = 20$) investigated the effectiveness of electro-acupuncture (EA) at **G.B.-34** and **ST-38** on **epicondylitis lateralis (tennis elbow)** compared to manual acupuncture at the same points. After six treatments over a period of two weeks, the EA group showed significantly better results in relation to pain relief (Pain visual analogue scale) and pain free hand grip strength (PFG). **Tsui et al, Acupunct Electrother 2002**

A British, prospective, randomised, sham-controlled, double-blinded experimental trial ($n = 240$) investigated the effect of transcutaneous electric nerve stimulation (TENS) at **G.B.-34** on mechanical **pain thresholds**. Low frequency, high intensity stimulation showed a significant analgesic effect that was sustained post-stimulation. **Chesterton et al, Pain 2002**

G.B.-37 → P-2; P-5; L.I.-15

G.B.-38 → P-5

G.B.-39 → LIV-3

G.B.-40 → LIV-3



G.B.-43 An Austrian prospective, randomised, placebo-controlled, single-blinded trial investigated the effect of laser acupuncture at **G.B.-43** on cerebral cortical and subcortical activations as evidenced by **fMRI**. Only true laser acupuncture led to ipsilateral activations within the thalamus, nucleus subthalamicus, nucleus ruber, the brainstem, and the Brodmann areas 40 and 22. **Siedentopf et al, Laser Med Sci 2005**

A purely descriptive study investigated the effect of **G.B.-43** and **L.I.-4** on **somatosensory evoked potentials**. Particular attention was paid to the effect of the *deqi*-sensation. **Wu et al, Zhen Ci Yan Jiu 1993**

Liver channel

LIV-1 → SP-1



LIV-3 → Du-20; BL-60; L.I.-4; L.I.-15; SP-6

In a Chinese-German single-blinded experimental trial, acupuncture at **LIV-3** and **G.B.-40** resulted in the activation of the secondary somatosensory cortical areas, frontal areas, the right side of the thalamus and the left side of the cerebellum. Sham-points had no effect. **Fang et al, Neuroradiology 2004**

An Italian open, prospective, randomised group-comparison trial investigated the effect of acupuncture, laser acupuncture and TENS on **LIV-3**, **SP-6**, **L.I.-4**, **G.B.-20**, **Du-20** and **Ex-HN-5** on **transformed migraines**. The number of days with headache per month significantly decreased during treatment in all groups. Acupuncture showed the best effectiveness over time. **Allais et al, Neurol Sci 2003**

An Italian prospective, randomised, controlled, non-blinded trial ($n = 160$) investigated the effectiveness of acupuncture at **LIV-3**, **SP-6**, **ST-36**, **Ren-12**, **L.I.-4**, **P-6**, **G.B.-20**, **G.B.-14**, **Ex-HN-5** and **Du-20** on **migraine attacks** without aura compared to flunarizine. The number of attacks after two and four months of therapy was significantly lower in the acupuncture group than in the flunarizine group, and analgesic consumption was accordingly also significantly lower in the acupuncture group. Pain intensity was significantly reduced only by acupuncture treatment. **Allais et al, Headache 2002**

A British prospective, randomised, placebo-controlled cross-over study ($n = 56$) investigated the effect of **LIV-3** on **rheumatoid arthritis (RA)**. There were no significant changes between the treatment and placebo group. The treatment of only one point for a condition such as RA is unusual. **David et al, Rheumatology (Oxford) 1999**

A US prospective, randomised, sham-controlled, single-blinded trial ($n = 10$) investigated the effect of electro-acupuncture (EA) on **LIV-3**, **ST-36** and **L.I.-11** on lowering diastolic blood pressure in hypertensive subjects. Compared to the sham group, diastolic blood pressure showed a significant decrease in the EA-group. **Williams et al, Phys Ther 1991**

LIV-13 → Du-20



LIV-14 A Chinese prospective, non-randomised, controlled, non-blinded trial ($n = 56$ plus control group) investigated the effect of water injections at **LIV-14**, **G.B.-24** and **Ren-14** on biliary colic pain. The pain disappeared in 57% of cases and showed improvement in a further 39%. This result is significantly better compared to the control group receiving conventional treatment. **Jiang et al, J Tradit Chin Med 1995**

Du mai (governing vessel)



Du-1 A prospective, controlled, group-comparison trial in **hypogalactic postpartum sows** ($n = 42$) showed that apitherapy (acupuncture with bee venom) at **Du-1** and **ST-18** was superior to treatment with conventional drugs. **Choi et al, J Vet Sci 2001**

A prospective, controlled, group-comparison animal experiment showed that apitherapy at **Du-1** and **ST-25** in piglets with preweaning **diarrhoea** ($n = 91$) is as effective as conventional treatment with drugs. **Choi et al, Am J Chin Med 2003**

In an earlier prospective, controlled, group-comparison trial in piglets ($n = 44$) with induced **enteropathogenic *Escherichia coli*** diarrhoea, traditional acupuncture at **Du-1**, **ST-36**, **BL-20**, **Ren-12** and **ST-25** produced the best results in comparison to the groups treated with electro-acupuncture or antibiotics. There were too many groups given the number of cases. **Hwang et al, Am J Vet Res 1988**

Several animal experiments investigated the effect of acupuncture on signalling and modulating pain. Acupuncture at **Du-1** and **Du-2** inhibited the reaction on **experimental pain stimuli**. **Bing et al, Neuroscience 1991, Xu et al, Zhen Ci Yan Jiu 1989, Xu et al, Zhen Ci Yan Jiu 1989**

Du-2 → Du-1


Level of the
iliac crests
Spinous process L4
Du-3
Spinous process L5

Du-3 Rats treated with electro-acupuncture at **Du-3**, **BL-54** and **BL-60** 15 minutes after a standardised **spinal cord injury** at T8, showed a marked improvement (regarding both morphology and functioning) three days post-operatively compared to rats not treated with acupuncture. However, none of the beneficial effects occurred in rats given acupuncture treatment 24 hours after spinal cord injury. **Politis et al, Acupunct Electrother Res 1990**


Spinous process L2
Du-4
Du
Spinous process L3
Level of the iliac crests
Spinous process L4
(dependent on
patient position)
Spinous process L4

Du-4 A Turkish prospective, randomised, non-blinded, controlled group-comparison trial ($n = 24$) investigated the efficacy of acupressure at **Du-4**, **Du-15**, **Du-20**, **BL-23**, **BL-28**, **BL-32**, **HE-7**, **HE-9**, **ST-36**, **SP-4**, **SP-6**, **SP-12**, **Ren-2**, **Ren-3**, **Ren-6**, **KID-3** and **KID-5** on **enuresis** compared to oxybutynin given to the control group. Acupressure was administered to 12 patients by the parents. While treatments in both groups were successful, complete recovery was significantly higher in the acupressure group (83.3%) compared to the control group (58.3%). **Yuksek et al, J Int Med Res 2003**


Spinous process T11
Du-6
Spinous process T12

Du-6 An earlier Chinese case study reports the application of **Du-6** for **acupuncture anaesthesia for hysterectomies. Authors' Collective, Chin Med J (Engl) 1978**


Spinous process T9
Du-18
Spinous process T10

Du-8 An experiment in rats supports the effect of **Du-8** on **seizures** (by releasing melatonin) and on **cerebral infarction** (reduction of the cerebral infarction volume due to release of taurine and decrease of aspartame). **Chao et al, Acupunct Electrother Res 2001, Zhao et al, Acupunct Electrother Res 1997, Yin et al, Zhen Ci Yan Jiu 1994**



Du-9 The effect of electro-acupuncture at **Du-9** was investigated in 23 patients suffering from **coronary heart disease**. The results showed a slight dilation of the coronary arteries and a slight decrease of the heart rate frequency (monitored by coronary arteriography). **Yan et al, Zhongguo Zhong Xi Yi Jie He Za Zhi 1998**

Two earlier Chinese case studies report decreased symptoms in patients with coronary heart disease after acupuncture or tuina at Du-9. Wang et al, Zhong Xi Yi Jie He Za Zhi 1988, Wang et al, Zhong Xi Yi Jie He Za Zhi 1987

A Chinese case study reports the successful treatment of **angina pectoris** by implanting a micro-depressor at **Du-9**. **Wang et al, Zhong Xi Yi Jie He Za Zhi 1988**


Spinous process C7
Du-11
Spinous process T3
Inferior
angle

Du-11 Electro-acupuncture at **Du-11** and **Du-16** prior to, during and after an experimentally induced **transient ischaemia** in gerbils suggests the protective influence of these points. They seem to suppress both glutamate release and reperfusion injury following the ischaemic insult. **Pang et al, Am J Chin Med 2003**


Spinous process C7
Spinous process T3
Du-12

Du-12 A Chinese case study reports that classic acupuncture at **Du-12**, **L.I.-10**, **BL-11** and **S.I.-3** with *deqi* sensation in the direction of the disorder in 55 patients with **cervical vertebra**

disease and **impaired cerebral blood flow capacity** led to a significant improvement of blood flow capacity. **Qie et al, Zhong Xi Yi Jie He Za Zhi 1991**



Du-14 → L.I.-4, ST-8; ST-36

A Chinese experimental trial ($n = 40$) investigated the effect of acupuncture at **Du-14** and **P-6** on driving performance during a three-hour driving simulator test. The acupuncture group showed a significantly better driving performance and a decrease in **driving fatigue**, compared to the untreated control group. **Li et al, Accid Anal Prev 2004**

A Chinese prospective, randomised, controlled, non-blinded trial ($n = 40$) investigated the effect of acupuncture at **Du-14 and P-6** on heart rate and driving performance during a three-hour driving simulator test. The acupuncture group showed a significantly decreased **activation of the sympathetic nervous system** and increased **parasympathetic activity** compared to the untreated control group. **Li et al, Eur J Appl Physiol 2003**

A Chinese retrospective case study ($n = 25$) investigated the effect of cupping at **Du-14**, **BL-13**, **BL-20** and **BL-23** on **bronchial asthma** while reducing orally administered cortisone. The author reports that 56% of patients showed a marked improvement after 30 treatments. **Hu, J Tradit Chin Med 1998**

A Chinese prospective case study ($n = 50$) reports the successful treatment of **perennial allergic rhinitis** by applying 10% *Cantharides* extract at **Du-14** and **P-6**. The results showed an effective rate of 88%. The allergic nasal mucosa provocative test of the treated group improved after the treatment, the number of eosinophils and basophils in nasal secretion decreased and the serum total IgE also reduced significantly. **Tang et al, Zhongguo Zhong Xi Yi Jie He Za Zhi 1995**

Du-15 → T.B.-8; Du-4

Du-16 → Du-11



Du-20 → T.B.-8; G.B.-4, ST-8; Du-4; LIV-3; HE-7, L.I.-4

A Chinese prospective randomised controlled single-blinded group-comparison trial ($n = 50$) investigated the effect of a standardised acupuncture protocol, used either on its own or accompanied by needling of **Du-20**, **Du-26** and **HE-7** (either singly or in combination) on **vascular dementia** in hemiplegic patients. Clinical symptoms were observed and scales such as HDS-R, ADL and functional activities questionnaire (FAQ) used for assessment. The group additionally treated with **Du-20 and HE-7** showed marked improvement of memory, orientation and reaction. At the same time mental rigidity and trance decreased. **Du-20** on its own improved understanding, calculating and social adaptation, while **Du-26** was helpful in treating mental retardation, failure to perform daily activities, trance and poor memory. The combination of the three points showed overall the best results in improving intelligence and social adaptation. The particular design of this trial – combining a standard protocol used in both groups with the actually relevant points in the verum group – presents an interesting model for eliminating persistent problems regarding placebo methods and blinding. However, in this particular trial the number of participants (5 groups of 10 subjects) was too low to determine if the results were statistically significant. **Lai et Huang, Chin J Integr Med 2005**

A German prospective, non-blinded, pair-matched, controlled trial ($n = 121$ pregnant women between 30 and 39 weeks of gestation) investigated the effect of acupuncture at **Du-20** and **ST-36** on **fetal and maternal cardiotocographic parameters and maternal circulation**. The main difference was a transient increase of the Fisher score in the treatment group compared to the control group, with a persistent increase of the Fisher score. **Scharf et al, Z Geburtshilfe Neonatol 2003**

A Croatian prospective, randomised, placebo-controlled trial ($n = 57$) investigated the effectiveness of **Du-20**, **L.I.-4**, **Ren-3**, **Ren-4**, **Ren-6**, **G.B.-34**, **BL-23**, **SP-6** and **HE-7** on **primary dysmenorrhoea** compared to placebo-acupuncture. Subjects were observed for a period of two years. After one year, 93.3% of acupuncture patients were symptom-free and/or not taking medication compared to only 3.7% of the placebo patients. **Habek et al, Gynakol Geburtshilfliche Rundsch 2003**

A Polish prospective, randomised, controlled, non-blinded trial ($n = 69$) investigated the effect of acupuncture at **Du-20**, **Ren-12**, **ST-36**, **ST-21**, **ST-25**, **LIV-3**, **LIV-13**, **P-6** and **HE-7** in addition to a low calorie diet in the treatment of obesity (BMI approximately 33 kg/m^2). This diet consisted of a daily intake of about 1200–1500 kcal, which was about 1000 kcal below the daily energy requirement of the patients. The acupuncture group showed a significantly better result after only 12 treatments over a period of 6 weeks. The mean body weight decreased from 85.5 kg to 72.7 kg, while it only decreased to 77.1 kg in the diet group. **Wozniak et al, Ginekol Pol 2003**

A German prospective, randomised, placebo-controlled, double-blinded trial ($n = 56$) investigated the effect of acupuncture at **Du-20**, **Ex-HN-6**, **HE-7**, **P-6** and **BL-62** in the treatment of **depression** and **generalised anxiety**. Results were assessed using questionnaires. After 10 treatments, the verum acupuncture group showed a significantly larger clinical improvement compared to the placebo group (61% vs 21%). **Eich et al, Fortschr Neurol Psychiatr 2000**

Du-26 → G.B.-4; Du-20

Ren mai (conception vessel)

Ren-2 → Du-4



Ren-3 → Du-4; Du-20

A Taiwanese prospective, randomised, controlled trial ($n = 60$) investigated the influence of electro-acupuncture (EA) at **Ren-3**, **Ren-4** and **BL-32** on the **neurogenic bladder of spinal cord injured patients** compared to the conventional bladder training programme received by the control group. The acupuncture group took significantly less time to achieve balanced voiding than the control group (on average 28 days less). The best results were achieved in patients who received acupuncture within three weeks after injury (39 days less). **Cheng et al, Spinal Cord 1998**

Ren-4 → Du-20; ST-25; Ren-3

Ren-6 → Du-4; Du-20; Ren-17



Ren-8 → P-6

A Chinese prospective, randomised, controlled, non-blinded trial ($n = 56$) investigated the effect of moxibustion at **Ren-8** in addition to chemotherapy for **nasopharyngeal carcinoma** (stage III and IV). There were significantly fewer toxic and side effects in the moxibustion group compared to the control group. The five-year survival rate in the two groups were 50.0% and 35.7% respectively. **Chen et al, Zhongguo Zhong Xi Yi Jie He Za Zhi 2000**

A Chinese prospective, randomised, controlled trial ($n = 140$) investigated the effect of applying a topical ointment at **Ren-8** on **epigastric pain**. Results in the treatment group were significantly better than in the control group (94% vs 53%). **Ba et al, J Tradit Chin Med 1999**

Ren-12 → L.I.-4; Du-1; Du-20; LIV-3; Ren-17

Ren-13 → P-6

Ren-14 → LIV-14



Ren-17 A Chinese prospective, randomised, controlled trial ($n = 60$) investigated the effect of **Ren-17**, **Ren-12**, **Ren-6**, **ST-36 and SP-10** on the symptoms of **vascular dementia** compared to conventional treatment. Both acupuncture and conventional treatment showed a highly significant increase of MMSE, HDS-R and ADL scores. However, the results of the acupuncture group were statistically more significant regarding MMSE, HDS-R and the total rate of effectiveness (80% vs 47%). **Yu et al, Neurol Res 2006**



Ren-23 A Chinese retrospective case study ($n = 120$) reports the successful treatment of **pseudobulbar palsy** with acupuncture at **Ren-23** and **LU-5. Wang et al, J Tradit Chin Med 1998**



Ren-24 A German prospective, single-blinded, controlled trial ($n = 41$) reports that acupuncture at **Ren-24** significantly reduced the severity of the **gag reflex** during transoesophageal echocardiography compared to acupuncture at a sham point. **Rosler et al, J Altern Complement Med 2003**

Extra points



Ex-HN-1 → BL-7

A Taiwanese, prospective, randomised, placebo-controlled, single-blinded experimental trial ($n = 9$) investigated the effect of the *sishencong*-points (**Ex-HN-1**) on the variance of heart rate frequency. The authors observed an increase in the vagal activities but a suppression of the sympathetic activity. **Wang et al, Auton Neurosci 2002**

A Chinese case study ($n = 51$) reports the successful treatment of **hyperthyreosis** with acupuncture at Ex-HN-1. **Xie et al, J Tradit Chin Med 1994**



Ex-HN-3 An Austrian prospective, randomised, single-blinded experimental cross-over study ($n = 25$) showed that acupuncture (but not laser acupuncture) at *yintang* monitored by EEG had a sedating effect. Clinical application of this point, for example for **sleeping disorders**, requires further investigation. **Litscher et al, Eur J Anaesthesiol 2004**

Ex-HN-4 → S.I.-18; L.I.-4
Ex-HN-5 → G.B.-5; LIV-3
Ex-HN-6 → HE-7; Du-20



Ex-B-1 A Chinese prospective, randomised, controlled trial ($n = 84$) investigated the effect of a herbal plaster at **Ex-B-1**, **BL-11**, **BL-12**, **BL-13** and **BL-15** on **chronic bronchitis** compared to intramuscular injection therapy. In the plaster group the clinical total effective rate was 93.2% immediately after the treatment course and 91.5% after 18 months (control group: 80% and 80%). X-rays of the thorax showed the effectiveness of the plaster as 40.7% and 89.8% after 18 months (control group: 20% and 76%). **Huo et al, Zhongguo Zhong Xi Yi Jie He za Zhi 2001**



Ex-B-2 A Chinese case study ($n = 43$) reports the positive effects of treating **ulcerative colitis** with acupuncture at **Ex-B-2** as well as stimulation with a plum-blossom needle at **BL-22** and **BL-25. Yue and Zhenhui, J Tradit Chin Med 2005**

A Chinese retrospective case study ($n = 168$) reports the successful treatment of **sciatica** with acupuncture at the **Ex-B-2** points. **Pei et al, J Tradit Chin Med 1994**



Ex-B-3 An experiment in diabetic rabbits demonstrated that electro-acupuncture at **Ex-B-3** decreased plasma glucose levels and inhibited the release of pancreatic glucagon. The effect was increased by adding **ST-36**. This latter point led to no significant changes when needled alone. **Zeng et al, J Tradit Chin Med 2002**

Ex-UE-9 → L.I.-4



Ex-UE-10 A case study describes the successful treatment of **hiccups** with acupuncture at **Ex-UE-10**. **Qi, J Tradit Chin Med 1993**

Ex-UE (*JIANNEILING*) → L.I.-15
Ex-UE (*JIANQIAN*) → L.I.-4
Ex-LE-4 → ST-35
Ex-UE (*ZHONGPING*)

A Chinese retrospective case study ($n = 115$) reports the successful treatment of **shoulder and back pain** with acupuncture at ***zhongping***. The point *zhongping* is located midway between ST-36 and ST-37. **Wang et al, J Tradit Chin Med 1995**

9.3 Summary

The data presented clearly demonstrates that several actions of a number of acupuncture points are undoubtedly effective. These points (for example P-6) were tested according to the highest scientific standards, comparing standard acupuncture to deep acupuncture at non-acupuncture points (a methodology considered the most superior acupuncture placebo).

This proof is even more important since the results of the two largest acupuncture trials to date, ART (Acupuncture Randomized Trials) and GERAC (German Acupuncture Trial), may have led to the impression that, while acupuncture is indeed effective, its effect is independent of the location of the acupuncture points. The hitherto unsurpassed size of the trials and the undoubtedly intelligent and biomathematically impeccable design (especially of the GERAC trial) further contribute to this impression. Due to their flexible point prescriptions and their complexity, these studies have not been included in section 9.2.

But what are the basic results of these trials? (up to May 2006: **Witt et al, Lancet 2005; Linde et al, JAMA 2005; Melchart et al, Br Med J 2005; Brinkhaus, Arch Intern Med 2006**; **Diener et al, Lancet Neurol 2006**)

For both **gonarthrosis** and **lower back pain,** acupuncture had significantly better results than the untreated waitlist (ART) or conventional therapy (GERAC). For **migraine**, acupuncture is significantly better than the untreated waitlist (ART), and treatments with acupuncture for only six weeks had the same results as treatments with conventional medicine for six months (GERAC). For **tension headaches**, acupuncture provided significantly better results than the waitlist (ART). A comparison between acupuncture and conventional therapy in the treatment of tension headaches within the framework of GERAC was not possible, since all but two patients refused the stigmatised conventional treatment with amitriptyline due to the high incidence of side-effects. So far the results do not hold any surprises. Their importance lies in the comparison between true and placebo acupuncture (acupuncture at non-acupuncture points).

For the treatment of lower back pain, both studies (GERAC and ART) showed no significant advantage for true acupuncture; the effect of acupuncture therefore seems to be independent of the location of the acupuncture points. For the treatment of gonarthrosis, the ART trial observed a significant short-term effect in favour of true acupuncture. However, without consistent treatments the disorder will progress, further data showing no significant difference between true and sham acupuncture. Results of the GERAC trial confirm the significant short-term results. For the treatment of migraines and tension headaches, the relevant ART trials could not establish a significant difference between true and placebo acupuncture. The migraine section of the GERAC trial found a significantly reduced number of days with headache in subgroup analyses. Regarding tension headaches, up to now the GERAC reports show significant differences in favour of true acupuncture.

How can we explain the good results of placebo acupuncture, especially for the treatment of lower back pain? And how can the differing results between the ART and GERAC trials for gonarthrosis, migraines and tension headaches be explained? Shouldn't the trials, which are both designed according to the criteria listed in Section 9.1, be very reliable because of the high power of their design? The key to the answer – besides the already well-known deficits of the GERAC trials (by international standards, with only 140 hours – lowest standard – of training, questionable choice of true and sham acupuncture points) – lies in the so-called 'internal validity' of the collected data. The external validation, especially of the GERAC trials, was carried out in an exemplary manner: patients and physicians were separately questioned about the treatments by telephone interviewers. This filtered out a high number of patients receiving unacceptable additional therapies, thus increasing the validity of the data. However, it was hardly possible to control the internal validity of the trial. With treatments taking place in hundreds of clinics, no one was able to control if true or sham points were needled. One peculiarity of both trials suggests that physicians treating patients in the placebo group selected true acupuncture points: generally, the participating physicians weren't research scientists, but family doctors who, by participating in the trial, were able to give their patients treatments paid for by their obligatory health insurance, thus securing a part of their own income. Therefore, participation in the trials not only contributed to the income of these physicians, it also meant that the crucial performers of the trials had other goals in mind – patient satisfaction, their income – rather than the trial itself (i.e. collecting reliable data regarding the effectiveness of acupuncture). These conflicting goals particularly affected the placebo-acupuncture, which had a higher potential of negatively affecting patient satisfaction and the income of the participating physicians, and which could not be balanced by external quality assurance through telephone interviewers. The part of the GERAC trials investigating tension headaches provides another interesting insight. This section of the trials prohibited needling of points located on the head and it was here that the treatment protocol was disregarded most often (according to GERAC symposium, RUB 16 November 2005). And it was exactly in this externally validated part of the trial that GERAC observed significant differences between true and placebo acupuncture!

An important lesson to be learnt from the ART and GERAC trials is that size and adherence to biomathematical standards alone will not guarantee quality. If, in a trial above a certain size, the data collection is compromised due to conflicting interests of the initiators of the trial and the treating physicians, this will have a considerable adverse affect on the validity of the study.

The above reservations should result in a rather cautious interpretation of the results of large-scale trials such as GERAC and ART.

Even conventional medical procedures, considered as proven beyond doubt, recently failed spectacularly in controlled, double-blinded trials (**Moseley, N Engl J Med 2002**), which means that the efforts for scientific proof regarding specific details of acupuncture will be seen in a different light.

Appendix

Notes on Chapter 1

1: The *yin yang sho yi mai jiu jing* (Treatise on the Yin Yang Eleven Vessels Moxibustion), a manuscript found at an archaeological site at Mawangdui and dated to 169 BC, contains a simple description of the channel system. In this manuscript, the channels refer to regions of the body rather than to internal organs. It does not mention the Pericardium channel (hand *jueyin*), the channels are not divided into three Yin and three Yang channels, nor is the concept of the Five Phases mentioned.

According to chapter 17 of the *Ling Shu* and chapter 22 of the *Nanjing*, the channels have a centripetal course, originating at the fingers and the toes. They do not represent a closed circuit. Equally, chapter 5 of the *Ling Shu*, describing the 'roots' and 'knots' of the channels (→ 1.2.3) is based on a centripetal model.

In contrast, chapter 21 of the *Su Wen* contains references about the early conceptual stages of the channel theory, listing channel categories:

- The posterior of the body is governed by the *taiyang*
- The anterior of the body by the *yangming*
- The lateral aspect by the *shaoyang*
- The medial aspect by the *taiyin.*

2: Chapters 10 and 15 of the *Ling Shu* describe the channel system as a continuous circuit in the order LU → L.I. → ST etc. But only later texts such as the *Shi Si Jing Fa Hui* ('Commentary on the 14 Channels', 1341 AD) routinely mention the circulation model, first hinted at in chapter 15 of the *Ling Shu*. 'The Yang declines when the Yin increases' – according to Manaka et al (1995); this statement from the classics is at the root of the later theory that the Yin channels represent the ascending flow of Qi, running from the toes to the trunk and from the trunk to the fingers. It was further suggested that the Yang channels represent the descending flow of Qi, running from the fingers to the head and from the head to the toes.

Bibliography

Bing Wang (Original note) 1997 Yellow Emperor's canon of internal medicine (*Su Wen* and *Ling Shu*), trans Wu NL, Wu AL. China Science & Technology Press, Beijing

Birch S, Junko I 1994 Japanese acupuncture: a clinical guide. Paradigm Publications, Brookline MA

Bschaden J 2001 Shen-Akupunkturatlas. Springer, Berlin

Chen J 1999 Anatomical atlas of Chinese acupuncture points. Shandong Science and Technology Press China, Beijing

Cheng X (ed.) 1987 Chinese acupuncture and moxibustion. Foreign Languages Press, Beijing

Clavey S 2003 Fluid physiology and pathology in traditional Chinese medicine, 2nd edn. Churchill Livingstone, Edinburgh

Deadman P, Al-Khafaji M, Baker K 1998 A manual of acupuncture. Journal of Chinese Medicine Publications, East Sussex

Denmai S 2003 Finding effective acupuncture points. Eastland Press, Seattle, WA

Ellis A, Wiseman N 1989 Grasping the wind. Paradigm Publications, Brookline, MA

Ellis A, Wiseman N 1991 Fundamentals of Chinese acupuncture. Paradigm Publications, Brookline, MA

Flaws B 1998 Sticking to the point. Blue Poppy Press, Boulder, CO

Focks C 1998 Atlas Akupunktur. Urban & Fischer, Munich

Focks C, Hillenbrand N (eds) 2003 Leitfaden Chinesische Medizin. Urban & Fischer, Munich

Foen Tjoeng Li, Zhen Jiu Xue 1987–1988 Course material and notes.

Geng J 2001 Die erfolgreiche Punktkombination. Verlag für Ganzheitliche Medizin, Kötzting

Gleditsch J M 2005 Reflexzonen und Somatopien. Urban & Fischer, Munich

Greten J 2004 Kursbuch traditionelle chinesische Medizin. Georg Thieme, Stuttgart

Hammes M 1992–1994 Namensgebung und Akupunktur. Zeitschrift Aku (Akupunktur, Theorie und Praxis) 4/92, 1/93, 4/93, 4/94

Hecker U, Steveling A, Peuker E, Kastner J 2001 Lehrbuch und Repetitorium Akupunktur. Hippokrates Verlag, Stuttgart

Helms J M 1997 Acupuncture energetics. Medical Acupuncture Publishers, Berkeley, CA

Hempen C-H 1995 DTV-Atlas zur Akupunktur. DTV, Munich

Hicks A, Hicks J, Mole P 2004 Five element constitutional acupuncture. Churchill Livingstone, Edinburgh

Jarrett L S 2003 The clinical practice of Chinese medicine. Spirit Path Press, Stockbridge, MA

Kampik G 1998 Propädeutik der Akupunktur. Hippokrates Verlag, Stuttgart

Kirschbaum B 1995 Die 8 außerordentlichen Gefäße in der traditionellen chinesischen Medizin. ML-Verlag, Uelzen

Kirschbaum B 1999 Seminar handouts and notes. Universität Witten/Herdecke

Kitzinger E 1995 Der Akupuktur-Punkt – Topographie und chinesische Stichtechnik, 2nd edn., Wilhelm Maudrich, Wien

König G, Wancura I (1979, 1983). Praxis und Theorie der neuen chinesischen Akupunktur, Bd 1 & 2. Wilhelm Maudrich, Wien

Kubiena G 2004 Therapiehandbuch Akupunktur, 3rd edn. Munich

Kubiena G, Ramakers F 2002 Bestzeitakupunktur – Chronoakupunktur. Wilhelm Maudrich, Vienna

Kubny, M 2002 Qi – Lebenskraftkonzepte in China. Definitionen: Theorien und Grundlagen. Karl F Haug, Heidelberg

Larre C, Rochat de la Vallée E 1987. The secret of the spiritual orchid. Monkey Press, Cambridge

Larre C, Rochat de la Vallée E 1997 The eight extraordinary meridians. Monkey Press, Cambridge

Larre C, Rochat de la Vallée E 1999 Essence, Spirit, Qi and Blood. Monkey Press, Cambridge

Larre C, Rochat de la Vallée E 2001 The lung, rev edn. Monkey Press, Cambridge

Larre C, Schatz J, Rochat de la Vallée E (1st edn in French 1979; English translation 1986). Survey of traditional Chinese medicine. Institut Ricci, Paris and Traditional Acupuncture Institute, Columbia, MD

Legge D 1997 Close to the bone. Sydney College Press, Sydney, New South Wales

Li Ding 1991 Acupuncture, meridian theory and acupuncture points. Foreign Languages Press, Bejing

Lie Fjoen Tjoeng 1987–88 Zhen Jiu Xue. Seminar handouts and notes. Hamburg

Lorenzen U, Noll A 1992–2000 Die Wandlungsphasen in der traditionellen chinesischen Medizin, Bd 1–5. Müller & Steinicke, Munich

Maciocia G 1989 The foundations of Chinese medicine. Churchill Livingstone, Edinburgh

Maciocia G 1998 Obstetrics and gynecology in Chinese medicine. Churchill Livingstone, Edinburgh

Manaka Y, Itaya K, Birch S 1995 Chasing the dragon's tail. Paradigm Publications. Brookline, MA

Matsumoto K, Birch S 1983 Five elements and ten stems. Paradigm Publications, Brookline, MA

Matsumoto K, Birch S 1996 Extraordinary vessels. Paradigm Publications, Brookline, MA

Morant G. S 1994 Chinese acupuncture [translated from French]. Paradigm Publications, Brookline, MA

Ngyen Van Nghi 1989, 1991 Traditionelle chinesische Medizin. Pathogenese und Pathologie der Energetik in der Chinesischen Medizin, Bd 1 & 2. ML-Verlag, Uelzen

Ngyen Van Nghi 1996 Hoang Ti Nei King, So Quenn, Bd 1. ML-Verlag, Uelzen

Van Nghi N 1997 Hoang Ti Nei King, So Quenn, Bd 2. ML-Verlag, Uelzen

Ni Yitian 1996 Navigating the channels of traditional Chinese medicine. Oriental Medicine Center, San Diego, CA

Nielsen A 1995 Gua sha: a traditional technique for modern practice. Churchill Livingstone, Edinburgh

O'Connor J, Bensky D 1981 Acupuncture, a comprehensive text. Shanghai College of Traditional Medicine/Eastland Press, Seattle, WA

Ogal H, Kolster B C 1999 Ohrakupunktur, Grundlagen-Praxis-Indikationen, 2nd edn. KVM-Verlag, Marburg

Ogal H, Stör W (eds) 1999 Seirin-Bildatlas der Akupunktur. KVM-Verlag, Marburg

Pabst R, Putz R 2004 Sobotta-Atlas einbändig. Elsevier, Munich

Peuker E T, Filler J F, Hecker H U, Steveling A 2005 Anatomie-Atlas Akupunktur. Hippokrates, Stuttgart

Pirog J E 1996 The practical application of meridian style acupuncture. Pacific View Press, Berkeley, CA

Platsch K D 2000 Psychosomatik in der chinesischen Medizin. Urban & Fischer, Munich

Platsch K D 2005 Die fünf Wandlungsphasen: das Tor zur chinesischen Medizin. Urban & Fischer, Munich

Pollmann N 2002 Basislehrbuch Akupunktur. Urban & Fischer, Munich

Porkert M, Hempen C-H 1997 Systematische Akupunktur, 2nd edn. Urban & Schwarzenberg, Munich

Ramakers F 2003 Physiologie und Pathologie der 72 Leitbahnen und Akupunkturtechniken (course material and notes)

Ross J 1986 Zang fu: the organ systems of traditional Chinese medicine, 2nd edn. Churchill Livingstone, Edinburgh

Ross J 1995 Acupuncture point combinations. Churchill Livingstone, Edinburgh

Schmidt J M 1990 Die klassischen Akupunkturpunkte. ML-Verlag, Uelzen

Schnorrenberger C C 1979 Lehrbuch der chinesischen Medizin für westliche Ärzte. Hippokrates, Stuttgart

Schnorrenberger C C 1994 Die topographisch-anatomischen Grundlagen der chinesischen Akupunktur und Ohrakupunktur. Hippokrates, Stuttgart

Shima M, Chase C 2000 The channel divergences, deeper pathways of the web. Paradigm Publications, Brookline, MA

Solinas H, Mainville L., Anteroche, B 1998 Atlas of Chinese acupuncture, meridians and collaterals. Publishing Canada Inc, Sillery, Quebec

State Standard of the People's Republic of China1990 The location of acupoints. Foreign Languages Press, Beijing

Tan R T-F 2003 Dr Tan's strategy of twelve magical points. R T-F Tan, San Diego, CA

Tan R T-F 2004 Seminar handouts and notes. Rothenburg

Thambijarah R (1991). Course material and notes. Hamburg and Berlin

Unschuld P U (trans and annotated) 1986 Nan-Ching: the classic of difficult issues. University of California Press, Berkeley, CA

Unschuld P U (trans and annotated) 2003 Huang Di nei jing su wen. University of California Press, Berkeley, CA

Wieger L 1965 Chinese characters. Paragon Book Reprint/Dover Publications, New York (unabridged and unaltered republication of the second edition published by the Catholic Mission Press in 1927)

Wiseman N, Ellis A 1994 Fundamentals of Chinese medicine. Paradigm Publications, Brookline, MA

World Health Organization 1991 A proposed standard international acupuncture nomenclature. WHO, Geneva

Wu Jing-Nuan (trans) 2004 Ling Shu or the Spiritual Pivot. Asian Spirituality, Taoist Studies Series, 2. University of Hawaii Press, Honolulu

Yan Zhengguo 2003 Anatomical atlas of acupuncture points – a photo location guide. Donica Publishing, London

Yin Ganglin, Lin Zhenghua 2000 Advanced modern Chinese acupuncture therapy. New World Press, Bejing

Yuan H 1999 Traditionelle Chinesische Akupunktur. Ullstein Mosby, Wiesbaden

Yuan H 2002 Chinesische Pulsdiagnostik. Urban & Fischer, Munich

Yuan H 2003 Chinesische Zungendiagnostik, 2nd edn. Urban & Fischer, Munich

Zhang Y H, Rose K 1995 Who can ride the dragon? Paradigm Publications, Brookline, MA

Index

A

Accumulation points (*xi* points) . . . 667
Achilles tendon . . . 77
Acromion . . . 52
Adjacent points . . . 685
Anatomical orientation . . . 37
Anatomical snuffbox . . . 59
Anatomy of the ear . . . 46
Anterior superior iliac spine (ASIS) . . . 71
Antique points . . . 670
Atlas . . . 47
Axillary line . . . 69
Axis . . . 60

B

Back-*shu* points . . . 668
Balancing the *du mai* and the *ren mai* . . . 692
Balancing *Yin* and *Yang* in paired channels . . . 693
ben points (root points) . . . 690
Biceps tendon . . . 55
Body positions . . . 35

C

Cardinal points . . . 678
Cervical spine . . . 60
Chain and lock point association method . . . 695
Channel circuits . . . 10
Channel system . . . 1
Cheek bones . . . 41
Cleft points (*xi* points) . . . 667
Combination of *Yin* and *Yang* channel points . . . 693
Combining local and distal points . . . 691
Combining points from above and below . . . 694
Combining points on the front and back of the body . . . 692
Confluent points . . . 18
Connecting points (*luo* points) . . . 666
Cubital crease (elbow crease) . . . 55
cun-measurements . . . 31
Cutaneous regions *(pi bu)* . . . 3
Cutaneous zones . . . 3, 24

D

Defensive *Qi (wei qi)* . . . 5
Distal points . . . 685
Divergent channels . . . 3, 20

E

Elastic tape . . . 34
Element points . . . 670
Eleventh rib, free end . . . 70
End points . . . 19
Entry points . . . 684
Epicondyles of the humerus . . . 55
Exit points . . . 684
Extraordinary vessels . . . 3, 24
Eyes of the knee . . . 73

F

Finger-*cun* . . . 32
Five Element points . . . 670
Five *shu*-transporting points . . . 670
Foot *Yang-Yin* connections . . . 12
Forms of *Qi* . . . 5
Front-*mu* points . . . 669

G

Gao Wu Command points . . . 681
Glabella . . . 40
Grand piqure . . . 695
Greater trochanter . . . 72

H

Hairline . . . 38, 48
Hand *Yang-Yin* connections . . . 12
Head of the fibula . . . 73
Head of the humerus . . . 52
Heavenly Star points of Ma Dan Yang . . . 683
he-sea points *(he xue)* . . . 676
hui-meeting points of the 8 tissues . . . 677

I

Iliosacral joint . . . 66
Infraorbital foramen . . . 41
Interior/exterior combination . . . 693

J

jing bie . . . 3
jing jin . . . 3, 21
jing luo . . . 1
jing qii . . . 5
jing zheng . . . 3, 8
jing-river points *(jing xue)* . . . 675
jing-well points *(jing xue)* . . . 671
Joint space on the anterior ankle . . . 76

K

König/Wancura spreading-hands technique . . . 36

L

Laryngeal prominence . . . 49
Left-right combination . . . 694
liu jing . . . 14
Local points . . . 685
Location methods . . . 31
Lower *he*-sea points (*xiahe* points) . . . 679
Lumbar spine . . . 63
luo-connecting points . . . 666
luo-vessels . . . 3, 23

M

Malleolus, medial . . . 75
Mamillary line . . . 69
Mandibular angle . . . 44
Meeting points (*jiaohui* points) . . . 679
Mentolabial groove . . . 45
Midclavicular line . . . 69

N

Nasolabial groove . . . 44
Navicular bone . . . 78
Network vessel system . . . 1
Nipple . . . 69
Nutritive *Qi (ying qi)* . . . 5

O

Occipital protuberance . . . 48
Olecranon . . . 56
Opening points of the 8 extraordinary vessels . . . 678
Organ clock . . . 7

P

Passage points . . . 666
pi bu . . . 3, 24
Pisiform . . . 58
Point location . . . 34
Points of the Four Seas . . . 682
Primary channels . . . 3, 8
Proportional *cun* . . . 32

Q

Qi circulation . . . 5
Qi flow . . . 1
qi jing ba mai . . . 3, 24

R

Root points (*ben* points) . . . 19

S

Sacral foramina . . . 65
Sacroiliac joint . . . 65
Sacrum . . . 65
Shoulder hollows . . . 52
Shoulder . . . 51
shu-mu method . . . 692
shu-stream points *(shu xue)* . . . 674
Source points (*yuan* points) . . . 665
Specific points . . . 665
Spreading-hands technique . . . 36
Starting points . . . 19
Sternocostal angle . . . 69
Sun Si Miao Ghost points . . . 683
Superciliary arches . . . 40
Symphysis . . . 72

T

Temporal corner of the forehead . . . 39
Temporomandibular joint . . . 42
Tendinomuscular meridians . . . 3, 21
Thoracic spine . . . 62
Tips for point location . . . 34
Treatments according to the Organ clock . . . 695
Tuffier line . . . 63
Twelfth rib . . . 62

U

Umbilicus . . . 72

V

Vertebra prominens . . . 61
Vertex . . . 37

W

wei qi (Defensive *Qi*) . . . 5
Window of Heaven points . . . 681
Wrist joint space . . . 58

X

xi points (cleft points) . . . 667
Xiphoid process . . . 69

Y

Yang-Yang connections . . . 13
ying qi (Nutritive *Qi*) . . . 5
ying-spring points . . . 673
Yin-Yang balancing for unpaired channels . . . 694
Yin-Yang combination . . . 693
Yin-Yin connections . . . 13
yuan qi . . . 5
yuan/luo combination . . . 693
yuan-Source points . . . 665

Z

zong qi . . . 5
Zygomatic arch . . . 42
Zygomatic bone . . . 42

Acupuncture points (in numerical order)

B
BL 1 JingSPng 251
BL 2 Zanzhu 252
BL 3 Meichong 253
BL 4 Qucha 254
BL 5 Wuchu 255
BL 6 CHEngguang 256
BL 7 Tongtian 257
BL 8 LUoque 258
BL 9 YuzHEn 259
BL 10 Tianzhu 260
BL 11 Dazhu 261
BL 12 Fengmen 262
BL 13 Feishu 263
BL 14 Jueyinshu 264
BL 15 Xinshu 265
BL 16 Dushu 266
BL 17 Geshu 267
BL 18 Ganshu 268
BL 19 Danshu 269
BL 20 Pishu 270
BL 21 Weishu 271
BL 22 Sanjiaoshu 272
BL 23 SHEnshu 273
BL 24 Qihaishu 274
BL 25 Dachangshu 275
BL 26 Guanyuanshu 276
BL 27 Xiaochangshu 277
BL 28 Pangguangshu 278
BL 29 Zhonglüshu 279
BL 30 Baihuanshu 280
BL 31 Shangliao 281
BL 32 Ciliao 281
BL 33 Zhongliao 281
BL 34 Xialiao 281
BL 35 Huiyang 282
BL 36 CHEngfu 283
BL 37 Yinmen 284
BL 38 Fuxi 285
BL 39 Weiyang 286
BL 40 Weizhong 287
BL 41 Fufen 288
BL 42 Pohu 289
BL 43 Gaohuang 290
BL 44 SHEntang 291
BL 45 Yixi 292
BL 46 Geguan 293
BL 47 Hunmen 294
BL 48 Yanggang 295
BL 49 YisHE 296
BL 50 Weicang 297
BL 51 Huangmen 298
BL 52 Zhishi 299
BL 53 Baohuang 300
BL 54 Zhibian 301
BL 55 HEyang 302
BL 56 CHEngjin 303
BL 57 CHEngshan 304
BL 58 Feiyang 305
BL 59 Fuyang 306
BL 60 KunLUn 307
BL 61 Pucan 308
BL 62 SHEnSTi 309
BL 63 Jinmen 310
BL 64 Jinggu 311
BL 65 Shugu 312
BL 66 Zutonggu 313
BL 67 Zhiyin 314

D
Du 1 Changqiang 499
Du 2 Yaoshu 500
Du 3 Yaoyangguan 501
Du 4 SPngmen 502
Du 5 Xuanshu 503
Du 6 Jizhong 504
Du 7 Zhongshu 505
Du 8 Jinsuo 506
Du 9 Zhiyang 507
Du 10 Lingtai 508
Du 11 SHEndao 509
Du 12 SHEnzhu 510
Du 13 Taodao 511
Du 14 Dazhui 512
Du 15 Yamen 513
Du 16 Fengfu 514
Du 17 Naohu 515
Du 18 Quiangjian 516
Du 19 HouL.I.ng 517
Du 20 Baihui 518
Du 21 QianL.I.ng 519
Du 22 Xinhui 520
Du 23 Shangxing 521
Du 24 SHEnting 522
Du 25 Suliao 523
Du 26 Renzhong 524
Du 27 Duiduan 525
Du 28 Yinliao 526

E
Ex-B JieHExue 582
Ex-B Tunzhong 583
Ex-B 1 L.I.ngchuan 573
Ex-B 2 Huatuojiaji 574
Ex-B 3 Weiwanxiashu 575
Ex-B 4 Pigen 576
Ex-B 5 Xiajishu 577
Ex-B 6 Yaoyi 578
Ex-B 7 Yaoyan 579
Ex-B 8 Shiqizhui 580
Ex-B 9 Yaoqi 581
Ex-CA Weishang 564
Ex-CA Qizhong sibian 565
Ex-CA Yijing 566
Ex-CA Qimen 567
Ex-CA Tituo 568
Ex-CA Zhishi 569
Ex-CA Sanjiaojiu 570
EX-HN 1 SisHEncong 539
EX-HN 2 Dangyang 540
EX-HN 3 Yintang 541
EX-HN 4 Yuyao 542
EX-HN 5 Taiyang 543
EX-HN 6 Erjian 544
EX-HN 7 Qiuhou 545
EX-HN 8 Shangyingxiang 546
EX-HN 9 Neiyingxiang 547
EX-HN 10 Juquan 548
EX-HN 11 Haiquan 549
EX-HN 12 Jinjin 550
EX-HN 13 Yuye 551
EX-HN 14 YiSPng 552
EX-HN 15 JinG.B.ailao 553
EX-HN ShangSPng 554
EX-HN AnSPan 555
EX-HN Jiali 556
EX-HN JiacHEngjiang 557
EX-HN Chonggu Zhuidong 558
EX-HN JinG.B.i 559
Ex-LIV 1 Kuangu 603
Ex-LIV 2 HEL.I.ng 604
Ex-LIV 2 XiL.I.ng 604
Ex-LIV 3 Baichongwo 605
Ex-LIV 4 Neixiyan 606
Ex-LIV 5 Xiyan 607
Ex-LIV 6 Dannang 608
Ex-LIV 7 Lanwei 609
Ex-LIV 8 Neihuaijian 610
Ex-LIV 9 Waihuaijian 611
Ex-LIV 10 Bafeng 612
Ex-LIV 11 Duyin 613
Ex-LIV 12 Qiduan 614
Ex-LIV Huanzhong 615
Ex-LIV Siqiang 616
Ex-LIV Lineiting 617
Ex-UE 1 Zhoujian 587
Ex-UE 2 Erbai 588
Ex-UE 3 Zhongquan 589
Ex-UE 4 Zhongkui 590
Ex-UE 5 Dagukong 591
Ex-UE 6 Xiaogukong 592
Ex-UE 7 YaotongL.I.an 593
Ex-UE 8 Wailaogong 594
Ex-UE 8 LUozHEn 594
Ex-UE 8 Xianqiang 594
Ex-UE 9 Baxie 595
Ex-UE 10 Sifeng 596
Ex-UE 11 Shixuan 597
Ex-UE Jianneiling 598
Ex-UE Bizhong 599

G
G.B. 1 Tongziliao 399
G.B. 2 Tinghui 400
G.B. 3 Shangguan 401
G.B. 4 Hanyan 402
G.B. 5 XuanLU 403
G.B. 6 Xuanli 404
G.B. 7 Qubin 405
G.B. 8 Shuaigu 406
G.B. 9 Tianchong 407
G.B. 10 Fubai 408
G.B. 11 Touqiaoyin 409
G.B. 12 Wangu 410
G.B. 13 BensHEn 411
G.B. 14 YanG.B.ai 412
G.B. 15 Toulinqi 413
G.B. 16 Muchuang 414
G.B. 17 ZHEngying 415
G.B. 18 CHEngling 416
G.B. 19 Naokong 417
G.B. 20 Fengchi 418
G.B. 21 Jianjing 419
G.B. 22 Yuanye 420
G.B. 23 ZHEjin 421
G.B. 24 Riyue 422
G.B. 25 Jingmen 423
G.B. 26 DaiSTi 424
G.B. 27 Wushu 425
G.B. 28 Weidao 426
G.B. 29 Juliao 427
G.B. 30 Huantiao 428
G.B. 31 Fengshi 429
G.B. 32 Zhongdu 430
G.B. 33 Xiyangguan 431
G.B. 34 Yanglingquan 432
G.B. 35 Yangjiao 433
G.B. 36 Waiqiu 434
G.B. 37 GuangSPng 435
G.B. 38 Yangfu 436
G.B. 39 Xuanzhong 437
G.B. 40 Qiuxu 438
G.B. 41 Zulinqi 439
G.B. 42 L.I.wuhui 440
G.B. 43 Xiaxi 441
G.B. 44 Zuqiaoyin 442

H
HE 1 Jiquan 207
HE 2 Qingling 208
HE 3 Shaohai 209
HE 4 Lingdao 210
HE 5 Tongli 211
HE 6 Yinxi 212
HE 7 SHEnmen 213
HE 8 Shaofu 214
HE 9 Shaochong 215

K
KID 1 Yongquan 321
KID 2 Rangu 322
KID 3 Taixi 323
KID 4 Dazhong 324
KID 5 Shuiquan 325
KID 6 Zhaohai 326
KID 7 Fuliu 327
KID 8 Jiaoxin 328
KID 9 Zhubin 329
KID 10 Yingu 330
KID 11 HEnggu 331
KID 12 DaHE 332
KID 13 Qixue 333
KID 14 SiSTn 334
KID 15 Zhongzhu 335
KID 16 Huangshu 336
KID 17 Shangqu 337
KID 18 Shiguan 338
KID 19 Yindu 339
KID 20 Futonggu 340
KID 21 Youmen 341
KID 22 Bulang 342
KID 23 SHEnfeng 343
KID 24 Lingxu 344
KID 25 SHEncang 345
KID 26 Yuzhong 346
KID 27 Shufu 347

L
L.I. 1 Shangyang 101
L.I. 2 Erjian 102
L.I. 3 Sanjian 103
L.I. 4 HEgu 104
L.I. 5 Yangxi 105
L.I. 6 Pianli 106
L.I. 7 Wenliu 107
L.I. 8 Xialian 108
L.I. 9 Shanglian 109
L.I. 10 Shousanli 110
L.I. 11 Quchi 111
L.I. 12 Zhouliao 112
L.I. 13 Shouwuli 113
L.I. 14 Binao 114
L.I. 15 Jianyu 115

L.I. 16 Jugu 116
L.I. 17 TianL.I.ng 117
L.I. 18 Futu 118
L.I. 19 KouHEliao 119
L.I. 20 Yingxiang 120
LIV 1 Dadun 449
LIV 2 Xingjian 450
LIV 3 Taichong 451
LIV 4 Zhongfeng 452
LIV 5 Ligou 453
LIV 6 Zhongdu 454
LIV 7 Xiguan 455
LIV 8 Ququan 456
LIV 9 Yinbao 457
LIV 10 Zuwuli 458
LIV 11 Yinlian 459
LIV 12 JiSTi 460
LIV 13 Zhangmen 461
LIV 14 Qimen 462
LU 1 Zhongfu 83
LU 2 Yunmen 84
LU 3 Tianfu 85
LU 4 Xiabai 86
LU 5 Chize 87
LU 6 Kongzui 88
LU 7 Lieque 89
LU 8 Jingqu 90
LU 9 Taiyuan 91
LU 10 Yuji 92
LU 11 Shaoshang 93

P

P 1 Tianchi 353
P 2 Tianquan 354
P 3 Quze 355
P 4 Ximen 356
P 5 Jianshi 357
P 6 Neiguan 358
P 7 Daling 359
P 8 Laogong 360
P 9 Zhongchong 361

R

Ren 1 Huiyin 471
Ren 2 Qugu 472
Ren 3 Zhongji 473
Ren 4 Guanyuan 474
Ren 5 Shimen 475
Ren 6 Qihai 476
Ren 7 Yinjiao 477
Ren 8 SHEnque 478
Ren 9 Shuifen 479
Ren 10 Xiawan 480
Ren 11 Jianli 481
Ren 12 Zhongwan 482
Ren 13 Shangwan 483
Ren 14 Juque 484
Ren 15 Jiuwei 485
Ren 16 Zhongting 486
Ren 17 Danzhong/
Shanzhong 487
Ren 18 Yutang 488
Ren 19 Zigong 489
Ren 20 Huagai 490
Ren 21 Xuanji 491
Ren 22 Tiantu 492
Ren 23 Lianquan 493
Ren 24 CHEngjiang 494

S

S.I. 1 Shaoze 223
S.I. 2 Qiangu 224
S.I. 3 Houxi 225
S.I. 4 Wangu 226
S.I. 5 Yanggu 227
S.I. 6 Yanglao 228
S.I. 7 ZhizHEng 229
S.I. 8 Xiaohai 230
S.I. 9 JianzHEn 231
S.I. 10 Naoshu 232
S.I. 11 Tianzong 233
S.I. 12 Bingfeng 234
S.I. 13 Quyuan 235
S.I. 14 Jianwaishu 236
S.I. 15 Jianzhongshu 237
S.I. 16 Tianchuang 238
S.I. 17 Tianrong 239
S.I. 18 Quanliao 240
S.I. 19 Tinggong 241
SP 1 Yinbai 181
SP 2 Dadu 182
SP 3 Taibai 183
SP 4 Gongsun 184
SP 5 Shangqiu 185
SP 6 Sanyinjiao 186
SP 7 Lougu 187
SP 8 L.I.ji 188
SP 9 Yinlingquan 189
SP 10 Xuehai 190
SP 11 Jimen 191
SP 12 SIChongmen 192
SP 13 FusHE 193
SP 14 Fujie 194
SP 15 DaHEng 195
SP 16 Fuai 196
SP 17 Shidou 197
SP 18 Tianxi 198
SP 19 Xiongxiang 199
SP 20 Zhourong 200
SP 21 Dabao 201
ST 1 CHEngqi 129
ST 2 Sibai 130
ST 3 Juliao 131
ST 4 L.I.cang 132
ST 5 Daying 133
ST 6 JiacHE 134
ST 7 Xiaguan 135
ST 8 Touwei 136
ST 9 Renying 137
ST 10 Shuitu 138
ST 11 QisHE 139
ST 12 QuePn 140
ST 13 Qihu 141
ST 14 Kufang 142
ST 15 Wuyi 143
ST 16 Yingchuang 144
ST 17 Ruzhong 145
ST 18 Rugen 146
ST 19 Burong 147
ST 20 CHEngSTn 148
ST 21 Liangmen 149
ST 22 Guanmen 150
ST 23 Taiyi 151
ST 24 Huaroumen 152
ST 25 Tianshu 153
ST 26 Wailing 154
ST 27 Daju 155
ST 28 Shuidao 156
ST 29 Guilai 157
ST 30 Qichong 158
ST 31 Biguan 159
ST 32 Futu 160
ST 33 Yinshi 161
ST 34 Liangqiu 162
ST 35 Dubi 163
ST 36 Zusanli 164
ST 37 Shangjuxu 165
ST 38 Tiaokou 166
ST 39 Xiajuxu 167
ST 40 Fenglong 168
ST 41 Jiexi 169
ST 42 Chongyang 170
ST 43 Xiangu 171
ST 44 Neiting 172
ST 45 Lidui 173

T

T.B. 1 Guanchong 367
T.B. 2 Yemen 368
T.B. 3 Zhongzhu 369
T.B. 4 Yangchi 370
T.B. 5 Waiguan 371
T.B. 6 Zhigou 372
T.B. 7 Huizong 373
T.B. 8 SanyangLUo 374
T.B. 9 Sidu 375
T.B. 10 Tianjing 376
T.B. 11 QingLIVngyuan 377
T.B. 12 XiaoLUo 378
T.B. 13 Naohui 379
T.B. 14 Jianliao 380
T.B. 15 Tianliao 381
T.B. 16 Tianyou 382
T.B. 17 Yifeng 383
T.B. 18 QiSTi 384
T.B. 19 LUxi 385
T.B. 20 Jiaosun 386
T.B. 21 Ermen 387
T.B. 22 ErHEliao 388
T.B. 23 Sizhukong 389

Acupuncture points (pinyin name)

A

AnSPan EX-HN 555

B

Bafeng Ex-LIV 10 612
Baichongwo Ex-LIV 3 605
Baihuanshu BL 30 280
Baihui Du 20 518
Baohuang BL 53 300
Baxie Ex-UE 9 595
BensHEn G.B. 13 411
Biguan ST 31 159
Binao L.I. 14 114
Bingfeng S.I. 12 234
Bizhong Ex-UE 599
Bulang KID 22 342
Burong ST 19 147

C

Changqiang Du 1 499
CHEngfu BL 36 283
CHEngguang BL 6 256
CHEngjiang Ren 24 494
CHEngjin BL 56 303
CHEngling G.B. 18 416
CHEngSTn ST 20 148
CHEngqi ST 1 129
CHEngshan BL 57 304
Chize LU 5 87
Chonggu Zhuidong EX-HN 558
Chongyang ST 42 170
Ciliao BL 32 281

D

Dabao SP 21 201
Dachangshu BL 25 275
Dadu SP 2 182
Dadun LIV 1 449
Dagukong Ex-UE 5 591
DaHE KID 12 332
DaHEng SP 15 195
DaiSTi G.B. 26 424
Daju ST 27 155
Daling P 7 359
Dangyang EX-HN 2 540
Dannang Ex-LIV 6 608
DannangL.I.an Ex-LIV 6 608
Dannangxue Ex-LIV 6 608
Danshu BL 19 269
Danzhong/Shanzhong
Ren 17 487
Daying ST 5 133
Dazhong KID 4 324
Dazhu BL 11 261
Dazhui Du 14 512
L.I.cang ST 4 132
L.I.ji SP 8 188
L.I.ngchuan Ex-B 1 573
L.I.wuhui G.B. 42 440
Dubi ST 35 163
Duiduan Du 27 525
Dushu BL 16 266
Duyin Ex-LIV 11 613

E

Erbai Ex-UE 2 588
ErHEliao T.B. 22 388
Erjian L.I. 2 102
Erjian EX-HN 6 544
Ermen T.B. 21 387

F

Feishu BL 13 263
Feiyang BL 58 305
Fengchi G.B. 20 418
Fengfu Du 16 514
Fenglong ST 40 168
Fengmen BL 12 262
Fengshi G.B. 31 429
Fuai SP 16 196
Fubai G.B. 10 408
Fufen BL 41 288
Fujie SP 14 194
Fuliu KID 7 327
FusHE SP 13 193

L.I. 16 Jugu 116
L.I. 17 TianL.I.ng 117
L.I. 18 Futu 118
L.I. 19 KouHEliao 119
L.I. 20 Yingxiang 120
LIV 1 Dadun 449
LIV 2 Xingjian 450
LIV 3 Taichong 451
LIV 4 Zhongfeng 452
LIV 5 Ligou 453
LIV 6 Zhongdu 454
LIV 7 Xiguan 455
LIV 8 Ququan 456
LIV 9 Yinbao 457
LIV 10 Zuwuli 458
LIV 11 Yinlian 459
LIV 12 JiSTi 460
LIV 13 Zhangmen 461
LIV 14 Qimen 462
LU 1 Zhongfu 83
LU 2 Yunmen 84
LU 3 Tianfu 85
LU 4 Xiabai 86
LU 5 Chize 87
LU 6 Kongzui 88
LU 7 Lieque 89
LU 8 Jingqu 90
LU 9 Taiyuan 91
LU 10 Yuji 92
LU 11 Shaoshang 93

P

P 1 Tianchi 353
P 2 Tianquan 354
P 3 Quze 355
P 4 Ximen 356
P 5 Jianshi 357
P 6 Neiguan 358
P 7 Daling 359
P 8 Laogong 360
P 9 Zhongchong 361

R

Ren 1 Huiyin 471
Ren 2 Qugu 472
Ren 3 Zhongji 473
Ren 4 Guanyuan 474
Ren 5 Shimen 475
Ren 6 Qihai 476
Ren 7 Yinjiao 477
Ren 8 SHEnque 478
Ren 9 Shuifen 479
Ren 10 Xiawan 480
Ren 11 Jianli 481
Ren 12 Zhongwan 482
Ren 13 Shangwan 483
Ren 14 Juque 484
Ren 15 Jiuwei 485
Ren 16 Zhongting 486
Ren 17 Danzhong/
Shanzhong 487
Ren 18 Yutang 488
Ren 19 Zigong 489
Ren 20 Huagai 490
Ren 21 Xuanji 491
Ren 22 Tiantu 492
Ren 23 Lianquan 493
Ren 24 CHEngjiang 494

S

S.I. 1 Shaoze 223
S.I. 2 Qiangu 224
S.I. 3 Houxi 225
S.I. 4 Wangu 226
S.I. 5 Yanggu 227
S.I. 6 Yanglao 228
S.I. 7 ZhizHEng 229
S.I. 8 Xiaohai 230
S.I. 9 JianzHEn 231
S.I. 10 Naoshu 232
S.I. 11 Tianzong 233
S.I. 12 Bingfeng 234
S.I. 13 Quyuan 235
S.I. 14 Jianwaishu 236
S.I. 15 Jianzhongshu 237
S.I. 16 Tianchuang 238
S.I. 17 Tianrong 239
S.I. 18 Quanliao 240
S.I. 19 Tinggong 241
SP 1 Yinbai 181
SP 2 Dadu 182
SP 3 Taibai 183
SP 4 Gongsun 184
SP 5 Shangqiu 185
SP 6 Sanyinjiao 186
SP 7 Lougu 187
SP 8 L.I.ji 188
SP 9 Yinlingquan 189
SP 10 Xuehai 190
SP 11 Jimen 191
SP 12 SIChongmen 192
SP 13 FusHE 193
SP 14 Fujie 194
SP 15 DaHEng 195
SP 16 Fuai 196
SP 17 Shidou 197
SP 18 Tianxi 198
SP 19 Xiongxiang 199
SP 20 Zhourong 200
SP 21 Dabao 201
ST 1 CHEngqi 129
ST 2 Sibai 130
ST 3 Juliao 131
ST 4 L.I.cang 132
ST 5 Daying 133
ST 6 JiacHE 134
ST 7 Xiaguan 135
ST 8 Touwei 136
ST 9 Renying 137
ST 10 Shuitu 138
ST 11 QisHE 139
ST 12 QuePn 140
ST 13 Qihu 141
ST 14 Kufang 142
ST 15 Wuyi 143
ST 16 Yingchuang 144
ST 17 Ruzhong 145
ST 18 Rugen 146
ST 19 Burong 147
ST 20 CHEngSTn 148
ST 21 Liangmen 149
ST 22 Guanmen 150
ST 23 Taiyi 151
ST 24 Huaroumen 152
ST 25 Tianshu 153
ST 26 Wailing 154
ST 27 Daju 155
ST 28 Shuidao 156
ST 29 Guilai 157
ST 30 Qichong 158
ST 31 Biguan 159
ST 32 Futu 160
ST 33 Yinshi 161
ST 34 Liangqiu 162
ST 35 Dubi 163
ST 36 Zusanli 164
ST 37 Shangjuxu 165
ST 38 Tiaokou 166
ST 39 Xiajuxu 167
ST 40 Fenglong 168
ST 41 Jiexi 169
ST 42 Chongyang 170
ST 43 Xiangu 171
ST 44 Neiting 172
ST 45 Lidui 173

T

T.B. 1 Guanchong 367
T.B. 2 Yemen 368
T.B. 3 Zhongzhu 369
T.B. 4 Yangchi 370
T.B. 5 Waiguan 371
T.B. 6 Zhigou 372
T.B. 7 Huizong 373
T.B. 8 SanyangLUo 374
T.B. 9 Sidu 375
T.B. 10 Tianjing 376
T.B. 11 QingLIVngyuan 377
T.B. 12 XiaoLUo 378
T.B. 13 Naohui 379
T.B. 14 Jianliao 380
T.B. 15 Tianliao 381
T.B. 16 Tianyou 382
T.B. 17 Yifeng 383
T.B. 18 QiSTi 384
T.B. 19 LUxi 385
T.B. 20 Jiaosun 386
T.B. 21 Ermen 387
T.B. 22 ErHEliao 388
T.B. 23 Sizhukong 389

Acupuncture points (pinyin name)

A

AnSPan EX-HN 555

B

Bafeng Ex-LIV 10 612
Baichongwo Ex-LIV 3 605
Baihuanshu BL 30 280
Baihui Du 20 518
Baohuang BL 53 300
Baxie Ex-UE 9 595
BensHEn G.B. 13 411
Biguan ST 31 159
Binao L.I. 14 114
Bingfeng S.I. 12 234
Bizhong Ex-UE 599
Bulang KID 22 342
Burong ST 19 147

C

Changqiang Du 1 499
CHEngfu BL 36 283
CHEngguang BL 6 256
CHEngjiang Ren 24 494
CHEngjin BL 56 303
CHEngling G.B. 18 416
CHEngSTn ST 20 148
CHEngqi ST 1 129
CHEngshan BL 57 304
Chize LU 5 87
Chonggu Zhuidong EX-HN 558
Chongyang ST 42 170
Ciliao BL 32 281

D

Dabao SP 21 201
Dachangshu BL 25 275
Dadu SP 2 182
Dadun LIV 1 449
Dagukong Ex-UE 5 591
DaHE KID 12 332
DaHEng SP 15 195
DaiSTi G.B. 26 424
Daju ST 27 155
Daling P 7 359
Dangyang EX-HN 2 540
Dannang Ex-LIV 6 608
DannangL.I.an Ex-LIV 6 608
Dannangxue Ex-LIV 6 608
Danshu BL 19 269
Danzhong/Shanzhong
Ren 17 487
Daying ST 5 133
Dazhong KID 4 324
Dazhu BL 11 261
Dazhui Du 14 512
L.I.cang ST 4 132
L.I.ji SP 8 188
L.I.ngchuan Ex-B 1 573
L.I.wuhui G.B. 42 440
Dubi ST 35 163
Duiduan Du 27 525
Dushu BL 16 266
Duyin Ex-LIV 11 613

E

Erbai Ex-UE 2 588
ErHEliao T.B. 22 388
Erjian L.I. 2 102
Erjian EX-HN 6 544
Ermen T.B. 21 387

F

Feishu BL 13 263
Feiyang BL 58 305
Fengchi G.B. 20 418
Fengfu Du 16 514
Fenglong ST 40 168
Fengmen BL 12 262
Fengshi G.B. 31 429
Fuai SP 16 196
Fubai G.B. 10 408
Fufen BL 41 288
Fujie SP 14 194
Fuliu KID 7 327
FusHE SP 13 193

Futonggu KID 20 340
Futu L.I. 18 118
Futu ST 32 160
Fuxi BL 38 285
Fuyang BL 59 306

G
Ganshu BL 18 268
Gaohuang BL 43 290
Geguan BL 46 293
Geshu BL 17 267
Gongsun SP 4 184
Guanchong T.B. 1 367
GuangSPng G.B. 37 435
Guanmen ST 22 150
Guanyuan Ren 4 474
Guanyuanshu BL 26 276
Guilai ST 29 157

H
Haiquan EX-HN 11 549
Hanyan G.B. 4 402
HEL.I.ng Ex-LIV 2 604
HEgu L.I. 4 104
HEnggu KID 11 331
HEyang BL 55 302
HouL.I.ng Du 19 517
Houxi S.I. 3 225
Huagai Ren 20 490
Huangmen BL 51 298
Huangshu KID 16 336
Huantiao G.B. 30 428
Huanzhong Ex-LIV 615
Huaroumen ST 24 152
Huatuojiaji Ex-B 2 574
Huiyang BL 35 282
Huiyin Ren 1 471
Huizong T.B. 7 373
Hunmen BL 47 294

J
JiacHE ST 6 134
JiacHEngjiang EX-HN 557
Jiali EX-HN 556
Jianjing G.B. 21 419
Jianli Ren 11 481
Jianliao T.B. 14 380
Jianneiling Ex-UE 598
Jianshi P 5 357
Jianwaishu S.I. 14 236
Jianyu L.I. 15 115
JianzHEn S.I. 9 231
Jianzhongshu S.I. 15 237
Jiaosun T.B. 20 386
Jiaoxin KID 8 328
JieHExue Ex-B 582
Jiexi ST 41 169
JiSTi LIV 12 460
Jimen SP 11 191
JinG.B.ailao EX-HN 15 553
JinG.B.i EX-HN 559
Jinggu BL 64 311
Jingmen G.B. 25 423
JingSPng BL 1 251
Jingqu LU 8 90
Jinjin EX-HN 12 550
Jinmen BL 63 310
Jinsuo Du 8 506
Jiquan HE 1 207
Jiuwei Ren 15 485
Jizhong Du 6 504
Jueyinshu BL 14 264

Jugu L.I. 16 116
Juliao G.B. 29 427
Juliao ST 3 131
Juquan EX-HN 10 548
Juque Ren 14 484

K
Kongzui LU 6 88
KouHEliao L.I. 19 119
Kuangu Ex-LIV 1 603
Kufang ST 14 142
KunLUn BL 60 307

L
Lanwei Ex-LIV 7 609
Lanweixue Ex-LIV 7 609
Laogong P 8 360
Liangmen ST 21 149
Liangqiu ST 34 162
Lianquan Ren 23 493
Lidui ST 45 173
Lieque LU 7 89
Ligou LIV 5 453
Lineiting Ex-LIV 617
Lingdao HE 4 210
Lingtai Du 10 508
Lingxu KID 24 344
Lougu SP 7 187
LUoque BL 8 258
LUozHEn Ex-UE 8 594
LUxi T.B. 19 385

M
Meichong BL 3 253
SPngmen Du 4 502
Muchuang G.B. 16 414

N
Naohu Du 17 515
Naohui T.B. 13 379
Naokong G.B. 19 417
Naoshu S.I. 10 232
Neiguan P 6 358
Neihuaijian Ex-LIV 8 610
Neiting ST 44 172
Neixiyan Ex-LIV 4 606
Neiyingxiang EX-HN 9 547

P
Pangguangshu BL 28 278
Pianli L.I. 6 106
Pigen Ex-B 4 576
Pishu BL 20 270
Pohu BL 42 289
Pucan BL 61 308

Q
QianL.I.ng Du 21 519
Qiangu S.I. 2 224
Qichong ST 30 158
Qiduan Ex-LIV 12 614
Qihai Ren 6 476
Qihaishu BL 24 274
Qihu ST 13 141
QiSTi T.B. 18 384
Qimen Ex-CA 567
Qimen LIV 14 462
QingLIVngyuan T.B. 11 377
Qingling HE 2 208
QisHE ST 11 139
Qiuhou EX-HN 7 545

Qiuxu G.B. 40 438
Qixue KID 13 333
Qizhong sibian Ex-CA 565
Quanliao S.I. 18 240
Qubin G.B. 7 405
Qucha BL 4 254
Quchi L.I. 11 111
QuePn ST 12 140
Qugu Ren 2 472
Quiangjian Du 18 516
Ququan LIV 8 456
Quyuan S.I. 13 235
Quze P 3 355

R
Rangu KID 2 322
Renying ST 9 137
Renzhong Du 26 524
Riyue G.B. 24 422
Rugen ST 18 146
Ruzhong ST 17 145

S
Sanjian L.I. 3 103
Sanjiaojiu Ex-CA 570
Sanjiaoshu BL 22 272
SanyangLUo T.B. 8 374
Sanyinjiao SP 6 186
Shangguan G.B. 3 401
Shangjuxu ST 37 165
Shanglian L.I. 9 109
Shangliao BL 31 281
ShangSPng EX-HN 554
Shangqiu SP 5 185
Shangqu KID 17 337
Shangwan Ren 13 483
Shangxing Du 23 521
Shangyang L.I. 1 101
Shangyingxiang EX-HN 8 546
Shaochong HE 9 215
Shaofu HE 8 214
Shaohai HE 3 209
Shaoshang LU 11 93
Shaoze S.I. 1 223
SHEncang KID 25 345
SHEndao Du 11 509
SHEnfeng KID 23 343
SHEnSTi BL 62 309
SHEnmen HE 7 213
SHEnque Ren 8 478
SHEnshu BL 23 273
SHEntang BL 44 291
SHEnting Du 24 522
SHEnzhu Du 12 510
Shidou SP 17 197
Shiguan KID 18 338
Shimen Ren 5 475
Shiqizhui Ex-B 8 580
Shixuan Ex-UE 11 597
Shousanli L.I. 10 110
Shouwuli L.I. 13 113
Shuaigu G.B. 8 406
Shufu KID 27 347
Shugu BL 65 312
Shuidao ST 28 156
Shuifen Ren 9 479
Shuiquan KID 5 325
Shuitu ST 10 138
Sibai ST 2 130
SIChongmen SP 12 192
Sidu T.B. 9 375

Sifeng Ex-UE 10 596
SiSTn KID 14 334
Siqiang Ex-LIV 616
SisHEncong EX-HN 1 539
Sizhukong T.B. 23 389
Suliao Du 25 523

T
Taibai SP 3 183
Taichong LIV 3 451
Taixi KID 3 323
Taiyang EX-HN 5 543
Taiyi ST 23 151
Taiyuan LU 9 91
Taodao Du 13 511
Tianchi P 1 353
Tianchong G.B. 9 407
Tianchuang S.I. 16 238
TianL.I.ng L.I. 17 117
Tianfu LU 3 85
Tianjing T.B. 10 376
Tianliao T.B. 15 381
Tianquan P 2 354
Tianrong S.I. 17 239
Tianshu ST 25 153
Tiantu Ren 22 492
Tianxi SP 18 198
Tianyou T.B. 16 382
Tianzhu BL 10 260
Tianzong S.I. 11 233
Tiaokou ST 38 166
Tinggong S.I. 19 241
Tinghui G.B. 2 400
Tituo Ex-CA 568
Tongli HE 5 211
Tongtian BL 7 257
Tongziliao G.B. 1 399
Toulinqi G.B. 15 413
Touqiaoyin G.B. 11 409
Touwei ST 8 136
Tunzhong Ex-B 583

W
Waiguan T.B. 5 371
Waihuaijian Ex-LIV 9 611
Wailaogong Ex-UE 8 594
Wailing ST 26 154
Waiqiu G.B. 36 434
Wangu S.I. 4 226
Wangu G.B. 12 410
Weicang BL 50 297
Weidao G.B. 28 426
Weishang Ex-CA 564
Weishu BL 21 271
Weiwanxiashu Ex-B 3 575
Weiyang BL 39 286
Weizhong BL 40 287
Wenliu L.I. 7 107
Wuchu BL 5 255
Wushu G.B. 27 425
Wuyi ST 15 143

X
Xiabai LU 4 86
Xiaguan ST 7 135
Xiajishu Ex-B 5 577
Xiajuxu ST 39 167
Xialian L.I. 8 108
Xialiao BL 34 281
Xiangu ST 43 171
Xianqiang Ex-UE 8 594
Xiaochangshu BL 27 277

XIAOGUKONG Ex-UE 6 ... 592
XIAOHAI S.I. 8 ... 230
XIAOLUO T.B. 12 ... 378
XIAWAN Ren 10 ... 480
XIAXI G.B. 43 ... 441
XIL.I.NG Ex-LIV 2 ... 604
XIGUAN LIV 7 ... 455
XIMEN P 4 ... 356
XINGJIAN LIV 2 ... 450
XINHUI Du 22 ... 520
XINSHU BL 15 ... 265
XIONGXIANG SP 19 ... 199
XIYAN Ex-LIV 5 ... 607
XIYANGGUAN G.B. 33 ... 431
XUANJI Ren 21 ... 491
XUANLI G.B. 6 ... 404
XUANLU G.B. 5 ... 403
XUANSHU Du 5 ... 503
XUANZHONG G.B. 39 ... 437
XUEHAI SP 10 ... 190

Y

YAMEN Du 15 ... 513
YANG.B.AI G.B. 14 ... 412
YANGCHI T.B. 4 ... 370
YANGFU G.B. 38 ... 436
YANGGANG BL 48 ... 295
YANGGU S.I. 5 ... 227
YANGJIAO G.B. 35 ... 433
YANGLAO S.I. 6 ... 28
YANGLINGQUAN G.B. 34 ... 432
YANGXI L.I. 5 ... 105
YAOQI Ex-B 9 ... 581
YAOSHU Du 2 ... 500
YAOTONGL.I.AN Ex-UE 7 ... 593
YAOYAN Ex-B 7 ... 579
YAOYANGGUAN Du 3 ... 501
YAOYI Ex-B 6 ... 578
YEMEN T.B. 2 ... 368
YIFENG T.B. 17 ... 383
YIJING Ex-CA ... 566
YISPNG EX-HN 14 ... 552
YINBAI SP 1 ... 181
YINBAO LIV 9 ... 457
YINDU KID 19 ... 339
YINGCHUANG ST 16 ... 144
YINGU KID 10 ... 330
YINGXIANG L.I. 20 ... 120
YINJIAO Ren 7 ... 477
YINLIAN LIV 11 ... 459
YINLIAO Du 28 ... 526
YINLINGQUAN SP 9 ... 189
YINMEN BL 37 ... 284
YINSHI ST 33 ... 161
YINTANG EX-HN 3 ... 541
YINXI HE 6 ... 212
YISHE BL 49 ... 296
YIXI BL 45 ... 292
YONGQUAN KID 1 ... 321
YOUMEN KID 21 ... 341
YUANYE G.B. 22 ... 420
YUJI LU 10 ... 92
YUNMEN LU 2 ... 84
YUTANG Ren 18 ... 488
YUYAO EX-HN 4 ... 542
YUYE EX-HN 13 ... 551
YUZHEN BL 9 ... 259
YUZHONG KID 26 ... 346

Z

ZANZHU BL 2 ... 252
ZHANGMEN LIV 13 ... 461
ZHAOHAI KID 6 ... 326
ZHEJIN G.B. 23 ... 421
ZHENGYING G.B. 17 ... 415
ZHIBIAN BL 54 ... 301
ZHIGOU T.B. 6 ... 372
ZHISHI BL 52 ... 299
ZHISHI Ex-CA ... 569
ZHIYANG Du 9 ... 507
ZHIYIN BL 67 ... 314
ZHIZHENG S.I. 7 ... 229
ZHONGCHONG P 9 ... 361
ZHONGDU G.B. 32 ... 430
ZHONGDU LIV 6 ... 454
ZHONGFENG LIV 4 ... 452
ZHONGFU LU 1 ... 83
ZHONGJI Ren 3 ... 473
ZHONGKUI Ex-UE 4 ... 590
ZHONGLIAO BL 33 ... 281
ZHONGLÜSHU BL 29 ... 279
ZHONGQUAN Ex-UE 3 ... 589
ZHONGSHU Du 7 ... 505
ZHONGTING Ren 16 ... 486
ZHONGWAN Ren 12 ... 482
ZHONGZHU KID 15 ... 335
ZHONGZHU T.B. 3 ... 369
ZHOUJIAN Ex-UE 1 ... 587
ZHOULIAO L.I. 12 ... 112
ZHOURONG SP 20 ... 200
ZHUBIN KID 9 ... 329
ZIGONG Ren 19 ... 489
ZULINQI G.B. 41 ... 439
ZUQIAOYIN G.B. 44 ... 442
ZUSANLI ST 36 ... 164
ZUTONGGU BL 66 ... 313
ZUWULI LIV 10 ... 458

Index of Indications, the effectiveness of which has been scientifically proven or disproven

A

Abdominal surgery, bowel movements following ... 705
Absorption of Tc-99m (radioactive technetium-marker) ... 709
Activation of neutrophils ... 702
Activity of the sympathetic and parasympathetic nervous system ... 700, 718
Acupuncture anaesthesia for hysterectomies ... 718
Adhesive capsulitis (‘Frozen shoulder’) ... 702
Anaesthetic requirement ... 715
Anaesthetic requirement for subtotal gastrectomies ... 705
Anaesthesia by electroacupuncture ... 705
Anaesthetic requirement (desflurane) ... 704, 715
Analgesia for operative dentistry ... 701
Analgesia for thyroidectomies ... 714
Analgesia, patient-controlled (requirement for hydromorphine) ... 701
Analgesic effect ... 701, 704, 716
Analgesic requirement after abdominal surgery ... 707, 711
Angina pectoris ... 713, 714, 718
Anxiety ... 719
Apoplexy ... 699
Appendectomies ... 705
Arthritis, rheumatoid ... 717
Asthma, allergic ... 699
Asthma, anaphylactic ... 704
Asthma, bronchial ... 699, 709, 719
Atropin-induced gastric dysrhythmia ... 704

B

Biliary colic pain ... 717
Bloating ... 707
Blood circulation, peripheral ... 705
Blood loss during cerebral operation ... 706
Bowel movements following abdominal surgery ... 705
Brain activation patterns, changes in ... 700, 709
Breast cancer, nausea due to chemotherapy ... 704
Breast surgery, emesis after ... 711
Breech presentation ... 707, 709
Bronchial asthma ... 699, 709, 719
Bronchial asthma in children ... 709
Bronchitis, chronic ... 721

C

Cancer patients ... 705, 713
Carbon dioxide production ... 713
Cardia, achalasia of the ... 716
Cardiotocographic parameters, foetal and maternal ... 719
Cerebral blood flow capacity, impaired and cervical vertebra disease ... 719
Cerebral infarction, acute ... 702, 718
Cerebral infarction, ischaemic ... 715
Cerebral operation, blood loss during ... 706
Cerebral traumatic dementia ... 706
Cervical vertebra disease and impaired cerebral blood flow capacity ... 718
Caesarean section, nausea and vomiting after epidural morphine for ... 713
c-Fos-positive cells in the primary visual cortex ... 709
Changes in brain activation patterns ... 700
CHD (coronary heart disease) ... 711, 712, 713, 718
CHD patients ... 714, 718
Chemotherapy, nausea and vomiting ... 704, 711, 714
Chemotherapy-induced leukopenia ... 704, 705
Chronic pelvic pain syndrome with intrapelvic venous congestion ... 708
Cold, tonic pain induced by ... 700
Colitis, chronic ... 703
Colonoscopy, analgesic effect for ... 701
Concentration, minimal alveolar ... 701
Constipation ... 701, 707
Contraction, uterine ... 705
Coronary heart disease ... 710
Cutaneous blood flow ... 700, 711
Cyclophosphamide chemotherapy, vomiting ... 711
Cystitis, interstitial ... 705

D

Dementia, cerebral traumatic ... 706
Dental pain, postoperative ... 701
Depression ... 706, 719
Desflurane anaesthesia, experimental pain stimuli under ... 704
Desflurane anaesthesia, pain stimuli under ... 704
Diabetic patients with gastric motor dysfunction ... 704
Diarrhoea ... 707, 716, 717
Discectomy, analgesia for anterior approach cervical ... 713
Driving fatigue ... 719
Duodenal ulcer ... 715
Dysmenorrhoea (painful periods) ... 719

E

EEG, resting ... 700
Effect, pain-reducing ... 704
Electro-acupuncture, anaesthesia with ... 705
ENT surgery, postoperative nausea and vomiting ... 712, 714
Enteropathogenic Escherichia coli induced diarrhoea ... 718
Enuresis ... 718
Epicondalgia lateralis (tennis elbow) ... 701. 702, 716
Epidural anaesthesia for gastrectomies ... 705
Epidural morphine, nausea and vomiting after, for post-caesarean section ... 713
Epigastric pain ... 720
Epiphora (tearing eyes) ... 706
Essential hypertension ... 709
Exhaustion ... 700
Extrasystole, intermittent ventricular ... 711

F

Facial paralysis ... 716
Faecal incontinence ... 708
Fever ... 699, 709
Finger flexion reflex, vibration induced ... 701
fMRI ... 709, 716, 717
fMRI in stroke patients ... 716

XIAOGUKONG Ex-UE 6 . . . 592
XIAOHAI S.I. 8 . . . 230
XIAOLUO T.B. 12 . . . 378
XIAWAN Ren 10 . . . 480
XIAXI G.B. 43 . . . 441
XIL.I.NG Ex-LIV 2 . . . 604
XIGUAN LIV 7 . . . 455
XIMEN P 4 . . . 356
XINGJIAN LIV 2 . . . 450
XINHUI Du 22 . . . 520
XINSHU BL 15 . . . 265
XIONGXIANG SP 19 . . . 199
XIYAN Ex-LIV 5 . . . 607
XIYANGGUAN G.B. 33 . . . 431
XUANJI Ren 21 . . . 491
XUANLI G.B. 6 . . . 404
XUANLU G.B. 5 . . . 403
XUANSHU Du 5 . . . 503
XUANZHONG G.B. 39 . . . 437
XUEHAI SP 10 . . . 190

Y

YAMEN Du 15 . . . 513
YANG.B.AI G.B. 14 . . . 412
YANGCHI T.B. 4 . . . 370
YANGFU G.B. 38 . . . 436
YANGGANG BL 48 . . . 295
YANGGU S.I. 5 . . . 227
YANGJIAO G.B. 35 . . . 433
YANGLAO S.I. 6 . . . 28
YANGLINGQUAN G.B. 34 . . . 432
YANGXI L.I. 5 . . . 105
YAOQI Ex-B 9 . . . 581
YAOSHU Du 2 . . . 500
YAOTONGL.I.AN Ex-UE 7 . . . 593
YAOYAN Ex-B 7 . . . 579
YAOYANGGUAN Du 3 . . . 501
YAOYI Ex-B 6 . . . 578
YEMEN T.B. 2 . . . 368
YIFENG T.B. 17 . . . 383
YIJING Ex-CA . . . 566
YISPNG EX-HN 14 . . . 552
YINBAI SP 1 . . . 181
YINBAO LIV 9 . . . 457
YINDU KID 19 . . . 339
YINGCHUANG ST 16 . . . 144
YINGU KID 10 . . . 330
YINGXIANG L.I. 20 . . . 120
YINJIAO Ren 7 . . . 477
YINLIAN LIV 11 . . . 459
YINLIAO Du 28 . . . 526
YINLINGQUAN SP 9 . . . 189
YINMEN BL 37 . . . 284
YINSHI ST 33 . . . 161
YINTANG EX-HN 3 . . . 541
YINXI HE 6 . . . 212
YISHE BL 49 . . . 296
YIXI BL 45 . . . 292
YONGQUAN KID 1 . . . 321
YOUMEN KID 21 . . . 341
YUANYE G.B. 22 . . . 420
YUJI LU 10 . . . 92
YUNMEN LU 2 . . . 84
YUTANG Ren 18 . . . 488
YUYAO EX-HN 4 . . . 542
YUYE EX-HN 13 . . . 551
YUZHEN BL 9 . . . 259
YUZHONG KID 26 . . . 346

Z

ZANZHU BL 2 . . . 252
ZHANGMEN LIV 13 . . . 461
ZHAOHAI KID 6 . . . 326
ZHEJIN G.B. 23 . . . 421
ZHENGYING G.B. 17 . . . 415
ZHIBIAN BL 54 . . . 301
ZHIGOU T.B. 6 . . . 372
ZHISHI BL 52 . . . 299
ZHISHI Ex-CA . . . 569
ZHIYANG Du 9 . . . 507
ZHIYIN BL 67 . . . 314
ZHIZHENG S.I. 7 . . . 229
ZHONGCHONG P 9 . . . 361
ZHONGDU G.B. 32 . . . 430
ZHONGDU LIV 6 . . . 454
ZHONGFENG LIV 4 . . . 452
ZHONGFU LU 1 . . . 83
ZHONGJI Ren 3 . . . 473
ZHONGKUI Ex-UE 4 . . . 590
ZHONGLIAO BL 33 . . . 281
ZHONGLÜSHU BL 29 . . . 279
ZHONGQUAN Ex-UE 3 . . . 589
ZHONGSHU Du 7 . . . 505
ZHONGTING Ren 16 . . . 486
ZHONGWAN Ren 12 . . . 482
ZHONGZHU KID 15 . . . 335
ZHONGZHU T.B. 3 . . . 369
ZHOUJIAN Ex-UE 1 . . . 587
ZHOULIAO L.I. 12 . . . 112
ZHOURONG SP 20 . . . 200
ZHUBIN KID 9 . . . 329
ZIGONG Ren 19 . . . 489
ZULINQI G.B. 41 . . . 439
ZUQIAOYIN G.B. 44 . . . 442
ZUSANLI ST 36 . . . 164
ZUTONGGU BL 66 . . . 313
ZUWULI LIV 10 . . . 458

Index of Indications, the effectiveness of which has been scientifically proven or disproven

A

Abdominal surgery, bowel movements following . . . 705
Absorption of Tc-99m (radioactive technetium-marker) . . 709
Activation of neutrophils . . . 702
Activity of the sympathetic and parasympathetic nervous system . . . 700, 718
Acupuncture anaesthesia for hysterectomies . . . 718
Adhesive capsulitis (‘Frozen shoulder’) . . . 702
Anaesthetic requirement . . . 715
Anaesthetic requirement for subtotal gastrectomies . . . 705
Anaesthesia by electroacupuncture . . . 705
Anaesthetic requirement (desflurane) . . . 704, 715
Analgesia for operative dentistry . . . 701
Analgesia for thyroidectomies . . . 714
Analgesia, patient-controlled (requirement for hydromorphine) . . . 701
Analgesic effect . . . 701, 704, 716
Analgesic requirement after abdominal surgery . . . 707, 711
Angina pectoris . . . 713, 714, 718
Anxiety . . . 719
Apoplexy . . . 699
Appendectomies . . . 705
Arthritis, rheumatoid . . . 717
Asthma, allergic . . . 699
Asthma, anaphylactic . . . 704
Asthma, bronchial . . . 699, 709, 719
Atropin-induced gastric dysrhythmia . . . 704

B

Biliary colic pain . . . 717
Bloating . . . 707
Blood circulation, peripheral . . . 705
Blood loss during cerebral operation . . . 706
Bowel movements following abdominal surgery . . . 705
Brain activation patterns, changes in . . . 700, 709
Breast cancer, nausea due to chemotherapy . . . 704
Breast surgery, emesis after . . . 711
Breech presentation . . . 707, 709
Bronchial asthma . . . 699, 709, 719
Bronchial asthma in children . . . 709
Bronchitis, chronic . . . 721

C

Cancer patients . . . 705, 713
Carbon dioxide production . . . 713
Cardia, achalasia of the . . . 716
Cardiotocographic parameters, foetal and maternal . . . 719
Cerebral blood flow capacity, impaired and cervical vertebra disease . . . 719
Cerebral infarction, acute . . . 702, 718
Cerebral infarction, ischaemic . . . 715
Cerebral operation, blood loss during . . . 706
Cerebral traumatic dementia . . . 706
Cervical vertebra disease and impaired cerebral blood flow capacity . . . 718
Caesarean section, nausea and vomiting after epidural morphine for . . . 713
c-Fos-positive cells in the primary visual cortex . . . 709
Changes in brain activation patterns . . . 700
CHD (coronary heart disease) . . . 711, 712, 713, 718
CHD patients . . . 714, 718
Chemotherapy, nausea and vomiting . . . 704, 711, 714
Chemotherapy-induced leukopenia . . . 704, 705
Chronic pelvic pain syndrome with intrapelvic venous congestion . . . 708
Cold, tonic pain induced by . . . 700
Colitis, chronic . . . 703
Colonoscopy, analgesic effect for . . . 701
Concentration, minimal alveolar . . . 701
Constipation . . . 701, 707
Contraction, uterine . . . 705
Coronary heart disease . . . 710
Cutaneous blood flow . . . 700, 711
Cyclophosphamide chemotherapy, vomiting . . . 711
Cystitis, interstitial . . . 705

D

Dementia, cerebral traumatic . . . 706
Dental pain, postoperative . . . 701
Depression . . . 706, 719
Desflurane anaesthesia, experimental pain stimuli under . . . 704
Desflurane anaesthesia, pain stimuli under . . . 704
Diabetic patients with gastric motor dysfunction . . . 704
Diarrhoea . . . 707, 716, 717
Discectomy, analgesia for anterior approach cervical . . . 713
Driving fatigue . . . 719
Duodenal ulcer . . . 715
Dysmenorrhoea (painful periods) . . . 719

E

EEG, resting . . . 700
Effect, pain-reducing . . . 704
Electro-acupuncture, anaesthesia with . . . 705
ENT surgery, postoperative nausea and vomiting . . . 712, 714
Enteropathogenic Escherichia coli induced diarrhoea . . . 718
Enuresis . . . 718
Epicondalgia lateralis (tennis elbow) . . . 701. 702, 716
Epidural anaesthesia for gastrectomies . . . 705
Epidural morphine, nausea and vomiting after, for post-caesarean section . . . 713
Epigastric pain . . . 720
Epiphora (tearing eyes) . . . 706
Essential hypertension . . . 709
Exhaustion . . . 700
Extrasystole, intermittent ventricular . . . 711

F

Facial paralysis . . . 716
Faecal incontinence . . . 708
Fever . . . 699, 709
Finger flexion reflex, vibration induced . . . 701
fMRI . . . 709, 716, 717
fMRI in stroke patients . . . 716

Foetal breech presentation 709
Forms of anaesthesia for anterior approach cervical discectomy..... 712
'Frozen shoulder' (adhesive capsulitis) 702

G
Gag reflex.................... 720
Gastrectomies, epidural anaesthesia for 705
Gastric dysrhythmia, atropine-induced.............. 704
Gastric motor dysfunction in diabetic patients 704
Gastric myoelectrical regularity ... 704
Gastrointestinal motility following trans-abdominal hysterectomy 711

H
Haemodynamics............... 705
Headaches after caesarian section under epidural anaesthesia 703
Headaches................ 703, 717
Heart disease, coronary 710, 712, 713, 714, 718
Heart rate frequency, variance of 720
Heart rate variability............ 703
Heart rate variability (HRV) under fatigue and non-fatigue states..... 700
Heat pain threshold............ 700
Hemiplegia............... 706, 716
Heroin withdrawal 712, 715
Hiccups..................... 721
HIV-related neuropathy 708
Homeostatic effect of this point ... 710
Hospice patients, nausea and vomiting in................ 714
H-reflex...................... 700
Hyperemesis gravidarum (morning sickness) 711
Hypertension, diastolic.......... 717
Hypertension, essential.......... 709
Hypertension, exercise-induced ... 710
Hypertension, forms of.......... 707
Hyperthyreosis 720
Hypogalactia.................. 717
Hypotension, controlled 706
Hypotension under general anaesthesia with halothane....... 703
Hysterectomy, trans-abdominal, gastrointestinal motility 711

I
Ileus, paralytic 707
Immune system................ 702
Immune system, effects on....... 699
Immuno-activity of NK cells 705
Incontinence in spinal-cord-injured patients 708
Induced labour 700, 705
Infarction, cerebral 702, 715, 718
Insufficiency of lacrimal passage 706
Intrapelvic venous congestion, chronic pelvic pain syndrome with 708
Irritable bowel syndrome 700
Ischaemia, transient 718

K
Knees, osteoarthritic........ 703, 705

L
Laparoscopy, gynaecological, vomiting and nausea following................ 713, 714
Laryngospasms................ 699
Leukocyte circulation........... 703
Leukopenia.................. 704
Leukopenia, chemotherapy-induced.................. 704, 705
Lumbar pain.................. 708

M
Migraine attacks............... 717
Migraines without aura.......... 703
Minor depression or anxiety.. 705, 706
Minor depression 705, 706
Morbid infantile night crying 715
Morning sickness...... 710, 711, 712, 713, 714
Motion sickness ... 710, 712, 713, 714
Myocardial infarction....... 710, 711

N
Nasal airflow 702
Nasopharyngeal carcinoma 720
Nausea and vomiting after paediatric strabismus surgery.. 712, 714
Nausea and vomiting during caesarean delivery under spinal anaesthesia.......... 710, 713
Nausea and gagging during gastroscopies 711
Nausea and vomiting, postoperative and chemotherapy-induced 704–714
Nausea induced by eccentric rotation 710
Nerve activity, sympathetic 702
Neurogenic bladder due spinal cord injury 720
Neuropathy, HIV-related......... 708
Neuroradiological changes....... 709
Nucleus gracilis, activity of nitric oxide synthase in the....... 708

O
Obesity...................... 719
Obesity in women............. 699
Opioid requirement......... 700, 704
Opioid-related side effects,....... 703
Oxygen requirement........... 713

P
Pain stimuli, experimental 704, 707, 718
Pain stimuli, experimental, under desflurane anaesthesia 704
Pain threshold of postoperative dental pain 701
Pain threshold............. 701, 717
Pain 700, 701 703, 708, 711
Painful disorders.............. 704
Palsy, pseudobulbar 720
Paralytic ileus 707
Parasympathetic activity......... 719
Patients with acute myocardial infarction 710, 711
Perennial allergic rhinitis 719
Periarthritis of the humerus 699
Peripheral blood circulation 705
Peristalsis 704
Phagocytic immune system, activity of neutrophils........... 702
Plasma glucose level............ 721
Poly-infarctional vascular dementia.................... 700
Positive chronotropic and bathmotropic effect............ 710
Postoperative nausea and vomiting............. 711, 712
Postoperative nausea and vomiting after gynaecological surgery 711, 712, 713, 714, 715
Postoperative nausea and vomiting after plastic surgery..... 711
Postoperative nausea and vomiting after urological surgery 713
Postoperative nausea following paediatric tonsillectomy 710, 712, 714
Post-partum urinary retention..... 708
Potentials, auditory endogenous.................. 704
Potentials, somatosensory evoked....................... 717
Pseudobulbar palsy............. 720
Pulse, components 705

R
Raynaud syndrome............. 700
Regulation of cellular immune function.............. 713
Resting heart rate 713

S
Sciatica...................... 721
Seizures 718
Severe spinal cord injuries 706
Shoulder and back pain 721
Side effects, opioid-related .. 701, 704
Sleeping disorders 721
Somatosensory evoked Potentials 717
Spasticity due to stroke.......... 700
Estimated date of confinement (EDC) 700
Spinal cord injury.......... 706, 718
Spinal-cord-injured patients, incontinence in................ 708
Strabism surgery in children, nausea and vomiting after ... 712, 714
Stress parameters 706
Surgery, minor gynaecological, nausea and vomiting after........ 712
Surgery, minor urological in paediatric patients............ 713
Surgery, plastic, vomiting and nausea following 711
Sympathetic nerve activity 701
Sympathetic nervous system, activation of the 719

T
Tc-99 (radioactive technetium marker), absorption of 709
Tenesmus 707
Tennis elbow............. 701, 702
Thermal pain thresholds......... 705
Thyroidectomies, analgesia for ... 714
Tonic pain................... 700
Tooth pain............... 701, 702
Torticollis.................... 706
Tumours, malignant 705, 713

U
Ulcerative colitis.............. 721
Uraemic pruritus.............. 701
Urinary incontinence 708
Urinary retention, post-partum.... 708

V
Vascular dementia.......... 719, 720
Visual cortex, c-Fos-positive cells in the.................... 709
Vomiting................ 710–715
Vomiting, postoperative 710–714

W
Wisdom tooth extraction, pain after..................... 700
Withdrawal symptoms of heroin addicts........... 712, 715
Word generation............... 715

Overview: Specific Point Categories

Channel Maximum time	Points	*jing*-Well point	*ying*-Spring point	*shu*-Stream point	*jing*-River point	*he*-Sea point	Tonification point	*ben* point	Sedation point	*yuan*-Source point	*luo*-Connecting point	*xi*-Cleft point	Back-*shu* point	Front-*mu* point
Yin		Wood	Fire	Earth	Metal	Water								
Hand-*Yin*	Lung 3–5 am	LU-11 *shaoshang*	LU-10 *yuji*	LU-9 *taiyuan*	LU-8 *jingqu*	LU-5 *chize*	LU-9 *taiyuan*	LU-8 *jingqu*	LU-5 *chize*	LU-9 *taiyuan*	LU-7 *lieque*	LU-6 *kongzui*	BL-13 *feishu*	LU-1 *zhongfu*
	Pericardium 7–9 pm	P-9 *zhongchong*	P-8 *laogong*	P-7 *daling*	P-5 *jianshi*	P-3 quze	P-9 *zhongchong*	P-8 *laogong*	P-7 *daling*	P-7 *daling*	P-6 *neiguan*	P-4 *ximen*	BL-14 *jueyinshu*	Ren-17 *danzhong*
	Heart 11 am–1 pm	HE-9 *shaochong*	HE-8 *shaofu*	HE-7 *shenmen*	HE-4 *lingdao*	HE-3 *shaohai*	HE-9 *shaochong*	HE-8 *shaofu*	HE-7 *shenmen*	HE-7 *shenmen*	HE-5 *tongli*	HE-6 *yinxi*	BL-15 *xinshu*	Ren-14 *juque*
Foot-*Yin*	Spleen 9–11am	SP-1 *yinbai*	SP-2 *dadu*	SP-3 *taibai*	SP-5 *shangqiu*	SP-9 *yinlingquan*	SP-2 *dadu*	SP-3 *taibai*	SP-5 *shangqiu*	SP-3 *taibai*	SP-4 *gongsun*	SP-8 *diji*	BL-20 *pishu*	LIV-13 *zhangmen*
	Liver 1–3 am	LIV-1 *dadun*	LIV-2 *xingjian*	LIV-3 *taichong*	LIV-4 *zhongfeng*	LIV-8 *ququan*	LIV-8 *ququan*	LIV-1 *dadun*	LIV-2 *xingjian*	LIV-3 *taichong*	LIV-5 *ligou*	LIV-6 *zhongdu*	BL-18 *ganshu*	LIV-14 *qimen*
	Kidney 5–7 pm	KID-1 *yongquan*	KID-2 *rangu*	KID-3 *taixi*	KID-7 *fuliu*	KID-10 *yingu*	KID-7 *fuliu*	KID-10 *yingu*	KID-1 *yongquan*	KID-3 *taixi*	KID-4 *dazhong*	KID-5 *shuiquan*	BL-23 *shenshu*	G.B.-25 *jingmen*
Yang		Metal	Water	Wood	Fire	Earth								
Hand-*Yang*	Large Intestine 5–7 pm	L.I.-1 *shangyang*	L.I.-2 *erjian*	L.I.-3 *sanjian*	L.I.-5 *yangxi*	L.I.-11 *quchi*	L.I.-11 *quchi*	L.I.-1 *shangyang*	L.I.-2 *erjian*	L.I.-4 *hegu*	L.I.-6 *pianli*	L.I.-7 *wenliu*	BL-25 *dachangshu*	ST-25 *tianshu*
	Triple Burner 9–11 pm	T.B.-1 *guanchong*	T.B.-2 *yemen*	T.B.-3 *zhongzhu*	T.B.-6 *zhigou*	T.B.-10 *tianjing*	T.B.-3 *zhongzhu*	T.B.-6 *zhigou*	T.B.-10 *tianjing*	T.B.-4 *yangchi*	T.B.-5 *waiguan*	T.B.-7 *huizong*	BL-22 *sanjiaoshu*	Ren-5 *shimen*
	Small Intestine 1–3 pm	S.I.-1 *shaoze*	S.I.-2 *qiangu*	S.I.-3 *houxi*	S.I.-5 *yanggu*	S.I.-8 *xiaohai*	S.I.-3 *houxi*	S.I.-5 *yanggu*	S.I.-8 *xiaohai*	S.I.-4 *wangu*	S.I.-7 *zhizheng*	S.I.-6 *yanglao*	BL-27 *xiaochangshu*	Ren-4 *guanyuan*
Foot-*Yang*	Stomach 7–9 am	ST-45 *lidui*	ST-44 *neiting*	ST-43 *xiangu*	ST-41 *jiexi*	ST-36 *zusanli*	ST-41 *jiexi*	ST-36 *zusanli*	ST-45 *lidui*	ST-42 *chongyang*	ST-40 *fenglong*	ST-34 *liangqiu*	BL-21 *weishu*	Ren-12 *zhongwan*
	Gall Bladder 11 pm–1 am	G.B.-44 *zuqiaoyin*	G.B.-43 *xiaxi*	G.B.-41 *zulinqi*	G.B.-38 *yangfu*	G.B.-34 *yanglingquan*	G.B.-43 *xiaxi*	G.B.-41 *zulinqi*	G.B.-38 *yangfu*	G.B.-40 *qiuxu*	G.B.-37 *guangming*	G.B.-36 *waiqiu*	BL-19 *danshu*	G.B.-24 *riyue*
	Bladder 3–5 pm	BL-67 *zhiyin*	BL-66 *zutonggu*	BL-65 *shugu*	BL-60 *kunlun*	BL-40 *weizhong*	BL-67 *zhiyin*	BL-66 *zutonggu*	BL-65 *shugu*	BL-64 *jinggu*	BL-58 *feiyang*	BL-63 *jinmen*	BL-28 *pangguangshu*	Ren-3 *zhongji*

Tissue	*zang*-Organs	*fu*-Organs	Qi	Blood (*xue*)	Tendons	Vessels	Bones	Marrow
hui-Meeting point	LIV-13 *zhangmen*	Ren-12 *zhongwan*	Ren-17 *danzhong*	BL-17 *geshu*	G.B.-34 *yanglingquan*	LU-9 *taiyuan*	BL-11 *dazhu*	G.B.-39 *xuanzhong*
Extraordinary Vessel	*chong mai*	*yin wei mai*	*du mai*	*yang qiao mai*	*dai mai*	*yang wei mai*	*ren mai*	*yin qiao mai*
Opening point/Coupled point	SP-4/P-6 *gongsun/neiguan*	P-6/SP-4 *neiguan/gongsun*	S.I. 3/BL-62 *houxi/shenmai*	BL-62/S.I. 3 *shenmai/houxi*	G.B.-41/T.B.-5 *zulinqi/waiguan*	T.B.-5/G.B.-41 *waiguan/zulinqi*	LU-7/KID-6 *lieque/zhaohai*	KID-6/LU-7 *zhaohai/lieque*

fu-Organ	Large Intestine	Triple Burner	Small Intestine	Stomach	Gall Bladder	Bladder
Lower *he*-Sea point	ST-37 *shangjuxu*	BL-39 *weiyang*	ST-39 *xiajuxu*	ST-36 *zusanli*	G.B.-34 *yanglingquan*	BL-40 *weizhong*

THE KATHARA™

Bio-Spiritual Healing System

LEVEL 1 CERTIFICATE PROGRAM

by A'sha-yana Deane

The Kathara™ Bio-Spiritual Healing System
is supplied by the Azurite Press of the Melchizedek Cloister Emerald Order

All Materials ©1999-2002 inc. A'sha-yana Deane, Eckr MCEO All Rights Reserved

KATHARA

BIO-SPIRITUAL HEALING SYSTEM

CERTIFICATE PROGRAM

The Maharic Recoding Process

LEVEL - 1
SESSION MANUAL

FOR FACILITATOR-INSTRUCTORS

FOUNDATIONS OF KATHARA HEALING™
KATHARA HEALING ™ FACILITATION
THE MAHARIC RECODING PROCESS ™

An advanced *Spiritual Healing Certificate Program* based upon KEYLONTIC MORPHOGENETIC SCIENCE. Sponsored by the **Kathara Alliance**–an associate of the Azurite Press World-wide Consulate. All Materials © 1/2000, 2001, 2002 Ashayana Deane, Eckr. MCEO–All Rights Reserved

Table of Contents

Chapter 1: **THE CONTEXT OF HEALING -** 7- 47
Structure of the Unified Field and the Multi-dimensional Anatomy of Form
Chapter Highlights 37

Chapter 2: **THE ELEMENTS OF HEALING** ....48 - 112
The Human Body Kathara and the Multi-dimensional Anatomy of the Human Form
Chapter Highlights..102

Chapter 3: **KATHARA HEALING BEGINNING APPLICATIONS** 113-165
Creating Field Integrity and Building the Knowledge Base
Chapter Highlights..149

Chapter 4: **GENERAL KATHARA HEALING FIELD WORK** 166-211
Skills to Facilitate Healing
Chapter Highlights 204

Topics and Techniques Locator Index

Chapter 1: The Context of Healing ....Pages 7-47
Structure of the Unified Field and the Multi-dimensional Anatomy of Form...8-9
* The Holographic Template..10-14
* The Structure of Dimensions, Partiki Phasing and Matter Density 15-25
* Universal and Planetary Kathara Grids, the 12-Tree, Kathara Centers and Lines, Scalar Shields, Crystal Seals and Diodic Points 26-31
* The Universal and Internal Templar Complexes...32-34
* The Transduction Sequence and Holographic Reality Construction...........................35-36
Highlights..**37-47**

Chapter 2: The Elements of Healing ....Pages 48-112
Human Body Kathara: Multi-dimensional Anatomy of the Human Form... ...49-50
* The Maharic Shield and the Imprint for Health...51-52
* The Planetary Bio-feed Interface System (PBIS) 53-54
* The Hierophant Symbol Code, PBIS, the Maharic Shield.......................................55-57
* Morphogenetic Expansion, Growth Cycles, Death, Molecular Compaction....................58-62
* Levels of Human Anatomy, Embodied Kathara 12-Tree Grid, Crystal Shields, Seals, Signets, Hova Bodies, Auric Capsules, Diodic Points, Seed Seals, Chakras, Axiom Lines, the Hara Level, DNA and Merkaba 63-93
* The 12 Human Senses, Apparthi and Human Perception..94-101
Highlights..**102-112**

Chapter 3: Kathara Healing Beginning Applications .... Pages 113-165

Creating Field Integrity and Building the Knowledge Base

* Tapping the Inner Mentor and Awakening the 6th and 7th Senses...............................114-120
Technique-1: Awakening the Mentor and the 6th and 7th Senses 117-120
* Morphogenetic Repatterning, Frequency Sub-Harmonics, Maharic Seal........................121-125
* Kathara Points and Kathara Point Sequences...126-131
***Sequence-1* Kathara Points for Regeneration 128-129**
***Sequence-2* Kathra Points for Revitalization 130-131**
Technique-2: The Maharic Seal and the Liquid Light Cleanse 132-137
* Opening the PBIS and the Maharic Seal, the Structure of Multi-dimensional Identity and the 4 Primary Triadic Healing Currents...138-148
Highlights **149-165**

Chapter 4: General Kathara Healing Field Work ....Pages 166-211

Skills to Facilitate Healing

* Opening the Healing Channels-Doradic-Phase-1 Current, the Doradic Sphere, Doradic Cords and Doradic Balls..167-174
Technique-3: Opening the Healing Channels-Doradic-Phase-1 Current.......175-177
* The Karmic-Miasmic Imprint Incarnational Time Vectors, Vector Imbedding.................178-180
* Multi-Vector Holographic Recoding through the Maharic Infusion..............................181-183
Technique-4: Multi-Vector Holographic Recoding Kathara Scan.................184-186
Technique-5: The Maharic Infusion 187-190
* Attitudes and Etiquette in Healing, the Motivation to Heal, Postures of Love, the Framework for Healing, and Fully Engaging the Love Vibration 191-197
Exercise-Client Greeting: The Mahara-Space Comfort Touch 198-199
* The 6-Step Maharic Recoding Session, Melchizedek Cloister Ordination and Becoming a Professional Spiritual Healing Facilitator-Instructor..200-203
6-Step Client Maharic Recoding Session: and Client Agreement Form...........**202-203**
Highlights **204-211**

Introduction to Kathara Level 2 Mentor – Healing Applications
MERKABIC RADIAL BODY HEALING

Topics and Techniques Locator Index

Chapter – 5: Mahara-Merkabic Master Key Healing – Manifesting the Blueprint for Health, Primal Currents, the DNA sub-Strand Matrix, Merkaba, Psonns, the Trinity Keys and Photo-Dynamic Manifesting

- Universal Life Force Currents .... 214 – 220
- DNA, Fire Letters, the Tribal Shield, Cue Zones .... 221 – 228
- **Technique – 6: The Maharic Quick Seal** 226
- **Technique – 7: Ps – 13 Tribal Shield Activation** .... 227 – 228
- Merkaba Activation, Solar & Lunar Salutations .... 229 – 237
- **Technique – 8: Merkaba Salutation** .... 235 – 236
- DNA, Khundaray Activation, Emerald & Amethyst Awakenings .... 237 – 241
- **Technique – 12: Kee-Ra-ShA Activation Sequence** .... 242 – 247
- Universal Trinity Keys & Merkaba Key Codes 248
- **Technique – 9: Merkaba Trinity Key Induction** 249
- Merkabic Healing .... 251 – 255
- Introduction to the Radial Body Trion-Meajhe Field .... 256 – 257
- The Radial Body Transduction Sequence .... 258 – 262
- Radial Body Healing .... 263 – 266
- The Radial Body and the Merkaba Vehicle .... 267 – 272
- Radial Body Healing and Veca Codes .... 273 – 276
- **Technique – 10: Restoring the Trion Field-Photo Radionic Veca Healing** 277 – 278
- **Technique – 11: Restoring the Meajhe Field-Photosonic Eckasha Healing** 279 – 280
- **Technique – 13: The Song of Lyra, Christos Invocation** .... 281 – 282

Diagrams Locator Index

- **Universal Life Force Currents & the 15 Dimensional Time Matrix** 214
- **Universal Life Force Currents & the Embodied Kathara Grid** 215
- **Universal Life Force Currents, Crystal Seals & Chakras** 216
- **Universal Life Force Currents, Hova Bodies & Auric Levels** 217
- **Universal Life Force Currents, Shields, Signets & Kathara** 218
- **Primal Currents, Silicate Matrix DNA & Subtle Body Anatomy** 219
- **Universal Life Force Currents & DNA Fire Letter Sequences** 220
- **Silicate Matrix DNA & Fire Letters** 222
- **The Tribal Shield Species & Divine Blueprint** 224
- **The Natural Nethra Phase Density 1 Merkaba** 233
- **Merkaba Phases Review** 234
- **The Ar-iE-a Khum-Nar'A** 236
- **The Trinity Master Key Selection Chart** 250
- **Universal Merkaba Fields** 255
- **The Radial Body & Manifestation Mechanics** 258
- **The Eiron Point** 261
- **The Radial Body in Creation of the Hologram** 262
- **The 5 Radial Body Levels** 265
- **Transduction Sequence of the Miasmic Body** 266
- **The Christos-Trion-Meajhe Fields, High Veca Codes & Universal Life Force** 276

Diagrams

Chapter 1

The Holographic Template 14
Vibration-Oscillation Correspondences 18
One 15-Dimensional Time Matrix 22
Frequency Bands and Sub-Frequency Bands Within a 15-Dimensional Scale... 23
Partiki Phasing, Harmonics of Manifestation and Matter Density 25
Structure of the Kathara Level-1 12-Tree Grid 27
The Primal Manifestation Template 28
The Universal Templar Complex 34
Transduction Sequence 35

Chapter 2

The Planetary Bio-Feed Interface System (PBIS) 54
The Hierophant Symbol Code 57
Growth Rates and Morphogenetic Expansion 60
Level-1 Kathara 12-Tree Grid Internal Templar 64
Shields, Signets and the Kathara Grid 70
Level-2 Kathara Crystal Seals Grid and Chakras 71
Auric Level, Chakra and Hova Body Correspondences 75
Primary Colors of Chakras 76
The Hara Level 86
12 Primary Axi-A-Tonal Lines 87
Silicate Matrix 12-Strand DNA Template 92
Merkaba Phases 93
The 12 Human Senses 101

Chapter 3

Awakening the Mentor 120
Frequency Sub-Harmonics in the 15-Dimensional Scale 123
The Maharic Seal 136
Liquid Light Cleanse 137
The 5 Hova Bodies 143
Stations of Identity and Levels of Mind in the Hova Bodies 144
The 5 Hova Bodies and Levels of Identity in the Time Matrix 145
4 Primary Triadic Currents and Hova Body Correspondences 147
Combined Triadic Currents 148

Chapter 4

Elements of Doradic-Phase-1 Current Activation 173
Intrinsic Process of Activating a Triadic Phase Current 174
Opening the Healing Channels 177
Maharic Recoding Process Elements 183
Amplifying Inner Audio-Visual and Kathara Scan 186
The Maharic Infusion-Client Facilitation 190
Postures of Love 197
Client Agreement Form 202
The 6-Step Maharic Recoding Session 203

INTRODUCTION TO KATHARA BIO-REGENESIS TECHNOLOGIES

COLOR, SYMBOL, SOUND AND BIO-REGENESIS TECHNOLOGIES

BIO-REGENESIS TECHNOLOGIES are tools to assist us in accelerating our expansion of consciousness through natural, gentle stimulation of the personal **DNA TEMPLATE, KUNDALINI ENERGIES, CHAKRAS AND MERKABA VEHICLE.** Bio-Regenesis techniques are built upon the foundations of **KEYLONTIC MORPHOGENETIC SCIENCE** and advanced **SCALAR MECHANICS,** as understood by races of higher evolution; these are paradigms of science not yet recognized or validated by contemporary earth science paradigms. Because Bio-Regenesis technologies are based upon what is viewed by modern earth science paradigms as a speculative rather than verifiable science, I present Bio-Regenesis techniques only as an option to explore in meditation.

Bio-Regenesis technologies were taught as "Common Knowledge" within the Ascension Schools of Pre-Ancient advanced human cultures and were utilized as standard practice in pre-ancient time periods. Bio-Regenesis Technologies are built upon the natural laws of scalar wave mechanics. Bio-Regenesis Techniques are **SPECIFIC APPLICATIONS OF CONSCIOUS ENERGY DIRECTION WITHIN THE MANIFESTATION TEMPLATE OF THE BODY** that stimulate into activity dormant portions of the personal Manifestation Template, which allows for a natural, progressive and accelerated advancement of the personal **ORGANIC EVOLUTIONARY BLUEPRINT** of the 12th-Dimensional Omni-polar Pre-matter Template. Bio-Regenesis Techniques simultaneously create subtle, natural acceleration within the interwoven energy systems of the DNA Template, Chakra System, Merkaba Fields, Kundalini energies, higher dimensional consciousness, and "Subtle Energy Body" anatomy.

In the Bio-Regenesis paradigm it is said that such techniques allow an individual to affect the function of the scalar wave template of the body, working co-creatively **under the direction of the individual's own higher dimensional levels of consciousness.** As the higher dimensional levels of the personal identity, the spiritual identity of the Soul, governs the processes of the personal Manifestation Template, Bio-Regenesis Technologies are completely safe and natural to the organic design of the human being. Using processes of Bio-Regenesis from the earthly conscious perspective expedites the natural processes of energy and consciousness by which the higher identity and earthly identity integrate to become one. In advanced ancient human cultures, Bio-Regenesis Technologies represented a natural attribute of consciousness expansion into the realms of higher evolution and assisted to biologically prepare humans for **STAR GATE** passage or **"ASCENSION"**.

If we can understand that the **HUMAN MIND** is an energy force that **CONTINUALLY GENERATES PATTERNS OF SCALAR WAVES** through the process of **THOUGHT,** it is not difficult to understand how **APPROPRIATELY DIRECTED THOUGHT** can directly influence the function of the personal Manifestation Template scalar blueprint. All thoughts serve this purpose, and directly effect the observable state of the mind-body-spirit system and the manifestation of events within the external life drama. **THOUGHTS ARE THINGS-** ***SCALAR WAVE CONFIGURATIONS*** of multi-dimensional vibrating patterns of **BI-POLAR ELECTROMAGNETIC ENERGY RADIATION,** which form **SPECIFIC PATTERNS OF SCALAR FREQUENCY** within the personal Manifestation Template.

Undirected thought creates chaotic patterns within the Manifestation Template, while thought directed through clear intention creates ordered patterns within the Manifestation Template. Thought directed with clear intention and **KNOWLEDGE OF THE STRUCTURE OF SUBTLE-BODY ANATOMY,** is a very potent form of **SCALAR POWER.** The patterns of scalar energy frequency that thought projects into the personal Manifestation Template serve as **ELECTROMAGNETIC OPERATIONAL INSTRUCTIONS** within the Template, directly effecting the conditions that will be met in manifest experience. To develop skill in the manifestation process, the conscious "intending" mind must become more familiar with the **"LANGUAGE OF SCALAR WAVES"**, as this is the **"LANGUAGE OF LIGHT AND SOUND"** upon which the Manifestation Template operates. The "language of scalar waves" is "spoken" through the forms of specific wave spectra, forms that appear to the conscious 3-dimensional mind as frequencies of **SOUND**, spectra of LIGHT or **COLOR**, and shapes or **SYMBOLS.**

What we perceive as color is specific spectra of **LIGHT-RADIATION WAVES** that have a specific measurable **WAVELENGTH** and vibrational **ENERGY SIGNATURE.** In using the conscious mind to direct quantities of color, we are **CONSCIOUSLY SELECTING SPECIFIC SCALAR FREQUENCIES** to add to the Manifestation Template. When we use the conscious mind to create images of **SYMBOLS**, we are further **SPECIFYING THE ARRANGEMENT OF SPECIFIC FREQUENCIES**, as they will appear within the Manifestation Template. **SYMBOL FORMS** (even those that compose the alphabets of outer languages) represent **SCALAR-WAVE GUIDES**, and directly affect the contours of the scalar wave blueprint of the Manifestation Template. The Manifestation Template governs the function of the body and consciousness within the manifest experience, and so the **"Language of Scalar Waves"** is the medium through which we gain conscious access to the **CASUAL LEVEL OF MANIFESTATION.** In using **color and symbol** to direct frequency, we are creating a pattern of energy that has a specific vibrational signature or **"TONAL SOUND SIGNATURE"**, which directly interfaces with the energetic vibrational sound signature of the Manifestation Template's scalar grid.

In Bio-Regenesis technology, Color and Symbol are used to direct the **TONAL SCALAR ARRANGEMENTS** of the Manifestation Template, to create natural, desired results within the body-mind-spirit system. There are many complexities within the process of conscious manifestation that one must learn to fully master the contours of space, time and matter. The beginning step is learning to give more finely tuned thought intention **"PROGRAMMING INSTRUCTIONS"** to the personal Manifestation Template. Thoughts and images rendered in **external language** and 3-dimensionally associated symbols affect the **outer layers** of the Manifestation Template, but they do not provided as finely tuned manifestation instructions as do the **"scalar wave languages"** of Color and Symbol image, which direct the contours of vibrational patterns of SOUND. Mastery within the interdimensional spectrum progressively develops as one masters the core **"PROGRAMMING LANGUAGES"** of **Color, Symbol** and **Sound Vibration.**

In **MIND TECHNOLOGIES**, such as **CREATIVE VISUALIZATION** and **VERBAL AFFIRMATION**, beginning skill in **SCALAR TEMPLATE PROGRAMMING** is developed through using emotionally charged images and precise sound patterns in the language to which we are accustomed, as methods to begin gaining conscious control over the processes of personal manifestation. Keylontic Science **BIO-REGENESIS TECHNOLOGIES** take us **ONE STEP DEEPER** into the manifestation process, by directly employing the **LANGUAGE OF SCALAR WAVES** and directing the **ENCODED INSTRUCTIONS** through **PRECISE LOCATIONS** within the body-mind-spirit system and the Manifestation Template upon which this system is built. Bio-Regenesis technologies take us from speaking the language of the 3-dimensional mind into speaking the intrinsic scalar-wave language of the Spirit, which is the **CASUAL ELEMENT** behind and within all manifestation.

Bio-Regenesis Technologies represent applications of Scalar Mechanics that utilize the inherent power of **SUBTLE WAVE FORMS** to created desired change within the core Manifestation Template of the body. Within this process, **COLOR** and **SYMBOL** become the **TOOLS** through which the 3-dimensionallyconscious mind becomes empowered to participate in conscious co-creation with the Soul and higher dimensional spiritual portions of identity. **Color** and **Symbol** possess power as **MATHEMATICALLY ENCODED** directors of scalar frequency; the ultimate effect of this directed power is the ability to affect the scalar arrangements of the **Manifestation Template**. Intrinsically, **scalar waves** are specific points of vibrating bi-polar energy signatures. Vibration of energy units creates patterns of internal and external **SOUND**, within and beyond the range of 3-dimensional detection. The Manifestation Template can be conceptualized as an **INTERWOVEN FABRIC OF SOUND FREQUENCY**, the "Silent Symphony" of personal and universal being. The tools of Color and Symbol affect the scalar-wave arrangement of the Manifestation Template, and thus alter the vibrational patterns of **SOUND TONES** within the personal blueprint. **COLOR AND SYMBOL are tools for the direction of SOUND**, and intentional application of **SPECIFIC SOUND TONES** can also be used in conjunction with Color and Symbol, to further amplify one's power to interact with the Manifestation Template.

Along with the techniques of Color and Symbol direction, **TONING**, or the **intentional generation of specific sounds to affect the Manifestation Template**, is also utilized in Bio-Regenesis technologies and spiritual expansion programs. "Toning Therapies" have emerged in recent years through the New Age and Holistic Healing paradigms, and have been applied for thousands of years, within the practices of spiritual masters in every religious tradition. SPOKEN LANGUAGE itself is a form of TONING, with its accompanying SYMBOL ALPHABET, and like all Symbols and Sound Tones, our languages directly affect the personal Manifestation Template, and the level of consciousness that can manifest through the body. In ancient cultures, the powers of language were better understood than they presently are in contemporary mainstream society. Particularly within the Priest-casts of ancient religions, language was used more consciously, with an understanding that words, sounds and images would directly effect the consciousness of the masses. Prayers, rituals and songs, some of which remain in use today, were used as a means of *altering consciousness*. Some assisted in spiritual development, others were intentionally used to limit and control the consciousness of populations.

The contemporary earth science paradigm is only beginning to explore the power of sound vibration and the connection between sound, symbol and color is not yet recognized or understood. **In advanced pre-ancient cultures, these sciences of Scalar Mechanics were fully understood and utilized in the most powerful of ways.** Color-Symbol-Sound technologies were not only used in **Bio-Regenesis** applications for personal health and consciousness expansion; they were also used among **GROUPS OF PEOPLE** to directly interface with the scalar-wave Manifestation Template of the **PLANTETARY SHIELDS**. Vortices, Time Portals, Star Gates, Ley Lines and free energy systems generated through the planetary core and solar light emanations were all **DIRECTED THROUGH THE FOCUSED MIND**, utilizing knowledge of Color-Symbol-Sound Scalar Mechanics. Since the fall of ancient cultures, which came as a result of abusing the powers of these Scalar technologies, the Color-Symbol-Sound sequences once used to direct massive amounts of power became the **"HIDDEN AND FORBIDDEN SACRED KNOWLEDGE"**.

The **COLORS, SYMBOLS** and **SOUNDS** used in Bio-Regenesis techniques are not simply random choices. The elements of Bio-Regenesis technique are drawn from a **UNIVERSAL STANDARD LANGUAGE OF "SCALAR SPEAK"**, through which **precise scalar frequencies** are generated through **specific Color-Symbol-Sound sequences** to create very specific effects within Manifestation Templates. The Bio-Regenesis Techniques presently offered represent only the beginning of our reawakening to this vast body of Sacred Science knowledge. Many Bio-Regenesis techniques utilizing Color-Symbol sequence scalar mechanics are accompanied by a corresponding exercise in **TONING**. Within the mystical **Ascension Schools** of ancient and pre-ancient times, there existed a very **SACRED SERIES OF TONING SEQUENCES** that were used **to directly interface with the DNA TEMPLATE** and the **AXIOM LINES** in the **PLANETARY**

SHIELD. On a **personal level,** through this specific series of Toning, dormant strands in the DNA Template could be progressively brought into activation, to expedite the process of Spiritual Actualization, Holistic Healing and building of the **PERSONAL MERKABA VEHICLE** within the bio-energetic field. On the **planetary level**, these **Sacred Toning Sequences** were used to **ENERGETICALLY OPEN** the **PLANETARY AXIOM LINES** for **CLEARING, REPROGRAMMING AND ACCELERATING THE ACTIVATION** of the **PLANETARY SHEILDS**. This series of Sacred Toning was collectively called "**THE MUSIC OF THE SPHERES**".

THE SONGS OF THE SPHERES

The **MUSIC OF THE SPHERES** represents the **ORGANIC TONAL SEQUENCES** of **EACH DIMENSIONAL FREQUENCY BAND** within the 15-Dimensional Time Matrix; the **CONSOLIDATED CORE VIBRATIONAL SOUND SIGNATURES** of each Dimensional frequency band. Of the 15 core vibrational signatures of the 15 Dimensions in a Time Matrix, 12 of these core signatures serve as the **PRIMARY 12 TONAL SEQUENCES** upon which each strand of the 12-Strand original human **DNA Template**, and each **AXIOM LINE** in the 4-Density **Planetary Shields** are structured. In using the **Tone Sequences of the Music of the Spheres**, the 12-Strand DNA Template can be **PROGRESSIVELY BROUGHT INTO NATURAL ACTIVATION.** Scalar-wave distortions within the Templates for the DNA Strands (which physically manifest as genetic distortions) can be systematically **REALIGNED** with their natural perfect 12th Dimensional **ORGANIC IMPRINT.** In using the **Music of the Spheres** for work with the **Planetary Shields**, each of the **24 AXIOM LINES** can be **OPENED** and **ENCODED WITH THE PERFECT PATTERN OF THE PLANETARY PLASMA BEAM.** Transmitting the 12th-Dimensional **MAHARIC SHIELD** pattern directly into the **Axiom Lines** in the Planetary Shields is the most rapid method to distribute the program of the **PLANETARY ORGANIC IMPRINT** throughout the 4 Density Levels of the PLANETARY SHIELDS.

In ancient days, the *Music of the Spheres* was used extensively for purposes of self-generated healing and to prepare the physical body for literal passage through the planetary Star Gates ("Ascension"). The **specific tone sequences** for each **SINGULAR DIMENSION** (which corresponded to one DNA Strand Template in the 12-Strand blueprint and the inherent Dimension of consciousness that would embody through activation of the strand) are called the "**SONGS OF THE SPHERES**". Each "**SONG**" contained very specific "**word sounds**" (from the first Universal Spoken language) for **lyrics**, and specific **multi-layered tones** (which generated inaudible Tri-tone Standing Waves) for **melody**, **harmony** and **overtones**. To be effective, the Songs had to be used through the **HUMAN VOICE**, externally or mentally as the "**SINGING OF SONGS**".

The Sacred Songs were sung in combination with directing specific corresponding **COLOR** and **SYMBOL** sequences through the bio-energetic field (or through the Planetary Axiom Lines for Planetary Shield work). **The Songs served to "open" specific areas of the DNA Template, or specific Planetary Axiom Lines, to receive instructions directed by the Color and Symbol sequences.** The tones of the Songs generated specific scalar-wave formations that triggered activation of corresponding configurations within the DNA Template and Planetary Shields. Activation of dormant portions of the DNA Strand Templates or Planetary Axiom Lines "opened" the Strand Template or Planetary Shield to directly receive Color-Symbol scalar wave instructions, through which desired outcomes within the personal or planetary body, and within the external reality experience, could be "**PROGRAMMED**" for manifestation.

The **SCIENCE OF THE MUSIC OF THE SPHERES** was one of the most highly guarded **"SACRED SECRETS"** in pre-ancient cultures, due to the power of interdimensional freedom and conscious manifestation that could be obtained through knowledgeable use of the **SONGS.**

Before the **SONGS OF THE SPHERES** will be fully returned to human awareness, our culture will have to mature enough to demonstrate **spiritually motivated ethical use of power.** Certain SONGS are now being slowly returned, so that we may assist those of higher evolution to realign Earth's Planetary Shield with its original 12th-Dimensional **MAHARIC SHIELD ORGANIC IMPRINT.** One of the **15 SONGS OF THE SPHERES** was provided to us by the Emerald Order. This SONG is used to activate dormant scalar-waves in the 8th **DNA STRAND TEMPLATE**, through which the process of activating the dormant **1st-8th Strands** of the 12-Strand DNA Template can be accelerated, expediting the natural processes of higher dimensional spiritual identity integration.

This SONG is also used to open the **8TH AXIOM LINE** in **GAIA'S PLANETARY SHIELD**, to facilitate realignment of **Earth's Planetary Shields** from **ETHERIC MATTER DENSITY-3.** This SONG was given so that **GROUPS** can begin assisting directly in Planetary Grid work, opening specific Axiom Lines and Vortices in the planetary body to help bring Earth's Planetary Shield Manifestation Template into its organic alignment and balance. The SONG that was given is called the **"Ariea Khum Nar'A"**. The English language translation is **"THE SONG OF ORION"**. This **SONG OF THE 8th SPHERE** corresponds to the **8th -Dimensional level** of the **UNIVERSAL KATHARA GRID** and its **8TH PRIMARY STAR GATE.** It also corresponds to the **8th PLANETARY AXIOM LINE** within the Etheric Matter Density-3 **GAIAN PLANETARY SHIELD** and to the **8th DNA STRAND TEMPLATE** in the human body. The **8th Dimensional STAR GATE** within the **UNIVERSAL KATHARA GRID** is the Star Gate that opens into the **ORION STAR SYSTEM**, thus the name of the **SONG OF THE 8th SPHERE** is **"THE SONG OF ORION"**.

Soon the SONGS that correspond to the 11th and 12th –Dimensional frequencies will be provided. Aside from its use in planetary grid work, when used as a **"MANTRA"**, repeatedly sung as a focus for the mind in meditation, the ***Ariea Khum Nar'A*** serves to stimulate consciousness expansion into the higher dimensional fields and amplifies and expedites the effects of personal Bio-Regenesis techniques.

CHAPTER 1

THE CONTEXT OF HEALING

The Structure of the Unified Field and the Multi-dimensional Anatomy of Form

- THE HOLOGRAPHIC TEMPLATE
- THE STRUCTURE OF DIMENSIONS, PARTIKI PHASING AND MATTER DENSITY
- UNIVERSAL AND PLANETARY KATHARA GRIDS, THE 12-TREE, KATHARA CENTERS AND LINES, SCALAR SHIELDS, CRYSTAL SEALS AND DIODIC POINTS
- THE UNIVERSAL AND INTERNAL TEMPLAR COMPLEXES
- THE TRANSDUCTION SEQUENCE AND HOLOGRAPHIC REALITY CONSTRUCTION

TOPICS OF DISCUSSION

The Ariea Khum-Nar' - A

The Song of Orion

Part 1 : the Resonant Tone Syllable Sequence (primary melody)

Verse 1: OM A Da E, Patum ah
OM A Da E, Patum ah
Patum ah A' DE E - Tah, A khum-na
OM A Da E, Patum ah

Verse 2: TrA TE La E' Durum Na
TrA TE La E' Durum Na
Durum' ah A' Khem - Tah, A khum -na
OM A Da E, Patum ah

Part 2 : the Base Tone Syllable Sequence (accompaniment 1)

OM A Da E, Patum ah - Lines 1, 2 & 4 Verse 1 & Line 4 Verse 2
TrA TE La E' Durum Na - Lines 1 & 2 Verse 2
UM ah OM, A
UM ah OM, A

Patum ah A' DE E – Tah, A khum- na
Durum ah A' Khem – Tah A khum-na
DO RAY' TU Ra"

OM A Da E, Patum ah
UM ah OM, A

Part 3: the Over Tone Syllable Sequence (accompaniment 2)

OM A Da E, Patum ah – Lines 1 & 2 Verse 1
TrA TE La E' Durum Na – Lines 1 & 2 Verse 2
BE HE Tah OM, A
BE HE Tah OM, A

Patum ah A DE E – Tah, A Khum –na – Line 3 Verse1
Durum ah A Khem- Tah, A Khum - na - Line 3 Verse 2
Thra Khem' Na, A

OM A Da E, Patum ah – Line 4 Verses 1 & 2

KhrA MiM, Tah A

THE STRUCTURE OF THE UNIFIED FIELD AND THE CONTEXT OF HEALING

If one is to become fluent in the art and science of **Bio-Spiritual Healing Facilitation**, it is necessary to become familiar with the *primary structures of energy* within which existence takes place. Without this understanding one will be unable to identify the *true nature of systems and their intrinsic functions*. If we do not understand the **intrinsic order of a system** and the elements that make up its parts, our ability to comprehend the *organic functions* of the system will be limited. Without comprehension of the intrinsic dynamics inherent to a system, our perceptions will be limited to observing the **effects of systems function**, rather than perceiving the **causal elements** behind and within the apparent observable effects. In relation to the **health and healing** of the human body, it is wise to view the human **Body-Mind-Spirit organism** as a series of interwoven systems, each with *inherent, implicit order*, the perceivable and observable aspects of which represent the effects of systems function. **The observable effects of the human condition emerge from an as yet unidentified causal order, a hidden and mysterious source out of which the manifest effects of human existence emerge.** Holistic Healing approaches human health and healing in terms of the *interdependent relationships* between *multiple interwoven systems*. The Body-Mind-Spirit organism is viewed in terms of the *intrinsic relationships that unite* the multiple systems of the human being, rather than in terms of the *observable boundaries* that appear to *separate and divide* the multiple systems inherent to the human organism.

Holistic Healing, and **KATHARA Healing** particularly, take the concept of **intrinsic unity** within the seemingly separate systems of the human being one step further than *simple interrelationship* between **physical, mental and spiritual aspects** of human experience. **In the paradigm of Kathara Healing, the human organism is viewed as a set of interwoven systems that is itself part of a larger system of interdependent systems.** The human individual is not only recognized as a *singular set of unified parts*, but rather as an *intrinsic part* of the species, planetary, galactic, universal and cosmic systems within which human existence finds **context** for being. The **Cosmic Unified Field of Energy and Consciousness** is viewed as the **indelible medium** within which all reality takes place, and human existence is viewed in terms of *its relationship to this greater Meta-system* of interwoven, interdependent systems. **The health and wellbeing of the human being is directly related to and effected by the systems-functions of the greater Unified Field**. In order to better understand and facilitate the health and healing of biological organisms, it is useful to understand the *basic order and function* of the **UNIFIED FIELD**- the context in which life itself takes place.

Kathara Healing is an ancient system of **Holistic Healing**, dating back beyond presently identified recorded human history. The principles of **Universal Order** as taught within Kathara Theory present a **broader context of universality** than is presently recognized by contemporary western science. Kathara is built upon **Laws of Multidimensional Universal Physics,** laws of intrinsic nature with which western science is not yet familiar. In Kathara Healing the *hidden order of universal systems* is recognized and the foundations of Kathara *demonstrate the interwoven systems-functions* between the human being and the order of the **Unified Field. To develop proficiency and genuine skill within the art and science of Holistic Healing, the basic order of the Unified Field must be understood.** For with this understanding comes the ability to *directly interact with and influence the causal elements* of the human experience. For this reason the teachings of Kathara Healing begin with providing a basic format through which the **CONTEXT of healing** can be understood ***– a glimpse at the intrinsic order of the Universal Unified Field.***

With foundations grounded in **coherent systems relationships**, the Kathara Healing Facilitator has more knowledge, power and comprehension to bring to the art and science of healing facilitation. **Through comprehension of the *intrinsic systems of universal order*, the Kathara Facilitator progressively evolves to embrace the *unity of SELF within the Unified Field*, opening to an ever-expanding capacity of spiritual awakening and the embodiment of UNCONDITIONAL LOVE.** The physical, mental and spiritual aspects of human anatomy represent one interdependent, interwoven system that is *continually in a state of relationship to the Unified Field.* This relationship must be acknowledged and embraced if true health and healing are to occur. **Human evolution is a Bio-Spiritual process, the body and the consciousness – the biology and the spirit - are inseparably intertwined within themselves and within the greater order of the Unified Field.**

Healing emerges through restoring order to the ONE-SYSTEM and its infinite parts.

THE HOLOGRAPHIC TEMPLATE

The externalization of life, manifestation of matter and individuation of identity are **HOLOGRAPHIC PROJECTIONS of CONSCIOUSNESS-ENERGY SUBSTANCE**, created through an *intrinsic order of energetic relationships*. Energetic relationships represent **interrelationships of consciousness**, in its infinite manifest and de-manifest forms.

Consciousness *IS ENERGY*
And
Energy *IS CONSCIOUS*.

True Science has a *spiritual core* and true spirituality has *its intrinsic translation within the Laws of Energy that govern the manifestation of universal systems*.

Reality is **THOUGHT CONSTRUCTION.** The core substance of the cosmos is **CONSCIOUSNESS.** *Thought is an attribute of CONSCIOUSNESS*, the **filter** through which consciousness manifests itself into the **Hologram of Form.**

Nothing is truly solid. All things are composed of *consciousness* and their *apparent solidity* is determined by the *relationship between the consciousness observing the form and the consciousness of which the form is made.* Human consciousness emerges through an **order of dimensionalization,** which sets frameworks within which the *interrelationships of consciousness* can take place. **Human perception of solidity and externalization is determined by the oscillation rates between dimensionalized units of consciousness.** Dimensionalized units of consciousness form **frequencies of energy,** which exist in *specific relationships* to each other. Human *consciousness* (the soul –spirit), and human *physical form* are **patterns of frequency** formed by *dimensionalization of units of consciousness. We perceive manifest solidity due to the relationship between the frequencies of consciousness of which we are made and those of the Unified Field of Conscious Energy around us.* **Humans perceive as solid the frequency bands that exist one full dimensional spectrum below the frequencies within which the individuated or collective consciousness is stationed.**

The only difference between a *thought* and a *manifest thing* is the *frequency of the consciousness of the observer*. Manifest reality is **thought projection,** made solid and externalized by relationships between the *frequencies of our focus of attention* and those of the *projected thought forms*. **We perceive as reality the thought forms of the collective masses as they were placed within the frequency bands that now exist one dimension below the frequencies within which our present focus of collective consciousness is stationed.**

As reality is a THOUGHT FIELD, composed of units of consciousness awareness, reality can be directly **AFFECTED by THOUGHT**, as the substance of both thought and reality are one and the same. **The key to mastery** of our present reality and to restoring our **imprint for health**, is understanding the *reality of dimensionalization* within which our consciousness now resides.

The human body is a HOLOGRAPHIC PROJECTION of consciousness that is built upon a *HOLOGRAPHIC TEMPLATE* of structured units of consciousness. The **Holographic Template** represents the **Living Morphogenetic Field** – the *dimensionalized blueprint of conscious light, sound and scalar waves*, within which the individuated consciousness is stationed, and *upon which the illusion of solidity of the body matter is formed.* **To affect *true and lasting change* within the Body-Mind-Spirit System of the human being, one must *go to the core* of its manifest structure – the *Holographic Template* or Thought-energy Blueprint, upon which the entire system of consciousness itself comes to know being.**

The body is a **HOLOGRAM** that can be directly affected by the *substance of which it is composed* – **CONSCIOUSNESS**. In learning the structure of dimensionalization through which the body-illusion manifests, one becomes progressively more masterful in directing this personal thought form to suit ones desired specifications. The core **Holographic Template** of the personal and universal body is called the **Kathara Grid. Kathara Healing** is the process by which the *embodied* aspects of human consciousness become more aware of and able to direct the *intrinsic processes of holographic projection,* with the intention of restoring integrity to the function of the Body-Mind-Spirit system.

***No thing is truly manifest*– it only appears to be so,**
due to the refraction of consciousness
within the energetic relationships inherent to
the *Holographic Template*–
the original *thought-form construct*
upon which our universal structure
is perpetually recreated.

All creatures and things are Spiritual Beings having a Manifest Experience...No creature or thing can be ever divorced from its innate spirituality, but only from the awareness of its nature. For life is the expression and substance of spirit- and manifest reality is but a Dreamscape, from which we eventually all awaken...

The causal element of all manifest experience is called a ***Morphogenetic Field*** or **MANIFESTATION TEMPLATE.** Keylontic Science, the science of Manifestation Templates is part of a larger advanced paradigm of science that is known as **15-Dimensional UNIVERSAL UNIFIED FIELD PHYSICS.**

PRIMAL SUBSTANCE

- A Manifestation Template is made of **PRIMAL SUBSTANCE;** units of conscious energy called **PARTIKI** that exist as ***Omni-polar points of fixed vibration. Partiki units*** are the smallest building blocks of matter, and they form the templates upon which consciousness in all forms enters manifestation.

- Partiki units are **Omni-polar** (containing the potentials for all polarities or none) units of vibrating energy that perpetually cycle back and forth between a state of **BI-POLAR LIGHT RADIATION** (scalar-standing-wave) and **OMNI-POLAR SOUND VIBRATION.**

- In the ***Omni-polar state,*** Partiki units exist as invisible, fixed points of ***sound vibration,*** forming what is called an **INTERDIMENSIONAL TRI-TONE WAVE.** An Interdimensional ***Tri-tone Wave*** is a singular point of fixed vibration that is composed of ***3 sub-vibrations*** (base tone, overtone and resonant tone). When Partiki units are in their Omni-polar state they exist as ***Ante-matter substance,*** the first state of energy organization before Pre-matter manifestation. Through a process of Internal Fission characteristic to their design, Partiki units break apart to form Bi-polar waves, while replicating their original Tri-tone Omni-polar design.

- In the ***Bi-polar state,*** two sub-vibrations of the Tri-tonal Standing Waves of Partiki units break down into two sub-units, ***sub-tones,*** called **PARTICUM**-*Base Tones* and **PARTIKA**-*Overtones,* interconnected units of **BI-POLAR LIGHT RADIATION** that form ***Electromagnetic Scalar-Standing-Waves.*** The third vibration of the Tri-tone wave, the *Resonant Tone,* remains as the core vibration through which the polarized vibrational units of Particum and Partika will reunite through ***Internal Fusion.***

- **PARTICUM** units form the energetic building blocks for **PARTICLE TEMPLATES** and **PARTIKA** units form the building blocks for simultaneously manifesting **ANTI-PARTICLE TEMPLATES.** Particle and Anti-particle Templates are interconnected, united by the Ante-matter **PARTIKI** units through which they manifest. The effects of **ELECTRICAL AND MAGNETIC FORCE** are set in motion through the **EXPANSION AND CONTRACTION** of energy vibration between Particle and Anti-particle matter units through the Ante-matter Partiki unit that unites them.

- **Particum-Particle units** represent the **CONTRACTION PHASE** of ante-matter energy, with higher **VIBRATION** (energy contracted into or received by the Ante-matter template) and lower **OSCILLATION** (energy expanded or transmitted from the Ante-matter template) and so are considered **BASE MAGNETIC. Partika-Anti-particle units** represent the **EXPANSION**

PHASE of Ante-matter energy, with lower Vibration and higher Oscillation, and are considered **BASE ELECTRICAL.**

- **ELECTROMAGNETIC ENERGY** is created through the continual cycling of energy, as the Omni-polar Ante-matter Tri-tone Wave of ***Sound Vibration*** projects its energy into Bi-polar Particum and Partika Scalar Waves of ***Light Radiation***. Energy thrust expands into the Anti-particle Partika vibration point as **electrical force**. It then contracts into the particle Particum vibration point, creating **magnetic pull**, (in ratio to its original electrical thrust), as the third vibration in the Ante-matter Tri-tone Wave draws the energy back to its source. Through the draw of the Ante-matter Partiki template, Partika-Ante-particles and Particum-particles are brought into a state of **Fusion.** Upon fusion, the energy of the Particum and Partika transmutes, the Bi-polar Standing Scalar Waves of Light Radiation returning to their original Omni-polar Ante-matter state of Partiki units. Once returned to the Partiki state, the process repeats as the Partiki creates Fission and replication. **Partiki, Particum and Partika units represent PHASES that Primal Substance energy passes through as it moves into and out of manifestation.**
- The process by which Partiki units perpetually convert conscious energy into Bi-polar Light Radiation Scalar-Waves (expansion) and back into Omni-polar Sound Vibration Tri-tone Waves (contraction) is called **PARTIKI PHASING.** Through perpetual cycles of Partiki Phasing, matter units "flash on" through **fission**, into Bi-polar Particle and Anti-particle manifestation built upon Scalar Waves of Light Radiation, then "flash off" through **fusion**, into Omni-polar Ante-matter Sound Vibration, continually cycling energy between the manifest and non-manifest state. **The perception of external physical matter, space and the passage of time are created through *variance in relationship* between rates of Partiki Phasing.**
- Consciousness in the form of Partiki Units is the **PRIMAL SUBSTANCE** of which the cosmos is structured and Partiki Phasing is the perpetual **PRIMAL ACT** of reciprocal fission and fusion through which Primal Substance is brought into manifestation.

The Holographic Template

PRIMAL SUBSTANCE

Units of Consciousness, Morphogenetic Fields and Scalar Grids

1. ***Partiki, Partika and Particum:*** Smallest units of energy-substance. Electro-tonal units of consciousness that are the building blocks of morphogenetic fields, matter and individuated conscious identity. Operate as minute, perpetual motion fission/ fusion generators.



2. ***Partiki Grids*:** The fabric of morphogenetic field structure. Partiki units group to form interwoven Strands, then Grids of electro-tonal substance, out of which morphogenetic fields are fashioned. Out of a Unified Field of Partiki units, Partiki Grids form to create the frequency bands that make up dimensional fields and then to form individuated morphogenetic fields .



3. Partiki units continue to group or accrete upon the Partiki Grids, forming
A. ***Keylons*** – crystallizations of "frozen light" (standing scalar wave patterns and fixed points of tonal frequency), and
B. ***Keylon Codes*** – complex groupings of Keylons, which together form a crystalline template of light spectra, sound frequency and electro-magnetism that is the morphogenetic field Crystal Body– the Blueprint upon which matter and identity will manifest.

A.



B.



The **Morphogenetic Field** is made of interwoven **Partiki Grids**. The electro-tonal units of consciousness out of which Partiki Grids form create standing wave patterns – **scalar wave grids**, which hold the form of consciousness within dimensionalized manifestation. Morphogenetic Fields are thus **Scalar Grids**, that form in specific ordered interrelationship. Partiki Grids form upon the core *geometrical-mathematical* structure of the **Kathara Grid**, and so the Kathara Grid represents the *core Scalar Field* upon which form manifests.

Morphogenetic Fields govern the form of matter manifestation and the evolution of biology and consciousness. Morphogenetic Field mechanics thus hold the key to mastery of physical reality and Bio-Spiritual Evolution.

THE STRUCTURE OF DIMENSIONS

Frequency Bands and Sub-Frequency Bands, Vibration-Oscillation-Particle Spin, Harmonics of Manifestation and Matter Density Levels.

The Hologram of manifest reality is a complex system of interwoven energy constructs, all built upon **dimensionalized sets of scalar grids**- or fields of standing wave points – that form the **base laws of energy** upon which manifest reality functions.

The physical portions of the human body represent ***wave strata*** that exist within specific relationships to the embodied consciousness. **The embodied consciousness itself is *regulated by the intrinsic behavior of the wave strata* in which it is ensconced.** The wave strata of seemingly physical forms appear to *human detection* in the form of *particles, sub-particles and wave bands* that group to form the 3-dimensionally manifest hologram of human life

The **behavior of dimensionalized wave strata** is an intrinsic element within the function of ***human anatomy***, and provides the *very context* within which human existence and evolution take place. When we come to understand ourselves as **vibrating quantities of conscious energy**, existing within a state of **vibrational co-resonance with all things**, which are themselves *vibrating quantities of conscious energy*, we can begin to understand the **fundamental structures** upon which the human condition is built.

*The human body is a **construct of conscious energy**, a living* morphogenetic field existing within the greater living morphogenetic constructs of the species, planetary, galactic, universal and cosmic morphogenetic structure. We are simply an element of sentient consciousness within a larger structure of sentient consciousness, a part of the **Unified Field of Consciousness** that IS the living identity of the cosmos. Our physicality emerges through the **perceptual lens of dimensionalization**, which provides us with the seeming manifestation of **particles, atoms, molecules** and the **physical systems** built upon them.

If we expect to **heal ourselves** of the manifest conditions that cause suffering within the Body-Mind-Spirit system, we must first understand the **nature of health**, the "way things are supposed to work" when they are *functioning properly*. To understand the intrinsic **Imprint and impetus for health** in the human organism, a basic understanding of the *contents of its parts* is in order. That understanding begins with *identifying the basic reality structures within which we reside, and how we exist in relationship to these structures.*

Our understanding of *health* begins with *identifying the context of existence*, the *Unified Field of Consciousness-Energy* of which we are all a part. **A simple *identification of the structures of the Unified Field* will work wonders in assisting us to understand ourselves, and through this understanding we become more empowered to foster a healthful and more joyous living experience.** To better understand ourselves we must return to the core of our intrinsic nature, the **dimensionalized fields of consciousness** within which we reside and out of which the substance of our SELVES is composed.

The following characteristics inherent to the manifestation of the human hologram are a place to begin our journey of self-understanding.

Characteristics of the Hologram

PRIMAL ORDER

SCALAR WAVES: Points of standing waves, composed of quantities of conscious energy that emanate out of fixed units of vibration (Partiki units), which form the morphogenetic field templates upon and through which consciousness dimensionalizes itself to experience the hologram of manifest reality. Created through Partiki Phasing (internal fission/fusion "flash on/flash off")

MORPHOGENETIC FIELDS: The templates of consciousness, light, sound and scalar standing-wave grids which serve as the structured blueprints upon which our consciousness manifests into dimensionalization, through which the holographic projections of space-time-matter and identity individuation can be experienced.

DIMENSIONS: *Morphogenetic Field Scalar Grids composed of interwoven layers of scalar waves, which serve to direct the flow of consciousness into multiple patterns of refraction through which the hologram of matter density, linear time and objectification of reality can be experienced.* Dimensions are specific structures of consciousness, composed of Partiki units with differing vibratory-oscillation rates, which exist in precise relationship to each other, and govern the intrinsic laws of function within the observably manifest worlds. The process of dimensionalization occurs through the wholeness of consciousness *compartmentalizing itself into various ordered sections having diversity of vibratory-oscillation*, through which the wholeness of consciousness may experience itself in an endless variety of forms. Each dimension represents a full frequency band.

FREQUENCY BANDS: Synchronized, cyclic, repeated sequences of "flashing on and off" of scalar-wave points within the dimensional scalar grids, which gives the appearance of manifest movement of wave spectra within a dimensional system. **Sub-frequency Bands** are shorter segments of the longer "flashing on and off" sequence of the full Frequency Band. The frequency of dimensional levels and the particles within them is determined by the vibratory-oscillation rate of the Partiki units that make up the scalar-wave grid. Frequency is the form consciousness takes on while ensconced within the framework of dimensionalization. Frequency is the vibrating-oscillating wave spectra of which matter particles and dimensionalized consciousness are composed.

VIBRATION-OSCILLATION: Vibration is the condition of **internal movement**, or ***holding of energy within*** units of consciousness (Partiki) and the particles built upon them. Vibration is determined by the **quantity of energy** ***held within*** Partiki units. **Oscillation** is the condition of **external movement**, or ***expending of energy from*** Partiki units and the particles built upon them.

The vibratory-oscillation rate of particles represents the *rate at which the scalar standing-waves "flash off and on"* within the morphogenetic field template. Vibration is the *internal measure of energy quantity* held *within* Partiki units and exists within direct proportion to the *oscillation* rate, or *external measure of energy quantity expended*, exhibited by Partiki and the particles built upon them.

The vibratory-oscillation rate represents the ratio between energy contraction (vibration) and energy expansion (oscillation), which sets the rhythm of particle pulsation that governs the formation of wave spectra within dimensionalization. The vibratory-oscillation rate of Partiki units determines the **frequency** (cyclic pattern of scalar waves "flashing off and on") of wave spectra within the various levels of the dimensionalized morphogenetic field. **The relationship of vibrational-oscillation between wave spectra determines the matter density levels particles will exhibit within the dimensional scale.**

Vibration-Oscillation Correspondences

Higher Dimensional Fields (8-15)	Lower Dimensional Fields (1-8)
Low Vibration	**Higher Vibration**
Higher Oscillation	**Lower Oscillation**
Expanding	**Contracting**
Higher Frequency	**Lower Frequency**
Shorter Wave Length	**Longer Wave Length**
Slower Electron Spin	**Faster Electron Spin**
Less Density	**More Density**
Electric	**Magnetic**
Lower Vibration =	Higher Vibration =
Less energy holding in Partiki =	More energy holding in Partiki =
More energy expended from Partiki =	Less energy expended from Partiki =
Higher Oscillation =	Lower Oscillation =
More expansion =	More contraction =
Faster flash rate of Partiki =	Slower flash rate of Partiki =
Higher Frequency of Flash =	Lower frequency of flash =
More external movement =	More internal movement =
Faster oscillation =	Slower oscillation =
Shorter wave length =	Longer wave length =
Slower electron spin around nucleus =	Faster electron spin around nucleus =
Greater expansion of energy units =	Greater compaction of energy units =
Less density =	Greater density =
Less magnetism =	Greater magnetism =
More electric	Less electrical

The human anatomy is a 15-dimensional morphogenetic field scalar grid structure, composed of wave spectra with varying degrees of matter density characteristic to the dimensional band within which each level of the anatomy is stationed. The portions of our anatomy that appear solid are those stationed one dimension below our focus of conscious attention.

PRIMAL ORDER OF MANIFESTATION TEMPLATES

- Morphogenetic Fields, or the **MANIFESTATION TEMPLATES** that serve as the blueprint through which consciousness manifests, are composed of the Primal Substance of **PARTIKI UNITS.** Partiki units draw together or **ACCRETE** to form **PARTIKI STRINGS.** Following a set **mathematical and geometrical design** inherent to their form, Partiki Strings interweave and overlap, forming a **"Fabric of Light and Sound"** called a **PARTIKI GRID.** A Partiki Grid is a fixed pattern of interwoven Bi-polar Scalar-Waves of light radiation,built upon Omni-polar Tri-tone Waves of sound vibration,that forms the foundation for diversified Manifestation Templates. A **Partiki Grid** is a **SCALAR GRID.**

- Following the precise mathematical design set by the will and intention of the manifesting consciousness, Partiki Grids further accrete, drawing in more Partiki Units, forming groups of Partiki units that are arranged following *3 different rhythms of Partiki Phasing.* **Tri-phase groupings of Partiki Units** form patterns of Scalar-wave and Tri-tone wave interrelationships that create ***crystallizations of energy*** called **KEYLONS.** Groups of Keylons continue to accrete, forming complex Keylon arrangements called **KEYLON CODES,** through which the Manifestation Template is progressively built up from Ante-matter through various stages of matter density, beginning with **PRE-MATTER SUBSTANCE,** the first density of **Liquid Silica Hydro-plasmic** energy to emerge into externalized form.

- The Morphogenetic Fields upon which universes manifest are built upon a Manifestation Template that has a specific order of mathematical interrelationships that govern the combining of Scalar Grids with different rates of ***Partiki Phasing.*** The **Cosmic Manifestation Template** is called the **ENERGY MATRIX.** Within the Energy Matrix there are many smaller manifestation templates upon which Universes are structured. **Universal Manifestation Templates** are called **TIME MATRICES.** There are uncountable Time Matrices within the Energy Matrix, which are collectively referred to as **THE TIME MATRIX.** All Time Matrices within the Cosmic Matrix follow a specific mathematical-geometrical program through which space, time and matter can be experienced by consciousness upon entering the Time Matrix structure.

- Time Matrices are arranged upon a pattern of 15 different, but interwoven, Partiki Phasing rhythms (rhythms of expansion and contraction of energy). Each of the 15 rhythms of Partiki Phasing creates one **DIMENSION.** A **Dimension** is a set pattern of **"FLASH LINE SEQUENCES",** or a cycle of singular Partiki Phasing rhythms that contains within it 12 smaller rhythms of Partiki Phasing. Each **Dimensional Manifestation Template** creates a set of fixed Scalar-Tri-Tone Wave Points that create a template of stationary **SCALAR FREQUENCY.** Each Dimension represents one **SCALAR FREQUENCY BAND** containing 12 smaller **SUB-FREQUENCY BANDS.** A **Scalar Frequency Band** is a cyclic pattern of specific Partiki Phasing Rhythms, or **EXPANSION AND CONTRACTION RATIOS OF ENERGY CIRCULATION,** to which consciousness conforms in order to enter the experience of manifestation.

- To create the Universal Manifestation Template upon which external space, time and matter experience can be known, Dimensions are ordered into sets of 15, forming the blueprint for a

15-Dimensional Time Matrix. Within a Time Matrix the 15-Dimensions are further arranged into sets of **3 Dimensions**, forming **5 3-Dimensional reality fields.** Each 3-Dimensional Reality Field is called a **HARMONIC UNIVERSE**, and each represents a **level of matter densification** specific to its intrinsic rates of Partiki Phasing. One Time Matrix is thus a **15-Dimensional Scalar Grid** with 5 separate yet interwoven reality fields and 5 different densities of matter manifestation.

- Each of the 5 Harmonic Universes within a Time Matrix represents a **TIME CYCLE.** A Time Cycle is a fixed, repeating pattern of Partiki Flash Line Sequences, or a repeating cycle of specific ratios of energy expansion-oscillation and contraction-vibration. The Time Cycle of a Harmonic Universe is called an **EUIAGO CYCLE.** There are **5 simultaneously manifesting Euiago Cycles in every Time Matrix,** through which consciousness passes in order to experience linear evolution through space, time and matter. Each Euiago cycle contains within it 6 smaller Flash Line Sequences forming6 smaller cycles of time called **TIME CONTINUUA.**

The **PRIMAL ORDER of Manifestation Templates** represents the core mathematical and geometrical interrelationships of energy that consciousness takes on in order to enter the holographically projected experience of external space, time and matter. All manifest forms, including the **HUMAN BODY** and **PSYCHE**, are built upon a Manifestation Template that begins with the Primal Order of Dimensionalization, through which the consciousness anchors itself into the Time Cycles of the Universal Manifestation Template Time Matrix, to begin the experience of evolution through time.

Understanding the **PRIMAL ORDER OF DIMENSIONAL STRUCTURE**, as it pertains to the human organism, allows for comprehension of the greater causal framework through which personal healing must occur. Such comprehension of the core causal structure of manifestation enables one to work cooperatively, rather than in resistance to, the natural **Universal Laws of Manifestation,** progressively restoring the **NATURAL HARMONIC ORDER** of wellbeing and **DIVINE RIGHT FORM,** through which the indelible **Organic Imprint for Health** can be progressively restored.

Dimensional Structure

A Dimension represents a full ***Frequency Band***, or repeating, cyclic sequence of "flashing on and off" scalar-wave points within a morphogenetic field. The morphogenetic field scalar grid structure of dimensions takes the form of ***sets of 15-Dimensional Matrices***. The 15 Dimensions are grouped into sets ***of 3 Dimensions each***, forming ***5 sets of 3-dimensional reality fields*** called **HARMONIC UNIVERSES**. The 15-Dimensions composing the 5 Harmonic Universes together represent one TIME MATRIX system.

Each dimension of frequency is composed of **12 Sub-frequency Bands,** or shorter cycles of the "flashing on and off" of scalar-wave points, which exist as part of the longer cycle of the full Dimensional Frequency Band. The Partiki in each dimension have a specific rate of **vibratory-oscillation** (contraction and expansion of energy), which determines the **Angular Rotation of Particle Spin** (angular axis upon which particles will spin). There is a **90-degree shift of angular rotation** of particle spin between each dimensional frequency band and a **45-degree reverse shift** between **Harmonic Universes** (sets of 3 dimensions/frequency bands.)

Particles having varying vibratory-oscillation rates and angles of spin allow multiple dimensional reality fields to co-exist within the same space while remaining perceptually invisible to each other. The *relationships between wave strata* within the dimensional frequency bands create the **holographic refraction** of light, sound and scalar waves that allows consciousness to *perceive the illusions of* **matter solidity, space, time and externalization of reality** while it is ensconced within the structures of dimensionalization.

One 15-Dimensional Time Matrix with 5 Harmonic Universes

PRIMAL ORDER of the Dimensionalized Universal Manifestation Template


HU-5
HU-4
HU-3
HU-2
HU-1
D15
D14
D13
D12
D11
D10
D9
D8
D7
D6
D5
D4
D3
D2
D1
TRIADIC LEVEL
POLARIC LEVEL
ECKATIC LEVEL

A *Dimension* is a full Frequency Band or repeated sequence of "flashing on and off" of scalar standing-wave points within a morphogenetic field.

5 HARMONIC UNIVERSES in one 15-Dimensional TIME MATRIX

Magnetic Repulsion Zones create separation between Harmonic Universes.

3 Levels of the non-dimensionalized **ENERGY MATRIX** within which **TIME MATRICES** reside.

11

Frequency Bands and Sub-Frequency Bands within the 15-Dimensional Scale

Frequency Bands are cyclic, repeated sequences of "*flashing on and off*" of scalar standing-wave points that create the appearance of manifest wave spectra within a dimensional system. ***Sub-frequency Bands*** are shorter cycle segments of the longer "*flashing on and off*" sequence of the *full* Frequency Band. **Frequency and Sub-frequency Bands make up the foundation wave strata of Dimensions.**

1 Harmonic Universe composed of 3 Dimensions, each Dimension composed of 12-Sub-frequency Bands, for a total of **36 Sub-frequency Bands in 1 Harmonic Universe.**
(3 D per 1HU x 12 SFB per D = 36 SFB per 1HU) 1

①

DIMENSIONS	SFB
D3	12 SFB
D2	12 SFB
D1	12 SFB
	36 SFB (12 x 3)

5 Harmonic Universes in one 15-Dimensional Matrix 2

Harmonic Universe	② Dimensions	③ 180 SFB
H 5	D15	12 SFB
	D14	12 SFB
	D13	12 SFB
H 2	D4	12 SFB
	D5	12 SFB
	D6	12 SFB
H 3	D9	12 SFB
	D8	12 SFB
	D7	12 SFB
H 4	D10	12 SFB
	D11	12 SFB
	D12	12 SFB
H 1	D3	12 SFB
	D2	12 SFB
	D1	12 SFB
		180 SFB (12 x 15)

3 15 Dimensions with 12 Sub-frequency Bands each create **180 Sub-frequency Bands in one 15-Dimensional Matrix.** (12 SFB per D x 15D = 180 SFB or 36 SFB per 1HU x 5HU = 180 SFB)

15 Frequency Bands (Dimensions) **and 180 Sub-frequency Bands within the 5 Harmonic Universes of one 15-Dimensional Time Matrix.**
SFB = Sub-frequency Band

PARTIKI PHASING, HARMONICS OF MANIFESTATION AND MATTER DENSITY

Partiki Phasing – *Scalar Standing-Wave flashing.* The internal expansion/ fission/ "flashing on" and contraction/ fusion/ "flashing off" of scalar standing-wave points made of Partiki units. *Partiki Phasing* governs the mechanics of matter manifestation within the Dimensionalized Frequency Bands of the Time Matrix. Through Partiki Phasing HARMONICS of Manifestation and varying levels of matter density are created.

Each of the 5 Harmonic Universes, moving upward in the 15-Dimensional Scale, has a progressively less dense state of perceivable matter. As you go up the Dimensional Scale each Dimension has a progressively faster rate of Partiki Phasing with its corresponding higher frequency, faster oscillation, lower vibration, shorter wave length, greater expansion and less matter density. **These conditions represent the stages of perceivable matter density consciousness will experience as the focus of attention expands progressively upward/outward into the higher Dimensions of the Dimensional Scale through the process of evolution** (accretion of frequency from the Unified Field into the personal morphogenetic field).

As consciousness progressively expands back into the 15-Dimensional structure of its original morphogenetic field, matter density perception will change from perceivable Gross Matter physical density, to Semi-etheric Matter density, to Etheric Matter density, to Pre-matter Liquid Light density and to its original Ante-matter scalar wave form of non-density consciousness. **As the morphogenetic field expands through drawing in more frequencies of consciousness, the perceivable matter density of the body and external reality field progressively lessens.**

Partiki Phasing, Harmonics of Manifestation and Matter Density

1. ***Partiki, Partika and Particum:***
Smallest units of energy-substance. Electro-tonal units of consciousness that are the building blocks of morphogenetic fields, matter and individuated conscious identity. Operate as minute, perpetual motion fission/ fusion generators.



1. Partiki Phasing- expansion/ fission/ "flash on" and contraction/ fusion/"flash off"of scalar points governs the manifestation process

2.

Dimensions #	Harmonic Universe #	density type
1-2-3	HU-1	Carbon based biology physical matter-1
4-5-6	HU-2	Carbon-Silica based biology physical matter-2
7-8-9	HU-3	Silica based biology Etheric matter
10-11-12	HU-4	crystalline liquid-light based biology Pre-Matter
13-14-15	HU-5	standing wave pattern flame or fire body ANTE-Matter

2. Density/ Biology: Progression of Matter Density and related Biology within the 15-Dimensional Scale

3. Harmonics of Manifestation:
Progressive expansion of consciousness into the Dimensional Scale creates progressive perceptual De-manifestation of matter Density within the Hologram of external reality. **Harmonics of Manifestation** are the stages of Matter Density and Vibration-Oscillation Consciousness perceives and passes through within the Dimensional Scale.



5 Harmonics of Manifestation in one 15-Dimensional Time Matrix

UNIVERSAL AND PLANETARY KATHARA

Kathara Level-1: 12-Tree, Kathara Level-2: Crystals, Kathara Level-3: Diodic Points, Kathara Centers and Kathara Lines.

The Kathara Grid is the *primary mathematical-geometrical organization of units of consciousness* upon which Partiki units group to form morphogenetic field scalar grids. It is the CORE level of scalar standing-wave creation and energetic organization within and behind all dimensionalized systems, and is thus considered to be the **Core of the Holographic Template** upon which the morphogenetic scalar wave blueprint and all other dimensions of form anatomy are built. The Kathara Grid is the causal element within all manifest affects of dimensionalization and consciousness.

The form of the Kathara Grid is reflected in the Macrocosm and Microcosm of all manifestation. All forms have at their core the *common structure of the Kathara Grid Holographic Template.* The Kathara Grids of all forms - universes, galaxies, planets and species - are linked to each other and to the Kathara Grid of the Cosmos through the interwoven Partiki scalar standing-wave grids of the *Kathara Grid Holographic Core.* **The *Cosmic Kathara Grid* represents the scalar field of the Cosmic Unified Field of Consciousness-Energy** through which the *Hologram of manifest experience* is perpetually created.

Energy cannot be created or destroyed, it only changes form. Energy IS *Eternal Consciousness* that perpetually changes form by projecting through the structures of the Kathara Grid, while simultaneously remaining *always the same* - the *singular wholeness* of the **Cosmic Unified Field of Consciousness-Energy.**

Structure of the Kathara Level-1 12-Tree Grid Core Scalar Template

12 PRIMARY KATHARA CENTERS:

Kathara Centers are condensed Scalar Wave points that hold the core electro-tonal geometrical-mathematical program for dimensionalized structure. There are 12 Kathara Centers, each holding the program for one Dimension. The program for Partiki Phasing and Vibration-Oscillation for each Dimensional Frequency Band is set in the corresponding Kathara Center. The Kathara Centers set the template for each Dimension, to ground consciousness within the Holographic experience of manifestation.

15 PRIMARY KATHARA LINES:

Kathara Lines are the primary sequences of Partiki Phasing that transmit the electro-tonal programs held within the Kathara Centers from one Dimension to another, to keep the continual flow of consciousness circulating throughout the 15-Dimensional levels of the Morphogenetic Field. When functioning properly, the Kathara Lines connect each Harmonic and Dimension of consciousness to the other and govern the synchronization of cycles of time within the Dimensional Fields and within the morphogenetic field, DNA and body rhythms of dimensionalized forms. **The 3 Vertical Kathara Lines** control the operation of the other 12 Kathara Lines. **The Central Vertical Kathara Line** is the control center for Partiki Phasing rhythms throughout the Kathara Line System.

3 Vertical Kathara Lines = 1-2-3
Central Vertical Kathara Line = 1



KATHARA LEVEL-1 12-TREE GRID

The 2 Interwoven Kathara Grids of Primal Order within the Universal Time Matrix and Cosmic Energy Matrix of the PRIMAL MANIFESTATION TEMPLATE


24(12)
23(11)
21(9)
20(8)
22(10)
18(6)
17(5)
19(7)
15(3)
16(4)
14(2)
13(1)
12
11
9
10
D9
8
D8
6
7
D7
5
3
4
2
1
D15
D14
D13
D12
D11
D10
D6
D5
D4
D3
D2
D1
D1-3 EARTH SYSTEM
TRIADIC LEVEL
POLARIC LEVEL
ECKATIC LEVEL
UNIVERSAL KATHARA GRID
COSMIC KATHARA GRID

12 Centers of the
COSMIC KATHARA GRID
The first Primal Organization of Partiki Scalar Grids that forms the 3 non-dimensional levels of the ENERGY MATRIX and ANTE-matter Density Dimensions 13-15 of the TIME MATRIX.

A *Dimension* is a full Frequency Band or repeated sequence of "flashing on and off" of scalar standing-wave points within a morphogenetic field.

5 HARMONIC UNIVERSES
In one 15-Dimensional TIME MATRIX

12 Centers of the
UNIVERSAL KATHARA GRID
The second Primal Organization of Partiki Scalar Grids that forms the 12 Dimensions of Time Cycles and Pre-matter to Gross Matter Density Levels of the TIME MATRIX, within the ENERGY MATRIX.

3 Levels of the non-dimensionalized ENERGY MATRIX within which TIME MATRICES reside.

5 HARMONICS OF MATTER DENSITY IN THE TIME MATRIX

1. **Gross-matter D1-D3**
2. **Semi-etheric D4-D6**
3. **Etheric D7-D9**
4. **Pre-matter D10-D12**
5. **Ante-matter D13-D15**

= ○

There are 3 **Primary Levels** to the structure of the Kathara Grid. **Level-1: *The Kathara 12-Tree*, Level-2: *The Crystal Seals* and Level-3: *The Diodic Points*.**

Level-1:The 12-Tree holds the first mathematical-geometrical program upon which Kathara Grid Levels 2 and 3 are created, and is composed of the **Kathara Centers** and **Kathara Lines.**

Level-2: The Crystal Seals are groups of 3-Dimensional Partiki scalar wave composites that regulate the rate of *Partiki Phasing* to create the base structures upon which *dimensionalization* is formed. The flow of Frequency (sequences of scalar standing-wave flashing/ cycles of Partiki Phasing) between dimensional bands and Harmonic Universes, the fixed expansion and contraction rates of Partiki, the Vibration-Oscillation and the Angular Rotation of Particle spin are all regulated by the Crystal Seals.

Level-3: Diodic/Miodic Points represent **concentrated areas of energy** that emerge at points where *dimensionalized levels of scalar grids cross over and through each other*, creating **minute vortices** of wave spectra that serve as *frequency modulation zones* (scalar flash-cycle transition points).between Dimensional Frequency Bands. **Diodic Point** vortices are **White Hole** vortices that **transmit energy** into the *Particle Universe* from their counterpart **Miodic Point** vortices within the *Anti-particle Universe*. Through the structure of Dimensionalization, each Harmonic Universe, and the structures contained there within, have within their morphogenetic fields *sets of Diodic and Miodic Points* – sets of **White and Black Holes** – that regulate the flux of consciousness-energy between systems.

The entire cosmic structure is built upon the morphogenetic foundations of *interwoven Kathara Grids*. Within the structures of forms, such as planets or people, the Kathara Grid is the *Core Template of Holographic Manifestation* and controls the structure and function of all of the other *subtle and physical energy systems.*

Planetary scalar templates - **Planetary Shields** - vortices, electro-magnetics, Axiom and Ley Lines are all governed by the operations of the *Kathara Grid*. In the **human body**, personal scalar templates - **Hova Bodies** -, Chakras, Axiom and Meridian Lines and Bio-energetic Field Auric Levels, as well as the physical systems, conscious awareness and DNA, are controlled by the *personal Kathara Grid*. **In terms of generating the *Imprint for Health* within the human organism, as well as *reclaiming dormant potentials of Immortality*, the Kathara Grid is the *causal mechanism* through which such affects can occur.**

KATHARA LEVEL-2 CRYSTAL SEALS GRID

Level-2: The Crystal Seals are groups of 3-Dimensional Partiki scalar wave composites that regulate the rate of *Partiki Phasing* to create the base structures upon which *dimensionalization* is formed. The flow of Frequency (sequences of scalar standing-wave flashing/ cycles of Partiki Phasing) between Dimensional Bands and Harmonic Universes, the fixed expansion and contraction rates of Partiki, the Vibration-Oscillation and the Angular Rotation of particle spin are all regulated by the Crystal Seals.

Planetary Star Crystal Seals

In the ***Planetary Kathara Grid***, the **15 Primary Star Crystal Seals** exist *between* each planetary Vortex or Chakra, on the **Central Kathara Line** or **Central Planetary Axis.** The Star Crystal Seals serve as **"Frequency Seals"** that open or close the *flow of wave spectra* and *Frequency Bands* from one **Harmonic Universe** to another, by regulating and modulating the *sequences of Partiki Phasing and the Vibration-Oscillation rates of Partiki units* within the Dimensional Scale. They control the opening and closing of the *Central Vertical Kathara Line* and *Central Planetary Axis*, through which particles are *phase-locked* into their respective dimensional placements and linear time cycle orientations. Opening of the *Star Crystal Seals* releases the planetary particles and *Ley Lines* from their *dimensional phase-lock*, opening **Inter-harmonic Star Gates (*wave spectra vortices*)** within the Ley Lines, for ***molecular transmutation and time continuum shift***, through blending the Inter-Harmonic wave spectra of the planetary morphogenetic field. **The Planetary Star Crystal Seals control the opening and closing of the 3 *Vertical* Kathara Lines (and Vertical *Star Gate passageways*) of the Level-1: 12-Tree Kathara Grid with in planetary body.**

Biological Star Crystal Seals

In the ***human body*** the **15 Primary Star Crystal Seals** exist *between* each Chakra on the **Central Kathara Line** or **Central Body Current.** The *biological Star Crystal Seals* serve as **"Frequency Seals"** that open or close the *flow of wave spectra and Frequency Bands* from one *Harmonic of consciousness* to another, by regulating and modulating the *sequences of Partiki Phasing and Vibration-Oscillation rates of Partiki units* within the Dimensionalized scalar wave grid of the morphogenetic field. They control the opening and closing of the *Central Vertical Kathara Line* and *Central Body Current*, through which particles are *phase-locked* into their respective dimensional placements and linear time cycle orientations. Opening of the *biological Star Crystal Seals* releases the *body particles* and **DNA** from their *dimensional phase-lock*, opening **Inter-Harmonic Star Gates** (*wave spectra vortices*) within the **DNA**, for **cellular transmutation (via** particle+anti-particle *fusion*) and time continuum shift, through blending the Inter-Harmonic wave spectra. **The Biological Star Crystal Seals control the opening and closing of the 3 *Vertical* Kathara Lines (and Vertical wave spectra vortices) of the Level-1: 12-Tree Kathara Grid within the biological form.**

Seed Crystal Seals

Along with the 15 Primary *Star Crystal Seals* that control the *Vertical* modulation of wave spectra, there are also **15 Secondary Crystal Seals** that control the **HORIZONTAL** Kathara Lines of the Level-1: 12-Tree Kathara Grid within the planetary and biological bodies. The *Horizontal Crystal Seals* are called **SEED SEALS**, they exist and serve as **"Frequency Seals"** ***within*** the planetary vortices and biological Chakras, modulating the wave spectra between Parallel (particle/ anti-particle) Dimensional Frequency Bands.

KATHARA GRID LEVEL-3 DIODIC POINTS

Level-3: Diodic/Miodic Points represent **concentrated areas of energy** that emerge at points where *dimensionalized levels of scalar grids cross over and through each other*, creating **minute vortices** of wave spectra that serve as *frequency modulation zones* (scalar flash-cycle transition points) between Dimensional Frequency Bands. **Diodic Point** vortices are **White Hole** vortices that **transmit energy** into the *Particle Universe* from their counterpart **Miodic Point** vortices within the *Anti-particle Universe*. Through the structure of Dimensionalization, each Harmonic Universe, and the structures contained there within, have within their morphogenetic fields *sets of Diodic and Miodic Points* – **sets of White and Black Holes** – that regulate the flux of consciousness-energy between systems.

Planetary Diodic Points

Within the **planetary body** and morphogenetic field, **Diodic Points** are located in **geographical locations** where Inter-dimensional and Inter-harmonic Horizontal and Vertical Kathara Lines *intersect* to form small **vortices** of inter-dimensional or inter-harmonic wave spectra that serve as passageways – **time portals**- between Dimensional Time Continua or Harmonic Time Cycles. They connect planetary and stellar bodies to their *anti-particle counterparts* and intersect with Vertical Inter-harmonic Star Gates and Horizontal Inter-dimensional Time Portals, through sets of Diodic-Miodic **White and Black Holes** at the center of planetary and stellar cores.

Biological Diodic Points

Within the **biological form** and morphogenetic field, Diodic Points are located in **physical body regions** where Inter-dimensional and Inter-harmonic Horizontal and Vertical Kathara Lines *intersect* to form small **vortices** of inter-dimensional or inter-harmonic wave spectra that serve as ***gateways of consciousness*** between Dimensional Time Continua or Harmonic Time Cycles. They connect physical bodies to their *anti-particle counterparts* and intersect with the Vertical and Horizontal *relationships of wave spectra within the DNA/ RNA and bio-energetic field*, through sets of **White and Black Holes** at the center of the biological Harmonic scalar grids.

Diagonal Grid Control

The *Kathara Grid Level-3: Diodic Points* control the **Diagonal Kathara Lines,** Diagonal *Inter-dimensional portals*, Diagonal *Planetary Ley Lines* and Diagonal relationships between inter-dimensional wave spectra within the biological DNA. **In *Kathara Healing*, the *Diodic Points* are used to open and close the *Diagonal Kathara Lines* for channeling higher dimensional frequency into the Level-1 Kathara Grid, to regenerate the Imprint for Health and to revitalize the Bio-energetic and physical systems.**

THE UNIVERSAL TEMPLAR COMPLEX

- The systems of interwoven Manifestation Templates within the 5 Matter Density Levels of the 15-Dimensional Universal Kathara Grid are collectively referred to as the **UNIVERSAL TEMPLAR COMPLEX.** The Manifestation Template of the human body, likewise structured upon this Primal Order, also manifests through a personal **INTERNAL TEMPLAR COMPLEX** of interwoven 15-Dimensional Manifestation Templates.

- Universal, Galactic and Planetary Scalar-wave Templates of the Universal Templar Complex are called **Scalar SHIELDS.** Shields are sets of 3-Dimensional Scalar Grids upon which the 5 Matter Density Levels of the Universal Manifestation Template manifest. A Shield is composed of the distinct **3 Primary Flash Line Sequences,** or Partiki Phasing Rhythms, characteristic to the 3 dimensions of which the Shield is composed. The Internal Templar Complex of the human body is also organized into 5 sets of 3-Dimensional **Personal Scalar Shields,** through which the matter form and 5 Matter Density Levels of the 15-Dimensional human consciousness are projected into manifest experience.

- Through the intrinsic dynamics of synchronistic Partiki Phasing, each 3-Dimensional Scalar Shield manifests a **3-DIMENSIONAL SPHERICAL ELECTROMAGNETIC DOMAIN** that creates the energetic framework within which externalized manifest experience can take place. Within the Universal Templar Complex, these Spherical Domains form 5 separate yet interwoven Reality Fields or **Harmonic Universes,** each with a different level of Matter Density, rate of Vibrational Oscillation, different Angular Rotation of Particle Spin and variance in Time Cycle orientation. Within the Personal Internal Templar Complex, the Spherical Electromagnetic Domains created by synchronistic, dimensionalized Partiki Phasing form within the 15-Dimensional Time Matrix 5 separate yet interwoven **STATIONS OF CONSCIOUSNESS** called **HOVA BODIES.** The **5 Hova Bodies** of human Manifestation Template Anatomy within the Time Matrix represent the **5 Subtle Energy Bodies** of human bio-energetic field construction, through which human identity experiences series of **SIMULTANEOUS INCARNATIONS** within the various Time Cycles and matter density levels of the Time Matrix. **Human Evolution** is the process by which the electromagnetic frequencies and stations of consciousness of the 5 Hova Bodies progressively merge to transmute the physical matter form backward through the various Matter Density stages through a process called **TRANSMUTATIONAL DIMENSIONAL ASCENSION.**

  Each of the 5 Shields within a 15-Dimensional Manifestation Template is structured upon **3 KATHARA CENTERS** within the core Primal Order of the Level-1 Kathara 12-Tree Grid. Each Kathara Center of the Universal Kathara Grid forms a core point of consolidated frequency called a **SIGNET Star Crystal Seal** within the 3-Dimensional scalar Shields. Within the universal, galactic and planetary Templar Complex the Signet Seals operate as **Star Gates** between the Time Cycles of the 5 Matter Density levels of the 15-Dimensional Time Matrix. Within the Personal Internal Templar Complex, each **Hova Body** is structured upon **3 Kathara Centers** within the embodied Personal Kathara Grid. Each embodied Kathara Center forms a **Signet Star Crystal Seal** within the human anatomy. The embodied **Signet Seals** operate **as Bio-electric Windows** within the **DNA-RNA,** that link the Stations of Consciousness and various **Simultaneous Incarnations** of the identity that exist within the Time Cycles of the Time Matrix to each other, across the illusions of time. Through the embodied Personal Kathara Grid, Scalar Shields, Signet Seals and DNA Windows, the individuated aspects of **ETERNAL IDENTITY** in time are indelibly linked in consciousness. This intrinsic linking of personal consciousness within the various simultaneous cycles of time appears to the embodied human awareness as **REINCARNATIONAL MEMORY.**

The embodied Manifestation Template of the human form is a microcosmic reflection of the Macrocosmic Universal and Cosmic Manifestation Templates. Both microcosmic and macrocosmic Manifestation Templates share, and are interwoven through, the same **Primal Structures** of the Kathara 12-Tree Scalar Grid, the 5 3-Dimensional Scalar Shields and Signet, Star and Seed Crystal Seals and the Diodic Point "Black and White Hole Sets" of energy vortices that manifest upon the Kathara Grid. Human consciousness and biology are directly and indelibly connected to the Universal Templar Complex through the **Personal Internal Templar Complex** of the Personal Manifestation Template.

HEALING AND PRIMAL FULFILLMENT

A rudimentary but operational understanding of the intrinsic structure of the embodied Personal Manifestation Template- (*the **Level-1**Personal Kathara 12-Tree Grid, **Level-2** Scalar Shields, Hova Bodies and Signet, Star and Seed Crystal Seals, and **Level-3** Diodic Points*) - and its relationship to the Universal Templar Complex, allows the embodied human consciousness the opportunity for progressive participation within the processes of **CONSCIOUS EVOLUTION** and intentional restoration of the **Organic Imprint for Health.** All manifest **DIS-EASE** originates through **distortions** in the electro-tonal scalar wave programs of the **Kathara Grid, Scalar Shields** and **Manifestation Template.** To achieve true and lasting healing, rather than suppression and transference of dis-ease to other embodied systems, distortions within the personal Manifestation Template need to be realigned from the causal Kathara Grid level through **REGENESIS** of **Primal Order** within the **Organic Imprint for Health.**

Manifestation Template healing therapeutics based upon knowledge of the Kathara Grid, simultaneously work to restore the natural intended **Primal Order** and function of the human body and consciousness, while expediting the evolutionary process of merging the stations of identity through time, to facilitate fulfillment of the organic **PRIMAL PURPOSE.** The **Primal Purpose** of human evolution is the achievement of **Transmutational Dimensional Ascension** and **Co-creative Mastery** over the Personal Eternal Consciousness and **Internal Templar Complex** within the Holographic Fields of the Time Matrix. Through fulfillment of the **Primal Purpose,** humanity will regain **THE PRIMAL CONDITION** of Conscious AT-ONE-ment with the Universe and the Central Source of Creation, or **GOD.**

The Universal Templar Complex

The First 4 SHIELDS each with 3 SIGNETS and correspondence to the Kathara Centers of the Level-1 12-Tree Kathara Grid.



Kathara Level-2 Scalar Shields & Crystal Seals

The 4 Scalar SHIELDS corresponding to the Kathara Center programs and Harmonics of Matter Density within the *Universal* Manifestation Template.(The 5th Scalar Shield in the 15-Dimensional Time Matrix corresponds to the first 3 Kathara Centers of the *Cosmic* Kathara Grid.) Shields are the 3-Dimensional scalar-wave grids that hold the blueprint for manifestation, as set by the mathematical encoding of Partiki Phasing Rhythm held within the Kathara Centers of the Manifestation Template.

HORIZONTAL SHIELDS

- **A. TELLURIC SHIELD** Gross Matter Shield *Dimensions 1-3*
- **B. DORADIC SHIELD** Semi-etheric Matter Shield *Dimensions 4-6*
- **C. TEURIC SHIELD** Etheric Matter Shield *Dimensions 7-9*
- **D. MAHARIC SHIELD** Pre-matter Shield *Dimensions 10-12*
- **E. RISHIC SHIELD** Ante-matter Shield *Dimensions 13-15* (vertical- not shown)

The 12-Dimensional UNIVERSAL KATHARA GRID within the 15-Dimensional Time Matrix. The 12 Kathara Centers hold the core mathematical and geometrical Partiki Phasing programs upon which the Shields of the Universal Manifestation Template organize.



The 12 SIGNET Star Crystal Seals of the Universal Kathara Grid. SIGNET SEALS are the core points of consolidated frequency corresponding to each Dimension that represent the first manifest arrangement of scalar waves created through the mathematical programs of the corresponding Kathara Centers. The Signets transmit the organizational programs upon which the Scalar Shields manifest. Each 3-Dimensional Scalar Shield manifests on the electro-tonal programs of 3 Signet Star Crystal Seals. Signet Seals keep the Harmonics of Matter Density separate from each other by keeping Partiki units phase-locked into their 3-dimensional electromagnetic domain.

When released, Signet Seals serve as Star Gates, allowing the Time Cycles and Matter Density Levels within the Time Matrix to merge and blend. Signet Seals are the central **control points for Scalar Shield programming.**

The structure of the macrocosmic **Universal Templar Complex** is replicated within the microcosmic structure of the personal **Internal Templar Complex** upon which **15-Dimensional Human Anatomy** manifests.

The Transduction Sequence

The *Transduction Sequence* represents the phases consciousness passes through into dimensionalization and the process by which conscious energy is transduced and *changes form* to enter the wave spectra within which perception of manifestation is possible.

Basic *Transduction Sequence* of Consciousness into Biological Form.

CONSCIOUSNESS TO **PARTIKI UNITS** TO

KATHARA SCALAR GRIDS LEVELS –1, 2 AND 3 TO **PARTIKI GRIDS** TO

MORPHOGENETIC FIELDS TO **MERKABA FIELDS** (Sets of Counter-rotating electro-magnetic spirals of energy –repeating scalar wave flash/ Partiki Phasing sequences that run between Dimensions and Harmonic Universes)

TO **DNA/ RNA IMPRINT** TO **BIO-ENERGETIC AURIC FIELD** TO **CHAKRAS**

TO **NADIAL CAPSULE** (tissue-like capsule that forms around the 3-Dimensional scalar grid of the Harmonic Universe-1 morphogenetic body.) TO

DNA/ RNA MANIFEST TO **NADIS** (energetic rivulets that feed energy from the Nadial Capsule into the Central Nervous System and molecular structure) TO

NUCLEAR CORE TO

CNS-METABOLIC/ BIOLOGICAL RHYTHMS- BLOOD-BRAIN-CHEMICALS-HORMONES-ORGANS-TISSUES.

HOLOGRAPHIC REALITY CONSTRUCTION

The Unified Field of Conscious-Energy

THE **SCALAR STANDING-WAVE GRIDS** THAT MAKE UP **DIMENSIONALIZED MORPHOGENETIC FIELDS** REPRESENT THE *INTRINSIC STRUCTURE* OF THE **COSMIC UNIFIED FIELD OF ENERGY** WITHIN WHICH ALL THINGS EXIST. *ENERGY IS CONSCIOUS AND CONSCIOUSNESS IS ENERGY.* **CONSCIOUSNESS-ENERGY CANNOT BE CREATED OR DESTROYED IT SIMPLY CHANGES FORM,** WHILE SIMULTANEOUSLY REMAINING ALWAYS THE SAME – **THE ETERNAL UNIFIED FIELD OF CONSCIOUSNESS.**

The Kathara Grid

ALL FORMS OF CONSCIOUSNESS AND PERCEIVABLY MANIFEST FORMS *DERIVE THEIR INDIVIDUATION* WITHIN THE UNIFIED FIELD THROUGH THE STRUCTURE OF THEIR **INDIVIDUATED MORPHOGENETIC FIELD.** THOUGH HAVING MUCH DIVERSIFICATION WITHIN THE **GEOMETRICAL-MATHEMATICAL PROGRAMS** THAT FORM **INDIVIDUALITY** WITHIN LIKE PATTERNS, THE *CORE OF ALL INDENTITY AND MANIFEST FORM IS THE SAME* – THE INTRINSIC STRUCTURE OF **THE KATHARA GRID – THE CORE HOLOGRAPHIC TEMPLATE OF DIMENSIONALIZATION UPON WHICH MORPHOGENETIC FIELDS ARE FORMED.**

Interwoven Morphogenetic Fields

THE INHERENT STRUCTURE OF **INTERWOVEN KATHARA GRIDS** FORMS **SPHERICAL DIMENSIONALIZED MORPHOGENETIC FIELDS** WITHIN WHICH CONSCIOUSNESS CAN EXPERIENCE THE **HOLOGRAPHIC PROJECTION** OF MANIFEST REALITY, SPACE, TIME, MATTER AND EXTERNALIZATION. THE SPHERICAL MORPHOGENETIC STRUCTURES OF THE **MICROCOSM** EXIST WITHIN THE GREATER SPHERICAL MORPHOGENETIC FIELDS OF THE **MACROCOSM**, FORMING A SYSTEM OF CONSCIOUS-ENERGETIC **SPHERES-WITHIN-SPHERES** THAT REPRESENTS THE ***INTERWOVEN MORPHOGENETIC FIELDS*** **OF THE COSMIC UNIFIED FIELD OF CONSCIOUSNESS-ENERGY.**



Spheres-within-Spheres ***Interwoven Morphogenetic Fields***
The Microcosm within the Macrocosm. The individual within the species within the planetary within the galactic within the universal within the cosmic within the INFINITE AND ETERNAL.

Five Over-lay Universes exist within the same space in 1 15-Dimensional Matrix.

CHAPTER 1 HIGHLIGHTS

THE HOLOGRAPHIC TEMPLATE

- **External reality is a HOLOGRAPHIC PROJECTION.** Perception of **solidity** and **externalization** are determined by the **oscillation rates** between **dimensionalized units of consciousness** - ***Partiki, Partika*** and ***Particum.*** Dimensionalized units of consciousness form **Frequency Bands** that exist in specific relationships to each other. We perceive as solid the Frequency Bands that exist **1** full Dimensional Band **below** the frequencies within which the consciousness is stationed.

- **Dimensionalization** creates the structure through which consciousness can perceive the **Hologram of Externalization.**

- The human body is a **Hologram** built upon a **Holographic Template** of units of consciousness structured into **Scalar Standing-wave Grids** that represent the **Living Morphogenetic Field** blueprint upon which matter and dimensionalized consciousness manifest.

THE STRUCTURE OF DIMENSIONS

- The **Unified Field** is built upon ***dimensionalized sets*** of ***Scalar Standing-wave Points*, Wave Strata** formed of units of consciousness that form the basis of energetic relationship through which the **Hologram of Manifestation** can be perceived.

- The human body is a construct of ***Conscious Energy***, built upon **a15-Dimensional Anatomy of Dimensionalized Scalar-Grids.** Perceived physicality emerges through the **Perceptual Lens of Dimensionalization** which provides the picture of seemingly manifest particles, atoms, molecules and physical systems.

- Understanding the nature and structure of **Holographic Reality** allows us to understand the foundations upon which the **body is** built and the **context** within which **healing** must occur.

- **Scalar Waves** are standing wave points that emanate out of fixed points of sound (electro-tonal Partiki units), which form the **Scalar Grid morphogenetic templates** that house consciousness in **dimensionalization** for experience of manifest reality. Scalar Grids are created through **Partiki Phasing.**

- **Partiki Phasing** is the process of ***internal fission/ expansion and fusion/ contraction*** characteristic of **Partiki Units,** through which the units perpetually break apart and replicate through *fission*, then re-merge through *fusion*. Creates a *"flashing on and off" of* ***Scalar Wave points,*** or **"Flash-line Sequences"** that determine the intrinsic orientation of consciousness within the Scalar Grids composing morphogenetic fields.

- **Dimensions** are Scalar Grids of consciousness composed of interwoven layers of Scalar waves with **varying Flash-line Sequences**, or *Frequency Bands.* **Dimensions are Frequency Bands**, or Partiki wave spectra, that exist within specific relationship to each other to form the template of Holographic Reality.

- **Frequency Bands** are synchronized, repeating ***Flash-line Sequences of Partiki Phasing*** that give the appearance of manifest movement of wave spectra within a Dimensional Scalar Grid **Sub-frequency Bands** are *portions* of the *Flash-Line Sequences* that make up the whole Dimensional Frequency Band. The Frequency of a Dimensional Band is determined by the **Vibratory-Oscillation** rate of Partiki units that make up the Dimensional Scalar Grids.

- **Vibration** is the "internal movement" or **ENERGY HOLDING** of Partiki units. **Oscillation** is the "external movement" or **ENERY EXPENDED** by Partiki units. **Vibratory-Oscillation rate is the rate at which Partiki Phasing "flashing on and off" occurs**. Vibration and Oscillation exist in **direct proportion** to each other. As Vibration increases (energy holding), Oscillation decreases (energy expenditure). Faster Flash-line Sequences (higher frequency) *expend* more energy, raise Oscillation and lower Vibration of Scalar Templates. **Higher Oscillation/ Slower Vibration creates slower electron movement around nucleus and less perceivable density of matter.**

- A **Dimension** is a full Frequency band or **full cycle** of a **Flash-line Sequence.**

- The **Universal Morphogenetic Template** is built upon ***sets of 15 Primary Flash-line Sequences*** that form **15-Dimensional Time Matrices** within which manifestation can be experienced.

- **Dimensions are organized into sets of 3, (**3 full Flash-line Sequences/ 3 Frequency Bands), that create the template through which 3-dimensional manifestation can be experienced. Each set of 3 Dimensions is called a **Harmonic Universe**. There are **5 Harmonic Universes** within a **15-Dimensional Time Matrix.**

- Each Dimension contains **12 Primary Sub-frequency Bands** (partial Flash-line Sequences).

- Partiki in each Dimension have specific set **Partiki Phasing rhythms** giving each Dimension a specific ratio of **Vibration-Oscillation.** Higher Dimensions have Faster Partiki Phasing, are higher frequency and thus have higher oscillation, lower vibration and less particle density.

- **Vibratory-Oscillation** rate within a Dimension determines the **Angular Rotation of Particle Spin (ARPS)**, or *rotational axis of particles* in a Dimension. There is a **90-Degree Shift** in ARPS between each Dimension and a **45-Degree Reverse Shift** in between Harmonic Universes.

- Particles having varying **Vibratory-Oscillation** rates and **ARPS** allow *multiple 3-Dimensional Reality Fields* to *co-exist* within the same space while remaining perceptually and experientially **invisible** to each other.

- The **relationship between wave strata** and **variance in Partiki Phasing Flash-line Sequences** within Dimensional Frequency Bands create **Holographic Refraction** of consciousness-energy that allows perception of an externalized, 3-Dimensional **Holographic Illusion** for consciousness focused within the Scalar Grids of the 15-Dimensional Time Matrix.

UNIVERSAL AND PLANETARY KATHARA

- The **Kathara Grid** is the **first level** of Partiki structure/ *Scalar Grid organization* that sets consciousness into dimensionalization. It is thus the **CORE HOLOGRAPHIC TEMPLATE** upon which the *morphogenetic field blueprint* is structured.

- The *Kathara Grid* is the *Core Holographic Template* for **dimensionalization of the Unified Field** of Consciousness-Energy through which the **Microcosm** and the **Macrocosm** are structured. **All things are built upon the foundation of the *Kathara Grid.***

- There are **3 Primary Levels to the Kathara Grid. Level-1:** ***The 12-Tree Grid*** with **Kathara Centers** and **Kathara Lines. Level-2:** ***The Crystal Seals*** with **Hova Bodies** and **Scalar Shields** and **Level-3:** ***The Diodic Points*** of minute energy vortex "**White and Black Hole" sets.**

KATHARA GRID LEVELS

KATHARA 12-TREE GRID

- **Level-1 Kathara** holds the base electro-tonal **programs** of Partiki Phasing and Dimensional/ Frequency structure upon which the other Kathara Levels and the morphogenetic field are built.

KATHARA SCALAR SHIELDS AND CRYSTAL SEALS

- **Level-2 Kathara Grid** is composed of 5 groups of 3-Dimensional **Scalar Shields** and **Crystal Seals** - that regulate the rates of Partiki Phasing to create the base structures upon which ~~dimensionalization is built.~~

KATHARA DIODIC POINTS

- **Level-3 Kathara Grid** is made of sets of minute White and Black Hole energy **vortices,** made of inter-dimensional Scalar Wave spectra, that **regulate the flux of consciousness-energy** between Dimensional, Harmonic and Parallel/ anti-particle systems.

- ***Cosmic*** *morphogenetic structure* is built upon interwoven **Kathara Grids** and the Dimensionalized Scalar Standing-wave Templates they form.

- The **5 Primary Scalar Templates of Dimensionalization** are formed on **Scalar Shields** composed of sets of 3 Dimensions, which form *5 3-dimensional spheres of energy* called **HOVA BODIES**. Hova Bodies and their Scalar Shields hold consciousness-energy into **5 separate but interwoven 3-dimensional systems.**

- The **Kathara Grid** and the multiple levels of morphogenetic structure built upon it is the **CAUSAL ELEMENT** behind and within all manifestation, and thus the **CORE HOLOGRAPHIC TEMPLATE** through which the **Imprint for Health** can be restored to Biology.

- All manifest **Dis-ease** originates through **distortions** in the natural electro-tonal programs/ *Partiki unit arrangements* of the *Kathara Grid* and *Hova Body Scalar Shields*. The Kathara Grid and morphogenetic field are the **core elements** through which **lasting healing** is created. **Healing** occurs through **REGENESIS** of natural electro-tonal **programs** of the **Holographic Template.**

- **Partiki Units, Scalar Standing Waves, and Crystalline Keylons and Keylon Codes** represent the **PRIMAL SUBSTANCE** in energy that consciousness takes on in order to create the **Holographic Projection** of external manifestation.

- The **Kathara Grid, 15-Dimensional Structure, Scalar Shields, Crystal Seals, 5 3-Dimensional Harmonic Universes and Hova Bodies, Diodic Point** vortices and the subtle and dense matter energetic systems that manifest upon them represent the **PRIMAL ORDER** of mathematical and geometrical interrelationship that **Primal Substance** utilizes to orchestrate the manifest Hologram through creation of **Manifestation Templates.**

- The interwoven, ordered structures of scalar wave fields that form the **Universal Manifestation Template** of the 15-Dimensional Time Matrix are collectively referred to as the **UNIVERSAL TEMPLAR COMPLEX.**

- The interwoven, ordered structures of scalar wave fields that form the **Personal Manifestation Template** of **15-Dimensional Human Anatomy** are collectively referred to as the **Personal INTERNAL TEMPLAR COMPLEX.** The Internal Templar Complex, a structural replica of the Macrocosmic Universal Templar Complex, anchors personal consciousness into the Time Matrix for the experience of the space, time and matter Hologram.

- The **PRIMAL PURPOSE** of human evolution is the achievement of **Transmutational Dimensional Ascension** and **Co-creative Mastery** over the **Personal Eternal Consciousness** and **Internal Templar Complex** within the holographic fields of the Time Matrix. **REGENESIS** of **Primal Order** within the **Organic Imprint for Health** creates true healing and expedites the natural processes of human evolution.

- Through fulfillment of the **Primal Purpose** humanity will regain **THE PRIMAL CONDITION** of **Eternal Conscious At-ONE-ment** with the Central Source of Creation or **GOD.**

CHAPTER 2

(Section One: *Foundations of Kathara Healing* – Part II)

THE ELEMENTS OF HEALING

The Human Body Kathara and the Multi-dimensional Anatomy of the Human Form

- THE MAHARIC SHIELD AND THE IMPRINT FOR HEALTH
- THE PLANETARY BIO-FEED INTERFACE SYSTEM (PBIS)
- THE HIEROPHANT SYMBOL CODE, PBIS AND THE MAHARIC SHIELD
- MORPHOGENETIC EXPANSION, GROWTH CYCLES, DEATH AND MOLECULAR COMPACTION
- LEVELS OF HUMAN ANATOMY, EMBODIED KATHARA 12-TREE GRID, CRYSTAL SEALS, SHIELDS, SIGNETS, HOVA BODIES, AURIC CAPSULES, DIODIC POINTS, SEED SEALS, CHAKRAS, AXIOM LINES, THE HARA LEVEL AND DNA.
- THE 12 HUMAN SENSES, APPARTHI AND HUMAN PERCEPTION

TOPICS OF DISCUSSION

THE HUMAN BODY KATHARA AND THE MULTIDIMENSIONAL ANATOMY OF HUMAN FORM

The Structures of Manifestation and Reclaiming Our Power

In *PART-I* of this program, **THE CONTEXT OF HEALING**, we explored the hidden foundations of *reality structure* within which our existence takes place, the *context of relativity* through and within which *healing* occurs. We learned that the context of existence can be viewed as taking place within a **Unified Field of Energy**, and that **Energy IS consciousness and Consciousness IS energy.** In our exploration we encountered the **Partiki, Partika** and **Particum**, the ultra-micro-particle units of consciousness in electro-tonal form, through which the tangible structure of living **Morphogenetic Fields** are formed. In learning the foundation structures of the Unified Field of Consciousness-Energy, we come to understand that the anatomy of any form, including that of the human Body-Mind-Spirit System, is a **multi-dimensional construct** built on an ordered template of **sets of 15-Dimensions**, through which all conditions of apparent manifestation are created.

Through reviewing the underlying structures of manifest reality (units of consciousness, the ***Partiki Scalar Standing-wave Grids*** that hold consciousness into individuated dimensionalized "packages" of awareness to allow for experience of space, time, matter and form, the core ***Kathara Grid Holographic Template*** that sets the pattern of dimensionalization for consciousness to follow into the manifest experience, the ***Levels of Matter Density*** corresponding to the ordered structure of Dimensions, and the reality that **Dimensions** are *tangible constructs of energy* created through the process of ***Partiki Phasing***-the fission-fusion "flashing on and off" of scalar standing-waves composed of units of consciousness) **we have already expanded our perceptions of the nature of reality itself.** With these **simple revelations of knowledge**, we have shifted ourselves from a perspective of viewing the reality before us as one of *separate manifestations disconnected from our being*, to a perspective of viewing reality as an *intricate system of interwoven consciousness, expressing in the form of standing-wave strata*, to which we are *intimately and indelibly connected.*

Suddenly we find that we cannot be "left out" of things, we cannot "be on the outside as life passes us by", **that there IS no "outside" to which we may stand separate, as by the *nature of our existence* we are an *intrinsic element and force of creative affect* within the whole of creation.** Through this knowledge we have begun to tap the **secrets of SELF**, as we shift from viewing ourselves as *mortal creatures trapped within a gross-matter finite physical body*, to **KNOWING OURSELVES AS THE EXPRESSION OF CONSCIOUS, SENTIENT WAVE-STRATA - ETERNAL BEINGS ENSCONCED WITHIN AN ETERNAL UNIVERSE, within which Energy-Consciousness cannot be created or destroyed, it simply changes form perpetually.** We move from perceiving ourselves as finite beings of limited power to affect a world that is separate from us, to knowing that we are *walking wave-forms within a sea of interrelated wave forms*, and that the pattern of our being operates as an intrinsic part of the whole. **As we begin to perceive ourselves in terms of the *unlimited reality of our nature*, rather than define ourselves by the limited boundaries of the *manifest illusion before* us, we begin to reclaim our power to *affect desired change* within the contours of our lives.**

Knowledge, KNOWING and the Imprint for Health

Knowledge is an agent of freedom, IF it is used to foster practical applications of change. Knowledge can also become a *perpetual quest of distraction*, through which we deny ourselves the ability to EMBRACE the experience of living as we seek outside of ourselves the answers that live within. **Knowledge is power if it is applied appropriately, it can be an agent that leads one through the door to the WISDOM that awaits on the other side.** Knowledge alone cannot provide **cognition,** cognition comes through the *application of applied knowledge* to provide **tangible, experiential** KNOWING, a knowing derived only through the **direct experience of BEING. In Kathara Healing™ *knowledge* is applied as a *tool* through which one can grow into the *wisdom of direct experience*** - from ***thinking or believing***, which are knowledge/data-based characteristics of a mind perceiving itself as *finite* - to **KNOWING,** through Direct Cognition of the Experience of BEING, which is a characteristic of a consciousness KNOWING itself as ETERNAL. .

In our first lessons of **Kathara Healing,** we gained *knowledge* of the *Context of Healing* and the *structure* of that which exists within and around us, so that we may become more empowered to serve as a *healing force*, within ourselves and within the collective of the Whole. **But this knowledge will only become practical or useful to us if it is applied to foster the direct experience through which the wisdom of KNOWING** may emerge. Then, and only then, will we be changed...then and only then will we become *true agents of healing*. **Knowledge can help you to *understand the nature of health and healing*, but only through KNOWING HEALTH through *direct experience* will you be *healed*.** To KNOW HEALTH we must rediscover this quality within ourselves, to EXPERIENCE the *quality of wellness* that emerges as the **Imprint for Health** is reawakened within the human body. **First we must use *knowledge* to recognize that the *Imprint for Health* is there, sleeping silently within us awaiting this awakening.**

Healing the Causal Core

Fixing symptoms does not restore the *Imprint for Health*, it simply masks from view the *causal elements* through which non-health manifested. Removing the symptom *without addressing the underlying cause* simply sets the stage for the cause to *re-manifest itself* in new ways, through *new sets of symptoms*. **Each symptom you remove will give birth to another symptom if the *underlying cause* is not changed.** Kathara Healing addresses the **deepest *causal factor*** in manifestation, the **Holographic Template Kathara Grid,** upon which all conditions come into being. **Within the intrinsic structure of the Kathara Grid the dormant *Imprint for Health* is sleeping, and through knowledge of the Kathara and applications of its methods we can reawaken the Imprint for Health within ourselves, to progressively move into KNOWING HEALTH** through the cognition of Direct Experience.

In Kathara Healing you are provided with the knowledge you need to understand the structures upon which the *Imprint for Health* is built, for in understanding these structures you will be enabled to call the Imprint for Health into awakening. **But it is through the APPLICATION OF KATHARA TECHNIQUE that you will AFFECT CHANGE. The technique applications offered in Kathara Healing allow you to "bring the knowledge home" to the core of its usefulness, the ability to lead you into the *direct experience of health-ward change*.**

Elements of Healing

In **PART II THE ELEMENTS OF HEALING,** we will apply the knowledge of the *Context of Healing* that we acquired in *PART I,* directly to its relevance in terms of the **HUMAN BODY**. We will now explore **Kathara Mechanics** as they apply directly to the human system, and you will gain the knowledge of your **15-Dimensional Anatomy** through which you may then effectively utilize **Kathara Mechanics Techniques** to begin your journey into the **EXPERIENTIAL REALITY OF HEALING.** We will discover the long forgotten potentials of the ***Planetary Bio-feed Interface System™*** and how to receive energy for healing directly from the Kathara Grid of the Earth. We will explore the real processes within and behind the experience of growth through time, so that we may finally identify the **true causal element intrinsic to the *degeneration* and *death* of the body.** We will come to understand the functions of the Body-Mind-Spirit System as they are **INTENDED to operate**, to identify the areas in which malfunction is occurring, so that we may *remedy the casual factors* to progressively restore the **INTENDED INTEGRITY OF THE BODY-MIND-SPIRIT SYSTEM. In PART II we will reclaim our knowledge of our *multidimensional anatomy*, and rediscover the buried secrets of awakening the *Imprint for Health*.**

MAHARIC SHIELD

The Imprint for Health and the *Maharic Shield*

Restoration of health within the body is a progressive endeavor that takes time. Portions of the Body-Mind-Spirit System that have been malfunctioning must readjust to a new process of function that will progressively work its way up from the core **Kathara Grid Holographic Template**, into the **Bio-energetic Field**, **Chakra System** and **DNA**, to progressively ***reset*** the **Imprint for Health** within the Body-Mind-Spirit System. **The Imprint for Health sleeps soundly now within a portion of the multidimensional anatomy called the *MAHARIC SHIELD*.** The Maharic Shield is a buried treasure of **REGENERATION and REVITALIZATION** of the human organism, as it is the key to *recoding the human Kathara Grid* back into its original Imprint for Health. **The *Imprint for Health* is a tangible construct of energy that is located within the structure of the *Maharic Shield*.** In calling these dormant energy systems into activation within the body, one has the opportunity to restructure the causal level of malfunction, and to recode the Holographic Template upon which malfunction manifests.

Reciprocal Reflection and the Kathara Grid

All conditions of dis-ease within the Body-Mind-Spirit System *share a common core of causality* - *distortions of the Kathara Grid* upon which manifestation is built. All symptoms affect the Body, Mind and Spirit *simultaneously*, malfunction in one aspect of being will have its *reciprocal reflection* in the other aspects of being, as the symptoms emanate from distortion in the *Kathara Core*, upon which all aspects of being simultaneously manifest.

As we work with restoring integrity to the *Holographic Template Kathara Grid*, we are thus creating *simultaneous restoration through Reciprocal Reflection* within the *Body*, the *Mind* and the *Spirit* (the CONSCIOUSNESS that makes up the substance of our multidimensional anatomy and identity).

The Maharic Shield and Whole-Being-Healing

In activating the *Maharic Shield* to regenerate the *Imprint for Health*, you will have change occurring within multiple levels of being. Your **BODY** will begin to reflect change as dis-ease-causing distortions are released from the *biological imprint*, and a higher level of order is reestablished within the ***atomic structure.*** Your **MIND** will begin to reflect change as dis-ease-causing distortions in your **thoughts, ideas and beliefs** are released from the *mental body* awareness. Your **SPIRIT**-consciousness, will reflect change, as divisions between your embodied awareness and the expanded portions of your multidimensional awareness will begin to dissolve, and you will become progressively more able to embody greater states of *cognition, creativity and awareness.* ***Kathara Grid recoding* through the use of the *Maharic Shield* will set in motion the processes of WHOLE BEING HEALING, as the *Imprint for Health* is progressively reawakened and restored within the Body-Mind-Spirit System**. Activation of the **Maharic Shield** within the personal Kathara Grid will lay the foundations for progressive, lasting and powerful restoration of the **Imprint for Health** within your Body-Mind-Spirit System.

Learning to activate the Maharic Shield to restore the Imprint for Health requires a bit of **knowledge** regarding *Elements* of the hidden anatomy of multidimensional being, and application of specific **energetic mechanics** that will directly affect these hidden structures of energy. We will begin PART II with a discussion on the **ELEMENTS OF HEALING as they apply to *developing the skills required to create the condition of Maharic Shield activation*, through which the *Imprint for Health* can receive its wake-up call.**

THE PLANETARY BIO-FEED INTERFACE SYSTEM™

Awakening the Personal and Planetary Templar Complex Connection

Interwoven Personal and Planetary Kathara Grids

The core Holographic Templates of both the *personal* and the *planetary* morphogenetic fields are built upon a Scalar standing-wave *Kathara Grid*. As the morphogenetic fields of **species** are interwoven into the larger morphogenetic field of the **planet** they inhabit, there is a **direct energetic connection between the Kathara Grids of individuals and that of the planetary body. This connection between personal and planetary Kathara Grids is called the *Planetary Bio-feed Interface System™*, - PBIS.** For thousands of years the **planetary Kathara Grid** has carried **distortions** in its natural pattern that have rendered the **PBIS** primarily inoperable. **Kathara distortions in the planetary morphogenetic field blocked the human's innate ability to draw energy for regeneration and revitalization from the planetary morphogenetic field.**

When the human Kathara Grid system is working properly there is a *natural sympathetic rapport* between the personal and planetary Kathara Grids that keeps the *Imprint for Health* within the human *Maharic Shield* functioning properly. Due to the distortions of the planetary Kathara, the human Kathara developed **reciprocal distortions,** which created **blockages between the Maharic Shield Imprint for Health and the other functional portions of the human Kathara.** The blockages with the human Kathara manifested as distortions within the natural function of the **DNA** and bodily systems, disarming many of the natural *self-regenerative functions* organic to human biology and rendering the human form more susceptible to disease and malfunction of the biological system. As there is a **Reciprocal Reflection** of patterns between the Body, Mind and Spirit aspects of the human organism, due to their *common causal element* of the *Kathara Grid Holographic Template*, **distortions within the DNA and physical body function also become reciprocal distortions** within the **mental body** and its **perceptual facilities,** and within the **Spiritual Body,** as the Kathara distortions *block and distort* the organic cycles through which higher dimensional aspects of consciousness would progressively embody within and expand the human form.

The Planetary Bio-Feed Interface System™

As the morphogenetic fields of species are interwoven into the larger morphogenetic field of the planet they inhabit, there is a direct energetic connection between the Kathara Grids of individuals and that of the planetary body. This connection between personal and planetary Kathara Grids is called the *Planetary Bio-feed Interface System* ™, - PBIS.


PERSONAL KATHARA GRID
12
11
9
10
8
6
7
5
3
4
2
1
Organic connection between Personal and Planetary Templar Complexes
LINK AT EARTH'S CORE
CREATING THE PBIS -
Planetary Bio-feed Interface System™
Interwoven Personal and Planetary Kathara Grids
EARTH
PLANETARY KATHARA GRID
1
2
4
3
5
7
6
8
10
9
11
12

Return of the PBIS - Gift of the 21st Century

The secrets of utilizing the PBIS have been passed down within the generations of the Melchizedek human families who brought these teachings to Earth long ago, kept hidden from public display until a day when the PBIS could once again become operational through evolution and clearing of the planetary Kathara Grid. These teachings are now being returned into the public arena because **progress has been made in restoring the integrity of the planetary Kathara Grid system. For the *first time in many thousands of years* the potentials of healing held within the PBIS can be returned to humanity, and the PBIS can now be *activated within the personal biology* to reawaken the *Maharic Shield* and its *Imprint for Health*, within the human Kathara System.** Reawakening the *PBIS* and the *Maharic Shield* within the human body *allows the personal Kathara Grid to open into the planetary Kathara Grid*, through which the now-functional **Holographic Template of the planetary Kathara can be used to RESET the original imprint of function within the personal Kathara,** for accelerated regeneration of the **Imprint for Health** within the human form.

HIEROPHANT SYMBOL CODE

The *Hierophant Symbol Code* PBIS Trigger

The first application of the PBIS that we will employ in Kathara Healing is utilizing the energies flowing through planetary Kathara to reawaken the Maharic Shield within human anatomy. The process of opening the PBIS within the personal morphogenetic field involves using a **specific scalar standing-wave-guide GEOMANCY - a consolidated inter-dimensional *frequency pattern* that triggers release of the *frequency seals* (Kathara Level-2 Crystal Seals) on the presently dormant 10th, 11th and 12th Chakras, opening the human Bio-energetic Field and Kathara Grid to the Kathara Grid, Bio-energetic Field, Ley Lines and energy Vortices of the planetary morphogenetic field.** The wave-guide Geomancy containing the frequencies to activate the PBIS and the Maharic Shield can be directed by the human consciousness **in the form of a visually created symbol code. This symbol code is called the HIEROPHANT.** In **TECHNIQUE # 2: *The Maharic Seal and the Liquid Light Cleanse***, to be explored in ***PART III. of Section I,*** the **Hierophant Symbol Code** will be used to bring the **Maharic Shield** and the **PBIS** out of dormancy, in order to **RESET** the **Imprint for Health** within the operational Holographic Template of the human **Kathara Grid.**

The *Hierophant Symbol Code Scalar Wave Guide* for Kathara Reprogramming

Thoughts and **Images** formed by the mind represent **small morphogenetic fields** with minute **Kathara Grids**, that become interwoven into the larger morphogenetic field and Kathara Grid of the human multidimensional anatomy. ***THOUGHTS ARE THINGS*** **in terms of the bio-energetic reality of the body and the Kathara Grid;** ***thoughts become translations*** **of electro-tonal "*digital*" *instructions* within the human bio-energetic field, and directly enhance or detract from the natural function of the electro-tonal programs of the human Kathara Grid.** In recognizing the **power of thought** ***as the power of creation of scalar standing-wave grids***, we can begin to apply that power effectively in regeneration of the Kathara Holographic Template, by **directing needed** ***electro-tonal instructions*** **for awakening the** ***Maharic Shield*** **into the embodied Kathara Grid.** The **Hierophant Symbol Code**, used in the form of a **visualized image**, sets a **powerful electro-tonal program** within the human Kathara, a program that **triggers the opening between the human Kathara and the PBIS**

The ***Hierophant Symbol Code*** **appears in the form of a** **Pale Silver Merkaba Star, a six-pointed "Star of David", which represents the** ***electro-tonal program*** **of the** ***11th and 12th-Dimensional aspects of the Universal Kathara Grid.*** The **frequency wave spectra** perceived by the human mind as **Pale Silver** represents the **electro-tonal program** of the ***Dark Silver*** *primary frequency band of the 11th-Dimensional wave spectra, combined with the* ***Pure White*** *primary wave spectra of the 12th-Dimensional frequency bands*. Using the **Hierophant Symbol** wave guide to direct *frequency and electro-tonal instructions* through the Kathara Grid, creates a ***scalar standing-wave pattern of 11th and 12th Dimensional frequency*** **within the personal Kathara Grid,** the frequencies in which the **original** ***electro-tonal instructions*** for the ***Imprint for Health*** are stored. By **awakening the 11th and 12th Dimensional frequencies within the human Kathara and bio-energetic field**, all of the *lower frequencies* within the Kathara electro-tonal program become **modulated and recoded** into their *organic, undistorted pattern*, by the *stronger wave influence* of the higher 11th and 12th Dimensional frequencies, which *contain within themselves* the organic imprint for the *entire dimensionalized wave spectra* of the dimensions that *oscillate below* them.

The Hierophant Symbol Code
Scalar Wave Guide for Kathara Reprogramming


PURE WHITE
12TH Dimensional Frequency
DARK SILVER
11TH Dimensional Frequency
PALE SILVER
11TH – 12TH Dimensional Frequency
THE HIEROPHANT SYMBOL CODE

Visualize the Hierophant Symbol Code as a *2-dimensional "flat" image* "drawn in Pale Silver Light".

The 11th-12th-Dimensional Scalar Standing-wave Guide for activating the Maharic Shield and the PBIS.

Ease of Kathara Healing Techniques

Through using the *Hierophant Symbol Code* we awaken the restorative frequency patterns within the *Maharic Shield* and the *PBIS*, beginning the process of regenerating the organic *Imprint for Health in* the human Holographic Template Kathara Grid. The restorative affects of using the *Hierophant Symbol Code* to activate the *Maharic Shield* and the *PBIS* will occur upon using the *Kathara Mechanics* provided in Technique # 2, *whether or not* an individual understands the realities in frequency that are taking place through using this process. **Therefore, the complex mechanics of activating the *Maharic Shield* to reset the *Imprint for Health*, can be *reduced to simple instructions* for the direction of energy.** Though the theory of Kathara Healing is highly *detailed and complex*, the Techniques by which *active results are achieved* employ simple exercises in ***Mental Symbol Code Visualization*** and mental energy direction, coupled with the application of simple ***Kathara-stimulating massage*** to specific corresponding body points. **The *Techniques* of Kathara Healing and regeneration of Kathara Grid integrity are *so simple* that even a young child can learn to actively employ them, to achieve the desired result of restoring the *Imprint for Health*.**

MORPHOGENETIC EXPANSION

Frequency Accretion, Growth, Age Rhythms, Degeneration, Death and Kathara Blockage

Frequency Accretion and Growth Through Time

The morphogenetic field of the human body evolves through time via the process of **Frequency Accretion**. The human morphogenetic field *exists within* the larger morphogenetic field of the planetary and universal dimensionalized **Unified Field of Consciousness-Energy.** Through the inherent function of the **Kathara Grid** and the multi-layered systems of energy built upon it, *progressively more frequency and corresponding wave spectra* from the *dimensionalized Unified Field* are **drawn into** the *personal morphogenetic field* to create **progressive expansion of the morphogenetic imprint and its resulting progressive *expansion of consciousness* and *growth of the physical body* in time.**

Kathara blockages and Organic Growth Cycles

Blockages and scalar wave distortions within the **Kathara Grid** *impede* the natural functions of **Frequency Accretion**, and so **distort the intended natural processes of consciousness expansion and growth of the body form in time.** When the Kathara Grid is functioning properly, there are **certain *specific points in linear time*** **when *specific aspects of morphogenetic expansion* via Frequency Accretion are intended to occur.** The **original cycles of growth and expansion inherent to the human form** occurred between **1. fetal integration through age 11-12, 2. age 11-12 through age 22, 3.age 22 through age 33** and **4. age 33 through age 44**, at which time the human morphogenetic field would reach its **full expansion**, the **DNA** would reach its organic **12-strand activation**, the identity would expand to hold **12-dimensionsof consciousness** within embodiment, and the organism would have **full conscious control** of ***manifesting and de-manifesting*** **its 15-Dimensional anatomy in time. The body forms of the original human imprint are IMMORTAL** - deterioration and death were **not a part of the original *Imprint for Health*** within the human Bio-Spiritual makeup. Through understanding how the natural process of growth and expansion in time were INTENDED to work, we can also understand the core reason for the manifestation of the SYSTEMS MALFUNCTIONS - the conditions of biological and mental deterioration that lead to the condition of **BIOLOGICAL DEATH** - a condition that is **INORGANIC TO THE ORIGINAL GENETIC IMPRINT OF THE HUMAN FORM!.**

The First Natural Expansion Cycle

In the original human genetic blueprint, the frequencies and dimensions of consciousness corresponding to the wave spectra of Dimensions 1, 2, and 3, were intended to accrete or draw into the morphogenetic field between fetal integration and the age of 11-12. At the age of 11-12 the wave spectra of which the body was composed would take a **leap in frequency**, beginning the process of **expanding the morphogenetic field** to hold the higher frequency wave spectra of **Dimensions 4, 5 and 6.**

The *expansion of the morphogenetic imprint* is reflected in the *DNA*, and *chemical and hormonal balances* within the body, which govern the function of the *metabolic rate* and the operation of molecular function. The **first cycle** of *morphogenetic expansion* into the wave spectra of **Dimensions 4, 5 and 6,** represents the process of **SOUL INTEGRATION** for the embodied identity, and **begins the natural process of de-densification of matter** - *by lowering of morphogenetic vibration, raising of oscillation rate and frequency, and shortening of the wave-length of the scalar waves that compose the matter form and consciousness.* **These changes in *intrinsic wave characteristics* have their reflection within the behavior of *atomic structure***- as the morphogenetic field wave spectra **raises in frequency**, the ***electron spin* around the atomic nucleus *slows***, thereby increasing the electrical nature, and reducing the magnetic orientation of atomic function, ***transmuting the perceivable matter substance* of the cells to a *less dense* state of being. Completion of the *Soul Integration process* marks the transmutation of *Carbon-based Gross-matter density* into the *Carbon-Silica based Semi-etheric matter density*, and the expansion of embodied awareness from 3 to 6 Dimensions of consciousness.**

Completing Expansion

This process of *progressive morphogenetic field and consciousness expansion* and *resulting de-densification of biological matter* continued throughout the remaining *expansion cycles*. Age **22 to age 33** marked the accretion of the **7th, 8th and 9th -Dimensional** wave spectra, the process of ***Over-Soul Integration,*** expansion into a **9-Dimensional consciousness** and transmutation to a ***Silica-based Etheric matter density biology***. Age **33 to 44** marked the accretion of the **10th, 11th and 12th Dimensional** wave spectra, the process of ***MAHARIC INTEGRATION***, expansion into a **12-Dimensional consciousness** and transmutation **out of biology** into the **Crystalline Liquid Light wave form of Pre-matter substance.** At this point the identity is considered a **full AVATAR** and has complete control over ***manifesting and de-manifesting*** the **Holographic Projection** of its desired body imprint in time.

Growth Rates and Morphogenetic Expansion

ORIGINAL HUMAN GENETIC IMPRINT

PERSONALITY INTEGRATION (Telluric Integration) – **BIRTH - AGE 12**
Expands the Morphogenetic Field through accreting the frequencies of Dimensions 1-3 and activating DNA Strand Templates 1-3.

SOUL INTEGRATION (Doradic Integration) – **AGE 12 – 22**
Expands the Morphogenetic Field through accreting the frequencies of Dimensions 4-6 and activating DNA Strand Templates 4-6.

OVERSOUL INTEGRATION (Teuric Integration) – **AGE 22 – 33**
Expands the Morphogenetic Field through accreting the frequencies of Dimensions 7-9 and activating DNA Strand Templates 7-9.

CHRISTOS AVATAR INTEGRATION (Maharic Integration) –**AGE 33 – 44**
Expands the Morphogenetic Field through accreting the frequencies of Dimensions 10-12 and activating DNA Strand Templates 10-12. Allows full Cellular Transmutation and Dimensional Ascension to the 12th Dimensional Pre-matter Liquid Light HYDROPLASMIC Substance Liquid Silica) and conscious mastery over 12 Dimensions within the 15-Dimensional Time Matrix. A "Christed" Immortal Being possessing non-polarized Unity or Christ Consciousness.

CONTEMPORARY HUMAN GENETIC IMPRINT

PERSONALITY INTEGRATION (Telluric Integration) – **BIRTH – DEATH**

SOUL INTEGRATION (Doradic Integration) – KATHARA BLOCKAGE

OVERSOUL INTEGRATION (Teuric Integration) – KATHARA BLOCKAGE

CHRISTOS AVATAR INTEGRATION (Maharic Integration) – KATHARA BLOCKAGE. Deterioration and Death of the physical body occur rather than progressive frequency accretion for Cellular Transmutation and Dimensional Ascension. Distortions in the personal Kathara Grid and Scalar Shields manifest in the DNA Template and block natural inflow and Morphogenetic Field accretion of frequency from the higher dimensional stations of identity. Conscious awareness remains polarized in Duality Consciousness and physical body is rendered finite and vulnerable to dis-ease.

THE 4 NATURAL CYCLES OF MORPHOGENETIC FIELD EXPANSION

THE *4 CYCLES OF MORPHOGENETIC FIELD EXPANSION* REPRESENT THE *ORIGINAL ORGANIC PROCESS* BY WHICH THE HUMAN ORGANISM WAS *INTENDED* TO EVOLVE THROUGH TIME.

The Inorganic Condition of Human Illness and Death

The processes of biological and mental deterioration and resulting DEATH of the biological form, which we presently view as FACTS OF LIFE regarding the process of human passage through linear time, ARE NOT ORGANIC CONDITIONS TO THE HUMAN ORGANISM. Other life forms, such as the **animal kingdoms**, that manifest through morphogenetic fields having *less than 12 Kathara Centers active* within their Kathara Grid, cannot undergo the full process of bodily transmutation into Pre-matter substance, and cannot fully expand their embodied awareness into 12th-Dimensional consciousness. For the **animal kingdom**, the process of evolution is also Frequency Accretion, but it is achieved through expanding one's body form to its full capacity, then entering the consciousness into a morphogenetic imprint with a bit higher capacity, until eventually the consciousness can accrete enough frequency to take it into the next level of matter de-densification and consciousness expansion. **Death is natural to the organic animal kingdom.**

Humans were intended to undergo the *full spectrum of morphogenetic expansion and cellular transmutation* WITHIN ONE ETERNAL BODY IMAGE, that was built upon a program of *full activation* of the *12 Kathara Centers* of the Kathara Grid. Death is NOT natural for humans.

Kathara Grid Blockage and Molecular Compaction

The process of *biological deterioration* and progressive movement toward biological DEATH is the *direct result* of unnatural BLOCKAGES WITHIN THE KATHARA GRID HOLOGRAPHIC TEMPLATE. Blockages within the Kathara Grid program presently block the process of Frequency Accretion **at the beginning of the First Expansion Cycle-** as accretion of the 4th, 5th and 6th Dimensional frequencies representing the *Soul Integration Process* is blocked within the Kathara Grid and thus within the biological DNA, the incoming frequencies of the Soul Level consciousness **push on and CRUSH the morphogenetic field**, rather than *expand the morphogenetic field into a higher level of frequency holding*. When the incoming scalar wave frequencies of Soul Integration begin to crush the morphogenetic field, a condition called **MOLECULAR COMPACTION** is created.

MOLECULAR COMPACTION -

***over exposure to scalar wave spectra* and its resulting *fragmentation of the morphogenetic field and Kathara Grid* - IS THE *ONLY TRUE CAUSE OF DIS-EASE*, AND THE *CORE CAUSAL ELEMENT* OF THE *UNNATURAL DEATH EXPERIENCE*.**

The *Maharic Shield* and Human Healing

Within the imprint of the **MAHARIC SHIELD** of human morphogenetic structure, is the dormant imprint of the *10th, 11th and 12th Dimensional electro-tonal programs* that represent the **ORGANIC PROGRAM OF THE KATHARA GRID. Through activation of the Maharic Shield** - the scalar standing-wave template that corresponds to the Pre-matter Liquid Light fields of Dimensions 10, 11 and 12 - **blockages within the Kathara Grid Holographic Template, that result in the genetic mutation that causes Molecular Compaction, can be progressively realigned with the original IMMORTAL IMPRINT FOR HEALTH.** Though it takes time and consistent application of **Kathara Healing Technique** to fully regenerate the **Imprint for Health and Immortality** within the 15-Dimensional Levels of human anatomy, working to heal distortions within the Kathara Grid through **MAHARIC INFUSION** (running the frequencies and wave spectra of the *Maharic Shield* through the Kathara Grid, Bio-energetic System and Body), **can create progressively more observable affects in creating and maintaining health, and slowing the bodily deterioration process, within the normal life span of an individual.**

Potentials of Kathara Healing

The true beauty and significance of *Kathara Healing* is that it can not only do wonders for creating and maintaining *higher standards of health* within the average human life span, but within the applications of KATHARA MECHANICS lies the *promise and potential* of human biological IMMORTALITY and the fulfillment of SPIRITUAL ACTUALIZATION and evolution to MASTERY- through progressive embodiment of and conscious mastery over our 15-Dimensional Anatomy and the creative process of Holographic Projection within the dimensionalized fields of space, time and matter.

KATHARA HEALING HOLDS THE KEY TO HUMANITY RECLAIMING ITS ANCIENT HERITAGE OF THE ETERNAL SELF AND IMMORTAL AT-ONE-MENT WITH SOURCE.

LEVELS OF HUMAN ANATOMY- THE EMBODIED KATHARA

The Human Body Kathara Grid

The Kathara Grid of the human body is the *Core Holographic Template* upon which the morphogenetic scalar-wave template, and all other levels of identity and form are built. It is the **"Control Center"** for manifestation of the human being.

LEVEL-1 KATHARA 12-TREE GRID

THE KATHARA GRID LEVEL-1: 12-TREE

Level-1 Kathara Grid 12-Tree: The first level of the Kathara Grid **sets the *pattern for dimensionalization of consciousness* through which identity can enter the Time Matrix for the Holographic Experience of manifestation. The Kathara Grid 12-Tree is the first wave spectra composite through which consciousness anchors itself into dimensionality in order to experience manifestation of form.** All things within dimensional structure have the Kathara 12-Tree at the core, but not all manifest forms have the full pattern of the 12-Tree *activated* within their morphogenetic pattern. The 12-Tree is composed of **12 Kathara Centers** or *Kathara Spheres*, and **15 Kathara Lines.**

KATHARA CENTERS

The **Kathara Centers** are *crystallizations of Partiki units* that hold *composite electro-tonal energy signatures for each dimensional band.* The electro-tonal programs of the Kathara Centers hold the **foundation template** upon which the biological **DNA** will manifest.

KATHARA LINES

The **Kathara Lines** are sequences of *Partiki Phasing rhythms* ("flashing on and off"/fission-fusion sequences) that *transfer the dimensionalized electro-tonal programs of the Kathara Centers between each center* , to form the **core level of the scalar standing-wave template** upon which subsequent levels of the Kathara Grid, Bio-energetic System and body will build.

KATHARA HEALING AND THE LEVEL-1 12-TREE GRID

The *Kathara Centers* and *Kathara Lines* are used in *Kathara Healing* to realign and awaken the original 12-Dimensional imprint within the human morphogenetic field, in order to *reinstate the original Imprint for Health and Bio-Spiritual Mastery* within the operational evolutionary blueprint for the Body-Mind-Spirit System of the Human form.

Level-1 Kathara 12-Tree Grid

of the INTERNAL TEMPLAR

KATHARA CENTERS

#12 – *The Capstone*
In 10th Chakra
6" above the head

# 11 – *Crown Jewel*
In Pineal Gland
at center of brain

# 9 & # 10 –*The Shar*
In brain
behind ears

# 8 – *Spark of Orion*
In Thyroid Gland
at 8th Chakra

# 6 & # 7-*The Wings*
In shoulder indents
through to back

# 5 –*Seat of Amenti*
At Navel in
Central Body Current

# 3 & # 4 -*The Dal*
male: Ureters
female: Ovaries

# 2 – *Naum-Yun*
male: Prostate Gland
female: Vagina

# 1 – *Earth Core*
at center of Earth
in 13th Chakra


12
11
9
10
8
6
7
5
3
4
2
1

Placement of *Kathara Level-1 12-Tree Grid Kathara Centers* and *Kathara Lines* within the human body.

Central Vertical Kathara Line controls all other Kathara Lines. Kathara Centers on *Central Vertical Kathara Line* control all other Kathara Centers.


12
11
9
10
8
3-6-9 Vertical Kathara Line
corresponds to Right side of body
4-7-10 Vertical Kathara Line
corresponds to Left side of body
Kathara Lines
6
7
Kathara Centers
5
3
4
2
1

Electro-tonal Programs within the *3 Vertical Kathara Lines* control the programs in all other Kathara Lines.

LEVEL-2 KATHARA CRYSTAL SEALS GRID

Level-2: Crystal Seals and 15 Primary Chakras

The Crystal Seals are groups of 3-Dimensional Partiki scalar wave composites that regulate the rate of Partiki Phasing to create the base structures upon which dimensionalization is formed. The *flow of frequency* between dimensional bands and Harmonic Universes, the fixed expansion and contraction/ fission and fusion rates of Partiki, the *Vibration-Oscillation Rates* of Partiki and the *Angular Rotation of Particle Spin* are all regulated by the Crystal Seals.

Star Crystal Seals are positioned between the Chakra Centers along the **Central Body Current**, and **Seed Crystal Seals** are positioned between them, and serve as the *point of composite frequency* out of which the **15 Primary Chakra Center Vortices** emerge.

HOVA BODIES AND SHIELDS

5 Dimensionalized Hova Body Shields and 5 Auric Capsules

Hova Bodies are **3-Dimensional, tri-tonal scalar standing-wave grids** composed of numerous sets of **Crystal Seals** that form the electro-tonal program upon which the **Kathara Grid Level-3: Doradic Points** emerge. **The Hova Body Grids are called Crystal Shields.** The **5 Dimensionalized Hova Bodies** are structured as **5 Concentric Spheres** of energy that *surround and permeate the human body* and serve to *hold the embodying consciousness into dimensionalized levels* through which the **Holographic Projection** of *experienced manifestation* can occur. The Hova Bodies form **"tissue capsules"** of *subtle energy* around **each 3-dimensional Harmonic** level of the **Bio-energetic Field**, within which the **15 Dimensional levels** of the **Auric Field** are stationed.

In Kathara Healing, restoration of the original **4th-Harmonic Maharic Shield** *Imprint for Health* is used to *realign and clear blockages* from the lower Hova Bodies and corresponding **Kathara Centers** and **Kathara Lines**, to awaken the **Imprint for Health and Spiritual Actualization** within the Body-Mind-Spirit System.

HOVA BODIES, SHIELDS & SIGNETS

5 Ariea Hova Bodies, Kathara Grid and Harmonics of Manifestation

Hova Bodies are *tri-tonal scalar grids* that form *spherical energy "tissue capsules"* around each 3-dimensonal level of the multi-dimensional identity. Within 15-Dimensional Human Anatomy, there are **5 Dimensionalized Hova Bodies** called **Ariea Hova Bodies.** The Ariea Hova Bodies form out of the electro-tonal programs held within the **Kathara Centers** of the *Level-1 Kathara 12-Tree Grid.* The *12th Kathara Center* of the Kathara 12-Tree Grid connects to the *12th Kathara Center* of the *Universal Kathara Grid*, just as the *1st Kathara Center* in the personal Kathara connects to the *1st Kathara Center* in the *Planetary Kathara Grid. The 12th and 1st Kathara Centers,the personal Kathara Grid and morphogenetic field connect to the planetary and universal morphogenetic fields.* **When working with the Hova Bodies we first focus upon the lower four , as these must be functioning properly before the 5th Hova Body and its connection to the Universal Kathara Grid can be activated within the Bio-energetic Field.** Four of the 5 Ariea Hova Bodies are directly connected to the Crystal Seals within the human body **Central Body Current** on a **HORIZONTAL PLANE.** These first **4 Hova Bodies** correspond to each of the **12 Kathara Centers** of the personal Kathara 12-Tree Grid. **The Hova Bodies represent Harmonics of Manifestation.**

Hova Bodies, SIGNETS and SHIELDS

Each Hova Body **emanates outward** from a set of **3 Kathara Centers** and their corresponding **Crystal Seals. The *core template of the Hova Body* is a *Triad of Crystalline Spheres* that connect directly to the *3 Kathara Centers* to which they correspond.** This Triad of Crystal Spheres is called a **SIGNET. The Signets are the smaller, *fixed, consolidated* :frequency points; out of which the *Seed Crystal Seals* that form the *Chakras* manifest.** The Signets and the smaller Crystal Seal formations that manifest through them, create a **disc** of spinning, **horizontal wave spectra** that direct the function of *Hova Body merger*, these scalar discs are the scalar templates upon which the Hova Bodies manifest, and are called **SHIELDS.**

The *Shields and the Signets* that direct them are considered to be the *core of the Level-2 Crystal Seals Kathara Grid.* Each of the 4 Hova Bodies of the first 12 Dimensions form upon a set of **3 Signets.** Each **Signet *transmits a flash-line*** (Partiki Phasing Sequence) **on a different axis**, one **vertical**, one **horizontal** and one **diagonal**, forming a **3-plane projection of flash-lines** that form the base of the **3-dimensional Holographic projection.**

Kathara Centers and Activating the Signets and Shields

In each set of *3 Signets* at least one corresponds to the *Central Vertical Kathara Line*, the control center of the Level-1 Kathara Grid 12-Tree. The Signets and Shields can therefore be used to direct the function of the Kathara Grid 12-Tree and all built upon it, and the Kathara Centers can be used to trigger activation of the Signets and Shields within the Hova Bodies. When a **Signet is activated** its corresponding **disc or *Shield* begins to spin**. When a certain spin rate of the Shield is reached, it triggers the activation of the next set of Signets in the next Harmonic setting the next Shield to spin. **When *2 Shields activate* and reach a reciprocal spin rate the *tissue capsule* separating the 2 corresponding Hova Bodies releases and the *2 Hova Bodies merge*, which is the process by which *Higher Identity Integration* occurs. It is also the process by which the *Merkaba Vehicle* is activated within the Bio-energetic field.** When all **four Shields** activate and spin, the body matter is able to **transmute** out of matter density and into pure wave form, which represents Maharic/ Avatar Integration for the identity.

THE 5 HOVA BODY SHIELDS

The Hova Bodies and the Shields

Each Hova Body contains at its core a Shield through which the Hova Body functions are governed. The **Nada Hova Body** of dimension 1-2-3 forms on the **TELLURIC SHIELD,** its control center being the 2nd Kathara Center that is composed of 2nd Dimensional Frequencies. The **Alphi Hova Body** of dimensions 4-5-6 forms on the **DORADIC SHIELD**, its control center being the DORA or Archetype of the 5th Dimensional Frequencies. The **Betcha Hova Body** of dimensions 7-8-9 forms on the **TEURIC SHIELD**, its control center being the TEURA or Monad of the 8th Dimensional Frequencies. The **Mahara Hova Body** forms on the **MAHARIC SHIELD**, its control center being the *Mahunta* or Avatar Core of the 11th Dimensional Frequencies. The 5th Hova Body, the **Raja Hova Body**, forms on a set of Signets that correspond to **stellar points** within the **Universal Kathara Grid.** Its Shield, the **RISHIC SHIELD**, rotates on a **vertical plane** and it comes into activation within the personal morphogenetic field only after the four lower Shields have transmuted the body into Pre-matter Liquid Light of the MAHARIC SHIELD. **In terms of healing and advancing evolution of the earthly identity, the first four Shields are of greatest significance.**

Hova Bodies, Shields, Signets and Healing

In all healing application knowledge of the Shields is of great value, for any manifest condition of disorder will have its first manifestations within the Kathara Grid and the Shields that form upon it. The process of healing, therefore, is the process of *restoring the Shields to their proper order* so they may activate to build the Merkaba Vehicle through progressive Higher Identity Integration. **In Kathara Healing we begin with the MAHARIC SHIELD**, the Shield that contains the *pure form of electro-tonal programs upon which the consciousness first entered matter density* through the Pre-matter Liquid Light Fields of the 4th Harmonic - Dimensions 10-11-12. **Through activating and progressively drawing in the highest 11th and 12th-Dimensional frequencies of the Maharic Shield, distortions in all lower Shields can be more rapidly realigned with their original pattern.** When we work with the **Kathara Centers** of the Level-1 12-Tree Grid we simultaneous create change within the **SIGNETS** that direct the function of the **SHIELDS**, and so we are able to more rapidly facilitate appropriate realignment of the Shields and Hova Bodies. **THE CORE OF HEALING IS RESTORING THE HOVA BODIES AND THE SHIELDS UPON WHICH THEY MANIFEST TO THEIR ORIGINAL INTEGRAITY OF ORDER.**

Shields, Signets and Diodic Points

Through the interaction and interplay of multi-harmonic frequency between the **Shields, Signets** and their **Crystal Seals, Kathara Grid Level-3- DIODIC POINTS** come into manifestation, to fill out the 3-plane, 3-dimensional "armature" of scalar waves and flash-lines, upon which more Partiki units will cluster and crystallize to build up the particle base for form manifestation. The **Diodic Points** within the body and morphogenetic field connect directly to the Shields of the Hova Bodies in areas where the *flash-lines and scalar points* within the Crystal Seals of the Shields *align with and pass through each other.* **Flash-Lines from one Hova Body Shield crossing through those in other Hova Body Shields form *COORDINATE POINTS*, or "Gateways" of energy-consciousness *transference* through which frequency and awareness from one Hova Body and identity level can cross through into other Hova Bodies and identity levels.** The *Coordinate Points*, or *regularly scheduled points of flash-line intersection*, form **tiny vortices of energy** , which keep energy and consciousness flowing throughout the multiple dimensional levels of identity and anatomy. **The vortices of energy created by the Coordinate Points of flash-line sequences are called *DIODIC POINTS* and they have a counter reflection within *anti-particle manifestation* called *MIODIC POINTS.*** Diodic and Miodic Points are sets of **White and Black Holes** that circulate energy throughout the anatomy.

LEVEL-3 KATHARA GRID DIODIC POINTS

Diodic and Miodic Points

Diodic/ Miodic Points represent *concentrated areas of energy* that emerge at points where *dimensionalized levels of scalar grids cross over and through each other*, creating minute **vortices** of wave spectra that serve as **frequency modulation zones** (*scalar flash-cycle transition points*) between Dimensional Frequency Bands. Diodic Point vortices are **White Hole** vortices that *transmit energy* into the Particle Universe from their counterpart **Miodic Point** vortices within the Anti-particle Universe. Through the structure of Dimensionalization, each Harmonic Universe, and the structures contained there within, have within their morphogenetic fields *sets of Diodic and Miodic Points* - **sets of White and Black Holes** - that regulate the flux of consciousness-energy between systems.

Within the biological form and morphogenetic field, Diodic Points are located in **physical body regions** where Inter-dimensional and Inter-Harmonic **Horizontal and Vertical Kathara Lines intersect** to form small **vortices** of inter-dimensional or inter-harmonic wave spectra that serve **as Gateways of Consciousness** between Dimensional Time Continua of Harmonic Time cycles. They connect physical bodies to their **anti-particle counterparts** and intersect with the Vertical and Horizontal relationships of wave spectra within the **DNA/ RNA** and bio-energetic field, through sets of White and Black Holes at the center of the biological Harmonic scalar grids.

Diodic Points and 3-Dimensionality

Diodic Points control the **Diagonal Kathara Lines**, the **sequences of Partiki Phasing** or ***"flash-lines"*** that run on a **diagonal** between the Kathara Centers. Whereas the **Kathara Level-1 Kathara Lines** direct the **Vertical flash-line sequences** and the **Level-2 Crystal Seals** control the primary **Horizontal flash-lines** and their relationships to the Vertical flash-lines, the **Diodic Points** further regulate the relationships of flash-line sequences through the Kathara Grid by serving as **"turnstiles of energy"**. The Diodic Points intersect with the crossover points of the Vertical and Horizontal flash-lines , *adding a further level of modulation* to the frequencies passing through, allowing a **3-dimensional Harmonic Projection of flash-lines** (flash-lines projecting on 3 differ angular planes)to build within the morphogenetic field. **The Diodic Points add the third plane of projection to the Kathara Grid, beginning the formation of what will appear as a 3-dimensional "armature" of flash-points upon which particles will accrete to "fill out" the Holographic illusion of 3-dimensionality.**

Diodic Points and Healing

In Kathara Healing Diodic Points are used to open the **Diagonal Kathara Lines** for reprogramming. When Diodic Points become blocked, due to blockages within the Kathara Grid (which appear as "gaps" or missing sequences of flashes along the flash-lines of Partiki Phasing), energy builds up in the *Level-3 Kathara Grid*, forming *distortions* in the natural pattern that will manifest in the body and bio-field systems as *disease or disharmonic condition*. In later applications of Kathara Healing we will learn to identify points of Diodic and Miodic build-up in the body, and use *primary flash-line sequences applied through touch points* to realign the natural flash-point sequences and clear the Diodic Blockages.

Shields, Signets and the Kathara Grid

Hova Bodies are spherical scalar wave grids that form tissue capsules between each 3-Dimensional Harmonic of Manifestation.
Signets are the core points of consolidated frequency that hold the programs for the Scalar grid SHIELDS upon which the Hova Bodies manifest.


Chakra 10
6"
C
Chakra 4
B
Chakra 1
A
Chakra 12
12"
D

The Signets and the Shields are the core of Kathara Level-2 Crystal Seals Grid

When activated, each SHIELD forms a rotating disc of scalar waves that emanate out from the body on a horizontal plane.


12
11
9
10
8
6
7
Kathara Level-1 12-Tree Grid
5
3
4
2
1
Shields
12
D
11
10
9
C
8
7
6
B
5
4
Shields
A
3
2
1
Signets

The First 4 SHIELDS each with 3 SIGNETS and correspondence to the Kathara Centers of the Level-1 12-Tree Kathara Grid.

HORIZONTAL SHIELDS

A. TELLURIC SHIELD
Nada Hova Body
B. DORADIC SHIELD
Alphi Hova Body
C. TEURIC SHIELD
Betcha Hova Body
D. MAHARIC SHIELD
Mahara Hova Body
E. RISHIC SHIELD
Raja Hova Body
(vertical- not shown)

Level-2 Kathara Crystal Seals Grid and Chakras

Chakras (C & MC)

SIGNET
Star Crystal Seals (S)

15 Chakras (C & MC)
7 Primary Chakras (C)
- C1- Base
- C2- Sacral
- C3-Solar Plexus
- C4- Heart
- C5- Throat
- C6- 3rd Eye- Pituitary
- C7- Crown-Pineal

8 Morphogenetic Chakras (MC)
- MC8-Thymus
- MC9-Thalamus
- MC10- Galactic 1
- MC11-Galactic 2
- MC12- Earth Star
- MC13-Earth Core
- MC14-Universal 1
- MC15-Universal 2


Deep Space S12.
MC14
36" above head
18" above head MC11
6" above head MC10
Deep Space S11
MC9.
C7.
C6.
S7.
C5
MC8
C4.
S6.
S5.
S4.
Central Body Current
Hara Line & Central
Vertical Kathara Line
C3
S9.
S3.
C2
S2.
S1. S15
C1
MC12
6" below feet
S8
MC13
Earth
Earth Core S10
MC15
Deep Space S13. S14.

The 5 Hova Bodies progressively merge with release of the embodied Signet Star Crystal Seals, forming the various phases of the personal Merkaba Vehicle within the bio-energetic field.

Release of the SIGNET Star Crystal Seals within the embodied Internal Templar Complex activates the 12-Strand DNA Template for Cellular Transmutation and Dimensional Ascension through the Signet Seal Star Gates of the Universal Templar Complex.

Signet Seals

15 Star Crystal Seals

Star Crystal Seals keep human identity & *Auric Levels* dimensionally separate. Control Dimensional *Merkaba Field Axis* & *Angular Rotation of Particle Spin.*

***15 Star Crystal Seals* (S):**
- S1. Red Star
- S2. Orange Star
- S3. Yellow Star
- S4. Green Star
- S5. Blue Star
- S6. Indigo Star (Blue-Violet)
- S7. Violet Star
- S8. Gold Star
- S9. Silver Star
- S10. Blue-Black Star
- S11. Silver-Black Star
- S12 White Star
- S13. Turquoise Star
- S14. Pale Yellow Star
- S15. Magenta-Pink Star

Hova Bodies and Corresponding Identity Stations

("Hova" means *Tri-tonal Scalar Grid)*

1. Nada Hova – HU-1 Incarnate Identity -*Taurenic Body* (Subconscious, Instinctual & Reasoning Minds)
2. Alphi Hova – HU-2 Soul Matrix – *Doradic Body* (Astral, Archetype & Angelic Minds)
3. Betcha Hova –HU-3 OverSoul Matrix – *Metatronic Body* (Ketheric, Monadic & Kertatric Minds)
4. Mahara Hova – HU-4 Avatar ID – *Hydronic Body* (Christiac, Buddhaic & Nirvanic Minds)
5. Raja Hova – HU-5 Rishi Collective – *Hedronic Body* (Universal Conscious Mind)

5 Hova Bodies


Nada Hova
Alphi Hova
Betcha Hova
Mahara Hova
Raja Hova

AXIOM LINES, AURIC LEVELS AND CHAKRAS

Diodic Points, Signets, Seed Seals and AXIOM LINES

Each **Signet** within a Hova Body Shield holds the electro-tonal program for one *Seed Crystal Seal* and one *dimensionalized flash-line sequence*. Each Seed Seal program corresponds to one *dimensionalized flash-line program* from one *Level-1 Kathara Center*. Each **Seed Crystal Seal** holds intact the electro-tonal program for one ***dimensionalized flash-line projection angle***, or **Single Axis Dimensional flash-line sequence.** The Single Axis Dimensional flash-line sequences controlled by each Seed Crystal Seal are called **AXIOM LINES.**

There are **12 Primary Axiom Lines** that correspond to the 12 Kathara Centers in the *Personal and Planetary Kathara Grids*. There are 12 additional **Stellar Axiom Lines** that correspond to the 12 Kathara Centers in the Universal Kathara Grid. **The Axiom Lines represent single-axis flash-line sequences -** (fixed points of conscious electrified sound- *electro-tonal units*- that form strands of scalar standing waves) **that intermesh to refine the scalar-grid webbing upon which Kathara Grid Level-3 Diodic Points will emerge.**

Axiom A-B Tonal Lines, Diodic-Miodic Vortices, Chakras-DNA-Portals-Ley Lines & Healing

Each of the 12 Primary Axiom Lines has a **reverse reflection** within the dimensions of the **anti-particle universe.** The 12 Primary Axiom Lines governing the **Diodic "White Hole" Vortices of the particle universe** are called **Axi-A-Tonal Lines** (or "Axiatonal" Lines). The corresponding reflections of the Axi-A-Tonal Lines in the **anti-particle universe,** which govern the **Miodic "Black Hole" Vortex** reflections of the Diodic Points, are called **Axi-B-Tonal Lines.** In Kathara Healing the integrity of the Axi-A-Tonal Lines is restored through realigning the electro-tonal programs within the corresponding **Kathara Centers.** The **12 Primary Axi-A-Tonal Lines** set the morphogenetic imprint upon which the **Chakra System** and foundation **DNA** organization of the human body will manifest and upon which the **Planetary Vortex/Portal System** and primary **Planetary Ley Lines** will emerge within the planetary body. Restoring the *Imprint for Health* to the **Axi-A-Tonal Lines** and corresponding **Kathara Centers** will regenerate integrity within the **DNA** and **Chakra System** of the body and will restore the organic operations of the planetary **Vortices-Portals** and **Ley Lines** of the planetary morphogenetic grid.

Restoring the **Imprint for Health** within the **Axi-A-Tonal Lines** simultaneously restores integrity to the corresponding **Diodic Points** and to the **Axi-B-Tonal Lines** and their **Miodic Points.** When working with *Kathara Techniques* that "clear the **Miasmic Imprint**" – *the anti-particle blockages within Diodic Points* – the *Diodic Points* are realigned by clearing their *Miasmic distortions*, which then reestablishes the integrity of corresponding **Axiom A and B Tonal Lines**, sending a realigned electro-tonal program back through the **Seed Seals** and the Level-1 **Kathara Centers.** If the programs within the **Kathara Centers** are **simultaneously realigned** using infusion of the frequencies from the **Maharic Shield,** the Kathara Center programs, the Axiom Lines and the Diodic Points will be progressively restored to health. If the Kathara Centers are not simultaneously realigned, the restored Axiom Line programs will be **overridden** by the Kathara Center programs until the restored programs reach *critical mass* through *prolonged repetition*. ***Clearing the Miasmic Imprint* while simultaneously *Repatterning the Level-1 Kathara Centers and Kathara Lines* via *Maharic Infusion* is the fastest way to restore the *Imprint for Health* within the Human Body-Mind-Spirit System and within the natural operations of planetary bio-mechanics.**

Axiom Lines, Diodic Points, Hova Bodies, Shields and Auric Field Levels

The Single Axis flash-line sequences of the **12 Primary Axiom Lines** cross over and through each other to form COORDINATE POINTS between the Hova Body Shields, through which the "White Hole" ***Level-3 Diodic Point Vortices*** emerge. **The varying angles of flash-line projection within the Axiom Lines create separate dimensionalized bands of frequency** (separate sets of flash-line sequences) **within the Hova Body structure.** As there are **3 Signets** and thus **3 Seed Seals** and **3 Axiom Lines** inherent to each **Hova Body Shield**, each Hova Body becomes *dimensionally compartmentalized* into **3** separate yet interrelated sections, each section having inherent sets of Diodic Points. **Each dimensionalized aspect of the Hova Bodies becomes a *Level of the Auric Field* within the bio-energetic system.** There are **12 Inner Layers of the Auric Field**, which correspond to Dimensions **1-12** and to the 12 Primary Kathara Centers, Seed Seals and Axiom Lines of the *first 4 Hova Bodies*. There are **3 Outer Layers of the Auric Field** that correspond to Dimensions and Seed Seals **13-15**, to the *first 3* Kathara Centers and Axiom Lines of the **Universal Kathara Grid** and to the *5th Hova Body*.

Seed Seals, Axiom Lines, Consolidated Diodic Points, Chakras and Auric Levels

The points in the Kathara Grid where the Single Axis Axiom Lines cross over and through the Central Vertical Kathara Line in the Level-1 Grid and the Horizontal flash-lines of the Seed Crystal Seals form fixed, **consolidated Diodic Points –larger vortices** of energy composed of many smaller Diodic Vortices. **The larger vortex points are called CHAKRAS.** Each Chakra Vortex is formed upon the electro-tonal program of its corresponding Dimensional Frequency Band, Kathara Center, Seed Seal and Axiom Line, and **each chakra corresponds to one Auric Field Level, DNA strand imprint and level of consciousness.** As *3 Signets, Seed Seals* and *Axiom Lines* correspond to each *Hova Body Shield*, **3 Chakras regulate and correspond to each of 5 Hova Bodies**, for a total of **15 Primary Chakras. Primary Chakras 1-12** correspond to Kathara Centers 1-12 in the **Personal and Planetary Kathara Grids** and **Primary Chakras 13-15** correspond to the *first 3 Kathara Centers and Axiom Lines* of the **Universal Kathara Grid.** Chakras 13-15 are considered **Universal Trans-stellar Chakras.**

The *Chakras* regulate the *transduction of flash-line sequences* from the *Dimensionalized Unified Field* and *Diodic Vortices* of the Axiom Lines and Auric Field Levels into the *Hova Body tissue capsules* and *rivulet channels* that connect to the physical, electro-magnetic, chemical and hormonal aspects of the visibly manifest form. Chakras regulate the flow of consciousness-energy between the dimensionalized Auric Field levels of the Hova Bodies, keeping the various multi-dimensional stations of consciousness separate, in order to allow for experiential perception of holographic manifestation. Each **Chakra circulates** its Single Axis flash-line sequence along the **angle of projection** carried within its corresponding **Axiom Line,** and this *angle of flash-line projection* determines the **Angular Rotation of Particle Spin (ARPS)** – or the *axis upon which particles rotate*- within each dimensionalized portion of the anatomy. There is a **90-degree shift** in the *flash-line angle of projection* from one Chakra and dimensional band to the next, which creates a 90-degree shift in the **Angular Rotation of Particle Spin** between each dimensionalized portion of the anatomy. Between each 3-dimensional Hova Body there is also a **45-degree reverse shift** in flash-line projection angle, which creates a **45-degree** rather than a 90-degree **forward shift** of flash-line projection angle between each Hova Body and between each **set of 3 Chakras** (Chakras 1-2-3 * 4-5-6 * 7-8-9 * 10-11-12 * 13-14-15). The precise angles of flash-line projection and ARPS between Chakras, creates the perceivable 3-dimensional hologram.

Chakras

A Chakra appears within the bio-energetic field as **2 cones or spirals of multi-colored energy that are linked together at the tip** in the **Central Body Current** through the **Seed Crystal Seal** out of which the cones emerged. **Chakras 2-6** extend from the Seed Seals outward through the body and Auric Field on a **Horizontal axis** and **Chakras 8 and 9** intersect with *6 and 7* at the *Pineal Gland* on **2 rotating Diagonal axes** running through the head. **Chakras 1 and 7 and 10-14** are stacked above and below the body on a **Vertical Axis** aligned with the *Central Body Current* (CBC) and the *Central Vertical Kathara Line*. Chakras 1&7, 10&12, 11&13 and 14&15 are actually the bottom and top cones of **4 Large Vertical Chakra Spirals**, but are counted as separate chakras. **Chakra 15** is a **"roving chakra"**, which travels the course of the **12 Primary Axiom Lines** far out in Level–15 of the Auric Field. Each Chakra draws in energy from and transmits energy into the dimensional Unified Field corresponding to the *chakra number* and carries as its **dominant perceivable color the hue** characteristic to the **primary frequency band wave-length** of its **dimensional affiliation.**

Primary Color of Chakras

Chakra	Dimension	Color	Chakra	Dimension	Color
CK-1	D-1	RED	**CK-8**	D-8	GOLD
CK-2	D-2	ORANGE	**CK-9**	D-9	SILVER
CK-3	D-3	YELLOW	**CK-10**	D-10	BLUE-BLACK
CK-4	D-4	GREEN	**CK-11**	D-11	SILVER-BLACK
CK-5	D-5	BLUE	**CK-12**	D-12	WHITE
CK-6	D-6	BLUE-VIOLET (INDIGO)	**CK-13**	D-13	PALE TURQUOISE
CK-7	D-7	VIOLET	**CK-14**	D-14	PALE YELLOW
			CK-15	D-15	MAGENTA-PINK

A Chakra will also carry, in lesser saturation, the colors/frequency bands associated with all of the dimensions below its own dimensional affiliation.

Chakras and Dimensional Merkaba Fields

When the Seed Seal at the core of a Chakra is released, the **2 cones of the Chakra move through each other** to form a **Dimensional Merkaba Field-** *2 counter-rotating spirals of electro-magnetic energy that take the form of a* ***Star-tetrahedron***. When the Seed Crystal Seal releases, the corresponding scalar-wave points within the Hova Body Shield are ***released from Dimensional Phase-lock*** – they are released from *polarity* by the re-combining of their inherent *Particum-Particles* and *Partika-anti-particles*. Through re-combining Particum and Partika the scalar standing-wave points undergo **fusion**, then a reciprocal **fission** and **replication** within the Harmonic above. Through release of the Seed Seals the *Dimensionalized Auric Field Levels* of the *lower Hova Body* align along the same *Angular Rotation of Particle Spin* / angle of flash-line projection, which transmutes them into the *angle of flash-line projection* and *Partiki Phasing rate* of the Dimensionalized Auric Field Levels of the Hova Body from the *Harmonic above*. **Seed Crystal Seals are released by infusing them with the frequencies/ flash-line sequences of the corresponding dimension from the Harmonic above.** Progressive release of the Seed Seals within the Chakras creates opening and merging of the Kathara Lines in the Level-1 12-Tree Grid, and merging of the *Hova Bodies, Shields, Diodic Points, Auric and Identity Levels* and *DNA strands, through which activation of the* ***Merkaba Vehicle*** *and de-densification of matter occurs.*

Auric Level, Chakra and Hova Body Correspondences

Each 3-Dimensional Scalar Shield forms a Spherical Electromagnetic Domain called a Hova Body.

Each Hova Body manifests the structure, and governs the function, of 3 Primary Chakras.

Chakras draw energy in from, and transmit energy into, the **Unified Fields** of each Dimension. Each Chakra carries as its **Primary Color** the hue associated with the **wave-length** of the dimensional frequency band to which the Chakra corresponds.

Each Chakra corresponds to a level of the *Auric Field* and one *Axi-A-Tonal Line*. Each ***Hova Body*** corresponds to a set of 3 Chakras and contains 3 dimensionalized frequency bands that form the dimensional levels of **Auric Field.**


MC14
MC11
MC10
MC9
C7
C6
C5
MC8
C4
Central Body Current
C3
C2
C1
Nirvanic Body – MC12
Buddhaic Body – MC11
Christiac Body – MC10
Keriatric Body – MC9
Monadic Body – MC8
Ketheric Body – C7
Angelic Body – C6
Archetypal Body – C5
Astral Body – C4
Mental Body – C3
Emotional-Elemental Body – C2
Etheric Body – C1
D-12 FREQUENCY
D-11 FREQUENCY
D-10 FREQUENCY
D-9 FREQUENCY
D-8 FREQUENCY
D-7 FREQUENCY
D-6 FREQUENCY
D-5 FREQUENCY
D-4 FREQUENCY
D-3 FREQUENCY
D-2 FREQUENCY
D-1 FREQUENCY
Axi-A-Tonal Line 1
Axi-A-Tonal Line 2
Axi-A-Tonal Line 3. NADA HOVA BODY
Axi-A-Tonal Line 4
Axi-A-Tonal Line 5
Axi-A-Tonal Line 6
ALPHI HOVA BODY
Axi-A-Tonal Line 7
Axi-A-Tonal Line 8
Axi-A-Tonal Line 9
BETCHA HOVA BODY
Axi-A-Tonal Line 10
Axi-A-Tonal Line 11
Axi-A-Tonal Line 12
MAHARA HOVA BODY
12 Inner Auric Levels
3 Universal Auric Levels (correspond to D13 through D15)
MC12
MC13
Earth
Earth Core
MC15

7 Primary Chakras (C)
C1- Base
C2- Sacral
C3-Solar Plexus
C4- Heart
C5- Throat
C6- 3rd Eye- Pituitary
C7- Crown-Pineal
8 Morphogenetic Chakras (MC)
MC8-Thymus
MC9-Thalamus
MC10- Galactic 1
MC11-Galactic 2
MC12- Earth Star
MC13-Earth Core
MC14-Universal 1
MC15-Universal 2

Primary Colors (wave spectrum)
C1- Red
C2- Orange
C3-Yellow
C4- Green
C5- Blue
C6 – Indigo
C7- Violet
MC8-Gold
MC9-Silver
MC10- Blue-Black
MC11-Silver-Black
MC12- White
MC13- Pale Turquoise
MC14-Pale Yellow
MC15- Magenta-Pale Pink

PRIMARY COLOR OF CHAKRAS

Chakra	Dimension	Color	Chakra	Dimension	Color
CK-1	D-1	RED	CK-8	D-8	GOLD
CK-2	D-2	ORANGE	CK-9	D-9	SILVER
CK-3	D-3	YELLOW	CK-10	D-10	BLUE-BLACK
CK-4	D-4	GREEN	CK-11	D-11	SILVER-BLACK
CK-5	D-5	BLUE	CK-12	D-12	WHITE
CK-6	D-6	BLUE-VIOLET (INDIGO)	CK-13	D-13	PALE TURQUOISE
CK-7	D-7	VIOLET	CK-14	D-14	PALE YELLOW
			CK-15	D-15	MAGENTA-PINK

A Chakra will also carry, in lesser saturation, the colors/frequency bands associated with all of the dimensions below its own dimensional affiliation.

AXI-A-TONAL LINES, THE HARA LEVEL, 6 HARA POINTS AND COMPLEXES

Axiom Lines, Rotating Flash-line Projection and the Human Body

Each Seed Crystal Seal within the Signets of the Hova Body Shields holds the electro-tonal program for a Single Axis Axiom Line flash-line projection. **The flash-line sequences of each Axiom Line are not simply *stationary* single-line projections of flash-lines, but rather operate as *rotating* single-line projections.** Each rotating Single Axis flash-line projection is ***synchronized*** with the other rotating Single Axis flash-line projections of Axiom Lines from the other Seed Crystal Seals. Through the ***rotational synchronization*** of the Axiom flash-line sequences, the flash-lines of each Axiom Line regularly cross through each other, and through the vertical and horizontal flash-line sequences from the Level-1 and Level-2 Kathara Grid. The points of *synchronized flash-line crossover* form ***consistent points of intersection*** through which the **Level-3 Diodic Vortices** and **Chakras** manifest. Within the human body and Auric Field the **consistent points of flash-line crossover** can be charted in the form of **fixed lines of energy** that run through the body. **The charted Axiom Lines within the human body represent series of regularly scheduled flash-line intersection points, created through the synchronized rotation of the Single Axis Axiom flash-line sequences.**

Axiom A Lines – "Axi-A-Tonal" Lines in the Human Body

The consistent points of Axiom Line flash-line crossover that form fixed lines of energy within the body can be charted as **Axiom A and B Line** energy flows within the body. The Axiom A Lines correspond to the body manifestation in the particle universe, the B Lines to the body double in the anti-particle universe. **For Kathara Healing applications the A Lines – Axi-A-tonal Lines- of the particle body are used for various purposes of facilitating Kathara Center realignment and revitalization of the Body-Mind-Spirit System.** Within the body the Axi-A-Tonal Lines can be charted as **Primary Flow Lines** – conduits through which energy-consciousness, in the form of scalar-point flash-line sequences, circulates through the morphogenetic field. The fixed flash-line crossover points that form the **charted Axi-A-Tonal Lines** appear in the body as a set of **12 Vertical Flow Lines**, one running from each of 12 Auric Field Levels, which run through the body within the **Level-2 Crystal Seals Kathara Grid**. Each Axi-A-Tonal Line corresponds to one of 12 Dimensional Frequency Bands, Kathara Centers, Seed Crystal Seals, Chakras and DNA strand imprints. **The 12 Primary Axi-A-Tonal Lines appear to enter and leave the body through the head and feet, with conduits running through the arms, hands and out the finger-tips, and through the legs, feet and out the tips of the toes. Each Axi-A-Tonal Line appears as a colored cord of energy, its hue determined by the wave length characteristic to its corresponding dimensional frequency band.** In charting the positions of the 12 Primary Axi-A-Tonal Lines in the body, **numbering** and **color** are used to denote the *Dimensional correspondences* of each Axi-A-Tonal Line.

Axi-A-Tonal Lines 11 & 12 and the "Hara Line"

Axi-A-Tonal Lines 11 and 12, which correspond to the 11th and 12th Dimensions, Kathara Centers, Seed Seals and Chakras, run vertically through the center of the body along the Kathara Grid Level-1 **Central Vertical Kathara Line**, forming a ***twisted "rope"*** of Dark Silver (D-11) and White (D-12) energy that wraps around the Central Vertical Kathara Line Flash-line Sequence. The **Central Vertical Kathara Line,** which appears as a **thin Silver-gold flash-line of energy** running from the 14th Chakra (36"above the head) through the body and into the 13th Chakra at Earth's Core, is imbued with frequencies from the **12th, 11th and 8th Dimensions –** the frequencies of White, Dark Silver and Gold.

In *Level-2 Kathara Grid*, the rotating single axis flash-lines of *Axi-A-Tonal Lines 11* and *12* spiral around the thin Silver-Gold flash-line of the *Central Vertical Kathara Line,* merging into a thin, vertical tri-tonal flash-line of primarily *Gold* hue that becomes the core of the *Central Body Current.* In ancient Eastern Healing Systems this **thin Gold Vertical Line** is called the **"Hara Line"**, and is often considered the foundation of the manifest form. In truth, the **Level-1 Kathara 12-Tree Grid** and the *Signets, Crystal Seals* and *Shields* of **Kathara Level-2** are the deeper foundations upon which the Hara Line manifests.

The *Hara Level* of Kathara Level-2 Crystal Seals Grid

The mechanics of the Crystal Seals in the Level-2 Kathara Grid are complex, but can be employed with relative ease through working with the energetic dynamics of the ***outer levels* of the Level-2 Kathara Grid**, the level in which the *Hara Line* can be viewed using *9th-dimensional Higher Sensory Perception.* We refer to this level of the Level-2 Crystal Seals Grid as the **HARA LEVEL.** The Hara Level is composed of the Hara Line, and 6 of the 15 Star Crystal Seals of the Kathara Level-2 Crystal Seals Grid.

The 6 *Hara Points* (Crystal Seals) apparent from the Hara Level are as follows:

1. The 9th *Silver* Core Star Crystal Seal, called the **HARA CENTER**
2. The 6th *Indigo (or Blue-Voilet)* Star Crystal Seal, called the **SOUL STAR**
3. The 12th *White* Star Crystal Seal, called the **GALACTIC STAR**
4. The 3rd *Yellow* Star Crystal Seal, called the **SUN STAR**
5. The 8th *Gold* Star Crystal Seal, called the **EARTH STAR**
6. The 10th *Blue-Black* Star Crystal Seal, called the **EARTH CORE SEAL**

The **6 Hara Points** govern and regulate the function of **Complexes** of *energy synthesization and distribution* that control the operations of all primary body systems and bio-energetic field dynamics. In *Kathara Healing Level-2* we will explore mechanics of the Hara Level. In Level-1 Kathara Healing we will simply become familiar with Hara Level as an element of 15-dimensional human anatomy.

THE HARA AND THE KUNDALINI

The Silvery-gold energies of the **Hara Center** (9th Star Crystal Seal) are interwoven at the **base of the spine** with what is referred to as the **KUNDALINI life-force energies.** The Kundalini energies represent the **PRIMARY ENERGY CURRENTS** through which the incarnating consciousness anchors its morphogenetic field within the **Fetal Body** through the **FIRST 8 CELLS** of conception. **The Hara Center energies interweave at the base of the spine with the frequencies of the first Star Crystal Seal, the *RED Star Seal*,** in the First Cell. When the Hara Center Seal is dormant and activated only to *the 3-Dimensional Level* its Pale Silvery-gold frequencies appear to be encased within a **crimson RED sheathe** of 1st-Dimenional energy, often **making the Hara Center and Hara Line appear to be RED in color.** As the Hara Center comes into activation through progressive release of the 9th Star Crystal Seal, the Gold 8th-Dimensional and Silver 9th Dimensional frequencies of the Hara become the dominant hues, giving the Hara Center and Hara Line its natural **Silvery-gold color.** With full activation of the Hara Center and **12th-Dimensional Maharic Integration**, the tri-tone frequencies of the Hara Center and Hara Line take on a **tri-color spectrum of Pale Silver, Gold and Red-Violet** (pale Magenta), as the Kundalini primary life force currents at the base of the spine activate within the Central Vertical Current of the body. Full activation of the Kundalini merges the 7th-Dimensional **Violet,** 1st-Dimensional **Red,** 8th-Dimenional **Gold** and 9th Dimensional **Silver** frequencies with the full spectrum **White-Silver** energies of the 12th Dimensional Maharic Current.

The Hara Center, like all Star Crystal Seals, is one of the primary regulatory elements of the natural Kundalini energies. As the Kundalini energies at the base of the spine are brought out of higher dimensional dormancy, through progressive activation of the Star Crystal Seals in the Kathara Level-2 Crystal Seals grid, the Hara Center progressively reflects these changes by expanding in size and energy processing capacities and taking on the hues (wave spectra) of the higher dimensional frequencies. The **Kundalini energies** at the base of the spine are the **key to physical cellular transmutation** of the body. Kundalini energy currents **regulate the physical body's position in space-time,** keeping the physical body phase-locked into the planetary Time Cycle in which it was conceived, following the mathematical programs set by the Star Crystal Seals and the Kathara Grid. For physical transmutation to occur, the Kundalini energies of the higher dimensions must be brought into embodied activation, setting the processes of the **Internal Templar Complex** in motion.

The **DNA Template** manifests upon the programs set by the **Kathara Grid.** As the Kathara Centers and their corresponding Star Crystal Seals, Shields, Kundalini currents, Cranial-Sacral (Pineal-Tailbone) Seals, Seed Crystal Seals and Chakras activate, dormant DNA Strand Template also activate, progressively altering the **Angular Rotation of Particle Spin,** energy-processing capacities, **metabolic orientation** and **neurological processes** of the body and molecular structure. As these physical changes occur through activation of the Crystal Seals and Kundalini energies, the **Merkaba Vehicle** (interdimensional counter-rotating electro-magnetic fields in star-tetrahedral form) progressively builds within the bio-energetic field, allowing the physical body **release from phase lock** within its home space-time vector. **Activation of the Hara Center represents one of the stages of this natural transmutational process.**

THE HARA CENTER

The 9th Core Star Crystal Seal, the Hara Center (Tan Tein) and the D-9 Thalamus Complex

The **Star and Seed Crystal Seals** of the Level-2 Kathara Grid that hold consciousness into the dimensional phase-lock set by the Level-1 Kathara Centers accrete along the Central Vertical Kathara Line and the Central Body Current. **From the *Hara Level* – the *outer portions of the Level-2 Kathara Grid*** - the *12th, 9th and 6th Star Crystal Seals*, **appear as *areas of condensed light* positioned along the *vertical Hara Line*.**

The **9th Star Crystal Seal**, located about 2 " below the Navel is known as the ***Core Star Crystal Seal*** – the point of **8th and 9th dimensional frequency** of the Harmonic-3 Over-Soul Matrix (***Teuric Shield***) that **anchor the personal morphogenetic field into that of the Earth** and serve as the **center of gravity** for the adult human body. **The *Core Star Seal* appears from the Hara Level as a 2" ball of Gold (D-8) energy encased in a thin Silvery (D-9) membrane; in Eastern theory this ball of energy is called the *Tan Tein*, and is used for direction of bodily and Earth energies in advanced martial arts and healing practices.** In Kathara theory we simply refer to this energy ball as the ***Hara Center***, or the 9th **Core Star Crystal Seal.**

The ***Hara Center*** is the point at which the dimensionalizing identity enters the **Etheric Matter densities** of Harmonic Universe-3. The Hara Center represents the point into which the **Over-Soul Identity,** its **Monadic Core, the Betcha Hova Body** and **Kathara Centers 7, 8 and 9** first anchor within the body. The Hara Center holds the morphogenetic imprint for **DNA strands 7, 8 and 9,** corresponds to **Chakra Centers** and **Axi-A-Tonal Lines 7,8 and 9** and is a key point for repatterning the electro-tonal programs of the **Teuric Shield** and realigning and activating corresponding DNA strands, Chakras, Axi-A-Tonal Lines and body regions they govern.

The Hara Center is associated with the ***Thalamus Complex***, the chemical translation and regulatory system that governs the **9th-Dimensional interface** between various **brain-function areas** and the glandular and metabolic operations of the **Thymus Complex, Gonads, Lymphatic System** and corresponding body systems. Through the ***9th-Dimensional Thalamus Complex*** the electrical impulse, chemical and hormonal relationships between the ***10th-Dimensional Shara Complex*** and the ***8th-Dimensional Thymus Complex*** and its related body systems are governed.

The Hara Center and the Thalamus Complex link the functions of the **Mahara** and **Betcha Hova Bodies,** the **Maharic** and **Teuric Shields** and the **Avatar** and **Over-Soul** levels of consciousness and identity within the body and bio-energetic field.

The primary area of dominion of the *D-9 Thalamus Complex* is *Brain Function*.

THE SOUL STAR

The 6th Soul Star Seal and the D-8 Thymus Complex

Also visible along the Hara Line of Kathara Grid Level-2 is the **6th Star Crystal Seal**, located around the **Thymus** at the top of the breast bone and associated with the **5th and 6th dimensional frequencies** of the Harmonic-2 Soul Matrix (*Doradic Shield*). The **6th Star Seal**, visible as a **pale Blue-Violet-white point of diffused light** along the Hara Line, is called the ***Soul Star Seal.***

The *Soul Star Seal* is the point at which the dimensionalizing identity enters the **Semi-Etheric Matter densities** of Harmonic Universe-2. The Soul Star represents the point into which the **Soul Identity**, its **Archetype Core**, the **Alphi Hova Body** and **Kathara Centers 4, 5 and 6** first anchor within the body. The Soul Star holds the morphogenetic imprint for **DNA strands 4, 5 and 6,** corresponds to **Chakra Centers** and **Axi-A-tonal Lines 4, 5 and 6** and is a key point for repatterning the electro-tonal programs of the **Doradic Shield,** and realigning and activating corresponding DNA strands, Chakras, Axi-A-Tonal Lines and body regions they govern.

The Soul Star is associated with the **Thymus Complex**, the chemical translation and regulatory system that governs the **8th-Dimensional interface** between the **Pineal, Pituitary,** and **Thyroid Glands,** which govern the chemical and metabolic operations of the **hormones, Adrenal Glands, Endocrine System, Spleen,** and *crystalline* formation of the **Red Blood Cells** and **Hemoglobin.**

The *Thymus Complex* and its related glandular and metabolic systems, govern the *cyclic rhythms* by which the **DNA strands** will activate through the **Pineal Gland**, the rate of *growth and degeneration* of body tissue through the **Thyroid Gland** and through the **Pituitary Gland** and its inter-glandular processes, the functions of *electro-tonal impulse conversation, translation and distribution* through the **brain, Central Nervous System** and **blood** are regulated.

The *Thymus Complex* controls the **inter-glandular systems balances** between the **Pineal, Thyroid and Pituitary Glands** and regulates the *primary operations* of electrical impulse and chemical translation and transfer throughout the brain and body systems via the **Thymus Gland.** The *8th-Dimensional Thymus Complex* is governed by the functions of the *9th-Dimensional Thalamus Complex* and the *10th-Dimensional Shara Complex.*

The Soul Star and the Thymus Complex link the functions of the **Betcha** and **Alphi Hova Bodies**, the **Teuric** and **Doraidic Shields** and the **Over-Soul** and **Soul** levels of consciousness and identity within the body and bio-energetic field.

The primary area of dominion of the *D-8 Thymus Complex* is *Metabolic Function.*

THE SUN STAR

The 3rd Sun Star Seal and the Nadial Complex

Also present, but less distinctly visible along the Hara Line of Kathara Grid Level-2 is the **3rd Star Crystal Seal**, located just beneath the **Hara Center** of the *9th Star Seal* 2" below the Navel and associated with the **2nd and 3rd dimensional frequencies** of the Harmonic-1 Incarnate Matrix (***Telluric Shield***). The **3rd Star Seal**, visible as a subtle **pale Yellow-Orange-Red point of diffused light** along the Hara Line, is called the ***Sun Star Seal.*** Due to its proximity to the Silver-Gold *Hara Center* 9th Star Seal the Sun Star is often considered to be part of the Hara Center, but in deeper Hara Level scanning the distinction between these crystal seals can be evidenced. The *Sun Star Seal* is the point at which the dimensionalizing identity enters the **Gross Physical-Matter densities** of Harmonic Universe-1.The Sun Star represents the point into which the **Incarnate Identity**, its **Subconscious-Telluric Core**, the **Nada Hova Body** and **Kathara Centers 1, 2 and 3** first anchor within the body. The Sun Star holds the morphogenetic imprint for **DNA strands 1, 2 and 3,** corresponds to **Chakra Centers** and **Axi-A-tonal Lines 1, 2 and 3** and is a key point for repatterning the electro-tonal programs of the **Telluric Shield,** and realigning and activating corresponding DNA strands, Chakras, Axi-A-Tonal Lines and body regions they govern.

The Sun Star is associated with the **Nadial Complex**, the electrical impulse and chemical translation and regulatory system that governs the **4th -Dimensional interface** between the **Thymus Complex, Thalamus Complex** and the functions of the **physical body systems,** through which the electrical, chemical and metabolic operations of the **Blood, Cardio-Vascular, Pulmonary** and **Respiratory Systems** are governed. The Nadial Complex governs the operations of **Heart and Breathing rhythms**, the flow of consciousness-energy or **"Prana"** from the higher dimensional anatomy into physical embodiment and regulates many key functions within the processes of **nutrient conversion and distribution** within the Skeletal and soft tissue systems. **The *Nadial Complex* is a key center for the direction of healing energies within the Nada Hova Body, Telluric Shield and physical body systems.**

In advanced applications of healing and manifestation, the Nadial Complex is combined with the attributes of the **Shara, Thalamus** and **Thymus Complexes** and with the **Universal Raja Complex** of Harmonic-5, which links the human body to the planetary, galactic and universal Unified Fields through the *12th and 13th Chakras* and *10th Star Crystal Seal* at Earth's core via the *Planetary Bio-Feed Interface System*. The frequencies of the *3rd Sun Star Crystal Seal*, that govern the function of the *Nadial Complex* can be combined with those of the 9th Core Star Seal *Hara Center* and the *8th and 10th Star Crystal Seals* through the 12th and 13th Chakras, *PBIS, Doradic, Teuric, and Maharic Shields* and *Raja Complex* to form a potent **Teuric-Telluric Current** for **healing and manifestation**, once the *Doradic* and *Teuric Currents* have been activated within the body.

The *Sun Star* and the *Nadial Complex* link the functions of the **Alphi** and **Nada Hova Bodies**, the **Doradic** and **Telluric Shields** and the **Soul** and **Incarnate** levels of consciousness and identity within the body and bio-energetic field.

The primary areas of dominion of the D-4 *Nadial Complex* are *Cardio-Vascular, Pulmonary* and *Nutrient Absorption/Conversion Functions.*

THE GALACTIC STAR

The 12th Galactic Star Seal and the D-10 Shara Complex

The third point of condensed light visible along the Hara Line of Kathara Grid Level-2 is the **12th Star Crystal Seal**, located at the **14th Chakra** 36" above the head and associated with the **11th and 12th dimensional frequencies** of the Harmonic-4 Avatar Matrix (***Maharic Shield***). **The 12th Star Seal**, visible as a **White-Silver point of Light emanating an inverted White-Silver-Gold *cone of energy* at the 14th Chakra**, is the White Star or ***Galactic Star Seal***.

The *Galactic Star Seal* is the point at which the dimensionalizing gestalt identity enters the **Pre-Matter Liquid Light densities** of Harmonic-4, the point at which identity begins its individuation and journey of densification into the wave spectra of perceivably experiential matter. The Galactic Star represents the point into which the **Avatar Identity**, its **Buddhaic Core**, the **Mahara Hova Body** and **Kathara Centers 10, 11 and 12** first anchor within the **Bio-energetic Field** to begin setting the scalar field for the body. The Galactic Star Seal holds the morphogenetic imprint for **DNA strands 10, 11 and 12**, corresponds to **Chakra Centers** and **Axi-A-Tonal Lines 10, 11, and 12** and is a key point for repatterning the electro-tonal programs of the **Maharic Shield**, and realigning and activating corresponding DNA strands, Chakras, Axi-A-Tonal Lines and body regions they govern.

The Galactic Star is associated with the *Shara Complex*, the regulatory system that governs the **10th-Dimensional interface** between the **D-9 Thalamus Complex** and the D-13 portion of the **Rishi Shield** in Harmonic-5. Through the Shara Complex the Scalar Fields holding the gestalt identity of Harmonic-5 Rishi Consciousness Collective- the *"Universal Family of Consciousness"* – translate via electro-tonal conduction, into the more individuated Scalar Fields that house the Avatar identity gestalt Consciousness Collective- the *"Galactic Family of Consciousness"*.

The **Shara Complex *regulates the disbursement of consciousness*** in individuated form through the dimensional fields of the Time Matrix and serves to link each individuated and incarnate member of the Geomantic Entity Collective beyond the Time Matrix, to its Avatar identity and Galactic Family of Consciousness in Harmonic Universe-4, through the Universal Family of Consciousness of the Rishi identity in Harmonic Universe-5. The Shara Complex represents the primary facility through which an individual consciousness retains its indelible energetic connection to its greater **family of consciousness**, through which it is directly linked to **Source.**

The Shara Complex governs, regulates and orchestrates the transduction, translation and cyclic rhythms of **electro-tonal projection of consciousness into dimensionalization**, sets the original operational structures of **Kathara Scalar Grid** arrangement and directs the synchronistic **evolution of families of consciousness** through time. Through the operations of the Shara Complex, an identity's cycles of **incarnation and manifestation** within the 5 Harmonics of a 15-Dimensional Time Matrix are regulated, which sets the **core regulatory rhythms of Partiki Phasing**, expansion and contraction of consciousness, and vibration-oscillation ratios that **govern the formation and function** of the **Thalamus and Thymus Complexes** and all aspects of the individuated **Kathara Grid, Bio-energetic Field** and **bodily systems**. The Shara Complex controls the cycles of in-flow and out-flow of energy between the personal morphogenetic field and that of the dimensional Unified Fields, and thus affects all systems of the body and consciousness, with a primary emphasis upon the functions of the **blood, consumption-excretion and immunological facilities** of the body and of the activation of **the higher dimensional sense facilities** within the embodied consciousness.

The Shara Complex links the functions of the **Mahara** and **Raja Hova Bodies**, the **Maharic** and **Rishic Shields** and the **Avatar** and **Rishi** levels of identity within the embodied consciousness. **Primary area of dominion of the D-10 Shara Complex is the Immune System and HSP.**

THE EARTH SEALS

Earth Seals 8 and 10 and the Raja Complex

Within the Hara level of field depth in which the 3rd Sun Star Crystal Seal can be detected there are 2 other Star Crystal Seals of primary importance stationed along the Hara Line of Kathara Grid Level-2; these are referred to as the **Earth Seals.** The Earth Seals function as intrinsic aspects of the **Planetary Bio-feed Interface System** and the ***Raja Complex.*** The **8th Star Crystal Seal,** called the ***Earth Star Seal*** is located within the **12th Chakra** 6" below the feet and is associated with the **7th, 8th and 12th dimensional frequencies** of the Harmonic-3 Over-Soul Matrix (***Teuric Shield***) and the Harmonic-4 Avatar Matrix (***Maharic Shield***). The Earth Star is visible as a subtle **Gold-Orange point of diffused light** positioned along the Hara Line **6" below the feet**, as the Hara Line leaves the physical body through the 1st Base Chakra to extend downward into the Earth's core. The **10th Star Crystal Seal,** called the ***Earth Core Seal***, is located within the **13th Chakra** where the Hara Line connects into the Earth's Core and is associated with the **9th, 10th, 12th and 13th dimensional** frequencies of the Harmonic-3 Teuric Shield, Harmonic-4 Maharic Shield and Harmonic-5 Rishi Matrix (***Rishic Shield***). The Earth Core Seal is visible as a **pale Blue-Black point of diffused light** positioned in the **Earth's Core,** at the point where the personal Hara Line connects to the center of the Earth's Core at the ***1st and 12th Planetary Kathara Centers.***

The ***8th Earth Star Seal*** is the point at which the dimensionalizing identity combines the 12th-dimensional frequencies of the **Harmonic-4 Pre-matter Liquid Light density** with the 8th and 9th-dimensional frequencies of the **Etheric Matter densities of Harmonic-3** to connect the personal morphogenetic field and Kathara Grid to those of the Planetary Body. The **Earth Star Crystal Seal** can be viewed as the point where **Personal and Planetary Kathara Grids connect to Galactic Kathara Grid.** The Earth Star represents the point into which the **Mahara and Betcha Hova Bodies, Kathara Centers 8, 9 and 12 and the 12th Galactic Star Seal and Shara Complex** first anchor into the **Planetary and Galactic Kathara Grids.** The Earth Star holds the morphogenetic imprint for **all DNA strands for all manifest incarnations in *4 Harmonics of Time,*** corresponds to **Chakra Centers and Planetary Vortices** and **Personal and Planetary Axi-A-tonal Lines 8, 9, 10 and 12** and is a key point for repatterning the electro-tonal programs of the ***Personal*** **Maharic, Teuric, Doradic and Telluric Shields,** and realigning and activating corresponding DNA strands, Chakras, Planetary Vortices, Axi-A-Tonal Lines and personal or planetary body regions they govern. In the **Maharic Shield Activation process** the **Earth Star** is activated to release phase-lock on the **12th Chakra** to open the personal Kathara Grid to the PBIS.

The ***10th Earth Core Seal*** is the point at which the dimensionalizing identity combines the frequencies of the **8th Earth Star Crystal Seal** with the **13th-dimensional frequencies** of **Harmonic-5 Ante-matter density** to connect the personal and planetary morphogenetic field and Kathara Grid to those of the Universal Kathara Grid of Harmonic-5. The **Earth Core Seal** can be viewed as the point where **Personal, Planetary and Galactic Kathara Grids connect to the Universal Kathara Grid.** The Earth Core represents the point into which the **Rishi Identity, the Raja Hova Body** and **Universal Kathara Centers 1, 2 and 3** first anchor into the 3rd Earth Star and 12th Galactic Star Seals to form the Raja Complex of 5 Harmonic scalar fields through which personal, planetary, galactic and universal experiential manifestation takes place. The Earth Core Seal corresponds to **Chakra 13,** and holds the morphogenetic imprint for **all manifest incarnations of persons, planets and galaxies within the 5 Harmonics of Time in one 15-dimensional Time Matrix.** Through the combined frequencies of the **Earth Star and Earth Core Seals** the personal Kathara Grid connects to the Planetary, Galactic and Universal Kathara Grids forming the Planetary Bio-feed Interface System and the ***Raja Complex*** – or ***Universal*** **Bio-feed Interface System** – that links personal, planetary, galactic and universal consciousness in time.

THE RA CENTER

The 3rd Sun Star Seal, 8 and 10 Earth Seals and *RA Center*

When combined with PBIS, **Doradic, Teuric** and **Maharic Shields** and **Raja Complex**, the **3rd Sun Star Crystal Seal** and the **12th Core Star Crystal Seal** *Hara Center merge* to form a *Teuric-Telluric Current* that encompasses the *Seed Crystal Seal* within the **3rd Solar Plexus Chakra**, forming a ***sphere of powerful healing energies*** at the **3rd Chakra** called the **RA Center**. In **Kathara Healing Level-2** we will begin activation of the *Teuric Current* of the Harmonic-3 Betcha Hova Body, through activation of Doradic Current Phase-2 and will explore beginning applications of combining the Doradic Phase –1 and Teuric Currents with the natural *Telluric Current* of the Harmonic-1Nada Hova Body to begin bringing the **RA Center for healing and manifestation** into activation. (For more on the 4 Primary Triadic Healing Currents see Chapter 4 of this manual.)

The Hara Level of Kathara Level-2 and the 6 Primary Hara Points

Though the study of the Crystal Seals of Kathara Level-2 Crystal Seals Grid is complex in detail, one can become skilled in healing facilitation through Crystal Seals mechanics by learning the basic orientation of **the outer levels** of the **Kathara Level-2** scalar grid – ***The Hara Level***. In simple analysis, the ***elements* of the Hara Level can be viewed as follows:**

The Hara Line – the Central Body Current, that is formed by the *11th and 12th Axiom Lines* wrapping around the fixed flash-line sequence of the *Level-1 Kathara 12-Tree Central Vertical Kathara Line.*

The 6 Primary Hara Points: Star Crystal Seals **1.** # 9-Hara Center, **2.** #6-Soul Star, **3.** #12 Galactic Star, **4.** #3-Sun Star, **5.** #8-Earth Star and **6.** #10-Earth Core. Each primary Hara Point governs the function of a **complex** of interwoven scalar, bio-energetic and physical systems. Knowledge of the **6 Hara Points** and the **Thalamus, Thymus, Shara, Nadial** and **Raja Complexes** they respectively govern, allows the healing facilitator a greater understanding of the 15-dimensional anatomy. Such **Foundations of Kathara Healing** are necessary in preparation for **Kathara Healing Level-2** practices that will utilize the **Hara Level** of the **Kathara Level-2 Crystal Seals Grid** in combination with the Kathara Healing Level-1 **Maharic Recoding Process** and other elements to begin activation of the **RA Center** for advanced healing and manifestation.

Axi-A-Tonal Lines 1-10

In our exploration of the Hara Level of the Crystal Seals Grid we have learned that of the **12 Primary Axi-A-Tonal Lines,** (12 primary vertical energy-flow lines within the body and bio-energetic field, created by cross-over points of the rotating, single axis, flash-line sequences projected by each of 12 Seed Crystal Seals), the 11th and 12th Axi-A-Tonal Lines spiral around the Kathara Level-1 12-Tree Grid *Central Vertical Kathara Line* to form the Hara Line and Central Body Current. Axi-A-Tonal Lines 1-10 also run vertically through the body, from the head to the toes and through each arm to the finger tips, connecting body regions to corresponding levels of the Auric Field, Chakras, Kathara Centers, Crystal Seals and DNA. The sequence of Axi-A-tonal Line position is as follows:

Right Side of Body to Center- 3,6,9,2,8 **Center of Body**-11, 12 **Center to Left Side of Body**-. 5,1,10,7,4

Each line of Axi-A-Tonal Lines **1-10** ends in one **finger-tip** and **toe** on the corresponding side of the body, and runs vertically through the top of the head to merge with Axi-A-Tonal Lines 11 and 12 and the Hara Line at **Chakra 10**, and down through the feet to merge with the Hara Line at **Chakra 12.**

The HARA LEVEL- Outer Portion of Kathara Level-2 Crystal Seals Grid

6 Primary Hara Points

(Star Crystal Seals on Hara Level)

1. **Hara Center (Core Star)**
   (9th Silver Star Crystal Seal)
   2" below Navel
2. **Soul Star**
   (6th Indigo Star Crystal Seal)
   Top of Breast Bone at Thymus
3. **Galactic Star**
   (12th White Star Crystal Seal)
   Cone at 14th Chakra 36" above head
4. **Sun Star**
   (3rd Yellow Star Crystal Seal)
   Just below Hara Center
5. **Earth Star**
   (8th Gold Star Crystal Seal)
   In 12th Chakra 6" below feet
6. **Earth Core**
   (10th Blue-Black Star Crystal Seal)
   In 13th Chakra at Earth's Core


Chakra 14
3
Maharic Shield- Axiom Lines, DNA , Chakras 10-11-12
Chak
Teuric Shield manifests here
(at 10th Chakra-6" above head)
2
Doradic Shield- Axiom Lines DNA, Chakras 4-5-6
Doradic Shield manifests here
(at 4th Heart Chakra)
Hara Line
Axi-A-Tonal Lines 11 & 12 wrap around the Central Vertical Kathara Line of Level-1 Grid
1
Teuric Shield- Axiom Lines, DNA, Chakras 7-8-9
4
Telluric Shield- Axiom Lines, DNA, Chakras 1-2-3
Telluric Shield manifests here
(at 1st Base Chakra)
Rishic Shield (vertical) manifests here
Maharic Shield manifests here
(6" below 12th Chakra-12" below feet)
Chakra 12
5
Chakra 13
6
Rishic Shield- Axiom Lines, DNA , Chakras- Universal

The **6 Primary Hara Points** (Star Crystal Seals) of the Hara Level in the Kathara Level-2 Crystal Seals Grid govern the functions of corresponding Shields and related physical systems.

Related Bio-energetic Complexes

1. Hara Center – **D-9 THALAMUS COMPLEX**
   Focus: *Brain Function*
2. Soul Star – **D-8 THYMUS COMPLEX**
   Focus: *Metabolic Function*
3. Galactic Star – **D-10 SHARA COMPLEX**
   Focus: *Immune System and HSP*
4. Sun Star – **D-4 Nadial Complex**
   Focus: *Cardio-Vascular, Pulmonary, Nutrition*
5. Earth Seals – **Harmonic-5 Raja Complex**
   Focus: *Transmutation*

12 Primary Axi-A-Tonal Lines
of the Kathara Level-2 Crystal Seals Grid

The 12 Primary Axi-A-Tonal Lines
Frequency Color and Correspondences.

(Axi-A-tonal Line, DNA Strand, Chakra, Kathara Center & Seed Seal all correspond to one dimensional number)

D1LINE 1	Red
D2LINE 2	Orange
D3LINE 3	Yellow
D4LINE 4	Green
D5LINE 5	Blue
D6LINE 6	Indigo
D7LINE 7	Violet
D8LINE 8	Gold
D9LINE 9	Silver
D10LINE 10	Blue-Black
D11LINE 11	Silver Black
D12LINE 12	White

Axi-A-Tonal Lines are Points where the rotating, single-axis flash-line sequences from the Seed Crystal Seals cross over and through each other, to form 12 primary vertical flow-lines within the body. The Axi-A-Tonal Lines create the web-work of energy upon which the Kathara Grid Level-3 ***Diodic Points*** and the DNA manifest.


3 6 9 2 8 11 12 5 1 10 7 4
Chakra 10
6" above head
8 2 9 6 3
4 7 10 1 5
3 6 9 2 8
5 1 10 7 4
11 12
8 2 9 6 3
4 7 10 1 5
3 6 9 2 8
5 1 10 7 4
8 2 9 6 3
4 7 10 1 5
3 6 9 2 8
5 1 10 7 4
8
2 9 6 3
5
4 7 10 1
3 6 9 2 8
5 1 10 7 4
8 2 9 6 3
4 7 10 1 5
3 6 9 2 8
6" below feet
Chakra 12
5 1 10 7 4
Central Body Current
& Hara Line

Each *Axi-A-Tonal Line* corresponds to a Dimension, DNA Strand, Kathara Center, Chakra & Seed Crystal Seal, & carries the *color* associated with the primary wave-length of its corresponding Dimension.

The 7 Primary Embodied Chakras emerge where the 11th & 12th Axi-A-Tonal Lines cross through each other as they spiral around the Central Vertical Current. Secondary Chakras form in areas where other Axi-A-Tonal Lines cross through each other.

Axi-A-Tonal Lines and the Meridians

The Axi-A-Tonal Lines within the body set the primary holographic scalar field upon which the Meridian Lines – or Secondary Flow Lines- of the body manifest. **The Meridian Lines can be used to access the Axi-A-Tonal Lines and the Axi-A-Tonal Lines can be used to access the flash-line programs of the Kathara Centers and 3 Levels of the Kathara Grid, if the *correspondences* between *the Meridians, Axi-A-Tonal Lines, Kathara Centers* and *Chakras* are understood.** For centuries the **Meridian Lines** and **Chakras** have been used in subtle-energy healing systems. This knowledge can be applied and the potential results of related healing techniques amplified by employing the correspondences between the Meridian and Chakra systems and the Axi-A-Tonal Lines and 3 Levels of the Kathara Grid. Bringing the Kathara Grid into the picture allows for restructuring the **Imprint for Health** within the *causal core* while *expediting* the healing process by restructuring the various other levels of the bio-energetic anatomy.

In Level-1 Kathara Healing we focus primarily upon **Core Morphogenetic Repatterning** – resetting the electro-tonal programs of the Kathara Grid through the uncorrupted programs of the ***Maharic Shield***- to set the "*ground*" into which other healing applications can *anchor.* In later Kathara Healing Levels we will explore technique applications that affect various other levels of the bio-energetic anatomy. **In Level-1 Kathara Healing we strive to create a basic familiarity with the elements of, and the interrelationships between, the various levels of bio-energetic anatomy.** Through understanding the basic correspondences between the **3 Levels of the Kathara Grid** – the *Kathara Centers* and *Kathara Lines*, the *Hova Bodies*, Auric Levels, *Signets, Shields, Crystal Seals* and *Axiom Lines*, and the *Diodic Points* and *Chakras* – and the other aspects of energetic anatomy, such as the **Meridian Lines** and **DNA**, the healing facilitator is equipped with a knowledge base through which more precise healing facilitation can be applied. Meridian Lines and their applications to Kathara Healing will be explored in later Levels of the Kathara Healing Program.

DNA

The DNA Connection

In this Chapter we have explored the various elements of the 15-Dimensional Anatomy of the human form, from the Kathara Grid holographic scalar template, to the Hova Bodies, Shields, Axiom Lines, Chakra Centers, Auric Field Levels and the Hara Level with its related Complexes of energetic interface. Throughout all of these elements of the multi-dimensional anatomy we have seen how each element interrelates with the others through their *correspondences within the structure of the 15-Dimensional Scale.* The elements of the subtle body anatomy also systematically correspond to the structure and function of the human **DNA.** Through direct interaction with various elements of the subtle body anatomy, the operations of corresponding aspects of the human DNA can be repaired, enhanced and altered, to advance applications of healing, and to expedite the evolution of human biology and consciousness. In the *Kathara Healing Level-2 program* we will further explore the correspondences between the subtle body anatomy and the DNA, and methods by which the DNA can be repaired and activated to a more advanced level through employing the use of Kathara Healing mechanics.

The Silicate Matrix 12-strand DNA Pattern

The core human DNA imprint is built upon a **12-Dimensional** Structure, each of 12 strands building up upon one of the Primary 12 Axi-A-Tonal Lines and each strand corresponding to 1 of 12 dimensional frequency bands within the 15-dimensional scale. The original human DNA imprint is called the **Silicate Matrix,** the 12-strand scalar-wave configuration that allows for the progressive **transmutation** of Harmonic-1 carbon-based molecular-elemental structure into the Silica-based structures of higher Harmonic matter. The 12-strand DNA imprint of the human form implies that human biology was designed to embody **12 dimensions of conscious awareness**, or to fully embody the Avatar identity level - the ***"Christed" Identity*** of Harmonic-4 Pre-matter Liquid Light matter density. The human form is organically designed to undergo **full cellular transmutation** through 4 Harmonics of manifestation and their corresponding matter density levels. When the gene code is working properly, the process of cellular transmutation is directed by the embodied human consciousness. In historical terms, the process of ***conscious cellular transmutation*** has been referred to as the process of **"Ascension"**, which is ***Dimensional Expansion,*** the mechanics of which have been hidden with ancient texts dealing with **Merkaba Mechanics.** The **Merkaba Vehicle** of inter-harmonic scalar-wave configurations, which forms within the bio-energetic field, is a consequence or *simultaneous affect* of progressive activation of the Silicate Matrix within the genetic code.

The Silicate Matrix and Subtle Body Anatomy

Just as each Axi-A-Tonal Line of the subtle body anatomy has its correspondence to a Kathara Center, Crystal Seal, Axi-A-Tonal Line, Auric Field Level and Chakra, so too do the DNA strands have their specific affiliations to each *dimensionalized element* of the subtle body anatomy. Each DNA strand translates into electrical-elemental-chemical form from the governing Axi-A-Tonal Line flash-line sequence to which it corresponds. The **Hova Bodies** and **Shields** of subtle body anatomy each correspond to a *set of 3* Axi-A-Tonal Lines, Auric Field Levels and Chakras and thus also correspond to a set of **3 DNA strands,** that together create the experiential projection of separate 3-Dimensional holographic reality fields. Distortions and blockages in the Kathara Grid, Hova Bodies, Shields, Axi-A-Tonal Lines and Chakras appear as distortions and malfunction within the DNA. **The function of the DNA determines the *quantity of interdimensional frequency,* and thus the *amount of dimensionalized consciousness,* that can actively process through and embody within the physical body system.** DNA distortions manifest as distortions of biology and consciousness.

The 12 DNA strands of the Silicate Matrix are *sets of scalar-wave spectra* that correspond to each dimensional band, through which each dimensionalized level of the subtle body anatomy is translated into wave-spectra that is within the range of perceivable matter manifestation. *The DNA can be viewed as the primary structure through which subtle energy-consciousness translates into manifest physicality.* As each full dimensional band contains 12 primary Sub-frequency Bands (See Chapter 1 for Dimensional Structure), each of the 12 DNA strands contains ***12 primary* Seed Codes,** or *consolidated scalar points* composed of electro-tonal flash-line sequences, that correspond to the Sub-Frequency Bands within each dimension. The 12 primary Seed Codes within each DNA strand have an *anti-particle counterpart* composed of frequencies from the Anti-particle system. The 12 particle Seed Codes in each strand are called **BASE CODES**, their anti-particle counterparts are called **ACCELERATION CODES**. The Seed Codes of the core DNA scalar imprint are the *points of consolidated frequency* through which energy-consciousness is drawn in from the dimensional Unified Fields to expand the personal morphogenetic field.

DNA Fire Codes- Genetic Time Codes

Along with the **12 Base Codes** and **12 Acceleration Codes** of each DNA Strand Template there are also 12 Primary DNA Codes called **DNA FIRE CODES** that regulate the relationship between human biology and the **Planetary Time Cycle** in which the biology manifests. The DNA Fire Codes can be conceptualized as existing *between* the Primary 12 Strands of the Silicate Matrix. Each Fire Code is composed of one half of the scalar frequency patterns from each of the two Primary Strands that the Fire Code is placed between. Each of the 12 Fire Codes corresponds directly to one of 12 **Signet Star Crystal Seals** in the Personal Shields of the Internal Templar Complex, and with release of the corresponding **Signet Seal**, the Fire Code comes into activation.

The DNA Fire Codes release the natural scalar barriers between particle and anti-particle DNA Strands, allowing **STRAND FUSION** to occur. Fusion of DNA strands in the particle body with corresponding strands in the anti-particle body creates a progressive transmutation of the scalar wave forms of the DNA Template and Scalar Shields, through which the polarized Particum-**Particles** and Partika-**Anti-particles** merge and transform into their original Omni-polar Partiki **Ante-matter** state. Through strand fusion, the biological carbon-based biology progressively **lessens in density** as its elemental agents are transmuted from the Kathara level, into elemental agents characteristic of the higher dimensional matter densities. **Dimensional Ascension** is achieved through release of the Kathara Grid Seals. Release of the Kathara Grid Seals creates merger of the Hova Bodies, activation of the Kundalini energies, release of the Cranial-Sacral Crystal Seals, **fusion of the DNA Strand Templates via the DNA Fire Codes**, building of the Merkaba Vehicle in the bio-energetic field and the resulting transmutation of bodily matter and shift in Angular Rotation of Particle Spin within molecular construction. Through this transformational process the human biology is released from its organic phase-lock within its current space-time cycle, and is able to engage in **transcendental travel** through the various matter density levels and Time Cycles in and beyond the 15-Dimensional Time Matrix. **As the DNA Fire Codes regulate the body's orientation to space-time, they are also referred to as the GENETIC TIME CODES.**

The DNA Fire Codes are an essential element in the natural process of restoring the natural immortal **Organic Imprint for Health** within the human body. The ability of the human form to become **perpetually self-sustaining** is dependent upon the Kathara Grid and DNA being able to continually renew the natural Primal Order of Maharic Shield scalar arrangement upon which the body is built, to keep the Star Crystal Seals and conduits of interdimensional energy supply open. **Perpetual revitalization of the body** is achieved through full activation of the **12-Strand DNA** pattern. When activated, the **DNA Fire Codes** keep the Crystal Seals, **the interdimensional INTERNAL STAR GATES of energy inflow**, open, so the finite supply of frequency held within the personal Manifestation Template can be continually renewed. Restoration of the Organic Imprint for Health, as held within the **Maharic Shield**, is achieved through progressively clearing distortions of scalar-wave arrangements within the Kathara Grid, Shields and DNA Template and realigning the entire subtle energy and physical energy systems with the Primal Order of the Maharic Shield. This process of whole-being-healing does not occur overnight, as many genetic distortions (which emerge from Kathara Grid misalignment) have served as the dominant bio-electrical program within the human genome for many thousands of years. With knowledgeable practice of Kathara Grid realignment, and supportive healing applications within the various Body-Mind-Spirit systems, these inherited distortions can be progressively healed through Regenesis of the Primal Order as held within the personal Maharic Shield.

Science, "Junk DNA" and Evolution

In the contemporary human genetic code the majority of the DNA strands corresponding to higher dimensional anatomy and consciousness are dormant or damaged due to ancient blockages within the Kathara Grid and its corresponding elements of the subtle body anatomy. Present day humans function primarily on a **3 to 3.5 DNA activation level**, while the imprint and potentialities for strands 4-12 lie dormant within the morphogenetic field and within the fragments of non-functional DNA that contemporary science has labeled ***"junk DNA"***.

The portions of the DNA chain that science has presently identified as the **"Double Helix"**, represent only the **surface portions** of the chemical, elemental and electrical components of the active DNA strands. Science has yet to identify the *multidimensional spectra* of DNA manifestation, and has yet to realize that within the structures of detectable DNA, there are *levels of structure and function* that direct the operations of the *entire genetic imprint*, which are *not presently detectable* by contemporary scientific technique. The human DNA imprint will always appear from external analysis, as a *2-strand Double Helix* configuration, but what is not understood, is that within this Double Helix there are, and will be progressively more, **additional Double Helix strands**, which *fuse together* and add their operational coding into the active DNA imprint. By contemporary standards of categorization, if science were to objectively observe the activated 12-strand pattern (or even an activated 4-strand pattern), the DNA would *not appear to be human at all*, but rather as the seemingly incomprehensible genetic signature of an "unknown" species. As science evolves into comprehension of the multi-dimensional spectrum, the understanding of the true structure and function of DNA will progressively advance.

DNA, Kathara Healing and Bio-Spiritual Evolution

One does not have to wait for scientific theology to catch up with a rapidly evolving humanity in order to begin advancing the functions of the DNA. Through the processes of Kathara Healing, as we work to clear blockages from the Kathara Grid and to reawaken the *Imprint for Health* within the human body, we are *simultaneously, directly affecting* the operational structure of the DNA. As we work to create **Hova Body merger**- *merging of the scalar-grid flash-line sequences of the 5 Harmonic Hova Bodies*- we are progressively reordering portions of the "junk DNA" and stimulating dormant portions of the DNA into activation. As we work with subtle energies to clear blockages within the Kathara Grid, we are progressively purging ancient distortions and mutations within the gene code, distortions that have kept our collective consciousness locked into the limited 3-dimensional perceptual range of Harmonic Universe-1.

It is through the ancient distortions of the human Kathara Grid and the resulting **mutations** of the human DNA, that the multidimensional portions of identity seem separate from each other. The higher levels of conscious awareness that are stationed within the scalar grids of the higher dimensional Hova Body Shields have been unable to *electronically translate* into the lower dimensional identity stations of the Nada Hova Body and its apparent physical manifestation. As we work with Kathara Healing to create progressive Hova Body merger and DNA strand ordering and activation, we will progressively experience *advancement of conscious awareness* and *expansion of the perceptual field* and *Higher Sensory Perception* (HSP). This expansion and advancement occurs because we are able to progressively embody higher frequencies of consciousness and scalar wave flash-line sequences into the personal morphogenetic field, via the energetic conduits of the DNA. **Kathara Healing modalities are the fastest and easiest methods available to repair and advance the function of the DNA and to expedite the organic processes of *Bio-Spiritual Evolution*.**

The Silicate Matrix 12-Strand DNA Template with Hova Body, Scalar Shield and Identity Level Correspondences

The Morphogenetic Field Scalar-wave Template for the Original Human Genome


Maharic Shield
Mahara Hova Body
Avatar "Christed" Identity
Chakras 10-12
Mahunta Phase Merkaba
(12 Dimensional Merkaba)
Telluric Shield
Nada Hova Body
Incarnate Identity
Chakras 1-3
STRAND-12
STRAND-1
STRAND-11
STRAND-2
STRAND-10
STRAND-3
STRAND-9
STRAND-4
STRAND-8
STRAND-5
STRAND-7
STRAND-6
FC-12
FC-1
FC-11
FC-2
FC-10
FC-3
FC-9
FC-4
FC-8
FC-5
FC-7
FC-6
Teuric Shield
Betcha Hova Body
Over-Soul Identity
Chakras 7-9
Quatra Phase Merkaba
(9Dimensional Merkaba)
Doradic Shield
Alphi Hova Body
Soul Identity
Chakras 4-6
Hallah Phase Merkaba
(6 dimensional Merkaba)

12 Base Codes per Strand = ● **12 Acceleration Codes per Strand = ○**

12 FIRE CODES between Strands = ✡

(Diagram presents simple conceptualization of DNA Strand Template orientation, not actual geometrical arrangement of wave-form structure and observable strand interrelationship.)

Merkaba Phases – Building the Merkaba Vehicle

Formation of the **Mahunta Merkaba** marks fulfillment of the 12-Strand DNA potential.


4
Rahunta Phase
15 Dimensional
3
Mahunta Phase
12 Dimensional
15-Dimensional
Time Matrix
Rishi Identity
Avatar Identity
Dimensions
15
14
13
12
11
10
9
Over-Soul Identity
8
7
Soul Identity
6
5
4
3
2
1
Incarnate Identity



The 4 Personal Scalar Shields merge to form the 12-Dimensional Mahunta Merkaba


Quatra Phase
9 Dimensional
2


HU/ Density-3
D9
D8
D7
HU/Density-2
D6
D5
D4
HU/Density-1
D3
D2
D1
QUATRA
HALLAH


Avatar Strands
Mahunta Merkaba
12
11
10
1
Incarnate Strands
2
3
9
8
4
Over-Soul Strands
Quatra Merkaba
7
6
5
Soul Strands
Hallah Merkaba


Hallah Phase
6 Dimensional
1

The Merkaba Vehicle: Counter-rotating Spirals of interdimensional electromagnetic energy in star-tetrahedron form that form in the auric field, enabling biological interdimensional travel and ascension.

12-Strand Silicate Matrix DNA Diagram shows Strand relationships

THE 12 HUMAN SENSES, APPARTHI AND HSP

Perception and the Hologram

In earlier text we have explained that **manifestation is not what it appears to be**, but rather a **Holographic Projection** of consciousness through the structures of **dimensionalization**. Further, that dimensionalization itself is a *compartmentalization* of consciousness created through units of consciousness (Partiki, Partika and Particum) *assembling in specific mathematical-geometrical ratios* to form **scalar grids**, interwoven fabrics of *fixed points of electro-tonal units* that form layers of standing-waves -**scalar waves** - that serve to "flesh out" the structure of the Hologram, through projection along a *vertical, horizontal* and *diagonal axis*. We have explored the **Kathara Grid** - the *core template* of scalar standing-waves upon which consciousness begins its experience of dimensionalization, the structures of the **15-Dimensional Universe** construction, and how these characteristics of the Hologram relate to forming the structure of **15-Dimensional Human Anatomy**. In understanding the basic foundations upon which our perceivable Hologram forms, we begin to better comprehend the nature of reality and of ourselves within this multi-dimensional reality structure. **Through the Holographic Projection of consciousness within the cosmic Unified Field of Energy-consciousness and its scalar fields of dimensionalization, we perceive the conditions of space, time, matter, externalization of reality and individuation of identity.** Within the Hologram of consciousness we perceive as **solid and objectified** the **wave spectra** and their inherent energy constructs of that which exists **precisely one dimensional band below the present station of our consciousness focus.**

In this section we will explore a bit about the **apparatus of perception** that allow us to perceive externalization in such a manner, the **facilities of energy inherent to the scalar-wave construct of the human form,** which together work to bring the Hologram into perceivable manifestation. We will call the constructs of energy formed through scalar organization, which allow for perception of the manifest Hologram, the **HUMAN SENSES.**

THE *HUMAN SENSES* ARE THE *EXPERIENTIAL RESULT* OF *ORGANIZATIONS OF WAVE PATTERNS* INHERENT TO THE ELECTRO-TONAL PROGRAM AND SCALAR ORGANIZATION OF HUMAN CONSTRUCTION.

What ARE Senses?

Senses are the **scalar-wave apparatus**, and their seemingly manifest parts, that allow the personal morphogenetic field to **synthesize and translate frequency** from the dimensional bands of the Unified Field, into **coherent perceptual and experiential qualities** that give embodied consciousness a **translation of its relationship to other forms of consciousness within the Unified Field.** Senses - or the apparatus which give us the *ABILITY TO SENSE*- are scalar arrangements inherent to our form that **TRANSLATE ENERGY SIGNATURES FROM THE UNIFIED FIELD INTO USABLE DATA OF RELATIONSHIP.**

Like the true substance of the human body and consciousness, the Unified Field exists as a *quantity of dimensionalized energy-consciousness in electro-tonal scalar wave form* - a compartmentalized field of **ENERGY SIGNATURES**, within which a vast number of **consciousness constructs** exist The human organism is one such **construct of consciousness**, and through its inherent form, the *energy signatures* of other scalar forms are translated into perceptual data. **The senses are simply *energy constructs* within the human morphogenetic field, that *separate and translate energy signatures from the Unified Field* into sets of experiential stimuli, through which the contours of the manifest Hologram can be *recognized* and *experienced.***

The APPARTHI and Perception

The sense facilities are *organizations of energy* within the morphogenetic field that hold sets of "*energy receivers" or magnetic points of cohesion*, into which *like frequency patterns* from the Unified Field are drawn in for translation. Every organism has a different configuration of energy receivers within its morphogenetic makeup, and so every organism will have a variation of perception. The **morphogenetic energy receivers**, or **APPARTHI** of an organism's construction serve to *draw certain frequency bands into the morphogenetic field for translation and to block out other frequency bands*, making them unavailable for translation. The frequency bands, or *flash-lines of Partiki Phasing*, that are blocked out of the personal morphogenetic field, create **GAPS OF PERCEPTION** of the Unified Field, through which the Holographic picture of "space between objects", "externalization of form" and "separation of SELF from the Unified Field" becomes perceivable to the organism. **These qualities of *objectification* are the result of BLOCKED FLASH-LINE SEQUENCES, portions of the *scalar fields* of the Unified Field and their inherent *sequences of Partiki Phasing*, that *cannot translate* through the personal morphogenetic field due to the arrangement of the APPARTHI within the personal morphogenetic structure.**

Senses as Scalar-wave Constructs & Expanding our Perception of Perception

If it can be recognized that externalization of experience is a perceptual illusion of consciousness created through selectivity of range within the perceptual field, the true nature of the human sense facilities can be better understood as a pattern of interrelated scalar-wave forms that serve to block out portions of the Unified Field so that other portions may be brought more fully into perceivable view. **When viewing the *physical apparatus* through which the known human senses appear to occur as part a of larger, interwoven system of *scalar construction*, it will be easier to understand that *perception is not a localized phenomena created by and limited to the identified organs of perception.*** The experiential capacities of even the 5 known human senses have a much broader range than what is presently assumed or identifiable through analysis of the manifest sense organs. *If one can understand that perception of manifestation itself is an affect of these greater scalar wave constructs, it will not seem so outrageous to consider the reality and integrity of sensing and perception beyond the range of the presently identified sense facilities.*

ESP, HSP and Evolution

"Extra-sensory perception" is not "EXTRA" at all, it is a *normal attribute* of the *evolving human organism*, as the consciousness ensconced within the *body hologram* continues its *natural expansion* into the greater portions of its evolutionary imprint. Individuals displaying abilities of "Extra-sensory Perception" are not gifted with something *other than what is characteristic to the human form*, **they are simply *a bit ahead in the stage of development* of the natural human perceptual capacities. Everyone has dormant potentials for some degree of "ESP"; like all things within the human organism, ESP is regulated by the *function of the DNA* and its naturally intended *relationship* to the *Kathara Grid and morphogenetic structure.*** Individuals with **less distortions and blockages** within the **Kathara Grid** (and the resulting DNA malfunctions such distortions create) will have *greater ease* in calling the dormant perceptual facilities into activation. *Individuals who consciously attempt to use the greater perceptual facilities will stimulate a more rapid advancement into reclaiming this stage of evolution, than those who refuse to acknowledge the existence of their greater sensing facilities.* **The greater sense facilities bring the *higher dimensional wave spectra* and its inherent reality fields into the *perceptual range* of the earthly embodied human consciousness, and so the greater sense facilities can be considered the HIGHER SENSES, a term far more accurately describing their orientation than the term *Extra Senses*. "ESP" becomes "HSP"- *Higher* Sensory Perception - a *natural attribute of experience for the evolving human organism.***

THE 5 KNOWN SENSES

The 5 Known Human Senses

In order to understand the nature of the **Higher Senses** it is necessary to understand a bit more about the nature of the **common senses**, or the *"lower senses"* if you will, for the **common senses** are those that are "tuned to" perception of the **lower frequency dimensions. Perception of *Sight, Sound, Touch, Taste and Smell* are *experiential affects* of the *scalar-wave constructs* that exist within the NADA HOVA BODY and the TELLURIC SHIELD, the Kathara Grid and morphogenetic field structures that are composed of and stationed within the frequency bands of dimensions 1, 2 and 3, the first Harmonic of manifestation.** The **APPARTHI**, or ***"energy receivers"*** within the Nada Hova body have their first imprint within the **Kathara Grid Level-2: Crystal Seals** structure. The first pattern for the sense facilities responsible for manifesting the organs of perception of the 5 identified senses exist within the configurations of electro-tonal Partiki units that form the crystalline seals of which the dimension-2 **Telluric Shield** is constructed. Through the Partiki Phasing flash-line projections of the Telluric Shield, the "armature" or 3-dimensional blueprint for the organs of perception are set for manifestation within the body hologram.

The 5 Known Senses and Sound Transduction

The 5 known senses are more intimately related than commonly supposed; ALL represent a form of SOUND TRANSDUCTION - the frequencies, or flash-line sequences, within the 1st, 2nd and 3rd dimensional bands, that form the identifiable wave patterns presently associated with sound waves, are drawn into the Level-2 Kathara Grid Crystal Seals by **Apparthi receivers** that carry like flash rhythms. Once drawn into the Apparthi receivers the sound spectrum becomes modulated into different flash-line rhythms and sent into the **Diodic Points of the Level-3 Kathara Grid.** Once intersecting with the frequencies within the Diodic Points the frequencies from the Apparthi are then **divided/ polarized** and projected up and down the Harmonic-1 dimensional scale, **creating a pattern of energy refraction** within the morphogenetic field and physical body apparatus. The polarized frequencies first appear within the **DNA** as part of the core electrical vibration, and then further transmute into **electrical impulse** that manifests as configurations with the **blood chemistry** and within the **Central Nervous System.** These synthesized electrical impulses are further projected through the **scalar-wave grids** that hold the form of the **identified sensory organs,** finally **culminating in the interrelated qualities of perception associated with the identified sensory organs and their 5 known attributes of sensing.**

THE 12 HUMAN SENSES

The Interwoven Senses and the Hova Bodies

As in the case of the Lower Senses, the *Higher Senses* and their experiential manifestations are the product of consciousness interacting with the *dimensionalized scalar organization* of the human morphogenetic anatomy. Whereas the Lower Senses are affiliated with the transduction of sound frequency within the *1st, 2nd and 3rd Dimensions*, through the structures of the *Nada Hova Body* and the *Telluric Shield* of the *first Harmonic*, the Higher Senses are in like fashion associated with the scalar organization of the *Higher Dimensional Hova Bodies* and their corresponding *Shields*.

In truth, all of the sensing facilities organic to the human form comprise interwoven and interrelated systems of *energy refraction* that together create the perceptual experience of *externalization* within the hologram of manifestation. For example, it is not commonly recognized that the sense of **smell** is in actuality part of the function of the **auditory facility**, and thus represents an intrinsic part of the sense of hearing. It is also not commonly understood that the processes associated with **vision** are not only connected to the processes of the brain and Central Nervous System, but also with the formation of *crystalline structures* with the plasma of the **blood. The senses are not nearly as *separate* and *independently functional* as they appear to be when viewed from outside analysis.** They are rather a part of an **interwoven system of electro-tonal information relay** that spans the 15-Dimensional morphogenetic field anatomy of the human organism.

The 12 Human Senses

In terms of breaking down the sense facilities for structural analysis, such as is done by modern science in identifying the 5 Known Senses, we will describe the sensory attributes of the **Higher Sense facilities** in terms of their *primary orientation*, *location of their primary Apparthi receivers* within the *Hova Body* structures and by the type of *perceptual or experiential attributes* produced through their function. **In such categorization of the human sense facilities there are *7 additional*, as yet unidentified, *sense facilities* operating within and through the human consciousness**, which are collectively responsible for translating the scalar fields of dimensionalized reality into the *illusionary holographic picture* of externalized manifestation and its qualities of space, time, matter and identity individuation. **Collectively there *are 12 Primary Sensing Facilities* within 15-Dimensional Human Anatomy.**

PERCEPTUAL BLOCKAGE, KATHARA GRID DISTORTION AND KATHARA HEALING

Perceptual Blockages

The Higher Senses are connected to the Lower Senses and provide attributes of perceptual experience characteristic to their dimensional levels, but in the present stage of human genetic evolution the Higher and Lower Senses are not fully "plugged into" each other, and so the various higher dimensional fields, and the sensory abilities associated with the Higher Senses, appear to be separate or unavailable to the embodied human consciousness.. **The Higher and Lower Senses plug in through opening of *Kathara Lines* in the *Level-1 12-Tree Kathara Grid*, which creates a reciprocal opening and expansion of the DNA, Hova Bodies and activation of dormant nerve networks within the brain, molecular core and Central Nervous System of the body.**

Presently the human senses are *phase-locked into a 3-dimensional perceptual field* due to blockages between the *3rd and 4th Kathara Centers*, which block the Apparthi receivers within the Nada Hova Body from accepting compatible electrical impulses from the higher dimensional Hova Bodies. This Kathara Grid blockage manifests within the body as fragmented units of DNA (**"Junk DNA"**), that serve to render the natural processes of multi-dimensional data transfer into the Central Nervous System inoperable. Portions of *higher dimensional experience* come to conscious attention in the form of *dream perception* or *intuitive impression,* but the natural clear pathways of multi-dimensional perception are blocked to a large degree within contemporary humanity.

Perceptual Blockages and Kathara Healing

Blockages in the Kathara Grid and their reciprocal blockages in the human perceptual field can be progressively removed through practices of *Kathara Healing*, and utilizing the *Maharic Shield* to reawaken the Organic Imprint for Health.. As Kathara blockages are progressively repaired, the genetic code will expand its function by reassembling and activating the presently dormant portions of the DNA imprint. DNA expansion will create reciprocal alterations in the bodily metabolic rate, brain, blood, glandular and hormonal function, particle spin speed and operation of the Central Nervous System, that will allow for a progressive, natural activation of the Higher Sense facilities and expansion of the human perceptual field into the multi-dimensional arena. **In Kathara Healing the dormant Higher Senses will be progressively brought into activation**, beginning with the **6th -Audurea-Merkaba Sense** and the **7th-Tristet-Cellular Telepathy Sense** through which **Inner audio-visual-direct cognition** skills will progressively develop. These skills will be employed in the processes of Kathara Healing, and in so doing they will be progressively stimulated into greater levels of activation. As the dormant Sense facilities are called into activation, Kathara Healing techniques to remove Kathara Grid blockages are used to realign the *Holographic Template* to restore the **Imprint for Health,** through which natural perceptual expansion will progressively take place.

The 12 Human Senses

The collective spectrum of human sense facilities, including the Higher Senses of 15-Dimensional Human Anatomy can be categorized as follows:

The 12 Human Senses, Hova Bodies and Primary Experiential Attributes

Identified Lower Dimensional Sense Facilities

1. Visual-Sight Sense- ***Nada Hova Body (dimensions 1-2-3)***
2. Auditory-Hearing Sense - ***Nada Hova Body***
3. Tactile-Touch Sense- ***Nada Hova Body***
4. Olfactory-Smell Sense- ***Nada Hova Body***
5. Sense of Taste- ***Nada Hova Body***

Unidentified Higher Dimensional Sense Facilities

6. **Audurea -Merkaba Sense -** *Encompasses all Hova Bodies*
   Primary Attribute: **Manifestation**-circulation of consciousness and frequency accretion
7. **Tristet-Cellular Telepathy** -*Alphi Hova Body (dimensions 4-5-6)*
   Primary Attribute: **Inner Audio-Visual-Direct Cognition** reading energy signatures.
8. **Nurgode-Transmutation Sense -** *Betcha Hova Body(dimensions 7-8-9)*
   Primary Attribute: **Molecular Transmutation** - shape-shifting
9. **Ragode-Transmigration Sense -** *Betcha Hova Body*
   Primary Attribute: **Transmigration** - Projection of Consciousness
10. **Geuard-Transfiguration Sense-** *Mahara Hova Body (dimensions 10-11-12)*
    Primary Attribute: **Bilocation**-multiple holographic manifestations
11. **Shara-Centrifugal Sense-** *Raja Hova Body (dimensions 13-14-15)*
    Primary Attribute: **Electrical Projection** - consciousness enters dimensionalization
12. **Aurt-U - Centripetal Sense -** *Raja Hova Body*
    Primary Attribute: **Magnetic Accretion** -consciousness exits dimensionalization

CHAPTER 2 HIGHLIGHTS

THE IMPRINT FOR HEALTH

- Healing occurs through correcting distortions within the Kathara Grid and Hova Body Shields.

- The human body blueprint was designed to hold 12 Dimensions of Frequency/ Flash-line Sequences and 12 Dimensions of Consciousness, the content of 4 out of the 5 Hova Bodies within the 15-Dimensional Anatomy.

- The **4th Hova Body** - the **Mahara Hova Body** - is composed of Frequencies/ Partiki Phasing Flash-line Sequences of the **10th, 11th and 12th Dimensions.** It manifests through the 10th, 11th and 12th *Kathara Centers* and the **Maharic Shield** Scalar Grid of the **4th Harmonic.**

- The **Maharic Shield** of *Level-2 Kathara Grid Crystal Seals* holds the original **IMPRINT FOR HEALTH**- the original *Flash-line Sequences* of *Harmonic 4 Pre-matter Liquid Light* - that represent the *point of entry* into perceivable manifestation.

- The **Maharic Shield** can be used to **repattern** the Kathara Grid Holographic Template back to the original **Imprint for Heath**. The Flash-line Sequences of *Dimension 12* can *override* and correct *faulty Flash-line Sequences* that manifest as distortions within the Kathara Grid and Hova Body Shields.

- The **Hierophant Symbol Code** is a *Scalar Standing-wave* pattern containing the electro-tonal programs of the 11th and 12th Dimensions. The Hierophant Symbol code serves as a *Frequency **WAVE GUIDE*** through which the **Maharic Shield** can be activated to run 11th and 12th Dimensional Frequency through the Kathara Grid for **repatterning** the **Imprint for Health** within the Core Holographic Template of the body.

- Using the *Hierophant Symbol Code* the **Planetary Bio-feed Interface System™** can be activated to **empower** the Kathara Grid repatterning process via drawing Frequency from the **Planetary Maharic Shield.**

MORPHOGENETIC EXPANSION

GROWTH RATES

- Growth through time is created through **FREQUENCY ACCRETION -** drawing Frequency Bands from the Dimensional Unified Fields of Consciousness into the personal morphogenetic field for expansion.

- When the Kathara Grid is functioning properly there are **set morphogenetic field expansion periods** within the linear growth cycles of the human body.
  1. **Fetal Integration** to age 11-12.
  2. **Harmonic 2 Integration** age 12-22
  3. **Harmonic 3 Integration** age 22-33
  4. **Harmonic 4 Integration** age 33-44

  If the Kathara Grid is working properly the **body does not die** but rather **progressively transmutes** into *less dense states of matter* in an **immortal body form,** via accretion of the 4 Harmonics of Frequency.

- Present **Kathara Distortions** block integration of **Harmonic 2** and begin Molecular Compaction, body degeneration and Death.

LEVELS OF HUMAN ANATOMY

- The **Kathara Grid** is the *Core Holographic Template* upon which the human body and consciousness enter dimensionalization in order to experience manifestation.

- There are **3 Levels** to the Human *Kathara Grid*: *Level-1*- The **12- Tree,** *Level-2* – **Crystal Seals** and *Level-3* – **Diodic Points.**

- *Kathara Level-1 –12-Tree* contains the primary **12 Kathara Centers** and primary **15 Kathara Lines,** that correspond to various regions of the physical body and bio-energetic field and which "ground" consciousness into the framework of dimensionalization.

- *Kathara Level-2 – Crystal Seals* contain the **Signets** *–consolidated points of dimensional frequency* – the **Shields** – *3-dimensional scalar-wave discs emanating from sets of 3 Signets* through which the *Hova Body* energy capsules form– and the **Star Crystal Seals** and **Seed Crystal Seals** through which the *Chakras* and *Bio-energetic Field* levels emerge.

- *Kathara Level-3 – Diodic Points* are **Coordinate Points** where the flash-line sequences from one Shield and its Seals cross over and through those of other Shields to form minute **"White Hole" vortices** of energy-consciousness relay between the Hova Bodies and stations of identity.

- **Hova Bodies** are *3-dimensional scalar grids* in the form of **Concentric Spheres** that form around each **Shield** in the *Kathara Level-2 Crystal Seals Grid,* which serve as "tissue capsule" encasements around each Harmonic of energy-identity within the 15-dimensional scale.

- There are **5** *Dimensionalized* **"Ariea" Hova Bodies** forming human anatomy, which emanate from the **5** 3-Dimensional scalar **Shields** of the *Level-2 Kathara Grid*. Each Shield and Hova Body corresponds to **3 Kathara Centers** in the *Level-1 12-Tree Grid.*

- **5 Ariea Hova Bodies** and Corresponding **Shields:**
  Nada Hova-Telluric Shield-Dimensions1-3
  Alphi Hova-Doradic Shield-Dimensions 4-6
  Betcha Hova-Teuric Shield-Dimensions 7-9
  Mahara Hova-*Maharic Shield*-Dimensions 10-12
  Raja Hova-Rishic Shield-Dimensions 13-15

- The **Signets** and the **Shields** can be used to direct the function of the *Kathara Level-1 12-Tree Grid* and all built upon it. **Kathara Centers** can be used to trigger activation of the *Signets* and *Shields*.

- The first **4 Hova Bodies** and their **Horizontal Shields**, are most important in terms of human evolution. Activation of the **Signets** activates their corresponding **Shield**, which in turn releases the **tissue capsules** between *Hova Bodies*, allowing merger to occur. When the **first 4 Shields** activate the body is able to integrate the Avatar identity and **transmute** into pre-matter liquid-light wave form.

- In *Kathara Healing* the Harmonic-4 **Maharic Shield** is used to restore integrity to all *Shields* and *Hova Bodies* below, which progressively clears the *Kathara Grid* of distortions.

- *Level-1 Kathara Lines* direct the **Vertical** Flash-lines, *Level-2 Crystal Seals* control the **Horizontal** Flash-lines and *Level-3 Diodic Points* govern **Diagonal** Flash-lines. Together the 3 levels of the Kathara Grid form the 3-plane armature upon which the 3-dimensional hologram is created.

- Each **Signet** within a Hova Body Shield holds the electro-tonal program for one *Seed Crystal Seal*. Each *Seed Crystal Seal* corresponds to one Level-1 **Kathara Center** and holds the program for one primary **Axiom Line** – a *single axis* dimensional flash-line sequence.
- The **12 Primary Axiom Line** programs of the *Seed Crystal Seals* create separate *dimensionalized bands of frequency* within each Hova Body, forming a distinction between *dimensionalized levels* within the bio-energetic **Auric Field**. The Axiom flash-lines cross over and through each other to form the *Coordinate Points* between the Shields through which the *Level-3* **Diodic Point Vortices** emerge.
- The points in the Kathara Grid where Axiom Lines cross over and through the **Central Vertical Kathara Line** in the *Level-1 Grid*, and the **Horizontal flash-lines** in the *Crystal Seals* of the *Level-2 Grid*, form **consolidated Diodic Points** with *numerous Diodic Vortices* – these are called **CHAKRAS**. Each Chakra corresponds to an *Axiom Line, Auric Level, Seed Seal, Kathara Center*, and *Dimensional Frequency Band* and ***Merkaba Field***.

- The **12 Primary Axi-A-Tonal Lines** are a set of 12 *Vertical Energy Flow-lines* that run through the body, which are created by the consistent cross-over points of the rotating, single-axis flash-line sequences projected from the **Seed Crystal Seals.**

- **Axi-A-Tonal Lines 11 and 12** combine with the **Central Vertical Kathara Line** to form the **Hara Line**, the foundation of the **Central Body Current.**

- The **Hara Level** is the ***outer level*** of the **Kathara Level-2 Crystal Seals Grid**, can be viewed from *9th-Dimensional perception* and is used in Kathara Healing Level-2 .

- The *Hara Level* is composed of the **Hara Line, 6 Primary Hara Points** and the **Complexes** of energy processing they govern.

- The **Axi-A-Tonal Lines** and **Hara Level** of the *Kathara Level-2 Crystal Seals Grid* are elements of 15-Dimensional anatomy that are used in later applications of Kathara Healing.

- *Axi-A-Tonal Lines* set the core electro-tonal scalar-wave program upon which the **DNA** will manifest. The human DNA imprint contains the program for **12 strands of DNA**, one manifesting upon each of the **12 Primary Axi-A-Tonal Lines.**

- The human form was designed to embody **12 dimensions** of consciousness. The original human genetic code is called the **Silicate Matrix** and when operational it allows human cellular structure to **transmute** through ***4 Harmonics*** *of matter density*.

- The Silicate Matrix is mutated in present day humans due to ancient **Kathara Grid blockages,** which manifest as distortions of form and function within the DNA. "*Junk DNA*" is part of this distortion.

- Contemporary human DNA can be **reverse-mutated,** and its interdimensional functions restored, by applications of **Kathara Healing**.

- Each of the 12 strands of DNA *corresponds to* one of 12 *Dimensional Frequency Bands, Kathara Centers, Seed Crystal Seals, Signets, Axi-A-Tonal Lines*, and *Chakras*. Each **Hova Body Shield** governs the function of a **set of 3 DNA strands.**

THE 12 HUMAN SENSES

- The **human senses** are the *experiential result* of the *scalar standing-wave organization* inherent to the human form.

- Senses are **scalar arrangements** that *translate energy signatures* from the **Unified Field** into *usable data of relationship*.

- The sensing systems are built upon sets of **energy receivers** within the morphogenetic field that are called **APPARTHI**. The Apparthi inherent to Kathara structure serve to **block certain flash-line sequences** out of the morphogenetic field and allow others in to translate into perception.

- The flash-line sequences blocked by the Apparthi create **Gaps of Perception** of the *Unified Field*, which give us the *experience* of **externalization** and **separation of form.**

- *Apparthi receivers* create **refraction and polarization of flash-line sequences** that translate into a variety of identifiable ***holographic sensory perceptions.***

- The sense facilities correspond to the structure of the **Hova Body Shields** and **DNA.** In categorizing the interwoven sense facilities by their *primary orientation*, location of their *Apparthi receivers* within the Hova Bodies and the *experiential attributes* they produce, the human organism can be said to possess **12 Primary Senses.**

- The **5 known senses** are products of the operations of the **Nada Hova Body** and **Telluric Shield**, and thus correspond to **dimensions 1-3**.

- There are **7 as yet unidentified senses** that correspond to the higher dimensional *Hova Bodies, Shields* and presently dormant strands of *DNA*.

- As we evolve to *activate* and *reverse-mutate* the **DNA** imprint, through *Hova Body* alignment and merger, the experiential attributes of the higher dimensional senses will become more apparent.

- Due to their *dimensional affiliation*, the *5 known senses* can be viewed as the **Lower Senses**, the *higher dimensional senses* as the **Higher Senses.** Perception through the *Higher Senses* is called ***Higher Sensory Perception*** or **HSP.**

TAPPING THE INNER MENTOR

Levels of Consciousness and the Perceptual Bridge

In earlier text we have learned of the structure human consciousness takes when entering the scalar fields of dimensionalization for the perceivable experience of manifestation. In comprehending the true structure of multi-dimensional anatomy, with its **Kathara Grid, Hova Bodies** and **Shields, Diodic Points** and **levels of bio-energetic substance**, we can begin to see that there is much more to human consciousness than meets the eye - **much more *energy-identity* operating presently beyond the view of our 3-dimensionally focused earthly personality.**

There are portions of our consciousness stationed within the Hova Bodies of the higher dimensional fields, and these expanded levels of ourselves hold knowledge and participate in perceptual experience beyond the usual range of our waking perceptions. As we evolve and expand through **Hova Body Integration** and the resulting activation of dormant **DNA** components, we will progressively have *greater conscious access* to these expanded levels of consciousness while we are actively focused within the waking 3-dimensionally embodied state. However, **we do not have to wait until our evolution plods along to bring us to these expanded perceptual states,** we can, from our waking state of 3-dimensional consciousness begin to actively tap this hidden reservoir of knowledge and perceptual experience. **We can take an active hand in *expediting the process* of our multi-dimensional evolution by using our dimension-3 *mental body awareness* to direct our higher awareness into our current range of perception.** We can begin to build a **PERCEPTUAL BRIDGE** between our 3rd-Dimensional and Higher Dimensional consciousness. **In taking the initiative for building this Bridge of Consciousness we begin to stimulate our Higher Senses into operation, expediting the natural process of Higher Identity Integration.**

Through building a PERCEPTUAL BRIDGE between our present state of awareness and the levels of our consciousness stationed in the Higher Dimensional Hova Bodies, we can actively expedite our own Bio-Spiritual Evolution.

THE MENTOR

The Perceptual Bridge and Creating the Mentor

The Higher Dimensional levels of human consciousness are not dormant within their respective dimensional bands of function, they are quite awake and aware within their own dimensional fields. As we perceive and interact with the 3-dimensional world within which our present awareness is focused, the Higher Dimensional portions of our consciousness are also actively perceiving and interacting with the dimensional environments within which they are focused. **Higher dimensional aspects of our awareness *seem cut off* from our perceptual view because our consciousness is presently focused through a *genetic code arrangement and Kathara Grid orientation* that blocks out the frequencies of those higher stations of identity.** If we can realize that expanded portions of our consciousness simultaneously exist within the higher dimensional frequency bands, we can also realize that it is possible to access such levels of our own identity by building **Perceptual Bridges** between our 3-dimensional perspective and the portions of our consciousness stationed within the Higher Dimensional Hova Bodies.

We can begin to build a *Perceptual Bridge* between ourselves and our *Higher Selves*, by using simple *frequency modulation techniques* of Kathara Healing, such as Technique #1: *Awakening the Mentor and the 6th and 7th Senses*. In this scalar-grid activating exercise, we will awaken dormant **Partiki Phasing Flash-lines** and activate dormant portions of the **Kathara Lines** in the *Kathara 12-Tree Grid*, to begin opening the channels of communication between the consciousness focused within the *Nada Hova Body* and that focused within the *Alphi Hova Body* of Harmonic-2. **In this exercise we will create the MENTOR, a portion of our consciousness composed of *3rd, 4th and 5th Dimensional frequencies*, that will serve as an *intermediary focus of awareness* through which we can begin to receive guidance and knowledge from our 2nd-Harmonic of consciousness.** Creating the MENTOR will begin the process of activating dormant **DNA** , opening new **nerve networks** within the Central Nervous System of the 3-dimensional body, and activating dormant **APPARTHI** frequency receivers within the *Level-2 Crystal Seals Kathara Grid*. **Through creating the MENTOR, we begin to build the Perceptual Bridge between the 1st and 2nd Harmonic of our conscious awareness.**

The MENTOR is a portion of our identity that we create to serve as an intermediary focus of awareness between the Nada Hova Body and the Alphi Hova Body; a PERCEPTUAL BRIDGE between our first and second Harmonics of Consciousness.

The MENTOR and Kathara Healing

In the practices of Kathara Healing we will use the MENTOR as a source of **guidance, information retrieval, objective observation** and as a **communications link** between our own higher consciousness and the higher levels of consciousness in those who come to us for healing facilitation. **Awakening and working with the MENTOR will become a standard practice in our applications of Kathara Healing.** In creating the MENTOR we are using our creative power of scalar-grid manifestation (thoughts and mental images are scalar-grid morphogenetic field forms) to bring into being a **specialized portion of our consciousness** that can **relay frequency** from our higher Harmonics of Consciousness to our 3-dimensionally focused identity. **With repeated use of the MENTOR focus of awareness we will develop the ability to simultaneously hold 2 Harmonics of consciousness, and we will begin to reclaim the natural flexibility of focus that is the healthful condition of embodied human consciousness.** Through the MENTOR focus of attention we can reach higher levels of cognition and understanding regarding application of healing facilitation, and we will more rapidly call into awakening the Higher Sense facilities of the 15-Dimensional Anatomy.

Other Uses of the MENTOR Focus

In creating the MENTOR focus we will begin to realize that even the 3-dimensional focus of awareness with which we are most familiar is far more flexible than once supposed. The MENTOR is not simply an **inert creation,** but rather a **living** portion of our conscious identity composed of portions of the waking self and portions of the Higher Self. MENTOR can become an **advisor**, a portion of self able to "keep its head above the illusion" when you are confronted with challenging events in the 3-dimensional arena; a part of you able to remain clam, focused and able to make clear decisions beyond the confusion of mental or emotional body processing. MENTOR can be sent into the **Cellular Memory** of the body to locate core issues or reincarnational blockages, and can serve to moderate between sub-personality fragments and the "Inner Child". MENTOR can like wise be used to **harmonize communications** between self and others, as you can send the MENTOR focus into the higher dimensional fields to connect with the higher selves of others for conflict resolution. Playing with the MENTOR focus can also have great rewards. You can focus your attention in the Mentor Space and then direct the MENTOR across the room to begin practicing affects of **BILOCATION.** You can travel with MENTOR to distant locations to develop **REMOTE VIEWING SKILLS**, which will be used in later Kathara Healing levels for **REMOTE HEALING FACILITATION**. MENTOR can become a **vehicle for conscious transport** of your awareness, while awake and also in **dreaming** and **higher dimensional projection.**

TECHNIQUE # 1

AWAKENING THE *MENTOR* AND THE 6TH AND 7TH SENSES

Awakening the Mentor:

1. Place the **fingertips** of both hands and the focus of your attention at the **Navel.** Take a few slow, full breaths then visualize the image of a **Blue Flame** (like a gas stove flame) deep inside the body behind the Navel. Gently **massage** the Navel region while envisioning the **Blue Flame.**

2. **Stop massage** and visualize a **Sphere of White Light within the Blue Flame** behind the Navel. **Place your attention within the White Sphere** and imagine that you can feel its reality around you, as if you are sitting within the White Light Sphere.

3. Breath gently and visualize the **White Light Sphere moving upward** through the center of your body until it reaches the center of the brain at the **Pineal Gland. Stop movement of White Light Sphere at the Pineal Gland,** then visualize the **White Light Sphere moving to the RIGHT** in a straight, horizontal line **OUTSIDE OF THE BODY** until it is positioned in your **auric field** just above your **RIGHT SHOULDER.** ***The White Light Sphere positioned over the Right Shoulder now represents a portion of your awareness*** *that was raised to the 5th-Dimensional frequencies via its passage through the Blue Flame and the 5th Kathara Center at the Navel.* You will name this part of your higher identity **MENTOR.**

4. Imagine that you can **feel the reality of the White Light Sphere** that holds your MENTOR resting gently above your Right Shoulder as a **"fuzzy ball of energy".** ***MENTOR*** *serves as the meeting point between your waking conscious mind and the* ***5th-Dimensional portion*** *of your Soul Matrix Identity-* ***the Archetype.*** *With practice, you* ***can lean the energy of your waking awareness*** *from its position within your head, over to the right and into the* ***MENTOR Sphere,*** *to receive direct cognition, audio and visual guidance from your 5th-Dimensional Identity Station.* **In Healing Facilitation** MENTOR will communicate with the 5th-Dimensional Archetype aspect of your **Client's Soul Matrix,** asking how you may best serve the Client's Highest Evolution; guidance MENTOR receives will be translated to you from MENTOR in the form of Intuitive urge, spontaneous cognition or audio-visual directions. MENTOR will also serve as a **translator of information from your higher dimensional Stations of Identity** to your conscious mind. MENTOR can also be taken into the Dream State with you to assist in **Dream Recall** and initiating **Out-Of-Body Travel.**

5. Practice creating and sensing the Mentor Sphere over your Right Shoulder. Carry it around with you wherever you go, and play with *moving the focus of your consciousness back and forth between the inside of your head and MENTOR.* Try perceiving from both focuses of attention simultaneously. Such play will help stimulate neurological sensitivities to translating and perceiving information from the 5th and higher dimensional Stations of Awareness.

TECHNIQUE # 1: continued

AWAKENING THE *MENTOR* AND THE 6TH AND 7TH SENSES

Awakening the 6th and 7th Senses: The *Audurea* and the *Tristet*

1. Focus your attention on the **MENTOR Sphere** over your Right Shoulder. Take a few slow, deep breaths and visualize MENTOR *expanding into a Sphere the size of a Basket Ball.* Use the next **INHALE** to draw the MENTOR Sphere *toward your head*, visualizing MENTOR moving from over your Right Shoulder to a position *surrounding your entire head.* **EXHALE**, *stop the movement* of the MENTOR Sphere, and imagine that you can feel its "fuzzy energy" all around the outside of your head; *as if your head is now within the Basket Ball size MENTOR Sphere.*

2. With the next **INHALE** breath, **contract MENTOR into a small Sphere of White Light** positioned inside the center of the brain at the **Pineal Gland**. Exhale and breathe slowly for a moment. With the next **EXHALE** breath, *push* the small MENTOR Sphere from the Pineal Gland, straight forward and into the **6th-Chakra** at the *Forehead.* Visualize MENTOR moving into the 6th-Chakra from inside the head, then continuing to move through the 6th Chakra spiral straight outward and *away from the body.* Imagine the MENTOR Sphere traveling outward through the long **Blue-Violet Tunnel** of the 6th Chakra spiral, until you visually loose track of the MENTOR Sphere far out in front of you.

3. Take a few slow breaths, then on the next **INHALE** visualize the MENTOR Sphere *re-appearing* in the distance of your 6th Chakra spiral, and *riding in on the inhale breath,* back into the **Pineal Gland.** Breathe slowly.

4. With the next **EXHALE**, visualize the MENTOR Sphere moving *down from the Pineal Gland* at the center of the brain, stopping at the center of the **5th Chakra** in the *Throat.* Breathe slowly. On the next **EXHALE** push the MENTOR Sphere straight outward, imagining it moving forward from inside the Throat, into the blue green spiral of the *5th Chakra.* Visualize MENTOR *riding the current of the exhale breath* out into the distance within the blue-green **tunnel** of the 5th Chakra spiral, until it fades from view. Take a few slow breaths and on the next **INHALE** imagine MENTOR returning through the 5th Chakra blue-green spiral to rest deep within the **Throat**. Use the **final INHALE** to move MENTOR back up to the **Pineal Gland** and the final **EXHALE** to *push* the MENTOR Sphere back out to its "home" position in the auric field over the **Right Shoulder.**

This process opens up the 1st-5th Sub-frequency Bands within each dimensional layer of the 6th and 5th Chakras, beginning the process of opening the 6th-Audurea and 7th-Tristet Senses, stimulating Inner Vision and Audio to higher dimensional frequency perception.

SYMBOL SHORTHAND

TECHNIQUE # 1: Condensed Version
Awakening the Mentor and the 6th and 7th Senses

AWAKENING THE MENTOR

1. Finger *tips* at *Navel*, see *Blue Flame* in body behind Navel. *Massage* Navel with finger tips
2. See *White Sphere in Blue Flame* at Navel. Imagine *yourself in White Sphere*, feel it around you.
3. Move *White Sphere* up to *Pineal Gland*, see White Sphere move out over *Right Shoulder* creating your *MENTOR*
4. Feel *MENTOR* as *fuzzy ball* of energy hanging in your auric field over your Right Shoulder
5. *Practice shifting* the *focus* of your attention back and forth between usual focus and *MENTOR*

AWAKENING THE 6TH & 7TH SENSES

1. Expand MENTOR over Right Shoulder to size of *Basket Ball*, *INHALE* drawing *MENTOR* around your *head*, as if your head is inside the Basket Ball size energy that is MENTOR.
2. *INHALE*, *contracting MENTOR* into *Pineal Gland* as a small Sphere of White Light, *EXHALE* to push *MENTOR* out of *Pineal Gland out to Chakra 6* and into the *Blue-Violet Tunnel* of the Chakra 6 spiral.
3. *INHALE MENTOR back from Blue-Violet Tunnel* of Chakra 6 and into the *Pineal Gland*
4. *EXHALE MENTOR* from *Pineal Gland to Chakra 5. EXHALE MENTOR out* through *Chakra 5 Green Tunnel. INHALE MENTOR back* through *Green Tunnel* into *Chakra 5* at Throat. *INHALE MENTOR* up from *Chakra 5* to *Pineal Gland. EXHALE MENTOR* out from Pineal Gland to its "Home Station" over *Right Shoulder.*

Awakening the Mentor and the 6th and 7th Senses

AWAKENING THE MENTOR


C. White Sphere over Right Shoulder "Fuzzy Ball" of MENTOR energy
B. White Sphere at Pineal Gland
MENTOR
Navel
Navel
A. Blue Flame with White Sphere in Navel. Massage Navel (Kathara Center # 5) with Fingertips.

Move MENTOR from Navel to Pineal Gland to position over Right Shoulder.

AWAKENING THE 6TH AND 7TH SENSES


MENTOR
Pineal Gland
Chakra 6 Spiral
3rd Eye- forehead
Chakra 5 Spiral
Throat

Run MENTOR energies through 5th and 6th Chakras.

- A. **Expand** MENTOR energy to **basketball size** and position **around head**
- B. **MENTOR** in **Pineal Gland** as **White Sphere**
- C. **White Sphere** into **6th Chakra Spiral** then **5th Chakra Spiral** and back to **Pineal Gland.**
- D. Reposition MENTOR over **Right Shoulder**

MORPHOGENETIC REPATTERNING

MAHARIC RECODING, FREQUENCY SUB-HARMONICS & THE MAHARIC SEAL

Kathara Healing and Reaching the Core of Dis-ease

In earlier text we have explored the significance of the **Kathara Grid** and its role as the **Holographic Template** upon which the morphogenetic field, body and consciousness manifest within the 15-Dimensional system. We have learned that the Kathara Grid is the **core template** upon which the *morphogenetic field* manifests, and that the *morphogenetic field* is the **blueprint** upon which the body systems and embodied consciousness manifest. Through our study of these *core structures of manifestation* we come to realize that *true and lasting health or healing* must be approached from the deepest levels of personal creation, the *morphogenetic reality* within which all dis-ease conditions have their origin. **Kathara Healing applications are intended to reach the *core of systems malfunction*, the various levels of the *morphogenetic field and Kathara Grid*, in order to restore the *Imprint for Health* within the Holographic Template for manifestation.**

The Mahara Hova Body, Maharic Shield and the Imprint for Health

In *Level-1 Kathara Healing* we will learn the first and most important level of *restructuring the Holographic Template* to hold its original Imprint for Health - the MAHARIC RECODING PROCESS. The **MAHARIC SHIELD** is the manifestation template upon which the **MAHARA HOVA BODY** of *Harmonic-4* manifests. The Mahara Hova Body is the scalar-grid that holds the **10th, 11th and 12th-Dimensional** aspects of consciousness, and represents the **ORIGINAL POINT OF MANIFESTATION** -the **creation point** when consciousness moved from its pure scalar-wave state of being into the dimensionalized scalar-grids through which the illusion of external holographic projection could be experienced. The Mahara Hova Body and its station in Harmonic Universe-4 represent the original **PRE-MATTER LIQUID LIGHT** fields of manifestation through which we passed in order to enter the experience of density and individuation of matter form.

Prior to our entering the dimensionalization of the systems within which matter can be perceived, we existed in **pure scalar-wave form** - a scalar-pattern that held the **original, pure and perfect pattern** for our creation as consciousness. The Mahara Hova Body and the Maharic Shield are the Liquid Light Pre-matter Scalar-templates that hold our original pattern of wholeness, our original **CREATION IMPRINT**. Our creation imprint is the **ORIGINAL IMPRINT FOR HEALTH**, the condition of **eternal being** free from Hova Body distortions picked up in the lower dimensional fields.

THE 12th-DIMENSION and FREQUENCY SUB-HARMONICS

In Level-1 Kathara Healing we will utilize the *Imprint for Health* as held within the *Maharic Shield* to begin REPATTERNING the Kathara Grid back to its original level of function. The frequencies of the **12th-Dimension**, as embodied within the **Maharic Shield**, contain within them as **Frequency Sub-Harmonics** ALL OF THE FREQUENCY BANDS FROM THE DIMENSIONS BELOW, along with the natural frequency spectra characteristic to the 12th-Dimension. Each Dimensional Frequency Band within the 15-Dimensional Spectra contains within itself its own **12 Primary Sub-frequency Bands** (portions of the whole dimensional Partiki Phasing flash-line sequences), plus a **reflection set** of the frequency spectra from **all of the Dimensional Bands below.**

For example, Dimension 2 contains its own *12 Primary Sub-frequency Bands*, **plus** *a reflection set of the 12- Primary Sub-frequency Bands* that make up the *Dimension-1 Frequency Band* below. Dimension-1 has 12 Primary Sub-frequency Bands, Dimension-2 thus has 12 Primary Sub-Frequency Bands plus 12 Secondary Sub-Frequency Bands from Dimension-1for a total of *24 Sub-Harmonics* in Dimension 2. **This pattern of FREQUENCY SUB-HARMONICS builds upward through the 15-Dimensional Scale. The 12th-Dimensional Frequency Band has a total of 144 Sub-Harmonics** - 12 Frequency Bands x 12 Sub-Frequency Bands each = *144 Sub-Harmonic Frequency Bands*. Because the 12th-Dimension holds within itself *all of the Frequency Spectra and scalar-grid programs* from the lower dimensions, the *12th-Dimensional Frequencies have the ability to "plug into" and override any Partiki Phasing flash-line pattern from the lower dimensional fields.* **The ORIGINAL PATTERN OF CREATION for the lower dimensional structure itself is held within the *12th-Dimensional Frequencies*, and so the 12th-Dimension *Sub-Harmonics* can be used to *correct any distortion* with the dimensional frequencies of the Lower Hova Bodies and their Shields.**

The Maharic Shield and the 12th-Dimension

As the Maharic Shield and Mahara Hova Body are composed of 10th, 11th and 12th-Dimensional scalar grids, they contain within them the **144 Frequency Sub-Harmonics** of the entire 12-Dimensional Spectrum. The human morphogenetic field is designed to hold the 144 Sub-Harmonic Spectrum, which is fulfilled through activation of the original **12-Strand DNA Silicate Matrix** gene code. Because of its 144 Sub-Harmonic scalar-wave spectrum, the 12th-Dimensional level of the **Maharic Shield** can **reset** the *original, non-distorted imprint of Partiki Phasing flash-line sequences* within the entire *Kathara Grid 12-Tree, the Kathara Centers, Kathara Lines, the Hova Bodies, DNA* and within any level of the morphogenetic field and manifest body built upon them. The *Maharic Shield* is the Kathara **RESET BUTTON.**

Frequency Sub-Harmonics in the 15-Dimensional Scale

Dimension (Primary SFB + Secondary SFBs)	Dimension x 12-SFB each =	# of Frequency Sub-Harmonics
Universal Morphogenetic Field: (cannot fully process through the human gene code for embodiment)		
Raja Hova Body-RISHIC SHIELD		
D-15 (12 + 168 =)	15 x 12 =	180 Frequency Sub-Harmonics
D-14 (12 + 156 =)	14 x 12 =	168 Frequency Sub-Harmonics
D-13 (12 + 144 =)	13 x 12 =	156 Frequency Sub-Harmonics
Human Morphogenetic Field: (can process through gene code via 12-Strand DNA Silicate Matrix)		
Mahara Hova Body- MAHARIC SHIELD		
D-12 (12 + 132 =)	**12 x 12 =**	**144** Frequency Sub-Harmonics
D-11 (12 + 120 =)	**11 x 12 =**	**132** Frequency Sub-Harmonics
D-10 (12 + 108 =)	**10 x 12 =**	**120** Frequency Sub-Harmonics
Betcha Hova Body- TEURIC SHIELD		
D-9 (12 + 96 =)	**9 x 12 =**	**108** Frequency Sub-Harmonics
D-8 (12 + 84 =)	**8 x 12 =**	**96** Frequency Sub-Harmonics
D-7 (12 + 72 =)	**7 x 12 =**	**84** Frequency Sub-Harmonics
Alphi Hova Body- DORADIC SHIELD		
D-6 (12 + 60 =)	**6 x 12 =**	**72** Frequency Sub-Harmonics
D-5 (12 + 48 =)	**5 x 12 =**	**60** Frequency Sub-Harmonics
D-4 (12 + 36 =)	**4 x 12 =**	**48** Frequency Sub-Harmonics
Nada Hova Body-TELLURIC SHIELD		
D-3 (12 + 24 =)	**3 x 12 =**	**36** Frequency Sub-Harmonics
D-2 (12 + 12 =)	**2 x 12 =**	**24** Frequency Sub-Harmonics
D-1 (12 + 0 =)	**1 x 12 =**	**12** Frequency Sub-Harmonics

REMEMBER: A FREQUENCY BAND is a *fixed, repeating sequence* of *Partiki Phasing Flash-lines* - "flashing on and off" cycles of scalar standing-wave points within the scalar-grid template, caused by the *fission/ expansion and fusion/ contraction of Partiki Units.* A SUB-FREQUENCY BAND is a *fixed, repeating sequence of Flash-lines* that is *part of* the full cycle of the *Frequency Band* Partiki Phasing sequence. A FREQUENCY SUB-HARMONIC represents a replica of Frequency Band Flash-line sequences from the dimensions below, carried within the Primary Flash-line sequences of the Dimensions above.

HIGHER DIMENSION = MORE FREQUENCY SUB-HARMONICS = FASTER FLASH RATES = HIGHER FREQUENCY = FASTER OSCILLATION/ SLOWER VIBRATION = SHORTER WAVE LENGTH = SLOWER ELECTRON SPIN = LESS PERCEIVABLE MATTER DENSITY

The Maharic Shield - Core of Healing Therapeutics

To restore the **Imprint for Health** within the *Body-Mind-Spirit System*, the **Holographic Template of scalar-grids** upon which the system manifests must be **restored to its original function.** *Topical applications* of healing modalities within the physical body, bio-chemistry, DNA, Auric Field, Chakra System, and Level-2: Crystal Seals and Level-3: Diodic Points of the Kathara Grid can create *temporary change* toward healing, but the **disharmonic conditions** held within the core **Level-1 12-Tree Kathara Grid** will eventually **override** alteration made to the outer levels of the morphogenetic field or body systems. **Working with outer levels of the Bio-system can *assist* in the healing process, but first the *Imprint for Health* must be restored within the *Level-1 12-Tree Kathara Grid*.** The *Level-1 12-Tree Grid*, with its *Kathara Centers* and *Kathara Lines* is created upon the **144 Frequency Sub-Harmonic** Pattern. As the **Maharic Shield** and Mahara Hova Body are the only portions of the dimensionalized scalar-grid anatomy that hold the full **12th-Dimensional Frequency Band** with its *144 Sub-Harmonics*, the **Maharic Shield** and its corresponding **10-11-12 Kathara Centers** are the *only portions of the morphogenetic anatomy that can override and restructure the electro-tonal scalar standing-wave point arrangements within Level-1 Kathara Grid.* **Thus it is with the *Maharic Shield* that core healing therapeutics must begin.**

Critical Mass and Simultaneous Healing of Core/ Outer Morphogenetic Levels

Activating the **Maharic Shield** will **open, activate and realign** the *scalar-wave flash-line sequences* of dormant *Kathara Centers, Kathara Lines, Crystal Seals, Hova Bodies, Diodic Points, Chakras* and *DNA* within the outer levels of the morphogenetic field and body. Once the **Imprint for Health** has been *temporarily restored* within the *Core Holographic Template Kathara Grid* via running the *Flash-line sequences* of the **Maharic Shield** through the *Level-1 Kathara Grid*, the *outer layers of the anatomy can be further realigned* to expedite manifestation of the Kathara Grid Repatterning into the outer levels of the Bio-system. **Technique # 2: The Maharic Seal and the Liquid Light Cleanse**, begin the process of running the 12th-Dimensional Flash-line sequences, via their Frequency Sub-harmonics, through the Kathara 12-Tree Grid to **REPATTERN** *distorted flash-line sequences* within the core Holographic Template. In the beginning of using this technique, the affects of this reprogramming will last only several hours, as the outer levels of the Bio-field will have greater "**Critical Mass**" in their distortion patterns, than the Kathara Grid can immediately override. **Full healing comes when the renewed Imprint for Health reaches CRITICAL MASS within the morphogenetic field.** Critical Mass is reached via *frequent use of the Maharic Seal* and *outer level Bio-field therapeutics*.

Kathara Healing Theory and Applied Methods

In Kathara Healing the first priority is to *reset the integrity* of the *Kathara Level-1; 12-Tree Grid* by Re-patterning its flash-line sequence program to the *Maharic Shield* via the *Maharic Seal and Liquid Light Cleanse*. This process sets the electro-tonal **"ground"** within which alterations of *outer morphogenetic levels* can connect, reawakening dormant **APPARTHI** *frequency receivers* within the *Level-2: Crystal Seals*, which allows the morphogenetic field levels to *expand* enough to hold the *higher frequencies* of the *Imprint for Health*. After the **Healing Ground** is set within the *Kathara Grid*, additional applications of Kathara Healing can then be applied to various other levels of the Kathara Grid, Morphogenetic Field and Body. **There is an infinite variety of Kathara Healing Bio-energetic applications**, that range from Levels 1, 2 and 3 Kathara Grid work, reprogramming the Kathara Centers, Kathara Lines, Hova Bodies, Shields and Signets, reversing the Miasmic/Karmic Imprint and accelerating the opening of the Diodic Points, to working with the Chakra System, Meridian and Axiom Lines, DNA and physical body points while running the Triadic Currents for healing. In coming Levels of the *Kathara Healing Program* we will learn the use of the **GEOMANCIES** and **FIRE LETTERS**- key **Symbol Codes** that serve as **scalar-wave guides** to reset the electro-tonal *flash-line sequences* within the morphogenetic body, and the application of the Symbol Codes to the treatment of specific physical, emotional, mental and spiritual dis-ease conditions. We will explore working with the **Color Cap Stones** of the Dimensional Frequency Bands and how they can be used in combination with the Symbol Codes for use in **Manifesting** desired conditions and **De-manifesting** undesirables, both within the body and in the 3-dimensional life drama.

Applications of the Level-1 Kathara Healing Program

In Program Level-1 we are setting the foundations upon which all the other skill levels of Kathara Healing are built. The focus of the Level-1Program is to create Morphogenetic Repatterning via the Maharic Shield, and to begin clearing the Miasmic/ Karmic Imprint that blocks various areas of the Hova Body Imprint. We will next learn to add **FORCE AND POWER** to our *Morphogenetic Recoding Process* by opening the **PLANETARY BIO-FEED INTERFACE SYSTEM™** to draw energy directly from the **Planetary Maharic Shield**, and we will begin learning of the *physical body massage point sequences*- **Sequence 1 and 2 Kathara Points** - through which we can begin to *regulate the flow of energy within the Bio-system* for **Regeneration** of the Imprint for Health and **Revitalization** of the Body-Mind-Spirit System. In **Section 2** of this course we will explore **MULTI-VECTOR HOLOGRAPHIC RECODING** - clearing the *Miasmic Imprint* from the Kathara Grid.

SEQUENCE 1 AND 2 KATHARA POINTS

Sequence-1 Kathara Points for REGENERATION

Sequence-1 Kathara Points are mini-energy-vortex points in the body that connect directly to **Diodic Points** within the *Kathara Level-3 Diodic Points Grid.* Stimulation of the Kathara Points affects the movement of energy within related areas of the Kathara Grid, which creates a reciprocal movement of energy within the cellular structure corresponding to the Kathara Points.

When used **in proper sequence,** *Sequence-1 Kathara Points* ***open energetic gate ways to the Kathara Lines*** of the Kathara Level-1 12-Tree Grid, allowing patterns of frequency to be entered into the Kathara Lines, to realign disharmonic patterns of frequency running through the Holographic Program of the Kathara Lines. When the Kathara Lines are opened to receive **11th** and **12th** dimensional frequency infusions from the **Mahara Hova Body,** the Holographic Program of the Kathara Grid can be progressively ***regenerated*** to the Imprint for Health, as held within the program of the Maharic Shield.

Sequence-1 Kathara Points are used to *open* the Kathara Lines prior to *Technique # 2: The Maharic Seal and the Liquid Light Cleanse* and *Technique # 4: The Maharic Infusion.* They **may also be used alone** with deep breathing, for frequent healing support, to draw energy up from the Maharic Shield, re-balancing and regenerating the Imprint for Health within the Kathara Grid and Body-Mind-Spirit System. It is not necessary to close the Kathara Lines after using Sequence-1 Points as they will **close automatically** in **several hours.** If one desires to further revitalize the cellular structure, running the *Sequence-2 Kathara Points* for *closing* the Kathara Lines will increase the amount of energy running through the *body cells,* as the Kathara Lines are no longer absorbing the energy.

Sequence-1 Points **regenerate and re-balance the *Kathara Core* first, which creates *more lasting but less immediate* changes in the body. *Sequence-2 Points* close the Kathara Lines if they are opened and draw energy from the Maharic Shield *directly into the bio-energetic field and physical cells,* rather than the core Kathara Grid, creating *more immediate, but temporary,* revitalization of the body.** The patterns held within the Kathara Grid- core holographic template will eventually override those set into the bio-energetic field alone. **Used in *combination* with each other the *Sequence-1 and Sequence-2 Kathara Points* can affect more lasting revitalization by *simultaneously realigning the core template and the outer layers* of the bio-energetic system and cellular structure.** In combination with other Kathara Healing techniques the affects and restoration of the Imprint for Health are further amplified and accelerated.

Sequence-2 Kathara Points for REVITALIZATION

Sequence-2 Kathara Points are mini-energy-vortex points in the body that, like *Sequence-1 Kathara Points*, connect directly to **Diodic Points** within the *Kathara Level-3 Diodic Points Grid.* Stimulation of the Kathara Points affects the movement of energy within related areas of the Kathara Grid, which creates a reciprocal movement of energy within the Bio-Field and cellular structure corresponding to the Kathara Points.

When used **in proper sequence,** *Sequence-2 Kathara Points* ***close the energetic gate-ways to the Kathara Lines*** of the Kathara Level-1 12-Tree Grid, which the *Sequence-1 Kathara Points* had opened. Closing of the Kathara Lines governed by the Sequence-1 Kathara Points, ***creates a reciprocal OPENING of Nadial Lines (Nadis*** energy rivulets that carry energy from the Nada Hova Body/ Nadial capsule, into the physically manifest systems**)** within the *outer levels* of the Bio-energetic Field. Opening of corresponding Nadis allows restorative patterns of frequency to be entered into the **outer levels** of the Bio-energetic Field and Chakra System, to realign disharmonic patterns of frequency running through the *Chakras, Auric Field and Physical Cells.* When the Nadis, Chakras and outer Bio-energetic Field are opened to receive 11th and 12th dimensional frequency infusions from the **Mahara Hova Body**, the energetic integrity of the physical cells and Bio-energetic Field can be progressively ***revitalized*** with Maharic frequency and the Imprint for Health, as held within the program of the Maharic Shield.

Sequence-2 Kathara Points are used to *close* the Kathara Lines following *Technique # 4: The Maharic Infusion.* They **may also be used alone** with deep breathing, for frequent healing support, to draw energy up from the Maharic Shield, through the Kathara Grid and into the **outer levels** of the Bio-energetic Field. Directing Maharic frequency into the outer levels of the Bio-energetic Field regenerates the Imprint for Health within, and directly **revitalizes** the *body cells* for accelerated Body-Mind-Spirit healing. If one desires to revitalize the cellular structure, running the *Sequence-2 Kathara Points* for closing the Kathara Lines will **increase the amount of energy running through the *body cells*,** as the Kathara Lines are no longer absorbing the energy. **Sequence-2 Points revitalize and rebalance the *outer levels of the Bio-energetic Field* first, which creates more immediate but temporary revitalization of the body, as restorative energies do not directly enter the Level-1 Kathara Grid.** To create *lasting change* when using the *Sequence-2 Points* alone, restorative electro-tonal programs must be **repeatedly** entered into the Bio-energetic field until the new programs reach **critical mass**, at which time the new programs will begin to *subtly influence* the programs held within the Kathara Grid. **The primary difference between Sequence-1 and Sequence-2 Kathara Points is this: *Sequence-1 Points*** channel energy from the Maharic Shield into the ***core Kathara Grid*** holographic template. ***Sequence-2 Points*** channel energy from the Maharic Shield into the ***outer levels** of the Bio-field and body cells*. **For this reason the affects of *Sequence-2 Kathara Points* are more *immediate*, and those of *Sequence-1 Kathara Points* are more *permanent*.**

The patterns held within the Kathara Grid core holographic template eventually override those set into the outer Bio-field alone. **Used in *combination* with each other and other healing applications the *Sequence-1 and Sequence-2 Kathara Points* can affect more lasting revitalization by simultaneously *realigning the core template and the outer layers* of the Bio-field and cellular structure.** Using ***Kathara Point Sequences*** in combination with each other and other Kathara Healing techniques will amplify and accelerate the affects and restorative function of the Imprint for Health within the Body-Mind-Spirit system.

14 SEQUENCE 1 KATHARA POINTS

Regeneration of the Imprint for Health

Sequence-1 Kathara Points **OPEN** energetic gate-ways with in the **Kathara Lines** of the *Kathara Level-1 12-Tree Grid*, to receive electro-tonal reprogramming for **regeneration** of the *Imprint for Health*. *Sequence-1 Points* are used to open the Kathara Lines **prior to** other energy-healing applications, to open the Kathara Grid so the regenerative patterns of other healing applications can "ground" within the Kathara. Sequence-1 Points re-generate and rebalance the **Kathara Core** first, creating **more lasting but less immediate changes** in the body.

1............CROWN
2 & 3.......TEMPLES
4.............BASE OF SKULL
5 & 6........BELOW SHOULDERS
7 & 8........ABDOMEN IN FROM HIPS
9 & 10......BACKS OF KNEES
11 & 12....SOLES AND TOPS OF FEET
13............4TH HEART CHAKRA
14............6TH THIRD EYE CHAKRA



Instructions: Breathe slowly and deeply. Imagine a flow of energy running from the **Maharic Shield** (12" below feet), up into the body through the **soles of the feet** and the **1st Chakra**. Gently **rub** the *Kathara Points* with fingertips for 10 – 20 seconds each, following the **precise sequence** described above.

14 Sequence-1 Kathara Points for Regeneration

LOCATION & APPLICATION SEQUENCE

1............CROWN

2 & 3.......TEMPLES

4.............BASE OF SKULL

5 & 6.........BELOW SHOULDERS

7 & 8.........ABDOMEN IN FROM HIPS

9 & 10......BACKS OF KNEES

11 & 12....SOLES AND TOPS OF FEET

13............4TH HEART CHAKRA

14............6TH THIRD EYE CHAKRA



Instructions: Breathe slowly and deeply. Imagine a flow of energy running from the **Maharic Shield** (12" below feet), up into the body through the **soles of the feet** and the **1st Chakra**. Gently **rub** the *Kathara Points* with fingertips for 10 – 20 seconds each, following the **precise sequence** described above.

6 SEQUENCE 2 KATHARA POINTS

Revitalization of the Imprint for Health

Sequence-2 Kathara Points **CLOSE** energetic gate-ways within the **Kathara Lines** of the *Kathara Level-1 12-Tree Grid*, to direct restorative frequencies into the **outer levels of the Bio-energetic Field** for **revitalization** of the *Imprint for Health* within the physical cells. *Sequence-2 Points* are used to close the Kathara Lines **following** use of the *Sequence-1 Kathara Points* or other energy-healing applications, to close the Kathara Grid so revitalizing frequencies can directly enter various *outer levels* of the Bio-energetic Field, such as the **Auric Levels, Chakras, Meridians, DNA** and **physical cells**. Sequence-2 Points revitalize and rebalance the **outer levels of the Bio-energetic Field** first, creating **more immediate but temporary changes** in the body.

1 & 2........NECK, BELOW EARS

3 & 4........BELOW CHEEKBONES

5..............BASE OF TAILBONE

6..............THYMUS

*** AMPLIFER –3RD SOLAR PLEXUS CHAKRA**



Instructions: Breathe slowly and deeply. Imagine a flow of energy running from the **Maharic Shield** (12" below feet), up into the body through the **soles of the feet** and the **1st Chakra**. Gently **rub** the *Kathara Points* with fingertips for 10 – 20 seconds each, following the **precise sequence** described above.

6 Sequence-2 Kathara Points for Revitalization

LOCATION & APPLICATION SEQUENCE



1 & 2........NECK, BELOW EARS

3 & 4........BELOW CHEEKBONES

5..............BASE OF TAILBONE
(one point on each side at base of tailbone)

6..............THYMUS

*** AMPLIFER –3RD SOLAR PLEXUS CHAKRA**

Instructions: Breathe slowly and deeply. Imagine a flow of energy running from the **Maharic Shield** (12" below feet), up into the body through the **soles of the feet** and the **1st Chakra**. Gently **rub** the *Kathara Points* with fingertips for 10 – 20 seconds each, following the **precise sequence** described above.

TECHNIQUE # 2

THE *MAHARIC SEAL* AND THE *LIQUID LIGHT CLEANSE*

1. Close your eyes and visualize the image of a flat (2-dimensional line drawing) 6-Pointed Star of David (**The Merkaba Star**) made of **White Light**, stationed at the **6th-Chakra** on the *inside of the Forehead.* (If you cannot yet generate inner visualizations, simply imagine that the symbol is there.) Continue to visualize or imagine, and move the **White Merkaba Star** image over toward the **left** in your inner field of vision. In the *center* of your inner field of vision, visualize/ imagine the image of *another Merkaba Star*, made of a **Dark Silver Light**. Observe or imagine the **2 Merkaba Stars** in your inner field of vision and then slowly *move the images toward each other* until they have merged into *one Merkaba Star* Symbol made **of Pale Silver Light**. (The *Pale Silver Double Merkaba Star Symbol* is called the **HIEROPHANT** – it is the scalar wave template that governs the release of phase-lock on the *Maharic Shield.)*

2. Visualize/ imagine the Hierophant Symbol clearly in mind, then shift attention to the sound of your breath. Take several slow, deep breaths. On the next **EXHALE** use the force of breath to *forcefully push* the **Hierophant** down from its position at the 6th-Chakra, through the *Central Body Current* and into the **Earth's Core.** Take a few more slow breaths while visualizing/ imagining the Hierophant Symbol in the center of the Earth's core. Imagine now that the *Hierophant begins to spin in the Earth's core*, the Dark Silver Merkaba Star and the White Merkaba Star spinning in *opposite directions.* Spin the Hierophant progressively faster until it "takes on a .life of its own", and suddenly "pops and expands" to form a **Pale Silver Sphere of Light** *spinning in the Earth's core.*

3. Observe the Pale Silver Hierophant Sphere spinning in Earth's core, then visualize/ imagine that a **huge, horizontal Pale Silver spinning disc** emerges out from the Hierophant Sphere, forming a **massive Pale Silver Disc of Light** *spinning throughout the Earth and extending outward into the atmosphere* as a **rotating, horizontal plane.**

This horizontal disc-plane extending through the Earth represents the *Mahara Hova Body*, or **Maharic Shield** of the planetary morphogenetic field – the Pre-matter Liquid Light scalar grid composed of frequency from dimensions 10, 11 and 12. (Known as the ***Shield of Amaratena***). Using the Hierophant wave template you have now activated the planetary Maharic Shield, *opening the **Planetary Bio-feed Interface System™** into your bio-energetic field.* This constitutes opening your personal Kathara Grid and morphogenetic field into the Planetary Kathara Grid and morphogenetic field, allowing you to draw an *unlimited supply of energy* from the planetary field. You can draw in only as much as your personal morphogenetic field can hold. With repetition of this practice the energy-holding capacity of your Kathara Grid progressively increases, allowing you *a continually expanding supply of energy* for healing and revitalization.

TECHNIQUE # 2: Continued
THE *MAHARIC SEAL* AND THE *LIQUID LIGHT CLEANSE*

4. While remaining aware of the *Planetary Maharic Shield* spinning on a horizontal plane throughout the Earth's body, return the focus of your attention to the spinning **Silver Hierophant Sphere** rotating at Earth's core. (You will now use the Hierophant Sphere to activate your **personal Maharic Shield** and release the 12th-Dimensional Pillar of Light within your bio-energetic field.). Take several slow, deep breaths, while visualizing/imagining the Hierophant Sphere spinning in Earth's core. On the next **INHALE**, draw the Hierophant Sphere *up from Earth's core* with the inhale breath, forming a **Pale Silver Cord** *about 6" thick* trailing behind the Hierophant as it rises to the **12th Chakra**, 6" beneath the feet. *One end of the Silver Cord remains rooted in* ***Earth's core****, the other end is attached to the* ***Hierophant Sphere*** *and follows its movement.* Visualize the **12th Chakra** as a small, **transparent disc** about *3" in diameter*, positioned *6" below the feet*. Stop the movement of the Hierophant in the *center of the 12th Chakra*, imagine the Sphere beginning to spin and *visualize the diameter of the 12th Chakra disc expanding to about 6" in diameter*, as the Hierophant spins at its center. Take a few slow, deep breaths as the *Hierophant spins in the center of the* ***12th Chakra.***

5. On the next **INHALE** draw the Heirophant Sphere *up from the 12th Chakra*, through the **Central Body Current** and up to the **14th Chakra** *36" above the head*. As the Hierophant Sphere rises, visualize the *6" thick* **Silver Cord** drawing up through the **12th Chakra** and farther up through the **Central Body Current,** following the path of the Hierophant Sphere to the **14th Chakra**. Visualize the Silver Cord as a long, thick **Pale Silver Cord of Light**, running from the *Earth's core, through your body and out the top of your head*, connecting to the **14th Chakra** 36" above the head. Take several deep, slow breaths while imagining that you can *feel the sensation* of this *massive current of clear, pure energy* running through the *center* of your body.

6. On the next **EXHALE**, push the spinning Hierophant Sphere *down* through the **Central Body Current,** while leaving the *top end* of the Pale Silver Cord attached to the **14th Chakra** 36" above the head. Move the Hierophant down through the **12th Chakra** 6" below the feet, and **stop the Hierophant** *6" below the 12th Chakra;* a position about **12" below the feet**. This is the location of the **Maharic Shield** within the morphogenetic field of the body. Breath slowly and visualize the Hierophant *spinning progressively faster* 12" beneath the feet, until the Hierophant "takes on a life of its own" and suddenly "*pops and expands*" to form an **expanding horizontal disc of Pale Silver Light spinning 12" beneath the feet.** ***Feel the disc as a circular platform 3 yards in diameter below feet.***

TECHNIQUE # 2: Continued
THE *MAHARIC SEAL* AND THE *LIQUID LIGHT CLEANSE*

7. Call to mind the image of the *massive horizontal disc of Pale Silver Light* spinning through the Earth's body – the **Planetary Maharic Shield**. Imagine the sensation of the large, spinning *Pale Silver platform disc* spinning 12" beneath your feet – your **personal Maharic Shield**. Breathe slowly and deeply while visualizing/imagining a *massive rush of pure, cool* ***Pale Silver energy*** running from the *planetary Maharic Shield*, up through the **Pale Silver Cord** and into the *personal Maharic Shield* 12" beneath your feet. Breath as this energy runs, *filling your Maharic Shield to its energy-holding capacity*. When your Maharic Shield has received as much Pale Silver energy as it can hold, it will "take on a life of its own", and suddenly "*pop and expand*" upward into an ***oscillating Pale Silver Pillar of Light*** *surrounding and permeating the body*, a *tube of light* extending beyond the body *about 18"*, and running from the **Earth's Core** to the **14th Chakra** 36" above the head. *Feel the reality of your body encased in the cool, refreshing Pale Silver Pillar of oscillating light.* Take a few slow deep breaths and imagine the energy from the Pillar *emanating through all of your body cells.* Your Bio-energetic Field is now sealed with a protective barrier of 11th/12th-Dimensional frequency – the **Maharic Seal**.

8. As the Pale Silver Pillar of Light oscillates around you, place your attention for a moment at the **13th Chakra** in Earth's core and **INHALE** a final **Spark** of *Pale Silver Light* from Earth's core, drawing the Spark up through the **Pale Silver Cord**, into the **Main Vertical Channel of the Kathara Grid**, and into the center of the **4th Heart Chakra**. Breath slowly and easily while visualizing energy from the *Silver Spark* radiating throughout the embodied **12-Tree Kathara Grid**, *filling it with Pale Silver Light.* When the Kathara Grid has reached its energy-holding capacity, the ***12th Chakra*** *will automatically contract* to decrease the flow of Silver Light from the Earth's core. As the 12th Chakra contracts, the *Planetary Maharic Shield* stops spinning and transmitting energy through the Silver Cord, returning the Silver Chord to its dormant state. The ***Maharic Seal*** **Pale Silver Pillar of Light** will remain in your bio-energetic field between **1-3 hours**. Over a *3-month period* of frequent, consistent *daily practice* of this process, the Maharic Seal will self-sustain in the bio-energetic field for **12-14 hours**.

Use of this technique allows a healing Facilitator to activate the **Maharic Shield** and **Seal** in others, through the ***Maharic Infusion process*** (Technique # 4), while Facilitator's Pillar remains active. Progressive use of the Maharic Seal and running the Liquid Light creates a reciprocal clearing, reordering and realignment of the Kathara Grid-***Holographic Template*** – and all subtle energy and physical systems built upon it. The Lower Hova Bodies are progressively cleared and realigned with the ***original perfection of the Pre-matter Liquid Light Mahara Hova Body***, and the body and genetic code progressively expand to hold higher dimensions of conscious awareness.

TECHNIQUE # 2B: THE MAHARIC QUICK SEAL

1. Work with a 24 pointed, 3 Dimensional Star (Heirophant) and be aware that you will be working with beings known as the Breneau Rishi ...

2 Begin by slowing your breathing , as you imagine or visualize a 24 point, 3 -Dimensional, Heirophant at the Pineal Gland in the center of your brain. Visualise the Heirophant surrounded by a Pale Blue Sphere of Light.

(The Blue Sphere serves as a buffer for your readiness to accept the frequencies associated with using the 24 pointed Star; the Blue Sphere holds the energy for you until your body can handle the energy. If you can handle it, the energy will simply pass through the blue sphere).

3 INHALE, as if you are going to grab the blue sphere containing the 24 point star located at the Pineal, and on the EXHALE move the 24 point star/ blue sphere, all the way down to Earth's Core. Try to hear a sound tone as the Heirophant/ Sphere hits the Planetary Shield ...

4 INHALE and draw the Heirophant/ sphere up to your Personal Maharic Shield 12" below your feet ... and EXHALE while watching the Pale Silver-Blue sphere expand out to a large sphere ... and watch as your Maharic Shield pop out as a disc, about 4' in diameter, Pale Silver with a light coating of Pale Blue.

5 Bring your attention to the center of your Maharic Shield 12" below your feet ... and INHALE the 24 point Star (only) up into the Heart Chakra. EXHALE, expanding the frequencies of the 24 point Star into the Heart Chakra.

6 INHALE to grab the 24 point Star, and EXHALE, pushing the Star up into the 14th Chakra 36" above the head. Imagine that the 24 point Star is spinning in a clockwise direction in the 14th Chakra. As you do this, try to feel/ sense the energy around you, just a few inches out from your body ...

7 Now, put your attention into your Maharic Shield 12" below your feet, take a couple of relaxing breaths and INHALE deeply pulling the Pale Silver and Blue energy up, as if you are pulling on your Maharic Seal to latch it on to your 14th Chakra. Try and feel the sensations just a few inches from your body now – feel the difference if you can. This procedure gives you a Quick Seal.

8 Now envision the cord of Pale Silver Maharic Light that would normally come up with your Shield and focus on the Earth's Core. Begin drawing energy all the way up the 4" diameter cord and into the body. INHALE the energy up into the Heart Center, and expand it there. Begin to form a pale Silver ball of Maharic frequency.

On each EXHALE send your energy down to the Earth's Core to bring up another load of Maharic frequency, up from the Planetary Shields, expand it into the Heart center and repeat several times. Notice that the Cord grows larger as you do this, expanding from approximately 4" to 6 to 8" diameter, until finally it feels like a skin around (as well as within) your body ... as you load your Astral field with Maharic Frequency.

9 Move your attention to the Pale Silver ball you have created in your Heart Center, INHALE and move it up to the 14th Chakra 36" above your head .. as you do, feel for the sheath of Maharic Frequency encasing your etheric body, close to your skin. (This Maharic/ Christos skin charges, and saturates, your etheric body – feel the peacefulness and all-knowing nature of this frequency).

SYMBOL SHORTHAND

TECHNIQUE # 2: Condensed Version
The Maharic Seal and Liquid Light Cleanse

Symbol Shorthand is used to help in remembering the primary steps of a technique

1. *Silver Hierophant Star at Chakra 6*
2. *EXHALE* Hierophant Star from *Chakra 6 to Earth's Core –Spin Hierophant Star* at Earth's core-until it *pops* into *Hierophant Silver Sphere at Earth's core.*
3. *Hierophant Sphere* spins *at Earth's core* until *Silver Disc of Earth's Shield* emerges.
4. *INHALE- Hierophant Sphere* up from *Earth's core to Chakra 12* trailing *Silver Cord* from Core.
5. *INHALE- Hierophant Sphere* up from *Chakra 12 to Chakra 14*, trailing *Silver Cord.*
6. *EXHALE- Hierophant Sphere* down from *Chakra 14 to Personal Maharic Shield* and *spin Hierophant Sphere* until *Personal Shield pops* out to become *Silver disc* plane 12"beneath feet.
7. Draw *Silver energy* into *Personal Shield from Earth's Shield* through *Silver Cord,* until *Personal Shield* is *filled* and *pops* to become vertical *Pillar* of Silver Light around body.
8. *INHALE*-draw *Spark of Silver Light* from *13th Chakra* at *Earth's Core,* into *main* vertical channel of *Kathara Grid* then to *Chakra 4;* from Chakra 4 transmit energy from Spark to fill *12-Tree* Kathara Grid. Chakra 12 auto-shut down when 12-Tree Grid is full.

THE MAHARIC SEAL


HIEROPHANT
THE HIEROPHANT SYMBOL CODE
PALE SILVER
11TH – 12TH Dimensional Frequency
PURE WHITE
12TH Dimensional Frequency
DARK SILVER
11TH Dimensional Frequency
Scalar Wave Guide
The 11th-12th-Dimensional Scalar Standing-wave Guide for activating the Maharic Shield and the PBIS.
Hierophant Symbol Code
CHAKRA-14
14
B
C
A
HIEROPHANT SYMBOL CODE
PINEAL GLAND
A
4
CHAKRA-4
CENTRAL VERTICAL CURRENT
SILVER CORD
MAHARIC SEAL
12TH-Dimensional Hydroplasmic Ante-matter "Flame" Scalar-wave Pillar that manifests in the bio-energetic field with activation of the Maharic Shield
CHAKRA-12
12
12"
B
C
A
PERSONAL MAHARIC SHIELD
CHAKRA-13
PLANETARY MAHARIC SHIELD

Visualize the Hierophant Symbol Code as a *2-dimensional "flat" image* "drawn in Pale Silver Light".

Follow with Liquid Light Cleanse

LIQUID LIGHT CLEANSE

KATHARA CENTERS

#12 – *The Capstone*
In 10th Chakra
6" above the head

# 11 – *Crown Jewel*
In Pineal Gland
at center of brain

# 9 & # 10 –*The Shar*
In brain
behind ears

# 8 – *Spark of Orion*
In Thyroid Gland
at 8th Chakra

# 6 & # 7-*The Wings*
In shoulder indents
through to back.

# 5 –*Seat of Amenti*
At Navel in
Central Body Current

# 3 & # 4 -*The Dal*
male: Ureters
female: Ovaries

# 2 – *Naum-Yun*
male: Prostate Gland
female: Vagina

# 1 – *Earth Core*
at center of Earth
in 13th Chakra


12
11
9
10
8
6
7
CHAKRA-4
5
3
4
2
12"
1
PLANETARY MAHARIC SHIELD

Central Vertical Kathara Line
controls all other Kathara Lines. Kathara Centers on *Central Vertical Kathara Line* control all other Kathara Centers.


12
11
9
10
8
3-6-9 Vertical Kathara Line
corresponds to Right side of body.
4-7-10 Vertical Kathara Line
corresponds to Left side of body
Kathara Lines
6
7
Kathara Centers
5
3
4
2
1

Liquid Light Cleanse

After activating the Maharic Seal **INHALE a Spark of Silver Light** up from Earth's core to **Central Kathara Line,** then to **4th Chakra.** From **4th Chakra** project **Maharic energy** through entire **Kathara Grid.**

The Planetary Bio-Feed Interface System and the Maharic Seal

Use of the *Maharic Seal and Liquid Light Cleanse* begins the process of activating the **8th through 12th Chakras** and opening the natural **PLANETARY BIO-FEED INTERFACE SYSTEM (PBIS)** within the human body. Through the **PBIS,** the finite quantity of scalar frequency of which the personal Maharic Shield, Hova Bodies and individual identity are composed expands to **infinite potential,** as the **Planetary Scalar Shields** can be used to open dormant **Crystal Seals** within the Scalar Shields of the personal Level-2 Kathara Grid. **Once activated through the 12th Chakra, the PBIS opens a conduit of perpetual energetic supply between the human body and the planetary Morphogenetic Field, allowing the body to continually draw in as much higher dimensional frequency as the DNA Template can hold.**

With the PBIS activated, the human body can also become a tool for reprogramming and re- balancing the Planetary Shields, Vortices, Ley Lines and energetic grids of the Planetary Templar Complex. When the Crystal Seals of the personal Shields are released, the **human DNA Template** can serve as a **bio-electric conduit** for running higher dimensional frequency into the **Planetary Shields.** The human body, with its **12-Strand DNA Template potential,** is the only mechanism on Earth, other than the Planetary Shields themselves, that is capable of running a full 12th-Dimensional **Maharic Current.** Just as within the human Manifestation Template, the Maharic Current can be used to purge distortions within the Planetary Shields, to restore the **Planetary Templar Complex** to its original **Primal Order.** Kathara Healing technologies not only provide the opportunity for individuals to facilitate healing in other *biological life forms*, they also reawaken the human potential to facilitate healing within the **geophysical planetary body.**

The Planetary Bio-Feed Interface System


The human DNA can serve as a Bio-electric Conduit for running inter-dimensional energy current into the Planetary Shields
EARTH
LINK AT EARTH'S CORE
CREATING THE PBIS -
PERSONAL KATHARA GRID
6
7
5
3
4
2
1
PLANETARY KATHARA GRID

The Maharic Seal and Client Sessions

Through understanding the **Context of Healing**- *The Structure of the Unified Field,* the **Elements of Healing –** *The Anatomy of the Human Body Kathara Grid* and **Kathara Healing Beginning Applications -** *Morphogenetic Repatterning* through the ***Maharic Seal and Liquid Light Cleanse*** and *Awakening the Mentor* for access to 5th Dimensional awareness, the Kathara Healing Facilitator has developed the rudimentary skills necessary to begin **personal Core Holographic Template Healing. To effectively facilitate Core Template healing in others it is important for Kathara facilitators themselves to employ personal Template Healing.**

The ability to hold the **12th-Dimensional Maharic frequency sub-harmonics** (the 12th-sub-frequency band within each of the full Dimensional Frequency Bands) in body to assist in its transmission to a client for healing support increases as the facilitator utilizes the **Maharic Seal and Liquid Light Cleanse** technique **for personal healing.** The *Maharic Seal and Liquid Light Cleanse* technique not only increases the facilitator's ability to transmit 12th-Dimensional frequency sub-harmonics, it also temporarily **realigns distortions** within the *facilitator's* bio-energetic field and Kathara Grid and creates a temporary **12th-Dimensional Scalar Frequency Seal** within the *facilitator's* bio-energetic field. **Without use of the *Maharic Seal,* the facilitator will inadvertently transmit bio-energetic field and Kathara Grid distortions to the client and will energetically pick up scalar distortions** (including part of the "Karmic" Miasmic Imprint) **from the client.** (This problem occurs in all subtle-energy healing modalities that do not employ the Maharic Seal). Both of these conditions serve to amplify, rather than remedy, dis-ease and disharmony within the Mind-Body-Spirit system, for both *facilitator and client.* For these reasons, **the *Maharic Seal and Liquid Light Cleanse* technique needs to be employed prior to ANY healing facilitation work,** to protect the **bio-energetic field integrity** of facilitator and client. **The *Maharic Seal and Liquid Light Cleanse* technique represents the facilitator's preliminary preparation prior to Kathara Healing Facilitation Client Sessions.**

Safety in Healing Facilitation!



The ***Maharic Seal and Liquid Light Cleanse*** technique, used as facilitator preparation prior to **Client Sessions,** protects facilitator and client from taking on bio-energetic field distortions from each other. **Maharic Seal** is the preliminary step before any **Kathara Healing** application and is needed to effectively run interdimensional healing currents.

CO-GENERATIVE HEALING

The final phase of education necessary before engaging the adventure of **Kathara Healing Client Facilitation** is rediscovering the structure of personal **Multi-dimensional Identity** and how to use the personal **Hova Bodies** to tap the higher dimensional scalar frequencies for enhanced healing facilitation ability. The ability to understand and utilize the **PRECISE HEALING CURRENTS** of the interdimensional spectrum adds **greater power and skill** to the healing facilitation process. Unlike many other energy healing systems, **Level-1 Kathara Healing** trains the facilitator to identify, awaken within the body and employ in client service **specific combinations of interdimensional healing current** that fine-tune and amplify the beneficial effects of subtle energy healing. This chapter will conclude with an overview of the **4 PRIMARY TRIADIC HEALING CURRENTS,** 4 of the 5 **3-Dimensional Primal Energy Currents** that can be awakened within the body through activation of the **Maharic Shield.**

The natural **Primal Triadic Healing Currents,** which exist naturally as part of the personal Hova Body, Scalar Shield and Kathara Grid anatomy, create powerful, effective and user-friendly energetic healing tools when combined with the 12th-Dimensional frequencies of the **Maharic Shield.** Running the Triadic Currents is achieved by using the current to first activate the frequencies of the corresponding Hova Body and station of awareness within the personal Scalar Shields and **DNA Template.** Once activated in the DNA Template, the **Hova Body** is used to draw perpetual supply of the desired current from the Dimensional Unified Field corresponding to the chosen current. **Running the Triadic Currents requires activation of the corresponding frequencies within the facilitator's DNA Template, thus using the Triadic Currents in Client facilitation also serves to progressively stimulate and expedite activation of dormant frequencies in the facilitator's DNA Template.** Using the Triadic Currents in client facilitation serves to accelerate the processes of Holographic Recoding, higher identity Hova Body integration and multi-dimensional evolution within the Body-Mind-Spirit system of the *facilitator,* as well as that of the *client,* creating a condition of **CO-GENERATIVE HEALING** between client and facilitator.

Healing, Evolution and Ascension

In the Kathara Healing paradigm the art and science of healing the Body-Mind-Spirit system is viewed in terms of the *human relationship to the natural structure and dynamics of creation.* **Healing becomes a necessity when the intrinsic energetic systems and scalar-wave constructions of consciousness upon which the biological manifestation is built become incongruent with the natural Primal Order of the dimensionalized Time Matrix system.** The processes of natural healing and the hidden, organic functions of **human evolution** are intimately intertwined. Conditions that facilitate natural healing also facilitate fulfillment of the naturally intended course of human evolution, while conditions detrimental to Body-Mind-Spirit health are likewise detrimental to the evolutionary objectives of both the individual and the species.

The processes by which lasting healing occurs through re-genesis of Primal Order within the Scalar Shields and personal anatomy, are the same processes by which the **CONSCIOUSNESS** evolves to the fulfillment of **Spiritual Actualization**, through embodiment of the 12-dimensions of consciousness inherent to human DNA Template design. The genetic code of the biological imprint is built upon the Scalar-wave Templates of Consciousness that serve to hold the identity as energetic substance into physical embodiment. **Distortions within the physical manifestation indicate distortions in the Manifestation Template and thus constitute distortions in CONSCIOUSNESS.** Genuine healing is a *FUNCTION OF CONSCIOUSNESS*, first and foremost, and it is through realignment of consciousness itself that full healing can occur.

In the Kathara program it is understood that biology and consciousness are intimately intertwined and thus interdependent. The techniques of **Bio-Regenesis** provided in Kathara Healing assist in the processes of restoring the **Organic Imprint for Health** while simultaneously serving to **expedite the natural processes of interdimensional evolution** through DNA Template, Kundalini, Crystal Seals and Merkaba activation. **Human evolution is not a random, goal-less occurrence; it is rather an ordered system of interdimensional physics dynamics by which human consciousness progressively masters the contours of creation in time.** The evolutionary objective of human creation is **mastery,** which is progressively attained through the dynamics of **Transmutational Dimensional Ascension. Ascension** is therefore the intrinsic and indelible **goal** within human evolution, the **hidden impetus for action** that moves the human species forward in time.

Healing and Bio-Spiritual Evolution

When we begin running the higher dimensional frequencies of the **4 Primary Triadic Currents** for Kathara Healing applications, we are, in truth, running **FREQUENCIES OF CONSCIOUSNESS**, that emanate from the **Hova Bodies** in which the expanded spiritual portions of our personal identity are stationed. As we reawaken the higher dimensional frequencies of consciousness within the **DNA Template** we are progressively expediting the reintegration of personal **Multi-dimensional Identity**, serving the **spiritual goal of Ascension** through stimulating into activation the scientific dynamics of **Unified Field Physics** by which genuine Ascension occurs. **Kathara Healing** progressively restores the functions of universal physics dynamics within the human body, as they apply to the pathway of Ascension, and so Kathara Healing applications are considered to be processes of **ACCELERATED BIO-SPIRITUAL EVOLUTION**, as well as processes of holistic Body-Mind-Spirit healing. Both facilitator and client simultaneously receive the subtle but progressive benefits of evolutionary acceleration and spiritual development through Kathara Healing **Bio-Regenesis Technologies**, through which the expansion of personal consciousness into the higher dimensional aspects of spiritual awareness occurs.

Kathara practices serve to stimulate progressive integration and embodiment of the Multi-dimensional Identity by activation of dormant portions of the **DNA Template** through which the scalar-wave patterns of the higher frequencies of identity can enter the physical form. As spiritual advancement through Hova Body integration and DNA Template activation is a beneficial "side effect" of Kathara Healing practice, it is helpful for the Kathara facilitator to understand the order of **Multi-dimensional Identity Structure**. It is also helpful to realize that the **Unified Field of Energy** utilized in Kathara Healing is, in fact, a **UNIFIED FIELD OF CONSCIOUSNESS.** Healing is a function of energy dynamics and at its core, energy is the **substance consciousness adopts** to experience manifestation, thus **HEALING IS A FUNCTION OF CONSCIOUSNESS.** When personal consciousness is applied in ways that are congruent with the natural **Laws of Unified Field Physics**, the effects of healing and wellbeing are met in manifestation.

MULTI-DIMENSIONAL IDENTITY STRUCTURE

Consciousness and the Physical Illusion

In Chapter 1 we explored the **Structure of the Unified Field** and discovered the morphogenetic framework, or **Holographic Template** upon which matter systems are constructed. We learned how the structure of dimensionalization applies to the anatomy of the **15-Dimensional Human body**, from the **Core Template Kathara Grid**, the **Hova Bodies and Shields**, to the **Chakras**, **Bio-energetic Field** and **physical matter** structures built upon them. **We also discovered that *physical manifestation* is not what appears to be - that *nothing is really manifest at all*, but only *appears to be so* due to the *relationships of compartmentalized consciousness interacting with each other through the framework of dimensionalization*.** Our physical parts and our manifest world are **scalar wave constructions**, appearing solid and externalized because we view them with a level of consciousness that is stationed **one full dimension above** the wave forms we perceive as solid and objectified. Our consciousness structures itself into the scalar wave forms of dimensionality in order for us to perceive the illusion of manifestation. There is no difference, other than the **dimensional frequencies from which one is perceiving,** between the *substance that composes physical matter* and that which *composes our seemingly non-manifest portions of consciousness*. **The core of reality is CONSCIOUSNESS - it is the *energetic substance* out of which all things are made.**

Hova Bodies- Platforms of Perception

In this Section we will learn how the attributes of mind and sentient identity fit into the multidimensional anatomy of human consciousness. The scalar grids of the **Hova Bodies** and **Shields** that hold portions of our consciousness separate from each other so we may experience objectification, can be understood as **PLATFORMS OF PERCEPTION.** A portion of our conscious identity is **stationed within each of the Hova Body Shields**, and the dimensions contained within the Shield become the *platform* from which *that portion of our selves* will perceive matter objectification. **We are simultaneously focused within each Hova Body Platform of Perception, and this gives us separated but interrelated stations of identity and different LEVELS OF MIND from which we simultaneously perceive.** The amount of perception we are able to incorporate into our embodied focus on Earth is determined by the Level of **Higher Identity Integration** that has occurred. Integration of Higher Identity is the *merger* of the **Hova Bodies**, which creates changes and advancement in the **biological gene code** that allows the neurological and metabolic functions of the body to expand.



THE 5 HOVA BODIES

3-Dimensional Electro-magnetic Domains created by the Scalar Shields that serve as stations of dimensionalized consciousness

1. **NADA HOVA** Density-1
2. **ALPHI HOVA** Density-2
3. **BETCHA HOVA** Density-3
4. **MAHARA HOVA** Density-4
5. **RAJA HOVA** Density-5

Our Present Platform of Perception

Presently we are accustomed to perceiving from the Platform of Perception provided by the **NADA HOVA BODY**, the *scalar grid* that houses the 1st, 2nd and 3rd Dimensional Aspects of our identity and anatomy. While perceiving from the Nada Hova Body and the **TELLURIC SHIELD** that holds its form, we are functioning as a **3-Dimensional consciousness** and will not be aware of the perceptions of the other levels of ourselves that are perceiving from the *Platforms of Perception* from the other Hova Bodies. **As we expand and evolve we will progressively incorporate the portions of our awareness stationed in the other Hova Bodies into our earthly focus of attention.**

The *Higher Identity Structure* of the Hova Bodies and related *Levels of Mind* within dimensionalization are as follows:

Stations of Identity and Levels of Mind in the Hova Bodies

INCARNATE IDENTITY: Nada Hova Body/ Telluric Shield / dimensions 1, 2 and 3. The Subconscious (D-1), Instinctual (D-2) and Reasoning (D-3) Levels of Mind

SOUL IDENTITY: Alphi Hova Body/ Doradic Shield/ Dimensions 4, 5 and 6 The Astral (D-4), Archetype or Dora (D-5) and the Angelic (D-6) Levels of Mind

OVER-SOUL IDENTITY: Betcha Hova Body/ Teuric Shield/ Dimensions 7, 8 and 9 The Ketheric (D-7), Monadic or Teura (D-8) and the Keriatic (D-9) Levels of Mind

AVATAR IDENTITY: Mahara Hova Body/ Maharic Shield/ Dimensions 10, 11 and 12 The Christiac (D-10), Buddhiac (D-11) and the Nirvanic (D-12) Levels of Mind.

RISHI IDENTITY: Raja Hova Body/ Rishic Shield/ Dimensions 13, 14 and 15 Universal Consciousness Mind

There are 3 **additional Platforms of Perception** and 3 additional Hova Bodies beyond the structure of Dimensions;Hova Bodies that represent 3 Levels of **Ascended Mastery Identity**.

Spiritual Actualization is the process of progressive Higher Dimensional Identity Integration. ***Higher Identity Integration*** is the merger of the ***Hova Bodies***, which creates changes and advancement in the biological ***Genetic Code*** through progressive activation of dormant portions of the ***Silicate Matrix 12-Strand DNA Template.***

5 Hova Bodies and Levels of Identity in the 15-Dimensional Time Matrix



The 5 Hova Bodies of personal anatomy hold Gestalts of Consciousness through which multiple singular Incarnate identities *simultaneously* manifest in the Time Matrix.

5 HARMONIC UNIVERSES
In one 15-Dimensional TIME MATRIX

Magnetic Repulsion Zones create separation between Harmonic Universes, and Hova Bodies, Shields and levels of the Auric Field.

3 Levels of the non-dimensionalized **ENERGY MATRIX** within which **TIME MATRICES** reside. Station of the 3 **Ascended Mastery** levels of identity and Hova Bodies.

HU-5
RISHI
D15
D14
D13
HU-4
AVATAR
D12
D11
D10
D9
HU-3
OVERSOUL
D8
D7
D6
D5
D4
HU-2
SOUL
D3
D2
D1
HU-1
INCARNATE
TRIADIC LEVEL
POLARIC LEVEL
ECKATIC LEVEL

THE 4 PRIMARY TRIADIC HEALING CURRENTS

Hova Bodies and the 4 Primary Triadic Currents

Each of the Hova Bodies and Shields contains a portion of your energy-identity that exists in the form of electro-tonal impulse born of Partiki Phasing. The energy of **your higher stations of identity and that of the Universal Unified Fields of Consciousness-Energy can be drawn into the Nada Hova body and earthly incarnate identity for the purpose of healing facilitation.** There are **four Primary Triadic Healing Currents,** each corresponding to one of the **four higher dimensional Hova Bodies.** Through *your* corresponding Hova Body station you can *draw energy from the higher dimensional Unified Fields* and channel it into your Nada Hova Body for direction into healing within the first Harmonic. **The *4 Primary Healing Currents* are HARMONIC CURRENTS OF ENERGY, each composed of *3 Dimensions of Frequency.*** Each Dimensional Band within a Harmonic or **TRIADIC** current is referred to as a **PHASE** *of that current.* **In Kathara Healing we develop the ability to activate each progressive PHASE of each TRIADIC CURRENT, through grounding the current into the body via the activated MAHARIC SHIELD.**

Triadic Currents and Color

Each *Phase* of Triadic Current corresponds to a wave length in the dimensional spectrum that appears as COLOR to the embodied human mind. In directing the **Triadic Currents** we therefore use the **color translation of the primary dimension wave spectra** to differentiate between Phases of current for various applications. **The first current to be activated in Kathara Healing is the that of the DORADIC CURRENT,** the frequencies drawn in from Harmonic 2 through the **Doradic Shield and Alphi Hova Body. The Doradic Current has 3 Phases: Phase -1: 4th Dimensional current/ GREEN wave, Phase-2: 5th - Dimensional Current/ BLUE wave and Phase -3: 6th-Dimensional current/ Blue-Violet wave.** In **Level-1 Kathara Healing** we learn to activate and run the **Phase-1 Green Doradic Current.**

The 4 Primary Triadic Currents and Hova Body Correspondences

TELLURIC CURRENT: Nada Hova Body/ Telluric Shield / Dimensions 1, 2 and 3.
Phase-1 RED, Phase-2 ORANGE-GOLD , Phase-3 YELLOW

DORADIC CURRENT: Alphi Hova Body/ Doradic Shield/ Dimensions 4, 5 and 6
Phase-1 GREEN, Phase-2 BLUE, Phase-3 BLUE-VIOLET

TEURIC CURRENT: Betcha Hova Body/ Teuric Shield/ Dimensions 7, 8 and 9
Phase -1 VIOLET, Phase-2 GOLD, Phase-3 Mid-tone Silver

MAHARIC CURRENT: Mahara Hova Body/ Maharic Shield/ Dimensions 10, 11 and 12
Phase-1 BLUE-BLACK, Phase-2 SILVER BLACK, Phase-3 WHITE

TRANSMUTATION CURRENT

(can be transmitted only by 12th-level Avatars with full Mahara Hova Integration)

RISHIC CURRENT: Raja Hova Body/ Rishic Shield/ Dimensions 13, 14 and 15
Phase-1 TURQUOISE, Phase-2 PALE YELLOW, Phase-3 MAGENTA

Current Combining

When using **Triadic Phase Currents, each Phase current is** *combined* **with the current running from the activated** ***Maharic Shield*****, in** ***combination with*** **the Phase current from the** ***Harmonic ABOVE the Phase current you are using*****.** The **DORA DIC PHASE-1** current is therefore composed of: **D-11/D-12 PALE SILVER** (Maharic Shield), **D-4 GREEN** Doradic Shield Phase -1 AND **D-7 VIOLET,** the *Phase-1 current* of Harmonic 3 - Teuric Shield, *one Harmonic up* from Doradic Phase-1. In activating the **DORADIC-1 (Doradic Phase-1) current you are using SILVER-GREEN-VIOLET color to direct Dimensions 12-11-7-4 current.**

COMBINED TRIADIC CURRENTS
Used in Kathara Healing

TELLURIC
PHASE-1: **PALE SILVER** (D11&12) + **RED** (D-1) + **GREEN** (D-4)
PHASE-2: **PALE SILVER** + **ORANGE-GOLD** (D-2) + **BLUE** (D-5)
PHASE-3: **PALE SILVER** + **YELLOW** (D-3) + **INDIGO** (D-6)

DORADIC
PHASE-1: **PALE SILVER** + **GREEN** (D-4) + **VIOLET** (D-7)
PHASE-2: **PALE SILVER** + **BLUE** (D-5) + **GOLD** (D-8)
PHASE-3: **PALE SILVER** + **INDIGO** (D-6) + **SILVER** (D-9)

TEURIC
PHASE-1: **PALE SILVER** + **VIOLET** (D-7) + **BLUE-BLACK** (D-10)
PHASE-2: **PALE SILVER** + **GOLD** (D-8) + **SILVER-BLACK** (D-11)
PHASE-3: **PALE SILVER** + **SILVER** (D-9) + **WHITE** (D-12)

MAHARIC
(Requires full 12-Strand DNA Template activation & accelerated DNA Template coding)
PHASE-1: **PALE SILVER** + **BLUE-BLACK** (D-10) + **PALE TURQUOISE** (D-13)
PHASE-2: **PALE SILVER** + **SILVER-BLACK** (D-11) + **PALE YELLOW** (D-14)
PHASE-3: **PALE SILVER** + **WHITE** (D-12) + **PALE MAGENTA** (D-15)

In **Level-1 Kathara Healing** we begin preparing the body and DNA Template to receive the higher dimensional Phase Currents by initiating transmission of the **Doradic Phase-1 Healing Current**- the *Pale Silver* + *Green* + *Violet* frequencies of dimensions *12, 11, 7 and 4.*

Through the 7th-Dimensional aspect of the **Teuric Shield** and 11th and 12th Dimensional aspects of the **Maharic Shield**, the **Doradic-1 Healing Current** allows for recoding and realignment of the **1st-4th**-Dimensional aspects of the **Nada** and **Alphi Hova Bodies**, the **Telluric Shield** and **Physical, Emotional** and **Mental Bodies** of Density-1, the **D-4** aspect of the **Doradic Shield** and **Astral Body**, the **1st-4th DNA Strand Templates**, the **1st-4th Chakras**, and the **1st-4th Sub-harmonics** of all Scalar Shields, DNA Templates, Hova Bodies and Chakras. Doradic-1 Healing Current is effective in clearing the **Karmic-Miasmic imprint** from the **Density-1 Time Cycle incarnations** and the beginning of Density-2 Time Cycle incarnations.

CHAPTER 3 HIGHLIGHTS

KATHARA BEGINNING APPLICATIONS

- The **Hova Bodies** of personal anatomy contain portions of our higher dimensional awareness. One can begin accessing this awareness by building a **Perceptual Bridge** between the 3-Dimensional Self and higher identity aspects.
- Taking conscious initiative in building a Perceptual Bridge expedites **DNA Template activation** and the organic evolutionary process.
- The **MENTOR Technique** assists in building the Perceptual Bridge and activates dormant **Kathara Lines** in our **Level-1 Kathara Grid** to open communication between our D3 and Density-2, D4 and D5 levels of awareness.

THE MENTOR

- The Mentor is a part of our awareness that is composed of **3rd, 4th and 5th Dimensional frequencies** of consciousness, which exists as a quantity of **Scalar Wave patterns** that span **Densities 1 and 2.**

- The **Mentor Focus** will be used in **Kathara Healing** for **guidance, information retrieval** and **objective observation.** It can also be used to access **Cellular Memory,** and in **"Inner Child", Bi-location, Remote Viewing** and **Dream** work.

MORPHOGENETIC REPATTERNING AND THE MAHARIC SHIELD

- Through a process called **Morphogenetic Repatterning,** Kathara Healing effects the **Core** of Dis-ease and dis-harmony in the Body-Mind-Spirit system by **repatterning** the Scalar-wave Programs in the personal **Holographic Template** to their original **Primal Order.**

- In **Level-1 Kathara Healing** we learn the **MAHARIC RECODING PROCESS**- the most important level of Holographic Template realignment.

- The **Maharic Shield** is the 3-Dimensional Scalar Grid corresponding to the **10th, 11th and 12th-Dimensional frequencies** of **Density-4.** It represents the **Original Point of Manifestation** and holds our original "Liquid Light" **Hydroplasmic Pre-matter Creation Imprint**, which is the **Organic Imprint for Health.**

- In Kathara Healing, the **Maharic Shield** Organic Imprint for Health is used to progressively **repattern** the embodied **Kathara Grid** and body systems to their original **Primal Order.**

- The **12th-Dimensional Frequencies** of the Maharic Shield contain within them the **144 Sub-frequency Band** Scalar patterns of **ALL** of the Dimensions below.

- 12th-Dimensional **Maharic Frequency** can be used to **effectively correct distortions** in the lower dimensional levels of the Manifestation Template, Scalar Shields and Kathara Grid.

- Activation of the **Maharic Shield** serves as the **RESET BUTTON** for the embodied **Kathara Grid** and for 12 Dimensions of Body-Mind-Spirit anatomy.

THE MAHARIC SEAL AND LIQUID LIGHT CLEANSE

- In bio-energetic healing, **Level-1 Kathara Grid** distortions override realignments made to the **outer levels** of the bio-fields alone. For **lasting healing** to occur, Level-1 Kathara Grid distortions must be realigned.

- The **Maharic Shield**, with its **144 Frequency Sub-Harmonics**, is the only portion of the Morphogenetic anatomy that can fully repattern and realign the **Level-1 Kathara 12-Tree Grid.** In **Kathara Healing**, the **Maharic Shield** is used to realign the Level-1 12-Tree Grid.

- The **Maharic Seal and Liquid Light Cleanse** technique is used to restore distorted **Partiki Phasing Sequences** and **Scalar-wave arrangements** within the **3 Levels of the Kathara Grid** and **Scalar Shields.**

- Realignment will be **temporary** until the Kathara Grid reaches "**Critical Mass**" of energy in the **new**, realigned pattern.

- Until **critical mass** is reached, the outer levels of the anatomy will continue to **reverse** the Kathara Grid healing. With practice and **consistent application** of the **Maharic Seal and Liquid Light Cleanse** technique, the realignment of the Kathara Grid will become **permanent.**

- In future applications of Kathara Healing processes will be used to realign the **outer levels** of the bio-field and the **Kathara Grid simultaneously,** to expedite the healing process.

- The Focus of **Level-1 Kathara Healing** is **Morphogenetic Repatterning** and **Holographic Template Recoding** via the **Maharic Shield,** to clear distortions and the **Karmic-miasmic imprint** from the personal **Scalar Shields, Kathara Grid** and **DNA Template,** utilizing the **accelerated energies** of the *Planetary Bio-feed Interface System* **(PBIS).**

KATHARA POINTS

- **Kathara Points** are mini energy-vortex points in the body that connect directly to **Diodic Point vortices** in the **Level-3 Kathara Diodic Point Grid.**

- Stimulation of the Kathara Points through **manual massage** effects the **movement of energy** within related areas of the Kathara Grid and body systems.

- Used in sequence, **Sequence-1 Kathara Points for Regeneration** *open* energetic gateways to the **Kathara Lines** of the **Kathara Level-1 12-Tree Grid**, to allow new, realigned scalar patterns from the **Maharic Shield** to run through the Kathara Lines and Kathara Grid for **Core Template Repatterning.**

- **Sequence-1 Kathara Points** create **more lasting but less immediate** effects of realignment and healing. They can be **used alone** for **deep healing** and re-balancing of the **Core Kathara Grid.**

- **Sequence-2 Kathara Points for Revitalization** *close* **Kathara Lines** in the 12-Tree Grid and **channel** energy into the **Nadial Lines** of the **outer bio-energetic field** for more rapid revitalization and re-balancing of the **outer auric levels, chakras** and **physical cells.**

- **Sequence-2 Kathara Points** create **more immediate but less lasting** effects of realignment and healing. They can be **used alone** to create **temporary revitalization** of the **outer levels** of the bio-system.

- **Used together, Sequence-1** Kathara Points can run **Maharic energy** through the **core Kathara Grid** for **Template Recoding. Sequence-2** Kathara Points can then be used to **direct the Maharic energy** into the **outer levels** of the bio-field and physical body, to **expedite healing** through **simultaneous** inner and outer bio-field realignment.

- In **Kathara Healing, Sequence-1** Kathara Points are used to **OPEN** the Kathara Lines **prior to** running the **Maharic Seal and Liquid Light Cleanse** and **Sequence-2** Kathara Points can be used **following** the procedure to **revitalize** the outer bio-field and body systems.

THE MAHARIC SEAL, PBIS AND HEALING

- Use of the **Maharic Seal and Liquid Light Cleanse** technique begins activation of dormant **Chakras 8-12** and the **Planetary Bio-feed Interface System (PBIS).**

- **Opening the PBIS** allows energy from the **Planetary Shields** to be drawn into the **human body** for **rapid activation** of the **personal Maharic Shield** and **Crystal Seals, to expedite** the processes of **DNA Template activation, healing, recoding of the Holographic Template** and interdimensional evolution.

- Opening of the PBIS can also allow the human **DNA Template** to serve as a **Bio-electric Conduit,** through which the **Planetary Scalar Shields** and Electro-magnetic Grids can be realigned with their **Primal Order** for **geophysical planetary healing.**

- Through the PBIS humans can directly facilitate healing of the **Planetary Templar Complex** from the Manifestation Template level, as well as facilitate healing in other biological organisms.

- Each use of the **Maharic Seal and Liquid Light Cleanse** technique assists in **planetary healing**, as the process progressively stimulates the **Planetary Maharic Shield** into activation, to realign **Planetary Shield** distortions.

- The **Maharic Seal and Liquid Light Cleanse** technique is used as **preliminary preparation** for **ALL Kathara Healing applications.** It creates a temporary **12th-Dimensional Scalar Frequency Seal** in the facilitator's bio-field to **protect** both facilitator and client from taking on each other's bio-field distortions.

- In **healing applications**, the **Maharic Seal** is needed to run interdimensional healing currents to their most effective **12th-Sub-Harmonic level.**

BIO-SPIRITUAL EVOLUTION, ASCENSION AND HEALING

- The processes by which **healing** occurs through re-genesis of Primal Order are the same processes through which true **Spiritual Actualization** takes place.

- **Biology** and **consciousness** are **intimately intertwined** through the natural **Laws of Universal Unified Field Physics**, the **energetic dynamics** through which consciousness enters manifestation.

- The hidden **impetus for action** behind human evolution is the core species objective of **Mastery of Co-creation** within the space-time system. This **Evolutionary Objective** is obtained through achievement of the Evolutionary **Goal** of **Transmutational Dimensional Ascension.**

- **Kathara Healing** applications generate **healing** through restoring the **Original Imprint for Health.**

- Restoration of the **Original Imprint for Health** simultaneously expedites the natural processes of **evolution,** through activation of the **12-Strand DNA Template, Kundalini** energies, and **Merkaba Vehicle** and integration of the **Hova Bodies, Scalar Shields** and higher dimensional aspects of personal **spiritual identity.**

- **Kathara Healing** facilitates healing while simultaneously facilitating **Spiritual Actualization** and expediting the Goal of **Transmutational Dimensional Ascension.**

- **Healing is a function of consciousness.** There is no difference between the substance that composes physical matter and the substance that composes consciousness, other than the **dimensional frequency** from which one is perceiving.

- When personal consciousness energy is applied in **congruence** with the natural Laws of Universal Unified Field Physics, **healing, wellbeing** and **Spiritual Actualization** result.

MULTI-DIMENSIONAL IDENTITY STRUCTURE

- **Human anatomy** is a **15-Dimensional Scalar-wave construct.** Part of our identity exists **simultaneously** within the Time Cycles of the higher dimensional **Harmonic Universes.**

- We are indelibly **linked** to our higher identity levels through our embodied **Kathara Grid, Scalar Shields** and **DNA Template.** As we evolve biologically to activation of dormant portions of our DNA Template and Scalar Shields, the conscious awareness of our higher identity levels **progressively embodies.**

- The 3-Dimensional Hova Body **Electro-magnetic Domains** and Scalar Shields that form them represent **Platforms of Perception** through which our higher identity levels perceive.

- **Merger** of the **Hova Bodies** via activation of the **DNA Template** and **Scalar Shields** creates **reintegration** of the **Multi-Dimensional Identity Structure.**

4 PRIMARY TRIADIC HEALING CURRENTS AND IDENTITY

- The **5 Levels of Multi-Dimensional Identity Structure** are: **Incarnate**-Density-1, **Soul**-Density-2, **Oversoul**-Density-3, **Avatar**-Density-4 and **Rishi**-Density-5. There are also **3 Ascended Master** identity levels, Hova Bodies and Shields existing **beyond** the dimensionalized **Time Matrix.**

- **In Kathara Healing** we use the various levels of higher dimensional identity to draw in **healing current** from the higher dimensional Unified Fields, by activating the portions of the **personal Scalar Shields, Kathara Grid** and **DNA Template** that correspond to the higher dimensional **Hova Bodies.**

- There are **4 Primary Triadic** (3-Dimensional) **Energy Currents** that can be used in **Healing Facilitation**: The **Telluric Current**-Density-1, the **Doradic Current**-Density-2, the **Teuric Current**-Density-3 and the **Maharic Current**-Density-4. The **Rishic Current** of Density-5 can be run only by beings with **full 12-strand DNA activation.**

4 PRIMARY TRIADIC CURRENTS

- Each of the **4 Primary Triadic Healing Currents** corresponds to one of the first 4 **Hova Bodies** of human anatomy.

- In Kathara Healing, the 4 Primary Triadic Currents are harmonically interwoven to create 4 powerful **Combined Healing Currents.**

- Each of the 4 Triadic Healing Currents has **3** Phases, or **3 Phase Currents,** each representing one of the three dimensional frequency bands within the **Triadic Current.**

- Each of the **12 Phase Currents** is run in combination with the 11-12th-Dimensional **Maharic Current** and the Phase Current from the **harmonic directly above,** to form a powerful **Triadic Healing Current.**

- In **Kathara Healing,** specific Healing Currents are directed by using the **Color** of their dominant **wave-length.**

DORADIC-PHASE-1 CURRENT

- **Level-1 Kathara Healing** teaches us to activate our **Doradic-Phase-1 Current**- the **Pale Silver** (D11-12) **+ Green** (D-4) **+ Violet** (D-7)- for **Healing Facilitation** and **personal** DNA Template and Shield activation.

- The **Doradic-Phase –1 Current** can realign the **1st-4th** Dimensional aspects of the **Scalar Shields**, the **1st-4th Chakras, Axi-A-Tonal Lines** and **DNA Strand Templates**, the **Physical, Emotional** and **Mental** bodies of the **Nada Hova Body** and the D-4 **Astral body** of the **Alphi Hova Body.**

- **Doradic-Phase-1 Current** can also be used to realign the **1st-4th Sub-Harmonics** of ALL Shields, DNA Strand Templates, Axi-A-Tonal Lines, Chakras and Hova Bodies and to clear the **Karmic-Miasmic Imprint** from the **Density-1** incarnational Time Cycles and the **first part** of the **Density-2** incarnational Time Cycles.

CHAPTER 4

GENERAL KATHARA HEALING FIELDWORK

Skills to Facilitate Healing

- OPENING THE HEALING CHANNELS- DORADIC-PHASE-1 CURRENT, THE DORADIC SPHERE, DORADIC CORDS AND DORADIC BALLS.
- THE KARMIC-MIASMIC IMPRINT, INCARNATIONAL TIME VECTORS, VECTOR IMBEDDING.
- MULTI-VECTOR HOLOGRAPHIC RECODING THROUGH THE MAHARIC INFUSION.
- ATTITUDES AND ETIQUETTE IN HEALING, THE MOTIVATION TO HEAL, POSTURES OF LOVE, THE FRAMEWORK FOR HEALING AND FULLY ENGAGING THE LOVE VIBRATION.
- THE 6 STEP MAHARIC RECODING SESSION, MELCHIZEDEK CLOISTER ORDINATION AND BECOMING A PROFESSIONAL SPIRITUAL HEALING FACILITATOR-INSTRUCTOR.

TECHNIQUES:

#3- OPENING THE HEALING CHANNELS- DORADIC –PHASE-1 CURRENT

#4- MULTI-VECTOR HOLOGRAPHIC RECODING KATHARA SCAN

#5- THE MAHARIC INFUSION

THE MAHARA SPACE COMFORT TOUCH

TOPICS OF DISCUSSION

OPENING THE HEALING CHANNELS

DORADIC-PHASE-1 CURRENT

Interdimensional Currents and Signet Star Crystal Seals

Activation of any **Triadic Healing Current** requires temporary release of the corresponding **Signet Star Crystal Seals** within the personal **Scalar Shield** and a temporary activation of the portions of the dormant **12-Strand DNA Template** that correspond to the Signet Seals. Signet Seals modulate the flow of frequency between the 3-Dimensional Harmonic Density Levels. When Signet Seals are in their usual (for this time period) dormant phase, they keep the **5 Hova Bodies** of the personal 15-Dimensional anatomy separate from each other by creating an electro-magnetic barrier or **Magnetic Repulsion Zone** between each 3-Dimensional level of the energetic anatomy. This *Magnetic Repulsion Zone* between embodied **Harmonics of Manifestation** manifests as **polarity resistance to frequency inflow** within the 3 Levels of the Kathara Grid, the Scalar Shields, Axi-A-Tonal Lines, Chakras and Auric Field levels of the embodied **Inner Templar Complex. In order to run higher dimensional frequency currents through the physical body for healing applications, it is necessary to temporarily release portions of the Magnetic Repulsion Zones between the Hova Bodies.** Releasing the electro-magnetic resistance to higher dimensional frequency inflow within the Inner Templar Complex is achieved through temporary activation of the **Signet Seals** within the **Kathara Level-2 Crystal Seals Grid** of the personal **Scalar Shields.**

Most contemporary energetic healing systems rely upon using the 1st, 2nd and 3rd-Dimensional frequencies of the **TELLURIC PHASE CURRENTS** in the **Nada Hova Body**. Through the Nada Hova Body alone, only the 3-Dimensional **Sub-Harmonics** of higher dimensional frequency currents can be run, as the dormant *Signet Seals* block the faster moving *Partiki Phasing Flash-line Sequences* of higher dimensional frequency bands from running through the DNA Template. **If a frequency band is blocked from running through the DNA Template that frequency cannot be energetically transmitted through the Nada Hova Body and physical bio-electrical systems.** In **conventional energy healing methods**, even those emerging from ancient systems of subtle-energy healing, the **Signet Seals**, and thus the *Scalar Shields, Hova Bodies* and *DNA Template* remain dormant in their usually **closed** position, **phase-locked** into a 3-Dimensional orientation. While the DNA Template remains phase-locked into the 3-Dimensional orientation of the Nada Hova Body, only the **1st through 12th Sub-frequency bands** (Sub-Harmonics) of **1st through 3rd Dimensional Current** (Telluric Current), and the **1st through 3rd Sub-frequency bands** of **4th through 12th Dimensional Current** can be run through the human body for transmission. Use of the lower frequency (slower Partiki Phasing rhythm) **Telluric Currents** can effect **temporary** beneficial change in the **outer layers** of the bio-energetic field, but Telluric Currents alone cannot facilitate full repatterning of the **3 Levels of the Kathara Grid** where **Scalar Shield** distortions that cause **genetic malfunction** are embedded. The **11th-12th-Dimensional frequencies** of the Pre-matter Hydroplasmic **Maharic Currents** are the only dimensional frequencies powerful enough to affect change in the embodied **Kathara Grid.** To run **Maharic Current**, and the high frequency interdimensional **Triadic Phase Currents**, through the human body requires release of the **Signet Seals within the personal Scalar Shields.**

Triadic Phase Currents, the Maharic Shield and the PBIS

Most healing systems have not incorporated the **Maharic Current** into their frequency application procedures because the **Planetary Templar Complex** has not been able to run a D-12 **Maharic Current** through the planetary grids for **210,216 years.** Like the human **DNA Template**, if the **Planetary Shields** and Manifestation Template are blocked from processing interdimensional frequency, that frequency will be **unavailable for use** on the planet. If the **Signet Star Crystal Seals** (Star Gates) in the **Planetary Shields** are dormant, closed and phase-locked into Density-1 orientation, no one on the planet will be able to draw interdimensional frequency into their **personal Shields** because the frequency is unavailable within the **Planetary Shields.** The personal and planetary Templar Complexes are **intimately interwoven**, and what effects one will inevitably effect the other.

In order to run the full spectrum of interdimensional **Triadic Phase Currents** through the human body it is necessary to open the **Signet Seals** in the personal **Inner Templar** and the **Signet Star Gates** in the **Planetary Templar Complex.** In conventional human evolution, the internal Signet Seals, which serve as the **Genetic Time Codes** or **"Fire Codes"** of the human **DNA Template,** automatically, progressively and sequentially open over **very long cycles of time.** During the slow activation of the Genetic Time Codes the conscious identity experiences passage through numerous incarnate lifecycles within the planetary Time Cycle, evolving through a series of **Single Vector incarnations** before being released from the 3-Dimensional phase-lock of Density-1 manifestation. One can **manually open the Signet Seals** in the embodied Inner Templar Complex to **expedite evolution** into the Multi-dimensional, **Multi-Vector Time Cycles** through use of the 11th-12th Dimensional **Maharic Current.**

Activation of the personal **Maharic Shield** allows for rapid release of the embodied **Signet Seals** and activation of the **Fire Codes** in the DNA Template. The **Maharic Current** from the personal Maharic Shield can be used to release the **Signet Star Crystal Seals** within the body, which in turn activates the dormant **Kundalini** energies at the base of the spine and the **Cranial-Sacral Kundalini Seals** within the **Tailbone** and **Pineal Gland.** Release of the Cranial-Sacral Seals of the Internal Templar Complex allows the **Magnetic Repulsion Zones** between the **Hova Bodies** to release so the DNA Template, personal Scalar Shields and physical body systems can receive inflow of higher dimensional frequency. To gain conscious mastery over the process of releasing the internal Signet Seals requires activation of the personal **Maharic Shield**, and the personal Maharic Shield can be **manually activated** only through drawing **Maharic Current** into the personal Shields via the **Planetary Maharic Shield. The entire process of releasing the internal *Signet Seals* by activating the personal *Maharic Shield*, in order to enable the *DNA Template* to run *Triadic Phase Currents* for healing is entirely dependant upon the *operational function* of the *Planetary Bio-feed Interface System* (PBIS).**

If the **Planetary Templar Complex** is blocked, or the Signet Star Gates are dormant, and **Maharic Current** from the **Planetary Maharic Shield** is not able to run through the planetary grids, humans on Earth do not have the option of **manually activating the personal Maharic Shield**, because the **PBIS** is not operational. The **PBIS** becomes **operationally functional** within the human body through activation of the **12th Chakra**. The *12th Chakra* cannot activate in the personal Templar Complex if the **Planetary Templar Complex** cannot run 12th-Dimensional **Maharic frequency.** For over 200,000 years, the Planetary Templar Complex could not run Maharic frequency, and thus manual activation of the personal Maharic Shield and release of the embodied Signet Seals to open the Hova Bodies for running interdimensional Triadic Phase Currents for healing were not available options for Earth humanity. Since the recent activation of the **Planetary Templar Complex, Maharic Shield** and **PBIS** activation and **Kathara Healing** applications are now available on Earth.

Opening Triadic Phase Currents in the Human Body

The method by which **Triadic Phase Currents** are activated within the human body is a **progressive process.** First, opening of the personal **Kathara Grid, Telluric Shield** and **Nada Hova Body** is orchestrated through activation of the **Maharic Shield** and **Signet Seals,** to allow inflow of frequency from the higher dimensional **Hova Bodies.** Next, the incoming frequency is harnessed and **collected** within the **Chakra System.** Finally, the collected frequency is then **transmitted** for healing facilitation in others, either through direct **Chakra transmission** or by close-range **Frequency Induction** via transmission of frequency from the activated **Secondary Chakra Centers** within the **PALMS.**

The ability to run the higher dimensional Triadic Phase Currents within the body must be built up within the Internal Templar Complex, starting with the **slowest-moving current** of the higher dimensional spectrum- the **DORADIC-PHASE-1 CURRENT.** The *Doradic-Phase-1 Current* utilizes the **sub-frequencies** of the **11th-12th-**Dimensional **Maharic Current** from the Density-4 *Mahara Hova Body* as a **carrier wave** that will carry the desired interdimensional currents through the **Signet Seals** of the personal **Scalar Shields.** The **full spectrum** of the **4th** Dimensional **Doradic-Phase-1** current from the Density-2 *Alphi Hova Body* is activated as the **primary healing frequency** for transmission. The **full spectrum** of the **7th-**Dimensional **Teuric-Phase-1 Current** (one Harmonic above the Doradic-Phase-1 Current) from the Density-3 *Betcha Hova Body* is used to release the 4th-Dimensional **Signet Seal,** allowing the 4th-Dimensional Doradic-Phase-1 current to enter the **Nada Hova Body.**

Activating the **4th Signet Seal** triggers **temporary** activation of the **4th DNA Strand Template** and corresponding **4th Kathara Center** in the Level-1 12-Tree Grid, which allows the 4th-Dimensional frequencies of the **Doradic-Phase-1 Current** to pass through the **active DNA** and into the bio-energetic and bio-electrical systems of the body for transmission. Once the DNA Template becomes accustomed to holding a **4th-DNA Strand Template Activation,** after **several months** of practice in running the 4th–Dimensional *Doradic-Phase-1 Current,* the body will be able to begin receiving the primarily 5th-Dimensional **Doradic-Phase-2 Current. The lower dimensional Triadic Currents must be activated within the DNA Template before the higher dimensional Triadic Currents can run.** In **Level-1 Kathara Healing** the first step of activating the full spectrum (12 sub-harmonics) of the 4th-Dimensional **Doradic-Phase-1 Current** is achieved.

Triadic Phase Currents and Color Cap-Stones

The **Color Cap Stone** of a dimensional frequency band is the visual representation of the **primary wave-length** formed by the specific **Partiki Phasing Rhythm** for that dimension. A specific dimensional frequency band can be chosen and directed by the **color translation** of its primary wave-length. The **Color Cap Stones** of the dimensional frequency bands are used in Kathara Healing to direct specifically selected dimensional frequency bands (Partiki Phasing Rhythms) for specific applications. The **Color Cap Stones** for the **Doradic-Phase-1 Current** are **PALE SILVER** (**D-11**-D-12 Maharic) + **GREEN** (D-4 Doradic) + **VIOLET** (D-7 Teuric). In **technique # 3 – OPENING THE HEALING CHANNELS-DORADIC-1** - the ***Pale Silver* + *Green* + *Violet*** Cap Stone Colors will be used to activate the **Doradic-Phase-1** Healing Current within the body.

DORADIC SPHERE, CORDS AND BALLS

The Doradic Sphere and Current Collection

The **DORADIC SPHERE** is a **frequency repository** that is formed to hold the activated **Doradic-Phase-1 Current** within the **Chakra system** for transmission in healing facilitation. As the Doradic-Phase-1 Current is primarily a **4th-Dimensional Current**, the **Doradic-1 Sphere** will be formed in the **4th Chakra**, which corresponds to the 4th-Dimensional **ASTRAL body** of the Alphi Hova Body and Auric Field. **Transmission** of the Doradic-Phase-1 Current will take place from the **Doradic Sphere** at the **4th Chakra**, creating a **4th-Dimensional ASTRAL INFUSION** of frequency into the bio-energetic field of the client in **close-range healing**, and a general **Astral Plane Infusion** of Doradic-Phase-1 frequency into **Manifestation Templates** of areas(and everything contained within the space) when transmitted directly from the **4th Chakra.**

Doradic Cords and Current Induction

The **DORADIC CORDS** are **energy conduits** that are formed by opening the embodied **Axi-A-Tonal Lines** within the **arms, hands and fingers.** Opening the Doradic Cords allows the **Secondary Chakras** within the **palms** of the hands to carry the **Doradic-Phase-1 Current** for application in **close-range** transmission. Though Triadic Phase Currents can be transmitted directly from the **Chakra Center** in which the **Collection Sphere** is placed, the energies are more **diffused** and **diluted** in this form of transmission, unless the personal DNA Template holds a **full, permanent activation** of the Strand Template corresponding to the Triadic Current being transmitted. It takes time, often years, for the DNA Template to acquire and permanently hold a higher strand activation level. One-on-one healing facilitation is more effective when conducted through **concentrating** the Triadic Current through the **Axi-A-Tonal Lines** for **DIRECT INDUCTION** of current through the **Palm Chakras** in **close-range** transmission. Close-range transmission also allows for **more precise application** of frequency to specific areas of the body systems. In **Level-1 Kathara Healing**, the **Doradic Cords** are activated within the arms, palms and fingers to allow for concentration, focused direction and **Direct Induction** of the **Doradic-Phase-1 Current.**

For **general healing** purposes, such as **"clearing rooms"** or geographical spaces, or when attempting to transmit healing current into **groups of people,** transmission of the **Doradic-Phase-1 Current** can be orchestrated directly from the **4th Chakra** for **NON-SPECIFIC INDUCTION.** In **Non-Specific Induction,** following activation of the Doradic-Phase-1 Current, each **INHALE** breath is used to fill the **Doradic Sphere** with more energy and each **EXHALE** breath is used to expand and transmit the energy into the room or bio-fields of a group of people. It is not necessary to activate the Doradic Cords for Non-Specific Induction applications. In **Level-1 Kathara Healing** applications use of the **Doradic Cords** and **Palm Chakras** is employed for Direct Induction close-range transmission in Client Sessions. To enhance and expedite **personal healing,** the activated **Doradic-Phase –1 Current** can be run through the personal **Level-1 Kathara Grid** with the ***Maharic Shield and Liquid Light Cleanse*** technique and then through each of the **7 Primary Embodied Chakras.**

Doradic Balls and Palm Transmission Direct Induction

The **DORADIC BALLS** are small energy repositories that form in the **Palms** of the Hands when the **Doradic Cords** have been activated to run Doradic-Phase-1-Current through the **Palm Chakras.** Doradic Balls are used to **accumulate current** in the **Palm Chakra vortices** prior to transmission, to **strengthen** the intensity of the current.

PALM CHAKRAS AND TRANSMITTING CURRENT

Primary Polarities of Palm Chakras

Along with the **15 Primary Chakras** within human anatomy there are many other smaller **Secondary** and **Tertiary Chakra Centers** throughout the body, which correspond to the energetic interrelationships of scalar-wave patterns within the **Kathara Level-3 Diodic Points Grid**. All Chakras operate as sets of **Black and White Holes,** through which energy from the Dimensional Unified Fields circulates into and out of the body and Manifestation Template. The **Palm Chakras** are part of the **Secondary Chakra System**. Like all Chakras, the Palm Chakras are structured as **2 vortices** of energy **joined at the tip** by a minute **Crystal Seal** within the **Kathara Level-2 Crystal Seals Grid**. The Palm Chakras run through the **center of the Palms** and out of the **back of the hands.**

In any set of Chakra vortex spirals, one vortex represents the **magnetic Black Hole,** a *counter-clockwise rotating* spiral that **draws energy IN** toward the central Crystal Seal, and the companion vortex represents the corresponding **Electrical White Hole,** the *clock-wise rotating* spiral that **sends energy OUT** from the central Crystal Seal. The **Black Hole** vortex represents the **RECEIVING spiral** or **Magnetic Pole** and the **White Hole** vortex represents the **TRANSMITTING spiral** or **Electrical Pole.** The **Electrical Pole** of a Chakra represents the **EXPANSION CURRENT** of the Chakra, through which it **expands energy out** from the personal Shields; it is referred to as **BASE ELECTRICAL**. The **Magnetic Pole** of a Chakra represents the **CONTRACTION CURRENT** of the Chakra, through which it **contracts energy in** from the external Unified Field to the personal Shields; it is referred to as **BASE MAGNETIC.**

The Chakras in the **Palms** are composed of many smaller minute **vortex sets**, each with Magnetic and Electrical Poles, but the **PRIMARY POLE** of each Palm Chakra is that pertaining to the **larger Black-White Hole set** and **Crystal Seal**. Though each Palm Chakra is capable of both **Transmitting and Receiving** energy current, the **strongest and most focused currents** can be achieved by utilizing the natural polarity orientation of the Primary Vortex Set. The Chakra in the **RIGHT PALM** is **BASE ELECTRICAL;** its corresponding vortex on the back of the right hand is **Base Magnetic.** The Chakra in the **LEFT PALM** is **BASE MAGNETIC;** its corresponding vortex on the back of the left hand is **Base Electrical.** When running Triadic Phase Currents it is helpful to understand the **Primary Polarities of the Palm Chakras** in order to create the **strongest** and **least distorted** healing current. In **Kathara Healing,** the **RIGHT HAND** is the **TRANSMITTING HAND,** through which Triadic Current is **Exhaled** down the **Cords** in the arms and **EXPANDED** into the **RIGHT PALM CHAKRA** for **TRANSMISION.** The **LEFT HAND** is the **RECEIVING HAND,** through which the Triadic Current transmitted from the Right Hand is **drawn back** into the facilitator's body **TO CREATE A CLOSED CIRCUIT OF CURRENT** for the **strongest current intensity** and **purest frequency content.**

HAND POSITIONS

Standard Hand Position for Transmitting Triadic Current

When transmitting Triadic Current, the **LEFT PALM** is **PLACED OVER THE BACK OF THE RIGHT HAND**. The *Base Magnetic* Current of the *Left Palm* **interfaces** with the *Base Magnetic* Current in the *Back of the Right Hand*, creating a **MAGNETIC REPULSION ZONE**, which **blocks the vortex on the Back of the Right hand** from drawing **non-specific frequency** from the Density-1 Unified Field. This keeps the current transmitted from the *Right Palm Chakra* **pure** to its specifically chosen content. The *Base Magnetic* vortex in the *Left Palm* simultaneously draws the **transmitted current** back up through the smaller vortex sets after it runs through the client's body, creating a **closed circuit of pure frequency** running between the **Hova Bodies** of the **client,** the **facilitator** and the higher dimensional **Unified Fields**. Options of **Frequency Modulation** for other healing applications also become available through using this **HAND POSITION** when transmitting healing current. In some applications a **modulated current** that includes bursts of Density-1 Telluric Current interspersed with current transmission from the higher dimensions is desired; this can be achieved by moving the Left Hand on and off of the vortex on the back of the Right Hand. The **LEFT OVER RIGHT HAND POSITION** is used in **Level-1 Kathara Healing** applications.

Elements of Doradic-Phase-1 Current Activation

Doradic-1 Cap Stone Colors:

PALE SILVER (D-11&D-12) + **GREEN** (D-4)+ **VIOLET** (D-7)


DORADIC SPHERE
Doradic Sphere collects current in 4th Chakra
CHAKRA 4 and Doradic Sphere
DORADIC CORDS & BALLS
Doradic Cords
Doradic Cords transmit current from *Doradic Sphere* to *Palm Chakras* via Axi-A-Tonal Lines in arms and hands.
Doradic Balls allow current to collect in *Palm Chakras* to intensify current.
CHAKRA 4
Doradic Balls
Maharic Seal
DIRECT INDUCTION
NON-SPECIFIC INDUCTION
CHAKRA 4
INHALE breath fills Doradic Sphere with current from D-4 *Alphi Hova Body*. EXHALE breath transmits non-specific D-4 *Astral Infusion* of current via Chakra 4


STANDARD HAND POSITIONS
E
L
M+M
R
E
Transmit
Client
Magnetic Repulsion Zone
LEFT HAND Receive
E
RIGHT HAND Transmit
Client
E
Transmit
R Base Electric Transmitting Hand
L Base Magnetic Receiving Hand
PALM CHAKRAS
LEFT OVER RIGHT HAND POSITION
E = Electrical Expanding Clockwise Spiral
M = Magnetic Contracting Counter-Clockwise Spiral

Intrinsic Process of Activating a Triadic Phase Current

ACTIVATE MAHARIC SHIELD

1. Open the PBIS using the D-11 – D-12 Wave Guide Symbol Code, the **Hierophant Symbol**, to open the **12th Chakra** and stimulate release of **Maharic frequency** from the **Planetary Maharic Shield.**
2. From the PBIS draw Maharic frequency from the Earth's Maharic Shield **up** into the dormant personal Maharic Shield 12" below the feet, to activate **the personal Maharic Shield.**

ACTIVATE TRIADIC PHASE CURRENT

3. Choose the specific Triadic Current you desire to run.
4. Use the inflow of **Maharic Current** from the personal and planetary Maharic Shield as a **Carrier Wave** to carry the **Cap Stone Color frequencies of the Signet Star Crystal Seals** in your Scalar Shields that correspond to the **Triadic Phase Current** you wish to activate.
5. Temporarily **release** the **Signet** and **Cranial-Sacral Kundalini Seals** and activate the **DNA Strand Template** corresponding to the chosen **Triadic Phase Current,** by running the **Primary Frequency** and the frequency **one Harmonic above it** through the **Signet Seals,** on the Maharic carrier wave current, to open the **Nada Hova Body** and physical body systems to inflow of the higher dimensional **Triadic Phase Current.**

COLLECT AND TRANSMIT HEALING CURRENT

6. As the Triadic Phase currents transmits into the body through the Signet Seals, Kundalini energies and DNA Template, **collect and build the current** as a **Sphere** of energy within the **Chakra** corresponding to the Primary Triadic Current you are running.
7. Run the current from the **Collecting Chakra** through **the Axi-A-Tonal Line Cords** in the arms, to activate the **Palm Chakras.**
8. **Exhale** current from the **Chakra Collection Sphere** through the **Cords** and allow it to build into **Balls** of energy within the **Palm Chakras** before transmitting.
9. Transmit the Triadic Current through the **RIGHT PALM CHAKRA** into client's bio-energetic field while drawing more current into the **Chakra Collection Sphere** with each **exhale** breath and draw the current back through the **LEFT PALM** on each **inhale** breath to create a higher dimensional Closed Circuit Healing Current. Use **LEFT PALM OVER BACK OF RIGHT HAND** hand position.

TECHNIQUE # 3

Opening the Healing Channels- Doradic-Phase-1 Current

1. Breathe slowly and deeply for several breaths while visualizing or imagining a **4" Violet Dot** on the center of the *inside of your forehead*. Make the color image as strong as you are able.(If you can't yet perceive inner colors or visualization, simply imagine the Violet Dot as being there). Move the Violet Dot to the center of the brain at the **Pineal Gland**, and then upward into the **7th Crown Chakra**, from the inside of the head moving upward and outward until the Violet Dot *rests on top of your head* at the Crown Chakra.

2. Call to mind the **Hierophant Symbol** (Pale Silver Merkaba Star formed by combining 2 Merkaba Stars). Visualize the spinning Hierophant stationed 12" below the feet within your **Maharic Shield** and slowly **INHALE,** drawing the Hierophant up through the Central Body Current, up to meet the Violet Dot at the **7th Crown Chakra** at the top of the head. When the *Hierophant connects with the Violet Dot* visualize the Violet Dot bursting into a **4" Vertical Pillar of Violet-Silver Light**. Imagine the *Violet-Silver Pillar* running down through the body into the *Earth Core* and upward to the **14th Chakra** 36" above the Head. You have activated **the Violet Ray of Transmutation.**

3. Move your attention to the **4th Heart Chakra** and imagine a *small Green Spherical Crystal* – the **Green Star**- stationed at its core. This is the *Green Star Crystal Seal* that controls release of *4th Dimensional* frequency – *Phase-1 Doradic Current* - into the body. **INHALE,** drawing Violet-Silver energy from the Violet-Silver Pillar into the *Green Star*. **EXHALE,** *expanding* the Violet-Silver energy *into the Green Star sphere. Repeat 2 more INHALE-EXHALE* breaths, drawing Violet-Silver Energy from the Pillar and expanding it into the Green Star sphere. At the end of the last **EXHALE,** imagine the **Green Star popping,** turning into a spinning Green and Violet Starburst of Light, as the *Violet-Silver Pillar disappears. Spin the Green-Violet Starburst* faster until it becomes a *ball of Green-Violet Light*, about the size of a *grapefruit*, spinning in the center of the *4th Heart Chakra*. The Green-Violet ball is the store-house for your Phase-1Doradic Current – it is called the **Doradic Sphere. INHALE** and draw Pale Silver energy from your **Maharic Shield,** through the Central Body Current and into the center of the **Doradic Sphere** at the **4th Heart Chakra,** encasing the Sphere in translucent Pale Silver Light.

4. **EXHALE quickly** and push **2 Cords** of *Green-Violet-Silver energy* – **Doradic Cords** -from the Doradic Sphere *down the inside of your arms*, one Cord through each arm. As the ends of the Doradic Cords reach the inside of the hands, notice a sensation of *mild resistance* as the Cords push against the *etheric membranes* covering the *small chakras* in the palms. **INHALE** a full breath, drawing Silver energy up from the **Maharic Shield,** into the *Doradic Sphere* at the 4th Chakra. **EXHALE forcefully,** pushing more energy down through the *Doradic Cords* in the arms, and feel this energy **"pop"** out of the *palms, releasing the membranes* on the palm chakras. Continue to **INHALE** energy up from the *Maharic Shield* into the *Doradic Sphere* and **EXHALE** it through the *Doradic Cords, building the strength of the Doradic Current* in both palms. Imagine the Doradic Current *pooling in the palms* to form *2 Green-Violet balls of light*, about the size of *tennis balls*. Energize the Doradic Sphere and Cords until you can sense the smaller **Doradic Balls** formed in the *palms* of your hands. **Your *Doradic Current* is now activated for use in healing facilitation.**

SYMBOL SHORTHAND

TECHNIQUE # 3: Opening the Healing Channels
Doradic-Phase-1 Current

1. **4" Violet Dot** inside forehead, move to **Pineal Gland** then up through **7th Crown Chakra** to **top of head.**
2. **Hierophant Symbol** at center of your **Maharic Shield** 12" below feet. Inhale Symbol **up** to **Violet Dot** at top of head. See **Violet Dot burst** into **4" Violet-Silver Pillar** running through body to **Earth's core** and up to **14th Chakra** 36" above head.
3. Small **Green Star Crystal Seal at 4th Heart Chakra.** Inhale drawing **Violet-Silver** energy from **Violet-Silver Pillar** into **Green Star Crystal Seal** and see **Green Star Crystal Popping** into a spinning **Green-Violet Starburst,** as Violet-Silver Pillar **disappears.** Spin Green-Violet Starburst faster until it becomes grapefruit-size **BALL** of **Green-Violet Light**, the **Doradic Sphere,** at the center of the **4th Heart Chakra.** Encase Green-Violet Sphere in **Pale Silver** Maharic energy.
4. Push a **Green-Violet-Silver Doradic Cord** down each arm to **Palm Chakra Membranes** and draw **Pale Silver** up from **Maharic Shield** to **Doradic Sphere** and forcefully push Maharic Current **down arms** to **pop Palm Chakra Membranes.** While running **Doradic-1 Current** draw energy from **Maharic Shield** to **Doradic Sphere** and push it down arms from **Doradic Sphere** through **Doradic Cords** to **pool** into **Doradic Balls** at **Palm Chakras.**

TECHNIQUE # 3: Opening the Healing Channels

Doradic-Phase-1 Current


CHAKRA-14
CHAKRA-7
Violet Dot
PINEAL GLAND
1
2B
Violet Dot
THE HIEROPHANT SYMBOL CODE
3A
3B
CHAKRA-4
VIOLET-SILVER PILLAR
Maharic Seal
4A
4B
THE HIEROPHANT SYMBOL CODE
2A
THE HIEROPHANT SYMBOL CODE
PERSONAL MAHARIC SHIELD
12"
EARTH CORE

2A Hierophant up from Maharic Shield to inside **Violet Dot** on head.

2B Violet Dot pops to **Violet-Silver Vertical Pillar**

3A Green Star Crystal Seal at 4th Heart Chakra.

3B Green Seal pops to make **Green-Violet Starburst** then Silver-Green-Violet **Doradic Sphere** in 4th Chakra.

1 Violet Dot moves from **forehead** to **Pineal Gland** to **7th Chakra** to top of head

4A Doradic Cords run Doradic-Phase-1Healing Current from Doradic Sphere to Palm Chakras

4B Doradic Balls pool energy in **Palm Chakras** to amplify current for **Direct Induction** transmission.

PALE SILVER
11TH – 12TH Dimensional Frequency

THE KARMIC-MIASMIC IMPRINT

THE NATURE OF KARMA

Karma, Identity, the Christos and the Physics of Divine Right Order

When an identity enters the **Time Matrix** to begin **simultaneous cycles of evolution** through time, it enters the manifest fields through first adopting a **Manifestation Template** composed of Partiki Units and Scalar Waves. The first Manifestation Template is called the **Rishic Shield**; it exists at the **Ante-matter** scalar-wave level of **Density-5** and holds the complete **Primal Scalar Pattern** for all of the **Singular Identities** that will **simultaneously** manifest into incarnation within the lower dimensional Densities and Time Cycles. The **Rishic Shield** represents the **Identity Gestalt** or **Family of Consciousness** through which identity enters manifestation. The Rishic Shield carries the precise configuration of Scalar-wave patterns, the **Primal Order** of energetic substance, through which the consciousness individuated to form a collective of consciousness within the dimensionalized Time Matrix. Every individual incarnate from the Rishic Family of Consciousness in time carries as part of its core **Kathara Grid** scalar program the **electromagnetic energy signature** of **Primal Order** carried by the **Rishic Shield** through which it manifested.

The Scalar-wave design of the Rishic Shield represents **DIVINE RIGHT ORDER**, the **Primal Order** of scalar-wave energetic relationship and **Partiki Phasing Sequences** that individual identities in time must re-evolve to hold within their embodied **Manifestation Templates** in order to **regain freedom** from the dimensional systems of the Time Matrix. Consciousness from the Rishic Shield, in the form of **Omni-polar wave spectra**, enters the manifest Densities by projecting portions of itself into **smaller Consciousness Gestalts** within the lower dimensional fields. The smaller Gestalts of Consciousness form the **3-Dimensional Scalar Shields** of the identity within the dimensionalized matter systems. **Each Scalar Shield holds the consciousness of numerous simultaneous Cycles of Incarnation within each of the 4 Primary Time cycles of Densities 1 through 4.** Each individual incarnate in time is directly linked to its original **Rishic Shield Family of Consciousness** through the **Density-4 Maharic Shield.** The Maharic Shield of dimensions **10-12** contains the first **Pre-matter Hydroplasmic scalar-wave spectra** through which identity began its experience within the holograms of Space, Time and Matter. The **personal Maharic Shield,** often called the **PERSONAL CHRISTOS IMPRINT**, holds the original **Primal Order** of scalar waves through which manifest consciousness links to its **Rishic Shield.** The **Christos Imprint** of the **Maharic Shield** represents the **PATH OF DIVINE RIGHT ORDER** through which each individual consciousness in time can **re-evolve** to its original Eternal Non-manifest State of Wholeness in Consciousness beyond the Time Matrix. **Divine Right Order is not only a spiritual concept; it is a reality in energy within the scientific dynamics of Universal Unified Field Physics.** Divine Right Order represents the **Primal Order** of scalar-waves that make up the original **Manifestation Template** from which individual **singular lifetimes** emerge, and it is the necessary pattern of energetic order within the personal multi-dimensional Manifestation Template which allows incarnate beings to fulfill the **evolutionary objective** of **Transmutational Dimensional Ascension. The result of an incarnate being's *Manifestation Template* and Conscious Awareness becoming mis-aligned with the energetic structure of *Divine Right Order* is called KARMA.**

Karma, Divine Right Order, the Scalar Shields, Free Will and Miasms

If it is understood that the universe and all things within it exist as **manifestations of consciousness** in the form of **precisely ordered** scalar wave arrangements, and that there is an intrinsic and indelible **Primal Order** upon which all manifestation functions, it will not be difficult to conceptualize the **literal and tangible nature** of the **Karmic Imprint**. In energetic terms, **Divine Right Order** represents the **natural alignment** of conscious energy fields within the intrinsic **Laws of Universal Physics** characteristic to the dimensional structures of time. Divine Right Order exists as a **tangible, specific** and **harmonious organization** of **energy interrelationships** within the Primal Order of energetic structure that creates dimensionality. The condition frequently referred to as **Karma** is, like Divine Right Order, a tangible, specific organization of energy interrelationships. Unlike Divine Right Order, *Karma* represents dis-harmonious interrelationships of energy within the context of the Primal Order that creates dimensionality. **Karma** can be viewed as **CHAOTIC, incoherent energetic disorganization**, whereas **Order** represents **coherent energetic** organization.

In terms of the **15-Dimensional anatomy** of the **personal Manifestation Template**, the **Karmic Pattern** represents **areas of incoherent energetic disorganization** within the structure of the personal **Scalar Shields**. The **12th–Dimensional** Level of the personal **Maharic Shield** holds the original **Christos Imprint**, the **Primal Order** *perfect organization* of scalar-wave configurations that links our consciousness and **DNA Template** to the **Rishic Shield Family of Consciousness** through which we entered the **Time Matrix**. While the Maharic Shield holds our original **Perfect Organization of Consciousness**, the Scalar Shields upon which our lower dimensional **Hova Bodies** and **Incarnate, Soul** and **Over-Soul Manifestation Cycles** emerge often become **distorted** from their original **Primal Order** as held within the **Maharic** and **Rishic Shields**. Human consciousness, in its multidimensional forms, was designed **"in the image of its Creator"**, having **Free Will** to *apply the dynamics of energetic creation in time* in accordance with **personal intention,** within the greater context of the fixed **Natural Energetic Laws of Creation.**

When we use our gift of **Free Will** to direct our energies in a manner **congruent** with the **Divine Right Order** of **Universal Unified Field Physics** (which implies co-creative, not competitive co-evolution for all), the scalar-wave design of our personal **Scalar Shields** remains organized upon the intrinsic design of universal and personal **Primal Order**. Through **embodiment** of Divine Right Order within our personal **Scalar Shields** and consciousness, we know conditions of **perfect health and harmony** within the Time Matrix. When our Free Will is used to direct our energies in ways that are **incongruent** with and non-supportive of **Primal Order**, the **disorganization** of our energetic orientation manifests as literal **Partiki Phasing Sequence distortions** that create **misshapen scalar-wave groupings** within the anatomy of the personal **Kathara Grid**, **Scalar Shields** and the **DNA Template** built upon them. These misshapen scalar-wave groupings within the Kathara Grid, Scalar Shields and DNA Template are called **MIASMS** and they hold, in **tangible scalar frequency** form, the **disorganized energetic patterns** of our **Free Will choices** through which we have used our energies in a manner **incongruent** with **Divine Right Order.**

Miasms* are the *tangible substance* of our *Karmic Pattern* that reflect the areas in which our *consciousness* and *Scalar Shields* are *distorted* from our original *Maharic Shield Christos Imprint* of *Perfect Organization* within the context of *Universal Primal Order.

TIME VECTORS AND THE KARMIC-MIASMIC IMPRINT

Miasms, Incarnational Time Vectors, Vector Imbedding and the DNA Template

The **Miasmic Imprint** within the body and Manifestation Template that holds the personal **Karmic pattern** manifests as **mathematical, geometrical** and **electro-magnetic distortions** in scalar-wave forms within the Kathara Grid and Scalar Shields, that cause groupings of **Anti-particles** to build up within the **Particle field** of the physical and energetic anatomy. The build-up of **Anti-particles** within the Particle Field blocks the natural flow of energy and consciousness through the Kathara Level-3 **Diodic Points Grid,** and manifests as **malfunctions** within the **Partiki Phasing Programs** within the **Kathara Centers** of the Level-1 **12-Tree Grid** and within the **Signet Star Crystal Seals** of the Kathara Level-2 **Crystal Seals Grid.** The **3 Levels of the Kathara Grid** set the blueprint for manifestation of the **Scalar Shields, Hova Bodies, Chakra System** and **DNA Template. Miasmic distortions** in the **Kathara Grid** effect **every level of personal manifestation,** from the operation of the **physical genetic code** to the ability of consciousness to successfully embody within the physical form, to the potentials of **Transmutational Dimensional Ascension** and attainment of **Spiritual Actualization.**

Karma*- the *Miasmic Imprint*- is a *biophysical phenomenon* of scalar-wave distortion that directly effects the *human DNA.

The **Incarnations of SELF** that **simultaneously manifest** into incarnational cycles of divergent space-time placement within the 4 Densities and 12-Dimensions of Matter are all **directly interconnect** through the **Kathara Grid, Scalar Shields** and **DNA TEMPLATE.** The **Free Will choices** made by other manifestations of ourselves **concurrently existing** in other space-time locations and different manifest body forms, effect the function of our personal **Kathara Grid, DNA Template, conscious awareness** and **life experience.** The **choices WE make** in our present lifetime directly effect the **Kathara Grid, DNA Template, consciousness** and **life experience** of **our other-time incarnations.** The energetic connection between incarnations of the SELF is an immediate, **living connection** of energy and consciousness. Because our numerous simultaneous incarnations in time are directly, energetically linked to each other via the Kathara Grid and DNA Template, we literally **inherit Miasmic Buildup from each other** on a continual basis. When we make the choice to restore our personal **Imprint for Health,** our **Christos Imprint,** as held within our **Maharic Shield,** part of these efforts must involve **clearing the Miasmic Imprint** that is bleeding through into our personal Manifestation Template for the other incarnations of Self.

Each of our simultaneous incarnations in time represents one **SINGLE VECTOR CONSCIOUSNESS,** one portion of our **Eternal Identity** that experiences 3-Dimensional **linear evolutionary progression** along **ONE TIME VECTOR** (one cycle of Partiki Phasing Sequences). **Each Incarnate represents a TIME VECTOR.** The multiple Time Vectors of our Multiple Simultaneous Selves are literally **encoded** within core scalar-wave programs of our **DNA Template;** this is called **VECTOR IMBEDDING.** To fully heal our Body-Mind-Spirit system by restoring it to its **Organic Imprint for Health,** the **Maharic Shield Christos Imprint,** we need to clear the Miasmic Imprint from our other simultaneous incarnations as it is presently embedded within our DNA Template. **Transmuting the Miasmic Imprint that is embedded in our DNA Template to restore the original perfect Primal Order is called "Clearing the Karmic Pattern" or MULTI-VECTOR HOLOGRAPHIC RECODING.**

MULTI-VECTOR HOLOGRAPHIC RECODING

REGENESIS OF THE PERSONAL CHRISTOS

Restoring the Organic Imprint for Health and Clearing the Karmic-Miasmic Imprint

Literally all conditions of **dis-ease** in the human body and dis-harmony in the life experience, including the unnatural condition of **death** of the human body form, result from **Miasmic Distortions** within the embodied **Kathara Grid, Scalar Shields, DNA Template** and personal **Inner Templar Complex.** The natural state of **Universal Primal Order** is harmonious co-creative interrelationship of consciousness. Humans can progressively return to their natural condition of **Ordered Perfection** through **re-genesis**, or *re-creation*, of the **Organic Imprint for Health – the Maharic Shield Christos Imprint** – within the Kathara Grid blueprint of the personal Manifestation Template. **Regenesis of the Personal Christos** is a **Multi-Vector Endeavor**, involving clearing the karmic-Miasmic Imprint from a myriad of various simultaneous selves presently evolving in the Time Matrix. The **hard way** to clear the Miasmic Imprint is by **"walking the Karma"**, which means allowing progressive levels of the **Miasmic Imprint** to repeatedly **re-manifest** in the personal life experience, until the **proper application of Free Will choice** used in congruence with **Divine Right Order** becomes consciously apparent and the **"Right Choices"** are made to re-ordered the disorganized use of energy that caused the Miasm to form. In our present time, this approach to "clearing the Karmic Pattern" is no longer effective as a learning tool by which embodied consciousness teaches itself the etiquette of creation. **The Miasmic Imprint within the collective human species has grown so extensively that the core issues of misapplied Free Will that cause Miasmic Buildup can no longer be consciously identified, and the Miasmic Imprint continues to compound and amplify itself as the same errors of Free Will energy use are perpetually repeated and reinforced.**

The Karmic-Miasmic Imprint is an **ENERGY FORM**; a literal **construct of scalar-wave frequency** with its corresponding **Anti-particle Manifestation.** As a form of energy, the **Miasmic Imprint** can be dealt with **AS ENERGY, WITH ENERGY**, for the most expedient clearing, healing and realignment of the **Karmic Imprint.**

The **Karmic-Miasmic Imprint** manifests within the **causal level** of manifestation, the **3 Levels of the embodied Kathara Grid** of the **personal Internal Template Complex**, and from the Kathara Level the Karmic-Miasmic Imprint manifests as **misalignment** and **malfunction** within all levels of Body-Mind-Spirit system. To clear the Karmic Imprint **AS ENERGY, WITH ENERGY,** its disorganized scalar-frequency patterns must be realigned from the **Core Template Kathara Grids**, the **causal level** of miasmic manifestation. Restoring the **Maharic Shield Christos Imprint** to the personal **Kathara Grid** takes time and **precise applications of frequency re-ordering** in all levels of the Body-Mind-Spirit system. The first step to **Regenesis of the Personal Christos** is the **MAHARIC RECODING PROCESS.**

MULTI-VECTOR HOLOGRAPHIC RECODING

Recoding the Time Vectors of the DNA Template and the DNA Fire Codes

The process of regenerating the **Christos Imprint** within the **Kathara Grid** of the human body is a **MULTI-VECTOR** undertaking. A **Vector** is a **set cycle of vibrational-oscillation rhythm** that creates a **specific repeating Partiki Phasing Rhythm** and **Flash Line Sequence.** Each individual incarnate self in time holds within the electro-magnetic programs of its embodied **Kathara Centers** the precise **Partiki Phasing Rhythms** that correspond to its particular placement within the planetary **Time Cycles.** The **Time Vector,** or **Flash Line Sequence** that creates one linear **Event Horizon,** is literally encoded and actively operational within the **Kathara Grid** and **DNA Template** of each incarnate identity. In the process of restoring the **Organic Integrity** to the personal Manifestation Template, the dormant **Partiki Phasing Rhythms** that correspond to one's **other-time incarnates** are progressively **brought into activation** and **realigned** with the Christos Imprint of the **Maharic Shield.**

The **Partiki Phasing Flash Line Sequence programs** within the embodied **Kathara Centers** manifest within the **DNA Template** as the **GENETIC TIME CODES,** or **Fire Codes,** of the DNA. In restoring **Maharic Order** to the personal **Kathara Grid,** the **12 Dormant Fire Codes** of the DNA Template will be slowly but progressively brought into **activation** through the 11th-12th –Dimensional Frequencies of the **Maharic Shield Mahara Hova Body Current.** Activation of the **DNA Fire Codes** creates a reciprocal release of the **Signet Star Crystal Seals** and **Cranial-Sacral Kundalini Seals** within the **Kathara Level-2 Crystal Seals Grid,** progressive activation of the dormant **Kundalini energies** and **Merkaba Vehicle Phases,** merger of the **Hova Bodies** and embodiment of the higher dimensional **Spiritual aspects** of conscious awareness. The process of recoding the multiple time vectors within the DNA Template – **Multi-vector Holographic Recoding-** is a process of progressive **WHOLE-BEING HEALING** that is achieved through **consistent application** of the **MAHARIC RECODING PROCESS,** and expedited through complimentary processes of **DNA Template, Kundalini** and **Merkaba Vehicle** activation. Level-1 Kathara Healing introduces the operational mechanics of the **Maharic Recoding Process.**

The Maharic Recoding Process

FOR MULTI-VECTOR HOLOGRAPHIC RECODING

The 4 Primary Elements of Action

1. **The Maharic Seal and the Liquid Light Cleanse** (Technique # 2)
2. **Opening the Healing Channels** (Technique # 3)
3. **Amplifying Inner Audio-Visual and Kathara Scan** (Technique # 4)
4. **The Maharic Infusion** (Technique # 5)

The **4 Primary Elements of Action** to begin the **Maharic Recoding Process,** through which **Multi-Vector Holographic Recoding** of the **Morphogenetic Field Manifestation Template** is achieved. Begins realignment of the Core Manifestation Template **Kathara Grid Levels,** the **Scalar Shields, Hova Bodies, Axi-A-Tonal Lines** and **DNA Template** with the **Primal Order** perfect scalar-wave pattern of the personal 12th-Dimensional Pre-matter Hydroplasmic **Maharic Shield-** the **Christos Imprint** and **Organic Imprint for Health.** Also begins activation of dormant **DNA Strand Templates, Kundalini** energies and the **Merkaba Vehicle** for **Transmutational Dimensional Ascension.**

Bio-Regenesis of the Christos Imprint
and 12-Strand DNA Template
within the human body.

TECHNIQUE # 4

AMPLIFYING INNER AUDIO-VISUAL AND KATHARA SCAN

1. Place **RIGHT palm** (*electrical-transmitting hand*) over the **5th Kathara Center** at the **Navel**, and place the *Left palm* (*magnetic-receiving hand*) over the *back of the right hand* (to block 3rd-Dimensional energies from entering the rear of the right hand chakra). **INHALE** energy from your **Maharic Shield** – the *Maharic Carrier Wave*- into your **Doradic Sphere** at the *4th Heart Chakra*. **EXHALE** and run the *Maharic Wave* down the *Doradic Cords* in the arms and into the *Doradic Balls* in the palms. Inhale, then **EXHALE**, using the exhale breath to *push* energy from the *Doradic Sphere*, down the *Doradic Cord* in the **RIGHT** arm, through the **RIGHT Doradic Ball** and into the **5th Kathara Center** at the *Navel*. Run several breaths of *Doradic-1 Current* into the *5th Kathara Center* at the Navel, until a **mild tingling sensation** is **felt**.

2. Place the **LEFT palm** over the **5th Chakra** at the *Throat*, with the *Right palm* covering the *back of the LEFT hand*, and **INHALE** the Doradic-1 Current up from the *5th Kathara Center* at the Navel, into the Seed/Center of the **5th Chakra**. **EXHALE** and *expand* the Doradic-1 frequency into the *5th Chakra spiral*, allowing the magnetic current from the LEFT hand to draw the energy out through the spiral. As you **EXHALE**, slowly **move the hands forward**, away from the body and the 5th Chakra.

3. Repeat the same process over the **6th Kathara Center**, placing the **RIGHT palm** over the *6th Kathara Center* below the **Right Shoulder**, with the *Left palm* covering the back of the *RIGHT hand*. **INHALE**/Draw energy up from the *Maharic Shield*, into the *Doradic Sphere*. **EXHALE** energy down the *Doradic Cords* into the *Doradic Balls*. Inhale, then **EXHALE** energy down the *RIGHT Doradic Cord* through the *RIGHT palm* and into **Kathara Center 6.** Run several breaths to energize the *6th Kathara Center*. Then move **LEFT palm** over the *6th Third Eye Chakra* in the forehead, with Right palm behind. **INHALE** the Doradic-1 Current from the *6th Kathara Center* into the Seed/Center of the *6th Chakra* and **EXHALE** the energy into the 6th Chakra spiral while drawing it through with the magnetic current from the LEFT hand. The **6th Sense-*Audurea***, which provides **inner audio** perception, and the **7th Sense-Tristet**, which provides **inner visual** perception are now energized and amplified in preparation for **Kathara Scan.**

4. Close your eyes and focus your attention in a **single point** at the *inside of your forehead*. Inhale, and as you **EXHALE** run your attention outward ***through your 6th Chakra spiral***, into the **6th Chakra Spiral of your Client**. Move your attention into the center of your Client's brain, the **Pineal Gland**. Inhale, and **EXHALE** moving your awareness down from the Client's Pineal, through your *Client's Central Body Current* and down into the **Earth's core. INHALE** and move your awareness back upward to your **Client's Maharic Shield**, and spread your awareness outward through the *Maharic Shield* with the **EXHALE.** On the *inside of your forehead*, imagine the image of the **Kathara 12-Tree Grid, INHALE** energy from the *Client's Maharic Shield* and **EXHALE** the energy out into the *12-Tree image*. Breathe gently for a moment, *observing the 12-Tree Grid*, which will register tones of white, black and ranges of gray in between. If you cannot yet visualize, you will still get a sense of the 12-Tree image and the areas of dark and light within it. The dark areas represent layers of the **MIASMIC BODY**, areas of the *karmic imprint* that need clearing when you run *Technique # 4: The Maharic Infusion*. Remember the areas of the Client's Kathara that need clearing. Inhale, and *open your eyes* on **EXHALE.**

SYMBOL SHORTHAND

TECHNIQUE # 4: Amplifying Inner Audio-Visual and Kathara Scan

Activate Maharic Seal and Open Healing Channels. (Techniques # 2 and # 3 first)

1. **RIGHT Palm** on **5th Kathara Center** in **Navel.** Breathe **Maharic Current** up from personal **Maharic Shield** and into **Doradic Sphere** at **4th Chakra.** Push **Maharic-Doradic-1 Current** down **Doradic Cords** and into **Doradic Balls** at **Palm Chakras.** Push Current from Doradic Ball in **RIGHT Palm** into **Kathara Center # 5** in **Navel.**

2. **LEFT Palm** on **5th Throat Chakra,** cover back with **Right Palm** (Reverse Standard Hand Position). Inhale **Doradic-1 Current** up from **5th Kathara Center** in **Navel** to center of **5th Throat Chakra** and expand Current into **5th Chakra Spiral,** with **Left Palm Chakra** drawing current out of **5th Chakra Spiral.**

3. **RIGHT Palm** on **Kathara Center # 6** below **Right Shoulder,** cover back with **Left Palm.** Push **Maharic-Doradic-1 Current** from Doradic Ball in **RIGHT Palm** into **Kathara Center # 6. LEFT Palm** over **6th 3rd Eye Chakra,** cover back with **Right Palm** (Reverse Standard Hand Position). Inhale **Doradic-1 Current** up from **Kathara Center # 6** to center of **6th- 3rd Eye Chakra** and expand Current into **6th Chakra Spiral,** with **LEFT Palm Chakra** drawing Current out of **6th Chakra Spiral.**

4. **KATHARA CLIENT SCAN: A.** Place **Point of Attention** inside **forehead** and run attention out of **6th Chakra Spiral** and into the **6th Chakra Spiral of Client,** then into **Client's Pineal Gland. B.** Run attention down **Client's Central Vertical Current** and into **Earth's Core,** then back up to **Client's Maharic Shield.** Expand attention out into **Client's Maharic Shield. C.** Visualize image of **Kathara 12-Tree Grid,** inhale energy from **Client's Maharic Shield** and exhale it into image of **Kathara Grid. D.** Observe for **Dark Miasmic Buildups** in image of **Kathara Grid;** run extra healing Current into these areas of the **Client's Kathara Grid** during the **Maharic Infusion** (Technique # 5).

Personal Kathara Scan: On **Step 4** run attention down **your Central Vertical Current** then back up to **your Maharic Shield** and out into **your Maharic Shield.** Breathe energy from your Maharic Shield into image of **Kathara 12-Tree Grid** and observe for **Dark Miasmic Buildup** areas to clear during the ***Maharic Seal and Liquid Light Cleanse*** technique. Send **extra Maharic Current** to these areas during ***Liquid Light Cleanse.***

TECHNIQUE # 4: Amplifying Inner Audio-Visual and Kathara Scan

1. A. RIGHT Palm on 5th Kathara Center in Navel.
B. Breathe Maharic Current up from personal Maharic Shield to Doradic Sphere and down Doradic Cords to Palm Chakras.
C. Push Current from RIGHT Doradic Ball into 5th Kathara Center.


1.
Right
Left
Kathara Center #5 In Navel
A.
Chakra 4 Doradic Sphere
Doradic Cords & Balls
B.
C.

2. A. LEFT Palm on 5th Throat Chakra, cover back with Right Palm.
B. INHALE Doradic-1 Current up from Kathara Center # 5-Navel to 5th Chakra and expand Current into 5th Chakra Spiral.


2.
Chakra-5
Kathara Center #5
Draw Current up from Kathara Center # 5 to Chakra-5
A
Right
Left
Draw Current through 5th Chakra Spiral into LEFT Palm
B.

3. A. RIGHT Palm on Kathara Center #6 in Right Shoulder, cover back with Left Palm. B. LEFT Palm on 6th 3rd-Eye Chakra, INHALE Current from Kathara Center # 6 into 6th Chakra Spiral and into LEFT Palm. C. Kathara Scan: a. Run your Attention from your 6th Chakra to Client's 6th Chakra and Pineal Gland. b. Run Attention down Client's Central Vertical Current to Earth's Core & into Client's Maharic Shield. c. EXHALE energy from Client's Maharic Shield into Image of Kathara 12-Tree Grid. d. Scan grid for Dark Areas of Miasmic Buildup for clearing with Maharic Infusion.


3.
Right
Left
Kathara Center #6
A.
Draw Current up from Kathara Center # 6 to Chakra-6
Chakra-6
Right
Left
Kathara Center-#6
B.

KATHARA SCAN


C.
a. Link with Client via 6th Chakra
Chakra-6
Client's Pineal Gland
Facilitator
Client
Facilitator
b.
Client
Client's Central Vertical Current
Client's Maharic Shield
Kathara 12-Tree Image
Facilitator
Client
c.
INHALE energy from Client's Maharic Shield to Kathara 12-Tree Grid Image
d.
Locate Dark Areas for clearing.
Kathara 12-Tree Dark Areas

TECHNIQUE # 5

THE MAHARIC INFUSION – CLIENT FACILITATION

Prior to using this technique you should have completed the following: 1.Positioned *MENTOR* over your Right shoulder to assist (*Tech. # 1:Awakening the Mentor and the 6th and 7th Senses*). 2. Activated your *Maharic Shield, Maharic Seal* and run the *Liquid Light.* (*Tech. # 2: The Maharic Seal and the Liquid Light Cleanse.*) 3.Activated your *Doradic Current, Inner audio/\Visual* and *Client Kathara Scan* (*Tech. # 3. and #4*)
4. Opened the *Kathara Lines* for you and your Client (*Sequence-1 Kathara Points*)

Place Client in a reclining position with shoes off:

1. Position yourself at the **feet** of the reclining Client. Place **RIGHT palm** *12" below Client's feet* at the **Maharic Shield,** *left palm* over the back of Right hand.
2. Visualize the **Hierophant symbol** on the *inside of your forehead.* Inhale, then **EXHALE,** moving the *Hierophant* down to **Chakra 4** and into the **Doradic Sphere** with the exhale breath. **INHALE** energy upward from *your* **Maharic Shield** and into the *Doradic Sphere.* **EXHALE** the **Hierophant** with *Doradic-1 current* down the **Right Doradic Cord** and into the *Doradic Ball* in the **Right palm.** .
3. Inhale, then **EXHALE** the *Hierophant and Doradic-1 current* into the *center* of the **Client's Maharic Shield.** Visualize the *Hierophant spinning* in the center of the Client's Maharic Shield until you sense a **mild shift** in the energy below the Client's feet. The shift indicates that the Client's *Maharic Shield* has activated and the *Maharic Pillar* has "popped" vertically upward from the Shield – the Client's bio-energetic field now carries the **Maharic Seal.**
4. **INHALE** energy from your *Maharic Shield* into your *Doradic Sphere,* then **EXHALE** the energy down **both Doradic Cords,** into the Doradic Balls in the palms. Visualize the **12-Tree Kathara Grid** *within the Client's body.* You will now run the **Maharic Infusion** through the *small chakra points in the feet.*

TECHNIQUE #5 : Continued
THE *MAHARIC INFUSION*

5. Place your **Right palm** on the *bottom* of **Client's Left foot** and your **Left palm** on *top of the foot*, centered over the *Right palm*. Imagine that you are lining up the *small vortex* beneath the ball of the Client's foot (which extends *through the foot* to come out on top), with the *small chakras* in your *palms*. Inhale, then **EXHALE** energy from your **Doradic Sphere** through the **Right Doradic Cord, Right palm** and *into the **sole** of the Client's foot.* Visualize the **Green-Violet-Silver energy** traveling up the **Kathara Line on the** *Left side of the body*, through the *4th, 7th and 10th Kathara Centers*. Continue **EXHALING** energy into the **Left foot** until you begin to feel a bit of **fuzzy energy** coming out of the foot toward your palm. This indicates that the *Kathara Line* has *reached its energy-holding capacity*. **Repeat** the process on the **Right foot**, running energy through the *Kathara Line on the Right side of the body and the 3rd, 6th and 9th Kathara Centers.*

6. You will now clear and align the **Central Vertical Kathara Line** to complete the **Maharic Infusion. Move to Client's head.** Place **Right palm** over **Client's 10th Chakra** 6" above the head, the location of the *12th Kathara Center*. Place *Left palm* over back of Right hand. **INHALE** energy from your **Maharic Shield** into your **Doradic Sphere** then **EXHALE** energy down the **Right Doradic Cord**, into the **Right palm** and through the **10th Chakra**. Visualize the energy moving down from the *10th Chakra* into the **7th Chakra**, to the **Pineal Gland** (11th Kathara Center), then *rapidly* down the **Central Body Current** and **Central Kathara Line**, through *Kathara Centers 8* (thyroid), *5* (Navel), *2* (at Base Chakra) and into *Kathara Center 1* at **Earth's core**. Continue **EXHALING** energy into the **10th Chakra** and **Central Kathara Line** until you feel **fuzziness** against your *Right palm*, indicating that the *Kathara Grid* has reached its *energy-holding capacity*.

7. *Before releasing 10th Chakra* direct a bit of additional energy through the **Central Kathara Line** into areas that revealed **dark spots** during the *Kathara Scan*. Visualize the areas *getting light* as the energy runs through them. **You may add other healing modalities at this point, if desired.** *Close* by using the **Sequence-2 Kathara Points** to close the Kathara Lines and *revitalize the body.* Allow Client a few moments to recline before ending session.

THE MAHARIC INFUSION – CLIENT FACILITATION

Preparation: A. *Technique #1*- Place MENTOR over your Right Shoulder B. *Technique #2*-Activate your Maharic Shield and run Liquid Light Cleanse. C. *Technique #3*- Activate yourDoradic-1 Current D. *Technique #4* – Amplify Inner Audio-Visual and run Client Kathara Scan E. *Sequence-1 Kathara Points* massage on Self and Client to open Kathara Lines.

Place Client in reclining position with shoes off

1. Stand at Client's feet, place **RIGHT Palm** 12" below Client's feet at **Client's Maharic Shield**, left palm over back of Right hand.

2. See **Hierophant Symbol Code** inside your forehead, **EXHALE** Symbol down to **Chakra-4 Doradic Sphere. INHALE** energy up from your **Maharic Shield** into Doradic Sphere. **EXHALE** *Hierophant Symbol* with *Doradic-1 Current* down **RIGHT Doradic Cord** into **RIGHT Doradic Ball in RIGHT Palm.**

3. **EXHALE** Doradic-1 Current and Hierophant Symbol into Center of **Client's Maharic Shield** via **Right Palm Doradic Ball** and **spin Hierophant** until sensed **Energy Shift** of **Client's Maharic Seal.**

4. **INHALE** Current from your Maharic Shield to Doradic Sphere and **EXHALE** Current down both **Doradic Cords** into **Doradic Balls**. See **Kathara12-Tree Grid** within **Client's** body and begin running the ***Maharic Infusion*** through the **Secondary Chakras** in **Client's feet.**

5. **RIGHT PALM** on **bottom** of **Client's LEFT FOOT, LEFT PALM** on **top** of **Client's LEFT FOOT,** both **centered** over Client's LEFT FOOT **Secondary Chakra. INHALE** Maharic energy into Doradic Sphere and **EXHALE** Doradic-1 Current into Client's **LEFT KATHARA LINE**, and through **Kathara Centers # 4, #7** and **# 10. EXHALE** Doradic-1 Current into Client's **LEFT FOOT** until **"Fuzzy"** resistance emerges from Client's foot Chakra. **REPEAT PROCESS** on **Client's RIGHT FOOT**, running Doradic-1 Current through the **RIGHT KATHARA LINE** and **Kathara Centers # 3, #6** and **#9.**

6. **Stand at Client's Head. RIGHT PALM** over **Client's 10th Chakra** (6" above head- the 12th Kathara Center), LEFT Palm over back of Right hand. Fill Doradic Sphere with Maharic Energy then **EXHALE** Doradic-1 Current down **RIGHT DORADIC CORD** and Palm and into **Client's 10th Chakra.** Run Current from **Chakra-10,** to **Crown Chakra-7, Pineal Gland,** rapidly down **Central Vertical Current** and **Kathara Centers #8** (Thyroid), **#5** (Navel) **#2** (Chakra-1) and **#1** (Earth's Core Chakra 13). Continue exhaling Current until **"Fuzzy"** resistance emerges from Client's 10th Chakra.

7. Direct **additional** energy through Client's **CENTRAL KATHARA LINE** to clear **DARK AREAS** of **Kathara Grid** located in **Kathara Scan.** Add any additional healing technologies following Client's Maharic Infusion. Close with **SEQUENCE-1 KATHARA POINTS** massage. Allow Client to remain relaxed in reclining position for several minutes following Maharic Infusion.

TECHNIQUE # 5: THE MAHARIC INFUSION – CLIENT FACILITATION

Maharic Infusion 6-STEP Sequence


Facilitator stands
at *Client's Feet*
for STEPS 1-5
Facilitator stands
at *Client's Head*
for STEP 6
Client in Reclining Position


Facilitator
Left
Right
Client's Maharic Shield
Client's
Maharic Seal
Client

STEPS 1, 2 & 3


Client's Right Foot
Client's Left Foot
Left Palm
on top of
Left Foot
Right Palm
on sole of
Left Foot
Start with Left Foot then do Right
Foot with same Hand Positions

STEPS 4 & 5


6" above Client's Head at
Chakra-10, Kathara Center #12
Left Palm
Right Palm

STEP 6


Central
Kathara
Line
Clear Kathara Centers 12, 11, 8,
5, 2 & 1 via Central Kathara Line
from Chakra-10 at Head
Right
Left
Clear Kathara Centers 3, 6 & 9
via Right Kathara Line from Right
Foot Chakra
Clear Kathara Centers 4, 7 & 10
via Left Kathara Line from Left
Foot Chakra
12
11
9
10
8
6
7
5
3
4
2
1
Right
Kathara
Line
Left
Kathara
Line

MOTIVATION TO HEAL

Healing Facilitation is an art and a science, but most importantly, healing facilitation is an **interrelationship of SOULS.** Egotistical objectives have no place in quality Healing Facilitation. The decision to participate in Healing Facilitation should not be motivated by a desire to prove you have "special abilities" to boast about, nor with the primary motive of gaining **financial profit** from Healing Facilitation endeavors. The energies exchanged in healing facilitation are **FREE TO ALL**, a **DIVINE GIFT** from **the universe, and they belong to all beings equally.** A facilitator cannot rightly request payment from a client for providing what the client already possesses- **Natural Healing Energies.**

In Divine Order, it is appropriate for the facilitator to accept **payment** for the **personal time and energies** invested in **learning and developing facilitation skills,** and for the time spent in active facilitation. It is important that the facilitator understands this subtle difference of **"fair exchange of energy"**. If the facilitator mistakenly assumes they are requesting payment **for healing energies** they supply, they are inadvertently misrepresenting themselves to the client. The client possesses personal healing energies and does not need to purchase such energies from others. The **time and expertise** offered by the facilitator to assist the client in stimulating their own healing energies, is a service worthy of reciprocation. If a client chooses such assistance, the **facilitator** has **legitimate right** to honor their own worth as a being by **requesting reasonable payment or barter** in **fair energetic exchange** for the service they offer. However, if a client is in need of healing facilitation, and has no means of fair exchange at that time, the facilitator should honor the worth of the client by providing assistance of equal value **free of charge.**

In spiritual principal, "making money" is not a legitimate motivation for participating in Healing Facilitation. Seeking to find one's personal **"Divine Right Livelihood"** in **sincere service** to others, which might possibly involve providing client service in Healing Facilitation, IS a spiritually legitimate motivation. Healing Facilitators will discover that when they put the objective of **GENUINE SERVICE TO THE DIVINE** as the **first Priority,** rather than the pursuit of personal monies or status, the **Universe Will Provide.** Facilitators who enter the healing field with hidden personal motivations incongruent with **Universal Laws of Energy**, which imply **equality, respect, reverence** and **balanced exchange of energy** between all beings, will find difficulties emerging in their lives as the personal **SOUL** sets up lessons through which **Universal Principles** become more apparent. There is only **ONE TRUE MOTIVATION** for participation in Healing Facilitation- **the motive is LOVE.**

POSTURES OF LOVE

The Energy-Reality of LOVE

In terms of **Universal Physics**, Love is an **energy reality**, a **STATE OF VIBRATIONAL HARMONIZATION**, or **CO-RESONANCE OF FREQUENCY** that allows an **energetic bridge** to build between individuals. It is through this energetic bridge of frequency that one can assist in running healing energies that will facilitate the healing process of others. Without the sentiment and **FREQUENCY** of **GENUINE LOVE**, one cannot energetically facilitate the healing of another. **LOVE is the essential ingredient in healing,** for it allows the opening of facilitator and client's bio-energetic fields to the **Universal Frequencies** of the interdimensional spectrum. Cultivating the ability to embrace and hold the frequencies of Universal or **OMNI-LOVE** is the responsibility of any true healing facilitator. The emotionally experienced reality of the ***frequency of Love*** takes many forms. In healing facilitation it is important to **assess the most appropriate form of love** to engage with each individual client

Soft Love

Many people respond well to **"SOFT LOVE"**, the kind, gentle, nurturing, soothing love often displayed by mother's comforting their infants. Soft Love works well with client's whom possess some degree of spiritual maturity and who have cultivated the ability to hold some degree of a love frequency within themselves. Soft Love is the appropriate form of love for client's possessing the maturity to accept personal responsibility for themselves, their actions and their emotional reaction patterns, and who do not attempt to manipulate, drain energies from or place blame on others. Soft Love is characterized by **engaged detachment** of the facilitator and is demonstrated through soft-spoken, calm and sincere words and actions that are intended to place the client at ease.

Soft Love is always built up sincerity, kindness, respect and a genuine desire to see the client thrive and prosper. Developing the ability to carry the Soft Love frequency takes time, attention and practice, and requires that the facilitator works to heal personal **internal conflicts**, unresolved issues from **childhood** and **karmic** reaction patterns that disrupt the Soft Love vibration. Soft Love is a **vulnerable love** in that it necessitates one to show the self as it is, honestly expressing personal feelings tempered with kindness. Soft Love **is not approval seeking**, it is rather genuine, honest and **self-generated**. Soft Love requires **love** and **respect** of the self and others mutually. It is built upon a level of spiritual maturity in which it is understood that personal value is implied by the fact of existence and is not determined by the approval or **validation** of others outside of the self and the personal relationship to the Divine. The ability to carry the Soft Love frequency emerges through **spiritual integration, personal healing** of internal conflicts and power struggle issues and **intentional application of kindness and mindfulness.**

Tough Love

Soft Love does not facilitate healing on all occasions. Certain clients who come to a facilitator for healing assistance bring with them a great need for **emotional healing** and development of spiritual maturity. They may demonstrate demanding, arrogant or pushy attitudes and refuse to accept responsibility for their personal actions and resulting consequences. Most often such individuals carry deep wounds from childhood or from reincarnational bleed-through. Because they are **wounded within,** they have not yet developed the self-control or maturity necessary to treat themselves or others with kindness, respect or love.

Individuals who display unreasonable behaviors or attitudes pose quite a challenge to the love-based healing facilitator. If they are approached with Soft Love, the facilitator will often find themselves as a scape goat for the individual's personal problems, may have their energies and time excessively **drained** by such clients and might possibly be subjected to outright verbal or physical **abuse.** Clients exhibiting such personality traits are struggling within themselves to **gain control** over the various **conflicting portions** of their personal energies, and they tend to objectify this internal conflict resolution in the form of **POWER STRUGGLE** with others.

Personalities trapped within cycles of subconscious self or other-abusive attitude patterns need **love** more than anyone, but most often their behaviors push others away. Intrinsically the behaviors serve to keep the individual sheltered from **self-exposure;** they do not allow others close enough to inspire feelings of vulnerability or lack of self-esteem. Often such personality traits effectively keep the individual from seeing themselves and the inner pain and conflict from which they attempt to hide. To facilitate healing in such individuals without succumbing to their manipulation, aggression or abuse requires that the facilitator adopt a posture of **TOUGH LOVE.** In Tough Love the facilitator clearly establishes **personal boundaries** in their own mind as to what treatment they will and will not accept. If the client crosses those boundaries the facilitator **assertively addresses the issue** with the client, requests that the offensive behavior cease and provides **CLEAR CONSEQUENCES** as to what will occur if the offense continues. The Tough Love approach is rendered from a base of **Soft Love** and **Omni-Love,** but it is strengthened with **Self Love** on behalf of the facilitator. The facilitator recognizes that they are only assisting the client to continue with the self-destructive patterns by condoning or allowing offensive behavior, and chooses to **love the client enough** to **confront the pattern** so that it may begin to release. In **lovingly, calmly,** but **firmly confronting** poor behavior and **setting clear boundaries** and **consequences,** the facilitator assists such clients to temporarily find a new pattern of action because the old one does not work for manipulation in this instance. The Tough Love approach frequently requires facilitators to demonstrate that they hold their own power, even in the face of client disapproval. Tough Love is an ability of **personal empowerment** worth cultivating for personal and client healing.

Self Love

In healing facilitation **Love** is the essential ingredient. All love begins with the **Divinity Within the SELF.** You will be able to transmit the frequency of love to others in direct proportion to your ability to hold the frequency of love within yourself. If you do not recognize your intrinsic value as a **Divine Being** and seek validation of your existence through external sources such as achievements, status or other-approval, you will likewise project these sentiments into your love relationships with others. If a client does not meet the external standards of validation that you have placed on yourself to determine your personal worthiness of love, you will have difficulty not falling into **judgement** of the client.

Judgement and **love** cannot transmit through the human body at the same time. Judgement creates an **energy reality** of separation or **Non-Resonant Frequencies** of energy, whereas Love creates the **Co-resonance of Frequencies** needed for open flow of Universal Energies for healing facilitation. If one can realize that **LOVE IS THE ONLY CONSTANT** and that all conditions of judgement change, it is easier to cultivate the innate ability to fully hold the frequency of Love. Though **ASSESSMENT** of conditions, actions or attitudes is useful and necessary, such assessment can be rendered through **"separating the person from the action".** You can judge the effectiveness or value of the **action or idea** without assigning a **value-judgement** to the **person** to which it is attached.

If the healing facilitator can feel love, reverence, respect and honor for the **Divinity Within Themselves,** they will also transmit these qualities of **excellence in Love** to the client. The quality of Love brought into the healing facilitation experience will directly effect the success of healing assistance given. **Love the Self** and know that all beings possess an **unalienable worth and value** as a living part of the **Divine.** Begin to cultivate this awareness within your personal life and you will greatly increase your effectiveness as a healing facilitator. Love, honor and respect yourself, your feelings, your dreams and your desires, so you may better love those you wish to serve.

Love others as you would love the Self,
and love the Self as you would like to love others.

The Illusion of Martyrdom

People who love themselves do not buy into the idea that they must play **"martyr"** to others in order to be of service. **Martyrdom** implies a belief that you are **lacking in worth,** or must **earn** your worth in being, by relinquishing that which feels of most value to you. It also **undermines expression of the God-Presence** within others, by assisting them to believe that you are so vital to their wellbeing that they cannot function without you. In truth, martyrdom is an **expression of EGO**, most often used by people who feel they are **personally insignificant** in the eyes of the Divine, in order to **give themselves significance** and a **sense of personal power and purpose** for being. People who actively *know* the intrinsic **Spiritual Divinity** within themselves treat that Divinity with honor and respect and do not allow or need others to **depreciate the Self** and its desires in order to prove the existence of a *belief* in personal Divinity.

Martyrdom **does not facilitate healing** within the self or client, as it reinforces the **erroneous belief** in intrinsic **personal unworthiness,** which exists in **direct contradiction** to the **innate God-Presence** that exists in every living thing. Within the energy dynamics of **Universal Law,** natural **balance** is achieved in the flow or **GIVING,** and back-flow or **RECEIVING** of energy. In human spiritual relationships this **balance of energy** is achieved by **mutually valuing** each person in a relationship, through which the natural giving and receiving of energy can be exchanged unimpeded. **Martyrdom impedes the natural flow of energy**; the martyr customarily gives more than receives, which progressively diminishes the martyrs ability to keep open a perpetual flow of energies from the Divine because the martyr does not allow the Self to receive.

Martyrdom is not a demonstration of Love,
it is an exhibit of Love Deprivation.
The remedy for Martyrdom is
OMNI-LOVE.

OMNI-LOVE; Fully Engaging the Love Vibration

The greatest love that can be embodied in human form is **OMNI-LOVE.** OMNI-LOVE is a pure state of vibrational Frequency Co-Resonance between the human identity and the **12 Dimensions** of reality within which the human anatomy is couched. Omni-Love is expressed in human form as **Christed Love** or **Christos Consciousness, the 12th-Dimensional Love** of the **Maharic Level of Identity.**

Christos Love is a state of full Frequency Resonance with **everything existing** in the many universes contained within **12 Dimensions** of the 15-Dimensional System. It is a **transcendent love** that is attached to no thing but is **AT ONE** with **ALL THINGS** in a state of perpetual **Engaged Detachment.** Through Christos-Omni Love, the **SELF** is known as an **extension of God**, or the **Divine Source**; a **temporary mask of form** worn by the **ONE CONSCIOUSNESS** of the Cosmos. All things and beings are known as **simultaneous expressions** of the **ONE-SELF** that is God-Source. From this state of transcendence in love, all activity is understood to **exist within** the reality of LOVE, and all conflict and strife are viewed as the ONE-SELF **progressively expanding the ability of its expressions** to **carry the frequencies of energy** that constitute **ONE-LOVE,** a state of **total vibrational Frequency Co-resonance** with the **Cosmos.**

Activation of the full **12-Strand Silicate Matrix DNA Template** and full integration of the **Mahara Hova Body Avatar Identity** allows for the experiential embodiment and transmission of Christos-Omni-Love. **Embodiment of Omni-love is the goal toward which human evolution moves forth.** Omni-Love is Soft, Tough, and Enduring, honoring **Self** , **Other** and the **Divine** simultaneously. It is the **strongest healing force** of frequency in the 4 Harmonics of Matter Density. Christos-Omni-Love is the **fulfillment** of the **Christos Principle.** Strive to bring Omni-love into your life, and personal and client healing facilitation, and you will assist your higher identity levels to create transformation! Omni-Love is the **natural structure** of reality. **AWARENESS** of Omni-Love is cultivated through **intention** and appropriate use of **personal ~~free~~ will choice** in congruence with the **natural Laws** of the **Unified Field Physics of Consciousness and Creation.**

Through living in Omni-Love all moments are known as Sacred, all beings are known as Blessed and life becomes an ecstatic study in Reverence for Existence.

Postures of LOVE

1. SOFT LOVE
KIND, NURTURING, **GENTLE**

2. TOUGH LOVE
KIND, NURTURING, **ASSERTIVE**

3. SELF LOVE
HONORING THE **DIVINITY** WITHIN **SELF**

4. OMNI-LOVE
HONORING THE **DIVINITY** WITHIN **ALL**
Namaste'

***Omni-Love** is the fulfillment of the **Christos Principle**, the goal toward which human evolution moves forth through progressive activation of the **12-Strand Silicate Matrix DNA Template** and embodiment of the **Avatar** Identity.*

OMNI-LOVE EXERCISE TO AMPLIFY HEALING FACILITATION

EXERCISE

The MAHARA SPACE-COMFORT TOUCH

1. **EXHALE Hierophant Symbol** from behind forehead, down *Central Body Current*, into **Earth's Core** (Chakra 13), then **INHALE** *Hierophant* back up to your **Maharic Shield 12" below feet.** *Spin Hierophant* to *activate* **Maharic Shield** and **Maharic Seal Pillar. INHALE** energy up from your *Maharic Shield* into your **Doradic Sphere** at *Chakra 4.*

2. Breathe slowly and deeply while visualizing a **small faceted Crystal Sphere** in the center of your *Doradic Sphere* at Chakra 4. This is the **Holographic Crystal Sphere**; it represents the station of your inner **AVATAR** identity – this is the **MAHARA SPACE.** Focus your consciousness within the *Holographic Sphere* and feel its reality around you, as if your body is encased within the Holographic Sphere.

3. Observe the interior of the Sphere as a **pale Silver-White mist.** Within the mist now envision a **golden treasure chest**- a treasure you had left for yourself long ago to one-day reclaim. This represents your **Inner Arc of the Covenant** – *a doorway to reclaiming your ancient immortal heritage.* **Mentally command** the lid of your inner *Arc of the Covenant* to lift. As the lid rises **pale rainbow colored light** fills the interior of your Holographic Sphere. Notice now that within the golden box there is a gleaming **Silver Sword**, the Silver Rod of Power that will enable you to more quickly evolve to your eternal state of being.

4. Mentally make the **Silver Sword** *rise from the golden box*, floating above the box in a vertical position. Now call to mind the image of your **body** *as it sits within the physical room.* Imagine *the Silver Sword positioned above the body's head*, directly over **Chakra 7. EXHALE** and **steadily lower the Silver Sword** through the *7th Chakra and down the Central Body Current, through the Maharic Shield and down into* **Earth's core.** Observe the Silver Sword turn into a *Pillar of Pale Silver Light with pale rainbow colors flashing through it.* The **Rainbow Pillar** now *surrounds and runs through your body, raising its frequency while lowering its vibration*, lifting your body cells into a **less-dense state of matter.** Feel your body growing lighter and lighter as the Rainbow Pillar slows the spin-rate of your matter particles, making you more and more electric- more light.

5. As you feel the sensations of your density lessening, **imagine that your body is beginning to glow with Pale Silver light** – the *Pre-matter Liquid Light* of dimensions 10, 11 and 12. Feel the *features of your face and the contours of your body begin to melt* into a **Silver, 2 –dimensional fluid body form.** The form of the body still remains but it has been returned to its **first-density state**- the **Silver Liquid Light holographic form of the avatar identity.** Know yourself now as this avatar identity and feel the essence of **pure love** and eternity flow through you. **Know yourself as this essence of Divine Love and Eternal Light.**

6. Now **INHALE** and draw the **Rainbow Pillar into the Holographic Sphere** at *Chakra 4*, visualize the base pulling up from Earth's core and the portion above your head simultaneously *contracting into the Holographic Sphere.* **EXHALE** the energy of the *Rainbow Pillar* fully into the *Holographic Sphere* and observe the **Holographic Sphere become a radiant Silver ball of Liquid Light stationed with your Doradic Sphere** in the Heart Chakra.

EXERCISE: Continued
THE *MAHARA SPACE-COMFORT TOUCH*

7. **You may now transmit the frequencies of the 4th-Harmonic, dimensions 10, 11 and 12, to serve as a healing force for others.** You may transmit this energy into your environment directly through the **4th Heart Chakra**, where it will enter the Unified Field at the 4th-Dimensional astral plane. You may use the breath to move the Holographic Sphere down into the **3rd Chakra** *for 3rd-Dimensional transmission* into the *Earth's atmosphere* and the *Mental Body* levels of people's Bio-energetic field. You may transmit through **Chakra 2** into the Telluric or *Elemental Kingdom* of the planet and into people's 2nd-Dimensonal *Emotional bodies*. Or you may transmit the frequencies of the Silver Sword through the **1st Base Chakra**, for *sacred bonding in intimate relationship*, or to *raise the frequency and lower the vibration* of the *molecular and sub-atomic fields* around you. To transmit the frequencies of the Silver Sword through the chakras, simply use the **EXHALE** breath to move the Silver Light "charged" **Holographic Sphere down** to lower chakras, inhale and use the next **EXHALE** to *push the frequency outward* from the selected chakra into the environment. Use the **INHALE** breath to move the *Holographic Sphere* up through the chakra system. *Always move the Holographic Sphere up or down along the* ***Central Body Current****, to which the core of each chakra is attached.*

8. **You may also transmit the frequencies of the Silver Sword through APPLIED TOUCH – *THE COMFORT TOUCH*** -to amplify specific healing facilitation functions and to establish a more harmonious rapport with other people and the nature kingdoms. Simply visualize the Silver Liquid-Light charged **Holographic Sphere** at the center of your **Doradic Sphere** in the **4th Chakra**. Activate your **Doradic-1 current** via the **Maharic Shield and Seal**, then visualize the *Silver Liquid Light from the Holographic Sphere combining with the Green-Violet-Silver Doradic-1 current* as you **EXHALE** the current into the **Doradic Cords** in the arms and into the **Doradic Balls** in the palms. *This application is especially useful to help Clients relax during sessions, or to comfort others when they are in a state of stress, unbalance or illness.*

   Once your current is moving into the Doradic Balls, **EXHALE** the current through the **Right palm.** *Place the* ***Right palm*** *gentle and briefly over the* ***Client's rear Chakra 2****, or touch them gently on the* ***left shoulder****.* The amplified *Doradic-1 current* will move into the *4th-Dimensional astral-body field*, and move its way into the *mental, emotional and physical bodies* from there. **The COMFORT TOUCH of the MAHARA SPACE can be applied to infants, children, older persons, animals and plants to comfort them and support their general well-being.**

PROFESSIONAL USE OF THE KATHARA BIO-SPIRITUAL HEALING SYSTEM PROGRAM – THE KATHARA ALLIANCE

The Kathara System introduced in **The Kathara Bio-Spiritual Healing System ™ Level 1 Workshop & Course Manual with Introduction to The Kathara Bio-Healing System™ Level 2** is destined to become a ***12-level program*** that is focused on "whole-being healing through progressive biological and spiritual awakening". Kathara is as much a course on (non-denominational, dogma-free) **Spiritual Integration Mechanics** as it is a Holistic Healing course.

An individual completing training in the **Kathara Level-1 Bio-spiritual Healing System** delivered by a Certified Kathara Alliance Instructor, will receive a **Certificate of Completion**, which recognizes the person named as attending and receiving training in the Kathara Level One Bio-Spiritual Healing System.

If you desire to practise the ***Kathara Bio-Spiritual Healing System***™ in a regular, professional capacity through Client Service, you may use the techniques provided within this Kathara Healing Manual to begin. Prior to professional use, it is suggested that one becomes a Certified member of the **Kathara Alliance** through the ***Azurite Press MCEO (World-wide Consulate***) and its appointed representatives.

The **Kathara Alliance** is a group of dedicated spiritual healing Practitioners and Instructors who have demonstrated a thorough understanding of the Theory and Practice of the **Kathara Bio-Spiritual Healing System**™ and the Maharic Recoding Process, as deemed necessary by the **Azurite Press** for professionalism in the practice of Spiritual Healing Facilitation and Instruction.

All members of the ***Kathara Alliance*** are **Certified Kathara Healing Practitioners and Instructors,** and are permitted to practice Kathara Healing facilitation as **SPIRITUAL SERVICE.** For the protection of both Client and Practitioner, as well as the ethics inherent to the Teachings themselves, Kathara Healing is to be promoted, explained and practiced as **a non-diagnostic spiritual healing enhancement service only** and not as a replacement for traditional medical diagnosis or treatment.

Certification in the **Kathara Alliance** as an **Independent Spiritual Healing Practitioner and Instructor** of the **Kathara Bio-Spiritual Healing System**™ requires formal application, including a written open-book examination and video presentation by the applicant. The examination is intended to reveal areas in which applicants may need to further strengthen understanding of and personal relationship to the practice of Kathara Healing Facilitation and Instruction within the parameters of Excellence recognized as intrinsic by the Azurite Press MCEO.

All Instructors and Practitioners must be CERTIFIED to conduct **public presentation** of copyright materials contained in this, the authorized Kathara Bio-Spiritual Healing System Manual. To uphold standards of Professionalism and Excellence in practice, the Azurite Press MCEO **cannot** recognize **Non-Registered Facilitators or Instructors** as active participants in the ***Kathara Bio-Spiritual Healing System Program.*** Obviously, non-certified Facilitators may use this program and its applications for their own **personal and spiritual enrichment. The Azurite Press MCEO authorizes only Certified Practitioners and Instructors** to professionally conduct Client Sessions.

With regards to teaching the program there is a distinction between 'Teaching' and 'Sharing'. **Teaching** is defined as formal presentation of the materials (following protocols described in the **Kathara Bio-Spiritual Healing System™** Manual and communications to Kathara Alliance applicants and members) in the form of a seminar/ workshop and payment is made by attendees. To teach the Kathara Bio-Spiritual Healing System™, one needs to be a member of the **Kathara Alliance**. '**Sharing**' is defined as leading a study group where attendees are not expected to pay (it would not be inappropriate to accept small donations if offered). To share one does not need to be a member of the Kathara Alliance but group size should be limited to less than 12.

Within the **Kathara Bio-Spiritual Healing System™** there are specific pages for Kathara Alliance Instructors to use in their classes. The Instructors pages are identified by having a number at the *top* of the page (as well as the regular number at the bottom). These are the only pages that can be photocopied for teaching purposes. Only certified Kathara Alliance members (or a Kathara Alliance applicant who is delivering and recording a workshop for assessment purposes) are authorized to photocopy these pages.

The easy-reference **Instructor's pages** need to be sequenced in the order denoted by the number at the *top* of the page. These pages have been carefully sequenced to facilitate delivery and learning of the materials. Learners' needs, including varying learning style preferences, were very much considered when preparing the text and visual presentation of these teaching materials. In terms of frequency, the learning process can be described as when previously dormant Scalar Standing Waves in the personal shields are stimulated and activate('switch on'). As frequency is accreted (by progressive exposure to, and interaction with, the materials) the scalar waves in the personal shield self –sustain (we would say the person has 'learned' the material). The specific sequence of the pages are pre-set to create optimum frequency accretion in the personal shields of learners *even if this is not immediately perceived or understood by the learner*. Therefore it is imperative that these pages are used in the delivery of this program and the instructor remains true to the given sequence.

As Independent Spiritual Healing Facilitators and Instructors, all Certified Facilitators and Instructors are expected to accept full personal responsibility and legal liability for the practice and application of the **Kathara Bio-Spiritual Healing System™.** Certified Facilitators-Instructors are **not required** to pay dues, royalties or revenues to the Kathara Alliance/APMCEO for use of this program other than the cost of initial personal **Training-Registration** and obtaining supplies of **Session Manuals, Certificates and Registration Examinations** for the professional Instruction-Certification of others.

THE KATHARA ALLIANCE CERTIFICATION AND COMPETENCY REQUIREMENTS

The Certification Program is designed to enable the applicant to fully demonstrate his/her understanding of the material in a way that maintains the level of integrity and purity of the Program desired of the Kathara Alliance. This also ensures the Student attains a desired level of understanding in taking the workshop. The requirements of Certification are designed to protect the integrity of the material, those who participate with it, and the rights and responsibilities of all concerned.

Certified Kathara Practitioners and Instructors must not only be knowledgeable in the practice and teaching of Kathara, but are also asked to commit to the behavioral guidelines originating from the Covenant of Regent Consulate of the Melchizedek Cloister Emerald Order (MCEO). In this way those seeking out a Kathara practitioner can reasonably expect the highest integrity in both the teachings and in the individuals with whom they are relating.

Certified Kathara Alliance members are in no way affiliated with the MCEO Vehicle, the Azurite Press and should at no time state or imply such representation. Kathara Alliance members are independent Practitioners who offer local, community-based Kathara Healing Level courses and facilitation for individuals.

PLEASE NOTE: The APMCEO & Kathara Alliance **reserve the right** to **revoke** any Kathara Alliance Certification and Rights of Association of Certified Facilitator-Instructors for ***any*** reasons of: *Misuse, misrepresentation and false claims pertaining to this Kathara Program; inappropriate treatment of APMCEO staff, clients or participants in Kathara Healing Programs; dishonest or unethical behavior and practices, and racial, gender, or religious discrimination of clients and participants or Kathara Alliance Members.*

For further information on the Kathara Alliance certification process visit our website at http://www.azuritepress.com/kathara/kathara_application_proceedures.html or contact

In the U.S. and Canada: Sandy Sayles, 8527 Cool Water Ct., Antelope, CA 95843 - email - siepearl@comcast.net **OR** Melissa Fathman, 855 W. Dillon Rd, Apt. H306 - Louisville, CO 80027 - email - mfathman@yahoo.com

Rest of World Office: Hilary Lyons 341A Green Lanes, Palmers Green, London N13 4TY, U.K. hilary.lyons@virgin.net 07970770404

THE 6-STEP MAHARIC RECODING SESSION

Before Client Arrives: ***Technique # 1***- Activate Your Mentor. Conduct ***Mahara-Space-Comfort Touch Exercise*** and remote-request permission from client's ***Rishi*** identity level to apply **Comfort Touch** when client arrives. Create a calm, pleasant environment where you will not be interrupted by phone or other distractions. Optional: Sing 3 rounds of the ***Ariea-Khum-Nar'A* toning** to amplify personal healing and DNA Template activation during healing facilitation session.

When Client Arrives: Apply Comfort Touch if Rishi gave remote permission. Sit with client and review terms of the ***Client Agreement Form*** and secure client's signature on form. Offer client the option of audio-taping the session for client's at-home review.

6-Step Technique Application Sequence- *Maharic Recoding Session*

1. ***Technique # 2*-The Maharic Seal and the Liquid Light Cleanse** *to seal and align personal bio-fields.*

2. ***Sequence-1 Kathara Points massage***- first your points, then client's points, *to open Kathara Lines.*

3. ***Technique # 3*- Opening the Healing Channels** to activate your *Doradic-Phase-1* healing current and ***Technique # 4*- Amplifying Inner-Audio-Visual and Kathara Scan** to locate miasms for healing in client's Kathara Grid.

4. ***Technique # 5*- The Maharic Infusion** to activate client's Maharic Shield and Seal, recode client's Kathara Grid to the Maharic Shield and clear miasmic buildups.

5. **Optional:** Apply **light touch-massage** to miasmic areas, or employ other healing therapeutics after Maharic Infusion.

6. ***Sequence-2 Kathara Points massage*** on client to revitalize outer body systems and close Kathara Lines. Allow client to rest a few minutes before leaving. Answer any client questions and allow time for client to discuss experience if desired.

When Client Leaves: To ensure clear bio-fields, while Doradic-1 Current is still running, draw energy up from Earth's Maharic Shield and run Maharic Current through your Kathara Grid and body, up to Chakra-14 and back down to Chakra-13, then push a Pillar of Silver Light out of Chakra-4 and EXHALE it to release it around body into auric field. Next massage *your* **Sequence-2 Kathara Points** to revitalize bio-field systems and close Kathara Lines.

CHAPTER 4 HIGHLIGHTS

GENERAL KATHARA HEALING FIELD WORK

- Activation of any **Triadic Healing Current** requires temporary release of corresponding **Signet Star Crystal Seals** in the **Kathara Level-2 Crystal Seals Grid.**
- **Maharic 12th-Dimensional Frequency** is required to **manually release** the **Signet Star Crystal Seals** to activate **Triadic Healing Currents. Kathara Healing** utilizes **Maharic Frequency** to activate interdimensional **Triadic Healing Currents** for more powerful healing support.
- Most healing systems have not used **Maharic Current** because the **Planetary Templar Complex** could not run 12th-Dimensional Maharic Frequency for over 200,000 years, until January 2000.
- Release of the **Signet Seals** also activates dormant Strands in the **DNA Template** and releases the **Cranial-Sacral Seals** on the **Kundalini Energies.** Kathara Healing represents advanced, **12-Dimensional Kundalini Healing.**

OPENING THE HEALING CHANNELS

- Triadic Phase Currents are activated in the body by using **Maharic Frequency** from the **PBIS** to release the **Signet Seals** of the **Internal Templar Complex**, which allows higher dimensional frequency to run through the **physical body system** for transmission.
- Triadic Phase Currents are composed of **3 interwoven frequencies**, the **Maharic Frequency**, plus a chosen **dimensional frequency** and its corresponding frequency from **one Harmonic up**.
- Triadic Phase Currents are **directed** by their corresponding **Color Cap Stone**, the **Primary Wave Length** of the dimensional frequency band from which the current is drawn. **Kathara Level-1** activates the **1st Triadic Phase Current**, the ***Silver (D-12) + Green (D-4) + Violet (D-7)*** **DORADIC PHASE-1 Current.**
- **Doradic Current** is activated through the **Maharic Shield,** then **collected** in the **4th Chakra** *DORADIC SPHERE*, projected down the *DORADIC CORDS* in the **arms** and into the *DORADIC BALLS* in the **Palm Chakras** for **DIRECT INDUCTION** of frequency transmission in healing facilitation.

PALM CHAKRA POLARITY

- The **Palm Chakras** are **Secondary Chakras** located in the **Palms of the Hands.** Like all Chakras, they function as **Black-White Hole Sets** for **transmitting** and **receiving energy** between the personal Manifestation Template and the dimensional Unified Fields of energy.
- The Palm Chakras are **double vortices** of energy, with **one spiral** exiting the **Palm** and its **corresponding spiral** exiting the **back of the hand.** The **2 Spirals** of the Palm Chakras are linked by a **Crystal Seal** at the center point where the 2 vortices meet. In one Palm Chakra, one spiral rotates **clock-wise**, is **Base Electrical** and **transmits energy** out of body, and the other spiral rotates **counter-clock-wise**, is **Base Magnetic** and **draws energy** into body.
- In **Level-1Kathara Healing** the **RIGHT PALM** is the **TRANSMITTING HAND** and the **LEFT PALM** is the **RECEIVING HAND.** For **transmission,** the **Standard Hand Position** is **LEFT Palm placed over the back of the RIGHT HAND** for pure transmission and **control of specific frequency** transmitted from the **RIGHT PALM.**
- The **RIGHT PALM** is **BASE ELECTRICAL**, the **LEFT PALM** is **BASE MAGNETIC**, but both have **subtle** electro-magnetic capacity.

THE KARMIC-MIASMIC IMPRINT

- To enter manifestation in time, identity enters **cycles** of **SIMULTANEOUS INCARNATION** within the **4 Harmonics of Matter Density** in **12-Dimensions** of the 15-Dimensional **Time Matrix.** The **PRIMAL ORDER Scalar-wave Template** through which an identity enters time is the **Density-5** (dimensions 13, 14 and 15) **RISHIC SHIELD**

- The **Rishic Shield** holds in the Time Matrix the identity of the **Family of Consciousness** from which **incarnates** emerge. The Scalar Patterns of the Rishic Shield represent the tangible **"DIVINE RIGHT ORDER"** in energy and consciousness, for each incarnate manifesting from it. The individual identity must **realign** its **Manifestation Template** with this **Primal Order** to become free from the Time Matrix in full **Ascension.**

- The **Density-4** Pre-Matter Hydro-plasmic **MAHARIC SHIELD** (Dimensions 10, 11 and 12) is the Scalar Template through which identity manifests in the lower-dimensional Densities and which **connects the individual incarnate** to its **Rishic Shield.** The **Maharic Shield** is often called the **PERSONAL CHRISTOS Template,** and it holds the consciousness and **Perfect Primal Order** for all incarnations of an identity in time.

- **"Karma"** is the result of **Free Will choices** made by **incarnates** that involve using personal energies in ways incongruent with the natural **Laws of Universal Unified Field Physics** and the **Primal Order** of the **Christos Template.** Karma creates **scalar-wave distortions** within the Scalar Shields of personal 15-Dimensional Anatomy that **manifest physically** as **energetic clusters** called **MIASMS.**
- **Miasms** are **unintended** groups of **anti-particles** lodged within the particle field of the personal **Manifestation Template** that block and impede the **natural flow of energy** and consciousness into embodiment. **Miasms,** and the misshapen scalar-wave distortions that form them, are the **cause of ALL disease** and dis-harmonic conditions.
- **Health** and Harmonious flow of energy are the **natural conditions** of human design. The **Maharic Shield Personal Christos Template** holds the **Organic Imprint for Health** for all simultaneous incarnates of an identity, and can therefore be used to **clear the Karmic-Miasmic Imprint** from the personal Manifestation Template to progressively restore **Healthful Primal Order.**

- Miasms from **all simultaneous incarnations** manifest within the personal Manifestation Template and within the DNA Template of each, where they become literal **genetic distortions.**
- Each of an identity's incarnates in various time cycles represents one **TIME VECTOR**, which is encoded in the Vector Codes of the **DNA Template.** Karmic-Miasmic **bleed-through** occurs **between incarnates** from different concurrent time cycles through the **living link** of scalar frequency that exists between the **DNA Templates** of simultaneous incarnations.
- The **Karmic-Miasmic Imprint** does not have to be suffered and cleared the "**old fashioned way**" by "walking through the Karma in physical reality". The **Miasmic Imprint** can be cleared **as energy, with energy**, to prevent its manifestation in physical terms via realignment of the **DNA Template** with the personal **Maharic Shield.**
- Any given incarnate can clear the Karmic-Miasmic Imprint by realigning the personal Manifestation Template with the shared Christos Template Maharic Shield. This process is called **MULTI-VECTOR HOLOGRAPHIC RECODING**, which creates **BIO-REGENESIS** of the original 12-Strand **Silicate Matrix DNA Template** of human design and restoration of the **Organic Imprint for Health.**

ATTITUDES AND ETIQUETTE IN HEALING

- **Holographic Recoding** and clearing the Karmic-Miasmic Imprint from the personal Manifestation Template begins with activation of the **Maharic Shield and Seal** in the bio-energetic field and progressive running of 12th-Dimensional **Maharic Frequency** from the **Personal** and **Planetary Maharic Shields** through the **3 Primary Levels** of the embodied **Kathara Grid**; the Level-1 **12-Tree Grid**, Level-2 **Crystal Seals Grid** and Level-3 **Diodic Points Grid.**
- Personal Holographic Recoding begins with consistent use of ***Technique* # 2- The Maharic Seal and the Liquid Light Cleanse**, and is further accelerated by facilitating **Maharic Recoding** in others through running the **Triadic Phase Currents** for **Co-generative Healing.**
- One can facilitate healing in others and amplify personal healing through the using ***Technique* # 5- The Maharic Infusion.**
- The **Maharic Recoding Session** utilizes the combined **Bio-Regenesis Techniques** presented in **Level-1 Kathara Healing** to facilitate **Client Healing Sessions.**

- Professionalism in Healing Facilitation requires an understanding of the **Postures of Love** and a willingness to **cultivate** the ability to hold and transmit **OMNI-LOVE, honoring the Divinity of ALL things and beings.**
- The Primary Postures of Love are **SOFT LOVE, TOUGH LOVE, SELF LOVE** and **OMNI-LOVE.**
- The emotionally experienced quality called **LOVE** is a **REALITY IN ENERGY PHYSICS.** LOVE is a **STATE OF VIBRATIONAL FREQUENCY CO-RESONANCE** that allows **free flow of energy** between consciousness within the Universal Unified Field.
- The human **12-Strand DNA Template** was designed to allow **12-Dimensions of Vibrational Co-Resonance**, the **Christos Consciousness** of the **Maharic Shield**, to embody in human form. **CHRISTOS-OMNI-LOVE** is Vibrational Co-Resonance with all that exists within **12 Dimensions** of the Time Matrix; its embodiment is the **primary goal** toward which **human evolution** progresses.
- Christos-OMNI-LOVE is the **strongest healing frequency** available within the Densities of Space, Time and Matter, and is **essential** for effective **Healing Facilitation** and personal **Ascension.**

CHAPTER 5

INTRODUCTION TO KATHARA LEVEL-2

The Kee-Ra-ShA Induction Process™

Mahara-Merkabic Master Key Healing-Manifesting the Blueprint For Health

Primal Currents, the DNA Sub-Strand Matrix, Merkaba, Psonns, the Trinity Keys and Photo-Dynamic Manifesting

- SPIRITUAL INTEGRATION
- PRIMAL LIFE FORCE CURRENTS-The Kundalini-Antahkahrana, Maharata, Kee-Ra-ShA & Khundaray
- DNA SUB-STRAND MATRIX, FIRE LETTERS, PSONNS & THE TRIBAL SHIELD
- MERKABA &THE SALUTATIONS
- 2 MASTERS KUNDALINI ACTIVATIONS-The Emerald & Amethyst Awakenings
- UNIVERSAL TRINTIY KEYS & MERKABA KEY CODES
- MAHARA MANIFESTING,DNA, KATHARA & PSONNS

TECHNIQUES:

TECHNIQUE # 6: The Maharic-24 Quick Seal
TECHNIQUE # 7: Ps-13 Tribal Shield Activation
TECHNIQUE # 8: Merkaba Salutations
TECHNIQUE # 9: Merkaba Trinity Key Induction
TECHNIQUE # 10: Photo-Radionic Manifesting
TECHNIQUE # 11: Photo-Sonic Manifesting
TECHNIQUE # 12: Kee-Ra-ShA Activation Sequence-Awakening the Flame

Sacred Sciences of the Mu'a Grail Line- *Tools of the Trade*

- **The Maharata-** *Universal Life Force Currents, Kundalini, Antahkarana, Maharata, Kee-Ra-Shay, Khundaray and the Maharic Seal.*
  Field Technique-1: ***Maharic Quick Seal***

- **The Tribal Shield and Cue Zones-** *DNA, Fire Letters, the Sacred Psonns and Cue Zones*
  Field Technique-2: ***Tribal Shield-Cue Zone Activation***

- **The Sacred Salutations-** *Electrical & Magentic Merkaba Activation*
  Field Technique-3: ***Sacred Salutations****- Merkaba Tone Dancing*

- **Expediting Spiritual Actualization -** *Tribal Shield Activation, Emerald and Amethyst Awakening Masters Kundalini Activations, DNA Template Bio-Regenesis, Master Key Codes, Melchizedek Cloister Ordinations*

Universal Life Force Currents

One 15-Dimensional Time Matrix with 5 Harmonic Universes

Universal Life Force Currents
Khundaray**- Three levels, **Primal Sound Field Currents** form **Energy Matrix**. ***Eckatic, Polaric and ***Triadic*** Currents of *Standing Sound Vibration.*
Kee-Ra-ShA'**- Three levels, **Primal Light Field Currents** emanating from Primal Sound Fields form First-Cause *Ante-matter* Density Dimensional Light Field of the ***Time Matrix.
Eckatic-*Blue Flame*-D-13 (Primal Ray from which the 2 other Primal Rays emerge).
Polaric-*Gold Flame*-D-14
Triadic-*Violet Flame*-D-15
***Maharata**- Three levels of frequency, D-10, D-11 and D-12, interwoven together to form the **D-12** Omni-Polar **Universal Christos Field** of *Pre-matter Density* Hydroplasmic **Liquid Light**.
***Antahkarana**- 9 levels of polarized **electro-magnetic** energy frequency that form **3 currents** of 3-dimensional energy called the **Universal Kundalini**, which form lower-frequency **dimensions 1-9**, creating *Etheric, Semi-Etheric, Gross-physical* Matter Densities.



A *Dimension* is a full Frequency Band or repeated sequence of "flashing on and off" of scalar standing-wave points within a morphogenetic field.

Khundaray
Primal Sound Fields

Kee-Ra-ShA'
Primal Light Fields

Maharata (Christos)
Liquid Light Fields

Antahkarana
Universal Kundalini

5 HARMONIC UNIVERSES
in one **15-Dimensional TIME MATRIX**

3 Levels of the non-dimensionalized **ENERGY MATRIX** within which **TIME MATRICES** reside.

Magnetic Repulsion Zones create separation between Harmonic Universes.

All things in manifest existence are perpetually fed **energy** and **consciousness**, in the form of **interdimensional frequency**, via the **Universal Life Force Currents.**

Universal Life Force Currents and the Embodied Kathara Grid Core Template



Electrical ("Male") Merkaba Spirals
Spin Currents CW down from Unified Field, into body and out into Earth body.
Pineal Gland
12
11
9
10
8
6
7
CHAKRA-4
Cranial-Sacral Kundalini Seals
5
3
4
2
Tail Bone
Antahkarana D-1-9
Central Vertical Current
Magnetic ("Female") Merkaba Spirals
Spin Currents CCW up from Earth body, into body and out into Unified Field.
12"
Personal Maharic Shield
Earth's Core
The Maharata (D-10-11-12)
Pre-matter Liquid Light
"Christos Platinum Ray"
Embodies with activation of
12-Strand DNA Template
PLANETARY MAHARIC SHIELD
Polaric Gold Flame
Eckatic Blue Flame D-13
D-14
Triadic Violet Flame D-15
3-6-9 Vertical Kathara Line corresponds to Right side of body.
4-7-10 Vertical Kathara Line corresponds to Left side of body
Kathara Lines
Kathara Centers
1
The Kee-Ra-ShA (D-13-14-15)
Primal Light Field Current.
Embodies with activation of
24-Strand-Plus Indigo Child
Maji Grail Line DNA Template

KATHARA CENTERS

#12 – *The Capstone*
In 10th Chakra
6" above the head

# 11 – *Crown Jewel*
In Pineal Gland
at center of brain

# 9 & # 10 –*The Shar*
In brain
behind ears

# 8 – *Spark of Orion*
In Thyroid Gland
at 8th Chakra

# 6 & # 7-*The Wings*
In shoulder indents
through to back.

# 5 –*Seat of Amenti*
At Navel in
Central Body Current

# 3 & # 4 -*The Dal*
male: Ureters
female: Ovaries

# 2 – *Naum-Yun*
male: Prostate Gland
female: Vagina

# 1 – *Earth Core*
at center of Earth
in 13th Chakra

Universal Life Force Currents enter the body via **Merkaba Fields, Kathara Grid** Core Template, **DNA Template** and **Central Vertical Current,** through progressive activation of the **12-Strand DNA Template.** Embodied Life Force Currents are regulated by the **Cranial-Sacral Seals** located in the **Pineal Gland** at brain Center and in the **First 8 Cells** in the **Tail Bone** at the base of the spine.

Universal Life Force Currents and Level-2 Kathara Crystal Seals Grid & Chakras

Chakras (C & MC)

Star Crystal Seals (S)


Deep Space S12.
MC14
36" above head
18" above head MC11
Deep Space S11
6" above head MC10
MC9
C7
C6
S7
C5
MC8
S6.
S5.
C4
S4.
Central Body Current
Hara Line & Central
Vertical Kathara Line
C3
S9.
S3.
C2
S2.
S1. S15.
C1
MC12
6" below feet
S8
MC13
Earth
Earth Core
S10
MC15
Deep Space S13. S14.

15 Chakras (C & MC)
7 Primary Chakras (C)
C1- Base
C2- Sacral
C3-Solar Plexus
C4- Heart
C5- Throat
C6- 3rd Eye- Pituitary
C7- Crown-Pineal
8 Morphogenetic Chakras (MC)
MC8-Thymus
MC9-Thalamus
MC10- Galactic 1
MC11-Galactic 2
MC12- Earth Star
MC13-Earth Core
MC14-Universal 1
MC15-Universal 2

Universal Life Force Currents

Enter via **Merkaba Fields, Kathara Grid, DNA Template &** Central Vertical Current and are regulated by the **Crystal Seals** to form the **Chakra System, Axi-a-Tonal and Meridians** of energy distribution in the manifest body. As Currents activate in the Kathara Grid, DNA, Crystal Seals, Chakras and body, **frequency and consciousness** from the higher-dimensional fields progressively embodies.

15 Star Crystal Seals

Star Crystal Seals keep human identity & *Auric Levels* dimensionally separate. Control Dimensional *Merkaba Field Axis* & *Angular Rotation of Particle Spin.*

15 Star Crystal Seals (S):
S1. Red Star
S2. Orange Star
S3. Yellow Star
S4. Green Star
S5. Blue Star
S6. Indigo Star (Blue-Violet)
S7. Violet Star
S8. Gold Star
S9. Silver Star
S10. Blue-Black Star
S11. Silver-Black Star
S12 White Star
S13. Turquoise Star
S14. Pale Yellow Star
S15. Magenta-Pink Star

Hova Bodies and Corresponding Identity Stations

(*"Hova"* means *Tri-tonal Scalar Grid*)

1. **Nada Hova** – HU-1 Incarnate Identity -*Taurenic Body* (Subconscious, Instinctual & Reasoning Minds)
2. **Alphi Hova** – HU-2 Soul Matrix – *Doradic Body* (Astral, Archetype & Angelic Minds)
3. **Betcha Hova** –HU-3 OverSoul Matrix – *Metatronic Body* (Ketheric, Monadic & Kertatric Minds)
4. **Mahara Hova** – HU-4 Avatar ID – *Hydronic Body* (Christiac, Buddhaic & Nirvanic Minds)
5. **Raja Hova** – HU-5 Rishi Collective – *Hedronic Body* (Universal Conscious Mind)


Nada Hova
Alphi Hova
Betcha Hova
Mahara Hova
Raja Hova

Universal Life Force Currents form and sustain the "**Auric Field" Levels** of 15-Dimensional Human Anatomy

Auric Level, Chakra and Hova Body Correspondences

Chakras draw energy in from, and transmit energy into, the **Unified Fields** of each Dimension. Each Chakra carries as its **Primary Color** the hue associated with the **wave-length** of the dimensional frequency band to which the Chakra corresponds.

Each Chakra corresponds to a level of the *Auric Field* and one *Axi-A-Tonal Line*. Each ***Hova Body*** corresponds to a **set of 3 Chakras** and contains 3 dimensionalized frequency bands that form the dimensional levels of **Auric Field.**


MC14
MC11
MC10
MC9
C7
C6
C5
MC8
C4
Central Body Current
C3
C2
C1
MC12
MC13
Earth
Earth Core
MC15
Nirvanic Body - MC12
Buddhaic Body - MC11
Christiac Body - MC10
Keriatric Body - MC9
Monadic Body - MC8
Ketheric Body - C7
Angelic Body - C6
Archetypal Body - C5
Astral Body - C4
Mental Body - C3
Emotional-Elemental Body - C2
Etheric Body - C1
D-12 FREQUENCY
D-11 FREQUENCY
D-10 FREQUENCY
D-9 FREQUENCY
D-8 FREQUENCY
D-7 FREQUENCY
D-6 FREQUENCY
D-5 FREQUENCY
D-4 FREQUENCY
D-3 FREQUENCY
D-2 FREQUENCY
D-1 FREQUENCY
Axi-A-Tonal Line 1
Axi-A-Tonal Line 2
Axi-A-Tonal Line 3
NADA HOVA BODY
Axi-A-Tonal Line 4
Axi-A-Tonal Line 5
Axi-A-Tonal Line 6
ALPHI HOVA BODY
Axi-A-Tonal Line 7
Axi-A-Tonal Line 8
Axi-A-Tonal Line 9
BETCHA HOVA BODY
Axi-A-Tonal Line 10
Axi-A-Tonal Line 11
Axi-A-Tonal Line 12
MAHARA HOVA BODY
12 Inner Auric Levels
3 Universal Auric Levels
(correspond to D13 through D15)

7 Primary Chakras (C)
C1- Base
C2- Sacral
C3-Solar Plexus
C4- Heart
C5- Throat
C6- 3rd Eye- Pituitary
C7- Crown-Pineal
8 Morphogenetic Chakras (MC)
MC8-Thymus
MC9-Thalamus
MC10- Galactic 1
MC11-Galactic 2
MC12- Earth Star
MC13-Earth Core
MC14-Universal 1
MC15-Universal 2

Primary Colors (wave spectrum)
C1- Red
C2- Orange
C3-Yellow
C4- Green
C5- Blue
C6 – Indigo
C7- Violet
MC8-Gold
MC9-Silver
MC10- Blue-Black
MC11-Silver-Black
MC12- White
MC13- Pale Turquoise
MC14-Pale Yellow
MC15- Magenta-Pale Pink

Universal Life Force Currents and the Embodied **Shields, Signets** and **Kathara Grid**


Chakra 10
6"
C
Chakra 4
B
Chakra 1
A
Chakra 12
12"
D

***Hova Bodies* are spherical scalar wave grids that form tissue capsules between each 3-Dimensional Harmonic of Manifestation.**

***Signets* are the core points of consolidated frequency that hold the programs for the Scalar grid SHIELDS upon which the Hova Bodies manifest.**

The Signets and the Shields are the core of Kathara Level-2 Crystal Seals Grid

As **Universal Life Force Currents** activate in the Kathara Grid, DNA, Chakras, Auric Levels & body, natural awakening of the dormant **Scalar Shields** occurs.

When activated, each SHIELD forms a rotating disc of scalar waves that emanate out from the body on a horizontal plane.


12
11
9
10
8
6
7
Kathara Level-1 12-Tree Grid
5
3
4
2
1
Shields
12
D
11
10
9
C
8
7
6
B
5
4
Shields
A
3
2
1
Signets

The First 4 SHIELDS each with 3 SIGNETS and correspondence to the Kathara Centers of the Level-1 12-Tree Kathara Grid.

HORIZONTAL SHIELDS

A. TELLURIC SHIELD
Nada Hova Body
B. DORADIC SHIELD
Alphi Hova Body
C. TEURIC SHIELD
Betcha Hova Body
D. MAHARIC SHIELD
Mahara Hova Body
E. RISHIC SHIELD
Raja Hova Body
(vertical- not shown)

The Silicate Matrix 12 Strand DNA
Primary Correspondences to Subtle Body Anatomy

Silicate Matrix 12-Strand DNA
Primary Correspondences to Subtle Body Anatomy.

DNA Strand #	Dimension #	Axi-A-Tonal Line	Chakra & *Seed* Crystal Seal	Auric Field Level
NADA HOVA BODY – TELLURIC SHIELD				
1	1	1	1	Etheric Body
2	2	2	2	Emotional Body
3	3	3	3	Mental Body
ALPHI HOVA BODY – DORADIC SHIELD				
4	4	4	4	Astral Body
5	5	5	5	Archetype Body
6	6	6	6	Angelic Body
BETCHA HOVA BODY – TEURIC SHIELD				
7	7	7	7	Ketheric Body
8	8	8	8	Monadic Body
9	9	9	9	Keriatric Body
MAHARA HOVA BODY – MAHARIC SHIELD				
10	10	10	10	Christiac Body
11	11	11	11	Buddhaic Body
12	12	12	12	Nirvanic Body

Three 3-Dimensional Kundalini Currents compose the 9-Dimensional Antahkarana **The Telluric, Doradic and Teuric Kundalini Currents**

Maharata D-10-11-12 Christos Current

As **Universal Life Force Currents** activate within the body, the **dimension of consciousness** contained in each **Auric Field Level** progressively embodies.

15-Dimensional Levels of Identity, DNA and Indigo Children



Progressive activation of dormant 12-48 Strand DNA Template creates activation of corresponding Universal Life Force Currents in body.

A *Dimension* is a full Frequency Band or repeated sequence of "flashing on and off" of scalar standing-wave points within a morphogenetic field.

The **DNA** represents fixed scalar-wave sequences/" **Fire Letters**" that correspond to each dimension/frequency of consciousness. Consciousness enters time by fragmenting into the scalar fields of the dimensions. Freedom from space-time-matter is achieved by reassembling the dimensional Fire Letters, progressively expanding the consciousness and DNA, & transmuting the body matter out of density. There are **48 Primary Fire Letter Sequences**/DNA Strands in full transmutation, through which the consciousness expands into non-dimensional levels of **Ascended Mastery**.

The 15-Dimensional Time Matrix holds 30 Fire Letter Sequences.

The Kee-Ra-ShA (D-13-14-15) Primal Light Field Current. Embodies with activation of 24-Strand-Plus **Indigo Child** Maji Grail Line DNA Template

3 Levels of Identity focused in the **Energy Matrix.** 3 levels of the Energy Matrix hold 18 Fire Letter Sequences

The 30 Fire Letter Sequences of the *Time Matrix* + 18 of the *Energy Matrix* form the **48 Codes of Ascension**

The Maharata (D-12 Christos) Pre-matter Liquid Light "Platinum Ray" Embodies with activation of 12-Strand Angelic Human DNA Template

3 Levels of Ascended Mastery
Khundaray
Primal Sound Fields
Emerald Sun
48 strand DNA
Source
Double-Diamond Sun
24 strand DNA
Kee-Ra-ShA'
Primal Light Fields
Maharata (Christos)
Liquid Light Fields
HU-5
Rishi
HU-4
Avatar
Diamond Sun
12 strand DNA
D12
D11
D10
D9
HU-3
Over Soul
D8
D7
D6
D5
D4
HU-2
Soul
D3
D2
D1
HU-1
Incarnate
Triadic Violet Flame
Polaric Gold Flame
Eckatic Blue Flame
Source
Eckatic "Blue Flame" Sound Field
Polaric "Gold Flame" Sound Field
Triadic "Violet Flame" Sound Field
Antahkarana
Universal Kundalini
Primal Light Fields
TRIADIC LEVEL
POLARIC LEVEL
ECKATIC LEVEL
Primal Sound Fields

The *Oraphim* genetic imprint of the **Indigo Children** allows more rapid re-assembly of the **48 DNA Fire Letters**/ scalar-wave grids, creating the potential to embody the *Avatar* identity and open the consciousness to *Ascended Master* Identity Levels. **Indigo Children are Avatars and Ascended Masters waiting to awaken.**

All Angelic Humans possess a minimum of **12-Strand** DNA potential through which activation of the **Maharata Current** and embodiment of the D-12 Christed Avatar identity can take place.

The Reality of Spiritual Integration

- **Spiritual Actualization** is as much a function of **Divine Physics** as it is a product of **Divine Consciousness.** The natural Primal Order of **Universal Structure** sets the **Templates of Manifestation** to which consciousness **must conform to** enter the experience of manifest expression within a space-time-matter system.
- The personal Christos **Maharic Shield** Manifestation Template and the Christos **Tribal Shield** Species Manifestation Template are **microcosmic replicas** of the macrocosmic Primal Order upon which Universal and Cosmic structure are built..
- The Personal D-12 Christos Divine Blueprint Maharic Shield connects each Individual Christos self to the **larger** D-12 Christos Divine Blueprint of the **Species.** The D-12 Christos Divine Blueprint is called the **TRIBAL SHIELD.**
- To understand the realities of **personal Spiritual Integration and Actualization,** in order to **fulfill our personal life purpose,** it is important to comprehend the basic **Primal Order** structures of energy, the **personal D-12 Maharic Shield** and the **D-12 Species Tribal Shields,** through which our consciousness manifests in time.
- The secrets to **reclaiming the Divine Birthrights and Responsibilities** of Angelic Human heritage are hidden within the realities of the **Tribal Shield** and the specific **"Fire Letter Sequences"** of the Tribal Shield that manifest within and **govern the function** of the Angelic Human **DNA Template.**
- The **key to Spiritual Actualization** is activation of the dormant personal 12-Strand DNA Template. The **most rapid means** of activating the dormant Angelic Human 12-Strand DNA Template is through **activation of the Tribal Shield,** the Species D-12 Christos Divine Blueprint, which represents the **CORE PROGRAMMING** of the personal D-12 Maharic Shield.

The Silicate Matrix 12-Strand DNA Template with Hova Body, Scalar Shield and Identity Level Correspondences

The Morphogenetic Field Scalar-wave Template for the Original Human Genome


Flame Codes of the Tribal Shield
12-Strand DNA Template
12 Fire Letter Sequences
144 Fire Letters
1728 Vectors Codes
Maharic Shield
Mahara Hova Body
Avatar "Christed" Identity
Chakras 10-12
Mahunta Phase Merkaba
(12 Dimensional Merkaba)
Telluric Shield
Nada Hova Body
Incarnate Identity
Chakras 1-3
STRAND-12
STRAND-1
STRAND-2
STRAND-3
STRAND-4
STRAND-5
STRAND-6
STRAND-7
STRAND-8
STRAND-9
STRAND-10
STRAND-11
FC-12
FC-1
FC-2
FC-3
FC-4
FC-5
FC-6
FC-7
FC-8
FC-9
FC-10
FC-11
A
E
A
E
A
6-Particle and 6 Anti-particle Fire Letters Per Strand.
1 Strand =12 Fire Letters or 1 Fire Letter Sequence or 144 Vector Codes (selves)
Doradic Shield
Alphi Hova Body
Soul Identity
Chakras 4-6
Hallah Phase Merkaba
(6 dimensional Merkaba)
Teuric Shield
Betcha Hova Body
Over-Soul Identity
Chakras 7-9
Quatra Phase Merkaba
(9Dimensional Merkaba)

12-Cycle #1 Particle Universe
12 Base Codes per Strand = ●

12-Cycle #2 Anti-Particle Universe
12 Acceleration Codes per Strand = ○

12 FIRE CODES between Strands = ✡

(E) Emerald Kundalini Awakening releases Fire Codes 1 & 4 (A) Amethyst Kundalini Awakening releases Fire Codes 7,10 & 12

(Diagram presents simple conceptualization of DNA Strand Template orientation, not actual geometrical arrangement of wave-form structure and observable strand interrelationship.)

Activating the Tribal Shield

- The 12-dimensional **Tribal Shield** is the dormant **Species Divine Blueprint** within the **DNA Template core** of the Angelic Human races of the 4 Evolutionary Rounds. The frequencies of energy and dimensions of consciousness of the **1728 simultaneous selves** of the Personal Eternal Christos Identity can be **activated in one incarnation** through **sequential activation** of the **Fire Letter Sequences** or **"Flame Codes'** of the **Tribal Shield.**
- The "Flame Code Fire Letters" within the DNA Template are the **DNA Signet Codes** that correspond to Earth's **12 Primary Star Gates** and the **Planetary Shields** through which the planetary body manifests. The Flame Codes serve as the core foundation of the personal 12-Strand DNA Template.
- The DNA Template Flame Codes of the Tribal Shield allow for the **Primal Life Force Currents** of the Density-5 (dimensions 13-14-15) **Kee-Ra-ShA Primal Light Fields** and the **Khundaray Primal Sound Fields** from the Energy Matrix, beyond the 15-Dimensional Time Matrix, to embody more fully within the Angelic Human form.
- A **Fire Letter** is a **fixed point of consolidated frequency** that holds specific frequencies consciousness into manifest form. The **Manifestation Templates** or Divine Blueprints of **all things** manifest are built upon **intricate patterns** of interwoven Fire Letters called **Fire Letter Sequences.** The Flame Codes of the Angelic Human personal DNA Template and Species Tribal Shield are composed of the **same Fire Letter Sequences** that make up the Divine Blueprint of **Earth's Planetary Shields.**
- Activation of the Tribal Shield sets in motion simultaneous "firing" or activation of the **144 Fire Letters (12** Fire Letter **Sequences)** of the 12-Strand DNA Template, expediting the natural evolutionary process of Soul, Over-Soul and Christos Avatar Identity Integration, through progressively opening the "Trans-time DNA Template Star Gates".
- Activating the 12-Strand DNA Template allows the D-12 frequency of the **Universal "Christos" Maharata Current** to activate within and run through the Angelic Human DNA Template and into the Earth's **Planetary Shields.** Activation of the **Maharata Current** within **groups of Angelic Humans** on Earth allows for **collective anchoring** of the **D-12 Planetary Christos Divine Blueprint,** the **Shield of Aramatena,** to achieve fulfillment of Angelic Humanity's **Sacred Commission** of the **Planetary Christos Realignment Mission.**

The Tribal Shield- *Species D-12 Christos Divine Blueprint*

The Angelic Human 12-Strand DNA Template contains
6 Fire Letter Sequences from particle universe 12-Cycle
plus 6 Fire Letter Sequences from anti-particle 12-Cycle
= **12 Fire Letter Sequences** or **144 Fire Letters** from the
Two Planetary 12-Cycles of the Cycle of the Rounds.
(1 12-Cycle = 4 Evolutionary Rounds)

The **Tribal Shield** connects our personal D-12 **Maharic Shield** Divine Christos Blueprint to the greater Christos Blueprint of the Angelic Human **Species. 144** Fire Letters (12 Fire Letter *Sequences*) of the **Tribal Shield** make up the **core program** of the Human **12-Strand DNA Template.**


12
216 selves in
Round-1
Palaidia Urtite-Cloister races
798,000BC-208,216BC
72 DNA Vector Codes
6 Fire Letters
1/2 Fire Letter Sequence
8
9
10
11
13
Contains 12-Cycle #2
Of parallel universe, with
The other ½ of DNA Strand
Template Fire Letters
216 selves in
Round-2
Urtite-Cloister races
208,100BC- 75,000BC
6
7
216 selves in
Round-3
Cloister races
73,000BC-future
2
3
4
5
216 selves in
Round-4
Root Races
71,000BC-future
1

Each of the **12 Planetary Time Cycles** in one Planetary 12-Cycle of the **"Cycle of the Rounds" has 72 Time Vectors. 12-Strand** Angelic Humans have **one self** in each of the 72 Time Vectors of the particle universe Planetary 12-Cycle and **72 selves** in the corresponding anti-particle Planetary 12-Cycle. **72 selves x 12** Planetary Time Cycles = **864 selves** per one Planetary 12-Cycle **+ 864 selves** parallel universe Planetary 12-Cycle = **1728 selves** in Tribal Shield.

Tribal Shield Activation Creates Cue Zones In Earth's Planetary Shields.

Cue Zones

"Cue Zones" are locations on Earth where a small portion of Earth's D-12 Shield of Aramatena **Christos Divine Blueprint** has been re-set within Earth's Planetary Shields. During Stellar Activations Cycles, Cue Zones can be **manually set** by individuals or groups by running the **D-12 Maharata Current**, activating the **Tribal Shield** to draw in the Khunarary Primal Sound frequencies, then singing the 12-Tribes **Master Psonns Suffixes** and running the tones through the body and feet and into Earth's Planetary Shields. After running the Master Psonns Suffixes, one can then allow the **"Song of the Christos Soul"**, the tones of the personal D-12 **Maharic Shield** (the "Elohei-Elohim Within") to run into the Planetary Shields. The personal Soul Song will create a **"Back Song"** transmission of frequency from Earth's Planetary Shields, a set of healing frequencies sent back to you in response to activating your Soul Song in Earth's Planetary Shields. Once set, Cue Zones will remain for a period of **3.5 to 5 years**, depending on strength of energy originally set. They can be **recharged** using the same "setting" procedure to **last indefinitely.**

Cue Zones are **"safe zone"** areas on the Planet that are protected from interdimensional interference. They can be used to amplify effects of energy **healing applications, to "charge" objects and substances** with sub-harmonics of D-12 Christos frequency and when used with the personal Temporary Maharic Seal, to get clear, protected **"meditation space"** free from interdimensional interference. Cue Zones are "keyed" to Earth's Planetary **Templar "Cue Sites"**, the activation sites for Earth's 12 Primary Star Gates, which exist on regions of Earth that correspond to the 12 Primary Star Gates of **Inner Earth.**

TECHNIQUE # 6: THE MAHARIC QUICK SEAL

1 Work with a 24 pointed, 3 Dimensional Star (Heirophant) and be aware that you will be working with beings known as the Breneau Rishi ...

2 Begin by slowing your breathing , as you imagine or visualize a 24 point, 3 -Dimensional, Heirophant at the Pineal Gland in the center of your brain. Visualise the Heirophant surrounded by a Pale Blue Sphere of Light.

(The Blue Sphere serves as a buffer for your readiness to accept the frequencies associated with using the 24 pointed Star; the Blue Sphere holds the energy for you until your body can handle the energy. If you can handle it, the energy will simply pass through the blue sphere).

3 INHALE, as if you are going to grab the blue sphere containing the 24 point star located at the Pineal, and on the EXHALE move the 24 point star/ blue sphere, all the way down to Earth's Core. Try to hear a sound tone as the Heirophant/ Sphere hits the Planetary Shield ...

4 INHALE and draw the Heirophant/ sphere up to your Personal Maharic Shield 12" below your feet ... and EXHALE while watching the Pale Silver-Blue sphere expand out to a large sphere ... and watch as your Maharic Shield pop out as a disc, about 4' in diameter, Pale Silver with a light coating of Pale Blue.

5 Bring your attention to the center of your Maharic Shield 12" below your feet ... and INHALE the 24 point Star (only) up into the Heart Chakra. EXHALE, expanding the frequencies of the 24 point Star into the Heart Chakra.

6 INHALE to grab the 24 point Star, and EXHALE, pushing the Star up into the 14th Chakra 36" above the head. Imagine that the 24 point Star is spinning in a clockwise direction in the 14th Chakra. As you do this, try to feel/ sense the energy around you, just a few inches out from your body ...

7 Now, put your attention into your Maharic Shield 12" below your feet, take a couple of relaxing breaths and INHALE deeply pulling the Pale Silver and Blue energy up, as if you are pulling on your Maharic Seal to latch it on to your 14th Chakra. Try and feel the sensations just a few inches from your body now – feel the difference if you can. This procedure gives you a Quick Seal.

8 Now envision the cord of Pale Silver Maharic Light that would normally come up with your Shield and focus on the Earth's Core. Begin drawing energy all the way up the 4" diameter cord and into the body. INHALE the energy up into the Heart Center, and expand it there. Begin to form a pale Silver ball of Maharic frequency.

On each EXHALE send your energy down to the Earth's Core to bring up another load of Maharic frequency, up from the Planetary Shields, expand it into the Heart center and repeat several times. Notice that the Cord grows larger as you do this, expanding from approximately 4" to 6 to 8" diameter, until finally it feels like a skin around (as well as within) your body ... as you load your Astral field with Maharic Frequency.

9 Move your attention to the Pale Silver ball you have created in your Heart Center, INHALE and move it up to the 14th Chakra 36" above your head .. as you do, feel for the sheath of Maharic Frequency encasing your etheric body, close to your skin. (This Maharic/ Christos skin charges, and saturates, your etheric body – feel the peacefulness and all-knowing nature of this frequency).

Technique # 7: Ps-13 Tribal Shield Activation

The Master Key Tones

- The **12-Tribes names** were the **audible-tone translations** of the **specific Fire Letter Sequences** contained within the **Tribal Shield DNA Templates** of each Tribe. The tones of the Tribal names were used to activate the **144 Fire Letters** of the Tribal Shield in the **personal DNA Template**, providing the Angelic Humans races with the ability to **consciously regulate** the **activation level** of their **DNA Templates** and **Primal Life Force Currents.**
- The **Sound-Tone Programs** that are used to activate the DNA Template and Primal Life Force Currents are called **"The Sacred Psonns"**. The **Tribal name** was the **Master Psonn**. In running the Rainbow Roundtables, the Signet Council Regents brought their Tribal Shield "Flame Codes" into activation by **singing rounds** of the **Sacred Master Psonns.**

The 12 Sacred Master Psonns

for activating the 144 Fire Letters of the Tribal Shield Flame Codes in the 12-Strand DNA Template.

Plus **Master Tone Activation Suffix.**

12. *A-reah-Azurta*
a- RI-a-Zoor- ta- Rha

11. *Zephar-Duun-Atur*
ze-far-Doon a-Tur- Dha

10. *Ma'ah-hu-ta*
Ma-a hoo ta- Khu

9. *Yun Zu-Xen*
Yu-Un Zoo-Zen KE

8. *Chia Zhun Zan La-Yung*
ChE' ah-Zoon Yan LA-Yoong' OM

7.*Mahata-Agrah*
ME hah' ta a'g-ra OE

6. *Ramyana-Shridveta*
rah ma yah na shrid vE' Da U

5. *Ionatu-Etillah*
I O' Na too et il' a EU

4. *Nuagu Hali*
Noo ah' goo ha' LE Ka

3. *Amekasan-Etur*
a ME' ka sun e too'r DO

2. *Maahali-Bruea*
Ma a ha' LE - BrU' A EL

1. *Isutu-Esheau*
I sU' too E' shoo UR

Tribal Shield-Cue Zones Activation

Creating a Cue Zone

1. **Choose location** and **activate a personal "Maharic Quick Seal"** to "run the D-12 **Maharata Current**" in your **body.**

2. Once you can feel sensation of Maharata Current running, sing-tone 12-Tribes **Master Psonns** (names) for **Tribe-12** and **Tribe-1** to activate **Tribal Shields Flame Codes** in your DNA Template to run the "**Rainbow Ray**". Direct Pale Silver Maharata Current and Rainbow Ray pale color spectrum through body and out **soles of feet** into Earth's Planetary Shields. Tone for a while to build critical mass of frequency.

3. Use a selected combination of **3 Master Psonns Suffixes** and tone for a while, running sound through body and feet into Earth's grids. (avoid the Suffix combination of Tribe-4-7-10 used in that sequence to avert present distortions in Earth's grids that run on this mathematical coding)

4. Allow the **Christos Soul Song** to emerge from you "free style" and send the tones into Earth's grids.

5. When complete, sit quietly for a while and listen for the Earth's telepathically transmitted **"Back Song"**, drawing its gentle frequencies into your body for healing.

6. Close with singing several rounds of the **3 Master Psonns Suffixs** that you opened with. The Cue Zone you have set will extend out from your position in a radius of about **5 yards** and will last **3.5-5 years** depending on strength of energy you used in setting the Cue Zone.

7. To **amplify** strength of Cue Zone you can use the **"Merkaba Spin"** just after closing. Remain in same position, stand, the gently spin, first **clockwise** (as if you are standing on a clock face with the "6" in front of your feet, "3" at the left hand, "9" at the right and "12" directly behind you). Spin gently clockwise to bring electrical frequency down through your "**top**" Merkaba spiral. Then slow, stop and **reverse spin** to **counterclock-wise**, to activate "**bottom**" Merkaba spiral", drawing frequency up from Earth's grids. Personal Merkaba Activation will accelerate the frequencies of the D-12 energies you set at the site, making the Cue Zone **stronger and more lasting.**

The Solar Salutation
Electrical Merkaba Activation

- The ancient **Mu'a** and **Lemurian** Guardian Races ran the **Maharata** and activated the **Tribal Shield** each day to conduct the **Sacred Solar and Lunar Salutation Rites** each morning and evening. The **Sacred Salutations** are **Toning Dances** that activate the personal **Merkaba Field** for sustained activation of the DNA Template and amplification of the Maharata and Universal Life Force Currents in the body.
- **Solar Salutations** accelerate the spin of the **Electrical Harmonic Merkaba Spiral** (Top, CW spin), drawing increased amounts of **Electrical Anti-particle** frequency from the Solar **Electrical Merkaba Spiral** light spectrum into the **Electrical Acceleration Codes** in the **DNA Template** to **"charge" the body** with **Electrical Anti-particle frequency.**
- Accelerated **Electrical Merkaba Spiral Spin** of **Solar Salutations** increases the amount of **Anti-particle Base-Electrical** frequency **brought into** the body's **DNA Template** and **Kathara Grid** from the Dimensional Unified Fields and increases the amount of **Anti-particle** frequency **sent out** from the body into Earth's **Planetary Shields.** Frequency passes between the Human Body and Earth's Planetary Shields via the embodied **Kathara Grid** core templates that make up the **Planetary Bio-Feed Interface System** ("PBIS")
- **Electrical Anti-particle** energy enters the body via the **"Top" Electrical** Harmonic and Dimensional **Merkaba Spirals**, the **Base-Electrical Acceleration Codes** in the DNA Template, the **Electrical Kathara Centers 2-5-8-11** of the Kathara Grid **Central Pillar**, the **Electrical aspect** of **Electro-magnetic Kathara Centers 1-3-6-9-12** on the **Right Side** of body ("Left Side Pillar" in Kathara diagram), **Electrical Chakras 2-5-8-11** and the **Electrical aspect** of **Electro-magnetic Chakras 1-3-6-9-12**.

- **Solar Salutations** (CW spin Top Electrical Merkaba Field Activation) **raise** the body's **Oscillation** (energy transmission-expansion), **lower** the body's **Vibration** (energy holding-contraction), making the body **Higher Frequency** and **More Electrical** (transmits more energy than it is drawing in).
- A **Higher Frequency Electrical Body** has:
    - **Lower Vibration**, Higher Oscillation/Frequency, **Less Matter Density**
    - More activated DNA Strands, more chromosomes, embodiment of more levels of consciousness.
    - **Slower** heart, breathing and metabolic rhythms (energy expansion and contraction rates),thus requires less food (burns fuel slower).
    - Greater **longevity** and **less sleep** (body can synthesize natural higher frequency energy and Stream of Consciousness for longer periods without taxing.)
    - Greater **Silica quantity** in **Silica-to-Carbon Ratio** of elemental composition and **larger size** (more space between cells; more expanded matter).
    - Perception of **expanded Space** and **slower Time** movement.
    - Greater **heat release**, thus **cooler** internal temperature.
    - Natural attribute of **transmitting** greater amounts of energy thrust into the Planetary Shields than it is drawing in/receiving from them. **Energy "giving".**

- The **Solar Salutations** "charge" the **Top Electrical CW Merkaba Spiral** to maintain its natural cycle of **33**(⅓) **rotations per 1 "trillionth" of a nano-second"**, through which the **Base-Electrical** systems of the body are naturally maintained.

The Lunar Salutation
Magnetic Merkaba Activation

- **Lunar Salutations** accelerate the spin of the **Magnetic Harmonic Merkaba Spiral** (Bottom, CCW spin), drawing increased amounts of **Magnetic Particle** frequency from the **Lunar Magnetic Merkaba Spiral** reflected light spectrum and Earth's Planetary Shields into the **Magnetic Base Codes** in the **DNA Template** to **"charge" the body** with **Magnetic Particle frequency.**
- Accelerated **Magnetic Merkaba Spiral Spin** of **Lunar Salutations** increases the amount of **Particle Base-Magnetic** frequency **brought into** the body's **DNA Template** and **Kathara Grid** from the **Earth's Planetary Shields** and increases the amount of **Particle** frequency **sent out** from the body into Dimensional Unified Fields.
- **Particle Base-magnetic** energy enters the body via the **"Bottom" Magnetic** Harmonic and Dimensional **Merkaba Spirals**, the **Base-Magnetic Base Codes** in the DNA Template, the **Magnetic Kathara Centers 4-7-10** of the Kathara Grid on the **Left Side** of the body ("Right Side Pillar" on Kathara Diagram), the **Magnetic aspect** of **Electro-magnetic Kathara Centers 1-3-6-9-12** on the **Right Side** of body ("Left Side Pillar" in Kathara diagram), **Magnetic Chakras 4-7-10** and the **Magnetic aspect** of **Electro-magnetic Chakras 1-3-6-9-12**.
- **Lunar Salutations** (CCW spin Bottom Magnetic Merkaba Field Activation) **lower** the body's **Oscillation** (energy transmission-expansion), **raise** the body's **Vibration** (energy holding-contraction), making the body **Lower Frequency** and **More Magnetic** (draws in more energy than it is transmitting out).

- A **Lower Frequency Magnetic Body** has:
  - **Higher Vibration**, Lower Oscillation/Frequency, Greater **Matter Density**
  - **Fewer** activated DNA Strands, fewer chromosomes, embodiment of fewer levels of consciousness.
  - **Faster** heart, breathing and metabolic rhythms (energy expansion and contraction rates), thus requires **more food** (burns fuel **faster**).
  - Lesser **longevity** and needs more **sleep** (body can synthesize natural higher frequency energy and Stream of Consciousness for **shorter periods**; taxes more easily)
  - Greater **Carbon quantity** in **Silica-to-Carbon Ratio** of elemental composition and **smaller size** (less space between cells; more contracted matter).
  - Perception of **contracted or more confined Space** and **faster Time** movement.
  - Less **heat release**, thus **warmer** internal temperature.
  - Natural characteristic of **drawing** greater amounts of energy thrust from the Planetary Shields than it is transmitting into them. **Energy "taking"**.

The **Lunar Salutations** "charge" the **Bottom Magnetic CCW Merkaba Spiral** to maintain its natural cycle of **11⅔ rotations per 1 "trillionth" of a nano-second"**, through which the **Base-Magnetic** systems of the body are naturally maintained.

The **natural ratio** between the **Top-CW-Electrical-"Male" Harmonic Merkaba Field** and the **Bottom-CCW-Magnetic-"Female" Harmonic Merkaba Field** is **Electrical-Top 33⅓CW** rotations per 1 "trillionth" of a nano-second and **Magnetic-Bottom 11⅔CCW** rotations per 1 "trillionth" of a nano-second.

The Natural Christos Merkaba Vehicle & Personal Shields

© 2000 Ashayana Deane



The Density-4 Christos Merkaba Spiral (Top-Electrical-Male-CW) begins above the head at Chakra-10, expands up to Chakra-11, then folds down expanding over the body to Chakra-12 and the Maharic Shield below the feet encasing the body in a Pre-matter Liquid-Light Density-4 Base-Electrical Anti-Particle Field that rotates CW on the Electro-magnetic Maharic Shield Horizontal Axis and circulates D-12 Maharata-Christos energy into Chakra-13 and the Rishiac Shield for distribution into the Central Vertical Current of the body (once Cranial-Sacral Kundalini Seals are Released via activation of the 12-Strand DNA Template.)

D-1-2-3 Sub-Harmonics
of Density-4 (D-10-11-12)
Christiac Merkaba Spiral. (Top)
Electro-Magnetic "FEMALE-MALE"
Base-Electrical Dominant
"Male" CW Spin
SHOULD Spin CW- 33 2/3
(NOT 34-CCW reversal)

via progressive merging of the 5 Harmonic Merkaba Spirals from each of the 5 Density Levels. Each Harmonic Merkaba Spiral merger creates a "Phase" of Merkaba Vehicle building and concurrent activation of the Antahkarana, Maharata and Kee-Ra-Shay "Pillar of Light" ("Ascension Tube") as each level of the Universal Life Force Currents and consciousness embody via activation of the 12-Strand + DNA Template. The "*Nethra Phase*" Merkaba is the natural level-1, Density-1, 3- *Dimensional* Merkaba; progressive building stages are the ***Hallah*** (6-dimensional), ***Quatra*** (9-Dimensional), ***Mahunta*** (12-Dimensional) and ***Rahunta*** (15-Dimensional) Merkaba Phases.

Density-1 (D1-2-3)
Telluric Shield
Antahkarana-Telluric Current
When fully & properly activated, the Telluric Shield expands to 144 miles. When it expands increments of 11, it is running a reversal and cannot link with the Christiac Merkaba.

D-1-2-3 Sub-Harmonics
of Density-5 (D-13-14-15)
Rishic Merkaba Spiral (Bottom)
Magnetic "FEMALE"
SHOULD Spin CCW- 11 2/3
NOT
21-CW

Density-4 (D-10-11-12
istos Maharic Shield
rata Christos Current
When fully & properly activated, the Teuric Shield expands to 144 miles

The Density-5 Rishiac Merkaba Spiral (Bottom-Magnetic-Female-CCW) begins below the feet in Chakra-13 at Earth's Core, expands up above the head to Chakra-14, then folds over the head and down to Chakra-15 many miles beneath the feet, through Earth's center and back out into deep space to the Vertical Axis Magnetic Rishiac Shield. The Rishiac Merkaba Spiral envelopes the body in a Magnetic Field that manifests as a Horizontal Axis CCW rotating Magnetic Particle Field at the Density-1 Telluric Shield and as a Vertical Axis Ante-particle Thermo-plasmic Primal Light Field that circulates D-12 Maharata-Christos and Kee-Ra-Shay Currents up the Central Vertical Current and front of the body, over the head and down Central Vertical Current and the back of the body via the Rishiac Shield Vertical Axis.

Density-5 (D-13-14-15)
Rishiac Shield
Kee-Ra-ShA Primal Light Current
M-EM-CCW-CW CW

Density-
-15)
Rishi
Shield
Kee-Ra-ShA Primal Light Current
Chakra-14
Rahunta Phase- 15-D
Chakra-11
M Mahunta Phase- 12-D
Chakra-10
Quatra Phase- 9-D
Pineal Gland
Density-3 (D7-8-9)
Teuric Shield
Antahkarana-Teuric Current
Hallah Phase- 6-D
Top- Electrical
"Male" CW Spin
Chakra- 4
Density-2 (D4-5-6)
Doradic Shield
Antahkarana-Doradic Current
Nethra Phase- 3-D
Chakra-3
Chakra-2
Chakra-1
Right
Left
Bottom CCW
Magnetic "FEMALE"
Chakra-12
Mahunta Phase- 12-D
Maharic Capsule
Rahunta Phase- 15-D
Chakra-13
Chakra-15
Telluric Shield
M-CCW
M-EM-CCW-
Teuric Sh
Doradic
E-CV
Maharic S
E-EM-CW-

The NATURAL Spin Ratio between the Top (Male-Electrical-CW-Anti-particle) Density-4 Christiac Merkaba Spiral and the Bottom (Female-Magnetic-CCW-Particle) Density-5 Rishiac Merkaba Spiral is 33 1/3-CW-Male-Top to 11 2/3-CCW-Female-Bottom. The 33 1/3-CW/11 2/3-CCW Spin Ratio creates the NATURAL ratio of 33 2/3-Parts-Electrical Anti-Particles to 11 2/3-Parts Magnetic Particles, (or 33 1/3 energy expansion/oscillation/thrust to 11 2/3 energy contraction/vibration/draw) within earth's Density-1 Matter Base, the organic Divine Blueprint of Density-1. This Christiac Internal Merkaba Vehicle Spin Ratio creates a self-sustaining, Eternal, Matter-base that is MORE ELECTRICAL than Magnetic, which perpetually re-fuels itself via natural circulation of the *Maharata*, *Kee-Ra-ShA* and *Khundaray* Universal Life Force Currents.

Merkaba Phases – Building the Merkaba Vehicle


RISHIC Merkaba
5 Harmonic Merkaba Spirals
15-Dimensional Time Matrix
Rishi Identity
Avatar Identity
Over-Soul Identity
Soul Identity
Incarnate Identity
Dimensions
9
8
7
4
Rahunta Phase
15 Dimensional
3
Mahunta Phase
12 Dimensional
CHRISTOS AVATAR Merkaba
4 Harmonic Merkaba Spirals
Form Constant "Manifest Zone" forms at center of interface between 2 or more Harmonic Merkaba Spirals
OVER-SOUL Merkaba
2
Quatra Phase
9 Dimensional
3 Harmonic Merkaba Spirals
SOUL Merkaba
Hallah Phase
6 Dimensional
2 Harmonic Merkaba Spirals
1
Density-5 M
Dimensions-13-14-15
Density-4 E
Dimensions-10-11-12
Magnetic
D9
D8
D7
HU/ Density-3
D6
D5
D4
Electrical
HU/ Density-2
D3
D2
D1
Magnetic
HU/ Density-1
RAHUNTA
MAHUNTA
QUATRA
HALLAH
Avatar Strands
Mahunta Merkaba
12
11
10
1
Incarnate Strands
2
3
4
5
6
7
8
Over-Soul Strands
Quatra Merkaba
Soul Strands
Hallah Merkaba

Formation of the Mahunta Merkaba marks fulfillment of the 12-Strand DNA potential.

The 4 Personal Scalar Shields merge to form the 12-Dimensional Mahunta Merkaba

12-Strand Silicate Matrix DNA Diagram shows Strand relationships

The Merkaba Vehicle: Counter-rotating Spirals of interdimensional electromagnetic energy in star-tetrahedron form that form in the auric field, enabling biological interdimensional travel and ascension.

Each dimension of the Human Body has *one* **Dimensional Merkaba Field** (EM set). The *three* **Dimensional Merkaba Fields** in *one* **Density Level** form *one* **Harmonic Merkaba Spiral** in each of **5 Density Levels** that **merge** to form the **Merkaba** Star Gate Transit (Ascension) **Vehicle.**

Technique # 8: Merkaba Salutations

Healing the Spin & Balancing Particle/ Anti-Particle Ratios

33 1/3-CW/11 2/3-CCW Christos Merkaba Activation

***Note:** Discern **CW** or **CCW direction of Merkaba Spin** by imagining that you are standing, with arms stretched out to the sides, in the center of a round 12-digit clock-face. The **FRONT** of your body faces the **"6"-digit, "12"-digit** is positioned **behind you,** the **"3"-digit** is positioned at your **LEFT ARM** and the **"9"-digit** is positioned at your RIGHT ARM. **CLOCKWISE "CW" SPIN:** Hold LEFT **"3-Arm"** firmly out to the side of the body like a **"clock hand"** and begin **Spin** toward FRONT, moving the **body** with the **LEFT arm** toward the **"6"-digit** position in **FRONT** of your feet. COUNTER-CLOCKWISE "CCW" SPIN: Hold RIGHT **"9-Arm"** firmly out to the side of the body like a **"clock hand"** and begin **Spin** toward FRONT, moving the **body** with the **RIGHT arm** toward the **"6"-digit** position in **FRONT** of your feet. The **TOP-ELECTRICAL-MALE** Merkaba Spiral **Christos Spin** is always **33 1/3-CW** rotation. The **BOTTOM-MAGNETIC-FEMALE** Merkaba Spiral **Christos Spin** is always **11 2/3-CCW** rotation.

Solar Salutation Rites: (best time *Dawn's First Light* & *12:00 Noon*)
begin with *Top-Electrical-CW-***"*Male*"** **Merkaba Spiral** activation, followed by *Bottom-Magnetic-CCW-"Female"* Merkaba Spiral
Use Tribe-12 Activation Suffix **"RHA"** as ***Initiating Tone***
Lunar Salutation Rites: (best time *12:00 Midnight* to *3:00AM*)
begin with ***Bottom-Magnetic-CCW-"Female"*** **Merkaba Spiral** activation, followed by *Top-Electrical-CW-"Male"* Merkaba Spiral
Use ribe-1 Activation Suffix **"UR"** as ***Initiating Tone***

1. Activate ***Maharic Quick Seal*** Technique- 6
2. Activate ***Tribal Shield-Cue Zone*** Technique- 7
3. Stand with spine comfortably straight, breath slowly, in a relaxed manner and begin **quietly toning** the ***Initiating Tone***, continuing repetition while progressively **increasing** the **volume** and extending the Exhale Breath Tone thrust behind Initiating Tone until you can **feel the subtle energy** of Tone sound waves oscillating in the body.
4. **Activate First Merkaba Spiral** (Top or Bottom Spiral first, depending on Solar or Lunar Salutation) by holding **arms out to the side**, parallel with the ground, and begin to **slowly SPIN** in the direction (CW or CCW) natural to the *** Christos Spin** of the Merkaba Spiral you are activating. Continue to **Spin AND Tone Initiating Tone** while progressively **increasing rate of Spin and Toning.** To **prevent dizziness,** hold one arm out to front with thumb positioned UP, and **focus your eyes on the THUMB** rather than the spinning scenery beyond. Do not Spin faster than comfort level. You may **modulate toning in rounds of 3,** between the **Initiating Tone** and toning the **Christos Spin Rate Number** (**"33 1/3"** for Electrical-Top Spiral, **"11 2/3"** for Magnetic-Bottom spiral), if desired.
5. When energy in body feels **"charged"** (a "doneness" intuitive feeling), **slow spin** to a **gentle STOP**, while **Toning 3 Times,** the **"*Um Shaddai Ur'-A ah-Khum' Tun*"** Lyra-**Halls of Amorea** D-12 activation sequence, to **amplify** the Merkaba Spiral "charge. **Stand STILL** and breathe quietly for a few moments while Spin stabilizes, then **repeat STEPS 3-5** to **activate other Merkaba Spiral.**
6. **End Salutation Rite** with full **3 Rounds** (minimum) **Toning** of the ***"Ariea Khum Nar-A"***" (Song of Orion D-8 activation sequence) **Part-1:Verses 1 and 2,** to be sung while **Walking 2 Circles**, one **CW**, one **CCW**, beginning Circle Walk with Spin direction of **First Merkaba Spiral** activation, followed by a **reverse-direction** Circle, then **Standing STILL** for a few moments to allow the **Christos Maharata Current** to run between your body and Earth's Planetary Shields.

The A*r-IE- a Khum –Nar' A*
The Song of Orion

Part 1 : the Resonant Tone Syllable Sequence (primary melody)

Verse 1: OM A Da E, Patum ah
OM A Da E, Patum ah
Patum ah A' DE E - Tah, A khum-na
OM A Da E, Patum ah

Verse 2: TrA TE La E' Durum Na
TrA TE La E' Durum Na
Durum' ah A' Khem - Tah, A khum -na
OM A Da E, Patum ah

Part 2 : the Base Tone Syllable Sequence (accompaniment 1)

OM A Da E, Patum ah - Lines 1, 2 & 4 Verse 1 & Line 4 Verse 2
TrA TE La E' Durum Na - Lines 1 & 2 Verse 2
UM ah OM, A
UM ah OM, A
Patum ah A' DE E – Tah, A khum- na
Durum ah A' Khem – Tah A khum-na
DO RAY' TU Ra"
OM A Da E, Patum ah
UM ah OM, A

Part 3: the Over Tone Syllable Sequence (accompaniment 2)

OM A Da E, Patum ah – Lines 1 & 2 Verse 1
TrA TE La E' Durum Na – Lines 1 & 2 Verse 2
BE HE Tah OM, A
BE HE Tah OM, A

Patum ah A DE E – Tah, A Khum –na – Line 3 Verse1
Durum ah A Khem- Tah, A Khum - na - Line 3 Verse 2
Thra Khem' Na, A
OM A Da E, Patum ah – Line 4 Verses 1 & 2

KhrA MiM, Tah A

The fastest means of naturally activating the Personal 12-Strand DNA Template is :

1. **Tribal Shield Activation:** Activating the 144 Fire Letters of the Tribal Shield & Sacred Salutations Merkaba Activations.
2. **Emerald and Amethyst Awakening 2 Masters Kundalini Activations:** Releasing key **Fire Codes** between the DNA Strand Templates to allow for **expedited DNA Strand Braiding.**
3. **DNA Template Bio-Regenesis:** Progressive use of internally directed DNA Template Bio-Regenesis technologies for progressive purging of Strand Template mutations, restoration of the natural D-12 Christos Divine Blueprint of the 12-Strand DNA Template and expedited, accelerated activation of the DNA Strand Template Base Codes and Acceleration Codes.
4. **Master Key Codes:** Use of the personal scalar-wave-guide Symbol Code Programs that correspond directly to the core programming of the personal D-12 Maharic Shield for further sequential expedition of Strand Template Activation.
5. **Melchizedek Cloister Level-3 Regent Ordination:** Transmission of the Kee-Ra-ShA Primal Light and Khundaray Primal Sound Field **"Rainbow Ray Current"** directly into the personal **DNA Template** via direct **Chakra Induction**. Sufficient Rainbow Ray frequencies to provide a level-3 Regent Ordination can be transmitted by a Melchizedek Cloister **level-5 Elder Consummate** or **Level-6 Eckar** Indigo Child-Type-1 Maji Grail Line Angelic Humans, who have the frequencies of the Primal Creation Currents integrated into their DNA Template from birth. **Expedites all of the above** while provided additional **bio-energetic field support** for more **stable cycles** of DNA Template activation.

The Khundaray RRT Activation Sequence

A progression of **manually initiated** *Kundalini and DNA Template Activations* that systematically induce *temporary release* the **Cranial-Sacral Kundalini Seals** (Pineal Gland & Tail Bone), in their **natural Release-Sequence,** allowing for temporary and ***progressive*** embodiment (nano-second burst of frequency) of the *Primal Universal Life Force Currents* via **Syncopated Activation** of the **12-Strand DNA Template**.

The ***Khundaray RRT ("K-RRT") Activation Sequence*** allows the Density-4 (D-10-11-12 Pre-matter) ***Maharata Christos Current***, Density-5 (D-13-14-15) ***Kee-Ra-ShA Primal Light Currents*** (Ante-matter *Blue, Gold* and *Violet* "Flames") and the ***Khundaray Primal Sound Currents*** (*Eckatic, Polaric* & *Triadic* Columnar Standing Waves) from *Source* to run through the DNA Template and body for accelerated ***TRUE 12-Strand or higher DNA Template Activation** and expedited human Spiritual Integration.

For the human body to **hold and transmit** a **minimum critical mass** of Kee-Ra-ShA and Khundaray frequency to **access the Planetary Shields** and **Star Gates** for ***Masters (Universal) K-RRTs,*** the ***K-RRT Activation Sequence*** must be conducted **4 to 24 hours** prior to the K-RRT. The *K-RRT Activation Sequence* must also be run **2-24 hours** prior to the ***Amethyst Awakening Masters-2 Kundalini Activation*** to prepare the body for the Amethyst Awakening frequencies. The *Amethyst Awakening* (Field Technique-6) can also be run **just before** a K-RRT (following prior *K-RRT Activation Sequence*) to **greatly amplify the power** of the K-RRT and Signet Council group.

There are **5 Specific Operations of Energy Management** within the ***K-RRT Activation Sequence***:

1. **Activating the Doradic Phase-1 Current**
2. **Awakening the KA**
3. **The Emerald Awakening**
4. **Activating the Kee-Ra-ShA**
5. **Activating the RA Center-Anchoring the Rainbow Bridge**

The Emerald & Amethyst Awakenings
Masters Kundalini-DNA Template Activations
For Accelerated ***DNA Template Activation*** and ***Spiritual Integration***, Running **K-RRTs** and enhanced ***Immune Support***

THE KUNDALINI LIFE-CURRENTS AND THE CRANIAL-SACRAL SEALS.

The human body is fuelled by ENERGETIC LIFE-FORCE CURRENT FROM SOURCE. In contemporary human anatomy, the only life-force currents running fully through the embodied Kathara Grid and body are those corresponding to the SINGLE-VECTOR time cycle of the Density-1 TELLURIC SHIELD. Each of the 4 HOVA BODIES and their corresponding SCALAR SHIELDS, DNA STRAND TEMPLATES, AXI-A-TONAL LINES, DIMENSIONS OF CONSCIOUSNESS AND MERKABA FIELD LEVELS process the frequencies of one TRIADIC CURRENT – a 3-dimensional, Bi-polar life-force current. The life-force currents corresponding to the first 9 dimension and first 3 Hova Bodies, Mater Densities and Shields are referred to as the KUNDALINI ENERGIES. Each KUNDALINI CURRENT is a TRIADIC CURRENT – a set of 3 dimensional currents that function together and are separated by Magnetic Repulsion Zones within the embodied Kathara Grid. The 3 embodied Kundalini Currents are the TELLURIC, DORADIC and TEURIC CURRENTS .

Each of the 3 Kundalini Currents is spiralled within the regions of the 1st 8 CELLS of human conception, located in the TAILBONE at the Base of the Spine. (The incarnating consciousness anchors its identity and Christos Manifestation Template within the FIRST 8 CELLS, to initiate the FETAL INTEGRATION PROCESS.) The first Kundalini Current, the TELLURIC CURRENT that corresponds to the DENSITY-1 Nada Hova Body, is active within the human form from birth, enabling 3 dimensions of consciousness awareness, in the form of scalar frequency, to embody within the human organism. When the 2 dormant Kundalini Currents in the tailbone, the DORADIC and TEURIC CURRENTS, are activated, the frequencies of consciousness from dimensions 4-9 progressively awaken within the body, activating the dormant 4-9 strands of the 12-strand DNA Template. The 3 Primary Kundalini Spirals each contain 3 single-dimension currents, and are controlled by the corresponding SIGNET STAR CRYSTAL SEALS in the Kathara Level-2 Crystal Seals Grid. The Signet Seals create polarization between dimensionalized sets of scalar waves within the Scalar Shields, that manifest within the Kathara Level-2 Grid, First Eight Cells and DNA Template as FREQUENCY SEALS or blockages within the TAILBONE (Sacral region) and the PINEAL GLAND in the center of the brain – the CRANIAL-SACRAL SEALS.

When the Cranial-Sacral Seals are released, through activation of the Signet Star Crystal Seals that govern them, the dormant Kundalini Currents come to life within the body, sending progressively higher-frequency energy through the CENTRAL VERTICAL CURRENT of the body. Activation of the 3 Kundalini Currents progressively creates integration of the higher dimensions of consciousness and de-densification of molecular structure. When ALL of the frequencies within the 3 embodied Kundalini Currents are activated, the 4th KUNDALINI CURRENT- the PRIMAL TRIADIC CURRENT, the KEE-Ra-ShA', is activated. The Frequency Seal on the KEE-Ra-ShA' is located in the 12th Chakra, 6" below the feet. Activation of the KEE-Ra-ShA' anchors the 12th-Dimensional HYDROPLASMIC BEAM within the body, initiating the process of CELLULAR TRANSMUTATION and intentional de-manifestation and Dimensional Ascension of the human biological form.

THE EMERALD AWAKENING AND THE KEE-Ra-ShA'

The Emerald Awakening Masters Kundalini Activation is one of two inter-harmonic energetic activations of previously dormant frequency within the body that sets in motion simultaneous activation of the 12 MAGNETIC BASE TONES within the FIRE CODES between the 12 Strands of the SILICATE MATRIX DNA Template. Activation of the 12 Fire Code Base Tones begins activation of the 3 PRIMAL CREATION FREQUENCIES – the KEE-Ra-ShA' – within the 4 Scalar Shields of the PERSONAL INNER TEMPLAR COMPLEX. Activation of the 12 DNA Fire Codes allow for progressive natural fusion of each dimensional DNA Strand Template to occur, through which the organic potentials of CELLULAR TRANSMUTATION are re-awakened within the physical body form.

Through the natural processes of Cellular Transmutation, once fully operational within human genetic design, the carbon-based elemental biology of Density-1 molecular structure is progressively and systematically transmuted to SILICA-based biology. Transmutation to Silica-based biology allows the physical body to pass through the levels of Semi-etheric, Etheric and Pre-matter Hydroplasmic Liquid-Silica Densities of Harmonics 2-4 (Dimensions 4-12), through which the consciousness continually enters manifestation, to achieve physical mastery of the organic process of Transmutational Dimensional Ascension. To accomplish mastery of the Ascension process, the SIGNET STAR CRYSTAL SEALS with the Scalar Shields, which keep the 12 dimensionalized frequency levels of the consciousness and molecular form Phase-locked into dimensional division/ polarization, must be released. Release of the Signet Star Crystal Seals allows the frequency spectra of the higher dimensional anatomy and the Primal Creation Currents of the KEE-Ra-ShA', to enter into the Template for the physical body and dormant DNA Fire Code Templates, progressively building the Merkaba Vehicle and setting the Cellular Transmutation process in motion. The process of progressive Transmutational Dimensional Ascension represents the function of the organic genetic design and evolutionary objective of the human creation blueprint, through which the natural Immortal Christos-Angelic Form of the human being is actualised.

In the evolutionary cycles of contemporary humanity, actualization of the 12-Strand DNA potential takes place slowly in Earthly terms, as the incarnate identity experiences in single-life time-vectors, several cycles of Density-1 incarnation, spanning many thousands of years, in order to progressively activate the DNA Fire Codes within the Manifestation Template. When the human genome was operating in its organic form, this process took place in one lifetime, over a period of about 44 years, as the immortal human incarnate matured to embody the 12 dimensions of consciousness within its original Christos Manifestation Template- the MAHARIC SHIELD, actualizing its organic Angelic-human heritage and mastery over 4 Densities of manifestation within the Time Matrix.

The EMERALD AWAKENING Masters Kundalini Activation releases the Density-2 4TH – Dimensional Green Signet Star Crystal Seal and the Density-1 1st-Dimensional Red Signet Star Crystal Seal, to open the Density-1 NADA HOVA BODY and TELLURIC SHIELD, and Density-2 ALPHI HOVA BODY and DORADIC SHIELD, to receive the Omni-polar frequencies of the 12th-Dimensional MAHARIC CURRENT (Hydroplasmic Beam) from the Pre-matter Christos Template Maharic Shield. Upon entering the Telluric and Doradic Shields, the 12th-Dimensional frequencies of the Maharic Current trigger simultaneous activation of the Base Tones within the 12 Fire Codes of the DNA Template, beginning the process of DE-POLARIZTION of the 12-Strands and levels of consciousness within the human Manifestation Template. Progressive de-polarization of the 12 levels of consciousness within the human Manifestation Template sets in motion the organic process of Cellular Transmutation and potential mastery over Transmutational Dimensional Ascension. The Emerald Awakening Masters Kundalini Activation initiates REGENESIS of the original function of the human genome, releasing the Base Tones of the 3 KEE-Ra-ShA' Currents within the body via opening of 2 Signet Seals, through which the physical body begins the carbon-to-silica transmutation process and is prepared to receive the higher dimensional OVER TONE frequencies of the KEE-RA-Sha', to complete Cellular Transmutation via fusion and de-polarization of the particle (Particum) and anti-particle (Partika) aspects of the Manifestation Template. This is the natural process of UNIFIED FIELD PHYSICS by which a human being becomes "Christed".

THE AMETHYST AWAKENING AND THE KHUN-DA-RAY

The final step in fulfilling the potentials of original Angelic-human design is activation of the OVER TONE frequencies of the KEE-Ra-ShA', which allows fusion between DNA Strand Templates to complete on 12 dimensions of frequency. The final step in Transmutational Dimensional Ascension is called the AMETHYST AWAKENING MASTERS KUNDALINI ACTIVATION. Through the AMETHYST AWAKENING, the DENSITY-3 7TH-Dimensional VIOLET Signet Star Crystal Seal and 8th-Dimensional GOLD Signet Star Crystal Seal, and the DENSITY-4 11TH-Dimensional DARK SILVER Signet Star Crystal Seal are released within the body's Scalar Shields. Release of the OVER TONE SIGNET SEALS allows the OVER TONES of the KEE-Ra-ShA Creation Currents to fuse with the BASE TONES, bringing the 3 OMNI-POLAR CREATION CURRENTS (Primal Creation Currents built upon a TRINITY OF TONES, BI-POLAR + NON-POLAR energy units) together as ONE PRIMAL NON-POLAR CURRENT – the KHUNDARAY (also called the "Rainbow Bridge" or the " Rainbow Serpent".)

The KHUN-Da-rAy is the PRE-LUMINAL vibration, or STANDING WAVE OF INTERNAL SOUND emitted from ONE-SOURCE/ GOD, that corresponds to the COMBINED ORIGINAL SOURCE CURRENT from which the 3 KEE-Ra-ShA' PRIMAL LIFE-FORCE CURRENTS of the 3 non-dimensionalized levels of the ENERGY MATRIX, beyond the 15-Dimensional Time Matrix emerge. The Emerald Awakening Masters Kundalini Activation, and its resulting activation of the BASE TONES of the KEE-Ra-ShA' within the human body, is the first step in manually expediting the natural process of Transmutational Dimensional Ascension.

AWAKENING THE KA AND REMOVING INORGANIC CRYSTAL IMPLANTS

Before the Emerald Awakening Kundalini Activation can be orchestrated, the MAHARIC SHIELD and the KA must be brought out of dormancy within the human Manifestation Template. Once the 12th-Dimensional Maharic Current is released within the embodied Kathara Grid, the KA can be activated. The "KA" refers to the 4 HOVA BODIES corresponding to dimensions 1 through 12. (Nada, Alphi, Betcha and Mahara Hova Bodies.) The KA becomes activated through removal of 4 inorganic Crystal Seal IMPLANTS that block the natural function of the 2nd, 3rd and 4th DNA Strand Templates. Following he procedure for AWAKENING THE KA, the Emerald Awakening Kundalini activation can be conducted.

Technique # 12: Kee-Ra-ShA Activation Sequence

ACTIVATING DORADIC PHASE I Awakening the Flame

Preparation: Activate Maharic Seal Technique-6 *Maharic Quick Seal*

1 Breath slowly and deeply for several breaths while visualizing or imagining a Violet Dot on the center of the *inside* of your forehead. Make the color image as strong as you are able (if you can't yet perceive inner colors simply imagine the Violet Dot being there).

Move the Violet Dot to the center of the brain, at the **Pineal Gland,** and then upward into the 7th Chakra, finally moving it out of your head to rest on the top of your skull, at the Crown Chakra.

2 Call to mind the Heirophant Symbol (Pale Silver Merkaba Star/ Star of David). Visualise the Heirophant spinning 12" below your feet, within your Maharic Shield, and slowly INHALE.... drawing the Pale Silver Heirophant up through the Central Body Current, up to meet the Violet Dot at the 7th Crown Chakra at the top of the head.

When the Heirophant connects with the Violet Dot, visualize the Violet Dot bursting into a 4" vertical Pillar of Violet-Silver Light. Imagine the Violet-Silver Pillar running down through the body and into the Earth's Core, as well as upward into the 14th Chakra positioned 36" above your head. (This activates the Violet Ray of Transmutation).

3 Now, move your attention to the 4th Heart Chakra, and imagine a small Green Spherical Crystal – the Green Star – stationed at it's core. This is the Green star Crystal Seal that controls release of 4th Dimensional frequency – Phase I Doradic Current – into the body. INHALE, drawing Violet-Silver energy from the Violet-Silver Pillar into the Green Star.

EXHALE, expanding the Violet-Silver energy into the Green Star sphere. Repeat two more INHALE/ EXHALE breaths, drawing Violet-Silver energy from the Pillar and expanding it into the Green Star sphere.

4 At the end of the last EXHALE, imagine the Green Star POPPING, turning into a spinning Green and Violet Starburst of Light, as the Violet-Silver Pillar disappears. Spin the Green-Violet Starburst faster until it becomes a ball of Green-Violet Light, about the size of a grapefruit, spinning the center of the Heart Chakra. (The Green-Violet ball is the storehouse for your Phase I Doradic Current; it's called the Doradic Sphere).

INHALE and draw Pale Silver energy from your Maharic Shield, through the central Body Current, and into the center of the Doradic Sphere at the heart Chakra ... encasing the sphere in Pale Silver Light.

AWAKENING the KA

1 Bring your attention back to the DORADIC SPHERE at the HEART CENTRE...

2 INHALE pale silver energy up from the EARTH CORE to fill & expand the DORADIC SPHERE; breath slow and deep 2-3 times ...

3 Now, put the tips of your fingers together, and feel the 'fuzziness' of the energy flow...

4 Next, move the fingertips to the tail bone... INHALE energy from the Maharic Shield into the DORADIC SPHERE

Continued Next Page

As you EXHALE, push PALE SILVER energy down to the finger tips and into the tail bone............... REPEAT 2-3 times and then remove the fingers.

5 Now, bring your attention to the 2nd CHAKRA (SACRAL) .....feel or visualize or just know ... a DOUBLE TERMINATED QUARTZ CRYSTAL (a crystal with a point at both ends) is beginning to "push out" of the front of your 2nd Chakra, the Sacral center.

6 Focus your attention on this, try to feel the crystal pushing.... use your hands to help ease it forward, and out.

7 There is a smaller double terminated crystal in the 3rd (Solar Plexus) Chakra; this will release on it's own because the currents have activated it to do so. Help it out with your fingers.

8 In the Heart Chakra, imagine a little sphere of energy, colored green. Bring this little green sphere more fully into focus ... and you will notice a little black cube of energy inside it ...look more closely again, and notice a smaller white cube inside the black one.

9 As you focus on the two little cubes, watch them merge together .. feel a ripple of vibration as they do, and then ... notice a little puff of smoke as they both disappear.

Now, the body is activated to open the 4th and 1st Crystal Seals; you are ready for the EMERALD AWAKENING ...

1 Now we will open the GREEN STAR CRYSTAL SEAL ....So, keeping your awareness on the Doradic Sphere, the GREEN-VIOLET- SILVER ball at the Heart Center.........INHALE,

2 and ... on the EXHALE visualize or imagine pushing a cord of GREEN-VIOLET-SILVER Doradic Current down into the tail bone... to the 1st Cell ...... at it's very tip .

3 Breathe easy ... and take a moment to visualize the 1st Cell at the tip of your tail bone.... as a WHITE-SILVER SPHERE...

5 Now within the WHITE SILVER SPHERE, visualize, a GREEN SPHERE ... and then visualize a RED SPHERE inside the GREEN SPHERE ...

6 Bring your attention back to the SPHERE of GREEN-VIOLET-SILVER energy in your Heart Center ...

and on the next EXHALE visualize, or imagine, sending a cord of GREEN-VIOLET SILVER energy all the way down your central vertical column and into the GREEN SPHERE in the 1st Cell at the tip of the tail bone.

7 AS you INHALE pull PALE SILVER LIGHT from your personal Maharic Shield, the platform-disc 12" below your feet, up into the tail bone and into the GREEN SPHERE.

8 As you do this, visualize, the GREEN SPHERE 'pop' into a STARBURST of PALE GREEN-SILVER LIGHT.

Continued Next Page

This has opened the kundalini seal – your WHITE-SILVER & RED Spheres REMAIN as you left them earlier ....Now, we will work to open the **RED STAR CRYSTAL SEAL....**

---

9 Return your awareness to the Doradic Sphere at the Heart Center....INHALE, and then on the EXHALE push a cord of GREEN-VIOLET-SILVER Doradic Current down to the 1st Cell at the tip of the tail bone, ...

10 INHALE and draw PALE SILVER energy up from the personal Maharic Shield, the platform-disc positioned 12" below your feet, up into the tail bone, and into the RED SPHERE ... inside .... the WHITE-SILVER SPHERE.

11 AS YOU DRAW the PALE SILVER energy into the RED SPHERE visualize the RED SPHERE 'pop' into a STARBURST of PALE PINK-SILVER LIGHT...... and ...... for the next few breaths EXHALE the PALE PINK-SILVER LIGHT into the 12th Chakra, positioned 6" below your feet...

You have now opened the Kee Ra ShA(Y) Seal ... so that the Sacred Flames of the Kee Ra ShA can be activated ......

ACTIVATING THE KEE RA SHA

The Kee Ra ShA appears as 3 little flames which exist in the 12th Chakra positioned 6" below the feet. The 3 flames are PALE BLUE, PALE YELLOW & PALE VIOLET.

1. Begin by focussing deeply on the 12th Chakra, 6" below your feet, and the three little flames held there ... one is PALE BLUE, one PALE YELLOW & the third PALE VIOLET.... We'll take a few moments to do this......

If you have difficulty visualizing, just imagine that they are there.

2 On the INHALE, draw the PALE VIOLET FLAME up from Chakra 12 ... into the central vertical column .. and all the way up ... and out through the top of the head, to the 10th Chakra ... 6" above your Crown chakra......

3 Next, return your attention to the 12th Chakra, 6" below your feet ... allow yourself time to connect with the little PALE YELLOW-GOLD FLAME. Breathe easy.

4 On the next INHALE draw the PALE YELLOW-GOLD FLAME up from Chakra 12 ... into the central vertical column .. and all the way up ... and out through the top of the head, to the 10th Chakra ... 6" above your Crown chakra......

Again, return your attention to the 12th Chakra, 6" below your feet ... and connect with the PALE BLUE FLAME... this FLAME is the INNER ARC of the COVENANT ... Take your time; breathe easy.

5 On the next INHALE draw the PALE BLUE FLAME up from Chakra 12 ... into the central vertical column .. and all the way up ... and out through the top of the head, to the 10th Chakra ... 6" above your Crown chakra......

5D Continued Next Page

© Rev. Ashayana Deane 2000

6 Now, visualize or imagine the 3 little FLAMES together within the 10th Chakra 6" above your Crown Chakra ………… in a moment we will create the Kee Ra ShA SPHERE… Breathe easy.

7 On the next INHALE draw PALE SILVER energy from your personal Maharic Shield 12" below your feet, all the way up your central vertical column, up into the 10th Chakra……

EXHALE gently and INHALE once more, drawing more PALE SILVER energy up into the 10th Chakra … visualize or imagine the 3 little flames enclosed within a SPHERE of PALE SILVER LIGHT…

8 Breathe easy. On the next EXHALE move the Kee Ra ShA SPHERE all the way down through the central vertical column, out through the 12th Chakra 6" below your feet, and all the way down to the 13th Chakra at EARTH'S CORE.

As the Kee Ra ShA enters EARTH'S CORE listen for sound tones w/ inner ear…

These TONES represent the AMENTI "PASS KEY" … which opens your personal GRU-AL POINT (#1) - the 1st Cell in the Tail Bone …. releasing the KEE RA SHA FLAMES into your AURIC FIELD.

9 Breathe easy… Watch as the Kee Ra ShA FLAMES rise up your Maharic Pillar and emerge through your 1st Cell … passing like radiating waves of PALE BLUE, PALE YELLOW & PALE VIOLET ……

10 As the waves of color move through you, bring your attention to your first 4 Chakras … the base, the sacral, the solar plexus and the heart … and visualize or imagine each Chakra emanate a SILVER MAHARIC SHEATH or OVAL POD, completely surrounding each one …

This completes the EMERALD AWAKENING, the natural process by which we use Unified Field Physics to trigger our CHRISTED Selves. Before we finish we must first establish the link to the Amethyst Awakening, the process of activation and sheathing of the higher Chakras.

To complete the session we will now work with 8th & 11th Dimensional Energies to open DORADIC PHASE 2 & 3 CURRENT and activate TEURIC PHASE 2 CURRENT…….THIS IS CALLED **ACTIVATING THE RA CENTRE in the THYROID – and ANCHORING THE RAINBOW BRIDGE**

1 Begin by moving your attention to the area of your 3RD EYE, and focus just inside your fore-head .. a little above and behind your eye brows…… Breathe easy.

2 Now, visualize, or imagine, a DARK SILVER DOT in the position you are focussed on … in the area of your 3RD EYE… Take a little time.

3 INHALE and move the DARK SILVER DOT into the Pineal Gland in the center of your head and then straight up through the CROWN CHAKRA until the DARK SILVER DOT sits on the top of your skull.

Continued Next Page

© Rev. Ashayana Deane, 2000

Activating the RA Center-Rainbow Bridge - Continued

4 On the next INHALE, pull PALE SILVER ENERGY up from your personal Maharic Shield 12" below your feet, all the way up the central vertical current and into the DARK SILVER DOT on the top of your head...

As the PALE SILVER ENERGY reaches the DARK SILVER DOT, the SILVER DOT 'pops' into a SILVER STARBURST ...

5 On the next EXHALE push the SILVER STARBURST down the central vertical channel, all the way to the tip of the tail bone ... EXPANDING the SILVER STARBURST FULLY into the 1st Cell...

6 Breathe easily and watch, as GOLD-SILVER-CURRENT emerges from the tailbone .. and begins to flow up through each Chakra ..

from the 1st Chakra at the base of the spine ... up through the Sacral ... the Solar Plexus ... all the way up to the Crown Chakra ... we'll take a little time for this ....

From the Crown Chakra the GOLD-SILVER-CURRENT continues upward out of the top of your head ... up through the 10th Chakra 6" above your head ... the 11th Chakra 18" above your head ... and finally the 14th Chakra 36" above your head.

7 Once the GOLD-SILVER-CURRENT reaches the 14th Chakra it returns to the 1st Chakra the flow of the current creates a GOLD-SILVER SHEATH throughout your central vertical channel.

8 Bring your attention to the 2nd Chakra now .. were going to create a GOLD -SILVER- BALL there, in the SEED SEAL at the center of the Chakra ... just imagine the chakra as a bow tie shape, the SEED SEAL is at the narrow point in the middle. The GOLD-SILVER BALL is called the TEURIC SPHERE ...

INHALE and draw GOLD -SILVER-CURRENT from the GOLD -SILVER-SHEATH into the center of the Chakra ... as you EXHALE create and EXPAND the BALL to surround the bow tie ...

9 Now ... INHALE and move the GOLD -SILVER-BALL up to the 1ST HARA CENTRE ... 2" BELOW the NAVEL (the 9th SILVER STAR SIGNET SEAL or TAN TIEN) ... EXHALE GENTLY allowing the BALL to EXPAND

10 On the NEXT INHALE move the GOLD-SILVER-BALL up to the SOLAR PLEXUS and EXHALE GENTLY

11 INHALE and move the GOLD-SILVER BALL up to the HEART CENTRE ...
EXHALE GENTLY ... ... INHALE ... drawing more GOLD-SILVER CURRENT into the BALL and THEN EXHALE FORCEFULLY pushing cords of GOLD SILVER CURRENT down each arm and into the PALMS ... bring your fingertips together and feel the fuzzy buzz of TEURIC PHASE 3 CURRENT

You have now activated TEURIC PHASE 3 CURRENT in your palms – and – you are now able to run CURRENT from D4 thru' D8 to transmit to the THYROID GLAND ... to activate and anchor the Rainbow Bridge in others.....

End of Field Technique-5 *The K-RRT Activation Sequence* (5A-B-C-D-E)

You are now ready for the **Amethyst Awakening *Masters Kundalini/DNA Template Activation-2*** (Field Technique-6 *Initiating the Amethyst Awakening*) **or to participate as an active member of *a Khundaray Rainbow Roundtable* (K-RRT) Signet Council** (Field Technique-4 A-B-C). **Wait at least 4 Hours before K-RRT participation, and no longer than 24 hours to maintain the appropriate level of critical mass Khundaray frequency in the body that is need for an effective K-RRT.** **© Rev. Ashayana Deane, 2000**

INITIATING THE AMETHYST AWAKENING

1 **Preparation:** Complete **Maharic Quick Seal** Technique 6 and **Activation Sequence**

2 This technique works to bring in a burst of the Khundaray, Eckatic Blue frequency ...that sets the Amethyst Awakening in motion.

3 Place your attention at the center of your brain, inside your pineal gland. Imagine that you see there a Pale Violet Spark of Light (this is the bottom of the Seal of your 7th Crown Chakra). Imagine that you are going to move this Pale Violet Spark of Light straight up into your 10th Chakra 6" above your head ... imagine that the 10th Chakra is a disc of Light, Blue/ Black – Sapphire.

4 Now see the disc of Light, that was Blue/ Black take on a Violet hue. Try to feel it there, a small horizontal disc ... On the INHALE you will move this disc of Violet-Sapphire Light up to the 24 point Silver Star at the 14th Chakra ...... and, on the EXHALE, move it down through the 10th Chakra, down through the Crown, down the Central vertical Current, down through your Personal Maharic Shield all the way down to the 13th Chakra at the Earth's Core ...

5 Notice, as you do this, a whole series of Violet-Blue Sparks flying out from the Planetary Maharic Shield, as if they are alive, as if electrical communication is taking place. Notice as this happens that the energy flowing up your Maharic Pillar from the Earth Core reflects this change as Violet-Blue energy flows slowly up toward you ... as this energy reaches your personal Maharic Shield, notice that it does the same thing as the Planetary Shields – throws out a shower of Violet-Blue sparks ... all communicating with each other about the mathematical instructions about what to do with your body, your crystal seals, your chakras ...

6 Now, move your awareness to the Pale Silver skin all round your body/ etheric body .. and be aware too of the Main Vertical Current that you brought the Pale Silver cord through ...and at the same time, on each coming INHALE, bring up the Pale Silver-Violet-Sapphire energy, simultaneously, from your Maharic Shield to infuse the Pale Silver skin all round you.

Take a few breaths to do this and watch as the 3 color flicker through you – when they reach the Heart Chakra feel them expand out ... and allow them to travel on up, all the way to the 14th Chakra ... expanding throughout every Chakra as the Pale Silver-Violet-Sapphire energy flows up, through and all around you ... See each Chakra respond with a spiraling burst of Silver-Violet-Sapphire, backward and forward through both sides of the Chakras until they all shift .. try to feel the process as it awakens all the cell's of your body.

The brain cells and brain patterns begin to respond, activating the Fire Letters, setting the grid of frequencies necessary to activate the Fire Codes 7, 10 and 12 in the DNA Template.

Your own **D-12 Christos Avatar identity level will slowly** release the ***Khundaray Activation Frequencies*** through which the Amethyst Awakening progressively unfolds in the DNA Templat and body. This process can be **naturally and safely accelerated** by receiving a **Level-3 MC Regent Ordination transmission** from a qualified **Indigo Child/Eieyani *Level-4 through Leve 6 MC Ordinate* Consummate, Elder Consummate** or **Eckar** that carries the necessary **Amethyst Awakening Khundaray Activating Frequencies** in their Eieyani DNA Templates.

The Merkaba Trinity Key Induction

The ***Merkaba Trinity Key Induction Technique*** begins the process of establishing a **conscious directional relationship** with various levels of your 15-Dimensional Anatomy (or that of your Client). The **Trinity Key Symbols** are **mathematical-geometrical programs** that carry the specific organic structure of **each dimensional frequency band** as it exists within the **D-12 Universal Divine Blueprint**. Imbuing the proper **Symbol Key** into the appropriate area of the personal anatomy can rapidly expedite **restoration the personal Divine Blueprint** within the **DNA Template, Chakra System** and embodied **Kathara Grid**. Use of the Trinity Master Key Symbols that correspond precisely to the natural order of each dimensional frequency band, can **intensify** all applications of **holistic and allopathic healing**, as well as progressively and systematically assist in the process of accelerating **DNA Template** healing and **activation.** Every **condition** within the body-mind-spirit system has a specific **Energy Signature** unique to its own construction. Every **dis-ease** condition within any aspect of the personal experience (physical, emotional, mental, spiritual, financial, social, etc.) is created and **held in manifestation** by a specific set of mathematical – geometrical energy relationships that are **stored** within the embodied **Kathara Grid** and **DNA Template** in the form of **Symbol Keys**. The mathematical-geometrical energy relationships that serve as the **blueprints** upon which experiential manifestation will emerge can be perceived by the conscious identity in its Symbol translation. When using the **Trinity Master Key Symbols**, you are **resetting and activating very specific portions** of the personal **Divine Blueprint** (D-12 Pre-matter Maharic Shield) into a naturally harmonious relationship with Universal Order (the organic structure of dimensionalized frequency bands). The Trinity Master Keys provided in this Technique trigger activation of very specific **Fire Letters** (Keylons) within the DNA Template, allowing the DNA Template to receive directly the **new electrical instructions** corresponding the personal Divine Blueprint. This technique can be used with Kathara Healing Techniques from Kathara Level-1, with any other healing modality or singly after activating the D-12 **Maharata Current** via **Techniue-6, *The Maharic Quick Seal.***

It is **necessary** to initiate a **D-12 Maharaic Seal** in order to run **any Symbol Key program** into the DNA Template and Level-1 Kathara Grid; it is the strength of the D-12 Maharata Current that allows access to the deepest levels of the Personal Shields and Divine Blueprint. The **Trinity Master Key Symbols** are a **set of 3 Symbol Keys** that are to be used **in sequence.** The first two Trinity Keys, the **Initiating Keys**, are used in **every application** to open the embodied Level-1 Kathara Grid to receive new instructions. The third Trinity Master Key Symbol, the **Transmitting Key,** corresponds directly to the Divine Blueprint of **one dimensional frequency band** and its corresponding **Kathara Center, DNA Strand Template, Chakra** and related body regions, **Axia-tonal Line, Auric Field Level** and **station of consciousness**. In a **Trinity Key Induction Session**, one can choose to work on only **one dimension** (Chakra-DNA Strand Template-Kathra Center-Axia-tonal Line-Auric Level) via its Transmitting Key, or each of the **12 Transmitting Key** of the Universal Kathara can be used, **in sequence**, following induction of the two Initiating Keys. The process of using the Trinity Keys is simple; the **Chakra** that corresponds to the Transmitting Key/ dimension/DNA Strand with which you desire to work is used as the **vortex** through which the Trinity Keys are **INDUCED** into the corresponding **Kathara Center**. From the Kathara Center, the Trinity Keys electrically pass on to the **DNA Template** and from there into the **Axia-tonal Line system** and corresponding areas of the body-mind-spirit system. Use of the Trinity Key Induction Technique progressively assists in activating the personal **Merkaba Vehicle** while **amplifying and expediting restoration** of the personal Divine Blueprint.

Technique # 9: Merkaba Trinity Key Induction

1. Activate the Maharata Current via **Technique-6: *The Maharic Quick Seal*** and decide which Transmitting Key(s) you will use. **Trace** the **3 Trinity Symbol Keys** onto **3 small squares of paper.**

2. First, place each of the papers with the two Initiating Keys **face up on the floor**, then **stand** (barefoot or socks only) with **one foot on top of each of the papers; Initiating Key #1** under the **LEFT foot, Key #2** under the **RIGHT foot.** (Note: To run Trinity Key Induction for a Client, have them recline on their back and place the papers with Initiating Keys between your palms and the soles of Client's feet. As introduced in Kathara Level-1, use your **palm Chakras** to **transmit** the Symbols and the Pale-Silver Maharata Current, using the same action as described below, into the **Client's foot Chakras**; Key-1LEFT foot-***right hand transmission***, Key-2 RIGHT foot-***left hand transmission***.) In Self-induction, the papers with Symbols should be positioned beneath the **balls of your feet**, in the area of the main **Chakra** on the sole of each foot. Simply begin to **breathe deeply** and slowly for a few minutes. With each **INHALE** draw a **thick stream** of **Pale-Silver Maharata Current** from Earth's core through the **Central Vertical Current** of the body and out the top of the head to the **14th Chakra** 36-inches above the head. With each **EXHALE,** imagine a grapefruit sized Pale-Silver **Maharic Ball** rapidly moving down your Central Vertical Current. When the Maharic Ball reaches your 2nd-Chakra near the navel, imagine the Ball splitting into **Two Balls**, each continuing to **travel down each leg and out your feet Chakras**, through the **Symbol Keys**. Once the Two Balls of Maharic Current have passed through the Symbol Keys, imagine that they **re-merge** into the **one grapefruit sized Pale-Silver Ball** that continues to move downward into the **13th Chakra** at Earth's core. **Continue** this process until you sense a **momentary slight warmth, tingling or subtle itching** at the **balls of your feet**. These mild, **momentary sensations,** called the **CUE RESPONSE**, will grow stronger the more frequently you use the feet Chakras for Symbol Key induction. Once you have noticed the **Cue Response**, you have **successfully induced** the two **Initiating Trinity Keys** and it is now time to utilize the remaining **Transmitting Key**.

3. If you have chosen to use the Transmitting Key for D-1-Strand-1-Axiatonal Line-1-**Chakra-1**, continue **standing** for the final Symbol Key Induction, placing the paper with the Transmitting Key face up on the floor between **slightly parted feet; do not stand on Symbol Key paper** for **Base Chakra Induction.** For all other Chakras, **recline on your back** and place the paper with the Transmitting Key **directly on top of the Chakra** to which it corresponds, **on the front of the body**. Use each **INHALE** breath to drawn Maharata Current up from Earth's Core, into the Central Vertical Current **only as far up as the selected Chakra**. On each **EXHALE**, push Pale-Silver Maharata Current **out from the Central Verticle Current** of the body and **into the Chakra**, imagining that the Chakra is progressively turning into a **radiant vortex of Pale-silver light** that **spins faster and faster**. When you begin to feel a bit of warmth, tingling, energy running or itching of the skin **at the Chakra region** (the **Cue Response**), use a final **INHALE breath** to draw the image of the Symbol **down through the Chakra into the body**, and into the **tiny Crystal Seal** that links the Chakra to the Central Vertical Current. Take a **FINAL exaggerated EXHALE**, and imagine that you have **pushed the energy of the Transmitting Symbol Key** out of the Chakra into the **corresponding level of the Auric Field.** Once imbued into the **Auric Field** the single image of the Symbol then **replicates automatically and rapidly**, creating **millions of mini-replicas of the Symbol** within your bio-energetic field. When the **Cue Response** sensation at the Chakra has **completely ceased**, you have **successfully induced** the entire **mathematiucal program** of the Transmitting Symbol into the corresponding Kathara Center, DNA Strand Template, Axia-tonal Line, body region and level of consciousness.

Technique-9: Merkaba Trinity Key Induction

Trinity Master Key Selection Chart

© 2001 Ashayana Deane

12 Transmitting Keys: ***Correspond to each Dimension-Chakra-Kathara Center-Axia-tonal Line etc.***

Number in circle represents the **number of Chakra** into which corresponding Transmitting Key Symbol will be induced.

Note: The **Smaller Symbols** placed **outside of SOME circles** are **Amplifier Key Symbols** corresponding to the Chakra by which they are positioned. The Amplifier Keys can be used **in place of** the Transmitting Key within the circle, or the two Keys can be drawn on one paper for **simultaneous induction**. It is **recommended** to begin with the Transmitting Key inside the circle, then after a few induction exercise, switch to the Amplifier Key, and after several exercises with the Amplifier Key, use both Transmitting and Amplifier Keys simultaneously.

Two Initiating Keys







Select one or more Transmitting Keys for induction following induction of the two Initiating Keys above.

In **Kathara Level-1** we have learned of the innate structures of multidimensional reality and how these structures are intimately intertwined with the ***15-Dimensional Human Anatomy*** and levels of personal identity through the personal ***Maharic Shield*** and ***DNA Template***. In rediscovering these long forgotten aspects of the Human condition and our inherently implied relationship to Universal Order, we've become empowered to draw upon the natural **Triadic Phase Currents** indigenous to our personal biology and universal structure, in order to take an active hand in personal *Conscious Bio-spiritual Evolution* and healing, and healing facilitation for others. ***Techniques 1-5*** (#1-*Awakening the Mentor*, #2-*Maharic Seal and Liquid Light Cleanse*, #3-*Opening the Healing Channels Doradic Phase-1 Current*, #4-*Multi-vector Holographic Recoding Kathara Scan* and #5- *The Maharic Infusion* client session) contained within *Chapters 1-4* of *the Kathara Level-1 Maharic Recoding Process* enable us to begin conscious interaction with the "invisible" processes of **Body-Mind-Spirit Evolution** that are inherent to Human design. In our introduction to **Kathara Level-2** we have begun to explore the greater nature of ***Universal Life Force Currents***, the "mysterious" sciences of ***Merkaba Mechanics*** and their indelible connection to our personal evolution and **Bio-spiritual Actualization Processes**. ***Techniques 6-7-8-9-12*** (#6-*Maharic Quick Seal*, #7-*Ps13 Tribal Shield Activation*, #8-*Merkaba Salutations*, #9-*Merkaba Trinity Key Induction* and #12 *Kee-Ra-Sha Activation Sequence*) so far explored within this *Chapter 5* of the *Kathara Level-2 Introduction* enable us to advance our conscious interaction with the processes of personal Body-Mind-Spirit Evolution and Bio-Spiritual Actualization. As we increase our personal abilities to understand, embody, hold and direct the inherent powers of the Universal Life Force Currents, and to access the levels of personal spiritual identity and wisdom to which they correspond, we progressively increase our ability to consciously facilitate healing in ourselves and for others we may choose to serve. An in-depth study of Universal Life Force Currents and Masters Merkaba Mechanics involves cultivating a necessary familiarity with a broad spectrum of interrelated subjects that take us into the heart of the Science of Vibrational Mechancis and Holographic Creation Physics, as well as into the very Soul of our spiritual relationship to consciousness, ourselves, each other, our world and God. Mastery of Merkaba Mechanics is an attribute inherent to achieving the state of consciousness often called "Ascended Mastery", which requires much in-depth study into the "mysteries" of creation. However, a functional mastery of Merkaba and the related constructs of the personal "Inner Templar" system upon which the personal body and identity manifest can be achieved through gaining familiarity with and actively employing core mechanics of the personal Merkabic System.

As our *Kathara Level-2 Introduction* began, our exploration of active techniques of *Tribal Shield Activation*, *Merkaba Salutations* and *Trinity Keys* set us on the path of becoming functionally able to consciously direct elementary operations of the personal Merkaba Vehicle and Life Force Currents, as a means of expediting our progress of Bio-Spiritual Evolution through DNA Template/Merkaba Field Activation. As our *Kathara Level-2 Introduction* continues, we will begin to explore the seemingly "***magical world of Merkaba"***, rediscovering the very tangible importance of the **Merkaba Field** in relation to the inherent dynamics of DNA, health, healing and spiritual actualization. To achieve genuine integrity in the facilitation of healing for others, one must simultaneously strive to heal and actualize the self. The greater the level of health and spiritual actualization possessed by a healing facilitator, the greater will be the facilitation of healing for the client to whom the healing facilitator is in service. As Kathara Level-2 Introduction draws to a close we will begin an introductory exploration of the "Ancient Secrets" of the **Veca Codes,** so that we may engage practical application of two additional techniques of Photo-Radionic and Photo-Sonic **Merkabic Healing. Techinque-#10** ***Restoring the Trion Field Veca Code Activation*** and **Technique-#11**-***Restoring the Meajhe Field Eckasha Activation*** will provide us with powerful tools of the Kathara Healing trade that will ***substantially increase the quality, amount and power of interdimensional frequency we are capable of receiving, holding and transmitting***. Through these simple but effective Merkabic Healing tools we can expedite our processes of personal healing and spiritual actualization, thereby enabling us to become more effective and powerful healing facilitators in our client session service.

The "Magic of Merkaba"

Spiritual-science teachings of **Merkaba Mechanics** emerge from the most ancient of times; record of Merkaba teachings is most often found in obscure traditional "Occult" texts or within New Age "Ascension" teachings. Genuine Merkaba Sciences hold the keys to understanding and mastering the processes of both spiritual and physical evolution, on a personal, planetary, galactic and universal level. Merkaba Mechanics are not the product of "science fiction", nor are they "magical hocus-pocus" of "occult mysticism". Merkaba Mechanics are not "magic" at all, but rather an intrinsic element of universal Primal Order. **Merkaba Fields**, sets of Star-tetrahedron shaped counter-rotating electro-magnetic energy fields within and surrounding manifest forms, are simply an inherent element of the15-Dimensional Anatomy of form manifestation and the Primal Order structure of multidimensional Creation Physics. In the "*Transduction Sequence*" described in *Kathara Level-1*, the sequence of energy transmutation by which conscious energy manifests into tangible biological form, the *Merkaba Field* represents the structure and stage of energy dynamics by which *Primal Life Force Currents* pass from the scalar-wave-template of the embodied *Kathara Grid levels* into the *DNA Template*. In terms of non-biological form manifestation, all forms possess an inherent structure of interwoven Merkaba Fields through which Primal Current energy is transmuted from the Kathara Grid Core scalar-template level into the outer levels of the Kathara Grid and Axiom Line template upon which the specialized structure of the form builds up, through particle/anti-particle accretion, into physical manifestation. Merkaba Mechanics seem "magical" only when the inherent **"Laws of Nature"** that govern the dynamics of **Multidimensional Universal Unified Field Physics** are not understood.

Through understanding of genuine *Universal Unified Field Science, Merkaba Fields*, and their inherent dynamics as utilized in the study of *Merkaba Mechanics*, are simply recognized as natural elements of the processes inherent to Creation Physics and the naturally occurring, organic relationships between Energy Consciousness, and the Holographic Manifestation of form.

As Merkaba Fields are an intrinsic, significant and natural part of the Body-Mind-Spirit anatomy, the study and application of Merkaba Mechanics is an essential component in any Masters Holistic Healing or Spiritual Actualization program. Merkaba Mechanics are *"Scientific"* in that they represent a core element within the innate processes of creation and manifestation that are intrinsic to the sciences of Creation Physics. Merkaba Mechanics are also "*Spiritual"* in that it is through the innate structures and dynamics of Creation Physics, of which Merkaba Mechanics are a natural part, that consciousness enters the manifest arena in the form of sentient, individuated, multidimensional identity. The "body, mind and spirit" of every manifest being is formed through and governed by the natural laws of Creation Physics and Primal Order. The Laws of Creation Physics and Primal Order are designed and maintained by and within a non-manifest, intelligent, central Consciousness Force and Source of Creation that is commonly referred to as "**God**". God expresses It-Self in the form of *Conscious-energy Constructs* that carry the living "Spirit and Consciousness of God" in the form of **Primal Life Force Currents**, which are the foundations for macrocosmic and microcosmic creation and manifestation. Merkaba Fields and the mechanics by which they function, are an indelible part of the physics of Creation and Consciousness, and are thus intimately involved with the Bio-Spiritual processes inherent to **Spiritual Actualization**.

Merkaba Fields, DNA, Healing and Spiritual Actualization

Particles, People, Planets, Galaxies and Universes all have **sets of interwoven Merkaba Fields** that serve as the "**core Primal Life Force Current circulation system**" between the Cosmic, Universal, Galactic, Planetary and Personal "Divine Blueprint" Kathara Grid scalar-templates and the manifestation of those blueprints into the tangible structures of matter. Merkaba Fields are the "**carriers of consciousness**" and the "**engines of energy**" by which physically manifest forms are created, maintained and evolved through the Holographic Unified Field of manifest space-time-matter reality. In relation to the processes of personal bio-spiritual healing and spiritual actualization, the personal Merkaba Field is an intrinsic aspect of 15-Dimensional Anatomy that directly governs the function of the physical, emotional, mental and spiritual body systems. **The multidimensional structure of the personal Merkaba Field is the system of electro-magnetic interface by which the Primal Life Force Currents and Consciousness of God-Source and Its sentient individuations pass from the Kathara Grid Core Template into the scalar-wave DNA Template that holds the blueprint for the physical-chemical biological DNA.** This reality of **Merkaba Field-DNA Connection** implies that the personal Merkaba Field is directly related to the function or dysfunction of the **biological genetic code.** As the Merkaba Field "carries the energy of consciousness" into the DNA and biological vessel, the *Merkaba Field-DNA Connection* also implies that the potentialities of consciousness and embodiment of spiritual identity, while a being is ensconced within the Time Matrix, are dependant upon the condition and function of the personal Merkaba Field, DNA Template and Kathara Grid.

*Merkaba Fields are the "**carriers of consciousness**" and the "**engines of energy**" by which physically manifest forms are created, maintained and evolved through the Holographic Unified Field of manifest space-time-matter reality.*

Universal Merkaba Field Structure

Basic Merkaba Field structure is relatively simple. Viewed Macrocosmically, in a 15-Dimensional Time Matrix there are **15 sets** of counter-rotating electromagnetic **Merkaba Spirals** that form **15 Universal Dimensional Merkaba Fields.** A "**Merkaba Field**" is composed of a set of **2 Merkaba Spirals**, one electrical-transmitting "cone", the other magnetic-receiving "inverted cone"; the 2 "cones" of the Merkaba Spirals, which operate as a **White Hole/Black Hole Pair**, intersect each other, creating a system of energy vortices that form an **Elliptical Sphere** of energy within the center of the intersected Merkaba Spirals. The Sphere of energy at the center of a Merkaba Field is called the **FORM CONSTANT**; it is a "**spherical energy domain**" within which the individuation of consciousness and holographic manifestation/projection of form can take place, akin to an "energy egg" within which manifest reality occurs. Within this Sphere of energy at the center of a Merkaba Field, the template-blueprints of a form are held "constant", allowing conscious Partiki units, particles, anti-particles and ante-particles to accrete in specific ratios to "fill out the form in matter". Within the Form Constant sphere, consciousness is able to perceive the **holographic illusion** of externalized space-time-matter manifestation, as the scalar-template of the form is held fixed within the sphere. The "hologram" appears to remain "constant" within the Form Constant sphere while consciousness is focused within the frequency bands of which the Merkaba Field is composed.

On the macrocosmic universal scale, the Form Constant of each Universal Dimensional Merkaba Field creates a single, elliptical-sphere shaped electromagnetic domain of frequency that represents a single dimension of manifestation. Following the innate mathematical-geometrical structure of Primal Order, the 15 Universal Dimensional Merkaba Fields group into **5 sets** of 3-Dimensional Merkaba Fields called **Universal Harmonic Merkaba Fields**. The 3 Form Constant Spheres from each set of 3 Universal Dimensional Merkaba Fields forms a **Universal HOVA BODY**, or a "Harmonic Universe" electromagnetic domain. Following the mathematical Primal Order program of a Time Matrix as held within the Universal Kathara Grid template and transmitted through the rotation ratios of the Harmonic and Dimensional Merkaba Fields, each of the 3 dimensional levels of a Universal Hova Body holds the Partiki units, consciousness and matter particulates of its dimensional field into a specific angle and speed of rotation. The 3-Dimensional Harmonic Merkaba Field controls the relationship of particle rotation angle (angular rotation of particle spin or "**ARPS**") and rotation speed between each of the 3 Dimensional Merkaba Fields, holding together a 3-dimensional electromagnetic domain, within which consciousness can experience a 3-dimensional space-time-matter hologram. In a single 15-Dimensional Time Matrix there are thus 15 singular Universal Dimensional Merkaba Fields governed by 5 larger 3-dimensional Universal Harmonic Merkaba Fields, all of which circulate consciousness in the form of Primal Life Force Currents into and out of the hologram of manifestation. The seeming solidity and durability of an externally manifest matter-field in space-time is created, maintained, perpetuated and completely dependent upon the intrinsic function of the Universal Merkaba Fields.

Within the larger Form Constant elliptical-spheres of the 5 Universal Hova Bodies of a 15-Dimensional Time Matrix, the holographic perceptual realities of space-time-matter take place. Every being or thing in manifest form enters its reality hologram by *taking on the mathematical program* of first the *Universal Kathara Grid* and *5 Universal Hova Bodies*, which set the "Life Stream" or "Stream of Consciousness" of Primal Creation

Currents in motion following the specific **Harmonic Merkaba Field spin ratios** characteristic to each Harmonic Universe System. Galaxies are formed in this way, as individualized expressions of the greater Harmonic Universe of which they are a part. **Universal Harmonic and Dimensional Merkaba Fields** govern the birth, evolution and transmutation of the **galaxies** within them. **Galactic Harmonic and Dimensional Merkaba Fields** govern the birth, evolution and transmutation of **star systems and planets** within them. **Planetary Harmonic and Dimensional Merkaba Fields** govern the birth, evolution and transmutation/death cycles of the **species and matter forms** existing upon the planet. The **Personal Merkaba Fields** of species and individuals direct the function of the personal **DNA Template, chemical DNA** and **biological genetic code**, thus governing the birth, evolution and transmutation processes of individual organisms. The mathematical-geometrical programs of the **Primal Order "Divine Blueprint"** that govern Merkaba Field formation and spin ratios are held within the Universal, Galactic, Planetary, Species and Personal Kathara Grid structures. In a singular 15-Dimensional Time Matrix, the **inter-linked Universal, Galactic and Planetary Harmonic and Dimensional Merkaba Fields** circulate Primal Life Force Currents and consciousness into and out of manifestation in space-time.

Universal Merkaba Fields



Electrical ***Merkaba Spiral***
Rotates Clockwise
"White Hole" Vortex



Magnetic ***Merkaba Spiral***
Rotates Counter-clockwise
"Black Hole" Vortex



FORM CONSTANT

One ***Merkaba Field*** =
a set of 2 *Merkaba Spirals*
Black-White Hole Pair

Universal Merkaba Field of One 15-Dimensional Time Matrix



HU-5
HU-4
Density-5 Dimensions 13-14-15
Primal Kee-Ra-ShA Light
Trion Fields
D-13-14-15
D-10-11-12
D-7-8-9
HU-3
S O U R C E
Energy Matrix Khundaray
Primal Sound Vibration
Meajhe Fields
D-4-5-6
HU-2
D-1-2-3
HU-1
HU-
= 5 **Form Constant** "Spheres"
form 5 Harmonic Universes
each with 3 dimensions and
3 **Universal *Dimensional***
Merkaba Fields
One 15-Dimensional Time
Matrix has **15 Universal**
***Dimensional* Merkaba Fields**
& 5 Universal *Harmonic* (3-D)
Merkaba Fields

The Personal Merkaba, Trion-Meajhe Field, Radial Body and Radis.

Each individual being receives its life force, consciousness, biology and manifest hologram through the innate connection between the **Personal Merkaba Field** and the Merkaba Fields of the Planet, Galaxy, Universe and Time Matrix. When the **D-12 Pre-matter Divine "Christos" Blueprint** is expressing naturally in a planetary system, the organisms on the planet circulate Life Force Currents and consciousness through the physical and "spiritual" bodies via the Personal and Planetary Merkaba Fields. The **Planetary Merkaba Field** circulates Life Force Currents through the **Personal Kathara Grid** template (morphogenetic field) of the organism via the **Planetary Bio-Feed Interface System.** The organism's **Personal Merkaba Field** then picks up the energy from the Kathara Grid and continues to circulate the Life Force Currents from the Personal Kathara Grid and into the **Maharic Shield imprint** in the **DNA Template** that is held within the Level-1 *Kathra 12-Tree Grid,* Level-2 *Kathara Crystal Seals-Hara Grid* and Level-3 *Kathara Diodic Grid.* From the Maharic Shield imprint in the Kathara Grid, the Personal Merkaba Fields distribute the Life Force Currents and consciousness into the **DNA/RNA Template** and **Axiom Lines.** The Life Force Current continues circulation from the DNA/RNA Template and Axiom Lines into the **Personal Hova Bodies** and **Auric Field**, to the **Chakras** and **Meridian Lines**. Passing through the Meridian Lines, the Life Force Current, imbued with the specific mathematical manifestation program picked up from the Kathara Grid Divine Blueprint Template, then enters a state of final transmutation into 3-dimensional particles by passing through an electrostatic **Repulsion Zone** barrier that exists surrounding each 3-dimensional Hova Body.

The frequency barrier surrounding each 3-dimensional Hova Body forms as **thin, skin-like membrane** or **"Tissue Capsule"** surrounding each of the 5 Hova Bodies in the 15-Dimensional Anatomy. The **Hova Capsule** membrane is composed of Density-5 **Primal Light** ante-matter units, called **TRION UNITS**, that exist in the form of fixed standing-columnar-scalar-light waves made of **Keylons**, or 3-dimensional **Partiki Grids**. The Trion Units and Keylon Partiki Grids within them are anchored upon a fixed field template of **Primal Sound** units, called **MEAJHE UNITS**, which exist as fixed points of mathematically organized vibration. The outer layer of each Hova Capsule is called the **Trion Field**, as it is composed of **Trions**, or units of Density-5 ante-matter Primal Light. The inner portion of the Hova Capsule is called the **Meajhe Field** as it is composed of **Meajhons** (mE' yans) or fixed points of Primal Sound vibration from the **Energy Matrix** beyond the holographic manifestation of the Time Matrix Light Fields. The collective body of the 5 Hova Capsules is called the **RADIAL BODY** or **Trion-Meajhe Field**. All manifest forms possess a core Radial Body/ Trion-Meajhe Field **Hova Capsule** structure as part of the intrinsic 15-Dimensional anatomy.

As multidimensional Life Force Currents pass through the Meridian Lines and into each of the 5 layers of the Radial Body, the energy currents and the consciousness carried upon them project the mathematical program of the Divine Blueprint into the Trion-Meajhe Field of each of the 5 Hova Capsules. Within the Hova Capsule, the individualized raw Life Force Currents enter a system of 3-dimensional energy conduits or **rivulets** called **Radis**, which are the "turnstiles" between "manifest matter" and "conscious energy". The Radis draw in the Life Force Currents with their manifestation program through the Trion-Meajhe Field, then polarize and break up the Trion and Meajhon units into negatively and positively charged electrical sub-units called **Mions** and **Dions**. Partiki, Keylons, Meajhons, Trions, Mions and Dions belong to a category of primal building blocks known as **IONIC PARTICULATES,** which are the building blocks of consciousness, energy, light, sound and scalar-wave-fields that form the blueprints upon which all matter manifests. **Trions** are electrostatic particulates that have both a negative and positive electrical charge, which renders them neutral or static; they are the foundations of what becomes **Ante-matter** Primal Light particles of pre-visible gaseous light. Meajhons are static units of pre-sound standing waves, also possessing neutral electrical charge, that form the Primal Sound Fields of the Energy Matrix. Within the structures of the Radial Body Radis rivulates, Trions and Meajhons are **polarized** into negative charged **Mions** ("Base Magnetic" vibrating pre-sound particulates, foundations of negatively charged particles such as electrons, originating from the Universal Particle Particum field.) and positively charged **Dions** ("Base Electrical" oscillating pre-light particulates, foundations of positively charged particles such as protons, originating from the Universal Anti-particle Partika field). Together, Mions and Dions create the **electromagnetic Ionic Particulate base field** within the Merkabic Form Constant through which particles emerge via Ionic Particulate accretion into tangible matter units.

The Trion-Meajhe Field Radial Body of any manifest form represents the 5-Density "Veil" through which consciousness-as-Primal Life Force moves into and out of externalized 3-dimensional manifestation. **Merkaba Fields are the "energy engines and consciousness carriers" by which Life Force and consciousness are circulated between the internal Kathara Grid scalar template and the Trion-Meajhe Field Radial Body "veil" as they pass into and out of external expression.** The perpetual polarization, electromagnetic expression and de-polarization of the Life Force Currents within the Merkaba Field Form Constant electromagnetic domain is the process by which the holographic projection of matter is perpetually brought into and taken out of perceptually experiential being. The **Radial Body** Trion-Meajhe Field receives, via Merkaba Field circulation, the template or "design" for its particle manifestation from the "instructions" held in the Divine Blueprint Maharic Shield and DNA Template of the Kathara Grid. Manifestation instructions pass from the Kathara Grid to the DNA Template via the Merkaba Field, then continue into the energy circulation systems (Axiom Lines, Hova Bodies, Chakras, Meridians) that deliver the instructions to the Radial Body for particulate manifestation. In biological life forms, the Radial Body and Radis then translate the scalar-wave blueprint of the DNA Template and Kathara Grid into the polarized Ionic Particulate Mion-Dion sub-units, which accrete following the DNA Template instructions to form sub-atomic, atomic, molecular, chemical DNA, physical matter form- the vehicles of embodied consciousness. The **Merkaba Field** also receives its instructions for energy circulation from the Kathara Grid and DNA Template.

The Radial Body Tissue Capsule, Radis
& the Mechanics of Manifestation

The **Radial Body** exists as a thin "***Tissue Capsule***" surrounding each of the **5 Hova Bodies.** Each of the **5 Radial Body Levels** are composed of an **Outer Layer** of electrostatic neutral-charge **Trion Primal Light Units** and an **Inner Layer** of **Meajhon Primal Sound Units.** Each of the 5 Levels of the Radial Body serve as the **polarizing filter or "lens"** through which **Multidimensional Primal Life Force Currents** flow, via **Merkaba Field** circulation, from the Kathara Grid and DNA Template, into manifest form.


One Level of the Radial Body
Trion Field Outer Layer
Meajhe Field Inner Layer
One Hova Body
5 "Nested" Hova Bodies & Radial Body Capsules

Radial Body Transduction-Manifestation Sequence



Primal Life Force Current *Partiki Units* Planetary Merkaba Field
(Units of Consciousness/Primal Substance)
Partika and Particum Units Kathara Template/Maharic Shield
(Polarized Primal Substance Units)
3-D Partiki Grid Keylon Units/Codes/Grid Morph. Keylon Thought-Form Field
(3-D Crystallized Pre-Light-Sound units, unit groups and grids)
Merkaba Field *Keylons* (3-D Crystallized Pre-Light-Sound Keylon Unit electromagnetic spiral sets)

DNA/RNA Template *Keylons* Kathara Grid (3-D Crystallized Pre-Light-Sound unit Template)
Axiom Lines-Hova Bodies-Auric Field-Chakras-Meridian Lines
Trion & Meajhon *Electrostatic Units* 5 Radial Body "Lens" Levels Trion-Meajhe Field
Dion (+) & Mion (-) Ionic Particulate *Electromagnetic Units* Radis Lines

Sub/Atomic Particles/Anti-Particles, Molecules...Chemical DNA
Physical Matter Body Hologram "Chemical Lens"

External Hologram Projection of Space-Time-Matter
Primal Life Force Currents ➡ Planetary Merkaba Field Partiki ➡ Kathara Grid -Partika-Particum ➡ Maharic Shield Divine Blueprint ➡ Keylon Morphogenetic "Thought-form" Field ➡ Merkaba Fields ➡ Kathara Grid DNA/RNA Template ➡ Axiom Lines ➡ Hova Bodies ➡ Auric Field ➡ Chakras ➡ Meridian Lines ➡ Trion-Meajhe Field 5 Radial Body Levels ⇨ Radis Lines ⇨ Mion & Dion Ionic Particulates ⇨ Strong and Weak Nuclear Force, Electromagnetism ⇨ Quarks, Muons, Measons, Sub-atomic & Atomic Particles and Anti-Particles ⇨ Blueprint translation into Nuclei, Molecules, Elements, Compounds, Chemicals ⇨ Chemical DNA Template and "Chemical Lens" of the manifest body form ⇨ Manifest Hologram ▭

Reverse Transduction De-Manifestation Sequence: matter- *chemical* DNA- *Sub-Atomic units*- Radis *Mion/Dion units*- Radial Body *Trion-Meajhon units*- Meridian Line-Chakra-Auric Field-Hova Body-Axion Line-DNA Template-Merkaba Field-Morphogenetic Thought-form Field *Keylon Grids & units*- Maharic Shield Template & Kathara Grid *Partika and Particum Units*- Planetary Merkaba Field *Partiki Units* of consciousness.

Radial Body Transduction-Manifestation Sequence

1. From the **Planetary Merkaba Field** (via the Planetary Shield, Axiom Lines, Hova Bodies Vortices, Meridian Lines and Radial Bodies), **rhythmic pulses of Conscious Primal Life Force Currents** enter the species and personal **Kathara Grid Core Template** as Primal Units of **Partiki**.

2. Within the **Kathara Grid Template** the **Partiki Units** pick up the **mathematical-geometrical program** from the **Maharic Shield** "Divine Blueprint" Template, **polarize** to form **Particum and Partika Units**, then **accrete** to form **3-dimensional** electro-magnetic **Partiki Grids** called **Keylons**. The Keylons group together mathematically forming complex templates of **Crystallized Keylon Codes** (or "***Keylon Thought-Crystals***"), which create a mathematically encoded **3-dimensional Morphogenetic Field ("Keylon Thought-form Field"** or Morphogenetic **"Keylon Crystal Grid"**) carrying the manifestation blueprint program of the Maharic Shield.

3. As the Primal Life Force Currents of the electromagnetic Keylon Crystal Grid interact with each other following the program of the D-12 Pre-matter **Universal Divine Blueprint**, they form **sets of spiraling electro-magnetic vortices** called **Merkaba Fields**, which carry the Maharic Shield-Kathara Grid Blueprint program into formation of the **DNA/RNA Template** Keylon Crystal Grid.

4. From the DNA/RNA Template held in the Kathara Grid, Primal Life Force Current carries the **Keylon Crystal Grid** of the blueprint into the **Axiom Lines, Hova Bodies, Auric Field, Chakras** and **Meridian Line** systems, finally carrying the Keylon Crystal Grid of the Divine Blueprint into the **5 Radial Body "Tissue Capsule" Levels.**

5. Within the **5 Levels of the Radial Body** the **incoming Keylon Crystal Grid** translates into **electrostatic Trion-Primal Pre-Light Units** (gaseous pre-light Ante-matter) and **Meajhon-Primal Pre-Sound Units** (units of vibrating pre-sound energy) that possess a **neutral electrical charge.** The **Encoded Primal Life Force Currents** (PLFCurrents+ Keylon Crystal Grid blueprint program) are converted into a **Trion-Meajhe Field blueprint replica;** a " Primal Light-Sound" translation of the original blueprint.

6. The **Encoded Primal Life Force Currents** then travel, **AS the Encoded Trion-Meajhe Field**, into the **Radis Lines** in each of the 5 Levels of the Radial Body. The Radis Lines first **replicate and store** the **mathematical blueprint encoding** of the **Trion-Meajhe Field,** then **polarize** the neutrally charged Trion-Meajhe units into **electromagnetic units** called **Mion** (-) and **Dion** (+) ***Ionic Particulates***. The **replicated Trion-Meajhe Field blueprint** becomes part of the "Primal ***Pre-sound*** vibration" ***Meajhe Field*** **Inner Layer** of the ***Radial Body*** **Trion-Meajhe Field**, serving as a living "***Memory Matrix***" composed of **Meajhon Unit** "Primal Pre-sound vibration". The **polarized Mion/Dion Units** become the foundations upon which the **"Strong and Weak Nuclear Force", Electromagnetism, quarks, Muons, Measons, Sub-atomic Particles** and **Anti-particles** etc. form. Particum-based **Mions** ("Base magentic) become **particles, negative electrical charge units** like **electrons** and **sound spectra**. Partika-based **Dions** become **anti-particles, positive electrical charge units** like **protons** and **light spectra.**

Radial Body Transduction-Manifestation Sequence- **Continued** page 2

7. Blueprint Encoded Primal Life Force Currents in the form of a **Mion-Dion Field** then translate the original Kathara Grid Blueprint into **Quarks, Muons, Measons, Sub-atomic** and **Atomic particles** and **anti-particles**, which **accrete** according to the blueprint to form **molecules, elements, chemicals**, the **Chemical DNA Blueprint** and the **physically manifest body form**. As this occurs the **body image "flashes on"** into manifestation as a **Pulse of Life Force Consciousness** carrying the **Chemically Translated Holographic Image** of the body form template blueprint. This Pulse of Consciousness continues to expand from the Kathara Grid and DNA via the Transduction Sequence, through and beyond manifestation of the body image and into **projection of portions of the Dimensional Unified Field** that **holographically translate** into **individualized experience** within a perceived **Common Planetary Time Rhythm and Matter Field.**

NOTE: ***An individual will holographically perceive and experience only the portions of the Dimensional Unified Field mathematical-geometrical program that are encoded within the personal Maharic Shield, species Tribal Shield and Planetary, Galactic and Universal Shield aspects of the personal Kathara Grid and DNA Template.***

A **global population** experiences a **common planetary reality field and time continuum** because the Kathara Grid Template and DNA of all beings entering a planetary field **adopt the common imprint** of the mathematical-geometrical program of the **Planetary Kathara Grid** blueprint in order to enter into the electromagnetic domain of the Planet's Form Constant Hova Body structure for experiential manifestation. Members of a **singular species** share a common **species Tribal Shield** template through which a **common Chemical Body Form** and perceptual orientation holographically manifest. The imprint for **individuality** in biological form, life experience variation and the application of **Free Will Choice** is held within the mathematical program of the **personal Maharic Shield** D-12 Pre-Matter **Divine "Christos" Blueprint**. Imbued within the mathematical program of the **Human species Tribal Shield**, and that of some other species, is the imprint for **probability** to exist. The Human species Tribal and Maharic Shields carry a program that allows for **new programs of probable creation** to be **added** to the personal and species **Kathara Grid**, allowing the embodied consciousness to retain **a degree of direct influence** over what sets of mathematical programs will be called into personal experiential Holographic Expression from the personal Maharic Shield Template. **Creative variation** on the original personal, species, planetary and galactic Divine Blueprint is possible as long as the new probabilities do not deviate so excessively from the Pre-set programs and **Original Intentions** of the Universal Divine Blueprint that the **structural integrity** and **Source-God Will Intentions** for our Time Matrix become **irreparably compromised. Free Will thus exists within a pre-set framework of overriding Divine Will**, and is permitted free reign in the manufacture of **co-creative experiential probability** up to the point at which the Original Divine Will of Source and the creative framework itself become unduly jeopardized.

8. The physical body form serves as a **Chemical Lens** through which ***portions*** of the **Dimensional Unified Field** are perceived by the embodied consciousness as a **3-dimensional Hologram,** as the Primal Life Force Currents continually carry **pulses of the individuated consciousness** through the ***Transduction Sequence*** from Kathara Grid, through the DNA, to the manifest Chemical Lens of the physical body structure and Holographic "external" reality field projection.

Radial Body Transduction-Manifestation Sequence- Continued page 3

9. As a Keylon-Thought-Form blueprint traveling on one Pulse of Consciousness **fully expands** (fully "Activates") into the manifest externalized hologram, **another Pulse of Consciousness** is released from the synchronized mathematical programs of the Planetary Merkaba Field, which sets the Transduction Sequence in motion ("Initiates")for the ***next portion*** **of the personal mathematical blueprint.** The blueprint of the **Planetary Kathara Grid** regulates the **cyclic rhythms** at which **Pulses of Life Force Current** will be released through the **Planetary Merkaba Field**; the Planet releases **"Pulses of Time"**.

NOTE: The linear time experience of life forms on a planet is synchronized into specific singular continua and cycles of time through the *DNA Template*; the species Tribal Shield, personal Maharic Shield and DNA Template are imbued with the *exact mathematical programs* of the specific *Planetary Time Cycle* and *Continuum* or "Time Wavef" into which the consciousness intends manifest embodiment. A singular Time Wave constitutes a Time Continuum, within which there are specific repeating cycles of progressively accelerating *Pulses of Time* that collectively form the linear time-progression continuum of a *Planetary Time Cycle*.

10. As one **Pulse of Time/Consciousness** brings its blueprint into manifest **Critical Mass Expansion** (fully activates specific portion of the blueprint in Holographic Expression), the Planetary Merkaba Field releases the **next "incoming" pulse** of Time, which carries the next portion of the Kathara Grid mathematical blueprint into the Transduction Sequence. As the new Pulse enters the Transduction Sequence and begins **Expansion** toward manifestation, the **first pulse** of the **fully expanded hologram** begins **Contraction**, entering a **back-return** through the **Reverse Transduction Sequence** (matter- *chemical* DNA-*Sub-Atomic units*- Radis *Mion/Dion units*- Radial Body *Trion -Meajhon units*- Meridian Line-Chakra-Auric Field-Hova Body-Axion Line-DNA Template-Merkaba Field-Morphogenetic Thought-form Field *Keylon Grids & Units*- Maharic Shield Template & Kathara Grid *Partika and Particum Units*- Planetary Merkaba Field *Partiki* Units)

11. A s **pulse-1 contracts** its hologram program **moving backward** through the Transduction Sequence, creating the **"Remembered Past" moment**, the **pulse-2** simultaneously **expands** its hologram program **moving forward** through the Transduction Sequence, birthing the as-yet-to-come **"Future" moment.** The backward moving **"Past"pulse-1** and the forward moving **"Future" pulse-2 intersect** at the **Radial Body Levels** in the Transduction Sequence. This **"past pulse-future pulse intersection point"** is called the **Eiron** (E'r-on) **Point,** also known as **"Zero Point"**, the **"Present moment of conscious focus within the hologram"**, or the "***Eiros*** Conscious, Breathing Life-Force Stream" (Also referred to as the **"Stream of Consciousness"**, the **"*Living Holy Spirit*"** or the **"*Breath of God*"** ..etc.).

12. The *Eiron/Zero Point*, or **Eiros**, is the **"Present Moment of Creation Power"** for the "manifest" conscious identity. It exists at the position where the **third dimensional field,** the electromagnetic **Resonant Tone "Mental Body"** field of a single 3-dimensional Hova Body, **intersects** with the **Meajhe Field Inner Layer** of the corresponding **Radial Body** Tissue Capsule.


Trion Field Outer Layer Pre-Light
1 Radial Body Level
Meajhe Field Inner Layer "Pre-sound"
1 HOVA BODY
MENTAL BODY 3RD Hova Body Dimensional Field
D-3-6-9-12-15 Resonant Tone (EM)
EMOTIONAL-ELEMENTAL BODY 2ND Hova Body Dimensional Field
D-2-5-8-11-14 Overtone (Base Electrical)
PHYSICAL-ATOMIC BODY 1ST Hova Body Dimensional Field
D-1-4-7-10-13 Base Tone (Base Magnetic)
Kathara Grid Primal Current Incoming from DNA Template
0-PT
EIROS
1st
2nd
3rd
Radial Body
DNA
HOLOGRAM
FREE WILL THOUGHT DIRECTIVES

Radial Body Transduction-Manifestation Sequence- **Continued** page 4

13. As the backward moving **"Past" pulse-1** and the forward moving **"Future" pulse-2 intersect** at the Radial Body Meajhe Layer **Eiros** (Eiron Point) ✹ the returning **contracting pulse-1** passes through the Trion Layer and into the ***Meajhon blueprint replica,*** called a " **Radial TILE"** ▨, that it **left behind** in the Meajhe Layer **Eiros** during pulse-1's **incoming** passage. Just as the returning pulse-1 retreats back through its Radial Tile, the **incoming pulse-2,** carrying the **next blueprint** coding ⬡ ,**simultaneously** passes through the **first Radial Tile, combining** the **"past" Radial Tile** mathematical-vibrational blueprint with the **incoming pulse-2 blueprint** ▨ At this moment-point, the hologram template from the "past moment" is adopted by the incoming "future moment" pulse-2 and expanded by the pulse-2 blueprint.



14. As pulse-2 picks up the pulse-1 Radial Tile, ▨ the **retreating pulse-1**, which now **holds the Radial Tile blueprint in *reverse mathematical sequence* as *TRION Pre-light Units*** ⬟ , collides with the incoming pulse-2. Both pulses carry the **common blueprint** of the first Radial Tile; the **incoming pulse-2** holding the blueprint in **forward** mathematical sequence as ***Meajhon Pre-sound Units*** ▨,the **retreating pulse-1** holding the blueprint in **reverse mathematical sequence** as ***Trion Pre-light Units*** ⬟ . As the expanding/advancing and contracting/retreating pulses collide with blueprint **"sequence and anti-sequence",** the pulse-1 reversed **Trion Radial "Anti-Tile" fuses** with the original **Meajhon Radial Tile** ✡ and both Radial Tile and Anti-tile **completely de-manifest** or ***"Ascend"*** from their original Harmonic Universe by **TRANSMUTING** to become a ***Merkaba Field.*** The **energy/ consciousness** once held by Radial Tile/Anti-tile then **replicates** its original blueprint via **Fission,** leaves a **dormant "Memory Imprint"** *Meajhon replica* ▨ in the Radial Body ***Meajhe Field,*** and **reappears** in faster oscillating form within the corresponding **Hova Body Form Constant** of the next Harmonic Universe up in the dimensional scale.

15. As transmutation of the "past" Radial Tile occurs in the Radial Body Eiros, the **incoming pulse-2** is momentarily held **static** as it leaves a **new Radial Tile** in the Meajhe Field; the new Radial Tile holds the **pulse-1+pulse-2** program. At this moment-point the **entire** externalized **Hologram** literally **"Flashes Off"** and de-manifests, its energy **held in suspension** within the **Radial Body** Trion/Meajhe Field. When the first Radial **Tile** is transmuted, the incoming **pulse-2**, carrying an **expanded imprint of the first Radial Tile**, progresses from the Meajhe Field Eiros to Trion Field, then begins to **"Flash On"** its blueprint in manifestation. The embodied self perceives a **"liner moment progression"**; the ***pulse-1***program becomes **"memory"** of the **"Past"** moment, ***pulse-2*** the **"Present"**.

The Radial Body, Mechanics of Manifestation, Healing and Human Potential

There is much more to be revealed regarding the subject of the *Mechanics of Manifestation*. Our introduction to the ***Radial Body anatomy***, the ***Transduction Sequence*** and the ***Mechanics of Manifestation*** represents a beginning in the quest for genuine mastery over the manifest experience. In this *Kathara Level-2 Introduction* we will **not yet address** the highly pertinent aspects of *Manifestation Mechanics* that pertain to **direct Creation of matter and events** through **Conscious Thought Projection** and applied personal **Will Intention**, nor will we yet investigate the complex realities of **Space-Time Travel, Star Gate Passage** and the **Spiritualized-science of Ascension**. All of these subjects and more are *intimately intertwined* with **personal healing** and the **Imprint for Health**, **attaining mastery** over Manifestation Mechanics and the Bio-Spiritual processes of genuine **Spiritual Actualization**. All of these abilities, and many others too numerous to mention, presently exist as **dormant evolutionary potentials** for the Human species; potentials that were once, long ago, fully actualized and commonly expressed. The ***Kathara Bio-Spiritual Healing System*** represents a body of Master teachings that focus upon the manifestation and maintenance of **Holistic Health through Bio-Spiritual Mastery and Spiritual Actualizaton**. Exploration of subjects such as ***Merkaba Mechanics***, ***Manifestation Mechanics*** and the ***Radial Body Trion-Meajhe Field*** is an intrinsic part of furthering our abilities to embody and practice the ideals of Healing and Health through Holism.

Before we can begin to actualize the exciting potentials of freedom, love, power and knowledge that await Human re-discovery, we must first focus upon **healing the obstacles** that have long stood in our way of actualizing true Human potential. Our study of *Merkaba Mechanics* in this *Kathara Level-2 Introduction* has included a *necessary introduction* to **Manifestation Mechanics** and **Radial Body Anatomy**; the greatest physical and spiritual difficulties presently facing Humankind emerge from a **HIDDEN ILLNESS** that has held our species hostage within a progressively deteriorating, **unnatural Mortal body form**. The **underlying cause of ALL Human illness** is an **unnatural genetic mutation** that manifests THROUGH the **DNA Template** and **chemical DNA.** The **Casual Element** of this species genetic deviation from its original Divine Blueprint can only be found through study of the 15-Dimensional Anatomy, ***Primal Life Force Currents, Kathara Grid, Maharic Shield, Merkaba Field, DNA Template***, the ***Radial Body*** and the intimate interplay that perpetually exists between these interwoven systems. It is precisely this ***species genetic deviation***, which has progressed and increased for over **200,000 years**, that has kept Humanity bound to a finite, limited world, unable to express the potentials that once existed as our birthright. Though the problem of this species "Internal Illness" is multi-faceted and highly complex, the **Soul-U-tions** through which progressive healing of the Human genome can be rendered are relatively simple. The **Soul-U-tions for healing** and restoring health to our species, and ourselves, **require familiarity with basic Kathara Grid, Manifestation Template, Radial Body, DNA Template and Merkaba Mechanics.** These are the elements of our 15-Dimensional anatomy within which the **Casual Element** of our genetic deviation is held, and thus these are the elements of our anatomy through which the **most rapid and permanent Healing Solutions** can be rendered.

In the following pages we will continue our investigation of the ***Transduction Sequence and the Miasmic Body***, in order to **identify** the regions of our 15-Dimensional Anatomy in which our hidden genetic mutations are created, stored and perpetuated. Once we can identify the regions in which the greatest healing is needed, we can then directly employ appropriate remedial measures. Working with the **Core Kathara Grid and Maharic Shield Divine Christos Blueprint** to reset the Imprint for Health (Kathara Level-1), while **simultaneously** working with the **elements of our anatomy within which the most significant remedial measures are needed**, will allow us to use Divine Blueprint technology to implement **expedited healing.** In this *Kathara Level-2 Introduction* we will examine the *Transduction-Manifestation Sequence* and how it's present **malfunction** creates the **Miasmic Body**, which creates the DNA Template distortion through which our **chemical DNA mutation**, and a phenomenon known as the "**Phantom**" or **"Shadow" Self** is brought into being within our manifest hologram. We will then continue our exploration of **Merkaba Mechanics** and **Radial Body Healing** applications, to discover the **"Secrets of the Veca Codes"**, and Photo-Sonic and Photo-Radionic Radial Body Healing technologies, through which our Kathara and Merkabic Healing applications can be tremendously intensified, amplified and expedited.

The 5 Radial Body-Hova Capsule-Trion-Meajhe Field Levels

and Dimensional, Triadic Phase Current, Density Level, Merkaba Phase, Hova Body, DNA Template, Axiatonal Line, Chakra, Identity Level and Memory Matrix Correspondences

NADIAL CAPSULE:(also called Telluric Capsule): Composed of **Dimensions-1-2-3 *Telluric Kundalini Current*** frequency, **Density-1** Trion-Meajhe **Gross Matter Density**, 3-Dimensional **Nethra Phase Merkaba**, surrounds **Nada Hova Body**, corresponds to **DNA Strand Templates, Axiatonal Lines and Chakras 1-2-3** and holds focus of consciousness in the D-1 *Lower-Physical-Atomic,* D-2 *Lower-Telluric-Emotional-Elemental* and D-3 *Lower-Mental* ***Taurenic Bodies*** of the embodied Density-1 **Incarnate Personality-*Tauren*** identity, the Sub-conscious, Instinctual and Ego-Reasoning aspects of the "***Mortal Mind***" and the **Personal *Taurenic Memory Matrix***. *Radis* rivulets are called "***Nadis Lines***" (or Telluradis Lines)

DORADIC CAPSULE: Composed of **Dimensions-4-5-6 *Doradic Kundalini Current*** frequency, **Density-2** Trion-Meajhe **Semi-etheric Matter Density**, 6-Dimensional **Hallah Phase Merkaba**, surrounds **Alpha Hova Body**, corresponds to **DNA Strand Templates, Axiatonal Lines and Chakras 4-5-6** and holds focus of consciousness in the D-4 *Astral-Mid-Physical-Atomic,* D-5 *Archetypal Mid-Telluric-Emotional-Elemental* and D-6 *Celestial Mid-Mental* ***Doradic Bodies*** of the embodied Density-2 **Incarnate Soul-*Dora*** identity, the "***Angelic Mind***" and the **Soul/Species *Akashic Memory Matrix***. *Radis* rivulets are called "***Doradis Lines***"

TEURIC CAPSULE: Composed of **Dimensions-7-8-9 *Teuric Kundalini Current*** frequency, **Density-3** Trion-Meajhe **Etheric Matter Density**, 9-Dimensional **Quatra Phase Merkaba**, surrounds **Betcha Hova Body**, corresponds to **DNA Strand Templates, Axiatonal Lines and Chakras 7-8-9** and holds focus of consciousness in the D-7 *Higher-Physical-Ketheric,* D-8 *Monadic Higher-Telluric-Emotional-Elemental* and D-9 *Keriatric-Higher-Mental* ***Metatronic Bodies*** of the embodied Density-3 **Incarnate Over-Soul-*Teura*** identity, the ***"Archangelic Mind"*** and the **Over-Soul/Planetary *Askashic-Eckashic Memory Matrix*** . *Radis* rivulets are called "***Teuradis Lines*"**.

MAHARIC CAPSULE: Composed of **Dimensions-10-11-12 *Maharic "Christos" Pre-matter Hydro-plasmic Liquid Light Primal Current*** frequency, **Density-4** Trion-Meajhe **Pre-matter Density**, 12-Dimensional **Mahunta Phase Merkaba**, surrounds **Mahara Hova Body**, corresponds to **DNA Strand Templates, Axiatonal Lines and Chakras 10-11-12** and holds focus of consciousness in the D-10 *Christiac-Transcendent Pre-Physical,* D-11 *Buddhaic Transcendant Pre-Telluric-Emotional-Elemental* and D-12 *Nirvanic Transcendent Pre-Mental* ***Hydronic Bodies*** of the embodied Density-4 **Incarnate Avatar-*Dolus*** identity, the ***"Christos Avatar Mind"*** and the **Avatar/Galactic *Dolaric Memory Matrix***. *Radis* rivulets are called "*Maharadis Lines*".

RISHIAC CAPSULE: Composed of **Dimensions-13-14-15 *M Kee-Ra-ShA Ante-matter Thermo-plasmic Gaseous Pre-Light Primal Current*** frequency, **Density-5** Trion-Meajhe **Ante-matter Density**, 15-Dimensional **Rahunta Phase Merkaba**, surrounds **Raja Hova Body**, corresponds to "Indigo Grail Line" **DNA Strand Templates, Axiatonal Lines and Chakras 13-14-15** and holds focus of consciousness in the D-13-14-15 *Transcendent Ante-matter* ***Hedronic Bodies*** of the Density-5 **Breneua Rishi** Consciousness Collective identity, the ***"Rishiac Universal Mind"*** and the **Rishi/ Universal *Rishic Memory Matrix of one 15-Dimensional Time Matrix.*** *Radis* rivulets are called "*Rishadis Lines*".

The **5 3-dimensional Levels** of the **Trion-Meajhe Field Radial Body** within the 15-Dimensional **Time Matrix** connect each Density Level of all manifest consciousness to the greater, non-dimensionalized structure of the **Energy Matrix *Khundaray* Primal Sound Vibration *Meajhe Field*** through the **Density-5** Ante-matter ***Kee-Ra-ShA*** **Primal Light *Trion Field***.

The Transduction Sequence and the Miasmic Body


PRIMAL CURRENTS
Earth
Planetary Kathara Grid
Solar Shield & Planetary Shields
Planetary Keylon Crystal Body Thought-form
Planetary Merkaba Fields
Planetary Axiom Template and Axiom Lines
Planetary Hova Bodies, Vortices Ley Lines
Radial Body & Radis
Earth Mions-Dions

Personal Transduction Sequence


HOLOGRAM
Personal Kathara Grid
Tribal Shield & Personal Shields
Personal Keylon Crystal Body Thought-form
Personal Merkaba Fields
DNA Template and Axiom Lines
Personal Hova Bodies, Chakras Meridian Lines
Radial Body & Radis
DNA & body

Primal Life Force Currents ➡ Planetary Merkaba Field Partiki ➡ Kathara Grid -Partika-Particum ➡ Maharic Shield Divine Blueprint ➡ Keylon Morphogenetic "Thought-form" Field ➡ Merkaba Fields ➡ Kathara Grid DNA/RNA Template ➡ Axiom Lines ➡ Hova Bodies ➡ Auric Field ➡ Chakras ➡ Meridian Lines ➡ Trion-Meajhe Field 5 Radial Body Levels ⇨ Radis Lines ⇨ Mion & Dion Ionic Particulates ⇨ Strong and Weak Nuclear Force, Electromagnetism ⇨ Quarks, Muons, Measons, Sub-atomic & Atomic Particles and Anti-Particles ⇨ Blueprint translation into Nuclei, Molecules, Elements, Compounds, Chemicals ⇨ Chemical DNA Template and "Chemical Lens" of the manifest body form ⇨ Manifest Hologram ▭

⊘ **Miasms block energy flow and create a "Phantom-Shadow Self" running on opposite mathematical program; blocks natural energy flow.**

- The Personal ***Radial Body*** or Trion-Meajhe Field is composed of **5 Hova Body Capsules** that manifest as electromagnetic barriers or "**frequency fences**" between each set of 3 DNA Strand Templates, each set of 3 associated Axiom Lines, Chakras and Meridians and between each 3-dimensional layer of the Auric Field and corresponding level of personal multidimensional identity.
- Each of the **5** 3-dimensional **Harmonic Merkaba Fields** corresponding to the *5 Hova Bodies* of 15 Dimensional Anatomy *govern the function* of the corresponding **Dimensional Merkaba Fields**, **Radial Body level** and its imbedded **Memory Matrix**, via the mathematical program held in the personal Kathara Grid, Shields and **Crystal Body** template. The Kathara Grid program is passed from the **Keylontic Crystal Body** into the **DNA Template** via the **Dimensional and Harmonic Merkaba Fields** and the "mini-Merkaba Fields" of the Level-3 Kathara **Diodic Grid**.
- Each Hova Capsule **Radial Body level,** receiving its instructions from the DNA Template and 3rd dimensional Mental Body Hova Body level, in turn governs the function of the **chemically manifest DNA** and all body-consciousness systems that are built upon chemical genetic code.
- The **Harmonic Merkaba Field** governs the **particle spin axis** (Angular Rotation of Particle Spin) ratios of the energy units that make up its corresponding 3-dimensional system. Each **Harmonic Merkaba Field** corresponds to one **Hova Body**, one set of **3-dimensions** and the Matter Density Level characteristic of that 3-dimensional system. Each Hova Body, and thus each Harmonic Merkaba Field Level and Radial Body Level, correspond to one set of **3 DNA STRAND TEMPLATES** within the Human12-Strand Template.
- Full activation of **one Harmonic Merkaba Field** creates reciprocal activation of the corresponding set of ***3 DNA Strand Templates,*** which creates embodiment of corresponding levels of identity and consciousness (personality, Soul, Over-Soul, Avatar, Rishi etc). When one Harmonic Merkaba Field fully activates through natural activation of the corresponding **Shields** and **Crystal Body Keylons**, the Harmonic Merkaba Field becomes capable of **merging** with the Harmonic Merkaba Fields from other Density Levels, in a process frequently called **Transmutative Dimensional Ascension**.

- During the process of "**Ascension**", (also called "space-time travel", "wave-riding", "Star Gate passage", "Teleportation" etc.) the **Harmonic Merkaba Fields** of more than one Density Level merge, progressively shifting the **two or more different sets of 3-dimensional particles** into a **common particle spin axis angle and spin speed**. The corresponding **Axiom Lines, Hova Bodies, Auric Field levels, Chakras, Meridian Lines** and **Radial Body Levels** also merge.
- When Harmonic Merkaba Fields, and their corresponding Inner Templar anatomy, merge, the **Fire Codes** between the corresponding **DNA Strand Templates activate, causing the DNA Strand Templates to merge,** which creates a reciprocal reaction called **"DNA Strand BRAIDING"** between corresponding **chemical DNA strands**. (The "Double Heli" configuration of "one strand" remains, as the chemical components of each strand overlay together to become a single Double Helix containing the chemical programs of multiple DNA strands.)
- When the **Fire Codes** between strands in the DNA Template activate, dormant sequences of chemical DNA called " **Transient Turnstile DNA Sequences**" "turn on" within the **Hydrogen Bonds** that link each DNA "Ladder Rung" together, producing a **transient trans-harmonic element** called **Celestalline** within the chemical DNA.
- Natural Braiding of the chemical DNA strands and activation of the chemical Turnstile DNA Sequences create a series of **sub-atomic bio-chemical DNA responses** that allows for Internal **Atomic Particle/Anti-particle Fusion** and **Fission.** Natural **Internal Atomic Fusion-Fission** enables the manifest atomic structure to temporarily de-manifest, returning to "*spirit form*", by re-entering the electrostatic **Trion-Meajhe Field** of the corresponding **Radial Body Levels.**
- During the Ascension process, the Harmonic Merkaba Fields of **2 or more Density Levels** merge, forming various **PHASES of Merkaba** activation that create a **Trans-Harmonic Merkaba Field** that is called the **Merkaba VEHICLE.** The 3-Dimensional **NETHRA Phase** Merkaba Field of Density-1accelerates in rotation speed to become the 6-dimensional **HALLAH Phase**, 9-Dimensional **Quatra Phase**, 12-Dimensional **Mahunta Phase** or 15-Dimensional **Rahunta Phase** Harmonic Merkaba Vehicle.

- As a phase of the Trans-Harmonic Merkaba Vehicle activates, the corresponding lower-dimensional **Hova Body and Radial Body Level dissolve**, their content of energy and consciousness **expanding** into the next Hova Body and Radial Body Level, forming a **Trans-Harmonic Radial Body "FORM CONSTANT"** within the **Merkaba Vehicle.**
- The Trans-Harmonic Radial Body and Merkaba Vehicle allow the consciousness and biological form to "de-manifest" from the lower dimensional Density Level. The identity can then **re-manifest** in another Density Level or space-time coordinate by projecting itself into the desired location, AS the *electrostatic* ***Trion-Meajhe Field*** **Trans-Harmonic Radial Body,** then returning the DNA Template activation level and Harmonic Merkaba Spin ratios to that of the new location for re-manifestation.
- When the Personal **Merkaba Field** is used to form the **Trans-Harmonic Radial Body** in the process of Ascension, the Merkaba Field is called a **MERKABA VEHICLE.** A ***Merkaba Vehicle*** is an electrostatic **Trion-Meajhe Field** of Primal Pre-Light-Sound through which the consciousness (AKA "spirit") can move itself, *and its atomic structure*, through **thought-projection**, to a desired location beyond the "veils" of the Planetary, Galactic and Universal Hova Capsule-Radial Body-Form Constant barriers.
- Conscious mastery of the Personal Merkaba Field, through which the organic **internally created Merkaba Vehicle** Trans-Harmonic Radial Body becomes available for conscious direction, implies **conscious control of DNA Template function.** The potentialities of **genuine Ascension** (etc…) and mastery of Bio-Spiritual Consciousness are **inborn attributes** of the Human 12-Strand DNA Template. Due to a **species de-evolutionary genetic mutation** that compromises natural function of the Personal Merkaba Field and DNA, the reality of Ascension on a species level has been lost to all but a few on Earth for over 200,000 years (re: Masters Templar Coursebook).
- The potentials of **Bio-Spiritual Actualization** CAN be returned to humankind through **reverse-mutation** of genetic dysfunction within the human genome and DNA Template. Healing the genetic template can be achieved by **manually employing** specific practices of **Kathara "Maharic Shield" Core Template Dynamics** in **combination** with **Harmonic Merkaba Mechanics** through which the many eons of biological miasmic distortion can be progressively and rapidly cleared from the Personal Kathara Grid and DNA Template.

- Restoration of the D-12 Pre-matter Divine Blueprint within the Human Kathara Grid and DNA Template will eventually **free the Personal Merkaba Field** for use as a **Trans-Harmonic Merkaba Vehicle.** Kathara Healing applications, and use of the D-12 Pre-matter Maharata "Christos" Current to reset the biological D-12 Pre-matter Divine Blueprint, are the beginning steps in reclaiming Bio-Spiritual Mastery.

- The function of the personal **Merkaba Field** and **DNA Template** are not only associated with abilities of **Atomic Transmutation** and **Dimensional Ascension**, they are directly linked to **every aspect of body-mind-spirit function**, including **biological longevity** and **health, memory, intelligence,** and **metabolic, chemical, mental** and **emotional balance** and stability.

- Most significantly, the **Merkaba Field/DNA Connection** is the Bio-Spiritual conduit through which the consciousness of an embodied individual is directly linked to the common Perpetual Force of Energy and Eternal Source of Intelligent Creation that is "**God".**

- When a being's Merkaba Field and DNA Template are functioning upon the innate program of **Universal Primal Order**, as it is held within the Pre-matter **Universal Divine Blueprint** of the D-12 "Christos" Liquid-Light field, the natural and perpetual supply of **Primal Life Force Currents** and "spiritual" consciousness emanating eternally from Source-God, flow through an open energetic channel or "**Pillar of Light**", which is called the "Um Shaddai Ur" (Pillar of First Cause Light-Sound') into the manifest embodiment. Such a being is called a "**Christed Being**". This implies that the integrity of its original D-12 Pre-matter Divine Blueprint has not been structurally compromised, and thus the perpetual Life Force Currents, consciousness, sentience, intelligence, wisdom, power, Will and LOVE of Source can freely express through the Um Shaddai Ur, into the manifest hologram of the Time Matrix through the Christed embodiment.

- If the Kathara Grid, DNA Template and Merkaba Field of a being are damaged, and no longer carry the **original mathematical-geometrical program** of the **D-12 Divine Blueprint** through which the being entered space-time, the flow of Primal Life Force Currents, the Um Shaddai Ur Pillar and thus the active consciousness connection to God will be distorted, reduced or severed at the dimensional level to which the template distortion corresponds.

- A manifest being incapable of running the Primal Life Force Currents of the Um Shaddi Ur "Pillar" becomes **biologically finite**, its consciousness "trapped in the Time Matrix", even following death of the physical body. According to the **natural Laws of Creation Physics** as set by Source-God, this condition of **finite mortality** will remain until the being's **Kathara Grid Template and Merkaba Field connection to** the D-12 **Universal Divine "Christos" Blueprint** and Universal Trion-Meajhe Field Um Shaddi Ur Pillar is restored.

- Healing Core Template genetic distortions that are severe enough to cause dysfunction of the Personal Merkaba Field first require **resetting of the D-12 Divine Blueprint** through activation of the **Personal Maharic Shield.** Until the Body-Mind-Spirit system has reached a **Critical Mass** of D-12 Divine Blueprint holding through frequent and progressive manual running of the D-12 Maharata Current, healing Core Template genetic distortions **also requires** simultaneous, direct and repeated **manual realignment and restoration** of **Personal Merkaba Field function** and **Radial Body Trion-Meajhe Field** integrity.

- If there **are distortions within the Kathra Grid or DNA Template** of an individual or species, the Personal Merkaba Fields will not function in harmony with the **natural energy circulation rhythms** of the **Planetary, Galactic, Universal** and **Time Matrix Merkaba Fields** and Universal Kathara Grid. Such Kathara Grid distortions create tangible **genetic and consciousness mutation** within biological organisms, and can divert the **intended evolutionary destiny** of an embodied consciousness or species on to a divergent path of **de-evolution and consciousness fragmentation** unintended by the original plan encoded within the D-12 Pre-matter Christos Divine Blueprint.

- Distortions with the DNA Template and resulting **Miasms** can be purged through **manual resetting of the D-12 Pre-matter Divine Blueprint,** via repeated manual activation of the Personal **Maharic Shield**. The activated Maharic Shield runs the Density-4 D-12 **Maharata Primal Life Force "Christos" Current** through the Kathara Grid and form embodiment, progressively resetting the original mathematical coding of the personal Divine Blueprint within the Kathara Grid and DNA Template. Use of the **Maharic Shield techniques** in *Kathara Level-1* sets this process of **Core Template Regeneration** in motion.

- The Core Template "Divine Blueprint" healing process can be expedited through applied **Christos-Merkabic Healing Mechanics** such as the ***Tribal Shield Activation*** (Technique-7), ***Merkaba Salutation*** (Technique-8), ***Merkaba Trinity Key Induction*** (Technique-9) and ***Kee-Ra-ShA Activation Sequence*** (Technique-12).

- Divine Blueprint Healing can be expedited further through **manual restoration** of the personal Trion-Meajhe Field **Radial Body** and its inherent **Memory Matrix. Radial Body Healing,** when **combined with** ***Kathara Maharic Shield*** and ***Christos-Merkabic Healing*** dynamics is the most powerful and rapid Holistic Healing technology available.

- **Radial Body Healing** dynamics, which also serve to progressively restore the organic **Memory Matirx,** involve use of the specific **mathematical programs** that govern formation of the **Radial Body Trion-Meajhe Field.** These mathematical programs are called **VECA CODES.**

- **Technique-10** ***Restoring the Trion Field-Photo-Radionic Healing*** **and Technique-*11Restoring the Meajhe Field-Photo-Sonic Healing,*** provide introduction to **Radial Body Healing Mechanics.** Use of these techniques, in **combination** with **Technique-2** ***The Maharic Seal and Liquid Light Cleanse,*** and **Merkabic Healing Techniques 6-12, will greatly expedite** the personal healing process while **significantly increasing** the body-mind-spirit abilities to **receive, hold/sustain and transmit greater quantity and quality** of interdimensional frequency in the Client Healing Facilitation process.

Radial Body Healing, the VECA CODES, DNA and Merkaba

- Veca Codes, also called the "I AM" or "**Immanuyana Sequence**" are very specific **SYMBOL CODES**, each possessing corresponding **Sound Tones** called ***Arieas*** and **energy movements** called ***Seurias***, which correspond to the Cosmic, Universal, Galactic, Planetary and Personal **Trion-Meajhe Field Radial Body Levels**.
- There are **5 categories of Veca Codes**, the Planetary **Low-Veca *Codes of Manu*** (Taurenic-Akashic Codes), the Galactic **Mid-Veca *Codes of Immanu*** (Akashic-Eckashic Codes), the Universal **Level-1 High-Veca *Codes of Immanuel*** (Dolaric-Rishic Codes), the Cosmic **Level-2 High Veca *Codes of Immanuyana*** (Triadic-Polaric-Eckatic Codes) and the God-Seed **Yunasai *Codes of Eckasha*** (Source Codes).
- Beginning applications of Veca Code Radial Body Healing begin with restoring the Trion-Meajhe Field Radial Body through resetting the ***Yunasai*-Eckasha and High Veca *Immanuyanas* and *Immanuel* Codes**, through **frequent manual Direct Induction** of the their corresponding **Symbol Codes** and **Sound Tones/Arieas**.
- The most powerful **Yunasai-Eckasha Codes** are **PHOTO-SONIC Codes**, carrying the Mathematical Programs of the ***Khundaray Current*** Primal Sound ***Meajhe Field*** AND their bridging **God-Seed vibration-rhythms** connecting to Source. The **Level-2 *Immanuyana*** and **Level-1 *Immanuel* High Veca Codes** are **PHOTO-RADIONIC Codes**, carrying the Mathematical Programs of the Trion-Meajhe Field **Khundaray Primal Sound** AND **Kee-Ra-ShA Primal Light Currents.**
- **Consistent use** of **Veca Code Radial Body Healing**, in combination with **Merkabic and Kathara Healing** applications, will progressively **clear the Miasmic Body** and heal, balance, re-integrate, and restore the Divine Blueprint within, the energies of the **Phantom-Shadow Self** in all levels of the Body-Mind-Spirit system.
- More advanced applications of Veca Code technologies include use of the **Mid-Veca *Immanu*** and **Low-Veca *Manu* Codes,** and the corresponding ***Seurias*** (body movements to direct frequency), following a period of initial induction and activation of the Yunasai and High Veca Codes. Full Spectrum Veca Code technologies are introduced in the "***Dance of Life***" Masters Spiritual Development Program.

- **Induction,** or **IMBEDDING** of the High Veca Codes into the 15-Dimensional Anatomy involves placing the corresponding **Symbol Code Sequence** (mathematical program) over the **regions of the physical body** that correspond to the appropriate aspects of the Kathara Level-2 **Crystal Seals Grid** and Level-3 **Diodic Grid.** Once the Symbol is in place, the **breath** is used to direct **D-12 Maharata Current** through each **Symbol Code** and **body region.** Use of the **Maharata Current** "carrier wave" (via **activation of the Maharic Seal/Shield**) is **required** to **induce** the code's **mathematical program** into the **Diodic** and **Crystal Seals Grid,** where the program will then naturally transfer into the corresponding areas of the **Level-1 Kathara 12-Tree Grid** core template.

- Once the High Veca and Eckasha Code Sequences are Imbedded/induced into the Level-1 Kathara Grid, they are then **Activated** in the Kathara Grid by **TONING** the corresponding **Veca Code Ariea Sequence.** The longer toning is sustained, the greater will be the quantity and quality of Veca Code Activation.

- Once Activated, the Veca Code programs travel upward through the stages of the **Transduction-Manifestation Sequence** from the **Kathara Grid**, to the **Shields**, into the **Keylon Crystal Body Morphogenetic Field,** then into the **Merkaba Field**, **DNA Template** and **Hova Body/ Radial Body Levels**, temporarily restoring the **Christiac Merkaba Field, Radial Body** and **Memory Matrix Divine Blueprint**. **Frequent and continued use** of the Veca Codes will progressively build **Critical Mass** of the **Divine Blueprint program simultaneously** within **ALL levels** of the 15-Dimensional Anatomy, eventually culminating in expedited full restoration of the D-12 Maharic Shield blueprint within the Body-Mind-Spirit system, via the Radial Body Trion-Meajhe Field.

- Activation of the Yunasai and High Veca Codes within the personal body **prior to conducting a Kathara Client Healing Session** will cause the facilitator's **Level-3 DIODIC GRID to activate**, temporarily **transmitting Veca Code sub-harmonics.** This will cause the **minute Diodic Chakras** in the facilitator's **FINGER TIPS** to activate **if the Palm Chakras** have been activated with either pure **Maharata Current** or a selected **Triadic Phase Current.** The facilitator will then **automatically transmit** Veca Code sub-harmonics into the client's **Diodic Grid** while conducting general Kathara Healing applications, allowing the client to benefit from temporary **Radial Body healing support**, which will **amplify the effects** of all healing applications.

- A more **Temporary Imbedding and Activation** of the Veca Code program can be achieved through **OPTICAL-PINEAL INDUCTION**, whereby the **eyes** are focused for a time upon the **Image** of the **Symbol Code.** The mathematical Veca Code program enters the **Pineal Seals** through the **Optical Currents** and **6th Chakra**, an then travels for Imbedding/induction through the **Central Vertical Current** into the body regions and Crystal Seals Grid areas to which the Veca Code corresponds. The **Veca Tones/Arieas** are then used to Activate the Imbedded Veca Code Sequence.
- In **Optical-Pineal Induction**, the Veca Program looses a bit a **frequency charge/ strength** during is travel in the Central Vertical Current. This creates a **more temporary imbedding and activation** of the Veca Codes than that which is achieved through Direct Induction. Optical-Pineal Induction is useful for **daily amplification** of the Vecas, and for Kathara Healing Client Sessions and planetary grid "site work", when used in **combination** with the **full induction procedure** employed at least **once per week**.
- To receive **full benefit** of **Veca Code Radial Body Healing** applications, **Technique-2** ***The Kee-Ra-ShA Activation Sequence*** should be fully run at least **ONE TIME**. *Technique-2* can also be used occasionally thereafter if desired to create **intensification and amplification** of the Primal Life Force Currents during Kathara, Merkabic and Veca Code Healing technologies.
- Frequent use of **Technique-13: The "Song of Lyra"** Christos Invocation will amplify all Kathara, Merkabic and Veca Code Radial Body Healing applications.

The Christos-Trion-Meajhe Fields, High-Veca Codes and Universal Life Force Currents

One 15-Dimensional Time Matrix with 5 Harmonic Universes



Universal Life Force Currents
***Khundaray**- Three levels, **Primal Sound Field Currents** form **Energy Matrix**. *Eckatic, Polaric* and *Triadic* Currents of *Standing Sound Vibration*.
***Kee-Ra-ShA'- Three levels, Primal Light Field Currents** emanating from Primal Sound Fields form First-Cause *Ante-matter* Density Dimensional Light Field of the *Time Matrix*.
Eckatic-*Blue Flame*-D-13 (Primal Ray from which the 2 other Primal Rays emerge).
Polaric-*Gold Flame*-D-14
Triadic-*Violet Flame*-D-15
***Maharata**- Three levels of frequency, D-10, D-11 and D-12, interwoven together to form the **D-12** Omni-Polar **Universal Christos Field** of *Pre-matter Density* **Hydroplasmic Liquid Light**.
***Antahkarana**- 9 levels of polarized **electro-magnetic** energy frequency that form **3 currents** of 3-dimensional energy called the **Universal Kundalini**, which form lower-frequency **dimensions 1-9**, creating *Etheric, Semi-Etheric, Gross-physical* Matter Densities.

Eckasha Crown Veca Code- The Universal God-Seed
TONE: Um-ah-A' ThrA'-E-na-A'

A *Dimension* is a full Frequency Band or repeated sequence of "flashing on and off" of scalar standing-wave points within a morphogenetic field.

Khundaray
Primal Sound Fields
Meajhe Field

Kee-Ra-ShA'
Primal Light Fields
Tri-Veca Code
Trion Field

Maharata (Christos)
Liquid Light Fields
Bi-Veca Code
Christos Field

Antahkarana
Universal Kundalini

5 HARMONIC UNIVERSES
in one 15-Dimensional **TIME MATRIX**

3 Levels of the non-dimensionalized **ENERGY MATRIX** within which TIME MATRICES reside.

Magnetic Repulsion Zones create separation between Harmonic Universes.

All things in manifest existence are perpetually fed **energy** and **consciousness**, in the form of **interdimensional frequency**, via the **Universal Life Force**

Rha-Veca Code
Dha-Veca Code
Khu-Veca Code
Ec'ka
DrU A' jha
Shar DA'z'a
Triadic-Violet Flame
Polaric-Gold Flame
Eckatic-Blue Flame
HU-5
'Ha' Sha
HU-4
Mu A' va
D12
D11
D10
D9
HU-3
Teuric Currents
D8
D7
Doradic Currents
D6
D5
D4
HU-2
D3
D2
D1
Telluric Currents
HU-1
TRIADIC LEVEL
POLARIC LEVEL
ECKATIC LEVEL

Technique # 4

Restoring the Trion Field-Photo-Radionic Healing

Regular use of this technique will strengthen and improve RRT Planetary healing Applications (excerpt from Kathara Level-2)

Creating a Personal Bio-field Link to the Universal Christos-Trion-Meajhe Field

Masters Merkaba Mechanics

© 2001 Ashayana and Azurtanya Deane

Exercise-1: **Once per day**, do **Maharic Insta-Seal** then practice **each set of Veca tones** separately while fixating **visual focus** on corresponding **Veca-Code** symbol; spend at least **three or four minutes** gazing at each symbol (optical-pineal induction) while **toning** corresponding tones (core template vibrational induction) With practice this will progressively expand the personal consciousness while activating the personal Christos-Trion-Meajhe Field of your Christos-Rishiac-Ascended Master identity levels within the cellular structure.

Exercise-2: Once per week, directly after completing **Exercise-1**, place all Veca-Code symbols over designated body areas, activate Maharic Shield, breathe D-12 Maharata Current through each symbol and body area to **induce code**, using the Bi-Tri-Khu-Dha-Ra Sequence, then begin **toning** the corresponding tones following the Bi-Tri-Khu-Dha-Ra Sequence. Memorize the tone sequence of the 5 High-Veca Codes as if it were a "**song**" and relax, close eyes and sing/tone this "song" (Psonn) for **5 to 10 minutes**. The longer you tone, the more frequency power you build within the body and the stronger your link will be to the Universal Christos-Trion-Meajhe Field. This exercise can also be used with groups, either singularly to create and amplify Christos-Trion-Meajhe Field links or just prior to beginning RRT work. Frequent and consistent use of these two exercises will progressively develop the spin-rate capacity of the personal Christos Merkaba Field, while expanding higer consciousness within the body and progressively enhancing the health, immunity and integrity of the Mind-Body-Spirit system.

The High-Veca Codes
Universal Time Codes for Primal Frequency Access

Cosmic Codes of Immanuyana



The Rha-Veca Code
Primal Sound-3 Eckatic
called the *Ec ka*
TONE: "*Rha Ec' ka*"
Symbol Placement:
Tailbone



The Dha-Veca Code
Primal Sound-2 Polaric
called the *DrU A' jha*
TONE: "[illegible]' *Dru A' jha*"
Symbol Placement:
Chakra-2 (just below naval)



The Khu-Veca Code
Primal Sound-1 Triadic
called the *Shar dA'z a*
TONE: "*Kh*[illegible]*har DA'z a*"
Symbol Placement:
Chakra-8 Front (clavicle)

Universal Codes of Immanuel



The Tri-Veca Code
Density-5 Dimensions 13-14-15
called the *Ha' Sha*
TONE: "*Kee' Ra ShA Ha Sha*"
Symbol placement:
Left Foot bottom



The Bi-Veca Code
nsty-4 Dimensions 10-11-12
called the *Mu A' va*
"*Ma ha ra' ta Mu A' va*"
Symbol placement:
Right Foot bottom

Technique # 11

Restoring the Meajhe Field-Photo-Sonic Healing

1. Use **Technique-6:** ***The Maharic Quick Seal*** to activate your Maharic Shield, Seal and Maharata Current.
2. **Stare at image** of the **Eckasha Code** for a few seconds, then gently begin to **"Cross Eyes"** until you can see a **"Double Image"** of the *Eckasha* when looking at the image. **Hold " Eye Cross"** focus while taking **three rapid breaths**; on each **EXHALE** projecting a **stream** of (D-6) **INDIGO current** from your **6th "3rd Eye" Chakra** at forehead. (This braids D-6 Optical Currents into a D-12 Current to carry the Eckasha program into the Pineal Seals.). Un-cross eyes, relax visual focus and close eyes for a moment or two.
3. **INHALE** several breaths of **Pale Silver D-12 Maharata Current** up from the **Earth Core** through your **Maharic Cord**, on each **EXHALE** depositing the Maharata Current in the **Pineal Gland** at the center of the brain, to form a Pale Silver **"Maharata Ball"** in the Pineal.
4. Breathe gently and **return visual focus to the image of the Eckasha**, focusing upon the **Eckasha Core** ***REUCHE'*** (the "Double Circles and their content at center of Eckasha).
5. **EXHALE** while projecting a **stream of INDIGO current** from the **6th Chakra** at forehead, into the **REUCHE** symbol before your eyes. **INHALE** while drawing the **INDIGO current stream** with the **REUCHE image at its end** back through the **6th Chakra** and into the **Maharata Ball** in the **Pineal.**
6. **INHALE** one more breath of **Maharata Current** up from **Earth Core** to the **Maharata Ball** at the **Pineal**, then use a forceful EXHALE to PUSH Eckasha-Reuche encoded Maharata Ball out to the right, to the "Mentor" position over the right shoulder. Visualize the Maharata Ball growing to the size of a "Basket Ball" over the right shoulder, and visualize the image of the Reuche as expanding to fill the inside of the Maharata Ball.
7. **INHALE forcefully** while drawing the **Maharata Ball** back to a position **centered around your head**, then use **three breaths** to **INHALE Maharata Current** up from **Earth's Core to Pineal** and **EXHALE** the **Maharata Current outward** to fill **and expand the Maharata Ball.**
8. Visualize the **Maharata Ball** expanding outward from around your head, until the Maharata Ball **fully encompasses your body and entire Chakra System**, from **Chakra-14** 36" above head to **Chakra-13** in Earth Core. Imagine that your entire body is now surrounded by a 3-dimensional "Eckasha Tear-Drop" shaped CLEAR CRYSTAL CAPSULE. The Eckasha Code Photo-Sonic Capsule is now temporarily activated in your Inner Templar system.

Eckasha Crown Veca Code- The Universal God-Seed

Tone: Um ......⇩ ah...........A' ⇧ ThrA'......⇩ E'- ⇩ na......A

Symbol Placement: Pineal Induction via Chakra-6 "3rd Eye"

The Yunasai-Eckasha God-seed Code



The REUCHE' Eckasha Core Code



Technique # 13

The Song of Lyra Christos Invocation

The Vectos Invocations

The Vectos Compendium Declariti
The Vectors Collective Declarations
(All self incarnations in all Time Vectors declaring in Unity as the Avatar Self)
English translation from Elohei-Anuhazi Emerald Covenant Decree Texts:
© 2001 Ashayana Deane

The Mah'-ah' Bi-Vectus Declaritum
Declaration of the Maharata

(Intention Decree AS the personal D-12 Christos Avatar Maharata self identity)

I decree now in this moment of KNOWING that all things here within me
are hence forth restored to the original Divine Intention of the ONESELF that is MINE.

I release now all bonds of manifest illusion that place veils of SELF-forgetting before mine eyes. I revoke all separations of duality through which my Heart is rendered numb with disillusion and discord.

In this moment I reclaim the Whole of my Condition, reaching forth into the depths of all creation to now call my SPIRIT home.

I AM the Sun of the Radiant Glowing. I AM the HEART of Divine LOVE. I AM the Still Point of the Face of All Creation. I AM the Voice of the Universal Song.

I decree now in full remembered Knowing that I AM ALL and WE are ONE.
In setting forth this decree of my Eternal Divine Power, I shall render Divine Intention only, through which the All and I are equally served
in the Highest Order of our collective Best Divine Intention.

I call now unto the many Selves and Shadows ensconced within the illusions of time, and decree unto thee that I AM THIS, I AM.
I AM the wind that brushes thy faces.
I AM the rain that renews thy field.
I AM the Whisper of the Breathe of God within YOU.
WE NOW are the expression of Divine Heart, Mind and Hand.
WE are the Rumbling Hymn Song of the earthen worlds of matter.
WE are the Prana-Breath of God Eternal, manifest.
We are the Waters of Eternal Life forever outward flowing.
We are the cooling, life force Flame of the Cosmic Fire expressed.
In our UNION now and always, declare WE in our Wholeness,
that all dissidence is rendered spent, all conflict NOW made healed.

As DIVINE NAME THIS.................(your Christos spiritual name)
I AS WE, the Maharata KHUM BI-Vec'TUS, (D-12 Christed Avatar Divine Blueprint self identity), DO NOW DECREE through the Divine Love, Wisdom and Power that is MINE....to express now AS this moment, the condition of **Mah'-ah BI-Vec'TI UN UR'-A-OR'-NaM' –OOR** (Christos beginning and ending NOW-completion of a manifest expression in its originally intended Divine Fulfillment, its past-present-future full expression made in the present time, clearing all duality, disharmony and distortion. Anchoring of the Divine Christos Maharata Blueprint in the moment). Upon this Invocation Divine Intention is rendered manifest in all conditions to which I now assign.

The Mah’-ah’ Bi-Vec’tus Inavhoki
Invocation of the Maharata

(Creation Decree Invocation AS the personal D-12 Christos Avatar Maharata self identity)

© 2001 Ashayana Deane

From this Still Point of my Wholeness in manifest decision,
I Decree in Sovereign Knowing, here expressed at my Command *(lovingly stated absolute intention)* ***the Divine Will and Intention of the ONE-SELF that is ONE GOD.***
The ONE-SELF that IS ONE GOD THIS I AM.

Mah–Hah-Rah-Tah KHUM BI-Vec’TUS ....(name)
I as D-12 Christos Avatar self.......(name)
IN-A-VHO’-KI UN’ E-BLE’UM BI-Vec’TI
Invoke by Divine Loving Command Now, by the Power of the Universal Christos,
Mah’-ah BI-Vec’TI UN UR’-A- OR’-NaM’ – OOR
the D-12 Divine Christos Blueprint past-present-future; NOW the Divine Sea of Liquid Light anchors in this moment.
E’-stA Un’-tA E’-Sa Tra’zd-Jha’ HA’-A Rha
Absolutely now established, always and forever, in eternal abiding reverent Love of the Eternal ALL-ONE
’’tah-TA Um a Ah-ShA’-Lum
Blessed Be all embracing, given forth from the Still Point of Eternal Peace
Thah-A’-Jha in’ta DO A”
Spoken AS IT IS STATED, As SO It IS DONE
Um Sha’-DI UR’- A ah Khum’ TUn
All Embracing Pillar of First Cause Light, I AS THIS expression now.

In the name of the Melchizedek Cloister Emerald Order Eieyani,
Holy Order of the Yunasai,
Sacred House of ONE.

English Translation:

Ma-Ha-Ra-Ta KHUM BI-Vec’TUS ....(name)
(Khum = “I AS”) (Ma-Ha-Ra-Ta BI-Vec’tus = D-12 Christos Avatar Self)
iN-A-VHO’-KI UN’ E-BLE’UM BI-Vec’TI
(*in-A-vhO-kI*= invoke by Divine Loving Command), (*UN*= Now), *(E-BLE’UM*= by the power of), (*Bi-Vec’ti* = Universal Christos)
Mah’-ah BI-Vec’TI UN’ UR’-A- OR’-NaM’ – OOR
(Mah’ah Bi-Vec’tI= D-12 Divine Christos Blueprint past-present-future)
(UN Ur’-A- Or’-Nam’ –OOR= Now the Divine Sea of Liquid Light anchors in this moment)
E’-stA Un’-tA E’-Sa Tra’zd-Jha’ HA’-A Rha
(E’StA Un’TA E’Sa = Absolutely now established, always and forever)
(Tra’zd-Jha’= in eternal abiding reverent Love) (HA’-A Rha = of the Eternal ALL-ONE)
P’tah-TA Um a Ah-ShA’-Lum
(P’tah-TA UM = Blessed Be, all embracing) (“a” in this context = given forth from)
(Ah-ShA-Lum = the Still Point of Eternal Peace)
Thah-A’-Jha in’ta DO A”
(Tha-A-Jha inta= Spoken AS IT IS STATED) (DO A”= As SO It IS DONE)
Um Sha-DI’ UR’ A’ ah Khum’ TUn
(Um Sha- DI’ UR’A = All Embracing Pillar of First Cause Light)
(ah Khum’ TUn = I AS THIS expression now)

Interior view of the Tesla Coil power supply for the Zephyr Technology Multiple Wave Oscillator.



This Tesla Coil power supply produces over 40 watts of output! It powers a pair of Golden Ratio MWO antennas or the remarkably gentle Violet Ray Bulb Assembly... Unit is designed for "practitioner use"; this means it can be run 8 or more hours a day, 7 days a week without overheating or malfunction! The Dual Spark Gaps have built in "governors" to limit the output power. (Don't worry folks, there is still plenty!) This is achieved by cutting the length of each nylon tuning bolt for a maximum spark gap distance of 1/8" per gap. With the two air quenched spark gaps in series, there is wonderful sensitivity and range down low! Most Tesla Coil devices form an "arc" in the spark gap at a certain minimum distance. Once a constant "arc" is formed in the spark gap, all the harmonics are lost and thus there is little resonance action put out by the Tesla Coil.

**With the Zephyr Technology system of two fan driven air quenched Spark Gaps in series, unit keeps frequency rich output at very low power for use on sensitve areas! (as with the Violet Ray Wand).
Most competition alternative medical units of this type simply use a Neon Sign Transformer as the primary high voltage. This practice results in Tesla Coil output being contaminated with unwanted 60 Hz from the ac power grid (complete with "junk" frequencies from Nuclear Power).**

Some Construction Details of Zephyr Technology Multiple Wave Oscillator:



Detail of the close coupled, mineral oil filled Tesla Coil. Secondary is approx 720 turns of #32 solid enameled copper wire. Primary is 19 turns of #14 stranded, tinned copper wire with soft vinyl insulation. Coil form for secondary is 1" i.d. pvc pipe, schedule 40. Coil form for primary is clear acrylic cast tubing, 2 1/2" outside diameter, seven inches long with 1/4" wall thickness. Connectors are banana jack and plugs. Non toxic mineral oil has a dielectric strength of approx 3 (air is 1). The most technically challenging task in building this coil is the "Fill Hole Seal" for the liquid mineral oil.



Detail of New Close Coupled Primary Winding on Tesla Coil. BENEFIT: Much stronger field strength resulting in stronger Resonance in body of experimental subject! This translates into increased Experimental Rejuvenation and Detoxification... With new Primary Winding, both Radiator and Resonator Antennas are "active"; encompassing the body with oscillating frequencies.



Call Zephyr Technology! today to order specific subassemblies for "build your own" projects: (937) 429-3847

Some Construction Details of Zephyr Technology Multiple Wave Oscillator Continued:


+ 12 volts
R.F.C.
50K
1N4004
.05uF
H.V.
100uF
50V
.25
100W
4.7K
8
4
Auto
coil
7
555
Timer
IC
3
1K
B
C
10K
2
6
1N4001
X3
1
5
.1uF
1N4001
E
.1uF
R.F.C.
−12 volts

Uses NTE 249 Darlington Transistor

Schematic of the 555 Timer/ Darlington Transistor Assembly.

This circuit "chops" the 12 volt power supply to drive the first stage high voltage: a MSD Blaster or Mallory Hot Rod auto coil.

This system has a tremendous advantage over a Neon Sign Transformer by eliminating unwanted 60 HZ ripple contamination in the Tesla Coil output!

Following in the tradition of Bob Beck, and heeding the words of Tom Bearden speaking at the USPA Conference in Columbus Ohio: "... No proprietary circuits please, publish and fully disclose your circuit designs so others may replicate your discoveries... The Government can shut down one solitary inventor, but if a hundred or a thousand people all start building these wonderful machines, the Government cannot shut everybody down..."

Zephyr Technology believes this is a good policy!

Detail of the hot rod auto coil fitted with a 45 KV Diode. The high voltage Diode (NTE 510) takes out any remaining ac ripple in the auto coil output. The benefit of this system over the commonly used Neon Sign Transformer (Bergstresser units) is that the Tesla Coil output is free from any "junk" frequencies (60 Hz) found on the Nuclear generated ac grid. Note the clear vinyl tubing used to wrap all high voltage components for safety and insulation.





Adjustable Tungsten Spark Gap Assembly

Detail of the spark gap assembly. Notice how dual spark gaps are tunable and are equipped with governors to limit output power. Not shown flanking each Nylon Tuning Bolt are two air inlet ports for each spark gap. These air inlet ports are driven by cooling fan in the center of the lid of case. By forcing a rush of air over each sparking gap, the gaps remain quenched and do not form a solid "arc" or short circuit, which robs the Tesla Coil output of valuable harmonics essential to proper action of the MWO. antennas.

Current edition of MWO from Zephyr Technology features Three Spark Gap Assemblies:

- **One Heavy Duty 3/16" Tungsten Rod Fixed Gap for extended operation.**
- **Two adjustable Tungsten Gaps for sensitive tuning with the Benefit of achieving Resonance with a variety of "Experimental Subjects"**




Schematic for Mosfet modification to MWO
Substitute Mosfet IRF 3710 for Darlington Transistor NTE 249
Heat Sink
TO-220 Case
Gate
Source
Drain
1kΩ ½W
10KΩ ½W
Tie to Pin 3 of 555 Timer
Tie to same wire as Emitter from NTE 249 Darlington Transistor
Tie to same wire as Collector from NTE 249 Darlington Transistor
(The Negative Terminal on Hot Rod Auto Coil)

- **A MOSFET can be used instead of Darlington Transistor. IRF 3710 from Digi-Key works well in this application. Call (800) 344-4539 to order Part # IRF 3710-ND. Hex/Mos N-CH, 100 Volt, 57Amp, TO-220 case.**

- **Use this blank circuit board template to make a printed board for this project. Radio Shack sells a circuit board etching kit; or you can buy a generic or test board and hand wire everything together.**
- **In the next diagram, the same board is populated with component parts.**
- **Slip a piece of vinyl tubing over shaft of Tuning Pot to prevent accidental shock.**


+12
R1
R0
OUT
EMITTER
GND
-12Volts
1
OUT
BASE

Actual Size


50K ohm Potentiometer
Linear Taper
NTE 519
HV Diode
45 KV P.I.V.
Plus + 12 Volts
Load Resistor
.25 ohm
@ 100 Watts
100uF 50V
+12
+ 12 V
R1
R0
1N4004
.05uF
R.F.C.
4.7K
10K
8
7
6
.1uF
5
555 Timer IC
4
Out Emitter
Out Emitter
Hot Rod Auto Coil MSD Blaster
C
B
E
1N4001 X 3
GND -12V
- 12 V
1
2
3
1K
Out Base
Out Base
.1uF
1N4004
R.F.C.
10K
NTE 249 Darlington Transistor
Outside Ground Strip

Schematic and Layout of 555 Timer Board:

- **12 Volt Power Supply should be simple fuse type rather than circuit breaker. High Voltage environment causes malfunctions in voltage regulation schemes.**
- **Insure that 12 Volt Supply automatically "Grounds" when unit plugs into wall socket! Insure that case of 12 Volt Power Supply is Grounded!**

- **Use small piece of plywood to mount circuit board. Then install completed assembly into MWO.**
- **Mount 50K Tuning Pot on same Heatsink as Transistor or MOSFET.**
- **50K Tuning Pot lets you walk primary frequency between 200 HZ up to approx 1300 HZ. Hot Rod Auto Coil runs cooler at faster frequencies.**




MWO Resonator Antenna
MWO Radiator Antenna
Primary
Secondary
MMC HV CAP
24KVDC
0.0125MFd
MMC HV CAP
24KVDC
0.0125MFd
Power Supply
Driver
-
+
C2+
C2-
C1+
C1-
45KV PIV
45KV PIV
HotRod Auto Coil
40KV
HotRod Auto Coil
40KV
50KOhm
Linear Taper
P1B P1A
Dwell
50KOhm
Linear Taper
P2B P2A
Frequency
Spark Gap
Spark Gap
Load Resistor
0.25 ohm 66 W
External Ground Bus
MWO Block Diagram Schematic
TITLE: mwodiag3
Document Number:
REV:
Date: 2/08/2007 08:09:25p
Sheet: 1/2

Current edition MWO from Zephyr Technology showing Dual Mosfets with both Frequency and "Dwell" Controls (To limit oversaturation and heat build up).

Component Discussion: Clockwise from Top:

- **Liquid Filled Tesla Coil**
- **12 Volt, 10 amp Power Supply**
- **555 Timer/MOSFET Assembly with its Primary Frequency Control (and Dwell)**
- **Load Resistor: .8 ohm @ 100 Watts**
- **Hot Rod Auto Coil and Diode Assembly (45 KV p.i.v.)**
- **Two HV Capacitors: 24KV AC @.0125 mfd (Polypropylene Film; multi-mini array of 12 Cornell Dubilier #942C20P15K in series)**
- **Ground Bus (MWO must be Grounded!)**
- **Dual Air Quenched and Tuneable Spark Gaps.**



Detail Capacitor Array

GOLDEN RATIO Multiple Wave Oscillator Antenna. Use this image as Template to create your own MWO Antenna.



Enlarge Image at Copy Center to suit; then etch yourself or take to circuit board shop.



GOLDEN RATIO ANTENNA FOR MULTIPLE WAVE OSCILLATOR

ZEPHYR TECHNOLOGY! is pleased to announce that the Golden Ratio Multi-Wave Oscillator Antenna designed by Eric Dollard of Borderland Sciences Research Foundation is back in production!
These double sided. Gold plated MWO antennas are based on the Golden Proportion as found in living systems in Nature. Using the mathematics of Life, the Golden Proportion or Golden Mean can be observed in the ratio of the vortex in a seashell or in the pattern of leaves swirling upward around their branch. Classical architecture in Greece used the Golden Mean in the symmetrical design of the Parthenon whereby the ratio of the smaller to the larger is the same ratio as the larger is to the whole.

Expressed numerically, the Golden Mean or Phi = 1.618 to 1. This apparently living relationship can be derived from the Fibonacci series of numbers (0, 1, 1, 2, 3, 5, 8, 13, 21, . . .) where each number in the series is the sum of the two preceding numbers and the ratio between them is Phi or 1 to 1.618 Furthermore, the Golden Ratio is found in the pyramid whereby the length of the slant height divided by the length of one side of the base equals 1.618 The ring structure of the Golden Ratio MWO Antenna reflects the proportions so often found in Nature.
Conjugate strips on the backside of the antenna capacitively couple the gaps in the rings. This capacitive loading of the Golden Ratio Antenna creates an oscillating virtual antenna (non-existent but functional or "Scalar") that extends out approximately 1.6 times the diameter of the physical antenna!
This "Radionic" function of the Golden Ratio MWO Antenna is not dependant upon the high voltage, high frequency stimulation of a driving Tesla Coil to produce a multiplicity of oscillating frequencies at different wavelengths... This has the benefit of allowing use of Golden Ratio Antenna as a Mandala to focus energies in a passive "Radionic" manner.

In this time lapse photo we get a glimpse of the radiated power of the new Jumbo Golden Ratio (16" diameter) MWO antenna! This fascinating (and effective?!) rejuvenation technology is now available again for "Experimental Use Only" (Arthritis and a host of other degenerative conditions). The heart of the MWO is a powerful, frequency rich, Tesla Coil with dual spark gaps. This allows for fine adjustment on sensitive areas without sacrificing output power!


Resonator Antenna Wire
ground wire
Radiator antenna wire from center hole to ground bus
resonator antenna wire

How it works:

"Experimental Use Only" subject is placed between two special Antennas which radiate a wide spread of electromagnetic frequencies (all at different wavelengths). Every cell in the body is then exposed to its very best correct vibratory frequency! Just as a tuning fork will make a guitar string resonate back to its original tuned note, so will the MWO try to make every cell in your body vibrate back to its original frequency (of youth?)

Violet Ray Bulb Assembly for The Multi-Wave Oscillator

Edgar Cayce praised the effects of the "Violet Ray"!

Edgar Cayce, one of America's greatest psychics, was able to tap into a higher consciousness (God or the Akashic record) to gain knowledge. He used this psychic power for readings (Such as VIOLET RAY) and to alleviate human suffering. He predicted that in 1958 the U.S. would discover some sort of death ray used in Atlantis (See: "Secrets of Cold War Technology" by Gerry Vassilitos!) Cayce is one of the main people responsible for our current understanding of Atlantis, including the idea that the Atlantaeans had some sort of Great Crystal. Cayce called the Great Crystal the Tuaoi Stone and said it was a huge cylindrical prism that was used to gather and focus "energy," allowing the Atlantaeans to do all kinds of fantastic things. But they got greedy and stupid, tuned up their Crystal to too high a frequency and set off volcanic disturbances that led to the destruction of that world.

ICE AGE!

- **The Violet Ray device is a plasma of Argon Gas used to transduce frequencies into the human body. When we want to work on just one spot or one experimental area, the Violet Ray Wand is the way to do it. This means we can choose a specific area (prostate, breast, lower back, arthritic joints) and focus our attention where it is needed most!**

- **Plasma is a state of matter. Take water for example: we have ice (solid), water (liquid), and steam (gas). There is another state of matter and it is called "Plasma". In our little universe, Plasma is the most common state of matter (like the Sun).**
- **When substances are excited and driven to a state of plasma, they become radiant and conductive. Thus our glass bulb filled with Argon Gas becomes an ideal Radiator for the Multi-Wave Tesla Coil output. (similar to Beam Tubes for output of "Rife" Machines) The effect is quite stimulating... yet gentle!**

Edgar Cayce Readings on The Violet Ray:
* Excerpts from: "An Edgar Cayce Home Guide"; copyright 1982 by the Edgar Cayce Foundation; ISBN 87604-139-X

This Violet Ray Wand was mentioned in the official Edgar Cayce Readings* 825 times ! In the 1930s, Edgar Cayce gave many Life and Health readings from his home in Virginia Beach. In these readings (which have proved to be amazingly accurate), Edgar Cayce often mentioned the effects of stimulation with "Violet Ray", which refers to a plasma of Argon Gas becoming conductive and transmitting the many frequencies of a Tesla Coil directly into the body of an experimental subject. The Violet Ray Wand is included as an attachment to the Multi-Wave Oscillator and is used instead of the Golden Ratio MWO antennas.

The experimental subject (or Practitioner) simply presses and moves glass bulb against any specific part of body! The Violet Ray Wand itself is a rugged Pyrex glass bulb in an insulated handle designed to be a sturdy Massage Tool!

Let's take a closer look at what Edgar Cayce said and then realize scope of experiments for Violet Ray Wand included with your Multi-Wave Oscillator from *ZEPHYR TECHNOLOGY!*

Circulation:

"The primary function of the Violet Ray is to stimulate the superficial circulation. In the process, additional beneficial effects can be achieved. This will make for the abilities of the body to rest better. It will tend to make for strengthening of the body, by the toning of the circulation -as combined with the adjustments that are taken." 1611-2

"The body should use the Violet Ray over the whole circulatory system, for five to ten minutes, sufficiently to start the proper elimination . Do that and we will be able to reduce the condition in the throat and over the system by absorption." 4831-2

"The Violet Ray provides a stimulation to any portion of the body for greater activity, and by not too much but as using the comb of such a Violet Ray machine through the hair and head, will make for such stimulation as to make more growth of the hair and also a better growth of hair" 1120-2

Arthritis

“And the activities of the Violet Ray are only to make for the electrical rejuvenation of nerve energies that have been depleted through the inactivity of the whole system of the body”. 676-1

“The Violet Ray is recommended to overcome these tendencies or to relieve these pressures in the bursae along the joints , along the nerves of the tendons and leaders-superficial activity to be sure”. 888-1

“This will give the ‘pick up’ or the stimulation that is needed for what might be called the recharging of the centers along the cerebrospinal system, so that there is better coordination between the ganglia of the cerebrospinal and the sympathetic nerve system. ” 1196-17

Eliminations

“We would use the hand Violet Ray; this for the nerve forces will aid especially, if it is gradually used across the abdominal area; this given just before the body retires, or when it is prepared for rest, will aid in rest and will aid in relaxing body and stimulating better eliminations.” 1553-20

Rejuvenation

“Apply to the body the correct vibrations from The Violet Ray that will give the incentives to the nerve centers to become rejuvenated again”. 269-1

“As also would the stimulating of the ganglia that are relieved by having the pressures in the spinal segments relieved or released, through the addition of the electrical vibrations from the plain Violet Ray over segments that are changed, which would bring the superficial circulation to such an activity as to cause the flow of the blood supply through same. Thus not only would the distresses in those particular portions be relieved, but the impulse for the circulation through the head and the neck and to the optic forces and to all portions of the face would be such as to improve the functioning of the organs; bringing a nearer normal condition.” 679-2



Primary Frequency Controls and Adjustable Spark Gaps mean you can "tune" your MWO (and Violet Ray Wand) to achieve maximum Resonance in Experimental Subject... With Benefit of achieving "Rejuvenation"!

A Look at the Competition

1) Gene Koonce of VIBE Technologies.
www.vibemachine.com
The "VIBRATIONAL INTEGRATION BIO-PHOTONIC ENERGIZER" or "VIBE Machine". The promotional literature states: "..technologies based on the theories of Lakhovsky, Tesla, Rife and Clark... Bio-Photonic Light .. increases your inner-connectively [*sic*] to your DNA, giving it what it needs to heal itself." I observed this device again at 2005 ExtraOrdinary Technology Conference in Salt Lake City : the VIBE Machine consists of a well made fixed spark gap Tesla Coil which powers a series of thin vertical glass tubes (from Edmund Scientific), each filled with a different noble gas, or combination of noble gasses. Vertical glass tubes are arranged in Star of David pattern and topped off with a thin copper wire toroid winding around an acrylic core. This unit is capped by a "Sacred Geometry" "Environmental Harmonizer" designed and/or made by Slim Spurling. Overall, the workmanship and attention to detail is outstanding on The Vibe Machine! During his lecture at the USPA Conference in Columbus Ohio, 2003 (which consisted solely and exclusively of testimonial stories describing miraculous and beneficial cures), I raised my hand and asked Gene Koonce to describe how his Tesla Coil circuit worked. *"It's a Secret"* was the friendly answer! From simple observation of unit in operation, this device uses 3 neon sign transformers (120° out of phase) connected directly to the ac grid (contaminates the output with unwanted 60 Hz). Device appears to be a fixed spark gap Tesla Coil, 1/4 wave, loose coupled with a pancake style primary winding. The unit is "closed architecture" which means, despite a nice "fruitwood" appearance, you cannot see or know for certain, what's inside. This means you're buying "the benefits" not knowing what you're really getting ...



Price: A whopping $17,500- (Yikes!)

2) Mike Brown Solutions:
www.mikebrownsolutions.com
This is a "Ralph Bergstresser" MWO virtually unchanged since 1965. Notice it has one small, single sided copper antenna, and a Violet Ray Wand using the good General Electric AR-1 bulb. Output power is weak and contaminated with the 60 HZ from the ac power lines. Camshaft style spark gap constantly forms a solid "arc" resulting in complete loss of harmonics. Price: $975-

A Look at the Competition Continued:



3) Hessel Hoornveld from Holland:
http://www.emfsafe.com/mwo
This is a slightly updated "Ralph Bergstresser" Tesla Coil power supply. As with all units of this design, output is basically that of a neon sign transformer (contaminated with unwanted 60 HZ ac from the power lines). Good effort on recreating the cumbersome solid metal rings of the antenna design. Note that it is difficult to space the suspended rings evenly, resulting in lack of harmonics. (Notice how they are out of round!) Unit is a real MWO!
Moderately overpriced at: $4500-



4) Bruce Copen Labs in England
www.brucecopenlaboratories.com
High quality "Fruitwood" Radionic instrument that bears a cursory resemblance to Multiple Wave Oscillator. There is no Tesla Coil and no output of any kind except "Subtle Energy". Price: About $1600-

5) Harmonic Pulser from Sota Instruments
http://www.sotainstruments.com/hp/
This is an Ed Skilling instrument (prolific inventor of the Super-Pro Rife Machine, Photon Sound Beam, and other instruments). The Harmonic Pulser is a small "black box" powered by a nine volt battery. Whatever features, advantages and benefits attributed to the Harmonic Pulser, it is not a Tesla Coil and resembles the Multi-Wave Oscillator only in name. Price: About $200-

6) Photon Sound Beam from Transformation Technologies
http://www.braintuner.com/photon.htm#PHOTON
This is another invention from the prolific Ed Skilling that does resemble the Violet Ray Wand of Edgar Cayce fame. Featuring multi-use application, the description continues: "The Photon Sound Beam provides a full-harmonic spectrum of bio-available photon energy to meet the body's essential need for direct, holistic photobiotic nutrition..." Whatever it is, the Photon Sound Beam is not a Multi-Wave Oscillator. Price: $1995-

A Look at the Competition Continued:

7) *Various Knockoffs of The Vibe Machine:*

A) The Sead 6000 (Subtle Energy Activation Device) $5000- to $8000-. Claiming all benefits accrued to both Lakhovsky and Rife; you get a "poor boy" imitation of the well made VIBE Machine.

B) The Novalite 3000: A better attempt to copy The VIBE Machine: $5000- to $8000- (Ralph Suddath here, a good guy!)
These "knockoffs" available at:
www.braintuner.com
www.wellnesstools.com
www.novaliteresearch.com


THE SEAD 6000 MACHINE

THE NOVALITE 3000

C) The BioCharger: Various Models. Evidently some contention about who invented what and who holds patents for various configurations of "The VIBE Machine".

- **Previous called: "The Bio-Electric Light Stimulator" BELS Machine.**
- **U.S. Patent #6,217, 604 (Larry Azure and James David Girard)**
- **U.S. Patent #5,908, 444 (Larry Azure)**
- **From the their Website: http://www.bestengineering.org/bels-88.html**
- "The *BioCharger* ADVANCED 1988 Model combines the work of early energy pioneers Tesla, Lahkovsky AND Royal Rife by incorporating an exclusive new option: a variable power input control that provides modulation of the output signal and Rife modality treatment benefits to the device." [*Sic*] Sounds like a Variac to me (ha)
- Closed architecture, of course; but here's exactly what it is: One 6000 volt Neon Sign Transformer, One .2 mfd HV Capacitor, One Spark Gap and twelve Noble Gas Demonstration Tubes from Edmond Scientific. Claims all benefits and legacy from Tesla, Lakhovsky, Royal Rife *and* Dinshah P. Ghadiali (Nice work if you can get it!)



Price: $17,500- Same as Vibe Machine (Ouch!)
Like the Vibe, it does have lots of power...but still not a real MWO (because no enclosing antennas to capacitively load subject into actual Tesla Coil Circuit)

A Look at the Competition Continued:

9) Dan's Enhancer:

http://www.dansenhancer.com/

From the Dan's Enhancer Website:

"The Molecular Enhancer© operates on a very simple principle. It oscillates the cell's subatomic structure to increase its energy-field. This, in turn, charges the total molecular structure of the cell, increasing its energy-field size."

"The Molecular Enhancer© is a multiple-wave oscillator. It saturates the cells of the body with the appropriate resonate energies on which the cells' electro-chemical systems depend (feed) on."

WRONG! Dan's Enhancer is a 12,000 volt neon sign transformer, two sheets of glass, one sheet of aluminum foil, a small sheet of copper, and a neon bulb. Well made, yes; but still a Neon Sign Transformer: no more and no less. And you get beaucoup 60 Hz in the bargain. Dan's Enhancer not Tesla Coil Device; Is NEON SIGN TRANSFORMER...

Price: $ 1840- Shipping Extra ($ 120-)

***10)* Tools for Healing:**

http://www.toolsforhealing.com/products/MWO/MWOHomePage.html

Designed and built by Ed Wahler of Fletcher North Carolina, Ed contacted Zephyr Technology in 2002 for help building his own Multi-Wave Oscillator; and now offers them for sale (Good!). Exactly what Bob Beck and Tom Bearden said all along: "The Government can shut down one inventor, but not thousands.." Thus policy of Zephyr Technology (Using Open Architecture) to freely disclose schematics and diagrams has yielded success! From the Tools for Healing Website: ***"The unit we have weighs 55 pounds. Half that weight is from the power transformer alone - this is a very high-powered device".*** **Sad to say, above statement reveals NEON SIGN TRANSFORMER lurks within... (Neon Sign Transformer means beaucoup 60 Hz whether you like or not!) "Closed architecture", means you cannot see what's in there... (too bad). But I will tell you exactly you get: One Neon Sign Transformer; one spark gap; one capacitor and two Tesla Coils, each driven by the Neon Sign Transformer. No Primary Frequency Adjustment and No Spark Gap Adjustment: i.e. No Way to "Tune" the MWO for each user (everyone is different due to the distributed Capacitance "Load" of the human body...)**

Price: $ 3249- Plus Shipping: approx $100- extra. This unit is actually a real MWO.

Multiple Wave Oscillator Parts Price List:

ZEPHYR TECHNOLOGY!
PO Box 55
Bellbrook, Ohio 45305
(937) 429-3847
mwo@zephyrtechnology.com
www.zephyrtechnology.com

Complete Multiple Wave Oscillator: $3960-

- **One year warranty on materials and workmanship**
- **90 day money back guarantee on performance and results! Experimental use only**

- **Jumbo Size (16" diameter) Golden Ratio MWO antennas! Designed by Eric Dollard of Borderland Science. These double sided, Heavy Duty, Gold plated, antennas produce a spatial field that reaches out to envelope the subject in an Ætheric field of oscillating vibrations:** ***$180- each; two for $320-***
- **Liquid Filled Tesla Coil: Close coupled; self healing Liquid Mineral Oil insulation between primary and secondary, with modular connections. This coil has never failed at 160,000 volts of dielectric stress! Coil is approx 8" long and 2 1/2" diameter; features see through clear acrylic (and liquid filled) design. This coil is close coupled and 1/4 wave; BOTH ENDS ARE HIGH VOLTAGE!** ***$560-***
- **Dual Timer/Mosfet Assembly; chops primary current from 130 cycles per second to approx 1300 cycles: Features dual Mosfets for both "Frequency" and "Dwell" to control "on time" of auto coils to prevent oversaturation.** ***$560-***
- **Capacitor Assemblies: .0125 mfd @24kvac (that's AC not dc!); These are MMC style capacitors of 12 Cornell Dubilier polypropylene film/foil #942C 20P15K; each Multi- Mini Capacitor array sealed in heavy Vinyl Tubing with wires: *ZT* MWO takes two assemblies.** ***Two for $560-***
- **Tungsten Spark Gap Assemblies; mounted on acrylic; with Nylon bolt and nut assembly for adjustment: ZT MWO takes two assemblies.** ***Two for $260--***
- **High Voltage Auto Coil/45KV piv Diode Assembly; mounted together in vinyl tubing with HV wires wrapped in vinyl. Features MALLORY or JACOBS Coils. MWO takes two Hot Rod Auto Coil/Diode Assemblies.** ***$190-each***
- **Violet Ray Wand with Quartz Glass Bulb (Argon & Neon) housed in heavy PVC safety handle with 6 foot vinyl lead wire.** ***$360-***

Bruce M. Forrester Jr and Steve Elswick at the recent Nikola Tesla Energy Science Conference & Exposition in College Park, Maryland. This well attended two day scientific conferrence, hosted by Tom and Jackie Valone of Integrity Research Institute featured both "Wireless Electricity" and "Electrotheraputics".

PACKING LIST:

1) THIS DEVICE IS NOT FOR HEALING OR MEDICAL USE! For experimental research only; all experimental subjects should be in at least reasonably good health!
2) DANGER! HIGH VOLTAGE! Use Caution when operating this High Voltage Tesla Coil Power Supply… Use the "One Hand Rule"; this means: "Keep one hand in pocket" when adjusting the unit. MWO MUST BE GROUNDED!

- **One large black case housing the Tesla Coil Power Supply**
- **Two Jumbo 16" Golden Ratio Multi-Wave Oscillator Antennas (One "Radiator" and One "Resonator").**
- **One Violet Ray Wand (Argon or Neon Bulb)**
- **One Short Insulated Radiator Antenna Wire (TEST WIRE) with clear vinyl sleeve. Use Test Wire to Ground Center Ring Terminal of Radiator Antenna.**
- **One 12' long Insulated Resonator Antenna Wire; with clear vinyl sleeve.**
- **One High Voltage Discharge Terminal. This is part of the Radiator Antenna Standoff System. Plug Radiator Antenna into High Voltage Jack.**
- **One Adjustable Resonator Antenna Stand (in three pieces: Round Oak Base; two PVC pieces, & Heavy rubber band height holder)**
- **One Extension cord (three hole kind: MWO must be grounded)**
- **One packet of Velcro Strips (to secure antennas into proper position)**



Multiple Wave Oscillator

ZEPHYR TECHNOLOGY!
PO Box 55
Bellbrook, Ohio 45305
(937) 429 3847
(937) 429 3849 FAX
bruce@zephyrtechnology.com
www.zephyrtechnology.com
Technology for The New Age

ORDER FORM:

- **Multi-Wave Oscillator: A high voltage Tesla Coil device used to expose the human organism to an Ætheric field and a multiplicity of oscillating frequencies . The idea is to elicit an intense detoxification response on a cellular level as the tissues attempt to resonate, each to their corresponding natural and innate frequency. This device has a powerful legacy, going back to the 1920s, of experimental rejuvenation in a variety of alternative conditions.**
- **A Russian émigré, Georges Lakhovsky, developed this device in Paris early in the 20th Century as a remarkable rejuvenation device. The Tesla Coil output contains an "Ætheric Field" considered to have rejuvenation properties. The MWO may be considered: "An Experimental Rejuvenation Machine"**

Today, the Multi-Wave Oscillator (MWO) is not for any healing or medical use. It is "experimental use only" on persons who are in reasonably good health.

- ***Read Carefully and please sign: I am in reasonably good health and understand the MWO is not for any healing or medical purpose. Should I have or develop a medical or disease condition, I agree to seek and get authorized medical treatment from a licensed physician (Medical Doctor) before attempting any program of experimental use with the MWO. I hold ZEPHYR TECHNOLOGY harmless from any improvement or worsening of my health or condition (Caveat Emptor!)***

Cost: $ 3960-; Shipping by United Parcel Service: $37-
Total Cost: $3997- Lead time: 2 to 3 weeks from pre-paid order.

- ***Warranty: One full year on materials and workmanship.***
- ***90 Day Refund Privilege for any reason.***
  25 % Restocking Fee on returns. Referral Program available…

Date:_________________________

Name:____
Address:____
City, State, Zip____
Phone:____
Amount enclosed:____
Visa/MC with exp date: _______________________________________

Signature:____

ZEPHYR TECHNOLOGY!
PO Box 55
Bellbrook, Ohio 45305
(937) 429-3847 Office
www.zephyrtechnology.com
bruce@zephyrtechnology.com
Technology for The New Age

Multi-Wave Oscillator

(Tesla Technology Experimenter's Kit)

This Technology for the New Age may be similar to that utilized by Flying Saucers… We strive to emulate, copy and mimic observed UFO technology as reported to be associated with the human-like UFO occupants known as "The Blondes":

- **Multi-Wave Oscillator: A high voltage Tesla Coil device used to expose the human organism to an Ætheric field and a multiplicity of oscillating frequencies. The idea is to elicit an intense detoxification response on a cellular level as the tissues attempt to resonate, each to their corresponding natural and innate frequency. This device has a powerful legacy (going all the way back to the 1920s) of experimental rejuvenation in a variety of alternative conditions.**
- **A Russian émigré, Georges Lakhovsky, invented and developed this device in Paris early in the 20th Century as a remarkable rejuvenation device.**



The Tesla Coil output contains an "Ætheric" or "Radiant Energy" field independent of any traditional electro-magnetic oscillations. This Ætheric field is the actual "Force" or Primary Energy (also called Orgone, Chi, Prana, Zero point) and is widely considered to have rejuvenation properties in and of itself.

- ***The Multi-Wave Oscillator is a "Rejuvenation Machine"***

Complete Multi-Wave Oscillator Includes:

- ***High Power Tesla Coil Power Supply (****Open Architecture****)***
- ***Two Golden Ratio Antennas with all wires & connectors***
- ***Violet Ray Bulb Assembly for direct stimulation of any part of body***
- ***High Voltage Discharge Terminal on Radiator Antenna.***
- ***Complete Info Pack and Instruction Booklet detailing the invention, history and use of this instrument complete with experimental protocols. (Easy to set up & use!)***
- ***Cost: $3960- Shipping by UPS ground $37-***
- **Grand Total: $3997- delivered**
- ***Delivery time two to three weeks from prepaid order. Visa/Mc accepted***

FROM ZEPHYR TECHNOLOGY!

THE LAKHOVSKY MULTIPLE-WAVE OSCILLATOR

- **Multi-Wave Oscillator**
  High voltage Tesla Coil device used to expose human organism to an Ætheric field and multiplicity of oscillating frequencies. The idea is to elicit an intense detoxification response on cellular level as tissues attempt to resonate, each to their corresponding natural and innate frequency. This device has powerful legacy (going back to 1920s) of experimental rejuvenation in variety of alternative conditions.
- **A Russian émigré, Georges Lakhovsky, invented and developed this device in Paris as a remarkable rejuvenation device used in the clinics of his day…**

How it works:

"Experimental Use Only" subject is placed between two special Antennas which radiate a wide spread of electromagnetic frequencies (all at different wavelengths). Every cell in the body is then exposed to its very best correct vibratory frequency! Just as a tuning fork will make a guitar string resonate back to its original tuned note, so will the MWO try to make every cell in your body vibrate back to its original frequency (of youth?) This device is a faithful replication of the original Lakhovsky Multiple Wave Oscillator using modern electronic components. This device must not be substituted for authorized medical care from a licensed physician.

ZEPHYR TECHNOLOGY!
PO Box 55
Bellbrook, Ohio 45305
(937) 429 3847 Office
(937) 429 3849 FAX
www.zephyrtechnology.com
bruce@zephyrtechnology.com
Technology for The New Age

The Rife Machine Report

A History of Rife's Instruments and Frequencies

www.rife.org


FILAMENT
SWEEP
OUTPUT

The Rife Machine Report

A History of Rife's Instruments and Frequencies

Updated 03/01/2013 Copyright www.rifevideos.com 2003-2013

www.rife.org

This report from its first writing back in 2003 has been an evolving document. The current report supersedes all previous reports that have been released.

Whenever original Rife instruments, schematics or documents have been found this report has been updated according to the information that was obtained. This report was updated in 2010 because at that time an original 1938-1939 Rife Ray #5 or Beam Ray Clinical Instrument had been found and analyzed. That instrument was built by the original 1938-1939 Beam Ray Corporation. At that time the analyzing of that instrument finally showed where the audio frequency instruments came from which Dr. Rife used in the 1950's. It was updated in 2011 and 2012 when some new information came to light about Dr. Gruner's Rife machine and John Marsh's documents. The last revision of this report was dated 12/01/2012.

This report is being updated now because more of John Marsh's documented information has come to light. Two of his ray tube instruments have been obtained that were built in the 1970's and 1980's. More extensive photos have been taken of those instruments and have been added to this report at this time. Also this report has had a great deal of updating and clarifying in almost all of its chapters. With these updates the report has increased from 153 pages to 224 pages.

In this report we will examine the way Dr. Rife's instruments were built. We will look at the evidence by quoting the sources such as Dr. Rife, John Crane, John Marsh, Dr. Couche, Dr. Lara, Dr. Stafford and Bertrand L. Comparet (Dr. Rife's attorney in the 1939 Beam Ray Corporation Trial, and later John Crane's attorney for Life Labs' trial in 1961). Hopefully anyone who reads this report will have a better understanding about Dr. Rife and the methods he used. Our goal is to try to give people information so that they will know how Dr. Rife's equipment worked so that they will not be misguided by all the misinformation and disinformation that has been published on this subject. The writer of this report has tried to explain the information in layman's terms.

This report, called by the same name, is also online at www.rifevideos.com. All of the quoted documentation is linked in the online report for those who want to study the documents used to back up the quotes used in this report. Also online are more photos of the equipment shown in this report.

We will continue to update this paper when new information is obtained.

The Rife Machine Report table of contents

Chapter 1 - What is a ray tube and how does it work? 4
Chapter 2 - What power levels did Dr. Rife use in his Rife Machines? 9
Chapter 3 - Is it necessary to use a Ray tube to output the frequencies? 12
Chapter 4 - Are Dr. Rife's RF frequencies safe to use? 17
Chapter 5 - Did Dr. Rife use audio frequencies? 20
Chapter 6 - Dr. Rife's 1920 to 1922 Rife Ray #1 Rife Machine 23
Chapter 7 - 1934 Rife Ray #3 Rife Machine used in the 1934 clinic 26
Dr. Rife's misread lab note frequencies from before 1935 (Chart) 48
Chapter 8 - 1935 Rife Ray #4 Rife Machine 49
Rife Ray #4 sine wave high RF frequencies (Chart) 57
Chapter 9 - 1938 to 1939 Beam Ray Corporation Clinical Rife Machine 58
The Beam Ray Clinical instrument sideband sine wave audio frequencies based on a 3.80 MHz carrier (Chart) 90
Beam Ray instrument sideband sine wave audio frequencies (Chart) 91
Oscilloscope waveform readings of the original Beam Ray Clinical instrument 93
Original Beam Ray spectrum analyzer graphs for microorganisms 94-100
Upper harmonic frequency charts for Microorganisms 101-102
Photos of the original 1938-1939 Beam Ray Clinical instrument when found 103-105
Chapter 10 - The Gruner schematic of Philip Hoyland's Beam Ray laboratory instrument 106
The initial Gruner schematic work done 3 years ago 108
Deciphering Dr. Gruner's Beam Ray instrument schematic 109
Rebuilding Philip Hoyland's Beam Ray Laboratory instrument 110
The modulated Audio Frequency pulsing circuit 113
Mr. Peters' photos of the rebuilt Beam Ray Laboratory instrument 118
Second machine photos of the rebuilt Beam Ray Laboratory instrument 119-121
Beam Ray Clinical instrument Schematic 122
Chapter 11 - Aubrey Scoon's Beam Ray replica Rife Machine Re-evaluation 123
Aubrey Scoon's sideband audio frequencies reconciled to Rife's original high frequency M.O.R.s. (Chart) 134
Aubrey Scoon's Beam Ray replica spectrum analyzer graphs for microorganisms 137-144
Photos of the rebuilt Aubrey Scoon Beam Ray Clinical instrument 145
Aubrey Scoon's Beam Ray Clinical replica schematic 146
Aubrey Scoon 1939 Rife Beam Ray website report 147-159
Aubrey Scoon's Beam Ray audio frequencies (Chart) 156
Chapter 12 - Dr. Rife and Verne Thompson's 1950's AZ-58 Beam Ray replica Rife Machine 160
Original 1950's AZ-58 frequencies used by Dr. Robert P. Stafford M.D. (Chart) 175
1950's Beam Ray Clinical instrument optimum sideband square wave audio frequencies based on a 4.68 MHz carrier (Chart) 176
Photos of the rebuilt AZ-58 Beam Ray Clinical instrument 179
AZ-58 Beam Ray Clinical instrument schematic 180
Chapter 13 - Rife Machine Harmonic Audio Frequency Misunderstanding 181
AZ-58 M.O.R. audio frequencies square wave harmonics (Chart) 184
Chapter 14 - Life Labs 1950's pad instrument (without ray tube) 186
Chapter 15 - John Marsh's 1970's Beam Ray replica Rife Machine 197
John Marsh's Beam Ray Clinical instrument sideband square wave audio frequencies based on a 4.122 MHz carrier (Chart) 209
John Marsh's Beam Ray Clinical instrument higher sideband square wave audio frequencies based on a 4.122 MHz carrier (Chart) 210
Chapter 16 - John Marsh's 1980's Ray Tube Rife Machine 211
Chapter 17 - Summary 219
Rife's M.O.R. frequencies and audio sideband frequencies (Charts) 224

www.rife.org

Chapter #1

What is a Rife ray tube and how does it work?



Dr. Rife used a ray tube with his Rife Machines. The photo, shown above, is a picture of the style of double-bubble ray tube which Dr. Rife used for many years in his laboratory. A ray tube was made out of glass, quartz or Pyrex and was filled with a noble gas or a mixture of noble gases.

The next photo, shown below, shows Dr. Rife's double-bubble ray tube in his laboratory right next to his microscope.



www.rife.org
www.rifevideos.com

Some people believe that there was something magical to the gas mixture that Dr. Rife used in his ray tube. There are also people who claim that they use some proprietary blend of gases that makes their ray tubes work exactly like Dr. Rife's. Others even claim that their gas formula works better than Dr. Rife's did. The truth is that none of this rings true because of what Dr. Rife has said on this subject. Dr. Rife knew more about these gases than most anyone else since he used different gas mixtures over a thirty year time span. The fact is Dr. Rife used many different mixtures of gases but eventually ended up using only helium. To verify this we will read his statement:

RIFE: *"We have experimented with various inert gases and we found that helium stood up by the bombardment better than any of the other gases. That's why we use it. We don't care about the color or anything of that sort. It stood up better over many more hours of bombardment than the argon and the crypton* [krypton] *and those different gases that we tried."* (John Marsh Collection, Gonin and Siner Papers, Page 25)

From what Dr. Rife said in the above quote it is apparent that he tested many different gases over the years in his laboratory and they all worked. But we find that he decided to use only helium because it lasted longer in the ray tube.

The ray tube was connected to Dr. Rife's Machine by two wires. These wires were connected to two round metal bars that went into the glass tube and they had round disks connected to their ends. One disk was straight and the other one was on a 45 degree angle. This gave it a directional effect towards the patient.

Below is a photo showing the internal electrodes that were built into the ray tube. You can see that one is straight and the other is on a 45 degree angle.



Dr. Rife stated that the ray tube was "a partial directional antenna". Because the scientific technology behind ray tubes had already been perfected, Dr. Rife worked with that technology and only had to make some adjustments for it to work the way he wanted it to in his applications. Bertrand L. Comparet, Dr. Rife's attorney, stated in an interview:

COMPARET: *"Now, the original instrument had a tube, like an X-ray tube. That was the way in which Rife developed it. You see, all the X-ray work necessarily was done with a beam projected from a tube. So, Rife worked on the same basis."* (1970's Bertrand Comparet Interview #32)

Although Dr. Rife used X-ray tubes in his work they did not put out any X-rays. Because the ray tubes used inert gases they did not produce X-rays. They work on the same principle as a neon sign. The gas that is used in a neon sign does not produce any harmful rays of any kind. Inert gases such as helium, argon, krypton, neon and others can safely be use in these ray tubes without producing X-rays. These gases are considered noble gases and there are 18 different types. The ray tube is just an antenna and the noble gas will emit the frequency when the plasma is lit. This makes a ray tube a safe

www.rife.org

method of delivering the frequencies. If you use a metal antenna and someone just happened to touch it they could receive severe third degree RF (Radio Frequency) burns.

Many people believe that ray tubes are just as efficient as metal antennas, and this may be true. They also believe that the energy emitted from a ray tube will actually travel farther with less loss than a metal antenna. Since there are no actual scientific tests comparing the output of ray tubes to metal antennas it is hard to know for sure if these assumptions are correct. For this report we will accept what is known, not what is un-known. Therefore we will compare ray tubes to metal antennas since they both are designed to emit frequencies.

There are limitations to metal antennas that need to be understood and this has to do with the laws of physics. It is referred to as the "Inverse-Square Law". This law deals with power loss and distance. We will give a simple explanation which should suffice since we are trying to stay in layman's terms and make it easy for the average person to understand this information. When a circuit is properly tuned metal antennas are very efficient. About 100% of the energy that you put into a metal antenna comes out, but only if the impedance is matched correctly.

Dr. Rife’s Rife Ray #3 instrument information which has been obtained from the Rife documents list that about 50 RF watts was input into the ray tube. If we compare this to a metal antenna this means about 50 watts would have passed through and come out of the ray tube. When it comes to metal antennas and the inverse-square law on signal loss this would mean that you would have to divide the 50 watts which come out of the metal antenna by four for every foot that you move away from the antenna. The exact power loss of a ray tube, as stated before, is not known but if a ray tube is equally as efficient as a metal antenna, and we believe it is, then the same laws of physics would also apply to it.

Because no actual scientific tests have been done with ray tubes demonstrating that they are exempt from the inverse-square law then we are left with only one conclusion, this law does apply to ray tubes. Because of this we will use this inverse-square law of power loss for a ray tube. Therefore, with a 50 watt power output at one foot away from the ray tube you would only have 12.5 watts. At two feet you only have 3.125 watts and at 3 feet you only have about .78 of a watt. The laws of physics are important to understand because Dr. Rife and the doctors that used his equipment put the ray tube within a few inches to a few feet of the patient’s body. One of Dr. Rife's 1950's business partners, John Marsh, wrote a paper in which he stated that the Ray tube should be used from 12 to 24 inches from the body:

MARSH: *"A frequency instrument with therapeutic applications which has been developed and successfully tested over a period of year’s works on the principle of stimulating tissue with low energy, low frequency pulsating current. It applies electron transmission at variable frequencies from an applicator source, which consists of either (1) a bare anode and cathode (in direct contact with the body) and constructed from metal for easy transmission flow of electrons, or (2) from an antenna broadcast source at a distance of 12 to 24 inches."* (An Explanation of the JLMSQ-1A frequency instrument and its use. Page 1-2).

Dr. Couche said that he would sometimes touch the body of the patient in the area that needed to be treated. When we discussed this with Dr. Robert P. Stafford M.D., he said that when he treated cancer patients he would put the ray tube within a few inches of the body and treat a 6 inch square area. He would move the ray tube up and down and back and forth so that the whole 6 inch area was treated. He said that he did this because of the way the phanotron (ray tube nickname) ray tube worked. The design of a phanotron ray tube makes it partially directional and concentrates its energy or power into a smaller area. Due to the "Inverse-square law" power loss it is easy to understand why Dr. Stafford, Dr. Couche, Dr. Rife and the other doctors used the ray tube right next to the body. Many people have used these RF (Radio Frequency) ray tube instruments and have notice that within several feet they will get a strong reaction but beyond this it drops of very quickly. It is apparent that there was a good reason why the ray tube was used close to the patients body.

We built both the Aubrey Scoon Beam Ray replica ray tube instrument and the 1953 AZ-58 Beam Ray replica ray tube Rife Machine. The 1953 AZ-58 (Rife instrument made by Life Labs) was built from schematics that are on Stan Truman's site, http://www.rife.org, under AZ-58 research information. This AZ-58 instrument is nearly the same as the original Rife Ray #5 or Beam Ray Clinical instrument and schematics can be found on this page.

Both Aubrey Scoon's instrument and the original Beam Ray instrument use sine wave audio frequencies and the 1953 AZ-58 uses square wave audio frequencies. We tested the AZ-58 and Aubrey Scoon's replica for penetration and found that at about 32 inches from the body full penetration of the carrier frequency emitted from the ray tube was lost with our frequency detection device. This test was done in this manner. A B&K frequency counter was used and the antenna was put in a fold of body tissue on the front of the body. The ray tube was put behind the person and move backwards until the carrier frequency could no longer be read through the person's body. John Crane listed the AZ-58 as outputting 14 watts out of the ray tube but we tested it and found it outputs at least 30 to 40 watts. The 1950's Aubrey Scoon instrument puts out about 30 to 40 watts also.

Another test was made using a crystal for testing resonance. The audio frequencies broadcast out of the ray tube from both of these machines could only resonate a crystal designed to test resonance through about two inches of tissue. From the tests made, it takes a carrier frequency of at least 0.125 watts to penetrate all the way through the body. It could take an output of 50 watts from a ray tube to resonate a crystal through 14 inches of tissue. These tests showed that it takes more power to penetrate all the way through the body when modulating an audio frequency on a carrier frequency than when a single un-modulated frequency is used. The tests were done using the AZ-58 replica and the Aubrey Scoon replica Rife machine using a phanotron ray tube outputting about 30 to 40 watts. Another interesting thing worth noting is when we turned the ray tube more than 45 degrees either to the right or the left of center we could not resonate the crystal. Another test showed we could not resonate the crystal at all on the backside of the phanotron ray tube proving what Dr. Rife said:

RIFE: *"The ray tube is a partially directional antenna."*

One interesting fact worth noting is the ray tubes that do not use the internal electrodes, like the Phanotron ray tube, have a higher field strength reading which indicates a greater output. These ray tubes use copper collars or wire wrapping around the ray tube. These ray tubes also last longer because the gas inside the ray tube does not get contaminated. The contamination comes from the internal metal electrodes. Over time the metal from the internal electrodes comes off and slowly contaminates the gas. It will also deposit on the inside of the glass making the ray tube go darker. In the photo below you can see how the ray tube has darkened.



www.rife.org

The next photo, show below, is a picture of Dr. James B. Couche's Rife Ray #5 or Beam Ray Clinical instrument which he purchase from the original 1938-1939 Beam Ray Corporation. The ray tube is Dr. Rife's original double-bubble ray tube which he used for over 30 years in his laboratory. You can see how the ray tube has darkened. This was a common problem which required the ray tubes to be cleaned and re-gassed on a regular basis. A better view of this double-bubble ray tube is shown in the two photos on page 4.



Chapter Summary: A ray tube is a plasma antenna built for the purpose of outputting frequencies. Dr. Rife built many different styles of ray tubes. The gas used inside the ray tube does not really matter as long as it is a noble gas (Helium, Argon, Krypton, Neon, etc.). Dr. Rife settled on using helium because it lasted longer in a ray tube that uses internal electrodes. The ray tube made it possible for Dr. Rife to safely use a powerful RF (Radio Frequency) frequency instrument next to a person or microscope. Dr. Rife preferred using a ray tube over pad type instruments because a great deal more power meant a better outcome for the patient.

Many people have wondered what power levels did Dr. Rife use in his instruments. In the next chapter of this report we will discuss the power levels of Dr. Rife's instruments.

www.rife.org

Chapter #2

What power levels did Dr. Rife use in his Rife Machines?

www.rifevideos.com

Many people have wondered what power levels are safe to use when using an instrument like Dr. Rife's machine. According to the documents we have Dr. Rife’s ray tube instruments, such as the Rife Ray #4 Rife Machine, was listed to be able to output as much as 400 watts. When the test for B. Typhosis was made it was listed that they used 400 watts. The milliamp meter was listed at 450 milliamps for those 400 watts. Since the equipment of that era would have only been about fifty percent efficient then the true power output from the ray tube would not have been more that about 200 watts, not 400 watts. The Rife Ray #4 was the most powerful of the five machines that Dr. Rife built. Dr. Rife did not notice any problems using instruments with power levels between 40 to 250 watts of power output. Next are two statements made by Dr. Rife about the safety of his instruments:

RIFE: *“I have operated the frequency instrument since 1921. I have watched it advance in style and performance with the advancement of electronics. In the many years I have used this equipment in my research, I have never suffered an injury or any ill effects whatsoever. I found it reliable in performance and efficient in results.”* (Letter from Dr. Rife to Dr. Justin Stein, July 2, 1956)

www.rife.org

Also on the John Marsh, Rife audio CD's Dr. Rife made this statement about his RF frequency instrument:

RIFE: *"I stood in front of that thing for thirty years finding these different frequencies that devitalize these different bacteria. And that thing* [RF ray tube] *was shooting on me right here [his chest], but it is absolutely harmless to normal tissue and each individual bacteria requiring a different frequency to devitalize."* (John Marsh Rife CD's)

www.rife.org

The Rife Ray #5 or Beam Ray Clinical instrument built by the Beam Ray Corporation in the 1930's output, at the most, about 40 watts out of the ray tube. The 1950's AZ-58 Life Labs instrument and the Aubrey Scoon 1950's instrument also only output about 40 watts. Because some of Dr. Rife's information about instrument power levels is confusing, most have believed Dr. Rife's Machines put out 400 to 600 watts to the ray tube: however, the new information from the building of some of these instruments shows these assumptions are not correct. The problem has been that the people who wrote down this information were incorrectly giving the power usage of Dr. Rife's Machines as the output power. Dr. Rife's Machines used generally about 400 to 600 watts but they only output about 40 to 250 watts out of the ray tube. The Rife Ray #4 did output more power but this was the exception not the rule. In the paper entitled "Development of the Rife Ray" it states:

www.rife.org

"The frequencies were generated by a tube oscillator with many stages [5 stages] *of amplification, the final stage being a 50 watt output tube."* (Development of the Rife Ray and use in devitalizing of pathogenic micro-organisms)

This part of the description is of his pre-1935 instrument. The output tube was not the ray tube. It appears from the documents that Dr. Rife's pre-1935 instruments did not output any more power than about 50 watts out of the ray tube. He said he lit the ray tube from another power source then input the frequencies into the ray tube. When Dr. Rife, John Crane and John Marsh were working on sea water conversion - a process that used frequencies - they boosted the output power in the instrument. Concerning that instrument and some 1930's Beam Ray instruments that Dr. Yale had increased the power level on, Dr. Rife said the following:

www.rife.org

RIFE: *"Now this outfit here - the way we have it boosted up here now with an extreme lot of power behind the actual output that is coming out of the thing...I wouldn't want to use this - or I wouldn't want to use this instrument here the way it is souped up there for this salt water proposition to treat a patient with."*

GONIN: *"No."*

RIFE: *"You can get beyond the limit* [power levels in excess of 250 watts]*."*

www.rife.org

GONIN: *"Yes, quite."*

CRANE: *"That's what Dr. Yale did. You see, he stepped it up and up and up…"*

RIFE: *"When Verne Thompson used to go down there and take care of Yale's machines - when he began stepping them up and so...where you get up into that extreme power…oh yes, that is not good. With the power that is in these* [50 to 100 watts of power coming out of the ray tube], *there is absolutely no harm because I had my microscope here - I had my tube [ray tube] right here in front of it - oh, about 11 or 12 inches away from the slide in the microscope and here I was with this thing all around like that and that tube going here and my specimens and the microscope year after year tuning that thing and it never harmed me any."* (See the photo at the beginning of this chapter for a better understanding of this statement about where the ray tube was located.) (1950's Gonin, Rife, Crane and Marsh Paper #27-32)

www.rife.org

Because Dr. Yale’s 1938-1939 Beam Ray Corporation Rife Machines were modified they were putting out a lot more power than Dr. Rife felt was safe. We do not know how Dr. Yale had his machines modified so it is not possible to know the exact power output they had. But he must have been exceeding the power output of the Rife Ray #4 which could output about 250 watts (true power). It may be that Dr. Rife was just overly cautious but his statement should be considered when anyone starts using power levels in excess of 250 watts true power output.

Chapter Summary: Dr. Rife's ray tube instruments output anywhere between 40 to 250 watts of RF (Radio Frequency) power levels. Dr. Rife found that his instruments were safe to use with power levels between 20 to 250 watts. Power levels in excess of about 250 watts (true power output) were not recommended by Dr. Rife.

In the next chapter we will discuss whether it is absolutely necessary that a ray tube should be used or if it is possible to use the contact method of delivering Dr. Rife’s frequencies which he used on microorganisms.

www.rife.org
www.rife.org
www.rife.org
www.rife.org
www.rife.org

Chapter #3

Is it necessary to use a Ray tube to output the frequencies?

www.rifevideos.com

We really shouldn’t care if an instrument uses a ray tube or hand cylinders and footplates (commonly called pad instruments) as long as it will devitalize the microorganism we desire. In the next photo, shown below, we see one of the first pad instruments built by John Crane and John Marsh back in the late 1950's early 1960's. You can see the aluminum disks which were used to come in contact with the body and deliver the frequencies. In the strictest sense of the word just because a ray tube is used doesn’t mean its “Rife.” By the time you read this whole report you will find out that very few are doing exactly what Dr. Rife did. But does this mean that these instruments don’t work? Most of those who are building pad instruments are not using ray tubes, and most are not using Dr. Rife’s original frequencies. Those who are building ray tube instruments are also not using Dr. Rife’s original frequencies or methods. So where does this really leave us since very few are really doing what Dr. Rife did?


RYMI
MODEL 602
SERIAL 18
NEW DEVICE-FOR
INVESTIGATIONAL
USE ONLY
0
10
20
30
40
50
60
70
80
90
RANGE
POWER
FREQUENCY INSTRUMENT
RIFE VIRUS MICROSCOPE INSTITUTE
SAN DIEGO CALIFORNIA
www.rifevideos.com

www.rife.org

We have quite a paradox. This is the problem we face. If we were to build a ray tube Rife Machine that worked exactly the way Dr. Rife's did and use frequencies from 139,200 to 1,607,450 Hertz then we would have an instrument that could cause interference with AM radio stations if we were too close to them. These ray tube instruments may have to be used with a Faraday cage which is a conducting cage used to stop electromagnetic fields. We may be able to use them as long as we do not operate them within one half of a mile of a radio station on that stations particular wavelength or call number. We can build a pad instrument that will use all of the frequencies Dr. Rife's Machines used but then we are not using a ray tube. When we consider the problems we face today with building instruments, the least expensive instrument we can build is a pad instrument. This type of instrument can produce all of Dr. Rife's frequencies output by his Rife Machine. Therefore we should look at this method carefully and not reject it out of personal bias.

As we already said, it really shouldn't matter if an instrument uses pads or a ray tube as long as it works. With this in mind let's look at the reasons why pad instruments were built in the first place. John Crane and John Marsh had really good reasons why they built pad instruments. After nearly 50 years of research and use, there is enough evidence that a pad instrument may work just as well as a ray tube instrument, as long as there is sufficient power used. In some cases, because of the electrical stimulation like a T.E.N.S. instrument, they may work even better than a ray tube on some problems. We will now take a look at some of the reasons that prompted John Crane and John Marsh to use pads:

RIFE: *"But the principle of this thing is basically built on a coordinative vibration. Just like one tuning fork pitched to the C. Another one here—you strike this one and this one vibrates."*

DR. LARA: *"What kind of vibration is it? Electromagnetic vibration?"*

RIFE: *"We won't say magnetic, we will say electronic frequency vibration. The same as put out on a broadcasting station for the radio. The same thing you know, only it's transmitted into a tube. And the tube acts as a partial directional antenna you see."* (John Marsh Rife CDs - CD 6 track 2)

In the John Marsh papers describing his trip to Ohio we read a statement made by Dr. Rife:

RIFE: *"You know we had an idea when we had our Clinic in La Jolla, of course that was battery and motor generator operated that set, you know, and boy it would sure raise the devil with all the radios so we had a couple of cars that was equipped with car radios and we sent them out and we would take the switch of that thing, and had a code you know like an S.O.S., and one of them went up north, and one of them went south from La Jolla. Before we started in we wanted to see how far we were going to disturb things with it you know, and incidentally we had it in a steel room, a steel lined vault about this size at the old Ellen Scripp's home. It was the vault in the library of the Scripp's home where they kept their valuable manuscripts and books in all steel lined and a door on it like a safe. We had the thing inside of that too, but it didn't make much difference, but we started in, and one car lost the pick up on top of Torry Pines, and the other one half ways through Mission Beach picked it up, and then they could go a hundred feet and lose and then they would have to pick it up again. Old Henry [Henry Siner] the boy that was with us out there, one of the lab boys, boy he went up in the air. He says, "By God" he says "look, we're going to fix them up right. At two o'clock we'll hook this up to a big radio station, a big transmitting station, and at two o'clock next week we'll broadcast for tuberculosis, and at half past three the week after we will broadcast for cancer, and everybody at the radio will pick it up". See, boy I said Henry that really is an idea."* (1957 John Marsh Trip to Ohio Paper #24)

www.rife.org

In 1960 one of Dr. Rife's close friends, Ben Cullen, stated in a talk given at a Rife Virus Microscope Conference the following:

CULLEN: *"The fact is, had it not been for certain very, very unpleasant circumstances, Dr. Rife would've had an arrangement with KFI or KFSD* [Radio stations] *where he would have been broadcasting out over quite a large radius from each broadcasting station the rays which are responsible for eradicating these various viruses, which we now know as being "killing" viruses. Just imagine as you walked around shopping downtown, or out in the street, you would receive the rays of this wonderful current."* (Ben Cullen's 1960 talk given at the First International Convention of the Rife Virus Microscope #G)

These two statements made by Dr. Rife and Ben Cullen were made over 20 years after the 1934 clinic. Dr. Rife knew that the frequencies would broadcast from a metal antenna just as well as from a ray tube. The fact that he felt that Henry Siner's idea was a good idea and the fact that he wanted to use a radio station indicates that Dr. Rife knew a metal antenna would give the same results as a ray tube. It is apparent from what we have read that Dr. Rife believed it was the frequency that was devitalizing the organism and the method of application really didn't matter. Clearly, Dr. Rife understood that the frequencies could be broadcast by a radio station, using a metal antenna, if they had enough power.

When John Crane and John Marsh, Dr. Rife's two business partners in the 1950's, came to understand this, they eliminated the ray tube and used pads or hand cylinders to apply the frequencies. The pads and hand cylinders work just like an antenna except you do not want too much power so that they are safe to use. The body also becomes an antenna when you hold the hand cylinders or use the pads and this is why pad instruments work. Bertrand Comparet stated this in his interview:

COMPARET: *"Now, Crane said "Well now look, Rife himself admits that no matter how much tube and ray, and so on, you have, you can't get any results unless you've got the right frequency. Therefore the real clue to the thing is the frequency and not the means by which you deliver it." Comparet also said: "Well, Crane originally was, with more modern techniques, duplicating the Rife machine, tube and all for early experiments. And, as I say, he came to the conclusion that you just weren't getting anything additional by the use of the tube. If you didn't get the frequency, you could run the rest of it indefinitely and nothing happened. So, what Crane did, he got an audio frequency generator. Now, you could make them up yourself by an awful lot of work, or you could buy a Heathkit audio frequency generator and get all the same results with a lot less time and effort. So he was using these Heathkit generators. Now, instead of a beam projected from a tube, a ray, he simply had two wires. I think they were aluminium knobs on the end of them, which would be used. They would be put on the body in such a position that the natural flow of the current from one to the other would go through the diseased area, and he got astonishing results."* (1970's Bertrand Comparet Interview #33 & 47)

These pads or hand cylinders act just like an antenna when in contact with the body, but only if you have an RF carrier frequency. This is where John Crane and John Marsh made a critical error, we believe, and the reason Dr. Rife probably did not like their pad instrument. Without an RF carrier frequency the audio frequencies will only go through the connective tissue and not the cell. There are exceptions to this and they have to do with the wave form of the frequency. If a square wave audio frequency is used then the higher harmonics produced from this waveform may penetrate the cell to some degree. How much power from these harmonics penetrates the cell is not known. But this may explain why instruments that do not use an RF carrier frequency also seem to work well. Dr. Rife expressed his dislike for John Crane and John Marsh's instrument that did not use a carrier frequency when Bertrand Comparet asked him about it:

www.rife.org

COMPARET: *"And I asked Rife, because I thought Rife would certainly say that the way Crane was working on it then was still using the Rife principle, but he indignantly denied it.*" (1970's Comparet interview papers #32)

We know that Dr. Rife knew that a metal antenna would work and we also know that the pad instrument worked on this principle. Logically it must have been the fact that it did not use an RF carrier frequency is what upset Dr. Rife. Pad instruments that do not use a carrier frequency are limited in power. The highest power output that can be safely used from a non RF carrier pad instrument is about 1/5 of one watt (0.20 to 0.40). Any more power than this and the muscles of the body will begin to lock up. If you use an RF carrier frequency then you can output a hundred times more power safely. It is apparent that it was the lack of power that concerned Dr. Rife. All of Dr. Rife's original frequencies were in the RF (Radio frequency) broadcast band of frequencies and used with at least 40 to 50 watts of power. We will cover these frequencies and the audio frequencies along with the importance of a carrier frequency later in this article.

In the next photo, shown below, we see another pad type instrument built by John Crane back in the 1960's. You can see the same kind of disks that he used to come in contact with the body.



Some people have thought that it was the color of the light from the ray tube that made the Rife Machine work. But the evidence doesn't seem to support that concept either because in the Gonin Papers of John Marsh, Dr. Rife said this with regard to the light that came from the ray tube:

RIFE: *"We don't care about the color or anything of that sort."* (John Marsh Collection, Gonin Papers, Page 25)

Dr. Couche, while visiting Dr. Rife's lab with some other men, said:

DR. COUCHE: *"There was fifteen inches of concrete on the floor so as to stop any earthquake shocks from interfering with his work. And in his laboratory upon the ground floor he had a microscope with a slide on it that this group of people and myself looked at. And this was not stained, there was no killing*

www.rife.org

of the bacteria on it. It was just a fresh culture of the colon bacillus…..Well we all went down under the stairs into the cellar right immediately under the microscope upon the floor above us and the Rife machine was down in underneath there under the culture in the cellar probably I suppose about ten feet away, eight or ten feet away. And he turned the machine on and gave it less than a half minute's frequency for the colon bacillus...Then he turned the machine off and we all came upstairs and waited for ten or fifteen minutes. And presently he came back to his microscope and he said, "Well gentlemen come and look at the slide now." Well to my astonishment the bacilli all had been killed and they were all stacked up on the slide." (John Marsh Rife CDs - CD 3 track 1)

There is no possible way the light from the ray tube of the Rife Machine could have penetrated that fifteen inch concrete floor. It is obvious that the light didn't make any difference but that it was the frequencies that were broadcast through the ray tube. It is easy to see that there is more than one way to deliver the frequencies. The ray tube could be easily replaced with metal hand cylinders and foot pads. It is interesting to note here that Dr. Rife said Abrams' Oscilloclast would devitalize the BX cancer virus and it was a contact type device. The waveform the Oscilloclast produced is shown in Dr. Rife's 1936 film. John Crane and John Marsh probably used this contact method because of the success of Abrams' instrument. The Abrams' instrument proved that a contact type device would work and it was used before Dr. Rife even started using a ray tube. In fact Abrams' contact instrument predates all of Dr. Rife's work. Pad instruments like Abrams' instrument come in contact with the body. Abrams instrument worked on the same RF principles as Dr. Rife's instruments. Pad instruments with an RF carrier turn the body into an antenna and work on the same principle as a metal antenna or ray tube. People have been using pad instruments without an RF carrier for almost 50 years now and have had very good results. But, in order to work the way the ray tube instruments do, an RF carrier frequency is necessary.

Chapter Summary: Dr. Rife knew that a metal antenna could be used in place of a ray tube. Frequency generators that use hand cylinders or footpads or footplates may work as well as a ray tube instrument as long as sufficient power is used. The only way to increase the power level in a pad instrument is with the use of an RF (Radio Frequency) carrier. Dr. Rife did not approve of John Crane and John Marsh's pad instrument due to its lack of power and its lack of an RF carrier frequency. Unless you can have a frequency generator with sufficient power you are better off using a ray tube instrument with 40 to 250 watts of power output. If a person is dealing with a very serious condition they may want to use a ray tube instrument instead of a pad type instrument if they have access to one.

Many people have wondered if the frequencies that Dr. Rife used are safe. In the next chapter we will discuss the safety of these frequencies.

www.rife.org

Chapter #4

Are Dr. Rife’s RF frequencies safe to use?

Rife Ray #3 And Rife Ray #4 High Sine Wave RF Frequencies	
Actinomycosis (Streptothrix)	192,000 Hz
Anthrax	139,200 Hz
B. Coli (Rod form)	417,000 Hz
B. Coli (Filterable virus)	770,000 Hz
Bacillus X or BX (Cancer Carcinoma)	1,604,000 Hz
Bacillus Y or BY (Cancer Sarcoma)	1,530,000 Hz
Gonorrhea	233,000 Hz
Spinal Meningitis	427,000 Hz
Staphylococcus Pyogenes Aureus	478,000 Hz
Staphylococcus Pyogenes Albus	549,070 Hz
Streptococcus Pyogenes	720,000 Hz
Syphilis	789,000 Hz
Tetanus	234,000 Hz
Tuberculosis (Rod)	369,000 Hz
Tuberculosis (Virus)	769,000 Hz
Typhoid Fever (Rod)	760,000 Hz
Typhoid Fever (Virus)	1,445,000 Hz

Today there are many who profess to believe in Dr. Rife and his method of coordinative resonance using frequencies. But they also claim that RF or Radio frequencies are bad or harmful. Some of these people build and sell instruments that do not use any RF carrier frequency and put in their sales information that RF frequencies are harmful. This is a great disservice to Dr. Rife. The instruments they build use low audio frequencies like those used in the Rife Ray #5 or Beam Ray clinical Rife Machine and the 1953 AZ-58 instrument. But they ignoring the importance of the RF carrier frequency these machines used. (These low audio frequencies will be discussed later).

When it comes to Dr. Rife and the method he used in his Rife Machine you cannot “have your cake and eat it too.” Dr. Rife’s principles were all based on coordinative resonance from RF frequencies. Any method used that does not use RF frequencies cannot be called Dr. Rife’s method nor can it truly be called a "Rife Machine." Today, regardless of the method used, people call their instruments “Rife Machines” no matter how they are built. Dr. Rife specifically asked that his name not be put on any instrument, yet this is exactly what people do. There is nothing wrong with people building non RF instruments, but claiming that RF is bad or unsafe just to sell their instruments is where the problem lies. Dr. Rife’s Colin B. Kennedy equipment (which will be discussed later in detail) had a frequency range of about 12,000 Hertz to about 2,000,000 Hertz. With this equipment Dr. Rife found the many frequencies (shown above in the chart) that would eliminate or devitalize the various organisms he tested.

www.rife.org

Anyone who understands anything about frequencies knows that the frequencies in that chart are all RF or radio frequencies. It is impossible to build an instrument that could output these frequencies of Dr. Rife's without it using RF frequencies. Every one of Dr. Rife's instruments from the Rife Ray #1 to the Rife Ray #5 used RF frequencies. This is a fact of history and it cannot be changed. Yet there are some who are so foolish as to state that RF instruments such as Dr. Rife's instruments are "Dangerous Rife Machines." It is hard to believe that this is being said by some who claim to be selling "Rife Machines." It is obvious that they know very little about Dr. Rife and his methods. All of the frequencies that Dr. Rife used were in the AM radio band of frequencies. If they were dangerous then we would not have any AM radio stations on the air today. AM radio stations have been around for almost 100 years. If these frequencies were dangerous then people would have been falling dead all over the place for the last 100 years. This is how foolish the idea is that Dr. Rife's RF frequencies and instruments were dangerous.

Another foolish statement that some have made is that these instruments include frequencies in the "Microwave band." The AM radio band is not in the Microwave band. Dr. Rife's Rife Ray #4 had a frequency range that went as high as 22.5 Megahertz (22,500,000 Hertz or 22.5 million Hertz). The microwave band begins at about 300 Megahertz (300,000,000 Hertz) and goes to about 3 Gigahertz. None of Dr. Rife's machines were ever in the microwave band of frequencies. It is clear that people who have written this false information clearly know nothing about Dr. Rife or his equipment. In this report we have no ax to grind other than to point out how foolish some of the false information that is being written by those who claim to know a great deal about Dr. Rife. There is a lot of nonsense being written by some people in order to try and sell some kind of so called "Rife Machine”.

In Dr. Rife’s tests he would have naturally started in the low frequency range and slowly worked his way higher until he found a frequency that would eliminate the organism. All of the frequencies that he found were in the RF range. They went from 139,200 Hertz for Anthrax to 1,604,000 Hertz for the BX cancer virus (Frequency range taken from the Rife Ray #4 documents). It was only these frequencies that Dr. Rife found that would resonate the organisms and devitalize them. Since Dr. Rife found that only these RF frequencies would resonate and kill the organism then it is impossible to separate RF from coordinative resonance. It would also be impossible to build an instrument that truly worked on Dr. Rife’s principles without the use of RF or radio frequencies. In order to prove the safety of Dr. Rife’s work we must quote him since he is the person who used these frequencies for over 30 years in his laboratory. Below are two of his quotes on the safety of using RF frequencies in the range and power level that he used in his Rife Machines. The first quote comes from a letter sent to Dr. Stein in 1956:

RIFE: *“I have operated the frequency instrument since 1921. I have watched it advance in style and performance with the advancement of electronics. In the many years I have used this equipment in my research, I have never suffered an injury or any ill effects whatsoever. I found it reliable in performance and efficient in results.”* (Letter from Dr. Rife to Dr. Justin Stein, July 2, 1956)

On the John Marsh, Rife audio CDs Dr. Rife also made this statement about his RF frequency instrument:

RIFE: *“I stood in front of that thing for thirty years finding these different frequencies that devitalize these different bacteria. And that thing [RF ray tube] was shooting on me right here [his chest], but it is absolutely harmless to normal tissue and each individual bacteria requiring a different frequency to devitalize.”* (John Marsh Rife CDs)

Dr. Milbank Johnson, M.D. also used the RF Rife Machine for many years and conducted clinics and found the instrument safe to use. Dr. James B. Couche, M.D. used the instrument in his private practice for over 22 years and also said he found the instrument safe to use. Dr. Tully, D.D.S. pur-

www.rife.org

chased one of Dr. Couche’s instruments and used it for several years and found it completely safe to use. Dr. Robert P. Stafford, M.D. used the frequency instrument for over 5 years and also expressed that he found the instrument completely safe to use. These statements along with Dr. Rife’s that we quoted above show that Dr. Rife found that his RF frequencies, in the ranges he used, were as safe to use as the frequencies output by any radio station. These frequencies are broadcast through the air day and night passing through our homes without any harm to the human body. There may be some people with RF sensitivity but this does not mean that RF is unsafe to use. This only means that these people are sensitive to RF and should avoid it if they find a problem using it.

Chapter Summary: An instrument that does not output Dr. Rife's RF frequencies is not a "Rife Machine" in the strictest sense of the word. Neither can they resonate the microorganisms that Dr. Rife proved could be devitalized with his RF frequencies. None of Dr. Rife's RF instruments ever put out frequencies in the "Microwave band" of frequencies. Dr. Rife found that his frequencies and the power levels he used in his instruments were safe to use. Non RF frequency generators appear to be very good instruments and help may people but they do not work on the same methods and principles that Dr. Rife used.

Many people have wondered if Dr. Rife ever used audio frequencies. In the next chapter we will discuss whether Dr. Rife ever used audio frequencies with his equipment.

www.rife.org

Chapter #5

Did Dr. Rife use audio frequencies?



In Dr. Rife’s 1961 deposition he revealed the fact that he was using some form of audio modulation from the beginning of his work with frequency instruments:

RIFE: *“Initially I worked with loose couplers to get an audio oscillation and then with the use of transmitters, I tried to balance the audio and modulate the audio on a carrier wave to transmit the audio energy.”* (Dr. Rife’s 1961 Deposition, answers page 5)

Dr. Rife stated that at the beginning of his work, back in the 1920's when loose couplers were used in generating frequencies, he was using audio modulation with an RF or radio frequency carrier. Above is a photo of a loose coupler courtesy of "Henry Rogers, Western Historic Radio Museum" (www.radioblvd.com). These loose couplers worked by moving one coil inside the other in order to change the frequencies.

In Dr. Rife’s Rife Ray #3 and Rife Ray #4 Rife Machines he used a specific audio circuit which gated or pulsed his frequencies. This circuit modulated a fixed audio frequency with all of his high frequencies which he used on the various organisms. This circuit will be discussed later when we discuss these Rife Machines.

It is apparent that Dr. Rife first tested audio frequencies on organisms in his search for the frequency which would devitalize them. The audio range would be the logical place to start. If he couldn’t find a frequency in the audio range, he then moved up into higher frequency ranges until he found a frequency that would devitalize an organism. In Dr. Rife’s early lab notes, he listed only two organisms that had an audio frequency M.O.R. Later when Dr. Rife found out that he was reading his frequencies incorrectly, one of those audio frequencies was changed to a much higher RF frequency. There are other statements made by Dr. Rife which show that he tested the audio range. In fact Dr. Rife gave the full range of his frequencies:

www.rife.org

RIFE: *"Some of them are in the visible band, or I mean not only the visible band but, uh, band of frequencies audible to the human ear [audio frequencies are frequencies that you can hear as tones]. Some of them are way beyond either way. They run through a very, very large gamut. Some of them are very, very broad, long. Some of them are...not extremely short. There are none of them what we call our ultra short wave that I have found yet. Well there's many of them...we would, uh, classify in the ultrasonic band because they're not visible* [sic] *with the human ear. They're way beyond you know. And some of them are even in the broadcast band. Your cancer is very high* [1,604,000 Hertz]. *You can't hear it, the oscillation. But now you take your T.B.* [Tuberculosis Rod 369,000 Hertz & Virus 769,000 Hertz]. *Now that's down. A little more you see...if you don't have an absolute coordinative resonance, you have nothing. One tenth of one meter off and you have nothing. Its got to be absolutely correct for that individual organism. It's got to be precise...the virus of cancer has a certain frequency. And it has to be there, otherwise if it's a little one way or the other, no good, no good for nothing. Infrared will penetrate, yes, but the heat is not the thing because the heat is not the frequency, it's [Infrared] way down in the very low band of frequencies and the laboratory rate of the BX is up into the high band."* (John Marsh Rife CDs - CD 5 track 2, CD 6 track 2, CD 7 track 1 and CD 9 track 1)

In these statements Dr. Rife clearly explains the broad range of his frequencies. Some were audio and could be heard by the human ear; others were in the ultrasonic range, and some were even in the broadcast band. Cancer he said was very high. He states the frequencies have to be very accurate to work. One tenth of one meter off and they would not work at all. We will talk about this later. Here are two additional statements that also verify that Dr. Rife's Machine's could output a modulated audio frequency:

RIFE: *"You know we had an idea when we had our* [1934] *Clinic in La Jolla, of course that was battery and motor generator operated that set, you know, and boy it would sure raise the devil with all the radios so we had a couple of cars that was equipped with car radios and we sent them out and we would take the switch of that thing, and had a code you know like an S.O.S., and one of them went up north, and one of them went south from La Jolla. Before we started in we wanted to see how far we were going to disturb things"* (John Marsh Collection, Trip to Ohio Papers, #24)

In the next photo, shown below, is the Rife Ray #3 which was used at the 1934 Clinic in La Jolla.



www.rifevideos.com

In order to be able to put out an S.O.S. type signal he would have had to modulate the audio frequency onto a carrier in order for the car radios to pick up the signal. On the John Marsh Collection of Dr. Rife's audio CD's, Dr. Couche makes an interesting comment about the Rife Ray #3 instrument. He was present at the 1934 clinic sponsored by Dr. Johnson and the University of Southern California. He stated:

DR. COUCHE: *"They gave him a treatment of the Rife frequencies which are in the auditory band."* (John Marsh Rife CD's - CD 3 track 1)

The cancer frequency (Rife Ray #4 1,604,000 Hertz and 1,607,450 for the Rife Ray #5) and tuberculosis (Rife Ray #4 Rod form 369,000 Hertz and 369,433 for the Rife Ray #5)(Rife Ray #4 and Rife Ray #5 Virus form 769,000 Hertz) frequencies used in the 1934 clinic were not audio frequencies. Why would Dr. Couche make this statement? The evidence shows that Dr. Couche was getting the Rife Ray #4 and the Rife Ray #5 methods of generating the frequencies mixed up. The Rife Ray #5 or Beam Ray Clinical Rife Machine which Dr. Couche used for over 22 years used audio frequencies to create the proper sideband spacing to hit the high harmonic RF M.O.R. frequency (Mortal Oscillatory Rate or the frequency that will kill or devitalize an organism). Dr. Couche purchased two of these clinical Rife Machines and used them until 1952 when he retired. We will cover this instrument later in this paper. All the evidence that we have acquired from the quotes show that the Rife Machines from 1934 and earlier could output audio frequencies above 12,000 Hertz and that Dr. Rife tested audio frequencies right from the beginning of his work in 1920.

Although we have been able to prove that Dr. Rife tested the audio range of frequencies, as any good scientist would have done, it should be pointed out that by 1935 when the Rife Ray #4 Rife Machine was built, he no longer felt that he needed to test audio frequencies any longer. This is indicated by the fact that no variable audio oscillator was included in this new Rife Ray #4 frequency instrument. The Rife Ray #4 Rife Machine will be discussed later in this article.

In 1936 Dr. Rife's engineer, Philip Hoyland, developed a new machine which used audio frequencies to create Dr. Rife's high RF frequencies through harmonic sidebands. The audio frequencies were not the frequencies that would devitalize or kill the various microorganisms. These audio frequencies were used to produce the frequencies that would devitalize or eliminate the disease organisms. This method of using harmonic sidebands will be discussed later in this report when we examine the Rife Ray #5 or Beam Ray Clinical instrument.

Chapter Summary: Dr. Rife tested and use audio frequencies in his instruments. Primarily the audio frequency was modulated onto the high RF frequency to create a pulse in the higher RF or radio frequencies he was using to devitalize the various microorganisms. When his engineer, Philip Hoyland, developed the new Rife Ray #5 or Beam Ray Clinical instrument the audio frequencies were used to produce Dr. Rife's High RF frequencies through harmonic sidebands.

In the next chapter we will look at Dr. Rife's first frequency instrument called the Rife Ray #1 and how he was able to devitalize his first microorganism using it.

www.rife.org

Chapter #6

Dr. Rife’s 1920 to 1922 Rife Ray #1 Rife Machine



1. Used a Ray tube.
2. Frequency range was probably about 1 MHz or less using loose couplers: Could modulate audio frequencies.
3. Output to the Ray tube was 8 to 10 watts.

From information taken from many different documented sources there is finally enough information to know what Dr. Rife did in the early years, from 1920 to about 1934. Dr. Rife designated his machines in numerical order beginning with the Rife Ray #1. Even though we do not have any photos of his Rife Ray #1, we know that Dr. Rife was using loose couplers (photo shown above is a loose coupler) because of this statement:

RIFE: *“Initially I worked with loose couplers to get an audio oscillation and then with the use of transmitters, I tried to balance the audio and modulate the audio on a carrier wave to transmit the audio energy.”* (Dr. Rife’s 1961 Deposition, question and answer #35)

In a paper that was written in the 1930's, probably by Jack Free, one of Dr. Rife’s lab assistants, we get a history of Dr. Rife’s machines. This paper starts with the Rife Ray #1.

“In January 1920 experiments were started at the Rife Research Laboratory by Commander Royal R. Rife U.S.N. Ret. to determine the effect of electrical influences upon pathogenic microorganisms. Tests were made for anode and cathode polarity influences and the effect of infrared, ultraviolet and X-ray. During these experiments the idea was conceived of the possibility of devitalizing the pathogenic micro-organisms by electrical frequencies of varying wavelengths. The initial apparatus [Rife Ray #1] *for the tests along this line of experiments was constructed and used in prolonged experiments during 1921 and 1922, with results that warranted the belief that the principles involved contained possibilities.”* (Development of The Rife Ray and use in devitalizing of pathogenic microorganisms).

www.rife.org

The tests that were done with the Rife Ray #1 which showed that it was possible to devitalize micro-organisms with frequencies was talked about in a 1938 Evening Tribune newspaper article. Also in this newspaper article we learn the power output of the Rife Ray #1 and the first organism that he was able to devitalize.

“Rife built a simple frequency generating apparatus of about 8 or 10 watts output. He grew some cultures of bacteria. Then he began the studies whose reported results now promise to revolutionize the entire theory and the whole treatment of the human diseases, other than those of a functional or accidental nature. Machine and cultures ready, the San Diegan anxiously, feverishly began testing his idea. Would those minute killers of men die under the frequency bombardment? It would be a patience-wracking task, for there was no way to measure what wave length or frequencies the organism might have. In the quiet loneliness of the laboratory, Rife simply had to turn and turn and turn the tuning dials of his machine and check after each bombardment the conditions of the disease organisms in his cultures to see if anything had happened to them. He just had to hunt by trial and error a frequency, which might do something to a certain organism. Then, if he found one for that disease, he would have to start all over again on the next kind.

The scientist took first a culture of b. coli, the organisms, which always seem to accompany the agency of typhoid fever yet apparently, are harmless themselves. He prepared microscope slides from the culture and saw that his little subjects were alive. Then he turned the ray on them, tuned it to a certain frequency, then took the slide back to the microscope to see if anything had happened. He did this time after time and the b. coli still remained discouragingly healthy. Then one day, Rife recounted, a culture of the organisms which had been bombarded with a certain frequency [417,000 Hertz] *appeared different under the microscope. They seemed lifeless! He tried to get them to grow, to reproduce in their laboratory media. He tried that same frequency on culture after culture of b. coli and always the results were the same. The organisms were dead. "It did kill them!" Rife told himself. And probably, cool, conservative scientists though he is, he allowed himself to hope that he, Royal Raymond Rife, had found that 'bullet" which scientist have sought for years, that "magic bullet' which would surely, certainly slay mankind's diseases.”* (Dread Disease Germs Destroyed By Rays, Claim Of S.D. Scientist-Cancer Blow Seen After 18-year Toil by Rife, The Evening Tribune, May 6, 1938)

These few statements that we have just read give us all that is really known about the Rife Ray #1. The most important development that was accomplished with the Rife Ray #1 was Dr. Rife was able to test and prove that microorganisms could be killed or devitalized using RF frequencies pulsed with an audio frequency.

The photo, shown below, is a picture of a more complex loose coupler setup.



www.rife.org

By 1923 Dr. Rife assembled his next Rife Machine called the Rife Ray #2 using off-the-shelf frequency generators. The same equipment that was used with the Rife Ray #2 was also used with the Rife Ray #3. The changes made to the Rife Ray #2 to create the Rife Ray #3 appear to be mostly an increase in the power output of the instrument through the ray tube. Since the full details of the changes are not known and the same equipment that was used with the Rife Ray #2 was used with the Rife Ray #3 we will look at the Rife Ray #3 in the next chapter.

Chapter Summary: The Rife Ray #1 was a simple frequency generating device built to determine if microorganisms could be devitalize by frequencies. The instrument was built using loose couplers which when moved in and out of the coil would produce different electrical RF frequencies. Dr. Rife modulated an audio frequency on the RF frequency he was using in order to produce a pulsed waveform. With this simple frequency generator he was able to devitalize his first organism which was B. coli. Dr. Rife after proving his theory went on to build more powerful equipment which we will look at in succeeding chapters in this report.

In the next chapter we will look discuss Dr. Rife's Rife Ray #3 instrument which was used in the 1934 cancer and tuberculosis clinic which Dr. Milbank Johnson conducted.

www.rife.org

Chapter #7

1934 Rife Ray #3 Rife Machine used in the 1934 clinic



1. This was a regenerative instrument that used a ray tube.
2. It consisted of two Kennedy Regenerative Receivers (the model numbers were the 110 and 281). These two receivers made it possible to have a combination of one low frequency oscillator and one high frequency oscillator or two high frequency oscillators.
3. The output was sine wave.
4. Power usage was from batteries. Output to the ray tube was about 50 RF watts?

This instrument was described in a document believed to have been written by Jack Free one of Dr. Rife's lab assistance. We will quote the portion of that document that pertains to this instrument:

"In 1923 more appropriate apparatus [Rife Ray #2 when improved became the Rife Ray #3] *was assembled and used. The different frequencies were generated by a tube oscillator with many stages of amplification, the final stage being a 50 watt Telefunken tube.*

This amplified frequency was in turn fed into an output tube, and as the voltage at this point was quite small, it was found necessary to apply external voltage across the anode and the cathode of the output tube [ray tube] *to act as a carrier wave for the frequencies that were generated in the apparatus.*

The output tube was constructed with a double expansion bulb, blown from quartz, using platinum anode and cathode it having a 45° target for directional effect. No heat is generated in output tube-

www.rife.org
www.rifevideos.com

temperature constant. The frequency control of the instrument was exact to a fraction of a wavelength making it possible to coordinate the frequency in each pathogenic micro-organism with its own wavelength of frequency delivered from the instrument. The current supply for the whole apparatus was supplied by batteries and generators.

During the next eight years these experiments continued and with the aid of the Rife super microscope and the frequency instruments the coordinating frequencies (termed mortal oscillatory rate MOR) of most of the pathogenic micro-organisms were found and recorded including the frequencies of many of the virus or filter passing forms of these organisms." (Development of the Rife Ray and use in devitalizing of pathogenic micro-organisms).

Dr. Rife was asked by Dr. Milbank Johnson M.D. to write a description of his Rife Ray #3 instrument in 1935. Dr. Rife had Jack Free, his lab assistant; include this description in a letter that Jack Free wrote to Dr. Milbank Johnson. Below is Dr. Rife's description.

RIFE: *"The basic principle of this devise is the control of a desired frequency. These frequencies varying upon the organisms being treated.*

The frequency is set which controls the initial oscillator, which in turn is run thru six stages of amplification, the last stage driving a 50 watt output tube.

The frequency with its carrier wave is transmitted into an output tube [double-bubble ray tube] *similar to the standard X-ray tube, but filled with a different inert gas. This tube acts as a directional antenna.*

The importance in the variable control of these frequencies is that each pathogenic organism being treated is of a different chemical consistency, the consequence being they carry a different molecular vibratory rate. Each one in turn under these conditions requires a different frequency or vibratory rate to destroy." (Letter from Jack Free to Dr. Milbank Johnson M.D., December 17, 1935).

This Rife Machine was used in the 1934 clinic by Dr. Milbank Johnson. See photo of Rife Ray #3 on page 26. If you look at the bottom of that photo of the Rife ray #3 you can see part of the bed railing and mattress where they treated the patients. If you look at the table you can see that the instrument was not a one piece instrument but had many components. This Rife Machine has always been considered the best instrument used by Dr. Rife because it produced the results of the 1934 cancer and tuberculosis clinic. Those interested in the work of Dr. Rife have always wanted to know how this instrument worked. They have also wondered what equipment he used. This has been one of the biggest Rife mysteries. There have been all kinds of speculation on how his first instrument worked. What was its waveform? What was the frequency range? Could it generate audio frequencies? Was it super-regenerative (as he wrote on his lab notes), or was it just regenerative? All of these things have remained mysteries for over fifty years. It was generally believed that the 1934 instrument was custom made for Dr. Rife. However, if the equipment had not been custom made, the mystery could be solved. And today, thanks to some great detective work done by Mr. Peters, the mystery, in fact, is now solved. The instruments were not custom made. They were standard off-the-shelf frequency generating equipment that Dr. Rife purchased. The equipment and frequency ranges are now known.

A better photo of the equipment Dr. Rife used is the first photo on the next page. It was when Mr. Peters was looking at this photo that he recognized the Kennedy frequency generating equipment. Dr. Rife most likely stacked it all up on a table and took a picture of it after he started to use the newer equipment built for him in 1935. This photo, amongst others, made it possible to figure out the equipment Dr. Rife used. This photo has been provided courtesy of Jason Ringas of Rife Research Group of Canada. Here in this paper you will be able to see the actual equipment along with the selling advertisements of the 1920's that give the specifications of the equipment.

www.rife.org

We will now look at each piece of equipment and take an in-depth look at the specifications of each. All pieces of equipment except the ray tubes and possibly the five stage amplifier were considered off-the-shelf equipment. This means that this was standard frequency generation equipment which could be purchased from companies in the 1920's. Although they are regenerative receivers, they could output whatever frequency Dr. Rife wanted to use when the regenerative circuit was turned up. Dr. Rife used top-of-the-line Kennedy equipment from the Colin B. Kennedy Company, which built some of the most accurate, high quality equipment that could be purchased in 1923. It was also some of the most expensive equipment to purchase.



We will now take a look at the next photo, shown below. This photo is one of several pictures of Dr. Rife's laboratory instruments. The bottom two pieces of radio equipment were the Kennedy Receiver Model 110 connected to the Kennedy Two-Stage Audio Amplifier Model 525. The other piece of equipment sitting on top of the Kennedy Receiver Model 110 we will look at later. On the next page are two more photos. The first photo is a better photo of this old antique equipment. The second photo is the 1923 advertisement from the Colin B. Kennedy Company which provides the frequency range and features of this regenerative receiver. It also gives the effective frequency range from 175 to 25,000 meters or from 12,000 Hertz to 1,700,000 Hertz.



www.rife.org


TYPE 110
UNIVERSAL RECEIVER
SERIAL No.
COUPLING
ANTENNA
GROUND
FILAMENT
GRID CONDENSER
REGENERATION
TELEPHONES
PRIMARY INDUCTANCE
SECONDARY INDUCTANCE
CONDENSER
PRI. CONDENSER
SER.
PAR.
FIL. BAT.
PLATE BAT.
THE COLIN B. KENNEDY CO.
SAN FRANCISCO
SAINT LOUIS
INPUT
OUTPUT



KENNEDY
EQUIPMENT

ANNOUNCING

THE NEW KENNEDY UNIVERSAL REGENERATIVE RECEIVER

TYPE 110

EFFECTIVE RANGE: 175 TO 25,000 METERS

DETECTS
REGENERATES
OSCILLATES
On all wave
lengths in
common use.

Licensed
under
Armstrong
U. S.
Patent
No. 1,113,149

Surpassing even our highest hopes when we undertook its development, this latest addition to the Kennedy line is of interest **to everyone who uses a radio receiving set.**

Our engineering staff spent many months in developing this unit and released it for production only when its performance surpassed every requirement we had set for it. By our long specialization in receiving equipment we have built up a reputation which is so precious that we can afford to put the Kennedy trade-mark on only the highest quality product.

We have spared no effort to make this the best receiver on the market. We honestly believe that it is.

These are some of its features:

Variable inductive coupling between primary and secondary.
Extremely sharp tuning because of very efficient inductance units.
Special Kennedy bank-wound moisture-proof inductors.
Generous overlap between inductance steps.
Large balanced primary and secondary variable condensers.
Micrometer adjustment of secondary condenser
Variable grid condenser with air dielectric, permitting most effective use of all types of available receiving tubes.
Adjustable feed-back circuit.
Fine adjustment of plate voltage by means of potentiometer connected between terminals of filament battery.
Weston ammeter for measuring filament current.
Bus-bar type insulated wiring.

Further details in Bulletin 101, mailed on request.

Ask your dealer for a demonstration. Compare the performance of this receiver with any other you have ever seen. The users of Kennedy Equipment are our best advertisers.

THE COLIN B. KENNEDY COMPANY
INCORPORATED
RIALTO BUILDING SAN FRANCISCO

ALWAYS MENTION Q S T WHEN WRITING TO ADVERTISERS 83

www.rifevideos.com

The Kennedy Model 110 could actually go from 12,000 Hertz to about 1,800,000 Hertz. The Kennedy Company was just being conservative in its advertisement. The next instrument that was on top of the Receiver Model 110 in Dr. Rife's laboratory photo is the Kennedy Short-Wave Regenerative Receiver Model 281. Below is a photo of the Kennedy Receiver Model 281. Below the 281 is a picture of the 1923 Kennedy 281 advertisement.





KENNEDY EQUIPMENT

Our new improved Type 281

SHORT-WAVE REGENERATIVE RECEIVER

Licensed under Armstrong U. S. Pat. No. 1,113,149

is designed for high efficiency on wave lengths of 185 to 620 meters. The ideal set for relay work. It embodies all the features of correct design and superior workmanship that have established the reputation of Kennedy Equipment.

You will be interested in the details of this new short wave set. Ask your dealer about it. If he cannot supply you we will send you Bulletin 201 on request.

The high quality of Kennedy apparatus is being appreciated by those who want the best results. *We again find it necessary to greatly increase our factory capacity to meet the demand.*

THE COLIN B. KENNEDY COMPANY
INCORPORATED
RIALTO BUILDING SAN FRANCISCO

This Kennedy 281 instrument had an effective range from 185 meters to 620 meters or from 483,000 Hertz to 1,620,000 Hertz. This instrument could actually go to about 1,800,000 Hertz. The Kennedy Company again being conservative on its frequency range.

www.rife.org
www.rifevideos.com

Above in the original lab photo which showed all of Dr. Rife's equipment stacked up on a table we see another Kennedy Regenerative Receiver, this being the Kennedy Model 220. The first photo, shown below, is a photo of this instrument. Its effective frequency range was from 175 meters to 3250 meters or from 92,000 Hertz to 1,700,000 Hertz. It could also go to about 1,800,000 Hertz. All three models of this Kennedy equipment could go higher in frequency than the advertisements state. Below the Kennedy Model 220 photo we see the 1923 advertisement for the Kennedy 220 instrument.


KENNEDY EQUIPMENT
TYPE 220 INTERMEDIATE WAVE RECEIVER SERIAL No 5324
THE COLIN B. KENNEDY CO. SAN FRANCISCO SAINT LOUIS
COUPLING
REGENERATION
ANT.
SER.
PAR.
PHONES
GND.
PRIMARY
SECONDARY
INCREASE
SEC. COND.
PRI. COND.
FILAMENT
FIL. BAT. +
PLATE BAT. +



Announcing

the new

KENNEDY

Intermediate-Wave Regenerative Receiver

Type 220

Range 175 to 3250 Meters

We believe there is no other receiver on the market which represents so much **concentrated quality value.**

See it at your dealer's. Examine it thoroughly, have a demonstration and form your own opinion. We don't ask you to accept ours.

Licensed under Armstrong
U. S. Patent No. 1,113,149

Bulletin 201, giving full details mailed on request

Ask Your Dealer

THE COLIN B. KENNEDY COMPANY
INCORPORATED
RIALTO BUILDING SAN FRANCISCO

www.rife.org
www.rifevideos.com

Now that we have all the frequency generating equipment identified we can now come to some conclusions. All of this Kennedy equipment was sine wave. Square wave was not used or even generated in this old equipment. The Kennedy Receiver Model 110 had a frequency range from 12,000 to about 1,800,000 Hertz. This shows that Dr. Rife's instruments had the ability to output audio frequencies, a fact that he mentioned in his 1961 deposition. The only audio frequencies he could have used would have been modulated from this equipment. Dr. Rife also mentioned in his 1961 deposition that he balanced the audio on a carrier which would have been a modulated waveform.

What is really surprising is the fact that none of the Kennedy equipment that Dr. Rife used could output a frequency higher than about 2 Megahertz (MHz). This fact changes a lot of things with regard to his lab notes dated before 1934. It was impossible for him to produce 11,780,000 Hertz or 17,033,000 Hertz using this equipment. These are the two frequencies that Dr. Rife listed on his lab notes for the BX cancer virus. The frequency range of the Kennedy equipment now explains why Dr. Rife's Engineer, Philip Hoyland, told Mr. Edwards, a business partner in Beam Ray Corporation, that Dr. Rife and not taken some factors into consideration when he read his frequencies prior to 1935. What this implies is that Dr. Rife may have misread his frequencies prior to 1935.

With Dr. Rife's approval, Philip Hoyland was hired by Dr. Milbank Johnson, M.D. and the University of Southern California Special Medical Research Committee in 1935 to build a more up-to-date portable frequency instrument to be used for their research. Dr. Rife's 1934 instrument was cumbersome because it was not just one, but several, pieces of equipment which were difficult to move and use. In order to build the new instrument, Philip Hoyland needed to know what frequencies Dr. Rife was using.

This is where the story gets interesting. Dr. Rife had many lab notes which had the frequencies written down on them for the various microorganisms. Dr. Rife could have just given Philip Hoyland a copy of the frequency ranges that the lab notes covered and he could have built the instrument from that information. But this is not what happened. Philip Hoyland brought his standard master oscillator into the laboratory and then Dr. Rife and Philip Hoyland went through the long process of putting many organisms under the microscope and checking to see what the frequency was when it was devitalized. If Dr. Rife had been confident that his original frequencies were correct on his lab notes this testing would not have been necessary. It is apparent that there were probably some questions in Dr. Rife's mind about the accuracy of his initial readings and frequencies which made this retesting of the organisms M.O.R. frequencies necessary.

Keeping this in mind, it was difficult to read the correct frequencies prior to this time unless you were very proficient at doing it. Philip Hoyland apparently wanted to know exactly what frequencies Dr. Rife was using in order to build the new instrument. While testifying on the stand in the 1939 Beam Ray trial, Philip Hoyland stated this about how he obtained the frequencies: (1939 Beam Ray Trial Transcript #778)

HOYLAND: *"They were taken off the last machine* [the Kennedy equipment] *that was built by Dr. Rife. I transferred them from one machine to another."*

At another point during the trial the transcript reads as follows. (#905-916):

COMPARET: *"In June of 1935 was when you made an agreement with the* [transcript missing words] *medical research to build a Rife Ray machine,* [the Rife Ray #4] *you did build it soon after that?"*

HOYLAND: *"Yes."*

www.rife.org

www.rife.org

COMPARET: *"You had an agreement with them that all work was to be done under Dr. Rife's direction?"*

HOYLAND: *"That's what the contract called for."*

COMPARET: *"Did you do this work without getting the frequencies from Dr. Rife?"*

HOYLAND: *"I recalibrated the machine according to the bacteria."*

COMPARET: *"What specifically did you do that constituted this recalibration?"*

HOYLAND: *"I used a standard oscillator against his machine to see what frequencies he was using."*

COMPARET: *"He set his machine and you measured his frequencies?"*

HOYLAND: *"Yes."*

COMPARET: *"Did you make any memorandum of these particular frequencies?"*

HOYLAND: *"Yes, I gave Dr. Johnson and Dr. Rife a list of them."*

Later during the trial Dr. Rife was asked where the frequencies came from. (#1290-1293):

JUDGE KELLY: *"When you constructed this Beam Ray machine* [from Kennedy equipment] *you had a dial representing the frequencies or harmonics?"*

RIFE: *"We had many dials on the original machine* [Kennedy Model 110]."

JUDGE KELLY: *"Is that the machine Mr. Hoyland got the frequencies from?"*

RIFE: *"Yes, he took them off that old machine* [Kennedy Model 110]*."*

From the court testimony given by Dr. Rife and Philip Hoyland we see the frequencies were read by Philip Hoyland off of the Rife Ray #3 or Kennedy Model 110 and 281 and used in the next instrument which was the Rife Ray #4 (We will be discussing this instrument next). Now let's continue on reading the court testimony: (Beam Ray Trial Transcript #1553-1555)

COMPARET: *"Now going back to your assumption that Dr. Rife knew the frequencies, had Mr. Hoyland ever told you that Dr. Rife knew them?"*

EDWARDS: *"No, he told me that Dr. Rife only thought he had them."*

COMPARET: *"What did you think that meant?"*

EDWARDS: *"Well, Mr. Hoyland told me about that time* [1934 and before], *that Dr. Rife measured the frequencies only by the length of the wire and that he did not take other factors into consideration."*

Here in the court testimony we just read that Dr. Rife had not read his frequencies correctly when he measured them. This would have been a mistake easy to make in the 1920's and 1930's. The frequencies which Philip Hoyland read off of Dr. Rife's #3 instrument, which consisted of the Kennedy equipment, were different from the earlier lab note frequencies recorded by Dr. Rife. This has caused a lot of confusion because the frequencies that Philip Hoyland read were all lower than 2,000,000 Hertz.

Dr. Rife had written down on his lab notes frequencies as high as 11,780,000 and 17,033,000 Hertz for the BX cancer virus. However, the Kennedy Models 110, 220 and 281 could not output these high frequencies. It is apparent that Philip Hoyland was absolutely correct when he told Mr. Edwards that Dr. Rife had misread his frequencies. Also, Philip Hoyland testified in court that he gave both Dr. Rife and Dr. Johnson a list of the correct frequencies he read off of the Kennedy Model 110. This verifies the truth of what Philip Hoyland said in court.

There is another verification that Dr. Rife had misread his frequencies. On the Rife audio CD's, Henry Siner, Dr. Rife's lab assistant, read from a lab note of the BX cancer virus. All the information was the same as Dr. Rife's earlier pre-1935 lab notes except the frequencies. On that corrected lab note Henry Siner read 187 meters for the wave length and 1,604,000 Hertz for the cycles per second frequency for the BX cancer virus. Both the meter frequency and the cycles per second measurement being the same frequency. However, on the pre-1935 lab note, both were different. One frequency was 11,780,000 and the other was 17.6 meters or 17,033,000 Hertz. Henry Siners reading of this corrected lab note also verifies that Dr. Rife had not read his frequencies correctly. At the end of that discussion about the BX cancer virus and the Lab note Henry Siner made this statement, quote:

SINER: *"That was a long time ago, but, and remember, I was just copying what he* [Dr. Rife] *dictated."* (John Marsh Rife CD's - MP3 track 11).

This quote from Henry Siner shows that it was Dr. Rife who made the corrections to the lab note. The frequency of 1,604,000 Hertz was the frequency Philip Hoyland read and gave to Dr. Rife and Dr. Johnson and it was used in the new instrument built in 1935 called the Rife Ray #4.

There is one thing we need to consider. Dr. Rife could have read a harmonic of the frequency instead of the correct frequency. It appears this is in fact what Dr. Rife did. Dr. Rife understood how easy it was to read a harmonic frequency instead of the correct frequency and recognized that he may not have had true fundamental frequencies. He stated:

RIFE: *"I've talked to you* [John Crane] *and Verne* [Verne Thompson] *and other people too that there may be some of the frequencies that we are using that may be harmonics, you know...It's not an impossibility that some of those frequencies may be a harmonic. We may not know the true frequencies of some of them. But it does the business. Maybe if we had the true frequency it would do it better because it has more power than a harmonic."* (John Marsh Rife CD's - CD 7 track 2).

The frequency that Philip Hoyland read off of Dr. Rife's 1934 Rife Ray #3 Machine was 1,604,000 Hertz. Dr. Rife had written two frequencies down on his pre-1934 lab notes. One was 11,780,000 Hertz and the other was 17,033,000 Hertz. The seventh harmonic of 1,604,000 is 11,228,000 which is close to the 11,780,000 especially if you consider that Dr. Rife was not reading his frequencies correctly. We now know Dr. Rife was not even reading the harmonic correctly. Now the eleventh harmonic of 1,604,000 is 17,644,000 which is close also to 17,033,000 Hertz. Had Dr. Rife read the frequencies correctly then both the meter frequency and the cycles per second frequency should have been the same frequency. This was the case with the new lab note when it was corrected by Dr. Rife and read by Henry Siner in the 1950's. The evidence is absolutely overwhelming that Dr. Rife was not reading his frequencies correctly because the frequencies Philip Hoyland read were used in the next Rife Machine which was called the Rife Ray #4. In the space of about 60 days all Dr. Rife's frequencies changed from from the pre-1935 lab note frequencies to the new frequencies that were used with the Rife Ray #4.

We wondered where these harmonics that Dr. Rife read might of come from. Did the Kennedy Model 110 have harmonics in its waveform? Did it output a sine wave waveform? Was the waveform distorted? The only way to answer these questions was to find a working Kennedy 110 and put it on a

www.rife.org

spectrum analyzer. Jason Ringas of the Rife Research Group of Canada and I contacted Henry Rogers the owner of the Western Historic Radio Museum (www.radioblvd.com) who owns two Kennedy 110s that are still operational. Henry Rogers knew nothing about Dr. Rife but agreed to let me come visit his location to check the readings of the Kennedy Model 110. He also owns a Kennedy 220 and a Kennedy Model 281, both of which are also in working condition. The Kennedy Company built top-of-the-line equipment and we were surprised to find out even after over 80 years, they still worked as well as they did when they were new. Very little attention is ever needed to get these instruments back in working condition because of the quality of their construction. So with spectrum analyzer in hand, I went to see Henry Rogers and we put the Kennedy 110 on the spectrum analyzer to get the answers to our questions. Below is the reading of the waveform of the Kennedy Model 110 at 417,000 Hertz using a PicoScope 3205 spectrum analyzer. On the left is the waveform which proves that Dr. Rife was using sine wave.



Kennedy Model 110 at 417,000 Hertz



That question was finally answered. The spectrum analyzing of the frequency revealed that there were no harmonics in the waveform. The noise which shows up as little spikes are from the power supply. These old receivers ran on batteries and when they are hooked up to batteries the noise in the circuit is greatly reduced. The amazing thing about the Kennedy Model 110 sine wave waveform was that it was picture perfect. This amazed us because everyone believed that the equipment that Dr. Rife used would have had a distorted waveform. No one that I have ever talked with believed that this old equipment was capable of producing a nearly-perfect waveform. It was as good as we can do today with our sophisticated modern frequency generating equipment. The fact that it produced no harmonics also amazed us. Below are the readings of the Kennedy Model 110 at 770,000 and 1,604,000 Hertz. At 1,604,000 Hertz the sine wave was still nearly perfect and it did not produce any harmonics. We checked all frequencies out to 50 Megahertz for harmonics and found none.



Kennedy Model 110 at 770,000 Hertz





Kennedy Model 110 at 1,604,000 Hertz



This testing showed that Dr. Rife's equipment, call a Rife Machine, output a sine wave waveform with no harmonics. So where did the frequencies come from that Dr. Rife read and recorded on his old lab notes? Why did he record two frequencies in his lab notes? We now knew what equipment he

www.rife.org

used. His pre-1935 lab notes just didn't make any sense. We know from Henry Siner's reading of the corrected BX lab note that the meter frequency and the cycles per second frequency should be the same. It is apparent that Dr. Rife used two different pieces of equipment to read his frequencies. One piece of equipment gave a reading in meters and the other piece of equipment gave a reading in cycles per second. However even knowing this did not explain where the harmonics came from.

We knew that the noble gas he used in his ray tube could double the frequency that went through it. These types of tests have been done with plasma in laboratories in the past. So we decided to make some tests. We tested the Icom 718 which we hooked up to a phanotron ray tube. This is the type of ray tube Dr. Rife used and is the only one we tested. We first tested to see what the sine wave looked like coming out of the Icom 718. We wanted to make sure that it did not produce any harmonics, and in fact, our testing showed it did not produce any harmonics. Then we hooked it up to the antenna tuner to see if the tuner distorted the waveform and produced any harmonics. We found it did not distort the waveform or produce harmonics through the antenna tuner except at 1,604,000 Hertz. This is only because the Icom is not supposed to output a frequency below 2,000,000 Hertz. Below this frequency it will produce two harmonics (see graph on page 37). The other two frequencies we tested were 11,780,000 and 17,033,000 Hertz. These were the frequencies Dr. Rife recorded on his pre-1935 lab notes and neither of these produced harmonics through the antenna tuner. Then we put it through the ray tube. The ray tube didn't just double the frequency - it also produced all the harmonics that Dr. Rife would have read. We now had the answers as to where the harmonics came from. The ray tube produces the harmonics. You can put a harmonic-free sine wave through a ray tube and get all the harmonics that Dr. Rife recorded on his lab notes. The photo below is the Icom 718 and on the next three pages are three graphs that show the readings taken in this testing.


www.rifevideos.com
MFJ DELUXE VERSA TUNER II
MFJ Adjustable Regulated DC Power Supply
ICOM IC-718
1.604.00

www.rife.org

Testing done with PicoScope 3205 spectrum analyzer at 1,604,000 Hertz using Icom 718



Sine wave out of Icom 718 at 1,604,000 Hertz.



Icom 718 at 1,604,000 Hertz measured with spectrum analyzer showing no harmonics.



Sine wave out of Icom 718 at 1,604,000 Hertz using the antenna tuner.



Icom 718 and antenna tuner at 1,604,000 Hertz measured with spectrum analyzer showing two harmonics. These two harmonics are only produced because the Icom is not designed to go below 2,000,000 Hertz. If you output 2,000,000 Hertz it produces no harmonics.



Sine wave out of Icom 718 at 1,604,000 Hertz using antenna tuner and ray tube. Sine wave is distorted. In all tests done the sine wave was always distorted when put through a ray tube.



Icom 718 at 1,604,000 Hertz using antenna tuner and ray tube. Measured with spectrum analyzer showing harmonics all the way up to 22,000,000 Hertz. This shows that Dr. Rife's Kennedy Model 110 which only had a top range of 2,000,000 Hertz did produce harmonic frequencies in the 11,000,000 and 17,000,000 Hertz range.

www.rife.org

Below are the measurements taken with the PicoScope 3205 spectrum analyzer from the Icom 718 using the antenna tuner and ray tube at 11,780,000 Hertz. This was the first frequency Dr. Rife listed on his pre-1934 lab notes which was later changed to 1,604,000 Hertz.

www.rife.org

Testing done with PicoScope 3205 spectrum analyzer at 11,780,000 Hertz using Icom 718



Sine wave out of Icom 718 at 11,780,000 Hertz.



Icom 718 at 11,780,000 Hertz measured with spectrum analyzer showing no harmonics.



Sine wave out of Icom 718 at 11,780,000 Hertz using the antenna tuner.



Icom 718 and antenna tuner at 11,780,000 Hertz measured with spectrum analyzer showing no harmonics.



Sine wave out of Icom 718 at 11,780,000 Hertz using antenna tuner and ray tube. The sine wave does not look like a sine wave. In all cases the sine wave is distorted to some degree when put through a ray tube.



Icom 718 at 11,780,000 Hertz using antenna tuner and ray tube. Measured with spectrum analyzer showing harmonics all the way up to 50 MHz.

Below are the measurements taken with the PicoScope 3205 spectrum analyzer from the Icom 718 using the antenna tuner and ray tube at 17,033,000 Hertz. This was the second frequency on his pre-1934 lab notes which was recorded in meters. This was later changed to 187 meters which would give us a frequency of about 1,604,000 Hertz. This confirms that Dr. Rife was just reading a harmonic at 17,033,000.

www.rife.org

Testing done with PicoScope 3205 spectrum analyzer at 17,033,000 Hertz using Icom 718



Sine wave out of Icom 718 at 17,033,000 Hertz.
Some distortion was in the sine wave.



Icom 718 at 17,033,000 Hertz measured to 50 MHz with spectrum analyzer showing no harmonics.



Sine wave out of Icom 718 at 17,033,000 Hertz
using the antenna tuner. Same slight distortion noticed.



Icom 718 and antenna tuner at 17,033,000 Hertz measured to 50 MHz with spectrum analyzer showing no harmonics.



Sine wave out of Icom 718 at 17,033,000 Hertz using antenna tuner and ray tube. Sine wave was distorted even more when put through a ray tube.



Icom 718 at 17,033,000 Hertz using antenna tuner and ray tube. Measured with spectrum analyzer showing harmonics all the way up to 50 MHz.

Westinghouse RC Receiver & Amplifier



Western Electric Audio Amplifier 7A



Kennedy Model 281 Receiver



Photo of Rife's equipment that he used in his lab for doing M.O.R. work.

Five stage 50 watt class A cascade RF amplifier

The three photos of Rife's lab on this page are courtesy of the Rife Research Group of Canada.



Kennedy RF Amplifier

Remler 700 I.F. Amplifier 3.5 MHz



Kennedy Model 110 and 525 Audio Amplifier



Kennedy Model 220 and 525 Audio Amplifier



Kennedy Model 110, 281 and 525 Audio Amplifier Set Up In Rife's Lab For Doing M.O.R Work

www.rifevideos.com
www.rife.org

After having done all this spectrum analysis testing we now know how Dr. Rife misread his frequencies. The ray tube gave him the harmonics that he read. Also, he evidently did not read the harmonics correctly. Philip Hoyland read the frequencies correctly because he was an electronics engineer and had the ability to read the frequencies properly. We wish to mention that we do not feel this in any way diminishes or questions the brilliance of Dr. Rife. Even Dr. Rife himself said he was not an electronics man and never claimed to be one. He made a mistake that any untrained person could have easily made.

Having said this, let's move on to the facts. Philip Hoyland read 1,604,000 Hertz for the frequency of the BX cancer virus. Dr. Rife corrected his lab notes to this frequency. This frequency was used in the later Rife Ray #4 instrument. With these documented facts, we now know what must have happened. Dr. Rife read the seventh harmonic of 1,604,000 Hertz and recorded it on his pre-1934 lab notes. The only problem was he was unable to read the seventh harmonic correctly and misread it as 11,780,000 Hertz. It should have been 11,228,000 Hertz because this is the actual harmonic frequency that came out of the ray tube. Dr. Rife had two different pieces of equipment for reading frequencies - one which read in cycles per second and the other which read in meters. These types of meters used to measure wavelengths were common electronic test equipment, just as digital frequency counters are in common use today. Wavelength meters were much harder to use and measure frequencies with if you didn't really understand how to use them. We know that this was the case. Dr. Rife then misread the eleventh harmonic of 1,604,000 Hertz. This harmonic should have been 17,644,000 Hertz instead of the 17,033,000 Hertz. Again, we know from the corrected lab note read by Henry Siner that the cycles per second and meters frequencies should match or be the same. In these early pre-1934 lab notes none of the cycles per second and meter frequencies matched. This shows Dr. Rife used two different pieces of equipment to read the frequencies. The final fact is the Kennedy Company equipment could only output frequencies up to about 1,800,000 Hertz (far below the 11 and 17 MHz range).

When we read the Kennedy Model 110 the instrument was surprisingly accurate. Dr. Rife could have very easily hit the frequency he wanted within the tolerances he gave. He gave "one tenth of one meter" as a gage to show how close you had to be to an organism's M.O.R. At 1,604,000 Hertz this would be 858 Hertz. He said if you were off by this amount the frequency wouldn't work. With that in mind it would be necessary to be within a few hundred Hertz of the BX M.O.R. in order to make sure the frequency was effective. The Kennedy instrument could hit within 200 to 300 Hertz very easily at 1,604,000 Hertz. After changing the dials and then coming back to the same dial settings you could get within 2000 to 6000 Hertz at 417,000 Hertz. This is less than 1% inaccuracy which is quite amazing. Even Philip Hoyland, when he measured the frequencies rounded off all but one frequency to the nearest thousandth. The testing of the Kennedy Model 110 shows that the frequency for the BX is most likely somewhere between 1,600,000 and 1,608,000 Hertz, however it could be as much as 10,000 Hertz plus or minus of 1,604,000 Hertz. All of the frequencies are only close and this should be considered when using them. One fact that helps to point this out is Philip Hoyland read 1,604,000 Hertz for the frequency of the BX. He also gave 187 meters as the frequency. One hundred and eighty seven meters is 1,603,168 Hertz. This is a difference of 832 Hertz and shows why the frequencies are only close. Today's frequency generating equipment is very accurate at hitting a specific frequency but in Dr. Rife's era this was not the case. Dr. Rife's microscope gave him an advantage that we do not have. He could see the organism die.

So now that we know that Dr. Rife's Kennedy Model 110, 220 and 281 only went to 1,800,000 Hertz with harmonics going to about 20,000,000 Hertz (see graph on the top of the next page). We have to ask this question: What frequency is really the true M.O.R? Is it the 1,604,000 Hertz or a harmonic of it? The actual M.O.R. frequency could have been very easily a harmonic, and Dr. Rife would have never known it. The spectrum analyzer graph, second down on the next page, of 1,604,000 Hertz shows it could be any one of these harmonics. Since the ray tube is what produces these harmonics it may be very important to have all these harmonics. Myth Busters, a cable television program did a test

www.rife.org





to see if they could break a crystal glass with sound waves. They found when they used only the fundamental frequency without the harmonics they could not break the glass. But when they used the harmonics along with the fundamental frequency then they were able to break the glass. This may or may not be pertinent but it is something that should be considered.

With this in mind we decided to see if there was a way that we could duplicate the harmonics without having to use a ray tube. The below reading with the spectrum analyzer shows that if we distorted the sine wave no more than what the ray tube did we could produce the same harmonics as a ray tube.

GB-4000 at 1,604,000 Hertz using PicoScope 3205 Spectrum Analyzer



The reading was done at 1,604,000 Hertz taken from an off-the-shelf GB-4000 Function Generator. This test showed it was very easy to duplicate the harmonics produced by a ray tube. We decided to test a triangle wave since the distorted sine wave out of the ray tube resembled it. It also produced the same harmonics as a ray tube. Then we gated an undistorted sine wave and it produced the harmonics. It is apparent that any sine wave frequency from any frequency generator, when gated will produce harmonics.


Inside of Kennedy 281

www.rife.org





We will now discuss Dr. Rife's tuning of the Kennedy Receiver Model 110 using headphones. In the photo above, on the left, you can see a set of headphones on the Model 525 audio amplifier. Headphones were used to tune the Kennedy Receiver Model 110 and Dr. Rife's earlier instrument that he used before purchasing the Kennedy equipment. When Dr. Rife first tested the audio range of frequencies he would tune his instrument using headphones. Bertrand Comparet, Rife's attorney for the Beam Ray trial of 1939 made this statement when he was interviewed by Dr. John Hubbard:

COMPARET: *"Way back in the old days, way, way back, Rife told me that the way he used to tune his instrument, which in those primitive days was, I guess, garbled. He would hook up headphones and turn the thing. He had a very keen musical sense of pitch and so on, and he would tune it in his headphones until he got the right pitch, and that was the frequency."* (1970's Bertrand Comparet interview #89).

The headphones were used for tuning the audio frequencies in Dr. Rife's early tests when he used loose couplers. The headphones also played an important role in the tuning of the Kennedy Receivers. In the second photo, above on the right, you can see the regeneration dial of the Kennedy Receiver Model 110. When you turned up the regeneration you would listen for clicks or some static in the headphones, this would tell you that the instrument was oscillating. If you turned the regeneration up too high you would hear feedback in the headphones. This feedback meant you did not have a pure sine wave waveform. The photo below, on the left, is the waveform with the feedback from the Kennedy Receiver Model 110. It is a form of audio modulation. The other photo, below on the right, is what is produced when there is no feedback. Dr. Rife always wanted to use a pure waveform. The fact that we could actually listen to the original type of equipment that he used made it so we could understand what Dr. Rife was doing.

www.rife.org






www.rifevideos.com


www.rifevideos.com


www.rifevideos.com


Radiotron
Model UV-201A
DETECTOR AND AMPLIFIER
RCA
Radiotron
RADIOTRON
Radiotron
UV-201A
1923
Radiotron
UX-210
1923
Radiotron
UV-202
-1922-
Radio tron
UV-202
-1925-
Thermo-Valve
TV-2
1925
www.rifevideos.com

www.rife.org

We will now discuss Dr. Rife's multi-stage-amplifier that he used with the Kennedy equipment. This was most likely a class A RC coupling cascade style amplifier. Daven Company started building this type of amplifier back in about 1925. Dr. Rife may have had Daven custom build his multi-stage-amplifier but we cannot be sure. The two photos, at the bottom of this page, are Daven amplifiers. Both of them are three stage amplifiers. The Kennedy Receiver Model 110 only output about 1.5 to 3 volts. Dr. Rife needed to be able to amplify the signal to a high enough power level to make it effective. In the three old lab photos above we see Dr. Rife's multi-stage-amplifier. In the above photo, bottom right, you can see the type of tubes he would have used in the early to mid 1920's. These tubes would have made it so Dr. Rife could amplify the signal from the Kennedy Receiver Model 110 to about 50 watts in multi-stages. If you look at the above three photos of Dr. Rife's multi-stage-amplifier you will see five switches. These five switches (representing five-stages) made it so he could choose different power levels determined by how many stages of amplification he wanted to use.

www.rifevideos.com

www.rifevideos.com

With this five stage configuration he could have easily produced the 50 watts he said he used. This 50 watts, was the power level that was mentioned in the Rife CD's for this instrument.

Ben Cullen, a close friend of Dr. Rife's, mentions on the Rife CD's that Dr. Rife would light the ray tube with a separate power source. His lab photos shows a spark gap transmitter which he probably used, in the 1920's, to light the ray tube. If you look at Dr. Rife's lab photo, shown below, you can see the spark gaps. The spark gaps are right below the "Spark gap" writing.



The next photo, shown below, is an up close photo of the spark gap transmitter diathermy from the 1920's. We purchased it so we could test the lighting of a ray tube with it.



www.rife.org

The next photo, shown below, shows the lighting of the ray tube using this spark gap transmitter. It lit the ray tube with ease and could output more power than the ray tube could handle.



This spark gap transmitter would make it so Dr. Rife didn’t have any difficulties tuning the ray tube when he changed frequencies from a low frequency of 139,000 Hertz to a higher frequency of 1,604,000 Hertz. The spark gap transmitter had a damped waveform and would have given him a damped wave carrier frequency (see the photo, below left) most likely somewhere around one Megahertz. This transmitter we purchased has a frequency of 920 KHz. Dr. Rife would not have modulated frequencies onto this carrier frequency but he would have just mixed the frequencies in the ray tube (see the photo, below right, is of sine & spark mix).





Mixing would have given him the combination of a damped wave and one or two sine wave frequencies, depending if he used two sine wave frequencies simultaneously. We do not believe that Dr. Rife continued to use a spark gap transmitter because it would have made it impossible for him to read the ray tube harmonic frequencies that his ray tube output. This is because a spark gap outputs broadband noise that makes it impossible to read any harmonic frequencies. Dr. Rife must have only used the spark gap transmitter in his early 1920’s work. From the document "Development of the Rife Ray" we learn what he replaced the spark gap transmitter with.

“And as the voltage at this point was quite small, it was found necessary to apply external voltage across the anode and the cathode of the output tube [ray tube] *to act as a carrier wave for the frequencies that were generated in the apparatus.”* (Development of the Rife Ray and use in devitalizing of pathogenic micro-organisms).

www.rife.org

It appears that the spark gap transmitter accomplished to important things. One: It lit the ray tub with an external voltage. Two: It produced a high potential voltage spike in the frequencies. Later he used a DC voltage transformer much like a neon light transformer to light his ray tube. Then he added an audio pulsing circuit to create the high potential voltage spike.

To better understand the reason why a high potential voltage spike is important we need to jump forward in the history of Dr. Rife's instruments to 1936-1937. The Beam Ray Laboratory instrument built by Philip Hoyland was built at this time and it had a fixed audio frequency pulsing circuit. The audio frequency that it produced was modulated with the RF frequencies it output. This audio pulsing circuit would have given Dr. Rife’s frequencies a very high potential voltage spike almost identical to the damped wave of the spark gap. John Crane made this statement when he was narrating Dr. Rife’s lab film.

CRANE: *“Now the spikes that you see on the frequencies are the lethal part that kill and devitalize the virus. They are the resonant peaks of the frequencies which increase the voltage to a very high potential which the cells of the virus wall can not tolerate and they break up into many pieces and are destroyed.”* (Dr. Rife’s Lab Film Narrated by John Crane in the 1970’s).

The modulated audio frequency in the 1936-1937 Beam Ray Laboratory instrument was in the shape of a damped wave. With both the Rife Ray #4 and the Beam Ray Laboratory instruments having waveforms in the shape of a damped wave doesn't seem like a coincidence. When Dr. Rife discontinued using the spark gap and replaced it with an external high voltage current to act as a carrier frequency he would have had to develop a new method of creating this high potential voltage rise in his frequencies. It appears, with the help of Lee Deforest, that Dr. Rife must have developed this audio frequency pulsing circuit for his instruments. It is apparent that this pulsing of the M.O.R frequencies is the reason why Dr. Rife was able to devitalize the many microorganisms he tested.

Dr. Rife described the method he used to find these frequencies on the Rife audio CD’s.

RIFE: “*Because when I check on that thing and look through that microscope hour after hour day after day, tuning that damn thing* [Kennedy 110] *to find something that will kill that bug. And every hour or half an hour, whatever is required, I put a new fresh culture under the microscope and keep that on and I find something that folds it up, alright!*” (John Marsh Rife CD’s - CD 7 track 2).

It was a very tedious task to find a frequency that would devitalize and organism. Dr. Rife recorded all his frequencies on lab notes. Even though he misread his frequencies many people want to know those frequencies anyway. On the next page in a chart are the misread lab note frequencies which he recorded prior to 1935. Each lab note had two frequencies. One was listed in cycles per second and the second was listed in meters. For the purpose of making this report easier to understand the meter wave lengths on Dr. Rife’s lab notes have been converted to cycles per second or Hertz. You will notice that there are two audio frequencies listed for organisms that are above 12,000 Hertz. They are the only audio frequencies ever listed by Dr. Rife for any organisms. One of them was changed to a higher RF frequency when Philip Hoyland read the correct frequencies in 1935 when he built the Rife Ray #4. Most likely the other audio frequency was really a higher RF frequency.

Chapter Summary: The Rife Ray #3 frequency generating equipment which Dr. Rife purchased back in 1923 was made by the Collin B. Kennedy Company. It mainly consisted of the Kennedy model 110 and model 281 to produce its frequencies. This equipment was regenerative not super-regenerative. Its frequency range, when the model 110 and model 281 were connected together, was from about 12,000 Hertz to about 2,000,000 Hertz (2 Million Hertz). Its power output through the ray tube was about 50 watts. The frequencies it output were mostly in the AM radio band of frequencies. This equipments frequency range now explains why all of Dr. Rife's frequencies were less than 2 million Hertz as

www.rife.org

listed on the Rife Ray #4 documents. The Rife Ray #3 was the instrument that was used by Dr. Rife and Dr. Milbank Johnson M.D back in the 1934 clinic on cancer and tuberculosis patients.

In the next chapter we will look at Dr. Rife's Rife Ray #4 Rife Machine and the correct frequencies which Philip Hoyland read with his master oscillator in order to build this instrument.

www.rife.org

Dr. Rife's Misread Lab Note Frequencies From Before 1935

Microorganism	First Frequency In Hertz	Second Frequency Meters To Hertz
Actinomycosis (Streptothrix)	678,000 Hz	186,554 Hz
Anthrax	900,000 Hz	272,539 Hz
Anthrax Symptomatic	400,000 Hz	16,655 Hz
B. Coli (Rod form)	683,000 Hz	317, 914 Hz
B. Coli (Filterable virus)	8,581,000 Hz	11,103,424 Hz
Bacillus X Cancer	11,780,000 Hz	17,033,662 Hz
Bubonic Plague	160,000 Hz	512,466 Hz
Catarrh	1,800,000 Hz	1,713,100 Hz
Cholera Spirillum	851,000 Hz	960,873 Hz
Contagious Conjunctivitis	1,206,000 Hz	2,025,625 Hz
Diphtheria	800,000 Hz	1,090,154 Hz
Glanders	986,000 Hz	736,591 Hz
Gonorrhea	600,000 Hz	150,649 Hz
Influenza	1,674,000 Hz	1,946,704 Hz
Leprosy	743,000 Hz	251,926 Hz
Pneumonia	1,200,000 Hz	381,901 Hz
Spinal Meningitis	927,800 Hz	1,795,164 Hz
Staphylococcus Pyogenes Aureus	998,740 Hz	555,171 Hz
Staphylococcus Pyogenes Albus	Found in Dr. Rife's papers	549,070 Hz
Streptococcus Pyogenes	1,214,000 Hz	2,111,214 Hz
Syphilis (Treponema Pallidum)	900,000 Hz	2,775,856 Hz
Tetanus	700,000 Hz	15,779 Hz
Tuberculosis (Rod form)	583,000 Hz	541,142 Hz
Typhoid Fever (Rod form)	900,000 Hz	868,964 Hz
Typhoid Fever (Filter passing)	9,680,000 Hz	13,943,835 Hz

www.rife.org

Chapter #8

1935 Rife Ray #4 Rife Machine



1. Used a ray tube.
2. Had two separate oscillators so it could output two frequencies at a time. Frequency range was from 87,000 Hertz to 22.5 MHz.
3. Power usage was about 450 to 600 watts. Output to the ray tube was variable (50 to about 250 RF watts).

Some have asked how we can be sure these photos we have are of the Rife Ray #4 Rife Machine. It is a simple process of deductive reasoning. John Crane, one of Dr. Rife's 1950's business partners, incorrectly dated the Rife Ray #4 as a 1942 Rife Machine. This misdating has led to some confusion which we will now attempt to clear up. In the photo, shown above, we see Dr. Rife using the instrument which John Crane dated as built in 1942. However, the lab film this picture was taken from was made in the summer of 1936 for use at a conference which Dr. Rife planned to attend in the autumn of that same year. He was presenting this film at this conference to demonstrate the isolation of the BX cancer virus. This properly dates the instrument as having been built before the summer of 1936 and shows that John Crane was incorrect. In the background of this photo, behind the instrument Dr. Rife is using, we see his Kennedy Company equipment back against the wall. Therefore this instrument could have only been built in late 1935 or early 1936. The Rife Ray #4 documents show it was completed in the fall of 1935. This logically dates the Rife Machine Dr. Rife is using in the 1936 film as the Rife Ray #4. The next picture, shown on the next page, is a better photo of the Rife Ray #4 instrument.

www.rife.org



www.rifevideos.com

Bertrand Comparet, Dr. Rife’s attorney, said three experimental machines were built. With the proper dating of this Rife Machine, which shows it is the Rife Ray #4, we will now discuss it in detail.

Of the three experimental machines it appears that two were Rife Ray #4's and the third was the Rife Ray #5 or Beam Ray Clinical experimental instrument which was used in a clinic in 1937. We will cover the Beam Ray Clinical instrument later.

Dr. Johnson's machine was the first Rife Ray #4 that was built in 1935. After Dr. Johnson's instrument was built he states in a letter that the second #4 instrument was soon to be built for Dr. Rife:

DR. JOHNSON: *"While you have the machine* [Dr. Johnson's Rife Ray #4] *down there, I hope you and Jack are working on those bananas so we can get an M.O.R. for them, if possible. As soon as you send Phil and the machine back, I am going to start Phil on making your Machine."* (Letter from Dr. Johnson to Dr. Rife, November 15, 1936).

Now that we have established the fact that both Dr. Milbank Johnson and Dr. Rife had their own Rife Ray #4 instrument we can continue with the history of this instrument. As pointed out earlier in this report Philip Hoyland eventually became Dr. Rife's engineer and business partner. Philip Hoyland was the one who measured Dr. Rife's frequencies when he came to Dr. Rife's lab in 1935.

www.rife.org

We will also point out that the frequencies used in this instrument were transferred from the Rife Ray #3 to the Rife Ray #4 after Philip Hoyland read the correct frequencies. We have in the document "Development of the Rife Ray" a description of this instrument:

"In 1935 in entirely new application of the old principle was incorporated in an instrument built under the direction of Commander Rife by Philip Hoyland of Pasadena California. The new instrument was light socket powered and had an output of 500 Watts. Designated #4 [Rife Ray #4] [Many of the power output measurements of Dr. Rife's equipment were misread]. *Furthermore it was equipped to deliver two distinct frequencies simultaneously and both variable. This apparatus proved to be more efficient with decidedly fewer factors of error in the laboratory tests using 75 pounds of horse meat."* (Development of the Rife Ray and use in devitalizing pathogenic micro-organisms).

In the laboratory tests that were performed with the Rife Ray #4 they made many tests to determine its capability. Dr. Johnson talked about the many different aspects of the machine they had to test in a letter:

DR. JOHNSON: *"Also, about this time, the new Rife Ray Machine* [#4] *had arrived at its point of construction when elaborate tests had to be made in order to synchronize the M.O.R. produced by it with the M.O.R. produced by the old machine* [#3]. *Now, we are in the throes of accurately charting the 14,000 possible settings on the new machine. Our next process, beginning next week, is to test its penetration, the time required in the different exposures, the different depths of lesions. So, take it altogether we are just about as busy as a bear in berrytime."* (Letter from Dr. Johnson to Dr. Schram, dated September 25, 1935).

Dr. Rife's Single M.O.R. Frequency

The Rife Ray #4 instrument documents show it could put out two RF or radio frequencies simultaneously. Dr. Rife's previous Kennedy Model 110 when connected to the Model 281 could output two frequencies simultaneously like the Rife Ray #4. It is apparent that Dr. Rife still wanted this capability in this new instrument. Dr. Rife from time to time would run two frequencies or M.O.R.s. simultaneously on two different organisms. This is pointed out by Dr. Rife on the John Marsh Rife audio CD's:

RIFE: *"We found the frequency of the virus, we found the frequency of the rod, which we had for years of course. But if we use the two of them simultaneously over the same carrier wave, the patient gets well and the Guinea pig gets well, but if you use one or either individually you either kill the patient or you don't do nothing.*"

This statement from Dr. Rife also shows that each organism only requires a single frequency to devitalize it. The rod form of tuberculosis requires a different frequency than the virus form. In the above quote from Dr. Rife he clearly states "frequency" for each organism, not frequencies. Since his instrument could only output two frequencies at the same time this clearly shows that each organism has a single frequency as its M.O.R. In another statement when Dr. Rife was talking to John Crane about tuberculosis he said:

CRANE: *"We have the frequency that will devitalize E. coli, don't we?*"

RIFE: *"We have yes. And we have the frequency also that will devitalize the filterable form of B. coli which is not necessary. There is only one organism that we have to use two frequencies simultaneously, and that as we've spoken of before John, and that is the Bacillus of tuberculosis, where it has that so-called poison molecule of Von that is released by any known methods of devitalizing the organism and that's it."* (Marsh collection, Rife audio CD's).

www.rife.org

Dr. Rife states in this quote that there is only one organism that needs two different frequencies to devitalize it. All the other organisms only need a single frequency to devitalize them. The reason that Tuberculosis needs two frequencies is due to the fact that Dr. Rife said both the rod form and the virus form must be devitalized at the same time or the virus form will feed on the dead body of the rod form causing the patient to die from toxemia.

Even with what Dr. Rife has said many have still believed that it took two frequencies to devitalize a single organism. This misunderstanding came about because Dr. Rife had two frequencies listed for each organism on his pre-1935 lab notes. From the reading of these documents we can see this is not the case. It was Dr. Rife's misreading of his frequencies, prior to 1935, which lead to this misunderstanding. To further make the point that it only takes a single frequency to devitalize an organism we will read more statements made by Dr. Rife on the Rife Audio CD's:

RIFE: *"The frequency of each bacteria is absolutely individual. They run through a very, very large gamut. Some of them are very, very broad, long. Some of them are not extremely short. There’s none of them what we call our ultra short wave that I have found yet."* (Marsh collection, Rife audio CD’s).

DR. DICKLAND: *"Is there a different frequency between cancer and tuberculosis?"*

RIFE: *"Oh much. Every organism requires a different frequency owing to its own chemical constituents or its premodel cell or predominate chemical factor. "* (Marsh collection, Rife audio CD’s).

RIFE: *"We found the frequency of the virus, we found the frequency of the rod, which we had for years of course."* (Marsh collection, Rife audio CDs).

RIFE: "*So we’re throwing an electronic frequency through the tissues of the body that simply devitalizes the bacteria with no harm to normal tissue."* (Marsh collection, Rife audio CD’s).

These statements clearly show again that each organism has its own frequency and that it only takes a single frequency to kill, devitalize or render it harmless. As we read other statements or documents you will easily be able to see that this understanding was plainly understood by Dr. Rife and all the other doctors that used his equipment.

Because this is a very important point that needs to be understood we will read a few more documents which contain added information on this subject. When the Rife Ray #4 was finally completed Dr. Johnson wrote a letter to Dr. Rife in which he made this observation:

DR. JOHNSON: *"Maybe these Much glands are another form of the T.B.* [tuberculosis] *corresponding to our filter passing form and we will have to get an M.O.R. for them so as to destroy them at the same time that we do the rod form of tuberculosis....Now that we have a machine in which we can give two M.O.Rs at one time, it would be easy to treat all forms of tuberculosis, both for the tubercle bacilli and the Much granules."* (Letter from Dr. Johnson to Dr. Rife dated, September, 12 1935. Page 3).

Since the Rife Ray #4 only had two variable oscillators and each one was set on a different M.O.R. frequency then it would only take one frequency to devitalize each organism. In another letter this same understanding is given:

DR. JOHNSON: *"I would suggest that you set up a slide with a hanging drop planted with the cryptomyces pleomorphia. Set your machine and the microscope together. After it gets growing, start out and set on of the groups to the MOR of BX. Then with the other group, start with a certain switch on Group 2 beginning at zero. Give one minute exposure, wait about fifty minutes, and then see if there is any change. Then move the dial of Group 2 up to ten and give another exposure, waiting about fifty min-*

www.rife.org

utes and the examining it carefully. Go on that way throughout the dial and you will get through about one switch a day. Pretty soon you will find some setting that will kill the organism. Mind you, you are running at every exposure Group 1 on the BX MOR. If you got this setting started, Jack could do the microscope work and if he got any change, he could call your attention to it. That would save your eyes and your time. It is very important that we find the MOR of this fungus before I start in with the clinical work in the hospital with this new machine." (Letter from Dr. Johnson to Dr. Rife dated, October 10, 1935).

www.rife.org

When this letter was written they already had the frequency for the BX cancer virus and they were trying to find the frequency for the cryptomyces pleomorphia fungi. It is clearly pointed out that one oscillator was set on the BX organism and the second oscillator was being used to try and find the frequency for the cryptomyces pleomorphia fungi. Dr. Rife when speaking about the BX virus clearly states that it had a certain frequency not frequencies:

RIFE: *"If you don't have an absolute coordinative resonance, you have nothing. One tenth of one meter off and you have nothing. It's got to be absolutely correct for that individual organism. It's got to be precise...the virus of cancer has a certain frequency. And it has to be there, otherwise if it's a little one way or the other, no good, no good for nothing."* (John Marsh Rife CD's - CD 5 track 2, CD 6 track 2, CD 7 track 1 and CD 9 track 1).

There are even more documented examples which show that only one frequency is needed for each organism. From the horse meat tests done with the Rife Ray #4 we read:

"The test being ready, the No. 4 Rife Ray Machine was set for the MOR of B. Typhosis (rod) and also for the filter-passing form. It was turned on for an exposure of three minutes at 400 watts..." (Test of the No. 4 Rife Ray Machine, Page 2).

The frequency listed on the Rife Ray #4 documents for B. Typhosis rod form is 760,000 Hertz and the frequency for the B. Typhosis filter-passing virus form is 1,445,000 Hertz. This document also confirms that only one frequency is needed for each organism to devitalize it.

There is one more document that we will look at. This document has the misread frequency of 11,780,000 Hertz for the BX frequency. The correct frequency that was read by Philip Hoyland was 1,604,000 Hertz. It is apparent that Dr. Rife was reading the 7th harmonic of 1,604,000 Hertz incorrectly. The correct 7th harmonic frequency of 1,604,000 Hertz is 11,228,000 Hertz. Had Dr. Rife read the 7th harmonic correctly this frequency would have been on his lab note. Regardless of this mistake Dr. Rife listed only one frequency for devitalizing the BX virus. Below is his statement:

RIFE: *"Since experiments show that the Bacillus X* [BX cancer virus] *in form A exists in malignant tissue, it is theoretically possible to change the cycle to form B by application of the Argon Ray and vacuum conditions. After the cycle change has been accomplished (in theory), the application of the oscillative ray at a cycles per second vibration of 11,780,000* [correct frequency measured in 1935 was 1,604,000] *should completely destroy the B.X. in the malignant tissue."* (Rife Research Laboratory lab note on the BX).

So that no one misunderstands this quote. It was the change of the Bacillus form from A to B using the Argon Ray and vacuum conditions that was the "theory" not the destroying of the B.X. using the 11,780,000 (corrected frequency of 1,604,000) Hertz. All these document show that Dr. Rife found that only one frequency is required for each organism.

There is one other thing that apparently needs to be combined with the M.O.R. frequency and that is the pulsing of the waveform. When we discussed the Rife Ray #3 we talked about a fixed audio frequency pulsing circuit. The Rife Ray #4 also had a fixed audio frequency pulse circuit. The waveform that it output was shown in Dr. Rife's lab film and is the next photo, shown below.





The other photo shown above, top left, is a clearer photo of what a damped wave looks like. Below those two photos is drawing of what a damped waveform looks like. How Dr. Rife created this waveform was not known until a circuit from an original Beam Ray Laboratory Rife Machine was rebuilt. This circuit will be discussed in detail later in this paper when we cover that instrument.

Dr. Rife's Audio Pulsing Circuit

Though we will discuss the building of this circuit later the importance of that fixed audio frequency pulsing circuit will be discussed now. The reason for this is without this pulsing circuit no organism could have been devitalized. This pulsing circuit was the secret to making Dr. Rife's high RF frequency instruments work. Bertrand Comparet, Dr. Rife's attorney said this in his 1970's interview:

COMPARET: *"The whole secret of the Rife thing was the audio frequency because Rife, way back in the old days, way, way back, Rife told me that the way he used to tune his instrument…he would hook up headphones and turn the thing. He had a very keen musical sense of pitch and so on, and he would tune it in his headphones until he got the right pitch, and that was the frequency."* (1970's Bertrand Comparet interview paper #89).

This audio frequency pulsing circuit was put into the Rife Ray #4 Rife Machine as a fixed audio frequency. It was not a variable audio frequency circuit. The Rife Ray #4 instrument documents show the #4 instrument had no variable audio oscillator which indicates that Dr. Rife believed that it was no longer necessary for M.O.R. work. But the fix audio pulsing circuit was absolutely necessary to be put into the instrument so that the high RF frequency M.O.R. frequencies were pulsed in order to devitalize the various organisms. All of the frequencies that Philip Hoyland read from the Kennedy Model 110 and transferred to the Rife Ray #4 were RF frequencies and needed to be pulsed. The lowest frequency was for Anthrax at 139,200 Hertz; the highest was 1,604,000 Hertz for the BX organism that caused cancer.

www.rife.org

The Rife Ray #4 would have also been a sine wave instrument just as the Kennedy Company equipment was. Since the Rife Ray #4 had two high RF frequency oscillators it would allow for the oscillators to be set at two different M.O.R.s. This instrument was probably built much like the Beam Ray Laboratory instrument which connected the ray tube between the two RF oscillator tank coils. The reason for this is the fact that the bandwidth of the RF tank coils could only pass a frequency of about 250,000 Hertz and Dr. Rife was using frequencies much higher than this.

Dr. Rife's Carrier Wave

We will now discuss Dr. Rife's use of a carrier wave in his instruments. This next statement by Dr. Rife's verifies the fact that with the Kennedy equipment or Rife ray #3 he used a carrier wave:

RIFE: *"We found the frequency of the virus, we found the frequency of the rod, which we had for years of course. But if we use the two of them simultaneously over the same carrier wave, the patient gets well and the Guinea pig gets well, but if you use one or either individually you either kill the patient or you don't do nothing".* (Marsh collection, Rife audio CD's).

Dr. Rife's mention of a carrier wave has lead to some confusion in the past because when we think of a carrier wave we think of a higher RF frequency that the lower RF or audio frequencies would ride on. But the documents show this was not the case. The "Development of the Rife Ray" document tells us what that carrier wave was:

"And as the voltage at this point was quite small, it was found necessary to apply external voltage across the annode and cathod of the output tube to act as a carrier wave for the frequencies that were generated in the apparatus." (Development of the Rife Ray and use in devitalizing of pathogenic micro-organisms).

Dr. Rife's carrier wave was just an external high voltage current that was used as a means to light the ray tube. The use of this high voltage current as a carrier wave was also used with the Rife Ray #4 and was not remove from the instruments until the summer of 1936 when the new Beam Ray Clinical instrument was built. This will be covered later.

Dr. Rife used the Rife Ray #4 Rife Machine in his laboratory until he closed it down in about 1947. The Rife ray #5 or Beam Ray Clinical instrument was completed in the summer of 1936 and was the new design that was used by all the doctors. Dr. Johnson used his Rife Ray #4 instrument in at least two medical trials. Dr. Johnson always had his patients sign a release card, shown on the bottom of page 56, in order to be treated with the frequencies output by the Rife instrument.

On page 57 is a chart showing the sine wave frequencies read off of the Kennedy Company equipment and used in the Rife Ray #4 instrument. We now know these frequencies were the frequencies used in the 1934 clinic since they were taken off of the Rife Ray #3 which was used in that clinic. The chart was made from The Rife Ray #4 document. This same document along with its additional page was mentioned in a letter written by Dr. Milbank Johnson to Dr. Rife dated Oct. 15, 1935:

DR. JOHNSON: *I am also inclosing a copy of a chart prepared for me by Phil* [Philip Hoyland] *which show the frequencies in kilocycles of the different M.O.R.'s we have worked with. Opposite these frequencies you will find the proper switch and settings on both groups. Now, in looking over the frequencies representing the M.O.R. of certain organisms, I find that the typhoid rod has 760 kc. And just above that you will find that the typhoid filter passing has 1445 kc. - that is almost an exact harmonic of the rod. Assuming that the banana might represent the rod form of the cryptomyces pleomorphia - on the same plan let us assume that the B.X. is the filter passing form of this organism. If that is so, we should kill the rod, it being the harmonic of the rod form, at 800 kc.* [this statement verifies that the BX

www.rife.org

M.O.R. frequency was 1.604 kc. - or 1,604,000 Hertz]. *This 800 kc. Will come in group No. 2 on switch 6. A reference to the proper chart under Group No. 2 would give the exact setting to get 800 kc. This is just a chance and I have no assurance that it will work out, but I think it is worth trying so I think I would try on switch 6 in Group N. 2 for your first effort to kill the fungus, or rather to kill the bananas.* (Letter from Dr. Milbank Johnson to Dr. Rife, October 15, 1935).

This letter and the Rife Ray #4 document confirm that Dr. Rife had misread his frequencies prior to 1935 and that each organism only has a single frequency as its M.O.R. The letter also shows that they were using the corrected frequencies read by Philip Hoyland when he came to Dr. Rife's lab to read the Rife Ray #3 in 1935. The frequencies used in Rife Ray #4 were used to create the next version of Dr. Rife's machine.

Chapter Summary: The Rife Ray #4 was built in 1935 at the request of Dr. Milbank Johnson because he wanted an instrument that was in the comforts of a single cabinet. It had the highest frequency range and power output of any of Dr. Rife's machines. There were only two of these machines built. The first one was built for Dr. Milbank Johnson and the second one was built for Dr. Rife. The frequencies used in this machine were the same frequencies that were used with the Rife Ray #3. Each organism only required one frequency to devitalize it. Like the Rife Ray #3 the Rife Ray #4 used a fixed audio frequency pulsing circuit to create a high potential voltage rise in the RF M.O.R frequency to devitalize the organism treated with the instrument. The Rife Ray #4 was used by Dr. Milbank Johnson in two clinical trials.

In the next chapter we will take an in-depth look the next instrument that was built by Dr. Rife's engineer, Philip Hoyland. Philip Hoyland developed a new method of delivering Dr. Rife's M.O.R. frequencies.



RELEASE

It has been determined that I, F. G. Adamson, am suffering from a malignant disease which I believe to be Sinus infection and I am informed that Dr. Milbank Johnson and his associates have been experimenting with a new method of treatment of said disease upon the lower animals with sufficient success to lead me to hope that it may be successful in my case. However, I wish it distinctly understood that neither Dr. Milbank Johnson nor his associates have made any promises, claims, representations or other assertions as to the outcome of their new method of treatment; Dr. Milbank Johnson and his associates have agreed to subject me to their new method of treatment without charge to me and in consideration of their services in this connection, I hereby consent to allow Dr. Milbank Johnson and his associates to subject me to their new method of treatment of my disease and further do consent to allow said Dr. Milbank Johnson and his associates to subject me to any other type of treatment, whether operative or otherwise, that they may in their opinion deem necessary or advisable in connection therewith or as a result thereof; and further, I hereby release said Dr. Milbank Johnson, his associates, employees and attendants, from any and all liability for any untoward results that I may suffer in connection with or as a result of any such treatment or treatments, whether operative or otherwise, with the full realization on my part of the experimental character of said new method of treatment. I agree that this consent and release shall be binding upon my heirs and legal representatives and that the same shall extend to and release the heirs and legal representatives of said Dr. Milbank Johnson, his associates, employees, and attendants. It is further understood that this release shall extend to and include any hospital or clinic that Dr. Milbank Johnson or his associates may be associated with, and also their respective staffs, employees, and attendants.

I have asked certain of my relatives to agree to the terms of this instrument and they have signed below.

Dated at San Diego this 24 day of August 1936

Witness: ______________________

F G Adamson
PATIENT

I or we hereby agree to be bound by the above:

______________________ ______________________
RELATIONSHIP

______________________ ______________________
RELATIONSHIP

www.rife.org
www.rifevideos.com

Rife Ray #4 Sine Wave High RF Frequencies	
Actinomycosis (Streptothrix)	192,000 Hz
Anthrax	139,200 Hz
B. Coli (Rod form)	417,000 Hz
B. Coli (Filterable virus)	770,000 Hz
Bacillus X or BX Virus (Cancer Carcinoma)	1,604,000 Hz
Bacillus Y or BY Virus (Cancer Sarcoma) This frequency was not on the Rife Ray #4 document because it was not found at that time. It was in 1936 when this viruses frequency was obtained and it was used in the Beam Ray Clinical machine. We included it here with this explanation.	1,530,000 Hz
Gonorrhea	233,000 Hz
Spinal Meningitis	427,000 Hz
Staphylococcus Pyogenes Aureus	478,000 Hz
Streptococcus Pyogenes	720,000 Hz
Syphilis	789,000 Hz
Tetanus	234,000 Hz
Tuberculosis (Rod)	369,000 Hz
Tuberculosis (Virus)	?769,000 Hz
Typhoid Fever (Rod)	760,000 Hz
Typhoid Fever (Virus)	1,445,000 Hz

www.rife.org

Chapter #9

1938 to 1939 Beam Ray Corporation Clinical Rife Machine


www.rifevideos.com

1. The instrument used a ray tube.
2. Had one variable Audio oscillator and one Fixed RF oscillator set at 3.30 or 3.80 MHz.
3. Power usage was about 450 to 600 watts. Output to the ray tube about 40 to 50 RF watts.

Just as with the Rife Ray #4 Rife Machine we must determine what the Rife Ray #5 or Beam Ray Corporation Rife Machine looked like. The reason we need to determine this is because unless we know what those instruments really looked like we may think we have a true Rife Ray #5 or Beam Ray Clinical instrument and find out later that it is not one. Beam Ray Corporation built two different instruments, one was called the Clinical instrument and the other was called the Laboratory instrument. The fact that Beam Ray built two different instruments was pointed out in the Trial: (Beam Ray Trial Transcript #209-210)

COMPARET: *"The four machines bought by the British were two so called laboratory types and two so called clinical types, what was the difference between the two?"*

HOYLAND: *"The clinical type was similar in all respects to the Rife machine except that it did not have* [word missing] *of the* [word missing] *used on Mrs. Henderson."*

We now know that Beam Ray Corporation built two different Rife Machines of which one was built using the original Rife principles and it was considered the Laboratory instrument. The other was built using a different method of generating the frequencies and we will show that it was called the Clinical instrument. First we will prove that the photo, shown above, and the next photo, shown on the top of the next page, are photos of the Rife Ray #5 or Beam Ray Clinical instrument.

www.rife.org

The instrument, shown below, is a photo of one of two Rife Machines owned by Dr. James B. Couche which he purchased from Beam Rays Corporation. Dr. Hamer also purchased one of these Clinical Rife Machines. This information was pointed out during the Trial and gives us the proof we are looking for: (Beam Ray Trial Transcript #98-99, 217-218, 1128-1131 and 2700)


www.rifevideos.com
www.rife.org

COMPARET: *"Before this agreement was signed did the company manufacture any Rife ray machines?"*

HOYLAND: "*They started to about the first of May* [May 1, 1938]. *Dr. Hamer was sold one."*

COMPARET: *"How was the price of these machines fixed?"*

HOYLAND: *"The price was decided from the costs of what it cost to manufacture the first machine that was sold to Dr. Hamer."*

COMPARET: *"Were the clinical machines the same as were made for Dr. Hamer?"*

HOYLAND: *"Yes."*

COMPARET: *"Was that the same as the machine used on Mrs. Henderson?"*

HOYLAND: *"No, but the same type."*

SAPIRO: *"These machines are perfectly good, they are just the same as the* [Dr.] *Couche machine and the one that gave Mrs. Henderson such relief."*

www.rife.org

These quotes show that Beam Ray Corporation sold the Clinical style Rife Machines to Dr. Hamer and Dr. Couche. In 1951 Dr. Couche sold one of his Beam Ray Clinical instruments to Dr. Tully.

The photo on the previous page of Dr. Couche's machine and the documents we have read show us that his machine is an original Rife Ray #5 or Beam Ray Rife Machine. With this machine we can make comparisons against it when looking at other instruments.

The next photo, shown below, is a picture of Dr. Rife and Philip Hoyland. Philip Hoyland was Dr. Rife's engineer and business partner in the Beam Ray Corporation. In this photo is an instrument. We will prove that this instrument is also a Beam Ray instrument by making some comparisons with other Beam Ray machines.



This photo of Dr. Rife and Philip Hoyland was taken for a May 6, 1938 newspaper article published by the San Diego Tribune. In the newspaper the caption below the photo said: "Royal Raymond Rife, left and Philip Hoyland with Rife ray apparatus". On May 1, 1938 the Beam Ray Corporation started selling its Rife Ray #5 or Beam Ray Clinical Machine to doctors. This front page newspaper article had the capability of selling many instruments. It is only logical they would have photographed the instrument they were selling.

The next two photos, shown at the top of the next page, are close-up photos of these instruments. You will notice the similarities of these two instruments. They are almost exactly alike except for the case. Beam Ray used both types of cases with the Rife Ray #5 or Beam Ray Clinical instruments they sold.

www.rife.org
www.rife.org
www.rife.org





Dr. Couche’s Rife Machine, above on the right, was in a case that extended all the way down to the floor. It had handles on the side and wheels on the bottom which would make it very easy to move around. Both instruments have one oscillator dial which is located on the left side of the front panel. Below that dial on Dr. Couche’s instrument was a four position band switch and on the other instrument, above on the left, is a fine tuning dial. The fine tuning dial was replaced by a four position band switch in order to give the instrument better accuracy. The second dial, in the center of both instruments, goes to 100 and was the amplitude dial. Above that dial on both instruments is a tuning eye for calibrating the instrument’s RF carrier frequency. Below is a photo of one of these tuning eyes.



Both instruments have a milliamp power meter located all the way over to the right next to where the ray tube is connected. Dr. Couche’s instrument had a timer below the power meter to help him make sure he treated the patient for the correct amount of time. Along the bottom are the filament, sweep and output switches which are not clearly marked on Couche’s instrument but we can see what appears to be three different switches, two below the center amplitude dial and one below the timer. The comparison we have just made with Dr. Couche’s Beam Rays instrument shows they are both Beam Ray instruments. Beam Ray Corporation just put this Clinical machine into two different cases.

In the document "Development of the Rife Ray" we have a description of this Beam Ray Clinical instrument:

"In the early part of 1936 Commander Rife and Mr. Hoyland spent much time collaborating on revising some of the applications of the fundamentals of the instruments due to the advancement that had

www.rife.org

taken place in the application of electronics and it was found that the carrier wave used in the previous instruments could be eliminated. During the summer of 1936 further experiments were carried on, which resulted in an entirely new method of generating the desired frequencies and produced a constant input and output in the instruments.

During this work several new test appliances were built for further studying the different frequencies and waveforms noteworthy among these was a 9 inch Cathode-Ray oscillograph of high sensitivity, built for the purpose of photographing the different frequencies on motion picture film and thereby allowing the numerous waves to be studied at will. During the fall of 1936 Dr. Couche of San Diego and Jack Free assistant to Commander Rife conducted a clinic with one of the frequency machines treating experimentally cases of carcinoma and senile cataract..." (Development of the Rife Ray and use in devitalizing pathogenic micro-organisms).

The first thing that we learn from this document is the high voltage current carrier wave that was used to light the ray tube in the Rife Ray #3 and Rife Ray #4 was no longer used or needed with the new Rife Ray #5 or Beam Ray Clinical instrument. The document is correct because this style of instrument only uses an RF carrier frequency to light the ray tube. The second thing we learn is that this instrument was working on an entirely new method of generating the M.O.R. frequencies. This method has been referred to over the years as harmonics. But it is more complex that what was originally believed.

This new method that was used to generate the frequencies has been a mystery for the past 75 years. Finally with the location and purchase of an original Beam Ray Clinical instrument and the use of spectrum analysis the method that Philip Hoyland used has been discovered.

In the first photo, below on the left, is the Rife Ray #5 or Beam Ray Clinical Machine that Dr. Rife and Philip Hoyland were photographed with for the may 1938 newspaper article. In the second photo, below on the right, is a picture of an original Beam Ray Rife Ray #5 instrument. This instrument was obtained from Dr. Larry Low. He has owned it for over 25 years. This is the only known original Beam Ray Corporation Clinical instrument to have survived. It was used by a Medical Doctor who died in the mid 1960's.





www.rife.org

We would like to thank Dr. Low for allowing us to get this instrument so we could analyze it. It is a low audio frequency instrument which uses an RF carrier frequency. This Rife Ray #5 or Beam Ray Clinical instrument is very important. The significance of this instrument is due to the fact that it is the only known original Rife Ray #5 or Beam Ray Clinical instrument to exist. There were about 14 instruments built by the original Beam Ray Company and until now no one has ever been able to find one. The fact that even one has survived is a miracle. This instrument proves beyond any doubt that Philip Hoyland was the one who first built the low audio frequency instruments such as the Rife Ray #5 Beam Ray Clinical instrument.

The next photo, below on the left, is also a Beam Ray Clinical instrument. This photo, was found inside the case of the original Rife Ray #5 or Beam Ray Clinical instrument obtained from Dr. Larry Low. The second photo, below on the right, is Dr. Couche's Beam Ray machine. Both of these Rife Machines are in the same case. If you look closely you will notice that both instruments have the same metal arm attached to the top of the instrument which holds the ray tube. This same arm is also on the top of the original machine obtained from Dr. Low.





In every detail the cases are the same. The only difference between these two machines is the layout of the front panel. Though the panels are laid out differently both machines have the frequency dial, amplitude dial, band switch, milliamp meter, timer, power light and two switches. It appears when Beam Ray Corporation built their first instrument, which was shown in the May 1938 newspaper photo, they had no band switches dividing out the audio frequency range. The doctors that used these instruments complained about the accuracy problems. It is apparent from the Beam Ray Trial testimony that a four position band switch was added to help stabilize the audio oscillator and hopefully solve this problem. The original Beam Ray instrument that we obtained has a band switch with four settings. Aubrey Scoon's Beam Ray Clinical replica instrument also has a four position band switch. We will fully evaluate the Aubrey Scoon instrument later in this report. But we will refer to it from time to time as needed as we look at this original Beam Ray Clinical instrument. The 1953 AZ-58 Beam Ray Clinical replica, which we will also evaluate later in this report, had a three position band switch. They only used a three position switch because they used audio frequencies which were ten times lower than the original Beam Ray Clinical instrument. Because of this they did not need or use a fourth band.

www.rife.org

To further analyze the two original Rife machines we will now do a comparison of the faceplates. We will look at the instrument obtained from Dr. Low and the instrument Dr. Rife and Philip Hoyland were standing next to in the 1938 news paper photo.

The first close up photos are of the variable audio oscillator control. The photo, below on the left, is the May 1938 photo. The photo, below on the right, is the original instrument we obtained. Normally the dial should only go 180 degrees from 0 to 100 as shown on the May 1938 dial. Our instrument does not have the original dial because it goes from 0 to 100 in 270 degrees.

www.rife.org





Though the dial shows 270 degrees it will only go 180 degrees. You will also notice that our dial is bigger than the original dial and partially covers where the old fine adjustment dial was located. The fact that the hole is still there, but was covered, indicates that this instrument at one time worked the same as the instrument in the 1938 photo. When they added the four position band switch the fine adjustment knob was no longer needed.

Our Rife Ray #5 or Beam Ray Clinical Rife Machine, like Aubrey Scoon's instrument, had four bands that cover these frequency ranges.

www.rife.org

Band 1: 160 Hertz to 820 Hertz.

Band 2: 594 Hertz to 3,190 Hertz.

Band 3: 2,440 Hertz to 12,930 Hertz.

Band 4: 9,430 Hertz to 42,600 Hertz.

www.rife.org

Aubrey Scoon's Beam Ray Clinical Replica instrument band ranges, listed below, were different.

Band 1: 20 Hertz to 200 Hertz.

Band 2: 200 Hertz to 2,000 Hertz.

Band 3: 2,000 Hertz to 20,000 Hertz.

Band 4: 20,000 Hertz to 200,000 Hertz.

These four bands were discussed by Philip Hoyland and Bertrand Comparet during the trial. (#257-260):

COMPARET: *"If you wanted to treat one with typhoid for instance wouldn't you have to set the machine so that it would be on a particular frequency."*

HOYLAND: *"No, the machines were made so that they varied over a band of frequencies."*

COMPARET: *"That band used for the treatment of each disease was different from other bands for other diseases, wasn't it?".*

HOYLAND: *"The whole list of bacteria that the machine was treating was divided into four bands."*

The next two photos, shown below, are of the tuning eye and the amplitude control. The photo, on the left, is from the May 1938 instrument. The photo, on the right, is our original Beam Ray Clinical instrument. Above the amplitude dial on the photo of the May 1938 instrument is the tuning eye.





www.rife.org

On our instrument you can see that the tuning eye was removed. Notice that you can still see the outline of the tuning eye mounting ring. On the May 1938 instrument the amplitude dial went from 0 to 100 and adjusted the audio frequency modulation. On our instrument the amplitude dial also goes from 0 to 100 and adjusts the modulation of all the audio frequencies. This modulation is not a true (AM) amplitude modulation. It is more of a pulse width modulation.

The next two photos, shown below, are of the milliamp meter that goes to 300 and the ray tube hookup. The photo below, on the left, is the May 1938 instrument. The photo, on the right, is our instrument.

www.rifevideos.com
www.rifevideos.com
www.rifevideos.com


www.rifevideos.com
100
200
300
D C
MILLIAMPERES
www.rifevideos.com
www.rifevideos.com

Until the discovery of our Rife Ray #5 or Beam Ray Clinical instrument we did not know exactly where the fixed RF tank coil was located. We thought it was probably behind the milliamp meter but now we know this is exactly where it was located.

The next two photos, shown below, are of the plaque. The first photo is of the May 1938 instrument. The second photo is our instrument. These photos show where the original plaque was on the instrument.


PROPERTY OF
RIFE RESEARCH LABORATORY
DESIGNERS AND BUILDERS

www.rifevideos.com

The plaque read; “Property of the Rife Research Laboratory, Designers and Builders.” On our instrument the plaque is missing but you can still see the four mounting screws that held the original plaque. Since this plaque had Dr. Rife's name on it this could have caused the doctor problems. So he may have removed it in order to avoid the machine being called a “Rife Machine.”

www.rife.org
www.rife.org
www.rife.org
www.rife.org

In the next two photos, shown below, you can see the “Filament”, “Sweep” and “Output” switches. The first photo is of the May 1938 instrument. The second photo is our instrument. On our instrument the sweep plaque was removed and the switch was replaced with a red light that indicated that the instrument had power.





This is where the power indicator light was put on almost all of the instruments built during the 1940's and 1950's. The filament switch turned on the power to the 866 rectifier vacuum tubes and the output switch turned on the power to the 809 main amplifier vacuum tube section. Turning on the power to the 809 tube would light the ray tube. Because of the accuracy problems (due to the old (RC) resistor capacitor audio oscillator) of the Beam Ray audio instruments the sweep switch was probably used to try and help solve this problem. The sweep switch appears to have been removed when the band switch was added. Above the output label on our instrument we see a 15 minute timer for setting the desired runtime for each frequency that was used. The Original 1938 Beam Ray Clinical instrument photo does not have a timer but Dr. Couche’s Beam Ray instrument shows his instrument had a timer on the front panel. Even the photo of the other Beam Ray Clinical instrument which was found inside our instrument has a timer built into it. These photos show that a timer was put in most all of the original Beam Ray instruments. The next photo, shown below, is a larger photo of the Rife Ray #5 or Beam Ray Clinical Rife Machine with the ray tube lit.



www.rife.org

The next photo, shown below, is of the inside of the Rife Ray #5 or Beam Ray Clinical instrument. The RF tank coil of our instrument was set at 3.80 MHz. The 809 was the main output power tube. There were two 866 rectifier tubes.


Tank coil set at 3.80 MHz
6SJ7 tube behind 6F6G tube
809 tube
#80 rectifier tube for audo circuit
Two 6F6G tubes
Variable capacitor for tuning audio frequencies
Two 2mf 1500V capacitors
Two 866 rectifier tubes
www.rifevideos.com

The audio section consists of 2 6F6G tubes and one 6SJ7 tube. All of the Philip Hoyland audio instrument designs built from 1936 through the 1953's AZ-58 resemble each other. Anyone looking at the different instruments can see that they are all built almost in the same way. Tubes may vary, such as the 812a eventually replaced the 809, but the workings of all the instruments are similar. Both this original Beam Ray Clinical instrument and Aubrey Scoon's Beam Ray Replica instrument have Hewlett Packard sine wave audio oscillators. Mr. Peter's and I was able to repair the audio oscillator and read the different frequency band settings. It was only a 25 watt 10,000 ohm resistor which had burned up that made it so this instrument would not work.

The readings for this report was done with this original Rife Ray #5 or Beam Ray Clinical instrument . Also with Aubrey Scoon's Rife Ray #5 instrument and the AZ-58 replica instrument that we built. They all work identically the same as the original instrument. This original Beam Ray Clinical instrument did not come with any paperwork which gave the dial settings for the various audio frequencies it used. This actually turned out to be for the best because we had no audio frequency data that could have stopped us from discovering how this instrument really worked on Dr. Rife's original high RF frequencies.

www.rife.org

www.rife.org

The Next photo, shown below, is the underside of our original Rife Ray #5 or Beam Ray Clinical instrument. The underside of the chassis shows both the audio section and part of the RF section.



www.rifevideos.com

Now that we have an original Beam Ray Clinical instrument we know without any doubt that Philip Hoyland's Clinical instrument design used audio frequencies and it modulated those audio frequencies onto a fixed RF carrier frequency. Dr. Rife and Philip Hoyland had an agreement that they would share evenly on the financial profits of the instruments. Philip Hoyland stated this when he was on the stand during the Beam Ray Trial: (Beam Ray Trial Transcript #505-507)

HOYLAND: *"Dr. Rife and I had always had the understanding that we shared evenly, as I had done all the development work."*

COMPARET: *"What do you mean by that."*

HOYLAND: *"I had done all of the building and designing of the machines other than the one original machine* [Rife Ray #3 which consisted of the Kennedy equipment] *that he had in his laboratory. I had brought that to a state where it could be carried around"* [Rife Ray #4].

From these trial statements we know that all the designs were Philip Hoyland's designs. When Hoyland built the audio instrument he built it on a completely different principle or method. Philip Hoyland had changed the instrument to work on a different method which used harmonics. Dr. Rife believed they were using the Rife Ray #4 RF frequencies along with harmonics. This was pointed out in the 1939 Beam Ray Trial (#1247-1250, 1278-1281):

COMPARET: *"Has the Plaintiff* [Philip Hoyland] *ever informed you that the machines that he designed and built for the Beam Ray were not operating on the same frequencies as your own?"*

RIFE: *"They were supposed to be operating on the same with harmonics."*

www.rife.org

COMPARET: *"Did he ever tell you that there was a fundamental difference?"*

RIFE: *"He said on one or two occasions that there was a difference in harmonics."*

SAPIRO: *"You say that the devices that were being built in the early part of 1938, the one that went to Dr. Couche and two that were in the lab were built on new harmonics?"*

RIFE: *"They were built on a different principal, we have a given wave length and it can be produced in different ways, but it should be the same no matter how it is produced."*

SAPIRO: *"You knew that these machines were being built with that machine."*

RIFE: *"Yes"*

Philip Hoyland when he was on the stand was asked (#935-938, 953-958):

COMPARET: *"I understand you say that the frequencies used in the machines put out by the corporation were not set to the same frequencies as Dr. Rife's machines* [Rife Ray #4]*."*

HOYLAND: *"That is correct."*

COMPARET: *"Did you inform the board of directors of Beam Ray that the machine you built was not the same as Dr. Rife's?"*

HOYLAND: *"I had spoken to them about it."*

COMPARET: *"Then it was during the period between September and November that you told Edwards at his home that the machines you were building were not putting out the same frequencies as Dr. Rife's machines?"*

HOYLAND: *"Yes."*

COMPARET: *"How did you explain that?"*

HOYLAND: *"In the summer of 1936 I designed a new machine, or rather I checked it there at the lab* [The Beam Ray Clinical instrument]. *I had designed it in Pasadena, and we tested it out then and the frequencies were not the same as on Dr. Rife's machine."*

COMPARET: *"Did you tell him how great the difference it was?"*

HOYLAND: *"I explained that there was quite a fundamental difference."* [Harmonic frequencies]

Comparet when asked a question by Judge Kelly made this statement. (#2673 & 2685):

COMPARET: *"Hoyland has said that the design and the frequencies of the machine itself is not that of a Rife Ray machine, and that the machine is in fact different. The company will have to have these machines junked, must draw up new designs according to Dr. Rife's ideas, must have Dr. Rife ok these designs, etc…Dr. Rife is not going to be a party to a fraud, and if the machines we sell are not the true Rife machines they are a fraud."* (Beam Ray Trial Papers).

When Edwards was on the stand he stated. (#1384-1385):

COMPARET: *"Did Mr. Hoyland tell you at any time in the fall of last year that the machines he was manufacturing for Beam Ray corporation operated on a principle fundamentally different from Dr. Rife's machine?"*

EDWARDS: *"No, Mr. Hoyland told me at one time that Dr. Rife thought that he had the frequencies but he didn't have them* [Here Edwards is talking about the Beam Ray Corporation instruments not the Rife Ray #4 instrument because Philip Hoyland said, on the stand, that he gave the Rife Ray #4 frequencies to Dr. Johnson and Dr. Rife in 1935]." (Beam Ray Trial Papers).

Philip Hoyland also stated this when he was on the stand. (#800):

HOYLAND: *"Regarding the frequencies of the machine* [Beam Ray Corporation Clinical instrument], *you will remember me telling you that the frequencies used are not the same ones on the Rife machine* [The Rife Ray #4]. *They* [Meaning the Rife Ray #4 frequencies] *were in the upper bands* [139,000 to 1,604,000 Hertz]." (Beam Ray Trial Papers)

In a letter which he sent to Dr. Gonin in 1939, there are indications that Dr. Rife wanted the so-called harmonics removed:

RIFE: *"I spoke only Friday evening to a Mr. John Chamblin, a radio man now connected with Beam Ray Inc., about the redesign and building of a device according to the old Rife Ray principles; as the present instrument has been so deviated away from that old principle that it is nowhere near the same...those devices which you have are merely working on a harmonic and not a true frequency; and in our research on electronics, we definitely know that there is no possible way of controlling electrical harmonics of a frequency."* (Letter from Dr. Rife to Dr. Gonin, May 14, 1939. Page 1 of 3).

We have just read a lot of trial testimony about how this Rife Ray #5 or Beam Ray Rife Machine worked on harmonic frequencies. Also, in the trial testimony it is mentioned that these Beam Ray audio machines were tested in Dr. Rife's lab to see if they would devitalize microorganisms. It was Philip Hoyland who made the tests using Dr. Rife's organisms. These tests were also repeated again in Dr. Johnson's laboratory in the summer of 1936. From the documents we know that Philip Hoyland put a lot of work into this instrument and didn't finish it until late 1936. Benjamin Cullen said Philip Hoyland spent a lot of time at the lab and stated the following in a taped interview in the 1950's:

CULLEN: *"Philip Hoyland was in there quite a lot...Hoyland developed some few items in the lab...Hoyland seemed to help quite a lot and he got into the bacteriology side with Rife a good deal because Rife had so much to work out...he finally got to the point where he* [Dr. Rife] *had to delegate some of the work."* (John Marsh Rife CDs, CD 6 track 1).

In the Beam Ray Trial manuscript we also read the following. (#91 & 93):

COMPARET: *"Were any experimental activities carried on in the lab?"*

HOYLAND: *"Yes."*

From the trial we learn that Philip Hoyland developed and tested his harmonic instrument in the lab. How could Philip Hoyland have tested it unless he put micro-organisms under the microscope? From the "Development of the Rife Ray" document we learned that:

"During the fall of 1936 Dr. Couche of San Diego and Jack Free assistant to Commander Rife conducted a clinic with one of the frequency machines treating experimentally cases of carcinoma and senile cataract..." (Development of the Rife Ray and use in devitalizing pathogenic micro-organisms).

www.rife.org

From the trial papers we learn that Philip Hoyland didn't tell Dr. Rife what frequencies he was using in the instruments. Dr. Rife thought the instruments were using his frequencies (the upper band frequencies) but with harmonics because this is what Philip Hoyland told him. The information that we now have obtained from this original Rife Ray #5 or Beam Ray Clinical instrument shows that Philip Hoyland's instrument was working on Dr. Rife's principles and on his frequencies but in a different manner than Dr. Rife was lead to believe. This is the reason that the instrument worked so well. Philip Hoyland was still using Dr. Rife's principle of coordinative resonance but hid the truth from Dr. Rife to protect his ownership interest. Philip Hoyland was a business man and Dr. Rife was not.

The fact that these tests were done along with the fact that these instruments were used by many doctors with incredible results show that this instrument which used audio frequencies modulated onto an RF carrier frequency did devitalize microorganisms. Though Dr. Rife did not like the method of harmonic frequencies that Philip Hoyland used it was pointed out in the trial that Dr. Rife knew there were changes. Dr. Rife also didn't think that these changes would make much of a difference as long as the instrument worked: (Beam Ray Trial Transcript #2700)

SAPIRO: *"Dr. Rife said that he knew there were changes made in his machine and that they were not changes that would make any difference. Dr. Rife is a genius but he didn't know how to put the machines in a form that could be used in offices of doctors. These machine are perfectly good, they are just the same as the* [Dr.] *Couche machine and the one that gave Mrs. Henderson such relief."*

It was only with the release of the complete Beam Ray Trial manuscript and other Rife documents; found in California a few years ago that we now know why Dr. Rife continued to have this style of instrument built even in the 1950's. Though Dr. Rife originally did not like Philip Hoyland's Rife Ray #5 or Beam Ray Clinical design instrument, because of the use of harmonics, he later tested it in his laboratory and found it would work as well as his original instruments that did not use harmonics. We will quote the complete letter since all of this information is important:

RIFE: *"My first association with Dr. Yale came through an organization known as the Beam Ray Corporation. In order to acquaint you with the details of the formation of this corporation I shall bring in a little background. My assistant at that time* [1934] *in the laboratory was Philip Hoyland whom I met through Dr, Milbank Johnson M.D., Medical Director for the Pacific Mutual Life Insurance Company. I considered Hoyland as a capable electronic engineer and brought him to my laboratory in Point Loma on Alcott Street, San Diego, Calif. Hoyland became associated with a promoter named Hutcheson and Dr. James B. Couche M.D. They came to me with the idea or forming the Beam Ray Corporation to manufacture and distribute the Frequency Instrument to the medical profession. I gave this considerable thought and came to the conclusion that if these instruments were manufactured and placed into the hands of legitimate and bonafide medical practitioners, my efforts, over a period of years would derive exceedingly more benefits, so I gave this corporation permission to manufacture these devices on two stipulated conditions (1) that they would adhere decidedly to the original basic principles of the Frequency Instrument and (2) that each Frequency Instrument would be thoroughly tested before delivery to determine its true devitalizing power and effect on pathogenic bacteria. And so they went ahead. Three instruments were built. The first two were shipped to England (unwired as Hoyland wanted a trip to England) and the third went to Dr. Hamer M.D. at the Paradise Valley Sanitarium and Hospital. Dr. Hamer was the superintendent there I believe. Hoyland was like many men with whom I have associated over a period of years. In a short time he began changing the basic principles of these instruments according to his own ideas. About this time he became associated with Dr. Yale and Yale ordered and received another or the Fourth Frequency Instrument. Since I was out of the city or San Diego at the time, all of these devices were delivered without being tested by myself.*

At a much later period, I called on Dr. Yale at 333 Plaza in San Diego which was the address of his clinic at that time and told him that I did not feel that the Frequency Instrument had been calibrated

www.rife.org

properly so that it would not work. In the interim, I became associated with another electronist by the name of Verne Thompson, of San Diego. Under my supervision, Thompson rebuilt Dr Yale's Frequency Instrument which I tested in my research laboratory on pathogenic bacteria and the Frequency Instrument proved effective. Then later at different times I had this instrument checked and found it lacking in its ability to devitalize anything. I later learned that Dr. Yale had ideas of his own and would have somebody change the Frequency Instrument to suit his individual whims. I will state here definitely that I have never been associated in any way with Dr. Yale outside of the interest that I have taken in some of the patients of Dr. Yale." (Letter written by Dr. Rife, March 22, 1958).

www.rife.org

This document shows that Dr. Rife, after the shutdown of Beam Ray Corporation, eventually tested Philip Hoyland's Beam Ray Clinical design and found that it would devitalize all the microorganisms it was tested on. This also confirms that Philip Hoyland's statement that he tested it out in the laboratory was a truthful statement.

With this information taken from the Rife documents we now know why Dr. Rife considered the Beam Ray Clinical machine his instrument and knew it worked. Add to this the fact that all of the doctors who used it had a great deal of success with this Rife Ray #5 or Beam Ray Clinical instrument design. This is why Dr. Rife, John Crane and John Marsh built this Rife Machine in the 1950's and called it the AZ-58. The only difference in the 1953 AZ-58 design was it only had a three band switch which covered a lower audio frequency range. Other than this change the 1953 AZ-58 was a replica of Dr. Couche's and Dr. Tully's original Beam Ray machine. In a letter dated July 6, 1956 this fact was pointed out:

"The Frequency Instruments used by Dr. Tully and Dr. Couche were built in 1938 and do not apply to this code. However the Frequency Instrument currently built are a copy of these earlier Frequency Instruments and are labeled "For Investigational Use Only" at the present time." (Application letter for approval of device in compliance with California Pure Drugs Act. Page 2).

This information that we have just read which shows that the 1953 AZ-58 was a copy of Dr. Couche's machine has more importance than it appears. We will explain why. The 1953 AZ-58's audio frequencies, which it used, were 10 times lower than the audio frequencies used in Aubrey Scoon's instrument. This correlation is important because it shows a direct link to the original Beam Ray Clinical instrument built by Philip Hoyland. This correlation shows that Dr. Couche's instrument used audio frequencies 10 times higher than the 1953 AZ-58. It also shows that Aubrey Scoon's Beam Ray Clinical replica instrument is also a replica or copy of Dr. Couche's Machine. This information now ties all these instruments together and shows that the original audio frequencies which came from Philip Hoyland and used in the Beam Ray Clinical instrument were the same audio frequencies used in Dr. Couche's machine and Aubrey Scoon's machine. This information also shows that these original audio frequencies were later lowered and used in the 1953 AZ-58 built by Dr. Rife, John Crane and John Marsh. Now we can understand why this letter showing that the 1953 AZ-58 is a copy of Dr. Couche's machine is so important. It ties all these machines together.

Since we now know the history of this instrument and that this instrument worked on Dr. Rife's frequencies we will go back to the harmonic method used by Philip Hoyland. From the documents that we have read we know that Hoyland's machine worked on harmonics. The problem with the Beam Ray instrument is it has to be built a certain way in order for it to work on the correct harmonics. It was from the analyzing of this original Beam Ray Clinical instrument that the mystery of how it worked was discovered. We will show how it worked after we read another important quote. Bertrand Comparet, Rife's attorney who eventually defended Dr. Rife against Philip Hoyland in the 1939 Beam Ray trial said this about Philip Hoyland's Beam Ray Clinical instrument:

COMPARET: *"Well, none of us know enough about it. Now, I remember at that time Rife saying that Hoyland had not used a simple straight forward circuit, as Rife had used, but he thought he had a short cut, through use of harmonics and so on, and Rife had no faith in Hoyland's circuit".* (1970's Bertrand Comparet interview #28).

This statement by Bertrand Comparet and all the quotes we have read sums up Dr. Rife and his Beam Ray business partners understanding of how this instrument worked on harmonic frequencies. Anyone can see that only Philip Hoyland knew how this machine really worked and he would not reveal the secret to anyone.

This confusion of how the instrument worked still remained throughout the building of the 1940's and 1950's Beam Ray replica instruments and even up until the present day (2010). It appears from the Beam Ray Trial testimony that Dr. Rife and the other owners of Beam Ray Corporation really didn't know how this instrument worked. The trial testimony shows that Philip Hoyland would not tell anyone in the Beam Ray Corporation the frequencies used with the Clinical instrument or explain how it worked on harmonics. John Crane and John Marsh who worked with Dr. Rife didn't understand how it really worked either. If Dr. Rife had really known how it worked then he would not have allowed John Crane and John Marsh to have a variable RF carrier frequency in the instrument. Having a variable RF carrier, in and of its self, is not the problem. Having a variable RF carrier frequency would be a good thing as long as you also understand that the audio frequencies have to be correctly matched to the RF carrier frequency in order to produce Dr. Rife's higher harmonic M.O.R. frequencies. The problems came about because John Crane and John Marsh did not have this understanding. The reason why John Crane and John Marsh put a variable capacitor in the instrument was so that they could tune the RF carrier frequency in order to make the ray tube brighter. By doing this it also made it so they could change the RF carrier frequency from about 4.9 MHz to about 2.2 MHz. This change showed that they did not understand how the instrument worked. They mistakenly believed that the audio frequencies were the M.O.R.s. or the frequencies that would devitalize the microorganisms. They also mistakenly believed that the RF carrier frequency was not important. This belief shows without any doubt that they did not understand how the Beam Ray Clinical instrument worked. If they had really understood how it worked they would have never called any of the audio frequencies M.O.R.s.

At this point we need to explain a few things. Philip Hoyland had very good reasons why he wanted to hide how this new Rife Ray #5 machine worked. He became Dr. Rife's Engineer in 1935 when he built the Rife Ray #4. In 1936 Philip Hoyland also began building the Beam Ray Clinical instrument that would be sold in 1938 by Beam Ray Corporation. Philip Hoyland was worried about keeping the original frequencies a secret because he felt people would try to steal their technology. This concern of Philip Hoyland's was not unfounded because Mr. Parsons of the British Group did try to steal their instrument. From the trial transcript we learn they had no way to patent the instrument because everything they were doing was in public domain in regards to the frequency generating equipment. Even the frequencies themselves cannot be patented. Philip Hoyland felt that he had to come up with a way to keep anyone from finding out what the true frequencies were. So he built the instrument a different way using harmonics to hit the harmonic frequencies of the Rife Ray #4 and Rife Ray #3 Kennedy equipment. Until a genuine Beam Ray Clinical Rife Machine could be found and tested, we would never know for sure how Philip Hoyland generated and used the harmonics in his instrument. Even though we now know that Aubrey Scoon's instrument is a Beam Ray Clinical replica no one knew for sure that it really was a genuine replica when he obtained it. This confusion and the lack of having the chronological history of when and what type of instrument was built made it very hard to find the truth.

Not only would Philip Hoyland not tell anyone how his instrument worked he also would not let anyone know the new frequencies he was using. Everything he did hid the frequencies. In the Beam Ray Trial manuscript we read that he always used a code to give the frequencies. This code would work with the dials. No digital readout was available in those days like we have today.

Since no one was ever given the frequencies from Philip Hoyland this has led to many problems. Some of the later Beam Ray Clinical instrument replicas have different audio frequencies and this also has led to a lot of confusion. Even John Crane was sending people different audio frequencies other than the standard set he used with the 1953 AZ-58. Because of the different audio frequencies used in these Beam Ray replicas we really didn't know which set of audio frequencies Philip Hoyland really used. So it was not possible to use any of these frequency sets and come to any reasonable conclusions.

When we obtained this original Rife Ray #5 or Beam Ray Clinical Rife Machine, from Dr. Low, we had to put aside all the frequency lists and thinking of the past in order to figure out how the instrument worked. From everything we had read about Philip Hoyland’s instrument we had come to the conclusion that the answer would be found in the math. However Hoyland came up with his idea it had to be a mathematical method. Like many others we tried to reconcile the audio frequencies as lower harmonics of Dr. Rife’s original high RF frequencies. But this proved not to be the case. We tested the frequencies that were used in Aubrey Scoon’s Beam Ray Clinical instrument and they didn’t match either as harmonics of Dr. Rife's original frequencies. We did the same with the AZ-58 audio frequencies and they didn’t match. We took the other audio frequencies that Crane had a list of and they also didn’t match. There is an instrument known as the 1947 instrument which we tried to reconcile with no success either. With all these audio frequencies only a few were close harmonic matches. If all these audio frequencies were true harmonics of Dr. Rife’s original high RF frequencies then they should have harmonically match up, but they did not.

Once we put all this aside and began to analyze this instrument we found out how it worked. This Beam Ray Clinical instrument is truly a harmonic instrument and works on harmonic frequencies of Dr. Rife's original frequencies which he found. Philip Hoyland was telling the truth when he told Dr. Rife that the instrument was working on harmonics. The only thing was Philip Hoyland would not tell exactly how this was being done. The fact that both the audio frequency and the RF carrier frequency were sine wave did not make it easy to understand how it worked. How could it be a harmonic instrument when it used a sine wave waveform for both the audio and the RF frequencies? The 1953 AZ-58 Beam Ray Clinical replica worked on square wave audio frequencies and the harmonics came from the square wave waveform. But this is not how the Beam Ray Clinical instrument was suppose to work.

The 1950’s square wave method has been used ever since the 1950's. But how can an instrument that uses sine wave audio frequencies be a harmonic instrument? With this understanding we knew that the audio frequencies could never be the true M.O.R.s. But how did they work in the instrument to produce Dr. Rife's M.O.R.s? The harmonic square wave method has been an accepted method for many years. For many years almost everyone has understood and has generally accepted that you can take a square wave audio frequency and the harmonics it creates and hit a higher frequency M.O.R. through those harmonics. These audio frequencies are usually many hundreds of harmonic steps lower that the higher M.O.R. frequency. This harmonic method must be kept in mind as well as the fact that not once, but several times, in the Beam Ray Trial manuscript and other documents everything said about this machine showed that it was using the harmonic method. We must remember that Dr. Rife said that he believed that many of his frequencies were sub-harmonics of a higher frequency. He said if we knew the true higher frequency it may even work better. Because of how this instrument works it is logical to conclude that Philip Hoyland understood this concept and apparently found through testing that all of Dr. Rife’s frequencies were sub-harmonics of higher frequencies. With this understanding he built the Rife Ray #5 or Beam Ray Clinical instrument. Philip Hoyland was being truthful when he said that this machine was using harmonics. With all this knowledge from the Trial testimony and the Rife documents we how have a good understanding of the facts behind this new instrument design. Here is what we found when we analyzed the Beam Ray Clinical instrument.

www.rife.org

The graph, below on the left, is of the harmonics from the 3.80 MHz RF carrier frequency coming out from the ray tube of our original Beam Ray Clinical instrument. It was taken using a PicoScope 3205 spectrum analyzer. The first photo, below on the right, with the black waveform comes from Dr. Rife's 1936 lab film. The photo to the right of that photo is an oscilloscope reading that we took of the waveform of the Beam Ray Clinical Rife Machine. You will notice the similarity of the waveforms. All the M.O.P.A. (Master Oscillator Power Amplifier designs used by Philip Hoyland) RF carrier waveforms we have tested look like this. When you put a non harmonic sine wave into a ray tube you will always see a distortion of the sine wave which will produce both odd and even harmonics through the ray tube. This is the reason the sine wave looks distorted.




Photo one: From Rife's lab film.

Photo two: Beam Ray carrier before ray tube.

Photo one: From Rife's Lab film.

Photo two: Beam Ray carrier after ray tube.

The graph, below on the left, is of a pure 2000 Hertz sine wave frequency. The oscilloscope photo, below on the right, shows a 2377 Hertz sine wave waveform coming from the audio oscillator of the original Beam Ray Clinical Rife Machine. The small photo shows it after it goes through the ray tube. You will notice that it almost looks like a square wave, but it is not. The circuit creates this waveform.




Beam Ray sine wave audio frequency before circuit and ray tube.

Beam Ray modulated sine wave audio frequency after going through circuit & ray tube

The next two graphs we will look at are on the top of the next page. The graph, on the left, was before modulation. The graph, on the right, during modulation. When we modulated 40,000 Hertz on a harmonic sine wave 3.80 MHz RF carrier frequency this is what the PicoScope spectrum analysis showed coming out of the ray tube. This was interesting to see. Not only did it create sideband frequencies 40 thousand Hertz above and below the harmonic RF 3.80 MHz carrier frequency but it created many harmonic sidebands every 40,000 Hertz. These harmonic sidebands covered a large frequency range of hundreds of thousands of Hertz.

www.rife.org





Below are two more graphs showing a closer view of these sidebands that were created from one audio frequency. The graph, below on the left, is with a 50,000 Hertz sine wave frequency. The graph, below on the right, is with a 100,000 Hertz sine wave frequency. This was done with a harmonic sine wave 2.4 MHz RF carrier frequency so you can see a closer view of these sidebands. When we saw this we knew there was only one way this Beam Ray Clinical Rife Machine could work on Dr. Rife's frequencies and principles. We will now explain how Philip Hoyland's Rife Ray #5 or Beam Ray Clinical instrument worked using a fixed RF carrier frequency of 3.80 MHz and a variable audio frequency. Philip Hoyland knew from working with Dr. Rife that his frequencies or M.O.R.s. were subharmonics of true higher frequencies. Understanding this must have given him the idea of how to build the new Rife Ray #5 or Beam Ray Clinical instrument. If we also understand this concept, that all frequencies have lower and higher harmonic frequencies, is half the key to understanding how Philip Hoyland made this machine work. What Philip Hoyland did was multiply Dr. Rife's original M.O.R. frequencies up in harmonic steps until he had the highest harmonic frequencies closest to 3.80 MHz. From the Beam Ray Trial quotes we know that Dr. Rife was told by Philip Hoyland that this Beam Ray Clinical machine was working on his frequencies with harmonics. What Philip Hoyland would not do is clarify exactly how it was working on harmonics of Dr. Rife's frequencies. Philip Hoyland also stated that his frequencies were not the same frequencies as Dr. Rife's frequencies. He was being truthful when he said this but what he would not reveal is the fact that his frequencies were exact harmonics of Dr. Rife's frequencies.





To clearly explain how Philip Hoyland used Dr. Rife's frequencies to come up with his new frequencies which were to be used in the Rife Ray #5 or Beam Ray Clinical instrument we will use the Rife Ray #4 frequency for Streptothrix as an example. That frequency was 192,000 Hertz. Philip Hoyland multiplied 192,000 Hertz by 20 times which will give you the 20th harmonic frequency at 3,840,000 Hertz. Since the RF carrier frequency of the Beam Ray Clinical instrument was fixed at 3,800,000 Hertz the difference would only be 40,000 Hertz between the two frequencies. This method of multiplying Dr. Rife's frequencies up in harmonic steps and using those frequencies was an ingenious method used by Philip Hoyland. Even though this was an igneous method it is only half the mathematical equation. The second half of the mathematical equation is probably even more ingenious than the first part.

www.rife.org

Philip Hoyland then put into this Beam Ray Clinical instrument an audio oscillator. We must keep in mind that none of Dr. Rife's frequencies that were transferred from the Rife Ray #3 to the Rife Ray #4 and then to the Rife Ray #5 or Beam Ray Clinical instrument were audio frequencies. The audio oscillator was put into this instrument to accomplish the second half the mathematical equation. Using the audio oscillator all Philip Hoyland had to do was use an audio frequency of 40,000 Hertz. The 40,000 Hertz frequency would then create what are called sideband frequencies. These sideband frequencies would be created by the 40,000 Hertz both above and below the RF carrier frequency being used. The first upper sideband frequency would then be 40,000 Hertz above the RF carrier frequency and hit the harmonic M.O.R. frequency of Streptothrix at 3,840,000 Hertz. This method of using sidebands was the second half of the mathematical method used by Philip Hoyland in this Beam Ray Clinical instrument. Now for further clarification of these sidebands, as shown in the photo on the previous page, which extend out many times above and below the RF carrier frequency depending on the audio frequency which is used. They are like pickets on a fence and every picket represents a harmonic sideband created from the audio frequency. These harmonic sidebands are part of the harmonics that the Rife Ray #5 or Beam Ray Clinical instrument used. So Philip Hoyland took Dr. Rife's frequencies and multiplied them up in harmonic steps as close as he could get them to the fix 3.80 Megahertz RF carrier frequency. Then these new higher harmonic frequencies of Dr. Rife's original frequencies then became Philip Hoyland's new M.O.R. frequencies which he would not reveal to Dr. Rife or any of his Beam Ray Corporation partners. Next he then used harmonic sidebands to hit those new higher frequencies.

Though Philip Hoyland's new frequencies were harmonic frequencies obtained from Dr. Rife's original frequencies they did not create harmonics in the Beam Ray Clinical instrument. The harmonics came from the RF carrier frequency and the harmonic sidebands created from the audio frequencies, which Philip Hoyland used. By using both of these methods combined into and instrument Philip Hoyland could then say that the Rife Ray #5 or Beam Ray Clinical instrument was a harmonic instrument capable of outputting Dr. Rife's frequencies. His method was truly a harmonic method but he kept it as a secret form Dr. Rife and the other owners of the Beam Ray Corporation. The sideband method that Philip Hoyland used was the new cutting edge of electronic technology back in 1936. There would be very few people who could understand what Philip Hoyland was doing unless it was fully explain to them as we have explain here.

We will now explain Philip Hoyland's method further so that there can be no misunderstanding. But first what needs to be pointed out here is this IMPORTANT fact which came from the analyzing of this Beam Ray instrument. Neither the harmonic 3.80 MHz RF carrier frequency nor the audio frequencies will do anything by themselves. But when the harmonic 3.80 MHz RF carrier frequency and the audio frequencies are combined together they will produce many sideband frequencies. And one of these sideband frequencies will line up with the true higher harmonic Rife M.O.R frequency and devitalize or render harmless the harmful microorganism. To re-emphasize this so that no one misunderstands. If you just use the audio frequencies by themselves you will get nothing. If you just use the 3.80 MHz RF carrier frequency without the audio frequencies you will get nothing. The audio frequencies used in this instrument must have the RF carrier frequency of 3.80 MHz or they will not produce Dr. Rife's frequencies. This is the reason the 1953 Beam Ray Clinical instrument called the AZ-58 did not work properly. In that instrument they were only using the audio frequencies without correctly matching them to the RF carrier frequency. In other words they were not using the sideband method that Philip Hoyland originally developed to be used in this style of instrument.

We know that Philip Hoyland was trying to hide the true M.O.R. frequencies of the organisms from anyone who used the equipment. Twice in the Beam Ray Trial it was mentioned that Dr. Rife had no ability to patent the Rife Ray tube instrument. The only secret was the frequencies and Philip Hoyland was trying to protect his and Beam Rays interests. The third and final secret that Hoyland used to hide the M.O.R. frequencies will now be explained. Keeping the harmonic sideband method in mind

www.rife.org

Philip Hoyland could have just divided the 40,000 Hertz by two and used a 20,000 Hertz audio frequency. Then you would have one upper sideband at 3,820,000 Hertz and the second upper harmonic sideband at 3,840,000 Hertz. The 3,840,000 Hertz sideband would hit the 20th harmonic of 192,000 Hertz. Philip Hoyland could have divided it by three and used a 13,333 Hertz frequency. He also could have divided it by 4 and used a 10,000 Hertz frequency. If he would have divided it by five he could have used an 8,000 Hertz frequency. Divided by six he could have used a 6666 Hertz frequency.

We could go on but anyone can see the many variable frequencies that could have been used to create the correct sideband frequency. Also, because of the "one tenth of one meter" factor that Dr. Rife mentioned you could add a few Hertz to each frequency without changing the frequency enough to make it so it would not work. This means you could change the 6,666 Hertz to 6,669 Hertz just to make things a little more confusing. By using this method Philip Hoyland could use many different audio frequencies to produce which ever number of sidebands he wanted to use. This would make it impossible to figure out which sideband was hitting the M.O.R. frequency that would devitalize the organism. By using this new method of using higher harmonic frequencies of Dr. Rife's original frequencies and then using harmonic sideband frequencies Philip Hoyland was able to build a machine that would hide the frequencies from anyone. Philip Hoyland's method as anyone can see was ingenious.

We know that Philip Hoyland's method worked very well except that the technology of the mid 1930's did have a few drawbacks. Dr. Couche said that he had to sweep the frequency dial in order to get his instrument to work consistently. This is understandable since the 3.80 MHz RF carrier frequency will wander in a sweeping motion five hundred to one thousand Hertz up or down from the fixed RF carrier frequency. The audio frequency oscillator also varied. Bertrand Comparet in his 1970's interview said this about the Beam Ray Clinical instruments inherent frequency drift:

COMPARET: *"Well, as they warmed up they'd shift frequency...Now, whether this was Hoyland's inability to do better, or whether it was just inevitable in those days, I don't know, but Hoyland's devices did have that frequency shift as they warmed up. So, they had their problems. Now what Couche did, see, he would have cases where he would get an instantaneous cure, like that, and other times when the treatment just didn't produce any results, because of the frequency shift. So, he would start in, he had from Rife (Hoyland dial settings) a set of the frequencies for several different diseases and he would tune it deliberately to one side of that frequency and then gradually tune it across to the other side making sure that somewhere in the process he crossed the correct frequency, even if the instrument wasn't exactly in tune anyway. Well, when they hit the exact frequency they got amazing results."* (1970's Bertrand Comparet interview #10).





Again if you look at the first graph, above on the left, you will also notice that there are harmonic frequencies created from the 3.80 MHz RF carrier frequencies at 7.60 MHz and 11.40 Megahertz. These sideband frequencies as shown in the above graph, on the right, are created not only for the 3.80 MHz RF carrier frequency but its entire harmonics. These harmonics continue all the way up to

www.rife.org

about 12 MHz with reasonable power. This creates an interesting effect and shows that all the harmonics of 192,000 Hertz are being hit over the whole spectrum of about 12 Megahertz. This is probably why this Beam Ray harmonic instrument worked as well as it did, when they hit the correct frequency. This Rife Ray #5 or Beam Ray Clinical machine was definitely a harmonic instrument as Philip Hoyland had stated. It may have even exceeded Philip Hoyland's original concept.

Now going back to the audio frequency method of creating the sidebands that Philip Hoyland used. No one could ever determine the 20th harmonic frequency of 3,840,000 Hertz or the original Rife Ray #4 frequency of 192,000 Hertz using this method. The secret of the Beam Ray Clinical instrument and the frequencies that would devitalize the microorganisms could never be figured out unless you had the original Rife Ray #4 frequency of 192,000 Hertz. Only a spectrum analysis of this instrument made it possible to figure out what Philip Hoyland was doing. Without this modern technology a person would have to be very knowledgeable about how frequencies and their harmonics worked.

The fact that it has taken this long, almost 75 years, to figure out how this Rife Ray #5 or Beam Ray Clinical Rife Machine worked is proof enough that the secret was well hidden. As pointed out earlier, Philip Hoyland would never tell anyone how this instrument really worked. If anyone changed the 3.80 MHz RF carrier frequency then the audio frequencies would not work. New audio frequencies would have to be calculated to match the new RF carrier frequency. Also, Philip Hoyland could have changed the audio frequencies any time he wanted for any machine in order to confuse anyone who had the equipment. Since the instrument that we obtained from Dr. Low is an original Beam Ray Clinical instrument then one would assume that its 3.80 MHz RF carrier frequency is the carrier frequency that was used with all the Beam Ray Clinical instruments. But we know that this is not the case because they used a different carrier for other machines. None of the audio frequencies used in all the replica instruments from the 1940's to the 1953 AZ-58 match up to the 3.80 MHz RF carrier frequency. With this understanding we also have to assume that the audio frequencies used in this original Beam Ray Clinical instrument were different than the 1940's and 1950's instruments. Aubrey Scoon's instrument had a 3.30 MHz carrier frequency so if his machine is a replica of one of the original machines, which it is, then the audio frequencies would logically have to be matched to its 3.30 MHz carrier frequency, which they are.

The 1953 AZ-58 technical data shows that it used a 4.68 MHz RF carrier frequency. But when the variable capacitor was put into the AZ-58, in about 1956, the carrier frequency then became variable. This made is so Dr. Robert P. Stafford could change the RF carrier frequency to different carrier frequencies. In Dr. Robert P. Stafford's "Electromagnetic Field Therapy" report he said the following about the carrier frequency they used on his patients with the 1953 AZ-58:

DR. STAFFORD: *"Radio Wave transmission is used as a carrier wave. We use between 3100 KC [3.10 MHz] and 3300 KC* [3.30 MHz] *(This does not appear to be a critical value). The carrier wave is modified with specific cycles per second modulations. We believe that the CPS [audio frequencies] is a critical value and it actually may prove to be the most important factor which this research may offer."*

You will notice that Dr. Stafford did not think that the RF carrier frequency was critical. He clearly states that they believed it was the "CPS" or cycles per second of the audio frequencies which were the most important part of making the AZ-58 work. If the AZ-58 was going to work on the sideband method that Philip Hoyland developed then the RF carrier frequency and the audio frequencies had to be correctly matched. John Crane and John Marsh at this time also did not think that the setting of the carrier frequency was important to make the instrument work properly. Dr. Stafford would have gotten his understanding from them. We now know that the proper setting of the carrier frequency was important. The audio frequencies used with the AZ-58 should have been recalculated to match its 4.68 RF carrier frequency because its carrier frequency was different than Aubrey Scoon Beam Ray replica instrument carrier or our original Beam Ray Clinical instrument carrier frequency. When the math is done to check

www.rife.org

the sidebands with the audio frequencies that were used with the AZ-58 it shows that those audio frequencies will not create the correct sideband spacing which will match up to the harmonic Rife Ray #4 frequencies. This is probably why Dr. Robert P. Stafford could not get the AZ-58 to devitalize any of the microorganisms he was testing in the laboratory. Here are two of his statements:

DR. STAFFORD: *"Please excuse my format in the following letter for I intend to ramble a bit and forget strict grammatical dictum. I am writing you at this time partially because John Marsh informs me in a recent letter that you may be somewhat disheartened or at least worried about your role in the experimentations with the Rife Machine. Believe me, Dr. Edward I know how you feel for I too have been through this same feeling with this matter. I have observed clinical results after treatments with this gadget which I can scarcely believe myself. Yet, despite these good results, I have been confused by some rather simple failures such as a recent experiment which I conducted at Good Samaritan Hospital where we used the machine to treat some cultures of Staph Aureus and Strept. Fecalis. In this work we failed to inhibit growth at all or influence the cultures with the Rife Rx. I sent the results to John Marsh and asked for clarification and to be very frank I am not satisfied with John's excuse of the failure as described by Dr. Rife. I am afraid I'm not a very good apostle for I'm getting some ideas myself on how this thing may work. I really wonder if this ultrasonic kills bacteria and virus at all or does it work like other forms of ultrasonic and merely stimulate the tissue in some unusual manner thereby improving the circulation and secondarily enhancing the body's defenses against infection…To summarize some of this rambling: I feel that the Rife Ultrasonic Therapy has a very definitely beneficial effect on the human (and canine) body...I furthermore feel that we, as doctors of medicine, using this machine must remain constantly alert to the condition of our patient and vary the Rx as indicated." (*Dr. Stafford letter to Dr. Jeppson April, 1 1958).

DR. STAFFORD: *"As yet, we have failed to "cure" any case of advanced, terminal malignancy. It appears in several instances that we may have impressed the disease favorably, temporarily. It is difficult to rule out the psychological, morale booster effect to the terminal patient when some definitive effort is made again in his behalf. However, several improvements have appeared to be more physical than emotional...All the patients in the series were treated with the same frequencies (e.g., 728 - 784 - 880 - 2008 - 2128). Perhaps these frequencies may be wrong, or only nearly correct."* (John Marsh Collection, Dr. Stafford's Report on using the AZ-58, page 4, www.rife.org)

If the incorrect audio frequencies were used with the 3.10 MHz to 3.30 MHz RF carrier frequency what Dr. Stafford M.D. reported is exactly what would have happened. From Dr. Stafford's statement we know that he did not think the RF carrier frequency was critical. If Dr. Rife had fully understood how Philip Hoyland had designed the instrument he would have never allowed John Crane or John Marsh to put a variable capacitor in its circuit without recalculating the audio frequencies for the new RF carrier frequency they wanted to use. Also they would not have lowered the original audio frequencies by a factor of 10 times and used them. The AZ-58 would have had a new set of audio frequencies correctly match to the new 4.68 MHz RF carrier frequency it was originally given in 1953. The new set of audio frequencies would then have been the correct audio frequencies that would create the proper sideband spacing. Dr. Rife would have also made sure that Dr. Stafford knew that the carrier frequency was critical. If John Crane and John Marsh really understood how this instrument worked they never would have wanted to change the 4.68 MHz carrier frequency. The 4.68 MHz RF carrier would have been a good carrier frequency if they would have used the correctly matched audio frequencies.

It is obvious they never really understood how the instrument worked or how the audio frequencies interacted with the carrier frequency to produce the M.O.R.s. which would devitalize the organisms. They, like us, were under the false belief that the audio frequencies they were using were the M.O.R.s. They unknowingly promoted this idea because Philip Hoyland would never tell anyone how the instrument worked. We know that Dr. Rife knew that this Beam Ray Clinical machine somehow

www.rife.org

worked on his frequencies with harmonics but it is apparent that no one but Philip Hoyland really understood how the instrument worked on the harmonic sideband method.

With the new variable capacitor that John Crane and John Marsh put into the AZ-58 they could change the RF carrier frequency from about 2.40 MHz to about 4.90 MHz. Dr. Stafford told me personally, when I talked to him, that it did not make any difference which carrier frequency he used, they all worked the same. We will probably never know the full story of how these mistakes were made but it is obvious that no one but Philip Hoyland had the proper understanding of how the instrument worked. Since the AZ-58 used the square wave harmonics method rather than the harmonic sideband method it would have been better if Dr. Rife, John Crane and John Marsh had used a true lower harmonic frequency of the Rife Ray #4 frequencies, but they didn't. Using the correct sub-harmonic audio frequencies derived from the higher Rife Ray #4 RF frequencies would have been a better approach. Those Rife Ray #4 sub-harmonic audio frequencies used with the square wave harmonics method, probably would have worked better than the incorrectly match 1950's audio frequencies they were using in the AZ-58. We should do the same today with our frequencies.

All that we have discovered with the analyzing of this original Rife Ray #5 or Beam Ray Clinical instrument reveals that the audio frequencies used with this equipment are not Dr. Rife’s true M.O.R.s. They are just the frequencies needed to produce the proper sideband spacing in order to hit the correct higher RF harmonics of Dr. Rife’s original M.O.R. frequencies. If the audio frequencies were the frequencies that would devitalize the microorganisms then logically all Dr. Rife’s frequencies would have been audio frequencies, but they are not. If these audio frequencies were Dr. Rife’s true M.O.R. frequencies then an RF carrier frequency would not have be needed and he would have never even needed to build a Ray Tube instrument. Dr. Rife would have been able to do all of his work with a simple frequency generator that would have had a frequency range of only about 25,000 Hertz. But this is not the case. Dr. Rife always said that almost all his frequencies were in the upper bands which match the Rife Ray #4 frequencies which covered a frequency range from 139,200 Hertz to 1,604,000 Hertz. None of those Rife Ray #4 frequencies where audio frequencies.

It is interesting to note that this Rife Ray #5 or Beam Ray Clinical instrument did not have a dedicated fixed audio pulsing circuit. This is also the case with the 1953 AZ-58. Aubrey Scoon mentions a sixty Hertz feedback pulse into the circuit of his instrument but he could not determine if the instrument was intended to work this way or if it was just a malfunction. When we built his instrument we could not get our instrument to work in the same manner as his did in producing this feedback, therefore we believe that it most likely was malfunctioning and was not intended to work in that manner. Since this original Rife Ray #5 or Beam Ray Clinical Rife Machine that we obtained didn’t work in this manner either and none of the other replica instruments work this way we believe that our conclusion is correct.

We know that Dr. Rife’s high RF frequency instruments such as the Rife Ray #3 and Rife Ray #4 used a fixed audio frequency pulsing circuit. This fixed audio frequency modulated the high RF frequency and was used to devitalize the organism. We have shown already in this report that this pulsed waveform was needed to devitalize the various microorganisms that Dr. Rife tested. The Beam Ray Clinical instrument did not use this circuit. The logical reason why it did not us this circuit is the modulated waveform created from the variable audio oscillator must have been sufficient to create the effect. The variable audio frequencies, which created the sidebands, would also pulse the waveform and this must have been sufficient to accomplish the same result. From this we can conclude that all that is needed is a modulated or pulsed waveform with the proper M.O.R. high RF frequency to devitalize microorganisms.

www.rife.org

In the photo, shown below, is the Rife Ray #5 or Beam Ray Clinical instrument waveform. It looks almost like a modulated square wave waveform but it is not produced with a square wave. This waveform is produced using a sine wave audio frequency.



The Beam Ray instrument uses sine wave audio frequencies modulated onto a sine wave RF carrier frequency. It is the unique design of the Beam Ray Clinical circuit that produces this waveform. The M.O.P.A (Master Oscillator Power Amplifier) circuit that Philip Hoyland used was built in a different manner than would normally be used. Instead of using one vacuum tube for the RF oscillator section and a second vacuum tube for the amplifier section he only used one vacuum tube for both sections.

Because he used only one vacuum tube the circuit over oscillates and shuts off for half of the cycle. This shutting off for half of the cycle makes the waveform look almost like a square wave. This new waveform replaced the damped wave waveform that was used in the Rife Ray #4 instrument. In the 1953 AZ-58 Beam Ray Clinical instrument the variable sine wave audio oscillator was replaced with a variable square wave audio oscillator. Had they really understood how the AZ-58 instrument was really supposed to work on the harmonic sideband method they probably would not have made this change. Changing the waveform from sine wave to square wave did not change how the harmonic sidebands worked in the AZ-58. It only shaped the waveform in a true square wave waveform. The only real change that could affect the output of the instrument is not matching the audio frequencies with the new 4.68 MHz RF carrier frequency. It was this change that proved to be the biggest mistake they made.

What must be kept in mind is the treatment frequencies were not the audio frequencies in the original Beam Ray Clinical instrument. It was the sideband frequencies created by the audio frequencies when match and combined with the 3.80 MHz RF carrier frequency that would create the M.O.R. treatment frequencies. We tested both sine wave and square wave with the spectrum analyzer and there was no change in the sidebands. But in the 1950's they were under the false assumption that the audio frequencies were the treatment frequencies.

Variable Audio Frequencies

Now we will discuss the variable audio frequencies used in the Rife Ray #5 or Beam Ray Clinical instrument. When we figured out how this instrument worked on harmonic sidebands we did not choose the optimum audio frequencies. We just used audio frequencies that would show how the instrument worked. There are better audio frequencies that could be used for optimum performance to hit the Rife Ray #4 higher harmonic frequencies. In order to determine the audio frequencies that were used to create the sideband spacing frequencies we first had to determine the difference between the 3.80 MHz RF carrier frequency and Hoyland's new higher harmonic M.O.R.s. which were derived from

www.rife.org

Dr. Rife's original frequencies. In order to make it easier for the reader to understand the difference between the RF carrier frequency and Dr. Rife's higher harmonic frequency will be call that the "difference number" in this report. In most cases we divided, the difference number, by 5 but the BX was divided by 15. The BX M.O.R. higher harmonic frequency, based on the Rife Ray #4 frequency, is 3,208,000 Hertz. This frequency is only the second higher harmonic of the Rife Ray #4 frequency of 1,604,000 Hertz, so it will still work just as well as all the other frequencies.

www.rife.org

One must keep in mind that the modern square wave audio frequency harmonics are projected to hit frequencies hundreds of harmonics up. This Beam Ray instrument has far more power in its harmonic sidebands than any square wave harmonic has in it. And the Beam Ray instrument only has to go to the 15th lower sideband to hit the BX M.O.R. frequency, not hundreds of harmonics like a square wave harmonic would. This Philip Hoyland method would be far superior to using low square wave audio frequencies since the harmonics would all be 40 harmonic steps or less.

So that you can better understand how this instrument worked we need to determine what RF carrier frequencies would be best to use with this Beam Ray Clinical instrument. Philip Hoyland would have also done these calculations back in the 1930's. The best RF carrier frequencies to use would always be calculated based on Dr. Rife highest original M.O.R. frequency. As an example the highest frequency that Dr. Rife used in the Rife Ray #4 was the BX cancer virus frequency of 1,604,000 Hertz. The best RF carrier frequency would be this 1,604,000 Hertz frequency multiplied by two which would be 3,208,000. So an RF carrier frequency in the 3.10 to 3.30 Megahertz range would be a good RF carrier frequency range. Dr. Couches' Rife Ray #5 or Beam Ray Clinical instrument, built by Philip Hoyland, used an RF carrier frequency of 3.30 MHz and Aubrey Scoon's instrument which is a copy of it also used a 3.30 MHz carrier frequency. The importance of this 3.30 MHz RF carrier frequency will be discussed later. The next best carrier frequency would then be three times this frequency which would be 4,812,000 Hertz. So a carrier frequency in the AZ-58 4.68 MHz range would also work very well. By using Dr. Rife's highest M.O.R. frequency it is easy to see that the best RF carrier frequencies can be determined. We are sure that Philip Hoyland had this same understanding.

Some of the following information was originally part of Chapter 8 but after restudying the Rife documents we found that this information, including the additional documents we found, actually belonged in this chapter. This information confirms Philip Hoyland's use of higher harmonic frequencies obtained from Dr. Rife's original M.O.R. frequencies.

When Dr. Johnson and Philip Hoyland were testing the first proto-type of the Rife Ray #5 or Beam Ray Clinical instrument in the summer of 1936 they had an interesting effect take place. At that time they were at Dr. Johnson's laboratory testing different bands of frequencies on the various microorganisms. Dr. Johnson wrote about what happened at his laboratory in a letter he sent to Dr. Gruner and Dr. Rife on November 4, 1936:

DR. JOHNSON: *"Last summer, in hunting for the M.O.R. for the other two reproductive forms of the cryptomyces pleomorphia, we ran into a new band of oscillations which introduced itself to us by killing all three forms - those that we called BX, our filter-passing form; then a transitional form such as you found in the monocytes in the blood; and then the third or highly developed form coming from the sporangius forming from the hyphas of the mycelium. At the same time that this new wave band arrived, we broke all the glass in the laboratory of a certain shape, not only in the room where we were working but in all the other rooms...we had been troubled a great deal with a mold because in the microscope room there were no windows, but this band not only destroyed that mold, which was growing on the leather objects in the room, but every bacteriological culture that we had in the laboratory! It cleaned us out completely so we had to start from scratch and replace our losses. In fact, we were all so surprised that we began to feel each other's pulses to see if we were still alive. As no harm had been done to us, we proceeded to test the new band out on mice, rats, rabbits, guinea pigs and dogs. So far as we were* *able to discover, it is not at all destructive or injurious to normal cell tissue. While we have been forced to modify our machine so as to produce this new band, still it is so much more effective clinically that we look upon it as a very advantageous discovery. However, our experience has forced us to do all of our experimenting with the new ray* [Rife Ray #5 or Beam Ray Clinical instrument] *completely outside of our laboratory building or abandon all form of bacteriological experiments, because it instantly kills them all."* (Letter from Dr. Johnson to Dr. Gruner (copy sent to Dr. Rife) dated, November 4, 1936).

Dr. Johnson clearly points out in this letter that this was done with a new Rife Ray. Dr. Johnson had been using the Rife Ray #4 since the fall of 1935 on his patients but here he points out that they were using a new Rife Ray machine and that it was clinically more effective than the machine he had been using up until this time. In the Beam Ray Trial documents Philip Hoyland stated that he had built a new Rife Ray instrument in the summer of 1936: (Beam Ray Trial Transcript #956)

HOYLAND: *"In the summer of 1936 I designed a new machine, or rather I checked it there at the lab. I had designed it in Pasadena, and we tested it out then."* (Beam Ray Trial Papers #956).

Also in another document called "Development of the Rife Ray" we have supporting evidence that a new Rife Ray was built in 1936:

"In the early part of 1936 Commander Rife and Mr. Hoyland spent much time collaborating on revising some of the applications of the fundamentals of the instruments due to the advancement that had taken place in the application of electronics and it was found that the carrier wave used in the previous instruments could be eliminated. During the summer of 1936 further experiments were carried on, which resulted in an entirely new method of generating the desired frequencies and produced a constant input and output in the instruments."

With the Rife documents showing that Philip Hoyland built the new Rife Ray or Beam Ray Clinical instrument in the summer of 1936 we know that this was the machine that Dr. Johnson was referring to in his letter. In that letter Dr. Johnson clearly states that during the summer of 1936 they had tested this new machine in his laboratory. Dr. Johnson's statement also confirms Philip Hoyland's statement given in the Beam Ray Trial documents that the machine was tested in the laboratory. The documents all support each other and show that it was the Rife Ray #5 or Beam Ray Clinical instrument that they were using which produced this amazing effect. In this same letter Dr. Johnson stated, not once, but twice that this work was done with the new Rife Ray machine. Here is his other statement:

DR. JOHNSON: *"I can assure you that no one, not even myself, could help but be astounded at the results we are now obtaining with the assistance of our new machines and our new band of MOR's."*

This letter was written in November of 1936 a few months after the laboratory testing was completed on this new Rife Ray machine. They now had built more than one of these new machines as pointed out by Dr. Johnson when he said "our new machines." Again Dr. Johnson points out that this is a new style of machine and it has a "new band of MOR's." In the Beam Ray Trial documents Philip Hoyland's complete statement reveals that he was using different frequencies than Dr. Rife:

HOYLAND: *"In the summer of 1936 I designed a new machine, or rather I checked it there at the lab. I had designed it in Pasadena, and we tested it out then and the frequencies were not the same as on Dr. Rife's machine."* (Beam Ray Trial Papers #956).

This statement made by Philip Hoyland about the frequencies not being the same as Dr. Rife's original frequencies is confirmed by Dr. Johnson. So Dr. Johnson's statement in his letter clearly shows that he understands that this new machine is using different M.O.R.s. than what Dr. Rife was originally

www.rife.org

using in the Rife Ray #4. Dr. Johnson also points out that these new M.O.R.s are more effective than the original M.O.R.s found by Dr. Rife. Today we now know that these new M.O.R.s. that Philip Hoyland was using were based on Dr. Rife's original M.O.R.s. They were just higher, more powerful, harmonics of Dr. Rife's original frequencies. From the Beam Ray Trial we know that Philip Hoyland stated that the frequencies he was using in this machine were not the same as the frequencies that Dr. Rife originally found. This however does not change the fact that all Philip Hoyland did was multiply Dr. Rife's original frequencies up in harmonic steps to use them with this new Rife Ray #5 or Beam Ray Clinical instrument. Without Dr. Rife's original frequencies Philip Hoyland would have had nothing. Probably the most important fact is the higher harmonics seemed to work better at devitalizing the organisms. As mentioned before, Dr. Johnson indicates in his letter that this new machine works better than any of the previous machines they had used up until that time (Rife Ray #3 and Rife Ray #4). His letter also shows that he is very impressed with the results they were obtaining with it. Another important fact we learn from this letter is Dr. Johnson now had the M.O.R. for the cryptomyces pleomorphia fungi. He had been trying to get Dr. Rife to find this M.O.R. for many months, without success, because Dr. Rife had developed eye problems and could not use his microscope. But now he had the ability to produce its frequency with the new machine. Another thing that Dr. Johnson pointed out was the fact that they had killed all the bacteriological specimens in his laboratory with the new Rife Ray machine and that they had to use it outside of the laboratory or it would kill all the new replacement specimens they had to obtain.

Dr. Johnson in this same letter to Dr. Gruner said the following about this new Rife Ray machine which Philip Hoyland built:

DR. JOHNSON: *"We are having a great time out here. I have opened a clinic in the Pasadena Home for the Aged and am having excellent luck. Of course, what I am trying to do is to experiment with the effect of the Rife Ray on bacteria in vivo. Our laboratory work has demonstrated pretty conclusively what it will do in vitro. The clinic is held three mornings a week, Tuesday, Thursday and Saturday. Yesterday I had eighteen patients. Among them were two cases of pulmonary tuberculosis, three cases of carcinoma, two cases of old chronic varicose ulcers of the leg, and sundry other cases of more or less definite infectious origins…I certainly wish that you were here to work with me because I am afraid that even you, who know what we are trying to do, will not believe some of the yarns that I would have to tell you as to what is occurring in the clinic without actually seeing them for yourself."* (Letter from Dr. Johnson to Dr. Gruner (copy sent to Dr. Rife) dated, November 4, 1936).

Many people believe that Philip Hoyland's Rife Ray #5 or Beam Ray Clinical machine was somehow inferior to Dr. Rife's previous instruments in effectiveness in devitalizing microorganisms. But Dr. Johnson points out that this instrument was working better than any previous instrument they had used in the past. In another letter to Dr. Meyer, M.D. Dr. Johnson again talks about the effectiveness of this new Beam Ray Clinical machine:

DR. JOHNSON: *"I am conducting a very interesting clinic three times a week with the Rife Ray, treating about twenty two patients a session, and we are obtaining much valuable information from our work. We are encountering many physical problems in the production of the Ray, the greatest difficulty being to obtain uniform results from the apparatus which we have. At times the results of the Ray are absolutely astounding, causing an instantaneous sterilization of the wounds whether interior or exterior. But owing to the slight changes in the temperature of the room and apparatus, the same setting of the dials does not give us the same output, and hence our results are unsatisfactory. However, we believe now that we have developed it to a point where we can very greatly diminish the errors in output and substantially increase the beneficial results or the effect of the apparatus."* (Letter from Dr. Johnson to Dr. Karl F. Meyer dated, December 7, 1936).

www.rife.org

Even with the calibration problems with the instrument Dr. Johnson was still impressed with how well the instrument was working. If Dr. Johnson only would have had the ability that we have today to measure the frequency correctly, rather that relying on dial settings, he would have always had consistent results. With modern technology we can accurately measure a frequency regardless of any changes that the climate may make. Dr. Johnson only had the dial settings to work with back in the 1930's. The limits of the 1930's technology would have given him the problems he talked about in his letter. Even with the limits of the 1930's technology Dr. Johnson stated they had solved many of their problems with the instrument and this helped them to obtain even better results.

During this same clinic which Dr. Johnson was conducting he was also using this new Rife Ray on 30 cataract patients. In a letter that Dr. Johnson wrote to Dr. Joseph Heitger he stated the following:

DR. JOHNSON: *"I closed my clinic on May 28, having been running it for eight months. Our special effort this past winter has been working on cataracts, and while we have treated a number of other infectious conditions (if cataract is an infection), still our principal work has been on the eye. We have had about thirty cases of cataract...Every case that we have treated, with the exception of one which was a traumatic cataract where the lens was absolutely opaque and of recent origin, has been benefited...The application of the Rife Ray as we have used it , does, in the great majority of cases restore the full visual function of the eye; that is, that portion of the visual disturbance due to opacities in the lens. How it does it and why it does it, I do not know, but the above statement is an actual fact, supported by many cases…Oh Lord; How I wish we could get together and go over this work! I believe it will result in epochal changes in the profession's handling of cataract cases."* (Letter from Dr. Johnson to Dr. Joseph D. Heitger dated, June 1, 1937).

In this letter to Dr. Heitger, Dr. Johnson again points out how well this instrument worked. In this letter he also talked about the calibration problems they were having with this new Rife Ray machine. The Beam Ray Clinical machine was known for its calibration problems. Even the Beam Ray Trial testimony and other documents show that this instrument had calibration problems. Eventually Philip Hoyland divided the audio frequency range of the Beam Ray Clinical instrument into four bands. This helped but did not solve the problems completely. By the early 1940's the audio oscillator was replaced by the new stable Hewlett Packard audio oscillator. This Hewlett Packard audio oscillator was far superior to the original RC (Resistor Capacitor) style audio oscillator used by Philip Hoyland. Had they had a modern frequency counter they could have easily solved any of the calibration problems they had. Today if anyone builds this instrument they would want to have the ability to check the RF carrier frequency so that they will have consistent results.

Next we will explain how this instrument had the ability to devitalize so many organisms as described by Dr. Johnson in his letter. He stated in his letter of November 4, 1936 that it was done using a "new band of oscillations." This happened at the time they were testing this new Rife Ray #5 or Beam Ray Clinical instrument at Dr. Johnson's laboratory. Since it was a proto-type machine we do not know what the original frequency range of the audio oscillator was when this happened. What we do know is the original Beam Ray Clinical instrument which we obtained from Dr. Low had four frequency bands which covered a frequency range from 160 Hertz to about 42,000 Hertz. Whether it was one of the lower bands or one of the higher bands we do not know. But this we do know, Dr. Johnson would have had this band put into the new instrument because he stated this:

DR. JOHNSON: "*While we have been forced to modify our machine so as to produce this new band, still it is so much more effective clinically that we look upon it as a very advantageous discovery."* (Letter from Dr. Johnson to Dr. Gruner (copy sent to Dr. Rife) dated, November 4, 1936).

www.rife.org

This statement from Dr. Johnson leaves no question that this band of oscillations was included in the new Rife Ray machine which eventually became the finished product that was sold by Beam Ray Corporation. Why this new machine was able to kill all the organisms that Dr. Johnson talked about is easy to explain since we now know how this instrument worked. If you look at the spectrum analysis graph, shown below, you can see the many sideband frequencies created by a single audio frequency.



It has been said that a "picture is worth a thousand words." From this spectrum analysis graph of the Beam Ray Clinical machine we know it produced many sideband frequencies simultaneously, sometimes over 100. This explains how this effect happened. Dr. Johnson did not say that it was a single frequency that killed the organisms. He stated that it was a band of frequencies. By the word “band” we know that they must have been turning the frequency dial of the audio oscillator looking for a frequency that would kill the “two reproductive forms of the cryptomyces pleomorphia” organism. These two forms of this disease were found to be a factor in cancers and Dr. Johnson wanted the M.O.R. for these organisms. If the dial of this instrument was turned slowly, as they would have done, then they would have be sweeping the frequency. Even though you are only sweeping a single audio frequency you are also sweeping as many as 100 harmonic sideband frequencies simultaneously which were created by a single audio frequency. For an example we will explain how this works. It must be kept in mind that if you sweep an audio frequency in the Beam Ray Clinical instrument from 6000 Hertz down to 500 Hertz all of the RF sidebands produced from the RF carrier frequency will start with a distance of 6000 Hertz apart and as you sweep down to 500 Hertz these sidebands will slowly close until they are only 500 Hertz apart. During this sweep every frequency between these sidebands will be hit because these sidebands are also all going in towards the RF carrier frequency.

Not only are the sidebands closing and getting closer together but they are also moving in towards the RF carrier frequency completely overlapping each other. Both the upper sidebands and the lower sidebands produced by the audio frequency close in towards the RF carrier frequency. This produces a large broadband sweep, with these many sideband frequencies, that can cover up to a one Megahertz or one million Hertz frequency range. This instrument would be very advantageous to use on patients but in a laboratory setting it would be your worst nightmare because it could very easily kill all your specimens as described by Dr. Johnson:

DR. JOHNSON: "*experience has forced us to do all of our experimenting with the new ray completely outside of our laboratory building or abandon all form of bacteriological experiments, because it instantly kills them all.*"

We know that Philip Hoyland used at least two different RF carrier frequencies, 3.80 MHz and 3.30 MHz, with his Beam Ray Clinical instruments. We also know from the Rife documents that Dr. Couche's Beam Ray Clinical instrument RF carrier frequency was set to 3.30 MHz. The audio frequencies went from 1200 Hertz for Tetanus to 21,275 Hertz for the BX Cancer virus. These audio frequencies produced the correct sidebands which hit the correct frequency for each organism. It is easy to understand that if all of Dr. Rife's frequencies for the various organisms are covered over this range from 1200 Hertz to 21,275 Hertz then a slow sweep over this range would cover all the organisms' M.O.R.s. or frequencies. It is also logical to conclude that if any organism's frequency is located between about 40,000 Hertz up to about 1.80 MHz it would also be hit at some point during this sweep. This is because any organism's frequency could be multiplied up in harmonics so that it would be as close to 3.30 MHz as you can get. With this understanding it would also be logical to assume that a sweep through that complete frequency range down to about 500 Hertz would cover all Dr. Rife's M.O.R. frequencies both known and unknown. During the Beam Ray Trial it was pointed out that Dr. Rife had found the M.O.R.s. for about 40 more organisms that were not included in the Beam Ray Clinical Machine. Here is that statement:

HUTCHINSON: *"There are about 40 frequencies discovered by Dr. Rife that have not yet been released to the public, and have not been included in the machine."* (Beam Ray Trial Papers #1689)

Those 40 frequencies could have been put into the Beam Ray Clinical machine had Dr. Rife understood how Philip Hoyland built the machine using the sideband method. Though they were never put into the instrument using a dial setting this does not change the fact that the instrument could output those frequencies. Since they probably all would have been within this same sweep range then it is reasonable to assume that this same sweep range would also hit all of these organisms' frequencies. This is why we said *"All Rife's M.O.R.s. both known and unknown."*

If you wanted to cover an even larger frequency range you could sweep from 40,000 Hertz down to about 100 Hertz. The mathematical calculations show that to hit each organism's M.O.R. with sufficient time a sweep should not cover more than 25,000 Hertz in 4 hours. One important fact that should be realized is when this sweep is done from 25,000 Hertz down to about 500 Hertz, or lower, each organism's frequency is hit more than 20 times. To understand how this is possible requires the understanding that when these sidebands close and move in toward the carrier frequency each organism's frequency is hit with multiple sidebands. To explain how this happens we will take the BX Cancer virus frequency of 21,275 Hertz as an example. It is the fourth lower sideband that first hits the BX Cancer virus frequency of 3,214,900 Hertz (1,607,450 X 2 = 3,214,900) when it hits 21,275 Hertz. The fifth lower sideband again hits 3,214,900 Hertz at 17,020 Hertz. The sixth hits it at 14,183 Hertz and the seventh at 12,157 Hertz. This continues on until each organism is hit by more than 20 sidebands.

What has just been explained is why Dr. Johnson had the experience of this instrument killing all the organisms in his laboratory. Just a sweep through one of these four frequency bands with the Beam Ray Clinical instrument could wipe out a great many organisms because the sidebands would hit many organisms' M.O.R.s one right after another. This is because there can be nearly 100 sidebands generated at the same time.

www.rife.org

The reason we did not make a schematic for this original Beam Ray Clinical instrument is due to the fact that Aubrey Scoon's Rife Ray #5 or Beam Ray Clinical replica schematic is available and will build the same type of instrument. Aubrey Scoon's instrument carrier frequency has been discovered even though his instrument was malfunctioning or had parasidic oscillations. He originally gave a 3.33 MHz carrier frequency using an 812a tube. Then he made the wrong assumption and used an 809 tube and replaced the 812a with the 809, but this did not eliminate the parasitic oscillations. The problem with the instrument malfunctioning is what made it hard to determine the true carrier frequency. Without having the correct RF carrier frequency it makes it very hard to verify the audio frequencies it used. Having done a lot of work with this style of instrument and knowing how harmonics can shift the carrier frequency we decided to test a 3.30 MHz carrier to see if it was the correct frequency it used. This 3.30 MHz carrier frequency would have been a more logical choice to use especially when it comes to making the correct sideband frequencies. The results of that decision will be shown later when we take a look at Aubrey Scoon's 1940's (actually 1950's) Beam Ray Clinical replica instrument built by Verne Thompson.

On the next page is a chart showing the "Rife Ray #4 Frequencies" with their "Higher Harmonic Frequencies" along with the "Carrier Difference Frequencies" and the "1/10 tenth Of One Meter" mentioned by Dr. Rife, converted to Hertz. Also included in this chart are "Beam Ray Clinical Frequencies" which are audio frequencies that would work with the Beam Ray Clinical instrument. It also includes "Aubrey Scoon's Frequencies" for a comparison even though we have not yet examined Aubrey's Beam Ray replica machine. After you have read about Aubrey Scoon's instrument this information will be even more understandable.

You will notice in the chart on the next page that many of the Beam Ray Clinical instrument audio frequencies, when divided with some numbers are very close to the audio frequencies used by Aubrey Scoon's Beam Ray instrument. It is easy to see the correlation between these two machines and the sideband method used by Philip Hoyland to hit the proper high frequency M.O.R. harmonics of the Rife Ray #4 frequencies. There could be many more audio frequency sets depending how you divide the "*Carrier Difference Frequencies." The best audio frequency set would be a list with the highest frequencies so that you have the lowest number of sideband harmonics. The reason for this is power loss: the more sidebands the less power in each sideband. The power loss after about 40 sidebands is so great, when looking on a spectrum analyzer, it is doubtful the sideband frequencies would work.

As mentioned before the higher the audio frequency used the more power there is in the sidebands. For this reason we have put in the chart, shown below, a list of the optimum Beam Ray Clinical instrument audio frequencies to be used with a 3.80 MHz RF carrier frequency and a 40,000 Hertz audio oscillator. We did this since this original Beam Ray Clinical instruments oscillator went to just over 40,000 Hertz. This would give the lowest number of sideband harmonics and the greatest power in each sideband.

Beam Ray Clinical Instrument Sideband Sine Wave Audio Frequencies			
Anthrax	20, 800 Hz	Streptococcus	33,333 Hz
B or E Coli Rod	23,500 Hz	Steptothrix	40,000 Hz
B or E Coli Virus	25,000 Hz	Syphilis or Treponema	36,250 Hz
BX Virus Carcinoma	39,467 Hz	Tetanus	28,000 Hz
BY Sarcoma	?37,000 Hz	Tuberculosis Rod	36,667 Hz
Gonorrhea	36,000 Hz	Tuberculosis Virus	?22,500 Hz
Spinal Meningitis	21,500 Hz	Typhoid Rod	100 Hz
Staphylococcus	24,000 Hz	Typhoid Virus	38,214 Hz

The Beam Ray Clinical Instrument Sideband Sine
Wave Audio Frequencies Based On A 3.80 MHz Carrier

Microorganism	Rife Ray #4 Frequencies	Higher Harmonic Frequencies	*Carrier Difference Frequencies	1/10 Of One Meter Freq.	Number of Sideband Harmonics	Aubrey Scoon's Frequencies	Beam Ray Clinical Frequencies
Actinomycosis or Strepto-thrix	192,000 Hz	3,840,000 or 20th	40,000 Hz	12 Hz	4	7,870 Hz	10,000 Hz
Anthrax	139,200 Hz	3,758,400 or 27th	41,600 Hz	6 Hz	5		8,320 Hz
B or E Coli Rod	417,000 Hz	3,753,000 or 9th	47,000 Hz	58 Hz	6	8,020 Hz	7,833 Hz
B or E Coli Virus	770,000 Hz	3,850,000 or 5th	50,000 Hz	198 Hz	3	17,220 Hz	16,667 Hz
BX Virus Carcinoma	1,604,000 Hz	3,208,000 or 2nd	592,000 Hz	858 Hz	15	21,275 Hz	39,467 Hz
BY Sarcoma	?1,530,000 Hz	3,060,000 or 2nd	740,000 Hz	780 Hz	20	20,080 Hz	37,000 Hz
Gonorrhea	233,000 Hz	3,728,000 or 16th	72,000 Hz	18 Hz	5		14,400 Hz
Pneumonia or Spinal Meningitis	427,000 Hz	3,843,000 or 9th	43,000 Hz	61 Hz	5	7,660 Hz	8,600 Hz
Staphylococcus Pyogenes Aureus	478,000 Hz	3,824,000 or 8th	24,000 Hz	76 Hz	3	7,270 Hz	8,000 Hz
Streptococcus Pyogenes	720,000 Hz	3,600,000 or 5th	200,000 Hz	173 Hz	24	8,450 Hz	8,333 Hz
Syphilis	789,000 Hz	3,945,000 or 5th	145,000 Hz	207 Hz	22	6,600 Hz	6,591 Hz
Tetanus	234,000 Hz	3,744,000 or 16th	56,000 Hz	18 Hz	5	1,200 Hz	11,200 Hz
Tuberculosis Rod	369,000 Hz	3,690,000 or 10th	110,000 Hz	45 Hz	13	8,300 Hz	8,462 Hz
Tuberculosis Virus	?769,000 Hz	3,845,000 or 5th	45,000 Hz	197 Hz	3	16,000 Hz	15,000 Hz
Typhoid Rod	760,000 Hz	3,800,000 or 5th	0 Hz	192 Hz	1	6,900 Hz	100 Hz
Typhoid Virus	1,445,000 Hz	4,335,000 or 3rd	535,000 Hz	694 Hz	14	18,620 Hz	38,214 Hz
Worms						2,400 Hz	

On page 93 you will find oscilloscope images of the original Beam Ray Clinical instrument. On pages 94 through 100 you will find the spectrum analyzer graphs showing the sideband frequencies for each organism using the Beam Ray Clinical instrument 3.80 MHz RF carrier frequency. These graphs show which sideband frequency is hitting the Harmonic Rife Ray #4 frequency that is closest to the 3.80 MHz carrier frequency. These graphs show clearly how this instrument worked.

On pages 101 and 102 are two charts that show the Rife Ray #4 frequencies and their M.O.R. harmonics so you can see the progression of harmonic frequencies as they go up in harmonics to the frequencies that were used by Philip Hoyland in this Beam Ray Clinical instrument. With these two charts you can do the same math that we did to determine the audio frequencies that will produce the proper sideband spacing. You will notice in the chart above called "The Beam Rays Clinical Instrument Sideband Sine Wave Audio Frequencies Based On A 3.80 MHz Carrier" that our list of audio frequencies for the Beam Ray Clinical instrument are in all four bands of frequencies. Philip Hoyland said:

HOYLAND: *"The whole list of bacteria that the machine was treating was divided into four bands."* (Beam Ray Trial Transcript #260)

You will notice that Aubrey Scoon's Beam Ray replica frequencies are only in three bands (bands 2, 3 and 4). This is because Dr. Rife's engineer, Verne Thompson, used a different audio oscillator with this instrument than the audio oscillator used in our original instrument. The first band which covered from 20 Hertz to 200 Hertz is not used since the lowest audio frequency was 1200 Hertz when

www.rife.org

using a 3.30 Megahertz carrier frequency. In the original Beam Ray Clinical instrument we obtained the audio oscillator was also changed but the RF carrier frequency was 3.80 Megahertz. With this carrier frequency you will get one audio frequency that has to be in band one because it is so close to the carrier frequency that only a frequency of less than two hundred Hertz will work.

IMPORTANT INFORMATION: Many people have asked why the frequencies that were used to determine how this Beam Ray Clinical instrument worked are different than those used with Aubrey Scoon's Beam Ray replica instrument. The reason they are slightly different is this instrument was evaluated and analyzed first. It also used an RF carrier frequency which is different than Aubrey Scoon's instrument. It was the evaluating and analyzing of this instrument using the Rife Ray #4 frequencies that made it possible figure out Aubrey Scoon's Beam Ray Clinical replica instrument. It was the information that was obtained from this Original Beam Ray Clinical instrument that made it possible to obtain the most accurate frequencies from Aubrey Scoon's Beam Ray Clinical instrument. In the Beam Ray Clinical instrument the frequencies had to be calculated precisely or it would not work. The reason for this precision is, if you happen to be off 20 Hertz on the first sideband then the second sideband will be off 40 Hertz. The error will continue to compounded with every sideband. It is easy to see that this simple small error would compound and make it so the instrument would not work. It is easy to see that though the instruments frequencies would wander a little the math to determine where the sidebands needed to be had to be exact. It was Philip Hoyland's precise math that made it so we would have the most accurate frequencies for the various microorganisms. Philip Hoyland said, on the stand, in the 1939 Beam Ray Trial that he tested the instrument in Rife's lab. His testimony revealed that he had tested the Beam Ray Clinical design using microorganisms to determine its effectiveness. Dr. Rife also tested this same instrument in his lab on micro-organisms in the early 1940's. So we know that this design worked.

Please read Chapter 11 of this report to understand how we obtained the most accurate frequencies from Aubrey Scoon's Beam Ray Clinical replica instrument.

Chapter Summary: Dr. Rife's engineer, Philip Hoyland, not John Crane, was the first person to built the instruments that used audio frequencies and an RF carrier frequency. This instrument which was called the Rife Ray #5 or Beam Ray Clinical instrument was fundamentally different than the Rife Ray #3 and Rife Ray #4 instruments because it was built with a variable audio oscillator and a fixed RF Carrier frequency. It was the modulation of the audio frequency with the RF carrier frequency which produced Dr. Rife's higher harmonic M.O.R. frequencies which devitalized the microorganisms. This new method which Philip Hoyland developed used harmonic sideband frequencies produced by the audio frequencies to produce Dr. Rife's higher harmonic frequencies. Dr. Rife's higher harmonic frequencies were the frequencies used in both the Rife Ray #3 and Rife Ray #4 instruments.

Philip Hoyland built this Beam Ray Clinical instrument using this new method because Dr. Rife was not able to patent his equipment or his frequencies. The audio frequencies were not the frequencies that devitalized any microorganisms as many believe today. The audio frequencies had to be combined with the correct RF carrier frequency to produce the correct sideband frequencies or they would not produce Dr. Rife's frequencies which would devitalize the various microorganisms. Because Philip Hoyland hid how the Beam Ray Clinical instrument worked it resulted in John Crane and John Marsh believing that the audio frequencies were the treatment frequencies for the microorganisms. They in turn passed on this incorrect understanding of the audio frequencies which has lead to the current belief that the audio frequencies are the treatment frequencies. It was the analyzing of the original Beam Ray Clinical instrument obtained from Dr. Low which revealed how the audio frequencies produce Dr. Rife's original higher harmonic frequencies through harmonic sidebands.

In Chapter 10 we will look at the next Rife Machine built by Philip Hoyland which was call the Beam Ray Laboratory instrument.

www.rife.org

Oscilloscope Readings Of The Original Beam Ray Clinical Instrument


3.80 MHz carrier frequency before ray tube.


3.80 MHz carrier frequency after ray tube.


2,377 Hertz frequency from audio oscillator.


9,360 Hertz frequency from audio oscillator.


18,630 Hertz frequency from audio oscillator.


40,980 Hertz frequency from audio oscillator.


Original Beam Ray modulated waveform.


Aubrey Scoon’s Beam Ray replica modulated waveform.

www.rife.org


Rife Ray #4 192,000 Hertz for Actinomycosis or Streptothrix. The 20th Higher harmonic frequency is 3,840,000 Hertz. The audio frequency used for the proper sideband spacing is 10,000 Hertz. The 4th upper sideband hit the M.O.R.

Philip Hoyland’s Beam Ray Clinical instrument 3.80 Megahertz spectrum analysis of sideband harmonic frequencies.


Rife Ray #4 139,200 Hertz for Anthrax. The 27th Higher harmonic frequency is 3,758,400 Hertz. The audio frequency used for the proper sideband spacing is 8,320 Hertz. The 5th lower sideband hit the M.O.R.

Philip Hoyland’s Beam Ray Clinical instrument 3.80 Megahertz spectrum analysis of sideband harmonic frequencies.

www.rife.org



Rife Ray #4 417,000 Hertz for B or E Coli Rod. The 9th Higher harmonic frequency is 3,753,000 Hertz. The audio frequency used for the proper sideband spacing is 7,833 Hertz. The 6th lower sideband hit the M.O.R.

Philip Hoyland’s Beam Ray Clinical instrument 3.80 Megahertz spectrum analysis of sideband harmonic frequencies.



Rife Ray #4 770,000 for B or E Coli Virus. The 5th Higher harmonic frequency is 3,850,000 Hertz. The audio frequency used for the proper sideband spacing is 16,667 Hertz. The 3rd upper sideband hit the M.O.R.

Philip Hoyland’s Beam Ray Clinical instrument 3.80 Megahertz spectrum analysis of sideband harmonic frequencies.

www.rife.org



Rife Ray #4 1,604,000 Hertz for the BX Cancer Virus. The 2nd Higher harmonic frequency is 3,208,000 Hertz. The audio frequency used for the proper sideband spacing is 39,467 Hertz. The 15th sideband hit the M.O.R. The greater the frequency difference from the carrier frequency to the M.O.R the weaker the sidebands become. The 15th lower sideband is about all you would want to have over a 592,000 Hertz spread.

Philip Hoyland’s Beam Ray Clinical instrument 3.80 Megahertz spectrum analysis of sideband harmonic frequencies.



Rife Ray #4 233,000 Hertz for Gonorrhea. The 16th Higher harmonic frequency is 3,728,000 Hertz. The audio frequency used for the proper sideband spacing is 14,400 Hertz. The 5th lower sideband hit the M.O.R.

Philip Hoyland’s Beam Ray Clinical instrument 3.80 Megahertz spectrum analysis of sideband harmonic frequencies.

www.rife.org


Rife Ray #4 427,000 Hertz for Spinal Meningitis. The 9th Higher harmonic frequency is 3,843,000 Hertz. The audio frequency used for the proper sideband spacing is 8,600 Hertz. The 5th upper sideband hit the M.O.R.

Philip Hoyland's Beam Ray Clinical instrument 3.80 Megahertz spectrum analysis of sideband harmonic frequencies.


Rife Ray #4 478,000 Hertz for Staphylococcus Pyogenes Aureus. The 8th Higher harmonic frequency is 3,824,000 Hertz. The audio frequency used for the proper sideband spacing is 8,000 Hertz. The 3rd upper sideband hit the M.O.R.

Philip Hoyland's Beam Ray Clinical instrument 3.80 Megahertz spectrum analysis of sideband harmonic frequencies.

www.rife.org



Rife Ray #4 720,000 Hertz for Streptococcus Pyogenes. The 5th Higher harmonic frequency is 3,600,000 Hertz. The audio frequency used for the proper sideband spacing is 8,333 Hertz. The 24th lower sideband hit the M.O.R. The smaller the difference between the M.O.R. frequency and the carrier frequency the greater the number of sideband frequencies that can be used with power.

Philip Hoyland's Beam Ray Clinical instrument 3.80 Megahertz spectrum analysis of sideband harmonic frequencies.



Rife Ray #4 789,000 Hertz for Syphilis. The 5th Higher harmonic frequency is 3,945,000 Hertz. The audio frequency used for the proper sideband spacing is 6,591 Hertz. The 22nd upper sideband hit the M.O.R.

Philip Hoyland's Beam Ray Clinical instrument 3.80 Megahertz spectrum analysis of sideband harmonic frequencies.

www.rife.org



Rife Ray #4 234,000 Hertz for Tetanus. The 16th Higher harmonic frequency is 3,744,000 Hertz. The audio frequency used for the proper sideband spacing is 11,200 Hertz. The 5th lower sideband hit the M.O.R.

Philip Hoyland’s Beam Ray Clinical instrument 3.80 Megahertz spectrum analysis of sideband harmonic frequencies.



Rife Ray #4 369,000 Hertz for Tuberculosis Rod. The 10th Higher harmonic frequency is 3,690,000 Hertz. The audio frequency used for the proper sideband spacing is 8,462 Hertz. The 13th lower sideband hit the M.O.R.

Philip Hoyland’s Beam Ray Clinical instrument 3.80 Megahertz spectrum analysis of sideband harmonic frequencies.

www.rife.org



Rife Ray #4 760,000 Hertz for Typhoid Rod. The 5th Higher harmonic frequency is 3,800,000 Hertz. The audio frequency used for the proper sideband spacing is 100 Hertz. The sidebands, when only 200 Hertz apart, look like one frequency hit the M.O.R.

Philip Hoyland’s Beam Ray Clinical instrument 3.80 Megahertz spectrum analysis of sideband harmonic frequencies.



Rife Ray #4 1,445,000 Hertz for Typhoid Virus. The 3rd Higher harmonic frequency is 4,335,000 Hertz. The audio frequency used for the proper sideband spacing is 38,214 Hertz. The 14th upper sideband hit the M.O.R.

Philip Hoyland’s Beam Ray Clinical instrument 3.80 Megahertz spectrum analysis of sideband harmonic frequencies.

www.rife.org

Streptothrix

1	192000
2	384000
3	576000
4	768000
5	960000
6	1152000
7	1344000
8	1536000
9	1728000
10	1920000
11	2112000
12	2304000
13	2496000
14	2688000
15	2880000
16	3072000
17	3264000
18	3456000
19	3648000
20	3840000
21	4032000
22	4224000
23	4416000
24	4608000
25	4800000
26	4992000
27	5184000
28	5376000
29	5568000
30	5760000
31	5952000
32	6144000
33	6336000
34	6528000

Anthrax

1	139200
2	278400
3	417600
4	556800
5	696000
6	835200
7	974400
8	1113600
9	1252800
10	1392000
11	1531200
12	1670400
13	1809600
14	1948800
15	2088000
16	2227200
17	2366400
18	2505600
19	2644800
20	2784000
21	2923200
22	3062400
23	3201600
24	3340800
25	3480000
26	3619200
27	3758400
28	3897600
29	4036800
30	4176000
31	4315200
32	4454400
33	4593600
34	4732800

B or E Coli Rod

1	417000
2	834000
3	1251000
4	1668000
5	2085000
6	2502000
7	2919000
8	3336000
9	3753000
10	4170000
11	4587000
12	5004000
13	5421000
14	5838000
15	6255000
16	6672000
17	7089000
18	7506000
19	7923000
20	8340000
21	8757000
22	9174000
23	9591000
24	10008000
25	10425000
26	10842000
27	11259000
28	11676000
29	12093000
30	12510000
31	12927000
32	13344000
33	13761000
34	14178000

B or E Coli Viurs

1	770000
2	1540000
3	2310000
4	3080000
5	3850000
6	4620000
7	5390000
8	6160000
9	6930000
10	7700000
11	8470000
12	9240000
13	10010000
14	10780000
15	11550000
16	12320000
17	13090000
18	13860000
19	14630000
20	15400000
21	16170000
22	16940000
23	17710000
24	18480000
25	19250000
26	20020000
27	20790000
28	21560000
29	22330000
30	23100000
31	23870000
32	24640000
33	25410000
34	26180000

BX Cancer Virus

1	1604000
2	3208000
3	4812000
4	6416000
5	8020000
6	9624000
7	11228000
8	12832000
9	14436000
10	16040000
11	17644000
12	19248000
13	20852000
14	22456000
15	24060000
16	25664000
17	27268000
18	28872000
19	30476000
20	32080000
21	33684000
22	35288000
23	36892000
24	38496000
25	40100000
26	41704000
27	43308000
28	44912000
29	46516000
30	48120000
31	49724000
32	51328000
33	52932000
34	54536000

Gonorrhea

1	233000
2	466000
3	699000
4	932000
5	1165000
6	1398000
7	1631000
8	1864000
9	2097000
10	2330000
11	2563000
12	2796000
13	3029000
14	3262000
15	3495000
16	3728000
17	3961000
18	4194000
19	4427000
20	4660000
21	4893000
22	5126000
23	5359000
24	5592000
25	5825000
26	6058000
27	6291000
28	6524000
29	6757000
30	6990000
31	7223000
32	7456000
33	7689000
34	7922000

Spinal Meningitis

1	427000
2	854000
3	1281000
4	1708000
5	2135000
6	2562000
7	2989000
8	3416000
9	3843000
10	4270000
11	4697000
12	5124000
13	5551000
14	5978000
15	6405000
16	6832000
17	7259000
18	7686000
19	8113000
20	8540000
21	8967000
22	9394000
23	9821000
24	10248000
25	10675000
26	11102000
27	11529000
28	11956000
29	12383000
30	12810000
31	13237000
32	13664000
33	14091000
34	14518000

www.rife.org

Staph Pyo Aureus

1	478000
2	956000
3	1434000
4	1912000
5	2390000
6	2868000
7	3346000
8	3824000
9	4302000
10	4780000
11	5258000
12	5736000
13	6214000
14	6692000
15	7170000
16	7648000
17	8126000
18	8604000
19	9082000
20	9560000
21	10038000
22	10516000
23	10994000
24	11472000
25	11950000
26	12428000
27	12906000
28	13384000
29	13862000
30	14340000
31	14818000
32	15296000
33	15774000
34	16252000

Strept Pyogenes

1	720000
2	1440000
3	2160000
4	2880000
5	3600000
6	4320000
7	5040000
8	5760000
9	6480000
10	7200000
11	7920000
12	8640000
13	9360000
14	10080000
15	10800000
16	11520000
17	12240000
18	12960000
19	13680000
20	14400000
21	15120000
22	15840000
23	16560000
24	17280000
25	18000000
26	18720000
27	19440000
28	20160000
29	20880000
30	21600000
31	22320000
32	23040000
33	23760000
34	24480000

Syphilis

1	789000
2	1578000
3	2367000
4	3156000
5	3945000
6	4734000
7	5523000
8	6312000
9	7101000
10	7890000
11	8679000
12	9468000
13	10257000
14	11046000
15	11835000
16	12624000
17	13413000
18	14202000
19	14991000
20	15780000
21	16569000
22	17358000
23	18147000
24	18936000
25	19725000
26	20514000
27	21303000
28	22092000
29	22881000
30	23670000
31	24459000
32	25248000
33	26037000
34	26826000

Tetanus

1	234000
2	468000
3	702000
4	936000
5	1170000
6	1404000
7	1638000
8	1872000
9	2106000
10	2340000
11	2574000
12	2808000
13	3042000
14	3276000
15	3510000
16	3744000
17	3978000
18	4212000
19	4446000
20	4680000
21	4914000
22	5148000
23	5382000
24	5616000
25	5850000
26	6084000
27	6318000
28	6552000
29	6786000
30	7020000
31	7254000
32	7488000
33	7722000
34	7956000

Tuberculosis Rod

1	369000
2	738000
3	1107000
4	1476000
5	1845000
6	2214000
7	2583000
8	2952000
9	3321000
10	3690000
11	4059000
12	4428000
13	4797000
14	5166000
15	5535000
16	5904000
17	6273000
18	6642000
19	7011000
20	7380000
21	7749000
22	8118000
23	8487000
24	8856000
25	9225000
26	9594000
27	9963000
28	10332000
29	10701000
30	11070000
31	11439000
32	11808000
33	12177000
34	12546000

Typhoid Rod

1	760000
2	1520000
3	2280000
4	3040000
5	3800000
6	4560000
7	5320000
8	6080000
9	6840000
10	7600000
11	8360000
12	9120000
13	9880000
14	10640000
15	11400000
16	12160000
17	12920000
18	13680000
19	14440000
20	15200000
21	15960000
22	16720000
23	17480000
24	18240000
25	19000000
26	19760000
27	20520000
28	21280000
29	22040000
30	22800000
31	23560000
32	24320000
33	25080000
34	25840000

Typhoid Virus

1	1445000
2	2890000
3	4335000
4	5780000
5	7225000
6	8670000
7	10115000
8	11560000
9	13005000
10	14450000
11	15895000
12	17340000
13	18785000
14	20230000
15	21675000
16	23120000
17	24565000
18	26010000
19	27455000
20	28900000
21	30345000
22	31790000
23	33235000
24	34680000
25	36125000
26	37570000
27	39015000
28	40460000
29	41905000
30	43350000
31	44795000
32	46240000
33	47685000
34	49130000

www.rife.org

Photos of the original 1938-1939 Beam Ray Clinical instrument when it was found


FILAMENT
OUTPUT







www.rifevideos.com



www.rifevideos.com



www.rife.org



Chapter #10

The Gruner Schematic and Philip Hoyland's Beam Ray Laboratory Rife Machine



1. Used a ray tube.
2. Had one RF oscillators which was set on a fix frequency.
3. Had a fix audio pulsing circuit.
4. Power usage was about 450 to 600 watts. Output to the ray tube was probably about 40 watts.

In this chapter we will cover two instruments. First, Dr. Gruner's Rife machine and second, the Beam Ray Laboratory Rife machine. The reason for this is the work done on the Gruner instrument lead too many discoveries of how Dr. Rife's machines worked. The first instrument we will discuss is the Gruner Rife Machine. From some recent documents that were found by Mr. Ringas we have found it necessary to change some of the information in this chapter which deals with Dr. Gruner's Rife instrument.

The new documents that were found by Mr. Ringas reveal the fact that the Gruner Rife machine had one fixed RF oscillator. It was previously believed that this instrument was a Beam Ray laboratory instrument which had two high RF frequency oscillators. We now know from these documents that this was an incorrect assumption. The new information comes from two letters written to John Crane back in 1953 from Dr. O. C. Gruner. John Crane at that time was inquiring about the status of Dr. Gruner's Rife machine that was sent to him in 1942 by Dr. Milbank Johnson M.D.:

www.rife.org

DR. GRUNER: *"You refer, I suppose, to the ray machine which Milbank Johnson sent "in bits" to me in Montreal* [Canada]. *Vergil Neher assembled it, but actually I had to purchase a large amount of the radio material to be able to get it completed. I used this machine quite a bit, and it was very successful at first; but after about six months it "faded", first the tubes seemed all right. The only reason would have been changes in the glass of the globe* [ray tube] *as a result of the discharges… I could send the plan* [schematic] *of the apparatus."* (Letter from Dr. Gruner to John Crane, March 31, 1953).

DR. GRUNER: *"I enclosed the diagram* [schematic] *of the Ray Machine as made here in 1942. So I hope it will be of interest to you. It will not be necessary to return it. It is to be noted that it was made only for one frequency; obviously it would be necessary to alter the design to enable many frequencies to be used."* (Letter from Dr. Gruner to John Crane, April 29, 1953).

These two letters changed all our understanding of this instrument. John Crane had altered the schematic and put a second Hartley oscillator on the schematic which confused us when we originally built the instrument. This second Hartley oscillator, added by John Crane, which will be shown in a photo below, made it so the instrument would have had one fixed RF oscillator and a second variable RF oscillator. This second variable RF oscillator, that John Crane added to the schematic, would make it so that instrument could output many different frequencies. Logically this is what Dr. Rife, John Crane and John Marsh wanted in an instrument. But this is not how Dr. Gruner's original instrument worked.

From the analyzing of the original Beam Ray Clinical instrument, which was built by Philip Hoyland, we know that it had the capability of variable audio frequencies. We need to point out here that Dr. Gruner's ray tube instrument did not work on the Beam Ray Clinical instrument harmonic sideband method. From these two letters we now know that Dr. Gruner's instrument work on the same principles as the Rife Ray #4 instrument. That instrument output the specific frequencies directly from its two variable RF oscillators. Because the Rife Ray #4 put out specific frequencies it also used a modulated fixed audio pulsing circuit to pulse the high RF frequencies that were used to devitalize the various microorganisms. This modulated fixed audio frequency pulsing method was used with all of Dr. Rife's instruments. The Gruner schematic which has this modulated fixed audio frequency pulsing circuit reveals how Dr. Rife used this pulsing method in his instruments. With this understanding we now have a clearer understanding of how these four instruments, Rife Ray #3, Rife Ray #4, Beam Ray Laboratory and Gruner Rife machine really worked.

As we pointed out when we initially looked at Dr. Gruner's schematic, several years ago, we were under the wrong assumption, because John Crane altered the schematic by adding the second Hartley oscillator to Dr. Gruner's schematic. But that wrong assumption actually caused us to build an instrument that worked almost exactly as the Rife Ray #4 did. Except the instrument that we built from Dr. Gruner's schematic did not have as high a frequency range as the Rife Ray #4. Because of what we have just explained we feel that the information that we obtained from the initial building of the Gruner schematic, several years ago, should be kept in this report. What was learned, even under the wrong assumption, revealed how the Rife Ray #4 was built and will still be of interest to those who may want to build this instrument.

The Beam Ray Laboratory instrument would have worked like the Gruner instrument and the Rife Ray #4 instrument since both of these were to be used in laboratory work. An instrument that worked like the Beam Ray Clinical instrument, which worked on the harmonic sideband method, would have been useless in any laboratory work since you could never know the exact frequency that killed, devitalize or rendered harmless an organism. For this reason the Beam Ray Laboratory instrument is still included in this information about Dr. Gruner's Rife instrument.

www.rife.org

The initial Gruner schematic work done in 2007-2008

In one of the previous version of this report we dealt with the concept that the Gruner instrument was a heterodyning instrument. We now know that this method was not used in the Gruner Rife Machine therefore the heterodyning concept was removed from a previous rewriting of this document. Though the Rife Ray #4 Rife Machine could output two frequencies at the same time and those two frequencies did heterodyn in the ray tube, this was a byproduct of the instrument not the method used to produce the M.O.R. frequencies needed to devitalize or render harmless the microorganisms. The knowledge that we gained through our testing of this concept is the reason much of the history and work that we did at that time is still included in this report. It was that testing which gave us the understanding of how the Rife Ray #4 worked and how the Beam Ray Laboratory Rife Machine would have worked.

We do not have a picture of Dr. Gruner's Rife instrument so we have no idea what it looked like. This however did not affect building the instrument from the schematic. The Rife Machine in the photo shown at the beginning of this chapter is probably a photo of the Beam Ray Laboratory instrument built by Philip Hoyland. John Crane dated that instrument as being built in 1935 but we know that the Rife Ray #4 was built in 1935. The knowledge of the Laboratory instrument came from the Beam Ray Trial manuscript. A complete copy of this transcript was provided when Steven Ross allowed us to scan it. I would like to acknowledge his generous contribution of this information which has given us a great deal of understanding so that we could figure out the history of how and when the instruments were built.

After reading for the first time the complete Beam Ray Trial manuscript I found there was mention of a Laboratory instrument. It appeared that this Laboratory instrument was probably to be used by those who would be working in laboratories with microorganisms for testing. Dr. O. C. Gruner worked in a laboratory with organisms and worked with Dr. Rife on the organism called Cryptomyces Pleomorpha fungi. The Laboratory instrument was mentioned two or three times but no real information was given about it. Below are statements made by Bertrand Comparet and Philip Hoyland in the Beam Ray Trial that gives us some important information about this instrument. (#209-210, 217-222):

COMPARET: *“The four machines bought by the British were two so-called laboratory types and two so-called clinical types, what was the difference between the two.”*

HOYLAND: *“The clinical type was similar in all respects to the Rife machine except that it did not have* [word missing] *of the* [word missing] *used on Mrs. Henderson.”*

COMPARET: *“How was the price of these machines fixed.”*

HOYLAND: *“The price was decided from the costs of what it cost to manufacture the first machine that was sold to Dr. Hamer.”*

COMPARET: *“How much was that?”*

HOYLAND: *“I think it was four hundred dollars plus the royalty.”*

COMPARET: *“Wasn’t it five hundred dollars plus royalty on the clinical type and six plus royalty on the lab type.”*

HOYLAND: *“I don’t remember.”*

Since this Beam Ray Laboratory Rife Machine was for Laboratory work it would have worked like the Rife Ray #4 but because the case was smaller it probably had a smaller frequency range. The

www.rife.org

Rife Ray #4 had nine frequency bands that covered from 87,000 Hertz to 22.5MHz (22,500,000 Hertz). The first four bands of the #4 covered from 87,000 Hertz to 2,140,000 Hertz. These four frequency bands would cover the whole list of Dr. Rife's disease organisms listed on the Rife Ray #4 documents. With this understanding we know that the Laboratory instrument at least covered this frequency range. We will not speculate if it had a higher frequency range because we really do not know if it did.

Deciphering Dr. Gruner's Beam Ray instrument schematic

Several years ago a group of us had been looking on the Gruner schematic in hopes of trying to figure out how it worked. I had built and tested both the 1953 AZ-58 Beam Ray Clinical instrument and 1950's Aubrey Scoon, Beam Ray Clinical replica instruments. To our knowledge none of these instruments ever obtained the same results as the original Beam Ray Clinical Rife Machine built by the original 1938 Beam Ray Corporation. All the documentation we had showed that there were changes made to the original Beam Ray design which compromised the1953 AZ-58, and possibly 1950's Aubrey Scoon, Verne Thompson instruments. John Crane, over the years told many people that the AZ-58 and the audio frequencies it used were Dr. Rife's original frequencies. The Rife documents we have show that what John Crane claimed was not correct. Dr. Rife was not using audio frequencies in 1934 as John Crane and John Marsh claimed. Rebuild of the 1953 AZ-58 and Aubrey Scoon's instrument partially made the rediscovery of the Beam Ray Laboratory instrument possible.

At the 2003 Rife Conference, a gentleman put up the Gruner schematic of an original Beam Ray instrument. From reading the Rife documents I knew that this schematic existed because John Crane had mentioned it in his papers. John Crane said that the AZ-58 was built from that schematic. When I saw it I knew it was important, so I took still photos of it with my video camera. Because the video camera only had a one mega-pixel capability I took many up close photos knowing I could put it back together at a later date. Back in 2004 I gave this schematic to Aubrey Scoon and his British Rife group in hopes that they could look it over and correct any mistakes that may have been made. They redrew the schematics, unfortunately without fully correcting them, and put them up on their web site. This information was released because we wanted everyone to have access to it.

Back on July 27, 2007 a Mr. Andrews, who was one of the British Rife group and I got into another conversation about the Gruner schematic. He asked me to send him another copy of the original Gruner schematic so he could look it over again. An email conversation began at that time which included Mr. Peters, Mr. Ringas, Mr. Andrews, Mr. Berger and myself. Mr. Peters immediately noticed that the schematic that had been redrawn by the British group had some errors in it. Discussions continued on and off for a few months until one day Mr. Peters noticed an over sight when looking over the schematic again. At the time we thought it had to do with the heterodyning method. But now we understand that this oversight was one of the keys to understanding how the Rife Ray #4 and Beam Ray Laboratory Rife Machines would have worked.

Mr. Peters sent Mr. Ringas and I an email. He mentioned that a possible test could be made that would determine if this observation of his was the key to understanding how the Beam Ray Laboratory instrument really worked. I called Mr. Peters and had a discussion with him and he told me how we could make these tests. I told him that we did not need to do the test with solid state frequency generators because I had conducted a similar test back when John Bedini and I were working on the AZ-58 tests. John Bedini and I knew that the original Rife Ray #4 instrument was a lot more powerful than the AZ-58 because of the Rife documents. After more accurate testing we found the AZ-58 only output about 40 watts from the ray tube. I told him that I still had my 1950's Aubrey Scoon replica and several AZ-58's on the shelf. I told John Bedini that the original Beam Ray Clinical instrument, from the documentation that we had, may have output about 50 to 60 watts from the ray tube. He told me how I could make a test, by putting two AZ-58s together, which would give me at least 60 watts out of the ray tube. I didn't know it at that time but that test was probably the way the Rife Ray #4 and Beam Ray Labora-

www.rife.org

tory instrument worked. I told Mr. Peters I would connect the AZ-58 and Aubrey Scoon instruments together again and make the tests that he suggested, but this time I would use my spectrum analyzer and we would fully make tests and find out if this was the method Philip Hoyland used. This test made the two instruments work exactly the same as the Gruner Beam Ray schematic would have worked with John Crane's addition of the second variable RF oscillator. This test was the key to understanding how Philip Hoyland's Laboratory instrument and Rife Ray #4 instrument worked. I had always stated that Philip Hoyland had to have come up with his method using math because they didn't have any spectrum analyzers back in 1936. In looking back that test showed that the Rife Ray #4 was heterodyning in the ray tube. Though we now know the heterodyning method was not used by Dr. Rife the method of connecting the ray tube up to two RF oscillators showed that this was the method used with the Rife Ray #4 which had two RF oscillators.

We will now show how Philip Hoyland's Rife Ray #4 and Beam Ray Laboratory instrument worked. We can do this because we have been able to rebuild these instruments from the Gruner schematic. This information should be of great interest to all who have been interested in Dr. Rife's work.

www.rife.org

Rebuilding the Philip Hoyland Beam Ray Laboratory instrument

When this schematic was analyzed Mr. Peters noticed that the British group had overlooked a second Hartley RF oscillator that was in the lower left corner of the Gruner schematic. This was the variable oscillator that John Crane added to the schematic after he received it from Dr. Gruner. At this time we did not know that this second oscillator was not a part of the original schematic. The British group believed this oscillator was the same RF fixed Hartley Oscillator that used the 809 tube. Below is a photo of the complete Gruner Beam Ray schematic.



First Hartley Oscillator for fixed RF carrier frequency.

Second Hartley Oscillator for variable RF frequency.

Two Hartley Oscillators. One fixed one variable. This was the key of how the two oscillators output there frequencies into the ray tube.

In next schematic photo, shown below, is the fixed RF carrier frequency section that used the 809 tube.


Up close view of first Hartley Oscillator for fixed RF carrier frequency.

809 Tube

In the next schematic photo, shown below, is the second oscillator that was overlooked by the British group. This was the oscillator that John Crane added to the schematic which caused us to misinterpret how the instrument worked. You will notice that the second oscillator that John Crane added says "Hartley Oscillator." Because the first fixed oscillator that used the 809 tube is a Hartley Oscillator the British group assumed that both of these oscillators were the same. This overlooking of the second oscillator that John Crane added would have made the instrument work exactly as Dr. Gruner had stated his instrument worked. Dr. Gruner stated that the instrument was fixed on one frequency. It was the overlooking of this second Hartley oscillator, added by John Crane, that Mr. Peters noticed. If you look at the second Harley Oscillator, in the photo below, that does not use the 809 tube, you will notice that it has a variable capacitor. This variable capacitor shows that there were two Hartley Oscillators shown on the schematic. One fixed and one variable.


Up close view of second Hartley Oscillator for variable RF frequency.

Variable capacitor.

Tank Coil.

www.rife.org

The next schematic photo, shown below, shows that the first fixed Hartley Oscillator was connected from the tank coil to the negative side of the ray tube. If you look closely at the photo you will notice that the positive side of the ray tube was also to be connected to a Hartley Oscillator.


Tank Coil
45
3 meg
809
RF TUBE
.002
80
PLUG FOR CABLE
0-500 mA
ACTUALLY SET TO 100
Negative
Ray Tube
Positive
RAY TUBE
Helium gas
12 mm press.
Electrodes 2" APART
IN DIA.
3 LITER PYREX FLASK
TO HARTLY
THOMPSON
By — John F. Crane 3-5-51
FROM O.C. GRUNNER M.D'S RECORDS FROM MILBANK JOHNSON & RIFE & HOYLAND'S CONCEPTION OF RIFE RAY TUBE FREQUENCY INSTRUMENT — 1951

If you hooked the positive side of the ray tube back up to the same fixed Hartley Oscillator it would have only output one frequency as described by Dr. Gruner. This adding of the second oscillator, by John Crane, is why there was confusion on how this instrument worked. The positive side of the ray tube was supposed to be hooked back up to the same fixed oscillator. But with the adding of the second variable Hartley Oscillator, by John Crane, would mean that the positive side of the ray tube would have been hooked up to the second Hartley oscillator. This would have made it so the ray tube would be connected between the two Hartley Oscillators. The negative side of the ray tube connected to one oscillator and the positive side of the ray tube connected to the other oscillator.

The second Hartley Oscillator was also an RF Oscillator. It had a tank coil and a variable capacitor for changing the RF frequencies. Anyone looking at this schematic will notice that it does not have any variable audio oscillator. Philip Hoyland's Beam Ray Gruner instrument was using an RF frequency not an audio frequency. This would logically mean that Dr. Gruner was using one of the Rife Ray #4 frequencies. Because Dr. Gruner was working on the cancer organism of Cryptomyces Pleomorpha fungi his instrument was most likely set on that organisms frequency.

Because we did not know that John Crane had added this second oscillator we came to the conclusion that the logical way to build the instrument would have been to have had two Hartley Oscillators using the 809 tubes. So this is the way that we rebuilt the instrument. By using the method of connect-

www.rife.org

ing the ray tube between the two Hartley Oscillators, both variable, the instrument could output two high RF frequencies at the same time without the bandwidth problems that would have come with trying to modulate frequencies through a tank coil. The tank coil in the Beam Ray Clinical instrument can only pass modulated frequencies up to about 250,000 Hertz. Because we put the ray tube between the two Hartley Oscillators and found that the instrument could work this way we determined that Philip Hoyland most likley built the Rife Ray #4 and Beam Ray Laboratory instrument in this same way. Our instrument could output two frequencies at the same time.

The Beam Ray Laboratory instrument probably had some band switches like the Rife Ray #4. What the frequency range of this Beam Ray Laboratory instrument was is not known but it would have gone up to at least 1.80 MHz like the Rife Ray #3 Kennedy equipment did. Dr. Rife's Rife Ray #3 and Rife Ray #4 machines put out specific frequencies and this instrument, it appears, was built to do the same thing. If Dr. Rife wanted 1,604,000 Hertz he would set the oscillator to 1,604,000 Hertz. This was the type of instrument Dr. Rife used. When you look at the case of the Laboratory instrument it is a large case that could have easily held the necessary components for this instrument. The instrument would have had two large dials on the front of it. In the photo, shown at the beginning of this chapter, the pole that holds the ray tube is blocking part of the panel where we would expect to see the second dial for the second oscillator.

The modulated Audio Frequency pulsing circuit

In this report, in the previous chapters, we have mentioned a fixed audio frequency pulsing circuit. We will now cover it in more detail because the Beam Ray Gruner instrument had this circuit in its schematic. This circuit pulsed the high RF frequencies. We know it was important because it was considered the secret that made the instrument work. If you look at the next schematic photo, shown below, you will see two audio transformers. This is the only indication of any audio frequency used in Dr. Gruner's instrument.



www.rife.org

It was not a variable audio oscillator but it was for a single fixed audio frequency. The 76 and 45 vacuum tubes along with the two audio transformers make up this circuit. Mr. Peters built this section and found that the frequency was at about 1330 Hertz and it pulses, through modulation, the fixed Hartley Oscillator RF carrier frequency that used the 809 tube. The next two photos, shown below, is this rebuilt circuit.





This 1330 Hertz frequency could have been a little higher or a little lower frequency because he used modern transformers instead of the original 1940's transformers. This pulsing frequency is a lot faster than the eye can see so no one would know it was in the instrument. If you look at the next photo, shown below, you will see the waveform of the pulsing frequency. It resembles a damped wave minus the ring oscillations of a true damped wave.



This waveform also looks like the waveform of the Rife Ray #4. This waveform would produce the effect that John Crane mentioned as he narrated Dr. Rife’s 1936 Lab video:

CRANE: *“Now the spikes that you see on the frequencies are the lethal part that kill and devitalize the virus. They are the resonant peaks of the frequencies which increase the voltage to a very high potential which the cells of the virus wall can not tolerate and they break up into many pieces and are destroyed.”* (Dr. Rife’s Lab Film Narrated by John Crane in the 1970’s).

www.rife.org

It's doubtful that this understanding of the spikes would have been something that John Crane would have known anything about had Dr. Rife not told him about it. From the statements we have read the resonant frequency of an organism is not enough to devitalize it. It's apparent that an organism's resonant frequency will not harm it unless the resonant frequency is pulsed through modulation with a waveform that produces a high potential voltage rise. It also appears that this modulated audio pulsing circuit would have been necessary for all of Dr. Rife's high RF frequencies. Logically this same type of circuit would have been in Dr. Rife's Rife Ray #3 and Rife Ray #4 and this is why the Gruner instrument also had this kind of circuit built into it. Also, logically his Beam Ray Laboratory instrument had this circuit.

In the previous chapter of this report when we covered the original Beam Ray clinical instrument. We showed that a sine wave audio frequency modulated onto a carrier frequency, in this M.O.P.A. style instrument, was sufficient enough to create the necessary pulse to devitalize the various microorganisms. The analyzing of that Beam Ray Clinical circuit showed that it almost creates a square wave frequency. The Beam Ray Clinical instrument output variable audio frequencies well above 10,000 Hertz. This indicates that the pulse rate of the modulated audio frequency is not important, only that the high RF frequency is pulsed.

There is another important effect that happens to the plasma of a ray tube when you pulse it with a low audio frequency of a damped shaped waveform or square wave waveform. Because the duty cycle is very low it allows deionization of the plasma which makes it possible for the very high potential voltage rise to be emitted from the ray tube. A square wave audio frequency of a 50% duty cycle should be just as effective as a damped waveform. A square wave has the same high potential voltage rise on the leading edge as this damped wave. Philip Hoyland found that even a sine wave frequency was sufficient to achieve the same result when used in the M.O.P.A circuit. His Beam Ray Clinical instrument circuit was modulated with a sine wave audio frequency that produced a waveform that almost looks like a square wave waveform and that waveform would devitalize the organisms. The next photo, shown below, is that waveform. We are showing this waveform so that the reader will understand what we are talking about.



www.rifevideos.com

This all indicates that an audio frequency modulation with a high RF frequency is what makes the frequencies work on microorganisms. The waveform of the audio frequency whether it is a damped wave or square wave makes no difference in its effectiveness because both of these waveforms have been used in Dr. Rife machines.

www.rife.org

The next photo, shown below, is a picture of Dr. Rife's waveform from his Rife Ray #4 Rife Machine. We showed this waveform in a previous chapter but we need to show it again. This waveform came from Dr. Rife's 1936 lab film. The lab film shows that he put a metal plate about 3" X 8" under the ray tube and ran his oscilloscope lead to it so he could read the frequencies. This photo shows the type of waveform he was using to devitalize organisms. It also matches the waveform produced by the 76 and 45 vacuum tubes in the Gruner instrument we are looking at in this chapter. We now know from the rebuilding of Dr. Gruners instrument and from the analyzing of the Beam Ray Clinical instrument, the two waveforms that were used, how they were created, and the method that should be used for doing M.O.R. research.



Both Mr. Peters and I rebuilt the Gruner instrument using two variable RF oscillators. We did not put the various bands in it like the Rife Ray #4 or the Beam Ray Laboratory instrument because we first believed it was a heterodyning instrument. Now that we know that Philip Hoyland's Beam Ray Clinical instrument used upper harmonics of the Rife Ray #4 frequencies it doesn't seem necessary that we put the different bands into the instrument. Our instruments will probably be adjusted so we can cover a range from about 1 MHz to about 4 or 5 MHz. Then we will multiply up the Rife Ray #4 frequencies into these ranges, like Philip Hoyland did with the Beam Ray Clinical instrument, and use them with this instrument. Other than John Crane adding the second Hartley oscillator the Gruner schematic was a complete schematic. The pulsing circuit was drawn correctly and worked. It also showed how Dr. Rife produced the damped waveform which pulsed his high RF frequencies in his instruments.

Mr. Peters built his instrument using 805 tubes and I built my instrument using 812A tubes. The AZ-58 Beam Ray Clinical replica RF section was almost exactly the same (809 vacuum tube replaced with the more powerful 812A tube) as the Gruner circuit. The reason I built the Gruner instrument using the 812A tubes is because the 809 is no longer being manufactured. We were also able to replace the modulated pulsing circuit consisting of the 45 & 76 tubes with a single high voltage switching transistor driven with a function generator which outputs the 1330 Hertz pulse frequency. With the use of this transistor we can use any audio frequency we want to use. Using this transistor we believe makes the design better because we can output all the lower audio frequencies including the original audio frequencies used in the AZ-58. My instrument has two Vernier dials which allows me to output two high RF frequencies at the same time like the Rife Ray #4 did. The ray tube is connected to both tank coils instead of having one side of the ray tube go to ground. It is the connecting of the ray tube between the two RF oscillators that makes this design work like the Rife Ray #4 would have done.

Please note: There is a modern instrument built today that is called the "Beam Ray." It works nothing like this original 1930's Beam Ray Laboratory instrument built by Philip Hoyland. We are not saying anything negative about the modern Beam Ray instrument but some people have asked us if these instruments work on the same principles and frequencies and they do not. We have only given this information so people are not confused about these two instruments.

www.rife.org

On page 118 are photos of Mr. Peters instrument which he built. On pages 119 through 121 are the photos of the Gruner instrument that we built. Because John Crane altered the schematic by adding the second oscillator we built this instrument with two oscillators. I built mine with two variable RF oscillators which made it work like the Rife Ray #4 and the Beam Ray Laboratory instrument. For this reason we refer to this instrument, in the photos below, as the Laboratory instrument.

On page 122 is a redrawn schematic of this design. We replaced the smaller vacuum tube of the second Hartley Oscillator with the 809 tube. The layout of the electronic parts of this instrument is very important because of the inherent interference problems that come with RF oscillators. Anyone wanting to build this instrument should have a good understanding of old tube technology. Some parts of this circuit use up to 2000 volts DC with substantial current and can easily kill anyone not experienced in working with this kind of current or voltage. We take no responsibility for anyone who builds this instrument. We recommend that you have professional help.

Chapter Summary: Dr. Gruner's machine was built to be set on one high RF frequency. It had no variable audio oscillator and did not work on the sideband method developed by Philip Hoyland. It had a fixed audio pulsing circuit that modulated the high RF frequency causing a high potential voltage rise in the waveform of the RF frequency being outputted to the ray tube. Because it used only one high RF oscillator it would have been set on Dr. Rife's high RF frequency for the organism Dr. Gruner was working on.

The Beam Ray Laboratory machine was built to work like the Rife Ray #4. It was built to be used in a laboratory for doing M.O.R. work on microorganisms. It would not have been built like the Rife Ray #5 or Beam Ray Clinical instrument which worked on harmonic sidebands. The Beam Ray Clincal instrument would not have worked in a laboratory setting since it devitalized all of the organisms in Dr. Johnson's laboratory due to the many sideband frequencies it would output.

In the next chapter we will now look at the next original Rife Machine replica that was purchased by Aubrey Scoon and his British Rife group.

www.rife.org

Mr. Peters' photos of the rebuilt Beam Ray Laboratory instrument











www.rife.org

Photos of the rebuilt Beam Ray Laboratory instrument









www.rife.org











www.rife.org


C113








PicoScope
File Edit Settings View Window Help
1 µs/div
x1
Auto
AC
Off
Off
AC
Off
Scope
V
1.0
0.8
0.6
0.4
0.2
0.0
-0.2
-0.4
-0.6
-0.8
-1.0
0 1 2 3 4 5 6 7 8 9 10
µs
12Mar2008 11:43
Spectrum
-20
-30
-40
-50
-60
0.0 2.5 5.0 7.5 10.0 12.5 15.0 17.5 20.0 22.5 25.0
MHz
12Mar2008 11:43
Meter
3073kHz
12Mar2008 11:43
Meter
269.6mV
12Mar2008 11:43
Running
Trigger None
mV
%
start
PicoScope


PicoScope
File Edit Settings View Window Help
200 µs/div
x1
Auto
AC
Off
Off
DC
Off
Scope
V
1.0
0.8
0.6
0.4
0.2
0.0
-0.2
-0.4
-0.6
-0.8
-1.0
0.0 0.2 0.4 0.6 0.8 1.0 1.2 1.4 1.6 1.8 2.0
ms
12Mar2008 13:10
Spectrum
-40
-50
-60
-70
-80
0.0 2.5 5.0 7.5 10.0 12.5 15.0 17.5 20.0 22.5 25.0
MHz
12Mar2008 13:10
Stopped
Trigger None
200
mV
0
%
start
PicoScope

www.rife.org


Transformer, Voltage Regulation
T1
Transformer, Power
T2
SW2
Hammond 726
V1 866-A
V2 866-A
Mercury Arc Tubes
GND
L1
Choke, Plate, 20H, 1100 V
Hammond 193C
C1
2uF,2000V
C2
2uF,2000V
HV B+
Transformer, Audio
T7
C4
0.0015uF
R4
250K
+250V
R1
50K
C3
0.0015uF
R2
100K
Gating Oscillator
V3
76
R3
2K
Amplifier
V4
45
Transformer
T8
R5
3K,10W
Choke, RF, 1-3.5mH,1A
L2
C8 0.006uF,2KV
Hartley Oscillator 1
V5
809
L3
C6
0.1uF
6.3V_1
6.3V_2
C7
0.1uF
9-110pF
2KV
Variable
Set at 4.68MHz
C10
C9
0.002uF,2KV
110 VAC
SW1
0 VAC
Transformer, Filament, 2.5V,10A
T3
Hammond 166S2
+250V
C11
40uF, 350V
Filter Choke
L4
Choke, RF, 1-3.5mH,1A
L5
C15
0.006uF,2KV
R7
3K,10W
Transformer, Plate & Filament
T4
6.3V, 2A
250V
0V
250V
5V, 2A
Hammond 270CAX
V6 80
Full Wave Rectifier
can substitute with silicon diodes
Hartley Oscillator 2
V7
809
L6
C13
0.1uF
C14
0.1uF
9 -110pF
2KV
Variable
C17
C16
0.002uF,2KV
Ray Tube
Helium Gas 12mm press
Electrodes 2" apart & 1 1/4 " dia.
7" dia. 3 Liter Pyrex Flask
PT1
Transformer, Filament, 2.5V,2.5A
T5
C12 0.1uF, 200V
R6 1.5K, 2W
Cathode Return for #45 Amplifier
Hammond 166L2
Transformer, Filament, 6.3V,10A
T6
6.3VCT, 10A
0 - 500mA
set for 100mA
Hammond 166S6

For Vern Thompson by - John F. Crane 3-5-51
From O. G. Grunner MD's Records from
Milbank Johnson & Rife & Hoyland's
Conception of Rife Ray Tube
Frequency Instrument - 1951

1936-39 Ray Tube Instrument

Dr. Grunner Schematic - 1951

Redrawn by Jeff Garff & Jim Peters	Rev 3.0 4/11/2008	Page 1 of 1

www.rife.org

Chapter #11

Aubrey Scoon’s Beam Ray replica Rife Machine Re-evaluation

1. Used a ray tube.
2. Used a fixed 3.30 MHz RF carrier frequency.
3. Modulated sine wave audio frequencies onto a sine wave RF carrier frequency.
4. Power usage was about 460 watts. Output to the ray tube about 40 watts.

In 2009 Aubrey Scoon passed away. His web site remained up on the web until the domain name expired last year. Since his web site is no long available and is an important part of this chapter, including this report, we have included all of his information pertaining to his machine on the www.rifevideos.com web site. To fully understand this chapter we suggest that you read Aubrey's information about his Beam Ray replica instrument at this web address:

http://www.rifevideos.com/aubrey_scoons_1939_rife_beam_ray.html

Aubrey Scoon’s 1950's Beam Ray Clinical replica Rife Machine was originally mistaken for an g original 1938-1939 Rife Ray #5 or Beam Ray Clinical instrument built by Philip Hoyland and the Beam Ray Corporation. We now know that it was not an original Beam Ray instrument built by Beam Ray Corporation but it is an exact replica of that instrument. It was originally for sale on www.rife.org. John Bedini and a group of men who had worked with John Crane for a year and a half considered purchasing it. After careful examination of the information available, at that time, they concluded that this instrument was not an original Beam Ray instrument built by the original 1938-1939 Beam Ray Corporation. They concluded that it was built later, perhaps, in the 1940’s by Dr. Rife’s engineer, Verne Thompson. Verne Thompson eventually replaced Philip Hoyland as Dr. Rife’s new engineer and he was building instruments during the 1940's and 1950’s for doctors that wanted Dr. Rife’s machines.

The reason we are re-evaluating Aubrey Scoon's Rife Ray #5 or Beam Ray Clinical replica instrument is this instrument is the second most important instrument that we have analyzed. When it was first analyzed by Aubrey Scoon's team they did not take their original evaluation of this instrument far enough. Had they used a spectrum analyzer there is a possibility that they may have figured out how this instrument really worked, but they did not. Once we determined how the "Original Rife Ray #5 or Beam Ray Clinical" instrument worked we were able to re-evaluate Aubrey Scoon's Beam Ray replica and show that it worked on the same principles and frequencies as the original Beam Ray Rife Machine obtained from Dr. Low. All of Dr. Rife's instruments, from the first to the last, worked on the same principles and the same high RF frequencies, or higher harmonics of Dr. Rife's original frequencies. The method of generating the frequencies may have changed but all the frequencies used in Dr. Rife's machines were based on the original frequencies he found that would eliminate, deactivate or devitalize those organisms he worked on in his laboratory.

For a better understanding of Aubrey Scoon's Beam Ray Clinical Rife Machine we need to give the history of it. Aubrey Scoon and a group of men from England purchased the above instrument believing it was an original Beam Ray Clinical instrument built by the 1938-1939 Beam Ray Corporation. The original Beam Ray Clinical instrument was known to be working on harmonics. Without really knowing it, they purchased a replica of the Beam Ray Clinical instrument. At that time no original instrument had been located. Because of this and the fact that we had no absolute concrete evidence that Dr. Rife's engineer, Philip Hoyland, built this style of audio frequency instrument it was not fully accepted as a genuine Rife instrument. Not even the later 1953 AZ-58 Beam Ray Clinical replica was accepted as a genuine instrument either.

A few years ago, before Aubrey passed away, I was communicating with him about this instrument. In the course of our communications he told me that he believed he had used the wrong main output vacuum tube in the instrument when they worked on it. Because they believed they had used the wrong vacuum tube (812a vacuum tube) the carrier frequency had parasitic oscillations which created harmonics. He said that when they discovered this mistake they put what they believed was the proper tube (809 vacuum tube) in and most of harmonics from the parasitic oscillations were gone. Aubrey Scoon mentions the change of this tube (809) on his web site. But they did not change the photos of the waveforms so we do not know how much the waveform really changed. This much we do know all of the photos of the waveforms on his web site are of an instrument that has parasitic oscillations. Using the wrong tube was a simple mistake that anyone could make but it led to a great deal of confusion causing many to believe, including myself, that this instrument was, an original Beam Ray Clinical instrument because of those parasitic oscillations. We believed these parasitic oscillations created the harmonics which the original Beam Ray Clinical instrument was supposed to be working on.

Both Jim Berger and I separately built Aubrey Scoon's instrument with the correct vacuum tubes (812a) and found using an oscilloscope that the RF output was clean of any parasitic oscillations. In our tests the 812a vacuum tube produced no harmonics like those seen in Aubrey Scoon's photos. At this time it confirmed to us that if the circuit was working correctly there would be no parasitic oscillations or harmonics from parasitic oscillations. The building of this instrument also showed that it didn't have the reported harmonics which the genuine Beam Ray Clinical instrument was supposed to have. Little did we know, at that time, that the harmonic concept we were looking for was there but we didn't really understand how the instrument was supposed to work. This wrongly convinced both Jim Berger and I that Aubrey Scoon's instrument was not a genuine Beam Ray instrument. Nevertheless, this mistake does not change the fact that we now know that this instrument is a genuine Beam Ray machine replica.

At a later date when both the 809 and 812a vacuum tubes were tested in the circuit neither tube created the same kind of waveforms as Aubrey Scoon's machine was producing. This proved to us that the parasitic oscillations are due to some other problem in the RF circuit of his machine. It was also determined that the 812a vacuum tube was the correct tube that should be used, not the 809 vacuum tube. The 812a vacuum produces the correct carrier frequency which should be used with the audio frequencies Aubrey Scoon's instrument used.

www.rife.org

The original Beam Ray Clinical instrument built by Beam Ray Corporation that we obtained from Dr. Low did not have any frequency list that came with it showing us what frequency band or dial settings should be used for the various microorganisms. However, Aubrey Scoon's Beam Ray replica instrument built by Verne Thompson came with a list of frequencies which the doctor used on the various organisms. It is this list of frequencies that makes this instrument so important.

We know from the previous documents that we have read in this report that Dr. Rife had Verne Thompson rebuilding and repairing these instruments. We also read that Dr. Rife had Verne Thompson rebuilt Dr. Yale's machine in 1940. Because Verne Thompson became Dr. Rife's engineer he would periodically repaired Dr. Couche's and Dr. Tulley's machines. We also know that Verne Thompson was making copies of Dr. Couche's Beam Ray Clinical instrument for other doctors. With this understanding we know that Verne Thompson was the one who would have written down these audio frequencies that were used in Aubrey Scoon's Beam Ray Clinical instrument. Also with this understanding we know that the same audio frequencies used in Aubrey Scoon's Beam Ray Clinical instrument were used in Dr. Couche's Beam Ray Clinical instrument. This information is very important. The importance of this information will become very clear as we continue to look at this instrument and the 1953 AZ-58 Beam Ray Clinical Replica instrument.

Since this paper was updated on 9/20/2010 we decided to test a 3.30 MHz RF carrier frequency believing that it could have been the correct RF carrier frequency. When Aubrey Scoon first tested the instrument with the 812a vacuum tube (not the 809 vacuum tube) he listed 3.33 MHz as the RF carrier frequency on his website. Knowing how parasitic oscillations in an RF carrier frequency could easily have shifted the carrier frequency 30,000 Hertz, it was thought that a 3.30 MHz RF carrier frequency would have been a more logical frequency to use. This assumption proved to be correct. In the summer of 2011 we obtained more of John Marsh's documents from his nurse. In one of these documents dated November 20, 1967 John Marsh stated the following:

MARSH: *John Crane's, a simple oscillator, which can be obtained easily for about $33.00. It produces a fuzzy band. He experimented with hooking up wires with an ordinary radio speaker and produced a different musical note for each frequency. The large instrument* [Beam Ray Clinical replica instrument] *is a RF frequency generator which carriers wave oscillations at 3300 kilocycles (3.3 Megahertz) on the marine band. Pre-auditory sound waves.* (John Marsh 1967 document about Dr. Robert P. Stafford).

This letter of John Marsh's confirms that the RF carrier frequency in the original Rife Ray #5 or Beam Ray Clinical instrument, which Dr. Rife, John Crane and John Marsh made a replica of in 1953, was set at 3.30 MHz. This also confirms that the 812a vacuum tube is the correct tube. It also confirms that that the original reading done by Aubrey Scoon of the RF carrier frequency being about 3.30 (3.33) was a correct reading. It was only slightly off due to the parasitic oscillations.

As mentioned before, Aubrey Scoon's instrument had four bands. These four bands were mentioned by Philip Hoyland in the Beam Ray Trial. He stated that they covered all the frequencies for the various organisms this instrument treated. The frequency range of each of the four bands is as follows:

Band 1: 20 Hertz to 200 Hertz.

Band 2: 200 Hertz to 2000 Hertz.

Band 3: 2000 Hertz to 20,000 Hertz.

Band 4: 20,000 Hertz to 200,000 Hertz.

www.rife.org

Our original Beam Ray Clinical instrument, along with Aubrey Scoon's Beam Ray replica instrument design, predates John Crane and John Marsh and this reveals that the audio frequencies came from Philip Hoyland not John Crane or John Marsh. This Aubrey Scoon Beam Ray replica instrument also shows a connection to the original 1938-1939 Beam Ray Clinical Rife Machine and the audio frequencies that were used in the 1953 AZ-58. This AZ-58 instrument will be discussed in greater detail later in this report. The 1953 AZ-58 Beam Ray replica instrument used almost the same frequencies as Aubrey Scoon's instrument except Crane and Marsh divided them down by a factor of 10 times and used these lower audio frequencies in the AZ-58.

Below is a chart that has the audio sideband frequencies that were used in Aubrey Scoon's Beam Ray Clinical replica instrument. It was these frequencies that John Crane and John Marsh lowered to get the audio frequencies they used in the 1953 AZ-58. We will reconcile these frequencies in this chart to Dr. Rife's original high RF frequencies that were used in the Rife Ray #3 and Rife Ray #4 Rife Machines in this section of this report. Before we do this we need to compare Aubrey Scoon's Beam Ray Clinical replica to the original Beam Ray Clinical Rife Machine which we obtained from Dr. Low.

The list of audio frequencies, shown below, of Aubrey Scoon's Beam Ray replica sine wave audio frequencies must be used with a 3.30 MHz RF carrier frequency. Testing of this 3.30 MHz RF carrier frequency showed that this was the correct carrier frequency for this instrument. It was this testing with the 3.30 MHz RF carrier frequency in combination with the audio frequencies which produced the correct sideband frequencies that hit the Rife Ray #3 and Rife Ray #4 higher harmonic frequencies.

What we need to point out here is this **IMPORTANT** fact which came from the analyzing of the original Beam Ray Clinical instrument. This fact also applies to Aubrey Scoon's Beam Ray replica instrument. Neither the 3.30 MHz RF carrier frequency nor the audio frequencies will do anything by themselves. But when the 3.30 MHz RF harmonic carrier frequency and the audio frequencies are combined together they will produce many sideband frequencies. And one of these sideband frequencies will line up with the true Rife M.O.R. frequency and devitalize or render harmless the harmful microorganism. To re-emphasize this so that no one misunderstands. If you just use the audio frequencies by themselves you will get nothing. If you use the 3.30 MHz RF carrier frequency without the audio frequencies you will get nothing. The audio frequencies used in Aubrey Scoon's instrument must have the RF carrier frequency of 3.30 MHz or they are useless. This is the reason the 1953 Beam Ray Clinical instrument called the AZ-58 did not work properly. In the chart, shown below, are the audio frequencies used in Aubrey Scoon's instrument. It is these audio frequencies when combined with the 3.30 MHz RF carrier frequency that will produce Dr. Rife's higher harmonic M.O.R. frequencies. It must be understood that these audio frequencies were not meant to treat these organisms.

Aubrey Scoon's Beam Ray Clinical Replica Audio Sideband Frequencies

B or E Coli Rod	8,020 Hz	Syphilis or Treponema	6,600 Hz
B or E Coli Virus	17,220 Hz	Tetanus	1,200 Hz
BX Virus Carcinoma	21,275 Hz	Tuberculosis Rod	8,300 Hz
BY Sarcoma	20,080 Hz	Tuberculosis Virus	16,000 Hz
Pneumonia or Spinal Meningitis	7,660 Hz	Typhoid Rod	6,900 Hz
Staphylococcus	7,270 Hz	Typhoid Virus	18,620 Hz
Streptococcus	8,450 Hz	Worms	2,400 Hz
Streptothrix	7,870 Hz		

The two photos below show Aubrey Scoon's RF section. The electronic components are almost identical to our original Beam Ray Clinical instrument. It used the same 866 rectifier tubes (two used) along with the 812a vacuum tube (one used).





Like the original Beam Ray Clinical instrument which used a Hewlett-Packard audio oscillator, Aubrey Scoon's Beam Ray replica instrument also used a Hewlett-Packard audio oscillator design. By design we mean that this oscillator used an incandescent light bulb in the circuit (patented by Hewlett-Packard) which stabilized the audio oscillator frequencies and waveform which it output. In the next two photos, shown below, is Aubrey Scoon's Beam Ray Rife Machine audio oscillator. In the photo, below on the right, you can see the small incandescent light bulb.



In 1938 when Beam Ray Corporation built this style of instrument the Hewlett-Packard Wein Bridge audio oscillator was not invented yet. Since this newer Hewlett-Packard audio oscillator patent was not filed until July of 1939 and the Beam Ray Corporation was at this time in a court battle it is only logical that the original Beam Ray instrument did not use Hewlett-Packard's new design. It was invented in early 1939 and a patent was filed July 11, 1939. The patent was granted on Jan 6, 1942.

In 1938 and 1939 the original Beam Ray Clinical instrument would have had an RC (resistor capacitor) type of audio oscillator. These RC audio oscillators were known to be very unstable and it was replaced in the original Beam Ray instrument that we have with the newer Hewlett-Packard design. The audio oscillator section of the original Beam Ray Clinical instrument that we have has many extra

www.rife.org

holes in the chassis and shows that modifications were made to update this instrument to the newer Hewlett-Packard design.

Aubrey Scoon in his evaluation of his Beam Ray replica instrument believed that his instrument was an original machine built by the 1938-1939 Beam Ray Corporation. He was correct that it was an original design but he was wrong about the year it was built. John Bedini was correct in his belief that it was not an original machine built by the 1938-1939 Beam Ray Corporation. The fact that the Hewlett-Packard design patent was not issued until 1942 should have indicated to Aubrey Scoon that his instrument was built later than 1939. Rather than accept that the patent had not been filed until July of 1939 and issue until 1942 he believe that Hewlett-Packard had somehow allowed Beam Ray Corporation the right to use their design before they even filed a patent on it. Of course this does not make any sense since they could have lost any patent rights if they did this. Just this information alone should have indicated that this machine was not an original machine built in 1938-1939.

Aubrey Scoon’s audio oscillator update

Roger Blain, who has had a great deal of interest in this technology, uncovered some very important information about the manufacture date of the audio oscillator design that was used in Aubrey Scoon's instrument. If you look at the above two photos which show both the underside and top view of the audio section of Aubrey's instrument you will notice that there are no signs of any retro-fitting of the audio oscillator to a newer design. If it had been built in 1938 or 1939 then it would have had the original (RC) resistor capacitor design which would have been replace. It also would have showed obvious signs of the necessary changes needed to update the old style (RC) audio oscillator to the newer Hewlett-Packard design which it now has. The next photo, shown below, shows the underside of the audio oscillator of the original 1938-1939 Beam Ray machine obtained from Dr. Low.



You will notice many small holes including two larger old vacuum tube holes (empty and without any vacuum tube sockets) in its chassis. This is what we would expect to see if an instrument's audio section had been replaced with the newer more accurate Hewlett-Packard design. The lack of any modifications to the audio section of Aubrey Scoon's instrument indicates that the instrument still has the original audio oscillator it was built with. Just this fact alone puts the building of his instrument after the original Beam Ray Corporation shut down in 1939.

www.rife.org

Roger Blain decided that if he could determine which design of audio oscillator was used in Aubrey Scoon's instrument then the correct dating of that instrument could be determined. In his discovery work he found that the audio oscillator that was used in the construction of this instrument was the EICO 377. Aubrey Scoon's instrument audio oscillator frequency range and the circuit design are identical to the EICO 377 including the component values, wiring and layout. The only thing that was left out was the double pole double throw switch that allowed for switching between square and sine wave. This new information leaves no doubts as to the approximate date Aubrey Scoon's instrument was built. This information also firmly put its construction date at 1952 or later instead of the 1939 date Aubrey Scoon gives in his report. The next three photos are of the EICO 377.


MODEL 377
SER. NO. A 5655
EICO
REG. U.S. PAT. OFF.
POWER
OUTPUT
D C B A
A B C D
AUDIO GENERATOR
SINE AND SQUARE WAVE
BAND
A B C D
SINE
SQUARE
WAVEFORM
AMPL.
0 10 20 30 40 50 60 70 80 90 100
ELECTRONIC INST. CO., INC. L.I. CITY 1, N.Y.



www.rife.org
www.rifevideos.com

Below are three more photos. The first photo, below on the left, again shows the top view of the EICO 377 component layout. The second photo, below on the right, shows the layout of Aubrey Scoon's audio oscillator. Looking at both of these two photos you can see that the layout is identical. The third photo is a slightly different view of the second photo.







www.rife.org

Once we knew that the EICO 377 was the audio oscillator that was used by Verne Thompson in the building of Aubrey Scoon's instrument we went through John Marsh's papers to see if they happened to mention the EICO 377 instrument. We found in his papers a document which shows that John Crane and John Marsh were using the EICO 377 as a pad instrument. This new style of pad instrument used aluminum discs to come in contact with the body of the user instead of using a plasma tube. Below is a quote found in that document:

"The device consists of: 1. An audio oscillator. These are produced by various firms such as Heath Company of Benton Harbor, Mich.; Electronic Instrument Co. of Long Island City, New York; R.C.A. ; General Radio; Knight Co.; and others as well as our own which was a Hartley oscillator initially.

The model submitted herein is Model 377 EICO which is manufactured and sold by them as a commercial item." (Rife Virus Microscope Institute - EICO 377 document).

It really shouldn't be a surprise that Verne Thompson used the EICO 377 in his building of Aubrey Scoon's original Beam Ray Clinical replica design since he was using it for their pad instrument. Since the EICO 377 was first built in 1952 this dates the building of Aubrey Scoon's instrument to 1952 or later. This is also when the 812a vacuum tube was used by Verne Thompson in the newer design called the AZ-58. The AZ-58, built in 1953, was also a Beam Ray Clinical replica design. This explains why the correct vacuum tube for Aubrey Scoon's machine was not the 1930's 809 vacuum tube but the 1950's 812a tube.

In the 1940's and 1950's Verne Thompson was still building Beam Ray replica designs for those doctors who wanted to own an instrument. It is apparent that he was building instruments for anyone that wanted one and was not exclusive to John Crane or John Marsh since Dr. Rife and Verne Thompson did not meet John Crane until 1950. The Rife documents show that Rife, Crane and Marsh had Verne Thompson build their new machine which they called the AZ-58 in 1953. It used lower audio frequencies (original 1930's audio frequencies divided by a factor of 10 times) than what the original Beam Ray Clinical design used. Even though Verne Thompson was building the AZ-58 he was still building the original 1930's design which used the higher audio frequencies. The fact that Aubrey Scoon's instrument was built in 1952, or later, proves that both designs were being built at the same time in the 1950’s. The 1953 AZ-58 was using the lower audio frequencies (from 120 Hertz to 2128 Hertz) and Aubrey Scoon's original Beam Ray replica was using the higher audio frequencies (1200 Hertz to 21275 Hertz).

Another discovery made by Roger Blain is also important. It is in regards to the Logo emblem that was on the case of Aubrey Scoon's instrument. Aubrey believed that the "B" Logo found on his instrument must have been the original 1939-1939 Beam Ray Corporation emblem. Below is a photo of this emblem. This was actually the Logo of the company that built the instrument case. The company was Bud Industries. This company is still in business today and are building encloses for electronic devices. Their web site is http://www.budind.com. This discovery, by Roger Blain, also indicates that Aubrey Scoon just didn't do enough investigative work or he would have also discovered that this logo was not Beam Ray Corporations logo.



The information in the next two paragraphs should actually be in Chapter 12. But we are also including it here for those who already have a good understanding of the audio frequencies used in this type of instrument. The reason we are including this information here is some people have asked whether the low audio frequencies (120 Hertz to 2128 Hertz) used in the 1953 AZ-58 are actually the original audio frequencies used in the 1938-1939 Beam Ray machine rather than the high audio frequencies (1200 Hertz to 21275 Hertz) used in Aubrey Scoon's Beam Ray replica instrument. This is a good question and it can easily be answered with certainty. The answer is in the math which produces the correct sidebands for each organism. Only the high audio frequencies (1200, 2400, 6600, 6900, 7660, 7270, 7870, 8300, 8450, 8020, 16000, 17220, 18620, 20080, 21275) will produce the correct sideband frequencies which will produce the higher harmonic frequencies from Dr. Rife's original frequencies. Only six of the low audio frequencies (120, 660, 727, 1862, 2008, 2127-2128 or 2127.5 Hertz as given by John Crane) used in the 1953 AZ-58 when multiplied by a factor 10 times give the exact same high frequency used in Aubrey Scoon's instrument. But the other seven (712, 784, 776, 800, 803, 880 and 1552 Hertz) when multiplied by a factor of ten times will not give the correct high audio frequency. These facts reveal which frequency list came first. Since we know that Philip Hoyland designed this Beam Ray Clinical machine and hid the method of using sideband frequencies to produce higher harmonics of Dr. Rife’s M.O.R. frequencies then only the list (Aubrey Scoon’s list) that will produce Dr. Rife’s higher harmonic frequencies could be the original list.

We will point out a few more facts. From the Beam Ray Trial we learned that no one but Philip Hoyland understood how the instrument worked. Not even Dr. Rife, Verne Thompson, John Crane or John Marsh or anyone else understood that the RF carrier frequency had to be matched to the audio frequencies in order to produce the sideband frequencies that would hit the higher harmonic frequencies of Dr. Rife’s original frequencies. John Crane and John Marsh said many times the RF carrier frequency did not matter. In fact, they eventually quit using the RF carrier frequency when they built their 1950's contact pad style instrument. This clearly shows that they did not understand that the original Rife Ray #5 or Beam Ray Clinical instrument worked on harmonic sidebands. Had they understood this simple fact they never would have changed the RF carrier frequency or built their contact pad style instrument without using an RF carrier frequency. They also would not have lowered or changed any of the audio frequencies if they understood the sideband method used by Philip Hoyland. Both frequency lists would be identical except that one list would be 10 times higher than the other list. Only someone who did not understand how the audio frequencies really worked would have lowered them and then changed them. Only the list which came first would have all the correct frequencies. Again this information proves that the high audio frequency list came first. The low audio frequency list used in the 1953 AZ-58 would have come later in the 1950's because it is the list, when multiplied by 10 times, will only produce some of the correct sideband frequencies. Only someone such as Philip Hoyland could have made the high audio frequency list since the high audio frequencies are the only frequencies that will produce Dr. Rife’s higher M.O.R. harmonic frequencies. As we said, the answer to this question is found in the math.

Now we will go back to the EICO 377 and Aubrey Scoon's audio oscillator. Other than the audio oscillator going to 200,000 Hertz (original Beam Ray instrument going to about 42,000 Hertz) Aubrey Scoon's instrument is a replica of the original Beam Ray Clinical instrument. With this knowledge we know that Aubrey Scoon's instrument was a faithful reproduction of Philip Hoyland's Beam Ray Clinical instrument. Just like the original Beam Ray Clinical instrument Aubrey Scoon’s Beam Ray Clinical replica instrument used the sine wave waveform for both the RF carrier frequency and the low audio frequencies. The original machines waveform is shown in the first photo, on the left, at the top of the next page. The second photo, on the right, at the top of the next page shows Aubrey Scoon's instrument's modulated waveform. These two waveforms are similar. The replica that we built of Aubrey Scoon’s instrument does not have any parasidic oscillations and its waveform looks like the original Beam Ray Clinical instrument waveform shown in the first photo, on the left, on the next page.

www.rife.org





The most important information that came with Aubrey Scoon's instrument was the higher audio frequency list which the doctor who owned it used on his patients. Dr. Low's original Beam Ray Clinical instrument frequency list was lost to time. However, Aubrey Scoon's frequency list was not lost so we can use it and reconcile its audio frequencies to Dr. Rife's original high RF frequencies using the side-band method that was used in this style of instrument.

Since we know that Philip Hoyland tested this Clinical instrument in the laboratory he would have calculated the exact audio frequencies to hit the M.O.R.s. The Rife ray #4 frequencies could be one quarter of one percent off, because of the limits of the 1930's technology, if Philip Hoyland only read the frequency one time. This appears to be what happened because the frequencies read in 1935 are rounded to the nearest one thousandth. In 1935 Philip Hoyland needed the information about the range of Dr. Rife's frequencies to build the Rife Ray #4. But in 1936 when he was building the Rife Ray #5 or Beam Ray Clinical instrument he needed more accurate frequencies for this new instrument since it was using the new sideband method. When the math was done using the high audio frequencies it showed that the frequencies were not rounded to the nearest one thousandth, but they were more precise. It is apparent that the testing Philip Hoyland did in the laboratory in the summer of 1936 on microorganisms allowed him to get the most accurate frequency for each organism. In 1935 the Rife Ray #4 frequency given for Streptothrix was 192,000 Hertz but the frequency for the 1936 Rife Ray #5 or Beam Ray Clinical instrument was 191,803. Not only was this frequency just a little different, but all the frequencies were a little different. This indicates that Philip Hoyland took a more accurate reading of the frequencies of each organism in 1936 for use in his new instrument.

When we did the mathematical equations in order to determine if the audio frequencies from Aubrey Scoon's instrument could produce the correct M.O.R. frequencies when used with the 3.30 MHz RF carrier frequency the math had to be done in reverse order. Using the audio frequencies to determine the most accurate M.O.R.s through the sideband frequencies was the only way to figure out what the frequencies were for each organism listed. If these harmonic frequencies, when divided down, were within one quarter of one percent of the Rife Rays #4 original M.O.R.s. then we knew that the 3.30 MHz RF carrier frequency was the correct carrier frequency. This would also prove that the sideband method was the method of producing the M.O.R.s. in the Beam Ray Clinical instrument. Doing this would also show that the two instruments worked identically the same way. Aubrey Scoon's Beam Ray Clinical instrument with its audio frequencies would firmly prove the sideband method was the method that Philip Hoyland developed. Aubrey Scoon's instrument would also prove that Philip Hoyland used at least two different fixed RF carrier frequencies in the instruments in order to help keep anyone from figuring out the secrets of the instruments. If the carrier frequency is different then the audio frequencies will also be different because they have to be properly matched in order to create the sidebands on the correct high RF harmonic M.O.R. frequencies.

www.rife.org

Below is a frequency comparison chart of Aubrey Scoon's Beam Ray Clinical replica instrument. In the "Rife Ray #4 Frequencies In Hertz" column are Dr. Rife's M.O.R. frequencies read by Philp Hoyland in 1935. In the "Aubrey Scoon's Sideband Audio Frequencies In Hertz" column are the audio frequencies used to create the correct sideband frequencies to hit the harmonic Rife Ray #4 frequencies. In the "Rife Ray #4 Frequencies Based on Scoon's Audio Frequencies" column we see the more accurate M.O.R. frequencies that these audio frequencies produce. You will notice in the "Rife Ray #4 Frequencies In Hertz" column that the frequency for Actinomycosis or Streptothrix is 192,000 Hertz and in the "Rife Ray #4 Frequencies Based on Scoon's Audio Frequencies" column is the frequency of 191,803 Hertz. There is only a 197 Hertz difference between these frequencies. If you compare both of these columns you will notice how closely these frequencies match up. All the frequencies which are in the column "Rife Ray #4 Frequencies Based On Scoon's Audio Frequencies" are less than one quarter of one percent off of the "Rife Ray #4 Frequencies In Hertz." Anyone looking at this chart can see that this could not be just a coincidence.

Aubrey Scoon's Sideband Audio Frequencies Reconciled To Rife's Original High Frequency M.O.R.s.

Microorganism *These frequencies were not included in Aubrey Scoon's instrument.	**Rife Ray #4 Frequencies In Hertz**	**Higher Rife Ray #4 Harmonic Frequencies In Hertz**	**Aubrey Scoon's Sideband Audio Frequencies In Hertz**	**Higher Rife Ray #4 Harmonic Frequencies in Hertz Based On Scoon's Audio Frequency and 3.30 MHz Carrier**	***Carrier Difference Frequency**	**Number of Sideband Harmonics**	**Rife Ray #4 Frequencies Based On Scoon's Audio Frequencies**
Actinomycosis or Streptothrix	192,000 Hz	3,264,000 or 17th	7,870 Hz	3,260,650 or 17th	39,350 Hz	5	191,803 Hz
Anthrax	139,200 Hz	3,340,800 or 24th	*10,200 Hz	3,340,800 or 24th	40,800 Hz	4	139,200 Hz
B or E Coli Rod	417,000 Hz	3,336,000 or 8th	8,020 Hz	3,332,080 or 8th	32,080 Hz	4	416,510 Hz
B or E Coli Virus	770,000 Hz	3,080,000 or 4th	17,220 Hz	3,076,140 or 4th	223,860 Hz	13	769,035 Hz
BX Virus Carcinoma	1,604,000 Hz	3,208,000 or 2nd	21,275 Hz	3,214,900 or 2nd	85,100 Hz	4	1,607,450 Hz
BY Sarcoma	1,530,000 Hz	3,059,040 or 2nd	20,080 Hz	3,059,040 or 2nd	240,960 Hz	12	1,529,520 Hz
Gonorrhea	233,000 Hz	3,262,000 or 14th	*9,500 Hz	3,262,000 or 14th	38,000 Hz	4	233,000 Hz
Pneumonia or Spinal Meningitis	427,000 Hz	3,416,000 or 8th	7,660 Hz	3,414,900 or 8th	114,900 Hz	15	426,862 Hz
Staphylococcus Pyogenes Aureus	478,000 Hz	3,346,000 or 7th	7,270 Hz	3,343,620 or 7th	43,620 Hz	6	477,660 Hz
Streptococcus Pyogenes	720,000 Hz	3,600,000 or 5th	8,450 Hz	3,595,750 or 5th	295,750 Hz	35	719,150 Hz
Syphilis	789,000 Hz	3,156,000 or 4th	6,600 Hz	3,154,800 or 4th	145,200 Hz	22	788,700 Hz
Tetanus	234,000 Hz	3,276,000 or 14th	1,200 Hz	3,276,000 or 14th	24,000 Hz	20	234,000 Hz
Tuberculosis Rod	369,000 Hz	3,321,000 or 9th	8,300 Hz	3,324,897 or 9th	24,897 Hz	3	369,433 Hz
Tuberculosis Virus	769,000 Hz	3,076,000 or 4th	16,000 Hz	3,076,000 or 4th	224,000 Hz	14	769,000 Hz
Typhoid Rod	760,000 Hz	3,040,000 or 4th	6,900 Hz	3,037,800 or 4th	262,200 Hz	38	759,450 Hz
Typhoid Virus	1,445,000 Hz	2,890,000 or 2nd	18,620 Hz	2,890,360 or 2nd	409,640 Hz	22	1,445,180 Hz
Worms	?		2,400 Hz				

www.rife.org

We will now give a simple description of how we reconciled these audio frequencies to Dr. Rife's original high RF frequencies which were used in the Rife Ray #3 and Rife Ray #4 Rife Machines. The Rife Ray #4 paperwork gives us the Streptothrix frequency of 192,000 Hertz. Since we know that Philip Hoyland used the higher harmonic frequency closest to the RF carrier frequency in these instruments what we have to do is multiply 192,000 Hertz by 17 to get the closest frequency to the 3,300,000 Hertz. The 192,000 Hertz multiplied by 17 give us a frequency of 3,264,000 Hertz. The difference between these two frequencies is only 36,000 Hertz. This math gives us the method that Philip Hoyland used.

Now Hoyland used an audio frequency of 7,870 Hertz as the frequency to produce the proper sideband spacing in Aubrey Scoon's instrument. If we multiply 7,870 Hertz times 5 we get the frequency of 39,350 Hertz which is the closest frequency to 36,000 Hertz. If we take 3,300,000 Hertz and minus 39,350 Hertz we get 3,260,650 Hertz which would be the higher harmonic frequency which was used by Philip Hoyland on Streptothrix. Now if we divide 3,360,650 Hertz by 17 we get the true frequency of 191,803 Hertz used by Dr. Rife on Streptothrix. Aubrey Scoon's sideband audio frequencies now give us the most accurate frequencies for the organisms since they are not rounded to the nearest thousandth. Those frequencies are found in the chart, on the previous page, with the column labeled "Rife Ray #4 Frequencies Based on Scoon's Audio Frequencies". The math we did for this chart shows that Aubrey Scoon's Beam Ray Clinical Replica instrument works on the harmonic sideband method to produce the M.O.R.s.

It wasn't until we were able to get the original Beam Ray Clinical instrument and figure out how it worked did we have the ability to determine how Aubrey Scoon's replica instrument really worked. Once we understood how these instruments really worked we could finally figure out the M.O.R. frequencies for Sarcoma, Pneumonia and Tuberculosis. This was made possible because some other documents that we have gave a second reference point to work with to help us determine the correct frequency. Worms (hookworms) however, did not have a second reference point so the only way to produce the M.O.R. frequency for worms is through the sideband method using the audio frequency of 2,400 Hertz in combined with the 3.30 MHz RF carrier frequency.

Also included on pages 137 through 144 are the spectrum analyzer graphs showing the sideband frequencies for each organism using Aubrey Scoon's Beam Ray replica instrument audio frequencies with his 3.30 MHz RF carrier frequency. These spectrum analyzer graphs also include Anthrax and Gonorrhea which was not included with Aubrey Scoon's audio frequency list.

On page 145 are photos of Aubrey Scoon's instrument that we built. On page 146 is the schematic of this 1950's instrument. The 866 vacuum tubes have been replaced with solid state rectifiers. Also the old vacuum tube audio oscillator was not included in the case of the instrument. It is easier and more accurate to use Aubrey Scoon's booster amplifier and a modern function generator to produce the audio frequencies that were used in this instrument. The layout of the electronic parts of this instrument is also very important because of the inherent interference problems that come with RF oscillators. Again anyone who would like to build this instrument should have a good understanding of old tube technology. Some parts of this circuit use up to 2000 volts DC with substantial current and can easily kill anyone who is not familiar with this kind of current or voltage. We take no responsibility for anyone who builds this instrument. We recommend that you have professional help.

On pages 147-159 we have included in this report Aubrey Scoon's original report that was on his website. The reason we have included his report in this report is due to the fact that Aubrey Scoon passed away a few years ago and his website is no longer available on the internet. The information that his report gives is very important to those who are interested in how Dr. Rife's machines worked.

www.rife.org

Chapter Summary: We now know that Aubrey Scoon's instrument is a copy Dr. Couches' original Rife Ray #5 or Beam Ray Clinical instrument which Dr. Couche purchased from the original 1938-1939 Beam Ray Corporation. Aubrey Scoon's instrument was built by Dr. Rife's engineer, Verne Thompson, sometime in 1952 or later. Dr. Low's original Beam Ray Clinical instrument, which was built by the original Beam Ray Corporation, was the most important machine found because it made it so we now know that it was Philip Hoyland who built the audio frequency instrument that used a fixed RF carrier frequency. With this information we were able to prove that Aubrey Scoon's instrument was a faithful replica of the original Beam Ray Clinical instrument. It came with a frequency list that the doctor who owned it used on his patients.

When it comes to the audio frequency list Aubrey Scoon's instrument is the most important Rife machine found because it gives us the original audio frequencies used in the original Beam Ray Clinical instrument. With this frequency list we have been able to prove that Philip Hoyland used higher harmonic frequencies of Dr. Rife's original Rife Ray #3 and Rife Ray #4 frequencies in his Beam Ray Clinical instrument. This list also gives us some of Dr. Rife's frequencies which had been lost, such as the BY Cancer virus frequency. This same audio frequency list was lowered by a factor of 10 times and used in the 1953 AZ-58 which was built by Verne Thompson. With this information we have been able to prove that these audio frequencies are not Dr. Rife's original M.O.R. frequencies and that they do not devitalize any microorganisms. These audio frequencies, when used with a 3.30 Megahertz carrier frequency, will produce harmonic sideband frequencies which will hit the higher harmonic RF M.O.R. frequencies found by Dr. Rife. Though Aubrey Scoon did not live to realize how important his instrument was we now know how important this Rife instrument really is. Dr. Low's instrument and Aubrey Scoon's instrument have revealed how Philip Hoyland's Beam Ray Clinical instrument was a harmonic instrument.

In the next chapter we will discuss the 1953 AZ-58 built by Verne Thompson and the history of that instrument in detail.

www.rife.org


Rife Ray #4 192,000 Hertz for Actinomycosis or Streptothrix. The 17th Higher harmonic frequency is 3,264,000 Hertz. Scoon's audio frequency used for the proper sideband spacing is 7,870 Hertz. The 5th lower sideband hit the M.O.R within 1/8 of 1%.

Scoon's Beam Ray Clinical replica instrument 3.30 Megahertz spectrum analysis of sideband harmonic frequencies.


Rife Ray #4 139,200 Hertz for Anthrax. The 24th Higher harmonic frequency is 3,340,800 Hertz. The audio frequency which could be used for the proper sideband spacing is *10,200 Hertz. The 4th upper sideband would hit the M.O.R.

Scoon's Beam Ray Clinical replica instrument 3.30 Megahertz spectrum analysis of sideband harmonic frequencies.

www.rife.org



Rife Ray #4 417,000 Hertz for B or E Coli Rod. The 8th Higher harmonic frequency is 3,336,000 Hertz. Scoon's audio frequency used for the proper sideband spacing is 8,020 Hertz. The 4th upper sideband hit the M.O.R within 1/8 of 1%.

Scoon's Beam Ray Clinical replica instrument 3.30 Megahertz spectrum analysis of sideband harmonic frequencies.



Rife Ray #4 770,000 Hertz for B or E Coli Virus. The 4th Higher harmonic frequency is 3,080,000 Hertz. Scoon's audio frequency used for the proper sideband spacing is 17,220 Hertz. The 13rth lower sideband hit the M.O.R Within 1/8 of 1%.

Scoon's Beam Ray Clinical replica instrument 3.30 Megahertz spectrum analysis of sideband harmonic frequencies.

www.rife.org



Rife Ray #4 1,604,000 for the BX Cancer Carcinoma Virus. The 2nd Higher harmonic frequency is 3,208,000 Hertz. Scoon's audio frequency used for the proper sideband spacing is 21,275 Hertz. The 4th lower sideband hit the M.O.R within 1/4 of 1%.

Scoon's Beam Ray Clinical replica instrument 3.30 Megahertz spectrum analysis of sideband harmonic frequencies.



? Rife Ray #4 1,530,000 Hertz for BY Cancer Sarcoma. The 2nd Higher harmonic frequency is 3,060,000 Hertz. Scoon's audio frequency used for the proper sideband spacing is 20,080 Hertz. The 12th lower sideband hit the M.O.R within 1/30 of 1%.

Scoon's Beam Ray Clinical replica instrument 3.30 Megahertz spectrum analysis of sideband harmonic frequencies.

www.rife.org


Rife Ray #4 233,000 Hertz for Gonorrhea. The 14th Higher harmonic frequency is 3,262,000 Hertz. Audio frequency which could be used for the proper sideband spacing is *9,500 Hertz. The 4th lower sideband would hit the M.O.R.

Scoon’s Beam Ray Clinical replica instrument 3.30 Megahertz spectrum analysis of sideband harmonic frequencies.


Rife Ray #4 427,000 Hertz for Spinal Meningitis. The 8th Higher harmonic frequency is 3,416,000 Hertz. Scoon’s audio frequency used for the proper sideband spacing is 7,660 Hertz. The 15th upper sideband hit the M.O.R within 1/30 of 1%.

Scoon’s Beam Ray Clinical replica instrument 3.30 Megahertz spectrum analysis of sideband harmonic frequencies.

www.rife.org



Rife Ray #4 478,000 Hertz for Staphylococcus Pyogenes Aureus. The 7th Higher harmonic frequency is 3,346,000 Hertz. Scoon's audio frequency used for the proper sideband spacing is 7,270 Hertz. The 6th upper sideband hit the M.O.R within 1/14 of 1%.

Scoon's Beam Ray Clinical replica instrument 3.30 Megahertz spectrum analysis of sideband harmonic frequencies.



Rife Ray #4 720,000 Hertz for Streptococcus Pyogenes. The 5th Higher harmonic frequency 3,600,000 Hertz. Scoon's audio frequency used for the proper sideband spacing is 8,450 Hertz. The 35th upper sideband hit the M.O.R within 1/8 of 1%.

Scoon's Beam Ray Clinical replica instrument 3.30 Megahertz spectrum analysis of sideband harmonic frequencies.

www.rife.org


Rife Ray #4 789,000 Hertz for Syphilis. The 4th Higher harmonic frequency is 3,156,000 Hertz. Scoon's audio frequency used for the proper sideband spacing is 6,600 Hertz. The 22nd lower sideband hit the M.O.R within 1/26 of 1%.

Scoon's Beam Ray Clinical replica instrument 3.30 Megahertz spectrum analysis of sideband harmonic frequencies.


Rife Ray #4 234,000 Hertz for Tetanus. The 14th Higher harmonic frequency Is 3,276,000 Hertz. Scoon's audio frequency used for the proper sideband spacing is 1,200 Hertz. The 20th lower sideband hit the M.O.R exactly.

Scoon's Beam Ray Clinical replica instrument 3.30 Megahertz spectrum analysis of sideband harmonic frequencies.

www.rife.org



Rife Ray #4 369,000 Hertz for Tuberculosis Rod. The 9th Higher harmonic frequency is 3,321,000 Hertz. Scoon's audio frequency used for the proper sideband spacing is 8,300 Hertz. The 3rd upper sideband hit the M.O.R within 1/8 of 1%.

Scoon's Beam Ray Clinical replica instrument 3.30 Megahertz spectrum analysis of sideband harmonic frequencies.



? Rife Ray #4 769,000 Hertz for Tuberculosis Virus. The 4th Higher harmonic frequency is 3,076,000 Hertz. Scoon's audio frequency used for the proper sideband spacing is 16,000 Hertz. The 14th lower sideband hit the M.O.R exactly.

Scoon's Beam Ray Clinical instrument 3.30 Megahertz spectrum analysis of sideband harmonic frequencies.

www.rife.org



Rife Ray #4 760,000 Hertz for Typhoid Rod. The 4th Higher harmonic frequency is 3,040,000 Hertz. Scoon’s audio frequency used for the proper sideband spacing is 6,900 Hertz. The 38th lower sideband hit the M.O.R within 1/11 of 1%.

Scoon’s Beam Ray Clinical replica instrument 3.30 Megahertz spectrum analysis of sideband harmonic frequencies.



Rife Ray #4 1,445,000 Hertz for Typhoid Virus. The 2nd Higher harmonic frequency is 2,890,000 Hertz. Scoon’s audio frequency used for the proper sideband spacing is 16,620 Hertz. The 22nd lower sideband hit the M.O.R within 1/80 of 1%.

Scoon’s Hoyland’s Beam Ray Clinical replica instrument 3.30 Megahertz spectrum analysis of sideband harmonic

www.rife.org

Photos of the rebuilt Aubrey Scoon Beam Ray Clinical instrument

www.rife.org








PLATE TRANSFORMER
728
MADE IN CANADA
REACTOR
193J
MADE IN CANADA




0 VAC
C7
.01uF 1KV
GND
110 VAC
SW1
F
C8
.01uF 1KV
GND
Transformer, Power
T1
0V
GND
Hammond 718
1250 VAC, CT, 200 mA
SS866A Solid State Substitution Rectifiers
Transformer, Filament, 6.3V,10A
T3
Hammond 1665G
DS1
Lamp, 6.3V
V1 SS866A
V2 SS866A
1
2
3
4
Choke, Plate, 10H, 200mA
L1
Hammond 193J
C1
2uF,2000V
GND
R1
10K (2.2K eff to GND), 75W
GND
http://www.scoon.co.uk/Electrotherapy/Rife/BeamRay/booster.jpg
Generator Input
Aubrey Scoons Booster Amplifier
GND
C5
0.47uF,630V
Hartley Oscillator
Choke, RF, 1-3.5mH,1A
L1
HV B+
C4
5.6nf,2KV ceramic
V3
809
GND
C3
270pF,2KV ceramic
C2
5.6nf,2KV ceramic
Choke, RF, 1-3.5mH,1A
L2
Tuning set to 4.68 MHz
B&W #3030 cut in half
2.5" dia. x 5" long
40t
17t
GND
C6
150pF,3KV ceramic
R2
10K (2.2K eff to GND), 75W
GND
PT1
Ray Tube
Helium Gas 12mm press
Electrodes 2" apart & 1 1/4 " dia.
7" dia. 3 Liter Pyrex Flask
Bill Chebs
6" Phanotron Ray Tube
with the 8" Ray Tube electrodes
set 2" apart works best
Reference: Reverse engineered by Aubrey Scoon's British Rife Group
Simplified and updated by Jeff Garff 4/11/08
1942 Aubrey Scoon Instrument. Built for Dr. Rife by Verne Thompson from Philip Hoyland's Beam Ray design
Redrawn by Jeff Garff
Rev 2.0
4/11/2008
Page 1 of 1

www.rife.org

Aubrey Scoon's 1939 Rife Beam Ray Website Report



1) Used a Ray Tube.
2) Used a fixed 3.30 MHz carrier frequency.
3) Modulated sine wave audio frequencies onto a sine wave carrier frequency.
4) Power usage was about 460 watts. Output to the ray tube about 40 watts.

The 1939 Beam Ray Machine?

Aubrey Scoon’s instrument is an important part of this report. We felt that his information about this machine should be added and included in Chapter 11. All of this information was originally on Aubrey Scoon’s web site but since he has passed away his website is no longer available. This information is to important to be lost. Even though we now know that his machine was not built by the original Beam Ray Corporation it is still a copy of the original Rife Ray #5 or Beam Ray Clinical instrument. This machine was built by Verne Thompson in 1952 or later and used the original 3.30 MHz RF carrier frequency. It also used Philip Hoyland’s original audio frequencies that will produce the original sideband frequencies that will would hit the higher harmonic frequencies of Dr. Rife’s original M.O.R.s.

Below is Aubrey Scoon's written Report:

In 1938, a group of British researchers headed by Dr Bertram Winter Gonin, sought to buy some experimental machines from Rife to confirm his work. At that time, Rife had no commercial operation capable of handling the orders and at the instigation of his old friend Ben Cullen, Rife consented to the formation of a commercial company called Beam Rays Inc. At that time, the majority owner of the

www.rife.org

rights to the machine was an electronics engineer called Philip Hoyland. Hoyland had designed and developed all of the original Rife machines since late 1934. Hoyland and Rife became partners in Beam Rays Inc. The company produced a small number of machines but suffered internal conflicts because of the actions of some of the other partners and because of frictions between Hoyland and Gonin's group. Hoyland believed that Gonin and his partners were trying to steal the technology for themselves. Subsequently, the company was destroyed in 1939/1940 when Hoyland brought a lawsuit against Beam Rays in an attempt to stop one of the partners from illegal stock trading and also to dissolve the contract with the British. Fuller details of this are being written up and will be posted here in the near future.

The Beam Ray Corporation produced a number of machines. I'm not sure of the exact number as I have seen varying accounts, but I believe that about 17 machines were produced and shipped to MD's in California. Another four machines were shipped to England to Dr. B. Winter Gonin of the London School of Tropical Medicine. There was some argument between Rife and Hoyland over these machines and their operating principle, however various MD's including James Couche used one of these machines for many allegedly successful treatments of patients for many years.

The U.K. Rife Research Group managed to get access to one of the machines believed to be one of the originals that were shipped to California in the late 1930's. I reverse engineered that machine and present the results below. I have a lot of data on this machine of which this is only part, I will add things as I get time as much of the data needs to be organized properly. The exact date of the machine is unknown - we know that it was built sometime between the autumn of 1938 and the early part of 1939 - so it may actually be a 1938 machine.

I would like to express my thanks to Robert Harrison, an expert valve/tube engineer (I'm not a valve/tube expert) who gave me massive help and support during the reverse engineering process and who corrected numerous silly mistakes that I made! My thanks also to Stuart Andrews and Bob Haining for their help and support in this effort.

Machine Schematic

Below are the machine schematics and links to some photographs. The schematics have been rendered into PDF format which allows them to be zoomed to resolve fine detail.

These machine schematics are only included in the online report due to the fact that some of them would not be readable. Please go to the following web address to obtain these schematics:

www.rifevideos.com/aubrey_scoons_1939_rife_beam_ray_.htm.

WARNING: These schematics are presented for information only. Do not try to construct a copy of this machine unless you are knowledgeable and experienced in high voltage valve/tube work. The tube filaments need to be heated for a couple of minutes before switching on the HT - failure to do this will blow them. In addition, some parts of this circuit use up to 1750 volts DC at substantial current and can easily kill in inexperienced hands.

Booster Amplifier Schematic

At the same www.rifevideos.com link, given above, is the booster amplifier schematic. This is for a transistor booster amplifier I designed. It is possible to separate the Beam Ray machine output stage from the oscillator stage and to drive the output stage directly from a modern digital frequency generator. This allows much more precise and accurate frequency control than the original. But the output

www.rife.org

stage requires over 40 V p-p to drive it properly at 100% modulation and most modern generators are not capable of outputting this kind of voltage. So the booster stage allows a low level signal between 20Hz and 200Khz (the original range of the machine) to drive the output at up to approx 66 V p-p without significant signal distortion (it can be driven at higher inputs of up to 2 V p-p with clipping). An input of 951 mV will cause 100% modulation of the Beam Rays machine and an input of 1.5 V p-p will result in significant over modulation without distortion of the modulating signal itself. The booster amplifier has a bandwidth of approximately 800 KHz and so can also be used as a general purpose wideband, high voltage buffer amplifier as well.

www.rife.org

Plasma Tube Photos

The first two photographs below show the Nazarov phanotron running on the Beam Ray Machine. And below in the third photo is a close-up of the electrodes of the original plasma tube.

www.rifevideos.com



Inside the Beam Rays Machine

The picture below is of the output stage of the machine. The tank coil can be clearly seen on the right with the 812 (should be 809) output triode next to it. The output jacks are in the center top. The HT transformer is at the back left with the two 866 mercury vapour rectifiers in front of it. Picture courtesy of Stuart Andrews.



The next photo below is the underside of the output stage (note that some components on both stages had to be replaced with modern ones to get the machine working because the originals had deteriorated too much).



www.rife.org

And this photo below is of the underside of the oscillator stage.

Beam Ray Carrier Waveform Photographs

Here are various photographs I took of the machine's waveforms on an oscilloscope. Note: these were taken with the 812A tube in place. The waveforms produced when an 809 is used are smoother and more sinusoidal.





These photos on the previous page are the carrier waveforms for both voltage and current. The actual carrier frequency of the machine depends very much on the plasma tube and also on coupling effects between the tube and any person in the vicinity.

This has made it very difficult to get accurate measurements of the machine because even being in the same room as the machine causes the frequency to alter!

However, after many experiments I am reasonably certain that the resting carrier wave frequency, undisturbed by any local effects is approximately 3.33 MHz.

Because the wave is not a pure sine there are strong harmonics at many other frequencies as well. Some of the dominant harmonics have been observed at approximately 2.3 MHz, 4.6 MHz and 9.09 MHz.

Photo Comparison To Earlier Rife Machine

Comparison of wave from original Rife machine (top) with the waveform from the Beam Rays machine (bottom). Note the similarities in the wave envelopes.



www.rife.org

Effect of Modulation Depth

Wave 1 - this is one burst of the tank waveform at 1430 Hz (scope settings on uncalibrated and adjusted for better resolution) and in excess of 90% modulation depth (sine wave).

Wave 2 through Wave 4, this is what happens as the modulation depth is successively increased - Wave 4 is pretty much 100%. The number of cycles per burst (a burst is approx 20ms apart and is set by the mains cycle) decreases with increasing modulation.

Wave 5 - as you enter over modulation, the burst breaks up into smaller chunks.

Wave 6 - at approx 50V p-p modulation the wave is over modulated and consists of single cycle pulses grouped into bursts.



Wave 1



Wave 2



Wave 3



Wave 4



Wave 5



Wave 6

www.rife.org

Analysis Of Beam Ray Machine Operation

Below is a more detailed description and brief analysis of the operation of the Beam Ray machine.

The machine has 3 external controls. The leftmost one is a 4 way rotary switch with positions labeled 1 through 4. These are the (modulation) frequency bands of the machine. The total range of the modulation settings is from approximately 20 Hz to 200 KHz in 4 decades as follows:



Band Frequency Ranges

Band 1: 20 Hertz to 200 Hertz.

Band 2: 200 Hertz to 2000 Hertz.

Band 3: 2000 Hertz to 20,000 Hertz.

Band 4: 20,000 Hertz to 200,000 Hertz.

1
2
3
4
www.rifevideos.com

www.rife.org

www.rife.org

Main frequency Dial Adjustment

The center control is the main modulation frequency dial. This is calibrated in one step units from 0-100. The dial superficially appears to be a vernier dial but isn't, although it is finely marked, of good quality and is geared down, so a single turn does not move it completely from end to end. A resolution of 1/2 a division is easily possible.



Modulation Amplitude Control Dial

The right hand control is the modulation depth control. It varies the modulation applied to the grid of the output triode from 0 to 50 V p-p. The highest setting of 50V p-p is not 100% modulation, but rather over modulation of about 115%.



Treatment Settings

The machine came with some old diary pages with a series of treatment settings scribbled on them. The year of the diary was not shown, just the months but February was shown. It was not a leap year and by matching the days of the week to the dates it had to be 1939. There were the "usual" Rife pathogens plus a few more ailments that I had never seen quoted on any other early Rife machine list. Unfortunately they were not all complete so it wasn't possible to derive the true frequencies for all of them. The anomalies included:

"V" with a setting of band 3, dial 39 - but I have no idea what this is.

"Radiation" with a strange setting of "2-17-3" which could mean band 2 or 3 dial setting 17.

Pain - "20", Iodine Poisoning - "92", Mercury Poisoning - "55", Tissue repair - "58", Scar Tissue - "13", Mucous Colitis - "38", Hemorrhoid - "88", Catarrh - "17", Inflammation - "40" and Irritation - "30".

The ones that could be clearly resolved are shown in the table Below. The treatment frequencies are all approximately 10 times the ones listed in the modern Crane derived frequency lists for the various conditions.

Pathogen	**Band**	**Dial**	**Frequency**
BX Carcinoma	4	10	21275
BY Sarcoma	4	6.5	20080
Typhoid Virus	3	94	18620
Typhoid Rod	3	58.5	6900
Tetanus	2	78.5	1200
Treponema or Syphilis	3	56	6600
Staphylococcus	3	59	7270
Streptococcus	3	63.5	8450
Streptothrix	3	61.5	7870
E Coli Rod	3	62	8020
E Coli Virus	3	89.5	17220
Tuberculosis Rod	3	63	8300
Tuberculosis Virus	3	88	16000
Pneumonia	3	61	7660
Worms	3	24	2400

www.rife.org

Audio Frequency Circuit Analysis

The most striking thing about the Beam Rays audio frequency circuit at first glance is the oscillator section. The machine oscillator is clearly a first generation Hewlett Wein Bridge circuit. What makes this particularly notable is that Hewlett (Hewlett-Packard) only invented the circuit around the time the Beam Rays machine was built. Because it was so new and had not found its way into commercial designs it tends to imply that there might have been some connection between Hewlett and Beam Rays.

I have written a detailed account of the history entitled: "The Hewlett Connection." To read this report go online to: www.rifevideos.com/aubrey_scoons_1939_rife_beam_ray_.htm.

The earlier Rife machines had used the Hartley oscillator circuit which was no where near as stable as the Hewlett Wein Bridge. So the use of this circuit was a big step forward for Beam Rays. The earlier machines had been plagued with apparent frequency instability which made consistent use very difficult. The Wein bridge circuit was an apparent solution, but in practice there was another factor that they apparently did not take into account.

The Beam Rays oscillator is remarkably stable - it drifts by only a few Hertz during normal operation and is superior to many modern analog generators. But it has one major drawback. Tuning is achieved by way of a variable capacitor. This capacitor is connected directly to the tuning dial. The tuning dial is a geared down dial that allows very precise turning of the capacitor shaft. However in practice it suffers from a slight degree of "backlash" - in other words, no matter how carefully you turn the dial, there is always some residual pressure on the rotary shaft - and left to itself for a while this residual pressure or tension causes the capacitor shaft to turn back by a small amount. This is enough to throw the tuning out by a couple of Hertz in the lowest range - and the problem multiplies by a factor of 10 for each higher range. So in the top range the backlash can throw the frequency setting off by approximately 2 KHz. In addition, because the relationship between the dial setting and the actual frequency is non-linear, the problem is always worse toward the top of the scale (i.e. the dial is calibrated

www.rife.org

from 0 to 100 - the problem is much more pronounced near 100 than it is near 0). One of the ways in which this manifests most noticeably is that turning the dial down from a higher number results in a lower overall frequency than turning the dial up from a lower number to the same final setting.

The frequency setting is obviously critical and this may explain why some frequency stability related problems were encountered even with this extremely good oscillator.

The presence of the Hewlett oscillator explains also the general build of the machine. When I examined the machine there were various minor anomalies. One of which was the size of the two chassis. They are both much bigger than they need to be. Also there are two separate chassis and the earlier Beam Rays machines had only one. Another thing is that there is a circuit on the oscillator stage which is not connected and not used. This was probably meant to be able to create square waves by sine overdrive and clipping. Finally the mounting holes on the chassis do not correspond with the mounting holes on the case - someone has drilled new holes in both chassis to remount them in the case. This could mean that the case the machine is in is not the original case it was shipped in. Alternatively it could mean that the chassis were previously mounted in a different way (maybe in a different case) prior to shipping.

Taking all these things together leads me to the conclusion that the machine I examined is probably an original prototype. This makes sense considering that the Hewlett oscillator was so new. Obviously, Phillip Hoyland or whoever built the machine decided to try making the oscillator stage separately from the output stage. The output stage is presumably the same as in earlier Beam Rays machines (it looks the same as a 1937 Beam Rays machine), but clearly they decided to build the oscillator on a separate chassis. The chassis were overlarge to allow for circuit expansion and modification. The unused circuit was probably tested at some point and found to be unnecessary. And it is likely that during development the different mountings were used on some sort of open frame to allow testing and measurement.

But this prototype machine was shipped and sold as a finished unit, why? The answer is probably quite obvious. The machine was produced during the great depression. Everything was expensive; Beam Rays was a small company and needed to keep down costs. The prototype was probably only needed during development. Once everything had been worked out satisfactorily, the prototype was no longer needed - and could be sold for a substantial profit, as it was effectively a working machine of a new design.

The 6SJ7 and 6K6(B) tubes on the combined schematic are the basic Hewlett Wein Bridge oscillator circuit. See "The Hewlett Connection" for a schematic of Hewlett's patented design. The third tube marked 6K6(A) is a simple cathode follower buffer stage, analogous to a modern transistor emitter follower circuit. This circuit has high input impedance, low output impedance and unity gain. It is designed to insulate the sensitive oscillator section from the following output stages. The 6SN7 tube is the unused circuit and as mentioned above was probably meant to be part of a fast clipper amplifier to produce square wave modulation.

The oscillator stage creates a pure sine wave from approx 20 Hz to 200KHz depending on range and dial setting. It also produces a variable amplitude output which can be adjusted from 0v right up to approx 50V peak to peak.

The output stage consists mainly of a single power triode. Although the machine had an 812A triode in it when I got it, I believe the correct original tube was an 809. The machine runs a lot more cleanly and stably with an 809 than an 812A. The stage is self-oscillating; it has a simple regenerative feedback arrangement from plate to grid via two capacitors and the tank coil. The degree of feedback can be adjusted by means of a large power resistor from the grid to ground.

Note: the machine was not actually grounded, the negative end of the supplies connected to the chassis and all "grounds" were actually referenced to the chassis. I found in practice that the chassis did tend to accumulate quite a nasty residual charge after the machine had been operating and so I grounded it which did not seem to affect the operation of the machine. The output stage is actually a Hartley oscillator, although not obviously so, because the output capacitor in series with the plasma tube capacitance represents the "tuning" capacitance of the circuit. The large power resistor in series with the tube affects the oscillator loading, the output field impedance and also the Q of the resonant circuit. Because the plasma tube is an active circuit element, capacitive coupling from anybody in the vicinity of the plasma tube actually causes changes in the oscillator frequency. The "resting" frequency of the output oscillator is around 3.30 MHz using the 812A and an Argon (Nazarov) phanotron tube. When the tube was was changed to an 809 and a 15mm Helium Cheb phanotron was used, the "resting" frequency changed to 4.68 Mhz and the wave became much more sinusoidal .

The output from the modulation oscillator stage is capacitively coupled to the output triode grid via an inductor. The latter is designed to prevent the carrier oscillations from feeding back into the modulation oscillator stage.

The DC HT power for the output triode is derived from a 1235 VAC plate transformer by two 866 mercury vapour rectifiers. The DC output is smoothed via a large choke and a filter capacitor to ground. There is also an RFC choke in the line to the plate. The net voltage at the plate of the triode is only around 550V DC which is consistent with a choke smoothed circuit. However much more interesting is the other end of the tube - the filaments (which double as cathodes) are connected to a direct AC filament heater transformer which means that there is an additional modulation at the 60Hz mains frequency (cathode modulation).

In practice during operation, the machine creates the carrier waveform (which is not very clean and contains a lot of harmonics - it has a superficial similarity to a sawtooth wave).

UPDATE: the carrier waveform is smoother with the 809, but still contains some strong harmonics. The carrier is then amplitude modulated by the sine wave produced by the modulation oscillator. However, in addition, the AC cathode connection causes a further modulation at 60Hz. In effect the modulated wave is chopped into chunks or bursts that are one period of a 60 Hz cycle apart. And the envelope of the wave is effectively the first quarter cycle of a 60Hz cosine wave. In some respects this is like a very crude approximation to a damped wave. I believe that the latter is not a design flaw but rather a feature.

In the next chapter we will discuss the 1953 AZ-58 built by Verne Thompson and the history of that instrument in detail.

www.rife.org

Chapter #12

Dr. Rife and Verne Thompson's 1950's AZ-58 Beam Ray Replica Rife Machine



1. Used a ray tube.
2. Variable RF carrier frequency between 2.20 and 5 MHz. (First used 4.68 carrier).
3. Modulated square wave audio frequencies onto the sine wave carrier frequency.
4. Power usage was about 460 watts. Output to the ray tube about 40 watts.

With the knowledge gained from obtaining the original Rife Ray #5 or Beam Ray Clinical instrument we know that the 1953 AZ-58 design is an updated replica of Philip Hoyland's Beam Ray Clinical Rife Machine. The 1953 version was updated with newer component parts. Dr. Rife's engineer, Verne Thompson had been building this type of Rife Machine during the 1940's and 1950's. We will now cover this information in more depth. This style of instrument worked well as long as it was using the sideband method. From the stress of the Beam Ray Trial, Dr. Rife became an alcoholic and all that he had worked so hard to accomplish was almost destroyed. Many of the doctors had returned their instruments because of AMA threats. Some of these returned Beam Ray Clinical instruments Dr. Rife parted out and sold to anyone who wanted radio parts. Under these circumstances Beam Ray Corporation eventually closed its doors. Verne Thompson became Dr. Rife's engineer around 1940 and built the Beam Ray style Rife Machines during the 1940's and 1950's for anyone who wanted an instrument. The documents show that back in 1939 Dr. Rife wanted to go back to the original principles of his instrument rather than use Philip Hoyland's harmonic Beam Ray Clinical design. This is what Dr. Rife said in a 1939 letter sent to Dr. Gonin:

RIFE: *"I spoke only Friday evening to a Mr. John Chamblin, a radio man now connected with Beam Ray Inc., about the redesign and building of a device according to the old Rife Ray principles; as the present instrument has been so deviated away from that old principle that it is nowhere near the*

www.rife.org www.rifevideos.com

same...those devices which you have are merely working on a harmonic and not a true frequency; and in our research on electronics, we definitely know that there is no possible way of controlling electrical harmonics of a frequency." (Letter from Dr. Rife to Dr. Gonin, May 14, 1939. Page 1 of 3).

Because Dr. Rife didn't understand Philip Hoyland's harmonic sideband method he believed that the harmonics could not be controlled. Sidebands can be controlled by the audio frequency which is used to create them. Had Dr. Rife been given the understanding of how the instrument worked he would have known that they were controllable. Because of this misunderstanding Dr. Rife wanted to go back to the original designs of his earlier Rife Machines. It is also a historical fact that he never did go back to using his original designs like the Rife Ray #4. There is a reasonable explanation for this. Back in the late 1930's and early 1940's the FCC began controlling the airwaves and hundreds of new radio stations were being granted licenses. The RF M.O.R. frequencies which were output by the Rife Ray #3 and Rife Ray #4 were almost all in the A.M. radio band of frequencies and would interfere with these new broadcasting stations. These events probably brought about the continued use of Philip Hoyland's Beam Ray Clinical Rife Machine since it operates out of the A.M. band and in the low ham radio range. In Chapter 9 of this report we also read that Dr. Rife tested Philip Hoyland's instrument, in about 1940, when he had Verne Thompson rebuild Dr. Yale's Beam Ray Clinical instrument. In those tests Dr. Rife found that Philip Hoyland's design would devitalize all the microorganisms. The tests that were done by Dr. Rife showed that this style of instrument worked. This meant that he really didn't need to go back to his earlier designs even though he may have wanted too.

There are a few important facts that should be pointed out. Dr. Rife at any time could have had an original Ray tube instrument built. He had a Rife Ray #4 in his lab that could have been copied. I am sure that he also had access to the Beam Ray Laboratory instrument. These facts, I believe show that it was probably because he knew that Philip Hoyland's design was a good design that he continued to use it. It could also be because of the FCC regulations Dr. Rife either had to use the Beam Ray Clinical instrument design or no longer build one. We know, from the documents, that Verne Thompson was copying Dr. Couches' instrument with its fixed RF carrier frequency of 3.30 MHz. This carrier frequency was well above the A.M. band of radio stations. Since the Beam Ray Clinical instrument used the higher harmonics of the original Rife Ray #4 frequencies this would not cause any problems with the A.M. radio stations. The FCC was, at the least, a contributing factor in why Dr. Rife continued to use Rife Ray #5 or the Beam Ray Clinical design.

With the understanding of this information let us continue on with the history of Dr. Rife's instruments. John Crane met Dr. Rife in 1950 when he inquired about purchasing a drafting set that Dr. Rife was selling. John Marsh met John Crane in 1952 when they were both working at Convair. See photos below. John Crane is the photo on the left and John Marsh is the photo on the right.



www.rifevideos.com

www.rife.org

They both went to talk to Dr. Rife in 1953 to see if he would be willing to help with John Marsh's wife who had cancer. In Dr. Rife's 1961 deposition #123-125 we have the verification that Dr. Rife gave John Crane his frequencies in 1950:

COMPARET: **"***Did you ever explain to John F. Crane, one of the defendants in this case, the principles upon which your electronic frequency-generator is used in the treatment of diseases?"*

RIFE: "*Yes in 1950."*

COMPARET: "*Did you also inform him of the particular frequencies which you had found to be effective in the treatment of various diseases?"*

RIFE: "*Yes. Verne Thompson and I gave the frequencies to John Crane."*

COMPARET: "*When did you furnish him with this information?"*

RIFE: "*In 1950."*

Dr. Rife always said that almost all his frequencies were in the upper bands (139,200 Hertz to 1,607,450 Hertz) so we know that he gave these high RF frequencies to John Crane in 1950. These frequencies would have been the frequencies used in the Rife Ray #4. The audio frequencies that were used in Dr. Couche's Beam Ray Clinical instrument also may have been given to John Crane at this time. There is an interesting correlation of these audio frequencies that needs to again be mentioned at this time which ties these machines together. The higher audio frequencies, which produce the side-band spacing, used in the 1950's Aubrey Scoon, Verne Thompson Beam Ray Clinical instrument were 10 times higher than those used in the Verne Thompson 1953 AZ-58 Beam Ray Clinical replica. It is apparent that these higher audio frequencies were lowered in the 1950's by Dr. Rife, John Crane and John Marsh and were used in the AZ-58 replica instrument. This gives us the knowledge that these audio frequencies came from Verne Thompson's reading of one of these Beam Ray Clinical instruments. The chart, shown below, is a list of the lowered audio frequencies which were used in the 1953 AZ-58.

AZ-58 Lower Audio Frequencies Derived From Aubrey Scoon's Beam Ray Replica Instrument.

B or E Coli Rod	800Hz	Streptothrix	784 Hz
B or E Coli Virus	1552 Hz	Syphilis or Treponema	660 Hz
BX Virus Carcinoma	2128 Hz	Tetanus	120 Hz
BY Sarcoma	2008 Hz	Tuberculosis Rod	803 Hz
Gonorrhea	712 Hz	Tuberculosis Virus	1552 Hz
Pneumonia or Spinal Meningitis	776 Hz	Typhoid Rod	712 Hz
Staphylococcus	727 Hz	Typhoid Virus	1862 Hz
Streptococcus	880 Hz		

The original Beam Ray Clinical instrument we have has an RF carrier frequency of 3.80 MHz. Aubrey Scoon's Beam Ray Clinical replica instrument's RF carrier frequency is 3.30 MHz. The audio frequencies Aubrey Scoon's instrument used, we showed earlier in this report, will not work with the original Beam Ray Clinical instrument that we have because the audio frequencies have to be matched

www.rife.org

to the RF carrier frequency. The AZ-58's RF carrier frequency was set at 4.68 MHz as written down on the schematic and as per the FCC. Aubrey Scoon’s Beam Ray Clinical instrument audio frequencies would not produce the correct sideband spacing with the AZ-58 RF carrier frequency because the audio frequencies are calculate to work with a 3.30 MHz RF carrier frequency not a 4.68 MHz RF carrier frequency. This also verifies to us that Philip Hoyland was using different RF carrier frequencies in the Beam Ray Clinical instrument. It also indicates that both Rife and Verne Thompson did not understand the importance of using the correct RF carrier frequency with the correct audio frequencies.

John Crane said this in his “Crane Report”:

CRANE: *“The instruments were completed by Crane and Thompson in 1953, but the test results were negative.”* (The Crane Report” page 6).

With the carrier frequency set at 4.68 MHz as per their FCC license, instead of 3.30 MHz, the audio frequencies they used would not make the correct sideband spacing and the instrument wouldn’t have worked like they expected. Logically, if they understood the relationship of the RF carrier frequency and the audio frequencies they would have change the RF carrier frequency back it to 3.30 MHz or recalculated new audio frequencies to work with the 4.86 MHz RF carrier frequency, but they didn’t do either.

Even with the wrong RF carrier frequency Dr. Rife, John Crane and John Marsh would have first tried the higher audio frequencies in the sine wave waveform like the original Beam Ray Clinical instrument used. Apparently when this didn’t work, because the carrier frequency was wrong, they lowered the audio frequencies by a factor of 10 times and then changed the sine wave waveform to a square wave waveform. This appears to be the first time square wave was used. This change from sine wave to square wave wasn’t really necessary since the circuit design will create a square wave looking waveform out of a sine wave anyway. The photo, shown below, is of AZ-58 waveform.



Using the square wave waveform would not have changed how the sidebands would have worked. But it would have created true square wave harmonics which the instrument did not have when it was using the sine wave waveform. John Crane mentions that this is when the instrument started to work better. So we are left to assume that he was referring to the use of the square wave waveform. It is ironic that they used a square wave waveform that produces harmonics in order to get the instrument to even begin to give them any results. Had they really understood how the audio frequencies interacted with the RF carrier frequency they would have recalculated the audio frequencies to work with the new 4.68 MHz carrier frequency instead of lowering the audio frequencies by a factor of 10 times. Then the square wave waveform change would not have been necessary. These important facts that have been pointed out again show they did not understand the relationship between the RF carrier frequency and the audio frequencies. All they managed to prove is neither the carrier frequency nor the audio frequencies will do anything by themselves.

www.rife.org

This change from sine wave to square wave also created a whole new methodology of using frequencies. Instead of relying on the interaction of the sine wave audio frequency with the sine wave RF carrier frequency to produce the correct sideband harmonic M.O.R. to devitalize the organisms they were now depending only on the harmonics from the square wave waveform to hit the correct M.O.R. frequency. This change was also another indication that they didn't understand how the Beam Ray Clinical instrument worked.

Another thing that shows that they did not understand how the Beam Ray instrument worked is the fact that they didn't recalculate the audio frequencies to properly use the square wave harmonics to hit the high frequency M.O.R.s. This shows that they believed that the lower audio frequencies, which they were using, were the M.O.R.s. of the organisms even though they had no harmonic relationship with the original M.O.R.s. used in the Rife Ray #4. We must point out that the square wave mathematical method we are talking about here is completely different than the harmonic sideband method which Philip Hoyland used.

In many of the documents we find that both John Crane and John Marsh firmly believed that these lowered audio frequencies were the M.O.R. frequencies that would devitalize the organisms. Even Dr. Rife appears to have believed that the audio frequencies were the M.O.R.s. as long as they were used with Philip Hoyland's Beam Ray Clinical design. In Dr. Rife's original equipment like the Rife Ray #3 and the Rife Ray #4 he knew that the M.O.R. frequencies were the high RF frequencies. But since Dr. Rife didn't really understand exactly how Philip Hoyland's instrument worked it appears that he accepted the concept that the audio frequencies were the M.O.R.s, or created the M.O.R.s, as long as they were used with that style of instrument. Without understanding these facts it is hard to understand the rest of the history of Dr. Rife's instruments. The fact that they believed that the audio frequencies were the M.O.R.s. compromised the effectiveness of the 1953 AZ-58 Beam Ray Clinical replica.

Below and on the next page are four photos of ray tube instruments which Verne Thompson built. The first instrument was Aubrey Scoon's 1950's Beam Ray replica. The second instrument is believed to have been built in 1947 but some of the transformers are 1960's vintage which indicate it was built in the 1950's or 1960's. The audio frequencies used in it were even lower than the 1953 AZ-58. Since all the evidence we have shows that the lower audio frequencies began with the 1953 AZ-58 this indicates that the instrument was not built in 1947 but was built sometime after 1953. The third and fourth photos, on the next page, are of two of the AZ-58 instruments built by Verne Thompson in 1953 for Dr. Rife, John Crane and John Marsh of Life Labs Co.

www.rifevideos.com



www.rife.org



www.rifevideos.com
www.rife.org

All four of these instruments, like the Beam Ray Clinical instrument, had the fixed Hartley Oscillator section which created the RF carrier frequency. Verne Thompson changed the 809 tube to the 812 tube as he updated the instruments from the 1940's to the 1950's. All three instruments also had one main frequency dial for adjusting the audio frequencies. The other two smaller dials were for adjusting the modulation amplitude of the audio frequencies and changing the audio frequency bands. These bands would take you through the various audio frequency ranges. The AZ-58 was limited to about 6000 Hertz, using 3 bands, because they lowered the audio frequencies. The original Beam Ray Clinical instrument we have went to just over 40,000 Hertz using 4 bands. The 1950's Aubrey Scoon Beam Ray Clinical replica instrument could go to about 200,000 Hertz using 4 bands. Other than the bands there is very little difference in the way these instruments worked. We built two of the three, tested them, and found no significant difference other than the use of sine or square wave audio frequencies. At any time the AZ-58 could have been changed to work on the original Beam Ray Clinical sideband method just by adding a fourth band and then recalculating the audio frequencies to work with the 4.68 MHz RF carrier frequency. As pointed out before we made some tests with the spectrum analyzer to see if square wave could be used instead of sine wave in creating the proper sideband spacing and found that the square wave waveform produces the same sidebands as the sine wave waveform.

The basic design of Philip Hoyland's Beam Ray Clinical instrument is very apparent when you compare the schematics. Six of the 1953 AZ-58's were originally built by Dr. Rife, John Crane and John Marsh. We decided to test the AZ-58 with the spectrum analyzer. Below in the graph you can see the results of these tests.

Testing done with PicoScope 3205 spectrum analyzer at 2,400,000 Hertz using AZ-58



Sine wave out of AZ-58 at 2,400,000 Hertz.



AZ-58 without ray tube at 2,400,000 Hertz measured with spectrum analyzer showing no real harmonics.



Sine wave carrier out of AZ-58 at 2,400,000 Hertz using ray tube. Sine wave carrier was always distorted when put through a ray tube.



AZ-58 at 2,400,000 Hertz using ray tube. Measured with spectrum analyzer showing harmonics all the way up to 20,000,000 Hertz.



AZ-58 at 2,400,000 Hertz using ray tube. Showing 50% square wave audio frequency modulation. The square wave shows some distortion.

www.rife.org

The instrument called the AZ-58 is significant because we have more information about what took place in the 1950's than any period before this. At this time in the 1950's John Crane and John Marsh recorded interviews with Dr. Rife, Dr. Couche, Ben Cullen, Henry Siner and many other individuals who were key players in the early years of Dr. Rife's work.

We will now cover in more detail the history of the 1953 AZ-58 instrument so we have more information about this instrument. Some of the information comes from the John Marsh Collection of Rife audio CD's. As we said, in 1950 John Crane met Dr. Rife and in 1952-53 he met John Marsh. John Marsh became John Crane's supervisor at Convair Aeronautics when John Marsh moved from Tucson, Arizona to California. John Marsh's wife had cancer and they were not able to help her in Tucson. The doctors recommended that he take her to San Diego for specialized care. John Marsh and John Crane became friends. John Crane told John Marsh about Dr. Rife and they went to see him. Dr. Rife gave them an old Beam Ray Clinical instrument which they had Verne Thompson repair. John Crane and John Marsh then used this instrument on John Marsh's wife and after several treatments John Marsh said she fully recovered. Here are John Marsh's statements which he made in 1976 and 1986:

MARSH: (1976) *"I met this Rife. I said Dr. Rife, I said, my name is John Marsh, I've got a wife that's dying. She's got cancer of the uterus." Dr. Rife said: "I won't touch that thing with a 20 yard pole."*

After some discussion Dr. Rife said:

RIFE: *"I have an old instrument down here in the basement."*

MARSH: *"I dug up that old instrument and of course it had tubes in it, antique stuff, and so I rebuilt the darn thing."* (John Marsh Rife CDs, CD 10 track 1)

MARSH: (1986) *"I went to see him* [Dr. Rife], *and I talked with him and he said he didn't want to have any part of it...I said look, I got a wife that's dying and I need your help! And so I got him out of his cocoon, so to speak, and we took an old instrument and rebuilt it. And I treated my wife and by darn all the pain left her and she got well." In another part of the tape he said: "I discovered that this Dr. Rife was a very great individual...I told John* [Crane], *I said look if we have any of those old instruments laying around loose, let's rejuvenate one of them and see if we can get my wife well. Well Verne Thompson who was with the San Diego police department radios, uh, radio expert, uh, had built some instruments and they were antiques when I saw them."* (John Marsh Rife CDs, CD 2 track 3).

John Marsh and John Crane then decided they would like to work with Dr. Rife and try to get the frequency instruments rebuilt and back into doctor's hands. They wanted to help people who were suffering from many incurable diseases. From earlier quotes we learned that Verne Thompson had worked on Dr. Yale's Beam Ray Clinical machine. He knew how to build these instruments and this is why John Marsh and John Crane had him repair the instrument that Dr. Rife gave them. It is apparent that Verne Thompson knew this instrument's circuit designs very well but he didn't understand how the Beam Ray Clinical instrument was using harmonic sidebands to hit Dr. Rife's higher harmonic M.O.R.s. From a patent application that Dr. Rife and Verne Thompson filed we know that Verne Thompson also believed the audio frequencies were the M.O.R.s. This document leads us to only one conclusion; no one in the 1950's understood how Philip Hoyland's sideband spacing method worked.

John Crane in his later years (1970's & 1980's) was not being very truthful in some of his statements. He said this in his paper titled "The Crane Report":

CRANE: *"Unfortunately, Rife had enlisted the help of electronic experts in the '30's who never wrote down the details of the instruments. Rife was unable to duplicate the marvels of his earlier Frequency instruments."* (The Crane Report, page 6).

www.rife.org

The documents we have read in this report show that Dr. Rife was having Verne Thompson build and repair the Beam Ray instruments originally built in the 1930's. For this reason we know that John Crane's statement, in his report, was not truthful. The facts have shown that this instrument design came from Philip Hoyland. It was Verne Thompson who updated the Beam Ray Clinical instrument for Dr. Rife, John Crane and John Marsh in 1953. If Verne Thompson was building these Beam Ray Clinical instrument then he surely would have had a schematic for them.

Others have felt that John Crane took advantage of Dr. Rife. This may be true in some things that took place later on in the late 1960's, 1970's and 1980's but the evidence does not support this in the 1950's and early 1960's. Here is a quote from the John Marsh Collection "Trip to Dayton Ohio Papers" and Gonin Papers. Dr. Rife, John Marsh and John Crane were talking at great length about John Marsh's trip to Ohio to see Dr. Robert P. Stafford M.D. In the Gonin papers they talked about the frequencies. I would recommend that everyone read these papers because they show that Dr. Rife, John Crane and John Marsh worked as a team. They also show that John Marsh and John Crane considered the frequencies to be Dr. Rife's and the AZ-58 Beam Ray replica instrument to be Dr. Rife's instrument. The following statements confirm this:

RIFE: *"Well I have lived my life for the benefit of humanity, and it is the end result of the accomplishment."*

MARSH: *"Yes, now here is what I did tell them. They wondered where I fit into the picture. I told them I had lay outs at the base, I designed part of it. You would say that I was possibly not an exactly an inventor, but I think we are all co-inventors of a sort by adding what we think would make the instrument better and if they try to validified* [verify] *any of the statements that I have said to them please don't let me down, and say no this isn't so, which might upset what might be the truth to them. I mean just by accident. Now what I mean by that is this. I don't think that I have in my own right lied to them. I did [didn't] try to impress them with the idea that I was the one that did it. I did impress that you* [Dr. Rife], *John Crane and myself had worked together on this thing, but that you* [Dr. Rife] *were inventor and John* [John Crane] *was the designer and inventor, co-inventor and myself for putting this thing together and making it. They asked if I helped putting this thing together and making it from time to time. I couldn't tell them that I didn't, because if I had built up a feeling in them that I knew nothing about what I was doing; psychologically that could have torn down, or have caused delay the foundation that now is laid. Now I think we have a solid footing there. I under no circumstances would want that torn down, and I will not under any circumstances accept the credit for this instrument as being invented, because it is Rife's instrument as printed on the plate in front and that is one of the reasons in building you up to them, which I don't think is unwarranted; not by a darn sight, and that is why they want you there. They want to hear you talk, and they also want to know your past experiences with the people of La Jolla and also I was very happy to have received the paper concerning the Dr. etc., because I'm sure Stafford will contact every blooming Dr. that you had given him to me and I turned over all the letters to him, because I didn't want anything to stand in the way if he could contact him, now whether he would do that, before he would talk to the group, and I do not know. I suppose he will, but he wants the truth as badly as you do. Now I don't know an easier way it can be done. I don't think there is going to be an easy way to get it on, but I think I've outlined this thing. I studied the moves I was going to make before I ever went there. I studied what I was going to do if I had the opportunity to do so, which I did."*

RIFE: *"Well I think that you did a very excellent job."* (1957 John Marsh trip to Dayton, Ohio #8, 9 and 16)

And in the John Marsh Collection, Gonin Papers we read:

CRANE: *"So the frequencies* [audio] *we have written down. I will give you those or Rife will give them to you. I think you ought to have them. Each one [organism] has a different frequency, you see. I don't*

www.rife.org

remember any of them off-hand. I should memorize them all, but I haven't yet. I've just written them down and they are in the lab."

GONIN: *"Those frequencies that you have written down, would only apply to your own machine* [AZ-58], *wouldn't it?"*

CRANE: *"That is because they have been calibrated for each machine. Each machine has its own calibration."*

GONIN: *"And that's constant?"*

CRANE: *"Yes."* (John Marsh Collection, Gonin and Siner Papers, Page 15)

After reading these documents the facts stand out that all three of these men knew the audio frequencies and they were not John Crane's invention. Both John Marsh and John Crane considered the instrument to be Dr. Rife's. Dr. Rife also had a plaque on the front of the instrument with his name on it. It is also clear from John Marsh's papers that Dr. Rife was not on the sidelines but he a working partner in Life Labs. Dr. Rife by this time had become what some people call a "working alcoholic." This type of drinker would have a little to drink during the day to take the edge off but would not be a total drunk. The documents show that Dr. Rife knew the audio frequencies that were used in the AZ-58. But it is clear that he didn't understand how those audio frequencies worked with the RF carrier frequency with Philip Hoyland's design. On the Rife CD's all of Dr. Rife's recorded conversations were very positive about the 1953 AZ-58 instrument. This does not sound like a man who was ignorant of what was going on, as some have claimed.

Anyone who reads the documents from this period of time can tell that there were a lot of high hopes for this instrument and the lower square wave audio frequencies it was using. Now the real question is how well did this instrument work when it was only working on square wave harmonics? There were a lot of good reports on how well the instrument worked but what really counts is how well it worked in the hands of the doctors who used it on their patients. Dr. Robert P. Stafford M.D., used the AZ-58 for 5 years on his patients and wrote a report and sent it to Dr. Rife, John Crane and John Marsh. The photo below is a picture of Dr. Robert P. Stafford M.D.

www.rifevideos.com
www.rifevideos.com
www.rifevideos.com

www.rife.org

Dr. Stafford's report is very favorable on many conditions that he used the AZ-58 on but when it came to cancer this instrument did not work as well as the Beam Ray high frequency harmonic side-band method. Dr. Stafford's report showed he treated 16 cancer patients and had a varied response rate using the AZ-58 on cancer. We must point out that the instrument did temporarily help some of his cancer patients while others did not see any benefits. Two of the women that he treated received a great deal of benefit but died from other complications. This made it so that he could not say they were cured by the instrument. When the first woman was autopsied she only had a small amount of cancer left in her breast. When Dr. Stafford started treating her she had cancer in several other places including her neck. Had she not died from a fall she probably would have fully recovered.

The second woman had cervical cancer for which other doctors used a great deal of radiation therapy. Dr. Stafford treated her at the hospital and after about four weeks she went home. She died of radiation damage that was done to the tubes that go from the kidneys to the bladder. When she was autopsied they found no cancer cells in her abdomen. In this case the cancer was completely gone. Since neither of these women lived for at least five years they could not be considered cured. So Dr. Stafford could never say that he had cured anyone of a terminal malignancy. He said this about the AZ-58 square wave audio frequency instrument:

DR. STAFFORD: *"As yet, we have failed to "cure" any case of advanced, terminal malignancy. It appears in several instances that we may have impressed the disease favorably, temporarily. It is difficult to rule out the psychological, morale booster effect to the terminal patient when some definitive effort is made again in his behalf. However, several improvements have appeared to be more physical than emotional...All the patients in the series were treated with the same frequencies (e.g., 728 - 784 - 880 - 2008 - 2128). Perhaps these frequencies may be wrong, or only nearly correct."* (John Marsh Collection, Dr. Stafford's Report on using the AZ-58, page 4).

It is clear that Dr. Stafford was questioning the accuracy of the square wave audio frequencies and felt that something was wrong. Everyone who has been around Rife technology for a long time has seen the very same results as Dr. Stafford. From time to time we see that someone has an amazing experience of recovery from cancer but for the majority this does not happen. Today these frequencies **728, 784, 880, 2008 and 2128** Hertz which Dr. Stafford used are the same frequencies used by just about everyone for cancer.

Many have wondered why the AZ-58 worked well for a few patients and not for others. We believe we know the reason why. The RF carrier frequency is the reason it worked. The AZ-58 RF carrier frequency was set at the new 4.68 MHz to comply with the new 1950's FCC license. Dr. Stafford changed the RF carrier frequency using the variable capacitor to operate between 3.10 MHz to 3.30 MHz with the two women who were treated for cancer. He also used this same RF carrier frequency with some of his other patients. If per chance the RF carrier frequency was set at about 3.20 MHz it would have been only about 15,000 Hertz off of the second higher harmonic of Dr. Rife's original BX cancer virus frequency, which was 3,214,900 Hertz. This second harmonic of the BX (1,607,450 X 2 = 3,214,900 Hertz) was the primary frequency used by Philip Hoyland in the Beam Ray Clinical instrument for the BX cancer virus. If an audio frequency of 2128 Hertz (AZ-58 BX audio frequency) was used, and it was, it would have created many harmonic sideband frequencies and the 7th harmonic sideband frequency would have hit Dr. Rife's higher harmonic BX frequency of 3,214,900 Hertz. We need to keep in mind that Dr. Stafford also used 728, 784, 880 and 2008 Hertz. It would have been almost impossible for him not to hit the BX frequency of 3,214,900 Hertz with one of the sidebands from all these frequencies. If we also take into account the "one tenth of one meter" tolerance frequency of 858 Hertz it gives room for the frequency to be off a few hundred Hertz and still work. What we have just explained is the reason why we think the AZ-58 worked so well on these two women.

www.rife.org

It is also known that Dr. Stafford tried other RF carrier frequencies. Once he changed the RF carrier frequency the instrument would have been relying completely on the harmonics from the square wave waveform of the audio frequency. This would have greatly affected the outcome of his testing. The fact is the square wave harmonics method did not work as well as the Beam Ray Clinical sideband spacing method. **The real problem is almost everyone believes the square wave audio frequencies are Dr. Rife's true M.O.R. frequencies.** The evidence shows that John Crane and John Marsh believed the audio frequencies were the true M.O.R. frequencies and they had given this understanding to Dr. Stafford. Without the correct understanding of how the instrument worked Dr. Stafford would not have understood how important the fixed RF carrier frequency was. If he changed it off of the 3.20 MHz RF carrier frequency many of the 16 cancer patients could have been affected negatively. Dr. Stafford followed these 16 people over many years and in some cases things looked good at first, but the people eventually died from their cancer anyway. One thing that needs to be pointed out is we do not know if Dr. Stafford treated many of his patients over a long enough time period as Dr. Couche and the other doctors did their patients.

In the 1934 clinic 16 patients who had cancer and tuberculosis were treated and considered clinically cured. This is quite a contrast; 100% success in 1934 using Dr. Rife's high RF frequency method. And a very limited success rate on cancer for the low square wave audio frequency harmonics method. Only when Dr. Stafford accidently used an RF carrier frequency close to the BX cancer virus frequency did the AZ-58 seem to get good results. Dr. Stafford used the AZ-58 instrument for a little over five years and sent his report to John Marsh. I am sure John Crane received it also. The big question that needs to be asked is why did John Crane and John Marsh continue to tell people these low audio frequencies were the frequencies which Dr. Rife used in the 1934 clinic when the medical proof showed they didn't work as well as the high RF frequencies? This again clearly shows they did not understand the sideband method. We have to ask the question, why do people today continue to say these frequencies cure cancer even after they have seen the same results? Could it be because having had a few good results they ignored the evidence and fool themselves? By the time all the evidence was available, John Marsh and John Crane were in jail on three or four different legal counts, one of which was for treating a woman without a medical license.

Dr. Rife did not want to have anything to do with all the legal trouble they were in. He was able to avoid it because he never made any claims and he would never treat anyone. The legal problems shut down Life Labs. Had this not happened I wonder if Dr. Rife would have ignored this evidence? I do not believe he would have. He would have realized that the changes they made to the instrument which depended solely on square wave audio frequency harmonics compromised its effectiveness. I think Dr. Rife would have eventually realized that they didn't fully understand how the Beam Ray Rife Machine worked and he would have gone back to the higher audio frequencies and put the RF carrier frequency back on 3.30 MHz. We will never know what he would have done because I do not think Dr. Rife ever read Dr. Stafford's report. This is because John Marsh received the report after he and John Crane were released from jail.

The troubling thing is this, because so few really understand Dr. Rife's early instruments and how Philip Hoyland's Beam Ray Clinical Rife Machine worked almost all frequency generators have been built using this limited square wave audio frequency harmonic method. The people who purchase these low square wave audio frequency instruments have been led to believe it is the same type of instrument used in the 1934 clinic. All because we didn't know the truth. Are people today just fooling themselves also? Are we trying to get these same square wave audio frequency harmonic type instruments and the frequencies they use to do what Dr. Stafford could not get them to do? Cure cancer? We know there have been incredibly good results on many other conditions using audio frequencies which show this type of instrument and method is of great worth but the truth is sometimes hard to accept.

www.rife.org

As we have already read, Dr. Stafford came to suspect that the audio frequencies were not true M.O.R.s. Another letter written by Dr. Stafford to Dr. Edward Jeppson in Salt Lake City also confirms his concerns. He wrote this letter to Dr. Jeppson because he was having the same type of results that he was having. Here is his statement from his letter:

DR. STAFFORD: *"Please excuse my format in the following letter for I intend to ramble a bit and forget strict grammatical dictum. I am writing you at this time partially because John Marsh informs me in a recent letter that you may be somewhat disheartened or at least worried about your role in the experimentations with the Rife Machine. Believe me, Dr. Edward I know how you feel for I too have been through this same feeling with this matter. I have observed clinical results after treatments with this gadget which I can scarcely believe myself. Yet, despite these good results, I have been confused by some rather simple failures such as a recent experiment which I conducted at Good Samaritan Hospital where we used the machine to treat some cultures of Staph Aureus and Strept. Fecalis. In this work we failed to inhibit growth at all or influence the cultures with the Rife Rx. I sent the results to John Marsh and asked for clarification and to be very frank I am not satisfied with John's excuse of the failure as described by Dr. Rife. I am afraid I'm not a very good apostle for I'm getting some ideas myself on how this thing may work. I really wonder if this ultrasonic kills bacteria and virus at all or does it work like other forms of ultrasonic and merely stimulate the tissue in some unusual manner thereby improving the circulation and secondarily enhancing the body's defenses against infection…To summarize some of this rambling: I feel that the Rife Ultrasonic Therapy has a very definitely beneficial effect on the human (and canine) body...I furthermore feel that we, as doctors of medicine, using this machine must remain constantly alert to the condition of our patient and vary the Rx as indicated."* (Letter from Dr. Stafford to Dr. Edward Jeppson dated, April 1, 1958).

Clearly Dr. Stafford was questioning whether the audio frequencies were correct. Little did he know they were not the same frequencies used with the Rife Ray #3 or the Ray #4 instrument? The AZ-58 could have output the higher harmonic sideband frequencies that Philip Hoyland used in his Beam Ray Clinical instrument if they had only understood how it really worked. Whatever was told to Dr. Stafford by Dr. Rife through John Marsh it did not satisfy Dr. Stafford's concerns. Dr. Rife, John Crane and John Marsh probably felt that Dr. Stafford had just made some errors in his work. The one thing that Dr. Stafford did inadvertently find out was the AZ-58 using the square wave audio frequency harmonic method did not kill organisms in the laboratory at the hospital. In the 1950's Dr. Rife no longer had a laboratory for testing any microorganisms. There is no evidence they ever tested just the square wave audio frequencies with Dr. Rife's microscopes. So they did the only thing they could. They let the doctors use the AZ-58 and tell them how well it worked. We must keep in mind that the instrument Dr. Rife gave to John Marsh and John Crane was an original Beam Ray Clinical instrument which used the harmonic sideband method developed by Philip Hoyland. It used the correct higher audio frequencies and the correct 3.30 MHz RF carrier frequency. This instrument apparently worked because John Marsh said it cured his wife of cancer. Again the fact is the AZ-58 Beam Ray Clinical instrument using square wave audio frequency harmonics never worked as well as Philip Hoyland's sideband method. It also didn't work as well as the Rife Ray #3 or Rife Ray #4.

The square wave harmonic method used in the AZ-58 produced very good results on many conditions but not the results hoped for on cancer. But still even with the changes the AZ-58 worked very well on many different conditions. These square wave audio frequencies are what people have been using for the past 50 years believing they were Dr. Rife's true M.O.R.s. All this time not knowing they were not Dr. Rife's original frequencies which he used in his earlier instruments built in the 1920's and 1930's. It wasn't until the papers from the 1939 Beam Rays Trial, John Marsh Papers, Kennedy Company equipment spectrum analysis and Philip Hoyland Beam Ray Clinical Rife Machine spectrum analysis came to light did we have the ability to finally figure out where all these frequencies came from. This information finally reveals which frequencies were the correct M.O.R.s. Notwithstanding the various setbacks Dr. Stafford was still amazed at the results he achieved with the AZ-58.

www.rife.org

Since we were able to obtain access to John Marsh's papers we were also able to discover that in 1976 John Marsh had some of these low square wave audio frequencies tested on microorganisms by a laboratory using his 1970's model of the AZ-58 Beam Ray Clinical ray tube instrument. Keep in mind that this instrument was miscalibrated like all the 1950' AZ-58 Beam Ray Clinical instruments. It was also only working on square wave harmonics. He paid for these tests and they were carried out between May 1976 and March 1977. The University that did the tests specifically stated that, whatever the outcome of the tests, John Marsh could not use their name in any way to endorse his equipment. These tests were similar to the tests Dr. Stafford conducted at Good Samaritan Hospital. Dr. Stafford's tests showed that these low square wave audio frequencies, which did not produce the correct sideband M.O.R. frequencies, would not devitalize any organisms. John Marsh's tests which he had done at this laboratory also showed that the low audio frequencies working on square wave harmonics will not devitalize any organisms. Both Dr. Stafford's and John Marsh's tests convincingly show the low square wave audio frequencies are not true M.O.R.s. Unless these instruments use the higher audio frequencies with a 3.30 MHz RF carrier frequency they will not devitalize anything.

No one that reads this information should in any way believe that this means that Dr. Rife's method of coordinative resonance is without merit. What these laboratory tests showed is that it is absolutely necessary that the instrument work on the same principles and frequencies as the original instruments that produce the true M.O.R. frequencies use in the Rife Ray #3, Rife Ray #4 and the Beam Ray Clinical instrument. These 1950's AZ-58 Beam Ray Clinical instruments were not calibrated correctly and they used the wrong audio frequencies. This miscalibration made it so the instruments did not work on the original sideband principles which produced Dr. Rife's frequencies. Because they were not calibrated correctly it rendered the instruments incapable of devitalizing any microorganism using just low square wave harmonics audio frequencies.

Even after these tests proved that the low square wave audio frequencies would not devitalize any microorganisms John Marsh continued to hold on to the false notion that these low square wave audio frequencies would devitalize microorganisms. He never would consider that something was wrong with the instruments. Today we understand that a simple correction would have solved all the problems. To read the document about this laboratory test that conclusively proves that the audio frequencies are not M.O.R.s. go to www.rifevideos.com and read this chapter and you will find the following link. (John Marsh's tests performed by: Brigham Young University Microbiology Department)

We covered this information in a previous chapter but it should be reviewed again here. Some people have wondered if the low audio frequencies (120 Hertz to 2128 Hertz) used in the 1953 AZ-58 are actually the original audio frequencies used in the 1938-1939 Beam Ray machine rather than the high audio frequencies (1200 Hertz to 21275 Hertz) used in Aubrey Scoon's Beam Ray replica instrument. This is a good question and it can easily be answered with certainty. The answer is in the math which produces the correct sidebands for each organism. Only the high audio frequencies (1200, 2400, 6600, 6900, 7660, 7270, 7870, 8300, 8450, 8020, 16000, 17220, 18620, 20080, 21275) will produce the correct sideband frequencies that will produce the higher harmonic frequencies from Dr. Rife's original frequencies. Only six of the low audio frequencies (120, 660, 727, 1862, 2008, 2127-2128 or 2127.5 Hertz as given by John Crane) used in the 1953 AZ-58 when multiplied by a factor of 10 times give the exact same high frequency used in Aubrey Scoon's instrument. But the other seven (712, 784, 776, 800, 803, 880 and 1552 Hertz) when multiplied by a factor of 10 times will not give the correct high audio frequency. These facts reveal which frequency list came first. Since we know that Philip Hoyland designed this Beam Ray Clinical machine and hid the method of using sideband frequencies to produce higher harmonics of Dr. Rife's M.O.R. frequencies then only the list (Aubrey Scoon's higher audio frequency list) that will produce Dr. Rife's higher harmonic frequencies could be the original list.

www.rife.org

From the Beam Ray Trial we learned that no one but Philip Hoyland understood how the instrument worked. Not even Dr. Rife, Verne Thompson, John Crane or John Marsh understood that the RF carrier frequency had to be matched to the audio frequencies in order to produce the sideband frequencies that would hit the higher harmonic frequencies of Dr. Rife's original M.O.R. frequencies. John Crane and John Marsh said many times the RF carrier frequency did not matter. In fact, they eventually quit using the RF carrier frequency when they built their 1950's contact pad style instrument. This clearly proves that they did not understand that the original Rife Ray #5 or Beam Ray Clinical instrument worked on harmonic sidebands. Had they understood this simple fact they never would have changed the RF carrier frequency or built their contact pad style instrument without using an RF carrier frequency. They also would not have lowered or changed any of the audio frequencies if they understood the sideband method used by Philip Hoyland. Both audio frequency lists would be identical except that one list would be 10 times higher than the other list. Only someone who did not understand how the audio frequencies really worked would have lowered them and then changed them. Only the list which came first would have all the correct frequencies. This information proves that the high audio frequency list came first. The low audio frequency list used in the 1953 AZ-58 would have come later in the 1950's because it is the list, when multiplied by 10 times, will only produce some of the correct sideband frequencies. Only someone such as Philip Hoyland could have made the high audio frequency list since the high audio frequencies are the only frequencies that will produce Dr. Rife's higher harmonic M.O.R. frequencies. As we said, the answer to this question is in the math.



www.rifevideos.com

www.rife.org

Below in the chart is a list of the "Original 1950s AZ-58 Frequencies" used by Dr. Stafford. The column to the right of the "Original 1950's AZ-58 Frequencies" is based on a 4.68 MHz RF carrier and is labeled "4.68 Correct Sideband Frequencies". They would be the correct sideband frequencies to make the AZ-58 instrument work like the original Beam Ray Clinical instrument, but, the problem is the large "Number of Sideband Harmonics". You will notice that almost all of the low audio frequencies exceed more than 40 sideband spacing steps to hit the high frequency M.O.R.

Original 1950's AZ-58 Frequencies Used By Dr. Robert P. Stafford M.D.

Microorganism	Rife Ray #4 Frequencies	Higher Harmonic Frequencies	*Carrier Difference Frequency	1/10 Of A Meter Freq.	Number of Sideband Harmonics	Original 1950s AZ-58 Frequencies	4.68 Correct Sideband Frequencies
Actinomycosis or Streptothrix	192,000 Hz	4,608,000 or 24th	72,000 Hz	12 Hz	92	784 Hz	782 Hz
Anthrax	139,200 Hz	4,732,800 or 34th	52,800 Hz	6 Hz	85		621 Hz
B or E Coli Rod	417,000 Hz	4,587,000 or 11th	93,000 Hz	58 Hz	116	800 Hz	802 Hz
B or E Coli Virus	770,000 Hz	4,620,000 or 6th	60,000 Hz	198 Hz	38	1552 Hz	1538 Hz
BX Virus Carcinoma	1,604,000 Hz	4,812,000 or 3rd	132,000 Hz	858 Hz	32	2128 Hz	2129 Hz
BY Sarcoma	1,530,000 Hz	4,590,000 or 3rd	90,000 Hz	780 Hz	45	2008 Hz	2000 Hz
Gonorrhea	233,000 Hz	4,660,000 or 20th	20,000 Hz	18 Hz	28	712 Hz	714 Hz
Pneumonia or Spinal Meningitis	427,000 Hz	4,697,000 or 11th	17,000 Hz	61 Hz	17	776 Hz	1000 Hz
Staphylococcus Pyogenes Aureus	478,000 Hz	4,780,000 or 10th	100,000 Hz	76 Hz	137	727 Hz	730 Hz
Streptococcus Pyogenes	720,000 Hz	4,320,000 or 6th	360,000 Hz	173 Hz	409	880 Hz	880 Hz
Syphilis	789,000 Hz	4,734,000 or 6th	54,000 Hz	207 Hz	82	660Hz	658 Hz
Tetanus	234,000 Hz	4,680,000 or 20th	0 Hz	18 Hz		120 Hz	20 Hz
Tuberculosis Rod	369,000 Hz	4,797,000 or 13th	117,000 Hz	45 Hz	146	803 Hz	801 Hz
Tuberculosis Virus	769,000 Hz	4,614,000 or 6th	66,000 Hz	197 Hz	44	1552 Hz	1500 Hz
Typhoid Rod	760,000 Hz	4,560,000 or 6th	120,000 Hz	192 Hz	168	712 Hz	714 Hz
Typhoid Virus	1,445,000 Hz	4,335,000 or 3rd	345,000 Hz	694 Hz	185	1862 Hz	1865 Hz

The large "Number of Sideband Harmonics" means that the power level of the correct sideband that hit the higher harmonic M.O.R. would be so weak that it would never work. If the "Number of Sideband Harmonics" go over about 40 sideband steps the power level on a spectrum analyzer shows that they become too weak to work.

You will notice how closely these two sets of low audio frequencies correspond to each other. The problem is when Dr. Rife, John Crane and John Marsh lowered the audio frequencies they compromised the AZ-58. The BX audio frequency that Dr. Stafford used was 2128 Hertz and the RF carrier frequency was about 3.20 MHz. The sideband spacing to the "Higher Harmonic Frequency" M.O.R. took only a few sidebands which had enough power to work. This appears to be the reason why the two women and a few others that he treated had such amazing results. The problem is most of the organisms far exceed the 40 sideband harmonics when using these low audio frequencies. This will happen even if you use a 3.20 MHz or 4.68 RF carrier frequency. As mentioned before the higher the audio frequency used the more power there is in the sidebands. For this reason in the next chart, at the top of the next page, we have put a list of the optimum AZ-58 audio frequencies to be used with a 4.68 MHz RF carrier frequency and a 40,000 Hertz audio frequency oscillator. This would make the instrument work like the original Beam Ray Clinical instrument.

www.rife.org

1950’s Beam Ray Clinical Instrument Optimum Sideband Square Wave Audio Frequencies Based On A 4.68 MHz Carrier

Anthrax	26,400 Hz	Streptococcus	32,727 Hz
B or E Coli Rod	31,000 Hz	Streptothrix	36,000 Hz
B or E Coli Virus	30,000 Hz	Syphilis or Treponema	18,000 Hz
BX Virus Carcinoma	33,000 Hz	Tetanus	20 Hz
BY Sarcoma	30,000 Hz	Tuberculosis Rod	39,000 Hz
Gonorrhea	20,000 Hz	Tuberculosis Virus	33,000 Hz
Pneumonia or Spinal Meningitis	17,000 Hz	Typhoid Rod	40,000 Hz
Staphylococcus	25,000 Hz	Typhoid Virus	38,333 Hz

Below and on the next page are three photos of the original AZ-58. The first photo is of the inside of the case showing the variable capacitor (bottom left corner with the black knob and the black wire leading to it) which could change the RF carrier frequency. The second photo is a view of the underside of the chassis. From the 1930's to the 1950's the instrument had only a few changes made in the electronic parts. The third photo is a side view of the first AZ-58 built in 1953. If you take a close look at this photo you will see that it did not have the variable capacitor when it was first built. The variable capacitor was added in 1956 and was used for tuning the brightness or resonance of the ray tube. This was done because they didn't believe the carrier frequency made any difference. It was not added for the purpose of changing the RF carrier frequency, this was just a side benefit. Doctor Stafford used this variable capacitor to set the carrier frequency to about 3,200,000 Hertz for some of his tests. This is the reason we believe he had such good success with the two women patients who had cancer. The BX cancer frequency was 3,214,900 Hertz (1,607,450 X 2 = 3,214,900 Hertz) and even using the low audio frequencies this would have worked very well because he would have been hitting the BX frequency with powerful harmonic sideband frequencies.

www.rife.org





www.rifevideos.com
www.rife.org

www.rifevideos.com
www.rife.org

The photos, shown on page 179, are of the AZ-58 we built back in 2000. It used to have the vacuum tube audio oscillator built into it but it never worked properly. So it was removed and replaced with Aubrey Scoon's audio amplifier.

On page 180 is a schematic of the 1950's AZ-58 instrument. The 866 vacuum tubes have been replaced with solid state rectifiers. Also the old vacuum tube audio oscillator has been removed. It is easier and more accurate to use Aubrey Scoon's booster amplifier and a modern function generator to produce the audio frequencies that were used in this instrument. The layout of the electronic parts of this instrument is very important because of the inherent interference problems that come with RF oscillators. Again anyone who would like to build this instrument should have a good understanding of old tube technology. Some parts of this circuit use up to 2000 volts DC with substantial current and can easily kill anyone who is not familiar with this kind of current or voltage. We take no responsibility for anyone who builds this instrument. We recommend that you have professional help.

Chapter Summary: To sum things up only a few changes were made to the original Beam Ray Clinical instrument design which produced the 1953 AZ-58 Beam Ray Clinical replica. Dr. Rife and Verne Thompson kept the original Hartley oscillator but changed the fixed RF carrier frequency from 3.80 MHz to 4.68 MHz as per the new FCC license. The RF carrier frequency section did not significantly changed with the use of the 812a vacuum tube instead of the 809 vacuum tube. They kept the variable audio oscillator which produced the low audio frequencies but lowered its range of frequencies using only three bands with a top audio frequency range of about 6000 Hertz. They then lowered Philip Hoyland's original sideband audio frequencies by a factor of about 10 times and used these lower audio frequencies in the AZ-58. Then they changed the audio frequency waveform from sine wave to square wave and depended on the harmonics produced by the square wave waveform instead of the sidebands. It is interesting that Philip Hoyland found that a modulated sine wave waveform when put thought his M.O.P.A. circuit was sufficient to devitalize organisms because it creates a wave form that looks almost like a square wave waveform. It appears that a damped wave is not really necessary. When you compare the original Beam Rays Clinical instrument and Aubrey Scoon's 1950's Beam Ray Clinical instrument to the 1950's AZ-58 Beam Ray Clinical replica they are almost identical except for the audio frequency bands. When we built both of these instruments, Aubrey Scoon's and the AZ-58, and compared them we found the AZ-58 replica appears to be the better design and easier to build.

Even with the changes Dr. Stafford had very good results which greatly impressed him. Today because of the changes that were made during the 1950's most people believe that the lowered audio frequencies that were used in the AZ-58 are Dr. Rife's original M.O.R. frequencies, but they not. Dr. Rife's original M.O.R. frequencies were the frequencies used in the Rife Ray #3 and Rife Ray #4. The Rife Ray #5 or Beam Ray Clinical instrument also worked on higher harmonics of Dr. Rife's frequencies. An instrument that could output both square wave harmonics and Philip Hoyland's harmonic sidebands would take advantage of both of these methods.

In the next chapter we will discuss the difference between using square wave harmonics and sideband harmonics.

www.rife.org

Photos of the rebuilt AZ-58 Beam Ray Clinical instrument








Variable Capacitor
For Changing Carrier
RT101



www.rife.org


0 VAC
C8
.01uF 1KV
GND
110 VAC
SW1
F
C9
.01uF 1KV
GND
Transformer, Power
T1
1000V
0V
1000V
Hammond 728
L1
Choke, Plate, 10H, 200mA
Hammond 193J
GND
V1 SS866A
V2 SS866A
SS866A Solid State Substitution Rectifiers
C1
2uF,2000V
GND
C2
2uF,2000V
GND
HV B+
Choke, RF, 1-3.5mH,1A
L1
Hartley Oscillator
V3
812A
GND
C3
0.002uF,2KV
B&W #3034 cut in half
3" dia., 5" long, 8turns/inch
31t
L3
13t
7t
GND
C4
100pF,3KV
Choke, RF, 1-3.5mH,1A
L2
http://www.scoon.co.uk/Electrotherapy/Rife/BeamRay/booster.jpg
Generator Input
Aubrey Scoons
Booster Amplifier
C5
0.47uF,630V
R1
2.5 K, 25W
0 - 300 mA Meter
set for 100mA
C8
.01uf 1KV
GND
10 - 365pf
Variable
2KV
Tuning set
to 4.68 MHz
C6
GND
C7
0.002uF,2KV
Transformer, Filament, 6.3V,10A
T3
DS1
Lamp, 6.3V
Hammond 166S6
Ray Tube
Helium Gas 12mm press
Electrodes 2" apart & 1 1/4 " dia.
7" dia. 3 Liter Pyrex Flask
PT1
−
+
GND
Bill Chebs
6" Phanotron Ray Tube
with the 8" Ray Tube electrodes
set 2" apart works best

Reference: Allied Industries, John Crane, 08/08/50
Schematic Corrected by James Cunningham 03/2000
Simplified and updated by Jeff Garff and Jim Peters 4/11/08

1950s AZ-58 Instrument. Built for
Dr. Rife by Verne Thompson from
Philip Hoyland's Beam Ray design

Redrawn by Jeff Garff	Rev 2.0 4/11/2008	Page 1 of 1

www.rife.org

Chapter #13

Rife Machine Harmonic Audio Frequency Misunderstanding

www.rifevideos.com

There is a belief that the audio frequencies that were used in the original Rife Ray #5 or Beam Ray Clinical Rife Machine and its 1940's and 1953 AZ-58 replica Rife Machines are harmonic M.O.R. frequencies derived by dividing Dr. Rife's original high RF frequencies down in octave steps until you reach the audio range of frequencies. For this to be true then all of the audio frequencies would have to be true harmonics of the higher RF frequencies. But this is not the case.

All the documents we have quoted and the understanding we now have, prove as a myth, the long believed concept that the low audio frequencies used in the 1950's were created by John Crane and John Marsh by dividing Dr. Rife's high frequency M.O.R.s down by harmonic steps until they reached the audio range of frequencies. If we take the correct frequency for the BX of 1,607,450 Hertz read by Philip Hoyland and divide it down by harmonics we do not get 2008 Hertz or 2128 Hertz. In fact, we do not get Philip Hoyland's higher audio frequencies of 20080 Hertz or 21275 Hertz either. This clearly proves John Crane and John Marsh did not create the audio frequencies by just dividing down Dr. Rife's higher RF M.O.R. frequencies. The fact is we know that the origin of these audio frequencies came from the sideband harmonic method used by Philip Hoyland in the original Beam Ray Clinical instrument.

The documented information we have shows that Dr. Rife's true M.O.R.s that would resonate organisms were the higher RF frequencies (139,200 Hertz to 1,607,450 Hertz) used in the Rife Ray #3 which consisted of the Kennedy Models 110, 281. These same frequencies were used in the Rife Ray #4 Rife Machine and the higher harmonic frequencies of these frequencies were used in the Rife Ray #5 or Beam Ray Clinical Rife Machine. All of Dr. Rife's Machines worked on RF frequencies not audio

www.rife.org

frequencies. From the spectrum analysis of Philip Hoyland’s Beam Ray Rife Machine we know that it used audio frequencies for one purpose only, to create the method of sideband harmonic spacing to hit the higher harmonic frequencies which were harmonics Dr. Rife's true RF M.O.R.s. Henry Siner reported Philip Hoyland’s design killed the organisms under microscope observation. This same instrument was tested by Dr. Rife in 1940 when Verne Thompson repaired it. Add to this the list of doctors who used the instruments and said they had many diseases cured. This shows that Philip Hoyland’s harmonic method works beyond question.

Dr. Robert P. Stafford was not able to kill any organisms in laboratory tests using just the square wave audio frequency harmonics. He did his tests under microscope observation. Today, like Dr. Stafford many have tried to kill the organisms which these audio frequencies correspond to, with no success. John Marsh had laboratory tests done in 1976-1977 which also confirmed Dr. Stafford's tests.

If these audio frequencies, as some have claimed, were really harmonic frequencies derived from the higher RF M.O.R. frequencies then one would think that they should be able to kill the microorganism they correspond to. If a true audio frequency harmonic of Dr. Rife’s RF M.O.R. will not devitalize an organism under microscope observation, can the harmonic association be valid? No rational person would believe this. Yet today this is exactly what most people believe because they do not have all of the facts.

When Dr. Rife started looking for frequencies to devitalize microorganisms he worked his way up from the lower frequency ranges to the higher frequency ranges until he found a frequency which would devitalize an organism he was working on. His Rife Ray #3 had the ability to start at about 12,000 Hertz which is in the upper audio frequency range. So Dr. Rife would have naturally started at 12,000 Hertz and moved up in the frequency range in his testing until he found the frequency that would devitalize the organism. Since the Rife Ray #4 documents show that the lowest frequency for any of the organisms was 139,200 Hertz we can conclude that he did not find any frequencies in the audio range or less than 139,000 Hertz that would devitalize any of these organisms listed on the Rife Ray #4 documents. Now this method of starting at the lowest frequency and moving up into the higher frequency ranges would be a logical method of finding the M.O.R. of an organism. What this also logically tells us is that no frequency lower than 139,000 Hertz could ever be a frequency that would devitalize any of these organisms. What this also reveals to us is that Dr. Rife had to get to a high enough frequency range before a resonant effect would devitalize an organism. What is the point that we are trying to make with this simple logic. Philip Hoyland found that higher harmonics of Dr. Rife's original M.O.R. frequencies would devitalize those organisms. But what Dr. Rife found was that there were no frequencies lower than the frequencies he found that would devitalize the organisms found in the Rife Ray #4 documents. We must keep in mind that the Rife Ray #4 did not have any variable audio oscillator. Its frequency range started at 87,000 Hertz. From this we can conclude that Dr. Rife found that the audio range up to about 87,000 Hertz was not needed because you cannot truly resonate any organism with frequencies below 87,000 Hertz using his method.

With this logical understanding you would not divided down in octave or harmonic steps any of the Rife Ray #4 resonant frequencies and expect these lower frequencies to devitalize those organisms using the same method Dr. Rife used. But this is what people claim can be done. If Dr. Rife could not find any frequency lower than 139,000 Hertz to devitalize the Rife Ray #4 organisms then this concept that people are claiming is a questionable concept depending on the number of harmonic or octave steps used. It is a known fact that square waves will create higher harmonic frequencies. Some claim infinite harmonics but this could only be true if there was infinite power behind those harmonics. So power determines the number of harmonics. In most situations the harmonics from a square wave are only readable, with sufficient power, to about 9 harmonics up from the original frequency used. Understanding this you would not take any of Dr. Rife's frequencies and divide them down in either harmonic steps or octave steps more than about 9 times and expect an audio frequency with a square wave

www.rife.org

waveform to resonate those organisms. Yet this is what people are claiming can be done using audio frequencies and square wave harmonics. They actually promote the idea that you can go down hundreds of harmonic steps with Dr. Rife’s frequencies and get them to resonate organisms with low audio frequencies. It is this false concept that John Crane and John Marsh promoted. This false concept has caused all of the confusion we have today. This is why so many people claim that Dr. Rife's original M.O.R. frequencies where the low audio frequencies that were used in the AZ-58.

We are not saying that low audio frequencies do not have positive effects, because they do. But they are working on a different concept than coordinative resonance. No one knows exactly how these low audio frequencies work, they just know they are beneficial. Dr. Stafford believed that they somehow stimulated the adrenals which in turn stimulated the immune system. He also believed when the immune system is stimulated the body will be able to overcome many ailments that it otherwise could not overcome. Again we will point out that it is not known how these low square wave audio frequencies work. But what is known is that they do not create a true resonate frequency effect like Dr. Rife's high RF frequencies or the higher harmonic RF frequencies Philip Hoyland used.

The evidence we have given in this report shows that if the RF M.O.R. frequency is lowered by too much it will lose its ability to devitalize an organism even though it is a lower harmonic frequency. Dr. Stafford's and John Marsh's laboratory tests showed this when they treated the organism with the low audio frequency that was supposed to devitalize it. The tests showed that the organism continued to grow even when they transferred it from one culture to another. Can there be any greater scientific proof than this? Even Dr. Rife would not have argued with this method of determining true M.O.R.s, because this is the method he used. This is the greatest proof, along with the fact that almost all the audio frequencies are not true harmonics of the original high RF frequencies. We know many other people who have made the same tests on microorganisms as Dr. Stafford and John Marsh and they told us they obtained the same results he did. John Marsh said on the Rife CD's that they came up with the frequencies using math. The documented information we now have show that the math they used was to lower Philip Hoyland's original audio frequencies by a factor of 10 times. If every audio frequency was a perfect harmonic match to its higher RF M.O.R. then we could say they were all derived from Dr. Rife's original M.O.R.s, but they are not. So this leaves us with only one conclusion. They lowered Philip Hoyland's higher audio frequencies and wrongly considered those lowered frequencies to be the true M.O.R. frequencies. Another thing we must understand is that even if the audio frequencies were derived from Dr. Rife's original RF M.O.R.s in lower harmonic steps or octave steps and they do not devitalize the organism they are not real M.O.R.s. either.

What the evidence in this report certainly proves is, without really knowing it, Dr. Rife, John Crane and John Marsh discovered that these lower square wave audio frequencies are beneficial. Even though they will not devitalize the organism they correspond to under microscope observation they still seem to help people? The fact is we really don’t know why the audio frequencies are beneficial, but for some unknown reason they are. Though the method of modulating a square wave audio frequency onto a fixed RF carrier did not work as well as Philip Hoyland's sideband method, nevertheless it works very well on many conditions. Even though the audio frequencies are beneficial in many ways, this still does not prove the claim that the 1950’s audio frequencies are harmonic M.O.R.s.

What needs to be kept in mind is how the original Beam Ray Clinical instruments worked. We will again point out here that neither the 3.30 or the 3.80 MHz RF carrier frequency nor the audio frequencies will do anything by themselves. But when the 3.30 or the 3.80 MHz RF carrier frequency and the audio frequencies are combined together they will produce many sideband frequencies. And one of these sideband frequencies will line up with the true Rife M.O.R. frequency and devitalize or render harmless the harmful microorganism. If you just use the audio frequencies by themselves you will get nothing. If you use the 3.30 or the 3.80 MHz RF carrier without the audio frequencies you will get nothing. The audio frequencies used in this style of instrument must be match to the RF carrier frequency of

www.rife.org

3.30 or 3.80 MHz or they are useless. This is the reason the 1953 AZ-58 Beam Ray Clinical instrument did not work properly.

Below is a chart showing the “High Frequency M.O.R.s” which were taken from the Rife Ray #3 and used with the Rife Ray #4. These frequencies were recorded in 1935 when Philip Hoyland went to Dr. Rife's laboratory to read them with his master oscillator. They were fine tuned with more precision in 1936 when Philip Hoyland built the Beam Ray Clinical instrument. This is the reason for the slight discrepancy in Dr. Rife's high frequencies. In 1935 the frequencies were rounded off to the nearest thousandth. In 1936 a more accurate reading was done of these frequencies so that the higher harmonics could be used in the Beam Ray Clinical instrument. These frequencies are the true M.O.R.s. The “Harmonic Higher Audio Frequency” column is the true harmonic of the “High Frequency M.O.R.s” column. How well these higher frequencies under 60,000 Hertz would work is anyone's guess using the square wave harmonic waveform that was used in the AZ-58 replica instrument. The “Harmonic Higher Audio Steps” column shows how many harmonic steps it takes to hit the fundamental “High Frequency M.O.R.s” using the “Harmonic Higher Audio Frequency” using a square wave waveform. As can be seen the higher the frequency the less harmonic steps it takes to hit the fundamental M.O.R. frequency. We did this chart just to show how the concept of square wave harmonics would work. Just keep in mind that any square wave audio frequency only goes up for about 9 harmonics with sufficient power. Many of the “Harmonic Higher Audio Steps” exceed 9 harmonics. With this understanding a higher frequency should be chosen that would be within 9 harmonics of Dr. Rife’s original high RF M.O.R. frequency.

AZ-58 M.O.R. Audio Frequencies Square Wave Harmonics

Microorganisms	**1950’s Low Audio Frequency For AZ-58**	**True Harmonic Low Audio Frequency For AZ-58**	**Harmonic Low Audio Steps for AZ-58**	**Harmonic Higher Audio Frequency**	**Harmonic Higher Audio Steps**	**High Frequency M.O.R.s**
Actinomycosis (Streptothrix)	784 Hz	750 Hz	256	48,000 Hz	4	192,000 Hz
Anthrax	None	1087.5 Hz	128	34,800 Hz	4	139,200 Hz
B. Coli (Rod form)	800 Hz	814.4531 Hz	512	52,125 Hz	8	417,000 Hz
B. Coli (Filterable virus)	1552 Hz	1503.9063 Hz	512	48,125 Hz	16	770,000 Hz
Bacillus X or BX (Cancer Carcinoma)	2128 Hz	3132.8125 Hz	512	50,125 Hz	32	1,604,000 Hz
Bacillus Y or BY (Cancer Sarcoma)	2008 Hz	2988.28125 Hz	512	47,812.5 Hz	32	1,530,000 Hz
Gonorrhea	712 Hz	910.15625 Hz	256	29,125 Hz	8	233,000 Hz
Pneumonia or Spinal Meningitis	776 Hz	1667.96875 Hz	256	53,375 Hz	8	427,000 Hz
Staphylococcus Pyogenes Aureus	727 Hz	933.59375 Hz	512	59,750 Hz	8	478,000 Hz
Streptococcus Pyogenes	880 Hz	703.125 Hz	1024	45,000 Hz	16	720,000 Hz
Syphilis	660 Hz	770.5078 Hz	1024	49,312.5 Hz	16	789,000 Hz
Tetanus	120 Hz	914.0625 Hz	256	29,250 Hz	8	234,000 Hz
Tuberculosis (Rod)	803 Hz	720.7031 Hz	512	46,125 Hz	8	369,000 Hz
Tuberculosis (Virus)	1552 Hz	1501.953125 Hz	512	48,062.5 Hz	16	769,000 Hz
Typhoid Fever (Rod)	712 Hz	742.1875 Hz	1024	47,500 Hz	16	760,000 Hz
Typhoid Fever (Virus)	1862 Hz	1411.1326 Hz	1024	45,156.25 Hz	32	1,445,000 Hz

Now if we take a look at the "1950's Low Audio Frequency For AZ-58” column we see the frequencies that were used by the AZ-58 back in the 1950's. These frequencies are still used today. In the “True Harmonic Low Audio Frequency For AZ-58” column we find the true low audio frequency harmonics of the “High Frequency M.O.R.s.” As you compare these columns you can see that the 1950's frequency for Actinomycosis or Streptothrix was 784 Hertz but the true harmonic frequency is 750

www.rife.org

Hertz. It is easy to see that the AZ-58 was not working on square wave harmonics of the true M.O.R.s. If you look at the “Harmonic Low Audio Steps For AZ-58” column you can see how many harmonic steps it takes to reach the true “High Frequency M.O.R.” These range from 128 harmonic steps to 1024 harmonic steps. Anyone looking at these numbers would wonder if these frequencies could ever work. Logically the higher the frequency the better the chance they will work. Also logically the less you go up in square wave harmonics the greater the chance they will work. When using the square wave method the highest frequency possible should be used.

Chapter Summary: None of the low audio frequencies used in the AZ-58 were Dr. Rife's original M.O.R. frequencies. Not even the higher audio frequencies used in the Beam Ray Clinical instrument were his original M.O.R. frequencies either. Both the lower and the higher audio frequencies are not true harmonics of Dr. Rife's original M.O.R. frequencies, as some have thought. The frequencies that Dr. Rife discovered were the lowest frequencies which he found that would resonate an organism and devitalize it. Dr. Rife knew that his frequencies were lower harmonics of a true higher frequency. Philip Hoyland used this understanding in the Rife Ray #5 or Beam Ray Clinical instrument. One thing we do know is dividing Dr. Rife's original frequencies down in octave or harmonic steps until you get into the low audio frequency range has not been proven through laboratory testing to resonate those organisms or any other organisms. Dr. Stafford and John Marsh had laboratory tests done and found that the 1950's AZ-58 square wave low audio frequencies would not devitalize any organisms they were tested on. The audio frequency range does have many beneficial frequencies but it is not understood how they really work. Dr. Stafford believed they stimulate the adrenal glands thus stimulating the immune system.

The real problem with not understanding which frequencies are Dr. Rife's original M.O.R. frequencies means that people will purchase frequency generating equipment that does not output Dr. Rife's original frequencies. It really is "buyer bewares". If a frequency generating piece of equipment cannot output both the low audio frequency range and the high RF range then you may want to reconsider purchasing it. Look for a frequency generator that can output all of Dr. Rife's frequencies. If a company will not tell you what the frequency range of their so called "Rife Machine" is then keep looking until you find a good frequency generator with the correct frequency range. Any frequency generator worth purchasing should have a range from at least 1 Hertz to 5,000,000 Hertz so you can use the full frequency range that Philip Hoyland used with the higher harmonics of Dr. Rife's original M.O.R. frequencies. If a frequency generator can go to 20,000,000 million Hertz, even better, because you can also work with many of the higher harmonics of Dr. Rife’s frequencies.

In the next chapter we will look at the pad type instrument developed by John Crane and John Marsh in the late 1950's.

www.rife.org

Chapter #14

Life Labs 1950's Pad Instrument without Ray Tube


RVMI
MODEL 802
SERIAL 18
NEW DEVICE-FOR INVESTIGATIONAL USE ONLY
0 10 20 30 40 50 60 70 80 90
RANGE
A B C D
POWER
FREQUENCY INSTRUMENT
RIFE VIRUS MICROSCOPE INSTITUTE
SAN DIEGO CALIFORNIA

1. Used round disks that came in contact with the body. Later changed in the 1960's to hand cylinders or foot pads.
2. Had no RF carrier frequency.
3. Used the square wave audio frequencies used in the AZ-58.

It was about 1957 when John Crane and John Marsh began building instruments without a ray tube. Earlier in this article Bertrand Comparet was quoted as saying:

COMPARET: *"Now, Crane said "Well now look, Rife himself admits that no matter how much tube and ray, and so on, you have, you can't get any results unless you've got the right frequency. Therefore the real clue to the thing is the frequency and not the means by which you deliver it."* (1970's Bertrand Comparet Interview #33).

John Crane and John Marsh replaced the ray tube with two aluminum disks (shown in the above photo) which they developed that came in contact with the body. As we pointed out earlier in this report it is interesting to note that Dr. Rife said Abrams' Oscilloclast would devitalize the BX cancer virus and it was a contact type device. John Crane and John Marsh probably used this contact method because of the success of Abrams' instrument. From the documented information we have it was also the high cost of building ray tube instruments that caused them to look at doing things in a different way. In addition to being expensive to build, the ray tube could break very easily. They had many problems with them. It does not appear that Dr. Rife, at least in his early years, ever had a reason to look at doing

www.rife.org

things differently. John Crane and John Marsh did. They didn't have the kind of money to spend that Dr. Rife did. They say that "Necessity is the mother of invention!"

In the photo, shown below, we see that they eventually added handles onto the disks so that they were easier to use.



John Crane and John Marsh used a Heathkit function generator to produce the frequencies. These Heathkit function generators had no built-in carrier frequency on which to modulate the audio frequencies. Therefore, the RF carrier frequency was no longer used. The fact that they didn't feel the RF carrier frequency was necessary shows that they totally believed that the audio frequencies were the M.O.R. frequencies. This also shows beyond doubt that they never knew the importance of the RF carrier frequency or had any understanding of the harmonic sideband method used in the original Rife Ray #5 or Beam Ray Clinical Rife Machine. They could have made a pad instrument work like the Beam Ray Clinical Rife Machine if they would have used a harmonic sine wave RF carrier frequency at 3,300,000 Hertz. After the many years that these pad instrument have been used it appears that the removal of the ray tube was not as important as the removal of the RF carrier frequency.

Dr. Rife would have never approved of using an instrument without an RF carrier frequency. He knew that Philip Hoyland's Beam Ray Clinical instrument which used the sideband method somehow needed an RF carrier frequency to make it work properly. Though Dr. Rife didn't fully understand Philip Hoyland's instrument he clearly understood the importance of the RF carrier frequency. The positive thing about using a Heathkit function generator in this way is they were inexpensive (about $200) and a lot more people could afford one. Many people can thank John Crane and John Marsh for this innovative method. John Crane and John Marsh proved that the square wave audio frequencies worked the same whether applied through a ray tube or pads if sufficient power is used. Many people think that John Crane and John Marsh built the pad instrument without Dr. Rife being fully informed about it. But this was not the case. John Crane and John Marsh had talked for some time about building a smaller ray tube instrument but instead of building it they built the pad instrument. In John Marsh's Trip to Ohio Papers we read this:

www.rife.org

RIFE: *"That is the only way that it can be handled properly."*

MARSH: *“Maybe we can sell small instruments for the purpose of small diseases like colds, flu and stuff like that, which are minor, which the Dr.s prefer not treating those kind anyway, because they are chronic, and there isn’t anything they can do with them. People keep coming in and coming in and they take up his time where he could spend it taking care of a bad case, or something or other. Dr. Stafford said that he would prefer that a small instrument would be made...What do you think John? I've been doing a lot of talking not even giving you a chance to get a word in edgewise.”*

CRANE: *“There is no doubt there is going to be an awful lot of development on this design…”* (1957 John Marsh trip to Dayton, Ohio #36-38).

From these statements we learn that Dr. Rife knew that they wanted to build small instruments. Also we learn that it was John Marsh and John Crane’s idea to build the pad instruments, not Dr. Rife’s. We know that Dr. Rife was upset with John Crane and John Marsh over the building of these pad instruments because he expressed it to Bertrand Comparet during his 1961 deposition. Comparet said:

COMPARET: *“And I asked Rife, because I thought Rife would certainly say that the way Crane was working on it then was still using the Rife principle, but he indignantly denied it.”*

HUBBARD: "*All right, I see. But, getting back, you say that Rife was very indignant, that the machine that Crane was building was really his* [Cranes] *idea. I suppose he did not compromise on that, did he?*

COMPARET: *"Oh no, he just blew up."* (1970’s Bertrand Comparet interview #32 & 40).

At this time John Crane and John Marsh were working on both the ray tube instrument and the pad instrument. We know that Dr. Rife considered the ray tube instrument to be his instrument. The ray tube instrument used an RF carrier frequency on which the square wave audio frequencies were modulated. So it is clear that the pad instrument without an RF carrier frequency is what Dr. Rife was upset about. It is also clear that Dr. Rife fully knew what they were doing but he did not approve of what they were doing. Because they didn’t use an RF carrier frequency the pad instrument would not be working on Dr. Rife's principle of coordinative resonance through high RF sideband frequencies. We know that this was the method Philip Hoyland used in his design. If there is no RF carrier then there would be no sideband frequencies and this would mean that none of Dr. Rife's higher harmonic RF frequencies would have been produced. This also means the pad instrument only worked on low square wave audio frequency harmonics not high RF frequencies. However, John Marsh and John Crane’s innovation with a pad instrument proved that the ray tube could be removed and frequencies could be applied electrically through the contact method which they used.

This new method made it possible for more people to have access to a less effective form of Dr. Rife’s technology. Though it was a less effective method many people over the years have been helped by this method of only using low square wave audio frequencies. Back when John Crane and John Marsh were building these pad instruments they could have built a pad instrument capable of producing all of Dr. Rife's frequencies. The reason they did not do this is due to the fact that they believed that the low square wave audio frequencies would work as well as Dr. Rife's original high RF frequencies. Time has proven that they were not correct in this belief. Today all of Dr. Rife's original high RF frequencies and the higher harmonics of those frequencies which Philip Hoyland used can be produced by any function generator with the proper frequency range of at least 1 Hertz to about 4,000,000 Hertz.

It appears that one of the reasons why John Crane and John Marsh didn’t use an RF carrier frequency is the Heathkit function generator that they used didn’t have the capability of using an RF carrier frequency. Audio frequencies will not broadcast; therefore, they are modulated upon the RF carrier frequency so that they will penetrate the body. In laymen’s terms, modulation is piggy-backing one or

www.rife.org

more low frequencies onto another higher frequency. The frequencies travel together but still keep the components of both waveforms. Almost all of the so called "Rife Machines" built today do not use an RF carrier frequency even though Dr. Rife's Beam Ray Clinical instrument and the 1953 AZ-58 Machine did. If Dr. Rife could have removed the RF carrier frequency from his instrument and gotten the same results, I believe he would have removed it because it would have made building an instrument a lot easier. He became upset with John Crane and John Marsh for doing this. As it is, Dr. Rife never removed the RF carrier frequency from any of his instruments. It was John Crane and John Marsh who remove it. If a person wants to try and obtain the same type of results which Dr. Rife did, then an RF carrier frequency should be considered and used with any audio frequency instrument.

We realize that there are ray tube instruments today that do not use an RF carrier frequency. These use a high electromagnetic field (EM) which will transfer the energy into the body. We do not doubt that these instruments work very well with low square wave audio frequencies. We have talked with people that are using these instruments and they say that they are getting very good results. But these instruments are still using just the low square wave audio frequencies without an RF carrier frequency. What we are talking about in this report is the way that Dr. Rife used RF frequencies and an RF carrier frequency modulated with an audio frequency to produce the proper sideband method. Some of these EM ray tube instrument builders like to compare EM devices to RF devices. This is like comparing apples and oranges. There is no comparison because if you do not have an RF carrier frequency then you cannot create any sideband frequencies. The EM devices work on a high electromagnetic field, the stronger the better. RF devices work on radio frequencies and the power output is measured in watts. Dr. Rife's instruments were all RF instruments and could resonate an organism when the proper RF frequency was used. EM devices use low audio frequencies because they cannot output RF frequencies. RF versus EM or apples and oranges cannot be compared because they are two totally different principles. EM devices are also limited in their frequency range. Usually they can only output frequencies to about 20,000 Hertz where Dr. Rife's RF devices were putting out frequencies in the millions of Hertz or cycles per second.

There is some misinformation being put out about pad instruments. Mostly it is done by people who believe that only a ray tube will work in delivering frequencies to the body, whether it is through the RF or the EM method of delivering frequencies. These people promote the false belief that audio frequencies when used in a pad instrument without an RF carrier or without an EM field will only travel along the surface of the skin of the body. They say that the frequencies cannot penetrate the body because of the "Skin Effect." We need to point out that the "Skin Effect" has nothing to do with human tissue or human skin. The "Skin Effect" has to do with the skin or surface of a metal conductor such as a copper wire. If the human body was made of metal then the "Skin Effect" would apply. These people are either totally ignorant or willfully trying to mislead people so that they will only purchase an instrument that uses a ray tube. What we should really believe is what the scientific tests have proven in regards to the "Skin Effect" as it pertains to human or animal tissue.

In scientific studies called "Bioelectric Impedance Analysis" it has been shown that sine wave audio frequencies, without an RF carrier frequency, will enter the body but will only travel in the connective tissues around the cells. These tests have prove beyond doubt that the frequency does go right through the skin contrary to what people have claimed. Also in these scientific studies it has been shown that the closer you get to 1 Megahertz the greater the penetration of the current through the cell. At 1 Megahertz or one million Hertz the current of the frequency will go through the cell and fully penetrate the body. These type of tests show why it is very important that an RF carrier frequency be used. A virus can enter a cell and live there. An RF frequency can enter the cell where it can do the most good. These kinds of scientific studies and their importance were not understood by John Crane and John Marsh in the 1950's and 1960's. These "Bioelectric Impedance scientific tests also prove that what many people have been saying about the "Skin Effect" is absolutely false. In this Rife machine report we do not ask people to believe what has been said without proof. For this reason we have in-

www.rife.org

cluded one of these scientific reports for you to read. There are other reports on the web that you can read but we found that this one is the easiest to understand. But even with that said, unless you have some understand of how electricity works then it may be difficult for some to understand. Because of this we added, in blue print, a layman's understanding at the end of each section. To read this file go to the following website address.

www.rifevideos.com/pdf/skin_effect_and_bio_electrical_impedance_analysis.pdf

Below is a schematic of John Crane & John Marsh's pad instrument. It was nothing more than an off-the-shelf audio frequency generator with the faceplate changed. There was nothing special about this frequency generator because any common function generator can do the same thing that this one could do. There have been people who have copied this instrument and who charge enormous sums of money for a replica. As much as four or five thousand dollars. They claim that this is a real genuine Rife Machine. Do not be fooled. The same audio frequencies that were used in the 1953 AZ-58 were also used with this instrument. Those frequencies were 120, 660, 712, 727, 776, 784, 800, 803, 880, 1552, 1862, 2008, 2128.


RIFE FREQUENCY INSTRUMENT

John F. Crane ©61

DIAL NUMBERS
"P L" - PILOT LIGHT
"P" - POWER SWITCH
"R" - RANGE DIAL
"F" DIAL TUNING KNOB
"O" - OUTPUT and GROUND
"O K" - OUTPUT KNOB
Anode and Cathode
RVMI MODEL 802 SERIAL 21
NEW DEVICE—FOR INVESTIGATIONAL USE ONLY
FREQUENCY INSTRUMENT
RIFE VIRUS MICROSCOPE INSTITUTE SAN DIEGO CALIFORNIA
RANGE
POWER
V-1, 6SJ7
V-2, 6K6
V-3, 6SN7
V-4, 6K6
V-5, 6X5
SQUARE WAVEFORM
S-1 POWER
S-2 BAND
T-1
J-1
J-2

AUDIO SQUARE WAVE GENERATOR

Square Wave Range: 60 - 30,000 c.p.s.

Rated Output Power: 100 milliwatts into rated load (10 volts across a 1000 ohm resistive load).

DIAGRAM OF INSTRUMENT

FOR ELECTRON THERAPY

Page 4

www.rife.org
www.rifevideos.com

Below are several photographs of the many pad type frequency generators that John Cane and John Marsh built. The first one was built by John Crane.


OUTPUT
FREQUENCY (CPS)
OUTPUT
RANGE
AC OFF
MAX
AMPLITUDE
FREQ. MULTIPLIER
MAX
AMPLITUDE
RANGE
JOHN F. CRANE

This next three photos, shown below and on the next page, are of another one of John Crane's pad instruments built in the 1960's.

www.rife.org


JOHN F. CRANE


6009
JOHN F. CRANE

www.rifevideos.com
www.rife.org

The next two photos, shown below, are of the pad instrument built back in 1961 by John Crane and John Marsh. They at that time were calling their organization the "Rife Virus Microscope Institute". This name is on the front of their instrument. The first photo is from back in 1961 and the second photo is a new photo of one of these instruments which has survived.


RVMI
MODEL SQ2
SERIAL 1
NEW DEVICE – FOR INVESTIGATIONAL USE ONLY
RANGE
A
B
C
D
POWER
FREQUENCY INSTRUMENT
RIFE VIRUS MICROSCOPE INSTITUTE
SAN DIEGO
CALIFORNIA
JOHN F. CRANE


RVMI
MODEL SQ2
SERIAL 2
NEW DEVICE – FOR INVESTIGATIONAL USE ONLY
RANGE
A
B
C
D
POWER
FREQUENCY INSTRUMENT
RIFE VIRUS MICROSCOPE INSTITUTE
SAN DIEGO
CALIFORNIA

www.rifevideos.com

The next two photos, shown below, are pictures of one of John Marsh's pad instruments which he built in the 1980's. The first photo is from the 1980's and shows the aluminum disks which he was using at that time. The second photo shows this same instrument with another pad instrument which he built.



The next photo, shown below, is a new photo take of an instrument which John Marsh owned and gave to his nurse. It is similar to the instrument show in the first photo above.


SER. JLMSC-II
For Investigational Research
12
1
2
3
4
5
6
7
8
9
10
11
LEVEL
OUT
CALIBRATED
By
Code
Cal. Date
1986
Due
I.D. #
LIMITED CALIBRATION

www.rifevideos.com
www.rife.org

The next two photos, shown below, are of a pad machine that John Marsh made out of a 1950's Heathkit frequency generator. Almost all of the pad type machines that both John Crane and John Marsh built were really made from off-the-shelf frequency generators without any changes being made to them. Many times they would either replace the faceplate with their own or they would cover it so that no one would know that they were just using an off-the-shelf frequency generator. Above in one of the photos of John Crane's machine you can see that he covered the original faceplate so no one would know what he was doing. In the next two photos you can see that John Marsh did the same thing with this one. The first photo was taken by John in the 1980's and the second photo is a new photo of this instrument.

www.rife.org


www.rifevideos.com


www.rifevideos.com
HONEYWELL METROLOGY SERVICE
calibrated
due date
cal. by
SYNC. INPUT
SYNC. LEVEL
100
1K
10K
RANGE
MODEL SG-8
OFF
ON
POWER
OUTPUT

New device, to be used for Investigational purposes only

Chapter Summary: Pad type audio frequency instruments have done a lot of good over the years. But without an RF carrier frequency properly match with the correct audio frequencies Philip Hoyland's sideband method cannot be used with them. These instruments need to have an RF carrier frequency or the ability to output the exact frequency that Dr. Rife used. We know from the documents that Dr. Rife preferred using the exact frequency rather than Philip Hoyland’s sideband method, but either method will work and Dr. Rife used both. Dr. Rife’s frequency range included both the audio range and the RF range of frequencies from 1 Hertz to about 1,800,000 Hertz. Philip Hoyland's design produced higher harmonic frequencies of Dr. Rife's original frequencies in the 2,000,000 and 3,000,000 Hertz range.

The so called pad "Rife Machines” that are sold today which cannot produce these frequency ranges cannot produce Dr. Rife's results. Make sure that the frequency generator you purchase can produce both the audio and RF frequencies that Dr. Rife used. Also it should be understood that the pad type instruments are not able to output the power that the ray tube instruments can. Pad style instruments that do not use an RF carrier frequency or the higher RF frequency range generally do not exceed one half of one watt of power. This is because the body cannot take more that about one fifth of one watt before the electrical current begins to lock up the muscles of the user. When an RF carrier frequency is used then the body does not react to the electricity and this makes it so that higher power levels can be used up to the 10 to 12 watt range. Dr. Rife's ray tube instruments had power ranges from 50 to 200 watts output. The Rife Ray #5 or Beam Ray Clinical instrument power output was between 40 to 50 watts.

In the next chapter we will look at an AZ-58 type of ray tube instrument built by John Marsh in the 1970's.

www.rife.org

Chapter #15

John Marsh's 1970's Beam Ray replica Rife Machine



1. Used a ray tube.
2. Carrier frequency was 4.150 MHz.
3. Modulated sine and square wave audio frequencies onto the sine wave carrier frequency.
4. Power usage was about 460 watts. Output to the ray tube about 40 watts.

John Marsh had this replica of the Beam Ray Clinical Rife Machine Model #JLMSQ-1A built back in November 1971 for $3,800. It was completed by January 1, 1972. He and John Crane were under court order not to associate with each other. Because of this court order they went their separate ways but communicated often through phone calls and letters. John Crane stayed in California and John Marsh went to Colorado but eventually settled back in SLC, Utah until his death in 1987. All of his Rife Machines and Rife information were given to his nurse before his death. His equipment and documents were obtained from her in 2012. Since we were able to obtain this instrument we have been able to properly date it and take better photos of the complete instrument. Some of this information and new photos are shown below and are now apart of this report.

The photo at the top of the next page shows the two chassis that were connected by wires with their covers taken off. This instrument was a mix of both tube technology and modern solid state components.

www.rife.org


OUTPUT
TIMER MANUAL
SEC. 24 V
SEC. 24 V
FREQUENCY ADJUST
COARSE
FINE
MINUTES
POWER
OUTPUT
ON OFF
START

In the next photo, shown below, you can see that the instrument could output both sine and square wave audio frequencies. The frequency range of the audio oscillator went from 20 Hertz to 20,000 Hertz over three bands. John Marsh initially want it to have a frequency range from 0 to 100,000 Hertz. It had coarse and fine adjustments for the audio frequencies. Above those knobs we see the digital readout window of the frequencies. John Marsh put in a modern solid state audio oscillator with a digital readout. To the right of the digital readout we see a timer with a range of up to 5 minutes.


Frequencies
728
784
803
880
1552
1862
2008
2128
OUTPUT
TIMER MANUAL
MINUTES
2
1
4
0
5
Cramet
TIMER
POWER
R F
FREQUENCY ADJUST
COARSE
FINE
1x 10x 100x
ON OFF
START
OUTPUT

www.rife.org

To the right of that timer, shown below, in the first photo on the left, we see the power meter which is written on it “Standing wave ratio” and “Percent reflected power”. The knob below the meter was for adjusting the standing wave ratio. Below the knob is where the ray tube was connected. John Marsh used the CB antenna style connection instead of the banana jack method use in the original 1953 AZ-58. In the second photo, shown below on the right, you can still see an up close view of the John Marsh's masking tape with the 1950’s frequencies written on it.


STANDING WAVE RATIO
PERCENT REFLECTED POWER
POWER
R
F
OUTPUT
www.rifevideos.com


Frequencies
728
784
803
880
1552
1862
2008
2128
FREQUENCY ADJUST
www.rifevideos.com

The next photo, shown below, is a top view of the chassis with the case removed. You can clearly see that John Marsh used a mix of old tube technology and solid state electronics.


www.rifevideos.com

www.rife.org

The next four photos, shown below and on the next page, are close up photos of the top of the chassis. The first photo is the built in timer. The second photo is the solid state audio oscillator.



www.rife.org



The third photo shows the 811a main power output vacuum tube. The fourth shows the transformer that powers the audio oscillator board.





www.rifevideos.com
www.rife.org

The next photo, shown below, is a back view of the instrument. The meter is a D.C. milliamp meter. The socket to the right of the meter is for connecting the smaller box that has the power transformers.


PLATE X20
OSC X5
D.C. MILLIAMPERES
INT
EXT
OSCILLATOR

In the next four photos, shown below, give you an understand of the various components. The first photo labeled #1 is looking at the inside front of the instrument and shows the audio oscillator. To the left of the audio oscillator is the five minute timer. Photo #2, is looking at the back of the instrument and shows the three vacuum tubes. The three photos of vacuum tubes labeled #4, #5 and #6 show a clear view of the 811a, 6L6GC and 6GK6 vacuum tubes and their placement into the chassis. Photo #3 is one of John Marsh's original 1970 photo which shows the underside of the chassis where you can see the RF tank coil that was fixed at 4.150 MHz (4,150,000 Hertz).


Tank coil is located under
chassis and set at 4.150 MHz
JAPAN
6GK6
6L6
GC
JAPAN
811A
SYLVANIA

The next photo, show below, is a side view of the 811a tube. You can also see the RF choke right in front of the 811a tube with a small coil on top of it. This coil helped eliminate any parasitic oscillations.



The first of the next two photos, shown below and on the next page, is a photo which was taken of the underside of the chassis. The first photo, was one of the three pictures we have of the underside of the chassis. This photo was not very detailed and was taken back in 1971 when the instrument was built.

www.rife.org

In the second photo, shown below, (new clearer photo) the larger coil is the RF tank coil which was set to 4.150 MHz. The variable capacitor which has the black knob was used to tune the carrier frequency to 4.150 MHz.



The next four photos, shown below and on the next page, are up close photos of the underside of the chassis showing the various components used to build this instrument.

www.rife.org









www.rife.org

The next two photos, shown below are of the inside of the small case. It contained almost all the transformers. The standard Beam Ray Rife Machine had two shelves in one case for components. The AZ-58 combined everything into one case but for some reason John Marsh used two cases to hold the components.


SEC.
24 V
1.2 AMP
SEC.
24 V
1.2 AMP.


C-3181
T
TRIAD

www.rifevideos.com

The next two photos, shown below, are of this instrument being used in a doctors office back in 1972 when John Marsh live in Colorado.



www.rifevideos.com
www.rife.org

www.rifevideos.com
www.rife.org

The photo below is the ray tube which was used with this instrument. The ray tube still worked when we tested it.



John Marsh's instrument, like the AZ-58, was a more modern replica version of the original Beam Ray Clinical Rife Machine. The carrier frequency that John Marsh chose to use with this instrument again clearly shows he did not understand the importance of the RF carrier frequency. He changed it from the 1953 AZ-58’s 4.68 MHz to 4.150 MHz. The 4.150 MHz RF carrier frequency is probably one of the worst carrier frequencies he could have chosen using the AZ-58 low audio frequencies for the sideband method. In fact it would not be a good carrier for the higher audio frequencies either. We will explain again how to determine the best RF carrier frequencies to use in an instrument.

The method Philip Hoyland used to determine the best RF carrier frequency to use was by doing multiples of the BY (Sarcoma 1,529,520 Hertz) and the BX (Carcinoma 1,607,450 Hertz) frequencies. Logically, multiples of these frequencies are the best RF carrier frequencies to use because they were Dr. Rife's highest M.O.R. frequencies that he found. If you multiply the BY frequency by two you get 3,059,040 Hertz and if you multiply the BX frequency by two you get 3,214,900. So an RF carrier frequency in the 3,100,000 to 3,300,000 Hertz range would work well. Philip Hoyland used 3,300,000 Hertz. The next best range would be to multiply these two frequencies by a factor of three. The BY multiplied by three gives you 4,588,560 Hertz and the BX multiplied by three gives you 4,822,350 Hertz. So a carrier frequency in the 4,600,000 to 4,700,000 Hertz range would be the next best RF carrier frequency to use in an instrument. So you can see by the math that 4,150,000 Hertz would not be a good carrier frequency to use if you were going to used the sideband method that Philip Hoyland used when building the Rife Ray #5 or Beam Ray Clinical instrument. The RF carrier frequency should always be determined by multiples of the highest frequencies that Dr. Rife found for the various organisms. The 1953 AZ-58 had an RF carrier frequency of 4,680,000 Hertz. This carrier frequency would have worked very well had they understood the sideband method Philip Hoyland used. Since they lowered the audio frequencies instead of recalculating them to work on the sideband method then this also again reveals that they did not understand how Philip Hoyland’s instrument really worked.

With the above understanding it is easy to see that the only reason you would use a 4.150 MHz RF carrier frequency is if you did not care what RF carrier frequency you used. The fact that they didn't really care what RF carrier frequency they used is without question since both John Marsh and John Crane have said in several documents and on audio tapes that the audio frequencies were the M.O.R. frequencies. The whole concept of using the sideband spacing method is to choose a carrier frequency that would work the best with all of the Rife Ray #4 higher frequency harmonics. Had John Marsh really understood the significance of the RF carrier frequency he would have chosen a different one. But just like the 1953 AZ-58 they changed it and relied on the square wave audio frequency harmonics rather than the sideband spacing method used in the original Beam Ray Clinical instrument. The Aubrey Scoon Beam Ray Clinical instrument replica was working on the sideband spacing method because the audio frequencies used with it were high enough to make the number of sideband harmonics reasonably low. So far Aubrey Scoon’s instrument is the only instrument that we have seen, except for the original Beam Ray Clinical Rife Machine, which worked properly on the sideband spacing method.

www.rife.org

It is clear that the 1953 AZ-58 was not working fully on the sideband principle even though it could have. It appears that just by chance or accident some of the frequencies, like the BX frequency, worked because the RF carrier frequency was set at about 3.2 MHz by Dr. Stafford. Just the fact that they lowered the audio frequencies by a factor of 10 and then depended solely on square wave audio frequencies showed they didn't understand Philip Hoyland's sideband method. Had Philip Hoyland revealed how his Beam Ray Clinical Rife Machine worked a lot of confusion could have been avoided. This machine of John Marsh's could have easily been changed to work properly on the sideband method. The audio frequency range was designed to go to 20,000 Hertz. If the RF carrier frequency was changed to 3,300,000 Hertz, which would have been easy to do, then most of the original audio frequencies could have been used. The only two that would need to have been re-calculated would have been the BX and the BY frequencies. This also would have been easy to do.

In the chart, shown below, the frequencies have been calculated for John Marsh's instrument. You will notice that the "Original 1950's AZ-58 Frequencies" (low audio frequencies) are almost a perfect match to the "Correct Sideband Frequencies." But before we place too much significance in this coincidence we need to keep in mind the "Number of Sideband Harmonics." These numbers are so high that almost any low frequency can be divided into the "Carrier Difference Frequency" and come out within a few Hertz of the "Correct Sideband Frequency." The audio frequency needs to be a great deal higher in order to make it so the sideband frequencies will work. This is due to the fact that power is lost in sidebands. We must keep in mind that the higher the audio frequency is, the lower the number of sidebands that will be created and the better they will work. So these low audio frequencies in the chart below are two low to work with an RF carrier frequency of 4.150 MHz. In fact they would be too low to work even if they were used with a 3.30 MHz RF carrier frequency as was used in the original Beam Ray Clinical instrument. Using the higher audio frequencies like Philip Hoyland used is the

John Marsh's Beam Ray Clinical Instrument Sideband Square Wave Audio Frequencies Based On A 4.150 MHz Carrier

Organism	Rife Ray #4 Frequencies	Higher Harmonic Frequencies	*Carrier Difference Frequency	1/10 Of A Meter Freq.	Number of Sideband Harmonics	Original 1950's AZ-58 Frequencies	Correct Sideband Frequencies
Actinomycosis or Streptothrix	192,000 Hz	4,032,000 or 21st	118,000 Hz	12 Hz	151	784 Hz	781 Hz
Anthrax	139,200 Hz	4,176,000 or 30th	26,000 Hz	6 Hz	41		634 Hz
B or E Coli Rod	417,000 Hz	4,170,000 or 10th	20,000 Hz	58 Hz	25	800 Hz	800 Hz
B or E Coli Virus	770,000 Hz	3,850,000 or 5th	300,000 Hz	198 Hz	193	1552 Hz	1554 Hz
BX Virus Carcinoma	1,604,000 Hz	4,812,000 or 3rd	662,000 Hz	858 Hz	311	2128 Hz	2129 Hz
BY Sarcoma	?1,530,000 Hz	4,590,000 or 3rd	440,000 Hz	780 Hz	219	2008 Hz	2009 Hz
Gonorrhea	233,000 Hz	4,194,000 or 18th	44,000 Hz	18 Hz	62	712 Hz	710 Hz
Pneumonia or Spinal Meningitis	427,000 Hz	4,270,000 or 10th	120,000 Hz	61 Hz	155	776 Hz	774 Hz
Staphylococcus Pyogenes Aureus	478,000 Hz	4,302,000 or 10th	152,000 Hz	76 Hz	209	727 Hz	727 Hz
Streptococcus Pyogenes	720,000 Hz	4,320,000 or 6th	170,000 Hz	173 Hz	193	880 Hz	880 Hz
Syphilis	789,000 Hz	3,945,000 or 5th	205,000 Hz	207 Hz	311	660Hz	659 Hz
Tetanus	234,000 Hz	4,212,000 18th	62,000 Hz	18 Hz	517	120 Hz	120 Hz
Tuberculosis Rod	369,000 Hz	4,059,000 or 11th	91,000 Hz	45 Hz	113	803 Hz	805 Hz
Tuberculosis Virus	769,000 Hz	3,845,000 or 5th	305,000 Hz	197 Hz	197	1552 Hz	1548 Hz
Typhoid Rod	760,000 Hz	3,800,000 or 5th	350,000 Hz	192 Hz	492	712 Hz	711 Hz
Typhoid Virus	1,445,000 Hz	4,335,000 or 3rd	185,000 Hz	694 Hz	99	1862 Hz	1869 Hz

www.rife.org

method that worked in the original equipment. If the frequency you want to hit is close to the RF carrier frequency then the lower the audio frequency you can use. But if the frequency is farther away from the carrier frequency then the higher the audio frequency you will need to use in order to make it work properly. Philip Hoyland could have used even higher audio frequencies since his audio oscillator in the original Rife Ray #5 or Beam Ray Clinical instrument would go to a little over 40,000 Hertz. He could have used frequencies up in the 30,000 to 40,000 Hertz range which would have worked with even less sidebands. But Philip Hoyland was also trying to hide the method he was using. So Philip Hoyland balanced his frequencies in order to make sure they would work and also not reveal the method he was using. He did accomplish his goal.

If you look at the “Number of Sideband Harmonics” it takes to hit the correct Rife Ray #4 “Higher Harmonic Frequencies” you will understand that this instrument could never work on the sideband spacing method using these low audio frequencies. None of the “Number of Sideband Harmonics” are less than 59 sideband steps and the highest is 750. The chance of this working would be almost zero. The best method to use with John Marsh’s instrument is the audio frequency square wave harmonic method. This is the method he used with his instrument.

Below in the chart is a list of the higher audio frequencies, 20,000 Hertz or lower, that could be used with John Marsh’s instrument and make it work using the harmonic sideband method. Many different audio frequencies could be calculated to work. We did the highest audio frequency for each organism. The BX and the BY frequencies probably would not work since the sidebands would have to go nearly 600,000 Hertz to hit the correct frequency. For this reason the RF carrier frequency should be changed. The best frequencies would always be the highest audio frequency you could use within in the 20,000 Hertz frequency range of the instrument.

John Marsh’s Beam Ray Clinical Instrument Higher Sideband
Square Wave Audio Frequencies Based On A 4.150 MHz Carrier

Anthrax	13,000 Hz	Streptococcus	18,889 Hz
B or E Coli Rod	10,000 Hz	Steptothrix	19,667 Hz
B or E Coli Virus	20,000 Hz	Syphilis or Treponema	18,636 Hz
BX Virus Carcinoma	19,471 Hz	Tetanus	15,500 Hz
BY Sarcoma	19,130 Hz	Tuberculosis Rod	18,200 Hz
Gonorrhea	14,667 Hz	Tuberculosis Virus	19,062 Hz
Pneumonia or Spinal Meningitis	17,143 Hz	Typhoid Rod	19,444 Hz
Staphylococcus	19,000 Hz	Typhoid Virus	18,500 Hz

Chapter Summary: The fact that John Marsh built these Beam Ray replica Rife Machines and used different RF carrier frequencies with the same audio frequencies conclusively proves that he never understood how the instrument was really intended to work. This also shows that John Crane didn't really know how the instrument was intended to work either. John Crane was doing the same thing that John Marsh was doing. The fact that Philip Hoyland did not reveal how the Beam Ray Clinical instrument really worked has affected Rife's work in a negative way to this very day.

In the next chapter we will look at the ray tube instrument that John Marsh built back in the 1980's when he lived in Salt Lake City, Utah.

www.rife.org

Chapter #16

John Marsh’s 1980’s Ray Tube Rife Machine



UNDER GOVERNMENT REGULATIONS SHALL THI
ELECTRONIC INSTRUMENT BE USED BY ANY
PERSON ILLEGALLY.
This instrument does not emit any radio-
active particles. Its range is between 100
hertz and 2.5 kilohertz. It is tested as
very safe on the use of it on any living
thing.Cleared by the FCC.X-Rayed as safe.
The sole property of John E. Marsh, et al.

1. Used a ray tube.
2. Carrier frequency was ?
3. Square wave audio frequencies modulated onto a sine wave carrier frequency.
4. Power usage was about 125 watts. Output to the ray tube about 25 to 30 watts.

This style of ray tube instrument Model JLMSQ-101, which was built in the 1980's, was the last design that John Marsh built before his death. All of his Rife Machines and Rife information were given to his nurse before his death. His equipment and documents were obtained from her in 2012. Since we were able to obtain this instrument we have been able date it and take better photos of the complete instrument. Some of this information and new photos are shown below and are now included in this report.

www.rife.org
www.rifevideos.com

John Marsh built two different models of this style of Rife Machine. In the next two photos, shown below, we see the first model of this style of instrument. The instrument was a mix of both old vacuum tube technology and modern solid state technology. The audio oscillator was a solid state variable audio oscillator with a digital readout for displaying the frequencies. The frequency range went from about 20 Hertz to 20,000 Hertz. The instrument used the same low square wave audio frequencies that were used in the 1950’s AZ-58 Rife Machine built in 1953. Those thirteen frequencies were 120, 660, 712, 727, 776, 784, 800, 803, 880, 1552, 1862, 2008, 2128. The RF carrier frequency section was built using old vacuum tube technology. The RF carrier frequency was set at 2,200,000 Hertz. This RF carrier frequency again shows that John Marsh did not understand the harmonic sideband method that Philip Hoyland used in the original Rife Ray #5 or Beam Ray Clinical Rife Machine sold by the 1938-1939 Beam Ray Corporation. His earlier 1971 instrument which was discussed in Chapter 15 of this report used a 4.150 MHz (4,150,000 Hertz) RF carrier frequency. Both of these RF carrier frequencies (2.2 MHz and 4.150 MHz) clearly show that Philip Hoyland's sideband method was not used. What became of this instrument is not known. John Marsh most likely sold it to someone because he was building these for a few people who wanted them.



www.rifevideos.com

In the first photo, shown below, we see John Marsh's second style of Rife Machine. This is the same machine shown in the first photo of this chapter. This machine John Marsh used until his death in 1987. This machine was given to his nurse. We now have this machine and know how it worked. The instrument uses the same low square wave audio frequencies that were used in the 1953 AZ-58 Rife Machine. This instrument was unique because he did not have it built with a variable audio oscillator. Instead it had a dial which had 13 different positions for the 13 different audio frequencies which he used. John also had this instruments RF section built using old vacuum tube technology. The RF carrier frequency was also set to 2,200,000 Hertz (2.20 MHz). The fact that this instrument is still being used even after about thirty years speaks of its quality of construction. In the second photo, shown below, we see John Marsh with this instrument in the 1980's shortly before his death.



www.rife.org

The ray tube used with this instrument has an interesting design because it was designed to stand up. In the new photo, show below, you can see an up close view of this ray tube.



Below is a photo of the inside of the case that held the ray tube. You will notice that the ray tube is darkened. This happens to this type of ray tube because the metal electrodes are on the inside of the ray tube. When the ray tube is lit the metal comes of the electrodes and over time slowly contaminates the gas and the interior of the tube. The metal deposits or coats the inside of the ray tube and then the ray tube becomes less effective. In many cases the ray tube begins to sputter requiring it to be replaced or cleaned out and re-gassed. The photo of the new ray tube, shown above, is one of the extra ray tubes that John had built for this instrument. Many people no longer use ray tubes with internal electrodes because of this problem. The tubes without internal electrodes last for many years without any need of replacement. Some people have used them for more than 15 years and the ray tubes are still working without any problems.



www.rife.org
www.rifevideos.com

The photo, shown below, is the underside of the instrument with the bottom removed.


GEN INSTR
TD-2000-6
SM-D-433109-
MFD. 6 V.D.C
MAX. 85°C
11 -64

The next picture, shown below, is a photo of the instrument with the top cover removed.



The next photo, shown below, is a close up of the RF carrier frequency section showing the RF tank coil and the two variable tuning capacitors for tuning the RF carrier frequency to 2.20 MHz and for tuning the ray tube resonance.



In the next photo, shown below, you can see the two brass colored nuts with regular screw driver slots. The one on the left labeled “Load” was for tuning the ray tube and the other on the right which is labeled “Tune” was for tuning the carrier frequency.



www.rife.org

The next photo, shown below, is a side view of the instrument showing the electronics for the thirteen square wave audio frequencies.



In the next photo, show below you can see the tuning dial for each of the thirteen square wave audio frequencies. The dial started with the lowest audio frequency and went to the highest. The audio frequencies went in clockwise order from the first setting to the last setting 120, 660, 712, 727, 776, 784, 800, 803, 880, 1552, 1862, 2008, 2128.


CALIBRATED
By
Code
Cal. Date
Due
I.D. #
Scales LABORATORIES, INC.
SALT LAKE CITY
LIMITED CALIBRATION
ON
OFF
JLM SQ-101
S/N 760101

UNDER GOVERNMENT REGULATIONS SHALL THIS ELECTRONIC INSTRUMENT BE USED BY ANY PERSON ILLEGALLY.
This instrument does not emit any radio-active particles. Its range is between 100 hertz and 2.5 kilohertz. It is tested as very safe on the use of it on any living thing.Cleared by the FCC.X-Rayed as safe. The sole property of John E. Marsh, et al.

www.rifevideos.com
www.rife.org

The final photo, shown below, is of the machine with the ray tube lit. The ray tube would be a lot brighter if the tube was in new condition.



Chapter Summary: This instrument built by John Marsh used the same frequencies as the 1953 AZ-58. It also worked on the same low audio frequency square wave harmonics method as the AZ-58. The power level was lower than the AZ-58 and his 1970's AZ 58 replica discussed in chapter 15 of this report. This instrument was the last ray tube instrument John Marsh built before his death in 1987.

The next chapter will be a summary of the complete "Rife Machine Report."

www.rife.org

Chapter #17

Summery of the Rife Machine Report

www.rifevideos.com

In summary, with all the historical information that has come to light in the past few years we finally know the truth about which frequencies were Dr. Rife's M.O.R.s. We also understand the audio frequency sideband spacing method used in the Rife Ray #5 or Beam Ray Clinical instrument which hit the high harmonics of Dr. Rife original RF M.O.R. frequencies. Because Philip Hoyland hid how his instrument worked these audio frequencies, due to lack of knowledge, were lowered and used with a square wave waveform in the 1953 AZ-58. These lower square wave audio frequencies may not work as well as Dr. Rife's original frequencies but they have accomplished a lot of good helping many people. With the use of even more square wave audio frequencies a whole new field of frequencies are now available for our use. Having said this, we still need to remember Dr. Rife still maintained his true M.O.R. frequencies were in the RF band of frequencies. Even though Dr. Rife, John Crane and John Marsh tested these square wave audio instruments in the 1950's and early 1960's to see how well they would work. It wasn't until after John Crane and John Marsh were released from prison that they received Dr. Stafford's report showing the limited capability of the low square wave audio frequencies on cancer.

From about 1964 on, John Crane and John Marsh continued to build the audio frequency instruments even though they had the evidence from Dr. Stafford which showed the audio frequencies alone didn't work on cancer like the original high RF frequencies. Even though John Crane and John Marsh said the square wave audio frequencies were Dr. Rife's true M.O.R.s this does not change the fact that

www.rife.org

we now know the true purpose of the audio frequencies. The evidence in this report proves that Dr. Rife, John Crane and John Marsh really didn't understand how Philip Hoyland's Beam Ray Clinical instrument worked. This lack of understanding caused them to miss the truth when it was right before their eyes. We would still be in the dark had it not been for the original instruments found and the written documents that revealed Dr. Rife's high frequencies. Add to this the audio tapes which have Dr. Rife's own voice on them telling us his frequencies ranged from the audio to the broadcast bands. Dr. Rife was a pure scientist and only believed what he could prove. Had he seen Dr. Stafford's final report we feel certain he would have considered the cancer tests a failure. Dr. Rife said "he never fooled himself". It is entirely possible that Dr. Rife would have insisted they go back to his original high frequency design used in the Rife Ray #4 or put the 1953 AZ-58 RF carrier frequency back on 3.30 MHz and use Philip Hoyland's audio frequencies.

The most important information that has been obtained from the original Rife Ray #5 or Beam Ray Clinical instrument and Aubrey Scoon's Beam Ray replica instrument is the fact that the audio frequencies used in these instruments had nothing to do with the treatment of disease. To put it bluntly, all of us have been led down the primrose path because we did not understand how the Beam Rays Clinical instrument really worked. The mistakes made have major implications since the audio frequencies used with the AZ-58 (120, 660, 712, 727, 776, 784, 800, 803, 880, 1552, 1862, 2008 and 2128 Hertz) have no ability to eliminate the diseases we thought they would eliminate. In all reality these audio frequencies should be replaced with higher frequencies that are true harmonics of Dr. Rife's original high frequency M.O.R.s instead of clinging to the old dogma. Those who are really trying to do what Dr. Rife did should no longer promote the concept that these AZ-58 audio frequencies are M.O.R.s and by so doing put many people at risk. The best frequencies to use would always be the original high frequency M.O.R.s followed by lower audio frequencies that are exact lower harmonics of the high RF M.O.R. frequencies. For the most accurate list of Dr. Rife's original high RF frequencies go to the first chart on page 223. These frequencies were set by Philip Hoyland in Dr. Rife's laboratory using his microscope.

Hopefully this information will help make a change and in the future we will begin to see what Dr. Rife's original high frequency M.O.R.s will do. Many helpful people have provided the records and resources so this new information could be brought to light: the release of the John Marsh information from John Marsh's nurse; the Beam Ray Trial Papers from Steven Ross; the many photos from Jason Ringas of the Rife Research Group of Canada; the great benefit from Dr. Larry Low who allowed us to purchase the original Beam Ray Clinical instrument; the British Rife group and their work on the Aubrey Scoon replica instrument; the help of James Cunningham along with the great detective work done by James Peters in figuring out that Dr. Rife was using the Kennedy company Model 110, 220 and 281 receivers. We also want to recognize the great work Jim Peters did on the schematic of Dr. Gruners original Beam Rays Laboratory instrument. His recognition of the second variable Hartley Oscillator made it possible to rebuild an instrument that works like the original Beam Ray Laboratory instrument.

The spectrum analyzing of these machines has finally given us the answers to how all these different instruments really worked. I believe the recognition of the Kennedy equipment and the locating of the original 1938-1939 Beam Ray Clinical instrument along with the Beam Ray Laboratory instrument schematic correction and rebuilding are three of the greatest pieces of information we have yet discovered about Dr. Rife. No longer are we guessing in the dark. We have purchased the Kennedy Company equipment Models 110, 220 and 281 along with the original Beam Ray Clinical instrument for all of this testing. We plan on doing more extensive spectrum analysis work on this equipment. We have built, into one case, the Beam Ray Clinical and Laboratory instrument designs. We wish also to give special thanks to Henry Rogers the owner of the Western Historic Radio Museum (www.radioblvd.com). He allowed us the opportunity to come and test the Kennedy receivers that he owns. As more information comes out we will update this article as necessary.

www.rife.org

For those who would like a complete list of Dr. Rife’s frequencies output by the Rife Ray #3, Rife Ray #4, Philip Hoyland's Rife Ray #5 or Beam Ray Clinical instrument, Aubrey Scoon’s 1950's Rife Ray #5 and the AZ-58 Beam Ray replica instrument we have listed them in a chart on page 222. Other charts that may be of interest are included on pages 223 and 224.

None of the sets of the low audio frequencies are true M.O.R.s and were originally used to create the proper sideband spacing frequencies. The square wave audio frequencies used by the AZ-58 were used in a different manner or method relying only upon the harmonics from the square wave waveform. This method has been used with very good results over the past 50 years by many people, but, these audio frequencies have never produced the true M.O.R. effect of devitalizing organisms. The correct high RF M.O.R.s are the frequencies that should be used since we know what these frequencies are. If people are determined to use the lower audio and ultrasonic range of frequencies below 50,000 Hertz then they should at least use the highest harmonic frequency of the true M.O.R.s. At the very least we should make sure that all frequencies used are true harmonics of the fundamental M.O.R.s that Dr. Rife found.

www.rifevideos.com
Copyright © 2003 & 2013
All rights reserved.

www.rife.org

Rife's M.O.R Frequencies And Audio Sideband Frequencies

Microorganisms From Rife's Lab Notes And Other Documents.	Square Wave Frequencies for Rife, Crane, Marsh 1950s AZ-58 Beam Ray Replica. Built by Verne Thompson.	Sideband Frequencies For Aubrey Scoon's 1940s Beam Ray Replica. Built by Verne Thompson. Used with 3.30 MHz	Sideband Frequencies For Original Beam Ray Clinical Instrument. Built By Philip Hoyland 1938-1939. Recovered in 2008. Used with 3.80 MHz	High RF Frequencies For Dr. Rife's Rife Ray #3 and #4 Instruments. Correctly read in 1935 By Philip Hoyland*. Rife Ray # 4 built by*.	1/10th Of One Meter Frequency Tolerance.	Rife's Misread Lab Note Frequencies Before 1935. Frequency #1	Rife's Misread Lab Note Meter Frequencies Before 1935. Meters	Rife's Misread Lab Note Meters Converted To Hertz. Frequency #2
	Square Wave	Sine Wave	Sine Wave	Sine Wave		Sine Wave	Sine Wave	Sine Wave
Actinomycosis or Streptothrix	784 Hz	7,870 Hz	10,000 Hz	192,000 Hz	12 Hz	678,000 Hz	1,607 M	186,554 Hz
Anthrax			8,320 Hz	139,200 Hz	6 Hz	900,000 Hz	1,100 M	272,539 Hz
Anthrax Symptomatic						400,000 Hz	18,000 M	16,655 Hz
B or E Coli Rod	800 Hz	8,020 Hz	7,833 Hz	417,000 Hz	58 Hz	683,000 Hz	943 M	317,914 Hz
B or E Coli Virus	1,552 Hz	17,220 Hz	16,667 Hz	770,000 Hz	198 Hz	8,581,000 Hz	27 M	11,103,424 Hz
BX Virus Carcinoma	2,128 Hz	21,275 Hz	39,467 Hz	1,604,000 Hz	858 Hz	11,780,000 Hz	17.6 M	17,033,662 Hz
BY Sarcoma	2,008 Hz	20,080 Hz	37,000 Hz	? 1,530,000 Hz	780 Hz			
Bubonic Plague						160,000 Hz	585 M	512,466 Hz
Catarrh						1,800,000 Hz	175 M	1,713,100 Hz
Cholera Spirillum						851,000 Hz	312 M	960,873 Hz
Contagious Conjunctivitis						1,206,000 Hz	148 M	2,025,625 Hz
Diptheria						800,000 Hz	275 M	1,090,154 Hz
Glanders						986,000 Hz	407 M	736,591 Hz
Gonorrhea	712 Hz		14,400 Hz	233,000 Hz	18 Hz	600,000 Hz	1,990 M	150,649 Hz
Influenza						1,674,000 Hz	154 M	1,946,704 Hz
Leprosy						743,000 Hz	1,190 M	251,926 Hz
Pneumonia						1,200,000 Hz	785 M	381,901 Hz
Pneumonia or Spinal Meningitis	776 Hz	7,660 Hz	8,600 Hz	427,000 Hz	61 Hz	927,740 Hz	167 M	1,795,164 Hz
Staphylococcus Pyogenes Aureus	727 Hz	7,270 Hz	8,000 Hz	478,000 Hz	76 Hz	988,740 Hz	540 M	555,171 Hz
Staphylococcus Pyogenes Albus							546 M	549,070 Hz
Streptococcus Pyogenes	880 Hz	8,450 Hz	8,333 Hz	720,000 Hz	173 Hz	1,214,000 Hz	142 M	2.111.214 Hz
Syphilis (Treponema Pallidum)	660 Hz	6,600 Hz	6,591 Hz	789,000 Hz	207 Hz	900,000 Hz	108 M	2,775,856 Hz
Tetanus	120 Hz	1,200 Hz	11,200 Hz	234,000 Hz	18 Hz	700,000 Hz	19,000 M	15,779 Hz
Tuberculosis Rod	803 Hz	8,300 Hz	8,462 Hz	369,000 Hz	45 Hz	583,000 Hz	554 M	541,142 Hz
Tuberculosis Virus	1,552 Hz	16,000 Hz	16,910 Hz	? 769,000 Hz	197 Hz			
Typhoid Rod	712 Hz	6,900 Hz	100 Hz	760,000 Hz	192 Hz	900,000 Hz	345 M	868,964 Hz
Typhoid Virus	1,862 Hz	18,620 Hz	38,214 Hz	1,445,000 Hz	694 Hz	9,680,000 Hz	21.5 M	13,943,835 Hz
Worms		2,400 Hz						

www.rife.org www.rife.org www.rife.org www.rife.org

Dr. Rife's Original High RF Frequencies Fine Tuned To The Precise Frequencies By Philip Hoyland.

Actinomycosis (Streptothrix)	191,803 Hz
Anthrax	139,200 Hz
B. Coli (Rod form)	416,510 Hz
B. Coli (Filterable virus)	769,035 Hz
Bacillus X or BX (Cancer Carcinoma)	1,607,450 Hz
Bacillus Y or BY (Cancer Sarcoma)	1,529,520 Hz
Gonorrhea	233,000 Hz
Spinal Meningitis	426,862 Hz
Staphylococcus Pyogenes Aureus	477,660 Hz
Staphylococcus Pyogenes Albus	549,070 Hz
Streptococcus Pyogenes	719,150 Hz
Syphilis	788,700 Hz
Tetanus	234,000 Hz
Tuberculosis (Rod)	369,433 Hz
Tuberculosis (Virus)	769,000 Hz
Typhoid Fever (Rod)	759,450 Hz
Typhoid Fever (Virus)	1,445,180 Hz

Philip Hoyland's Audio Frequencies Used With 3.30 MHz To Produce Through Sidebands Dr. Rife's Frequencies

B or E Coli Rod	8,020 Hz	Syphilis or Treponema	6,600 Hz
B or E Coli Virus	17,220 Hz	Tetanus	1,200 Hz
BX Virus Carcinoma	21,275 Hz	Tuberculosis Rod	8,300 Hz
BY Sarcoma	20,080 Hz	Tuberculosis Virus	16,000 Hz
Pneumonia or Spinal Meningitis	7,660 Hz	Typhoid Rod	6,900 Hz
Staphylococcus	7,270 Hz	Typhoid Virus	18,620 Hz
Streptococcus	8,450 Hz	Worms	2,400 Hz
Streptothrix	7,870 Hz		

www.rife.org

Philip Hoyland’s New M.O.R.s.
Used In The Beam Ray Clinical Instrument.

B or E Coli Rod	3,332,080 Hz	Streptothrix	3,260,650 Hz
B or E Coli Virus	3,076,140 Hz	Syphilis or Treponema	3,154,800 Hz
BX Virus Carcinoma	3,214,900 Hz	Tetanus	3,276,000 Hz
BY Sarcoma	3,059,040 Hz	Tuberculosis Rod	3,324,897 Hz
Gonorrhea	3,262,000 Hz	Tuberculosis Virus	3,076,000 Hz
Pneumonia or Spinal Meningitis	3,414,900 Hz	Typhoid Rod	3,037,800 Hz
Staphylococcus	3,343,620 Hz	Typhoid Virus	2,890,360 Hz
Streptococcus	3,595,750 Hz		

www.rife.org www.rife.org www.rife.org www.rife.org www.rife.org

Color Atlas of
Forensic Medicine and Pathology



Edited by

Charles A. Catanese

CRC Press
Taylor & Francis Group

Color Atlas of
Forensic Medicine and Pathology

Color Atlas of
Forensic Medicine and Pathology

Edited by

Charles A. Catanese

CRC Press
Taylor & Francis Group
Boca Raton London New York

CRC Press is an imprint of the
Taylor & Francis Group, an **informa** business

Contributor Gina Marie Santucci retains copyright of photo of New York City skyline used on the dedication page and the photo of the morgue used on the back cover.

CRC Press
Taylor & Francis Group
6000 Broken Sound Parkway NW, Suite 300
Boca Raton, FL 33487-2742

© 2010 by Taylor and Francis Group, LLC
CRC Press is an imprint of Taylor & Francis Group, an Informa business

No claim to original U.S. Government works

Printed in the United States of America on acid-free paper
10 9 8 7 6 5 4 3 2 1

International Standard Book Number: 978-1-4200-4320-4 (Hardback)

This book contains information obtained from authentic and highly regarded sources. Reasonable efforts have been made to publish reliable data and information, but the author and publisher cannot assume responsibility for the validity of all materials or the consequences of their use. The authors and publishers have attempted to trace the copyright holders of all material reproduced in this publication and apologize to copyright holders if permission to publish in this form has not been obtained. If any copyright material has not been acknowledged please write and let us know so we may rectify in any future reprint.

Except as permitted under U.S. Copyright Law, no part of this book may be reprinted, reproduced, transmitted, or utilized in any form by any electronic, mechanical, or other means, now known or hereafter invented, including photocopying, microfilming, and recording, or in any information storage or retrieval system, without written permission from the publishers.

For permission to photocopy or use material electronically from this work, please access www.copyright.com (http://www.copyright.com/) or contact the Copyright Clearance Center, Inc. (CCC), 222 Rosewood Drive, Danvers, MA 01923, 978-750-8400. CCC is a not-for-profit organization that provides licenses and registration for a variety of users. For organizations that have been granted a photocopy license by the CCC, a separate system of payment has been arranged.

Trademark Notice: Product or corporate names may be trademarks or registered trademarks, and are used only for identification and explanation without intent to infringe.

Library of Congress Cataloging-in-Publication Data

Color atlas of forensic medicine and pathology / editor, Charles Catanese.
p. ; cm.
Includes index.
ISBN 978-1-4200-4320-4 (hardcover : alk. paper)
1. Forensic pathology--Atlases. 2. Autopsy--Atlases. I. Catanese, Charles. II. Title.
[DNLM: 1. Forensic Pathology--Atlases. 2. Pathology, Clinical--Atlases. W 617 C7186 2010]

RA1063.4.C65 2010
614'.10222--dc22 2009029826

Visit the Taylor & Francis Web site at
http://www.taylorandfrancis.com

and the CRC Press Web site at
http://www.crcpress.com

Dedicated

This book is dedicated to the members of service who lost their lives as a result of the 9/11 attacks, and further dedicated to all those who suffered a loss associated with the aftermath.

Table of Contents

Preface **ix**
Acknowledgments **xi**
Editor **xiii**
Contributors **xv**
Research Assistants and Photo Imaging Contributors **xvii**

1 Sudden Natural Death in a Forensic Setting **1**
CHARLES A. CATANESE AND AMY V. RAPKIEWICZ

2 Therapeutic Interventions, Complications, and Accidents **57**
MICHAEL J. CAPLAN AND CHARLES A. CATANESE

3 Substance Abuse and Poisoning **85**
CHARLES A. CATANESE AND LAURA M. LABAY

4 Postmortem Change and Time of Death **111**
CHARLES A. CATANESE, BRUCE LEVY, AND GERARD CATANESE

5 Pediatric Forensic Pathology **147**
MICHAEL J. CAPLAN AND CHARLES A. CATANESE

6 Blunt-Force Injuries **189**
CHARLES A. CATANESE AND JONATHAN LUCAS

7 Sharp-Force Injuries **239**
CHARLES A. CATANESE

8 Gunshot Wounds **283**
CHARLES A. CATANESE, THOMAS GILSON, AND THOMAS ANDREW

9 Burns **353**
CHARLES A. CATANESE AND GERARD CATANESE

10 Asphyxia **373**
CHARLES A. CATANESE AND BARBARA K. BOLLINGER

Index **399**

Preface

While death investigation, and what we have come to understand as "forensic pathology," has been practiced in one way or another back to antiquity, official designation of forensic pathology as a subspecialty by the American Board of Pathology dates back only to 1956. The subspecialty comprises a small band of trainees in pathology and at any given time there are only 400 to 500 full-time practitioners of the specialty in the United States.

Furthermore, as a recognized subspecialty, forensic pathology is young enough that each of its full-time practitioners can trace his or her roots back to one of the six individuals who sat for that original examination back in 1956. For many of the authors of this volume, that family tree goes from Lester Adelson through Charles Hirsch and ultimately to us. We acknowledge and are proud of the fact that we stand on the shoulders of giants.

Our collective experiences as trainees and staff at the Office of the Chief Medical Examiner in New York City under the tutelage of Dr. Charles S. Hirsch has made us the forensic pathologists we are today. Our mentor's emphasis on precision and accuracy in description of findings, translation of these descriptions into language easily understood by a broad range of end users, and the public health importance of our work has left an indelible imprint that we desire to pass on to others. It is our hope that this atlas reflects these qualities.

With sincerest gratitude,

Thomas Andrew
Fellowship Class of 1992

Michael J. Caplan
Gerard Catanese
Bruce Levy
Fellowship Class of 1993

Thomas Gilson
Charles A. Catanese
Fellowship Class of 1995

Barbara K. Bollinger
Jonathan Lucas
Fellowship Class of 2000

Acknowledgments

I would first like to thank my parents, S. John Catanese and Helen J. Amendola, and my grandparents, with a special thanks to my grandfather, Anthony J. Amendola, who taught me a strong work ethic and instilled a driving force to succeed while helping others. I would also like to thank my older brother, Anthony Catanese, MD, who first excited my interest in pursuing a career in medicine.

I would like to thank my judo sensei, Hank Kraff, who taught me how to defend myself, the nature of competition, and the value of pursuing an education.

I would like to thank my analytical chemistry professor at St. John's University, Richard E. Cover, PhD, whose kind nature and brilliant thought first excited my interest in the field of forensics.

I am grateful to Edward Laski, MD, PhD, who instilled in me an interest and understanding of psychiatry during medical school at SUNY Downstate, which led me to further understand different motivations leading to death.

I would like to thank Alistair Cunningham, MD, Dominick DiMaio, MD, Thomas Athanassiades, MD, Martin J. Salwen, MD, and Theresa DiMaio, MD, who taught me autopsy pathology during medical school and residency training at Downstate Medical Center/Kings County Hospital in Brooklyn, NY.

My fellowship training in forensic pathology was by Charles S. Hirsch, MD, at the New York City Office of the Chief Medical Examiner. My gratitude goes to Dr. Hirsch again for being such a great teacher and mentor.

I would also like to thank Maria Luz Alandy, MD, Joaquin Gutierrez Jr., MD, Thomas Andrew, MD, Gerard Catanese, MD, Kari Reiber, MD, Vernon Armbrustmacher MD, and Joseph Veress, MD for their patience in teaching and mentoring me as a junior attending in the New York City Medical Examiner system.

Thanks to Charles V. Wetli, MD, and Stewart Dawson, MD, who taught me many important concepts about forensic medicine while I worked for several years giving locums coverage at the Suffolk County (New York) Medical Examiner's Office.

I would like to thank all the NYC Medical Examiners, and the New York City Office of the Chief Medical Examiner for giving me access to many high quality academic images. More specifically, I thank Corinne Ambrosi, MD, Vernon Armbrustmacker, MD, Barbara Bollinger, MD, Stephen deRoux, MD, Thomas Gilson, MD, James Gill, MD, Lara Goldfeder, MD, Beverly Leffers, MD and Kristen Roman, MD.

I would also like to thank the Photography Department, the interns and clerical staff who assisted on this work over several years, and without whose help this publication would not have happened.

I would like to thank the Brooklyn District Attorney's Office and the New York City Police Department for always following through and maintaining the highest standard of work and professionalism in a harsh environment. Included in this is a special thanks to the Brooklyn North and South Homicide Divisions, with a very special thanks to Louis Savarese, Detective First Class, retired, and Terence Murnane, Detective First Class, retired.

Finally, I would like to thank the Orange County Executive, Edward Diana; the Orange County Commissioner of Health, Jean Hudson, MD; and the Orange County Deputy Commissioner of Health, Chris Dunleavy, for giving me the opportunity to serve the public and for helping me establish Orange County's first medical examiner system.

My sincerest thanks to all of you,

Charles A. Catanese

Editor

Charles A. Catanese, MD completed his medical school education at SUNY Downstate and his residency training at State University Hospital—Kings County Hospital complex in Brooklyn, New York. He is board certified by the American Board of Pathology in Anatomic Pathology and Forensic Pathology. Following his forensic pathology fellowship training in New York City, he was employed as a full time medical examiner in the Brooklyn office of New York City for more than 10 years. He has performed in excess of 4000 autopsies, including more than 400 homicides, and has supervised many more. As educational coordinator of Brooklyn, he accumulated many academic images demonstrating a wide variety and spectrum of presentation for many forensic topics. The Brooklyn Office is the busiest of the five boroughs and New York City has the largest medical examiner's system in the country. Dr. Catanese has also worked as a private consultant for many years and has provided locums coverage in the States of New Hampshire, New Jersey, Tennessee, Rhode Island, Vermont, and New York. He also worked through several disasters including TWA Flight 800, AA Flight 587 and more than 9 months on the World Trade Center fatalities. He is currently the Chief Medical Examiner of Orange County New York, where he established and converted that office from a preexisting coroner system.

Contributors

Thomas Andrew, MD
Chief Medical Examiner
State of New Hampshire
Concord, New Hampshire

Barbara K. Bollinger, MD
Deputy Chief Medical Examiner
Orange County, New York

Michael J. Caplan, MD
Pediatric and Forensic Pathologist
Mercy Hospital-Cadillac
Cadillac, Michigan
and
Department of Pathology and Laboratory Management
Medical University of South Carolina
Charleston, South Carolina

Gerard Catanese, MD
Deputy Medical Examiner
Nassau County, New York
East Meadow, New York

Thomas Gilson, MD
Chief Medical Examiner
State of Rhode Island
Providence, Rhode Island

Laura M. Labay, PhD
Forensic Toxicologist
National Medical Services Laboratory
Willow Grove, Pennsylvania

Bruce Levy, MD
Chief Medical Examiner
President and CEO Forensic Medical
State of Tennessee
Nashville, Tennessee

Jonathan Lucas, MD
Deputy Medical Examiner
San Diego County, California
and
Associate Clinical Professor
Department of Pathology
University of California at San Diego
San Diego, California

Amy V. Rapkiewicz, MD
Director of Autopsy Service
Director, Anatomic Pathology
New York University/Bellevue Hospital
New York, New York

Research Assistants and Photo Imaging Contributors

Vanessa Cannone
Autopsy/Research Assistant
Orange County, New York

Jim Carlson
Department of Forensic Imagery and Radiology
New York City Office of the Chief Medical Examiner
New York, New York

Patrick Horan
Autopsy/Research Assistant
Orange County, New York

Salwa Jwayyed
New York City Police Department
New York, New York

Jaclyn McCarthy
Autopsy/Research Assistant
Orange County, New York

Jennifer McMahon
Medical Investigator
Orange County, New York

Tarin Romich, MPH
Osteopathic Medical Student
New York College of Osteopathic Medicine
Old Westbury, New York

Gina Marie Santucci
Department of Forensic Imagery
New York City Office of the Chief Medical Examiner
New York, New York

Sudden Natural Death in a Forensic Setting

1

CHARLES CATANESE AND AMY V. RAPKIEWICZ

Introduction

This chapter offers a brief overview of some common and some not so common natural deaths that typically may occur in a medical examiner system. Also demonstrated are examples that may alter appearance of tissue such as formaldehyde fixation and variation due to different types of photographic imagery. There are also examples of normal organs in both a fresh and formaldehyde fixed state that can be used by the reader to compare with diseased organs.

Deaths under this category are often unexpected and sometimes unwitnessed. There is often a suspicion of foul play. Families may say, "But Doctor, he was in fine health. I saw him an hour ago. It cannot be natural. Somebody must have harmed him," etc. Because of the sudden, often unexpected nature of these deaths, it is best to do an autopsy to clarify exactly what happened. This decision to autopsy depends on many factors, including the decedent's age, medical history, family wishes, decedent's wishes (wills, etc.), religious beliefs, circumstance at time of death, resources of a particular system, etc. As one becomes less certain of the cause of death, the level of suspicion will increase. At some point, the decision to autopsy becomes obvious and absolutely necessary. This decision is based on experience, knowledge, and sound judgment. Not infrequently, seemingly natural deaths can have unnatural or traumatic previous circumstances; therefore, when uncertain, an autopsy is best performed. In many medical examiner systems, the majority of deaths end up being certified as natural.

Sudden death is defined in different ways. It may indicate a death that occurs within 24 hours of the onset of symptoms. It may also indicate the death occurred within 1 hour or even within seconds. There are not many diseases that can cause death within minutes of the onset of symptoms. Natural death means the manner of death is exclusively or 100% natural. If there is a 1% component of another manner of death, it is no longer natural. If there are multiple components of different manners of death commingled in a case investigation, the following rule will apply: a homicide overrides all, then an accident, then a therapeutic complication. A suicide requires the establishment of intent to do harm to oneself. For example, someone with end-stage metastatic liver cancer ingests 100 acetaminophen tablets to commit suicide. In the process of waiting to die, he decides to walk to a store. On the way, he trips in a pothole, falls in the street, strikes his head, and has an expanding subdural hemorrhage. While he is lying there waiting for EMS, a stolen car fleeing the scene of a robbery runs him over, lacerates his heart in half, and he dies within seconds. The manner of death in the case would be homicide. The death occurred as a result of being run over by a car during an illegal act. A lacerated heart is universally fatal regardless of the other violent and natural processes. The death certificate should include only the trauma from the car. If the trauma from the car was not lethal by itself, one may add "other finding" to part two of the cause of death, but the manner would remain homicide.

Heart Disease

Heart disease leading to ventricular irritability to create a lethal arrhythmia is the most significant cause of death in this category. The most common arrhythmia leading to sudden cardiac death is ventricular fibrillation. Ventricular tachyarrhythmias are most commonly seen within 12 hours of a myocardial infarction. Critical coronary atherosclerosis and hypertension are by far the leading causes of these processes. Some diseases that contribute to atherosclerosis and arteriosclerosis formation include hyperlipidemia, high blood pressure, diabetes mellitus, obesity, cigarette smoking, stress, and sedentary life style.

Having 75% or greater blockage in any of the epicardial vessels is considered critical stenosis and is consistent with being alive one second and having loss of consciousness leading to death the next. Hypertensive cardiovascular disease is usually essential in origin from an intrinsic abnormality of sodium metabolism. Other significant causes of hypertension include many types of kidney disease including adult polycystic kidney disease and renal artery stenosis. Hypertension may be sporadic and missed on routine doctor appointments. High blood pressure is also associated with small-vessel coronary artery disease, as is diabetes mellitus, which is a reasonable cause of death by itself. Once people reach a pivotal point of myocardial irritability and go into ventricular fibrillation they usually have approximately 15 seconds of consciousness left. Prior to losing consciousness, decedents may reach up to chest or neck and mention a fluttering sensation in the chest. They may have pressure, pain, or no expectation of what is to come. Ventricular irritability associated with coronary artery ischemia is due to lack of oxygen and nutrients reaching the conducting system of the heart. If the heart is not cardioverted back to a normal rhythm within 4–6 minutes, there is usually irreversible brain damage.

Another major cause of ventricular irritability leading to fatal arrhythmia is hypertension. Concentric left ventricular hypertrophy usually defined at autopsy as having a left ventricular wall thickness greater than 1.5 cm for most average-sized adults is a known risk factor for sudden cardiac death. Left ventricular thickness is best measured approximately 2 cm below the mitral valve annulus and excludes trabeculations and papillary muscles. As the disease process causing cardiac hypertrophy advances, heart failure may ensue with chamber dilatation. Although the overall heart size is enlarged, the left ventricle wall thickness may be less than 1.4 cm. Although hypertensive disease is the major risk factor for the development of left ventricular hypertrophy, other risk factors include aortic stenosis, either congenital or acquired. The hearts of patients with hypertensive or arteriosclerotic cardiovascular disease typically show evidence of prior infarction and interstitial fibrosis. Both findings also predispose to myocardial irritability and fatal (tachy)arrythmias.

Complications other than tachyarrhythmia and pump failure of myocardial infarctions can result in sudden cardiac death; the most common include the myocardial rupture syndromes including ventricular wall and papillary wall rupture. Typically, these insults occur approximately 1 week following a myocardial infarction, the point at which there is removal of necrotic myocytes by macrophages. Hemopericardium with ensuing cardiac tamponode can occur following ventricular free wall rupture; this scenario is rapidly fatal in most cases, causing decreased venous return to the heart with jugular venous distention.

In young patients, particularly athletes, hypertrophic cardiomyopathy is not an uncommon cause of sudden death. These patients can be asymptomatic prior to the sudden event or may have past episodes of palpitations or syncope. Typically, macroscopic heart evaluation shows cardiac hypertrophy with significant asymmetry of the subaortic septal region, which poses as an outflow obstruction. Microscopic sections from this region show variable degrees of myocyte disarray, fibrosis, myocyte hypertrophy, and small-vessel disease. The disease is due to an autosomal dominant mutation in the cardiac sarcomere apparatus, most commonly the myosin heavy chain, but many mutations have been described.

Arrhythmogenic right ventricular cardiomyopathy can present with sudden unexpected death. At autopsy, the right ventricle is thinned, with microscopic evaluation showing significant transmural infiltration by fibrofatty tissue.

Myocarditis due to a variety of causes including viral, bacterial, fungal, parasitic, autoimmune, and hypersensitivity can present as sudden death. The degree of activity, myonecrosis, and the location of the inflammation (i.e., conduction system involvement) are important in determining the significance of the infiltrates. Notably, eosinophils are seen quite commonly in hypersensitivity myocarditis and can be a clue to the underlying etiology.

Dilated cardiomyopathy is common, and has many etiologies that include idiopathic arteriosclerotic disease, hypertensive cardiovascular disease, alcoholism, elevated catecholamines, myocarditis, postpartum, doxorubicin, endocrinopathies, and genetic diseases. The heart typically is enlarged with a globoid configuration. The microscopic analysis shows interstitial fibrosis.

Rare infiltrative cardiac disease such as amyloidosis, hemochromatosis, primary or metastatic tumors, and sarcoidosis can result in sudden death. Microscopic evaluation in these cases is necessary, with particular attention to nodal tissues.

S. aureus is the most common organism found in infective endocarditis (IE). *S. aureus* endocarditis is associated with the highest mortality and risk of embolism. Increasing age, periannular abscess, heart failure, and absence of surgical therapy were identified in multivariate analysis as independent poor prognostic factors for increased mortality in patients with *S. aureus* IE. Other risk factors for the development of IE include congenital or acquired anatomic valve abnormalities such as stenosis. Impaired cardiac conductivity and function with heart failure not infrequently develops in patients with multiple septic myocardial emboli and infarcts due to IE, particularly with paravalvular abscess formation. According to a recent study of a cohort of 606 cases of infective endocarditis, 99 cases have embolization, of which 32 cases involve the central nervous system (CNS) with significantly higher mortality (65%) than those without CNS emboli.

Recently, genetic abnormalities have been found to underlie many of the intrinsic abnormalities of conducting systems including Wolff–Parkinson–White syndrome (WPW) and long Q-T syndrome. Sudden death in WPW is thought to occur as a result of an induction of ventricular tachycardia via an atrioventricular reentry pathway. Long-QT syndrome can also present with sudden death. Investigations are ongoing around the association of sudden infant death syndrome with long-QT syndrome. Recent data is suggesting that a genetic basis for the arrhythmogenic disease with the identification of the long-QT genes.

Sudden death related to cardiac valve pathology other than endocarditis is relatively uncommon, as valve replacement surgery has become a standard therapy. Patients with aortic stenosis, especially when acutely symptomatic, can experience sudden cardiac death. Most cases of aortic stenosis are caused by either rheumatic heart disease or valve calcification, which can occur on trileaflet or congentially (uni)bicuspid valves. The mechanism for death in severe aortic stenosis (valve area <1cm2) appears to be through left ventricular hypertrophy and subsequent myocardial instability. In rare instances of severe aortic valve calcification, the deposits can erode the region and involve the conduction system. Mitral valve prolapse has long been associated with sudden cardiac death. The underlying etiology is not well understood, but seems to most frequently involve a severe valve deformity with a redundant, thickened, myxomatous mitral valve and ventricular arrhythmias such as ventricular fibrillation. On histologic sectioning, the mitral valve will show deposition of acid mucopolysacchrides.

Coronary artery anomalies are not uncommon but only certain anomalies result in ischemia such as anomalous origin of a coronary artery from the opposite sinus (ACAOS), anomalous left coronary artery from the pulmonary artery (ALCAPA), ostial atresia/stenosis, and coronary artery fistulas. Left-sided ACAOS can result in acute takeoff angles with an increased risk of sudden death during or shortly after exercise. Besides the acute angle take off, there maybe ridge like defect at the coronary ostea further decreasing blood flow in times of accelerated heart rates with increased oxygen demand. Myocardial tunneling is another anomalous coronary artery distribution that maybe associated with increased arrhythmogenic potential. There is debate about the significance of this anomaly. Some still believe it may be significant when a large portion of the epicardial coronary artery dips deeply into the left ventricle wall for a considerable distance, during times of rapid muscle contraction.

Vascular Disease

Causes of sudden death associated with vascular disease include those that lead to occlusion, narrowing, or rupture of a blood vessel. Atherosclerotic aneurysms can rupture, leading to rapid loss of consciousness and death. These aneurysms can occur just about anywhere, but are by far most common in the abdominal aorta. Most abdominal aortic aneurysms occur below the renal artery. The risk of rupture increases with the size of the aneurism, smoking history, and hypertension. The annual risk of rupture over 7 cm in size is 33%. Retroperitoneal rupture is typically associated with hematoma formation, whereas rupture into the abdominal cavity can be rapidly fatal, with hemoperitoneum and shock. Patients who have a ruptured aortic aneurysm and reach the hospital have a 50% mortality rate, with the overall mortality rate greater than 85%.

Aortic dissection is characterized by an intimal tear followed by a dissection of blood within the wall of the aorta, most commonly the tunica media. Rupture of this dissecting aortic hematoma may lead to hemothoraces, hemopericardium, or fatal arrhythmia. Aortic dissection is a major cause of sudden death, mostly in patients over 50 years of age with the underlying risk factor being essential hypertension. However, pregnant women and patients with connective-tissue diseases such as Marfan's syndrome also make up a significant affected patient population. Aortic dissection can also occur following accidental or iatrogenic trauma to the aortic intima. In younger patients and those with connective tissue disease, microscopy may reveal cystic medial degeneration of the aortic media.

Most spontaneous subarachnoid hemorrhages (SAH) (90%) are caused by ruptured intracranial saccular (berry) aneurysms. SAH occurs at a peak age of 55–60 years. Rupture of an intracranial aneurysm is believed to account for 0.4 to 0.6% of all deaths. SAH is associated with a greater than 50% mortality rate. Some hospital-based studies suggest that approximately 10% of patients with aneurismal SAH die prior to reaching the hospital, 25% die within 24 hours of SAH onset, and about 45% die within 30 days. It is not unusual to perform forensic autopsies where death was almost instantaneous and outside of a hospital. The mechanism of death in such cases is cardiac arrhythmia, which is described in greater depth later. Most intracranial aneurysms (approximately 85%) are located in the anterior circulation, predominately on the circle of Willis. Risk factors for both SAH and intracranial aneurysms are similar and include hypertension, cigarette smoking, and alcohol consumption. Atherosclerosis is an independent risk factor for the development of intracranial aneurysms. The natural history of subarachnoid hemorrhage shows that rupture often occurs when they reach a size over 7 mm. Rupture of an aneurysm releases blood directly into the cerebrospinal fluid (CSF) under arterial pressure. The blood spreads quickly within the CSF, rapidly increasing intracranial pressure. A major symptom associated with SAH includes patients describing the worst headache of one's life. Increased intracranial pressure is associated with the Cushing's triad (hypertension, bradycardia, and abnormal respiration). SAH is associated with cerebral edema and subsequent herniation. Tonsillar and central transtentorial herniation is associated with compression of cardiovascular and respiratory centers in the medulla and as such is rapidly fatal. Other less common causes of subarachnoid hemorrhages include angiomas and arteriovenous malformations. Ruptured berry aneurysms are the most common natural cause of SAH, whereas trauma is the most common overall cause. Ruptured berry aneurysms are a leading cause of sudden death in women during sexual activity, whereas for men it is heart disease.

Cerebrovascular accidents (episodes), which include ischemic or intracerebral hemorrhage, can lead to sudden death. I recommend not using the term "accident" because there is nothing accidental about this process and its use often adds confusion in forensic proceedings. The terms "stroke" or "event" as an alternative is less confusing to nonmedical personnel. Thromboembolic events can underlie ischemic cerebral events and are associated with heart disease, valvular pathology, or carotid artery disease. Hypertension is a major risk factor for intraparenchymal hemorrhage and may lead to increased intracranial pressure, herniation, and death.

The greatest percentage of thrombi resulting in pulmonary embolism is thought to originate in the deep veins of the lower extremities. Deep-venous thrombosis can also occur in the pelvis or other locations. Fragments of blood clot may break off and embolize to the pulmonary arteries. An occlusion greater than 50 to 75% of the large pulmonary vessels results in a rise of the pulmonary artery pressure greater than 40 mmHg. This rise of pulmonary arterial pressure is accompanied by an increase in right ventricular diastolic, right atrial, and systemic venous pressures, with a decrease in cardiac output resulting in sudden death. Patients who have multiple small pulmonary emboli or in situ thrombus formation over time may present with increasing shortness of breath and right-sided heart failure. Because the lungs have dual circulation, infarctions are less common unless there is significant underlying natural disease with decreased cardiac function.

Various types of vasculitis or blood vessel inflammation can cause wall thickening, thrombosis, dissection, and rupture. Mesenteric thrombosis may be associated with polyarteritis nodosum and other autoimmune conditions.

Other Causes of Sudden Death

Rare undiagnosed brain tumors may present with sudden death. Infiltration or edema formation into the key respiratory/cardiac centers of the brain with possible herniation are two mechanisms. Early or late stage malignancies may sometimes metastasize to the heart and interfere with the conducting system, causing a fatal arrhythmia. Other causes of sudden death in patients with malignancies include cardiovascular events such as acute myocardial infarction, therapeutic complications (i.e., anaphylaxis), and metabolic derangements. Rare causes of sudden death in patients with tumors or malignancies include erosion of large vessels or visci with fatal hemorrhage. A colloid cyst of the third ventricle may lead to sudden death and is usually associated with premortem postural headaches. In certain positions, the cyst will act like a ball valve and suddenly block the flow of cerebral spinal fluid, resulting in acute obstructive hydrocephalus. One may be fine standing but develop symptoms when he or she lies down. This buildup of cerebral spinal fluid pressure can cause a fatal arrhythmia. Bacterial pneumonia with the combination of hypoxia and bacterial toxins and end products can cause sudden death.

Status asthmaticus and sudden asphyxic asthma are life-threatening forms of asthma. These cases are not unusual in a forensic setting. Status asthmaticus is defined as an acute attack of respiratory failure due to airway inflammation, edema, and mucous plugging. Sudden asphyxic asthma is due to brochospasm rather than airway inflammation. Viral infections and other causes have been implicated as precipitants of these potentially fatal complications. Grossly in both cases, the lungs may appear so much hyperaerated that at times rib indentations will show. Thick mucus plugs may obstruct the upper airways. Sudden death in asthmatic patients is thought to be secondary to fatal arrhythmia, occurring as a consequence of global hypoxia and right heart failure.

There is a condition known as sudden unexpected death in epilepsy (SUDEP). The mechanism is unclear but this phenomenon occurs in up to 18% of patients with epilepsy, presumably in those with subtherapeutic levels of anticonvulsants. Autonomic dysfunction has been proposed as a mechanism. Other mechanisms for death in patients with epilepsy include accidental/traumatic incidents such as drowning and choking that occur during a seizure. Hypoxia as a result of respiratory compromise can result in ischemic cardiac events. This may be part of the final mechanism of death in epileptic patients experiencing status epilepticus. Another interesting point to remember is that there is often very rapid rigor mortis formation in deaths directly following static epilepticus due to substantial adenosine triphosphate (ATP) depletion associated with prolonged muscle contractions from prolonged convulsions. Usually there are few pathologic findings that explain the sudden death in epileptic patients. Autopsy findings may include bite marks to the tongue with hemorrhage or a voided urinary bladder. There may be no finding at all. These are nonspecific findings and seizure activity may also occur prior to many other nonepilepsy-related deaths.

Fatal anaphylaxis can result from exposure to insect stings, foods, latex, drugs, chemicals, and exercise. This mast cell-mediated systemic reaction results in severe angioedema and bronchoconstriction of the upper respiratory tract along with hypotension resulting in respiratory and circulatory collapse. Death caused by anaphylaxis is primarily due to airway obstruction when laryngeal edema fills the rich lymphatic supply of the epiglottic folds. Increased mast cell tryptase levels in the patient's serum can be detected that peaks approximately 15 to 60 minutes after the onset of anaphylaxis and then declines with a half-life of about 2 hours.

The mortality for gastrointestinal bleeding (GI) in the case of ruptured esophageal varices most commonly encountered in patients with portal hypertension is high. Intra-aortic balloon pumps are lifesaving procedures but only if the patient presents in a timely fashion. Other causes of fatal upper gastrointestinal bleeding include stomach and duodenal ulcers; in this scenario the source is arterial as opposed to venous in esophageal varices. Fatal lower gastrointestinal bleeding can be seen in patients with angiodysplasia, diverticulitis, and carcinoma; however, this scenario is less common than upper GI bleeding.

Mostly complications of morbid obesity are thought to underlie the association with sudden death. Hypertension, left ventricular hypertrophy, and cardiomegaly are all independent risk factors for sudden death. Postural asphyxia may occur as a result of obesity. Morbid obesity is a reasonable cause of death by itself due to stress on the heart. An individual who is three times the expected body weight has roughly three times the vasculature with three times the blood volume to pump. In times of other stress, this can have devastating consequences on the heart, with death by arrhythmia.

Waterhouse–Friderichsen syndrome was first described as occurring in patients with meningococcemia and is characterized by severe bacteremia and bilateral adrenal hemorrhages. This combination results in overwhelming shock and, if untreated, sudden death can occur. Organisms other than *N. meningitis,* such as *E.Coli,* have been reported to produce this syndrome.

Multiorgan failure and death can be seen in sickle cell anemia patients with an acute crisis. Precipitants may include infection, dehydration, hypoxia, physical excretion, vaso-occlusion, or fat embolus following bone infarction. This acute hemolytic sickling crisis results in severe hypoxemia with end organ failure. Patients with sickle cell anemia have auto-infracted spleens and are much more susceptible to encapsulated organisms such as pneumococcal bacteria. Even patients with sickle cell trait may develop crisis in times of great physical exertion with dehydration, such as basic training in the army or boot camp.

Natural disease processes may weaken the body, making fatal traumatic injury more likely. Osteoporosis from aging, Cushing syndrome, steroid use, and other natural disease processes will make bones more fragile and allow fractures to occur more easily.



When examining photographic evidence it may be important to have knowledge of the type of camera, film, and lighting used when documenting different disease states. These four photos demonstrate different types of lighting causing variation in picture color. Figure (a) was taken in overcast sunlight, (b) with camera flash, (c) under fluorescent light, and (d) with a Tungsten filament regular light bulb. If your opinion is that a photographic image is not interpretable, it is perfectly acceptable to say that you cannot render an opinion based on this two-dimensional image.



Normal fresh heart.



Sections of a normal fresh heart showing right and left ventricle.



Normal fresh left lung (a) demonstrating two lobes. Right lungs (b) have three lobes.



Sections of normal right and left ventricle after formaldehyde fixation.



Normal lung fixed in formaldehyde.



Normal fresh kidneys.



Non-fixed fresh kidneys. Note the pale discoloration resulting from fatal blood loss prior to death due to a gunshot wound.



Normal kidney fixed in formaldehyde.



Normal fresh liver.



Normal fresh spleen.



Normal liver fixed in formaldehyde.



Normal spleen fixed in formaldehyde.



Normal fresh adrenal gland intact (a) and sectioned (b).



Normal fresh thyroid gland.



Normal adrenal gland section fixed in formaldehyde.



Normal thyroid fixed in formaldehyde.



Normal fresh testes.



Normal testes fixed in formaldehyde.



Normal fresh prostate.



Normal prostate fixed in formaldehyde.



Normal fresh pancreas.



Normal fresh esophagus.



Aorta with slight atherosclerosis. Note the fatty streaks on the intimal surface.



Normal fresh bladder.



Figure (a) demonstrates congestion of fresh brain. Note the slight pink color. Figures (b) and (c) demonstrate fresh brain in an individual who exsanguinated from a ruptured aortic aneurysm. Note the pale discoloration due to blood loss.



This figure depicts a decedent with an endotracheal tube in the right side of his mouth. It also demonstrates the "purple head sign," a common finding in victims of sudden death, particularly cardiac death. The explanation for this finding is not known in entirety but is attributed to uncontrolled terminal sympathetic nervous system discharges, which open free capillary sphincters and produce a gush of capillary blood.



Morbid obesity. This is a legitimate cause of death and can stand alone on a death certificate.



Petechiae associated with heart disease and resuscitation.



Low-power magnified view of small coronary arteries with thrombosis.



Epicardial vessel with complete occlusion by organizing thrombus. Note the adjacent epicardial hemorrhage.



Coronary artery with a ruptured atherosclerotic plaque and thrombus formation.



Marked coronary atherosclerosis in an epicardial vessel.



An acute myocardial infarction. Note the yellow discoloration due to necrosis. This infarction is approximately 3 to 6 days old. In Figure (b) and (c), there is a transmural acute myocardial infarction with rupture.



Acute myocardial infarction.



View of the thoracic cavity looking downward at the heart during autopsy (a) and (b). Note the purple discoloration of the pericardial sac due to underlying accumulation of blood. Note the two different examples with large blood clot encasing the heart after the pericardial sac was removed (c) and (d). This demonstrates a cardiac tamponade following an acute ruptured myocardial infarction.



Two examples of hearts demonstrating acute ruptured myocardial infarction. Note the adjacent hemorrhage and perforation site. This resulted in cardiac tamponade and sudden death.



This microscopic section of heart muscle reveals an acute myocardial infarction with hemorrhage, polymorphonuclear cell infiltrates, and myocardial necrosis.



This acute myocardial infarction demonstrates coagulative necrosis with contraction bands. There are also polymorphonuclear cell infiltrates.



This histopathologic section of myocardium reveals an old infarction with fibrosis.



This low-power view of heart muscle reveals patchy areas of fibrosis consisting of healed hypoperfusion infarctions secondary to a remote trauma with severe shock. Also note the perivascular fibrosis.



Early to moderate nephro-arteriolosclerosis.



Moderate to marked nephro-arteriolosclerosis.



Nephro-arteriolosclerosis associated with hypertensive cardiovascular disease. Note the cardiac hypertrophy and biventricular dilatation in this failing heart. There is also moderate atherosclerosis of the aorta. Note the markedly granular subcapsular kidney surfaces and cortical scarring also associated with this process.

Arteriovenous hemodialysis grafts for treatment of chronic renal failure due to hypertensive cardiovascular disease.





This microscopic image of myocardium reveals significant perivascular fibrosis and small vessel disease in a patient who had a long history of hypertensive cardiovascular disease and diabetes mellitus.



Normal cross sections of heart (a). Compare this image to the ones below. Figure (b) shows a markedly enlarged heart due to hypertensive cardiovascular disease. This heart is diffusely enlarged and shows cardiac hypertrophy. Figure (c) is a markedly hypertrophied heart with extreme concentric left ventricle hypertrophy. This individual had severe hypertension.







This is a microscopic section of kidney showing fibrosis, arteriolosclerosis, and nephrosclerosis due to hypertensive cardiovascular disease.



The right and left ventricles show marked dilatation. This individual died of a peripartum cardiomyopathy. A dilated cardiomyopathy or end stage hypertensive cardiovascular disease with cardiac failure will appear the same grossly.



The sections of these ventricles reveal marked right ventricle hypertrophy. This individual had end-stage primary pulmonary fibrosis with cor pulmonale and cardiac failure.



The intimal lining of an aorta with marked atherosclerosis in a decedent with a longstanding history of smoking, diabetes, high cholesterol, and high blood pressure.



Abdominal aortic atherosclerotic aneurysm shown in its typical location inferior to the renal arteries and above the iliac bifurcation.



An abdominal atherosclerotic aneurysm with a rupture at its anterior aspect and visible thrombosis.



This abdominal aortic aneurysm that has been opened to remove half of the vessel wall and show the underlying intimal surface with moderate atherosclerosis except for the region of the aneurysm, which has marked atherosclerosis and a large overlying thrombus.



This abdominal aortic aneurysm has been cross sectioned to show the partial obstruction of the aneurysm by organizing thrombosis. The lumen is demonstrated by fresh red blood clot at its surface and the thrombus is demonstrated by the light grey regions adjacent to the right and left wall.



Abdominal aortic aneurysm with vascular graft repair.



Thoracic aortic atherosclerotic aneurysm. This is not the typical location for such an aneurysm. Also note the aneurysm begins distal to the root of the aorta.



This demonstrates a decedent who had multiple atherosclerotic aneurysms including both iliac arteries.



Hemothorax from a ruptured thoracic atherosclerotic aneurysm.



Thoracic atherosclerotic aortic aneurysm adherent to lung with rupture into the lung parenchyma causing massive hemoptysis. Note that Figure (b) demonstrates the rupture site with adherent blood clot removed.



Intimal tear of the ascending aorta with dissection. Note blood tracking through the separated media.



Aortic dissection with exposed separated media with blood clot in a person with Marfan's syndrome.



An in situ aortic dissection. Note the hemorrhage extending from the root of the aorta down the paravertebral region shown by dark red hemorrhagic discoloration. This decedent had severe hypertensive cardiovascular disease.



Cross section of aorta revealing a double-barrel lumen. The superior aspect of this figure shows an opened aorta with the exposed lumen. Directly inferior to this is the separated media and adventitia with a second lumen that is partially thrombosed.



Microscopic view of an aortic dissection.



This endocardial surface shows large nonbacterial thrombotic endocarditis associated with a hypercoagulable state from metastatic adenocarcinoma. Special stains were negative for microorganisms.



This perforated mitral valve is secondary to acute bacterial endocarditis. This individual first went to the emergency room approximately a day and a half before with the complaint of fever and chest pain. He was sent home with antibiotics and later returned with severe pulmonary edema and died shortly after.



Close-up view of an acute infectious endocarditis with valve perforation. Gram stain revealed numerous gram positive organisms.



Acute infectious endocarditis with valve leaflet perforation.



Remote cardiac valve damage from rheumatic fever.



These figures are views of a remotely damaged tricuspid valve secondary to chronic intravenous drug abuse and past endocarditis. Note the fibrosis of the adjacent endocardium secondary to regurgitive turbulent blood flow. The decedent was known to have a longstanding cardiac murmur.



These figures show a markedly hypertrophic heart with concentric left ventricle hypertrophy and a congenital subaortic band causing marked aortic stenosis and sudden cardiac death at age 42 years. The decedent had decided years earlier not to have a valve replacement.



Bicuspid aortic valve. With advancing age and atherosclerosis, these valves may become markedly stenotic and increase one's risk for sudden cardiac death.



Markedly stenotic bicuspid aortic valve from an older individual with a longstanding history of atherosclerotic cardiovascular disease.



Severely stenotic and insufficient aortic valve associated with childhood rheumatic fever. Correction of aortic stenosis will decrease the risk of sudden cardiac death.



A fulminant pulmonary edema with foam extending from the mouth and nose due to congestive heart failure.



Note the frothy fluid from pulmonary edema extending into the laryngeal airway.



Pitting edema of the leg due to congestive heart failure.



Lung with marked congestion and edema. Note the diffuse purple discoloration.



Marked pink to red frothy fluid extending from the cut parenchyma of a lung due to fulminant pulmonary edema.



Cut section of a lung with pulmonary edema.



Microscopic view of lung with acute fulminant pulmonary edema.



These two figures demonstrate a coronary artery anomaly with acute angle takeoff and luminal narrowing in a 15-year-old who died suddenly during a basketball game. There was no history of blunt impacts to the chest during the game. There was no past history of syncopal episodes or chest discomfort.



A coronary artery anomaly with acute angle takeoff and luminal narrowing. This individual died a sudden cardiac death shortly after exertion.



This coronary anomaly reveals a bicuspid aortic valve with superior displacement of one of the coronary ostia. This child died of trauma sustained in a motor vehicle accident and this finding was incidental.



This low-power histopathologic view demonstrates "myocardial tunneling" where the left anterior descending coronary artery dipped deeply into the left ventricle wall.



Pulmonary thromboembolus in an obese woman who was on birth control pills and smoked cigarettes.



Incision of the lower leg with dissection of the gastrocnemius muscle demonstrating multiple deep venous thrombi in an individual who underwent organ donation with removal of bone and soft tissue from each leg. Note the plastic tubing left by the organ donor network.



Microscopic view of a pulmonary thromboembolus. Note the laminated alternating lighter fibrin bands referred to as the lines of Zahn.



These are different views of two hearts with the classical variant of hypertrophic cardiomyopathy. Note the large degree of asymmetric left ventricle hypertrophy.



Hypertrophic cardiomyopathy with myocyte fiber disarray and fibrosis.



Hypertrophic cardiomyopathy with myocyte fiber bundle disorganization.



Hypertrophic cardiomyopathy. Note the marked septal hypertrophy with asymmetry.



Note the waxy pink myocardial discoloration in this individual with amyloidosis.



This decedent's pericardial sac was full of several hundred cc's of yellow-pink fluid. The gradual buildup of this fluid over a long period was due to advanced secondary hemochromatosis.



Microscopic section of heart showing iron deposition from secondary hemachromatosis associated with blood transfusions for treatment of beta-thalassemia major.



Microscopic section of heart with Prussian blue staining of iron deposits in the heart of the same individual with secondary hemochromatosis.



These microscopic myocardial views demonstrate Chagas' disease. Note the extensive chronic inflammation.



Myocarditis secondary to toxoplasmosis in an individual with acquired immunodeficiency syndrome.



Eosinophilic myocarditis associated with a hypersensitivity drug reaction.



Microscopic view of myocardium in an individual who died of Pompe's disease. Note the many artifactual empty vacuoles following processing leading to glycogen loss.



This candidal myocarditis was found in an individual with acquired immunodeficiency syndrome.



This focal viral myocarditis demonstrates myocardial necrosis with inflammation made up predominately of lymphocytes.



Aspergillosis myocarditis from an immunocompromised individual who underwent a recent bone marrow transplant.



Macroscopic section of myocardium from an individual who died of cardiac sarcoidosis.



Sarcoidosis. Note the noncaseating granulomas consisting of chronic inflammation, epitheloid cells, lymphocytes, and giant cells found throughout the body. These views demonstrate examples from the heart and lungs.



These figures demonstrate acute and chronic bronchial asthma. Note the lungs within the thoracic cavity are hyperaerated and expand to overlie the pericardial sac. Upon removal of the lung, they appear markedly hyperaerated. If these lungs were placed in a water bath they would float almost entirely on the surface. Cut section through the parenchyma reveals thick copious mucoid secretions within the bronchial distribution. Microscopic section reveals increased amounts of goblet cells and smooth muscle. There is a large mucous plug within the airway with numerous eosinophils. The parenchyma also has numerous inflammatory cells, predominantly eosinophils.



Chronic obstructive pulmonary disease (COPD) with hyperaeration and emphysematous change.



Pleural adhesions most likely due to past bouts of pneumonia.



Bolus emphysema in a person with COPD. These bullae may occasionally rupture and cause a pneumothorax.



Hypertensive intracerebral hemorrhage. Mostly caused by rupture of a small intraparenchymal vessel.



Old healed stroke. Note the indentation of the cerebral hemisphere.



Intracerebral hemorrhage due to ruptured A-V malformation.



Astrocytoma causing significant compression of the surrounding structures.



Bite marks to tongue with hemorrhage from an individual who died of epilepsy. This was the only finding at autopsy.



Anterior cranial fossa meningioma.



Pick's disease. Note the asymmetric atrophy of the frontal, temporal, and parietal lobes. This form of chronic dementia occurs far less frequently than Alzheimer's disease.



Two separate cases of pituitary adenoma. Figure (a) depicts a large erosion into the sela turcica and (b) demonstrates a large adenoma viewed on a cross section of a cut formaldehyde-fixed brain. These adenomas may vary largely in size.



Colloid cyst of the third ventricle. This decedent had a history of severe headache with postural changes. This may be associated with sudden cardiac death following a buildup of cerebrospinal fluid pressures associated with central nervous system cardiac center disruption and fatal arrhythmia.



Sudden death associated with ruptured saccular cerebral artery aneurysm with subarachnoid hemorrhage. These are examples of giant berry aneurysms, which are greater than 2.5 centimeters in greatest dimension. Small saccular aneurysms may rupture the same way. The jolt of increased pressure from arterial blood through the subarachnoid space at the base of the brain may disrupt the cardiac centers, causing fatal arrthymia.



Decubital ulceration or pressure sore. This is often associated with poor patient care.



Healing ankle ulceration associated with peripheral vascular disease.



Dry gangrene associated with peripheral vascular disease due to long-term diabetes mellitus.



Ischemic bowel due to small intestine volvulus with vascular compromise. The arrow indicates purulent exudate at the serosal surface.



This decedent had a longstanding history of difficulty swallowing. She was seen to gesture as though she could not breathe and then collapsed. Autopsy revealed a large benign esophageal polyp that obstructed the upper airway. Note the ulceration at the tip of the polyp from constant rubbing. During this last episode she was unable to clear the obstruction.



Cecal volvulus. Note the red discoloration of the serosal surface. Figure (a) demonstrates cecal enlargement due to obstruction, (b) demonstrates the cecal volvulus with rotation and obstruction, and (c) demonstrates this region untwisted.



This individual never sought medical attention for her breast carcinoma and died at home.


cm 1 2 3 4 5 6 7 8
MEDICAL EXAMINER
NASSAU COUNTY
CASE #
Inches 1 2 3

Bronchogenic carcinoma with erosion through the airway.



This individual never sought medical attention for his gastric cancer and died at home.



Metastatic bronchogenic carcinoma of the lung. Note the metastatic nodule in the heart muscle causing fatal arrhythmia.


CENTIMETERS
1 2 3 4

Primary rhabdomyosarcoma of the heart.



Multiple healed granulomas most likely from a past fungal infection.



Cryptococcal meningitis in an individual with AIDS caused by intravenous drug use.



Neurofibromatosis type 1. Note the numerous neurofibromas at the surface of the body. These tumors may be found throughout the body. Death may occur by tumor growth leading to damage of adjacent structures such as the gastrointestinal track with obstruction, central nervous system with compression, renal artery with hypertension, etc.









This decedent had Duchenne's muscular dystrophy and was bedridden for many years. He developed severe osteoporosis. While being removed from bed one day by a new caregiver, he sustained bilateral femur fractures and died shortly after.





Cushing's syndrome due to hypercortisolism. Note the "moon face," "truncal obesity" and purple striates at the lower abdomen. This syndrome is also associated with glucose intolerance. From a forensic standpoint and interpreting injuries, it is important to know this is associated with osteoporosis, increased bruisability, and poor healing.



Goiter with hyperthyroidism may lead to thyrotoxicosis and sudden cardiac death due to tachyarrthymia.



This portion of gastric mucosa reveals multiple small areas of hemorrhage in an individual with hypothermia. "Leopard skinning" of the gastric mucosa and acute pancreatitis are often seen with cases of marked hypothermia followed by short-term survival.



This individual had his fingers and toes amputated years before following extensive hypothermic injury with frostbite.



Jaundice due to hemolysis associated with sickle cell crisis.



Sickle cell anemia. Peripheral blood smear showing sickled cells.



Sickle cell crisis. Note the dark red-black sludge within the gall bladder from hemolysis.



Autoinfarction of spleens from adult individuals with sickle cell anemia. These spleens are typically shrunken and firm. Note the histopathology sections with marked congestion fibrosis and Gamna-Gandy bodies from iron pigments with calcium salts.



Sickle cell anemia with crisis. Kidney with papillary necrosis (a) and congestion (b) and (c).



Sickle cell anemia with crisis. Lung with marked congestion and pulmonary edema.



Adult polycystic kidney disease. This autosomal dominant disorder is another significant cause of hypertension. These kidneys weighed over 3000 grams each. There is also an association with cysts in other organs and intracranial berry aneurysms.



Simple benign cyst.



Chronic pyelonephritis with “stag horn calculi” associated with urea splitting bacterial infection such as proteus or staphylococci causing magnesium ammonium phosphate salt precipitation. It is also important to know that acute obstructive urolithiasis with urosepsis can be rapidly fatal.



This is a postpartum death involving a 30-year-old nurse. This woman was known to be colonized by group A beta-hemolytic streptococcus (strepococcus pyogenes). Approximately 8 hours following an uneventful delivery, she began to complain of back and pelvic pain. Within 4 hours she was in full-blown shock and was refractory to resuscitative measures. Death was pronounced approximately 14 hours following her delivery. Figure (a) depicts the gravid uterus and confluent brown-black discoloration of the left adnexa, which proved microscopically to show areas of necrosis with numerous clusters of bacterial cocci and scant neutrophilic infiltrates. Postmortem cultures of multiple organs, including lungs, liver, spleen, uterus, and peritoneal fluid, all grew group A beta-hemolytic streptococcus betahemolitic streptococcus. This "toxic shock like" death due to group A streptococcus has given rise to the term "flesh-eating bacteria."

Therapeutic Interventions, Complications, and Accidents

2

MICHAEL J. CAPLAN AND CHARLES A. CATANESE

The evaluation of deaths related to complications of diagnostic and therapeutic procedures has traditionally been a problematic area for forensic pathologists and death investigators. The reasons for this are multiple: (1) these deaths often blur the boundaries dividing medicolegal and hospital death investigation; (2) many forensic pathologists do not feel comfortable approaching the often complex and highly technical issues present today in modern medicine; and (3) at least some forensic pathologists believe that these types of death belong more appropriately within the domain of the hospital autopsy. Despite this ongoing controversy, most forensic pathologists and death investigators will, at some point during their careers, be forced to handle these types of deaths.

If a patient dies either during or sometime following a diagnostic and therapeutic procedure, the first question in the diagnostic algorithm or decision tree becomes: Was the death in any way related to the procedure or was the procedure simply an artifact, with the death attributable to some underlying natural disease process or injury? For example, if a 65-year-old man who has stubbornly refused surgical intervention of a known 8-cm-diameter abdominal aortic aneurysm suddenly collapses and manages to make it to the operating room but dies before repair can be attempted, the "intraoperative death" is simply an artifact of modern medical resuscitation and transport technologies. In such a case, the medical intervention or procedure played no part in the death, and the cause of death would be worded as "ruptured abdominal aortic aneurysm due to atherosclerotic cardiovascular disease, manner: natural." On the other hand, if an otherwise healthy individual underwent an elective procedure, for example, a bunionectomy, and died on the operating table, to ascribe the death to "hallux valgus" would be as ridiculous as it was erroneous. It is for cases like this that the concept of therapeutic complication merits consideration for a place in manner-of-death certification.

Once it is determined that the death was related somehow to the procedure, the next question in the algorithm becomes: Was the death a result of a known or predictable (albeit rare or unusual) complication of a properly performed diagnostic procedure or appropriately administered therapy, or did it ensue from a procedural error? When the former scenario exists, the term *therapeutic complication* is preferred, because that is a neutral designation as opposed to the term "therapeutic misadventure," which is inflammatory and prejudicial. When the latter situation is present, the manner of death is most accurately designated *accident.* Many examples of legitimate therapeutic complications exist. In the case of a 64-year-old man who sustained a non-ST (non-Q wave) segment elevation myocardial infarct, and who was treated with the antiplatelet drug eptifibatide (Integrilin), a platelet glycoprotein IIb-IIIa antagonist, he suffered intractable pulmonary hemorrhage and ultimately succumbed to respiratory failure. Pulmonary hemorrhage has been a recently reported complication of eptifibatide therapy. No error was committed in this case; rather, the decedent experienced an unusual yet known (documented) complication of appropriate therapy for his non-ST elevation MI. Therefore, the cause of death would be worded as: "Complications of pulmonary hemorrhage following eptifibatide (Integrilin) treatment for non-ST (non-Q wave) segment elevation myocardial infarct (due to atherosclerotic heart disease)" and the manner, therapeutic complication. On the other hand, if a middle-aged woman underwent a surveillance colonoscopy and presented days later with peritoneal signs and was found to have *E. coli* bacteremia and sepsis due to peritonitis resulting from inadvertent perforation of the colon during the procedure, the death certificate would read: "*E. coli* sepsis due to peritonitis due to colonic perforation complicating surveillance colonoscopy." However, because this complication is not an accepted sequela of an appropriately performed diagnostic or therapeutic procedure, but rather, an unintentional error, the manner of death in this case is most accurately deemed accident. Admittedly, there are cases that fall within the murky zone between natural and therapeutic complication and between therapeutic complication and accident. In such cases, all that one can do is exercise one's best objective clinical judgment. It is important to recognize and remember that death certificates are not immutable documents that are "written in stone"; rather, they can be amended should more accurate information regarding the circumstances of death become available at a later time.

While the concept of therapeutic complication is an invaluable tool in the assessment of these types of deaths, the practical applicability of the term to the death certificate has enjoyed less success. Only two known jurisdictions—Cuyahoga County, Ohio, and New York City—include "therapeutic complication" as a choice in the manner of death on the death certificate. Therefore, when a death fits the criteria for therapeutic complication as the manner, but the particular jurisdiction does not include it on the death certificate, then the manner defaults to natural. One other option is to list "therapeutic complication" in parentheses after "natural," but this probably is not common practice. Thus, for the indefinite future, forensic pathologists will be resigned to using the term as a conceptual tool in the evaluation of these most challenging deaths.



These figures show one of many possible artifacts associated with organ donation that may be mistaken for injuries. Note (a) the hemorrhagic discoloration around each eye (periorbital) and (c) the plastic insert in the opened eye following tissue removal. Medical record review and clinician interview revealed that these periorbital hemorrhages were not present at the time of admission.



Tissue procurement of superficial skin.



Postmortem tissue procurement and full thickness skin.



Sutured incisions following long bone, soft tissue, and saphenous veins removal for postmortem tissue procurement.



Figures (a) and (b) show ill-defined, parallel, vertically oriented gray-brown marks on the forehead. These are artifacts of transport. The child's head was stabilized with a strap while flown by helicopter from an outside hospital to a tertiary pediatric center. Figure (c) shows reflected scalp and well-defined sagittal and lamboidal sutures without features of subgaleal contusions or skull fractures.



This individual was ejected from a car during a collision. She was taken to the hospital in an unconscious state and remained so until her death. There was initial speculation that she was struck by another motor vehicle due to the "tire-like" patterns on her legs (a–c). Further investigation revealed these injuries were not present at the time of arrival to the emergency department. She survived in the hospital for approximately 2 days. There was a pelvic fracture with blood seeping into the legs, extensive generalized edema, and disseminated intravascular coagulation (b). Pressure boots were placed to decrease the risk of deep venous thrombosis (d). This pattern of ecchymosis was caused by the pressure boots in conjunction with the complications of the injuries.



Figures (a), (b), and (c) show electrical burns caused by defibrillation with damaged cardioversion paddles during attempted resuscitation.



These figures show perimortem injuries to the anterior chest, axillary regions, and the anterior aspects of the upper arms associated with incorrect placement of a rib splitter during a thoracotomy.







These figures demonstrate the posterior pharyngeal/esophageal cut surface with intramural hemorrhage. This is an artifact encountered frequently during resuscitative measures. The rich esophageal venous plexus tends to be a very hemorrhagic area following intubation.



This demonstrates an esophageal intubation with the tip of the endotracheal tube protruding from the esophageal lumen. The epiglottis can be seen slightly behind the endotracheal tube, confirming an esophageal intubation.



This autopsy involved an infant who succumbed to sudden infant death syndrome (SIDS). The close-up photograph depicts an esophageal intubation, with the endotracheal tube clearly within the esophageal lumen and the concentric tracheal rings visible slightly anterior to and (anatomically) to the right of the tube. Esophageal intubation is not an uncommon finding associated with resuscitation and usually plays no substantial contributory role in the death; however, it should always be documented as part of a complete autopsy and may, in some situations, be a quality control measure for Emergency Medical Services (EMS) personnel and paramedics. Esophageal intubations during an elective procedure, on the other hand, are very important and potentially causal or contributory to the death.



This endotracheal tube was inserted through the trachea and paratracheal soft tissues into the thoracic cavity during resuscitation.



A tracheostomy tube was inserted through the posterior aspect of the trachea (a) into the esophagus (b) (traumatic tracheoesophageal fistula). Note the perforations on the posterior surface of the trachea (a) and the anterior aspect of the esophagus (b).



This is a view of the chest wall of an 18-month-old toddler with a history of tracheomalacia and subaortic stenosis who required a tracheostomy. During a bout of crying, the tracheostomy tube became dislodged, and after nurses attempted to reposition it, the baby rapidly developed subcutaneous emphysema, followed by bilateral tension pneumothoraces. Autopsy demonstrated marked subcutaneous emphysema, including periorbital swelling. The tube had been removed before the autopsy, precluding assessment of its placement. This particular view demonstrates air bubbles within the subcutaneous fat. It is important that all tubes remain in the body for objective postmortem (autopsy) evaluation of their placement.



Subcutaneous emphysema. Anterior chest with air bubbles throughout the mediastinal soft tissues. This may be commonly observed with vigorous resuscitation or trauma. Palpation of these regions often reveals crepitus.



One must be careful while examining injuries altered by therapeutic intervention. This picture demonstrates a catheter placed into an injured blood vessel through a stab wound.



This demonstrates a stab wound adjacent to a sutured chest tube incision. This may make injury interpretation more challenging.



Healing infected incision. This individual died of septic complications of his initial trauma. Had it not been for this trauma, the infection that took his life would not have occurred. The manner of death in this case was ruled accidental.



This demonstrates a stab wound that the clinicians converted along one side (edge) into a thoracotomy incision. If at all possible, this should never be done, because it makes injury interpretation much more difficult.



This is a "cutdown site" used for vascular access by a hospital emergency department (ED) physician, created by a transverse incision within the antecubital fossa This decedent had also sustained stab and incised wounds in other parts of the body. Again, this illustrates the importance of having a complete medical record and discussions with the treating ED physicians or trauma surgeons to properly differentiate between therapeutic interventions and injuries sustained before such therapeutic interventions.



This chest tube was inserted through a previously existing perforation. Notice, however, that along the left margin of this perforation (from the 7–11 o'clock positions), there is a distinct abrasion. Further investigation established that the chest tube was inserted through a previously sustained entrance gunshot wound, thus explaining the abraded margin of this perforation.



Arteriovenous hemodialysis grafts with healing needle puncture marks.



These individuals exsanguinated in their residences following ruptures of their infected arteriovenous dialysis grafts.



This woman underwent (a) Cesarean section (c) for an otherwise unremarkable term pregnancy hours before going into hemorrhagic shock while in the recovery room. Autopsy disclosed a large hemoperitoneum with clotted blood extending from a bleeding abdominal wall vein (a) and (b).



These figures show an individual who died of hemorrhagic complications following (a) a thyroidectomy. A large accumulation of clotted blood collapsed his airway while he was sedated at home. He was found unresponsive lying on a sofa. Note the hemmorhage and larger blood clot in the anterior neck and chest.



These figures show a patient who was admitted in cardiac arrest following an acute asthma attack. Chest tube placement was inserted through the lung parenchyma during resuscitation. Approximately 150 mL of liquid blood were recovered from the left hemithorax, indicating that this injury was perimortem and iatrogenic.







This individual underwent placement of a nasogastric tube that perforated the esophagus and entered the right thoracic cavity (hemithorax). The injury went unnoticed for many hours. The decedent was fed through the nasogastric tube, which is demonstrated by the accumulation of yellow fluid within the thoracic cavity. Autopsy revealed a fibrinous pleuritis and an early pneumonia.



Percutaneous endoscopic gastrostomy feeding tube.



Panoramic view illustrating the anterior gastric wall, with a probe through the previous PEG site, also demarcated by an arrow, and the other arrow demonstrating greater omentum with fibrinous exudate. Similarly appearing exudate can also be seen on the anterior surface of the gastric body and fundus.



This is a close-up anterior view of the stomach, demonstrating the previous PEG site through the anterior gastric wall, as well fibrinous exudate on the surface of the greater omentum, with both features demarcated by arrows.



This depicts the parietal peritoneum with a gray, shaggy, fibrinous exudate.

This case involved an elderly woman with a history of dementia who could no longer live independently and was made a ward of the state. She was hospitalized for long-term intermediate care. She had undergone percutaneous endoscopic gastrostomy (PEG) tube insertion due to insufficient oral intake (a). She underwent a tube replacement for leakage. Later that evening, she experienced acute onset of abdominal pain that was complicated by increasing abdominal distension, green discoloration of the abdominal wall site, and purulent drainage from the tube site. The remainder of her course was characterized by respiratory distress, aspiration of gastric contents, hypotension, and tachypnea, culminating in systemic inflammatory response syndrome with lactic acidosis, multisystem organ failure, and hemodynamic instability, refractory to aggressive resuscitative measures. Autopsy revealed intraperitoneal placement of the gastrostomy tube with intraperitoneal administration of enteral feedings and a collection of approximately 700 mL of turbid peritoneal fluid with extensive fibrinous adhesions. Microscopic examination confirmed an exuberant fibrinous exudate with scattered clusters of bacterial cocci and yeast, as well as birefringent material. The cause of death was certified as complications of peritonitis following intraperitoneal placement of gastrostomy tube during tube change, following percutaneous endoscopic gastrostomy insertion for insufficient oral intake related to atherosclerotic cerebral vascular disease and dementia. The manner of death was certified as accident.



This was a middle-aged woman with primary biliary cirrhosis who underwent a transjugular intrahepatic portosystemic shunt (TIPS) for decompression of high portal venous pressure (portal hypertension). The picture (a) depicts a large hemoperitoneum, with greater omentum, stomach, and intestines floating on top of a pool of blood. There was advanced end-stage cirrhosis (b), with confluent scar enveloping and entrapping regenerative parenchymal nodules. Liver diseases such as this are associated with an increased risk of hemorrhagic complications due to coagulopathy and portal hypertension. This fatal hemorrhage resulted from laceration of a portal vein branch occurring during stent placement (c).



Note the probe inserted through the perforation site, which is also demonstrated with the arrow.



This image demonstrates the sutured cannulation site as well as one of the bypass grafts.



Close-up of perforation site demonstrated by probe and arrow.

This case involved a patient who underwent six-vessel coronary artery bypass grafting that was followed by intractable postoperative hemorrhage. The pericardial and left pleural drainage exceeded 1 liter within the first postoperative hour. The patient became hypotensive, requiring emergent re-exploration that was refractory to resuscitative efforts. Autopsy revealed an approximately 3-mm perforation of the ascending aorta, immediately above and distal to a sutured aortic cardiopulmonary bypass cannulation site, with residual bilateral hemothoraces. (left: 1,100 mL and right: 450 mL). The cause of death was certified as intractable hemorrhage with perforation at the aortic cannulation site complicating coronary artery bypass grafting for atherosclerotic coronary artery disease. Hypertensive heart disease was listed as a contributory cause (heart weight: 690 grams and body weight: 120 kgs). The manner of death was certified as therapeutic complication.



Right hemothorax (a) due to perforation of right internal jugular vein complicating catheter insertion. Note the probe (b) and (c) demonstrating the perforation through the right internal jugular vein and the hemorrhage within the anterior overlying soft tissues.



This case involved complications of a transbronchial biopsy in an individual who was HIV-positive and was slightly thrombocytopenic (platelet count: approximately 75,000/uL). The procedure was followed by extensive pulmonary hemorrhage, which culminated in respiratory compromise and death. Figure (a) demonstrates a Swan-Ganz catheter within the pulmonary arterial system. Figures (b) and (c) is a close-up view with a probe through a perforation of one of the large branches of the right main pulmonary artery with the arrow head demarcating the tip of the probe.



Heart with labels illustrating the aorta (AO), obtuse marginal graft (OMG), and left atrial appendage (LAA).



Close-up view of grafts.



This image demonstrates the relationship of obtuse marginal graft and native obtuse marginal vessel, as well as a stent protruding through the lacerated native obtuse marginal artery.



Close-up view of the junction between the obtuse marginal graft and the native obtuse marginal artery demonstrating the irregularity in the arterial wall.



Posterior view of heart demonstrating confluent epicardial hemorrhage associated with this procedure.

These pictures demonstrate a complication of coronary artery bypass grafting. In this case, a stent perforated the native obtuse marginal branch of the left circumflex artery immediately distal to the anastomosis between the graft and native vessel.



This depicts the lower lobe of the left lung with congestion and pneumonia. Note at the inferolateral aspect of the left lower lobe is a fragment of gauze that was inadvertently left behind during another operation months earlier. The gauze is adherent to the surface with overlying adhesions and adjacent purulent exudate.



This individual was in a motor vehicle accident and sustained a skull fracture involving the cribriform plate. A nasogastric tube was inserted that inadvertently penetrated the cranium. The tube was placed on intermittent suction. Aspirated brain matter is visible at the end of the tube.



This demonstrates a large gray-tan thrombus encasing a pacemaker lead extending from the heart.



In busy trauma centers, the body is sometimes received with multiple instruments used for resuscitative efforts. This photograph was taken after the body bag was opened at the morgue. It is always important to be careful of sharps that have been inadvertently left behind.







This Vietnamese woman died of Takayasu arteritis that was complicated by a ruptured aortic aneurysm. She was treated at home by her grandmother with Southeast Asian folklore remedies, including coining, which involves rubbing of hot oils and medicine onto skin (d). Note the unusual location of the coin marks at her neck (a) and (b). At first this was mistaken for manual strangulation. There were no internal neck injuries and no scleral or conjunctival hemorrhages (c).

Substance Abuse and Poisoning

3

CHARLES A. CATANESE AND LAURA M. LABAY

Introduction

The term substance abuse is most simply defined as the excessive use of one or numerous drugs. In general, most people typically have some level of access to several types of drugs, including legitimately prescribed medications, and on average, will benefit from their appropriate use. However, the term substance abuse can be applied to a variety of situations or circumstances. For example, one person may intentionally be abusing a multitude of substances including illicit drugs, prescribed medications, and over-the-counter remedies (i.e., supplements, herbals, diet aids, etc.). This is in direct contrast to another individual who may be taking only a single medication, but deliberately using it in a manner that is not consistent with normal therapeutic use. It stands to reason that when individuals begin to abuse one or more substances, and use them in an uncontrolled manner without the appropriate oversight, that they place themselves in a potentially harmful or lethal situation.

In a forensic or medicolegal setting it often becomes a matter of necessity to interpret drug findings and render an opinion regarding the toxicological, physiological, and pathological impact the drugs may have had upon an individual. To this end, it is important to evaluate and consider a host of factors. These factors are not always straightforward or quantifiable, but nevertheless include the drug's inherent physical and chemical properties, the dosage of the drug used, the frequency of the drug intake, the route of drug administration, the concentration of drug and drug metabolite found, the person's tolerance level to the drug and any medical conditions or disease states the person may have experienced.

It is important to recognize that for a particular drug to ultimately produce a toxic or lethal effect, it must be present in an individual at a sufficient concentration for a sufficient length of time. However, while references and other texts are available that help to classify drug concentrations as "therapeutic," "toxic," or "lethal," interpretation is often not so simple. For example, postmortem methadone concentrations are often challenging to interpret because the range of blood concentrations detected in people enrolled in narcotic maintenance programs may overlap the blood concentrations found in overdose or lethal situations.

Also, some drugs, depending on their physical and chemical properties and their concentrations in the body, will exert their most toxic or lethal effects in an acute manner, while others will take a longer period of time to act. In general, deaths associated with substance abuse may be related to acute or chronic complications. *Acute substance abuse* indicates that the death was related to direct toxic effects of the drug shortly after administration. In a *delayed overdose,* the drug produces damage to the body over hours or days following acute intoxication, with complications that may include coma, sepsis, brain swelling, and herniation. This process may evolve over days with the drug(s) metabolized from the body. The underlying process that set off this sequence of events is the acute intoxication.

Depending on the type of drug and its half-life there may be no or minimal amounts of drug left in the blood or other tissues at the time of death. However, the possibility exists that the drug or its metabolite(s) could still be detected and identified in the urine. In these circumstances, it is important to take into account that urine is really a pooled specimen collected in the bladder over a period of time and that a quantitative result represents only the average drug–urine concentration over the period of time that the urine was produced. Therefore, this type of specimen does not accurately reflect the blood–drug concentration at any single point in time. Rather, a positive finding of a drug or drug metabolite in urine indicates prior exposure only to that particular drug and in this regard it is relevant to consider other information (e.g., case history, medical records, anatomical findings, etc.) as well.

If a decedent suffered trauma while intoxicated and developed an *epidural* or *subdural hemorrhage*, you would expect to find the drug present in these samples even after many days. *Chronic sequela* associated with substance abuse include complications of infections such as HIV disease, hepatitis, hepatic cirrhosis, and endocarditis. Injection of ground-up oral medications may lead to pulmonary failure, with multiple foreign body granulomas and fibrosis demonstrated on histopathologic section. There are many other complications, including Wernicke's-Korsakoff's encephalopathy, alcoholic cardiomyopathy, and hardening of the arteries due to cocaine use.

Intravenous drug abuse may present with many different features. If the drugs are injected acutely in the same vein during binges, they appear as multiple fresh needle marks in a row. These are called "track marks" because they resemble a pattern of railroad ties being laid down one after another. It may be possible to detect the parent drug by excising the immediate area surrounding the injection site and submitting this section for toxicological analysis. If several injection sites are observed and a decision is made to submit more than one for testing, make certain to package the specimens in separate containers, identify the sites from which each was taken, and note their age and appearance. Alternatively, the syringe or other drug paraphernalia such as vials, pipes, or spoons, if available, can also be submitted for analysis. This is a good option if, for whatever reason, limited biological specimens exist. Once the nonbiological contents of the items are identified, directed toxicological analysis on the biological specimens can then proceed. If this is done, it is important that the items be packaged in individual containers, away from biological specimens, so that contamination does not occur.

Injecting drugs into blood vessels can lead to the introduction of many types of infections. Sharing of needles may cause transmission of the hepatitis virus or the human immunodeficiency virus. Various types of bacteria can also be introduced during injection, leading to vasculitis, cellulitis, pneumonia, and endocarditis. Acute intravenous fatalities, such as those caused when individuals inject themselves, are usually classified as *accident*. If one can demonstrate the drug was given to the individual in order to purposefully cause his or her death, the manner would be classified as *homicide*. Also, if another individual injects the drug into the decedent's arm the manner of death should be homicide.

As the vein is chronically abused, it will scar and develop a chronic track mark. Chronic track marks appear as linear scars that traverse the path of underlying veins. Histological sections from these regions often show polarizable debris from impurities found in past-injected drugs. If a chronic intravenous drug abuser consistently rotates the injection sites from one vein to another chronic track marks will not develop.

Skin-popping refers to drugs, such as heroin, injected into the subcutaneous tissues. This usually indicates a long history of drug abuse with destruction of the previously accessible peripheral veins. This may appear as fresh needle marks, usually at the surface of the thighs, or in other places without an underlying vein. These sites often get infected and lead to cellulitis, abscess formation, and scarring.

Another route of drug administration includes *inhalation*. Inhalation (i.e., snorting) of drugs may lead to mucosal reddening from direct irritation. Crack pipes may become very hot during use and burn the drug abuser's mouth and lips. Sometimes histopathology sections of the lungs reveal numerous pigment-laden macrophages from constant inhalation of smoke and debris from inhaled burning drugs such as crack. *Chronic snorting* of drugs may lead to a perforated nasal septum.

Keep in mind, it is not only the illicit drugs such as cocaine or heroin that can be inhaled; an individual may choose to *crush* and *"snort" a tablet or pill* as well**.** In some instances, residue may be observed in the nasal or oral cavity, and these areas can be swabbed and the parent drug identified though analytical testing. Individuals may also choose to inhale or "huff" commercial products such as gases, fuels, aerosols, solvents, or propellants as a means of abuse. This may be accomplished by breathing in the fumes from a rag that has been soaked in the material or by placing a bag containing the fumes over the nose and mouth. In some cases, the inhalation may take place directly from the item (i.e., aerosol can, glue bottle), as well. Users have died from hypoxia, pneumonia, cardiac failure, and aspiration of vomit. If the latter situation is relevant to the case, it is important to inform the toxicology lab of this, as most routine toxicology screens do not include these substances in the scope of their analysis. For these cases, lung tissue or tracheal air, in addition to the routine biological samples, can be collected as well.

Transdermal drug delivery systems introduce medications into the general circulation through a slow diffusion process, and may be considered a desirable alternative to taking oral medications or using substances that require repeated injection. In addition, the transdermal systems, perhaps most importantly, help to minimize the extreme blood spikes and trough levels that may be experienced with orally administered medications. Instead, blood–drug concentrations are maintained at more consistent concentrations.

Examples of commonly encountered medications delivered through transdermal systems include nicotine, hormones (i.e., contraceptives) and the potent narcotic analgesic fentanyl. However, similar to any medication, these patch-style systems may be subject to abuse. For instance, a person may make the decision to apply a multiple number of patches to the body, or through manual or chemical means remove the drug from the drug reservoir or from the adhesive matrix. It is also not uncommon for a person to chew or even swallow them. In these cases, remnants of patches may be observed in the oral cavity or the gastric contents. Other signs of this type of abuse would be if a person presented with patches applied in a manner not consistent with normal therapeutic use. For these cases, document the number of patches found on the body, their locations, any writing or markings on the patches and any other descriptive features. Make an attempt to ascertain if all the patches represent a single acute application or if some of the patches may be from remote use.

In these types of death situations where patch use is known or suspected (i.e., old adhesive markings are noted on the body) it is important to make certain that specimens are not collected in proximity to a vein or artery that is in the immediate vicinity of a patch or patch marking. As a specific example, following the death of an individual wearing a fentanyl patch, some drug may still be present in the depot beneath the patch. If a blood specimen is collected from an area immediately beneath or near the location of the patch, the concentration of fentanyl may not accurately reflect the circulating concentration at or around the time of death.

Similar to the patch, suppositories represent another type of drug delivery system. Suppositories contain medicated material for insertion into a bodily passage or cavity such as the rectum. Once the suppository, typically a solid substance, is inserted, it will begin to dissolve over time and subsequently will deliver the medication into the body. Substance abuse using this route of administration is relatively rare.

Substance Abuse

Acute and Chronic Alcoholism

Death occurring from acute alcoholism is usually classified as *natural*, although this may not always be the case. A young adult at a party trying to impress friends may attempt to guzzle a liter of whisky. This is more than enough alcohol at one time to kill most adults. In this case, the manner of death would be accident. Sometimes depressed people with an acute triggering event, tell their family that they are going to “drink themselves to death.” After several days of drinking large quantities of alcohol, they die. If you can establish the intent to do harm, the manner of death would be *suicide*. If someone at a party drinks alcohol from a funnel and a hose, by pouring the alcohol themselves, and then dies, the manner of death would be accident. If someone holds the hose and pours the alcohol for them, the manner of death should be homicide.

The deaths of individuals with a history of chronic alcoholism, including varying degrees of liver disease, intoxications, and withdrawal, are mostly certified as natural. Chronic alcoholics who stop drinking abruptly may get the “shakes” and eventually experience seizures leading to death. Withdrawal of many other drugs without other underlying natural disease will not typically cause death.

It is very difficult to give an opinion about individuals’ state of mind or behavior while they were drinking or using any drug, for that matter. One has no way to know their true thought processes unless their behavior was witnessed or somehow clearly documented. Chronic alcoholics, with a high degree of tolerance, may be able to achieve a high blood alcohol level and not show visible signs or symptoms consistent with intoxication. Some alcoholics become aggressive, loud, and agitated while others become subdued and complacent.

It is important to obtain blood samples with care in cases where there is suspected alcohol use, and trauma played a role in the person’s death. If one obtains a blood sample only from the pericardial sac or chest cavity, where other visceral lacerations may exist, contamination with gastric contents or other bodily fluids is a likely possibility. In turn, the measured blood alcohol level may be markedly increased as compared with the actual circulating blood concentration at and around the time of death.

As a more specific example relating to alcohol, when death is a consequence of multiple traumatic injuries there is the possibility that significant damage to the internal organs occurred. These organs include, but are not necessarily limited to, the stomach, small intestine, and liver. If those organs, now damaged, contained unabsorbed alcohol, a blood specimen collected from the chest area may readily become contaminated. As a result, the concentration of alcohol determined may not accurately reflect the circulating concentration at and around the time of the fatal event. Instead, ideally, for postmortem alcohol analysis and to mitigate some of these issues, an alternative specimen type should be harvested. These specimen types would include a vitreous specimen, a urine specimen, or blood collected from a peripheral site such as the femoral vein. This is because, in those cases where the heart blood may have become contaminated due to events such as trauma, the alternative specimen can be used to help provide an interpretable alcohol concentration.

Alternative specimens, such as vitreous fluid, are vital to collect, especially when alcohol is suspected or involved. It is important to recognize that alcohol may form postmortem, and analytical testing cannot make the distinction between this type of alcohol and alcohol that was present prior to death. Indeed, an alcohol finding may represent a combination of these two circumstances. To prevent or minimize postmortem formation once blood is collected, it should be placed into an appropriate type of specimen collection container, one that contains preservatives that help to inhibit microbial growth. If the postmortem formation of alcohol is a concern, such as in a case where marked decomposition has occurred, a positive alcohol finding may be confirmed in the vitreous fluid, a specimen type that is more resistant to microbial growth.

Post-Mortem Redistribution

Besides contending only with the issue of contamination as caused by trauma, drugs and their metabolites may also be subject to postmortem redistribution. Postmortem redistribution is the movement of drugs among tissues, organs, and bodily fluids after death. The rate and extent of this movement varies according to several factors, including the nature of the drug, and the time interval between death and the postmortem collection time of specimens. Within the torso, the major organs constitute potential drug pools, and the gastrointestinal tract might contain considerable quantities of unabsorbed drug. Therefore, central blood is subject to redistribution from these local organs. In general, redistribution into central vessels is greater than redistribution into peripheral vessels and this is why it is preferred that final quantitative amounts be determined from a peripheral blood source. Therefore, while central blood pools are acceptable for screening purposes, it is always better to get a peripheral blood sample for quantitative confirmation work, if possible.

Cocaine

Cocaine, a Schedule II controlled substance, is found in the leaves of a South American shrub called *Erythroxylon coca* and is one of the most potent of the naturally occurring central nervous system (CNS) stimulants. First isolated in 1855, it has been used medicinally as a local anesthetic. However, because of its high potential for abuse, the use of cocaine for clinical situations has become severely limited. When cocaine is taken for illicit reasons it is either taken as the water-soluble hydrochloride salt by nasal insufflation (“snorting”), intravenous injection, or as the free-base (“crack”) by smoking. Regardless of the chemical form or route of administration, once cocaine is administered it is rapidly absorbed and distributed throughout the body. Once inside the body, the dosage form of cocaine cannot be distinguished and analytical determinations are reported as the free-base form.

Cocaine is rapidly biotransformed in the body to a few major metabolites and products including benzoylecgonine, ecgonine methyl ester, ethylecgonine, and ecgonine. These metabolites are all pharmacologically inactive. Small amounts of an active metabolite, norcocaine, may also be produced. However, this product is rarely detected in blood. Cocaethylene is a pharmacologically active substance formed in the liver when cocaine and ethanol are co-ingested. The most predominant cocaine product detected in the majority of biological specimens is benzoylecgonine. Elimination on half-lives are approximately 4.5 hours for benzoylecgonine and approximately 0.8 hours for cocaine.

Effects displayed by an individual under the influence of cocaine may include dilated pupils, increased blood pressure, increased pulse rate, and increased sense of strength or invincibility. It is believed that cocaine is toxic to the cardiovascular system causing thrombosis, myocardial infarction, tachycardia, or fibrillation that may occur in cases of acute and chronic abuse.

Heroin

Heroin is a Schedule I controlled substance and a synthetic derivative of morphine. It is made by first extracting morphine from opium and then chemically treating the morphine with acetic anhydride, sodium chloride, and hydrochloric acid.

Once heroin is taken into the body, most frequently by injection, smoking, or inhalation, it is rapidly deacetylated to 6-monoacetylmorphine (6-MAM), a product that is then hydrolyzed at somewhat of a slower rate than morphine. Unlike the heroin, which has little affinity for the opiate receptors in brain tissue, both 6-MAM and morphine are pharmacologically active. Because 6-MAM is a specific product of heroin, if it is found to be present in a biological specimen, it can be concluded that the individual either used or was exposed to heroin at some point prior to death. However, due in part to the short half-life of 6-MAM, morphine is most often the predominant species detected in biological specimens. Therefore, in cases where heroin is suspected to be the lethal agent and morphine is found in the blood but 6-MAM is not, it may be of benefit to test an alternate specimen type such as urine for the presence of this heroin specific marker as well.

The primary toxic manifestations of heroin use may last for approximately 4 to 6 hours and include the same effects most commonly associated with other opioids. Some of the more common effects include drowsiness, loss of coordination, decreased blood pressure, decreased pulse and respiration, mental clouding, sedation, and sweating. At sufficiently high levels, the user may slip into a coma and may ultimately stop breathing.

Lysergic acid diethylamide (LSD)

LSD, a Schedule I semisynthetic controlled substance, is manufactured from the main precursor chemicals lysergic acid, lysergic acid amide and ergotamine tartrate. LSD is normally taken by placing a "dot" laced with the material on the tongue. The LSD is then dissolved by the saliva and readily absorbed through the mucous membranes. This method of ingestion allows for its effects to be rapidly felt. Other means of ingestion include mixing the LSD with liquids or adding it to sugar cubes. However, the drug cannot be taken into the body by smoking, as pyrolysis destroys the LSD.

LSD is generally classified as a hallucinogen or psychedelic drug, and may produce both auditory and visual illusions. Approximately 30 to 60 minutes after ingestion, the user will experience the initial effects which, in general, may last for about 8 to 12 hours. Physiological effects are primarily sympathomimetic and may include mydriasis, hyperthermia, seizures, panic, and paranoid reactions. Flashback reactions, a brief recurrence of the LSD experience, are not uncommon in the experienced user, and may occur for weeks, months, or years after the last usage.

Death due to the pharmacological effects of LSD is rare, with most deaths occurring as a result of LSD-induced suicide and accidental trauma.

Marijuana

Marijuana, a Schedule I controlled substance, is a complex mixture of several products obtained from various parts of the *Cannabis sativa* plant, and is the most widely used illicit substance in the United States and the rest of the world. More than 400 chemical substances are found in marijuana. Sixty of these substances are called cannabinoids and are responsible for the psychoactive properties of the plant. The most relevant cannabinoid is tetrahydrocannabinol (THC), as it is the primary psychoactive ingredient in marijuana.

One of the most notable features of this drug is its long half-life, with some metabolic components exceeding 50 hours. This is because the drug is a highly lipid soluble and may undergo significant enterohepatic recirculation. In fact, the redistribution of THC from tissue to blood has been shown to be the rate-limiting step in its metabolism. In the body, THC is metabolized to two major metabolites, 11-hydroxy-THC (11-OH-THC) and tetrahydoxycarboxylic acid (THCC). The former metabolite is pharmacologically active, while the later is devoid of any pharmacological activity.

Marijuana is most frequently smoked, although it can be ingested as well. THC rapidly leaves the blood, even during a smoking period, and falls to below detectable levels within several hours. The most common physical effects are acceleration of heart rate, a moderate increase in blood pressure, a slight decrease in body temperature, reddening of the eyes, and a dryness of the mouth. The psychological effects of marijuana use include a pleasant feeling of well-being and euphoria, distortion of time, reduced ability to concentrate and memorize, and impaired short-term memory. Individuals under the influence of marijuana may have difficulties in tracking movement and demonstrate an inability to appropriately respond to stimuli. In general, this condition may persist for hours after the feelings of intoxication have dissipated, leaving users with a false sense of security concerning their abilities to safely operate a motor vehicle or machinery.

Death strictly due to the pharmacological effects of marijuana is not well documented, with most deaths occurring as a result of accidental trauma.

Methamphetamine

Methamphetamine is a Schedule II controlled substance with a very high potential for addiction and abuse. There are two different chemical forms or isomers of methamphetamine, each producing effects that differ in scope and magnitude. The l-isomer of methamphetamine may be found in over-the-counter nasal inhalers and is used for its vasoconstrictive properties. Compared with d-methamphetamine, it is a weak central nervous system stimulant. In contrast, the d-isomer may represent the licit or illicit forms of methamphetamine. In terms of legitimate or legal use, methamphetamine may be prescribed for a limited number of medical conditions such as weight loss, narcolepsy, and attention deficit disorder. However, because other less addictive and dangerous substances that do not quickly result in patient tolerance to the drug are also available, it is not that frequently prescribed.

Methamphetamine in the body undergoes demethylation to its primary active metabolite amphetamine; in most cases both methamphetamine and amphetamine will be detected. Analytical methods that differentiate the isomers of methamphetamine (and amphetamine) exist and may be employed if warranted.

People who abuse methamphetamine experience certain sequelae of such drug use. In general, the effects of methamphetamine can be broken down into three main stages. The first stage is the "high," where blood concentrations are at their greatest and people are feeling the stimulant effects of methamphetamine. The second stage is the "tweaking" period, where blood levels are on the decline and it is this period where people crave the drug and may behave in an aggressive and violent manner. The third stage is the "crash," where people feel exhausted and drained. High doses of methamphetamine can elicit restlessness, confusion, hallucinations, circulatory collapse, and convulsions.

Methadone

Methadone is a Schedule II controlled substance that is often prescribed during the process of narcotic detoxification, narcotic maintenance, and treatment programs, and to control severe and chronic pain. As compared with morphine, it produces less sedation and euphoria, but cessation of its use may result in withdrawal symptoms—not as severe as those seen with morphine, but longer in duration. Methadone works by decreasing the withdrawal symptoms felt by the narcotic abuser and, when a person attempts to reuse, the desired effects of the illicit drug are minimized.

In the body, methadone is metabolized to EDDP (2-ethylidene-1,5-dimethyl-3,3-diphenylpyrrolidine) and EMDP (2-ethyl-5-methyl-3,3-diphenylpyrroline). These metabolites do not possess any pharmacological activity and do not accumulate to an appreciable extent in plasma during therapy.

Methadone overdose is characterized by stupor, lethargy, pupillary constriction, hypotension, coma, respiratory collapse, and death.

3,4-Methylenedioxymethamphetamine (MDMA)

MDMA is a synthetic sympathomimetic compound with mixed stimulant, psychotropic, and hallucinogenic activities. It was used briefly as an adjunct to psychotherapy, but because of widespread abuse it has now been reclassified as a Schedule I controlled substance. The synthesis of MDMA is both complex and time-consuming. As a direct result, the final product may contain a variety of impurities that may be toxic in their own right. Also, drug manufacturers may add an illicit substance or a stimulant in an attempt to enhance the effects of the MDMA. The drug is available in tablet and powder form and it may be injected, inhaled, or ingested. Tablets of MDMA come in a litany of colors and shapes, and may be imprinted with a variety of images including things such as peace symbols, cartoon characters, butterflies, and angels.

In the body, MDMA is metabolized to many other compounds, but the main metabolite is a demethylated product called methylenedioxyamphetamine (MDA).

The effects of MDMA are related to the dose. A lower-level dose (approximately 50 mg) may result in feelings of enhanced creativity, while mid-level doses (approximately 100 mg) may make the user feel open to improved communication and empathy. The ability of the user to undergo self-exploration and analysis is achieved with the doses typically greater than 125 mg. In general, the psychological effects are much more pronounced than the physical effects. Abusers of the drug have been reported to experience longlasting neurobehavioral disorders following cessation of its use. Symptoms of MDMA toxicity include visual hallucinations, confusion, hypotension, agitation, coma, and death.

Phencyclidine (PCP)

PCP is a Schedule II controlled substance that was developed and marketed in the 1950s for use as an intravenous anesthetic. However, it was discontinued for medicinal use in 1965 as patients frequently would become agitated, delusional, and irrational, and experience the distortion of sights and sounds. In the early 1960s, PCP gained a reputation as a drug that produced certain desired feelings such as detachment and dissociation, but also caused the user to sometimes experience unwanted reactions (i.e., bad trips).

At low doses, PCP may cause changes in body awareness and produce psychological effects of euphoria, an alteration of time and space, confusion, bizarre behavior, and panic. Physical effects produced by PCP include impaired motor skills, shallow breathing, sweating, blank staring, speech disturbance, and an inability to regulate body temperature. At high doses, PCP may result in hallucinations, seizures, coma, and death. Because PCP has sedative-like effects, interactions with other central nervous system depressants, such as alcohol and benzodiazepines, may also lead to a life-threatening situation. In general, chronic PCP users may repeatedly use the drug for days at a time and during this period go without food or sleep. There appears to be no relation between plasma levels of phencyclidine and the degree of intoxication that a person may experience.

Oxycodone

Oxycodone is a Schedule II controlled semisynthetic narcotic analgesic derived from thebaine. It is used to control pain associated with such ailments as bursitis, injuries, simple fractures, and neuralgia, and is often found in combination with other drugs such as acetaminophen and aspirin. The addiction liability of oxycodone is about the same as for morphine.

Oxymorphone is a pharmacologically active metabolite of oxycodone that may be seen in blood in very low concentrations. Of interest is that oxymorphone may be prescribed as a parent drug and has a greater analgesic potency than morphine.

In overdose, oxycodone can produce stupor, coma, muscle flaccidity, severe respiratory depression, hypotension, and cardiac arrest. However, sustained-release preparations appear to produce adverse reactions, up to and including death, at lower-level concentrations, especially in combination with other central nervous system depressants, depending on use pattern and route of administration.

Poisons

Arsenic

Arsenic is a metalloid that is present in all parts of the environment and, for example, may be found in water, soil, and sediment. In broad terms, there are two main forms of arsenic —organic and inorganic. Organic arsenic is present in food, with crustaceans and fish being some of the richest sources. These organic forms of arsenic (arsenobentaine and arsenocholine) are considered to be relatively nontoxic and will be rapidly excreted unchanged in the urine. Inorganic arsenic occurs in two oxidation states: a trivalent form (arsenite) and a pentavalent form (arsenate), with the trivalent form being more toxic than the pentavalent form, which undergoes metabolism to monomethylarsonic acid (MMA) and dimethylarsenic acid (DMA). MMA and DMA are then excreted in the urine.

Arsenic inactivates up to 200 enzymes, most notably those involved in cellular energy pathways, and DNA replication and repair. Unbound arsenic also exerts its toxicity by generating reactive oxygen intermediates that cause lipid peroxidation and DNA damage. Inorganic arsenic binds thiol or sulfhydryl groups in tissue proteins of the liver, lungs, kidney, spleen, gastrointestinal mucosa, and keratin-rich tissues such as the skin, hair, and nails.

The lethal dose of arsenic in acute poisoning ranges from 100 mg to 300 mg. Severe acute arsenic intoxication produces several well-described symptoms. Bloody vomit and diarrhea may occur within 1 to 4 hours of ingestion. Gastrointestinal volume loss is compounded by profound capillary permeability produced by arsenic's interruption of cellular energy metabolism. Cerebral edema, microhemorrhage, encephalopathy, and seizures may also arise from loss of capillary integrity. The rate-corrected QT interval (QT_c) prolongation and tachyarrhythmias may develop.

Subacute arsenic toxicity involves predominately the neurologic and cardiovascular systems. Within days to weeks after ingestion, many untreated or undiagnosed patients describe debilitating peripheral neuropathy characterized by excruciating pain and severe motor weakness. Persistent QT_c prolongation and the accompanying risk of *torsades de pointes*, a specific type of cardiac arrhythmia, occur among patients with clinically significant body burdens of arsenic.

Chronic arsenic toxicity presents itself following months or years of exposure. Some hallmark features of this type of toxicity not described above include hyperpigmentation of the skin, hyperkeratosis of the hands and feet and the appearance of Mee's lines in the fingernails.

It is important to note that death may occur in all of the above situations (e.g., acute, subacute, and chronic) if the person is exposed to a sufficiently high dose of arsenic.

Carbon Monoxide

Carbon Monoxide (CO) is an odorless, colorless gas without taste that forms as the result of the incomplete combustion of carbon-containing material. Motor vehicles, appliances, and heaters that use carbon-based fuels are major sources of exposure. However, it is important to note that natural sources of carbon monoxide also exist. These sources include fire, gases emitted from mines, marine algae, and human metabolism. Carbon monoxide is endogenously produced when hemoglobin, the molecule responsible for oxygen transport, and other heme-containing substances are degraded or broken down. Because of this, endogenous levels of CO, analytically measured as carboxyhemoglobin, are typically less than 1%. It is important to note that CO levels within the body may vary depending on several other factors as well. For example, because cigarette smoke contains CO, a smoker may exhibit carboxyhemoglobin levels as high as 8% saturation.

A person becomes exposed to CO via inhalation with the ultimate biological saturation level dependent upon several factors including CO concentration, duration of exposure and the activity level of the individual. Carbon monoxide poisoning produces hypoxia by two main mechanisms of action. First, CO binds to hemoglobin with an affinity that is greater than 200 times that of oxygen and therefore, by occupying the oxygen binding sites of hemoglobin, CO directly decreases the oxygen-carrying capacity of blood. Second, when CO binds to hemoglobin, the hemoglobin undergoes a change in its configuration so that oxygen release from the hemoglobin is hindered. Early signs of CO poisoning include headache, nausea, and vomiting. As the CO poisoning progresses, the person may experience impaired mental function, an inability to concentrate, and personality changes. Finally, the individual may develop seizures, coma, and death. Classic pathological signs that are most often associated with CO poisoning, although rarely observed, include cherry red skin and retinal hemorrhages.

Cyanide

Cyanide is a potent, rapidly acting lethal poison, and death may occur within minutes following its ingestion.

Common sources of cyanide include industrial manufacturing byproducts, plants, fruit pits, chemicals, and combustion products of certain plastics. Because of the latter, cyanide may play a role in the hypoxic events from fires.

Cyanide exerts its effects by disrupting electron transport at the cytochrome c oxidase step and this in turn adversely impacts the production of adenosine triphosphate (ATP). This break in the oxidative phosphorylation process stops the Kreb's cycle, and ultimately causes a metabolic acidosis as both pyruvic and lactic acid begin to accumulate.

The signs and symptoms of toxicity are dependent upon several factors. These factors include the form of the cyanide (e.g., gas versus solid), the route of exposure (e.g., inhalation versus ingestion), the duration and the extent of the exposure. The minimum lethal dose in an adult has been estimated to be 100 mg for hydrocyanic acid and 200 mg for potassium cyanide.

Cyanide produces a range of symptoms including dizziness, weakness, motor impairment, and mental impairment. These symptoms may progress toward slowed respiration, lactic acidosis, seizures, coma, and death.

It is important to recognize that blood concentrations of cyanide can increase or decrease during storage depending on the length of time, the temperature, and the presence of cyanogenic bacteria.

Ethylene Glycol

Ethylene Glycol is a nonvolatile liquid that is a common ingredient of automotive products such as antifreeze, de-icers, and coolants. It can also be found in some preservatives and as a glycerin substitute.

Following ingestion, ethylene glycol is rapidly absorbed, and manifestations of toxicity may be noted within approximately 30 minutes. Ethylene glycol is metabolized in the liver to several toxic metabolites including glycoaldehyde, glycolic acid, glyoxylic acid, and oxalic acid, and it is these metabolites that then may elicit central nervous system, cardiopulmonary, and renal dysfunction as well as produce a severe metabolic acidosis. The magnitude of the toxicity is dependent upon dose and the onset and success of treatment.

The effects of an ethylene glycol exposure are typically described in three main stages. In the first stage (0.5 to 12 hours post ingestion), neurological symptoms that include signs consistent with ethanol intoxication are manifested. Coma, convulsions, and possibly death may result in this stage. The second stage (12 to 24 hours post-ingestion) is often characterized by cardiopulmonary disturbances including tachycardia, tachypnea, and hypertension. In severe ingestions, congestive heart failure, pulmonary edema, and circulatory collapse may be seen. The end stage of ethylene glycol toxicity is renal failure (24 to 72 hours post-ingestion).

Methanol

Methanol is a type of alcohol that is extremely versatile, and so can be found as a component in industrial solvents, fuels, and antifreeze preparations, and as a denaturant for ethanol. Methanol may be introduced into the body through multiple routes of administration including inhalation and ingestion. Once in the body, methanol is first metabolized to formaldehyde and then to formic acid. Interestingly, although formaldehyde is considered a toxic substance, it has on average a half-life of only several minutes and it is the formic acid that ultimately produces the hallmark features of methanol toxicity, including metabolic acidosis and the loss of visual acuity. Methanol poisoning can be treated by the administration of ethanol, because both methanol and ethanol share a common metabolic pathway. In essence, the ethanol competes for binding to the alcohol dehydrogenase enzyme and indirectly limits the formation of formic acid. Acute methanol exposure may produce severe signs and symptoms of toxicity, including nausea, abdominal pain, and lethargy. In some cases, the poisoning will progress to where the person experiences an anion gap metabolic acidosis leading to coma, seizure, and respiratory collapse. It is important to recognize that methanol may be a component found in embalming fluids and, because of this, tissues or other samples that have come into contact with this type of material may test positive for the presence of methanol.

Poison Hemlock

Poison hemlock (*Conium Maculatum*) is a biennial member of the carrot family that grows wild throughout the United States, especially along roadsides. Socrates is thought to have died from ingestion of poison hemlock. Its toxicity is from several simple piperidine alkaloids including coniine, gamma-coniceine, conhydrine, N-methylconiine, and pseudoconhydrine. Coniine and gamma-coniceine are thought to have the most significant contribution to the toxic effects, which are similar to nicotine poisoning.

Thallium

Thallium is a metal that was once used in rodenticides, insecticides, and depilatories, but was banned from residential use in the 1970s. Today, it is used in the semiconductor industry and may be found in switches and electronic devices. Thallium is readily absorbed from the gastrointestinal tract and may be detected in most of the body's tissues and fluids, including blood, brain, liver, kidney, spleen, bone, hair, and urine. The half-life of thallium in the blood is approximately 2 to 4 days, with one of the hallmark symptoms of this type of poisoning, alopecia or loss of hair, occurring after about 1 to 3 weeks. Symptoms of acute exposure include severe gastrointestinal distress, tingling of the hands and feet, paralysis, and respiratory failure. In people being chronically exposed, additional signs and symptoms include paralysis, hepatic and renal issues, and respiratory failure.



Acute track marks. Multiple fresh needle mark injection sites that traverse the path of underlying veins. Incision of these regions will often reveal underlying hemorrhage. Toxicological testing of underlying injection site tissue may reveal the parent compounds, such as heroine.







Chronic track marks. Linear scars that traverse the path of underlying veins. Microscopic sections may demonstrate inorganic debris in sub-adjacent soft tissues.











Tattoos are sometimes used to disguise intravenous drug abuse. These figures show examples of track marks in tattoos. Note the fresh injection site at the tip of the bird beak (d) and the healing injection sites at the stars (e), as well as other chronic linear track marks. Also note the fresh needle mark to the left of the tattoo (b) due to documented therapeutic intervention.



Fresh "skin popping" lesions. When drug abusers exhaust peripheral vein access they may start injecting drugs subcutaneously.



Recent healing infected skin popping lesion with adjacent cellulitis. It is common for these lesions to become infected due to the nonsterile nature of the injection equipment.



Recent healing infected skin popping lesion.



Healed and almost completely healed skin popping lesions. Note the lower wound has almost complete replacement by scar except for the central healing defect.



Remote old healed skin popping lesions.





Examples of jaundice following hepatic failure due to hepatic cirrhosis as the result of chronic alcoholism; and viral hepatitis caused by chronic intravenous drug abuse. Note the yellow discoloration in the sclera and skin (a) and (c). Figure (b) demonstrates a comparison to a nonjaundiced individual. Also note the patchy areas of ecchymosis due to coagulopathy associated with the liver disease.





Marked hepatic steatosis due to acute alcoholism.



This image demonstrates cut portions of liver. Normal liver is brown (a); the yellow section demonstrates marked steatosis or fatty liver (b). The green section demonstrates micronodular cirrhosis due to chronic alcoholism with inspisated bile (c). The bile imparts this green discoloration.



Micronodular hepatic cirrhosis with steatosis due to chronic alcoholism.



Macronodular hepatic cirrhosis due to hepatitis B infection as a result of chronic intravenous drug abuse.



Chronic alcoholic with hepatic cirrhosis and gynecomastia. This individual also had neurofibromatosis, which is demonstrated by the multiple subcutaneous nodules.



Chronic alcoholic with hepatic cirrhosis and coagulopathy. Note the multiple areas of ecchymosis and contusion caused by minimal blunt force trauma.



Gastrointestinal hemorrhage due to Mallory-Weiss tears in a chronic alcoholic. Note the laceration of the gastroesophageal junction leading to death from gastrointestinal hemorrhage following multiple episodes of vomiting.



Acute gastritis associated with chronic alcoholism. Note the red discoloration of the mucosa.



Esophageal varices due to hepatic cirrhosis and increased portal hypertension. Note the dilated red to brown submucosal veins that may rupture and possibly cause exsanguination.



Bleeding peptic ulcers in a chronic alcoholic with gastrointestinal hemorrhage and hepatic cirrhosis.



Acute peritonitis in a chronic alcoholic. Note the purulent exudate at the intestinal surface.



Hyaloserositis. Old healed peritonitis with fibrosis at the surface of the liver and spleen in a chronic alcoholic.







Acute pancreatitis due to chronic alcoholism. Note the white flecks due to fat necrosis and areas of hemorrhage.



Fatty metamorphosis or atrophy of the pancreas with duct concretions in a chronic alcoholic.



Pyogenic liver abscesses. This decedent had a history of chronic alcoholism with chronic pancreatitis and recent abdominal pain of unknown etiology. This photo depicts multiple geographic, creamy yellow-white collections of purulent material within the liver parenchyma that microscopically proved to be dense collections of neutrophils, karyorrhectic nuclear debris, and masses of faintly basophilic, fine filamentous bacteria. Samples of the abscesses were submitted to the microbiology laboratory but the best that they could do was anaerobic gram negative rods. Candidates included bacteroides, prevotella, and fusobacterium. Actinomyces would have been a consideration but they are gram positive. Pyogenic liver abscesses, while relatively rare, are known complications of chronic alcoholism and pancreatitis.



Suicidal overdoses demonstrating intact and fragmented granular pieces of partially digested pills. Note the containers with the granular white flecks at the bottom that indicate pill fragments.



Note the multiple scars demonstrating destructive behavior associated with drug abuse, mental illness, and suicide.



Acting as a "mule," this person ingested multiple packets of drugs to smuggle them into the country. One of the packets ruptured and the individual died of a drug overdose before the plane landed. Note the typical x-ray findings demonstrating these packets within the gastrointestinal tract.







Packets of drugs discovered at autopsy in individuals who died in hotels next to an airport. Note the broken packets demonstrated at the bottom of the last picture.



Epicardial vessels with slight atherosclerosis and occluding thrombosis associated with acute cocaine intoxication.



Carbon monoxide poisoning with cherry red lividity.

Postmortem Change and Time of Death

4

CHARLES A. CATANESE, BRUCE LEVY,
AND GERARD CATANESE

Introduction

In most jurisdictions the time of death is legally defined as the time that the person is declared or recognized to be dead. Thus, a decomposed body or skeletonized remains, clearly deceased for significant periods of time, may have an official time of death that is days, weeks, months, or even years after the actual death of the individual. However, being able to estimate the actual time of death (or the postmortem interval) can be critically important in criminal investigations, civil litigation, or settlement of the deceased's estate.

The concept of a "window of death" was developed to help answer these questions. This window can be initially bracketed by the time that the person was last known to be alive and the time he or she was declared dead. Forensic science can then apply a variety of observations and tests in an attempt to narrow that window as much as is scientifically and medically possible. Accurate interpretation of postmortem change is crucial in helping to establish the actual time of death.

Postmortem changes can be subdivided into several categories. These categories include early postmortem changes, decomposition, and skeltonization. Each has characteristics that can overlap with advancing time and are variable depending on environmental conditions and the physiologic state of the body at the time of death. The activity of insects and animals will also create artifacts that can lead to misinterpretation of the postmortem interval. Interpreting postmortem changes is not an exact science, and without a witness, one can only estimate a time period in which the death was most likely to have occurred.

Early Postmortem Changes

Generally considered to occur or evolve within the initial 24 hours after death, these consist of algor mortis, livor mortis, and rigor mortis.

Algor Mortis

The cooling of the body after death. After death the body will gradually cool until it equilibrates with the ambient temperature. Under standard climate controlled conditions, with average humidity and a room temperature of about 72° F, the body generally loses about 2° F per hour for the first 12 hours and than approximately 1° F per hour for the next 12 to 18 hours. If the ambient temperature is greater than the body temperature, algor mortis occurs in reverse and the body temperature rises until it reaches the ambient temperature.

The above calculations apply only at or near room temperature and will become variable as the ambient temperature changes. As a general rule, the rate of temperature change in a body is proportional to the difference between the temperature of the body and its environment. In other words, if the ambient temperature is below 72° F, the rate of heat loss will be increased from the numbers above. The reverse would be true for temperatures greater than 72° F. Moving air will cool faster than still air, and wet bodies will cool faster than dry bodies. Bodies found in stagnant water, flowing water, or those found buried in the ground will cool at different rates from those in the air and from each other. When the body and environment are at the same temperature, they have reached steady state and estimates of time of death based on temperature are limited to a minimum period of time.

Many other variables can influence algor mortis. In general, an elevated body temperature at the time of death will give the appearance of a shorter postmortem interval based on a measurement of the body temperature. A lower body temperature will have the reverse effect. Things that effect body temperature include infection, strokes, seizures, thyroid disease, and many other natural diseases. Whether or not the person was involved in strenuous physical activity prior to death (such as a violent struggle) will increase body temperature. Many other factors, including the age of the person, his or her overall health, and many drugs or medications can also have an effect on the calculation of postmortem interval based on this and other observations.

It is important to make certain there is consistency in how the body temperature is obtained. First, these calculations are based on a core body temperature, meaning either taking a rectal temperature or, more ideally, introducing a thermometer into the abdominal cavity beneath the liver to measure core temperature. Temperature readings on the surface of the body, including axillary, oral, or ear temperature are unacceptable for determining a postmortem interval. The thermometer must be kept in place long enough for the body temperature to equilibrate.

Livor Mortis

The settling of blood under the effects of gravity after death. It can first be appreciated as early as 20 minutes after death in very light-skinned individuals. The color of the livor will deepen to a purple color over the first 8 to 12 hours after death. During this period the livor is typically blanching, meaning that pressure on an area of livor will cause the color to briefly leave the area, resulting in a pale mark. After about 12 hours the livor will become fixed and no longer blanch under pressure. As with algor mortis, temperature will influence the rate at which livor becomes fixed, with increased temperatures shortening the time for livor to become fixed and decreased temperatures lengthening the fixation time. In some cases, livor mortis advances to cause small visible hemorrhages in the skin known as Tardieu spots, which should be distinguished from petechiae.

The medical condition of the person and the cause of the death can also create changes in livor mortis. People who are anemic (low blood count) or sustain an injury resulting in significant loss of blood might have very faint or even absent livor mortis. It can also be difficult to appreciate livor in dark-skinned individuals.

When evaluating livor mortis, it is important to note its location, intensity, whether it is blanching or fixed, and if it is appropriate for the position of the body. If livor is inappropriate for position, you can conclude that the person was moved at some point after the onset of livor. You can also evaluate livor for its color. For example, people who die as a result of carbon monoxide or cyanide poisoning will have a bright “cherry red” color to their livor mortis. People who die in a cold environment might also have a similar red color to their livor.

Rigor Mortis

The stiffening of the body after death. It is the result of a physiochemical process within the muscles of the body that does not cause actual contraction of the muscles. Under typical conditions, rigor will first be appreciated within 30 minutes to 2 hours after death. It will progress to a maximum intensity over the first 12 hours and remain at a maximum until about 24 hours after death. It will then “pass” from the body between 24 and 36 hours after death, after which the body will remain flaccid.

As with algor mortis and livor mortis, many variables will affect the rate of development and passing of rigor mortis. In general, increased environmental or body temperatures will speed the rate of development and passing of rigor mortis. Lower environmental or body temperatures will have the reverse effect. People at the extremes of age (children and the elderly) will have different rates of appreciation of rigor mortis due to the decreased muscle mass in these age groups.

When evaluating rigor mortis, it is important to note its location and intensity and whether it is appropriate for the position of the body. If rigor is inappropriate for position you can conclude that the person was moved at some point after the onset of rigor.

Decomposition

As time advances, decomposition gradually increases. Decomposition can be subdivided into two basic categories, putrefaction and mummification. While they can be seen in isolation, careful observation will typically reveal features of both processes simultaneously.

Putrefaction

Decomposition that occurs due to the actions of bacteria. The bacteria typically break down the body from the inside out, causing many of the changes we associate with a person who has been deceased for a longer period of time. However, when there is penetrating trauma that breaks the surface of the body, bacteria from the environment can gain access and hasten putrefaction. These changes include darkening and slipping of the skin, the production of a foul-smelling gas, with bloating of the body and marbling of blood vessels. A dark colored bloody-appearing purge fluid will come from the nose and mouth and should not be confused with blood related to trauma.

This process is extremely environmentally dependent. As with the early postmortem changes, warmer temperatures accelerate this process and cooler temperatures slow it down, with many of the same factors playing a role. A body placed in a dark dumpster in the hot summer sun for half a day can reach a state of putrefaction equivalent to a body left at room temperature for several days or one in the winter cold for greater than a week. In the case of fire fatalities, charring will preserve the body and decelerate this process. A frozen body that has thawed will putrefy at a markedly accelerated rate due to spaces left by frozen ice crystals.

Mummification

Mummification occurs in a dry environment, typically such dry outside environments as a desert, or in heated indoor environments during the winter months when the relative humidity is low. Initially, there is a darkening and hardening of the skin. This will progress to produce flaking of the surface of the skin that can give extremities the appearance of a log, thus the term "tree barking." As with putrefaction, the skin will begin to split and eventually the skin and soft tissues under the skin are also lost.

Skeletonization

Both putrefaction and mummification eventually lead to skeletonization of the body. The loss of soft tissue progresses at a variable rate, depending on the environmental conditions and access of the body to a variety of animals and insects. The face and ends of the extremities are the first areas where bone is exposed, and the pelvic soft tissues are the last to be lost. While this process is usually measured in months, work performed at the Anthropologic Research Facility at the University of Tennessee in Knoxville has demonstrated that complete skeletonization of a person can occur within days under appropriate conditions.

Autolysis

Autolysis associated with decomposition occurs after cell death and is due to the actions of digestive and catalytic enzymes released from cells in the body. This term, "self-destruction," is advanced in certain organs, especially the intestinal tract and pancreas, due to their rich enzyme content. This is important to note because autolysis can mimic certain disease processes at the time of gross examination. Maceration of stillborns who were dead inside a uterus for days is a type of autolysis associated with moist sterile environments, appears as a red discoloration with skin slippage, and is not to be confused with trauma or disease.

Adipocere

A process that is rarely seen outside of exhumation cases. It is a chemical change that occurs in the fatty tissues of the body exposed to wet conditions. Adipocere takes many months to develop, and once it forms is extremely persistent, stopping the typical loss of soft tissue and skeletonization of the body.

Other Factors in Evaluating Postmortem Interval

When a deceased body has been exposed to insect or animal activity, we can make observations that might assist in the determination of the post-mortem interval. Maggots (the larval stage of blowflies) can be collected from the body and examined by an entomologist. You need to collect two sets of specimens. One set should be kept alive while the other set is killed. The entomologist will determine the exact species of fly from the matured living specimens and the likely time of death from the killed specimens. In persons who have been deceased for a prolonged period of time (months to years), an evaluation of the type and age of plants growing up through the body might also provide useful information.

Examination of the stomach and intestinal contents can also provide clues to help us in the determination of time of death. Our bodies digest food at a fairly predictable rate, depending on the quantity and types of foods consumed. Higher caloric content foods, such as fats, are digested slower than less complex foods. Larger meals remain in the stomach for a longer period of time. The rate of stomach emptying can be accelerated or slowed by natural disease, drugs, alcohol, or emotional stress. The description of the quantity, type, and condition of food in the stomach is part of the routine autopsy. This can be combined with information about that person's recent consumption of food obtained during the investigation to estimate the time from the eating of that meal until the time of death. Even without information about the last meal consumed, the stomach contents might provide clues as to when death occurred based on the types of food in the stomach.

Finally, markers found at the scene of death might provide the best information regarding the date or time of death of the individual. Observations regarding uncollected mail or newspapers, information from the telephone company about the last time the phone was used, dated sales receipts, or a noted change in habitual behavior might assist with determining the date of death. The clothing the person is wearing or the status of lighting in the home might provide clues regarding the time of the day or night that death occurred.

In conclusion, determining the postmortem interval can be difficult. Start with a broad window of death (last-known-alive to found-dead). Then use as many of the above elements as are available to attempt to narrow that window as much as possible. It is important to remember that there is variability of these observations and calculations, so keep an open mind and be willing to reevaluate your opinion based on new information as it becomes available.



Blanching lividity. Note the finger marks caused by pressing the blood away from the skin surface at the posteromedial aspect of the right thigh.



Fixed lividity at the lateral and posterior torso. Note the absence of lividity underlying the pressure region exerted by the arm against the weight of the chest. This child was discovered lying on his left side. This body was stored in a cold refrigerator for many hours prior to being autopsied.



This individual was placed in the morgue on her back the day before this examination. Note the fixed anterior lividity with partial sparing over with pressure points caused by lying on a wrinkled bedspread in her home for many hours prior to being discovered. Also note the early putrefaction consisting of slight green discoloration of the lower right abdomen.







Marked fixed lividity with dark purple spots known as "tardieu spots." Also note the vague chain pattern. It is not unusual for objects such as this to leave postmortem imprints.



In carbon monoxide poisoning, the color of the livor mortis is more of a bright red instead of the typical red-purple color. This change can also be seen in cases of cyanide poisoning or in decedents who have died in cold environments. Note that the color differences are very subtle and it may not be possible to make a determination from visual inspection alone.



The decedent was found lying on his back with his head elevated on top of several pillows. He was in full rigor mortis at the scene and maintained this position through his arrival into the morgue.



Full rigor mortis. Note the morgue technician pulling tightly on this decedent's arm, which is stuck in a bent position.



Congealing of fat. Adipose tissue at very cold temperatures will demonstrate increased viscosity. This might be mistaken for poor skin elasticity due to dehydration, which may or may not be present with congealing of fat. Note figure (b) shows indentations that have been retained following pressure exerted by fingers.



These are examples of "tache noire," which is a dark discoloration of a portion of sclera exposed to air. This is due to drying and is usually brown to red. This postmortem change may be misinterpreted as hemorrhage associated with strangulation.

This drying of the lips and tongue with dark discoloration is due to postmortem drying associated with mucosal exposure to air. This may be misinterpreted as an antemortem finding resulting from ingestion of caustic substances. The process of suicidal hanging caused the individual's tongue to stick out and become dry and dark.





This is also postmortem drying with dark discoloration of the scrotum and shaft of the penis. This may also be mistaken for an antemortem injury such as an abrasion. If there is doubt, one may make an incision to document underlying hemorrhage.



This is early mummification with drying of the hands and feet. Note the dark discoloration of the fingers with indentation from dehydration. Portions of the body with larger surface areas relative to underlying tissue mass will mummify more rapidly.



Early putrefactive change with green-brown discoloration of the lower abdomen. The first place for this to occur is typically the lower left abdomen above the cecal region.



This large hernia demonstrates early decomposition with slight green discoloration of the scrotum due to a portion of the large intestine extending into the scrotal sac.



Disproportionate advancing putrefactive change of the abdomen due to acute peritonitis. Note the green discoloration of the abdomen and the absence of green discoloration elsewhere. The presence of infection with bacteria caused this regionally accelerated process. Note the parulent exudate at the surface of the intestines, indicated by the arrow.



This individual committed suicide by ingesting excess prescription medication and placing a loosely fixed plastic bag over the head. The moisture collecting at the face covered by plastic during breathing helped to create an environment where mold and mildew could form at the chin and face.



Postmortem hot water burns of the face in this individual, who was found partially submerged in the warm water of a bathtub. He suffered a cardiac event while taking a shower. It requires less heat to cause thermal damage to a dead body than to a living body. Note the sharply demarcated red region indicating his nose and mouth were below the hot water.







Marbling. This early presentation of putrefaction is predominantly caused by bacteria tracking through the superficial blood vessels causing pigment changes in blood and vessel walls as microorganisms digest the body.



Early to moderate putrefactive change with green-brown fluid-filled blisters. Such blisters may be mistaken for second degree thermal burns or aggressive antemortem bacterial skin infections.



Early putrefactive change with clear yellow fluid-filled blister formation. The rupture of these blisters would appear as skin slippage.



Putrefaction with "purging." Note the red to brown fluid gurgling from the mouth and nose. This can sometimes be mistaken for an upper gastrointestinal hemorrhage.



Putrefactive change with bloating and expansion of the scrotum due to gas accumulation.



Green-brown-red discoloration with fluid-filled blister formation and skin slippage, scrotal enlargement from gas formation due to metabolism of proliferating microorganisms.



There is mummification of the fingertips with an expanded gas-filled blister and green to brown putrefied fluid in its inferior aspect.



Marbling and skin slippage; early to moderate putrefaction.



These images, (a) and (b), demonstrate skin slippage that occurred at different times. Note the regions of underlying dermis that are dry and dark, indicating older regions of skin slippage. Also note the other adjacent regions, which are moist, pale, and less dark, indicating shorter duration of underlying dermis exposure to air. This darker discoloration is due to more drying and longer exposure to the air.



Decomposing homicide victim with multiple decomposing blunt impact injuries. The combination of postmortem change with injuries may make interpretation challenging. Note the red to brown abraded contusions at the individual's face and head, with skin slippage and darker discoloration.





This individual was found lying on his left side with a mild to moderate degree of putrefaction. Note the puddle of purged fluid underneath his upper trunk and head (a). Also note the greater decomposition with green discoloration in the regions of dependent lividity where the body contacted the warm floor. Purged fluid such as this is often misinterpreted as the result of traumatic injury.



Accelerated putrefaction due to bacterial sepsis at the time of death. This picture depicts the left side of the patient's body with extensive skin slippage as well as green discoloration within the left infraclavicular area. Additionally, an endotracheal tube can be seen protruding from the mouth and taped to the side of her face. Such a depiction might lead one to conclude that overzealous paramedics had worked on a decedent who was decomposing. Marbling is also visible on the lateral and anterior aspects of the left arm. What this case really illustrates is the rapidity with which bacteria, already present within the blood stream at the time of death, can disseminate and propagate throughout the blood system, leading to accelerated postmortem putrefactive change.



Same case with front view of patient's face, also illustrating green discoloration around right infraclavicular puncture site and defibrillator marks.



This is the same case, demonstrating skin sloughage and exudation of hemolytic fluid from the external genital region.



Another case depicting a decedent with dark red-brown discoloration due to postmortem putrefactive change that was accelerated by the probable bacteremic state at the time of death.



Skin slippage with confluent red to brown discoloration, moderate putrefaction. Note figure (b) shows multiple nitroglycerin patches in an individual with known significant heart disease.



Moderate to marked putrefaction with dark brown discoloration and early mummification.



Moderate to marked putrefaction. Identification may sometimes be challenging with advancing decomposition. This individual had a tattoo on his left arm that was initially difficult to view due to putrefactive change. Cleaning of this area with removal of the superficial layers of skin made visualization and thus identification much easier.



Marked putrefactive change with dark brown discoloration and maggot feeding. Note the small circular perforations caused by maggots tunneling through skin and soft tissue.





Mummified fetuses retrieved from dried-out formaldehyde containers found within an abandoned building that once housed a doctor's office that closed more than 30 years earlier.







Advanced decomposition with mummification of the entire body. Note the dry dark leathery appearance of the skin.



Adipocere is a decomposition process seen with immersions or damp, warm environments. The neutral fats are converted to oleic, palmitic, and stearic acids. Note the white/tan-colored adipocere, which has a waxy feel. In some areas you can see a light sheen of oil on the surface. Once formed, adipocere is resistant to further decomposition.

Skull found tucked under the bottom of a stairwell in the basement of a brownstone in Brooklyn, New York. Note the dried skin at the nose. There was resin and perforation of the cribiform plate. This was the historical remains of an Egyptian mummy skull that was most likely used in religious ceremonies. There were also commingled chicken bones, feathers, and wax.











Advanced decomposition with skeletonization from a body dumped in a wooded area approximately 1 year earlier. The last image demonstrates five toenails from inside a shoe.





This frozen individual was murdered approximately 1 month prior to being found. His body was in a slight state of putrefaction due to preservation by the freezing winter temperature. Once the body thawed out for autopsy, putrefaction advanced at a markedly accelerated rate.



Photograph taken at time of autopsy. Note the advancing putrefaction with skin slippage. Also note the scalp laceration.



Macerated stillborns with red to brown discoloration. This type of decomposition is autolysis. The womb is normally a sterile environment and there should not be putrefaction unless there is an infection such as chorioamnionitis.



This child was discovered in the back of a garbage truck after being crushed by the trash compactor. The child was commingled with rotting food. Note the green discoloration of the skin due to putrefaction. Note the skull fracture with hemorrhage and dark discoloration due to putrefaction.



These slides show antemortem injuries that have been obscured by postmortem change. These individuals had multiple stab wounds and lacerations. Note the wound margins are dark and irregular due to drying. This may make wound interpretation challenging and at some point impossible. Also, animals and insects will often more readily feed from injured areas with exposed soft tissue and blood, further obscuring these findings.



These are examples of moderate putrefactive changes of internal organs with softening, dehydration, shrinkage, and partial loss of architecture. In (a) note the crepitant adipose tissue due to expanding cavities of gas from proliferating microorganism metabolism. Also note in (c) the gray discoloration of the brain with partial loss of architecture. As central nervous system putrefaction advances, the brain will develop into a liquid, oatmeal-like consistency with few or more recognizable structures. Figure (d) is of a putrefying liver and (e) is of a putrefying heart.









Note the fixed anterior lividity. The decedent was lying prone on a bed with a wrinkled comforter. Postmortem dog feeding occurred around the anus. Autopsy revealed the absence of large portions of intestines. Note that the torn clothing has dog hairs and blood staining. This case was first suspicious for homicidal violence. Large amounts of blood had drained from the body to the bedding, which was further spread about by the dog.



This is another example of postmortem dog feeding, which often initially involves the face, genitals, anus, and areas of wounds.



Postmortem animal feeding with dog claw abrasions.



Postmortem feeding by the decedent's dog.



Postmortem anemic superficial linear abrasions from a body retrieved from the Hudson River. This region of the body was noted to be scraping against a rocky surface just prior to retrieval from the water.



Larger carnivore activity is common in rural and suburban areas. In many cases, there may be activity from several different animals in the same environment. In this case, the damage appears to mostly be from the canine family (likely wild) with evidence of tearing of the skin and ribs. There is no obvious vital reaction, indicating the damage occurred postmortem. In these cases, one must consider whether the postmortem activity has obscured injuries sustained during life.









Advanced decomposition with mummification and animal feeding by the decedent's cats. Note the margin with claw marks and a scalloped border from feeding. One arm, a larger portion of the chest and most of the internal organs were absent.





In this case the carnivore activity was caused by domestic pigs.





Postmortem feeding from fish and crustaceans found on these bodies retrieved from the ocean.





Postmortem feeding of the ear due to mice and rats.



Note the varying stages of blowfly development. Eggs have an appearance similar to grated cheese or sawdust. When the eggs hatch, maggots develop and are shown in this picture in varying sizes as small, white, and wormlike. The dark brown pupa cases from hatching flies are also apparent. This entire cycle is accelerated in hotter temperatures.



Embalmed body. Figures (a) and (b) demonstrate sutured incisions made by funeral directors to gain access for blood removal with addition of embalming fluid. Figures (c)–(f) demonstrate multiple "trocar" (a metal rod used to infuse embalming fluid) puncture marks through the body's surface and organs. These may be misinterpreted as injuries.

Pediatric Forensic Pathology

5

MICHAEL J. CAPLAN AND CHARLES A. CATANESE

Introduction

Pediatric forensic pathology is the name for the unofficial and poorly defined subspecialty of forensic pathology that focuses on the evaluation of sudden, unexpected, unexplained or traumatic deaths in children, infants, neonates, and even fetuses. By definition, therefore, this discipline requires specialized knowledge of and familiarity with the various stages in growth and development that occur during childhood, infancy, and intrauterine life, along with the differential vulnerabilities of these periods to various insults, and finally, the unique patterns of injury that characterize these different periods.

Perhaps one of the most illustrative examples of this concept is the assessment of nonaccidental or inflicted head trauma in infants and very young children. An understanding of this type of injury would not be possible without being thoroughly acquainted with the following concepts: (1) the elasticity of the infant's scalp, such that it could potentially sustain a serious blunt impact without necessarily manifesting the impact in the form of a subgaleal contusion; (2) the thin, pliable, unilaminar quality that renders the skull less susceptible to fracture but also allows it to transmit forces to the underlying brain more readily; (3) the broad, shallow skull base in infants, which facilitates rotational movement of the brain and lowers the threshold for diffuse axonal injury; (4) the incompletely myelinated infant brain, with a gray- and white-matter water content substantially higher than that of an adult, imparting a consistency of unset gelatin and making the brain more vulnerable to shearing forces; and (5) the top-heavy calvarium and the weak, underdeveloped neck muscles that fail to effectively dampen the oscillations that are initiated when rotational movement of the brain begins. It is the interface of pediatric and forensic pathology that allows the most complete and comprehensive understanding of these concepts to occur; however, very few individuals actually have such expertise in both fields. As a result, forensic pathologists may have to rely on pediatric pathologists and neuropathologists when they are evaluating difficult, complex, or problematic cases involving deaths in the pediatric population.

Of the many scenarios encountered by the pediatric forensic pathologist, none is as enigmatic as the seemingly healthy infant who is found unresponsive after being put to sleep sometime earlier by a parent, sibling, or other caretaker, either in a crib, a child or adult bed, a couch, or some other location, often in a prone (face-down) position, and with soft bedding, pillows, and clothing. Sudden infant death syndrome (SIDS), a term that was coined in the early 1960s to remove the stigma of an unforeseeable and unpreventable death of an infant from that baby's parents, has now come full circle and runs the risk of being used as a "wastebasket" term for any infant death that is not obviously explainable by a disease or injury. The time-honored external and internal autopsy findings of froth (pulmonary edema) at the nares, intrathoracic (thymic, epicardial, or visceral pleural) petechiae, moderately congested organs, and an empty urinary bladder, while characteristic, are in no way specific for or pathognomonic of SIDS, and have been observed in a wide variety of other types of deaths. Forensic pathologists and pediatricians are just beginning to gain some appreciation of the myriad of factors involved in achieving respiratory control, arousal, and autoresuscitation.

Even in this modern age of molecular medicine, SIDS remains largely an unexplored entity. Thus, the forensic pathologist probably makes the greatest contribution in this area by identifying which deaths do not lie within the spectrum of SIDS. To do this effectively demands a carefully conducted medicolegal death investigation, a meticulously performed autopsy, and the use of ancillary studies, including postmortem toxicology, microbiology, chemistry, radiography, and metabolic screening. Only after all of these studies have been completed and integrated with the autopsy, scene, and anamnestic findings can the pathologist make an opinion about the cause and manner of death.

Other situations necessitating specific pediatric forensic expertise include the assessment of sudden unexplained deaths in otherwise healthy children, either during sleep or while awake, at rest or following exertion; sudden deaths in infants or children who have undergone operations for congenital heart disease; unexpected or unexplained deaths during or following diagnostic or therapeutic procedures; complex child abuse cases involving a multiplicity of injuries separated over space and time; deaths from genetic diseases that might mimic child abuse, such as osteogenesis imperfecta; and unexplained deaths following apparent minor trauma. In all of these scenarios, knowledge of the specific disease processes or related therapies is required in order to achieve the most complete understanding of the circumstances that culminated in the infant's or child's death. Other types of deaths affecting infants and children that are similar to those involving adults are typically fatal injuries sustained in motor vehicle crashes, either as occupants or pedestrians, although the considerable disparity in height, weight, and center of gravity often produces patterns of injury in infants and children that are distinctly different from those in adults.

Fatal child abuse presents primarily in two forms: (1) as the culmination of a repetitive pattern of inflicted injury, creating wounds of varying ages, in different parts of the body (what has been coined "the battered child syndrome"); and (2) as an impulse act by a caretaker who, following an act of urinating, defecating, or vomiting by the infant or child, lacks the self-control to prevent anger and frustration from translating into physical violence. The pediatric forensic pathologist must know what studies are necessary to perform in order to document not only what did happen, but to exclude all of the other reasonable possibilities that undoubtedly will be introduced by the defense in the adjudication of the case.

In some ways, the pediatric forensic pathologist often walks a diagnostic tightrope—deciding between SIDS and smothering, between inflicted closed-head injury and spontaneous intracranial hemorrhage, or between preeclampsia and maternal blunt trauma precipitating placental abruption. Toward that end, it is equally important to be aware of the limitations of a particular case and not offer opinions beyond what the circumstances and pathologic evidence allow. In some situations, "undetermined," while unsatisfying, is at the same time the fairest and most reasonable ruling until additional information is obtained that allows a more definitive ruling.



This child was brought to the emergency room and vigorously resuscitated. Note the marks left on the face as a result of endotracheal intubation and application of tape. It is important to document such findings and not confuse them with possible signs of child abuse, such as faint abrasions or contusions due to smothering. It is very important for clinicians to leave all tubes in place for postmortem (autopsy) confirmation of their placement.



Posterior lividity, which may be mistaken for injuries such as contusions related to child abuse.



Diaper rash. Note the red cutaneous eruptions. These indicate some degree of neglect.



Child abuse case with resuscitative efforts and perimortem sternal contusions due to chest compressions. Note other small contusions at the lateral aspect of the upper abdomen and lower chest. These were inflicted while the child was grabbed and flung about violently during the assault.



The same case showing perimortem contusions to the middle aspect of the chest due to resuscitation. Note the small amounts of subcutaneous hemorrhage overlying the sternum. Note the other segment of the "Y"-shaped incision is devoid of hemorrhage.



This case involved an infant who was found unresponsive in her crib. The case was referred to the medical examiner's office for autopsy. However, as the external examination was about to begin, this sutured midline incision was encountered. Further inquires revealed that the emergency department physician had authorized postmortem procurement of the infant's heart for heart valves. When this was discovered, the organ procurement agency was contacted, and released the heart to the medical examiner's office. The heart was found to have an anomalous origin of the left coronary artery from the right sinus of Valsalva, a rare yet documented cause of sudden death in both adults and infants. The issue of organ procurement remains a controversial and at times problematic one for the forensic pathologist. Consistently reliable methods for evaluating the coronary ostia have not been established in many tissue procurement agencies for the retrieval of hearts.



View of lower trunk, external genitalia, and lower extremities depicting a right-sided intraosseous catheter. This is a common mode of resuscitation in infants with extremely small, often collapsed blood vessels.



Hemorrhage with swelling of the thigh due to a misplaced femoral line.



Healing infected tracheotomy incision.



Scars to each wrist due to past therapy. Note image (b) has fresh needle marks as well. Therapeutic procedures should not be mistaken for injuries.



Small tear of the upper frenulum due to vigorous resuscitative efforts by an untrained person. Note the small bruise to the left side of the face, which had been caused by a fall several days earlier. The first phase of resuscitation was captured on a department store video camera when this child became lifeless following a seizure.



This case involved an infant who suffered an asphyxial death. He was found with his head compressed (wedged) between an adult bed and a wall. He was pulseless, apneic, and asystolic, and despite resuscitative efforts could not be revived; (b) depicts the frontal and temporal regions of the scalp with two ill-defined contusions within the frontal subgaleal region; (c) shows the relationship between the mattress and the wall. The mattress was separated from the wall by at least several inches, allowing the infant to fall into this space and become compressed; (d) is a view looking toward the floor, where the infant was found lying wedged between the wall and the mattress.





This child was brought to the Emergency Department (ED) by parents who spoke a foreign language. The child was reported to be found dead in a crib. The ED physicians believed that this death could be a result of SIDS but there was no initial scene investigation. Note the posterior patchy red lividity. There is also a faint Mongolian-type birthmark within the left gluteal region. Further scene investigation by the Medical Examiner's office and police department revealed that the child had actually slid between the crib railing and mattress, suffering an asphyxial death. There were no marks on the child's body at autopsy. The mattress was from another crib and was slightly smaller, allowing the child to slide between the railing and mattress. Note the doll demonstrating how the child was found at the scene.



This image demonstrates brain swelling with flattening of gyri and obliteration of sulci due to hypoxic-ischemic brain injury. This 7-month-old female infant was found unresponsive in a car seat that fell off of an adult bed, with her chin tightly opposed to her chest, satisfying the criteria for positional asphyxia. She survived for several days and was ultimately declared brain dead. No other injuries were identified upon autopsy examination.



This 9-month-old child with a history of asthma was found unresponsive in her crib. Autopsy demonstrated multiple mucous plugs within the medium-sized airways, along with well-defined pathologic features of chronic asthma. No injuries were found. Death was certified as complications of bronchial asthma. Although unusual in a child this young, asthma can indeed be fatal. These bilateral vertical incisions made at the time of autopsy failed to demonstrate contusions.

This was the body of a completely healthy female infant. Her mother, who had left her unattended for an unknown period of time with her 18-month-old brother, found her submerged in a bathtub. The mother reportedly left them both in the tub without water and claimed the brother had to have turned on the faucets. When police attempted to reconstruct the scene, the older brother was unable to turn the faucets. Although the cause of death in this case was certified as drowning and the manner homicide, the mother was released on probation.



This normally developed neonate was delivered with the placenta enclosed in an intact amniotic sac. The baby died of asphyxia and the manner of death was certified as natural. The child was delivered at home and the young mother did not have medical knowledge to know that the membranes had to be immediately opened following delivery. She noted the child to be moving within this placental unit.



It is important to examine the frenulum and mouth region internally and externally in infants to rule out possible findings associated with smothering. Both of these cases show no injuries.



Healed frenulum laceration. This individual fell as a small child and accidentally struck her face on a kitchen cabinet.



Intact frenulum with postmortem drying of the lips. This does not indicate child abuse.















These children have varying degrees of abrasions to their face with trauma to the lips and torn frenula. All are cases of homicidal smothering. It is important to also realize that a homicidal smothering may occur without leaving marks of any kind.



These images demonstrate a case involving a several-month-old infant who was found unresponsive in her crib. She had no known previous illnesses. If possible, it is always important to photograph infants in their original clothing, which allows for more accurate reconstruction of the terminal events (i.e., stains of blood-tinged fluid.) View (a) demonstrates clear fluid emanating from the left nostril with a faintly frothy quality, probably indicative of pulmonary edema, which is a common finding in victims of SIDS, particularly when attempts are made to resuscitate. The elastic nature of infants' lungs and the vigorous resuscitation efforts collectively contribute to the formation of this edema fluid, which is often blood-tinged due to rupture of small capillaries. Oftentimes, the blood-tinged fluid is misinterpreted by police personnel as being suspicious of foul play. It is important for pathologists and emergency medical services (EMS) personnel to educate people with nonmedical backgrounds regarding the distinction between blood-tinged edema fluid and actual clotted blood.



This case involved sudden death in an otherwise healthy infant. Notice the confluent burns and abrasions on his left anterior chest wall, extending to the midline (a). These marks are indicative of defibrillation attempts from resuscitation. Additional therapeutic interventions can be seen, including an endotracheal tube, along with electrocardiogram (ECG) electro pads. Notice also the blotchy red discoloration of the forehead and face (left side slightly greater than right). While one might be tempted to conclude that this is livor mortis, it is important to realize that vigorous resuscitative efforts may also alter the patterns of vascular congestion; in the same case, (b) demonstrates an intact upper frenulum with dried blood-tinged secretion around the left side of the mouth and no trauma.



This infant was found unresponsive in his crib and could not be resuscitated. Maternal history was significant only for group B streptococcal infection. This picture depicts prominent petechiae on the anterior capsular surface of the thymus. Petechiae involving the thymic, visceral pleural, and epicardial surfaces are extremely common findings in sudden infant deaths, including deaths that have been ascribed to SIDS (up to ~85 % of SIDS fatalities). The precise mechanism underlying the formation of petechiae remains elusive, but is believed to be related to the negative pressure created by terminal gasping in infants. However, it is well known that these petechiae are not in any way specific or pathognomonic for SIDS and may be found in deaths due to many other causes, including definable natural disease conditions, accidental injuries, and inflicted injuries (homicides). In this case, the petechiae, which appear as pinpoint hemorrhages, are particularly striking.



This is a view of the thoracic contents of an infant who was found unresponsive while sharing a bed with his mother while in a supine position. She called 911 and paramedics arrived to find him apneic and pulseless. He could not be resuscitated. Pertinent history included prematurity, maternal group B streptococcal infection, and a recent upper respiratory infection. The only significant findings at autopsy were a moderately cellular mononuclear leptomeningeal exudate consistent with a viral meningoencephalitis. However, there was no significant brain swelling. This fatality occurred in the early to mid-1990s, and the death was ascribed to SIDS. If a similar case were encountered today, bedsharing in an adult bed would probably be listed as a risk factor in part two of the cause of death statement and the manner of death would be undetermined. This picture depicts prominent petechiae on the anterior epicardial surface of the heart.



This case involved an infant who was born prematurely at 35 weeks gestation and was found prone in a bassinet with his face between a “covered” adult-sized pillow and the corner of the bassinet. The findings of this case were not sufficient to render a diagnosis of mechanical asphyxia, but asphyxia was of sufficient concern to denote the cause of death as sudden unexplained death in infancy and the manner undetermined. This picture shows sparse, inconspicuous visceral pleural and thymic petechiae, which were the only gross findings at autopsy.



View of the mediastinal surface of the left lung (a) demonstrates confluent subpleural hemorrhages within the lower lobe, likely an artifact of vigorous cardiopulmonary resuscitation (CPR). Note the way the hemorrhages conform to anatomic boundaries, similar to what is observed in aspiration of blood; (b) demonstrates the costal surface of the lung, with blotchy subpleural hemorrhages, some slightly larger than petechiae. Note also the confluent congestion within the posterior aspects of the lung, most likely a result of postmortem hypostasis, or settling of blood due to gravity.



This was a case involving the enigmatic death of a 2-year-old child who was previously completely healthy. She had finished a course of amoxicillin for otitis media 3 days prior to her death. On the day before her death, she apparently fell off a "teeter-totter" and struck her head on the ground, which was a muddy, grassy surface, but she never lost consciousness and experienced no mental status changes. She could not be aroused from an afternoon nap and could not be resuscitated by pediatric life support protocol. The gross autopsy findings were unrevealing, including absence of injuries of scalp, skull, and brain. The only finding in addition to thymic, epicardial, and visceral pleural petechiae (b) was fibromuscular hyperplasia of the atrioventricular (AV) nodal artery, which was discovered by an expert cardiac pathologist who consulted on the case. This picture depicts a posterior neck dissection (a), demonstrating soft tissues and skeletal muscles that are entirely free of injury. In this case, anterior neck dissection was negative for injuries as well; (b) depicts prominent epicardial petechiae on the anterior surface of the heart. This case illustrates that the findings of intrathoracic petechiae are not confined to infants but can also be seen in young children.



This child died of complications of dehydration following a prolonged viral gastroenteritis. Note the sunken eyes.



Poor skin elasticity (turgor) is demonstrated in these infants who were refrigerated in the morgue overnight. These infants were shown not to be dehydrated by vitreous analyte determination and antemortem hospital chemistry testing. The poor skin elasticity in these cases is due to the congealing of fat as a result of postmortem refrigeration.





Mongolian spot. This is a birthmark and is sometimes mistaken for a contusion. During the time of autopsy it is easy to differentiate between the two by making an incision and documenting the presence or absence of underlying hemorrhage. The author has had at least one case where a contusion was demonstrated subjacent to a Mongolian spot.



Recent contusion.



Old contusion.



While performing autopsies on suspected child abuse cases it is important to be very thorough and it is recommended to incise the extremities and back to further document deep contusions, particularly in darker-skinned children. When examining the rib cage it is important to strip the pleural surface, separate each rib and evaluate each one separately. It is also good practice to do a posterior neck and back dissection while examining each rib as well.



This figure demonstrates how the body is sutured prior to funeral home release.



This 2-year-old child was brought to the ED by his mother's boyfriend after he was found unresponsive. The only observed external injury was a small faint contusion to the child's forehead. Autopsy revealed a fracture of the lumbar spine with a transected descending thoracic aorta and an old healed fractured clavicle. This picture demonstrates bilateral hemothoraces.



Right hemothorax due to aortic transection.



Image (a) demonstrates the volume of blood collected from the bilateral hemothoraces (approximately 165 mL in total). In a case such as this, the mechanisms of death are probably multifactorial, including not only blood loss but also a component of spinal cord or sympathetic nervous system dysfunction; (b) depicts transected free ends of lacerated descending thoracic aorta, marked with arrows; (c) is a panoramic view of lumbar fracture, which resembles a "hinge" at L1-L2.



This child died from multiple blunt force injuries. (a) Note the hand pattern with parallel contusions across the child's face. The contusions are more obvious when depicted following the intermastoid incision and scalp reflection (b). Note the excessive dark red blood clot at the inferior portion of the side of the head. Also note that this is not as visible when viewed from the external skin surface. Deep contusions may be difficult to see when viewed only from the external surface of the body; (c) demonstrates the same child approximately 2 days after autopsy. Note that the characteristics of the facial bruises have changed slightly due to the extended postmortem interval.







This child sustained multiple blunt force injuries to his head, back, and extremities (a–b). The child's hair was traumatically pulled from his scalp (c). Note the multiple angulated red to brown abraded contusions on the child's back (d), consistent with a belt buckle strike. Also note, following incision of the back and extremities during autopsy (e), the large degree of red bruising within the subcutaneous soft tissues of the back. Note the pale yellow subcutaneous tissue within the posterior compartments of the lower extremities, which are atraumatic and without hemorrhage.







Note the multiple therapeutic interventions documented at autopsy. This documentation is important to help prevent misinterpretation of therapeutic intervention as injuries.



This case demonstrates a sutured right-sided scalp incision as part of a craniotomy for evacuation of a right-sided subdural hematoma.



Superior view of the calvarium (a) illustrating marked widening of the coronal suture (diastasis) due to brain swelling, along with a right-sided craniotomy window; (b) right side of face and skull, including craniotomy window. Marked diastasis of the coronal suture is also seen; (c) residual right-sided subdural hemorrhage and marked brain swelling, characterized by complete flattening of gyri and effacement of sulci on the cerebral convexity of the left cerebral hemisphere. The inner surface of the left vertex dural leaf is blood-stained.



Formaldehyde-fixed portion of dura mater from an approximately 4-month-old infant with a history of tetralogy of Fallot who was found unresponsive by his mother's boyfriend. The boyfriend claimed that he had fallen approximately 3 feet from a couch onto a carpeted floor. Such explanations are often incompatible with the spectrum of injuries observed at autopsy. In this case, the adherent, thin-layered, clotted subdural blood indicates a duration of approximately 3–4 days following the injury, which correlates with the survival period of this infant after being found unresponsive. (b) Illustrates the fixed, markedly friable, fragmented brain attributable to marked hypoxic-ischemic injury, and is therefore a nonspecific finding, as it can be seen within the setting of hypoxic-ischemic brain injury of any cause.



Cross-section of the optic nerve in an infant found to have unilateral subdural hematoma and brain swelling, who underwent evacuation of the subdural hematoma. The infant never regained consciousness and was declared brain dead approximately 3 days following the surgery. Optic nerve sheath hemorrhage is correlated with retinal hemorrhages, although it is not specific for inflicted injury , and may be seen in conditions of sepsis, hemorrhagic diathesis, and other rare natural conditions.





Note the vague pattern contusion of a fist on the anterior chest in this child-abuse fatality. This child died of multiple blunt impact injuries and was discovered dead at the scene in full rigor. No resuscitation was performed.



Antemortem contusions associated with child abuse combined with superimposed perimortem contusions associated with resuscitation. The resuscitative injuries overlie the sternum.



This demonstrates saw cuts through the floor of the anterior cranial fossa (orbital plate of the frontal bone) prior to removal of the eye with its attached optic nerve.





Note the optic nerve sheath hemorrhages. Both of these images demonstrate optic nerve sheath hemorrhages in small children who died from shaken-impact syndrome. Histopathology revealed retinal hemorrhages. There was no evidence of natural disease including coagulopathic syndromes or connective tissue disorders.



The first image of this child-abuse case demonstrates vague contusions on the child's forehead. Reflection of the scalp shows much more prominent soft tissue (subgaleal) hemorrhage.



Child abuse case with reflected scalp demonstrating contusions and underlying linear skull fracture.









This child was visiting his grandfather with his parents from another country. The grandfather's apartment was not made "child-safe" prior to the visit. The toddler was standing and rocking a large old wooden television back and forth on a stand that was missing several screws. The television toppled over and crushed the child's head. Note the fracture pattern to the skull indicating a crush-type injury. Also note the photograph demonstrating the top of the skull reflected with underlying dura mater still overlying the brain with epidural hemorrhage. The fractures involved the temporal, frontal, and parietal bones and there was severe brain injury with brain swelling and herniation.



Note the large contusion to the side of the child's face from being punched.



This child was the victim of an assault and suffered a skull fracture with brain injury that caused his death. Note the area of hemorrhage to the mastoid portion of the scalp demonstrating "battle sign."



Child abuse case with comminuted skull fracture. This was most likely produced by flinging the child in a downward trajectory, and striking the child's head against a hard countertop. A fracture of this nature would take tremendous force to produce.



This demonstrates the top portion of the skull (calvarium) removed during autopsy with the dura mater still attached and clotted, partially adherent, subdural hemorrhage. Clotted adherent red-black subdural hemorrhage indicates an injury age of approximately 2–4 days.



This is the top portion of the skull with adherent clotted subdural hemorrhage involving the left vertex dura (overlying the left cerebral hemisphere) with portions of dura mater separated at the posterior temporal-parietal-occipital regions, adjacent to sites of skull fracture.



Portion of formaldehyde-fixed dura mater saved for further neuropathologic evaluation. Note the adherent clotted, black-brown subdural hemorrhage.



Formaldehyde-fixed portion of spinal cord removed with the dura mater demonstrating subdural hemorrhage. It is important to remove the cervical spinal cord as carefully as possible during the autopsy process in order to avoid potentially troubling postmortem artifact.



This shows the top portion of the skull (calvarium) being unroofed during the autopsy process for removal of the brain. Note that the dura mater is still adherent to the inner aspect of the skull (endocalvarial surface). There is a large left-sided adherent clotted subdural hemorrhage. There is diffuse cerebral swelling with flattening of the gyral configuration and obliteration of the sulci. There is patchy subarachnoid hemorrhage, which is greatest over the left cerebral hemisphere.





Close-up views of brain swelling with flattening of gyri and obliteration of sulci in a child who survived several days following blunt force trauma due to homicidal violence.













This child sustained multiple posterior rib fractures after being stomped by an adult while lying face-down on the floor. The fractured segments of the ribs penetrated the posterior aspect of the right lung, producing extensive pulmonary and intrathoracic hemorrhage. There were also large lacerations to the posterior aspect of the liver and heart.



X-ray showing multiple recent rib fractures.



These images demonstrate multiple lacerations involving the mesentery, mesocolon, and peripancreatic soft tissues following blunt abdominal impacts associated with homicidal violence.



This 2-year-old child was found by a caretaker unresponsive in the bathtub. An autopsy revealed confluent subgaleal contusions, essentially spanning from ear to ear, along with brain swelling, although the skull was intact. Death was attributed to blunt impacts to the head with brain swelling. A component of drowning cannot be ruled out in this case. The defendant, a casual acquaintance of the mother, was convicted of second-degree murder and sentenced. Note the bilateral intraosseous catheters, used while attempting to resuscitate this child even though he was slightly over 2 years old. This image depicts the face and anterior trunk of a child with patchy contusions involving the forehead and the left paramedian aspect of the anterior chest wall. Multiple therapeutic interventions are also present. As stated previously, differentiating between the effects of therapy and antecedent injury can be problematic, and the two processes may coexist.



This depicts lower trunk and lower extremities of child, with multiple therapeutic interventions including transverse cutdown sites within both groins, bilateral intraosseous catheters, and a right groin catheter.



This image shows the perineal area of this child (a). No injuries are detected. (b) depicts the child's anus. No injuries are demonstrated. In cases such as these, it is good practice to document photographically the presence or absence of injuries, as the multiplicity of injuries may be one of the determining factors in the ultimate sentencing. Sometimes external examination may be difficult and mucosal folds may be misinterpreted as lacerations. If there is any question as to the nature of a possible lesion or injury, we recommend removing the region en bloc, opening the anorectal segment and photographing it for documentation.



These images demonstrate sexual abuse in a young child. Note the abrasions and lacerations around the anal region. En bloc dissection of this region with the anal-rectal segment of the intestine removed. Note the internal lacerations near the anal border and the intestinal hemorrhage



Superficial, healing, criss-crossed, linear abrasions due to rubbing of Velcro jacket patches on each side of this child's neck. This indicates rough handling. This child was later killed by multiple blunt impact injuries during an assault. Note the suture and fresh needle marks at the right chest from a removed subclavian line.



These are multiple scars, many of which were associated with chronic child abuse. When evaluating old injuries, it is important to take into context the child's age and developmental status. A child who is able to run and jump about may fall and sustain blunt-impact injuries. Sometimes it may be difficult, if not impossible, to formulate the nature of such old injuries without history or witnesses. (a) and (b) images are associated with abuse; (c) and (d) represent healed scars from accidental injuries. Note the healing injury at the nose associated with a nasogastric tube and therapy.



This demonstrates a coronal section of a humerus. Microscopic sections of long bones may be sampled in cases involving a suspicious death of an infant or young child in order to identify transmetaphyseal fractures in situations in which shearing forces have been applied (i.e., violent shaking). Unlike the case in more obvious fractures with extensive visible hemorrhage, these fractures (alternatively referred to as "bucket handle" or "corner" fractures on radiologic plain films, depending upon the view), may sometimes be more readily documented with microscopic examination.





Old healed rib fractures from a case of battered child syndrome.



These x-rays demonstrate healing fractures.



Osteogenesis imperfecta with multiple fractures. This may or may not indicate child abuse. Fractures may occur with very little force.



Inca bone skull anomaly. In both of these cases it was mistaken for a skull fracture. The x-rays at the bottom correspond to (b).



This child was retrieved from the back of a garbage truck partially tied within a torn plastic bag following compression by a trash compactor. Note the confluent hemorrhage to the scalp and the largely empty cranial vault. This child was mildly to moderately decomposed with bloating and separation of tissue planes. The brain material was squeezed from the cranium through the neck following compression of the head by the compactor. When the initial Y-shaped autopsy incision was made to the skin of the trunk, brain material leaked from the chest region (d). The child's body was found mixed with decomposing food material. Note the green discoloration from putrefaction.



Late-second-trimester pregnancy demonstrating the uterus (a), placenta (b), and fetus (c).



Second trimester stillborn with omphalocele, illegally aborted following administration of drugs given by a nonmedical practitioner. Note the x-ray and the sunken lungs at the bottom of the water container indicating no breaths were taken.



Lungs from a live birth that were expanded with air. Note how they float on top of this water bath. Admittedly, the "flotation test" to confirm independent respiration is far from foolproof and is subject to a number of artifacts and exceptions, thus limiting its utility in resolving the question of live birth versus stillbirth.



First-trimester pregnancy.



Brown fat.



Early first-trimester pregnancy.

Blunt-Force Injuries

6

CHARLES A. CATANESE

Introduction

These are injuries produced when the body is struck with, or strikes, a blunt object. A blunt surface produces injuries by scraping, tearing, shearing, or crushing. This is in contrast to a sharp force injury, which cuts and separates the tissue as it penetrates. What injuries result from trauma are a balance of the amount of force, the area over which it is applied, and the duration of force. In general, the greater the force, smaller the area, or shorter the duration over which the force is applied, the greater the injury will be.

Blunt objects have a relatively large surface area in contrast to sharp objects, where the cutting edge has a relatively small surface area. It takes much less force to penetrate the skin with an ice pick than with the end of a baseball bat. Examples of blunt objects are fists, shoes, pipes, bricks, bats, hammers, roadways, sidewalks, cars, trains, airplanes, walls, etc. Types of blunt-force injuries include *abrasions, contusions* and *lacerations*. These may occur separately but are often present at the same time. As an example, an injury maybe described as an abraded contusion with central laceration. *Fractures* are breaks in the bone as a result of blunt force. *Avulsions* are splits in the soft tissue or soft tissue planes with or without a laceration as a result of shearing forces.

Abrasions

Abrasions are simply scrapes. They are produced as the body contacts a surface and rubs across it with sufficient force. The distance of travel can be very short (falling and scraping your knee) or very long (being dragged under a car). It is often possible to determine the direction of impact. Layers of skin are scraped away and bead up at the margin where the contact to the wound last occurred. Fragments of skin beading up at the inferior wound margin indicate a downward impact. Antemortem abrasions or those that occur during life are typically red to brown and will eventually form a scab with dried blood. Postmortem abrasions are yellow in non-lividity-dependent areas. In general, one needs a beating heart with blood pressure to produce hemorrhage and a red to brown discoloration. A postmortem scrape in a lividity-dependent region will appear red and may be difficult to differentiate from an antemortem injury.

This is important in certain cases. Lawyers will argue different ways to create reasonable doubt. For example, some may argue that an injury occurred during resuscitative efforts in the hospital, or the body was dropped from the stretcher in the morgue. Some other arguments may include: he was dead already when the second car hit him, the other perpetrator shot the body after he was dead, the child had no injuries before entering the hospital, etc.

Abrasions may also change character with increasing time. For example, initial examination of a body retrieved from water may reveal no or much less obvious injuries due to the moisture from the water at the skin's surface. As the body is stored in the morgue overnight and allowed to dry, the abrasions will darken and may become much more apparent.

Contusions

Contusions are simply bruises. These are produced following an impact where the soft tissues and blood vessels, underneath or within the skin, are torn and produce hemorrhage. Grabbing an arm tightly can produce bruising with minimal impact and greater crushing force. One needs a beating heart and blood pressure to produce a contusion. A postmortem impact may accumulate blood due to lividity in a gravity-dependent area. This type of postmortem artifact may be difficult to differentiate from an antemortem injury.

One must exercise great care when dating contusions at the time of autopsy with gross findings alone. One must account for skin color, whether the contusion is deep or superficial, the presence of hematoma, etc. Bruises go through various color changes with advancing time as the body reacts to repair the injury. This depends on the size of the injury, the physiologic state of the individual, including his or her immune and coagulation systems, the vascular efficiency adjacent to the damaged tissue, etc. Color changes range from light blue-red to dark purple then green to yellow-brown as time progresses. Inaccurate interpretations of dating contusions grossly can create significant problems in court. If one sees a variability with color ranges demonstrating some bruises as red-purple and others as yellow-brown, it is reasonable to say that some injuries are older than others. It is much more accurate to use histopathology to date the injuries using established time ranges for advancing inflammation and healing. Random sections of injuries should be taken including the wound margins. The first several hours reveal hemorrhage with no inflammation. This is followed by iron deposition as a result of hemoglobin breakdown. Estimation of injury dating should be given in ranges.

Bruises can also change appearance as the postmortem time interval increases. A contusion will become more obvious as blood settles away from the impact site. The surrounding tissue will become paler and the contusion will be more pronounced, as in a supine body with anterior contusions in full livor. Bleeding associated with a contusion does not settle away from the impact site as lividity forms, because it is spread throughout the soft tissues and cannot drain within the vessels. Also, during vigorous emergency room resuscitation, the head and upper trunk may become congested. As lividity settles to the back of the head, injuries to the face become more prominent. Clinicians may sometimes miss these subtle contusions.

It is also important to realize that deep contusions may not be visible at external exam and may be visualized only after incisions are made. Clinicians should realize this and create a medical record that is as accurate as possible. If one documents that no bruises are present to regions of the body, yet they are found on autopsy, this may potentially weaken the case in court. The autopsy remains the most accurate way to demonstrate these findings.

Lacerations

Lacerations are tears of the skin, soft tissues, or internal organs or vessels as a result of an impact, overstretching, or crushing-type forces. These injuries are characterized by irregular margins, often with a marginal abrasion, with tissue bridging by fibrous strands and small blood vessels. If the laceration is large and gaping, tissue bridging may not be present due to the strands' being pulled apart. Skin lacerations tend to occur more often over hard surfaces, such as the scalp, knees, elbows, etc. The direction of the impact can be determined by the presence of soft tissue undermining. The underlying soft tissue adjacent to the laceration may form a pocket of separation extending in the direction of impact. A downward impact will produce undermining at the inferior aspect. These directions should be described with reference to standard anatomic planes.

Motor Vehicle Injuries

Motor vehicles include any motorized means of carrying or transporting someone. These include trucks, buses, cars, motorcycles, mopeds, snow mobiles, etc. It is always important to be as accurate as possible, including the *type of vehicle* on the death certificate for vital records. The type of vehicle is obviously important when evaluating injuries.

It is important to recognize various patterns that might help *differentiate drivers from passengers*. In high-speed collisions with unrestrained occupants, people may be ejected from the vehicle. If criminal or civil charges are filed, the living driver may indicate that the dead passenger was driving.

One should look for steering wheel impact marks to the chest, seatbelt-related abraded contusions, and pattern injuries associated with impacts to the windshield, dashboard, or vehicle roof. *Front and back windshields* are often made of laminated glass and fracture with elongated curves or splinters. *Side windows* are often made of tempered glass and fracture into small cubes. Seatbelt-patterned injuries or side impact dicing pattern injuries to the right or left side of the head will help formulate opinions about an individual's seating position. Dicing injuries to the left side of the head of an individual found next to a car with a broken left side window is evidence that he or she was the driver. One could also collect DNA samples from these regions and compare it with ejected occupants. Those not wearing seatbelts are much more likely to be ejected from the vehicle, especially in a rollover accident. Those who are ejected may impact other objects (such as a tree or pole) or may sustain crush injuries due to the vehicle's rolling over them.

Pedestrian clothing and impact sites to the body can reveal many clues with evidence about the circumstances of a collision. Questions one should ask include: Was the pedestrian standing or lying in the street? Was the individual run over or run under by the vehicle? Was more than one vehicle involved? Impact sites may reveal different front grill or tire pattern injuries. With standing pedestrian impacts, one should measure the distance between the impact site and the bottom of the foot or shoe the pedestrian was wearing at the time of the incident. It may be necessary to incise this region to visualize it better. It is good practice to include the measuring stick in the picture. This may give insight into whether the vehicle was braking before the impact occurred. As a driver jams on the brakes, the front end of a car will go downward. Fractures may occur to weight-bearing legs. Fracture patterns may be difficult to interpret when the bone is splintered and fractured into many pieces. Generally speaking, as a force passes through a bone, the fracture pattern extends outward from the impact site similar to a skull fracture from an entrance gunshot wound producing internal beveling. With posterior standing impact, one might find stretch marks at the inguinal region opposite the impact site. This is caused by hyperextension of the hip and leg in an anterior direction.

Slow-moving vehicles tend to run over people. Fast-moving vehicles tend to run under people, meaning after being struck, the victim is tossed onto and over the hood. Flaps of skin may be torn away as a tire passes over a body. The clothing may yield significant evidence such as paint fragments. The car may have fragments of blood and hair that can be used for DNA analysis. This can be useful when there are multiple pedestrians and cars involved in collisions. Many pedestrian collisions involve children, who are sometimes impulsive and careless and may run out into oncoming traffic; the elderly, may not be quick enough to get out of the way; or individuals who have psychological histories, such as the homeless, or intoxicated individuals, who may think it's not that dangerous to cross a busy freeway.



Recent antemortem abrasions.



Recent deep antemortem abrasions.



Large yellow anemic postmortem abrasion.



Recent contusion of the left hand associated with a fist fight. This individual punched the attacker before being murdered.



Damaged fingernails with nail bed contusions. Blunt-force injury during struggle.



Recent purple contusion of arm.



Older yellow-brown contusion.



Multiple abrasions and contusions of face. Note the bilateral periorbital ecchymosis associated with fracture of the anterior cranial fossa. This is also known as "raccoon eyes." A similar injury is Battle's sign, hemorrhage behind the ear, also a sign of basilar skull fractures. Figure (c) demonstrates a basilar skull fracture.



Recent laceration with adjacent abrasion. Note the irregular margin at the point of skin separation due to the skin's ripping or tearing apart.



Recent laceration of scrotum.



Large recent abraded contusion at the back of the head with a stellate laceration. This individual was intoxicated at a party on a rooftop. He was taking a group photograph and while backing up accidentally fell three stories to the pavement below. He had a comminuted skull fracture.



These are multiple recent lacerations and contusions at the inner aspect of the mouth following multiple blunt impacts to this individual's face with a fist.



This is a postmortem anemic laceration in an individual who was stabbed to death in an apartment and later thrown out of a window.



This decomposing body has skin slippage with separation of scalp hair. Note the scalp lacerations with slight to moderate decomposition.



This individual was struck by a train. Note the soft tissue avulsion underneath the intact thick skin.



This individual died of multiple homicidal blunt- and sharp-force injuries. These are scalp lacerations in an individual with moderate decomposition. Note the extensive drying of the wound margins with clotted blood and fragments of hair. Also note the separation of the scalp from the skull with sub adjacent fractures.



Note the recent abraded contusion to the middle aspect of the chest (a). This individual had multiple layers of clothing and was reportedly stomped on by an individual with heavy boots following assaults with other weapons. The abraded contusion to the middle aspect of his chest forms a rough outline of a boot (b). The multiple layers of clothing prevented a more discernable defined boot pattern. The individual had a fractured sternum and a cardiac contusion (c).







Pattern injuries associated with impacts from the bottom of a shoe while being stomped and kicked.



This individual was assaulted with fists and a metal pipe or rod. Note the parallel linear contusions at the posterior aspect of the left thigh (a). Depression of the soft tissues contacting the rod causes stretching at each margin with blood vessel injury and parallel linear bruises.



This individual was struck multiple times with a putter golf club. Note the pattern injury at the forehead and face, with the shaft of the club extending at the inferior aspect.



This individual was assaulted by multiple people with bottles and a baseball bat. These abraded contusions at his face and head are characteristic of a baseball bat impact. Note the oval contusion with sparing of the central aspect with overlying abrasion. Also note the abraded central region.



This elderly women had a history of an unsteady gait associated with Parkinson's disease and remote stroke. She was found in her apartment with several impact injuries to her scalp. It was initially thought by investigators that she had fallen several times and possibly suffered a heart attack. Further examination of her scalp revealed more lacerations and impacts that were initially not observed at the scene due to poor lighting and dried blood matted in her scalp hair. These scalp lacerations were produced by being struck with a hammer head.







Depressed skull fractures due to multiple impacts with the head and claw of a hammer. Standard household hammer heads have a diameter of 3/4 to 1 inch, and the injuries on the skull tend to reflect this.







This individual was assaulted by multiple people including one with a bicycle chain. These injuries are characteristic for bicycle chain impacts.





This individual was found naked from the waist down in an abandoned pipe yard. She had multiple defects to her scalp with exposed bone and extensive maggot and animal feeding. Careful inspection of the skull revealed a 1/4″ linear fracture of the superior temporal bone with a 1/16″ roughly square indentation. Further investigation of the scene revealed a board with a nail at the other side of the yard. Further testing confirmed this was the murder weapon.







This psych patient had a history of swallowing miscellaneous objects. The blunt side of this toothbrush, in conjunction with peristalsis, eroded through the intestinal wall. This person died of peritonitis with septic complications.





Pierced ear lobe with sociopathic pirate earring.



This is a homicide case where the individual had her earring torn from her ear lobe during the assault.



Note the slit elongation of the piercing site from wearing very heavy earrings. Also note the healed linear scar to the left due to a traumatic tearing of the earring from the ear lobe with complete separation and nonplastic-surgical repair.











These are various examples of recent bite marks with different placement of the mouth while exerting pressure and different degrees of force applied. Note some patterns are very vague and others are extremely prominent. The typical example of a bite mark reveals a circular pattern with a central region of contusion. It is good practice to consult a forensic dentist as soon as possible whenever a bite mark is suspected. The injury should not be cleaned until swabs are taken to detect oral DNA left behind from the perpetrator. As time goes on with drying and decomposition, the injury may yield less valuable information for dental comparison and DNA analysis.



Image (a) demonstrates both a recent and a healed bite mark. The old bite mark is largely healed with hypo-pigmented deep abrasions from teeth dragging across the epidermal surface.



This individual and her roommate were found in their apartment with multiple blunt- and sharp-force injuries. Note the roughly semicircular lacerations at the superior and inferior aspect of the cheek, with the deeper lacerations of the lip revealing exposed underlying teeth. There was a large cylindrical storefront padlock within a tube sock found at the scene. There were multiple other pattern injuries to the decedent's body consistent with these roughly circular impacts.



Note the furrow indentations associated with extremities bound by rope and cord prior to the victim's being stabbed to death.



This individual suffered a witnessed fatal cardiac event while standing. While falling to the ground he sustained this pattern injury by striking his head on a radiator.



This individual suffered a fatal cardiac event while riding on an escalator. He was found lying at the bottom of the escalator. Note the pattern injury to his arm from the continued rubbing of escalator treads.



This individual impacted a fence at a high rate of speed, leaving a pattern injury from the top of the fencepost's contacting his chest.

This individual was an unrestrained passenger in a motor vehicle during a head-on collision. His face went through the front windshield. He sustained multiple curvilinear lacerations and sharp-force injuries from broken glass and impact with the car roof. This type of pattern is consistent with a front windshield impact.









Note the dicing type injuries to the scalp with cubed fragments of glass embedded in the injuries. This type of injury is consistent with an impact and fracture of tempered glass, which is present in many side windows. These individuals were passengers with left-door-window head impact.



This individual was the passenger in a front seat collision. Note the abraded contusion from his seat belt.



Note the abraded contusion at the chest and arm of this individual from a steering wheel impact. He was the driver of this car in a multiple-fatality vehicular accident.



This was the driver of a car in a motor vehicle accident. Note the abraded contusion from the seat belt.





These demonstrate a transection of the aorta in the proximal descending region just distal to the ductus ligatosum. This is a common location of laceration.







This photograph demonstrates an individual who was struck at a high rate of speed and hit the pavement with great force. Note the exposed comminuted skull fracture with brain material.



These pictures of a car show an impact from a pedestrian who was struck and run under. Note the fragment of scalp with hair embedded in the top part of the windshield and adjacent car roof. The driver of this car initially fled the scene.



Pedestrians struck by cars with grill pattern injuries.



Motor vehicle accident with decapitation.



This is another pedestrian who was struck by a car. Note the tibial fracture at the weight-bearing left leg.







This individual was a pedestrian who was struck from behind by a car. Due to her dark skin, the contusions are not obvious from external examination alone. Incision of the posterior aspects of her leg reveal hemorrhage due to the bumper impact. It is good practice to photograph these impact sites with a ruler to demonstrate the distance from the decedent's heels. This can be matched to a particular car and to whether the driver applied brakes before striking this pedestrian. The front of the motor vehicle will go downward when the braking occurs.





These individuals were both struck by cars and dragged across the pavement. (a) shows yellow anemic abrasions that occurred after the first impact, where the decedent sustained extensive central nervous system injury and a transected aorta. He was thrown into another lane of traffic and dragged by another car. The anemic nature of this injury and yellow discoloration suggests decreased blood perfusion. The injury in (b) shows red to brown discoloration, which is significant for vital reaction in an individual who had an intact beating heart with blood pressure.



These are multiple examples of tire imprints from people who were run over by cars. In one case, the individual was thrown into another lane of traffic after being struck. The second car denied hitting the individual, but his tire pattern was a perfect match and there was forensic evidence found on the under surface of his car.



Individual trapped under a car with tire imprint to chest.







These individuals were run over by a motor vehicle while lying on the ground. Note the flap of skin being torn away from the thigh as the tire rolled over the leg.



These individuals were struck from behind by a car. Note the inguinal stretch marks caused by hyperextension of the hips and legs at the time of impact.



This fractured motorcycle helmet shows blood clot and brain material from an individual who fractured his skull after striking a pole.

















These figures demonstrate various subway fatalities where individuals were run over by trains. Note the separated body portions with extensive crush injury and axle grease from the train wheels.



This individual fell from the top of her steps and sustained multiple blunt-impact injuries including a femur fracture and a skull fracture. Note the slipper at the top steps.



This individual has a femur fracture. Note that the fractured leg is shorter and the foot is laterally rotated.





People with significant osteoporosis may fracture bones with little force. These two pictures demonstrate large areas of contusion and ecchymosis following a femur fracture secondary to a standing height fall.



Angulated irregular abrasions of back due to striking a gravel bed with great force.



This decedent jumped from a great height and fractured his right femur. Note the fractured bone protruding from the thigh. Also note the shortening of the right leg with lateral rotation.



Ring fracture. This usually occurs following a fall with initial impact to the feet or buttocks.



The decedent fell from a great height and landed on his feet. The fractured tibia was forced through the bottom of the foot upon impact.



This individual was placed in a garbage dumpster and left to decompose. The trash compactor in the truck was engaged before the body was observed. Note the garbage truck shovel laceration to the back (a). Also note the intestines forced from the anus following compactor compression (b).











This individual was shot in the head, processed through a trash compactor, and left to decompose. Note the flattening of the body with extensive blunt-force injury and fragmentation.







This individual slipped into a terrain leveler and sustained multiple abrasions, with blunt- and sharp-force injuries including extensive fractures and internal lacerations.



This individual had a severe blunt impact to his face that caused the atlanto-occipital ligaments to stretch and dislocate. This caused brainstem and upper cervical spinal cord injury resulting in asystole and apnea.



This picture of the base of the brain shows a medullary pontine laceration with extensive subarachnoid hemorrhage.



Comminuted skull fracture where the bone is broken into separate pieces.



Diastatic skull fracture showing the fracture site passes through a cranial suture.



Healing skull fracture.



Frontal and temporal contusional hematomas associated with a falling impact to the back of the head in an individual with liver disease.



Temporal lobe with multiple splinter-type hemorrhages demonstrating typical cerebrocortical contusions.



These images demonstrate gliding cortical contusions that typically occur near the white and gray matter junction following blunt-force head trauma.



Spinal cord with a region of purple discoloration and softening demonstrating a spinal cord contusion.



Epidural hemorrhage in an individual with a temporal bone fracture and middle meningeal artery laceration. Note the clotted blood at the surface of the dura mater.



Epidural hemorrhage.



This shows the dura mater stripped from the inner aspect of the calvarium. Note the clotted adherent epidural hemorrhage within the temporal region of the skull.



Acute right subdural hemorrhage.



Left subdural hemorrhage that is slightly older with clotted adherent blood.



This demonstrates an older, clotted, red, adherent, subdural hemorrhage with portions of rust discoloration and membrane formation.



This cerebral cortex demonstrates an irregular flattened surface caused by a chronic subdural hematoma. In contrast, a chronic epidural hematoma generally leaves a flattened and less irregular cerebral cortex deformation.



Old subdural hemorrhage with clear to rust-colored membrane formation. Note the membrane separation with beading up away from the midline caused by scraping a scalpel blade along the subdural surface.



Large antemortem subdural hemorrhage altered by excessive heat due to fire.



This brain demonstrates multifocal subarachnoid hemorrhage with subarachnoid hematoma at the base of the brain. This hemorrhage occurred following a blunt impact to the face causing hyperextension and rotation of the head with laceration of the right vertebral artery.
Source: Kindleburger D., Gilmore K., Catanese C., Armbrustmacher V. Subarachnoid hemorrhage due to internal carotid artery laceration following blunt impact to face with hyperextension and rotation of neck: A case report and review of the literature. *Journal of Forensic Science* 48:1366–1368, 2003.



This demonstrates a large subarachnoid hemorrhage in an individual who died several days following a traumatic head injury.



These brains are diffusely swollen with flattened gyral configuration and sulci obliteration. These individuals lived from several hours to several days after the initial insult.



Note the large areas of contusion with ecchymosis following minimal trauma in these individuals with chronic alcoholism, hepatic cirrhosis, and coagulopathy.



Lacerations of liver and kidney due to blunt-force trauma. Note that (c) and (d) have hepatic cirrhosis, which is less commonly associated with laceration due to fibrosis. A normal liver is the most common organ in the peritoneal cavity to lacerate (a) in association with blunt-force trauma.



This opened airway demonstrates a large piece of aspirated brain in an individual who was resuscitated following extensive blunt-force head trauma with comminuted skull fracture and communicating lacerations extending into the oral cavity. When Emergency Services arrived, the decedent was found in agonal respirations.



This cut section of lung demonstrates a small white to gray fragment in the parenchyma at the lower lateral aspect. Microscopic examination of this revealed intravascular embolic cerebellar tissue. This individual sustained a comminuted skull fracture with multiple central nervous system lacerations. He was vigorously resuscitated several times over the course of several hours. Brain tissue embolized through damaged blood vessels at the base of the brain.



Note the patchy red to purple discoloration indicating aspiration of blood in an individual with a gunshot wound to the head, lacerations extending to the oral pharynx and residual respiratory effort before death.



This is another pedestrian who was struck by a car and survived approximately 2 days in the hospital. Note the tibial fracture with adjacent abrasions and broken skin. There is also blister formation confined to this region associated with sepsis following infection associated with this trauma.

7

Sharp-Force Injuries

CHARLES A. CATANESE

Introduction

Sharp-force injuries are defined as injuries produced by an instrument with a thin edge or point. Examples of these instruments include a knife, razor, box cutter, scalpel, sharp-edged piece of metal, broken glass bottle, broken glass window, scissor, ice pick, fork, propeller, screw driver, saw blade, axe, machete, arrow, nail, pickaxe, spiked fence post, meat cleaver, etc.

A *stab wound* is typically made by a knife blade and is defined as having a greater depth of penetration than surface dimension. An *incised wound* is a slicing-type injury where the surface dimension is greater than the depth of penetration.

Accurate, concise, and organized wound documentation is important, as with all other injuries. Each injury should have a documented location on the body, including a description of adjacent abrasions or contusions, wound dimensions, depth of penetration, and direction of penetration into the body. All injured structures should be documented, including the amount of hemorrhage both in the wound track and within body cavities. In cases where there are multiple injuries, it is acceptable to group them with ranges. It is good practice to take overall photographs of the body before and after cleaning; as well as close-up photographs of each wound.

Important aspects concerning interpretation of injury involve pattern recognition. Familiarization with this will allow opinion formulation concerning correlation of a particular instrument to a particular wound. One example involved the arrest of several suspects with different concealed weapons. The police may approach you to render an opinion about what type of weapon produced injuries so they can focus their early investigation. In one actual case, each suspect had a different instrument in his or her pocket, including a flat-edged pocket knife, a box cutter, a screw driver, and a slightly bent serrated table knife. The injuries to the decedent's body consisted of slit-like perforations with multiple adjacent parallel linear abrasions. This pattern injury is consistent with a serrated knife. Many of the images in this chapter are designed to help with pattern recognition.

Location and Direction of Injury

This should be given with reference to a particular body position, usually standard anatomic planes. Each wound should be documented by location on the body's surface, and measured from vertical and horizontal planes of reference. An example of this would be from below the top of the head or above the feet, and to the right or left of the midline. Standard anatomic planes are demonstrated with the body in an upright position with the head tilted slightly upward, the legs together, the arms at the sides, and palms facing forward. The head is superior and the feet inferior, medial is toward the midline and lateral away from the midline. The anterior or front of the body includes the face, chest, and the palms. The posterior part of the body includes the back, buttocks, etc. The direction of the wound into or through the body should be given with reference to three planes when possible, front–back, right–left, and up–down. This is important because it allows one to correlate the injuries to possible assault descriptions and help discredit or substantiate statements.

Wound Dimension

This should be documented separately for each sharp-force injury, unless there are many that can be grouped together and described in ranges. Example: There are twenty 1-inch to 2-inch, by up to 1/4-inch, stab wounds within a 5-inch × 7-inch region at the middle aspect of the right chest, which is centered 13 inches below the top of the head and 4 inches to the right of the midline.

It is good practice to document the injury as it exists on the body and then again when in a relaxed state. The important aspect is to document the wound dimension in ranges that most closely reflect the actual dimensions of the knife blade or instrument. A stab wound can be put into a relaxed state by pressing the surrounding skin toward the wound and releasing the surrounding tension, or by placing tape over the perforation site to approximate the margins. It is also acceptable to cut a square around the surrounding skin to release the tension. The skin and underlying tissues are elastic, with different degrees of tension. This can make the surface dimension of the wound length and width slightly variable depending on location and orientation of the body. Cut marks through bone and cartilage may reflect accurate weapon dimension with tool marks and should be retained in formaldehyde.

This same concept applies for the depth of penetration, as well. Dimensions should be given in a range to account for changes in body position when examined on the autopsy table compared with the body position when the injuries were inflicted. Variables that may change this parameter while the assault is taking place include deep breaths or exhales, flexion, extension, rotation, the force used to inflict the injury, the location on the body including underlying bone or soft tissue, etc.

Adjacent Abrasions and Contusions

These may indicate body contact from the knife handle, lower part of the knife blade, or the knife hilt. This is important information in formulating an opinion as to how much force was needed to produce the injury. If the knife blade penetrates a bone and there are hilt marks adjacent to the perforation site, one can extrapolate that the knife must have been stuck into the body with great force.

Injured Organs or Structures

This information helps to allow interpretation of how functional one might be after an assault. The number and extent of internal injuries give insight into the nature of the assault and perpetrator.

For instance, “I stabbed him in the neck and he continued to chase me so I stabbed him again in the chest and abdomen.” If the neck wound injured the spinal cord, you know the statement is false because the victim would no longer have voluntary movement to part of the body, as with a tendon or peripheral nerve’s being cut. Also, depending on the structures damaged, the rate of blood loss may be quite variable. This would help define how fast the individual would lose blood, and what the individual might be capable of doing after the injury, and for how long. Questions like this may often come up in trial. A transected aorta would incapacitate someone more rapidly than a transected brachial (arm) artery, which would be more rapid than a transected cephalic (superficial) vein. Someone with a stab wound to the heart will often lose consciousness within minutes but still be capable of running away, defending themselves, or continuing an assault, particularly if the heart does not go into a lethal arrhythmia. It is possible for someone to get stabbed in the heart, run several blocks and shoot several people before dying.



Stab wound consisting of a flat slit-like perforation with minimal surrounding skin tension.



Stab wound with moderate surrounding skin tension. Note the separation of the wound margins.



Gaping stab wound consisting of an oval perforation caused by significant surrounding skin tension.



A non-serrated knife blade similar to the one used to inflict these wounds. It is important to take the surrounding skin tension into account when estimating the size and type of weapon used.



Incised wounds produced by a broken bottle.



Incised wound to the face produced by a knife.



Incised wounds produced by a box cutter.



These are multiple stab wounds to the back. Note the varying dimensions and gaping nature due to the varying degrees of skin tension from underlying tissue planes in different locations.



Several of these wounds were chosen based on estimation that they were more reflective of the actual knife blade size. These wounds were then cut into a relaxed state and re-measured to help estimate the actual size of the knife blade.



This is a close-up of one of the wounds that were cut into a relaxed state and measured. Note the sharp end at the left aspect and the blunt end at the right aspect.



Stab wounds to body with slight drying of the margins and a "linear extension" from one end due to the sharp part of the knife blade being dragged through the wound and across the body surface, changing the dimension of the injury.



These two images demonstrate a "swallowtail"-type injury where the knife was inserted into the body in one direction, turned and then removed in another direction, producing two angulated cuts. This type of injury may be produced by the movement of the perpetrator, victim, or both.



These stab wounds demonstrate adjacent abrasions from the hilt of the knife contacting the skin with great force.



Multiple self-inflected linear abrasions and incised wounds to the arms and wrists demonstrating hesitation marks in individuals who committed suicide with other lethal injuries.



Multiple linear incised wounds in an individual who lived for several hours. He died of a heart attack associated with the stress and blood loss from the self-inflicted injuries. The manner of death in this case was classified as suicide. The cause of death was listed as both multiple incised wounds and heart disease.



Multiple self-inflicted sharp-force injuries including stab and incised wounds. Note the tightly clustered orientation of these injuries, which is common in suicides.



Multiple self-inflicted stab wounds. This individual was found with her hands surrounding the knife handle in a moderate state of rigor mortis.







This individual was found with multiple clustered linear abrasions, incised wounds, and stab wounds to the wrists, arms, and ankles. She first attempted suicide by ingesting large quantities of acetaminophen, then inflicted the above sharp-force injuries. Note the erythema around the wounds, indicating vital reaction. There was blood noted all over the apartment. The individual later jumped out a window and died from blunt-impact injuries. The wounds shown are hesitation wounds.



Superficial linear abrasions caused by dragging a knife blade across the wrist and hand prior to committing suicide by hanging.



Multiple clustered self-inflicted incised and stab wounds located on each side of the neck and chest in an individual who committed suicide. Most of these stab wounds were very superficial in depth of penetration and can be described as hesitation marks. Three of these stab wounds to the chest entered the thoracic cavity and penetrated the heart and lung, causing death. Note the slight degree of decomposition with wound margin drying.



Multiple clustered homicidal stab wounds in individuals who were also bound during a sexual assault. Note the location of the multiple stab wounds to the middle aspect of the individual's back, making it virtually impossible for them to have been self-inflicted.



These are multiple examples of defensive-type wounds from individuals who were attempting to ward off an assault from a knife-wielding attacker. Note the multiple linear abrasions, incised wounds, and stab wounds to the hands. Several of these injuries show cut marks between the thumb and fingers, due to the individual's attempting to grab the knife blade.



Other examples of wounds consistent with being inflicted while an individual is fending off an attack.



This individual was stabbed in the neck and then thrown from a window. The perpetrator described the injuries as being self-inflicted by the decedent who cut herself and then jumped out a window. The window ledge and outside wall were smeared with blood, which was easily visible from below. During autopsy, approximation of the margins revealed a stab wound just below the left ear from a knife blade that exited through her neck and stuck in her right shoulder. There was also an anemic abrasion to her back and an anemic laceration to the scalp, indicating the decedent had lost much of her blood volume and did not have a beating heart with blood pressure enough to produce hemorrhage from the injuries sustained when striking the ground.



Note the two stab wounds to the left back and the broken knife blade extending from one of the wound tracks. Note the close-up view of the back, demonstrating the knife within the wound track and then with the knife removed. Note the change in the wound dimension after the knife was removed. This demonstrates the elastic nature of skin and the possible challenges of correlating a weapon to a particular wound dimension. Also note the x-ray, which demonstrates the knife blade within the body. Note the dimension of the actual knife blade compared with the dimension of the blade image on the x-ray. This is due to the angle in which the x-rays contacted the knife blade in the thoracic cavity. Weapon.



Broken knife blade left in body following a homicidal assault. This knife was stuck into this individual with great force and the blade got stuck in a bone. When the perpetrator attempted to remove it, the handle broke off and the knife blade was left behind.



This individual was stabbed more than 75 times by a scorned lover. The tip of the knife blade broke off in the skull during this violent assault. Note the small radio-dense fragment depicted in these skull x-rays. This reinforces the notion that it is good practice to x-ray all sharp-force homicidal violence cases. A fragmented portion of knife blade can later be matched to a suspect's knife.



These individuals were attacked multiple times with machetes. Note the long gaping hack marks, several of which cut into and through bone. Most often, this degree of violent rage indicates the victim and the perpetrator had a relationship.



Chopping-type sharp-force injuries produced by an axe. Image (b) shows an individual whose eyes were chopped out by another person with a long history of psychosis. These types of assaults are not common. He reportedly did this because she kept staring at him.









This individual was chased up several flights of stairs in an apartment complex and was cut multiple times with a box cutter similar to the one shown here. Note the blood splatter pattern on the steps. Also note that the individual was almost decapitated. This was reportedly over a dispute concerning gang-related drug dealing territory.











This individual had multiple stab wounds with adjacent abrasions consisting of multiple superficial linear parallel lines. This is a typical pattern found following a serrated knife attack. The absence of these marks does not preclude the use of a serrated knife. If a serrated knife is stuck directly into a body and not dragged across the surface, there will be no parallel linear abrasions.







This individual was stabbed multiple times with a Ginsu-type knife. His dwelling was then set on fire and he sustained extensive thermal burns with charring of the skin. Note the costal cartilages with tool markings forming an imprint of the knife blade. Image on lower right demonstrates a knife similar to the one used in the attack.







Note this irregular incised wound with curved sharp margins produced by a knife similar to the one depicted in the previous figure.



This child was stabbed multiple times with a pair of scissors. Note that the entrance defects to the anterior trunk have a slightly widened angulated character consistent with being inflicted by a pair of scissors. The posterior trunk demonstrates the pointed end of the scissor perforating the entire body.



This image shows an x-ray of an adult who was stabbed with a pair of scissors that were left in the wound.









This individual was stabbed more than 75 times with an ice pick. Note the linear abrasions extending in different angles across the back as the tip of the ice pick was dragged across the skin's surface. The small dimension of these perforation wounds would take more time to lose significant blood compared with a typical knife blade. Generally speaking, the larger the wound, the faster the blood flow in a extravascular region. There was evidence of a violent struggle over a long period of time in this case.



This individual was found within a crack house, in a mild to moderate state of decomposition. He sustained multiple stab wounds and puncture-type wounds to his body that were produced by broken pieces of antenna used as crack pipes. One of these antennas was jammed down his throat. He also sustained multiple blunt-impact injuries with rib fractures and other broken bones from being stomped. Note the drying and slight distortion of the wound margins due to decomposition.



This individual was shot with a hunting arrow. The entrance wound is to the medial aspect of the right chest and the exit wound was to the right back. Note the comparison of the injury to the arrow head.



This individual was struck with a bottle that produced a minimal abrasion with a greater underlying contusion and a central laceration. Note the slightly irregular margins at the laceration site due to this blunt impact. The surrounding scalp hair was shaved to demonstrate the injury in greater detail. The presence of the scalp hair at the time this injury was inflicted also served to cushion the impact site.



This is the same individual, who was then cut multiple times with the sharp broken glass end of the bottle, producing a partial transection to the carotid artery and exsanguination.



The individual had multiple curvilinear parallel abrasions and other superficial abrasions caused by a bottle top and broken glass scraping across the body surface during the assault. This initial argument began over which rival baseball team was better.











Suicide by multiple sharp-force injuries with broken glass taken from an empty picture frame.



These are multiple examples of puncture wounds caused by a Phillips-head screwdriver, demonstrating the range of presentation of this type of injury.



These are multiple examples of flat-head screwdriver puncture wounds.



This approximately 30-year-old woman was found naked from the waist down in a construction yard. She had moderate decompositional changes with insect and animal feeding. She had multiple defects to her scalp and face with numerous maggots tracking through the underlying soft tissue. The soft tissues in this region were darkly discolored throughout. It becomes more difficult to interpret soft-tissue injuries as decomposition progresses. Careful examination of the underlying bone in such cases may often yield valuable information. Note the approximately 1/4″ linear skull fracture with a 1/16″ roughly square indentation at the superior right temporal bone. Further examination of the scene revealed a bloodstained board with a nail at the opposite side of the construction site.



Antemortem boat propeller injuries. Note the presence of wound track hemorrhage and the parallel slicing-type injuries.



Injuries produced by a boat propeller.



Injuries produced by a boat propeller. Note the hemorrhage at the autopsy incision (lower right), demonstrating the individual was alive when these injuries occurred. Note the range of injury presentation, including superficial abrasion to deep slicing-type wounds with extensive soft-tissue damage.













These are examples of dismembered bodies with saw cut marks through bone. It is important to save these portions of bone for possible later tool mark comparison with saw blades used during the dismemberment. Note image (a), where sexual mutilation was performed, with the breasts cut from the body. Also note image (d) of this young individual, who was cut into multiple pieces and neatly stacked on a rooftop.







This individual was killed by being struck in the back of the neck with a pickaxe. Note the abraded margin and the perforation matching the roughly squared dimension of the pickaxe. This dispute was reportedly over not receiving back pay after complete work.



This individual committed suicide by jumping out of a window and landing on top of a spiked metal fence similar to the one shown in image (c). The hair surrounding these injuries was shaved to demonstrate the nature of the wound in greater detail. Note the pointed circular perforation site leading into a square abrasion, which was perfectly consistent with the fence spike that penetrated his chest.



This infant was found partially eaten by dogs in a building courtyard. Note the irregular nature of the wounds to the back (b–d), demonstrating a scalloped border produced by teeth and claws. Other injuries to the child's body were inconsistent with animal feeding and more likely were produced by a sharp instrument such as a knife. Note the sharp wound margins in image (e). Dogs may eat a decomposing body when they are left to starve, or they may kill living individuals, more often without eating them. It has been my experience that it is rare for a domesticated dog to eat an individual unless it is coaxed into it by exposing the hungry dog to initiate feeding activity. The dog should always be examined including the gastrointestinal contents. In one such case, neatly cut strips of soft tissue were found within the dog's stomach that were fed to the dog by the perpetrator to initiate more feeding activity.





These are multiple puncture marks and lacerations with extensive adjacent hemorrhage due to an antemortem dog attack by a pit bull. This individual died as a result of blood loss.



This perpetrator killed his family by inflicting multiple stab wounds and then setting their house on fire. Note the relationship between environmental factors such as heat and the change in wound characteristic. This is demonstrated to a greater degree in the following figures.



This individual was stabbed multiple times and his apartment was set on fire to conceal evidence of the crime. Note the charring of the skin with the sharply margined defect, which was from a stab wound. Internal examination revealed extensive hemorrhage throughout and surrounding the wound track. Sometimes the surface interpretation of such injuries can be challenging. Thermal damage may cause cracking of the skin, which may be misinterpreted as antemortem sharp- or blunt-force injuries.



This individual sustained multiple blunt- and sharp-force injuries due to homicidal violence. She was found many hours after the assault during a hot summer month. Note the putrefactive changes with skin slippage and green to brown discoloration. Also note the wound margins are dry and dark. Some of these wounds could obviously be classified as lacerations or stab wounds and others could not be classified due to distortion by decomposition.



Healed stab wound.

Gunshot Wounds

8

CHARLES A. CATANESE, THOMAS GILSON,
AND THOMAS ANDREW

Introduction

The evaluation of gunshot wounds is an area of importance in forensic medicine. Analysis of gunshot wounds should involve:

- Differentiation of wounds of entrance from exit
- Range of fire estimation for entrance wounds
- Determination of trajectory through the body
- Recovery of evidence (e.g. ballistics)

Whenever possible, clothing worn by a gunshot wound victim should also be examined.

Entrance and Exit Differentation

Entrance Gunshot Wounds

Most entrance wounds appear as circular perforations with a margin of abrasion, a collar of abraded skin, and the entrance defect. The margin of abrasion is produced by stretching with eventual tearing of the skin surface as the bullet enters the body. It is the most reliable feature in identifying entrance gunshot wounds. Exit gunshot wounds lack this feature, as the undersurface of the skin is stretched outward when a bullet exits the body. The margin of abrasion may provide useful preliminary information regarding trajectory of a bullet through the body. When the bullet enters the body perpendicular to the surface, the margin of abrasion is symmetric. As the bullet enters the body on an angle, the margin will be elongated on the side where the bullet first contacts the skin. The trajectory is confirmed by subsequent internal examination.

Exit Gunshot Wounds

These types of wounds typically appear as slit-like or irregular perforations without margins of abrasion. An exception to this is a shored or supported exit, which occurs when a bullet exits from the body where the skin is firmly supported. This might occur as a bullet exits when an individual is leaning against a wall, lying on the sidewalk, or even wearing tight-fitting clothing. These wounds generally have a round appearance and may have superficial abrasion around the defect. Unlike the true abrasion margin of an entrance wound, the shored exit abrasion tends to lack any significant depth and is often very irregular.

Atypical Gunshot Wounds

These are entrance wounds characterized by an irregular appearance. They may have irregular or obscure margins of abrasion. The skin adjacent to the entrance wound may show irregular abrasions or lacerations. Sometimes these perforations may appear as irregular tears. Ricochet bullets, or bullets that pass through intermediate targets, often produce atypical entrance wounds. Sometimes the jacket and the slug may separate and produce two separate irregular entrance wounds. Bullets may strike surfaces such as concrete and fragment into pieces, causing multiple irregular defects from impacts of both twisted metal and rock fragments. Fragments from upholstery, chrome, plastic, etc. may be found at the wound surface or even within the wound track. This atypical appearance may also be seen in certain areas of the body where the skin is thicker (palms and soles) or the skin contour is irregular (face). Atypical wounds may be difficult to interpret, particularly in perforating gunshot wounds where the bullet passes through soft tissue only. Fracture characteristics of bone (especially flat bones such as the skull) and lead fragmentation patterns may give great insight into establishing direction of fire.

Range of Fire Estimation

In estimating range of fire, an attempt is made to determine the distance from the end of the barrel of the gun to an entrance wound at the time the weapon is discharged. This is most reliably estimated by observing the wound and trying to re-create an observed pattern by test firing the weapon. Because the weapon is often not available, estimates based on the physical characteristics of the wound are frequently employed.

An understanding of ammunition aids in understanding range of fire estimation. The ammunition placed into a firearm is a cartridge. A cartridge consists of a bullet, which rests atop a casing containing gunpowder. A primer located at the base of the cartridge ignites the powder. The primer is itself ignited by the mechanical action of the hammer of the firearm, when the hammer strikes the base of the cartridge. The bullet is the portion of the cartridge that exits the barrel. It is propelled by the burning gunpowder. In general, there is some residual gunpowder that does not burn. In addition to the bullet, burned and unburned gunpowder exits the barrel when a weapon is discharged. This forms the basis of range of fire and estimation.

Range of fire can be divided into three major categories. These include *close range, intermediate range,* and *distant range.* As noted, range of fire is best estimated by the use of test firings employing the known weapon with similar ammunition. Lacking these ideal conditions, estimates can be made on the basic wound characteristics as described next. Even when test firings can be performed it is worth remembering that the wounding characteristics of skin are not identical to gunpowder residue deposition on a test-firing cloth.

Close Range of Fire

This is characterized by the presence of *soot* on the adjacent skin surface or within the wound track. Soot is burned gunpowder residue with a dark powdery appearance. It is critical to remember that soot can be wiped from the body's surface, so gunshot wounds need to be examined prior to any washing, whenever possible. The presence of soot indicates the end of the barrel of the gun was held within approximately 6 to 8 inches from the body's surface. Different guns may have different ranges. The closer the end of the barrel is to the body, the denser the soot deposition. As this distance increases, the soot deposition becomes sparser. Soot may be present with stippling (see intermediate range of fire), but this is more accurately still considered close range of fire. When the end of the barrel is very close to the body, there may also be searing of the adjacent skin from burning gunpowder and flame that extends from the end of the barrel. Soot can be filtered away through intermediate targets such as clothing, car doors, walls, etc. This pattern becomes more dispersed as the distance becomes greater.

Within the close-range-of-fire category are contact gunshot wounds where the end of the barrel touches the body. These may be further subdivided into *tight contact* and *loose contact.* Some classify wounds where the barrel is very close to the body as *near contact*. The term "close contact" is redundant, potentially confusing, and best avoided.

Tight Contact Gunshot Wounds

These are produced when the barrel of the gun is held tightly against the body's surface. Most of the soot will be deposited within the wound track and may not be apparent until autopsy examination. Small amounts of soot may be present at the wound margins. Depending on the body region, type of gun, type of ammunition, and force with which the gun is pressed against the body, the wound may appear different. There are often abrasions adjacent to the gunshot wound. These are associated with the muzzle of the gun rubbing against the body's surface as the gun is discharged. These may take the form of a semicircular rim or a complete imprint pattern of the entire muzzle. When the gun is held tightly to the body, particularly over a bony surface such as the skull, there may be multiple radiating linear lacerations. These lacerations may be small or large and are more commonly associated with larger-caliber bullets. Approximation of the laceration margins reveals a central circular perforation typical of an entrance wound with abraded margins. Observation of the muscle under a tight contact wound may reveal a pink discoloration owing to the introduction of combustion products into the wound track such as nitrites and especially carbon monoxide binding with myoglobin.

Loose Contact and Near Contact

When a gun is held less tightly against the body, soot may escape more readily to the skin's surface. If the gun is discharged at an angle to the body's surface, the pattern of soot dispersion will extend over a greater surface area in the direction of fire. A partial muzzle imprint may be observed. In near contact wounds, the soot is deposited in a dense, relatively small area around the entrance and searing of the skin may be observed as noted above.

Intermediate Range of Fire

This range of fire is characterized by the presence of *stippling* defects around the entrance wound. These are small, (approximately 1/16 inch) red to brown, punctuate abrasions of the skin's surface. Stippling indicates the end of the barrel of the gun was held approximately 18 to 24 inches away from the body's surface. These defects are produced primarily by fragments of unburned gunpowder that exit the barrel with the bullet. These fragments strike the body with greater force than soot and produce permanent defects. Such defects cannot be wiped away from the body's surface. The appearance of stippling may vary depending on the type of gunpowder used in the cartridge, (e.g., ball, disk, or flake).

The term *stippling* applies to the defects in the body's surface. This pattern will become more dispersed as the distance from the weapon to the body's surface increases. Like soot, stippling can be dampened or completely filtered by clothing or other intermediate targets. Powder residue found on intermediate targets at this range of fire is characterized by small, separate, gunpowder fragments.

Soot or stippling defects may be present on an outstretched hand but not surrounding the entrance wound. For this reason, close examination of the upper extremities in gunshot wound cases may be helpful. Range of fire is estimated in the same way and the distance between the weapon and the entrance wound can be approximated by factoring in the distance from the wound to the upper-extremity findings.

Occasional "pseudostippling" may be seen around an entrance wound. This phenomenon is generally seen when a bullet passes through an intermediate target and fragments of the intermediate target strike the skin's surface (causing abrasions) around the entrance wound. As noted, such entrance defects tend to be irregular and the adjacent stippling defects exhibit wider size variation than true stippling, where the abrading gunpowder tends to produce abrasions of relatively uniform size.

Distant Range of Fire

This range of fire is characterized by the absence of gunpowder residue around an entrance gunshot wound without an intermediate target between the end of the barrel and the wound. This indicates the end of the barrel of the gun was held more than approximately 18 to 24 inches away from the body's surface. Some experts prefer to call this intermediate range, especially when the possibility of an intermediate target cannot be excluded.

Trajectory Determination

The path a bullet takes through the body may have substantial medicolegal significance. In some cases, the trajectory can be easily determined by careful dissection. In other cases, (e.g., multiple gunshot fatalities), full delineation of wound tracks may be harder to accomplish as a result of extensive internal injury. Surgical intervention may also obscure wound tracks in part. It is also worth remembering that a wound sustained in a certain body position may look slightly out of alignment with the body lying supine on the autopsy table. Superficial wounds can pose difficulties in trajectory determination as entry and exit wounds may not be easily identified. These include graze and tangential gunshot wounds.

Graze-Type Gunshot Wounds

These are produced when the bullet contacts the skin superficially at a very narrow angle, producing an elongated superficial oval abrasion. One may determine direction of fire by a semicircular margin of abrasion at the entrance side and a more irregular margin at the exit side.

Tangential Gunshot Wounds

These are produced when the bullet strikes the skin superficially at a narrow angle and creates lacerations of the underlying subcutaneous tissue and overlying skin. Direction of fire may be established by the presence of a semicircular margin of abrasion at the entrance side. Also, the laceration of the skin overlying the wound track produces tears with skin tag formation. These tags will extend outward on angles. The tips of these lacerations, at their most medial aspects (e.g. within the wound track), point toward the side from which the bullet entered the body.

Gunshot Wounds in Bone

Gunshot injuries of bone may be helpful in trajectory determination, especially in the skull and, less frequently, other flat bones. When a bullet passes through the skull, it creates a cone-shaped beveled defect. The entry point has crisp margins and the exit point is larger and represents the wider portion of the cone. Bullets entering the skull produce internal beveling and those exiting the skull produce external beveling. A tangential bullet strike of the skull may cause the bullet to fragment and result in complex beveling if a portion enters the cranial cavity and a portion shears off and remains outside the surface. In such cases, the bony defect created may exhibit internal and external beveling. Such defects are referred to as "keyhole" defects, as their appearance may resemble a keyhole.

High-Velocity Gunshot Wounds

Trajectory delineation in high-velocity gunshot wounds is similar to low-velocity injury, however, the extent of injury is far more significant and exit wounds are often dramatically large. Hunting ammunition used at high velocity will fragment more in the body than low-velocity bullets, creating a characteristic x-ray picture called a "lead snowstorm."

Evidence Recovery

Bullets retained in the body must be recovered at autopsy. Rifled firearms leave characteristic markings on bullets that can be used for identification of a firearm by comparison with projectiles known to have been fired from that weapon. Care must be taken during dissection to avoid or minimize the creation of any additional marks on the bullet that might obscure the rifling marks. This also applies to any identifying marks inscribed place directly on the bullet after recovery. These identifying marks should be inscribed on the base of the bullet. Older bullets should be recovered at the time of autopsy. These may be enclosed in fibrous capsules at the site of lodgment and often have a dull gray appearance as a result of oxidation. Rifling marks may still be present and useful for ballistic comparison.

Shotgun Wounds

Because of differences in construction and ammunition, shotguns merit special consideration. Shotguns can be used to fire a single projectile (slug) or several pellets (shot). Shot size can vary (buckshot versus birdshot). Slugs behave essentially as single projectiles. The shotgun cartridge (or shell), contains some additional components (e.g., wadding, filler material) that might produce injuries that can be used in range of fire estimation. Soot and stippling remain useful in close- and intermediate-range determinations. The wounds produced by shotgun shells containing shot look different from conventional bullet wounds. Soot, stippling, wadding, and other components can be used for range of fire estimation, but the behavior of the pellet cluster over distance provides additional information regarding range of fire. When the shot exits the barrel, it travels initially as a tightly grouped cluster. Striking the skin, the tight cluster produces a round defect. The grouping opens up over distance with the first noticeable change in wound appearance occurring at about 3 feet. A single defect is still observed but the margins now take on a scalloped appearance. With further distance (and more pellet dispersal), wounds now consist of a central defect with scattered satellite defects surrounding them. These satellite defects increase in number with greater distance, until the central defect is lost entirely and pellets maintaining sufficient velocity strike the skin's surface individually. The dispersal pattern of pellets is not predictable once an intermediate surface intervenes. It is not possible to evaluate these wounds for range estimations and, for similar reasons; estimates of range of fire by x-ray examination are unreliable. As with other firearms, test firings are the most reliable means for range of fire approximations.



Distant entrance gunshot wound. This bullet struck the body nose end first, roughly perpendicular to the surface. Note the thin and roughly symmetric margin of abrasion surrounding the slightly oval perforation.



Distant entrance gunshot wound in a darker-skinned individual. Note the slightly asymmetric margin of abrasion, which is greatest at its inferior aspect. This indicates the bullet struck the body nose first, and at a slight upward trajectory. These directions are stated *relative to the body*.



Distant entrance gunshot wound with slightly asymmetric margin of abrasion, which is greatest at the right inferior aspect. This usually indicates the bullet struck the body nose first, almost perpendicular and at a slightly upward and right-to-left trajectory. These directions are stated *relative to the body*.



Distant entrance gunshot wound with slightly asymmetric margin of abrasion greatest on its superior and left aspect. This usually indicates that the bullet struck the body nose first, almost perpendicular and at a slightly downward, left-to-right trajectory. These directions are stated *relative to the body*.



Distant entrance gunshot wound with slightly irregular, widened margin of abrasion, which is greatest at the right lateral aspects. This indicates the bullet struck the body from a slightly inferior and right-to-left trajectory. The slightly irregular nature of the margin of abrasion may sometimes be seen, as the bullet perforates clothing first.



Distant entrance gunshot wound that is slight stretched into an oval due to skin tension. Note the slightly asymmetric margin of abrasion, which is greatest at the 9 o'clock through 12 o'clock position, indicating the bullet struck the body with a slightly downward and left-to-right trajectory.



There are six separate clustered entrance gunshot wounds to this individual's head. Note the abrasion to the posterior ear helix caused by a bullet. Shaving the hair is recommended for external examination of such gunshot wounds.



Distant entrance gunshot wound to the palm of the hand through thick skin.



Distant entrance gunshot wound through the thick skin of the sole of the foot. This bullet first perforated the bottom of a shoe and a sock before entering the body.



Entrance gunshot wound with surrounding stippling defects indicating intermediate range of fire. This gunshot wound (a) to the thick skin of the palm of the hand reveals typical small radiating lacerations without prominent margin of abrasion. These characteristics are typical for gunshot wounds of the palms of the hand and soles of the feet. These images (b–e) represent the same contact gunshot wound with varying degrees of tension surrounding the wound's surface. Note that with approximation of the margins (d–e) the wound forms a roughly circular perforation with margin of abrasion typical of an entrance gunshot wound. Also note the copious amounts of soot within the wound track and at the underlying bone surface. Such large radiating linear lacerations are usually associated with higher-caliber guns and tight contact of the gun muzzle on the body surface with underlying bone close to the skin. The expanding gases from burning gunpowder forced into the wound track causes such lacerations.



Contact gunshot wound to the scalp with radiating lacerations and soot deposition within the wound track and at the wound margins. These lacerations are caused by burning gunpowder, with expanding gases forced into the wound track and causing the overlying skin to lacerate.



Contact gunshot wound to the face (a). Note the stellate lacerations radiating from the perforation site with soot deposition; (b) a close-up view with a different orientation.



Contact gunshot wound to the right temporal region. Note the larger lacerations extending from the perforation site with adjacent soot deposition.



Contact gunshot wound to the eye. Note the lacerations of the eyelid and eye globe with soot deposition at the adjacent skin and within the wound track.



Contact gunshot wound to the temple. Note the small radiating lacerations from the perforation site. Note the presence of soot within the wound track and adjacent skin.



Note this tight contact gunshot wound to the right temporal region with lacerated borders and soot deposition. A .357 Magnum caused a comminuted skull fracture with head deformity and the eye protruding from the socket.



Contact gunshot wound to the scalp. (a) Note the small radiating lacerations with soot deposition. (b) Note the same wound after cleaning. The tension surrounding the wound is relieved by pressing the surrounding skin inward toward the perforation. This will approximate the wound margins and reveal a roughly circular perforation with margin of abrasion characteristic for an entrance gunshot wound. Note that even after cleaning, small amounts of soot are still present at the wound margins. Further cleaning might eliminate this gunpowder residue as well. In many cases, such as this one, it is essential to photograph the body before cleaning.



Contact entrance gunshot wound to the temple. Note the abraded imprint of the eyepiece portion of the gun at the superior aspect. The perforation site has a margin of abrasion. There is no obvious soot at the surface of the adjacent skin, but there were copious amounts of soot within the wound track. Note the pink to red discoloration surrounding the perforation due to nitrates and carbon monoxide released from burning gunpowder. These components may sometimes cause this discoloration when reacting with the underlying muscle. In this case, it is more obviously due to the decedent's light skin color.



Contact gunshot wound with muzzle imprint.



Contact gunshot wound. Note the adjacent abrasion to the perforation site due to contact with a revolver ejector rod when the gun was discharged. There are also small amounts of soot visible at the wound margins and more within the wound track.



Contact gunshot wound to the scalp with an abrasion at the superior left aspect due to the gun muzzle. There is visible soot within the wound track. Sometimes it may be difficult to visualize the presence of gunpowder residue on thick, dark, scalp hair.



Contact gunshot wound. Note the soot at the margin of the perforation site. Note the surrounding abrasion from a partial muzzle imprint.



Contact gunshot wound to the right temporal scalp. Note the soot deposition surrounding the margin and the red discoloration of the adjacent skin.







Underlying soot deposition within the wound track on the outer surface of the exposed skull. This is typically seen with a tight contact gunshot wound where soot is forced into the wound track.



Close-range gunshot wounds with soot deposition.



Note the entrance wound is to the left where soot is visible at the adjacent skin.



Close-range gunshot wound to a body with early decompositional changes. Note the soot deposition surrounding the perforation site. These early putrefactive changes consist of skin slippage and discoloration.



Loose contact with more soot extending to the right side of the perforation.



Loose contact with the muzzle more tightly applied at the right aspect. Note the greater soot deposition to the left of the perforation.



Close-range gunshot wound with soot deposition.



Close-range gunshot wound in a very dark-skinned individual. Note the gunpowder residue surrounding the entrance gunshot wound.



Close-range gunshot wound with a muzzle flare burn and soot encircling the perforation site.



Close-range gunshot wound with sparse soot deposition surrounding the perforation site with adjacent superficial skin erosions due to muzzle flare.



Close-range gunshot wound with soot deposition, superficial skin erosions from muzzle flare with tightly compacted stippling-type defects.



Close-range gunshot wound to the scalp with sparse soot deposition, adjacent burning of the scalp due to muzzle flare, and closely packed stippling defects.



These demonstrate histopathology sections of skin with soot deposition at its surface. The soot appears as a black film on the skin's surface; unburned powder particles may also be visible.



Gunpowder residue at the fingers due to firing a handgun. This individual died from a self-inflicted gunshot wound to the head. The amount of gunpowder residue following discharge of a firearm may be quite variable and sometimes not very obvious.



Soot may also be deposited as it exits from the muzzle of the gun or from cylinder gap in revolver type handguns.



This pattern of soot was caused by holding a revolving cylinder while discharging the weapon.



Note the "blowback" blood spatter pattern on the hands of these individuals who died from self-inflicted gunshot wounds to the head. Note that in (a) the spatter pattern is partially obscured by subsequent contact deposit of blood. Also note in (d) the extent of spatter may be minimal.



All of these are articles of clothing demonstrate close-range gunshot perforations with soot deposition. It is always important to inspect the decedent's clothing. Multiple layers of heavy clothing may filter gunpowder residue from the body surface. It is also important to distinguish bullet wipe from soot deposition. Bullet wipe is a small, encircling, gray discoloration around the perforation site of the clothing due to lubricants and residue from within the barrel of the gun that adhere to the bullet surface as it passes through the barrel. Unlike soot, bullet wipe is not useful in range of fire estimations.



Clothing with soot indicating close range of fire. The individual wearing the hat had long curly black hair and there was no appreciable soot noted at the scalp.



Note the large tear in the clothing from this contact wound and the minimal amount of adjacent external hemorrhage. This is an antemortem injury with more than a liter of blood observed in the thoracic cavity during autopsy.



This entrance gunshot defect is surrounded by dark clotted blood. The dark discoloration of blood, particularly on dark clothing, may make if difficult to observe soot. This is a distant gunshot wound (d).



Bullet wipe. This individual had his shirt tucked in, creating folds in the cloth. Note the dark discoloration around the perforation site with the right aspect separated several inches from the site of bullet entry. By refolding the fabric and approximating the margins we can simulate how the individual actually wore his shirt (a–c).



Intermediate range of fire. Tightly packed stippling defects surrounding this entrance gunshot wound to the cheek. There is no apparent soot deposition.



Multiple stippling defects to this individual's forehead indicating intermediate range of fire.



Intermediate range of fire with stippling defects. Stippling defects represent abrasions that, unlike soot, cannot be wiped away.



Intermediate range entrance gunshot wound to the eyebrow with stippling defects across the face. Note the irregular nature of the wound due to the location of the gunshot wound through the eyebrow ridge, with the underlying frontal bone closely subadjacent to the skin surface.



Intermediate range of fire.



Intermediate-range entrance gunshot wound with stippling defects. The scalp is partially shaved. Note the decreased number of defects in the shaved area as a result of hair dampening the effect. The weapon was a sawed-off 30/30 hunting rifle that was reportedly discharged approximately 15 inches away from the decedent's head.



Entrance gunshot wound with stippling defects indicating intermediate range of fire.



Intermediate-range gunshot wound with stippling in a dark-skinned individual.



Intermediate-range gunshot wound. Note the sparse stippling defects along the bicep and forearm with sparing of the anticubital fossa region. This indicates the decedent had his arm bent when he was shot.



This individual had stippling defects involving the posterior portion of his lateral outer ear and temporal scalp. Note the sparing of the posterior medial ear.



Stippling defects with soot deposition on the side of an outstretched hand, indicating intermediate to close range of fire.



Multiple-entrance gunshot wounds. Note the sparse stippling defects indicating intermediate range of fire at the skin anterior to the ear. The farther away a gun is discharged from the body, the more spread out the stippling defects become.



Intermediate range of fire. Note the sparse stippling defect surrounding the bullet perforation site.





A few sparse stippling defects indicating intermediate range of fire. Note the contusion surrounding the perforating gunshot wound at the arm. This dark discoloration should not be confused with gunpowder residue.



Note the multiple gunshot wounds to this individual in varying directions. She was shot multiple times while jumping in different directions in an attempt to run away. Note the contusion to her left shoulder and the stippling defects to her face. It is important to realize that the direction of fire may vary greatly.



Gunshot wound perforation of clothing with multiple gunpowder residue flecks at the surrounding surface. The underlying entrance gunshot wound still revealed a sparse stippling pattern consistent with intermediate range of fire.



Distant gunshot wound with pseudostippling to this individual's face caused by fragmented debris as the bullet passed through a car window.



Distant gunshot wound with pseudostippling. Note the large size variation in the abrasions to the gunshot wound. True stippling defects are more uniform in size.



Atypical distant-entrance gunshot wound with surrounding contusion.



Distant-entrance gunshot wound with surrounding clotted blood. In this case, histopathology of the adjacent skin demonstrated no dark particles consistent with gunpowder residue. It may be challenging to visualize soot when it is mixed with dried blood. Dried clotted blood has a shinier character than gunpowder residue, which has a duller appearance. It may be challenging to interpret range of fire when both dried blood and soot are present simultaneously. If there is any question concerning the presence of soot, we recommend microscopic examination to help clarify this point.





Thoracotomy incision through entrance gunshot wound. One should never cut through the wound during resuscitative efforts. No one would argue the importance of saving the individual's life. Cutting next to the wound will not affect the chances for survival. Cutting through the wound may make wound interpretation very difficult and hinder criminal proceedings. Note one gunshot wound was cut through and hidden in the suture line. The defect becomes more obvious with suture removal.



Note the large gunshot wound at the medial aspect of this thoracotomy incision.



This is a gunshot wound that is several days old. This person died of septic complications. Note the adjacent wound infection distal to the GSW site.



Exit gunshot wounds. Note the typical, often irregular, slit-like defects without margins of abrasion. The appearance is generally more irregular and less round than the entrance wound.



Exit gunshot wounds.



Exit wound with lacerated margins.



Exit wound from a sawed-off 30/30 hunting rifle.



Exit wound from a handgun. It is not typical to get such a large laceration from a medium-caliber bullet that already perforated the skull.



Exit gunshot wound through the right nares.



Exit gunshot wound to the lower face caused by a bullet that was markedly deformed by striking underlying bone before exiting.



Exit gunshot wound through the finger.



Exit gunshot wounds through the palm of the hand.



Exit gunshot wound through the thumbnail bed.



This individual was shot in the lower back while leaning forward. The bullet perforated the structures of the thoracic cavity and neck, producing a grazing-type gunshot wound to the tongue. The bullet then knocked out the individual's front tooth before exiting the body from the open mouth.



Note the lumps directly underneath the skin's surface. These are caused by bullets just beneath the surface of the skin that did not have enough kinetic energy to exit the body.



A bullet was retrieved just beneath the surface of the skin within this area of contusion.



There is a large deformed gray metal slug just underneath the surface of the skin that is partially visible underneath the broken skin.



Bullet retrieved from skull fracture directly underneath the skin's surface.



This image demonstrates a hemorrhagic pulpified wound track through the cerebral hemispheres caused by a medium-caliber handgun bullet.



This bullet was retrieved within this portion of thoracic vertebra. It is important to carefully remove such bullets encased in bone, so as not to destroy ballistic markings on the sides of the bullet.



These figures demonstrate a wound track through the liver caused by a medium-caliber handgun.



This individual had been shot several weeks earlier with a .22 caliber handgun. One of his ribs fractured while removing the breastplate during autopsy and a bullet was retrieved from within the medullary cavity.



A wound track through the aorta with adjacent surrounding hemorrhage. This wound was caused by a medium-caliber weapon.



Shored exits. These wounds were produced by bullets exiting the body where the skin's surface is supported (e.g., by a firm surface or tight clothing).



Atypical entrance gunshot wound caused by a bullet that was deformed by passing through an intermediate target. Note the large irregular abrasion caused by the deformed edges of the bullet's striking the skin surface.



Shored exit wounds.



Irregular exit gunshot wound with adjacent abrasion due to its location on the body through a region of folded skin.



This distant-entrance gunshot wound has slight oval shape with an irregular margin of abrasion that is greatest at its inferior right aspect. This wound was produced by a ricochet bullet that first struck a brick wall. Part of the bullet had an irregular scratched surface. Also, this bullet most likely struck the body sideways.



Atypical gunshot wound. This is a re-entry gunshot wound produced from a bullet that was markedly deformed from striking a bone in another part of the body. Note the irregular nature of the perforation with the irregular adjacent abrasions.







Atypical gunshot wounds from deformed and fragmented bullets that passed through an intermediate target, such as a car door and window, before entering and exiting the body. Note the markedly irregular nature of these injuries.













Multiple atypical entrance gunshot wounds produced by fragmented pieces of lead caused by .22 caliber nonjacketed bullets that struck concrete and fragmented before striking an individual who was lying on the sidewalk. Note the irregular nature of these injuries with superficial fragmented pieces of lead observed in several of the wound tracks.





Several atypical injuries produced by fragmented nonjacketed lead bullets. The individual survived in the hospital for days. Note the healing margins and fragments of lead being pushed from the underlying soft tissue.









This child was shot multiple times. One of the bullets struck another object, fragmented, and produced this atypical entrance wound to his wrist (a). There were fragments of bullets retrieved from the decedent's jacket corresponding to this location (b). X-ray (c) shows multiple fragments of deformed metal retrieved just underneath the skin surface adjacent to the bones of the hand. The last image (d) shows all the bullet fragments retrieved from this individual's hand and wrist. There were no other wounds to this region of the body.



This ricochet bullet was retrieved within the abdomen of an individual with a perforated iliac artery. The bullet perforated the individual's shirt and did not strike bone while passing through the body.



This bullet struck the ground, fragmented portions of tile, and became markedly deformed before ricocheting upward and striking the body of an individual already lying on the ground. The resulting gunshot wound was markedly atypical, producing irregular injuries to the body surface.

This deformed bullet was retrieved from an individual after it ricocheted off an intermediate target.



Intermediate-entrance gunshot wound with stippling. Note the irregular natural of the wound due to the location on the body. The bullet entered between the cartilage of the ear at a skin fold between the ear and the scalp. Note the elongated abrasion at the posterior ear due to the bullet's grazing the skin before entering the body.



Distant-entrance gunshot wound with an asymmetric margin of abrasion. This indicates that the bullet grazed the body at an upward trajectory before perforating the skin.



Graze gunshot wounds; (a) is more atypical.



Graze gunshot wounds.



Tangential gunshot wound with a trajectory from the middle to distal aspect of the finger. Note the semicircular entrance defect at the right side of this wound overlying the proximal middle phalange.



Tangential gunshot wounds to the arm and trunk. Note the skin tag formation at the wound margin produced as the bullet perforated underneath the skin's surface.



Tangential gunshot wound with skin tag formation. The direction of fire is from left to right.



Distant tangential gunshot wound. Tangential gunshot wounds are produced when the bullet strikes the body at a narrow angle, producing skin tag formation. Usually the bullet exits the body leaving an open wound through the skin's surface, connecting the path of entrance and exit perforations. These wounds are deeper than graze gunshot wounds. This wound is associated with bullet fragmentation and partial exit, which may occur when the bullet strikes the body at a surface directly adjacent to underlying bone. This is an example with bullet fragmentation, partial exit, and underlying keyhole deformity of the skull. Note the entrance side of this wound is at the anterior aspect. There is a semicircular margin of abrasion leading into this laceration. The direction of fire is from left to right.



Tangential gunshot wound of the scalp. The direction of fire is from right to left. Note the skin tag formation pointing away from the semicircular entrance site at the right side of the wound.



Note the tangential gunshot wound through the palmar surfaces of the fingers.



Tangential gunshot wound to the forehead. Part of this bullet entered the cranium and a portion of the bullet exited the body. There was an underlying keyhole deformity to the skull.



After this bullet perforated the fingers it produced a tangential gunshot wound to the nose before entering the body at the face.



This demonstrates an entrance and exit gunshot wound that passed superficially beneath the skin surface. The direction of fire is right to left. Note that the perforation at the right side has a more uniform oval shape with a more symmetric margin of abrasion. The exit component to this wound is more irregular.



This gunshot wound produced multiple tears and perforations to the surface of the skin as the bullet passed close to the underlying surface. Such injuries often occur in regions of the body where skin folds on itself, such as the inguinal, gluteal, and axillary regions.



This single gunshot wound passed through the superficial soft tissues of the chest, producing multiple perforations and tears to the surface. Note the irregular nature of the torn skin and irregular abrasions at the exit reentry site.



This is another example of an entry–exit–reentry wound where the bullet passed close to the underlying skin surface. Note the larger irregular abrasions connecting the exit and re-entry sites. Also note the dark discoloration due to drying.



This is an entrance and exit gunshot wound where the bullet passed very close to the under surface of the skin.



These images show different examples of nailgun wounds. Both of these cases were suicides. Both nailguns were similar to the one shown in the last image, which used gunpowder-loaded cartridges. Both entrance wounds consisted of circular perforations with symmetric margins of abrasion indistinguishable from typical entrance gunshot wounds. Note the orange plastic ejected into the entrance perforation of the temporal skull that is used in some nail guns to hold and steady the nail prior to discharge.



This individual was shot multiple times. Note the exit gunshot wound to the superior aspect of his middle chest (a). He was wearing a medallion on a string that was struck by the bullet as it exited the body, producing an imprint on the skin surface. The chest surface was most likely pressing against another object when the bullet exited. Figure (b) illustrating the medallion actually demonstrates it facing the wrong way. The medallion should be oriented with the inward curvature facing the chest. This was at first erroneously thought to be an entrance gunshot wound. Among other points arguing this to be an exit wound was the sternum fracture with bone splinters pointing in an outward anterior direction(d).



This individual was shot multiple times and survived in the hospital for approximately 2 weeks. One of the bullets entered the lung parenchyma and embolized to the heart, where it got wedged in papillary muscles of the left ventricle. He developed bronchopneumonia and his lung wound reopened, causing hemorrhage and death.







An otherwise healthy, full-term pregnant woman was shot multiple times in the abdomen. There were multiple perforating gunshot wounds to her fetus that were atypical due to the intermediate targets, including the mother, uteroplacental unit, and amniotic fluid. All the fetal wounds appeared as irregular lacerations with irregular abrasions. Direction of fire could not be determined.
Source for upper right and lower figures: Catanese C. and Gilmore K. A case report and brief analysis of fetal gunshot wound characteristics. *Journal of Forensic Science* 47:1067–069; 2002. Reprinted with permission from ASTM International.



This individual was shot in the face while wearing eyeglasses. Note the irregular nature of the entrance gunshot wound just beneath the eye (a) and the elongated abrasion extending across the cheek to the decedent's ear (b), corresponding to the eyeglass frame.



This individual was shot multiple times and had psoriatic skin disease. Note the irregular nature of this entrance gunshot wound through one of the plaques (a). The skin had small radiating lacerations and decreased abrasion similar to what is sometimes seen with gunshot wounds through thick skin found on the palms of the hands or soles of the feet (b).



These are gunshot wounds to an individual who was set on fire to destroy evidence after being shot in his residence. His carbon monoxide blood level was negligible. Note the change in character of these injuries due to thermal effect. These thermal burns are postmortem.



This individual was shot multiple times where the bullet struck bones and fragmented into multiple pieces. It is important to keep track of which bullets are associated with which gunshot wounds. There may be three different shooters and only one of the bullet wounds lethal. Linking the lethal bullet to a particular shooter may have different legal implications.



This individual was shot in the abdomen with a hunting rifle. Note the snowstorm effect of bullet lead fragmentation depicted on this x-ray.



This individual (a) was shot with an aluminum-jacketed bullet. This fragment of aluminum (b) was retrieved within the wound track. Aluminum, being a relatively less dense metal, may not be apparent on x-ray, particularly when it is lying over a dense thick bone.



Note from this x-ray that one can tell the direction of travel. The bullet struck the humerus, fragmented into pieces, and then left a trail of metal fragments as it passed through the soft tissues before coming to rest.



This is a contact gunshot wound to the chest with visible muzzle imprint abrasion (b). Note the blue-tipped Teflon plug Glazer safety ammunition visible within the revolver chamber (a). Note the yellow metal jacket, Teflon plug, and multiple lead pellets seen on x-ray (c), and demonstrated after removal from the body (d).



Tangential distant gunshot wound produced by Mag-safe ammunition (prefragmented).



This diagram shows a comparison of the components of Mag-safe ammunition and Glaser safety slug.



This x-ray is taken from an individual shot with Mag-safe ammunition. Note the metal jacket, gray to blue epoxy fragments, and gray metal pellets.



This demonstrates a bullet retrieved from an individual who was shot approximately 1 day prior to autopsy. Note the shiny surface of the bullet, signifying no significant oxidation.



These are multiple weathered fragments of bullet retrieved from underneath and within the body of a partially skeletonized individual who was shot and thrown down a well shaft several years earlier. Note the irregular weathering marks at the surface of the bullets due to erosion.



This demonstrates a bullet retrieved from an individual who was shot over a year before. This bullet remained in his body until it was retrieved during autopsy after somebody else shot and killed him. Note the dull oxidized surface on this old bullet.

The homicide victim who owned this dog died of multiple perforating gunshot wounds. The dog sustained penetrating gunshot wounds during the attack and was autopsied to retrieve ballistic evidence.

This is a recent gunshot wound to an individual who was shot through the subcutaneous and fatty tissues of the gluteal region and thigh. Note the curvature of the wound track. This demonstrates how wound tracks may change when the body is laid on a flat autopsy table. One must keep this in mind when formulating bullet trajectories with reference to standard anatomic planes. This information may later be used as a reference to help explain possible body positions during the actual shooting. Interpreting wound track directions can become complicated when there are multiple gunshot wounds in proximity, particularly when the individual was shot while curled up in a fetal position and then later examined while spread out on an autopsy table. Directions should be stated with reference to standard anatomic planes.





This is a healing wound track through the subcutaneous and fatty tissues of the gluteal region. Note the dull granular nature due to healing and the presence of granulation tissue.



This is a healing gunshot wound that is approximately a week old.



Atypical healing gunshot wounds with fragmented pieces of lead.



Varying stages of healing gunshot wounds.



This case involves a suicidal tight-contact intraoral .44-caliber rifle wound with extensive fractures and lacerations to the head. Note the gaping injury at the top of the head with the empty cranial vault. The brain was ejected almost entirely intact due to expanding muzzle gases.



This individual died from a self-inflicted contact 16-gauge buckshot shotgun wound to his forehead. His cerebral hemispheres were ejected from the cranium almost completely intact and were discovered behind the body. Note reconstruction of this wound produces an obvious circular perforation with soot at the individual's forehead. Initially, at the scene investigation, it was thought to have been an intraoral shotgun wound, many of which are associated with stretching and lacerations of the lips and mouth region.



This individual died of a self-inflicted, contact, 12-gauge shotgun wound to the superior aspect of his neck underneath his chin. Note approximation of the wound margins produces a roughly circular perforation with soot. There were extensive lacerations to the face and head. Note the extensive stretch marks at the decedent's face. Note the blood spatter pattern and gunpowder residue on the hand.











These are contact shotgun wounds to the chest. Note the roughly symmetric margin of abrasion with small amounts of soot. More soot was observed within the wound track. Note in (a) another encircling abraded ring corresponding to where the muzzle contacted the body when the gun was discharged. Note in (b–c) there is an encircling vague pink discoloration from carbon monoxide and nitrites in the burning gunpowder that reacted with the underlying muscle and blood, producing this red discoloration.



This is another example of a shotgun-slug wound. Note the extensive fragmentation and laceration to the heart. The last image shows the deformed lead shotgun slug with wadding retrieved from the wound track.



This is a .12-gauge shotgun wound through clothing showing few stippling defects and a larger abrasion adjacent to the entrance defect (a and b). The power piston was retrieved within the wound track (d). Note the abrasions adjacent to the entrance wound due to power piston impact (b). There was extensive fragmentation of the lung (c). Note the multiple exit buckshot-pellet wounds to the decedent's back (e).


CENTIMETERS
INCHES

Distant birdshot-shotgun wounds.



This birdshot-shotgun wound to the forearm is estimated at a range of approximately 3 to 4 feet.



Birdshot shotgun wound with an estimated range of fire of 4 to 5 feet.



Birdshot shotgun wound with an estimated range of fire of 6 to 8 feet.



Birdshot with power piston type cup from a shotgun shell.





This individual was shot multiple times with shotgun slugs. Note the large circular perforations with margins of abrasions typical for entrance handgun wounds (a). Note the elongated margin of abrasion at the middle wound (b), indicating the slug struck the body on an angle, traveling in a left-to-right direction.



Entrance shotgun wound with an estimated range of fire of 3 to 4 feet based on the scalloped appearance of the wound margins.

Mini-14 Ruger rifle.



Flash suppressor.



Contact Ruger mini-14 gunshot wound with a .223 bullet. Note the flash suppressor burns with soot deposition.



Internal injuries caused by a .223-caliber high-velocity military bullet.



Entrance gunshot wound to the roof of the mouth in the skeletonized remains of this individual with a history of depression. The remains were found with a handgun.



This is the inner aspect of a fractured portion of skull with a roughly circular perforation and internal beveling visible at the inner aspect of the skull indicating this to be an entrance gunshot wound.



Entrance gunshot wounds to the head demonstrating internal beveling of the inner calvaria.



Exit gunshot wound through the skull. This image demonstrates the surface of the skull with external beveling typical for an exit gunshot wound.



These defects at the external surface of these skulls were produced by an entrance tangential gunshot wound. This demonstrates a keyhole deformity with both internal and external beveling. The bullet typically strikes the bone tangentially, producing internal beveling at the entrance side. Then it will often fragment and partially exit the body. The exit side will have external beveling.

Burns

9

CHARLES A. CATANESE AND GERARD CATANESE

Introduction

Burns may occur following exposure to heat (thermal burns), electricity, chemicals, or radiation.

First-degree burns are the most superficial and involve the epidermis. They appear as a red discoloration of the skin. An example of this would be sunburn without blister formation. S*econd-degree burns* have deeper penetration of injury involving the epidermis and dermis causing blister formation. An example of this may occur when one touches a hot pot on a stove and pulls the hand away quickly. *Third-degree burns* are full thickness, involving the epidermis, dermis, and subcutaneous layer, and appear as collapsed blisters with skin sloughing and red-to-brown discoloration. *Fourth-degree burns* have even deeper penetration of damage, often with charring and exposed underlying tissue including bone. The bones may be fractured from intense heat and the internal organs may have a firm, discolored, and shrunken appearance.

Burns following exposure to heat are *thermal burns,* which may occur following contact with hot liquid or fire. Children may be scalded while left unattended in a bath tub. They may inadvertently hit the hot water knob to increase hot water flow. They may jump into a bath tub full of very hot water, scalding their feet. One must exercise great care in evaluating these cases as they may be a result of abuse or neglect. A child with both feet scalded with scarring around a shoe pattern is more likely the result of abuse or neglect. A child who is waiting to take a bath will not usually have shoes on and will most likely step one foot into the tub at a time. The burns will be on one foot but not usually both. Both feet scalded at once may indicate dunking into hot water as punishment.

If an individual dies and is placed in a tub full of hot water after death, the body will develop thermal injury more readily than if a living body was placed in the same water. A living body can counteract heat injury by vasodilation and circulating the heat to the body's core away from the surface, thus providing some protection to the skin. A dead body left in warm water will quickly develop postmortem thermal burns that appear as skin slippage. Decomposition may also present with skin slippage and blister formation. An individual may sustain full thickness burns to greater than half of his or her body and still be conscious without immediate death. Death often occurs later due to electrolyte imbalances or infection.

Also, mortality increases with age. Second- to third-degree thermal burns to half the body's surface would much more likely kill a senior citizen than a child. Second-degree burns are more painful than third- or fourth-degree burns due to less damage to nerve endings.

Antemortem burns may be characterized by fluid-filled-blister formation. To have fluid-filled blisters in a nondecomposing body in a nongravity-dependent area not adjacent to an area with more extensive burns with contracted tissue, one needs a blood pressure and a beating heart. Antemortem blisters also typically have a red base with surrounding erythema. This concept remains controversial in some jurisdictions. Also, a dead body from a house fire will decompose at a much slower rate than a dead body not exposed to smoke and intense heat Smoke and heat serve as preservatives. Low heat will accelerate the putrefication process. Radiant heat in a dry environment will quickly cause tissue to become firm and dehydrated, often with hair still present. This depends on the amount of heat and humidity and the duration of exposure. Also, intense heat may produce postmortem artifacts that may be misinterpreted as antemortem injury, such as an epidural hemorrhage. Epidural hemorrhage may be postmortem and is caused by heat-related contracture of the dura mater forcing blood from adjacent vessels into the epidural space. Subdural hemorrhages do not occur in this manner and are antemortem injuries.

Thermal burns sustained by fire may be accompanied by smoke inhalation. In general, most fatalities from house fires are caused by smoke inhalation. Decedents dying directly in house fires usually have mostly postmortem burns. Fire fatalities that occur outside in an open space often do not have associated significant smoke inhalation because the smoke rises rapidly and is not inhaled. In the case of a flash fire, inhaled super-heated gases damage the upper airways, including the laryngeal mucosa, and causing death from reflexive closure of the airway at the level of the vocal cords with asphyxia and eventual fatal arrhythmia. The effects of smoke inhalation are often reflected by the amount of carbon monoxide present in the blood. This depends on the nature of the burning material.

There are often other significant poisons associated with burning materials that can rapidly contribute to death, such as hydrogen cyanide. A fire victim does not need a lethal level of carbon monoxide to die of smoke inhalation. Carbon monoxide is produced from incomplete combustion of organic fuels. Carbon monoxide, in the absence of smoke, is a colorless, odorless gas that reversibly binds the hemoglobin molecule approximately 200 times greater than oxygen, resulting in hypoxia and possible death. Levels of carbon monoxide that exceed 50% saturation are considered life threatening, but may cause death with levels less than 26% saturation. Carbon monoxide levels of greater than 80% are possible. These levels need to be correlated with the physiologic disease state of the individual's body, including heart disease, for example. Someone with marked coronary-artery atherosclerosis would often require much less carbon monoxide exposure to produce death than a young healthy individual with slight atherosclerosis. Cigarette smokers may reach carbon monoxide levels of 10%. Carbon monoxide levels of 15–30% are associated with dizziness, nausea, and headache. Cherry-red lividity first becomes apparent at levels of 30–35%. The half-life for carboxyhemoglobin elimination in a resting adult at sea level is generally 4 to 5 hours. This may be reduced to 80 minutes following administration of pure oxygen, and may be further reduced to 24 minutes by using oxygen at 3 atmospheres of pressure. Primary elimination of unchanged carbon monoxide occurs by pulmonary excretion. Also, if there is more than one fatality without obvious cause, one should consider carbon monoxide poisoning.

Electrical burns may be due to low- or high-voltage exposure. The electrical current may be direct or alternating in nature. Alternating current is more likely to cause a fatal cardiac arrhythmia than direct current. High voltage is generally defined as greater than 1000 volts for alternating current and greater than 1500 volts for direct current. High-voltage burns are usually associated with extensive obvious injury. Low voltage is generally defined as being less than 1000 volts for alternating current and less than 1500 volts for direct current. Low-voltage burns may present with no visible marks to the body's surface at all. The degree of injury depends on many factors, including the duration of exposure and the amount of heat generated.

Electrical burns may also occur as a result of a lightning strike. Lightning bolts occur with an enormous short-term release of electricity, often producing minimal injuries. Lightning strikes may also produce a fern-like red pattern at the skin's surface. Patterns similar to this may be observed in high-voltage electrocution. These types of electrical discharges present with different autopsy findings. The mechanism of death is usually arrhythmia and more likely to occur if the current passes directly through the heart. Death may also occur due to asphyxia if there is interference with the central nervous system's respiratory centers or paralysis of the chest muscles. To complete an electrical circuit one needs an entrance and exit point for electricity to pass through the body. An otherwise healthy individual may be found lying barefoot and on a damp floor next to a power tool with a frayed electrical cord. This is why adequate scene investigation is crucial. It is also important to keep the electrical device as evidence to be tested, and to prevent any other fatalities. There may or may not be burns to the body's surface at autopsy.

Chemical burns are due to exposures to caustic substances. These burns most often involve injury to the skin or mucosa, leaving red discoloration or sloughing of the superficial layers. More extensive injuries may involve damage to the underlying tissue including bone. This depends on the strength and nature of the caustic substance, which include acids, bases, and other chemicals that can damage the body. Individuals may die acutely following chemical burns from many different mechanisms including hemorrhage, infection, dehydration, or they may die many years following such injuries. For instance, if an individual attempts to commit suicide by ingesting lye 20 years earlier and later develops esophageal cancer as a result of these burns, the manner of death would be suicide. Children may accidently drink caustic substances, leading to gastrointestinal perforation that may lead to adhesion and gastrointestinal obstruction many years later. In this case, the manner of death would be accidental. It is always very important to find out the initial event that starts the ball rolling in the sequence of events that eventually leads to an individual's demise.

Radiation is defined as energy distributed as waves or particles across the electromagnetic spectrum. This includes electric, radio, radar, microwaves, infrared, visible light (lasers), ultraviolet light, x-rays, gamma rays, and cosmic radiation. Waves are characterized as having long wavelengths and low frequencies, whereas particles have short wavelengths and high frequencies. The types of biological effects vary greatly depending on the type of radiation, duration of exposure, and intermediate barriers. Acute exposure to skin may range from erythema to overt necrosis with eventual epidermal atrophy and dermal fibrosis. Biological effects include cataracts, burns to the retina and skin, necrosis, fibrosis, and cancer. Generally speaking proliferating cells are affected more substantially with acute exposure as indicated by damage to the gastrointestinal and hematopoietic systems with increased risks of infection, nausea, vomiting, diarrhea, and hemorrhage. Damage to DNA may eventually lead to many different forms of cancer.



Soot within the nares due to smoke inhalation.



Smoke inhalation with soot deposition on the airway mucosa of the larynx and trachea.



Microscopic view of lung with soot deposition in the distal bronchi.



Microscopic view of airway with soot deposition at the surface of respiratory epithelium.



First-degree burn characterized by red discoloration with injury limited to the epidermis.



Second-degree thermal burns characterized by fluid-filled-blister formation. Second-degree burns include damage to both the epidermis and cermis and are often more painful than third-degree burns due to less destruction of nerve endings.



Second- to third-degree thermal burns. These areas demonstrate fluid-filled-blister formations that were interpreted as antemortem. To have fluid-filled-blister formation associated with thermal injury, one usually needs to have a blood pressure. Fluid-filled blisters generally do not occur due to putrefaction in burn victims due to the preservative effects of fire and smoke. Postmortem blister formation may occur in gravity-dependent regions without significant thermal damage or adjacent to regions with soft-tissue heat-related contractures. Also, postmortem blisters lack vital reaction.



First- to third-degree thermal burns involving the posterior aspect of the left thigh and gluteal region. The right leg is without thermal burns. First-degree thermal burns in this picture are characterized by the red discoloration without blister formation or skin slippage. Note the areas of collapsed blister formation, which are consistent with a postmortem burn. Sometimes it is difficult to interpret antemortem burns if continued heat causes fluid-filled blisters to collapse and fluid to evaporate. Most fire fatalities succumb from smoke inhalation before extensive burns occur.



Postmortem second- to third-degree thermal burn with skin slippage and collapsed blister formation.



Full-thickness or third-degree burns in an individual who lived hours after being shot in the head and having his or her residence set on fire to destroy evidence. Full thickness refers to involvement of the epidermis, dermis, and subcutaneous layers. These are often less painful than second-degree burns due to more complete damage of nerve endings in the latter.



Note the sparing of thermal injury at the bottom of the decedent's foot due to protection by a shoe.



Antemortem third-degree burns. This is self-immolation of an individual who was wearing sandals. Note the lack of thermal injury in the region protected by the shoe strap.



This image demonstrates postmortem second- to third-degree thermal burns to the sole of this foot. Note the wrinkled thick skin demonstrating skin slippage. There was minimal underlying fluid accumulation or blister formation.



Postmortem fourth-degree thermal burns with extensive charring and exposed muscle and bone. Note the pugilistic stance of the body with arms raised (b). Also note the postmortem skeletal fractures due to extensive heat (c).



This individual was wheeled out of a building in a shopping cart and set on fire. Note the postmortem cracking of the skin due to heat exposure. This is indicated by the exposed yellow subcutaneous tissue with no hemorrhage. There were extensive fourth-degree thermal burns to the entire body.







Extensive third- to fourth-degree thermal burns with partial skeletal fragmentation due to the wick effect, which refers to a self-perpetuating, low-intensity flame following ignition of certain materials contacting the body, where the skin is cracked from heat and the underlying fatty tissue is rendered into oil that is absorbed into the charred clothing, producing a wick. This low-level heat can produce extensive destruction to a body over hours.



This is a rare finding of decomposition after extensive thermal injury and exposure to smoke. The decedent was involved in a fatal fire and the body was not discovered for several days after being soaked in water following fire extinguishing. Note the microorganisms and mold growing at the body surface shown by the gray-white discoloration. Putrefactive changes were markedly inhibited due to the effects of exposure to smoke and heat.



These are all examples of homicides where apartments or houses were set on fire to destroy evidence. Figures (b–d) are examples of antemortem stab wounds that have been altered by postmortem thermal burns. Note that the margins are relatively sharp and do not appear as though the skin has cracked secondary to heat exposure. Upon internal examination, these injuries become much more apparent with hemorrhage and blood accumulation. Note in (a) areas of cracked skin with exposed yellow subcutaneous tissue without hemorrhage, which is indicative of postmortem thermal injuries. Note the wound at the upper aspect of the lateral left neck with hemorrhage due to an antemortem stab wound.



These figures demonstrate postmortem epidural hemorrhage. These can sometimes be misinterpreted as antemortem blunt force trauma. With exposure to flames, the brain and dura mater may contract, and blood may be forced from the small vessels at the inner aspect of the cranial bone and through the dural sinuses, producing epidural blood accumulation that will coagulate with heat.



Extensive postmortem thermal injury with brain shrinkage. Organs exposed to extensive heat will decrease in size largely due to dehydration.



This individual died of an overdose and was found with dried vomitus on her face. Note the red discoloration caused by gastric acids producing burns to her face.



Chemical skin burns caused by spilling sulfuric acid. The sutured linear incisions are due to organ donation with retrieval of bone and soft tissues.



This individual drank a mixture of lye, kerosene and other caustic chemicals. Note the white discoloration from chemical burns at the lips, mouth, tongue, and esophagus.



Note the red to brown discoloration in the abdominal cavity following gastric perforation and leakage of the caustic chemicals into the peritoneal cavity.



Electrical burn on the hand of this individual who reached into a ceiling and grabbed a live wire. He was standing on an aluminum ladder wearing shorts. His leg contacting the ladder completed the circuit through his heart, producing a fatal arrhythmia.



This individual fell from a subway platform onto the third rail and sustained these electrical burns.



These are examples of second- to third-degree electrical burns caused by inadvertently contacting live wires at construction sites. These individuals died as a result of a fatal cardiac arrhythmia. They fell to the ground lifeless within about 15 to 20 seconds after contact.



This individual was found lying next to an electrified subway rail with his pants down, and an electrical burn to his penis. He was lying in a puddle of urine and was markedly intoxicated at the time of his death.



These individuals died of heart disease while taking a bath. These are examples of second- to third-degree postmortem burns due to being submerged in warm to hot water. Postmortem burns occur with less heat than antemortem burns. Note the red discoloration with skin slippage and a sharply demarcated border defining the submerged and unsubmerged areas. To help the viewer distinguish between these regions we placed a line adjacent to this demarcation. Individuals who drown in bathtubs have some contributing factor dictating why they could not keep their head above the water. They maybe neurologically compromised or intoxicated. People with seizures may accidentally drown.



Child abuse cases with homicidal scalding. Image (a) demonstrates second- to third-degree burns to both feet and ankles from repeatedly being dunked in hot water. Images (b–d) show skin grafting with therapeutic intervention in a child with fourth-degree burns who was left sitting in scalding water.



These are fasciotomy incisions made by physicians for medical therapy to relieve pressure in extremities.



Identifications may be very challenging in fire fatalities. These cases may require dental analysis for identification. Incisions may be made in the face to access the teeth. Funerals in such cases are closed casket due to the severe extensive nature of the injuries.



Swelling of the tongue due to inhaling super heated gases in an individual who survived for 1 day.



This individual crashed an airplane and sustained extensive blunt force trauma. These images demonstrate an antemortem subdural hematoma altered by extensive postmortem thermal injuries.

Asphyxia

10

CHARLES A. CATANESE AND BARBARA K. BOLLINGER

This is a general term used to describe decreased oxygen uptake or use, together with decreased carbon dioxide elimination.

Airway obstruction may occur by smothering, neck compression, foreign body aspiration, excess secretions or swelling of the airway, etc. *Smothering* is defined as external occlusion of the mouth and/or nose which prevents air exchange. Children may *aspirate foreign bodies* such as peanuts, hotdogs, popcorn, watch batteries, coins, etc. Adults who aspirate food are invariably neurologically compromised or intoxicated. Airway obstruction due to *excess mucus or swelling* as with asthma or anaphylaxis can produce asphyxia. Also various body positions may produce airway obstruction *(positional asphyxia)* as with occupants of motor vehicles trapped after collisions or intoxicated people passing out and sliding into awkward positions that prevent chest expansion and air exchange.

Autopsy findings associated with *smothering* may be very subtle or non-existent. Findings may include abrasions around the nose and/or mouth that *cannot* be explained by other means (i.e., resuscitative efforts). Great force is applied to the mouth and lips which may cause tears to the frenulum of the lip, the mucous membrane that connects the inside of the lip to the corresponding gum. Smothering may occur with the use of hands or by placing an object over a face, such as a pillow.

Depending on the degree of force applied and the structures compressed, there may or may not be petechiae present on the skin of the face, mucous membranes or eyes. Arguably, the greater the disparity in size between the perpetrator and the victim (i.e., adult and child), the less likely there will be a demonstrable injury due to the overpowering relative nature of this type of struggle. It is important that in cases of suspected smothering, experienced police interrogators and medical investigators perform the interviews. In cases where autopsy findings are very subtle, well-documented descriptions of the circumstances with specific details are extremely important.

Chemicals can produce asphyxia. *Inert gases* like methane or carbon dioxide will displace oxygen from the air and produce asphyxia by depletion or replacement of oxygen. Various *poisons* such as carbon monoxide or cyanide interfere with oxygen uptake and utilization, respectively.

Chest compression can produce asphyxia by *preventing air flow* into the lungs.

Neck compression as with *hanging and strangulation* can also produce asphyxia by obstruction of various neck structures including the airway, venous circulation and arterial circulation.

Interpretation of autopsy findings with respect to *hanging vs. strangulation* can be challenging. Each subheading below will describe the presenting classic and most common features, and then elaborate on less common features. It is important to realize that there is overlap between how the two present; depending on how the act is carried out, they may appear very similar. In establishing the manner of death, one should consider all aspects of the case including the past medical history (i.e., depression, end stage cancer, etc.), scene investigation and autopsy findings.

Hanging refers to ligature compression of the neck mitigated by the gravitational forces of the hanging head, causing partial or complete obstruction of the neck structures including blood vessels and the airway.

In a typical non-judicial suicidal hanging an individual places a ligature with a slip knot encircling the superior aspect of his or her neck. He or she secures the other end of the rope to a fixed support and allows the entire or partial body weight to pull downward, occluding the neck structures until loss of consciousness and death. In this case there should be furrow pattern that matches the overlying ligature which forms an inverted "v" mark or indentation, extending upward at the superior aspect of the neck and head. With the entire body weight pulling downward, all of the neck structures are (i.e., arterial, venous, and airway) are usually occluded at the same time and one would not expect to find petechiae in the face or eyes. There are typically no hemorrhages or fractures of the neck structures or other injuries to the body indicating a struggle. The cervical vertebrae are rarely fractured in suicidal hangings. When the body hangs for longer periods of time the furrow indentation becomes more prominent. Individuals cut down shortly after this act may have little or no furrow mark. This depends on the type of ligature used. A wide soft ligature will leave less of a mark than a narrow, more resistant ligature. If the body is left to hang for days, decomposition with stretching may eventually lead to the head being pulled away from the body.

In the case of a judicial hanging, the body is dropped from a height to produce sufficient force to fracture the upper cervical vertebrae resulting in spinal cord injury with cardiac and respiratory satiation.

An individual hanging in a sitting or lying position may have partial occlusion of the neck structures before loss of consciousness ensues. In situations where the body is adjacent to another structure, the individual may partially pull his or her body up and down, causing varying degrees of pressure–release before loss of consciousness. This will produce a similar effect to what is seen in strangulation. In these circumstances, the up and down motion of pressure release will obstruct different neck structures at different intervals. Venous circulation requires the least amount of pressure for occlusion, as compared to the arterial system and the airway. When venous circulation is obstructed without the arterial circulation, the higher pressure arterial blood beats through the capillary beds rupturing small blood vessels producing petechiae. As this process continues the hemorrhage size increases and may become confluent. These are most obvious within the sclera and conjunctivae. These movements may also produce hemorrhages or fractures to the neck structures including the airway cartilages and hyoid bone. These findings are more characteristic for strangulation, but may be seen in hangings.

Though unusual, people have been known to tie their hands behind their backs during the process of hanging themselves. The individual may have tried to complete this act several times in the past but the will to survive overpowered the will to end life. The tied hands are usually loosely tangled and not tightly tied. This will give the individual enough time to prevent himself from stopping the process. There are usually no other signs of a struggle or defensive type injuries.

With a free hanging and total body weight suspension, an otherwise healthy individual, using a slip knot, would be expected to lose consciousness within 15 to 20 seconds, and suffer irreversible brain damage within 4 to 6 minutes.

Hanging is usually suicidal, but may be accidental or homicidal.

Strangulation may be by ligature or manual. A *ligature* is something flexible that can encircle the neck, like a cord, belt or piece of clothing, etc. *Manual* strangulation refers to the use of one's hands leading to compression and blockage of the neck structures.

Manual strangulation is usually characterized by multiple irregular, angulated, abraded contusions around the neck. The marks may be curvilinear, corresponding to fingernail prints. These external marks can be somewhat variable and can range from a few to many.

Ligature strangulation is usually characterized by a horizontal furrow or mark pattern around the neck. The extent of these injuries depends on the type of ligature, how broad and soft it is, and the amount of struggle, etc.

The act of strangulation is often a very physically dominating, often non-premeditated, way of killing somebody. This act takes time and comes with the risk of injury to all those involved. The individual strangled is usually smaller and of weaker strength. Often a sexual component to the assault exists and a rape kit should be performed in all cases of suspected strangulation. Petechiae are usually present in the face and eyes. There are usually hemorrhages in the strap muscles of the neck, and there may be fractures of the laryngeal cartilages and/or hyoid bone. These fractures are more common in older victims because the cartilages are more calcified, brittle and less elastic. Older people may also have osteoporosis. Younger victims or children tend to have more flexible upper airways that often will stretch or collapse rather than fracture. Depending on how great the struggle, the amount of force used, and the type of neck compression, there may or may not be petechiae and/or hemorrhages above the ligature or region of neck compression. The presence of petechiae formation is more likely when there is a pressure–release component associated with a struggle or if less variable force is applied and if the ligature is wide with a large surface area. The presence of petechiae is less common when the force is very strong, consistent, and applied with a small surface area ligature. The latter example is more similar in nature to a hanging. Victims of strangulation often have defensive type injuries including other abrasions and contusions to their body.

It is possible to ligature strangle yourself; it is not possible to manually strangle yourself. If one is able to apply enough force to lose consciousness manually, revival occurs after the pressure is released. Continued force is necessary for death to ensue.

Someone murdered by ligature strangulation may die within a similar time frame as someone hanged; however, the time frame is usually longer. If there are multiple petechiae with hemorrhages and fractures of the neck structures, whether ligature or manual, the time frame may be much longer. This latter example usually indicates pressure–release, pressure–release over several minutes until loss of consciousness, and then continued pressure for several more minutes until death occurs. If an individual is released shortly following loss of consciousness, revival may follow.

Proper autopsy technique dictates that the *brain and visceral organs be removed prior to a layered neck* *dissection* being performed. Photographs of the neck dissection in layers are recommended.

Drowning occurs when water is inhaled, filling up the alveolar spaces and preventing gas exchange. The manner of death will vary depending on how the individual came to be in the water. If the event is not witnessed the manner often remains undetermined. Water in the lungs (pulmonary edema) and the paranasal sinus is often present. The degree of pulmonary edema may vary in a fraction of the cases due to the heart beating after respirations cease. As the heart beats, before eventual asystole, some of the fluid in the lungs will be absorbed. An adult may drown in a big pool or ocean but not in a small pool or bathtub unless *neurologically compromised or intoxicated*. Homicide victims are sometimes placed in a water-filled *bathtub* to wash away evidence. The story given may be, "I found him in the tub, and he must have drowned." Common sense would dictate that an individual does not need to move very much to get his head above the water.



Suicidal hanging. Note the black cord (a) that matches the underlying furrow pattern at the superior aspect of the neck with upward extension at the left side of the face. Also note that the individual's lividity becomes more apparent and is fixed at the level of the upper thigh extending down to the feet (b). This fixed lividity pattern is appropriate for an individual who remained in an upright position for many hours after death. If his lividity was fixed posteriorly and not inferior; this would indicate prior scene alteration. There were hesitation marks at the wrist with blood seeping downward due to gravity (c).



Suicidal hanging with matching rope and furrow pattern circling superior aspect of the neck forming a slight inverted "V" pattern behind the right ear.



Suicidal hanging with computer cord.



Suicidal hanging with nylon bag strap.



Accidental hanging in an individual with Alzheimer's dementia who enjoyed whirling around in circles while sitting on a desk chair. The person was left unattended for a short period of time by chronic care nursing staff, and got tangled in the cord from a window blind. This furrow pattern matches a blind cord as a ligature.



Suicidal hanging with chain.



Suicidal hanging by braided belt. Note the matching skin pattern.



Suicidal hanging with earphone cord (a). This individual also took part of the cord and loosely wrapped his hands behind his back so he would not be able to reach up and prevent the hanging from being successful. This is not very unusual for people to hang themselves and loosely tie their hands in this fashion. Note the force of the ligature caused the tongue to protrude from his mouth (b). Also note the dark postmortem drying of the mucosa exposed to air.



Homicidal ligature strangulations with horizontal cord marks surrounding the necks. Note the other injuries to the decedent's face in (b), including abrasions. Both of these victims were also sexually assaulted.



Homicidal ligature strangulation in a prostitute who had large amounts of cocaine and heroin in her system. Her fingers were also noted to be crushed by a pair of pliers during the assault.



This is a suicidal ligature strangulation in an individual with a longstanding history of depression who was found in a locked secured apartment with a suicide note. Note the cord is tied tightly around his neck. There is also a moderate state of putrefactive change with skin slippage, bloating, and purging.



Manual strangulation. Note the multiple irregular abraded contusions surrounding the neck. There were multiple areas of strap muscle hemorrhage and a fractured hyoid bone. She was sexually assaulted and left in a stairwell. There were multiple petechiae with areas of hemorrhage in the sclerae and conjunctivae of each eye. The constellation of these findings are typical for a homicidal manual strangulation.



Manual strangulation. Note the abraded contusions to the anterior neck.



Manual strangulation. There is early decomposition with skin slippage. There are vague abrasions and superficial contusions at the neck. As decomposition progresses it may become more difficult to interpret these findings.



This individual was punched in the face and then yoked from behind during a sexual assault. There were no visible external injuries to the neck except this contusion at the border of the right chin. Careful internal examination after the brain and visceral organs had been removed revealed areas of hemorrhage within the anterior strap muscles and posterior paraspinal muscles. There were also petechiae with hemorrhage of the sclera and conjunctivae. This individual was found face down and the eye hemorrhages were originally thought by some to be associated with postmortem lividity. The perpetrator was caught after bragging about the assault.



This image demonstrates an eye from a person who hanged him or herself. Note there are no petechiae or scleral/conjunctival hemorrhages. The decedent's weight pulling down on the ligature produced a significant enough force to obstruct the entire blood supply to the head. Therefore, there was no pressure–release mechanism, leading to capillary rupture and hemorrhage. The absence of scleral or conjunctivae hemorrhages is more typical in hanging fatalities.



Anterior neck dissection after the visceral organs and brain have been removed. Part of the undersurface of the platysma muscle is visible at the top of this image adjacent to the yellow subcutaneous tissue of the neck. The anterior strap muscles are visible directly above the label and are free of antemortem injury. There were no hemorrhages or fractures of the remaining neck structures. The absence of these injuries is common in hanging fatalities.





These figures demonstrate anterior neck dissections with no hemorrhages. The absence of hemorrhage is typical for most hangings.





This demonstrates a normal hyoid bone with no fractures or contusions.



Some cases may require further evaluation including a posterior neck and back dissection. This case involved a 12-year-old African American child who was strangled. Dissection should be done in a layer-by-layer fashion until the surface of bone is exposed. It is important to dissect the arms as well, which may demonstrate contusions from being held during a struggle. There were no hemorrhages found in this case. It is often more difficult to externally visualize contusions in darker-skinned individuals.







Strangulation. Hemorrhage of the medial left sternocleidomastoid muscle.



Strangulation. Note the large hemorrhage to the anterior neck structures including the left sternohyoid muscle.



Strangulation. Note the hemorrhage in the anterior neck structures.



Strangulation. Note the hemorrhage overlying the left superior horn of the thyroid cartilage. The underlying cartilage was fractured.



Note the fractures of this hyoid bone with vague hemorrhages in a decedent with slight to moderate decomposition. Fractures of the hyoid bone are often found in association with homicidal strangulation. The presence of a hyoid bone fracture does not indicate that the case must be a strangulation and the absence of fractures to the hyoid bone does not indicate the decedent was not strangled. Fractures can occur as a result of a blunt impact as well.



Strangulation. Posterior neck dissection with hemorrhage to the superior aspect of the semispinalis capitis muscle.



Cases of strangulation demonstrating petechiael hemorrhages of the sclera and conjunctivae.





These demonstrate a range of scleral and conjunctival hemorrhages. As varied degrees of neck pressure continue after petechiae formation these hemorrhages progressively become larger and possibly confluent until death ensues.



Petechiael hemorrhages of the face.



Strangulation. Petechiael hemorrhages within the mucosal surface of the mouth.



Petechiael hemorrhages at the surface of the heart associated with asphyxia due to chest compression.



Strangulation. Petechiael hemorrhages within the mucosa of the tracheal and laryngeal cartilage.



This individual was strangled and then hanged in an attempt to stage a suicide and cover up this crime. Note the injuries to the back of the decedent's feet during a struggle and the haphazard scuff marks to the floor surrounding the body (b–c). Also note the decedent's hair and clothing stuck under the noose (d–e). There are also injuries with hemorrhage to the neck structures. These findings are completely inconsistent with a suicidal hanging.



This individual was abducted, bound, and had multiple superficial stab wounds associated with a sexual assault. Her head was wrapped in multiple layers of plastic that covered her mouth and nose.



This individual committed suicide by taking multiple pills and tying a plastic bag tightly over her head. It is the author's experience that it is better to pend these cases for toxicology.







Homicidal asphyxia due to airway obstruction. This individual was found in a moderate to marked state of decomposition within her apartment. She was reportedly dealing drugs and was found tied up with a piece of cloth stuck down her mouth and throat.





Anal trauma with abrasions and lacerations due to sexual assault during strangulation. One should always assume strangulation victims have been sexually assaulted. A rape kit should always be performed in these cases.





This is an airway from a 2-1/2 year-old who was fed a hot dog by her older sibling. The large size of the hot dog piece caused it to get wedged in her throat, leading to asphyxia.



This individual had a pencil in his mouth when he collapsed at work. The pencil was inhaled and wedged in the right mainstem bronchus.



This child was found to have a pebble wedged within her right mainstem bronchus, as evident on this radiograph.



These individuals were trapped in machines that caused chest compression and inability to breathe. One was stuck in a box folding machine, another trapped under a car and another stuck under a single-person elevator lift. Note the imprint of the individual's hand (d) while he was struggling to escape, with the blister formation between these finger marks. Also note the pulmonary edema demonstrated by froth coming out of the mouth (f). This individual also had numerous petechiael hemorrhages of the upper trunk, face, eyes, and visceral organs including the heart.



Homicidal asphyxia due to compression of chest and neck. Note the extensive hemorrhage at the superior chest visible at the superior aspect of the Y-shaped incision during autopsy. The lower aspect of this incision is yellow, anemic, and postmortem. This individual was punched, strangled and then the perpetrator sat on her chest during the assault.





Positional asphyxia. These individuals were markedly intoxicated and passed out in positions that prevented them from breathing, thus obstructing blood circulation.



Index

A

Abrasions, 194, 224, 227
Accidental head trauma due to falling television, 173
Acute alcoholism with hepatic steatosis, 100
Acute and chronic bronchial asthma, 37
Acute and chronic pancreatitis in a chronic alcoholic, 105
Acute and chronic track marks hidden by tattoos, 96
Acute and healed peritonitis in a chronic alcoholic, 104
Acute peritonitis, 121
Acute, chronic and healing skin popping lesions, 97, 98
Adenosine triphosphate (ATP), 4, 92
Adipocere, 113, 133
Adult polycystic kidney disease, 54
Airway obstruction
  hotdog, 395
  pebble, 395
  pencil, 395
Altered homicidal stab wound with postmortem blunt force trauma, 254
Amyloidosis, cardiac, 33
Anterior neck dissection, 161
Aortic dissection, 3, 23
Aortic stenosis, 68
Artifacts of therapy, 59, 61, 65
Asphyxia
  accidental, pediatrics, 153, 154
  Cloth gag, 393
  due to un-ruptured placental membranes, 156
Aspiration of brain, 236
Asthma, pediatrics, 155
Astrocytoma, 39
Atherosclerosis
  aortic with aneurysm, 21

  coronary artery, 15
Atypical entrance gunshot wound with contusion, 309
Atypical gunshot wounds, 318, 319
ATP, *see* Adenosine triphosphate
Autopsy dissection, suspected child abuse, 164
Avulsions, 189

B

Bite marks, 207, 208
Blanching lividity, 114
Blunt-force injuries, 189–237
Bloating, 125, 185
Blood aspiration, 236
Blowfly activity, 145
Boat propeller injuries, 274, 275
Brain
  embolism, 236
  shrinkage due to thermal injury, 363
  swelling, 179
Breast carcinoma, 46
Bronchogenic carcinoma, 46
Brown fat microscopy, 188
Bucket handle or corner fractures, pediatrics, 182
Bullet wipe, 301, 303
Bullets
  subadjacent to skin, 304
  new, old and weathered, 339
Bumper impacts to legs, 216
Burns, 353–372
  thermal, 353
  third-degree, 353

C

Carbon monoxide (CO), 91
  poisoning with cherry red lividity, 110
Cardiac tamponade, 17
Central nervous system (CNS), 2, 88
  contusions, 217
Cardiopulmonary resuscitation (CPR), 161
Cerebral artery aneurysm, 42
Cerebrospinal fluid (CSF), 3
Cesarean section, abdominal wall hemorrhage, 72
Chagas' disease, 34
Chemical burns, 354
Chest compression with asphyxia, 373
Chest tube, 69, 70, 74
Child abuse, 150, 170, 174, 181, 369
Chopping type injuries with axe, 259
Chronic
  alcoholism with micronodular cirrhosis, 100
  obstructive pulmonary disease (COPD), 38
  pyelonephritis with urolithiasis, 55
  track marks, 95
Close range gunshot wounds, 296, 297, 298
Coining, Asian folklore remedy, 83
Colloid cyst of third ventricle, 41
Congealing of fat, 117, 162
Conjunctival petechiae, heart disease and resuscitation, 14
Contact gunshot wounds, 291, 292, 293, 294
Contusions, 193, 194, 195
  and ecchymosis with coagulopathy, 234
  old and recent, 163
Cor pulmonale, 20
Coronary artery
  anomalies, 29
  bypass grafting with hemorrhage, 78
  stent placement with hemorrhage, 81
  thrombosis, 15
    due to acute cocaine intoxication, 110
Crushing
  by terrain leveler, 227
  by trash compactor, 185
Cushing's syndrome, 50
Cutdown site, 70

D

Decapitation, 215
Decubital ulceration, 43
Defensive type wounds, 252
Dehydration, pediatrics, 162
Diaper rash, 150
Dilated cardiomyopathy, 2, 20
Dimethylarsenic acid (DMA), 91
Dismembered bodies with saw, 276
Dog feeding, 139, 140, 279
Drowning, pediatrics, 155
Drug packing, 109, 110
Drying artifact, 119
Duchenne's muscular dystrophy, 49

E

Early mummification, 119
Early putrefication, 123
Electrical burns, 354
Embalmed body, 146
Emergency department (ED), 70, 154
Emphysema, pulmonary, 38
Endocarditis, 24, 25
Entrance gunshot wound, 290, 305, 351
  through thick skin, 289
  with clotted blood, 309
Epidural hemorrhage, 230, 363
Epilepsy, 4, 39
Escalator injury, 210
Esophageal polyp, 44
Esophageal varices due to hepatic cirrhosis, 103
Exit gunshot wounds, 283, 311, 312, 313, 314

F

Fasciotomy incisions, 370
Fetal gunshot wounds, 333

Fibromuscular hyperplasia of AV nodal artery, 161
First degree burn, 353, 356
Fixed lividity, 115
Flesh eating bacteria, group a beta-hemolytic streptococcus, 56
Fourth degree thermal burns, 360
Frenulum
  healed laceration, 157
  normal with dried blood, tinged secretions, 159
  postmortem drying, 157
  resuscitative laceration, 152
Fresh track marks, 94
Frozen body, 135

G

Gastric cancer, 46
Gastritis due to chronic alcoholism, 103
Gastrointestinal (GI) bleeding, 5
Gastrostomy feeding tube, 76
Glazer safety ammunition, 337
Graze type gunshot wounds, 314, 324
Gunpowder residue
  soot deposition on hands, 299
  soot on clothing, 301
Gunshot skull fractures, 315
Gunshot wound
  "blowback" blood spatter, 300
  therapeutic alteration, 70
  through eye glasses, 334
  to dog, 339
  with medallion imprint, 331
  with septic complication, 310
  with burns, 334
Gynecomastia due to hepatic cirrhosis, 102

H

Healed gunshot wounds, 340
Healed stab wound, 282
Healing atypical gunshot wounds, 321
Healing skeletal fractures, 183
Hemochromatosis, cardiac, 33
Hemodialysis, arteriovenous graphs, 19
Hepatic cirrhosis
  with coagulopathy, 102
  with jaundice, 99
Homicidal sharp force injury, 196, 282
Hunting arrow injury, 267
Hyperextension injuries to pedestrians stuck by car from behind, 220
Hypertensive cardiovascular disease, 19, 20, 23
Hyperthryoidism with goiter, 50
Hypertrophic cardiomyopathy, 31
Hypostasis, pediatrics, 161
Hypothermia, 51

I

Identification following extensive thermal injury, 371
Impact injuries
  to fence post, 210
  to front windshield, 211
  to gravel, 224
  to side windshield, 211
Impaled on fence post, 278
Inca bone, 184
Incised wounds, 242
Infant crushed in trash compactor, 185
Infective endocarditis (IE), 2
Injury
  caused by baseball bat, 200
  caused by bicycle chain, 203
  caused by gold putter, 199
  caused by hammer, 201
  caused by metal lock, 209
  caused by nail through board, 204
  caused by pipe, 199
  caused by swallowed toothbrush, 205
  due to broken bottle, 242
  produced by tires, 218
  due to dog attack, 280
  to bound extremities, 209
  to ear lobes, 206
Intermediate range of fire, 304, 305, 307
Internal injuries caused by gunshot wounds, 350
Internal lacerations, 227
Internal organs and putrefication, 138
Intra-cerebral hemorrhage, 39
Intubation complications, 65

J

Jugular vein catheter placement with hemorrhage, 79

L

lacerations, 195, 201, 209, 225
ligature strangulation
  homicidal, 381
  suicidal, 380, 381
linear extensions and "swallow-tail" injury, 244
lividity and contusions, pediatrics, 150
Lysergic acid diethylamide (LSD), 88

M

3,4-Methylenedioxymethamphetamine (MDMA), 90
Maceration, 136
Machete injuries, 258
Macronodular cirrhosis due to viral hepatitis, 101
Mag-safe ammunition, 338
Mallory-Weiss tears due to chronic alcoholism, 103
Manual strangulation, 382, 383
Marbling, 123, 126, 128
Marked decomposition with skeletonization, 134
Marked putrefication, 131
Meningioma, 40
Meningitis, cryptococcal, 47
Mini-14 ruger rifle, 350
Moderate putrefication, 126
Mold and mildew formation, 122
Mongolian spot, 163
Monomethylarsonic acid (MMA), 91
Morbid obesity, 14
Motor vehicle impact damage, 211
Motorcycle collision, 221
Mummification, 132, 142
Myocardial infarction, acute, 16, 17, 18
Myocarditis
  asperigillosis, 35
  candidal, 35
  eosinophilic, 34
  toxoplasmosis, 34
  viral, 35

N

Nail guns, 330
Nasogastric tube
  aspiration of brain, 82
  misplacement of, 82
Neck dissection, 384, 386, 387
Neonate putrefication, 136
Neurofibromatosis, 48
Normal, fresh, and fixed organs, 7–12

O

Omphalocele, 187
Organ procurement, heart, 151
Osteogenesis imperfecta, 183
Osteoporosis, 5, 49, 223

P

PCP, see Phencyclidine
Pacemaker lead with thrombus, 82
Pattern injuries caused by car grills, 214
Peptic ulcer disease in a chronic alcoholic, 104
Periorbital ecchymosis "raccoon eyes," 194
Peripartum cardiomyopathy, 20
Peripheral vascular disease, 43
Petechiael hemorrhages
  of airway, 390
  of face, 390
  of heart, 390
Phencyclidine (PCP), 90
Photographic imagery, 1
Pick's disease, 40
Pickaxe injury, 277
Pituitary adenoma, 40
Plastic bag, asphyxia, 392
Pleural adhesions, 38
Pompe's disease, heart, 35
Portal vein stent placement with hemorrhage, 77
Positional asphyxia, 373, 398
Posterior neck and back dissection, 386

Postmortem
    abrasions, 140
    eating by fish and crustations, 144
    feeding by domestic pigs, 143
    feeding by domesticated cat, 142
    feeding by mice and rats, 144
    water burns, 122
Pregnancy
    first trimester, 188
    late second trimester, 186
Pseudostippling, 309
Pulmonary edema, 28, 159
Pulmonary thrombo-embolus, 30
Puncture wounds with nail through board, 273
Purple head sign, 14
Putrefactive
    blister formation, 124
    purging, 125
Putrefication
    following sepsis, 128
    with thermal injury, 356
Pyogenic liver abscess with chronic pancreatitis due to chronic alcoholism, 106

R

Radiator impact head injury, 210
Renal cyst, simple benign, 54
Resuscitation artifact, pediatrics, 149, 150, 161, 170
Rhabdomyosarcoma, 46
Ricochet bullets, 323
Rigor mortis, 112

S

SAH, see Subarachnoid hemorrhages
Sarcoidosis, 36
Scalding injury, child abuse, 369
Scars
    demonstrating past suicide attempts and destructive behavior, 108
    interpretation, pediatrics, 181
Scleral and conjunctivae hemorrhages, 389
Scleral and conjunctivae petechiae, 388
Seat belt injuries, 212
Second-degree burn, 353, 356
Second- to third-degree burn, 367
Septic complications of blunt force trauma, 69
Serrated and Ginsu knife injuries, 262, 263
Sexual assault with strangulation, 394
Sharp force injury
    by box cutter, 242
    with broken glass from picture frame, 270
Sharps, improper disposal, 82
Shoe pattern injuries, 198
Shored exit gunshot wounds, 317
Shotgun wounds, 344, 345, 346, 349
Sickle cell disease, 52, 53
Skeletal fractures due to falls from great height, 224
Skin
    elasticity (turgor), postmortem, 162
    slippage, 135
Skull fractures, 213
    postmortem thermal, 372
Small vessel disease, 19
Smoke inhalation, 355
Smothering, homicidal, pediatrics, 158
Stab wounds, 241
    altered by decomposition, 282
    altered by fire, 281
    therapeutic alteration, 69
    with flat head screwdriver, 272
    with hilt marks, 245
    with ice pick, 265
    with knife and broken antenna, 266
    with knife blade stuck in body, 257
    with Phillips screwdriver, 271
    with scissors, 264
    with skin tension, 241
    with thermal injury, 362
Steering wheel impact injury, 212
Stillborn, second trimester, 187
Stomping injury, 177, 198, 266
Strangulation staged as a suicidal hanging, 391
Subarachnoid hemorrhage, 3, 228
Subdural hematoma, antemortem thermal injury, 372
Subdural hemorrhage, 231
Subway train injuries, 222
Sudden infant death syndrome (SIDS), 66, 147, 154, 159, 160
Suicide
    hanging, 376, 377, 378, 379, 380
    overdoses by ingestion of drugs, 107
    sharp force injury, 246, 247
Superficial gunshot wounds, 329
    tracks, acute and healing, 320

T

Tetrahydrocannabinol (THC), 89
Tache noire, 118
Tangential gunshot wounds, 326, 327, 328, 338
Tardieu spots, 115
Thymic and visceral petechiae, pediatrics, 160
Thyroidectomy hemorrhage, 73
Tissue procurement, 60
Tongue and mouth swelling due to heat injury, 371
Transbronchial lung biopsy with hemorrhage, 80
Transjugular intrahepatic portosystemic shunt (TIPS), 77

V

Volvulus
    cecal, 45
    small intestine, 44

W

Water, postmortem burns, 122
Wick effect, 360
Wolff–Parkinson–White syndrome (WPW), 2

FORENSICS & CRIMINAL JUSTICE

Color Atlas of
Forensic Medicine and Pathology

New York City has the largest medical examiner's office in the United States, and the Brooklyn division is the busiest of the five boroughs. Charles A. Catanese received his Forensic Pathology fellowship training in New York, and then worked full time as a Medical Examiner in the Brooklyn office for more than 10 years. He has personally performed more than 4000 autopsies, including over 400 homicides. Dr. Catanese has worked through several disasters, including TWA Flight 800, AA Flight 587, and more than nine months on the World Trade Center fatalities. He is currently the Chief Medical Examiner of Orange County, New York. Drawing on his wealth of knowledge and experience in solving some of the most difficult cases a forensic examiner could encounter, he assembles hundreds of images from his own work experience to present the ***Color Atlas of Forensic Medicine and Pathology.***

Featuring twice the number of images as any other forensic pathology atlas, the book is filled with high-resolution photos that demonstrate postmortem changes of the human body and the different types of patterns produced in deaths caused by

- Natural causes
- Diagnostic or therapeutic procedures
- Substance abuse
- Poisoning
- Child abuse
- Firearms
- Blunt instruments
- Sharp instruments
- Burns
- Asphyxia

This easy-to-read atlas, created for medical and non-medical personnel, covers basic and advanced forensic concepts that relate to all manners of deaths. The carefully worded, unambiguous text describing each photo and the side-by-side comparisons of similar, yet different, pathologies make this remarkable atlas a powerful teaching tool for all those who must confront and solve the mystery of human demise. A fully searchable DVD version is also available.

4320X

ISBN: 978-1-4200-4320-4

90000

9 781420 043204

CRC Press
Taylor & Francis Group
an **informa** business
www.crcpress.com

6000 Broken Sound Parkway, NW
Suite 300, Boca Raton, FL 33487
270 Madison Avenue
New York, NY 10016
2 Park Square, Milton Park
Abingdon, Oxon OX14 4RN, UK

www.crcpress.com

KNIGHT'S

Fourth Edition

Forensic Pathology

Pekka Saukko | Bernard Knight

CRC Press
Taylor & Francis Group

WITH VITALSOURCE®
EBOOK

Accessing the E-book edition

KNIGHT'S FORENSIC PATHOLOGY
FOURTH EDITION

Using the VitalSource® ebook

Access to the VitalBook™ ebook accompanying this book is via VitalSource® Bookshelf – an ebook reader which allows you to make and share notes and highlights on your ebooks and search across all of the ebooks that you hold on your VitalSource Bookshelf. You can access the ebook online or offline on your smartphone, tablet or PC/Mac and your notes and highlights will automatically stay in sync no matter where you make them.

1. **Create a VitalSource Bookshelf account at** *https://online.vitalsource.com/user/new* or log into your existing account if you already have one.
2. **Redeem the code provided in the panel below to get online access to the ebook.** Log in to Bookshelf and select **Redeem** at the top right of the screen. Enter the redemption code shown on the scratch-off panel below in the **Redeem Code** pop-up and press **Redeem**. Once the code has been redeemed your ebook will download and appear in your library.

No returns if this code has been revealed.

DOWNLOAD AND READ OFFLINE

To use your ebook offline, download BookShelf to your PC, Mac, iOS device, Android device or Kindle Fire, and log in to your Bookshelf account to access your ebook:

On your PC/Mac

Go to ***https://support.vitalsource.com/hc/en-us*** and follow the instructions to download the free **VitalSource Bookshelf** app to your PC or Mac and log into your Bookshelf account.

On your iPhone/iPod Touch/iPad

Download the free **VitalSource Bookshelf** App available via the iTunes App Store and log into your Bookshelf account. You can find more information at ***https://support.vitalsource.com/hc/en-us/categories/200134217-Bookshelf-for-iOS***

On your Android™ smartphone or tablet

Download the free **VitalSource Bookshelf** App available via Google Play and log into your Bookshelf account. You can find more information at ***https://support.vitalsource.com/hc/en-us/categories/200139976-Bookshelf-for-Android-and-Kindle-Fire***

On your Kindle Fire

Download the free **VitalSource Bookshelf** App available from Amazon and log into your Bookshelf account. You can find more information at ***https://support.vitalsource.com/hc/en-us/categories/200139976-Bookshelf-for-Android-and-Kindle-Fire***

N.B. The code in the scratch-off panel can only be used once. When you have created a Bookshelf account and redeemed the code you will be able to access the ebook online or offline on your smartphone, tablet or PC/Mac.

SUPPORT

If you have any questions about downloading Bookshelf, creating your account, or accessing and using your ebook edition, please visit ***http://support.vitalsource.com/***

KNIGHT's

Forensic Pathology

This page intentionally left blank

Fourth Edition

KNIGHT's Forensic Pathology

Professor Pekka Saukko Dr. med. (Vienna, Austria), DMSc, Dr. h.c., FFFLM (Hon), FBAFM (Hon)
Emeritus Professor of Forensic Medicine, University of Turku, Turku, Finland; Member of the German National Academy of Sciences Leopoldina; Honorary Member of the Hungarian Society of Legal Medicine, Royal Belgian Society of Legal Medicine, German Society of Legal Medicine, and Japanese Society of Legal Medicine

Professor Bernard Knight CBE MD, BCh, MRCP, FRCPath, FHKCPath, DMJ (Path), FRSM, FFFMRCP, LLD (Hon), DM (Hon), DSc (Hon), PhD (Hon), DPhMed (Hon), Barrister of Gray's Inn
Emeritus Professor of Forensic Pathology, Cardiff University, Cardiff, Wales; Honorary Member of the Royal Belgian Academy of Medicine, Hungarian Society of Legal Medicine, Finnish Society of Forensic Medicine, German Society of Legal Medicine, and Medico-Legal Society of China

CRC Press
Taylor & Francis Group
Boca Raton London New York

CRC Press is an imprint of the
Taylor & Francis Group, an **informa** business

CRC Press
Taylor & Francis Group
6000 Broken Sound Parkway NW, Suite 300
Boca Raton, FL 33487-2742

© 2016 by Taylor & Francis Group, LLC
CRC Press is an imprint of Taylor & Francis Group, an Informa business

No claim to original U.S. Government works
Version Date: 20150915

International Standard Book Number-13: 978-1-4441-6508-1 (eBook - PDF)

This book contains information obtained from authentic and highly regarded sources. While all reasonable efforts have been made to publish reliable data and information, neither the author[s] nor the publisher can accept any legal responsibility or liability for any errors or omissions that may be made. The publishers wish to make clear that any views or opinions expressed in this book by individual editors, authors or contributors are personal to them and do not necessarily reflect the views/opinions of the publishers. The information or guidance contained in this book is intended for use by medical, scientific or health-care professionals and is provided strictly as a supplement to the medical or other professional's own judgement, their knowledge of the patient's medical history, relevant manufacturer's instructions and the appropriate best practice guidelines. Because of the rapid advances in medical science, any information or advice on dosages, procedures or diagnoses should be independently verified. The reader is strongly urged to consult the relevant national drug formulary and the drug companies' and device or material manufacturers' printed instructions, and their websites, before administering or utilizing any of the drugs, devices or materials mentioned in this book. This book does not indicate whether a particular treatment is appropriate or suitable for a particular individual. Ultimately it is the sole responsibility of the medical professional to make his or her own professional judgements, so as to advise and treat patients appropriately. The authors and publishers have also attempted to trace the copyright holders of all material reproduced in this publication and apologize to copyright holders if permission to publish in this form has not been obtained. If any copyright material has not been acknowledged please write and let us know so we may rectify in any future reprint.

Except as permitted under U.S. Copyright Law, no part of this book may be reprinted, reproduced, transmitted, or utilized in any form by any electronic, mechanical, or other means, now known or hereafter invented, including photocopying, microfilming, and recording, or in any information storage or retrieval system, without written permission from the publishers.

For permission to photocopy or use material electronically from this work, please access www.copyright.com (http://www.copyright.com/) or contact the Copyright Clearance Center, Inc. (CCC), 222 Rosewood Drive, Danvers, MA 01923, 978-750-8400. CCC is a not-for-profit organization that provides licenses and registration for a variety of users. For organizations that have been granted a photocopy license by the CCC, a separate system of payment has been arranged.

Trademark Notice: Product or corporate names may be trademarks or registered trademarks, and are used only for identification and explanation without intent to infringe.

Visit the Taylor & Francis Web site at
http://www.taylorandfrancis.com

and the CRC Press Web site at
http://www.crcpress.com

**Those who have dissected or inspected many bodies
have at least learned to doubt, while those who are ignorant of
anatomy and do not take the trouble to attend to it, are in no doubt at all.**

Giovanni Battista Morgagni 1682–1771
The Father of Morbid Anatomy

**Taceant colloquia. Effugiat risus. Hic locus est
ubi mors gaudet succurrere vitae.
(Let conversation cease. Let laughter flee.
This is the place where death delights to help the living.)**

Latin proverb

Seldom say never – seldom say always!

Forensic proverb

Notes on the cover design

Title of work: Illustrated Hand Scroll of the Poem of the Nine Stages of a Decaying Corpse (Kusoshi emaki)
Date: fourteenth century
Medium: scroll painting
Photographed by Shin'ichi Yamazaki
In the collection owned by: Kyushu National Museum, Dazaifu, Japan

This illustrated handscroll of 'The Poem of the Nine Stages of a Decaying Corpse' – an anatomically precise depiction of a female corpse in the various stages of decomposition – represents one of the earliest examples of this artform executed in Japan over a period of several centuries.

Its origins can be traced back to teachings of old Indian Buddhist sutras from the early fifth century promoting systematic meditation on the impurity of a decaying corpse as a means to conquer carnal desires and achieve enlightenment.

In general context, it can be understood as a symbol of the impermanence of human life, which a forensic pathologist in particular encounters in his daily work.

In scholarly context, it can be associated with other forensic pathological connotations: factual representation of the process of decomposition of the human body (shown in chronological sequence on the back cover) starting from the aspect of recent death, and proceeding through the various stages of putrefaction such as discoloration, bloating, destruction of the soft tissues by maggots, animal predation, skeletalization and complete disintegration of the body.

This page intentionally left blank

Contents

Preface ix
Acknowledgements xi
Abbreviations xiii
Chapter 1 The Forensic Autopsy 1
Chapter 2 The Pathophysiology of Death 55
Chapter 3 The Establishment of Identity of Human Remains 95
Chapter 4 The Pathology of Wounds 133
Chapter 5 Head and Spinal Injuries 167
Chapter 6 Chest and Abdominal Injuries 215
Chapter 7 Self-Inflicted Injury 229
Chapter 8 Gunshot and Explosion Deaths 241
Chapter 9 Transportation Injuries 277
Chapter 10 Abuse of Human Rights: Deaths in Custody 299
Chapter 11 Burns and Scalds 311
Chapter 12 Electrical Fatalities 325
Chapter 13 Complications of Injury 339
Chapter 14 Suffocation and 'Asphyxia' 353
Chapter 15 Fatal Pressure on the Neck 369
Chapter 16 Immersion Deaths 399
Chapter 17 Neglect, Starvation and Hypothermia 415
Chapter 18 Deaths Associated with Sexual Offences 425
Chapter 19 Deaths Associated with Pregnancy 437
Chapter 20 Child Homicide 447
Chapter 21 Sudden Death in Infancy 461
Chapter 22 Fatal Child Abuse 475
Chapter 23 Deaths Associated with Surgical Procedures 497
Chapter 24 Dysbaric Fatalities and Barotrauma 509
Chapter 25 The Pathology of Sudden Death 515
Chapter 26 Forensic Dentistry for the Pathologist 553
Chapter 27 Poisoning and the Pathologist 567
Chapter 28 Forensic Aspects of Alcohol 579
Chapter 29 Carbon Monoxide Poisoning 589
Chapter 30 Organophosphorus Poisoning 595
Chapter 31 Poisoning by Medicines 599

Chapter 32 Death from Narcotic and Hallucinogenic Drugs 613
Chapter 33 Corrosive and Metallic Poisoning 623
Chapter 34 Deaths from Organic solvents 633
Appendix 639
Index 649

Preface

Professor Bernard Knight wrote the first edition of this textbook based on his decades-long experience as a full-time forensic pathologist, consultant pathologist to the Home Office in the United Kingdom, academic teacher and author of several textbooks on forensic pathology and legal medicine. The first edition was published in 1990 followed by the second edition in 1996. The second edition of *Forensic Pathology* consolidated the international reputation of the original book as one of the foremost manuals of forensic pathology in the English language. After the second edition Professor Knight transferred the editorship to Professor Pekka Saukko, and the third edition was the product of collaboration with the original author and was published under the title of *Knight's Forensic Pathology* in 2004. This fourth volume follows the same concept. The text has undergone a complete revision to update where necessary, and 200 new colour illustrations have been added, replacing many of the old monochrome illustrations. This book uses photographs only where a relevant point is displayed, with a full caption that stands alone without having to refer to the text. Many line drawings are used, as the authors feel that they often get the message across better than a photograph, which of necessity contains irrelevant and perhaps distracting features. All the black and white drawings have been redrawn in full colour.

Many textual citations not listed in the previous edition have been added. However, the literature is now so vast (more than 1,000 forensic pathology-related papers, and around 4,000 in its sister discipline forensic science, are published annually in forensic and other specialist journals) that it is futile to try to capture all of even the most seminal papers. To give perspective and to remind us that our present scientific knowledge rests largely on the shoulders of earlier generations, historical references have also been included where appropriate. The interpretation of autopsy findings and many of the principles of morbid anatomy founded in the nineteenth century and earlier are still valid. The value of a publication is in its content, not in its date, as Harvey's *De Motu Cordis* and Morgagni's *De Sedibus* clearly demonstrate! Some of the most valuable papers in forensic pathology were written decades or even a century ago; the critical writings of Moritz, Shapiro, Adelson, Helpern, Gonzales, Polson – right back to Taylor and Tardieu in the nineteenth century – are examples of careful observation and logical thinking, which some modern pathologists, given to over-interpretation, would benefit from studying.

This is a textbook of forensic pathology, not forensic medicine. Though there is a considerable overlap, forensic medicine includes medical jurisprudence, the legal aspects of medical practice and many ethical matters, none of which are found – nor are intended to be found – in these pages. Such topics have marked geographical limitations, as a result of legal, ethnic, cultural and even religious variations from place to place. The subject matter of this volume is solely concerned with the examination of the dead body for medico-legal purposes. Even in this limited sphere, police procedures and the habits of pathologists will vary considerably with country and with resources, but it is hoped that the routines, techniques and philosophy offered in this book will offer a guide to good practice that can then be modified according to local circumstances.

The contents are intended to lead the pathologist – and in some countries, the non-pathologist – through the procedures that are needed in the examination of a body found under obscure, suspicious or frankly criminal circumstances. In developed countries with sophisticated medico-legal systems, such autopsies will be performed only by forensic pathologists or by histopathologists with considerable experience, but in many areas of the world – especially the developing countries – lack of manpower and resources as well as considerations of distance and facilities mean that almost any doctor may be called upon to perform medico-legal examinations. For both of these classes of medical men and women this book aims to act as a guide and a source of reference. Where the pronoun 'he' is used throughout this book, it is intended that the word 'she' is equally applicable, unless obviously inappropriate from the context.

The subject matter follows a fairly conventional pattern, but the treatment of each topic is designed to offer practical advice linked with a philosophical approach that leads the doctor to analyse and question the interpretations drawn from physical findings. All too often, dogmatic opinions are derived from an unsound factual base, learned from lectures or textbooks that repeat previous dogma with little sense of critical evaluation. In some parts of the world forensic pathology is learned by rote from teachers who studied it themselves in the same fashion, and who have little or no practical experience in the hard schools of mortuary or witness-box. We hope that this book will at least stimulate trainee forensic pathologists to think twice, question and disagree.

Pekka Saukko
Bernard Knight

Acknowledgements

It is our pleasure to recollect and acknowledge the help received during the preparation of the 4th edition of *Knight's Forensic Pathology*. We are indebted to colleagues who by encouragement, advice or criticism, or by permission to use material, have contributed to this book. In particular, we would like to thank the following for their advice and criticism: Prof. Claus Henssge (Chapter 2, The Pathophysiology of Death); Prof. Cristina Cattaneo (Chapter 3, The Establishment of Identity of Human Remains; Chapter 18, Deaths Associated with Sexual Offences; and Chapter 26, Forensic Dentistry for the Pathologist); Prof. Hannu Kalimo (Chapter 5, Head and Spinal Injuries); Prof. Stefan Pollak (Chapter 8, Gunshot and Explosion Deaths); and Prof. Antti Saraste (Chapter 25, The Pathology of Sudden Death). We have also had the benefit of advice on post-mortem imaging by Prof. Christian Jackowski and on entomology by Adjunct Prof. Ilari Sääksjärvi.

The following individuals and institutions provided access to specimens and/or contributed to figures, images or case material which was incorporated throughout the text: Prof. Cristina Cattaneo, Laboratory of Forensic Anthropology and Odontology, University of Milan, Italy; Edi.Ermes s.r.l., Milano, Italy; Robert Hale Publishers, UK; Dr. Martin Hall and Dr. Amoret Whitaker, Natural History Museum, London, UK; Prof. Christian Jackowski, Institute of Forensic Medicine, University of Bern, Switzerland; Prof. Hannu Kalimo, Turku, Finland; Dr. Terhi Launiainen, Hjelt Institute, University of Helsinki, Finland; Dr. Stephen Leadbeatter, Forensic Pathology, Cardiff University School of Medicine, Wales; Prof. Eberhard Lignitz, Germany; Prof. Thomas K. Marshall, UK; Prof. Ilkka Ojanperä, Hjelt Institute, University of Helsinki, Finland; The National Bureau of Investigation, Vantaa, Finland; Prof. Juha Peltonen, Department of Anatomy, University of Turku, Finland; Prof. Stefan Pollak and Mr. Thomas Rost, Institute of Forensic Medicine, University of Freiburg, Germany; Prof. Antti Sajantila, Hjelt Institute, University of Helsinki, Finland; Adjunct Prof., Dr. Ilari. E. Sääksjärvi, Department of Biology, University of Turku, Finland; South-western Finland Police Department, Turku, Finland; Dr. Sauli Toivonen, the National Institute of Health and Welfare, Turku, Finland; Prof. Duarte N. Vieira, Institute of Legal Medicine, University of Coimbra, Portugal; Prof. David Whittaker, UK.

Ms Kristiina Nuutila and Dr. Vilma Pääkkö are acknowledged for helping out with the updating of the literature database.

Our thanks go also to CRC Press for the opportunity to publish this book, and in particular to Caroline Makepeace, Stephen Clausard, Rachael Russel, Kay Conerly, and Jennifer Blaise. Finally, Dr. Ruth Maxwell excellently steered the book through the various stages of production with Paul Bennett.

P.S. & B.K.

This page intentionally left blank

Abbreviations

ABFO American Board of Forensic Odontology
ADD accumulated degree day
ADP adenosine diphosphate
AER alcohol elimination rate
AF acid fuchsin
AFE amniotic fluid embolism
AHA American Heart Association
AHT abusive head trauma
AI axonal injury
AIDS acquired immunodeficiency syndrome
AIS Abbreviated Injury Scale
APP amyloid precursor protein
ARVC arrhythmogenic right ventricular cardiomyopathy
ATP adenosine triphosphate
AV atrio-ventricular
AVM arteriovenous malformation
βAPP β-amyloid precursor protein
BAC blood-alcohol content
BBB blood–brain barrier
BMI body mass index
BP before period
BSAC British Sub-Aqua Club
BZP benzylpiperazine
CDC Centers for Disease Control and Prevention
CEMD Confidential Enquiry into Maternal Deaths
CFC chlorofluorocarbon
CHD coronary heart disease
CiRCA cardioinhibitary reflex cardiac arrest
CL chemiluminescence
CLSM confocal laser scanning microscopy
CMACE Centre for Maternal and Child Enquiries
CNS central nervous system
CO carbon monoxide
COM calcium oxalate monohydrate
CPR cardiopulmonary resuscitation
CSF cerebrospinal fluid
CSI crime scene investigator
CT computed tomography
D2PM diphenylprolinol
D&E dilatation and evacuation
DAI diffuse axonal injury
DAN Divers Alert Network
DCM dilated cardiomyopathy
DI dysbaric illness
DIC disseminated intravascular coagulation
DIMS Diving Incidence Monitoring Study
DNA deoxyribonucleic acid
DNOC dinitro-orthocresylphosphate
2-DPMP desoxypipradrol
DPR dermatopathia pigmentosa reticularis
DVT deep vein thrombosis
EA European Co-operation for Accreditation
ECG electrocardiogram
EDH extradural haemorrhage
ECLM European Council of Legal Medicine
EDTA ethylenediamine tetra-acetate
EDX energy dispersive X-ray microanalyser
ELISA enzyme-linked immunosorbent assay
ENFSI European Network of Forensic Science Institutes
FABP fatty acid binding protein
FDA Food and Drug Administration
FDCM familial dilated cardiomyopathy
FISH fluorescent *in situ* hybridization
GBL gamma-butyrolactone
GC-MS gas chromatography-mass spectrometry
GCS Glasgow Coma Scale
GINA Global Initiative for Asthma
GSR gunshot residues
GTN glyceryl trinitrate
H&E haematoxylin and eosin
HbCO carboxyhaemoglobin
HBFP haematoxylin/basic fuchsin/picric acid
HCM hypertrophic cardiomyopathy
HETP hexaethyltetraphosphate
HIV human immunodeficiency virus
H-MRS proton magnetic resonance spectroscopy
ICP intracranial pressure
IDCM idiopathic dilated cardiomyopathy
IEC International Electrotechnical Commission
IIH idiopathic intracranial hypertension
ILAC International Laboratory Accreditation Cooperation
INVM isolated non-compaction of the ventricular myocardium
ISO International Organization for Standardization

IVCT *in vitro* muscle contracture test
IVH intraventricular haemorrhage
IVRA intravenous regional anaesthesia
LAD left anterior descending
LFB luxol fast blue
LOC loss of consciousness
LOQ limit of quantification
LSCB Local Safeguarding Children Board
LSD lysergic acid diethylamide
LSS live skeletal survey
LUCAS Lund University Cardiac Arrest System
MDA methyl 3,4-methylenedioxyamphetamine
MDMA 3,4-methylenedioxymethamphetamine
MH malignant hyperthermia
MI myocardial infarction
miRNA micro ribonucleic acid
MMR maternal mortality ratio
MRI magnetic resonance imaging
MRSI magnetic resonance spectroscopic imaging
MSB Martius scarlet blue
MSCT multislice computed tomography
msw metres of sea water
mTBI mild traumatic brain injury
mtDNA mitochondrial deoxyribonucleic acid
NAA N-acetylaspartate
NAHI non-accidental head injury
NAI non-accidental injury
NFJS Naegeli–Franceschetti–Jadassohn syndrome
NICHD National Institute of Child Health and Human Development
NMR nuclear magnetic resonance
NSCLC non-small cell lung carcinoma
NSPCC National Society for the Prevention of Cruelty to Children
OC oleoresin capsicum
OFSTED Office for Standards in Education, Children's Services and Skills
OI osteogenesis imperfecta
OMPA octamethylpyrophosphamide
OP organophosphorus
PBT pulmonary barotrauma
PCP piperidine hydrochloride
PCR polymerase chain reaction
PCS post-concussive symptoms
PD Parkinson's disease
PDS Pokkuri death syndrome
PG prostaglandin
PICA posterior inferior cerebellar artery
PMCTA post-mortem computed tomography angiography
PMI post-mortem interval
PMN polymorphonuclear neutrophil
PMSS post-mortem skeletal survey
PSA prostate-specific antigen
PTAH phosphotungstic acid-haematoxylin
PVC polyvinylchloride
RCA right coronary artery
RIA radioimmunoassay
SA sino-atrial
SAH subarachnoid haemorrhage
SAP standardized autopsy protocol
SCLC small cell lung carcinoma
SCR Serious Case Review
SDH subdural haemorrhage
SEM scanning electron microscopy
SG semenogelin
SIADH syndrome of inappropriate antidiuretic hormone hypersecretion
SIB sacroiliac joint bridging
SIDS sudden infant death syndrome
SOCO scene of crime officer
SOP standard operating procedure
SS skeletal survey
STD sexually transmitted disease
STR short tandem repeat
SUDI sudden unexpected death in infancy
TAI traumatic axonal injury
TBSA total body surface area
TEPP tetraethylpyrophosphate
THC tetrahydrocannabinol (cannabis)
TSS toxic shock syndrome
UAC urine alcohol content
UV ultraviolet
VR volume rendering
WHO World Health Organization

CHAPTER 1

The Forensic Autopsy

- Types of autopsy
- Autopsy legislation, guidelines, standards
- The procedure for a forensic autopsy
- Examination of the scene of death
- Property, clothing and identification
- The use of the history of the case
- Precautions regarding potential infective conditions and other risks and hazards in autopsy room
- The autopsy: external examination
- The autopsy: internal examination
- Examination of organs
- Examination of the brain
- Ancillary investigations
- Autopsy radiology and post-mortem imaging
- Forensic photography
- The autopsy report
- Post-mortem artefacts
- Exhumation
- The autopsy on the putrefied corpse
- Resuscitation artefacts at autopsy
- Mass disasters – the role of the pathologist
- The obscure autopsy
- References

Though 'necropsy' is semantically the most accurate description of the investigative dissection of a dead body, the word 'autopsy' is used so extensively that there is now no ambiguity about its meaning.

The term 'post-mortem examination' is a common alternative, especially in Britain, where its meaning is never in doubt. Unfortunately, it suffers from a lack of precision about the extent of the examination, for in some countries many bodies are disposed of after external examination without dissection.

It is obvious that even in a primitive tribal society there must have been an interest in discovering the causes of death of its members. In particular, a sudden, unexepected or unwitnessed death must have signalled a potential danger, either from within the society by its own members or by an enemy from the outside.[1] Therefore, it is logical that, when societies started to develop and get more organized, the forensic investigation of deaths was introduced relatively early due to the requirements of the judicial system. The oldest known official instructions about the external investigation of corpses have been dated to the Ching-dynasty (~2000 BC) in ancient China. A decree enacted during the Song-dynasty (960–1279 AD), in 995 AD, provided that a government official had to investigate a violent or suspicious death within 4 hours and failure to do so was punishable.[2,3] The earliest known forensic dissections took place in Italy, probably in the middle of the thirteenth century, at the University of Bologna. One was recorded by Guglielmo de Placentinus Saliceto, or William of Saliceto (1210–1277), a surgeon and a teacher in the medical faculty there. In his book *Surgery* he mentioned a case examined in about 1275.[4] It is, however, uncertain whether this was an autopsy or just an external examination of the body. Possibly the first reliable record of a medico-legal autopsy in those days has been attributed to Bartolomeo da Varignana, a professor of medicine, who served the municipality of Bologna in a medico-legal capacity. The public prosecutor had ordered an autopsy in the suspected poisoning of a nobleman, Azzolino, in February 1302. The autopsy was performed by two physicians and three surgeons under the leadership of da Varignana.[2,5,6]

The principles of the modern medico-legal investigation were developed based on the codes of the sixteenth century Europe: the Bamberg Code in 1507, the Caroline Code in 1532 and later the Theresian Code in 1769. Further development of the medico-legal autopsy has been greatly influenced by the judicial system adopted, the main emphasis in most countries being in the detection and investigation of criminal and other unnatural or unexpected deaths.

In the course of the following centuries autopsies were increasingly performed and recorded, contributing to the advancement of pathology. The hospital or clinical autopsy became meaningful after the introduction of improved autopsy methods by Carl von Rokitansky (1804–1878) and Rudolf Virchow (1821–1902) and by modern concepts of the pathogenesis of disease, in particular, cellular pathology introduced by Virchow.[7]

Types of autopsy

Though medical conventions and legal systems vary considerably from country to country, there are generally two main types of autopsy:

- The *clinical* or *academic autopsy* is one in which the medical attendants, with the consent of relatives, seek to learn the extent of the disease for which they were treating the deceased patient. In most jurisdictions this type of autopsy should not be held to determine the nature of the fatal disease because, if this was unknown to the physicians, the death should have been reported for medico-legal investigation.
- The *medico-legal* or *forensic autopsy*, which is performed on the instructions of the legal authority responsible for the investigation of sudden, suspicious, obscure, unnatural, litigious or criminal deaths. This legal authority may be a coroner, a medical examiner, a procurator fiscal, a magistrate, a judge, or the police, the systems varying considerably from country to country.

  In most systems the permission of the relatives is not required, as the object of the legal investigation would be frustrated if the objections of possibly guilty persons could prevent the autopsy.

  In many jurisdictions the medico-legal autopsy is often further subdivided into:
- those held on apparently non-criminal deaths, such as accidents, suicides, deaths from sudden natural causes, or associated with medical and surgical treatment, industrial deaths, and so on
- the truly forensic autopsy held on suspicious or frankly criminal deaths, usually at the instigation of the police. These deaths comprise murder, manslaughter, infanticide and other categories that vary in different jurisdictions.

Autopsy legislation, guidelines, standards

Discussions about the correct performance and quality of the autopsy started at the beginning of the nineteenth century. When Virchow started in 1844 as assistant to the Prosector at the Charité in Berlin, he found a rather disorganized autopsy facility where most of the autopsies were performed by the youngest, not yet fully qualified, physicians without any basic training in autopsy technique. This was the starting point for the publication of his book on autopsy technique.[8]

Probably the best-known regulations from that era concerning medico-legal autopsy are the Austrian decree of 1855 and the Prussian edict of 1875. The former included, in its 134 paragraphs, very detailed instructions as to the performance of medico-legal autopsies. It is noteworthy that it is still valid legislation in Austria.[1,9,10] It took about another 100 years until various national organizations in the industrialized world, mainly professional bodies, began to take an interest in autopsy guidelines.[11–14]

In addition to the national measures to create guidelines and to harmonize the medico-legal autopsy, there has been international interest in achieving harmonized and internationally recognized rules on the way autopsies should be carried out. In 1991, the General Assembly of the United Nations endorsed the Model Autopsy Protocol of the United Nations. The European Council of Legal Medicine (ECLM) document *Harmonisation of the Performance of the Medico-Legal Autopsy* was adopted by the General Assembly in London 1995. The latter document served largely as basis for the pan-European Council of Europe – *Recommendation No. R (99) 3 On the Harmonisation of Medico-Legal Autopsy Rules and Its Explanatory Memorandum* – which was adopted by the Committee of Ministers in February 1999 (see Appendix 1).[15] Although the document is a 'recommendation' by nature, it has legal implications, because Council of Europe member countries have to implement these principles into their national legislation.

The idea of quality control and quality assurance, first introduced into industrial production of goods in the twentieth century, found its way into medicine later via laboratory medicine. Although regional and national differences in this respect are huge and the pace of progress has generally been very slow, the need for standards in specialist education, continuing professional development, harmonization of investigative procedures and necessity of quality systems is now better understood. As guidelines usually

Box 1.1 Accreditation

Accreditation is a procedure by which an authoritative body gives formal recognition that a body or person is competent to carry out specific tasks. This aims to increase the credibility and acceptability of the reports and certificates issued by them. It is achieved by ensuring that the infrastructure, personnel and the methods comply with pre-established criteria. The structure, processes, policies and goals of the body to be accredited are described in a quality manual. Standard operating procedures (SOPs) have to be defined to describe the specific tasks that will be carried out at the entity.

International Organization for Standardization (ISO) and ISO's sister organization, the International Electrotechnical Commission (IEC), are the world's largest developers and publishers of International Standards and a network of the national standards institutes of 163 (10.1.2011) countries, one member per country, with a Central Secretariat in Geneva, Switzerland, that co-ordinates the system.

The International Laboratory Accreditation Cooperation (ILAC), is an international co-operation of laboratory and inspection accreditation bodies. European co-operation for Accreditation (EA), is the European network of nationally recognized accreditation bodies located in the European geographical area. According to the Regulation (EC) No765/2008 of the European Parliament and of the Council of 9 July 2008, the main mission of the EA is to promote a transparent and quality-led system for the evaluation of the competence of conformity assessment bodies throughout Europe and to manage a peer evaluation system among national accreditation bodies from the European Union member states and other European countries.

Accreditation procedures have usually been applied to calibration and testing laboratories but the European Network of Forensic Science Institutes (ENFSI) and EA are currently working in a joint project aiming to define which standard, ISO/IEC 17020 or ISO/IEC 17025, is to be used for the different forensic fields. Several German and Swiss institutes of legal medicine have recently been accredited by their respective national accrediting bodies regarding medico-legal activities including autopsies.

represent recommendations allowing some variation in practice, the most recent trend, particularly in medico-legal field, seems to be moving towards accreditation that necessitates standardized operational procedures.

The type of pathologist that deals with these categories also varies from place to place but, as the systems are so diverse, there is little point in discussing the details. What is much more important is that whichever pathologist tackles each type of case, he or she should be trained and experienced in that particular field. Unfortunately, either from lack of staff and resources or because the system is deficient, medico-legal autopsies – especially of major criminal cases – are frequently performed by pathologists inexperienced in forensic procedures. According to Spitz most medico-legal autopsies in the USA in the 1980s were performed by hospital pathologists with little or no medico-legal training or experience.[16] Even today more than half of the USA states still have county coroners, an office for which no medical training is necessary, and there were in 2009 only about 500 trained forensic pathologists in the nation's more than 3000 counties.[17]

Another serious defect in many countries is the separation of those who practise forensic pathology from those who profess to teach it in universities. It is impossible to be a credible and convincing teacher unless one has continuing practical experience of the subject.

When quality assurance measures do not exist or fail, systemic errors may remain undetected for longer periods of time. When eventually detected the repercussions can be serious; they can be costly to society, not only in terms of money but also in loss of confidence as to the rule of law, and involve personal tragedies for those affected.

A good example of the repercussions of such practices was revealed in the recent Inquiry into Pediatric Forensic Pathology in Ontario. It was established by the Government of Ontario under the Public Inquiries Act on April 25, 2007 to address serious concerns over the way criminally suspicious deaths involving children were handled by the Province of Ontario in Canada from 1981 to 2001. The Inquiry's mandate was to conduct a systemic review and an assessment of the policies, procedures, practices, accountability and oversight mechanisms, quality control measures and institutional arrangements of paediatric forensic pathology in Ontario.[18]

Even more unfortunate is the performance of medico-legal autopsies by doctors who have no training in pathology at all. Though lack of resources makes this a widespread and inevitable practice in many developing countries, the same regrettable practice is seen in some parts of Europe, the Americas and elsewhere. This is to the detriment of the high standard of expertise that is vital for the support of law enforcement and the administration of justice. A poor opinion is often worse than no opinion at all, as in the latter case, the legal authorities will at least be aware of the deficiency in their evidence, rather than be misled by the often dogmatic inaccuracies of an inexperienced doctor.

The procedure for a forensic autopsy

Though the actual performance of an autopsy is fairly uniform whatever the nature of the death, there are a number of associated matters that vary according to the circumstances. For example, the procedural precautions required in a murder are not necessary in a sudden natural death, and the dissection in a criminal abortion or fatal rape is different from that upon a drowned body.

There are, however, many facets of the autopsy that are common to every death. These will be discussed in turn here, though the full significance of each item is discussed in detail in other chapters.

Box 1.2 The objectives of an autopsy

- To make a positive identification of the body and to assess the size, physique and nourishment.
- To determine the cause of death or, in the newborn, whether live birth occurred.
- To determine the mode of dying and time of death, where necessary and possible.
- To demonstrate all external and internal abnormalities, malformations and diseases.
- To detect, describe and measure any external and internal injuries.
- To obtain samples for chemical, toxicological or genetical analysis, microbiological and histological examination, and any other necessary investigations.
- To retain relevant organs and tissues as evidence.
- To obtain photographs and video for evidential and teaching use.
- To provide a full written report of the autopsy findings.
- To offer an expert interpretation of those findings.
- To restore the body to the best possible cosmetic condition before release to the relatives.

Preliminaries to an autopsy

Before the body is even approached, a number of preliminaries are necessary.

Authorization and consent

A medico-legal autopsy is carried out at the behest of the appropriate authority. The pathologist must not begin his examination until he is satisfied that such authority has been issued in respect of that particular death. The means of delivering such authority will vary from place to place: it may be a written document, a verbal or telephoned message, or a tacit standing arrangement.

Where two official organizations are involved, it must be clear who has the premier right to order an autopsy. For example, in England and Wales, the police may request a pathologist to examine a body externally at the scene of death, but the right to order an autopsy is the sole prerogative of the coroner. Though in serious incidents he or she should take the advice of the Chief of Police regarding the choice of a pathologist, the final decision remains that of the coroner.

As stated earlier, in a medico-legal autopsy the relatives are not consulted for their consent to autopsy, as such permission cannot be withheld. As a matter of courtesy it is usual to inform them before the autopsy is carried out unless the circumstances are too urgent. In most cases, however, a relative will have attended to identify the body before the examination begins. Pathologists should be cautious about performing autopsies where the authorization or consent aspects are not clear. It sometimes happens that a 'consent document' for a hospital death has been obtained but the case has later been reported for medico-legal investigation. The pathologist should not then proceed under the 'consent' authority until the coroner or other official has decided whether to order his own autopsy (perhaps using another pathologist). If that official decides not to proceed, then usually the consent document becomes valid once more.

Permission for the retention of material from an autopsy (ranging from small fluid samples to the entire body, if necessary) is usually covered in a medico-legal case by the original authority issued for the examination. There is, however, considerable variation in the legal aspects of tissue and organ retention in different countries, and each pathologist must become fully conversant with local regulations.

In the legislation controlling the English coroner, it is not only permissible, but also obligatory, for the pathologist to retain any tissue that may assist in the further investigation of the death.

However, the coroner (or procurator fiscal in Scotland) has only a negative power to forbid the use of tissues or organs for purposes other than the investigation of the death, and so cannot give positive consent for the use of these for transplantation, teaching or research; such permission must be obtained from the relatives, if the coroner does not object, under the Human Tissue Act 2004.[19–21]

Who may be present at an autopsy

Once again, each nation or state has different legislation and regulations on the conduct of medico-legal examinations. Though it is pointless to try to survey these, it must be emphasized that every pathologist must learn and abide by the laws applicable to his or her position.

Often the relatives of the deceased person, or an accused person, must be informed of the place and time of the autopsy so that they may be represented by a lawyer or doctor acting on their behalf. In some jurisdictions, including Britain, there is nothing that specifically forbids the relatives attending in person and the authors have had several experiences of this nature. It is open to the pathologist to refuse to conduct the autopsy if he objects to their presence.

In many homicides, a second autopsy is performed by another pathologist acting on behalf of the defence lawyers representing the accused person. This usually takes place at a later date, after the accused has been charged and granted legal representation, but sometimes the second pathologist will attend the original autopsy. This is quite in order and is more valuable than a later exploration of extensively dissected and autolysed tissues.

The permission for such attendance is granted by the coroner, medical examiner or equivalent legal authority. The first pathologist should grant his colleague every courtesy and facility in the expectation of similar behaviour when the roles are reversed.

Others entitled to be present naturally include the officials or deputies of the department ordering the autopsy – for example, a coroner, magistrate or judge. The police, including their technical teams, are also present if the death is criminal or suspicious. Whether other doctors and medical students are allowed depends upon the wishes of the official commissioning the examination. When the deceased has been under medical care before death, it is almost invariable practice to allow – and indeed encourage – the physician to be present, as he has the best knowledge of the medical history.

In a criminal or suspicious case, the pathologist should try to limit the number of those present to a minimum. Not only is there a greater risk of loss of confidentiality, but sheer physical numbers, can make the mortuary overcrowded. This hampers movement, causes distraction, and adds to the risk of infection and contamination, especially with the present concern about the various forms of hepatitis (B, C, D, E), tuberculosis and human immunodeficiency virus (HIV) infectivity. No one should be present merely as a casual observer, not even senior police officers not directly involved in the investigation. With the increased sophistication and complexity of forensic and police procedures, more and more people cram into the mortuary, cluttered with cameras, videos, recorders, scene-of-crime kits and so on, until there is hardly room for the pathologist to move.

Whoever is present at an autopsy on a criminal or suspicious death should be listed and named by the pathologist on the autopsy report.

Examination of the scene of death

In homicide, suspected homicide and other suspicious or obscure cases, the pathologist should visit the scene of the death before the body is removed (Figs 1.1–1.3).

Once again, local practice varies but any doctor claiming to be a forensic pathologist should always make himself available to accompany the police to the locus of the death. This duty is often formalized and made part of a contract of service for those pathologists who are either full-time or substantially involved in assisting the police. In England and Wales, the ‘Home Office Pathologists’ are permanently on call for such visits and in many other jurisdictions, such as the medical examiner systems in the USA and the European State and University Institutes of Forensic Medicine, there is usually a pre-arranged duty roster for attendance at scenes of death. The function of an experienced forensic pathologist at the scene of death is generally to assess the environment, the local circumstances, and the position and the condition of the body. In a large proportion of instances crime can rapidly be excluded in favour of accident, suicide or even natural causes. This is a most useful and cost-effective function, as a spurious murder investigation involving perhaps scores of police, many vehicles and other expensive public facilities, may be disbanded promptly when the pathologist recognizes innocent circumstances.

The pathologist should always have appropriate equipment ready to take to a scene investigation at a moment's notice. Further equipment may be carried if autopsies have to be carried out in places where good mortuary facilities are not available. Most forensic pathologists carry a 'murder bag' in their car and though every expert has his own choice of equipment, the following is a reasonable inventory:

Box 1.3 Equipment for scene of crime investigation

- Waterproof apron, rubber gloves and disposable overalls and mask.
- Thermometer, syringes and needles, sterile swabs.
- Autopsy dissection set, including handsaw.
- Cutting needles and twine for body closure.
- Swabs and containers for blood and body fluids.
- Formalin jars for histological samples.
- Plastic bags, envelopes, paper, spare pen and pencil.
- Printed body charts for recording external injuries.
- Hand lens, electric torch, digital dictaphone or mini-tape recorder.
- Digital or 35 mm single-lens reflex camera with electronic flash or digital video camera.

The thermometer can be either a long chemical mercury type, reading from 0 to 50°C, or the more modern electronic digital variety with a probe carrying a thermocouple. The amount of equipment varies with the facilities likely to be available. In developed countries there are likely to be good mortuary facilities available in a hospital or municipal mortuary and the police forces will have extensive scenes-of-crime expertise with photography, specimen containers and so on. In developing countries and the more remote areas of other states, the pathologist may have to be virtually self-sufficient in respect of both crime investigation and the subsequent autopsy.

In addition to medical kit, the experienced forensic pathologist will always have appropriate clothing such as rubber boots and rain- or snow-wear ready to hand for any call.

When at the scene of death, the pathologist's actions are dictated by the particular circumstances. Much will depend upon the availability or otherwise of police and forensic science assistance. In Britain, for example, several teams converge on a scene of crime, including photographers and video-operators, and scenes of crime officers (SOCOs), formerly known as crime scene investigators (CSIs), whose function is to preserve and protect the crime scene so that evidence is not spoilt or destroyed, collect trace evidence such as fibres, blood, hair, paint or glass, search and collect fingerprints, footprints and toolmarks. Scientists from the nearest forensic laboratory often attend with their police liaison officers, as well as fingerprint officers and, of course, the investigating officers from the Criminal Investigation Department.

Where no such backup is available, the pathologist must try to collect trace evidence himself, but he should remain within the limits of his own expertise.

The pathologist should accept the instructions of police officers in relation to the approach to the body so as to preserve the immediate environment as much as possible. Out-of-doors access is often limited to a single pathway marked by tapes, and in a building, a track to the corpse is usually pointed out by the detective in charge.

The doctor should not touch anything unnecessarily and certainly not smoke or leave any object or debris of his or her own. Increasingly, those visiting the scene of a crime are given disposable overalls and overshoes to wear, so that fibres, hairs and so on from the visitor are not spuriously transferred to the scene.

If a forensic doctor has to act both as pathologist and clinical medico-legist or 'police surgeon' (that is, examining live victims or suspects), he or she must change clothing or wear a new set of protective garments to avoid transferring trace evidence, such as fibres or hairs, from victim to suspect.

The pathologist should observe a great deal, but do very little. He or she should note the position of the body in relation to nearby objects and establish the plan of the premises if indoors. A sketch or his own photograph is sometimes useful, and it is advisable to use a digital or video camera for instant recording of the death scene.

Any obvious cause of death should be observed, and any blood pools or splashes noted in relation to the position of the corpse. The shape of such splashes should be observed, as blood striking perpendicularly to a surface leaves a circular mark, whilst that landing obliquely is pear-shaped, with the sharper end towards the direction of flight (Fig. 1.4).



Figure 1.1 The scene of a rape-homicide. The attending pathologist must record the posture, state of clothing and general relationship of the victim to the surroundings, but limit the examination at the scene to avoid any interference with the vital process of obtaining trace evidence. Rectal temperatures should not be taken until all swabs are completed, usually in the mortuary. Temperatures can be taken in the ear or deep nostrils, though with severe head injuries (as here) even this must be done with care.



Figure 1.2 Scene of a homicide-suicide where the locus of bodies should be widely marked off by tape to restrict access, and the actual body protected by a shelter from the weather and unauthorised onlookers.



Figure 1.3 Scene from inside of the cordoned area of Figure 1.2 with scene of crime officers and one of the victims.



Figure 1.4 At a scene of crime, the position of the body at the time of an assault can sometimes be clarified by observing the direction of blood splashing that may have been thrown off a weapon or blood-stained hands. Blood striking vertically causes round or crenellated circles, while blood hitting at an angle is lance-shaped, with the narrow end facing the direction of travel. There is often a preceding drop of blood in advance of the major splash, forming an 'exclamation mark' stain.

When photographs have been taken of the body in its original position, the pathologist then approaches it, after checking with the investigating officers that it is appropriate for him to do so. Close examination can be made and the skin felt to assess temperature. The eyes, neck and hands can be examined and where necessary, clothing gently moved aside to look at the throat or upper chest. Any relevant findings should be photographed by the police before further disturbance.

If forensic scientists or SOCOs require any samples at this stage, their wishes must be respected. They may want to 'tape' the body, that is, press adhesive tape across the skin and clothing to capture any loose hairs and fibres. The body can then be moved to look at the sides and undersurface, again with caution so that no weapon, other object or trace evidence is disturbed. No set routine can be advised, as each case has its own individual aspects. The prime object is to assess the whole scene while causing the least disturbance to the body and clothing before the scientific teams have finished their tasks (Fig. 1.12).

Estimating the post-mortem interval at the scene

The last sentence above raises the matter of estimating the time since death. The problem is fully discussed in Chapter 2, but has relevance here in relation to the pathologist's actions at the scene of death.

The general warmth or coolness of the hands and face can be assessed by touch, and the degree of rigor mortis felt by gently testing the limbs. The ambient (environmental) temperature must be taken as soon as possible after the discovery of the body, preferably by police SOCOs who usually arrive at the locus before the pathologist. The ambient temperature should be taken as near to the body as possible, as microenvironments can exist, even inside buildings or rooms. Information should be sought as to how much disturbance of the ambient temperature might have occurred, such as opening doors and windows, or turning fires or central heating on or off, so that some idea of post-discovery distortions of temperature can be estimated later. The insertion of a thermometer into the rectum at this stage in the investigation, as advocated by some textbooks, is controversial.

At a scene of death, this usually means either pulling down trousers or pants, and otherwise disturbing clothing, often in cramped and ill-lit places, frequently out in the open. It also risks contaminating the rectum and perineum, by introducing seminal fluid from the anal margin into the rectum, making subsequent examination of that area (and taking swabs for semen) of reduced value. As so many violent crimes now have sexual or homosexual overtones, the practice of taking rectal temperatures at the scene should be performed only if the forensic scientists or police SOCOs are satisfied that trace evidence from the clothing, swabs from the vulva, vagina and anus, etc., can be obtained satisfactorily before rectal thermometry is performed.

In other words, a cost–benefit analysis must be made at the scene, to decide if the difficulties of taking a rectal temperature are worth the small potential advantage of an earlier measurement. In many cases, where the body has obviously been there long enough for the core temperature to have reached ambient – or where other circumstantial evidence has indicated that the time of death is known to a greater degree of accuracy that can be hoped for by thermometry – then nothing is lost by postponing the procedure until the body arrives at the mortuary for autopsy, which, in British practice, is usually directly after the body is moved from the scene.

If the autopsy is to be delayed for many hours owing to difficulties with transport or lack of facilities, then much more must be done at the scene and temperature measurements are justified.

An alternative is to use a place other than the rectum. The axilla and mouth give low readings, which cannot reliably be correlated with the deep temperature because of variable exposure to the air temperature. More useful is the auditory meatus or nostril, the thermometer or thermo-couple probe being inserted as deeply as possible. Reliable, reproducible readings can be obtained from these sites, which have the great advantage of being easily accessible without moving clothing, as well as not being required for swabbing to investigate possible sexual assaults. The use of temperatures to attempt to calculate the post-mortem interval is discussed fully in Chapter 2.

When the pathologist has made the best examination possible in the circumstances, his next function is to ensure that the corpse is removed to the mortuary for autopsy with the least disturbance and loss of evidence. He should supervise the removal himself or at least delegate the duty to another person whom he knows is careful and competent. Each hand should be enclosed in a bag, secured at the wrist by adhesive tape or string. A similar bag should be placed over the head. The packaging medium may vary, but generally paper bags are recommended.

The body should be placed gently in a 'body-bag', which has a zip closure, or moved on to a large, new plastic sheet, at least 2 metres square. If a sheet is used, the edges should be wrapped over the body and secured with adhesive tape. The object of the exercise is to retain any loose objects, hairs and fibres that may be adhering to the body or the clothing. The sheet or bag is taken by the forensic laboratory after the body is removed in the mortuary so that they may screen it for trace evidence. The transport of the body is the responsibility of the police or other agency such as the coroner or his officer. The body in its plastic wrapping should be placed in a rigid fibreglass 'shell' or ordinary coffin, and taken by hearse, van or police transport to the chosen mortuary.

Physical damage during the removal should be avoided as much as possible, though in difficult or inaccessible sites this is easier said than done. In fires, the body may be seriously damaged before or during recovery, sometimes because its presence is not suspected in the smoke-filled, often waterlogged, debris of a conflagration. The author (BK) has experience of such a scene where firemen walked over two bodies for several hours before it was realized that they were buried under burnt furniture and other debris. Handling brittle, charred, bodies can easily cause the splits at joints that may mimic ante-mortem injuries (see Chapter 12).

In summary, the function of a pathologist at any scene of suspicious death is to observe the situation, to conserve any fragile evidence, to supervise the removal of the body and offer an opinion, based on experience, about the nature of death where this can reasonably be done. He is not there to act as a latter-day Sherlock Holmes, voicing unsubstantiated theories on non-medical matters, nor attempting to overinterpret the situation from the flimsiest of facts. The pathologist is part of a team of specialists, all experts in their own field, and it is as a member of such a co-operative, co-ordinated group that his best contributions can be made.

Property, clothing and identification

Whether or not the pathologist has been to the scene of a death, he should take notice of the clothing and other property of the body upon which he is to carry out an autopsy. This applies not only to every criminal or suspicious death, but also to many traffic and industrial accidents, as well as to the victims of falls from a height, drowning and so on.

In many instances, there will be no opportunity to examine the clothed body in the mortuary: if death has occurred in hospital or in an accident department, the clothing may have been removed before transfer to the mortuary. The pathologist should make a permanent request that a body from any traffic accident, or other case where trauma was the provisional cause of death, should be brought to the mortuary without having the clothing removed by police or nursing staff – unless of course the victim was still alive on arrival at hospital, and undressing was performed before attempted resuscitation or treatment. As a second best, the removed clothing should accompany the body to the mortuary so that it can be examined, if necessary, for damage, stains and other evidence. Unfortunately, such clothing is frequently destroyed before it can be seen.

The mortuary staff should be trained to regard clothing and property as important items of evidence, and a system should be established to retain, identify and store these, both from the evidential aspects and for the safety of valuables. The contents of the pockets, documents, keys and other items all assist in identification. Though primarily the task of the police, the pathologist will sometimes have an interest in this aspect. The clothes themselves, the style, fabric, colour and labels all assist in identity.

In trauma deaths, the injuries on the body should be matched up with damage on the clothing. Tears, slashes, stab wounds and especially firearm wounds in the clothes must be compared with the position of external lesions on the body, making allowance for movement and displacement during life. Some self-inflicted wounds may be confirmed by the non-alignment of the clothing damage with the injuries (see Chapter 8).

Blood, seminal, vaginal and other body secretions may be found on the clothing, and though this is primarily the responsibility of the forensic science laboratory, the pathologist may be the first or only person to detect their presence. In firearm deaths, gunshot residues on the clothing may be vital evidence about the range of the discharge and the identity of the ammunition.

In traffic fatalities, tearing of the clothes, grease marks, road dirt, broken lamp or windscreen glass, and even metallic or paint fragments from the vehicle may all assist in reconstructing the event and in identifying the unknown vehicle in a 'hit-and-run' tragedy.

Other objects associated with the body that may be helpful include medicines, which may assist in determining the nature of the disease from which the deceased had suffered, for example, glyceryl trinitrate (GTN) or insulin. In some suicides, empty drug or poison containers may be with the body. Other helpful artefacts include such items as hearing aids, syringes, external pacemakers and inhalers. The clothing must be removed carefully and, especially in criminal or suspicious cases, the pathologist should supervise and assist the mortuary technician, especially as some technicians are not always aware of the importance of clothing in the reconstruction of events.

If the body is not bleeding or otherwise fouled, it is best to remove clothing in the usual way by pulling over the head and limbs, unless this might interfere with any injuries or soiling. If rigor is intense or if there is blood on the face or hands, it may be advisable to cut off some or all of the clothing. This should be done after consultation with the forensic scientists, if they are present, so that the cuts will be made where they will least interfere with later laboratory examination. In any event, cuts should avoid passing through pre-existing damage or staining of the garments. Each item of the clothing should be placed separately into a paper bag to allow them to 'breathe'.

Identification of the body

The identification of an unknown body is a major forensic exercise, and is fully discussed in Chapter 3. Here, however, we are concerned with the formal recognition of the subject of an imminent autopsy. Before a pathologist makes any examination (and certainly before he begins any mutilating dissection), it is essential that he ensures that the corpse before him is indeed the correct person.

In every medico-legal case, some responsible person must have identified the body. This is usually a relative or close friend of the deceased person, who looks at the face of the body and verbally certifies to a police officer, mortuary attendant or doctor that it is indeed 'John Smith'. Where the body is burned beyond recognition, mutilated or putrefied, attempts at identification must be made by showing the relative documents, or items such as clothing or jewellery.

In non-criminal cases, such as sudden deaths and most accidents and suicides, the continuity of identity is carried on by a label or tag attached to the body by the police officer, nursing staff or mortuary attendant, which carries the name, address, serial number and other relevant details. This label may be tied firmly to a toe, or a durable wrist or ankle bracelet may be used. Some mortuaries write the name on the leg with an indelible marker, but this can be smudged or obscured during autopsy.

The pathologist should always satisfy himself of the identity by comparing the documents authorizing the autopsy with the toe label or bracelet. The details should agree and, if they do not, he should not proceed with the autopsy until the discrepancy is cleared up, if necessary by calling back the police officer or even the relative to make absolutely sure of the identity.

Many mistakes have been made in the past, with adverse publicity, embarrassing enquiries and even legal consequences. Autopsies on the wrong person, incorrect causes of death, relatives attending the wrong funeral and even cremation of the wrong body are regularly reported as a result of laxity in identification. To avoid confusion, the body should always be labelled as soon as it arrives in the mortuary. Labels on shrouds become detached and those on refrigerator doors are unreliable, as other parties (such as night porters) may shift occupants around without the knowledge of the pathologist or regular mortuary staff.

Some large mortuaries use special means of identity. One known to the authors has an automatic camera fitted in the ceiling of the mortuary entrance. Every new body wheeled in is photographed on its trolley with a serial number prominently displayed on a board placed across the upper chest, so that the face appears with the record number to resolve any later discrepancy.

In serious cases such as homicide, the pathologist must not rely on second-hand evidence of identity such as a toe label. Before the autopsy, someone must verbally confirm to him that the body they are both then viewing is 'John Smith'. This person must be either a relative or the police officer to whom a relative has already formally identified the corpse.

The pathologist must record in his autopsy report the date, time and particulars of the person identifying the body to him, so that 'continuity of evidence' is ensured for legal purposes, which cannot successfully be challenged by the defence at a subsequent trial.

The use of the history of the case

As in clinical medicine, the history of the deceased 'patient' or victim is a vital and indispensable part of the investigation. The extent to which it should influence the pathologist in coming to a decision as to the cause of death, however, is more controversial, as is discussed below.

In medico-legal autopsies – compared with hospital 'clinical' cases – the history is often scanty, absent or misleading. If a person has been found dead, having had no previous medical attendant, there may be virtually no information at all. In criminal deaths, the person who knows most about the death may well be the perpetrator, who naturally may remain silent or give a distorted, misleading or totally false account of the circumstances. The forensic pathologist then often has to contend with a scanty or incorrect history.

Even when a story is given in good faith by relatives, the medical facts are often distorted because of incomplete knowledge and understanding. It may be further warped by transmission by a police officer or other non-medical person, so that only a garbled history reaches the pathologist. The latter should attempt to supplement deficiencies in information by further requests to the commissioning authority, such as the coroner or the police. Wherever possible, the pathologist should try to contact the doctor who may have treated the deceased in the recent past. In the urgency of forensic work, however, frequently at night or weekends, the autopsy may have to proceed without any additional history.

Though more detail may be obtained afterwards, the course of the autopsy might well have been different if such knowledge was available beforehand. For example, the author (BK) once performed an autopsy on a coal miner with no history other than a knowledge of his occupation and chronic chest disease. Autopsy revealed sufficient cardiopulmonary disease to account for death and the body was released for burial. It was not until the following day that the police in the rural area where the male had died, tardily produced the information that both an empty bottle of sleeping tablets and a suicide note had been found with the body. Paradoxically, the history is often less important in violent deaths where the wounds are self-evident, though a good description of the circumstances may assist in interpreting the direction of injuries, the nature of the weapon and other aspects.

In most autopsies the history directs the pathologist to the appropriate ancillary investigations, as should have happened in the case described above. Some pathologists have in the past advocated that the autopsy should be performed 'blind', so that the history does not prejudice the opinion of the pathologist. This is patently impracticable, for every autopsy would then have to be totally comprehensive, including such techniques as the removal of the spinal cord in every case, and all possible ancillary investigations, such as toxicology, microbiology, virology, radiology, diatoms, histology and so on, as there would be no means of knowing what was necessary and what was irrelevant. Apart from the intolerable burden of work, the expense of such an approach would be prohibitive, if applied to all autopsies.

A particular difficulty often arises in relation to bodies returned to a home country after death in a foreign state. The problems vary greatly with the degree of both pathological and administrative sophistication of the foreign country. Where these are poor, then the problems of obtaining a good – or even any – history may be great, even after attempts at using international police or diplomatic channels.

Sometimes, a 'doctor-to-doctor' approach by telephone, email or fax may be the best way of obtaining information. Even a cause of death from the foreign country may be either unobtainable or so vague (such as 'heart failure') as to be useless. Previous autopsies may be incomplete, of poor quality or even fraudulent, such as finding a stitched skin incision but no underlying dissection of organs. Several surveys of such problem autopsies have been published, with a plea for some kind of international death certificate.[22,23]

Difficulties arise when objective autopsy findings are scanty or even absent. The pathologist then has the dilemma of choosing between a cause of death based on a subjective knowledge of the alleged history (which may be wrong) or admitting that the cause of death is unascertained.

This problem, fully discussed by Leadbeatter and Knight, Cordner and Pollanen, is by no means uncommon.[24–26] For example, sufferers from epilepsy or asthma are known to die suddenly and unexpectedly, an autopsy usually revealing no adequate morphological cause for their death. Another prime example is sudden infant death syndrome (SIDS), discussed in Chapter 21, where by definition there are no significant autopsy lesions and the history is usually essentially barren.

In hypothermia where the patient is warmed up in hospital but dies in a day or two, there may be nothing to find at autopsy, yet there is firm clinical history of a rectal temperature of 26°C. Moving to more forensic cases, a body may be recovered from a river after clothing and a suicide note have been found on the bank – yet at autopsy there may be no visible evidence of drowning whatsoever.

In these cases, should the pathologist – in the absence of objective evidence of hypothermia or drowning – decline to offer a cause of death and perhaps be accused of being obstructive or perverse? Or should he certify 'hypothermia' or 'drowning', and perhaps be challenged in court by a lawyer who claims that the pathologist relied only on hearsay and has no objective evidence to offer?

The best course is for the pathologist, if he feels that the history is sufficiently strong, to give the most likely and reasonable cause of death, but make it clear in his discussion in the autopsy report that this opinion is based on a consideration of the circumstances and is not a dogmatic statement of the kind that could be offered if the victim was shot through the brain. Where a summary of the history prefaces the autopsy report, the pathologist should be careful to indicate what is 'hearsay' as far as he is concerned. Thus he should not say 'The deceased was struck on the head by two males', but 'I was told that the deceased was struck on the head by two males'.

As is discussed later, the autopsy report should not be merely a bald recital of the anatomical findings, but should have a final commentary that includes a 'differential diagnosis' where the cause of death is not clear cut, as well as a justification for the eventual opinion or an admission that there is no way of deciding between alternative possibilities.

The main difficulty arises with the actual 'cause of death' phraseology, which will be entered into the legal and national records in the format required by the World Health Organization (WHO). This gives no opportunity to express preferences or give explanations but, on the 'best-guess' principle, the pathologist can do no more than enter his most reasoned choice or, with legitimate honesty, state that the cause is 'undetermined'.

Precautions regarding potential infective conditions and other risks and hazards in autopsy room

The autopsy room as a working environment poses a number of health and safety risks and hazards to individuals working there. These can be minimized by awareness, appropriate design of the facility, adoption of safe working practices, proper supervision and management. The main risks include: infection; physical risks due to injuries associated with the use of sharp instruments or due to sharp bone fragments or other dangerous foreign objects such as exploding bullets hidden in the body or when performing necropsy on a body contaminated by toxic chemicals or radioactive materials; injuries resulting from lifting heavy loads or slipping or falling due to slippery floor; or electrocution due to faulty equipment, incorrect fittings or poor maintenance.

Risk of infection

Every cadaver has to be considered carrying a potential risk for infection as very often the death has been unwitnessed, there is no knowledge of the circumstances of death nor any previous history of the deceased and even the identity of the person may be obscure. As many forensic situations involve drug abusers and persons with promiscuous sexual behaviour, the statistical risk of HIV and concomitant tuberculosis or hepatitis infection is probably greater than in the general autopsy population. This poses a risk to pathologists, mortuary staff, police and laboratory staff who may deal with post-autopsy samples.

Pathogens can be aquired through skin injuries due to sharp bone fragments, scalpel or needle stick injuries or inoculation through pre-existing skin injuries, through the mucous membranes of the eyes, nose or mouth or possibly even by inhalation of blood-containing aerosols. A great deal has been written about such risks but no consensus has yet been reached; a recent review has been published by Burton.[27] The first case of documented seroconversion after occupational exposure to HIV was reported in 1984.[28] Since then altogether 106 documented occupationally-acquired HIV seroconversions and further 238 possible occupationally-acquired infections have been reported worldwide (data to December 2002) in a summary of published reports by the Health Protection Agency in the UK published in 2005. The true incidence of occupationally-acquired HIV infection is unknown but probably higher. The reported cases include altogether four subjects belonging to an occupational group defined as embalmer/mortuary technician. In one of them the mechanism of exposure was deep percutaneous injury sustained by a bone saw during autopsy.[29] In the three other subjects occupationally-acquired infection was considered possible.[30] Johnson and coworkers have published a well-documented case of autopsy-acquired HIV infection in a pathologist who sustained a 1 cm deep scalpel wound to the hand while reflecting the scalp.[31]

One school maintains that all autopsies should be carried out with total precautions against infective risks, so that it does not matter what case is handled. However, this is almost impossible to achieve in a busy coroner or medical examiner practice and does not solve the problem of possibly infected material being sent out to other laboratories.

Another regime is to carry out pre-autopsy testing for HIV and hepatitis, using blood from a femoral needle puncture. The result can often be returned within hours, when a decision may be made as how to handle the autopsy – or even whether to abandon it, if the risk–benefit aspect is high. More usually, a positive result will result in the autopsy being carried out with special care, additional protective clothing, visors, masks and metal gloves, with restriction of access to observers, choice of more senior technicians and warnings sent to laboratories liable to handle samples.

The time for which a corpse remains potentially contagious with HIV is variable. Infectious virus has been recovered from liquid blood held at room temperature for 2 months and virus in high concentrations has been found to remain viable for 3 weeks.[32] Fiftyone (51) per cent of the virus has been shown to survive in plasma and monocyte fractions from infected cadavers up to 21 hours post-mortem.[33] Other series found survival in corpses from 18 hours to 11 days after death. Virus has been recovered from the spleen after 14 days post-mortem. Refrigeration seems to make little difference to viability. Douceron and co-workers cultured blood and effusions from refrigerated bodies and obtained viable virus up to 16 days post-mortem and concluded that there was no safe maximum time at which corpses ceased to be an infective risk.[34] In industrialized countries, it has become standard to offer post-exposure prophylaxis after significant percutaneous exposure to blood or tissues of HIV patients.

Other infections, such as tuberculosis, hepatitis viruses, anthrax, plague, Creutzfeldt–Jakob, Marburg, green monkey diseases, etc., are usually the subject of specific health and safety regulations, which vary from country to country.

Other toxic chemical or biological agents

Box 1.4 History

The use of toxic chemical or biological agents as weapon for murder or warfare goes back to antiquity. Toxic roots (hellebore – the siege of Kirrha, ~ 595 BC) and cadavers (Battle of Tortona, 1155) have been used to contaminate water supplies, plague-infected corpses have been catapulted into the besieged city of Caffa (now Feodosija, Ukraine) in 1346–1347 or deposited in the Swedish-held town Reval (now Tallin, Estonia) by Russians in 1710, to give just a couple of examples.[35,36] Despite the international treaties on the laws of war (Hague Convention of 1899 and 1907), prohibiting '*the use of projectiles the object of which is the diffusion of asphyxiating or deleterious gases*', numerous irritant chemicals and lung- or skin-damaging agents were tested and used during World War I. According to Wheelis, the Germans had even an ambitious programme of biological warfare directed against animals in neutral trading partners of the Allied forces from 1915 to 1918.[37,38] Before, during and after World War II the use of various toxic chemicals or biological agents has continued in individual invasions, interventions, wars and acts of terrorism.

The autopsy: external examination

In contrast to the 'clinical autopsy' performed to evaluate natural disease, the importance of the external examination is far greater in the forensic case, especially in deaths from trauma. In the latter, the medico-legal value of the external description may be paramount, as it is often from the outer evidence that inferences may be made about the nature of the weapon, the direction of attack and other vital aspects. Thus the forensic pathologist must spend all the time that is necessary in a careful evaluation of the body surface and not be too impatient to wield the knife (Fig. 1.5).

The routine for external examination will naturally vary according to the nature of the case but certain general principles apply. The following procedure is a useful baseline and may be adjusted according to personal preference. Variations in criminal cases to accommodate the needs of the investigating and scientific teams are mentioned later.



Figure 1.5 External examination must note every feature; here there is obvious abdominal distension in a battered child with facial bruising. The intestine had been ruptured by a blow and oxygen administered by the ambulance crew escaped to distend the peritoneal cavity.

- After identification and removal of any clothing, the race and gender are noted. The apparent age is assessed in children by size and in adults by changes in skin and eyes, such as the loss of skin elasticity, senile hyperkeratosis, Campbell de Morgan spots (haemangioma/cherry angioma),[39] senile purpura and arcus senilis. Hair colour, tooth loss and arthritic changes are also obvious signs of ageing. The apparent age should be compared with the alleged age and enquiries made about any obvious discrepancy, in case it is the wrong body, an error that plagues most autopsy rooms from time to time.
- The body length is measured from heel to crown (in infants, more detailed measurements are described later). Ensure that the attendant does not take the 'undertaker's height' from toe to crown, as due to the plantar flexion of rigor, this can be a considerable number of centimetres more than the live standing height.

  It should also be appreciated that the post-mortem height may differ from the known living height by several centimetres. There are several opposing causes of variation, which do not necessarily cancel each other. For example, muscle flaccidity allows joints to relax, unless rigor is present, but intervertebral discs appear to shrink, allowing shortening.
- The body weight in kilograms is measured if facilities are available; if not, it should be estimated. The weight of infants must always be measured. The general nutrition and physique is assessed in terms of obesity, leanness, dehydration, oedema, emaciation, and so on.

- The state of cleanliness, personal hygiene, hair and beard length, toenail and fingernail state, and urinary and faecal soiling and other associated signs such as emaciation, suggesting neglect by the person himself or a care giver, such as infestation by maggots (see Figs 2.13–2.15), is noted. Any parasitic infestation, such as fleas or lice, is combated before proceeding.
- The general skin colour is noted, especially hypostasis (discussed at length in Chapter 2). Congestion or cyanosis of the face, hands and feet is sought. Localized discolouration, especially unilateral in a limb (Fig. 1.6), suggests arterial embolism or incipient gangrene. Pink or brownish pink patches over the large joints may indicate hypothermia (Chapter 17). Other abnormal colours include the brownish hue of methaemoglobinaemia in some poisonings, the bronze speckling of clostridial septicaemia and the dark red of cyanide that somewhat resembles the cherry-pink colouration of carboxyhaemoglobin. Naturally racial pigmentation will modify the ease with which abnormal skin colouration can be seen.
- Congenital deformities of any type are recorded, from club foot (*talipes equinovarus*) to *spina bifida*, from a naevus to extra toes.
- Acquired external marks may be important for identification purposes or in relation to past injuries and disease. Tattoos (see Figs 3.1–3.4), body piercing, circumcision, amputations, surgical scars, old fracture deformities and scars of injuries, burns or suicidal attempts on the wrist and throat are noted. These are discussed further in Chapter 3. Increasingly, artefacts – both external and internal – arise from resuscitation attempts (Fig. 1.7) and must be carefully distinguished from original trauma. This emphasizes the importance of the history, to determine whether cardiopulmonary resuscitation was attempted by trained or untrained persons.
- The hands should be carefully examined for such signs as old and new injuries, defence wounds, bruised knuckles and electrical marks. The latter are often insignificant and difficult to see unless the rigor of flexed fingers is overcome, either by force or even cutting the flexor tendons at the wrist.
- Vomit, froth or blood may be present at the mouth and nostrils, and faeces and urine may have been voided. This must be correlated with the degree of post-mortem decomposition, which often leads to purging of fluids from orifices; most forensic pathologists have had the experience of being called by the police to the scene of 'a fatal haemorrhage', to discover only bloody fluid being purged by gases from a decomposing corpse.

Vaginal discharge or bleeding is noted and the ears examined for leakage of blood or cerebrospinal fluid (CSF). Post-mortem ejaculation of semen from the external meatus is of no significance and can be seen in many different types of death. It is not particularly associated with asphyxial deaths, as sometimes stated.[40]

- The degree of rigor mortis is assessed by flexing the arms and legs to test the resistance. One should



Figure 1.6 Occasionally even minute changes in external examination, if correctly interpreted, can give a clue to the underlying cause of death. In this case a septic embolus due to bacterial endocarditis has led to a small skin necrosis on the big toe.



Figure 1.7 Post-mortem artefacts on the body of a sudden cardiac death victim. These are due to a mechanical chest compression device LUCAS (Lund University Cardiac Arrest System) applied by the paramedics after the male had collapsed on the street.



Figure 1.8 Full external examination is vital, including the interior of the mouth. Here a large number of amylobarbitone capsules offer a presumptive cause of death, though analytical confirmation is still required.

test both arms and legs, as sometimes a joint may be stiff as a result of a disease process or an old injury. If just a single joint is tested, it may give a wrong impression of the rigor. The significance of this and hypostasis is discussed in Chapter 2.

- Recent injuries (other than scars already noted) are carefully examined. In fact this part of the autopsy is often the most significant element of forensic cases. Injuries may be conveniently recorded in the mortuary by marking them on printed body diagrams. The forms can be secured on a clipboard and the data later transcribed into a written description for the autopsy report. The original diagrams should be retained, as their production may be demanded in court if there is controversy about any particular injury (Fig. 1.9).

All traumatic lesions should be clearly differentiated into abrasions, bruises, lacerations, incised wounds, burns and so on, according to the definitions given in Chapter 4. The shape and condition of the margins of each injury should be described where appropriate. It must be meticulously measured in terms of length, breadth, orientation to the axis of the body and the position with reference to surface anatomical landmarks. For example, a knife wound of the thorax might be described as follows, using ordinary language to explain any medical terms:

> A stab wound was present on the left upper chest, placed obliquely, with the inner end lower than the upper outer end. The wound was 20 mm in length, which extended to 22 mm when the edges were opposed. The maximum width at the centre was 4 mm. The centre of the wound was just below the line joining the nipples, being 6 cm from the midline, 7 cm from the left nipple and 18 cm below the centre of the left clavicle (collar bone). The wound was 132 cm above heel level and was elliptical in shape, with the inner lower end slightly more sharply cut than the rather blunt upper end. The wound was shelved in a downwards direction, with subcutaneous tissue visible along the inside of the upper edge.

This description, along with police photographs, will convey an excellent impression of the wound at any future date, including at the trial, which may be many months later. The position of the injury is related to obvious anatomical points and the height above the ground may have relevance if the stature of the victim and assailant, and the angle of attack, become legal issues. On the scalp, the occiput and the tip of the ear can be used as reference points, together with the vertex and the centre line of the head. On the face, the obvious landmarks are the eyebrows, nasion (craniometric point where the top of the nose meets the ridge of the forehead), tip of nose, lips, point of chin and angle of jaw. Where large areas of abrasion or bruising are present, similar measurements of lesion size are needed, but more general descriptions of position may be sufficient, such as ‘covering the external aspect of the left thigh’ or ‘extensive bruising 23 cm by 18 cm on the right side of the chest extending from axilla to costal margin’.

Where widespread burns are present, an estimate of the total area using the ‘Rule of Nines’ should be made, as described in Chapter 11.[41–43]

Other injuries, such as firearm wounds, are described in the same manner, being careful not to clean off any powder residues or other trace evidence before the forensic scientists have collected their samples.

With head injuries, the scalp is examined in its original condition first and any trace evidence collected. Then any clotted blood that frequently obscures the injuries can be gently removed, using a sponge and water. After this stage has been studied, it is usually necessary to shave off hair carefully around the wounds, so that the full extent of the lacerations and especially the state of their margins can be assessed and photographed. This shaving is best carried out with a scalpel fitted with a new blade,


rt.
lt.
rt.
lt.
lt.
rt.
rt.
lt.
(a)
rt.
rt.
rt.
lt.
rt.
(b)

Figure 1.9 ***(a, b)*** Typical examples of the many anatomical diagrams available for the recording of external findings at autopsy.


14
13
12
11
10
9
8
INDEX
7
K.78
6

Figure 1.10 Examination and photography of injuries; after full preliminary examination and forensic sampling the area is cleaned, shaved if necessary, and photographed with a scale adjacent to the injuries.



Figure 1.11 Where there are numerous similar lesions, it assists the clarity of the autopsy report if numbers used during photography match those listed in the autopsy protocol.

the blade being kept almost parallel with the surface to avoid making false cuts. The procedure should be carried out by the pathologist himself and not delegated to a mortuary technician. In this way any artefactual cuts can be recognized as such and not misinterpreted as part of the original wound.

- The eyes must be examined carefully, especially to detect petechial haemorrhages on the outside of the eyelids, conjunctivae and sclera. Though these do not necessarily indicate an asphyxial process, such petechiae require an explanation. Petechiae should also be sought behind the ears and in the skin of the face, especially around the mouth, chin and forehead. Care must be taken to differentiate these fine petechiae from the more coarse intradermal blood spots often seen across the shoulders or upper chest, which are caused by post-mortem hypostasis in a body with marked agonal venous congestion – especially when that surface of the body has been dependent (see Fig. 2.6). Haemorrhages in postural hypostasis are of no diagnostic significance, as true ante-mortem bleedings can never be differentiated from those that commonly develop after death.

  The size of the pupils is rarely useful, as rigor in the iris musculature can produce any degree of constriction, which may be unequal on either side (see Chapter 2). False eyes, contact lenses, lens opacity and other defects are to be noted. It is not possible to evaluate the degree of visual acuity during life from any type of post-mortem examination – though obviously a significant defect such as a cataract or a large vitreous haemorrhage is likely to affect vision.
- The mouth may reveal foreign bodies, drugs (Fig. 1.8), damaged teeth, injured gums and lips, and the bitten tongue of epilepsy or blows on the jaw. Dentures should be identified and removed before autopsy. Gastric contents in the mouth need not indicate ante-mortem regurgitation, as discussed in Chapter 14, but should be noted. Dried powder on the lips may suggest the recent taking of medicaments or poisons (see Fig. 31.1); corrosion of the mouth, lips and chin may be seen in irritant poisons (see Fig. 33.4). Bleeding from mouth, nostrils, or ears must be recorded, and later investigated as to source from internal examination. Frothy fluid, sometimes blood-tinged, may be seen issuing from the mouth or nostrils, or both, in drowning and from pulmonary oedema due to a variety of causes. Froth is sometimes pink or frankly blood-tinged. This has no particular significance unless gross, as in drowning, sudden infant death and other conditions with marked pulmonary oedema; rupture of small pulmonary or even pharyngeal vessels can add a little blood to colour the foam.
- The external genitals require careful examination, as does the anus. The state of the latter can be misleading, as a widely open, patulous anus is often seen post-mortem, due to flaccidity of the sphincter. The inner mucosa is often visible through the orifice. This is also the case in infants and children, and a diagnosis of sexual abuse must not be assumed without other corroborative evidence such as fresh mucosal tears or swabs positive for semen.

The ‘funnel-shaped’ anus, beloved of traditional textbooks as a sign of chronic homosexual activity, is such an extreme rarity that its true existence is doubtful. A funnel shape is a normal anatomical variant, the anus being set deeply between the buttocks, sometimes with a commissure of skin above it, making the approach seem even deeper. The alleged ‘shiny, silvery hyperkeratinized skin of the habitual pederast’ is also of little diagnostic value as scratching from chronic irritation, often associated with haemorrhoids, viral infections or threadworms, may lead to the same appearance. The only reliable criteria are fresh tears and old scars, as well as mucocutaneous eversion, though even these can arise from severe chronic constipation (see also Chapter 18).

Examination of the vulva and vagina is made to exclude obvious injury and disease, unless the nature of the case suggests some sexual interference, when a far more detailed examination and a special autopsy technique is carried out (Chapter 18). Routine examination of the male genitals usually need only extend to general inspection of the penis, glans and scrotum, with palpation of the testes. Circumcision should be noted, as (rarely) it may assist in identification.

The autopsy: internal examination

The dissection in a forensic case is basically similar to any other autopsy, with variations according to the nature of the death and the needs of the particular investigation, whether it be a criminal case, a civil dispute or an accident investigation. (Fig. 1.12)

There are a number of manuals devoted to the performance of an autopsy as well as one for the instruction of mortuary technicians.[44–47] Only an outline of the technique is offered here for those unaccustomed to examining the dead who may have autopsies thrust upon them by circumstances.

Figure 1.12 Scene of crime officers recovering trace evidence from hands before a homicide autopsy. The pathologist must offer the rest of the team every facility to complete their work before he begins his dissection.



Figure 1.13 Autopsy incisions: (a) standard midlline; (b) 'V-shape'; and (c) subclavicular.



Figure 1.14 The minimum instruments needed for performing an autopsy. Any further items may be useful but not essential.

In addition, special forensic procedures are described, though these are also discussed in each of the chapters devoted to the various types of injury and death. The autopsy on infants is dealt with in Chapters 20–22.

The usual incision is an almost straight line from laryngeal prominence to pubis, deviating to avoid the umbilicus. The upper end of this incision should not be prolonged above the larynx, as even a high-necked shroud will then fail to hide the subsequent suture line from relatives (Figs 1.13, 1.14).

Another common method is to cut from behind each ear to a point above the manubrium and continue downwards in a 'Y-shape'. This is often done in infants and wherever it is desired to avoid disfiguring the front of the neck. In the USA in particular, the Y-incision is favoured or even a deep 'U-shape' carried across the upper chest.

In strangulation, hanging, and any condition where the larynx might be damaged, the Y-incision is to be preferred, as the skin of the upper neck can then be dissected off the mandible and raised clear to give a wide approach to the neck structures. Here, the incision should not be made until the skull-cap and brain have been removed, to avoid the congestive artefactual haemorrhages in the neck structures, described by Prinsloo and Gordon, which can be confused with true ante-mortem trauma.[48] Pollanen *et al.* developed a model, where uninjured human cadavers, with unfixed lividity, were placed prone on a wooden board and kept at an angle of approximately 25° with the anterior neck at the lowest point. The bodies were kept for 24 hours at room temperature (~22°C) and subsequently for an additional 24 hours refrigerated (4°C) in the same position. They reported that extensive hypostatic haemorrhages or haemorrhagic lividity could be reproducibly but not universally induced in the soft tissues of the anterior neck and strap muscles and that they were microscopically indistinguishable from the acute haemorrhages observed in contusions.[49] Gordon *et al.* have further suggested that the brain be removed first in all autopsies so that abnormal odours can be detected before being swamped by the smell from the opened abdominal cavity.[50]



Figure 1.15 Angled saw-cuts for removal of skullcap to avoid slippage during reconstruction.

The Y-incision is also required when dissection of the face is necessary, to look for deep bruising or bony damage. In fact the whole face can be dissected off completely from the skull and replaced with little effect upon the cosmetic result, if careful dissection is employed. The Y-incision in the neck is made continuous with the transverse scalp incision, joining these behind each ear, so that the anterior neck and facial skin can be removed in entirety.

Returning to the autopsy in general, the primary incision should be shallow over the neck to avoid cutting underlying structures, especially the trachea. The thorax can be cut down to the sternum, but care must be taken over the abdomen, where a light cut is made, sufficient to incise only skin and fat. A small puncture should then be made in the peritoneum and a finger inserted to lift it away from the intestines. The knife is then used to cut outwards along the length of the abdomen, to avoid penetrating the intestines.

The incision for access to the skull is made from behind each ear, meeting over the crown of the head. It is well to keep this posterior to the actual vertex, again to make the stitching less obvious, especially where the hair is scanty or absent. With abundant hair – and especially in children – the hair should be wetted and then combed backwards and forwards from a transverse parting made in the line of the prospective incision. Hair is not then severed and can be combed back later to cover the stitching (Fig. 1.15).

Exposing the body cavities

The skin, subcutaneous tissues and fat are flayed off laterally from the main incision, taking care not to let the edge or point of the knife come through the skin, especially in the neck area, where repair can be unsightly. The tissues are taken back to the lateral edge of the neck and to the outer third of the clavicles. Over the thorax, the tissues, including pectoral muscles, are flayed off to the midaxillary line in the upper part and even further posteriorly towards the costal margin.

The anterior abdominal wall is similarly separated. This can be done either in two stages, first stripping back the skin and fat to expose the muscles – or the full thickness of skin, fat and muscle can be reflected together. The muscle must be cut from the costal margin and, if thick fat overlies, then some transverse relieving incisions can be made on the peritoneal surface of the lower abdominal wall, taking care not to come through to the skin.

Opening the thorax

If a pneumothorax has been suspected beforehand, a post-mortem radiograph (CT etc.) is the best confirmation. One can also dissect the intercostal space down to the parietal pleura and visualize the lung directly underneath and its collapse when incising the pleura with the tip of a scalpel. The presence of pleural adhesions must be considered. Alternatively, the chest wall can be punctured in the midaxillary line after filling the reflected skin with water to observe if bubbles escape. This test is rarely successful and cannot succeed if there is a patent communication between the pleural cavity and the bronchial tree. If there is a marked tension pneumothorax, the hiss of escaping air may be heard when the tip of the knife penetrates the intercostal muscles and parietal pleura.

The thorax is opened by first disarticulating both sternoclavicular joints. This is carried out by moving the shoulder tip with one hand, to identify the joint capsules. The point of a knife is then introduced vertically and cut laterally in a half-circle to separate the joints. If they are ankylosed, which often occurs in old age, then the clavicles can be cut through at the end of the next operation. This consists of the severing of the ribs and can be performed either with a handsaw or a rib shears. In children and many adults, the costal cartilages may be cut through with a knife, though this provides a rather narrow exposure of the chest contents. In infants, the soft cartilage can easily be divided with a scalpel: in older bodies, a stout knife should be kept for the purpose to save blunting the knife that is needed for organ dissection. Often the first rib has to be sawn through, even though the remainder are cut with a knife.

When a saw is used, the ribs are cut through lateral to the costochondral junctions from a point on the costal margin to the sternoclavicular joints or nearby. If a saw is used, it must be kept at a low angle to avoid the tip lacerating the underlying lung, especially if there are pleural adhesions. When the sternum and medial rib segments are free, the section is lifted and dissected away from the mediastinum, keeping the knife close to the bone to avoid cutting the pericardium. The sternal plate is examined for fractures or other lesions before it is put aside: damage caused by the considerable trauma of resuscitatory cardiac massage is frequently found at this point.

The whole of the thorax and abdomen is now open for inspection. The degree of inflation of the lungs should be assessed, noting complete or partial collapse, emphysema, overdistension and any asymmetry of inflation.

The pleural cavities are inspected for adhesions, effusions, pus, blood, fibrin and even gastric contents.

Examining the abdomen

The abdomen is then inspected (Fig. 1.16), though ascites, faeculent fluid, pus and blood may already have escaped on first opening the peritoneal cavity.

The omentum may show inflammation or fat necrosis. When moved aside, the loops of bowel are inspected for any abnormality, especially infarction, peritonitis and the distension of ileus. Beware of mistaking post-mortem hypostasis for the necrosis of mesenteric embolism or strangulated bowel. Though the dark colour may be similar, hypostasis usually has irregular segments when the gut is stretched out, whereas infarction occupies one continuous section – and if well established, the bowel wall will be lustreless and friable.



Figure 1.16 White shining fat droplets (chylomicrons) in mesenterial lymphatic vessels suggesting post-prandial state.

The bowel is gently moved aside to look at the posterior part of the abdomen: a retroperitoneal haemorrhage from a ruptured aorta may be visible, or an aneurysm itself.

The collection of body fluid samples

In a large proportion of forensic autopsies and virtually every one with criminal connotations, samples of blood and other body fluids and tissues are needed for laboratory examination. In relation to sexual offences, the taking of swabs and other samples is described in Chapter 18. Where blood and other fluids are required for toxicological, biochemical, microbiological and serological investigations, they are usually collected at the early stages of the autopsy (see Chapter 27).

The site of collection depends on the nature of the test. When samples for toxicological analysis are required, considerable care should be employed in sampling; this is more fully discussed in Chapter 27.

It is not advisable to use visceral blood for sampling, especially for small molecule substances that can easily diffuse after death; these include alcohol and many pharmaceutical products. Though older textbooks advocate the use of heart blood as a convenient source of samples, it may be contaminated by post-mortem diffusion from the stomach and intestine. After death, the cellular barrier of mucosa and serous membranes breaks down, and substances in the stomach, intestine and air passages can migrate to other organs in the main thoracoabdominal cavity, causing a false rise of the true ante-mortem blood level.

Pounder and Yonemitsu (see Chapter 27) found that a slurry containing alcohol and paracetamol, placed in the trachea after death to resemble gastric contents, gave rise to appreciable concentrations of those substances in blood samples taken from thoracic vessels, whereas femoral blood remained uncontaminated.[51]

For substances such as carboxyhaemoglobin this does not matter, but alcohol is the prime example of a potential source of error if visceral blood is collected. The better choices for collection sites are:

- By needle and syringe puncture of the femoral vein before the autopsy dissection begins. This requires practice but, in adults, 20 ml can usually be aspirated without trouble. This is the method of choice if only an external examination is possible.
- From the subclavian or external iliac veins after the body has been eviscerated. By holding a small container under the cut end of a subclavian vein and raising the arm, blood can be collected directly.

If the flow is slow, the arm can be massaged towards the shoulder. Similarly – and preferably if volume is required – by cutting across the iliac veins at the brim of the pelvis, a container can be dropped into the pelvis with its mouth under the vein and blood massaged into it by firm pressure moved up the inner thigh. As all these containers will be soiled externally, the blood should be decanted into a fresh tube for transmission to the laboratory.

- When the skin is dissected off the neck, the internal jugular vein is exposed, especially if a sternomastoid muscle is divided and pulled aside. When cut, a copious flow of blood is usually obtained, which can be collected directly into a container. The only disadvantage of this method is that if the blood wells up from the thoracic inlet via the superior vena cava, heart blood is likely to be admixed, with the possible errors mentioned earlier. If the blood is collected from the upper segment of the jugular, then blood from the head is collected: this flow can usually be stimulated by raising and lowering the head during collection.

Samples for serology and for analysis for substances such as carboxyhaemoglobin, which are not absorbed from the gastrointestinal tract, can be collected from any blood vessel, but blood should never be scooped up from the general body cavity after evisceration, as this can be contaminated with any leakage from other structures, such as gastric or bowel contents, mucus, urine, pus or serous fluids.

Urine can be collected by catheter before autopsy or even by suprapubic puncture with a syringe and long needle. However, it is usually obtained after the abdomen is opened, but before the organs are removed. If the bladder is full, the fundus is penetrated, and urine collected either by syringe or directly into a container. If almost empty and contracted, the fundus is gripped and pulled upwards so that it stretches, then is incised and the contents removed by syringe. Care should be taken not to contaminate the urine with blood.

The removal of vitreous humour and CSF may be required for toxicology or for attempts at estimating the time since death by the potassium content (see Chapter 2). Vitreous humour must be aspirated with care if any reliable results are to be attained. A fine hypodermic needle attached to a 5 ml syringe is inserted into the outer canthus of the globe after pulling the eyelid aside. When released, the lid will cover the small puncture mark, hiding any sign of interference. The needle should be entered into the centre of the globe to avoid aspirating material near the retina, which has a markedly different chemical composition due to shreds of detached retina entering the aspirate. The fluid should be sucked off slowly and gently, and as much taken as possible to obtain a mixed fluid: both eyes should be used, as they often differ somewhat in their chemical composition. After withdrawing vitreous, the globes can be re-inflated with water, to improve the cosmetic appearance of the eyes.

Cerebrospinal fluid may be obtained in the same way as in living patients, by passing a needle into the theca between the lumbar spines. A baby can be held upright by an assistant in a fully flexed position; an adult must be pulled into flexion while lying sideways on the autopsy table. An alternative technique is to perform a cisternal puncture through the atlanto-occipital membrane.

As there is no pressure within the theca in a cadaver, the fluid must be actively aspirated: sometimes all attempts at obtaining fluid by external puncture fail. The only course then is to try to puncture the ventricles through the exposed brain surface when the skull is opened. Attempting to obtain clear CSF from the interior of the skull after removal of the brain is generally useless: though blood-stained fluid can be centrifuged to clarity, its chemical composition is then unreliable.

Removal of the viscera

After the body cavities have been inspected, the organs are removed *en bloc* by a modified Rokitansky procedure, more accurately described as Letulle's method (Maurice Letulle, 1853–1929). First, the intestine is removed, as follows.

The omentum is lifted upwards to expose the coils of small intestine. The uppermost part of the jejunum is identified, where it passes retroperitoneally to join the termination of the duodenum. Here the mesentery is perforated with the knife and the gut cut through. If it is essential to retain the duodenal/gastric contents or the small intestinal contents, two string sutures may be passed through the hole and tied before cutting the gut between them, but little contents are lost if this is not done. The intestine is stripped out by cutting along the mesentery near the attachment with the bowel until the ileocaecal valve is reached.

The caecum is then mobilized medially using manual traction with minimum use of the knife, to avoid puncturing the lumen. When the hepatic flexure is reached, the omentum is pulled downwards to draw the transverse colon tense against the mesocolon, which is cut through, taking care not to open the adjacent stomach. The splenic flexure is then pulled medially and downwards, and the descending and sigmoid colon separated from the posterior abdominal wall. The upper rectum is cut across, though some pathologists merely lay the gut outside the body, leaving the sigmoid and rectum attached.

Removing the neck structures

To make the removal of the neck structures easier, a block 10–15 cm high should be placed under the shoulders of the cadaver. This allows the head to fall back and thus extends the neck. This should be done gently, as with all handling of the body, to avoid the well-known 'undertaker's fracture', which is a subluxation of the lower cervical spine due to tearing of the intervertebral disc at about C6–C7. This can be misinterpreted as an ante-mortem injury, especially if the other common artefact of haemorrhage over the anterior longitudinal ligament of the cervical spine is present.[48] The neck structures are then freed by passing a knife under the skin of the upper neck until it enters the floor of the mouth. The knife is then run around the inside of the mandible to free the tongue. The tissues at the back and sides of the pharynx are divided, and the tonsillar area cut through. Fingers are then passed up behind the mandibular symphysis to grasp the tongue, which is then drawn down, the remaining tissues behind the larynx being divided to release the neck structures. This should be done as far lateral as possible, so that the carotids can be removed with the laryngeal structures. It is now advisable to look into the pharynx and glottis before any further disturbance, to see if any obstruction, bleeding or other abnormality is present in the upper airway.

Removal of the thoracic contents

The subclavian bundles of vessels and nerves are divided by passing the knife from inside the thorax around the medial ends of the clavicles and first ribs to release the trachea and oesophagus. With gentle traction, the neck structures are held up and pulled caudally, while carefully clearing all attachments to the thoracic spine with the knife, taking care to keep the blade on the bone and not stray anteriorly to damage oesophagus or aorta.

Traction should be minimal and, as soon as the thorax is entered, the hand should move from the neck structures to place two fingers under the upper lobes of the lungs, lifting them and the mediastinum as the knife clears the midline structures down to the diaphragm. If the neck structures are pulled too hard by using them as a handle to drag out the thoracic viscera, they may be ripped off. In addition, the descending aorta may suffer transverse intimal tears from traction, which resemble the genuine 'ladder tears' seen in many traffic accidents (Chapter 9).

Pleural adhesions may prevent clean removal of the lungs. If there are only a few, they can be cut through. If the whole pleural cavity is obliterated by adhesions, they may be pulled away by making a cleavage plane with the hand and stripping them off. Sometimes (especially in industrial chest disease and old tuberculosis) the adhesions are dense, tough or even calcified. Removal of the lung may then be achieved by running a knife down the whole length of the parietal pleura over the inner anterior aspect of the ribs, and forcing a hand through the slit to form a cleavage plane to force the parietal pleura off the intercostal muscles and ribs.

Removal of the abdominal organs

When the chest organs are free, they are laid back in the thorax and the diaphragm incised. One hand should pull the liver and spleen medially, putting the left leaf of the diaphragm on the stretch, while the knife cuts it through laterally, near the costal margin. The cut curves posteriorly under the organs to reach the spine, where it must cut through the cruciate ligaments, then passes caudally behind the kidney, which is mobilized forwards.

The knife cut then curves up over the psoas muscle and ends at the brim of the pelvis. The same is done on the opposite side, the operator moving around the body if necessary. The chest organs are then lifted and gently pulled forwards to carry the abdominal viscera towards the feet. Any resistance is usually due to incompletely severed cruciate ligaments, which must be transected.

Eventually the organs will lay inverted across the pubis, secured only by the iliac vessels and ureters, which are cut through and the whole pluck of viscera taken away to the dissecting bench where running water and good illumination must be available.

Removal of the pelvic organs

The treatment of the pelvic contents depends on the type of case. Where the presumed cause of death is unrelated to pelvic lesions, then in males the bladder may be opened widely and the mucosa and trigone inspected before the prostate is incised for examination. The testes are pushed upwards through the inguinal canals, which are widened with the knife. In women, the ovaries are incised and the tubes examined from above before the uterus is sliced in the midline from fundus to cervix.

A more thorough examination of either gender may be made by enucleating the pelvic contents. The knife is passed circumferentially around the pelvic bowl after pulling the bladder away from the pubis. When the walls are free, the knife cuts through below the prostate and then through the lower rectum to allow the pelvic organs to be lifted out. In women the ovaries and tubes are mobilized forwards and the knife passed around the wall of the pelvic bowl, then in front of and below the bladder. The vault of the vagina and rectum is transected, freeing the whole contents. In cases where sexual interference or abortion is suspected, a special technique described in Chapter 19 is employed.

Removing the brain

Attention is then turned to the head. The scalp is incised across the posterior vertex from a point behind the ear to the corresponding place on the other side. Where a Y-incision is used on the neck, the limbs of the Y may be continued right across the scalp, especially if a face dissection is necessary.

The tissues are reflected forwards to the lower forehead and back to the occiput. The deep scalp tissues may peel off by traction, but often require touches of the knife to free them. Bruising is sought and, where head injuries are present or suspected, the scalp should be reflected right back to the nape of the neck, paying particular attention to the tissue behind and below each ear where injuries causing vertebrobasilar artery damage occur. Where there are facial injuries, the skin of the face may be peeled back from the jaw line and downwards from the forehead, restoration being excellent if care is taken not to perforate the facial skin during removal.

The skull is sawn through, using either hand or power tools. The line of the cut should not be along a circumference, as it is then impossible to reconstitute the head without unsightly sliding of the calvarium. There should be an angled removal, with a horizontal cut from forehead to behind the ears joined by a second, which passes diagonally upwards at a shallow angle over the occipitoparietal area. Care must be taken not to place this posterior saw-cut too vertically (and thus anteriorly) on the skull, or the brain may be damaged by forcing its removal through too narrow an aperture.

The calvarium is then removed by leverage after complete cutting through. A mallet and chisel should not be used in forensic autopsies, even to ensure that the dura is kept intact. The risk of extending or even causing fractures by the use of excessive hammering is too great merely to justify an unmarked dural membrane. A cut dura is easily recognized as such by any competent pathologist. What is more important is to inspect the surface of the exposed dura and brain and assess any oedema, bleeding or inflammatory conditions that may be present. The skull-cap is carefully inspected for fractures and the dura peeled off the inside to study the inner skull surface.

To remove the brain, the dura is incised around the line of skull removal and two fingers slipped beneath each frontal lobe. With gentle traction the frontal lobes are lifted to expose the optic chiasma and anterior cranial nerves. The falx may have to be cut to free the brain, then a scalpel or blunt-pointed bistoury is passed along the floor of the skull to divide the cranial nerves, carotid arteries and pituitary stalk until the free edges of the tentorium are accessible. A cut is made along each side of the tentorium, following the line of the petrous temporal bones to the lateral wall of the skull. Continuing with traction on the brain, but being careful not to impact the upper surface against the posterior saw-cut, the knife severs the remaining posterior cranial nerves and then passes down into the foramen magnum to transect the spinal cord as far down as can be reached. The hand is now slid under the base of the brain, which is rotated backwards for removal, any attached dura being severed where necessary. The brain is taken into a scale pan and weighed before either fixation or dissection.

The floor of the skull is now examined and the basal dura stripped out with a strong forceps to reveal any basal fractures. Discarded dental forceps can be useful for this purpose. The venous sinuses are incised to search for thrombosis. Where appropriate – and always in infants – the petrous temporal bones are sawn, chiselled or cut with bone forceps to examine the middle and inner ears for infection.

Removal and examination of the spinal cord

It is not an invariable routine to remove the spinal cord at autopsy unless there are indications that some lesion may be present. Where there is the slightest possibility of damage to the vertebral column, its blood vessels or the contents of the spinal canal, however, there should never be any hesitation in extending the autopsy to include this area.

There are several methods of removing the cord and for full details, the texts of Ludwig or Knight should be consulted.[45,47] Briefly, there are two main approaches to the spinal canal, the anterior and posterior.



Figure 1.17 The two approaches to the spinal canal for the removal of the spinal cord at autopsy.

In the anterior method, the vertebral bodies are removed after complete evisceration of the body, by sawing through the pedicles by a lateral cut down each side. The advantages are that the body need not be turned over onto its face and an extensive dorsal incision is avoided, which requires subsequent repair. The author finds this method more laborious, however, especially in the thoracic region where the heads of the ribs make the approach difficult.

The more usual posterior approach requires a midline incision from occiput to lumbar region, the paraspinal muscles being reflected along with subcutaneous tissues. Two parallel saw-cuts are then made down the length of the spine to divide the right and left laminae, and to give access to the spinal canal. This is best done with an electric oscillating saw, taking care not to cut so deeply that the spinal dura is penetrated. The strip of bone may be dissected off from below upwards to expose the spinal canal (Fig. 1.17).

The cuts should be placed sufficiently lateral to allow the cord to be removed without difficulty. When the canal is exposed, the dura is examined for haemorrhage, infection or other abnormalities, then removed – still within its dural sheath – by transecting the nerve roots and dural attachments, and peeling it out progressively from below upwards. The dura is then carefully opened with forceps and scissors to examine the cord itself. It can be fixed in formalin, as with the brain, before cutting, or dissected immediately and samples taken for histology. Crushing, infarction, infection, haemorrhage and degeneration are the main lesions in a forensic context. The empty spinal canal must be carefully examined for disc protrusions, tumours, fractures, haemorrhage, dislocations and vertebral collapse.

Where in any autopsy spinal damage is suspected, a good preliminary test is to slide the hands under the back of the eviscerated body on the autopsy table and lift the dorsolumbar spine upwards, while watching the interior vertebral bodies. If a fracture or dislocation is present, abnormally acute angulation will be seen, instead of smooth bending. The cervical spine can be tested by manual manipulation. If suspicious angulation is seen, a slice can be taken along with the anterior spine, through the vertebral bodies and discs, with an electric or handsaw. This will reveal the interior of the spine and exhibit any crushing, haemorrhage or torn disc spaces: if one of these is found, the cord must always be removed.

Examination of organs

Examination of viscera

The thoracic and abdominal viscera are laid on a cutting bench at a convenient height and under good illumination. Ample washing water should be available from a flexible pipe, to flush the tissues as dissection proceeds. Some pathologists maintain that this should not be done, as the water can have an effect on the quality of subsequent histological sections, but this has been disproved.[52] In any case, the vastly inferior naked-eye examination that results if blood is not removed at frequent intervals greatly outweighs any unsubstantiated objections about the more exquisite details of cell structure, especially as in most forensic autopsies the gross appearances are usually far more important.

The viscera should be laid so that the tongue faces the pathologist, with the aorta upwards. The same sequence of examination should be carried out whatever the nature of the case, so that a fixed routine will ensure that nothing is left undone.

The neck structures

The tongue is examined for disease and injuries, including bites suggesting blows in the jaw or epilepsy. The tongue should be sliced to detect deep haemorrhages sometimes seen in strangulation. Such haemorrhage is seen mostly at the sides and centre of the midpart of the tongue. Gross congestion, which may be due to either pressure on the neck or to other congestive modes of death, is usually in the posterior part of the tongue. The tonsils and pharyngeal walls are inspected.

The glottis is examined for mechanical or infective obstruction, and the hyoid and thyroid horns palpated for fractures. The oesophagus is opened with large (20 cm) blunt-nosed scissors, which along with a very sharp 10–15 cm bladed knife and a long-bladed 'brain knife', are the most useful tools for performing an autopsy.

The carotid arteries on each side are opened, including the bifurcations and sinuses. If necessary, the upper portions of the carotids are explored in the body itself and followed to the base of the skull. If thrombosis is suspected, the intracranial part should be examined in the cavernous sinus.

Returning to the neck structures, the thyroid should be sliced and inspected, then the oesophagus opened almost to the cardia of the stomach and any suspect material such as capsules, tablets or powder retained for analysis.

The scissors are then passed down the posterior line of the larynx and trachea to the carina. If pressure on the neck of any type, such as strangulation, is suspected, then special examination should be made, as described in Chapter 14.

The trachea and main bronchi should be inspected for disease and obstruction. Gastric contents are often found, but the significance of this is discussed in Chapter 13 – it should not be assumed that ante-mortem aspiration has occurred merely from the presence of gastric contents in the air passages.

The lungs

The lungs are then removed, after careful examination of their external surfaces for patchy collapse, emphysema, petechiae and so on. Almost every autopsy will reveal a few petechiae, especially around the hilum and in the interlobar fissures. Their significance is also discussed in Chapter 13.

The lungs are removed from the thoracic pluck by passing a long-bladed knife (such as a brain knife) under the hilum with the blunt edge upwards. The knife is settled in the correct position before turning the sharp edge upwards to cut through the hilum. Before doing this it may be necessary to remove adhesions over the diaphragm and to cut through the pulmonary ligament, a thin sheet of tissue that ties the inferior medial edge of the lower lobe to the mediastinum.

As the hilum is being cut, the pathologist must notice if any embolism is visible within the pulmonary arteries. It has happened that such an embolism has slid out and been washed unnoticed down the sink. Some pathologists insist on opening the main pulmonary trunk and even right ventricle before removing the lungs, to seek a saddle embolus. This is not necessary, as any large embolus will be readily visible on examining the heart and the lungs in the usual sequence.

Both lungs are taken off and the hilum inspected before being laid aside for cutting. The lung should be weighed before cutting, as appreciable oedema fluid can run away during dissection. Then each is laid with the hilum down on the dissecting board, the opportunity being taken during handling to evaluate weight and oedema, as well as emphysema.

The lung is held on the upper surface by the left hand of the operator (or by an interposed sponge) and the organ cut across in the sagittal plane from apex to base with the large brain knife, held parallel to the board. This produces an anteroposterior slice, the lower medial part carrying the hilum. The cut surfaces can now be opened like a book and the surface examined for oedema, tumour, pneumonias, infarction, trauma and so on. The smaller bronchi must be inspected for such signs as mucosal thickening, infection and blockage. The smaller pulmonary arteries may reveal thrombosis or embolism that was not visible in the larger vessels.

Inflating the lungs with formalin

In some medico-legal autopsies, especially in industrial lung disease such as pneumoconiosis or asbestosis, one or both lungs need to be inflated with formalin for fixation before cutting. This preserves the shape and histology in excellent condition, but delays examination for at least several days. It is carried out by holding or tying a cannula into the bronchus while 10 per cent formol saline is perfused through a tube from a reservoir held about 1 metre above the lung. The lung is then left in a bath of formalin covered with a formalin-soaked cloth to prevent drying. Sutinen *et al.* described a post-mortem method for correlative radiological and pathological studies of the lung, including radiography after air inflation, fixation with formalin–polyethylene glycol–alcohol solution, air drying and systematic histological sampling of lung tissue.[53]

The heart and great vessels

There are almost as many ways of examining the heart as there are pathologists, and each operator must decide upon the method that appeals most. In this summary there is no space for discussion of post-mortem angiography, which is moving from the field of research and special interest into routine use. A common and practical routine for examining the heart is described here.


Right atrium
Right auricular appendage
IVC
1
2
Pulmonary conus
Right ventricle
Septum marked by anterior descending vessels
(a)
Aorta
1
Pulmonary artery
2
3
Left ventricle
(b)
Pulmonary veins
Right atrium
4
Left auricular appendage
Posterior descending vessels
(c)
6
5
(d)

Figure 1.18 Incisions for opening the heart at autopsy. (**a**) The right atrium is slit with an incision (1) to join the vena cava to the appendage; a cut parallel to the interventricular septum is made on the anterior wall of the right ventricle (2) passing up through the pulmonary conus. (**b**) These cuts are joined through the tricuspid valve (3). (**c**) The heart is reversed and the left atrium opened by a cut (4) joining pulmonary veins. (**d**) On the anterior wall a cut (5) is made parallel to the septum through the mitral valve and joined by (6), which passes through the aortic valve.

First, the organ mass minus the lungs is rotated so that the lower end now faces the pathologist. The scissors are passed into the cut end of a common iliac artery and passed right up to the aortic arch and around to a few centimetres above the aortic valve, staying outside the reflection of the pericardium. The interior of the aorta is studied, especially for the degree of atheroma and for any aneurysms or trauma. The inferior vena cava is opened from its lower end into the liver. The organ pluck is then turned over so that the heart is uppermost. The pericardium is inspected externally for fluid and blood tamponade, then opened widely with scissors. The heart is delivered through the incision and inspected externally for pericarditis, adhesions, discolouration of an underlying infarct and cardiac aneurysms, for example. In a child, the thymus would be inspected and dissected off at this stage.

The heart is then removed by holding it up with the left hand so that its attachment is tensed against the other organs. A long knife, such as a brain knife, is then passed horizontally across at the reflection of the pericardium, cutting through the root of the aorta and other great vessels just above the atria.

The now-detached heart is washed externally and placed in the anatomical position on the dissecting board, with the apex facing the operator and the anterior surface upwards. It should not be weighed until all the contained blood and clot is removed. The general size, shape and ventricular preponderance should be noted. Any dilatation or thickening of the pulmonary conus should be noted as an index of right ventricular hypertrophy, especially if striae of transverse muscle fibres are seen crossing the conus.

The right atrium is then opened by introducing the scissors into the inferior vena cava and cutting across to the atrial appendage. The interior of the atrium is examined and the septum and tricuspid valve inspected (Fig. 1.18).

The interventricular septum is then identified externally by the vessels running down the outside. With a knife a cut is made about 15 mm to the right of and parallel to the septum, over the right ventricle. This should be deep enough to enter the lumen, but not enough to cut the posterior wall. The scissors are now introduced into the cut and run up through the pulmonary conus and into the pulmonary artery until they meet the transected end. They are also extended downwards to the apex of the ventricle. The scissors are now put in midway down this linear cut and passed outwards at right angles, guided by the fingers of the left hand passed into the tricuspid valve from the opened atrium. The whole of the right side of heart is now open and displayed. It should be washed out and the endocardium and valve examined.

A similar routine is now employed on the left side. The scissors are introduced into a pulmonary vein and passed horizontally across to an opposite vein, thus opening the atrium. Fingers are introduced down through the mitral valve to estimate its size and detect any stenosis.

The heart is then restored to the anatomical position and a cut made again parallel to the septum, but on the left side, going deeper as the ventricle is thicker. Guided by the fingers still in the mitral valve, the cut is extended upwards through that valve and out at the top of the atrium.

A finger is now passed up the outflow tract to the aortic valve to estimate its size. Then the scissors are passed up at the side of the mitral valve, and the aortic valve and aortic stump opened. The whole heart is now open and can be washed out and weighed.

Various estimates of the normal heart weight exist and vary considerably. It has been related to gender and body weight, though this is not altogether sound, as a fat person of moderate stature does not have a heart weight comparable with a large muscular person unless there is associated hypertension. This controversial matter cannot be pursued here, but as a rule of thumb the author (BK) accepts up to 380 g as normal in an adult male of average build.

After weighing, the endocardium and valves are examined, then the coronary arteries. Once again, controversy exists about methods of opening the coronary vessels, but the weight of opinion now lies almost universally with those who cut serial interrupted cross-sections with a knife, rather than open them longitudinally with small scissors. The disadvantages of lengthwise opening are that percentage assessment of stenosis or the recognition of total occlusion cannot be made once the vessel is flapped open, as restoring the cut edges can never reproduce the original conditions. In addition, the tip of the scissors may dislodge thrombus or an intimal flap. Cutting across the vessels allows an estimate of the percentage stenosis. It is admitted that this may not be the size of the lumen during life when normal blood pressure is operating, but the same disadvantage applies to longitudinal opening. An estimate of luminal size is relatively constant, however, in that the collapsed abnormal can still be compared with the collapsed normal.

The coronaries are therefore cut across at frequent intervals. Before the first cut, the ostia are examined for congenital variations (which are frequent) and for obstruction. The left coronary artery is then cut across from the epicardial surface, starting as close to the ostium as possible, as occlusion and severe stenosis can occur very near the origin. Serial cuts are then made at intervals of not more than 3 mm, first into the common trunk, then following the left circumflex laterally until the vessel becomes too small, usually when it dips down from the epicardium to become intramuscular. The anterior descending branch is then followed down the front of the septum almost to the apex.

Turning to the right coronary artery, the proximal segment is cut back from the point where the right ventricle was opened, transecting the artery in its midpart. The cuts are made back to the aorta, then the distal segment is followed laterally until it becomes the posterior descending branch. During this process, the dominance of right versus left vessels is noted.

Difficulty arises where severe calcification exists, as the knife either fails to cut through the artery or shatters it because of the excessive force required. The lumen is crushed and the percentage stenosis is difficult or impossible to assess. Scissors may be used to exert more force than a knife, but the only real solution is to decalcify the vessels. Except for research purposes, it must be admitted that the days or even weeks of delay occasioned by decalcification provide a formidable deterrent for the busy coroner's pathologist unless the issues involved are important. Post-mortem angiography is the other alternative, though where autopsy caseloads are high, this can be difficult to arrange. During autopsy, a contrast medium, such as barium sulphate/gelatin suspension or radio-opaque silicone compound is injected into the coronary arteries while the heart is *in situ* or into the vessels of the isolated heart and can be visualized by conventional or digital X-ray or by computed tomography.[54–56]

Once the coronary arteries have been examined, the myocardium can be studied more closely. One useful technique is the intramural or 'sandwich' cut through the thickness of the left ventricle. This is easier when there is some ventricular hypertrophy, but can be carried out in any heart. The heart is placed open on the cutting board, with the endocardium downwards. A long knife such as a brain knife is passed carefully into the cut edge of the left ventricle and sliced right through the muscle, keeping equidistant between endocardium and epicardium. The myocardium can then be opened out like a book, showing the interior with any infarcts or fibrotic plaques. If histological blocks through the entire wall are needed it is best to take these before slicing the heart as described, otherwise a full-thickness block will be hard to obtain. Some pathologists make a series of transverse heart slices about 8–10 mm thick, starting at the apex, before opening the heart. This displays the distal myocardium wall, but cannot expose the proximal part, as examination of the coronary arteries would then be compromised.

The abdominal organs

The remaining organs are laid on the dissecting surface in the anatomical position, with the liver and stomach away from the pathologist, and the anterior surface upwards.

The stomach is opened and, if there is any question of requiring the contents for analysis, a suitable container should be ready. The stomach is washed externally with a stream of water and a small cut made in the greater curvature. If the contents are to be saved, this can best be done with the edge of the stomach projecting over the raised cutting board or over the edge of the sink, so that the container can be held underneath (Fig. 1.19). The contents are allowed to run into the container, then the greater curvature is opened widely with scissors, and any remaining contents drained or scraped out. If powder or other substance is adherent to the mucosa, this can be scraped off and added to the container, or kept in a separate tube for analysis.

Some laboratories require the stomach wall to be retained for analysis as well as the contents. This can be done after the organ has been fully opened and the lining examined. If the contents are not required – or when they have been collected – the organ is opened up from cardia to pylorus along the greater curvature. The lining is washed and inspected. The scissors are now passed through the pylorus around the duodenum until they meet the point where the gut was detached earlier. The gall bladder may be squeezed to demonstrate the patency of the bile ducts. Bile is an important matrix for toxicological analysis, in particular, if there is no urine. The adrenals are examined next, the right one being on top of its kidney, the left being on the medial side. If the right kidney is taken in the left hand and lifted against the weight of the liver, a single cut into the stretched tissues between liver and kidney will transect the adrenal. The left is buried in the tissue between pancreas, spleen and kidney. The amount of cortical lipoid and the absence of bleeding or other abnormality is noted in each gland.



Figure 1.19 Collecting stomach contents at autopsy. The exterior of the stomach is washed free from blood and the viscera moved to overhang the dissecting board. A chemically clean receptacle is held beneath the greater curvature while the latter is opened with scissors and the contents allowed to drain out. The stomach is then opened, the mucosa inspected and any adherent material scraped into the container. The stomach wall should then be dissected off and added to the contents if the laboratory is able to deal with tissue analysis.

The spleen is removed by cutting through its pedicle and is sliced after weighing. The pancreas lies under the stomach and should be cut lengthwise from the curve of the duodenum to its tail lying against the splenic hilum.

The kidneys are exposed by incising their capsules, often after a thick layer of perirenal fat is traversed. The kidneys can usually be peeled out of their capsules unless these are adherent.

The renal vessels were examined when the aorta was opened, but can be re-examined at this stage and the ureters inspected. The organs can be detached at their hilum and weighed, then cut lengthwise to inspect the interior. The width of the cortex is important, being about 1 cm in a healthy subject. The granularity of the surface and the clarity of the corticomedullary junctions is assessed, as well as the size of the renal pelvis.

The small intestine may have been examined at the earlier stage of removal, but can be inspected now. It is not usual to open the whole length of the gut in a forensic autopsy unless there is any particular indication to do so, though ideally this should always be carried out.

Examination of the brain

After weighing, a decision has to be made whether to examine the brain immediately – the so-called 'wet-cutting' – or to suspend it in formalin until fixed. The advantage of fixation is, of course, that the firmness of the tissue allows thinner and more accurate knife-cut sections to be taken, as well as better histological preservation. Where neurological issues are involved, either traumatic or from natural disease, it is almost mandatory for the brain to be fixed before cutting. Even the impatience of the investigative authorities can usually be overcome if the advantages of a higher standard of opinion are explained.

The technique of brain fixation is well known, but to summarize briefly, the brain is suspended in a container of 10 per cent buffered formalin, the volume being about 10 litres, for at least 10–14 days. The fixative ought to be changed after 48 hours and 10 days.[57] The brain is removed with the dura, leaving the parasagittal bridging veins and falx intact and suspending the brain in an upright position by the falx (Fig. 1.21). An alternative method is to pass a thread or metal paperclip under the basilar artery and tie it to a support across the mouth of the container, so that the vertex is clear of the bottom (Fig. 1.20).

In the majority of autopsies there is no real need for fixation if no cerebral lesions are either expected or apparent on external examination of the brain. Here, 'wet-cutting' is sufficient, though if any unexpected lesions are found, the process can be stopped and the slices of brain fixed by placing them in a large volume of formalin, on cotton wool pads, to prevent distortion.

One lesion is better examined in the unfixed state, though the brain may be suspended later: this is subarachnoid haemorrhage. It is easier to wash away fresh, unfixed blood with a stream of water and blunt dissection than the hardened blood that develops during formalin fixation. Further details are given in Chapters 5 and 25.

Whether the brain is examined 'wet' or fixed, the sequence is the same. The weight is first considered, the normal for a young male adult being between about 1300 and 1450 g, the female equivalent being around 100 g less. It should be noted that formalin fixation adds about 8 per cent to the original weight.



Figure 1.20 A brain suspended in formalin for fixation before cutting. The tank is specially made of fibreglass, being cubical for stacking with a lid (not shown). There are lugs moulded into the sides to hold the suspensory strings, which support the brain by means of a paperclip hooked under the basilar artery. There should be sufficient fluid to allow the brain to float clear of the bottom of the receptacle.



Figure 1.21 An alternative method of suspension is to leave the falx intact and use it to suspend the brain base down in formalin.

The brain is first examined for surface abnormalities, which in forensic practice usually means haemorrhage. This is dealt with in Chapter 5, but suffice to say here that meningeal bleeding is one of the most important lesions in forensic pathology, be it extradural, subdural or subarachnoid. This means that examination of the cerebral vessels, especially the arteries of the circle of Willis and the vertebral vessels, is vital – especially in the search for berry aneurysms (see Fig. 5.38). The general symmetry of the brain is then noted as well as any depression of the cortex from skull or meningeal masses. An estimate of cerebral oedema is made, partly from the weight, but mainly from flattening of the gyri, filling of the sulci and evidence of hippocampal herniation through the tentorial aperture. In lesser degree this may be seen as grooving of one or both unci, though a normal slight anatomical groove is often present. True uncal herniation is marked and often discoloured as a result of incipient infarction. Similarly, herniation or coning of the cerebellar tonsils through the foramen magnum must be distinguished from the common anatomical pouting of many tonsils: true pressure coning is often discoloured by local infarction (see Figs 5.48–5.50). After careful inspection of the basal vessels and the exterior of the brain, and palpation for any fluctuant masses under the cortex such as internal haemorrhage, abscesses or cystic tumours, the organ is cut.

The first cut should be made through the cerebral peduncles using a long, broad-bladed knife to separate the cerebrum from the brainstem and cerebellum. The cerebellum is then held in one hand with the cut stem upwards. This is examined to assess the substantia nigra and aqueduct, as well as to note any primary or secondary haemorrhage, the latter often being due to raised intracranial pressure. The cerebellum and pons are then cut down vertically and opened like a book to display the fourth ventricle, dentate nuclei and the interior of the cerebellum. The lower pons and medulla can be further sectioned transversely or longitudinally.

The cerebral hemispheres are then placed base down on the cutting block and serial sections made in the coronal plane from the frontal lobes back to the occiput. The sections should be about 1 cm thick and each should be slid into a sequential place in rows along the cutting board so that orientation is preserved. Cuts should be made with careful but bold sweeps of the knife as erratic sawing motions will leave an irregular surface on each section, which obscures a good view. Cutting a fresh brain is less satisfactory than cutting a firmer fixed brain, especially if there is any post-mortem autolysis or softening as in a dead ischaemic brain after mechanical ventilation.

Ancillary investigations

A wide range of samples may need to be taken either before, during or after the gross examination is completed. The nature of such ancillary investigations naturally depends upon the nature of the death, the history and the interests of the pathologist.

Microbiology

Though more common in clinical autopsies than forensic work, culture samples for ‘bacteriology’, virology and (rarely) fungi may be needed. For post-mortem bacteriological cultures Tsokos and Püschel recommend spleen and heart blood and claim that results from lung culture are often unreliable due to frequently false positive results.[58] They also suggest that collection of specimens from at least two different sampling sites should be the standard procedure in cases where an underlying infection is presumed. Either plain swabs or swabs immersed in a transport medium can be employed for sampling a wide variety of sites at autopsy. Alternatively, tissue samples may be collected in sterile containers and this is the usual method for virological culture of lung and brain, for example. Blood cultures may be desired, and it is best to take blood with a sterile needle and syringe from a large vessel, such as the femoral vein, before starting the autopsy with its attendant inevitably widespread contamination with putrefactive organisms. Alternatively, blood can be taken from a freshly opened heart chamber using sterile instruments. If an infective endocarditis is suspected, it is best to open the heart later with a sterile scalpel and excise the mitral or aortic valve cusps or vegetations for direct culture.

According to a review of published articles on post-mortem bacteriology by Morris *et al.*, there are, in theory, four mechanisms through which bacteria can appear in post-mortem cultures: 1) invasion during life (genuine positive); 2) agonal spread i.e. bacterial invasion during the dying process or during artificial maintenance of circulation and respiration at resuscitation; 3) post-mortem translocation due to migration from the mucosal surface into the blood and body tissues and 4) through contamination where bacteria are introduced into the blood, CSF or tissues during sampling.[59] They conclude that the main post-mortem artefact is contamination, which can be considerably reduced by careful technique; agonal spread is less common than is often assumed and post-mortem translocation is not a problem if the body is appropriately stored. They further consider that a pure growth of a pathogen in blood or CSF should be regarded as a possible contributing factor to death at all ages.

It requires the expertise of an experienced microbiologist to advise on what is significant in the subsequent growth in the laboratory.

Toxicology

This has already been mentioned and is further discussed in the later chapters of this book but, as far as the collection of specimens is concerned, it may be repeated here that sampling is extremely important



REQUEST FOR TOXICOLOGICAL ANALYSIS

Name ________ Age ________

Post Mortem No ________ Date of P.M. ________

Date of Death ________ Pathologist ________

SPECIMENS SUBMITTED: ____ Blood ____ Urine ____ Liver ____

Stomach contents ____ Kidney ____

Intestines ____ Brain ____

OTHER SPECIMENS ________

Any infective conditions suspected ________

ANALYSIS REQUIRED

BACKGROUND INFORMATION:

Figure 1.22 Sample request form for toxicological analysis.

if reliable analytical results are expected. Blood, urine, stomach contents, organs (especially liver), intestinal contents, CSF, bile and ocular fluid may be required.

The containers in which specimens are collected must be chemically clean to a very high standard. They are often supplied by the laboratory that will carry out the analyses.

The pathologist should submit a form with the samples indicating the analyses required, the personal details of the deceased person, a brief history with details of suspected toxic substances and a statement as to whether the subject was known to suffer from any infective condition, including hepatitis or HIV infection (Fig. 1.22).

Histology

As long ago as 1893, Virchow pointed out in his book about dissection technique, with particular relevance to medico-legal practice, that certain pathological changes cannot be recognized by the naked eye, but only with the help of a microscope or a magnifying glass.[60]

It is advisable, whenever possible, to carry out a histological examination on a range of tissues in all autopsies and inevitably in all criminal or litigious cases, to confirm or to exclude the presence of a natural disease. In other situations histology may be able to provide answers in questions concerning the timing, vitality and causes of injuries or identification of the nature of aspirated or ingested material found in the airways or gut. The need to confirm the human origin of isolated tissue fragments may arise, e.g. in mass disasters, although molecular biological methods are necessary to establish the personal identity.

The Council of Europe recommendation on the harmonization of medico-legal autopsy recommend that histology be taken from every autopsy.[15] Similarly, the Royal College of Pathologists (United Kingdom) Guidelines on autopsy practice, September 2002, recommends as best practice the sampling of all major organs for histology in all autopsies.[14]

The Code of practice and performance standards for forensic pathologists by the Home Office Policy Advisory Board for Forensic Pathology and The Royal College of Pathologists,[61] and Code of Practice and Performance Standards for Forensic Pathologists dealing with Suspicious Deaths in Scotland by Scottish Government, Crown Office Procurator Fiscal Service

(COPFS) and The Royal College of Pathologists, recommend that:

> "A histological examination should be made, by the pathologists themselves, of the major organs (assuming that they are not heavily decomposed) in all suspicious deaths. Histology is of value in confirming, evaluating and sometimes revising the course of natural disease processes that may have contributed to the cause of death. Other samples should be taken for histological examination depending on the circumstances of the case, e.g. for the purposes of aging injuries. The reasons behind any decision not to undertake a histological examination must be adequately recorded, in order that the pathologist may be in a position to defend this decision if required.".[62]

This advice should be followed wherever possible, even though in some medico-legal autopsies, the cost of such techniques may provide difficulty if the coroner or other commissioning authority declines to fund the procedure. It is customary to retain samples of brain, heart, lung, liver, kidney, pancreas, spleen, thyroid, adrenal and muscle as a minimum. Even in decomposed bodies histology may sometimes reveal disease processes that without histology would remain undetected. The author (PS) once autopsied a hospital death, where a patient had been taken to the hospital because of back pain and a fall on the stairs, after which he had developed weakness of both legs, progressive paraparesis and associated sensory deficits. The patient died before diagnosis was made and the hospital pathologist refused to perform the autopsy as the cause of death was obscure. Due to further bureaucratic delays, the body was already decomposed when the medico-legal autopsy took place. As the autopsy was completely negative but the clinical symptoms had concentrated in the back, the spinal cord was removed along with other organs for histology. The results of all ancillary investigations, including toxicology, were negative, except for the histology of the spinal cord, that showed an abundant infiltration with inflammatory cells that, in spite of the advanced decomposition, were recognizable as granulocytes suggesting myelitis.

Where there are indications to examine other parts of the body, these are retained in addition to the routine tissues. One should always use sharp instruments for cutting to minimize mechanical damage to the tissues to avoid artifactual changes that may hamper the interpretation of the findings. Sites, where the samples have been taken from, have to be recorded and numbered in the autopsy protocol to enable topographical correlation and comparison with macroscopic findings and possible later review and quality assurance measures. The tissues are either sampled by taking relatively large pieces at autopsy (which are soon thereafter trimmed down to size) or by cutting blocks of a standard size (such as 20 × 12 × 3 mm) at the time of autopsy. The choice of appropriate histological methods is most important for reliable results. For routine histopathology most tissues are fixed using buffered formaldehyde to stop the autolytic processes and degradation by bacteria and to stabilize the proteins. The size and the thickness of the samples must be in compliance with the choice of the fixation and staining methods. The tissue is placed in a large volume of buffered formol–saline and allowed to fix for at least several days before processing. However, if special methods, such as immunohistochemistry, are used, shorter fixation time may be necessary, as too long fixation may destroy the antigenic properties of the tissue resulting in false negative results. The volume of fixative should be six times the total volume of tissue: it is all too common to see a mass of tissue squeezed into a small container, barely covered with formalin, half-fixed and even semi-dried.

Autopsy radiology and post-mortem imaging

An historical introduction

It is astonishing how quickly after the discovery of a new, unknown type of radiation, 'X-rays', in November 1895 by Wilhelm Conrad Roentgen (1845–1923), it was applied to forensic medicine.[63,64] The first record of radiology in medico-legal context dates back to 1895, when, only few weeks after the first radiograph of a human hand, X-rays were used in a clinical forensic case in Montreal, Canada. The experiment was done to locate a bullet in the leg of a gunshot victim. It also became the first X-ray plate to be admitted to a court as evidence in North America.[65,66]

Professor Arthur Schuster at Owens College, Manchester, UK, was one of the two physicists in Great Britain (along with Lord Kelvin), who had received from Roentgen the original monograph and photographs at the turn of the year 1895/96. In April 1896, Schuster was asked to travel to a remote mill town in the north of Lancashire, to locate bullets in the head of a dying woman. She had suffered four shots from a pistol fired at close range by her husband. As Schuster was unwell, he sent his assistants, C. H. Lees and A. Stanton to take the first plates. Schuster developed the plates himself and found three of the missiles in her cranium. A few days later he went himself to take another plate that eventually revealed the fourth bullet. As surgery was not possible and the victim died a week later this became the first recorded use of radiology in a homicide.[63,67,68]

In December 1896, an X-ray plate was admitted as evidence for the first time in the USA in Arapahoe County, Colorado. James Smith had been injured in a fall from a ladder while trimming trees, receiving an injury of the hip. The surgeon, who had been consulted some time after the injury, had made no attempt at immobilization of the thigh but had advised exercise of various kinds, as if treating a contusion, after which Smith had sued him for malpractice. An X-ray of the hip taken about 7 months after the law suit, revealed an impacted fracture of the left femur and was, after initial denial, eventually admitted by the court as evidence.[68]

Radiologic methods were gradually and increasingly applied to various fields of forensic medicine, e.g. in identification by comparison radiography matching of the frontal sinus pattern (see Fig. 3.24),[69–71] the skull (cephalometry)[72] and the dentition,[73–75] as well as in detecting vascular changes by post-mortem angiography.[76–79]

Relatively soon after the introduction of computed tomography (CT) in the early 1970s it was applied to clinical forensic medical purposes in patients with acute gunshot injuries to the head.[80] In the 1990s, the Institute of Forensic Medicine of the University of Bern started a joint research project with the Institutes of Diagnostic Radiology and Neuroradiology of the University of Bern using multislice CT (MSCT) and magnetic resonance imaging (MRI) post-mortem and comparing the results with autopsy findings. At present, only few centres in the world are routinely implementing post-mortem imaging, using mainly CT but also MRI as a screening method, prior to conventional autopsy (Fig. 1.23). One of the latest is the 'Postmortales Imaging Center' of the Zürich University Institute of Forensic Medicine, in Switzerland, inaugurated in November 2010 and comprising an MRI and CT facility in the immediate vicinity of the autopsy room.

The scientific literature in this field is rapidly accumulating and in the course of time will give us a more precise picture about the advantages and flaws of these methods. Because of the high costs of the equipment and the necessary personnel to run these, they will remain out of reach for most forensic departments for the time being.[81–112]



Figure 1.23 Radiography is essential before some autopsies. When available, advanced post-mortem imaging methods, such as CT but also MRI can be used as a screening method. Here a multiplanar reconstruction of humerus detected an abscess in its proximal part (arrow), which was confirmed to contain pus at autopsy. (Reproduced by kind permission of Professor C. Jackowski.)

The details of radiological findings are discussed in each appropriate chapter, particularly in relation to child abuse, gunshot wounds, identification and dentistry.

The quality of radiographic assistance available will vary widely from none to the most sophisticated techniques. The main difference is usually whether the autopsy is carried out in the mortuary of a well-equipped hospital where there is radiographic apparatus, radiographers to use it and radiologists to read the films – or whether the autopsy is performed in some remote public mortuary or in makeshift premises far from clinical facilities.

In many developing countries, radiography may be scarce for living patients let alone corpses, and the same standard of assistance for the pathologist cannot be expected. In larger, more affluent countries, remoteness may be the problem; here mobile equipment is available and sometimes used by forensic pathologists. There are small, portable X-ray kits that can be carried in two suitcases, and can function from an ordinary domestic power supply or from a portable petrol generator. In many instances a mortuary will have a small portable machine, sometimes one discarded from clinical use. This can be wheeled into position when needed, and films and technical assistance obtained from the nearest hospital, which is often adjacent.

For isolated organs and tissues, cabinet-type radiographic equipment is available, which can be used without the assistance of trained radiographers.

Where there is a large forensic institute, then full radiological facilities with the staff and equipment to operate and process plates will be available at all times. Where research projects involving radiology, such as post-mortem coronary angiography, are being carried out, there will usually also be ample facilities for routine use.

The stage at which radiology is employed in an autopsy will vary according to the individual circumstances, but is likely to be after the external examination is complete, but before dissection begins. Straight radiographs for bony injury are not often required, as the skeleton can be inspected directly by dissection in major trauma. The exception is child abuse, where, as fully described in Chapter 22, a full skeletal survey is needed before autopsy. Indeed, many forensic and paediatric pathologists would consider radiology essential in all infants who did not die of some obvious disease.

Suspected air embolism, pneumothorax, barotrauma, gunshot and explosive deaths should have radiological examination before the autopsy, and when a traumatic subarachnoid haemorrhage is suspected, vertebral artery angiography might be necessary, as described in Chapter 5.

Mutilated remains, especially those from mass disasters, may need to be X-rayed, as may victims die from fires where the external damage makes dissection difficult. Where bombs or explosive devices are involved, it is essential to have radiographs to detect any parts of the mechanism that are embedded in the tissues.

Though the radiographs are usually taken before the autopsy begins, some lesions may be better demonstrated on isolated organs or structures. In child abuse, the callus of old fractures of posterior ribs may be better visualized on X-ray if the chest cage is dissected out, and radiographs taken without the soft tissues and the obscuring structures of sternum and anterior ribs. Similarly, a block of upper cervical spine may better reveal fractures of transverse processes carrying the vertebral artery, or a larynx may show fractures of the hyoid or thyroid cornuae more clearly when they are X-rayed outside the body.

Forensic photography

Many forensic pathologists take their own photographs of both scenes of death and of autopsy appearances. Others rely on professional photographers such as the police and hospital medical photographers. The standard of expertise amongst some doctor photographers is excellent, and their pictures grace many lectures and textbooks. It is to the more inexpert camera operators that these few general tips are offered.

Recent advances in electronics have totally revolutionized photography, and have wide application and potential for forensic and autopsy work. Digital cameras of varying grades of sophistication, resolution and cost, can now instantly store images on various data storage devices and the images can then be reviewed immediately on a camera or computer display or printed on an inkjet or colour laser printer. The advantage of instant prints is that a record of the scene of death can be obtained before the autopsy is carried out, and any findings checked back against the original surroundings. For example, if some linear mark is seen on the leg at autopsy, the pathologist can immediately refer to his digital prints to check whether that leg had been resting on some object. Again, where multiple injuries exist, their number, position and size can be checked when writing the autopsy report, without waiting for the police album to arrive. Correlation of wounds with blood splashes may also be useful.

These images can be processed in many ways to enlarge sections or correct colour balance, sent via computer networks to distant locations, or incorporated within textual material and reports. Alternatively, conventional photographs and slides can be scanned within minutes, the optical image being digitized into electronic storage for similar processing.

Various storage media, such as various optical discs (CD, DVD, BD), flash drives, hard drives and solid-state drives offer huge storage and retrieval capacities for record-keeping and educational display purposes. In addition, single frames from video camera recordings can be captured as still pictures and electronically stored.

If conventional photography is preferred, the type of camera most favoured is the 35 mm single-lens reflex, of which there is a vast range available, in all grades of sophistication and price. Some means of exact focusing is essential (either automatic or split-screen, for example) as picture sharpness is of prime importance.

The type of lens is a matter of personal choice, as some will prefer interchangeable lenses of various focal lengths. The standard 50 mm is most useful, but for scenes of crime or taking a full-length shot of a body in cramped conditions, a wide-angle lens of 28 or 30 mm is needed. A longer focal length of up to about 80 mm can be useful for close-up pictures of small lesions, but telephoto lenses of 100–200 mm are not required, though extension tubes, some with lenses, can be obtained for macrophotography.

Many pathologists, including the authors, prefer to combine lenses into a single variable-focus 'zoom' lens of 28–80 mm range. This saves time spent in changing lenses, and the image resolution of good-quality equipment is virtually indistinguishable from fixed focal length lenses.

Illumination is usually by electronic flash now often an integral part of the camera body, and the use of automatic thyristor control means that no complicated calculations about range are needed. For very close-range work, a flash attached to the camera may be unsatisfactory, so an extension cable is a useful and cheap accessory to keep the flashgun at a distance. Alternatively, the flash can be 'bounced' off the ceiling in the autopsy room or a 'ring-flash' around the lens used to avoid camera shadow.

Some will prefer tungsten light rather than flash, though this is more cumbersome unless a fixed station is installed in the autopsy room for taking photographs of organs. It is impracticable to use floodlights at the autopsy table or at a scene.

The type of film depends on the nature of the illumination. Speeds of 100 or 200 ASA are more than adequate for most flash work, though 400 ASA is now frequently used. Some keen medical photographers carry a separate camera body loaded with high-speed 1000 ASA film for special circumstances.

Ultraviolet (UV) and infrared sensitive film has been used to demonstrate surface lesions that are not visible to the human eye. It has been claimed that occult bruising can be revealed by UV photography, such as in child abuse, but care must be taken and experience gained to eliminate artefactual false positives. Alternative light source illumination has been applied to bite mark photography.[113] David and Sobel reported a rape case, where the bite mark had at the time of the crime been photographed without a reference scale, but 5 months later the authors were able to 'recapture' the bite mark pattern with a reference scale by means of reflective ultraviolet photography.[113,114]

In relation to the actual photography, a marked improvement in the pictorial quality can be achieved with a little care in composition. At scenes of death the viewpoint is often limited and the surroundings have to be photographed as they exist, without modification. The camera position can, however, usually be chosen to cut out as much extraneous background as possible. In the autopsy room, considerable improvement can be made by using the optimum viewpoint and by modifying the background. Many photographs are spoiled by having irrelevant and distracting objects in the background such as observers, buckets, boots and the other extraneous paraphernalia of the autopsy room. The picture frame should be filled as completely as possible with the object under display. A close shot should be taken to limit the irrelevant margins though, where necessary, anatomical landmarks should be included to orientate the viewer. The camera should be at right angles to the lesion being photographed, whenever possible. Tangential shots may foreshorten the required feature and, where size needs to be displayed, may distort both shape and length because of the foreshortening. A ruler or special white adhesive tape with centimetre markings should be placed very near the lesion or wound to provide a size reference (Figs 1.10, 1.11).

Where a feature is obscured or insignificant, it may be pointed out by a probe or finger held in the appropriate position. Where part of the picture area consists of the metal or porcelain autopsy table or dissection bench, allowance should be made in exposure, as these very reflective areas may give a false reading in the light meter of the camera and thyristor of the flashgun.

If a full length or half shot of a body is required, an untidy background may be avoided by turning a mobile or rotatable table so that a blank wall forms the backdrop. If this is not possible, assistants can hold up a sheet behind the table to screen the distant confusion.

When photographing viscera, the camera should be near enough for the frame to be almost completely filled by the required object. The shot should be vertical to the lesion and it is often necessary either to place the dissecting board on the floor, or for the photographer to stand on a stool or some elevation to gain the required height.

Where isolated organs are being photographed, they should be placed on a green or blue cloth, such as a discarded operating gown. White can be used, though it may affect the exposure meter if much is visible around the periphery. The organ should be placed on the cloth in one movement and not moved thereafter, otherwise a wet dark stain will obtrude on the green or blue background. The organ should not be oozing blood onto its surface or onto the background. It should be dabbed with a dry cloth or sponge just before the photograph is taken to remove shiny wet highlights.

Ideally a special stage for organs should be used, such as a glass-topped table with a coloured (usually green) background set sufficiently far below the glass to be out of focus. Tungsten lights can be used to advantage on such a fixed stage.

The autopsy report

Equally important as the autopsy itself is the report that the pathologist provides for whoever commissioned the examination. An autopsy is of little value if the findings and opinion of the forensic pathologist are not communicated in the most lucid and helpful way. The report is an integral part of the procedure and should receive as much attention as any physical procedure in the autopsy room. Unfortunately, some pathologists treat the process of making a report in a somewhat cavalier manner, which diminishes the expertise that they may otherwise possess.

The autopsy report is a permanent record of the findings and is especially vital for medico-legal purposes, when every word may be dissected in a court of law months or even years afterwards, and when all recollection of the examination has been driven from the mind of the pathologist by hundreds of subsequent autopsies. In a clinical autopsy in a hospital, the dissection may be demonstrated and discussed at the time with the interested physician. However, the report of a forensic autopsy becomes a legal document of possibly vital significance, and every effort must be made at the time to make it as comprehensive and useful as possible.

The form of the autopsy report

Reports fall into two main types described below, and local practice and indeed legislation may determine which is used, irrespective of the wishes of the pathologist. The choice is, however, often dictated by the nature of the case.

- A free-style 'essay', which usually adheres to a conventional sequence, but leaves the pathologist free to expand on various aspects according to his estimate of their importance. This type is usually used in criminal deaths and cases in which litigation is likely. It has the advantage that any part of the autopsy can be expanded without constraint; also the form of the report can be turned into a legal statement or a deposition for the court with little alteration.
- A printed proforma, in which the various sections of the examination and organ systems are already set out by title, leaving blank spaces for the insertion of the findings. The advantage includes the fact that this 'shopping list' acts as an *aide-mémoire* to those pathologists who do not conduct large numbers of autopsies – and also the non-medical recipient is more able to follow the set pattern of the report. One disadvantage is that the spacing prevents flexibility of description unless the proforma is large, when much of the space may be left blank. Also there is rarely enough space at the end of the form for an expansive discussion and opinion about the preceding factual findings. This type of form is commonly used for non-litigious autopsies – for example, the usual coroner's cases of sudden death and suicide.

Concentrating upon the more serious cases, the report, whatever the format, must contain certain information in some logical order. Consecutive numeration, computer codings and other administrative aspects are naturally conditioned by local practice, but the following matters must be catered for in all autopsy reports, though not necessarily in this sequence:

- Full personal details of the deceased subject, unless unidentified. This includes the name, gender, age, occupation and address.
- The place, date and time of the autopsy.
- The name, qualifications and status of the pathologist.
- Persons present at the examination.
- Usually, the authority commissioning the autopsy.
- A record of who identified the body.
- The name and address of the deceased subject's regular (or last) medical attendant.
- The date and time of death, where known.
- The history and circumstances of the death. The inclusion of this on the actual autopsy protocol may not be permitted in some jurisdictions as it is hearsay evidence, but unless expressly forbidden it should be included, as it remains a record for the pathologist's own files. It also justifies his eventual cause of death in those cases where the morphological findings are scanty or even absent, as his conclusions will

be strongly influenced by his pre-knowledge of the mode of death. When the autopsy report is converted to a statement or deposition for legal use, this history may be omitted by those legal authorities responsible for transcribing the document.

- External examination.
- Internal examination.
- A list of specimens and samples retained for further examination. Those handed to other agencies, such as the forensic science laboratory, should be formally identified by means of serial numbers and the name of the person to whom they were handed.
- The results of further examinations such as histology, microbiology, toxicology and clinical and/or forensic genetics. When the main report is issued soon after the autopsy, these will not yet be available and a supplementary report will be necessary.
- A summary of the lesions displayed by the autopsy (often coded for departmental computer retrieval).
- Discussion of the findings, if necessary in the light of the known history.
- An opinion as to the definite or most likely sequence of events leading to the death.
- A formal cause of death, in the format recommended by the World Health Organization, suitable for the completion of a death certificate.
- The signature of the pathologist.

The ‘external examination’ should record those details described earlier in the chapter, the major items being:

- The height, weight and apparent state of nutrition.
- The presence of natural disease such as oedema, abdominal swelling, cutaneous disease, senile changes, and so on.
- Identifying features such as skin colour, tattoos, scars, congenital or acquired deformities, dentures, eye colour and hair colour. When identity is an issue, naturally this section will be greatly expanded.
- The presence of rigor, hypostasis, decomposition and abnormal skin colouration. Body and ambient temperature should be recorded where appropriate, with calculations concerning the estimated range of times since death, though this aspect may well be deferred until the final ‘Summary and Conclusions’.
- The condition of the eyes, including petechiae, arcus senilis, pupil size and the condition of iris and lens.
- Condition of mouth and lips, including injuries, teeth and presence of foreign material.
- Condition of external genitals and anus.
- Listing and description of all external injuries, recent and old.

The internal examination records all abnormalities, usually in a conventional sequence such as:

- Cardiovascular system: heart weight, any dilatation, ventricular preponderance, congenital defects, the pericardium, epicardium, endocardium, valves, coronary arteries, myocardium, aorta, other great vessels and peripheral vessels.
- Respiratory system: external nares, glottis, larynx, trachea, bronchi, pleural cavities, pleura, lungs (including weight) and pulmonary arteries.
- Gastrointestinal system: mouth, pharynx, oesophagus, peritoneal cavity, omentum, stomach, duodenum, small and large intestine, liver (weight), pancreas, gall bladder and rectum.
- Endocrine system: pituitary, thyroid, thymus and adrenals.
- Reticuloendothelial system: spleen (weight) and lymph nodes.
- Genitourinary system: kidneys (weight), ureters, bladder, prostate, uterus, ovaries and testes.
- Musculoskeletal system: skull, spine, remaining skeleton and musculature where necessary.
- Central nervous system: scalp, skull, meninges, cerebral vessels, brain (weight), middle ears, venous sinuses and spinal cord (when examined).

The timing of the report

As with the format, there are two schools of practice in this respect. One advocates the issue of as full a report as possible on the gross findings as soon as the autopsy is completed, usually within a day or two. Obviously this can only be a preliminary, provisional report, as it may have to be modified (sometimes radically) by the results of ancillary investigations that may take days or weeks to return. Where modern polymerase chain reaction (PCR)-based bacteriological and virological diagnostic methods are not available, virological cultures, for instance, may take up to several weeks before a growth can be reported.

In a large proportion of forensic cases, however, especially those due to violence, the gross findings are unlikely to be substantially amended by ancillary investigations, though the possibility must always be left open until all data have been gathered in.

The other philosophy will delay any report (except perhaps a provisional oral opinion) until everything is to hand, when a single final document is provided.

Whichever course is adopted, one aspect is vital to both. The descriptive facts must be recorded at or immediately after the completion of the autopsy. It is vital that no significant interval – certainly no more than few hours – be allowed between the physical performance of the examination and the setting down of the objective findings. The words 'setting down' are chosen carefully as the report may be handwritten or typed, or may be dictated to a secretary or into a tape recorder or other audio system. What is vital is that it is not consigned to the pathologists' memory for a few days, even reinforced by notes written on scraps of paper.

In Britain and many other jurisdictions, the court may demand to see any contemporaneous notes and even tapes from a tape recorder. Any diagrams, notes or rough drafts must be preserved for production on demand of the judge, coroner or advocates in court. Where the report is dictated (either to a secretary or into a tape recorder), then the first typed (or word-processed) draft constitutes the 'original report', along with any contemporaneous notes including body sketches.

The use of printed body sketches can be a very useful aid in the autopsy room. Many versions exist from the simple front and back views of the whole body used in clinical neurology to multiple sketches portraying every possible view of the body surface. Separate diagrams are available for the male and female perineum, and for the different body proportions of infants. Used on a clipboard these diagrams can be most useful, especially where there are multiple injuries, or large areas of burns or abrasions. Each lesion can be drawn in, with a measurement noted alongside each and distances from anatomical landmarks recorded. The data from the sketches can be transposed to written form at the end of the examination.

Discussion and conclusions in an autopsy report

Some pathologists, usually those not normally concerned with criminal and litigious cases, claim that an autopsy report should be a bare recitation of the physical findings, with no discussion or interpretation of the significance of those findings. In the authors' opinion, this is an abdication of the pathologist's responsibility because, especially in criminal deaths, it is these conclusions that are of most interest and use to the investigating officers, lawyers and courts.

After the detailed description of the external and internal appearances, a short resumé should be offered of the major positive findings and their relationship to the cause of death. In many cases this will be obvious, as in a gunshot wound of the head. Matters such as the probable type of weapon, the range, the direction and the likely rapidity of death, however, should also be discussed.

When the findings are less clear cut, or are multiple, then the alternatives should be discussed, giving a differential diagnosis of the cause of death and detailing the possible sequence of events. If it is possible, a ranking order of probability of the various alternatives can be offered. Time of death and the limitations of accuracy in this particular case should be set out when the issue is relevant to the investigation. What is really required is as full an interpretation as possible, without venturing into the undesirable fields of unwarranted speculation or 'Sherlock Holmes' style of overinterpretation, which was the bane of forensic pathology in former years and is still practised too much even today, to the detriment of the good reputation of the speciality.

Post-mortem artefacts

Forensic pathology can only be learned by experience but no account would be complete without drawing attention to common artefacts found at autopsy, which can mislead the pathologist with insufficient forensic experience and even lead to a miscarriage of justice.

Some of the 'classic' mistakes were described many years ago by Shapiro and Moritz, but each generation of pathologists discovers them anew – or what is worse, fails to discover them.[115,116] Most artefacts are described in the various chapters dealing with specific lesions, but a reminder of some of the most important is given here:

- The pancreas is one of the first organs to undergo autolysis, because of the proteolytic enzymes within it. The autolysed tissue is often haemorrhagic and can easily be mistaken for acute pancreatitis, though histology will rapidly resolve the problem.
- Patches of haemorrhage, sometimes quite large and confluent, can occur in the tissues behind the oesophagus in the neck. These lie on the anterior surface of the cervical vertebrae and are caused by distension and leakage from the venous plexuses that lie in this area. They were described well by Prinsloo and Gordon and are sometimes known by this name.[48] Their importance lies in confusion with deep neck bleeding in strangulation (and sometimes with spurious neck fractures), which is why the skull should be opened before the neck in any suspected strangulation or hanging, to release the pressure in the neck veins before handling the tissues.

- Autolytic rupture of the stomach can occur post-mortem in both child and adult, described by John Hunter in the eighteenth century.[117] This so-called 'gastromalacia' appears as a slimy brownish black disintegration of the fundus with release of the stomach contents into the peritoneal cavity. Sometimes, the left leaf of the diaphragm is also perforated through a ragged fenestration, with escape of gastric contents into the chest.
- Heat fractures of the bones, either skull plates or long bones, may be seen in victims of severe fires, but are not evidence of ante-mortem violence. Also in conflagrations, the 'heat haematoma' within the burned skull can resemble an extradural haemorrhage of ante-mortem origin. The site is often at the vertex or occiput; however, unlike the usual parietal haemorrhage, there is no fracture line crossing the middle meningeal artery, the usual cause of a true extradural bleed. The frothy brown appearance of the false clot, together with heating effects in the adjacent brain, should indicate the true diagnosis. Shrinkage of the dura due to heat may cause it to split, with herniation of the brain tissue into the extradural space. Severe burns of the body surface may lead to heat contractures of the limbs with tears over joints such as the elbow. These must not be confused with ante-mortem lacerations or incised wounds.
- The bloating, discolouration and blistering of a putrefying body must not be misinterpreted as disease on injury. Blisters are quite unlike those of burns and dark blackish areas of discolouration must be distinguished from bruising. The latter can be difficult and incision into the tissues to seek blood in the dermis is advised. Histological sections may help but, where a body is badly decomposed, special stains for blood traces in the histological sections may assist, such as alpha-glycophorin to detect red cell envelopes. However, often it is quite impossible to differentiate the discolouration of decomposition from true bruising.
- Blood or bloody fluid issuing from the mouth may be due to putrefaction, even if the body surface is not overtly decomposed. If the lungs and air passages are discoloured and filled with sanguineous liquid, then this must be taken to be cause of the purging from the mouth and nostrils.
- Dark red discolouration of the posterior part of the myocardium is usually due to post-mortem gravitational hypostasis, not early infarction. Similarly, segmental patches of dark red or purple discolouration of the intestine is hypostasis, not infarction. The latter tends to be a single continuous length, the serosa being dull and the gut wall friable.
- Large petechiae or ecchymoses, sometimes with raised blood blisters, are often seen in the dependent skin of persons who have died a congestive death or where the upper part of the body has been hanging down after death. The usual place where these are seen is over the front of the upper chest and across the back of the shoulders, though in dependent heads the face may be shot with haemorrhages.
- Resuscitation artefacts are of increasing importance to the forensic pathologist and are discussed later.

Exhumation

Exhumation is the retrieval of a previously buried body for post-mortem examination. This is usually followed by a first autopsy or a re-autopsy following new information. The term 'exhumation' is usually applied to the removal of a body buried in a legitimate fashion in a cemetery or graveyard ('inhumation'), rather than the recovery of an uncoffined, clandestinely buried victim of a suspicious death. The latter is really a true 'scene of crime' and the pathologist should treat it as such.

Exhumations are required for one of the following reasons:

- Where all or part of a graveyard has to be moved for some development of the ground. Often no special examination of each body is made unless there is some historical or anthropological interest.
- Where some civil legal matter needs to be investigated, such as personal injuries for insurance or civil litigation for negligence – usually after a road, industrial or other accident.
- Where new information or substantiated allegations arise to suggest that a death was due to criminal action, either from injury or poison.
- In ancient or historical circumstances to investigate either the individual or a series of individuals for academic interest. A number of such investigations have been carried out on medieval and later inhumations in England, to study disease patterns and nutritional states in old populations – though many of these have been from dry vaults, rather than earth burials.

The legal procedures authorizing an exhumation do not concern us here, as they vary greatly from country to country. In all jurisdictions, however, there must be strict safeguards to identify the grave and the



Figure 1.24 Exhumation; the final approach to the coffin. Sometimes a metal cassion has to be used to protect the gravesides from collapsing (not here). The grave must be identified by the cemetery superintendent.

coffin, so that no mistake can be made. The grave must be positively identified by the cemetery authorities by reference to plans and records: an official must personally point out the grave to be opened.

Traditionally, exhumations are carried out at dawn but, except to avoid spectators and publicity, there is no real need to stumble about in a dark cemetery before first light. A better plan is for the grave to be dug down to just above coffin level by a mechanical digger or workmen on the previous day so that, the following morning, the police, coroner, pathologist and others can arrive in time to see the final exposure of the coffin. The coffin nameplate must be cleaned and read to confirm the identity, and, if possible, the funeral director who carried out the original burial should be present to identify the coffin and the plate (Figs 1.24, 1.25).

If there is a suspicion of poisoning, samples of earth should have been taken from the surface of the grave, from other parts of the cemetery and from immediately above the coffin. When the coffin has been removed, further samples should be obtained from the sides and beneath the coffin, but these matters will usually be attended to by forensic scientists.

When the coffin is lifted to the graveside it is as well for the lid to be loosened a little by slackening the holding screws or prising the lid loose. This allows foul gases to escape into the open air, rather than in the mortuary. The coffin is then transported to the mortuary; if it is in a bad state of decay, it may have to be supported on a rigid base such as a trestle, or placed inside an extra large coffin or fibreglass shell. Excess earth and mud should be removed before transportation to avoid excessive fouling of the autopsy room (Fig. 1.26).



Figure 1.25 Exhumation; when the coffin is exposed it must be identified by the funeral director and the coffin plate checked. If death from poisoning is suspected, samples of earth from above, below and the sides of the coffin as well as from a distant part of the cemetery must be taken, together with a sample of any grave water.



Figure 1.26 Following exhumation, the body is transported to a mortuary for full autopsy. The former practice of autopsy in inadequate premises near the cemetery is no longer justified. Here the original rotted coffin is placed within a temporary coffin for transit.

Where criminal action is suspected or has been alleged, a full photographic record must be kept (usually by the police) of every stage from identification of the grave to the findings during the autopsy.

At the mortuary, the coffin lid should be completely removed and the contents again identified, if possible by the funeral director who originally buried the body. He can again confirm the coffin plate, but also identify the internal coffin fittings, such as fabrics and shroud. When the body has not been buried for too long, he may be able to identify the features of the corpse from personal knowledge.



Figure 1.27 When the coffin is first opened in the mortuary, the coffin fitting and fabrics should again be identified by the funeral director, as well as the body and its clothes, if they can be recollected. This infant has been buried for 3 years. The upper part of the coffin has leaked, allowing liquid mud to cover and substantially destroy the head.



Figure 1.28 Exhumation after 9 months due to suspicion of death due to iatrogenic causes.

If poisoning is suspected, samples of the shroud, coffin trimming and any loose material such as packing or fluid should be retained for analysis. The body is then removed, undressed and a full autopsy carried out, as far as the condition of the body allows. Putrefaction, adipocere and mummification complicate the examination – sometimes, all three may be present in the same body.

The pathologist is sometimes asked by the authorities or by lawyers whether a proposed exhumation is worth carrying out, because of doubts about the usefulness of the result. Certainly the balance between the potential advantages must be weighed against the cost, publicity and distress to relatives that might be caused. In general, however, it is surprising how much information may be gained even when the body has been buried for many months or even a few years (Figs 1.27–1.29). Much will depend on the actual environment of the grave: a gravel or sandy soil, especially in an elevated position, will allow a body to remain in a much better state of preservation than one in the waterlogged loam of a valley. The author (BK) has seen burials only 20 years old with empty coffins containing silt, but no soft tissue or even bones (due to a constantly rising and falling water table) in an area of acidic peat.



Figure 1.29 An early pregnancy found incidentally in a decomposed body, confirming the value of autopsy on even the most unpromising material.

Even negative information gained at exhumation, such as the absence of alleged or suspected fractures, may be of considerable legal value. Some poisons, especially heavy metals, may persist for many years in a buried body and be detectable at exhumation.[118] Even many organic chemicals may survive for a long time.[119–124] In all cases of suspected poisoning, it is vital that ample control samples are taken from the grave and its surroundings, to avoid the later accusation that any abnormal substances found were environmental artefacts or were unassociated with the corpse.

The autopsy on the putrefied corpse

In forensic work, decomposed bodies are commonplace, especially in warm climates. Though the value of an autopsy is progressively reduced as the state of putrefaction advances, no short cuts should be taken by the pathologist merely because of the unpleasant nature of the examination. However bad the condition of the corpse, every effort should be made to carry out the autopsy as near to the usual routine as possible. It is often surprising – as with an exhumation – how much information can be gained. The interior of the body is often far better preserved than the outward appearances would suggest, so a policy of defeatism that leads to a skimped examination should never be adopted.

Externally, putrefaction hides bruising to a variable degree, the greenish black colouration of the skin masking the usual features of contusion. Abrasions, lacerations, incised wounds and gunshot wounds may, however, survive severe degrees of decomposition. Loss of bloody fluid from the mouth and nostrils (the so-called 'purging') is often mistaken by the public, police and even some doctors as evidence of haemorrhage, but loss of serous, bloody or frothy fluid from any body orifice is common in the advanced stages of putrefaction (see Fig. 2.12).

Peeling and slippage of skin may hide some abrasions, though they may be visible when the desquamated epidermis is removed and the underlying skin examined. Marks around the neck from the tissues swelling with gas and becoming embedded in a collar have been mistaken for strangulation.

Where maggot or other insect infestation is present, some may be taken for expert entomological examination to help in assessing the post-mortem interval, as described in Chapter 2 (Figs 2.14–2.16, 2.27–2.29). As stated above, the external examination should be conducted as near as possible to the routine for a fresh body, and the back and perineum not neglected because of physical difficulties in handling the body.

Identity may be a problem when the facial features are too bloated for visual recognition. The usual procedures described in the next chapter may be employed where necessary. Fingerprints may be required by the police to assist in identity, but decomposition may seriously destroy the fingertips. These may become swollen and desquamate, or may shrivel and become leathery. Several methods of restoring the amputated tips have been described: some recommend a simple method of immersing the tips in 20 per cent acetic acid for 28–48 hours, when the shrivelling will swell to normal size. Others recommend immersion in glycerine.

Internally, much will depend on the state of decay. The abdominal and chest organs may be in a better state of preservation than the exterior. The subcutaneous tissues may be distended and crepitant with gas, as may be the swollen abdomen. Judicious penetration of the peritoneum with the tip of knife may be needed to release the pressure of gas. The technique of lighting the escaping methane with a burning newspaper may be spectacular and sometimes near explosive, but does little to reduce the smell and is not to be recommended.

Examination of the organs follows the usual pattern, modified according to state of putrefaction. The heart may be limp and discoloured, with haemolysis staining of the endocardium and vessels. The coronary arteries are often very well preserved, especially if atheromatous or calcified, or both. Ante-mortem thrombi may persist even after the muscle is semiglutinous. The larynx may be discoloured, but the hyoid and thyroid horns can be examined for fractures and may need to be X-rayed. It may be difficult to detect ante-mortem bleeding at the fracture sites. Fractures elsewhere in the skeleton naturally persist and may require radiography for their detection, as may foreign objects such as bullets.

The brain often decomposes early, and all too often is merely a pinkish-grey paste within the dura. Gross lesions like a large meningeal or intracranial haemorrhage may survive for examination, but the trauma of removing the calvarium and attached dura may seriously damage a semifluid brain.

In Belgium, a technique was developed in the University of Gent whereby the head of a decomposed body was removed from the body and deep frozen until solid. The head was then cut across in the coronal plane with a band-saw, leaving the brain in two halves within the cranium. These were then immersed in a large volume of formalin until fixed, when they could be removed in a relatively solid state for examination.

Internally, the detection of true subcutaneous bruising may be very difficult due to the discolouration of putrefaction. Histology is often highly unsatisfactory because of cellular lysis and degeneration; stains for haemoglobin may help in revealing focal collections of lysed blood, but are often diffusely positive even in control areas. Claims have been made for staining for glycophorin A to detect red cell envelopes, as opposed to diffuse haemolysis.[125]

Resuscitation artefacts at autopsy

In recent years, the advent of effective, but often aggressive and invasive, resuscitation procedures has made the task of the pathologist more difficult. At autopsy, injuries and abnormalities are now often found that could be due to terminal and even post-mortem resuscitatory measures. Where the pathologist is made aware of these, he can often exclude the damage being due to non-resuscitatory injury, though even when he is informed of the procedures they can still mask or mimic more sinister trauma. When he is not made aware – or such information cannot be made available – then the difficulties of interpretation are compounded.

There are now many publications describing resuscitation artefacts.[48,126–129] The following are the main categories of damage, for which the pathologist must always be alert:

- Bruising of the anterior chest wall, haemorrhage into the subcutaneous tissues and pectoral muscles, fractures of the sternum, fractures of the ribs, haemothorax, bruised lung, lacerated lung, pericardial haemorrhage, and even fractured dorsal spine, following energetic external cardiopulmonary resuscitation (CPR). Thoracic cage fractures are rare in children, however, because of the pliability of the ribs and costal cartilages, but it cannot be denied that they sometimes occur. The differentiation is naturally of vital interest where child abuse is being alleged.

  Internally all types of damage to the heart may occur, including ruptured atria and even ventricles, septal rupture and valve damage. The great vessels can suffer severe trauma, as described in the now extensive publications on resuscitation artefacts. Fat and bone marrow emboli in the pulmonary vessels have also been reported after cardiac massage.[128] Petechiae in the eyes and intraocular haemorrhages can occur after CPR, as well as after violent sneezing or coughing; they are well known to occur during whooping cough.
- Bruising of the face and neck, finger marks and nail marks on the face and neck, and damage to the lips and inner gums from mouth-to-mouth resuscitation, when the face and neck have been gripped by hands. Damage to lips, gums, teeth and pharynx can occur from the introduction of an artificial airway or endotracheal tube, especially in difficult, hurried emergency situations.

  Injuries to the larynx, even including fracture of the hyoid and thyroid cornuae, can occasionally occur from these procedures, which are difficult to distinguish from manual strangulation if the circumstances are obscure.
- Puncture marks for venepuncture may be confused with injection marks in drug dependence. The introduction of intravenous cannulae into veins in the neck may cause large haematomata and more diffuse bleeding into the tissues alongside the larynx. Similar bruising may occur around puncture sites in the arms and groin. Intracardiac injections leave marks on the chest wall and may lead to a slight haemopericardium. The effects of injected noradrenaline and electrical defibrillation on the histological appearance of the myocardium are well recorded, with contraction bands being the most obvious artefacts, which can be mistaken for pre-existing myocardial ischaemia.
- Damage to the mouth, palate, pharynx and larynx can occur from attempts to introduce a laryngoscope or airway. Even fracture of the mandible has been caused in this way. In infants, even digital clearance of the pharynx can cause mucosal damage. Damage to the pharyngeal mucosa may cause bleeding, which can seem sinister to police or relatives; this may be mixed with the fluid of pulmonary oedema to produce copious pink, bloody froth, seen in a number of cases, including SIDS.
- Electric defibrillator pads make marks on the chest, though these are usually easy to interpret, except where there is an unusual shape. Defibrillators and injected β-adrenergic catecholamines such as noradrenaline can, however, cause widespread histological damage to the myocardium, consisting of coagulation necrosis and contraction bands, which can be confused with infarction or electrocution. When both defibrillation and catecholamines have been used to resuscitate, the myocardial changes are even more marked.[126]
- During the Heimlich manoeuvre to clear an airway obstruction, rupture of the oesophagus, stomach and intestines have been reported.[130–132] The oesophagus can be perforated by an incorrectly inserted airway. In the abdomen, external cardiac massage may cause ruptured stomach, ruptured liver, and damage to spleen and pancreas.
- Gastric contents in the air passages may have reached there by spontaneous agonal regurgitation or by pumping the chest and upper abdomen during resuscitation attempts. This makes the finding of vomit in the larynx and trachea of even less significance as a cause of death, as discussed in Chapter 14.
- The administration of oxygen by mask or tube may cause damage, as can overenergetic mouth-to-mouth resuscitation. Ruptures of oesophagus and lung have occurred, and other types of barotrauma include ruptured stomach and intestine. Where a pre-existing gut lesion exists, the administered gas may escape into the abdomen. The diagnosis of a pre-existing pneumothorax may be impossible where forced ventilation has been administered.

- In the central nervous system, subarachnoid haemorrhage has been described after external cardiac massage, and from hyperextension of the neck to pass an airway or perform mouth-to-mouth resuscitation. The forced posture can tear the vertebral arteries, making another source of confusion for the forensic pathologist in this difficult area of potential trauma to the neck (Chapter 5).
- Myocardial and pulmonary bone marrow embolism has been reported following cardiac massage.[133]
- Retinal haemorrhages, classically a sign of raised intracranial pressure and of head injury, have also been described in whooping cough and after CPR.
- Miscellaneous artefacts of which every pathologist should be aware include: skin maceration from a body lying in urine, kerosene, and so on; post-mortem burns from adjacent radiant heat or hot-water bottles; and petechiae and larger haemorrhages in the face from postural hypostasis.

Mass disasters – the role of the pathologist

With the exception of the more dramatic murders, the activity which focuses most public attention on the work of forensic pathologists is the mass disaster. Unfortunately, such tragedies are becoming more common with the increase in terrorism, the expansion of travel facilities and the larger size of passenger aircraft. There has been a tragically frequent need for the expertise of mass disaster teams, following such events as the Zeebrugge and Estonian ferry capsizes, football tragedies like Ibrox Park, Heysel, Moscow and Hillsborough, crush tragedies at Mecca, and numerous massive aircraft crashes, such as Tenerife, Air India, Japan, Lockerbie, and the 9/11 terror attacks in the USA in 2001, recent major natural disasters such as the 2004 Indian Ocean earthquake and Tsunami as well as the 2010 Haiti earthquake, both of which with an estimated death toll of over 220,000.[134,135] Mass disaster management is a discipline in itself and only the briefest summary can be offered here, together with useful references at the end of the section (Figs 1.30–1.32).

Forward planning

Many pathologists will thankfully spend their entire careers without having to participate in a major mass disaster; a commonly accepted definition is the death of more than 12 victims in a single event. No one can predict when such a tragedy might occur, however, as typified by the 1988 Pan Am sabotage, when almost 300 bodies fell out of the sky on a quiet and unsuspecting Scottish village.[136–138] It is thus essential that every forensic institute, department and individual pathologist should make some forward provision for such an eventuality. In Britain, the Royal College of Pathologists have published a useful booklet on the role of the pathologist in these disasters.[139]

In most advanced countries each region now has a Mass Casualty Plan covering medical and hospital services, fire service and police. This is often very detailed, covering every aspect of transfusion, drugs, casualty transport, emergency surgery and anaesthesia. The plans are clinically orientated, but often completely ignore provision for the dead – or they have some cursory statement at the end such as ‘Mortuary accommodation will be provided’ with obviously no thought given to how several hundred corpses are to be accommodated and examined. Though clinical planning is, of course, vital – especially in rail disasters, multiple motorway crashes and urban bomb outrages – it has to be appreciated that, in many air crashes, there are few if any survivors, and that all the clinical planning may be redundant, leaving a massive and unprepared crisis in relation to the dead.

It is therefore essential that forensic pathologists should ensure that, in the area for which they are responsible, there is cooperative pre-planning that includes adequate provision for collection, accommodation, examination and disposal of large numbers of dead victims. Naturally the pathologist is usually in no position to do this alone, but he is often the person with the most foresight and professional knowledge to act as the stimulus and catalyst between the major agencies responsible for overall planning. These are usually the police and the local health administration. When a Mass Casualty Plan does exist, but has serious omissions in respect of dealing with the dead, or where no such plan exists, the forensic pathologist should energetically stimulate the responsible authorities into making a comprehensive plan. This entails a series of meetings to identify danger areas in the region (such as airports, motorways, railways and military installations), and to discuss potential buildings for temporary mortuaries, the provision of materials such as markers, plastic bags and labels, which may be needed in large quantities at a few hours’ notice. Communications between such groups as police, pathologists, mortuary and laboratory technicians, radiographers and dentists also need to be established in advance. The expertise of international funeral directors with experience in mass disaster fatalities is invaluable.

The objects of pathological investigation in mass disasters are:

- To retrieve and reconstruct bodies and fragmented bodies decently.
- To establish personal identity.
- To conduct autopsies on some or all of those bodies.
- To establish the cause of death in some or all, especially aircrew and drivers, and to assist in reconstructing the cause of the disaster.
- To obtain material for toxicological analysis (especially alcohol and carbon monoxide) where appropriate.
- To seek evidence of the cause of the disaster from autopsy examination, such as bomb or detonator fragments that may be embedded in the bodies.

Outline of necessities in mass disaster planning

Provision of pathologists and other staff

Depending upon the scale of the tragedy, it may be necessary to recruit other pathologists to assist. In large cities, there may be sufficient persons with expert forensic knowledge, but elsewhere, hospital pathologists may be able to assist; forensic pathologists from a distance may also volunteer. It has to be remembered that a really large disaster may need many days, weeks or even months of work, and therefore personnel may be unavailable for the whole period. In addition, whatever the degree of willingness and unselfish devotion offered by doctors and all other staff, the physical and especially psychological stresses of this harrowing work mean that strictly limited periods of work should be imposed. Apart from the deleterious effect upon the doctor, the standard of work declines dramatically with fatigue and therefore it is in the interests of the investigation – as well as of the pathologists – that sufficient staff be recruited. This may, however, be easier said than done. One person must be in overall charge of the investigation. Usually a senior police officer has the ultimate responsibility, but the medical aspects should be firmly under the control of a senior pathologist, though he must delegate extensively to avoid being swamped by less important tasks and thereby being rendered totally inefficient. Again, all these aspects are modified by the scale of the disaster. Proper facilities for meals, rest and washing must be established, and again forward planning is essential for these mundane, but vital, features. Forensic dental and radiological expertise will be run independently by their own specialists, but there must still be a nominal chief in the form of the senior pathologist who acts as overall co-ordinator and arbiter of medical matters.

When a disaster, almost always an aircraft crash, occurs in some remote place or abroad where there are no satisfactory forensic or pathological services, it is the usual practice for a team from the country of origin of the aircraft – or a volunteer team arranged at governmental level – to fly to the scene and provide expertise to the local authorities. In many advanced countries, especially Britain, the armed services have permanent aviation pathologists who deal with all service aircraft crashes anywhere in the world and who are often available to deal with, or attend as advisers, any civil air disaster.

Provision of mortuary facilities

Most hospital mortuaries and even larger public mortuaries have limited storage capacity for bodies, and even smaller provision for performing simultaneous autopsies. It must also be appreciated that the normal business of a mortuary has to continue even through a mass disaster, so the massive increase in work is an addition to, not a substitution for, the normal handling facilities. Where more than about 10 bodies are involved, most mortuaries cannot cope with these problems, especially when it has to be remembered that some of the corpses may have to be retained for considerably longer periods than usual if identification cannot be made rapidly. Thus external facilities will have to be provided in some temporary accommodation. When the disaster is a long distance from the regular mortuary, transport and other logistic considerations may make it imperative to store and examine the bodies nearer to the crash site. Again forward planning is essential to identify hangars, storehouses, empty factories, halls and other buildings near potential danger spots such as airports. Whenever possible, all bodies should be taken to one site, as the separation of identification sites is a recipe for inconvenience, delay and mistakes. It is sometimes necessary, especially in remote regions, to set up tented mortuaries, but this is a last resort as facilities cannot be laid on with the same degree of efficiency. Where the crash is totally remote, it is usual for the authorities or the armed services to bring out the dead by helicopter or other transport to an urban site. A prime example was the Mount Erebus crash in Antarctica, where the dead were flown back to New Zealand.

If a warehouse, or factory or building of similar size, can be used, certain minimum facilities are needed. Good electric lighting, portable lights for close inspection, and power points for radiographic equipment and electric instruments are required. Adequate piped water, and washing and toilet facilities are essential. If any of these is deficient, then portable generators and water tankers must be supplied by the armed services or the police. Telephone and, if possible, internet and fax facilities should be available for the input of identifying data.

In hot climates, or in the summer in temperate climates, body refrigeration is vital, not only for the decent preservation of the dead but for retention of tissues awaiting identification. If a disaster is too large to be handled in the usual mortuary, then some form of cooling is required. The renting of refrigerated trucks used for the transport of foodstuffs is the usual answer and, again, pre-planning is necessary to discover sources of such facilities. Sometimes portable air-conditioning units can be installed in part of the mortuary, if this is sufficient to cool the storage area to an acceptable level. In disasters where there are both living and dead victims, the mortuary should be sited away from the clinical facilities or screened in some way to avoid the distressing sight of bodies arriving being visible to survivors or their relatives, and the press.

The temporary mortuary should be large enough for the expected load, and the area to be used for examinations and autopsies should not be too congested. No one should be allowed in who does not have direct business there, no matter of what eminence or rank. Security of admission should be tight, this being the responsibility of the police. Flooring should be waterproof and capable of being hosed down. It can be protected against blood, mud and burned fragments by covering with polythene from large rolls. Tables for examination can be wooden trestles, covered with polythene. These should be in rows 1 metre apart, with 2 metres between rows.

Retrieval of bodies

This is the task of the police or armed services, but must be carried out in a manner approved by the forensic identifying team. It is essential that every body is first certified as dead by a doctor at the scene. Often, volunteer casualty surgeons may be the first medical persons at the scene, whose primary duty is to rescue living survivors and to confirm death in the remainder.

Each body or fragment should be flagged with a sequential and unrepeatable serial number and marked on a grid plan, being photographed *in situ* wherever possible. It is then bagged and taken with its numbered label to the mortuary. Different teams will have different methods of dealing with the logistics of handling data and, increasingly, this is being performed on either microcomputers or on terminals linked to a central computer. The police have responsibility for these aspects, as they collect and record the clothing and personal belongings that play such an important part in personal identification.



Figure 1.30 Temporary coffins used to transport victims of the m/s Estonia disaster from the archipelago to the autopsy facility. (Reproduced by kind permission of the National Bureau of Investigation [NBI], Finland.)

Either the same serial number is used from the recovery stage or a different ‘pathology’ number is begun in the mortuary, which must be matched up with the previous serial number. Everything that has come from that body, including clothing, wallets, rings, teeth and jewellery, must carry the same number.

The pathologist and lay assistants undress the clothed bodies, and dictate a description of what is found as accompanying artefacts. The clothes are stored in strong paper bags to avoid the fungal growth that inevitably appears on damp fabric kept in plastic bags.

Many items will have been found loose at the site, but they must all be tagged and an attempt made to relate them to a nearby body, though this is obviously fraught with error. The objects found on a body are recorded on an inventory form and a separate form (usually the Interpol document) used for the purely medical and anatopathological aspects. The latter data are acquired by meticulous and systematic external examination, followed by an internal autopsy if this is to be carried out.

Whether or not an autopsy is to be performed on some or all of the victims will depend upon facilities, availability of pathologists, the legal direction and the system prevailing in the particular country. The wishes of the legal authority, such as coroner, judge,



Figure 1.31 Particular problems are associated with mass disasters in warm climates as the time frame for visual identification is very short due to rapidly advancing decomposition. This scene is from the Indian Ocean Tsunami disaster in December 2004. (Reproduced by kind permission of the National Bureau of Investigation [NBI], Finland.)



Figure 1.32 The enormous magnitude of the Indian Ocean Tsunami disaster, huge number of victims, and lack of refrigerated storage facilities, led to an unorthodox attempt to cool down the bodies using large blocks of dry ice. (Reproduced by kind permission of the National Bureau of Investigation [NBI], Finland.)

medical examiner or police, will be the deciding factor in determining how many victims are subjected to autopsy. The pathologist should exert his influence where there is reluctance to sanction any autopsies, emphasizing the benefit to the crash investigators of autopsy data on key victims.

As mentioned, the aircrew or other persons in charge of a vehicle or train should always have a full examination and analysis of body fluids as part of the accident investigation. Full photography of the clothing and bodies should be taken, and then all physical features such as height, weight, gender, race, colouring, scars, tattoos and deformities must be recorded. The forensic dental examination is then carried out on those bodies where obvious identity cannot be established by non-medical or dental means.

Radiological examination will almost always be required to assist in identification from osteological features and dental aspects – and perhaps also to seek foreign bodies that may assist in accident reconstruction, such as metal fragments blown upwards into the thighs and buttock in a hold explosion in an aircraft bomb – or even parts of the bomb or detonator itself, more especially in land-based terrorist attacks.

Toxicology should be taken as extensively as possible, even from some of those bodies that are not to have an autopsy. The data acquired from this painstaking work is then forwarded to the police bureau who have been collecting personal data from the records and relatives of the victims, and efforts are made to match the two sets of data. This is increasingly being performed by computer, and many efforts have been made by international agencies such as Interpol to set up universally compatible systems so that data can be acquired and exchanged electronically via telephone systems and modems from any part of the world.

The obscure autopsy

Several surveys in various countries have shown that where a physician offers a cause of death without the benefit of autopsy findings, the error rate is of the order of 25–50 per cent, even in deaths in hospital. Thus the value of an autopsy in improving the value of death certificates is undoubted, but it still has to be conceded that the autopsy is by no means infallible in revealing the true cause of death. Estimates of the frequency with which autopsies fail to deliver an adequate or even any cause of death vary from pathologist to pathologist, as well as with definitions of what type of case a is included in such series. For example, SIDS could be considered to provide ‘negative autopsies’, in that by definition, no significant findings are discovered.

Even excluding SIDS, there is probably at least a 5 per cent ‘failure rate’ in autopsy series from large medical centres and forensic pathology departments. This rate will also vary according to the habits, personality and seniority of the pathologists involved. Contrary to what might be expected, a higher rate of negative conclusions will originate from older and more experienced pathologists than from juniors. The younger pathologist is often uneasy about failing to provide a cause of death, feeling that it reflects upon his ability, whereas the more grizzled doctor, enjoying the security of tenure and equality with – or even seniority over – his clinical and legal colleagues, is less inhibited in his admissions of ignorance when the cause of death remains obscure.

These 'obscure autopsies' are more common in the younger age group. Even apart from SIDS, many autopsies on infants, especially neonates, are less than satisfactory in terms of definite morphological lesions discoverable in the autopsy room or the laboratory. The deaths often have a biochemical or hypoxic basis and, though inferences can be made from the clinical history, even expert paediatric pathologists have to make do with minimal or even absent findings in a significant proportion of cases. In teenagers and young adults, up to the age of about 35 years, there is a higher proportion of negative autopsies than in the older group, which provides the vast majority of the autopsy workload. An example is the obscure syndrome seen in East Asia, where Thai construction workers in Singapore suddenly die with no demonstrable pathological cause. Similar cases occur in China, Japan and Hong Kong; known as 'Pokkuri death syndrome' (PDS) in Japan, 'Lai Tai' in Thailand, 'Bangungut' in the Philippines, 'Dream disease' in Hawaii and 'Sudden unexpected nocturnal death syndrome' among South Asian immigrants in the USA.[140]

This preponderance in the young may carry an inherent fallacy, even though there may be an absolute increase in the incidence of obscure fatal causes. The young adult does not have the almost universal overlay of degenerative cardiovascular disease that is seen in the older group. Thus it is probable that the same occult disease processes occur in that older group as in the young, but as the latter do not have other lesions that can be grasped (usually quite legitimately) as a valid cause of death, then nothing presents itself to the pathologist. For example, on one autopsy table might be the body of a male of 22 who dropped dead shortly after taking part in a football match. There may be no adverse medical history, the gross examination revealed nothing abnormal and subsequently full histology with special stains, full toxicological screening, and microbiological and virological studies, were unrewarding. No cause of death can be extracted from these negative findings and the case must be recorded as 'unascertained' – or, as Professor Alan Usher of Sheffield once pointed out, as 'unascertainable', if the pathologist is feeling particularly omnipotent!

On the next table in the autopsy room, however, may be a male of 60 who has been found dead with no available history. On examination he is found to have 60 per cent stenosis of the anterior descending branch of his left coronary artery, but no recent or old damage to the myocardium. Histology may well be performed, with no further information obtained. The cause of death is likely to be recorded as 'coronary artery disease' by most pathologists, yet he might well have died from the same obscure cause as the young male, but because he has just sufficient arterial degenerative disease to prove fatal, the latter is accepted as the most likely cause of death. This feeling of disillusion may be reinforced by the presence on the third autopsy table of another male of 60 who has been killed by a firearm, yet who has 80 per cent stenosis of all three coronary vessels, this obviously having played no part in the death.

Whatever the philosophical aspects of this problem, the practical difficulty remains of the pathologist's course of action when faced with negative findings in an autopsy.

At the end of the gross examination in the autopsy room, as the depressing realization increases that nothing significant has been found, further action will depend partly upon the facilities available to the pathologist, especially in relation to toxicological, biochemical, microbiological, virological and histological laboratory service.

Before proceeding further to review the dissection, attention must be paid to obtaining adequate samples for ancillary investigations. In many cases, especially where the history alerts the experienced pathologist that this might be a difficult case – and usually always in young people – samples of blood, urine and stomach contents will have been taken as routine during the removal and first dissection of the viscera.

If a blood sample has not already been taken, it should now be obtained, preferably from a peripheral vein such as the axillary or femoral to avoid contamination from the now empty trunk cavities. If urine was not retained from the bladder, a few drops may still be found in that opened organ by suction with a syringe. Stomach contents may well have been lost, but the liver can be retained for toxicological analysis. It might be useful to take vitreous humour if urine and stomach contents have been lost.

Some blood may be used for inoculation of blood culture bottles and swabs can still be taken for microbiological investigations. If a lung infection is possible, then either a few grams of lung tissue can be removed into a sterile jar, or swabs can be taken from peripheral bronchi or from the lung parenchyma itself. As the surface of all cut organs will have been contaminated during the first dissection, cuts should be made into the surface of the lung using a new sterile scalpel so that relatively fresh tissue is obtained for culture. At the same time, a cube of lung – or other organ if desired – should be taken into a sterile container for virus studies.

Before tissue for histology is taken, a full review of the more vital parts of the dissection should be reviewed. Even in younger victims the first area to be studied again is the coronary system, and in older obscure deaths it is essential to re-examine these vessels. Although the coronaries should have been transected at short intervals (not more than 3 mm apart) on the first examination, it is prudent to retrace each vessel carefully from the aortic origin distally, looking again at each cut segment and, where the interval appears too large, to make further intermediate cuts. In addition, it may be wise to join the segments longitudinally between cuts, in case a small isolated thrombus is lurking in the lumen. This should be done for common left trunk, anterior descending branch, left circumflex and right coronary artery.

This review of the coronary system sometimes pays dividends, especially in the middle-aged group that at first sight appears to have good coronary vessels. A tiny segment may be occluded or severely stenosed over a distance of only 2 or 3 mm, either by pure atheroma or by a subintimal haemorrhage, ruptured plaque or a localized thrombosis. If nothing is found, then after a quick review of the valves and great vessels, the myocardium can be sliced more extensively and a number of representative blocks taken for histology, to seek a myocarditis or some obscure cardiomyopathy.

The other organs should be examined again, the pulmonary arteries being scrutinized for pulmonary emboli in the smaller branches. This is rarely productive, but the author (BK) has on several occasions found multiple small emboli in more peripheral lung vessels, although whether these were a valid cause of death was debatable. The brain should be looked at once more, with special attention being paid to the basal arteries. These should be opened with coronary scissors and the dissection carried up into the middle cerebral arteries where they lie in the Sylvian fissures. It is also always worthwhile looking in the carotid arteries in the neck, though these should always be opened routinely at the first dissection from the aorta to a point just distal to the carotid sinuses; even the difficult area above this at the base of the skull has provided some surprises in the past. It is a place rarely examined, except by neuropathologists, but forensic pathologists should add it to their 'repertoire', as occasionally total thrombotic occlusion may be found, especially following some undisclosed neck injury.

When a complete review of the gross pathology has proved fruitless, then a full histological survey is required, especially of the myocardium. Special stains such as phosphotungstic acid-haematoxylin, dehydrogenase enzyme histochemistry (which requires unfixed, frozen sections), acridine-orange fluorescence stains and any other technique that the pathologist favours. Admittedly, where no cardiomegaly or coronary artery stenosis is present, the chances of finding an abnormality are slight, but an isolated myocarditis is an outside chance.

Toxicology may be difficult and expensive if there is no cause to suspect any particular drug or poison. A screen for unknown substances can be time consuming for the laboratory, which means a large expense to public funds. An alcohol estimation and a screen for acidic and basic substances, however, though not comprehensive, can at least exclude most common poisons. Microbiology and virology rarely point to a previously unsuspected fatal disease process unless the patient had clinical signs and symptoms before death.

When all the results are available, which may take several weeks, the case must be reviewed and an honest opinion offered as to whether any positive findings are sufficient to have caused death. In the experience of the authors, these ancillary investigations more often provide no help, than the times when they offer some assistance, but they must be carried out whenever possible in order to exclude such causes and to prevent allegations that the death was not investigated as fully as it should have been.

If at the end of the process no cause of death is apparent, then the appropriate investigating authority must be informed that no opinion can be offered in the present state of medical and scientific knowledge. It can be added, however, that the absence of injuries, evidence of poisoning, lethal infection or well-recognized natural disease is in itself significant negative evidence in that it confirms what the deceased did not die of, and the assumption is then that the balance of probabilities is that it was natural causes, rather than some unnatural external event.

There must be complete honesty on the part of the pathologist and a readiness to admit that the cause of death cannot be determined. The use of some meaningless euphemism such as 'heart failure' or 'cardiorespiratory arrest' is pointless and merely confuses the issue for non-medical persons such as police or magistrates. As mentioned above, there is a tendency on the part of some younger pathologists or histopathologists who rarely become involved in medico-legal cases to assume some unwarranted disease process or to attribute significance to insignificant findings. A **mode** of death is useless in lieu of a **cause** of death, so is the dangerous practice of using some agonal event such as 'inhalation of vomit' where there is no eyewitness confirmation of such an event taking place during life. It is also useless and positively dangerous to guess at some totally unprovable process, such as 'vagal inhibition', 'reflex cardiac arrest' or 'suffocation', just because these conditions – though valid in association with the right circumstances, as discussed elsewhere in this book (Chapters 14 and 15) – are thought to leave no traces and therefore a death with no traces must be due to such a cause. This is illogical thinking and has led to several miscarriages of justice in the past, as well as to far more family anguish.

As the pathologist increases in experience and maturity, he or she is more ready to concede that he cannot find a cause of death, and this is far more satisfactory. In forensic work, this is not 'abrogating responsibilities' but being objective, sensible and just. There is no point in producing a speculative cause of death if that cannot be substantiated in later court evidence or legal statements. It is, of course, quite justifiable and indeed, part of the pathologist's responsibilities, to discuss the range of possible causes with the authorities responsible for investigating the death, but to be dogmatic about a single cause where the grounds for such a decision are tenuous does not help anyone and can lead to unfortunate consequences.

The principle, 'whatever can possibly go wrong will', is probably well known to everyone from the daily life. It became generally known as Murphy's Law in 1949.[141]

When human errors accumulate in the spirit of Murphy's Law and interfere with the medico-legal cause of death investigation, it can have disastrous consequences as illustrated by a case experienced by the author (PS): a 46-year-old waitress was found dead in her bed in a normal sleeping position by her brother and her ex-husband and, for reasons unknown to us, the death was reported to the police as murder. The detectives who went to investigate the scene of crime did not find anything suspicious, but due to the sudden and unexpected nature of the death, a medico-legal autopsy was ordered. Murphy's law would have it that the post-mortem was first performed 1 week later. At the external examination, the classical signs of strangulation were quite obvious and the police were again notified and came to photograph the findings before the autopsy was begun. The following day the police photographer reported that there had been no film in the camera. A week later, the technician at the histology laboratory called having noticed that all the histology samples had been destroyed by decomposition. The substitute for the regular mortuary technician, who had been sick on the day of the post-mortem, had erroneously filled the containers with distilled water instead of formalin.

The boyfriend of the victim as well as her son, both of who had spent the previous evening together with her, were arrested but the boyfriend was soon released because he had an alibi. The son of the victim was kept the maximum time in detention but the police was not able to get any information from him.

Due to the multiple failures during the investigation, the unknown circumstances of death and a possible competitive cause of death found at the autopsy (evidence of heart disease and blood alcohol level of 1.7 U/ml) the case at first remained obscure.

One year later, another victim was found strangled and the perpetrator was caught immediately after the crime had been detected. When interrogated, he confessed having also strangled his mother the year before.[142] Although it is quite evident that the occurrence of such extreme cases can be minimized by painstaking methods of work, it is probable, that, like printer's error, they will obey Murphy's Law and remain imperishable.

References

1 Saukko P, Pollak S. Autopsy, procedures and standards. In: Jason P-J (ed). *Encyclopedia of Forensic and Legal Medicine*. Oxford: Elsevier, 2005, pp. 166–71.
2 King LS, Meehan MC. A history of the autopsy. A review. *Am J Pathol* 1973; 73(2):514–44.
3 Tz'u S. The washing away of wrongs. In: Sivin N (ed). *Science, Medicine, and Technology in East Asia*, Vol. 1. Ann Arbor: The University of Michigan Center for Chinese Studies, 1981, p. 181.
4 Cunha F. William of Saliceto – The School of Bologna. *Am J Surg* 1941;52(1):144–9.
5 Rabl R. [Approach to postmortem examination in the change of times; a study in history of culture.]. *Virchows Arch* 1952;321(2):142–52.
6 O'Neill YV. Innocent III and the evolution of anatomy. *Med Hist* 1976;20(4):429–33.
7 Virchow R. Die cellularpathologie. In: *Ihrer Begründung auf Physiologische und Pathologische Gewebelehre*, 1st edn. Berlin: August Hirschwald, 1858.
8 Virchow R. Die sections-technik. In: *Leichenhause des Charité-Krankenhauses, mit Besonderer Rücksicht auf Gerichtsärztliche Praxis*, 1st edn. Berlin:Verlag von August Hirschwald, 1876.

9 Saukko P, Pollak S. Postmortem examination, procedures and standards. In: Siegel JA (ed). *Encyclopedia of Forensic Sciences*. Oxford: Elsevier, 2000, pp. 1272–5.

10 Saukko PJ, Pollak S. Autopsy. In: Jamieson A, Moenssens A (eds). *Wiley Encyclopedia of Forensic Science*. Chichester: John Wiley & Sons, 2009, pp. 256–62.

11 Hutchins GM. Practice guidelines for autopsy pathology. Autopsy performance. Autopsy Committee of the College of American Pathologists. *Arch Pathol Lab Med* 1994;118(1):19–25.

12 Powers JM. Practice guidelines for autopsy pathology. Autopsy procedures for brain, spinal cord, and neuromuscular system. Autopsy Committee of the College of American Pathologists. *Arch Pathol Lab Med* 1995;119(9):777–83.

13 Randall BB, Fierro MF, Froede RC. Practice guideline for forensic pathology. Members of the Forensic Pathology Committee, College of American Pathologists. *Arch Pathol Lab Med* 1998;122(12):1056–64.

14 Royal College of Pathologists. Guidelines on Autopsy Practice. London: Royal College of Pathologists, 2002.

15 Council of Europe. Recommendation no. R (99) 3 of the Committee of Ministers to member states on the harmonization of medico-legal autopsy rules. *Forensic Sci Int* 2000;111(1–3):5–58.

16 Spitz WU. The medicolegal autopsy. *Hum Pathol* 1980;11(2):105–12.

17 Holden C. Science and the law. Forensic science needs a major overhaul, panel says. *Science* 2009;323(5918):1155.

18 Goudge ST. Inquiry into Pediatric Forensic Pathology in Ontario. Toronto: Ontario Ministry of the Attorney General, 2008.

19 Samuels A. Human Tissue Act 2004: the removal and retention of human organs and tissue. *Med Leg J* 2004;72(4):148–50.

20 Brahams D. How should we amend the Human Tissue Act 1961? *Med Leg J* 2004;72(2):37–8.

21 Baum M. The use and abuse of human tissue: an analysis of the ethical issues raised by the proposed Human Tissue Act. *Med Leg J* 2004;72(2):67–9.

22 Green MA. Sudden and suspicious deaths outside the deceased's own country – time for an international protocol. *Forensic Sci Int* 1982;20(1):71–5.

23 Leadbeatter S. Deaths of British nationals abroad – a 10-year survey. *Forensic Sci Int* 1991;49(1):103–11.

24 Leadbeatter S. Knight B. The history and the cause of death. *Med Sci Law* 1987;27(2):132–5.

25 Pollanen M.S. Deciding the cause of death after autopsy – revisited. *J Clin Forensic Med* 2005;12(3):113–21.

26 Cordner SM. Deciding the cause of death after necropsy. *Lancet* 1993;341(8858):1458–60.

27 Burton JL. Health and safety at necropsy. *J Clin Pathol* 2003;56(4):254–60.

28 Anon. Needlestick transmission of HTLV-III from a patient infected in Africa. *Lancet* 1984;2(8416):1376–7.

29 Jarke J. Accident compensation and occupationally acquired HIV infections in German health care workers. *Euro Surveill* 1999;4(3):37–8.

30 Tomkins S, Ncube F (eds). Occupational transmission of HIV. In: Summary of Published Reports. London: Health Protection Agency Centre for Infections, 2005, p. 39.

31 Johnson MD, *et al*. Autopsy risk and acquisition of human immunodeficiency virus infection: a case report and reappraisal. *Arch Pathol Lab Med* 1997;121(1):64–6.

32 Cao Y, *et al*. Decay of HIV-1 infectivity in whole blood, plasma and peripheral blood mononuclear cells. *AIDS* 1993;7(4):596–7.

33 Bankowski MJ, Landay AL, Staes B. Postmortem recovery of human immunodeficiency virus type 1 from plasma and mononuclear cells. Implications for occupational exposure. *Arch Pathol Lab Med* 1992;116(11)):1124–7.

34 Douceron H, *et al*. Long-lasting postmortem viability of human immunodeficiency virus: a potential risk in forensic medicine practice. *Forensic Sci Int* 1993;60(1–2):61–6.

35 Wheelis M. Biological warfare at the 1346 siege of Caffa. *Emerg Infect Dis* 2002;8(9):971–5.

36 Szinicz L. History of chemical and biological warfare agents. *Toxicology* 2005;214(3):167–81.

37 Redmond C, *et al*. Deadly relic of the Great War. *Nature* 1998;393(6687):747–8.

38 Wheelis M. First shots fired in biological warfare. *Nature* 1998;395(6699):213.

39 Rosser EM. Campbell De Morgan and his spots. *Ann R Coll Surg Engl* 1983;65(4):266–8.

40 Hofmann E. *Lehrbuch der Gerichtlichen Medicin*, 2nd edn. Wien und Leipzig: Urban & Schwarzenberg, 1881.

41 Berkow SG. A method of estimating the extensiveness of lesions (burns and scalds) based on surface area proportions. *Arch Surg* 1924;8:138–48.

42 Lund CC, Browder NC. The estimation of areas of burns. *Surg Gynecol Obstet* 1944;79:352–8.

43 Wallace AB. The exposure treatment of burns. *Lancet* 1951;1(6653):501–4.

44 Knight B. *The Post-Mortem Technician's Handbook*. Oxford: Blackwell Scientific Publications, 1984.

45 Ludwig J (ed). *Handbook of Autopsy Practice*, 3rd edn. Totowa, NJ: Humana Press, 2002.

46 Saukko P, Knight B. *Knight's Forensic Pathology*, 3rd edn. London: Arnold, 2004.

47 Knight B. *The Coroner's Autopsy*. London: Churchill-Livingstone, 1983.

48 Prinsloo I, Gordon I. Post-mortem dissection artefacts of the neck and their differentiation from ante-mortem bruises. *South African Med J* 1951;25:358–61.

49 Pollanen MS, Perera SD, Clutterbuck DJ. Hemorrhagic lividity of the neck: controlled induction of postmortem hypostatic hemorrhages. *Am J Forensic Med Pathol* 2009;30(4):322–6.

50 Gordon I, S. H.A., B.S. D. *Forensic Medicine; a Guide to Principles*, 3rd edn. Edinburgh: Churchill Livingstone, 1988.

51 Pounder DJ, Yonemitsu K. Postmortem absorption of drugs and ethanol from aspirated vomitus – an experimental model. *Forensic Sci Int* 1991;51(2):189–95.

52 Cotton DW, Stephenson TJ. Impairment of autopsy histology by organ washing – a myth. *Med Sci Law* 1988;28(4):319–23.

53 Sutinen S, Paakko P, Lahti R. Post-mortem inflation, radiography, and fixation of human lungs. A method for radiological and pathological correlations and morphometric studies. *Scand J Respir Dis* 1979;60(1):29–35.

54 Kornegoor R, *et al*. Digitalization of post-mortem coronary angiography. *Histopathology* 2009;55(6):760–1.

55 Rah BR, *et al*. Post-mortem three-dimensional reconstruction of the entire coronary arterial circulation using electron-beam computed tomography. *Circulation* 2001;104(25):3168.

56 Weman SM, *et al*. Post-mortem cast angiography in the diagnostics of graft complications in patients with fatal outcome following coronary artery bypass grafting (CABG). *Int J Legal Med* 1999;112(2):107–14.

57 Kalimo H, Saukko P, Graham D. Neuropathological examination in forensic context. *Forensic Sci Int* 2004;146(2–3):73–81.

58 Tsokos M, Püschel K. Postmortem bacteriology in forensic pathology: diagnostic value and interpretation. *Leg Med (Tokyo)* 2001;3(1):15–22.

59 Morris JA, Harrison LM, Partridge SM. Postmortem bacteriology: a re-evaluation. *J Clin Pathol* 2006;59(1):1–9.

60 Virchow R. Die sections-technik. In: *Leichenhause des Charité-Krankenhauses, mit Besonderer Rücksicht auf Gerichtsärztliche Praxis*, 4th edn. Berlin:Verlag von August Hirschwald, 1893.

61 Home Office Policy Advisory Board for Forensic Pathology and The Royal College of Pathologists, Code of practice and performance standards for forensic pathologists. London: The Royal College of Pathologists, 2004, p. 23.

62 Scottish Government, Crown Office Procurator Fiscal Service, and the Royal College of Pathologists, Code of Practice and Performance Standards for Forensic Pathologists Dealing with Suspicious Deaths in Scotland. Edinburgh: Scottish Government, 2007, p. 27.

63 Schuster N.H. Early days of roentgen photography in Britain. *Br Med J* 1962;2(5313):1164–6.

64 Brogdon BG (ed). *Forensic Radiology*. Boston: Boca Raton/CRC Press, 1998.

65 Cox J, Kirkpatrick RC. The new photography with report of a case in which a bullet was photographed in the leg. *Montreal Med J* 1896;24:661–5.

66 Brogdon BG, Lichtenstein JE. Forensic radiology in historical perspective. In: Brogdon BG (ed). *Forensic Radiology*. Boston: CRC Press/Boca Raton, 1998, p. 477.

67 Evans KT, Knight B. *Forensic Radiology*, 1st edn. 1981, Oxford: Blackwell Scientific Publications.

68 Withers S. The story of the first roentgen evidence. *Radiology* 1937;17(1):99–103.

69 Schüller A. A note on the identification of skulls by X-ray pictures of the frontal sinuses. *Med J Aust* 1943;25:554–556.

70 Schüller A. Das Röntgenogram der stirnhöhle. *Monatschrift Ohrenheilkunde* 1921;55:1617–20.

71 Culbert WL, Law FM. Identification by comparison of roentgenograms. *JAMA* 1927;88(21):1634–6.

72 Sassouni V. A roentgenographic cephalometric analysis of cephalo-facio-dental relationships. *Am J Orthod* 1955;41(10):735–64.

73 Adams BJ. The diversity of adult dental patterns in the United States and the implications for personal identification. *J Forensic Sci* 2003;48(3):497–503.

74 Adams BJ. Establishing personal identification based on specific patterns of missing, filled, and unrestored teeth. *J Forensic Sci* 2003;48(3):487–96.

75 Wood RE. Forensic aspects of maxillofacial radiology. *Forensic Sci Int* 2006;159(Suppl 1):S47–55.

76 Huittinen VM, Slatis P. Postmortem angiography and dissection of the hypogastric artery in pelvic fractures. *Surgery* 1973;73(3):454–62.

77 Karhunen PJ. Neurosurgical vascular complications associated with aneurysm clips evaluated by postmortem angiography. *Forensic Sci Int* 1991;51(1):13–22.

78 Karhunen PJ, *et al.* Vertebral artery rupture in traumatic subarachnoid haemorrhage detected by postmortem angiography. *Forensic Sci Int* 1990;44(2–3):107–15.

79 Karhunen PJ, *et al.* Diagnostic angiography in postoperative autopsies. *Am J Forensic Med Pathol* 1989;10(4):303–9.

80 Wüllenweber R, Schneider V, Grumme T. [A computer-tomographical examination of cranial bullet wounds (author's transl)]. *Z Rechtsmed* 1977;80(3):227–46.

81 Plattner T, *et al.* Virtopsy-postmortem multislice computed tomography (MSCT) and magnetic resonance imaging (MRI) in a fatal scuba diving incident. *J Forensic Sci* 2003;48(6):1347–55.

82 Thali MJ, *et al.* Virtopsy, a new imaging horizon in forensic pathology: virtual autopsy by postmortem multislice computed tomography (MSCT) and magnetic resonance imaging (MRI)–a feasibility study. *J Forensic Sci* 2003;48(2):386–403.

83 Aghayev E, *et al.* Virtopsy—fatal motor vehicle accident with head injury. *J Forensic Sci* 2004;49(4):809–13.

84 Aghayev E, *et al.* Virtopsy post-mortem multi-slice computed tomography (MSCT) and magnetic resonance imaging (MRI) demonstrating descending tonsillar herniation: comparison to clinical studies. *Neuroradiology* 2004;46(7):559–64.

85 Yen K, *et al.* Virtopsy: forensic traumatology of the subcutaneous fatty tissue; multislice computed tomography (MSCT) and magnetic resonance imaging (MRI) as diagnostic tools. *J Forensic Sci* 2004;49(4):799–806.

86 Jackowski C, *et al.* Postmortem diagnostics using MSCT and MRI of a lethal streptococcus group A infection at infancy: a case report. *Forensic Sci Int* 2005;151(2-3):157–63.

87 Jackowski C, *et al.* Virtopsy: postmortem imaging of the human heart *in situ* using MSCT and MRI. *Forensic Sci Int* 2005;149(1):11–23.

88 Jackowski C, *et al.* Virtopsy: postmortem minimally invasive angiography using cross section techniques--implementation and preliminary results. *J Forensic Sci* 2005;50(5):1175–86.

89 Thali MJ, *et al.* VIRTOPSY—scientific documentation, reconstruction and animation in forensic: individual and real 3D data based geo-metric approach including optical body/object surface and radiological CT/MRI scanning. *J Forensic Sci* 2005;50(2):428–42.

90 Aghayev E, *et al.* Virtopsy hemorrhage of the posterior cricoarytenoid muscle by blunt force to the neck in postmortem multislice computed tomography and magnetic resonance imaging. *Am J Forensic Med Pathol* 2006;27(1):25–9.

91 Dirnhofer R, *et al.* VIRTOPSY: minimally invasive, imaging-guided virtual autopsy. *Radiographics* 2006;26(5):1305–33.

92 Grabherr S, *et al.* Postmortem angiography after vascular perfusion with diesel oil and a lipophilic contrast agent. *Am J Roentgenol* 2006;187(5):W515–23.

93 Jackowski C, *et al.* Postmortem unenhanced magnetic resonance imaging of myocardial infarction in correlation to histological infarction age characterization. *Eur Heart J* 2006;27(20):2459–67.

94 Jackowski C, *et al.* Postmortem imaging of blood and its characteristics using MSCT and MRI. *Int J Legal Med* 2006;120(4):233–40.

95 Thali MJ, *et al.* Dental CT imaging as a screening tool for dental profiling: advantages and limitations. *J Forensic Sci* 2006;51(1):113–9.

96 Jackowski C, *et al.* Intrahepatic gas at postmortem computed tomography: forensic experience as a potential guide for in vivo trauma imaging. *J Trauma* 2007;62(4):979–88.

97 Oesterhelweg L, *et al.* Virtopsy: fatal stab wounds to the skull – the relevance of ante-mortem and post-mortem radiological data in case reconstructions. *Leg Med (Tokyo)* 2007;9(6):314–7.

98 Thali MJ, *et al.* VIRTOPSY – the Swiss virtual autopsy approach. *Leg Med (Tokyo)* 2007;9(2):100–4.

99 Aghayev E, *et al.* Virtopsy – the concept of a centralized database in forensic medicine for analysis and comparison of radiological and autopsy data. *J Forensic Leg Med* 2008;15(3):135–40.

100 Bolliger SA, *et al*. Virtual autopsy using imaging: bridging radiologic and forensic sciences. A review of the Virtopsy and similar projects. *Eur Radiol* 2008;18(2):273–82.

101 Grabherr S, *et al*. Two-step postmortem angiography with a modified heart-lung machine: preliminary results. *Am J Roentgenol* 2008;190(2):345–51.

102 Jackowski C, Persson A, Thali MJ. Whole body postmortem angiography with a high viscosity contrast agent solution using poly ethylene glycol as contrast agent dissolver. *J Forensic Sci* 2008;53(2):465–8.

103 Jackowski C, *et al*. Ultra-high-resolution dual-source CT for forensic dental visualization-discrimination of ceramic and composite fillings. *Int J Legal Med* 2008;122(4):301–7.

104 Jacobsen C, *et al*. Unusually extensive head trauma in a hydraulic elevator accident: post-mortem MSCT findings, autopsy results and scene reconstruction. *J Forensic Leg Med* 2008;15(7):462–6.

105 Ross S, *et al*. Postmortem whole-body CT angiography: evaluation of two contrast media solutions. *Am J Roentgenol* 2008;90(5):1380–9.

106 Verhoff M.A, *et al*. Digital forensic osteology – possibilities in cooperation with the Virtopsy project. *Forensic Sci Int* 2008;174(2-3):152–6.

107 Weilemann Y, *et al*. Correlation between skeletal trauma and energy in falls from great height detected by post-mortem multislice computed tomography (MSCT). *Forensic Sci Int* 2008;180(2–3):81–5.

108 Bolliger SA, *et al*. Is differentiation of frequently encountered foreign bodies in corpses possible by Hounsfield density measurement? *J Forensic Sci* 2009;54(5):1119–22.

109 Pomara C, *et al*. Virtopsy versus digital autopsy: virtual autopsy. *Radiol Med* 2009;114(8):1367–82.

110 Ampanozi G, *et al*. Virtopsy: CT and MR imaging of a fatal head injury caused by a hatchet: a case report. *Leg Med (Tokyo)* 2010;12(5):238–41.

111 Christe A, *et al*. Clinical radiology and postmortem imaging (Virtopsy) are not the same: specific and unspecific postmortem signs. *Leg Med (Tokyo)* 2010;12(5):215–22.

112 Filograna L, *et al*. Diagnosis of fatal pulmonary fat embolism with minimally invasive virtual autopsy and post-mortem biopsy. *Leg Med (Tokyo)* 2010;12(5):233–7.

113 Golden GS. Use of alternative light source illumination in bite mark photography. *J Forensic Sci* 1994;39(3):815–23.

114 David TJ, Sobel MN. Recapturing a five-month-old bite mark by means of reflective ultraviolet photography. *J Forensic Sci* 1994;39(6):1560–7.

115 Shapiro H. Medico-legal mythology; some popular forensic fallacies. *J Forensic Med* 1954;1:144–69.

116 Moritz AR. Classical mistakes in forensic pathology. *Am J Clin Pathol* 1956;26:1383–92.

117 Hunter J. On the digestion of the stomach after death. *Phil Trans Royal Soc Lond* 1772;447–52.

118 Lech T. Exhumation examination to confirm suspicion of fatal lead poisoning. *Forensic Sci Int* 2006;158(2–3):219–23.

119 Grellner W, Glenewinkel F. Exhumations: synopsis of morphological and toxicological findings in relation to the postmortem interval. Survey on a 20-year period and review of the literature. *Forensic Sci Int* 1997;90(1–2):139–59.

120 Spiller HA, Pfiefer E. Two fatal cases of selenium toxicity. *Forensic Sci Int* 2007;171(1):67–72.

121 Politi L, *et al*. Ethyl glucuronide and ethyl sulfate in autopsy samples 27 years after death. *Int J Legal Med* 2008;122(6):507–9.

122 Ehrlich E, Riesselmann B, Tsokos M. A series of hospital homicides. *Leg Med (Tokyo)* 2009;11(Suppl 1):S100–2.

123 Gaillard Y, *et al*. Detection of amitriptyline, nortriptyline and bromazepam in liver, CSF and hair in the homicidal poisoning of a one-month-old girl autopsied 8 months after death. *Forensic Sci Int* 2011;207(1–3):e16–18.

124 Poli D, *et al*. Nitrous oxide determination in postmortem biological samples: a case of serial fatal poisoning in a public hospital. *J Forensic Sci* 2010;55(1):258–64.

125 Kibayashi K, *et al*. Differentiation between bruises and putrefactive discolorations of the skin by immunological analysis of glycophorin A. *Forensic Sci Int* 1993;61(2–3):111–17.

126 Karch SB. Resuscitation-induced myocardial necrosis. Catecholamines and defibrillation. *Am J Forensic Med Pathol* 1987;8(1):3–8.

127 Leadbeatter S, Knight B. Resuscitation artefact. *Med Sci Law* 1988;28(3):200–4.

128 Mason J. Resuscitation artefacts, including bone marrow. In: *Forensic Medicine: An Illustrated Reference*. London: Chapman & Hall, 1993, pp. 39–42.

129 Plunkett J. Resuscitation injuries complicating the interpretation of premortem trauma and natural disease in children. *J Forensic Sci* 2006;51(1):127–30.

130 Haynes DE, Haynes BE, Yong YV. Esophageal rupture complicating Heimlich maneuver. *Am J Emerg Med* 1984;2(6):507–9.

131 Meredith MJ, Liebowitz R. Rupture of the esophagus caused by the Heimlich maneuver. *Ann Emerg Med* 1986;15(1):106–7.

132 Majumdar A, Sedman PC. Gastric rupture secondary to successful Heimlich manoeuvre. *Postgrad Med J* 1998;74(876):609–10.

133 Dziecioł J, *et al*. Widespread myocardial and pulmonary bone marrow embolism following cardiac massage. *Forensic Sci Int* 1992;56(2):195–9.

134 Centers for Disease Control and Prevention. Post-earthquake injuries treated at a field hospital – Haiti, 2010. *Morb Mortal Wkly Rep* 2011;59(51):1673–7.

135 Morgan OW, *et al*. Mass fatality management following the South Asian tsunami disaster: case studies in Thailand, Indonesia, and Sri Lanka. *PLoS Med* 2006;3(6):e195.

136 Busuttil A. Lockerbie and Dunblane: disasters and dilemmas. *Med Leg J* 1998;66(4):126–40.

137 Eckert WG. The Lockerbie disaster and other aircraft breakups in midair. *Am J Forensic Med Pathol* 1990;11(2):93–101.

138 Moody GH, Busuttil A. Identification in the Lockerbie air disaster. *Am J Forensic Med Pathol* 1994;15(1):63–9.

139 Busuttil A, Jones JSP, Green MA, (eds). *Major Disasters, The Pathologist's Role*. London: Royal College of Pathologists, 2000, p. 49.

140 Nakajima K, *et al*. Pokkuri Death Syndrome; sudden cardiac death cases without coronary atherosclerosis in South Asian young males. *Forensic Sci Int* 2011;207(1–3):6–13.

141 Bloch A. *Murphy's Law and Other Reasons Why Things Go Wrong*. Los Angeles: Price/Stern/Sloan Publishers, 1977.

142 Saukko P. Das Gesetz von Murphy und ein fall von erwürgen. In: Brinkmann B, *Püschel* K (eds). Ersticken. Fortschritte in der Beweisführung. Festschrift für Werner Janssen. Berlin: Springer-Verlag, 1990, pp. 119–21.

CHAPTER 2

The Pathophysiology of Death

- Types of death
- Hypostasis
- Rigor mortis
- Post-mortem decomposition
- Putrefaction
- Formation of adipocere
- Mummification
- Post-mortem damage by predators
- The entomology of the dead and post-mortem interval
- Determination of time since death
- Stomach emptying as a measure of time since a death
- The use of vitreous humour chemistry in timing death
- Post-mortem chemistry
- References

Most of the discussion concerning the definitions of death belongs to the field of legal medicine and even that of ethics, rather than forensic pathology. Notwithstanding this, a quick review of this complex problem is appropriate here, as when we come to describe the various post-mortem phenomena, some appreciation is necessary of the zero point from which such changes are timed.

Types of death

It is conventional to describe two types of death:

- Somatic death, in which the person irreversibly loses sentient personality, being unconscious, unable to be aware of (or to communicate with) their environment, and unable to appreciate any sensory stimuli or to initiate any voluntary movement. Reflex nervous activity may, however, persist, and circulatory and respiratory functions continue either spontaneously or with artificial support so that the tissues and cells of the body, other than those already damaged in the central nervous system (CNS), are alive and functioning.
- Cellular death, in which the tissues and their constituent cells are dead – that is, they no longer function or have metabolic activity, primarily aerobic respiration.

Cellular death follows the ischaemia and anoxia inevitably consequent upon cardiorespiratory failure, but it is a process rather than an event, except in the exceptionally rare circumstance of almost instantaneous total bodily destruction, such as falling into molten metal or a nuclear explosion. Even fragmentation of a body by a bomb does not kill all cells instantly.

Different tissues die at different rates, the cerebral cortex being vulnerable to only a few minutes' anoxia, whereas connective tissues and even muscle survive for many hours, even days after the cessation of the circulation.

Brain death

Without trespassing too far into clinical medicine, it may be further noted that somatic death is virtually equated with brain death. When the higher levels of cerebral activity are selectively lost, either from a period of hypoxia, trauma, or toxic insult, the victim will exist in a 'vegetative state'. Here the survival of the brainstem ensures that spontaneous breathing will continue and therefore cardiac function is not compromised. The victim can remain in deep coma almost indefinitely – certainly for years – though debilitating complications such as postural skin necrosis, muscle contractures and secondary chest infections may well shorten life. Such vegetative patients are not considered 'dead' by most standards, though there is a faction of the medical profession who claim that, because of the irreversible loss of their awareness of themselves and the world around them, they can no longer be considered 'human beings'.

As they are not on life-support machines, however, there is nothing short of euthanasia that can be done about their condition. Attitudes are changing, however, as evidenced by the case of Tony Bland, who declined into a persistent vegetative state, with functioning respiration, after hypoxia caused by crush asphyxia during the Sheffield Hillsborough football disaster. After several years in this persistent vegetative state, his family obtained the consent of the courts in 1993 to allow nutrition to be withdrawn and natural death to supervene.[1]

It is another matter when brain death spreads below the tentorium. When the brainstem (specifically the midbrain, pons and upper medulla) suffers neuronal damage, the loss of the 'vital centres' that control respiration, and of the ascending reticular activating system that sustains consciousness, causes the victim not only to be irreversibly comatose, but also to be incapable of spontaneous breathing. Without medical intervention, hypoxic cardiac arrest inevitably follows within minutes and then the usual progression of 'cellular death' ensues. This invariably occurred in the past, before the advent of sophisticated devices that allowed the support of respiration after spontaneous function has ceased. Because of continued oxygenation, the heart continues to function, though it has been pointed out by Pallis that the vast majority of brainstem-dead patients suffer a cardiac arrest within 48–72 hours, even when adequately oxygenated.[2]

This then is the state of 'brainstem death', and almost all doctors and most jurisdictions now accept that, once irreversible damage to the brainstem has been proved, the patient is 'dead' in the somatic sense. They are, however, not yet dead in the cellular sense and it is through this 'physiological window' that the spectacular advances in cadaver donor transplant surgery have been made.

Medico-legal aspects of brain death

In relation to forensic pathology and criminal procedure, these matters have now a largely historical relevance, in that several decades ago a number of fatal assaults were defended in court on the basis that the original head injuries led to the victims being placed on life-support machines that were later disconnected when brainstem death was diagnosed. The defence was that the assailant did not 'kill' the victim, because 'death' was caused by the action of the doctors switching off the machine. Several judicial decisions have disposed of this defence, however, as it was accepted, first, that death was diagnosed by the doctors before discontinuing artificial ventilation and, second, that the criminal act that initiated the train of events was not remote enough to avoid culpability for the death.

The indications of death

Here the signs of somatic death are considered; those of cellular death are manifested by post-mortem changes, to be discussed in later sections. When cardiorespiratory arrest occurs, brain function ceases within seconds as a result of the collapse of cerebral blood pressure and consequent cortical ischaemia. Within minutes, this loss of brain function becomes irreversible. The actual number of minutes for which total anoxia will cause cortical damage is controversial; it was formerly held that 3 minutes was sufficient, but this time has been extended to 7 or 9 minutes. Even much longer times of total hypoxia, such as immersion under water, has been survived without brain damage. In these cases, an element of hypothermia is usual, which reduces the oxygen needs of the tissues. Thus 20 or even 40 minutes of hypoxia has been claimed as not leading to brain damage. All that can be said is that the period is very variable and that 3–4 minutes of cardiac arrest or failure of respiratory gas exchange carries the risk of cortical damage, even though three or four times this period may sometimes be survived without ill-effects.

- Unconsciousness and loss of all reflexes occurs, and there is no reaction to painful stimuli.
- Muscular flaccidity occurs immediately upon failure of cerebral and cerebellar function. All muscle tone is lost, though the muscles are physically capable of contraction for many hours.
- Eye signs include loss of the corneal and light reflexes leading to insensitive corneas and fixed, unreactive pupils. Though the iris responds to chemical stimulation for hours after somatic death, the light reflex is lost as soon as the brainstem nuclei suffer ischaemic failure. The pupils usually assume a mid-dilated position, which is the relaxed neutral position of the pupillary muscle, though they may later alter as a result of rigor. There may be a marked difference in the degree of dilatation of each pupil, but this has no significance as a diagnostic sign either of a brain lesion or of drug intoxication. In conditions such as morphine poisoning, where

the pupils may be contracted during life, death may allow this to persist or the pupils may dilate to the 'cadaveric position'.

In addition to irregular size, the pupils may lose their circular shape after death as a result of uneven relaxation. This is usually easy to differentiate from the more obvious irregularity caused by ante-mortem abnormality of the iris. The eye globe tension decreases rapidly, as it is dependent upon arterial pressure for its maintenance. The eyeball feels progressively softer within minutes and the cornea soon loses its normal glistening reflectivity because of laxity and failure of lachrymal moistening. Normal tension was measured by Nicati in 1894, who found that it halved at death, fell to as low as an eighth in 30 minutes, and was nil by 2 hours after death.[3] The eyelids usually close, but this is commonly incomplete, the flaccid muscles failing to produce the full occlusion that occurs in voluntary closure. Where the sclera remains exposed, two yellow triangles of desiccated discolouration appear on each side of the cornea within a few hours, becoming brown and then sometimes almost black, giving rise to the name 'tache noire'. This phenomenon was first communicated by Sommer who also confirmed it by experiments (Fig. 2.1).[4,5]

When viewed with an ophthalmoscope, the retina provides one of the earliest positive signs of death. This is the well known 'trucking' of blood in the retinal vessels, when loss of blood pressure allows the blood to break up into segments, similar to trucks in a railway train. This phenomenon occurs all over the body, but only in the retina is it accessible to direct viewing.



Figure 2.1 Post-mortem change in the eye, the so-called 'tache noire'. These are brown areas of scleral drying caused by failure of the lids to close after death.

The test is not easy to carry out, as the retina of a corpse seems far more difficult to visualize than in a living person. Many observers have described the agonal and early post-mortem appearances of the retina, though some of their accounts are rather contradictory and of little practical value, especially when they attempt to use them to estimate the time since death. Most observers – for example, Kervorkian and Salisbury and Melvin – confirm that the blood flow slows and becomes irregular in density before breaking up into segments.[6–8] This was apparent within 15 minutes of death as assessed by other means. Kervorkian claimed that colour changes in the retina were closely related to the post-mortem interval (PMI). Tomlin believed that segmentation was more indicative of cerebral death than cessation of the circulation, and agreed with others in accepting that 'trucking' was of grave prognostic significance.

One of the best investigations into the phenomenon was by Wroblewski and Ellis, who studied retinal and corneal changes at death in 300 patients.[9] About a third of the total exhibited trucking, most of them within an hour of death. Part of the difficulty in examining the remainder was that clouding of the cornea occurred in 75 per cent of patients within 2 hours of death. They concluded that segmentation was a purely post-mortem change and any intravascular movement of blood, however irregular, was an indication for continued resuscitation.

- Cessation of the heart beat and respiratory movements was the primary marker of death until the advent of mechanical cardiorespiratory support as it led to immediate ischaemia and anoxia of all other tissues. Determination of cardiac arrest may be made by prolonged auscultation of the chest to exclude heart sounds though, as in life, a feeble heartbeat may be muffled by a thick chest wall. The electrocardiograph is unchallengeable in confirming cardiac arrest.

  Respiration is more difficult to confirm, especially in deep coma such as barbiturate poisoning, and prolonged listening with a stethoscope over the trachea or lung fields is necessary. All archaic procedures such as saucers of water on the chest, feathers before the nostrils and tourniquets around the fingers are only of historical interest.

The mode versus the cause of death

Confusion often arises, especially among students and younger doctors, about the distinction between the *mode* of death and its *cause*. This is particularly important in relation to the documentary certification of deaths, but the same confusion sometimes occurs among pathologists, especially those who are not habitually involved in medico-legal cases.

The mode of death refers to an abnormal physiological state that pertained at the time of death: for example, 'coma', 'congestive cardiac failure', 'cardiac arrest' and 'pulmonary oedema'. These offer no information as to the underlying pathological condition and should not be used as the definitive cause of death unless further qualified by the more fundamental aetiological process.

In most cases, the mode is unhelpful and immaterial in describing and understanding the cause of death, and some modal terms are quite useless, such as 'syncope' or 'cardiorespiratory failure'. Even 'bronchopneumonia' is such a common terminal event in numerous diseases that, used alone, it conveys no information about why the patient died. The British Registrar General has recently requested that it should be omitted from death certificates, the basic condition being preferable and sufficient for statistical purposes.

In addition to the mode and cause of death, there is also the *manner* of death, which in the countries with a coronial system, is not really a medical decision. Manner refers to the circumstantial events, such as 'homicide, suicide, accident or natural cause' and is a legal or administrative categorization.

The recommendations of the World Health Organization, as given in its publication *The Medical Certification of Death*, should be followed to improve both the comprehension and statistical accuracy of the cause of death. Even this booklet is inconsistent with the practice of certification in many advanced countries, in that it requests the doctor to enter the 'manner' of death (for example, homicide, accident or suicide) which, for example in the UK, is the prerogative of the legal authorities after full investigation.[10]

Post-mortem changes of forensic importance

To the forensic pathologist a number of post-mortem changes are of interest and potential usefulness, mainly in relation to the estimation of the PMI, possible interference with the body, and an indication of the cause of death (Fig. 2.8).

Hypostasis

Post-mortem hypostasis is known under a variety of older names, such as 'lucidity', 'staining' or 'cogitation', but the current title is most suitable as it indicates the cause. Hypostasis occurs when the circulation ceases, as arterial propulsion and venous return then fail to keep blood moving through the capillary bed and the associated small afferent and efferent vessels.



Figure 2.2 Blotchy post-mortem hypostasis, forming in the early hours after death. The patchy disposition has no significance and this usually sinks down and becomes confluent in the most dependent areas within a few more hours.

Gravity then acts upon the now stagnant blood and pulls it down to the lowest accessible areas. The red cells are most affected, sedimenting through the lax network, but plasma also drifts downwards to a lesser extent, causing an eventual post-mortem 'dependent oedema', which contributes to the skin blistering that is part of early post-mortem decay.

The arrival of erythrocytes in the lower areas is visible through the skin as a bluish red discolouration, 'hypostasis'. It often begins as blotchy patches on both lateral and dependent surfaces, but also on the upper surfaces of the legs, especially thighs. These soon coalesce and slide down to the lowest areas (Fig. 2.2).

The distribution of hypostasis

The pattern of hypostasis depends on the posture of the body after death. It is most common when the deceased body is lying on its back, with the shoulders, buttocks and calves pressed against the supporting surface. This compresses the vascular channels in those areas, so that hypostasis is prevented from forming there, the skin remaining white. When the body lies for a sufficient time on the side or face, the hypostasis will distribute itself accordingly, again with white pressure areas at the zones of support (Figs 2.3, 2.5).

If the body remains vertical after death, as in hanging, hypostasis will be most marked in the feet, legs and to lesser extent in the hands and distal part of the



Figure 2.3 Post-mortem hypostasis in the normal distribution. The pale areas are the result of pressure against a hard supporting surface.



Figure 2.4 Post-mortem hypostasis in a death from hanging. The discolouration of the skin is in the legs and hands, due to the vertical posture after death.

arms (Fig. 2.4). In addition to pallor of the supporting areas, any local pressure can exclude hypostasis and produce a distinct pattern in contrast to the discoloured area. Examples include the irregular linear marks made by folds in rumpled bedlinen, the pattern of fabric from coarse cloth, the pressure of tight belts, brassière straps, pants' elastic and even socks. According to Bonte *et al.*, when electrocution takes place in water (usually a bathtub), the hypostasis is sharply limited to a horizontal line corresponding to the water level.[11]

The colour of hypostasis

The usual hue is a bluish red, but variation is wide. This depends partly on the state of oxygenation at death, those dying in a congested, hypoxic state having a darker tint as a result of reduced haemoglobin in the skin vessels. This is an unsure indicator of the mode of death, however, and no reliance can be placed on a cyanotic darkening of the hypostasis to indicate a hypoxic death in the sense of 'asphyxia'. Many natural deaths from coronary or other disease have markedly dark hypostasis. Often the colour of the hypostasis varies from area to area on the same body. Sometimes a rim of lighter colour may be seen along the margin of the lower darker area and sometimes there is a definite contrast between a bluish zone and a pink margin. This may appear and change as the PMI lengthens. Often the whole area of hypostasis is pink or bright red. When death has been due to hypothermia or exposure to cold in the agonal period, such as from drowning, the colour may assist in confirming the cause of death; again this is relatively non-specific because bodies exposed to cold after death (especially in mortuary refrigeration) may turn pink after an initial stage of normal bluish-red tint.

The mechanism is not understood, but is obviously a result of oxyhaemoglobin forming at the expense of the darker reduced haemoglobin. This is understandable in hypothermia, where the reduced metabolism of the tissues fails to take up oxygen from the circulating blood, but its frequent formation in the post-mortem period is difficult to explain.

Several researchers have investigated the colour of hypostasis in relation to time since death. Schuller *et al.* noted an increasing paleness between 3 and 15 hours post-mortem, measuring this as a change in wavelength from 575 nm at 3 hours at an average rate of 2 nm per hour.[12] Vanezis has used tristimulus colorimetry to study colour changes and secondary shifting of hypostasis, and claimed that there is a linear relationship between the fading colour and time during the first 2 hours after death, following which changes are unpredictable.[13] Inoue *et al.* have also described measurement of hypostatic colour as a measure of time since death.[14]

It may sometimes be noticed that originally bluish hypostasis becomes pink along the upper part of the horizontal margin, the lower parts remaining dark, so a quantitative change probably occurs, the haemoglobin being more easily re-oxygenated where the erythrocytes are packed less densely in the upper layers of hypostasis.

Other changes in the colour of hypostasis are more useful. The best known is the 'cherry-pink' of carboxyhaemoglobin, which is a unique colour and is often the first indication to the pathologist of carbon monoxide poisoning (see Fig. 29.1). Cyanide poisoning



Figure 2.5 White patches within the hypostasis on the face merely indicate pressure against the supporting surface after a face-down position. As in this case, they are usually post-mortem and are not indicators of suffocation.



Figure 2.6 Extensive confluent skin haemorrhages may occur within the dependent hypostasis. They worsen as the post-mortem interval lengthens and must not be taken to indicate so-called 'asphyxia'.

is said to have its own characteristic dark blue–pink hue, but it is really an index of the congested, cyanotic, mode of death and, if the pathologist was not already aware of the potential cause from the history – and perhaps the odour of cyanide – it is doubtful whether hypostasis would be a primary indication of the nature of the death. The hypostasis may be a brownish red in methaemoglobinaemia and may be various shades in aniline and chlorate poisoning. In deaths from septic abortions where *Clostridium perfringens* is the infecting agent, a pale bronze mottling may sometimes be seen on the skin, though this is not confined to the areas of hypostasis.

Skin haemorrhages, varying in size from small petechiae to large blotches and even palpable blood blisters may develop in areas of hypostasis (Fig. 2.6). The most common place is the back of the shoulders and neck, though they may appear on the front of the chest, even on a body lying on its back. They are more common in cyanotic, congestive types of death and become more pronounced as the PMI lengthens. Their importance is in not being mistaken for the so-called signs of 'asphyxia'. They appear in the most gross form when a body dies or is left with the head downwards: the confluent petechiae and ecchymoses may be so marked that they virtually blacken the face and neck.

The timing and permanence of hypostasis

Too much has been claimed in the past for the usefulness of hypostasis as an indicator of the time of death and post-mortem disturbance of the body. The phenomenon appears at a variable time after death – indeed, it may not appear at all, especially in infants, old people or those with anaemia. It may be so faint as almost to escape detection.

Hypostasis can appear within half an hour of death or it may be delayed for many hours. Its variability is such that it is useless for any estimation of the time since death. It is claimed that hypostasis can sometimes be observed in the living if the heart action is failing or if venous return is impaired by the immobility of deep coma. The latter is certainly associated with skin blistering caused by dependent oedema.

Once hypostasis is established, there is controversy about its ability to undergo subsequent gravitational shift. If the body is moved into a different posture, the primary hypostasis may either:

- remain fixed
- move completely to the newly dependent zones or
- be partly fixed and partly relocated.

Thus if a corpse is found with the hypostasis in an obviously inappropriate distribution related to the present posture, it must have been moved after death. This fact may have important significance in the investigation of criminal deaths, such as the return of the culprit or some other person to the scene. It may also migrate either partly or completely, however, thus negating its diagnostic usefulness. Older theories about 'fixation' of the staining after a certain time are not tenable, as there is no constant interval when this occurs.

Mallach analysed data including onset, confluence, maximum intensity, displacement and shifting, taken from publications between 1905 and 1963.[15] These are summarized in Table 2.1, 'thumb pressure' meaning displacement by thumb pressure. Table 2.2 shows the variable opinions on hypostasis culled from standard textbooks.

A considerable amount of research has been devoted to the investigation of clotting of post-mortem blood, its subsequent lysis and inhibition of coagulation by fibrinolysins, but this cannot be translated into practice. Formerly, it was held that if a body had remained in its original posture for a certain minimum length of time, the blood would coagulate in the hypostatic areas, so that secondary shifting could not then occur if the body was moved. This is not true in the majority of instances, as there may be partial or complete secondary gravitation at any time – at least, until true staining of the tissues due to haemolysis begins as part of early decomposition, which is not until the second or third day in temperate conditions.

Table 2.1 Hypostasis related to the time of death (hpm) as derived from previous literature

Stage	Mean	Standard deviation	Limits	
			Lower	Upper
Beginning	0.75	0.5	0.25	3
Confluence	2.50	1.0	1.00	4
Maximum	9.50	4.5	3.00	16
Thumb pressure	5.50	6.0	1.00	20
Complete shifting	3.75	1.0	2.00	6
Incomplete shifting	11.00	4.5	4.00	24

Table 2.2 Time of onset of hypostasis as stated by previous authors

Reference	Onset	Maximum
Adelson	30 min–4 h	8–12
Polson and Gee	30 min–2 h	6–12
Spitz and Fisher	2–4 h	8–12
Taylor (ed. Simpson)	0 h	12
Taylor (ed. Mant)	1 h	12
Gradwohl (ed. Camps)	20–30 min	6–12
Glaister	-	8–12
DiMaio	30 min–2 h	8–12
Sydney Smith	0 h	12
Mant	0 h	12
Gordon and Shapiro	'few' h	12

Suzutani *et al.* examined 430 bodies by pressure on hypostatic areas, finding that the colour could not be squeezed out in 30 per cent where death had occurred 6–12 hours previously.[16] More than 50 per cent were fixed after 12–24 hours and no fading occurred in 70 per cent of those dead for more than 1–3 days. However, in a significant number, hypostasis was still mobile for at least 3 days.

Fechner *et al.* found no linear relationship between fixation and time of death and also observed variations in fixation according to storage temperatures.[17]

Hypostasis in other organs

Just as blood settles in dependent skin, so it does in other tissues and organs. The importance in forensic autopsy work is the differentiation of organ hypostasis from ante-mortem lesions. In the intestine, dependent loops of jejunum and ileum may be markedly discoloured and mislead the inexperienced pathologist into suspecting mesenteric infarction or strangulation. This hypostasis is discontinuous, however, revealing interrupted segments when the gut is laid out. Often loops in the pelvis are worst affected, because of their lower position.

The lungs almost always show a marked difference in colour from front to back, the anterior margins being pale and the posterior edges lying in the paravertebral gutters being dark blue. This is often accompanied by an obvious difference in fluid content, congestion and oedema being more marked posteriorly. The myocardium often shows a dark patch in the posterior wall of the left ventricle that must not be mistaken for early infarction.

One of the most important hypostatic artefacts is haemorrhage behind the oesophagus at the level of the larynx. This has many times been confused with the trauma of strangulation, but the true nature was best investigated by Prinsloo and Gordon.[18] Areas of congestion developing into haemorrhage appear in the loose tissues on the back of the oesophagus lying on the anterior longitudinal ligament of the cervical spine. They may be prominent, sufficient to produce actual haematomas. They arise in the veins and venous plexus on the front of the spine, and can be avoided in cases of strangulation and suspected strangulation by draining the neck of blood before starting the dissection. This can be achieved either by removing the brain first or by opening the chest and incising the great veins in the superior mediastinum.

Differentiation between hypostasis and bruising

This is rarely a problem in fresh bodies, but when decomposition begins the two conditions become blurred. In fresh material the appearance of hypostasis is of a regular, diffuse engorgement of the surface vessels, the colour varying between purple–red and bright pink. The density varies from place to place but there are no sudden changes in colour nor any sharply circumscribed areas as occurs in bruising. As mentioned above, in the early stages of hypostasis there may be mottled blue areas, which later coalesce. This mottling is unlikely to be confused with bruising by any but the most inexperienced pathologist. The position in dependent areas is also characteristic, giving a generally horizontal orientation. Bruises may be anywhere on the body, are often discoid or have an irregular margin, but rarely cover a large area with uniform density – and do not have a horizontal margin. Abrasions may be topographically associated with a bruise, but not with hypostasis. When there is difficulty in differentiating between the two – usually where there is racial pigmentation or really deep, cyanotic hypostasis that obscures possible bruises – the classic test is to incise the suspect area to see if the underlying blood is intravascular (hypostasis) or infiltrating the tissues outside the vessels (contusion).

Fresh bruises may also be swollen and slightly raised above the surface. If a post-mortem pressure mark (such as from a belt or tight clothing) crosses an area of hypostasis, there will be a pale bloodless zone, but a bruise will not be affected. Hypostasis is in the most superficial layer of the dermis and any exuded blood can be wiped or washed away from the incised surface. A bruise is often deeper in the skin or underlying tissues and is fixed, being infiltrated through the tissues outside the ruptured vessels. An exception is intradermal bruising, but this is usually patterned or linear and rarely can be confused with hypostasis. Histological examination may be necessary finally to decide the matter.

When post-mortem autolysis has developed, the diffusion of haemolysed blood from vessels makes the differentiation between hypostasis and bruising difficult and eventually impossible. Even histological examination may be of little help when the tissues become markedly degenerate.

Rigor mortis

Unlike hypostasis, the stiffening of the muscles after death has some relevance in determining the PMI. It has been known since antiquity that immediately after death there is general muscular flaccidity, usually followed by a period of partial or total rigidity, which in turn passes off as the signs of decomposition appear. The timing of this sequence of events is so variable, however, that it is a poor indicator of the time since death. The usual range of times when rigor appears can be summarized as follows.

- The flaccid period immediately after death is variable, but commonly extends to between 3 and 6 hours before stiffening is first detected, depending on environmental temperature and other factors. Rigor is first apparent in the smaller muscle groups, not because it begins there, but because the smaller joints, such as the jaw, are more easily immobilized. The sequence of spread of rigor is also variable but tends to affect the jaw, facial muscles and neck before being obvious in the wrists and ankles, then the knees, elbows and hips.

  The usual method of testing is by attempting to flex or extend the joints, though the whole muscle mass itself becomes hard, and finger pressure on the quadriceps or pectorals can also detect the change. The onset of rigor may be markedly accelerated or retarded by the factors mentioned below, so that stiffness may develop within half an hour of death (even excluding cadaveric spasm) or may be postponed almost indefinitely. Some subjects, usually infants, the cachectic and the aged, may never develop recognizable rigor mortis, mainly because of the feebleness of their musculature.
- Rigor spreads to involve the whole muscle mass, again within a variable period but in ‘average’ conditions it might be expected to reach a maximum within 6–12 hours. This state then remains constant until the muscle mass begins to undergo autolysis, which releases rigor gradually at a stage before overt post-mortem changes are visible externally, except perhaps for a commencing discolouration of the lower abdominal wall (Fig. 2.7).



Figure 2.7 Full rigor mortis 12 hours post-mortem.

If rigor is broken before it has reached its maximum, it continues to develop again in those muscle fibres where it was not yet fully developed. It will not, however, reach the same intensity as it would have without breaking.[4,19] According to Henssge, the probable explanation for the uneven development of rigor mortis in individual muscle fibres is their different glycogen content.[20]

The duration of full rigor may be 18–36 hours, until it begins to fade in roughly the same order of muscle groups as it appeared. However, there are many exceptions to this rather misleading generalization.

Factors affecting the timing of rigor mortis

As a chemical process, the speed of onset and the duration of rigor is modified by temperature. The colder the environment the slower the process and vice versa. In near freezing conditions rigor will be suspended almost indefinitely. The author (BK) has attended a scene outdoors in winter where the body was quite flaccid 1 week after death, rigor developing rapidly as soon as the corpse was brought into the comparative warmth of the mortuary. Conversely, hot weather or tropical conditions can speed up the whole cycle so that rigor appears within an hour or even less. Total stiffness develops rapidly, then fades during the first day as decomposition supervenes.

The other modifier of the speed of onset of rigor is physical activity shortly before death. As will be seen when the physicochemical basis of the phenomenon is discussed, the availability of glycogen and adenosine triphosphate (ATP) in the muscle is a crucial element in rigor formation. Muscular exertion affects the interaction of these substances and hastens the onset of rigor. Cadaveric spasm, dealt with later, may well be an extreme variant of this accelerated rigor.

In view of the wide range of times at which the various stages of rigor appear and fade, it is a poor determinant of the time since death, compared with estimations of body temperature. Niderkorn's early work on 113 bodies showed a range of 2–13 hours for rigor to be complete, the main cluster being from 3 to 6 hours after death, a shorter period than would be accepted now.[21] Mallach compiled a table (Table 2.3).[15]

The following is a reasonable 'spot check' for use in average temperate conditions:

- if the body feels *warm* and is *flaccid*, it has been dead less than 3 hours
- if the body feels *warm* and is *stiff*, it has been dead from 3 to 8 hours
- if the body feels *cold* and is *stiff*, it has been dead from 8 to 36 hours
- if the body feels *cold* and is *flaccid*, it has been dead more than 36 hours.

Table 2.3 Time course of cadaveric rigidity as stated by previous literature

Rigor phase	Mean ± SD(s)	Hours post-mortem				Number of publications evaluated
		Limits of 95.5 per cent probability (2s)		Variations		
		Lower limit	Upper limit	Lower limit	Upper limit	
Delay period	3 ± 2	-	7	<1/2	7	26
Re-establishment possible	Up to 5	-	-	2	8	-
Complete rigidity	8 ± 1	6	10	2	20	28
Persistence	57 ± 14	29	85	24	96	27
Resolution	76 ± 32	12	140	24	192	27

This crude estimate should never be used as a definitive statement in legal proceedings, as it is only meant as a rough guide 'on the spot'.

Rigor mortis in other tissues

Rigor occurs in all muscular tissues and organs, as well as the skeletal muscles. The iris is affected so that ante-mortem constriction or dilatation is modified. The rigor may be unequal in each eye, making the pupils unequal, confirming the fact that the post-mortem position is an unreliable indicator of toxic or neurological conditions during life.

In the heart, rigor causes the ventricles to contract, which may be mistaken by the inexperienced pathologist for left ventricular hypertrophy; this can be excluded by measuring the total weight, estimating the relative size of the left side, measuring the ventricular thickness (admittedly a rough guide) and – where the issue is important – by dissection and differential weighing of the two ventricles.

Rigor in the dartos muscle of the scrotum can compress the testes and epididymis which, together with the contraction of muscular fibres in the seminal vesicles and prostate, may lead to post-mortem extrusion of semen from the urethral meatus. This has been wrongly attributed to sexual activity and orgasm just before death in cases where a defence of provocation against a homosexual advance has been put forward. Mant showed that many corpses dying from a variety of causes have seminal fluid either at the meatus or in the penile urethra.[22–24] It is also said, without much foundation, that deaths from hanging and 'asphyxia' are commonly associated with post-mortem seminal emission.

Rigor in the erector pili muscles attached to the hair follicles can cause a pimpling or 'goose-flesh' appearance with elevation of the cutaneous hairs. This may have given rise to the persistent myth that the beard grows after death, though an additional explanation is that post-mortem desiccation and shrinkage of the skin allows the hair stubble to appear more prominent.

Studies by Krompecher and Bergerioux have shown that rigor also sets in more quickly in deaths from electrocution – and that it passes off more rapidly.[25]

The biochemistry of rigor mortis

Though this has little direct forensic relevance apart from the association of the early onset of rigor with muscular exertion, the muscle chemistry of the phenomenon has been studied in great detail.

Szent-Gyorgi discovered that the essential contractile substances in muscle were the two proteins actin and myosin, arranged in interdigitating filaments.[26] They form a loose physicochemical combination called 'actomyosin', which is physically shorter than the two substances uncombined.[27] If energy is supplied to the latter pair, the subsequent combination contracts. This energy is obtained by the splitting off of a phosphate complex from ATP, which then becomes adenosine diphosphate (ADP).[28] The free phosphate then engages in a phosphorylation reaction that converts glycogen to lactic acid, high energy being released in the process. Some is used to re-synthesize the ATP from ADP, by the donation of a phosphate group from creatine phosphate; the remainder goes to activate the actin–myosin reaction.

In addition to supplying energy, ATP is responsible for the elasticity and plasticity of the muscle. The lactic acid is leached away back into the bloodstream and is returned to the liver for re-conversion into glycogen. All these reactions are anaerobic and can continue after death, albeit in a distorted form.

In life there is a fairly constant concentration of ATP in the muscular tissues, there being a dynamic balance between utilization and re-synthesis. At death, however, the ADP to ATP reaction ceases and the triphosphate is progressively diminished, with lactic acid accumulating. After a variable period, depending on temperature and the amount of ATP remaining, the actin and myosin become linked into a rigid, inextensible gel, with consequent stiffening of the muscle.[29,30]

The re-synthesis of ATP is dependent upon the supply of glycogen, which is depleted by vigorous activity before death; this explains the rapid onset of rigor in these circumstances. Normally there appears to be an initial period soon after death when the ATP level is maintained or even increased as a result of phosphate liberation by glycogenolysis.

Rigor is initiated when the ATP concentration falls to 85 per cent of normal, and the rigidity of the muscle is at maximum when the level declines to 15 per cent.[31]

Gross effects of rigor mortis

There has been some controversy over whether rigor only stiffens the muscles or actually shortens them. Sommer, as long ago as 1833, claimed that muscles contracted after death and the changes were actually known as 'Sommer's movements'.[4] There have always been semi-apocryphal tales of corpses moving in the mortuary and there seems little doubt that, if a limb happens to be poised in unstable equilibrium on the edge of a tray or table, the developing tension may occasionally cause it to spring off as rigor supervenes. The author (BK) has seen athetoid writhing of the foot of a corpse that lasted for 40 minutes, occurring more than an hour after death.

There seems to be no doubt that some shortening does occur, but the noticeable effects are slight because both flexor and extensor muscle groups oppose each other across most limb joints. Bate-Smith and Bendall decided that shortening only occurred when there had been marked depletion of glycogen by activity before death, but Forster was of the opinion that, when a muscle was under some tension, it did shorten.[30,31] His experiments showed that when the muscle was unloaded there was no change in length when rigor set in. Forster further showed that a high environmental temperature and poisons that increase muscle tone, such as parathion, lead to more shortening during rigor.

When fully established, rigor is 'broken' by forcible movements of the limbs or neck, then it will not return, a phenomenon utilized daily by mortuary staff and undertakers when preparing a body for a coffin. If rigor is still developing, it will continue in the new posture of the limbs after they have been stretched. 'Breaking' fully established rigor is an accurate description, as the rigid, inelastic fibres are physically ruptured – sometimes tearing the muscle insertions from the bone. Rarely, rigor can assist in showing that a body has been moved between death and discovery. If an arm or leg is found projecting into free space without support, in a posture that obviously could not have been maintained during primary post-mortem flaccidity, then it must have been rolled over or otherwise moved. In these cases, a simple restorative movement (after the scene has been fully examined) can usually indicate the original attitude quite simply.

Conversely, it can never be assumed that the posture of rigor in which a body is found was that which obtained at the time of death, as any amount of movement during the period of primary flaccidity will not be mirrored in the subsequent rigor.

Cadaveric spasm

This topic has received a disproportionate amount of notice in textbooks compared with its practical importance. No doubt this is because of its curiosity value rather than its usefulness. Cadaveric spasm is a rare form of virtually instantaneous rigor that develops at the time of death with no period of post-mortem flaccidity.

Krompecher, a major authority on rigor mortis, is extremely sceptical about the existence of true cadaveric spasm, but many forensic pathologists claim to have seen such a phenomenon far too soon after death for it to be normal rigor mortis.[32] The authors retain a healthy scepticism about the controversy, believing that most cases are misreported because of errors or uncertainties about the true time of death, so that early normal rigor could have supervened. However, one or two cases within BK's experience seem to be genuine enough to be remarkably early for true rigor.

It seems confined to those deaths that occur in the midst of intense physical and/or emotional activity, though how the latter can lead to instant post-mortem rigor is quite inexplicable. It presumably must be initiated by motor nerve action, but for some reason there is a failure of the normal relaxation. The phenomenon usually affects only one group of muscles, such as the flexors of one arm, rather than the whole body.

It was shown in the earlier section on the biochemistry of rigor that marked depletion of glycogen stores in the muscle by violent exertion immediately before death can hasten the onset of muscular rigidity. Most cases of cadaveric spasm occur in similar circumstances and it was said to be particularly common on the battlefield amongst soldiers slain in combat. In the civilian sphere it is most often seen in persons who fall into water or drop some distance down a precipitous slope such as a cliff. They may clutch at some nearby object, such as grass or shrubs, in an effort to break their fall and such material may be found held tightly in their fingers, even when the body is examined within a few minutes.

Another possibility, more common in detective fiction than in practice, is the gripping of a pistol with the finger still tightly flexed on the trigger, as evidence of true suicide rather than a 'planted' weapon in a homicide where an attempt has been made to simulate self-shooting. The chances of this actually being encountered by a pathologist are less than once in several professional lifetimes.

If found in the victim of drowning, or of a slide from a height, it has some value in confirming that the person was alive at the time of the fall, thus excluding the post-mortem disposal of an already dead body. Of course the body must be examined before ordinary rigor might be expected to have developed, or the presence of cadaveric spasm cannot then be assumed.

Heat and cold stiffening

At extremes of temperature the muscles may undergo a false rigor. In extreme cold, well below zero, once the intrinsic body heat is lost, the muscles may harden because the body fluids may freeze solid – as in the commercial or domestic preservation of meat in a freezing cabinet. The temperature has to be below −5°C for cold stiffening to occur and is usually much lower. Part of the apparent stiffness is also due to solidification of the subcutaneous fat. When the body is warmed up, true rigor may supervene, though it may fail to appear as a result of intracellular damage caused by cell membranes being punctured by ice crystals.

Heat applied to the body also causes stiffness of the muscles, as the proteins of the tissues become denatured and coagulated as in cooking. The degree and depth of change depends on the intensity of the heat and the time for which it was applied. At autopsy the muscles may be shrivelled and desiccated, even carbonized on the surface. Beneath this there is a zone (which may be total) of brownish-pink 'cooked meat' and under that, if the process has not penetrated, normal red muscle. Marked shortening occurs, causing the well-known 'pugilistic attitude' of a burned body (see Figs 11.9, 11.10). This is because of the greater mass of flexor muscles compared with extensors, which forces the limbs into flexion and the spine into opisthotonus. These changes are purely post-mortem and are no indication of burning during life, as similar distortions occur during cremation.

Post-mortem decomposition

Hypostasis and decomposition occur relatively soon after death when somatic death has occurred, but cellular death is incomplete. As discussed earlier, death is a process not an event and, while the cells of some tissues are still alive and even capable of movement (such as fibroblasts, leucocytes and muscle), others are dying or dead. The process of decomposition begin in some cells while others are still alive, and this overlap continues for several days in temperate climates.

Decomposition is a mixed process ranging from autolysis of individual cells by internal chemical breakdown to tissue autolysis from liberated enzymes, and external processes introduced by bacteria and fungi from the intestine and outer environment. Animal predators, from maggots to mammals, can be included in the range of destruction. Decomposition may differ from body to body, from environment to environment, and even from one part of the same corpse to another. Sometimes one portion of a corpse may show leathery, mummified preservation whilst the rest is in a state of liquefying putrefaction (Fig. 2.8).

In addition, the time scale for decomposition may vary greatly in different circumstances and climates, and even in the same corpse: the head and arms may be skeletalized, whilst the legs and trunk, perhaps protected by clothing or other covering, may be moderately intact. All permutations may be found,



Figure 2.8 The fate of a body after death.



Figure 2.9 Moderately early changes of decomposition, showing gaseous distension of scrotum and abdomen, and skin slippage and blistering in dependent areas. This was after about 1 week since death, but the changes vary greatly with environmental temperatures.

making it even more difficult to estimate the probable time since death.

Within the general description of ‘decomposition’ there are several subclasses, which, as just stated, may merge into each other or may be uniform throughout the same cadaver. Most unembalmed bodies undergo putrefaction, in which the tissues become moist and gas-ridden, and eventually liquefy down to the skeleton.

Alternatives are dry decomposition, termed mummification, or a conversion to waxy substances, called adipocere; rarely, tannin occurs by the action of acid, protein-precipitating fluids in the anaerobic conditions of a peat bog. In some stillbirths an aseptic autolysis of a fetus dead *in utero* is known as maceration.

Putrefaction

The usual process of corruption of the dead body begins at a variable time after death, but in an average temperate climate may be expected to begin at about 3 days in the unrefrigerated corpse.

Even in temperate zones there can be a wide range of ambient temperatures, from below freezing to near blood heat. In the tropics, far higher temperatures are commonplace, but in high latitudes or elevations, deep-freeze conditions can keep decomposition at bay indefinitely, as in the case of modern discoveries of pre-historic mammoths and medieval Esquimaux. It is therefore futile to attempt to construct a timetable for the stages of decomposition, except to point out salient markers for an undisturbed body in an ‘average’ indoor environment of about 18°C in temperate climates. From this approximate baseline the pathologist must then extrapolate for local variations appropriate to his climatic and geographical conditions.

Sequence of putrefactive changes

Whatever the time scale, the general order of corruption is similar, though the degree of advancement may vary between different areas of even the same corpse (Fig. 2.10).

Usually the first external naked-eye sign is discolouration of the lower abdominal wall, most often in the right iliac fossa where the bacteria-laden caecum lies fairly superficially. Direct spread of organisms from the bowel into the tissues of the abdominal wall breaks down haemoglobin into sulphaemoglobin and other pigmented substances. This discolouration spreads progressively over the abdomen, which in the later phase begins to become distended with gas.

At about this time, more generalized spread of bacteria begins to discolour the more moist tissues, which often comprise those dependent areas that show hypostatic colouration and oedema. The face and neck become reddish, and begin to swell. The putrefactive bacteria, which largely originate in the intestines and lungs, spread most easily in fluid so they tend to colonize the venous system, haemolysing the blood that stains the vessel walls and adjacent tissues. This gives rise to ‘marbling’, a branching outline of arborescent red, then greenish pattern in the skin, seen most clearly on the thighs, sides of the abdomen, and chest and shoulders (Fig. 2.11). This stage may be about 1 week in the ‘baseline’ timetable, where the corpse is in air at 18–20°C.



Figure 2.10 Post-mortem decomposition showing varying degrees of putrefactive changes in the face, trunk and extremities. The illustration shows the contrast sometimes seen between one part of the body and another, as the right leg and lower left side of the trunk are only slightly affected. The face, neck and hands are swollen with gas.



Figure 2.11 Post-mortem decomposition of about 2 weeks’ duration in water in a summer temperature. There is ‘marbling’ of the skin where breakdown products of haemoglobin have stained the venous channels.

At or even before the stage of marbling, skin blisters may appear, at first on the lower surfaces of trunk and thighs where hypostatic oedema has loaded the tissues with fluid. The upper epidermis becomes loosened, the so-called 'skin-slippage' giving rise to large, fragile sacs of clear, pink or red serous fluid. These may become so large that they are pendulous and soon burst, leaving areas of slimy, pink epidermis. Where this skin change occurs in hairy parts, such as scalp, axilla and pubis, the hair becomes detached and will slide off on slight pressure. Gas formation will now become marked, with increased tension in the abdomen.

The scrotum and penis may swell up to remarkable size and the neck and face will become grotesquely bloated, making visual identification difficult or impossible. The pressure may cause the eye globes and tongue to protrude (Figs 2.9, 2.12).

Purging of urine and faeces may occur due to the intra-abdominal pressure and, occasionally, a uterine prolapse may be extruded. There are recorded instances of pregnant females having a macabre post-mortem 'delivery' of the fetus, from the same cause. Bloody fluid, which is tissue liquefaction stained by haemolysis, may leak from any orifice, especially the mouth, nostrils, rectum and vagina. By this stage, some 2–3 weeks may have elapsed since death.

To the inexperienced, this may suggest evidence of some lethal haemorrhage and many pathologists have been called to a scene of 'crime' because of the understandable concern of an investigating police officer that such bloody purging may be evidence of a violent mode of death. Pressure inside the chest due to gas formation in the abdomen may expel air, so that the fluids of decomposition in the trachea and bronchi may be blown into a bloody froth from the mouth and nostrils.

After several weeks, the reddish-green colour of the skin may deepen to a dark green or almost black, but there is marked variation in this aspect. Heavy maggot infestation will almost certainly have supervened except in winter conditions, and the destruction of skin by innumerable maggot holes and sinuses gives better access to other bacteria that may invade from



Figure 2.12 Bloating of face and effusion of blood-tinged fluid from the nostrils and mouth. A body recovered from water, post-mortem time approximately 11 days.



Figure 2.13 Particular caution is advisable when dealing with heavily decomposed bodies. In (a) head of a young man infested with insect larvae, which (b) may disguise real pellet or bullet holes or create an illusion of them. In (c) entrance wound from a 6.35 cal. pistol detected in the forehead of a decomposed body after the scalp tissues had been reflected forward. Therefore, an external examination alone is never sufficient and a full autopsy is necessary.

the environment. The maggots secrete a proteolytic enzyme that speeds up the destruction of the tissues, in addition to the direct loss from the voracious appetites of these predators (Figs 2.13, 2.14). Skin slippage causes shedding of the outer layers of the fingers and toes, making identification by fingerprints more difficult. Finger- and toenails last longer than the surrounding skin, but they too become loose and eventually fall out. Skin slippage may allow tattoos to become more visible and colourful for a time until the moist underlying dermis itself decomposes.

Internally, decomposition proceeds more slowly than at the surface. It is often quite surprising how valuable an autopsy on a putrefying corpse can be, as the internal organs may be in far better condition than the exterior would suggest. Organs putrefy at markedly different rates. The lining of the intestine, the adrenal medulla and the pancreas autolyse within hours of death, yet the prostate and uterus may still be recognizable in a partially skeletalized body a year later. The brain soon becomes discoloured, being a soft pinkish-grey within a week and liquefying within a month. Meningeal haemorrhage and haematomata persist well, but apart from some tumours, non-haemorrhagic lesions in the brain substance vanish quite early.

The heart is moderately resistant, and examination of the coronary arteries for the degree of atheromatous stenosis may be well worthwhile for many months, though staining of the vessel walls by haemolysis makes recognition of mural thrombosis difficult. Complete occlusion by firm ante-mortem thrombus persists well. The heart may show a curious white granularity on the epicardial and endocardial surfaces, seen either during putrefaction or even on exhumation after a long interval. The nodules are a millimetre or less in size and are often called ‘miliary plaques’. They were investigated by Gonzales *et al.* who found that microscopically they consisted of calcium and soapy material.[33] The origin is obscure, but they seem to be confined to the heart and to be some degenerative product of the cardiac tissue.



Figure 2.14 Almost complete destruction of the facial soft tissues by maggots. Post-mortem time about 2 weeks in a centrally-heated apartment.

In obese people, the body fat (especially perirenal, omental and mesenteric) may liquefy into a translucent, yellow fluid that fills the body cavities between the organs, and makes autopsy even more difficult and unpleasant.

Later putrefactive changes lead to the breakdown of the thoracic and abdominal walls, often hastened by the perforations of maggots and sometimes larger predators, such as rats and dogs. In some tropical countries, such as India and Sri Lanka, bodies left in the open are attacked by many animals, including monitor lizards, and in other parts of the world the indigenous fauna all contribute to the natural cycle that returns the body fats and proteins to the food chain.

After several months, the softer tissues and viscera progressively disintegrate, leaving the more solid organs, such as uterus, heart and prostate, together with the ligamentous and tendinous tissues attached to the skeleton. Often some areas of skin persist, especially where protected by clothing or under the body against the supporting surface. Much depends upon the environment, as a corpse in the open air will suffer far more from rain, wind and especially animal predators, compared with one in a locked room.

Eventually, the body will be reduced to a skeleton, but for some time, ligaments, cartilage and periosteal tags will survive. The season of year and the location will make a great difference to the time scale of skeletalization: a body dying outdoors in the late autumn will ‘survive’ longer through the cold winter and spring than one dying in the early summer. The effects of animal predators are profound in terms of removing soft tissues from the bones. In broad terms, a corpse outdoors in a temperate climate is likely to be converted to a skeleton carrying tendon tags within 12–18 months, and to a ‘bare-bone’ skeleton within 3 years; there are, of course, numerous exceptions, depending mainly on the local environment. In closed conditions indoors, a body may never skeletalize, often being converted to a dried, partly putrefied, partly mummified shell (Fig. 2.15).



Figure 2.15 Maggot-infested body cavity with complete destruction of the internal organs.



Figure 2.16 A body recovered from the Baltic Sea with numerous superficial skin defects on the face and neck due to post-mortem predation, probably by the crustacean *Saduria entomon*, shown in the inserted picture with a smaller shrimp in the middle.

Decomposition in immersed bodies

The old rule-of-thumb that bodies decay twice as fast in air as in water is grossly inaccurate, but emphasizes the slower rate of decomposition of immersed corpses. Though in mortuary practice ‘drowners’ are generally regarded as being the major source of offensively rotten bodies, this is usually because discovery and recovery is far later than in deaths on dry land. Water, in fact, slows up putrefaction, mainly because of the lower ambient temperature, and protection from insect and small mammal predators (Figs 2.16, 2.17).

The water also affects the usual processes of decay in that the epidermis becomes macerated and eventually detached, as described in the Chapter 16. Gas formation is the reason for the inevitable flotation of an unweighted body, though the time of reappearance at the surface is extremely variable and certainly does not follow the speculative timetable of the older textbooks. The usual posture of a freely floating body is face down, as the head is relatively dense, and does not develop the early gas formation in the abdomen and thorax. This lower position favours fluid gravitation and hence more marked decomposition, so that the face is often badly putrefied in an immersed body, making visual recognition difficult or impossible at an early stage. As stated, temperature is the major determinant of the rate of putrefaction. Though it is usually claimed that the nature of the water in respect of sewage, for instance, is important, it is a minor factor as most of the micro-organisms responsible for decay come from the alimentary canal and respiratory passages of the body itself.



Figure 2.17 Marine predation in a body after 3 months in the North Sea. The victim was from an oil rig and had floated on the surface in a life jacket. Much of the skin has been removed by crustaceans, and the arm muscles by larger fish who have cleaned out most of the body cavity.

Decomposition in buried bodies

The rate of decay of bodies buried in earth is much slower than of those in either air or water. In fact the process of putrefaction may be arrested to a remarkable degree in certain conditions, allowing exhumations several years later to be of considerable value. In this respect the prospect of an exhumation should never be dismissed on the grounds that because of the lapse of time, it is bound to be worthless. It may turn out to be of little value, but this cannot be anticipated, and not infrequently the condition of the body may be surprisingly good.

The speed and extent of decay in interred corpses depends on a number of factors. If the body is buried soon after death, before the usual process of decay in air begins, putrefaction is less and may never proceed to the liquefying corruption usually inevitable on the surface. A lower temperature, exclusion of animal and insect predators, and lack of oxygen are important factors. Although most bacteria originate in the intestine, there is less access for secondary invaders and the restriction of oxygen inhibits aerobic organisms. If the body is rotting before burial then, although the process slows down, it will still severely damage the corpse, as enzymatic and bacterial growth have had initial encouragement from a higher ambient temperature and free access of air, thereby producing conditions in which secondary invaders (including anaerobes) can continue their work in a good culture medium that is already partly liquefied by the earlier stages.

Deep burial, as in the usual cemetery interment, preserves the corpse better than the shallow grave seen in some concealed homicides. The deep burial is colder (except in extremely cold weather), it excludes air better and, unless waterlogged, is not directly affected by rain.

The nature of the soil is not directly relevant except in its drainage and aeration properties. Heavy clay will exclude air and, if well above the water table, will exclude percolating surface water. By contrast, light sandy soil may allow access of both air and rainwater, but will drain more effectively. The soil factor is less important than the topography in which it lies – in a valley floor or below the water table, waterlogging is inevitable, but on a well-drained hillside the grave may remain relatively dry.

Another factor that aids the preservation of legitimately buried corpses is the coffin. Though modern coffins are often of wooden laminate or chipboard, which rapidly disintegrates when wet, any kind of coffin helps to exclude water and air for a time. A substantial, sound jointed coffin may last for years and the modern rarity of a sealed metal liner can keep a body in an excellent state of preservation for a long time.

A major factor that helps to slow decomposition is, of course, the absence of animal predation in burials. Again, if a corpse is buried before insect eggs are laid, the profound effect of maggot infestation is avoided. Rodents and larger mammals can only reach shallow burials, and in deep interments the coffin has to be breached before even the limited fauna of that stratum can gain access.

As in all putrefaction, it is unrealistic to try to construct a timetable for the stages of decay in burials. The permutations of factors mentioned above make it impossible, especially where adipocere formation takes place, as described below. The author (BK) has exhumed a chapel cemetery in the waterlogged peat of a Welsh valley and found not a trace of body, even skeleton, in graves with headstones confirming death only 20 years previously. By contrast, other bodies elsewhere were perfectly recognizable – and a standard autopsy could be carried out – 1.5 years after death.



Figure 2.18 Advanced adipocere formation after 2.5 years in a grave. Exhumation due to exclusion of an accidental death (fall) in a bathtub.

When bodies are buried in coffins in vaults, rather than in earth, then again there can be a variable rate of decay. Some bodies may develop adipocere, others may wholly or partly mummify (Fig. 2.18).

There are many publications on this subject, mainly derived from the examination of historical sites or church crypts that have had to be cleared. The subject is of considerable interest but of limited forensic relevance.

Formation of adipocere

An important and relatively common post-mortem change is the formation of adipocere (lat. *Adeps* = fat, and *cera* = wax), a waxy substance derived from the body fat. The name was given to it by Fourcroy having observed this substance when the Cimetiére des Innocents in Paris was cleaned out from bodies in 1786. He presented his observations to the Royal Academy of Sciences of Paris and has therefore often been credited as the first scientific discoverer of this phenomenon.[34] However, it must have been known to grave-diggers from ancient times and it has been shown that already Sir Thomas Browne (1605–1682) described adipocere and gave a hypothesis of its formation in his

Hydriotaphia published in 1658.[35] Another early but not as accurate a reference was made by Francis Bacon (1561–1626) in his posthumously published book *Sylva Sylvarum: or A Natural History, in Ten Centuries*.[36] An excellent review about what is known after over two centuries of adipocere research has recently been published by Ubelaker and Zarenko.[37]

In most instances the change of adipocere is partial and irregular, though occasionally almost the whole body may be affected. In small amounts, adipocere is more common than usually thought in buried or concealed corpses. It is caused by hydrolysis and hydrogenation of adipose tissue, leading to the formation of a greasy or waxy substance if of recent origin. After months or years have passed, adipocere becomes brittle and chalky. The colour can vary from dead white, through pinkish, to a grey or greenish-grey. The substance itself is off-white, but staining with blood or products of decomposition can give it the red or greenish hues. The smell was accurately described by Evans as being 'earthy, cheesy and ammoniacal'.[38]

The chemistry of adipocere has been studied extensively. It contains palmitic, oleic and stearic fatty acids together with some glycerol, though the latter may have been leached out in older adipocere. These form a matrix for remnants of tissue fibres, nerves and muscles, which give some slight strength to the fats.[24] Crystals with radial markings can be found in the adipocere. Body fat at the time of death contains only about 0.5 per cent of fatty acids, but in adipocere, this may rise to 20 per cent within a month and more than 70 per cent in 3 months.

The formation of adipocere, as an alternative to total putrefaction, requires certain environmental conditions. A body left exposed in air, unless the conditions are conducive to mummification, will undergo moist putrefaction if the temperature remains above about 5–8°C. In burials, immersion in water and in incarceration in vaults and crypts, adipocere often forms to a greater or lesser extent (Figs 2.19, 2.20).

It is usually taught that moisture is necessary for the process, and it is undoubtedly a fact that most adipocere formation occurs in immersed bodies and those in wet graves and damp vaults. Numerous cases have been described, however, in which dry concealment also led to adipocere formation and here it must be assumed that the original internal body water was sufficient for the hydrolysis to proceed.

It is said that some warmth is necessary for adipocere formation, but the process seems to occur even in deep graves and in cold water. Early activity by anaerobes such as *Clostridium perfringens* assist in the reaction, as the bacteria produce lecithinase, which facilitates hydrolysis and hydrogenation.[23] Such bacteria need some warmth in the initial stages to reproduce and metabolize and Mant suggests that rapid cooling soon after death, such as by immersion in water, may actually retard the formation of adipocere.



Figure 2.19 Adipocere formation in a body after 3 months in the sea. Subcutaneous fat has been released from crustacean bites on the skin and has been converted into adipocere, which has been rolled by wave action within the clothing to form ovoid masses.



Figure 2.20 Complete conversion of a body to adipocere. The body was recovered from a deep lake 8 years after disappearing in a boating accident during a heavy storm.

The frequency with which adipocere forms may be gauged by the observations of those who have exhumed old cemeteries and vaults, as well as the victims of wartime slaughter.[23,38–40] Evans found that over half (56 per cent) of the occupants of dry vaults had some adipocere. It was present in 62.2 per cent of females and 45.4 per cent of males.

The importance of adipocere formation

The process is more than a biochemical curiosity as, once it is formed, adipocere may persist for decades or even centuries. The usual dissolution of putrefaction is replaced by a permanent firm cast of the fatty tissues and, although distorted compared to the immediate post-mortem shape, it allows the form of the body and sometimes even of the facial features to be retained in recognizable form. Injuries, especially bullet holes, may be preserved in a remarkable fashion.[23] Though adipocere mainly affects the subcutaneous fat, it may also preserve the omental, mesenteric and perirenal adipose deposits; in addition, organs containing fat through pathological or degenerative processes may be preserved by adipocere forming in their parenchyma.

The time required for the production of adipocere has been a matter of controversy. The old authors claimed that 3–12 months were required, and Casper suggested 6 months, but it is obvious that the process can occur much faster than this.[41]

There seems little reason to doubt that hydrolysis of body fat begins soon after death, as crystals of fatty acids have been found in infant bodies lying in water for only a week. This process is usually overtaken by liquefying putrefaction, however, which allows the fat, especially in obese persons, to collect as extracellular pools and pockets of triglycerides in the body cavities.

If the putrefactive process is slowed by burial or immersion, then hydrolysis and hydrogenation can outpace putrefaction. In addition, adipocere formation actually inhibits putrefaction, as the increasing acidity of tissues and the dehydration caused by the consumption of water in hydrolysis slow the growth and spread of the usual putrefactive organisms. The point at which adipocere becomes visible to the naked eye varies greatly, but it has been observed as early as 3 weeks, though 3 months is a more typical period. Adipocere is often mixed with the other forms of decomposition. Even within a coffin or other place of sequestration, there may be several different 'mini-environments'. One end of the body may be putrefied or skeletalized, whilst other parts may be mummified or in adipocere. Certain areas tend to develop adipocere, such as the cheeks, orbits, chest, abdominal wall and buttocks. Only rarely is the face preserved well enough by adipocere to be genuinely recognizable, as disintegration of the eye globes and shrinkage of the tissues around the nose and mouth obscure the most characteristic features.

Mummification

The third type of long-term change after death is mummification, a drying of the tissues in place of liquefying putrefaction. Like the other modes of decomposition, this can be partial and can coexist with them in different areas of the same body. It is, however, more likely than the others to extend over the whole corpse.

Mummification can only occur in a dry environment, which is usually, but not exclusively, also a warm place. Mummification can occur in freezing conditions, partly because of the dryness of the air and partly because of the inhibition of bacterial growth. The most widely known forms of mummification are those in hot, desert zones. The process of artificial mummification practised for millennia in Egypt was an imitative process founded on the natural mummification of bodies in pre-dynastic times. The essential requirement for mummification is a dry environment, preferably with a moving air current. If sterility of the tissues can be attained, as in a newborn baby, then putrefaction is held at bay while drying occurs. The appearances of mummification display desiccation and brittleness of the skin, which is stretched tightly across anatomical prominences such as the cheekbones, chin, costal margin and hips. The skin is discoloured (usually being brown), though secondary colonization by moulds may add patches of white, green or black (Figs 2.21, 2.22).

The skin and underlying tissues are hard, making autopsy dissection difficult. The condition of the internal organs is variable, depending partly on the length of time since death. They may be partly dried,



Figure 2.21 Mummification in a male dead in a locked room for 10 weeks. The corpse is dry and leathery, with very little moist putrefaction.



Figure 2.22 The mummified body of an absconder from a mental hospital who was found a year later in a hay barn. The dry environment had inhibited wet decomposition.

partly putrefied – and adipocere is not uncommon. In fact, slight adipocere formation is common in mummification, and perhaps the two are related in that the utilization of body water to hydrolyse fat in turn helps to dehydrate the tissues. The major factor, however, is evaporation from the surface in dry conditions.

Like adipocere, facial recognition may be possible in some instances, though the shrunken distortion and loss of eyes and full lips considerably alter the features. Mummification is likely to occur in temperate climates when the body is left undisturbed in a dry, warm place. These include closed rooms and cupboards, haylofts, attics and beneath floorboards. Because concealment favours mummification, a number of these bodies are hidden homicides – one of the best known being the 'Rhyl mummy' in North Wales, when a strangled female was concealed in a cupboard for many years, whilst her pension continued to be claimed.[42] Other instances are where a natural death has been concealed for some purpose. The author (BK) has also seen two deaths in hay barns, where the corpses were undisturbed for over a year.

Most experienced forensic pathologists are familiar with the mummified fetus or newborn infant, concealed in domestic circumstances, such as a house loft, where complete mummification has taken place. With small bodies such as these, evaporation is faster and more complete, and may extend to all organs, especially as there would have been no invasion of putrefactive micro-organisms from the gut.

The timing of mummification is not well documented, as most mummified corpses have been concealed so well that discovery does not occur until long after the process has reached its maximum effect. It certainly takes some weeks and the early stages are often mixed with a degree of putrefactive change, especially in the internal organs.

After complete drying has taken place, the body may remain in that state for many years. Eventually, mould formation and physical deterioration progress, the dried tissues becoming split and powdery and gradually disintegrating. This process is usually hastened by animal predation. Even in the shelter of a barn or house, moths, beetles, mice and rats will wreak damage on the corpse. It will eventually skeletalize, though tough, leathery shreds of skin, tendon and ligament may persist for many years. Mummification allows major injuries to be preserved, though as in the putrefied body, the detection of bruises and abrasion may be difficult or impossible to differentiate from discolouration, artefacts and fungal damage. The stiff tissues can be softened for better examination and histology, by soaking in a 15 per cent solution of glycerine for several days (see Evans).[43]

Post-mortem damage by predators

Animal predation is part of the natural food chain, which returns the proteins, fats and carbohydrates of dead bodies to other animals, some of it passing back to the vegetable kingdom through soil nutrition. All types and sizes of animal are involved, the largest seen by the author (BK) being a 'near-miss' by a Malayan tiger, who dragged a sleeping soldier from his tent. Most animal damage is more mundane, the beasts varying from ants to foxes, and from bluebottles to monitor lizards. Foxes can drag parts of a body away to a distance of at least 2 miles.

The type of predation varies greatly with geography, season and whether the dead body is indoors or out in the open. If it is lying in the countryside, large predators will cause prompt and severe damage, even complete destruction being possible in a short time. In temperate countries, foxes and dogs form the main agents, and the body may be dismembered and scattered over a wide area, especially if advancing putrefaction makes disarticulation easy. If corpses are in inland waters, damage from water rats and fish is possible, as well as attacks from dogs and foxes if the body lies exposed on the bank of a river or a lake.

The type of damage from canine and rodent predators is usually obvious, as the local removal of large amounts of flesh is usually accompanied by



Figure 2.23 Post-mortem rat bite of the orbit. Such injuries are – not unnaturally – often regarded with suspicion by the police. The complete absence of bleeding or reddening of the wound margins, as well as the unlikely shape and situation of the injury, make its post-mortem origin obvious.



Figure 2.24 Loss of all soft tissues of head and neck, in areas not covered by clothing, by post-mortem animal predation.

evidence of teeth marks (Fig. 2.24). Rats and cats leave a crenated edge to fairly clean-cut wounds, the post-mortem nature of which is obvious from the lack of bleeding or an inflamed marginal zone (Fig. 2.23). Mice rarely attack bodies, but may help to remove the dried, crumbling tissue of a mummified corpse.

The most active tissue removers are maggots, the larval stage of bluebottles (*Calliphora*) and flies (*Musca*). The use of the life cycle in timing death is dealt with elsewhere, but here we are concerned with their destructive effects on corpses. In temperate zones their activity is seasonal, but in hot countries their predatory work is ever present. The adult insects lay eggs on the fresh corpse (or even on a debilitated live victim), choosing wounds or moist areas such as the eyelids, lips, nostrils and genitalia. Once skin decomposition begins, the eggs can be deposited anywhere. The eggs hatch in a day or so, and several cycles of maggot develop, shedding their cases at intervals, depending on the species.

The maggots are voracious and energetic, first exploring the natural passages, such as mouth and nostrils, then burrowing into the tissues. They secrete digestive fluids with proteolytic enzymes that help soften the tissues, burrowing beneath the skin, and making tunnels and sinuses that hasten putrefaction by admitting air and access to external micro-organisms. Successive waves of eggs are laid, producing new generations of maggots. Eventually, loss of tissue and drying make the host cadaver unattractive to egg-laying insects, and the later stages of decomposition become free from maggots.

Beetles and many other types of insect and arthropod join in the destruction, but one particular insect must be mentioned. This is the ant, which can attack the body soon after death before putrefaction begins. A common place for ant attack is around the eyelids, lips and on the knuckles. The lesions are superficial ulcers with scalloped, serpiginous margins. They can be mistaken for ante-mortem abrasions, but their position, margins and lack of bleeding or inflammatory changes usually make them easily recognizable. Shapiro, however, has documented cases where extensive linear ant lesions have resembled ligature abrasions around the neck.[44]

Tropical ants can devour tissues to a considerable extent and, although stories of soldier ants reducing horses to skeletons within minutes are apocryphal, predation by large numbers of insects can be extensive.

In water, all manner of aquatic animals can mutilate immersed bodies, as well as land mammals if the corpse is in shallow water or grounded on a mudbank or the beach. Large fish can be totally destructive, especially in tropical waters, but even in temperate seas severe damage can occur. Some of the victims of the Air India aircraft disaster near Ireland in 1985 were ravaged by sharks. Large gouges from the wound edges, punctures from teeth and extensive tissue loss, even fractures of large bones such as the femur, characterize shark attacks.[45–49]

Smaller fish can wreak severe damage, the prime example being piranhas, though many species will devour both fresh and decomposing bodies. Crustaceans are also predatory and can remove circular areas of skin to expose the subcutaneous fat, which may detach inside the clothing to form masses of adipocere. Birds also cause damage, usually to the dead, though crows may mutilate live lambs. The habits of carrion birds, such as the vulture, are well known, but smaller birds will inflict injury on exposed bodies, especially when putrefaction softens the tissues.

All animal predation varies in appearance according to the size and shape of the teeth or jaws of the predator, but all such post-mortem injuries have features in common. There is no bleeding apart from the minute quantity actually in the vessels of the damaged part, and certainly no active haemorrhage into the wound margins. Naturally, there is no oedema or reddening of the edges as might be seen in an ante-mortem wound earlier than the perimortal period. Crenation of the edges is a useful guide where small rodents or other animals are involved, though large carnivores can make totally irregular tears in the tissue. Some animals, such as dogs and foxes, may leave punctured wounds adjacent to the damaged edge where sharp teeth have penetrated. On bones, the incisor teeth of rodents and larger carnivores can leave parallel gouges, which must not be mistaken for illicit human activities. In domestic surroundings, pets may inflict drastic post-mortem injuries if they are locked in with a dead person. Dogs and cats can cause injuries that puzzle those, such as the police, who are unaware of the possibility. Complete decapitation by Alsatian dogs has been seen by both of the authors, as well as genital injury.[50]

The entomology of the dead and post-mortem interval

This is a highly specialized subject and, when the issue of time since death is important, such as a criminal investigation, it is essential that, wherever possible, the pathologist has the assistance of an entomologist with forensic experience. As in forensic toxicology and serology when serious medico-legal issues are at stake, there is no place in forensic entomology for the ‘occasional expert’ who dabbles in the subject when the opportunity arises. Having said this, it is helpful to know sufficient about the topic to recognize when expert help is required, and to understand what information and specimens need to be obtained.

The rationale of forensic entomology is that after death invasion of an unprotected body by sarcosaprophagous insects and other small fauna comes in successive waves. Different species of arthropods colonize the corpse at different periods after death. In addition, some species (including the most common blowflies) pass through complex life cycles that can be used to determine at least the minimum time since death by studying the stage of the life cycle of the insects. The science is inexact and is modified by a number of factors, both climatic and geographical, but in expert hands can sometimes yield useful information about the date of death at a period when other indicators have ceased to function. These methods have been used since the middle of the eighteenth century, but Megnin placed forensic entomology on a sound basis with his publication of *La faune des cadavres* in 1894.[51] There are now a substantial number of publications on the subject, though most of them need specialist zoological knowledge for the interpretation of the species involved and their complicated life cycles. It is essential that the entomologist has the fullest possible information about the nature of the environment in which the body was found and, if possible, he should visit the scene himself. It is also vital to have accurate data on the weather, especially the ambient temperature of the area during the period in which the body had been lying there, as the maturation times of insects (e.g. blowflies) are markedly altered by climatic conditions.

The most common insects found on relatively fresh corpses are blowflies (order Diptera, family Calliphoridae). They mainly comprise the bluebottles (*Calliphora*) and the greenbottles (*Lucilia*) (Figs 2.25, 2.26). Fleshflies (Diptera: Sarcophagidae) and houseflies (Diptera: Muscidae) may also be encountered in large numbers. There are numerous species of sarcosaprophagous flies, with variations in life cycles that are altered by climatic conditions. The bluebottles (genus *Calliphora*) are common, e.g. *Calliphora vicina* Robineau–Desvoidy (*Calliphora erythrocephala* Meigen), one of the most frequent invaders of dead flesh. These are large, bristly flies about 6–14 mm long, with iridescent blue abdomens.



Figure 2.25 Blowfly (*Cynomya mortuorum*). (Reproduced by kind permission of Adjunct Professor, Dr. I. E. Sääksjärvi, Department of Biology, University of Turku.)



Figure 2.26 Greenbottle (*Lucilia*). (Reproduced by kind permission of Adjunct Professor, Dr. I. E. Sääksjärvi, Department of Biology, University of Turku.)

They do not fly in the dark in natural conditions, though may possibly fly in artificial light, for instance in the vicinity of buildings, and thus eggs are usually laid only in daylight. This means that a corpse found at night or early in the morning with eggs upon it, almost certainly died the previous day. Bluebottles rarely fly in winter, but may do on fine days, though when the temperature is below 12°C they are unlikely to lay eggs. Rain is also a marked deterrent to egg-laying, except in the case of the Sarcophagidae, which larviposit, i.e. bear and deposit living larvae instead of eggs. Bluebottles prefer fresh rather than decayed carrion and lay their eggs soon after death, which may be of medico-legal significance. Indeed, they may lay eggs on the living (myiasis), especially when the victim (human or animal) is debilitated or wounded. A single bluebottle may lay 300–2000 eggs in clusters of 30–150. The eggs are laid on moist areas, such as the eyelids, canthi of the eyes, nostrils, lips, mouth, genitals and anus. If there are any open wounds or weeping abrasions, these may also be colonized. The eggs are yellow and banana-shaped, about 1.7 mm in length.

The many tables and diagrams available for the succession and life cycle durations of sarcosaprophagous insects on corpses must be read in the knowledge that the environment, especially the temperature, makes a marked difference to the time span of the larval and pupal stages. As Nuorteva *et al.* state:

> Crimes do not occur under experimental conditions and standardized food supplies. Flies, as medico-legal indicators, must therefore be used in conjunction with the records of meteorological conditions existing at the time subsequent to the presumed crime.[52]


ex. bodies of Ruxton's victims,
Maggots from bodies of Ruxton's victims, 1935
Moffat murder.
(new 70% Alc., 1961)

Figure 2.27 In 1935, the remains of two human bodies infested by blowfly larvae, and identified as belonging to the wife and the maid of Dr. Buck Ruxton, were found in Dumfriesshire, Scotland. This case was the first in which insect evidence succesfully contributed to a murder investigation in the UK. The vial and the tube contain some of the blowfly larvae collected from the remains of the victims of Dr. Ruxton. (Reproduced by kind permission of the Natural History Museum©, London [Martin Hall].)

Thus the following examples, mainly taken from Glaister and Brash's account of the notorious Ruxton murder, must be read with this caution firmly in mind – and wherever possible, the pathologist must enlist the aid of an experienced entomologist (Fig. 2.27).[53]

Adult bluebottles will begin to lay eggs about 4–5 days after emergence from pupa. Eggs will not hatch at temperatures below 4°C, but they will develop at 6–7°C. The time from laying to hatching is 8–14 hours, depending on the temperature.

The first maggot stage (first 'instar') tries to penetrate the tissues or enter any nearby body cavity such as the mouth or wounds. Maggots have powerful proteolytic enzymes that aid dissolution of the tissues and facilitate penetration. The first larval instar persists for another 8–14 hours, then the outer skin is shed and the second larger instar feeds for another 2–3 days.

After a final moult, the third instar spends about 6 days on the body before leaving it to migrate some distance to hide in the ground or under some other cover (even a carpet) to pupate (only a very few species pupate on the corpse) (Fig. 2.28). The pupa is a dark brown (younger pupae are paler) leathery capsule in which the insect metamorphoses into the winged fly after about 12 days. The new bluebottle emerges and



Figure 2.28 Maggots of the third instar that have left the body to pupate. Dark brown and paler (younger) blowfly pupae (*Protophormia terranovae*).



Figure 2.29 Mummified body of an elderly male that had been lying dead in a block of flats for about 2 months in temperate climate in summer time. There are a few maggots of different stage and the head is covered with a thick layer of pupae.

leaves the empty pupa case behind, ready to begin the cycle over again, which thus lasts about 18–24 days from egg to adult (Fig. 2.29). The greenbottle (e.g. *Lucilia caesar*) and the sheep maggot fly (*Lucilia sericata*) have life histories that are similar to that of the bluebottle.

The common house fly (*Musca domestica*) is different in that, unlike the bluebottles, it prefers to lay its eggs on already decomposed flesh, though it is more attracted to garbage and manure than to cadavers. The eggs are much smaller and white rather than yellow. Hatching time is 8–12 hours, the first instar at about 36 hours, the second instar at 1–2 days and the third at about 3–4 days. Pupation lasts up to 7 days, less in warm weather. The whole cycle is thus about 14 days at about 22°C, though again it must be emphasized that variations in ambient temperature make considerable differences to the speed of maturation. A table by Busvine shows that the total cycle length varies from 9 days at 40°C to 32 days at 16°C.[54]

Entomologists have constructed tables of variation in larval length according to age and temperature; expert knowledge and strict identification of the species is needed before definite opinions upon minimum times since cadaver death are offered. Some of the times quoted above were taken from the extensive entomological work performed on the Ruxton case in 1935, but do not correspond to the cycle periods published by Kamal.[55] The total maturation times that he found in experimental conditions at 22°C are much longer, being 14–25 days (average 18) for *Calliphora vicina*. One should always remember that the insect life cycle durations depend a lot on the environmental conditions and geographical location of the corpse (e.g. south European forensic entomological data may not be applicable in northern Europe, even in the case of the same species).

In many of the published cases where *Calliphora* have assisted in the estimate of the time since death, it is an assessment of the age of larvae that is made from their size. Of course this can only be a minimum estimate, especially if mixed generations are present as a result of successive waves of flies laying eggs at different times. As already said, however, bluebottles do not favour decomposed tissue for oviposition, so egg-laying is likely to cease within a couple of days of death. If pupa cases are seen either on or near the body, then any larvae present may be from later waves – even second- or third-generation insects.

In addition to maggots on the body, other fauna in the soil beneath a corpse leave the area and a reduction in the number of species of normal soil arthropods may be a marker for the site of a body, even for some time after the latter has been removed. The minimum number of arthropods under a corpse is reached after about 2 months; it then revives, but with quite a different range of species from the original inhabitants. The absence of eggs or maggots on a body may sometimes be of use, as it may indicate that a body has been in a sheltered place inaccessible to flies, even if it was later moved out. Where a body has been buried, even a shallow covering of soil may protect it from blowfly oviposition; where part of the body protrudes, this may well be the focus of maggot infestation.

Different types of insects invade the body after the moist, putrefaction stage that is associated with blowfly maggots has passed. At different seasons, different


FLIR
41
25
Trefl=20 Tatm=20 Dst=2.0 FOV 24
20/07/08 22:30:01 -40 - +120 e=0.96
°C

Figure 2.30 The growth of the larval masses is associated with substantial heat production. Infrared thermal image of human body showing increased temperatures at sites of larval masses, i.e. on the head, the anogenital region and the body–soil interface. (Reproduced by kind permission of the Natural History Museum©, London [Amoret Whitaker and Martin Hall].)

insects may be prevalent so that the finding of say, *Phoridae* and *Sphaeroceridae* in Europe would suggest that the body had been there in the summer months. Larder beetles (*Coleoptera*: Dermestidae) may arrive 3–6 months after death; house moths may attack dried tissues such as mummies and can dispose of keratin such as hair and beard. Beetles (*Coleoptera*) are late arrivals and are usually found in dried or adipocerous corpses. These and many more are related more to season than time, so again the considered opinion of an expert is necessary. The absence of insects in certain climates may indicate that death took place in the winter months when no active colonization was occurring.

Collection of material for entomological study

To the practising forensic pathologist, the main concern in this context is the careful collection and dispatch of specimens to an entomologist with forensic experience.

First, the entomologist needs to know all available facts about the environment in which the body was found – preferably he should visit the locus himself if the matter is of legal importance. He should be told the temperature of the maggot mass and ambient temperature around the time the body was found (Fig. 2.30). If no actual temperature measurements were taken by the pathologist at the scene – and even if they were – local records should be obtained from the nearest meteorological centre. Without this information the probable life cycle duration cannot be estimated well. The nature of the locus should be described, in terms of vegetation, trees and undergrowth if outdoors. Where maggots are present, some should be placed live in a large tube or a jar and, if there is delay in transit to the entomology laboratory, a fragment of meat should be included for food. Eggs and pupae should also be collected without preservative. Any adult flies, other insects and empty pupae may be stored in alcohol.

In addition, some maggots (representing different sizes) should be sent after fixation. They can be placed directly into 80 per cent alcohol, but preferably in three parts 80 per cent alcohol with one part glacial acetic acid. Even better is Pimple's fluid, which is six parts 35 per cent formalin, two parts glacial acetic acid, 15 parts 95 per cent alcohol and 30 parts water. Formol saline 10 per cent (as used for histological fixation) should not be used. Larvae may also be dipped briefly into hot water (not boiling) for fixation. The fixation preserves the actual size of the larvae.

If there are different insects on the body, they should be placed in separate tubes – especially if they are alive – as some may devour the others before they reach the laboratory. Also, larvae and other insects collected from different body parts should be placed separately.

Whatever is sent should be labelled or numbered according to a key that records where on the body they were found. If outdoors, the soil beneath the body should be sampled and, where a full cycle has occurred, pupae or cases should be obtained by shallow trenching in radii around the body. One should also make sure that there are no other animal carcasses nearby. When the body has been recovered from water, any insects or crustaceans should be recovered. Body parasites may occasionally be useful. Fleas and lice can survive total immersion for some hours, but the advice of an entomologist should be sought if parasites are found on an immersed body to determine the minimum survival time of that particular species under the existing circumstances.

Determination of time since death

Estimation of the time since death by body cooling

Though the study of the rate of cooling of the dead human body is essentially an exercise in physiology, its potential use in determining the time since death have made it the most frequent topic for research in forensic medicine.

For more than one and a half centuries, papers have been published devoted to refining the problem further, which has obvious and important connotations in the investigation of criminal deaths. Unfortunately, the vast amount of labour in this direction has not been rewarded by comparable improvements in accuracy because of the permutations of factors that defeat exact calculation of the PMI. The history of this research is in itself extensive but a few cardinal points might be mentioned here to mark the various phases of investigation.[56]

Though the fact that a dead body becomes progressively colder after death has naturally been known since earliest times, scientific measurements were first published in the nineteenth century. Dr. John Davy recounted experiments with dead soldiers in Malta and Britain, using a mercury thermometer. Though this pioneer made no practical contribution to understanding the problem, some of his comments are remarkably pertinent across a gap of more than 150 years:

> "Much judgment, however, and nice discrimination may be requisite on the part of the medical man, in appreciating the circumstances likely to modify temperature, so as to enable him, when called on for his opinion," (of the time of death) "to give one which will be satisfactory to the legal officers, and to himself, on reflection."[57]

These cautionary words are just as applicable nowadays when, unfortunately, some doctors offer a time of death with a confidence often inversely proportional to their experience. In 1863, Taylor and Wilkes wrote a classic paper that introduced many of the current concepts, such as the initial temperature plateau, the core temperature, heat gradient and the effect of insulation.[58] Taylor was, of course, Alfred Swaine Taylor of Guy's Hospital, author of the textbook that remained the definitive work on forensic medicine for almost a century. Later in the nineteenth century, Harry Rainy (1792–1876), Chair of Medical Jurisprudence and Forensic Police, though he preferred the title Professor of Forensic Medicine of the University of Glasgow, first applied mathematical concepts to the problem and produced a formula for calculating the time of death. He also pointed out that Newton's Law of Cooling did not apply to the human body. In 1887, Frederick Womack first used centigrade units, though his use of the now familiar temperature graphs was anticipated by Burman in 1880.

In this century, the most quoted papers were those by De Saram in Ceylon (since 1972, the Democratic Socialist Republic of Sri Lanka) who published careful and detailed measurements of control cases obtained from executed prisoners.[59,60] His data are still being studied and reworked. The names Fiddes and Patten are known to all those interested in this subject as, in 1958, they produced a paper that was a classic, as Taylor's had been in the previous century.[61] Using repeated temperature measurements they devised a percentage cooling method and explored complex theoretical aspects, such as the 'infinite cylinder' model, for the human body.

Marshall and his collaborators dominated the publications in the 1960–1970 period, with papers that explored in depth the mathematical aspects and confirmed the double exponential or 'sigmoid' shape of the rectal cooling curve.[62–66] In the last few decades or so, many more papers and new techniques have been produced, with computer assistance increasingly used. Amongst these, Henssge and Madea in Germany have been predominant.[67–78] Microwave and infrared thermography have been explored and the physics and mathematics of body cooling probed in such depth that often the scientist in the research group has difficulty in explaining the concepts to his medical collaborator. In spite of all this activity, practical methods of determining the time of death continue to lack accuracy. Though some recent publications offer firm advice and describe methods, they can do no more than provide a 'time bracket' of probability within which death is thought to have occurred.

Post-mortem cooling

Except where the environmental (ambient) temperature remains at or even above 37°C, the human body will cool after death. A uniform, homogeneous laboratory 'body' will cool according to Newton's Law of Cooling, which states that the rate of cooling is proportional to the difference in temperature between the body surface and its surroundings. Graphically represented, this will display the curve of a single exponential expression, not a straight line (Fig. 2.31). A human body does not obey Newton's Law, though the size of the discrepancy varies according to several factors. When death occurs, heat transfer within the body through the circulation ceases. Metabolic heat production, occurring mainly in the muscles and liver, does not cease uniformly and some heat generation continues for a variable time. As soon as the supply of warmed blood ceases with cardiac arrest, the skin surface immediately begins to lose heat. The rate is variable because of clothing, posture and shielding against the supporting surface and, of course, the environmental temperature.



Figure 2.31 Cooling curves: the Newtonian single exponential curve (a) does not occur in practice, except on the surface of the body. Because of the variable plateau (c), the true curve for deep core temperature (b) assumes a double exponential shape.

The centre or 'core' of the body cannot begin to cool until a 'temperature gradient' is set up by the cooling at the skin surface. As the tissues are poor heat conductors, this gradient takes a variable time to become established and therefore a thermometer placed near the core (usually in the rectum) will not register a fall for some time. This is the well-known 'plateau', which forms the upper flattened or slightly sloping part of the double exponential curve when rectal temperatures are measured. If skin temperatures are used, as in some of the nineteenth century research, no plateau is found, and, using cranial temperatures taken through the nose, ear or skull, the plateau is less, as the core is nearer the surface.

The central part of the cooling curve approximates to Newtonian principles, being fairly straight or only a shallow curve. As the temperature differential between the body and environment approaches zero, the graph again flattens off into a lower shelf. Unlike the laboratory body, the human body rarely reaches the ambient temperature unless the latter is at or near freezing. This is probably because enzyme and bacterial action starts during early decomposition and, much as a compost heap warms up, the temperature may actually rise a few days after death.

The typical rectal cooling curve then, is a 'sigmoid' shape or 'double exponential' curve. The part that is of use in forensic medicine is the central section showing the steepest fall. Theoretically, if one assumes that the body temperature at the time of death was 37°C, then finding the point on this section corresponding to the measured rectal temperature should allow extrapolation back to the 37°C point which is at zero on the time scale, thus giving the PMI.

Unfortunately, a number of variables make this attractive proposition impossible to attain in practice. Not only are there variables, but the variables themselves often vary during the period before the body is discovered and examined. For example, the ambient temperature may change markedly – perhaps several times – and often this may not be known to the examiner. Even opening doors and allowing draughts to play on the body will have profound effects on the cooling curve, which cannot be detected or corrected retrospectively.

Factors affecting the cooling curve

Initial body temperature

This cannot be assumed to be 37°C and in fact is incapable of ever being measured in retrospect. Not only is there a difference between the rectal, liver, brain, axillary, mouth and skin temperatures in the living person, but the absolute values vary slightly from person to person and from time to time, even in health.

If the oral temperature is taken to be 37°C, then that in the axilla will be several degrees lower and that in the rectum at least one degree higher. There is a diurnal variation of almost 1°C, the temperature being lowest between 0200 and 0600 and highest between 1600 and 1800. Strenuous exercise raises the temperature by up to 3°C, which persists for up to 30 minutes after returning to rest.

When there is illness or trauma, much wider variations occur, which again are impossible to detect retrospectively. In febrile illness from micro-organisms or parasitic infections, the temperature may be 4 or 5°C higher. In the forensic context, infected wounds or a septic abortion are obvious examples. Cerebral (especially pontine) haemorrhage may also cause hyperthermia, as may some drug reactions. It is traditionally stated in many textbooks that asphyxia and strangulation cause agonal hyperthermia, but there is very little hard evidence for this, apart from anecdotal opinions passed from one author to another. One explanation may be that a homicide victim struggling desperately for life against strangulation will generate muscular heat as in any violent exercise, irrespective of an asphyxial mode of death.

At the other end of the scale, hypothermia is common even in temperate winters. Many victims of criminal assault may be left exposed before death and their temperature may be as much as 10°C lower than normal.

As virtually all methods and formulae for calculating the time of death depend upon the body temperature being 37°C, even a slight variation can introduce a fundamental error.

The body dimensions

The temperature gradient, which drives cooling, varies with the mass of the body and the surface area as well as with the conducting properties of the tissues. Some more complex calculations correct for mass:surface area ratio by means of nomograms (for example, those served by Henssge), but these can only be an approximation. The height and weight of the body must be known, which is often impossible at the scene of discovery. The amount of subcutaneous and abdominal fat will affect the insulating properties and hence the temperature gradient, but there is no way of assessing or correcting accurately for obesity. Oedema and dehydration both have a marked effect because of the high specific heat of water.[79] In general, a thin person cools more quickly because of both the mass:surface area ratio and the lack of fatty insulation. Children have a larger surface area for a given body weight (Fig. 2.32).

Posture

The loss of heat from the skin that drives the temperature gradient is affected by the access of air to the skin and the opportunity for radiation and convection. A body curled into a fetal position will expose much less surface than one in an extended, spread-eagled posture. Another factor is the amount of skin resting on the supporting surface and the nature of that surface. A body lying full length on its back will lose heat by conduction faster than one resting semiprone, though radiation and convection may be facilitated. A body on a metal mortuary tray will cool more quickly than one lying on straw.



Figure 2.32 Diagrammatic representation of some variables in body cooling curves: (a) average body, (b) obese body, (c) heavily clothed body, (d) thin body, (e) naked body, (f) hypothermic body and (g) febrile body.

Clothing and coverings

All too obvious is the effect of external insulation by clothing or other coverings, even a hat. Radiation is a minor pathway for heat loss because of the low biological temperatures involved, but convection and conduction are markedly reduced by coverings. Even more confusion may be added when coverings actually contribute heat, such as an electric blanket left on after death. A duvet or 'continental quilt' will markedly retard cooling and in fact will accelerate decomposition to a considerable degree. Wet clothing will accelerate cooling, compared with dry coverings, because of the uptake of heat for evaporation.

The ambient temperature

This is, of course, the major factor in cooling and, as was said at the outset, a body will not cool after death if the temperature of the environment is higher than the nominal 37°C, in fact, it may warm up. This may be climatic and seasonal, as in large areas of the world, not necessarily in the tropics. It may also be due to local heating, usually in dwellings or other buildings. This includes radiant heat from fires left burning near the body after death, electric blankets or death in a house or vehicle fire. Where a victim dies in a warm bath then the whole cooling process is grossly distorted, the opposite of when immersion takes place in the cold water of baths, rivers, lakes or the sea.

Air movement and humidity

Most skin cooling takes place by convection and conduction with the adjacent air as the transporting medium. In still conditions, a layer of warm air clings to the skin, especially if clothed or hairy, blocking the temperature differential. Any air movement brings fresh cooler air into contact with the skin and encourages the gradient from the core. The humidity is a less active factor, but damp air conducts heat more readily than dry. A body in a small space will cool more slowly than one exposed to the open air, as transfer of heat to the small volume of air will reduce the temperature differential.

The medium around the body

This is usually air, but when it is water or (rarely) another fluid, skin cooling is far more effective. A body immersed in water, especially the moving water of a river or the sea, will rapidly lose heat, as is all too familiar during life when fatal hypothermia can occur within minutes in a cold sea. It is commonly stated that cooling is less rapid in contaminated water (such as sewage) than in clean water, but this is hard to believe, given the same temperature for each type of medium. As mentioned above, death in the warm water of a bath-tub reduces the cooling rate – and may even elevate the temperature, making any attempt at estimating the time of death futile.

Haemorrhage

It is traditional to say that severe haemorrhage shortly before death causes more rapid cooling. As the estimation of the time of death is fraught with such inaccuracy, it is difficult to see how this opinion can have been derived. The volume of blood lost will reduce the mass of the body, but only in a minimal fashion. It may be that terminal bleeding may cause a shutdown of cutaneous circulation in an effort to maintain blood pressure and that this might encourage the early formation of the temperature gradient shortening the plateau phase.

Methods of measuring body temperature

Estimation of temperature by touching with the hand is a useful first manoeuvre when at the scene of a death. A hand placed on the forehead, face or exposed hand may give a first impression of whether death occurred recently or not. Even if these exposed areas are cold, feeling inside the clothing to touch the chest, abdomen or axilla may detect some heat, as may sliding a hand under the body where it is in contact with the supporting surface. These crude methods are combined with an estimate of rigor mortis to provide a preliminary screening of a recent, as opposed to a remote, time of death. Though conditions vary enormously, a body indoors will feel cold on exposed areas in 2–4 hours and in protected areas after some 6–8 hours. The traditional method of taking the post-mortem temperature is by placing a mercury thermometer in the rectum. This must be a chemical thermometer (not a clinical instrument) or thermocouple, ideally reading from 0 to 50°C. The tip must be inserted to at least 10 cm above the anus, the instrument preferably having most of its gradations still visible when *in situ*. It should be left in place for several minutes for the reading to stabilize before being recorded. Where possible, it should be left *in situ* for multiple readings at intervals, though in operational circumstances (especially in criminal deaths) this may be difficult to arrange. There is considerable controversy about when such measurements should be carried out. It is often recommended that a doctor at the scene of death should measure the rectal temperature at once but logistic difficulties exist. Many cases where estimation of the time of death is important are criminal or suspicious deaths. These will often be associated with at least the possibility of sexual or homosexual assaults, and it may not be practicable to interfere with clothing in the perineal area or to contaminate the anal and vaginal region before full trace evidence procedures are carried out, usually by police scene of crime officers or forensic scientists, which may include adhesive taping of the clothing and skin, and the retention of underclothes for seminal stains, etc.

To wrestle with tight clothing, perhaps at night, in inclement weather and in confined spaces, and to try to introduce a thermometer into the rectum in these circumstances might ruin vital evidence of more importance than the admittedly uncertain calculations about time of death. However, many pathologists and police teams do carry out this manoeuvre as a routine, but each pathologist must decide in every individual case, whether it is preferable to wait until the body is taken to the mortuary where proper, controlled undressing is possible.

This applies where pathology and criminalistic expertise is readily available, but it is acknowledged that in less ideal circumstances, when no such expertise is likely to appear within a few hours (if at all), then a doctor at the scene should take a temperature. The procedure must be tailored to the individual circumstances but where there is a possibility of sexual interference, the rectum (and vagina) should be avoided until after full swabbing for semen and other examinations are completed. Alternatives are to use the axilla, deep nasal passage or external ear for the insertion of a thermometer.

The technique of introducing a mercury or 'rototherm' thermometer through a stab wound in the abdomen to measure liver temperature is never justified. It inevitably leads to blood contamination of the skin and clothing and also leads to intraperitoneal bleeding that might be confused with existing internal injuries.

More modern measuring devices include thermocouples, which register temperature accurately with minimum stabilization time. They may be part of a compact electronic instrument that has a digital readout, or they may be connected to a computerized



Figure 2.33 Measuring the rectal temperature at the scene of a murder. This should be done only after forensic procedures such as rectal swabbing have been completed. Normally the temperature should be taken at the mortuary where removal of clothing can be carried out with full photographic and forensic science monitoring. In this case the body was unclothed at the scene and the circumstances did not warrant rectal swabbing.

recorder that can analyse several other sites at regular intervals.[80] Microwave thermography of brain and liver[81,82] and infrared monitoring of skin temperature are at present research tools that may lead to practical devices in the future (Fig. 2.33).

The use of thermometry in estimating the post-mortem interval

In spite of the great volume of research and publications already mentioned, accuracy in estimating the time since death from temperature remains elusive. The old rule-of-thumb was that the temperature fell at about 1.5°F/h, something under 1°C/h. Another rule-of-thumb was that the fall in °C from 37°C, plus three (to arbitrarily allow for the plateau), was equal to the time since death in hours. The only confidence that one could place in these methods was that they were almost always wrong and that, if the answer happened to be correct, it was by chance rather than science! To hope for a linear fall was against all the principles of heat loss alluded to earlier. The first method took no account of the 'plateau' when rectal temperatures were used. This upper part of the double exponential curve is of variable length. If the body has been dead for some hours, serial temperature recordings fail to identify it, as the measurements begin on the steeper part of the curve, but where thermometry is begun soon after death, there is a variable flat area at the top of the sigmoid graph.

The length of the plateau has been discussed by several authors.[83,84] Shapiro in particular has drawn attention to the invalidation of many formulae by the unknown length of the plateau. He claims that this can be as much as 4 hours 'and is possibly considerably longer'. Marshall and Hoare admit that the plateau may be as long as 5 hours.[66] The plateau is the result of the lag in conducting heat from the core to the skin that is caused by the insulating properties of human tissue. This delays the establishment of the temperature gradient that must be in operation along the radius of the 'infinite cylinder', which is the model for the human body, before the core can begin to lose heat to the exterior. There may also be a small element of continuing heat production in the liver and musculature, as a number of investigators (including the first) noted that the body temperature could actually rise soon after death. As the length of the plateau is unknown in any particular case when there is a delay in starting measurements, most methods begin within this inbuilt inaccuracy.

At the lower end of the sigmoid curve, measurements again become almost useless, as when the temperature is within about 4°C of the environment, the rate of cooling becomes so slow that it provides no separation in time.[61] Another empirical rule-of-thumb was devised by James and Knight to include variation in ambient temperature.[79] The fall from 37°C was multiplied by a factor of 1, 1.25, 1.5, 1.75 or 2 for ambient temperatures of 0, 5, 10, 15 or 20°C, respectively, to give the time since death in hours. As another linear method, this was doomed to inaccuracy and was found to provide too short a PMI, though the authors emphasized that it was meant to be modified in each case by an appreciation of all other factors such as physique and clothing.

Nomogram method

At present one of the most useful practical guides is the nomogram published by Henssge (Figs 2.36, 2.37).[67,68,71,72,85–91] Based on conventional calculations such as those of De Saram and Marshall and backed up by a great volume of experimental data, Henssge has produced a method which can be carried out either by a simple computer program or by a nomogram. Adjustments are built in for body weight, ambient temperature, dry or wet clothing, still or moving air, or still or flowing water. The result is given within different ranges of error, with a 95 per cent probability of the true time of death falling within these ranges, which vary from 2.8 hours each side at the best estimate, down to 7 hours at worst. As with most methods, the difficulties arise in estimating the strength of the variable factors. It also cannot allow for variation of these factors over time, especially changes in ambient temperatures during the period before the body was examined. Henssge and Madea have recently refined their method to reduce the standard deviation of their nomograms so that the confidence range becomes smaller, by a whole battery of methods not dependent on temperature, such as electrical stimulation of muscle and the reaction of the eye pupils to drugs.[68,71,72,90] The nomograms are shown at the end of this chapter (Figs 2.36, 2.37) but they should not be reproduced for practical casework: instead the original forms should be used, which can be downloaded online at http://www.rechtsmedizin.uni-bonn.de/dienstleistungen/for_Med/todeszeit.

Friedlander, a US pathologist of Kansas City University of Medicine and Biosciences, with an interest in pathology education and forensic pathology, has designed and published a Time-of-Death Applet that can be accessed at his website at http://www.pathguy.com/TimeDead.htm. The applet is based primarily on the formulas developed by Henssge and it takes into account the following parameters: core body temperature (F/C), body weight (lb/kg), type of location where the body was found (still or moving air; body dry/soaked; water still/flowing), covering, environmental temperature, and the presence and type of rigor and lividity as well as some other factors.[92]

Another graphical method is that developed by Al-Alousi in Glasgow.[93] In addition to his publications on microwave thermography, Al-Alousi has published a simple method based on rectal temperatures. He has constructed cooling curves for both naked and covered bodies, using the concept of 'temperature ratios'. The accompanying cooling curves may be used from a knowledge of the rectal temperature, ambient temperature and whether or not the body surface was covered. Again no correction is made for body size, posture or other variables, but the author claims that such factors made little difference to the standard errors, which he gives as shaded errors on each side of his graphs (Fig. 2.34).

Multiple-site serial measurement methods

In an effort to reduce or eliminate the effect of the external variables when calculating the PMI, Morgan *et al.* have developed models using multiple sites in the body for temperature estimations.[80] These are then



Figure 2.34 Cooling curves for estimation of the post-mortem interval. In Al-Alousi's 'temperature ratio' method, the graphs above are used as follows. Assume that the body temperature (rectal) is 36.6°C at the time of death (T_b). Measure the environmental and rectal temperatures at the time of examination (T_r and T_e). Then the 'temperature ratio' is Tr2Te/Tb2Te. This ratio is then found on the vertical scale of the rectal graph, using either the graph for 'naked' or 'covered' as appropriate. The time since death is the point on the lower scale where a perpendicular falls from the point on the graph where a horizontal line meets it from the temperature ratio level. The shaded area indicates the limits of a 68 per cent probability at that particular point. For example, if the rectal temperature is 23.4°C and the air temperature 19°C, then the temperature ratio is 0.25. If the body is naked, then this gives 18 hours as the time since death, with a margin of plus 2.5 hours and minus 5 hours. (Reprinted with permission from Al-Alousi LM, Anderson RA. 1986. Microwave thermography in forensic medicine. *Police Surgeon* **30**:30–42.)

taken serially at frequent intervals over a period using highly sensitive thermocouples and computerized data acquisition, and calculation, which is miniaturized sufficiently for use at scenes of crime.

The method also attempted to use the deep ear canal and nasal passages for temperature measurements, which avoids the problems of perineal contamination that occur when the rectum is used at scenes of death. The results were not encouraging, but recently French workers have revived the ear method, with claims of relative success. These methods have not been in routine use for sufficiently long to evaluate their operational accuracy.[94,95]

Stomach emptying as a measure of time since a death

With one exception, this controversial topic could be dismissed summarily as being quite irrelevant. For many years pathologists have argued over the reliability of the state of digestion of gastric contents as an indicator of the time between the last meal and death, the leading case in modern times being that of Truscott in Canada. There is now almost a consensus that with extremely circumscribed exceptions, the method is too uncertain to have much validity.

The original hypothesis was founded on the belief that food spent a fairly uniform time in the stomach before being released into the duodenum. In addition, it was claimed that its physical state was progressively altered by gastric juices and movements so that its appearance and volume was a measure of the time since it had been swallowed. Therefore, if the time of the last meal was known from circumstantial evidence, the time of death could be estimated.

It was assumed that the physiological process of digestion of an ‘average’ meal lasted some 2–3 hours. This is based on the consumption of a test meal of gruel, however, hardly a representative example of a modern mixed diet. Moreover, the subjects of experimental work were healthy and presumably free from sudden stress during the experiments. More elaborate descriptions of digestion times of various foods have been drawn up, but they are of dubious value. As an example of the great variations offered, Modi gives 4–6 hours for a meat and vegetable meal and 6–7 hours for a farinaceous meal.[96] Adelson stated that the stomach begins to empty within 10 minutes of swallowing, that a ‘light’ meal leaves the stomach by 2 hours, a ‘medium’ meal takes 3–4 hours and a large, heavy meal takes 4–6 hours.[97] He noted that the head of an ‘ordinary’ meal usually reached the ileocaecal valve between 6 and 8 hours after ingestion. All these values, however, are subject to considerable variation.

More modern methods of investigation have used radioisotope techniques and have shown some interesting facts. When a solid meal is eaten and water drunk with it, the water leaves the stomach quickly irrespective of the nature or calorific content of the solid part. However, calorific liquids stay longer in the stomach.[98] The emptying rate also increases with the weight of the meal, as long as the calorific content remains constant. If the latter is increased, then the pyloric opening is delayed. Further work by Moore *et al.* again emphasized the marked variability of emptying times, even in normal circumstances.[99]

The following factors frustrate the use of gastric emptying as a measure of time since death:

- Digestion may continue for some time after death.
- The physical nature of a meal has a profound effect on emptying time: the more fluid the consistency, the faster the emptying. Liquids entering an empty stomach pass through without any appreciable pause.
- The nature of the food modifies emptying time, notably fatty substances, which markedly delay the opening of the pylorus. Strong alcohol, such as spirits and liqueurs, also irritate the mucosa and tend to delay emptying.
- Importantly, any nervous or systemic shock or stress, mediated through the parasympathetic (vagus) system, can slow or stop gastric motility and digestive juice secretion as well as holding the pylorus firmly closed.

The intestine, as opposed to the stomach, may increase its motility with psychogenic upsets, as noted by De Saram in his autopsies on hanged criminals.

The state of digestion, as opposed to the volume and exit of food from the stomach, is almost impossible to assess. Variations in the type of food eaten make vast differences to the dissolution rate. Hard objects, such as nuts and seeds, resist digestion and may even be voided intact *per rectum*, whereas soft carbohydrates can liquefy almost immediately. The size and dispersion of particles is crucial, including the amount of chewing and admixed saliva. The efficiency of the teeth and gastric acid, enzymes and motility are also of prime importance, as is the amount of liquid either in the original food or drunk during the meal. Fat and oil in the meal slow up pyloric opening, and all these variables make it impossible to time the rate of digestion.

One of the most important factors in the forensic context is the effect of a physical or mental shock or stress during the digestion process. As stated, this can completely inhibit digestion, gastric motility and pyloric opening. The author (BK) recalls a victim of a traffic accident who lived in a coma for a week after a mortal head injury. At eventual autopsy, the large volume of gastric contents looked as fresh as if it had just been swallowed.

Even if one accepts an 'average' gastric transit time of an 'average' meal as being of the order of 2–3 hours, the assumption that death took place within this time can only be valid if the death was quite sudden and unexpected, with no stressful prodromal event. For example, if an unsuspecting person was suddenly shot or run down without warning and died almost immediately, then one can assume that the undisturbed physiological processes of digestion – albeit with its many variables – had taken place. If, however, a domestic dispute or a developing altercation culminated in a strangling or stabbing, the antecedent stresses would almost certainly affect gastric function and render invalid any interpretation of the condition of stomach contents at autopsy.

What is valid is the nature of the last meal, which may be helpful in establishing the time of death. If it was known to the investigators that the deceased person ate a certain type of meal at a certain time, whether it be chicken curry or green beans, the identification of such food in the stomach would be persuasive evidence that he died after taking that food and that it was his final meal, before any other substantial food of a different type was taken.

The use of vitreous humour chemistry in timing death

This topic has been the subject of considerable research in forensic medicine over the last 50 years. It has never gained sufficient acceptance to become a routine tool, remaining a controversial procedure in spite of the large number of reports that now exists.

The most common chemical estimation performed on the vitreous fluid in the context of the PMI is that of potassium.[100]

After death, intracellular potassium leaches from the retina through the now permeable cell membranes into the vitreous body, with an uneven distribution depending on the distance from the wall of eyeball. The sampling methods are then critical, as the measured values obtained from small or marginal samples may vary greatly (Fig. 2.35). If fragments of retina are aspirated by the syringe due to excessive suction, then a falsely elevated potassium measurement will be obtained. The potassium values from either eye often differ, sometimes by a considerable amount.[75,101–103] Different analytical techniques used to estimate the potassium give different results, the older flame photometric methods producing a different range of values compared with selective-electrode procedures.[104] There is a marked and progressive rise in the potassium concentration after death, the controversy revolving around whether this rise is simply linear or whether it is biphasic. Differences in the recommended regression gradient are observed between various workers: Madea states that 0.19 mmol/l/h should be used, whereas Sturner claims 0.14 mmol/l/h is preferable. The literature should be consulted for details.[70] Taking a sample from one eye at a later time than the first to attempt to calculate the rate of rise does not seem to add any accuracy to a single estimation method.[105] The effect of temperature changes post-mortem is also undoubtedly important. In addition, the errors seem much greater in persons dying of chronic illnesses, with nitrogen retention, compared with sudden deaths, presumably because of the pre-mortal electrolyte disturbances in patients with metabolic disorders.[70] With all these variables, it is little wonder that different authors suggest widely different standard errors, varying from 1–7 hours to 26 hours either side of the true time of death. Generally speaking, the vitreous potassium method is of most use after the first 24–36 hours, when other methods have ceased to have application. Although the errors are great, some information can be derived for up to 100 hours post-mortem.



Figure 2.35 Obtaining vitreous humour for analysis. The lids should be retracted and the needle introduced near the outer canthus, so that the hole will be covered when the lids are released. Fluid should be withdrawn slowly, keeping the tip of the needle in the centre of the globe to avoid dislodging the retina. Water can be re-introduced through the needle to restore the tension in the globe for cosmetic reasons.

Hypoxanthine estimation in vitreous humour has also been used to attempt to time death, but more often as a marker of hypoxia. The results are not convincing, but there is an accumulating literature on the subject.[77,106–108]


PERMISSIBLE VARIATION OF 95% (±h)
TEMPERATURE–TIME OF DEATH
RELATING NOMOGRAM
For ambient temperatures up to 23°C
Using corrective factors
Standard (naked–still air)
2,8
2,8
4,5
3,2
7,0
4,5
°C
RECTUM
KILOGRAM
AMBIENT
°C
10
15
20
30
40
50
60
70
80
90
100
110
120
140
160
180
200

Do not use a reproduction of this page for calculations but download and print the original form as instructed at http://www.rechtsmedizin.uni-bonn.de/dienstleistungen/for_Med/todeszeit

Figure 2.36 Henssge's nomogram method for estimating the time since death from a single rectal temperature, where the environmental temperature is below 23°C.

Proton magnetic resonance spectroscopy and time of death

Saukko and co-workers measured the effect of post-mortem autolysis and storage temperature on nuclear magnetic resonance (NMR) proton relaxation times (T1, T2) of mouse myocardium to find out whether the method could be used for diagnostic purposes in post-mortem material. The results suggested that the longitudinal relaxation time (T1) did not appear to be stable enough to be used for diagnostic purposes, whereas T2 was stable and worth of further investigation.[109] Quite recently, Ith and co-workers have used *in situ* proton magnetic resonance spectroscopy (^{1}H-MRS) in a sheep head model to study post-mortem decomposition in order to characterize and identify decay products of brain tissue that might be used to estimate the PMI up to 2–3 weeks post-mortem.[110–113] They were able to



Do not use a reproduction of this page for calculations but download and print the original form as instructed at http://www.rechtsmedizin.uni-bonn.de/dienstleistungen/for_Med/todeszeit

Figure 2.37 Henssge's nomogram method for estimating the time since death from a single rectal temperature, where the environmental temperature is above 23°C.

identify several compounds showing linear concentration changes; however, it appeared that the temperature dependent onset of bacterial decomposition may systematically change the entire kinetics of the system and significantly reduce the time window of practical applicability. Though only very few researchers will have access to this kind of methodology, it can be hoped that this ongoing work increases our knowledge about the chemical processes of decomposition and may lead to new ideas that might be useful in daily forensic work.

Post-mortem chemistry

The analysis of physiological chemical constituents of the body, as opposed to toxic substances, is often useful in investigating deaths from metabolic and biochemical disturbances.

Unfortunately, the concentration of many natural chemical substances in the dead body is rapidly distorted by post-mortem autolysis. Cell membranes become permeable to small molecules soon after the cells suffer ischaemic or anoxic damage, and agonal changes themselves may grossly alter the biochemical environment, even in the few minutes of the dying process. Thus both terminal and early post-mortem changes may render many of the analyses that are commonplace in clinical practice of little value – and indeed, quite misleading – when applied to body fluids obtained at autopsy. Some substances are more stable, however, and when results are carefully interpreted, considerable information can be obtained. Urea and creatinine are stable post-mortem, with little variation even up to 100 hours after death, so the diagnosis of ante-mortem nitrogen retention is quite reliable. The normal urea nitrogen range found in post-mortem serum is from 4.9 to 5.5 mmol/l, creatine being from about 70.7 to 212.2 μmol/l.

In the context of post-mortem chemistry the work of John Coe is best known in forensic pathology and his writings should be consulted for detailed information.[104,114–121] Another very useful source is Madea, especially for vitreous fluid.[75–77,107,122–129] The vitreous humour is much to be preferred to blood for post-mortem chemical analyses. Although still influenced by temperature changes, the vitreous is far less contaminated by body autolysis and is remote from the large organs and blood vessels of the abdominothoracic cavity.

Caution must be used when interpreting results, as different analytical techniques provide different values. For instance, in relation to electrolytes, Coe and Apple state that flame photometric methods yield values about 5 mmol/l less for sodium, 7 mmol/l less for potassium and 10 mmol/l less for chloride, compared with more modern specific electrode methods.[104] Electrolyte concentration differences between left and right vitreous humor samples were studied by Pounder *et al.* in 200 medico-legal autopsies using an ion-specific electrode system.[102] Between-eye concentration differences of sodium and chloride were tolerable using this methodology, whereas differences in potassium, even in biochemically non-putrefied cases (potassium 15 mmol/l), were 0–2.34 mmol/l (0–21.8 per cent of mean) averaging 0.37 mmol/l (3.3 per cent), thus undermining the usefulness of vitreous potassium in estimation of time of death.

In relation to other vitreous electrolytes, the concentration of sodium and chlorides decrease after death, while potassium rises. The latter can be used as a check on the reliability of the others: if potassium is 15 mmol/l, then the sodium and chloride concentrations may be acceptable. Chlorides decrease at less than 1 mmol/l/h and sodium by about 0.9 mmol/l/h, so the loss of this and sodium is insignificant in the first few hours, differing from potassium, which rises appreciably.

With the analysis of glucose in autopsy material, five different methods yielded five different results, presumably because interfering substances were included in varying amounts.

Returning to vitreous electrolytes measured by flame photometry (in mmol/l), measurement of sodium >155, chloride >135 and urea >40 is a reliable indication of ante-mortem dehydration. When sodium and chloride are normal but the urea exceeds 150 mmol/l, a diagnosis of uraemia is acceptable. These values can be distinguished from post-mortem decomposition, in which sodium is <130, chloride <105 and potassium >20 mmol/l, respectively.

In relation to glucose, a common problem is the autopsy diagnosis of uncontrolled diabetes and of hypoglycaemia. The vitreous glucose usually falls after death and can reach zero within a few hours. In 6000 analyses, Coe found that a vitreous glucose of more than 11.1 mmol/l was an invariable indicator of diabetes mellitus.[115,121] The agonal or post-mortem rise in blood sugar is not reflected in the vitreous concentrations. In relation to hypoglycaemia, a vitreous glucose of less than 1.4 mmol/l was taken by Sturner *et al.* to be an indication of a low ante ante-mortem blood sugar, but others feel that whatever the concentration, no reliable interpretation can be made.[121,130–136] In hypothermia there is also an elevated vitreous glucose.[137–140]

References

1 UKHL, *Airedale NHS Trust v. Bland*, in *All Engl Law Rep* 1993, pp. 821–96.

2 Pallis C. *ABC of Brain Death*. London: British Medical Association, 1983.

3 Nicati S. Loss of eye tension as a sign of death. *Med Rec* 1894;45:4801.

4 Sommer AG. *Dissertationis de signis, mortem hominis absolutam ante putredinis accessum indicantibus, Particula prior [et posterior]* Copenhagen, 1833, p. 277.

5 Forbes J, Conolly J (eds). Dr. Sommer on the signs of death. *British and Foreign Medical Review* Vol. IV. London: Sherwood Gilbert and Piper, 1837.

6 Kevorkian J. The fundus oculi and the determination of death. *Am J Pathol* 1956;32:1253–67.

7 Kevorkian J. The eye in death. *Ciba Symposia* London, 1961.

8 Salisbury CR, Melvin GS. Ophthalmoscopic signs of death. *Br Med J* 1936;i:1249–51.

9 Wroblewski B, Ellis M. Eye changes after death. *Br J Surg* 1970;57(1):69–71.

10 Leadbeatter S, Knight B. The history and the cause of death. *Med Sci Law* 1987;27(2):132–5.

11 Bonte W, Sprung R, Huckenbeck W. *[Problems in the evaluation of electrocution fatalities in the bathtub]. Z Rechtsmed* 1986;97(1):7–19.

12 Schuller E, Pankratz H, Liebhardt E. *[Colorimetry of livor mortis]. Beitr Gerichtl Med* 1987;45:169–73.

13 Vanezis P. Assessing hypostasis by colorimetry. *Forensic Sci Int* 1991;52(1):1–3.

14 Inoue M, *et al*. Development of an instrument to measure postmortem lividity and its preliminary application to estimate the time since death. *Forensic Sci Int* 1994;65(3):185–93.

15 Mallach HJ. Zur frage der todeszeitbestimming. (Definition of the time of death.). *Berlin Med* 1964;18:577–82.

16 Suzutani T, Ishibashi H, Takatori T. [Studies on the estimation of the postmortem interval. 2. The postmortem lividity (author's transl)]. *Hokkaido Igaku Zasshi* 1978;52(6):259–67.

17 Fechner G, Koops E, Henssge C. [Cessation of livor in defined pressure conditions]. *Z Rechtsmed* 1984;93(4):283–7.

18 Prinsloo I, Gordon I. Post-mortem dissection artefacts of the neck and their differentiation from ante-mortem bruises. *South African Med J* 1951;25:358–61.

19 Zink P. [The mechanical behaviour of human skeleton muscle during the course of rigor mortis]. *Z Rechtsmed* 1972;71(1):47–63.

20 Henssge C. *Personal communication*, 2011.

21 Niderkorn F. *Contribution à l'étude de Quelques-uns des Phénomènes de la Rigidité Cadavérique chez l'homme*. Paris: Faculté de médecine de Paris, 1874, p. 93.

22 Mant AK. Factors influencing changes after burial. In: Simpson K (ed). *Modern Trends in Forensic Medicine*. London: Butterworth, 1953.

23 Mant AK. Adipocere. In: Simpson K (ed). *Modern Trends in Forensic Medicine*. London: Butterworth, 1967.

24 Mant AK, Furbank R. Adipocere - a review. *J Forensic Med* 1957;4:18–22.

25 Krompecher T, Bergerioux C. Experimental evaluation of rigor mortis. VII. Effect of ante- and post-mortem electrocution on the evolution of rigor mortis. *Forensic Sci Int* 1988;38(1–2):27–35.

26 Szent-Gyorgyi A. *Chemistry of Muscular Contraction*. New York: Academic Press, 1947.

27 Hanson J, Huxley H. The structural basis of contraction in striated muscle. *Symp Society Exp Biology* 1955;9:228–64.

28 Erdos T. Rigor, contracture and ATP. *Stud Ins Med Chem Univ Szeged* 1943;3:51–6.

29 Bate-Smith E, Bendall J. Rigor mortis and adenosine triphosphate. *J Physiol* 1947;106:177.

30 Forster B. The plastic, elastic and contractile deformation of the heart muscle in rigor mortis. *J Forensic Med* 1964;11:148.

31 Bate-Smith E, Bendall J. Factors determining the time course of rigor mortis. *J Physiol* 1949;110:47.

32 Krompecher T. Experimental evaluation of rigor mortis. VIII. Estimation of time since death by repeated measurements of the intensity of rigor mortis on rats. *Forensic Sci Int* 1994;68(3):149–59.

33 Gonzales M, Bankowski MJ, Landay AL. *Legal Medicine and Toxicology*, 2nd edn. Vol. 64. New York: Appleton Century Crofts, 1954.

34 Fourcroy A. Mémoire sur les différens états cadavers trouvés dans le fouilles du cimetiére des Innocens en 1786 &1787. *Ann Chimie* 1790;(5):154–185.

35 Barnes WH. Browne's "Hydriotaphia" with a reference to adipocere. *Isis* 1934;20(2):337–343.

36 Bacon F. *Sylva Sylvarum: or A Natural History, in Ten Centuries*, 1st edn, Rawley W (ed). London: J.H. for William Lee, 1627.

37 Ubelaker DH, Zarenko KM. Adipocere: what is known after over two centuries of research. *Forensic Sci Int* 2011;208 (1–3):167–72.

38 Evans WED. *The Chemistry of Death*. Springfield: Charles C. Thomas, 1963. 101.

39 Evans WE. Adipocere formation in a relatively dry environment. *Med Sci Law* 1963;3:145–53.

40 Polson CJ, Marshall TK. *The Disposal of the Dead*, 3rd edn. London: English Universities Press, 1975.

41 Casper JL. *Practisches Handbuch der Gerichtlichen Medicin*,1st edn. Berlin: Verlag von August Hirschwald, 1857.

42 *GREAT BRITAIN: A Mummy in the Closet*. In: *Time Magazine*. Time Inc: US, 1960.

43 Evans WE. Some histological findings in spontaneously preserved bodies. *Med Sci Law* 1962;2:155–64.

44 Shapiro HA, Gordon I, Benson SD. *Forensic Medicine – a Guide to Principles*, 3rd edn. Edinburgh: Churchill Livingstone, 1988.

45 Iscan MY, McCabe BQ. Analysis of human remains recovered from a shark. *Forensic Sci Int* 1995;72(1):15–23.

46 Byard RW, Gilbert JD, Brown K. Pathologic features of fatal shark attacks. *Am J Forensic Med Pathol* 2000;21(3):225–9.

47 Byard RW, James RA, Gilbert JD. Diagnostic problems associated with cadaveric trauma from animal activity. *Am J Forensic Med Pathol* 2002;23(3):238–44.

48 Ritter EK, Levine M. Bite motivation of sharks reflected by the wound structure on humans. *Am J Forensic Med Pathol* 2005;26(2):136–40.

49 Byard RW, James RA, Heath KJ. Recovery of human remains after shark attack. *Am J Forensic Med Pathol* 2006;27(3):256–9.

50 Buschmann CT, Wrobel D, Tsokos M. [Post-mortem animal predation of the genital region caused by a half-breed dog]. *Arch Kriminol* 2008;222(5–6):182–6.

51 Megnin P. *La Faune des Cadavres.* Paris, France: Gauthier-Villars, 1894.

52 Nuorteva P, Isokoski M, Laiho K. Forensic entomology. *Ann Entomology Fenn* 1967;33:217–20.

53 Glaister J, Brash J. *Medicolegal Aspects o the Ruxton Case.* Edinburgh: Livingstone, 1937.

54 Busvine J.R. *Insects and Hygiene*, 3rd edn. London: Chapman & Hall, 1980.

55 Kamal AS. Comparative study of thirteen species of Sacrosaprophagous Calliphoridae Sarcophagidae (Diptera). 1 Bionomics. *Ann Entomol Soc America* 1958;51:261–71.

56 Knight B. The evolution of methods for estimating the time of death from body temperature. *Forensic Sci Int* 1988;36(1–2):47–55.

57 Davy J. *Researches, Physiological and Anatomical.* Vol. 1. London: Smith, Elder, 1839.

58 Taylor A, Wilkes D. On cooling of the human body after death. *Guy's Hosp Rep* 1863(October):180–211.

59 DeSaram GS, Webster G, Kathirgamatamby N. Postmortem temperature and the time of death. *J Criminal Law Criminol Police Sci* 1955;1:562–77.

60 DeSaram GS. Estimation of the time of death by medical criteria. *J Forensic Med* 1957;4:47–57.

61 Fiddes F, Patten TA. Percentage method for representing the fall in body temperature after death. *J Forensic Med* 1958;5:2–15.

62 Marshall TK. *The cooling of the body after death.* Leeds: University of Leeds (MD Thesis), 1960.

63 Marshall TK. Estimating the time of death. *J Forensic Sci* 1962;7:210–21.

64 Marshall TK. Temperature methods of estimating the time of death. *Med Sci Law* 1965;5(4):224–32.

65 Marshall TK. The use of body temperature in estimating the time of death and its limitations. *Med Sci Law* 1969;9(3):178–82.

66 Marshall TK, Hoare F. Estimating the time of death - the rectal cooling after death and its mathematical representation. *J Forensic Sci* 1962;7:56–81.

67 Henssge C. Death time estimation in case work. I. The rectal temperature time of death nomogram. *Forensic Sci Int* 1988;38(3–4):209–36.

68 Henssge C, *et al*. Experiences with a compound method for estimating the time since death. II. Integration of non-temperature-based methods. *Int J Legal Med* 2000;113(6):320–31.

69 Henssge C, *et al*. *The Estimation of the Time Since Death in the Early Postmortem Period*. Knight B (ed). London: Edward Arnold, 1995.

70 Henssge C, *et al*. *The Estimation of the Time Since Death in the Early Postmortem Period*, 2nd edn. London: Arnold, 2002.

71 Henssge C, Madea B, Gallenkemper E. [Determination of the time of death—integration of various partial methods]. *Z Rechtsmed* 1985;95(3):185–96.

72 Henssge C, Madea B, Gallenkemper E. Death time estimation in case work. II. Integration of different methods. *Forensic Sci Int* 1988;39(1):77–87.

73 Henssge C, Wang H, Hoppe B. Light microscopical investigations on structural changes of skeletal muscle as artifacts after postmortem stimulation. *Forensic Sci Int* 2002;125(2-3):163–71.

74 Madea B, Henssge C. Electrical excitability of skeletal muscle postmortem in casework. *Forensic Sci Int* 1990;47(3):207–27.

75 Madea B, *et al*. References for determining the time of death by potassium in vitreous humor. *Forensic Sci Int* 1989;40(3):231–43.

76 Madea B, Herrmann N, Henssge C. Precision of estimating the time since death by vitreous potassium—comparison of two different equations. *Forensic Sci Int* 1990;46(3):277–84.

77 Madea B, *et al*. Hypoxanthine in vitreous humor and cerebrospinal fluid – a marker of postmortem interval and prolonged (vital) hypoxia? Remarks also on hypoxanthine in SIDS. *Forensic Sci Int* 1994;65(1):19–31.

78 Madea B, Kreuser C, Banaschak S. Postmortem biochemical examination of synovial fluid—a preliminary study. *Forensic Sci Int* 2001;118(1):29–35.

79 James WR, Knight B. Errors in estimating the time of death. *Med Sci Law* 1965;5:111–16.

80 Morgan C, *et al*. Estimation of the post mortem period by multiple-site temperature measurements and the use of a new algorithm. *Forensic Sci Int* 1988;39(1):89–95.

81 al Alousi LM, Anderson RA, Land DV. A non-invasive method for postmortem temperature measurements using a microwave probe. *Forensic Sci Int* 1994;64(1):35–46.

82 Al-Alousi LM, Anderson RA. Microwave thermography in forensic medicine. *Police Surg* 1986;30:30–42.

83 Nokes LD, Hicks B, Knight BH. The post-mortem temperature plateau—fact or fiction? *Med Sci Law* 1985;25(4):263–4.

84 Shapiro HA. The post-mortem temperature plateau. *J Forensic Med* 1965;12(4):137–41.

85 Henssge C. [Estimation of death-time by computing the rectal body cooling under various cooling conditions (author's transl)]. *Z Rechtsmed* 1981;87(3):147–78.

86 Henssge C, *et al*. [Determination of the time of death by measurement of central brain temperature]. *Z Rechtsmed* 1984;93(1):1–22.

87 Henssge C. [Ambulatory electronic data processing using the hand-held computer (HP 71B)]. *Beitr Gerichtl Med* 1989;47:327–31.

88 Henssge C. Rectal temperature time of death nomogram: dependence of corrective factors on the body weight under stronger thermic insulation conditions. *Forensic Sci Int* 1992;54(1):51–66.

89 Henssge C. [Rectal temperature-time of death nomogram: dependence of corrective factors of body weight in significant thermal insulating conditions]. *Beitr Gerichtl Med* 1992;50:169–81.

90 Henssge C, *et al*. Experiences with a compound method for estimating the time since death. I. Rectal temperature nomogram for time since death. *Int J Legal Med* 2000;113(6):303–19.

91 Bisegna P, *et al*. Estimation of the time since death: sudden increase of ambient temperature. *Forensic Sci Int* 2008; 176(2–3):196–9.

92 Friedlander E. *Estimating the Time of Death*: *http://www.pathguy.com/TimeDead.htm*.

93 Al-Alousi LM. *The Post-mortem Interval: A Study of the Postmortem Cooling Rate*. Glasgow: University of Glasgow (PhD Thesis), 1987.

94 Baccino E, *et al*. Outer ear temperature and time of death. *Forensic Sci Int* 1996;83(2):133–46.

95 Rutty GN. Concerning the paper by Baccino *et al*., entitled: 'Outer ear temperature and time of death' (*Forensic Sci Int* 83 (1996) 133–146). *Forensic Sci Int* 1997;87(2):171–3.

96 Modi JP. *Medical Jurisprudence and Toxicology*. Bombay: Tripathi, 1957.

97 Adelson L. *The Pathology of Homicide*. Springfield Thomas, 1974.

98 Brophy CM, *et al*. Variability of gastric emptying measurements in man employing standardized radiolabeled meals. *Dig Dis Sci* 1986;31(8):799–806.

99 Moore JG, *et al*. Influence of meal weight and caloric content on gastric emptying of meals in man. *Dig Dis Sci* 1984;29(6):513–9.

100 Sturner WQ. The vitreous humour: postmortem potassium changes. *Lancet* 1963;i:807–8.

101 Balasooriya BA, St. Hill CA, Williams AR. The biochemistry of vitreous humour. A comparative study of the potassium, sodium and urate concentrations in the eyes at identical time intervals after death. *Forensic Sci Int* 1984;26(2):85–91.

102 Pounder DJ, *et al*. Electrolyte concentration differences between left and right vitreous humor samples. *J Forensic Sci* 1998;43(3):604–7.

103 Tagliaro F, *et al*. Potassium concentration differences in the vitreous humour from the two eyes revisited by microanalysis with capillary electrophoresis. *J Chromatogr A* 2001;924(1–2): 493–8.

104 Coe JI, Apple FS. Variations in vitreous humor chemical values as a result of instrumentation. *J Forensic Sci* 1985;30(3):828–35.

105 Adjutantis G, Coutselinis A. Estimation of the time of death by potassium levels in the vitreous humour. *Forensic Sci* 1972;1(1):55–60.

106 Rognum TO, *et al*. A new biochemical method for estimation of postmortem time. *Forensic Sci Int* 1991;51(1):139–46.

107 Madea B, Rodig A. Time of death dependent criteria in vitreous humor: accuracy of estimating the time since death. *Forensic Sci Int* 2006;164(2–3):87–92.

108 Passos ML, *et al*. Estimation of postmortem interval by hypoxanthine and potassium evaluation in vitreous humor with a sequential injection system. *Talanta* 2009;79(4):1094–9.

109 Saukko P, Leinonen K, Kiviniitty K. The effect of autolysis and storage temperature on the NMR proton relaxation times in mouse myocardium. In: *Fifth National Meeting on Biophysics and Biotechnology*. Oulu: University of Oulu, 1986.

110 Ith M, *et al*. Observation and identification of metabolites emerging during postmortem decomposition of brain tissue by means of *in situ* 1H-magnetic resonance spectroscopy. *Magn Reson Med* 2002;48(5):915–20.

111 Thali MJ, *et al*. Virtopsy, a new imaging horizon in forensic pathology: virtual autopsy by postmortem multislice computed tomography (MSCT) and magnetic resonance imaging (MRI) – a feasibility study. *J Forensic Sci* 2003;48(2):386–403.

112 Scheurer E, *et al*. Statistical evaluation of time-dependent metabolite concentrations: estimation of post-mortem intervals based on *in situ* 1H-MRS of the brain. *NMR Biomed* 2005;18(3):163–72.

113 Ith M, *et al*. Estimation of the postmortem interval by means of (1)H MRS of decomposing brain tissue: influence of ambient temperature. *NMR Biomed* 2011;24(7):791–8.

114 Coe JI. Postmortem chemistries on human vitreous humor. *Am J Clin Pathol* 1969;51:741–50.

115 Coe JI. Further thoughts and observations on postmortem chemistry. *Forensic Sci Gaz* 1973, p. 26.

116 Coe JI. Postmortem chemistries on blood with particular reference to urea nitrogen, electrolytes, and bilirubin. *J Forensic Sci* 1974;19(1):33–42.

117 Coe JI. Postmortem chemistry: practical considerations and a review of the literature. *J Forensic Sci* 1974;19(1):13–32.

118 Coe JI. Postmortem chemistry of blood, cerebrospinal fluid, and vitreous humor. *Leg Med Annu* 1977;1976:55–92.

119 Coe JI. Vitreous potassium as a measure of the postmortem interval: an historical review and critical evaluation. *Forensic Sci Int* 1989;42(3):201–13.

120 Coe JI. Postmortem chemistry of blood and vitreous humour in pediatric practice. In: Mason J (ed). *Paediatric Forensic Medicine and Pathology*. London: Chapman and Hall, 1989, pp. 191–203.

121 Coe JI. Postmortem chemistry update. Emphasis on forensic application. *Am J Forensic Med Pathol* 1993;14(2):91–117.

122 Madea B. [Comments on: "Determination of calcium and magnesium in postmortem human vitreous humor as a test to ascertain the cause and time of death" by R. Nowak and S. Balabanova]. *Z Rechtsmed* 1990;103(3):231–3.

123 Madea B. Time since death extrapolated from vitreous potassium. *Forensic Sci Int* 1993;59(1):80–2.

124 Madea B, Henssge C. [Information value of potassium concentration in the vitreous humor for the time of death. Gaining precision by detecting antemortem dysregulation?]. *Beitr Gerichtl Med* 1987;45:151–5.

125 Madea B, Henssge C. Determination of the time since death. III. Potassium in vitreous humour. Rise of precision by use of an 'inner standard'. *Acta Med Leg Soc (Liege)* 1988;38(1):109–14.

126 Madea B, Henssge C, Staak M. [Postmortem increase in potassium in the vitreous humor. Which parameters are suitable as indicators of antemortem agonal electrolyte imbalance?]. *Z Rechtsmed* 1986;97(4):259–68.

127 Madea B, Hermann N, Henssge C. [Calcium concentration in vitreous humor—a means for determining time of death?]. *Beitr Gerichtl Med* 1990;48:489–99.

128 Schmidt V, *et al*. [Potassium concentration in the vitreous body—sample collection at different time intervals to determine time of death]. *Beitr Gerichtl Med* 1988;46:423–6.

129 Thierauf A, Musshoff F, Madea B. Post-mortem biochemical investigations of vitreous humor. *Forensic Sci Int* 2009;192(1–3): 78–82.

130 Sturner WQ, *et al*. Osmolality and other chemical determinations in postmortem human vitreous humor. *J Forensic Sci* 1972;17(3):387–93.

131 Patel F. Diabetic death bed: post-mortem determination of hypoglycaemia. *Med Sci Law* 1994;34(1):84–7.

132 Sippel H, Mottonen M. Combined glucose and lactate values in vitreous humour for postmortem diagnosis of diabetes mellitus. *Forensic Sci Int* 1982;19(3):217–22.

133 Kernbach G, *et al*. [Initial results of postmortem diagnosis of diabetes mellitus by Hb A1 determination]. *Z Rechtsmed* 1983;90(4):303–8.

134 Valenzuela A. Postmortem diagnosis of diabetes mellitus. Quantitation of fructosamine and glycated hemoglobin. *Forensic Sci Int* 1988;38(3-4):203–8.

135 Osuna E, *et al*. Glucose and lactate in vitreous humor compared with the determination of fructosamine for the postmortem diagnosis of diabetes mellitus. *Am J Forensic Med Pathol* 2001;22(3):244–9.

136 Nikolaev BS, Kinle AF, Samarkina O. [On the possibility of postmortem diagnosis of diabetes mellitus]. *Sud Med Ekspert* 2010;53(5):39–40.

137 Bray M, Luke JL, Blackbourne BD. Vitreous humor chemistry in deaths associated with rapid chilling and prolonged freshwater immersion. *J Forensic Sci* 1983;28(3):588–93.

138 Bray M. The eye as a chemical indicator of environmental temperature at the time of death. *J Forensic Sci* 1984;29(2): 396–403.

139 Coe JI. Hypothermia: autopsy findings and vitreous glucose. *J Forensic Sci* 1984;29(2):389–95.

140 Bray M. Chemical estimation of fresh water immersion intervals. *Am J Forensic Med Pathol* 1985;6(2):133–9.

This page intentionally left blank

CHAPTER 3

The Establishment of Identity of Human Remains

- Characteristics useful in identifying the dead
- Identification by DNA characteristics
- Identification of skeletalized remains
- The determination of sex
- Estimating the subject's age from skeletal structures
- Determination of ancestry from skeletal remains
- Reconstruction of the facial appearance from the skull
- Personal identity from skeletal material
- Photosuperimposition techniques for identification
- The dating of skeletal remains
- References

The identity of the dead is an essential part of post-mortem examination, for various reasons. These include:

- the ethical and humanitarian need to know which individual has died, especially for the information of surviving relatives
- to establish the fact of death in respect of that individual, for official, statistical and legal purposes
- to record the identity for administrative and ceremonial purposes in respect of burial or cremation
- to discharge legal claims and obligations in relation to property, estate and debts
- to prove claims for life insurance contracts, survivor's pensions, and other financial matters
- to allow legal investigations, inquests and other tribunals, such as those held by coroners, procurators fiscal, medical examiners, judges and accident enquiries to proceed with a firm knowledge of the identity of the decedent
- to facilitate police enquiries into overtly criminal or suspicious deaths, as the identity of the deceased person is a vital factor in initiating investigations.

The establishment of identity has many facets, some of which have no medical content, such as the recognition of clothing, documents and personal property. Some aspects, though primarily the responsibility of the police, have a medical content, including identification of fingerprints and personal property such as surgical prostheses. Dental work have such central importance that they will be considered in the section on odontology.

Identification from anatomical and medical features comprises two major aspects:

- The establishment of certain broad groupings, such as sex, stature, ancestry and age. These may be determined solely from the available bodily remains, though corroboration may be obtained from other evidence. An obvious example would be sex determination from clothing and jewellery, though even this may not be absolutely reliable.
- Comparison of the remains with ante-mortem information and records from those thought to be the victims, which restricts the method by making it dependent upon the existence or availability of such comparable material.

The establishment of identity may be required upon:

- Intact fresh corpses. Here visual recognition, directly or by photography, may be made. Hair colour, skin pigmentation, scars and tattoos can be examined without difficulty.
- Decomposed corpses. Many surface features may be partially or wholly lost, but more information can be obtained than from a skeleton. Direct measurement of body height, for example, may be possible, as well as DNA investigations and organ abnormalities, such as past surgical intervention, may be found (Figs 3.5, 3.25).

- Mutilated and dismembered corpses. Depending on the degree of mutilation and the amount of tissue missing, identification may be hampered. If the remains are fresh, facts such as racial pigmentation may be determined, but direct measurement of stature may be impossible. Selective mutilation in some homicides may be deliberately directed at frustrating identification, such as the removal of teeth and finger-pads.
- Skeletalized material. If all soft tissues are absent, identity depends solely on osteological examination and measurements and the recognition of any pathological or anatomical abnormalities in bone, as well as DNA extraction and analysis from compact bone tissue.

Characteristics useful in identifying the dead

Facial appearance

Even in perfectly fresh bodies, recognition may be difficult because of alterations in the features caused by death. It is a common occurrence in mortuary viewing rooms for a close relative, even a parent or spouse, to have doubts about – or even to deny or mistakenly agree to – the identity of the deceased person. Though distress and emotion play a part, changes in the features may be profound. Hypostasis, contact flattening, oedema, muscle flaccidity and pallor may all combine to distort the face. Recognition in the living is partly a dynamic process, aided by facial muscle tone and especially eye contact and movement, all of which are absent in the corpse.

Eye colour

In the fresh corpse, eye colour corresponds with the living state, but it quickly deteriorates. Loss of intraocular tension and clouding of the cornea develops progressively within a few hours, making the iris harder to observe. Collapse of the front of the globe occurs within a day or two and, with developing decomposition, all irises tend to darken to brown. It is unsafe to depend on eye colour as a criterion of identity later than a few days following death – or even much sooner where environmental conditions hasten decomposition.

Skin pigmentation

In undamaged, unputrefied bodies, the major ethnic differences in skin pigmentation are obvious, though the slight melanin increase of the misnamed 'yellow' races of Asia may be impossible to differentiate from Mediterranean or Middle Eastern races. The onset of deathly pallor and post-mortem hypostasis is more profound than slight variations between sunburnt White people or northern Asians. When putrefaction sets in, skin slippage progressively removes the pigmented layers and eventually pigmentation becomes unavailable as a marker of identity, though histologically melanin may still be visible in the basal layer of any surviving epidermis.

Burnt bodies may also lose pigmented skin, either by heat destruction or by deposition of soot and other combustion products on the surface, though it is rare for this to be so complete as to obscure all evidence of pigmentation.

Hair colour

The head, pubic and axillary hair is one of the most resistant identifying features, sometimes lasting millennia in favourable environments. The original colour may, however, alter after burial, becoming a brownish-red or 'foxy' colour within as short a time as 3 months. The colour may be obscured by dirt or staining and expert treatment (usually by a biologist or museum technologist) may be required to restore the original colour. The possibility of deliberate chemical coloration or bleaching before death may have to be considered and again expert chemical analysis in a forensic science laboratory may be needed to confirm or eliminate this if the hair colour conflicts with other positive evidence of identity.

Hair structure

This is more the province of the forensic biologist or anthropologist, but factors such as whether the hair ends have been cut or are naturally pointed may sometimes have importance in identity. Racial features exist, Negroid head hair being dark and having a spiral twist with a flattened, elliptical cross-section. Mongoloid hair is less pigmented and is straight with a cylindrical cross-section. Caucasian hair is round or ovoid in cross-section, but shows great variation in colour and morphology compared with the other two major ethnic groups. Though head hair in Caucasians is round to ovoid in section, eyebrow hair tends to be triangular and pubic hair flattened. The cells of the hair root can give a DNA profile and the analysis of mitochondrial DNA (mtDNA) from shafts of shed hairs has gained high importance in forensic casework.

Microscopic examination of the hair can assist in determining the species, if not human. Human hair has broad groupings when viewed microscopically. However, the topic of individual identity from hair is now the province of forensic biologists, and has a specialism and literature of its own.

Tattoos

Deliberate ornamentation of the skin by introducing pigments under the epidermis has been practised for millennia and in all parts of the world. The word 'tattoo' comes from the Polynesian '*ta tau*', meaning 'to mark'. Some races such as the Ibans of Sarawak may be tattooed over much of their body surface, but many males and some females in most countries have localized tattoos, which can be of considerable assistance in identification. Many different pigments are used, as well as more unusual substances such as soot or gunpowder. The colour is pricked into the upper dermis with a sharp instrument, usually a needle used manually, or by an electric vibrator.

Once under the outer skin, the material persists for a long time. Colours such as blue, green or red may be scavenged by tissue cells and leached into the lymphatic system after a number of years or decades. Black pigments, usually carbon particles in the form of Indian ink, are so resistant as to be virtually lifelong, though some may be transported to regional lymph nodes (Fig. 3.2).

Hellerich found in 31 of 275 unselected forensic autopsies tattoos on one or both sides of the upper extremities, which were nearly always accompanied by pigmentations of the axillary lymph nodes. The deposits of tattoo pigment reflected the colour ingredients of the tattooed skin and could already be identified with the naked eye.[1] Lehner *et al.* investigated the decrease of pigment concentration in red tattooed skin and estimated a decrease of 87–99 per cent of pigment concentration in skin after tattooing.[2] Thus an original pattern of different colours may fade differentially over years, the black areas standing out in strong relief.

The patterns are so diverse as to defy classification, though much has been written on the subject. From the point of view of identity, tattoos may be useful in both a general sense and for comparison with potential victims. The general applications require a knowledge of ethnic, national, cultural, religious and social practices, so that the tattoo can be assigned to some particular group of people (Fig. 3.3). In Western society, the popularity of tattooing changes from time to time. The appearance of tattoos varies geographically and can have a very specific meaning assigning their bearer to a particular (sub)culture. From the beginning of the 20th century tattooing in Europe was predominant among sailors and other working class members.[3] Later it was picked up by the punk and gay movement, mainly as a protest against the conservative middle class society, remaining as a provocative sign of various subcultures.[4] In the last two decades the popularity of tattoos has significantly increased involving a larger part of the population and reducing its signalling function so that a tattoo does not necessarily anymore assign the bearer to a certain subculture.[5]

Tattoos are of most use when individual enough to be compared with known designs on a missing person. The design is often supplemented by actual names, though these are mostly forenames rather than family names. Designs are by no means unique and a professional tattooist may turn out hundreds of identical decorations, so names are a bonus when trying to achieve identity (Fig. 3.1).



Figure 3.1 Individualistic tattoos may assist the identification of unknown persons.



Figure 3.2 Black tattoo pigment in a regional lymph node.



Figure 3.3 Shoulder region of a decomposed body recovered from the sea showing a tattoo with Cyrillic letters (D, K, B, F) and a flag with a star and hammer and sickle, suggesting a connection with the Russian Baltic Fleet.

Initials may be used, but these can be misleading due to the use of nicknames and diminutives, such as 'B' for Bill, rather than William. In general, males have the names of girls on their tattoos, but initials are usually their own. Conversely, females with tattoos almost always display the names of sweethearts, rather than their own. Some tattoos may be numbers or unadorned names, the most tragic examples being those from Nazi concentration camps during the Second World War.

The photography, distribution and matching of tattoos is police business, but the pathologist's duty is to make them accessible and clear to the police. Where decomposition has set in, tattoos may be obscured by wrinkled, peeling epidermis, but often this can be wiped off to reveal tattoos that are more vivid than on fresh skin. Once the tissues become green and slimy, then the pattern progressively vanishes, but early decomposition is no barrier to recognition. Where skin pigmentation may hide a design, skin slippage may actually enhance the clarity, especially of the weaker colours like blue, red and green. Attempts at the deliberate removal of tattoos are common, either from regret at having disfigured the body during youthful or drunken euphoria, or to remove evidence of identity. Many methods have been used, from surgical excision to scarification with sandpaper and from caustic soda to electrolysis. All methods depend upon damage to the epidermis and dermis, with consequent inflammation and scar formation. The tattoo can certainly be removed, but always by replacing it by a cicatrix to a greater or lesser extent, which will itself indicate that something pre-existed at that site.

It has been suggested (PA Edwards, personal communication) that the chemical nature of tattoo pigments might be used in identification. Although all manner of substances have been used to tattoo, most tattooists use black pigments containing carbon, green pigments containing potassium dichromate and red pigments containing mercuric chloride. Others use aniline-based dyes, so that microextraction and analysis in a forensic science laboratory might confirm or exclude the tattoo having been executed by a particular artist in the locality.

Finger, palm, foot and lip prints

The science of fingerprints, their classification, retrieval from records and methods of recording lie in the domain of police procedure, and, as with tattoos, the pathologist's role is merely to facilitate the taking of prints by police officers. Sometimes when a strange print is found at a scene of crime, the police may wish to take the fingerprints of doctors who visited the locus to eliminate them from their enquiries and there is obviously nothing objectionable about this. Indeed, some forensic pathologists who habitually assist the police leave their prints on file so that they are permanently available for exclusion. When called to a scene of death, the doctor should take care to avoid handling objects and furniture to reduce the need for such laborious screening of prints.

The doctor need know nothing about fingerprints except for his own interest, though it is as well to be prepared for the inevitable questions – no two fingerprints have ever been found to be identical and even identical twins have different prints. However, some recent claims point out that some prints are so similar that the criteria usually accepted as proof of congruence may not be sufficient. Police usually attend the mortuary to take full sets of fingerprints in the usual way by rolling ink on to the finger-pads and pressing the pulps against record cards.

The pathologist may help when there is strong rigor present, by either forcing the flexed fingers back or even by slitting the flexor tendons, though this has the danger of fouling the fingers with blood.

When the body is putrefied, the doctor can again assist by removing desquamated casts from the fingers for the police. These may need to be preserved or hardened up so that the decaying tissue does not lose further definition from the ridges that form the prints. The skin may be placed in formalin, alcohol or glycerine solution, especially where maceration in an immersed body has caused swelling and blurring of the epidermis.

Recently, more novel techniques using latex and other similar plastic materials have been devised to help the pathologist.[6] There exist two rare closely related autosomal dominant ectodermal dysplasia syndromes: Naegeli–Franceschetti–Jadassohn syndrome (NFJS) and dermatopathia pigmentosa reticularis (DPR) that share the complete absence of fingerprints.[7,8] Rarely, a criminal may attempt to obliterate his fingerprints by scarring the finger-pads. To be effective, this must be drastic enough to damage the underlying dermis and the consequent cicatrices will be more obvious than the original prints. Surgical grafting of skin from elsewhere on the body has been reported as a means of removing fingerprints, but again the result is self-evident proof of nefarious intent.

As with fingerprints, the skin pattern of palms, soles and even lips are said to be unique and have been used in identification, but again this is really police business. The pattern of veins on the back of hands is also said to be characteristic to one individual.

Identifying scars

These can be important in the identification of unknown bodies, even when some degree of putrefaction exists. The author (BK) used a cholecystectomy scar and scars of old surgical incisions on the legs to identify the body of a homicide victim submerged in a river for 6 weeks and many other cases are on record where scars provided similar vital information. Probably the best known instance is the case of Dr. Hawley Crippen, who was accused, convicted and hanged of murdering his wife in London in 1910. Much forensic controversy was generated then over the distinction between a surgical scar and a skin crease on a piece of abdominal wall of the human remains found in the Crippen's coal cellar and believed to belong to his wife Cora. Quite recently Foran and coworkers were able to prove, based on the genealogical and mitochondrial DNA research, that the tissue on the pathology slide used to convict Dr. Crippen was not that of Cora Crippen. Moreover, that tissue was male in origin.[9] This case is a prime example that illustrates how important it is to retain the tissue samples in a medicolegal case.

Scars on the skin may arise from any previous injury that has breached the epidermis, as superficial injuries to the upper layer of skin will heal without a trace. Where the dermis has been entered, healing occurs by organization of the plug of blood clot and/or granulation tissue, as described in Chapter 4. If the wound is narrow, such as that inflicted by a surgical instrument, sharp knife, razor or glass, then if the edges are kept together, especially by stitches or dressings, the resulting scar will be narrow and insignificant. Gaping or infection will widen the scar and obviously larger lacerations or burns will result in similarly greater scarring. In relation to identification, scars are of use only if those thought to be the victims are known to have similar scars, both in nature and position. The specificity of scars varies greatly, as many people may have appendicectomy scars, and many females have had hysterectomies or other gynaecological operations that leave lower abdominal scars. As always, scar evidence must be taken in conjunction with all other details of identity, but where a cicatrix is unusual or even unique in nature or position, its value is greatly enhanced (Fig. 3.4).

Turning to traumatic scars other than surgical, the pathologist may be able to recognize the cause, which can assist in identity. Naturally the vast majority of non-surgical scars are the result of accidental trauma and where family, friends, photographs or medical records indicate the existence of specific scarred sites on the body, then confirmation of identity may be greatly assisted or confirmed.

Some scars are deliberately produced as part of some ethnic or religious tradition, such as the facial scars in some African tribes, as well as deformed or perforated ear lobes or lips. Regrettably, another class of scars is becoming more common in many parts of the world, due to physical torture; this is dealt with in Chapter 10. Linear scars, cicatrices of burns, keloid overgrowth (especially in negroid races), hyperpigmentation or depigmentation and other persistent lesions may assist in identity in the appropriate circumstances. Much depends on the accuracy of the information concerning the person thought to be the victim; relatives are notoriously vague and inaccurate about medical



Figure 3.4 Nipple areola complex reconstruction with areola tattoo.



Figure 3.5 Post-mortem imaging is increasingly used for identification. Image from a corpse in a state of severe putrefaction reveals changes, which are in keeping with an old femoral fracture with surgical marrow nailing and removal of the nail (arrows). (Reproduced by kind permission of Professor C. Jackowski.)

matters and frequently confuse different surgical operations, thus misleading the investigators about scars. Sometimes surgical scars may be almost invisible. The author (PS) once worked as surgical assistant in a private hospital where one of the surgeons used to perform appendicectomy (in non-acute cases) through a 1 cm wide incision, closing the wound, for cosmetic reasons, with subcutaneous catgut sutures. Most of these wounds healed with virtually no scar whatsoever, unless the person had a tendency to keloid formation. Wherever possible, old hospital records or the notes of a family physician should be obtained.

The old scars of wrist- or throat-slashing indicate previous attempts at suicide. Large areas of scarring on the trunk or limbs that have parallel grooves and marginal extensions suggest severe brush lacerations, probably from a traffic accident. Knife stab wounds may scar in an elliptical fashion, sometimes even with a blunt and a sharp end indicating the position of a single-edged blade. Bullet wound scars may persist – and in 1989, became a matter of political controversy over the identity of Nazi war prisoner Rudolf Hess, who was alleged to have been an imposter because he had no scar from an old rifle bullet wound through the chest. Burns may provide good evidence of identity, especially if they are widespread cicatrices that may have been quite noticeable during life. Cigarette burns are frequently seen in victims of child abuse, torture in custody, inter-prisoner violence, self-harm in individuals with low self-esteem and personality disorders.[10] Similar scarring resembling cigarette burns, though rarely observed in the Western countries is more frequently seen in Asia due to moxibustion, a traditional Chinese medicine therapy using moxa (mugwort herb) directly by burning it on a patient's skin.[11]

Many scars on the fronts of the lower legs may indicate the repeated stumblings of a chronic alcoholic, who frequently walks into or falls over furniture.

The age of scars

The age of a scar is very difficult to assess and, once it becomes mature, no change will occur for the rest of the person's life. When a linear wound is inflicted, be it a surgical operation or a knife slash, the edges become mechanically strong within a week, assuming that no infection or haematoma develops. The wound is brownish red at this stage and remains vascular for several months, depending upon its width. The pinkness of contained blood vessels gradually fades and a narrow surgical incision may be white by 4–6 months. The avascular collagen tends to shrink for a year or so, but is white–silver after a year and remains in this state indefinitely. These times are variable depending on the nature of the skin, its pigmentation and the part of the body involved. Where a wound crosses a skin crease that is frequently flexed or extended, it tends to gape and widen, the subsequent scar following suit.

Histology does not contribute much to the examination of scars, except to confirm that a skin mark actually is a scar. Stains for collagen or elastin may confirm the discontinuity in the dermis. Scars do not carry hair follicles, sweat glands or sebaceous glands, though an occasional accessory skin structure may be present as a result of the inclusion of a viable fragment of original skin in an irregular wound – or where surgical repair has detached or invaginated a piece of the margin.

Occupational stigmata

Formerly given prominence in most textbooks, distinctive physical marks of occupation have decreased in incidence and importance. They are still of use in certain areas, but local knowledge of occupations and industries is required. The Victorian days of pen callosities in clerks and shoemaker's kyphosis have gone, but many other occupations have their stigmata, though most are relatively non-specific. The best known is the 'blue scar' of coal-miners, an involuntary tattoo caused by dust entering small lacerations on the hands and face (Fig. 3.6). Some miners and quarrymen also have small facial scars due to rock splinters scattered



Figure 3.6 Careful external examination may yield evidence that can assist identification. The small 'blue scar' on this forehead establishes that the deceased had been a coal-miner; coal dust enters small lacerations and remains visible after healing. Virtually every coal-worker has such marks on hands or face.

during blasting. Steel workers and foundry males may have tiny burn scars on exposed areas from the spattering of hot metal. In more general terms, examination of the hands will indicate whether the deceased was a manual worker or involved in more sedentary occupations. Cuts, scars, callosities and hyperkeratosis of the hands are obvious indicators of rough work.

Internally, black, dust-laden lungs – with or without pneumoconiosis – points to mining, as coal trimmers no longer exist as dock workers. Thickened, pearly plaques on the parietal pleura and diaphragm are caused by exposure to asbestos, though the widespread use of this substance in the past in so many industries makes it less helpful in identifying the occupation.

The stature of an intact body

The stature of a corpse is not necessarily exactly that of the person measured during life. In the mortuary, care must be taken to measure the body from heel to crown, and not to accept the mortuary attendant's or funeral director's 'coffin measurement', which is made from toe to crown. Because of the usual plantar flexion of the foot, this latter height may be as much as 10 cm longer than the heel– crown length.

The height of a dead body may differ from the height during life in either direction, being slightly longer or shorter, though lengthening is much more common. In addition, the measured height may change a little at different periods after death. Because of the complete loss of muscle tone in the first stage of flaccidity, relaxation at large joints, such as the hip and knee, together with the lost tensioning effect of paraspinal muscles on intervertebral discs, the body may lengthen by up to 2–3 cm. Rigor mortis may then replace the muscle tone, shortening the body and tending to flex the legs a little. When rigor passes off and decomposition sets in, joints become lax. Loss of tension in the intervertebral discs tends to shorten the spinal column and hence the total height by a centimetre or so. According to Trotter and Gleser, the average increase is about 2–5 cm.[12] The errors in getting a really accurate post-mortem length include the difficulty of locating the measuring device exactly at the heel and the crown of the head, as well as fully extending the limbs, spine and neck of a body in rigor.

Determination of sex in non-skeletalized bodies

This is usually obvious and rarely presents problems. The issue of intersex and hermaphroditism is so rare as to be discounted in most forensic practice, except in some areas, such as South-east Asia, where deliberate trans-sexualism in males, aided by surgical intervention to feminize the genitalia and breasts occurs more frequently. Where this problem arises, expert advice must be sought. In general, the external genitalia remain recognizable until a late stage of putrefaction. In addition, breasts and general body shape, as well as the pattern of pubic hair, reveal the sex. Female pubic hair usually grows low on the abdomen, the upper margin being a horizontal or semicircular edge above the mons veneris. The male pattern rises more in the centre line, sometimes as far as the umbilicus. There are, however, always exceptions to these generalizations. The presence or absence of circumcision should be noted, as it may help in identification of certain ethnic and religious groups such as Jews and Muslims. Naturally it is of assistance here in eliminating only those where the prepuce is present, as many males of other religions are circumcised.

Clothing, hair length, hair style, hair coloration, earrings and other jewellery are no longer the reliable guide to sex that they once were. In certain cultures and religions there are obvious criteria that can assist in the determination of sex, but these are rarely needed as the more apparent anatomical differences can be used. Where putrefaction is advanced, examination of the internal pelvic organs may still reveal unequivocal evidence of sex. Internal viscera are often in better condition than the outside of the body. The uterus is the organ in the body most resistant to decomposition, though the prostate is also quite persistent.

Where almost total dissolution exists, then radiology of the pelvis or the criteria used in skeletal assessment can be used. DNA analysis now can give give additional powerful tools in sexing and determining the human origin of subanatomical fragments. As far as the diagnosis of species is concerned the mere amplification for a human DNA sequence may be sufficient, along with immunoassays that detect species-specific proteins. Sex is now generally established on soft tissues via amplification for the amelogenin gene.[13,14]

Age of non-skeletalized bodies

Determining the personal age of a corpse is far harder than determining its sex. Ageing a living person can be difficult and a wide margin of error exists, especially as age advances, so the same exercise in a corpse can be expected to be even less exact.[15] Where the body is relatively intact, the usual criteria known to the man in the street are applied to make a general estimate. Hair colour is of general applicability, though every one knows of someone whose hair is grey at 25 or someone who is dark haired at 70. The loss of elasticity in the skin, its thinness and hyperkeratosis and its red Campbell de Morgan spots are indicators of senility. These days teeth are less useful than in the past from the point of view of extractions, clearance, full dentures and oral hygiene, but the general impression remains. The objective determination of age from tooth attrition is a matter for a specialist forensic odontologist (see Chapter 26).

The eyes are useful, in that a grey or white ring around the pupil – the 'arcus senilis' – is rarely seen below 60 years. In infants and children, the height and weight may be compared with standard tables, but developmental defects, disease and malnourishment may introduce considerable errors. Internally, the evolution of degenerative changes such as arterial atherosclerosis and arthritis, may give a general impression, but personal variation is so great that it offers little more than a distinction between 'young' and 'old'. Where a distinction has to be made in a double death between two people of markedly different ages, however, then these generalities may be of considerable use. Up to the age of about 20–25, teeth, ossification centres and epiphyseal fusion are good indicators, but these are described in the section on skeletalized material.

Recent research, aimed mainly at skeletalized bodies but available for any corpse, is the determination of the racemization ratio of amino acids in teeth, as the preponderance of laevo- and dextro-compounds appears to be a function of personal age.

In addition, the Lamendin technique (which has replaced the more complex Gustafson technique) on teeth, described later, is also applicable to a non-skeletalized body, if ageing is important.[16–25]

Ancestry

Much of the identification of ancestry depends on common knowledge and recognition of various ethnic traits, and is not primarily a medical problem. Everyone can recognize the deep pigmentation of a West African, the epicanthic folds of the Mongoloid ancestry, the red-haired Celt and the pale blond common in Scandinavia. There is a wide and almost continuous range of biological variability, however, not only because of extensive ethnic interbreeding, but also because of marked variations even within a coherent racial group. The most elliptic cross-sectional shape is observed in African hair, whereas Asian hair is almost circular and Caucasian hair shows an intermediate elliptic shape. In terms of variability, African hair shows the greatest percentage of section variability, compared with Asian and Caucasian hair.[26]

In the intact or only partially decomposed body, the following factors may be used as pointers to ethnic classification, but the non-specificity of most of these must always be borne in mind:

- Clothing, ornaments and other associated objects. A vast catalogue can be assembled (such as the string around the wrist in Hindus), but it must be borne in mind that other ancestry may adopt these through choice, marriage or deception.
- Hair texture, style and length and beards. Examples are the hair of the Sikh, the beard of the orthodox Jew, the crinkly hair or 'peppercorn' (clumped growth) of some Negroids, the multiplaiting of Rastafarian West Indians, the straight black hair of Asians and the ginger hair most common in Celtic people. With affected styles and convincing modern coloration and texture alteration, however, these

features can be most misleading. Forensic science techniques may be needed to detect and identify bleaching and dyeing changes in hair.

- Physical artefacts include penile and vulval circumcision, nose and ear piercing, lip perforation, tribal facial scars, and earlobe distension in East Africans and some tribes in Sarawak. More bizarre forms, such as neck-stretching by rings, are now rare. Tattoos (mentioned elsewhere) may have an ethnic basis, as in the Ibans of Sarawak.
- Facial appearance is, of course, a major criterion with the high cheek bones and epicanthic folds of the Mongoloid peoples, and the prognathism and nasal differences in Negroid peoples. So many intermediate forms exist, however, such as the Slav and the Polynesian, that only the classic groupings can be identified with confidence.
- Body size gives rise to the same uncertainty, especially as racial differences have lessened with better nutrition in some groups. It is obvious, however, that Japanese are generally smaller than northern Europeans and that in Negroid bone structure the femora are proportionately longer and less curved than those of other ancestry. Teeth are discussed later, but the shovel-shaped upper central incisors of the Mongoloid ancestry can be helpful on occasions, though they are not absolutely specific.
- Finally, skin pigmentation can obviously differentiate the Negroid ancestry from the other main groups, though again there is a continuous range of skin colour. To a lesser extent the slighter melanin content of the skin of Mongoloid ancestry is recognizable, but merges into the variable tints of Semitic, Asian and Mediterranean peoples.

It may well be that, in the near future, genetic DNA studies will revolutionize this aspect of identification. They have done so for personal identification.

Identification by DNA characteristics

Identification of human remains by DNA is nowadays standard procedure thanks to the myriad of alleles and DNA regions in general which can be amplified and used to compare genetic patterns. Human stains, residues, and remains can now be identified with almost 100 per cent certainty in most cases. In the case of human remains only two factors can hinder genetic testing: the degradation of the sample and related problems of DNA extraction, and the lack of appropriate antemortem comparative data. In the first instance DNA may pe particularly 'ruined' by taphonomical factors, or well-preserved DNA may still be present but difficult to free from hydroxyapatite crystals or from byproducts of putrefaction, which may act as PCR inhibitors. In the second case, adequate antemortem DNA sources (eg. toothbrushes, razors, etc.) may not be available or appropriate relatives may not be present for a proper DNA comparison.

Identification of skeletalized remains

One of the classic problems of forensic pathology, the identification of a whole or partial skeleton, involves techniques and expertise that span a number of disciplines from anatomy to radiology, from archaeology to dentistry, as well as genetics. It often overshadows the equally important need to identify intact or decomposed corpses, but the disproportionate amount of space occupied by skeletal identification in most textbooks can be partly justified by the fact that bones can survive for decades, centuries or millennia, so that the cumulative reservoir of material is vast. As was observed in relation to intact bodies, the procedure for identifying bony remains falls into two distinct sections:

- allotting the bones to general categories based on absolute criteria concerning species, ancestry, sex, stature, age and date
- comparative studies, where the remains are matched against ante-mortem data derived from those people who might be potential victims.

The general categorization of skeletal remains

When objects thought to be skeletal remains are found, the following questions need to be asked and, where possible, answered:

- Are they bones?
- Are they human bones?
- What is the sex?
- What is the stature?
- What is the ancestry or race?
- What is the age?
- How long have they been dead and/or concealed?
- What was the cause of death?

Are the remains actually bones?

This question is not as facetious as it may seem, as untrained persons may provide objects that falsely resemble bones. The author (BK) has been offered shaped stones, plastic and even hard wood, which were thought to be bones. The mistake is even more common when these objects are mixed with undoubted bones, usually animal in origin, which may be found burnt, buried or mingled with rubble.

Recognition is usually easy, by the shape, texture and especially weight of the objects. Greater difficulty may be experienced when simulated human 'bones' are found, such as the 'radius' brought to the author (BK). This originated from a medical student's anatomical skeleton and was made from plaster coated with a plastic polymer. Visually it was indistinguishable from a real bone, but the abnormal lightness indicated the true nature. In the more difficult cases, microscopic and chemical tests will usually lead to an adequate solution (Fig. 3.7).[27]

Are the bones of human origin?

The recognition of species is important, but deciding on a human origin is usually easy, unless marked fragmentation has occurred. Many animal bones are found by the general public and police who are not qualified to decide whether they are human. Extensive rebuilding programmes and the renovation and demolition of old sites reveal many caches of bones, but in the authors' experience the majority are of animal origin, often originating from butchers' debris.

First, the size is assessed and many small, slender bones excluded on obvious grounds. Even a turkey thigh cannot be mistaken for a metatarsal, nor a beef rib for human. The gross anatomy is then studied, and even if the pathologist makes no pretensions to being a comparative anatomist, the majority of intact animal bones can be recognized from their lack of correspondence to any human bone.[28] Difficulties arise with smaller bones from some animals, especially the hands and feet, where digits, metatarsals and metacarpals require careful study to distinguish them from the human (Fig. 3.8). Several errors have been made in respect of bear paws, which closely resemble the human hand.

When bones are incomplete or fragmentary, the problems escalate rapidly. If the ends of longer bones are present, then their non-human shape may be more readily determined, but cylindrical segments of the central shaft have little in the way of distinguishing features, apart from size. Burnt bone fragments offer similar problems, added to which is the possibility of heat distortion and shrinkage (Figs 3.9, 3.10).[29]

The advice of a forensic anthropologist is needed in such cases, or if not available, an anatomist preferably one with forensic experience and enthusiasm for the project. Unfortunately, every anatomist is not necessarily an osteologist and it may be more effective for the bone to be examined by a pathologist who has both enthusiasm and the relevant reference books.



Figure 3.7 All bones are not human – and not all 'bones' are bones. The smaller bones are animal, but the central 'radius' is from an ersatz student skeleton, made from plastic material, but thought by the police to be evidence of a criminal death.


A
B
C
ISTITUTO DI MEDICINA LEGALE - MILANO
LABANOF
0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15
ISTITUTO DI MEDICINA LEGALE - MILANO
LABANOF

Figure 3.8 Striking similarity between chicken bones (**A**), human metatarsals (**B**) and fetal long bones (**C**). (Milano skeletal collection reproduced by kind permission of Professor C. Cattaneo.)



Figure 3.9 An example of type of debris that may be found when a body has been cremated by log fire. When the charred pieces of wood are small and commingled with fragments of burnt bone they are difficult to distinguish from each other and need to be carefully sifted and analysed.



Figure 3.10 A piece of burnt bone, which according to its shape and size can be identified as a fragment of the distal part of a human femoral bone.



Figure 3.11 Histological structure of compact bone showing species-characteristic differences in osteon morphology in a young human individual (**A**), old (**B**), sheep (*Ovis aries*) (**C**) and cow (*Bos taurus*) (**D**). (Milano skeletal collection reproduced by kind permission of Professor C. Cattaneo.)

Histological examination may offer a species differentiation – or at least help to exclude a human origin. The Haversian architecture is different in many animals and frequently osteon size and shape may help exclude human origin, but the few specialist papers on this subject must be consulted for details (Figs 3.11, 3.12).[30]

Where the animal species is relevant to the enquiry, then a veterinary or comparative anatomist must be consulted. If the bones are too fragmentary to provide any anatomical data, then serological investigations must be attempted. These depend on species-specific proteins being extracted from the bone into solution where



Figure 3.12 Histological structure of compact bone of cat (*Felis catus*) with irregularly margined osteons with small Haversian channels. (Milano skeletal collection reproduced by kind permission of Professor C. Cattaneo.)



Figure 3.13 Two recovered and reassembled skeletons. After cleaning, the bones should be laid out in correct anatomical position, to gain an approximate direct measure of the stature, allowing as well as possible for lost soft tissue. The upper skeleton, obviously male, shows the frequent loss of small hand and foot bones, but no injuries. The lower remains, from a hidden 40-year-old homicide, reveal that the body was sawn into six sections, there being cuts above the knees and through spine, scapula and humeri.

they can be tested against specific antisera, particularly monoclonal ones. Thus the test is essentially seeking plasma constituents within the bone, the recognition being carried out by techniques such as enzyme-linked immunosorbent assay (ELISA) or radioimmunoassay (RIA).[29,31,32] Once again, DNA testing also may solve the problem.

The determination of sex

The accuracy of determination of the sex of skeletal remains varies with the age of the subject, the degree of fragmentation of the bones and biological variability.

Particularly when studying the skull and pelvis, a subjective impression by the experienced observer defies complete analysis, yet objective measurement may be no more accurate: in other words, the processes comprise morphological traits versus morphometry. The determination of sex is statistically the most important criterion, as it immediately excludes approximately half the population whereas age, stature and ancestry each provide points within a wide range of variables. It is further important for the correct selection and application of all sex-dependent metric formulas. Obvious sex differences do not become apparent until after puberty, usually in the 15–18-year period, though specialized measurements on the pelvis can sometimes indicate the sex even in fetal material. Sex and age are linked, especially where body size and weight are concerned. Similarly, ancestry confuses sexing, for example, the size of the supraorbital ridges in a normal negroid female may exceed those in the average Caucasian male.

The accuracy of sexing is hard to estimate, as various loading factors exist. Krogman comments that he scored 100 per cent accuracy using the whole skeleton, 95 per cent on pelvis, 92 per cent on skull, 98 per cent on pelvis plus skull, 80 per cent on long bones and 98 per cent on long bones plus pelvis. He admitted, however, that, as most anatomy department material has a sex ratio of about 15:1 in favour of males, marked bias could be introduced by assigning all doubtful bones to the male category.[33–35]

Stewart records that, for the whole skeleton, one can expect a 90–95 per cent success rate and for the skull alone only 80 per cent, but, if the mandible is also present, this rises to 90 per cent.[36–41] In general, adult female skeletal measurements are about 94 per cent that of the male of the same ancestry, but different measurements may vary from 91 to 98 per cent.

The skull

The following features develop after puberty and are modified by senility, so are applicable only between about the 20th and the 55th year. Age as well as ancestry has a profound effect.

- **General appearance.** The female skull is rounder and smoother than the rugged male.
- **Size.** Male skulls are larger, with an endocranial volume some 200 ml greater.

- **Muscle ridges** are more marked in male skulls, especially in occipital areas where larger muscles are attached to the nuchal crests, and in temporal and mandibular areas for larger masseter and temporalis muscles.
- **Supraorbital ridges** are more marked in male skulls and may be absent in female.
- **Mastoid process.** This is larger in male skulls.[42]
- **Frontal and parietal eminences.** These are more prominent in female skulls, which resemble the shape in an infant more than in a male.
- **Palate.** This is larger and of a more regular U-shape in males. The smaller female palate tends to be parabolic.
- **Orbits** are set lower on the face in the male skull, with more square and less sharp edges (especially upper edge) than the female.
- **Glabella** (central forehead eminence above the nose) is more marked in males and orbital margines are rounder and less sharp
- **Nasal aperture.** This is higher and narrower in the male skull and has sharper edges. The nasal bones are larger and project further forward to meet at a more acute angle than in the female.
- **Forehead.** This is high and steep in the female skull, with a more rounded infantile contour than the male.
- **Zygomatic process.** The posterior ridge projects back beyond external auditory meatus in the male skull. The zygomatic arches bow outward more than the female, where they remain more medial.
- The nuchal crest is more pronounced in males.
- **Mandible.** This is large in the male skull, with a squarer symphysis region. Female jaws are more rounded and project less at the anterior point. The vertical height at the symphysis is proportionately greater in the male. The angle formed by the body and the ramus is more upright in the male, being less than 125°. The condyles are larger in the male skull, as is the broader ascending ramus, and there is a more prominent coronoid process.

These sex variations represent the 'typical' White and, to a great extent, Asian skull. There is considerable overlap, especially in subjects from the Indian subcontinent, where osteological sex differences are much less marked. The criteria set out above exclude prepubertal and senile persons, and are less valid for those outside the 20–55 age group. For methods of sexing by discriminant function analysis, the work of Giles and Elliot should be consulted.[43]



Figure 3.14 Frontal view of male and female skull. The male (left) is larger, more massive and has heavier eyebrow ridges. The chin is squarer and the mandible heavier, The female has relatively larger height orbits, a smoother cranium and fuller frontal and parietal eminences.

In recent years craniometry has been applied to sexing the skull and multiple accurate measurements between discrete anatomical points have been used to produce discriminant function analysis. The papers of numerous authors must be consulted for details of this sophisticated and difficult technique that is accurate in 83–88 per cent of cases. The frequency of correct sexing is no greater than more subjective methods, but commands a greater degree of confidence level in respect to its accuracy (Fig. 3.14).[44–55]

Sex characteristics in the pelvis

The post-pubertal female pelvis is wider and shallower than the rather upright male girdle to allow for the passage of the fetus during childbirth.

As in the skull, the male pelvis is more rugged because of the attachment of stronger muscles. It stands higher and more erect than the smoother, flatter, female pelvic girdle. The subpubic angle, measured at the medial intersection of two lines drawn along the best approximation of the lower border of both inferior pubic rami, approaches 90° in the female pelvis, but usually about 70° in the male.

This is often a subjective measurement, however, and depends in turn upon the shape of the pubic bone itself. When the line of the inferior ramus is projected medially and intersected with a horizontal line laid across the upper border of the superior ramus, the reverse size of angle is seen, the male being wider than the female.

The body of the pubic bone, the block lateral to the symphysis, tends to be triangular in shape in the male, whilst the female pubis is more rectangular.[56,57] Certain sexual variations in the pubis have been used by Phenice. In the female these are:

- a bony ridge ('ventral arc') running down the ventral surface from the pubic crest
- a concavity of the lower margin of the inferior pubic ramus immediately lateral to the lower border of the symphysis
- a ridge of elevated bone on the medial aspect of the ischiopubic ramus, immediately lateral to the symphysis; in the male this area is broad and flat.

The 'ischiopubic index' devised by Washburn may be helpful, in which the pubic length (×100) is divided by the ischial length.[58] The measurements must be carefully made, the pubic length being from the plane of the symphysis to the reference point in the acetabulum and the ischial length being from the same point to the most distal edge of the ischium. The reference point is the site of fusion of the three elements of the immature innominate bone, usually marked by a notch in the articular surface of the acetabulum.[59] If the ischiopubic index (in White race) is less than 90, the pelvis is male; if over 95, it is female. The acetabulum is larger in the male, being an average of 52 mm in diameter, compared with 46 mm in the female. The male joint cup also faces more laterally than that of the female, which tends to look more forward. Naturally, acetabular size is related to that of the femoral head, which will be considered later. The greater sciatic notch is an important criterion, being deep and narrow in the male, wide and open in the female. The angle formed by the margins approaches closer to a right angle in the female than it does in the male. Hrdlicka and Harrison both felt that the greater sciatic notch was one of the best discriminants for sex, the latter claiming a 75 per cent success rate using this criterion alone (Fig. 3.15).[36,60]

The obturator foramen is somewhat ovoid in the male, but triangular in the female. The pre-auricular sulcus, which marks the attachment of the anterior sacroiliac ligament, lies just lateral to the sacroiliac joint and is usually well marked in females but often absent in males. The pelvic inlet, looked at from above, is more circular in the female, the male being heart-shaped as a result of the protrusion of the sacrum into the posterior brim.[61] A number of other pelvic 'indices' have been devised by various authors (see, for example, the work of Turner, Greulich and Thomas, Caldwell and Molloy, Straus, and Derry).[61–66]

Sex characteristics in the sacrum

The sacrum is functionally part of the pelvis and shares in its sex variations (Fig. 3.16). The female sacrum is wide and has a shallow curve, again related to the larger pelvic canal for childbirth. It is shorter in the female and the curve is limited almost entirely to that distal part below the centre of the third sacral vertebra. The male sacrum may have more than five segments, which is rare in the female. The curve in the male is



Figure 3.15 Male and female innominate bones. (Milano skeletal collection reproduced by kind permission of Professor C. Cattaneo.)



Figure 3.16 Female and male sacrum. (Milano skeletal collection reproduced by kind permission of Professor C. Cattaneo.)

continuous down the whole bone and there may even be a slight forward projection of the coccyx. Fawcett compared the transverse diameter of the first sacral vertebra (CW) with that of the base of the sacrum (BW). The formula CW × 100/BW averaged 45 in the male and 40 in the female.[67] Kimura has developed a 'base wing index', where the relative widths of the wing and base provide discriminant function coefficients for sex determination.[68] The ilium and sacrum of 2845 skeletons were examined by Dar and Hershkovitz for new bone formation and for bridging/fusion in/across the sacroiliac joint. They found that sacroiliac joint bridging (SIB) was present in 12.3 per cent of the males and 1.8 per cent of the females. In 97 per cent of the males bridging was extra-articular, whereas in all females bridging was intra-articular.[69]

Sexing from the long bones

The femur is the most useful, its length and massiveness themselves being significant. There is, as usual, considerable overlap of all long-bone sex characteristics, but Brash's series showed that the maximum (oblique) length in the male femur was around 459 mm, while that of the female was only 426 mm. Other figures from Pearson and Bell suggested mean values of 447 mm for males and 409 mm for females.[70] Using the trochanteric oblique length, they suggested a range of 390–405 mm for females and 430–450 mm for males, though there was the usual overlap in the middle. Ancestry and nutrition (which is related to the era and the place in which the samples were obtained) must be allowed for in such measurements.

The size of the femoral heads is claimed to be a better discriminant of sex, the vertical diameter being said by Pearson and Bell to be greater than 45 mm in the male and less than 41 mm in the female, though again there is an overlap in the distribution curves around the 43 mm size (Table 3.1). Maltby, however, measured 43–56 mm in the male and 37–46 mm in the female.[71]

Femoral head size is part of Pearson's 'mathematical sexing of the femur', which incorporates several measurements (Table 3.2). Dwight studied the size of both femoral and humeral heads, claiming that they were more useful than bone length.[72] Once again, discriminant function sexing has been carried out, using a number of measurements. Details should be sought in the work of Black and of Iscan and Miller-Shaivitz.[73,74]

Another sex trait in the femur is the angle that the shaft makes with the vertical. Because the pelvis is relatively wider in the female, the shafts have to slope more to converge at knee level, so that the condyles at the lower end of the femur sit horizontally on the tibial plateau. Thus when a female femur is seated on its condyles on a flat surface, the angle the shaft makes with that surface is of the order of 76°, while a male bone is more upright, the angle being around 80°. The angle of the neck on the shaft of the femur (the 'collodiaphyseal angle') was studied by Godycki, the results suggesting that a bone with an angle of less than 40° had an 85 per cent chance of being male, while if the angle exceeded 50°, there was a 75 per cent chance of it being from a female.[75]

Table 3.1 Dwight's table for sexing from humeral and femoral head diameters (in millimetres)

	Vertical humeral	Transverse humeral	Vertical femoral
Female	42.67	36.98	43.84
Male	48.76	44.66	49.68
Difference	6.09	5.68	5.84

Table 3.2 Pearson and Bell's table for the 'mathematical sexing of the femur'.[70] The area of uncertainty extends in increasing degrees of confidence outwards from the central column to the more definite limits on each side. Measurements are given in millimetres

	Male	Male or female	Female
Vertical diameter of head	>45.5	43.5–41.5	<41.5
Popliteal length	>145	114–132	<106
Bicondylar width	>78	74–76	<72
Oblique trochanteric length	>450	405–430	<390

Most workers have worked with dry bone specimens; when methods using fresh bone are used, allowance must be made for articular cartilage where relevant. For example, the vertical diameter of a femoral head is 3 mm less in the dried specimen.

Sex determination from other bones

The sternum may be helpful in that the length of the manubrium in the female may equal or exceed half the length of the body, while the manubrium of the male is less than half the body length. This was claimed in the nineteenth century by Hyrtl, but was denied by Krogman and by Dwight.[34,76,77] The latter claimed that the ratio of manubrium: body was 52:100 in females and 49:100 in males, a poor discrimination. However, the method has been rehabilitated by Iordanidis, who alleged a success rate of 80 per cent using the sternum alone.[78] Stewart and McCormick used a radiographic technique and claimed total accuracy in stating that a sternal length of less than 121 mm must be female and over 173 mm must be male.[79]

The scapula has been studied extensively, but mostly in relation to age. There are relatively poor sex variations in the vertical diameter of the glenoid cavity: the threshold, according to Dwight, is 36 mm, those smaller being female. Iordanidis made an extensive study of scapular measurements and concluded that scapular height was the best discriminant, the male usually being greater than 157 mm, the female less than 144 mm.

The humerus, radius and ulna yield little helpful sexing evidence, apart from overall size. The presence of a perforated olecranon fossa at the lower end of the humerus occurs more often in females and more commonly on the left side, there being a 3.7:1 ratio compared with males. Godycki studied this and other characteristics of the arm bones as sex determinants, but their value is poor.

There are many reports on sexing from limb and girdle bones and the best approach seems to be a multiple assessment using the data for discriminant function analysis.

In conclusion, virtually every bone in the body has been tested for its sexing potential and in different racial groups; nonetheless methods relying on the cranium and pelvis, only in adults, are the most reliable.

Evidence of pregnancy from the skeleton

More accurately, parturition causes some changes in the pelvis as a result of the local trauma of childbirth, which is reinforced by multiple pregnancies. These include 'pubic scars' from the tearing of tendon insertions and periosteum around the pubic bone. The use of dorsal pubic surface and the pre-auricular sulcus as an indicator of past pregnancies is considered to be somewhat controversial.[80]

Estimation of stature from skeletal remains

When a full skeleton is available, then obviously direct measurement of the correctly assembled bones will give the original height within a few centimetres. Allowance has to be made during assembly, however, for the loss of cartilage in joint spaces and especially for missing intervertebral discs. The accuracy achieved with direct measurement is not great, in that even with an intact body there can be a lengthening of up to 2.5 cm compared with the live height. The skeleton needs scalp and heel soft tissue thickness added – and with the obvious uncertainty about the cumulative allowances for disc thickness and joint cartilage, it is unrealistic to expect accuracy of less than about 4–8 cm compared with the living height.

When incomplete skeletal material is available, calculations have to be made on the basis of one or more bones. Where possible, all available bones should be used and a consensus of results assessed, though the accuracy derived from different bones varies and the result from – say, a femur – is more reliable than that from an ulna. The descending order of usefulness is: femur, tibia, humerus, radius.

Many formulae have been constructed for the determination of stature from the length of long bones. The following cautions must be appreciated before they are used:

- The tables were constructed from differing ethnic groups and at different times, so that racial and nutritional factors introduce significant variations. The table most appropriate to the bones under investigation should be used, though by definition the exact provenance of these bones may be unknown, even including their ethnic origins.
- There is a marked sex difference in stature estimation and ageing of the person also reduces stature relative to long bone length. Trotter and Gleser found in 855 bodies that there was a 1.2 cm loss of height for each two decades of age over the age of 30, a loss of height equivalent to about 0.6 mm a year after the fourth decade. The same investigation showed that the length of the cadaver was about 2.5 cm longer than the known height during life. The maximum stature (at least in American males) was found in 1951 to be reached at the age of 23 years, a change from earlier estimates in which the peak was found to occur between 18 and 21 years of age.[12]
- The bone lengths must be measured in exactly the same way as that used by the author of the tables.
- Old dry bones are slightly shorter than recent material, even when one excludes the loss of articular cartilage. Telkkä stated that 2 mm must be deducted from the length of fresh bone before the calculation is made, as most tables are based on dried skeletons.[81] These differences, however, are slight compared with the greater errors likely if incorrect measuring methods are employed.

- There are inbuilt errors, which are expressed in the formulae. These standard errors are given as 'plus or minus' a certain figure, which applies only when the length of the bone is near the mean of the usual range of length for that particular bone. When the bone is near the extremes of the range (that is from a very tall or very short person), then the standard deviation must be doubled in order to stay within the same range of confidence of accuracy. The same holds good if the tables used are not from the same ethnic group as those being estimated. Krogman indicated that a 95 per cent confidence rate applies only if twice the standard error is accepted each side of the favoured height – in an average man, this means a latitude of over 12 cm, which is too great to be of much use in identification.

Of the many available systems of calculation, those of Trotter and Gleser are most widely used, being based on Caucasian and Negroid Americans from the 1950s (Table 3.3). Older tables include those of Rollet, whose measurements of French people were later reworked by Manouvrier and by Pearson and quoted in a review by Hrdlicka.[12,36,70,82,83] Pearson allowed a standard addition of 2.5 cm to compensate for the difference between dead and living height. Other tables include those of Dupertuis and Hadden and Trotter and Gleser, from American subjects.[12,83] The latter used casualties from World War II and later from the Korean War to construct their tables. Other calculation systems include Breitinger (Germans),[84] Telkkä (Finns),[81] Allbrook (African Negroids and English),[85] Shiati (Chinese),[86] Mendes-Correa (Portuguese)[87] and Stevenson (Chinese).[88] Critics of the accuracy of the estimation of stature from long bones include Wells, who suggested that even the preferred method of Trotter and Gleser has less accuracy than is generally acknowledged.[89]

Table 3.3 The stature tables of Trotter and Gleser.[12,35] The upper table represents their original 1952 figures, the lower their modification of 1977, as quoted by Krogman and Iscan. All lengths are in centimetres, valid only for Americans between 18 and 30 years of age. Femur and tibia are maximum lengths. SE = standard error

Male Whites	Male Negroes
Stature = 63.05 + 1.31 (femur + fibula) ± 3.63 cm	Stature = 67.77 + 1.20 (femur + fibula) ± 3.63 cm
Stature = 67.09 + 1.26 (femur + tibia) ± 3.74 cm	Stature = 71.75 + 1.15 (femur + tibia) ± 3.68 cm
Stature = 75.50 + 2.60 fibula ± 3.86 cm	Stature = 72.22 + 2.10 femur ± 3.91 cm
Stature = 65.53 + 2.32 femur ± 3.94 cm	Stature = 85.36 + 2.19 tibia ± 3.96 cm
Stature = 81.93 + 2.42 tibia ± 4.00 cm	Stature = 80.07 + 2.34 fibula ± 4.02 cm
Stature = 67.97 + 1.82 (humerus + radius) ± 4.31 cm	Stature = 73.08 + 1.66 (humerus + radius) ± 4.18 cm
Stature = 66.98 + (humerus + ulna) ± 4.37 cm	Stature = 70.67 + 1.65 (humerus + ulna) ± 4.23 cm
Stature = 78.10 + 2.89 humerus ± 4.57	Stature = 75.48 + 2.88 humerus ± 4.23 cm
Stature = 79.42 + 3.79 radius ± 4.66	Stature = 85.43 + 3.32 radius ± 4.57 cm
Stature = 75.55 + 3.76 ulna ± 4.72	Stature = 82.77 + 3.20 ulna ± 4.74 cm
Female Whites	**Female Negroes**
Stature = 50.12 + 0.68 humerus + 1.17 femur + 1.15 tibia ± 3.51 cm	Stature = 56.33 + 0.44 humerus 0.20 radius + 1.46 femur + 0.86 tibia ± 3.22 cm
Stature = 53.20 + 1.39 (femur + tibia) ± 3.55 cm	Stature = 58.54 + 1.53 femur + 0.96 tibia ± 3.23 cm
Stature = 53.07 + 1.48 femur + 1.28 tibia ± 3.55 cm	Stature = 59.72 + 1.26 (femur + tibia) ± 3.28 cm
Stature = 59.61 + 2.93 fibula ± 3.57 cm	Stature = 59.76 + 2.28 femur ± 3.41 cm
Stature = 61.53 + 2.90 tibia ± 3.66 cm	Stature = 62.80 + 1.08 humerus + 1.79 tibia ± 3.58 cm
Stature = 52.77 + 1.35 humerus + 1.95 tibia ± 3.67 cm	Stature = 72.65 + 2.45 tibia ± 3.70 cm
Stature = 54.10 + 2.47 femur ± 3.72 cm	Stature = 70.90 + 2.49 fibula ± 3.80 cm
Stature = 54.93 + 4.74 radius ± 4.24 cm	Stature = 64.67 + 3.08 humerus ± 4.25 cm
Stature = 57.76 + 4.27 ulna ± 4.20 cm	Stature = 75.38 + 3.31 ulna ± 4.83 cm
Stature = 57.97 + 3.36 humerus ± 4.45 cm	Stature = 94.51 + 2.75 radius ± 5.05 cm

(Continued)

Table 3.3 (Continued) The stature tables of Trotter and Gleser.[12,35] The upper table represents their original 1952 figures, the lower their modification of 1977, as quoted by Krogman and Iscan. All lengths are in centimetres, valid only for Americans between 18 and 30 years of age. Femur (Fem) and tibia (Tib) are maximum lengths. Hum = humerus, Fib = fibula, Rad = radius, SE = standard error

White Males	SE	Black Males	SE
3.08 Hum + 70.45	4.05	3.26 Hum + 62.10	4.43
3.78 Rad + 79.01	4.32	3.42 Rad + 81.56	4.30
3.70 Ulna + 74.05	4.32	3.26 Ulna + 79.29	4.42
2.38 Fem + 61.41	3.27	2.11 Fem + 70.35	3.94
2.52 Tib + 78.62	3.37	2.19 Tib + 86.02	3.78
2.68 Fib + 71.78	3.29	2.19 Fib + 85.65	4.08
1.30 (Fem + Tib) + 63.29	2.99	1.15 (Fem + Tib) + 71.04	3.53
1.42 Fem + 1.24 Tib + 59.88	2.00	0.66 Fem + 1.62 Tib + 76.13	3.49
0.93 Hum + 1.94 Tib + 69.30	3.26	0.90 Hum + 1.78 Tib + 71.29	3.49
0.27 Hum + 1.32 Fem + 1.16 Tib+ 58.57	2.99	0.89 Hum + 1.01 Rad + 0.38 Fem + 1.92 Tib + 74.56	3.38
White Females	**SE**	**Black Females**	**SE**
3.36 Hum + 57.97	4.45	3.08 Hum + 64.67	4.25
4.74 Rad + 54.93	4.24	3.67 Rad + 71.79	4.59
4.27 Ulna + 57.76	4.30	3.31 Ulna + 75.38	4.83
2.47 Fem + 54.10	3.72	2.28 Fem + 59.76	3.41
2.90 Tib + 61.53	3.66	2.45 Tib + 72.65	3.70
2.93 Fib + 59.61	3.57	2.49 Fib + 70.90	3.80
1.39 (Fem + Tib) + 53.20	3.55	1.26 (Fem + Tib) + 59.72	3.28
1.48 Fem + 1.28 Tib + 53.07	3.55	1.53 Fem + 0.96 Tib + 58.54	3.23
1.35 Hum + 1.95 Tib + 52.77	3.67	1.08 Hum + 1.79 Tib	3.58
0.68 Hum + 1.17 Fem + 1.15 Tib+ 50.122	3.51	0.44 Hum + 0.20 Rad + 1.46 Fem+ 0.86 Tib + 56.33	3.22

Estimation of stature from bones other than the major limb bones is far more inaccurate. Measuring the spinal column (from the tip of the odontoid to the bottom of the fifth lumbar vertebra) has been used by Krogman and by Dwight; Fully and Pineau used the spine plus a long bone.[90] Tibbetts, in his more modern study on the spine, measured 23 individual vertebrae and produced a regression formula for both males and females.[91] However, the results were far superior when long bones were used. Others have employed the clavicle and the scapula.[92,93]

The use of fragmentary bones and those immature bones from which the epiphyses have been lost have been studied, the survey by Krogman and Iscan being the best account of the techniques employed by researchers such as Steele and McKern and Muller.[94,95] The estimation of the heights of infants and fetuses is even more difficult when working with skeletal material, as substantial parts of these bones may be detached and missing because of non-fusion of epiphyses and non-appearance of ossification centres. Mehta and Singh have specifically addressed this problem, as well as others summarized by Krogman and Iscan.[35,96]

Estimating the subject's age from skeletal structures

The age of the subject at death is usually more important than the stature and rivals the sex as the most vital indication of identity. The estimation of skeletal age falls into various groups, which have marked differences in both method and accuracy. In general, the greater the personal age the less the confidence quotient. There are many publications on the subject,[97] many of them arising from archaeological rather than forensic interest, as the age structure of a skeletal population is of great interest to social anthropologists and historians.

The fetus and young infant

It is more usual to have to estimate fetal and neonatal age on the intact dead body, rather than the skeleton, as the immature bones are so easily dispersed, lost and destroyed compared to the more robust bones of older subjects. Both in archaeology and forensic pathology, however, such fetal and immature remains are sometimes present.

The major dating indices are the appearance of ossification centres in growing cartilage but, as stated above, these are rarely available in dried bones as the cartilage disintegrates within weeks or months and small ossification centres – both in diaphyses and epiphyses – rarely survive. The bones have to be examined with the cartilage still attached to offer much hope of ageing the remains. Radiology may provide more information than visual inspection.

Specialized books such as the classics by Fazekas and Kosa, Krogman and Iscan, and by Scheuer and Black and the numerous papers and monographs on the subject must be consulted where fetal issues are complex and important.[35,98,99] Once again the help of interested anatomists and radiologists can be invaluable, especially as biological variation poses a constant trap for the inexperienced who slavishly follow printed tables without the knowledge to appreciate their limitations. Stewart has produced a useful nomogram that relates fetal femoral length to crown–rump length and hence to approximate gestational age. Teeth are discussed in Chapter 26. Fazeka and Kosa's book is particularly useful to the pathologist (as bone lengths, etc. are directly related to fetal and infant age), as are the profuse illustrations.

Skeletal age in the child and young adult

There is no break in the methods used for the fetus and small infant and the older child and young adult. The appearance of ossification centres is complete by around 5 years and after this stage the fusion of epiphyses acts as a calendar up to the age of about 25, when the medial clavicular epiphysis is usually the last evidence of such fusion (Fig. 3.18).

Lists and diagrams such as those shown here are the usual method of tracing the maturity of the skeleton. Several cautionary points must be appreciated and where possible the advice of a radiologist be obtained if there are important issues at stake. The paper by McKern and Stewart gives a valuable commentary on personal variation in skeletal age determination (Table 3.4).[100,101]

- Maturity is not synonymous with calendar age. There are both sexual, racial, nutritional and other biological variations.
- Females are almost always in advance of males, and maturity tends to be accelerated in hotter climates, though the latter may be tempered by nutritional disadvantages.

Table 3.4 Time of appearance of major ossification centres

(a) Healthy White boys

Birth
Calcaneus
Talus
Femur, distal
Tibia, proximal
Cuboid
Humerus, head

2 months
Capitate
Hamate
Lateral cuneiform

3 months
Femur, head
Capitulum
Tibia, distal

6 months
Fibula, distal

7 months
Humerus, greater tuberosity
Radius, distal

10 months
Triquetrum

11 months
Third finger – first phalanx
First toe – second phalanx

12 months
Second finger – first phalanx
Fourth finger – first phalanx
First finger – second phalanx

13 months
Third toe – first phalanx
Second metacarpal
Medial cuneiform

14 months
Fourth toe – first phalanx
Second toe –first phalanx
Fifth toe – second phalanx

15 months
Third metacarpal
Second toe – second phalanx
Fifth finger – first phalanx

16 months
Fourth toe – second phalanx
Fourth metacarpal

18 months
Second finger – second phalanx
Third finger – second phalanx
Fourth finger – second phalanx
Fifth metacarpal

20 months
First toe – first phalanx
Middle cuneiform

(*Continued*)

Table 3.4 (Continued) Time of appearance of major ossification centres

(a) Healthy White boys			
21 months Third finger – third phalanx Fourth finger – third phalanx Navicular of foot Fifth toe – first phalanx *22 months* First metacarpal First metatarsal *23 months* First finger – first phalanx	*2 years* Fifth finger – second phalanx Lunate *2 years, 2 months* Second metatarsal *2 years, 5 months* Second finger –third phalanx Fifth finger – third phalanx *2 years, 11 months* Third metatarsal Fibula, proximal	*3 years, 1 month* Femur, great trochanter Patella *3 years, 3 months* Fourth metatarsal *3 years, 4 months* Fifth toe – third phalanx *3 years, 7 months* Third toe – third phalanx Fourth toe – third phalanx *3 years, 8 months* Fifth metatarsal Second finger – third phalanx	*3 years, 10 months* Radius, proximal *4 years, 2 months* Multangulate majus *4 years, 4 months* Navicular, hand *4 years, 8 months* Multangulate minus *5 years +* Humerus, medial epicond Ulna, distal Fifth toe – second phalanx
(b) Healthy White girls			
Birth Calcaneus Talus Femur, distal Tibia, proximal Cuboid Humerus, head *2 months* Capitate Hamate Lateral cuneiform *3 months* Femur, head Capitulum Tibia, distal *4 months* Humerus, greater tuberosity *6 months* Fibula, distal Radius, distal *7 months* First toe – second phalanx Third finger – first phalanx Fourth finger – first phalanx	*8 months* Second finger – first phalanx First finger – second phalanx Third toe – first phalanx *9 months* Third toe – second phalanx Fourth toe – first phalanx Medial cuneiform *10 months* Second metacarpal Second toe – second phalanx Fourth toe – second phalanx Third metacarpal Second toe – first phalanx Triquetrum *11 months* Fourth metacarpal Fifth finger – first phalanx *12 months* Fourth finger – second phalanx Third finger – second phalanx *13 months* Fifth metacarpal Second finger – second phalanx	*14 months* First metacarpal First toe – first phalanx Fifth finger – first phalanx Third finger – third phalanx Fourth finger – third phalanx Navicular of foot Middle cuneiform First metatarsal *15 months* First finger – first phalanx Fifth finger – second phalanx *17 months* Second finger – third phalanx Fifth finger – third phalanx *19 months* Second metatarsal *21 months* Fifth toe – third phalanx *22 months* Third metatarsal *23 months* Patella	*2 years* Lunate Third toe – third phalanx Fourth toe – third phalanx Fibula, proximal Femur, greater trochanter *2 years, 2 months* Second toe – third phalanx Fourth metatarsal *2 years, 5 months* Fifth metatarsal *2 years, 8 months* Multangulate majus *2 years, 9 months* Humerus, medial epicon *3 years* Radius, proximal Multangulate minus *3 years, 2 months* Navicular, hand *4 years, 6 months* Ulna, distal *5 years +* Fifth toe – second phalanx

After Francis & Werle.[101]

- There is a marked range of closure dates in epiphyseal union, and the year suggested in some charts is merely the midpoint of that range.
- Union is a process, not an event. It may be different radiologically from gross inspection; it may also be slow in completion, so that it may be difficult to pinpoint a date that is needed to refer to published data. An example is the one that is usually the last to fuse, the medial end of the clavicle, which may slowly close during any period from about 18 to 31 years. Finally, as emphasized by Krogman and Iscan, multiple criteria of skeletal age should be used, dependence not being placed upon any single measurement.

Skeletal ageing in later years

The eruption of the third molar teeth and the fusion of the last epiphysis occurs approximately in the middle of the third decade (Fig. 3.17). This is a watershed in skeletal dating, as the more objective markers of age are almost all on the younger side of this time. From around 25 years until old age, there are no dramatic events such as tooth eruption or the appearance of ossification centres. There are more subtle changes available for specialized interpretation, but the general decline through middle age to senility prevents assessment of age to within the nearest half-decade.

The major advances in this difficult period have been the use of the pubic symphysis and sternal ribs and the radiology of cancellous bone. However, dental technology may further refine the assessment of age.

Aging adults

Determination of biological age in adult skeletons is quite difficult and constitutes one of the most difficult tasks of forensic anthropology. Once dental and osseous development have occurred, very little remains on which one can accurately evaluate aging, if not pathology, degenerative changes, histological alterations and chemical alterations of the components of bone and teeth.

General markers of old age do exist: osteoporosis, articular surface degeneration, osteophytes; however, these are severely influenced by pathology, nutrition and interindividual variability.

Physical anthropology has established several methods for determining age in adults – macroscopic, microscopic and biomolecular, but most methods have error ranges, which encompass 10–15 years. Macroscopic methods are the most important ones and consist principally in the degree of degeneration of selected articulations such as the pubic symphysis, osteochondral surface of the 4th rib, auricular surface of the ilium. The rationale behind these anatomical sites is that they are articulations, which are equally stressed for all individuals, regardless of activity. Thus they should reveal a degree of degeneration, which should be proportional to age only and thus standardisable for aging procedures. Less reliable techniques are cranial bone suture analysis and radiological evaluation of bone rarefaction.

Pubic symphysis

Todd, McKern, Stewart and Gilbert were the first authors who extensively studied the pubic symphysis for aging and developed a method.[100,102–105] More recently Brooks and Suchey devised a 6-stage method, which



Figure 3.17 Mixed dentition (deciduous and permanent) of the molars. The window through the mandible shows the level of root formation. (Milano skeletal collection reproduced by kind permission of Professor C. Cattaneo.)



Figure 3.18 Ulnae at three different stages: top, 18 years; middle, 15 years (note the non-fusion of the distal end); lower, 3 months. (Milano skeletal collection reproduced by kind permission of Professor C. Cattaneo.)

has become the most user-friendly and popular for aging.[106] Briefly, in young adults the symphyseal surface of the pubic bones (i.e. the joint between the two pubic bones) has a billowed appearance, with deep and furrowed bone ridges running across the surface in parallel. As the person ages, the furrows gradually become filled and the surface becomes flatter and even. Around this surface an oval outline is formed and an initial crest begins to form on the ventral margin. Then the surface starts to deteriorate (Fig. 3.19).

Phases are as follows:

1. Symphyseal face has a billowing surface (ridges and furrows), which usually extends to include the pubic tubercle. The horizontal ridges are well marked and ventral bevelling may be commencing. Although ossific nodules may occur on the upper extremity, a key to the recognition of this phase is the lack of delimitation of either extremity (upper or lower); mean age in males 18.5 (95 per cent CI 15–24), in females 19.4 (95 per cent CI 15–23).
2. The symphyseal face may still show ridge development. The face has commencing delimitation of lower and/or upper extremities occurring with or without ossific nodules. The ventral rampart may be in beginning phases as an extension of the bony activity at either or both extremities; mean age in males 23.4 (95 per cent CI 19–34), in females 25 (95 per cent CI 19–40).
3. Symphyseal face shows lower extremity and ventral rampart in process of completion. There can be a continuation of fusing ossific nodules forming the upper extremity and along the ventral border. Symphyseal face is smooth or can continue to show distinct ridges. Dorsal plateau is complete. Absence of lipping of symphyseal dorsal margin; no bony ligamentous outgrowths; mean age in males 28.7 (95 per cent CI 21-46), in females 30.7 (95 per cent CI 21–53).
4. Symphyseal face is generally fine grained, although remnants of the old ridge and furrow system may still remain. Usually the oval outline is complete at this stage, but a hiatus can occur in upper ventral rim. Pubic tubercle is fully separated from the symphyseal face by definition of upper extremity. The symphyseal face may have a distinct rim. Ventrally, bony ligamentous outgrowths may occur on inferior portion of pubic bone adjacent to symphyseal face. If any lipping occurs it will be slight and located on the dorsal border; mean age in males 35.2 (95 per cent CI 23–57), in females 38.2 (95 per cent CI 27–49).
5. Symphyseal face is completely rimmed with some slight depression of the face itself, relative to the rim. Moderate lipping is usually found on the dorsal border with more prominent ligamentous outgrowths on the ventral border. There is little or no rim erosion. Breakdown may occur on superior ventral border; mean age in males 45.6 (95 per cent CI 27–66), in females 48.1 (95 per cent CI 25–83).
6. Symphyseal face may show ongoing depression as rim erodes. Ventral ligamentous attachments are marked. In many individuals the pubic tubercle appears as a separate bony knob. The face may be pitted or porous, giving an appearance of disfigurement with the ongoing process of erratic ossification. Crenulations may occur. The shape of the face is often irregular at this stage. mean age in males 61.2 (95 per cent CI 49–73), in females 60 (95 per cent CI 42–87).



Figure 3.19 Casts of Suchey–Brooks phases (males) by Diane France Casting (Milano skeletal collection reproduced by kind permission by Prof. C. Cattaneo).

Fourth rib

This method was developed by Iscan *et al.* and evaluates the profile of the osteochondral articulation of the rib, its depth and the profile of the margin. As age increases the profile becomes more irregular with margins, which go from a V-form to a U-form; depth increases and sternal insertion is more irregular. These alterations are expressed in eight phases for males and females. One disadvantage of this method is that at times, with commingled remains, it is difficult to identify the 4th rib, or it may not be available.[107–109] In the following, the age ranges for phases are presented according to the 3rd edition of *Human Skeleton in Forensic Medicine* where the authors had taken a more conservative



Figure 3.20 To the left, sternal end of the 4th rib of a young second stage according to Iscan *et al.* with fairly regular margins and a shallow concavity; to the right an older rib, stage 8, with scalloped and irregular osteophytic margins. (Milano skeletal collection reproduced by kind permission of Professor C. Cattaneo.)

approach with the statistical analyses and quoted the data as mean ± 2 SDs (Fig. 3.20).[110,111]

Male

Phase 0 (16 and younger): the articular surface is flat or billowy with a regular rim and rounded edges. The outer surface of the sternal rib end is bordered by an epiphyseal ring. The bone itself is smooth, firm and very solid.

Phase 1 (16–18): there is a beginning amorphous indentation in the articular surface, but billowing may also still be present. The rim is rounded and regular. The epiphyseal ring has disappeared. In some cases scallops may start to appear at the edges. The bone is still firm, smooth and solid.

Phase 2 (18–26): the pit is now deeper and has assumed a V-shaped appearance formed by the anterior and posterior walls. The walls are thick and smooth with a scalloped or slightly wavy rim with rounded edges. The bone is firm and solid.

Phase 3 (19–33): the deepening pit has taken on a narrow to moderately wide U-shape. Walls are still fairly thick with rounded edges. Some scalloping may still be present but the rim is becoming more irregular. The bone is still quite firm and solid.

Phase 4 (21–36): pit depth is increasing, but the shape is still a narrow to moderately wide U. The walls are thinner, but the edges remain rounded. The rim is more irregular with no uniform scalloping pattern remaining. There is some decrease in the weight and firmness of the bone; however, the overall quality of the bone is still good.

Phase 5 (25–53): there is little change in pit depth, but the shape in this phase is predominantly a moderately wide U. Walls show further thinning and the edges are becoming sharp. Irregularity is increasing in the rim. Scalloping pattern is completely gone and has been replaced with irregular bony projections. The condition of the bone is fairly good; however, there are some signs of deterioration with evidence of porosity and loss of density.

Phase 6 (28–72): the pit is noticeably deep with a wide U-shape. The walls are thin with sharp edges. The rim is irregular and exhibits some rather long bony projections that are frequently more pronounced at the superior and inferior borders. The bone is noticeably lighter in weight, thinner and more porous, especially inside the pit.

Phase 7 (40–78): the pit is deep with a wide to very wide U-shape. The walls are thin and fragile with sharp, irregular edges and bony projections. The bone is light in weight and brittle with significant deterioration in quality and obvious porosity.

Phase 8 (51 and older): in this final phase the pit is very deep and widely U-shaped. In some cases the floor of the pit is absent or filled with bony projections. The walls are extremely thin, fragile and brittle with sharp, highly irregular edges and bony projections. The bone is very lightweight, thin, brittle, friable and porous. 'Window' formation is sometimes seen in the walls.

Female

Phase 0 (13 and younger): the articular surface is nearly flat with ridges or billowing. The outer surface of the sternal rib end is bordered by an epiphyseal ring. The rim is regular with rounded edges, and the bone itself is firm, smooth, and very solid.

Phase 1 (±14): a beginning, amorphous indentation can be seen in the articular surface and the epiphyseal ring has disappeared. Ridges or billowing may still be present. The rim is rounded and regular with a little waviness in some cases. The bone remains solid, firm, and smooth.

Phase 2 (14–20): the pit is considerably deeper and has assumed a V-shape between the thick, smooth anterior and posterior walls. Some ridges or billowing may still remain inside the pit. The rim is wavy with some scallops beginning to form at the rounded edge. The bone itself is firm and solid.

Phase 3 (19–26): there is only slight if any increase in pit depth, but the V-shape is wider, sometimes approaching a narrow U as the walls become a bit thinner. The still rounded edges now show a pronounced, regular scalloping pattern. At this stage, the anterior or posterior walls may first start to exhibit a central, semicircular arc of bone. The rib is firm and solid.

Phase 4 (19–37): there is a noticeable increase in the depth of the pit, which now has a wide V- or narrow U-shape with, at times, flared edges. The walls are thinner but the rim remains rounded. Some scalloping is still present, along with the central arc; however, the scallops are not as well defined and the edges look somewhat worn down. The quality of the bone is fairly good but there is some decrease in density and firmness.

Phase 5 (16–64): the depth of the pit stays about the same, but the thinning walls are flaring into a wider V- or U-shape. In most cases, a smooth, hard, plaque-like deposit lines at least part of the pit. No regular scalloping pattern remains and the edge is beginning to sharpen. The rim is becoming more irregular, but the central arc is still the most prominent projection. Bone is noticeably lighter in weight, density and firmness. The texture is somewhat brittle.

Phase 6 (21–81): an increase in pit depth is again noted, and its V- or U-shape has widened again because of pronounced flaring at the end. The plaque-like deposit may still appear but is rougher and more porous. The walls are quite thin with sharp edges and an irregular rim. The central arc is less obvious and, in many cases, sharp points project from the rim of the sternal extremity. The bone is fairly thin and brittle with some signs of deterioration.

Phase 7 (43–88): in this phase, the depth of the predominantly flared U-shaped pit not only shows no increase, but actually decreases slightly. Irregular bony growths are often seen extruding from the interior of the pit. The central arc is still present in most cases but is now accompanied by pointed projections, often at the superior and inferior borders, yet may be evidenced anywhere around the rim. The very thin walls have irregular rims with sharp edges. The bone is very light, thin, brittle and fragile, with deteriorations most noticeable inside the pit.

Phase 8 (62 and older): the floor of the U-shaped pit in this final phase is relatively shallow, badly deteriorated, or completely eroded. Sometimes it is filled with bony growths. The central arc is barely recognizable. The extremely thin, fragile walls have highly irregular rims with very sharp edges, and often fairly long projections of bone at the inferior and superior borders. 'Window' formation sometimes occurs in the walls. The bone itself is in poor condition – extremely thin, light in weight, brittle, and fragile.

Auricular surface of the ilium

This method was devised by Lovejoy *et al.* in 1985 and is based, as for the pubic symphysis, on the degeneration, in eight phases, of the auricular surface of the ilium, according to the degeneration of the apex, the superior half of the surface, the inferior half, the retroauricular area, granulosity, density, micro- and macroporosity of the surface.[112]

20–24: the surface displays fine granular texture and marked transverse organization. There is no retroauricular activity, apical activity, or porosity. The surface appears youthful because of broad and well-defined billows, which impart the definitive transverse organization. Billows are well defined and cover most of the surface. Any subchondral defects are smooth-edged and rounded. Note distinct transverse billows and very fine granularity.

25–29: changes from the previous phase are not marked and are mostly reflected in slight to moderate loss of billowing, with replacement by striae. There is no apical activity, porosity or retroauricular activity. The surface still appears youthful owing to marked transverse organization. Granulation is slightly more coarse.

30–34: both faces are largely quiescent with some loss of transverse organization. Billowing is much reduced and replaced by (definite) striae. The surface is more coarsely and recognizably granular than in previous phase, with no significant changes at apex. Small areas of microporosity may appear. Slight retroauricular activity may occasionally be present. In general, coarse granulation supersedes and replaces billowing. Note smoothing of surface by replacement of billows by fine striae, but distinct retention of slight billowing. Loss of transverse organization and coarsening of granularity is evident.

35–39: both faces are coarsely and uniformly granulated, with marked reduction of both billowing and striae, but striae may still be present under close examination. Transverse organization is present but poorly defined. There is some activity in the retroauricular area but this is usually slight. Minimal changes are seen at the apex, microporosity is slight, and there is no macroporosity. This is the primary period of uniform granularity.

40–44: no billowing is seen. Striae may be present but very vague. The face is still partially (coarsely) granular and there is a marked loss of transverse organization. Partial densification (which may occur in islands) of the surface with commensurate loss of grain is present along with slight to moderate activity in the retroauricular area. Occasional macroporosity is seen, but this is not typical. Slight changes are usually present at apex. Some increase in microporosity is seen, depending upon the degree of densification. The primary feature is the transition from a granular to a dense surface.

45–49: significant loss of granulation is seen in most specimens, with replacement by dense bone. No billows or striae are present. Changes at apex are slight to moderate but are almost always present. There is a distinct tendency for the surface to become dense. No transverse organization is evident. Most or all of any microporosity is lost to densification process. There is increased irregularity of margins with moderate retroauricular activity and little or no macroporosity.

50–60: this is a further elaboration of previous stage, in which marked suface irregularity becomes paramount feature. Topography, however, shows no transverse or other form of organization. Moderate granulation is occasionally retained, but is usually lost during previous phase and is generally absent. No striae or billows are present. The inferior face generally is lipped at inferior terminus, so as to extend beyond the body of the innominate bone. Apical changes are almost invariable and may be marked. Increasing irregularity of margins is seen. Macroporosity is present in some cases but it is not requisite. Retroauricular activity is moderate or marked in most cases.

60+: the paramount feature is a nongranular, irregular surface, with distinct signs of subchondral destruction. No transverse organization is seen and there is a definitive absence of any youthful criteria. Macroporosity is present in about one-third of all cases. Apical activity is usually marked but is not requisite for this age category. Margins become dramatically irregular and lipped, with typical degenerative joint change. The retroauricular area becomes well defined with profuse osteophytes of low to moderate relief. There is clear destruction of subchondral bone, absence of transverse organization and increased irregularity.

Less accurate methods, which involve the observation of suture closure both ecto- and andocranial exist. These methods involve the assessment of the degree of suture closure and give a score, which results in a specific age with a very large error range.

Macroscopic alterations of teeth are also relevant. In particular, dentine translucency seems important – a variable which increases with age. As far as dental methods are concerned, the Lamendin method[16] is the most reliable among dental tests: it utilizes parodontal disease and translucency of rooth in monoradicular teeth throughout the following formula:

$$\text{Age} = (0.18P') + (0.42T') + 25.53$$

where $P' = P/L \times 100$
$T' = T/L \times 100$
L = teeth length
P = height of periodontosis
T = height of root traslucency

The Lamendin test is considered by literature the most accurate method of age estimation, especially between 40 and 60 years, but recent studies have demonstrated a variability in accordance with ancestry and gender, requiring specific correction factors. It has however replaced the Gustafson–Johanson test, which is based on abrasion, secondary dentin deposition, periodontosis, root translucency, secondary cementum, root reabsorption, with a score from 0 to 3 for each element. However, new radiological methods, which study pulp chamber dimensions are being introduced into the forensic scenario but still need testing.

Recently a 'two step procedure' has been developed for quickly achieving age: if the idea one has of the age of an individual by looking at the skeleton is that it is within the first 3 stages of the Suchey–Brookes pubic symphysis method, then this should be the method of choice. If the subject is classified in the last 3 phases, then one should switch to the Lamendin technique in order to more accurately assess age. Currently age diagnosis at over 60 remains a problem.

If macroscopic methods cannot be performed (for fragmentation, loss of the anatomical areas), one must then proceed to microscopic methods. The rationale behind the microscopic method is that since bone remodelling occurs constantly throughout life, an older bone will have more osteons and osteon fragments compared with a younger bone. Microscopic analysis of a bone section from long-bone diaphyses can provide an age estimation throughout several methods, the most acclaimed being the Kerley–Ubelaker one, which counts the number of secondary osteons, of osteon fragments and number of primary osteons in a 100× microscopic field with a diameter of 1.62 mm; the method can be applied to tibial, femoral and fibular diaphyses.[113] The numbers are then inserted into an appropriate formula.

Many other macroscopic and microscopic methods are available, including evaluation of the acetabulum and cementum annulation, respectively. These are however more difficult to apply and/or more costly, less user-friendly or still need to be tested on larger populations.

Finally there are also chemicophysical methods, which seem to yield a smaller error range. These are based on the racemisation of aspartic acid, but are expensive and their limits have not yet been defined.

Determination of ancestry from skeletal remains

This is more difficult than any of the preceding investigations, partly because racial traits are not so marked and partly because so much ethnic mixing has taken place, especially in the large-scale immigrations into Europe and North America in recent years. There is no consensus as to whether forensic anthropologists or osteologists should include assesments of 'race' or ancestry in skeletal reports as according to Iscan and Steyn it seems to remain tentative at best.[111]

As usual, those at the extreme ends of the osteological range present little difficulty, as Brothwell remarks when comparing Eskimos with Australian Aboriginals.[114] Unfortunately, there is a large proportion of racially neutral skeletal material and also some that presents apparently classical racial features but turns out to be totally atypical, so providing a quite incorrect diagnosis. The following criteria are offered, but the usual warnings about dogmatic opinions are even more important in this field.[115,116]

There are three main racial groups: Caucasian, Mongoloid and Negroid. All others are derived from these and skeletally cannot be distinguished, though when archaeologists and anthropologists are working within a major ancestry, there may well be local criteria that can distinguish subgroups with varying degrees of confidence. Most work has been performed in North America and thus most available data are derived from Caucasian and Negroid Americans and Native Americans.

The skull offers the best evidence on racial origins; Krogman and Iscan claimed that ancestry can be determined in 90–95 per cent of cases.[35] The mandible is excluded from this, apart from the teeth, which will be dealt with in another chapter. It may be mentioned here, however, that one of the most useful pointers to a Mongoloid skull is the present of posteriorly concave, 'shovel-shaped', upper incisors, which may be grooved on the rear surface. These were found by mainly in Chinese and Japanese populations but occur ocasionally also in Caucasoid ones.

The wide zygomatic arches that give the typical high-cheekboned features of the Mongoloid ancestry can sometimes produce a skull in which, uniquely, the transverse facial width is greater than the width of any other part of the head. Krogman provides a useful table outlining the major differences in the skull. Elsewhere he subdivides the Caucasian group into its three main subgroups: Nordic, Alpine and Mediterranean. He points out once again that these describe the 'stereotypes' of each group and that there is an extensive grey zone of more neutral characteristics. Subjects in the Negroid group tend to be long headed (dolichocephalic), broad headed (brachycephalic) in the Mongoloid group, with the whole range occuring in the Caucasian group. The Negroid orbit is lower and wider, compared with the higher, rounder eye socket of the Mongoloid. The Negroid nasal aperture is wide, and the prognathism of the lower face and jaw relatively marked, along with the absence of a nasal sill (Figs 3.21, 3.22).

There are racial differences. The sinuses are well protected from all but the most extreme damage and are unique in that – as first pointed out by Poole in 1931. The long bones offer some assistance, especially



Figure 3.21 Frontal view of a female Negroid/African skull. (Milano skeletal collection reproduced by kind permission of Professor C. Cattaneo.)



Figure 3.22 Lateral view of a female Negroid/African skull. (Milano skeletal collection reproduced by kind permission of Professor C. Cattaneo.)

the femur. This is straighter in Negroid groups, the anteroposterior bowing being less.

Together with other long bones, especially those of the lower limb, Negroid bones are longer than those of Caucasian or Mongoloid skeletons, even for equal total body length, the leg proportions being greater. The radius and tibia are relatively longer. Several writers offer various indices of relative bone lengths, such as those of Modi, Munter and Schultz.[117–119] The scapula has been extensively studied, but seems a poor discriminator of ancestry.

More recently interactive computer programs, such as FORDISC 3.0, have been devised for classifying adult skeletons by ancestry and sex using any combination of standard measurements.[120] Features of FORDISC 3.0 are: larger number of variables, including postcranial variables; larger numbers of groups, including Howells' worldwide cranial data. Softwares such as FORDISC, which provide racial affinity acccording to cranial metrics, can be used for cases pertaining to the United States.[120]



Figure 3.23 Reconstruction of the facial muscle layers and positioning of tissue depths in facial approximation. (Milano skeletal collection reproduced by kind permission of Professor C. Cattaneo.)

Reconstruction of the facial appearance from the skull

The reconstitution of the visage from the skeletal base has been a goal for workers in many different fields in recent years. The advantages of such a technique are obvious as, when a skull is discovered one prime method of identification would be a reliable reconstruction of the face, so that direct recognition could be obtained from relatives, friends and photographic records (Fig. 3.23).

The first methods were as much artistic as scientific and depended to a great extent on the sculpturing ability of the operator. Gerasimov was a Soviet pioneer of this method, though much of his work was archaeological and historical, rather than forensic.[121]

The method depends on a pre-knowledge of the usual tissue thickness at a multitude of points on the normal skull, an anatomical exercise that now has quite a large database. Modelling clay is laid on to the unknown skull in layers corresponding to these standard thicknesses, then more imaginative modelling added to 'humanize' the basic shape. The obvious defects in this technique are the lack of knowledge about eyes, lips, nose, ears and head hair, all of which contribute greatly to individual characteristics. Similar methods have been used by graphic artists, rather than sculptors, who use their portraiture talents to create a face on the two-dimensional base provided by the skull profile, plus a knowledge of tissue thicknesses at many anatomical points. Additional information has been provided on tissue thicknesses by radiography of heads.

The method was used with success in the 1988 investigation of the murder of Karen Price in Cardiff. Skeletalized after being buried for 8 years in a carpet beneath a garden, medical artist Richard Neave rebuilt her face upon a skull with sufficient accuracy for its display on public television to be recognized by her parents.

Considerable progress has been made by the use of computer graphic techniques, both in drawing reconstituted heads and in gathering tissue thickness data.[122] Some devices are mechanical, measuring the profile of the skull with a device that converts angles and distances into digital data. More recently, a combination of video and laser equipment has allowed 20,000 measurements to be taken and stored within 30 seconds. The data from an unknown skull are then electronically 'clothed' with standard soft tissues from the memory bank and modified on screen to produce various images. These can be rotated electronically so that various profiles can be seen. A variety of stored eyes, ears and noses can be added, and any feature altered almost instantaneously to give a viewer a number of opportunities to recognize the missing person. Nowadays several softwares exist for craniofacial reconstruction that will apply standard soft tissue parts on the bony substructure.[123] As with so many techniques in forensic medicine and science, the technology is one for super-specialists at present, but the forensic pathologist should be aware that such methods exist and are increasing in availability and accuracy. Regardless however, of whether one proceeds manually or by computer techniques, the method is still a very approximate one, so much so that some experts prefer to call it facial approximation. The accuracy of this technique is not known and for this reason it should never be used as an identification method;[124] nonetheless this final step is always worth pursuing since even a single character that reminds the observer of a person he or she knew in life may lead to identification.

Personal identity from skeletal material

After the general groups of race, sex, stature and age have been investigated (to construct what is generally called the biological profile in order to cross-match data referring to an unidentified decedent with missing persons), the bones must be examined for any idiosyncratic features that give them a personal identity when a suspicion of identity arises. This is invariably a matter of matching up such feature(s) with known pre-existing conditions, and depends upon a potential match being available. Circumstances are infinitely variable and the ways in which this suspected matter comes to the examiner's knowledge are legion. Sometimes there may be one 'good bet' and, indeed, the potential identity may be virtually certain from the circumstances, the anatomical confirmation being almost a formality. In other cases there may be a list of hundreds of potential cases to search through in the hope of finding a match.

Individual characteristics may be of two main types:

- Anatomical shapes that can be matched by radiology, measurement or other means. Examples would be frontal sinus comparison, craniometry and radiological bone architecture.
- Discrete abnormalities such as healing fractures, metal prostheses, bone disease or congenital defects. Some artefacts, such as drill holes or wire, may immediately indicate that the bone is an anatomical specimen.

Anatomical matching depends upon accurate and detailed information about the living subject who is thought to correspond with the skeleton. Such information is usually radiographic and is derived from clinical records. The examples par excellence are dental charts and radiographs obtained from the dentist of the potential match; this is discussed in Chapter 26. Where skull films are available from ante-mortem sources, identity can be almost assured. The lateral view of a head can be matched with similar views taken of the skull, and both obvious anatomical landmarks compared and cranial measurements taken. The matter is further discussed later in relation to radiology, but the profile of the pituitary fossa as well as various intracranial diameters can rapidly exclude a match. In fact, a cursory glance can often confirm that the two skulls are dissimilar; making a positive correlation takes more time and requires accurate orientation of the radiographs.

Frontal sinus and postcranial identification

This has been extensively studied since Schüller suggested the technique in 1921, as it is particularly useful in mutilated or burnt bodies, such as those from mass disasters like air crashes.[125] The sinuses are well protected from all but the most extreme damage and are unique in that – as first pointed out by Poole in 1931 – no two persons (not even identical twins) have the same profile of these air spaces (reported by Mayer).[126] They appear in the second year of life and increase in size for the first two decades. They are absent in about 5 per cent of persons and unilateral in another 1 per cent. For the sinuses to be used, an ante-mortem anteroposterior skull radiograph must be available, the most common source being from a previous hospital admission or examination, usually for a head injury. The cadaver skull or head must be X-rayed in exactly the same orientation and degree of enlargement, so that some superimposition technique can be employed (Fig. 3.24). The 'forehead–nose' position was recommended by Schüller, with the tube axis positioned level with the supraorbital margins.[127] The scalloped upper margins of the sinuses are used for comparison, these being smaller and more numerous in the female. Asherson's thesis of 1965 recommends using the Caldwell occipitomental plane for the radiographs, used clinically for investigation of the nasal sinuses.[128] This is preferable to the Wallers occipitofrontal view and the two projections are not necessarily identical in terms of sinus profile. Asherson recommends outlining the sinus shape in black ink on the film or tracing it onto a sheet of paper. Turpin and Tisserand projected their films onto a cardboard screen and cut out a template, weighing these from both ante- and post-mortem films to determine whether they were identical.[129] Computed tomography of the sinuses is recommended by Reichs.[130] Other authors have focused on the application of advanced techniques to the frontal sinuses, with the aim of defining an objective and quantitative method of analysis to replace simple visual comparison,[131] encouraging for example future statistical studies of the number, position, length, and so on. Identification is also possible through details of the sphenoid sinus, mastoid and ethmoid air cells, torcular and sagittal cranial suture.



Figure 3.24 Personal identification by radiographic superimposition of the frontal sinuses. **A**: post-mortem antero-posterior cranial X-ray of an unidentified skeleton; **B**: ante-mortem X-ray of the presumed victim. In both one can appreciate the frontal sinuses. **C, D**: the enhancement of the sinus profile showing a perfect morphological match. (Reproduced by kind permission of Professor C. Cattaneo.)

Post-cranial structures have also been validated for identification. Several studies using thoracic X-rays have measured the reliability of the visual comparison, established useful features for identification processes and evaluated possible sources of error. According to these, the most useful are the normal anatomical features, such as vertebral, costal and clavicular morphology.[132–134] The abdomen and pelvis maintain their anatomical position in the case of an accident, and the complex morphology of vertebrae is useful for identification purposes. For upper and lower limbs several studies on bone trabecular patterns have been performed, even with the use of specific softwares. Their reliability however still has to be assessed.



Figure 3.25 Identification of a skeletalized body was achieved by matching this callus from a previous ulnar fracture, with the medical notes and radiographs obtained from a hospital. The shape and size of the callus, was identical to follow-up films taken during life.

Wherever ante-mortem X-rays are available, especially of skull, thorax, hip or shoulder, then radiological comparisons of the dead material can almost always exclude an identity and, in many circumstances, can confirm it.

Photosuperimposition techniques for identification

Where potential candidate(s) for the identity of a skull are known to the investigating authority and photographs taken during life are available, a well-established technique used for identification is 'photosuperimposition'. In this method, photographs of the skull are taken in exactly the same orientation in three planes as the available photograph. These are then enlarged to exactly the same dimensions as the photograph, and either the negative or a positive print is made on transparent film. This is then laid over the photograph and adjusted in an attempt to match up the major anatomical landmarks such as nasion, supraorbital ridges, angle of the jaw, nasal aperture, external auditory meatus and, especially, teeth. More recently the use of 3D laser scanners to reproduce a computerized 3D model of the head allows one to superimpose and match a 3D model of the cranium onto the photograph via specific softwares.[135] The actual anatomical markers will depend on what is visible, in frontal, lateral or oblique views. The test is mainly an exclusory one, in that, if the match cannot be made, then the skull is not that of the person in the photograph. If the match is good, even excellent, then the two could be the same person, though the standard of proof is low unless some individualistic feature, such as a distinct dental character, is apparent. A similar procedure in fact can be applied to dental profiles if the ante-mortem picture of the missing person shows him or her smiling. In such cases the identification potential is much greater because the method compares the same structures, i.e. teeth.[136]

The photofit method has been used for many years, one of the most familiar examples being that reproduced in many forensic textbooks, of the skull and face of the wife of Dr Buck Ruxton, a notorious murder in 1935 investigated by Glaister and Brash in Scotland.

In conclusion, as concerns positive identification via the morphological analysis of human remains, the recurrence of discordant characters settles the case, by excluding the identity; the occurrence of several concordant characters, commonly observed within the population does not allow one to express a final judgement on identification, whereas even a few characters rarely observed can lead to a personal identification. Some authors have attempted at determining a minimum number of criteria for identification, for example, one to four unique analogous features without discrepancies, but a general agreement concerning this topic does not exist, as there is no univocal and valid definition of the term unique. This should always be kept in mind especially in consideration of Daubert and Kumho rulings.[137]

The dating of skeletal remains

One of the issues in identity, as well as in estimating the time since death, is the date (as opposed to the age) of human bones. A knowledge of the time of death, measured in years, decades or even centuries, can assist the investigating authorities considerably. In fact, where skeletal remains are shown to be of considerable antiquity, no investigation at all is required, as even if the death was criminal, the culprit may long since have died. This threshold of investigative interest lies at around 70 years and material older than this may be of concern only to historians and archaeologists.

It is the marginal cases that present difficulties, especially as the methods of dating in this period are so approximate. For example, the skeleton shown in Fig. 3.13 was discovered 41 years after the female had been murdered. When the police went searching for the suspected killer, they found that he had died peacefully 3 years before the discovery, of coronary disease – thus qualifying for the 'perfect murder'.

The major problem in dating bones is that the environment is far more potent than time in changing the state of the bone. In Wales, a historic country where a spectrum of skeletal material has been found dating back some 18000 years, frequent opportunities present for examining bones from many periods and many conditions of environment. Some Roman or even Bronze Age material, which had been concealed in dry sand dunes or in well-drained ancient burial mounds, appeared almost as pristine as an anatomical demonstration skeleton. On the other hand, modern material buried in coffins in graves marked with headstones only 20 years old have completely vanished because acidic, peaty water repeatedly eluted the bone as the water table in marshy ground rose and fell. An even more striking demonstration of the effect of local conditions was the observation that some limb bones buried vertically in a rock fall in a cave were in excellent condition at the upper ends, yet the lower parts were totally eroded where they had been surrounded by damp rubble.

These facts emphasize that vast errors can be made in dating bone merely by the gross morphological appearances and – as is so often the case – the less experienced the examiner, the more dogmatic his incorrect opinions are likely to be. For this reason forensic anthropologists have begun to consider how to correlate decomposition and skeletonization with time of death by using decomposition as a semi-continuous variable in conjunction with accumulated degree days (ADD).[138] A scoring method for decomposition using a point-based system and taking into account temperatures to which the remains were exposed, has in fact been devised and has been the object of several promising studies in the past 10 years (Table 3.5).

The following schedule can therefore be nothing more than a rough guide, which must be modified

Table 3.5 Accumulated degree days (ADD) method for estimation of post-mortem interval in decomposed bodies: the sum of the three scores from head and neck, trunk and limbs gives the total body score (TBS); this value is inserted within the equation, provides the number of ADD in °F, which is the sum of all the °F recorded over the 0°F threshold every day after death (adapted from Megyesi *et al.*, 2005)[138]

Score	Head and neck	Trunk	Limbs
1	Fresh, no discolouration	Fresh, no discoloration	Fresh, no discolouration
2	Pink-white appearance with skin slippage and some hair loss	Pink-white appearance with skin slippage and marbling present	Pink-white appearance with skin slippage of hands and/or feet
3	Gray to green discolouration: some flesh still relatively fresh	Gray to green discolouration: some flesh still relatively fresh	Gray to green discolouration: marbling; some flesh still relatively fresh
4	Discolouration and/or brownish shades particularly at edges Drying of nose, ears and lips	Bloating with green discolouration and purging of decompositional fluids	Discolouration and/or brownish shades particularly at edges Drying of finger, toes, and other projecting extremities
5	Purging of decompositional fluids out of eyes, ears, nose, mouth, some bloating of neck and face may be present	Post-bloating following release of the abdominal gases Discolouration changing from green to black	Brown to black discolouration Skin having leathery appearance
6	Brown to black discouloration of flesh	Decomposition of tissue producing sagging of flesh: caving in the abdominal cavity	Moist decomposition with bone exposure less than one-half that of the area being scored
7	Caving in of the flesh and tissues of eyes and throat	Moist decomposition with bone exposure less than one-half that of the area being scored	Mummification with bone exposure less than one-half that of the area being scored
8	Moist decomposition with bone exposure less than one-half that of the area being scored	Mummification with bone exposure less than one-half that of the area being scored	Bone exposure over one-half the area being scored Some decomposed tissue and body fluids remaining
9	Mummification with bone exposure less than one-half that of the area being scored	Bones with decomposed tissue, sometimes with body fluids and grease still present	Bones largely dry, but retaining some grease
10	Bone exposure of more than one-half of the area being scored with greasy substances and decomposed tissue	Bones with desiccated or mummified tissues covering less than one-half of the area being scored	Dry bone
11	Bone exposure of more than one-half the area being scored with desiccated or mummified tissue	Bones largely dry, but retaining some grease	
12	Bones largely dry, but retaining some grease	Dry bone	
13	Dry bone		

$\mathrm{ADD} = 10^{(0.002\times \mathrm{TBS}\times \mathrm{TBS}+1.81)}+/-388.16$

where possible, by a knowledge of the environment in which the bones lay. Certain physicochemical tests are of assistance, but even these are themselves dependent on the environment, with the exception of radiochemical tests that are of increasing importance in the period of forensic concern.

Physical appearance

Recent bones will have soft tissue remnants adhering, in the form of tendon and ligament tags, especially around the joint ends. Periosteum may be visible as fibrous material closely adherent to the shaft surface. Cartilage may also be present on articular surfaces. The time for which these remnants persist is variable, according to the conditions in which the bone has been left. Animal predators may rapidly remove all soft tissue and cartilage, sometimes within days or weeks. If the body has been left in a protected place, such as a vault or closed building, then dried tissue can remain for many years. In temperate climates, bodies left out in the open usually become substantially skeletalized within the first year, though tendon tags and periosteum may survive for 5 or more years. If a body dies in the autumn, then the preservation is likely to be longer through the colder winter months than if it died in the spring or summer.

After all soft tissue has vanished, recent bones may still be differentiated from old material by the density and feel of the bone. For a variable period, depending on storage conditions, a bone will feel slightly greasy to the fingers for several years, sometimes up to a decade if kept indoors. It will also feel heavy compared with older skeletal material because of the preservation of the organic stroma. On sawing a recent bone, it will be hard (especially the shafts of limb bones such as the femur) and will be uniform through the whole thickness. A smell of burning organic tissue will be obvious if vigorous sawing produces heat. In an old bone, the loss of the collagenous stroma will lighten the bone and make it easier to cut. The outer cortex and – to a lesser extent – the zone around the marrow cavity, will lose the stroma first, so a 'sandwich' effect may be seen in which a central ring of hard collagenous bone is layered on each side by a zone of more porous, crumbling material. This is not seen in less than several decades – and sometimes centuries – unless the bone has been exposed to the sun and other elements. The fragile, brittle appearance of old bones is usually first apparent on the ends of long bones, adjacent to the joints, such as the tibial plateau or the greater trochanter of the femur. This is often because the outer layer of compact bone is thinner there than in the shaft, so that the soft cancellous bone of the extremities is more readily exposed. This occurs within a few decades if the bone has been outside, but may not develop for a century in protected material. The aged cortex will feel rough and porous and, in really old material, can be crumbled or pitted with a fingernail.

Another factor that markedly affects the rate of decay of bones is the size and type of the bone itself. While thick, dense bone, such as femoral or humeral shaft, may last for centuries, smaller and thinner items may disintegrate rapidly. Skull plates, tarsal and carpal bones, digits and the thin bones of the facial skeleton will rot more quickly, as will the small bones of fetuses and infants.

Bone microscopy has also been investigated in this sense. Undecalcified thin sections of bone (similar to those used for aging and for species determination) can be studied in order to verify degradation of the microscopic osteonal structure. Tunneling, erosion and basically the disappearance of the primary bone struture made of Haversian systems along with fungal infiltration usually gives old bone a 'rotten' aspect. Once again, however, this depends on type of burial and external variables to which the bone has been exposed.

Bone microscopic and macroscopic appearance certainly is somehow, but not only, related to time. Forensic taphonomy is a relatively new discipline with which all those who study human skeletal remains should be acquainted. Efremov coined this term in the 1940s as the "study of the transition, in all details, of organics from the biosphere into the lithosphere of the geological record" and it was originally applied to palaeontology and archaeology.[139] Haglund and Sorg however, re-defined the object of taphonomy as the preservation, observation or recovery of dead organisms, the reconstruction of their biology or ecology and the reconstruction of the circumstances of their death: particularly the study of factors related to skeletal element survival.[140] This makes of taphonomy the science that can help us understand the effects of the environment on bone and why and how degradation cannot be directly correlated to time since death.

Physical tests

In parallel with the physical appearance of the sawn bone, fluorescence in ultraviolet light can be a useful preliminary test. If a shaft is cut across and inspected in the dark under ultraviolet light, such as that from a Wood's lamp, recent bone will shine with a silvery-blue tint right across the whole section. As the bone ages, the outer rim will cease to fluoresce and this will progressively deepen towards the centre. As with visual and tactile examination, a similar zone will work its way outwards from the marrow cavity until only a thin sandwich-filling will survive. This then fragments and eventually vanishes so that all the cut surface is non-fluorescent. The time that this process takes is variable, but total loss of ultraviolet fluorescence takes somewhere of the order of at least 100–150 years to complete. Other physical tests have been described, including density and specific gravity measurements, ultrasonic conduction and thermal behaviour when heated under special conditions. All these criteria depend on the loss of organic stroma and the development of a calcified matrix with a porous structure.

Serological and chemical tests Sr, C14

Positive tests for the presence of haemoglobin may be obtained for a variable time on either the bone surface or powdered bone, this being partly dependent on the sensitivity of the technique. Using the dye-peroxide methods (benzidine is most sensitive, but is now proscribed by Health and Safety regulations, so that the less satisfactory Kastel–Meyer test must be used), positive results may be obtained up to about 100 years.

Serological activity lasts only a short time in bones exposed to the weather. Bone powder eluted with weak ammonia and vacuum concentrated, may give a positive reaction with antihuman sera, such as Coombs reagent, for only about 5–10 years – again depending greatly on the environmental conditions.

More recent research has also tested the survival of blood proteins such as albumin and immunoglobulins via immunological assays. Many molecules in fact can be used with the rationale that their degradation (referred to as diagenesis) or survival can be a an indicator of time since death. As mentioned above, this can in theory be true of the epitopic components of most animal proteins or other molecules, even DNA. But once again biomolecular degradation can depend on so many variables (in the same fashion as the macroscopic decay of bone) that in more cases than one would think DNA may be more difficult to amplify and detect in recent bone than in older bone. Thus somewhat paradoxically old archaeological bone has been known to still harbour legible DNA whereas recent 50-year-old bone may not.

Chemical testing seeks to measure the degradation of the proteinous stroma, so knowing the total nitrogen and amino acid content can be useful. Fresh compact bone contains about 4.5 per cent nitrogen, which progressively diminishes with time. If a bone contains more than about 4 per cent nitrogen, it is unlikely to be older than 100 years, but if it has 2.5 per cent or less, it is likely to be older than 350 years.

Residual protein can be converted to its constituent amino acids by prolonged heating in 6 M hydrochloric acid. The digest can then be analysed, either by autoanalytical methods or by two-dimensional chromatography. Fresh bone contains about 15 amino acids, mostly derived from collagen. Glycine and alanine are predominant, but proline and hydroxyproline are more specific markers for collagen. The latter two tend to vanish in about 50 years (as always, depending on the storage environment), so they are useful markers for the time threshold of forensic relevance. The other amino acids diminish over the succeeding scores and hundreds of years, so that a bone containing only four or five amino acids is likely to be relatively ancient. Glycine persists for millennia, being found in palaeolithic material.

Estimation of the racemization of amino acids in teeth (laevo/dextro proportions) is being used to determine age, and there is some evidence that it also changes linearly with post-mortem interval. Its use on skeletal structures other than teeth is being investigated.

In the past 50 years many other chemical and biochemical approaches have been attempted, which involve the study of several bone components such as X-ray diffraction of the crystalline structure of bone, decomposition byproducts, amino acids and citrate. Among these, the luminol technique has perhaps been the most thoroughly investigated. Measurement of chemiluminescence (CL) by the luminol reaction (5-amino-2,3-dihydro-1,4-phthalazinedione), is a method for detecting blood residues in all sorts of substrates, including bone. The bone is usually ground into a fine powder and then tested for luminescence by mixing with a small amount of luminol. Recent studies have shown false positive results in approximately 7.5 per cent of historical cases and false negative results in approximately 15 per cent of recent samples. Altogether, a correct classification of 88.75 per cent is to be expected. This makes it a method which cannot be used for distinguishing beyond reasonable doubt historical from recent bones.[141]

Radiochemical testing seems to be the future. These are based on decay rates of radioisotopes fixed in bone during life. The methods available for archaeologists to use on ancient skeletal remains are proportionately more accurate, but of little or no use in forensic science. The radiocarbon test, which measures the loss of carbon-14 after death, cannot be applied to material less than a couple of centuries old, as the loss of radioactive carbon, which has a half-life of well over 5000 years, is too small to be measured in the half-century or so that interests the forensic pathologist. Thus the use of carbon-14 provides accurate information about post-mortem interval (PMI) in case of archaeological remains, but its importance in forensic material is reduced because its BP (before period) date refers to the 1950s. Strontium 90 may also be useful; its high atmospheric concentration is due to massive explosions and nuclear weapon pollution, which occurred during World War II. The principle behind the method is that pre-1945 bones should be free of endogenous strontium-90, derived from nuclear weapons and atmospheric tests, which was at a maximum in the environment in the early 1960s (Fig. 3.26). The possibility exists that atmospheric contamination with other isotopes laid down in bone from dated tests and nuclear accidents may provide a profile that could bring forward the latest date during which the person must have been alive.

At the moment the most reliable and useful method is the one that benefits from the high levels of artificially introduced carbon-14 in terrestrial organisms by thermonuclear devices between 1950 and 1963. It is based on the observation that different tissues of the body have a diverse time of development and a diverse turnover rate. Quantifying radiocarbon values in different tissues and placing these values in the bomb-curve (Fig. 3.27), taking care of noting the age of the individual and other factors, allows an estimation of the date of death.[142]

In conclusion it is therefore evident how difficult it may be to determine time since death with skeletal remains. This is why the context of retrieval is of fundamental importance. Upon retrieval the pathologist should look out for all sorts of entomological, botanical or even geological evidence, which may help determine time of death. The botanical analysis of leaves, roots and seeds on and around the remains for example can give a *post quem non* or *antequem non* temporal limit by aging the elements that have invaded the site after the deposition (Figs 3.28, 3.29). Entomological studies of insects colonizing remains may provide a more accurate indication about age of deposition; corpses are in fact colonized by different insect populations in accordance with season, climatic conditions, environmental characteristics and decomposition stage. Finally, clothes and personal belongings found at the site may also be crucial in determining time of death. Thus a general rule is that the more decomposed a body is the less it will reveal concerning PMI and the more important the natural environment in which it has dwelled becomes.



Figure 3.26 Average annual atmospheric $^{14}CO_2$ record for the northern hemisphere (adapted from Ubelaker *et al.*, 2006).[142]



Figure 3.27 Example of an artificial radiocarbon (F-C14) curve for samples from a skeleton belonging to a person who died after the 1950s. The search for artificial C-14 at the moment therefore designates remains as of forensic interest. The present example refers to a death that probably occurred in the early 1980s.



Figure 3.28 A shoe worn by a skeleton found in an irrigation ditch in the autumn of 2011. (Reproduced by kind permission of Professor C. Cattaneo.)



Figure 3.29 Cross-section of the root of American Pokeweed (*Phytolacca americana*), which was found growing through a shoe worn by a skeleton. The rings show that the root grew between 2006 and 2011, thus placing a '*post quem non*'-time of death at 2006. (Reproduced by kind permission of Professor C. Cattaneo.)

References

1 Hellerich U. [Tattoo pigment in regional lymph nodes—an identifying marker?]. *Arch Kriminol* 1992;190(5–6):163–70.

2 Lehner K, *et al*. The decrease of pigment concentration in red tattooed skin years after tattooing. *J Eur Acad Dermatol Venereol* 2011;25(11):1340–5.

3 Sanders C. *Customizing the Body: the Art and Culture of Tattooing*. Philadelphia: Temple University Press, 1989, xi.

4 Pitts-Taylor V. *In the Flesh: the Cultural Politics of Body Modification*. New York: Palgrave Macmillan, 2003, vi.

5 Wohlrab S, Stahl J, Kappeler PM. Modifying the body: motivations for getting tattooed and pierced. *Body Image* 2007;4(1):87–95.

6 Porta D, *et al*. A new method of reproduction of fingerprints from corpses in a bad state of preservation using latex. *J Forensic Sci* 2007;52(6):1319–21.

7 Naegeli O. Familiarer chromatophorennävus. *Schweiz Med Wochenschr* 1927;8(48):48–51.

8 Lugassy J, *et al*. Naegeli-Franceschetti-Jadassohn syndrome and dermatopathia pigmentosa reticularis: two allelic ectodermal dysplasias caused by dominant mutations in KRT14. *Am J Hum Genet* 2006;79(4):724–30.

9 Foran DR, *et al*. The conviction of Dr. Crippen: new forensic findings in a century-old murder. *J Forensic Sci* 2011;56(1):233–40.

10 Faller-Marquardt M, Pollak S, Schmidt U. Cigarette burns in forensic medicine. *Forensic Sci Int* 2008;176(2-3):200–8.

11 Buschoff HS. *The gout, more narrowly searcht, and found out; together with the certain cure thereof.* Michel W (ed). London (Fukuoka-City): Kyushu University, Faculty of Languages and Cultures, 1676 (2003), p. 118.

12 Trotter M, Gleser GC. A re-evaluation of estimation of stature based on measurements of stature taken during life and of long bones after death. *Am J Phys Anthropol* 1958;16(1):79–123.

13 Sullivan KM, *et al*. A rapid and quantitative DNA sex test: fluorescence-based PCR analysis of X-Y homologous gene amelogenin. *Biotechniques* 1993;15(4):636–8, 640–1.

14 Mannucci A, *et al*. Forensic application of a rapid and quantitative DNA sex test by amplification of the X-Y homologous gene amelogenin. *Int J Legal Med* 1994;106(4):190–3.

15 Cattaneo C. Anthropology: aging the living. In: *Wiley Encyclopedia of Forensic Science*. London: John Wiley, 2009.

16 Lamendin H, *et al*. A simple technique for age estimation in adult corpses: the two criteria dental method. *J Forensic Sci* 1992;37(5):1373–9.

17 Baccino E, *et al*. Evaluation of seven methods of estimating age at death from mature human skeletal remains. *J Forensic Sci* 1999;44(5):931–6.

18 Foti B, *et al*. Limits of the Lamendin method in age determination. *Forensic Sci Int* 2001;122(2–3):101–6.

19 Prince DA, Ubelaker DH. Application of Lamendin's adult dental aging technique to a diverse skeletal sample. *J Forensic Sci* 2002;47(1):107–16.

20 Soomer H, *et al*. Reliability and validity of eight dental age estimation methods for adults. *J Forensic Sci* 2003;48(1):149–52.

21 Gonzalez-Colmenares G, *et al*. Age estimation by a dental method: a comparison of Lamendin's and Prince & Ubelaker's technique. *J Forensic Sci* 2007;52(5):1156–60.

22 Martrille L, *et al*. Comparison of four skeletal methods for the estimation of age at death on white and black adults. *J Forensic Sci* 2007;52(2):302–7.

23 Kimmerle EH, Prince DA, Berg GE. Inter-observer variation in methodologies involving the pubic symphysis, sternal ribs, and teeth. *J Forensic Sci* 2008;53(3):594–600.

24 Meinl A, *et al*. Comparison of the validity of three dental methods for the estimation of age at death. *Forensic Sci Int* 2008;178(2–3):96–105.

25 Prince DA, Konigsberg LW. New formulae for estimating age-at-death in the Balkans utilizing Lamendin's dental technique and Bayesian analysis. *J Forensic Sci* 2008;53(3):578–87.

26 Franbourg A, *et al*. Current research on ethnic hair. *J Am Acad Dermatol* 2003;48(6, Supplement 1):S115–S119.

27 Ubelaker DH, *et al*. The use of SEM/EDS analysis to distinguish dental and osseus tissue from other materials. *J Forensic Sci* 2002;47(5):940–3.

28 Owsley DW, Mires AM, Keith MS. Case involving differentiation of deer and human bone fragments. *J Forensic Sci* 1985;30(2):572–8.
29 Cattaneo C, *et al.* Determining the human origin of fragments of burnt bone: a comparative study of histological, immunological and DNA techniques. *Forensic Sci Int* 1999;102(2–3):181–91.
30 Cattaneo C, *et al.* Histological determination of the human origin of bone fragments. *J Forensic Sci* 2009;**54**(3):531–3.
31 Ubelaker DH, Lowenstein JM, Hood DG. Use of solid-phase double-antibody radioimmunoassay to identify species from small skeletal fragments. *J Forensic Sci* 2004;49(5):924–9.
32 Lowenstein JM, *et al.* Identification of animal species by protein radioimmunoassay of bone fragments and bloodstained stone tools. *Forensic Sci Int* 2006;159(2–3):182–8.
33 Krogman WCA. A guide to the identification of human skeletal material. *FBI Law Enforcement Bull* 1939;8:3.
34 Krogman WCA. The skeleton in forensic medicine. *Proc Inst Med* 1946;16:154.
35 Krogman WM, Iscan YM. *The Human Skeleton in Forensic Medicine*, 2nd edn. Springfield: Charles C. Thomas, 1986.
36 Hrdlicka A. *Practical Anthropometry*. Philadelphia: Wistar, 1939.
37 Stewart TD. Medicolegal aspects of the skeleton. *Am J Phys Anthropol* 1948;6:315–21.
38 Stewart TD. Medico-legal aspects of the skeleton; sex, age, race and stature. *Am J Phys Anthropol* 1948;6(2):244.
39 Stewart TD. Medico-legal aspects of the skeleton; age, sex, race and stature. *Am J Phys Anthropol* 1948;6(3):315–21.
40 Stewart TD. Sex determination of the skeleton by guess and by measurement. *Am J Phys Anthropol* 1954;12(3):385–9.
41 Stewart TD. New developments in evaluating evidence from the skeleton. *J Dent Res* 1963;42(1)Pt 2:264–73.
42 Hoshi H. Sex difference in the shape of the mastoid process in norma occipitalis and its importance to the sex determination of the human skull. *Okajimas Folia Anat Jpn* 1962;38:309–13.
43 Giles E, Elliot O. Sex determination by discriminant function analysis of crania. *Am J Phys Anthropol* 1963;21:53–68.
44 Richman EA, *et al.* Determination of sex by discriminant function analysis of postcranial skeletal measurements. *J Forensic Sci* 1979;24(1):159–67.
45 Taylor JV, *et al.* Metropolitan Forensic Anthropology Team (MFAT) studies in identification: 1. Race and sex assessment by discriminant function analysis of the postcranial skeleton. *J Forensic Sci* 1984;29(3):798–805.
46 Leopold D, Novotny V. [Sex determination from the skull and parts of the hip bone]. *Gegenbaurs Morphol Jahrb* 1985;131(3):277–85.
47 Johnson DR, *et al.* Determination of race and sex of the human skull by discriminant function analysis of linear and angular dimensions. *Forensic Sci Int* 1989;41(1–2):41–53.
48 Inoue M, *et al.* Sex determination by discriminant function analysis of lateral cranial form. *Forensic Sci Int* 1992;57(2): 109–17.
49 Song HW, Lin ZQ, Jia JT. Sex diagnosis of Chinese skulls using multiple stepwise discriminant function analysis. *Forensic Sci Int* 1992;54(2):135–40.
50 Hsiao TH, Chang HP, Liu KM. Sex determination by discriminant function analysis of lateral radiographic cephalometry. *J Forensic Sci* 1996;4**1**(5):792–5.
51 Ross AH, McKeown AH, Konigsberg LW. Allocation of crania to groups via the 'new morphometry'. *J Forensic Sci* 1999;44(3):584–7.
52 Patil KR, Mody RN. Determination of sex by discriminant function analysis and stature by regression analysis: a lateral cephalometric study. *Forensic Sci Int* 2005;147(2–3):175–80.
53 Ramsthaler F, Kreutz K, Verhoff MA. Accuracy of metric sex analysis of skeletal remains using Fordisc based on a recent skull collection. *Int J Legal Med* 2007;121(6):477–82.
54 Walker PL. Sexing skulls using discriminant function analysis of visually assessed traits. *Am J Phys Anthropol* 2008;136(1):39–50.
55 Spradley MK, Jantz RL. Sex estimation in forensic anthropology: skull versus postcranial elements. *J Forensic Sci* 2011;56(2):289–96.
56 Phenice TW. A newly developed visual method of sexing the os pubis. *Am J Phys Anthropol* 1969;30(2):297–301.
57 Iscan MY, Derrick K. Determination of sex from the sacroiliac; a visual assessment technique. *Florida Sci* 1984;47:948.
58 Washburn S. Sex differences in the pubic bone. *Am J Phys Anthropol* 1948;6:199–298.
59 Schultz A. Proportions, variability and asymmetry of the long bones of the limbs and clavicles in man and apes. *Hum Biology* 1937;9:281–328.
60 Harrison R. *Gradwohl's Legal Medicine*, 2nd edn. Camps F (ed). Bristol: John Wright, 1968.
61 Greulich WW, Thomas H. The dimensions of the pelvic inlet of 789 white females. *Anat Rec* 1938;72:45–51.
62 Turner W. The index of the pelvic brim as a basis of classification. *J Anat Physiol* 1886;20:125–43.
63 Caldwell WE, Molloy HC. Anatomical variations in the female pelvis. *Am J Obstet Gynecol* 1933;26:479–505.
64 Straus WL. The human ilium: sex and stock. *Am J Phys Anthropol* 1927;11:1–28.
65 Derry DE. On the sexual and racial characters of the human ilium. *J Anat* 1923;58:71–83.
66 Derry DE. Note on the innominate bone as a factor in the determination of sex: with special reference to the sulcus praeauricularis. *J Anat Physiol* 1909;43(Pt 3):266–76.
67 Fawcett E. Sexing of the human sacrum. *J Anat* 1938;72:633–7.
68 Kimura K. Sex differences of the hip bone among several populations. *Okajimas Folia Anat Jpn* 1982;58(4–6):265–76.
69 Dar G, Hershkovitz I. Sacroiliac joint bridging: simple and reliable criteria for sexing the skeleton. *J Forensic Sci* 2006;51(3):480–3.
70 Pearson K, Bell JA. A study of the long bones of the English skeleton. 1. The Femur. In: Drapers' Company Research Memoirs. Biometric Series X. London: Cambridge University Press, 1917.
71 Maltby J. Some indices and measurements of the modern femur. *J Anat* 1917/18;52:363–82.
72 Dwight T. The size of the articular surfaces of the long bones as characteristic of sex. *J Anat* 1904/05;4:19–32.
73 Black TK 3rd. Sexual dimorphism in the tooth-crown diameters of the deciduous teeth. *Am J Phys Anthropol* 1978;48(1):77–82.
74 Iscan MY, Miller-Shaivitz P. Discriminant function sexing of the tibia. *J Forensic Sci* 1984;29(4):1087–93.
75 Godycki M. Sur la certitude de determination du sexe l'après le femur, le cubitus et l'humerus. *Bull Mem Soc Anthrop Paris* 1957;Serie 10:405–10.
76 Hyrtl J. *Handbuch der Topographischen Anatomie*. Vienna: Wilhelm Braumüller, 1893.
77 Dwight T. The sternum as an index of sex, height and age. *J Anat Physiol* 1889;24:527–35.
78 Iordanidis P. Determination du sexe par les os du squelette (atalas, axis, clavicle, omoplate, sternum). *Ann Med Leg* 1961;41:28–91.

79 Stewart JH, McCormick WF. The gender predictive value of sternal length. *Am J Forensic Med Pathol* 1983;4(3):217–20.

80 Snodgrass JJ, Galloway A. Utility of dorsal pits and pubic tubercle height in parity assessment. *J Forensic Sci* 2003;48(6):1226–30.

81 Telkkä A. On the prediction of human stature from long bones. *Acta Anat (Basel)* 1950;9:103–17.

82 Manouvrier L. Le determination de la taille d'après les grands os des membres. *Mem Soc Anthropol Paris* 1893;4:347–402.

83 Dupertuis CW, Hadden JA. On the reconstruction of stature from long bones. *Am Journal Phys Anthropol* 1951;9:15–54.

84 Breitinger, E., *Zur Berechnung der Körperhöhe aus den langen Gleidmassenknochen*. Anthropology Anz, 1937. **14**: p. 249-74.

85 Allbrook, D., *The estimation of stature in British and East African males; based on tibial and ulnar bone lengths.* Journal Forensic Med, 1961. **8**: p. 15-28.

86 Shiati, M., *Estimation of stature by long bones of Chinese male adults in South China*. Acta Anthropol Sinica, 1983. **2**: p. 80–5.

87 Mendes-Correa, A.A., *Le taille des Portugais d'après les os longes.* Anthropology (Praque), 1932. **10**: p. 268-72.

88 Stevenson, P.H., *On racial differences in stature long bone regression formulae with special reference to stature reconstruction formulae for the Chinese.* Biometrika, 1929. **21**: p. 303-18.

89 Wells, L.H., *Estimation of stature from long bones: a reassessment*. Journal of Forensic Medicine, 1959. **6**: p. 171-7.

90 Fully, G. and H. Pineau, *Determination de la stature au moyen du squelette.* Ann Med Leg, 1960. **40**: p. 3-11.

91 Tibbetts, G.L., *Estimation of stature from the vertebral column in American Blacks.* J Forensic Sci, 1981. **26**(4): p. 715-23.

92 Jit, I. and S. Singh, *Estimation of stature from the clavicles.* Indian Journal of Med Res, 1956. **44**: p. 137-55.

93 Olivier, G., *Practical Anthropology*. 1969, Springfield: Thomas.

94 Steele, D.G. and T.W. McKern, *A method for assessment of maximum long bone length and living stature from fragmentary long bones.* Am J Phys Anthropol, 1969. **31**(2): p. 215-27.

95 Muller, G., *Zur Bestimmung der Länge beschädigter Extremitätenknochen*. Anthropology Anz, 1935. **12**: p. 70-2.

96 Mehta, L. and H.M. Singh, *Determination of crown-rump length from fetal long bones: humerus and femur.* Am J Phys Anthropol, 1972. **36**(2): p. 165-8.

97 Cunha E, *et al.* The problem of aging human remains and living individuals: a review. *Forensic Sci Int* 2009;193(1–3):1–13.

98 Fazekas G, Kosa F. *Forensic Fetal Osteology.* Budapest: Akademiai Kiado, 1978.

99 Scheuer L, Black SM. *Developmental Juvenile Osteology*. San Diego: Academic Press, 2000.

100 McKern TW, Stewart TD. Skeletal age changes in young American males: analysed from the stand point of age identification. In: *U.S. Army Technical Report*. Natick: Quarter master research and development centre, 1957, p. 71.

101 Francis, G.C. and P.P. Werle, *The appearance of centers of ossification from birth to 5 years.* Am J Phys Anthropol, 1939. **24**(3): p. 273-86.

102 Todd TW. Age changes in the pubic bone. *Am J Phys Anthropol* 1920;3:285–334.

103 Todd TW. Age changes in the pubic bone I–IV. *Am J Phys Anthropol* 1921;4:407.

104 Stewart TD. Distortion of the pubic symphyseal surface in females and its effect of age determination. *Am J Phys Anthropol* 1957;15(1):9–18.

105 Gilbert BM, McKern TW. A method for aging the female os pubis. *Am J Phys Anthropol* 1973;38(1):31–8.

106 Brooks S, Suchey J. Skeletal age determination based on the os pubis: a comparison of the Acsádi-Nemeskéri and Suchey-Brooks methods. *Hum Evol* 1990;5(3):227–38.

107 Iscan MY, Loth SR, Wright RK. Age estimation from the rib by phase analysis: white males. *J Forensic Sci* 1984;29(4):1094–104.

108 Iscan MY, Loth SR, Wright RK. Metamorphosis at the sternal rib end: a new method to estimate age at death in white males. *Am J Phys Anthropol* 1984;65(2):147–56.

109 Iscan MY, Loth SR, Wright RK. Age estimation from the rib by phase analysis: white females. *J Forensic Sci* 1985;30(3):853–63.

110 Steyn M. [Personal communication. 2015]

111 Iscan MY, Steyn M. *The Human Skeleton in Forensic Medicine*, 3rd edn. Springfield: Charles C Thomas Publisher, 2013, xxii.

112 Lovejoy CO, *et al.* Chronological metamorphosis of the auricular surface of the ilium: a new method for the determination of adult skeletal age at death. *Am J Phys Anthropol* 1985;68(1):15–28.

113 Kerley ER, Ubelaker DH. Revisions in the microscopic method of estimating age at death in human cortical bone. *Am J Phys Anthropo*l 1978;49(4):545–6.

114 Brothwell DR. *Digging up Bones*, 2nd edn. British Museum (Natural History), 1972.

115 Sauer NJ. Forensic anthropology and the concept of race: if races don't exist, why are forensic anthropologists so good at identifying them? *Soc Sci Med* 1992;34(2):107–11.

116 Ousley S, Jantz R, Freid D. Understanding race and human variation: why forensic anthropologists are good at identifying race. *Am J Phys Anthropol* 2009;139(1):68–76.

117 Munter AH. A study of the lengths of long bones of the arms and legs in man, with special reference to Anglo-Saxon skeletons. *Biometrika* 1936;28:84–22.

118 Schultz A. Proportions, variability and asymmetry of the long bones of the limbs and clavicles in man and apes. *Hum Biology* 1937;9:281–328.

119 Modi JP. *Medical Jurisprudence and Toxicology*. Bombay: Tripathi, 1957.

120 Jantz RL, Ousley SD. *FORDISC: Computerized Forensic Discriminant Functions*. Knoxville: University of Tennessee, 2005.

121 Gerasimov MM. *The Face Finder*. Philadelphia: J. B. Lippincott, first English language edn., 1971.

122 Vanezis P, *et al.* Application of 3-D computer graphics for facial reconstruction and comparison with sculpting techniques. Forensic Sci Int 1989;42(1–2):69–84.

123 Rynn C, Wilkinson CM, Peters HL. Prediction of nasal morphology from the skull. *Forensic Sci Med Pathol* 2010;6(1): 20–34.

124 Stephan CN, Cicolini J. Measuring the accuracy of facial approximations: a comparative study of resemblance rating and face array methods. *J Forensic Sci* 2008;53(1):58–64.

125 Schüller A. Das Röntgenogram der Stirnhöhle. *Monatschrift Ohrenheilkunde* 1921;55:1617–20.

126 Mayer, J., *Identification by sinus prints.* Virginia Med Monthly, 1935. **62**: p. 517-19.

127 Schüller A. A note on the identification of skulls by X-ray pictures of the frontal sinuses. *Med J Aust* 1943;25:554–6.

128 Asherson N. *Identification by Frontal Sinus Prints: A Forensic Medicine Pilot Survey*. London: HK Lewis, 1965.

129 Turpin R, Tisserand M. Etude correlative de sinus. *Compte Rendu Soc Biology* 1942;136:203–10.

130 Reichs KJ. Quantified comparison of frontal sinus patterns by means of computed *tomography*. *Forensic Sci Int* 1993;61(2–3): 141–68.

131 Yoshino M, *et al*. Classification system of frontal sinus patterns by radiography. Its application to identification of unknown skeletal remains. *Forensic Sci Int* 1987;34(4):289–99.

132 Ciaffi R, *et al*. *Identification from chest x-rays: reliability of bone density patterns of the humerus. J Forensic Sci* 2010;55(2):478–81.

133 Ciaffi R, Gibelli D, Cattaneo C. Forensic radiology and personal identification of unidentified bodies: a review. *Radiol Med* 2011;116(6):960–8.

134 Stephan CN, *et al*. Skeletal identification by radiographic comparison: blind tests of a morphoscopic method using antemortem chest radiographs. *J Forensic Sci* 2011;56(2):320–32.

135 Gordon GM, Steyn M. An investigation into the accuracy and reliability of skull-photo superimposition in a South African sample. *Forensic Sci Int* 2012;216(1–3):198 e1–6.

136 De Angelis D, Cattaneo C, Grandi M. Dental superimposition: a pilot study for standardising the method. *Int J Legal Med* 2007;121(6):501–6.

137 Grivas CR, Komar DA. Kumho, Daubert, and the nature of scientific inquiry: implications for forensic anthropology. *J Forensic Sci* 2008;53(4):771–6.

138 Megyesi MS, Nawrocki SP, Haskell NH. Using accumulated degree-days to estimate the postmortem interval from decomposed human remains. *J Forensic Sci* 2005;50(3):618–26.

139 Yefremov I.A. Taphonomy: a new branch of Paleontology. Pan-A*mer Geol* 1940;74:81–93.

140 Haglund WD, Sorg MH (eds). *Forensic Taphonomy: The Postmortem Fate of Human Remains*, 1st edn. CRC Press, 1996.

141 Ramsthaler F, *et al*. Dating skeletal remains with luminol-chemiluminescence. Validity, intra- and interobserver error. *Forensic Sci Int* 2009;187(1–3):47–50.

142 Ubelaker DH, Buchholz BA, Stewart JE. Analysis of artificial radiocarbon in different skeletal and dental tissue types to evaluate date of death. *J Forensic Sci* 2006;51(3):484–8.

CHAPTER 4

The Pathology of Wounds

- Definition of a wound
- Mechanism of wounding
- Classification of wounds
- Forensic anatomy of the skin
- Abrasions
- Contusions or bruises
- Kicking
- Lacerations
- Blunt penetrating injuries
- Incised wounds
- Dating of wounds by histology and histochemistry
- Survival period after wounding
- References

Definition of a wound

A wound or injury can best be defined as 'damage to any part of the body due the application of mechanical force'. Some jurisdictions have a legal definition of a 'wound', which usually requires the integrity of the body surface to be breached. As this obviously excludes bruising and damage to deep organs, it is unrealistic in a medical sense, but there is always some legal alternative, such as 'causing serious bodily harm', which covers any injury to any tissue or organ. Other jurisdictions grade wounds not by their physical nature, but by the perceived risk to life or health of the victim; this can be an extremely difficult prognostic exercise.

Mechanism of wounding

The human body is constantly subjected to mechanical forces during the normal course of life, varying from unceasing gravitational forces to the forceful impacts of a sporting contest. The body usually absorbs such forces either by the resilience and elasticity of its soft tissues or the rigid strength of its skeletal framework. It is only when the intensity of the applied force exceeds the capability of the tissues to adapt or resist that a wound or injury occurs.

The intensity of the force obeys the usual laws of physics, in that the force varies directly with the mass of the 'weapon' and directly with the *square* of velocity of impact. Of course, the weapon can be anything, including the body itself, as is often seen in the violent deceleration of a fall or in a traffic accident.

The well-known formula: *Kinetic energy* = ½ *mass* × *velocity*^{2}, means that a 1 kg brick pressed against the scalp will cause no injury, but the same brick thrown against the head at a velocity of 10 m/s may smash the skull. This principle is relevant not only in relation to blunt injury and firearm missiles, but also to stab wounds, as is discussed later.

Another factor of importance is the area over which the force acts. If a plank of wood is struck against the skin, the damage to the tissues will be far greater if the narrow edge is used, than if the impact is from the flat surface. Obviously, the force derived from the same mass and velocity is applied over a smaller area, thus delivering a greater impact to any given unit of tissue. This again is relevant to stab wounds, as all the kinetic energy of a moving knife is concentrated into the tiny area of the tip of the blade; the same energy delivered by the large surface area of a cricket bat might not even cause a bruise.

The effect of excessive mechanical forces on the tissues of the body can cause compression, traction, torsion, and tangential (shear) and leverage stresses. The resultant damage depends not only on the type of the mechanical insult but also on the nature of the target tissue. For instance, violent compression (as in an explosion) may do little harm to muscle, but may rupture lung or intestine, while torsion may leave adipose tissue unaffected, yet cause a spiral fracture in a femur.

The transfer of kinetic energy from the relative movements of the body and the weapon is the source of damage to the tissues. If the attacking object comes to rest in the tissues, then all its kinetic energy must have been transferred. A bullet which passes clean through the tissues thus fails to exchange all its energy into trauma production, which is the reason for the illegal 'dumdum' or more recent, explosive-tipped bullets, the object of which is to expand the missile and prevent its exit from the body, so increasing its 'stopping power' (see Chapter 8). If such energy transfer can be slowed down or spread over a wider area, then the intensity of force applied to the tissues per unit of time is less. This is part of the function of a seatbelt in a vehicle crash, where the stretching of the belt fabric extends the time of energy exchange and the considerable area of the belt surface is a preferable alternative to transferring all the kinetic energy via a few square centimetres of forehead against the windscreen.

Other ways in which the transfer of kinetic energy may be modified is in moving the body in the direction of the force. When a car strikes a pedestrian, that proportion of the momentum of the car that is used in projecting the victim along the road is not then available for damaging the tissues.

Similarly, if a boxer 'rides the punch', he is reducing the differential velocity between his head and his opponent's fist, as well as extending the time over which energy transfer occurs. With a high-speed impact, such as a bullet and – to a lesser extent a stab or violent blow – the inertia of the victim's body prevents any significant loss of energy transfer by movement. If the force does not strike in a linear fashion, but leads to a tangential impact – as in a glancing blow causing a 'graze' – then only part of the kinetic energy is transferred and the damage will be proportionately less.

Classification of wounds

This is quite arbitrary, but when writing medical reports (especially for legal purposes) it is essential that every doctor should use a standardized nomenclature when describing wounds. All too often reports are seen – especially from clinicians who are not used to medico-legal work – where 'laceration', 'incised wound' and 'abrasion' are used loosely, the accompanying descriptions making it obvious that no clear distinction between them was appreciated by the doctor.

Wounds may also be categorized by the motivation of their infliction, such as 'suicidal or accidental' (the 'manner' index of the WHO International Classification of Disease, ICD E-codes), but a pathologist should classify them by their appearance and the method of causation, such as 'laceration' or 'incised wound'. The most useful classification is (Fig. 4.1):

- Abrasions – colloquially 'grazes or scratches'.
- Contusions – colloquially 'bruises'.
- Lacerations – colloquially 'cuts or tears'.
- Incised wounds – colloquially 'cuts', 'slashes' or 'stabs'.

Forensic anatomy of the skin

As most wounds involve the body surface, a reminder of the structure and nomenclature of the skin and subcutaneous tissues is appropriate. Most superficial is the keratinized dead layer of cells, the stratum



Figure 4.1 Types of injury to the skin.



Figure 4.2 General structure of skin.



Figure 4.3 Simple abrasion of the skin caused by a perpendicular impact of the head against the side pillar of a car. There is no clear tangential scuffing though most abrasions have some element of sideways contact that damages the epidermis.

corneum, which varies greatly in thickness from one part of the body to another. That on the soles and palms is the thickest, while that on protected areas such as the scrotum and eyelids measures only a fraction of a millimetre. This has forensic relevance in the amount of injury that is needed to penetrate the skin and allow bleeding from the underlying tissues.

The living layers of the skin combine with the horny layer to form the epidermis, which has no blood vessels in its thickness. The epidermis is generally corrugated, the under surface by papillae that dip into the dermis. The degree of undulation also varies greatly from place to place, the thinner skin tending to have a flatter junction between dermis and epidermis. The dermis (or 'corium') consists of mixed connective tissue carrying the skin adnexae, such as hair follicles, sweat glands and sebaceous glands. It has a rich network of blood vessels, nerves and lymphatics, and has numerous nerve endings of various types for tactile, pressure and heat sensing. The lower zone of the dermis has adipose tissue and – depending on the site in the body – deep fascia, fatty tissue and muscle will form strata below the skin itself (Fig. 4.2).

Abrasions

An abrasion is the most superficial of injuries and, in the most restrictive of definitions, is one that does not penetrate the full thickness of the epidermis. Thus the pure abrasion does not bleed, as blood vessels are confined to the dermis. Because of the corrugated nature of the dermal papillae, however, many abrasions enter the corium and bleeding commonly occurs (Fig. 4.3).

Another definition (all of which are arbitrary) would describe an abrasion as a superficial injury to 'the skin', which would allow penetration of the upper dermis rather than only the epidermis, so that bleeding would fall within the definition.

Abrasions are known in lay terms as 'scratches' or 'grazes', though the former usually indicates a linear mark and the latter a 'brush' abrasion caused by wider tangential impact. Where these brush abrasions are the result of scraping contact with the ground, the lay term is a 'gravel rash'. There are many causes of abrasions, which are common every-day lesions, especially in children whose legs are rarely free from some scratches and bruises. Any contact that rubs across the epidermis and removes the keratinized layer and underlying cells will cause that area to become discoloured and moistened by exuded tissue fluid, even if bleeding does not occur from abraded dermal papillae.

When death ensues soon afterwards, the abrasion becomes stiff, leathery and of a parchment-like brown colour as a result of the drying of the moist exposed surface (Fig. 4.10). This is classically seen, for example, in the ligature mark of hanging or strangulation. It is impossible to tell whether a superficial abrasion occurred immediately before or after death if there was insufficient time for any inflammatory reaction to occur at the margins. Post-mortem abrasions are common, especially after autopsy when the body is re-examined, because mortuary instruments and the moving of bodies into refrigerators and coffins can often make marks. These abrasions commonly appear yellow and translucent, and are absolutely devoid of any colour change at the edge.

Tangential or brush abrasions

Most abrasions are caused by a lateral rubbing action rather than vertical pressure. Where this tangential component is marked, the direction of the force can often be determined by tags of epidermis dragged to the terminal end of the abrasion. For example, in the 'brush abrasion', which is common in childhood falls and pedestrian accidents, the skidding of the body across a rough surface scrapes linear furrows across the skin. Strands and tags of epidermis may be peeled along these furrows to the further end where contact ceased. Visual examination, using a lens if necessary, can indicate the direction of movement of the body. Similarly, if a victim is struck a glancing blow with a rough object such as a stone or brick, similar epidermal tags may indicate the direction of the blow (Figs 4.4–4.7).

The same type of grooved abrasions can be caused when a victim is dragged along the ground, either in a vehicular accident or by an assailant. It may be important, though difficult, to attempt to differentiate such drag marks as being ante-mortem or post-mortem, a problem, which is discussed, in another chapter (Fig. 4.8).



Figure 4.4 A linear abrasion or 'graze', confined to the upper layers of the skin. The tangential direction of impact of the weapon was from above downwards (along the longitudinal axis of the upper arm), as can be determined by the shreds of epidermis peeled towards the lower end.



Figure 4.6 'Brush abrasion' or 'grazes' caused by tangential contact of a moving body with a rough surface. Although most are seen in traffic accidents from contact with the road surface, this example is from a murdered female dropped down a mine shaft. There are grazes running in two directions at right angles, indicating that she must have struck the wall twice, in different postures.



Figure 4.7 Brush abrasion from skidding contact with the road surface. A moped driver got to the oncoming traffic lane in a gradual bend and collided with a bus. The lesion is partly abraded and partly bruised. The direction of movement can be discerned, as the bruises begin more abruptly below the kneecap, and tail off superficially towards the ankle.



Figure 4.5 Determination of the direction of impact in an abrasion caused by a tangential force. The epidermal tags raised by the impact tend to pile up at the distal end.



Figure 4.8 Drag marks on the front of the thighs of a murder victim. In addition to the drag marks there are bruises, and burn injuries above the knees on both sides. Death was caused by stab wounds to the chest.

Crushing abrasions

Where the impact is vertical to the skin surface, no scraping or tangential marks occur. Instead the epidermis is crushed and an imprint of the impacting object is stamped on the surface. If the impact is substantial and the area of contact small, a punctured wound will be made, but otherwise a crushed abrasion will occur. The lesion is slightly depressed below the surface unless an underlying bruise or local oedema bulges the tissues. These abrasions are the ones that most clearly reproduce the pattern of the injuring object. An example would be the marks of a vehicle radiator on a pedestrian victim or the pattern of a floor grid on to which a person has fallen. If the impact is forcible then the dermis may also be injured: an area of bruising may underlie the abrasion.

Fingernail abrasions

These are important because of their frequency in assaults – especially child abuse, sexual attacks and strangulation. Often associated with focal bruises, fingernail abrasions are most often seen on the neck, the face, the upper arms and the forearms. They may be linear scratches if the fingers are dragged down the skin, or short, straight or curved marks when the skin is gripped in a static fashion. As females tend to have longer, sharper fingernails than males, they are naturally more often associated with causing such abrasions. A victim resisting a sexual or other attack may rake her nails down her assailant's face, causing linear, parallel scratches that may be several millimetres wide and placed a centimetre or two apart. The expected pattern may be fragmentary, however, as is often seen on the neck when a victim of either manual or ligature strangulation attempts to tear away the attacking fingers or cord. These marks are usually vertical, as opposed to the more random marks that may be inflicted by the nails of the assailant in manual strangulation (Fig. 4.9).

The upper arms are a frequent site for gripping and restraint, both in adult assaults and child abuse. Bruising is most common, but fingernail marks may be superimposed. Static fingernail abrasions may be straight or curved, often about 0.5–1.0 cm long. The direction of curvature must be interpreted with care if one wishes to decide which way the hand was held at the time of infliction.



Figure 4.9 Abrasions in manual strangulation. The area is more extensive than is usually seen in such circumstances. The large area of superficial damage to the epidermis is caused by sliding movements of the assailant's hands, the area having become dried and leathery during the post-mortem interval. The smaller marks are fingernail scratches.



Figure 4.10 Extensive abrasion of the knees and shins, in a drunk who stumbled amongst furniture before dying of a head injury. The damaged skin has exuded tissue fluid, which has dried post-mortem to produce the dark, leathery appearance.

Although it is natural to assume that the concavity of the mark indicates the orientation of the fingertip, experiments by Shapiro *et al.* have shown that this is often not the case.[1] Because the skin is put under lateral tension when it is indented by the nails, it may distort, so that when the tension is released the elasticity of the skin causes it to return to its original position, carrying the nail mark with it. The curve may then reverse to form either a straight line or a convexity. The shape of the free edge of the fingernail also affects the mark, as pointed nails are more likely than those with straight edges to give these paradoxical results. Once again, the pathologist has to be wary of incorrect interpretation when, for instance, deciding if nail marks on a neck were made by hands approaching from the front or passing around the back of the neck. However, personal experiments with the Shapiro *et al.* contention have shown that it by no means always applies.

Patterned abrasions

Formerly it was often claimed that abrasions retained the pattern of the impacting object more accurately than other injuries such as bruises and lacerations. Though abrasions undoubtedly do preserve such patterns well, many of the examples were not in fact true abrasions, but were intradermal bruises, mentioned in the next section.

Patterned injuries occur when the force is applied at or near a right angle to the skin surface, rather than with the skidding impact of a graze. If a weapon with a patterned surface strikes the skin – or the body falls against a patterned surface – the abrasion of the epidermis follows the ridges of the object if it has a profile of varying height. Not only may the epidermis be damaged, but also, the skin may be compressed into the cavities of the pattern, with consequent capillary damage leading to an intradermal bruise. Probably the best example of this is seen when a motor tyre passes over the skin, leaving a pattern where the skin has been squeezed into the grooves of the rubber tread.

There is little point in trying to list all the possible patterns that can be distinguished in abrasions on a body, but a few have particular medico-legal significance. In former years the honeycomb grid of a motor-vehicle radiator provided many examples of patterned abrasions, but changes in vehicle design have relegated these to historical interest. There may still be projections on vehicles that cause damage, but these are more likely to inflict bruises and lacerations. The muzzle of a firearm can imprint an abrasion on the skin, which is of importance in that it confirms that the discharge was contact in nature (see Fig. 8.30).[2] Impact against ribbed ceramic tiles in a bathroom or swimming bath may assist in reconstructing unwitnessed events (Fig. 4.11). Blows from a weapon with a recognizable surface may help to identify that weapon, such as a plaited rope or leather whip, or a solid object with an embossed pattern. Abrasions from objects with a recurring pattern, such as bicycle chain used in gang fights, or a serrated knife, can readily provide a clue to the nature of the weapon (Fig. 4.12).



Figure 4.11 Abrasions and intradermal bruising on the forehead of a swimming bath attendant. He was found drowned when there were no witnesses, but the spacing of the marks exactly matched the ridged tiles at the edge of the bath, so it was presumed that he had slipped and struck his head before falling unconscious into the water.



Figure 4.12 Patterned abrasions from the back edge of a serrated 'Rambo' knife. Measurements and photographs with a scale should always be obtained to assist in the identification of the weapon.

Post-mortem abrasions

Unlike post-mortem bruises, artefactual abrasions are common. They may have been inflicted after death from a variety of causes, including dragging a corpse or buffeting in moving water. Some post-mortem animal injuries also resemble abrasions such as insect bites, especially by ants.

Other damage may be caused following autopsy. As the post-mortem interval increases, so the skin becomes more fragile. Even the normal procedures of post-autopsy reconstruction and handling in the mortuary may cause dermal damage, especially after washing with hot water. If the pathologist returns for a later examination, or if he is retained to perform a second autopsy for the defence, the appearances should be checked with the original description or photographs, if some injuries suggest a post-mortem origin.

Contusions or bruises

Although often combined with abrasions or lacerations, a pure bruise lies beneath an intact epidermis and consists of an extravascular collection of blood that has leaked from blood vessels damaged by mechanical impact. An extravasation of blood that is (arbitrarily) larger than a few millimetres in diameter, is usually termed a ‘bruise’ or ‘contusion’. This size overlaps the older and now little used term ‘ecchymosis’, which is really a small bruise.

Even smaller is the ‘petechial haemorrhage’, which is the size of a pin head or less. Both ecchymoses and petechiae are not usually caused by direct mechanical trauma and are often seen on serous membranes and conjunctivae as well as on skin. However, moderate pressure, impact or, especially, suction on the skin can produce a patch of localized petechiae.

Bruises are caused by damage to veins, venules and small arteries. Capillary bleeding would be visible only under a microscope and even petechiae originate from a larger order of blood vessel than a capillary.

The word ‘bruise’ usually implies that the lesion is visible through the skin or present in the subcutaneous tissues, while a ‘contusion’ can be anywhere in the body, such as the spleen, mesentery or muscles. The two words are often interchanged at random, however, though ‘bruise’ is to be preferred when a doctor gives reports or evidence to a non-medical audience.

Intradermal bruises

These are important but rarely mentioned in most texts. The usual bruise from a blunt impact is situated in the subcutaneous tissues, often in the fat layer. When viewed through the overlying corium and epidermis, the bruise is somewhat blurred, especially at the edge. When a bruise is made by impact with a patterned object, however, the haemorrhage may be far more sharply defined, if it lies in the immediate subepidermal layer. The amount of blood is relatively small, but because of its superficial position and the translucency of the thin layer that overlies it, the pattern is distinct (Fig. 4.13).

Such bruises are especially likely to occur when the impacting object has alternating ridges and grooves, as the skin will be forced into the grooves and be



Figure 4.13 Patterned abrasion on forehead due to falling down steps onto a metal grid. Here the abrasions are not produced by tangential force, but imprinted directly by impact at a right angle to the skin.



Figure 4.14 Intradermal bruising showing the pattern of rubber soles of ‘trainer’ shoes on the neck and T-shirt of a homicide victim.



Figure 4.15 Multiple bruises on the trunk of a victim of child abuse. The bruises are of the 'finger-tip' type, caused by heavy prodding by adult fingers. The child died of a ruptured liver.



Figure 4.16 Bruising on the upper arm, typical of forceful gripping in a struggle. There are contusions from fingers on either side of the biceps, with small abrasions from fingernails.



Figure 4.17 Kicking and stamping injury to the face. The nose is bruised from a kick and the patterned rubber sole of the shoe has imprinted intradermal bruising on the forehead. It is essential to obtain accurate photographs and measurements of the shoe-tread pattern, to allow identification of the footwear.

sharply distorted. Intradermal bleeding will occur here and the areas in contact with the raised ridges may remain pale, as the pressure forces the blood from the small vessels. A good example is that of a motor tyre running across the surface. Impacts from whips with patterned thongs may also show the same phenomenon, as do the ribbed rubber soles of 'trainer' shoes (Figs 4.14, 4.17).

Factors affecting the prominence of a bruise

Several factors influence the apparent size and prominence of a bruise and, because of these, it is not possible to be dogmatic about the amount of force needed to produce any given bruise.

- As it is a leakage of blood from a vessel, there must be sufficient space outside that vessel for free blood to accumulate. This explains the ease with which bruising appears in lax tissues such as the eye socket or scrotum and its rarity in the sole of the foot or palm of the hand, where dense fibrous tissue and restrictive fascial planes prevent accumulation of blood. Because of the greater volume of soft subcutaneous tissue in fat people, they tend to bruise more easily than thin ones, other factors being equal (such as vessel fragility and senile changes).
- The apparent prominence of a bruise beneath the skin varies with the amount of blood in the extravasation. The size of the haemorrhage depends partly, but not entirely, on the intensity of the injuring force. The size and density of the vascular network varies from place to place and the amount

of damage that a given blow causes to local blood vessels is partly a matter of chance.

- Resilient areas, such as the abdominal wall and buttocks, bruise less with a given impact than a region where underlying bone acts as an anvil with the skin between the bone and the inflicting force. The head, chest and shins are examples (Figs 4.15, 4.23).
- The depth at which the bruise is placed affects the apparent severity. A bruise may be placed superficially in the dermis to form the well-patterned intradermal bruise mentioned in the previous section; here, a minute amount of blood will be obvious. Most bruises are in the subcutaneous tissues above the deep fascia and will therefore be fairly obvious, but others can be confined below deeper fascial membranes so that the free blood has to be viewed through the skin and underlying adipose tissue. For a given size of extravasation, this bruise will be less prominent. Some bruises are confined to deep fascial compartments and never become visible without dissection.
- For a given impact, the volume of blood lost into the tissues can depend upon the fragility of the blood vessels and the coagulability of the blood. In old persons, vessel fragility may be extreme and a large bruise may develop from the slightest of knocks. Any bleeding diathesis resulting from disease, a toxic condition, or certain medication, will also retard the normal clotting process that heals the breach in the bleeding vessels. Those with scurvy and chronic alcoholics bleed easily but, in contrast, certain people (such as boxers) seem able to avoid bruising from blows that would severely damage other people.
- It is common knowledge among lay people, as well as doctors, that a bruise may 'come out' – that is, become more prominent with the passage of hours or days. This is partly caused by continued bleeding from the ruptured vessels, but mainly by percolation of free blood from its origin deeper in the tissues upwards towards the epidermis. Another factor may be haemolysis, when the freed haemoglobin is able to stain the tissues in a more diffuse way and become more noticeable than intact red blood cells. This latter mechanism is certainly the reason not only for the well-known post-mortem phenomenon of bruises becoming more prominent after death, but of new bruises appearing later where none was visible at an autopsy performed soon after death. This is further considered in the chapter on post-mortem changes, but is repeated here because of the importance of recognizing the differences in appearance that can occur between two autopsy examinations spaced a few days apart. The second, usually for a defence opinion, may find new bruises not recorded by the first pathologist, but if the phenomenon of delayed appearance is appreciated, potential disputes may be avoided.

Movement of bruises

A bruise may appear at a different place on the surface from the point of impact. When the bruise is superficial, especially intradermal bruising, the lesion appears immediately – or at least rapidly – and is at the point of infliction. When blood extravasates in the deep tissues, however, it may take time to reach the surface (if it ever does), and this may be some distance away because of deflection and obstruction by fascial planes and other anatomical structures.

In addition, bruises may move under gravity. The most frequent example is a bruise or a bleed under a laceration on the upper forehead. If the victim survives for at least some hours, then the subcutaneous haemorrhage can slide downwards over the eyebrow ridge and appear in the orbit, to give a 'black eye', which might be misinterpreted as direct trauma. Similarly a bruise of the upper arm or thigh may surface lower down around the elbow or knee.

Alteration of bruises with time

As already mentioned, bruises often become more prominent some hours or days after infliction because red cells or haemoglobin diffuse closer to the translucent epidermis. There is another temporal series of changes in bruises in the living person, this being part of the healing process. Fresh extravasation of blood is obviously dark red, though when viewed through the skin this may be purple or almost black in appearance. In racially pigmented victims, a bruise may sometimes be undetectable from the surface, apart from swelling caused by a haematoma and tissue oedema.

With the passage of time, the haematoma breaks down under the influence of tissue enzymes and cellular infiltration. The red-cell envelopes rupture and the contained haemoglobin undergoes chemical degradation, which causes a sequence of colour changes. The haemoglobin is broken down into compounds including haemosiderin, biliverdin and bilirubin,



Figure 4.18 Extensive bruising of the face due to hitting, kicking and stamping 6 days earlier. The victim had multiple fractures of the facial bones, bilateral serial rib fractures and a tension pneumothorax.

which lead the colour changes through a spectrum of purple to bluish brown, to greenish brown to green to yellow, before complete fading.

A small skin bruise in a healthy young adult might be expected to pass through all these stages and vanish in about 1 week, but there is a tendency to overestimate the length of time needed as shown by Roberts (1983), who observed that 'love bite' bruises in sexual offences could become yellow and vanish within a couple of days.[3] Langlois and Gresham (1991) and Langlois (2007) reviewed the literature on this subject, indicating the wide variation in opinion.[4,5] They also made careful photographic records of the macroscopic appearance of bruising on 89 subjects, aged between 10 and 100 years. They concluded that the most significant change was the appearance of a yellow colour (in persons less than 65 years of age), which indicated that the bruise could not be less than 18 hours old. Blue, purple and red did not assist in dating bruises; brown was held to be a mixture of colours and was not considered as useful.

In the present authors' experience, it is impossible to comment on the age of a bruise less than 24 hours since infliction, except to say that it is 'fresh', as no visible changes occur in that time.[6–9]

It is not practicable to construct an accurate calendar of these colour changes, as was done in older textbooks, as there are too many variables for this to be reliable. These include:

- the size of the extravasation – changes begin at the margin and a larger bruise will take a longer time to be absorbed. A large old bruise may contain all the colours possible – from purple in the centre to yellow at the edges
- the age and constitution of the victim. Aged persons may not heal their bruises at all and carry them for the remainder of their lives
- a personal idiosyncrasy in the rapidity with which such changes occur in any one person, including coagulation defects.

Even histological examination is unreliable in the accurate dating of bruises, as is discussed later in this chapter. The appearance of stainable iron, in the form of haemosiderin, however, does not usually appear within the first 2 or 3 days, though Simpson suggests that it may be found as early as 24 hours. In meningeal haemorrhage, it seems to appear from around 36 hours.

Haematoidin, another breakdown product of blood pigment, can appear in old bruises and haematomas after the first week.

Though an absolute date cannot therefore be placed upon a bruise, the following observations are legitimate.

- If a bruise appears fresh over all its area, with no observable colour change, it is unlikely to have been inflicted more than about 2 days before death, except in old persons.
- Colours appearing as red, blue, purple, black or green cannot reliably guide to the age of a bruise.[4,5]
- If bright yellow discolouration is seen in a bruise, it is not recent, most probably more than 18 hours old, in most cases at least 24 h and closer to 48–72 h.[4,5]
- If several bruises (of roughly comparable size and site) are present and are of markedly different colours, then they could not have been inflicted at the same time. This is particularly important in suspected child abuse, where intermittent episodes of injury have important diagnostic significance.

One has to consider that there can also be individual variation in colour perception and for example, the sensitivity for yellow decreases with age.[10]

Bruising of special significance

Certain types of bruise and bruises at particular sites have a specific significance. Clusters of small discoid bruises of about 1 cm in diameter are characteristic of fingertip pressure from either gripping or prodding. These groups are often seen in child abuse, when an adult hand grips the infant by a convenient 'handle' (Fig. 4.16). Once called 'sixpenny bruises' from their size, the lesions are commonly seen on the forearms or upper arms of the child, or sometimes around the wrist or ankle, though they can occur on the abdomen. Similar bruises from fingertips may be seen on the neck of children or adults in manual strangulation, though there is often additional diffuse bruising caused by a sliding grip on the neck.

When the skin surface is struck by a rod or rectangular sectioned object such as a cane or lath, the consequent bruising may be of the 'tram-line' or 'railway line' type. This appears as two parallel lines of bruising with an undamaged zone in the centre. The mechanism of this double line is that the weapon sinks into the skin on impact so that the edges drag the skin downwards and the traction tears the marginal blood vessels. The centre compresses the skin, which, in the absence of underlying bone, causes little or no damage to the vessels (Figs 4.19, 4.20). When the momentary impact is released, blood flows back into the injured marginal zones and leaks into the tissues. Impact from broom handles, narrow planks and wood or metal rods can all cause this characteristic lesion.

As with abrasions, bites can result in bruises; this is dealt with in Chapter 26. It might be noted here that the so-called 'love bites' are often bruises, with or without associated abrasions, being a shower of small petechial lesions caused by oral suction on the skin (Fig. 4.21).

The common 'black eye' is dealt with under 'Head injuries' in Chapter 5, but again it is worth repeating that not all black eyes are true bruising from a blow in the orbit (Fig. 4.22). Some are from fractured orbital roofs and others are the result of gravitational movement of a forehead injury (see Fig. 5.9).



Figure 4.19 Formation of 'tram-line' bruising from the application of a rectangular or cylindrical object.



Figure 4.20 Bruises from a beating with a broom handle. They are approximately parallel and several, especially the lowermost, show a double 'tram-line' appearance typical of the impact of a round or square-section rod. The pressure in the centre compresses the vessels so that they do not bleed.



Figure 4.21 Suction marks in the left breast of a 22-year-old homicide victim, who was killed by manual and ligature strangulation.



Figure 4.22 A black eye (periorbital haematoma) of a live victim from a direct fist blow, which has also bruised the bridge of the nose and lacerated the corner of the eye (sutured).

A bruise below the ear in a death from subarachnoid haemorrhage needs careful examination of the upper cervical spine and basilovertebral arteries, again as discussed under 'Head injuries' in Chapter 5.

Post-mortem bruising and other artefacts

It is possible to cause what appears to be a bruise by deliberate violence to a dead body, but the amount of force required is great. As there is no internal pressure in the small vessels that have to be ruptured, bleeding is a passive ooze rather than an active extravasation, so the size of the haemorrhage is slight in relation to the amount of effort expended. Thus, post-mortem skin bruising is of little practical significance to the pathologist – in most instances he can be reassured that new or more obvious bruising apparent when he returns several days later for a second examination of a body is genuine. Post-mortem abrasions are common, especially after a first autopsy and additional handling of the body in the mortuary, but these procedures rarely produce artefactual bruises.

More important than dermal artefacts are spurious bruises inside the body. Especially in congestive deaths, such as pressure on the neck, the venous system may be engorged at death and a number of artefactual haemorrhages may occur. One particularly important area described fully elsewhere is the neck, in which collections of blood between the oesophagus and cervical spine may simulate bruising from manual strangulation. These were fully investigated by Prinsloo and Gordon (1951) and, where neck trauma is suspected, it is advisable to remove the brain before dissecting the neck region to allow drainage of the engorged venous plexuses that give rise to the artefact.[15] This phenomenon appears to be related to the post-mortem interval and is more likely to arise if there is a delay in autopsy.

Kicking

The shod foot may leave a patterned bruise on the body, most often on the abdomen or chest, though it may be recognizable on the neck or face. A glancing kick is more likely to cause scuffed abrasions and bruising, and a kick from a toecap, a curved abrasion or even laceration. A vertical stamping action may imprint an intradermal bruise corresponding to the sole pattern, especially in these days of rubber 'trainer' shoes (Figs 4.14, 4.17). As with a motor tyre, the skin can be forced into the slots in the sole, creating an accurate pattern of superficial bruising. There may also be more diffuse deep bruising if the impact is severe, but this is less useful in delineating an identifiable sole pattern.

Kicking has become increasingly common with the increase in violence and vicious hooliganism in society. The heavy footwear fashionable among some of the least responsible citizens adds to the severity of the lesions.

Though most kicking injuries end up in hospital casualty departments, an increasing number reach the pathologist. Not all victims are drunken youths, as many assaults upon old people by intruders and muggers involve severe kicking.

Obviously, most kicks are delivered with the victim already lying or sitting on the ground, having been brought there by some other means of violence, including pushing, tripping and fist punches. Once prostrate, the 'boot is put in' towards the most convenient targets, which tend to be the concavities of the body. The loin, the groin, the neck and the face are often attacked, and – when the victim assumes a 'fetal position' on his side for protection – swings may be taken into the abdominal area. As an alternative to swinging kicks, the foot may be brought vertically down on the prone victim, the heel being the most damaging part, rather than the toecap. A grinding motion can also be added, which may tear the skin and cause ragged lacerations.

Yet another variant is standing on the body or actually jumping onto it with one or both feet. The chest is the most common target for this practice and fractured ribs or sternum, a flail chest and cardiac injuries can result.

The major characteristic of most kicking injuries is the severity of bruising and underlying damage. Even if the toecap does not cause lacerations, there may be large haematomata and intramuscular contusions from heavy kicks. Abdominal and thoracic viscera can be ruptured and the genitalia are also vulnerable, especially the scrotum and sometimes urethra.

A common danger with kicking to the face is fracture of either (or both) mandible and maxilla, nasal bones and zygoma, though the cranial vault is seldom fractured and kicks to the vertex of the head seem less common (Fig. 4.18). With such facial injuries, death may occur from filling of the pharynx and air passages with blood. A kick on one side of the face can completely detach the lower maxilla – with the upper dental arch and palate – from the rest of the maxilla. A unilateral kick of the jaw can fracture both rami of the mandible, there being no necessity for kicks on either side.[11–14]



Figure 4.23 Bruising of the interior of the lip from a blow to the mouth. The lip has been impacted on the underlying teeth, but not sufficiently hard to cause a laceration.

Lacerations

The third major type of blunt injury is the laceration, in which the full thickness of the skin is penetrated (Figs 4.24, 4.26, 4.27).

Lacerations differ from incised wounds in that the continuity of the tissues is disrupted by tearing rather than clean slicing, but the distinction is often blurred because some lacerations are caused by jagged projections ripping into the skin in much the same manner as a blunt knife or axe.

Unless great force is used, most lacerations require a firm base to act as an anvil for the skin and underlying tissue to be pinned against. It is unusual for a blunt impact to lacerate the abdomen or buttock, but the scalp, shins, shoulder, face and – to a lesser extent – the thorax, are all prone to lacerated injury. Where a soft area such as buttock, thigh, calf or forearm is lacerated, the lacerating agent is either a projecting point or edge, or a completely blunt object is pulled obliquely against the tension of the skin until it tears. Because of the crushing and tearing components of a laceration, there is usually associated abrasion and bruising, though these may be minimal if the lacerating force acts at right angles to the surface.

The scalp offers the best example of a laceration, as the skin and subcutaneous tissue lie over the bony platform of the skull and are crushed against it when the force impacts. In fact, scalp lacerations can resemble incised wounds, because this ‘sandwich effect’ is so pronounced that a blow from a blunt instrument can cleanly split the tissues against the skull, leaving a linear wound that appears to the inexperienced to be a knife or chopper cut.



Figure 4.24 Lacerated upper lip from a fist blow to the mouth.

A laceration can be distinguished from an incised wound by:

- the bruising and crushing of the margins, though this may be a very narrow zone, requiring inspection through a lens
- the persistence of tissue strands across the interior of the wound, including fascial bands, vessels and nerves. In a wound from a sharp weapon these are divided
- the absence of a sharply linear injury in the underlying bone, especially if it is the skull. A knife or axe is likely to chip or score the base of the wound
- if the area is covered with hair, as on the scalp, intact hairs will survive to cross the wound; an incised injury would divide them.

A flat impact may cause a laceration, especially on the scalp. If the head falls to the ground or is hit by a wide, flat weapon, the skin and subcutaneous tissues are compressed on the anvil of the skull and may split sideways, often with a zone of surrounding bruising (Fig. 4.25).



Figure 4.25 Laceration of the forehead with surrounding bruising. The wound is stellate as a result of crushing against the underlying bone. The victim fell down stairs and sustained a fracture of CVII and died of a spinal cord injury.



Figure 4.26 Simple laceration of the eyebrow. A chronic alcoholic who hit his head when falling at home. Death due to acute pancreatitis.

Other lacerations are caused by the impact of an edged object, be this a rod, a brick, the edge of a kerbstone or the wing mirror of a vehicle (Figs 4.28–4.33). Though the impact may be virtually perpendicular to the skin surface, there is usually some tangential element and this can cause one edge of the wound to differ from the other. Where there is a glancing element, one edge will be relatively clean-cut, whereas the other will be ripped away from the first, suffering more tearing of the margin and often showing undercutting of the edge. If the impact is significantly asymmetrical, then this undercutting may be pronounced enough to form a flap of skin and underlying tissue, which is peeled off the underlying bone or deep fascia.

In extreme forms, this produces a ‘flaying injury’, where a large area of skin and subcutaneous tissue is



Figure 4.27 Multiple homicidal lacerations of the forehead. The perpetrator finalized his act by squeezing toothpaste on the left eye.



Figure 4.28 A laceration of the scalp from a blunt weapon, a metal bar. The edges are crushed and abraded, with tissue elements and hair driven into wound.



Figure 4.29 Laceration of the scalp from a 30 cm long heavy torch (insert). The skin over the shoulders is reddish due to 1° and 2° burns. The victim was hit on the head while sleeping in bed, after which the husband poured petrol over the body and set it on fire.



Figure 4.30 Homicidal lacerations of the scalp penetrating the skull. Although some of the injuries resemble incised wounds, their margins are crushed, and hairs and tissue strands cross the injuries. The damage was probably inflicted with a metal rod with sharp edges.



Figure 4.31 Crushing impact of a blunt object on skin supported by bone, such as scalp on skull. The skin is sandwiched between weapon and bone and this causes a lacerated split that has bruised margins and bridges of hair and tissue in the wound.



Figure 4.32 A healing shallow laceration of the forehead, about 1 week after infliction. The base of the injury has filled with granulation tissue and the surrounding skin shows puckering due to contraction of the central scab.

rolled off a limb, almost always by the rotary action of a revolving motor wheel. A similar injury can occur on the scalp again from a rotating wheel – though a similar 'scalping' lesion can be caused by traction from hair being trapped in machinery. This was formerly



Figure 4.33 Transection of a body into two halves at waist level. The victim jumped from a high-rise building and landed on a fence.

a common industrial accident and was the reason for the ‘snood’ hairnet being worn by women factory workers during the Second World War.

Patterned lacerations

Lacerations do not reproduce the shape of the injuring agent nearly as well as do abrasions and intradermal bruises. As with skull fractures, the magnitude of the force needed to cause a blunt tearing of skin leads to blurring of the impact shape, often with radiating or totally irregular tearing. Sometimes the shape is recognizable and probably the best example is a hammer blow to the head. A circular face may punch out a circle or an arc of a circle, which may also be reproduced in an underlying depressed skull fracture. The exact size of the hammer face may not be accurately reproduced in the laceration, which may be slightly larger than the hammer.

Kicks may cause lacerations, especially if a heavy boot with a hard toecap is used. These tend to be tangential and may peel up a flange of tissue. They can be clean-cut and are sometimes mistaken for knife wounds. Stamping injuries are more likely to cause abrasions and bruises than lacerations, unless the violence is extreme. A heavy focal blow may cause a linear or a stellate laceration, the latter radiating out from the focus of impact. The surface may be abraded and the surrounding tissue deeply bruised, so the final lesion is complex.

Firearm wounds are a special form of laceration and will be dealt with separately.

Blunt penetrating injuries

These ‘puncture wounds’ are a hybrid between lacerations and incised wounds, and have more of the features of the latter. Such injuries can occur from metal spikes, wooden stakes, garden or farm forks, and a variety of vehicular and industrial accidents. They are occasionally seen in homicides or suicides when weapons like screwdrivers are used as daggers. The interpretation of such skin wounds can be difficult, as in the ‘Yorkshire Ripper’ cases, when some small stellate stab wounds were thought to have been caused by a Phillips-type screwdriver.[16] A number of fatal wounds, some of them homicidal, have been caused by chisels, usually very sharp woodworking tools with one face of the edge ground to a straight line. The edges of the chisel are squared off and the resulting skin defect may be rectangular.

When a blunt spike is driven through the skin, there will be inversion and abrasion of the edges, though the former may vanish if the weapon has been withdrawn. Foreign material such as rust, dirt or splinters may be left in the wound, and must be carefully preserved for forensic examination if the weapon has not been recovered.

Incised wounds

Injuries caused by sharp objects are classified as ‘incised’ wounds, though the nomenclature is again somewhat confused. Some authors make these a subcategory of lacerations and, when the weapon is relatively blunt (as in some axe or spike injuries), there may be sufficient crushing and bruising of the wound margins to make differentiation between incised and lacerated wounds difficult.

The term ‘incised wound’ usually covers all types of injury from, for example, a knife, sword, razor, glass or sharp axe – though some writers would make stab wounds a separate category, reserving incised wounds for injuries that are longer than they are deep. These semantic variations are not important in themselves, but can lead to confusion in medical and autopsy reports, as well as in oral testimony if the doctor fails to clarify his meaning. The essential feature of all incised wounds is the clean division of the skin and underlying tissues so that the margins are almost free from any damage. Microscopically there is always a narrow zone of injury, but this is minimal compared with the tissue destruction caused by blunt injury. Healing is affected, as well as the extent of subsequent scarring.

Cuts or slashes

When an incised wound is longer than it is deep, it may be referred to as a 'cut' or 'slash', though a 'cut' may also be used by lay persons to describe a laceration. Such slashes when inflicted by knife, sword, razor, cleaver, parang, machete, panga, broken glass or bottle, are typical of a fight, when the assailant strikes out with a swiping action, rather than the thrust of a stabbing attack. They are common in gang fights and bar-room brawls and the weapon may be swung at arm's length in a horizontal arc so that if it contacts a body it will slice the skin and tissues as it passes by. They are also seen in suicidal injuries, usually on the wrist or throat. The characteristics of any given wound are a matter of a chance and relative positions. The slash may be deeper at the entry end or the exit point, though it seems true that many such injuries tend to dig in near the point of first contact and become progressively more shallow as the wound approaches the distal end. There may be a superficial 'tail', a shallow scratch, running out of the termination of the slash, as the weapon rises out of the wound and is drawn across the skin surface before leaving the body altogether (Figs 4.34, 4.43).

There is a tendency among advocates to visualize a fight as a static confrontation and to attempt to reconstruct events as if the two participants were standing still, the assailant merely moving his arm. This is an unrealistic interpretation, as all fights are dynamic, with constant relative movement of the bodies and limbs of both parties. Therefore any relative angles and depths of contact between the victim and the weapon can occur and overinterpretation and simplification should be avoided.

Slashed wounds are less dangerous than stabs, as the relative shallowness of the wounds is less likely to affect vital organs – especially as the arms and face are the common targets. The rib cage and skull protects the chest organs and brain and the more vulnerable abdomen is seldom the target for a swung knife. Wounds of the neck are the most dangerous and are discussed below. Bleeding is the most serious complication of any slashed wound, though it will be external and more amenable to immediate treatment than the hidden internal bleeding of a stab wound.

A particular form of slashed wound arises from 'glassing', that is, the use of a broken drinking glass or bottle as a weapon. The glass may sometimes be broken prior to the attack, to produce edges that are exquisitely sharp. There may also be spikes of glass, which can inflict deep, almost stab wounds. Where, more commonly, a glass or bottle is used as a blunt instrument, it may shatter on impact with a victim's head, and the resulting injuries may both be blunt and incised.



Figure 4.34 Homicidal slashed wounds caused by knife; the length is greater than the depth, unlike stab wounds. The long tails are due to the knife rising from the skin, thus indicating the direction of the slash.



Figure 4.35 A knife slash of the back showing regular scratches along the margin. This was inflicted with a 'Rambo' knife, which has deep serrations along the back edge that have somehow marked the skin on withdrawal.

Stab wounds and penetrating injuries

These are of major importance in forensic pathology, as they are extremely common in homicide. In Britain, stabbing with a knife is easily the most frequent mode of murder and manslaughter, primarily in domestic disputes and street violence. A stab wound is an incised wound that is deeper than it is wide. Though many penetrate only the skin and subcutaneous tissues, those seen by forensic pathologists are most often fatal, having entered vital deep structures. Several aspects of this important topic need discussion.

The nature of stabbing weapons

Knives are the weapons most frequently involved and their physical characteristics are important in shaping the wound. A pathologist called upon to examine a knife that may have been used in an assault should note and measure:

- the length, width and thickness of the blade
- whether it is single or double-edged
- the degree of taper from tip to hilt
- the nature of the back edge in a single-edged knife (for example, serrated or squared-off)
- the face of the hilt guard adjacent to the blade
- any grooving, serration or forking of the blade
- most importantly, the sharpness of the edge and especially of the extreme tip of the blade.

Other knife-like weapons include scissors, chisels, swords, open razors and sharp tools of many kinds, including deliberately modified tools such as sharpened screwdrivers. Larger cutting instruments such as axes, choppers, parangs, machetes and pangas and agricultural implements such as shears, bill-hooks, hay-knives and many others have been used as stabbing weapons when used by the point rather the long edge.

Spiked instruments come in many forms, from icepicks to hay-forks, from case-openers to fire-irons. The appearances of their wounds vary with the physical nature of the implement. Some weapons are exquisitely sharp and the wounds made by them exhibit extremely fine division of the tissues. To razors and razorblades may be added surgical and craft knives, often with a disposable blade, together with carpet and general utility and hobby tools, such as the ‘Stanley’ knife. Equally sharp is broken glass and sometimes porcelain. Both sheet glass and smashed glass utensils can provide edges that equal or exceed surgical scalpels in their cutting ability.

A common weapon in a bar-room fight is a smashed beer tankard, which when held by the intact handle provides a formidable weapon for both slashing and stabbing. Smashed china, such as cups and mugs, can also provide sharp cutting edges. The external glaze can project, if the fracture line is oblique, producing a glass-like edge. From personal experiment, the author (BK) has shown that broken china can easily slice through the full thickness of skin and thus validate a defence that injuries were the result of falling on a broken mug.

The characteristics of a stab wound

The surface and internal appearances of a stab wound allow the pathologist to offer an opinion upon:

- the dimensions of the weapon
- the type of weapon
- the taper of the blade
- movement of the knife in the wound
- the depth of the thrust
- the direction of the thrust
- the amount of force used.

Dimensions of the weapon

The dimensions of the knife may be a vital part of the investigation of a homicide when the weapon has been removed from the scene by the assailant. The pathologist can sometimes assist the investigators by telling them, within limits, what size and type of knife to seek. When suspect weapons are recovered, his inspection of them may indicate whether or not they are consistent with having caused the wounds in question. As always in forensic medicine, however, caution must be employed and the cardinal sin of overinterpretation avoided.

The length of the wound should be measured to the nearest millimetre as it lies undisturbed on the skin. In most instances the wound will have gaped across the centre, to form a long ellipse. The extent of gaping will depend on the anatomical situation, for example, over joints or in the axilla or groin, and whether the axis of the stab is in line with or across the tension of Langer’s lines or underlying muscle bundles.[17–21]

When the edges are gently opposed, the length of the wound may then extend slightly and should be measured again in this position, which more accurately approximates to the length when the blade was *in situ*.

An important additional factor, however, must always be taken into account because, when the knife is withdrawn the elasticity of the skin causes it to retract, making the wound smaller than when the blade was *in situ*. This mechanism may be amplified by contraction of the underlying muscles, which, if at right angles to the axis of the wound, may cause the wound to shorten from end to end, while gaping more widely at the centre. Using wound measurements to predict the size of the knife blade, one must take into account the other matters discussed below, such as movement of the blade in the wound, the taper of the blade and the depth of penetration (Figs 4.36–4.40, 4.42).

Type of weapon

The type of blade usually refers to whether it had a single or double cutting edge. Most knifes have a single sharp edge, the back edge being blunt or otherwise machined. A few dagger-like weapons have both edges ground to sharpness, some have only the distal part of the back of the blade sharpened. On inspecting the skin wound, the pathologist frequently finds that both ends of the defect appear sharply cut, coming to a fine 'V-point' at the extremities. Unfortunately, this does not



Figure 4.36 A stab wound and the inflicting knife. The wound is slightly shorter than the width of the blade at the depth of penetration because of sideways gaping and the contractile elasticity of the skin.



Figure 4.37 Two knife wounds in the back. The wounds have a sharper lower edge compared to a rounder upper edge, due to a one-edged blade.



Figure 4.38 A stab wound gapes across its width and shortens in length, especially when across skin or muscle planes.



Figure 4.39 Multiple stabs on the back from the same knife, showing differing shapes and sizes.



Figure 4.40 Multiple stabs in the lungs from the same knife with fresh wound haemorrhage and varying wound size according to the angle and depth of the stabs. The lungs appear anaemic due to the massive loss of blood.

necessarily indicate that a knife with two sharp edges was used, as the skin often splits behind the blunt edge to produce a symmetrical appearance (Figs 4.46, 4.49).

If, however, there is an obvious difference between one sharply pointed end and a rounded or even square-cut opposite extremity, then it can be said with some confidence that a single-edged knife was employed.

A knife with a thick blade that is squared off to a flat surface on the edge opposite the cutting edge, may sometimes be identified from the wound, where a definite double right-angled end to the skin defect is apparent. The skin may split back slightly from each of these corners, forming the so-called 'fish-tail' appearance (Fig. 4.41).

Where a knife with a serrated back edge has been used, such as is found on some boy scout or other Bowie-type knives (or the recently fashionable 'Rambo' weapons), the back edge of the wound may be torn or ragged and – on some occasions where the knife has entered very obliquely – serrated abrasions may be seen on the skin adjacent to the end of the wound (Fig. 4.35).



Figure 4.41 A stab wound showing a minute bilateral 'fish-tail' split caused by the blunt back edge of the knife blade. The other end of the wound is pointed due to the cutting edge of the blade.



Figure 4.42 Multiple stab wounds from the same knife, showing variations in the size and shape of the injuries. With multiple injuries, it is advisable to number each to facilitate easy reference in the autopsy report and when giving evidence in court.



Figure 4.43 A slashed facial wound from a knife, showing undercutting or 'shelving' on the edge nearest the mouth, indicating the angle of the knife relative to the surface. The tailed nature of the lower end also indicates that that knife was drawn downwards across the face.

If the knife has been plunged into the full extent of the blade, then there may be a hilt bruise or abrasion on the skin surrounding the wound. This may even reproduce the pattern of the guard at the base of the hilt, if there is one. Careful photography, sketches and measurements are needed to capture the exact outline of such a mark, which are, admittedly, unusual.

Taper of the blade

The taper of the blade is naturally related to wound size. If a tapered blade is inserted to 4 cm, then the length of the wound (ignoring skin retraction for the moment) will be that of the width of the blade at that level. If the taper continues to the 8 cm level, then the wound will be correspondingly longer. Only when the blade edges become parallel will the wound size remain constant for further penetration of the knife.

Movement of the knife in the wound

Movement of the knife in the wound can result in loss of evidence as to the size of the blade, but can also add other information. Where a knife is stabbed directly into the body and withdrawn along the same track then, within the limits discussed above, the size of the wound will indicate the minimum width of the blade at the maximum depth of penetration.

If, however, the knife is 'rocked' in the wound, the skin defect will be enlarged, sometimes considerably. The term 'rocking' means a leverage or angulation in the plane of the wound, so that the cutting edge extends the incision. This rocking can occur either by the knife being actively moved in the wound by the assailant – or by the body moving relative to the knife – or by a combination of the two (Figs 4.47, 4.48, 4.50).

It is sometimes a misapprehension among both doctors and (especially) lawyers that stabbings and other assaults occur in static circumstances, with the victim standing in the anatomical position. Directions of wounds are all too often interpreted as if the only movement came from the hand of the assailant, whereas in most fatal assaults the victim bends, turns and twists, and the assailant often follows with similar gyrations. Thus a knife that is thrust into the body may itself move or the body may move against it before it is withdrawn.

This relative movement may extend the wound in a linear fashion, as described above or there may be twisting of the blade in the wound. In the latter case, the resulting skin incision may be V-shaped or totally irregular. Rarely, a single stab may produce multiple skin wounds, such as a tangential stab of the arm, which passes through the superficial tissues and then re-enters the chest wall. Another instance is a stab through a female breast where, especially if the breast is sagging, the knife can pass right through the edge before re-entering the thorax (Fig. 4.44).

Depth of the thrust

The depth of a stab wound may be important in attempting to assess the length of a missing weapon. Again there are pitfalls to be avoided. First, if a knife is driven in up to the hilt, the depth of the wound as measured at autopsy may be greater than the true length of the blade. This is common in the abdomen and to a lesser extent in the chest, because the impact of a forceful stab may momentarily indent the abdominal or chest wall so that the tip of the knife penetrates tissues that apparently should have been out of reach (Fig. 4.45). This is particularly so when the hilt guard



Figure 4.44 Three wounds from a single stab with a knife, which was in place when the body was discovered. The knife had entered obliquely through the inner side of the right breast, emerged into the cleavage and re-entered the mid-line. If the knife had not been *in situ*, interpretation could have been more difficult.



Figure 4.45 Forcible stabbing can indent the body surface so that deep structures can be injured that appear to be beyond the reach of the knife.



Figure 4.46 Multiple stab wounds from the same knife. Although those at the bottom left are obviously square-ended, the more central ones are almost equally sharp at the extremities – illustrating the dangers of being too dogmatic about describing a missing knife to the investigators.



Figure 4.47 Homicidal stab wounds misdiagnosed by an attending doctor as 'haematemesis or epistaxis'. The lower right wound clearly shows evidence of a single-edged blade. The wound in the left axilla is V-shaped because of the twisting knife.



Figure 4.48 Multiple homicidal knife wounds, all inflicted with the same weapon. This shows the marked variation in wound size from the same knife, caused by rocking and twisting movements of either weapon or victim.

of the weapon impinges on the skin. For example, the author (BK) has seen the tip of a broken knife embedded in a thoracic spine, where the distance from that tip to the anterior skin wound was less than the length of the blade when recovered.

As with direction, discussed below, the pathologist must also allow for differences in the position of internal organs as measured at autopsy in a supine body, compared with their position in the living body, often in the upright posture. Such variations in the *in vivo* distance from the skin wound to the organs penetrated must be taken into account when assessing the depth of a wound. In the chest and abdomen, visceral relationships vary with the stage of respiration. The lower ribs move upwards and laterally, and increase the distance between the skin and deeper structures.

Direction of the thrust

The direction of a stab wound is often a matter of contention in homicides, especially as trial lawyers (and their medical advisers) sometimes tend to overinterpret the facts when trying to reconstruct the scene of the fatal assault.

As mentioned above, a stabbing incident is often moving and dynamic, and the victim is rarely in a static, anatomical position. For example, a wound that enters the upper part of the left side of the chest and travels steeply downwards, is not inevitably the result of the killer being taller or situated above the victim, using a downward blow. The victim could equally well have been bending or crouching, the knife then entering on a horizontal plane relative to the floor. All that the pathologist can do is to determine the direction of the wound relative to the axis of the body – it is then a matter of non-medical evidence to relate that to the posture of the victim when struck.



Figure 4.49 A stab wound of the centre of the chest. Although each end of the wound is identical, the weapon was a single-edged kitchen knife. The end of the wound adjacent to the back of the blade has split making it impossible to say if a single- or double-edged knife was used. The sternum beneath was penetrated to reach the heart, so considerable force must have been used.

Determination of the direction relies on both the appearance of the skin wound and the track in the deep tissues. Where a knife penetrates the skin with the plane of the blade at appreciably less than a right angle to the surface, the wound is often 'undercut', being shelved so that subcutaneous tissue is visible below one edge of the wound. Where the knife is plunged in obliquely, but the



Figure 4.50 Homicidal stab wounds of the neck and head showing the pleomorphism of injuries caused by the same knife. The wound behind the ear is V-shaped caused by twisting of the weapon.



Figure 4.51 Homicidal stab wound to the left groin (arrows).



Figure 4.52 The stab shown in 4.51 has split a branch (probe) of the femoral vein (V). Femoral artery (A). Death due to exsanguination.

plane of the blade remains perpendicular to the surface, no such shelving can be seen at the sides of the wound though it may just be visible at the end of the wound.

More information about direction comes from careful examination of the track of the stab wound (Figs 4.51, 4.52, 4.58–4.60). This is an anatomical exercise during autopsy, the layers of tissue being examined in sequence from the surface downwards and damage to deep structures and organs compared with the position of the surface wound. For example, a stab wound of the chest may lie below the left nipple. Dissection of the subcutaneous tissues and muscles may reveal that the defect in the chest wall lies in the sixth intercostal space and that, inside the thorax, the right ventricle of the heart has been transfixed, and that there is a wound in the diaphragm that terminates in the liver just to the right of the midline. This information obviously indicates that the direction of the wound was downwards and from left to right. Similar deductions can be made for all other sites, but caution must be exercised, as mentioned earlier, in allowing for the change in position of organs in the supine post-mortem posture compared with the erect, living state. A thorough knowledge of surface anatomy is required, especially of the thorax, as well as diagrams of the position of internal organs mapped out in relation to surface markers; samples of such diagrams are given in this book.

Attempts have been made to delineate the track of a stab wound before dissection either by filling the defect with a radio-opaque fluid before taking X-rays, or by filling with a plastic or even metallic substance that will harden to form a cast. In practice, these methods appear to have little advantage over careful dissection. When radio-opaque liquids or pastes are used, there is often leakage from the stab wound into the thoracic or abdominal cavities, leading to a confusing radiological picture. Recently, magnetic resonance imaging (MRI) has been used to visualize the wound track, but such facilities are rarely available for dead victims.

Estimation of the degree of force used in stabbing

The amount of force required to inflict any given stab wound is often a matter of extensive debate in criminal trials. The prosecution naturally gains from showing that a stabbing was inflicted with ‘considerable force’, sometimes even using pejorative terms such as ‘violent’ or ‘frenzied’. This tends to confirm the intention to stab, whereas the defence proposition is often that the victim inadvertently fell or was pressed against a weapon held passively by the accused. An expert medical witness has difficulty in replying to the almost inevitable question by counsel: 'What amount of force was necessary to cause this wound, doctor?'

Assessment of force is subjective and cannot be quantified in any satisfactory way that is meaningful to the court. Physical units such as dynes/cm^2, even if they can be measured, mean nothing to a judge and jury. The only measure that the medical witness can offer is a broad grading, based on common sense knowledge, such as 'slight pressure', 'moderate force', 'considerable force' and perhaps 'extreme force', the latter being reserved for exceptional cases where the knife has impacted in dense bone, penetrated the skull, or left a marked bruised impression of the hilt guard on the skin. A number of investigators, including the author (BK), have carried out measurements on the force needed to inflict stab wounds, both in animal, cadaver and surrogate tissues. The usual method is to attach some type of dynamometer or transducer to a knife, which records the maximum force applied during penetration, preferably with the duration of impact.

From this work, the following useful generalizations can be made.

- Apart from bone or calcified cartilage, the tissue most resistant to knife penetration is the skin (Knight 1975), followed by muscle where large muscle bundles underlay the fascia.[22]
- The sharpness of the extreme tip of the knife is the most important factor in skin penetration. The cutting edge of the knife, once the tip has penetrated, is of relatively minor importance.
- The speed of approach of the knife is particularly important in achieving penetration. A knife held against the skin, then steadily pushed, requires far more force to penetrate than the same knife launched against the skin like a dart. As in blunt injury, this is an example of the physical law that requires that the force varies directly not with the mass of the weapon, but also with the square of the velocity.
- Stretched skin is easier to penetrate than lax skin. The chest wall, where skin tends to be intermittently supported by underlying ribs, is relatively easy to puncture with a sharp knife as the skin and tissues are stretched over intercostal spaces in the manner of a drum membrane.
- Though the thick skin of the palms and soles is much tougher than on the rest of the body, the variation in resistance of the rest of the skin to a sharp knife is of little importance compared with other factors. Similarly, the skin of the aged, or of females, is not appreciably less resistant to a sharp point than that of males or young persons.
- When a knife-point impacts against skin, the latter dimples and resists until penetration suddenly occurs. The tension developed in the stretched skin appears to act as an 'elastic reservoir' and, when the threshold of resistance is exceeded, the knife 'falls' through the subcutaneous tissues without any further force being imparted to it unless impeded by bone or cartilage. Thus no additional effort is needed by the assailant to achieve deep or even full penetration up to the hilt. It is sometimes incorrectly claimed by the prosecution that a deep stab wound must imply extreme force or continued pushing after penetration. This is not so and experiments have shown that once penetration occurs, it is difficult or even impossible to prevent deep penetration because of the suddenness of the breakthrough.
- When the knife penetrates the skin rapidly, for example, if the body falls or runs on to the blade, the knife does not need to be held rigidly in order to prevent it being pushed backwards. Its inertia, if the tip is sharp, is quite sufficient to hold it in place while the body spears itself on the blade. It has been wrongly argued against a defence of falling or running onto a knife, that the hilt would have had to have been supported against, for example, the hip of the person holding the knife to immobilize it against the advancing body. Experiments have shown that this theory is invalid.
- Uncalcified cartilage, especially that in the costal cartilages of young and middle-aged persons, is easily penetrated by a sharp knife, though naturally more force is required than if the blade passed through an intercostal space. Calcified rib and bone provide a much more resistant barrier, but a forceful stab from a strong, sharp knife can easily penetrate rib, sternum or skull. Firm tissues like myocardium, liver and kidney are easily traversed by all but the most blunt of weapons, and their resistance is far less than that of cartilage or skin.

Hainsworth *et al.* (2008) studied a range of kitchen knives using a drop test to examine how the different aspects of knife geometry influences sharpness. The results showed that the radius of the blunt edge at the tip is important for controlling the penetration ability of a kitchen knife.[23] Their simulated stabbing tests using pigskin and knives with a blunted tip reinforced Knight's observation that the tip is important in penetrating flesh.[22]

Injuries by weapons other than knives

The general features of injuries from knives apply equally to other sharp objects that cause incised and stab wounds. Parmar *et al.* (2012) studied the forces required for penetration of various types of screwdrivers. They found out that there was a direct correlation between the cross-sectional area of screwdriver head and amount of force required for penetration.[24] Razors and broken glass have extremely sharp edges so that, when applied tangentially or at a small angle to the skin, undercutting may be a marked feature. The wound may appear as a shallow slice, which bleeds profusely and, in a hairy area such as the scalp, it will reveal cut hair bulbs on the shelved surface. Deliberate wounds with razors or sharp knives may exhibit patterns or even words; these may occur in gang fights or sadistic homicides (Figs 4.53, 4.55).

Glass can be employed as a cutting weapon, again typically in bar fights or gang vendettas, where a broken bottle may be held by the neck or a smashed beer tankard by the handle. Official estimates in Britain suggest that between 3400 and 5400 offences occur annually in which glass is used as a weapon. Surveys in London and Bristol by Shepherd *et al.* (1990a) and Hocking (1989) showed that bar drinking glasses were the most common weapons, and that 75 per cent of these were from straight-sided pint glasses.[25,26] Unexpectedly, this research showed that most of the glasses were intact until thrown or thrust at the victim – they had not been smashed prior to the assaults. Most of these non-fatal injuries were to the face. The fragility of these glasses varies greatly from manufacturer to manufacturer, so that there can be a sixfold difference in their propensity to smash on impact (Fig. 4.54).



Figure 4.53 Multiple homicidal stab and incised wounds inflicted with various kitchen utensils.



Figure 4.54 A wound over the eyebrow caused by impact from a broken drinking glass. Although this situation is commonly the site of laceration from blunt blows, this injury is sharp-edged and has unbruised margins, indicating that it is an incised wound. There is an associated abrasion from non-cutting contact and there is bleeding into the upper eyelid, probably from gravitational seepage from the wound.



Figure 4.55 Incised wounds, which in spite of their large size are typical of those inflicted by a sharp-edged weapon rather than a crushing laceration. The instrument was a chopper.

Though these formidable weapons are usually used for slashing, long slivers of glass can act – sometimes inadvertently – as stabbing agents. The sliver may break off and remain in a deep wound, which may be overlooked if the entry is small.

As many casualty surgeons have learned to their cost – or to the cost of their medical protection society or medical insurers – glass is almost invariably radio-opaque, even though this is either unknown or even denied by the doctor. Numerous civil actions for negligence have occurred – though usually in non-fatal circumstances – but, on occasion, the first person to find a deep fragment of glass in a vital position has been a forensic pathologist.

As mentioned earlier, broken china and porcelain, as from a smashed cup, mug or plate, may have a sharp edge on the exposed glaze and can easily cause a slashed wound.

Injuries from scissors

Stabbing by a pair of scissors is not uncommon and is seen most often in domestic circumstances where a female uses a weapon upon her partner, which is both familiar and near to hand. The appearances of the wound will differ according to whether the scissors were used open or closed. If open and one blade is stabbed into the victim, then the appearances will be virtually indistinguishable from a knife wound. Some modern scissors, however, have a two-part blade in which a steel cutting edge is riveted to a carrier continuous with the handles. This may produce a stepped wound that may show a notch or variation in linearity in the margin of the stab wound (Figs 4.56, 4.57).

More characteristic is the wound produced when both blades of a closed pair of scissors are plunged through the skin. Some scissors have a double-sharp point, but most domestic, tailors' or dressmaking scissors are fairly blunt at the tips when closed, so considerable force is needed to drive them through the skin – tending to work against a defence of an accidental movement against a passively held weapon.

The skin wound made by closed scissors is typically shaped like a flat 'Z' or the usual impressionist sign for a flash of lightning. The offset of the two blades gives this shallow zig-zag pattern, which is unmistakable when present. Some scissors, however, especially long narrow ones in which the blades close almost completely over



Figure 4.56 Various profiles made by scissors stabbed through the skin. The cross shapes are caused by blade screws or rivets; the one on the right is a full penetration of one blade of an open pair of scissors, the other blade impinging flat on the skin.



Figure 4.57 Multiple homicidal stab wounds by closed scissors.



Figure 4.58 Broken blade of a kitchen knife protruding from the eye. The victim was stabbed to death and dismembered thereafter by the perpetrator.



Figure 4.59 X-ray of the skull of the victim in 4.58, showing the position of the knife blade.



Figure 4.60 Dismembered body of the victim shown in 4.58, 4.59.

one another, may not reproduce this appearance and the wound may look more like that from a thick knife. Sometimes, there are small lateral splits in the wound centre from a projecting hinge screw.

Defence wounds

In assaults of any kind, the natural reaction of the victims is to protect themselves. The limbs used for protection can themselves be injured and these defence wounds may be of considerable medico-legal significance, as they indicate that the victim was conscious, at least partly mobile and not taken completely by surprise. Defence wounds can be sustained from attacks by fists, feet and blunt or sharp instruments. The classic position for them is on the forearms and hands, which are instinctively raised to protect the eyes, face and head. Other defence injuries may be inflicted on the thighs, when attempts are made to shield the genitals.

With attacks from blunt instruments or fists, bruises are the hallmark of defence attempts. They are common on the outer sides of the forearms, the wrists, the backs of the hands and knuckles (Fig. 4.61). The size and shape of the bruises naturally depends upon the attacking object. Abrasions may accompany the bruises but the latter are more common. Fractures of the carpal bones, metacarpals and digits may occur. If the arm is held in front of the face, the inner (palmar) side of the forearm may also receive blows. There may also be defence bruises and abrasions on the thigh, as blows or kicks aimed at the lower part of the body cause the victim, especially men, to protect the genitals. The leg may be brought across the other or the thigh raised, so that its outer side may receive blows or kicks.

The most obvious defence injuries are seen in knife attacks, as the victim often attempts to ward off the thrusts by seizing the weapon. When the fingers are closed around the blade, its withdrawal cuts across the flexures of the phalanges, slicing through the skin and perhaps tendons, or sometimes all four fingers. This may be seen in one, any, or even all of the three sets of flexures (Figs 4.63, 4.64).

The other typical knife defence wound is in the web between the base of the thumb and index finger, when the blade is grabbed in an attempted pincer action. Other knife wounds can be on the backs of the hands or fingers from non-grasping movements trying to ward off the weapon (Fig. 4.62). Defence wounds from knives are often sharply sliced, as the blade is drawn across the tightly applied skin. They are often markedly 'shelved', with loose flaps of skin and copious bleeding.

Defence wounds also occur in firearms injuries, where an arm is raised in a desperate attempt to shield



Figure 4.61 Defence injuries: extensive bruising on the hand in an attempt to fend off kicks. Such injuries confirm that the victim was conscious and active during the attack, and that it was not made covertly while the victim was unaware.



Figure 4.62 Defence wound on the back of the hand from trying to ward off the knife.



Figure 4.63 Typical defence injuries in a victim of a knife attack. In grasping the blade to deflect it, there have been cuts across the palmar surfaces of the finger joints and a slash between the thumb and forefinger, together with a cut at the base of the thumb.



Figure 4.64 Defence wounds of hand in attempts to ward off an assault with a knife.

the trunk or head from the blast (see Fig. 8.35). This accounts for some shooting deaths where there is an entrance and an exit wound in (often) the upper arm, the missile(s) then re-penetrating the trunk.

Dating of wounds by histology and histochemistry

Wound repair is a complex interplay of processes involving formed blood elements, parenchymal cells, extracellular matrix and numerous mediators and factors released by them and re-establishing haemostasis and initiating tissue repair.[27]

There are many publications on this subject, as it is a favourite topic for research. As with time of death, it can be an important matter in forensic medical investigations to determine whether a wound found at autopsy was inflicted before or after death and, if inflicted ante-mortem, how long before death it was sustained.[28–32]

Unfortunately, as with so many problems, biological variability introduces a wide margin of uncertainty, so that a range of probabilities can be offered, but never a definite time interval. Much of the experimental work has been performed on animals and the results are not transferable to man – a common defect in all animal work. The smaller the animal, the more rapid the tissue scavenging and reparative changes: more primitive animals have far greater powers of regeneration than man, both in wounds and in re-growing organs and even limbs.

The changes will also vary according to the size of a wound, the type of wound (bruise, abrasion, incision or laceration), the tissue (epidermal or mesodermal), whether there is infection and the age and health of the victim.

The subject is complex and often contradictory and the following schedule of events is offered only as a guideline. The original papers should be consulted if any particular criterion is to be followed; histological appearances, including fluorescence studies may be backed up by histochemical and biochemical assays and quite recently, increasingly by molecular biological methods.[33,34] The sequence of changes in bruises is far less distinct than in abrasions or lacerations and histology is much less helpful. The most useful criterion in a bruise is probably Perls' reaction [Prussian blue/Berliner–Blau–Reaktion; Max Perls (1843–1881)] for haemosiderin, which becomes positive about 24–90 hours after infliction – though some workers claim an earlier appearance, even down to 12 hours.[32,35] Haemolysis of red blood cells is irregular and patchy, many intact cells being seen in some bruises after many days, so their rupture and ghosting cannot be used as an index of age.

Chronological histological changes after wound infliction

30 minutes–4 hours

Margination of polymorph leucocytes in dilated small vessels may occur, a feature, which is often completely absent. It is also not a reliable sign of ante-mortem infliction, as leucocytes may congregate for many hours after death, especially in skin and around aspirated material in the lung.

Some extravascular emigration may begin at the end of this period, but a significant number of polymorphs usually delay for many more hours. Polymorphs tend to appear earlier in the subcutaneous fat than in the upper dermal layers. Basophilic 'mast cells' lose their granules. Fibrin appears in the wound within a few minutes, but this also occurs in post-mortem injuries.

4–12 hours

Leucocyte infiltration is likely to be more definite, still mostly polymorphs, but some mononuclear cells as well. A scanty mixed population of lymphocytes and poorly differentiated 'monocytes' appears, usually after 12 hours. Tissue oedema and swelling of vascular endothelium occurs. In small wounds involving the skin, the start of epithelial regeneration may be seen at the sides at the level of the basal layer of epidermis.

12–24 hours

Leucocytes tend to demarcate the area of the wound by forming a marginal palisade. The polymorph response declines and the macrophage and mononuclear cell population increases from now on. Removal of necrosed tissue begins, with macrophages evident and a basophilic tinge to the ground substance. Mitoses are visible in fibroblasts from about 15 hours. The epidermis begins to spread across the surface of the scab and down the sides of a cut into the wound.

24–72 hours

Leucocyte infiltration reaches a peak at about 48 hours; repair begins concurrently with many fibroblasts appearing, but rarely before 72 hours. New capillaries then begin to bud from vessels, the vascular, infiltrated stroma becoming 'granulation tissue'.

3–6 days

Repair is proceeding apace: collagen begins to form and giant cells may be visible around necrotic debris and foreign matter. The epidermis is actively growing if the wound involves the surface: in animals, it grows laterally at about 200 mm/d.

Haemosiderin becomes stainable from about the third day onwards, if there is a bruise or any bleeding into the wound, but is often not obtainable by Perls' reaction until the fifth day even though some claim it can appear on the first or second day.

10–15 days

Cellular reaction subsides in small wounds. Vascularity decreases and the cell population drops, especially leucocytes. Fibroblasts are most active, with collagen being laid down. The epidermis becomes thin and flat, but no papillae ('rete pegs') are reformed for many weeks. Elastic fibres are scarce for a long time and less than in adjacent undamaged tissue.

2 weeks to several months, depending on size and other factors

Consolidation of the healing tissue continues. The inflammatory response has vanished, unless the wound has become infected. Collagen and elastin increase and a vascular scar is formed, which gradually becomes more dense and avascular. The epithelium remodels and dermal papillae reappear unless the wound is wide and irregular. Skin adnexae do not reappear in the scar unless islands of viable skin survive within the wound area.

Histochemical changes in injured tissues

Histochemical and immunohistochemical methods have been studied widely and the pioneering work of Jyrki Raekallio in Finland, and Steffen Berg in Germany on the histochemical sequence of events in wounds is still frequently cited in this context.[30,31,36–45] Some techniques need frozen sections, others can be carried out on fixed tissue. Estimations of histamine or serotonin are usually 'tube' methods, rather than microscopic, though some fluorescent techniques have been developed.

Electrolytes, such as sodium, zinc, magnesium and calcium, serotonin, esterases, and glycophorin A have been used for this purpose.[30,37,39,46–53]

Betz and his co-workers have also published extensively on the immunohistochemistry of wound dating.[32,54–69]

More recently the emphasis has been on molecular biological methods, again mainly on animals, the transfer to the human situation being often unclear.[34]

At the present time these methods still remain mainly in the realm of the research laboratory, apart from a few enthusiasts who employ them in casework. For the histochemical novice, it would be unwise to put such procedures into evidence without first gaining extensive experience of control material. Experience emphasizes that strictly standard conditions are required for the production of such histochemical sections, the end result depends largely on laboratory procedures – 'change your technician and you change the answer'.

The following are some of the histochemical wound changes described by Raekallio and others:

- In a wound through the skin surface there is a central zone 0.2–0.5 mm wide that will become necrotic and in which enzyme activity rapidly decreases. This may be termed 'negative vital reaction'. Immediately beyond this layer, is a 0.1–0.3 mm zone of reaction and eventual repair, where a number of enzymes and other substances become increased in concentration during the reparative process, compared to the normal level in the areas outside the wound. Enzymatically, this can be called 'positive vital reaction', as no such zone develops in a post-mortem wound.
- Within 1 hour after injury, esterases and adenosine triphosphatase increase in the positive zone. At around 2 hours, aminopeptidase activities increase and, at 4 hours, acid phosphatase activity increases. Alkaline phosphatase activity is delayed another hour or so though, of course, all these times are relative and subject to the usual biological variability.
- Where death occurs at some stage of this process, the enzyme pattern is 'frozen' at that point and post-mortem changes do not substantially alter the reactions within a few days after death, especially if autolysis is kept at bay by refrigeration. Senility, severe illness and cachexia, as well as widespread multiple injuries, may distort the usual pattern by reducing the ability to produce these reparative enzymes. In contused wounds, the reactions are less useful than in cutaneous injuries, as the damage is more diffuse and there are no definite 'zones'. In all wounds, lack of reaction cannot be taken as indisputable proof of a post-mortem origin, though, if the opposite occurs, positive increase in the outer zone must only be the result of a vital reaction. Other enzymes have been used for wound dating: the review by Janssen (1984) in his authoritative book on forensic histology should be consulted for details, as well as the work of Betz.[54–71]
- Tissue cathepsins are said to increase almost immediately if the stroma is damaged, being demonstrable within 5–10 minutes. Two other substances are of use in establishing that wounds are ante-mortem and giving some idea as to their age. Both are produced during the inflammatory response that accompanies tissue damage – histamine and serotonin (5-hydroxytryptamine). They tend to be complementary to the enzymes, as they appear soon after infliction, within the hour or so before adenosine triphosphatase and esterases become detectable. These vasoactive amines appear in maximum concentration about 10 minutes (serotonin) and 20–30 minutes (histamine) after wounding. One of the first demonstrations of this forensic aid was by Fazekas and Varagos-Kis (1965), who showed that a ligature mark in hanging revealed increased serotonin; presumably the hanging was atypical and the victim took 10 minutes to die which is rather unusual.[46] For the employment of the test in human autopsy work, about 2 g of skin freed from subcutaneous fat are sampled, together with a similar control sample from a nearby normal area of skin from the same corpse. This is to allow for the markedly different amounts found in different people and, indeed, in the same persons at different times. To establish that a wound was ante-mortem rather than inflicted after death, the level of histamine in the wound must be at least 50 per cent greater than the control sample – and, for serotonin at least, twice the concentration of the control skin.
- In her recent excellent review on the characteristics of various methods and parameters applied for estimating wound age, Cecchi (2010), gives also practical advice as to the selection of appropriate markers depending on time window and available methods. For instance, vitality of wound can be assessed by using marker, such as *selectin E*, that is never present in healthy skin, or, to differentiate between vital and post-mortem injury by selecting parameters that are always known to be absent in wounds inflicted post-mortem, such as *kathepsin A and D*.[34]

Survival period after wounding

A pathologist is often asked either by police during an investigation, or by counsel at trial, what was the probable interval between the fatal injuries and death? A supplementary query is how long would the victim have been active, even if still alive?

These are extremely difficult questions to answer, as a number of variables enter the estimation. The doctor should never give a dogmatic answer, unless the nature and severity of injuries are obviously incompatible with continued life or activity.

A person who has his brainstem destroyed by a penetrating injury, or his aortic arch completely transected, will be inactive and clinically dead almost immediately. It would not necessarily be the case if his frontal lobes were damaged or his abdominal aorta was crushed by a railway wheel. Extraordinary instances of survival in both these latter instances are on record.

An opinion should always err on the side of caution in expressing opinions on this subject, as victims can do far more than might be expected after injury. The author (BK) once dealt with a homicide in which the victim was stabbed through the heart, yet ran more than a quarter of mile before collapsing. A wound in the left ventricle can partly seal itself by the contraction of the muscle around the defect and collapse may only occur when sufficient blood has leaked into the pericardium to form a tamponade. Wounds of the right ventricle are often more rapidly fatal as, although the pressure of contained blood is less, the thinner wall is not so effective in preventing the leak.

Head injuries can present many paradoxical instances of prolonged survival, depending partly on what part of the brain is injured. As mentioned, frontal lobes seem remarkably resistant to damage and it is often the generalized head impact, rather than focal damage to this area, that causes most harm. For example, a Finnish man who committed suicide made a home movie of himself firing a small calibre pistol into his brain. There was immediate collapse but, just at the end of the 4-minute film, the victim opened his eyes and raised his head, finally dying some time after the spool ran out, having fired a second shot into his head.

In the more usual stabbing, head injury, cut throat or shooting, the pathologist must try to assess the nature and severity of the physical damage, and relate that to the age, health and environment of the victim. This is naturally an imprecise exercise. An elderly female, or someone with severe cardiac or respiratory disease, is less likely to survive multiple injuries for as long as a robust young person – though if the nature of the injury is grossly life-threatening, these factors will make little difference.

A cut artery will lose blood faster than a vein of the same general size, especially if it is only partly severed so that it cannot retract. Other factors, such as the possibility of air embolism occurring in a cut jugular vein, might alter the usual pattern of expected events. The heart is less vulnerable than great thoracic vessels in many stab wounds, as mentioned above. Many wounds of the ventricles are survivable. The author (BK) has twice been warned by police of an imminent autopsy on victims admitted for emergency surgery – only to hear later that, thankfully, they had walked out of the hospital after a successful operation. One had a through-and-through stab wound of the left ventricle that transfixed the heart from front to back.

Where a wound has transected a major coronary artery, then prolonged survival is unlikely, as is one that interrupts a major branch of the conducting system. Other than injuries to the brain or to a large blood vessel, most other injuries can rarely be declared to have caused sudden death or rapid loss of function. In criminal cases, it may be a point of some importance to decide whether the victim could have continued fighting, have run away, have resisted, or even have inflicted injuries on someone else before collapsing and dying. It is difficult to swear that at least some activity was not possible in the great majority of instances. In the adrenaline response of 'fight or flight', the shock element of pain is greatly suppressed – many soldiers have been quite unaware of having sustained severe or lethal wounds until they notice the blood or the battle is over. Thus the usual 'shock' effect may be damped down considerably in an assault and only the sheer physical and haemodynamic sequelae of the injury will eventually lead to a slowing down, then collapse and death. In the interval, injured victims may be able to perform normal physical activity, sometimes to an astonishing degree, albeit followed by sudden deflation of their capacity for exercise.

As in most aspects of forensic medicine, it is unwise of the doctor to be too definite about these matters – the old forensic aphorism 'Seldom say never – seldom say always' is even more true here than usual.

Most issues of this nature revolve around periods of a few minutes, the perimortal or agonal time when few morphological signs are available. The more sophisticated enzyme and serotonin techniques mentioned elsewhere in this chapter may give some clue about the survival period, but are rarely unequivocal enough to be used as hard forensic evidence. If survival is longer, then both gross and histological changes of 'vital reaction', such as thrombosis, inflammation, infection and healing may be useful, but they usually require hours or even days of survival to appear.

The accepted wisdom of wound dating is that polymorph leucocytes begin to appear in wounded tissue within a few minutes, but it has been shown that this can happen even several hours after death, as all leucocytes do not become immobile with cardiac arrest. A good, conventional inflammatory response must be a vital reaction, however, though several hours' survival is needed for it to be convincing. The author (BK) has seen a dramatic red flare caused by post-mortem burning at least 30 minutes after undoubted death from strangulation.

Another problem with differentiating 'ante-mortem' from 'post-mortem' injuries is the definition of the moment of death. Again, lawyers, judges and coroners tend to assume that death is an *event*, whereas, in reality, it is a *process* (Chapter 2). Though in most criminal or accidental deaths the moment of death is conventionally – and reasonably – taken to be the moment of cardiac arrest, and thus collapse of blood pressure and cerebral circulation, the cells of the body are still alive and remain so for a variable time – only minutes in the case of neurons, but leucocytes and muscle cells survive for many hours, and connective tissue cells, such as fibroblasts, for days. Thus, it is unreasonable to expect dramatic changes within minutes in skin wounds, etc., until progressive hypoxia alters biochemical processes and enzyme activity. Leucocytes may be motile for more than 12 hours and can aggregate around chemotactically active material, such as gastric contents aspirated into the air passages. This makes the 'vital reaction' a dubiously valid phenomenon in the perimortal period. Much more research is needed into the histology, histochemistry and biochemistry of the perimortal period to clarify these issues, but in the mean time, less dogmatic reliance must be held upon the old criteria of 'ante-' and 'post-' mortem phenomena and the 'vital reaction'.

References

1 Shapiro HA, Gluckman J, Gordon I. The significance of finger nail abrasions of the skin. *J Forensic Med* 1962;9:17–19.

2 Werkgartner A. Eigenartige Hautverletzungen durch Schüsse aus angesetzten Selbstladepistolen. *Beitr Gerichtl Med* 1924;6:148–61.

3 Roberts R. Sexual offences. In: *Rape – The New Police Surgeon Supplement*. Northampton: APSGB, 1983.

4 Langlois NE, Gresham GA. The ageing of bruises: a review and study of the colour changes with time. *Forensic Sci Int* 1991;50(2):227–38.

5 Langlois NEI. The science behind the quest to determine the age of bruises – a review of the English language literature. *Forensic Sci Med Pathol* 2007;3(4):241–51.

6 Stephenson T, Bialas Y. Estimation of the age of bruising. *Arch Dis Child* 1996;74(1):53–5.

7 Munang LA, Leonard PA, Mok JY. Lack of agreement on colour description between clinicians examining childhood bruising. *J Clin Forensic Med* 2002;9(4):171–4.

8 Maguire S, *et al*. Can you age bruises accurately in children? A systematic review. *Arch Dis Child* 2005;90(2):187–9.

9 Byard RW, *et al*. Histologic dating of bruises in moribund infants and young children. *Forensic Sci Med Pathol* 2008;4(3):187–92.

10 Hughes VK, Ellis PS, Langlois NE. The perception of yellow in bruises. *J Clin Forensic Med* 2004;11(5):257–9.

11 Serina ER, Lieu DK. Thoracic injury potential of basic competition taekwondo kicks. *J Biomech* 1991;24(10):951–60.

12 Grass H, *et al*. [Phenomenology of kicking and kicking to death]. *Arch Kriminol* 1996;198(3–4):73–8.

13 Henn V, *et al*. [Morphology and phenomenology of death by kicking (II)]. *Arch Kriminol* 2000;205(3–4):65–74.

14 Strauch H, *et al*. Kicking to death - forensic and criminological aspects. *Forensic Sci Int* 2001;123(2–3):165–71.

15 Prinsloo I, Gordon I. Post-mortem dissection artefacts of the neck and their differentiation from ante-mortem bruises. *South African Med J* 1951;25:358–61.

16 Gee DJ. The pathological aspects of the Yorkshire ripper case. *Acta Med Leg Soc (Liege)* 1984;34:25–31.

17 Gibson T. Karl Langer (1819–1887) and his lines. *Br J Plast Surg* 1978;31(1):1–2.

18 Langer K. On the anatomy and physiology of the skin. I. The cleavability of the cutis. *Br J Plast Surg* 1978;31(1):3–8.

19 Langer K. On the anatomy and physiology of the skin. II. Skin tension. *Br J Plast Surg* 1978;31(2):93–106.

20 Langer K. On the anatomy and physiology of the skin. III. The elasticity of the cutis. *Br J Plast Surg* 1978;31(3):185–99.

21 Langer K. On the anatomy and physiology of the skin. Conclusions. *Br J Plast Surg* 1978;31(4):277–8.

22 Knight B. The dynamics of stab wounds. *Forensic Sci* 1975;6(3):249–55.

23 Hainsworth SV, Delaney RJ, Rutty GN. How sharp is sharp? Towards quantification of the sharpness and penetration ability of kitchen knives used in stabbings. *Int J Legal Med* 2008;122(4):281–91.

24 Parmar K, Hainsworth SV, Rutty GN. Quantification of forces required for stabbing with screwdrivers and other blunter instruments. *Int J Legal Med* 2012;126(1):43–53.

25 Hocking MA. Assaults in South-east London. *J R Soc Med* 1989;82(5):281–4.

26 Shepherd JP, Price M, Shenfine P. Glass abuse and urban licensed premises [letter]. *J R Soc Med* 1990;83(4):276–7.

27 Clark RAF, Singer AJ. *Wound Repair: Basic Biology to Tissue Engineering*, in *Principles of Tissue Engineering*. Robert PL, Robert L, Joseph V (eds). San Diego: Academic Press, 2000, pp. 857–78.

28 Walcher K. Über vitale Reaktionen. *Dtsch Z Gesamte Gerichtl Med* 1930;15(1):16–57.

29 Orsós F. Die vitale Reaktionen und ihre gerichtsmedizinische Bedeutung. *Beitr Pathol Anat* 1935;95:163–241.

30 Berg S. [Age determination of skin wounds]. *Z Rechtsmed* 1972;70(3):121–35.

31 Raekallio J. Histochemical distinction between antemortem and postmortem skin wounds. *J Forensic Sci* 1964;9(1):107–18.

32 Betz P. Vitale reaktionen und zeitschätzungen. In: Brinkmann B, Madea B (eds). *Handbuch Gerichtliche Medizin*. Berlin: Springer-Verlag, 2004, pp. 297–333.

33 Kondo T, Ishida Y. Molecular pathology of wound healing. *Forensic Sci Int* 2010;203(1–3):93–8.

34 Cecchi R. Estimating wound age: looking into the future. *Int J Legal Med* 2010;124(6):523–36.

35 Perls M. Nachweis von eisenoxyd in gewissen pigmenten. *Virchows Arch Pathol Anat* 1867;39(1):42–8.

36 Raekallio J. Applications of histochemistry to forensic medicine. *Med Sci Law* 1966;6(3):142–6.

37 Raekallio J. Determination of the age of wounds by histochemical and biochemical methods. *Forensic Sci* 1972;1(1):3–16.

38 Raekallio J. Estimation of the age of injuries by histochemical and biochemical methods. *Z Rechtsmed* 1973;73(2):83–102.

39 Raekallio J. Estimation of time in forensic biology and pathology. An introductory review. *Am J Forensic Med Pathol* 1980;1(3):213–8.

40 Raekallio J, Makinen PL. The effect of ageing on enzyme histochemical vital reactions. *Z Rechtsmed* 1974;75(2):105–11.

41 Berg S. [Histamine level and lung mast cells in death from hemorrhage (author's transl)]. *Z Rechtsmed* 1974;74(4):245–51.

42 Berg S, *et al*. [The influence of loss of blood and alcohol intoxication on early vital wound reactions (author's transl)]. *Z Rechtsmed* 1977;80(1):39–49.

43 Berg S, Bonte R. [The catecholamine contents of cadaver blood and cerebrospinal liquor in different types of agony]. *Z Rechtsmed* 1973;72(1):56–62.

44 Berg S, *et al*. [Histamine content and histidine-decarboxylase-activity in dermal injuries]. Z Rechtsmed 1971;69(1):26–40.

45 Berg S, Garbe G, Luerssen B. [The significance of topic differences and cadaveric changes of histamine and serotonin levels for the determination of the age of wounds in animal experiments (author's transl)]. *Z Rechtsmed* 1978;82(3):165–74.

46 Fazekas IG, Viragos Kis E. [Free histamine content in the groove caused by hanging as an in vivo reaction]. *Dtsch Z Gesamte Gerichtl Med* 1965;56(4):250–68.

47 Fazekas IG, Viragos Kis E. [Free histamine-content of different wounds as vital reaction]. *Z Rechtsmed* 1971;68(2):86–94.

48 Hernandez-Cueto C, Luna-Maldonado A, Villanueva Canadas E. Study of cathepsin A and D activities and Ca, Mg, Cu, Zn, Fe, Na and K levels in pig skin as a tool for the differential diagnosis between vital and postmortem skin wounds. *Acta Med Leg Soc (Liege)* 1984;34:174–8.

49 Hernandez-Cueto C, *et al*. Cathepsin D as a vitality marker in human skin wounds. *Int J Legal Med* 1993;106(3):145–7.

50 Hernandez-Cueto C, *et al*. Study of cathepsin A, B and D activities in the skin wound edges. Its application to the differential diagnosis between vital and postmortem wounds. *Forensic Sci Int* 1987;35(1):51–60.

51 Chen YC, *et al*. Diagnostic value of ions as markers for differentiating antemortem from postmortem wounds. *Forensic Sci Int* 1995;75(2–3):157–61.

52 Kibayashi K, *et al*. Differentiation between bruises and putrefactive discolorations of the skin by immunological analysis of glycophorin A. *Forensic Sci Int* 1993;61(2–3):111–17.

53 Tabata N, Morita M. Immunohistochemical demonstration of bleeding in decomposed bodies by using anti-glycophorin A monoclonal antibody. *Forensic Sci Int* 1997;87(1):1–8.

54 Betz P, *et al*. Time-dependent appearance of myofibroblasts in granulation tissue of human skin wounds. *Int J Legal Med* 1992;105(2):99–103.

55 Betz P, *et al*. The time-dependent rearrangement of the epithelial basement membrane in human skin wounds – immunohistochemical localization of collagen IV and VII. *Int J Legal Med* 1992;105(2):93–7.

56 Betz P, *et al*. Immunohistochemical localization of fibronectin as a tool for the age determination of human skin wounds. *Int J Legal Med* 1992;105(1):21–6.

57 Betz P, *et al*. Time-dependent pericellular expression of collagen type IV, laminin, and heparan sulfate proteoglycan in myofibroblasts. *Int J Legal Med* 1992;105(3):169–72.

58 Betz P, *et al*. Comparison of the solophenyl-red polarization method and the immunohistochemical analysis for collagen type III. *Int J Legal Med* 1992;105(1):27–9.

59 Betz P, *et al*. Localization of tenascin in human skin wounds – an immunohistochemical study. *Int J Legal Med* 1993;105(6):325–8.

60 Betz P, *et al*. The time-dependent expression of keratins 5 and 13 during the reepithelialization of human skin wounds. Int J Legal Med 1993;105(4):229–32.

61 Betz P, *et al*. The immunohistochemical analysis of fibronectin, collagen type III, laminin, and cytokeratin 5 in putrified skin. *Forensic Sci Int* 1993;61(1):35–42.

62 Betz P, *et al*. Analysis of the immunohistochemical localization of collagen type III and V for the time-estimation of human skin wounds. *Int J Legal Med* 1993;105(6):329–32.

63 Betz P, *et al*. The immunohistochemical localization of alpha 1-antichymotrypsin and fibronectin and its meaning for the determination of the vitality of human skin wounds. *Int J Legal Med* 1993;105(4):223–7.

64 Betz P, *et al*. The time-dependent localization of Ki67 antigen-positive cells in human skin wounds. *Int J Legal Med* 1993;106(1):35–40.

65 Betz P, *et al*. Immunohistochemical localization of collagen types I and VI in human skin wounds. *Int J Legal Med* 1993;106(1):31–4.

66 Betz P. Histological and enzyme histochemical parameters for the age estimation of human skin wounds. *Int J Legal Med* 1994;107(2):60–8.

67 Betz P. Immunohistochemical parameters for the age estimation of human skin wounds. A review. *Am J Forensic Med Pathol* 1995;16(3):203–9.

68 Betz P, Tubel J, Eisenmenger W. Immunohistochemical analysis of markers for different macrophage phenotypes and their use for a forensic wound age estimation. *Int J Legal Med* 1995;107(4):197–200.

69 Betz P, *et al*. Detection of cell death in human skin wounds of various ages by an *in situ* end labeling of nuclear DNA fragments. *Int J Legal Med* 1997;110(5):240–3.

70 Janssen W. *Forensic Histopathology*. Berlin: Springer Verlag, 1984.

71 Betz P, Eisenmenger W. Morphometrical analysis of hemosiderin deposits in relation to wound age. *Int J Legal Med* 1996;108(5):262–4.

This page intentionally left blank

CHAPTER 5

Head and Spinal Injuries

- Injury to the scalp
- Facial injuries
- Falls
- Fractures of the skull
- Intracranial injuries
- Forensic anatomy of the brain membranes
- Extradural (epidural) haemorrhage (EDH)
- Heat haematoma
- Subdural haemorrhage
- Subarachnoid haemorrhage
- Forensic implications of brain membrane haemorrhage
- Ruptured berry aneurysm and trauma
- Subarachnoid haemorrhage and alcohol
- The rapidity of death in subarachnoid haemorrhage
- Rotational trauma to the head and upper neck: basilovertebral artery injury
- Head injuries in boxers and contact sport athletes
- Cerebral injuries
- Diagnosis of early cerebral hypoxia–ischaemia
- Secondary brainstem lesions
- Spinal injuries
- References

Of all regional injuries, those of the head and neck are the most common and most important in forensic practice. Adelson gives these sound reasons for this dominance of head injuries:[1]

- The head is the target of choice in the great majority of assaults involving blunt trauma.
- When the victim is pushed or knocked to the ground, he often strikes his head.
- The brain and its coverings are vulnerable to degrees of blunt trauma that would rarely be lethal if applied to other areas.

A sound practical understanding of the neuropathology of trauma is more essential to the forensic pathologist than any other aspect of his subject, as head injuries provide the major contribution to death in assaults, falls and transportation accidents.

Injury to the scalp

The scalp is often, though by no means invariably, damaged in trauma that causes injury to the underlying skull and brain. The usual range of abrasions, contusions and lacerations may be inflicted, though a modifying factor is the presence of hair, which may deflect a tangential blow or partly cushion a direct impact.

When an injury is visible on the forehead, the back of the neck, the lower temple or on a bald area, the examination is no different from elsewhere on the body. In hair-covered areas, care must always be taken at autopsy to palpate the scalp in any case in which there is a possibility of injury, otherwise abrasions, swelling, bruising and even lacerations may be missed. When a lesion is found or suspected, the hair must be carefully shaved away to expose the scalp for further examination and photography.

Forensic anatomy of the scalp

Superficially, the skin carries hair follicles, sebaceous glands and sweat glands. The skin is attached to the aponeurosis (see below) by vertical strands of fibrous tissue that break up the subcutaneous layer into pockets filled with fat. The blood vessels and nerves lie in this layer, above the epicranial aponeurosis (formerly called the 'galea aponeurotica'). This is a dense sheet of fibrous tissue that lies in the deep layer of the scalp over the whole cranium. It is really a flattened tendon uniting the frontal and occipital bellies of the occipitofrontalis muscle (Fig. 5.1).

Deep to the aponeurosis is a thin layer of loose connective tissue that separates it from the pericranium, which is the exterior periosteum of the skull, the dura



Figure 5.1 Anatomy of the scalp.

being the internal counterpart. Emissary veins traverse all the layers from the superficial fascia to the pericranium, and go on to penetrate the skull and communicate with the intracranial venous sinuses, thus forming a route for meningitis and sinus thrombosis from infected injuries of the scalp (Fig. 5.13).

Abrasion of the scalp

Brush abrasions are less common than in other sites because of the protective effect of the hair, which also tends to prevent or blur the patterned effect of less severe impacts. Impact abrasions from a perpendicular force are imprinted as usual on to the scalp, though again the intervening hair may reduce the severity. Unless the hair is carefully removed at autopsy, with a sharp scalpel or razor, and care taken not to cause artefactual cuts, lesser degrees of abrasion will inevitably be missed.

Bruising of the scalp

Bruising may be difficult to detect until the hair has been removed. Marked swelling is a common feature of extensive bruising, as the liberated blood cannot extend downward because of the rigidity of the underlying skull. However, this subsides, or at least diffuses, after death. Commonly, a severe head injury leads to a thick, swollen, indurated layer of blood beneath the scalp, which may extend over a wide area. The blood is sometimes below the aponeurosis, the tough fascial layer of the scalp, but is more often between this and the epidermis.

Blood may also be present beneath the pericranium, the periosteum that is closely applied to the outer surface of the skull. This is often seen in head injuries in infants, usually in association with skull fractures, as the source of the blood is from the fracture line itself. The close attachment of the pericranium to the suture lines in infants may sharply circumscribe the extent of the bleeding.

In addition to frank bleeding beneath the scalp, marked oedema may occur after injury and the layers of the scalp may be greatly swollen and thickened by a jelly-like infiltration of tissue fluid.

As will be discussed under ‘black eye’, bleeding under the scalp may be mobile, especially under gravity. Thus a bruise or haematoma under the anterior scalp may slide down-wards within hours – even minutes – to appear in the orbit, simulating a black eye from direct trauma (Fig. 5.9). Similarly, a temporal bruise may later appear behind the ear, suggesting primary neck impact. As with bruises elsewhere, those under the scalp may be obvious immediately after infliction – or their appearance may be delayed, either during life or as a post-mortem phenomenon. They may first become evident, or much more prominent, some hours – or even a day or so – after death. This is caused either by movement of the extravasated blood through tissue planes or by haemolysis spreading outwards to stain the subcutaneous tissues, making it always advisable to return to examine the body a day or two following the autopsy.

The shape of an inflicting weapon or object is poorly reproduced on the scalp, again due to the padding effect of the hair. Where the scalp is free of hair, as in the upper forehead or bald areas, all traumatic lesions are similar to elsewhere on the body, with the exception that blunt impact may cause very sharply defined lacerations.

Laceration of the scalp

Lacerations of the scalp bleed profusely, and dangerous and even fatal blood loss can occur from an extensive scalp injury if it is not checked by treatment. The most gross injury is avulsion of a large area of scalp, which can be torn from the head, thereby exposing the aponeurosis or skull. This may happen if the hair becomes entangled in machinery, as was formerly not uncommon in females working in factories. A more common cause nowadays is a traffic accident, where a rotating vehicle tyre comes into contact with the head, causing a ‘flaying’ injury similar to that seen on limbs.

Scalp injuries may bleed profusely *even after death*, especially if the head is in a dependent position. A post-mortem injury to the head may bleed considerably if inflicted soon after death and these facts may sometimes cause confusion about the ante-mortem or post-mortem nature of the wound, or about the length of time of survival following the injury. There is no reliable way of resolving this difficulty.

Lacerations of the scalp may reproduce the pattern of the inflicting object, even though a random splitting is so common. Severe blows from shaped objects such as hammers or heavy tools may reproduce the profile of the weapon totally or in part. A circular-faced hammer may punch a circle in the scalp, but more often only an arc of a circle is seen. In such cases, the position of the edge that digs in most deeply may give an indication of the angle of the blow. There may be a depressed fracture of the underlying skull of the same shape and size, though the interposition of the dense scalp may cause the skull defect to be slightly larger than the weapon. A depressed fracture in these circumstances is not inevitable, however, and one or more linear fractures may radiate from the impact site.

A major problem in scalp injuries is the differentiation between incised wounds and lacerations from blunt injury (Figs 5.5–5.7).

The scalp is the best example of a surface tissue lying over an unyielding bony support. Violent compression will crush the scalp against the underlying skull, so a blow from a blunt rod-like weapon may split the skin and underlying tissues in a sharply demarcated fashion, which may appear remarkably like a slash from a sharp instrument. Close examination, using a lens if necessary, will show that this blunt laceration has:

- bruised margins, even though this zone may be narrow
- head hairs crossing the wound, which have not been cut
- fascial strands, hair bulbs and perhaps small nerves and vessels in the depths of the wound (Figs 5.2–5.4).



Figure 5.2 A laceration of the scalp caused by a blow from an iron bar. The edges are crushed and bruised, with strands of connective tissue and hairs crossing the gap, indicating that it was not caused by a sharp-edged weapon.



Figure 5.3 Lacerations of the scalp from an iron bar. The margins are bruised and the scalp tissue is extruding in places. The generally parallel direction of the five wounds indicates that the assailant probably delivered the blows in rapid succession with little change of orientation between weapon and head.



Figure 5.4 Stellate laceration of the scalp caused by a heavy blow with a piece of timber. The support of the underlying skull has caused the tissues to split widely. At autopsy, full clearance of the hair must be made to allow detailed examination and photography.

Scalp injuries from falls

It is vital for the pathologist to appreciate that falls on to a flat surface, or a blow from a wide, flat object such as a plank or paving stone, may sometimes leave no external mark whatsoever on the exterior of the head, but commonly such an injury will cause a ragged split which may be linear, stellate or quite irregular.



Figure 5.5 Wounds from a metal poker superficially resembling incised cuts, but having edges and tissue bridges within the wounds. The black eyes are due to basal fractures of the anterior fossae.



Figure 5.6 Deep linear incised wounds due to a heavy, sharp cleaver. The depth of penetration varies, the large wound overlying extensive skull fractures. The wounds on the neck are due to light contact with the edge of the same blade.



Figure 5.7 Sliced incised wound of the scalp, from a large knife. The wound is markedly undercut, turning a wide flap of scalp. The clean edges, with a lack of any abrasion or bruising, indicate the sharpness of the weapon.

Such injuries on the back point of the head are commonly caused by falling, especially in inebriated victims. Falls backwards against a ridge, such as a wall or pavement kerb, may cause a transverse laceration, which may be undercut and partly detached from the underlying bone so that a flap of scalp is loosened from the skull.

Falls usually injure the occipital protuberance, the forehead or the parietotemporal areas. Injuries on the vertex should always raise the suspicion of assault, as it is unusual to fall upon the top of the head, even from a considerable height. Occasionally, a fall backwards that just happens to reach a vertical surface, such as a wall or piece of furniture, can cause damage to the top of the head, but there is then usually an obvious grazing component to the lesion.

Facial injuries

Damage to the face is common, but unless gross, with skeletal damage, is rarely fatal in itself unless it leads to bleeding into the air passages. It is often ancillary to fatal cranial damage, or it may be the route by which severe trauma reaches the brain.

The usual range of injuries may be present externally, but all degrees of underlying damage may also occur in the facial skeleton. Because of the complex contours of the face, the various prominences of chin, nose, cheekbones, eyebrows, ears and lips may intercept impacts, with consequent characteristic damage. The eyebrow is particularly vulnerable, being exposed during falls and blows. A blunt impact on the brow often splits the skin and may cause an underlying frontal fracture that can involve the orbital margin.

The distal part of the nose is flexible and often escapes serious damage, though abrasion is common. The bony bridge of the nose is often fractured, which may be detected by movement and crepitus during external palpation – and by dissection at autopsy. Bleeding in the nose is more important than structural damage, as profuse haemorrhage in an unconscious victim may pass back through the posterior nares into the throat and cause fatal airway obstruction.

The maxillae and mandible may be fractured by direct blows and again cause dangerous intraoral bleeding from associated soft-tissue damage. A heavy blow or kick to one side of the jaw can cause ipsilateral, bilateral or even contralateral fractures. Gross injury to the face, seen in kicking and some transport accidents, may actually detach the facial skeleton from the base of the skull. The lower part of the maxilla, carrying the palate and upper teeth, may be completely separated from the rest of the skull. At autopsy, the best view of the facial skeleton may be gained by dissecting the whole facial skin upwards from the neck incision and reflecting it as far as the orbits, if necessary. Good restoration can be achieved as long as the skin is not penetrated by the knife.

Injuries to the mouth and lips are very common in 'beating-up' incidents, including child abuse. The lips may be bruised or lacerated, much of the damage arising from compression of the lips against the teeth or bony gums. Lacerations on the gingival aspect of the lips may often be exactly matched with the edges of teeth. A torn labial frenum has been widely regarded as pathognomonic of abuse; however, recent literature reviews do not support the diagnosis of abuse based on a torn labial frenum in isolation.[2–5]

Kicking

Kicking of the face is regrettably common and again the prominences suffer most. Bruising, laceration and fractures may result from kicking under the side of the jaw: similar lesions occur on the maxillary area and the eyebrows. Patterned abrasions from boot soles may be seen or crescentic marks from toecaps. Brush abrasions from glancing kicks may be present on the cheeks or forehead as the sole of the shoe scrapes across the skin. It is uncommon to suffer a 'pure' black eye from a kick without other facial injuries, such as scuffed abrasion on the cheekbones, or marks on the brows or bridge of the nose. Teeth may be loosened, broken or detached by both kicks and heavy punches and black eyes and fractures of the nose are common. A kick on the side of the jaw may cause bilateral jaw fractures or even a single contralateral fracture (Fig. 5.8).

It may be difficult or impossible to differentiate in every case, between injuries (especially to the face) caused by kicks and those from blows from a blunt object. Toecap marks are not all that common, especially since the more flexible rubber 'trainer' shoes have become almost universal footwear.

In stamping, there is the chance that the sole pattern may leave an imprint, but a swing from a toe may leave a non-specific abrasion, bruise or laceration (see Fig. 4.17). It may be that the severity of the injury, including underlying bone damage, may be a better indication of a kick than the shape of the injuries, as the force delivered by a swinging foot at the end of a muscular leg is greater than that from a fist.[6–8]



Figure 5.8 Facial injuries caused by kicking and stamping. Death was caused by multiple fractures of the facial bones and by blockage of the air passages by blood.

Black eyes

The usual periorbital haematoma or 'black eye' is usually caused by a direct punch or kick into the eye-socket, but the pathologist must always consider the several alternative explanations. A black eye may be the result of (Fig. 5.9):

- direct violence, which may or may not be associated with abrasion or laceration on the upper cheek, eyebrow, nose or other part of the face (Figs 4.22, 5.10)
- gravitational seepage of blood beneath the scalp from a bruise or laceration on or above the eyebrow (Fig. 5.11). Survival and at least a partially upright posture of the head must have been maintained for at least some minutes, usually longer, between the time of injury and death. When the scalp lesion is high up on the frontal region, this time will probably be measured in hours. In a retrospective analysis of 21 subjects with scalp wounds in the forehead by Betz and coworkers, black eyes were seen at the earliest approximately 4 hours after wound infliction[9]
- percolation of blood into the orbit from a fracture of the anterior fossa of the skull. This is often from a contrecoup injury caused by a fall on to the back of the head, leading to secondary fracture of the paper-thin bone of the orbital roof (Fig. 5.12). It is invariably associated with contrecoup contusion of the frontal lobes of the brain, as described later in this chapter.



Figure 5.9 The production of a black eye: 1. A direct blow into the orbit. 2. An injury to the front of the scalp, draining down over the supraorbital ridge. 3. A fracture of the base of the skull (direct or contrecoup) allowing meningeal haemorrhage to escape through the orbital roof.



Figure 5.11 Black eye as a result of gravitational seepage of blood downwards from a forehead injury. The female was struck with a rock on the frontal area and eyebrow, blood then descending during the few hours of coma before death occurred.



Figure 5.10 Black eye from a direct impact into the orbit from a punch. This is the third mechanism of production of a periorbital haematoma, the others being a fracture of the anterior base of the skull and a frontal scalp wound.



Figure 5.12 Bilateral black eyes caused by leakage of blood into the orbits through comminuted fractures in the floor of the anterior fossa. This homicide victim was struck on the head with a shovel and survived for some days. Brain tissue is escaping from the nostrils through basal skull fractures.

A simple fall onto the face on a flat surface does not usually cause a black eye, as the prominences of the eyebrow, cheekbone and nose prevent damage to the orbit.

Damage to the ear

The external ear often suffers from blows to the head and is an obvious target in child abuse. Bruising and laceration of the pinna is obvious on examination and – in severe trauma – the root of the ear may be detached from the head, usually by a tear at the posterior margin where the ear joins the head. Where gross damage is present, especially with partial avulsion of the pinna, kicking must be considered.

The ear may be bitten and even partly detached, a fate which occasionally is suffered by the nose. In such cases the advice of a forensic odontologist may be invaluable, as teeth marks may form vital evidence.

Falls

Falls are extremely common, the severity not necessarily being directly related to the distance that the person falls. Many people die after falling from a standing position, yet others sometimes survive a fall of many metres.

Falls from a standing position can occur if a person is drunk, from an assault, during illness (such as a fit or faint) and for many other reasons. Death can follow from a head injury, especially onto the back of the head. An occipital scalp laceration or a fracture of the skull is not necessary for cerebral damage (often frontal contrecoup contusion) to occur. There may also be a subdural or (less often) an extradural haemorrhage, the latter more common from a fall on to the side of the head.

The vexed question of head injury from falls in children is discussed in Chapter 22, but here it may be stated that, although fatal head injury from a fall usually requires a drop of a number of feet, there are well-authenticated instances of skull fractures and brain damage from trivial falls, including some medically witnessed falls from tables and settees. The experimental work of Weber (see Chapter 22) showed that the skulls of small infants could be fractured against a variety of floor surfaces from passive falls of only 82 cm (32 in). It is thus invalid for medical witnesses to claim it **cannot** happen, as even one authenticated case creates a precedent.[10] In adults, fractures have certainly occurred from falls onto very hard surfaces from only approximately 30 cm (about 1 ft). One such case was a drunk lying on concrete; equally drunken friends attempted to lift him but allowed his head and shoulders to fall back from about half-sitting position, causing occipital fracture.

Falls in old people very frequently cause fractures of the post-cranial skeleton – especially the neck of femur – though ribs, arms and pelvis may also suffer. Osteoporosis is the major reason for the large number of such injuries from falls. More than 47000 fractured femora occur each year in Britain, with a 25 per cent mortality rate, mainly from subsequent pulmonary embolism or bronchopneumonia.

Falls from a height

Falls from a considerable height, usually from a building, are common in suicide and in some accidents, especially to children. Occasionally deaths from a high fall may be homicidal, again especially in children.

When a person falls or jumps from a height, the trajectory is downwards and outwards, and the distance that the body strikes the ground from the jumping point is variable. Goonetilleke has published some research on how far from the wall a body is likely to land.[11] Much depends on whether the victims fell passively from near the wall or projected themselves outwards at the top. The body may fall while maintaining the same orientation to the ground, but usually turns and twists in an unpredictable manner, the amount of alteration of posture partly depending upon the height of the fall and so the time available for turning. This means that the body may strike the ground in a number of different attitudes – and may also strike some obstruction part of the way down, making interpretation of injuries difficult (see Fig. 4.6).

The primary impact is usually the site of the most severe injury, but this is not always the case, as it may strike two areas simultaneously, such as the head and shoulder – or it may bounce or ricochet so that two or more major impacts occur in quick succession. The amount of kinetic energy acquired during the fall has to be fully expended by the time the body comes to rest so that, if only one impact occurs, it is likely to be more damaging than a series of lesser impacts, such as a bouncing, rolling strike.

If the body falls on to the head, there is likely to be a massive fracture, often (but not always) a scalp laceration and possibly extrusion of brain. Both vault and base can fracture and sometimes the base is driven down over the cervical spine, the latter projecting into the posterior fossa. The latter injury is, however, more common with high falls onto the feet when the impact is transmitted up the spinal column and the upper vertebrae – together with a ring of bone around the foramen magnum – are intruded into the skull, causing the classic 'ring fracture' of the occipital bone. Where the fall is onto the feet, the deceleration stress can break the axial skeleton at a number of points. The legs can be broken at any point, at tibial or femoral level, often bilaterally. The femoral necks can be snapped off, the hip joints can dislocate and over-ride, or the pelvis may fracture. The latter is often through the sacroiliac joints, the upward force (or more accurately, downward force of the body on to the legs) driving the sacrum down as a wedge into the pelvis.

If the lower limbs and pelvic girdle remain intact, the transmitted force may then fracture the spine, often at mid- or upper thoracic level.

Where the fall occurs onto the side of the body, any combination of injuries can occur. Multiple rib fractures, shoulder girdle or arm fractures, lacerations of back, buttocks or limbs and severe abdominal injuries can occur, with consequent internal lesions, such as rupture of the liver, lungs, heart or spleen.

In falls from high-rise buildings, the injuries can be extreme, as in a suicide from the 20th floor seen by the author (BK), where the victim fell onto a fence and was completely transected at waist level (see Fig. 4.33).

It must also be remembered that biological and circumstantial variability allows for some remarkable escapes from falls; some persons, including children, have fallen from great heights yet have virtually walked away unscathed. Once again, it is very unwise to overinterpret the relationship between observed injuries and the likely length of the fall.

Fractures of the skull

Forensic anatomy

The cranium and facial bones are laid down from membrane in fetal life. The anterior fontanelle closes functionally between 9 and 26 weeks after birth, though is not tightly sealed until about 18 months. The posterior fontanelle closes between birth and 8 weeks of age. Suture lines close by interdigitation during childhood and osseous fusion occurs irregularly at variable dates during adult life.

The adult cranium consists of two parallel tables of compact bone called the 'diploë', the outer being about twice the thickness of the inner. They are separated by a central zone of soft cancellous bone, which is often misnamed the diploë. This zone is interrupted at suture lines and vanishes where the bone becomes particularly thin, especially in the floor of the skull.



Figure 5.13 Forensic anatomy of skull and meninges.

The cranium varies in thickness in adults and varies from place to place, thin plates being reinforced by stronger buttresses, such as the petrous temporal, the greater wing of the sphenoid, the sagittal ridge, the occipital protuberance and the glabella. This tensile architecture of the skull has been well described and illustrated by Rowbotham.[12] The more vulnerable thin areas lie in the parietotemporal, lateral frontal and lateral occipital zones.

The average frontal and parietal thickness in a young male is between 6 and 10 mm. The thinnest area is in the temporal bone, where it may be only 4 mm, while in the occipital bone in the midline it may be 15 mm or even more. Rare bone diseases, such as fibrous dysplasia, can lead to extreme thickening of cranium due to overproduction of disorganized, fibrotic bone matrix (Fig. 5.14).

The thickness of the skull is sometimes an issue in courtroom propositions about the special vulnerability of a victim but, unless it is abnormally thin, such theorizing has little forensic relevance as it is well known that fatal brain damage can often occur with an intact skull. It has even been claimed that a thin skull is less likely to fracture, as it is more flexible and can return to normal after distortion without cracking; this is certainly true of the skulls of infants. This may be irrelevant when assessing intracranial damage, however, which is the major issue in head injuries.

It is rarely the skull fracture itself that is a danger to life, but the concomitant effect of transmitted force upon the cranial contents. The presence of a skull fracture is, however, an indication of the severity of the force applied to the head and it is uncommon for a head injury that is sufficiently severe to crack the skull not to cause some intracranial



Figure 5.14 Extreme thickening of the skull due to fibrous dysplasia.

effect, even if it is only transient concussion, though, once again, there are many remarkable exceptions to this generalization.

In skeletal material, fractures of the skull are often seen and the differentiation between ante-mortem injury and post-mortem damage can sometimes be difficult or even impossible in the absence of any soft tissues. Artefactual damage to a skull may be caused during recovery or exhumation, and even stones in the soil can cause erosion and even cracking of the softened, degenerate bone after long burial. Zuo and Zhu have described scanning electron microscopic details of microfractures and collagen damage, which can differentiate ante- from post-mortem injury, but these are unlikely to assist in old decayed material.[13]

The mechanics of skull fracture

The characteristics of human skull to various types of mechanical loading; tension, bending, compression and shear have been extensively studied in isolated human heads and dried skulls as well as in experiments with living animals. For details, the writings of Gurdjian, Webster and Lissner, Evans and Lissner, Evans *et al.*, Lissner and Evans, Rowbotham, Weber, Shapiro *et al.*, and Leestma should be consulted.[10,12,14–19] The mechanical input can be static, e.g. when head is slowly (>200 ms) squeezed or crushed as in earthquakes, or most commonly, when the loading is dynamic and takes place more rapidly (<200 ms; in most cases <20 ms), with or without an impact. These and other workers have shown that:

- When the skull receives a focal impact there is momentary distortion of the shape of the cranium, the extent of which may be surprisingly large, though transient. Infant skulls, which are more pliable and have flexible junctions at suture lines, may distort much more than the more rigid skulls of adults. The area under the point of impact bends inwards and, as the contents of the skull are virtually incompressible, there must consequently be a compensatory distortion or bulging of other areas – the well-known ‘struck hoop’ analogy. Both these intruded and extruded areas can be the site of fracturing if the distortion of the bone exceeds the limits of its elasticity (Fig. 5.15).



Figure 5.15 The ‘struck hoop’ illustration of impact on the skull. There is a momentary deformation, with the area of impact bending inwards and compensatory bulging elsewhere. This sets up stresses in the inner and outer tables.



Figure 5.16 The skull is more susceptible to traction forces than compression, so that convexities tend to fracture during the distortion of the 'struck hoop'.

- When the skull is deformed, compression occurs on the concavity of the curved bone and tension (tearing) forces on the convexity. If the latter exceed the elastic threshold, then fracturing takes place. Thus the inner table will fracture where the skull is indented and the outer table will fracture at the margins of the deformed area. If the forces are great enough, a depressed comminuted fracture will occur (Fig. 5.16).
- In the more common circumstance of a wider impact from a blunt injury, the deformation of the skull is less localized but where the force is sufficient, fractures can still occur from the same mechanism of exceeding the elastic limits. The fractures may be remote from the area of impact, following lines of structural weakness – or may extend from the area of impact, or even commence at a distance and run back to the impact site.

By using skulls coated with a brittle varnish, Gurdjian showed that stress lines developed in the cranium when it was struck and that these corresponded with the fractures that occurred with heavier impacts.[14]

Blows in certain areas of the skull constantly give rise to fractures in specific localities – for instance, impact on the upper temporal or parietotemporal areas cause fissured fractures running obliquely downwards across the temporal area. If heavier, another fracture line tends to run obliquely contralaterally across the vault of the skull.

A heavy impact on the side or top of the head often leads to the vault fracture running into the base of the skull, usually across the floor of the middle cranial fossa along the anterior margin of the petrous temporal bone, to enter the pituitary fossa. In major injuries, this fracture line may often cross the floor of the skull completely to form a 'hinge fracture', separating the base of the skull into two halves (Fig. 5.20). These fractures do not start at the point of impact unless there is also local depressed fracturing; they are initiated at a distance due to the compensatory deformation, but usually run back towards the impact site.



Figure 5.17 Linear fracture of the posterior fossa, due to a fall on the occiput. The fracture typically crosses the thinner bone, avoiding the central buttress and ends near the foramen magnum.

When the frontal area is struck, the usual course for a linear fracture is vertically down the forehead, turning around the orbital margin to run backwards across the floor of the anterior fossa, perhaps into the cribriform plate or air sinuses, or both. A blow or fall onto the occiput may produce a fracture that typically passes vertically or obliquely downwards, just to the side of the midline of the posterior fossa, commonly reaching the foramen magnum (Fig. 5.17). In addition, the contrecoup element of an occipital fall may cause fractures of the orbital plates in the anterior fossa, as a result of transmitted force through the brain itself, though the mechanism is not fully understood.

- When severe local impact causes focal and general deformation, a combination of depressed fractures and radial fracture lines may form a 'spider's-web' pattern.
- When the focal impact is severe, the depressed fracture may follow the actual shape of the impacting object, such as a hammer-head (Fig. 5.28). The shape may follow only that part of the object that drives into the skull – for example, the circular head of the hammer may strike at an acute angle, so only a semicircle of bone will be punched inwards, the opposite edge sloping downwards from an irregular crack.



Figure 5.18 Diagram to illustrate Puppe's rule for the sequence of fractures. The course of a later fracture will be interrupted by an earlier pre-existing fracture line.

The deepest part of the depression will indicate where the weapon first struck; there may be 'terracing' of the margins. The author (BK) has seen an instance where a victim was struck with a hammer through a thin plastic bag enveloping the head. Parallel terracing cracks had opened for a fraction of a second during the blow, sufficient to trap lines of plastic into the multiple defects in the outer table. Where the impact is from a narrow edge or ring, only the outer table may be fractured, being punched into the softer centre without depression of the inner table.

- The presence of hair and scalp markedly cushions the effects of a blow, so that a far heavier impact is required to cause the same damage, compared to a bare skull. The pattern and nature of the skull fractures are, however, the same. It should be noted that the interposition of scalp and hair may slightly alter the dimensions of the skull lesion from a focal blow. For example, the padding effect of the scalp may add a few millimetres in diameter to the depressed fracture caused by a hammer, compared with the actual measured diameter of the hammerhead.
- Where two or more separate fractures occur from successive impacts and meet each other, the sequence of injuries may be determined by 'Puppe's rule', which is really eponymous common sense.[20] The later fracture will terminate at (that is, not cross) the earlier fracture line, which naturally interrupts the cranial distortion, which precedes fracturing (Fig. 5.18).

Types of skull fracture

Arising from the mechanisms described above, it is conventional to classify skull fractures as follows (Figs 5.19, 5.24).


(a)
(b)
(c)
(d)
Secondary fracture in anterior fossa floor
Transverse 'hinge' fracture
Ring fracture around foramen magnum

Figure 5.19 Types of skull fracture: (a) linear fracture; (b) 'spider's-web' fracture; (c) depressed fracture; and (d) base fractures.

Linear fractures

These are straight or curved fracture lines, often of considerable length. They either radiate out from a depressed zone, or arise under or at a distance from the impact area, from bulging deformation. They may involve the inner or outer table, but commonly traverse both.

In a recent retrospective medico-legal study comprising 428 subjects with cranial fractures caused by blunt trauma to the head in Denmark between 1999 and 2004, Jacobsen and Lynnerup found that the most common fracture types were linear (~60 per cent) caused mainly by traffic accidents and falls. Most of the fractures were accompanied by moderate to severe intracranial injuries and/or severe injuries of other organ systems.[21,22]

Depending on the stress contours of that part of the skull and the localization of the impact, the fractures may occur anywhere in the skull, but are especially common in the weak unsupported plates. The temporal, frontal, parietal and occipital plates may all carry single or multiple linear fractures. They may extend downwards into the foramen magnum, across the supraorbital ridges, or into the floor of the skull. A common basal linear fracture is one that passes across the floor of the middle fossa, often following the petrous temporal or greater wing of the sphenoid bone into the pituitary fossa. This frequently continues symmetrically across the other middle fossa separating the base of the skull into two halves, usually being caused by a heavy blow on the side of the head; this lesion was sometimes called the 'motorcyclist's fracture' for obvious reasons (Fig. 5.20).

Linear fractures may follow a horizontal course around the skull, usually from one temporal area to the other via the occiput rather than around the front.



Figure 5.20 A 'hinge' fracture of the base of the skull where the fracture line runs from side to side across the floor of the middle cranial fossa, passing through the pituitary fossa in the midline, following the course of least structural resistance. The victim was a young pedestrian who was hit by a car and then sustained secondary injuries by striking the left side of the head on the ground. This injury is common in road accidents and is sometimes called the 'motorcyclist's fracture'.



Figure 5.21 Springing of the sagittal suture of the skull of an infant. Though there was no skull fracture, the suture line has widened after a fall that caused a subdural haemorrhage.

In children and young adults, a linear fracture may pass into a suture line and cause a 'diastasis' or opening of the weaker seam between the bones (Figs 5.21–5.23). This is most often seen in the sagittal suture between the two parietal bones, but the interfrontal line of weakness left by the earlier fusion of the metopic suture can also re-open under mechanical stress. In infants, especially in the child abuse syndrome, a linear fracture of a parietal bone may reach the sagittal suture and continue across it into the opposite plate. The continuation may be direct or may be 'stepped', so that the two fractures are not in line. This appearance usually means a blow or fall onto the vertex, and the two fractures may be simultaneous but not continuous, explaining the 'stepping'.

Ring fractures

These occur in the posterior fossa around the foramen magnum and are most often caused by a fall from



Figure 5.22 Diastasis or 'springing' of the sagittal suture of a young adult who fell from a height onto the vertex of his head. The opening of the interparietal suture has extended anteriorly along the line of weakness of the fused metopic suture between the two halves of the frontal bone.



Figure 5.23 Post-mortem diastasis of the sutures as an artefact due to freeze-up of the brain simulating intravital skull fracture.

a height onto the feet. If the kinetic energy of the fall is not absorbed by fractures of the legs, pelvis or spine, the impact is transmitted up the cervical spine. This may be rammed into the skull, carrying a circle of occipital bone with it.



Figure 5.24 Linear fractures of the skull in child abuse. Blunt impact near the vertex has caused a double fracture to run down the parietal bone and continue into the temporal area, the course of the fracture being determined by lines of stress and weakness in the skull. The central burr-hole was for the surgical evacuation of a subdural haemorrhage.



Figure 5.25 Pond fracture.

Pond fractures

This is merely a descriptive term for a shallow depressed fracture forming a concave 'pond'. It is more common in the more pliable bones of infants and, indeed, a depression can occur in the absence of a fracture akin to the distortion produced by squeezing a table-tennis ball (Figs 5.25–5.27).

Mosaic or spider's-web fractures

As already described, a comminuted depressed fracture may also have fissures radiating from it, forming a spider's-web or mosaic pattern. The degree of actual depression may be minimal or even absent.



Figure 5.26 Haemorrhage on the brain surface corresponding to the pond fracture in 5.25.



Figure 5.27 Comminuted skull fracture with depression of the central area. This could also be termed a ‘pond fracture’ in that there is an ovoid depressed zone with radiating linear fractures. The head was struck with a heavy piece of wood along the line of the depressed area.



Figure 5.28 A depressed fracture of the skull from a blow with a heavy club hammer. The defect is wedge shaped with a curved anterior border caused by the hammer striking at an angle. The depression is concentrically terraced, with the lowest fragments lacerating the surface of the brain.



Figure 5.29 Multiple fractures due to sword-cut injuries in an archaeological cranium from 14th century. (Milano skeletal collection reproduced by kind permission of Professor C. Cattaneo.)

Depressed fractures

Focal impact causes the outer table to be driven inwards and, unless absorbed in the diploë, the inner table will also usually be intruded into the cranial cavity with all the dangers of direct damage to the contents. Even sharp-edged weapons, such as heavy knives and axes, which may cause a clean-cut defect externally, usually split and deflect flaps downward from the inner table.

With axes and heavy cutting weapons such as swords, there is a characteristic lesion in the bones, whether skull or elsewhere. The initial impact slices cleanly through the bone on one edge, often burnishing the bone to an ivory-like gloss. The rebound removal of the weapon is at a slightly different angle, either from deliberate intent, or from relative movement between bone and blade. This cracks off an irregular fragment of bone of the opposite face so that the residual defect has one smooth and one rough edge. It is often seen in historical and archaeological material from battles or massacres (Fig. 5.29).

The force required to cause fractures of the skull

Skull fracture mechanics have been studied using various approaches and different impact loading scenarios in the analysis and determination of the human response to injury; however, the details are beyond the scope of this book. A comprehensive review of the early and more recent studies of the biomechanics of temporoparietal skull fracture is presented by Yogandan and Pintar.[23] For detailed information see literature in Leestma.[19]

- The adult head weighs between 3 and 6 kg (7–14 lb), averaging 4–5 kg (10 lb). When falling through about 1 metre (3 ft), so that the frontal area strikes a hard surface, impact energy of about 64.5 Nm (47.6 ft-lb) develops. This can cause one or two linear fractures or a mosaic fracture.[14]
- Only a small additional amount of energy above that needed to cause a single crack is required to produce multiple fractures.

In spite of these experimental data, it must never be forgotten that, like all biological phenomena, great variation is encountered. The area of the skull struck, the thickness of the skull, scalp and hair, the direction of the impact and other imponderables, all affect the outcome.

As further discussed in Chapter 22, Weber carried out experiments in which he dropped the bodies of dead infants from a fixed height of only about 82 cm (32 in) onto various hard and soft surfaces.[10] A high proportion sustained skull fractures, both of the parietal and occipital areas, some of them crossing suture lines.

Dangers of fractures of the skull

It has been emphasized that, in the majority of cases, the significance of a fractured skull is an indicator of a substantial insult to the head, with possible injury to the vital contents, rather than the fracture itself being a danger to life.

There are occasions, however, when the fracture itself has dangerous sequelae. The most common is when the crack passes through an embedded meningeal artery, causing a meningeal haemorrhage, which is considered later. A depressed fracture may impinge upon the brain and its membranes, and bone fragments may lacerate or penetrate the brain tissue.

Post-traumatic epilepsy

A late effect of a depressed skull fracture may be ‘post-traumatic epilepsy’. This is of great medico-legal significance, especially in the field of civil litigation where an accident or assault may result in lifelong neurological disability for which very large monetary compensation may be awarded.

Post-traumatic epilepsy usually manifests as tonic and clonic fits, which may be difficult to differentiate from idiopathic epilepsy, if the injury occurred in early life. When fits begin within weeks, or a year or two of a major head injury in a mature person who had never had fits before, the diagnosis is easier, but all cases need expert neurological examination. There must have been a substantial head injury, usually with a depressed fracture impinging on the underlying cortex, often in the parietotemporal area. The epilepsy appears usually within a range of a few weeks to up to 2 years.[24] It is more common in open head injuries when infection has occurred, or when a spicule of bone has penetrated the meninges, as the mesodermal scarring of the cortex that results is more likely to irritate the brain than the astrocytic reaction found in closed head injuries.

Infection following skull fracture

Other complications may occur, even in the absence of depression or comminution. The most common is infection of the meninges, or the development of a brain abscess, or both. Infection can gain access via skull fractures:

- by direct spread through a compound fracture, especially where there is a contaminated scalp injury
- by spread from the nasal cavity when a fracture of the cribriform plate has allowed communication with the anterior fossa. This fracture is not uncommon as part of ‘contrecoup’ lesions, described later. Sometimes the cribriform plate is ruptured by objects entering a nostril and carrying infected material into the cranium: the author (BK) has seen two such fatalities, one from an umbrella ferrule and another from a dirty bamboo garden cane. Another case was seen by PS where a suicide attempt was made with a small calibre pistol. The bullet penetrated the right temple and went through the skull just above the anterior cranial fossa, which was fractured and caused a leakage of the cerebrospinal fluid (CSF) through the nose. The victim recovered well but, in spite of prophylactic treatment with antibiotics, died 1 year later from purulent meningitis
- by spread from fractures that involve a paranasal sinus, such as the frontal or ethmoid, or from the mastoid air cells or middle ear cavity. Basal fractures may allow these spaces, which communicate with the infected outside environment, to reach the meninges, especially when the latter are torn by the traumatic event. A history of leakage of CSF from the nose or ear must alert both clinician and pathologist to the possibility of communicating basal fractures. In any autopsy on a suspected head injury, however slight, care must be taken to remove the dura from the interior of the vault and base so that a close inspection for fracture lines can be made.

Intracranial injuries

The contents of the skull are the most fragile of the vital organs, necessitating their enclosure in the strong bony box of the cranium. Damage may occur either to the neural tissues or to the rich vasculature that surrounds and penetrates those tissues.

Forensic anatomy of the brain membranes

The meninges consist of the dura mater (pachymeninx) and the leptomeninges, the arachnoid and the pia mater (see Fig. 5.13). The *dura* is formed of two layers of tough collagenous tissue, the outer of which is firmly attached to the skull and acts as its internal periosteum. The inner layer merges with the arachnoid, so that in reality there is no true subdural space, only a potential cleavage plane.

The dura forms the falx and tentorium, and the intracranial venous sinuses run within it. Branches of the meningeal arteries course over and through its substance. The dura is penetrated by bridging veins, especially along the vertex and at the tips of the temporal lobes, also to a lesser extent at the frontal and occipital poles, as well as by random vessels elsewhere.

The *arachnoid* is a thin, vascular meshwork that is intimately applied to the inner surface of the dura by means of the 'boundary layer' so that no subdural space exists in normal conditions, though their junction is so tenuous that they are easily split apart. Protrusions of the arachnoid penetrate the walls of the venous sinuses, especially the sagittal sinus, to form the 'arachnoid granulations'. Sheaths of arachnoid follow vessels into the brain as they penetrate into the neural surface. These vessels and thin strands of connective tissue anchor the brain within the subarachnoid space. This is filled with CSF and the width of the space varies from less than a millimetre in the young to a centimetre or more in the old, in whom cerebral atrophy has developed. This means that the anchoring strands and the bridging vessels are longer and more vulnerable to shearing and rotatory stresses. Even though anatomically in the subarachnoid space, rupture of these bridging vessels often manifests itself in the subdural space.

The *pia* is not a true membrane, but a surface feltwork of glial fibres that are inseparable from the underlying brain.

Extradural (epidural) haemorrhage (EDH)

Also known as 'epidural haemorrhage', bleeding between the inner surface of the skull and the dura mater is the least common of the three types of brain membrane haemorrhage and occurs in about 2 per cent of all types of head injury.[25] According to Rowbotham, only about 3 per cent of head injuries have an EDH large enough to be of surgical significance; a similar figure of between 1 and 3 per cent was recorded by Tomlinson.[12,26] Of the 635 fatal head injuries investigated by Adams in Glasgow, 10 per cent had extradural haemorrhages.[27] The mortality rate, even with surgical intervention, averages about 11 per cent under the age of 20 years, rising to between 18 and 40 per cent in later life.

The dura is closely applied to the interior of the skull, forming the endocranium or periosteum. It is so tightly applied to the base of the skull that, except in the posterior fossa, extradural bleeding does not occur over the skull floor. In the vault there is a potential space between the dura and the bone, which can be separated by both arterial and – less often – venous leakage. Most extradural haemorrhages are associated with fractures of the skull, but about 15 per cent occur in intact skulls (Figs 5.30–5.33).[28] According to Harwood-Nash *et al.*, the incidence in children without a fracture is only 1 per cent, though Adams found that half the children with extradural bleeds in his series of over 600 fatal head injuries had no fracture.[27,29] About 10 per cent of EDHs are associated with subdural haemorrhages. Bilateral epidural haemorrhages are rare, but have been recorded.[30–38]



Figure 5.30 Formation of an extradural haemorrhage.



Figure 5.31 A large temporoparietal extradural haemorrhage. The under surface of the scalp on the right shows bruising at the point of impact. There was a linear fracture of the skull passing through the right middle meningeal artery.

The usual site is unilateral in the parietotemporal area, caused by rupture of a branch of the middle meningeal artery where the latter is transected by a fracture line. The posterior branch of this vessel is most commonly involved as it courses diagonally backwards across the squamous temporal bone on the lateral wall of the cranium. The anterior (frontal) branch is rarely the source of bleeding, occurring only twice in Rowbotham's series of 33 cases. The vessel usually lies in a deep osseous groove in the first part of its course. It has been claimed that almost all ruptures occur where the artery is completely roofed over in a bony tunnel so that it is unable to escape damage from a fracture, but observation does not confirm this contention.

Leakage of the high-pressure arterial blood strips back the underlying dura with progressive accumulation of a haematoma, which can reach a volume of several hundred millilitres and cover an appreciable part of the hemicranium. Adams suggests that a minimum volume of 35 ml is needed before clinical signs are apparent, though other writers suggest 100 ml is usually the minimum associated with fatalities. According to Bullock *et al.* an epidural hematoma greater than 30 cm^3 should be surgically evacuated regardless of the patient's Glasgow Coma Scale (GCS) score. An EDH less than 30 cm^3 and with less than a 15-mm thickness and with less than a 5-mm midline shift in patients with a GCS score greater than 8 without focal deficit can be managed non-operatively with serial computed tomographic (CT) scanning and close neurological observation in a neurosurgical center.[39]

In the less common occipital and frontal sites, smaller branches of meningeal arteries may be involved or the bleeding may be from torn venous sinuses, in which case there need not be a fracture. When bleeding is venous, the haematomas rarely reach a large size as the pressure is insufficient to tear back much of the dura. These are uncommon (15 per cent) compared with the arterial EDH (85 per cent), and are seen more frequently in the occipital region, at the point of laceration of venous sinuses. The onset is often delayed by several hours.[40]



Figure 5.32 An extradural haemorrhage in the posterior fossa. This is an unusual site for this type of lesion, as most occur in the temporal or parietal area as a result of tearing of the middle meningeal artery. In this case a fracture line passed down the posterior fossa towards the foramen magnum, but no bleeding point could be identified.



Figure 5.33 A fresh extradural haemorrhage in the temporoparietal area from a fracture crossing the middle meningeal artery. About 85 per cent of such haemorrhages are associated with skull fractures.

The clinical signs of an epidural haemorrhage are classically those of a 'lucid' or 'latent' interval, as there may be recovery from the initial phase of concussion (see below) before sufficient blood accumulates to cause raised intracranial pressure (ICP) and consequent relapse into unconsciousness. This classic picture is so frequently absent, however, that no diagnostic reliance can be placed upon it. The coma from the increasing space-occupying lesion formed by the bleed may follow the period of concussion without a break so that there is no temporary phase of recovery. Only 27 per cent of McKissock's series showed the classic history.[28]

The latent interval may be of variable duration and, as just noted, may not occur if either concussion is prolonged or other brain damage coexists. Half an hour may be enough for the formation of a significant arterial haematoma, though some slow bleeds have taken more than a day to become clinically apparent. In Rowbotham's series, the range was from 2 hours to 7 days, but most were apparent after 4 hours.

Investigations using CT, quoted by Adams, suggest that the old concept of worsening clinical symptoms being caused by the progressive accumulation of blood is incorrect, as computed tomograms show that the major volume of blood may appear soon after the injury and that, as with many space-occupying lesions, clinical signs result from other factors, such as cerebral oedema or diffuse neuronal injury.

Medico-legal considerations of extradural haemorrhage

A medico-legal danger is that a victim may be discharged from the care of a doctor or hospital casualty department when he recovers from his transient concussion only to deteriorate and perhaps die at home; negligence may then be alleged against the unsuspecting doctor. Unfortunately, even when the diagnosis is made, the results of surgical intervention are not good, there being a fatal outcome in more than half the cases operated on. Part of the reason for this poor prognosis is that many victims of EDH also have other damage such as cerebral contusion.

When a victim of a head injury recovers from concussion and then lapses into coma within the first 24 hours, the differential diagnosis is between an extradural or subdural haemorrhage, or cerebral fat embolism, especially if there is other skeletal damage. At autopsy the lesion is self-evident, as most haematomas lie in the temporal or parietal areas, and are opened when the usual saw-cut is made to remove the calvarium. If in the posterior fossa, the dark blood is seen through the raised dura. Wherever it is situated the dimensions and approximate volume should be measured and an estimate made of the inward projection. The brain surface will be flattened or otherwise distorted if the haematoma is of significant size and may have given rise to the usual appearances of raised ICP, described later. The midline of the brain may be shifted laterally if the bleed is large.

Extradural haemorrhage is never a 'contrecoup' injury, this being purely a cerebral tissue lesion.

Heat haematoma

One well-known artefact mimics an EDH. When a head has been exposed to severe external heat sufficient to burn the scalp and perhaps the skull, blood may be extruded from the diploë and venous sinuses into the extradural space to produce a 'heat haematoma' (Fig. 5.34).

The mechanism is obscure, but may be the result of blood being 'boiled' from the diploic layer of bone through emissary veins, or shrinkage of the brain may aspirate blood from the skull. The false haematoma is brown and friable, and the adjacent brain shows hardening and discolouration from the heat.

The importance of the artefact is that it may be mistaken for a true epidural bleed from a head injury, and may mislead the pathologist and investigators into thinking that the fire was started criminally to cover up a fatal assault. As most instances are seen in conflagrations in buildings, there is often a significant level of carboxyhaemoglobin in the body if the death occurred when the fire was in progress. This should be of the same concentration in the heat haematoma as in



Figure 5.34 Fire victim with extensive defect of the carbonized skull showing reddish-brown 'heat haematoma' on the inner surface of the skull and shrunken brain with brain tissue oozing out through a split in the dura.

the peripheral blood; if the victim suffered a head injury before the fire started, then there should be little or no carboxyhaemoglobin in the haematoma.

Subdural haemorrhage

Bleeding beneath the dura is much more common than EDH. It is also proportionately less often associated with a fractured skull, but in absolute numbers far more fractured skulls cover subdural than EDHs. The Glasgow series of 635 fatal head injuries described by Adams included 18 per cent of subdural haematomata.

The lesion is traditionally classified into three types: the acute, the subacute and the chronic. It is unhelpful to subdivide the acute type, however, and only acute and chronic haemorrhage need be considered.

Subdural haemorrhage can occur at any age, but is common at both extremes of life. It is one of the major causes of fatal child abuse and the rediscovery of that syndrome by Caffey consisted of an association of subdural haemorrhage with long-bone fractures.[41] In old people they commonly exist in a chronic form and can be mistaken either for 'strokes' or for senile dementia. The condition is always due to trauma and there is probably no such entity as 'spontaneous subdural haematoma'. Even in states of vascular fragility, such as in senility and in bleeding diatheses, some minimal trauma must precipitate the bleeding even if it was too trivial to be recorded in the history. It is almost certain that minor subdural bleeds, insufficient to give rise to any neurological or clinical symptoms or signs other than a transient headache, occur with the trivial knocks of everyday life. Only when the bleeding is extensive enough to become either a cortical irritant or a space-occupying lesion (probably between 35 and 100 ml) does it become clinically apparent. Of course, many subdural haemorrhages exist in combination with both subarachnoid bleeding and with cerebral damage, making its contribution to the overall symptomatology impossible to assess.



Figure 5.35 Formation of a subdural haematoma.

As with the extradural haematoma, the position of a subdural can never be interpreted as a 'contrecoup' lesion and is thus of no use in differentiating a blow from a fall.

Acute subdural haemorrhage

This is a common sequel to any substantial head injury, and the presence or absence of a fracture is immaterial except as an indicator of trauma to the head. Unlike extradural bleeding, a fracture plays no part in the pathogenesis of the haemorrhage, which arises from torn communicating veins, so called bridging veins that traverse the subdural space between the cortical vessels and the dural sinuses. Less often the sinuses themselves or superficial cerebral arteries give rise to the haemorrhage (Fig. 5.35).[42]

Naturally in an open head injury or when comminuted fractures penetrate the membranes and perhaps the brain itself, subdural bleeding is merely part of a complex that includes subarachnoid bleeding, and cerebral laceration and contusion.

The lesion is often pure, however, being associated with a closed head injury where the only other signs may be scalp bruising – or even nothing at all, as blunt impacts may leave no signs in the scalp, externally or internally, and no skull fracture.

The latter situation is probably the explanation in most of the cases formerly attributed to shaking of the infant. Many paediatricians and pathologists have enthusiastically adopted the shaking aetiology when there was no overt sign of impact (or sometimes even where there was such evidence!) to such an extent that it is frequently proffered as the favoured diagnosis. However, the concept of the shaken-baby subdural has been strongly challenged recently and there is controversy and continuing debate as to the nature and magnitude of the forces and mechanisms of injury involved. It has further been shown that the shearing force (required to rupture subdural vessels) is of the order of 50 times less in shaking than in impact.[43] Thus it is very probable that perhaps the majority of allegedly shaken babies have, in fact, had an occult head impact, which has not left any signs on the scalp, subscalp tissues or skull. An excellent recent review of the pathology and mechanisms of the 'shaken baby' syndrome has been written by Squier.[44]

Subdural bleeding arises from shear stresses in the upper layers of the cerebrum, which moves the bridging veins laterally sufficiently to rupture their junctions at either the cortical veins or the sinus surfaces. It is very rarely possible to identify the bleeding points. Subdural bleeding is most often over the lateral surface of a cerebral hemisphere, high up in the parasagittal area.

As with most intracranial damage, the mechanical cause is a change of velocity of the head, either acceleration or deceleration, almost always with a rotational component.[45] Where a blunt impact strikes the skull, the subdural bleed need not be situated directly under the impact area – it need not even be on the same side of the head. It is sometimes tempting to attribute a localized subdural to either a 'coup' or to a 'contrecoup' effect (see below), but this is an unsafe interpretation. In addition, a subdural haemorrhage – unlike an epidural – is quite mobile. Lesions that have obviously originated high on the parietal area commonly drain down under gravity and cover the whole hemisphere, with a large accumulation in the middle and anterior fossae, and even through the tentorial opening into the posterior fossa.

The haemorrhage may remain fluid or may clot into a firm mass: both modes are commonly present. If the bleeding is relatively slight, then a 'thin-film' subdural may be found. In young babies, according to Squier and Mack, new insights into the anatomy of infant dura suggest an origin within the deep layers of the dura for 'thin-film' subdural bleeding.[46] If the thickness of blood is less than a few millimetres, it cannot be claimed to be a space-occupying lesion, even if the area covered is quite large, as the CSF in the adjacent subarachnoid compartment can be displaced sufficiently to accommodate an equivalent volume of blood.

Again, Adams suggests that, as in any intracranial space-occupying lesion, a minimum volume of about 35 ml is required to cause neurological signs, though other writers prefer a larger volume, such as 100 ml.

Whether this film of fresh blood is a sufficient irritant to cortical activity – as it undoubtedly is in a subarachnoid haemorrhage (SAH) – to be a danger to life, is uncertain. It is difficult to claim that a thin layer of blood in the subdural space is the sole cause of death, but almost inevitably the force that caused the bleeding will also have had a deleterious effect on the brain tissue, even if this is macroscopically occult such as diffuse axonal damage.

As with the EDH, there may be a latent interval before clinical signs and symptoms appear. After the almost inevitable concussion, which may be very brief, the victim may recover, then relapse into deepening stupor and coma when ICP rises as the subdural bleeding proceeds. Associated brain damage may, however, cause uninterrupted coma from the time of injury.

When there is a lucid interval, this may be longer than the average 4 hours of the faster arterial bleeding of the epidural haemorrhage. In fact, there is no upper limit to this interval, as the acute subdural haemorrhage merges into the chronic condition, which may recur after weeks or even months. In severe acute bleeds, as are commonly encountered in criminal cases, such intervals tend to be short or non-existent.

Chronic subdural haematoma

This lesion is most often found in old people, frequently as an incidental finding at autopsy where death was caused by some unrelated condition.

The gross appearance varies with age; recent lesions up to several weeks old are tan or red-brown with a gelatinous membrane covering the surface (Figs 5.36, 5.37). The contents are thick but liquid and may have areas of redder, more recent bleeding. An older haematoma, up to months or even a year old, is firmer, with a tough membrane around both surfaces, resembling a rubber hot water bottle filled with jelly or oil. The contents are liquid and may be brown or even straw coloured. Sometimes the interior may be much firmer and variegated in colour due to bleeds of different ages. Loculation is common, with different coloured fluids or ooze in each locule. The underlying brain will be depressed if the haematoma is large (more than 50–100 ml), and is often stained brown or yellow from altered haemoglobin.



Figure 5.36 Chronic subdural haemorrhage in an old person. Brown liquid escaped from the encapsulated lesion adherent to the meninges leaving a gelatinous outer membrane, as seen. The surface of the right cerebral hemisphere is stained brown from old altered blood and there is some compression of the hemisphere with a midline shift to the left. There was no history of a head injury and no significant neurological deficit.



Figure 5.37 A chronic subdural haemorrhage discovered at an autopsy. The old person was suffering from Alzheimer's disease and was found unconscious on the floor of his apartment. Death about 7 weeks later. The blood was brown and gelatinous, and there was no membrane.

Many such subdural bleeds in old people are small and obviously gave rise to no neurological abnormality; the mere finding of such a small lesion at autopsy should not be used to provide a cause of death, which should be sought elsewhere in the body. Some subdurals are substantial, however, reaching a volume of 100–150 ml. They may still have been asymptomatic, but others give rise to neurological symptoms that may have been ascribed to some other pathological cause. Examples are 'strokes', when unilateral signs were thought to be caused by a cerebral thrombosis or haemorrhage; disordered behaviour of the old person may have been blamed upon senile confusion or dementia, whereas in fact a space-occupying haematoma was really responsible.

The chronic haematoma may become large and press down on the cerebral hemisphere sufficiently to dent and distort the surface. This may progress, as does the large acute haemorrhage, to cause signs of hippocampal or cerebellar tonsillar herniation and all the attendant dangers to the vital centres in the brainstem. The chronic haematoma arises from the acute lesion, which, after an interval, becomes sheathed in a capsule of connective tissue. The haematoma may eventually absorb, it may remain dormant at the same size, or it may enlarge at any later date.

The mechanism of the enlargement is controversial. One common explanation, which seems the most reasonable, is that it occurs from repeated further bleeding, perhaps from new blood vessels that penetrate the mass as part of the healing process. The other theory involves osmosis, said to operate because the centre of the haemorrhage commonly liquefies, forming a haemorrhagic fluid that osmotically attracts into it the CSF from outside the capsule, which acts as a semipermeable membrane.

The first mechanism seems more likely, as areas of fresh bleeding are often found inside a substantial haematoma but, whatever the cause, the final effect is a worsening of the space-occupying effect.

The dating of a subdural haemorrhage

An estimation of the date of onset of a subdural haematoma may have considerable forensic significance, especially if the lesion is obviously mature. There may have been one or more episodes of trauma on record, any of which may have criminal or civil connotations and the opinion of the pathologist will be sought to relate or to eliminate the lesion found from the potential causative event.

For example, in one of the author's (BK) cases an elderly female was struck on the head by intruders and died several weeks later. At autopsy, a large chronic subdural haematoma was the main finding, but the defence sought to show that the haematoma must have been present before the assault by claiming that her confused behaviour over the previous year was caused by the pre-existing intracerebral lesion. Furthermore, in accidents of any type, there may be doubt about whether the subdural haematoma arose as a result of the injury, or whether a pre-existing lesion caused unsteadiness that may have precipitated the accident.

Unfortunately, in spite of several claims to reliable methods of dating subdural haematomata, such estimations are of doubtful value, partly because repetitive bleeding results in varying ages within the same haematoma.

A subdural haematoma gradually changes from dark red to a brownish colour, first being apparent not before 5 days and sometimes not obvious for 10–12 days.[47]

Reaction to subdural bleeding begins within a few hours of onset, when cellular infiltration begins from the dural surface. A delicate ‘neomembrane’, histologically composed of thin-walled capillaries and fibroblastic granulation tissue, grows from the periphery to cover the outer (dural) surface of the clot during the next few days and weeks. If no further enlargement occurs, this capsule becomes more and more fibrous, though rarely does it completely absorb the haematoma by fusing with the outer capsule. According to Crompton, the presence of a membrane firm enough to be picked off with forceps makes the subdural haemorrhage at least 12 days old.

Although claims have been made for accurate dating of subdural haematomas by histological criteria, these cannot be depended upon, especially after a few months, as there is considerable personal variation in healing rates.[48] Also, because of the frequency of repeated subsequent fresh bleeding, attempts at estimating the date of the original bleed are unrealistic. As they are of some use as an approximate guide to age, Munro and Merrit’s histological criteria are summarized briefly here:

- Fibroblasts appear at the margin of the clot within 36 hours and in 4 days the neomembrane adjacent to the dura is a few cells thick. From 5 to 8 days, the membrane becomes well established and fibroblasts migrate from it into the clot.
- By 8 days the membrane is 12–14 cells thick and is visible to the naked eye. From a few days after onset, there is progressive red-cell lysis and after 5 days haemosiderin-laden phagocytes are present, which may be stained by Perls’ reaction.
- From 11 days the clot is subdivided by strands of fibroblasts. By 15 days a membrane is also present on the under surface of the clot and the outer neomembrane is half to one-third the thickness of the dura itself. By day 26 it equals the thickness of the dura, but the inner membrane is still only half as thick.
- Between 1 and 3 months the membrane has lost many fibroblast nuclei and is becoming hyaline. By 6–12 months the membrane becomes thick and fibrous, resembling the dura itself.

A number of later writers have pointed to marked variations in this chronological scheme. Within the first couple of months large sinusoidal vessels appear in the newly formed connective tissue.

From gross appearances, a rough guide is that brown colour changes occur between the first and second week, when a discrete surface membrane becomes obvious. After a month or so a firm capsule develops, forming a cystic cavity containing dark brown, watery fluid. According to Munro, liquefaction of the contents does not occur in less than 3 weeks. Some haematomas remain solid with an organizing blood clot within, often with areas of fresher haemorrhage of different ages.

When a substantial subdural bleed has occurred, the underlying cerebral cortex may be infarcted, caused by either a natural infarct having bled through the arachnoid into the adjacent subdural space or, more often when there has been a head injury, the pressure of the haematoma on cortical blood vessels.[47,49]

Subarachnoid haemorrhage

The third type of brain membrane bleeding is even more common than subdural haemorrhage, but has a mixed aetiology. Whenever there is damage to the cortex, there will be some degree of subarachnoid bleeding, so all penetrating injuries of the brain, as well as many blunt injuries that give rise to extradural or subdural haemorrhage, will be associated with traumatic subarachnoid bleeding.

It is not common, though not unknown, for traumatic subarachnoid bleeding to occur as a pure lesion where there is no cortical contusion, no neck injury, no deep brain lesion and no other membrane haemorrhage. Slight subarachnoid bleeding probably occurs very frequently after a moderate impact upon the head (as with slight subdural bleeding), but as the vast majority of such victims survive, no autopsy evidence is forthcoming. The increased sensitivity of medical imaging techniques, especially nuclear magnetic resonance, can demonstrate such minor bleeds which hitherto went undetected.

The other complicating issue with subarachnoid bleeding is that it frequently occurs as a result of natural disease, especially rupture of vascular malformations of several types. When trauma is also present, the complex association of either the trauma precipitating the rupture or a rupture causing a fall or other accident leading to the trauma has to be considered. This is discussed in a later paragraph.

Although the pathology of SAH is of prime forensic importance, because of the relationship to ruptured berry aneurysm, much of the description is offered in the chapter on sudden natural death (Chapter 25), and only the interaction between trauma and this type of bleeding is discussed here.

Appearances and mechanism of formation

The appearance of SAH caused by trauma varies greatly according the nature and extent of the injury. Where it is secondary to laceration of the brain or extensive cortical contusion, then its localization and severity depend upon the primary injury. Where it arises from a blunt impact, with or without other membrane bleeding or cortical bruising, its position is not a good localizing sign. Once again, its position cannot be interpreted in the same way as contrecoup contusion of the cortex, though some pathologists use its position to claim that a head injury was sustained either from a fall or from a blow to a mobile head; this is unjustified. Although where the circumstances are known, the meningeal bleeding may be seen in the correct location, this is fortuitous and is equally often sited elsewhere.

Blood in the subarachnoid space mixes with the CSF, which dilutes it, makes it less ready to clot and allows more mobility. Thus bleeding high over the cerebral hemispheres readily slides down to cover the brain and enter the basal skull fossae, but usually not in a concentration sufficient to form a thick clot. The sulci tend to collect more blood, especially in the insula. Unlike those with subdural bleeding, survivors from a SAH rapidly dispose of the blood. Haemolysis turns the CSF a xanthochromic yellow and, within weeks, the blood is gone. There may be some residual brown or yellow staining of the pia or arachnoid similar to that seen when a slight subdural bleed leaves its signature on the inner surface of the dura. A positive Perls' reaction for haemosiderin can develop within 36 hours and may remain for months or even years, even after macroscopic discoloration of the membranes has vanished.

This forms a trap for those attempting to date both subdural and subarachnoid haemorrhage in infants, as the common bleeding arising from head-moulding during childbirth may leave a positive haemosiderin reaction for at least 1 year. Thus if a suspected child abuse head injury occurs in the first months of life, histological attempts to date the bleeding by Perls' reaction may be affected by residual haemosiderin from parturition.

Traumatic bleeding in the subarachnoid space is caused by the same mechanism as that in the subdural space, as shear stresses and rotational movements of the brain, described in a later section, shear or rupture the bridging veins that leave the cortex and penetrate the arachnoid, and bleed into the subarachnoid space en route to the large draining veins and sinuses that lie in the dura. In addition, small cortical arteries may contribute much of the leakage. Where laceration, contusion or infarction of the cortex is present, bleeding will come from cortical veins and small arteries directly into the subarachnoid space. It may also arise from intracerebral bleeding breaking out through the cortex. The SAH allegedly caused by damage to the vertebral arteries near the foramen magnum will be discussed under spinal injuries.

The relevance of a SAH in causing death may be difficult to decide, though this is of more importance in the natural variety caused by a ruptured aneurysm (Figs 5.38, 5.39).

In head injuries, death is far more likely to be the result of the other concomitant associated injuries to the brain substance than to a moderate amount of blood in the subarachnoid space.

In the uncommon instances when a substantial SAH seems to be the only sequel of a fatal head injury it must be accepted as the cause of death, though cerebral oedema and microscopic diffuse axonal injury should be excluded as competitors even though this exclusion may be difficult or impossible when death follows rapidly after injury. It is indisputable, however, that



Figure 5.38 Cerebral arteries ('circle of Willis') and common sites for aneurysms.



Figure 5.39 Subarachnoid haemorrhage from a tiny berry aneurysm (arrow) of the right middle cerebral artery.



Figure 5.40 An extensive basal subarachnoid haemorrhage arising from a traumatic tear of a basilovertebral artery caused by a blow on the side of the neck.

sudden death can occur from massive natural SAH in the absence of any traumatic lesions so, by analogy, the pure traumatic bleed – if severe enough – cannot be excluded as a sole cause.

Death can be remarkably rapid when a profuse haemorrhage occurs into the subarachnoid space. The mechanism is not understood, but seems to be confined to those cases where the brainstem is suddenly exposed to a large volume of blood bathing the brainstem in the posterior fossa, usually from a ruptured aneurysm or from a torn basilar or vertebral artery (Fig. 5.40). Numerous instances of victims virtually dropping dead are on record, though many more exhibit the familiar signs of headache, neck stiffness, vomiting and progressive failure of consciousness, before dying at a variable period after the haemorrhage.

Forensic implications of brain membrane haemorrhage

Because of its common occurrence, certain medico-legal problems associated with bleeding into the brain membranes must be considered.

First, the latent or 'lucid' interval in both extradural and subdural haemorrhage may lead to civil suits for negligence where a doctor – usually in a hospital emergency department – discharges an apparently well patient who later dies at home or is readmitted *in extremis*. The clinical aspects cannot be considered here, but suffice to say that it is highly unlikely that such patients would not have suffered concussion, albeit transient. Radiology of the skull is not mandatory if the clinical indications are not present, but failure to X-ray can be a legal impediment for the defence. A subdural haemorrhage is commonly present with an intact skull, though this is uncommon with extradural bleeding.

Both CT and MR are important in the assessment of intracranial traumatic injury, haemorrhage and mass effect. As routine CT of all minor head injury patients would result in a large number of normal CT scans, unnecessary radiation exposure and uneconomic use of health care resources, clinical decision rules are being developed to identify those at risk of intracranial injury.[50]

As already mentioned, the dating of subdural haematomas may be crucial in both criminal and civil cases when it is being either maintained or denied that a particular episode of head injury causes the haematoma. Dogmatic adherence to any accurate histological dating regimen is unjustified, though broad distinctions in terms of days, weeks or months may be justified.

The possibility of a previous bleed being the precipitating factor in some later accidental injury, which then caused further bleeding, must be kept in mind.

Using a membrane haemorrhage to localize an impact can be subject to overinterpretation. An extradural haematoma is almost invariably on the same side as the blow, but because of the distortion of the skull described earlier, the fracture that traverses the meningeal artery can be some distance from the point of impact. Using Gurdjian's work, however, a reasonable estimate of the zone can be offered.

Where subdural or subarachnoid bleeding is concerned, it can be misleading to offer dogmatic opinions about the nature and position of the impact, unless there is scalp or skull damage. Though sometimes it is clear from the presence of a scalp injury that the haemorrhage is either 'coup' or 'contrecoup', there are so many exceptions when the bleeding is unrelated to the site of the blow, that a firm opinion is not justified.

Ruptured berry aneurysm and trauma

A major cause of medico-legal problems is the association of trauma and SAH either from a ruptured pre-existing 'berry' aneurysm or a traumatic aneurysm occurring after blunt, penetrating or iatrogenic head trauma. Traumatic intracerebral aneurysms are rare. The reported incidence is less than 1 per cent, and they are more commonly seen in children. They are caused by direct injury to the vessel wall or by acceleration-induced shear forces and more than half of them are associated with skull fracture.[51] The concept of traumatic intracranial aneurysm was suggested already in the early 19th century and by the 1980s around 100 cases had been recorded in the literature.[52–74] Histologically 'false' aneurysm is the most common form of lesion. In a series of 11 cases of post-traumatic intracranial aneurysms the aetiology was assault in 5 cases, unknown in 2, motor vehicle accident in 2, fall in 1, and iatrogenic (post-operative) in 1.[53] Mao *et al.* assessed a cohort of 2335 patients with cerebral aneurysm from January 1, 2005 to December 31, 2011, and identified 15 patients (0.64 per cent) where the aneurysms were secondary to blunt brain injury. Motor vehicle accidents were the most common cause of injury (10 patients, 66.7 per cent), followed by falls (5 patients, 33.3 per cent).[74]

The interval between the initial injury and rupture can vary between a few hours and years, with an average of 14–21 days.[53,55,69,70,75–77] Ngo *et al.* reported on a rapidly growing traumatic cerebral aneurysm with early SAH in a 40-year-old male, who was hit by a car when riding a scooter.[78] Initial angiography revealed a 2-mm supraclinoid aneurysm, which a week later had grown to 10 mm and was coiled. Two weeks later the aneurysm had enlarged again with partial reopening.

Purgina and Milroy described a case where a 22-year-old male collapsed immediately and became unconscious after being struck on the head when interfering in a fight between two other men.[77] Initial CT scan showed diffuse moderate subarachnoid (SAH) and intraventricular haemorrhage (IVH) as well as a mild hydrocephalus. There was no evidence of obvious aneurysm or fistula in the conventional angiogram. The blood alcohol level on admission was 39 mmol/l. On Day 7, CT angiogram showed a tiny 1.0 mm aneurysm at the origin of the left posterior inferior cerebellar artery (PICA) but the rest of the intracranial arteries appeared normal and the previously seen SAH had completely resolved. By Day 9 when the patient was fully mobilizing and had left the ward to smoke a cigarette, he was reported to go limp and unresponsive. Repeat CT scan showed new IVH and SAH in keeping with a ruptured left PICA aneurysm, the size of which was now shown to be 4.0 × 3.7 mm. Brainstem death was confirmed on Day 12.[77]

A further possibility is that a person with an already spontaneously leaking aneurysm may have a rapidly developing neurological or even behavioural abnormality that leads him into conflict with another person, or into a dangerous physical position, such as a fall or traffic accident. If all this occurs over a short period of time, autopsy may not be able to distinguish the sequence of events and the aneurysmal rupture may be blamed on the trauma instead of the reverse. This may have profound civil as well as criminal legal consequences.

Subarachnoid haemorrhage and alcohol

A factor that is often said to increase the chance of rupture is alcohol, though there is no objective proof of this claim. A high blood alcohol is said to facilitate bursting of an aneurysm because it dilates cerebral blood vessels, increases cerebral blood flow and raises blood pressure.

The latter is not true because alcohol does not raise systolic pressure, though the pulse pressure – the difference between systolic and diastolic – may widen. The fibrous wall of an aneurysm is incapable of dilating, neither can the major basal arteries do so to any appreciable degree, as they possess little muscle in their walls. The pharmacological evidence that alcohol has any significant effect on the cerebral circulation is extremely weak. There is no evidence that alcohol is associated with completely natural SAH from a ruptured aneurysm, though intense physical activity, such as sport or coitus, certainly does predispose to rupture.

Where alcohol and ruptured berry aneurysm are concerned, a more likely explanation is that the association is coincidental – as most altercations resulting in ‘flight, fight and fisticuffs’ are catalysed by alcohol. Many of the cases of ruptured aneurysm and violence occur within and on the pavements outside bars and clubs, where a high blood alcohol is virtually inevitable – but not necessarily causative.

The other aspect of alcohol is that it may cause or contribute to unsteadiness, a fall or some other traumatic event, which itself might lead to rupture of a fragile aneurysm. Ataxia and hypotonia are a feature of acute drunkenness and, together with the aggressive behaviour and alcoholic environment of most physical violence, seem sufficient to account for their circumstantial association.

The rapidity of death in subarachnoid haemorrhage

The immediacy of death is sometimes surprising, especially in association with trauma. It is general clinical experience that the victim of a spontaneous rupture of a berry aneurysm suffers a severe headache, neck stiffness and vomiting, which may resolve or which may progress over hours or days to coma and death. Sudden death is certainly the exception in these clinical cases – but these are from a hospital population, which, by definition, excludes the rapid deaths that reach the mortuary rather than the wards.

In forensic practice, much more rapid demise is not uncommon. For example, the author (BK) recollects that as two males involved in a violent argument in a public house emerged through the outer doors, one struck the other a heavy blow on the head. The victim fell to the ground and never moved again, being certified dead a few minutes later. At autopsy, a typical fresh subarachnoid bleed from a ruptured aneurysm was displayed.

The amount of blood present in most SAHs, from whatever cause, often seems insufficient to constitute a space-occupying lesion, especially as, unlike subdural bleeding, it is able to diffuse more widely over the brain and displace CSF into the spinal theca. The total volume may be considerable, however, and where survival for some hours has occurred, then the typical appearances of raised ICP may be seen at autopsy, though some of this may be contributed by progressive cerebral oedema.

Most rapid deaths exhibit substantial bleeding into the basal cisterns at autopsy, the brainstem and cranial nerve roots being bathed in a thick layer of blood and clot. As blood in the subarachnoid space seems irritant even in small quantities, it seems possible that such sudden irrigation of the medulla may lead to a rapid cardiorespiratory failure. Where the haemorrhage appears less extensive, the mechanism of death is more obscure.

Crompton points out the sensitivity of cerebral arterioles during surgical operations, when a slight touch upon the cortex leads to blanching spasm of the vessels. Subarachnoid bleeding is undoubtedly irritant and a possible reason for the sudden collapse and death is a widespread vascular spasm, which may have an effect on vital centres in the brainstem.

Rotational trauma to the head and upper neck: basilovertebral artery injury

During the last few years it has been recognized that blows to the side of the neck and/or head can give rise to fatal subarachnoid bleeding. This has been attributed to tearing or dissection of a vertebral artery, allowing blood to track along the upper part of the vessel and enter the cranial cavity where the artery penetrates the dural membrane at the foramen magnum.

The evolution of this concept of traumatic subarachnoid bleeding is interesting. Originally, it was thought that most cases had a fracture of the transverse process of the first cervical vertebra, thus damaging the artery contained in the tunnel-like foramen in this bone – indeed, it was often called the ‘CV-One syndrome’.

The hypothesis was that a blow to the side of the neck caused deep injury, usually manifested by skin bruising and bleeding into the muscles deep in the upper neck. This same injury was considered to fracture the transverse process and lead to tearing or dissection of the wall of the contained vertebral artery; blood then tracked upwards and medially to penetrate the dura and emerge inside the subarachnoid space of the posterior cranial fossa to cause a fatal haemorrhage.

Soon cases were being described with no such atlas vertebra fracture, but it was still accepted that mechanical forces, especially of a tilting and rotational nature, could damage the vertebral artery within the foramina of the upper cervical spine and lead to the same dissecting lesion, and hence to fatal SAH. Until very recently, this was the theory – which is still strongly held by many pathologists – that satisfied the aetiological needs of this injury.

However, though it is likely that this classical mechanism does account for some of the deaths, there are several problems with universal acceptance of the hypothesis.

- Many pathologists – including the authors – find it hard to believe that a tiny dissection of a small artery like the vertebral artery – a lesion that often needs serial microscopic sections to confirm – could allow the torrent of blood necessary to enter the cranial cavity and produce a massive haemorrhage (sometimes well in excess of 100 ml) that may cause death within minutes.
- Several instances of a damaged vertebral **vein** have been reported in association with SAH. Because of the very much lower intravascular pressure in a vein compared with an artery, the possibility of this causing a massive intracranial bleed by percolation through the dural fenestration is even less credible than in the case of the artery.
- Increasing numbers of cases are being described with positive evidence of a blow on the side of the neck or head and a large fatal SAH, but with completely intact vertebral arteries.

Thus, if sudden tilting and rotational forces acting on the upper spine and head can lead to SAH without damage to the vertebral vessels, then the causative link is destroyed. Even where vertebral damage is demonstrable, this may be merely a *concomitant* event, the mechanical forces, which primarily led to SAH by direct injury to intracranial vessels also having caused the vertebral artery damage. In other words, the two lesions may in some cases – or for all we know, every case – be a *parallel* phenomenon, not a *cause-and-effect* situation. There may well be a further concomitant effect, in that direct occult brain damage, manifested later by diffuse axonal injury, is the major cause of cerebral dysfunction, both the SAH and the vertebral artery lesion (if there is one) being merely markers of a heavy impact.

In these deaths – and certainly where no lesion at all is discernible in the upper spinal vessels – we need to look elsewhere for an explanation of the subarachnoid bleeding.

Occasionally, this is quite obvious and is situated in the intracranial vertebrobasilar vessels. For example, the author (BK) has seen a wide split in the wall of a vertebral artery *within* the posterior cranial fossa, and another where the vertebral artery was totally avulsed and transected at the internal side of the dural perforation. Both these cases arose as a result of trauma to the side of the neck, and both had a massive SAH with no damage to vessels outside the cranium.

Bostrom *et al*. published details of two cases of rupture of the posterior inferior cerebellar artery due to blunt basal head trauma, and proposed that the term 'traumatic SAH' be abandoned and replaced by the nature and localization of the bleeding site.[79]

The demonstration of intracranial bleeding from the vertebrobasilar system is difficult, as the very process of opening the skull at autopsy and removing the brain, however carefully performed, inevitably causes vascular damage. These artefacts cannot be distinguished from original bleeding points due to ante-mortem trauma.

The use of post-mortem angiography by the injection of radio-opaque contrast medium into the lower vertebral and carotid arteries has not lived up to its original claims. There is almost always diffuse leakage of contrast medium from apparently artefactual defects, and localization of true bleeding points is often obscured by a haze of contrast opacity. However, occasionally the method reveals a specific leak, usually within the posterior cranial fossa.

The original descriptions of and claims for vertebral artery damage as the cause of traumatic SAH were published by Cameron and Mant, Coast and Gee, Contostavlos, Simonsen and others.[80–84] Leadbeatter drew attention to the problems of a universal cause-and-effect relationship; Contostavlos refuted these claims, but did not satisfactorily dispose of the concomitant hypothesis. Pathologists, both from their dissection experience and reading of the literature must make up their own minds on the matter, but should make a critical evaluation of the practicality of a massive subarachnoid bleed appearing, sometimes within minutes, from a tiny dissection of a small artery outside the dural membrane.

As many pathologists still adhere to the original concept of a subcranial vertebral artery causation for traumatic SAH (and in a small number of instances, the evidence is persuasive), the topic is further pursued here, with the over-riding qualification that most traumatic massive meningeal bleeds are due to intracranial causes consequent upon a tilting, rotatory impact upon the head and/or neck, with or without concomitant damage to a vertebral vessel.

Forensic anatomy

The two vertebral arteries arise from each subclavian artery in the region behind the sternoclavicular joints. Each artery ascends behind the common carotid to reach the transverse process of the sixth cervical vertebra. It enters the foramen in that process and passes upwards through each similar foramen until



Figure 5.41 The origin and course of the vertebral arteries. They arise from the subclavian arteries at the level of the sternoclavicular joints and ascend via the foramina in the transverse process.



Figure 5.42 Most vulnerable points for trauma to the vertebral arteries: 1. At penetration of dura. 2. At exit from atlas transverse process. 3. In osseous canal in atlas.



Figure 5.43 The first cervical ('atlas') vertebra viewed from above to show the foramina in the transverse processes through which the vertebral arteries pass. (Reproduced by kind permission of Professor J. Peltonen, Department of Anatomy, University of Turku.)

it emerges from the upper edge of the second (axis) vertebrae. The artery then bends laterally and enters the final foramen in the atlas vertebrae. Emerging on the upper surface, the artery bends back and medially around the superior articular process, and penetrates the posterolateral aspect of the atlanto-occipital membrane and the underlying spinal dura and arachnoid, emerging on the lateral side of the spinal canal just below the foramen magnum. Both arteries then ascend and converge on the ventral surface of the medulla and pons to fuse in the midline to become the basilar artery. Each vertebral artery is often of markedly different size (Figs 5.41–5.43).

Autopsy appearances

With the caveats expressed earlier, the possibility of vertebral artery trauma, concomitant or otherwise, should always be borne in mind when an external bruise is seen on the side of the neck of the victim of a fatal assault. A blow from a fist, foot or blunt weapon may land in the region between the angle of the jaw to the side of the back of the neck, the area below the ear being the most common place to find an injury.

There may be no external sign at all, but on dissection of the neck, a subcutaneous or deep bruise may be found. Unfortunately, this is an area that is not routinely dissected at autopsy, the usual incision for the removal of the neck organs being too far anterior to reveal many of these injuries, which usually lie in the strong neck muscles. This is probably why the syndrome was not recognized until a few years ago – and also an explanation why so many SAHs were said to be due to a berry aneurysm that could not be found because the bursting had destroyed it. No doubt a number of subarachnoid bleeds are due to rupture of non-aneurysmal vessels or to an aneurysm too small to find, but equally, unrecognized head trauma, with or without vertebral artery damage, must have accounted for some of the remainder.

In some autopsies, there is no external neck injury and the cause of death is unknown until the cranium is opened, and a fresh SAH discovered. A decision then needs to be made whether to remove the brain to search for a ruptured berry aneurysm – or begin specialized techniques to seek a rupture of a vertebral artery (described below). If there is a history of assault or other trauma, as opposed to a presumed natural death, then particular methods should be employed. The two avenues are not mutually exclusive, as long as the pathologist is aware of his objectives. The vessels can be clamped off at the base of the brain and the brain removed for a search for an aneurysm or other bleeding-point without spoiling the other techniques.

Mechanism of vertebral artery trauma

When a head is rapidly rotated by a blow that lands at the junction of the head and the neck, there may be a sudden lateral rocking (tilting sideways) at the atlanto-occipital joint, accompanied by rotation of the head. There may also be an element of hyperextension or hyperflexion, the whole episode forming a complex pattern of sudden abnormal movement at the atlanto-occipital junction. It may be that the unexpected impact may allow more unrestrained rotation and angulation of the head, due to absence of anticipatory muscle tensing in the large paravertebral and sternomastoid musles; this may be exacerbated by alcoholic intoxication causing slow protective responses, as most of such episodes occur during altercations related to drinking sessions.

The mechanics are not fully understood and probably differ from case to case but, whatever the mechanism, the vertebral artery can become damaged either:

- in the canal within the first cervical vertebra (whether or not the transverse process is fractured)
- just below the axis, in the space between the transverse processes of the axis and atlas
- as it emerges from the exit of the canal in the atlas to penetrate the spinal dura just below the foramen magnum
- probably much more frequently within the subarachnoid space above the foramen magnum or even higher in its course towards the confluence with the basilar artery – and even the basilar itself. The type of damage is usually a tear or dissection of the wall of the vertebral artery.

Vertebral artery damage was originally said to allow blood to track under arterial pressure within the adventitia and to appear in the subarachnoid space after the vessel has penetrated the dura and arachnoid, though, as discussed above, the likelihood seems slight of these minute lesions allowing the large volume of blood seen in most SAHs to flow through the small periarterial window in the dura.

Autopsy demonstration of basilovertebral artery damage

Over the last few years, after the introduction of various post-mortem imaging techniques, there has been considerable progress in the diagnosis of traumatic brain injury including injuries involving the vascular system.[85–90] Particularly post-mortem computed tomography angiography (PMCTA) has, according to Palmiere *et al.*, shown even a higher sensitivity for detecting the source of haemorrhage than ante-mortem radiological investigations.[91] When circumstantial evidence suggests a SAH following trauma or where a bruise is seen on the side of the neck, vertebral artery damage should be suspected, then confirmed or eliminated and whenever available these imaging techniques should be used.

The first intimation that it may have occurred may be when the skull-cap is removed and a SAH is discovered.

If the view is taken that most SAH following upper neck trauma is due to intracranial vascular damage, then logically it is unnecessary to use time-consuming and laborious procedures, which slow up the completion of the case. In many such deaths, there will be no lesion in the upper cervical spine or extracranial vertebral arteries and even if there is, it is likely to be a concomitant lesion, occurring synchronously, but with no cause–effect relationship with the intracranial vessel rupture.

However, there may be academic satisfaction in demonstrating the concomitant neck lesion, even if it played no role in producing the SAH. In such a case, when the deceased has been in a fight or had some violence applied to the side of his neck, the same routine should be employed.

Different pathologists have different procedures, but the following would be a reasonable method of investigation.

- When post-mortem CT-imaging techniques are not available, radiographs of the upper cervical region, both anteroposterior and lateral, should be taken as these may (rarely) reveal a fracture of the transverse process of the atlas vertebra. Such a fracture is, however, present in only a minority of vertebral artery injuries – and even when present, straight X-rays may not reveal it. Post-mortem angiograms should be taken if facilities exist. There are several methods of performing these. The lower neck is carefully dissected to reach the origins of the vertebral arteries. The best method is to open the subclavian vessels and identify the ostia of the vertebrals, which are the first (most medial) branches of the subclavian arteries. These can be cannulated and contrast media injected, one side at a time, while cervical and skull radiographs are taken. This method tends to fill many intracranial vessels and produce a confused, blurred picture.

- More satisfactorily, the brain should be carefully lifted from the skull and, as soon as the basilar artery is accessible, it should be clamped off with surgical forceps and/or ligated and the brain completely removed as usual after the basilar artery has been transected just above the clamp. Alternatively, each vertebral artery can be clamped or ligated in its terminal course. The angiogram is now performed, either by perfusing up one vessel and forcing contrast medium back down the other via the clamped basilar, or by consecutive injections on either side. Only sufficient medium to fill the system should be introduced to avoid spillage from small branches, which obscure the films. The object is to detect any significant leakage from a vertebral vessel in its upper course, usually within the foramen of the atlas or just outside the atlanto-occipital membrane or within the spinal theca.
- Johnson and Lyall refer to a method by McCarthy *et al.*, who suggested a technique where after removing the cerebral hemispheres and leaving the posterior fossa structures undisturbed, water is injected via the proximal end of one of the extracranial vertebral arteries in the neck with the basilar artery tied off and the contralateral extracranial vertebral artery clamped. The posterior fossa is directly visualized and the procedure as well as the escape and accumulation of fluid recorded by video footage.[92] A similar technique, but using milk instead of water, has been suggested and described in detail by Ikegaya *et al.*[93]
- As by definition, there will have been a substantial SAH, this sometimes makes it difficult to identify and ligate the basilar or vertebral vessels. The brain should be minutely examined for berry aneurysms or other vascular malformations as, if they are present (and ruptured), then further investigation of vertebral artery damage is pointless. Assuming no such bleeding point is found, the upper cervical region is dissected to determine whether the vertebrals have been injured. When no X-ray or angiographic facilities exist, this is the only method available.

The upper cervical spine should be exposed by a posterior approach, which is continued up to meet the transverse scalp incision. The spine should be freed from the surrounding muscles, taking care to detect and record any muscular bruising in the vicinity. It should then be sawn through at about C4 level or lower.

The occipital bone should then be cut through on each side from the transverse skull saw-cut and prolonged down on each side of the foramen magnum, and then across the clivus to release the central part of the floor of the posterior fossa, carrying the foramen magnum and attached upper spine. Alternatively, using a power saw with a wedge-shaped blade, a square may be cut out of the floor of the posterior fossa to detach the spinal block. If possible, X-rays should be taken of the detached portion, as it may be possible to see a fracture of the transverse process of the atlas better than in the intact body.

The block of bone removed should then be decalcified by prolonged immersion in a large volume of 10 per cent formic acid.

After a week, the spine will be soft enough to slice with a scalpel, so that the lateral parts of the transverse processes can be shaved away, taking care not to get near the arterial foramina. The block is then returned to fresh decalcifying fluid for a further week.

Once the bone has been softened enough to be cut easily by a sharp knife, the transverse processes can be further shaved down on each side to the level of the foramina, so exposing the artery in its whole course. Both sides should be so dissected, the last stages being taken deeper and deeper with extreme care to remove the lateral walls of the canals without damaging the underlying vessel. Naturally, the crucial area is in the upper one or two vertebrae, but though laborious, this method provides the most elegant and convincing demonstration.

Specimens should be taken of any obvious or suspicious breach in the wall for histological examination. The usual type of damage is either a frank tear of the intima and media, or a dissection that allows blood to track through the adventitia.

The above-mentioned papers should be consulted for further details of the recommended procedures, but the above is a practical approach to demonstrating vertebral artery lesions. Once again, the relationship must be assessed of any tiny dissection, to the volume of blood found in the cranial meninges – and a decision made as whether this is more likely to be a concomitant injury to intracranial vessels rather than a solitary external vertebral artery lesion.

Head injuries in boxers and contact sport athletes

It has become increasingly apparent in recent years that persons who indulge in boxing and other combat sports or contact sport athletes are at risk of both acute and chronic damage to their brains. The acute injuries are less common but occur during or soon after the fight itself. A number of boxers have died in the ring or after removal to hospital and, in these fatalities by far the most common lesion is a subdural haemorrhage. Extradural bleeding almost never occurs, because boxing injuries rarely cause skull fractures. Occasionally a SAH may occur in rare cases where a berry aneurysm is present.

Much attention has been paid to the chronic changes in boxers' brains, which are very common and give rise to what is generally known as the 'punch-drunk' syndrome. It appears that the length of time for which a boxer has been involved in fighting is more important than the number of serious traumatic events he has suffered. It is a cumulative process and many episodes of minor head injury add up to produce the typical lesions described in the now extensive publications on the subject.[94–104]

There are both anatomical and microscopic lesions in such brains, both in professionals and amateurs exposed over a number of years. The clinical symptoms do not concern the pathologist, but they are explained by the morphological abnormalities. Grossly affected brains may show some cortical atrophy and slight hydrocephalus; the septum pellucidum is characteristically perforated with enlargement of the cavum pellucidum and tearing of the septal leaves. The fornices and adjacent corpus callosum may be thinned or torn, and throughout the brain substance there may be glial scars. Neurons are lost from the cerebellum and the substantia nigra, the latter often losing pigment.

Another change that has intrigued neuropathologists is the development of an Alzheimer's-like condition, with neurofibrillary tangles throughout the cerebral cortex and brainstem, though no senile plaques are present.[105–108] Furthermore, repetitive head traumas have been claimed to cause Parkinson's disease (PD), and it appears that, even though they apparently are not a direct cause of PD, they do pose an additional risk to certain individuals who already are susceptible to PD.[109,110]

Cerebral injuries

Though bleeding or infected scalp injuries, depressed fractures, meningitis and substantial meningeal haemorrhage can themselves cause death, in most fatal head injuries it is damage to the substance of the brain itself that is lethal.

In medico-legal practice it is sometimes difficult to convince lawyers that, in most instances, a victim does not die of a simple fractured skull, but that the fracture is evidence only of a substantial head injury, being a 'marker' for concomitant brain damage, which was the real lethal lesion. Similar problems of communication exist with a fracture of the hyoid bone in strangulation, lay persons often being under the misapprehension that a broken hyoid is a mortal injury, instead of merely being an inconstant marker of pressure on the neck.

The neuropathology of brain damage is a large and complex subject, the more subtle varieties requiring both specialist techniques for demonstration and expert knowledge for interpretation. The textbooks of Love *et al.*, Itabashi *et al.* and Leestma are recommended for detailed description and discussion of cerebral trauma.[19,111,112]

The mechanisms of production of some traumatic lesions are matters of conflicting theories, but the forensic pathologist still has to be aware of the general principles of causation in order to offer some interpretation of the injuries.

As always, caution has to be employed, as both the pathological and clinical manifestations of a head injury may appear to be at variance with the degree of force applied to the head. There is a wide range of lesions from a given insult to the head and it is dangerous to be too dogmatic in theorizing about the magnitude of an injury that gave rise to the demonstrable lesions.

It is similarly unwise to hypothesize too firmly about what clinical features must have occurred when the head injury was sustained – for example, quite severe head injuries have been known to be unaccompanied by concussion, while other apparently slight damage has often been followed by prolonged unconsciousness even ending in death. The aphorism of Munro must be kept in mind that: any type of head injury can give rise to any type of intracranial damage.[113]



Figure 5.44 Mechanical events that contribute to primary brain injury. (From *Greenfield's Neuropathology*, 7th edn, 2002; graph reproduced by kind permission from Arnold.).

The mechanism of brain damage

The brain may be injured in the following ways (Fig. 5.44):

- By direct intrusion, either by a foreign object such as a penetrating weapon, bullet or other missile – or fragments of skull in a compound fracture where the skull is disrupted. In these open wounds the mechanism of the damage to the brain is obvious, though of course it may be compounded by the second type of injury described below.
- By deformation of the brain in closed head injuries. Here the mechanism of injury is complicated and variable, with several competing theories of causation that have been put forward since the eighteenth century public debate was held in 1766 in Paris, where rival theories of coup and contrecoup brain damage were hotly defended at the Academy of Surgeons.[114,115]

The brain is almost incompressible and purely axial impact may give rise to little or no damage. It is extremely rare, however, for an impact not to impart some rotatory movement and it seems agreed that this component is the main culprit in causing brain damage. What is now clear is that no actual blow or fall need be suffered by the head to cause severe and even fatal brain damage. It is the change in velocity – either acceleration or deceleration – with a rotational rather than solely axial element, that leads to damage. The surface of the head need never contact any hard object or surface, though recent research indicates that the quantum of energy delivered by impact is of a far greater order of magnitude than non-impact violence, which lessens the former conviction that shaking, as in child abuse, is a common and potent mechanism in the production of intracranial damage.

In most head injuries – notably traffic accidents and falls – there is marked deceleration of the moving head on contact with a fixed surface but, in many criminal and combat injuries, the head is accelerated by a blow. In either case the initial sudden change in velocity is applied to the scalp and skull, the latter then transmitting the change to the brain via the anatomical suspensory system within the cranium. This system is slightly flexible and consists of the falx and tentorium, which divide the cranial cavity into three major compartments; these contain the two cerebral hemispheres, the cerebellum and the brainstem. When violent relative movements take place between the brain and the dura, forming the partitions of the cranium, the cerebral tissue can become damaged against both the sharp edges and the flat surface of these membranes. In addition, vessels traversing the subdural and subarachnoid spaces can be torn by such relative movements, especially in old people where cerebral atrophy may have widened these spaces.

Among the competing theories of impact brain damage are:

- the rotational shear force theory
- the pressure gradient theory
- the vibration theory
- the transmitted wave force theory
- the brain displacement theory
- the skull deformation theory.

These hypotheses overlap and most are correct in some aspect. Because experiments on primates and mechanical models have been pursued vigorously in recent years, it is now widely accepted that there are marked pressure changes within the cranium on impact.[116] When a head falls against the ground, pressure momentarily increases at the impact point but falls to a negative value diametrically opposite. As these suction or cavitation effects are more damaging to neural and meningeal tissue than pressure, this is good evidence for claiming that contrecoup damage is largely a result of this vacuum effect.

The actual physical disruption of cerebral tissue is caused, according to both Gurdjian and Holbourn, by one or more of the following processes:

1. compression of the constituent units, by their being forced together
2. tension of the units, which pulls them apart
3. sliding or 'shear' strains, which move adjacent strata of tissue laterally. The usual homely example is given of a pack of playing cards being displaced, so that each card slides upon its neighbour.

Transient deformation of the skull almost certainly contributes to brain damage.[12] The area of the skull beneath an impact becomes momentarily depressed even if it does not fracture and therefore may impinge on the underlying brain causing compression, as in 1, above. This is responsible for the typical cone-shaped contusions on the cortex, with the base at the surface, as the impact – possibly via short-lived oscillations of decreasing amplitude – injures the cortex and passes a diminishing force down into the deeper layers.

Simultaneously, other areas of the skull must bulge outward to accommodate the deformation – the so-called 'struck-hoop' action – when it is suggested that a 'rarefaction' remote from the impact may cause tension damage, as in 2, above.

More important is 3, being laminar deformity or 'shear stress' caused by the angular rotation of the head. As the head is pivoted on the first cervical vertebra, almost any impact on jaw, face or cranium will produce an angular momentum, the acceleration being conveyed first to the skull.

Alternatively, if the head is moving and is suddenly arrested, then the skull will decelerate first and the momentum of the brain will cause it to continue in motion, again almost certainly with some rotatory component.

In either the deceleration or acceleration mode, the skull and brain cannot change their velocities simultaneously and the brain will speed up or slow down only by virtue of the restraint provided by the dural septa and the configuration of the interior of the skull. In other words, the brain is either retarded or set into motion secondarily by the skull, especially by the dural septa and the bony prominences.

This restraint will occur first – and with maximum effect – on the most superficial layers of the cortex. These in turn will drag on the next deepest layer and so on until the difference in velocity is equalized – but this will have been at the expense of laminar tearing of the cerebral tissue and its associated blood vessels. In addition to this shearing damage, the brain may be forced against the sharp edge of the tentorial opening and the lower edge of the falx, causing damage to the base of the cerebrum, the corpus callosum and the brainstem. Impact against the side wall of the skull and against the falx may cause diffuse contusion of the cortex. The cerebellum tends to suffer less damage, as it is much smaller and lighter than the cerebrum and there is less room for relative movement in the more tightly enclosed posterior fossa. The configuration of the interior of the cranium is thought to be partly responsible for the common localization of cerebral damage at the tips and undersurface of the frontal and temporal lobes. The rough floor of the anterior fossa, the sharp edge of the wing of the sphenoid and the massive bar of the petrous temporal bone are in contrast to the smooth inner surface of the vault of the skull.

Cerebral contusion

When either linear or, more often, laminar stresses are applied to the cortex, this soft tissue may disrupt. Part of the injury is directly upon the neurocellular structure, but damage to vessels is an important component. If the cortex still retains its shape, but is bruised and swollen, this constitutes 'contusion'. A greater degree of disruption, sufficient to produce macroscopic tearing, is termed 'laceration', but the difference is only one of degree. In gross head injuries, such as crushing, missile wounds and other major penetration, the degree of laceration may lead to partial or even complete extrusion of the brain from the cranial cavity.

In the usual type of cortical contusion seen in a closed head injury, the cortex is blue or red from haemorrhage, though if survival has lasted for some time, there may be added discolouration from associated cortical infarction. The haemorrhage may be diffuse or may be punctate and is often a mottled purplish red when confined to the cortex. Extension into the underlying white matter tends to be pure red in fresh lesions. The lesion is often wedge-shaped, with the base on the surface, tapering away into the deeper layers.

Cerebral laceration

Laceration of the cortex is an extension in severity of contusion in which mechanical separation of the tissue can be seen. When widespread, but relatively superficial, the cortex appears to have a 'red velvet' appearance, which becomes progressively more tattered as the severity increases.

When it is even more severe, the cerebral surface becomes fissured, fragments of cortex may detach and deep lacerations run into the depths of the hemisphere, sometimes reaching even the basal ganglia or ventricles. There may be deep haemorrhage and – especially in the frontal and temporal lobes – the lacerations may be continuous with areas of traumatic haemorrhage. In cerebral lacerations and most contusions, the pia mater and often the arachnoid are torn, so that blood from damaged cortical vessels leaks into the subarachnoid and even subdural spaces. The corpus callosum is commonly torn, especially at its posterior end. This must be distinguished from damage caused by clumsy removal of the brain at autopsy (as must tears of the cerebral peduncles), but when genuine, may represent either a guillotine effect of the free lower edge of the falx or differential lateral movement of one hemisphere relative to the other, again because of unilateral restraint by the falx. Lacerations and contusions are most often found in those areas of the brain where the cortex is most likely to come into contact with irregularities in the internal profile of the skull. The undersurface of the temporal lobes and the orbital surface of the frontal lobes suffer most often.

Traumatic intracerebral haemorrhage

Substantial areas of haemorrhage, either infiltrating the brain tissue or forming actual haematomas, are common in severe head injuries. Some are primary, occurring at the time of impact or soon afterwards; others are secondary and caused by changes in ICP or bleeding into infarcts caused by vascular damage. These have been seen all more often ever since artificial ventilation has been available, as victims of severe head injuries survive longer so that there is time for secondary lesions to become apparent.

In the cerebral hemispheres, deep haemorrhage can be caused by coup or contrecoup mechanisms (see below) and may be situated anywhere within the hemispheres. They may rupture into the ventricular system or through the overlying cortex. In some severe contrecoup lesions, there may be large haematomas in one or both frontal lobes with overlying cortical contusion and laceration. These may rupture through the cortex into the meningeal spaces, forming what is sometimes called a ‘burst lobe’. Such haemorrhages sometimes pose a problem for the pathologist when they occur in older subjects, especially those with hypertension and perhaps cerebral atherosclerosis. When a scalp injury is present – and perhaps even a fractured skull – it may be difficult to decide if a head injury (such as a fall) was responsible for the cerebral haemorrhage, or whether a sudden ‘stroke’ caused by a natural cerebral haemorrhage resulted in the fall. The problem is discussed further in the chapter on natural death, but briefly, the presence of left ventricular (cardiac) hypertrophy, a history of hypertension and the site of the (usually solitary) haemorrhage tends to point to a natural bleed. This is especially so if the large size of the lesion seems inconsistent with the degree of head injury sustained. Hypertensive lesions tend to be in the putamen, thalamus, external capsule, pons and cerebellum, and are more often occipital than frontal or temporal. Having said that, on occasions it can be impossible to differentiate the two conditions.

Primary brainstem haemorrhage

Secondary brainstem bleeding is dealt with under ‘cerebral oedema’ so here we are concerned with haemorrhage that occurs at the time of injury. As mentioned above, hypertensive haemorrhages not associated with trauma can occur in the brainstem, especially the pons. These tend to be large, explosive lesions that greatly swell the pons and disrupt the central part of the stem, usually with a ragged rim of white matter around the periphery. Traumatic haemorrhage in the brainstem is often a well-circumscribed lesion, sometimes rounded, which lies laterally in the tegmentum, the shape of the midbrain being undistorted (unlike a secondary bleed into an elongated stem).

The typical site is between the aqueduct and the outer end of the substantia nigra. Primary brainstem haemorrhages are usually associated with occipital impacts and the victim is often unconscious from the time of the injury, as opposed to the lucid interval and gradual decline of those who suffer secondary stem lesions because of a developing cerebral oedema or space-occupying haematoma.

Coup and contrecoup damage

Whatever the underlying mechanics of cerebral damage, one aspect is of considerable practical importance to the pathologist. When a mobile head is struck with an object, the site of maximum cortical contusion is most likely to be beneath or at least on the same side as the blow. This is the so-called ‘coup’ lesion. When a moving head is suddenly decelerated, as in a fall, though there might still be a ‘coup’ lesion at the site of impact, there is often cortical damage on the opposite side of the brain – the ‘contrecoup’ lesion (Figs 5.45–5.47).

The mechanism of the ‘coup’ and ‘contrecoup’ injuries has long been debated – at least since the time of the famous Paris meeting of 1766. The controversy has been continued, but no satisfactory resolution has been agreed though the work on ICPs by Yanagida *et al.* seemed to provide proof that a ‘vacuum’ occurs at the contrecoup site.[116–118] More recently Halabieh and Wan investigated the positive pressure theory, the negative pressure theory, and the CSF theory by using a mathematical model of the human head, which consisted of the rigid skull, the CSF and the solid brain. Based on their numerical simulations together with pathological findings they concluded that no one theory can explain the mechanics of the brain during the different types of accident scenarios.[119,120]



Figure 5.45 (a) 'Coup' brain damage to fixed head. (b) 'Contrecoup' brain damage to moving (decelerated) head.



Figure 5.46 Typical contrecoup injury to the tips of the frontal and, to a lesser extent, temporal lobes of a brain. The victim fell backwards, striking the right side of his occiput indicated by the haemorrhage of the right crebellar lobe. Due to the oblique direction of the force, from the primary impact to the right cerebellar lobe towards the tip of the left frontal lobe, the injuries are more extensive on the left side.



Figure 5.47 Contusion of the right cerebellar lobe at the site of the primary impact of the case shown in 5.46.

The following practical points should be considered:

- There may be no coup damage at all, only contrecoup.
- There need be no fracture of skull, even in the presence of severe coup and contrecoup lesions.
- The most common site for contrecoup injury is in the frontal and temporal lobes. It is often at the tips and on the undersurface of these lobes, and may be symmetrical, if a fall on the occiput has occurred.
- In temporal or parietal impacts, the contrecoup lesions are likely to be diametrically opposite on the contralateral surface of the brain, but exact geometrical correspondence is not necessarily present.
- It is virtually unknown for a fall on the frontal region to produce occipital contrecoup. This is thought to be due to the anatomical configuration of the floor of the cranium, but the reasons are by no means understood.
- In a temporal impact, the contrecoup damage may be not be on the contralateral hemisphere, but on the opposite side of the ipsilateral hemisphere from impact against the falx cerebri.
- The degree of contrecoup damage may be severe, sufficient to cause blood-filled cavitation in the deep cortex and underlying white matter, especially in the frontal lobes and tips of the temporal lobes.
- With severe frontal contrecoup from a fall on the occiput, the transmitted force may be sufficient to fracture the thin bone of the floor of the anterior fossa. Such cracks in the roofs of the orbits may allow meningeal haemorrhage to seep into the orbits and appear as 'black eyes'. In assaults where a fall has occurred, care must be taken not to attribute such periorbital bleeding to direct punches.

- Though contrecoup contusion is classically caused by deceleration of a falling head, it can also occur when a *fixed* head is struck. If the victim is already lying on the ground or against some other unyielding surface, a heavy blow on the upper side may cause typical contrecoup lesions either in the contralateral temporal or parietal cortex, or against the falx on the inner side of the ipsilateral lobe. In these circumstances, there is often coup damage as well. No external scalp injury need be visible.
- The interpretation of contrecoup lesions is most reliable in the form of cortical contusions or lacerations. Meningeal haemorrhage, either subdural or subarachnoid, may also arise in association with a contrecoup lesion, but its diagnostic value is virtually nil compared with cortical damage when interpreting a falling or fixed head injury. Where no associated cortical contusion is present, it is quite unsafe to rely upon a unilateral meningeal haemorrhage as an indicator of the type of head injury.

Concussion

Concussion is a clinical, not a pathological entity, but the pathologist must consider it, as it is related to intracranial lesions and he is often questioned about it in court proceedings. Concussion, according to Wilson, is 'a disorder of cerebral function which follows immediately upon the impact of a force to the head'.[121] A more full definition is offered by Trotter: 'a transient paralytic state due to head injury which is of instantaneous onset, does not show any evidence of structural cerebral injury and is always followed by amnesia from the actual moment of the accident'.[122]

More recently, as concussion is a common medical problem in sports, sports-physicians have been actively involved in concussion research. The most recent concussion consensus statement, developed by a collaboration of six major professional associations concerned about clinical sports medicine issues in the USA, defines concussion as follows:[123]

Concussion or mild traumatic brain injury (mTBI) is a pathophysiological process affecting the brain induced by direct or indirect biomechanical forces. Common features include the following:

- Rapid onset of usually short-lived neurological impairment, which typically resolves spontaneously.
- Acute clinical symptoms that usually reflect a functional disturbance rather than structural injury.
- A range of clinical symptoms that may or may not involve loss of consciousness (LOC).

Routine neuroimaging studies are typically normal.

It is an extremely common, but not inevitable, sequel to any significant mechanical insult to the brain. Though in general terms its duration is loosely related to the severity of the injury, there are many exceptions. Gross skull and brain damage have occurred with little or no apparent concussion, though concussion may be so transient that the subject may not even fall to the ground. Relatively minor head injuries have given rise to prolonged unconsciousness so, once again, it is most unwise to be dogmatic about retrospective estimates of concussion.

True concussion may last for seconds or minutes. If prolonged unconsciousness extends into hours, days or longer, then there is likely to be some structural brain damage. Occasionally what appears to be simple concussion proves to be fatal, causing respiratory paralysis, though at autopsy no significant lesions are found.

Where a victim of 'simple' concussion dies of some incidental non-neurological condition, autopsy usually reveals no macroscopic damage, though sometimes there is slight cerebral oedema and scattered non-specific petechial haemorrhages may be found. There seems to be a connection between concussion and rotatory movements of the head, which are usually responsible for obvious structural damage because, when a head is fixed before impact, loss of consciousness may not occur. The classic example is trapping of a head against a wall or being jammed between buffers.

That shear stresses are instrumental in causing neuron damage seems confirmed by the frequency in which concussion occurs in boxing contests, where a blow on the jaw is the ultimate in producing a rotational movement of the cranium.

Concussion may be followed by post-concussive symptoms (PCS) characterized by early and late clinical symptoms, such as headaches, dizziness, unsteadiness and anxiety. These are subjective and conventional imaging is typically unremarkable. Sports-related concussions have been shown to cause neurometabolic changes in both the acute and subacute phases of head injury.[124] According to recent views, the mechanical insult causes mitochondrial dysfunction and initiates complex metabolic events leading to perturbation of the maintenance of metabolic equilibrium within the neurons.[124,125] PCS seems a genuine phenomenon, though it has been pointed out that it may be overlain by a 'compensation syndrome' whilst civil litigation is in progress over responsibility for the accident, which often clears up rapidly once the claim is settled.

Quite recently, Kirov *et al*. tested in a retrospective study whether diffuse axonal abnormalities quantified with three-dimensional (3D) proton magnetic resonance spectroscopic imaging (1H-MRSI) correlated with patients' PCS.[126] They found that the PCS-positive patients had lower concentrations of N-acetylaspartate (NAA) in white matter, suggesting a potential biomarker role in post-traumatic biochemical damage.[125,126]

Retrograde amnesia is almost inevitably associated with concussion, though, like concussion itself, it may be so transient as to escape notice. A protective mechanism, it seems to be caused by loss of sensory input before the latter is transferred to permanent memory storage in the brain. Though commonly only of minutes' duration, it can extend to several days before the head injury. Though there is often a later recovery of much of this lost period, the memory of events immediately before the incident rarely returns, which may fortuitously be a protective device.

Diffuse neuronal and axonal injury

According to Graham *et al*., diffuse brain damage exists in four principal forms: diffuse vascular injury, diffuse axonal injury, hypoxic brain damage and diffuse brain swelling.[127] Diffuse vascular injury consists of multiple small haemorrhages throughout the brain and is virtually restricted to patients, who die within 24 hours, whereas the latter three are encountered in patients who survive long enough to reach the hospital. Recent research and new immunohistochemical methods have shown that traumatic axonal injury is much more common than previously realized, and that axons can also be diffusely damaged by other processes than head injury. Therefore, Geddes *et al*. suggested new definitions of the terminology to get rid of the incoherent use of terms in the literature:[128]

- Axonal injury (AI) is a non-specific term referring to damage to axons of any aetiology.
- Traumatic axonal injury (TAI) is a damage to axons caused by trauma, which may vary from small foci of axons to more widespread brain damage, diffuse TAI is the most severe form of traumatic axonal damage (originally termed 'diffuse axonal injury, DAI').
- Diffuse axonal injury (DAI), first described as a clinicopathological syndrome of widespread axonal damage throughout the brain, including the brainstem, should not be used as a term without reference to the aetiology, because axonal injury may be caused by other pathological processes.

Experimental work has suggested that DAI is primarily a non-impact rotational acceleration–deceleration phenomenon, deformation by stretching probably being the most significant factor. A low level of injury causes transient changes in the permeability of the axolemma, gradually leading to ionic changes, accumulation of fluid and axonal swelling and eventually, with an increasing grade of injury, to intracellular Ca^{2+} accumulation, proteolysis and collapse of the cytoskeleton.

The disruption of axons leads to bulbous and clubbed 'retraction balls or globes' in the axons in the cerebral hemispheres, cerebellum and brainstem. Disturbance of axoplasmic transport causes accumulation of substances in damaged axons that can be demonstrated immunohistochemically. At present, β-amyloid precursor protein (βAPP) is considered to be the most reliable indicator of axonal damage, revealing axonal injury within 2–3 hours of the insult, whereas it takes about 12–18 hours for axonal bulbs to become visible on routine or silver stains. However, one should keep in mind that βAPP is not specific to head injury but is an indicator of derangement of fast axonal transport, which has also been demonstrated in other pathological conditions.

It is preferable to examine the brain after proper fixation, usually after 10–14 days in 4 per cent buffered formaldehyde and, where possible, consultation with a neuropathologist with experience in forensic practice. Due to the diffuse nature of the axonal injury, extensive and systematic sampling is essential, as the diagnostic yield is directly related to the number of blocks taken. In addition to any obvious focal pathology, the minimum set of samples should include: 1) corpus callosum with parasagittal posterior frontal white matter; 2) splenium of the corpus callosum; 3) deep grey matter to include posterior limb of the internal capsule; 4) cerebellar hemisphere; 5) midbrain including the decussation of superior cerebellar peduncle; and 6) pons including superior or middle cerebellar peduncles. In addition to these, it may also be advisable to include: 7) corpus callosum with parasagittal anterior frontal white matter; and 8) temporal lobe including hippocampus.[128]

Retraction globes are most numerous in the corpus callosum, the superior peduncles, the parasagittal white matter, the medial lemnisci and the corticospinal tracts, but can be seen anywhere in the white matter. The retraction globes or axonal bulbs have been shown to lose positive staining for βAPP after about 1 week, but to persist in adjacent varicose axons up to 30 days. After some weeks in those who survive long enough, clusters of microglia, presumably as part of a repair process, congregate at the site of ruptured axons. These are best seen in 20 μm thick sections stained with cresyl violet or more specifically using CD68 or Iba1 immunostaining. One problem with the microscopic evidence of both microglial clusters as well as DAI (as demonstrated by βAPP expression), is that neither of them is specific as a marker for trauma: retraction globes may also be seen around the periphery of natural lesions such as cerebral infarcts and haemorrhages and microglial clusters have been reported in viral/human immunodeficiency virus (HIV) encephalitis, previous global hypoxia and fat embolism. Geddes *et al.* conclude in their excellent review that 'the demonstration of traumatic axonal damage is likely to be of limited use in most forensic situations, except perhaps to confirm that there has been a head injury'.[128]

Cerebral oedema

Swelling of the brain tissue may be a local phenomenon around almost any lesion, be it contusion, laceration, tumour or infarct, but here we are more concerned with generalized oedema. Swelling of the brain is extremely common after a substantial head injury, especially in children. Though it is an almost inevitable accompaniment of almost all intracerebral damage as either a local or general phenomenon, it can occur as the sole abnormality – and not infrequently prove fatal, particularly in young victims. It is the most common cause of raised ICP, being seen more often than localized space-occupying lesions such as haematomas and tumours, though of course these often coexist with cerebral oedema.

Uncontrollable swelling and subsequent rise in ICP is the single most frequent cause of death after severe traumatic brain injury.[42,129] Oedema may be vasogenic, hydrostatic, cytotoxic, osmotic or hydrocephalic (Table 5.1).

In vasogenic oedema the permeability of the blood–brain barrier (BBB) increases as the result of an injury to the vasculature due to tumour, trauma, infection, intracerebral haemorrhage or infarction. Oedema fluid is primarily in the extracellular space and tends to occur in the white matter.

Table 5.1 Types of cerebral oedema

Type	Oedema location	Blood–brain barrier permeability	Mechanism	Clinical situations
Vasogenic	Extracellular White matter	Increased	Increased permeability of vessel walls	Tumour, trauma, infection, abscess, ICH, infarction
Hydrostatic	Extracellular White and grey matter	Increased	Increased blood pressure	Hypertensive encephalopathy, epileptic seizure
Cytotoxic	Intracellular (mainly) Grey matter (mainly)	Normal	Lack of energy or toxic influence leads to malfunction of Na/K pump	Hypoxia/ischaemia, Reye's syndrome, some intoxications (e.g. cyanide)
Osmotic	Intra- and extracellular White and grey matter	Normal	Hypo-osmolarity of plasm	Hyponatraemia, SIADH, excessive infusion therapy, water intoxication, freshwater drowning
Hydrocephalic	Extracellular Periventricular white matter	Normal	Leakage of pressurized liquor into periventricular brain tissue	High-pressure hydrocephalus, pseudotumour cerebri (idiopathic intracranial hypertension [IIH])

ICH: intracerebral haemorrhage; SIADH: syndrome of inappropriate antidiuretic hormone hypersecretion.
Adapted from Paetau A, Öhman J, Kalimo H. Aivoedeema. In: Mäkinen M, Carpén O, Kosma V-M, Lehto V-P, Paavonen T, Stenbäck F (eds). *Patologia, Kustannus Oy Duodecim*, 2012 with permission.

In hydrostatic oedema BBB fails because of increased blood pressure, as in hypertensive encephalopathy or in epileptic seizure. The excess water is mainly extracellular both in white and grey matter.

Cytotoxic oedema results from disturbance of the energy-dependent transmembrane ionic pumps, most commonly due to ischaemia as a result of vascular occlusion or other causes, such as traumatic brain injury, metabolic disorders or certain intoxications.[130] This leads to intracellular accumulation of fluid, mainly in the grey matter, due to its high metabolic activity and greater astrocyte density.

Osmotic oedema results from hypo-osmolality of blood plasma in conditions where the BBB is intact but blood becomes too diluted, e.g. because of freshwater drowning, water intoxication or excessive administration of intravenous fluids or the syndrome of inappropriate antidiuretic hormone hypersecretion (SIADH).

Hydrocephalic or interstitial oedema is caused by leakage of pressurized CSF through the ependyma into periventricular brain tissue because of obstruction within the ventricular system or the obstruction is distal to the ventricles, e.g. decreased transfer of CSF into the subarachnoid space, impaired flow of CSF in constricted subarachnoid space or hindered reabsorption of CSF via arachnoid granulations into venous blood.

The autopsy features of cerebral oedema are readily recognized. On removing the calvarium, the dura is stretched and tense, the brain bulging through the first incision in the membrane. The gyri are pale and flattened, and the sulci filled, giving the normally corrugated cerebral surface a smoothness that can easily be felt at autopsy. The cut surface is pale and, especially in children, the ventricles may be reduced to slits by the swelling of the adjacent white matter.

Severe cerebral oedema causes the larger volume cerebral hemispheres to press down upon the tentorium and herniate through the tentorial opening. The hippocampal gyrus may impact in the opening, lesser degrees causing grooving of the hippocampal unci. Both these effects may lead to haemorrhage and necrosis at the sites of pressure, especially where the sharp edge of the tentorium cuts into the cerebral tissue. The tonsils of the cerebellum may be impacted or ‘coned’ into the foramen magnum, and sometimes are forced down into the upper part of the spinal canal. The pathologist must be careful not to mistake the normal anatomical grooving that often exists around the cerebellar tonsils for ‘coning’. There should be other signs of brain swelling and true tonsillar herniation will show discolouration or even necrosis of the ischaemic, trapped tissue (Figs 5.48–5.50).

Cerebral oedema may be the only intracranial abnormality found at autopsy after a substantial head injury has occurred. This seems to be more commonly found in children and, in the absence of any other demonstrable lesions, the cause of death has to be attributed to this swelling of the brain, compressing the vital centres in the brainstem.

Obviously, many other cases of cerebral oedema resolve either spontaneously or with treatment, so


Normal
Oedematous
Normal weight (<1500g)
Palpable sulci
Rounded gyri
Normal hippocampal gyrus and uncus
Normal cerebellar tonsil
Increased weight (>1500g)
Flattened gyriln
Filled sulci
Grooved uncus Swollen hipocampal gyrus
Herniated cerebellar tonsil
Midline shift if oedema is unilateral

Figure 5.48 Signs of cerebral oedema.



Figure 5.49 Tonsillar herniation as a consequence of lumbar puncture in a patient with increased intracranial pressure. The pressure gradient has forced the cerebellar tonsils into foramen magnum and caused compression of the brainstem and patient's death. (Reproduced by kind permission of Professor H. Kalimo.)



Figure 5.50 Transtentorial herniation in brain trauma. Compression of medial temporal lobes against the tentorium edges has caused bilateral haemorrhagic necroses (white arrows). In addition, the compression of left posterior cerebral artery has resulted in haemorrhagic infarcts in the left temporal lobe (black asterisk). There is also a slight shift of the midline to the right (white line). (Reproduced by kind permission of Professor H. Kalimo.)

that fortunately no opportunity arises to prove its existence by post-mortem examination. Such oedema is, however, not infrequently found during surgical exploration for a meningeal haemorrhage, the latter sometimes being presented though often only brain swelling is demonstrated.

Cerebral oedema may be self-potentiating, in that once it begins as a result of direct brain trauma, the consequent rise in ICP then impairs the venous return from the intracranial sinuses. The pressure is insufficient to restrict the arterial inflow, so further congestion and swelling occur. This may lead to worsening cerebral hypoxia and oedema to the stage of actual cerebral infarction and brain death – again, a distressing common syndrome seen especially in child victims of head injuries, usually from road accidents.

Cerebral oedema, either traumatic or hypoxic, can develop with surprising rapidity, especially in children. Macroscopic evidence of brain swelling can be seen at autopsy in cases where the interval between trauma or onset of hypoxia and death was less than 1 hour.

Several methods are available to reverse oedema, including hyperventilation, which acts by providing full oxygenation and reducing the peripheral carbon dioxide tension, thus causing constriction of arterioles resulting in a reduction of the amount of intracranial blood and therefore also the brain volume and transudation.

Diagnosis of early cerebral hypoxia–ischaemia

Unfortunately for the pathologist, most of the hypoxic–ischaemic conditions seen in forensic practice cause death too quickly for any recognizable histological changes to develop. Acute deaths from strangulation, suffocation and choking occur within minutes or less, even excepting the sudden vasovagal type of cardiac arrest.

There are, however, occasions when a longer period of survival occurs after an acute ischaemic episode and in some of these there may be the opportunity to detect histological changes in the central nervous system (CNS). Probably a minimum of 2–4 hours of survival is necessary for unequivocal changes to be observed, though some neuropathologists claim to detect signs after as little as 1 hour. More cautious investigators prefer 4 hours as the minimum. A short post-mortem interval is a considerable advantage in searching for these changes, as they are subtle and can be overlaid by post-mortem autolysis, even if the latter is slight.

It takes 12–24 hours from the onset of infarction before it can be detected with the naked eye on post-mortem examination of unfixed brain. When brain is fixed properly, the early infarct can be identified by palpation, because necrotic tissue does not become fixed and is soft and velvety to touch in contrast to the firm consistency of fixed, non-necrotic tissue. The blurring of the boundary between the grey and white matter is another early macroscopic change.

It may be helpful to seek the assistance of a neuropathologist in detecting or confirming the relatively minor changes seen in a brain affected by hypoxia, but with experience, a good knowledge of the normal appearances and a laboratory that is able to turn out constantly good-quality sections and uniform staining, any forensic pathologist can build up a considerable expertise in this localized aspect of neuropathology. The parts of the brain most suitable for seeking evidence of hypoxic damage are the hippocampus (especially CA1 sector = Sommer's area and subiculum), the cerebellar folia, the globus pallidus in the basal ganglia, and the boundary zones of the cerebral cortex where the grey matter is most vulnerable because it lies at the terminal reaches of the arterial supply (for example, parasagittally at the middle frontal gyrus where the watershed between middle and anterior cerebral arteries lies). The third and fourth cortical layers are best for displaying the histological changes of hypoxia.

The following is a summary of the stages and changes that may be seen using different staining methods. The brain should be fixed by suspension in buffered 4 per cent formaldehyde, though if this is impossible, small blocks should be wet-cut from the target areas of the brain mentioned above and immediately fixed in a large volume of buffered formaldehyde.

Stage 1

The earliest change is microvacuolation in the neuron cytoplasm (swollen mitochondria), which may be seen in 2–4 hours. The cell outline remains smooth and its size is normal but, internally, small vacuoles appear in the cell body, and the proximal parts of the axon and dendrites. There may be a slight eosinophilia in haematoxylin and eosin (H&E) stains and a violet colour in luxol fast blue (LFB).

The microvacuolar change is said to begin earlier in small neurons and last for a shorter time, being present for up to 4–6 hours after insult in large cells and 2–4 hours in cerebellar Purkinje cells, though these times are arbitrary.

Stage 2

In the next stage, more prolonged hypoxia–ischaemia causes distortion in the shape of the neurons, the cell body becoming shrunken and staining darker with aniline dyes. The Nissl granules become fine and are dispersed more widely throughout the cell. Some vacuoles remain, the cytoplasm shows marked eosinophilia in H&E, and is bright blue to mauve in LFB stain. The nucleus becomes triangular and may be placed eccentrically in the cell body. The nucleolus becomes obscured and the nucleus condensed, pyknotic and it stains a darker blue than normally with LFB. This change is seen after up to 6 hours survival or later in large neurons.

Stage 3

The ischaemic cell stage, described last, becomes worse during the following day or two if survival continues. The cell shrinks further, becoming narrow and tapered in many cases. Eosinophilia and blueness when stained with LFB persists, but small spherical or irregular bodies begin to adhere to the exterior of the cell membrane. These incrustations persist longer than the remnants of the cytoplasm, which vanish, leaving the bare nucleus. The dark, shrunken nucleus becomes more apparent and survives for a number of days before karyolysis occurs. As an inflammatory reaction to the evolving necrosis polymorphonuclear neutrophils (PMNs) accumulate by 15–20 hours in the lumina and perivascular space of small arteries supplying the territory of the developing infarct and if the ischaemic injury to the blood vessels is of sufficient severity, PMNs also infiltrate to the brain parenchyma.

Stage 4

Homogenizing cell damage is best seen in the Purkinje cells, in which the cytoplasm is uniformly eosinophilic with no Nissl granules. The nucleus stays dark and triangular until it vanishes and leaves a pale 'ghost' of the cell body with a vague perimeter. Blood-derived monocytes/phagocytes appear on day 2–3 and begin phagocytosis of the cell debris in which the activated (phagocytic) microglial cells (which actually are not glial cells, but monocytic reticuloendothelial cells residing in the CNS) also participate.

Proliferation of astrocytes (which show mitoses) begins some 4–6 days later if the patient survives. This is most noticeable in the cerebellum and persists for 10–14 days. Astrocytes proliferate, but not the oligodendroglia. A later stage of cerebral hypoxic–ischaemic (infarct) damage is a cystic cavity lined by astrocytes and with lipid-laden macrophages (foam cells), which may persist for several months in larger infarcts.

Secondary brainstem lesions

When severe brain swelling (or a space-occupying lesion such as a large subdural or extradural haematoma) causes raised ICP above the tentorium, amongst the possible sequelae is tentorial herniation. When symmetrical, the oedema forces the undersurface of the cerebrum against the tentorium so that the parahippocampal gyri are squeezed into the tentorial opening. The compression against the free edge of tentorium results in grooving of the unci and, in extreme cases, in focal infarction of the parahippocampal gyrus. The compression on the brainstem elongates the midbrain in an anteroposterior direction. In addition, the distortion stretches, and compresses the paramedian and nigral vessels that supply the midbrain, leading to haemorrhages and infarcts in the upper pons and midbrain. Damage to cranial nerves and to the circulation of the CSF may be added complications. The calcarine cortex on the medial aspect of the occipital lobe may be infarcted by the posterior cerebral artery being trapped around the edge of the tentorium by the cerebral herniation. Tentorial herniation may be unilateral and when massive it may cause grooving of a cerebral peduncle (called 'Kernohan's notch') associated with subpial petechial haemorrhages and often false localizing/paradoxical ipsilateral hemiparesis.

Firsching *et al.* performed MRI in 61 consecutive patients within 7 days after severe head injury. Brainstem lesions were visualized in 64 per cent (39) of the subjects. Bilateral pontine lesions carried a 100 per cent mortality rate, whereas non-brainstem lesions were fatal in 9 per cent of the patients. Histopathology in two MR-verified brainstem lesions showed perivascular haemorrhages, intraneural calcifications and swollen axons. However, differentiation between primary and secondary brainstem injury was histopathologically not possible.[131]

Secondary lesions are almost exclusively midline or paramedian haemorrhages, or haemorrhagic necrosis placed centrally in the upper pons and midbrain, though some may be obliquely placed in the substantia nigra. They may be difficult to distinguish from primary brainstem haemorrhages that arise at or soon after the original head injury – the secondary lesions tend to obscure the primary, rather than the converse. In children, the typical stem haemorrhages may not be present as in adults, but instead the medulla oblongata may be buckled or kinked due to fixation of the upper spinal cord by the denticulate ligaments.

Spinal injuries

The spine and head should be thought of as part of the same system in relation to trauma. For instance, interruption of ascending fibres in the cervical cord has been shown to be associated with neuronal chromatolysis in the brainstem and Spicer and Strich have shown that haemorrhage into spinal root ganglia may be associated with head injury.[132] Electroencephalographic changes have been shown to occur in many victims of cervical spine whiplash injury.[133,134]

Though all segments of the spine are vulnerable to trauma, the cervical part holds the most interest for the forensic pathologist, mainly because of its close association with head injuries and vehicular accidents, the latter of which account for most of the cervical spine injuries followed by falls, and sporting activities (Fig. 5.51).[135] The upper two cervical vertebrae provide most of the rotational movement of the head, while the



Figure 5.51 Crushing of the spinal cord following a compression fracture of the 5th cervical vertebra due to hitting the bottom after a head-on jump into shallow water. At autopsy the cord and its membranes should be pinned out and fixed for a proper examination to be made.

lower neck allows flexion and extension. Violent force applied to the head tends to damage those parts of the neck corresponding with this functional distinction. Spinal damage may be caused by compressional, hyperflexion and hyperextension stress.

Compression damage

This occurs when the victim falls from a height either onto his feet or his head, though in the latter case, head injuries may overshadow damage to the spine, as well as absorbing most of the impact.

When a person falls a long distance onto the feet, the kinetic energy of the deceleration may be absorbed by fractures of the feet, legs and pelvis, but can be transmitted up the spinal column. This can be fractured at one or more points, or the force may cause the upper cervical spine to impinge on the base of the skull and cause a 'ring fracture' around the foramen magnum as the spine is rammed into the posterior fossa.

A fall onto the head may also cause the 'burst atlas' injury, where the impact of the occipital condyles in an axial direction wedge the superior atlantal articulating facets apart and split the ring of the vertebra.[136] The posterior arch can also be fractured in hyperextension by compression between the occiput and the posterior spine of the axis.[137]

Compression fractures of vertebral bodies may occur, most commonly in the lower thoracic and upper lumbar zone, particularly T12 and L1. There is less chance of spinal cord injury compared with the angulation injuries described below, unless posterior extrusion of a disc or backward displacement of fragments of a disrupted vertebral body occurs.

Hyperflexion and hyperextension injury

Of the two, hyperextension is much more dangerous in causing spinal damage, possibly because flexion is protected by contraction of the strong posterior neck muscles, whereas the weak anterior longitudinal ligament is incapable of preserving the integrity of the cervical spine during hyperextension. In frontal or rearward motor vehicle crashes, which comprise 80 per cent of accidents, there is usually a hyperflexion and hyperextension component to the spines of the occupants, though head restraints and seatbelts restrict the range of movement.

Where a car undergoes violent frontal deceleration, the subject's head will swing down into hyperflexion and, unless restrained, will then strike the fascia or windscreen, and rebound into hyperextension.

When the vehicle is struck from the rear, the head will fly into hyperextension first unless a head-rest is available; such collisions often then smash the vehicle into the one in front, when a deceleration hyperflexion takes place (Fig. 5.52).

Whatever the cause, a whole range of lesions can follow, both in the cervical, and to a lesser extent into the thoracic and lumbar segments. Bleeding into the surrounding muscles, rupture of the anterior longitudinal ligament and tearing of intervertebral discs and of the annulus fibrosus may occur.

Nerve roots may be torn or compressed, and the spinal canal may be narrowed, distorted or even almost obliterated by fracture dislocations of the vertebrae. Compression, ischaemia, haemorrhage and even pulping of the spinal cord are the most serious complications. In older persons with cervical spondylosis, further narrowing of the canal by trauma may cause neurological effects that would not occur in younger subjects.



Figure 5.52 Crushing of a thoracic vertebral body with disintegration of the adjacent disc following a violent hyperflexion in a car driver sustaining a deceleration injury. These lesions are best displayed at autopsy by cutting a longitudinal slice down the anterior aspect of the spinal column with an electric saw.

The cervical spine accounts for 60 per cent of the adult spine injuries and the most common part of the spine to be injured is the region of the upper cervical vertebrae (C1–C4), and injury to the C1/C2 complex accounts for 19–25 per cent of the cervical spine injuries. These are followed by injuries to the thoracolumbar (20 per cent), lumbar (10 per cent), thoracic (8 per cent), and sacral level (2 per cent).[135,138] In a series of fatal motor car accidents reported by Mant, 35 per cent of passengers and 30 per cent of drivers suffered cervical spine damage.[139] Of these the most common was a dislocation of the atlanto-occipital joint and Mant claims that one-third of all victims of fatal motor vehicle accidents suffer this lesion, even though it is often undetected at autopsy. The mechanism of fracture of the atlas is said to be an axial impact via the head, when the occiput is held rigidly in line with the spine by contracted neck muscles. This most frequently occurs when the vertex of the lowered head violently strikes the windshield of a decelerating vehicle. Fracture or dislocation of the atlas or fracture of the odontoid of the axis can all occur from this type of impact. Hyperextension injuries tend to force the vertebral body forwards and, if there is significant displacement, the arch is intruded into the spinal canal with the consequent risk of cord damage. In addition, hyperextension – especially in the presence of cervical cord enlargement – can cause the ligamentum flavum to corrugate and intrude into the anterior part of the spinal canal to impinge upon the cord. When the injury is due to hyperflexion, dislocation of a vertebra causes it (or its fragments) to tilt backwards, again compromising the lumen of the spinal canal.

Dislocation of cervical vertebra can occur under many conditions. An anterior dislocation can be caused by a fall onto the back of the head and a unilateral dislocation is common when a head strikes a windscreen. Posterior dislocation may be caused by blows to the jaw or face that jolt the head backwards with a hyperextension element. Falling onto the face, especially from a height (such as down a staircase), is a likely cause. Fracture of the odontoid peg of the axis can occur from a variety of violent movements of the head on the neck, and is sometimes associated with fracture of the skull or mandible. Where gross injury to the spinal column is inflicted – such as a relatively high-speed motor vehicle or railway accident – the cord may be transected by a guillotine action of the two displaced fragments. This is most often seen on the upper or midthoracic region, from direct impact or gross 'whiplash' effects. The thoracic aorta at this level is often torn at the point where the descending arch meets the spine, even in the absence of a spinal fracture.

Damage to the cervical spine in hanging is rarely seen in the usual suicidal hangings in which sudden death is caused by carotid compression or – much less often – asphyxia. The drop in such cases is small or even absent, the subject merely slumping his weight against the neck restraint. Spinal damage can occasionally occur, however and the author (BK) has seen a fractured neck when a heavily built soldier stepped from a lavatory seat with the rope attached to the overhead cistern.

Judicial hanging with a long drop causes a severe fracture dislocation (rather than fracture) of the cervical spine, often with complete severance of the two fragments and transection of the spinal cord. Where such hanging is carried out with the knot of the suspension point beneath the chin, a violent hyperextension is produced that often fractures the axis and dislocates it from the third cervical vertebra. With a heavy person and a long drop, there may be complete decapitation.

Spinal cord injury

Most damage to the spinal cord arises from intrusion of some part of the spinal column into the canal, be it bony fragments or displacement, ligamentum flavum, disc annulus or extruded nucleus pulposus.

There may be bleeding into the space outside the spinal dura causing a space-occupying lesion in the canal that can compress the cord, or bleeding may occur within the dura, either from ruptured vessels or from haemorrhage in the cord itself. Damage to the cord may also occur in the absence of any apparent intrusion into the canal, in a manner similar to that seen in the brain in closed head injuries without a fracture. Haematomyelia and oedema may develop without any obvious mechanical defect at that level in the spinal column. Such injuries must be attributed to some momentary collision of the cord against the wall of the canal or a transient deformity of the profile of the canal that did not exceed the threshold for either fracture, dislocation or ligament rupture of the vertebral column.

The damage in the cord may extend for several segments above and below the point of impact. A haemorrhage within the cord tends to occupy the central grey matter more than the white columns, because of the softer and more vascular nature of the former tissue. Infarction of the cord can occur either in association with contusion, or because the local blood supply – often the anterior spinal artery – has been damaged.

An originally firm cord may undergo liquefaction ('myelomalacia') over several days or even longer, with progressive worsening of neurological symptoms.

References

1 Adelson L. *The Pathology of Homicide*. Springfield Thomas, 1974.
2 Teece S, Crawford I. Best evidence topic report. Torn frenulum and non-accidental injury in children. *Emerg Med J* 2005;22(2):125.
3 Maguire S, *et al*. Diagnosing abuse: a systematic review of torn frenum and other intra-oral injuries. *Arch Dis Child* 2007;92(12):1113–7.
4 Welbury R. Torn labial frenum in isolation not pathognomonic of physical abuse. *Evid Based Dent* 2007;8(3):71.
5 Koe S, *et al*. Medical, social and societal issues in infants with abusive head trauma. *Ir Med J* 2010;103(4):102–5.
6 Grass H, *et al*. [Phenomenology of kicking and kicking to death]. *Arch Kriminol* 1996;198(3–4):73–8.
7 Henn V, *et al*. [Morphology and phenomenology of death by kicking (II)]. *Arch Kriminol* 2000;205(3–4):65–74.
8 Strauch, H, *et al*. Kicking to death – forensic and criminological aspects. *Forensic Sci Int* 2001;123(2–3):165–71.
9 Betz P, Lignitz E, Eisenmenger W. The time-dependent appearance of black eyes. *Int J Legal Med* 1995;108(2):96–9.
10 Weber W. [Experimental studies of skull fractures in infants]. *Z Rechtsmed* 1984;92(2):87–94.
11 Goonetilleke UK. Injuries caused by falls from heights. *Med Sci Law* 1980;20(4):262–75.
12 Rowbotham OF. *Acute Injuries of the Head*, 4th edn. Edinburgh: Churchill-Livingstone, 1964.
13 Zuo ZJ, Zhu JZ. Study on the microstructures of skull fracture. *Forensic Sci Int* 1991;50(1):1–14.
14 Gurdjian ES, Webster JE, Lissner HR. Studies on skull fracture with particular reference to engineering factors. *Am J Surg* 1949;78(5):736–42; Disc 749–51.
15 Gurdjian ES, Webster JE, Lissner HR. The mechanism of skull fracture. *Radiology* 1950;54(3):313–39.
16 Evans FG, Lissner HR. Tensile and compressive strength of human parietal bone. *J Appl Physiol* 1957;10(3):493–7.
17 Evans FG, Lissner HR, Lebow M. The relation of energy, velocity, and acceleration to skull deformation and fracture. *Surg Gynecol Obstet* 1958;107(5):593–601.
18 Shapiro HA, Gordon I, Benson SD. *Forensic Medicine – a Guide to Principles*, 3rd edn. Edinburgh: Churchill Livingstone, 1988.
19 Leestma JE (ed). *Forensic Neuropathology*, 2nd edn. Boca Raton: CRC Press, Taylor & Francis Group, 2009.
20 Puppe G. Über priorität der schädelbrüche. *Arztl Sachverst Zt* 1914;20:307–9.
21 Jacobsen C, Lynnerup N. Cranial fractures caused by blunt trauma to the skull. A retrospective analysis of medico-legal autopsies in Denmark from 1999–2004. *Scand J Forensic Sci* 2008;14(2):64–70.
22 Jacobsen C. *Cranial Fractures Caused by Blunt Trauma. Characterization of Medico-legal Material and Assessment of Post-mortem Computed Tomography*. Copenhagen: Department of Forensic Medicine, University of Copenhagen, 2009, p. 168.
23 Yoganandan N, Pintar FA. Biomechanics of temporo-parietal skull fracture. *Clin Biomech (Bristol, Avon)* 2004;19(3):225–39.
24 Agrawal A, *et al*. Post-traumatic epilepsy: an overview. *Clin Neurol Neurosurg* 2006;108(5):433–9.
25 Lindenberg R. Trauma of meninges and brain. In: Minckler J (ed). *Pathology of the Nervous System*. New York: McGraw-Hill, 1971, pp. 1705–65.
26 Tomlinson BE. Brain-stem lesions after head injury. *J Clin Pathol Suppl (R Coll Pathol)* 1970;4:154–65.
27 Adams JH. Head injury. In: Adams JH, Corsellis JA, Duchen LW (eds). *Greenfield's Neuropathology*. London: Edward Arnold, 1992.
28 McKissock H. Extradural haemorrhage; observations on 125 cases. *Lancet* 1960;2:167–74.
29 Harwood-Nash DC, Hendrick EB, Hudson AR. The significance of skull fractures in children. A study of 1,187 patients. *Radiology* 1971;101(1):151–6.
30 Maurer JJ, Mayfield FH. Acute bilateral extradural hematomas. A case report. *J Neurosurg* 1965;23(1):63.
31 Subrahmanian MV, Rajendraprasad GB, Rao BD. Bilateral extradural haematomas. *Br J Surg* 1975;62(5):397–400.
32 Frank E, Berger TS, Tew, TM Jr. Bilateral epidural hematomas. *Surg Neurol* 1982;17(3):218–22.
33 Dharker SR, Bhargava N. Bilateral epidural haematoma. *Acta Neurochir (Wien)* 1991;110(1–2):29–32.
34 Gupta SK, *et al*. Bilateral traumatic extradural haematomas: report of 12 cases with a review of the literature. *Clin Neurol Neurosurg* 1992;94(2):127–31.
35 Rasmussen GL, Holme S. [Bilateral epidural hematomas]. *Ugeskr Laeger* 1992;154(4):203–4.
36 Gorgulu A, *et al*. Bilateral epidural hematoma. *Neurosurg Rev* 2000;23(1):30–3.
37 Huda MF, *et al*. Double extradural hematoma: an analysis of 46 cases. *Neurol India* 2004;52(4):450–2.
38 Gelabert-Gonzalez M, *et al*. [Simultaneous bilateral epidural haematomas]. *Neurocirugia (Astur)* 2005;16(3):256–60.
39 Bullock MR, *et al*. Surgical management of acute epidural hematomas. *Neurosurgery* 2006;58(3 Suppl):S7–15; Discussion Si–iv.
40 Provenzale J. CT and MR imaging of acute cranial trauma. *Emerg Radiol* 2007;14(1):1–12.
41 Caffey J. Multiple fractures in the long bones of infants suffering from chronic subdural haematoma. *Am J Radiology* 1946;56:163–73.
42 Blumbergs P, Reilly P, Vink R. Trauma. In: Love S, Louis DN, Ellison DW (eds). *Greenfield's Neuropathology*. London: Hodder Arnold, 2008, pp. 733–832.
43 Duhaime AC, *et al*. The shaken baby syndrome. A clinical, pathological, and biomechanical study. *J Neurosurg* 1987;66(3):409–15.
44 Squier W. The 'shaken baby' syndrome: pathology and mechanisms. *Acta Neuropathol* 2011;122(5):519–42.
45 Gennarelli TA, Thibault LE. Biomechanics of acute subdural hematoma. *J Trauma* 1982;22(8):680–6.
46 Squier W, Mack J. The neuropathology of infant subdural haemorrhage. *Forensic Sci Int* 2009;187(1–3):6–13.
47 Crompton R. *Closed Head Injuries*. London: Edward Arnold, 1985.
48 Munro D, Merritt HH. Surgical pathology of subdural haematoma. Based on a study of 105 cases. *Arch Neurol Psych* 1936;35:64–78.
49 Crompton MR. Brainstem lesions due to closed head injury. *Lancet* 1971;**1**(7701):669–73.
50 Harnan SE, *et al*. Clinical decision rules for adults with minor head injury: a systematic review. *J Trauma* 2011;71(1):245–51.

51 Holmes B, Harbaugh RE. Traumatic intracranial aneurysms: a contemporary review. *J Trauma* 1993;35(6):855–60.
52 Smith S. On the difficulties attending the diagnosis of aneurism being a contribution to surgical diagnosis and medical jurisprudence. *Am J Med Sci* 1873;66:401–9.
53 Parkinson D, West M. Traumatic intracranial aneurysms. *J Neurosurg* 1980;52(1):11–20.
54 Courville CB. Traumatic aneurysm of an intracranial artery. Description of lesion incident to a shot gun wound of the skull and brain. *Bull Los Angel Neuro Soc* 1960;25:48–54.
55 Burton C, Velasco F, Dorman J. Traumatic aneurysm of a peripheral cerebral artery. Review and case report. *J Neurosurg* 1968;28(5):468–74.
56 Weiler G, *et al*. [Contribution of intracranial 'traumatic aneurysm' (author's transl)]. *Z Rechtsmed* 1980;85(3):225–33.
57 Wortzman D, Tucker WS, Gershater R. Traumatic aneurysm in the posterior fossa. *Surg Neurol* 1980;13(5):329–32.
58 Tani S, *et al*. [Traumatic aneurysm of the posterior inferior cerebellar artery (author's transl)]. *No Shinkei Geka* 1982;10(4):423–7.
59 Amagasa M, *et al*. [Traumatic anterior cerebral artery aneurysms—experiences in 4 cases and review of the literature]. *No Shinkei Geka* 1986;14(13):1585–92.
60 Rahimizadeh A, *et al*. Traumatic cerebral aneurysms caused by shell fragments. Report of four cases and review of the literature. *Acta Neurochir (Wien)* 1987;84(3–4):93–8.
61 Buckingham MJ, *et al*. Traumatic intracranial aneurysms in childhood: two cases and a review of the literature. *Neurosurgery* 1988;22(2):398–408.
62 Soria ED, Paroski MW, Schamann ME. Traumatic aneurysms of cerebral vessels: a case study and review of the literature. *Angiology* 1988;39(7 Pt 1):609–15.
63 Senegor M. Traumatic pericallosal aneurysm in a patient with no major trauma. Case report. *J Neurosurg* 1991;75(3):475–7.
64 Sasaoka Y, *et al*. [Ruptured traumatic aneurysms of the peripheral anterior cerebral artery: study of delayed hemorrhage after closed head injury]. *No Shinkei Geka* 1997;25(4):337–44.
65 Diaz A, *et al*. [Trauma-induced arterial aneurysm in childhood. Report of a case and review of the literature]. *Neurochirurgie* 1998;44(1):46–9.
66 Uzan M, *et al*. Traumatic intracranial carotid tree aneurysms. *Neurosurgery* 1998;43(6):1314–20; Discussion 1320–2.
67 Horowitz MB, *et al*. Multidisciplinary approach to traumatic intracranial aneurysms secondary to shotgun and handgun wounds. *Surg Neurol* 1999;51(1):31–41; Discussion 41–2.
68 Uribe G, *et al*. [Post-traumatic intracranial arterial aneurysm. Two cases with review of the literature]. *Neurochirurgie* 1999;45(4):301–6.
69 Larson PS, *et al*. Traumatic intracranial aneurysms. *Neurosurg Focus* 2000;8(1):e4.
70 Nishioka T, *et al*. Unexpected delayed rupture of the vertebral-posterior inferior cerebellar artery aneurysms following closed head injury. *Acta Neurochir (Wien)* 2002;144(8):839–45; Discussion 845.
71 Horiuchi T, *et al*. Traumatic middle cerebral artery aneurysm: case report and review of the literature. *Neurosurg Rev* 2007;30(3):263–7; Discussion 267.
72 Yang TC, *et al*. Traumatic anterior cerebral artery aneurysm following blunt craniofacial trauma. *Eur Neurol* 2007;58(4):239–45.
73 Kaiser C, *et al*. Traumatic rupture of the intracranial vertebral artery due to rotational acceleration. *Forensic Sci Int* 2008;182(1–3):e15–17.
74 Mao Z, *et al*. Traumatic intracranial aneurysms due to blunt brain injury – a single center experience. *Acta Neurochir (Wien)* 2012;154(12):2187–93; Discussion 2193.
75 Benoit BG, Wortzman G. Traumatic cerebral aneurysms. Clinical features and natural history. *J Neurol Neurosurg Psychiatry* 1973;36(1):127–38.
76 Asari S, *et al*. Traumatic aneurysm of peripheral cerebral arteries. Report of two cases. *J Neurosurg* 1977;46(6):795–803.
77 Purgina B, Milroy CM. Fatal traumatic aneurysm of the posterior inferior cerebellar artery with delayed rupture. *Forensic Sci Int* 2015;247:e1–5.
78 Ngo DQ, van Rooij WJ, Tijssen C. Rapidly growing traumatic cerebral aneurysm with early subarachnoid hemorrhage. *Neurology* 2008;70(6):490.
79 Bostrom K, Helander CG, Lindgren SO. Blunt basal head trauma: rupture of posterior inferior cerebellar artery. *Forensic Sci Int* 1992;53(1):61–8.
80 Cameron JM, Mant AK. Fatal subarachnoid haemorrhage associated with cervical trauma. *Med Sci Law* 1972;12(1):66–70.
81 Coast GC, Gee DJ. Traumatic subarachnoid haemorrhage: an alternative source. *J Clin Pathol* 1984;37(11):1245–8.
82 Contostavlos DL. Massive subarachnoid hemorrhage due to laceration of the vertebral artery associated with fracture of the transverse process of the atlas. *J Forensic Sci* 1971;16(1):40–56.
83 Contostavlos DL. Isolated basilar traumatic subarachnoid hemorrhage: an observer's 25 year re-evaluation of the pathogenetic possibilities. *Forensic Sci Int* 1995;73(1):61–74.
84 Leadbeatter S. Extracranial vertebral artery injury – evolution of a pathological illusion? *Forensic Sci Int* 1994;67(1):33–40.
85 Aghayev E, *et al*. Virtopsy post-mortem multi-slice computed tomography (MSCT) and magnetic resonance imaging (MRI) demonstrating descending tonsillar herniation: comparison to clinical studies. *Neuroradiology* 2004;46(7):559–64.
86 Yen K, *et al*. Post-mortem forensic neuroimaging: correlation of MSCT and MRI findings with autopsy results. *Forensic Sci Int* 2007;173(1):21–35.
87 Aghayev E, *et al*. MRI detects hemorrhages in the muscles of the back in hypothermia. *Forensic Sci Int* 2008;176(2–3):183–6.
88 Grabherr S, *et al*. [Forensic imaging]. *Rev Med Suisse* 2008;4(164):1609–14.
89 Saunders SL, *et al*. Post-mortem computed tomography angiography: past, present and future. *Forensic Sci Med Pathol* 2011;7(3):271–7.
90 Lundstrom C, *et al*. State-of-the-art of visualization in post-mortem imaging. *APMIS* 2012;120(4):316–26.
91 Palmiere C, *et al*. Detection of hemorrhage source: the diagnostic value of post-mortem CT-angiography. *Forensic Sci Int* 2012;222(1–3):33–9.
92 Johnson CP, Lyall MS. Injection methods in the investigation of traumatic subarachnoid hemorrhage. *Am J Forensic Med Pathol* 2012;33(3):e9.
93 Ikegaya H, Yajima D, Iwase H. Vertebral artery rupture in a sudden death case after mild trauma. *Am J Forensic Med Pathol* 2008;29(3):276–8.
94 Unterharnscheidt F, Sellier K. [Traumatic lesions of the central nervous system in boxers]. *Hefte Unfallheilkd* 1967;91:162–8.
95 Unterharnscheidt F, Sellier K. [Boxing. Mechanics, pathomorphology and clinical picture of traumatic lesions of

the CNS in boxers]. *Fortschr Neurol Psychiatr Grenzgeb* 1971; 39(3):109–51.

96 Colmant HJ, Dotzauer G. [Analysis of a boxing match with fatal outcome resulting from unusually severe brain damage (author's transl)]. *Z Rechtsmed* 1980;**84**(4):263–78.

97 Lundberg GD. Brain injury in boxing. *Am J Forensic Med Pathol* 1985;6(3):192–8.

98 Omalu BI, *et al*. Chronic traumatic encephalopathy in a National Football League player. *Neurosurgery* 2005;57(1): 128–34; Comments 133–4.

99 Loosemore M, Knowles CH, Whyte GP. Amateur boxing and risk of chronic traumatic brain injury: systematic review of observational studies. *Br Med J* 2007;335(7624):809.

100 Zazryn TR, McCrory PR, Cameron PA. Neurologic injuries in boxing and other combat sports. *Neurologic Clinics* 2008;26(1):257–270.

101 Jordan BD. Brain injury inboxing. *Clin Sports Med* 2009;28(4):561–78.

102 Omalu BI, *et al*. Chronic traumatic encephalopathy, suicides and parasuicides in professional American athletes: the role of the forensic pathologist. *Am J Forensic Med Pathol* 2010;31(2):130–2.

103 Zazryn TR, McCrory PR, Cameron PA. Neurologic injuries in boxing and other combat sports. *Phys Med Rehab Clin North Am* 2009;20(1):227–39.

104 Potter MR, Snyder AJ, Smith GA. Boxing injuries presenting to U.S. Emergency Departments, 1990–2008. *Am J Prevent Med* 2011;40(4):462–7.

105 Hof PR, *et al*. Differential distribution of neurofibrillary tangles in the cerebral cortex of dementia pugilistica and Alzheimer's disease cases. *Acta Neuropathol* 1992;85(1):23–30.

106 Geddes JF, *et al*. Neurofibrillary tangles, but not Alzheimer-type pathology, in a young boxer. *Neuropathol Appl Neurobiol* 1996;22(1):12–16.

107 Schmidt ML, *et al*. Tau isoform profile and phosphorylation state in dementia pugilistica recapitulate Alzheimer's disease. *Acta Neuropathol* 2001;101(5):518–24.

108 Areza-Fegyveres R, *et al*. Dementia pugilistica with clinical features of Alzheimer's disease. *Arq Neuropsiquiatr* 2007;65(3B):830–3.

109 Lolekha P, Phanthumchinda K, Bhidayasiri R. Prevalence and risk factors of Parkinson's disease in retired Thai traditional boxers. *Mov Disord* 2010;25(12):1895–901.

110 Bhidayasiri R, *et al*. Boxing and Parkinson disease: a link or a myth? An 18F-FDOPA PET/CT study in retired Thai traditional boxers. *Parkinsonism Relat Disord* 2012;18(5):694–6.

111 Itabashi HH, *et al*. eds. *Forensic Neuropathology: a Practical Review of the Fundamentals*. Burlington: Academic Press, 2007.

112 Love S, Louis DN, Ellison DW (eds). *Greenfield's Neuropathology*, 8th edn. London: Hodder Arnold, 2008.

113 Munro D. *Cranio-cerebral Injuries*. Oxford: Oxford University Press, 1963.

114 Ledran H. *Observatis des Chirurgies*. Paris: Osmont, 1751.

115 Morgagni J. *De Sedibus et Causis Morborum per Anatomen Indagatis.* Lovanii: Typographia Academia, 1766.

116 Yanagida Y, Fujiwara S, Mizoi Y. Differences in the intracranial pressure caused by a 'blow' and/or a 'fall' – an experimental study using physical models of the head and neck. *Forensic Sci Int* 1989;41(1–2):135–45.

117 Courville CB. Coup-contre coup mechanism of craniocerebral injuries: some observations. *Arch Surg* 1942;45:19–43.

118 Holbourn AH. Mechanics of head injuries. *Lancet* 1943;245:438–41.

119 Drew LB, Drew WE. The contrecoup-coup phenomenon: a new understanding of the mechanism of closed head injury. *Neurocrit Care* 2004;1(3):385–90.

120 Halabieh O, Wan JWL. *Simulating Mechanism of Brain Injury During Closed Head Impact*. Bello F, Edwards P (eds). Berlin: Springer, 2008, pp. 107–118.

121 Wilson JV. *The Pathology of Traumatic Injury*, 1st edn. Edinburgh: Livingstone, 1946.

122 Trotter W. Concussion. *Brit J Surg* 1914;2:271–91.

123 Herring SA, *et al*. Concussion (mild traumatic brain injury) and the team physician: a consensus statement – 2011 update. *Med Sci Sports Exerc* 2011;43(12):2412–22.

124 Chamard E, *et al*. A prospective study of physician-observed concussion during a varsity university hockey season: metabolic changes in ice hockey players. Part 4 of 4. *Neurosurg Focus* 2012;33(6):E4:1–7.

125 Signoretti S, *et al*. The pathophysiology of concussion. *PMR* 2011;3(10 Suppl 2):S359–68.

126 Kirov II, *et al*. Proton MR spectroscopy correlates diffuse axonal abnormalities with post-concussive symptoms in mild traumatic brain injury. *J Neurotrauma* 2013;30(13):1200–4.

127 Graham DI, Gennarelli TA, McIntosh TK. Trauma. In: Graham DI, Lantos PL (eds). *Greenfield's Neuropathology*. London: Arnold, 2002, pp. 823–98.

128 Geddes JF, Whitwell HL, Graham DI. Traumatic axonal injury: practical issues for diagnosis in medicolegal cases. *Neuropathol Appl Neurobiol* 2000;26(2):105–16.

129 Miller JD, *et al*. Significance of intracranial hypertension in severe head injury. *J Neurosurg* 1977;47(4):503–16.

130 Nag S, Manias JL, Stewart DJ. Pathology and new players in the pathogenesis of brain edema. *Acta Neuropathol* 2009;118(2):197–217.

131 Firsching R, *et al*. Early magnetic resonance imaging of brainstem lesions after severe head injury. *J Neurosurg* 1998;89(5):707–12.

132 Spicer EJ, Strich SJ. Haemorrhages in posterior-root ganglia in patients dying from head injuries. *Lancet* 1967;2(7531): 1389–91.

133 Henry GK, *et al*. Nonimpact brain injury: neuropsychological and behavioral correlates with consideration of physiological findings. *Appl Neuropsychol* 2000;7(2):65–75.

134 Alexander MP. The evidence for brain injury in whiplash injuries. *Pain Res Manag* 2003;8(1):19–23.

135 Kalani MYS, Filippidis AS, Theodore N. Injuries to the cervical spine. In: *Principles of Neurological Surgery*, 3rd edn. Philadelphia: W.B. Saunders, 2012, pp. 397–411.

136 Ivancic PC. Atlas injury mechanisms during head-first impact. *Spine (Phila Pa 1976)* 2012;37(12):1022–9.

137 Rao SK, Wasyliw C, Nunez DB Jr. Spectrum of imaging findings in hyperextension injuries of the neck. *Radiographics* 2005;25(5):1239–54.

138 Pratt H, Davies E, King L. Traumatic injuries of the c1/c2 complex: computed tomographic imaging appearances. *Curr Probl Diagn Radiol* 2008;**37**(1):26–38.

139 Mant AK. Injuries and death in motor vehicle accidents. In Mason JK (ed). *Pathology of Violent Injury*. London: Edward Arnold, 1978.

This page intentionally left blank

CHAPTER 6

Chest and Abdominal Injuries

- Chest injuries
- Injuries to the chest wall
- Haemorrhage and infection in the chest
- Pneumothorax
- Injuries of the lungs
- Injuries of the heart
- Haemopericardium and cardiac tamponade
- Injuries to great vessels
- Abdominal injuries
- Foreign bodies in the gut
- Injuries to the pelvis and pelvic organs
- Complications of abdominal injury
- References

The major categories of wound previously described can be inflicted on any part of the body. In forensic practice certain areas are particularly vulnerable or have special medico-legal significance. Head injuries are so important that they have been discussed in a separate chapter, but here consideration will be given to other regions, especially the chest and abdomen.

Chest injuries

Damage can be sustained to either the chest wall or to the contents.

Forensic anatomy

The most important aspect is the relationship of the visceral contents to external landmarks. This is best described by reference to diagrams, where the relationship of pleural cavities, lungs, heart, mediastinum and diaphragm is depicted. It should be appreciated that, from the forensic aspect, the spleen and most of the liver and stomach are thoracic organs in that they lie largely beneath the costal margin, and are vulnerable to both stabbing and blunt injury to the chest (Figs 6.1, 6.2).

Penetrating injuries, especially by knife to the lower lateral wall of the thorax, may enter the peritoneal cavity as well as the pleural spaces, perforating the diaphragm en route. The stomach, being largely within the rib cage, may often be penetrated. The common stab wounds of the heart may also include diaphragmatic and upper abdominal injuries. A knife can enter the front of the lower thorax, pass through either or both ventricles, and exit through the pericardial surface of the diaphragm to enter the upper surface of the liver. The orientation of the heart is often not appreciated after it is removed as an isolated organ, as the tendency is to visualize it as hanging with the apex downwards.


Common carotid artery
Internal carotid artery
External carotid artery
Hyoid bone
Internal jugular vein
Thyroid cartilage
Cricoid cartilage
Trachea
Apex of lung
Subclavian artery
Left lung
Right lung
Heart
Male nipple level
Lower edge of lung
Lower edge of lung
Lower limit of pleural cavity
Lower limit of pleural cavity
Structures of the thorax and neck
1
2
3
4
5
6
7
8
9
10

Figure 6.1 Surface anatomy of heart, lungs and neck structures.



Figure 6.2 Anterior view of trunk showing surface relations of heart and aorta.

In fact, it sits flat on the diaphragm on the lateral edge of the right ventricle, with the inferior vena cava passing immediately downwards into the abdomen.

Injuries to the chest wall

Respiration is dependent on the integrity of the rigid chest wall and, if the expansion is prevented or severely limited, then air entry will be correspondingly diminished. The integrity can be compromised either by severe mechanical failure of the rib cage or by penetration of the pleural cavities.

Fractures of ribs are common, but do not greatly embarrass respiration unless:

- they are so numerous that they prevent expansion of the thorax
- broken ends penetrate the pleura and lungs
- pleural and muscular pain limit respiratory effort.

Where many bilateral fractures are present, especially on the anterolateral sides of the thorax, the condition of 'flail chest' may be present, usually defined as an injury of the thoracic cage with three or more rib fractures in two or more places and sometimes with added fracture(s) of the sternum. As a result of loss of rigidity of the chest cage, attempts at expanding the thoracic volume during inspiration are impaired. The loose section is sucked inwards during inspiration, this clinical sign being known as 'paradoxical respiration'. Dyspnoea and cyanosis may develop and extreme degrees of flail chest are rapidly incompatible with life because of progressive hypoxia.

The flail chest is caused by frontal violence, most often sustained in motor vehicle accidents – where the victim is thrown against the steering wheel or fascia – or in stamping assaults, where the shod foot is violently applied to the supine body. In any substantial chest injury, broken rib ends may be displaced inwards, the jagged tips ripping the parietal and visceral pleura. This may cause a pneumothorax or a haemothorax, or both, from penetration of the lungs, with the formation of a bronchopleural fistula. In gross chest injuries there may be compound fractures of ribs that allow a pneumothorax to form from external communication with the atmosphere, but this is rare in civil practice, though common in battle casualties (Figs 6.3, 6.4).

Rib fractures are most often seen in the anterior or posterior axillary lines caused by falls onto the side. The upper ribs are less often fractured, except by direct violence from kicking, heavy punching or traffic accidents. The fracture sites almost always show bleeding beneath the periosteum or the parietal pleura if the fractures occurred during life – though it must be admitted that (rarely) undoubted ante-mortem fractures may be totally bloodless, whereas some post-mortem cracks may exhibit slight oozing from the



Figure 6.3 Extensive abrasions and deformity of the chest in a man found by the roadside. All his ribs and sternum were fractured, resulting in a 'flail chest'. It was thought to be a road accident until bovine hairs were found on his clothing. He had been crushed by a bull and then tossed over the field wall.



Figure 6.4 Extensive bruising of the chest caused by kicking and stamping, resulting in multiple rib and sternal fractures. Over the left costal margin there is a pattern suggestive of the sole and heel of a shoe.

marrow cavity into the adjacent tissues. Attempts at resuscitation, especially external cardiac massage, now provide a common cause for extensive rib fractures (the frequency varying enormously up to 97 per cent) and make the task of the pathologist much more difficult when trying to differentiate original trauma from the effects of enthusiastic first aid.[1–7] Bleeding may or may not be seen in these resuscitation fractures and, as the attempts at revival are, by definition, perimortal in timing, it is often impossible to say if they were immediately ante-mortem or post-mortem.

As the bracing action of adjacent intercostal muscles may conceal any mobility of the ribs when being examined at autopsy, it is a useful procedure to slit all the intercostal muscles with a knife when chest injury is suspected to allow any mobility to be detected more easily. In the osteoporosis of senility and some diseases, the ribs may be so fragile as to be breakable by finger pressure. Allowance must be made for this fragility in interpreting the cause of the fractures.

In infants, especially victims of child abuse, rib fractures are common and may be an important diagnostic sign of abuse in doubtful cases. Where a small infant is squeezed from side to side, as when adult hands are clamped in each axilla or lower on the lateral sides of the chest, the hyperflexion can easily break ribs in their posterior segments, usually near their necks. The ribs are levered against the transverse processes of the vertebrae by excessive anterior flexion, which explains the tendency to fracture in the paravertebral gutter.[2,7–9] Fresh fractures may be difficult to detect on routine skeletal radiology and even at autopsy each rib should be investigated after stripping of the pleura. Possible fractures should be confirmed histologically also regarding the age of the injury.[10] Within about 2 weeks (though this is very variable), callus will form and be visible both on X-ray and by direct post-mortem inspection.[11] It is extremely difficult to date such callus.

Infant ribs are very pliable and, therefore, rib fractures in children after cardiopulmonary resuscitation (CPR) are rare. In four studies of consecutive series of autopsies after CPR, comprising altogether 720 children, the incidence of rib fractures varied between 0 and 2.1 per cent.[8,9,12,13] In a further autopsy series of 546 sudden unexpected deaths in infancy (SUDI) all of the resuscitation-related rib fractures were situated in the anterolateral chest supporting earlier observations by Saternus and Oehmichen and Betz and Liebhardt.[8,14,15] In very young infants, the possibility of older fractures dating back to birth injury cannot be dismissed, though again these are rare; however, sporadic cases have been reported in the literature.[16]

The sternum may be fractured by stamping or other frontal impacts, but far more force is necessary than with ribs. If posterior displacement of a fragment occurs, the underlying heart or great vessels may be severely damaged.

Haemorrhage and infection in the chest

Any injury to the chest wall or lung surface that breaches blood vessels and the pleural lining can lead to a haemothorax. Intercostal and, less often, mammary arteries can bleed into the pleural cavities, but most massive haemorrhage comes from large vessels in the lung or mediastinum. The lung hilum can be torn or penetrated by stabs wounds. Another obvious source of a haemothorax is the heart itself, though there must also be a defect in the pericardial sac before the blood can reach the chest cavity. Several litres of blood may accumulate in the chest, either as liquid or clot, or usually a mixture of both. Death may occur from loss of circulating blood volume, even if there is relatively little external bleeding (Fig. 6.5).

Many intrathoracic haemorrhages may be fatal with virtually no external blood loss, a fact that the police often find hard to credit if there is little blood at the scene of a fatal stabbing. A knife that passes obliquely into the chest through intercostal muscles may puncture a great vessel or heart chamber, allowing a fatal cardiac tamponade or haemothorax, yet the valve-like overlap of the tissues after withdrawal of the blade may seal up the external wound almost completely and prevent significant bleeding, especially as the blood inside the chest is not under any appreciable pressure.

The same may apply to a gunshot wound, where bleeding can be virtually absent if the wound is uppermost after death. Where the body lies above the wound, of whatever type, then considerable post-mortem gravitational leakage can take place.



Figure 6.5 Penetrating stab wound of chest, which has traversed the lung. The blade has passed through the upper lobe, crossed the interlobar fissure and re-entered the lower lobe. Death was caused by a haemothorax from severed branches of the pulmonary vessels within the lung.

Whatever the source of the bleeding, post-mortem haemorrhage can add very considerably to the volume found in the chest at autopsy. Due to the great variability of post-mortem coagulation – and subsequent lysis – much of the blood found at autopsy may not have been there at the moment of death. It is impossible to quantify this additional leakage in retrospect, but the ever-present possibility makes it unwise to be dogmatic about the amount of blood loss prior to death.

Infection following a chest wound is uncommon in forensic practice, as most deaths occur from haemorrhage within a relatively short time before infective sequelae have time to be established. Where survival is longer, then effective medical care usually prevents secondary infection. However, cellulitis, pleural inflammation and even empyema may supervene, especially where some dirty weapon is used, or where clothing or other foreign material has been carried into the wound. Infection may be of many types, but staphylococci, *Proteus*, coliforms and *Clostridium perfringens* are commonly found on culture.

Pneumothorax

Pneumothorax is caused by entry of air into pleural space either by disruption of the alveoli due to sudden increase of intrathoracic pressure as in blunt chest injury, or sharp penetrating injury, such as fractured rib or stab with a sharp instrument.

There are three types of pneumothorax:

1. A simple type where a leakage through the pleura allows air to enter the pleural cavity, but where the communication rapidly closes. The lung partly collapses, but if death does not supervene the air is soon absorbed. If the communication remains open, then a bronchopleural fistula ensues with air in the pleural cavity but, as it is not under pressure, like type 2, it will not bubble out when the autopsy 'water test' is attempted. Radiology is then the best means of demonstrating the air in the pleural cavity.
2. When the leak in the pleura (or rarely the chest wall) has a valve-like action, air is sucked into the pleural cavity at each inspiration, but cannot escape on expiration. This pumping action leads to a 'tension pneumothorax', which causes complete collapse of the lung onto its hilum and a shift of the mediastinum


Subpleural abscess or tuberculous cavity
Torn pleural adhesion
Blast injury
Burst emphysematous bulla
Punctured chest wall
Punctured lung
Barotrauma (decompression)

Figure 6.6 Common causes of pneumothorax.

to the opposite side. It is this type of pneumothorax that may be demonstrated at autopsy by penetrating an intercostal space under water, though radiology is a much better method of detection of all types of pneumothorax.

3. When an injury of the chest wall communicates with the pleural cavity, a 'sucking wound' may form with direct passage of air from the exterior. This type is most often seen in military surgery, and may be complicated by haemorrhage and infection.

A common traumatic cause of pneumothorax is a stab wound of the chest that allows direct communication with the exterior, though usually the layered skin and intercostal muscles closes the track when the weapon is withdrawn. The knife often enters the lung, however, so that air can enter the pleural cavity from the bronchi.

Natural disease can also cause a pneumothorax, which can lead to sudden death. Common causes are a ruptured emphysematous bulla, a tuberculous lesion at the lung periphery, or a tear at the site of a fibrous pleural adhesion (Fig. 6.6). This may initially appear suspicious, as in a case seen by the author (BK) in which a teenage boy bent down to tie a shoelace and fell dead. At autopsy the only finding was a pneumothorax that had been caused by a single pleural adhesion that had torn the visceral pleura. This illustrates the fact that sometimes a pneumothorax can cause sudden unexpected death, presumably via some vagal cardioinhibitory mechanism.

Injuries of the lungs

Bruising of the lungs is common in both open and closed chest injuries. Any substantial impact on the chest can contuse the lung surface or deeper parts. This may be beneath the area of impact or 'contrecoup' damage on the opposite surface. Deceleration injuries are seen in falls and traffic accidents, most commonly along the posterolateral surfaces where a vertical line of subpleural bruising occurs, often in the paravertebral gutter. The outline of ribs may be imprinted in lines of contusion on the pleural surface of the lungs. Bruising may be so severe as to form subpleural blood blisters, which may rupture to release blood or air into the pleural cavities.

In all severe chest injuries the central parts of the lung may show bleeding, sometimes sufficient to form actual haematomas with breakdown of lung tissue. Osborn describes 'pincer contusions' of the lung, where the expanded lower margins of the lungs become trapped in the narrow costophrenic angles.[17]

Laceration of the lung can occur in blunt injuries and even lobes or parts of a lobe may be detached. The hilum may tear and the pulmonary ligament below the hilum is a frequent site of haemorrhage. Vessels in the hilum (especially pulmonary veins) or those more peripherally, may be ripped, causing severe intrapleural or mediastinal haemorrhage. In children, lung injuries can occur without fracturing of the ribs, because of the greater elasticity of the latter and the ability of the chest wall to deform.

Penetrating injuries of the lungs are common, usually from stabbing by knives. The wounds may end in the lung parenchyma or in large vessels, or may be 'through-and-through' injuries that emerge to cause further damage to the heart or great vessels. They assist the pathologist by delineating the track and the direction of the stabbing, but due allowance must be made for the marked variation in topography during inspiration, compared with the collapsed state seen at autopsy.

Blast injury is dealt with elsewhere, but the lungs are the most vulnerable organs to this type of injury due to their large tissue–air interface.

Injuries of the heart

The heart is vulnerable to both penetrating and blunt injuries. A common form of homicide is a stab wound of the chest that penetrates the heart. The entry point may be anywhere over the praecordium or adjacent areas if the angulation of the track is sufficient. Sometimes the sternum is penetrated by a forceful blow that reaches the underlying heart, but most stab wounds enter via the intercostal spaces, or through a rib or costal cartilage.

Rarely, an upward stab from the abdomen reaches under the costal margin to penetrate the diaphragm. The right ventricle is often injured by a stab wound as it presents the largest frontal area, but the anterior interventricular septum and the left ventricle are also vulnerable. A shallow stab wound may enter the myocardium and not reach the lumen of the ventricle. In such a case there may be little disability unless a coronary vessel is severed, which may either cause death from myocardial insufficiency (if a major artery is transected) or cardiac tamponade (Figs 6.7, 6.8).



Figure 6.7 Even a small penknife can inflict a fatal wound. This injury was caused by a boy to a police officer when the latter was apprehending him for some minor offence. Though the blade was only about 6 cm long, this is sufficient to enter alongside the sternum and puncture the ventricular wall.



Figure 6.8 Stab wound penetrating the pericardium (reflected upwards) with a wound in the corresponding point on the heart. Death was caused by cardiac tamponade from leakage of blood from the ventricular lumen.

More often – especially in the right ventricle – the knife passes into the cavity. In the thin right ventricle this usually leads to copious bleeding into the pericardial sac even though the intraventricular pressure is relatively low because of the inability of the thin wall to close the defect by muscle overlap and contraction.

In the left ventricle, the contraction of the layered thick wall may partly or wholly seal the wound, and bleeding can be slight. It is, however, more common for persistent bleeding to occur and, if the drainage from the pericardial wound is less than the leakage from the ventricle, eventually a tamponade will develop. These variables make it impossible to calculate how long the victim was able to carry on with his activities, often a matter of dispute at a criminal trial. In general, wounds in the right ventricle are more dangerous than in the left because of the absence of the muscular 'self-sealing' effect.

Many stab wounds of the heart are transfixing or 'through-and-through' injuries, the knife entering one wall and emerging through another. If the left ventricle carries both wounds, the rapidity of bleeding may still not be torrential. Some of these wounds pass downwards and transfix the heart, then exit through the lower wall of the right ventricle and pass on via the diaphragm to end in the liver.

The cause of penetrating cardiac injuries varies according to the population and culture and access to guns, e.g. in the United States the ratio of gunshot wounds to stabbings is 2:1.[18]

Blunt injuries of the heart are seen in civilian practice mainly in traffic accidents, falls from a height and in stamping assaults, though any heavy impact (including a punch) can cause fatal damage. The exact incidence of cardiac contusion in blunt chest trauma is unknown and it is difficult to estimate it from the literature. The reported incidences vary depending on the definition and diagnostic criteria and range from 3 per cent to 71 per cent.[19–21] There are usually multiple rib and sometimes sternal fractures, with or without a flail chest. Occasionally there can be heart damage in an intact chest cage, especially in a child with a pliable thorax. Fatal blunt damage of the heart may occur, however, without a mark on the skin of the thorax nor damage to the bony chest cage. The cardiac injuries are usually on the front of the organ, especially to the right ventricle, though posterior bruising and laceration can occur if the heart is compressed against the thoracic spine, as in stamping assaults and steering wheel impacts (Fig. 6.9).[19,22,23]

All degrees of damage can occur, from mere epicardial bruising to lacerations that open the ventricular lumen widely. Internal damage to the heart may be present, without external signs of injury to either the heart or the external chest wall. The interventricular septum may be ruptured as a sole lesion, the mechanics of which seem obscure. In gross injuries, such as aircraft crashes, the whole heart may be avulsed from its root, to be found lying loose in the thorax. Histological damage, especially contraction band necrosis, can be found even when there is no macroscopic abnormality.



Figure 6.9 Ruptured interventricular septum as a result of impact on the front of the chest. The septum can tear without damage to the outer walls of the heart.

Haemopericardium and cardiac tamponade

Bleeding into the pericardial sac may occur from the surface or the cavities of the heart, or from the intrapericardial segments of the roots of the great vessels, particularly the aorta and pulmonary artery. Most causes of haemopericardium are from natural disease, such as a ruptured myocardial infarct or a ruptured dissecting aneurysm of the aorta (Chapter 25), but it is not an uncommon sequel to injury to the chest. When the damage has been caused by a stab that has perforated the pericardial sac, bleeding can escape into the pleural cavities, mediastinum or even abdomen if the diaphragm is penetrated. Death may occur from sheer blood loss if the haemorrhage can escape from the confines of the pericardium, but another common lethal condition is ‘cardiac tamponade’. Normally this double-walled sac contains a small amount (15–50 ml) of pericardial fluid. Essential in the tamponade is the rate of fluid accumulation in relation to pericardial stretch and other compensatory mechanisms.[24] In rapidly accumulating cardiac tamponade the limit of pericardial stretch can be exceeded with as little as 200 ml of fluid.[25] In slow pericardial effusion volumes of up to 1500 ml have been reported in uraemic patients.[26]

In the tamponade resulting from penetrating cardiac injury, blood can accumulate in the pericardial sac faster than it can escape, either because the bleeding rate exceeds the drainage or because the exit hole in the pericardium becomes blocked by blood clot. In cases where the bleeding is from a contusion or laceration of the heart, there is no escape route from the sac. When sufficient blood accumulates, the pressure in the pericardial sac increases and begins to prevent the passive filling of the atria during diastole. The cardiac output falls, as does the systemic blood pressure and the venous pressure rises. If unrelieved, death will follow, though the time that this takes is variable and almost impossible to calculate retrospectively on pathological findings. It has been stated that about 400–500 ml of blood is sufficient to cause death, though this seems a greater volume than is usually seen in tamponades.[27] Where trauma to the heart coexists, it is difficult to apportion the relative contribution to death of the tamponade as opposed to the other injuries.

Injuries to great vessels

The most vulnerable vessel is the aorta, which most commonly suffers injury in deceleration trauma from both road and air accidents, as well as from falls from a height. Jaffé and Sternberg reported a series of ten aortic ruptures half of which were flying accidents but, in general, before the Second World War traumatic rupture of the aorta was considered to be relatively rare.[28,29]

When the thorax is suddenly decelerated, the heart – being relatively mobile in the chest – attempts to continue in the original direction. This causes severe traction on the root of the heart, and a common sequel is complete or partial rupture of the aorta in the descending part of its arch. In falls from a height Fiddler claims that the lesion is the result of the abdominal and thoracic viscera being forced caudalwards by the abrupt deceleration when landing on the feet or buttocks.[30] Tannenbaum and Ferguson, however, postulate that the mechanism is a sudden rise in intra-aortic pressure.[31] Lasky has reviewed the biomechanics of impact injury of the aorta.[32]

According to Fiddler, rupture occurs almost constantly at a point 1.5 cm distal to the attachment of the ligamentum arteriosum, the remnant of the ductus. The lower thoracic aorta is closely bound to the anterior longitudinal ligament on the front of the dorsal spine, until it reaches the termination of the arch, where it curves forwards. This appears to be the weak point and transection occurs at this level, sometimes so cleanly that it looks like a surgical incision. The tear is annular and at right angles to the axis of the aorta. Sometimes, there may be multiple parallel intimal tears near the main transection, the so-called 'ladder-rung tears'. In deceleration trauma, these incomplete tears, which affect only the intima and inner media, may be found without major transection; where death is delayed, false aneurysms and dissections may be diagnosed on aortograms (Figs 6.10, 6.11).



Figure 6.10 The usual site of rupture of the aorta in deceleration injury.



Figure 6.11 Complete transection of the aorta in the distal part of the arch. The victim was a car driver who suffered a severe deceleration impact. There is also some pulmonary bruising.

The pulmonary artery is much less vulnerable to blunt trauma than the aorta but, in stamping assaults and steering wheel impacts, it may be damaged by depressed rib cage and sternal fractures. The pulmonary artery and vein branches may also be damaged in the root of the lung, where hilar tears are not uncommon. The great vessels are often involved in penetrating injuries, notably stab wounds. Stabs of the upper part of the chest may pass directly into the arch of the aorta, especially on the right side of the sternum. Here even a shallow injury may reach the aorta and the authors have seen several cases in which a short-bladed penknife has caused death in this way.

Stabs that are either too high, or are directed too laterally to puncture the chambers of the heart may penetrate the ascending aorta or the pulmonary artery. If the wound is below the reflection of the pericardium, a haemopericardium and perhaps cardiac tamponade may result. Other stab wounds may injure the heart valves or may enter the root of the lung to penetrate the large primary branches of the pulmonary artery or veins, causing gross bleeding into the corresponding pleural cavity or the mediastinum.

Abdominal injuries

As with the thorax, the damage caused by blunt and penetrating trauma of the abdomen depends upon the location of the injury (Figs 6.12, 6.13). In addition, the large area of the anterior abdomen occupied by the intestine provides a target for perforation with consequent chemical or infective peritonitis.

Open or penetrating wounds need little description, as they follow the characteristics of stab-like injuries in general. The liver, and especially the spleen, may bleed extensively, causing a haemoperitoneum. The intestine and mesentery are the other major targets, wounds often being multiple, because of the overlapping nature of the coils and their mesentery. The stomach, being partially protected by the rib margin, is less often penetrated from the abdomen, but is not uncommonly involved in chest stabbings that pass downwards through the diaphragm. The kidneys are rarely stabbed except from a thrust in the back.

Closed or blunt injury to the abdomen is common from both accidents and assault. Impact on the abdomen by a car steering wheel was more common before the widespread use of safety-belts and air-bags and still occurs in severe deceleration accidents. The liver, intestine, spleen and mesentery are most vulnerable. Crushing between two vehicles, or between a vehicle and a wall is another mechanism for abdominal trauma, and may also be seen in railway and industrial accidents where squeezing between two opposing surfaces occurs. In homicides, assaults and child abuse, kicking, stamping and heavy punching can also cause blunt injury to the abdomen.



Figure 6.12 Surface anatomy of liver, stomach and heart.

Whatever the mechanism of infliction, the following features may be present:

- Bruising of the abdominal wall, both of the skin and the underlying muscles, is often (but by no means invariably) seen in abdominal trauma. Where subcutaneous bleeding is profuse it may track from the initial area of impact to become more diffuse and may cover a large area of abdominal wall, especially in the lower segment. Blood may track down the inguinal canal and appear in the scrotum or labia (Fig. 6.14).



Figure 6.13 Posterior view of trunk to show surface relations of organs.



Figure 6.14 Abdominal wall bruising with fatal intraperitoneal haemorrhage from a ruptured mesentery. There is also a large haematocele from a gang attack in which repeated kicking occurred.

More often there are discrete bruises on the abdominal skin, associated in some instances with surface abrasions. Kicks will usually leave scuffed abrasions if tangential, unless protected by clothing. Fingertip or knuckle bruises may be seen, especially in child abuse. In infants, bruises may be seen on the sides of the abdomen where adult fingers have forcibly gripped or lifted the child, though these are more common in the axillary line of the chest.

Severe or fatal intra-abdominal injury may be present, however, without any mark on the skin. This can occur if clothing protects or if a blunt impact is applied over, a relatively large surface. In child abuse, for example, the liver, mesentery or duodenum can be ruptured with no external sign whatsoever.

- Extensive bleeding into the peritoneal cavity, usually from rupture of a solid viscus or bleeding from the mesentery.
- Bruising or rupture of the stomach and diaphragm. The stomach is less vulnerable than the intestines, but may be lacerated by a heavy blow in the upper abdomen, especially when full of food or fluid.
- The intestine and its mesentery are frequently damaged in abdominal trauma. Extensive bruising of the gut and its vascular mesentery may occur, mainly from being crushed against the prominent lumbar vertebrae in the midline (Fig. 6.15). The duodenum and jejunum are particularly vulnerable to transection from being compressed against the spine, especially in children, where a heavy blow in the central or upper abdomen can cut through the third part of the duodenum almost as cleanly as a scalpel. Laceration of the mesentery is not uncommon both in traffic accidents and assaults. The same mechanism of compression against the lumbar spine causes bruising and tearing of the central parts of the mesentery, which usually occurs towards the intestinal margin of the membrane. Multiple fenestrations may be seen, presumably because folds of mesentery overlie each other and are injured when in apposition.



Figure 6.15 Injury or rupture of intestine or mesentery in violent blow to the upper central abdomen. Because of its small size and the thin abdominal wall, the infant duodenum is especially vulnerable.

Severe and intractable bleeding can occur in circumstances where surgical treatment is often not offered because the condition is unrecognized. Kicks and punches in the abdomen may be sustained by drunken persons who may be apparently unaware of the seriousness of their injuries until collapse and death supervene, perhaps hours later.

In a case seen by the author (BK), a man was involved in a fight and then allegedly assaulted the police. He was forcibly restrained and may have been struck in the abdomen by a knee. He remained apparently well, though drunk, in a police cell for more than 5 hours, before collapsing and dying on his way to the lavatory, never having complained of any abdominal pain. Autopsy revealed several litres of blood in his peritoneal cavity, which had escaped from several large tears in the mesentery. Similar bleeding from mesenteric lacerations has been seen in abused infants, where the thin abdominal wall provides little protection from blows on the abdomen.

Injury to the mesentery may damage local arteries without causing severe bleeding, but may occlude or thrombose them, with infarction of the bowel as a consequence. Perforation may be delayed for a day or two and in children and old people there need not be the dramatic symptoms of the onset of peritonitis that is usually seen in clinical surgical practice.

The colon is rarely injured unless the abdominal injury is gross. One well-known lesion is rupture of the rectum or sigmoid by a high-pressure air hose being placed in or near the anus as a practical joke.[33–35]

- Rupture of the spleen is a common surgical emergency after trauma but may be first found at autopsy if undiagnosed, or if death occurs from lack of speedy surgical treatment, or if other injuries made recovery impossible. An enlarged spleen is more vulnerable and more fragile than a normal organ. Malaria, glandular fever and other infections increase the risk of rupture.[36,37] The 'stiletto' dagger was specifically designed in medieval Italy for puncturing the enlarged malarious spleen by an upward blow under the left costal margin (Fig. 6.16).
- The spleen can be damaged either from impact on its surface or from traction on its pedicle. The rupture may be immediate or may be delayed if a large subcapsular haematoma and underlying tear are held intact for a time by the capsule. This delay can last for a number of days or even weeks.[38,39]



Figure 6.16 Laceration of the spleen following lower chest impact during a road traffic accident.



Figure 6.17 Complete bisection of the liver in a high-speed deceleration during a traffic accident. The abdomen of the driver was hurled against the steering wheel as he was projected through the windscreen.

- Rupture of the liver is also a common lesion following serious abdominal trauma, such as fall from a height or a crush injury between two wagons. It is seen especially in traffic accidents, either from impact of the driver on the rim or centre of the steering wheel or by the unrestrained passenger being thrown against the fascia. A pedestrian can also suffer a ruptured liver either as a primary impact from a vehicle or as secondary damage from being thrown to the ground (Fig. 6.17).[40–43]

  A more recent cause of liver injury is enthusiastic external cardiac massage. Even if death has already taken place, there may still be a significant amount of blood oozing from the liver tears into the peritoneal cavity. Moritz has described six varieties of hepatic laceration, but such a differentiation is of little practical use.[27] The liver may show one or more linear cracks, most often on the convex upper surface, which may be of any severity from superficial subcapsular tears to complete transection of the organ. Not infrequently, several roughly parallel tears are seen on the upper surface, obviously from the same type of mechanical stress. The surface lacerations may extend deeply into the liver and may even appear on the opposite surface. Occasionally, there may be internal tears that do not communicate with the surface. As in the spleen, a subcapsular haematoma can reach a large size before bursting into the peritoneal cavity, causing a delay in collapse or death.

  Infants readily suffer liver damage from trauma and it is a well-known component of the child abuse syndrome. Liver tears can occur during the process of birth, particularly in breech presentation.
- Injuries to the kidney. Being deeply situated at the back of the abdomen in the paravertebral gutter, the kidneys are rarely damaged by frontal trauma, but may be involved in kicks or heavy blows to the loin. Traffic impacts, mainly in pedestrians, can damage the kidney, but kicking is another cause of this rather uncommon injury. When a victim is lying on the ground, a swinging boot can conveniently enter the slightly raised arch between the rib margin and hip, where the kidney is situated.

  Perirenal haemorrhage is much more common than damage to the actual organs themselves, but when they are injured, all grades of damage from comminuted pulping through transection to shallow surface lacerations may be seen. Like the mesentery and spleen, damage to vessels may lead to post-injury infarction. The suprarenal vessels can be damaged by impact and, statistically, the right suprarenal artery is more often involved in traffic accidents in Britain because the direction of traffic tends to favour lesions on that side. It is, however, difficult to differentiate direct trauma to the suprarenal vessels from the common post-stress haemorrhages, often bilateral, of the Waterhouse–Friderichsen type. These occur quite commonly a few days after any trauma, surgical operation or infection, and are rarely diagnosed by clinicians (see Chapter 13).[44]

Foreign bodies in the gut

Though not usually a feature of trauma, foreign bodies and material are not infrequently found in the alimentary system in forensic practice, both clinically and at autopsy.

Disorders of the mental state may lead to extraordinary numbers of objects being swallowed, which may be present anywhere from mouth to anus, but especially in the stomach. Betz *et al.* describe two such deaths, where, in one, 2000 cm^3 of debris, including broken glass, was in the alimentary tract; the other suffered intestinal obstruction due to ingestion of a large quantity of his own hair.[45]

Similar aberrations may lead to insertion of foreign objects into the rectum, urethra, bladder and vagina.[46–55] The authors have seen large objects of various types, e.g. potatoes in the rectum, lengths of broom handle and wood in the colon (one penetrating the liver) and a banana and a beer can in the vagina. Sexual perversions, masturbation and heterosexual or homosexual activities may account for these, as well as frank mental abnormality.

In recent years, the smuggling of narcotics through ports and airports has commonly been accomplished by 'body-packing', the drugs being concealed in condoms, which are then either swallowed or, less often, inserted into the rectum or vagina. Deaths have occurred in these body-packers, usually by rupture of a package within the gut, so that a massive dose of heroin or cocaine is released with all the attendant toxic effects.[56–68] Rarely, the mass of illicit material may cause intestinal obstruction, leading to a surgical emergency, which the carrier does not wish to be investigated, for obvious reasons.

Injuries to the pelvis and pelvic organs

The bony pelvis suffers a variety of fractures and dislocations in severe trauma:

- Where great pressure is applied to the front of the abdomen or pubic area – as in running over by a vehicle wheel – the pelvis may be splayed open, the symphysis parting and one or both sacroiliac joints becoming dislocated.
- An impact from the side may shatter the superior and, less often, the inferior pubic ramus, and again dislocate the sacroiliac joint on that side.
- A fall from a height onto the feet may transmit the force up the legs either to dislocate the hips or even to drive one or both femoral heads through the acetabulum. If the hip joints remain intact, the pelvic girdle may crack and again the sacroiliac joints may be sheared apart.
- A kick or heavy fall onto the base of the spine may fracture the coccyx or sacrum.

The pelvic organs with the exception of the bladder are generally protected from all but the most severe trauma. When it is full, the bladder can be ruptured by heavy blows or kicks on the lower abdomen.[69] The empty bladder is rarely injured by blunt trauma. The male urethra is also vulnerable to direct trauma, such as falling astride a solid object like a gate, or being kicked in the crotch, both of which compress the urethra against the undersurface of the pubis.[70,71]

The external genitals may suffer injury, apart from the sexual assaults discussed in Chapter 18. The scrotum is vulnerable to severe bruising, especially from kicks: a large haematocele may develop. Scrotal and vulval injuries can occur from falling astride an object or in traffic accidents. Impact of a bicycle wheel between the legs is one such cause.

Complications of abdominal injury

The most common fatal sequel to intra-abdominal trauma is haemorrhage from any of the contained organs. The spleen and mesentery tend to bleed most copiously and quickly, though even here there can be a delay of many hours before serious symptoms are obvious – and, in the case of a subcapsular laceration of the spleen, the time can be far longer. The liver tends to ooze more slowly unless a major injury opens a large vessel or an extensive area of hepatic tissue.

The mesentery contains numerous blood vessels that are not covered by parenchymatous tissue as in the liver or spleen, so bleeding is usually brisk from significant tears – although, as illustrated by the case described above, even this injury can lead to delayed death.

Because all bleeding in the abdomen, unless it is from a wound of the aorta, takes time to accumulate, restriction of the victim's activity immediately after the injury need be minimal or absent unless there are other factors involved. It is never safe for a pathologist to declare that rapid immobility must have ensued, unless there are other gross injuries.

As mentioned in relation to intrathoracic bleeding, some of the blood found at autopsy within the peritoneal cavity may have accumulated there after death, adding to the true ante-mortem volume.

In spite of common surgical experience, even severe intra-abdominal injuries leading to bleeding need not necessarily be painful, especially in the commonly associated circumstance of the victim being under the influence of alcohol.

Perforation of the gastrointestinal canal is another serious complication of trauma, though often death ensues from the totality of injuries before infection can become established. As in natural perforated peptic ulcer, penetration of the stomach or duodenum will cause a chemical peritonitis that can be a cause of severe and immediate shock – perhaps a major factor in a rapid death. Rupture of the small or large intestine is less damaging but, if survival continues, will inevitably lead to generalized peritonitis unless vigorously treated. Open wounds of the abdomen, including stabbing, will introduce organisms from the outside into the peritoneal cavity. In addition to infection, trauma to the intestine may cause an intractable ileus; if the pancreas is damaged, there may be widespread fat necrosis in the mesentery and omentum.[72,73]

References

1 Leadbeatter S, Knight B. Resuscitation artefact. *Med Sci Law* 1988;28(3):200–4.
2 Plunkett J. Resuscitation injuries complicating the interpretation of premortem trauma and natural disease in children. *J Forensic Sci* 2006;51(1):127–30.
3 Bode G, Joachim H. [Differential diagnosis of accident and resuscitation traumas]. *Z Rechtsmed* 1987;98(1):19–32.
4 Buschmann CT, Tsokos M. Frequent and rare complications of resuscitation attempts. *Intensive Care Med* 2009;35(3):397–404.
5 Gunther WM, Symes SA, Berryman HE. Characteristics of child abuse by anteroposterior manual compression versus cardiopulmonary resuscitation: case reports. *Am J Forensic Med Pathol* 2000;21(1):5–10.
6 Klintschar M, Darok M, Radner H. Massive injury to the heart after attempted active compression-decompression cardiopulmonary resuscitation. *Int J Legal Med* 1998;111(2):93–6.
7 Hoke RS, Chamberlain D. Skeletal chest injuries secondary to cardiopulmonary resuscitation. *Resuscitation* 2004;63(3):327–38.
8 Betz P, Liebhardt E. Rib fractures in children—resuscitation or child abuse? *Int J Legal Med* 1994;106(4):215–8.
9 Bush CM, *et al.* Pediatric injuries from cardiopulmonary resuscitation. *Ann Emerg Med* 1996;28(1):40–4.
10 Weber W. [Quantitative investigations concerning penetrating wounds of the human skull (author's transl)]. *Z Rechtsmed* 1974;74(2):111–16.
11 Rao P, Carty H. Non-accidental injury: Review of the radiology. *Clin Radiol* 1999;54(1):11–24.
12 Price EA, *et al.* Cardiopulmonary resuscitation-related injuries and homicidal blunt abdominal trauma in children. *Am J Forensic Med Pathol* 2000;21(4):307–10.
13 Spevak MR, *et al.* Cardiopulmonary resuscitation and rib fractures in infants. A postmortem radiologic-pathologic study. *JAMA* 1994;272(8):617–18.
14 Saternus KS, Oehmichen M. Cardiopulmonal reanimation in infants [Kardiopulmonale reanimation bei sauglingen]. *Notarzt* 1985;1(4):77–81.
15 Weber MA, *et al.* Rib fractures identified at post-mortem examination in sudden unexpected deaths in infancy (SUDI). *Forensic Sci Int* 2009;189(1–3):75–81.
16 van Rijn RR, Bilo RA, Robben SG. Birth-related mid-posterior rib fractures in neonates: a report of three cases (and a possible fourth case) and a review of the literature. *Pediatr Radiol* 2009;39(1):30–4.
17 Osborn GR. Findings in 262 fatal accidents. *Lancet* 1943;242(6262):277–84.
18 Kang N, *et al.* Penetrating cardiac injury: overcoming the limits set by Nature. *Injury* 2009;40(9):919–27.
19 Sybrandy KC, Cramer MJ, Burgersdijk C. Diagnosing cardiac contusion: old wisdom and new insights. *Heart* 2003;89(5):485–9.
20 McGillicuddy D, Rosen P. Diagnostic dilemmas and current controversies in blunt chest trauma. *Emerg Med Clin North Am* 2007;25(3):695–711, viii–ix.
21 Holanda MS, *et al.* Cardiac contusion following blunt chest trauma. *Eur J Emerg Med* 2006;13(6):373–6.
22 Gonin J, *et al.* Cardiac contusion and hemopericardium in the absence of external thoracic trauma: case report and review of the literature. *Am J Forensic Med Pathol* 2009;30(4):373–5.
23 Koehler SA, *et al.* Cardiac concussion: definition, differential diagnosis, and cases presentation and the legal ramification of a misdiagnosis. *Am J Forensic Med Pathol* 2004;25(3):205–8.
24 Spodick DH. Acute cardiac tamponade. *N Engl J Med* 2003;349(7):684–90.
25 Restrepo CS, *et al.* Imaging findings in cardiac tamponade with emphasis on CT. *Radiographics* 2007;27(6):1595–610.
26 Reddy PS, *et al.* Cardiac tamponade: hemodynamic observations in man. *Circulation* 1978;58(2):265–72.
27 Moritz A. *The Pathology of Trauma*. Philadelphia: Lea & Febiger, 1942.
28 Jaffé RH, Sternberg H. Der fliegertod. Ein beitrag zur frage der traumatischen aortenrupturen. *Vrtljschr f gerichtl Med* 1919;58:74–90.
29 Strassman G. Traumatic rupture of the aorta. *Am Heart J* 1947;33(4):508–15.
30 Fiddler J. *The Pathology of Traumatic Injury*. Edinburgh: Livingstone, 1946.
31 Tannenbaum I, Ferguson JA. Rapid deceleration and rupture of the aorta. *Arch Pathol (Chic)* 1948;45(4):503–5.
32 Lasky I. Human aortic laceration due to impact. In: Wecht C (ed). *Legal Medicine Annual*. New York: Appleton Century Crofts, 1974.
33 Kim SJ, *et al.* Pneumatic colonic rupture accompanied by tension pneumoperitoneum. *Yonsei Med J* 2000;41(4):533–5.
34 Suh HH, Kim YJ, Kim SK. Colorectal injury by compressed air – a report of 2 cases. *J Korean Med Sci* 1996;11(2):179–82.
35 Comlin JC. Pneumatic rupture of the colon. *Br Med J* 1952;1(4761):745–6.
36 Bell JS, Mason JM. Sudden death due to spontaneous rupture of the spleen from infectious mononucleosis. *J Forensic Sci* 1980;25(1):20–4.
37 Lippstone MB, *et al.* Spontaneous splenic rupture and infectious mononucleosis in a forensic setting. *Del Med J* 1998;70(10):433–7.
38 Kodikara S. Death due to hemorrhagic shock after delayed rupture of spleen: a rare phenomenon. *Am J Forensic Med Pathol* 2009;30(4):382–3.
39 Abeyasinghe N. Delayed rupture of spleen in a case of spouse abuse. *J Clin Forensic Med* 1999;6(4):243–5.
40 Sutton BC, *et al.* Fatal postpartum spontaneous liver rupture: case report and literature review. *J Forensic Sci* 2008;53(2):472–5.

41 Toro K, *et al.* Fatal traffic injuries among pedestrians, bicyclists and motor vehicle occupants. *Forensic Sci Int* 2005;151(2–3):151–6.

42 Miltner E, *et al.* Liver and spleen ruptures in authentic car-to-car side collisions with main impact at front door or B-pillar. *Am J Forensic Med Pathol* 1992;13(1):2–6.

43 Vock R. Liver rupture caused by isolated blunt force impact: the result of a blow, a kick or a fall? *Int J Legal Med* 2001;114(4–5): 244–7.

44 Knight B. Sudden unexpected death from adrenal haemorrhage. *Forensic Sci Int* 1980;16(3):227–9.

45 Betz P, van Meyer L, Eisenmenger W. Fatalities due to intestinal obstruction following the ingestion of foreign bodies. *Forensic Sci Int* 1994;69(2):105–10.

46 Busch DB, Starling JR. Rectal foreign bodies: case reports and a comprehensive review of the world's literature. *Surgery* 1986;100(3):512–9.

47 Goldberg JE, Steele SR. Rectal foreign bodies. *Surg Clin North Am* 2010;90(1):173–84, Table of Contents.

48 Kurer MA, *et al.* Colorectal foreign bodies: a systematic review. *Colorectal Dis* 2010;12(9):851–61.

49 Yaman M, *et al.* Foreign bodies in the rectum. *Can J Surg* 1993;36(2):173–7.

50 Rieder J, *et al.* Review of intentionally self-inflicted, accidental and iatrogetic foreign objects in the genitourinary tract. *Urol Int* 2010;84(4):471–5.

51 Rafique M. Intravesical foreign bodies: review and current management strategies. *Urol J* 2008;5(4):223–31.

52 Ahmad M. Intravaginal vibrator of long duration. *Eur J Emerg Med* 2002;9(1):61–2.

53 Kihara M, *et al.* Magnetic resonance imaging in the evaluation of vaginal foreign bodies in a young girl. *Arch Gynecol Obstet* 2001;265(4):221–2.

54 Melamed Y, *et al.* Foreign objects in the vagina of a mentally ill woman: case series. *Gen Hosp Psychiatry* 2007;29(3):270–2.

55 Nwosu EC, *et al.* Foreign objects of long duration in the adult vagina. *J Obstet Gynaecol* 2005;25(7):737–9.

56 Book RG. Body packing with a twist. *Am J Forensic Med Pathol* 1993;14(2):170.

57 Bruck S, *et al.* [Atypical 'body packing syndrome' – a case report]. *Arch Kriminol* 2006;218(1–2):35–43.

58 Bulstrode N, Banks F, Shrotria S. The outcome of drug smuggling by 'body packers' – the British experience. *Ann R Coll Surg Engl* 2002;84(1):35–8.

59 Cawich SO, *et al.* Colonic perforation: a lethal consequence of cannabis body packing. *J Forensic Leg Med* 2010;17(5):269–71.

60 Gherardi R, *et al.* A cocaine body packer with normal abdominal plain radiograms. Value of drug detection in urine and contrast study of the bowel. *Am J Forensic Med Pathol* 1990;11(2):154–7.

61 Hutchins KD, *et al.* Heroin body packing: three fatal cases of intestinal perforation. *J Forensic Sci* 2000;45(1):42–7.

62 Kashani J, Ruha AM. Methamphetamine toxicity secondary to intravaginal body stuffing. *J Toxicol Clin Toxicol* 2004;42(7): 987–9.

63 Koehler SA, *et al.* The risk of body packing: a case of a fatal cocaine overdose. *Forensic Sci Int* 2005;151(1):81–4.

64 Lutz FU, Reuhl J. [Body packing as a fatal risk – results of a questionnaire survey in Western Europe]. *Beitr Gerichtl Med* 1992;50:211–4.

65 Nichols GR 2nd, Davis GJ. Body packing with a twist. Death of a salesman. *Am J Forensic Med Pathol* 1992;13(2):142–5.

66 Rouse DA, Fysh R. Body packing presenting as sudden collapse. *Med Sci Law* 1992;32(3):270–1.

67 Wetli CV, Rao A, Rao VJ. Fatal heroin body packing. *Am J Forensic Med Pathol* 1997;18(3):312–8.

68 Wilcher G. Drug-related deaths with evidence of intracorporeal drug concealment at autopsy: five case reports. *Am J Forensic Med Pathol* 2011;32(4):314–8.

69 Lunetta P, Penttila A, Sajantila A. Fatal isolated ruptures of bladder following minor blunt trauma. *Int J Legal Med* 2002;116(5):282–5.

70 Henn V, *et al.* [Morphology and phenomenology of death by kicking (II)]. *Arch Kriminol* 2000;205(3-4):65–74.

71 Strauch H, *et al.* Kicking to death – forensic and criminological aspects. *Forensic Sci Int* 2001;123(2–3):165–71.

72 Higashitani K, *et al.* Complete transection of the pancreas due to a single stamping injury: a case report. *Int J Legal Med* 2001;115(2):72–5.

73 Rouge-Maillart C, *et al.* Fatal blunt pancreatic trauma secondary to assault and battery: a case report. *Int J Legal Med* 2001;115(3):162–4.

CHAPTER 7

Self-Inflicted Injury

- Introduction
- Suicidal injuries
- Self-inflicted injuries other than suicide
- References

Introduction

Injuries that are deliberately self-inflicted are common and their examination is a frequent task for both pathologists and clinical forensic practitioners. These events consist of five main categories of non-accidental, self-inflicted injuries:

- Suicidal acts (suicide, attempted suicide and suicidal gestures), the latter lacking the intention to kill though death may inadvertently ensue.
- Non-suicidal self-inflicted trauma such as:
  - self-mutilation for the purpose of insurance fraud
  - self-inflicted bodily harm or self-mutilation among soldiers and prisoners
  - self-mutilation and other forms of self-induced bodily harm in psychiatric patients
  - simulated offenses (fictitious sexual offences, feigned robbery or alleged assaults with a political or xenophobic background).[1–3]

One of the most difficult decisions that can face pathologists, medical examiners and legal authorities, such as coroners, is the differentiation between homicide, suicide, accident and other self-inflicted injury. Though it is not the legal function of a pathologist to attribute motive, his experience and training are often the factors that lead the official authority to make a decision as to the classification of the manner of death or injury. One such situation is fatal auto-erotic activities, described in Chapter 15.

In addition, when a pathologist is assisting the police in the early stages of a death investigation, his opinion and decision about the manner of the death may be crucial in initiating or aborting a homicide investigation – an onerous decision which may have serious and expensive consequences if wrong. It is therefore a most important function of the forensic pathologist to decide on the evidence of a death scene and subsequent autopsy whether murder, suicide or accident is the most likely explanation.

Self-inflicted injury, when not suicidal, is often not fatal and the pathologist is usually not consulted unless he also includes clinical forensic medicine in his work. The pathologist may, however, be asked for his opinion, as he is a specialist in trauma and may be able to provide the most useful opinion available. In other cases, self-inflicted injury, which the victim did not intend to be fatal, may end in death from a variety of causes and thus the pathologist will be directly involved.

Suicidal injuries

This discussion is confined to physical trauma, self-poisoning being considered later in the book.

Suicides may injure themselves in many different ways, some bizarre in the extreme. The pathologist must always be alert to the possibility that such injuries are not true suicides, but some manifestation of peculiar practices that have taken a course unintended by the victim. A prime example is masochistic asphyxia, which is still sometimes mistaken for suicide (Chapter 15). Even more serious is the homicide that appears to be a suicide, though the reverse also occurs.

Suicides, apart from poisoning, may use one (or even more) of the following methods, though the list is by no means exclusive:

- stabbing and cutting
- firearms and explosives
- jumping from a height

- jumping into water
- burning
- suffocation, e.g. plastic bag
- hanging and strangulation
- electrocution
- road and railway injuries.

Most of these modes are discussed in the appropriate chapters.

Suicidal knife wounds

Many incised and stab wounds are self-inflicted, either from motives of self-destruction, from mental aberrations or deliberately for some form of gain. These must be differentiated from each other, and from accidental and homicidal wounding. Sometimes the distinction may be difficult and even impossible, but the experience of the forensic pathologist is paramount in assisting investigative agencies to come to the correct conclusion. Suicide, attempted suicide and suicidal gestures commonly employ cutting weapons as the means of injury. There are certain features that are quite reliable pointers to these motives, though they are by no means infallible:[1,2,4–9]

- Suicidal knife wounds favour certain 'sites of election', which are predominantly the throat, the wrists and the front of the chest. As with most violent methods, cut throat and chest stabbing is predominantly seen in males – though cutting wrists is not uncommon in females (Fig. 7.1).
- Suicidal wounds are typically multiple, often being characterized by a number of preliminary trial cuts, called 'tentative incisions'. These are most often seen on the throat and wrists, where the person often makes a series of shallow incisions, presumably hesitating while gaining courage to make a final decisive cut. In many suicidal attempts the subject abandons this method after a few trial incisions and uses some other method of self-destruction. Although the presence of tentative incisions is strong presumptive evidence of suicide, exceptions do occur, and the pathologist must take all other aspects of the scene into account before giving an opinion to the investigators. In fact, the almost absolute statements of some older textbooks that tentative incisions must indicate suicide, is to be disregarded. The author (BK) has dealt with two murders in which 'typical' suicidal injuries were present on wrist or throat causing considerable doubt to the investigators until other factors clarified the situation (Fig. 7.3).
- A suicidal cut throat usually has these trial incisions; there may be only one or two, or there may be scores of trial cuts. If successful, there will be one or more deep incisions superimposed, which may destroy some of the previous shallow cuts. The classical description of the cut throat is of incisions starting high on the left side of the neck below the angle of the jaw, which pass obliquely across the front of the neck to end at a lower level on the right. This assumes that the victim is right-handed, the obliquity being reversed in a left-handed person. The cuts are said to be deeper at their origin, becoming shallower as they cross the throat, tailing off into surface cuts at the extremity (Fig. 7.2).



Figure 7.1 Sites of election in violent suicide.

This description, though hallowed by repetition in many textbooks, is often incorrect and many cut throats have horizontal cuts that show no variation in depth at either end. Most suicides appear to raise the chin to provide better access to the throat, so that the skin is stretched when cut. This tends to cause straight-edged incisions, rather than the jagged cut (the so-called 'dentele' toothed incision) seen when a knife is drawn over loose skin. Throwing back the head moves the carotid bundle under the protection of the sternomastoid muscles and, if the cuts are confined to the centre of the front of the neck, only the larynx or trachea may be damaged, rather than large blood vessels.

Death from a cut throat depends on the nature and extent of local damage to the neck. Severe haemorrhage from the jugular veins, or less often the carotid arteries, may lead to death from exsanguination (Figs 7.4–7.6).



Figure 7.2 Suicidal cut throat. The wounds are horizontal, rather than the more common sloping-down from left to right in a right-handed person. The numerous 'tentative cuts' are the hallmark of self-infliction, though there are rare exceptions. The larynx has been entered and death was due to aspiration of blood into the air-passages. The great vessels in the neck were undamaged.



Figure 7.3 Homicidal cut throat, simulating a suicide. There are several apparently 'tentative cuts', but the deep penetrating central laceration and adjacent stab wound is atypical. The face is congested and shows some petechiae from prior pressure on the neck.



Figure 7.4 Homicidal cut throat, showing single slash with no tentative cuts. Clean-cut edges with no sign of repetitive strokes, severing muscles, larynx and some large vessels.



Figure 7.5 Gaping laceration in front of the neck of a mental patient, who on leave from a psychiatric hospital, had used a frame saw to commit suicide (see also Fig. 7.6).



Figure 7.6 Back of the neck showing marks of the saw teeth around the laceration and medulla at the bottom (arrow). Mental patient, who on leave from a psychiatric hospital, had used a frame-saw to commit suicide (see also Fig. 7.5).

If the larynx or trachea is opened, then even relatively minor haemorrhage from local vessels may cause blockage of the airways by blood and clot, though many slashed air-passage victims survive. A rare cause of death is air embolism, caused by aspiration into cut jugular veins while standing or sitting with the neck at a higher level than the thorax. The possibility that the victim of a cut throat may have died from some unrelated cause must always be borne in mind. Many suicides either use multiple methods of suicide to ensure success – or may abandon the pain of a cut throat for some other mode, such as poison or a fall from a height (Fig. 7.10).

- Deliberate cutting of the wrists is rarely effective as the sole method of suicide, but it is a common injury (Fig. 7.8). Many suicides from other causes are seen at autopsy to have scars on the wrists from previous unsuccessful attempts or gestures. The usual site is on the flexor surface at the level of the skin flexion creases. As with the neck, there may be a number of shallow tentative incisions, but commonly several deep gashes are made without trial cuts. The left wrist is the more common target, because more than 90 per cent of the population show right-handed dominance.[10–12] Several studies have also suggested that males are more prone to left-handedness than females (Fig. 7.7).[13,14]

As with the neck, there is a tendency for the victim to hyperextend the wrist before making the cut, which causes the radial artery to slip into the shelter of the lower end of the radius. The knife cuts may then miss major blood vessels and merely divide flexor tendons, though many cuts are too shallow to cause anything but superficial damage. Most cut wrists are but an accompaniment to other more effective methods of self-destruction. Once again, the presence of tentative cuts, though very significant, cannot be unquestioningly accepted as an exclusion of homicide.

- Suicidal injuries of the chest are almost always stab wounds. Sometimes linear incised cuts are made over the precordium or more widely over the front of the chest; these may be multiple, parallel and sometimes criss-cross, but rarely do any serious damage. Stab wounds are usually over the left side of the chest where common knowledge places the heart, but they may be alongside the sternum or even on the right side. The wound is often single, but multiple wounds are not uncommon (Fig. 7.9). Though naturally a series of severe wounds always raises the presumption of homicide, many undoubted suicides can inflict a number of injuries upon themselves, each potentially fatal. The author (BK) has seen a suicide in a doctor, where eight severe knife wounds of the lower chest had created a large external defect and detached a portion of liver.



Figure 7.8 Self-inflicted cuts on the wrist of a suicide with ample haemorrhage indicating vitality of the wounds (A). For comparison, post-mortem cuts on the wrist of a dismembered homicide victim (B).



Figure 7.7 Numerous self-inflicted cuts on the wrist, as part of a futile suicide attempt. Most of these attempts fail and the person turns to another method of self-destruction.



Figure 7.9 Suicidal stab wound of heart. The front of the chest is one of the suicidal sites of predilection; multiple stabs do not exclude self-infliction.



Figure 7.10 A combination of two suicide methods, by firearm and hanging. The man had stood on a stool with a noose around his neck and then shot himself through the forehead. The entrance wound is seen in the forehead (white arrow) and the double ligature mark around the neck shows ecchymoses on the ridge between the two furrows (black arrow).

Suicidal knife wounds are not often made in the abdomen, though they do occur, sometimes to the extent of disembowelling. The author (PS) has seen a suicide in a person, where several meters of the gut had been removed through a single and relatively small incision before dying of exsanguination. There is usually frank mental abnormality present in these cases, which merge into the self-mutilation described below.

- Stab wounds of the neck are uncommon in suicide, but are recorded (such as those described by Gee and Watson, where actual transfixion of the neck was achieved).[15]
- The position of the clothing in suicidal knife wounds is equivocal. It is more common for the self-stabber to lift the garments to expose the area of chest or abdominal skin to be attacked, but exceptions are common and the point has little diagnostic significance.

Suicidal firearm wounds

The characteristics of gunshot wounds are fully discussed in Chapter 8 but, as far as suicide is concerned, the following salient features may be repeated:[16–21]

- Females rarely shoot themselves. In Britain, a shot female is a murdered female until proved otherwise, though – as always – exceptions do occur, especially in communities where firearms are commonplace, such as farming or hunting areas.
- The weapon must always be present.
- The range must be within arm's length, depending upon the nature of the weapon and excluding some mechanical device to fire the gun. The pathologist may be asked if a dead person could have reached the trigger of a rifle or long shotgun, which may have been placed against the neck, head or chest. Having first established that the entry wound was close contact, the length of the gun from muzzle to trigger can be measured and compared with the distance from wound to tip of finger. It must be remembered, however, that the length of the limb after death, especially if rigor is present, is not necessarily the same as in life when mobile joints and muscles may have allowed a slightly longer reach than that measured after death. Allowance must also be made for lateral or other flexion of the trunk, and mobility of the shoulder girdle before declaring dogmatically that the victim could not have fired the gun and therefore did not shoot himself.
- Sites of election are the temple, the neck, the mouth and the chest. Suicides rarely shoot themselves in the eye or abdomen. The lifting of clothing to expose bare skin, usually in the chest, is very variable, and has even less significance in differentiating suicide from homicide or accident than in knife wounds.[22]
- Shooting in anatomically inaccessible sites cannot be suicide.
- It is not true that suicides always shoot themselves in the head on the same side as their dominant hand.
- It is difficult to differentiate homicide from accident, even though the circumstances may be suggestive. The distance of discharge may be beyond arm's reach in both, the weapon may be missing in both, inaccessible sites may be shot in both and sites of suicidal election may not be used in both.

Suicide by submersion

This is a common mode of self-destruction, in both males and females. It has a marked geographical variation as a favoured method of self-destruction, naturally depending on the availability of water – it is relatively infrequent in Egypt, but very common in the west of Ireland.

Either large bodies of water, such as rivers, lakes or seas may be used – or the bathtub. The pathology of immersion deaths are dealt with in Chapter 16, but the following features will assist identifying suicides:

- Other means of self-destruction may also be present, such as drug overdose: in baths, associated electrocution is not uncommon, especially in the former West Germany.[23]

- Suicide notes may or may not be present, but those who kill themselves usually remove top clothes, hats and spectacles that may be left on the river bank; as usual, exceptions are commonplace.
- Other injuries on the body may be the result of agonal or post-mortem damage in the water.

Suicide by burning (self-incineration)

Heat injuries are dealt with in Chapter 11, but suicide from burns has recently increased in Western countries (where it was formerly almost unknown), though in Asia it has always been relatively common. The spread to the West followed political self-martyrdom modelled on that practised by some Vietnamese protesters. There are no particular medical features to distinguish suicide from accident or homicide, this being a circumstantial matter. It is almost invariable, however, for some container of inflammable accelerant to be within reach. The myth of 'spontaneous combustion' is discussed in Chapter 11.[24–27]

Suicide by 'asphyxia'

The pathology is described in Chapters 14 and 15, but the following facts are pertinent to suicide:

- The masochistic or sexual asphyxias must be carefully distinguished from homicide and suicide. Some asphyxial deaths with sexual aspects appear to be suicidal in nature – or at least, the inevitability of a fatal outcome must have been apparent to the victim.[28,29]
- Hanging, though not usually truly asphyxial, is a common mode of suicide, especially (though not exclusively) in males. It is also common as a sequel to homicide, especially in domestic murders, where the perpetrator often commits suicide by this means.[30–32]
- Plastic bag suicide (sometimes in combination with inhalation of a gas such as propane, ether, helium or natural gas) is increasing in incidence, the means being universally available.[33–43]
- Suicidal ligature strangulation is not uncommon and sometimes causes difficulty in differentiation from murder. The winding of several turns of ligature and the tying of multiple knots is still consistent with suicide, even though it is hard to understand how, in some cases, death appears to have been caused by reflex cardiac arrest rather than the more florid 'asphyxial' mode of death.

Sometimes a stick or other object is inserted under a ligature and twisted to tighten the cord against the neck. This is called a 'Spanish windlass', the stick becoming jammed against the body to prevent the tightened ligature from becoming loose once the twisting is completed.[44] Though usually suicidal, this device is sometimes used for murder.[44–47]

Jumping from a height

'Precipitation' – jumping from a height – is another mode of suicide where the circumstances rather than the autopsy findings determine the motivation. It may sometimes be possible to deduce, by measuring the distance from the jumping point to where the body strikes the ground, the fact that the victim must have actively projected himself outwards rather than fallen close to the wall or cliff face. Some experiments on this aspect have been carried out.[48] The injuries may be variable, depending on the attitude of the body when striking the ground, contact with obstacles during the fall and the height of the drop.[49–52]

Head injuries are common and are described in Chapter 5. If the fall is onto the feet, damage may occur at any point from the ankles to the skull. The legs may fracture, the hip joints may impact, the pelvis may split, the spine may be fractured (especially vertebral body compression, hyperflexion or hyperextension lesions) or the base of the skull may be imploded as a ring fracture.

It is extremely difficult, to the point of impossibility, to deduce the height of the fall from the nature and severity of the injuries, as was evident from the medical testimony in the Helen Smith inquest in Leeds, where an open verdict was returned by the jury in 1982. Ms Smith had died on the 20th of May, 1979 after she and a Dutch man apparently fell approximately 21 m (70 ft) from a balcony in the city of Jeddah, Saudi Arabia. Her father refused to allow a funeral suspecting a cover up of the real truth surrounding the circumstances of her death and the body was stored in a mortuary in Britain until she was eventually cremated and buried 30 years later in 1999.[53]

Some persons will be killed from a fall from a standing height, whilst other may make remarkable escapes without injury from a very high fall. The rare survivals in falls from a great height – usually when some cushioning effect, such as snow, exists – may still defy mechanical explanation.

Self-inflicted injuries other than suicide

In most cases self-harm is associated with some abnormality of mind that leads the victim to injure or mutilate his body (Figs 7.20, 7.21). Some mentally disordered persons may inflict hundreds of small wounds upon themselves, which may be additional to the actual cause of death, if death has taken place. Forensic physicians, such as police surgeons, may be called upon to examine living victims of this type.

The arms may be covered with scores of parallel superficial incisions from a knife, razor or broken glass. These may cross each other in groups and again are more frequent on the non-dominant side, usually the left. Small stabs may be made on the chest or temples. In a case seen by the author (BK), there were more than 200 knife-point stabs on each temple and the centre of the forehead. Another well-recognized syndrome is self-mutilation of the genitals, almost invariably by males. Paranoid schizophrenics, often with a strong religious flavour to their delusions, are known to attack themselves in this manner. The penis, scrotum and testes may be removed, and death from intractable haemorrhage can follow. In one of the cases illustrated, there was also perforation of the eyeballs and 40 stab wounds on the top of the head, as well as a complete circumferential cutting of the throat, all with the same blunt scissors that performed the castration. The forensic implications arose from the initial suspicions of the police that a sadistic homicide had taken place (Figs 7.11, 7.12).[54–61]

Self-inflicted injuries, usually non-fatal unless some complication has arisen, may be motivated by some form of gain. The most common is fabrication of injuries to simulate an assault, either to divert attention from the person's own theft or to arouse sympathy.[62] Fabricated accidental injuries are usually a form of malingering, as in the armed forces, or in fraudulent attempts to obtain compensation.[63–66] In other cases, the 'victim' may claim that a specific person assaulted them, from motives of hate or spite.[67] Others may injure themselves and then waste police time by insisting on a futile search for a non-existent assailant, the motive often being impossible to discover, even by a psychiatrist.[68]



Figure 7.11 Complete self-amputation of the scrotum and penis with scissors.



Figure 7.12 Self-mutilation thought by the police to be a bizarre homicide. The genitals have been amputated, the throat cut through 360°, the eyeballs punctured and the scalp stabbed many times, all with scissors. The dead man had paranoid delusions of a religious nature.

Though these matters are usually seen by the clinical forensic physician, the pathologist may be asked for an opinion where no other medico-legal doctor is available, or if death supervenes. The so-called 'Münchausen syndrome' consists of repeated simulations of illness or the infliction of repeated minor injuries, with the object of gaining admission to hospital, or obtaining medical care and attention.[58,69]

The following features assist in the recognition of self-inflicted incised injuries:

- The cuts are usually superficial and rarely any danger to life, unless they become infected. Occasionally, they may penetrate the full thickness of the skin, but not in sensitive areas like the face.
- The incisions are regular, with an equal depth at origin and termination, unlike more serious wounds that tend to be deeper at the start and tail off to the surface.

- The cuts are usually multiple and often parallel. They avoid vital and sensitive areas like the eyes, lips, nose and ears, usually being drawn on the cheeks and jaws, temples and forehead, sides of the neck, chest, shoulders, arms and backs of hands and thighs. This is inconsistent with an attack by another person, as the victim is unlikely to stand still to allow these multiple delicate and uniform injuries to be carefully executed.
- In right-handed persons, most of the injuries are on the left side, especially the sides of the face and left hand.
- When the incisions are made on areas covered by clothing, the relevant garments may show either no cuts or cuts that do not match the injuries in position or direction.

In summary, the whole range of injuries and surrounding circumstances may suggest to the experienced pathologist that the lesions do not constitute a genuine assault. This diagnosis may be virtually immediate on first looking at the 'victim' and may be almost intuitive after some experience – though this is of little use when giving legal testimony, when every opinion has to be backed up by hard fact and reasoned opinion (Figs 7.13–7.19).

The so-called 'Münchausen syndrome' and the 'Münchausen syndrome by proxy' lie within the realm of the forensic psychiatrist, but a pathologist or clinical forensic physician may be called upon to confirm – or even first detect – that the injuries are self-inflicted.



Figure 7.14 Self-inflicted injury in an attempt to produce an excuse during shop-breaking. Surprised by the police, he cut himself with broken glass to claim that he had been assaulted by the robbers while trying to defend the premises. There were similar shallow, straight cuts on the other side of the face and on the backs of the hands.



Figure 7.13 Self-inflicted scissors injury around the full circumference of the neck.


Avoids eyes, nose, mouth and ears
Parallel uniformly shallow cuts (more on left side)
Mostly on back or palm of least dominant hand
Left
Right
Forehead, neck, jaw and cheek (more on left side)

Figure 7.15 Characteristics of non-fatal self-inflicted injuries.



Figure 7.16 Cuts on the backs of the hands in the male shown in Fig. 7.14. He was right handed and most of the shallow incisions are on the left hand.



Figure 7.17 Self-inflicted injury in the living. The 'victim' alleged that he had been attacked and robbed. The superficial, uniform, mostly parallel scratches avoid the eyes, nose and mouth.

The Münchausen syndrome refers to adults who injure themselves or feign signs of illness, in order to gain medical attention and often admission to hospital.[58,66,69–71] They can be a plague to casualty departments until recognized. More sinister is the Münchausen syndrome by proxy, where a parent will repetitively injure their child – occasionally fatally – to gain the same attention from doctors and medical facilities. The relationship with child abuse, of which it is a variety, must be recognized.



Figure 7.18 Extensive self-inflicted cuts on the chest, one exposing subcutaneous fat. The youth persistently claimed to the police that he had been attacked, but the cuts in his shirt were horizontal. He later confessed, explaining that he wanted to get his father's sympathy over some domestic crisis.



Figure 7.19 Multiple, criss-cross arranged, linear, equally shallow, and symmetrical skin lesions characteristic of self-inflicted injuries with a sharp instrument.



Figure 7.20 Typical round pigmented scars from cigarette burns.



Figure 7.21 Several linear scars and fresh drug abuse-related injection marks on the left forearm. The victim is the same as in Fig. 7.20, demonstrating the practice of multiple self-harm.

References

1 Pollak S. Clinical forensic medicine and its main fields of activity from the foundation of the German Society of Legal Medicine until today. *Forensic Sci Int* 2004;144(2–3):269–83.

2 Pollak S, Saukko PJ. *Clinical Forensic Medicine; Self-inflicted Injury*. In: Siegel JA (ed). *Encyclopedia of Forensic Sciences*. Oxford: Elsevier, 2000, pp. 391–7.

3 Pollak S, Saukko P. Self-inflicted injury. In: Siegel JA, Saukko PJ (eds). *Encyclopedia of Forensic Sciences*. Waltham: Academic Press, 2013, pp. 110–15.

4 Harris CN, Rai K. The self-inflicted wrist slash. *J Trauma* 1976;16(9):743–5.

5 Karlsson T, Ormstad K, Rajs J. Patterns in sharp force fatalities – a comprehensive forensic medical study: Part 2. Suicidal sharp force injury in the Stockholm area 1972–1984. *J Forensic Sci* 1988;33(2):448–61.

6 Karlsson T. Homicidal and suicidal sharp force fatalities in Stockholm, Sweden. Orientation of entrance wounds in stabs gives information in the classification. *Forensic Sci Int* 1998;93(1):21–32.

7 Karger B, Niemeyer J, Brinkmann B. Suicides by sharp force: typical and atypical features. *Int J Legal Med* 2000;113(5): 259–62.

8 Pollak S, Saukko PJ. Wounds: Sharp Injury. In: Jamieson A, Moenssens AA (eds). *Wiley Encyclopedia of Forensic Science*. John Wiley, 2009.

9 Pollak S, Saukko P. Clinical forensic medicine – overview. In: *Encyclopedia of Forensic Sciences*. Siegel JA, Saukko PJ (eds). Waltham: Academic Press, 2013, pp. 83–8.

10 Iscan YM. Progress in forensic anthropology: the 20th century. *Forensic Sci Int* 1998;98(1–2):1–8.

11 Corballis MC. From mouth to hand: gesture, speech, and the evolution of right-handedness. *Behav Brain Sci* 2003;26(2): 199–208; Discussion 208–60.

12 Sun T, Walsh CA. Molecular approaches to brain asymmetry and handedness. *Nat Rev Neurosci* 2006;7(8):655–62.

13 Papadatou-Pastou M, *et al*. Sex differences in left-handedness: a meta-analysis of 144 studies. *Psychol Bull* 2008;134(5):677–99.

14 Vuoksimaa E, Kaprio J. Sex differences in left-handedness are also evident in Scandinavia and in twins: comment on Papadatou-Pastou, Martin, Munafo, and Jones (2008). *Psychol Bull* 2010;136(3):344–7.

15 Gee DJ, Watson A. *Lecture Notes in Forensic Medicine*, 5th edn. Oxford: Blackwell Scientific Publications, 1989.

16 Karger B, *et al*. Autopsy features relevant for discrimination between suicidal and homicidal gunshot injuries. *Int J Legal Med* 2002;116(5):273–8.

17 Karger B, DuChesne A. Who fired the gun? A casuistic contribution to the differentiation between self-inflicted and non-self-inflicted gunshot wounds. *Int J Legal Med* 1997; 110(1):33–5.

18 Blumenthal R. Suicidal gunshot wounds to the head: a retrospective review of 406 cases. *Am J Forensic Med Pathol* 2007;28(4):288–91.

19 Avis SP. Suicidal gunshot wounds. *Forensic Sci Int* 1994;67(1): 41–7.

20 Eisele JW, Reay DT, Cook A. Sites of suicidal gunshot wounds. *J Forensic Sci* 1981;26(3):480–5.

21 Garavaglia JC, Talkington B. Weapon location following suicidal gunshot wounds. *Am J Forensic Med Pathol* 1999;20(1):1–5.

22 Hejna P, Safr M. Shooting through clothing in firearm suicides. *J Forensic Sci* 2010;55(3):652–4.

23 Bonte W, Sprung R, Huckenbeck W. [Problems in the evaluation of electrocution fatalities in the bathtub]. *Z Rechtsmed* 1986;97(1):7–19.

24 Castellani G, *et al*. Suicide attempted by burning: a 10-year study of self-immolation deaths. *Burns* 1995;21(8):607–9.

25 Crosby K, Rhee JO, Holland J. Suicide by fire: a contemporary method of political protest. *Int J Soc Psychiatry* 1977;23(1):60–9.

26 Mohanty MK, *et al*. Self-inflicted burns fatalities in Manipal, India. *Med Sci Law* 2005;45(1):27–30.

27 Thombs BD, Bresnick MG, Magyar-Russell G. Who attempts suicide by burning? An analysis of age patterns of mortality by self-inflicted burning in the United States. *Gen Hosp Psychiatry* 2007;29(3):244–50.

28 Knight B. Fatal masochism – accident or suicide? *Med Sci Law* 1979;19(2):118–20.

29 Solarino B, *et al*. An unusual death of a masochist: Accident or suicide? *Forensic Sci Int* 2011;204 (1–3):e16–19.

30 Lecomte D, Fornes P. Homicide followed by suicide: Paris and its suburbs, 1991–1996. *J Forensic Sci* 1998;43(4):760–4.

31 Bourget D, Gagne P, Moamai J. Spousal homicide and suicide in Quebec. *J Am Acad Psychiatry Law* 2000;28(2):179–82.

32 Gregory MJ, Milroy CM. Homicide and suicide in Yorkshire and the Humber: 1975–1992 and 1993–2007. *Am J Forensic Med Pathol* 2010;31(1):58–63.

33 Winek CL, Collom WD, Wecht CH. Suicide with plastic bag and ethyl ether. *Lancet* 1970;1(7642):365.

34 Perez Martinez AL, Chui P, Cameron JM. Plastic bag suffocation. *Med Sci Law* 1993;33(1):71–5.

35 Athanaselis S, *et al*. Asphyxial death by ether inhalation and plastic-bag suffocation instructed by the press and the Internet. *J Med Internet Res* 2002;4(3):E18.

36 Barnung SK, Feddersen C. [Suicide by inhaling helium inside a plastic bag]. *Ugeskr Laeger* 2004;166(40):3506–7.

37 Byard RW, Simpson E, Gilbert JD. Temporal trends over the past two decades in asphyxial deaths in South Australia involving plastic bags or wrapping. *J Clin Forensic Med* 2006;13(1):9–14.

38 Stemberga V, *et al*. Propane-associated autoerotic asphyxiation: accident or suicide? *Coll Anthropol* 2007;31(2):625–7.

39 Maryam A, Elham B. Deaths involving natural gas inhalation. *Toxicol Ind Health* 2010;26(6):345–7.

40 Perdekamp MG, *et al*. [Plastic bag as the method in suicide and homicide]. *Arch Kriminol* 2001;207 (1–2):33–41.

41 Hunt AC, Camps FE. Plastic-bag suicide. *Br Med J* 1962; 1(5275):378.

42 Skold G. Fatal suffocation in plastic bag. *Dtsch Z Gesamte Gerichtl Med* 1967;59(1):42–6.

43 Polson CJ, Gee DJ. Plastic bag suffocation. *Z Rechtsmed* 1972;70(3):184–90.

44 Atilgan M. A case of suicidal ligature strangulation by using a tourniquet method. *Am J Forensic Med Pathol* 2010;31(1):85–6.

45 Kogan Y, Bloom T. Suicidal ligature strangulation with an elastic band. *Am J Forensic Med Pathol* 1990;11(4):329–30.

46 McMaster AR, *et al*. Suicidal ligature strangulation: case report and review of the literature. *J Forensic Sci* 2001;46(2):386–8.

47 Doberentz E, Hagemeier L, Madea B. [Cable tie used for suicidal ligature strangulation – a case report]. *Arch Kriminol* 2009;224(1–2):17–25.

48 Goonetilleke UK. Injuries caused by falls from heights. *Med Sci Law* 1980;20(4):262–75.

49 Cetin G, *et al*. Suicides by jumping from Bosphorus Bridge in Istanbul. *Forensic Sci Int* 2001;116 (2–3):157–62.

50 Copeland AR. Suicide by jumping from buildings. *Am J Forensic Med Pathol* 1989;10(4):295–8.

51 Hanzlick R, Masterson K, Walker B. Suicide by jumping from high-rise hotels. Fulton County, Georgia, 1967–1986. *Am J Forensic Med Pathol* 1990;11(4):294–7.

52 Li L, Smialek JE. The investigation of fatal falls and jumps from heights in Maryland (1987–1992). *Am J Forensic Med Pathol* 1994;15(4):295–9.

53 Bingham J. Father agrees to bury daughter's body after 30 years in mortuary. In: *The Daily Telegraph*. Telegraph Media Group, 2009.

54 Oumaya M, *et al*. [Borderline personality disorder, self-mutilation and suicide: literature review]. *Encephale* 2008;34(5):452–8.

55 Zinka B, Rauch E. [Self-mutilation from a forensic medicine viewpoint]. *Hautarzt* 2007;58(4): 328–34.

56 Krysinska K, Heller TS, De Leo D. Suicide and deliberate self-harm in personality disorders. *Curr Opin Psychiatry* 2006;19(1):95–101.

57 Paris J. Understanding self-mutilation in borderline personality disorder. *Harv Rev Psychiatry* 2005;13(3):179–85.

58 Kocalevent RD, *et al*. *Autodestructive syndromes*. *Psychother Psychosom* 2005;74(4):202–11.

59 Patton N. Self-inflicted eye injuries: a review. *Eye (Lond)* 2004;18(9):867–72.

60 Kennedy BL, Feldmann TB. Self-inflicted eye injuries: case presentations and a literature review. *Hosp Community Psychiatry* 1994;45(5):470–4.

61 Faller-Marquardt M, Pollak S, Schmidt U. Cigarette burns in forensic medicine. *Forensic Sci Int* 2008; 176(2–3):200–8.

62 Faller-Marquardt M, Ropohl D, Pollak S. Excoriations and contusions of the skin as artefacts in fictitious sexual offences. *J Clin Forensic Med* 1995;2(3):129–35.

63 Bonte W. Self-mutilation and private accident insurance. *J Forensic Sci* 1983;28(1):70–82.

64 Bonte W, Rudell R. [Accident or planned self mutilation? Probability of accidental injuries during chopping]. *Arch Kriminol* 1978;161(5–6):143–52.

65 Dotzauer G, Iffland R. Self-mutilations in private-accident-insurance cases. *Z Rechtsmed* 1976;77(4): 237–88.

66 Eckert WG. The pathology of self-mutilation and destructive acts: a forensic study and review. *J Forensic Sci* 1977;22(1):242–50.

67 Faller-Marquardt M, Pollak S. Self-inflicted injuries with negative political overtones. *Forensic Sci Int* 2006;159(2–3):226–9.

68 Karger B, *et al*. Unusual self-inflicted injuries simulating a criminal offence. *Int J Legal Med* 1997; 110(5):267–72.

69 Asher R. Munchausen's syndrome. Lancet 1951; 1(6650): 339–41.

70 Carney MW, Brozovic M. Self-inflicted bleeding and bruising. Lancet 1978;1(8070):924–5.

71 Gibbon KL. Munchausen's syndrome presenting as an acute sexual assault. *Med Sci Law* 1998;38(3): 202–5.

This page intentionally left blank

CHAPTER 8

Gunshot and Explosion Deaths

- Introduction
- The mechanics of missile injury
- Types of weapon
- Wounds
- Wounds inflicted by a smooth-bore shotgun
- Wounds from rifled weapons
- Exit wounds
- Firearm damage to internal organs
- Estimating the range of discharge
- Airgun injuries
- Humane (veterinary) killers, industrial 'stud-guns' and blank-cartridge guns
- Rubber and plastic bullets
- Deaths from explosion
- References

Introduction

Though the majority of missile wounds are caused by firearms, other devices such as crossbows, captive-bolt guns, air weapons and even catapults can launch lethal projectiles. In the bombing deaths now so commonly associated with terrorism, missile fragments cause more deaths than the blast effects, so, overall, an understanding of projectile trauma is essential. Ballistics (Gr. βάλλειν, 'throw') is the science of mechanics that deals with the flight, behaviour and effects of projectiles. Internal ballistics deals with the processes in a firearm. Exterior ballistics deals with the behaviour of the projectile after leaving the barrel. Wound ballistics comprises the changes caused when a missile penetrates a human or animal body.

The mechanics of missile injury

With the exception of deceleration injuries, all mechanical trauma, whether punching, stabbing or kicking, is caused by the transfer of energy from an external moving object to the tissues and nowhere is this more obvious than in shooting. For damage to occur, some or all of the kinetic energy of the missile has to be absorbed by the target tissues, where it is dissipated as heat, noise and mechanical disruption. When a missile passes completely through soft tissues, it may retain much of its original kinetic energy and fail to transfer any appreciable amount to the tissues, which may remain relatively intact apart from the immediate bullet track. If the latter is in a limb muscle, there may be no serious effects if major blood vessels are not involved, though the same track in brain, lung or heart may prove fatal (Fig. 8.48).

To ensure transfer of energy to the tissues, some missiles are especially designed or modified to slow up or stop within the body. Softheaded bullets will flatten on impact and some are designed to fragment. The 'dumdum' bullet, which has a scored nose, and the missiles with an air-cavity within the tip are intended to splay open on impact to increase the 'braking' or deceleration effect, and transfer more energy for tissue displacement and disruption. Explosive-tipped bullets, such as those used in the assassination attempt on the USA President Reagan in 1981, are not designed to cause damage by the tiny detonation, but drastically to deform the missile to cause maximum deceleration.[1,2] Weapons designed to be fired in confined spaces, such as those for combating hijack attempts in an aircraft, may be of relatively low velocity and have a deceleration feature incorporated to ensure the absence of an exit wound, and thus limited travel of the missile to avoid puncture of the pressurized passenger cabin.

The trajectory of the missile also determines how much and how fast its energy is given up to the target. Shotgun pellets are spherical, so the orientation of impact is not relevant, but all conical bullets may acquire an erratic course in the tissues. They may tumble end-overend, especially when nearing the limit of range; they may 'wag' or 'yaw' from side to side of their axial trajectory; the base may rotate around the axis, with the tip remaining on the straight path; and they may 'precess' or 'nutate' with complex spiral or circular movements about the axis.

Whatever the deviation, it offers more contact between the projectile and the tissues, allowing more transfer of energy and thus greater tissue damage. The amount of kinetic energy possessed by a projectile accords to the familiar formula of half the product of the missile mass and the square of its velocity. Relatively slow projectiles are those travelling at up to the speed of sound in air (340 m/s or 1115 ft/s), which of course includes all non-explosively propelled missiles like crossbow bolts and air-rifle pellets, as well as most revolver bullets. Modern military science takes advantage of the squaring of the velocity to develop weapons that have a missile of small mass but exceedingly high velocity to provide the maximum kinetic energy for tissue damage.

The mode of injury depends on several factors: the shape, velocity and possible deformation or fragmentation of the missile, which all affect the tissue–missile interaction.

When the missile strikes the body it first produces a sonic compression wave (shock wave) of a very short duration (in the range of microseconds) that propagates in tissue at about the speed of sound in water (1500 m/s or 4921 ft/s). Though this wave raises the tissue pressure to extreme values, up to thousands of kilopascals, there is controversy as to its potential to cause tissue damage.[3–10]

When the missile penetrates the skin it mechanically thrusts aside the tissues along a track wider than the missile. The tissues are lacerated or crushed, secondary damage occurs from rupture of blood vessels and other structures resulting in a permanent wound cavity.

High-velocity projectiles produce yet another phenomenon, that of cavitation. The missile accelerates the tissues adjacent to the track, so that they continue to move centrifugally outwards even after the missile has travelled onwards. This forms a cavity around the track that is far wider than the diameter of the projectile. It reaches a maximum size within milliseconds and then pulsates with decreasing amplitude so that a fusiform cavity rapidly follows in the wake of the bullet. When the bullet stops or leaves the organ, the cavity rapidly subsides, but the track of damage persists in a tubular zone much wider than the actual missile. In high-velocity bullets from military weapons – for example, 980 m/s (3215 ft/s) this cavitation effect is the most damaging mechanism; in addition to the physical damage, the near-vacuum sucks infected dirt and clothing fibres into the depths of the wound.[11,12] Solid organs such as brain and liver are affected more than spongy matrices like lung. Those tissues that contain most water are most severely damaged by penetrating missiles and high-velocity missile damage is proportional to the specific gravity of the tissue injured.

In most of the shooting cases seen by forensic pathologists, death will have occurred rapidly but, where it is delayed, secondary damage from infarction, local necrosis of muscle and organs and infection must always be borne in mind.

Types of weapon

The nature of firearm wounds varies considerably with the type of weapon employed. A general knowledge of the main features of the various types of gun in common use is essential, though there is no need for the pathologist to master the unnecessary mass of detail on firearm construction offered by some forensic medicine textbooks. Indeed, much of this is solely the province of the firearms examiner, not the doctor. The inordinate amount of detail sometimes provided is perhaps symptomatic of the fascination which firearms hold for many males – but rarely females (Figs 8.1–8.4).

In the context of wounding, guns are of two main types.

The smooth-bore weapon or 'shotgun'

A shotgun consists of one or more metal barrels of relatively wide diameter, which are smooth on the inner surface. They fire a variable number of spherical lead shot (pellets), which emerge from the end (muzzle), from where they gradually diverge in the form of a long, narrow cone. Exceptionally, a shotgun may fire a few large projectiles or even a single slug, but these are rarely met with in forensic practice, the usual load of pellets totalling scores or hundreds. Special types of projectile are described later. A shotgun often has two barrels, either side by side or 'up-and-under'. One barrel may be parallel sided (the 'cylinder') and the other slightly tapered towards the muzzle (the 'choke'). The latter will produce a narrower cone of shot and this affects estimates of range derived from the size of the wound. There are several gradations of choke, such as 'improved cylinder', 'modified choke', 'half-choke' and 'full-choke'.

Some modern weapons have the facility for removing one particular type of barrel and replacing it



Figure 8.1 Types of smooth-bore weapon.



Figure 8.2 Relative calibre of common weapons.



Figure 8.3 Various types of ammunition. From the right, there are two twelve-bore shotgun cartridges, .22 rifle, .38 automatic pistol and .45 revolver bullets and two military rifle shells. On the left is a cannon shell, which is unlikely to be encountered in civilian forensic pathology.



Figure 8.4 Types of weapon and ammunition.

with another degree of choke. Modern accessories can convert a cylinder barrel to a choke barrel – for example, variable choke such as Poly-Choke, Kutts Compensator and Weaver-Choke are available, especially in the USA.

Another typically American modification is the ability to fire a single projectile through the smooth bore. A number of devices intended for hunting are available, but they may be involved in a human fatality. One of the older types is the solid round 'pumpkin ball' or the Brenneke rifled slug, but more recent devices include the Foster rifled slug and the French Blondeau, which is a dumb-bell-shaped projectile.

Shotguns come in two main sizes, which determine the nature of the wound. The first is the 'twelve-bore', usually called 'twelve-gauge' in North America, which has a diameter of about 19 mm or 0.748 in. The other is the smaller 'four-ten', usually single-barrelled with a diameter of 10.6 mm or 0.417 in.

Shotgun ammunition

The ammunition for the shotgun is a cartridge made of a cardboard or plastic cylinder fitted into a metal base. This carries a percussion detonator that is struck by the spring-loaded firing pin when the trigger is pulled. The cartridge contains a charge of propellant, above which are 'wads' or pistons of felt, and cardboard or plastic



Figure 8.5 Shotgun cartridge, which has been tampered with placing into the cartridge various sized metal balls in addition to the pellets.

discs, or both. Above these is the charge of shot, which varies greatly in number and size, finally covered by a card or plastic disc.

This description is of the old, classical cartridge but modern ammunition has a variety of devices incorporated into the cartridge to improve efficiency and accuracy. These include the Power Piston, a proprietary name for one of a class of cartridges that holds the shot inside a polythene cup and which itself may contribute to the wound at short range. Other modern cartridges may have plastic granules as a filler between the shot; this brightly coloured material may be found inside the wounds.

Tampering with the contents of cartridges may markedly alter the spread and other characteristics of the shot and hence the resulting wound. The shot may be fused into a mass by pouring paraffin wax or even molten pitch into the cartridge (Fig. 8.5). The cardboard or plastic cylinder may be partly cut through at the level of the wads, so that, on firing, the upper part of the casing is blown out to restrain the divergence of the pellets.

The propellant has also changed in recent years, so that the old black gunpowder has been largely replaced by cleaner explosives that do not produce the same volume of soot and unburnt propellant, which may be deposited in and around the close-range wound.

‘Country’ guns

In developing countries, in some rural and poor areas of other countries, in subversion and terrorism and sometimes in juvenile hands, weapons and ammunition may be ‘home-made’. These are common in India, where the name ‘country gun’ is well understood; they are also made in Sri Lanka and other Asian areas, but may be encountered anywhere.[13–19]

One of the authors (BK) had experience of such weapons in the terrorist campaign in Malaya (Malaysia) in the 1950s, where crude weapons were made in the jungle from pieces of water-pipe attached to roughly carved wooden stocks, with a primitive firing mechanism. The guns were muzzle-loaded with black powder and the projectiles were often wood-screws, nuts and bolts and irregular fragments of metal or even stones.

In civilian practice in Britain, two similar weapons have been seen, both made by juveniles out of electrical conduit pipe, using potassium chlorate–sugar propellant. In one, the user was killed when the device exploded; the other one successfully propelled a small screwdriver across several fields to (slightly) injure a cow.

Terrorists in Northern Ireland have also manufactured some of their own weapons, but these were relatively sophisticated, being made in clandestine but well-equipped workshops.

The problem for the pathologist with such guns is that few of the criteria to be described apply to the injuries, especially where random, irregular missiles such as wood-screws are employed. Local knowledge and experience are essential for the interpretation of these wounds.

The rifled weapon

Handguns, rifles, air rifles and military weapons differ from shotguns in that they fire one projectile at a time through a thicker barrel that has spiral grooves machined on its inner surface. The elevations between the grooves are the ‘lands’, which grip the bullet as it passes down the barrel and give it a rotatory movement. This has a gyroscopic effect that increases the stability of the bullet’s trajectory and hence the accuracy.

Handguns, which caused over 50 per cent of all homicides in the USA in 2005, comprise the revolver and the automatic pistol.[20] The revolver has a rotating cylinder carrying a variable number of shells, which are brought into the firing position one by one each time the trigger is pulled. The revolver has a low muzzle velocity of the order of 250 m/s (820 ft/s). The ‘automatic’, more accurately called a ‘self-loading’ pistol, has its shells in a spring-loaded magazine, each spent round being ejected and a new one positioned by means of the gas pressure developed at each discharge. The muzzle velocity may be 300–350 m/s (around 1000 ft/s) (Figs 8.57, 8.66).

Rifles are long-barrelled guns that may be single-shot, bolt-loaded or self-loading and used for hunting, target-shooting or for military purposes. Military weapons come in a vast range of types, most of them now either 'self-loading', which means that the trigger has to be pulled for each shot – or truly 'automatic', when the weapon will continue to fire while the trigger is depressed until the magazine is empty. The muzzle velocity varies greatly, from 450–1000 m/s (1500–3300 ft/s) (Fig. 8.58).

Ammunition for rifled weapons

The variety of types of rifled ammunition is even greater than the range of weapons designed to fire them, but all conform to a general pattern. There is a metal cylinder, closed at one end, which is the 'shell' or cartridge, carrying a percussion detonator in the base, either centrally or peripherally. The shell is loaded with explosive propellant such as nitrocellulose and the bullet is firmly clamped into the open end. The bullet may be composed of a variety of metals, often compound. A lead core may be covered in a nickel or steel jacket, but there are many other variations. The detonator may contain elements such as barium, lead or antimony.

Both shotgun and rifled weapon ammunition have a common purpose when detonated – to produce large volumes of hot gas under pressure that expel the bullet or shot from the barrel. One kilogram of black powder produces about 280 litres and nitrocellulose produces some 900–970 litres of gas, which consists of carbon dioxide, monoxide, nitrogen, hydrogen sulphide, hydrogen, methane and many other substances, all at high temperatures.[8]

Wounds

Though the construction and performance of weapons is of vital interest to the forensic firearms examiner, the relevance to the pathologist is concentrated in those aspects which affect the nature of the wound:

- whether the weapon is smooth-bore or rifled
- if rifled, the muzzle velocity of the weapon
- the nature of the projectile(s)
- the nature of the propellant
- the degree of choke, if any
- the range of discharge
- the angle of discharge.

Wounds inflicted by a smooth-bore shotgun

The following constituents of the cartridge emerge on the discharge of a shotgun and all may contribute to the wound:

- lead pellets
- soot in the form of smoke and debris
- unburnt and burning propellant particles
- flame and hot gases under pressure
- carbon monoxide
- wads – either felt, cardboard or plastic
- detonator constituents
- fragments of the cartridge case.

When a shotgun is fired, a compact mass of shot emerges from the muzzle and then begins to disperse, the divergence increasing progressively as the distance lengthens. A tongue of flame and hot gas follows the shot. High pressure and temperature exists just outside the muzzle, but this rapidly expands and cools. This gas is composed of oxides of nitrogen, carbon dioxide, hot air and other compounds, but the one of interest to the pathologist is carbon monoxide. Soot from the combustion of propellant is expelled, along with some flakes or grains of propellant that may be still burning. The wads are also expelled, their nature depending upon the type of cartridge. Some modern ammunition may contain other devices that may contribute to the wound.

Chemical traces of the elements in the detonator or percussion cap cannot be seen, but may be vital laboratory evidence, where lead, barium, antimony and other metals can be recovered on analysis or by means of the scanning electron microscope. Fragments of the cartridge case may also be ejected, especially if it has been tampered with, as described earlier.

The most important deduction that a pathologist is asked to make is the estimation of the range of discharge of the gun, as this may substantially influence the distinction between accident, suicide and homicide. The appearance of the wound is greatly modified by variation in range and it is convenient to describe them in terms of increasing range of discharge (Fig. 8.6).

Shotgun contact wound

Shape

Where the muzzle is placed tightly against the surface of the abdomen, thorax, limb or neck, the consequent wound will be single and circular, of a size



Figure 8.6 Variation in appearance of a shotgun wound at increasing range of discharge: 1(a) Split wound from contact over bone. 1(b) Usual round contact wound. 2 Close but not contact range up to about 30 cm (variable). 3 'Rat-hole' wound from 30 cm to about 1 m (variable). 4 Satellite pellet holes appearing over 1 m. 5 Spread of shot increases, central hole diminishes. 6 Uniform spread with no central hole over about 10 m. All these ranges vary greatly with barrel choke, weapon and ammunition.

approximately equal to the bore of the weapon, though a .410 wound may be smaller because of the relatively greater effect of elastic contraction of the skin. The edges of the wound may be crenated by individual shot, but usually this feature is not noticeable.

Soiling and burning

In a tight contact wound, the skin forms a seal around the muzzle, preventing much escape of hot gas and soot, so that external soiling and burning are minimal or absent (Fig. 8.10). The recoil, which takes the muzzle away from the skin, may, however, loosen the seal and, if the muzzle is not pressed firmly, flame, gas and soot may escape sideways and affect the skin in the immediate vicinity. Where clothing is interposed between the muzzle and skin, soot is much more likely to escape sideways and may be found in each layer of fabric, as well as on the underlying skin. The cloth may be singed at the edge of the hole and there may be a ring of burning around the skin wound, especially in shots with black powder ammunition. In the depth of the entrance wound, the tissue is blackened due to soot deposition (Figs 8.7–8.9).

Muzzle impression

There may be a muzzle impression in a tight contact wound made by firm mechanical pressure or impact of the metal rim against the skin. Many textbooks quite wrongly attribute this to 'recoil', though of course recoil takes the muzzle away from the skin, not towards it. The true explanation of a muzzle mark is that the subcutaneous expansion shortly to be described, lifts the skin forcibly up against the muzzle. A muzzle



Figure 8.7 Soot-soiling of hand that had grasped a shotgun barrel.



Figure 8.8 Suicidal firearm wound with a twelve-bore shotgun. There is abundant smoke soiling particularly above the wound, suggesting a loose and oblique contact with the muzzle and skin.



Figure 8.9 Suicidal firearm wound from a twelve-bore shotgun. The wound shows a muzzle impression with soot soiling, the double-barrelled shotgun having been pressed against the skin at discharge.



Figure 8.10 Firm contact wound from a twelve-bore shotgun. The clothing has prevented any soot soiling, but there are minor peripheral abrasions from impact of a belt. As the abdomen was distensible, the gas expansion has not caused splitting of the skin at the wound edges.

mark is a most useful indication to the pathologist of a contact wound and Anton Werkgartner (1890–1970) was the first to realise and describe the significance of this patterned injury.[21–25] Actual bruising can occur around the muzzle imprint, though this is more likely to be the result of deep contusion from the effects of the blast. Rarely, a double-barrelled weapon may make a ring-like mark adjacent to the entry wound (Fig. 8.9).

Carbon monoxide

Carbon monoxide in the gases combines with haemoglobin and myoglobin to give a pink colouration to the interior of the wound track and adjacent tissues.[26,27] This, along with the other discharge residues, such as soot, powder particles and primer elements, diminish in concentration along the wound track, but can still be present in its depths – and even at exit wound, if there is one.[12] The presence of carboxyhaemoglobin and myoglobin has been advocated as a test for distinguishing the exit from the entrance wound, especially where decomposition has blurred the morphological appearances. This test must be used with caution.

Contact wounds over bone

When the wound is made over a site with underlying bone, the wound may have a different appearance. Especially in the scalp, but also over the back of the neck, sternum, shoulder, hip and other areas where the soft tissue lies thinly over bone, the large volume of discharge gases cannot dissipate, as they can into the abdomen, chest or mass of muscle. When the gas is forced through the skin, it is reflected back by the underlying hard layer and momentarily raises a dome of skin and subcutaneous tissue. This is rammed back against the muzzle to increase the pressure of contact further, sometimes producing a muzzle mark. When the gas volume is large, as with a twelve-bore gun, this dome may then split, causing a cruciate, stellate or ragged wound, with skin flaps. This is less likely with a .410 because the cartridge is smaller, but it can occur, as of course it can with rifled weapons.

The close discharge of a shotgun

When the muzzle is held near the skin, but not actually in contact with it, a number of helpful signs are produced. Once again the appearance is naturally modified by clothing, which must always be carefully preserved and subjected to forensic scientific examination. Where clothing is present, then it will trap most, but not necessarily all, of the soot and powder grains (Figs 8.11–8.15).[28–31]

Assuming that the body surface is uncovered, a close discharge – one between actual contact and about 15 cm (6 in.) – is likely to show the following features:

- Singeing of hairs around the wound, unless the skin is hairless. The fine downy hairs of the trunk and limbs may be burnt away, though this is unlikely with dense, long, head hair. Where the distance is greater, the keratin of the hair may melt with the flame and then solidify on cooling, causing a ‘clubbed’ appearance of the hairs because of rounded bulges at the tips.



Figure 8.11 Homicidal very close-range wound of the abdomen from a sixteen-bore shotgun fired through clothing. There is some abrasion of the wound edges, but no irregularity from the close-packed pellets, which have not begun to disperse. The clothing has protected the skin from smoke and powder soiling. The circular wound indicates discharge at right angles to the body surface.



Figure 8.12 Close-range twelve-bore shotgun wound of the head. This homicidal discharge was made through thick layers of fabric, which has filtered out any smoke or powder soiling. However, there is a wide zone of skin parching due to the muzzle gases. The wound is oval due to the downward angulation of the weapon.

- Especially in shots with black powder ammunition also burning of the skin, unless protected by head hair. There may be a wide flare or narrow parched reddish-brown rim or even blistering from the flame of incandescent gas blown from the muzzle.
- The tissues within and around the wound may be cherry-pink from reaction with carbon monoxide.



Figure 8.13 Suicidal twelve-bore shotgun wound. The entrance is in one of the 'sites of election', in the neck, and the circular smoke fouling indicated a close or even contact discharge.



Figure 8.14 Suicidal twelve-bore shotgun wound. The entrance is one of the 'sites of election', in the neck.

- There will be 'smoke soiling' or 'soot staining' of the skin, from carbon deposition. This spreads more widely than powder tattooing, but does not carry as far as the heavier propellant grains. This effect is much less or even absent with modern 'clean' propellants.



Figure 8.15 Suicidal contact entrance wound in the neck. One barrel of a double-barrelled shotgun was used, the unfired barrel causing a muzzle mark.

- This soot or smoke soiling is easily washed off the skin, and care must be taken at autopsy to obtain all photographs and trace samples before allowing the bloodstains to be washed from the body (Fig. 8.50). Tattooing will not wash off, though adherent unburnt propellant may be physically detached from the skin during any washing or swabbing process.
- Burning, partly burnt and unburnt propellant flakes and grains may pepper the surrounding of the wound. As stated above, these carry further than smoke staining, but usually spread over a smaller area. The incandescent particles cause small burns on the skin, but the unburnt flakes (such as nitrocellulose) may be seen as small glistening particles on the skin, sometimes coloured.
- The wound will be circular if the weapon is held at right angles to the skin and elliptical if slanted, often with undercut edges on one side. Depending partly on the size of the pellets, ‘nibbling’ or crenation of the edge may be seen, though this is usually imperceptible in close discharges. The edge of the wound will be blackened and there will be soot in the exposed tissues. There may be annular bruising around the wound and distant bruising a few centimetres away as a result of tissue damage. Other bruises or abrasions may be seen in the vicinity from objects such as buttons or buckles being hurled against the skin by the gas pressure.
- Any felt or cardboard wads or plastic cups from the cartridge will be within the depths of the wound.

Short- to mid-range shotgun discharge

From about 15 cm (6 in.) to 2 m (6 ft), considerable variation occurs in the appearance of the wound. The shorter range will provide a similar picture to that of close discharge, but the soot soiling diminishes and over 20–40 cm it may vanish. Powder tattooing near the wound periphery may persist for somewhat further than this.

At the upper end of this range the edges of the wound will become crenated and scalloped, especially with larger shot. This is sometimes called the ‘rat-hole’ or ‘rat-nibbling’ from its resemblance to rodent teeth marks. From 2 m upwards, the number of satellite pellet holes will progressively increase around the main wound.

It must be emphasized that these are useful generalizations, but that marked variations occur between different weapons, different barrels of the same weapon and different ammunition fired from the same gun. Only test firing can give a measure of the length of the flame, the distance and pattern of soot staining and powder tattooing, the beginning of pellet spreading and the distance over which the wads are projected. As a rough rule-of-thumb, which is often incorrect, hair singeing occurs over the first 30 cm (1 ft), soot staining can be seen for the first half-metre (20 in.) and a single large hole persists for at least 1 m (3 ft).

Mid- to distant-range shotgun wounds

Here, test firing is even more vital for an estimate of range, as the variation is great. The choke as opposed to cylinder barrel on the same gun will provide different appearances at the same range. Once beyond 2 m, there will be no burning or smoke staining, rarely will there be powder tattooing and the presence of the wads will be variable. Sometimes the latter fall away within 2 m, but they can sometimes be found in a wound up to 5 m distant. Often the wad takes a lower trajectory and may strike the body below the shotgun wound. It may penetrate the skin, causing a second lacerated wound or it may only bruise the skin or cause an excoriation. Some of the plastic cup devices now used open up in flight to form a square-edged star or capital ‘X’ shape. This can strike the skin at or near the shotgun wound and produce a characteristic bruise or abrasion of a similar shape. The spread of pellets, which usually begins at a range of 1–2 m, increases progressively, the central ‘rat-hole’ diminishing at the same rate (Figs 8.16–8.18).



Figure 8.16 Characteristic capital 'X'-shaped bruise caused by opening up of the plastic cup containing the shotgun pellets and surrounding the circular entrance wound from a homicidal short-range discharge.



Figure 8.17 An alcoholic shot his wife who was sitting in a rocking chair, and thereafter, reported himself to the police. The weapon was a twelve-bore shotgun. The entrance wound has a central hole with crenated wound edges with one satellite hole, which suggests that the range was about 1 m. Test firing must always be carried out, however, to obtain a more exact estimate. Whatever the actual range, it is clear that it could not be suicidal.



Figure 8.18 Homicidal close-range shotgun wound from a twelve-bore weapon.

There is an old (and extremely inaccurate) rule-of-thumb which states that the diameter of the spread in inches is roughly equal to the range in yards (metric: one-third of the spread in centimetres equals the range in metres). This of course applies to a circular wound or the narrow diameter of an oblique elliptical wound; it is of no use other than a quick first check to indicate if suicide can be excluded, but expert examination and test-firing are essential.

At distant ranges, beyond 6–10 m, the central hole may shrink to nothing. There will naturally be no wad injuries, no smoke or tattooing, and no way of determining range except to say that it must be within the maximum discharge distance of that particular weapon, which may be 30–50 m. At such ranges the shot usually will not be lethal and the pellets, if they penetrate the skin, will lie just in the subcutaneous tissues. Death may occur, however, from an unlucky shot in the eye.

The direction of a shotgun injury

It has already been stated that, where the discharge has been at right angles to the body surface, the shape of the wound will be symmetrical and circular. A shotgun blast traces out a shallow cone from the muzzle and simple geometry demands that where this cone intersects a plane (the skin), a circle will result only when the cone is at 90° to the plane. In all other positions an ellipse will be traced out, its elongation increasing as the angle between them decreases. This pattern applies not only to the pellet spread but to soot deposition and provides a ready indication of the direction. In addition to the surface features, the internal wound assists in orientating the discharge (Figs 8.19–8.24):

- The wound edges may be shelved, the tissues being undercut below the margin distal to the origin of the discharge. The appearances are similar to those seen in some knife wounds, where an oblique stab leaves tissue visible at one edge and undercut on the other. In firearm wounds this is better seen in injuries from a single rifled projectile than from the more diffuse mass of shotgun pellets, but is still sometimes apparent in the latter.
- The track of the wound in the deep tissues can be established and this line projected backwards to



Figure 8.19 Suicidal twelve-bore shotgun wound. Not all such wounds are circular – this one has torn a large defect in the chest wall because the shot struck at an acute angle. The smoke smudging is extensive, showing an asymmetrical soot pattern. The precordium is another site of election for suicidal shooting.



Figure 8.20 Pellet injuries from a medium distance twelve-bore shotgun discharge. The range was very approximately 7–9 m, which excludes suicide.



Figure 8.21 Tangential shotgun wound of face. The edge of the dispersal cone of pellets and gas has ploughed through the cheek, and removed the ear. The facial bones and base of the skull were fractured.



Figure 8.22 Shelving and undercutting of entry wound in oblique discharge.



Figure 8.23 A suicidal tangential shotgun wound of the forehead. Though most of the shot passed the head of the victim the discharge fractured the skull and created a 4 cm × 2.5 cm large oval bone defect (see Fig. 8.24).



Figure 8.24 Oval bone defect from a tangential shotgun discharge, the direction of which is indicated by the arrow. Note the shelved distal wound edge.

indicate the discharge direction relative to the body. Again, a missile from a rifled weapon usually gives a clearer picture than those from a shotgun, but a general estimate can be obtained from knowledge of the positions of the surface wound and the mass



Figure 8.25 Radiography should be carried out before autopsy in all deaths from firearms. The extent of dispersal of shot can be assessed – as in this film – and, in single bullet injuries, the position and possible fragmentation can be detected in order to assist in recovering the missile.

of pellets. Unless computed tomography (CT) scanning is an option, examination of a radiograph may be of more assistance than the laborious search from pellets at autopsy (Fig. 8.25). Whatever the type of missile(s), considerable deviation caused by deflection by bone and other tissues can occur, so that the final resting place of the projectile may be far off the initial track. Thus the actual path through the tissues before ricochet must be established, if possible.

Other features of shotgun wounds

- Exit wounds are uncommon in the trunk as the energy possessed by each pellet is small because of its tiny size and the relatively low muzzle velocity of the weapon. The 'four-ten' will almost never exit and even the twelve-bore rarely causes a through-and-through wound of the adult chest or abdomen. The pellets often penetrate the distal chest wall, but are held up beneath the skin of the further side of the trunk. Commonly a bruise may be seen in the deep tissues of the frustrated exit site and lead shot may be felt under the skin, which is tough enough to prevent the final exit phase.
- In the head, neck and limbs, and in children and small thin adults, the twelve-bore commonly causes an exit wound which may be extremely large and ragged, with gross tissue destruction exposed. One of the most common is that seen when a twelve-bore is discharged suicidally into the mouth; this may disrupt the head, and expel most of the brain through a massive skull and scalp defect – the so-called 'burst head'.
- The internal track is more diffuse than that caused by a rifled weapon, though where the discharge is contact or close, the compacted mass of shot travels as a unit for some distance into the tissues before dispersing. In general, the internal damage caused by a shotgun is diffuse and is caused by direct mechanical disruption by the shot, which enters at relatively low velocity. There is no cavitation effect as is seen in high-velocity injuries, the tissue being physically smashed by the impact of a heavy load of pellets and, in the case of near discharges, by the large volume of hot propellant gases.
- Wad wounds can be caused by the non-metallic contents of a shotgun cartridge. As mentioned earlier, the new devices now often used in shotgun ammunition may cause characteristic injuries, such as the square cruciate mark from the wings of the opened plastic cup that contains the shot. Felt and plastic wads travel a variable distance from the gun muzzle, depending on many factors, such as the type of cartridge, the amount of propellant load and the nature of the wads. The wads fall away much more quickly than the lead shot because of their low weight and high air resistance. At contact and close ranges they will almost always enter the wound and should be recovered at autopsy in order to assist in identifying the type of ammunition (Fig. 8.26).
- Beyond 1–2 m, the wad may drop sufficiently to miss the main wound and strike the skin at a lower point. From 2–5 m, the wads may or may not strike the body, and further than this distance it is almost certain that the wads will fall to the ground. As with all variables associated with firearm wounds, however, it is essential for test firing to be performed wherever possible. The pathologist should not be dogmatic or impracticably precise about distances, but offer a bracket of reasonable probability.
- Tangential wounds can offer considerable difficulty in recognition to the inexperienced observer, who may attribute them being knife wounds or blunt



Figure 8.26 Lead pellets and felt cartridge wads from a twelve-bore shotgun wound. It is important to recover at least a sample of pellets and the wads so that the type of cartridge can be identified.

injuries, when in fact they have been gunshot wounds. The shallow cone of a shotgun discharge may pass any part of the body so that the central axis is clear of the tissues, but the periphery strikes the body surface tangentially. The most common position is probably the side of the chest, in the lower axilla. If the arm is raised it may escape damage, but sometimes an opposing injury is seen on the chest wall and inner part of the upper arm. Another area is the side of the face, where a glancing gun blast may gouge the face and perhaps carry away an ear.

The appearance of the wound depends, of course, on the range and the depth to which the cone of shot and gas penetrates. On the side of the chest, a large elliptical skin area may be ripped from the surface to expose underlying muscle and ribs. If a close discharge, then the nature of the injury will be clear from the usual soiling of the muzzle gases, but a more distant shot may cause a clean wound that can give rise to doubt about causation. CT scan or radiography will usually reveal lead shot in the tissues, unless the contact is extremely superficial.

In the chest – even if shot penetration is minimal – severe damage to the pleura and lungs may occur from the tangential impact, and death may occur from a haemothorax with or without lung laceration or contusion or rarely from air embolism (Figs 8.27–8.29).[32–34]

When the side of the head is hit, shattering of skull or facial bones can occur and intracranial damage is common, even though no metallic projectiles enter the cranium.



Figure 8.27 Pellet injuries from a distant twelve-bore shotgun discharge (see also Fig. 8.28). The child had been walking behind a hunter carrying a shotgun on his shoulder the barrel pointing down. When the hunter was ducking to avoid branches of a tree the shotgun was triggered by a branch.



Figure 8.28 Pellet injuries puncturing the oesophagus and both lungs (see also Fig. 8.27).



Figure 8.29 Hunting accident in which the male was hit by four pellets from a distant twelve-bore shotgun discharge. Pellet No. 1 punctured the abdominal skin and was found in the subcutaneous fat; pellet No. 2 bruised the right wrist; pellet No. 3 penetrated the chest wall and was found in the pericardial fat tissue without any injury to the heart; pellet No. 4 hit the corner of the left eye and travelled through the left cerebral hemisphere, causing death.

Wounds from rifled weapons

Injuries from rifled weapons vary greatly according to the velocity of the projectile, as discussed at the beginning of this chapter, but there are some characteristics common to all types. Unlike shotguns there is only one missile in each discharge, though an automatic weapon may well cause multiple wounds in close succession which impact upon the same area of the body. Occasionally, because of some defect in the weapon, two bullets may be fired at once, or a fragment of metal may detach from cartridge, barrel or bullet, so that two missiles may strike simultaneously; this is described later.

Contact wounds

When a weapon is fired in contact with the skin, the appearances can vary according to whether the muzzle was firmly pressed against the surface so as to form a tight seal – or whether it was merely held in loose contact, so that the backward jerk of recoil can permit a small gap to appear (Figs 8.32, 8.39, 8.40, 8.45). Yet another permutation is when clothing is interposed between the muzzle and the skin.

When a rifled weapon is held firmly against the body surface during discharge, the resulting wound is in many respects similar to that from a shotgun. A twelve-bore wound is usually much larger, but a .410 can closely resemble a large-calibre rifled weapon injury. Over deep soft tissues, such as the limbs, abdomen, neck and usually chest, the wound will be small and circular. There will be blackening of the immediate wound edges, but if the seal between muzzle and skin is tight, there will be little or no sideways escape of soiling unless clothing is interposed.

Within the wound, there will be some flecking with soot in the tissues, a powder cavity, the amount varying with the 'cleanliness' or otherwise of the particular ammunition.[12,35,36] Most rifled weapon ammunition is 'clean', compared with many shotgun cartridges, so that superficial soot may be absent altogether. There is usually an areola of reddening that extends beyond the diameter of the muzzle as carbon monoxide has reacted with the haemoglobin and myoglobin in the vicinity of the skin wound and in the deeper track. There may be bruising, sometimes extensive, though this is rarely symmetrical and is often absent. The expansion of the tissues by gas entry tends to force the skin even harder against the end of the barrel and a 'muzzle imprint' may be formed. In rifled weapons, especially handguns, there are more features at the end of the barrel than in shotguns, so complex imprints may be made of foresights and mechanisms for self-loading in 'automatics' (Fig. 8.30).



Figure 8.30 Suicidal contact wound with muzzle mark from a 9 mm pistol (see also Fig. 8.31 for corresponding exit wound).

If the contact wound is over a bony support, especially the skull, then the same phenomenon occurs as in shotgun wounds. The muzzle gases entering the subcutaneous tissues cannot expand by displacing adjacent soft structures and are reflected from the bone to raise a dome of gas that often splits the skin around the entry hole. This results in radial (cruciate or stellate) skin tears due to overstretching (Fig. 8.38). In contact shots to the cerebral cranium, the periosteum around the bone defect is often detached and covered with soot on its underside.[36] As the volume of gas produced is usually less than that formed by the large mass of propellant in a twelve-bore shotgun cartridge, the radial tears may be shorter – though the charge in some rifles and handguns is comparable to that of shotgun shells.

When the contact is loose, soiling in the immediate vicinity of the muzzle may occur – again modified as in the case of shotguns, by the interposition of clothing between muzzle and skin. The fabric allows a lateral passageway for the combustion gases, as the muzzle cannot make such a good seal as against skin.



Figure 8.31 Suicidal exit wound from a 9 mm pistol (see also Fig. 8.30 for corresponding entrance wound).



Figure 8.32 Numerous tears in the lips due to expansion of muzzle gases from a 9 mm pistol fired in the mouth.

If the skin of the gun hand remains in firm contact with the weapon steel for a longer period of time, rust stains may develop as seen in Fig. 8.37. In experiments in the living as well as corpses, the formation of rust stains depends on the firmness of the contact, humidity of the skin and the environment, contact time and the



Figure 8.33 Slightly deformed full-jacketed bullet in the middle of the cone-shaped exit wound on top of the skull. Homicidal entrance wound under the chin.



Figure 8.34 Slit-like exit wound on top of the head from a suicidal gunshot wound to the mouth with the entrance wound in the palate.



Figure 8.35 Wrist of a homicide victim, who had raised her left hand to ward off the attack, showing a 'clean' exit wound of a full-jacketed bullet in the middle and soot-soiled entrance wound beneath it.



Figure 8.36 Intravital CT scan of a 23-year-old male who in the course of a 'Russian roulette' shot himself in the right temple with a .357 cal. Magnum revolver. Extensive injury of the cranium and brain with several dense metallic structures (lead fragments from the bullet). (Department of Radiology of Turku University Hospital, reproduced by kind permission of Professor M. Kormano.)



Figure 8.37 Rust stains on the gun-hand of a suicide corresponding to the shape of the grip.

state of the weapon surface.[37] The shortest period of time necessary for the formation of rust under the most favourable circumstances, as reported by Ulrich and Zollinger, was 135 minutes for a corpse and 27 minutes for a living person.

Blow back into the barrel – 'back spatter'

Contact wounds – and also close-range discharges – may cause blood and tissue fragments to enter the muzzle, sometimes penetrating for several centimetres, this being called 'back spatter'. There appears to be a momentary suction effect after the pressure of the gas blast subsides, possibly as a result of rapid relative cooling in the barrel. This seems to aspirate material into the muzzle and pieces of skin, hair and adipose tissue have been found inside the weapon. Sometimes blood and tissue may soil the hand or arm of the person firing the gun, a matter of considerable significance in forensic science.[31,38–49]

Close-range wounds

When there is a short distance between the muzzle and body surface, the appearances of the wound will vary accordingly to the type of ammunition used. The wound will almost invariably be circular as the tearing due to gas intrusion is unlikely to occur. As will be described in medium-range wounds, there will be an abrasion collar.

Modern propellant produces less flame than the black powder of older shotgun cartridges, but within a few centimetres of bare skin there may be singeing of hairs. Even where hairs are not destroyed, they may be 'clubbed', that is, the keratin melts at the tip and resolidifies as a tiny blob.



Figure 8.38 A firm contact discharge against tissue overlying bone (such as the skull) causes gas to rebound from the rigid base. This raises a dome under the skin that can split to give a ragged entrance wound. This effect is by no means invariable.



Figure 8.39 Suicidal contact wound in the neck (arrow) from a 7.62 cal. rifle with destruction of the head.



Figure 8.40 Suicidal entrance wound in the chest from a 7.62 cal. rifle.



Figure 8.41 Exit wound of the 7.62 cal. rifle shot shown in Fig. 8.40.

Soot or smoke soiling and powder tattooing

Though most propellant is now 'clean', some soot may be seen around the wound. In addition, there will be tiny lesions from specks of incandescent propellant, the so-called 'powder tattooing'. These gunshot residues (GSR) may pepper the vicinity of the entry hole in a roughly symmetrical pattern, which may assist in determining the angle of impact. Particles of propellant carry further than smoke, so tattooing around the entrance wound in the absence of soot indicates a greater distance (Figs 8.42–8.44). The soot rarely carries more than 15 cm (6 in.) from a pistol, whereas powder grains will travel 30–45 cm (12–18 in.); however, these distances are approximate and can be doubled for a rifle compared with a handgun. In addition to the firing distance the gunpowder residue pattern depends on several other factors such as the type and make of the gun, calibre, barrel length, propellant type and burning rate, primer, muzzle-target angle and target material.[12,30,31,50–58] It must be emphasized once again that test firing is essential for any hope of accuracy.

Minute flakes of unburnt propellant or inert filler may land on the same area of skin; these tend to glisten and may be orange or blue, depending on the manufacturer. It is important that a forensic scientist or police scene of crime officer has the opportunity to retrieve these before the wound is washed. If no such person is available, the pathologist should collect the GSR using a kit according to the instructions provided by the local police or crime laboratory. Usually the



Figure 8.42 Close-range pistol entrance wound. The eyelid and lower forehead show tiny lesions from propellant flakes. The eyes are blackened by fractures of the floor of the anterior fossa.



Figure 8.43 Entrance wounds from a 7.65 cal. auto-loading pistol in the forehead and right side of the face (arrow) of a homicide victim, with soot soiling.



Figure 8.44 A suicidal shooting from a .22 rifle. The extensive soot staining of the clothing indicates a very close discharge.



Figure 8.45 A suicidal entrance wound of a .22 rifle bullet with a silencer imprint.

tape-lift method is used where aluminium stubs coated with adhesive tape are repeatedly pressed against the surface (e.g. hand) to collect the particles.[57,59–61] If none of this is available the pathologist should cut out the skin around the wound and preserve it unfixed (refrigerated if necessary). These specimens should be sent for expert forensic examination, as they may indicate the nature of the ammunition and may be matched to that in the possession of a suspect. As with contact wounds, carboxyhaemoglobin and myoglobin will be present in the wound track in diminishing concentrations as the range increases.

The estimation of range is dealt with later, but here it is again emphasized that until test firing is carried out with a similar weapon and ammunition, only an approximate estimate can be offered from the appearances of the wound. The use of a silencer is likely to reduce the energy of the projectile and the amount of soot soiling and powder tattooing creating the impression of a longer firing distance.[57,62]

Medium-distance wounds

Unlike the shotgun, once the discharge of a rifled weapon is greater than 1 m, there is nothing to indicate increasing range, until perhaps the erratic trajectory of extreme distance suggests maximum range. From perhaps less than half a metre to up to several kilometres the entry wound of a high-velocity rifled weapon appears the same (Fig. 8.46).

The size of the hole is rarely equal to the diameter of the missile and therefore the calibre of the weapon cannot instantly be determined by inspection of the wound – in spite of the apparent ease with which television drama doctors and detectives can instantly spot 'a thirty-two' or a 'thirty-eight'. Immediately after entry, the skin undergoes elastic recoil and the resulting hole is usually smaller than the diameter of the bullet unless the range is so close that gas entry – or gas rebound – contributes to the size of the wound. The most striking difference between the size of the entrance hole and the diameter of the bullet is seen where the cornified layer (stratum corneum) of the epidermis is thick as in palmar and plantar skin and particularly in nails where the entrance hole can be minute in comparison to the bullet size.[63,64]

The abrasion collar

The skin immediately around the central hole is discoloured, the so-called 'abrasion collar' or 'contusion ring' (Figs 8.47, 8.49, 8.51). This may be only a narrow rim or may be equal in width to the central defect. The theories as to its origin are still somewhat diverging. It was long assumed that the collar was due to the inversion of the skin during penetration by the missile so that the epidermis is abraded by friction. Based on his experimental work applying human skin and high-speed photography (70,000 frame/s), Sellier was the first to show that when the bullet head perforates the skin, the latter is radially accelerated and centrifugally displaced and does not come into contact with the bullet in such a way that it would directly abrade the skin.[65] He further showed that fine tissue particles are 'back spattered' in the opposite direction and considered them the cause of the abrasion ring. Thali and coworkers applied high-speed photography (up to 50 million frames/s) to



Figure 8.46 Entrance of a .22 rifle bullet in a shooting accident.



Figure 8.47 Homicidal entrance wound from a 7.62 cal. hunting rifle in the back of the victim fired from across the room. There is a clear abrasion ring but no ring of dirt because of the covering clothing.

their synthetic ‘skin–skull–brain model’ and showed that after the initial contact of bullet and synthetic skin at the moment of penetration, the synthetic skin bulges and stretches conically outwards, losing direct contact (within approximately 50 µs) with the projectile. This bulging and stretching continues after the projectile has fully penetrated the synthetic skin after which it retracts due to its elasticity. They postulate that the abrasion ring is primarily due to the massive overstretching and subsequent drying-up of the skin adjacent to the area of projectile impact.[66]

In addition to the true abrasion collar, there is often a slightly wider circle where the epidermis is lifted



Figure 8.48 Extensive destruction and haemorrhage of the lung by the rifle shot shown in Fig. 8.47.



Figure 8.49 Multiple entry wounds from a military weapon capable of fully automatic fire. The wounds are in line and approximately evenly spaced. Each is a typical entry, with a roundish skin defect surrounded by a circumferential abrasion collar. There were massive exit wounds on the back, caused by .303 bullets from a Bren gun used by a Malayan patrol.



Figure 8.50 Bullet entrance wound, showing the removal of a wide area of skin for forensic examination, the hair having already been removed and preserved before photography. The autopsy incision around the wound is wide, to include any discharge residue and burned skin. The shape of the incision is obviously asymmetrical, to indicate the orientation of the sample after removal from the body.



Figure 8.51 Entrance of a .22 rifle bullet at a range of a few inches. There is slight smoke soiling around the wound, which has a well-marked abrasion collar, which appears black due to additional bullet wipe-off (ring of dirt). In fact, two shots were fired in quick succession through the same hole, which is slightly ovoid because of the non-congruence of the two shots.



Figure 8.52 The exit wounds in the fatality shown in Fig. 8.51. The two bullets have diverged inside the head from their common entrance wound and emerged separately. The exit wounds are typically stellate or slit-like and clean. With small-calibre missiles, such as a .22, there is often no exit wound, but here the small head and thin skull provide less resistance to complete traversing.

off showing irregular and torn-in edges. Progressive drying-up of this border zone simulates that the abrasion collar increases in width over time.[64]

The grease ring

The abrasion collar or its inner parts may be blackened due to overlying sooty remnants wiped-off by the bullet when hitting uncovered skin. This finding is called ‘grease ring’, ‘ring of dirt’ or ‘bullet wipe-off’. It can be regarded as a reliable sign of entrance. It is absent if the missile was clean because of prior perforation of another target (e.g. clothing).[67–69]

There may also be bruising around the wound from mechanical damage to adjacent intra- and subcutaneous blood vessels. No soot or powder particles can be found beyond a variable distance that usually will not exceed 1 m in the case of a rifle, and half that distance with a handgun.

The direction of discharge

As with smooth-bore weapons, a close range discharge may provide information about the angle of the shot because of the geometry of any smoke soiling and powder tattooing on the skin.[31,53,57,70,71] An impact at right angles will produce a circular zone of discolouration on the skin, while an oblique angle will result in an elliptical mark, the length of which increases as the angle decreases. As rifled weapons produce relatively little soiling except at close range, this clue is of less assistance than with shotguns.

Again as with smooth-bore guns, the edges of the wound may be shelved or ‘undercut’ when the discharge enters at an oblique angle. Tissue may be seen in the floor of the wound at one side, which indicates the direction from which the bullet came. Muscular contractions may distort this picture, however, and it is not always present, though minute inspection (using a lens if necessary) may reveal shelving in the deeper layers of the skin rather than in the tissues below. More useful is the shape of the abrasion collar, which will be asymmetrical if the bullet enters at an angle, even though the central hole often remains circular. The other means of determining direction, which is not usually available with shotguns, is the trajectory between entrance and exit wounds. These can be joined and projected in direction of approach to indicate the site of discharge. Two important conditions attach to this interpretation, however:

- If the bullet strikes a solid object, either bone or even a firm organ, it may be diverted within the body to exit well off the original trajectory.
- The posture of the victim’s body at the instant of impact must be taken into account. It is too often assumed, especially by lawyers, that all persons are injured – in whatever fashion – while standing passively in the ‘anatomical position’. Nothing is further from the truth, as people, especially in conditions of fight, fright or flight, may be moving or dodging in a variety of postures, which change by the second. For example, in one of the author’s (BK) cases, a female accidentally shot by a police officer had the anterior entrance wound much higher than the exit in her back. This did not mean that she was shot from above, but that she was leaning forward when the bullet hit her. Much more bizarre examples occur from time to time, such as another case seen by the author (BK) in which a puzzling high-angle wound in the chest was later proved to have been fired from an upstairs window as the victim was knocking on the front door below.

Bullet wounds in bone

Where a bullet passes through bone, especially the thin bone of the skull, the well-known pattern of ‘cratering’ can usually be seen, though there are exceptions.[25,36,45,46,66,72–96] Using the cranium as



Figure 8.53 The entrance wound of a bullet into a skull. Externally the defect is clean-cut and slightly ovoid because of the oblique impact of the missile. Internally, the inner table of the cranium is cratered, the bevel being caused by lack of support from the diploë. The exit hole on the opposite side of the skull showed a reversal of this pattern, with the cratering on the exterior surface.

the best example, the initial contact of the missile punches a clean hole through the outer table of the skull. Where the bullet emerges internally, the inner table is then unsupported and a cone-shaped plug is detached, forming a crater that is appreciably larger than the external hole. If the bullet traverses the cranium and penetrates the opposite side, the same pattern occurs, this time with the small hole on the inner table and the crater on the outside. In addition to these penetrating defects, there are often fissured, sometimes comminuted, fractures running away from the central holes (Figs 8.53, 8.54).

However, though this is the classical picture, a number of exceptions have been reported in the literature, where the cratering has been reversed or is otherwise atypical.[46,97,98]



Figure 8.54 Cone-shaped exit wound of the calvarium, with radial fractures in left parietal bone.

A shotgun usually destroys a large area of the skull, but similar shelving may be seen on the edges of bone fragments if a bolus of shot strikes the bone. Individual pellets rarely penetrate, but the massive cranial damage from close range of contact shotgun discharges is largely the result of the rapid and violent increase in intracranial pressure caused by the entry of a large volume of gas, as well as the bolus of shot and wads.

Where several bullets have struck the cranium, the sequence of shots can usually be determined using Puppe's rule, which is applicable to any multiple blunt force causing skull fractures.[99–102] Madea and Staak have developed this rule in relation to bullet injuries: the test depends on the observations of the fracture lines either when they intersect each other or when they intersect a cratered lesion, so that one can determine which crack or defect must have been formed first.[76,78]

Where bones with a medullary cavity are hit by a bullet the calibre of which is less than the diameter of the bone, fractures are caused primarily by hydraulic pressure in the bone marrow. Depending on the velocity of the bullet, part of the kinetic energy is transferred to the bone and fragments will be propelled both in direction of the shot as well as into the opposite direction; however, they will stay within the temporary wound cavity. Contrary to earlier beliefs, they do not act as secondary projectiles as they posses too little energy to create wound channels outside the temporary wound cavity.[103] CT scan or radiography, where available, can be used to detect and orientate fragments of bone and differentiate them from missiles and missile fragments.[57,85,94,95,104,105]

Exit wounds

When a gunshot wound completely traverses the part of the body struck, an exit wound will result.

Shotgun exit wounds

When smooth-bore weapons are involved, the residual energy of the individual pellets (which have a small mass and a relatively low initial velocity) is usually insufficient for them to emerge through the wider parts of the body, such as the chest and abdomen. Wounds of the limbs, neck and head may well be 'through-and-through' with a twelve-bore shotgun and occasionally, though rarely, with the small 'four-ten'. The range has an effect on the possibility of a shotgun exit wound, as contact or close-range discharge will allow the compacted mass of shot to act like a single bolus – in addition to which, the large volume of intruded gas assists in disrupting the tissues and clearing a path for the missiles, especially in the head. A shotgun blast into the mouth may well remove much of the back of the head as an exit wound, but this is in part caused by the explosion of the cranium by the gas, the so-called 'burst head', which can occur in any gunshot wound of the head, whether into the mouth or elsewhere.[57,106]

The appearance of a shotgun exit wound is totally random, depending on the anatomical part injured and the addition of any bone or tissue fragments blown out in the discharge. Typically, it is a jagged, irregular laceration with everted edges that exposes deep tissues and comminuted bone fragments beneath. A shotgun injury of the chest or abdomen often just fails to exit on the opposite side, because the toughest obstruction, other than bone, is the skin. It is not uncommon to be able to palpate lead shot under the skin in the contralateral position after it has traversed the body and been trapped by the skin.

As a contact shotgun discharge may produce a large, ragged, entrance wound, this may resemble the exit wound, if present. Differentiation is usually simple if soiling is present around the entrance. It has been said that the presence of carbon monoxide in the tissues marks the entrance wound, even in decomposed bodies, but carbon monoxide can in fact be detected right through a close shotgun discharge, though the concentration should be greater near the entrance.

Exit wounds from rifled weapons

As stated above, many wounds from rifled guns are 'through-and-through', especially from high-velocity military weapons. The muzzle velocity is important in determining whether a single bullet will completely traverse the body. A high-velocity missile (of the order of 800 m/s or 4200 ft/s) is likely to pass right through the body unless it strikes a large bony structure like the spine, large limb bone or base of the skull. As discussed at the beginning of the chapter, this may be inefficient in terms of wounding capability, as much of the kinetic energy fails to be transferred to the tissues to cause damage, although the cavitating effects of a high-speed missile in vital tissues may be extremely damaging. If the missile does not strike bone or cartilage, it is likely to emerge on the other side of the body, even through the thickness of the chest or abdomen. Of course, in many cases where bone is penetrated (especially the skull or ribs), the bullet will still emerge, but this is considered below (Figs 8.31, 8.33, 8.34, 8.36, 8.41).

If a fairly intact bullet emerges, not having been seriously deformed or fragmented, the size of the exit wound depends mainly on the size of the temporary wound cavity at that particular point of exit and is likely to be an everted defect, either circular or with torn edges. The classical description is likely to be a slit-like or stellate skin severance, where the bullet has pushed out against unsupported skin (Figs 8.52, 8.55, 8.56, 8.59–8.62).

It is naturally important to confirm the direction of the shot, but where a bullet has come from any distance between half a metre and near the extreme range of the weapon, then both entrance and exit wounds can look remarkably similar. There will be soiling to indicate the entry and identification will depend upon the close examination of the margins of the wounds. Where the skin was covered by clothing, fibres of fabric may enter both the entrance and the exit wound.



Figure 8.55 Atypical slit-like exit wound of a homicidal firearm wound from a hunting rifle with entrance wound in the back of the same victim shown in Figs 8.47, 8.48.



Figure 8.56 Homicidal exit wound behind the ear. Weapon Smith & Wesson cal. 0.357.



Figure 8.57 Schmeisser pistol, cal. 6.35, found on the lap of the perpetrator at the scene of a homicide suicide. Case jammed in ejection port.

The skin may be supported at the moment of penetration. A firm brassière band or an elasticated trouser waistband can press on the skin and prevent eversion, as can a plaster or fibreboard wall, if the victim was leaning against it. In these instances, there may even be a spurious 'abrasion collar', which is really caused by the emerging bullet slamming the wound periphery against the resisting surface. In difficult cases the forensic pathologist or a deputy should examine clothing and the scene, to see if there are any such factors that will help in arriving at a definite answer as to direction.



Figure 8.58 Disintegration of the head of a young female terrorist in the Malayan emergency from a single bullet entering the external auditory meatus. The weapon was a F-N rifle with a high muzzle velocity; the impact of the missile on the base of the skull instantly converted the kinetic energy into a virtual explosion.



Figure 8.59 Atypical slit-like exit wound of a 7.65 cal. bullet (see Fig. 8.43).

Usually, the abrasion collar and frayed keratin ring of the entrance wound will be of diagnostic significance, as it is absent in the exit wound, except as detailed above. Occasionally, however, the abrasion collar of the entrance wound is merely a narrow rim that needs close inspection to detect. Where the bullet has hit bone within the body, the bullet may emerge sideways causing a longer or otherwise distorted exit wound.



Figure 8.60 Typical exit wound from a 9 mm bullet. The wound in the scalp is everted, stellate and quite clean, the missile having been wiped by its passage through the tissues.



Figure 8.61 Exit wound of a 9 mm pistol fired into the mouth.



Figure 8.62 Exit wound of the bullet responsible for the wound seen in Figure 8.50, showing the classical everted, split edges, with no soiling of the surrounding skin.

Of the many bizarre findings in gunshot wounds, re-entry can pose some problems.[107–116] One case seen by the author (BK) had two entrance and one exit wounds, with a single bullet in the body. The victim had been standing against a wall when shot from the front: the bullet emerged through his back, ricocheted from the wall and re-entered his body.

Penetration of two parts of the body is quite common, a single missile causing several wounds. The most usual is a through-and-through wound of the arm or leg, the bullet then re-entering the abdomen or chest. Placing the limb in the appropriate position immediately clarifies the situation and can considerably aid an estimation of direction (Fig. 8.35).

Firearm damage to internal organs

This may be of any nature, but broadly falls into two categories:[117,118]

- Contusion and laceration from low-velocity impact. Where a mass of shotgun pellets and gas strike tissues or an organ the damage is simple mechanical disruption, with widespread haemorrhage from local vessels. Similar, though less extensive, damage is likely from a low-velocity rifled bullet or slug, which pushes the tissues apart as it ploughs through an organ or muscle. The danger to life that ensues naturally depends upon the target tissues – a clean wound through the thigh may cause only temporary disability, whereas the same wound through heart or brain may well be rapidly fatal.
- High-velocity missiles produce disproportionate damage relative to their diameter because of cavitation effects, described at the beginning of the chapter. This is particularly damaging in solid organs, such as the brain and liver. The track may be many times wider than the diameter of the bullet, and may consist of pulped and haemorrhagic tissue left behind by the pulsating cavitation effect caused by the lateral transfer of energy as the missile passes through.

Estimating the range of discharge

This is one of the most important aspects of the interpretation of firearm wounds.[12,50,51,55,57,58,119–127] Though guidelines can be offered, it cannot be emphasized too strongly that every weapon and batch of ammunition will vary, so that medical opinion must always defer to the results of test firing with the same gun and similar shells. Allowance must also be made for the effect of interposed clothing.

Rifled weapons

Tight contact over soft tissues

- Possible muzzle imprint.
- Circular hole with abrasion collar.
- Bruising.
- Powder cavity ('pocket').
- Local reddening from carbon monoxide.
- Little or no external propellant soiling or powder tattooing.

Tight contact over underlying bone

- Muzzle imprint.
- Split or cruciate wound (not always in .22 and .25 cal.).
- Local reddening and carbon monoxide.
- Bruising.
- Detached periosteum with soot soiling underneath.
- Little or no external propellant soiling.

Discharge from less than 15 cm (6 in.)

- Circular hole with abrasion collar.
- Ring of dirt (on primary targets).
- Burnt hairs.
- Soot soiling (depending on ammunition).
- Small punctate skin lesions from propellant tattooing.
- Unburnt propellant flakes.
- Little or no carboxyhaemoglobin in tissues.

Discharge from 15–30 cm (6–12 in.)

- No soot, but perhaps powder tattooing, depending on barrel length.
- No carboxyhaemoglobin.

Discharge from more than 40–60 cm (16–24 in.)

- Circular hole with abrasion collar and ring of dirt (on primary targets).
- No burning, soiling, burnt hairs or carboxyhaemoglobin.

Smooth-bore shotguns

Tight contact discharge over soft tissues

- Single circular wound about diameter of muzzle.
- Smooth margin.
- Often muzzle imprint.
- Blackened edge.
- No surrounding smoke soiling unless clothing allows leakage.
- Deep bruising.
- Pink tissues from carboxyhaemoglobin.
- Wads in the depth of the wound.

Tight contact discharge over skull or bony area

As last type, but wound may be ragged and split from gas rebound.

Discharge within a few centimetres

- Circular wound, unless oblique discharge.
- Smooth or slightly crenated margin.
- No satellite pellet holes.
- Surrounding soot soiling.
- Punctate skin lesions from powder particles.
- May be unburnt powder flakes.
- Burnt hairs.
- Pink carboxyhaemoglobin in tissues.
- Wads in the depth of the wound.

Discharge from 30 cm (12 in.)

- Circular 'rat-hole' wound with nibbled margins.
- No satellite pellet holes.
- Soot soiling may persist.
- Powder tattooing present.
- Little or no carboxyhaemoglobin.
- Wads in the depth of the wound.

Discharge from 1–5 m (39–195 in.)

- Central 'rat-hole' wound.
- Satellite pellet holes around periphery.
- No soot.
- Maybe slight tattooing at 1 m.
- No carboxyhaemoglobin.
- Wads not in wound at upper part of this range, but possibly imprint in the vicinity.

Discharge over 5 m (195 in.)

- Diffuse pellet pattern.
- Probably no central hole.
- No burning, soot, tattooing, carboxyhaemoglobin, no imprint from wads.

All the foregoing data are very variable, being dependent upon the individual weapon and ammunition. Test firing must be used to validate the pathological interpretation.

Airgun injuries

Air rifles and pistols produce wounds that have some of the characteristics of firearm injuries. The missile is single and fired through a rifled barrel, but is small and sometimes (Diabolo) resembles a shaped (waisted) shotgun pellet.

The muzzle velocity is relatively low, but some more sophisticated rifles, such as the German Weirauch, can produce more than 16 Joules (>12 foot-pounds) of energy and the pellet can sometimes penetrate a wooden door – and even the human skull (Fig. 8.65).

Two calibres are common, the .177 and the .22 inch, the latter naturally being the more dangerous. The .177 can, however, penetrate the thin temporal bone of a child and adult.[128] Wounds from an air weapon are rarely fatal except when the head is struck – and children are the usual victims. The pellet can enter the skull and traverse the whole width of the brain, but never produce an exit wound, being usually found in the contralateral meninges. The track may be surprisingly wide for such a low-velocity missile (Figs 8.63, 8.64).



Figure 8.63 Track through a child's brain made by a .177 inch air-rifle pellet (arrowed). Although a relatively low-velocity missile, the track is much wider than the pellet from lateral transfer of kinetic energy.

Apart from fatal head wounds, a number of eye injuries occur from airguns, the pellet lodging within the globe, the orbit or the adjacent air-sinuses. Radiology is obviously of prime importance in locating the missile, prior to surgical removal.

There are no particular features of an air weapon wound, as, of course, there are none of the heat, powder or soot effects of a firearm. The entry wound is small, but may show an abrasion ring. There is no ring of dirt and never an exit wound, unless the tissue traversed is extremely narrow. Both suicides and homicides have been reported in the literature.[129–138]



Figure 8.64 Airgun pellet in brain tissue.



Figure 8.65 Radiography can assist in locating a missile before autopsy, so that random searching does not cause instrument damage to the delicate striation pattern used for weapon identification. Here there is a lead pellet in the occipital lobe, with a bone defect in the extreme front of the skull.



Figure 8.66 A relatively unusual photograph in Britain, in that the suicide is of a female and an auto-loading pistol is used. Note the massive haemorrhage on the floor, which illustrates the possible extent of external bleeding.

Humane (veterinary) killers, industrial 'stud-guns' and blank-cartridge guns

> Slaughter-houses had to be licensed in the UK since 1785 and since 1835 the licence could be revoked on evidence of cruelty. In the beginning of the 20th century there were campaigns to introduce more humane slaughtering methods. In 1903 Hugo Heiss won a prize in Germany for his concept for a humane killer, the 'captive bolt pistol' and in 1906 Major Derriman in the UK designed a long-handled humane killer, which fired a large-calibre soft-nosed bullet.[139]

Powder-actuated tools of a specialized type are used in abattoirs and by veterinary surgeons to stun large animals. They may be of the 'captive-bolt' type, which consists of a metal rod, the distal end of which is propelled for several centimetres from the muzzle of the weapon by a blank cartridge inserted in a chamber behind the proximal end. The captive bolt inflicts a clean, penetrating injury. Some types (e.g. German Kerner) of the 'captive-bolt' weapons may have two or four symmetrical gas outlets in the muzzle plane beside the central opening, showing characteristic pattern of soot-soiling in contact or close range shots.[31,57,72,73,140,141]



Figure 8.67 Suicidal contact wound from a humane veterinary killer (see also Fig. 8.68).

Humane killers may cause injuries on humans either accidentally or suicidally, homicide being rare.[142–147] The nature of the weapon will almost always be apparent from the circumstances, including the presence of the weapon (Figs 8.67, 8.68). Death may be delayed due to complications, as in one case seen by the author (BK) where a farmer died of tetanus after accidentally shooting himself in the knee with a humane killer.

Blank cartridges have already been used in the 19th century as exercise ammunition of military rifles where



Figure 8.68 Bone defect in the right temporal region (arrow) from a humane veterinary killer (see also Fig. 8.67).

the projectile was replaced first by a paper bullet and later by a hollow wooden projectile or plastic wad that disintegrates when hitting a special blank-firing adaptor attached to the muzzle of the firearm. Nowadays blank firing guns are used similarly in training, theatrical events, as starter pistols in sports events but also in self-defence to threaten a potential assailant, particularly when loaded with tear gas cartridges. Often these pistols or revolvers are replicas of real weapons and are, due to easier access, also frequently used in criminal activities. In contact shots, or even when fired at close range, blank firing guns are capable of causing extensive damage to soft tissues, as the expelled gas can penetrate the thoracic wall, the neck and the inguinal region or cause fractures to the neurocranium. The presence of a muzzle imprint, the extent of burns (burns only with black powder), powder tattooing and soot soiling depend on the firing distance and the type of propellant. The injuries can be acutely lethal, e.g. due to air/gas embolism, exsanguination from injured blood vessels or heart rupture.[123,148–155]

Devices used in industry, especially the building trade, are the 'stud-guns' used for driving a hardened metal pin or threaded stud into masonry, or other wood or metal structures as a rapid and convenient means of attachment. A cartridge, often of .22 calibre, is used to drive a piston that acts as a hammer on the pin or stud. Many accidents and the occasional suicide have occurred from these tools, which resemble a long pistol, with a flat faceplate attached to the muzzle for pressing against the structure. Some accidents occur because the guns are used on relatively flimsy partitions, and the stud traverses the structure and flies on to injure or kill someone on the other side.[156–159]

Rubber and plastic bullets

Batons made of soft wood were introduced by the Federal Laboratories USA as a practice round for the tear gas (also CS gas; 2-chlorobenzalmalononitrile) cartridge and these were first used in the 1950s and 60s as anti-riot weapon by the Hong Kong Police Force.[160,161] In 1970 in Northern Ireland, the 'rubber bullet' was introduced as the first specially designed 'less-lethal' projectile for riot control that was intended to restrain by causing pain but not to cause severe injuries. The missiles used in the early 1970s were made of solid rubber measuring 15 cm by 35 mm in diameter tapering to a blunt point at one end and weighing 135–140 g. It was fired from a riot gun with a muzzle velocity of 73 m/s (240 ft/s), originally designed for firing canisters of tear gas.[160] The bullet is about the same weight as a cricket ball (155.9–163.0 g), but travels twice as fast as the best bowler could deliver it. Between 1970 and 1975, over 55,000 rubber bullets were fired during riot control in Northern Ireland.[162] These were abandoned in Britain in 1976 in favour of 'plastic batons', more commonly known as 'plastic bullets'. The baton round is a solid cylinder of polyvinylchloride (PVC) 38 mm in diameter and 10 cm long, weighing 135 g. When fired from a smooth-bore weapon it has a muzzle velocity of about 69 m/s (228 ft/s) and an effective range of 50–70 m. Police are instructed to fire at the lower half of the body, to avoid the more serious injuries arising from hitting the head or chest. It should not be fired at a person under about 20 m range. Many injuries and some deaths have been reported from their use. Fractures of the face and skull, eye damage including blinding, broken ribs and limbs, and contusions of liver, lung and spleen have occurred.[160,161,163] The death rate is said to be 1/16000–1/18000 rounds fired, compared with rubber bullets, which had a mortality rate of 1/4000 rounds.[160,161]

Since then, there are several reports on various new types of missiles for riot control by different manufacturers and injuries caused by them in Israel–Palestine, France, Kenya, Switzerland and the USA.[160,162–168]

Deaths from explosion

Deaths from the effects of explosive substances or devices occur in both civil and 'military' circumstances, though the latter now include a considerable proportion of terrorist activities rather than conventional wars. Civil tragedies are usually industrial, as in individual incidents in mines and quarries, or on a larger scale, such as the detonation of chemical stores, ships or factories.

The nature of explosive trauma

Several different factors cause injury following an explosion, and the relative importance of each varies considerably with the type of detonation. For example, pure blast effects are far more important with high-explosive projectiles designed for purely military use than with the home-made terrorist bombs, the lethality of which may be primarily caused by flying fragments. Death and injury from explosives is caused by:

- blast effects
- impact of projectiles derived from the explosive device
- impact from surrounding objects and debris impelled by the explosion
- burns from hot gas and incandescent objects
- secondary injuries from falling masonry, beams and furnishings dislodged by the explosion.

A blast consists of a wave of compression passing rapidly through the air – or water in the case of a submarine explosion, such as a mine. The velocity of the shock wave depends on the distance from the epicentre, being many times the speed of sound at the start, but rapidly decreasing as it spreads out. The compression wave is followed by a transient zone of low pressure (below atmospheric), so that a rapid double change in pressure is suffered by the body. The magnitude of the blast varies with the energy released and also with the distance from the epicentre, the intensity obeying the inverse square law. With all but powerful military high explosives, the blast effects of most terrorist devices fall off so rapidly with distance that only those in the immediate vicinity will suffer severe damage from blast. Not uncommonly, this type of victim is the bomb-setter himself, when a premature detonation occurs.

A blast causes the most damage at an interface between tissues in contact with the atmosphere, which is why the lung usually suffers the most. According to a study on fresh human cadavers the minimum pressure to rupture the tympanic membrane is about 35 kPa (5 lb/in.^{2}).[169,170] The minimum threshold for blast lung injury is about 104 kPa (15 lb/in.^{2}), the minimum lethality threshold about 207–290 kPa (30–42 lb/in.^{2}) and the 95–100 per cent fatal range about 400–552 kPa (58–80 lb/in.^{2}).[171,172] The shock wave can pass through solid, homogeneous tissues such as liver and muscle, causing little or no damage, but in the lung there is marked variation in density between the alveolar walls and the contained air so that damping of the shock wave occurs and energy is absorbed, with disruptive effects.

There is controversy about whether pulmonary damage occurs from direct transmission of the shock wave through the thoracic wall, or through the oronasal orifices and air passages. In any event, the autopsy signs are of subpleural patchy haemorrhages, often in the line of the ribs, intrapulmonary haemorrhage and bullae at the lung margins. The air passages may be filled with bloody froth causing airway obstruction and hypoxia in addition to the primary damage.

Microscopically the alveolar walls can be shredded by the acceleration and consequent tearing of the air-sac wall when the blast waves traverse the lung. Desquamated alveolar and bronchial epithelium is seen lying free. Large areas of haemorrhage are found, with either the alveolar pattern still visible or the architecture completely disorganized. Pulmonary haemorrhage in explosive incidents is often not caused solely by the blast, but may be from direct impact on the chest from flying objects, aspiration of blood from nasopharyngeal injuries.

The ear may suffer severe damage from a blast, but this is usually not discernible at autopsy without otoscopic or endoscopic examination of the tympanic membranes.[173,174] Clinical examination and testing (obviously in the living) reveals many lesions, but these are of little relevance to the pathologist.

The gastrointestinal system suffers from the effects of a blast because, like the lung, it contains air and gases, and is thus not a uniform medium for transit of the shock wave. Once again haemorrhage is the most common lesion, usually small foci of the order of 1 cm in size. They may form circumferential bands around the intestine or may be confined to the serous coat as focal haemorrhages. The caecum and colon are more often injured than the ileum, jejunum and stomach, probably because they are larger and often contain more gas. Occasionally ruptures of the gut occur if the blast is violent and the victim in near proximity.

Victims of explosions in water suffer a reverse order of gastrointestinal to lung damage. The former is more common and may be manifested as haemorrhages under the serous coats and mucosa. Perforations may occur and, in survivors, peritonitis is not uncommon. The perforations are often multiple and in any part of the intestine. Lung damage is believed to be less common in water; however, the vulnerability of various organs depends also on which parts of the body are exposed to the blast, i.e. whether the whole body is immersed in the water or floating on the surface with or without of a floating aid.[175] In some instances lung damage may be caused by impact transmitted up through the diaphragm.

Missile injuries in explosions

It is again emphasized that unless a sophisticated high-explosive military device is involved, or if the victim is virtually adjacent to a lower energy terrorist bomb, blast effects will rarely be the sole cause of death. The body will, however, be vulnerable to impact from solid fragments originating from the bomb casing or a container or conveyance, such as a car in which the bomb was concealed. Fragments of metals, from tiny splinters to large chunks or sheets, will be projected at high speed (Fig. 8.69). The smaller ones will not travel more than a few metres, but larger, heavier pieces can fly over considerable distances and can cause serious or fatal injuries in just the same way as projectiles from a firearm. In the open, debris is scoured away, including dust and dirt, which can impinge on the body to injure and discolour it.

At autopsy the body may appear pigmented from this dust blasting, the clothing causing a shadow effect similar to bathing suit protection from sunburn. A more common appearance is a 'peppering' as a result of the numerous small missiles causing bruises, lacerations and abrasions (Fig. 8.70). The lacerations are often puncture wounds, of varying size and depth. Burns may also discolour the body, especially those areas unprotected by clothing. Flash burns from the bomb itself only affect those nearby unless the device is massive, though singeing of hair and eyebrows is not uncommon. Other burns may be caused by ignition of clothing, or by the building or vehicle catching alight from the bomb effects –or from gas or petrol ignition.



Figure 8.69 Localized injury by an explosive device. The soldier picked up an apparently 'dud' smoke shell, which then detonated. He lived for some weeks, the injury having partly healed, though part of the face and skull were destroyed.

A massive bomb, or one where the victim is virtually on top of the device, may totally disrupt the body and fling unidentifiable pieces over a wide area (Fig. 8.72). Alternatively, part of the body may be totally destroyed, sometimes the remainder of the victim being remarkably intact. The legs may be blown off or the abdomen disrupted, or the hands and arms torn away. In terrorist attacks these effects may be seen in the person who was planting the bomb or carrying it to the place chosen for detonation. A premature explosion, sometimes during the act of setting the timer, may cause these localized injuries (Fig. 8.71).

The pathologist may be able to assist in reconstructing the events, as localized severe trauma obviously indicates



Figure 8.70 Numerous wounds and peppering by debris projected in a terrorist bomb blast. Blast injuries occur only in close proximity to the device – most injury is caused by flying projectiles. (Reproduced by kind permission of Professor T. K. Marshall.)



Figure 8.71 Anterior aspect of a male who had constructed an explosive device using dynamite. The device probably detonated prematurely, the blast disrupting the head and abdominal region.



Figure 8.72 Remains of a car where a suicide detonated dynamite on his lap. The roof of the car blew off and the disintegrated body parts lay scattered around the vehicle (arrow).

the relative position of the bomb and the victim at the time of detonation. If the lower legs are destroyed, then the person was standing near the device that lay on the ground. Punctured wounds and bruises on the front of the thighs and trunk will indicate that he was facing the bomb. If the thighs, pelvic region and abdomen are damaged, the bomb may have been carried on the lap – and if the hands, chest and face are the most affected areas, the deceased may have been bending over the device.[176]

The autopsy in explosion deaths

The salient features have already been described and much of the autopsy is directed at listing the injuries, as in any other trauma death. The interpretation outlined above, however, may be most important for the investigators.

There are some more specific matters in an explosion death, which the pathologist must bear in mind. Firstly, trace evidence may be vital to the forensic scientists and bomb experts, who are trying to trace the maker of a terrorist device. X-rays, or multislice CT whenever available, should be taken of all bodies before autopsy to identify any radio-opaque objects. Not only will this assist in detecting lethal missiles not visible from the surface, but it may reveal small metal objects that form part of the bomb mechanism, such as small springs or contacts from the timer or detonator. These may be invaluable in allowing the experts to recognize the handiwork of a particular bomb-maker or terrorist group. Such radiography may also reveal the unexpected, which in the past has included a bullet, the victim having been blown up after death from shooting. Even prior to radiography, there may be much that the pathologist has to do. Though many explosion victims are relatively intact, where extensive disruption has occurred, the fragments have to be collected and sorted out in the mortuary.

A major initial problem is to discover how many bodies are represented and to try to allot the correct fragments to the right individuals. Where there are a number of victims and a large pile of small fragments, this task may be difficult or impossible, but it is naturally of paramount importance to determine how many victims are involved and to determine the sex of each. This is largely an anatomical exercise, akin to the sorting of multiple skeletal remains. Careful identification of all recognizable structures, such as prostate, uterus, breasts, scalp, eyes, for example, is needed in addition to more gross sorting of limb and trunk fragments. Radiology may again assist in matching contained skeletal structures, but much of the debris accumulated after a large explosion consists mainly of skin and attached tissues.

In spite of the most thorough police search of the scene, considerable proportions of some bodies are never recovered, having been disrupted into tiny fragments and mixed with the masonry and other debris of the bomb site. The collected fragments have to be washed clean from the inevitable dirt that coats them and sorted into groups by anatomical similarity. Non-human tissue is discarded, as animal material is not uncommonly admixed. The completed piles of tissue are then resorted by any apparent similarity, such as racial pigmentation, hair colour and sex. Limbs and large joints are then sorted, allotting them to left and right from anatomical considerations.

The difficulties of such a task were emphasized by Professor TK Marshall, whose experiences in Northern Ireland make his writings on the subject the definitive guide to such tragedies. In one of his incidents, eight victims were accounted for, when a single penile fragment forced the inevitable conclusion that there were in fact nine victims, not eight, though no other recognizable part of this ninth man was ever discovered. He had presumably been the bomb-carrier and had been completely disintegrated.

References

1 Taubman P. Explosive Bullet Struck Reagan, F.B.I. Discovers. In: *The New York Times*. New York: The New York Times Company, 1981.

2 Aaron BL, Rockoff SD. The attempted assassination of President Reagan. Medical implications and historical perspective. *JAMA* 1994;272(21):1689–93.

3 Powers DB, Robertson OB. Ten common myths of ballistic injuries. *Oral Maxillofac Surg Clin North Am* 2005;17(3):251–259.
4 Harvey EN, Korr IM, *et al.* Secondary damage in wounding due to pressure changes accompanying the passage of high velocity missiles. *Surgery* 1947;21(2):218–39.
5 Suneson A, Hansson HA, Seeman T. Peripheral high-energy missile hits cause pressure changes and damage to the nervous system: experimental studies on pigs. *J Trauma* 1987;27(7):782–9.
6 Fackler ML. Wound ballistics. A review of common misconceptions. *JAMA* 1988;259(18):2730–6.
7 Fackler ML, Peters CE. Ascribing local, regional, and distant injuries to the sonic pressure wave. *J Trauma* 1989;29(10):1455.
8 Sellier KG, Kneubuehl BP. *Wound Ballistics and the Scientific Background*. Amsterdam: Elsevier Science, 1994.
9 Courtney A, Courtney M. Links between traumatic brain injury and ballistic pressure waves originating in the thoracic cavity and extremities. *Brain Inj* 2007;21(7):657–62.
10 Maiden N. Ballistics reviews: mechanisms of bullet wound trauma. *Forensic Sci Med Pathol* 2009;5(3):204–9.
11 Owen-Smith MS. *High Velocity Missile Wounds*. London: Edward Arnold, 1981.
12 Große Perdekamp M, *et al.* GSR deposition along the bullet path in contact shots to composite models. *Int J Legal Med* 2011;125(1):67–73.
13 Karger B, Teige K, Brinkmann B. [2 suicides with self-fabricated gunshot devices: technical forensic and morphologic ballistic characteristics]. Arch Kriminol 1995;195(5–6):147–52.
14 Uner HB, Gurpinar SS, Cakir I. Mole gun – an unusual firearm, a case note. *Forensic Sci Int* 2001;118(1):83–5.
15 Alessi G, Aiyer S, Nathoo N. Home-made gun injury: spontaneous version and anterior migration of bullet. *Br J Neurosurg* 2002;16(4):381–4.
16 Cunliffe CH, Denton JS. An atypical gunshot wound from a home-made zip gun – the value of a thorough scene investigation. *J Forensic Sci* 2008;53(1):216–8.
17 Demirci S, *et al.* Deaths caused by mole guns: three case reports. *Int J Legal Med* 2008;122(4):323–5.
18 Keskin M, *et al.* Close range gun shot injuries of the hand with the 'mole gun'. *J Trauma* 2009;67(1):139–42.
19 Hejna P, Safr M. An unusual zip gun suicide – medicolegal and ballistic examination. *J Forensic Sci* 2010;55(1):254–7.
20 Fox JA, Zawitz MW. *Homicide Trends in the United States*. Office of Justice Programs: B.o.J. Statistics, 2011.
21 Werkgartner A. Eigenartige hautverletzungen durch schüsse aus angesetzten selbstladepistolen. *Beitr Gerichtl Med* 1924;6:148–61.
22 Werkgartner A. Schürfungs – und stanzverletzungen der haut am einschuß durch die mündung der waffe. *Dtsch Z Gesamte Gerichtl Med* 1928;11(1):154–168.
23 Hausbrandt F. Experimentelle studien zur entstehungsmechanik und morphologie einiger nahschußzeichen. *Dtsch Z Gesamte Gerichtl Med* 1943;38(2):45–76.
24 Elbel H. Studies on the development of punch wounds at absolute close range [Studien zur entstehung der stanzverletzung bei absoluten nahschüssen]. *Die Medizinische Welt* 1958;2(9):343–5.
25 Thali MJ, *et al.* The dynamic development of the muzzle imprint by contact gunshot: high-speed documentation utilizing the 'skin–skull–brain model'. *Forensic Sci Int* 2002; 127(3):168–73.
26 Paltauf A. Über die einwirkung von pulvergasen auf das blut und einen neuen befund beim nahschuss. *Wien Klin Wochenschr* 1890;3:984–91, 1015–17.
27 Meyer W. Die kriterien des nahschusses bei verwendung rauchschwacher pulver. *Vierteljahresschr Gerichtl Med* 1908; 3.F.(55):22–37.
28 Prokop O. *Lehrbuch der Gerichtlichen Medizin*, 2nd edn. Berlin: VEB Verlag Volk und Gesundheit, 1966.
29 Ropohl D. Schussverletzungen. In: Forster B (ed). *Praxis der Rechtsmedizin für Mediziner und Juristen*. Stuttgart: Georg Thieme, 1986, pp. 155–87.
30 Karger B. Forensische ballistik von schussverletzungen. *Rechtsmedizin* 2001;11(3):104–19.
31 Pollak S, Rothschild MA. Gunshot injuries as a topic of medicolegal research in the German-speaking countries from the beginning of the 20th century up to the present time. *Forensic Sci Int* 2004;144(2–3):201–10.
32 Nicolaou N, Conlan AA. High-velocity missile injuries of the thorax. *South African Med J* 1982;62(10):324–8.
33 Platz E. Tangential gunshot wound to the chest causing venous air embolism: a case report and review. *J Emerg Med* 2011;41(2):e25–9.
34 Temlett J, Byard RW. Air embolism: an unusual cause of delayed death following gunshot wound to the chest. *Med Sci Law* 2011;51(1):56–7.
35 Perdekamp MG, *et al.* [Contact shot from infantry weapons with a flash-suppressor]. *Arch Kriminol* 2003;212(1–2):10–18.
36 Faller-Marquardt M, Bohnert M, Pollak S. Detachment of the periosteum and soot staining of its underside in contact shots to the cerebral cranium. *Int J Legal Med* 2004;118(6):343–7.
37 Ulrich U, Zollinger U. [Development of rust stains on the skin due to contact with a gun]. *Arch Kriminol* 2001;208(1–2):32–41.
38 Pex JO, Vaughan CH. Observations of high velocity bloodspatter on adjacent objects. *J Forensic Sci* 1987;32(6):1587–94.
39 Burnett BR. Detection of bone and bone-plus-bullet particles in backspatter from close-range shots to heads. *J Forensic Sci* 1991;36(6):1745–52.
40 Karger B, *et al.* Backspatter from experimental close-range shots to the head. I. Macrobackspatter. *Int J Legal Med* 1996;109(2):66–74.
41 Karger B, Brinkmann B. Multiple gunshot suicides: potential for physical activity and medico-legal aspects. *Int J Legal Med* 1997;110(4):188–92.
42 Karger B, *et al.* Backspatter from experimental close-range shots to the head. II. Microbackspatter and the morphology of bloodstains. *Int J Legal Med* 1997;110(1):27–30.
43 Schyma C, Placidi P. The accelerated polyvinyl-alcohol method for GSR collection –PVAL 2.0. *J Forensic Sci* 2000;45(6):1303–6.
44 Kleiber M, Stiller D, Wiegand P. Assessment of shooting distance on the basis of bloodstain analysis and histological examinations. *Forensic Sci Int* 2001;119(2):260–2.
45 Karger B, Nusse R, Bajanowski T. Backspatter on the firearm and hand in experimental close-range gunshots to the head. *Am J Forensic Med Pathol* 2002;23(3):211–3.
46 Verhoff MA, Karger B. Atypical gunshot entrance wound and extensive backspatter. *Int J Legal Med* 2003;117(4):229–31.
47 Yen K, *et al.* Blood-spatter patterns: hands hold clues for the forensic reconstruction of the sequence of events. *Am J Forensic Med Pathol* 2003;24(2):132–40.
48 Padosch SA, *et al.* Two simultaneous suicidal gunshots to the head with robbed police guns. *Forensic Sci Int* 2006; 158(2–3):224–8.

49 Taylor MC, *et al*. The effect of firearm muzzle gases on the backspatter of blood. *Int J Legal Med* 2011;125(5):617–28.

50 Nag NK, Sinha P. A note on assessability of firing distance from gunshot residues. *Forensic Sci Int* 1992;56(1):1–17.

51 Rowe WF. Firearms range. In: Siegel JA (ed). *Encyclopedia of Forensic Sciences*. Oxford: Elsevier, 2000, pp. 949–53.

52 Fojtášek L, *et al*. Distribution of GSR particles in the surroundings of shooting pistol. *Forensic Sci Int* 2003;132(2):99–105.

53 Plattner T, *et al*. Gunshot residue patterns on skin in angled contact and near contact gunshot wounds. *Forensic Sci Int* 2003;138(1–3):68–74.

54 Lepik D, Vasiliev V. Comparison of injuries caused by the pistols Tokarev, Makarov and Glock 19 at firing distances of 10, 15 and 25 cm. *Forensic Sci Int* 2005;151(1):1–10.

55 Lepik D, *et al*. Comparison of injuries caused by the pistols Tokarev, Makarov and Glock 19 at firing distances of 25, 50, 75 and 100 cm. *Forensic Sci Int* 2008;177(1):1–10.

56 Brozek-Mucha Z. Distribution and properties of gunshot residue originating from a Luger 9 mm ammunition in the vicinity of the shooting gun. *Forensic Sci Int* 2009;183(1–3):33–44.

57 Pollak S, Saukko PJ. Gunshot wounds. In: Jamieson A, Moenssens AA (eds). *Wiley Encyclopedia of Forensic Science*. Chichester: John Wiley, 2009, pp. 1380–401.

58 Vinokurov A, *et al*. The influence of a possible contamination of the victim's clothing by gunpowder residue on the estimation of shooting distance. *Forensic Sci Int* 2010;194(1–3):72–6.

59 Singer RL, Davis D, Houck MM. A survey of gunshot residue analysis methods. *J Forensic Sci* 1996;41(2):195–8.

60 Kage S, *et al*. A simple method for detection of gunshot residue particles from hands, hair, face, and clothing using scanning electron microscopy/wavelength dispersive X-ray (SEM/WDX). *J Forensic Sci* 2001;46(4):830–4.

61 Zeichner A. *Firearm discharge residue: analysis of*. In: Jamieson A, Moenssens AA (eds). *Wiley Encyclopedia of Forensic Science*. Chichester: John Wiley, 2009, pp. 1189–2000.

62 Missliwetz J, Denk W, Wieser I. Shots fired with silencers – a report on four cases and experimental testing. *J Forensic Sci* 1991;36(5):1387–94.

63 Pollak S. [Morphology of bullet entrance wounds in palms and plantae (author's transl)]. *Z Rechtsmed* 1980;86(1):41–7.

64 Pollak S. [Macro-and micromorphology of bullet wounds caused by handguns]. *Beitr Gerichtl Med* 1982;40:493–520.

65 Sellier K. [Bullet entry studies of the skin]. Beitr Gerichtl Med 1969;25:265–70.

66 Thali MJ, *et al*. A study of the morphology of gunshot entrance wounds, in connection with their dynamic creation, utilizing the 'skin–skull–brain model'. *Forensic Sci Int* 2002; 125(2–3):190–4.

67 Strassman F. *Lehrbuch der Gerichtlichen Medicin*. Stuttgart: Enke, 1885.

68 Haberda A. *Eduard R. v. Hofmanns Lehrbuch der Gerichtlichen Medizin*, 10th edn. Berlin, Wien: Urban & Schwarzenberg, 1919.

69 Elbel H. Experimentelle untersuchungen über den schmutzsaum bei schußverletzungen. *Dtsch Z Gesamte Gerichtl Med* 1937;28(1):359–65.

70 Meixner K. *Schussverletzungen durch Handfeuerwaffen*. *Arch Kriminol* 1923;75(2):81–108.

71 Elbel H. Schußwinkel und schmauchbild. *Dtsch Z Gesamte Gerichtl Med* 1939;32(3):165–71.

72 Pollak S. [Morphology of injuries by 'humane killer' (livestook stunner) (author's transl)]. *Z Rechtsmed* 1977;80(2):153–65.

73 Pollak S, Reiter C. ['Bolt projectiles' discharged from modified humane killers (author's transl)]. *Z Rechtsmed* 1981;87(4): 279–85.

74 Berg S, Kijewski H. [Alleged and real signs of contact gunshot wounds of entrance holes of skull bones (author's transl)]. *Z Rechtsmed* 1982;88(1–2):103–11.

75 Coe JI. External beveling of entrance wounds by handguns. *Am J Forensic Med Pathol* 1982;3(3):215–9.

76 Madea B, Henssge C, Lockhoven HB. [Priority of multiple gunshot injuries of the skull]. *Z Rechtsmed* 1986;97(3):213–8.

77 Sellier K. [On the work: Madea B, Henssge C, Lockhoven HB (1986) Priorities in multiple gunshot wounds of the skull]. *Z Rechtsmed* 1987;98(4):281–4.

78 Madea B, Staak M. Determination of the sequence of gunshot wounds of the skull. *J Forensic Sci Soc* 1988;28(5–6):321–8.

79 Sellier K. [Is Puppe's law a reliable principle for reconstruction?]. *Arch Kriminol* 1990;186(5–6):163–5.

80 Berryman HE, Smith OC, Symes SA. Diameter of cranial gunshot wounds as a function of bullet caliber. *J Forensic Sci* 1995;40(5):751–4.

81 Bhoopat T. A case of internal beveling with an exit gunshot wound to the skull. *Forensic Sci Int* 1995;71(2):97–101.

82 Karger B. Penetrating gunshots to the head and lack of immediate incapacitation. I. Wound ballistics and mechanisms of incapacitation. *Int J Legal Med* 1995;108(2):53–61.

83 Betz P, *et al*. Fractures at the base of the skull in gunshots to the head. *Forensic Sci Int* 1997;86(3):155–61.

84 Quatrehomme G, Iscan MY. Bevelling in exit gunshot wounds in bones. *Forensic Sci Int* 1997;89(1–2):93–101.

85 Karger B, *et al*. Morphological findings in the brain after experimental gunshots using radiology, pathology and histology. Int J Legal Med 1998;111(6):314–9.

86 Quatrehomme G, Iscan MY. Gunshot wounds to the skull: comparison of entries and exits. *Forensic Sci Int* 1998; 94(1–2):141–6.

87 Quatrehomme G, Iscan MY. Analysis of beveling in gunshot entrance wounds. *Forensic Sci Int* 1998;93(1):45–60.

88 Quatrehomme G, Iscan MY. Characteristics of gunshot wounds in the skull. *J Forensic Sci* 1999;44(3):568–76.

89 de la Grandmaison GL, Brion F, Durigon M. Frequency of bone lesions: an inadequate criterion for gunshot wound diagnosis in skeletal remains. *J Forensic Sci* 2001;46(3):593–5.

90 Karger B, *et al*. Proof of a gunshot wound and its delayed effects 54 years post injury. *Int J Legal Med* 2001;115(3):173–5.

91 Thali MJ, *et al*. The 'skin–skull–brain model': a new instrument for the study of gunshot effects. *Forensic Sci Int* 2002;125(2–3):178–89.

92 Kneubuehl BP, Thali MJ. The evaluation of a synthetic long bone structure as a substitute for human tissue in gunshot experiments. *Forensic Sci Int* 2003;138(1–3):44–9.

93 Oehmichen M, *et al*. Forensic pathological aspects of postmortem imaging of gunshot injury to the head: documentation and biometric data. *Acta Neuropathol* 2003;105(6):570–80.

94 Thali MJ, *et al*. New horizons in forensic radiology: the 60-second digital autopsy full-body examination of a gunshot victim by multislice computed tomography. *Am J Forensic Med Pathol* 2003;24(1):22–7.

95 Thali MJ, *et al*. Image-guided virtual autopsy findings of gunshot victims performed with multi-slice computed tomography and magnetic resonance imaging and subsequent correlation between radiology and autopsy findings. *Forensic Sci Int* 2003;138(1–3):8–16.

96 Gervaise A, *et al*. [Imaging of cranial gunshot traumas]. *J Radiol* 2010;91(11 Pt 1): 1113–20.

97 Smith OC, *et al*. Atypical gunshot exit defects to the cranial vault. *J Forensic Sci* 1993;38(2):339–43.

98 Chattopadhyay S. Accidental low velocity atypical missile injury to the head. *Am J Forensic Med Pathol* 2008;29(4):334–6.

99 Puppe G. Traumatische todesursachen. In: Kutner R (ed). *Gerichtliche Medizin. Zwölf Vorträge*. Jena: Gustav Fischer, 1903, pp. 65–84.

100 Puppe G. *Die gewaltsamen todesursachen*. In: Schmidtmann A (ed). *Handbuch der Gerichtlichen Medizin*. Berlin: Hirschwald, 1907, pp. 90–5.

101 Puppe G. Atlas und grundriß der gerichtlichen medizin. *Lehmann's Medizinische Handatlanten*. Vol. 1. München: J.F. Lehmann's Verlag, 1908.

102 Puppe G. Über priorität der schädelbrüche. *Arztl Sachverst Zt* 1914;20:307–9.

103 Kneubuehl BP. General wound ballistics. In: Kneubuehl BP (ed). *Wound Ballistics Basics and Applications*. Berlin: Springer, 2011, pp. 131.

104 Levy AD, *et al*. Virtual autopsy: preliminary experience in high-velocity gunshot wound victims. *Radiology* 2006;240(2):522–8.

105 von See C, *et al*. Forensic imaging of projectiles using cone-beam computed tomography. *Forensic Sci Int* 2009;190(1–3):38–41.

106 Breitenecker R, Senior W. Shotgun patterns. I. An experimental study on the influence of intermediate targets. *J Forensic Sci* 1967;12(2):193–204.

107 Sellier K. [Wounding capacity of bullets after ricochet from sand or concrete (author's transl)]. *Z Rechtsmed* 1976; 78(2):149–58.

108 Donoghue ER, *et al*. Atypical gunshot wounds of entrance: an empirical study. *J Forensic Sci* 1984;29(2):379–88.

109 Kampmann H, Kijewski H. [Atypical bullet entry injuries. A case report and experimental contribution]. *Z Rechtsmed* 1986;97(3):185–93.

110 Hawley DA, Pless JE, Palmer H. Tumbling abrasions. Injuries from ricocheting bullets. *Am J Forensic Med Pathol* 1987;8(3):229–32.

111 Sellier K. [Double ricochet marks]. *Z Rechtsmed* 1987;98(4):241–4.

112 Grey TC. The incredible bouncing bullet: projectile exit through the entrance wound. *J Forensic Sci* 1993;38(5):1222–6.

113 Schyma C, Placidi P. Traces of ricocheted action safety bullets. *Am J Forensic Med Pathol* 1997;18(1):15–20.

114 Karger B, Joosten U. A case of 'boomerang' bullet ricochet. *Int J Legal Med* 2001;115(2):70–1.

115 Haag LC. Wound production by ricocheted and destabilized bullets. *Am J Forensic Med Pathol* 2007;28(1):4–12.

116 Grosse Perdekamp M, *et al*. Experimental simulation of reentry shots using a skin-gelatine composite model. *Int J Legal Med* 2009;123(5):419–25.

117 Dixon DS. Determination of direction of fire from graze gunshot wounds of internal organs. *J Forensic Sci* 1984;29(1):331–5.

118 Leppaniemi A, Cederberg A, Tikka S. Truncal gunshot wounds in Finland, 1985 to 1989. *J Trauma* 1996;40(3 Suppl):S217–22.

119 Stone IC, DiMaio VJ, Petty CS. Gunshot wounds: visual and analytical procedures. J *Forensic Sci* 1978;23(2):361–7.

120 Challener RC, Rosenberg SB. An unusual shotgun injury pattern produced by an intermediate target. *Am J Forensic Med Pathol* 1986;7(3):249–51.

121 Thornton JI. Close proximity gunshot residues. *J Forensic Sci* 1986;31(2):756–7.

122 Betz P. *et al*. Frequency of blood spatters on the shooting hand and of conjunctival petechiae following suicidal gunshots wounds to the head. *Forensic Sci Int* 1995;76(1):47–53.

123 Nadjem H, *et al*. [Marks on clothing and skin in absolutely and relatively close distance gunshots with fright weapons]. *Arch Kriminol* 1996;197(5–6):175–84.

124 Missliwetz J, *et al*. [Pump-gun as a weapon. Type of injuries, prohibition of weapons]. *Arch Kriminol* 1999;203(1–2):10–18.

125 Grosse Perdekamp M, Braunwarth R, Pollak S. Patterned imprint mark due to the folded shoulder stock: a possible finding in contact shots from submachine guns. *Forensic Sci Int* 2008;178(1):e1–5.

126 Grosse Perdekamp M, *et al*. Secondary skull fractures in head wounds inflicted by captive bolt guns: autopsy findings and experimental simulation. *Int J Legal Med* 2010;124(6):605–12.

127 Grosse Perdekamp M, *et al*. Two-gun suicide by simultaneous shots to the head: interdisciplinary reconstruction on the basis of scene investigation, autopsy findings, GSR analysis and examination of firearms, bullets and cartridge cases. *Int J Legal Med* 2011;125(4):479–85.

128 Pollak S. [Statistics and phenomenology of combined suicides and other multiple suicidal injuries in the urban area (II), with 2 case reports]. *Arch Kriminol* 1978;161(3–4):68–81.

129 Barnes FC, Helson RA. A death from an air gun. *J Forensic Sci* 1976;21(3):653–8.

130 Kijewski H, Berg S, Sprung R. [Suicide with air gun. Research in would ballistics of air-driven weapons (author's transl)]. *Z Rechtsmed* 1980;84(3):209–20.

131 DiMaio VJ, *et al*. Minimal velocities necessary for perforation of skin by air gun pellets and bullets. *J Forensic Sci* 1982;27(4):894–8.

132 Green GS, Good R. Homicide by use of a pellet gun. *Am J Forensic Med Pathol* 1982;3(4):361–5.

133 Warniment DC. Discussion of 'Minimal velocities necessary for perforation of skin by air gun pellets and bullets'. *J Forensic Sci* 1983;28(3):551.

134 Mattoo BN. Discussion of 'Minimal velocities necessary for perforation of skin by air gun pellets and bullets'. *J Forensic Sci* 1984;29(3):700–3.

135 Jacob B, *et al*. Suicides by starter's pistols and air guns. *Am J Forensic Med Pathol* 1990;11(4):285–90.

136 Ng'walali PM, *et al*. Unusual homicide by air gun with pellet embolisation. *Forensic Sci Int* 2001;124(1):17–21.

137 Aslan S, *et al*. Air guns: toys or weapons? *Am J Forensic Med Pathol* 2006;27(3):260–2.

138 Clarot F, Proust B, Vaz E. Air guns: weapons or toys? *Am J Forensic Med Pathol* 2008;29(4):382–4.

139 Ryder RD. *Animal Revolution: Changing Attitudes Toward Speciesism*, 2nd edn. Oxford: Berg, 2000.

140 Nadjem H, Pollak S. [Wound entry findings of animal anesthesia guns without smoke outlets]. *Arch Kriminol* 1999; 203(3–4):91–102.

141 Pollak S, Saukko PJ. Firearms; humane killing tools. In: Siegel JA (ed). *Encyclopedia of Forensic Sciences*. Oxford: Elsevier, 2000, pp. 939–44.

142 Betz P, *et al*. Homicide with a captive bolt pistol. *Am J Forensic Med Pathol* 1993;14(1):54–7.

143 Bohnert M, *et al*. Diagnosis of a captive-bolt injury in a skull extremely destroyed by fire. *Forensic Sci Int* 2002;127(3):192–7.

144 Simic M, *et al*. The characteristics of head wounds inflicted by 'humane killer' (captive-bolt gun) – a 15-year study. *J Forensic Sci* 2007;52(5):1182–5.

145 Frank M, *et al*. Ballistic parameters of cal. 9 mm × 17 mm industrial blank cartridges (cattle cartridges). *Forensic Sci Int* 2009;192(1–3):83–7.

146 Viel G, *et al*. Planned complex suicide by penetrating captive-bolt gunshot and hanging: case study and review of the literature. *Forensic Sci Int* 2009;187(1–3):e7–11.

147 Forbes J, Conolly J (eds). Dr. Sommer on the Signs of Death. *Br Foreign Med Rev*, London: Sherwood Gilbert and Piper, Vol. IV, 1837.

148 Rothschild MA, Maxeiner H. Unusual findings in a case of suicide with a gas weapon. *Int J Legal Med* 1994;106(5):274–6.

149 Rothschild MA, Liesenfeld O. Is the exploding powder gas of the propellant from blank cartridges sterile? *Forensic Sci Int* 1996;83(1):1–13.

150 Rothschild MA, *et al*. Fatal wounds to the thorax caused by gunshots from blank cartridges. *Int J Legal Med* 1998; 111(2):78–81.

151 Rothschild MA, Vendura K. Fatal neck injuries caused by blank cartridges. *Forensic Sci Int* 1999;101(2):151–9.

152 Giese A, *et al*. Head injury by gunshots from blank cartridges. *Surg Neurol* 2002;57(4):268–77.

153 Padosch SA, Schmidt PH, Madea B. Planned complex suicide by self-poisoning and a manipulated blank revolver: remarkable findings due to multiple gunshot wounds and self-made wooden projectiles. *J Forensic Sci* 2003;48(6):1371–8.

154 Ogunc GI, *et al*. Modified blank ammunition injuries. *Forensic Sci Int* 2009;193(1–3):112–17.

155 Demirci S, Dogan KH, Koc S. Fatal injury by an unmodified blank pistol: a case report and review of the literature. *J Forensic Leg Med* 2011;18(6):237–41.

156 Marshall RA. Stud guns still lethal. *N Engl J Med* 1963;269:641.

157 Weedn VW, Mittleman RE. Stud guns revisited: report of a suicide and literature review. *J Forensic Sci* 1984;29(2):670–8.

158 Lignitz E, Koops E, Puschel K. [Death caused by projectile guns – a retrospective analysis of 34 cases in Berlin and Hamburg]. *Arch Kriminol* 1988;182(3–4):83–93.

159 Hagemeier L, Schyma C, Madea B. Extended suicide using an atypical stud gun. *Forensic Sci Int* 2009;189(1–3):e9–12.

160 Millar R, *et al*. Injuries caused by rubber bullets: a report on 90 patients. *Br J Surg* 1975;62(6):480–6.

161 Sheridan SM, Whitlock RI. Plastic baton round injuries. *Br J Oral Surg* 1983;21(4):259–67.

162 Rocke L. Injuries caused by plastic bullets compared with those caused by rubber bullets. *Lancet* 1983;1(8330):919–20.

163 Shaw J. Pulmonary contusion in children due to rubber bullet injuries. *Br Med J* 1972;4(5843):764–6.

164 Balouris CA. Rubber and plastic bullet eye injuries in Palestine. *Lancet* 1990;335(8686):415.

165 Hiss J, Kahana T. The fatalities of the Intifada (uprising): the first five years. *J Forensic Sci Soc* 1994;34(4):225–9.

166 Hiss J, Hellman FN, Kahana T. Rubber and plastic ammunition lethal injuries: the Israeli experience. *Med Sci Law* 1997;37(2):139–44.

167 Chute DJ, Smialek JE. Injury patterns in a plastic (AR-1) baton fatality. *Am J Forensic Med Pathol* 1998;19(3):226–9.

168 Kobayashi M, Mellen PF. Rubber bullet injury: case report with autopsy observation and literature review. *Am J Forensic Med Pathol* 2009;30(3):262–7.

169 Zalewski T. Experimentelle untersuchungen über die resistenzfähigkeit des trommelfells. *Zeitschrift für Ohrenheilkunde* 1906;52:109–28.

170 Hirsch FG. Effects of overpressure on the ear – a review. *Ann N Y Acad Sci* 1968;152(1):147–62.

171 Stapczynski JS. Blast injuries. *Ann Emerg Med* 1982;11(12): 687–94.

172 Peters P. Primary blast injury: an intact tympanic membrane does not indicate the lack of a pulmonary blast injury. *Mil Med* 2011;176(1):110–14.

173 Saternus KS. [Possibilities for using rhinoscopy and otoscopy in forensic autopsy]. *Beitr Gerichtl Med* 1988;46:497–502.

174 Amberg R, Strutz J. [Differential diagnosis of hematotympanum in forensic autopsy]. *Laryngorhinootologie* 1995;74(5):312–6.

175 Owers C, Morgan JL, Garner JP. Abdominal trauma in primary blast injury. *Br J Surg* 2011;98(2):168–79.

176 Pollak S, Saukko P. *Atlas of Forensic Medicine*. Amsterdam: Elsevier Science, 2003.

This page intentionally left blank

CHAPTER 9

Transportation Injuries

- Introduction
- The dynamics of vehicular injury
- Pattern of injury of vehicle occupants
- The effect of seatbelts
- The vulnerability of children in vehicles
- Injuries to motorcyclists
- Injuries to pedal cyclists
- Injuries to pedestrians
- Cause of death in traffic accidents
- Suicide and homicide by motor vehicle
- Railway injuries
- References

Introduction

Injuries and fatalities occur in all forms of transportation but numerically road traffic accidents account for the great majority worldwide, causing more than 3000 deaths each day and killing more than a million people annually and injuring some 20–50 million. If the current trends continue, road traffic injuries are predicted to come the fifth leading cause of death by 2030. Approximately 90 per cent of these deaths occur in low- and middle-income countries, where the road traffic fatality rates (21.5 and 19.5 per 100,000 population, respectively) are higher than in high-income countries (10.3 per 100,000 population). In 2010 the United Nations General Assembly adopted resolution 64/255 which proclaimed the period 2011–2020 as the Decade of Action for Road Safety. The goal of the Decade is to stabilize and then reduce the forecast level of road traffic fatalities around the world by increasing activities conducted at national, regional and global levels. The Global status report on road safety by the the World Health Organization (WHO) published in 2013, is the second broad assessment of the status of road safety in 182 countries, building on the first Global status report on road safety published in 2009, the latter of which used data drawn from a standardized survey conducted in 2008. Large regional disparities exist in the death rates of road traffic accidents, the risk being highest in the African region (24.2 per 100,000 population), and the lowest in Europe (10.3 per 100,000). Young adults (between 15 and 44 years) account for almost 60 per cent of all traffic deaths, and half of the world's road traffic deaths occur among pedestrians (22 per cent), cyclists (5 per cent) and motorcyclists (23 per cent). Proportion of deaths among different road user types show, however, considerable inter- and intraregional variation.[1,2]

The pattern of injury, fatal and otherwise, varies considerably depending upon whether the victim is a vehicle occupant, a motorcyclist, a pedal cyclist or a pedestrian.

The dynamics of vehicular injury

A number of elementary physical facts help to explain the complex pattern of traffic injuries, especially those sustained by the occupants of a vehicle.

- Tissue injury is caused by a change of rate of movement. A constant speed, however rapid, has no effect whatsoever as is evident from space travel or the rotation of the earth. It is the change of rate that is traumatic – that is, acceleration or deceleration. Acceleration is defined as the rate of change in velocity of a mass and is frequently stated in units of metres (feet) per second per second or m/s^2 (ft/s^2). It is related to force by the familiar equation, $F = ma$, where F = force, m = mass, and a = acceleration.
- Change of rate is conveniently measured in 'gravities' or 'G-forces', which is the ratio of a particular acceleration (a) to the acceleration of gravity at sea level ($g = 9.8\ m/s^2$ or $32.2\ ft/s^2$) or $G = a/g$. The amount that a human body can tolerate depends greatly on the duration and direction in which the

force acts, surviving better short-term exposure, and if the G-forces act at right angles to the long axis of the body. The frontal bone may resist 800 G without fracture and the mandible 400 G, as can the thoracic cage.

- During acceleration or deceleration the tissue damage produced will depend upon the force applied per unit area, just as a sharp knife penetrates more easily than a blunt one used with the same force. If a car driver is brought to rest from 80 km/h by striking 10 cm^2 of his head on the windscreen frame, the damage will be vastly more severe than if the same decelerative force was spread over 500 cm^2 of a safety belt.
- Between 60 and 80 per cent of vehicular crashes (either into a fixed structure or into another vehicle) are frontal, causing violent deceleration. Another 6 per cent are rear impacts, which accelerate the vehicle and its occupants. Of the remainder, about half are sideswipes and the rest 'roll-overs'.
- In the common frontal impact, there is never instant arrest of the vehicle, even when it runs into a massive, immovable structure. The vehicle itself deforms from the front so that there is always a deceleration distance and time, albeit small. In fact, much of the manufacturers' design research now goes into making deliberate provision for the crumpling or 'concertinaing' of the front and rear of the car, leaving a central rigid cell that comprises the passenger compartment. The object is to extend the stopping distance and time, so that the G value acting on the occupants is reduced (Fig. 9.4).
- The value of the G forces can be calculated from the formula: $G = C\,(V^2)/D$, where V is velocity in km/h, D is the stopping distance in metres after impact, and C is a constant 0.0039. (If V is in mph and D is in feet, C becomes 0.034.) For example, if a car travelling at 80 km/h runs into a stone wall that it penetrates for 25 cm, plus 50 cm crumpling of the front of the car, the deceleration would amount to about 33 G. If an occupant was rigidly belted into his seat (a practical impossibility), he would also suffer the same deceleration, which would be survivable. If, however, he was unrestrained, he would continue forwards momentarily at 80 km/h and suffer massive G forces, the magnitude of which would depend on his deformation stopping distance (a few centimetres of tissue compression) when he struck the internal car structures in front of him.

Pattern of injury of vehicle occupants

The type of vehicle (other than motorcycles) in theory makes little difference to the mechanism of injury, but most statistical surveys divide them into cars and light vans under 1.5 tonnes, on the one hand and heavier vehicles, such as trucks and buses, on the other, though the latter have different features more akin to passenger aircraft.

Heavy goods vehicles naturally suffer less than cars and light vans in crashes because of their far greater mass and strength, and also due to their height above the ground. Structural damage from impact with other smaller vehicles is less and often sustained below the level of the driver. Given smaller deceleration forces, however, the cab occupants are vulnerable to the same injury patterns.

Light vans are virtually identical to cars with respect to the front-seat occupants. In fact they may be more at risk, as modern vans tend to be flat-fronted and thus have little or no 'crumple' potential to increase the stopping time. Concentrating on cars, the most common vehicular casualty, the pattern of injury varies according to the position of the occupant.

The driver

Numerous investigations have been made by road research organizations and car manufacturers using dummies and actual corpses, together with sophisticated recording equipment and high-speed cinematography or video footage. These have established a detailed picture of the sequence of events in automobile crashes. When the most common event – frontal impact – occurs, the unrestrained driver first slides forwards so that his legs strike the fascia/parcel-shelf area, and his abdomen or lower chest contacts the lower edge of the steering wheel (Fig. 9.1). The body then flexes across the steering wheel and begins to rise. The heavy head goes forwards, and there is flexion of the cervical and thoracic spines. The upward and forward component causes the head to strike the windscreen, the upper windscreen rim or the side pillar. The windscreen is often perforated by the head or face, and the whole body may be ejected through the broken glass, to land on the bonnet or even on the roadway ahead.

Another factor causing injury is the intrusion of structural parts into the passenger compartment. Though modern cars are designed to maintain a rigid central passenger compartment, if the impact is gross, the engine or front-wheel assembly may be forced



Figure 9.1 Major points of injury to an unrestrained driver of a vehicle in deceleration impact.

back into the seating area, intruding upon the driver. Similarly, the roof or front corner pillar (the so-called 'A'-frame) may cave in on top of the driver.

One effect of column, engine, or gearbox intrusion may be to force the floor up and backwards against the driver's feet and legs. The control pedals also take part in intrusion, and, in the usual desperate braking and declutching, the reflex pressure of feet on rising pedals and floor may cause transmitted force up the legs and into the pelvic girdle. The steering column was formerly a more dangerous item for intrusion, being forced back to 'stab' or crush the driver's chest or abdomen. Modern design has reduced this danger by making the column telescopic, hinged or otherwise collapsible, but injuries still occur – sometimes from the wheel itself breaking and penetrating the chest. Additionally, the door may burst open and the driver, if unrestrained, ejected sideways onto the road, especially in a crash that has a roll-over component.

In a rear impact, the driver is violently accelerated and, if no rigid head restraint is fitted to the seat, severe hyperextension of the neck occurs, often followed by the sequence of deceleration events when the car is cannoned into the vehicle or other obstruction in front, causing the popular, if inaccurate name of 'whiplash'.

In side impacts, the injuries depend upon the amount of intrusion of the driver's door and side panels. Restraint devices can offer no protection, though modern vehicles usually have strengthened side-impact bars built within the doors.

This range of traumatic events can produce the following lesions in drivers not wearing seatbelts or protected by airbags:

- Impact against the fascia can cause abrasions, lacerations and fractures of the legs around knee or upper shin level.
- Pressure of feet on the floor, especially when it is intruded by the engine, can cause fractures anywhere from foot to femur (Fig. 9.5). The leg can also be injured by violent contact with the fascia or dashboard and the hip joint may be dislocated posteriorly. In Mant's series of 100 driver fatalities there were still 22 pelvic injuries and 31 of the lower limb, whereas now they seem to be getting rarer as pelvic and hip fractures were present in only 7 per cent of frontal impacts of passenger cars analyzed by Kramer.[3–5]
- Impact of the abdomen and chest against the steering assembly, the side door, the arm rest (depending on the direction of the impact) may cause severe internal injuries, usually rupture of the liver, less often, the spleen, the kidneys or the intestines. There may be bruising of the skin surface, but this is often absent even in the presence of severe internal injuries. Laceration of the skin is rare unless the steering wheel snaps and penetrates the trunk. Other steering-wheel lesions include bruising of the lungs, fractured ribs and sternum, cardiac contusion and haemothorax or pneumothorax or both. Almost 70 per cent of Mant's series had broken ribs.
- Upper limb injuries are less common but may occur from transmitted force through gripping the steering wheel or from impact against the windscreen, pillars, intrusive roof, bonnet or ground when held up in a reflex protective position. Only 19 per cent of Mant's series had arm injuries.
- The most obvious injuries are often those to the face and head as a result of projection against and ejection through, the windscreen. The unrestrained driver rises and flexes forwards so that his forehead and skull are likely to contact the upper rim of the windscreen, leading to lacerations (Fig. 9.6). First windscreens were made of ordinary window glass but were replaced, because of their potential dangerousness in the event of a crash, by ones made of toughened glass, which shattered into many less harmful fragments when the windscreen broke. Modern windscreens are generally made of laminated safety glass and glued into the window frame and contribute to the vehicle's rigidity. They usually stay in one piece even if broken, and prevent injury from sharp glass fragments.[6,7]
- The impact against the windscreen rim or corner pillar – or after ejection – can cause any type or degree of head injury, including scalp laceration, fractured skull, intracranial haemorrhage or brain damage (Figs 9.2, 9.3). In Mant's series there were



Figure 9.2 Facial lacerations from a shattered windscreen in an unrestrained driver. The toughened glass breaks into small fragments, which produce the characteristic 'sparrow-foot' marks. The laceration on the forehead was made by the windscreen rim.



Figure 9.3 Ring fracture around the foramen magnum caused by an impact on the crown of the head in a car driver, who lost the control of his vehicle and crashed into a tree.

42 skull fractures in 100 drivers. This was less than in the front-seat passengers, a figure at variance with Eckert's series of 300 in the USA, where drivers suffered twice as many head injuries as the passenger, though it is not stated how many accidents were to vehicles occupied only by the driver.[8]

- Hyperflexion of the cervical spine when the head swings can cause fractures or dislocation. There is often a double component in that the hyperflexion of deceleration is followed by a rebound hyperextension when the head strikes an obstruction in front. Rear impacts also cause the double 'whiplash' effect, as already mentioned.
- One injury that is frequently overlooked at autopsy is the atlanto-occipital dislocation, which Mant found in one-third of his series. Other fractures can occur anywhere in the cervical spine, often at about C5–6. Seatbelt restraint cannot prevent cervical spine damage, though a rigid head restraint can reduce injuries resulting from hyperextension. The thoracic spine is less often damaged, but in unrestrained drivers the same 'whiplash' effect can fracture or dislocate the upper dorsal spine, often around T5–6–7.
- A more common thoracic injury associated with deceleration is the ruptured aorta (Fig. 9.7). It may be associated with a severe whiplash effect on the thoracic spine, as the aorta is tethered to the anterior surface of the vertebrae where the distal arch joins the straight descending segment. Probably the most common reason for aortic rupture, however, is the 'pendulum' effect of the heart within the relatively pliable thoracic contents. When the thorax is violently decelerated, the heavy cardiac mass attempts to keep moving ahead and may literally pull itself off its basal mountings, the most rigid part of which is the aorta. Separation takes place at the point where the aorta is attached to the spine at the termination of the arch (Fig. 9.8).



Figure 9.4 When vehicle structures impinge on the occupants even belt restraints offer little protection. The engine, front suspension, roof and 'A' frame are frequent intruders.



Figure 9.5 Bruising, laceration and bilateral leg fractures of a car driver in a frontal impact.



Figure 9.6 Facial injuries in a car driver unrestrained by a seatbelt. Following a deceleration impact his face struck the windscreen, causing the typical small cuts from broken safety glass and lacerations of the temple from striking the windscreen rim or 'A' frame.



Figure 9.7 Mixed injuries in a restrained car driver from a head-on collision. Death was caused by ruptured aorta.



Figure 9.8 Ruptured aorta in which the car occupant, unrestrained by seatbelt, suffered severe deceleration. Aorta has torn in the usual place, the distal arch where the curve of the vessel meets the thoracic spine.

- The appearance of the aortic rupture is often of a clean-cut circular break, almost as sharp as if it had been transected with a scalpel. Sometimes there are additional transverse intimal tears adjacent to the main rupture, the so-called 'ladder tears', as they can resemble the rungs of a ladder. These may be present when no actual rupture has occurred and may be found as an incidental finding at autopsy. Sometimes they are deep enough to allow a local dissection of blood to seep into the intima, when death has not been virtually instantaneous. Rarely, a major dissection may lead to delayed death some hours or even days later. Ruptured aorta is a common lesion in traffic accidents–in a two-car crash, the author (BK) has seen three transected aortas among the four fatalities (Fig. 9.8).

- The frequency of such tears is common enough for a warning always to be offered to the autopsy prosector not to use undue force on the neck and thoracic structures when removing the organ pluck from the body. Rough handling during this stage can produce artefactual ladder tears in the aorta.
- Other chest injuries can be caused by impact with the steering wheel, ejection through the windscreen or impact with the road. There may be bruising or laceration on the chest from the steering wheel, though padding, collapsible columns, less fragile wheels, airbags and seatbelts have reduced the incidence of this formerly common lesion. Beneath the skin, sternal and rib fractures are common, though fatal visceral injuries can occur without rib fractures in young people because their ribs are more pliable.
- The heart may be damaged even in the absence of external marks or thoracic cage fractures. Bruising of the epicardium and underlying myocardium is not uncommon and the posterior surface may be damaged from impact against the spine. In high-speed impacts, the heart may be completely avulsed from its base and be found lying loose in the chest. Less severe degrees of damage may lacerate the ventricles or atria, and cause gross haemorrhage. Coronary artery thrombosis has been described following contusion over a coronary artery. Penetrating injuries from sternum, ribs or external objects may lacerate the heart directly (Figs 9.9, 9.10). Subendocardial haemorrhages on the left side of the interventricular septum and opposing papillary muscles are not a sign of impact, but an index of catastrophic hypotension. They are also seen in head injuries; they can occur within the space of a few beats, as the author (BK) has seen these prominent lesions in an avulsed heart after a military aircraft crash.



Figure 9.9 Penetration of the wrist and chest by a wooden component of a bus seat. The victim drove his car at speed into a bus and part of the resulting debris penetrated his left ventricle.



Figure 9.10 A car collided with a mobile home towed by an oncoming car. The caravan broke into pieces and a wooden component impaled the head of a car passenger.

- The lungs are frequently injured, either from stabbing by fractured ribs penetrating the pleura or from blunt impact. The latter often leads to a line of bruising down the posterior part of the lung where it lies in the paravertebral gutter. There may be air bullae or blood blisters under the pleura overlying the bruised areas and a pneumothorax or haemothorax may result. The interior of the lung may be pulped even in the presence of an intact visceral pleura, from transmitted force or massive variations in intrathoracic pressure during the impact. The lung often shows areas of bleeding under the pleura, which may be from direct contusion, from aspiration of blood from other damaged areas of lung or from blood sucked down the air passages from injuries in the nose or mouth.
- The major abdominal injury is a ruptured liver, which may be damaged in any part. A common lesion is central tearing of the upper surface, which may extend deeply and even transect the organ. Less serious damage is often seen in the form of shallow, sometimes multiple, parallel tears on the upper surface of the right lobe. Subcapsular tears can occur with the formation of a subcapsular haematoma, which can rupture later (Figs 9.11, 9.12). The spleen also shows shallow tears in some accidents, often



Figure 9.11 Large subcapsular haemorrhage of the liver in a driver who struck the rim of the steering wheel during severe deceleration. Such subcapsular lesions can remain intact for hours or even days, then rupture into the abdominal cavity.



Figure 9.12 Anterior tear through the full thickness of the liver; there is also a haemorrhage around the suspensory ligament. The victim was a car driver who was impacted against the steering wheel in a frontal crash.

around the hilum; in rare cases, it may be avulsed from the pedicle. The mesentery and omentum often show bruising and, rarely, there is laceration and fenestration sufficient to cause a lethal haemorrhage.

- Ejection injuries are common, and lethal in both driver and passengers. This is particularly likely to happen in roll-over accidents. Much research has been pursued by manufacturers to develop antiburst door locks, which have improved safety. Where there has been considerable distortion of the vehicle frame, however, nothing can prevent the doors from opening or even being torn off. It has been shown in an early detailed study comprising 3261 passenger cars and 7337 vehicle occupants at Cornell in the 1950s that, if a victim was ejected, there was a fivefold greater chance of dying than if he was retained in the vehicle.[9,10] Green *et al.* analysed vehicle and injury data from 919 accidents in the UK for frequency, cause and consequences of occupant ejection, resulting in between 3.6 and 4.5 times higher risk of severe injuries and fatalities in ejected occupants.[11]
- Almost any kind of injury, usually multiple, may be sustained after ejection, either from contact with the road surface or (in a significant proportion) from being struck by other vehicles, especially on motorways.

The front-seat passenger

In Western countries, far more drivers than passengers are killed or injured, but this reflects the fact that a high proportion of cars contain only a driver – one-third in Mant's series. In countries with a lower ratio of vehicles to population the converse is true and indeed many accidents are due to gross overcrowding of passenger vehicles. The pattern of injuries is similar to that of the driver, but this position in the car is even more dangerous, as indicated by the title of a safety film made by the French Michelin Tyre Company – *La place du mort*.

Though there is no steering wheel to impact into the chest, its absence also denies the slight protection offered to the driver in reducing the collision with the windscreen, perhaps by giving him something to brace against. Another factor may be that the driver gives his attention constantly to the road and so has momentary warning of an impending crash, compared with the passenger who may be oblivious of imminent disaster and fail to 'brace up' ready for the impact. This may explain the greater number of skull fractures and brain damage in unrestrained passengers in Mant's series, the percentages being 55 per cent and 42 per cent, compared with 64 per cent and 53 per cent, respectively. However, these figures were compiled before seatbelts and airbags became commonplace or even mandatory.

In a series of 55 fatally injured front-seat occupants wearing belts head/neck trauma was over twice as frequent a cause of death than chest trauma. Abdominal injuries occurred more frequently in drivers than passangers. The most serious injury was caused by intruding truck in 32 per cent, fascia in 27 per cent and steering assembly in 22 per cent.[12]

Thomas and Bradford analysed data on 1514 restrained front-seat occupants in frontal crashes of which 105 died and 80 of these sustained a fatal head injury. The most common cause was contact with steering wheel in 32 per cent, exterior objects in 27 per cent and pillars and roof in 21 per cent.[7]

Rear-seat occupants

Before the more widespread use of front seatbelts – now mandatory in many countries – it was thought that the rear-seat position was fairly safe, as indeed it is compared with the front seats.

When the widespread use of seatbelts dramatically reduced the deaths and serious injuries amongst front-seat occupants, the dangers of the back seats became much more obvious. Campaigns and legislation similar to the previous crusade were waged on behalf of the rear-seat occupants, and the use of these has now become mandatory in Britain and many other countries.

Bilston *et al.* performed a matched-cohort analysis of belted front and rear seat occupants in newer and older model vehicles using data on restrained occupants from the USA National Automotive Sampling System to evaluate the relative risk of AIS3+ injury in front- and rear-seat occupants. They found that relative risk of AIS3+ injury for front and rear occupants was influenced by age and model year. For those aged 16–50 years in older vehicles, the front and rear seat offered similar levels of protection. However, in newer model vehicles (1997–2007), the rear seat carried a higher risk of injury. For adults over 50 years, the rear seat carried a higher risk in both older and newer vehicles, and for 9–15 year olds, the rear seat carried a lower risk, suggesting that safety for front-seat occupants has improved over the last decade, to the point where, for occupants over 15 years of age, the front seat is safer than the rear seat. While the benefit of rear seating for children aged 9–15 years has decreased over time, they are still at lower risk in the rear seat.[13]

During violent deceleration, unrestrained occupants in the rear are projected forwards and strike the back of the front seats, including head-rests where fitted. They may be thrown over the seats, striking and adding further injuries to the front-seat occupants and may even be ejected through the windscreen, which is broken by them or by the people in front. According to a study by Ichikawa *et al.* the risk of death of belted front-seat occupants with unbelted rear-seat passengers was raised nearly fivefold.[14]

In roll-over accidents, they share in the general trauma of being churned inside the passenger compartment, when multiple injuries can occur from contact with fitments, such as mirrors, door handles and window winders. Design changes have reduced these hazards by making handles smoother or countersunk and mirrors that easily snap off their mountings. Ejection is another common cause of death and serious injury in rear-seat occupants, a wide range of head, chest and limb injuries being seen.

The effect of seatbelts

The majority of countries (69 per cent of the world's population) now have comprehensive legislation making the wearing of seatbelts mandatory for all vehicle occupants.[2] Where no laws exist, persuasion seems to have little effect, in spite of the fact that it is uncontested that their use reduces the risk of fatal injury by 40–50 per cent for drivers and front-seat occupants, and by 25–75 per cent for rear-seat occupants.[2,15,16]

Seatbelts are now almost all of the lap-strap and shoulder diagonal type, the so-called 'three-point attachment belt'. The simple lap-strap is now fitted only in aircraft, where it is really only of token effectiveness. Most car belts are now of the 'inertia-reel' type, which allow slow movement but jam at a sudden tug. The advantage, apart from the comfort, is that they automatically tighten up around the body, as a slack belt is not only less effective but can actually constitute a danger. More complex restraints, such as double shoulder harness and crotch strap, are fitted only in light aircraft, gliders and racing cars. Though far more effective, their use would be socially unacceptable in ordinary road vehicles, as would head-band restraints, which are almost the only way of preventing hyperflexion damage to the cervical spine.

The various forms of strap restraints act by (Fig. 9.13):

- Holding the occupant back against the seat, so that forward projection against the steering wheel, windscreen and corner 'A' frame is prevented.



Figure 9.13 Types of seatbelt restraint: (a) simple lap-strap (dangerous to aorta); (b) diagonal only (can slip underneath); (c) diagonal plus lap-strap (usual car type); and (d) shoulder harness (used in aircraft and racing cars).

The head, though still subject to hyperflexion, is prevented from smashing through the glass and the body cannot be projected through the screen onto the bonnet or roadway. The belt cannot cope with backward intrusion of the engine, floor, roof or corner pillar if those structures reach the occupant sitting in the original seat position. The effectiveness of the belt is also dependent on the secure fixation of the seat to the vehicle floor.

- The belt restrains the occupants within the vehicle in the event of a door bursting, as ejection greatly increases the risk of death or serious injury. A belt is relatively ineffective in a side impact, except in that it reduces injuries from ejection. It has been reported, however, that head injuries were fewer in restrained victims of side-swipes, though the reason is not clear.

It has been claimed (mainly in insurance disputes) that seatbelts can worsen this sort of injury by holding the occupant in more dangerous proximity to the intruding impact. There would seem few occasions, however, in which even the unrestrained occupant could voluntarily escape from any significant degree of sudden lateral intrusion from a speeding vehicle.

- Extending the deceleration time and distance by substantial stretching of the belt fabric, which may lengthen by many centimetres during a violent arrest. To be effective the belt must be held tightly against the body to get the maximum restraint, either by adjusting the buckle or using an inertia reel. The belt should never be used again, as it cannot stretch further and may break on the next application of tension.
- Spreading the area of application of deceleration forces. As stated earlier, the body has to absorb whatever G forces are applied to it, as calculated by the $G = C(V^2)/D$ equation. If these are absorbed by a focal impact covering a few square centimetres over the skull, fatal injury may well ensue. The same deceleration diffused against the thorax and abdomen by 500 cm^2 of belt may leave no injury or merely surface bruising.

Seatbelt injuries

There is no doubt that seatbelts can themselves cause injury, occasionally of considerable severity. This was one of the arguments of the vociferous antiseatbelt lobby that opposed legislation in several countries, but it is largely illogical, because an impact that causes seatbelt injuries would almost invariably have caused even worse injuries or death if no seatbelt had been worn.

Another invalid criticism of restraints was that they impede escape from a burning vehicle. Fires involving passenger car crashes are, however, quite rare. A report by Bako *et al*. from Canada showed that, of 1297 vehicle fatalities, only 24 were from burns, a mere three in passenger cars.[17]

Incorrectly adjusted or positioned straps such as a twisted belt, which reduces the area of contact, can increase the danger of injury. Loose straps allow the body to move relative to the belt before sudden restraint occurs, decreasing the distance between the passenger and facing structures.

Where the person is too small for the harness, such as a child or a small female, the body may slide from under the strap – the so-called ‘submarining’ – or it may act as a garrotte around the neck. Some females find that the diagonal strap compresses the breast even in normal use, so that the greatly increased tension during deceleration is likely to injure the gland.



Figure 9.14 Typical band-shaped subcutaneous haemorrhage due to diagonal seatbelt injury.

Pregnant females also have problems with belts but, although uterine and fetal injuries have been recorded in accidents, the incidence is relatively low and without the belt the consequences would have been as bad or probably worse.[18–20]

Injuries from seatbelts can vary from the trivial to the fatal. Bruising is the most common and may be seen either under the diagonal or the transverse component of the three-point belt (Fig. 9.14). It is more common with the single aircraft-type lap-strap because of the smaller area of pressure. Bruising may occur in the abdominal or chest wall, but the dangerous lesions are visceral. The abdominal contents suffer most, especially from single lap-straps. Rupture of the mesentery, or the small or large intestine, usually occurs from acute flexion over a lap-strap.[21–24] The full bladder can be ruptured as can the caecum. The abdominal aorta can be crushed and the lumbar spine suffer a compression fracture or be dislocated through a disc in the midlumbar region.[25] The posterior arch, pedicles or transverse processes may also be damaged.

The diagonal strap usually prevents serious abdominal injury as it prevents hyperflexion, but it may contribute to thoracic injury. Bruising of the skin and underlying muscles and fractures may accompany a broken clavicle or sternum where the belt crosses them.

Airbags

In recent years, the use of airbags has spread from only the most expensive vehicles to many standard production cars. The device consists of a large fabric bag, which is normally folded into the steering-wheel hub in the case of the driver position and into the fascia in front of the front-seat passenger.

A sensitive deceleration device triggers the ignition of sodium azide, a solid and highly toxic explosive propellant, which is converted in milliseconds to nitrogen gas. The deploying airbag can reach speeds up to over 300 km/h (200 mph). Deflation is also rapid, so that residual car control and escape from the vehicle is not impeded.

The inflated bag is designed to interpose itself between the occupant and the frontal structures of the passenger cabin, to cushion the impact and prevent forceful contact and hyperflexion.

In addition to the life-saving capabilities, airbags can also cause serious and even fatal injuries either by the airbag itself or the module cover overlying it in the steering wheel or in the fascia on the passenger side. Injuries can be inflected at any stage of the deployment process, depending on the posture and possible objects between the occupant and the deploying airbag or the module cover. They vary from facial bruising, partial or complete amputation of fingers to dislocated and fractured arms or cervical spine and fatal head injuries.[26–34] Eye injuries are common and range from mild corneal abrasions and chemical burns from contact with unburned sodium azide or the alkaline byproducts of combustion, which are released into the passenger compartment, to globe rupture from blunt trauma or perforation by interposed objects.[35–39]

The vulnerability of children in vehicles

This is a particular problem with several aspects. Many countries have brought in laws to protect children in cars because of their special vulnerability.

First, it is an understandable, but highly dangerous, indulgence for adults to allow small children to travel unrestrained in the front seat of a car. Some parents even allow them to stand gripping the fascia edge immediately below the windscreen, an invitation to facial and eye damage even in minor accidents. The seating of a child on the mother's lap is hazardous, as on violent deceleration either mother and child pitch against the windscreen – or the child flies out of the arms of a belt-restrained mother. The close proximity to the fascia and windscreen causes many deaths and facial injuries, especially to the eyes.

Adult-secured seatbelts will not properly accommodate a child (or even a small adult), because the fixation point on the door pillar is too high even if the straps can be shortened sufficiently to be made tight. The diagonal may pass across the throat and, unless special drop-plates are fitted to the door pillars, the restraint is often worse than useless.

As discussed above, a similar campaign has been successfully waged for rear-seat restraints for children and adults. Banished from the front, children were thought to be safe in the back of the car, but many have died and far more have been injured from being projected against the seat backs, front passengers and internal fitments. Special seats secured on top of the regular seating are required and, for a baby, the cot must be lashed down with equally robust restraints.

Since 18th of September 2006 the UK law requires all children travelling in cars to use the correct child restraint until they are either 135 cm in height or the age of 12 years (whichever they reach first). After this they must use an adult seat belt.

An appropriate child restraint is one which:

- Conforms to the United Nations standard, UN ECE Regulation 44.03.
- Is suitable for the child's weight and size.
- Is correctly fitted according to the manufacturer's instructions.

Injuries to motorcyclists

Though there are fewer motorcycles than four-wheeled vehicles, especially in developed countries, the rate of injury and death amongst motorcyclists is far higher than among car drivers. In the USA motorcyclists have a 34-fold higher risk of death in a crash per vehicle mile travelled than people driving other types of motor vehicles.[40] In Great Britain the number of motorcycle users killed fell by 9 per cent from 362 in 2011 to 328 in 2012. Motorcycle traffic decreased by 2 per cent over the same period.[41]

The two extremities of the body suffer most in motorcycle accidents, though Larsen and Hardt-Madsen's analysis in Denmark in 1988 also showed high injury rates for chest and abdomen (Figs 9.15, 9.16).[42]

- Because the rider inevitably falls to the ground, head injuries are common and often severe, causing most of the deaths.[43] Though crash helmets are mandatory in most countries, the severity of the impact often defeats the protective effect of the helmet.

  Impact with the road surface or another vehicle at speed causes skull fractures at any part of the head, but often temporoparietal. A common complication is a basal skull fracture, especially a 'hinge' fracture. This transverse crack across the floor of the skull, crossing the petrous base or behind the greater wing of the sphenoid bones through the pituitary fossa to the opposite side, has also been called 'the motorcyclist's fracture'.

  Another type is the ring fracture around the foramen magnum in the posterior fossa caused by an impact on the crown of the head (Fig. 9.3). The neck suffers quite often and Mant found cervical spine fractures in over one-quarter of his series. Brain damage may be severe, even with a helmet in place. Cortical contusion and laceration, sometimes contrecoup, may be gross enough to cause brain tissue to extrude through compound fractures of the skull. In Mant's series of motorcyclists, 60 per cent had skull fractures and almost 80 per cent had brain damage.[3]



Figure 9.15 Severe brush abrasions or 'friction burns' in a motorcyclist, who came off his machine and skidded across the road surface.



Figure 9.16 Pulmonary contusions in a motorcyclist, who collided with a truck and was hurled into a signpost. Death was caused by a cranial fracture and multiple injuries of the internal organs.

- The legs are often injured, either by primary impact with another vehicle or fixed road structures, or by becoming trapped by part of the motorcycle frame. Lacerations, friction burns and fractures – often compound – are common. Mant recorded leg or pelvic fractures in 55 per cent of his cases.
- Any part of the body may suffer injury, but less often than the extremities. Falling from the machine, especially at speed, can cause rib fractures and visceral damage, especially rupture of the liver and spleen.
- An injury common with motorcycles is the 'tail-gating' accident, where a rider drives into the back of a truck so that the machine passes underneath, but the head of the motorcyclist impacts upon the tail-board. Decapitation may occur in the most extreme cases, but severe head and neck injuries are almost inevitable.[44–46] Trucks in many countries must now have strong bars fitted at the rear to prevent this 'tail-gating', which may also happen to motor cars, the rear of the truck smashing into the windscreen and driver.

Safety helmets act both by providing a rigid barrier against impact, which depends partly on the shock absorbing padding within the helmet and by providing a smooth surface, which is designed to skid across the road surface, thus lengthening the stopping distance and time to reduce the G force of deceleration. Their strength is designed to be finite to control the rate of deceleration but in massive impacts seen at high speeds the helmet may be penetrated or the head and brain damaged by the transmission of blunt force.[46–53] Crash-bars are another safety measure on motorcycles, being fitted in front of the engine to project on each side and protect the legs if the machine falls over. Unless extremely strong, however, such bars can themselves trap the legs if they bend backwards on impact.

Injuries to pedal cyclists

These form a less severe counterpart of motorcycle lesions, as the pedal cycle has the same instability but far lower speeds. Once again, head injuries figure largely in accidents, as the height above the ground is considerable and the rider suffers from the passive fall, added to by any forward motion or projection from impact by a motor vehicle. Helmets are now worn by many cyclists and naturally afford considerable protection.[54–58]

Other injuries are from the primary impact from a striking vehicle, which may hit the rider around thigh, hip or chest level. Secondary damage to the shoulder, chest and arm may occur from striking the ground, when friction grazes are common. (A unique injury, though not fatal, was entrapment of the leg between wheel spokes with compression of the soft tissues of the calf, when the leg penetrated the wheel.)

Injuries to pedestrians

Worldwide these are easily the most common road fatalities, and over one-third of road traffic deaths in low- and middle-income countries are among pedestrians and cyclists. In the densely populated areas of the globe where vehicles are greatly outnumbered by people, such as Southern Asia, parts of Africa, the Middle East and Central America, pedestrian casualties form a significant part of the total mortality. For example, 38 per cent of all African road traffic deaths occur among pedestrians.[2]

Most pedestrians are struck by motor cars or trucks, and the type of vehicle makes a difference to the dynamics of the impact, which – unlike injuries to vehicle occupants – is an *acceleration* not a *deceleration* process.

Primary injuries are caused by the first impact of the vehicle on the victim, while secondary injuries are caused by subsequent contact with the ground (Figs 9.17–9.19).



Figure 9.17 A pedestrian struck by the front of a car may be projected forwards or lifted onto the vehicle.



Figure 9.18 At speeds of over 23 km/h (15 mph) a pedestrian can be 'scooped up' onto a car, suffering head injuries against the windscreen. He may then fall off sideways or – at higher speeds – be thrown over the roof.


Body attains velocity = V
Intial car velocity = V
1 Scooping - up
Velocity still V
Projected forward
Decelerates: velocity now V - x
2 Violent braking
Decelerated to velocity zero
Decelerates to velocity V - 3x but still moving
3 Running over

Figure 9.19 Sequence of events when a carried pedestrian is projected forwards during braking.

Some writers also use the term 'tertiary injuries' to describe the impact with the ground, reserving 'secondary' for additional contact with the vehicle, as when the pedestrian is hurled up against the windscreen. The usual sequence of events is as follows:

- The height of the car bumper bar is well below the centre of gravity of the adult pedestrian, which lies in the abdominal region. Thus the first impact tends to knock the legs from under the victim and rotate them towards the oncoming vehicle. Depending on the profile of the front of the car, the struck pedestrian is either thrown forwards in the direction of travel if the bonnet-front is high and blunt – or scooped up onto the bonnet top, as with many slope-fronted modern vehicles.
- If thrown forward, secondary injuries will be suffered as a result of striking the ground, as well as the primary impact on legs and often the hips. If the car speed is appreciable (anything over 20 km/h is sufficient), the body can be thrown into the air or knocked down flat with a severe impact. The secondary injuries may fracture the skull, ribs, pelvis, arm or thigh.

  A further hazard is being run over by the vehicle if the victim is projected directly in front. Sometimes he may be dragged by the underbelly of the car, and seriously soiled and injured, perhaps appearing at the rear if the vehicle does not stop quickly. Many impacts are on the front corner of the car and the pedestrian may then be knocked diagonally out of the path of the car. If thrown into the centre of the roadway, the person can be run down by a different vehicle overtaking in another lane or by one coming in the opposite direction on a single carriageway.
- If scooped up, the victim will land on either the bonnet or against the windscreen or corner-supporting pillar (the 'A' frame). The flat bonnet usually does relatively little damage, though linear abrasions, brush grazes, or friction burns may be seen. Violent contact with the windscreen, especially the rim or side pillars, is the most frequent cause of severe head injury from primary impact.

  Scooping-up can occur at speeds as low as 23 km/h (about 15 mph; below 19 km/h the body will usually be projected forwards). If the speed is high, the victim can be thrown up onto the car roof, sometimes somersaulting so that the head strikes the roof. He can then slide or be flung right over the back of the car, landing behind it in the roadway. This is more likely to happen if the car does not brake, but literally drives from under the body.
- In most cases, the scooped pedestrian falls or is flung off on one side of the car or the other, again to suffer secondary injuries in the road and perhaps be run over by another vehicle. The usual pattern of events is that, at the instant of contact – or even slightly before – the driver will apply the brakes violently. The scooped-up victim will acquire the speed of the car by the time he lands on the bonnet, but then

the vehicle decelerates. As the adhesion to the shiny surface is small, the newly acquired velocity of the body will cause it to slide off the front of the car as the latter brakes. The victim then hits the ground in front of the car, sustaining secondary injury – and may even be run over during the residual motion of the vehicle before it finally stops.

- In a high-speed impact, which may be anything over 50 km/h (31 mph), the body can be flung high in the air and for a considerable distance, either to the side or in the path of the car – or even backwards over the roof. In general, the severity of the injuries – both primary and secondary – will be the more severe the higher the speed.

It is impossible to estimate the speed of impact from the nature of the injuries. These can be fatal even at slow speeds of the order of 10 km/h (6 mph), yet occasionally high-speed impacts can produce only minor damage. In Ashton's, series half the deaths occurred at speeds less than 48 km/h (30 mph).[59,60] Rosén *et al.* have recently reviewed the literature on pedestrian fatality risk as a function of car impact speed and reported that papers written after 2000, while still showing a steep increase of risk with impact speed, provided substantially lower risk estimates than had been previously estimated.[61]

In child victims, although the general pattern of injuries is similar, their shorter height and smaller weight affects the mechanics of impact. The primary contact is higher up their body, so they tend to be hit forwards rather than rotated upwards, though many do become scooped up onto the bonnet. Children tend to be projected further by impact and may be hurled in the air at lower speeds than with adults. They are also more prone to be run over by reversing vehicles, especially trucks, as they often play between parked vehicles and – being small – are less visible to the driver. Recent safety measures on trucks include audible reversing warnings that are automatically linked to the gear-shift lever.

- When a pedestrian is struck by a larger vehicle, such as a van, truck or bus, the initial point of impact is higher and may cause primary damage to pelvis, abdomen, shoulder-girdle, arm or head. Because of the profile of these vehicles, there is no scooping-up effect, and the victim is usually projected forwards to suffer secondary damage from road contact and sometimes to be run over.
- The nature of pedestrian injuries reflects these dynamic effects.

The most common trauma is to the legs, some 85 per cent of pedestrian casualties having lower limb injuries (Figs 9.20, 9.21). Abrasions and lacerations to the upper shin and knee area are typical of car bumper contact, and fractures of the tibia and fibula, often compound, are so common that they are present in one-quarter of fatalities, according to Eckert.[8] The femur is fractured less often, but is no rarity. The midshaft may be broken or the head may be driven into the acetabulum, together with a fractured pelvis. In children, because of their small stature, the femur may be fractured by the low bumper bar. At autopsy, the skin of the lower legs



Figure 9.20 Primary injury to a pedestrian struck by a car. There is damage to both legs at about the same level, with a compound fracture of the right leg. These are sometimes called 'bumper fractures'. The height of the injuries above heel level should always be measured at autopsy.



Figure 9.21 Abrasions and laceration at knee level in a pedestrian struck by a car bumper. Their anterior position indicates that the victim was facing the vehicle at the moment of contact, but this may be a last-instant turn during final awareness of the car's proximity.

should be incised to seek deep bruising, as the clothing often protects the surface from obvious marking.

When a bumper strikes a leg, the tibia is often fractured in a wedge-shaped manner; the base of the wedge indicates the direction of the impact (often from behind), the front of the wedge pointing away from the side of contact.

If the leg is weight-bearing at the time of the impact, the tibial fracture tends to be oblique, whereas if not stressed, as when being lifted during walking, the fracture line is often transverse. When both shins are damaged, the level may be different on each side; this indicates that the person was moving at the time, with one leg raised in walking or running. Sometimes the level of injury appears too low for the normal bumper height of most cars, but this may indicate that the vehicle was braking violently at the moment of impact, going down on its suspension as the front wheels decelerated or locked, unless dip compensators were fitted.

Because of impact with the windscreen, pillars and roof, together with secondary contact with the ground, the head is the next most frequently damaged region – and the one which leads to most causes of death. Any type of injury may be sustained, as described in Chapter 5. Traffic accidents are the most frequent cause of skull fracture, especially of the base. Fractures of chest, arm and pelvis and injuries to the abdomen follow in frequency. Often the injuries are concentrated on one side, usually on the opposite side to the point of primary impact, because the body was thrown down onto the road. Because of rotation and the variable posture from being thrown off the car structure, however, the injuries are often widespread and may show no particular pattern.

Soft tissue injuries are common and, apart from abrasions, bruises and lacerations, muscle laceration and crushing can occur. A characteristic lesion from running-over, as opposed to knocking-down, is the 'flaying' injury, where a rotating motor wheel tears the skin and muscle from a limb or head (Fig. 9.22). The rotatory effect against a fixed limb may strip off almost all tissue down to the bone. When a wheel passes over the abdomen or pelvis, multiple parallel striae or shallow lacerations may occur near the contact area because of ripping tension in the skin.

When a wheel passes over the pelvis, abdomen or head, there may be great internal damage with little surface injury. The weight of a large vehicle can virtually flatten a head, crushing the cranial vault. Often the brain is extruded through scalp lacerations, as may be the intestine through an abdominal wound. The pelvis may flatten out when run over, the symphysis or superior rami breaking, and one or both sacroiliac joints becoming detached. Any type of intra-abdominal injury may occur from ruptured liver and spleen to perforated intestine, lacerated mesentery and fractured lumbar spine. In the chest, ribs, sternum and thoracic spine may fracture, and heart and lung damage occur from crushing or laceration from jagged ribs. A 'flail chest' is sometimes produced when a heavy wheel runs across the supine body, breaking all the ribs on each side in the anterior axillary line.


Figure 9.22 Injuries caused by being run over by a bus. The large rotating wheel has 'flayed' the right leg, stripping the skin and subcutaneous tissues from the muscles. The passage of the adjacent double wheel over the abdomen has extruded the intestines through the perineum.

Patterned injuries may be important, in that they can assist the police in identifying a vehicle in a 'hit-and-run' accident (Figs 9.23–9.25). The most common is a tyre pattern outlined in intradermal bruising and these should be measured carefully and photographed. These marks are usually caused by the skin being forced into the grooves of the tyre tread, the edge of the raised rubber tracing out the pattern (Figs 9.25, 9.26). The elevated parts do not leave bruises, but may imprint dirt on the skin.

Paint fragments and glass shards are also trace evidence that must be carefully retained, as the forensic laboratory may be able to identify the make and model of vehicle involved, and match the fragments when a suspect car is examined.

Parts of the vehicle may leave patterned imprints on the skin, such as headlamps, mirrors or other components (Fig. 9.23). Safety regulations for manufacturers have now almost eliminated the dangerous devices such as bonnet mascots, projecting door handles and non-flexible mirrors that used to adorn older cars. Metallic and plastic objects may still be found in the tissues from time to time, however; the author (BK) has recovered



Figure 9.23 A patterned injury in a pedestrian struck by a truck. The circular bruise and abrasion over the front of the shoulder are from a headlamp rim. There is also a well-demarcated imprint around the left eye from some other projection on the vehicle.



Figure 9.25 Intradermal bruising on the forehead of a live boy who was found wandering in the street with amnesia for recent events. He had been struck by a 'hit-and-run' car, which left identifiable tyre marks on the skin. An astute casualty officer had a photograph taken as the marks faded in a few hours.



Figure 9.24 Primary pedestrian injury. The pattern is caused by the bumper bar striking the leg. The height from the heel should always be measured for the police to compare with the vehicle – though during extreme braking, many vehicles will dip down at the front, thus lowering their bumper height.



Figure 9.26 Intradermal bruising reflecting the tyre tread pattern. Note the bruising is of the 'valleys' and not the 'hills' in the tread.

a door handle from the interior of the liver and a chromium bonnet insignia from a cerebral hemisphere. Any such artefacts must be preserved for the police in cases in which the identity of the vehicle is not known.

In Britain, where traffic drives on the left side of the road, it is more common for pedestrians to be struck on the right side as they walk off the pavement. Many, however, are struck facing the vehicle, from turning during last-minute awareness, and some are hit from behind.

These factors will all affect the distribution of injuries, but it is too hazardous to try to reconstruct unwitnessed events in any detail from a study of the injuries. Suprarenal haemorrhage is more common in the right gland than the left after a traffic injury in Britain (Johnson, unpublished communication), but this observation must be modified by the fact that many such haemorrhages occur several days after the trauma and are usually the result of general systemic effects, rather than direct impact.

Cause of death in traffic accidents

In gross injuries this is often obvious, as in the crushed head with extrusion of brain or rupture of the aorta. Often multiple injuries make it difficult to decide which was the most serious and mortal lesion, but in such cases it is quite acceptable to use the term 'multiple injuries', preferably listing several of the most lethal.

When death occurs on the road or soon afterwards, there is usually macroscopic evidence of gross musculoskeletal or organ damage, severe haemorrhage, blockage of air passages from blood, or traumatic asphyxia from fixation of the chest caused by crushing from some part of a vehicle.

Delayed death can be caused by continuing bleeding, secondary haemorrhage, renal failure from hypotension and/or extensive muscle damage, fat embolism, local infection, chest or other systemic infections, myocardial or cerebral infarction and other sequelae discussed in Chapter 13.

The presence of natural disease is always an important consideration in all transportation deaths, as a possible cause or contribution to the accident. In pedestrians, a sudden collapse in the roadway may lead to fatal injuries when a vehicle comes along – or even a dead body being run over by the next car.

Similarly, defects in sight or hearing may have contributed to the accident, though this is almost never detectable at autopsy, unless there are gross corneal or lens abnormalities. Of course, the possibility of drug or alcohol intoxication in the pedestrian victim must always be considered.

Where drivers or pilots are concerned – or even shipmasters – the presence of disease or intoxication may be a vital element, with both civil and criminal connotations possible.

Generally speaking, sudden natural disease does not often cause road vehicles to go out of control, as there seems to be a sufficient warning in most instances of cardiac or cerebral disablement, to allow the driver to pull over and stop.

Even the regular medical checks on older drivers legally enforced by some countries are no warranty that sudden collapse will not occur the very next day.

Schmidt *et al.* analysed 39 deaths at the wheel in Germany and found that 97 per cent had cardiovascular disease and 90 per cent had coronary heart disease. This was confirmed in a more recent retrospective study covering a 15-year time period in Munich, Germany, ranging from 1982 until 1996. Ischaemic heart disease was the underlying cause of death in 113 (84 per cent) of the 147 natural deaths at the wheel. Morild found that 14 of 133 traffic deaths in Norway had died of natural disease, again predominantly coronary atherosclerosis.[62–64]

The autopsy on a road traffic death

The autopsy is in general identical to the usual procedure, but with special attention to the following points:

- As criminal proceedings against a driver may follow, legal matters such as identity of the body and continuity of evidence must be assured, as discussed in Chapter 1.
- The body should be seen clothed, if brought dead to the mortuary or hospital, so that injuries can be matched against soiling and damage to the garments. Often this is not possible, especially if temporary survival allowed admission to a hospital or accident department, but where practicable the clothing should be preserved and examined by the pathologist. In any event, the clothes should be retained by the police for submission to the forensic science laboratory, usually when criminal proceedings are likely.
- Blood samples must be retained for blood grouping and now perhaps even 'DNA fingerprinting' in case a 'hit-and-run' vehicle is found with blood or tissue traces upon it. Sometimes hair samples may be required for the same purpose. Where death occurs within 12 or even 24 hours of the time of the accident, blood analysis for alcohol is essential, whether in the driver or pedestrian (see Chapter 28). Where possible, screening for drugs of dependence and common medicinal substances that might have caused drowsiness should be carried out. In combination with alcohol, even low levels of sedative, hypnotic and antihistamine drugs may be relevant in the causation of an accident. In certain cases, where leakage of carbon monoxide is

suspected, the circumstances will suggest analysis of the blood for carboxyhaemoglobin concentration.

- The external examination, as in all trauma deaths, is vital and should be detailed, accurate and fully recorded. The height of major or patterned injuries above heel level must be noted, in order to compare these against dimensions of a vehicle. Patterned injuries must be photographed with a scale in view. Any foreign bodies or particles, either in the clothing, hair, on the skin or in the wounds, must be carefully retained for forensic science examination, especially in a 'hit-and-run' accident, where the identity of the vehicle may be vital (Fig. 9.26).

  All types of trace evidence may be found by a pathologist, from paint flakes and glass debris (which may be traced to a certain make, age, type and even individual vehicle) to parts of the vehicle structure. In past years, the author (BK) has retrieved a door handle from inside a liver and a bonnet insignia from within a brain. In the last few decades vehicles have become more pedestrian-friendly due to better design of front-end shape and removal of protruding parts, such as bonnet insignia, that may cause injuries on impact.
- A full autopsy must be carried out, not merely a catalogue of injuries. The presence of any natural disease is relevant, especially if it might have contributed to the accident, either by causing a driver to lose control or ability to drive, or a pedestrian to exercise proper caution or behaviour in the roadway. Old and recent cardiac and cerebral lesions are particularly important, as is any evidence of a fit, such as a bitten tongue, or old meningeal adhesions over cortical damage. It is almost impossible to assess visual acuity at autopsy, but obvious lesions such as lens opacities must be noted. Similarly, it is virtually impossible to give any opinion on acuity of hearing from autopsy findings unless there is a gross neurological abnormality in the auditory tract.

Suicide and homicide by motor vehicle

There is little that the pathologist can contribute to the elucidation of motivation in traffic accidents, as it is circumstantial and sometimes forensic-laboratory evidence that is more likely to reveal a non-accidental cause. Homicidal traffic deaths are rare, though the author (BK) has been involved in one incident where racial hatred led to the running-down of youths of one ethnic group – and another where a man repeatedly crashed the near-side of his own car in an effort to kill his passenger (his wife). There are no specific pathological features that can assist, except that the incident is likely to occur at relatively high speed, without braking effects. The victims of homicide by other means – or persons rendered unconscious first – may be deliberately placed in motor vehicles which are then crashed, preferably with a subsequent fire. The author (BK) dealt with one such case where a husband placed the body of his strangled wife in his car and secretly pushed it over the edge of a mountain road. Unfortunately (for him), he left the ignition key in the 'off' position. This faking of a vehicular 'accident' to conceal homicide is by no means unknown, the author (BK) being involved in another case where a police officer disposed of the body of his wife who died in suspicious circumstances, by crashing her car and smashing the windscreen with a hammer to add to the effect. Further nine 'true vehicular homicides' have been presented by Copeland and one by Nadesan.[65,66]

In such circumstances, the pathologist's role is to match the injuries with a traffic accident, to detect any which are atypical. For instance, focal depressed fractures of the skull of the type caused by a weapon are unusual in a car occupant unless there was a localized intrusion of the vehicle roof. The ante-mortem nature of the injuries should be demonstrated, though this is not always possible. When there is a fire, some evidence of ante-mortem burns, soot inhalation or carbon monoxide absorption should be sought, though – as mentioned in Chapter 11 – some flash petrol fires may kill before any monoxide is absorbed. Where the victim was unconscious though not dead, no such differentiation is possible. Full analysis for alcohol and stupefying drugs must be made if there is any suspicion.

Attempts at deliberate self-destruction by the use of a motor vehicle are said to be not uncommon, though this is difficult to prove in most cases.[67–69] Once again, the evidence is more likely to be based on circumstantial rather than medical evidence – a matter for the investigating authorities rather than the pathologist. Driving at speed into the path of an oncoming truck or into a solid obstruction at the roadside are the methods employed, though it is hard to prove in the absence of definite evidence. It has been said that the imprint of the accelerator pedal on the undersurface of the shoe may be an indication, though this can never be the only indication. A witnessed lack of other causative factors may offer some corroboration, but this is police business, not pathology.

Railway injuries

These are not uncommon, especially in countries with many 'level crossings' (called 'grade crossings' in the USA), where a public road crosses a railway track with either no barrier at all or with only a flimsy lifting pole. Many vehicles are struck each year by passing locomotives.

Few rail passengers are killed or injured in moving trains compared with accidents to railway staff and to other types of accident on railway property. Track workers may be run down and some die from electrocution from overhead cables. The pathology of all these is no different from accidents elsewhere, the interest lying in the occupational epidemiology and preventive aspects.

One worrying development in recent years is the malicious damage caused to trains, either by placing objects on the tracks, which may cause a derailment, or the dropping of objects from bridges. The author (BK) has conducted an autopsy on a driver killed by a concrete block dropped from a bridge, which smashed through the windshield of his cab.

The other fairly common railway fatality is the suicide who lays himself in front of an approaching train. Decapitation is the most common injury and the obvious features are the local tissue destruction, usually with grease, rust or other dirt soiling of the damaged area (Figs 9.27, 9.28).

The usual search for alcohol and other drugs must be made, as suicides often employ multiple methods to ensure self-destruction. As well as lying down before a locomotive, another common method of suicide in large cities is to jump from the subway platform of an underground 'tube' or 'metro' system. Here injuries are sometimes complicated by high-voltage electrical lesions, as the typical traction voltage of an electric railway is in excess of 600 volts.



Figure 9.27 Amputation of the right arm and bruising of the face and chest in a pedestrian struck by a passing locomotive.



Figure 9.28 Extensive disintegration of the body that has been run over by a train.

References

1. WHO. *Global Status Report on Road Safety: time for action*. Geneva: World Health Organization, Dept. of Violence and Injury Prevention and Disability. 2009.
2. WHO. *Global Status Report on Road Safety 2013: supporting a decade of action*. Geneva: World Health Organization, Department of Violence and Injury Prevention and Disability (VIP). 2013.
3. Mant AK., *Injuries and death in motor vehicle accidents*, in *Pathology of Violent Injury*, J.K. Mason, Editor. 1978, Edward Arnold: London, UK.
4. Kramer, F. *Passive Sicherheit von Kraftfahrzeugen Grundlagen – Komponenten – Systeme; mit 24 Tabellen*. ATZ-MTZ-Fachbuch. Braunschweig u.a.:Vieweg. IX. 1998, 329 S.
5. Schmitt, K-U, *et al.* Injuries of the pelvis and the lower extremities. In: *Trauma biomechanics: accidental injury in traffic and sports*. Heidelberg: Springer; 2010, pp. 183–212.
6. Schmidt G, Kallieris D. [Injuries caused by automobile safety glass]. *Beitr Gerichtl Med* 1992;50:21–9.
7. Thomas P, Bradford M. The nature and source of the head injuries sustained by restrained front-seat car occupants in frontal collisions. *Accid Anal Prev* 1995;27(4):561–70.
8. Eckert W. Traumatic pathology of traffic accidents; review of 302 cases. *J Forensic Sci* 1959;4:3–20.
9. Moore JO, Tourin B. *A Study of Automobile Doors Opening Under Crash Conditions*. New York: Cornell University Medical College, 1954.
10. Tourin B. Ejection and automobile fatalites. *Public Health Rep* 1958;73(5):381–91.
11. Green PD, *et al. Car Occupant Ejection in 919 Sampled Accidents in the UK – 1983–86*. SAE Technical Paper, 1987. DOI: 10.4271/870323.

12 Mackay GM, *et al*. Restrained front seat car occupant fatalities – the nature and circumstances of their injuries. *Accid Anal Prev* 1992;24(3):307–15.
13 Bilston LE, Du W, Brown J. A matched-cohort analysis of belted front and rear seat occupants in newer and older model vehicles shows that gains in front occupant safety have outpaced gains for rear seat occupants. *Accid Anal Prev* 2010;42(6):1974–7.
14 Ichikawa M, Nakahara S, Wakai S. Mortality of front-seat occupants attributable to unbelted rear-seat passengers in car crashes. *Lancet* 2002;359(9300):43–4.
15 Elvik R, Vaa T. *The Handbook of Road Safety Measures*, 1st edn. Amsterdam: Elsevier. 2004, xi.
16 Zhu M, *et al*. Association of rear seat safety belt use with death in a traffic crash: a matched cohort study. *Inj Prev* 2007;13(3):183–5.
17 Bako G, Mackenzie WC, Smith ES. What is the risk of being burned in a motor vehicle crash? A survey of crash fatalities in Alberta. *J Traffic Med* 1970;4:20–4.
18 Wolf ME, *et al*. A retrospective cohort study of seatbelt use and pregnancy outcome after a motor vehicle crash. *J Trauma* 1993;34(1):116–9.
19 Bunai Y, *et al*. Fetal death from abruptio placentae associated with incorrect use of a seatbelt. *Am J Forensic Med Pathol* 2000;21(3):207–9.
20 Hitosugi M, *et al*. The benefits of seatbelt use in pregnant women drivers. *Forensic Sci Int* 2007;169(2–3):274–5.
21 Asbun HJ, *et al*. Intra-abdominal seatbelt injury. *J Trauma* 1990;30(2):189–93.
22 Legier JF. *Traumatic seromuscular rupture of intestine. Am J Forensic Med Pathol* 1992;13(3):253–4.
23 Deambrosis K, *et al*. Delayed duodenal hematoma and pancreatitis from a seatbelt injury. *West J Emerg Med* 2011;12(1):128–30.
24 O'Dowd V, *et al*. Seatbelt injury causing small bowel devascularisation: case series and review of the literature. *Emerg Med Int* 2011;2011:675341.
25 Warrian RK, *et al*. Seatbelt injury to the abdominal aorta. *J Trauma* 1988;28(10):1505–7.
26 Cunningham K, *et al*. Airbag associated fatal head injury: case report and review of the literature on airbag injuries. *J Accid Emerg Med* 2000;17(2):139–42.
27 Perdikis G, *et al*. Blunt laryngeal fracture: another airbag injury. *J Trauma* 2000;48(3):544–6.
28 Zaglia E, *et al*. Occipital condyle fracture: an unusual airbag injury. *J Forensic Leg Med* 2007;14(4):231–4.
29 Batra S, Kumar S. Airbag-induced fatal subaxial cervical spinal cord injury in a low-velocity collision. *Eur J Emerg Med* 2008;15(1):52–5.
30 Donaldson WF, 3rd, *et al*. Cervical spine injuries associated with the incorrect use of airbags in motor vehicle collisions. *Spine* (Phila Pa 1976) 2008;33(6):631–4.
31 Monkhouse SJ, Kelly MD. Airbag-related chest wall burn as a marker of underlying injury: a case report. *J Med Case Rep* 2008;2:91.
32 Hoye A. Are airbags a dangerous safety measure? A meta-analysis of the effects of frontal airbags on driver fatalities. *Accid Anal Prev* 2010;42(6):2030–40.
33 Francis D, *et al*. Sodium azide-associated laryngospasm after air bag deployment. *J Emerg Med* 2010;39(3):e113–5.
34 Smock WS. Airbag related injuries and deaths. In: Siegel JA, Saukko PJ (eds). *Encyclopedia of Forensic Sciences*. Waltham: Academic Press, 2013, pp. 414–21.
35 Pearlman JA, *et al*. Airbags and eye injuries: epidemiology, spectrum of injury, and analysis of risk factors. *Surv Ophthalmol* 2001;46(3):234–42.
36 Scarlett A, Gee P. Corneal abrasion and alkali burn secondary to automobile air bag inflation. *Emerg Med J* 2007;24(10): 733–4.
37 Subash M, Manzouri B, Wilkins M. Airbag-induced chemical eye injury. *Eur J Emerg Med* 2010;17(1):22–3.
38 Barnes SS, Wong W, Jr, Affeldt JC. A case of severe airbag related ocular alkali injury. *Hawaii J Med Public Health* 2012;71(8):229–31.
39 Kung J, *et al*. Traumatic airbag maculopathy. *JAMA Ophthalmol* 2013;**131**(5):685–7.
40 National Highway Traffic Safety Administration. *Traffic Safety Facts 2005: Motorcycles*. Washington: U.S. Department of Transportation, National Highway Traffic Safety Administration, 2007, p. 205.
41 Reported Road Casualties in Great Britain: Main Results 2012. In: *Statistical Release*, 2013, p. 8.
42 Larsen CF, Hardt-Madsen M. Fatal motorcycle accidents in the county of Funen (Denmark). *Forensic Sci Int* 1988;38(1–2): p. 93–9.
43 Lin MR, Kraus JF. A review of risk factors and patterns of motorcycle injuries. *Accid Anal Prev* 2009;41(4):710–22.
44 Hitosugi M, *et al*. Decapitation in helmeted motorcyclists. *Am J Forensic Med Pathol* 2005;26(2):198.
45 Ihama Y, *et al*. Complete decapitation of a motorcycle driver due to a roadblock chain. *Int J Legal Med* 2008;122(6):511–5.
46 Zoja R, *et al*. Death by complete decapitation of motorcyclist wearing full face helmet: case report. *Forensic Sci Int* 2011;207(1–3):e48–50.
47 Reich H, Dalgaard JB. [Would a crash helmet have been life-saving? An analysis of 188 fatal motor scooter accidents (author's transl)]. *Z Rechtsmed* 1975;75(4):235–9.
48 Hitosugi M, *et al*. Analysis of fatal injuries to motorcyclists by helmet type. *Am J Forensic Med Pathol* 2004;25(2):125–8.
49 Liu BC, *et al*. Helmets for preventing injury in motorcycle riders. *Cochrane Database Syst Rev* 2008(1):CD004333.
50 Mayrose J. The effects of a mandatory motorcycle helmet law on helmet use and injury patterns among motorcyclist fatalities. *J Safety Res* 2008;39(4):429–32.
51 Weiss H, Agimi Y, Steiner C. Youth motorcycle-related brain injury by state helmet law type: United States, 2005–2007. *Pediatrics* 2010;126(6):1149–55.
52 Crompton JG, *et al*. Motorcycle helmets associated with lower risk of cervical spine injury: debunking the myth. *J Am Coll Surg* 2011;212(3):295–300.
53 Ouellet JV. Helmet use and risk compensation in motorcycle accidents. *Traffic Inj Prev* 2011;12(1):71–81.
54 Ostrom M, *et al*. Pedal cycling fatalities in northern Sweden. *Int J Epidemiol* 1993;22(3):483–8.
55 Hawley DA, Clark MA, Pless JE. Fatalities involving bicycles: a non-random population. *J Forensic Sci* 1995;40(2):205–7.
56 Rowe BH, Rowe AM, Bota GW. Bicyclist and environmental factors associated with fatal bicycle-related trauma in Ontario. *CMAJ*, 1995;152(1):45–53.
57 Toro K, *et al*. Fatal traffic injuries among pedestrians, bicyclists and motor vehicle occupants. *Forensic Sci Int* 2005;151(2–3):151–6.
58 Stipdonk H, Reurings M. The effect on road safety of a modal shift from car to bicycle. *Traffic Inj Prev* 2012;13(4):412–21.

59 Ashton SJ. The cause and nature of head injuries sustained by pedestrians. In: *2nd Conference of Biomechenical Serious Trauma*, Lyon, France, 1975.

60 Ashton SJ, Mackay GM. Pedestrian injuries and death. In: Mason JK (ed). *The Pathology of Violent Injury*. London: Edward Arnold, 1978.

61 Rosen E, Stigson H, Sander U. Literature review of pedestrian fatality risk as a function of car impact speed. *Accid Anal Prev* 2011;43(1):25–33.

62 Schmidt P, Haarhoff K, Bonte W. Sudden natural death at the wheel – a particular problem of the elderly? *Forensic Sci Int* 1990;48(2):155–62.

63 Buttner A, Heimpel M, Eisenmenger W. Sudden natural death 'at the wheel': a retrospective study over a 15-year time period (1982–1996). *Forensic Sci Int* 1999;103(2):101–12.

64 Morild I. Traffic deaths in western Norway. A study from the county of Hordaland 1986–1990. *Forensic Sci Int* 1994;64(1): 9–20.

65 Copeland AR. True vehicular homicide. *Am J Forensic Med Pathol* 1986;7(4):305–7.

66 Nadesan K. Murder and robbery by vehicular impact: true vehicular homicide. *Am J Forensic Med Pathol* 2000;21(2): 107–13.

67 Selzer ML, Payne CE. Automobile accidents, suicide and unconscious motivation. *Am J Psychiatry* 1962;119:237–40.

68 Elnour AA, Harrison J. Lethality of suicide methods. *Inj Prev* 2008;14(1):39–45.

69 Henderson AF, Joseph AP. Motor vehicle accident or driver suicide? Identifying cases of failed driver suicide in the trauma setting. *Injury* 2012;43(1):18–21.

This page intentionally left blank

CHAPTER 10

Abuse of Human Rights: Deaths in Custody

- Introduction
- Evidence of fatal physical abuse
- Extrajudicial execution
- Death in custody
- Human rights organizations
- References

Introduction

Regrettably, abuse of human rights is so widespread on a global scale that some reference must now be made in forensic pathology texts to the physical manifestations of torture. According to Amnesty International, torture of one kind or another was practised in one-third of the member states of the United Nations, in spite of them being signatories to United Nations resolutions banning these atrocities.[1] Their worldwide Report in 2012 recounted specific restrictions on free speech in at least 91 countries as well as cases of people tortured or otherwise ill-treated in at least 101 countries.[2]

Although most torture does not result in death, there are sufficient cases of physical abuse of human rights that progress to fatality that a number of organizations offer expertise when any alleged case needs to be investigated, usually calling upon forensic pathologists to assist them in such circumstances. These include Amnesty International (based in London), Physicians for Human Rights (PHR), the Medical Foundation for the Treatment of Victims of Torture (London) and many others (see list of some of the organizations with contact information at the end of this chapter).

Evidence of fatal physical abuse

In many instances the autopsy appearances of fatal abuse are no different from those by any other homicide, and the confirmation of lethal torture must depend upon circumstantial and other corroborative evidence, which is no concern of this book. For example, if a political detainee is kicked to death, the physical findings may be identical to those of a murder by kicking in a street crime. Similarly, head injuries, shooting and suffocation may show no variation from the same modes of death outside a political context.

Certain features may arouse suspicion or provide definite evidence that the death had political overtones. The word ‘political’ is used in a wide sense as many abuses of human rights are not directed or even condoned by higher levels of government, though often there is an indifference to being informed about such activities. Many instances of illegal death and injury are perpetrated by the military or the security forces – and even here, the level of command that directs or condones the abuse varies greatly. In general, the civil police and the regular prisons are usually not the perpetrators of gross abuse, though there are many exceptions. It tends to be the armed forces, clandestine security police and special detention camps that are most often guilty of torture and illegal executions.

One of the features that characterizes torture and abuse is that the victim is usually either in detention or some form of custody, or is temporarily in the power of the authorities, even if that means that soldiers have just burst into a private house. All deaths in custody – discussed later in the chapter – should be examined with care, as much to ensure that the guardians are cleared of any suspicion of ill-treatment as to discover any ill-treatment itself. The fatal event may be quite different from the non-fatal abuse, as a victim who is beaten may be disposed of by shooting. As in all forensic work, the pathological investigations can only be part of the overall enquiry, another example of co-operation and teamwork between all disciplines.

One of the major differences – and great problems – in the investigation of torture and abuse of civil rights is that the authorities in the state where it occurred may be totally unco-operative and, indeed, wholly hostile to impartial enquiry. It is through respected international agencies, such as the International Committee of the Red Cross (ICRC), Amnesty International, Physicians for Human Rights (PHR), and the United Nations' Office of the High Commissioner for Human Rights (OHCHR), often in collaboration with National Human Rights Institutions, that pathologists have the best chance of being allowed access to the relevant material, and the organizations mentioned above are willing to undertake or assist legitimate investigations anywhere in the world.

One particular problem associated with human rights abuse is the frequent long delay before being able to examine the victim. In the living, they may have been detained for months or years after the ill-treatment, or may have been exiled or in hiding before they have the opportunity to be seen by an impartial medical observer, by which time acute injuries will have healed, bruises absorbed and wounds and burns scarred over (Fig. 10.1). In the dead, long-term post-mortem changes are common: the body may have been buried and exhumed before examination.

Even skeletal material is all that is sometimes available, as in the 'lost children' of Argentina or in the killing fields of Uganda. Problems of identification are often difficult. Contemporary photographs of injuries are often of poor quality and the facilities for autopsy are primitive in some of the less developed countries. When the suspicion, lack of co-operation and often open hostility of the local authorities is added, the task for the visiting pathologist is formidable indeed.

The following types of injury may confirm or arouse suspicion of torture, though, as stated, virtually any type of injury can be inflicted deliberately to extract information, punish or degrade the victims or to exterminate them. Repetition of a particular injury, such as 'tramline' bruises from beating, is suspicious, because in ordinary assaults and homicides such excessive and perhaps regularly placed repetitive lesions would be unusual.

- Beating is one of the most common forms of torture and can take many forms, varying both with the weapon used and the part of the body injured.[3–5] Blows both to the head and to other parts of the body were present in all the cases reported by Hougen.[3] Unless severe and repeated, beating is not often the sole cause of death, though this can occur from haemorrhage, sepsis, injured internal organs or from sheer exhaustion and pain in an already debilitated victim. The blows may be inflicted by fist or foot, but are more often applied with a weapon. The use of a whip or lath-like instrument is common, but metal or wooden bars, clubs, batons, rifle butts or belts may be used. More recently, lengths of plastic hosepipe or tubing have come into favour in some parts of the world.

  Many of these produce a characteristic skin lesion, namely a single- or double-edged linear bruise (Fig. 10.2). The bruise may be a line of confluent petechial haemorrhages or a continuous mark of red



Figure 10.1 A scar about 1 year after the original injury. The female victim was shot while escaping from an East African concentration camp. The wound was opened surgically and healed imperfectly with keloid formation. The other surgical incision is of more recent origin. Such scars will remain unaltered for life, apart from possible increase in the keloid formation.



Figure 10.2 Recent bruising inflicted within the previous 2 days, from blows by lengths of plastic tubing about 15 mm wide. The injuries show parallel 'tramlining' typical of impact from a cylindrical weapon. The assailants were vigilantes administering a punishment beating to an alleged collaborator in a Middle Eastern country.

skin. The 'tramline' bruise is a double line of parallel marks with a pale unbruised zone between them, caused by the impact of a rectangular or circular-sectioned object. This is described in more detail in Chapter 4.

The bruising may be intradermal, when it reproduces the pattern of the weapon well. If a leather whip with, for example, plaited thongs, is struck against the skin, the pattern may be imprinted clearly on the skin. Buckles on belts and other recognizable artefacts may occasionally be useful in identifying the weapon. Where the bruising is deeper, no such pattern is likely. The skin may be broken, causing abrasions or lacerations and, if the full thickness is breached, healing will cause scars, which may even be recognizable as 'tramlines' (Fig. 10.3).

Repeated beating leaves multiple marks, which though overlapping and often criss-crossing, may have a generally similar orientation that indicates that the attacker stood in a relatively fixed position to the victim. For example, lashing across the back may leave marks running from top right to bottom left, suggesting that a right-handed perpetrator stood to the left of the victim.

The use of a multi-thonged whip, such as a 'cat-o'nine-tails' will leave a series of marks, again generally in the same orientation. The thongs tend to be narrow and may cause linear marks with tramlining. There may be metal tags or knots on the end of each thong, which can cause focal damage. The back is the most frequent target, but whipping and beating may be applied to the buttocks, thighs, front of chest, breasts and abdomen, lower legs, soles of the feet, and even perineum and genitals.



Figure 10.3 Scars from beating with a thin metal rod in an East African torture camp. Though more than 1 year old, the 'tram-line' nature of one of the scars is outlined in keloid.

Beating of the soles of the feet with canes or rods is a torture rooted in antiquity and this so-called 'falanga' may leave relatively little to see, even though it is extremely painful and debilitating. The tough tissue and thick fascial planes of the foot do not readily reveal bruising, though it may be found on deep dissection in victims who have been killed by some other means.

If injuries were inflicted months before examination, little or nothing may be found unless the skin was broken, when scarring will have taken place. Sometimes, however, faint red lines may be seen in pale-skinned people and in those with appreciable racial melanin pigment there is often hyperpigmentation along the lines of injury. Where severe damage has been caused and sometimes where there is scar tissue, depigmentation may be seen. Bone scintigraphy was suggested for early recognition of deliberate child abuse to reveal occult skeletal lesions by Sfakianakis *et al.*[6,7] and this method has later been used in screening of torture survivors, where positive bone scans have been reported even in falanga victims and which may show detectable signs of bone trauma after months.[8–11]

- Burns are unfortunately common and may be either the actual cause of death or visible as recent or scarred evidence of previous torture. All kinds of burns may be suffered. The author (BK) has seen extensive burns from molten rubber dripped onto victims from motor tyres suspended overhead, hot irons applied to skin, ignited kerosene-soaked rags wrapped around limbs and numerous burns from cigarettes pressed into the skin. Knowledge of local practices, such as the burning motor tyre 'necklace', can help identify burns in typical sites. Where molten liquids have been dripped from above onto a bound-up victim, there may be shadow areas that indicate the direction of contact, which makes any innocent explanation highly unlikely. In survivors, scarring occurs in all but the most superficial burns, and may lead to large, unsightly cicatrized areas. In victims of African origin, large keloids may form, and further complicate the damage and attempts at surgical treatment (Figs 10.4, 10.5).
- Cutting and stabbing may be inflicted with a variety of weapons, but wounds from knives and bayonets are most common in the context of torture and extrajudicial execution. The features are identical to



Figure 10.4 Keloid scars from extensive burns during torture. The elderly female was tied to a chair and a burning motor tyre suspended over her. The shadowed area between the breasts indicates the downward trickle of molten burning rubber. Her face was also extensively scarred.



Figure 10.5 Extensive keloid scars following deliberate burning of a 16-year-old student in an East African concentration camp. An electric hot plate was pressed against his neck and kerosene-soaked rags were ignited on his arm.

those described in Chapter 4. The site on the body may be anywhere, but the chest and upper arms seem to be favourite targets. The scars of old stab wounds, such as those from a bayonet, may still be recognizably elliptical many months or years after infliction (Fig. 10.6).

- Clubbing and blunt injury is extremely common, either to cause death or as a form of abuse. It is sometimes dispensed almost casually, as when guards lay about themselves with rifle butts against the inmates of detention camps. Again the features are non-specific and are described in the chapter on wounding. The head is the most common target, but the legs and knees are also often struck. Blows on the back or side of the neck can be particularly lethal from vertebrobasilar artery damage (Chapter 5).
- Deaths from suffocation and drowning are not common, though non-fatal practices of this kind are well-known methods of abuse. Repeated dipping of the victim's head under water or even foul liquid such as sewage is called 'submarining', and may cause drowning, air-passage occlusion or a later pneumonia. Enveloping the head in an opaque plastic bag is more a means of disorientation than physical torture, but partial suffocation by similar means may eventually prove fatal.
- Electrical torture is common and well documented. Either mains voltage of 110 or 240 V is used – which carries the risk of fatal cardiac arrhythmia as well as local burning – or a magneto delivering high voltage, which is painful but not lethal. The latter will not leave any significant skin marks, as the amperage is so low.



Figure 10.6 The scar of a bayonet stab wound inflicted many months earlier in a Ugandan torture camp. Though scars are usually of little help in interpreting the cause of the injury, here the elliptical shape of the original stab wound can still be seen as a keloid scar and even the sharp upper end of the blade edge, as opposed to blunter lower end.

The later demonstration of electrical injury is difficult, as healed lesions have few characteristic features. The acute injuries which may cause burns and death are described in Chapter 12. The current may be applied anywhere, but the genitals are sites favoured by torturers, especially the penis and scrotum. The female nipples are also targets. According to Peel various devices, such as metal bedframes (*la parilla*), and modified cattle prods (*picana eléctrica*) have been used.[12] Barber *et al.* reported a case where electric shock torture was applied to the tympanic membrane.[13]

Danielsen, Thomsen, Karlsmark and co-workers carried out a series of experimental studies on the pathology of heat exposure and electrically induced dermal injury in pigs. They described a characteristic calcification pattern of collagen fibres a few days after application of AC and DC in the cathode area. They also describe a case of a 5-year-old female with skin injuries to the chest and one arm where calcification localized to collagen fibres and situated both superficially and deeply in the skin appeared similar as observed in their electrically induced lesions in pig skin.[14–26] Although the authors consider that 'collagen calcification in the pattern observed in this patient is probably diagnostic of electrical injury', they also state that: 'because of a lack of evidence with regard to the circumstances under which the child received her injuries, the case has not yet been presented in court', leaving too many open questions as to the diagnostic reliability of the reported findings until they have been corroborated by further research and casework.

- Injuries to the ears can rarely be demonstrated at autopsy, but a favourite torture is the (*teléfono*), consisting of simultaneous repeated slapping of the ears by the open palms of the assailant. This may rupture the tympanic membranes and injure the inner ear.
- Suspension is a common torture, though again not often fatal in itself. If the victim is seen relatively soon after the ordeal then abrasions, bruises and chafing marks may be found at ligature sites, usually on legs, arms and sometimes genitals (Figs 10.7–10.9).
- Shooting is not a method of torture in the accepted sense, but is a common means of execution or of non-fatal punishment, such as the 'knee-capping' perpetrated in Northern Ireland, where opponents and suspected traitors are shot either through the knee joint or the lower thigh. In some primitive prison camps the detainees are sometimes shot through the instep to prevent them from escaping (Figs 10.10, 10.11).



Figure 10.7 Fresh bruising from hand cuffs.



Figure 10.8 Fresh bruising from shackles.



Figure 10.9 Multiple scars from suspension and hand cuffing. (Reproduced by kind permission of Professor D.N. Vieira.)



Figure 10.10 Infected gunshot wound to the foot with a large tissue defect. A brutal means to keep the inmates from escaping. The arrow shows the entrance wound. (Reproduced by kind permission of Professor D.N. Vieira.)



Figure 10.11 Entrance wound from a close range gunshot, which was fired to obtain confession from a prisoner. (Reproduced by kind Permission of Professor D.N. Vieira.)

- Sexual abuse is also common and in females, rape – sometimes multiple – may leave physical signs as described in Chapter 18.

Medical examiners of alleged victims of torture must be careful not to misinterpret non-torture lesions as evidence of abuse, as such lapses will be seized upon by opponents wishing to discredit the medical opinion, either for political or immigration reasons. Forrest's guide (Forrest *et al.*) lists most of these, which include innocent occupational, sporting or other accidents, tribal marks, skin infections, variations in pigmentation, traditional scarification, healing marks, stretch marks, etc.[27]

The Manual on the Effective Investigation and Documentation of Torture and Other Cruel, Inhuman or Degrading Treatment or Punishment, (Istanbul Protocol) was submitted to the UN High Commissioner of Human Rights in August 1999 as the result of a collaborative effort by more than 75 experts in law, health and human rights, representing 40 organizations or institutions from 15 countries. It serves as international guidelines for the assessment of persons who allege torture and ill-treatment, for investigating cases of alleged torture and for reporting findings to the judiciary or any other investigative body. The revised version of the manual was published in 2004 by the UN and includes principles for the effective investigation and documentation of torture and other cruel, inhuman or degrading treatment or punishment.[28] In 2003 Brogdon *et al.* published a radiologic atlas of torture and more recently Özkalipci *et al.* published an atlas of torture.[29,30]

Extrajudicial execution

Many hundreds of thousands – indeed probably millions – of victims have been assassinated in recent years by governmental agencies acting quite outside the legal system. Because of ethnic origin, tribal feuds or political views, whole sections of populations have 'disappeared' on a scale sometimes amounting to genocide as in Rwanda, Cambodia, Bosnia and Kosovo. It is common knowledge that these disappearances are usually explained by murder, either on a mass scale or by continuous individual or group extermination by 'extermination squads'. Specific instances are not the concern of a textbook, but as recent years have shown, severe excesses have taken place in most continents leading to several forensic exercises directed towards identification of victims and proving methods of torture.

When vanished people have been presumed to have been killed by troops or security agencies, the evidence is usually very late in coming to light, so that forensically, much of the work consists of skeletal identification and investigations into causes of death. Where the bodies have decomposed or skeletalized, shooting or head injuries may be the only mode of death to leave any telltale evidence on exhumation. Autopsy examination may resemble mass-disaster procedures where there are large numbers of victims. The talents of odontologists and anthropologists, and the techniques of archaeology may be needed in such cases, as described by Clyde Snow in relation to the 'lost children' of Argentina or more recently in Bosnia and Herzegovina, Croatia and Kosovo.[31–35] The vast numbers of skeletal remains in the Lowero triangle of Uganda have so far had no such attention.

Death in custody

The occurrence of death while a person is either in the custody of the police or the inmate of a prison, raises public interest and emotions that require careful handling and investigation. There is often an immediate complaint or rumour of ill-treatment by the relatives or the media. A meticulous autopsy is a necessary part of the investigation needed to dispel – or sometimes confirm – allegations that an act of commission or omission on the part of the custodians has led to, or contributed to, the death. This applies in all countries and has no relationship to the preceding section, when political issues may be suspected as a cause of the death. The two aspects are not always totally separate, however, as countries with excellent human rights records have sometimes been suspected of occasional lapses of standards where custodial deaths are concerned.

Most of the cases dealt with by a forensic pathologist will concern civil police forces and the regular prison service. Many countries, including Britain, have strict legislative rules that make all deaths in custody, whether police or prison, reportable for medico-legal investigation by the appropriate law officer (the coroner in England and Wales), in addition to a searching internal enquiry by officers from a different police force (e.g. in Finland the National Bureau of Investigation).

An autopsy will inevitably be held, regulations in UK making this a case for an accredited forensic pathologist. It is sometimes helpful if the pathologist visits the scene of the death, especially if it was caused by hanging or some form of mechanical trauma.

There are several situations in which death may occur in custody. The deceased may die during or soon after arrest by police officers, as there is often a struggle in which the offender is resisting arrest, sometimes violently. It may be a physical struggle, especially when police officers are attempting to control or overpower a resisting offender. In these situations, the use of so-called personal defence sprays has increased, as they have been shown to be very effective in incapacitating an aggressor. They cause acute ocular irritation, lachrymation, conjunctivitis, blepharospasm and extreme discomfort. Most of these sprays contain *o*-chlorobenzylidene malononitrile (CS), 2-chloroacetophenone (CN), oleoresin capsicum (OC), or a combination of these ingredients as the active agent. Capsacain (8-methyl-*N*-vanillyl-6-nonenamide) is a neurotoxin component of cayenne pepper. It stimulates excitatory afferent sensory neurons, causes hypothermia, neurogenic inflammation and pain, followed by subsequent desensitization. Although these sprays have been considered to be relatively safe, unexpected deaths have been reported after the exposure to OC spray devices. Pepper spray has been suspected to induce bronchoconstriction. Chan and co-workers tested the effect of OC spray inhalation on respiratory function in 35 healthy subjects by itself and combined with restraint but could not find evidence of hypoxaemia or hypercapnia in either group. OC exposure did not result in abnormal spirometry, hypoxaemia or hypoventilation when compared to placebo in either sitting or prone maximal restraint position.[36] In another study on clinical toxicity of OC, in Kansas, Watson *et al.* reported on 81 emergency department patients who had been investigated after exposure to OC. Ocular burning and redness were the most common presenting symptoms. None of the patients required hospitalization due to OC toxicity. Corneal abrasions and respiratory symptoms occurred in seven and six patients, respectively.[37] Reilly and coworkers observed variability among capsaicinoid-products obtained from different manufacturers as well as from different product lots from the same manufacturer indicating that commercial pepper products are not standardized for capsaicinoid content. They concluded that variability in the capsaicinoid concentrations in oleoresin capsicum-based self-defence weapons could alter potency and ultimately jeopardize the safety and health of users and assailants.[38]

In case of death after OC exposure, a thorough autopsy, with ancillary investigations, including complete histology and toxicological analysis with assessment of the circumstances and symptomatology, is necessary to assess whether the exposure to OC spray has been causative, contributory, or unrelated to death.

On other occasions, the offender may threaten police officers with a knife, gun or blunt weapon, and the police have to subdue him either by sheer physical force – truncheons or riot sticks – or by the use of firearms.

The most common event is the arrest of a drunken offender and this poses extra problems, discussed below. Other drugs, such as cocaine, cannabis, amphetamine and hallucinogens, rather than opiates such as morphine, heroin and barbiturates, may also be involved.

The physical overpowering of a suspected offender poses definite risks to health and life, and has been the subject of numerous controversial enquiries and litigation in many countries. The police usually outnumber the offender, sometimes by a considerable margin, but even a one-to-one struggle can be dangerous for either party. The following risks exist, though the list is by no means comprehensive.

- Traumatic asphyxia may occur where several policemen fall upon a resisting subject to overpower him. The author (BK) has dealt with several deaths where a number of large police officers piled on top of a prisoner fighting maniacally, to apply handcuffs. When they got up, the man was not breathing and died in hospital shortly afterwards. Death was caused by traumatic asphyxia, the weight of the officers on top of him causing chest compression and prevention of respiratory movements. The appearances are described in Chapter 14.
- Arm-locks or neck-holds applied by police officers to resisting persons are other causes of deaths during arrest. These have been particularly notorious in the USA, where police officers have been trained to apply neck-holds as a form of restraint, but similar deaths have been seen elsewhere. The arm-lock is applied either from behind or with the head of the offender tucked under the police officer's arm against his waist. The dangers are compression of the front or sides of the neck, and death can occur either from reflex cardiac arrest or cerebral ischaemia during carotid compression, or asphyxia from airway obstruction, though the latter is unlikely as the sole mechanism. According to American writers such as Reay and Eisele, there are two types of neck-hold – the 'bar arm control' and the 'carotid sleeper'.[39,40] The former is alleged to be more dangerous; the officer's forearm is pulled across the front of the larynx to occlude the airway. The carotid sleeper uses the two sides of the 'V' formed by the flexed upper and lower arm to compress the carotids and produce transient cerebral ischaemia. Both varieties are dangerous, however, as there is the ever-present hazard of reflex cardiac arrest from vagal stimulation from the carotid sinus and sheath, as well as the potential danger of neck traction and hyperextension causing subarachnoid haemorrhage from vertebrobasilar artery damage.
- Postural (positional) asphyxia has been reported to have caused sudden deaths in persons after the use of the 'hogtie', 'hobble' or prone maximal restraint and even in situations where a person has been placed in a prone position in the rear compartment of a police car. In experiments with healthy subjects, the restraint position resulted in a restrictive pulmonary function pattern but did not cause clinically relevant changes in oxygenation or ventilation.[41–43] It has been postulated that the hogtie restraint position by itself does not cause respiratory compromise to the point of asphyxiation but other factors, e.g. acute intoxication by alcohol or drugs, are responsible for the sudden deaths of individuals placed in this position. Pollanen *et al.* reviewed the records of 21 cases of unexpected death in people with excited delirium analyzing eyewitness testimony, findings during post-mortem examinations, clinical history, toxicological data and other official documents describing the events surrounding the deaths. In all 21 cases of unexpected death associated with excited delirium, the deaths were associated with restraint, with the person either in a prone position (18 people [86%]) or subjected to pressure on the neck (3 [14%]). All of those who died had suddenly lapsed into tranquillity shortly after being restrained. Eighteen people (86%) were in police custody when they died. Four (19 per cent) had been sprayed with oleoresin capsicum, and heart disease was found in another four at autopsy. The blood level of cocaine in those whose excited delirium was cocaine induced was similar to levels found in recreational cocaine users and lower than levels found in people who died from cocaine intoxication. The authors concluded that restraint may contribute to the death of people in states of excited delirium, and recommended further studies to test this hypothesis; they also drew attention to the potential for the unexpected death of people in states of excited delirium who are restrained in the prone position or with a neck hold.[44]
- Blunt injury may occur from the use of fist, arm or leg – or the use of a weapon such as a truncheon, riot stick or pistol butt. During a struggle, usually with one or more police officers who are attempting to subdue a fighting offender, injuries may be received by either side. All types of blunt injury may be sustained, some potentially fatal and these are discussed in Chapter 4. Head injuries may

occur during a scuffle from falls either against the ground, or against a wall or other obstruction. A heavy punch in the face may cause nasopharyngeal bleeding that can block the air passages, especially in a person affected by alcohol. A blow on the side of the neck can cause reflex cardiac arrest or a subarachnoid haemorrhage from vertebrobasilar vascular damage.

A backward blow from the point of an elbow can be damaging, if it strikes the face, neck or abdomen. Kicking and stamping are unusual, but not unknown, in custodial deaths. A blow in the abdomen can also be serious if delivered with sufficient force. Though in an adult a fist blow is not very likely to cause serious harm, it can in a slighter young person. The use of the elbow, knee or a head butt can deliver extreme force, especially from a fit, muscular police officer, as well as from an offender.

The author (BK) has seen fatal intraperitoneal bleeding amounting to three litres in a drunken male arrested after a scuffle with two police officers, in which there were allegations that one struck or fell on the offender with his knee. Several hours later the prisoner collapsed and at autopsy there were several large tears in the mesentery.

- Alcohol is a frequent cause of death in custody. Not only is it the major factor in provoking aggression and violent resistance, with the consequences mentioned above, but it can have other effects which lead to death while in the care of the police. Acute alcoholic poisoning, described more fully in Chapter 28, may lead to death while the victim is thought to be ‘sleeping it off’ in a police cell. When blood alcohol levels rise to above 350 mg/100 ml there is an increasing risk of coma and central respiratory depression. Although most responsible police forces have standing orders about placing drunken prisoners in the semiprone position and observing them at frequent intervals, a quiet drunk may still slip into irreversible coma and respiratory arrest.

At lower blood alcohol levels there is still the risk of aspiration of vomit and choking on gastric contents. Though drunken prisoners are placed in the safest posture for drainage, they can still vomit and choke when unobserved, between visits by the often busy police station officers. At autopsy, caution must be observed before ascribing death to aspiration of vomit, as this is a common agonal phenomenon in deaths from other causes. Where an otherwise healthy person dies with a high blood alcohol concentration in these circumstances, however, gross blocking of the trachea and bronchi with vomit forms one of the most convincing arguments for acceptance of aspiration as the cause of death if no other factors can be identified.

Alcohol also contributes to accidents during custody, especially head injuries, which come about because of falls to the ground, falls down steps and stairs, and being run over by traffic, as a result of the ataxia and inco-ordination of the drunken state. Falls onto a hard surface are often on the occiput and the frequent finding of frontal and temporal contrecoup brain damage at autopsy is good evidence of a deceleration injury rather than an assault with a weapon.

Some falls may occur during custody or in transit from the site of arrest to the police station – others have happened before arrest, but the ill-effects and death may become manifest during the stay in the police cell, when the police are often blamed either for allowing or causing the injury – or for not summoning or providing urgent medical attention. Drugs, especially those causing excitement, such as amphetamine, cocaine or hallucinogens, may also lead to physical damage, but alcohol remains by far the most common.

Drugs are commonly available within prisons and overdose or hypersensitivity deaths are occasionally seen among prisoners, as they are in the outside world.

- Suicide in custody is not uncommon, and often leads to accusations and recriminations from the relatives over lack of supervision. There has recently been a spate of such deaths in Britain, especially among young offenders on remand awaiting trial. It is such a well-recognized hazard of custody that most police forces deprive the prisoner of any objects, such as belts, braces, cord or even bootlaces, that could be used to hang himself in his cell. In addition, the police cell may be specifically designed to avoid any convenient suspension points, such as hooks, bars or even internal door handles. In spite of these precautions, prisoners regularly manage to find some means of killing themselves. Strips of bedding material, sleeves of clothing and handkerchiefs have all been used for self-suspension. As described in Chapter 14, hanging can be successfully accomplished by traction on the neck at low levels and need not occur from high suspension points, so prisoners have killed themselves by attaching ligatures to bed-heads, chairs and other unlikely objects in the cell (Figs 10.12, 10.13).



Figure 10.12 Suicidal hanging in a prison cell. This is an infrequent but regular tragedy, which, in spite of strenuous efforts by prison officers and designers of cells, occurs because of the determination of the prisoner to defeat the safeguards. The belt used as ligature has been removed and lies on the bed.



Figure 10.13 Satanism- and 'black'witchcraft-associated tattoos (inverted pentagram) and self-inflicted injuries (inverted crosses symbolising mockery and rejection of the Christian cross) of a prison inmate who wrote an inscription on the wall of the prison cell using his own blood before hanging himself (see Fig. 10.14).



Figure 10.14 Inscription on the wall of a prison cell written by the inmate shown in Fig. 10.13 using his own blood from self-inflicted injuries before hanging himself.

Accusations that apparent suicidal hangings were in reality homicides by the custodians can usually be resolved by the autopsy showing no signs of bruising, abrasions or a struggle. It would seem impossible to hang a conscious person against his will without leaving some signs of restraint. The proposition that the hanging was a ligature strangulation is usually disproved by the rising angle of the ligature mark, which most commonly sets under the angles of the jaw and has a defect in the skin mark where the suspension point pulls the ligature away from the surface. A homicidal strangulation usually encircles the neck and a cross-over point is often seen. The level is lower, nearer the horizontal (Chapter 14).

Where a true hanging mark is caused by a ligature with a slip-knot, there may also be a full circle of skin abrasion and compression. If the suspension point is low, as might happen in a cell using a doorknob or a bed-frame, then the direction of pull can be oblique. If the body also leans over against the direction of pull, the resultant mark can be virtually horizontal and, unless the situation is fully assessed – preferably by a visit to the scene with the body *in situ* – confusion can occur, as with the controversy over the death of Rudolph Hess in 1988, while an inmate in Berlin's Spandau prison.

- Death may be from purely natural causes, usually cardiovascular in origin, which happened to have occurred during detention. It must be admitted, though it is almost impossible to provide objective proof, that the emotional and sometimes physical upset of being arrested and confined may have affected the blood pressure and heart rate sufficiently, by an adrenaline response, to have precipitated an acute cardiac crisis in the presence of severe pre-existing disease.

  The presence of diabetes, epilepsy, asthma or other diseases that can potentially cause sudden or unexpected death should be sought by medical history and autopsy appearances (Chapter 25).

Human rights organizations

Amnesty International UK
17–25 New Inn Yard The Human Rights Action Centre London EC2A 3EA GB
Email: sct@amnesty.org.uk
Web: http://amnesty.org/

Asia Pacific Forum of National Human Rights Institutions
GPO Box 5218
Sydney NSW 2001, Australia
Email: apf@asiapacificforum.net
Web: www.asiapacificforum.net

Association for the Prevention of Torture
Route de Ferney 10
PO Box 2267
CH-1211 Geneva 2, Switzerland
Email: apt@apt.ch
Web: www.apt.ch

Office of the United Nations (UN) High Commissioner for Human Rights
Palais des Nations
CH-1211 Geneva 10, Switzerland
Email: nationalinstitutions@ohchr.org
Web: http://www.ohchr.org/EN/Pages/WelcomePage.aspx

Office of the Commissioner for Human Rights, Council of Europe (COE)
F-67075 Strasbourg Cedex, France
Email: commissioner@coe.int
Web: http:// http://www.coe.int/en/web/commissioner/home

Medical Foundation for the Care of Victims of Torture
111 Isledon Road, London N7 7JW
Web: http://www.freedomfromtorture.org/

Physicians for Human Rights (PHR) National Office
Physicians for Human Rights
2 Arrow Street Suite 301
Cambridge, MA 02138
Web: http://physiciansforhumanrights.org/

References

1. Amnesty International. *Amnesty International Report 2001*. London: Amnesty International, 2001.
2. Amnesty International. *Amnesty International Report 2012*. London: Amnesty International, 2012.
3. Hougen HP. Physical and psychological sequelae to torture. A controlled clinical study of exiled asylum applicants. *Forensic Sci Int* 1988;39(1):5–11.
4. Moisander PA, Edston E. Torture and its sequel – a comparison between victims from six countries. *Forensic Sci Int* 2003;137(2–3):133–40.
5. Sanders J, Schuman MW, Marbella AM. The epidemiology of torture: a case series of 58 survivors of torture. *Forensic Sci Int* 2009;189(1–3):e1–7.
6. Sfakianakis GN, *et al*. The value of bone scanning in the early recognition of deliberate child abuse. *J Nucl Med* 1979; 20(6):675.
7. Haase GM, *et al*. The value of radionuclide bone scanning in the early recognition of deliberate child abuse. *J Trauma* 1980;20(10):873–5.
8. Lök V, *et al*. Bone scintigraphy as clue to previous torture. *Lancet* 1991;337(8745):846–7.
9. Mirzaei S, *et al*. Bone scintigraphy in screening of torture survivors. *Lancet* 1998;352(9132):949–51.
10. Tunca M, Lök V. Bone scintigraphy in screening of torture survivors. *Lancet* 1998;352(9143):1859.
11. Altun G, Durmus-Altun G. Confirmation of alleged falanga torture by bone scintigraphy – case report. *Int J Legal Med* 2003;117(6):365–6.
12. Peel M. History of torture. In: Jason PJ (ed). *Encyclopedia of Forensic and Legal Medicine*, Oxford: Elsevier, 2005, pp. 520–4.
13. Barber B, Cote DW, Liu R. Electric shock ear torture: a rare cause of tympanic membrane perforation and mixed hearing loss. *J Otolaryngol Head Neck Surg* 2011;40(3):E22–5.
14. Danielsen L, *et al*. Electrical and thermal injuries in pig skin—evaluated and compared by light microscopy. *Forensic Sci Int* 1978;12(3):211–25.
15. Thomsen HK, *et al*. Early epidermal changes in heat- and electrically injured pig skin. II. An electron microscopic study. *Forensic Sci Int* 1981;17(2):145–52.
16. Thomsen HK, *et al*. Early epidermal changes in heat- and electrically injured pig skin. I. A light microscopic study. *Forensic Sci Int* 1981;17(2):133–43.
17. Karlsmark T, *et al*. Tracing the use of torture: electrically induced calcification of collagen in pig skin. *Nature* 1983;301(5895):75–8.
18. Karlsmark T, *et al*. Tracing the use of electrical torture. *Am J Forensic Med Pathol* 1984;5(4):333–7.

19 Karlsmark T, *et al*. Immediate dermal changes in pig skin after exposure to moderate amounts of heat and electrical energy. *J Invest Dermatol* 1986;87(4):528–32.

20 Karlsmark T, *et al*. The occurrence of calcium salt deposition on dermal collagen fibres following electrical injury to porcine skin. *Forensic Sci Int* 1988;39(3):245–55.

21 Karlsmark, T., *et al*., *Electrically-induced collagen calcification in pig skin. A histopathologic and histochemical study.* Forensic Sci Int, 1988;39(2):163–74.

22 Karlsmark T, *et al*. The effect of sodium hydroxide and hydrochloric acid on pig dermis. A light microscopic study. *Forensic Sci Int* 1988;39(3):227–33.

23 Karlsmark T, *et al*. Ultrastructural changes in dermal pig skin after exposure to heat and electric energy and acid and basic solutions. *Forensic Sci Int* 1988;39(3):235–43.

24 Karlsmark T, *et al*. The morphogenesis of electrically and heat-induced dermal changes in pig skin. *Forensic Sci Int* 1988;39(2):175–88.

25 Karlsmark T. Electrically induced dermal changes. A morphological study of porcine skin after transfer of low-moderate amounts of electrical energy. *Dan Med Bull* 1990;37(6):507–20.

26 Danielsen L, *et al*. Diagnosis of electrical skin injuries. A review and a description of a case. *Am J Forensic Med Pathol* 1991;12(3):222–6.

27 Forrest D, *et al*. A guide to writing medical reports on survivors of torture. *Forensic Sci Int* 1995;76(1):69–75.

28 United Nations (UN). *Istanbul Protocol: Manual of the Effective Investigation and Documentation of Torture and Other Cruel, Inhuman or Degrading Treatment or Punishment*, in *Professional Training Series No. 8/Rev. 1*. New York and Geneva: Office of the United Nations High Commissioner of Human Rights, 2004, p. 76.

29 Brogdon BG, Vogel H, McDowell JD. *A Radiologic Atlas of Abuse, Torture, Terrorism, and Inflicted Trauma*. Boca Raton, London: CRC Press, 2003.

30 Özkalipci Ö, *et al*. *Atlas of Torture: Use of Medical and Diagnostic Examination Results in Medical Assessment of Torture*, 1st edn. Ankara: Human Rights Foundation of Turkey, 2010.

31 Snow CC, *et al*. The investigation of the human remains of the 'disappeared' in Argentina. *Am J Forensic Med Pathol* 1984;5(4):297–9.

32 Primorac D, *et al*. Identification of war victims from mass graves in Croatia, Bosnia, and Herzegovina by use of standard forensic methods and DNA typing. *J Forensic Sci* 1996;41(5):891–4.

33 Rainio J, Lalu K, Penttila A. Independent forensic autopsies in an armed conflict: investigation of the victims from Racak, Kosovo. *Forensic Sci Int* 2001;116(2–3):171–85.

34 Sprogoe-Jakobsen S, *et al*. Mobile autopsy teams in the investigation of war crimes in Kosovo 1999. *J Forensic Sci* 2001;46(6):1392–6.

35 Klonowski EE, Soltyszewski I. [Process of exhumation and identification of victims of the 1992–1995 war in the territory of Bosnia and Herzegovina]. *Arch Med Sadowej Kryminol* 2009;**59**(3):225–31.

36 Chan TC, *et al*. The effect of oleoresin capsicum 'pepper' spray inhalation on respiratory function. *J Forensic Sci* 2002;47(2):299–304.

37 Watson WA, Stremel KR, Westdorp EJ. Oleoresin capsicum (Cap-Stun) toxicity from aerosol exposure. *Ann Pharmacother* 1996;30(7–8):733–5.

38 Reilly CA, Crouch CD, Yost GS. Quantitative analysis of capsaicinoids in fresh peppers, oleoresin capsicum and pepper spray products. *J Forensic Sci* 2001;46(3):502–9.

39 Reay DT, Eisele JW. Death from law enforcement neck holds. *Am J Forensic Med Pathol* 1982;3(3):253–8.

40 Reay DT, Eisele JW. Law enforcement neck holds. *Am J Forensic Med Pathol* 1986;7(2):177.

41 Chan TC, Vilke GM, Neuman T. Reexamination of custody restraint position and positional asphyxia. *Am J Forensic Med Pathol* 1998;19(3):201–5.

42 Chan TC, *et al*. Weight force during prone restraint and respiratory function. *Am J Forensic Med Pathol* 2004;25(3):185–9.

43 Michalewicz BA, *et al*. Ventilatory and metabolic demands during aggressive physical restraint in healthy adults. *J Forensic Sci* 2007;52(1):171–5.

44 Pollanen MS, *et al*. Unexpected death related to restraint for excited delirium: a retrospective study of deaths in police custody and in the community. *CMAJ* 1998;158(12):1603–7.

CHAPTER 11

Burns and Scalds

- Heat injury
- Classification of the severity of burns
- Moist thermal damage – scalds
- Burns from dry heat
- Burns and sudden death associated with bathing
- Gross appearances at autopsy
- Spurious ‘wounds’ in burns
- Ante-mortem versus post-mortem burns
- Fumes and fires
- Inhalation of soot
- Atypical localized burning and ‘spontaneous combustion’
- References

Damage to the tissues arising from the application of heat is commonly encountered in forensic pathology and sometimes provides a challenging problem in the distinction between ante-mortem and post-mortem burning, which may have serious criminal aspects.

Heat injury

This may arise following a defect in body temperature control or, more commonly, from the external application of heat. Mammalian tissues can survive only within a relatively narrow range of temperatures, approximately 20–44°C.

When external heat is applied, the extent of damage depends upon:

- the applied temperature
- the ability of the body surface to conduct away the excess heat
- the time for which the heat is applied.

The temperature/time relationship is important, for it is sometimes forgotten that relatively low temperatures, even as little as 44°C, can cause damage if sustained long enough. This is attested by many negligence lawsuits concerning unconscious patients burned by forgotten hot-water bottles.

The degrees of thermal damage were investigated by Moritz and Henriques, who found that the lowest temperature that would cause damage was 44°C, though it required no fewer than 5 hours before a burn appeared. Only 3 seconds was needed, however, if the object was at 60°C.[1]

Radiant heat can also cause severe damage, as is obvious from overexposure to sunlight or artificial sunlamps. The long-term effects also include malignant changes, now more important because pollution-induced changes in the stratosphere are allowing more ultraviolet radiation to reach the earth’s surface. In forensic practice it is more often seen when an old or disabled person falls unconscious within close range of a gas, electric or coal fire, those areas of skin unprotected by clothing becoming burned, often to a blistered state. It can be difficult or impossible to tell how much of such a condition is ante-mortem or post-mortem, as the presence of reddening and blistering cannot always be depended on as criteria of vital infliction. Mottled pigmentation and reddening of the fronts of the legs (erythema ab igne) is a familiar sign in those addicted to sitting before an open fire.

Classification of the severity of burns

Already Guilhelmus Fabricius Hildanus (Wilhelm Fabry von Hilden; 1560–1634) pointed out in his book *‘De combustionibus’* (Basel, 1607) that the classification of burns should be a guide to treatment and he was the first to suggest a three-stage classification for burns and their treatment. Several modifications of classifications have been proposed since then, among others, the four-stage classification by Heister, the three-stage classification by Boyer, the six-stage classification of Dupuytren, the three-stage classification by Hebra and later by Wilson; all of them indicating the depth of tissue implicated in the injury.[2–8]

- **First degree:** erythema and blistering without loss of dermis. There is capillary dilatation and transudation of fluid into the tissues, causing swelling. A split may occur in the epidermis to form a blister with an upper cap of pale skin enclosing fluid, surrounded by a zone of hyperaemia. If small (<1 cm) this blister may resorb, otherwise it will burst, leaving a reddened base. A first-degree burn will heal without scarring.
- **Second degree:** destruction of the full thickness of skin. The epidermis is coagulated or charred, and a central zone of necrotic tissue is surrounded by first-degree burns or a zone of hyperaemia, or both. The central necrosis sloughs in due course and the epidermis grows in from the margins. The injury cannot heal without scarring, which usually contracts during the healing process, causing puckering and distortion of the surface.
- **Third degree:** destruction of deeper tissues below the skin. This can be of any severity, from damage to subcutaneous fat to loss of muscle, bone and even a whole limb.



Figure 11.1 The ‘Rule of Nines’ for calculating the area burned. It does not apply to infants whose body proportions are different from adults.

According to Pruitt *et al.* the importance of extent of injury in determining burn outcome was already recognized by Holmes in 1860.[9] The area involved, expressed as percentage of total body surface area (TBSA), is visually estimated by subdividing the body surface into clearly demarcated areas according to the ‘Rule of Nines’, introduced by Berkow in 1924 and later modified by Wallace (Fig. 11.1). To avoid certain systematic errors that could occur when Berkow’s table for adults is applied to children, Lund and Browder constructed a new table and diagram to avoid these and other systematic errors.[10] Burns covering more than 15 per cent of TBSA in adults and more than 10 per cent in children warrant fluid resuscitation. Clinically the depth of burn injury is categorized as superficial, superficial dermal, deep dermal and full thickness.[11] For the pathologist a more precise anatomical description of the areas burned is essential for his autopsy report.[12,13]

Small burns rarely cause deaths, but as burn size increases mortality rises. A large area involved may be more dangerous to life than a deeper, more localized burn. The mortality rates vary a lot depending on the burn size, prior condition of the injured person, age, possible concomitant inhalation injury and the effectiveness of treatment. During the past three decades several factors have contributed to better survival after burn injury: better control of wound infection through new antibiotics and better infection control techniques, early wound excision, improved grafting techniques and establishment of specialized burn centres.[14]

Moist thermal damage – scalds

A ‘scald’ refers to tissue damage from hot liquids, usually water. Other hot fluids include oils, molten rubber, other liquid chemicals and steam. Molten metals are usually at such a high temperature that the results are similar to dry burns. The water scald is a common domestic accident, especially to children and old people, that group at the extremes of life who are vulnerable to so many types of accident (Fig. 11.2).

A scald, unless from some superheated oil, does not cause charring, carbonization or singeing of surface hairs, as does dry heat. It resembles a first-degree dry burn



Figure 11.2 First- and second-degree burns on the right thigh and scrotum of a 5-year-old diabetic child, who had been treated by a 'quack', who had promised the parents to cure the child by hot baths. Death was caused by the untreated diabetes.



Figure 11.3 Scalds or wet burns in a child accidentally left in a hot bath while her mother went to answer the telephone. This illustrates that time, as well as temperature, is a factor in causing heat damage to skin. The child died some days later from an intercurrent chest infection.

(see later) in that there is reddening, desquamation and blistering, but the shape of the scald tends to be different. There is usually a sharply demarcated edge, corresponding to the limits of contact of the fluid (Fig. 11.3). If due to immersion in hot water, such as a bath, there will be a horizontal fluid level, though this may be made irregular by splashing. When tipped or splashed, the hot liquid runs under gravity so that trickle patterns may be seen, which may enable the medical examiner to determine the posture of the victim when scalded.

The intensely red base of a severe scald may at first be covered by wrinkled, macerated epidermis. The scalded skin may swell and exude serum. Infection may supervene but where the burns are extensive, death usually results from the systemic effects of shock, fluid and electrolyte disturbance and secondary chest infections. The severity of a scald depends on the duration of contact with the skin, as well as the temperature. When hot water is splashed, tipped or thrown, it has only a momentary contact, falling away under gravity. The large surface area allows rapid cooling, so damage must occur in a short time, which necessitates the temperature being high if severe damage is to be caused. Often the water is boiling, especially in the kitchen accidents that, sadly, occur to children with such regularity. The interposition of clothing may have two opposite effects; it may protect the underlying skin from the hot liquid, especially if poorly permeable, but it may also hold the hot liquid in contact with the skin for a longer time, especially if the fabric is absorbent.

The appearance of scalds may resemble dry burns except for the distribution and the fact that, if due to immersion, the severity of the skin damage is usually uniform over the whole of the burnt area up to the sharply demarcated margin. When hot or boiling water has been poured or splashed onto the body, the worst scalds will be at the area of initial contact where the fluid was hottest, but decrease in severity as the cooling liquid runs away. In children who pull containers of hot liquid down on themselves, the scalds tend to be on the face, neck, chest and arms, with 'shadow areas' of undamaged skin in the axillae and on the back.

Burns from dry heat

More common than scalds, burns due to dry heat may be caused by high temperature applied to the body surface by conduction or radiation. Convection is merely a variant of conduction in this respect; as hot gas impinges on the surface, the molecules transfer their high energy in a similar fashion to the direct contact of a hot solid (Fig. 11.4).



Figure 11.4 A second degree burn in a house fire victim. Note the pink colouration of the hypostasis due to carbon monoxide poisoning and the vertical pale pressure marks produced by clothing.



Figure 11.5 Haematoxylin-eosin-stained histological section of a second degree burn showing a blister filled with eosinophilic liquid covered by a thin layer of epidermis.

Radiation causes damage through the conversion of infrared frequencies into thermal heat on absorption at the skin interface. As with scalds, the tissue damage is a function of temperature and time. A warm water-pipe will cause a burn if left long enough in contact with the same area of skin, but the vast majority of dry burns are due to high temperatures acting for a shorter time.

Where the time is extended beyond that needed for initial burning, the tissues may be charred, carbonized or completely destroyed, as in cremation.

The severity of dry burns

The Wilson classification of severity of burns is given above, with three degrees according to the depth of tissue damage:[7]

- Erythema leads to redness and swelling of the skin. Blisters may form either within the thickness of the epidermis or at the epidermal–dermal junction (Fig. 11.5).
- Destruction of the full thickness of the skin, which may be total or incomplete. If epidermal structures survive, such as the deeper parts of hair follicles, then epithelialization may occur from islands within the burned area. If not, slow coverage with more probability of extensive scarring will occur from invasion of epidermis at the periphery.
- Destruction of subcutaneous tissues, such as fat, muscle and even bone, is the most serious grade of burning, though, as mentioned elsewhere, it may be less dangerous to life than larger areas of more superficial burns.

Burns and sudden death associated with bathing

Voluntary exposure to heat during recreational activities is becoming increasingly common, as bathing in saunas or other types of hot baths has become more popular due to the recognition of the health benefits.[15,16] Burns associated with sauna bathing are rare and can occur by direct contact with the heat source, i.e. stove or flames in the case of a stove heated with a wood fire, hot steam, water or prolonged exposure to hot dry air, the latter of which is usually associated with unconsciousness and can be potentially fatal due to the risk of rhabdomyolysis.[17,18]

Larger series of deaths associated with sauna bathing have been reported only from Finland and Sweden.[19–23] Eren *et al.* reported on 15 sudden or suspicious deaths in the Turkish hot bath (hamam).[24] The most obvious explanation lies probably in the fact that elsewhere bathing usually takes place in public baths where there are usually other people around to help if someone is suddenly taken ill, whereas in Finland, the number of private saunas is quite high. Most of the new family houses and even small apartments are built with saunas and, according to a recent estimate, the total number of saunas in 2010 was over 2 million for a population 5.46 million (as of 2014). Most Finns go regularly to sauna, at least once a week on average, although some go almost daily, hence deaths are bound to take place in sauna. The great majority of these deaths are reported to the police for a cause of death investigation and they are practically always subjected

Table 11.1 Sauna death surveys in the literature

Country	Period	N Total/Included	Gender: M/F (%)	BAC (+)	Ref.
Finland	1976–1983	158	127/31 (80.4/19.6)	47.5%	19
Finland	1970–1986	230/228	184/44 (80.7/19.3)	84.2%	20
Finland	1990–2002	393	271/122 (69/31)	50%	21
Sweden	1992–2003	96/77	63/14 (82//18)	71%	22
Finland	1986–1995	690/544	402/142 (74/26)	56.6%	23

BAC +: blood alcohol content positive.

to a medico-legal autopsy. Between 1998 and 2010 there were altogether 475 deaths (36.5±5/y) classified as deaths in sauna (W92 = exposure to excessive heat of man-made origin; ICD10), of which 76 per cent were male and 24 per cent female. In almost two-thirds (74 per cent) of the deaths the subjects were under the influence of alcohol (80 per cent of male and 56 per cent of female).[25]

Earlier autopsy surveys have attributed sauna deaths mainly to ischaemic heart disease, heat exposure and alcohol.[19–22] Each one of these causes is, however, problematic as to the reliability of the diagnosis. The diagnosis of sudden cardiac death is, in most cases, a diagnosis per exclusion and presupposes the use of ancillary investigations, such as microscopy and forensic toxicology, to rule out other possible causes of death. The estimation of the significance of pre-mortem heat exposure as cause of death is also problematic because there are no specific diagnostic markers for hyperthermia. Additionally, the diagnostic accuracy has been hampered in all the cited surveys by the fact that many of the victims have been found dead in the steam room hours or days post-mortem showing varying grades of decomposition. Alcohol appears to be the most important single contributing factor in the majority of deaths associated with sauna bathing in Finland. The presence of diseases, such as coronary heart disease, and exposure to heat may have contributed to these deaths but their significance is difficult to determine due to above-mentioned diagnostic problems and post-mortem changes.[23]

Table 11.2 shows a compilation of alcohol-associated deaths in the sauna from the survey by Saukko where the pathologist performing the autopsy has classified the underlying cause of death (Ic) due to natural causes, heat exposure or alcohol intoxication. Considerable overlapping of alcohol concentrations and the presence of toxic alcohol concentrations in all the three groups raises the question as to how it has been possible to differentiate one from the other, particularly as most of the victims have been found dead with a significant delay, i.e. hours or even days after death has occurred. This illustrates the difficulties associated with cause of death studies without characteristic pathology, as in the case of hyperthermia. When the diagnosis is based on circumstantial evidence and exclusion of other causes of death the quality of autopsy becomes of paramount importance. Considering that in this survey comprising altogether 544 deaths in the sauna (when the subjects without alcohol were included), toxicology was taken in only one-third of the cases and histology in less than one-half of them, it is obvious that the quality of most autopsies in this series has not been satisfactory.

Gross appearances at autopsy

The body may present a wide range of damage from mere reddening over wide areas to almost total cremation, in which a search may have to be made at the scene of the fire to collect or even discover the remnants.

Usually, where leathery coagulation or charring has not occurred, ante-mortem burns will be reddened and often blistered. The latter have a marginal red zone of variable width, usually 5–20 mm across. Blisters may be present either in the main burn or as islands beyond the periphery. Most ante-mortem blisters will have a bright red base when burst and an erythematous areola. The whole of the burned area may form one large blister or be a coalescence of blisters. These are usually collapsed at autopsy, so that sheets and shreds of white epidermis lie across an angry red base.

Where the burns are more severe, the skin may be stiffened, yellow–brown and leathery, a half-way stage to actual carbonization. Drying after death of areas that were weeping serum leads to a stiff, parchment-like surface. Post-mortem heating and deposition of smoke may mimic or overlie the ante-mortem appearances, the surface often being blackened by soot deposition.

Table 11.2 Mean blood (BAC) and urine (UAC) alcohol concentrations in medico-legally autopsied alcohol-associated deaths in the sauna in Finland between 1.1.1986–19.5.1995

Cause of death	N (309)	Age mean (range)	BAC (per mille) mean (range)	UAC (per mille) mean (range)
Natural causes	91	63.2 (38–82)	1.73 (0.20–3.3)	2.6 (0.10–4.2)
Heat exposure	150	53.7 (25–81)	2.11 (0.29–3.9)	3.15 (0.54–4.8)
Alcohol intoxication	68	50.7 (20–80)	2.8 (1.3–7.4)	3.85 (1.9–5.0)

Modified from Saukko.[23]



Figure 11.6 Body of a 42-year-old male found dead in the steam room approximately 8 hours after having gone alone to sauna. Blood alcohol concentration 2.3 per mille; urine alcohol concentration 3.2 per mille. Due to the long heat exposure, a 'parboiled' appearance with patchy loss of epidermis due to skin slippage was found when the body was recovered and showing post-mortem drying of the lesions.



Figure 11.7 Second- and third-degree burns and singeing of hair on a suicide who doused himself with petrol and set himself on fire.

Hair is singed or completely burnt away in severe burns (Fig. 11.7). In lesser degrees it may survive and the ends of the hairs may be 'clubbed'. Here the keratin melts at the distal end nearest the heat, then resolidifies on cooling, forming a terminal blob on the shaft like an unlit match. Eyelashes, eyebrows, pubic, axillary and general body hair may all suffer this scorching. Where skin has actually ignited, the subcutaneous fat acting as a fuel, black brittle masses will occupy the tissues merging into cooked, dry muscle beneath, which in turn grades into more moist and normal-looking soft tissue at greater depths. Beneath burns of any degree, the deeper tissues may be affected, especially muscle, which becomes pale, brownish and obviously 'part-cooked'. This is often a post-mortem phenomenon caused by the dead body remaining in a heated environment and such cooked muscle may extensively underlie normal skin, which shows no evidence of ante-mortem burning, especially if protected by clothing. It is the general high temperature of the environment over a relatively long period which produces this 'parboiled' appearance, similar to the cooking effect of a slow oven (Fig. 11.6).

Where heat has been intense and continuous, all soft tissue down to bone may be consumed and the bone itself may be blackened. The most extreme stage is conversion of the bone to brittle greyish-white splinters, sometimes with loss of skeletal structures, leading to absent feet, hands or limbs. It is rare for the whole body to be completely consumed, even in deliberate cremations, but only a fraction of the original body mass may remain, often almost inseparable from the burned surroundings. Where much smoke has been generated, as in most house fires, the skin will be discoloured where exposed. Sharply demarcated areas of soot deposition may coincide with burning from hot gas. Even the thinnest layer of clothing may protect completely from both these effects (Fig. 11.8).



Figure 11.8 Post-mortem smoke soiling and superficial burns on the leg of a house-fire victim who died of smoke inhalation. Note the complete protection of the skin, which had been covered only by a sock.

Muscle contractures are common where substantial heat has reached the body. This is almost always a post-mortem occurrence, as deep-heating effects sufficient to cook muscle are incompatible with life. The muscle becomes shortened by dehydration and protein denaturation. The flexors, being bulkier than the extensors, contract more and force the limbs into a position of general flexion, the so-called 'boxer's' or 'pugilistic' attitude (Figs 11.9, 11.10). Contraction of the paraspinal musculature often causes a marked opisthotonos. Froth, often pink-stained, may appear at the mouth and nostrils as a result of pulmonary oedema caused by heat irritation of the air passages and lungs. The tongue frequently protrudes and may be scorched.

Spurious 'wounds' in burns

Heated skin contracts markedly and splits often appear. This may lead inexperienced observers to suspect that ante-mortem wounds have been inflicted, the fire being used to cover up a criminal offence. These splits may be anywhere, but are especially seen over extensor surfaces and joints, as well on the head. Some, especially those at elbows and knees when the limbs are flexed across brittle skin, are caused by firemen handling the body during recovery (Figs 11.11, 11.13).

The possibility of true wounds being present must always be kept in mind, as many homicides have been concealed in fires. The false split will show no bleeding



Figure 11.9 Heat flexures of the limbs, part way towards the 'pugilistic attitude' formed when the arms are raised higher. The elbows, knees and wrists are strongly flexed because muscle contraction is stronger in the flexor groups. The victim was the captain of a Russian ship who set fire to his cabin during a bout of heavy drinking.



Figure 11.10 Charred body at the scene of a fire showing the 'pugilistic attitude' and post-mortem skin splits on the chest.



Figure 11.11 Post-mortem injuries caused by heat simulating head injuries. The fire service were concerned about an apparent preconflagration assault, but such skin splits are commonly seen as a result of heat contracture of the tissues. The scalp on the top of the head has been burned through and the skull is charred. Beneath this is a spurious 'heat haematoma', sometimes confused with a traumatic extradural haemorrhage.



Figure 11.12 Dead bodies in fires pose a problem for pathologists and investigators. Death was shown to have occurred after the fire began from soot in the lungs and carboxyhaemoglobin in the blood. There were no ante-mortem burns and there was a high blood alcohol concentration.



Figure 11.13 Post-mortem burns in a victim recovered from a house fire. Note the raised right arm caused by heat contractures. The left forearm has burnt up to the elbow and there is extensive skin splitting on the left brachium and shoulder area. The left side is charred but the pelvis has been better protected by clothing.

in the deeper tissues and its position is usually suggestive. The differentiation may be difficult or even impossible, however, especially when severe heat damage in the area makes examination of the underlying tissue impracticable.

The other major false lesion is the 'heat haematoma' in the extradural space. When severe heat is applied to the cranium, a mass of blood resembling a true extradural haematoma may form between the skull and the dura. This may arise either from venous sinuses or be virtually 'boiled' out of the diploic space in the skull through emissary venous channels. The blood is spongy from gas bubbles and tawny or chocolate brown. The exterior of the skull overlying the haematoma is usually charred and the scalp burnt away. If it is a purely post-mortem phenomenon, the heat haematoma will have a similar level of carboxyhaemoglobin to the blood, whereas if it was an ante-mortem lesion sustained before the fire began, it will be free from monoxide, as discussed in more detail below. Where the heat is intense the spurious haematoma may be outside a grossly shrunken dura, which compresses the brain into a cooked mass. The dura may split under the tension and allow brain tissue to ooze out into the large space within the cranium, where it may form a mass of frothy paste. These changes may be present without a haematoma, but the latter is often present. In the absence of a skull fracture, other than one due to heat, this haematoma should not be ascribed to trauma.[26,27]

Ante-mortem versus post-mortem burns

In severe conflagrations, either in buildings or vehicles, the terminal state of the body often does not reflect the condition at the time of death. Indeed, many deaths will have occurred before any heat reaches the body, death being caused by the inhalation of smoke. It may be difficult or impossible for the pathologist to determine the extent of ante-mortem damage if the ensuing fire later reaches the body and causes post-mortem burning. The exposed skin surface may be reddened in both ante-mortem and post-mortem burns, the classical distinction of a 'red flare' or 'vital reaction' being unsafe as an index of infliction before death. The author (BK) has seen several cases of undoubted post-mortem burns, one at least 30 minutes after fatal strangulation, where an extensive 'red flare' was caused during attempts at disposal of the body by fire.

Blisters can form post-mortem, but are pale yellow unless on scorched skin. There is rarely a red base or erythematous areola, though this sign cannot be depended upon absolutely. The contained fluid is thin and clear. Traditionally most authors claim that differentiation can be made between an ante-mortem and a post-mortem blister by an analysis for protein and chloride in the fluid. The blister formed in life is said to contain more protein and chlorides, but no absolute figures are offered and the authors have yet to meet a pathologist who does this as a routine. One suspects that the test is another of the apocryphal procedures that have been handed down from textbook to textbook without verification (Figs 11.14, 11.15).



Figure 11.14 It can be difficult or impossible to differentiate between ante-mortem and post-mortem burns when they are sustained near to the time of death. Here the blister with no erythema at the base could either be post-mortem or ante-mortem, as reddening of the margins and adjacent skin can occur for at least 1 hour after death. It is preferable to call doubtful lesions 'peri-mortal'.



Figure 11.15 Post-mortem burn on the arm and chest caused by a hot-water bottle being left over the heart in an attempt at resuscitation. The lesion is sharp-edged, there is no erythematous margin, and the surface is brown and leathery from post-mortem drying.

Most useful of all in fatalities is the presence of carbon monoxide in the circulating blood and carbon particles in the air passages and lungs, and this is dealt with in the section on inhalation of fumes (Fig. 11.12). They do not necessarily prove that any burns were ante-mortem, but that the victim was still alive when the fire was in progress, which is not the same conclusion. The extradural heat haematoma may be investigated in a different way to determine its time of origin. If it is a true traumatic lesion produced before the fire began, it should contain no carboxyhaemoglobin. A spurious heat haematoma is formed from blood that will contain carboxyhaemoglobin if the victim has absorbed this gas during the fire. It must be appreciated, however, as discussed below, that not all persons alive during a fire accumulate carboxyhaemoglobin in their blood.

If there is carboxyhaemoglobin absorption, then the heat haematoma will also yield it on analysis. The use of this test, again related in most classical texts, is, however, extremely limited.

Fumes and fires

The majority of fatal dry burns in civilian practice occur in conflagrations in buildings, rather than in vehicles or aircraft. In many of these tragedies death is not caused by burns, but to inhalation of fumes produced by the combustion of the building structure and contents. Indeed, most burns seen by forensic pathologists are post-mortem, either because the victim was already dead from smoke inhalation or because severe post-mortem burning obliterates the lesser degrees of burns present up to the moment of death.

Death from inhaling fumes may be caused in several ways:

- Thermal damage to the air passages and lungs from the direct effect of hot gases. At autopsy the tongue, pharynx and especially glottis may be scorched, lesser degrees causing a greyish-yellow blanching of the mucosa. The interior of the larynx, trachea and main bronchi may be thickened and blanched, or reddened and inflamed, if the temperature is too low actually to burn the lining. Heat effects on the pharynx and epiglottis can occur post-mortem through passive percolation of hot gas through the open mouth. The lungs usually respond to heat damage by marked pulmonary oedema, though this is often present in fire victims even when the inhalation of hot gas has been insufficient to cause visible damage to the bronchial tree (Fig. 11.16).



Figure 11.16 Larynx of a house-fire victim showing heat blanching of the epiglottis and glottal entrance from breathing hot gas. The lower cut end of the trachea shows copious soot-containing mucus, also indicating respiration during the fire.

- Carbon monoxide poisoning is an important aspect of most fires – indeed it is the major or even sole cause of death in many victims of conflagrations, especially in house fires. When any combustible material burns in air, most of the carbon in organic material, such as timber, fabric and furnishings, is converted to carbon dioxide. Carbon monoxide is also produced, however, and, where the access of oxygen is limited or exhausted by the ongoing combustion, larger volumes of the monoxide are produced. Slow, smouldering fires with little flame are likely to produce more monoxide, as with burning bedclothes and mattresses. At the other extreme, rapid flash fires with flames fanned by moving draughts and those involving volatile fuels, such as petrol or kerosene, produce relatively little monoxide – though much depends upon the free access of air.

In many house fires, where the seat of the fire is originally remote from the victim, death may occur from carbon monoxide poisoning long before the flames reach the body. A person may be asleep in an apartment or house, and die without ever waking if large volumes of monoxide creep through the rooms. Burns are often post-mortem in such cases and, where extensive charring occurs, the differentiation between ante-mortem and post-mortem damage may be impossible.

It is often a comfort for bereaved relatives to be told that their loved ones were either already dead or unconscious before the agony of burning reached them, and the pathologist may be able to emphasize this at any inquest or inquiry. Unfortunately, where the bodies are found in positions obviously indicating escape or concealment, such an explanation loses its conviction – though even then it may well be that coma from monoxide poisoning overtook them before burning began.

The pathology of carbon monoxide is dealt with in another section of this book, but it may be repeated here that the autopsy signs are primarily that of a cherry-pink colouration of the skin, blood and tissues. Where smoke staining or extensive charring has occurred, there may be little skin to examine, though there is usually some in a protected position under the body. The blood and tissues usually have the characteristic colour but, when the person is anaemic or exsanguinated, this may be hard to detect. A high saturation with monoxide is usually unmistakable at autopsy, though sometimes certain types of artificial light in the autopsy room, such as some fluorescent tubes, make the cherry-pink colour difficult to confirm. The colour may be better seen if blood is diluted with water against a white background, such as a porcelain autopsy table or sink. Nothing replaces laboratory analysis of a sample, however, and this must be done in every case of death from fire, irrespective of the subjective appearance of the skin, blood and tissues.

The saturation of haemoglobin with carbon monoxide varies greatly from one fatal case to another. Many variable factors exist such as the concentration in the atmosphere, the time of exposure and local changes in oxygen content. When carbon monoxide is the sole cause of death, a blood saturation of at least 40 per cent is required, except in old and debilitated persons where deaths have been reported at 25 per cent. Many fatalities will display 50–60 per cent saturation, though levels in general are less than in pure carbon monoxide poisoning, such as car exhaust suicides or industrial exposure, where concentrations of up to 80 per cent may occur. In fires, additional factors such as other toxic fumes and reduction of the atmospheric oxygen may operate, resulting in death at lower carboxyhaemoglobin concentrations.[28–31]

Yoshida *et al.* published data from 120 house-fire victims in Japan, in which only nine people had carboxyhaemoglobin (HbCO) concentrations below 10 per cent, the range being from 1 to 95 per cent saturation. Of 31 victims in whom cyanide analyses were made, two had high cyanide and low HbCO.[32]

The variability of monoxide poisoning may be illustrated by the fact that two bodies lying side by side in a burned house may have widely differing blood saturations – indeed, sometimes one victim may have a zero blood monoxide saturation. Children often have much lower levels than adults in the same situation, but even two adults may differ in their HbCO concentrations, the explanation being unclear. Local variations in draughts, levels above the floor and respiration rates may account for these anomalies.



Figure 11.17 The finding of a body in a burnt-out car is always suspicious, but is usually accidental or suicidal. Post-mortem imaging or radiography should always be carried out to exclude firearm injuries. Carboxyhaemoglobin levels are often low or even absent in a rapid flash gasoline fire; this makes the diagnosis of being alive during the fire difficult, especially when there may also be little soot to foul the air-passages.

Carbon monoxide in the blood is a valuable indicator that the victim was alive after the fire began. Where a dead body is disposed of by arson no absorption can take place, as the gas can gain entry only through the pulmonary interface. Thus the presence of more than a smoker's level of 5 per cent saturation of the blood with HbCO means that breathing occurred after the fire began. It is vital, however, to appreciate that the converse is not true. *The fact that a body in a fire does NOT have HbCO in the blood does NOT mean that they must have been dead before the fire began*. In a retrospective analysis of 286 fire deaths in Norway, Rogde and Olving found 28 individuals with negative HbCO, eight of whom had no soot in the respiratory tract. Seven of these were considered to have died from burns and one from gas produced in the fire.[33] The records of all forensic departments have examples of this occurrence and therefore it is illogical – and sometimes legally dangerous – to draw the unwarranted inference that such a victim must have been already dead before the fire began, however common the generalization may be. In rapid flash fires, especially where gasoline or kerosene are involved, the monoxide level is more likely to be low or even negative, than in the slower conflagration with restricted access of oxygen that occurs in a burning building (Fig. 11.17).[34]

Toxic substances in fumes

In recent years it has been appreciated that a number of toxic substances other than carbon monoxide may be present in the fumes from fires. Cyanides are predominant and the blood of fire victims may often be shown to have high levels of this toxic compound. Nitric oxide, phosgene and other more complex substances may be liberated, especially when modern plastic polymers are burned. Furnishings, upholstery, paints, lacquers, varnishes and actual structural components are increasingly made from polystyrene, polyurethane, polyvinyl and other plastic materials. These are particularly liable to generate toxic gases when ignited.[29,30,32,35–37]

Caution must be employed when interpreting the analysis of cadaver blood for cyanide, as this substance can be produced in significant concentration by post-mortem decomposition.[38–40] Post-mortem diffusion was considered to explain the high cyanide level in a homicide victim that had been burned after death wrapped in a plastic sheet.[41]

Particular care must be taken in preservation of samples, which should have fluoride added, and in ensuring there is no delay before analysis so that further decomposition is kept to a minimum. Where cyanides, oxides of nitrogen and other toxic substances are inhaled during a fire, carbon monoxide is inevitably absorbed as well. It then becomes difficult to apportion the relative blame for the death among these different toxic agents – and where there are also ante-mortem burns, the differentiation may be impossible. If the pathologist considers that he cannot identify any ante-mortem burns, then the most logical cause of death is 'inhalation of smoke'. If vital burns are present then, according to the circumstances, these can be given as the cause of death, with or without the addition of 'carbon monoxide or smoke inhalation'.

Inhalation of soot

As well as the inhalation of carbon monoxide, victims in a fire usually breathe in carbon particles present in the sooty smoke. Once again this is more pronounced in a building fire than a vehicle blaze, though there are many exceptions. The combustion of timber floors, roofs, furniture, and the fabric of furnishings and carpets produces large volumes of dense black smoke. Every pathologist attending the scene of a house fire is aware of the thick layer of soot than clings to every surface and may hang in fronds from the ceilings. It is little wonder that such material suspended in the air finds its way into the respiratory passages of the victims.



Figure 11.18 As small bronchus from a fire victim, showing histological evidence of soot deposition, together with desquamation of the epithelium and plugging with cellular debris.

As a marker of ante-mortem inhalation, it is almost as useful as carbon monoxide (Fig. 11.19). Soot particles may enter the open mouth of a corpse, stain the tongue and pharynx, and may even passively reach the glottis. No significant amount can pass the vocal cords and enter the trachea after death, however, so carbon in the lower respiratory tract is a certain indicator of breathing during the fire. Histological demonstration of soot in the more peripheral bronchi, out as far as the terminal bronchioles, is absolute proof of such respiratory function (Fig. 11.18). The carbon is usually mixed with mucus adherent to the tracheal and bronchial walls because of heat irritation of the mucosa. Often there is swallowed soot and mucus in the stomach, and again this is evidence of life during the smoky phase of the fire (Fig. 11.20).

Atypical localized burning and 'spontaneous combustion'

Some very strange instances of fatal burning occur and most experienced forensic pathologists have recollections of apparently inexplicable cases.

A human body may sometimes burn away almost completely, yet the surrounding fire damage is minimal. These almost invariably occur near a hearth or open fire-grate or chimney. The burning may be confined to the body, its clothing, and a narrow zone of floor or carpet. The author (BK) has seen a circumscribed hole burned through a hearthrug and the floorboards beneath, with an ashed body lying in the space under the floor. He also remembers a pair of undamaged house slippers, with feet still within, the legs burned off at ankle level and no remaining body above, apart from ashed material



Figure 11.19 Soot in the tracheal mucus, a sign of breathing while the fire was in progress. Though soot can passively reach the glottis after death if the mouth is open, it cannot reach the lower air passages in any significant quantity. Histology of the smaller bronchi offers complete proof of active respiration.



Figure 11.20 Soot in oesophagus of a house-fire victim indicating respiration during the fire.



Figure 11.21 Substantial destruction of the body by fire. The upper half of the victim has virtually vanished, including skeletal structures, leaving the lower part intact. The gas stove was ignited with a match after a delay while gas was escaping, causing a near-explosion that consumed the upper part of the body, the fat burning with clothing acting as a 'wick'. Such events have given rise to the myth of 'spontaneous combustion'.

lying on the adjacent floor. Both these deaths occurred in front of a fireplace with an open chimney.

It seems extraordinary that virtually a whole adult body can be consumed, including the skeleton, with minimal surrounding fire damage, but many such cases are on record and have helped to substantiate the myth of 'spontaneous human combustion' (Fig. 11.21).

Experiments carried out many years ago by Professor David Gee indicated that body fat can burn slowly, using the clothing as a 'wick', similar to a candle flame.[42]

Most cases have in common the fact that there was a source of ignition in an open fire and a chimney that can provide a constant updraught – and often the victims are alcoholics. Though it is not suggested that alcohol plays any part in the burning process, the confusion, instability and lack of judgement which goes with inebriation may well precipitate the ignition process.[43–45]

As indicated above, the myth of 'spontaneous combustion' is one which refuses to go away, as endless unsubstantiated reports, and newspaper, magazine and television features have continued to fascinate a credulous public ever since Charles Dickens included a description of a case in his novel *Bleak House*.[46]

Numerous allegations have been made of people bursting into flames as they walk down the street, but as yet, no photographs or film has been produced; in fact, the majority of the retrospective claims for this phenomenon have been of bodies next to some source of ignition and where alcohol was involved – as indeed was Dickens' original example.

References

1 Moritz AR, Henriques FC. Studies of thermal injury: II. The relative importance of time and surface temperature in the causation of cutaneous burns. *Am J Pathol* 1947;23(5):695–720.

2 Fabry W. *De Combustionibus*. Basle: Carolus Uttenhove, 1607.

3 Naylor IL, Curtis B, Kirkpatrick JJ. Treatment of burn scars and contractures in the early seventeenth century: Wilhelm Fabry's approach. *Med Hist* 1996;40(4):472–86.

4 Kirkpatrick JJ, *et al.* A modern translation and interpretation of the treatise on burns of Fabricius Hildanus (1560–1634). *Br J Plast Surg* 1995;48(7):460–70.

5 Boyer A. *Traité des Maladies Chirurgicales et des Opérations qui leur Conviennent*.Vol. 1. Paris: Migneret, 1814.

6 Jackson DM. [The diagnosis of the depth of burning. *Br J Surg* 1953;40(164):588–96.

7 Wilson JV. *The Pathology of Traumatic Injury*, 1st edn. Edinburgh: Livingstone, 1946.

8 Heister L. *A General System of Surgery in Three Parts*. London: W. Innys, 1743.

9 Holmes T (ed). *A System of Surgery, Theoretical and Practical*.Vol. I. London: John W. Parker and Son, 1860.

10 Lund CC, Browder NC. The estimation of areas of burns. *Surg Gynecol Obstet* 1944;79:352–8.

11 Hettiaratchy S, Papini R. Initial management of a major burn: II—assessment and resuscitation. *Br Med J* 2004;329(7457):101–3.

12 Berkow SG. A method of estimating the extensiveness of lesions (burns and scalds) based on surface area proportions. *Arch Surg* 1924;8:138–48.

13 Wallace AB. The exposure treatment of burns. *Lancet* 1951;1(6653):501–4.

14 Pruitt BA, Jr, Wolf SE, Mason AD, Jr. Epidemiological, demographic, and outcome characteristics of burn injury. In: Herndon DN (ed). *Total Burn Care*, 3rd edn. Edinburgh: WB Saunders, 2007, pp. 14–32.

15 Hannuksela ML, Ellahham S. Benefits and risks of sauna bathing. *Am J Med* 2001;110(2):118–26.

16 Ohori T, *et al.* Effect of repeated sauna treatment on exercise tolerance and endothelial function in patients with chronic heart failure. *Am J Cardiol* 2012;109(1):100–4.

17 Koski A, Koljonen V, Vuola J. Rhabdomyolysis caused by hot air sauna burn. *Burns* 2005;31(6):776–9.

18 Koljonen V. Hot air sauna burns – review of their etiology and treatment. *J Burn Care Res* 2009;30(4):705–10.

19 Penttila A. [Unexpected and sudden deaths in Finnish saunas]. *Beitr Gerichtl Med* 1985;43:223–32.

20 Kortelainen ML. Hyperthermia deaths in Finland in 1970–86. *Am J Forensic Med Pathol* 1991;12(2):115–18.

21 Kenttamies A, Karkola K. Death in sauna. *J Forensic Sci* 2008;53(3):724–9.

22 Rodhe A, Eriksson A. Sauna deaths in Sweden, 1992–2003. *Am J Forensic Med Pathol* 2008;29(1):27–31.

23 Saukko P. Sudden death during sauna bathing in Finland. *J Japn Soc Balneol, Climatol Phys Med* 2012;76(1):7–11.

24 Eren B, *et al.* Deaths in the Turkish hamam (hot bath). *Bratislava Med J* 2009;110(11):697–700.

25 *Official Statistics of Finland (OSF): Causes of death [e-publication]*. Statistics Finland: Helsinki, 2012.

26 Dotzauer G. [About the socalled burn hematomas (author's transl)]. *Z Rechtsmed* 1974;75(1):21–4.

27 Kondo T, Ohshima T. Epidural herniation of the cerebral tissue in a burned body: a case report. *Forensic Sci Int* 1994;66(3):197–202.

28 Gill JR, Goldfeder LB, Stajic M. The happy land homicides: 87 deaths due to smoke inhalation. *J Forensic Sci* 2003;48(1):161–3.

29 Grabowska T, Nowicka J, Olszowy Z. [The role of ethanol in complex poisonings with carbon monoxide and hydrogen cyanide in fire victims]. *Arch Med Sadowej Kryminol* 2006;56(1):9–14.

30 Levin BC, *et al.* Analysis of carboxyhemoglobin and cyanide in blood from victims of the Dupont Plaza Hotel fire in Puerto Rico. *J Forensic Sci* 1990;35(1):151–68.

31 Stefanidou M, Athanaselis S, Spiliopoulou C. Health impacts of fire smoke inhalation. *Inhal Toxicol* 2008;20(8):761–6.

32 Yoshida M, *et al.* A study on house fire victims: age, carboxyhemoglobin, hydrogen cyanide and hemolysis. *Forensic Sci Int* 1991;52(1):13–20.

33 Rogde S, Olving JH. Characteristics of fire victims in different sorts of fires. *Forensic Sci Int* 1996;77(1–2):93–9.

34 DeHaan JD. The dynamics of flash fires involving flammable hydrocarbon liquids. *Am J Forensic Med Pathol* 1996;17(1): 24–31.

35 Anderson RA, Harland WA. Fire deaths in the Glasgow area: III. The role of hydrogen cyanide. *Med Sci Law* 1982;22(1): 35–40.

36 Anderson RA, Watson AA, Harland WA. Fire deaths in the Glasgow area: I General considerations and pathology. *Med Sci Law* 1981;21(3):175–83.

37 Anderson RA, Watson AA, Harland WA. Fire deaths in the Glasgow area: II the role of carbon monoxide. *Med Sci Law* 1981;21(4):288–94.

38 Curry AS, Price DE, Rutter ER. The production of cyanide in post mortem material. *Acta Pharmacol Toxicol Copenh* 1967;25(3):339–44.

39 Lokan RJ, James RA, Dymock RB. Apparent post-mortem production of high levels of cyanide in blood. *J Forensic Sci Soc* 1987;27(4):253–9.

40 Ballantyne B. In vitro production of cyanide in normal human blood and the influence of thiocyanate and storage temperature. *Clin Toxicol* 1977;11(2):173–93.

41 Karhunen PJ, Lukkari I, Vuori E. High cyanide level in a homicide victim burned after death: evidence of post-mortem diffusion. *Forensic Sci Int* 1991;49(2):179–83.

42 Gee DJ. A case of 'spontaneous combustion'. *Med Sci Law* 1965;5:37–8.

43 Christensen AM. Experiments in the combustibility of the human body. *J Forensic Sci* 2002;47(3):466–70.

44 Gromb S, *et al.* Spontaneous human combustion: a sometimes incomprehensible phenomenon. *J Clin Forensic Med* 2000;7(1): 29–31.

45 Weed HG. A case of spontaneous combustion. *Ann Emerg Med* 1991;20(2):219.

46 Dickens C. *Bleak House*, 1st edn. London: Bradbury & Evans, 1853.

CHAPTER 12

Electrical Fatalities

- Physical factors
- Electrical considerations
- Effects upon muscle
- Mode of death
- The cutaneous electric mark
- Patterned electric marks
- Metallic traces in electrical marks
- Internal appearances
- Histological appearances
- Electrocution in the bathroom
- Suicide by electricity
- Homicide by electricity
- Deaths from lightning
- References

The passage of a substantial electrical current through the tissues can cause skin lesions, organ damage and death. This injury is commonly called 'electrocution', though some would use this term only if death occurs. Fatalities are usually accidental, in both a domestic and industrial environment. They are more common in developing than in industrialized countries. Suicides from electricity are relatively rare. Homicide is rare but is recorded and, in the USA, electricity has again become a means of judicial execution since 1976, and was in 2010 in use in nine states.[1]

Physical factors

The severity of tissue damage 'including death' is directly related to a number of physical factors, which include current, voltage, resistance and time. For biological damage to occur, the body must be incorporated into an electrical circuit, so that there is a passage of electrons through the tissues. A mere accumulation of electrons in the form of a static charge can do no harm; scientists in the ball of a Van de Graaf static generator may be at a potential of more than a million volts (V), but experience nothing other than their hair standing on end. Similarly, a person outdoors in a thunderstorm may accumulate a high charge from the capacitance effect of an overhead cloud but, unless the insulation of the air breaks down to allow a lightning strike at or near the person, no ill-effects will occur.

In electrocution there must be a pathway for electrons across part of the body which, in fatal cases, contains vital structures. The current enters at one point (most often a hand being used to hold, touch or manipulate some electrical device) and then leaves the body at an exit point, usually to the earth or the neutral conductor of the electricity supply. The pathway of the current will depend mainly on the relative resistance of various potential exit points. It tends to take the shortest route between entry and best exit, irrespective of the varying conductivity of different internal tissues. If a person places a finger on a 240 V conductor while standing with damp shoes on a wet concrete floor, then an appreciable current will pass from hand to feet, with possibly fatal results. If, however, the person is standing on a carpeted upstairs wooden floor, the poor earth return will allow only a small current to flow and all that may be suffered is a painful muscular spasm.

In another variant of the upstairs scene, should the neutral wire of the supply be touching the skin of the same finger a few centimetres away from the live conductor, a severe local burn may occur but no danger to life, because the high resistance through the feet to earth will prevent any significant current flow passing through the thorax.

Should the person upstairs happen to be turning a bath tap with the other hand, the contact with the opposite finger would allow a current to pass to earth via the tap and metal water-pipes from hand to hand across the thorax – an extremely dangerous position.



Figure 12.1 Pathways of current in electrocution.

The pathologist is concerned with fatal electrocution and three major events may occur, which are a threat to life:

- The most common is the passage of a current across the heart, usually when a hand is brought into contact with a live conductor, and the body is earthed either through the feet or the opposite hand. It has been claimed that the most dangerous current path is contact with the right hand and exit through the feet, as this causes the maximum (up to 8.5 per cent) of the total body current to flow through the heart when compared with head to feet (up to 5.9 per cent), left hand to feet (up to 5.1 per cent), hand to hand (up to 4.4 per cent) or foot to foot (up to 0.4 per cent).[2,3] Compared with the other variables of voltage, skin resistance and time, these differences between the routes seem immaterial, with the exception of foot to foot, where the current flow through the heart is so much lower. The fatal process is a cardiac dysrhythmia, usually a ventricular fibrillation ending in asystole.
- Less often, the passage of a current across the chest and abdomen may lead to respiratory paralysis from spasm of the intercostal muscles and diaphragm.
- Rarely, the current passes through the head and neck, usually in circumstances when the head of a worker on overhead power lines comes into contact with the conductor. In such instances, there may be a direct effect on the brainstem so that cardiac or respiratory centres are paralysed (Fig. 12.1).

It is commonly said that tolerance can be gained to electric shock and that professional electricians often work on live 240 V conductors with impunity. It seems more likely that expectation of a shock decreases sensitivity, but only for brief contacts, less than would be required for physiological or structural damage.

Electrical considerations

Electrons are moved around a circuit by the 'potential difference' between two points, which may be looked upon as the 'pressure' of the electricity, measured in volts (V). The number of electrons flowing constitutes the 'current', analagous to the volume of electricity and is measured in amperes, though in the present discussion, milliamperes (mA) are more relevant to biological effects. The tissues also have 'resistance' to the electrical flow. There is a mathematical relationship between potential difference, current and resistance – the well-known Ohm's law – in which the current varies directly with the voltage and inversely with the resistance. This law has considerable relevance to biological electrical damage.

Alternating and direct current

In spite of the folklore of electricians there is no doubt that direct current (d.c.) is less dangerous than alternating current (a.c.); a current of 50–80 mA a.c. can be fatal in seconds, whereas 250 mA d.c. for the same time is often survived. Alternating current is four to six times as likely to cause death, partly because of the 'let-go' or 'hold-on' effect described below, which is the result of tetanoid muscle spasm and prevents the victim from releasing the live conductor.

Alternating current is also much more likely than direct current to cause cardiac arrhythmias. High amperage d.c.

(above 4 A) may even cause an arrhythmic heart to revert to sinus rhythm, as in medical defibrillation.

The usual frequency of a.c. is 50 cycles/s (cps), though some American and European systems run at 60 cps. Alternating current between 40 and 150 cps is most dangerous in terms of ventricular fibrillation, and regrettably the usual mains supply lies in the centre of this range. Above 150 cps, fibrillation is progressively less likely as the frequency increases: at 1720 cps the heart is 20 times less likely to fibrillate than at 150 cps.

Current

The degree of damage to the tissues is proportional to the actual quantity of electricity flowing through them. This quantity is expressed by the number of electrons per unit time and strictly speaking should be measured in 'coulombs', which is the product of amperes and seconds, though amperes are usually accepted as an index of the current flow. According to Ohm's law, current depends on the applied voltage, the resistance of the tissue and, for tissue damage, the time for which the current is flowing.

In forensic pathology, we are concerned with fatal electrocution and, as most deaths are the result of cardiac dysrhythmias, the most important measure of current is that which leads to acute heart failure. Estimates vary among authors, but it is generally considered that the passage of 50–80 mA across the heart for more than a few seconds is likely to cause death. The most that can be tolerated voluntarily by most people is 30 mA applied to the hand, which results in painful muscle contractions. Consciousness is likely to be lost at about 40 mA and, as stated, currents sustained for some seconds at over 50–80 mA carry a substantial risk of death.[4–6]

Voltage

To produce a potentially fatal current across the chest, a certain minimum voltage must be applied to the skin surface. As the latter has a relatively high resistance (see below), Ohm's law dictates that an appreciable voltage is required to produce the 50 mA or so needed for ventricular fibrillation. Most fatalities occur with the domestic voltage of 240 V, though the common alternative in parts of the USA and Europe of 110 V is still lethal in many instances.

It is uncommon to encounter deaths at less than 100 V, mainly because there are few sources of supply between 110 V and the 12 V or 24 V used in vehicle electrical systems. These are almost always innocuous, though Polson has reported a fatality at 24 V in a man pinned beneath an electrical vehicle for several hours.[7] That case emphasizes the importance of the time element in electrical injury. Extremely high voltages, such as those encountered in power transmission systems and in electronic equipment, may paradoxically be safer on some occasions, as the shock may physically fling the subject off the conductor, thus reducing the contact time below the threshold for cardiac damage.

Resistance

The major barrier to an electrical current is the skin, which has a far higher resistance than internal tissues. That is why skin electric burns occur, as the resistivity causes energy transfer from the electron flow to the skin. Once inside the dermis, the semi-fluid cytoplasm, and especially the vascular system filled with electrolyte-rich fluid, passes the current through the body quite easily. The resistance of skin varies greatly according to the thickness of the keratin-covered epidermis; that on the soles and finger-pads is greater than the thin skin elsewhere. The average resistance is between 500 and 10000 ohms for areas other than the horny hand and foot pads, which may offer 1 million ohms resistance when dry.

A more potent factor is the dryness or dampness of the skin, which greatly affects its resistance. While dry palm skin may have a resistance of the order of 1 million ohms, when wetted this may fall to only 1200 ohms. Jellinek found the horny skin of a workman to have a dry resistance of from 1 to 2 million ohms; Jaffe stated that sweating could reduce skin resistance from 30000 to 2500 ohms.[8,9] When the current begins to pass, there is a further marked drop in resistance, as a result of electrolytic changes in the skin, which may fall to only 380 ohms. Thus for a fixed voltage, such as the mains supply of 240 V, the resultant current will be far greater if the skin is wet from sweating or external moisture. This emphasizes the dangers of bathrooms and using electrical equipment in damp surroundings. Where alternating current is concerned (as in most forensic cases), resistance is replaced by 'impedance', but this is not relevant to the pathological aspects.

Effects upon muscle

One effect of electricity that has practical implications is the spasm that occurs in skeletal muscle if the current reaches between 10 and 40 mA at 50 cps. When, as most often happens, the entry point is in the hand, the stronger flexor muscles of the arm go into spasm and cause a 'hold-on' effect. This means that any object being held in the hand is involuntarily clenched and, as it is likely to be the faulty electrical appliance or a wire, the object cannot be released and the current thus continues to flow. This adds to the time element and progressively worsens the risk of both cutaneous burns and the risk of cardiac or respiratory arrest. Tingling may be felt in the skin with a current of only 1 mA and 'hold-on' can begin at a current as low as 9–10 mA.[3]

Mode of death

As already stated, most deaths from electricity are from cardiac arrhythmias, usually ventricular fibrillation ending in arrest. This is caused by the passage of current through the myocardium, especially in the superficial epicardial layers and possibly across the endocardium. The current has a profound effect directly upon the myocardial syncytium, the possible dislocation of the pacemaking nodes and conducting systems being ill-understood. When death occurs from cardiac arrest, the body remains either pale or only slightly congested, the autopsy appearances being unhelpful apart from the presence of any external electrical marks.

The second (and far less common) mode of death is respiratory arrest, in which the passage of current through the thorax causes the intercostal muscles and diaphragm to go into spasm, or become paralysed. In either case, respiratory movements are inhibited and a congestive–hypoxic death occurs. The brainstem is affected rarely, when the current enters through the head. Either cardiac arrest or respiratory paralysis can then supervene.

Many electrical deaths are not observed, the person being found dead later, so that the mode of death is unknown. Sometimes the witnessed mode of death is hard to explain on physiological grounds, in that there appears to be a delay (often some minutes in duration) between the shock and the death. In the interval, the victim may be conscious and even apparently recovering. It is difficult to know why a sudden cardiac arrest should take place after the current is switched off, but presumably some fundamental damage has been caused on an intracellular level to cardiac or neural tissue.

Finally, when discussing the mode of death, it must always be remembered that non-electrical trauma is quite common. In a series reported by Bissig, some 15 per cent of cases had injury from falls and other associated trauma.[10] In industrial accidents and when working on power lines, victims of shock may be thrown from a height, or suffer violent muscular spasms that may lead to fractures and other serious injury.

The cutaneous electric mark

The point of contact on the body surface may leave skin lesions, which are either called 'electrical burns' or 'electrical marks', whereas the term 'Joule burn' has not gained popularity. These are the sites of entry of the current, but another mark or marks may also appear where the body was earthed or 'grounded'. It must be emphasized here that fatal electrocution may occur with no skin mark whatsoever, making the diagnosis entirely dependent upon the circumstances of the death. An extreme example is electrocution in the bath, when the large surface area for entry plus the low skin resistance caused by the water abolishes the possibility of a focal burn.

An electrical mark may not be externally obvious, as the current can be applied to the genitals, anus or abdomen in sexual perversions or through the mouth, especially in children. Infants may place a live plug between their lips and sustain electrical burns on the tongue or buccal mucosa, which may not be readily apparent on external examination at autopsy.

When a current passes, there may or may not be a visible lesion, depending upon:

- the density of the current passage in terms of skin area and
- the conductivity, usually varying with the moisture content and pressure of contact.



Figure 12.2 (a) Firm contact electric mark, and (b) spark burn across air gap.

The skin lesion is a thermal burn from heating of the epidermis and dermis as the current passes. Theoretically, the heat generated can be determined from the formula $GC = C2R/4.187$, where GC is the heat in gram calories per second, C is the current in amperes and R the resistance in ohms. If the electron flood passes through a relatively wide area, then the resistance per unit area is small (especially if the skin is damp) and thus the heating effect is proportionately diminished. For example, a person resting the palm of the hand on a flat metal plate which is electrified will pass a far smaller current per square centimetre of skin than another touching the plate with the tip of a finger. The first is likely to have no demonstrable lesions, while the second will have a blistered burn or a keratinized nodule, depending on the firmness of the contact.

The temperature in the tissues directly under the contact point can easily reach 95°C. Tissue damage can occur within 25 seconds when the temperature reaches a mere 50°C. The focal electric mark is largely a thermal burn and even some of the histological features to be described later, which were once thought to be peculiar to the electrical current, are now generally ascribed to thermal effects. There are some features, however, that are characteristic of an electrical cause (Figs 12.2–12.7).

- When the skin has been in firm contact with an electrical conductor, the passage of the current through the high skin resistance heats up the tissue fluids and produces steam. This may split the layers of the epidermis or the epidermal–dermal junction and produce a raised blister. This may rupture if the current continues or if the area is relatively large.

  When the current ceases, the blister cools and collapses, giving the familiar appearance seen at autopsy. The collapsed blister is often annular, producing a raised grey or white ring with an umbilicated centre. The mark sometimes reproduces



Figure 12.3 Firm contact electric marks on a fingertip. Two blisters have been formed by the heat of local skin resistance; they have collapsed on cooling.



Figure 12.4 Firm contact blister and adjacent spark burn from 240 V mains supply. The victim was holding a faulty electric drill. There were no other marks on the body.



Figure 12.5 Collapsed blisters and a spark burn from holding a faulty power tool.



Figure 12.6 Electrical burns on the hand caused by contact with a faulty electrical tool.



Figure 12.7 Multiple electrical burns on a hand, with blisters showing the typical pale raised margins and areas of peeling epidermis. There is a blackening from metallization as the current was passing for several hours; the victim was an electrician who fell into an air-conditioning plant.

the shape of the conductor, especially where this is a linear wire or a shaped metal object. Where the tip of a wire or rod is at right angles to the skin, a focal pit is created, sometimes penetrating quite deeply into the skin.

- Where the contact is less firm, so that an air gap (albeit narrow) exists between skin and conductor, the current jumps the gap as a spark. In dry air 1000 V will jump several millimetres and 100 kV about 35 cm. This is at extremely high temperatures (about 4000°C), as in the sparking plug of a petrol engine, and causes the outer skin keratin to melt over a small area. On cooling, the keratin fuses into a hard brownish nodule, usually raised above the surrounding surface, the so-called 'spark lesion'.
- In many electrical burns these two types are combined, as a result of movement of the hand or body against the conductor and sometimes because of irregularity of the shape of the conductor. Where the time has been prolonged, the voltage is high, or the conductor is large, the burn may be correspondingly severe with large areas of peeled blistered skin, charred keratin, and a mixture of hyperaemia, deep scorching and shed epidermis.
- A characteristic feature of the electric mark that is the most useful indicator of the nature of the lesion, is the common occurrence of an areola of blanched skin at the periphery. Presumably because of arteriolar spasm from the direct effects of the current on vessel-wall musculature, the pallor survives death and is virtually pathognomonic of electrical damage. Often there is a hyperaemic border outside the blanching, though reddening may also be seen inside the pale zone, as the outermost rim of the heated burn area. Occasionally, an alternating spectrum of blister-reddening-pallor-reddening can be observed centrifugally from the centre of the lesion. When the burn is linear, such as that from a bare wire pressed against the skin, the 'areola' takes the form of a pale zone parallel to the central burn.
- When the marks are minimal, all that may be seen are tiny white discs representing minute flat blisters where the epidermis has split, but no reddening or areola has formed – or at least, has not persisted until the time of autopsy. These can be hard to find and, as they are likely to be present on the palmar surface of the hands (the usual site from grasping an electrical appliance), the strong flexion of rigor mortis may bring the fingers down to the palms, so obscuring any lesions (Fig. 12.11). It is essential in all autopsies to examine the flexor surface of the fingers by forcible breaking of the rigor – and, where electrocution is a possibility, minute inspection of the hands must be carried out, even if the flexor tendons at the wrist have to be cut to release the rigor clenching of the fingers.
- In high-voltage burns, such as those sustained from high-tension grid transmission cables, where the voltage is in the multi-kilovolt range, sparking may occur over many centimetres. This can cause multiple spark lesions giving rise to a 'crocodile-skin' effect (Figs 12.8–12.10). Both linesmen and copper thieves working on high pylons may suffer non-electrical injuries from being thrown to the ground, or they may sustain gross charring burns or even limb fractures from both direct electrical energy and the muscle spasm caused by a massive bolt of electricity.



Figure 12.8 Extensive burns from high-voltage (multi-kilovolt) supply lines of the grid system.



Figure 12.10 Thigh of the victim in Fig. 12.9 showing high-voltage burns. The appearance is sometimes called 'crocodile skin' and is caused by arcing of the current over a considerable distance.



Figure 12.9 Severe high-voltage burns in the body of a suicide who jumped from a railway bridge and landed first on the railway power line getting electrocuted and thereafter fell on the track.

- Earthing or 'grounding' lesions are not often seen, but should be looked for on the contralateral hand and on the feet. The lesions may be similar, though less severe. In a case seen by the author (BK), in which a workman pushed a metal wheelbarrow over a live cable lying in a pool of water, the entry burns were on the hands, but on the soles of both feet the electrical burns matched the metal studs in his boots where the current earthed through damp socks and leather.

  In another case, a homicide in a bath, there were no entry burns but the current went to earth by contact of the breasts with the metal taps (Fig. 12.12).



Figure 12.11 Reconstruction of a fatal electrocution. While replacing a bulb a workman dropped dead, even though the light was not illuminated. The circuit had been improperly 'wired through' – that is, the switch had been placed in the neutral wire, instead of the live. The porcelain holder was broken so that his little finger touched the brass base of the bulb, thus completing the circuit across the chest to the other hand, which held an earthed base-plate. The only electrical mark was on the little finger.

- When the current has flowed for an appreciable time, even at a domestic voltage of 240, the effects may be severe. Charring and more extensive peeling and blistering of skin may occur, with deep muscle damage and cooking of the tissues. This is partly because of the fact that the initial damage lowers skin resistance so that progressively more current flows and therefore more burning and necrosis follows.

Much of this damage seen at autopsy may have occurred post-mortem, if death from cardiac arrest occurs early in the event and, where the victim is alone, there is no one to remove his body from the source of the current. It has been conclusively shown by Polson and others that post-mortem burns can be inflicted on a dead body, the appearances being similar in terms of blistering and burning, though the red flare of 'vital reaction' will be absent if death has occurred some time before.

Patterned electric marks

As with many other injuries, a pattern of the shape of the causative object may sometimes be identified. When the electrical conductor is a wire, a linear burn may occur. The shape and spacing of electrical plugs or contacts may be seen, and faulty electrical equipment may impress its shape into the skin. These marks may be useful when the pathologist tries to reconstruct the events – and indeed, may indicate for the first time that the death was caused by electricity, when the unwitnessed events are particularly obscure.

As electric shock and burns are commonly seen in torture victims in abuse of human rights, a pattern may be useful in determining what object was used and give evidence of deliberate repetition. The deliberate use of a male-pin plug connected to the mains supply, then pressed against the skin, may give a series of regularly spaced marks, consisting of hyperaemia, blistering, areola formation or even charring.

Metallic traces in electrical marks

When a current passes from a metal conductor into the body, a form of electrolysis occurs so that metallic ions are embedded in the skin and even in the subcutaneous tissues. This occurs with both d.c. and a.c. because of the combination of metallic ions with tissue anions to form metallic salts. These may be invisible to the eye, but detectable by chemical, histochemical and spectrographic techniques. They persist for some weeks during life and resist a moderate amount of post-mortem change. Where gross they may be observed directly on the skin, and where copper or brass conductors are involved a bright green imprint may be obvious (Figs 12.15, 12.16). Where an electric arc forms, vaporized metal may be deposited on the skin, often extensive enough to be visible to the naked eye.[11,12] In high-voltage contacts, the skin of a wide area may be brown or greyish, partly from heat effects, but partly from metallization.

Recently, using the scanning electron microscope, it has become possible to see tiny globules of molten metal on the skin at and near an electrical mark, deposited there by the almost inevitable 'mini-arcing' that accompanies any electrical contact. Combined with energy dispersive X-ray microanalyser (EDX), Kinoshita and coworkers were able to identify titanium metallization on the surface of the current mark.[13] Atomic absorption spectroscopy has also been applied for detection of multimetal traces in low-voltage electrical marks.[14] Chemical tests for metallic deposits include that devised by Adjutantis and Skalos, which is a simple touch-test using elution on strips of filter paper. Copper, iron, aluminium, zinc or nickel are dissolved in nitric or hydrochloric acid, and the solution tested with a variety of simple but specific reagents.[15] Pierucci and Danesino used a fluorescent technique to visualize *in situ* latent current marks or electrical metallic traces on cloth by spraying them with a 0.2 per cent solution of 8-hydroxyquinoline in ethanol followed by observation under shortwave ultraviolet light.[16]

Internal appearances

In fatal electrocution, gross findings in the internal organs may be absent and even histological changes are a matter of controversy. Because the internal tissues are largely aqueous and contain conductive electrolytes, the current pathway is usually too diffuse to cause thermal damage. The absence of visceral damage is made up for by physiological and functional abnormalities, mainly in muscle and nervous tissue.

The usual mode of death is cardiac arrhythmia leading to ventricular fibrillation and arrest. In these deaths there is little to find at autopsy apart from the skin lesions. It is claimed that epicardial petechiae may occur, but these are too non-specific to be of any use. The body is either pale or only slightly congested, in contrast to the *few* deaths that occur from respiratory paralysis.

In the latter group the intercostal muscles and diaphragm go into spasm or are paralysed, which leads to marked congestion and cyanosis of the face, with similar changes in the lungs. There may be some petechiae on the pleura, though this again is such a non-specific finding as to be unhelpful as a diagnostic sign. At autopsy, the usual signs of a congestive death are found, with dark blue–red post-mortem hypostasis.

A number of other signs of electrocution have been claimed, but they are rarely confirmed by personal experience. These include intracerebral petechiae, which are probably part of the general congestive state in respiratory paralysis.

Histological appearances

These are rather controversial, as some changes formerly claimed to be specific for electrical lesions have been shown to be thermal.

The skin mark consists of vacuolation in the epidermis and sometimes dermis, caused by the gas spaces from the heated tissue fluids splitting the cells apart. The affected tissues become more eosinophilic. The cap of epidermis may be detached and raised into a blister, with a large space beneath. The cells of the epidermis are often elongated, with the nuclei of the lower layers orientated and horizontally stretched; this was once claimed to be an electromagnetic effect, but the same appearance can be seen in purely thermal burns and in hypothermic lesions.

Changes in the brain have been described, even when the cause of death was cardiac. Focal petechial haemorrhages, spaces around small blood vessels and tears in white matter have been described. Electron microscopy reveals a variety of changes, especially in the nuclei of skin cells, which are deformed with clumped chromatin. Janssen has compiled a review of electrical histological lesions in his book on forensic histology, but it seems evident that there is little that is absolutely pathognomonic of electrical as opposed to purely thermal burns.[17] Calcification of collagen fibres in electrically induced dermal injury has been described in pigs and the authors have assumed the changes to be similar to the skin injuries associated with electric shock torture (Chapter 10).[18–29] As cutaneous calcification is known to occur through various pathogenetic mechanisms (metastatic, dystrophic, idiopathic or iatrogenic) the diagnostic significance of these experimental findings is unclear.

Histochemical reactions for metallization can also be carried out, though, again, metals can be transferred into the skin by purely thermal means if hot metallic objects are pressed against the skin.

Scanning electron microscopy appears to be the best way of distinguishing between electrical and thermal damage, as the punctate nature of the deposition and the possibility of chemical analysis by electron microprobes offer a sophisticated means of identifying the metallic deposit. Internal organs reveal no true diagnostic lesions of electricity. The wavy appearance of the myocardial fibres and their fragmentation may be suggestive, but by no means diagnostic. Contraction bands within the fibres, especially of a ‘bark-like’ appearance, have been described but, again, are non-specific, though they are often seen in the subepicardial myocardium after resuscitation that includes electrical defibrillation. However, they are identical to catecholamine effects on the myocardium and so may not be electrical in origin.



Figure 12.12 Homicidal electrocution in the bath. An electric heater was dropped into the water with the wire to the earth terminal deliberately disconnected. The 240 V supply entered the body diffusely through the water and completed the circuit by earthing through contact with the breasts against the metal taps, leaving electrical marks on the skin.

Electrocution in the bathroom

The bathroom is a common site for electrical tragedies. Accidents, suicides and even homicides occur there because of its vulnerability to electrical shock.[30–39] The bathroom is electrically the most dangerous place in a house as there is a moist atmosphere, ample water, good earthing through metal taps and pipes, and a wet, unclothed body – all of which are conducive to low electrical resistance and hence high tissue currents. Accidents are common, usually as a result of the careless use of electrical appliances, such as hairdryers and room heaters. Most European countries have strict regulations about electrical installations in bathrooms because of the danger. In Britain, no wall switch is permitted for the light, a ceiling switch operated by an insulating cord being mandatory. No power sockets are allowed except for a shaver socket that incorporates a step-down transformer with a low maximum current output. In spite of this, people unwisely use extension leads or plug into light sockets to operate a variety of appliances.

Suicide by electricity (Figs 12.13, 12.14)

There was a remarkable increase in the number of suicidal electrocutions in the 1980–1990s, especially in the bath. Bonte *et al.* have described an increasing number of cases in the former West Germany, drawing attention to the unusual demarcation of post-mortem hypostasis in such deaths, where the water level during electrocution appears to limit the subsequent appearance of the hypostasis.[32] Various circuit arrangements are made by suicides in baths: these range from the pulling of an electrical appliance into the water to complex connections to metal soap dishes and wiring up contacts on the body. There may even be arrangements to break the circuit when the bathroom door is opened to safeguard those who find the body. The circumstances are rarely in doubt except that some less sophisticated cases may be difficult to differentiate from the many other accidents that occur in bathrooms.[32,38,40–43]

Homicide by electricity

Homicide is occasionally committed by electricity, the author (BK) having dealt with two such incidents and his co-author (PS) with one. The first took place in the bath and provided good illustrations of the electrical aspects of fatal shock. A young female was found dead in her bath, slumped forwards in a kneeling position with one breast resting against a chrome tap. The left arm was trailing over the edge of the bath, in which was the usual level of water plus an electric fan-heater immersed near the feet. The heater was connected by a long cable to a 240 V 13A socket in an adjacent bedroom. Significantly, the third 'earth' wire had been deliberately disconnected from the earth pin inside the plug. Subsequent forensic tests showed that the enamel lining of the metal bath was an excellent insulator so that earthing of the current through the bath water could only occur via the chrome waste pipe. The circuit was completed, however, with fatal results, by the female falling (or being pushed) against the tap, so that she sustained an electrical burn on the breast. She also had another typical burn on the inside of her left



Figure 12.13 Suicide by electricity. Both wrists were wired in this fashion to a 240 V supply socket, the circuit being completed from arm to arm across the chest.



Figure 12.14 Suicide by electricity. Both forefingers were wired to a 240 V supply socket, the circuit being completed from arm to arm across the chest.



Figure 12.15 The deceased male had electrical marks on his fingers and lips, which were stained green from metallization from the brass fittings of the table lamp.



Figure 12.16 In addition, the male in Fig. 12.15 had a metal comb resting over a large electric burn on his abdomen, also wired up to the lamp socket. No circumstantial evidence of suicidal intent could be discovered and some masochistic exercise was suspected.

arm near the axilla, where the insulating enamel of the bath ceased at the turned-over edge. Forensic tests showed that there was a progressive gradient of voltage down the bath from over 200 V near the heater to virtually zero near the earthed waste pipe. The current had preferentially taken a course through the victim's body from feet to exit through breast and arm, rather than through the higher resistance of the fresh water.

It was also shown that, when the earth safety wire was reconnected, the voltage at the top of the bath fell to negligible levels, even though the fuse did not blow. Her husband, after several denials, eventually confessed to dropping the heater into the bath – and also to borrowing a book from the public library the previous day entitled *The Do-it-yourself Home Electrician*!

The other homicide, which could not be proved for lack of evidence or a confession, concerned the wrapping of bare electric wires around the neck of a female. The wire was thick 30A cooker cable with 40 cm of insulation stripped except for the extreme tips. Her husband, a professional electrician, provided the unlikely explanation that he was using this to test his electric shaver (Figs 12.17, 12.18)!

The third homicide went first undetected as the perpetrator, the husband of the victim, had staged it as an accident. The wife was supposed to have been ironing in the kitchen early one morning and been electrocuted by a faulty cord of the iron, the water-pipe of the sink providing the contact to the earth. In addition to the SOCs, an electrician, but not the pathologist, was called to the scene to investigate the faulty device, but nothing suspicious was detected. Ironically, in spite of the clumsy way in breaking the insulation of the cord and leaving only a couple of millimetres of the naked wire visible, a picture of the faulty cord and iron landed in a textbook for electricians, pointing out the dangers of faulty household appliances. At autopsy the only finding was an electrical burn on the chest. Eight years later, when the husband was in detention in the course of an investigation due to a stolen money transport, he wrote a very detailed confession of the murder of his wife. He had attached two copper electrodes to an extension



Figure 12.17 Electrical burn around the neck from a mains wire being held against the skin. The typical pale areola and peeled skin blistering can be seen. There was suspicion of homicide, but it could not be proved.



Figure 12.18 The opposite side of the neck of the victim in Fig. 12.17.

cord and, while the wife was asleep, pressed them to her chest. In court, in spite of the withdrawal of his confession, he was sentenced to a long imprisonment. Several details that came out in the course of the criminal investigation, implied, although it was never proven, that the husband had first attempted to kill his wife by feeding her diazepam tablets without her knowledge, and when this had failed, electrocuted her. It is hindsight and fruitless to contemplate what might have happened if the pathologist had been to the scene. The lesson of the case is, however, that if electrocution is suspected, it certainly is worthwhile to take a look at the scene of death. Two homicides by electrocution have been reported by al-Alousi, an attempted homicide by Pfeiffer and Karger and two further homicides by Wick *et al.*[44–47]

Deaths from lightning

In tropical and subtropical countries deaths from lightning are not uncommon and, even in higher latitudes, occasional tragedies occur where numbers of people are killed or injured in single episodes. An example was at Ascot on July 14, 1955, just after 4 p.m., when a severe thunderstorm occurred in the vicinity of Ascot racecourse while a meeting was in progress. Several lightning flashes struck a tea-stall throwing a considerable number of people near it to the ground, injuring many and killing one on the spot and another one later, both of them from head injuries. Of the 37 patients seen in hospital, 26 complained of paraesthesiae in one or more limbs. The burns observed in 15 patients showed feathering, flash, erythema and blistering, punctate full-thickness skin loss, linear charring and contact burn from metal.[48]

The physics of a lightning strike are complex and not fully understood. Gigantic voltages and amperages are involved when a highly charged thundercloud discharges via a huge arc to the ground.

Lightning deaths cannot be other than accidental and provide no real problems for the forensic pathologist. Occasionally the nature of the death may be uncertain if a dead body is discovered in the open with no marks upon it, but usually there will be reports of a lightning strike nearby and artefacts, such as torn and scorched clothing and magnetized metallic objects in the pockets, may assist in explaining the event.

It is well known that injury from lightning is capricious and unpredictable. Two people can stand side by side during a flash and one may be mutilated and killed while the other is unharmed. The physical damage in fatal cases can vary from virtually nil to gross burning, fractures and tissue destruction. Cutaneous marks may be present, the well-known 'fern-like' or 'arboresque' pattern, also referred to as 'Lichtenberg' figures (because of their similarity to the pattern described by a German physicist, Georg Christoph Lichtenberg, in 1777) being much less common than the standard texts suggest (Fig. 12.19).[49–55] Irregular red marks, often linear first-degree burns, may follow skin creases, especially if damp from sweating. These marks may be many inches long and generally follow the long axis of the body towards the ground. Frank blistered or charred burns are also present in some cases.

An excellent picture of the Lichtenberg figures was taken by Domart and Garet, published in the



Figure 12.19 The fern-like, arboresque pattern seen over the shoulders and chest in a victim of lightning stroke. Although this is always mentioned in descriptions of lightning deaths, it is seen in a small minority of cases.

New England Journal of Medicine in 2000, showing a 54-year-old male struck by lightning. With the exception of numbness and paraesthesia of the left shoulder, flank and leg, he felt well on the arrival at the emergency department. The serum creatine kinase and myoglobin concentrations were slightly elevated. After a 24-hour observation period, the patient was sent home and 2 days later, on a follow-up visit, the fern-leaf pattern of marks had disappeared.[51]

The clothing may be torn off and this can sometimes raise the suspicion of foul play if the lightning aspect is obscure. The clothing is typically ripped open as if by an internal explosion, and belts and boots may be similarly ruptured. Metal objects in the pockets may be fused or magnetized, as may be metal buttons and tooth fillings. Burns on the skin may be adjacent to metal objects in or on the clothing.

There is often a smell of singeing or burning about the body and its clothing. The hair may be scorched and there is often a head injury, caused either by the lightning strike itself or by falling to the ground.

References

1 Snell TL. Capital punishment, 2009 – statistical tables. In: Walsh G, Duncan J (eds). *Capital Punishment Series*. Washington: Office of Justice Programs, Bureau of Justice Statistics, 2010, p. 24.

2 Reilly JP. *Applied Bioelectricity: From Electrical Stimulation to Electropathology*, 1st edn. New York: Springer-Verlag, 1998.

3 Sutherland PE, Dorr D, Gomatom K. Response to Electrical Stimuli. *IEEE Industry Applications Magazine* 2009(May/June); 22–30.

4 Dalziel CF, Lee WR. Lethal electric currents. *IEEE Spectrum* 1969(February);44–50.

5 Lee RH. Electrical safety in industrial plants. *Industry and General Applications, IEEE Trans* 1971;IGA-7(1):10–16.

6 Reilly JP. Scales of reaction to electric shock. Thresholds and biophysical mechanisms. *Ann NY Acad Sci* 1994;720:21–37.

7 Polson CJ. *Essentials of Forensic Medicine*. Oxford: Pergamon Press, 1963.

8 Jaffe, R.H., *Electrical injury*. Arch Pathol, 1928. **5**: p. 837-70.

9 Jellinek S. *Elektrische Verletzungen*. Leipzig: Barth, 1932.

10 Bissig H. Über Niederspannungsunfälle. Untersuchungen an 426 fällen aus dem verletztengut der SUVA der jahre 1956 und 1957. *Biomed Technik/Biomed Eng* 1960;5(3):154–83.

11 Moar JJ, Hunt JB. Death from electrical arc flash burns. A report of 2 cases. *S African Med J* 1987;71(3):181–2.

12 Nagesh KR, *et al.* Arcing injuries in a fatal electrocution. *Am J Forensic Med Pathol* 2009;30(2):183–5.

13 Kinoshita H, *et al.* The application of a variable-pressure scanning electron microscope with energy dispersive X-ray microanalyser to the diagnosis of electrocution: a case report. *Leg Med (Tokyo)* 2004;6(1):55–60.

14 Jakubeniene M, *et al.* Application of atomic absorption spectroscopy for detection of multimetal traces in low-voltage electrical marks. *Forensic Sci Int* 2006;161(1):36–40.

15 Adjutantis G, Skalos S. The identification of the electrical burn in cases of electrocution by the acro-reaction test. *J Forensic Med* 1962;9:101–4.

16 Pierucci G, Danesino P. Fluorescent technique for macroscopic detection of electrical metallization. *Z Rechtsmed* 1981;86(4):245–8.

17 Janssen W. *Forensic Histopathology*. Berlin: Springer Verlag, 1984.

18 Danielsen L, *et al.* Electrical and thermal injuries in pig skin – evaluated and compared by light microscopy. *Forensic Sci Int* 1978;12(3):211–25.

19 Thomsen HK, *et al.* Early epidermal changes in heat- and electrically injured pig skin. I. A light microscopic study. *Forensic Sci Int* 1981;17(2):133–43.

20 Karlsmark T, *et al.* Tracing the use of torture: electrically induced calcification of collagen in pig skin. *Nature* 1983;301(5895):75–8.

21 Karlsmark T, *et al.* Tracing the use of electrical torture. *Am J Forensic Med Pathol* 1984;5(4):333–7.

22 Karlsmark T, *et al.* Immediate dermal changes in pig skin after exposure to moderate amounts of heat and electrical energy. *J Invest Dermatol* 1986;87(4):528–32.

23 Karlsmark T, *et al.* The occurrence of calcium salt deposition on dermal collagen fibres following electrical injury to porcine skin. *Forensic Sci Int* 1988;39(3):245–55.

24 Karlsmark T, *et al.* Electrically-induced collagen calcification in pig skin. A histopathologic and histochemical study. *Forensic Sci Int* 1988;39(2):163–74.

25 Karlsmark T, *et al.* The effect of sodium hydroxide and hydrochloric acid on pig dermis. A light microscopic study. *Forensic Sci Int* 1988;39(3):227–33.

26 Karlsmark T, *et al.* Ultrastructural changes in dermal pig skin after exposure to heat and electric energy and acid and basic solutions. *Forensic Sci Int* 1988;39(3):235–43.

27 Karlsmark T, *et al.* The morphogenesis of electrically and heat-induced dermal changes in pig skin. *Forensic Sci Int* 1988;39(2):175–88.

28 Karlsmark T. Electrically induced dermal changes. A morphological study of porcine skin after transfer of low-moderate amounts of electrical energy. *Dan Med Bull* 1990;37(6):507–20.

29 Danielsen L, *et al.* Diagnosis of electrical skin injuries. A review and a description of a case. *Am J Forensic Med Pathol* 1991;12(3):222–6.

30 Schwerd W, Lauterbach L. Mord mit elektrischem Strom in der badewanne. *Arch Kriminol* 1960;126:33–49.

31 Schneider V. [Electrocution in the bathtub]. *Arch Kriminol* 1985;176(3-4):89–95.

32 Bonte W, Sprung R, Huckenbeck W. [Problems in the evaluation of electrocution fatalities in the bathtub]. *Z Rechtsmed* 1986;97(1):7–19.

33 Kallieris D, *et al.* [Electrocution death in the bath tub]. *Beitr Gerichtl Med* 1988;46:301–6.

34 Roll P. [Interesting observation in a case of electrocution in the bath tub]. *Beitr Gerichtl Med* 1988;46:307–12.

35 Fechner G, Brinkmann B, Heckmann M. [Heart current density as the most important biological parameter of electrocution in the bathtub]. *Beitr Gerichtl Med* 1990;48:335–8.

36 Mackenzie EC. Electrocution in a bath. *Sci Justice* 1995; 35(4):253–8.

37 Bligh-Glover WZ, Miller FP, Balraj EK. Two cases of suicidal electrocution. *Am J Forensic Med Pathol* 2004;25(3):255–8.

38 Pfeiffer H, Du Chesne A, Brinkmann B. An unusual case of homicidal near drowning followed by electrocution. *Int J Legal Med* 2006;120(1):36–41.

39 Pelissier-Alicot A, *et al.* Planned complex suicide: an unusual case. *J Forensic Sci* 2008;53(4):968–70.

40 L'Epee P, *et al.* [Suicide by electrocution in a bathtub]. *Ann Med Leg Criminol Police Sci Toxicol* 1965;45(6):550–1.

41 Lawrence RD, Spitz WU, Taff ML. Suicidal electrocution in a bathtub. *Am J Forensic Med Pathol* 1985;6(3):276–8.

42 Karger B, Suggeler O, Brinkmann B. Electrocution – autopsy study with emphasis on 'electrical petechiae'. *Forensic Sci Int* 2002;126(3):210–3.

43 Byard RW, *et al.* Death due to electrocution in childhood and early adolescence. *J Paediatr Child Health* 2003;39(1):46–8.

44 al-Alousi LM. Homicide by electrocution. *Med Sci Law* 1990; 30(3):239–46.

45 Pfeiffer H, Karger B. Attempted homicide by electrocution. *Int J Legal Med* 1998;111(6):331–3.

46 Mellen PF, Weedn VW, Kao G. Electrocution: a review of 155 cases with emphasis on human factors. *J Forensic Sci* 1992;37(4):1016–22.

47 Wick R, *et al.* Fatal electrocution in adults – a 30-year study. *Med Sci Law* 2006;46(2):166–72.

48 Arden GP, *et al.* Lightning accident at Ascot. *Br Med J* 1956;1(4981):1450–3.

49 Johnstone BR, Harding DL, Hocking B. Telephone-related lightning injury. *Med J Aust* 1986;144(13):706–9.

50 Resnik BI, Wetli CV. Lichtenberg figures. *Am J Forensic Med Pathol* 1996;17(2):99–102.

51 Domart Y, Garet E. Images in clinical medicine. Lichtenberg figures due to a lightning strike. *N Engl J Med* 2000;343(21):1536.

52 Gupta A. Lichtenberg figures. *J Assoc Physicians India* 2001; 49:1131.

53 Cherington M, *et al.* Lichtenberg figures and lightning: case reports and review of the literature. *Cutis* 2007;80(2):141–3.

54 Mahajan AL, Rajan R, Regan PJ. Lichtenberg figures: cutaneous manifestation of phone electrocution from lightning. *J Plast Reconstr Aesthet Surg* 2008;61(1):111–3.

55 Arnould JF, Le Floch R. Lichtenberg figures associated with a high-voltage industrial burn. *Burns* 2011;37(3):e13–15.

CHAPTER 13

Complications of Injury

- Introduction
- Haemorrhage
- Infection
- Pulmonary embolism
- Fat and bone marrow embolism
- Acute respiratory distress syndrome
- Acute kidney injury following trauma
- Disseminated intravascular coagulation
- Air embolism
- Subendocardial haemorrhage
- Sudden death from suprarenal haemorrhage
- References

Introduction

Serious bodily injury, from whatever cause, may either lead to virtually instantaneous death from destruction of vital organs and structures, or may cause delayed death from complications of the original injury. This delay may be short, as in torrential haemorrhage or acute respiratory failure, or it may be progressively longer, stretching into hours, days, weeks or even years. For example, the author (BK) dealt with a death in which a glider crash 15 years previously had to be implicated as the sole reason for the death, as the victim suffered a fractured spine, a paraplegia, paralysed bladder and recurring ascending urinary infection leading to death in renal failure from bilateral pyelonephritis.

Many even more delayed deaths can be found in the records of most experienced forensic pathologists. As long as a direct chain of events can be traced from the injury to the death, then the former must be considered to be the basic cause, a fact which may have profound legal implications both for civil compensation and criminal responsibility. Some of the most difficult problems in forensic pathology – and some of the most arduous testimony and cross-examination in court – concern deaths from which post-traumatic complications are disputed as being causative factors.

Haemorrhage

Bleeding may occur externally through lacerations and incised wounds or via natural passages, such as the bronchi and trachea, oronasal passages, ears, vagina, urethra or rectum. Internal bleeding comprises contusions, which are leakages of blood into tissue spaces from rupture of vessels and free bleeding into body cavities, notably the pericardium, peritoneum, pleura and cranium.

The volume varies greatly, from the tiny petechiae of ruptured venules to the massive amounts seen in a ruptured aorta. As a primary cause of death it is not only the total volume that is lethal, but the rapidity and the site of the bleeding. When the leakage is slow the body can compensate for the loss of a far greater volume, both by adjustment of the vascular bed and by restoration of the blood volume by transfer from other aqueous compartments.

As to site, it is obvious that a small quantity of bleeding into the brainstem is likely to be lethal, whereas the same volume exuded into the pleural cavity would be of little consequence. Bleeding usually begins at the time of injury, though there is often a momentary delay at the instant of infliction. When a sharp blade cuts the skin, it is a matter of common observation that the blood may hesitate for a second or so before welling out. This is caused by transient spasm of local vessels from the stimulus of the injuring object. Bleeding then continues until normal haemostasis plugs the vessels.

In some injuries involving arteries, the musculoelastic vessel may retract and its wall invaginate, so that an almost immediate seal prevents copious haemorrhage. Occasionally even gross injuries, such as the amputation of a limb by a railway wheel, may be almost devoid of significant bleeding, because the crushing effect may combine with arterial wall retraction to seal the cut vessel effectively. It can sometimes be more dangerous partly to transect an artery than to divide it completely, as retraction cannot then take place. Failure of haemostasis is a haematological matter, but may have medico-legal connotations if an injury (which includes a surgical procedure) is performed on someone who has a haemorrhagic diathesis either from natural disease, or from therapeutic anticoagulant treatment, such as heparin or warfarin.

Delayed bleeding may be seen in a number of conditions. In trauma, especially traffic accidents, organs, such as the liver, spleen or (sometimes) lung, may be injured within their capsules or covering membranes, which initially remain intact. A good example is a subcapsular haematoma of the liver, which may be large and grow even larger as continued bleeding strips more capsule from the parenchymal surface. Eventually, the blister may rupture and the now unrestrained bleeding area can pour into the peritoneal cavity (Fig. 13.1).

Trauma can also weaken the wall of an artery or vein, leading to a false aneurysm, which can later rupture. An arteriovenous fistula can also form and later burst.

Infections can also develop in trauma sites and involve vessels in the vicinity, so that an abscess or cellulitis can secondarily lead to severe haemorrhage when the vessel wall is eroded. This is rare except among poorly treated accident or battle casualties, as are mycotic aneurysms that result from infected emboli impacting in a branch of an artery and causing local septic necrosis.

It is sometimes difficult to know how much of a haemorrhage found at autopsy may be accounted for by post-mortem bleeding. There is little doubt that the volume may increase after death, but, except in serous cavities, such as the pleura and peritoneum, or externally from the body surface, in most cases this is a small proportion of that which leaked under arterial pressure during life, due to the tissue pressures opposing passive bleeding.



Figure 13.1 Massive intra-abdominal bleeding from a subcapsular haematoma of the liver due to blunt abdominal trauma.

However, a haemothorax from a ruptured aorta may amount to several litres and much of this may be in the form of a large shaped clot. A clot can form post-mortem, so its presence cannot be taken as an index of *in vivo* formation, but the source of the bleeding will usually be obvious and any post-mortem addition will not affect the interpretation. Copious external bleeding can continue after death, especially from the scalp, particularly if the head is dependent after death.

Infection

Infection used to be so common after open wounds that it was the norm rather than the exception. Prior to the introduction of sulphonamides and antibiotics, many criminally inflicted wounds, which in themselves were not a danger to life, became fatally infected so that an assault became a homicide. This illustrates the fallacy of comparing murder rates in the last century with today, as the survival rate because of rapidly available ambulance and resuscitation services, blood transfusion, emergency operations and antibiotics is vastly greater now than in former times, when even a trivial injury was often fatal.

The types of post-traumatic infection are legion and vary greatly from country to country. Purulent wound infection from Gram-positive cocci, Gram-negative bacilli, anaerobes, such as *Clostridium perfringens*, and other more common organisms, is the most frequent, but in some countries tetanus and anthrax are common dangers. The whole matter is one of clinical microbiology, and the main forensic relevance is to prove a chain of causation between the original injury and a death from intercurrent infection. There may be medico-legal issues involved, such as failure to give or delay in giving antibiotic cover, which can have both civil and criminal legal consequences. A criminal assault that ends in death because of a neglected infection does not exonerate the perpetrator from all responsibility, even though there has been a *novus actus interveniens* in the form of defective medical treatment.

Pulmonary embolism

This is a most important topic in forensic pathology, as the medico-legal implications of a fatal pulmonary embolus are common and profound. Pulmonary embolism is the most underdiagnosed cause of death where no autopsy is performed; it has been estimated that, in the USA – and probably elsewhere – less than half of fatal pulmonary emboli are recognized clinically.[1,2]

As with infection, an originally non-lethal injury may end in death because of venous thrombosis and pulmonary embolism, making what might be a simple accident or a common assault into a grave legal issue. The victims of many forms of trauma are at risk from pulmonary embolism because:

- Tissue trauma increases the coagulability of the blood for several weeks, the peak being between 1 and 2 weeks.
- Injury to the tissues, especially the legs or pelvic region, may cause local venous thrombosis in the contused muscles or around fractured bones.
- The injury may confine the victim to bed, either because of general shock and debility (especially in old people) or because the trauma itself necessitates recumbency, as in head injuries, severe generalized trauma or injury affecting the legs. In either case, recumbency leads to pressure on the calves and immobility causes reduced venous return and stasis because of lessened muscular massage of the leg veins. The common result is thrombosis of the deep veins of the legs, which can extend proximally into the popliteal and femoral vessels, forming a dangerous source of venous thromboemboli. Small emboli may break off and impact in more peripheral branches of the pulmonary arteries, sometimes causing pulmonary infarcts that may be precursors of a massive embolus that impacts in the major lung vessels and causes rapid death.

At autopsy, such large emboli are readily visible and can usually be easily distinguished from post-mortem clot. The latter is dark red, soft and jelly-like, with a shiny, glistening surface. It is often separated into ‘chicken-fat’ plasma clot and dark red-cell clot by sedimentation after death. When pulled out of the vessels it forms a cast of the branches, albeit shrunken by clot retraction. It is less evident in peripheral branches and, when the lung is sliced post-mortem, clot does not pour out of cut small vessels.

Conversely, ante-mortem embolus (especially if a number of days old) is firm, though brittle and has a dull, matt, striated surface from fibrin lamination. Older thrombus tends to be greyish-red and varies in colour from place to place. Although it may appear to be a cast of the large vessel in which it is impacted, it may often be unravelled to form a long length that obviously originated in a leg vein. Side branches, or the stumps thereof, may be seen that do not correspond to the branches of the pulmonary artery in which they lie.

Post-mortem clot may be adherent to the ante-mortem embolus and sometimes forms a sheath around it, so that the true nature is obscured unless a careful examination is made. On cutting the lung with a knife, ante-mortem emboli may be seen in the more peripheral vessels, often standing up slightly ‘proud’ above the surface, like toothpaste coming from a tube.

The importance of the differentiation between ante-mortem emboli and post-mortem clot is emphasized, as the legal issues hanging upon the unequivocal diagnosis may be very important. Histological confirmation of an ante-mortem origin must be made if there is any doubt. Pulmonary infarction does not occur from fatal massive pulmonary embolism, as death is too rapid. There may be infarcts present in the lungs but these must be caused by previous smaller emboli, at least a day earlier and probably much longer.

Medico-legal aspects of pulmonary embolism

Pulmonary embolism is the most underdiagnosed condition in British death certification, frequently being unsuspected as the cause of death by clinicians. The various aspects of pulmonary embolism have been investigated in several retrospective autopsy surveys with somewhat different results depending on the source and era of the material.[1,3–9] Knight and Zaini made a survey of 38,406 post-mortem investigations of the Institute of Pathology at the Welsh National School of Medicine between the years 1908 and 1977. In 1176 subjects the cause of death was recorded as being due to pulmonary embolism.[4] It is noteworthy that there was not a single death recorded from pulmonary embolism during the first two decades of the period, *viz*., 1908–1927, suggesting that the recognition of pulmonary embolism and autopsy techniques were deficient. In trauma cases the peak incidence was at about 2 weeks after traumatization, whereas in series by Lau the peak time of death following trauma and/or immobilization was 1 week.[6] In a comparative study of autopsy incidence in Hong Kong and Cardiff, Wales, Dickens *et al.* found that, when comparing a similar case mix, the incidence of fatal pulmonary embolism in the period studied was 3.58 per cent for Hong Kong and 4.2 per cent for Cardiff. The age distribution for the patients dying in hospital was very similar in both locations, with the majority of cases in patients over 60 years and the maximum incidence in the age group 80 years and above, with mean ages of 72 for Hong Kong and 77 for Cardiff.[7] Steiner surveyed the change of pulmonary embolism incidence over time in a series where virtually all subjects came from one tertiary-care university hospital. In the six reference years 1960, 1970, 1980, 1990, 2000, and 2005 there was a total of 3,877 adult autopsies. Pulmonary embolism was found in 628 patients; the overall incidence in the 6 reference years was 16.2 per cent. The incidence showed a steady decline, from 19.2 per cent in 1960 to 10.0 per cent in 2005.[9]

In Knight's survey, more than three-quarters of the victims had predisposing factors such as injury, surgical operation or immobility in bed, but the remaining 20 per cent were ambulant and apparently healthy. This has important medico-legal implications because, if fatal pulmonary embolism can strike an appreciable proportion of the population who have not suffered one of the recognized predisposing factors, then the cause–effect relationship after trauma is weakened. If the standard of proof in criminal trials must be 'beyond reasonable doubt', then the fact that up to 20 per cent of pulmonary embolism deaths have not followed trauma or immobility must surely remove the cause–effect relationship from near-certainty to mere probability, which is sufficient for a civil decision, but not for a criminal conviction. This is a legal matter for the judge, however, who may or may not let the matter go to the jury – and if it does, for the jury to decide. There is marked variation in these decisions from case to case.

After the lung appearances have been examined and pulmonary embolism confirmed, the source of the embolus must be sought. In almost all cases this will be found in the vessels draining into the femoral veins, though rarely pelvic vessels are involved (usually in relation to pregnancy or abortion). Here pelvic veins may be thrombosed, with extensions into the iliac system and exceptionally into the inferior vena cava. An even more rare source is from jugular thrombosis, sometimes seen as extensions of intracranial venous sinus thrombosis. Axillary and subclavian vein thrombosis is equally unusual, the legs accounting for the vast majority of emboli.

In the usual leg vein thrombosis, various autopsy techniques are available to seek the site of obstruction. Extensive dissection is favoured by some, in which the femoral vein is exposed through a skin incision, this being continued distally as far as necessary to find the residual thrombosis. Of course, after a massive pulmonary embolus, by definition a large part of the source thrombus has been detached and therefore the pathologist has to search further distally to find the remnants. This makes dissection an extensive and disfiguring process, so alternative techniques can be used.

Zaini found that many thrombi begin far distally, even in the dorsum of the foot. He used a flexible wire with a blunt terminal knob (a Bowden cable from a bicycle brake) inserted down the femoral vein until it was arrested, then cut down from the skin at that point to examine the peripheral veins. Alternatively, transverse or longitudinal incisions can be made into the calf of the leg to examine the deep veins. The soleus and gastrocnemius muscles are transected to view their contained veins, but often the thrombus is found in the interosseous veins between tibia and fibula. If ageing of the thrombus is attempted histologically, then it should not be expressed from the vein, but the vein should be taken out with adjacent muscle, as it is the junction between thrombus and vein wall that offers the most information about the maturity of the thrombus.

Dating of pulmonary emboli and deep vein thrombi

As discussed above, it can be a matter of considerable medico-legal importance to know if a pulmonary embolus arose prior to, or subsequent to, some traumatic event. A major difficulty is that the embolus may be the most recent addition to an extending venous thrombosis that is considerably older.

It is also difficult to use histological criteria to date the free embolus from the lungs, as it is the thromboendothelial junction that provides the most information. The best method, therefore, is to examine the residual thrombus, almost always in the leg veins, to see if the oldest part could have formed as far back in time as the suspected traumatic event. For this, the vein wall with the contained thrombus is required. A segment of thrombosed vein, if necessary with adjacent muscle, should be dissected out of the leg. The presence of thrombus will have been confirmed prior to removal by transverse cuts across the calf or thigh muscles containing the veins. Sometimes the original site of thrombosis may be as far distal as the dorsum of the foot.

The thrombus-containing vein is processed in the usual way and subjected to various histological stains. Though accuracy about dating is impossible, the following is a useful scheme to provide at least an approximate idea of the duration of thrombosis in the section of vein under study – remembering always that other segments or other veins may have thrombi of different dates.

- Platelet and red-cell appearances give no useful information. Red cells begin to haemolyse between 24 and 48 hours to form amorphous masses, but many intact red cells survive for weeks.
- Using phosphotungstic acid-haematoxylin stain (PTAH), fibrin can be seen as purplish strands on the first day, but they aggregate into small masses with a meshwork of thicker strands and sheets by 4 days. After 2 weeks, the fibrin becomes more deeply purple stained, but begins to be absorbed by about the 25th day. Using Martius scarlet blue stain (MSB), the early pink fibrin strands become fringed by scarlet in about 1 week.
- Endothelial proliferation is most useful in the first week, as buds begin to arise from the vessel wall about the second day and proliferate during the first week. Clefts lined by endothelium are seen around the periphery of the thrombus against the vein wall. Artefactual contraction caused by fixation shrinkage must be excluded by seeking endothelial nuclei. These endothelial buds anchor the thrombus to the vein wall, and represent the first stage of healing and recanalization. They are usually noticeable by about the fourth day when they begin growing into the fibrin mass and breaking it up into compartments.
- Collagen fibres do not appear for about 5–10 days, often much later. Fibroblasts may be seen as early as 2 or 3 days, but tend to appear towards the end of the first week and reach a maximum at 2 or 3 weeks, reaching a maximum at about 4 weeks. Elastic fibres appear late, not before 28 days and often much later. They reach their maximum density in about 2 months, mainly in the walls of recanalizing vessels.
- Haemosiderin, blue granules demonstrated by Perls' reaction, may be seen by the end of the first week and reach a maximum in 3 weeks. It does not seem to be present as early in thrombi as in extravascular haemorrhages, such as bruising or meningeal bleeding, where it can be seen in 2 or 3 days.
- Capillaries begin to appear on the second day as endothelial buds, but do not contain red cells until about 2 weeks. Over the next 3 months, substantial canalization occurs by widening and merging of these channels. The full lumen may be restored within 6–12 months, but endothelial thickening and haemosiderin deposits in the vein wall may form permanent evidence of a former thrombus.
- Leucocytes, both polymorph and mononuclear, are inconsistent markers; sometimes they do not appear at all. Polymorphs may be seen within the first day – sometimes in profusion – but they vanish rapidly, often by the next day when mononuclears take their place.
- Covering of the thrombus surface by endothelium is rapid and may begin on the first day and be complete within a few days. Various authors have given 24–72 hours as the time required. Naturally, the size of the thrombus surface is a variable factor. Also, only sections taken where the thrombus does not fully fill the vein lumen will provide an opportunity for observing the endothelial covering.

Fineschi *et al.*[10] investigated 140 selected cases of pulmonary embolism using immunohistochemistry and confocal laser scanning microscopy (CLSM) to assess the chronological transformation of the thrombus and to determine the causal relationship with the pulmonary embolism as the cause of death. They concluded that only three chronological stages (Phase I: 1st – 7th day; Phase II: 2nd – 8th week; Phase III: older than 2 months) can be distinguished with any degree of certainty using immunohistochemistry and CLSM, emphasizing the complexity of this issue (for details see ref 10).

Fat and bone marrow embolism

Another important sequel to trauma – fat embolism – is the subject of considerable controversy about the source of the lipoid; this does not, however, detract from the autopsy significance of its detection.

A great deal has been written about the pathophysiology of fat embolism and it is now evident that it is not just a simple extrusion of marrow or adipose tissue material by mechanical trauma.[11–22] Wherever the fat comes from, embolism is most often seen after injury to bone or fatty tissue. In simplistic terms, where skeletal structures containing fatty marrow are damaged or where subcutaneous fat is compressed or lacerated, fat globules commonly appear in the pulmonary capillaries – and where they are numerous they somehow leak through the lungs into the systemic circulation where they can cause severe disability or death from impaction in vital organs, such as brain, kidney or myocardium. Not only fat, but cellular haematopoietic tissue from bone marrow, can be liberated into the venous system and reach the lungs.

The clinical manifestations of fat embolism depend on the volume of fat reaching the lungs. If substantial, ventilatory problems can ensue because of vascular obstruction and pulmonary oedema. The most dramatic symptoms occur, however, with systemic fat embolism when globules reach the brain and cause a range of neurological abnormalities, usually coma and death from brainstem involvement.

There is usually a delay between trauma and cerebral fat embolism while fat builds up in the lungs, so that a 'lucid interval' occurs, which may be confused clinically with the development of an extradural or subdural haemorrhage. Sevitt stated that of patients with multiple bone fractures, no fewer than 45 per cent had pulmonary fat emboli and 14 per cent had cerebral embolism.[17]

Fat embolism is also associated with burns, barotrauma, soft tissue injury, osteomyelitis, diabetes, surgical operations on fatty tissues (especially mastectomy), septicaemia, steroid therapy, acute pancreatitis and the fatty liver of alcoholism, though fractures remain the most potent cause of the condition. In burns, there is some doubt whether pulmonary fat embolism is a true ante-mortem process, or whether fat can be melted out of tissues and organs in the perimortal period. Mason's experience in rapid air-crash fires was that fat embolism was not present,[23] but Sevitt's hospital series revealed embolism in 47 per cent of deaths from burns.[17]

Pulmonary fat embolism

After trauma, fat commonly appears in the lungs and can be demonstrated there histologically in the majority of cases of fractures and injury to fatty parts of the body such as the buttocks. Indeed, Lehman and Moore (1927) showed that half of a series of non-trauma deaths had histological evidence of fat in the lungs.[14] Mason found fat in the lungs of 20 per cent of his series of non-trauma deaths, but emphasized that quantitatively the amount was small in contrast to that found in cases of fatal trauma.[23] He used a simple scale for assessing the histological severity of embolism as seen in Oil Red-O frozen sections of lung (Fig. 13.2):

- Grade 0: no emboli seen.
- Grade 1: emboli found after some searching.
- Grade 2: emboli easily seen.
- Grade 3: emboli present in large numbers.
- Grade 4: emboli present in potentially fatal numbers.

In systemic fat embolism, no such grading is possible; they are either absent or scanty, or they are abundant.

In most instances, pulmonary fat embolism is merely a phenomenon and not a clinical syndrome and the difference between the two seems closely related to the amount of fat impacted in the lung vessels. When clinically manifest it appears as acute respiratory insufficiency, the incidence being up to 2 per cent in long-bone fractures and as much as 10 per cent in multiple fractures, especially with pelvic injuries. In small to moderate amounts, fat in the lungs gives rise to no disability, but large amounts, easily seen by a cursory glance at any field of a fat-stained histological section, give rise to acute respiratory distress. Marked pulmonary oedema is the pathological marker for this syndrome, but caution must be employed, as cerebral fat embolism can also cause pulmonary oedema by its effect upon the brain.



Figure 13.2 Pulmonary fat embolism (Oil Red-O frozen section of lung; original magnification ×20).

Systemic fat embolism

Here the fat penetrates the lung capillaries and appears in the major circulation, so that it can be carried to any organ or structure, including the skin, where it can cause petechial-like lesions. Systemic fat embolism is the fatal manifestation, except where pulmonary loading is so great that it causes respiratory distress. The brain, kidneys and myocardium are the most vulnerable target organs, the brainstem being the one that is most likely to lead to death from impaction of fat globules in its capillaries.[24–26]

Autopsy findings in fat embolism

When fat is released through the lungs into the systemic circulation, a number of target organs and tissues exhibit abnormalities demonstrable at autopsy, either by gross or histological examination.

Petechial haemorrhages are the typical lesion, caused by the impaction of fat droplets in small venules. These may be seen in the skin of any part of the body, but especially over the front of the chest and on the face and eyelids. Internally they can be widespread but are classically seen in the white matter of the brain, both cerebral and cerebellar hemispheres, as well as the brainstem. Microscopically, when frozen sections are stained by Oil Red-O or other fat stain, the cerebral petechiae will show a central fat globule or globules, and others will be visible without haemorrhage.

In the myocardium, fat may be seen in the inter-fibre capillaries and in the kidney glomeruli may be stuffed with stained fat. There can be fat in the retina and in the optic nerve, which, in survivors, can cause visual impairment.

Fat embolism is markedly underdiagnosed, both clinically and at autopsy. The more often and the more thoroughly it is sought, the more often it is found. Mild to moderate degrees of pulmonary fat embolism, without systemic overspill, however, must not be given as a cause of death unless there are corroborative clinical features.

Bone marrow embolism

Bone marrow embolism is almost wholly a pulmonary phenomenon, as only in quite exceptional circumstances can cellular material penetrate the lung capillaries, though again the frequency with which it is seen is directly related to both awareness and the thoroughness of the search. Bone marrow embolism within the pulmonary arteries was first observed in animal experiments and man by Lubarsch and his pupil Lengemann and almost simultaneously and independently by Maximow in trauma experiments with rabbits.[27–29] In addition to traumatic deaths with bone fractures, bone marrow embolism has been observed in cases of post-convulsive deaths due to tetanus, eclampsia, convulsive shock therapy, electrocution, and therapeutic or investigative procedurers, such as thoracotomy, sternal puncture, cardiac massage, or traumatic deaths as in blast injury.[30–36] It is quite common in association with fractures of long bones or in multiple bone injuries and may or may not be associated with fat embolism. The common concurrence of fat and cellular embolism is strong evidence of a marrow source for embolic fat, as pointed out by Mason, who found marrow cells in 81 per cent of his cases that had a grade 2 or more lung loading with fat, on a scale of 0–4. According to both Sevitt and Mason, the finding of both substantial fat and marrow emboli in the lungs is definite evidence of ante-mortem infliction of any discovered trauma.[17,23] For these elements to reach the lungs there must be a competent circulation, albeit for a short time after the trauma (Fig. 13.3).

With the possible exception of burns, any injury inflicted after cessation of effective cardiac function cannot transmit fat or marrow to the pulmonary capillary bed. This is therefore a useful forensic marker on some occasions, such as differentiating between ante-mortem and post-mortem fractures in a body recovered from water. Systemic embolism is not seen in rapid deaths following trauma: there is an interval averaging 24 hours before lung percolation takes place.

Foreign body embolism

A number of other objects may be found as emboli during forensic autopsies and histology. The lung granulomata of talc, etc., seen in the lungs of intravenous drug users, are emboli from contaminants introduced into the venous system by syringe and needle (Fig. 13.4).[37–44] Shotgun pellets and bullets may enter the circulation via tissue



Figure 13.3 Pulmonary bone marrow embolism (Van Gieson staining, original magnification ×10).



Figure 13.4 Small perivascular granuloma in the lung of a drug addict showing in polarized light birefringent material from the use of adulterated drugs.

damage and embolize to various sites including coronary arteries.[45–51] In fat and bone marrow embolism, even fragments of bone and cartilage have been found as emboli in the lungs.

Amniotic fluid embolism is discussed elsewhere.

Acute respiratory distress syndrome

Following severe lung injury, such as gross impact upon the thorax or blast injury from explosion, or from aspiration of gastric contents, infections, toxins, systemic shock, irritant gases, near-drowning and many other causes, the lung epithelium may suffer 'diffuse alveolar damage'. Clinically the victim may suffer marked dyspnoea and progressive respiratory failure, becoming hypoxaemic. Pathologically the lungs show a stiff oedema that progresses to a rigid, infiltrated lung if survival is long enough. At autopsy the lungs are hard and retain their shape after removal, having a 'dry-oedema' appearance, being almost double in weight in some instances.[52,53]

Histologically the initial changes are shedding of type I pneumocytes with intra-alveolar exudates, the formation of hyaline membrane and patchy alveolar haemorrhage. This destructive phase is then replaced after a few days with a proliferative stage, when type II pneumocytes begin to fill the alveoli and a mononuclear response infiltrates the interstitial areas. The alveolar proliferation organizes, if survival continues, and eventual pulmonary fibrosis may seriously incapacitate the half who survive. A typical progression is seen in paraquat poisoning, though here there are virtually no long-term survivors.

A condition that is similar to the appearances of acute respiratory distress syndrome is the so-called 'respirator lung', which develops when a patient dies after an appreciable period of mechanical ventilation. It may appear within a few days, but usually supervenes after many days or weeks on a ventilator. The gross appearances are of a stiff, rigid lung, which, though heavy, does not usually appear obviously oedematous. Microscopically, proteinaceous fluid and a mixture of proliferative cells may be seen in the alveoli.

Acute kidney injury following trauma

Acute kidney injury (formerly known as acute renal failure), is a clinical syndrome characterized by a rapid decrease of the kidney's excretory function or decreased urinary output, or both.[54] It is common sequel to extensive muscle damage or to burns that affect considerable areas of skin, as well as from certain poisons. It was formerly ascribed most often to 'acute tubular necrosis', but recent experimental work has thrown some doubt upon this as an accurate clinicopathological entity.[55] When muscle is crushed, severely torn or otherwise rendered ischaemic, where extensive burns are suffered or where poisons, such as mercuric salts or carbon tetrachloride, are given, destruction of the renal tubular epithelium may be seen.

Unfortunately for histological diagnosis, a similar change occurs during post-mortem autolysis. In burns and muscle damage, the tubules may also be blocked with brown casts of myoglobin and these two changes of distal tubular necrosis and casts were thought to cause the profound oliguria or anuria often associated with trauma and burns. In biopsy as opposed to autopsy material, however, the tubular damage has been found to be minimal and the casts may be a sequel to reduced filtration rather than to tubular damage, so the validity of 'acute tubular necrosis' as an explanation of renal failure following trauma has been questioned. The true mechanism is still obscure, but may well involve the juxtaglomerular apparatus and the renin–angiotensin system, as well as disseminated intravascular coagulation effects on the glomeruli.

Disseminated intravascular coagulation

The importance and frequency of this condition has been increasingly recognized in recent years, as it may follow a whole range of traumatic, infective and other acute events. Widely known as 'DIC', it has a number of other names indicating that it is a consumption coagulopathy associated with the blood clotting mechanism.

In DIC there is an abnormal activation of the coagulation process within the blood vessels caused by a wide variety of factors related to the blood itself, the vessel walls and to blood flow. Damaged tissue from trauma and burns can trigger thromboplastin-initiated coagulation: entry of tissue cell elements, especially from erythrocytes, brain and placenta are particularly potent. Particulate matter such as micro-organisms or microemboli of all types (including fat and air emboli, especially those from decompression) can precipitate coagulation via factor XII. Vascular endothelial damage and stasis of blood flow can have a similar effect.

Whatever the causes – and they are extremely complex – fibrinogen is consumed and fibrin precipitated in vessels, leading to both vascular obstructive effects and to a haemorrhagic diathesis from depletion of the coagulation system. Platelets are also consumed, adhering to the fibrin thrombi. Fibrinolysis is activated and there is a dynamic contest between intravascular coagulation and its removal.

After death there can be post-mortem fibrinolysis,[56] which lessens the ease with which fibrin deposits can be detected; staining techniques are also an imperfect method of visualizing the fibrin, so that a careful search must be made in autopsy histology for fibrin remnants. Lungs, kidney, liver and adrenals are the most likely organs to yield positive results.

Microvascular obstruction, leading sometimes to frank infarction as well as reduced function, together with bleeding, form the major dangers of DIC in a forensic context.

Air embolism

Most examples of air embolism have a medico-legal significance as the entry of air into the circulation usually comes about as a result of trauma, sometimes surgical or therapeutic, from barotrauma or from criminal intervention.

Air embolism consists of an interruption of the circulatory system by bubbles of air (or other gas) that gain access to the circulation, usually through the venous side. It is an 'airlock', familiar to plumbers and owners of diesel engines, where the normal flow of liquid through tubes is wholly or partially blocked by air.

In the animal body the major disability is in the heart, as air is compressible and the contractions of the heart fail to move on the bolus of gas, being designed to pump an incompressible liquid. The air must enter on the venous side to be sucked towards the heart, causing pulmonary air embolism. The air usually remains in the right side of the heart, pulmonary trunk and arteries, and in the pulmonary vessels, rarely emerging on the pulmonary vein side. Death is usually immediate, but can be delayed by up to about 2 hours.

In the surgical context, aspiration of air into neck veins may occur while operating on the head or neck (especially thyroid and neurosurgical operations) with the patient in a sitting position. When the atria are below any breach in a vein, there is a suction effect that can draw in air; this can also happen in suicidal or homicidal cut throat. Refilling of a therapeutic pneumothorax has also led to fatal air embolism, either because the lung is punctured or an adhesion has torn the visceral pleura. In either case air under pressure may enter an exposed vein.

Some accidents have arisen during transfusion or infusion, and may form the basis for a medical negligence action. Now that flexible, collapsible fluid or blood containers are widely used the danger is less, but where rigid bottles are still used, the need for a vent tube may allow air to enter the connecting tubing when a bottle is allowed to empty completely. This in itself is innocuous, but if a fresh bottle is then connected, the new flow will drive all the air in the tubing into the vein.

Even more dangerous is the practice of connecting pressurized air or oxygen to the vent in order to hasten the transfusion speed: if the bottle is allowed to empty, gas under pressure enters the vein.

Arterial air embolism is rare, but can occur in lacerations of the lungs, refilling of an artificial pneumothorax or in some forms of barotrauma where the lung is ruptured in a diver who ascends too rapidly from a great depth. The 'bends' are also a type of gas embolism, in which dissolved nitrogen appears in gaseous form in the blood. This is caused by a sudden release of pressure on the return of a diver to atmospheric conditions after being supplied with air at high pressure. Death can be the result of air locks in the cerebral vessels or of ventricular fibrillation from coronary air embolism.[57]

Criminal abortion accounted for many deaths from air embolism in former years (and still does in some parts of the world), from the insufflation of the uterus by a Higginson syringe (Chapter 19). Though therapeutic abortion by suction aspiration of the uterine contents is an extremely safe procedure, several somewhat inexplicable deaths have occurred from air embolism. The mechanism is obscure but may have been caused by muscular rebound of the uterus sucking air into the cervix. Some homicides, including 'mercy killings' committed by doctors, have been caused by deliberate injection of air into peripheral veins. The volume of air needed to cause fatal embolism has been hotly debated for years, but no real consensus has emerged, estimates varying from 10 to 480 ml.[58] If the volume of the right side of the heart is accepted as the minimum space that has to be filled, about 100 ml would appear to be a reasonable volume. In the rare event of air gaining access to the arterial system, presumably much less would be required to be effective; it would have to be introduced into a carotid artery to be of much danger, as this is the only way it could gain access to the cerebral circulation. To reach the coronary vessels – always mentioned in books, but virtually never seen – the air would have to enter the pulmonary veins to reach the root of the aorta via the left side of the heart. Virtually all of the few cases of arterial air embolism have arisen in relation to dysbarism, where bubbles have either been generated within the vessels by decompression, or have entered the arterial system in the lungs from tears in the lung tissue.

Certainly air injected into a limb artery would do no harm at all, especially as most of the gas is likely to be absorbed very rapidly by the tissues. Thus the ingenious plot in Dorothy L. Sayer's novel, *Unnatural Death*, where 'a hypodermic of air was injected into an artery' would have failed on two counts: site and volume!

The autopsy in suspected air embolism

When the circumstances indicate the possibility of fatal air embolism, special precautions must be taken over the autopsy. Air embolism or gas accumulations in diving fatalities are best examined using computed tomography (CT) but if such a facility is not available a pre-autopsy chest radiograph must be taken, as this is then the next-best way of demonstrating air in sufficient quantities to be fatal (Fig. 13.5).[59–62] A chest radiograph is also essential in any kind of barotrauma as it may also indicate a pneumothorax, a lesion so often the cause of air embolism.

Almost the only mechanism of death is 'pump failure' of the right side of the heart. Air fills the great veins, right atrium and right ventricle, causing a froth that cannot be pumped on by the heart in systole because air is compressible. It is unlikely that air will penetrate the pulmonary capillaries in any quantity, unless some vascular shunts are present, so froth is unlikely to be seen in the left side of the heart, except in dysbarism.

Following radiography – in place of it, as second-best – the body must be carefully inspected for any tissue swelling, especially in the upper thorax and neck region, where crepitant gas bubbles may form surgical emphysema from leakage from lung damage or pneumothorax, or both, in dysbarism.



Figure 13.5 AP view on a volume rendering (VR) air reconstruction of a CT data set in a gunshot to the head. Only soft tissue and gas borders are visible. Within the mediastinum the right atrium, the right chamber, the main pulmonary artery and the right pulmonary artery are displayed (arrows) only due to their gaseous content (lethal air embolism). (Reproduced by kind permission of Professor C. Jackowski.)

The head should be dissected first, not to detect air bubbles in the cortical veins, as almost every textbook erroneously states, but to look for air in the cerebral arteries. Descriptions and photographs of air segments in the cerebral veins are part of the mythology of forensic pathology, handed on uncritically from one book and one author to another. There is no way in which air bubbles can reach the pial veins on the brain surface. They cannot get there via the venous system, as there is no way in which they could struggle against the flow in the jugular veins, pass through the complex arrangement of intracranial venous sinuses retrograde to the circulation and dispose themselves over the cortical surface. Neither can they reach the same veins by penetrating the capillary bed of the brain, in the rare instances of arterial air embolism. As was demonstrated almost 30 years ago, these bubbles are artefacts and can be seen in many routine autopsies where there can be no question of air embolism.

The basal arteries should be inspected for air, however, which can reach them during episodes of dysbarism where air gains access to the arterial system in the lungs during decompression. The calvarium is removed gently and the dura opened. The brain is carefully lifted and small artery forceps clamped on the intracranial part of both internal carotid arteries and vertebral arteries. The vessels are then cut below these before the brain is removed from the skull in the usual manner. The whole pluck can then be submerged in water and the ends of the vessels watched for escaping bubbles when the clamps are removed.

The thorax is opened in the fashion appropriate for the detection of a pneumothorax, with puncture of an intercostal muscle beneath a pool of water supported by the reflected skin flap. This is done on each side, remembering that a positive result can only be expected in a *tension* pneumothorax.

The abdomen should next be examined, especially where air may have gained access through the uterus. The intestines should be gently displaced and the mesenteric veins examined for air bubbles. The inferior vena cava, the common iliac veins and the various pelvic veins should be scrutinized, and, if necessary, opened under water by pouring water into the opened abdominal cavity.

The sternum and costal cartilages are then removed carefully, preferably keeping the manubrium and upper ribs intact at this stage to avoid damage to the great vessels in the thoracic inlet. The superior vena cava should be inspected for bubbles. The pericardium is opened and the right and left ventricles punctured under water.

Bajanowski *et al.* consider that an aspirometer has to be used for the detection, measurement and storage of gas originating from the heart ventricles.[63,64] It should be filled completely with distilled water containing two drops of Tween 80 to reduce the surface tension of the water to prevent adherence of small air bubbles to the wall of the aspirometer. Subsequently the gas should be analysed by gas chromatography and the results assessed according to the criteria defined by Pierucci and Gherson before the diagnosis ‘air embolism’ is justified (Figs 13.6, 13.7).[65,66]



Figure 13.6 An aspirometer should be used to recover air from the heart ventricles for subsequent analysis by gas chromatography.



Figure 13.7 Leucocyte and platelet accumulation around an empty space, ‘air bubble’ in blood, considered by some authors as evidence of venous air embolism. (Figure reproduced by kind permission of Professor E. Lignitz.)

If air embolism substantial enough to have caused death is present, frothy blood will be quite evident oozing from the ventricular lumen, almost invariably the right. If this is apparent, however, it will almost certainly already have been seen on the pre-autopsy radiograph.

If there has been a considerable delay between death and autopsy, the air can dissipate, presumably dissolving into the tissues. Any degree of decomposition of the body negates a diagnosis of air embolism, because of the production of gases of putrefaction.

Subendocardial haemorrhage

A striking feature of many forensic autopsies, especially on victims of severe trauma, is the presence of well-marked haemorrhage under the endocardium of the left ventricle. This is often so striking as to provide an indication of some catastrophic event shortly before death.

Though the haemorrhages have been described since the last century, they were specifically studied in the 1930s by Sheehan in cases of abortion and acute haemorrhage associated with pregnancy; they were formerly known as ‘Sheehan’s haemorrhages’.

The lesions are seen in the left ventricle, on the interventricular septum, and on the opposing papillary muscles and adjacent columnae carneae of the free wall of the ventricle. The haemorrhages are flame-shaped and confluent, not petechial, and tend to occur in one continuous sheet rather than patches. The bleeding is in a thin subendocardial layer, but when severe may actually raise the endocardium into a flat blister that can be palpable on the smooth septum. The mechanism of production is obscure, but they are commonly seen in the following circumstances:

- After sudden, profound hypotension, either from severe blood loss or from 'shock' in the widest sense.
- After intracranial damage, from head injuries, cerebral oedema, surgical craniotomy or large intracranial tumours. Sudden intracranial decompression also seems to be associated with subendocardial bleeding.
- Obstetric catastrophes seem particularly prone to produce these haemorrhages, as found by Sheehan. Death from ante-partum or post-partum haemorrhage, ruptured ectopic gestation, abortions of various types and ruptured uterus often reveal these lesions.
- Various forms of poisoning, especially acute heavy-metal toxicity, particularly arsenic. The most profound subendocardial haemorrhages ever seen by the author (BK) were in a massive suicidal poisoning with arsenious oxide: the endocardium was raised into a large blood blister on the interventricular septum.

The haemorrhages can appear extremely rapidly, within a few heartbeats. The author (BK) has seen well-marked lesions in a heart that was avulsed from its base during the crash of a military aircraft, obviously causing virtually instantaneous death. Similar observation in an aircraft crash has been reported by Hellerich and Pollak, who attributed them to mere local tissue bruising at the moment of impact.[67] The common factor seems to be sudden hypotension and it has been suggested that, if the intraventricular pressure drops precipitously, the existing blood pressure in the coronary system is then unsupported across the endocardium by an equal pressure within the ventricular lumen, so that rupture of the superficial vessels occurs. There are flaws in this theory, one being the common incidence in intracranial lesions. Experimental work in goats has shown that prior vagotomy prevents the occurrence of subendocardial haemorrhages, suggesting that the phenomenon is mediated by the autonomic nervous system. To support this hypothesis, they are known to be part of Virchow's triad of 'pulmonary oedema, gastric erosions and subendocardial haemorrhage' seen in head injuries and cases of raised intracranial pressure.

Keil *et al.* compared the macroscopic and microscopic findings in 175 samples of endocardium presenting such haemorrhages of varying intensity. They reported that only 8.6 per cent showed a histological correlate and therefore could be verified as true haemorrhage, whereas 53.7 per cent presented mere hyperaemia and the remaining 37.7 per cent could not be microscopically verified. The authors were not able to give a satisfactory explanation to these findings, as they did not seem to depend on their localization nor did they differ in relation to the cause of death or resuscitative measures.[68] In a series of 1,034 consecutive forensic autopsies by Harruf subendocardial haemorrhage was observed in 43 subjects of which 26 (60 per cent) died of head injuries.[69] An analysis of 1331 forensic autopsy reports by Plattner *et al.* showed that head injury and significant blood loss alone or in combination were the main mechanisms of death associated with subendocardial haemorrhage. The incidence of subendocardial haemorrhage was 50 per cent in exsanguination, 80 per cent in combined exsanguination and head injury, and 31 per cent in solitary head trauma. They concluded that subendocardial haemorrhages are important indicative signs for both fatal exsanguination and brain injury at medico-legal autopsies.[70]

Sudden death from suprarenal haemorrhage

Though not common, haemorrhage into the adrenal glands is a well-recognized terminal event, usually after some trauma to the body not related to direct injury to the suprarenal vessels themselves.

Originally these haemorrhages were thought to be confined to meningococcal septicaemia in children, the lesion being called the 'Waterhouse–Friderichsen syndrome'. It is now recognized that adrenal haemorrhage is part of a general response to stress, of which meningococcal infection is only one of a wide range.

In a recent 5-year period, the author (BK) found 16 cases of 'adrenal apoplexy' (to give it its old name) in the autopsy records of a forensic pathology service that performed 4890 autopsies in that period, giving an incidence of about 0.3 per cent.

Of these 16 cases, more than half (9) were bilateral. There were more male than female subjects, probably because of the greater amount of trauma in males. Three were infants, all with meningococcal infections.

None of the adult cases was diagnosed or even suspected clinically. Most were traffic accidents, the remainder being post-operative, other trauma or poisoning, together with several cases of hypertension and chronic renal failure. The most frequent common denominator was trauma, whether that trauma was direct injury or surgical trauma. The sudden collapse and rapid death usually occurred a few days after the trauma, varying from 2 to 21 days.

At autopsy one or both of the adrenal glands are found to be swollen, sometimes to the size of a large walnut (3–5 cm) the cortex being tightly stretched around a large haematoma occupying the medulla. The haemorrhage is usually dark red and fairly fresh, though occasionally an area of brown bleeding indicates a previous episode.

The late Professor Hugh Johnson, of St Thomas' Hospital, London, collected between 150 and 200 autopsy cases of suprarenal haemorrhage (unpublished) and considered that they fell into six main groups:

- Trauma of all types. Johnson was of the opinion that the predominance of right-sided gland haemorrhages was a result of the frequency of right-sided impacts on pedestrians in Britain because of the side of traffic flow.
- Perinatal, newborn or stillborn infants, especially when they were breech births or had fetal anoxia.
- Infancy and childhood, especially meningococcal and disseminated intravascular coagulation.
- Infective and post-operative septicaemia, often with Gram-negative organisms. Sometimes there was direct surgical trauma to the gland, as in gastric surgery.
- Tumour: haemorrhage into a secondary deposit or invasion of adrenal vasculature.
- Thrombosis of central vein with adrenal infarction.

References

1 Sandler DA, Martin JF. Autopsy proven pulmonary embolism in hospital patients: are we detecting enough deep vein thrombosis? *J R Soc Med* 1989;82(4):203–5.
2 Patriquin L, Khorasani R, Polak JF. Correlation of diagnostic imaging and subsequent autopsy findings in patients with pulmonary embolism. *Am J Roentgenol* 1998;171(2):347–9.
3 Knight B. Fatal pulmonary embolism: factors of forensic interest in 400 cases. *Med Sci Law* 1966;6(3):150–4.
4 Knight B, Zaini MR. Pulmonary embolism and venous thrombosis. A pattern of incidence and predisposing factors over 70 years. *Am J Forensic Med Pathol* 1980;1(3):227–32.
5 Zaini MRS. Medicolegal aspects of pulmonary embolism. In: *Medical Faculty*. Cardiff: University of Wales, 1981.
6 Lau G. Pulmonary thromboembolism is not uncommon – results and implications of a five-year study of 116 necropsies. *Ann Acad Med Singapore* 1995;24(3):356–65.
7 Dickens P, *et al*. Fatal pulmonary embolism: a comparative study of autopsy incidence in Hong Kong and Cardiff, Wales. *Forensic Sci Int* 1997;90(3):171–4.
8 Menaker J, Stein DM, Scalea TM. Incidence of early pulmonary embolism after injury. *J Trauma* 2007;63(3):620–4.
9 Steiner I. Pulmonary embolism – temporal changes. *Cardiovasc Pathol* 2007;16(4):248–51.
10 Fineschi V, *et al*. Histological age determination of venous thrombosis: a neglected forensic task in fatal pulmonary thrombo-embolism. *Forensic Sci Int* 2009;186(1–3):22–8.
11 Zenker FA. *Beiträge zur Anatomie und Physiologie der Lunge*. Dresden: Braunsdorf, 1861.
12 Bergman EB. Ein fall tödlicher fettembolie. *Klin Wochenschr* 1873;10:385–7.
13 Scriba J. Untersuchungen über die Fettembolie. *Langenbeck's Arch Surg* 1879;12(1):118–220.
14 Lehman EP, Moore RM. Fat embolism including experimental production without trauma. *Arch Surg* 1927;14:621–6.
15 Peltier LF. An appraisal of the problem of fat embolism. *Surg Gynecol Obstet* 1957;104(4):313–24.
16 Bergentz SE. Studies on the genesis of posttraumatic fat embolism. *Acta Chir Scand Suppl* 1961;Suppl 282:1–72.
17 Sevitt S. *Fat Embolism*. London: Butterworth, 1962.
18 Ellis HA, Watson AJ. Studies on the genesis of traumatic fat embolism in man. *Am J Pathol* 1968;53(2):245–51.
19 Edland J. Post-traumatic fat embolism. In: Wecht C (ed). *Legal Medicine Annual*. New York: Appleton Century Crofts, 1971.
20 Buchanan D, Mason JK. Occurrence of pulmonary fat and bone marrow embolism. *Am J Forensic Med Pathol* 1982;3(1):73–8.
21 Giannoudis PV, Tzioupis C, Pape HC. Fat embolism: the reaming controversy. *Injury* 2006;37 Suppl 4:S50–8.
22 Husebye EE, Lyberg T, Roise O. Bone marrow fat in the circulation: clinical entities and pathophysiological mechanisms. *Injury* 2006;37 Suppl 4:S8–18.
23 Mason JK. Pulmonary fat and bone marrow embolism as an indication of ante-mortem violence. *Med Sci Law* 1968; 8(3):200–6.
24 Nikolic S, *et al*. [Post-traumatic pulmonary and systemic fat embolism in forensic practice. Prospective histological study]. *Srp Arh Celok Lek* 2000;128(3–4):90–3.
25 Hain JR. Subcutaneous corn oil injections, fat embolization syndrome, and death. *Am J Forensic Med Pathol* 2009;30(4): 398–402.
26 Flach PM, *et al*. Massive systemic fat embolism detected by postmortem imaging and biopsy. *J Forensic Sci* 2012;57(5): 1376–80.
27 Lengemann P. *Ueber die Schicksale verlagerter und embolisierter Gewebsteile im tierischen Körper*. Rostock: Wiesbaden, Bergmann, 1897, p. 70.
28 Lubarsch O. Ueber knochenmarkgewebs-embolie. *Virchows Arch* 1898;151(3):546–9.
29 Maximow A. Zur lehre von der parenchymzellen-embolie der lungenarterie. *Virchows Arch* 1898;151(2):297–318.
30 Rappaport H, Raum M, Horrell JB. Bone marrow embolism. *Am J Pathol* 1951;27(3):407–33.
31 Fisher JH. *Bone marrow embolism*. *Am J Pathol* 1951;27(4):701–2.
32 Schmidt JH. Fatal bone marrow embolism following thoracotomy. *Am J Surg* 1958;95(1):94–101.

33 Yoell JH. Bone marrow embolism to lung following sternal puncture. *AMA Arch Pathol* 1959;67(4):373–4.
34 Winkel EC, Brown WG. Bone marrow embolism following closed chest cardiac massage. *JAMA* 1961;178:329–31.
35 Dzieciol J, *et al.* Widespread myocardial and pulmonary bone marrow embolism following cardiac massage. *Forensic Sci Int* 1992;56(2):195–9.
36 Tsokos M, *et al.* Histologic, immunohistochemical, and ultrastructural findings in human blast lung injury. *Am J Respir Crit Care Med* 2003;168(5):549–55.
37 Siegel H, Helpern M, Ehrenreich T. The diagnosis of death from intravenous narcotism. With emphasis on the pathologic aspects. *J Forensic Sci* 1966;11(1):1–16.
38 Hopkins GB, Taylor DG. Pulmonary talc granulomatosis. A complication of drug abuse. *Am Rev Respir Dis* 1970;101(1): 101–4.
39 Siegel H. Human pulmonary pathology associated with narcotic and other addictive drugs. *Hum Pathol* 1972;3(1):55–66.
40 Rajs J, Harm T, Ormstad K. Postmortem findings of pulmonary lesions of older datum in intravenous drug addicts. A forensic-pathologic study. *Virchows Arch A Pathol Anat Histopathol* 1984;402(4):405–14.
41 Janssen W, Trubner K, Puschel K. Death caused by drug addiction: a review of the experiences in Hamburg and the situation in the Federal Republic of Germany in comparison with the literature. *Forensic Sci Int* 1989;43(3):223–37.
42 Tomashefski Jr, JF, Felo JA. The pulmonary pathology of illicit drug and substance abuse. *Curr Diag Pathol* 2004;10(5):413–26.
43 Passarino G, *et al.* Histopathological findings in 851 autopsies of drug addicts, with toxicologic and virologic correlations. *Am J Forensic Med Pathol* 2005;26(2):106–16.
44 Dettmeyer RB, *et al.* Widespread pulmonary granulomatosis following long time intravenous drug abuse. A case report. *Forensic Sci Int* 2010;197(1–3):e27–30.
45 DiMaio VJ, DiMaio DJ. Bullet embolism: six cases and a review of the literature. *J Forensic Sci* 1972;17(3):394–8.
46 Jones AM, Graham NJ, Looney JR. Arterial embolism of a high-velocity rifle bullet after a hunting accident. Case report and literature review. *Am J Forensic Med Pathol* 1983;4(3):259–64.
47 Adelson L. Bullet embolism with radiologic documentation. A case report. *Am J Forensic Med Pathol* 1984;5(3):253–6.
48 Guileyardo JM, *et al.* Renal artery bullet embolism. *Am J Forensic Med Pathol* 1992;13(4):288–9.
49 Pollak S, Ropohl D, Bohnert M. Pellet embolization to the right atrium following double shotgun injury. *Forensic Sci Int* 1999;99(1):61–9.
50 Lucena JS, Romero C. Retrograde transthoracic venous bullet embolism. Report of a case following a single gunshot with multiple wounds in the left arm and chest. *Forensic Sci Int* 2002;125(2–3):269–72.
51 Slobodan S, Slobodan N, Djordje A. Popliteal artery bullet embolism in a case of homicide: a case report and review of the tangible literature. *Forensic Sci Int* 2004;139(1):27–33.
52 Ashbaugh DG, *et al.* Acute respiratory distress in adults. *Lancet* 1967;2(7511):319–23.
53 Ware LB, Matthay MA. The acute respiratory distress syndrome. *N Engl J Med* 2000;342(18):1334–49.
54 Bellomo R, Kellum JA, Ronco C. Acute kidney injury. *Lancet* 2012;380(9843): p. 756–66.
55 Langenberg C, *et al.* The histopathology of septic acute kidney injury: a systematic review. *Crit Care* 2008;12(2):R38.
56 Mole RH. Fibrinolysin and the fluidity of the blood post mortem. *J Pathol Bacteriol* 1948;60(3):413–27.
57 Moore RM, Braselton CW. Injections of air and of carbon dioxide into a pulmonary vein. *Ann Surg* 1940;112(2):212–8.
58 Polson CJ. *Essentials of Forensic Medicine*. Oxford: Pergamon Press, 1963.
59 Jackowski C, *et al.* Visualization and quantification of air embolism structure by processing postmortem MSCT data. *J Forensic Sci* 2004;49(6):1339–42.
60 Dedouit F, *et al.* Post-traumatic venous and systemic air embolism associated with spinal epidural emphysema: multi-slice computed tomography diagnosis. *Forensic Sci Int* 2006;158(2–3):190–4.
61 Gao GK, *et al.* Cerebral magnetic resonance imaging of compressed air divers in diving accidents. *Undersea Hyperb Med* 2009;36(1):33–41.
62 Persson A, Lindblom M, Jackowski C. A state-of-the-art pipeline for postmortem CT and MRI visualization: from data acquisition to interactive image interpretation at autopsy. *Acta Radiol* 2011;52(5):522–36.
63 Bajanowski T, West A, Brinkmann B. Proof of fatal air embolism. *Int J Legal Med* 1998;111(4):208–11.
64 Bajanowski T, *et al.* Proof of air embolism after exhumation. *Int J Legal Med* 1999;112(1):2–7.
65 Pierucci G, Gherson G. [Experimental study on gas embolism with special reference to the differentiation between embolic gas and putrefaction gas]. *Zacchia* 1968;4(3):347–73.
66 Pierucci G, Gherson G. [Further contribution to the chemical diagnosis of gas embolism. The demonstration of hydrogen as an expression of 'putrefactive component']. *Zacchia* 1969;5(4): 595–603.
67 Hellerich U, Pollak S. Airplane crash. Traumatologic findings in cases of extreme body disintegration. *Am J Forensic Med Pathol* 1995;16(4):320–4.
68 Keil W, Rothamel T, Troger HD. [Subendocardial hemorrhage from the forensic medicine viewpoint]. *Beitr Gerichtl Med* 1991;49:45–53.
69 Harruff RC. Subendocardial hemorrhages in forensic pathology autopsies. *Am J Forensic Med Pathol* 1993;14(4):284–8.
70 Plattner T, Yen K, Zollinger U. The value of subendocardial haemorrhages as an indicator of exsanguination and brain injury – a retrospective forensic autopsy study. *J Forensic Leg Med* 2008;15(5):325–8.

CHAPTER 14

Suffocation and 'Asphyxia'

- The nature of 'asphyxia'
- Mechanical 'asphyxia'
- The classic signs of 'asphyxia'
- Suffocation
- Smothering
- Choking
- Traumatic 'asphyxia'
- Postural asphyxia
- References

Though traditionally every textbook of forensic medicine has a chapter entitled 'Asphyxia', it is a partial misnomer, as many of the conditions described under this heading are not truly asphyxial in nature. It is difficult to find a succinct alternative, however, unless each subcondition is described individually – and some deaths have a mixed aetiology. The conventional title is therefore retained in this book, though it is emphasized that 'asphyxia' is both inappropriate and inaccurate when applied to many of the mechanisms of death formerly ascribed to this cause.

The nature of 'asphyxia'

Common usage has led to the term 'asphyxia' being equated with 'lack of oxygen', though etymologically the word means 'absence of pulsation'. Interestingly – if fortuitously – this original sense is sometimes more accurate in certain deaths associated with pressure on the neck, where cardiac arrest – certainly a prime reason for absence of pulsation – is the fatal mechanism, rather than hypoxia.

Reverting to the usual meaning of asphyxia, a whole series of disturbances can lead to lack of oxygen. The basic purpose of respiration is to convey atmospheric oxygen to the peripheral tissue cells. Anything that interferes with oxygen transfer can be called 'asphyxia', though other terms such as 'hypoxia' or 'anoxia' are more accurate, and should be preferred. The following conditions may legitimately be considered to be defects in the chain of respiration and hence are examples of asphyxia:

- Absence or reduction of oxygen tension in the external atmosphere, such as reduced barometric pressure or replacement of oxygen by an inert gas, such as nitrogen or carbon dioxide.
- Obstruction of the external respiratory orifices, as in smothering or gagging.
- Blockage of the internal respiratory passages, at either pharyngeal, laryngeal, tracheal or bronchial level.
- Restriction of the respiratory movements of the thorax, preventing the inspiration of air through patent respiratory passages, as in the so-called 'traumatic asphyxia' or in paralysis from brainstem or cord damage, or the use of curare-like drugs.
- Disease of the lungs that prevents or reduces gaseous interchange. Extensive pneumonia, pulmonary oedema, adult respiratory distress syndrome, diffuse fibrosis and many other conditions may lead to hypoxia, but these are rarely of forensic concern.
- Reduction in cardiac function leading to impairment of the circulation of oxygenated blood may be considered as a type of 'asphyxia', sometimes called 'stagnant anoxia'. Again, the condition is rarely relevant to forensic problems.
- A reduced ability of the blood to transport oxygen can also be thought to be asphyxial in nature, such as severe anaemias and the replacement of the oxygen-combining power of haemoglobin by carbon monoxide.
- Finally, an inability of the peripheral tissue cells to utilize the oxygen delivered to them by the bloodstream is seen in conditions such as cyanide poisoning, where the cytochrome-oxidase enzyme systems are inactivated.

Several schemes of classification of asphyxia have been devised, such as those of McIntyre and Shapiro.[1,2]

Mechanical 'asphyxia'

The usual relevance of asphyxia in a forensic context is in mechanical asphyxia, rather than some of the internal conditions mentioned above, which are more likely to arise as a result of natural disease or toxic conditions.

The normal oxygen content of blood (PO_2) at sea level varies according to the age and health of the subject. Young to middle-aged adults have almost complete saturation of their arterial blood with oxygen, at a level of 90–100 mmHg (12–13 kPa), while in persons over 60 it may drop to between 60 and 85 mmHg (8–11 kPa).[3] These normal values in the younger group may be contrasted with those sufferers from mild hypoxia of about 60 mmHg (8 kPa), and those in severe to fatal hypoxia when oxygen tension falls to between 40 and 20 mmHg (5–3 kPa).

Unfortunately for pathologists, post-mortem analysis of oxygen levels in the blood is of no value in the retrospective diagnosis of hypoxia, as changes soon after death rapidly distort the distribution of gases and make the results meaningless.

Definition of terms

A number of different names have been used to describe the various types of mechanical 'asphyxia', some of which are confusing or inexact:

- *Suffocation* is a general term used to indicate death from deprivation of oxygen, either from lack of the gas in the breathable environment or from obstruction of the external air passages.
- *Smothering* is more specific, in that it indicates blockage of the external air passages, usually by a hand or soft fabric. A variety of suffocation may be called *gagging* where fabric or adhesive tape occludes the mouth to prevent speaking or shouting. While the nasal passages remain patent, air can enter, but later blockage by mucus or oedema may lead to death.
- *Choking* refers to blockage of the upper airways by some foreign body, but is also used for manual strangulation.
- *Throttling* refers to strangulation, usually by hand, the word rarely being applied to ligature strangulation.
- *Strangulation* is the most specific term, indicating the use either of the hands or a ligature as a means of applying external pressure to the neck. *Garrotting* has been used for ligature strangulation, but more accurately refers only to a Spanish method of judicial execution. Other methods exist in various parts of the world, such as the Indian technique of pressing a flexible stick or 'lathi' across the front of the neck.
- *Mugging* originally meant the application of pressure to the neck by means of an arm crooked around from the rear, but more recent American usage has widened the term to mean any kind of robbery with violence. More recently still the *arm-lock* has been used as means of restraint by law enforcement officers, sometimes with fatal results.

As an aside, in some deaths during arrest, usually where a violent struggle occurs between several police officers and a drunken or drugged offender, the death of the latter occurs where no neck or chest pressure can be implicated. Though the mechanism is obscure and impossible to demonstrate objectively at autopsy, it has been provisionally ascribed to a catecholamine-induced cardiac arrhythmia from an exaggerated adrenal response.

As most of these victims are given energetic cardiopulmonary resuscitation, any markers of this catecholamine effect, such as contraction-band necrosis in the myocardium, cannot be differentiated from resuscitative artefacts.

The classic signs of 'asphyxia'

For many years the autopsy diagnosis of an asphyxial death was made by reference to a set of findings that have come to be known as the 'classic signs of asphyxia'. Unfortunately, it is now quite clear that most of these signs are so non-specific that little reliance can be placed on them in the absence of other confirmatory evidence. They are scathingly referred to by Lester Adelson as the 'obsolete diagnostic quintet'.[4]

In many cases of undoubted fatal hypoxia these signs are absent and, conversely, they are often present in some degree in conditions that can be shown to be non-hypoxic in origin. The major difficulty for the pathologist is that 'asphyxia' cannot reliably be equated with 'hypoxia'. There are no truly distinctive autopsy signs of pure hypoxia and most of the alleged criteria are caused by factors other than a lack of oxygen.

To confuse the issue further, some apparently hypoxic states lead to sudden or rapid death before there is time for oxygen lack to take effect, such as often happens when a victim enters a space devoid of oxygen, has the trachea suddenly blocked by food or has a plastic bag pulled over the head.

Each of the 'classic features' must be looked at in depth.

Petechial haemorrhages

These are small pin-point collections of blood lying in the skin, the sclera or conjunctivae and under thoracic serous membranes such as the pleura or pericardium. They vary in size from one-tenth of a millimetre to about 2 mm. If larger than this, they are more accurately called 'ecchymoses' (Figs 14.1, 14.2).

Petechiae are often known as 'Tardieu's spots', but this eponym should be restricted to those lying in the visceral pleura, where they were described by the Parisian Professor Ambroise Tardieu in 1860, in the bodies of infants who he claimed had been 'overlain'.[5] A further common error is to attribute the petechiae to the rupture of *capillaries*, whereas they actually emanate from small venules – capillary bleeding would be invisible to the naked eye.

Petechiae are caused by an acute rise in venous pressure that in turn causes overdistension and rupture of thin-walled peripheral venules, especially in lax tissues, such as the eyelid, and in unsupported serous membranes, such as the pleura and epicardium. It is traditionally claimed that hypoxia of the vein wall is an added factor, but there is no experimental proof of this conjecture, which seems unlikely considering the rapid formation of these lesions when venous pressures rise; for example, petechiae can appear almost instantly after violent sneezing or coughing before any hypoxia is possible.

Petechiae are seen most often in the face and eyes of victims of compression of the neck or fixation of the chest. In the former, where strangulation by either hand or ligature has occurred, occlusion of the jugular veins prevents venous drainage from the head, while almost always allowing the arterial supply to continue via the more deeply placed and much less compressible carotid and vertebral arteries. There is a rapid rise in venous pressure in the head, leading to engorgement of the veins. The consequences are swelling of the tissues, both from an increase in intravascular volume and from rapid transudation of fluid into the tissues, followed by showers of petechial haemorrhages in unsupported areas, such as the skin of the upper eyelids, the forehead, the skin behind the ears, the circumoral skin, and the conjunctivae and sclera of the eye. The same venous engorgement often leads to frank bleeding from the nasal mucosa and the external auditory meatus.



Figure 14.1 Petechial haemorrhages in the eye in manual strangulation. There are also some petechiae on the facial skin.



Figure 14.2 Scleral haemorrhages in manual strangulation. These are larger than the usual petechiae, but the latter are present inside the lower lid.

In the internal tissues and organs, petechiae are most often seen on serous membranes in the thorax, where the presence of a body cavity leads to lack of support for the superficial venules and hence predisposes to rupture when venous pressure rises. They are almost never seen in the peritoneal serosa and it has been postulated that, in the chest, attempts at breathing against a closed airway may lead to a sudden extreme decrease in intrapleural pressure causing petechiae in the same way as suction on the skin can cause a shower of pin-point haemorrhages. As described by Tardieu, petechiae in the thorax are often seen on the visceral pleura, especially in the interlobar fissures and around the hilum (Fig. 14.3).

Petechiae are also common on the surface of the heart, especially on the epicardium around the atrioventricular groove, particularly on the posterior surface, though these have been shown to appear or worsen as a post-mortem phenomenon. In infants and children, the thymus or thymic remnants may show numerous petechiae. It is claimed that in the sudden infant death syndrome these are confined to the



Figure 14.3 Subpleural petechial haemorrhage – the true 'Tardieu spots' – in manual strangulation. These are no longer considered to be specific for 'asphyxia' and a few petechiae can frequently be found in many autopsies unassociated with asphyxia.

cortex, whereas in other 'asphyxial' conditions they are scattered throughout the gland; this is doubtful.

Petechiae are rarely seen in the parietal pleura or the peritoneum except in haemorrhagic diatheses. In the brain, petechiae occur in the white matter and there may be larger patches of bleeding in the subarachnoid space where superficial vessels have ruptured because of acute venous engorgement. The same mechanism often produces profuse petechiae and ecchymoses under the scalp. With regard to the scalp, caution must be observed as numerous haemorrhages can be caused as a common autopsy artefact during the reflection of the scalp flaps.

Petechiae may also disappear with lengthening post-mortem interval. Betz *et al.* have shown that in putrefaction and freshwater immersion, conjunctival petechiae may vanish.[6]

The significance of petechiae

A number of factors cause difficulty in the interpretation of petechial haemorrhages. First, there is no doubt that both cutaneous and visceral petechiae, especially the latter, can both appear and enlarge as a post-mortem phenomenon. Gordon and Mansfield have shown that the presence and number of petechiae is a function of the post-mortem interval, in common with other haemorrhagic artefacts such as those found behind the larynx by Prinsloo and Gordon.[7,8]

Posture also has an effect on the appearance of haemorrhages. They are commonly seen, along with larger ecchymoses, on the front or back of corpses who have died from a variety of causes in which mechanical asphyxia is absent. They are often present in normal post-mortem hypostasis, especially where the mode of death was congestive as in many types of natural heart disease. Their appearance in the hypostatic areas is also time-related, the longer the post-mortem interval, the more likely – and more prominently – they are to occur.

Where some abnormal posture is present – such as the deceased being slumped out of bed or otherwise found with the head lower than the body – marked congestion, cyanosis and petechial haemorrhages are common (Fig. 14.4).

Occasionally the abnormal posture may have occurred during life, such as in overdose victims, drunks and senile persons, who have fallen into a position with the upper part of the body lowermost. This may embarrass respiration and contribute to death and the ante-mortem component may be difficult or impossible to distinguish from post-mortem accentuation of the congestive-petechial appearances.

Another problem in the autopsy interpretation of petechiae is that not all punctate lesions in the pleura



Figure 14.4 Dense confluent skin haemorrhages in the face of an elderly female who had slipped from her bed and was found with her head on the floor and her legs on the bed. The signs of this 'postural asphyxia' may well have been accentuated by post-mortem worsening of the hypostatic haemorrhages.

are petechiae. Zaini and Knight showed that many such apparent petechiae were either intravascular venous pools, subpleural microbullae or pigment foci.[9]

Lasczkowski *et al.* and Wyss and Lasczkowski used confocal laser scanning microscopy (CLSM) and immunohistochemistry to investigate the pathogenesis, vitality and age of conjunctival petechiae. They observed conjunctival petechiae to be a rhexis haemorrhage. They studied the expression of the endothelial adhesion molecule P-selectin in a collection of samples from medico-legal cases (positive petechiae: n = 65; post-mortem artefacts: n = 12; control: n = 19) to differentiate intravital petechiae from post-mortem artefacts and to establish the age of the vessel damage. Except for cases with massive congestion, where the victim had survived for around minutes, CLSM examination revealed a strong endothelial reaction at the rupture site. They were not able to see a strong P-selectin expression in either those vessels, which had not suffered any mechanical insult, nor in those that had ruptured post-mortem. They suggested that the elevated expression of P-selectin could be used as a criterion to distinguish between intravital petechiae from post-mortem artefacts.[10,11]

In summary, petechial haemorrhages are highly unreliable indicators of an asphyxial process, taking this to mean a hypoxic state. They are the result of venous engorgement, usually from mechanical obstruction of venous return to the heart – or in the thorax, from attempts to inspire against a blocked airway. Petechiae and ecchymoses are common non-specific autopsy findings and many are post-mortem in origin, especially in dependent positions. They may occur in many non-asphyxial states and, in the lungs, some petechiae can be found in the interlobar fissures and around the hilum in most routine autopsies.

Conversely, in some types of death where oxygen deprivation is to be expected (such as drowning, plastic-bag suffocation and entering an atmosphere devoid of oxygen), petechiae are seldom demonstrable.

The most significance must be placed on facial and ocular petechiae, because showers of pin-point haemorrhages in the eyelids, conjunctivae, sclera and facial skin require urgent explanation unless the body was face down or head down.

Congestion and oedema

The next 'classic' sign of asphyxia is congestion. This is even more non-specific than petechiae and once again is the result of obstructed venous return. When the neck is compressed, the face, lips and tongue become swollen and reddened. The true colour change of congestion is usually darkened by the onset of cyanosis. Internal organs also become congested and in strangulation this is most notable in the tongue, pharynx and larynx above the level of venous obstruction. In pressure on the chest, failure of respiratory movements cause an intense rise in venous pressure, accompanied by cyanosis.

Congestion is often associated with tissue swelling if the venous obstruction continues. The oedema is the result of rapid transudation through capillary and venule walls, again mainly a function of back pressure in the venous system. Hypoxia of the vascular endothelium is alleged to allow increased permeability, but generalized hypoxia from other causes does not produce the tissue swelling seen in strangulation.

Tissue fluid also escapes rapidly into the brain in strangulation that continues for even a few minutes, though here the well-known effect of hypoxia might be an added factor. Pulmonary oedema, causing excess fluid to enter the alveoli, is often found in hypoxic deaths. Here the mechanism is more obscure, but is probably a combination of hypoxia and raised pulmonary vessel pressure. In strangulation, froth may sometimes be so profuse as to emerge from the mouth and nostrils – yet in other throttlings, it may be absent. Pulmonary oedema is such a common and non-specific phenomenon in a whole range of fatal conditions that it has little diagnostic significance.

Cyanosis

The colour of blood depends upon the absolute quantity of oxyhaemoglobin and reduced haemoglobin present in the erythrocytes. The normal pink colour of well-oxygenated skin may change to purple or blue when oxygen is lacking – indeed, the word 'cyanosis' is derived from the Greek, meaning 'dark blue'. Cutaneous cyanosis, however, depends on the absolute amount of reduced haemoglobin, rather than the proportion of reduced haemoglobin to oxyhaemoglobin. It is not apparent in marked anaemia, even if the ratio of oxyhaemoglobin to reduced haemoglobin is low. There must be at least 5 g of reduced haemoglobin per 100 ml blood before cyanosis becomes evident, irrespective of the total amount of haemoglobin.[12]

In the common forensic event of constriction of the neck, cyanosis almost invariably follows congestion of the face, as venous blood containing much reduced haemoglobin after perfusing the head and neck is dammed back and becomes more blue as the blood accumulates. If and when the airway becomes blocked, then impaired oxygenation in the lungs leads to a diminution in the oxygen content of arterial blood. This will lead to a darkening of all organs and tissues, and will accentuate the cyanosis of the face. This does not happen in the first phases of strangulation, however, and depends on complete or substantial occlusion of the airway, or restriction of the respiratory excursions of the chest.

Cyanosis produced during life may be partly or wholly overshadowed by hypostasis, which may be a deep purple or blue, and may be mistaken for true cyanosis – indeed, some pathologists refuse to use 'cyanosis' in respect of the dead, claiming that it cannot reflect the ante-mortem situation.

'Engorgement of the right heart and fluidity of the blood'

Descriptions of an abnormal fluidity of the blood seen at autopsy in asphyxial deaths are part of forensic mythology and can be dismissed with little discussion. Post-mortem clotting in the heart and venous system is a most erratic process, as is the eventual dissolution of those clots by the action of fibrinolytic enzymes.[13,14] It is irrelevant in the diagnosis of asphyxia.

Engorgement of the chambers of the right side of heart and the great veins is also a non-specific autopsy observation, useless as a marker of an asphyxial process. Any type of congestive death, including primary heart failure from many diseases, leads to terminal engorgement of the right ventricle and atrium as part of the generalized rise in venous and intracardiac pressure.

The autopsy diagnosis of 'asphyxia'

Thus there are no specific autopsy findings for 'asphyxia', taking this in its hypoxic sense. As stated earlier, the so-called 'classic signs' have been well described by Adelson as the 'obsolete diagnostic quintet'. He goes on to observe that 'the coexistence of these findings, in themselves, does not prove that death resulted from mechanical asphyxia. All these phenomena are non-specific and are in no way peculiar to this mode of death. Inasmuch as they are observed frequently in deaths arising from unquestioned natural disease, they are of no value in proving that death resulted from mechanical asphyxia'.

Other salutary cautions on the significance of 'asphyxial signs' may be found in the important publications of Gordon and Turner, Camps and Hunt, Shapiro, Swann and Brucer and Ely and Hirsch.[15–19]

It is impossible to make a post-mortem diagnosis of acute hypoxia by measuring the blood gases, as rapid changes after death – and indeed agonal changes – make analysis worthless. Only by a careful assessment of the history and circumstances of the death, exclusion of other causes and a cautious evaluation of the signs described above can any conclusion be reached. Most important of all is the finding of a cause for airway obstruction or other local trauma, such as prolonged pressure on the neck or chest, obstruction of the airways, postural causes or occlusion of the external respiratory orifices.

It cannot be emphasized too strongly that the mere finding of any of the non-specific features, such as congestion and petechiae, without firm circumstantial or preferably physical evidence of mechanical obstruction of respiration, is quite insufficient to warrant a speculative diagnosis of asphyxia. If such collateral evidence is not forthcoming, then the cause of death must be left undetermined.

Histological and biomechanical diagnosis of anoxia/'asphyxia'

Many attempts have been made to find markers of hypoxia, anoxia and 'asphyxia' by means of laboratory techniques, including histology, histochemistry and various biochemical methods. Although many claims have been made for their usefulness, the fact that such tests are virtually never put forward in criminal or civil litigation makes it self-evident that they are not reliable.

This is hardly surprising, given the vague and contentious nature of the 'asphyxial' condition, where the mechanisms are diverse and even the nomenclature is unstandardized. If the target for research is narrowed down to severe hypoxia at a tissue or cellular level, then perhaps more success might be expected, by being able to demonstrate cellular damage by one or more of the great battery of techniques now available. However, even this limited objective is not yet attained with the degree of reliability required for legal purposes. The extensive strangling, drowning and gassing of legions of small animals may have produced many theses and papers, but has had no practical impact upon a long-standing problem in forensic pathology. Cell death, especially in neurons or myocytes, due to ischaemic/hypoxic damage is the most common focus for research, but the problem in a forensic context is that a considerable period of hypoxia – usually a minimum of many minutes or even hours – is needed before changes can be detected, even in experimental circumstances. In human autopsy material, the ever-present post-mortem and agonal changes interfere with the subtle early signs of hypoxic damage.

Histological changes in the lung and also chemical markers in blood or vitreous, such as hypoxanthine, have been claimed to indicate generalized hypoxia, but the application of such techniques in routine practice has not been fruitful.[20–27]

Suffocation

Although not a specific term, suffocation usually refers to a death caused by reduction of the oxygen concentration in the respired atmosphere, formerly called a 'vitiated atmosphere'. It is less often used to include smothering or choking. Reduction of atmospheric oxygen may occur in a wide variety of situations. Decompression, such as cabin failure of aircraft at high altitudes, causes a dramatic fall in the partial pressure of oxygen and hence reduced penetration of the gas through the alveolar wall. Other factors, however, such as the direct effects of a partial vacuum and often mechanical trauma from the near-explosive situation may overshadow the hypoxic aspects.

More common is the reduction of oxygen in the atmosphere by physical replacement by other gases, or chemical changes such as combustion. In fires, the loss of respirable air may be a potent factor in causing death, though other complications, such as the presence of toxic gases such as carbon monoxide, cyanide and many other poisonous substances liberated by the burning of plastics, may cause death more quickly than pure hypoxia. Carbon dioxide, which though not itself poisonous, is irrespirable and may accumulate in fires, and in wells and shafts in limestone. In former years, vagrants sleeping for warmth near limekilns were sometimes suffocated by this heavy gas creeping over them.

Carbon dioxide is also the cause of deaths in a more modern agricultural setting – the grain silo. Here, many tons of grain are stored in gas-tight towers; the seed produces carbon dioxide that settles to the bottom of the tower. When a blockage occurs in the gravity discharge, farm workers may enter the tower to clear the obstruction. Although safety precautions demand venting before the men enter, some workers still suffer a sudden death on encountering an atmosphere rich in carbon dioxide.[28–30]

A similar hazard exists in ships' tanks or other industrial metal chambers, in which oxygen is replaced by nitrogen. This happens because the damp steel walls become rusty and use up much of the contained oxygen in forming ferric oxides. In all these deaths associated with replacement of oxygen with an inert gas, rapid death is common before hypoxia can have had any physiological effect. For example, the author (BK) has dealt with two deaths in which seafarers entered closed ships' tanks and virtually fell dead off the entry ladder. The presumed mechanism, which was far too quick to be hypoxic, was considered to be some overstimulation of the chemoreceptor system, leading to a parasympathetic 'vasovagal' cardiac arrest.

Even where death was not witnessed as sudden, the 'classic signs' of asphyxia are almost always absent. In domestic circumstances, death may be seen where a heating apparatus has removed oxygen from the atmosphere in the absence of ventilation. Though oxides of carbon are usually formed, a kerosene or natural gas appliance may kill from pure hypoxia, especially where left burning all night in a small room where the occupants lie sleeping. The effect may be accentuated by the victims having blocked up cracks in the doors and windows to keep out draughts. An open wood or coal fire does not present the same hazard, as it requires a flue or chimney in order to burn. In all such deaths, carbon monoxide poisoning must first be excluded by blood analysis, as it is a common accompaniment to lack of oxygen, especially as the reduction in oxygen availability tends to make the heat source produce progressively more monoxide than dioxide during combustion.

In a different variety of hypoxic death, persons – especially children – may asphyxiate by being confined in a small airtight space. Examples include boxes and discarded refrigerators; the danger of the latter is so well known that in Britain it is illegal to dump a refrigerator in a place with public access, unless the self-locking handle is rendered inoperative.

In all such 'hypoxic' deaths (though some are patently due to vasovagal cardio-inhibitory mechanisms) it is very rare to find any petechial haemorrhages, as these are mainly the result of venous obstruction, which is absent in these circumstances. In the true hypoxic deaths, there may be congestion and cyanosis, though even these are often absent and the autopsy findings are essentially negative.

Smothering

This term refers to death from mechanical occlusion of the mouth and nose, though sometimes 'suffocation' is used to include this class of death. The smothering agent is usually fabric, an impervious sheet or a hand, though occasionally (especially in industrial accidents) a mobile solid, such as sand, mud, grain or flour may be responsible for blocking the air passages. In the 1966 Aberfan disaster in South Wales, more than 140 victims – almost all children – were smothered when semi-liquid coal slurry from a collapsing mine tip swept over their school.[31]

In smothering, death may occur either by the occluding substance pressing down upon the facial orifices, or by the passive weight of the head pressing the nose and mouth into the occlusion. Deliberate homicide is seen usually in the old, the debilitated and in infants. It is extremely difficult to prove homicide from objective findings.[32–37]

In relation to infants, the matter will be further discussed in the chapter on sudden infant death syndrome (SIDS), but it is essential to appreciate that the smothering of babies, whether intentional or accidental, is both rare and difficult to prove. The so-called 'classic signs' of asphyxia, for what they are worth, are rarely present in proven suffocation – and as intrathoracic petechiae are common in undoubted 'cot deaths', these signs cannot therefore be accepted in isolation as evidence of suffocation.

Pressure marks on the face can rarely be distinguished from post-mortem postural changes, where circumoral and circumnasal pallor is caused merely by passive pressure of the dependent head after death, preventing the gravitational hypostasis from entering these areas.

Even where the head is found supine, variation in colour is still common on the face, with contrasting white and pink patches, which usually change as the post-mortem interval lengthens. Unless there are bruises or abrasion on the cheeks, around the mouth, lips or lesions within the lips or mouth, it is dangerous to overinterpret mere colour variations from alterations in the amount of blood in the facial capillary bed, which is almost always a post-mortem phenomenon.

Even a confession from a parent/carer is not always reliable – cases are on record where a mother has falsely confessed to smothering her child to rationalize the inexplicable events of a true SIDS fatality.

A similar situation exists with the elderly, who may be victims of a 'mercy killing', often a euphemism for the exhaustion of patience of long-suffering caring relatives. A pillow placed over the face of a sleeping octogenarian leaves no signs, *unless a struggle develops*, when protracted attempts at respiration against obstruction may lead to congestion, cyanosis and sometimes facial and conjunctival petechiae (Fig. 14.5).



Figure 14.5 Smothering from a towel being tied over the face. Death was contributed to by head injuries, also inflicted by the aged husband, who died within a few hours of natural causes from hypertensive heart disease.

'Overlaying' of infants

This alleged condition has an ancient pedigree, being mentioned in the Old Testament. In Chapter III of the First Book of Kings, Solomon has to adjudicate between two women who both claim the same child, as the other infant was 'overlain'. This event, some 3000 years ago, has been mentioned at intervals through history, as in Wales in AD 1188, when Giraldus Cambrensis records that the Lord punished a woman for preventing her husband joining the Third Crusade, by causing her infant son 'to be overlain in the night'.

When an infant was found dead in the morning in the maternal bed (as separate cots or cribs are a relatively modern invention), it was assumed that the mother had turned over onto the baby in her sleep and suffocated it. When infants began to be placed in cots, the deaths continued unabated and it seems obvious that most of these were victims of SIDS. Whether or not overlaying really exists is doubtful and seems incapable of proof, given that any infant found dead in bed with no physical signs at autopsy could, by definition, be a SIDS.

The recent marked decline in numbers of SIDS in Britain has coincided with a campaign to discourage parents from putting their infants to sleep face down – but, as yet, no definite cause-and-effect relationship has been proved, so any consequent strengthening of the 'overlaying' hypothesis cannot be substantiated.

Plastic bag suffocation

Although an increasingly common form of suicide in Britain, plastic bag suffocation may also be homicidal or accidental.[38–46] In all these types, the essential mechanism is that a hood of impervious substance, usually polythene or other plastic, is placed over the head down to neck level. The plastic is usually in the form of an open-ended bag, either transparent or a 'supermarket' shopping bag (Figs 14.6, 14.7).

Although many suicides tie the open end of the bag around their neck with cord or a tie, this is not necessary for a fatal result. Indeed, even flat sheets of polythene have killed infants when placed on the face. The mechanism is not understood, as it was formerly but erroneously thought to be the result of the clinging effect of static electricity.

Plastic bag suffocation can be rapid and leave no signs whatsoever. In the author's (BK) series of accidental, suicidal and three homicidal deaths from plastic bags, not one had any petechial haemorrhages or, indeed, any signs of 'asphyxia' at all, the faces being pale and uncongested. In another case, a person was convicted of murder by plastic bag, yet was only arrested after a spontaneous confession 6 weeks after an autopsy that had revealed no signs whatsoever of an asphyxial cause of death. As with hypoxic atmospheres, it seems that the mechanism of death in plastic-bag facial occlusion is some rapid cardio-inhibitory mode, rather than a purely hypoxic process. This conclusion is strengthened by the causes mentioned above, where flat sheets of plastic, not bags, have killed infants by clinging to the face, which of necessity must have been rapid deaths.



Figure 14.6 Plastic bag suicide. The bag is sometimes tied around the neck, as in this case, but this is not necessary for a fatal outcome. The deaths are not asphyxial in the hypoxic sense; facial congestion and petechiae are almost always absent.



Figure 14.7 Plastic bag suicide, with an open bag placed loosely over the head. As usual there are no congestive petechial signs in the face.

At autopsy, unless the bag is still present, these cases can present great difficulty. In fact, as in the homicide mentioned above, unless a confession or other corroborative evidence is forthcoming, the pathologist may never even know that he has dealt with an occult suffocation. Where the bag is still in place, a search must be made for other indications of suicide, such as drug analysis and futile injuries, such as slashed wrists. Masochistic activities, described later in this chapter, are sometimes, though not often, associated with plastic bag suffocation.

It is sometimes said that moisture seen inside the bag indicates that it was put on during life, the water being from respiration. It is rare for this to be an important issue, as placing a bag on a corpse's head would seem excessively unusual; in any event, the test is invalid, as evaporation from the skin, nose and mouth can produce beads of moisture inside, whether the victim is dead or alive.

Autopsy signs of suffocation

Where smothering is suspected, local signs must be sought to try to substantiate pressure on the face. Such signs include bruising around the mouth, chin and nose, though these are rarely seen except in the more violent incidents. Pressure of the lips on the teeth or dentures may cause the buccal surfaces to be bruised or abraded, though lacerations are rare unless a blow has been administered. It must be remembered that as small infants and many old people have no teeth, these injuries are less likely. The dangers of accepting areas of facial pallor as 'pressure marks' when the face shows post-mortem hypostasis has already been mentioned. In the early stages of post-mortem discolouration of the skin, variable colouring may not be truly 'hypostatic' as mottling and patchy variation is common due to uneven vasodilatation after death. It takes some time for gravity to pull cutaneous blood down to lower levels.

Smothering may occur accidentally where a person who is incapacitated from one of a variety of causes lies face down on a surface that is impervious to air. Drunkenness, epilepsy, drug overdose, coma or stupor from natural disease, may lead to this. Though it has long been proved in connection with 'cot death' that woven fabrics of most types can still admit enough air to support quiet respiration when placed over the mouth and nose, fabric that becomes saturated with saliva, nasal mucus or vomit may form an impervious seal that ceases to allow the passage of air. The weight of the inert head also distorts the nose and presses the nostrils and mouth so hard against a mattress or pillow that this adds to the airway stenosis.

In these instances, congestion and cyanosis are common, but when the body is examined after death, some of these findings may be postural and hypostatic in nature. As always, however, it must be recognized that skin haemorrhages often appear post-mortem in dependent hypostasis.

Gagging

Smothering may also occur where a pad or gag is fixed over the face, as sometimes happens in robbery with violence. A householder, caretaker or night-watchman may be tied up and silenced by having a scarf, tie or other fabric tied around his face. At first this admits air, but when it becomes progressively soaked with saliva or mucus it may become impervious and lead to an asphyxial death, again usually without any petechiae in the face or eyes.

A similar situation arises when a gag is thrust into the mouth to silence a watchman or security officer. Another variant is adhesive tape applied over the mouth. Though the nasal airway may originally be quite patent, any later obstruction from oedema and mucus, or movement of the gag backwards into the nasopharynx, may cause an unforeseen death and turn a robbery charge into a homicide.

In addition to above mentioned circumstances, gagging is occasionally seen in combined suicides or other self-inflicted situations such as autoerotic deaths.[47–49]

Choking

This term refers to blockage of the internal airways, usually between the pharynx and the bifurcation of the trachea. Death can be the result of pure hypoxia from occlusion of the airway, when all the attendant signs of congestion, cyanosis and perhaps petechiae may be present, usually where the victim struggles to breathe for an appreciable period. As described below, however, a large proportion of deaths occur suddenly before any possible hypoxic manifestations have time to take effect; these fatalities must be caused by neurogenic cardiac arrest, either purely neurogenic or accelerated by excess catecholamine release from the adrenaline response.

Causes of choking include the following.

- Foreign bodies: objects such as gags, dummies, small toys, table-tennis balls and a multiplicity of objects may be placed in the mouth and inhaled, usually by children and the mentally retarded.[50,51] Occasionally adults will do the same, accidentally or by design; an example of the latter was a suicide seen by the author (BK), who died (without any asphyxial signs whatsoever) by pushing a closed pill-bottle into his pharynx.
- Dentures and haemorrhage: false teeth (especially partial plates), extracted large teeth, blood clots, and frank haemorrhage following dental or ear, nose and throat operations such as tonsillectomy.
- Acute obstructive lesions: lesions of the glottis or larynx, such as the oedema of acute hypersensitivity (including insect stings), irritant vapours, inhalation of hot gas and acute infective conditions. The most dangerous of the latter is diphtheria or *Haemophilus influenzae* epiglottitis in children, which is a medical emergency sometimes requiring an immediate tracheostomy to relieve the airway obstruction.[52] At autopsy, great thickening of the epiglottis and aryepiglottic folds by jelly-like oedema and inflammatory tissue will be found occluding the entrance to the larynx.
- Food material: this is an important topic, as the cause of death 'aspiration of vomit' is used too often without real justification. Food may be drawn into the larynx either as it is being taken down from the mouth in the act of swallowing, or it may be regurgitated from the stomach.

  The first instance is rarely misinterpreted, as whole undigested food may be found in the air passages and there is usually a history of death taking place while eating. Though most commonly encountered in old persons and the mentally disturbed, it can occur in any age group.[53–56] A notable example was the so-called 'café coronary' syndrome, which received considerable publicity in the USA some years ago. The most frequent victims were well-nourished businessmen, who died suddenly and unexpectedly during a meal with no signs of respiratory distress or any of the 'classic signs of asphyxia'. Initially thought to be coronary heart disease, autopsy revealed a bolus of food, often steak, lodged in the pharynx or larynx. In any choking on food, the bolus can be quite large, such as a whole pancake, a whole tangerine or masses of meat, fruit or vegetable. Senile persons in retirement homes and mentally retarded children in institutions are also vulnerable. In such fatalities, the history and mode of death gives no hint of a hypoxic mechanism. Many cases have been observed where the victim merely sits back in their chair, dead – the mode clearly being cardiac arrest, presumably from overactivity of the parasympathetic nervous system from stimulation of the laryngeal or pharyngeal mucosa – the so-called 'vasovagal reflex' or 'reflex cardiac inhibition' (Figs 14.8–14.10).



Figure 14.8 Impaction of an extracted molar tooth in the larynx. Though now uncommon with modern dental and anaesthetic practices, it can still happen in less satisfactory circumstances. Blood clot from dental extraction, tonsillectomy, and other ear, nose and throat surgery can also block the airway.

The finding of gastric contents in the air passages is by no means as significant as the presence of freshly swallowed food. First, difficulties can arise in distinguishing gastric contents from fresh food material if digestion of the former has not proceeded far – which is not always a function of the time since the last meal, as any physical or psychological disturbance can retard or completely halt digestion. The history, if available, is a better guide, unless the material is obviously partly or wholly digested. In cases of doubt, the smell and acid reaction to pH indicators may be useful.



Figure 14.9 Blockage of the larynx by a complete small orange in a mentally disturbed patient. The fruit had just been swallowed and was not regurgitated from the stomach. The face was pale and death was rapid, unaccompanied by symptoms of choking.



Figure 14.10 Blockage of the larynx by meat. The victim was an old person with senile dementia who gulped food and who eventually died suddenly without asphyxial signs from reflex cardiac arrest.

Gastric contents are commonly found in the larynx, trachea and bronchi at autopsy when no other evidence of aspiration exists, and when there is a clear and unconnected cause of death. Knight found that no less than one-quarter of a series of 100 consecutive autopsies on both adults and children contained some gastric contents in the air passages, and Pullar observed that this was a low figure compared with his series.[57,58] These findings were obviously caused in the great majority of cases by agonal or post-mortem spillage.

Gardner described experiments in which barium was placed in the stomachs of recently dead patients while still in bed in the hospital wards. When X-rays were taken after they were first moved to the mortuary and thence into the autopsy room, most had barium in their tracheobronchial tree, confirming that overspill was common as a post-mortem phenomenon. Even histological evidence of leucocyte clustering around foci of gastric contents deep in the bronchi was shown by Gardner to be an early post-mortem event, not a 'vital reaction'.[59] Leucocyte migration in the skin up to 16 hours post-mortem was demonstrated by Ali.[60]

Almost the only definite evidence of aspiration of gastric contents is either reliable witnessed observation during life or the histological finding of an advanced 'vital reaction' with infection, necrosis and a definite inflammatory reaction. This is a relatively late change and cannot be seen where death occurred within a few hours of aspiration. Finding a few foci of leucocytes around a bronchiole is of no evidential use. There is therefore no reliable method of distinguishing agonal or even early post-mortem overspill from true vital aspiration, unless clinical or other witnessed evidence is available. In most instances, it is not justifiable for a pathologist to claim that death was caused by inhalation of stomach contents without such confirmatory evidence. Unfortunately, where other lesions are absent or unconvincing at autopsy, especially in the SIDS, many pathologists use the presence of gastric contents in the air passages as the primary and often the only cause of death. This unwarranted assumption may have distressing consequences, both in the field of medical negligence, deaths in custody and especially in SIDS, where parents may be misled into thinking that some negligence on their part in failing to observe vomiting, may have caused the death.

The only circumstance where a firmer opinion may be held is in acute alcoholism, though even here certainty is usually elusive. Where an undoubtedly drunken person (usually with a blood alcohol of at least 150 mg/100 ml) is found dead with massive blockage of his air passages by copious gastric contents and where other causes of death can be excluded by autopsy, then it might be reasonable to assume that regurgitation may have killed him, especially if there is other evidence of external vomit on the clothing or immediate surroundings. However, it is not an autopsy diagnosis to be made lightly.

Traumatic 'asphyxia'

This condition is unfortunately misnamed, as the word 'traumatic' could equally be applied to hanging or strangulation. It is well recognized now, however, as meaning mechanical fixation of the chest, and is important both because of its frequency in accidents and because it provides the most extreme demonstration of the 'classic signs' of asphyxia (Figs 14.11–14.13).[61–66]

Whereas other types of mechanical asphyxia may cause obstruction of air entry into the lungs, 'traumatic asphyxia' acts by restricting respiratory movements and thus prevents inspiration. It was termed 'traumatic' because gross mechanical forces are usually the reason



Figure 14.11 Traumatic asphyxia showing gross congestion of confluent petechial haemorrhages of the face and parts of the shoulders. The victim had been buried up to the axillae in an avalanche of iron ore in a factory bunker.



Figure 14.13 Traumatic asphyxia showing gross congestion of the face and red blood-tinged froth exuding from the nostrils and mouth. The victim had lost the control of the tractor he was driving, fell out of the cab and was compressed under the overturned vehicle.



Figure 14.12 Gross conjunctival haemorrhages in traumatic asphyxia. The victim was a workman who was buried up to his chest in an avalanche of ash.

for the fixation of the thoracic cage. Traumatic asphyxia occurs in two main conditions:

- The chest and usually the abdomen are compressed by an unyielding substance or object, so that chest expansion and diaphragmatic lowering are prevented. Burial in earth following the collapse of an excavation is a common cause and may kill workmen even if their heads remain above the fallen soil. Similarly, burial in grain, sand, coal or minerals, may have the same effect, and is usually encountered in industrial, marine or agricultural accidents. An avalanche in a silo, hopper, or other large-scale storage container may bury the worker up to neck level and, unless rescue is rapid, asphyxia will prove fatal. Similar restriction of chest movement may be caused by the victim being pinned under an overturned vehicle, or by falling timber or masonry. Many fatalities have occurred on farms, especially in hill country, by the toppling of a tractor, pinning the driver underneath. Protection in the form of a 'roll-bar' over the driving position or the provision of a rigid cab on a tractor was specifically designed to avoid such accidents.
- Crushing in crowds also leads to traumatic asphyxia, and this has caused some mass disasters, the largest probably being in Mecca. Most of the football-ground tragedies such as Bolton, Ibrox Park (1971), Lima (1964), Hillsborough (1989) and the Heisl Stadium in Belgium (1986) have been the result of crushing in crowds out of control. A similar mechanism led to 173 deaths in wartime London, when a panic on the stairs of Bethnal Green underground station, used as an air-raid shelter, caused the crowd to fall on those beneath.[67]

Other forms of chest crushing arise from trapping between a vehicle and a wall, or between the buffers of two railway trucks. Individual cases of traumatic asphyxia can occur when one person allows the whole weight of his body to fall upon another for a protracted period. This may happen in sexual intercourse, especially when one or both parties are incapacitated by drink or drugs.

Features of traumatic asphyxia

The appearances just mentioned are the hallmark of traumatic asphyxia and in no other condition, apart from postural dependency, is the degree of congestion and cyanosis so marked. When the chest is fixed, the face, neck and shoulders down to the thoracic inlet are grossly discoloured. Sometimes this colour is more red than purple. It can extend lower than the clavicles, Polson *et al.* being of the opinion that it often reaches down to the level of the third rib.[68]

The conjunctivae are grossly congested and haemorrhagic. Rather than the petechiae seen in pressure on the neck, the conjunctivae and sclera may be so engorged with blood that the haemorrhagic tissue actually bulges out through the lids, completely obliterating the whites of the eyes. The face, lips and scalp may be swollen and congested, being dotted with petechiae and ecchymoses. There may be copious bleeding from the ears and nostrils. The whole picture is commonly an exaggeration of the appearances seen in slow death from manual strangulation, but local injury is absent and the signs extend down to or beyond the root of the neck. Where the compression has been caused by pinning under a solid object – as opposed to soil, sand or squeezing in a crowd – there may be local bruises and abrasions from the weight of a vehicle or heavy beam, but these are unrelated to the margin of the congestive–haemorrhagic zone.

Internally, the congestion is less marked than on the surface, but the lungs are usually dark and heavy and may well have subpleural petechial haemorrhages, the true 'Tardieu spots'. The right heart and all the veins above the atria are markedly distended. There may be injuries to the chest wall from the trauma of the fixating object.

It is not clear why there should be such gross venous congestion, but it is usually explained rather unconvincingly by the failure of the pulmonary circulation consequent upon the cessation of the normal expansion and collapse of the pulmonary vasculature. Shapiro suggested that the pressure on the chest forces blood back into the great veins and, as the venous valves in the subclavian vessels prevent displacement into the arms, the extra volume is forced up the valveless jugular system to congest the head and neck.

Postural asphyxia

Closely allied to traumatic asphyxia is the so-called 'postural asphyxia', whose description as a separate entity is quite recent. When a person remains in a certain position for an extended time, either due to being trapped, or being in a drunken or drugged state, there may be a mechanical impediment to adequate respiratory movements. In addition, the normal venous return to the heart may be impaired.

Such positions usually entail inversion, either of the whole body or of the upper half; the syndrome and the pathophysiology are described well by Madea, though most forensic pathologists will have had experience of such situations from time to time.[69]

Persons who have been trapped upside down or even only in a 'jack-knife' position, with the upper half of their body bent acutely downwards from the waist, may have such impairment of their respiratory movements that they become hypoxic and suffer marked disturbance of their circulatory system, especially the venous return to the heart (Fig. 14.14).

The author (BK) has seen two cases in which a victim has become stuck whilst trying to climb through the upper part of a window, one as a thief, the other in trying to get into a house without



Figure 14.14 Postural asphyxia in an inebriated man attempted to climb through a fanlight window. His feet slipped from the sill and he was unable to make sufficient respiratory movements against the weight of his body. Note the marked difference in congestion and cyanotic lividity between his two hands, the face and lower hand being discoloured at least partly from post-mortem hypostasis.

his key. Others have been seen where, in a state of drunkenness or other disability, they have slipped out of bed, so that their head and shoulders are on the floor, with the legs and pelvis still at a higher level on the bed. These may also suffer the same disturbance of respiratory movements, which when prolonged may lead to death.

Inversion may occur during torture: crucifixion has an element of postural asphyxia. In the case of inverted crucifixion, as in the death of St Peter, it would be the major factor, as inspiration would be impeded by the weight of abdominal viscera upon the diaphragm.

References

1 McIntyre J. The classification of asphyxia. *Br J Hosp Med* 1969;2:1113–15.
2 Shapiro H. Asphyxia. In: Gordon I, Shapiro H, Berson S (eds). *Forensic Medicine: A Guide to Principles*. Edinburgh: Churchill, 1988.
3 Severinghaus JW. Arterial blood gases. In: Geoffrey JL, Steven DS (eds). *Encyclopedia of Respiratory Medicine*. Oxford: Academic Press, 2006, pp. 144–50.
4 Adelson L. *The Pathology of Homicide*. Springfield Thomas, 1974.
5 Tardieu A. Etude medico-legale sur les services et mauvais traiments exerces sur les enfants. *Ann Hyg Pub Med Leg* 1860;13:361–98.
6 Betz P, Penning R, Keil W. The detection of petechial haemorrhages of the conjunctivae in dependency on the postmortem interval. *Forensic Sci Int* 1994;64(1):61–7.
7 Prinsloo I, Gordon I. Post-mortem dissection artefacts of the neck and their differentiation from ante-mortem bruises. *South African Med J* 1951;25:358–61.
8 Gordon I, Mansfield RA. Subpleural, subpericardial and subendocardial haemorrhages: a study of their incidence at autopsy and of the spontaneous development after death of subepicardial petechiae. *J Forensic Med* 1955;2:31–50.
9 Zaini MR, Knight B. Sub-pleural petechiae and pseudo petechiae. *J Forensic Sci Soc* 1982;22(2):141–5.
10 Lasczkowski G, *et al.* Pathogenesis of conjunctival petechiae. *Forensic Sci Int* 2005;147(1):25–9.
11 Wyss A, Lasczkowski G. Vitality and age of conjunctival petechiae: the expression of P-selectin. *Forensic Sci Int* 2008;178(1):30–3.
12 Lundsgaard C, Van Slyke D. Cyanosis. *Medicine Monographs*. Baltimore: Williams & Wilkins, 1923.
13 Mole RH. Fibrinolysin and the fluidity of the blood post mortem. *J Pathol Bacteriol* 1948;60(3):413–27.
14 Obersteg JI. Tod und Blutgerinnung. *Dtsch Z gerichtl Med* 1954;43(3):177–216.
15 Swann HG, Brucer M. The cardiorespiratory and biochemical events during rapid anoxic death; obstructive asphyxia. *Tex Rep Biol Med* 1949;7(4):593–603.
16 Gordon I, Turner R. Deaths from rapid anoxia. *AMA Arch Pathol* 1951;52(2):160–7.
17 Shapiro H. Is asphyxia a pathological entity recognisable at post-mortem? *J Forensic Med* 1953;1:65–8.
18 Camps FE, Hunt AC. Pressure on the neck. *J Forensic Med* 1959;6:116–35.
19 Ely SF, Hirsch CS. Asphyxial deaths and petechiae: a review. *J Forensic Sci* 2000;45(6):1274–7.
20 Brinkmann B, Fechner G, Puschel K. Identification of mechanical asphyxiation in cases of attempted masking of the homicide. *Forensic Sci Int* 1984;26(4):235–45.
21 Betz P, *et al.* Pulmonary giant cells and their significance for the diagnosis of asphyxiation. *Int J Legal Med* 1993;106(3):156–9.
22 Madea B, *et al.* Hypoxanthine in vitreous humor and cerebrospinal fluid – a marker of postmortem interval and prolonged (vital) hypoxia? Remarks also on hypoxanthine in SIDS. *Forensic Sci Int* 1994;65(1):19–31.
23 Grellner W, Madea B. Immunohistochemical characterization of alveolar macrophages and pulmonary giant cells in fatal asphyxia. *Forensic Sci Int* 1996;79(3):205–13.
24 Zhu BL, *et al.* Immunohistochemical investigation of a pulmonary surfactant in fatal mechanical asphyxia. *Int J Legal Med* 2000;113(5):268–71.
25 Grellner W, Madea B. Role of pulmonary macrophages and giant cells in fatal asphyxia – comment on 'Is the appearance of macrophages in pulmonary tissue related to time of asphyxia?'. *Forensic Sci Int* 2002;127(3):243–4; author reply 245.
26 Krous HF, *et al.* Pulmonary intra-alveolar hemorrhage in SIDS and suffocation. *J Forensic Leg Med* 2007;14(8):461–70.
27 Byard RW, *et al.* Could intra-alveolar hemosiderin deposition in adults be used as a marker for previous asphyxial episodes in cases of autoerotic death? *J Forensic Sci* 2011;56(3):627–9.
28 Troisi FM. Delayed death caused by gassing in a silo containing green forage. *Br J Ind Med* 1957;14(1):56–8.
29 Jackson L. Grain silo cleanup operation leads to two occupational deaths. *Appl Occup Environ Hyg* 2002;17(7):464–6.
30 Gill JR, Ely SF, Hua Z. Environmental gas displacement: three accidental deaths in the workplace. *Am J Forensic Med Pathol* 2002;23(1):26–30.
31 Howe G. The Aberfan disaster. *Med Leg J* 1968;36(3):107–21.
32 Luke JL. Recovery of intact respiratory epithelium from a cloth pillowcase four days following its utilization as a smothering instrument. *J Forensic Sci* 1969;14(3):398–401.
33 Hicks LJ, *et al.* Death by smothering and its investigation. *Am J Forensic Med Pathol* 1990;11(4):291–3.
34 Banaschak S, Schmidt P, Madea B. Smothering of children older than 1 year of age – diagnostic significance of morphological findings. Forensic Sci Int 2003;134(2–3):163–8.
35 Turillazzi E, *et al.* An unusual mechanical asphyxia in a homicide-suicide case by smothering and strangulation. *Am J Forensic Med Pathol* 2006;27(2):166–8.
36 Schmeling A, *et al.* Unassisted smothering in a pillow. *Int J Legal Med* 2009;123(6):517–9.
37 Schyma C, Madea B. Comments on unassisted smothering in a pillow. *Int J Legal Med* 2011;125(1):155–6.
38 Skold G. Fatal suffocation in plastic bag. *Dtsch Z Gesamte Gerichtl Med* 1967;59(1):42–6.
39 Polson CJ, Gee DJ. Plastic bag suffocation. *Z Rechtsmed* 1972;70(3):184–90.
40 Perez Martinez AL, Chui P, Cameron JM. Plastic bag suffocation. *Med Sci Law* 1993;33(1):71–5.
41 Perdekamp MG, *et al.* [Plastic bag as the method in suicide and homicide]. *Arch Kriminol* 2001;207(1–2):33–41.
42 Ogden RD, Wooten RH. Asphyxial suicide with helium and a plastic bag. *Am J Forensic Med Pathol* 2002;23(3):234–7.
43 Auwaerter V, *et al.* Toxicological analysis after asphyxial suicide with helium and a plastic bag. *Forensic Sci Int* 2007;170(2–3):139–41.

44 Schon CA, Ketterer T. Asphyxial suicide by inhalation of helium inside a plastic bag. *Am J Forensic Med Pathol* 2007;28(4):364–7.
45 Saint-Martin P, *et al*. Plastic bag asphyxia – a case report. *J Forensic Leg Med* 2009;16(1):40–3.
46 d'Aloja E, *et al*. A case of suicidal suffocation simulating homicide. *J Forensic Sci* 2011;56(3):810–2.
47 Pollak S, Vycudilik V. [Gagging in the frame of combined suicides]. *Beitr Gerichtl Med* 1981;39:129–36.
48 Marsh TO, Burkhardt RP, Swinehart JW. Self-inflicted hanging with bound wrists and a gag. *Am J Forensic Med Pathol* 1982;3(4):367–9.
49 Grellner W, Madea B. [Physical restraints and gagging in unnatural death]. *Arch Kriminol* 1993;192(1–2):17–26.
50 Mittleman RE. Fatal choking in infants and children. *Am J Forensic Med Pathol* 1984;5(3):201–10.
51 Jumbelic MI. Airway obstruction by a ball. *J Forensic Sci* 1999;44(5):1079–81.
52 Ganeshalingham A, *et al*. Fatal laryngeal diphtheria in a UK child. *Arch Dis Child* 2012;97(8):748–9.
53 Althoff H, Dotzauer G. [The problems of deaths by bolus aspiration ('cafe-coronary') (author's transl)]. *Z Rechtsmed* 1976; 78(3):197–213.
54 Leadbeatter S, Douglas-Jones AG. Asphyxiation by glottic impaction of nasal secretions. *Am J Forensic Med Pathol* 1989; 10(3):235–8.
55 Hunsaker DM, Hunsaker JC, 3rd. Therapy-related cafe coronary deaths: two case reports of rare asphyxial deaths in patients under supervised care. *Am J Forensic Med Pathol* 2002;23(2):149–54.
56 Wick R, Gilbert JD, Byard RW. Cafe coronary syndrome – fatal choking on food: an autopsy approach. *J Clin Forensic Med* 2006;13(3):135–8.
57 Knight B. The significance of gastric contents in the air passages. *Forensic Sci Int* 1976;14:398–402.
58 Pullar P. Mechanical asphyxia. In: Mant AK (ed). *Taylor's Medical Jurisprudence*. London: Churchill, 1984.
59 Gardner AN. Aspiration of food and vomit. *Q J Med* 1958;27:227–42.
60 Ali TT. *Post-mortem Autolytic Changes in Skin and the Role of White Blood Cells*. Leeds: University of Leeds, PhD thesis, 1989.
61 Brinkmann B. [Traumatic asphyxia: pathophysiology and pathomorphology (author's transl)]. *Z Rechtsmed* 1978;81(2): 79–96.
62 Copeland AR. Vehicular-related traumatic asphyxial deaths – caveat scrutator. *Z Rechtsmed* 1986;96(1):17–22.
63 Betz P, Beier G, Eisenmenger W. Pulmonary giant cells and traumatic asphyxia. *Int J Legal Med* 1994;106(5):258–61.
64 Grellner W, Madea B. [Death caused by Perthes pressure congestion]. *Arch Kriminol* 1996;198(5–6):167–75.
65 Gill JR, Landi K. Traumatic asphyxial deaths due to an uncontrolled crowd. *Am J Forensic Med Pathol* 2004;25(4):358–61.
66 Byard RW, *et al*. The pathological features and circumstances of death of lethal crush/traumatic asphyxia in adults – a 25-year study. *Forensic Sci Int* 2006;159(2–3):200–5.
67 Simpson K. Mass asphyxia – medical aspects of the tube shelter disaster. *Lancet* 1943;2(6263):309–11.
68 Polson C, Gee D, Knight B. *Essentials of Forensic Medicine*, 3rd edn. London: Pergamon Press, 1985.
69 Madea B. Death in a head-down position. *Forensic Sci Int* 1993;61(2–3):119–32.

CHAPTER 15

Fatal Pressure on the Neck

- Introduction
- Mechanism of death in pressure on the neck
- Manual strangulation
- Strangulation by ligature
- Arm-locks and 'mugging'
- Hanging
- The sexual asphyxias: autoerotic or masochistic practices
- References

Introduction

This provides one of the most complex and controversial areas of 'asphyxial' deaths, as the mechanism is uncertain and the frequency of such deaths makes them a common problem for both forensic pathologist and jurist.

Pressure on the neck may arise from manual strangulation, ligature strangulation, hanging, direct blows, arm-locks and a variety of accidental lesions, such as entanglement with cords or falling onto the neck (Fig. 15.1).

Strangulation was formerly thought to be a pure asphyxia as a result of 'cutting off the air' by occlusion of the airway during the constriction of the neck.[1] Since the end of the nineteenth century, however, it has been recognized that the rapidity of death in many cases made it impossible for hypoxia to be the sole or even major cause.[2] Many victims died almost immediately and exhibited none of the so-called 'classic' signs of asphyxia.

Others, though showing these signs, still died too quickly for it to be reasonably argued that lack of oxygen had proceeded to a fatal stage. It was common knowledge that most people could hold their breath for over a minute and that some pearl divers could be physically active and yet not breathe for at least 3 minutes, so the much more rapid onset of death seen in many cases required further explanation.

Mechanism of death in pressure on the neck

A number of anatomical and physiological factors must be considered in analysing the effects of pressure on the neck.

Airway occlusion

This may occur either from direct compression of the larynx or trachea, or from a lifting of the larynx so that the pharynx is closed by the root of the tongue being pressed against the soft palate and roof of the mouth. The latter explanation is far more likely, as the strong cartilages of the larynx will resist all but the most extreme compression. Various experiments have been attempted to quantify the force needed to close the airway and blood vessels, but it is difficult to translate the often conflicting results to the degree of violence actually used in fatal events. For example, Brouardel calculated that the force needed to close the trachea was of the order 15 kg.[3]

Occlusion of the neck veins

This factor is almost solely responsible for the appearance of the 'classic' signs of congestion, cyanosis, oedema and petechiae above the line of constriction. The external jugular system is most vulnerable, but any significant pressure encircling the neck will also obliterate the lumen of the internal jugular system, causing a rapid rise in venous pressure in the head, especially if the carotid arteries are still patent, which is usually the case. Brouardel's experiments suggest that a ligature with a tension of 2 kg blocks the jugular return; Reuter found an even lower figure.[4]

Compression of the carotid arteries

The higher internal pressure of the carotid arteries resists occlusion as they are situated much more deeply obscured by the sternomastoid muscles. If bilateral occlusion of the carotids is achieved, almost immediate unconsciousness will ensue, as the supply of arterial blood to the brain by the vertebral circulation is insufficient to maintain cortical function, which depends mainly upon the anterior and middle cerebral arteries that arise from the carotid supply.

Hofmann was the first to suggest this as the main pathophysiological mechanism of death by hanging based on his observations on judicial hangings and experiments with corpses.[2,5] According to Brouardel a ligature with a tension of 5 kg is necessary to occlude the carotid arteries and 30 kg the vertebral arteries, respectively.[3]

Schwarzacher repeated Brouardel's experiments and thereafter, in an improved test setting, made new experiments reporting that a tension of 3.5 kg was enough to occlude carotid arteries and 16.6 kg to occlude the vertebral arteries.[5]

If the carotid circulation is totally occluded for an unremitting period of 4 or more minutes, then irreversible cerebral damage may occur. The time for this to happen is variable and the minimum has been disputed for many years, but the consensus of opinion is that permanent brain damage is very unlikely if the supply has been cut off continuously for less than 4–5 minutes. Total recovery has often been recorded after total ischaemia of considerably longer than this, even in normothermic conditions, with 9–14 minutes being quoted. Where the body has been subjected to low temperature, far longer times have been recorded, including in a 5-year-old boy in Norway who had been submerged for 40 minutes in ice-cold fresh water. Cardiopulmonary resuscitation and re-warming were successful and after 2 days of respiratory treatment the patient gradually regained consciousness. On examination 13 months after the accident all findings were normal.[6]



Figure 15.1 Causes of mechanical asphyxia.

Nerve effects

According to Shoja *et al.* the Persian Avicenna (Ibn Sina) (980–1036) described in his encyclopaedia of medical knowledge, *The Canon of Medicine* (Qanoon fi al-Tibb), patients who became unconscious and fell after having been subjected to pressure on the carotid artery by masseurs in public baths.[7] Pressure on the baroreceptors situated in the carotid sinuses, the carotid sheaths and the carotid body, can result in bradycardia (slowing of the heart), or in total cardiac arrest. This is an example of the physiological mechanism that monitors and adjusts blood pressure and heart rate.

An historical observation of the bradycardia was recorded by a Welshman, Parry, in his book on *Syncope Anginosa*, where he describes the case of the late Admiral K.S. as follows: "*Pressure on one carotid almost instantly reduced the pulse fifteen or twenty beats in a minute, without having previously increased either its frequency or strength; and the pulse returned to its former state as soon as the pressure was removed.*"[8,9]

This mechanism acts through a reflex arc in which the afferent (sensory) nerve impulses arise in the carotid complex of nerve endings, but not – as is sometimes alleged – in the vagus nerve trunk itself.

These impulses pass up to the brain via the glossopharyngeal nerves to the tenth nucleus (*nucleus tractus solitarii*) in the medulla of the brainstem, then return via the vagus (efferent) supply to the heart and other organs. This reflex arc acts through the parasympathetic side of the autonomic nervous system and is independent of the main motor and sensory nerve pathways. It is often claimed, admittedly without much concrete evidence, that fear, apprehension, struggling and possibly the effect of drugs such as alcohol, may heighten the sensitivity of this vagal mechanism. The release of catecholamines during such adrenal responses may well sensitize the myocardium to such neurogenic stimulation (Fig. 15.2).

The vagal reflex has profound implications in relation to pressure or blows on the neck. Sometimes called 'vagal inhibition', 'vasovagal shock' or 'reflex cardiac arrest', the rapid onset of heart stoppage may ante-date any evidence of congestive or 'asphyxial' signs, causing death immediately or within seconds, or at any time thereafter.

It is a matter of some dispute as to whether this reflex can cause immediate cardiac arrest or whether there has to be a period of marked slowing of the heart with negligible cardiac output – or whether an arrhythmia such as ventricular fibrillation precedes such an arrest. Probably any combination can occur, but it is an



Figure 15.2 Possible effects of pressure on the neck: (a) carotid sinus reflex leading to cardiac arrest; (b) jugular venous compression leading to cyanosis and petechiae; (c) carotid artery compression leading to unconsciousness; (d) airway obstruction leading to hypoxia.

indisputable fact that collapse and apparent death can occur immediately on the application of pressure to the neck. Overstimulation of nerve endings in the carotid sinus or adjacent arterial sheath may be brought about by direct pressure from fingers, or from a ligature during strangulation or hanging – or from a blow directed at the side of the neck. Severe pain, such as a blow on the larynx or genitals, may also trigger a 'vagal response'.

The frequency of vagal cardiac arrest

Though different authors vary in the proportion of such deaths that they attribute to reflex cardiac arrest, many believe in the existence of such a mechanism. Quite recently an anonymous electronic questionnaire was sent to 1380 medico-legal experts worldwide and asked about their opinion on the cardioinhibitory reflex, its role in causing death and their diagnostic criteria. A total of 182 (13.2 per cent) questionnaires from 32 different countries were returned. The survey showed that 146 (80.2 per cent) of experts believed that the cardioinhibitory reflex can *theoretically* cause death, whereas of the remaining 36 (19.2 per cent) experts, 18 (9.9 per cent) had no opinion and 18 (9.9 per cent) rejected this possibility. The diagnostic criteria applied varied considerably and the study was further limited by the low response rate.[10] However, one should bear in mind that the reliability of any diagnostic criteria cannot be based on opinion polls but only on scientific facts.

In the author's (BK) own series of fatal pressure on the neck from a variety of causes, the 'classical signs', denoting vascular and perhaps sometimes airway obstruction, were present in slightly less than half the cases. The remaining deaths presented with an absence of congestion, cyanosis and petechiae, the pale faces indicating that cardiac arrest had taken place before the congestive signs had time to appear.

One aspect which is uncertain – and virtually incapable of experimental proof in humans – is whether vagus-mediated cardiac arrest can be spontaneously reversible. Where an arrhythmia leads to arrest, resuscitation by cardiac massage or direct current electrostimulation has an excellent chance of revival – though in most forensic situations, such assistance is often lacking or too late.

However, it is not known whether cardiac arrest caused by the vasovagal reflex, can spontaneously revert to normal rhythm some minutes later – or whether it inevitably leads to death if no timely resuscitation is offered. This may have forensic relevance, as the author (BK) has been involved in several cases where pressure on the neck has lead to a comatose, but heart-beating victim, who later dies on artificial ventilation from irreversible brain damage.[11] In the absence of medical data, the problem then arises as to whether the brain damage was caused by prolonged carotid artery occlusion from neck pressure – or was the result of a momentary neck pressure which caused reflex cardiac arrest, with spontaneous reversion to normal rhythm more than 5 minutes later, by which time irreversible cerebral damage had occurred.

Medico-legal aspects

This phenomenon has considerable legal as well as medical significance, as sudden death from reflex cardiac arrest has been said to occur with total unexpectedness even with relatively slight pressure to the neck. Keith Simpson recorded a case where a soldier at a dance playfully 'tweaked' his partner's neck and was mortified to see her drop lifeless to the floor.[12] Many other such cases have been reported.[3,13,14] Schrag *et al.* reviewed the literature between 1881 and 2009 pertaining to deaths caused by cardioinhibitary reflex cardiac arrest (CiRCA) and found altogether 48 published cases.[15] Their attempt to assess the most likely mechanism of death based on the information presented in the publications, several of which were anecdotal, cannot be considered feasible; however, we agree with the authors that the death due to reflex cardiac arrest is a diagnosis by exclusion that requires a thorough investigation including all the customary ancillary investigations to rule out other causes of death.

Where it can be shown that the death occurred rapidly and without prolonged manual gripping of the neck, the defence may be raised that neither death nor serious injury was contemplated by the accused. It would be much harder to establish this lack of intent if the grip was maintained long enough to lead to florid congestion and petechiae in the face.

A combined mechanism of injury and the duration of neck compression

It is important to remember that the cardiac arrest mode of death may be mixed with the congestive–petechial mode in that, though the first stages of pressure may continue for long enough for congestive–asphyxial signs to appear (perhaps a minimum of 15–30 seconds), a change in grip may then allow the fingers to impinge on the carotid structures and lead to reflex cardiac arrest. Thus the progression of the pure 'asphyxial' process may be abruptly terminated at any point along its pathway to death by the superimposition of 'vagal inhibition', so that the intensity of the congestive changes may be of any degree in any given death.

The duration for which pressure must be maintained is often a contentious issue in criminal trials, as the 'inadvertent squeeze' which causes rapid vasovagal cardiac arrest is likely to be viewed as less culpable than a prolonged, unremitting gripping of the throat.

It is virtually impossible to measure the average minimum time of gripping that will produce congestion, cyanosis and petechiae from venous occlusion. As so often is the case in forensic medicine, animal experiments are useless for this purpose and obviously few cases of strangulation homicide are ever reliably witnessed, especially by some dispassionate observer with a stopwatch! Even in non-fatal cases – which incidentally, can produce far more florid examples of facial and eye haemorrhages than deaths – there is almost never any independent, accurate measurement of the time for which the neck was compressed.

It has been arbitrarily suggested that 15–30 seconds is probably the minimum period which will give rise to petechiae in the eyelids, conjunctivae and facial skin, but this really is 'picking a figure from the air', with little scientific justification.

Years ago, the British Home Office and the Royal College of Pathologists set up a small working party to study this problem, composed of several experienced forensic pathologists and a respiratory physiologist – but the project was soon abandoned because of a total lack of reliable data.

Though it is easy to demonstrate that facial congestion develops within a few seconds of total jugular occlusion, petechiae – the only lasting sign after the venous return is re-opened – do not appear as quickly from neck pressure. However, they can occur from sudden, transient rises in venous pressure, such as sneezing or coughing – whooping-cough is a well-known example – and during the Valsalva experiment of forcibly trying to expire against a closed glottis.

Whether eye petechiae and retinal haemorrhages can also occur during the chest compression of energetic cardiac massage during resuscitation is somewhat controversial. Hood *et al.* claim that it is not uncommon to encounter them in subjects in whom cardiopulmonary resuscitation has re-established blood flow and pressure in small vessels already damaged by hypoxia.[16] Raven *et al.* examined a series of 50 deaths due to natural and unnatural causes in which there had been endotracheal intubation and chest compression during resuscitation. In addition to other injuries they recorded the presence of facial (6 per cent) and conjunctival petechiae (21 per cent) and attributed these changes to resuscitative chest compression.[17] Maxeiner and Winklhofer analysed 474 consecutive autopsies at their institute, 144 (31 per cent) of which had been subjected to cardiopulmonary resuscitation (CPR). Petechial bleedings, predominantly in the conjunctivae, were seen in 19 per cent of the victims as compared to 11 per cent in the non-resuscitated group. However, this was not a consistent finding in all subgroups: if the group of acute cardiac deaths of middle-aged subjects was taken separately, the difference in petechial rate between resuscitated and non-resuscitated subjects in the remaining material was not statistically significant. Further analysis revealed an influence of the following factors in the development of petechial bleedings: cause of death, age and body mass index. The authors concluded that a clear causal relation between resuscitation efforts and petechial bleedings in the face is not likely.[18,19] In another prospective study Maxeiner and Jekat reported on the examination of 196 resuscitated adult patients where the presence of petechiae was assessed also prior to resuscitation. Petechiae were present in 8 of 12 cases already prior to resuscitation. Three other subjects with petechiae found only after CPR were in the group of successfully resuscitated patients, showing petechiae hours after CPR during therapy in intensive care unit – during a phase of on-going cardiac insufficiency. The series included only one subject with petechiae (of low intensity) found during re-examination of the victim in a funeral home 1 day after the unsuccessful resuscitation; however, the authors were unable to offer an absolutely certain explanation to this finding.[20]

Weedn *et al.* presented a case of a non-abused infant who showed retinal haemorrhages, which the authors concluded to be due to CPR.[21] Gilliland and Luckenbach tested that hypothesis by post-mortem ocular examinations following unsuccessful resuscitation attempts on a sample of 169 children. They found no support to the hypothesis that retinal haemorrhages are caused by resuscitation attempts.[22,23]

Causes of reflex cardiac arrest

Vagal inhibition of the heart from stimulation of the carotid neural complex may occur in any form of pressure on the neck, but is much more common in manual strangulation than with a ligature, hanging excepted. Fingers seem more prone to dig deeply and find the structures under the anterior edge of the sternomastoid muscle. Perhaps the movements of the fingers, especially during the shifting postures of a struggle, more readily impinge upon the carotid bifurcation than the more static position of a ligature.

The majority of hangings, however, present with a pale face, free from congestive–haemorrhagic signs. This seems to be caused by the more precipitate impact of the noose on the carotid structures when the victim's weight abruptly bears down, though Polson *et al.* favoured actual carotid occlusion and hence cerebral ischaemia as the common cause of death in hanging[24].

Blows to the throat

Another cause for sudden cardiac arrest is a blow to the neck or throat. This is the basis of the so-called 'commando punch' and some of the oriental martial arts also contain this in their repertoire – often forbidden because of its potential lethality. The edge of the hand is brought forcibly across the side of the neck or the front of the larynx.

Direct violence to the carotid region naturally causes gross stimulation of the afferent nerve endings. Blows directly to the larynx indirectly stimulate the sinus region or the laryngeal sensory nerve endings may themselves trigger the cardio-inhibitory reflex.

It is well known that the hypopharynx and larynx are particularly sensitive to stimulation, which accounts for the sudden deaths from impaction of food in the larynx, or from the flooding with cold water that causes some sudden immersion deaths. The testicles and uterine cervix also have a similar reputation for leading to sudden cardiac death, if unexpectedly overstimulated, especially when the myocardium is pre-sensitized by catecholamines released by fear or emotion.

Manual strangulation

A common method of homicide, manual strangulation is most often encountered when the physical size and strength of the assailant exceeds that of the victim. It is most commonly seen in domestic homicides when a husband kills his wife, in sex-related murders when the victim is again a female, and in child killings, when the killer is an adult.[25] Manual strangulation is rarely committed by a female except on a child and a male rarely kills another male of equal physique in this manner.

Autopsy appearances in manual strangulation

The autopsy findings fall into two groups, namely, the local signs of violence and the signs of the mechanism of death, where discernible.

- Bruising on the neck is the result of the assailant's attack, whereas abrasions may be from either victim or assailant. The bruises are mainly discoid, but may run together into larger areas of confluent bruising. The discoid marks are from finger-pads and are about 1–2 cm in size, though where the fingers skid across the skin surface, longer, irregular marks may occur, especially along the jaw margins. The bruises tend to cluster at the sides of the neck, often high up under the angles of the jaw. Some may overlap the jaw line and trespass on the chin, but others can be lower on the neck spreading down to the inner ends of the clavicles (Figs 15.3–15.8).

  As a result of the shifting grip, often caused by the struggles of the victim, bruising can be anywhere, even at the posterolateral sides of the neck, and on the upper chest over the sternum and collar bones. Some may be seen in the grooves on either side of the larynx, over the anterior edge of the sternomastoid. They are also common over the prominence of the larynx and at the level of the cricoid.

  As in most of the cases seen by a pathologist, death will have taken place at or about the time of the attack, most bruises will be fresh, being dark red or purple. Some may be so severe as to form actual superficial haematomas raised slightly above


Petechiae
Ear bleed
Nose bleed
Congestion
Petechiae
Bruises, abrasions and fingernail marks
Ligature mark
Paler skin below neck

Figure 15.3 Classical features of strangulation when cardiac arrest is delayed.



Figure 15.4 Bruising on the neck and jaw margin in manual and ligature strangulation. Separate bruises along the jaw are due to high finger pressure. Horizontal abrasions due to strangulation with a belt.



Figure 15.5 Manual strangulation with bruising from the assailant and fingernail abrasions from the victim. The face is pale as a result of rapid vasovagal cardiac arrest before congestive signs could develop.



Figure 15.6 Manual strangulation, showing scattered bruises from the fingers of the assailant, but also a pattern of abrasions under the chin and below the larynx, caused by the nails of the victim while attempting to pull off the strangling fingers.



Figure 15.7 Illustration of the need for all doctors to be observant and vigilant. This female was seen in bed by a family doctor and pronounced a 'heart attack' victim. Later examination revealed facial congestion, fingernail marks on the neck and the impression of her necklace on the skin by strangling hands.



Figure 15.8 Abrasion and bruising in manual strangulation. The face is pale, indicating a rapid sudden death; much of the skin damaged is directly over the position of the underlying carotid sinus.

the skin surface. Bruises may often be seen in an asymmetrical pattern, with just one or two on one side of the neck, and a larger group on the opposite side. This may well suggest that a thumb was applied on one side and a group of fingers on the other; this may well be correct, but is not necessarily so and may be fortuitous if a shifting grip caused several reapplications of fingers.

It is sometimes tempting to use such asymmetrical grouping to decide 'handedness', that is to suggest that one bruise on the right side of the victim's neck and a group on the left means that a right-handed assailant gripped from the front. The grouping may not be genuine, however, and because it can be fortuitous, it cannot be definitely determined that it was the right hand nor that it was not placed around the neck from the back. Overinterpretation must be avoided, as in all fields of forensic medicine and 'Sherlock Holmesian' opinions as to the handedness, size of hand, and orientation of attacker and victim in strangulation must be suitably restrained if both justice and the credibility of pathologist are to be preserved.

- Abrasions on the neck: scratches may be caused by the assailant or the victim, usually from fingernails. As with bruising, rough finger-pads (especially from a male hand on the delicate skin of a female neck) may abrade the epidermis and underlying bruises may be overlain by diffuse abrasions, again often seen along the margin of the jaw line.

Linear scratches are the hallmark of fingernails and, when a female strangles a child, the often longer nails of the female may leave obvious marks. Whether male or female, the scratches are of two types: when the pressure is static, straight or curved marks up to 1 cm in length are made; when the nails skid down the skin, linear lines may result, sometimes several centimetres in length.

A static nail mark is often semi-lunar in shape, but caution must be used in interpreting the posture of the hand from this shape. Though it would seem obvious that the concavity of the mark should face the finger-pad, experiments by Shapiro *et al.* showed that the converse may be true.[26] This is caused by fixation of the skin at the centre where the nail digs in, with escape at the margins, so that when the traction relaxes, the mark appears inverted, with the convexity facing the finger-pad. However, experiments by others, including the author (BK), show that this phenomenon is by no means invariable and often the marks are the result of the nails being applied in the expected direction.



Figure 15.9 Mucosal haemorrhages in the interior of the larynx immediately below the vocal cords, in manual strangulation. This is a common finding and the mechanism is uncertain. It can occur as here – in the absence of generalized congestive–petechial changes and appears to be caused by local trauma.

Scratches are the result of the victim's attempts at pulling away the strangling hand. As most victims are female, the nails may be long and the scratches more severe than those from the assailant, which are often absent altogether. These defence scratches may run in parallel lines from grouped fingers and run in a vertical direction in the long axis of the neck, though they are often random.

In the autopsy on a strangled victim it is good practice to take fingernail scrapings or clippings for full forensic science investigation. These should be preserved and labelled so that each clipping or scraping is individually identified – or failing that, at least the left- and right-hand material should be kept separate. Skin fragments or blood under these nails may provide blood typing or DNA characteristics that can be matched to an alleged assailant – and other valuable trace evidence, such as hairs and fibres might be trapped in a torn fingernail – though admittedly, the number of occasions when such evidence has been gained is extremely small.[27]

The alleged assailant should always be examined medically to correlate any injuries that may have been inflicted on him by the fingernails of the victim, such as facial or hand scratches. If he is examined soon after the offence, his own fingernail scrapings should be taken, especially if the victim has neck abrasions, so that comparison studies can be made between any debris found and the tissue types of the victim.

Internal appearances in manual strangulation

Internally, the bruises described above may be visible to a greater or lesser extent in the tissues of the neck. Often they are quite superficial and are confined to the dermis, but some may be visible to an appreciable depth in the muscles and other structures in the neck (Fig. 15.10).

The platysma muscle may be bruised, but the sternomastoid and the deeper strap muscles that run vertically along the larynx may show patchy bleeding, not always corresponding exactly to the position of surface bruises. They may contain infiltrated blood or even frank haematomata, especially the sternomastoid.

At autopsy, it is essential to release the blood in the venous system before dissecting the neck to avoid or reduce artefactual haemorrhages that can occur in the region. It may be easiest to reflect the scalp and remove the brain before dealing with the neck, to release venous engorgement. Alternatively, after the skin of the neck has been carefully flayed off in a wide 'V' incision,



Figure 15.10 Dissection of the neck in a victim of manual strangulation. In this case there are relatively few areas of bleeding in the strap muscles, on the submandibular gland and jaw margin. Removal of the brain and heart before dissection of the neck reduces the risk of artefactual haemorrhages in this region.

the internal jugular vessels can be incised before any further manipulation to release the venous pressure, but removal of the skull is preferable.

When available, multislice spiral computed tomography (MSCT) and magnetic resonance imaging (MRI) or radiography of the neck may be carried out before any dissection to determine the state of the soft tissues of the neck, cervical spine and the laryngeal cartilages.[28,29] If the new techniques of post-mortem imaging are not available an alternative method is to X-ray the isolated larynx before dissection.

When examination of the deep neck structures begins, careful removal of the overlying tissues layer by layer is required, seeking genuine haemorrhage as each set of muscles is exposed. There may be bruising into the thyroid capsule and into any of the strap muscles. The vascular bundles must be handled carefully and the large veins opened with scissors. The carotids can be opened *in situ*, or after the laryngo-oesophageal pluck has been removed.

Spurious bleeding behind the larynx

Bleeding over the front and sides of the larynx is usually genuine, if the venous pressure has been released beforehand, but great caution must be employed in interpreting bleeding behind the larynx and pharynx.

In any autopsy, substantial haemorrhage may be seen over the posterior surface of the oesophagus and on the anterior longitudinal ligament of the cervical spine. This is a common post-mortem artefact, described fully by Prinsloo and Gordon and sometimes known by their name (Fig. 15.11).[30]

In the absence of any other neck lesions, especially bleeding in the lateral and anterior parts of the neck, no reliance can be placed on this haemorrhage. It tends to develop more as the post-mortem interval lengthens and even releasing the venous pressure in the neck by removal of the brain, or opening the jugulars early, does not ensure its absence. To avoid the Prinsloo and Gordon artefact, a special technique of dissecting the neck is recommended by Shapiro.[31]

Another artefact in the neck, much easier to recognize as false, is 'banding' of the oesophagus, especially when the tissues are congested. These bands are pale areas in the mucosa caused by post-mortem hypostasis being prevented from settling by the external pressure of adjacent anatomical structures, including parts of the larynx, trachea and aortic arch. Banding is common in routine non-trauma autopsies, but has been misinterpreted by inexperienced pathologists as evidence of strangulation.



Figure 15.11 Artefactual post-mortem haemorrhage on the posterior surface of the oesophagus in a natural death. This was fully described by Prinsloo and Gordon,[30] and is a reason for draining the blood from the venous system of the head and neck before beginning to dissect.

Forensic anatomy of the larynx

The larynx consists of a large 'V'-shaped thyroid cartilage, which has a prow-like prominence anteriorly and is open at the back. Below this is the smaller cricoid cartilage, which is narrow at the front, but expands posteriorly to occupy the lower part of the space left by the open thyroid cartilage (Fig. 15.12).

At the upper margin of the posterior wing of the thyroid on each side, are the superior horns or 'cornuae', which are connected by the thyrohyoid membrane to the greater horns of the hyoid bone that lies immediately above.

The hyoid bone lies at the root of the tongue, and consists of a central horizontal 'body', to which are attached two long 'greater horns', which sweep backwards and slightly upwards above the upper margin of the thyroid cartilage and superior horns. The hyoid often has natural joints, sometimes even with synovium, which lie at the junction of the body with the greater horns (Fig. 15.13).



Figure 15.12 The forensic anatomy of the larynx. The hyoid and thyroid bones fracture either from direct lateral compression, or from traction from the thyrohyoid membrane when it is compressed.



Figure 15.13 The hyoid bone.

There are two lesser horns on the upper surface of the body that have no forensic anatomical significance. The hyoid calcifies at variable times: the body is usually calcified, but the horns may calcify irregularly, both in space and time. In teenagers and young adults they are usually cartilaginous and the joints mobile. In middle and later life, the hyoid and thyroid horns calcify and become more brittle. The cricoid cartilage is a modified upper tracheal ring but can also become partly calcified as age increases; no meaningful ages can be placed on any calcification, but traumatic fractures can occur at any time except in children and most teenagers, in whom fractures are rare.

Injury to the larynx

During manual strangulation the larynx may become damaged in various ways. The pressure is mainly bilateral, so that the sides of the larynx are squeezed. Particularly vulnerable structures are the four 'cornuae' or horns, which protect backwards to maintain the patency of the airway around the glottis. Lateral pressure of the fingers can displace any of the four horns inwards, either by direct pressure or by pressure on the thyrohyoid membrane, which then drags the horns medially. In young persons, the horns are so pliable that they return to their normal position on release of the pressure but, variably beyond the third decade, they may be sufficiently calcified to fracture.

The appearance of a fractured horn is of a loose or even flapping termination. The horn usually displaces medially, but is held by the thyrohyoid ligament. At autopsy it is advisable to cut down this ligament carefully between thyroid cartilage and hyoid to destroy the 'splinting' effect that may support a broken horn. As will be discussed later, however, there will be a haemorrhage at the fracture site that will make the lesion obvious. In the case of the hyoid, care must be taken not to misinterpret a natural joint as a fracture. These are more medial than the usual site of fracture, which is likely to be within 1 cm of the tip. The jagged edge of the fracture line may be exposed, especially in an older person with a brittle horn. Radiography before dissection is an excellent way of confirming a fracture, identifying natural joints and detecting any other fractures in the thyroid or cricoid cartilage.

Though the hyoid bone has received most attention in publications as being the marker of violence to the larynx, in fact the thyroid horns are far more vulnerable. Simpson found that, in 25 successive deaths from manual strangulation, there were 22 fractures of thyroid horns but only one fractured hyoid.[32] Though this ratio is not typical of the experience of most pathologists, there is no doubt that the superior horn of the thyroid is much more fragile and more vulnerable than the greater horn of the hyoid bone. Although fractures of the horns are more common with advancing age, they can on rare occasions be found even in teenagers. Care must be taken, however, not to confuse mobility at natural joints with a fracture.[33]

Conversely, undoubted severe violence to the neck in older persons does not necessarily cause horn fractures. The frequent persistence of joints at the base of the greater horns of the hyoid may allow movement and so avoid fractures when compressed. The cricoid and the main ala of the thyroid cartilage may be cracked, but this is an index of much greater pressure from strangling fingers. The plates may break in a spiral or oblique fashion and the cricoid may crack anteriorly through the narrow bridge rather than at the wider posterior plate. Fractures of these larger areas are also found in direct blunt violence such as punching, kicking or arm-locks, often as part of general severe damage and disruption of the entire larynx.

Significance of laryngeal fractures

Laryngeal cornual fractures are, of course, merely indicators of pressure applied to the neck and are not themselves relevant in terms of a threat to life. This is sometimes misunderstood by laymen, especially police and lawyers, who have been misled by the importance that pathologists attach to the finding of a fractured horn into thinking that the injury itself is a significant contribution to the death.

Such fractures, if proved to be genuine, are certainly significant in proving the application of violence to the neck, but certain precautions must be observed in their interpretation. The sole finding of a fractured horn, where there is no other injury to the skin, subcutaneous tissues, muscles or rest of the larynx is of little value unless there is firm circumstantial evidence of violence to the throat.

When a fracture of a laryngeal horn is found, it must first be proved to be ante-mortem in origin. Post-mortem fractures undoubtedly occur, either from mishandling the body during transit or from incorrect autopsy techniques – though the frequency of the latter has been overestimated.

It is certainly possible to damage the larynx post-mortem by allowing the neck to fall against a hard surface or sharp edge during removal from the place of death, or during handling in the mortuary. Such damage, however, is more likely to occur to the laryngeal plate of the thyroid cartilage or to the cricoid, rather than to the laterally placed horns, though these can be broken. Damage at autopsy is usually caused by an inexperienced pathologist or autopsy-room technician, especially when forensic expertise is lacking. Clumsy removal of the tongue and neck structures can break the thyroid or hyoid cornuae, especially in old persons where they are calcified and brittle and when any natural joints are ankylosed.

This may be one justification for post-mortem imaging or radiography before autopsy, but probably the danger of artefactual breakage has been overestimated, especially where a gentle removal technique is employed.

Proof of ante-mortem laryngeal fracture

This must be obtained by demonstrating haemorrhage at the fracture site. It is usually obvious to the naked eye and can be confirmed histologically. Sometimes the bleeding is prominent, with a blood bleb under the periosteum or perichondrium at the fracture line, and the broken end of a calcified horn may be palpable and even slightly crepitant. Where no macroscopic evidence of bleeding is found, careful histology of the fracture site will almost always reveal some red-cell extravasation, but this evidence is of less value because microscopic – and even slight macroscopic – oozing can occur from a post-mortem fracture of a horn. Bleeding is therefore a ‘one-way’ criterion: if there is no haemorrhage, the fracture must be post-mortem, but if there is a small bleed, then the lesion can be either ante-mortem or post-mortem. Naturally the findings must be taken in conjunction with other evidence of neck injury and, if there are surface bruises, scratches, muscle bleeding, intralaryngeal and tongue haemorrhage, then a minimal bleed at a fractured horn can be accepted as probably ante-mortem (Fig. 15.23).

Conversely, it must again be emphasized that the solitary finding of a fractured laryngeal horn, even with slight associated bleeding, is not in itself sufficient evidence of ante-mortem trauma to the neck.

Other causes of fractured laryngeal horns

The hyoid and thyroid horns can be broken other than by manual strangulation. Ligature strangulation and hanging can certainly cause these lesions, though not as often as manual throttling. Direct violence can also break the cornuae, but usually only as part of more diffuse laryngeal damage. A punch or kick in the throat can disrupt the larynx and break the horns as part of general damage. Even wide, blunt pressure can fracture the horns, however, such as an arm-lock from behind squeezing the larynx against the cervical spine. It has been said that such direct violence from the front tends to splay the fractured horns laterally, whereas in manual strangulation the horn tends to fall inwards – but this is too tenuous a claim to be of much practical value.

In accidents, the larynx can be damaged. In falls, the larynx is usually protected by the prominences of the chin and chest, but if the fall is onto a ridged object, such as gate or chair-back, then a focal impact can injure the throat.[34] The author (BK) has seen a death in a housebreaker, who slipped when trying to climb through a sash window. He fell with his throat across the top of the window-frame and died – presumably of a vagal cardiac arrest – being found suspended by his neck next morning with fractures of the laryngeal cartilages.

Other laryngeal injuries in strangulation

Other injuries to the larynx include splitting of the ala of the thyroid cartilage, often either in the midline or obliquely across the left or right plate. This may be part of a violent strangulation, seen by Green in 12 per cent of his series – but is more often seen in blows to the front of the neck, either by fist or the edge of the hand, or a kick or any other kind of substantial trauma directed at the front of the neck.[35]

The cricoid cartilage, a circle shaped like a signet ring that lies below and partly within the thyroid cartilage, may also be fractured by manual throttling when pressure is applied rather lower than usual. Again, this cartilage tends to break either across the front midline or obliquely (Figs 15.14, 15.15). Though an uncommon injury, a severe displacement of a broken cricoid – especially if accompanied by mucosal tearing and bleeding – may project backwards into the airway and cause a partial obstruction.

The interior of the larynx may also show indications of pressure on the neck. This usually takes the form of haemorrhage into the mucosal lining and is most often seen immediately below the vocal cords (Fig. 15.9). Bleeding may be intense here, but its cause is obscure. It can occur with no other damage to the cartilages of the larynx and it is then hard to equate it with direct physical pressure as it lies on the protected inner surface.

Similar, but less intense, haemorrhage is sometimes seen on the surface of the epiglottis, which more often shows a shower of petechial haemorrhages if the death was not sudden.

Such haemorrhage inside the larynx is often a bright, fiery red, unlike the dark cyanotic discolouration that is seen in the pharynx, root of tongue and larynx in congestive–asphyxial deaths, and is caused by obstructed venous return rather than direct trauma. At autopsy the base of the tongue should always be sliced, as deep haemorrhages may be present, usually at the sides of the tongue, deep congestion being more central or across the whole posterior part of the tongue.



Figure 15.14 Manual strangulation with fingernail marks and scratch-like abrasions on the neck and the jaw.



Figure 15.15 Manual strangulation with fracture of the cricoid cartilage and tiny blood extravasation in the adjacent tissue (arrow). The victim is shown in Fig. 15.14.

Damage to the carotid arteries

In the sudden 'vagal inhibition' type of death caused by pressure on the baroreceptors of the carotid sinus and sheath, it is unusual to find anatomical confirmation of injury to these structures.

There may be deep haemorrhage in the neck tissues surrounding or adjacent to the bifurcation of the common carotid artery, but this is often absent in these cases of cardiac arrest – and conversely, such bleeding may be found in the slow 'asphyxial' deaths, as part of the generalized diffuse bleeding into the tissues.

Rarely, careful dissection of the carotid arteries may reveal an intimal tear or bleeding into the walls of the vessels at or near the carotid sinus. Amussant was the first to describe these intimal tears in cases of hanging.[36] Simon carried out hanging and strangulation experiments with corpses and demonstrated that they also can be produced post-mortem.[37]

A delicate technique is required and artefactual damage must be carefully excluded, especially that from the point of scissors used to slit open the artery. Such tears are more often found when a forcible impact or a more focal pressure has been applied, such as from a thin ligature that can cut deeply and abruptly into the neck, especially in hanging. Generally, little or no morphological confirmation is to be expected in the cardiac arrest type of death, following pressure on the neck. The diagnosis is one of exclusion, based on the absence of any congestive–cyanotic–petechial appearances, together with some circumstantial history of sudden death while pressure is being applied to the neck.

As already mentioned, one problem is that pressure may be maintained for long enough – perhaps a minimum of 15–30 seconds – to produce these signs, yet not cause death, but death then supervenes abruptly because a vagus-mediated cardiac arrest is superimposed on the early asphyxial mode. In the absence of any structural damage to the carotid apparatus, autopsy cannot differentiate between the two mechanisms and only the history (which is rarely available for obvious reasons) can assist in interpreting the sequence of events.

Strangulation by ligature

Pressure on the neck may be effected by constricting all or part of the circumference of the neck by a ligature. This is sometimes called 'garrotting', though strictly this refers to the tightening of a noose around the neck by twisting a rod within the ligature, a form of judicial execution once employed in Spain, from which also comes the description of the twisting device as a 'Spanish windlass'. This method had a refinement in which the back of the neck was forced against a sharp spike which penetrated the spinal cord.

In forensic practice, if hanging is excepted as a separate entity, most ligature strangulations are homicidal. Some are suicidal and a few accidental, usually in children.[38]

The nature of the ligature

The ligature may consist of a wide variety of objects, some not obviously suitable for the purpose, yet effective in causing death. Cords, wires, ropes and some belts are strong and relatively thin, so that they tend to cut deeply into the neck if the tension is great. Softer fabrics, however, in the form of scarves, ties, towels, stockings, tights and even strips of bed-linen may be used and may cause some problems in interpretation if they are removed from the scene before the investigation begins. The ligature may be applied as one turn around the neck – or even less, as homicides have been perpetrated by the assailant pulling a U-shaped ligature against the front and sides of the neck, while standing at the back. Even a flexible rod, such as bamboo cane or – in India – a flat 'lathi', can act as a ligature if the two ends are forcibly pulled back from behind against the front of the throat.

In the majority of cases, however, the ligature is crossed over itself after passing a full circle around the neck – and several turns may be wound around, secured with one or more knots. These multiple turns are not uncommon in suicide, where two, three, or even more circles are wound around, often with complex knots. The presence of these more complicated ligatures by no means confirms homicide – in fact they are more common in suicide, where the determined victim is eager to succeed. The ligature may be tightened even further by means of the 'Spanish windlass' mentioned above, which consists of some rod-like object, which may be a ruler, stick or screwdriver inserted between the ligature and the skin, and twisted around several times. The rod may be held in position by being wedged under the chin or against the shoulder or chest. This device may be seen in either homicides or suicides (Figs 15.27, 15.28).

The ligature mark

The appearance at autopsy naturally depends on the nature and texture of the ligature. When there is a pronounced pattern, such as the weave of a cord or the plaiting of a thong, the same pattern may be imprinted into the skin. In homicide, where the ligature has been removed by the killer, such a pattern may be of great value in tracing its origin. When a fabric has been used, such as a scarf or towel, the marks on the neck are more difficult to interpret. A broad, flat band may leave no mark whatsoever, but it usually leaves one or more linear marks on the skin of the neck, often discontinuous. These may fade if the body is not seen soon after death and if the surface has not been abraded (Figs 15.17, 15.18).

A fabric ligature may leave a sharply defined mark, which may be misinterpreted as being caused by a narrow cord or wire. The reason for this is that when a broad piece of cloth is tightly stretched, one or more bands appear that are under greater tension than the rest. It is these that mark the skin, and no sign may be left that a wider area was lying on either side of the most tensed band. These marks are usually less well demarcated at the edges than a cord or rope, but can cause confusion (Fig. 15.16).



Figure 15.16 Homicidial ligature strangulation by a silk scarf. Although wide fabric was used, a narrow linear mark was made by the most tightly stretched band.

When the ligature is still in position when the body is examined, it may appear to be deeply embedded in the skin, sometimes almost out of sight, and on removal a deep groove may be seen in the skin. This embedding may be accentuated by oedema of the tissues, especially above the ligature, which initially may not have been applied so tightly. The swelling can continue to develop to some extent even after death, accentuating the depth of the groove. Presumably some passive transudation of tissue fluid continues even after the circulation has stopped. In suicides, multiple turns and knots may have been applied and obviously the degree of tightness as seen later at autopsy could not have been present during the application of the ligature, otherwise incapacity would have been so rapid that the process could not have been completed. In such cases, it is remarkable how often the mode of death still seems to be of the non-asphyxial cardiac arrest type. It might be expected that vagal stimulation could not have occurred once the expected static position was attained with the completion of ligation – but experience indicates otherwise, the mechanism remaining obscure.

The skin mark may remain red, especially if the ligature was of softer material such as cloth, but cords, ropes and wires tend to abrade the surface, which later becomes yellow or brown and parchment-like. This is seen particularly in hanging, when the friction and chafing may be greater.



Figure 15.17 Self-strangulation of an inpatient on a psychiatric ward because of severe depression. Ligature with a woollen scarf fastened with a simple knot on the front of the neck.



Figure 15.18 After removal of the scarf in Fig. 15.17, only a pale band-shaped area without hypostasis is seen.

The stiff, brownish-yellow appearance occurs post-mortem and tends to become more pronounced as the interval lengthens after death. The mark may be slightly wider, narrower or the same width as the actual ligature, depending partly upon how deeply it cut into the skin. There is often a narrow zone of reddened hyperaemia at either margin of the mark. This used to be taken to indicate that the ligature must have been applied during life – though by analogy with the spurious 'vital reaction' sometimes seen as a post-mortem development at the margin of burns (see Chapter 11), this sign is of doubtful reliability. Experiments by Pollak (personal communication) confirm this by the production of similar marginal reddening by applying ligatures soon after death – it seems to be due to lateral displacement of blood from the squeezed area immediately below the ligature.

The position of the ligature mark

The geometry of the mark is important in interpreting the fatal events. In strangulation, unlike hanging, the mark tends to encircle the neck horizontally and at a lower level (Figs 15.19–15.21). Typically it crosses immediately above or below the prominence of the larynx and passes back to the nape of the neck. In homicide, where a single turn is used, there is often a cross-over point where the two ends of the ligature mark overlap. This may be at the front, side or back of the neck, depending on the relative positions of assailant and victim.

When a knot is tied, it may leave a mark on the skin and, of course, if multiple loops are present, some or all of these will be represented on the skin. Unless the killer is pulling upwards, the mark will not be seen to rise nor will there be a gap in the mark at the highest point, as seen in most hangings.



Figure 15.19 After drinking all-day with an acquaintance, an argument broke out and the acquaintance grabbed the victim by his string vest and strangled him. Horizontal ligature marks and some abrasions visible next to the ligature marks.



Figure 15.20 Ligature strangulation with a generally horizontal course for the two strands of cord that diverge from the skin at the back of the neck.



Figure 15.21 Horizontal ligature mark encircling the neck of a female who was strangled with a string by her lover after she refused to terminate her pregnancy.

In the later section on hanging, the point will be made that sometimes a hanging mark may resemble a ligature mark, but the converse is almost unknown.

Other signs of local injury in ligature strangulation

There may be scratches on the neck, but these are usually caused by the attempts of the victim to pull away the ligature. Fingernail marks, sometimes linear and vertical, may be present as in manual strangulation, but not focal abrasions or bruises. Internally there may be superficial haemorrhage under the ligature mark, though this is often minimal. Depending on the force with which the ligature was applied, there may be deep damage in the muscles of the neck, but this tends to be less than in manual strangulation. Similarly, there may be laryngeal injury, but less severe than from pressure from the hands. The hyoid bone and thyroid horns may be fractured, especially where the ligature rides at the level of the thyrohyoid ligament, but damage to the laryngeal cartilages is much less common than in manual strangulation. Gonzalez found in 24 fatal manual strangulations, four hyoid fractures but nine thyroid and cricoid fractures.[39] In 25 deaths from manual strangulation, Simpson found only one hyoid fracture but 22 with thyroid horn fractures. It is rare for the main thyroid plate or the cricoid to be fractured unless gross violence was applied with excessive pressure by a strong ligature. Uncommonly, a narrow wire may be used, the so-called 'cheese-cutter' method. Here, strong pressure over a small area – such as that delivered by a piano wire – may actually lacerate the skin, and even cut into the deeper tissues and cartilages.

Where much bruising and abrasion is seen, especially if scattered and away from the actual ligature mark, then the possibility of a combination of manual and ligature strangulation must be considered (Figs 15.24, 15.25). This is not uncommon, the handling of the throat either preceding or accompanying the application of the ligature. Fractures of the laryngeal structures may be caused by this element, rather



Figure 15.22 Subconjunctival haemorrhages and facial petechiae in homicidal ligature strangulation.



Figure 15.23 Fracture of the left laryngeal horn (arrow) with haemorrhage. The body was recovered from a lake based on the confession of the perpetrator. Further findings were haemorrhage in the fractured cricoid cartilage, bruising on the neck and petechiae in the conjunctivae and larynx.



Figure 15.24 Typical appearance of congested, cyanosed forehead, with multiple petechiae in the skin, in a female strangled manually and by ligature. Circular bruising probably due to knuckle-blows. The scarf tied around the neck initially suggested only ligature strangulation.



Figure 15.25 In the case shown in Fig. 15.24, when the scarf was removed typical bruises and abrasions of manual strangulation were seen in addition to the ligature mark.

than the associated ligature. A deeply sunken narrow ligature applied with force may damage the carotid arteries and focal injury to the intima may rarely be found on careful dissection.

The mode of death in ligature strangulation

The mode of death is more often the 'classic asphyxia' picture than in manual strangulation, where sudden cardiac death is common before congestive–petechial changes have time to occur. The contrast in the appearance of the skin immediately above and below the ligature mark is often striking, with pale skin below, and a puffy, oedematous, congested, cyanotic and haemorrhagic surface above. Petechiae may abound in the eyelids, conjunctivae and facial skin, and there may be bleeding from the ear and nose (Fig. 15.22). This is by no means invariable, and many ligature strangulations die rapidly from vagal reflex cardiac arrest before any congestive signs have had time to appear.



Figure 15.26 Self-strangulation by ligature, with three turns around the neck and a complex knot. There was no doubt from the circumstances that the deceased male had deliberately killed himself with this telephone cord, but the mechanism of apparent vasovagal death before any congestive changes could appear remains obscure.

This can occur in both homicide and suicide and, as mentioned earlier, the mechanism is obscure, especially where the victim – bent on self-destruction – has been able to complete multiple loops around his neck and tie several knots before dying (Figs 15.26, 15.29).

Accidental ligature strangulation – which may be actual hanging if the body weight is thrown wholly or partially upon the ligature – is seen in the tragedies that occur to young children, who may become entangled in blind or curtain cords, usually when their cot or playpen is left too near a window.[40–42] Occasionally accidental ligature strangulation has been caused in adults when scarfs or other pieces of clothing have become entangled in various types of machinery or houshold devices.[43–46]



Figure 15.27 Suicidal ligature strangulation by means of a 'garrotte'-type device. The metal band has been cushioned by a cloth. The head of the screw (not shown) has a knob to twist the ligature tight.



Figure 15.28 Horizontal parched ligature mark is seen after removal of the strangling device shown in Fig. 15.27.


[redacted] CONSTABULARY
Ligature from [redacted]
Removed by Dr. [redacted]
at 1.30 a.m. 14/5/ 6[redacted]
Endś cut at point below right ear

Figure 15.29 At autopsy on a victim of ligature strangulation, the ligature should be cut well away from the knot, if one is present. The knot should never be untied, but preserved for forensic examination. If the ligature is in danger of unravelling, it should be tied at two places and divided between these points. (Reproduced with permission from Robert Hale Publishers.)

Arm-locks and 'mugging'

The original meaning of 'mugging' has now been confused by its application, especially in North America, to any form of robbery with violence. The term strictly means throttling by pressure from an arm held around the throat. The attack is usually made from behind, the neck being trapped in the crook of the elbow. Pressure is then exerted either on the front of the larynx, or at one or both sides by the forearm and upper arm. The mechanism is further discussed in Chapter 10, as an arm-lock (or 'choke-hold') is a method of restraint used by police officers for law enforcement, but it is rapidly losing favour because of the number of inadvertent fatalities due either to 'asphyxia' or to reflex cardiac arrest. Following several fatalities during police arrests in the early 1990s, the Association of Chief Police Officers in Britain have issued recommendations that arm-locks be avoided during the restraint of violent prisoners.

The autopsy features are those of ligature strangulation with a broad object, in that signs may be minimal. Some diffuse abrasion may be seen, especially along the margin of the jaw or lower face, sometimes over a considerable area, caused by the friction of the forearm. Internally there may be diffuse bruising, but this again may be slight or even absent. The larynx may also escape damage, though if it is pressed backwards against the spinal column the thyroid horns and even the hyoid may fracture (see also Chapter 10).

Hanging

Hanging is a form of ligature strangulation in which the force applied to the neck is derived from the gravitational drag of the weight of the body or part of the body.

Judicial hanging

The modern form of judicial execution is unrelated to the usual suicidal hangings seen in routine forensic practice, as it depends upon severe mechanical disruption of the neck structures. Until the nineteenth century judicial hanging in Britain was carried out even more barbarically by 'ordinary' hanging, where the victim was strangled at the end of a rope by his own weight. At the infamous Tyburn execution site near the present Marble Arch in London, tens of thousands were dispatched, the usual method being the placing of a rope noose around the neck of the condemned person, who stood on a cart or ladder. This support was then removed leaving the victim suspended. Some contemporary accounts suggest that many died with little further movement, but this was not the case for a considerable number and it was not unusual for the victims' relatives to pull on the victims' legs to shorten the agony. It appears to have been a desire to increase the rapidity with which death occurred that 'improvements' were made, principally the use of a drop effected suddenly by means of a trapdoor. The use of a drop required the placing of the 'knot' – really a brass eyelet and rubber washer – under the left ear where it was less likely to be pulled over the head than at the occiput, a traditional site. The aim was that, when the rapidly falling body was suddenly arrested, the cervical spine would be dislocated resulting in traction on the spinal cord with consequent spinal cord or brainstem disruption. Exhumation of persons executed by this method shows that fracture was not usual but post-mortem accounts of findings indicate that cervical spine dislocation – occurring at various levels – was common, with resulting cord or brainstem damage. However, the effects do seem to be variable with decapitation occurring at drop heights, which, in others, judging by contemporary descriptions of the execution, appear not even to have caused rapid unconsciousness. Though cerebral function presumably ceased immediately on cord or brainstem damage, the heart usually continued to beat, sometimes for up to 20 minutes until hypoxia caused arrest.[47–51]

Suicidal and accidental hanging

Apart from the now rare 'lynching', hanging is almost always suicidal or accidental, the former being by far the most common.[52–54] Hanging has many features in common with ligature strangulation. Death is, however, more often caused by reflex cardiac arrest from pressure on the carotid structures. Many more victims of hanging are found to have pale faces, rather than the congested, haemorrhagic appearance of the slower asphyxial type of death. James and Silcocks, in a 15-year survey of hangings in Cardiff, found congestive–petechial features in 27 per cent, being related to the completeness of suspension.[55]

Polson *et al.* suggested that the usual pale face in hanging is caused by cerebral ischaemia from bilateral occlusion of the carotid arteries rather than a vasovagal effect, though this seems incapable of proof.[24] In either event, the death can be taken to be rapid if no asphyxial signs are present.

Methods of hanging

Most hangings are self-suspension. This may be carried out by a wide variety of methods, but a typical method of self-suspension is to attach a thin rope to a high point such as a ceiling beam or staircase. The lower end is formed into either a fixed loop or a slipknot, which is placed around the neck while the intending suicide stands on a chair or other support. On jumping off or kicking away the support, the victim is then suspended with all or most of his weight upon the rope (Fig. 15.30).[56]



Figure 15.30 Typical posture in hanging with the suspension point rising to the ear, tilting the head to the opposite side. The tongue is projecting because of upward pressure on the larynx and root of the tongue. There are no congestive appearances. As a slip-noose was used, the rope is in contact with the skin throughout the full circumference of the neck.

The many variations of this involve either the ligature or the height of suspension. Wires, string, pyjama cords, belts, braces (suspenders), scarves, neckties, stockings and numerous other devices may be used, depending on availability. In prison or police custody considerable ingenuity may be employed to defeat the efforts of the custodians to remove anything that could be used for self-destruction: shoelaces, stockings and torn bed-sheets have been used in prison cells (Figs 15.31, 15.32, 15.34, 15.35).[57,58]

Suspension is often not high enough to keep the victim's feet clear of the floor. Commonly, when the person steps from his support, the stretch in the ligature rope is sufficient to allow the feet to reach the ground, but this by no means prevents a fatal outcome. The weight of the upper part of the body leaning into the noose is often more than enough to cause death. Successful hanging can occur from low suspension points, where the person is merely slumped with part of his weight into the ligature. Hanging can take place from doorknobs, bedposts and any other convenient low securing point (Fig. 15.33). The body may be merely slumped against the door or bed or chair, with the legs and buttocks supported on the floor, so that only the weight of the chest and arms is contributing to the fatal pressure within the noose. One 'hanging' seen by the author (BK) was successfully achieved by merely leaning the neck into the shallow curve of a low clothesline stretched between two posts in a garden.



Figure 15.31 Suicidal hanging with the feet flat on the floor. The deceased male stepped off the low stool, but the stretching of the cloth ligature prevented total suspension. Many suicidal hangings are successful at much lower levels, such as doorknobs and bed headboards.

It is unusual for a suicidal hanging to be sufficiently violent for damage to the cervical spine to occur as the length of drop is usually too short. Only occasionally will a person jump from a roof or other high place with a rope around his neck – here severe injury can occur, even decapitation if the rope is strong enough (Fig. 15.43).[59,60] More often the jump will be from an attic trapdoor or a tree, sufficient to damage the vertebrae or atlanto-occipital joint. The author (BK)



Figure 15.32 Suicidal hanging by means of a necktie. The deceased male had suspended his neck from a hook on the back of a door by tying two neckties together. The hook had pulled out and he was found on the floor. Note the pale, uncongested face, indicating rapid cardiac arrest.



Figure 15.33 Hanging deaths in children are very rare. This 7-year-old boy took his leave from his playmates and hanged himself from a bedpost under their very eyes.



Figure 15.34 Hanging with a fixed knot in the cord, so that there is a segment of skin free from the mark where the cord rises towards the knot. This was part of the common murder–suicide pattern in a domestic homicide.



Figure 15.35 This inmate had torn up a sheet and attached both ends to a water tap (not shown) and is leaning into the loop in sitting position with sparing of the back of the neck.

once saw a fractured cervical spine when a heavily built soldier jumped off a lavatory seat after securing a rope to the overhead cistern, but this is unusual.

The hanging mark

The mark on the neck in hanging can almost always be distinguished from ligature strangulation. The circumstances will usually indicate the fact of hanging, but sometimes the rope will break or become detached, and the deceased will be found lying with a ligature around his neck. There may then be doubt as to whether he was hanged or strangled. Obviously a search of the locus for a suspension point and signs of rope attachment will be the task of the investigators.

The hanging mark almost never completely encircles the neck unless a slipknot was used, which may cause the noose to tighten and squeeze the skin through the full circumference of the neck. In most instances the point of suspension is indicated by a gap in the skin mark, where the vertical pull of the rope leaves the tilted head to ascend to the knot and thence to the suspension point. This gap is usually seen at one or other side of the neck or at the centre of the back of the neck. Much less often it is under the chin. The knot itself may be impressed into the skin, especially if at the side of the head, above the gap where the anterior mark begins (Fig. 15.36).

The hanging mark, the features of which resemble those described earlier in strangulation, is usually deepest at the side diametrically opposite the suspension point where the maximum load-bearing occurs. Like ligature strangulation, the mark may be abraded, brown and dried to a parchment-like consistency after death. There may be a narrow red zone either above or below (or both sides) the ligature mark. This is not an indicator of vital reaction, as explained in relation to ligature



Figure 15.36 A deep hanging mark showing the high position under the chin rising to the back of the neck. The spiral weave of the rope is clearly imprinted in the skin. The dark tint of the face is racial, not congestive.

strangulation, but is due to displacement of blood laterally from under the zone of maximum pressure.

The position of the hanging mark

The hanging mark is situated higher on the neck than in strangulation, usually being directly under the chin anteriorly, passing round beneath the jawbones and rising up at the sides or back of the neck to the usual gap under the knot (Figs 15.37–15.42).

An exception may be seen where the suspension point is low and part of the body is supported. For example, the victim may sit or slump on a chair, bed or floor with the rope attached to a point only slightly above neck level. Then the pull on the rope is almost at right angles



Figure 15.37 A perfectly horizontal mark around the neck in a male who hanged himself from a staircase. A slip-knot was used, which tightened so that the usual rising line of a hanging mark did not occur, illustrating the dangers of assuming that the usual is invariable.



Figure 15.38 A hanging mark showing the plaited imprint of a six-strand cable. There is a central line of abrasion, within a zone of pallor caused by vascular compression, outside of which is a narrow band of hyperaemia.



Figure 15.39 The position of the hanging mark on the neck. (a) Usual position with fixed noose and high suspension point. The mark rises high to a gap; (b) if a slip-knot is used, the tightness of the deeply impressed loop tends to find the smallest circumference on the neck, and may be lower and more horizontal; (c) if the suspension point is low and the subject leans away, the mark can be horizontal.



Figure 15.40 Hanging by frontal suspension. A leather noose has been used so that compression has occurred round the whole periphery of the neck. The imprint of the metal ring on the jaw is well seen.



Figure 15.41 Suicidal hanging with the rope in a frontal position. Even though the larynx cannot be compressed, death is due to pressure on the carotid arteries and sinuses. The face is pale, with no so-called 'asphyxial' signs.



Figure 15.42 The back of the victim in Fig. 15.41 showing tying of the wrists. This does not indicate a homicide, unless the ligature could not have been self-applied. Some persons bent on self-destruction will try to ensure that they do not attempt to rescue themselves. A suicide note was left in this case.

to the axis of the body when the latter slumps away, so that the resulting mark may be almost horizontal and set at a lower level than usual on the neck. In such cases, if the body is cut down before investigators arrive, it may be much more difficult to distinguish hanging from strangulation, a fact which has been argued in more than one criminal trial or controversial death, such as that of Rudolf Hess in Spandau Prison, Berlin in 1987.

On rare occasions, hanging will take place with the suspension point at or above the point of the chin with the rope cutting into the back of the neck. Where the rope passes across the jaw margins to a knot in front of the face, the mechanism of death is somewhat obscure as the laryngeal region suffers little or no compression. Fatalities, however, certainly do occur, presumably as there is still opportunity for pressure on the carotids.

Autopsy appearances in hanging

Apart from the appearances of the hanging mark, there are some other features to note. First, post-mortem hypostasis will occur in the legs and hands if the body has been in the vertical position for at least a few hours. When the body is cut down and laid horizontal for a considerable time, some or all of this appearance may flow back into the usual pattern.

Petechial haemorrhages are the exception rather than the rule, most series reporting them in approximately 25 per cent of cases. Such petechiae appear to occur more frequently in incomplete suspension but are frequently present in the absence of significant congestion. Congestion itself is far less usual than a pale face.

In the neck tissues there may be surprisingly little to find with an absence of laryngeal fracture or strap muscle haemorrhage being a common finding, especially if a soft ligature has been used. However, the literature suggests that an average figure for the incidence of soft tissue haemorrhage would be about 20–30 per cent of cases and for laryngeal fractures approximately 35–45 per cent of cases. Fractures of both the hyoid and thyroid may be seen.

According to Simon, Amussat was the first to observe damage to the intima and media of the carotid artery when performing an autopsy in a case of hanging.[37] Damage to the intima of the carotid arteries, often in the region of the sinuses, may sometimes be found on careful dissection. In hangings with an unusually long drop, severe disruption of the larynx can be found.

Another Simon described a finding, which can frequently be observed in cases of hanging, particularly in lower thoracic and lumbar spine, and if the body is completely suspended: streaky haemorrhages on the anterior aspects of the intervertebral disks ('Simon's haemorrhages'; 'Simon's sign'; 'Simon's symptom').[61] The latter Simon considered this to be a vital sign of hanging but they have been shown to occur also in the course of traumatic overextension of the spinal column, e.g. in traffic accidents or as a post-mortem artefact in decomposed bodies.[62,63]

Mechanism of hanging

There are a number of mechanisms by which hanging may cause death, which may act independently or in concert. These include: stretching of the carotid sinus causing reflex cardiac arrest; occlusion of the carotid (and possibly vertebral) arteries; venous occlusion; airway obstruction resulting from pushing the base of the tongue against the roof of the pharynx or from crushing of the larynx or trachea; and finally spinal cord–brainstem disruption.



Figure 15.43 Complete decapitation of a suicide who jumped from 8th floor balcony with the noose around his neck and fell two floors before the rope was tightened and decapitated him. An abraded area corresponding to a hanging mark can be seen in the marginal zone where the skin was severed. (Reproduced by kind permission of Dr. S. Toivonen.)

While hanging shares some features with manual strangulation, the majority of victims of hanging are seen with pale faces rather than the congested, haemorrhagic appearance associated with the slower death resulting from pressure on the neck. This probably reflects a different mechanism, with reflex cardiac arrest and carotid occlusion more prevalent in hanging than in strangulation. Such mechanisms cause death rapidly, with unconsciousness resulting from bilateral carotid occlusion 3–11 seconds after the application of circumferential pressure.

However, the precise interplay of different mechanisms, which themselves appear only partially dependent on the completeness of suspension and the location of the noose, is impossible to determine from the pathological findings alone.

Accidental and homicidal hanging

Though most hangings are suicidal, accidental hangings occur from two main causes. The first is entanglement in ropes or cords; this is relatively uncommon, and is usually seen in infants and children. The straps of a baby harness, used to support or restrain an infant, have led to death on a number of occasions, the child becoming entangled in leather or plastic reins when no adult was present. Any other cords may present a similar hazard, as in several cases seen by the author (BK), where infants standing in a cot near the bedroom window became entangled in a noose formed by the control cords hanging from a nearby blind or curtain.

On rare occasions, similar tragedies have befallen adults in factories, farms or ships, where a trip or fall has precipitated the victim head-first into machinery or structures, where ropes or cords have caused hanging or strangulation.

More commonly, a totally different situation causes fatal hanging or strangulation, almost exclusively in males and most often in young males, which is described in the next section.

Homicidal hanging is very rare, outside abuse of human rights and 'lynching'.[64–69] For one individual to hang another, there must be either a disparity in their size and strength – or the victim must be drugged, drunk or otherwise incapacitated by fear, illness or senility. For a conscious, presumably unwilling, victim to be hanged by another, there will inevitably be signs of resistance, such as grip bruises on the arms due to restraint, or signs of binding the arms, wrists or legs.

The sexual asphyxias: autoerotic or masochistic practices

Though not all of this group are hangings or strangulations, this well-recognized phenomenon is conveniently considered here. The sexual asphyxias occur much more frequently in males than in females but there are several reports of the latter indulging in this dangerous habit.[70–77] Byard *et al*. have been able to contrast the death scenes in the two sexes, indicating that males tend to use more apparatus, while females are usually found naked with only a ligature in evidence (Fig. 15.44).[72]

The age of the male victims can vary widely, but is most often seen in young to middle-aged adults. The deaths that occur are obviously a small proportion of the total incidence of this strange practice. A fatal outcome is usually because of some failure of the equipment and this emphasizes the accidental nature of most of these deaths.



Figure 15.44 Hanging in circumstances, which suggest a sexual–masochistic motive. The young male showed no signs of previous depression or suicidal tendency. He was found naked, with arms and legs tied together with wire. Though homicide was suspected at first, the bonds were loose and easily self-applied. No satisfactory explanation was forthcoming.

Features of the sexual asphyxias

The basic mechanism of the sexual asphyxias is the production of cerebral hypoxia, which in some males appears to produce hallucinations of an erotic nature.

This hypoxia is most often achieved by constriction of the neck by a ligature, which can be voluntarily tightened to produce vascular obstruction and perhaps airway stenosis. It would seem reasonable to think that vascular obstruction, either by blocking venous return – or even carotid flow – to the brain was the most likely explanation, as this would occur early. The production of cerebral hypoxia by anoxaemic anoxia through airway narrowing would surely be painful, distressing and slow in onset – hardly features which persons intent on self-gratification would welcome.

Some autoerotic procedures use other means of hypoxia, such as anaesthetic agents and a variety of volatile substances, tapering into 'solvent abuse', discussed in Chapter 34. Whatever the mechanism, when cerebral hypoxia occurs with its attendant erotic sensations, progressive loss of voluntary control as consciousness fades allows the constrictive device to slacken, so that the subject recovers. As some fatal cases show clear evidence of repeated previous escapades, it is obvious that the mechanism usually functions quite successfully and that death was the result of some unforeseen complication (Figs 15.46, 15.48).



Figure 15.45 A hanging in which it was not clear if there was a true sexual–masochistic element. The victim was suspended by electric cable from an attic trapdoor with his face plastered with surgical tape and the wrists tied together. Homicide could be excluded. In some deaths with an undoubted sexual element, the means used would inevitably lead to a fatal outcome, so there seems to be an overlap between masochism and suicide.



Figure 15.46 Fatal sexual asphyxia in an engineer with a rubber fetish. He was found dead connected to a dental anaesthetic machine, with a rubber face mask strapped on over a rubber teat in the mouth. Bizarre pornographic material devoted to dentistry was in the vicinity. (Figure reproduced by kind permission of Dr S. Leadbeatter.)



Figure 15.47 A presumed instance of sexual asphyxia. The deceased was naked and had enveloped himself in a large impervious bag, which he had made himself. It seems impossible for him to save himself once unconsciousness had occurred, but there seemed to be no suicidal tendencies in the history.

A common practice is to place a fixed noose around the neck, so that compression will cease as soon as muscular tension on the free end is relaxed. This free end may be passed down the front or back to be fastened to the ankles, so that by extending the legs, the noose around the neck is tightened. Compression may also be attained by passing the rope over a support and hanging a weight on the end to produce tension.

Other males may secure the end to an overhead support and achieve constriction by slumping against the pull of the rope. In these and similar cases, it is difficult to understand how death can be avoided once consciousness is lost, but evidence of repetition on previous occasions indicates that enough voluntary control must be retained to allow the person to retrieve the situation after obtaining his erotic satisfaction.



Figure 15.48 A classical sexual asphyxia where the deceased has used a dog collar round the neck (removed before photography), the chain passing down to the ankles, which provide temporary traction. The common features of rubber fetishism and penile bondage were present.

Similar hypoxia may be produced by placing the head in a plastic bag, by pushing the head into a confined space, by postural contortions (often associated with bondage) that constrict the airway, or a host of other ingenious methods. One case seen by the author (BK) deliberately constructed a large sack made from impervious material, into which he crawled to attain his hypoxia (Fig. 15.47). Certain features of these deaths make them fairly easy to differentiate from suicides, a distinction which is important, though some cases are impossible to separate from deliberate attempts at self-destruction (Fig. 15.45).[78]

Bondage is common, with sometimes elaborate and bizarre methods of restriction.[79] The wrists and ankles may be tied together with cord, wire, chains, padlocks or handcuffs, for example, and it is vital for the investigators to ensure that such bondage could have been secured by the deceased himself to exclude the possibility of homicide, usually by a heterosexual or homosexual partner involved in the ritual.

The bonds may be sexually orientated, with straps around the crutch or constricting the genital organs. In cases seen by the author (BK), one had made a metal sheath for the penis that was padlocked in place and another clamped the penis within a metal shackle (Fig. 15.49).

Masks and gags may be in place, again a manifestation of restraint. The mouth may be sealed by adhesive plaster and the eyes blindfolded. Rubber or leather often features in the masks, which may have eye-slits or completely envelope the face. Transvestism is common, female attire being worn either overtly or under male clothing. False breasts and nipples may be fabricated or brassières padded with cloth. This is a common phenomenon, however, without sexual asphyxia, as any coroner's autopsy service will reveal some males (often elderly) as hidden transvestites, wearing female underclothing beneath their suits. Fetishism is often seen, especially rubber or shiny plastic or leather. Female wigs and make-up are sometimes encountered, though the syndrome does not seem to be overtly associated with homosexual activity.

Pornographic literature is often within view and may be spread around the body at the scene of death. The act is sometimes performed before a mirror and masturbation is common. The mere emission of semen found at autopsy does not confirm sexual activity in itself, however, as post-mortem discharge of semen from the meatus is common in any type of death, not only in asphyxia (as used to be commonly alleged by standard textbooks). Occasionally, lewd writings are left near the body and even upon the body surface. The author (BK) has seen one where obscene graffiti were written with a ball-pen on the abdomen and around the glans penis.



Figure 15.49 A sexual asphyxia from a buckled belt applied tightly to the neck and a metal shackle on the penis. Obscene phrases were written on the glans and abdomen.

Perhaps more importantly, overt suicide notes are never present, helping to distinguish the cases from definite self-destruction. Another important piece of evidence against suicide is the fact that, in some neck ligatures, the rope may be padded by fabric to avoid leaving a telltale mark on the neck – an act incompatible with an intention of suicide.

Rarely, autoerotic gratification may be achieved by the application of electric current, usually low voltage applied to the genitals. Electrical faults, such as in a transformer, may lead to a fatal outcome.

Medico-legal aspects of the sexual asphyxias

Though all these features make the true nature of the death clear to the medical examiner, it can sometimes be difficult to convince the police, the coroner or judge – and especially the relatives – that death was accidental. The stigma still attached to suicide and the revulsion felt at the perverted sexual element may cause the relatives to prefer homicide as the cause. The judicial authorities often lean towards suicide, especially when they are unaware of the existence of this strange syndrome of the masochistic or sexual asphyxias. The doctor is often the only person able to explain the relatively common occurrence of this phenomenon and assist in reaching the correct conclusion. It has to be admitted, however, that in a small minority of these deaths, it seems inevitable that the victim must have been aware of the fatal outcome, as the mechanics of the asphyxia are such that no escape could have been foreseen. In these instances the circumstances are such that a mixed motivation must have existed. For example, hanging by the neck in free suspension from a tree or from the trapdoor of an attic is a situation from which escape is impossible, even though sexual attributes such as nudity, bondage and masking were present.[78]

Where the victim is young, motivation is again less clear. Youths of 12 or 14 years are sometimes found hanged, usually without the secondary sexual or bizarre attributes listed above. There is usually nothing in the history to suggest suicide, and quite often the coroner or other legal authority will decide that death was due to 'experimenting with ropes', sometimes alleging that it followed watching lynching in cowboy films on television. It is probable that most of the obscure deaths are also associated with aberrant sexual activity, even if more positive evidence is lacking. Recognition of the true nature of most of these deaths is vital for the medical examiner, as spurious homicide investigations may be initiated if they are misinterpreted. More commonly a false suicide verdict may result, which can have financial implications in respect of life insurance. A mistaken belief in suicide may be preferred by some families, however, rather than the shame of a publicised sexual aberration.

References

1 Clément R, Redpath M, Sauvageau A. Mechanism of death in hanging: a historical review of the evolution of pathophysiological hypotheses. *J Forensic Sci* 2010;55(5):1268–71.
2 Hofmann E. *Lehrbuch der Gerichtlichen Medicin*, 2nd edn. Wien: Urban & Schwarzenberg, 1881.
3 Brouardel P. *La Pendaison, la Strangulation, la Suffocation, la Submersion*. Paris: Ballière, 1897.
4 Reuter F. *Lehrbuch der Gerichtlichen Medizin*. Berlin: Urban & Schwarzenberg, 1933.
5 Schwarzacher W. Beiträge zum mechanismus des erhängungstodes. *Dtsch Z Gesamte Gerichtl Med* 1928; 11(1):145–53.
6 Siebke H, *et al*. Survival after 40 minutes; submersion without cerebral sequeae. *Lancet* 1975;1(7919):1275–7.
7 Shoja MM, *et al*. Vasovagal syncope in the Canon of Avicenna: the first mention of carotid artery hypersensitivity. *Int J Cardiol* 2009;**134**(3):297–301.
8 Parry CH. *An Inquiry into the Symptoms and Causes of the Syncope Anginosa, Commonly Called Angina Pectoris; Illustrated by Dissections*. Bath: R. Cruttwell, 1799.
9 Lewis T. A lecture on vasovagal syncope and the carotid sinus mechanism. *Br Med J* 1932;1(3723):873–6.
10 Schrag B, *et al*. Death caused by cardioinhibitory reflex: what experts believe. *Am J Forensic Med Pathol* 2012;33(1):9–12.
11 Anscombe AM, Knight BH. Case report. Delayed death after pressure on the neck: possible causal mechanisms and implications for mode of death in manual strangulation discussed. *Forensic Sci Int* 1996;78(3):193–7.
12 Simpson K. Deaths from vagal inhibition. *Lancet* 1949; 1(6553):558–60.
13 Lochte T. Über einen fall von tod durch erdrosseln und über die bedeutung des sinus caroticus. *Dtsch Z ges Gerichtl Med* 1930;**15**:419–32.
14 Giese E. Bemerkung zu der mitteilung von Prof. Lochte: Über einen fall von tod durch erdrosseln und über die bedeutung des sinus caroticus (Hering) in dies. Zeitschrift 15. Bd, 5. Heft. *Dtsch Z ges Gerichtl Med* 1930;15(1):572–4.
15 Schrag B. *et al*. Death caused by cardioinhibitory reflex cardiac arrest – a systematic review of cases. *Forensic Sci Int* 2011;207(1–3):77–83.
16 Hood I, Ryan D, Spitz WU. Resuscitation and petechiae. *Am J Forensic Med Pathol* 1988;9(1):35–7.
17 Raven KP, Reay DT, Harruff RC. Artifactual injuries of the larynx produced by resuscitative intubation. *Am J Forensic Med Pathol* 1999;20(1):31–6.
18 Maxeiner H, Winklhofer A. [Eyelid petechiae and conjunctival hemorrhage after cardiopulmonary resuscitation]. *Arch Kriminol* 1999;**204**(1–2):42–51.
19 Maxeiner H. Congestion bleedings of the face and cardiopulmonary resuscitation – an attempt to evaluate their relationship. *Forensic Sci Int* 2001;117(3):191–8.
20 Maxeiner H, Jekat R. Resuscitation and conjunctival petechial hemorrhages. *J Forensic Leg Med* 2010;17(2):87–91.
21 Weedn VW, Mansour AM, Nichols MM. Retinal hemorrhage in an infant after cardiopulmonary resuscitation. *Am J Forensic Med Pathol* 1990;11(1):79–82.
22 Gilliland MG, Luckenbach MW. Are retinal hemorrhages found after resuscitation attempts? A study of the eyes of 169 children. *Am J Forensic Med Pathol* 1993;14(3):187–92.
23 Gilliland MG, Luckenbach MW, Chenier TC. Systemic and ocular findings in 169 prospectively studied child deaths: retinal hemorrhages usually mean child abuse. *Forensic Sci Int* 1994;68(2):117–32.
24 Polson CJ, Gee DJ, Knight B. *The Essentials of Forensic Medicine*, 4th edn. Oxford: Pergamon Press, 1985.
25 Rogde S, Hougen HP, Poulsen K. Asphyxial homicide in two Scandinavian capitals. *Am J Forensic Med Pathol* 2001;22(2):128–33.
26 Shapiro HA, Gluckman J, Gordon I. The significance of finger nail abrasions of the skin. *J Forensic Med* 1962;9:17–19.
27 Matte M, *et al*. Prevalence and persistence of foreign DNA beneath fingernails. *Forensic Sci Int Genet* 2012;6(2):236–43.
28 Aghayev E, *et al*. Virtopsy hemorrhage of the posterior cricoarytenoid muscle by blunt force to the neck in postmortem multislice computed tomography and magnetic resonance imaging. *Am J Forensic Med Pathol* 2006;27(1):25–9.
29 Oesterhelweg L, *et al*. Virtopsy: postmortem imaging of laryngeal foreign bodies. *Arch Pathol Lab Med* 2009;133(5):806–10.
30 Prinsloo I, Gordon I. Post-mortem dissection artefacts of the neck and their differentiation from ante-mortem bruises. *South African Med J* 1951;25:358–61.
31 Shapiro H. Asphyxia. In: Gordon I, Shapiro H, Berson S (eds). *Forensic Medicine: A Guide to Principles*. Edinburgh: Churchill, 1988.
32 Simpson CK. *Forensic Medicine*, 9th edn. London: Arnold, 1985.
33 Evans KT, Knight B. *Forensic Radiology,* 1st edn. Oxford: Blackwell Scientific Publications, 1981.
34 Bux R, *et al*. Laryngohyoid fractures after agonal falls: not always a certain sign of strangulation. *Forensic Sci Int* 2006; 156(2–3):219–22.
35 Green MA. Morbid anatomical findings in strangulation. *Forensic Sci* 1973;2(3):317–23.
36 Amussat JZ. *Recherches Experimentales sur les Blessures des Artères et des Veines. Résumé des Trois Memoires lus à l'Academie Royale des Sciences*. Paris: P. Dupont et Co, 1843.
37 Simon G. Ueber die zerreissung der inneren häute der halsarterien bei gehängten. *Virchows Arch* 1857;11(4):297–324.
38 Rupp JC. Suicidal garrotting and manual self-strangulation. *J Forensic Sci* 1970;15(1):71–7.
39 Gonzalez TA. Fractures of the larynx. *Arch Pathol* 1933;15:55–62.
40 Clark MA, *et al*. Asphyxial deaths due to hanging in children. *J Forensic Sci* 1993;38(2):344–52.
41 Sabo RA, *et al*. Strangulation injuries in children. Part 1. Clinical analysis. *J Trauma* 1996;40(1):68–72.
42 Dogan KH, *et al*. Accidental hanging deaths in children in Konya, Turkey between 1998 and 2007. *J Forensic Sci* 2010; 55(3):637–41.
43 Deidiker RD. Accidental ligature strangulation due to a roller-type massage device. *Am J Forensic Med Pathol* 1999; 20(4):354–6.
44 Shetty M, Shetty BS. Accidental ligature strangulation due to electric grinder. *J Clin Forensic Med* 2006;13(3):148–50.

45 Ambade VN, *et al.* Accidental ligature strangulation due to crop thrasher. *J Forensic Leg Med* 2008;**15**(4):263–5.

46 Dogan KH, *et al.* Accidental ligature strangulation by an ironing machine: an unusual case. *J Forensic Sci* 2010;55(1):251–3.

47 James R, Nasmyth-Jones R. The occurrence of cervical fractures in victims of judicial hanging. *Forensic Sci Int* 1992; 54(1):81–91.

48 Reay DT, Cohen W, Ames S. Injuries produced by judicial hanging. A case report. *Am J Forensic Med Pathol* 1994;15(3): 183–6.

49 Hartshorne NK, Reay DT. Judicial hanging. *Am J Forensic Med Pathol* 1995;16(1):87.

50 Spence MW, *et al.* Craniocervical injuries in judicial hangings: an anthropologic analysis of six cases. *Am J Forensic Med Pathol* 1999;20(4):309–22.

51 Hellier C, Connolly R. Cause of death in judicial hanging: a review and case study. *Med Sci Law* 2009;49(1):18–26.

52 Bowen DA. Hanging – a review. *Forensic Sci Int* 1982;20(3):247–9.

53 Bohnert M, Pollak S. [Complex suicides—a review of the literature]. *Arch Kriminol* 2004;213(5–6):138–53.

54 Sauvageau A, *et al.* Six-year retrospective study of suicidal hangings: determination of the pattern of limb lesions induced by body responses to asphyxia by hanging. *J Forensic Sci* 2009; 54(5):1089–92.

55 James R, Silcocks P. Suicidal hanging in Cardiff – a 15-year retrospective study. *Forensic Sci Int* 1992;56(2):167–75.

56 Kanchan T, Menon A, Menezes RG. Methods of choice in completed suicides: gender differences and review of literature. *J Forensic Sci* 2009;54(4):938–42.

57 Marcus P, Alcabes P. Characteristics of suicides by inmates in an urban jail. *Hosp Community Psychiatry* 1993;44(3):256–61.

58 Southall P, *et al.* Police custody deaths in Maryland, USA: an examination of 45 cases. *J Forensic Leg Med* 2008; 15(4):227–30.

59 Rothschild MA, Schneider V. Decapitation as a result of suicidal hanging. *Forensic Sci Int* 1999;106(1):55–62.

60 Racette S, Vo TT, Sauvageau A. Suicidal decapitation using a tractor loader: a case report and review of the literature. *J Forensic Sci* 2007;52(1):192–4.

61 Simon A. Vitale Reaktionen im bereich der lendenwirbelsäule beim erhängen. *Wiss Z Univ Halle* 1968;XVII:591–7.

62 Geserick G, Krocker K, Schmeling A. [Simon's bleedings as a vital sign of hanging – a literature review]. *Arch Kriminol* 2012;229(5–6):163–78.

63 Zivkovic V, Nikolic S. An uncommon finding of subtle Simon's bleedings in a fatally injured skydiver. *Forensic Sci Med Pathol* 2013;9(3):437–40.

64 Wright RK, Davis J. Homicidal hanging masquerading as sexual asphyxia. *J Forensic Sci* 1976;21(2):387–9.

65 Lew EO. Homicidal hanging in a dyadic death. *Am J Forensic Med Pathol* 1988;9(4):283–6.

66 Vieira DN, Pinto AE, Sa FO. Homicidal hanging. *Am J Forensic Med Pathol* 1988;9(4):287–9.

67 Leth P, Vesterby A. Homicidal hanging masquerading as suicide. *Forensic Sci Int* 1997;85(1):65–71.

68 Mallach HJ, Pollak S. [Simulated suicide by hanging after homicidal strangulation]. *Arch Kriminol* 1998;202(1–2):17–28.

69 Sauvageau A. True and simulated homicidal hangings: a six-year retrospective study. *Med Sci Law* 2009;49(4):283–90.

70 Danto BL. A case of female autoerotic death. *Am J Forensic Med Pathol* 1980;1(2):117–21.

71 Byard RW, Bramwell NH. Autoerotic death in females. An underdiagnosed syndrome? *Am J Forensic Med Pathol* 1988;9(3):252–4.

72 Byard RW, Hucker SJ, Hazelwood RR. A comparison of typical death scene features in cases of fatal male and autoerotic asphyxia with a review of the literature. *Forensic Sci Int* 1990;48(2):113–21.

73 Marc B, Chadly A, Durigon M. Fatal air embolism during female autoerotic practice. *Int J Legal Med* 1990;104(1): 59–61.

74 Byard RW, Hucker SJ, Hazelwood RR. Fatal and near-fatal autoerotic asphyxial episodes in women. Characteristic features based on a review of nine cases. *Am J Forensic Med Pathol* 1993;14(1):70–3.

75 Gosink PD, Jumbelic MI. Autoerotic asphyxiation in a female. *Am J Forensic Med Pathol* 2000;21(2):114–8.

76 Behrendt N, Buhl N, Seidl S. The lethal paraphiliac syndrome: accidental autoerotic deaths in four women and a review of the literature. *Int J Legal Med* 2002;116(3):148–52.

77 Sauvageau A, Racette S. Female autoerotic deaths – still often overlooked: a case report. *Med Sci Law* 2006;46(4):357–9.

78 Knight B. Fatal masochism – accident or suicide? *Med Sci Law* 1979;19(2):118–20.

79 Blanchard R, Hucker SJ. Age, transvestism, bondage, and concurrent paraphilic activities in 117 fatal cases of autoerotic asphyxia. *Br J Psychiatry* 1991;159:371–7.

This page intentionally left blank

CHAPTER 16

Immersion Deaths

- Introduction
- Signs of immersion
- Estimation of duration of immersion
- Death from natural causes before entering the water
- Natural death while in the water
- Injuries sustained before entering the water
- Injuries sustained in the water
- Deaths from immersion other than drowning
- Death from drowning
- The autopsy signs of drowning
- Chemical changes in the blood in drowning
- Histological changes in drowning
- Diatoms and the diagnosis of drowning
- References

Introduction

Many corpses are recovered from water, but not all have drowned. Of those that have drowned, pathological proof is often difficult or even impossible to obtain (Figs 16.1–16.3). The autopsy diagnosis of drowning presents one of the major problems in forensic medicine, especially when there is delay in recovering the victim.

Bodies retrieved from water may have:

- died from natural disease before falling into the water
- died from natural disease while already in the water
- died from injury before being thrown into the water
- died from injury while in the water
- died from effects of immersion other than drowning
- died from drowning.

All the above may show signs of immersion on examination, but this is rarely helpful, other than confirming that they had indeed been in water. It does not assist in differentiating the mode of death.

Signs of immersion

- Maceration of the skin begins within minutes in warm water, such as death in a bathtub, but in cold water is visible after a variable time, depending upon temperature and the type of water (fresh or salt). However, the concepts vary according to the author to such an extent that it is difficult to give any reliable guideline that would be of much practical use.[1–6]

  The first signs tend to be on areas with an appreciable keratin layer (such as the fingertips, palms, backs of the hands and later the soles) where the surface becomes wrinkled, pale and sodden – the so-called 'washer-woman's skin', for obvious reasons (Figs 16.4, 16.5). Areas protected by clothing develop these changes later than exposed parts so that the hands usually reveal more marked maceration than the feet during the first few days.

  After prolonged immersion, wide areas of skin assume the same appearance, especially where the stratum corneum is thick or naturally creased, such as the extensor surface of knees and elbows. After some days in warmer water and up to several weeks in cold, the thick keratin of hands and feet becomes detached and eventually peels off in 'glove and stocking' fashion (Fig. 16.6). The nails and hair become loosened at about the same time. Problems of obtaining fingerprints in such circumstances are dealt with later.
- Cutis anserina – or 'goose-flesh' – is a common finding in immersed bodies, but is related to cold rather than warm water. The erector pilae muscles attached to each hair follicle can contract in any type of death and cause a generalized pimpling of the skin. From whatever cause, however, agonal contraction of the erector pilae is common and in immersed bodies has no diagnostic significance.



Figure 16.1 The diagnostic problems associated with bodies recovered from the water. In a death such as this, where a body is left by the falling tide, it may be difficult or even impossible to prove drowning, especially if the post-mortem period is long.



Figure 16.2 When a body is recovered from the sea wrapped in a sheet and tied up with a plastic rope like this, it is obvious that the probability of a homicidal death is very high. In this case, the perpetrator had smashed the skull of the victim with a baseball bat and tried to get rid of the body by dropping it to the sea from a bridge. A week later the body was found floating in the sea and recovered.

- The distribution of post-mortem hypostasis is also of no value in immersed bodies. According to Bonte *et al*., electrocution in the bath seems cause the margin of hypostasis to correspond with the horizontal line of the water level (see Chapter 12).[7] It is usual for most corpses to float or hang in the water with buttocks uppermost, and the head and limbs hanging down, but water movements often roll the body constantly unless in a placid lake or wide river. Other corpses



Figure 16.3 Tying of the legs in a body removed from the water is suspicious, but not absolute proof of foul play. Some suicides who are good swimmers, deliberately tie their legs to prevent instinctive self-preservation. In this illustration, however, the bonds were used to secure a heavy weight after homicide.



Figure 16.4 Waterlogged skin ('washer-woman's hands') after 2 weeks' immersion in a temperate climate. Fingerprints can still be obtained from hands like these, with appropriate techniques.



Figure 16.5 Waterlogged skin after 1 week's immersion in a cold climate.



Figure 16.6 Peeling of the epidermis in a 'stocking' fashion after a few weeks' immersion. The rate at which such changes occur is so variable, because of environmental factors that no timetable can be offered to attempt to date death. In a temperate-zone summer, this stage would require at least 2 weeks and probably much longer.

may float upon the back, and gravitational staining of the skin may therefore be in any pattern if the body is subject to frequent changes or posture. The hypostasis of bodies from cold water is frequently pink, but this has no diagnostic value. The reddish colour is caused by the presence of unreduced oxyhaemoglobin in the superficial blood vessels and is the result of cold, whether ante-mortem or post-mortem. It may be seen in any body taken from a mortuary refrigerator or found in a cold environment, irrespective of immersion. In immersion, however, it does not have the typical distribution over extensor surfaces and large joints, nor the rather dusky tinge that is seen in true ante-mortem hypothermia.

- Mud, coal-slurry, oil, silt or sand may be present on or in the body, as well as other artefacts such as seaweed, water weed, algae and small aquatic animal life of many types. Mud may be adherent to the whole body surface and clothing, or may be retained in the hair, mouth, nostrils, ears and other more protected sites. In appropriate circumstances, such deposits should be retained for scientific examination, if they might help establish where the body has travelled from in marine or riverine waters. Sand may be found deep in the respiratory passages and stomach, especially if the body has been rolled by the waves on a beach (Fig. 16.10). Such deep penetration is not evidence of live aspiration. Where a body is decomposed and partly skeletalized, molluscs may colonize the bones. The author (BK) has had several cases recovered from the sea where mussels and barnacles filled the eye sockets and other crevices of the skull.

Estimation of duration of immersion

This is another difficult problem and one that is often too dogmatically answered by doctors with insufficient experience to appreciate the potential errors. The overriding variable factor is water temperature, which has the most effect upon decomposition. Water pollution has little to do with speed of putrefaction, as most of the decomposing organisms come from the gut of the body itself.

When a body falls into water in average temperate climates, the following is an approximate guide to timing, in conjunction with the other usual signs, such as rigor:

- if no wrinkling of the finger-pads is present, less than a few hours
- wrinkled fingers, palms and feet, progressively from half a day to 3 days
- early decomposition, often first in the dependent head and neck, abdomen and thighs: 4–10 days
- bloating of face and abdomen with marbling of veins and peeling of epidermis on hands and feet, and slippage of scalp: 2–4 weeks
- gross skin shedding, muscle loss with skeletal exposure, partial liquefaction: 1–2 months.

These times may be reduced or exceeded by wide margins according to animal predation, climatic changes and bodily build.

Death from natural causes before entering the water

This is relatively uncommon, but does occur. The victim may suffer one of the many causes of sudden natural death, most commonly a cardiovascular catastrophe, in circumstances where he involuntarily falls into the water. The last such instance dealt with by the author (BK) was a man returning to his yacht in a rubber dinghy, alone and in the dark. The dinghy was found empty and a search recovered the body, autopsy revealing a well-established myocardial infarct with no evidence of drowning, though the latter is never conclusive. Other instances have involved persons collapsing from natural disease while on boats, a canal tow-path or a river bank.

Of course, in the absence of witnesses it is difficult to separate such cases from those who first fall into the water and then suffer a natural death. The autopsy must be directed towards identifying the pathological lesions and to excluding, as far as is possible, any evidence of drowning.

Natural death while in the water

As discussed above, it may well be impossible to determine whether a person recovered from the water, with a potentially fatal natural disease, suffered this before or after immersion. Because of the problems (to be described later) of positively diagnosing drowning, it is difficult to exclude this as either the primary or contributory cause in someone with a lethal disease.

Cardiovascular disease is the most common reason for death in the water. A pre-existing condition may be exacerbated either by the physical exertion of swimming or struggling, or by the effects of cold. The common belief that swimming after a heavy meal is dangerous probably has some basis in fact, because of circulatory changes such as the 'splanchnic shunt'. When an acute cardiac episode occurs, such as sudden myocardial insufficiency or an arrhythmia, death may follow either from the cardiac lesion itself, or from drowning because of sudden physical incapacity.

Injuries sustained before entering the water

The disposal of a murdered corpse in water is by no means uncommon, as it provides a convenient means of concealing the body, of transporting it from the scene of the crime by means of currents in river or sea, and – if discovery is delayed – of preventing identity by post-mortem decay and damage. Occasionally, accidental or suicidal injuries may be inflicted on a person before he or she enters the water. In marine, air or (rarely) road transport accidents, the victims may be injured or killed before entering the water. Persons falling from docks, bridges or ships may strike masonry or solid obstructions before hitting the water. Suicides may suffer in the same way or in exceptional circumstances, may stab themselves or cut their throats in a position where they fall into water immediately afterwards.

Whatever the means, the difficulties for the pathologist are the same, in that he must try to differentiate them from injuries sustained in the water before death occurs – and from post-mortem injuries. Often this is an impossible task, as such injuries are sustained perimortally, so that the time span involved is far too short for any of the usual criteria of ante-mortem infliction to be applied.

When the nature of the injuries is such that they could not have occurred in water, the issue is clear. Burns, missile wounds, the effect of explosions (other than compression injury) and patterned injuries may be incompatible with infliction in water, and must therefore be related to the effects of a previous assault or some accident on board ship or aircraft.

Injuries sustained in the water

As stated, this category is often impossible to differentiate from injuries inflicted before entering the water. Trauma in the water is common, as both an ante-mortem and a post-mortem phenomenon. Before drowning or another mode of death can supervene, the victim may be washed by waves or current against any kind of obstruction, from bridge pier to wharf, from rocks to weirs. Contact with the rough bottom of a river or a stony beach is another common cause of trauma. Damage from boats, ship's propellers, and marine or animal predators is frequent (Fig. 16.8).

The issue usually becomes one of attempting to distinguish injuries sustained during life from those after death. Water complicates the problem by washing away surface bleeding from open injuries. A laceration inflicted during life will, however, usually show some bleeding into the tissues under the margins of the wound, at least until post-mortem decomposition blurs the appearances. Many decomposed bodies from water reveal green or black areas under the skin, especially in the scalp. It can be difficult or impossible to decide whether these are areas of altered blood, or merely autolytic changes. Even histological examination is often unhelpful in this respect. A similar problem exists with bruises in a decomposed body, which are often mimicked by discoloured areas of putrefaction. Post-mortem damage from animal predators is common in water and is discussed in the chapter on post-mortem changes.

In cold climates, if a body enters the cold water in late autumn, the gas formation due to putrefaction may be so slow that the sea, lake or river will be covered with ice before the body surfaces and this takes place first in the spring when the ice is melting. In rivers, additional injuries may occur if the body gets pinned down between moving ice blocks (Fig. 16.7).

Internally, there is no particular problem distinct from the examination of injured bodies in general, until post-mortem decomposition begins to obscure the appearances. This is more common in immersed bodies because of the frequent prolonged delays before the body is discovered. Bodies that have been suspended in shallow water may bear post-mortem damage from being dragged against the bottom. A common posture is with the head, hands and knees hanging downwards, so that these areas (especially the backs of the hands)



Figure 16.7 Decomposed head and fractured skull of a person, who disappeared in the autumn before the river was covered with ice. The injuries have possibly been caused post-mortem by the ice packs when the body surfaced in the spring.



Figure 16.9 Post-mortem injury to the back of the hand in a drowned person. Bodies usually hang suspended in the water with the back upwards and the knees, head and arms hanging down. In shallow water these areas may be dragged against the bottom, causing injuries similar to those shown here.



Figure 16.8 Marine predator injuries on a body from the sea. The circular defects in the skin are probably made by crustaceans such as crabs.



Figure 16.10 The bifurcation of the trachea and main bronchi at autopsy on a body recovered from a beach. The air-passages are full of sand, but this is not proof of vital aspiration of water, as foreign material can enter the bronchi by passive percolation after death.

may suffer extensive abrasions against a rough stone or gravel bottom (Fig. 16.9).

Damage from the propellers of ships and smaller boats is common in commercial waterways and where pleasure craft abound. The screw of a large vessel may inflict serious damage – even dismemberment – on a body, but more characteristic is that caused by a small, high-speed propeller, such as an outboard motor or the out-drive of a motor cruiser. These injuries are becoming more common with the increase in water-skiing, and the number of other small pleasure boats on rivers, lakes and off beaches. The characteristic lesions are parallel wounds set a few centimetres apart, often of a sliced, undercut incised nature, usually on the head or back.[8]

Deaths from immersion other than drowning

Irrespective of natural disease or injury, some persons who die after falling into water do not drown, in the accepted physiological sense. The great problem for the pathologist is that, even in true drowning, there may be no autopsy signs, especially if any appreciable delay has occurred before recovery or autopsy, or both. Therefore it may be difficult or impossible for him to say whether a death is a true drowning or one from the non-drowning mechanisms. All that can then be offered is that death was due to 'immersion' – and even then such a diagnosis is usually one reached by exclusion of natural disease, trauma or toxic conditions, using hearsay circumstantial evidence to arrive at a pathological diagnosis. This is why drowning and immersion deaths present one of the most difficult problems for the forensic practitioner.

In certain circumstances, death may be extremely rapid after falling into water, there being insufficient time for drowning to occur. The typical occasion is familiar to any forensic pathologist with a harbour or dockside within his area. A seaman (often the worse for drink) returns to his ship at night, misses the gangway and falls into the water. The night-watchman immediately raises the alarm and the victim is pulled from the water within a minute or two, but is dead. At autopsy, none of the typical signs of drowning are present.

Other witnessed accidents of a similar nature are relatively common, in which rapid, almost instantaneous death must be presumed, in circumstances where true drowning can be excluded by history and lack of autopsy findings. The mechanism must be attributed to a reflex cardiac arrest, of a type similar to 'vasovagal inhibition', which is discussed elsewhere. Powerful stimulation of sensitive nerve endings can induce sudden overactivity of the parasympathetic system, inducing bradycardia and triggering cardiac arrest via the tenth cranial nerve nucleus and its vagal outflow. The afferent arc of this reflex varies from case to case, but is probably either:

- sudden immersion in cold water, causing intense stimulation of cutaneous nerve endings. Alcohol is known to potentiate such effects, perhaps by the general vasodilation of skin vessels – which would make the contrast with cold water all the more severe – and possibly by some central effects on the vasomotor centre;
- sudden entry of cold water into the pharynx and larynx, and perhaps nasal passages can produce powerful stimulation of nerve endings in the mucosa.[9] A bolus of water entering the trachea can also cause reflex cardiac arrest before there is time for airway insufficiency to have any effect.

Bühring and Spies measured increased catecholamine plasma levels in 20 healthy males after exposure to cold water baths of 15°C, which may lead to cardiac arrhythmias and increase the risk of sudden death.[10] Ishikawa *et al.* tested 64 children with various arrhythmias using five methods: diving, swimming, face immersion in 25°C water, face immersion in 6°C water. Significant arrhythmias occurred during diving or swimming in 51 children, with 44 developing arrhythmias while diving. Both tachyarrhythmias and bradyarrhythmias were seen during diving, but 17 children who also showed significant arrhythmias while swimming mostly had tachyarrhythmias. A comparison with the incidence of arrhythmias produced by diving showed that face immersion in cold water had a sensitivity of 88.6 per cent, a specificity of 85.0 per cent, a predictive value of 92.9 per cent, and an accuracy of 87.5 per cent.[11] Datta and Tipton reviewed the ventilatory responses to immersion and proposed that immersion into cold water results in three distinct patterns of response: 1) face-only stimulation by water, even when cold, leads to a diving-reflex mediated bradycardia; 2) anticipation, anxiety and cold cutaneous stimulation to a sympathetic overdrive and tachycardia; and 3) release of breath holding in cold water, produces supraventricular and junctional arrhythmias in 60 per cent of head-out immersions and around 80 per cent of submersions when the vagal tone is raised still further.[12]

As with any reflex cardiac arrest, there will be nothing to find at autopsy, a situation that forces this diagnosis to be speculative and based on the circumstances and exclusion of other conditions. Another mechanism that is often postulated as a cause of non-drowning immersion death is 'laryngeal spasm', leading to a hypoxic death from closure of the airway. The evidence for such a condition is tenuous, as such closure would have to operate for many minutes for hypoxia to kill, all the time keeping the larynx closed to prevent entry of water. Cyanosis is an uncommon feature of immersion deaths and in its absence it is difficult to see how laryngeal spasm could be differentiated from 'dry-lung drowning' or vasovagal cardiac arrest, the latter being a more reasonable diagnosis in those found dead after rapid recovery from the water.

Cardiac channel defects have been associated with swimming-triggered arrhythmia syndromes.[13,14] When signs of drowning at autopsy are absent genetic analysis can be applied to confirm or exclude the presence of gene-specific arrhythmogenic factors as potential cause of drowning.[15] Lunetta *et al.* retrospectively screened specific founder mutations in *KCNQ1* (KVLQT1) and *KCNH2* (HERG) genes in 165 consecutive bodies found in water in Finland and found one KCNH2-Fin mutation in a suicidal drowning, whereas Tester *et al.* reported that nearly 30 per cent of the 35 victims of swimming-related unexplained drowning hosted pathogenic mutations in genes associated with the long-QT syndrome and catecholaminergic polymorphic ventricular tachycardia.[16–18]

Deaths in the bathtub

Fatalities in the bathroom are common, from a variety of causes, some unconnected with immersion.[7,15,19–22] For example, Schmidt and Madea reported no fewer than 215 deaths in bathtubs from their Cologne Forensic Institute in 13 years, including 11 homicides.[23]

Many suicides take place in the bathroom, including slashing of the throat or wrists, in or out of the bath. The bathroom cabinet or cupboard commonly holds razors for cutting and medicinal poisons for overdose. Electricity is more likely to be fatal in wet surroundings and a number of self-killings from electricity occur in the bathroom. Accidents include falls on slippery, wet floors or bath lining, with hard ceramic surfaces to cause head injuries.

Where gas appliances are used to heat water, the risk of carbon monoxide toxicity from faulty equipment is greater, as is also the case with electrical appliances such as hair-dryers, heaters and other devices.[24,25] Although most countries have strict regulations about the electrical supply in bathrooms, people often defeat these safety measures by various means. Natural deaths from many causes may occur in the bathroom, but epileptics having unsupervised baths may have a fit and fall or drown.

Even homicide may be committed in bathrooms, by almost any means, but also from electricity and forcible immersion. The notorious multiple murders of ‘The Brides in the Bath’ perpetrated by George Joseph Smith in the early 20th century were probably accomplished by sudden pulling of the feet of the three women, so that their heads slid under the water.[26] There is now a considerable literature about death in the bathtub, and all deaths in these circumstances must be investigated with particular care (Figs 16.11, 16.12).



Figure 16.11 Death in the bath is not uncommon and always requires careful investigation. In this case, the dressed body of a female was found in the bath facing the bottom and covered with a sheet and bed spread (not shown), on top of which there was a large ice cube. There had been an altercation during which she had threatened her husband with a knife after which he had strangled her. In order to cool the body down the man had regularly filled the bath with cold water and ice cubes until the body was found 4 weeks later.



Figure 16.12 Suicide in the bath. The body is dressed in a bathing suit and an electrocution device (blow-dryer) was in the bath switched on. The victim had left a suicide note and on the chair there was an empty package of sleeping pills, illustrating the frequent presence of alternative methods in suicide.

Death from drowning

Medico-legal aspects of drowning have been dealt with in all important textbooks of forensic medicine since the *Hsi yüan chi lu* by Sung Tz’u.[27] The characteristics of the drowning process was studied in animal experiment in the 19th century, in particular by Falk and Bert.[28,29]

During the past five decades, views on the mechanism of drowning have undergone a radical change and perhaps the pendulum of opinion has swung a little too far. Until the research stimulated by the Second World War, when large numbers of seamen and airmen were exposed to the risks of cold water, the classic view of drowning was that the victim was plunged into an airless medium and died of lack of oxygen. Following the experiments of Swann and many others (see References), it was recognized that, in animals, fluid and electrolyte disturbances had a major role in causing acute myocardial failure. The hypoxic element was relegated to such a secondary role that some commentators on drowning seemed to ignore the fact that the victims may have suffered 10 or more minutes without drawing a single breath of air. This criticism by no means disputes the undoubted role of fluid and electrolyte changes in drowning, but the effects of hypoxia must be considered in parallel when discussing the pathophysiology of drowning. The biochemical findings in the experimental animals did not seem to be matched by constant changes in human subjects and, in delayed and near-drowning victims, the electrolyte changes in aspiration have been shown to differ considerably from those in experimental animals.

A number of investigators long before Swann showed that blood and plasma were radically affected by drowning. In 1902, Carrara used specific gravity and other methods to demonstrate marked dilution of left heart blood in freshwater drowning and its absence in seawater.[30] Freimuth in 1955, however, used such specific gravity methods and found similar differences in non-drowning deaths.[31]

The classical work of Swann and his colleagues and others was conducted on conscious dogs imprisoned in cages and immersed totally under water – which, as pointed out by Crosfill, does not accurately reflect human drowning, in which submersion is intermittent at first, prolonging the process and altering the physiological effects.[32–34] In summary, the findings of Swann were that in freshwater drowning there was a massive absorption of water through the alveolar membranes, which could amount to 70 per cent of the original blood volume within 3 minutes. This haemodilution caused a relative anaemia and myocardial hypoxia, as well as rapid overloading of the cardiac capacity by hypervolaemia. It was also suggested that haemolysis of red cells released potassium, a powerful myocardial toxin – yet in dogs, unlike man, sodium is the main electrolyte in the erythrocyte. In fact, because of the hypoxia and haemodilution, there was a fall in plasma potassium and sodium, which led to early ventricular fibrillation in dogs that did not occur in seawater. Such fibrillation is said to be rare in man.[35]

In seawater the hypertonic medium caused a withdrawal of water from the plasma into the lungs and a rise in plasma sodium concentration. This was less deleterious to heart function and helped to explain the longer survival time in seawater immersion.

Pulmonary oedema developed in both types of aqueous medium but was slight and inconstant and, where abnormal, rapidly returned to normal. Death in freshwater typically took some 4–5 minutes, whilst seawater drowning was delayed for 8–12 minutes.

Occasional instances have been reported of survival after remarkably long periods of total submersion in the sea, always in cold water where oxygen uptake is reduced: these periods may exceed 20 minutes, and there are already case histories of children and even adults who have survived being submersed in cold water for up to 66 minutes.[36–38]

Modern commentators on the researches of Swann, such as Giamonna and Modell, have pointed out the inconsistencies between animal and human responses, and emphasized the role of hypoxaemia as a result of interference with the blood–air interface in the alveoli.[39] This once again indicates the dangers of transposing the results of animal experiments to man and poses the question of how many dogs died in vain.

The autopsy signs of drowning

At autopsy much depends on the delay, both in recovering the body from the water and in starting the post-mortem examination. Where a considerable period has elapsed between death and retrieval of the body, the positive signs of drowning progressively fade. Depending on temperature, a period of several days in the water is likely to minimize most changes and, once significant putrefaction has occurred, then (apart from the controversial diatom tests) there is little hope of finding positive signs of drowning.

Even when a fresh body is recovered, delay in performing the autopsy reduces the amount of evidence. The author (BK) has seen several drowned bodies soon after retrieval in which a large plume of froth has been present at the mouth, yet when commencing the autopsy several hours later, such froth had vanished and was present only in the deeper air-passages.

Froth in the air passages

The positive signs of drowning, as opposed to mere immersion, are scanty and not absolutely specific. The most useful, has just been mentioned – the presence of frothy fluid in the air passages – which in fresh bodies, often exudes though the mouth and nostrils, sometimes in the form of a plume (Figs 16.13–16.15). The froth



Figure 16.13 A typical plume of froth from the mouth of a recently drowned boy. This will vanish as the post-mortem interval extends.



Figure 16.14 Froth exuding from the mouth of a drowned person. Froth disappears with increasing post-mortem interval, though it persists in the internal air-passages for a much longer time.



Figure 16.15 Red-tinged froth exuding from the nostrils of a drowned person.



Figure 16.16 Frothy fluid in the trachea and main bronchi of a person who was first strangled and subsequently fell or was thrown into sea and drowned.

is oedema fluid from the lungs, and consists of a proteinaceous exudate and surfactant mixed with the water of the drowning medium. It is usually white, but may be pink or red-tinged, because of slight admixture with blood from intrapulmonary bleeding. It is similar in appearance to the oedema of left ventricular failure that is commonly seen in deaths from cardiac disease such as hypertension (Fig. 16.17), though some drownings exhibit a column of froth that is rarely, if ever, seen in natural pulmonary oedema. The froth extends into the trachea, main bronchi and smaller air passages (Fig. 16.16). The lungs themselves in such cases will inevitably be waterlogged, and frothy fluid will exude from the bronchi when the lung is squeezed and from the cut surfaces when they are sectioned with a knife.

Unfortunately, although such oedema can be taken as diagnostic when combined with the appropriate circumstances and lack of other lethal pathology, the absence of waterlogging by no means excludes true drowning. The so-called ‘dry-lung drowning’ is not uncommon, in which the lungs appear normal in all respects, presumably because all the aspirated water has been absorbed through the alveolar walls into the plasma.

It has been suggested that this is more likely to occur if cardiac arrest takes place after removal from the water or if laryngeal spasm supervenes to prevent further water entry, so that continued circulatory function is able to clear away intra-alveolar fluid into the plasma. This theory, however, often fails to conform to the available facts of the drowning episode.



Figure 16.17 Not all froth around the mouth is from drowning. This female died in bed from hypertensive heart disease with profuse pulmonary oedema.

Copeland measured lung weight in non-drowning deaths and deaths from salt-water and freshwater drowning.[40] There was no significant difference in the weights of the last two, though 10–20 per cent of undoubted drownings were 'dry-lung' cases with no excess weight. Generally, the weights of a lung in drowning were around 600–700 g, while the non-drowned were in the 370–540 g range – though there was a considerable overlap in the two groups. The lung weights were also studied by Kringsholm *et al.* who claimed that the duration of submersion is related to lung weight.[41] They found that 7 per cent of cases were 'dry-lung drownings' with a combined lung weight of less than a kilogram. In the remainder, the average weight of both lungs was 1411 g, compared with 994 g in controls. This was where the body was in the water less than 24 hours. After this, lung weight decreased, but pleural transudate increased. By combining the weight of lungs and transudate, more than 75 per cent of the cases lay between 1000 and 2200 g, up to 30 days. In Morild's series of 133 drownings only 6 per cent had a combined lung weight less than 1000 g.[42]

Overinflation of the lungs

Apart from generalized waterlogging, the lungs may be markedly overinflated, filling the thoracic cavity when the sternum is removed (Fig. 16.18). The normally bare area over the heart may be covered and the lungs may bulge upwards, meeting in the midline to obliterate the anterior mediastinum. The texture is rather pale and crepitant, superficially resembling that shown in asthma – for the same reasons. The older name for this condition is 'emphysema aquosum'. True pre-existing emphysema may partially mimic the distension of drowning, but in the latter, bullae are never present. The oedema fluid in the bronchi blocks the passive collapse that normally occurs at death, holding the lungs in the inspiratory position. In addition, there is often an element of over-distension caused by the valvular action of the bronchial obstruction – again similar to asthma. In drowning this may be sufficient to mark the lateral surfaces of the lungs with the impression of the ribs, leaving visible and palpable grooves after removal of the organs from the thorax. This may be one of the most valuable positive signs of drowning to be gained at autopsy.

There may be some areas of intrapulmonary haemorrhage, which give the red tinge to the oedema fluid. These areas are seldom large or intense, and the general oedema and distension tend to minimize their prominence. Some may lie near the pleural surface and can be seen as rather blurred blotches on the exterior of the lung, the blurring being partly the result of spreading haemolysis. There are almost never subpleural petechial haemorrhages in drowning, apart from the few non-specific spots that can be found in



Figure 16.18 Overinflation of the lungs (emphysema aquosum) in drowning with overlapping of the anterior margins and haemorrhages in the right middle lobe.

the fissures and around the hilum in virtually every autopsy, no matter what the cause of death.

Other organs in drowning

There are no other reliable autopsy changes in drowning. The heart and great veins have often been said to be 'dilated and engorged with fluid blood, especially the right side', but this is such a subjective and non-specific finding as to be useless, meriting no further consideration.

Many pathologists have for centuries claimed that the blood remains more fluid in drowning, and the physiological researchers of this century have confirmed the haemodilution in freshwater drowning. As a gross sign at autopsy, however, it is totally subjective and unreliable.

The stomach may contain watery fluid or even foreign material from the water, such as silt, weed or sand, but this cannot be accepted as a positive aid to the diagnosis. Many undoubted drownings show no water in the stomach, yet other cases in which a dead body was immersed reveal copious water in the stomach. The limiting factor is the tone in the oesophagus and cardiac sphincter, not the drowning process. The same applies to foreign materials in the trachea. Haemorrhage into the middle ears and into the temporal bone has been postulated as a positive sign of drowning, but in the author's (BK) own experience, and according to Sanchez-Hanke *et al.*, it is a non-specific finding (Fig. 16.19).[43] It can occur in any type of death where drowning can be definitely excluded, yet in classic instances of drowning, such bleeding may be absent. It has been said to be related to the depth to which the body sinks because of the hydrostatic pressure within the ear, but even this does not accord with the experience of most pathologists.[44] Neither is the presence of fluid in the middle ear or paranasal sinuses a reliable diagnostic sign of drowning.[45,46]



Figure 16.19 Bilateral haemorrhages within the petrous temporal bones in drowning. Though claims have been made for the usefulness of this observation, its occurrence seems random, sometimes being present in non-drowning and absent in proven drowning.

Chemical changes in the blood in drowning

Because of the marked haemodilution that occurs in freshwater drowning and the electrolyte shifts in salt-water drowning, it is reasonable to expect that chemical analyses of the plasma should provide reliable evidence of drowning. Unfortunately, these theoretical hopes have not been realized in practice, mainly because of the biochemical chaos that occurs soon after death from any cause, in which the ability of live cell membranes to partition fluid and electrolytes is rapidly lost. Gettler published results of analyses of chloride content from the left and right sides of the heart, suggesting that the haemodilution from freshwater drowning would differentially reduce the plasma concentration on the left side, a difference of 25 mg/100 ml being significant.[47] Salt-water drowning was said to produce the opposite effect. Gettler's claims have often been refuted and they are now no longer accepted. It has been shown that post-mortem changes in blood chloride concentrations occur irrespective of drowning and that the rate of change may be different on each side of the heart. Even the differentiation between freshwater and seawater drowning was discredited by the work of Durlacher *et al.,* who found no reliable changes in sodium, potassium and chloride concentration.[48] Similar results were found by Fuller.[49]

Electrolyte measurements in surviving victims of near-drowning showed no regular pattern, according to Rivers *et al*.[35] Moritz attempted to use magnesium as a similar marker in drowning, but the unreliability of such analyses has prevented their being used as a routine procedure. Once again, the hazards of extrapolating the results of animal experiments to humans is highlighted by these results, as even other mammals like dogs have quite different responses to the same environmental changes.

Other chemical substances have been used as markers of drowning, such as strontium. Azparren *et al.* claim that differences in the strontium concentration of blood from left and right heart are always greater than 75 mg/l in seawater drowning.[50]

Histological changes in drowning

Much has been written about both light and electron microscopy of the lungs in immersion deaths, especially in continental Europe. The accounts are confusing, however, and sometimes contradictory, the consensus of opinion being that such changes are inconstant and unreliable.

Much of the work has tried to confirm histologically the genuineness of 'emphysema aquosum' in both fresh and decayed bodies, but the dilatation and rupture of the terminal air spaces can occur not only as a result of drowning, but of passive immersion in water deeper than 4 m. Dilatation of the alveoli, thinning of the walls and compression of the capillaries are easy to observe, but the significance is always ambiguous. Reh classified such lungs on the basis of reticulin fibres, but Heinen and Dotzauer showed similar changes in undrowned material.[51,52] Janssen has reviewed the subject and concludes that though histological evidence may be helpful and indicative, it is never probative.[53]

The number of macrophages in the alveoli, adjusted to the size of the alveoli where distended, was studied by Betz *et al.*, who claimed a diagnostic usefulness of the method as long as no autolytic changes were present.[54]

The reduction of spleen weight and spleen–liver ratios postulated as a diagnostic marker in drowning by Haffner *et al.* when compared with other modes of 'asphyxia', could not be confirmed in a larger material by Hadley and Fowler.[55,56]

The skin changes in maceration are also well recorded, and some have been claimed to have use in dating the period of immersion.[57,58] Schleyer is pessimistic on the reliability of such histological criteria.[59]

The early formation of adipocere can be detected microscopically after 3–4 weeks; this is dealt with in the chapter on post-mortem changes.

Diatoms and the diagnosis of drowning

Few topics in forensic pathology have given rise to so much argument as the use of diatoms in the diagnosis of drowning. Revenstorf in 1904 was the first to attempt to use diatoms as a test for drowning, though he stated that Hofmann in 1896 was the first to discover them in lung fluid.[60] Excellent reviews of the diatom controversy were published by Peabody, Pollanen, Lunetta and Lunetta and Modell.[61–65]

The basic premise is that when a live person is drowned in water containing diatoms (microscopic algae with a silicaceous exoskeleton), many diatoms will penetrate the alveolar walls and be carried to distant target organs such as brain, kidney, liver and bone marrow. After autopsy, samples of these organs can be digested with strong acid to dissolve the soft tissue, thus leaving the highly resistant diatom skeletons to be identified under the microscope. Alternatively, blood can be used to seek the organisms (Fig. 16.20).

When a dead body is deposited in water or when death in the water is not due to drowning, then, although diatoms may reach the lungs by passive percolation, the absence of a beating heart prevents circulation of diatoms to distant organs.

The great advantage of the diatom test, if it was reliable, would be that a positive diagnosis of drowning could be made even in the frequently putrefied bodies that are recovered, where no hope of anatomical recognition of drowning is possible. In addition, evidence of the site of the drowning might be obtained from the ecological typing of the diatoms, especially in relation to salt-water or freshwater locations.

Meticulous attention to technique must be employed at autopsy to recover suitable samples of tissue, which must not be contaminated by the body surface or instruments, before digestion is commenced.

Diatoms belong to the class of plants known as Diatomaceae and consist of a box or 'frustule' composed of two valves that fit together to enclose the cytoplasmic contents. They have either radial symmetry ('centric' diatoms) or are elongated ('pennate' diatoms). The valves are highly complex in shape and are extremely resistant to decay, fossil diatoms from Jurassic times being abundant. The floor of the oceans have an area of 11 million square miles of thick diatomaceous ooze and upraised beds on land may be hundreds of feet thick, which emphasizes the vast amount of potential contaminant available (Figs 16.21, 16.22).

There are at least 10000 species, and the identification of the various types is a matter for an experienced botanist or biologist, but the following general classification is useful: 'oligohalophilic' diatoms live in freshwater with a salinity less than 0.05 per cent, and 'mesohalophilic' and 'polyhalophilic' diatoms live in brackish water and seawater with a salinity higher than 0.05 per cent.


Live entry into diatom-containing water
Diatom enters lungs
Penetrates alveolar membranes
Enters blood stream
Beating heart pumps to
brain
marrow
kidney
After acid digestion, diatoms
Recoverable on microscopy

Figure 16.20 The principle of the diatom test for drowning. When a dead body enters the water, diatoms cannot progress further than the lungs.



Figure 16.21 Diatoms seen under dark-ground illumination (original magnification ×350). These are from fresh-water. There are at least 10,000 different types and, where identification of locus of likely origin is required, the help of a biologist with expert knowledge is essential.



Figure 16.22 Scanning electron micrograph of a diatom, original magnification ×4000, 20 kV.

The critics of the diatom test point to certain problems:

- Diatoms are ubiquitous, being present in soil, water supplies and in the air. Many commonly used minerals, such as kieselguhr, are largely fossil diatoms. Manufactured substances like board-chalk and abrasives – even toothpaste – contain diatomaceous raw materials. Mant, however, examined the filters of the air-conditioning system of Guy's Hospital in London and found no diatoms taken from the city atmosphere.
- Though entry into the body is thought to be mainly through the lungs, there seems no reason why they cannot penetrate the intestinal lining, and gain access to the bloodstream and hence any body tissues.
- Certain foods, notably shellfish, contain vast quantities of diatoms that may enter the circulation and reach the tissues.

- Examination of the tissues of both animals and man reveal the presence of diatoms when the cause of death is other than drowning. Schellmann and Sperl found them in the tissues of 15 out of 16 non-drowned bodies, but other workers found no diatoms in 33 out of 34 bodies, including two drownings.[65]

Foged made a detailed investigation into drowned and non-drowned bodies in Denmark, and concluded that the diatom test was quite invalid.[66] He quoted many references both for and against the reliability of the technique, and no doubt the controversy will continue. It seems probable that there may be a quantitative difference between the numbers of diatoms recovered from the tissues in drowning and non-drowning deaths, and a careful analysis of the species identification in relation to the locus and circumstances of the death may be useful. At the present time the diatom test should be used only as an indicative aid and not as legal proof of drowning. Recently, other water organisms have been advocated as tests for drowning, including soft-bodied protozoa and crustaceans.

Japanese workers have used other methods to digest autopsy tissues to seek diatoms because it has been shown that strong acid digestion markedly reduces the yield. The new methods introduced for diatoms, such as enzymatic and detergent digestion, allowed soft-bodied microscopic organisms to be recovered and claims for better specificity for drowning have been made.[67,68] Chinese workers have claimed that the spectrofluorophotometric detection in the lungs of chlorophyll derived from plankton is diagnostic, but it is not clear how this can be differentiated from plankton passively entering the lungs after death.[69]

References

1 Devergie A. Recherches sur les noyés. In: *Annales d' Hygiène Publique et de Médecine Légale*. Paris: Gabon, Libraire-Éditeur, 1829, pp. 160–96.
2 Kolisko A. *Eduard R.v. Hofmann's Lehrbuch der Gerichtlichen Medizin*, 9th edn. Berlin: Urban & Schwarzenberg, 1903.
3 Weber W. [On fingertips of 'washerwoman's hands' (author's transl)]. *Z Rechtsmed* 1978;81(1):63–6.
4 Reh H. [Early postmortem course of washerwoman's skin of the fingers]. *Z Rechtsmed* 1984;92(3):183–8.
5 Weber W, Laufkotter R. [Stages of postmortem formation of washerwoman's skin –results of systematic qualitative and quantitative experimental studies]. *Z Rechtsmed* 1984; 92(4):277–90.
6 Püschel K, Schneider A. [Development of immersion skin in fresh and salt water at different water temperatures]. *Z Rechtsmed* 1985;95(1):1–18.
7 Bonte W, Sprung R, Huckenbeck W. [Problems in the evaluation of electrocution fatalities in the bathtub]. *Z Rechtsmed* 1986;97(1):7–19.
8 Di Nunno N, Di Nunno C. Motorboat propeller injuries. *J Forensic Sci* 2000;45(4):917–19.
9 Keatinge WR. *Survival in Cold Water: the Physiology and Treatment of Immersion Hypothermia and of Drowning*. Oxford: Blackwell Scientific, 1969.
10 Bühring M, Spies HF. [Sympatho-adrenal activity in acute cold stress. The mechanism of sudden death following water immersion]. *Z Rechtsmed* 1979;83(2):121–7.
11 Ishikawa H, *et al*. Screening of children with arrhythmias for arrhythmia development during diving and swimming – face immersion as a substitute for diving and exercise stress testing as a substitute for swimming. *Jpn Circ J* 1992;56(9):881–90.
12 Datta A, Tipton M. Respiratory responses to cold water immersion: neural pathways, interactions, and clinical consequences awake and asleep. *J Appl Physiol* 2006;100(6):2057–64.
13 Ackerman MJ, Tester DJ, Porter CJ. Swimming, a gene-specific arrhythmogenic trigger for inherited long QT syndrome. *Mayo Clin Proc* 1999;74(11):1088–94.
14 Ackerman MJ, *et al*. Molecular diagnosis of the inherited long-QT syndrome in a woman who died after near-drowning. *N Engl J Med* 1999;341(15):1121–5.
15 Lunetta P, *et al*. Death in bathtub revisited with molecular genetics: a victim with suicidal traits and a LQTS gene mutation. *Forensic Sci Int* 2002;130(2–3):122–4.
16 Lunetta P, *et al*. Molecular screening of selected long QT syndrome (LQTS) mutations in 165 consecutive bodies found in water. *Int J Legal Med* 2003;117(2):115–7.
17 Tester DJ, *et al*. Unexplained drownings and the cardiac channelopathies: a molecular autopsy series. *Mayo Clin Proc* 2011;86(10):941–7.
18 Tester DJ, Ackerman MJ. Drowning. *N Engl J Med* 2012; 367(8):777; author reply 777–8.
19 Saxena A, Ang LC. Epilepsy and bathtub drowning. Important neuropathological observations. *Am J Forensic Med Pathol* 1993;14(2):125–9.
20 Schmidt P, Madea B. Death in the bathtub involving children. *Forensic Sci Int* 1995;72(2):147–55.
21 Stumpp JW, Schneider J, Bar W. Drowning of a girl with anomaly of the bundle of His and the right bundle branch. *Am J Forensic Med Pathol* 1997;18(2):208–10.
22 Somers GR, Chiasson DA, Smith CR. Pediatric drowning: a 20-year review of autopsied cases: III. Bathtub drownings. *Am J Forensic Med Pathol* 2006;27(2):113–6.
23 Schmidt P, Madea B. Homicide in the bathtub. *Forensic Sci Int* 1995;72(2):135–46.
24 Thomsen JL, Kardel T. Intoxication at home due to carbon monoxide production from gas water heaters. *Forensic Sci Int* 1988;36(1–2):69–72.
25 Tirasci Y, *et al*. Electrocution-related mortality: a review of 123 deaths in Diyarbakir, Turkey between 1996 and 2002. *Tohoku J Exp Med* 2006;208(2):141–5.
26 Robbins J. *The Magnificent Spilsbury and the Case of the Brides in the Bath*. London: John Murray, 2010.
27 Tz'u S. The washing away of wrongs. Sivin N (ed). *Science, Medicine, and Technology in East Asia*. Vol. 1. Ann Arbor: The University of Michigan Center for Chinese Studies, 1981.
28 Falk F. Ueber den tod im wasser. *Virchows Arch* 1869;47(1): 39–89.

29 Bert P. *Leçons sur la Physiologie Comparée de la Respiration*. Paris: Baillière, 1870.
30 Carrara M. Electrolytes and osmotic pressure in drowning. *Vrtlschr Gericht Med* 1902;24:236–40.
31 Freimuth HC, Swann HE, Jr. Plasma specific gravity changes in sudden deaths; observations with specific reference to drowning. *AMA Arch Pathol* 1955;59(2):214–8.
32 Swann HG, *et al*. Fresh water and sea water drowning; a study of the terminal cardiac and biochemical events. *Tex Rep Biol Med* 1947;5(4):423–37.
33 Swann HG, Spafford NR. Body salt and water changes during fresh and sea water drowning. *Tex Rep Biol Med* 1951;9(2):356–82.
34 Crosfill JW. Drowning. *Proc R Soc Med* 1956;49(12):1051–8.
35 Rivers JF, Orr G, Lee HA. Drowning. Its clinical sequelae and management. *Br Med J* 1970;2(5702):157–61.
36 Bolte RG, *et al*. The use of extracorporeal rewarming in a child submerged for 66 minutes. *JAMA* 1988;260(3):377–9.
37 Chochinov AH, *et al*. Recovery of a 62-year-old man from prolonged cold water submersion. *Ann Emerg Med* 1998;31(1):127–31.
38 Thalmann M, *et al*. Resuscitation in near drowning with extracorporeal membrane oxygenation. *Ann Thorac Surg* 2001; 72(2):607–8.
39 Giammona ST, Modell JH. Drowning by total immersion. Effects on pulmonary surfactant of distilled water, isotonic saline, and sea water. *Am J Dis Child* 1967;114(6):612–6.
40 Copeland AR. An assessment of lung weights in drowning cases. The Metro Dade County experience from 1978 to 1982. *Am J Forensic Med Pathol* 1985;6(4):301–4.
41 Kringsholm B, Filskov A, Kock K. Autopsied cases of drowning in Denmark 1987–1989. *Forensic Sci Int* 1991;52(1):85–92.
42 Morild I. Pleural effusion in drowning. *Am J Forensic Med Pathol* 1995;16(3):253–6.
43 Sanchez-Hanke M, Westhofen M, Puschel K. Temporal bone hemorrhages caused by intracranial congestion in different causes of death (for example: drowning). *Rechtsmed* 1996;6(4):120–4.
44 Niles NR. Hemorrhage in the middle-ear and mastoid in drowning. *Am J Clin Pathol* 1963;40:281–3.
45 Blumenstok L. Zur verwerthung der ohrenprobe für die diagnose des ertrinkungstodes. *Friedreich's Bl für ger Med* 1876.
46 Bohnert M, Ropohl D, Pollak S. [Forensic medicine significance of the fluid content of the sphenoid sinuses]. *Arch Kriminol* 2002;209(5–6):158–64.
47 Gettler AO. A method for the determination of death by drowning. *JAMA* 1921;77:1650–2.
48 Durlacher SH, Freimuth HC, Swan HE, Jr. Blood changes in man following death due to drowning, with comments on tests for drowning. *AMA Arch Pathol* 1953;56(5):454–61.
49 Fuller RH. The clinical pathology of human near-drowning. *Proc R Soc Med* 1963;56:33–8.
50 Azparren J, de la Rosa I, Sancho M. Biventricular measurement of blood strontium in real cases of drowning. *Forensic Sci Int* 1994;69(2):139–48.
51 Reh H. [About the problem of 'lungs in drowning' (author's transl)]. *Z Rechtsmed* 1976;77(3):219–21.
52 Heinen M, Dotzauer G. [The lung of a drowned person]. *Beitr Gerichtl Med* 1973;30:133–41.
53 Janssen W. *Forensic Histopathology*. Berlin: Springer Verlag, 1984.
54 Betz P, *et al*. Alveolar macrophages and the diagnosis of drowning. *Forensic Sci Int* 1993;62(3):217–24.
55 Haffner HT, Graw M, Erdelkamp J. Spleen findings in drowning. *Forensic Sci Int* 1994;66(2):95–104.
56 Hadley JA, Fowler DR. Organ weight effects of drowning and asphyxiation on the lungs, liver, brain, heart, kidneys, and spleen. *Forensic Sci Int* 2003;137(2–3):239–46.
57 Ökrös S. Gerichtlich-medizinische bedeutung des elastischen fasersystems der haut. *Dtsch Z Ges Gerichtl Med* 1938;29(6): 485–500.
58 Dierkes K. Über die histologie der waschhaut. *Dtsch Z Gesamte Gerichtl Med* 1938;30:262.
59 Schleyer F. [Histology of skin changes in the drowned]. *Dtsch Z Gesamte Gerichtl Med* 1951;40(7–8):680–4.
60 Revenstorf V. Der Nachweis der aspirierten ertränkungsflüssigkeit als kriterium des todes durch ertrinken. *Vjschr Gerichtl Med* 1904;27:274–99.
61 Peabody AJ. Diatoms and drowning – a review. *Med Sci Law* 1980;20(4):254–61.
62 Pollanen MS. *Forensic Diatomology and Drowning*. 1st edn. Elsevier Science, 1998.
63 Lunetta P. Bodies found in Water, Epidemiological and Medico-legal Issues. Helsinki, University of Helsinki, 2005, p. 124.
64 Lunetta P, Modell JH. Macroscopical, microscopical, and laboratory findings in drowning victims. In: Tsokos M (ed). *Forensic Pathology Reviews*. Humana Press, 2005, pp. 3–77.
65 Schellmann B, Sperl W. [Detection of diatoms in bone marrow (femur) of nondrowned (author's transl)]. *Z Rechtsmed* 1979;83(4):319–24.
66 Foged N. Diatoms and drowning – once more. *Forensic Sci Int* 1983;21(2):153–9.
67 Funayama M, *et al*. Detection of diatoms in blood by a combination of membrane filtering and chemical digestion. *Forensic Sci Int* 1987;34(3):175–82.
68 Matsumoto H, Fukui Y. A simple method for diatom detection in drowning. *Forensic Sci Int* 1993;60(1–2):91–5.
69 Qu J, Wang E. A study on the diagnosis of drowning by examination of lung chlorophyll(a) of planktons with a spectrofluorophotometer. *Forensic Sci Int* 1992;53(2):149–55.

This page intentionally left blank

CHAPTER 17

Neglect, Starvation and Hypothermia

- Introduction
- General features of neglect and starvation
- Medico-legal problems
- Injury caused by cold: hypothermia
- The 'hide-and-die' syndrome
- Deaths from exposure
- Local injury due to cold: frostbite
- References

Introduction

Though, tragically, starvation is one of the most widespread scourges of our planet, we are here concerned with individual neglect with which starvation is often associated, either as a potentially criminal act or as a manifestation of self-neglect. As with so many conditions, the extremes of life are most affected, rather than the middle years (Fig. 17.1). Infants and children are at the mercy of their parents or guardians for the provision of care and sustenance. The old are prey to senile dementias and other disorders of the mind, as well as often being devoid of spouse or caring relatives – or sometimes even the financial means to stay warm and adequately fed.

Many countries have legislation designed to protect children, on the basis that they are totally dependent upon adults for the necessities of life. In Britain, the Children Act places a responsibility upon parents, guardians or the community to care for children.[1] The minimum requirements laid down by law are the provision of food, clothing, shelter and education. Unfortunately, these requirements are evaded in spite of official supervision and, from time to time, scandals explode in the public eye when a child has died, not from physical abuse, but from sheer neglect.

Voluntary organizations, such as the National Society for the Prevention of Cruelty to Children (NSPCC) were founded in the nineteenth century to combat the widespread neglect of children consequent upon the population explosion of the Victorian industrial revolution. Their present-day role, however, has changed radically so that now most of their efforts are directed against physical, sexual and mental abuse, rather than starvation and neglect. Notwithstanding this change of emphasis, deaths still occur from deliberate or negligent lack of provision of proper care and nutrition of children. In general – though there are many exceptions – nutritional neglect and physical battering tend to be mutually exclusive. The abused child is usually well nourished and the emaciated child is usually uninjured.

Neglect and starvation are not synonymous, but are so often closely associated that the two conditions are usually considered together. When fatal, they may come to the attention of the pathologist either as a potentially criminal death or, when self-inflicted, in the usual course of coroners' or similar enquiries. Rarely, victims will starve from being isolated in some catastrophe, such as a mining incarceration or shipwreck, but these days a more common occurrence is a hunger strike or voluntary fast for some political or similar motive.

General features of neglect and starvation

The obvious and outstanding appearance is of emaciation caused by an inadequate intake of food. A minimum of about 1500–1900 calories is needed to maintain body weight in active adults. Life is threatened when more than 40 per cent of the original body weight has been lost, though the speed of loss is relevant. Total deprivation of food will obviously kill faster than a severe reduction. Total lack of food is likely to cause death in about 50–60 days as long as adequate water is available, but this depends on weather and temperature as well as the original fitness – and fatness – of the individual. Deprivation of water will kill in about 10 days – or less in higher ambient temperatures.

In the numerous cases of fatal and non-fatal starvation seen at the end of the Second World War in Nazi concentration camps, two main types were seen. These were the 'dry' type, in which there was emaciation, but only leg oedema, with a body weight up to half the normal. Alive, these showed marked hypotension, feeble pulse and cyanosis. The other 'wet' group had marked oedema of face, trunk and limbs, with ascites and pleural effusions. The oedema of hypoproteinaemia is caused by protein being diverted to produce energy when carbohydrate and fat are grossly deficient in the diet. In some victims, the skeleton accounted for 50 per cent of the total body weight, instead of the usual 15 per cent.

Other features are secondary to this nutritional deficiency, such as intercurrent infections, avitaminoses, skin disorders and nutritional oedema. Dehydration, hypothermia and actual necrosis of the extremities are the most severe manifestations that contribute to death.

Most fatally neglected infants are under 1 year of age.[2–5] At autopsy great care must be taken to measure, not estimate, the full indices of size and weight. Crown–heel, crown–rump, head diameter, foot length and exact weight must be measured accurately, so that comparison may be made with standard paediatric percentile growth charts, consonant with age, birth weight, sex and race.

The diameter of limbs at major landmarks such as wrists and ankle should be measured with a flexible tape. Photographs should be taken in all major views, using colour to record skin tints and lesions, as well as the general aspect of the emaciated body. The words 'cachexia', 'emaciation' and 'marasmus' are all synonymous as used today, though 'marasmus' is confined to the description of infant victims. The so-called 'Hippocratic facies' is not confined to the emaciation of neglect, as cachexia from any cause – such as an obstructive carcinoma of the oesophagus – can give rise to the same appearance. The skin of the face is stretched tightly across the cheekbones, the cheeks are sunken and the lines of the jaw are obtrusive. The eyes are deeply sunken from loss of orbital fat, though dehydration may contribute to this manifestation (Figs 17.2, 17.3).

On the trunk the ribs are prominent, with concavities in the intercostal spaces and sunken supraclavicular fossae. The abdomen is of the classical 'scaphoid' shape, being concave from costal margin to iliac crests, the latter sticking up like wings. The limbs are almost skeletal from loss of fat and muscle, and the head may appear deceptively large by contrast with the narrowed neck.



Figure 17.1 Death from neglect and hypothermia in an elderly female. The discolouration of the feet and hands was cyanotic.



Figure 17.2 Fatal neglect and starvation in an infant. The limbs are emaciated, the abdomen scaphoid and the head appears relatively large. The back shows extensive pressure ulceration. The sunken eyes and cheeks from malnutrition, and dehydration constitute the 'Hippocratic facies'.



Figure 17.3 The abdominal contents of the infant in Fig. 17.2, showing the empty intestines, distended with gas.

The skin surface may present differing appearances according to the length of time that nutritional loss has been suffered and the qualitative defect in the diet, especially of certain vitamins. The skin may be pale, lustrous and semitranslucent, with an almost blue tinge in infants, partly as a result of the loss of subcutaneous fat.

It may also be coarse and rough, however, with flaking hyperkeratosis, though this is more often seen in aged persons, partly as a result of senile changes. Pigmentation, either diffuse or of a punctate nature, is sometimes seen.

Dehydration is a common feature, especially in infants and may be the major contribution to death. The skin is dry and wrinkled and, when pinched between the fingers, remains ridged because of loss of subcutaneous fat and fluid. The fontanelles may be depressed from loss of pressure of cerebrospinal fluid. In chronic starvation, hypoproteinaemia can lead to oedema, though this is rarely seen in forensic practice. In famines it may be widespread, associated with other nutritional disorders such as kwashiorkor.

Skin infections are common, partly as a result of nutritional loss of resistance to infections and partly because of neglect in care and hygiene, especially in infants. Pressure sores on buttocks, heels and spine may occur in both infants and old people who are lying inert because of weakness, and, in infants, urine dermatitis and lack of any skin care after defecation worsens these (Figs 17.4, 17.5). Sores may be seen on any pressure or friction points, such as the elbows, knees, shoulders and occiput. Apart from pressure areas, any part of the skin surface may develop infected lesions, which often crust over after partial healing. Sores on the lips, blepharitis and conjunctivitis may also occur. The hair is dry and brittle, sometimes becoming depigmented and even gingery with chronic malnutrition.

Internally, the same loss of adipose tissue will be evident both subcutaneously and in the internal fat stores, such as the omentum, mesentery and perirenal area. The organs will be small (except the brain) and it is therefore important to weigh the major viscera to compare them with standard tables for sex and age. Organ atrophy will be more apparent in old people, but the problem then exists of distinguishing weight loss caused by nutritional defects from the usual senile atrophy. The differentiation is one of degree, as chronic starvation can reduce organs to unusually low weights. More specific internal signs will include an empty gut, which may be gas-filled and translucent from stomach to colon (Fig. 17.3). Any faeces in the rectum are likely to be inspissated, especially if there has been fluid restriction and dehydration. Faecoliths may ulcerate the intestinal lining. In infant starvation, however, the stools may be fluid and offensive unless dehydration was severe. The gall bladder is distended in starvation if there has been no recent meal to stimulate emptying. The tongue may be thickly coated, but this is such a non-specific finding that it is of no practical use.



Figure 17.4 Neglect of an elderly diabetic female with a history of alcohol abuse who had stayed in bed for a long time and had allegedly forbidden her husband to call for a doctor. Faeces– and urine-soiled shirt infested by different-aged blowfly larvae as well as pupae. Entomological analysis of the samples collected from the scene of death confirmed the dominant species as *Protophormia terranovae*, which typically pupariates at the feeding medium or in its immediate vicinity. In the prevailing circumstances, the time from oviposition to an adult blowfly was calculated to take approximately 2–3 weeks, which gives an estimate for the duration of the assumed neglect.



Figure 17.5 Faeces– and urine-soiled back of the female in Fig. 17.4, showing blowfly larvae and extensive skin erosions.

Medico-legal problems

In infants there may sometimes, if rarely, be physical abuse associated with neglect, so post-mortem imaging or radiography prior to autopsy is essential – in fact the whole procedure must be conducted on the lines indicated for the ‘battered child’ (Chapter 22). In both children and adults, a major problem is cause and effect, especially where some pathological disease process is found. Did a cancer lead to cachexia or is it an incidental finding? Did pulmonary tuberculosis cause the emaciation or was the infection secondary to the nutritional deficiency? The relevance of diseases such as diabetes, Addison's disease, chronic infections and neoplasms must be evaluated. Particularly important in children are familial metabolic diseases that may be associated with failure to thrive and frank emaciation.

Where death from a wasting condition is alleged to be the result of malnutrition, either from wilful withholding of food or from indifference about its provision, a defence may be raised against criminal prosecution that the condition was caused by a natural disease. Indeed, such a claim may be true on occasions. Both the prosecution and defence medical advisers must undertake a thorough investigation using all anatomical, histological and biochemical means at their disposal to discover any such metabolic or pathological cause for fatal wasting, before attributing the death to sheer malnutrition.

Injury caused by cold: hypothermia

Until about 40 years ago, injury and death from the effects of low temperature was thought to occur almost exclusively among those subjected to extremes of climate out of doors. Mountaineers, polar explorers and those exposed in some disaster on sea or land were considered to be the prime candidates for frostbite and 'freezing to death'. Only after some noteworthy medical publications, such as those by Emslie-Smith, Duguid *et al*. and others, was it generally appreciated that hypothermia was a common and widespread danger in temperate climates and indoors.[6,7] Recognition was rapid and Special Committees of both the Royal College of Physicians and the British Medical Association produced reports on hypothermia in the 1960s.[8,9]

As in so many other conditions, the aged and the infants are most vulnerable, especially as the condition is insidious and may not be suspected in time by those more active persons who are the potential guardians of those at the two extremes of life.

Factors involved in hypothermia

Low environmental temperature

No precise figures can be given in degrees Celsius for temperatures potentially dangerous to life, as other factors and the personal vulnerability of different individuals vary considerably. Certainly the air temperature need be nothing like as low as was thought in former years, when profound frost was considered essential for the production of lesions. Air temperatures below 10°C are probably low enough to cause hypothermia in vulnerable persons, but air movements such as external wind or internal draughts will make things worse by markedly increasing the rate of body cooling. Damp conditions, especially of clothing, will also aid cooling from the latent heat of evaporation.

Age and physique

As stated, the elderly and the young are at greatest risk. The old person may have poor musculature and a lack of mobility, thus depressing heat production from muscular activity. Often thin, there may be a lack of insulating subcutaneous fat. Poor thyroid function is common, especially in elderly females, and is discussed below. Cerebral dysfunction – often from degenerative arterial disease – may lead to poor central heat regulation, a disinclination to move around and apathy concerning personal nutrition, heating and general well-being. Depression and mental illness are not uncommon, as in the early cases reported by Emslie-Smith and by Duguid *et al*.[6,7]

In infants, the body mass is small and the surface area:mass ratio large, so that heat is lost more easily. In small infants, there is naturally complete dependence on others in regard to clothing and environment (Figs 17.10, 17.11).

Hypothyroidism

Myxoedema, either occult or obvious, is an important factor in hypothermia.[10] Many elderly females have a thyroid deficiency and this is a potent factor in vulnerability to cold. The majority of victims are females over 70 and the environmental conditions in which thyroid dysfunction is a factor may be little below optimum. Cases were first reported in the 1950s by Le Marquand, soon followed by the paper of Angel and Sash.[11,12] In hypothyroid subjects, certain drugs may have a deleterious effect by precipitating hypothermia, even when the environment is relatively normal. Imipramine, chlorpromazine and diazepam are particularly hazardous. Barbiturates, phenothiazines and alcohol are also dangerous in this respect.[13]

Lack of food, adequate clothing and indoor heating

These are factors that may be social or financial, but are often related to the depressed, apathetic state of many old people, especially those with cerebral atherosclerosis. Cause and effect are often hard to separate, as the effects



Figure 17.6 Hypothermia in a 56-year-old female. She lived in extreme squalor, with no heating and broken windows, even though she had been a state registered nurse. The knees, hands and feet showed hypothermic discolouration as well as dirt.

of cold may bring on or worsen mental sluggishness and confusion (Fig. 17.6).

The manifestations of hypothermia

The clinical manifestations are not the concern of the forensic pathologist, though when unsuspected before autopsy the history may give a clue to the fatal process.

It is sometimes claimed that hypothermia in the elderly never occurs unless there is some predisposing disability, such as cerebrovascular disease, hypothyroidism, alcoholism or diabetes, for instance. This seems too restrictive an attitude, though in general is probably true. The rectal temperature is used as the measure of severity in hypothermia. Between 37°C and 32°C there are no ill-effects beyond the normal subjective feeling of being cold, with shivering and constriction of blood vessels.

When the core temperature falls further below 32°C to 24°C, there is dulling of consciousness, a fall in respiration and heart rate, and a lowering of blood pressure. If maintained without relief, death will ensue and recovery is rare if the rectal temperature falls below about 26°C, though one remarkable case reported by Laufman recovered after falling to 18°C, albeit with severe mutilating frostbite.[14]

Autopsy findings in hypothermia

There may be no signs whatsoever at autopsy in a death from hypothermia and thus the history may be all-important. The usual difficulties then arise as to how much the pathologist is entitled to rely upon hearsay evidence – as opposed to the objective findings of his own examination – when deciding on a cause of death. This is more fully discussed in the first chapter of this book.

Hypothermia, like some cases of epilepsy, asthma and drowning, provides some of the more difficult pathological dilemmas when there are slight, non-specific or absent autopsy findings. When a victim of hypothermia has been admitted to hospital and 'warmed-up', death may supervene at any time up to a few days later. In such circumstances the autopsy may reveal no positive findings. The skin changes will almost certainly be absent, but intra-abdominal signs may persist.

In a classical death from hypothermia the body will usually be that of an old person – almost half the Royal College of Physicians' series was over 65 years of age; most will be female.[9] The exterior of the body may present suggestive signs of hypothermia, in that patches of pink to brownish-pink discolouration may be seen in certain areas in around 50 per cent of the cases.[15–19] They are most often present over extensor surfaces and large joints, such as the outer sides of the hips, the elbows and the knees, and less often on the flanks and face (Figs 17.7, 17.8).



Figure 17.7 A death from hypothermia showing brownish-pink discolouration over the hip and elbow.



Figure 17.8 Frostbite of the knuckles after being left unconscious during winter in Wales. It does not require Arctic temperatures to cause tissue damage or death.



Figure 17.9 Bright red discolouration of the cheeks and nose from hypothermia. The victim suffered from mitral stenosis (where malar flush is one of the clinical signs) and was in bed in an unheated room during a Welsh winter. The tissues of the nose were virtually necrotic, amounting to actual frostbite.



Figure 17.10 Fatal child neglect. The infant has extensive skin ulceration and was underweight. Death was the result of an intercurrent chest infection.



Figure 17.11 This infant died of neglect, hypothermia and frostbite, having been left in an unheated farmhouse bedroom, the cardboard box that acted as a cot having crystals of frozen urine in the bedclothes. After death the child was dropped down the farm well in this sack with a brick as a weight.

The colour is similar to that seen in bodies exposed in cold water or in severe outdoor cold – and to the post-mortem pinkness that often develops in mortuary refrigerators. In hypothermia, however, the distribution over the large joints is distinctive, in addition to the pinkness of hypostasis. There may be pink patches on the cheeks, chin and nose, especially in victims who already had impaired cardiac function, such as the ‘malar’ flush of mitral stenosis (Fig. 17.9). The slight brownish tinge often seen in the pinkness and the rather indefinite blurred edges of the patches suggest that some haemolysis may have occurred, perhaps in the early post-mortem period as well as during the terminal stages of life. The colour is presumably due to persistent oxyhaemoglobin in the skin capillaries, which, because of the low metabolic activity of the cold tissues, fail to take up the delivered oxygen. Pooling of blood in surface vessels from the breakdown of normal vasomotor control allows this unreduced haemoglobin to show through the skin. Why a normally coloured body placed after death in a mortuary refrigerator should also become pink has never been satisfactorily explained.

In addition to pink areas of skin, the extremities may be cyanosed or they may be white. Sometimes the feet are blue to the ankles, above which is pale. The hands may show blueness of the fingers or nail beds. Oedema may be seen, most often in the feet and lower legs, but many of the victims of hypothermia already have pre-existing congestive cardiac failure. Rarely there may be blistering of the skin, usually in dependent parts such as the buttocks, backs of thighs and upper arms. This may or may not be in pink areas and seems to be caused by skin oedema which then breaks down.

The face, especially of an elderly female, may show appearances suggestive of myxoedema or hypothyroidism, with coarsening of the features, puffy eyelids and loss of eyebrow hair. Internally there may be nothing specific to note, even if the external skin changes are obvious. Signs of pre-existing disease are common, especially if one subscribes to the view that hypothermia in the elderly never occurs in the absence of systemic disease. Degenerative arterial disease, senile myocardial degeneration, hypertension, chronic renal lesions and obstructive airways disease are common. More specific lesions are considered below.

Acute gastric erosions

In the authors' view, these are found much more often than pancreatitis. The stomach mucosa is frequently studded with numerous shallow ulcers, first described by Wischnewski, the floor of each containing a dark brown plug of altered blood.[20–22] Frank haematemesis is rare, but the stomach contents sometimes contain dark acid-affected blood (Figs 17.12, 17.13).



Figure 17.12 Gastric mucosa from a hypothermia death showing numerous characteristic acute erosions (Wischnewski spots).



Figure 17.13 Microscopy of acute erosions of the gastric mucosa (Wischnewski spots) in hypothermia (H&E).

Acute pancreatitis

This is the lesion most often quoted in textbooks, but is present in less than half the deaths from proven hypothermia. It may have been diagnosed before death from an increase in serum amylase activity. The most obvious feature may be areas of stiff, yellow, fat necrosis when the pancreas is sectioned at autopsy. There may be adjacent areas of fat necrosis in the omentum and mesentery. Haemorrhage into the gland may occur, but caution has to be employed here, as post-mortem autolysis of this organ commonly gives a haemorrhagic appearance in many other modes of death seen at autopsy. Histologically, necrosis, leucocyte infiltration and fat necrosis may be confirmed in some instances, but in others the pancreas, even if haemorrhagic, yields little information on microscopy. In a review of 143 autopsy reports from hypothermia cases by Preuss *et al.*, description of pancreatic haemorrhage was found in five cases (3.5 per cent) as well as one acute and one chronic pancreatitis. Retrospective study of pancreatic histology of 62 of these hypothermia victims confirmed haemorrhage in 11 (18 per cent) subjects. Optically empty vacuoles in adenoid cells were observed in 24 (39 per cent) subjects, whereas in 15 (24 per cent) subjects pancreatic tissue was too autolytic to allow a definitive diagnosis.[23]

Pulmonary oedema

This is common, but as it is such a common finding in any death from cardiac failure, its diagnostic value in hypothermia is almost nil.

Perivascular haemorrhages

These have been described in the brain, especially in the walls of the third ventricle, but again they are not particularly specific, especially in an autopsy population that has a high incidence of cerebrovascular disease. Sludging of blood in peripheral vessels may occur, partly from cold agglutinins. This contributes to skin oedema and necrosis, though peripheral vasoconstriction is the main cause of the infarction of frostbite. Microinfarcts are common in many organs in hypothermia, presumably from cold agglutinins blocking small vessels. Deep vein thrombosis in the legs and pulmonary embolism are occasionally found, but again cause and effect is hard to establish.

It is said that the good preservation of tissues when examined histologically is characteristic of hypothermia, as autolysis is retarded by the low temperature. In the experience of the authors, this claim is not justified.

The 'hide-and-die' syndrome

There is a peculiar aspect to some cases of hypothermic death in that it is associated with the victim undressing and hiding away from sight.[24–27] The subject is usually an old person, male or female. When found dead (usually, but not always at home), the body may be partly or even totally naked, even though the environment is cold. In addition, the victim may have burrowed his or her way into some corner or cupboard, or alternatively pulled down furniture and household articles into a heap on top of the body. In fact, the house may be in such a state of disorder that when the police break in and find a corpse amongst such chaos they may naturally suspect a homicide and robbery.

The author (BK) has seen old people who have crawled into small cupboards, the bottom of wardrobes, under low shelves, and into corners of pantries and outhouses. They have been found under piles of books pulled from a bookcase, or hidden under a mound of old clothes, newspapers and other debris.

The signs of hypothermia are usually present and the problem then arises as to whether the victim became hypothermic first, which led to mental confusion that caused the strange behaviour, or whether – as a result of some mental aberration, perhaps related to senility or other cerebral episode – they began behaving abnormally, including shedding their clothes and so became fatally hypothermic.

Though some geriatricians claim that hypothermia is almost always precipitated by some natural illness, including cerebral vascular episodes, the experience of most pathologists is that it is not common to find definite lesions of such predisposing factors at autopsy.

Biochemical analyses of vitreous humor, cerebrospinal fluid, blood and urine have been used to find biochemical markers of hypothermia but, so far, none of the investigated parameters have been shown to be reliable.[28–38]

Deaths from exposure

Fatal hypothermia can occur in healthy adults, as well as infants and old people. This is caused by purely environmental conditions, which need not be extreme. One common group, especially in more northern countries, is the inebriated person who becomes exposed to even moderate cold. The typical circumstances are a person who gets drunk and either falls asleep outdoors in his drunken state or sustains some accident – such as a fall or even mild head injury – which incapacitates him for long enough for him to become hypothermic. Alcohol seems to have a secondary effect, apart from causing incapacity and immobility. Its vasodilating effect on skin allows heat loss to be more rapid and in higher concentrations it may have a direct action on the heat-regulating centres. Apart from drunken victims, many other classes of person may fall prey to hypothermia. Hill-walkers, climbers, yachtsmen and dinghy-sailors, swimmers and other classes of sportsmen and women can become cold and exhausted. Every year sees deaths and rescue escapades in the hill country of Britain, even when the weather is far from Arctic in severity. Naturally the risks in colder countries and at high altitudes almost anywhere in the world are much greater. For the pathologist, the features are similar to domestic hypothermia, but there may be the added lesions of frostbite.

Local injury due to cold: frostbite

There are a number of different clinical lesions caused by the effect of prolonged cold on the extremities. 'Immersion foot' and 'trench foot' refer to damp cold damage, whereas 'frostbite' is caused by dry conditions below zero. In the context of forensic pathology, they may be found in victims of fatal hypothermia, but rarely kill in themselves unless tissue necrosis becomes infected. Severe damage with sloughing and separation of toes, or part of the foot is likely to be seen only in survivors or victims of some catastrophe on sea or mountainside, but the author (BK) has seen one case where a neglected infant was left in a urine-soaked cot at temperatures below zero for many days. When it died of a mixture of hypothermia and chest infection, the parents placed it in a sack with a brick and dropped it down a well. On recovery of the body, separation of the necrotic distal part of a foot was seen, with a red zone of inflammatory tissue on the proximal margin. Frostbite may affect only the skin or may extend deeply into the underlying tissues. Lesser degrees are reversible, but infarction and necrosis may ensue if the blood supply is cut off by vasoconstriction, sludging and thrombosis, for a sufficient time (Figs 17.14, 17.15).



Figure 17.14 Frostbite of the foot from the infant shown in Figure 17.10. The distal part of the foot is infarcted and a line of separation has appeared between the distal slough and the rest of the limb.



Figure 17.15 Frostbite on left auricle of a male who, heavily intoxicated by alcohol, left for home at night in the Arctic winter, but lost his way at −40C° and was found dead the following day.

References

1 *Children Act 2004 (c. 31).*

2 Madea B, Henssge C, Berghaus G. [Child neglect death of an infant by faulty nutrition]. *Arch Kriminol* 1992;189(1–2):33–8.

3 Vock R, *et al*. [Fatal child neglect in West Germany 1 January 1985 to 2 October 1990. Results of a multicenter study]. *Arch Kriminol* 1999;204(1–2):12–22.

4 Vock R, *et al*. [Fatal child neglect in East Germany 1 January 1985 to 2 October 1990. Results of a multicenter study]. *Arch Kriminol* 2000;205(1–2):44–52.

5 Fieguth A, *et al*. Lethal child neglect. *Forensic Sci Int* 2002;130(1): 8–12.

6 Emslie-Smith D. Accidental hypothermia; a common condition with a pathognomic electrocardiogram. *Lancet* 1958;2(7045): 492–5.

7 Duguid H, Simpson RG, Stowers JM. Accidental hypothermia. *Lancet* 1961;2(7214):1213–9.

8 Famma PG, Paton WB, Bostock MI. Accidental hypothermia in the elderly. *Br Med J* 1964;2(5419):1255–8.

9 Royal College of Physicians of London, C.o.A.H., *Reports*. 1966; p. 36.

10 Wartofsky L. Myxedema coma. *Endocrinol Metab Clin North Am* 2006;35(4):687–98, vii–viii.

11 Le Marquand HS, Hausmann W, Hemsted EH. Myxoedema as a cause of death; report of two cases. *Br Med J* 1953;1(4812): 704–6.

12 Angel JH, Sash L. Hypothermic coma in myxoedema. *Br Med J* 1960;1(5189):1855–9.

13 Kortelainen ML. Drugs and alcohol in hypothermia and hyperthermia related deaths: a retrospective study. *J Forensic Sci* 1987;32(6):1704–12.

14 Laufman H. Profound accidental hypothermia. *JAMA* 1951;147(13):1201–12.

15 Keferstein A. Leichenbefund beim erfrierungstod. *Z f Medicinalb* 1893;6:201–8.

16 Mant AK. Autopsy diagnosis of accidental hypothermia. *J Forensic Med* 1969;16(4):126–9.
17 Gillner E, Waltz H. Zur symptomatik des erfrierens. *Kriminal Forens Wiss* 1971;5:179–85.
18 Hirvonen J. Necropsy findings in fatal hypothermia cases. *Forensic Sci* 1976;8(2):155–64.
19 Madea B, Preuss J, Lignitz E. Unterkühlung. Umstände, morphologische befunde und ihre pathogenese. *Rechtsmed* 2004;14:41–59.
20 Wischnewsky SM. Ein neues kennzeichen des todes durch erfrieren. *Bote Gerichtl Med* 1895;3:12–20.
21 Tsokos M, *et al*. Histological and immunohistochemical study of Wischnewsky spots in fatal hypothermia. *Am J Forensic Med Pathol* 2006;27(1):70–4.
22 Preuss J, *et al*. Wischnewsky's spots in an ectopic stomach. *Forensic Sci Int* 2007;169(2–3):220–2.
23 Preuss J, *et al*. Pancreatic changes in cases of death due to hypothermia. *Forensic Sci Int* 2007;166(2–3):194–8.
24 Wedin B, Vanggaard L, Hirvonen J. 'Paradoxical undressing' in fatal hypothermia. *J Forensic Sci* 1979;24(3):543–53.
25 Carter N, *et al*. Terminal burrowing behaviour – a phenomenon of lethal hypothermia. *Int J Legal Med* 1995;108(2):116.
26 Rothschild MA, Schneider V. 'Terminal burrowing behaviour' – a phenomenon of lethal hypothermia. *Int J Legal Med* 1995;107(5):250–6.
27 Turk EE. Hypothermia. *Forensic Sci Med Pathol* 2010;6(2):106–15.
28 Sadler DW, Pounder DJ. Urinary catecholamines as markers of hypothermia. *Forensic Sci Int* 1995;76(3):227–30.
29 Zhu BL, *et al*. Evaluation of postmortem urea nitrogen, creatinine and uric acid levels in pericardial fluid in forensic autopsy. *Leg Med (Tokyo)* 2005;7(5):287–92.
30 Zhu BL, *et al*. Postmortem serum catecholamine levels in relation to the cause of death. *Forensic Sci Int* 2007;173(2–3):122–9.
31 Maeda H, *et al*. Postmortem serum nitrogen compounds and C-reactive protein levels with special regard to investigation of fatal hyperthermia. *Forensic Sci Med Pathol* 2008;4(3):175–80.
32 Preuss J, *et al*. The expression of heat shock protein 70 in kidneys in cases of death due to hypothermia. *Forensic Sci Int* 2008;176(2–3):248–52.
33 Quan L, *et al*. Postmortem serum erythropoietin levels in establishing the cause of death and survival time at medicolegal autopsy. *Int J Legal Med* 2008;122(6):481–7.
34 Jakubeniene M, *et al*. Post-mortem investigation of calcium content in liver, heart, and skeletal muscle in accidental hypothermia cases. *Forensic Sci Int* 2009;190(1–3):87–90.
35 Yoshida C, *et al*. Postmortem biochemistry and immunohistochemistry of chromogranin A as a stress marker with special regard to fatal hypothermia and hyperthermia. *Int J Legal Med*, 2011;125(1):11–20.
36 Wang Q, *et al*. Combined analyses of creatine kinase MB, cardiac troponin I and myoglobin in pericardial and cerebrospinal fluids to investigate myocardial and skeletal muscle injury in medicolegal autopsy cases. *Leg Med (Tokyo)* 2011;13(5):226–32.
37 Palmiere C, *et al*. Usefulness of postmortem biochemistry in forensic pathology: illustrative case reports. *Leg Med (Tokyo)* 2012;14(1):27–35.
38 Palmiere C, Mangin P. Postmortem chemistry update part I. *Int J Legal Med* 2012;126(2):187–98.

CHAPTER 18

Deaths Associated with Sexual Offences

- Introduction
- External findings in fatal sexual assaults
- Internal examination
- References

Introduction

The examination of living victims of sexual assaults is the province of the forensic physician or 'police surgeon', in places where such doctors exist. In many countries, any physician may be asked by the police to examine the victim of an alleged sexual offence, but this difficult and onerous task in the living victim is outside the experience of many pathologists – though in some jurisdictions, this function is combined with that of the forensic pathologist.

In this book, attention will be confined to those cases in which a sexual assault leads to death, almost always rape and homicide (Fig. 18.1). Regrettably, a significant proportion of non-domestic homicides are associated with sexual offences, death occurring either because the female rejects the sexual approaches or because a sadosexual motive colours an intended murder. The most common mode of killing is either pressure on the neck, head injuries, or, less often, stabbing. In some instances death may be the result of violence associated with the sexual activities themselves, especially in child victims when pelvic trauma may be the immediate cause of death. In this chapter, only the sexual aspects are discussed, as other modes of violent death are covered elsewhere.



Figure 18.1 Sexual assaults are sometimes associated with extreme violence, often of a sadistic nature. Here, rape has been followed by severe head injury from the large rock seen near the central gutter of this back lane.

External findings in fatal sexual assaults

As with most forensic autopsies, a meticulous external examination is as important – and usually more important – than the internal dissection. The study of the body surface in sexual assaults is similar in both the living and dead and may be divided into general appearances and those of the perineum. The whole body surface should be searched for sexually orientated injuries.

Mouth and lips

Bruises may be found on the lips and especially inside on the buccal surfaces, from rough kissing. Petechial haemorrhages on the mucosa of the soft palate have been observed in the living in connection with fellatio.[1–3] The lips may have been forced back on to the edges of the teeth, causing abrasions, bruises and even laceration of the buccal surface. Swabs should be taken from the mouth in every case before substantial manipulation for examination, to seek evidence of seminal fluid from oral penetration. Though such swabs rarely yield a positive result as to the presence of spermatozoa, modern analytical methods may be able to detect other components of the seminal fluid or the presence of male epithelial cells.

Bites

Other bruises may be found on the neck, shoulders, breasts and buttocks from oral suction or biting. These are somewhat euphemistically termed ‘love bites’ and may range from minor lesions inflicted from enthusiastic passion to mutilating bites of a sadistic nature.

Suction lesions may comprise a circular or oval area of bruising, in which the damaged zone consists of many small intradermal petechial haemorrhages caused by sucking the skin into the mouth, the reduced air pressure rupturing the small vessels. There may be semilunar marks at the periphery from the lips, and there may be associated teeth indentations or abrasions. Such suction marks are often seen at the sides of the neck, below the ears, on the upper shoulder, and on the upper part of the breasts and around the nipples.

Actual bites may accompany suction marks or may be independent. The characteristics are described in Chapter 26, but the main features are abrasions or bruises matching the dental arches, often with discrete marks from each tooth. These may be linear if the teeth are scraped down the skin in closing the jaws. They may be superficial or deep enough to penetrate the skin as lacerations. The latter are especially common at the nipples in sexual assaults, and the nipple and part of the areola may even be partly or wholly amputated.

In sexual homicides, it is essential to obtain expert forensic odontological advice, if at all possible. In any event, photographs and measurements must be taken of these injuries and, if practicable, a cast of any teeth indentations for later comparison. Before any handling of the lesions, swabs should be taken of the surface in an effort to recover DNA (first with swabs moistened in sterile distilled water and thereafter with dry swabs, preferably in duplicate, after which the swabs should be dried or stored at −20°C).

General bruising and abrasion

Apart from bruises that may be associated with the fatal assault, such as throat or head injuries, some bruises are indicative of the sexual motivation. The breasts are often manually squeezed and manipulated, causing discoid bruises of 1–2 cm on any part, especially around the nipples. Linear abrasions, usually from fingernails, may also be present. Bruises may also be seen on the thighs and buttocks, from struggles to achieve intercourse. Both the outer and inner sides of the thighs may be bruised and scratched: a typical area is the inner aspect of the upper thigh, where the legs are manually forced apart. There may be bruising around the anus from fingers opening the buttock cleft to achieve either anal or posterior vulval penetration (Fig. 18.5).

Where the assault takes place on a hard or uneven surface, bruises and abrasions may be seen on the back, especially the shoulders and buttocks (Figs 18.2, 18.3). If outdoors, there may be marks from stones or sticks and remnants of vegetation, such as leaves, and grass and green staining may be adherent to the skin, together with earth or dirt. Examination of the clothing is usually a function of the forensic scientist (‘criminalist’), but when the pathologist examines the body *in situ*, he will naturally note damage, disarray and foreign material on the garments.

Other general injuries

The hands should be carefully examined, as in all assaults. The fingernails, especially the often longer and



Figure 18.2 In fatal rape the pathologist must note at the scene, or at the mortuary, the position and condition of clothing and presence of foreign material on the skin. Full co-operation with scene of crime officers or forensic scientists is vital in collecting trace evidence.



Figure 18.3 Multiple superficial abrasions from undergrowth and ground debris on the back of the victim of rape. This is an indication of pressure of the unclothed body on the ground. There is a ligature mark around the neck with a crossover point visible.

manicured nails of younger female, may be broken from a struggle. Occasionally, there are hairs or fibres trapped in nail splits, which may have come from the assailant or his clothing. At autopsy, the nails should be cut closely to the junction with the fingers and all parings carefully collected for forensic laboratory examination. It is rarely necessary to collect those from each finger in individual packets, but each hand should be identified separately. Some pathologists or scientific officers prefer to scrape out the space under each nail with a pointed orange-stick or toothpick, carefully retaining any debris. The reason for this interest, especially in sexual assault victims, is that they may have scratched their assailants and have blood, or even skin parings, under the nails that can be identified as to individually specific DNA characteristics.

Signs of head injury and throttling are dealt with elsewhere, but some fatal trauma may be sexually orientated, especially knife injuries. Sadistic cutting or stabbing may be inflicted on sexually significant areas, especially the breasts, buttocks, perineum and lower abdomen. The vulva itself may be mutilated. These may be slashes or deeply penetrating stabs, often multiple and indeed numerous. They may be arranged in a pattern or may be mutilating, as when whole breasts are amputated (Figs 18.4, 18.6).

Decapitation is sometimes performed and ritual acts may be performed, with objects placed in definite sites near the body. The notorious 'Jack the Ripper' murders in London in 1888 exhibited the arrangements of disembowelled organs and this type of mutilation is another feature of some sadistic sexual homicides.[4] Intestine or uterus may be removed, either through abdominal wounds or manually through the vagina. General injuries may be continuous with genital



Figure 18.4 Some homicides have obvious sexual connotations even if there is no genital interference. Most of these stab wounds are centred on a breast.



Figure 18.5 Fresh bleeding and mucosal abrasion on the lower wall of the vagina in a sexual assault associated with fatal head injuries in an elderly female.



Figure 18.6 Stab wounds (arrows) in the vaginal wall of a homicide victim (U = uterus).



Figure 18.7 Laceration of the fourchette after rape in an 8-year-old girl. (Reproduced from Abuso e violenza sessuale by Cattaneo C. *et al.* [2006], by kind Permission of Edi.Ermes s.r.l. ©, Milano.)



Figure 18.8 Two anal fissures in a young woman who reported that she had been anally abused the previous day. (Reproduced from Abuso e violenza sessuale by Cattaneo C. *et al.* [2006], by kind Permission of Edi.Ermes s.r.l. ©, Milano.)

trauma, as in knife or broken bottle wounds of the abdomen and perineum.

Genital injuries

Once the pathologist has examined all the external general injuries, attention should be turned to the perineum. As with the clinical examination of sexual offences, a set routine should be used, as the incorrect order may lose valuable forensic evidence.

The vulva and anus should be inspected externally and laceration, swelling, bruising, bleeding and discharge noted (Fig. 18.9). Any blood or suspected semen stains anywhere on the body or clothing should be sampled either by the pathologist or by the forensic scientist or scene of crime police officer. The pubic hair should be examined for foreign material, hairs, vegetation and dried seminal stains, and samples of hair and combings taken. The hair may be combed using a fine comb with the base of the teeth packed with cotton wool to trap any loose fibres. Dried stains on hair may be cut away and placed in clean folded paper in an envelope or plastic bag for transit to the laboratory. The vulval labia may show clear signs of trauma, especially in children. In forcible rapes, especially in young persons, there may be external signs of perineal tears, with laceration of the margin of the vaginal introitus or anus, sometimes causing a complete rip between the two orifices (Figs 18.7, 18.8, 18.10–18.14).

Caution must be used in interpreting the degree of dilatation of the anus in a dead body, as the sphincter can become patulous and wide open as a normal post-mortem change. Unless the dilatation is very marked, the sole finding of an open anus in the absence of abrasion, bruising, or semen is difficult to sustain as proof of anal penetration. This applies to children as well as adults; in fact, post-mortem dilatation of the anus is particularly noticeable in children.

Once external examination and assessment has been made, samples should be taken for forensic biological testing, for the presence of semen and venereal infection, as well as samples for DNA profiling, which may be able to distinguish between any semen and the vaginal secretions present or any organic or chemical residues left by condoms. If any fluid is running from the vulva or anus, it should be picked up with clean pipettes and preserved in the smallest available tube, to prevent drying from evaporation. Then cotton-wool swabs on sticks (ensuring that those used for semen detection are plain



Figure 18.9 External genitals of a live 8-year-old girl, a victim of repeated sexual abuse by an adult living in the neighbourhood. The lack of intact hymen, reddened and larger than normal orifice of the vagina as well as thickened skin and ulcers perianally (not shown) are in keeping with abuse.

swabs, not those containing albumin or other media) should be used to take the following samples in duplicate by touching gently on to the mucosal surfaces:

- the interior of the vulval labia and around the vaginal orifice
- the margins and interior of the anus
- the mid-vagina, using a speculum or broad handle of a dissecting forceps to part the lower vaginal walls gently to allow the swab to reach the area without contamination from the lower vagina
- the upper vagina, cervix and posterior fornix, again using a spatulate instrument to open the canal to give access to the swab. If more fluid contents are seen higher in the vagina, either now or during the later dissection, they should be recovered by pipette.

After samples are taken, the interior of the anus, vulva and vagina, as far as can be seen from the exterior, should be examined. Lacerations, abrasions, bruises and bleeding may be evaluated, though they can be seen in more detail at dissection. The presence and condition of



Figure 18.10 Extensive bleeding from inner lacerations of the vaginal walls in a fatal rape. Blood is pooling in the posterior part of the vaginal canal. A full autopsy dissection is required, keeping the perineum *en bloc* with the genital tract to display any injuries and to exclude natural disease as a contribution to the bleeding.



Figure 18.11 Rape and anal intercourse of a small girl who was then strangled. The vulva has a slight posterior tear and there is a large vaginal tear internally, the canal being filled with blood. The anus is widely ripped, especially posteriorly. Swabs were positive for semen in both orifices.



Figure 18.12 Bruising of the external genitals (navicular fossa) in a 6-year-old girl. (Reproduced from *Abuso e Violenza Sessuale* by Cattaneo C. *et al.* [2006], by kind permission of Edi.Ermes s.r.l. ©, Milano.)



Figure 18.13 Extensive bruising from fingers during a multiple anal and vaginal rape. Though penetrated by several males in a short space of time, the anus shows no injury.

a hymen is noted, with any evidence of recent tearing. Where injuries are gross, especially in children, fistulae between the vagina and the rectum or even peritoneal cavity may be seen. There may be extrusion of intestine.

Internal examination

The order of the autopsy may be determined by the nature of the death. The fatal injuries, such as strangulation or head injuries, may be dealt with first or the pelvic region may command prime attention. The autopsy incision should be similar to that described for the examination of deaths associated with pregnancy, with an incision circumscribing the perineum, removal of the anterior part of the pelvic bones and the extraction of all the pelvic organs in continuity from ovaries to vulva and anus. This block of tissue is then dissected separately. Before this is done, the bladder should first be emptied of urine (either by catheter or through a small incision in the fundus) and the fluid retained for toxicological analysis, especially for alcohol and drugs that may have been used in drug-facilitated sexual assaults.[5–7]



Figure 18.14 The anus of a girl who has suffered penetration. The sphincter is overdilated, there is slight tearing of the anal margin and some epidermal tags have been abraded from the surface. This degree of dilatation in a dead subject however, should not be used as the sole indication of buggery, as the post-mortem anus can be patulous in quite innocent circumstances.

The vagina should be opened with large scissors, the track of the cut depending on the assessment of any injuries seen on external examination. If there are tears or bruises in the vulva or vagina, the cut should be orientated to avoid them wherever possible; the anus is later dealt with in a similar way. The vagina is laid open to the posterior fornix and all injuries carefully examined and photographed. The cervix and uterus are examined in the same way.

Injuries may be of all types, from mere reddening or swelling to complete disruption of the vaginal canal. This may occur in small children from sheer brutality of penetration, especially if there is gross disproportion between the adult penis and infantile canal. It may also occur from instrumental injury, as it is by no means uncommon for deliberate incised wounds to be made. The author (BK) has seen abdominal knife wounds carried over the pubis into the vagina in a murdered prostitute; another murder-rape was found to have a broken milk bottle high in the vagina, to the potential hazard of the examining fingers. Vaginal injuries, especially by instrument, may continue up into the abdominal cavity, either via the posterior fornix or lateral vaginal walls. This will have been examined through the abdominal autopsy incision before removal of the pelvic organs.

Interpretation of minimal findings

As in clinical forensic practice, there is little difficulty in interpreting gross sexual interference, but problems arise when only minimal evidence is present in a death (traumatic or otherwise) where the circumstances suggest some sexual offence or activity.

It is commonly assumed that sexual assault is invariably associated with physical injury. Sugar *et al.* investigated 819 women aged 15 years and older (mean age 29.3 years) that presented to a hospital emergency department with a complaint of sexual assault, in most cases, within 72 hours after the assault. General body injuries such as bruises and abrasions were seen in 52 per cent of the patients but serious injuries were uncommon and grossly visible genital–anal injuries were seen in a minority of patients (Fig. 18.15).[8]

Unless the pathologist has been trained and has practical experience in investigating cases of sexual abuse, it is advisable to consult an expert when interpreting the findings. Particularly, the nomenclature and classification of signs, which may indicate sexual abuse in children, has been rewritten and updated in recent years.[9,10] One has to be able to identify and recognize congenital anatomic variants that are unspecific, such as deep notches or clefts at the posterior rim of the hymen and to differentiate them from signs that are highly suggestive for abuse, e.g. healed hymenal transections.

Kellogg *et al.* studied the genital anatomy in 36 pregnant adolescents, where 56 per cent (N = 22) of the pregnancies were a result of sexual abuse; however, only two of subjects had genital changes diagnostic of penetrating trauma, whereas the majority of examinations (82 per cent) were normal or suggestive (11 per cent). They concluded that either penetration had not resulted in visible tissue damage or acute injuries had healed completely.[11]

In such cases, the following questions need to be answered, in the light of all the available findings at the end of the autopsy and ancillary investigations:

- Is there any evidence of sexual intercourse at any time – that is, absence of virginity as determined by an intact hymen? This does not exclude sexual activity short of penetration and technically rape can occur from even the minimal passage of a glans between the labia, which does not affect the hymen. Evidence of previous pregnancy, such as abdominal striae, old damage to the cervix and breast changes is almost incontrovertible evidence of previous sexual intercourse.
- Is there evidence of recent sexual intercourse? A recently ruptured hymen, with swelling, a raw unepithelialized edge and bleeding may be found, though admittedly it is relatively uncommon except in children and previously virginal young persons. The labia may be red and inflamed with slight oedema of the vaginal introitus if it is the first episode, or if there is disproportion between an adult man and a young person, even in voluntary sexual connection. The presence of semen on swabs is the best evidence, though with the use of condoms it may be absent. Swabs may be useful even for the collection of condom residues. Literature is still ambiguous concerning the survival and detectability of such residues, which may be the only element indicative of sexual intercourse but they may be worth looking for.[12–18]



Figure 18.15 Fresh, still bleeding laceration in the fossa of vestibule of vagina (fossa navicularis) due to digital and penile penetration.

After vasectomy, though no sperms will be present, chemical and enzyme tests for semen remain positive.

The presence of venereal disease or sexually transmitted diseases (STDs) in general, e.g. chlamydia, condyloma, gonorrhoea, is presumptive evidence of intercourse, though it can be contracted other than by sufficient penile penetration to constitute rape.

If recent intercourse has taken place, was it by force? This may be all too obvious in the presence of gross injury, especially in small children. Where vaginal or rectal tearing has occurred, or where there is obvious abrasion, bruising or laceration of the vulva, anal margins or perineum, then this can hardly be compatible with voluntary intercourse. The possibility of sexually motivated injury without actual penile penetration must be considered when no semen can be recovered, as equally severe damage can be caused by digital or instrumental trauma (Figs 18.16, 18.17). All kinds of foreign objects can be forcibly introduced into the vagina and rectum, and are not infrequently employed by sadistic and perverted killers. The author (BK) has seen candles, bottles, a banana, broken glass and knives introduced into the vagina, and broom-handles and potatoes lying in the rectum.

In a retrospective study of 500 consecutive cases of adult complainants of penile-vaginal rape by a single assailant the majority (77 per cent) of complainants did not sustain any genital injury.[19] Therefore, the lack of any kind of blunt force injury to the genitalia or the body does not necessarily mean the absence of rape.



Figure 18.16 Discharge covered excoriation on the inner aspect of the right labium minus 3 days after digital manipulation.



Figure 18.17 Fresh laceration of the posterior anal circumference from digital rape.

Tests for semen

In countries with sophisticated forensic science or police laboratories, the pathologist will not be called upon to carry out the actual techniques for the detection of seminal fluid. His role is to be a careful collector of the original samples at autopsy and, to some extent, to be able to interpret the results for the benefit of the police and the courts. He should be conversant with the general principles of the tests and aware of any potential shortcomings. In places where forensic science facilities are deficient or their availability may be delayed, the pathologist may have to conduct the more simple tests himself. The detection of semen depends upon the following methods:

- Naked-eye and lens recognition is a screening method, which may identify suspicious stains on clothing, skin and pubic hair. Liquid semen leaking from the vagina or anus may be obvious, though leucorrhoeic vaginal discharge may be mistaken for seminal fluid. Dried seminal stains are stiff and rather silvery, depending upon the nature and colour of any fabric they may be upon. On the skin they flake off readily and can easily be lost if not carefully lifted with a blade or needle into a container. Dried stains on hair should be retrieved by cutting away the clump on which they lie. Suspect smears on skin may be collected by wetting the swab with sterile water and rubbing the stain gently and thereafter repeating the procedure with a dry swab.[20] All material should be examined as soon as possible after collection.

- Examination under ultraviolet light causes seminal stains to fluoresce a bluish-silver, but many other biological fluids and vegetable juices give false positive results. Many detergents, such as washing powders, also produce a confusing background fluorescence. The method is a useful screening process but cannot be used as definitive evidence of the presence of semen. Areas that fluoresce, especially on fabric, should be outlined to identify them for more specific testing. In an experimental setting using scanning electron microscopy (SEM), Gibelli *et al.* were able to detect spermatozoa on badly decomposed material much longer than by light microscopy.[21]
- Enzyme reactions are valuable, and though not absolute proof, are strong presumptive evidence of the presence of semen. They depend on detecting high concentrations of acid phosphatase originating in prostatic secretion. Acid phosphatase activity in semen is 500–1000 times greater than in any other normal bodily fluid. Also, vaginal fluid contains endogenous acid phosphatase showing considerable variation in activity depending on various factors, which complicates the interpretation of the findings. There are several methods of detecting phosphatase, including a rapid commercial 'spot' test, which should not be used as hard evidential proof.
- Immunological methods, where animal antihuman semen sera are set up against extracts of the stain, can only be used by trained laboratory staff. Prostate-specific antigen (PSA, p30) is a glycoprotein produced by the prostatic gland and is found in seminal plasma, male urine and blood, but not in any tissues or fluid of the female body. A positive PSA finding is an indicator of semen regardless of the presence of spermatozoa or elevated acid phosphatase level. Simple and sensitive methods have been developed for analysis of the presence of PSA. However, Lunetta and Sippel cautioned that PSA membrane tests could be misleading when derived from male rectal samples obtained at autopsy. In their test setting 64 per cent of the 39 male cadavers tested positive for the PSA, although the Y STR multiplex revealed no DNA other than that of the subject tested. The false positive PSA reaction was more frequent in the 20 males with advanced decomposition than in the 19 males with no putrefaction signs (70 per cent vs. 58 per cent).[22] Another group of proteins expressed by testicular tissue, semenogelins (SGs), is also used in immunoassay kits to identify semen. Semenogelins may also have a role in some human malignancies, such as prostate cancer.[23] They have been reported to be ectopically expressed in small cell lung carcinomas (SCLC) and in a minority of non-small cell lung carcinomas (NSCLC) and it has been claimed that ectopic expression of this marker protein in individuals affected by cancer could represent a potential source of forensic pitfalls.[24]
- DNA extraction and analysis is the standard technique in the armamentarium of the forensic biologist; this is a remarkable advance, especially in sexual offences, as the previous problems of blood group and enzyme typing caused by the admixture of semen and vaginal secretion can now be solved in many instances. The sensitivity of detection and identification has also been enormously enhanced by amplification techniques, such as polymerase chain reaction (PCR). Y-chromosome short tandem repeat (STR) markers have been successfully used to analyse mixed stains with a male component.[25]
- Until recent years, the only absolute proof accepted by the courts was the demonstration of spermatozoa in stain extracts and it remains the best evidence, though DNA identification is now equally reliable. One modern problem in using spermatozoa retrieval is the widespread and increasing incidence of vasectomy as a method of male contraception, so the seminal fluid contains no sperm; this also occurs naturally in azoospermic men. The phosphatase and some serology tests are unaffected by vasectomy. Fluorescent *in situ* hybridization (FISH) has been suggested as a sensitive and specific test for the detection of male epithelial cells in the post-coital vagina up to 1 week.[26,27] Y-chromosome positive epithelial cells have been identified in vaginal swabs even in cases with no ejaculation.

- Quite recently, some small non-protein coding RNAs, microRNAs (miRNAs) have been reported to be expressed in a tissue-specific manner and may provide an alternative approach to body fluid identification for forensic casework in the future.[28,29]

Homosexual offences

As with heterosexual offences, the cause of death in fatal cases is almost always some form of general trauma, such as strangulation or head injuries. Homosexual activity, however, may be a parallel event; it is a fact that some of the most violent homicides seen by pathologists are among male homosexuals.[30–33] In addition, quite a number of fatal altercations arise because a heterosexual man becomes violent when importuned by a homosexual.

The pathologist's attention will almost always be directed to the anal region of the passive participant, as the other partner or assailant is rarely dead, and any examination will be carried out by a police surgeon or clinical doctor. The examination of the victim follows closely on that for a female subject of rape, in that general injuries are sought first – including the one that caused death – together with any sexually orientated marks such as scratches anywhere on the body, but especially down the back, on the buttocks or on the thighs. Bruising around the anus and in the cleft of the buttocks is significant, especially if discoid finger bruises are seen. The anus should be inspected and the warning given earlier about the degree of dilatation in corpses should be heeded. Though most marked in children, a patulous anus can be seen in any adult post-mortem. An open anus cannot be used in isolation as an index of homosexual penetration. In recent or forcible anal intercourse, especially by a large penis upon a 'virgin' or young person, the margins of the anus may be reddened, sometimes abraded, and occasionally torn, especially in a child. There might be some eversion of the lower rectal mucosa through the sphincter. In gross anal rapes, especially on a young person, there may even be severe perineal tearing. At autopsy, swabs must be taken from the anal margin, and deeper in the anus and rectum. Mouth swabs should also always be taken. The presence of blood or lubricant should also be sought.

The classic description of the chronic passive homosexual has been passed down from textbook to textbook over the years, but is a rarity. The so-called 'funnel anus' is usually an anatomical variant. Some males and females have a deeply set anus as an anatomical variant, sometimes with a bridge of skin dorsally across the cleft of buttocks. This causes the anus to appear as if it was at the bottom of a funnel, but has no significance. The other classic feature was said to be silvery thickening of the skin outside and at the margins of the anus – but this is often due to chronic scratching from pruritus, rather than from prolonged friction during homosexual activities. In life, a lax anus, prolapsed mucosal rim and thickened anal margin may well be genuine signs to the experienced clinical eye, but at autopsy only acute damage and the presence of semen or lubricant is of much evidential value.

References

1 Schlesinger SL, Borbotsina J, O'Neill L. Petechial hemorrhages of the soft palate secondary to fellatio. *Oral Surg Oral Med Oral Pathol* 1975;40(3):376–8.

2 Worsaae N, Wanscher B. Oral injury caused by fellatio. *Acta Derm Venereol* 1978;58(2):187–8.

3 Terezhalmy GT, Riley CK, Moore WS. Oral lesions secondary to fellatio. *Quintessence Int* 2000;31(5):361.

4 Eckert WG. The Whitechapel murders: the case of Jack the Ripper. *Am J Forensic Med Pathol* 1981;2(1):53–60.

5 Jones AW, Holmgren A, Ahlner J. Toxicological analysis of blood and urine samples from female victims of alleged sexual assault. *Clin Toxicol (Phila)* 2012;50(7):555–61.

6 Dinis-Oliveira RJ, Magalhaes T. Forensic toxicology in drug-facilitated sexual assault. *Toxicol Mech Methods* 2013;23(7):471–8.

7 Hagemann CT, *et al.* Ethanol and drug findings in women consulting a Sexual Assault Center – associations with clinical characteristics and suspicions of drug-facilitated sexual assault. *J Forensic Leg Med* 2013;20(6):777–84.

8 Sugar NF, Fine DN, Eckert LO. Physical injury after sexual assault: findings of a large case series. *Am J Obstet Gynecol* 2004;190(1):71–6.

9 Adams JA. Medical evaluation of suspected child sexual abuse. *J Pediatr Adolesc Gynecol* 2004;17(3):191–7.

10 Adams JA. Guidelines for medical care of children evaluated for suspected sexual abuse: an update for 2008. *Curr Opin Obstet Gynecol* 2008;20(5):435–41.

11 Kellogg ND, Menard SW, Santos A. Genital anatomy in pregnant adolescents: 'normal' does not mean 'nothing happened'. *Pediatrics* 2004;113(1 Pt 1):e67–9.

12 Maynard P, *et al.* A protocol for the forensic analysis of condom and personal lubricants found in sexual assault cases. *Forensic Sci Int* 2001;124(2–3):140–56.

13 Burger F, *et al.* Forensic analysis of condom and personal lubricants by capillary electrophoresis. *Talanta* 2005;67(2):368–76.

14 Campbell GP, Gordon AL. Analysis of condom lubricants for forensic casework. *J Forensic Sci* 2007;52(3):630–42.

15 Coyle T, Anwar N. A novel approach to condom lubricant analysis: *in-situ* analysis of swabs by FT-Raman spectroscopy and its effects on DNA analysis. *Sci Justice* 2009;49(1):32–40.

16 Bradshaw R, *et al.* A novel matrix-assisted laser desorption/ionisation mass spectrometry imaging based methodology for the identification of sexual assault suspects. *Rapid Commun Mass Spectrom* 2011;25(3):415–22.

17 Spencer SE, *et al.* Matrix-assisted laser desorption/ionization time-of-flight mass spectrometry profiling of trace constituents of condom lubricants in the presence of biological fluids. *Forensic Sci Int* 2011;207(1–3):19–26.

18 Musah RA, *et al*. Direct analysis in real time mass spectrometry for analysis of sexual assault evidence. *Rapid Commun Mass Spectrom* 2012;26(9):1039–46.
19 McLean I, *et al*. Female genital injuries resulting from consensual and non-consensual vaginal intercourse. *Forensic Sci Int* 2011;204(1–3):27–33.
20 Sweet D, *et al*. An improved method to recover saliva from human skin: the double swab technique. *J Forensic Sci* 1997;42(2):320–2.
21 Gibelli D, *et al*. Persistence of spermatozoa on decomposing human skin: a scanning electron microscopy study. *Int J Legal Med* 2013;127(5):975–9.
22 Lunetta P, Sippel H. Positive prostate-specific antigen (PSA) reaction in post-mortem rectal swabs: a cautionary note. *J Forensic Leg Med* 2009;16(7):397–9.
23 Canacci AM, *et al*. Expression of semenogelins I and II and its prognostic significance in human prostate cancer. *Prostate* 2011;71(10):1108–14.
24 Berti A, *et al*. Expression of seminal vesicle-specific antigen in serum of lung tumor patients. *J Forensic Sci* 2005;50(5):1114–5.
25 Sibille I, *et al*. Y-STR DNA amplification as biological evidence in sexually assaulted female victims with no cytological detection of spermatozoa. *Forensic Sci Int* 2002;125(2–3):212–6.
26 Collins KA, *et al*. Identification of sperm and non-sperm male cells in cervicovaginal smears using fluorescence *in situ* hybridization: applications in alleged sexual assault cases. *J Forensic Sci* 1994;39(6):1347–55.
27 Vandewoestyne M, *et al*. Suspension fluorescence *in situ* hybridization (S-FISH) combined with automatic detection and laser microdissection for STR profiling of male cells in male/female mixtures. *Int J Legal Med* 2009;123(5):441–7.
28 Hanson EK, Lubenow H, Ballantyne J. *Identification of forensically relevant body fluids using a panel of differentially expressed microRNAs.* Anal Biochem, 2009;387(2):303–14.
29 Zubakov D, *et al*. MicroRNA markers for forensic body fluid identification obtained from microarray screening and quantitative RT-PCR confirmation. *Int J Legal Med* 2010; 124(3):217–26.
30 Bell MD, Vila RI. Homicide in homosexual victims: a study of 67 cases from the Broward County, Florida, Medical Examiner's office (1982–1992), with special emphasis on 'overkill'. *Am J Forensic Med Pathol* 1996;17(1):65–9.
31 Taff ML, Boglioli LK. Gay homicides and 'overkill'. *Am J Forensic Med Pathol* 1996;17(4):350–2.
32 Taff ML, Boglioli LK. Gay homicides and 'overkill'. *Am J Forensic Med Pathol* 1997;18(4):411–3.
33 Granados JA, Delgado G. Mortality by homicide in homosexuals: characterization of the cases registered in Mexico between 1995 and 2000. *Am J Forensic Med Pathol* 2008;29(1):43–8.

This page intentionally left blank

CHAPTER 19

Deaths Associated with Pregnancy

- Maternal deaths
- Deaths associated with abortion
- The autopsy in abortion deaths
- Amniotic fluid embolism
- References

Maternal deaths

Though not usually a forensic problem, deaths associated with pregnancy (other than criminal abortions) are a major health problem worldwide; however, these are decreasing from an estimated 536,000 deaths in 2005 to 289,000 in 2013. Identification of the true numbers of maternal deaths is difficult due to differences in medical certification of causes of death. Even in developed countries they are often under-reported and special investigations may be necessary to elicit the true numbers.[1,2]

In Britain, the concern about the persistently high level of maternal mortality led first to major local enquiries into maternal deaths in Scotland, England and Wales in the 1920s and 1930s; from 1952 onwards the Department of Health has had a nationwide on-going 'Confidential Enquiry into Maternal Deaths (CEMD)', now carried out by the Centre for Maternal and Child Enquiries (CMACE), publishing valuable reports at 3-yearly intervals that have helped to clarify both the clinical and pathological aspects of the problem. A recent such investigation in the UK identified 261 maternal deaths in comparison to the 155 deaths reported in the routine civil registration system.[3]

In the *International Statistical Classification of Diseases and Related Health Problems, Tenth Revision*, 1992 (ICD-10), the World Health Organization (WHO) defines *maternal death* as: the death of a woman while pregnant or within 42 days of termination of pregnancy, irrespective of the duration and site of the pregnancy, from any cause related to or aggravated by the pregnancy or its management but not from accidental or incidental causes. *Pregnancy-related death* is an alternative definition included in ICD-10 incorporating maternal deaths during pregnancy, childbirth or the postpartum period due to any, even due to accidental or incidental causes. Definitions of maternal deaths are shown in Table 19.1.

Table 19.1 Definitions of maternal deaths

*Maternal deaths** Deaths of women while pregnant or within 42 days of the end of the pregnancy† from any cause related to or aggravated by the pregnancy or its management, but not from accidental or incidental causes

*Direct** Deaths resulting from obstetric complications of the pregnant state (pregnancy, labour and puerperium), from interventions, omissions, incorrect treatment or from a chain of events resulting from any of the above

*Indirect** Deaths resulting from previous existing disease, or disease that developed during pregnancy and which was not due to direct obstetric causes, but which was aggravated by the physiologic effects of pregnancy

*Late*** Deaths occurring between 42 days and 1 year after abortion, miscarriage or delivery that are due to *Direct* or *Indirect* maternal causes

Fortuitous (coincidental) Deaths from unrelated causes, which happen to occur in pregnancy or the puerperium

*Pregnancy-related deaths*** Deaths occurring in women while pregnant or within 42 days of termination of pregnancy, irrespective of the cause of the death

† This term includes delivery, ectopic pregnancy, miscarriage or termination of pregnancy.

* ICD-9

** ICD-10

Forensic pathological interest in pregnancy revolves on the one hand on sudden unexpected deaths due to direct or indirect natural causes such as thromboembolism, subarachnoid haemorrhage, epilepsy or asthma, and complications of investigative or therapeutic procedures, or on the other hand fortuitous (coincidental) violent deaths as well as around deaths associated with abortion, either criminal or legally induced.

Statistical measures for maternal mortality are: *maternal mortality ratio* (MMR) = number of maternal deaths during a given time period per 100,000 live births during the same time period and *maternal mortality rate* = number of maternal deaths during a given time period per 100,000 women of reproductive age during the same time period.



Figure 19.1 Ruptured tuba in (ectopic) pregnancy. Death due to massive intraperitoneal haemorrhage. (Figure reproduced by kind permission of Professor E. Lignitz.)



Figure 19.2 Fetus and placenta in the abdominal cavity after ruptured tubal (ectopic) pregnancy. Death due to massive intraperitoneal haemorrhage. (Figure reproduced by kind permission of Professor E. Lignitz.)

The pathologist has an important role in furthering the understanding of the causes of death in pregnancy and after childbirth. A good autopsy is essential, with full histological examination and other ancillary investigations where necessary. Only in this way can the full range of causes of death be recognized, especially amniotic fluid embolism, which is a histological diagnosis.

To give an example of the range of fatal conditions that occur in association with pregnancy, the following causes are taken from CMACE,[3] the figures referring to death during pregnancy and within 6 weeks of parturition in the years 2006–2008. Altogether 261 deaths were reported to or identified by the enquiry in the UK during that period. Of the 261, there were 107 (41 per cent) direct and 154 (59 per cent) indirect deaths. The number of underlying causes of death of the direct maternal deaths is shown in Table 19.2 (Figs 19.1, 19.2).

The term 'therapeutic abortion' is used in many countries, including Britain, where there is no abortion on request, as there is in the majority of developed countries (Table 19.3).[4] The description 'legal termination of pregnancy' is a wider definition for all but illegal (that is, criminal) abortions. The autopsy investigation of deaths from legal abortions has much in common with that into fatalities associated with surgical and anaesthetic procedures.

Table 19.2 Number of direct maternal deaths by cause, UK 2006–2008

Cause of death	n	Rates per 100,000 maternities
Sepsis*	26	1.13
Pre-eclampsia and eclampsia	19	0.83
Thrombosis and thromboembolism	18	0.79
Amniotic fluid embolism	13	0.57
Early pregnancy deaths**	11	0.48
Haemorrhage	9	0.39
Anaesthetic	7	0.31
Fatty liver	3	0.13
All direct	107	4.67

* Including early pregnancy deaths as the result of sepsis.
** Ectopic pregnancy, spontaneous miscarriage or legal termination of pregnancy.
Source: Cantwell R, *et al.*[3]

Table 19.3 Grounds on which abortion is permitted (percentage of countries)

	To save the woman's life	To preserve physical health	To preserve mental health	Rape or incest	Fetal impairment	Economic or social reasons	On request
Developed countries	96	88	86	86	86	82	71
Developing countries	97	61	58	39	38	20	16

Source: United Nations.[4]

Deaths associated with abortion

Worldwide, an estimated 42 million abortions were induced in 2003 of which about 20 million were unsafe; close to 70 000 women were estimated to have died due to unsafe abortion in 2005.[5] The WHO defines unsafe abortion as a procedure for terminating an unintended pregnancy carried out either by persons lacking the necessary skills or in an environment that does not conform to minimal medical standards, or both.[6]

An overview of grounds on which abortion is permitted is shown in Table 19.3. The overwhelming majority of countries either explicitly permit abortion to be performed when a pregnancy threatens a mother's life or allow it under the general criminal law principle of necessity. Exceptions include Chile, El Salvador, the Holy See, Malta and Nicaragua, all of which have provisions restricting the performance of abortion.[4] Even in those states where legal termination is possible, criminal abortions are still carried out, albeit on a small scale. The reasons for this survival are varied, but are either because of restrictive grounds for legally available termination or to some sections of society that do not wish to avail themselves of the legal provisions. Whatever the cause, criminal abortion is associated with a considerable risk of both morbidity and mortality, especially in countries with a lower level of medical and social care.

Legal termination of pregnancy

When carried out with proper facilities, legal abortion has an extremely low mortality rate, 0.6 per 100,000 legal induced abortions in the USA in 1997,[7] being less than the mean death rate associated with pregnancy. The methods for induced abortion vary depending on the gestational age as the risk of abortion increases with the duration of the pregnancy; furthermore, there is great regional variation of practices worldwide.

Medical methods

Early induction methods comprised various compounds such as hypertonic saline, urea and naturally occurring prostaglandins ($PF2_{\alpha}$ and PGE_2) or prostaglandin analogues such as Carboprost (15-methyl $PGF2_{\alpha}$) that were injected into the amniotic sac or through a catheter into the extra-amniotic space to stimulate uterine contraction resulting in the expulsion of the fetus and placenta. Complications reported after intra-amniotic use of hypertonic saline included:[8]

- hypernatraemia;
- blood coagulation disorders;
- haemorrhage;
- infection;
- cervical damage.

Invasive administration routes became gradually obsolete due to the invention of PG analogues that could be administered vaginally. Presently, the WHO-recommended medical abortion method is the use of mifepristone (also known as RU 486), an antiprogestin that softens the cervix and increases uterine sensitivity to prostaglandins, followed by repeated administration of PG analogues either gemeprost (16, 16-dimethyl-trans-Δ^2-PGE_1 methyl ester) or misoprostol (synthetic PGE_1 analogue). Three fatal complications have been associated with mifepriston-induced abortion in the United States and one in Canada by November 2004, 4 years after the drug had been approved for use: one due to a ruptured ectopic pregnancy and, including the one in Canada, three due to septic shock. By July 2005 the USA Food and Drug Administration (FDA) was aware of altogether four USA deaths due to sepsis.[9] Characteristic to these deaths was that all the four women were healthy and developed endometritis and toxic shock syndrome (TSS) associated with *Clostridium sordellii* within 1 week after apparently successful medically-induced abortions. Clinical findings included tachycardia, hypotension, oedema, haemoconcentration, profound leucocytosis and absence of fever.[10] So far, TSS from *C. sordellii* has not been observed in Europe in spite of the increasing rate of the use of medical abortion in many countries, e.g. most abortions in Sweden and Finland in the second trimester are performed medically.[11,12]

Surgical methods

The most common procedure in the first trimester in the USA is the vacuum aspiration or suction curettage. The most common surgical method in the second trimester is dilatation and evacuation (D&E) involving dilatation of the cervical canal, evacuation of the amniotic fluid with vacuum aspiration and extraction of the fetus and placenta using forceps. The complications with potential risk of death include haemorrhage, infection, disseminated intravascular coagulation (DIC), embolism and uterine perforation as well as mishaps associated with anaesthesia or other iatrogenic causes.

Of the traditional surgical methods hysterotomy/hysterectomy has the highest mortality rate and there is rarely indication for this procedure as the primary method for abortion and it should no longer be used.[13,14]

Death from illegal abortion

This has a much wider range of causes. The risks vary according to the skill, experience and facilities of the abortionist. When this is carried out by a doctor with aseptic and antiseptic methods, together with antibiotic cover if needed, the risk may be small compared with the crude methods of a layperson using makeshift instruments. The most common methods together with the associated dangers to health and life are as follows (Fig. 19.3).

Instrumental interference

The intention is to disturb the pregnancy sac so that, once damaged, it will be expelled by uterine contractions. This usually consists of dilatation of the cervical canal, which in itself also tends to dislodge the pregnancy. All manner of instruments have been used, from surgical dilators to bicycle spokes. A favourite in the hands of paramedical abortionists is the bougie or stiff catheter. When used by doctors or nurses with anatomical knowledge and sterile instruments, the risk is small, but laypersons often have no idea of the relationship of uterus to vagina. The instrument is then often pushed into the posterior fornix in the misguided belief that the cervix lies axially with the vagina. The vault of the vagina can be perforated and the instrument may even be passed through coils of intestine as far as the liver. Penetration of the lower or mid-vagina can also occur. If the cervix is entered, then the canal may be punctured and the instrument emerges through the side.

The external os may be badly injured by repeated, clumsy attempts to introduce too thick an object into the undilated canal. If successfully passed into the cavity of the uterus, it may be pushed right up through the fundus, again to damage the contents of the peritoneal cavity.

The dangers of such instrumentation are bleeding and infection. Perforation of the wall of vagina or uterus


Damage to viscera
Fundal perforation (haemorrhage and peritonitis)
Sepsis to blood stream
Air embolism
Infected endometrium and placenta
Pelvic thrombo -phlebitis
Toxic effects of soap, disinfectants, permanganate and other chemicals
Uterine perforation
Cervical perforation (haemorrhage)
Cervical shock (sudden cardiac arrest)
Posterior fornix perforation (haemorrhage)
Vaginal perforation (haemorrhage)
Instrumental interference

Figure 19.3 Dangers of a criminal abortion.

may cause severe bleeding, which may be internal or external. Sepsis can supervene in the peritoneal cavity or pelvic tissues either directly from a dirty instrument or from transfer of vaginal, skin or bowel organisms.

Another less common danger of the use of instruments (including syringes) is cervical shock. The mere act of dilating the cervix with an instrument in an unanaesthetized patient may trigger a vagal reflex, the efferent pathway being via the parasympathetic nervous system, causing a cardiac arrest. This is known to be a more potent mechanism in states of fear, apprehension and nervous tension, which obviously will apply to many candidates for a criminal abortion.

Insufflation of air

In Europe, this is becoming more of historical interest, but occasional cases still occur. A rubber pump, usually a Higginson enema syringe, is used to introduce fluid under pressure into the cavity of the uterus. This strips the chorionic sac from the wall of the uterus, exposing the placental bed. If sufficient detachment is achieved, then abortion will occur. It was formerly a popular method of abortion, both by women themselves and by abortionists. The main danger – apart from the usual risks of bleeding and infection from damage to the tissues by the stiff nozzle – was air embolism, and in the first half of this century it was a major cause of abortion deaths. The intention was to introduce a fluid such as water–soap solution or disinfectant through the cervix by means of the syringe nozzle, the other end, which carried a one-way valve, being dipped in a receptacle of the fluid.

As the level in the receptacle dropped, the inlet tube rose above the surface and the syringe began to inject air instead of fluid, often as soapy foam. In addition to this danger, unless the bulb of the pump was primed with fluid before use, the first ejection would be the appreciable volume of air contained in the empty syringe, which in itself was enough to cause a fatal embolism. Under the considerable pressure available from the instrument (as much as 28 cm of mercury),[15] this air was forced into the exposed vascular channels of the placental bed and from there into venous sinuses and pelvic veins to cause cardiac embolism.

Though this occurred almost immediately in most instances, some delay was possible – perhaps because contained air was further squeezed by contraction of the uterus. Some victims were able to leave the premises of an abortionist and survive for up to 2 hours or more before the embolism occurred (Fig. 19.6).[16] The addition of various substances, such as phenol, formalin, alcohol and turpentine, to the fluid introduced a toxic element, and in some cases these fluids were extruded into the peritoneal cavity through the uterine tubes, causing a chemical peritonitis.

Dilatation of the cervix

Another crude method was to introduce a 'tent' into the cervical canal. This was a strip of substance that absorbed water and became greatly enlarged, such as *Laminaria digitale* or slippery elm (*Ulmus fulva Michx*). These vegetable materials are hard and compact when dehydrated, so that a strip about 3–8 cm long could be slid into the cervix. When water was absorbed from the surrounding tissues, the cervical canal became widely dilated and abortion might take place. The risks were perforation of the cervix and also infection, especially if the strip tore into the tissues. The substances used, often crude vegetable material, could be the source of infecting micro-organisms including anaerobes.

Physical violence

Females anxious to lose their pregnancy have resorted to extremes of physical activity and even violence in efforts to dislodge the fetus. Frenzied exercise, horse riding and severe purging with laxatives were usually ineffective, and some unfortunate people went on to seek violent treatment from husbands or consorts. Punching and kicking of the abdomen were most common, and death from visceral rupture, such as liver, spleen or intestine, has been reported. Ironically, the uterine contents were usually undisturbed.

Syringe aspiration

The suction method most often used in therapeutic abortion has also come to be used for illegal operations, mainly by medical or nursing personnel. A large syringe attached to a catheter or length of plastic tubing can produce suction within the uterus sufficient to rupture the chorionic sac and precipitate abortion. The method is safe as long as aseptic methods are used, though, if evacuation is incomplete, some products of conception may be left behind that can form a nidus for infection.

Use of drugs and chemicals

A wide variety of substances, applied locally or taken by mouth, have been used since time immemorial to induce miscarriage. Some have a sound pharmacological basis, others are dangerous, and yet more lie in the realms of folk medicine. Substances applied locally include phenols and Lysol, mercuric chloride, potassium permanganate, arsenic, formaldehyde and oxalic acid. All have their own dangers, both from local corrosion and systemic effects if absorbed. A necrotic pseudomembrane may form in the vagina and severe damage to the cervix may also ensue.

Potassium permanganate was a substance that appeared during the Second World War and its use in abortion persisted for some years, 650 cases being reported up to 1959, though only a few were fatal. It can cause local necrosis in the vagina and, if absorbed, can have fatal systemic effects including renal failure. Permanganate can cause profuse vaginal bleeding from necrosis, which may give the impression that abortion is threatened and lead an unsuspecting doctor to carry out a curettage. 'Utus paste' is a mixture of soap, myrrh resinoid and potassium iodide, and was used earlier in the century for legitimate abortions, but soon became popular with the criminal abortionist. Another similar product containing elemental iodine, is 'Interruptin'; both were used for late abortions and the induction of labour when the fetus was dead. These pastes are squeezed into the cervical canal through an applicator and the halogen component acts as an irritant, which causes eventual expulsion of the chorionic sac. Used medically, they are relatively safe,[17,18] but fatalities can occur from air or fat embolism or from the toxic effects of absorption.

Substances taken by mouth or injection are legion. The old classification into 'ecbolics' and 'emmenagogues' is now quite redundant and most of the lists of substances are of historical interest only, as their efficacy is either nil or the dose needed to produce abortion is perilously near the fatal level. These include pennyroyal, tansy, rue, savin, laburnum, colocynth, aloes, castor oil, nutmeg, hellebore, cantharides, cotton root, wintergreen and turpentine. Many of these may cause purging, gastrointestinal irritation and general illness if taken in quantity, but have no specific action whatsoever on the uterus. There are other substances that have more chance of causing uterine contractions, though many of them are effective only on a late pregnancy, not at the usual time of 1–3 months when most abortions are sought.

Quinine can be dangerous, as the dosage required for any effect on the uterus is likely to cause cinchonism. Ergometrine has been known from ancient times to lead to abortion, though like most drugs its effectiveness is greater later in pregnancy. Excess dosage may cause peripheral vascular spasm and gangrene. Its availability to doctors and midwives is similar to pituitary extract, oestrogens, and – more recently – PGs. Heavy metals, particularly lead, were used for abortion in the past. Plasters coated with a lead compound 'diachylon' were scraped to recover the metallic substances and ingested. Though abortion sometimes occurred, illness and death from acute and subacute lead poisoning was more common; this method has also become of historical interest only. It has been well said that most substances that are successful in killing the fetus are likely to kill the mother as well.

A wide variety of medical substances have been used for abortion, including aminopterin, steroids, antimitotic drugs, such as vincristine and ergocornine, and other cytotoxic drugs used in malignant diseases. Even monoamine oxidase inhibitors have been reported as abortifacients. In all these, the autopsy findings in fatal cases will be non-specific or negative, and the history and toxicology provide virtually all the available evidence.

Intrauterine infection

Whatever method is used to evacuate the uterus, the risk of haemorrhage or sepsis is always present. Where an instrument, tent or syringe is used, any remaining fragments of placenta or other products of conception may form a substrate for infection. The organisms involved in sepsis are varied, the most dangerous being non-haemolytic streptococci and *Clostridium perfringens*, though coliforms and staphylococci may also be responsible (Figs 19.4, 19.5).

The uterus becomes swollen, spongy and discoloured. The serosal surface seen at autopsy may be brownish – especially in clostridial infections – and the endometrium may be ragged, foul-smelling and even purulent. Signs of septicaemia may develop with an enlarged, soft spleen, prominent lymph nodes and



Figure 19.4 Autopsy appearances of a septic uterus following instrumental attempts at abortion.



Figure 19.5 Septic, necrotic uterus following an instrumental criminal abortion. The endometrium, containing some retained products of conception, is chocolate brown, and foul-smelling, the predominant organism on culture being *Clostridium perfringens*.



Figure 19.6 Burns from a hot-water bottle on the inner side of the upper thigh in an attempt to resuscitate the victim of a criminal abortion who died from air embolism.

hepatorenal failure. The kidneys may show bilateral cortical necrosis in extreme cases. In clostridial septicaemias there may be a characteristic bronze colouration of the skin. This may have a mottled or 'raindrop' appearance.

The autopsy in abortion deaths

Where a death in pregnancy or the puerperium occurs, every effort should be made to obtain an autopsy, even if the death does not fall within the usual category of death reportable for medico-legal investigation. National guidelines may apply; for instance, the Royal College of Pathologists in the UK, has published Guidelines on Autopsy Practice and a set of standardized best practice scenarios to cover specific autopsy situations including maternal death. When a criminal abortion is suspected, then virtually every jurisdiction will require necropsy.

The usual full autopsy is performed, but a number of additional measures are required, varied to suit the particular circumstances. The fullest possible history is required and, where the death has taken place under medical care, a prior discussion with the clinician is vital. A careful external examination must be carried out, noting especially:

- Abnormal colouration of the skin, such as in the bronzing of clostridial septicaemia and the jaundice of liver damage.
- Signs and duration of pregnancy, such as abdominal swelling and breast changes.
- Signs of injury, including bruising or abrasion of the vulva from instrumentation, and vaginal bleeding.
- The vagina should be examined for signs of recent or current pregnancy, and attempted or successful recent abortion. Any fluid should be removed by pipette and sent for toxicology. A swab should be taken for microbiological culture.
- Where any possibility of air embolism is considered, pre-autopsy radiology of the chest and abdomen must be performed. Some pathologists would consider this obligatory in any death associated with pregnancy, as it is the best method of detecting air embolism by visualizing air bubbles in the heart, great veins in the thorax, inferior vena cava, peritoneal cavity and – possibly – pelvic veins. In the few centres where magnetic resonance imaging (MRI) or computed tomography (CT) is available for autopsy material, this may greatly increase the chance of detecting air in the vessels.

Where radiology is not possible, air must be sought by dissection methods, which are not so reliable. The thorax is opened carefully, making sure that removal of the costal cartilages and sternum does not damage the underlying mediastinum or open any of the veins at the thoracic inlet. The cardiovascular system is first examined for the presence of air. The classic method, discussed elsewhere in this book is to open the heart chambers *in situ* under water poured into the pericardial sac. Escaping bubbles are then said to be indicative of air embolism, though the technique is by no means as reliable as past authors have claimed. In fact, if the post-mortem interval is short, in terms of a few hours, then any fatal air embolism will almost always be quite apparent from the frothy contents of the right ventricle when it is opened in the usual way. Appreciable delay allows absorption of air, as can be proved by the failure to find air in the heart on dissection, even after radiology has clearly indicated its presence. Of course, where any degree of decomposition has set in, which may be on the first day after death in hot countries, gases of putrefaction completely negate any chances of proving air embolism.

Before the organs are disturbed, the great veins of the abdomen should be inspected for bubbles, then the pelvic veins. The uterus itself may be crepitant and bubbles may be seen under the serosal surface or even under the parietal peritoneum of the pelvis. On opening the uterus, gas bubbles may be evident in the wall or placental bed, but this is later in the examination. The usual instructions in most forensic textbooks for opening the head first, carefully removing the calvarium and minutely inspecting the cerebral veins for air bubbles, can be totally disregarded, as this is yet another example of forensic mythology repeated from one book to the next, without critical evaluation. As discussed in Chapter 13, air embolism cannot occur in the cerebral veins and it was proved many years ago that air bubbles in those veins are artefacts caused by removing the calvarium.

The thorax and upper abdomen should be examined as usual, with particular attention to signs of infection. Blood cultures and peritoneal and other swabs should be taken as indicated by the circumstances.

The pelvic organs should be removed *en bloc*, as in the examination of fatal rape victims. The lower end of the abdominal incision is carried on each side around the labia and into the cleft of the buttocks to meet beyond the anus. The dissection is taken along the superior pubic rami, which are then carefully sawn through a few centimetres laterally to the symphysis on each side, the cuts being continued down through the inferior rami. The central block of bone is removed and the perineal incision dissected deeply, so that the vagina, rectum and anus, uterus, tubes and ovaries can be lifted out in continuity, and removed for detailed dissection. The vagina is carefully opened along one side to avoid over-running any midline injuries. Abrasions, bruises, lacerations and any foreign material are noted in the vagina, and any samples kept for chemical or microbiological testing. Any abnormality of the cervix is noted, especially instrument marks, such as forceps or volsellum teeth. The state of dilatation of the cervical canal is noted and the uterus opened, again keeping away from the midline if possible. The colour, size and texture of the uterus is noted, and the state of the interior is naturally vital. If the chorionic sac is still present, its integrity and the attachment to the deciduae are noted. If a fetus is present, this is examined separately for maturity and damage.

If no fetus is present, products of conception are sought and the state of the placental bed noted. Infection, bleeding and air crepitancy are all sought, and the appropriate ancillary investigations made. The tubes are then opened and any foreign fluid collected. The ovaries are examined and the state of any corpus luteum recorded. Finally, extensive histological specimens are taken from all organs and special stains employed where necessary, such as those for seeking amniotic squames in lungs and other organs. Blood, urine, liver and stomach contents are retained for analysis, should this be indicated.

Amniotic fluid embolism

Some deaths associated with childbirth or pregnancy are caused by the entry of amniotic fluid into the maternal circulation. The fluid contains fetal squames, lanugo, lipoid from the vernix, meconium, cells from chorion and amnion and other cellular detritus. The solid elements are usually impacted in the lung capillaries, but rarely have been found in the systemic circulation, including embolization into the kidney, liver and brain. In addition to the solids, the actual fluid itself (which is naturally undetectable histologically) is blamed for the ‘allergic’ response that may cause such profound collapse, leading to death. Amniotic fluid embolism is also one of the most potent causes of disseminated intravascular coagulopathy (DIC), mentioned also in Chapter 13.

A variety of causes exist apart from the pelvic trauma of parturition, including rupture of the uterus, but instrumental interference late in pregnancy may also allow opening of the sinuses in the placental bed with consequent escape of amniotic fluid. Further details of the causes and mechanisms must be sought in obstetric works, but from the autopsy point of view, it is important both to bear the possibility in mind and to have techniques that will reveal the



Figure 19.7 Squamous cells in a pulmonary artery in amniotic fluid embolism. Phloxin-tartrazine (A) versus cytokeratin-stain (B). (Lung sample courtesy of Professor A. Sajantila, Hjelt Institute, Department of Forensic Medicine, University of Helsinki.)

embolism after autopsy. The diagnosis is histological and depends upon identifying the squames detached from the fetal epidermis, which float freely in amniotic fluid. These can be seen in ordinary haematoxylin and eosin stained sections of the lung, but are much better visualized and a greater yield obtained if special staining methods are used (Fig. 19.7). Fibrin deposition in many organs may occur as a result of the DIC and careful search for this must be made, using fibrin stains. Immunohistochemical techniques have also been used in the lung sections to demonstrate human keratin-, meconium- and amniotic fluid-derived mucin as well as isolated trophoblastic cells in deaths due to amniotic fluid embolism (AFE) syndrome.[19–23]

References

1. World Health Organization. *Maternal Mortality in 2005: Estimates Developed by WHO, UNICEF, UNFPA, and the World Bank: WHO, UNICEF, UNFPA, and the World Bank*. Geneva: World Health Organization, 2007.
2. World Health Organization. *World Health Statistics 2014*. Geneva: World Health Organization, 2014, p. 177.
3. Cantwell R, *et al*. *Saving Mothers' Lives: Reviewing maternal deaths to make motherhood safer: 2006–2008. The Eighth Report of the Confidential Enquiries into Maternal Deaths in the United Kingdom*. *BJOG* 2011;118 Suppl 1:1–203.
4. United Nations. *World Abortion Policies 2011*. Department of Economic and Social Affairs, Population Division. United Nations publication, Sales No. E.13.XIII.2). Data available online at www.unpopulation.org.
5. Åhman E, Shah I. *Unsafe Abortion: Global and Regional Estimates of the Incidence of Unsafe Abortion and Associated Mortality in 2003*. P. Butler (ed). Geneva, 2007.
6. World Health Organization (WHO). *The Prevention and Management of Unsafe Abortion: Report of a Technical Working Group*. Geneva: WHO, 1992.
7. Bartlett LA, *et al*. Risk factors for legal induced abortion-related mortality in the United States. *Obstet Gynecol* 2004;103(4):729–37.
8. Bygdeman M, Gemzell-Danielsson K. An historical overview of second trimester abortion methods. *Reprod Health Matters* 2008; 16(31 Suppl):196–204.
9. Greene MF. Fatal infections associated with mifepristone-induced abortion. *N Engl J Med* 2005;353(22):2317–8.
10. Fischer M, *et al*. Fatal toxic shock syndrome associated with *Clostridium sordellii* after medical abortion. *N Engl J Med* 2005; 353(22):2352–60.
11. Lohr PA, Hayes JL, Gemzell-Danielsson K. Surgical versus medical methods for second trimester induced abortion. *Cochrane Database Syst Rev* 2008(1):CD006714.
12. STAKES. *Induced abortions and sterilisations 2007*. Helsinki: Official Statistics of Finland, 2008.
13. Binkin NJ. Trends in induced legal abortion morbidity and mortality. *Clin Obstet Gynaecol* 1986;13(1):83–93.
14. Stubblefield PG, Carr-Ellis S, Borgatta L. Methods for induced abortion. *Obstet Gynecol* 2004;104(1):174–85.
15. Teare D. Death in criminal abortion. *Med Legal J* 1958;26:132–4.
16. Simpson K. Air embolism. *Med Legal J* 1951;19:81–5.
17. Barns H. Therapeutic abortion by means of soft soap pastes. *Lancet* 1967;ii:825.
18. Berthelsen H, Ostervaard E. Techniques and complications in therapeutic abortion. *Dan Med Bull* 1959;6:105–10.
19. Fineschi V, *et al*. The diagnosis of amniotic fluid embolism: an immunohistochemical study for the quantification of pulmonary mast cell tryptase. *Int J Legal Med* 1998;111(5):238–43.
20. Fineschi V, *et al*. Complement C3a expression and tryptase degranulation as promising histopathological tests for diagnosing fatal amniotic fluid embolism. *Virchows Arch* 2009;454(3):283–90.
21. Lunetta P, Penttila A. Immunohistochemical identification of syncytiotrophoblastic cells and megakaryocytes in pulmonary vessels in a fatal case of amniotic fluid embolism. *Int J Legal Med* 1996;108(4):210–4.
22. Sinicina I, *et al*. Forensic aspects of post-mortem histological detection of amniotic fluid embolism. *Int J Legal Med* 2010; 124(1):55–62.
23. Wang J, *et al*. Evaluation of specific marker CK13 and CK10/13 combined with APM staining for the diagnosis of amniotic fluid embolism and aspiration. *Forensic Sci Int* 2014;238:108–12.

This page intentionally left blank

CHAPTER 20

Child Homicide

- Incidence of child homicides
- Stillbirth
- Functions of the pathologist in infanticide
- Definition of 'live birth' and 'separate existence'
- Concealment of birth
- The autopsy on a suspicious death of a newborn infant
- Infanticide by omission to offer proper care
- Proof of a separate existence
- Estimation of maturity
- References

Historically, child killing has by no means always been a crime, and has been practised as child sacrifice, a method of population control or as a social and economic necessity since the dawn of humanity.[1–4] The cultural and socioeconomic setting is still relevant today and reverberates through phenomena such as son-preference and sex-selective abortions, particularly in South Asian countries (Box 20.1).[5,6]

Incidence of child homicides

It is difficult to get a reliable picture of the true incidence of child homicide worldwide and many are generally believed to remain undetected or become wrongly categorized.[7] There are few recent surveys and to make it more complicated, the terminology and definitions used in various jurisdictions are not uniform. For example, *neonaticide* is usually defined in the literature as the homicide of a child within the first 24 hours of life, whereas in the USA, because of the Federal Bureau of Investigations-Uniform Crime Reporting System (FBI-UCR) rules, it is defined as the homicide of a person aged 1 week or less. Using these criteria the average annual neonaticide rate in the period 1976 to 1979 in the USA was 1.3 per 100,000 live births and the rate for infanticide (>1 week–<1 year) 4.3 per 100,000 infants.[8] Another study based on World Health Organization (WHO) data compared death rates (1974) between 23 developed countries, reporting a mean death rate of 2.3 ± 2.6 per 100,000 live births for children less than 1 year of age.[9] A more recent study from the USA comprising 34 deaths of newborns (up to 4 days of age), covering the 16-year period 1985–2000 in North Carolina, gave a rate of 2.1 per 100,000.[10]

A total of 292 child homicides (<14 years) were reported during the 25-year period, 1970–1994 in Finland. Excluding 57 cases that even after a more detailed study had remained undetermined, that left 235 cases and gave an annual rate of 1.9 (per million total population). Fifty-six of the children were neonaticides.[11] Another study assessing 47 suspected neonaticides in Finland between 1980 and 2000 reported a rate of 0.07–0.18 per 100,000 live births per year.[12] A comparison of all *filicides* registered in Austria and Finland between 1995 and 2005 found 86 victims in Austria and 66 in Finland equalling 5.2 and 5.9 per 100,000 inhabitants respectively.[13]

Multiple, repeated infanticides have been described in Japan[14,15] and Finland,[12] whereas, so far, reports from other countries have been rare. Resnick's review of the

Box 20.1 Definitions

- Filicide – deliberate killing of one's own child
- Infanticide – child homicide; in many jurisdictions statutory offence when committed by mother with specific infanticide provisions with more lenient penalties than those for homicide.[19] The time following childbirth is mostly limited to 12 months. An exception is New Zealand, where the time can be much longer, possibly up to 10 years[20]
- Neonaticide – a subgroup of infanticide usually defined as homicide of a newborn child within the first 24 hours of life

world literature 1751–1968 found one case in France and one in Germany.[16] The first attempted repetition of neonaticide in Britain was reported in 1985.[17] Recently (July–August, 2010) reports published in the news media suggest, however, that the phenomenon may be more common than has been assumed in the scientific literature. According to BBC News a French nursing assistant aged 45 and mother of two grown-up daughters has been arrested after admitting killing eight of her own newborn babies between 1989 and 2006.[18] The same account listed three other multiple infanticides that had been detected in France (one of seven infants in Limousin 1984; another of four infants in Alsace in 2003, of which at least three had the same parentage, and a third one of six infants in Lower Normandy 2010). Quite recently (June 2014) the news media in Finland reported that five more or less decomposed infant bodies had been found in the cellar of an apartment house. A 35-year-old female admitted having given birth to them all in the course of the last 5–10 years. She further claimed that all had been home births and that the infants were born dead. She was arrested under suspicion of infanticide and the police investigation is in progress.

The pathologist, however, has to deal with the practicalities of infanticide, as they exist today. Though legal definitions vary among different countries, the medical concept of infanticide is uniform, being the deliberate killing of a newborn infant by the mother. In England and Wales, infanticide was not accepted as a legal entity in the criminal law until 1922. Before then all child killing was murder – and the convicted mother was liable to be sentenced to death until the Infanticide Act, which was re-enacted in a more satisfactory form in 1938, see account by Kellett.[2]

In many other countries there is no specific infanticide legislation – even Scotland did not adopt the English statute, having a separate crime of ‘child murder’, but long before 1922 that country had held a more enlightened attitude towards the mentally stressed mother. In Austria, Colombia, Finland, Greece, India, Korea, The Philippines, and Turkey, specific infanticide provisions lead to reduced culpability for homicide; in others, such as Italy, Norway, and Switzerland, child homicide is a specific and less culpable form of homicide.[20,21] In Luxembourg, the killing of a newborn child by the mother, at the moment of birth or immediately thereafter, qualifies as infanticide and, depending on the circumstances, can be punished for murder or manslaughter. However, the mother who has committed this crime on her illegitimate child shall be punished by imprisonment of 10–15 years.[19]

This book generally avoids territorial legal comparisons, but the foregoing facts serve to illustrate that the killing of a young child by the mother is a well-recognized medical and psychiatric phenomenon that distinguishes it from other types of homicide. There is a profound responsibility laid upon the forensic pathologist called to examine such infants, to investigate the death with particular caution.

The substance of infanticide that has relevance to the pathologist is well set out in the English Infanticide Act 1938 (Section 1):

> “Where a woman by any wilful act or omission causes the death of a child being under the age of 12 months, but at the time the balance of her mind was disturbed by having given birth or the effect of lactation, she may be dealt with as if she had committed manslaughter.”[22]

It should be noted that:

- Only the mother can benefit from this alternative to murder – not the father or any other person.
- The child has to be less than 1 year old, though in fact the majority of infanticides occur within hours or even minutes of birth.
- It has to be a ‘child’ – that is, a person with a separate existence living independently fully outside the mother’s body.
- It must have died because of a wilful (deliberate) act of omission or commission.

All these provisos have an effect on the pathologist’s task. Even in those jurisdictions where there is no formal infanticide legislation, there is usually recognition that the acts of a mother soon after childbirth, often in adverse conditions, are different from common murder.

Stillbirth

To clarify later definitions, a stillbirth is defined in English law and, from a medical point of view no doubt has a broadly similar description in other jurisdictions. In England and Wales, a baby is stillborn if after 24 weeks’ gestation, ‘it did not at any time after being completely expelled from its mother, breathe or show any other sign of life’.

Theoretically, this is a medically unsatisfactory definition, as it could be alive when its head was born but die before completion of expulsion, and therefore legally be a stillbirth. However, in practice this would be rare, as most stillbirths either die *in utero* or during the earlier stages of parturition. Fetal losses before the legally defined gestation duration are defined as miscarriages. Stillbirths are not reported in WHO's routine mortality data and therefore there are no reliable global statistics as only an estimated 2 per cent of all stillbirths are counted through vital registration.[23] There is great regional variation in the rates of preterm births and they appear to be higher in the least developed regions.[24] Recent rates of pre-term births have been published from Australia, 6.6 per cent; Finland, 5.2 per cent; Israel, 9.4 per cent; Japan, 5.2 per cent; UK, 6.0 per cent; USA (all races), 12.7 per cent; Sweden, 5.6 per cent; Chile, 6.0 per cent; Bangladesh, 16.5 per cent; Gambia, 12.3 per cent; and Nepal, (rural) 23.1 per cent. For relevant literature see Lawn *et al.* [23]

Functions of the pathologist in infanticide

To assist in identifying the mother, if she is unknown

Newborn infants found dead (especially in clandestine circumstances) are not necessarily the victims of infanticide. Those stillborn or dying naturally or from unintentional lack of care may be hidden or abandoned, a minor crime in Britain called 'concealment of birth'. The autopsy, as well as artefacts discovered with the body, such as bags, blankets and newspapers can assist to a greater or lesser degree in the police search for the mother.

The apparent ethnic group of the child will be disclosed and DNA profiling can be performed, which will usually assist by eliminating or helping to confirm the consanguinity of any putative mother. The appearance of the cut end and any ligation of the umbilical cord (see below) may help to decide whether the birth was one where medical, nursing or only amateur attention was available. In spite of these clues, most abandoned newborn corpses fail to be linked to the mother, delay in discovery making both identification and evidence of live birth unattainable.

To estimate the maturity of the child

Though any newborn infant, whatever the length of gestation, can be the victim of infanticide if born alive, it is obviously relevant to this issue if the fetus is too immature to have survived birth. In another context (Infant Life [Preservation] Act 1929, concerning child destruction), the age of viability in English law was taken as 28 weeks' gestation, though this has now been reduced to 24 weeks as even younger fetuses can now survive with intensive medical support.[25] If a child is shown to be that premature, there is a strong presumption that it would not long survive a birth away from medical attention.

To determine whether or not the child was stillborn and whether it had a separate existence

There is a presumption in English law that all infants are stillborn and, when a female is charged with infanticide, the burden of proof is upon the prosecution to demonstrate that the child had a separate existence. Adelson states that the same legal situation exists in the USA, and gives the following useful and interesting commentary:

> "Unless the pathologist has incontrovertible criteria of post-natal survival, e.g. well-expanded lungs, food in the stomach or vital reaction in the stump of the umbilical cord, he is legally bound not to diagnose live birth. Convictions for infanticide have been set aside when there has been any doubt whatsoever that the child was born alive. Many courts have pushed this proposition to the extent that the State has been given the burden of proving that the baby was born alive beyond any possible doubt rather than beyond any reasonable doubt, the latter being the general level of proof required in a criminal prosecution."[26]

In the late 19th century Kockel reported on a microscopical study of the umbilical cords of 19 neonates that had survived between 45 minutes and 8 days and observed a peripheral inflammatory zone of demarcation surrounding the naval, umbilical cord stumps suggesting that the microscopical changes might help to establish how long time the neonates had survived.[27] Later histological studies with larger materials including stillbirths have not been able to confirm the same regularity of the changes as originally reported and the value of microscopy in this context has remained controversial.[28–30] According to Janssen, the whole navel should be removed for the histological investigation together with a 1–2 cm-long piece of the umbilical cord and a similar-sized piece of the umbilical vessels running intra-abdominally and within the abdominal walls. The samples should be investigated by serial sectioning them parallel to the longitudinal axis of the umbilical cord at the level of the border with the navel skin.[31] The microscopical findings probably vary depending, among other things, on the maturity of the child, the duration of labour and the cause of death. Quite recently, an immunohistochemical study of umbilical cords of 24 stillborns and 21 samples taken from newborns after normal labour showed a statistically significant ($p < 0.0001$) different expression of tryptase for the mast cell, CD68, and alpha-1-antichymotrypsin.[32] However, the practical implications of this observation need to be corroborated by further studies.

Herein lies the most difficult task for the pathologist, one which has given rise to considerable controversy in forensic pathology.

To determine whether its death was due to natural causes or to any act of omission or commission

Where the pathologist claims to have proved separate existence (or at least, live birth), he has an additional burden in that he must show that death occurred from an act of commission or omission, The 'wilful' aspect is a matter for the lawyers, but it is for the pathologist either to demonstrate lethal injuries or to prove that some lack of care led to the death – often an impossible task. There is a considerable burden upon the investigating authorities when finding a hidden newborn infant if they wish to pursue an infanticide charge.

First, they must find the mother – often another impossible task. Then the pathologist must prove live birth, which is often impossible, especially in a decomposed body. To prove a separate existence is even more difficult and is rarely a purely medical decision. The firm diagnosis of death from wilful inattention is equally hard to make.

It is small wonder that only a small proportion of suspicious neonatal deaths ever reach the court – where few females are convicted, and those who are, rightly receive lenient and sympathetic treatment, usually consisting of probation and psychiatric support.

Definition of 'live birth' and 'separate existence'

There is no definition of live birth in English law, except by inference from the defined 'stillbirth', given earlier. Using the live birth as the converse of a stillbirth, the infant should have attained the gestational age of 24 weeks, but this is not a factor in 'separate existence' with which live birth is almost synonymous.

A child with a 'separate existence' would be an infant that had issued forth from its mother irrespective of its gestational age, and who breathed or showed any other signs of life after being completely expelled from the maternal passages – though the child could still be attached to the placenta within the mother. This is almost synonymous with a live birth, though medically all would agree that a child that was crying lustily, but with a foot still in the vagina, was undoubtedly live born even though it did not satisfy the legal criteria of a 'separate existence'.

Viability

Yet another medical and legal concept is that of viability, which is the potential ability of an infant to survive after birth. An immature fetus may be born alive, but be incapable of maintaining an independent existence. Naturally the stage of gestation at which this occurs varies not only with the condition of the particular fetus, but also with the state of medical knowledge and the facilities available at the relevant time and place.

In English law, a period of 24 weeks is fixed for the onset of viability, for the purposes of the Infant Life (Preservation) Act, 1929.[25]

Concealment of birth

Mentioned earlier, this is a relatively minor crime in most jurisdictions and is basically an offence against registration, and perhaps public decency, in that the body of an infant is neither notified to the authorities nor accorded a proper burial or other form of disposal. The crime is the hiding of the body to conceal the fact of birth. It does not depend at all on live birth, separate existence or viability, and the law is not concerned about the cause of death or whether it was stillborn. One problem is the stage of gestation at which the 'child' becomes noticed by the law – obviously an early abortion is of no concern to anyone, except the family.

Though not specified in relation to concealment of birth, English law takes no regard of products of conception under 24 weeks' gestation. In a judicial decision (*R v Matthews, CPD 8, 1943*), it was held that a charge of concealment of birth could not be sustained at an age where the law did not require the (still)birth to be registered.[33]

Whatever the legal ramifications, the forensic pathologist is not infrequently asked to examine dead infants in which he can neither prove live birth nor a wilful act that might have caused death (Figs 20.7, 20.10, 20.11). The only remaining charge, if he can show an age above that of viability, is 'concealment of birth'. This is the end result of the discovery of most decomposed babies, in the minority where the mother can be traced.

The autopsy on a suspicious death of a newborn infant

A number of important matters need specific attention, over and above the usual meticulous autopsy procedure on any infant.

The coverings and any other associated articles with the infant must be examined and retained. Though this is mainly police business, the pathologist usually has the task of unwrapping the baby – often in a decomposed and offensive state – from the coverings of newspaper, plastic bags, rags or blankets. He must recover any foreign material or objects that may assist in the identification of the mother when the disposal has been clandestine (Figs 20.1, 20.2, 20.5, 20.6).

When the baby has been found in a house or other building, he may need to visit the scene, preferably with the child still *in situ*. Numerous cases are on record of the infant being in a lavatory pan and, if there are head injuries or drowning, the circumstances must be evaluated (Fig. 20.4).

The external examination is, as always, important. It is vital to assess the degree of putrefaction because if it is in any way decomposed, it will almost certainly be impossible to determine whether live birth had occurred.



Figure 20.1 Newborn baby with umbilical cord and placenta, abandoned in a car park. It was wrapped in a curtain and though the head was in a plastic bag no signs of suffocation nor of live birth could be detected. The mother was never identified.



Figure 20.2 Full-term newborn found wrapped in a blanket inside a shopping bag in a refuse container. The cord had been cut with a sharp instrument, but the child was not washed or fed. The lungs showed no positive evidence of respiration.



Figure 20.3 A stillborn child concealed by the mother after birth. The injuries around the neck were viewed with suspicion by the police, but are the result of traction on the neck in an attempt to assist self-delivery in an unattended birth.



Figure 20.4 A newborn child of a young mother who had denied the pregnancy and had allegedly found the infant in the lavatory pan after visiting the toilet because of stomach pain. When the paramedics arrived at the scene, the infant and the placenta were lying in the pan under the water except buttocks and legs. Notice the red-tinged froth exuding from the nostrils.



Figure 20.5 A putrefied newborn infant disposed of in a plastic bag in the countryside. There is no hope of determining whether it was live or stillborn with this degree of post-mortem decomposition. There was a strip of fabric knotted around the neck, but it is impossible to decide if that was related to the death, if the child was not stillborn.



Figure 20.6 A decomposed newborn infant found in a rubbish dump.



Figure 20.7 Remains of a newborn infant, who was born during a weekend when the mother, a schoolgirl, was alone in her room in a boarding-school. After the birth she wrapped the child in a plastic bag. The following day she left for home and tried to burn the body in a stove but when that did not succeed she buried the partly burned body in a snowdrift where it was later found by a dog.

Decomposition must be distinguished from intrauterine maceration, as the latter is definite proof of stillbirth. If death occurred within 2–3 days before expulsion from the uterus, the appearances may be fairly normal, apart from general softening and histological evidence of general cellular autolysis. When it has been dead for many days, the macerated fetus is usually a brownish-pink, rather than the greenish hue of putrefaction. The surface is slimy, blistered, desquamating and sometimes almost jelly-like. The joints are grotesquely loose and the cranial plates may be virtually detached beneath the scalp. Rarely, a macerated fetus – which is normally sterile – may become infected if not expelled after the membranes rupture; it will then be born in a putrefied state.

External examination will next be directed at the cord and placenta, if present. The latter must be measured and weighed to estimate the maturity and any abnormalities, such as placental infarcts, noted as possible reasons for fetal death. The cord is important as an indicator of separate existence, if survival has been for an appreciable period. Even where early putrefaction renders evaluation of breathing impossible, vital signs in the cord may indicate live birth if survival reached 24–48 hours. Until this period, no evidence of cord separation is reliable, but after a day or so, a ring of reddening appears around the base of the cord and adjacent abdominal skin. This becomes more marked in the succeeding few days as the cord dries and shrivels, detachment taking place between 5 and 9 days. As most infants die or are killed within hours of birth, however, these signs are rarely of much practical use.

The severed end of the cord should be examined, as it may indicate whether the cord had been broken or actually cut. This is occasionally important if death is the result of head injuries and the defence on behalf of the accused mother claims that the child fell to the ground head first during a precipitate delivery. The length of the cord must be measured, especially if the placental segment is available, so that the distance from the vulva to the floor can be calculated. The average cord length is about 50 cm, but more than twice this length is not uncommon, as are much shorter ones. Naturally, if a ligature is present it indicates either the attendance of a professional or at least knowledgeable person, but this is rare in these cases. The severed end may be examined in the hand, but may also be floated out in water, to better study the detail of the detachment. Morris and Hunt conducted experiments on 38 cords and determined that they could easily be broken by hand traction. Most cords broke at about 5 kg (approx. 11 lb) strain, and the strongest had a breaking strain of only

12 kg (approx. 26 lb).[34] A broken cord can show a clean transverse termination, but is usually ragged. If cut by a sharp instrument such as knife or scissors the cut may be clean, but may also be ragged if the instrument is blunt.

If the baby is examined as found, either at the scene or undisturbed in wrappings, it should be noted if the cord was coiled around the neck. Although it is usually unsafe to claim that death during delivery was from pressure on the neck from the cord, the fact must be noted and evaluated along with all other findings.

The skin may still have vernix caseosa present. This is not a useful observation but, if none is present, it may indicate that the child had been washed, which suggests survival for some time after birth.

Measurements are vital for an estimate of maturity. Weight, crown–heel, crown–rump, head circumference, and foot length are required.

Abnormalities incompatible with continued life may be obvious, such as anencephaly, severe spina bifida or abdominal ectropion. It is, however, often unsafe to assume that actual live birth, as legally defined, could not have taken place.

Injuries are obviously of prime importance as evidence of the 'act of commission', though most newborns seen by the pathologist will be free of such trauma. The types of injury perpetrated by distraught mothers are numerous:

- Strangulation presents the usual features of bruises and abrasions on the neck, though these may be minimal. The classical features of facial congestion, cyanosis, oedema and petechiae may be present, but are often absent, presumably because of the ease with which the vulnerable infant dies. Abrasions on the neck, however, may also be caused by the frantic efforts of the mother to deliver herself, leaving finger-nail marks on the infant's neck (Fig. 20.3). A ligature may be used, which may still be in place. Again caution must be employed, as the fact of some object around the neck, though suggestive, is not absolute proof of strangulation unless corroborative evidence of congestive and petechial signs in the face or skin, and tissue damage beneath the ligature is demonstrated. The explanation has been advanced in the past that a cloth ligature around the neck was an attempt to assist self-delivery by the woman in an obstructed labour (Fig. 20.9).
- Smothering is almost impossible to prove, as the infant will almost never show conjunctival petechiae or other signs that may be seen in strangulation. Only if excessive pressure is applied, so that marks are left on the lips and face, can any evidence be retrieved. These must be definite intradermal or deep bruises, abrasions or marks within the lips and mouth – and not shadowy, vague variations in post-mortem staining. The arguments about criteria of suffocation in infants are further discussed in Chapter 14. Choking by the internal obstruction of the pharynx by various materials has been described in old reports, but it is excessively uncommon these days.
- Cutting and piercing is well known as a means of infanticide. Stabbing with scissors, either in the chest or neck, has been seen or even cutting the throat with a blade (Fig. 20.8). The defence may be



Figure 20.8 Definite infanticide, the child having fully respired before having this severe incised wound of the neck made with a kitchen knife.



Figure 20.9 A putrefied newborn infant with a scarf knotted tightly around the neck. (Reproduced by kind permission of Professor E. Lignitz.)



Figure 20.10 Frozen newly born infant found in a freezer by the children of the family who thought that they had found a doll. The child and placenta were packed and frozen in separate plastic bags, the umbilical cord is still attached. The family had moved twice after the birth of the child.



Figure 20.11 A positive finding in a baby whose body was abandoned after death. Respiration had occurred but, on examination of the cranium, a tear in the tentorium was found with an adjacent meningeal haemorrhage, presumably caused by excessive moulding of the head during precipitate delivery.

offered that the wounds were inflicted accidentally during frenzied efforts by the mother to cut the umbilical cord. Though not seen in Europe, deliberate infanticide has been described in India by clandestine stabbing by a long needle or pin into the spine, fontanelle, eye or nose.

- Head injuries are relatively common. The mother may throw the child to the floor, or dash its head against a wall or other obstruction, sometimes by swinging it by the legs. This mode of death is similar to child abuse in older infants. The defence may be raised that the child fell to the ground, either from the mother's arms, but especially during a precipitate birth from the standing or crouching position. Though this defence sounds like a desperate excuse, the author can attest – no doubt in common with all doctors who have practical experience of childbirth – that some deliveries, especially in multiparous women, can occur with considerable speed and force. This is why the length of the cord needs to be measured, as it is obviously an effective brake on such a descent. There is no doubt, however, that cords have broken during precipitate birth, a reason for a careful inspection of the severed ends at every autopsy.

  The lavatory pan has special significance in this respect, as many unexpected births have taken place while the mother is sitting on the toilet. A common story is that the pregnant female, often a teenage girl – is unaware that she is pregnant and goes to the toilet under the misapprehension that she has stomach pain from constipation. There is no doubt that some naïve girls are genuinely ignorant of their gravid condition, and are shocked and devastated to the point of blind panic when a baby emerges into the pan. The question may then arise as to whether fatal head injuries on the infant can be accounted for by the descent into the lavatory. It is unlikely to produce the severe fracturing sometimes seen – and falling to the floor in a precipitate delivery is also unlikely to produce fatal damage. Much depends on the severity and nature of the scalp and skull injury, and although it cannot be said that it is impossible for a fatal head injury to be caused in this way, it must be a rare event. Minor fractures of the parietal bones may occur in natural delivery if there is excessive head moulding. These are usually non-displaced linear fractures of the parietal bone and unassociated with internal brain or meningeal damage, and naturally there is no associated scalp damage.[35,36]
- Drowning is another unusual form of infanticide, but is more often a way of disposing of an already dead child, either stillborn, a natural death or the victim of some other mode of infanticide. It may take place in any form of water, from a washbasin to the open sea. Most often the mother will use a household receptacle such as bowl, bucket or bath, but the infant may be taken out and disposed of in any source of open water, where delay in recovery may add decomposition to the pathologist's difficulties. In a case seen by the author (BK), the young parents admitted that the child was live born. After some hours, they wrapped the infant

in a blanket with a brick and dropped it into a river. The partial remains, largely converted to adipocere, were recovered some 3 months later, there obviously being no prospect of offering any opinion upon either live birth or the cause of death. The only objective, but equivocal evidence, was the recovery of diatoms from the femoral bone marrow, which resembled those in the river water. Returning to the lavatory pan once again, cases are on record where the birth into the toilet led not to head injuries, but to drowning.

Infanticide by omission to offer proper care

This is both rare and almost outside the province of the pathologist's examination. If the infant is older than newborn, then deliberate starvation will leave obvious signs, but the proof of lack of care immediately after birth will be a matter of witnesses and clinical opinion. The only possible signs, which the autopsy might reveal, would be hypothermia (Chapter 17), and obstruction of the air passages by mucus or amniotic fluid.

Proof of a separate existence

Strictly speaking, the pathologist can never demonstrate evidence of a separate existence in the English legal sense of complete expulsion from the mother, but it is usually taken to mean proof of live birth, specifically the attainment of breathing air. In the slightly older child the presence of food in the stomach would obviously prove a separate existence, but most autopsies are upon the recently newborn.

Changes in the cord have already been mentioned, but are of no use in the immediate post-partum period. Polson *et al.* make mention of the presence of 'extraneous material' in the deeper (secondary) bronchi as evidence of a stillbirth, on the grounds that, if this material, such as soil or sand, gained entry after respiration had commenced, the air in the deeper areas of the lung would prevent its ingress. The practicality of this appears suspect.[37]

The unequivocal demonstration of breathing in a newborn infant is fraught with difficulty. Along with the estimation of the time of death, it has probably provoked more discussion, printed words and controversy than any other topic in forensic medicine. The controversy revolves around the 'hydrostatic test' on the lungs, in which it has been claimed since medieval times that, if the lungs float in water, then the infant breathed. There are modifications of technique, but this is the thrust of the claim. The authors' attitude must be stated at the outset: the test is of limited value, whatever modifications are made and it can at best be a suggestive pointer, but never a definitive test in itself.

There are too many recorded instances when control tests have shown that stillborn lungs may float and the lungs from undoubtedly live-born infants have sunk, to allow it be used in testimony in a criminal trial. Even one such failure negates the whole history of the test and the authors are saddened to contemplate the number of innocent mothers who were sent to the gallows in previous centuries on the testimony of doctors who had an uncritical faith in this crude technique. As this is such an important issue and one that is still contested today, the words of the late Professor Polson may be recalled from his notable textbook:

> "The test was suspect even in 1900 and requires no detailed discussion, because it is now known to have no value. The lungs of the live-born, even those who have been known to live for days, may sink,[38,39] and those which float are not necessarily those of live-born infants …. It is therefore pointless to apply the hydrostatic test, which will impair the material for other and more important investigations."[37]

Before dismissing the test so absolutely, there are some points both for and against its use as part of the feeble armamentarium that the pathologist has in determining this vital issue. First, the slightest degree of post-mortem decomposition immediately negates any interpretation of the flotation test. As so many potential infanticides are found hidden, buried or submerged, decomposition is more the rule rather than the exception, so the test cannot even be considered in a large proportion of cases. Even when obvious putrefaction with gas formation is not apparent, slight decomposition will still begin to produce gas on a microscopic scale from the second unrefrigerated day in temperate surroundings – and much earlier in hot climates. In recent years the advent of resuscitation attempts make the evaluation of breathing even more difficult or even impossible. The use of mouth-to-mouth revival, external cardiac massage and the administration of oxygen, completely negate any of the already fragile tests for respiration in a newborn infant.

On the positive side – assuming fresh tissue – the floating of the whole pluck of thoracic organs in water makes one tend to accept that respiration had taken place.

This means that the attached heart, mediastinum and neck structures are also buoyed up by the lung – but in this case, it is almost invariable that the lungs are sufficiently aerated for this to be obvious on naked-eye inspection.

This is about the total extent of the usefulness of the hydrostatic test. The complicated instructions offered in many textbooks concerning cutting the lung into lobes and then into pieces, squeezing them with knife blades and even pressing them underfoot on the mortuary floor before floating them, all smatter of black magic and are a complete waste of time. Worse, they can simulate a false sense of scientific validity and even to an eventual miscarriage of justice.

The best way of seeking proof of respiration is to look at, to feel and to listen to the lungs. The lungs of a stillbirth are dark, small, heavy and liver-like, even though they may still float. They lie contracted against the mediastinum, though when the body is intact they must still fill the thoracic cavity, as the pliable rib cage pulls inwards and the diaphragm rises to eliminate the free space in the chest. Though this fact is seldom considered, it must be obvious that there can be no free space in the pleural cavities until the thorax is opened at autopsy. As soon as this is done, air enters the pleural sacs and the lungs then appear much smaller than the expanded chest cavity than is seen when the sternal plate is removed.

Unrespired lungs appear smaller than those that have breathed for a significant time, though there is a continuous range of expansion. According to Polson *et al.,* unrespired lungs weigh something of the order of 1/70th of the body weight; when aeration begins, the lung weight increases because of the increased vascular volume and become about 1/35th of the body weight.[37] This seems at variance with actual measurements at autopsy as the combined weight of both lungs in an infant of average birth weight is about 40 g and, although there is a fairly wide variation between individuals, no combined lung weights approach 85 g, which would be 1/35th the weight of a 3000 g baby.

The texture of an unrespired lung is rubbery and uniform, with no paler, crepitant areas at the margins, which tend to be sharply angled. On slicing, the interior is uniform in colour and texture, being moist and resembling stiff strawberry jelly. On rubbing a small piece between the fingers close to one's ear, no crepitation is heard (Fig. 20.12).



Figure 20.12 The pluck of thoracic organs from a known stillbirth in hospital. The lungs are firm and heavy with no crepitation when squeezed. Margin portions of lung floated in water, however, demonstrating the fallacy of the 'flotation test'.

The lung that has respired will change quantitatively from the above appearances depending on the length of time and the depth to which breaths have been taken. Feeble or brief respiration will affect only the margins, whilst more robust or prolonged breathing may lead to total expansion. Even a single good breath can unfold some of the fetal pulmonary tissues – and of course, resuscitation, whether by mouth-to-mouth, chest compression or administration of oxygen, will actively inflate the lungs, dead or alive. Even ordinary handling of the dead baby may aspirate air into the lungs. Fully respired lungs will be obvious on inspection. The organs are pink or mottled, the medial edges overlapping the mediastinum and part of the pericardium, though not as fully as in the older neonate. The weight is greater, but not as much as recorded by Polson and colleagues, as described above. The edges of the lung, including the interlobar fissures, are more rounded by the expansion, compared with the angular margins of the unrespired organ.

The major change is in the colour and texture. It may be pink all over the surface or there may be patches of darker atelectasis under the pleura. The lung is spongy and resembles the familiar adult tissue. On cutting, the aerated texture is apparent, and on holding a piece to the ear, typical crepitance is heard on rubbing gently between the fingers.

The problem arises with the minimally respired lung, where the changes are intermediate between the two extreme states described above. The anterior margin best shows partial expansion, the areas such as the lingula, anterior diaphragmatic margin and the medial edge of the lower lobe sometimes being pinker and more expanded than the posterior parts. The most sensitive criterion is the ear crepitance test, but it is all a matter of degree as to whether the pathologist is impressed enough – having excluded any possibility of decomposition or resuscitation artefact – to consider that significant respiration has occurred.

Any doubts must be resolved in the direction of no breathing and, even in doubtful instances when the pathologist decides – on balance – that respiration has occurred, he should convey his uncertainty in the body of his report. As to the corroborative role of the flotation test, if performed, when the whole chest pluck floats, the descriptions of the lungs given above will usually indicate clearly that the lungs had breathed. A sinking lung will never correspond with a pink crepitant appearance, but what appears to be a dark, fetal lung may float. The test unfortunately tends to mislead more in one direction than the other, in that almost all lungs float irrespective of their appearance. To repeat the advice of Lester Adelson, whose experience and clarity of expression makes his voice one of the most respected in forensic pathology:

> "Unless the pathologist has incontrovertible criteria of post-natal survival, e.g. well-expanded lungs, food in the stomach or vital reaction in the stump of the umbilical cord, he is legally bound not to diagnose live birth. Convictions for infanticide have been set aside where there was any doubt whatsoever that the child was born alive. Many courts have pushed this proposition to the extent that the state has been given the burden of proving that the baby was born alive beyond any possible doubt rather than beyond any reasonable doubt, the latter being the general level of proof required in a criminal prosecution."[26]

Histological appearances of newborn lungs

Histology is not as helpful as might be expected in the problem of demonstrating the onset of breathing. It was formerly thought that the shape of the alveoli and the height of the lining epithelium would indicate whether they had been expanded by the passage of air, but this has proved to be a disappointing exercise. According to Shapiro, the height of the epithelium and the shape of the alveoli are more a measure of fetal maturity than respiration at birth.[40] The lung parenchyma develops in the fetus as a branching ramification of the trachea and at an intermediate stage – around 800 g body weight or 4 months' gestation – appear as gland-like structures with a cuboidal or columnar cell lining. The evolution to the thin-walled adult-type alveolus is complete before full term, or when the fetal weight is about 2500 g. The alveolar spaces may be found substantially distended even in fetuses who could not have breathed air, such as the one described by Shapiro that was found free in the maternal abdomen after rupture of the uterus. No intra-alveolar epithelium was visible and the lung could not be distinguished histologically from that of a child that had breathed.

Other authors have described the maturation of the fetal lung and it is undisputed that fully expanded alveoli can be present before full term, even in infants who have not inspired air.[41–43] After the fifth month, the glandular nature of the air sacs of the lumen are filled with amniotic fluid. In fact, there is evidence that amniotic fluid may be produced by the nascent pulmonary lining, because it is present even in cases of congenital bronchotracheal atresia. When breathing starts, the alveoli further enlarge, and the fluid is partly expelled through the bronchi and partly absorbed back into the pulmonary circulation. Ham and Shapiro point out that the finding of open alveoli with no cuboidal or columnar epithelium means that the fetus has passed the two-thirds stage of its maturation process, not that it has respired air.[44,45]

Further proof is found in the histological appearance of sequestrated parts of lung tissue in infants, which were not connected to the bronchial system but which still showed alveolar ducts and alveoli.[46,47] Fetal lung transplanted into the anterior chamber of an animal eye also developed alveoli with terminal bronchioles.[48] Post-mortem handling has also been incriminated for the entry of air into fetal lungs. Apparently respired alveoli have been found in lung sections from a dead infant taken from the uterus of a dead mother.

Janssen agrees that resuscitation will lead to post-mortem aeration of the lungs, but claims that such artificial respiration cannot cause the alveoli of stillborn neonates to be perfectly and uniformly aerated. Against this view, however, is the undoubted patchy appearance of the lung expansion of many infants who have undoubtedly breathed for some time, so it is difficult to see how the two situations could ever be differentiated. Janssen's statement about the histological appearances is reasonable:

> "According to the present level of knowledge and possibilities for examination, ventilation of the lungs alone cannot be taken as a certain indication of a live birth. Under various circumstances, lungs originally aerated can become devoid of air: conversely, the lungs of stillborn neonates can appear aerated. It is not possible to be certain in all cases."[31]

In general, an infant who has breathed strongly for some time – probably hours in most cases – will have lungs that histologically resemble the older child with full, uniform, expansion of alveoli. In many infants who undoubtedly have lived and breathed for an appreciable time, however, there may be only patchy expansion, which corresponds to the uneven aeration seen macroscopically under the pleural surface. The difficulty arises when paradoxical appearances are seen, examples of which are illustrated in many textbooks. Thus an undoubted stillbirth may reveal quite extensive alveolar expansion, whilet a baby that unequivocally lived for some time may show totally collapsed air sacs.

In medico-legal work, though it is quite in order to refer to the usual state of affairs, when a criminal trial is in progress, the standard of proof is 'beyond reasonable doubt' and the well-documented exceptions just mentioned (as with the flotation test) make it unsafe to be dogmatic over a histological opinion.

Estimation of maturity

This is a necessary part of the autopsy, both as matter of record of the size and presumed age of the infant, but also as a legal requisite in those jurisdictions that require proof of viability before either stillbirth can be recorded or a charge of infanticide brought (Figs 20.13–20.15).

First, it must be accepted that – as at any time of life – morphological measurements are by no means infallible indicators of chronological age. Personal variations are compounded by sex, race and nutritional factors to prevent accuracy. The time of appearance of ossification centres is no longer as uniform as once thought. As with so many biological conditions, there is the typical 'bell-shaped curve' of probability, so that though most subjects will lie in the large central zone, there will be a progressively diminishing number at each extreme of the graph. It should be remembered that a female infant is usually at least 100 g less in weight at full term than the male, though individual differences in either sex can be far larger than this statistical variation. Twins, even those going to full term, are each lighter than a singleton child. The full-term singleton fetus, at 40 weeks' gestation, will have the following vital specifications, subject to the above cautions:

- a weight of between 2550 and 3360 g
- crown–heel length of 48–52 cm
- crown–rump length of 28–32 cm
- head circumference of 33–38 cm
- the ossification centre in the lower end of the femur will almost always be present, being about 6 mm in diameter
- lanugo is absent or present only over the shoulders; head hair is about 2–3 cm long
- the testes are palpable in the scrotum; the vulval labia closes the vaginal opening
- the umbilicus is midway between xiphisternum and pubis
- there is dark meconium in the large intestine



Figure 20.13 Fetal maturity: up to the 20th week the length of the fetus in centimetres is approximately the square of the age in months (Haase's rule).



Figure 20.14 Fetal maturity: this infant is 21 cm crown–heel length, which is approximately 4.6 months' gestation.



Figure 20.15 Fetal maturity: this infant is 30 cm crown–heel length, which is approximately 6 months' gestation, as the length in centimetres beyond the fifth month is about five times the age in months.

- an ossification centre in the upper end of the tibia will be present in 80 per cent of full-term infants. The length of finger and toenails is an unreliable guide. More detailed information may be obtained from obstetric and paediatric texts.

At 36 weeks, the crown–heel length is about 45 cm and the weight around 2200 g. There will probably be ossification centres in the cuboid and capitate bones, often in the lower end of the femur and perhaps also in the upper end of the tibia.

At 28 weeks, the fetus is likely to be about 900–1100 g in weight, have a crown–heel length of 35 cm, a crown–rump length of 23 cm, and a foot length of 8 cm.

The old Haase rule-of-thumb for fetal age and size was that, up to the 20th week, the length in centimetres was the square of the gestation period in (lunar) months. Beyond the 20th week, the length in centimetres divided by five represents the age in months.

Examination of the ossification centres may be performed radiographically, which requires the advice of a radiologist, as the time of appearance may not be synchronous with visual identification of the centres. At autopsy it is usual to seek them directly, as follows: at the knee, the leg is flexed and a lengthwise cut made over the patella. The bones are pushed forwards through the cut, and transverse slices made with a knife through the cartilage of the lower end of the femur. If the ossification centre is revealed, the cuts should continue through plain cartilage above it until the diaphyseal centre is reached. This is to avoid mistaking the lower margin of the diaphyseal bone for the separate epiphyseal centre. The upper end of the tibia is then dealt with in a similar way.

In the foot, a cut is made in the axis of the limb up between the third and fourth toes into the ankle joint, to seek the cuboid bone. The talus and calcaneum can be entered by cuts across the upper dorsum of the foot when the latter is plantar-flexed. The centre in the calcaneum appears at about 7 months' gestation, that in the talus at about 7 months', and the cuboid at full term.

In assessing skeletal age in the fetus, the reference book of Fazekas and Kosa is invaluable.[49] Other non-osseous methods of estimating maturity exist, such as the progressive development of surfactant-producing alveolar type II cells in fetal lungs.[50]

References

1 Moseley KL. The history of infanticide in Western society. *Issues Law Med* 1986;1(5):345–61.
2 Kellett RJ. Infanticide and child destruction – the historical, legal and pathological aspects. *Forensic Sci Int* 1992;53(1):1–28.
3 Kouno A, Johnson CF. Child abuse and neglect in Japan: coin-operated-locker babies. *Child Abuse Negl* 1995;19(1):25–31.
4 Lagaipa SJ. Suffer the little children: the ancient practice of infanticide as a modern moral dilemma. *Issues Compr Pediatr Nurs* 1990;13(4):241–51.
5 George SM. Female infanticide in Tamil Nadu, India: from recognition back to denial? *Reprod Health Matters* 1997;5(10):124–32.
6 Oberman M. Mothers who kill: cross-cultural patterns in and perspectives on contemporary maternal filicide. *Int J Law Psychiatry* 2003;26(5):493–514.
7 Wilczynski A. The incidence of child homicide: how accurate are the official statistics? *J Clin Forensic Med* 1994;1(2):61–6.
8 Jason J, Gilliland JC, Tyler CW, Jr. Homicide as a cause of pediatric mortality in the United States. *Pediatrics* 1983;72(2):191–7.
9 Christoffel KK, Anzinger NK, Amari M. Homicide in childhood. Distinguishable patterns of risk related to developmental levels of victims. *Am J Forensic Med Pathol* 1983;4(2):129–37.
10 Herman-Giddens ME, *et al*. Newborns killed or left to die by a parent: a population-based study. *JAMA* 2003;289(11):1425–9.
11 Vanamo T, *et al*. Intra-familial child homicide in Finland 1970–1994: incidence, causes of death and demographic characteristics. *Forensic Sci Int* 2001;117(3):199–204.
12 Putkonen H, *et al*. Legal outcomes of all suspected neonaticides in Finland 1980–2000. *Int J Law Psychiatry* 2007;30(3):248–54.
13 Putkonen H, *et al*. Filicide in Austria and Finland – a register-based study on all filicide cases in Austria and Finland 1995–2005. *BMC Psychiatry* 2009;9:74.
14 Funayama M, *et al*. Case report: repeated neonaticides in Hokkaido. *Forensic Sci Int* 1994;64(2–3):147–50.
15 Yamauchi M, *et al*. Medico-legal studies on infanticide: statistics and a case of repeated neonaticide. *Forensic Sci Int* 2000;113(1–3):205–8.
16 Resnick PJ. Murder of the newborn: a psychiatric review of neonaticide. *Am J Psychiatry* 1970;126(10):1414–20.
17 Wilkins AJ. Attempted infanticide. *Br J Psychiatry* 1985;146:206–8.
18 BBC. *Details emerge in French baby killing case*. [2010 29.7.2010]; Available from: http://www.bbc.co.uk/news/world-europe-10803080.
19 *Act of June 16, 1879*, in *Code pénal*. 1879, Service central des Imprimés de l'Etat: Grand Duchy of Luxembourg.
20 Dean PJ. Child homicide and infanticide in New Zealand. *Int J Law Psychiatry* 2004;27(4):339–48.
21 Oberman M. Mothers who kill: coming to terms with modern American infanticide. *Am Crim Law Rev* 1996;34(1):1–110.
22 *Infanticide Act*. UK: UK Statute Law Database (SLD), 1938.
23 Lawn JE, *et al*. Global report on preterm birth and stillbirth (1 of 7): definitions, description of the burden and opportunities to improve data. *BMC Pregnancy Childbirth* 2010;10 Suppl 1:S1.
24 Beck S, *et al*. The worldwide incidence of preterm birth: a systematic review of maternal mortality and morbidity. *Bull World Health Organ* 2010;88(1):31–8.
25 *Infant Life (Preservation) Act 1929*. UK: UK Statute Law Database (SLD), 1929.
26 Adelson L. *The Pathology of Homicide*. Springfield Thomas, 1974.
27 Kockel R. Die mikroskopischen vorgänge beim nabelschnurabfall und ihre verwertung zur bestimmung der lebensdauer neugeborener. *Beitr Path Anat* 1898;24:231–254.
28 Fazekas IG, Kosa F, Fabrik E. [The periumbilical inflammatory zone of demarcation in live birth]. *Dtsch Z Gesamte Gerichtl Med* 1969;66(2):35–45.

29 Fritz E. Die Bestimmung des alters von neugeborenen am hautnabel. *Beitr Gerichtl Med* 1935;8:28–35.
30 Glinski LK, Horoszkiewicz S. Über mikroskopische vorgänge beim nabelschnurabfall und deren gerichtsärtzliche bedeutung. *Vjschr Gerichtl Med* 1903;24:243.
31 Janssen W. *Forensic Histopathology.* Heidelberg: Springer, 1977.
32 Neri M, *et al*. Stillborn or liveborn? Comparing umbilical cord immunohistochemical expression of vitality markers (tryptase, alpha(1)-antichymotrypsin and CD68) by quantitative analysis and confocal laser scanning microscopy. *Pathol Res Pract* 2009;205(8):534–41.
33 Gordon I, Shapiro HA, Berson SD. *Forensic Medicine; a Guide to Principles*, 3rd edn. Edinburgh: Churchill Livingstone, 1987.
34 Morris JF, Hunt AC. Breaking strength of the umbilical cord. *J Forensic Sci* 1966;11(1):43–9.
35 Reichard R. Birth injury of the cranium and central nervous system. *Brain Pathol* 2008;18(4):565–70.
36 Zelson C, Lee SJ, Pearl M. The incidence of skull fractures underlying cephalhematomas in newborn infants. *J Pediatr* 1974;85(3):371–3.
37 Polson CJ, Gee D, Knight B. *Essentials of Forensic Medicine,* 4th edn. Oxford: Pergamon Press, 1985.
38 Dilworth T. The hydrostatic test of stillbirth. *Br Med J* 1900; II:1567.
39 Randolph C. The hydrostatic test of stillbirth. *Br Med J* 1901; I(19. January):146.
40 Shapiro HA. Microscopy of human fetal lung and the diagnosis of postnatal respiration. In: Wecht C (ed). *Legal Medicine Annual 1976.* New York: Appleton Century Crofts, 1977.
41 Ham A, Baldwin K. A histological study of the development of the lung with particular reference to the development of the alveoli. *Anat Rec* 1941;81:369–79.
42 Kuroda S, *et al*. Medicolegal studies on the fetus and infant with special reference to the histological characteristics of the lungs of liveborn and stillborn infants. *Tohoku J Exp Med* 1965;85:40–54.
43 Parmentier R. L'aeration neonatale due poumon. *Rev Belg Path Med Exp* 1962;29:121–244.
44 Ham A. Histology. In: *Histology*. Philadelphia: Lippincott, 1950, pp. 448–96.
45 Shapiro H. The limited value of microscopy of lung tissue in the diagnosis of live and still birth. *Clin Proc* 1947;6:149–58.
46 Potter E. Pathology of the fetus and newborn. In: *Pathology of the Fetus and Newborn*. Chicago: Year Book Publishers, 1952, p. 262.
47 Potter E, Bohlender G. Intra-uterine respiration in relation to the development of the fetal lung. *Am J Obstet Gynecol* 1941;42:14–22.
48 Waddell W. Organoid differentiation of the fetal lung: a histologic study of the differentiation of mammalian fetal lung in utero and in transplants. *Arch Path* 1949;47:227–47.
49 Fazekas G, Kosa F. *Forensic Fetal Osteology.* Budapest: Akademiai Kiado, 1978.
50 Betz P, *et al*. Determination of fetal age by immunohistochemical estimation of surfactant-producing alveolar type II cells. *Forensic Sci Int* 1992;53(2):193–202.

CHAPTER 21

Sudden Death in Infancy

- Definition of the sudden infant death syndrome (SIDS)
- Incidence of sudden infant death
- Factors influencing the risk of SIDS
- The case history in sudden infant death
- The scene of death and external findings
- Autopsy appearances
- Histological findings in SIDS
- Theories of causation
- The SIDS autopsy
- Medico-legal problems in cot deaths
- References

This distressing condition has a variety of names and abbreviations. The one now most generally accepted is ‘sudden death in infancy syndrome’, often shortened to (and pronounced as) ‘SIDS’. An older title was ‘SUD’, standing for ‘sudden unexpected death’, but this in itself did not denote the infant connotations. Colloquially, SIDS is known as ‘cot death’ in Britain and ‘crib death’ in North America.[1] As SIDS is a diagnosis per exclusion other possible causes of sudden unexpected death in infancy have to be excluded (Table 21.1).

Definition of the sudden infant death syndrome (SIDS)

Following one of the international conferences on the condition (held in Seattle in 1969) the following useful definition of the syndrome was proposed by Beckwith: ‘the sudden death of any infant or young child which is unexpected by history and in whom a thorough necropsy fails to demonstrate an adequate cause of death’.[2] Other definitions have been proposed later, e.g. the definition by the National Institute of Child Health and Human Development (NICHD) in 1989 emphasizing the necessity of the scene of death examination, and a three-tiered definition by Beckwith 1992 in Sydney, during the Second SIDS International Conference, dividing the SIDS into three different categories according to the age, the occurrence of similar deaths in siblings or other close relatives, and the presence of petechial haemorrhages and inflammatory lesions or other abnormalities found during the autopsy.[3,4] The ‘Stavanger definition’, proposed during the Third SIDS International Conference in Stavanger, Norway 1994, lays stress on the importance of the investigation of the circumstances of death: sudden death in infancy unexplained after review of the clinical history, examination of the circumstances of death and post-mortem examination. However, when put to the vote during a subsequent SIDS Global Strategy Meeting in Stavanger, the original definition from 1969 received the most votes. Again in 2003, Beckwith proposed a re-examination of the SIDS definition, and a meeting was held in San Diego, California, in 2004, where the following definitions and subclassifications were agreed (Table 21.2). If these criteria are not fulfilled, the cases should be termed ‘unclassified infant death’ (USID) or ‘sudden unexpected death in infancy’ (SUDI).

Obviously the use of different definitions of SIDS may hamper the comparison of data among different studies. Byard and Lee reviewed 50 randomly selected papers dealing with SIDS that were published between 2010 and 2011 in peer-reviewed journals to determine whether one of three internationally accepted definitions of SIDS had been either written in the text or referenced. The 1989 NICHD definition remained the most commonly used definition (35.1 per cent) followed by the 2004 San Diego definition (26.3 per cent). Although a significant improvement in the use of definitions had occurred since 2005, still nearly one in three papers that were included in this study did not cite a standard definition.[5]

Table 21.1 Causes of sudden unexpected death in infancy

Natural causes of death	Unnatural death
SIDS*	Suffocation by
Infection	• Soft covering
• Various types of pneumonia	• Occlusion of mouth and nose
• Meningoencephalitis	• Chest compression
• Gastroenteritis	• Aspiration of stomach contents
• Myocarditis	
• Septicaemia	
Metabolic diseases	Shaken baby syndrome
• Disturbances of fatty acid oxidation	Poisoning
• Pyruvate dehydrogenase deficiency	Other types (masked) of blunt trauma
• Biotilidase deficiency	Munchausen syndrome by proxy
• Hyperinsulinism	Neglect
• Disturbance of thiamine metabolism	Hyperthermia of external causes
Malformation	
• Blood vessels	
• Cardiac malformation	
• Fibroelastosis of the myocardium	
• Pierre Robin sequence	
Reye syndrome	
Hyperthermia from natural causes	
Dysplasia of lungs	

* Strictly speaking SIDS cannot be considered to be due to natural causes as long as it is by definition a diagnosis per exclusion, i.e. the cause of it is unknown.

Modified from Bajanowski and Venneman[39] with kind permission of Elsevier.

Incidence of sudden infant death

The reliability of national death statistics and data on the incidence of SIDS continues to be a problem. Only one-third of world's countries have properly functioning civil registration systems and coverage of death registration varied at the end of 2003 from close to 100 per cent in the World Health Organization (WHO) European Region to less than 10 per cent in the African Region. Only 23 countries had data that were more than 90 per cent complete, where ill-defined causes account for less than 10 per cent of total of causes of death, and where ICD-9 or ICD-10 codes are used. Among the high-income countries in western Europe there were a dozen countries with intermediate-quality data.[6] According to Mahapatra *et al.* only about 80 of WHO's member countries, representing 27 per cent of the world's population, have reported useable cause-of-death data to WHO in the past decade.[7] Furthermore, autopsy rates and the certifying habits of different pathologists and clinicians are variable.

According to a review by Rognum, the percentage of sudden deaths in infancy that are diagnosed by various authors as pure SIDS varied between 2.5 per cent and 70 per cent.[8] This situation still applies in many countries, especially those where high infant mortality from many causes overshadows sudden infant deaths. In advanced countries, the progressive and often dramatic reduction in total infant mortality since the beginning of the century has eliminated many infective, nutritional and congenital diseases to the point where the 'law of diminishing returns' has flattened out the mortality curve to a low level. Until 1990, there was little evidence that the SIDS rate had changed significantly for centuries or even

Table 21.2 Criteria used in the San Diego definition of sudden infant death syndrome (SIDS)

	Previous history	Circumstances of death	Autopsy findings
General definition	• Sudden and unexpected death • Under 1 year of age • Lethal episode during sleep • Death unexplained by clinical history	• Unexplained after review of the circumstances	• Unexplained after complete autopsy
Specific definition			
Category IA SIDS	1. Older than 21 days, under 9 months	• Scene investigation performed and gave no explanation	1. No lethal pathological findings
	2. Normal clinical history	• Safe sleep environment	2. No unexplained trauma, abuse, neglect or unintentional injury
	3. Full-term pregnancy (≥37 weeks)	• No evidence for an accident	3. No substantial thymic stress
	4. Normal growth and development		4. Toxicology, microbiology, radiology, vitreous chemistry and metabolic screening
	5. No similar deaths in siblings/relatives		
Category IB SIDS	1–5 (criteria for category IA SIDS)	Scene investigation was not undertaken	1–4 and 5. One or more of the following analyses were not performed: toxicology, microbiology, radiology, vitreous chemistry and metabolic screening
Category II SIDS	Differences to category I criteria: 6. Age range (0–21 days, 270–365 days) 7. Neonatal/perinatal conditions that have resolved by the time of death 8. Similar deaths in siblings, near relatives	Mechanical asphyxia or suffocation by overlaying not determined with certainty	1–5 and 6. Abnormal growth and development not thought to have contributed to death 7. More marked inflammatory changes or abnormalities not sufficient to cause the death
USID	• Criteria for cat. I or II SIDS are not fulfilled	• Alternative diagnoses of natural or unnatural death are equivocal	• Autopsy has not been performed

According to Bajanowski and Venneman[39] with kind permission of Elsevier.

millennia, so the pre-1990 straight-line incidence of SIDS became a far greater proportion of the total infant deaths compared with the early years of this century. In many advanced countries, SIDS is still the most common single cause of infant mortality after the perinatal period.

Until about 1990, Britain had a SIDS rate of about 2 per 1000 live births, but the risk varied considerably in various sections of the population. Golding *et al.* give a comprehensive table in their book of known variations in worldwide incidence before the dramatic decline.[9] For example, in the USA there was an overall rate of 2.3/1000, though again this varies considerably from place to place, and among different ethnic and social groups. In Chicago the rate in 1969 was 3.4 compared with 1.4 in upstate New York in 1974. There is far more variation among ethnic groups in the USA, the rate being much higher among non-White infants. In Nebraska, for instance, the rate was 1.9/1000 Whites and 5.9/1000 in non-Whites. There is other evidence, however, that social differences are the predominant factor rather than any intrinsically ethnic cause. According to the Centers for Disease Control and Prevention (CDC), the overall rate of SIDS in the USA has declined by more than 50 per cent since 1990, and SIDS is presently the third leading cause overall of infant mortality. In 2010, 2063 deaths were reported as SIDS, which is a rate of 0.51 deaths per 1000 live births.[10,11]

As noted above, in Britain and several other European countries the SIDS rate has dropped remarkably in the past years. In France there was stagnation for post-neonatal mortality between 1979 and 1993 followed by a sharp decrease to 2/1000 in 1995. In England and Wales the rate peaked in 1988 at 2.3 deaths per 1000 live births but thereafter there was a 69 per cent fall in the sudden infant death rate between 1988 and 1992 from 2.01 to 0.63 and further down to 0.3 in the year 2000. The decrease since 1995 was accompanied by a 10-fold increase in the mortality rate for deaths with an 'unascertained' or 'unknown' cause, from 0.02 deaths per 1000 live births in 1995 to 0.19 in 2003; however, it is unclear whether the decline in the sudden infant death rate and the rise in the unascertained death rate are linked.[12]

The decrease in SIDS rate almost coincides with a vigorous publicity campaign by the Department of Health and the Foundation for the Study of Infant Deaths, which advocated sleeping babies on their back, not on the face and in avoiding overheating and smoking near the baby, as well as exhortations to seek medical advice whenever the infant was unwell.[13–21] However, the fall slightly ante-dated this campaign, so that the contribution of sleeping position, etc., to the decline is not fully understood, though there is other evidence from The Netherlands that recommendations about sleeping supine favourably affects the death rate.[22–26] These same years, however, have shown a series of very mild winters, which may also be a factor.

The present figures for unexplained infant deaths in England and Wales include both sudden infant deaths and unascertained deaths. Sudden infant deaths (ICD-10 code R95 'Sudden infant death syndrome') include any mention of 'sudden infant death', 'cot death', 'SIDS', 'crib death', or another similar term anywhere on the death certificate, whereas unascertained deaths (ICD-10 code R99 'other ill-defined and unspecified causes of mortality') include cases where the only mention on the death certificate is unascertained death. The term 'unascertained', is used by pathologists when the death does not fulfil the criteria used for sudden infant deaths and doubt remains about its cause. According to the provisional figures for 2010, there were 254 unexplained infant deaths in England and Wales in 2010, which is a rate of 0.35 deaths per 1000 live births.[27]

Factors influencing the risk of SIDS

Age

The age range in which sudden infant death occurs follows the usual 'bell-shaped curve' of most biological phenomena. As the Seattle definition stated, the ends of the curve lie at 2 weeks and 2 years, but these boundaries are far too wide for the great majority of victims. The peak incidence occurs at around 3 months and the time bracket of 2–7 months will encompass most cases. It is rare after 9 months, but deaths can occur well into the second year which, by all the criteria, can only be called 'cot deaths'.[9,28–39]

Similarly, a few small infants die unexpectedly and inexplicably before the first month, but it must be accepted that true SIDS is not a condition of the neonatal period. There is almost always a gap between the deaths that must be attributed as being a sequel to birth, and those that suddenly occur subsequently in babies who have apparently weathered that dangerous period successfully. It is obvious, however, that such an absolute distinction cannot be made, as premature and underweight infants have a higher risk of SIDS, and some perinatal deaths are indistinguishable from SIDS in that autopsy may reveal the same negative findings.

Sex

There is a slight but definite sex bias in the syndrome, showing the usual slight weighting against the male infant, which is a common feature of many conditions and at all ages. Most surveys have shown a ratio of 1:1.3 or thereabouts, with an excess of male infants; however, SIDS in indigenous populations such as Australian Aboriginal infants, Native Alaskan and American Indians seem to lack this association with male sex.[29,33,34,37,39–47] In Maori population in New Zealand the association of SIDS with male sex has been inconsistent.[48,49]

Twinning

There is a marked excess of deaths in a member of a twin pair as opposed to singletons. Figures have varied in different surveys, but the risk is at least twofold. The reason for the excess among twins lies partly in the fact that physically disadvantaged infants, such as premature births and those of low birth weight are at greater risk; these two factors are often present in twins.[29,50–56] In an epidemiological survey of live births and cases of SIDS in England and Wales between 1993 and 1998, Platt and Pharoah failed to observe any effect of zygosity on the risk of death.[54] However, in a further study by the same authors comprising 3092 singleton infant SIDS among 6,755,416 live-births and 172 SIDS among 187,048 twin live-births in England and Wales, they concluded that the significant difference between same- and opposite-sex twins, when neonatal and postneonatal mortality are separately examined, suggests that the role of zygosity in some subsets of twin SIDS should be reassessed.[57]

There have been several reports of both twins having died of SIDS on the same day, a phenomenon that understandably evokes suspicion and bewilderment.[58–66] In a series of 637 twin infant pairs in the literature surveyed by Beal, 12 (2 per cent) died simultaneously.[51] Bass studied 13 pairs of healthy twins who died together of no apparent cause. Ten of the 13 pairs were certified by medical examiners as simultaneous twin SIDS. Bass concluded that the findings in this study suggest that all 13 sets died from injuries, either unintentional or otherwise, and that these deaths could have been prevented.[59] Malloy and Freeman analysed data from the USA-linked birth and infant death certificate tapes for the years 1987–1991 to determine the risk of SIDS in twin births (n = 1056) compared with singleton births (n = 23464). They found that, independent of birth weight, twins do not appear to be at greater risk for SIDS compared with singleton births, and further that the occurrence of both twins dying of SIDS is uncommon (rate ratio, 4.0 per 100,000 twin pregnancies), and the occurrence of both twins dying on the same day is extremely uncommon (rate ratio, 0.58 per 100,000 twin pregnancies).[53] The authors speculate that the differences when compared with the results of earlier studies may be due to the fact that they were based on case series and not on analysis of an entire birth cohort. However, they admit that a limitation of their study is that when using vital statistics one cannot guarantee that the cause of death has been accurately ascribed.

Seasonal incidence

There is a marked seasonal variation in SIDS, the excess occurring in the colder, wetter months in temperate zones. In Europe and North America, most SIDS die between October and April, while in Australasia the monthly incidence is reversed.[9,25,28,29,33,38–40,42,43,67–71] In tropical and subtropical zones, no clear pattern emerges, partly because many of the countries in these latitudes are relatively underdeveloped so have both high infant mortality, and often death certification and statistical records of lesser accuracy. SIDS undoubtedly occurs in the tropics, however, but the incidence is often swamped by that of more obvious disease. Returning to temperate zones, many efforts have been made to relate SIDS to changes of temperature and the incidence of respiratory infections in the community. The results are conflicting, but there seems little doubt that respiratory infections are a precipitating trigger in SIDS.

Social class and housing

This is not the place to expand upon the social epidemiology of cot death, but there is ample evidence that lower levels of social disadvantage, as measured by occupation and housing quality, are strongly related to the incidence of SIDS.[34,37,43,72–74] It is difficult to reconcile these epidemiological factors with the numerous pathological theories and the few facts concerning the aetiology of sudden infant death.

The case history in sudden infant death

The history is usually brief and remarkably similar from case to case. The infant is either quite well on the preceding day or (in about half the victims) has trivial symptoms, usually of upper respiratory infection or a bowel upset. Even these symptoms may be overstated, as the history is of necessity taken retrospectively from distraught parents trying to rationalize the tragedy.

The story usually records that the infant was put to sleep in the evening and was found dead in the morning when a parent first visited it. Alternatively, the baby was given an early morning feed when it appeared well, but was later found dead in its sleeping place. Most infants are found dead in the first half of the day, before mid-morning. A minority die (or are found dead) in the afternoon and evening. Death can be rapid and silent. Though most victims die unobserved, the author's (BK) experience can confirm that a number of cases indicate that an infant observed to be quite well at a given moment can be found dead within 5 minutes, and cases are on record of SIDS occurring in hospital and even in a physician's arms.

The scene of death and external findings

The scene of the death is rarely available for examination in its original state (Table 21.3). When found, the child is naturally either rushed to a doctor or a hospital, or an ambulance team arrives and attempts resuscitation, again usually hurrying to a hospital emergency department.

When found, a few children have slight oedema fluid exuding from the mouth. This may sometimes be blood-tinged, and frank bleeding – apparently from a congested mouth or pharyngeal vessel – is occasionally seen.

Stomach contents may be present in the mouth, nostrils or on the face, but this must not be assumed to be a cause of death (from aspiration), as is discussed below. The hands of the child are often found to be clenched around fibres from the bedclothes, as if there were spasmodic agonal grasping movements.

Some children are found under the bedclothes, even huddled upside down at the foot of the cot. Again, this has no significance, as thousands of healthy infants habitually sleep in this way without suffering SIDS.

A number of infants have been found moist with sweat and even with a raised body temperature.[50,75] The significance of this is not known, but part of the recent preventative advice given in Britain, is to avoid overwrapping and overheating.

There are no external findings of significance. The face may be pale or slightly cyanosed or congested; there are no petechial haemorrhages in the face or eyes. The posture at death is not necessarily relevant, even if the initial sleeping position is important in the aetiology – some are found face down and may have a pallid area around the mouth and nose where pressure has prevented post-mortem hypostasis from settling. This develops after death and on no account must be misinterpreted as a pressure mark indicating suffocation.

Autopsy appearances

These have given rise to much controversy over the years. Essentially the gross findings are nil, almost by definition. If any significant pathological lesion is found on naked-eye examination, the death ceases to be a true SIDS, and is categorized as whatever lesion was discovered. The proportion of 'explained' cot deaths varies greatly with the pathologist, though this variation is more in relation to microscopic than gross findings. Of all babies found dead in their sleeping place, that is, 'cot deaths', most will be true SIDS, but a few will have a significant pathological condition. The relative proportions of these two subsets varies from pathologist to pathologist. Many would accept that about 15 per cent reveal some pathological lesions at autopsy, though this is not to say that those lesions – sometimes slight – were a factor in the death. For example, some mild congenital heart lesion or the presence of Down's syndrome is occasionally revealed, but this is not to say that they were causative. Thus almost all SIDS are cot deaths, but not all cot deaths are SIDS.

The external appearances have already been discussed and are essentially negative, apart from inconstant froth at the lips and nostrils, and fibres sometimes clenched in the fists. The length, weight and other physical

Table 21.3 Scene of death investigation

External conditions	Surrounding	Situation found dead	External examination
Size of room	Type of bed	Body position	Signs of death
Size of windows	Type of blanket	Clothing	Time of death
Heating	Size and weight of blanket	Covering	Resuscitation
Air exchange rate	Type of mattress	Sweating	Signs of violence
Room temperature	Toys in bed	Vomiting	Body temperature
Temperature outside		Fixation used	

Modified from Bajanowski and Venneman[39] with kind permission of Elsevier.

measurements are of no direct relevance, though naturally they must always be carefully recorded as in any other infant autopsy, for it may transpire that the death was not a typical SIDS.

Internally, the findings are again non-specific in a typical SIDS.[39] A large number of reports now exist on the microscopy, microbiology and biochemistry of the syndrome, but no diagnostic criteria have yet been confirmed. The following naked-eye features may be present at autopsy:

- Petechial haemorrhages on the visceral pleura.
- Petechial haemorrhages in the thymus gland.
- Petechiae or larger ecchymoses on the epicardial surface of the heart, especially posteriorly. These petechiae have been the subject of intense controversy since they were first described in infant deaths by Tardieu in 1855, but they are almost certainly agonal in origin. One explanation suggests that they are the result of forced inspiratory efforts against a closed airway, the latter being either from laryngeal spasm or from a collapsed pharynx in hypotonic infants, but neither of these hypotheses has been substantiated. Petechiae in the thorax are found in about 70 per cent of true SIDS infants. Thymic haemorrhages are often prominent, the organ being studded with both petechiae and larger ecchymoses: it has been claimed recently that in SIDS as opposed to mechanical suffocation, the haemorrhages are in the thymic cortex, rather than the medulla, but few pathologists accept this (Fig. 21.1).
- Gastric contents, usually milk-curds, in the air passages. All too often this has been used by some pathologists as the definite cause of death, but there is no evidence that it is the reason for the death. It is either an agonal regurgitation or even a post-mortem phenomenon. In a series of 100 consecutive autopsies, including adults and children, the author (BK) found gastric contents in greater or lesser amount in no less than 25 per cent of cadavers, almost all of which had quite satisfactory pathological lesions to account for death. This aspect is discussed in more detail in Chapter 14.
- Respiratory infections in the form of inflamed laryngeal or tracheobronchial mucosa are not common, but are macroscopically evident in some SIDS victims. If the infection is severe enough to produce pus and especially if there are obvious inflammatory changes in the lung parenchyma, then the death is removed from the SIDS category into a fatal chest infection group. The finding of minimal 'inflammatory' cells on microscopy must be viewed with caution. Some pathologists undoubtedly lay too much emphasis on sparse or small collections of leucocytes in the peribronchial zones. In control infants, small foci of lymphocytes are common and can be disregarded. It is usually the lung histology that causes the variations in the proportions of 'cot deaths' that are classified as true 'SIDS'.
- Pulmonary oedema is common, though usually moderate in intensity. The surface of the lungs often shows patchy sublobular partial collapse, with areas of blue lung alternating with better-aerated pink zones.



Figure 21.1 Subpleural haemorrhages – the original 'Tardieu spots'. These are far more pronounced than those seen in adult lungs, being taken from a case of SIDS, in which 70 per cent of cases exhibit these lesions.

In some infants dying unexpectedly, abnormalities such as Down's syndrome, congenital heart disease or other chronic systemic disease are found. The problem then is to decide whether the death should be ascribed to 'SIDS' or to the obvious disease, even though there is no evidence that such a disease should have suddenly caused death. There is a natural temptation to use an established lesion to explain the death, especially as both doctors and parents tend to be less unhappy with a specific disease process than with the rather nebulous diagnosis of 'SIDS'.

In most cases, however, there is no real reason why an infant with Down's syndrome, perfectly well one night, should be found dead the following morning – and many relatively mild (and often previously undiagnosed) congenital defects similarly are unlikely to cause death in such an abrupt manner. It is probably more logical to assume that SIDS has occurred in a child with Down's or a septal defect, or whatever. It may be accepted that this defect may be one factor among the many involved in SIDS, and therefore it is probably reasonable to enter 'SIDS' in Part I of the certificate and add the other lesion in Part II, as a contributory cause.

Histological findings in SIDS

Again a huge and controversial topic, there have been numerous papers on the microscopic appearances in SIDS. Much of this is pure research material and is often irreproducible by other workers.

Most interest has focused on the lung changes and especially evidence of pulmonary inflammation. The frequency with which positive findings are made depends upon the criteria threshold of the observer, as mentioned earlier. Peribronchiolar cell infiltration is the main finding and some workers claim to find an abnormal cellular response in the majority of SIDS material. Others, more used to the less equivocal appearances in adults, fail to attach significance to marginal increases in cell population in the peribronchial zone.

Many of the other findings are inconstant and claimed by a variety of researchers. For example, Richard Naeye supported his hypothesis of chronic hypoxia by finding thickened pulmonary artery walls, gliosis in the brainstem, retention of brown fat in the adrenals and abnormalities in the carotid body.[76] Changes in the myocardium, adrenals, parathyroids and liver have all been described, but have either not survived critical assessment, appear incompatible with clinical and epidemiological data, or fail to be reproducible in subsequent investigations.

Theories of causation

Since the mid-1970s over 10000 articles have appeared concerning sudden infant death and one now needs review papers merely to keep up with mainstream research. Theories include allergy to cow's-milk proteins, house-mite allergy, deliberate suffocation, spinal haemorrhages, botulism, calcium deficiency, selenium deficiency, biotin deficiency, vitamin E deficiency, vitamin C deficiency, vitamin D deficiency, thiamine deficiency, hypoglycaemia, hypothyroidism, magnesium deficiency, carbon monoxide poisoning, carbon dioxide poisoning, overlaying, pharyngeal hypotonia, nasal obstruction, tracheobronchitis, respiratory syncytial virus, prolonged sleep apnoea, deficient or abnormal pulmonary surfactant, cardiac conduction defects, sodium overload in feeds, narrow foramen magnum, hyperthermia, hypothermia, influenza infection, metabolic enzyme defects, immunodeficiency, hypogammaglobulinaemia, deleterious genetic mutations and many others.[17,18,77–110]

In 1989 and again in 1994, press publicity in the UK drew considerable attention to claims that fungal growth on certain antiflammable chemicals used on cot mattress covers produced gases containing arsenic and antimony, and some chemical analyses showed that antimony could be demonstrated in some SIDS tissues.[90,111] However, a causative link has not been proven and the theory fails to fit the epidemiology – especially as SIDS has been occurring for hundreds and probably thousands of years before mattress covers existed. Reports of cot deaths can be found in sources as ancient as the Old Testament and twelfth century Welsh literature.

In the 1970s and early 1980s, one hypothesis gained widespread favour and was beginning to gain general acceptance. This was the claim that some infants, with poor respiratory drive, suffered from exaggeration of the normal periods of apnoea that all infants have during sleep. A complex mechanism was built up in which progressive hypoxia and failure to respond adequately to hypercapnia and hypoxia drove the sleeping infant into a descending spiral of hypoxia–apnoea–hypoxia, which ended in bradycardia and cardiac arrest. Respiratory infections, sleep, and nasal obstruction contributed to an acute-on-chronic state of hypoxia, which histological findings claimed to substantiate.

This attractive theory was largely deflated, however, when prospective studies of infants with sleep apnoea and other respiratory problems were found to have no greater risk of SIDS than normal controls. The theory led to a great popularity of apnoea alarms, which parents of subsequent children following a SIDS loss have insisted on using. There is no evidence that they have any beneficial effect, other than reassurance of the parents; indeed, in some instances, the stress of waiting for the alarm to sound and the many false alarms, have led to marital problems.

In the present state of knowledge, it seems that SIDS is the final common pathway that leads to death in infants who have been compromised by a number of deleterious factors, which have to come together in one baby at one time in order to summate to a fatal outcome. The factors may be quite different in each case, but all manifest themselves in terminal acute cardiorespiratory failure.

Some of the factors are known such as sleep, which depresses the brainstem, and virus infections – especially of the respiratory tract – which provide a viraemia, reduce oxygenation and may narrow the effective airway lumen by mucus and exudate. Other factors are 'constitutional', in that many SIDS victims are physically compromised in some way, often since fetal life, being premature and of low birth weight (though most SIDS are neither of these). Other factors from the long list given above may operate in certain circumstances, such as botulism which has been detected in individual cases presenting as SIDS.[112–115]

It is thus futile to search for 'the cause' of cot death, as there is no single cause, but a galaxy of factors that vary from death to death, though the mediating terminal mechanism appears to be the same.

One of the most difficult aspects is the failure of pathological explanations to be compatible with epidemiological findings. It has been shown that non-specific health-care improvements reduce the incidence of SIDS, such as in the excellent ante-natal and post-natal services of countries such as Finland and Holland, which have the lowest SIDS rates – and the Sheffield project, where it was shown that the strongest factor in reducing incidence was the use the family made of the health services.

As far as the pathologist is concerned, his function is to perform a meticulous autopsy, to exclude any overt natural disease or injuries, and to offer sympathetic advice to those parents who want an explanation of the syndrome in comprehensible lay terms. There are several highly proficient counselling charities in Britain, the USA and other countries, who can provide literature and direct help to parents – and who also usually support most of the ambitious research schemes now operating.

The SIDS autopsy

The routine for an autopsy on a sudden infant death follows that for any infant and is little different from that in suspected child abuse. Indeed, exclusion of child abuse is a prime consideration as, although there is no aetiological connection between the two conditions, sometimes occult abuse – or sometimes genuine accident – may present as a 'cot death'. Some pathologists, both forensic and paediatric, insist on a whole-body post-mortem imaging or radiological survey before commencing the autopsy and, where such facilities exist, this is a wise precaution. Full measurements of the infant are essential, as in all paediatric autopsies, to monitor the size-for-age of the child and to compare it with centile graphs, provided the birth weight is known.

A recent recommendation for a standardised investigation of SIDS has been outlined by Bajanowski *et al.* with a standardized autopsy protocol (SAP), which is similar and in accord with the Council of Europe recommendation on the harmonization of medico-legal autopsy rules.[116]

The gross examination is the standard meticulous scrutiny of all external surfaces, orifices and organs. A full histological survey is vital, with even more blocks being taken than may be the norm for many forensic pathologists. The lungs in particular should be extensively sampled and six blocks is a bare minimum for these organs. In addition to histology, swabs should be taken from the major air passages and the lung parenchyma for microbiological culture, and heart blood may also be cultured. The middle ears should always be opened and a swab taken if infection is suspected. A separate piece of lung should be sent for virological culture. Where there has been any history of gut upset before death, a sample of ileal contents should be cultured. It has to be said that the return on such microbiological and virological studies is poor in terms of positive findings, both because of the post-mortem interval and because many of the micro-organisms found may be indistinguishable from commensals or post-mortem contaminants.

Similarly, by the very definition of SIDS, significant histological findings are absent. If a definite pathological lesion capable of causing death is discovered, the case is removed from the SIDS category and classified according to the disease process discovered. The problem arises when 'significant' or 'definite' has to be defined, as the criteria threshold of different pathologists varies considerably, especially where the diagnosis of an inflammatory condition in the lungs is concerned.

Medico-legal problems in cot deaths

Differentiating SIDS from external suffocation

This is the oldest problem in cot death and one that is virtually insoluble on purely pathological grounds.[117–122] The signs of infant suffocation are usually nil and the signs of SIDS are nil, so in a completely negative autopsy no reliable criteria exist. The presence of intrathoracic petechiae has little or no diagnostic value, in spite of one recent report that claims to distinguish SIDS from mechanical suffocation by the confinement of petechiae to the thymic cortex in SIDS. In any event, they are usually absent in known suffocation, such as those caused by a plastic bag over the head, yet some 70 per cent of SIDS have serosal petechiae.

In Britain, there are about 290 cot deaths each year and around 2000 in the USA. The majority of these were found dead with the face uncovered, and in a posture where the mouth and nose are not obstructed. No one believes that all these children have been smothered by their parents; therefore, as petechiae are valueless for differentiation, it is not possible for an autopsy to state or even suggest that any particular child has been suffocated. This naturally presupposes the absence of facial bruising, scratching or other positive signs that would immediately remove the case from the SIDS category.

It is possible for circumstantial or other non-medical history to suggest or confirm deliberate suffocation, though this is extremely rare and not the concern of the pathologist. A caution must be offered about maternal confessions of smothering, however, as several instances are known where such a confession has proved totally false, the desperately bereaved mother in her grief and recrimination deluding herself in order to rationalize an inexplicable tragedy.

Multiple sudden infant deaths

Again, these pose a formidable problem for pathologist, paediatrician and investigating authority. Considering that there is no objective positive criteria to diagnose SIDS, as it means that we do not know the cause of death, it does not seem feasible to make statistical calculations on the probability of repeat sudden unexpected deaths of such data.[123–126] There is always the possibility of foul play in such circumstances, though some familial metabolic or other genetic disease – albeit obscure – must also be considered. Even where no trace of the latter can be detected by the most exhaustive medical investigations, if the autopsies reveal no positive evidence of mechanical suffocation or other demonstrable cause of death, the pathologist cannot then substantiate any allegation of mechanical suffocation. He can – and should – express his concern to the investigating authorities but, if their investigations produce no corroborative evidence, it is pointless for him to continue to support a hypothesis that cannot be substantiated by any pathological evidence.

Counselling of parents

Many families, primarily the mother, have an intense desire to know why their baby died, a need that is often unfulfilled by any official contacts, such as with a coroner. Once any legal processes are complete, there is no reason why a pathologist should not meet and offer explanations to the parents of a child upon whom he has performed an autopsy. Often an earlier line of counselling is provided by a paediatrician, but some mothers wish to talk to the pathologist. Both Adelson and Knight have advocated that the pathologist should make himself readily available for this purpose, though some pathologists shelter behind an imaginary legal barrier to avoid what should be an ethical obligation.[28,127]

References

1 Barret AM. Sudden death in infancy. In: Gairdner D (ed). *Recent Adv in Pædiatrics*. London: Churchill, 1954, pp. 301–20.
2 Beckwith JB. Discussion of terminology and definition of sudden infant death syndrome. In: *The Second International Conference on Causes of Sudden Death in Infants*. Seattle, WA: University of Washington Press, 1969.
3 Willinger M, James LS, Catz C. Defining the sudden infant death syndrome (SIDS): deliberations of an expert panel convened by the National Institute of Child Health and Human Development. *Pediatr Pathol* 1991;11(5):677–84.
4 Beckwith, JB. *Discussion of Terminology and Definition of the Sudden Infant Death Syndrome* Ithaca: Perinatology Press, 1993.
5 Byard RW, Lee V. A re-audit of the use of definitions of sudden infant death syndrome (SIDS) in peer-reviewed literature. *J Forensic Leg Med* 2012;19(8):455–6.
6 Mathers CD, *et al*. Counting the dead and what they died from: an assessment of the global status of cause of death data. *Bull World Health Organ* 2005;83(3):171–7.
7 Mahapatra P, *et al*. Civil registration systems and vital statistics: successes and missed opportunities. *Lancet* 2007;370(9599):1653–63.
8 Rognum TO. [Crib death or cot death in the Nordic countries. A forensic pathologist's point of view]. *Ugeskr Laeger* 1999;161(48):6612–8.
9 Golding J, Limerick S, McFarlane A. *Sudden Infant Death*. Shepton Mallet: Open Books, 1985.
10 Martin JA, *et al*. Births: final data for 2010. In: *National Vital Statistics Reports* 2012. Hyattsville: National Center for Health Statistics, 2012.
11 CDC. *Sudden Infant Death Syndrome (SIDS) and Sudden, Unexpected Infant Death (SUID)*. 2013 August 9, 2013 [cited 2013 Oct 29]; Available from: http://www.cdc.gov/SIDS/index.htm.
12 Corbin T. Investigation into sudden infant deaths and unascertained infant deaths in England and Wales 1995–2003. *Health Stat Quart* 2005;27:17–23.
13 Fleming P, *et al*. Bedding and sleeping position in the sudden infant death syndrome. *Br Med J* 1990;301(6756):871–2.
14 Fleming PJ, *et al*. Interaction between bedding and sleeping position in the sudden infant death syndrome: a population based case-control study. *Br Med J* 1990;301(6743):85–9.

15 Gilbert RE, *et al*. Signs of illness preceding sudden unexpected death in infants. *Br Med J* 1990;300(6734):1237–9.

16 Cole TJ, *et al*. Baby check and the Avon infant mortality study. *Arch Dis Child* 1991;66(9):1077–8.

17 Fleming PJ, Azaz Y, Wigfield R. Development of thermoregulation in infancy: possible implications for SIDS. *J Clin Pathol* 1992;45(11 Suppl):17–19.

18 Gilbert R, *et al*. Combined effect of infection and heavy wrapping on the risk of sudden unexpected infant death. *Arch Dis Child* 1992;67(2):171–7.

19 Golding J, Fleming P, Parkes J. Cot deaths and sleep position campaigns. *Lancet* 1992;339(8795):748–9.

20 Wigfield RE, *et al*. Can the fall in Avon's sudden infant death rate be explained by changes in sleeping position? *Br Med J* 1992;304(6822):282–3.

21 Stewart A, *et al*. Lessons from the New Zealand and UK cot death campaigns. *Acta Paediatr Suppl* 1993;82 Suppl 389: 119–23.

22 de Jonge GA, Engelberts AC. Cot deaths and sleeping position. *Lancet* 1989;2(8672):1149–50.

23 de Jonge GA, *et al*. Cot death and prone sleeping position in The Netherlands. *Br Med J* 1989;298(6675):722.

24 Engelberts AC, de Jonge GA. Choice of sleeping position for infants: possible association with cot death. *Arch Dis Child* 1990;65(4):462–7.

25 Engelberts AC, de Jonge GA, Kostense PJ. An analysis of trends in the incidence of sudden infant death in The Netherlands 1969–89. *J Paediatr Child Health* 1991;27(6):329–33.

26 de Jonge GA, *et al*. Sleeping position for infants and cot death in The Netherlands 1985–91. *Arch Dis Child* 1993;69(6):660–3.

27 Office for National Statistics. Unexplained Deaths in Infancy – England and Wales, 2010. In: *Statistical Bulletin* 2012, Office for National Statistics.

28 Knight B. *Sudden Death in Infancy: the 'Cot Death' Syndrome*. London: Faber and Faber, 1983.

29 Rintahaka PJ, Hirvonen J. The epidemiology of sudden infant death syndrome in Finland in 1969–1980. *Forensic Sci Int* 1986;30(2–3):219–33.

30 Hoffman HJ, Hillman LS. Epidemiology of the sudden infant death syndrome: maternal, neonatal, and postneonatal risk factors. *Clin Perinatol* 1992;19(4):717–37.

31 Mitchell EA. The changing epidemiology of SIDS following the national risk reduction campaigns. *Pediatr Pulmonol Suppl* 1997;16:117–9.

32 Oyen N, *et al*. Combined effects of sleeping position and prenatal risk factors in sudden infant death syndrome: the Nordic Epidemiological SIDS Study. *Pediatrics* 1997;100(4): 613–21.

33 Vege A, Rognum TO, Opdal SH. SIDS – changes in the epidemiological pattern in eastern Norway 1984–1996. *Forensic Sci Int* 1998;93(2–3):155–66.

34 Leach CE, *et al*. Epidemiology of SIDS and explained sudden infant deaths. CESDI SUDI Research Group. *Pediatrics* 1999;104(4):e43.

35 Krous HF, *et al*. Sudden infant death syndrome and unclassified sudden infant deaths: a definitional and diagnostic approach. *Pediatrics* 2004;114(1):234–8.

36 Li L, *et al*. Investigation of sudden infant deaths in the State of Maryland (1990–2000). *Forensic Sci Int* 2005;148(2–3):85–92.

37 Blair PS, *et al*. Major epidemiological changes in sudden infant death syndrome: a 20-year population-based study in the UK. *Lancet* 2006;367(9507):314–9.

38 Tursan d'Espaignet E, *et al*. Trends in sudden infant death syndrome in Australia from 1980 to 2002. *Forensic Sci Med Pathol* 2008;4(2):83–90.

39 Bajanowski T, Vennemann M. Sudden infant death syndrome (SIDS). In: Siegel JA, Saukko PJ (eds). *Encyclopedia of Forensic Sciences*. Waltham: Academic Press, 2013, pp. 63–9.

40 Froggatt P, Lynas MA, MacKenzie G. Epidemiology of sudden unexpected death in infants ('cot death') in Northern Ireland. *Br J Prev Soc Med* 1971;25(3):119–34.

41 Oyen N, *et al*. Secular trends of sudden infant death syndrome in Norway 1967-1988: application of a method of case identification to Norwegian registry data. *Paediatr Perinat Epidemiol* 1994;8(3):263–81.

42 Byard RW, Krous HF. *Sudden Infant Death Syndrome: Problems, Progress, and Possibilities*. London: Arnold; Oxford University Press, 2001.

43 Fujita T. Sudden infant death syndrome in Japan 1995–1998. *Forensic Sci Int* 2002;130 Suppl:S71–7.

44 Findeisen M, *et al*. German study on sudden infant death (GeSID): design, epidemiological and pathological profile. *Int J Legal Med* 2004;118(3):163–9.

45 Adams MM. The descriptive epidemiology of sudden infant deaths among natives and whites in Alaska. *Am J Epidemiol* 1985;122(4):637–43.

46 Irwin KL, Mannino S, Daling J. Sudden infant death syndrome in Washington State: why are Native American infants at greater risk than white infants? *J Pediatr* 1992;121(2):242–7.

47 Alessandri LM, *et al*. An analysis of sudden infant death syndrome in aboriginal infants. *Early Hum Dev* 1996;45(3):235–44.

48 Borman B, Fraser J, de Boer G. A national study of sudden infant death syndrome in New Zealand. *N Z Med J* 1988;101(848):413–5.

49 Mitchell EA, *et al*. Ethnic differences in mortality from sudden infant death syndrome in New Zealand. *Br Med J* 1993;306(6869):13–16.

50 Kahn A, *et al*. Sudden infant death syndrome in a twin: a comparison of sibling histories. *Pediatrics* 1986;78(1):146–50.

51 Beal S. Sudden infant death syndrome in twins. *Pediatrics* 1989;84(6):1038–44.

52 Kleinman JC, Fowler MG, Kessel SS. Comparison of infant mortality among twins and singletons: United States 1960 and 1983. *Am J Epidemiol* 1991;133(2):133–43.

53 Malloy MH, Freeman DH, Jr. Sudden infant death syndrome among twins. *Arch Pediatr Adolesc Med* 1999;153(7):736–40.

54 Platt MJ, Pharoah PO. The epidemiology of sudden infant death syndrome. *Arch Dis Child* 2003;88(1):27–9.

55 Getahun D, *et al*. Sudden infant death syndrome among twin births: United States, 1995–1998. *J Perinatol* 2004;24(9):544–51.

56 Malloy MH, Freeman DH. SIDS among twins: a confounded relationship. *J Perinatol* 2005;25(4):293; author reply 294.

57 Pharoah PO, Platt MJ. Sudden infant death syndrome in twins and singletons. *Twin Res Hum Genet* 2007;10(4):644–8.

58 Smialek JE. Simultaneous sudden infant death syndrome in twins. *Pediatrics* 1986;77(6):816–21.

59 Bass M. The fallacy of the simultaneous sudden infant death syndrome in twins. *Am J Forensic Med Pathol* 1989;10(3):200–5.

60 Ramos V, Hernandez AF, Villanueva E. Simultaneous death of twins. An environmental hazard or SIDS? *Am J Forensic Med Pathol* 1997;18(1):75–8.

61 Carter N, Rutty GN, Green MA. Simultaneous death of twins: an environmental hazard or SIDS? *Am J Forensic Med Pathol* 1998;19(2):195–6.

62 Koehler SA, *et al*. Simultaneous sudden infant death syndrome: a proposed definition and worldwide review of cases. *Am J Forensic Med Pathol* 2001;22(1):23–32.

63 Ladham S, *et al*. Simultaneous sudden infant death syndrome: a case report. *Am J Forensic Med Pathol* 2001;22(1):33–7.

64 Balci Y, *et al*. Simultaneous sudden infant death syndrome. *J Forensic Leg Med* 2007;14(2):87–91.

65 Mitchell EA, Elder DE, Zuccollo J. Simultaneous sudden unexpected death in infancy of twins: case report. *Int J Legal Med* 2010;124(6):631–5.

66 Huang P, *et al*. Sudden twin infant death on the same day: a case report and review of the literature. *Forensic Sci Med Pathol* 2013;9(2):225–30.

67 McGlashan ND, Grice AC. Sudden infant deaths and seasonality in Tasmania, 1970–1976. *Soc Sci Med* 1983;17(13):885–8.

68 Helweg-Larsen K, Bay H, Mac F. A statistical analysis of the seasonality in sudden infant death syndrome. *Int J Epidemiol* 1985;14(4):566–74.

69 Beal SM. Sudden infant death syndrome: epidemiological comparisons between South Australia and communities with a different incidence. *Aust Paediatr J* 1986;22 Suppl 1:13–16.

70 Alm B, *et al*. Changes in the epidemiology of sudden infant death syndrome in Sweden 1973–1996. *Arch Dis Child* 2001;84(1):24–30.

71 Mollborg P, Alm B. Sudden infant death syndrome during low incidence in Sweden 1997–2005. *Acta Paediatr* 2010;99(1): 94–8.

72 Fleming PJ, *et al*. Sudden infant death syndrome and social deprivation: assessing epidemiological factors after post-matching for deprivation. *Paediatr Perinat Epidemiol* 2003;17(3):272–80.

73 Blair PS, *et al*. Hazardous cosleeping environments and risk factors amenable to change: case-control study of SIDS in south west England. *Br Med J* 2009;339:b3666.

74 Wood AM, *et al*. Trends in socioeconomic inequalities in risk of sudden infant death syndrome, other causes of infant mortality, and stillbirth in Scotland: population based study. *Br Med J* 2012;344:e1552.

75 Krous HF, *et al*. Sudden infant death while awake. *Forensic Sci Med Pathol* 2008;4(1):40–6.

76 Naeye RL. Pulmonary arterial abnormalities in the sudden-infant-death syndrome. *N Engl J Med* 1973; 289(22):1167–70.

77 Money DF. Vitamin E and selenium deficiencies and their possible aetiological role in the sudden death in infants syndrome. *N Z Med J* 1970;71(452):32–4.

78 Read DJ. The aetiology of the sudden infant death syndrome: current ideas on breathing and sleep and possible links to deranged thiamine neurochemistry. *Aust N Z J Med* 1978; 8(3):322–36.

79 Tonkin SL, *et al*. The pharyngeal effect of partial nasal obstruction. *Pediatrics* 1979;63(2):261–71.

80 Johnson AR, Hood RL, Emery JL. Biotin and the sudden infant death syndrome. *Nature* 1980;285(5761):159–60.

81 Southall DP, *et al*. Prolonged apnea and cardiac arrhythmias in infants discharged from neonatal intensive care units: failure to predict an increased risk for sudden infant death syndrome. *Pediatrics* 1982;70(6):844–51.

82 Jeffrey HE, *et al*. Thiamine deficiency–a neglected problem of infants and mothers–possible relationships to sudden infant death syndrome. *Aust N Z J Obstet Gynaecol* 1985;25(3): 198–202.

83 James D, *et al*. Surfactant abnormality and the sudden infant death syndrome – a primary or secondary phenomenon? *Arch Dis Child* 1990;65(7):774–8.

84 Burchell A, *et al*. Glucose metabolism and hypoglycaemia in SIDS. *J Clin Pathol* 1992;45(11 Suppl):39–45.

85 Byard RW, *et al*. *Clostridium botulinum* and sudden infant death syndrome: a 10 year prospective study. *J Paediatr Child Health* 1992;28(2):156–7.

86 Fleming KA. Viral respiratory infection and SIDS. *J Clin Pathol* 1992;45(11 Suppl):29–32.

87 Fleming PJ, *et al*. Interactions between thermoregulation and the control of respiration in infants: possible relationship to sudden infant death. *Acta Paediatr Suppl* 1993;82Suppl 389:57–9.

88 Fleming PJ, *et al*. Fire retardants, biocides, plasticisers, and sudden infant deaths. *Br Med J* 1994;309(6969):1594–6.

89 Platt MS, *et al*. Endotoxemia in sudden infant death syndrome. *Am J Forensic Med Pathol* 1994;15(3):261–5.

90 Blair P, *et al*. Plastic mattresses and sudden infant death syndrome. *Lancet* 1995;345(8951):720.

91 Sawczenko A, Fleming PJ. Thermal stress, sleeping position, and the sudden infant death syndrome. *Sleep* 1996;19(10 Suppl):S267–70.

92 Hagan LL, *et al*. Sudden infant death syndrome: a search for allergen hypersensitivity. *Ann Allergy Asthma Immunol* 1998; 80(3):227–31.

93 Caddell JL. A review of the status of magnesium and related minerals in the sudden infant death syndrome (SIDS). *Magnes Res* 2000;13(3):205–16.

94 Buckley MG, Variend S, Walls AF. Elevated serum concentrations of beta-tryptase, but not alpha-tryptase, in sudden infant death syndrome (SIDS). An investigation of anaphylactic mechanisms. *Clin Exp Allergy* 2001;31(11):1696–704.

95 Fleming PJ, *et al*. The UK accelerated immunisation programme and sudden unexpected death in infancy: case-control study. *Br Med J* 2001;322(7290):822.

96 Sawaguchi T, *et al*. From physiology to pathology: arousal deficiency theory in sudden infant death syndrome (SIDS) – with reference to apoptosis and neuronal plasticity. *Forensic Sci Int* 2002;130 Suppl:S37–43.

97 Sawaguchi T, *et al*. Association between sleep apnea and reactive astrocytes in brainstems of victims of SIDS and in control infants. *Forensic Sci Int* 2002;130 Suppl: S30–6.

98 Alm B, *et al*. Vitamin A and sudden infant death syndrome in Scandinavia 1992–1995. *Acta Paediatr* 2003;92(2):162–4.

99 Turillazzi E, *et al*. Heterozygous nonsense SCN5A mutation W822X explains a simultaneous sudden infant death syndrome. *Virchows Arch* 2008;453(2):209–16.

100 Opdal SH, *et al*. Mitochondrial DNA point mutations detected in four cases of sudden infant death syndrome. *Acta Paediatr* 1999; 88(9):957–60.

101 Opdal SH, *et al*. Possible role of mtDNA mutations in sudden infant death. *Pediatr Neurol* 2002;27(1):23–9.

102 Morris JA. Common bacterial toxins and physiological vulnerability to sudden infant death: the role of deleterious genetic mutations. *FEMS Immunol Med Microbiol* 2004; 42(1):42–7.

103 Tester DJ, Ackerman MJ. Sudden infant death syndrome: how significant are the cardiac channelopathies? *Cardiovasc Res* 2005;67(3):388–96.

104 Wedekind H, *et al*. Sudden infant death syndrome and long QT syndrome: an epidemiological and genetic study. *Int J Legal Med* 2006;120(3):129–37.

105 Opdal SH, Rognum TO. The IL6 -174G/C polymorphism and sudden infant death syndrome. *Hum Immunol* 2007;68(6):541–3.

106 Tester DJ, *et al.* A mechanism for sudden infant death syndrome (SIDS): stress-induced leak via ryanodine receptors. *Heart Rhythm* 2007;4(6):733–9.

107 Courts C, Madea B. Genetics of the sudden infant death syndrome. *Forensic Sci Int* 2010;203(1–3):25–33.

108 Dettmeyer RB, Kandolf R. Cardiomyopathies – misdiagnosed as sudden infant death syndrome (SIDS). *Forensic Sci Int* 2010; 194(1–3):e21–4.

109 Hu D, *et al.* A novel rare variant in SCN1Bb linked to Brugada syndrome and SIDS by combined modulation of Na(v)1.5 and K(v)4.3 channel currents. *Heart Rhythm* 2012;9(5):760–9.

110 Courts C, Grabmuller M, Madea B. Dysregulation of heart and brain specific micro-RNA in sudden infant death syndrome. *Forensic Sci Int* 2013;228(1–3):70–4.

111 Emery JL. Sleeping position, cot mattresses, and cot deaths. *Lancet* 1988;2(8613):738–9.

112 Aureli P, Ferrini AM. [Identification of C. botulinum spores in a case of sudden infant death in Italy. Description of a clinical case]. *Minerva Pediatr* 1988;40(2):125–6.

113 Bartram U, Singer D. [Infant botulism and sudden infant death syndrome]. *Klin Padiatr* 2004;216(1):26–30.

114 Fischer D, Freislederer A, Jorch G. [Sudden death of twins: botulism because of contamination by pap vegetables]. *Klin Padiatr* 2004;216(1):31–5.

115 Nevas M, *et al.* Infant botulism acquired from household dust presenting as sudden infant death syndrome. *J Clin Microbiol* 2005;43(1):511–3.

116 Council of Europe. Recommendation no. R (99) 3 of the Committee of Ministers to member states on the harmonization of medico-legal autopsy rules. *Forensic Sci Int* 2000;111(1–3):5–58.

117 Cashell AW. Homicide as a cause of the sudden infant death syndrome. *Am J Forensic Med Pathol* 1987;8(3):256–8.

118 Bajanowski T, *et al.* Unnatural causes of sudden unexpected deaths initially thought to be sudden infant death syndrome. *Int J Legal Med* 2005;119(4):213–6.

119 Bohnert M, Grosse Perdekamp M, Pollak S. Three subsequent infanticides covered up as SIDS. *Int J Legal Med* 2005;119(1): 31–4.

120 Vennemann B, *et al.* Suffocation and poisoning – the hard-hitting side of Munchausen syndrome by proxy. *Int J Legal Med* 2005;119(2):98–102.

121 Krous HF, *et al.* Pulmonary intra-alveolar hemorrhage in SIDS and suffocation. *J Forensic Leg Med* 2007;14(8):461–70.

122 Krous HF, *et al.* A comparison of pulmonary intra-alveolar hemorrhage in cases of sudden infant death due to SIDS in a safe sleep environment or to suffocation. *Forensic Sci Int* 2007;172(1):56–62.

123 Carpenter RG, *et al.* Repeat sudden unexpected and unexplained infant deaths: natural or unnatural? *Lancet* 2005; 365(9453):29–35.

124 Di Maio VJ. Repeat sudden unexpected infant deaths. *Lancet* 2005;365(9465):1137–8; author reply 1138.

125 Bacon CJ, Braithwaite WY, Hey EN. Uncertainty in classification of repeat sudden unexpected infant deaths in Care of the Next Infant programme. *Br Med J* 2007;335(7611): 129–31.

126 Nobles R, Schiff D. Misleading statistics within criminal trials. *Med Sci Law* 2007;47(1):7–10.

127 Adelson L. *The Pathology of Homicide*. Springfield Thomas, 1974.

This page intentionally left blank

CHAPTER 22

Fatal Child Abuse

- General aspects of child abuse
- Modes of death in child abuse
- The range of injuries in child abuse
- Surface bruising
- Skeletal damage in child abuse
- Bone diseases and infant fractures
- Head injury in child abuse
- Visceral injury in child abuse
- Damage to eyes, ears and mouth
- Burns in child abuse
- Bite marks in child abuse
- Other injuries in child abuse
- The autopsy in child abuse
- References

There is now a vast collection of publications on the child abuse syndrome, including international journals devoted to the topic. Most of this interest concerns the clinician, as child abuse is now a major concern in paediatrics. When no intervention is offered, an abused child has a risk of having eventually fatal injuries, so unfortunately the forensic pathologist will be involved in this tragic problem from time to time. This chapter will deal solely with the physical manifestations of the child abuse syndrome as seen at autopsy, though naturally these will in large measure coincide with the non-fatal injuries seen by clinicians.

General aspects of child abuse

Though the modern phase of recognition of the syndrome dates only from the middle decades of the 20th century, almost all the classical features were described by Tardieu in 1860.[1] In 1946, Caffey published his well-known first paper and in 1962 Kempe and co-workers published their survey on 'The battered-child syndrome'.[2,3] From then on, an avalanche of articles led to the present intense awareness of the problem that throws into stark contrast the apparent unawareness of the medical profession during the previous century.

Though definitions are variable, it can be said that the 'child abuse syndrome' (also known as the 'battered baby' or 'non-accidental injury in childhood') exists when an infant or child suffers repetitive physical injuries inflicted by a parent or guardian, in circumstances that exclude accident.

Most of the fatal victims are young, more than two-thirds being under 3 years of age.[4–30]

The true incidence of fatal child maltreatment is not known.[31] In the USA in 2012 it is estimated 1640 children died from abuse and neglect, which is a rate of 2.20 deaths per 100,000 children (2.54 boys *vs.* 1.94 girls). Nearly three-quarters (70.3 per cent) of all child fatalities were younger than 3 years old. Four-fifths (80.0 per cent) of child fatalities were caused by one or both parents.[32] Putnam-Hornstein *et al.* linked records of 514,232 children born in California between 1999 and 2006, and referred to child protective services for maltreatment, to vital birth and death data to estimate variations in risk of fatal injury before age 5 years. They reported that children with a previous allegation of physical abuse sustained fatal injuries at 1.7 times the rate of children referred for neglect.[28]

In England, every case of fatal child abuse or neglect is subject to a multi-agency Serious Case Review (SCR). There are equivalent case reviews in Northern Ireland, Scotland and in Cymru/Wales. The purpose of them is to establish whether there are lessons to be learned about the way in which local professionals and organizations work together to safeguard and promote the welfare of children. A Local Safeguarding Children Board (LSCB) must undertake a SCR when:

- abuse or neglect of a child is known or suspected; and
- either – (i) the child has died; or (ii) the child has been seriously harmed and there is cause for concern as to the way in which the authority, their Board partners or other relevant persons have worked together to safeguard the child.

Each LSCB is required to notify the Office for Standards in Education, Children's Services and Skills (OFSTED) of any case, which may result in a SCR.

Sidebotham *et al.* reviewed 457 incidents, which progressed to a SCR during 2005–2009. Of these 276 related to fatalities, of which 59 per cent were in males. The median age of the children was 16 months at the time of the incident, with a range of 0–215 months. 27 per cent of children were of non-White ethnicity; 29.5 per cent of children were known to child protection services prior to the incident. In 108 subjects, death was considered to be directly caused by physical abuse or neglect. In a further 138, maltreatment was considered a factor in the death, though not the direct cause of death. In 30 the nature of the death was not clear. Taking estimated resident population within the age group as a baseline, the annual incidence of fatal maltreatment was 1.44 per 100,000 per year (0–4 years). Excluding those deaths related to but not directly caused by maltreatment, the average was 0.67 per 100,000 per year (0–4 years).[26]

The syndrome includes, of course, psychological and sexual abuse, but the forensic pathologist can only be concerned with physical damage, some aspect of which has led to death. Though all homicides of children are 'child abuse' in the broad sense, the term is usually reserved for a fatal outcome in those who have suffered repetitive ill-treatment, though admittedly some cases span the borderline between chronic injuries and a single episode of trauma.

The definition of 'child abuse' is itself controversial, as what is unacceptable now may well have been considered valid and even desirable discipline in Victorian times. However, serious physical injury must be wrong, irrespective of societal attitudes.

Even so, for a pathologist to label an injury as 'child abuse' or 'non-accidental injury (NAI)' is to be rather pejorative and judgemental, so perhaps 'adult-induced injury' might be a more neutral description, which leaves decisions as to motivation to those who possess a wider picture of the whole circumstances. Having said that, the more gross forms of injury are self-evidently 'abuse' but, in lesser degrees of trauma, it may be impossible to differentiate deliberate battering from inexpert rough handling, albeit contributed to by exasperation, panic or even attempts at resuscitation.

Though it is vital to recognize non-fatal child abuse, because of the need for intervention to prevent the recurrence and risk of death, it can be almost as tragic to falsely accuse and/or convict parents or guardians where the injuries were non-culpable.

There has sometimes been perhaps some excess of zeal on the part of paediatricians, radiologists, accident surgeons and pathologists to overinterpret injuries and scenarios that had an alternative and less sinister explanation. Though it is natural and vital for doctors to protect children and their siblings, medical opinion has to remain free from emotive bias and be confined within the bounds of what can be proved in each individual case, or injustice may be done. Over a decade ago, a situation developed where even innocent parents were afraid to take their accidentally injured child to a doctor, for fear of the euphemism NAI being applied.

Modes of death in child abuse

The majority of deaths are caused manually, either by hitting or beating with the hands, shaking, throwing, dropping and – less often – by burning or suffocation.[12,19–21,33–39] It is exceptional for death to be caused by the impact of a blunt instrument, though non-fatal bruises from beating with a strap, for instance, are sometimes seen. Shooting, strangling and stabbing are characteristic of classical homicide, which is distinct from the child abuse syndrome.

The most common mode of death is head injury.[40–42] Next in frequency is rupture of an abdominal viscus, leaving a wide range of miscellaneous injuries to account for the small remainder.[18,43,44]

The range of injuries in child abuse

Concentrating on autopsy findings, the various types of trauma will be described, though many will not in themselves have caused or even contributed to death. Their recognition is none the less vital as, at the end of the examination, they may well be the decisive factors that may distinguish an accident from deliberate maltreatment.

Surface bruising

One of the classic aphorisms in the study of child abuse was stated by the forensic pathologists, Cameron, Johnson and Camps, who said: "The skin and bones tell a story which the child is either too young or too frightened to tell" (Figs 22.1–22.3).[45]

Skin bruising is the most common injury and may be seen almost anywhere on the child's body but external bruising may be absent in spite of fatal



Figure 22.1 Multiple fingertip bruises on the chest and abdominal wall of an infant left with a male babysitter. The child was ill on the mother's return and died during admission to a hospital emergency department.



Figure 22.2 Bruising of wrist and back of the hand after maltreatment by a mentally ill mother.

intracranial injuries.[46] In a systematic review of 88 studies of children aged 0–18 years with confirmed abusive etiology and visceral injuries, Maguire *et al.* found that abdominal bruising was absent in up to 80 per cent of those with abdominal injuries.[47]



Figure 22.3 Bruising of upper extremity after maltreatment by a mentally ill mother.

There are, however, certain sites of predilection which help to strengthen the diagnosis of abuse:

- Bruising around the limbs, especially the wrist and forearms, upper arms, thighs and – in small infants – around the ankles. These places form convenient 'handles' for an adult to grip the child. In the small infant the lower leg bruises may indicate that the child has been held by the leg or ankle in order to swing it – and may be associated with head injuries. The older child, as an adult, may be gripped by the upper arms in order to be shaken.
- The buttocks are a frequent site of bruising from hand smacks or beating with a strap. Bruises on the thigh are less common, but on the outer side may signify slaps and on the inner, possible sexual interference.
- The face is often bruised, especially the cheeks and mouth area, from slaps, which may also be present on the forehead and ears. Associated damage to the mouth and eyes is common. Bruising of the scalp is harder to see because of the hair, but is often part of deeper head injury.
- Bruises on the chest, abdomen and neck are usually from finger pressure rather than slaps or blows. Those on the abdomen and lower chest may be associated with deep visceral injury. Bruises may be of any size or type, but a common variety in child abuse is the small discoid lesion about 1–2 cm in diameter; these were once called 'sixpenny bruises' from the size of coinage at that time. These are caused by impact or pressure from the finger-pads of adults, and may be seen in groups around the limbs and on the neck, chest or abdomen (Figs 22.1–22.3).

Bruises from slapping or punching may be larger and irregular. Occasionally, a partial or even almost whole handprint may be seen outlined in bruises on the buttocks or trunk.

The age of bruises is an important issue in child abuse because:

- The observed age may be at variance with the history given by a parent, so increasing the suspicion of a non-accidental event.
- Bruises of different ages indicate episodes of injury at different times, one of the hallmarks of child abuse that usually continues over a period.

Though it is impossible to be accurate about the absolute age of a bruise, those of markedly different colours cannot have been inflicted during the same episode. The interpretation of patterns and the ageing of bruises are more fully considered in Chapter 4, but any bruise with yellow colouration must be more than 18 hours since infliction.



Figure 22.4 Injuries found at autopsy of an infant left with a male babysitter showing a generalized haemoperitoneum.



Figure 22.5 The infant shown in Figs 22.1 and 22.4 showing a full-thickness tear extending through the liver. Rupture of an abdominal viscus is the second most common mode of death in child abuse, head injury being the most frequent.

Skeletal damage in child abuse

This is the second part of the aphorism about battered children as, both clinically and pathologically, diagnosis is largely a radiological matter. Just as a whole-body survey is needed in the live victim, so it is essential before an autopsy on a suspected fatal case of child abuse.[48–52] When available post-mortem imaging or conventional radiological skeletal survey on all infants prior to autopsy is recommended, if they had not been under constant clinical care for some well-recognized natural disease. This would include all sudden infant deaths but, because of lack of facilities and finance, many pathologists have to confine their requests for such extensive radiology to those deaths in which there was some possibility of abuse, though this decision may lead to injuries being missed.

The range of skeletal injuries seen in child abuse is wide and there are very extensive publications on the subject, including at least one textbook by Cameron and Rae and a section on the radiology by Evans and Knight and more recently by Brogdon.[53–55]

Worlock *et al.* compared fractures in 35 abused children with 826 controls and found that the abused were all under 5 years old, whereas 85 per cent of the others were more than 5 years. The abused infants were more likely to have multiple fractures, and to have bruising of the head and neck. Rib fractures were almost confined to abused children, when major chest trauma was excluded. Spiral fractures of the humeral shaft were more common, though classical chipped metaphyses were uncommon. They concluded that one in eight infants under 18 months of age with a fracture had been abused.[56]

King *et al.* analysed 429 fractures in 189 battered children and observed that approximately half of the patients had a single fracture. The most commonly fractured bones were the humerus, femur and tibia, transverse fractures being the most common type.[15]

Duffy *et al.* assessed the use of the skeletal survey (SS) in a large retrospective, descriptive study comprising 703 children to identify characteristics of those who are most likely to have unsuspected fractures. A positive SS result was defined as a SS that identified a previously unsuspected fracture(s). Of the 703 SSs, 10.8 per cent yielded positive results. Children <6 months of age, children with an apparent life-threatening event or seizure and children with suspected abusive head trauma had the highest rates of positive SS results. Of children with positive SS results, 79 per cent had ≥1 healing fracture.[50]

Karmazyn *et al.* evaluated the prevalence and site of fractures detected on SSs performed for suspected abuse from 2003 to 2009 of children younger than 2 years. Nine hundred thirty children (515 boys and 415 girls) with a median age of 6 months met the entry criteria for the study. Fractures were detected in 317 children (34 per cent), of whom 166 (18 per cent) had multiple fractures. The most common sites for fractures were the long bones (21 per cent), ribs (10 per cent), skull (7 per cent), and clavicle (2 per cent). Ten children (1 per cent) had fractures in the spine (n = 3), pelvis (n = 1), hands (n = 6), and feet (n = 2). All 10 children had other signs of physical abuse.[51]

Hughes-Roberts *et al.* evaluated potential differences between live (LSS) and post-mortem skeletal surveys (PMSS) in 195 subjects suspected of NAI. There were significantly fewer positive PMSS (11/128; 8.6 per cent) than LSS (16/67; 23.8 per cent), but no difference between the actual injuries encountered. Of those who had a positive SS, dead children were significantly younger (mean age 2.6 +/− 3.4 months old) than live children (7.8 +/− 6.9 months old; $p < 0.05$).[52]

The following is a summary of the more important bony lesions.

Fractures of the skull

Skull fractures are common in fatal child abuse, often in association with intracranial haemorrhage, usually subdural, though numerically less than half of infants with subdural haematomata have skull fractures.[57] Of 4465 childhood head injuries, 1187 had skull fractures, but that there was little correlation with neurological signs and intracranial damage, subdural haemorrhage (SDH) being twice as frequent in the non-fracture cases (Fig. 22.6).

Fractures have been discussed in relation to head injuries in Chapter 5, but some particular features in child abuse must be mentioned, as it is a controversial subject, especially when such cases come to trial.

The most common fracture lies in the occipitoparietal area, but the differentiation from accidental falls is impossible on anatomical or radiological grounds alone, in spite of the dogmatic claims of some radiologists. An infant's skull is more flexible than that of an adult and may absorb some impacts without fracturing. Occasionally, a parietal bone may 'dimple' inwards without cracking, much as a table-tennis ball may be dented with a thumb. The skull of a child is much thinner than that of an adult,



Figure 22.6 Fractured skull of an infant after repeated blows against the floor by a mentally ill mother.

even though the brain size and weight is greater relative to the post-cranial mass. This means that there are two opposing factors operating:

- Because of the thin skull, less force is required for fracturing.
- Because of the elasticity or 'springiness' of the skull, recovery from distortion caused by impact is greater, so more force is needed to fracture the pliable bone, relative to its thickness.

Notwithstanding the flexibility, however, it remains a fact that an infant skull will fracture with the application of much less mechanical force than would be needed to fracture a mature skull. In addition, because the cranium is more easily deformed, a momentary depression of the skull can impinge upon the underlying brain (including membranes), damage it and return to its original shape so that, even in the absence of a fracture, brain damage is more likely to occur.

There is now a large literature on infant fractures (especially of the skull) in relation to child abuse, some of it contradictory.

One aspect that arouses much controversy is the which can (a) fracture a child's skull and (b) cause brain damage. The two injuries are certainly not synonymous, as it is clear that most fractures, both in infants and adults, are not accompanied by any brain damage or neurological effects. However, forces that can cause a skull fracture certainly **can** – though not **must** – cause brain or meningeal lesions, and it is impossible to forecast what will happen following a fall of even minor magnitude.

In respect of skull fractures, Weber experimentally dropped dead infants from a horizontal position at only 'table height' (82 cm, 34 inches) onto a variety of surfaces and found that fractures were common.[58] Fifteen infants less than 8 months old were dropped passively from a horizontal position onto concrete, carpet and linoleum; all developed cranial vault fractures in various positions. Though most fractures were in the parietal bones, some extended into the occipital bone. In 1985, Weber again dropped dead infants from 82 cm (34 inches) onto soft cushioning, such as 10 cm (4 inches) thick foam mat and 8 cm (3.2 inches) thick double blanket.[59] Fractures were much less frequent, as was to be expected, but still one occurred on the thick foam and four out of 25 drops onto the folded blanket, all from only 82 cm (34 inches).

Holczabeck *et al.* analysed 380 patient records of infants (under 1 year of age) who had been brought to hospital because of a fall. Most of them were considered to be accidental falls, two were definitive and one suspected victim of abuse.[60] The distance of the falls varied from 35 cm to 1.1 m (approximately 1–4 ft) except for the two definitive and one suspected victim of abuse where the exact injury mechanism was unknown. Severe injuries occurred in only 36 (9.5 per cent), two of whom with skull fractures were operated but subsequently died. Altogether 17 (4.5 per cent) of them had skull fractures; in 13 there were additional fractures of the upper and lower limbs and in six of the clavicle.

Reichelderfer *et al.* indicated that serious head injuries in playgrounds can occur when the impact force exceeds 50 g (gravity force); a fall of only 7.5 cm (3 inches) onto concrete can generate 150–200 g and one of 0.3 m (1 foot) no less than 475–525 g.[61]

In 246 falls of infants under 5 years from bed or low structures less than 90 cm (36 inches) high, Helfer *et al.* found no serious injuries or deaths.[62] Of these, 161 occurred at home and 175 had some injury, including two skull fractures. In 85 hospital falls, there were 28 injuries, with one skull fracture. Nimityongskul and Anderson investigated 76 childhood falls in hospital, 75 per cent of which were in children younger than 5 years.[63] The height of fall was between 30 and 91 cm (1 and 3 ft), and only one doubtful skull fracture occurred.

Of 398 falls studied by Williams, 106 were observed by independent witnesses.[64] There were 14 severe injuries in falls between 4.5 and 12.2 m (15 and 40 ft), but below 3 m (10 ft), there were no life-threatening injuries, though three skull fractures were detected. Similarly, Reiber found three skull fractures in infants who had died after witnessed short falls of less than 1 m (3 ft).[41] This was from a series of coroners' cases where all had intracranial bleeding. One 21-month-old infant fell 1.5–1.8 m (5–6 ft) and had a SDH, but no skull fracture. Another 17-month-old child fell only 0.6–0.9 m (2–3 ft), but suffered a SDH and cerebral contusion. Reiber gives a good short survey of the competing literature, indicating that opinions fall into two groups – the 'major injury–major fall' set and the 'major injury–minor fall' camp.

Hall *et al.*'s series confirms that severe or fatal damage can occasionally arise from low falls.[65] In a 4-year study, there were 18 deaths following falls from less than 0.9 m (3 ft). Two of these were witnessed by medical care persons, excluding abuse as a covert reason. Sixteen other similar deaths were not so witnessed, but abuse was not corroborated as a cause.

Chadwick *et al.*, analysing 317 childhood falls, saw seven deaths in 100 falls from less than 1.20 m (4 ft), but doubted the veracity of the histories, as there was only one death in those who fell between 3 and 13.7 m (10 and 45 ft).[66] Hobbs studied 89 children with skull fractures, 29 thought to have been abused. Of 20 deaths, 19 were abused.[67] The characteristics of the battered infant fractures were multiplicity or complex configuration; depressed, wide and 'growing' fractures, the latter meaning widening of the fracture line after infliction; accidental fractures were felt to be narrow, linear and single, usually in the parietal area.

Leventhal *et al.* investigated 104 infant skull fractures and concluded that abuse was the cause in 34 per cent, accident in 62 per cent, the rest being doubtful.[68] Billmire and Myers claimed that 64 per cent of all infant head injuries, excluding simple fractures, were caused by abuse and that of serious intracranial damage, 95 per cent were from abuse.[40]

Plunkett reviewed 18 fall-related head injury fatalities associated with the use of playground equipment filed in the United States Consumer Product Safety Commission database. The age of the victims varied between 12 months and 13 years of whom 10 were 5 years old or younger. The falls were from 0.6 to 3 m (2–10 ft); however, the exact height of the fall could be determined in only 10 cases. Half of the falls of the 10 youngest victims were unwitnessed and only four of them were followed by a full autopsy and one by a limited autopsy. The author concluded that an infant or child may suffer a fatal head injury from a fall of less than 3 m (10 ft) but received critical comments from various authors.[69–71]

Thompson *et al.* reviewed in a prospective, descriptive study short-distance household falls of 79 children aged 0–4 years. Injuries were rated according to the Abbreviated Injury Scale (AIS). AIS 1-injuries included mostly lacerations and contusions and two subjects with radial head subluxation (nursemaid's elbow). AIS 2-injuries consisted of fractures (six skull, two clavicle, three radius and ulna, four supracondylar humerus, one femur, and one metatarsal). There were two AIS 3-injuries, which were both small, isolated subdural haematomas. The first was a 3 mm subdural haematoma located in the left posterior frontal region. The second was a very thin right frontoparietal subdural haematoma accompanied by a right parietal minimally depressed skull fracture. Both children with subdural haematomas were clinically well appearing and had no neurological abnormalities. No subjects had AIS 2 or greater injuries to more than one body region, and no subjects had injuries classified as AIS 4 or higher. The mean fall height for subjects in the no/minor injuries category was 80 cm (2.6 ft) compared with 91 cm (3 ft) in the moderate/serious injury category. The authors found that furniture height, impact velocity, and child body mass index (BMI) had the greatest influence on injury severity outcomes. Children with moderate or serious injuries tended to have fallen from greater heights, had greater impact velocities and had a lower BMI than those with minor or no injuries.[72]

These varying figures emphasize the lack of consensus in the literature.

Though the immature skull has more flexibility, once its elastic limit is exceeded during deformation, it will fracture. The pattern of fracturing is similar to that in the adult, but there are some variations because of the presence of open sutures and fontanelles. Fracture lines tend to end at sutures, but if they cross them there is frequently a lateral displacement so that the two limbs of the fracture are not in line. Most instances where what appears to be a fracture line crossing a suture with a 'side-step' are really two independent fractures either approaching or receding from each other, the origins or terminations being slightly offset. The most common example is seen in a child who has been dropped on the vertex of the head. Both parietal bones may then deform and crack transversely from the vertex anterior to the point of impact, the bilateral fracture lines running downwards towards the parietal bosses. The upper ends of both fractures terminate in the sagittal suture, but may be 'staggered' by a centimetre or so.

Another common fracture is a horizontal crack running backwards from the frontoparietal suture, which courses across the parietal bone, often turning down towards the base of the skull. This can be caused by a blow or fall on the side or top of the head. Such fractures can occur bilaterally, which is then an indication of an impact on the vertex of the skull, which causes marked depression of the top of the skull with crack fractures along the lines of maximum stress. These are then more marked on the outer aspect than the inner table – though the diploë of infants' skulls are absent or only partially formed, according to the age. Of course, such bilateral fractures can also be caused by two separate impacts on each side of the head; here multiple bruises on or under the scalp may assist in interpretation.

The frontal bone is less often involved than the parietotemporal area, the frontal suture that is still present in young infants giving more flexibility than in the fused older bone. Occipital fractures may occur from falls onto the back of the head, but again these are much less common than cracks at the vertex or sides of the cranium, though, as the experiments of Weber showed, occipital bone cracks can occur from simple low-level falls in small infants. Wherever the vault fractures, if it is severe enough, extension lines may run down into the base of the skull, but this is not a frequent finding in child abuse injuries.

Sutural 'diastasis' (separation) may occur with or without fractures, the loosely knit skull plates being easily parted by distortion of the calvarium when struck. As mentioned above, some fractures widen after infliction (sometimes due to rising intracranial pressure). These so-called 'growing fractures' are thought by some writers to be more likely to be associated with abuse, though logic would relate it more to severity of impact rather than to motivation.

Limb fractures

These provide some of the most characteristic signs of child abuse, as injuries are common around the metaphyses and epiphyses of growing bones, as well as being the cause of periosteal lesions. Most of the limb injuries are indirect, that is, the bone damage is caused by stresses from abnormal angulation, torsion or traction, rather than from a direct impact upon the bone. Swinging the child by the wrists or ankles, dragging it by an arm or shin and violent shaking using the limbs as 'handles', are the usual mechanisms.

Avulsion of the metaphysis or chipping of the edges of the metaphyses or epiphyses may occur, with small fragments seen isolated on radiographs. Swinging, wrenching or twisting actions can fragment the metaphysis. Small pieces of the adjacent cortex and parts of the provisional zone of calcification may be avulsed from the shaft. The epiphysis may even separate from the metaphysis. Cameron and Rae suggested that metaphyseal fragments are virtually pathognomonic of child abuse.[53]

Kleinman *et al.* compared the prevalence of the classic metaphyseal lesion in a retrospective skeletal survey in infants at low and high risk for abuse (low risk: n = 42; age range, 0.4–12 months; mean age 4.4 months/high risk: n = 18; age range, 0.8–10.3 months; mean age 4.6 months). At least one classic metaphyseal lesion was identified in nine infants (50 per cent) in the high-risk category but none in the low-risk group, supporting the view that the classic metaphyseal lesion is a high-specificity indicator of infant abuse.[73]

The periosteum in infants is only loosely attached to the bone and easily lifts where there is shearing or traction injury. In a series of 82 fractures in 63 children (mean age 4.8 years) altogether 228 films were independently assessed by three paediatric radiologists blinded to the age of the fractures.[74] Soft tissue swelling was identified by two or more radiologists in 59 per cent of the radiographs at 1–2 days after fractures. Periosteal reaction was first seen at day 5 and was present in 62 per cent of the films obtained between 15 and 35 days after the fracture. Blood accumulates under the raised periosteum and this rapidly calcifies (usually within 7–14 days) to give a characteristic radiological picture of a bony shell extending along the shaft, often thicker at the extremity, having a lumpy, irregular profile.[54,75] In almost half the cases, this may be seen radiographically within 1 week.[76] The calcified rim may extend around the end of the metaphysis and epiphysis, or between the two, giving a 'bucket-handle' loop effect around the end of the bone, especially the lower end of the femur.

In early infancy it must be appreciated that some breech deliveries have legs that radiologically show long, smooth periosteal thickening secondary to subperiosteal bleeding caused by handling during delivery. It is also accepted that mere growth can produce faint subperiosteal calcification, but this is symmetrical and limited to the central parts of the shaft, keeping clear of the metaphyses.

A spiral fracture of the diaphysis of a long bone must be considered a suspicious injury in infants, as such a lesion is likely to be the result of a twisting strain, unlikely to occur in accidental circumstances.

The lower end of the shaft of a long bone may be 'squared-off', as described by Caffey, by metaphyseal fragments reuniting.[2] Damage to the epiphyseal cartilage may cause permanent growth defects, sometimes with increased growth from hyperaemia following injury. The axis of growth may be deviated and cupping of the metaphysis may occur because of retarded longitudinal growth in the centre.

Although the metaphyseal and epiphyseal lesions described above are classically those seen in child abuse, transverse and spiral fractures of the diaphysis are also common. In a series of 100 cases reported by Kogutt *et al.*, these fractures were more common than the injuries to ends of the bones.[77]

Damage to the chest cage

Apart from occasional perinatal fractures during delivery, accidental fractures of ribs are very uncommon in infants, though the incidence is a matter of considerable controversy.[78]

Melville *et al.* highlighted the difficulty in detecting first rib fractures on SSs and describe four anterior first rib fractures in three abused infants. They did not find in literature a case of first rib fracture in a healthy infant that was not the result of child abuse, and suggested that, compared with other rib fractures, first rib fractures in infants are particularly specific for child abuse.[79]

In child abuse, ribs are commonly fractured, often several consecutive bones being affected on one or both sides. The damage may be fresh or old, giving different radiological appearances. The most characteristic picture of old fractures is of sequential callus formation seen in a vertical line down one or both paravertebral gutters. These form a 'string-of-beads' appearance on X-ray (Fig. 22.7), where the ribs have been fractured near their angles, a sufficient time previously for new bone formation to occur – probably a minimum of 10 days, though dating is notoriously variable, and even the claims by experienced radiologists to date fractures have been confounded by a knowledge of the actual time of breakage.

These multiple posterior fractures are more common in small infants who have been picked up by adult hands under the armpits and squeezed from side to side. Whether or not such fractures can be caused by innocent handling, albeit rough or robust, as opposed to angry or impatient violence, is again a matter of dispute, beyond the competence of doctors to resolve – although this does not deter some from expressing strong opinions based on weak facts (Fig. 22.8).



Figure 22.7 Chest radiograph of an infant showing multiple callus formation on the necks of the ribs, giving a 'string-of-beads' appearance down the paravertebral gutter. These indicate previous multiple fractures caused by lateral squeezing by adult hands.



Figure 22.8 Recent fractures of ribs of an abused infant. These breaks are near the necks of the ribs in the paravertebral gutter, caused by side-to-side squeezing of the chest.

These fractures, a centimetre or so from the head of the ribs, are due to the rib being levered against the transverse process until breaking point is reached. They may be very difficult or impossible to see as fresh lesions on radiographs, if the fracture line is not exactly in line with the X-ray beam. This explains the occasional discrepancy between the radiologist's and the pathologist's report; the fractures are much more visible after a week or two, when callus is present.

If such injuries are recent (probably less than 10 days) no visible callus is formed, but the fractures may be seen on X-ray and confirmed at autopsy. However, as with fractures elsewhere – and perhaps more often in ribs than skull – the radiological and dissection diagnosis sometimes does not concur. Fractures seen at autopsy may not be visible radiologically – and conversely, alleged fractures seen on films may not be discoverable at autopsy, even after the most diligent dissection.

Rib fractures in the axillary line are likely to be the result of anteroposterior pressure, rather than side-to-side squeezing, but this mechanism is not exclusive.

With fresh fractures found at autopsy, the possibility of chest compression during cardiopulmonary resuscitation must always be considered, even though some paediatricians and radiologists will strenuously deny the possibility of this happening. The literature has different opinions on this matter, though it is admittedly very uncommon. As with other aspects of child abuse, the published material seems to flow more from those who lean towards abuse in the majority of injured children, rather from those who retain a more cautious approach and admit to the possibility of an innocent explanation.

It must be conceded that pliable infant ribs are unlikely to be broken by proper cardiac massage, which in infants should be performed with finger pressure; however, lay persons, especially in the panic of apparent collapse and death, may forcibly pump the small chest using techniques intended for adult resuscitation.

Fractures elsewhere are more likely to arise from direct impact such as a fist blow or kick. The clavicle is sometimes broken, usually from indirect stress from swinging by an arm. Fractures of the scapula or sternum are rare and arouse the probability of 'parental infliction' if some obvious trauma such as a traffic accident can be excluded.

Wherever the site of bony injury, the cardinal features that arouse suspicion are multiplicity and variation in fracture age. Though children often sustain accidental fractures, these are usually single lesions, unless some pathological bone disease is present. Similarly, the radiological demonstration of multiple fractures of varying ages must be accepted as evidence of abuse until proved otherwise.

Dating of fractures

As in the case of skin bruises, though the absolute dating of healing fractures by the state of callus formation is far from accurate, marked differences in appearance on radiology usually indicate that the injuries were not sustained at the same time.[54] As it can be shown, however, in control material, that the same person reveals callus of different extent and maturity in different but similar bones fractured contemporaneously, it becomes impossible to be dogmatic about radiological healing rates. Bone healing is rapid in healthy children and within months the abnormalities may have completely resolved, depending on the severity of the original damage.

Histological appearances are also very unreliable in placing an absolute date on fractures, in spite of assertions that this can be done with accuracy.

Bone diseases and infant fractures

Both in the differential diagnosis of childhood fractures and in the defence of allegations of child abuse, the several 'brittle bone diseases' that can cause abnormal skeletal fragility must be considered, on the grounds that lesser force, within normal parental handling or even spontaneous movements of the infant, could give rise to the observed fractures.

It has to be said at the outset that only a small minority of injured infants can be shown to have such abnormalities. When this possibility is being run as a defence in a criminal trial or child protection proceedings, it is essential to have an opinion from a radiologist or paediatrician with specialist knowledge of these conditions.

It is also important to have original radiographs, not copies, as the latter may not show marginal, indistinct abnormalities visible on the originals, although the situation is changing as conventional analog radiographic images are increasingly being converted into a digital image or have been replaced by equipment modalities that directly produce digital images that are archived in digital libraries and not as films.

Osteogenesis imperfecta

This is a group of genetic disorders of variable phenotype ranging from almost asymptomatic individuals with a mild predisposition to fractures to severe bone deformities or perinatal death. Classification by Sillence in 1979 divided osteogenesis imperfecta (OI) on the basis of clinical, radiographic and genetic criteria into four types, numbered I, II, III and IV, of which there are now also various other types.[80–83] The disease is a dominantly or recessively inherited disorder of connective tissue, with abnormal collagen, resulting in varying degrees of bone fragility, ligamentous laxity, skin fragility, sometimes blue sclera, hearing defects and dental abnormalities.

Types II and III have obvious bone disease and can hardly be confused with child abuse lesions.

Type I forms 40 per cent of cases and is the classical variety with a family history, blue sclera, Wormian bones and often dental changes, which again is hardly likely to be confused with abuse. It is type IV (only about 5 per cent of the overall disease incidence) that may cause difficulties in diagnosis, though it must be said that of all the medico-legal occasions in which this disease is postulated as a reason for brittle bones as a defence against allegations of abuse, the times upon which it can be proven are few indeed.

Type IVB, the larger subgroup, has dentinogenesis imperfecta. Type IVA has no family history of the disease, no osteoporosis, a high incidence of skull fractures and metaphyseal fractures and normal sclera. Subgroup IVA has Wormian bones, like IVB, but it has been postulated that some alleged cases of type IVA were really abuse.

It has been calculated that the incidence of type IV OI in infants under 1 year, with fractures, no family history, no Wormian bones or dentinogenesis imperfecta is one in 1–3 million. A case would occur in a city of half a million population only once every 100–300 years.

Recent techniques of genetic testing can provide evidence of OI in about 95 per cent of cases. The case reports by Ojima *et al.* and Sing Kocher and Dichtel give useful surveys of the problem.[84,85] Bone strength in otherwise normal SIDS infants has been measured by Morild *et al.* to obtain a baseline for comparison with alleged OI where this is raised as a defence against child abuse.[86]

Infantile cortical hyperostosis ('Caffey's disease')

Here there is extensive new periosteal bone laid down around the diaphyses, the bones most involved being the ribs, ulnae, clavicles and especially the mandible. The condition is rarely seen over the age of 3 years.

Congenital syphilis

This can mimic the changes seen in child abuse, though the condition is extremely rare in most Western communities. The periosteal thickening is similar to that of trauma, but tends to be symmetrical. The metaphysis may be fractured and even separated, the shaft adjacent to the metaphysis being porotic.

Copper deficiency

Again rare, this condition has radiological features in which periosteal thickening of the shafts of the long bones may be accompanied by symmetrical spurring of the metaphyses, osteoporosis, fractures and cupping of the metaphyses. Abnormalities of the hair may be present in this deficiency disease that is caused by lack of copper impairing the enzyme lysyl oxidase. The radiological appearances may cause confusion with child abuse. Other clinical features include psychomotor retardation, hypotonia, pallor, hypopigmentation of the skin and hair, prominent scalp veins, sideroblastic anaemia and neutropenia.

Menke's syndrome ('kinky hair' syndrome)

This is another rare condition also associated with copper deficiency in which there are abnormal metaphyses. It affects males only, with abnormal hair, Wormian bones in the skull and mental retardation.[87–91]

Head injury in child abuse

The most common cause of death in abused children is intracranial damage, with or without skull fracture. As well as being the most frequent fatal condition, brain trauma is responsible for the common tragedy of severe, and often permanent, neurological impairment.

The classic head injury associated with battered children is SDH was noted in Tardieu's famous publication of 1860, when he described bleeding on the side of the cerebrum and other classical features.[1] Subdural haemorrhage is most common at the extremes of life, the topic being discussed fully in Chapter 5. In infants, it most often occurs from direct impact on the skull – as in a blow or fall. It has been held that vigorous shaking, without an impact, is also a common cause of subdural bleeding. Guthkelch made the first mention of shaking of infants as a possible cause of subdural haematoma in 1971 and Caffey somewhat later.[92,93] Guthkelch considered that because not all the patients have external marks of injury on the head this suggests that in some cases repeated acceleration/deceleration rather than direct violence is the cause of the haemorrhage.

Duhaime *et al.* investigated 13 fatalities alleged to have occurred from shaking, but though seven showed no external head injury, all 13 revealed evidence of impact at autopsy. In infant models, they then compared impact with violent shaking; the mean tangential acceleration for 69 shaken babies was less than 10 g (gravity force), whereas for 60 impacts, the mean was 428 g, some 50 times greater. The mean time for shakes was 106 milliseconds, but for impacts only 20 milliseconds.[94]

According to Gennarelli *et al.* and Gennarelli and Thibault it is the rate of change and the duration of deceleration – the 'strain rate' – that is most damaging, rather than a steady deceleration. A head impacting on an immovable surface after a fall is an example of a high strain-rate injury, whereas low strain-rate injuries are those where the head decelerates over a longer period of time. Non-impact shaking of the head is a low strain-rate mechanical insult. Subdural bleeding from bridging veins is likely to occur from high strain-rate injury, even though this may be a low-energy injury, insufficient to cause cerebral tissue disruption (Fig. 22.15). By contrast, low strain-rate injuries are more likely to cause cerebral contusion, with vascular damage only if concomitant high energy is generated.[95,96]

Geddes and Whitwell have pointed out that there have been no formal systematic neuropathological studies of infant head injury and the evidence base for diffuse axonal injury (DAI) being a common finding in infant head injury is poor.[97] In fact the idea of the presence of DAI in these cases was widely accepted before the advent of the modern diagnostic methods and before the diagnostic criteria for DAI had been established. Moreover, the findings of Shannon *et al.*, the first formal study of microscopic damage in NAI, suggesting that axonal injury in such cases had been ischaemic or vascular in origin, had been largely ignored or misunderstood.[98] In a series of 53 fatally injured infants DAI was present in only two children, both of whom had multiple skull fractures and severe head injury, whereas the most frequent histological finding was global hypoxic damage in 84 per cent of the cases.[99,100] In 11 of these cases (21 per cent), however, there was gross and microscopic evidence of injury to the craniocervical junction and concomitant axonal damage in the caudal brainstem long tracts in eight subjects. This finding is in keeping with cervical hyperflexion/hyperextension injury pattern in adults and suggests as a possible mechanism of death brainstem injury, apnoea and hypoxic brain swelling. In another systematic study of dural bleeding in 50 paediatric cases, including intrauterine deaths up to infants of 5 months of age but without head injury, fresh haemorrhage into the layers of dura was found in a majority (36/50) of cases.[101] The authors believe that this is a manifestation of severe hypoxia similar to the haemorrhages found in internal organs in birth asphyxia or prematurity, rather than being caused by trauma, and postulate that hypoxia is sufficient to cause extravasation of significant amounts of venous blood both in and under the dura.

Although shaking presumably may cause SDH, it is likely that it is a relatively uncommon cause compared with impact. This situation may well have arisen because a blunt impact upon the head of infant, if spread over a wide area following contact with a flat surface, can leave no external scalp mark, no subscalp bleeding and no fracture of the skull – yet the transmitted forces can still be sufficient to cause high strain-shearing stresses within the cranium leading to subdural bleeding. In addition, as has been discussed elsewhere in this book, death is often not due to the irritative or space-occupying effects of the SDH, but is due to the intrinsic brain damage beneath, even if this is occult. Diffuse axonal injury, cerebral oedema and consequent circulatory disturbances are likely to be the fatal consequences, but detecting neuronal damage may be difficult or impossible histologically, due to the relatively rapid death of the child within 12–24 hours. Also, the microscopic features of DAI seem to be less common and less distinct in infants compared with adults, though the use of immunocytochemical methods, such as the demonstration of β-amyloid precursor protein (βAPP), described in Chapter 5, may provide a marker of use within the first few hours after injury. These factors combine to negate any proof of an impact injury and thus the shaking theory, which requires none of these criteria to be demonstrated, is an easier option.

Howard *et al.* looked at 28 instances of SDH in infants under 18 months of age.[102] All had a history more consistent with an impact rather than shaking. Six Caucasian infants fell less than 0.9 m (3 ft), such as from a chair or standing adult. Eight non-Caucasians fell from a sitting or standing position or rolled off a bed onto a carpeted floor. There was a history of shaking in three, but these also had signs of impact, the shaking being resuscitation attempts after falling. Of these, 47 per cent of the Caucasians and 20 per cent of the non-Caucasians had a skull fracture. The authors state: "Our findings do not support shaking as the only cause of SDH and also suggest that non-accidental injury is a less common cause of SDH than it is believed to be."

Japanese infants have been reported with SDH after a fall backward while sitting or standing and by hitting the head against a Japanese tatami mat (a thick mat of woven straw). Aoki and Masuzawa published a series of 26 such cases with acute SDH, with retinal haemorrhages, no loss of consciousness but, according to the authors, not caused by battering.[103] When Rekate doubted that bilateral SDHs with retinal haemorrhages could result from such minor head injuries the authors responded that their series "might include some injuries caused by abuse."[104] This example illustrates the difficulties that may arise when one tries to assess the validity of scientific theories, in this particular case, the potential harmfulness of short falls, on the basis of inadequate information in the literature.

Most direct impacts in child abuse are caused by the moving head striking a fixed object, rather than the fixed head being struck. The latter certainly occurs, but is usually from an open-handed slap, albeit often of considerable force. It is unusual for the child's head to be struck with a weapon or for a direct punch to be given with the clenched fist. The moving head injury either arises from a fall in circumstances which are non-accidental, or by deliberate swinging or throwing of the child against a hard surface, often with added momentum being gained by holding the infant's ankles or wrist. For example, one such case seen by the author (BK) was a 1-month-old baby whose father grasped it by the ankles to dash its head against stones at the edge of a canal, after which it was stripped so that its clothing could be sold in a street market, the body then being thrown into the canal.

Several other mechanisms of head injury have been described, including some seen by the author (BK) in which fathers were throwing their baby up in the air in a catching game called 'up-and-away', but for some reason missed the child on the downward return, allowing it to fall to the floor. When unwitnessed, this situation can give rise to accusations of deliberate malice, which are difficult to disprove.

Presumably, as vigorous shaking can sometimes rupture vessels in the subdural space, this must still be accepted as an alternative to impact in the causation of SDH. In an infant, the head is relatively large and heavy and the neck musculature undeveloped and often hypotonic. Thus repetitive shaking of the body – often attained by grasping under the armpits – can lead to unrestrained flexion and extension movements of the head with rotational movements of the heavy cerebral hemispheres relative to the skull.

Extradural haemorrhage is uncommon in child abuse, perhaps because the meningeal arteries do not run in deep grooves or even tunnels in the immature skull, as they do in the adult. Subarachnoid haemorrhage is, as always, an inevitable accompaniment of cerebral cortical contusion.

Brain damage may be of any type, as catalogued in Chapter 5, but as in any childhood head injury, cerebral oedema is more common than in the adult. Indeed, a significant proportion of deaths after a head injury in a child are caused by raised intracranial pressure without skull fracture, meningeal haemorrhage or visible brain injury. The typical autopsy indications may be found consisting of a heavy brain, flattened gyri, obliterated sulci and slit-like ventricles. The more florid signs seen in adults, such as herniation of the hippocampal gyrus through the tentorial gap, secondary brainstem haemorrhages and coning of the cerebellar tonsils are seen less frequently in children.

When there has been a severe head injury, with or without a fractured skull, cerebral contusion or laceration may occur. The position of this damage is usually related to the site of external impact. Although many episodes of child abuse involve dropping or throwing to the floor, classical contrecoup lesions are not as common as in similar adult injuries. They certainly do occur, but are often absent when the circumstances would indicate that contralateral contusion might be expected. The smoother internal profile of the infant skull may be a factor.

The distance of a fall sufficient to cause head injury has been mentioned earlier and is a matter of considerable controversy in the literature and amongst expert medical witnesses. There is no doubt, both from reliable anecdotal evidence and from experimental data, such as that by Weber, that skull fractures can occur in infant skulls from very low passive falls, including heights not exceeding chair or table level (82 cm; 34 in.).[58] However, as catalogued above, skulls often fracture without any significant internal brain damage – although the reverse is also true. The evidence that low falls may cause brain or meningeal lesions is much less convincing than that proving skull fractures – but the possibility exists and cannot be dismissed by inflexible, dogmatic opinion. The problem with assessing the mechanical basis of head injury is that human experimentation is virtually impossible – Weber's work on dead infants probably could not be repeated in the present ethical climate – and obviously no data can be derived from the living. Animal models are useless, so the frequent difficulties for pathologist, lawyers and the courts have to rest on available statistical evidence – which can never give a definitive answer in any one case. If a phenomenon has definitely occurred once, then it can occur again, whatever the statistical weight is against its frequency, as a precedent has been established which cannot be gainsaid as a possibility.

One of the problems is the 'standard of proof'; in the criminal courts, it is 'beyond reasonable doubt', whereas in civil matters, it only has to pass the test of 'balance of probabilities', where statistical evidence is far more persuasive.

To rely on the 'experience' of medical witnesses is also fraught with difficulty, as their anecdotal memories of previous cases will provide unsatisfactory data in respect of the causation of the injury. Where adults are accused of malice or neglect, they are very likely to fabricate or distort the circumstances of the injury, and claim that the infant fell from the chair, the arms or the bed. Even in genuine accidents, feelings of guilt, clouded recollection from grief and panic, will often lead to an inaccurate account of the circumstances, so the doctor's past experience is often of lesser value than the accused adults, the lawyers and the court imagine, due to inadequate or false knowledge of the true circumstances of previous cases.

In the USA expert testimony on novel scientific evidence used to be admissible in court only if the opinion offered was based on a "*well-recognized scientific principle or discovery … sufficiently established to have gained general acceptance in the particular field in which it belongs* (Frye *vs*. United States, 293 F. 1013, 1014 [D.C. Cir. 1923])." In 1993, the USA Supreme Court implemented major changes concerning the admittance of expert testimony. Daubert *vs*. Merrell Dow Pharmaceuticals superseded the Frye ruling in federal courts and established judges, not the scientific community, as the 'gate-keepers' regarding the credibility of scientific evidence. In 1999, another equally important decision, Kumho Tire *vs*. Carmichael, ruled that a trial court's 'gate-keeping' obligation extended to all expert testimony. The challenge of this ruling to the 'gate-keeper' in the controversy regarding the expert opinions on abusive head trauma/shaken baby syndrome can be studied in detailed reviews by Narang and Findley *et al*.[105–108]

The American Academy of Pediatrics recommended in 2009 that paediatricians embrace a less mechanistic term, abusive head trauma (AHT), when describing an inflicted injury to the head and its contents.[109] In 2011 the UK Crown Prosecution Service published a legal guidance to provide information on the stance taken by the Court of Appeal and the High Court in relation to non-accidental head injury (NAHI) cases, and according to which: "*The use of the term 'shaken baby syndrome' should now be avoided as it can be considered to have emotive connotations, and more importantly, does not adequately describe the range of causes of head injuries*."[110]

Visceral injury in child abuse

Damage to internal organs is almost always confined to the abdomen, as the heart and lungs are rarely injured.[39,47] As stated earlier, rupture of an abdominal viscus is the second most common cause of death in child abuse after head injury. Forcible impacts on either the lower chest or the abdominal wall are responsible. Direct punching or heavy 'prodding' are the usual mechanisms rather than being dropped or thrown, a common cause of head injury. Often there will be an excuse that the child fell or tripped upon some protruding obstruction, such as a toy or piece of furniture; occasionally this may be true and it is a matter of fact and interpretation as to whether the circumstantial evidence is compatible with the medical findings. The liver is frequently injured, the most common lesion being a deep tear in either lobe, sometimes being a complete penetration or, more rarely, actual detachment of hepatic tissue. A haemoperitoneum results and in fatalities, may be the proximate cause of death. A heavy blow over the lower ribs or xiphi-sternal area is the most likely site of impact (Figs 22.4, 22.5).

The small intestine is the other common target organ, the duodenum or jejunum being the most frequent site of damage (Fig. 22.9). The second part of the duodenum is vulnerable to blows in the central abdomen, as beneath this area, the duodenum crosses the midline and is liable to be 'sandwiched' between the compressed anterior abdominal wall and the promontory of the lumbar spine. As the tissue thickness is small in a child, the gut can be virtually 'guillotined' at this point and may be completely transected, appearing almost as clean-cut as if it had been done with a surgical knife. Alternatively the gut wall may be damaged and, though it may not leak or rupture at the time of impact, ischaemic and necrotic changes over the next few hours or even days may lead to a delayed rupture, with the later onset of peritonitis.

The same lesions, though rarely as sharply cut, can occur in the jejunum, often accompanied by laceration of the mesentery and haemorrhage into the peritoneal



Figure 22.9 A ruptured duodenum in an abused child who suffered a blow in the central abdomen. This relatively common mode of death in fatal child abuse is caused by the duodenum being guillotined against the lumbar spine by an impact that indents the thin anterior abdominal wall. The gut may be severed immediately or may become infarcted because of damaged blood supply over the ensuing few days, then rupture into the peritoneal cavity.



Figure 22.10 A child with numerous bruises on the body, totalling 80 on the face, neck, abdomen, back and legs. The male adult in the house claimed that she had 'slipped while being bathed'. At autopsy, there was a massive haemoperitoneum arising from multiple ruptures of the mesentery.

cavity instead of – or in addition to – leakage of intestinal contents (Fig. 22.10).

Rupture of the stomach can occur, but must be carefully differentiated from gastric rupture from non-traumatic causes and (these days) especially from external cardiac massage, which produces linear tears in the mucosa and even rupture of the complete wall.

Damage to eyes, ears and mouth

As part of general facial damage, black eyes, and scleral and conjunctival haemorrhages are often seen, but damage to the interior of the globe is much less apparent at autopsy. Some considerable time after the general recognition of the child abuse syndrome, it was discovered that a considerable proportion of victims, both live and dead, had significant internal damage to the eyes. Direct violence to the head and allegedly shaking can cause bleeding into the vitreous humour, dislocation of the lens, retinal detachment and retinal haemorrhages (Fig. 22.14).[111]

The latter can also be caused by cardiopulmonary resuscitation, where vigorous compression of the chest has been applied; the literature on this topic is controversial, but numerous papers confirm this mechanism,[112–115] yet others deny it.[116–118] Once again, there are hotly contested viewpoints in the position taken by different doctors over the aetiology of various lesions in child abuse, both by clinicians and pathologists. They are also, of course, often secondary to raised intracranial pressure from head injuries, rather than due to primary direct violence. During life, these can be diagnosed by ophthalmoscopy, but at autopsy they must be sought by dissection. As disfigurement of the body of a child must be avoided wherever possible, examination for eye lesions may be achieved either by enucleation and replacement with glass prostheses – or by opening the orbits from the anterior cranial fossae and removing the globes and orbital contents *en bloc* as described by Gilliman *et al*.[119]

Injury to the external ear is frequent, as abuse of a child is often directed at the obvious targets, such as face, head, arms, buttocks and ears. The pinnae may be bruised or even lacerated, usually by an open-handed slap. Damage to the internal ear from heavy impacts on the head may be diagnosed clinically, though often in retrospect from later deafness. At autopsy, damage to such minute structures is rarely visible, though sometimes haemorrhage into the petrous temporal bone may be found when routinely examining this area for middle-ear sepsis.

Infants and older children are commonly slapped across the mouth, the swipe usually having a tangential component that moves the tissues laterally and can tear the frenulum (or 'frenum') (Fig. 22.11). This the small median band of mucosa that joins the upper gum to the upper lip is ripped as the lip is jerked sideways. A torn labial frenum has been widely regarded as pathognomonic of abuse; however, recent literature reviews do not support the diagnosis of abuse based on a torn labial frenum in isolation.[120–123] The other possible cause of a ruptured frenulum is the forcible entry of a feeding bottle teat into the mouth of a reluctant infant. Instead of entering between the gums, the teat is rammed up between the gum and lip, causing a tear. The lesion heals rapidly, as do all injuries in the mouth and, within a few days, nothing may be seen except perhaps a loose mucosal tag or an absent frenulum, or both (Fig. 22.12).

Damage to the lips themselves is common, the type of injury varying somewhat according to whether or not the child is old enough to have teeth. In any event, bruising, swelling, abrasion and sometimes external



Figure 22.11 Bruising of the lips in child abuse caused by smacking in the mouth. When the child is old enough to have teeth, lacerations may occur inside the lips. The frenulum behind the midline of the upper lip (not shown) was ruptured in this child, a strong pointer to a blow across the upper lip.



Figure 22.12 Tearing of the frenulum of the upper lip of a child, a classical injury from a tangential slap across the mouth.

laceration may be seen. The inner mucosal aspect of the lips may be bruised even if the child has no teeth and, if the blow is hard enough, laceration can occur. This is far more likely to happen if the lips are forced against the teeth, especially the cutting edge of the incisors.

The teeth themselves may be damaged, especially in older children. Total avulsion from the sockets, loosening and breakage may occur. In small infants, developing teeth may be forced back into the sockets, like pegs into holes. Expert dental advice should be sought wherever possible when injuries to teeth and jaws are found, both in live children and at autopsy.

Burns in child abuse

Unfortunately, thermal injuries are by no means uncommon in abused infants. These may be moist scalds, dry burns or, exceptionally, electrical injuries.[9,13,19,22,33,35,124–128]

Scalds result from dipping in hot fluid and often involve over-hot bath water. The line between accident and abuse may be blurred in some cases, but it can occur as a form of chastisement. In one case, a child was deliberately held in water at over 80°C as a punishment for persistently complaining about being cold. Other scalds may be from boiling water from a kettle or saucepan deliberately being poured over the child.

Dry burns can be inflicted in innumerable ways as a deliberate and sadistic act. Children have been forcibly sat on electric cooking rings and hotplates, branded with hot shovels and electric soldering-irons, or pressed against the bars of a fire. A particular type of burn seen relatively often in abused children is never the cause of death but may be found incidentally. This is the cigarette burn, seen most often on skin not normally covered by clothing, such as the hands, arms, neck and head. Such burns are usually circular, but not always; if the cigarette has been held obliquely against the skin, the mark may be triangular. The regular shape and size usually indicate the nature of the burn, though some skin diseases may simulate an old burn, such as a small patch of impetigo. Fresh cigarette burns are red, sometimes with a narrow rim of a deeper red. When healing, they become pink and later have a silvery sheen on the surface.

Bite marks in child abuse

Most bites on the skin surface are seen either in sexual offences or in child abuse. In the author's (BK) own experience, all bitten infants have had these inflicted by the mother, though published reports indicate that both male and female guardians can bite their infant charges. The topic is discussed in more detail in Chapter 26, but as they are relatively common in child abuse, a summary is repeated here.

Bites may be seen anywhere on the child's body.[125,129] The arms, back of the hands, cheeks, shoulders, buttocks and abdomen are favoured sites (Fig. 22.13). A bite mark usually consists of two opposing semicircles, which may be incomplete. Individual teeth marks may be visible or the dental arch may be represented by a continuous line. The mark is either an abrasion or a bruise, or a combination of both. There may be confluent petechiae



Figure 22.13 An adult bite mark on the face of an abused child. Death was due to fractured skull and subdural haemorrhage.

in the centre caused by suction, but this is much more common in sexual assaults – the so-called 'love bite'. In child abuse, the centre is more often undamaged. The size of the dental arch should be carefully measured to determine whether it was formed by an adult, another child or even an animal, as is sometimes alleged in defence.

In older children, the possibility of self-biting must be borne in mind – the author (BK) has seen multiple self-bites all the way up one arm in a young person.

As with all dental matters, the advice of a dentist experienced in forensic problems is highly desirable. Not only can he confirm or exclude doubtful lesions, but he can identify individual teeth marks, make casts of any residual impression in the skin and take swabs for saliva identification. He can also examine any suspects to compare their dentition with the marks – a common excuse of the parents is that another child or even the family dog caused the bite. If no forensic odontologist is available, however, the pathologist must make the best examination possible and details are given in Chapter 26.

Other injuries in child abuse

A variety of injuries, some bizarre and sadistic, occur from time to time in battered children. The hair may be pulled out in clumps (epilation), leaving pseudoalopecia on the scalp. Fingers may be broken by hyperextension and fingertips crushed by blows or other means. Patterned marks from straps and ropes may be seen on the skin, usually on buttocks, thighs and abdomen. 'Pinch' or 'tweaking' marks are not uncommon, made by the skin being nipped between adult fingernails. These appear as two small opposing semi-circular or triangular bruises, often with a clear zone between them.

The autopsy in child abuse

This follows the usual routine for any forensic autopsy, but certain additional matters must be given close attention. Because of the emotive nature of child abuse, especially where a fatality is concerned, the pathologist must pay meticulous attention to all aspects of his examination and report. A full description of the autopsy in child abuse may be found in the chapter by Knight in *Paediatric Forensic Medicine and Pathology*.[130] The following matters must be borne in mind:

- The scene should be visited wherever possible, though usually the child will already have been removed, usually to a hospital accident department. Even a retrospective visit can be helpful, however, to assess such matters as the nature of the floor and its coverings, where falls are alleged, the height of settees and chairs, and the general size and space between walls, doors and furniture, as claims of colliding with household structures are a constant line of defence – and may well be true in some instances.
- The child should be examined in its original clothing where possible.
- The appearances before washing and other cosmetic manoeuvres should be recorded; when children die in hospital accident departments, such compassionate acts may remove useful evidence, and the balance between sympathy and justice can sometimes be hard to reconcile.
- Careful enquiries should be made about any resuscitatory attempts, as these can introduce a number of artefacts.
- Where any suspicion of abuse is present, a full post-mortem imaging and/or radiological SS should be carried out before the autopsy is begun.

- Full physical measurements must be made including weight, crown–heel length, crown–rump length, foot length and head diameter.
- A meticulous external examination must be made, covering every square centimetre of the body, including all body orifices. The interior of the mouth and lips must be searched.
- A full photographic record must be made of any abnormality discovered. Where bruising is suspected, but not definitely apparent, the use of both infrared- and ultraviolet-sensitive film has been advocated, though experience is required in their interpretation, as artefacts are common.
- Extensive dissection of subcutaneous tissues is required wherever bruising is seen or suspected. Incisions must be made into doubtful areas or the skin flayed away to reach such areas, if disfigurement is to be avoided.
- Full sampling of blood, urine, stomach contents, liver, ocular fluid and cerebrospinal fluid must be taken, according to the circumstances. It is best to be liberal with the range of samples – it is easy to discard unwanted samples, but difficult or impossible to obtain them at a later date.
- Where appropriate, skin samples for fibroblast culture and swabs for microbiological culture are taken. Blood samples for grouping and other blood characteristics may be needed and a sufficient amount for DNA testing.



Figure 22.14 Retinal haemorrhages in a 3-month-old infant who became lifeless after shaking, and was reanimated by an emergency doctor. The infant did not regain spontaneous breathing and had to be artificially ventilated. Death 6 days later from subdural haematoma due to ruptured bridging veins. At autopsy there were no signs of an impact injury.



Figure 22.15 The same infant as in Fig. 22.14 showing bleeding that had spread into the spinal subdural space.

- Bite marks may need to be swabbed for saliva and casts made of tooth indentations. The co-operation of a forensic odontologist is then vital (see Chapter 26).
- A full internal dissection of all organs is required, with full sampling for histological purposes. If post-mortem imaging of the whole body is not available, further radiographs may need to be taken on isolated bones or on the chest cage. The latter can be removed entirely by careful dissection if multiple rib fractures are present. X-rays can then be taken of the detached thoracic cage free of soft tissue and further histological blocks taken for decalcification in an attempt to date the lesions.
- If there is obvious or suspected brain damage, the brain should be removed carefully and suspended in formalin until firmly fixed. On no account should ‘wet cutting’ take place if intracranial damage or cerebral oedema is present.
- The globes of both eyes should be removed for histological examination: they can be taken entire and false eyes replaced for cosmetic purposes – or the globes and orbital contents can be removed *en bloc* via a superior approach through the base of the anterior fossa.

References

1 Tardieu A. Étude médico-légale sur les sévices et mauvais traitements exercés sur des enfants. *Ann Hyg Pub Med Leg* 1860;13:361–98.

2 Caffey J. Multiple fractures in the long bones of infants suffering from chronic subdural hematoma. *Am J Roentgenol* 1946;56:163–72.

3 Kempe CH, *et al.* The battered-child syndrome. *JAMA* 1962;181:17–24.

4 Silverman FN. Unrecognized trauma in infants, the battered child syndrome, and the syndrome of Ambroise Tardieu. Rigler Lecture. *Radiology* 1972;104(2):337–53.

5 Herbich J, *et al.* [Differential diagnosis in child abuse]. *Beitr Gerichtl Med* 1973;31:97–101.

6 Caffey J. The whiplash shaken infant syndrome: manual shaking by the extremities with whiplash-induced intracranial and intraocular bleedings, linked with residual permanent brain damage and mental retardation. *Pediatrics* 1974;54(4):396–403.

7 Lauer B, ten Broeck E, Grossman M. Battered child syndrome: review of 130 patients with controls. *Pediatrics* 1974;54(1):67–70.

8 Brown RH. The battered child syndrome. *J Forensic Sci* 1976;21(1):65–70.

9 Zumwalt RE, Hirsch CS. Subtle fatal child abuse. *Hum Pathol* 1980;11(2):167–74.

10 Christoffel KK, Liu K, Stamler J. Epidemiology of fatal child abuse: international mortality data. *J Chronic Dis* 1981;34(2–3):57–64.

11 Creighton SJ. An epidemiological study of abused children and their families in the United Kingdom between 1977 and 1982. *Child Abuse Negl* 1985;9(4):441–8.

12 Showers J, *et al.* Fatal child abuse: a two-decade review. *Pediatr Emerg Care* 1985;1(2):66–70.

13 Caniano DA, Beaver BL, Boles ET, Jr. Child abuse. An update on surgical management in 256 cases. *Ann Surg* 1986;203(2):219–24.

14 Knight B. The history of child abuse. *Forensic Sci Int* 1986; 30(2–3):135–41.

15 King J, *et al.* Analysis of 429 fractures in 189 battered children. *J Pediatr Orthop* 1988;8(5):585–9.

16 Ledbetter DJ, *et al.* Diagnostic and surgical implications of child abuse. *Arch Surg* 1988;123(9):1101–5.

17 McClain PW, *et al.* Estimates of fatal child abuse and neglect, United States, 1979 through 1988. *Pediatrics* 1993;91(2):338–43.

18 Bouska I. [Causes of death in fatal cases of child abuse 1964–1988]. *Cas Lek Cesk* 1995;134(11):344–6.

19 Ellis PS. The pathology of fatal child abuse. *Pathology* 1997;29(2):113–21.

20 Ohtsuji M, *et al.* [Fatal child abuse in Japan and Germany. Comparative retrospective study]. *Arch Kriminol* 1998;202(1–2): 8–16.

21 Vock R, *et al.* [Fatal child abuse (caused by physical violence) in Germany during 1 January 1985 to 2 October 1990. Results of a multicenter study]. *Arch Kriminol* 1999;203(3–4):73–85.

22 Sibert JR, *et al.* The incidence of severe physical child abuse in Wales. *Child Abuse Negl* 2002;26(3):267–76.

23 Hobbs C. The prevalence of child maltreatment in the United Kingdom. *Child Abuse Negl* 2005;29(9):949–51.

24 Newton AW, Vandeven AM. Update on child maltreatment. *Curr Opin Pediatr* 2008;20(2):205–12.

25 Schnitzer PG, *et al.* Public health surveillance of fatal child maltreatment: analysis of 3 state programs. *Am J Public Health* 2008;98(2):296–303.

26 Sidebotham P, *et al.* Fatal child maltreatment in England, 2005–2009. *Child Abuse Negl* 2011;35(4):299–306.

27 Damashek A, Nelson MM, aBonner BL. Fatal child maltreatment: characteristics of deaths from physical abuse versus neglect. *Child Abuse Negl* 2013;37(10):735–44.

28 Putnam-Hornstein E, *et al.* Risk of fatal injury in young children following abuse allegations: evidence from a prospective, population-based study. *Am J Public Health* 2013; 103(10):e39–44.

29 Palusci VJ, Covington TM. Child maltreatment deaths in the U.S. National Child Death Review Case Reporting System. *Child Abuse Negl* 2014;38(1):25–36.

30 Ross AH, Juarez CA. A brief history of fatal child maltreatment and neglect. *Forensic Sci Med Pathol* 2014;10(3):413–22.

31 Schnitzer PG, Gulino SP, Yuan YY. Advancing public health surveillance to estimate child maltreatment fatalities: review and recommendations. *Child Welfare* 2013;92(2):77–98.

32 *Child Maltreatment 2012.* Washington: A.f.C.a.F. U.S. Department of Health and Human Services, Administration on Children, Youth and Families, Children's Bureau, 2012.

33 Russo S, *et al.* Scald burns complicated by isopropyl alcohol intoxication. A case of fatal child abuse. *Am J Forensic Med Pathol* 1986;7(1):81–3.

34 Merrick J. [Child abuse and the lack of care. 2. An epidemiologic and social pediatric study of fatal child abuse and neglect in Denmark in 1970–1979]. *Ugeskr Laeger* 1989; 151(14):874–7.

35 Reece RM. Unusual manifestations of child abuse. *Pediatr Clin North Am* 1990;37(4):905–21.

36 Arieff AI, Kronlund BA. Fatal child abuse by forced water intoxication. *Pediatrics* 1999;103(6 Pt 1):1292–5.

37 Boos SC. Constrictive asphyxia: a recognizable form of fatal child abuse. *Child Abuse Negl* 2000;24(11):1503–7.

38 Pandya NK, *et al.* Child abuse and orthopaedic injury patterns: analysis at a level I pediatric trauma center. *J Pediatr Orthop* 2009;29(6):618–25.

39 Dedouit F, *et al.* Lethal visceral traumatic injuries secondary to child abuse: a case of practical application of autopsy, radiological and microscopic studies. *Forensic Sci Int* 2011;206(1–3):e62–6.

40 Billmire ME, Myers PA. Serious head injury in infants: accident or abuse? *Pediatrics* 1985;75(2):340–2.

41 Reiber GD. Fatal falls in childhood. How far must children fall to sustain fatal head injury? Report of cases and review of the literature. *Am J Forensic Med Pathol* 1993;14(3):201–7.

42 Bennett S, *et al.* Head injury secondary to suspected child maltreatment: results of a prospective Canadian national surveillance program. *Child Abuse Negl* 2011;35(11):930–6.

43 Vock R, Schellmann B, Schaidt G. [Isolated injuries of intestinal tract due to body maltreatment (author's transl)]. *Z Rechtsmed* 1980;84(2):155–9.

44 Dye DW, Peretti FJ, Kokes CP. Histologic evidence of repetitive blunt force abdominal trauma in four pediatric fatalities. *J Forensic Sci* 2008;53(6):1430–3.

45 Cameron JM, Johnson HR, Camps FE. The battered child syndrome. *Med Sci Law* 1966;6(1):2–21.

46 Atwal GS, *et al.* Bruising in non-accidental head injured children; a retrospective study of the prevalence, distribution and pathological associations in 24 cases. *Forensic Sci Int* 1998; 96(2–3):215–30.

47 Maguire SA, *et al.* A systematic review of abusive visceral injuries in childhood—their range and recognition. *Child Abuse Negl* 2013;37(7):430–45.

48 Kleinman PK, *et al*. Inflicted skeletal injury: a postmortem radiologic-histopathologic study in 31 infants. *Am J Roentgenol* 1995;165(3):647–50.
49 Belfer RA, Klein BL, Orr L. Use of the skeletal survey in the evaluation of child maltreatment. *Am J Emerg Med* 2001;19(2):122–4.
50 Duffy SO, *et al*. Use of skeletal surveys to evaluate for physical abuse: analysis of 703 consecutive skeletal surveys. *Pediatrics* 2011;127(1):e47–52.
51 Karmazyn B, *et al*. The prevalence of uncommon fractures on skeletal surveys performed to evaluate for suspected abuse in 930 children: should practice guidelines change? *Am J Roentgenol* 2011;197(1):W159–63.
52 Hughes-Roberts Y, *et al*. Post-mortem skeletal surveys in suspected non-accidental injury. *Clin Radiol* 2012;67(9):868–76.
53 Cameron JM, Rae LJ. *Atlas of the Battered Child Syndrome.* Edinburgh: Churchill Livingstone, 1975.
54 Evans KT, Knight B. *Forensic Radiology*, 1st edn. Oxford: Blackwell Scientific Publications, 1981.
55 Brogdon BG. Child abuse. In: Thali M, Viner MD, Brogdon BG (eds). *Brogdon's Forensic Radiology*. Boca Raton: CRC Press, 2011, pp. 255–78.
56 Worlock P, Stower M, Barbor P. Patterns of fractures in accidental and non-accidental injury in children: a comparative study. *Br Med J Clin Res Ed* 1986;293(6539):100–2.
57 Harwood Nash CE, Hendrick EB, Hudson AR. The significance of skull fractures in children. A study of 1,187 patients. *Radiology* 1971;101(1):151–6.
58 Weber W. [Experimental studies of skull fractures in infants]. *Z Rechtsmed* 1984;92(2):87–94.
59 Weber W. [Biomechanical fragility of the infant skull]. *Z Rechtsmed* 1985;94(2):93–101.
60 Holczabek W, Lachmann D, Zweymuller E. [Downfall in infancy]. *Dtsch Med Wochenschr* 1972;97(43):1640—6.
61 Reichelderfer TE, Overbach A, Greensher J. Unsafe playgrounds. *Pediatrics* 1979;64(6):962–3.
62 Helfer RE, Slovis TL, Black M. Injuries resulting when small children fall out of bed. *Pediatrics* 1977;60(4):533–5.
63 Nimityongskul P, Anderson LD. The likelihood of injuries when children fall out of bed. *J Pediatr Orthop* 1987;7(2):184–6.
64 Williams RA. Injuries in infants and small children resulting from witnessed and corroborated free falls. *J Trauma* 1991;31(10):1350–2.
65 Hall JR, *et al*. The mortality of childhood falls. *J Trauma* 1989;29(9):1273–5.
66 Chadwick DL, *et al*. Deaths from falls in children: how far is fatal? *J Trauma* 1991;31(10):1353–5.
67 Hobbs CJ. Skull fracture and the diagnosis of abuse. *Arch Dis Child* 1984;59(3):246–52.
68 Leventhal JM, *et al*. Fractures in young children. Distinguishing child abuse from unintentional injuries. *Am J Dis Child* 1993;147(1):87–92.
69 Plunkett J. Fatal pediatric head injuries caused by short-distance falls. *Am J Forensic Med Pathol* 2001;22(1):1–12.
70 Spivack B. Fatal pediatric head injuries caused by short-distance falls. *Am J Forensic Med Pathol* 2001;22(3):332–6.
71 Schaber B, *et al*. Fatal pediatric head injuries caused by short distance falls. *Am J Forensic Med Pathol* 2002;23(1):101–3; author reply 103–5.
72 Thompson AK, *et al*. Pediatric short-distance household falls: biomechanics and associated injury severity. *Accid Anal Prev* 2011;43(1):143–50.
73 Kleinman PK, *et al*. Prevalence of the classic metaphyseal lesion in infants at low versus high risk for abuse. *Am J Roentgenol* 2011;197(4):1005–8.
74 Prosser I, *et al*. A timetable for the radiologic features of fracture healing in young children. *Am J Roentgenol* 2012;198(5):1014–20.
75 Halliday KE, *et al*. Dating fractures in infants. *Clin Radiol* 2011;66(11):1049–54.
76 Cameron JM. The battered baby. *Br J Hosp Med* 1970;4:769–74.
77 Kogutt MS, Swischuk LE, Fagan CJ. Patterns of injury and significance of uncommon fractures in the battered child syndrome. *Am J Roentgenol Radium Ther Nucl Med* 1974;121(1):143–9.
78 Polson CJ, Gee D, Knight B. *Essentials of Forensic Medicine*, 4th edn. Oxford: Pergamon Press, 1985.
79 Melville JD, Lukefahr JL, Clarke EA. First rib fractures in abused infants: a report of three cases. *Clin Pediatr (Phila)* 2012;51(5):426–30.
80 Sillence DO, Senn A, Danks DM. Genetic heterogeneity in osteogenesis imperfecta. *J Med Genet* 1979;16(2):101–16.
81 Ben Amor IM, Glorieux FH, Rauch F. Genotype-phenotype correlations in autosomal dominant osteogenesis imperfecta. *J Osteoporos* 2011;2011:540178.
82 Forlino A, *et al*. New perspectives on osteogenesis imperfecta. *Nat Rev Endocrinol* 2011;7(9):540–57.
83 Cundy T. Recent advances in osteogenesis imperfecta. *Calcif Tissue Int* 2012;90(6):439–49.
84 Ojima K, *et al*. An autopsy case of osteogenesis imperfecta initially suspected as child abuse. *Forensic Sci Int* 1994;65(2):97–104.
85 Singh Kocher M, Dichtel L. Osteogenesis imperfecta misdiagnosed as child abuse. *J Pediatr Orthop B* 2011;20(6):440–3.
86 Morild I, Gjerdet NR, Giertsen JC. Bone strength in infants. *Forensic Sci Int* 1993;60(1–2):111–19.
87 Stanley P, Gwinn JL, Sutcliffe J. [The osseous abnormalities in Menke's syndrome]. *Ann Radiol (Paris)* 1976;19(1):167–72.
88 Osaka K, *et al*. Congenital hypocupraemia syndrome with and without steely hair: report of two Japanese infants. *Dev Med Child Neurol* 1977;19(1):62–8.
89 Lott IT, *et al*. Abnormal copper metabolism in Menke's steely-hair syndrome. *Pediatr Res* 1979;13(7):845–50.
90 Williams DM, Atkin CL. Tissue copper concentrations of patients with Menke's kinky hair disease. *Am J Dis Child* 1981;135(4):375–6.
91 Martinez-Granero MA, *et al*. [Menkes' disease: anatomo-clinical presentation of a case]. *Rev Neurol* 1997;25(139):465–70.
92 Guthkelch AN. Infantile subdural haematoma and its relationship to whiplash injuries. *Br Med J* 1971;2(5759):430–1.
93 Caffey J. On the theory and practice of shaking infants. Its potential residual effects of permanent brain damage and mental retardation. *Am J Dis Child* 1972;124(2):161–9.
94 Duhaime AC, *et al*. The shaken baby syndrome. A clinical, pathological, and biomechanical study. *J Neurosurg* 1987;66(3):409–15.
95 Gennarelli TA, Adams JH, Graham DI. Acceleration induced head injury in the monkey. I. The model, its mechanical and physiological correlates. *Acta Neuropathol Suppl* 1981;7:23–5.
96 Gennarelli TA, Thibault LE. Biomechanics of acute subdural hematoma. *J Trauma* 1982;22(8):680–6.
97 Geddes JF, Whitwell HL. Inflicted head injury in infants. *Forensic Sci Int* 2004;146(2–3):83–8.

98 Shannon P, *et al*. Axonal injury and the neuropathology of shaken baby syndrome. *Acta Neuropathol* 1998;95(6):625–31.

99 Geddes JF, *et al*. Neuropathology of inflicted head injury in children. I. Patterns of brain damage. *Brain* 2001;124(7):1290–8.

100 Geddes JF, *et al*. Neuropathology of inflicted head injury in children. II. Microscopic brain injury in infants. *Brain* 2001; 124(7):1299–306.

101 Geddes JF, *et al*. Dural haemorrhage in non-traumatic infant deaths: Does it explain the bleeding in 'shaken baby syndrome'? *Neuropathol Appl Neurobiol* 2003;29(1):14–22.

102 Howard MA, Bell BA, Uttley D. The pathophysiology of infant subdural haematomas. *Br J Neurosurg* 1993;7(4):355–65.

103 Aoki N, Masuzawa H. Infantile acute subdural hematoma. Clinical analysis of 26 cases. *J Neurosurg* 1984;61(2):273–80.

104 Rekate HL. Subdural hematomas in infants [letter]. *J Neurosurg* 1985;62(2):316–7.

105 Grivas CR, Komar DA. Kumho, Daubert, and the nature of scientific inquiry: implications for forensic anthropology. *J Forensic Sci* 2008;53(4):771–6.

106 Narang S. A Daubert-analysis of abusive head trauma/shaken baby syndrome. *Hous J Health L & Pol'y* 2011;11:505–633.

107 Findley KA, *et al*. Shaken baby syndrome, abusive head trauma, and actual innocence: getting it right. *Hous J Health L & Pol'y* 2012;12:209–312.

108 Moreno JA. What do pediatric healthcare experts really need to know about Daubert and the rules of evidence? *Pediatr Radiol* 2013;43(2):135–9.

109 Christian CW, Block R. Abusive head trauma in infants and children. *Pediatrics* 2009;123(5):1409–11.

110 The Crown Proscecution Service. Non-accidental head injury (NAHI, formerly referred to as shaken baby syndrome [SBS]) – prosecution approach. 2011.

111 Gilliland MG, Luckenbach MW, Chenier TC. Systemic and ocular findings in 169 prospectively studied child deaths: retinal hemorrhages usually mean child abuse. *Forensic Sci Int* 1994;68(2):117–32.

112 Bacon CJ, Sayer GC, Howe JW. Extensive retinal haemorrhages in infancy – an innocent cause. *Br Med J* 1978;1(6108):281.

113 Goetting MG, Sowa B. Retinal hemorrhage after cardiopulmonary resuscitation in children: an etiologic reevaluation. *Pediatrics* 1990;85(4):585–8.

114 Weedn VW, Mansour AM, Nichols MM. Retinal hemorrhage in an infant after cardiopulmonary resuscitation. *Am J Forensic Med Pathol* 1990;11(1):79–82.

115 Kramer K, Goldstein B. Retinal hemorrhages following cardiopulmonary resuscitation. *Clin Pediatr (Phila)* 1993;32(6): 366–8.

116 Gilliland MG, Luckenbach MW. Are retinal hemorrhages found after resuscitation attempts? A study of the eyes of 169 children. *Am J Forensic Med Pathol* 1993;14(3):187–92.

117 Odom A, *et al*. Prevalence of retinal hemorrhages in pediatric patients after in-hospital cardiopulmonary resuscitation: a prospective study. *Pediatrics* 1997;99(6):E3.

118 Pham H, *et al*. Retinal hemorrhage after cardiopulmonary resuscitation with chest compressions. *Am J Forensic Med Pathol* 2013;34(2):122–4.

119 Gilliland MG, *et al*. Guidelines for postmortem protocol for ocular investigation of sudden unexplained infant death and suspected physical child abuse. *Am J Forensic Med Pathol* 2007;28(4):323–9.

120 Teece S, Crawford I. Best evidence topic report. Torn frenulum and non-accidental injury in children. *Emerg Med J* 2005;22(2):125.

121 Maguire S, *et al*. Diagnosing abuse: a systematic review of torn frenum and other intra-oral injuries. *Arch Dis Child* 2007; 92(12):1113–7.

122 Welbury R. Torn labial frenum in isolation not pathognomonic of physical abuse. *Evid Based Dent* 2007;8(3):71.

123 Koe S, *et al*. Medical, social and societal issues in infants with abusive head trauma. *Ir Med J* 2010;103(4):102–5.

124 Darok M, Reischle S. Burn injuries caused by a hair-dryer– an unusual case of child abuse. *Forensic Sci Int* 2001;115 (1–2):143–6.

125 Kos L, Shwayder T. Cutaneous manifestations of child abuse. *Pediatr Dermatol* 2006;23(4):311–20.

126 Hicks RA, Stolfi A. Skeletal surveys in children with burns caused by child abuse. *Pediatr Emerg Care* 2007;23(5): 308–13.

127 Hayek SN, *et al*. The efficacy of hair and urine toxicology screening on the detection of child abuse by burning. *J Burn Care Res* 2009;30(4):587–92.

128 Maguire S. Which injuries may indicate child abuse? *Arch Dis Child Educ Pract Ed* 2010;95(6):170–7.

129 Andree C, Thomas P. [Bite marks in fatal child abuse: a case report]. *Kinderkrankenschwester* 2004;23(2):75–7.

130 Knight B. The autopsy in child abuse. In: Mason JK (ed). *Paediatric Forensic Medicine and Pathology*. London: Chapman and Hall Medical, 1989, p. 516.

This page intentionally left blank

CHAPTER 23

Deaths Associated with Surgical Procedures

- Introduction
- The autopsy on deaths associated with surgery and anaesthesia
- The mode and cause of death after surgery and anaesthesia
- Deaths associated with anaesthesia
- Malignant hyperthermia
- Autopsy procedure
- References

Introduction

In most jurisdictions, deaths that occur during or within a short time after surgical operation, invasive diagnostic procedure or an anaesthetic, become the subject of a medico-legal investigation. Similarly, any death thought to be caused or contributed to, by any of these procedures – irrespective of the interval – may be enquired into if the medical attendants or the relatives consider that a causal relationship exists. To be effective such investigations must include an autopsy, and the pathologist involved in these has a difficult and often professionally sensitive task (Figs 23.6, 23.11).

The pathologist should, wherever possible, be independent of the institution in which either the death occurred or which carried out the procedure. This is partly why the services of a forensic pathologist should be retained by the investigating authority, rather than a clinical or histopathologist belonging to the hospital, or associated institution. It is important that a separation should exist – and be seen to exist – between the loyalties of these two elements, not because there is any substantial likelihood of collusion, but because the public and private interest is best served by displaying the independence of the pathologist. In addition, there may be professional embarrassment when a close colleague of a surgeon or anaesthetist is placed in a potentially critical position within the same institution.

It is also sometimes useful to have the technical advice and expert opinion of an independent clinical consultant who is unconnected with the hospital, and who is not a colleague of the team involved in incident.

The autopsy on deaths associated with surgery and anaesthesia

A number of difficulties exist, that are peculiar to this type of death. The following matters need particular attention:

- The morphological findings, especially in so-called ‘anaesthetic deaths’, may be minimal or even absent so, more than in any other type of case, expert advice and full clinical information are essential.
- Technically the autopsy on a post-operative death may be difficult as a result of the surgical intervention and its sequelae, especially in abdominal and thoracic procedures. Exudate, sepsis, adhesions, haemorrhage, oedema and distortion of the normal anatomy may make the dissection difficult, especially if the details of the surgical procedure are not fully known. Post-mortem changes can further complicate the appearances: for example, recent suture lines in the intestine or stomach may appear to be leaking, but this may be caused by autolysis, and even handling the tissues at autopsy may tear devitalized and autolytic structures even further.
- Numerous surgical and anaesthetic devices may have been introduced into the patient during the procedure, such as airways, endotracheal tubes, indwelling needles, intravascular cannulae, self-retaining catheters, wound drains, chest tubes, monitoring electrodes and metal or plastic prostheses. It is essential that none of these be removed before autopsy, as their proper placement and patency may

need to be checked. Standing orders should be issued to hospitals within the jurisdiction of any coroner or medical examiner to the effect that no post-mortem interference with the body be made by members of the medical, nursing, technical or portering staff, as it has happened in the past that the single vital piece of evidence about some technical mishap has been discarded by some well-meaning person.

- Before any further disturbance of the body is made (for instance, by turning it over to look at the back) and certainly before a knife is picked up, the position of any endotracheal tube that may remain after anaesthesia must be checked. If the clinical information raises any doubt whatsoever about its malposition, wherever available, post-mortem imaging methods should be applied, or at least a pre-autopsy radiograph should be obtained, both anteroposterior and lateral.

Oesophageal intubation is not all that uncommon in anaesthetic mishaps and should be investigated carefully. The tube may be palpable through the skin if properly in the trachea – if there is doubt, a small primary incision in the midline of the neck with a further careful cut into the trachea can resolve the matter. Sometimes the intubation has been into the oesophagus, then been rectified after the damage has been done. Here the pathologist may find a ring of oedematous oesophageal mucosa still present at a level equal to that of the tube in the trachea. When nitrous oxide or other anaesthetic gas has previously been passed down a tube in the oesophagus there may be distension of the stomach and intestines. A sample of the contained gas may reveal the agent on analysis.

- The hospital laboratory should be requested to retain any ante-mortem blood or body-fluid samples sent to them so that they remain available for analytical checks, such as blood grouping in transfusion mishaps, or metabolic abnormalities or creatine phosphokinase activity in malignant hyperthermia or toxicological analysis to exlude or confirm errors in medication.
- Even more than usual, the fullest information is needed before beginning the autopsy. The patient's notes are essential, together with any other relevant information. Sometimes the nursing records may be more helpful than the medical notes, as they are frequently more detailed and recorded at shorter intervals.

Equally important is the attendance of clinicians at the autopsy. Indeed, in deaths associated with anaesthesia, this is usually more useful than the post-mortem dissection, which frequently reveals little or no morphological evidence. Sadly, attendance at autopsies has declined markedly in recent years, as have requests for clinical autopsies, but every effort should be made to secure the presence of someone who knows the circumstances of the case well and who can point out to the pathologist the procedures that were carried out. A discussion across the autopsy table is of paramount importance and it is of little use if a junior doctor is delegated to attend, especially if he confesses to knowing little or nothing about the patient.



Figure 23.1 Aorto-oesophageal fistula (arrow) due to ruptured anastomosis causing fatal haematemesis 18 days after replacement of the thoracic aorta with prosthesis.



Figure 23.2 Gut strangulated through the handle of forceps left in the abdomen during surgery and detected during an unrelated autopsy 6 weeks later for pneumoconiosis assessment.

Especially in anaesthetic-related deaths, this dialogue with a clinician – in this case, the anaesthetist – may provide virtually all the data upon which to base a cause of death. Discussion between pathologist, surgeon and anaesthetist may arrive at an amicable conclusion that will be the best consensus of opinion to offer the investigating authority in cases where a bare autopsy might reveal little or nothing upon which to base any interpretation of the fatal processes.

- During the autopsy, care must be taken to detect any surgical emphysema, pneumothorax or air embolism. When surgical operations have been conducted with the patient in the sitting position, as in posterior fossa neurosurgery or some thyroidectomies, the possibility of air aspiration into open veins or venous sinuses always exists.



Figure 23.3 Bronchial obstruction by the cover of a ballpoint pen, used by a midwife to hold down the tongue of a pregnant woman, who died days after childbirth from pneumonia.



Figure 23.4 A) Rectal mucosa showing two tissue defects (arrows) two days after rectal biopsy. One of the biopsies had perforated the rectal wall. B) Microscopical section of the perforated rectal wall with haemorrhage, fibrin, and strong inflammatory reaction.

Where infusion or transfusion mishaps may be a possibility, especially where gas pressure has been used to hasten the infusion rate, the possibility of air embolism must always be borne in mind.

The mode and cause of death after surgery and anaesthesia

The rather loose terms ‘operative deaths’ and ‘anaesthetic deaths’ are usually inaccurate descriptions. When used without due consideration, they may lead to medico-legal enquiries and even civil litigation, which is not justified by the actual circumstances.

Fatalities associated with surgical intervention or invasive diagnostic procedures can be separated into several categories:

- those directly caused by the disease or injury for which the operation or anaesthetic was being carried out
- those caused by a disease or abnormality other than that for which the procedure was being carried out
- those resulting from a mishap during, or a complication of, the surgical or diagnostic procedure
- those resulting from a mishap during, or a complication of, the anaesthetic being administered.

These groups must be considered in more detail.

Deaths directly caused by disease or injury for which surgery is performed

Many deaths during a surgical or diagnostic procedure or an anaesthetic are caused by the disease process or injury for which the procedure was being performed. The death may be virtually inevitable in some ‘heroic’ operations where urgent intervention is the only hope of saving life. Presumably there must have been some chance of success or even palliation, otherwise the intervention would not have been justified, but the decision not to operate may be difficult. When death occurs from the effects of such disease or injury, some medico-legal systems will certify the original condition as the cause of death and omit any reference to the intervention.

The American Society of Anesthesiologists have a classification system for deaths during surgical procedures, as follows:

- ASA 1: those with no serious disease
- ASA 2: those who may have a serious disease, but have no limitations on their activities
- ASA 3: those with serious disease and some limitation of their activities
- ASA 4: those with a serious disease that is a constant threat to their health and that limits their activities
- ASA 5: those with such serious disease that their death can be expected within 24 hours, with or without treatment.

The Society recommended that classes 1–3 require full investigation, as they were expected to survive; those in class 4 that were elective and not emergency procedures, with no expectation of death, are also included. The general principle is that unexpected deaths are investigated, though in the British coroner and Procurator Fiscal system there are no exceptions to such investigations, once reported by doctors to the appropriate legal authority.

Pathologists in some jurisdictions have problems in the nomenclature of certification following an autopsy. The strict test to be applied should be: 'Would death have occurred when it did, if the operation had not taken place?' Sometimes this is impossible to answer and the balance of probabilities may be evenly poised. If a patient has a leaking aortic aneurysm, which catastrophically ruptures while the surgeon is still making his skin incision, most would agree that the original disease process was the primary cause of death. Even here, however, it may be argued that the added disturbance of preparation and anaesthesia contributed something to a possible slight rise in blood pressure that further split the aneurysm wall.

Where a person dies of a pulmonary embolus 7 days after an elective gastrectomy for peptic ulcer, the connection between the operation and the death can hardly be denied, even though in up to one-fifth of fatal pulmonary embolisms, depending on the study, no predisposing factors have been found (see Chapter 13).

When both trauma and surgical operation have taken place, then it can be impossible to separate the relative contributions of each to a death. A common example would be death a few days after the pinning of a fractured neck or femur in an elderly person. A fatal bronchopneumonia, pulmonary embolism or acute cardiac failure might all be caused either by the original trauma, by the stress of operation or by the subsequent immobilization in bed.

Death due to a disease or disability other than that for which surgery is performed

Where death is due to a disease or disability other than that for which the operation was performed, a distinction has to be drawn between those conditions that were known before the operation and those which were unsuspected.

When some disease is known beforehand, it must be evaluated in deciding whether or not the operative procedure is justified. For example, a patient with a non-obstructing hernia who has chronic obstructive airways disease might be thought to be too poor a risk for an elective, prophylactic operation. If that same patient's hernia becomes strangulated and he develops potentially fatal intestinal obstruction, however, the risk:benefit ratio dramatically changes and the danger of a perioperative death may have to be accepted. Naturally, operative and anaesthetic techniques may have to be modified to take account of the known adverse conditions.

The accuracy and reliability of ASA grade 5 as an outcome predictor has been questioned. One dilemma that arises with high-risk patients that have been classed as ASA grade 5 is that, consequently, the decision to operate and the potentially lifesaving intervention is withheld. A number of other scoring systems for assessing a patient's risk of complications or death have been developed over the years. These include, among several others, The Physiological and Operative Severity Score



Figure 23.5 Thrombocytopenic purpura in a polymyalgia rheumatica –a patient who, because of poor response to corticosteroids, had been given immunosupressive therapy. This resulted in bone marrow injury, and finally causing death due to *Escherichia coli* septicaemia.



Figure 23.6 Large chronic pressure sore in praesacral region should raise the issue of its possible role in the chain of events leading to death, and the quality of nursing and medical care.



Figure 23.7 A 17-month-old infant had been hospitalized 6 months earlier because of a sudden cough and a suspicion of a foreign body in the airways. However, nothing was found in bronchoscopy. The cough continued and was considered to be asthmatic but medication had relieved the symptoms only temporarily. The infant was hospitalized anew because of sudden worsening of the symptoms but died a few days thereafter. At autopsy an ulceration of the tracheal wall as well as a foreign body, a piece of a plastic toy (insert), was found in the trachea having escaped detection in spite of two bronchoscopies.



Figure 23.8 Calcification of myocardium and vascular endothelium (arrow) due to post-operative rhabdomyolytic myoglobinuria and acute renal failure after reconstructive hand surgery and the interruption of blood circulation to the corresponding arm for the time of a nerve reconstruction. Von Kossa–staining. Original magnification ×100.



Figure 23.9 Immunohistochemical demonstration of myoglobin in the renal tubuli with polyclonal rabbit anti-human myoglobin (DakoCytomation Denmark A/S).

for enumeration of Mortality and morbidity (POSSUM), the Portsmouth predictor equation (p-POSSUM) for risk-adjusted surgical audit, and the Surgical Risk Score (SRS) as well as the Acute Physiology and Chronic Health Evaluation II (APACHE II).[1,2]

It is different when an occult disease process is not suspected by the clinicians. It may be that they had no diagnostic means of appreciating the risk – such as an unsuspected phaeochromocytoma – but a medico-legal problem can arise if they took no reasonable precautions in detecting common risk factors, such as hypertension, lung disease or ischaemic heart disease, which in retrospect could have been diagnosed.[3,4]

Death as a result of failure of surgical technique

Exceptionally, death is the result of a failure of surgical technique (Figs 23.1, 23.2, 23.4, 23.8, 23.9, 23.12). This may be inadvertent, from a true 'accident', sometimes caused by unusually difficult operative circumstances, to anatomical abnormalities or even failure of equipment. When it is the result of error or incompetence, then a legal action for negligence may ensue and the pathologist must be even more meticulous than usual in producing a detailed, objective and impartial report. In all these cases, the presence of the surgeon is essential, so that agreement can be reached on what actually was found at autopsy.

When a failure of equipment may be responsible, then expert examination and advice is essential. Anaesthetic machines, gas supply, compatibility of connections and all the sophisticated hardware of operating theatres must be subjected to the most rigorous inspection if a malfunction is suspected. This is no part of the pathologist's concern but, as he is responsible for the eventual decision about the cause of death, any conclusions about an equipment failure must be communicated to him.

Deaths due to anaesthetic administration

The foregoing categories account for most perioperative deaths and fatalities following surgery, even if delayed. True 'anaesthetic deaths' are comparatively rare, but have such potential medico-legal importance that they must be discussed in more detail.

Deaths associated with anaesthesia

Even more than is the case with surgeons, any autopsy on an anaesthetic-related death must be a co-operative process with the anaesthetist. Not only are the objective autopsy findings in true anaesthetic deaths meagre or absent, but the pathologist's training and experience of the complex techniques of modern anaesthesia is insufficient for him to appreciate, analyse and criticise constructively without the expert knowledge of the anaesthetist.

Most anaesthetic-related deaths are not caused by the anaesthetic agent itself, but due to other aspects of the procedure. Patients have anaesthetics because they have some significant – often very serious – disease or injury and, as has already been discussed, it is more likely that the fatality was the result of these or of some co-existent condition rather than the anaesthetic. There is a tendency on the part of relatives – and sometimes their lawyers – to assume that because someone died 'under' an anaesthetic, then this must be the major or even sole factor in the death because it was so closely related in time.

When factors other than anaesthesia can be excluded, certain features can be identified. A survey conducted at the beginning of the 1980s for the Association of Anaesthetists indicated that, although 1 in every 166 patients died within 6 days of a surgical operation, only 1 in 10,000 die solely as a consequence of anaesthesia. Anaesthesia contributed to (but not totally caused) the death of 1 in every 1700 patients, many of these deaths being potentially avoidable.[5]

The survey also showed that the causes have not changed significantly when compared to the previous 30 years, in spite of marked changes in anaesthetic technology and that anaesthesia may contribute to deaths that occur more than 24 hours after the administration. Many patients suffer from intercurrent disease unrelated to their surgical condition, but the implications for the anaesthetist are all too often ignored. The major causes of true anaesthetic fatalities include inexperienced and insufficiently supervised junior staff. Allowing periods of hypoxia to occur appears to be one of the common faults leading to a fatal outcome.

As far as the pathologist is concerned, the survey complained that the autopsy is of limited value in investigating the death. All too often irrelevant findings are offered, such as 'bronchitis'. Ischaemic heart disease was recorded in 39 per cent of the series. It was emphasized that the investigation of such deaths cannot be the sole province of the pathologist, but must rely heavily upon clinical data and co-operation with other doctors. Earlier investigations indicated that acute cardiovascular failure was the most common cause of unexpected death during anaesthesia.

Cardiac arrests due solely to anesthesia were studied in a large university hospital over a 15-year period. There were 27 cardiac arrests among 163,240 anaesthetics given, for a 15-year incidence of 1.7 per 10,000 anaesthetics. Fourteen of these patients (0.9 per 10,000) subsequently died. The paediatric age group had a threefold higher risk than adults, and the risk for emergency patients was six times that for elective patients. Failure to provide adequate ventilation caused almost half of the anaesthetic cardiac arrests, and one-third resulted from absolute overdose of an inhalation agent.[6]

Reid and Brace showed that the arrest is mainly neurogenic and that any irritation of the respiratory tract, such as laryngoscopy or intubation, may cause a lightly anaesthetized patient to have a cardiac arrest. Inexperienced anaesthetists may not keep the patient at a level of unconsciousness appropriate to the manipulations of the surgeon, as it has been shown that such procedures can also precipitate arrest during light anaesthesia.[7]

Arbous *et al.* assessed all consecutive patients (n = 811) who died within 24 h or remained unintentionally comatose 24 h after anaesthesia to determine a relationship with anaesthesia in a cohort comprising 869,483 patients. The incidence of 24-h perioperative death per 10,000 anaesthetics was 8.8, of perioperative coma was 0.5 and of anaesthesia-related death 1.4. Of the 119 anaesthesia-related deaths, 62 (52 per cent) were associated with cardiovascular management, 57 (48 per cent) with other anaesthetic management, 12 (10 per cent) with ventilatory management and 12 (10 per cent) with patient monitoring. Inadequate preparation of the patient contributed to 30 (25 per cent) of the anaesthesia-related deaths. During induction of anaesthesia, choice of anaesthetic technique (n = 18 [15 per cent]) and performance of the anaesthesiologist (n = 8 [7 per cent]) were most commonly associated with death. During maintenance, the most common factors were cardiovascular management (n = 43 [36 per cent]), ventilatory management (n = 12 [10 per cent]) and patient monitoring (n = 12 [10 per cent]). In both the recovery and the postoperative phases, patient monitoring was the most common factor (n = 12 [10 per cent]) for both.[8]

Braz *et al.* assessed the incidence and causes of perioperative and anesthesia-related mortality in a systematic review of the Brazilian and worldwide studies published between 1954 and 2007. They showed a similar decline in anaesthesia-related mortality rates, which amounted to fewer than 1 death per 10,000 anaesthetics in the past two decades. The main causes of anaesthesia-related mortality were problems with airway management and cardiocirculatory events related to anaesthesia and drug administration.[9]

In another systematic review and meta-analysis Bainbridge *et al.* identified all studies published up to February 2011, in any language, with a sample size of over 3000 that reported perioperative mortality across a mixed surgical population who had undergone general anaesthesia. They asessed whether the risk of perioperative and anaesthetic-related mortality has decreased over the past five decades. Altogether 87 studies met the inclusion criteria, within which there were more than 21.4 million anaesthetic administrations given to patients undergoing general anaesthesia for surgery. Mortality solely attributable to anaesthesia declined over time, from 357 per million (95 per cent, CI: 324–394) before the 1970s to 52 per million (42–64) in the 1970s–80s, and 34 per million (29–39) in the 1990s–2000s ($p < 0.00001$). Total perioperative mortality decreased over time, from 10,603 per million (95 per cent CI: 10,423–10,784) before the 1970s, to 4533 per million (4405–4664) in the 1970s–80s, and 1176 per million (1148–1205) in the 1990s–2000s ($p < 0.0001$). Baseline risk status of patients who presented for surgery as shown by the ASA score increased over the decades ($p < 0.0001$). They concluded that despite increasing patient baseline risk, perioperative mortality has declined significantly over the past 50 years.[10]

Hypoxia is one of the most feared adverse events during anaesthesia and in the post-operative period and also a potent precipitating factor in cardiac arrest. Deaths from respiratory failure also occur, and hypoxia is again a prime example – either from faults in the apparatus or more commonly to inexperience of the anaesthetist, especially in handling equipment with which he is not familiar. An overdose of the anaesthetic agent may depress the respiratory centres and begin a descending spiral of hypoxia. Excessive premedication and the use of muscle paralysing agents may also predispose towards respiratory failure unless appropriate measures are taken, such as assisted respiration. Although the means for continuous peri- and post-operative monitoring of oxygen saturation and pulsation levels have improved after the introduction of the pulse oximeter, a recent analysis of data from a total of 22,992 patients was not able to detect statistically significant differences in cardiovascular, respiratory, neurological or infectious complications between the oximetry group and controls.[11]

Airway obstruction is another danger – from blood, teeth, dentures, faults in the connecting tubing, laryngeal spasm, swabs and an abnormal posture of the neck (Figs 23.3, 23.7). Though regurgitation of gastric contents is a real danger, the use of cuffed endotracheal tubes has greatly reduced the hazard. From the pathologist's point of view, the finding of gastric contents in the airways must be backed up by some clinical evidence of its ante-mortem origins, as a quarter of bodies have some gastric contents in some part of the air passages at autopsy, mostly as a result of agonal or even post-mortem transfer that is a consequence of the dying process, not a cause (Chapter 14).

There have been occasional reports on physical faults in the anaesthetic equipment.[12–19] Mention has been made of faults in the connecting tubing, which may be internal delamination, not visible from outside. Flow-meter errors occur, but a more common one is the confusion of bottled or piped gas supplies, and the inadvertent use of the wrong substance or the connection of an empty cylinder.

Fires are not uncommon, the most frequent danger being the ignition of spirit-based skin antiseptics ignited by cautery. Any electrical apparatus is potentially dangerous, and defective cauteries, defibrillators and diathermy equipment have all caused death. In one fatal case oxygen that had been used during cardiopulmonary resuscitation had entered the peritoneal cavity through the perforation. The source of ignition was diathermy.[20]

Explosions from inflammable gases and vapours, such as cyclopropane and ether, have been catastrophic on occasions.[21]

Hazards of local and epidural anaesthesia

Complications of regional anaesthesia are usually relatively minor and often temporary in nature and the incidence of serious complications is very low. According to Fisher, they fall into three general categories – technique-related, equipment problems and poor patient management.[22]

Intravenous regional anaesthesia (IVRA; Bier block) is a technique applied for various types of hand and forearm surgery. IVRA has also been associated with serious complications and death.[23,24] Aitkenhead emphasized that cardiac arrest may result from intravascular injection of local anaesthetics, particularly bupivacaine, either inadvertently or in association with Bier block if the tourniquet is applied inadequately or released prematurely, or if the drug is injected rapidly into a large vein.[25]

Liposuction is one of the most frequently performed cosmetic operations in many countries. In the tumescent technique an extensive regional anaesthesia of skin and subcutaneous tissue is achieved by subcutaneous infiltration of a large volume of diluted lidocaine and epinephrine in a physiologic saline solution. Through this the targeted tissue becomes swollen and firm, or tumescent, and permits a large-volume liposuction to be done entirely by local anaesthesia.[26]

In a survey in Germany, Lehnhardt *et al.* reported on severe complications in 72 subjects, including 23 deaths following cosmetic liposuction in a 5-year period from 1998 to 2002. The most frequent complications were bacterial infections such as necrotizing fasciitis, gas gangrene and different forms of sepsis.[27]

Martinez *et al.* reported a further complication of liposuction. A 38-year-old female attended an outpatient clinic for liposuction of the abdomen and both hips and thighs. Around 30 min after anaesthesia administration, the patient suffered an episode of tonic–clonic convulsions, became asystolic and died in spite of cardiopulmonary resuscitation. A complete autopsy did not reveal anything specific. Anaphylactic shock was considered a possible but unlikely explanation for the fatality. Toxicological analyses confirmed the presence of lidocaine and mepivacaine in heart blood, at concentrations of 4.9 and 16.2 mg/l, respectively. Based on the autopsy findings, case history and toxicology results, the forensic pathologists ruled that the cause of death was an overdose of local anaesthetic agents. The Court of Law ruled the death as an involuntary homicide due to gross negligence.[28]

In a multicentre study in France, Auroy *et al.* prospectively evaluated the incidence and characteristics of serious complications related to regional anaesthesia during a 5-month study period. There were altogether 103,730 regional anaesthetics, consisting of 40,640 spinal anaesthetics, 30,413 epidural anaesthetics, 21,278 peripheral nerve blocks, and 11,229 intravenous regional anaesthetics. Severe complications were reported in 98 subjects, with follow-up information being obtained for 97. In 89 cases, complications were attributed fully or partially to regional anaesthesia. There were 32 cardiac arrests, seven of which were fatal. Of these, 26 occurred during spinal anaesthesia, with six being fatal. A further three cardiac arrests occurred during epidural anaesthesia, and three during peripheral blocks. The higher incidence of cardiac arrest during spinal anaesthesia (6.4 ± 1.2 per 10,000 patients) compared with all other regional anaesthesia (1.0 ± 0.4 per 10,000 patients) was statistically significant ($P < 0.05$).[29]

Epidural and spinal anaesthesia has returned to favour, especially in obstetrics, after a period in which spinal injection of anaesthetic agents fell into disrepute because of a number of lawsuits brought because of spinal cord damage as a result of contaminants or excessive dosage.

In obstetric regional analgesia, inadvertent intravascular, intrathecal or subdural injection are potentially life-threatening. The upwards diffusion of the active agents may cause paralysis, and the effect upon the vasomotor system may lead to a precipitous fall in blood pressure. Total spinal anaesthesia from upward diffusion blocks all sympathetic efferent impulses so, if the concentration of the anaesthetic agent in the upper thoracic and cervical spinal fluid level is high enough, efferent transmission to all motor fibres of the respiratory muscles will be blocked.

In a prospective study on complications of obstetric epidural analgesia and anaesthesia, data was collected from maternity units in the South West Thames Region from 1987 to 2003. Altogether 145,550 epidurals (26.3 per cent) were administered to 553,905 mothers. The incidence of intravascular injection was 1 in 5000 epidurals (0.02 per cent [95 per cent CI: 0.014–0.029 per cent]), of intrathecal injection 1 in 2900 epidurals (0.035 per cent [95 per cent CI: 0.027–0.046]), of subdural injection 1 in 4200 epidurals (0.024 per cent [95 per cent CI: 0.017–0.033]) and of high or total spinal block 1 in 16200 epidurals (0.006 per cent [95 per cent CI: 0.003–0.012]). The incidence of serious complications did not change during the course of the study, nor was there any difference in the incidence of serious complications in obstetric units of different sizes or in obstetric units with different rates of epidural analgesia.[30] In the rare autopsies on deaths following epidural analgesia, a sample of cerebrospinal fluid should be taken for analysis to ascertain the concentration of anaesthetic substance. An attempt should be made to find the puncture in the dura, which is easier said than done. If an epidural catheter is still in place for continuous administration of the active agent, dye or Indian ink can be injected to see if it enters the subdural space.

Malignant hyperthermia

Malignant hyperthermia (MH) is a rare, pharmacogenetic disorder of the skeletal muscle, which is triggered by halogenated volatile anaesthetics, depolarizing muscle relaxants and in rare cases by strenuous exercise and/or heat exposure.[31–33] Susceptibility to MH is inherited as an autosomally dominant trait with variable expression and incomplete penetrance and is based on an altered regulation of calcium within the skeletal muscle fibre. The disorder was first described by an Australian anaesthesiologist who was asked to evaluate a patient with a family history of 10 deaths during anaesthesia.[34] Between 50 and 70 per cent of cases of MH are associated with mutations of the ryanodine receptor (RYR1) but also other calcium channel mutations are causally involved. When triggered, an abnormally high release of calcium from the sarcoplasmic reticulum is initiated resulting in a hypermetabolic state, leading to typical clinical signs, such as tachycardia, muscle rigidity, hypercapnia as well as hyperthermia.[31]

The incidence of MH reactions ranges from 1:5,000 to 1:50,000–100,000 anaesthesias; however, the incidence of MH in the USA has increased in recent years.[35,36] The prevalence of genetic polymorphisms associated with this disorder is thought to be as high as 1 per 3000. After the introduction of dantrolene sodium, a specific antagonist of the pathophysiological changes of MH and progress in understanding the clinical manifestation and pathophysiology of the syndrome, the mortality from MH has dropped from over 80 per cent 30 years ago to less than 7 per cent.[31,35,37–39]

When MH is diagnosed, the family members should be investigated, preferably by muscle biopsy. The *in vitro* muscle contracture test (IVCT) is the standard test, to assess the risk of an individual's risk of susceptibility to MH and their risk of suffering a similar crisis if subjected to anaesthesia.[40] Genetic testing has also been introduced.[41–43]

There are virtually no autopsy features of any significance and the diagnosis is made on clinical grounds. The features of MH include a sudden rise in temperature, sometimes reaching 43°C, with stiffening of the skeletal muscles, rapid heart rate and respiratory distress.

Halothane anaesthesia has acquired the reputation for causing liver injury known as halothane hepatitis and, rarely, a fulminant hepatic failure.[44–47] Its incidence varies between 1:35000 and 1:600000 and if halothane anaesthesia is repeated within 1 month, 1:6000–1:22000. It is a typical example of immune-mediated adverse drug reactions.

Autopsy procedure

Usually the function of the autopsy is to discover or exclude natural disease and mechanical blockages in peri-operative deaths; however, it is also important to exclude the possibility of any drug involvement (Fig. 23.5). Therefore, the post-mortem analysis of inhalation anaesthetics and other drugs is justified in the investigation of deaths during anaesthesia.[48,49] The analytical methods have been improved and inhalation anaesthetics have been determined in various tissues including blood, which is most useful for sampling. Glass tubes should be used, preferably with a cap lined with metal foil. The tube should be as full as possible and should only be opened when required for analysis,



Figure 23.10 Birefringent material in the alveoli due to contrast medium aspiration (barium sulphate).



Figure 23.11 A teenage girl died from intestinal obstruction during emergency admission to hospital. It was alleged that the family doctor had negligently failed to visit her after several requests by the parents.

and then only when cold (4°C). An anticoagulant (sodium ethylenediamine tetra-acetate [EDTA] or lithium heparin) should be used and 1 per cent (w/v) sodium fluoride should be added to minimize enzymic activities. In addition to standard toxicological specimens (femoral blood, urine, stomach contents, vitreous humor), tissues (about 10 g each of brain, lung, liver, kidney and subcutaneous fat) should also be obtained. Tissues should be stored before analysis in the same way as blood (between −5 and +4°C). No preservative should be added.[50]



Figure 23.12 A rare complication of suction-cup delivery with massive diffuse subcutaneous haematoma, and fracture of the left parietal bone.

Even when it seems obvious that a surgical error has taken place, one should be careful and not jump to conclusions nor let this distract from a thorough investigation. A full range of specimens for histological examination should be taken to exclude occult conditions such as a lymphoma or myocarditis, as well as to investigate the severity of the disease for which the surgical procedure was being performed (Fig. 23.10). This includes also the investigation of any surgical specimens taken during the operation and sent to the histopathologist. Histological examination of the brain (fixed before cutting wherever possible) must be carried out. Though most mishaps will have occurred too quickly for much hope of any stigmata of cerebral hypoxia to be seen, changes can classically occur in Sommer's area of the hippocampal gyrus.

References

1 Jones HJ, de Cossart L. Risk scoring in surgical patients. *Br J Surg* 1999;86(2):149–57.

2 Brooks MJ, Sutton R, Sarin S. Comparison of Surgical Risk Score, POSSUM and p-POSSUM in higher-risk surgical patients. *Br J Surg* 2005;92(10):1288–92.

3 Preuss J, *et al.* Non-diagnosed pheochromocytoma as a cause of sudden death in a 49-year-old man: a case report with medico-legal implications. *Forensic Sci Int* 2006;156(2–3):223–8.

4 Howell SJ, *et al.* Risk factors for cardiovascular death within 30 days after anaesthesia and urgent or emergency surgery: a nested case-control study. *Br J Anaesth* 1999;82(5):679–84.

5 Lunn J, Mushin W. *Mortality Associated with Anaesthesia.* London: Nuffield Provincial Hospital Trust, 1982.

6 Keenan RL, Boyan CP. Cardiac arrest due to anesthesia. A study of incidence and causes. *JAMA* 1985;253(16):2373–7.

7 Reid L, Brace D. Irritation of the respiratory tract and its reflex effect upon the heart. *Surg Gyn Obst* 1940;70:157–62.

8 Arbous MS, *et al.* Mortality associated with anaesthesia: a qualitative analysis to identify risk factors. *Anaesthesia* 2001;56(12):1141–53.

9 Braz LG, *et al.* Mortality in anesthesia: a systematic review. *Clinics (Sao Paulo)* 2009;64(10):999–1006.

10 Bainbridge D, *et al*. Perioperative and anaesthetic-related mortality in developed and developing countries: a systematic review and meta-analysis. *Lancet* 2012;380(9847):1075–81.

11 Pedersen T, Moller AM, Hovhannisyan K. Pulse oximetry for perioperative monitoring. *Cochrane Database Syst Rev* 2009(4):CD002013.

12 Lohmann G. Fault with an Ohmeda Excel 410 machine. *Anaesthesia* 1991;46(8):695.

13 Lum ME, Ngan Kee WD, Robinson BJ. Fault in a Selectatec manifold resulting in awareness. *Anaesth Intensive Care* 1992;20(4):501–3.

14 Gregg AS, Jones RS, Snowdon SL. Flow reversal through a Mark III halothane vaporizer. *Br J Anaesth* 1993;71(2):303–4.

15 Kidd AG, Hall I. Fault with an Ohmeda Excel 210 anaesthetic machine. *Anaesthesia* 1994;49(1):83.

16 Hay H. Delivery of an hypoxic gas mixture due to a defective rubber seal of a flowmeter control tube. *Eur J Anaesthesiol* 2000;17(7):456–8.

17 Armstrong P, Flick R. An intermittent fault involving an Ulco anaesthetic machine. *Anaesth Intensive Care* 2001;29(2):204–5.

18 Cheng CJC, Bailey AR. Flow reversal through the anaesthetic machine back bar: an unusual assembly fault. *Anaesthesia* 2002;57(1):86–8.

19 Prophet N, Davey A. Fault in Blease Frontline 860 anaesthetic machine. *Anaesthesia* 2009;64(3):335; discussion 335–6.

20 Dhebri AR, Afify SE. Free gas in the peritoneal cavity: the final hazard of diathermy. *Postgrad Med J* 2002;78(922):496–7.

21 Kalkman CJ, Romijn C, van Rheineck Leyssius AT. [Fire and explosion hazard during oxygen use in operating rooms]. *Ned Tijdschr Geneeskd* 2008;152(23):1313–6.

22 Fischer B. Complications of regional anaesthesia. *Anaesth Intensive Care Med* 2007;8(4):151–4.

23 Reynolds F. Bupivacaine and intravenous regional anaesthesia. *Anaesthesia* 1984;39(2):105–7.

24 Guay J. Adverse events associated with intravenous regional anesthesia (Bier block): a systematic review of complications. *J Clin Anesth* 2009;21(8):585–94.

25 Aitkenhead AR. 2 Injury attributed to anaesthesia. *Baillière's Clin Anaesthesiol* 1996;10(2):251–76.

26 Kucera IJ, *et al*. Liposuction: contemporary issues for the anesthesiologist. *J Clin Anesth* 2006;18(5):379–87.

27 Lehnhardt M, *et al*. Major and lethal complications of liposuction: a review of 72 cases in Germany between 1998 and 2002. *Plast Reconstr Surg* 2008;121(6):396e–403e.

28 Martinez MA, *et al*. Reporting a fatality during tumescent liposuction. *Forensic Sci Int* 2008;178(1):e11–16.

29 Auroy Y, *et al*. Serious complications related to regional anesthesia: results of a prospective survey in France. *Anesthesiology* 1997;87(3):479–86.

30 Jenkins JG. Some immediate serious complications of obstetric epidural analgesia and anaesthesia: a prospective study of 145,550 epidurals. *Int J Obstet Anesth* 2005;14(1):37–42.

31 MacLennan DH, Phillips MS. Malignant hyperthermia. *Science* 1992;25**6**(5058):789–94.

32 Wappler F. Malignant hyperthermia. *Eur J Anaesthesiol* 2001; 18(10):632–52.

33 Carsana A. Exercise-induced rhabdomyolysis and stress-induced malignant hyperthermia events, association with malignant hyperthermia susceptibility, and RYR1 gene sequence variations. *Scientific WorldJournal* 2013;2013:531465.

34 Denborough MA, *et al*. Anaesthetic deaths in a family. *Br J Anaesth* 1962;34(6):395–6.

35 Rosenberg H, *et al*. Malignant hyperthermia. *Orphanet J Rare Dis* 2007;2:21.

36 Rosero EB, *et al*. Trends and outcomes of malignant hyperthermia in the United States, 2000 to 2005. *Anesthesiology* 2009;110(1):89–94.

37 Denborough M. Malignant hyperthermia. *Lancet* 1998; 352(9134):1131–6.

38 Wappler F. Anesthesia for patients with a history of malignant hyperthermia. *Curr Opin Anaesthesiol* 2010;23(3):417–22.

39 Kim DC. Malignant hyperthermia. *Korean J Anesthesiol* 2012;63(5):391–401.

40 Ording H, *et al*. *In vitro* contracture test for diagnosis of malignant hyperthermia following the protocol of the European MH Group: results of testing patients surviving fulminant MH and unrelated low-risk subjects. The European Malignant Hyperthermia Group. *Acta Anaesthesiol Scand* 1997;41(8): 955–66.

41 Urwyler A, *et al*. Guidelines for molecular genetic detection of susceptibility to malignant hyperthermia. *Br J Anaesth* 2001;86(2):283–7.

42 Girard T, *et al*. Molecular genetic testing for malignant hyperthermia susceptibility. *Anesthesiology* 2004;100(5): 1076–80.

43 Rosenberg H, Rueffert H. Clinical utility gene card for: malignant hyperthermia. *Eur J Hum Genet* 2011;**19**(6).

44 Ger R. Halothane re-examined. *Br Med J* 1964;2(5405):325–6.

45 Mushin WW, *et al*. Halothane and liver dysfunction: a retrospective study. *Br Med J* 1964;2(5405):329–41.

46 Mushin WW, Rosen M. Halothane hepatitis. *Br Med J* 1971; 3(5771):431–2.

47 Mushin WW, Rosen M, Jones EV. Post-halothane jaundice in relation to previous administration of halothane. *Br Med J* 1971;3(5765):18–22.

48 Pihlainen K, Ojanpera I. Analytical toxicology of fluorinated inhalation anaesthetics. *Forensic Sci Int* 1998;97(2–3):117–33.

49 Ojanpera I, Hyppola R, Vuori E. Identification of volatile organic compounds in blood by purge and trap PLOT-capillary gas chromatography coupled with Fourier transform infrared spectroscopy. *Forensic Sci Int* 1996;80(3):201–9.

50 Flanagan RJ, Fisher DS. Volatile substances and inhalants. In: Siegel JA, Saukko PJ (eds). *Encyclopedia of Forensic Sciences*. Waltham: Academic Press, 2013, pp. 230–42.

This page intentionally left blank

CHAPTER 24

Dysbaric Fatalities and Barotrauma

- Introduction
- Physical damage
- The autopsy in dysbarism and barotrauma deaths
- References

Introduction

Damage to the body from changes in external pressure usually lies in the province of specialized occupational or armed services medicine, rather than that of the forensic pathologist. The major exception is recreational and sporting diving, using SCUBA (self-contained underwater breathing apparatus) equipment developed from the open-circuit breathing apparatus, the 'aqua-lung', designed by Jacques-Yves Cousteau and Émile Gagnan in the French Navy in 1943.[1] When death occurs in such circumstances, however, though criminality is rarely a factor, there is usually some form of official enquiry, be it quasi-judicial or an internal investigation. Civil suits for compensation may arise and in these circumstances a forensic pathologist may well become involved as the expert witness providing the autopsy evidence.

Diving poses various risks that can be due to:[2]

- impact of environmental conditions, such as increase in hydrostatic pressure on structure and function of the body, affecting breathing by increasing respiratory work through increased gas density, altered respiratory mechanics as well as displacement of blood from periphery into the chest reducing lung volume, added dead space because of the breathing apparatus. All these may contribute to impairment of ventilation and to carbon dioxide retention; and to further direct damage to the tissue due to rapid changes of pressure, particularly expansion during ascent, barotrauma or decompression illness
- individual characteristics of the diver, for example, poor buoyancy control, poor dive planning and proneness to panic in stressful situations
- concomitant morbidity such as coronary heart disease, diabetes or epilepsy
- equipment malfunction or poisoning by inappropriate gas mixtures or contaminant gases
- the potential hazards of the diving environment, such as cold water, strong currents or physical trauma.

As early as in 1670, Robert Boyle (1627–1691) the pre-eminent 17th century scientist, performed experiments with various animal species demonstrating the effects that could be produced by sudden lowering of atmospheric pressure.[3,4] Calder refers to an incident in Stockholm in 1631, which may be one of the earliest observations on dysbaric illness (DI). During an attempt to raise the battleship 'Vasa' that had capsized and sunk on her maiden voyage in 1628, a diver was seen 'spitting blood' when surfacing.[5] Another early observation of the symptoms of DI was reported in 1839 by a French mining engineer named Triger, who initiated the use in construction work of pressurized metal tubes or boxes, so called 'caissons', in coal mining to access a rich vein of coal through a layer of quicksand.[6] In the 1800s the caissons were widely used for under-water construction of riverine piers and abutments anchoring bridges.[7] Various medical problems, including two fatalities, were reported from Douchy mines in France in 1854.[8] In 1878, Paul Bert identified the cause of DI demonstrating that high external pressure forces atmospheric nitrogen to dissolve in the blood and tissues.[9] Rapid decompression leads to bubble formation that can have various harmful effects. Bubbles can cause venous stasis, obstruct vessels and cause ischaemic injury of the tissues and injure endothelium.[10] The origin of gas bubbles is ambiguous but animal experiments suggest that they may be formed in perivascular tissues and are admitted into vessels through endothelial gaps.[11] Intravascular bubbles can also be formed as a result of pulmonary barotrauma when expanding gas stretches and ruptures alveolar capillaries and enters the arterial circulation.[12]

Injurious pressure effects are virtually always the result of a decrease in atmospheric pressure from a previous level. This can occur either from a decrease of high pressure to normal atmospheric pressure (hyperbaric exposure) or a decrease from normal to a low pressure (hypobaric exposure). An example of the first is the decompression of a diver ascending to the surface, while the second is seen in depressurization of an aircraft at high altitude or floating and manoeuvring in space outside the spacecraft. The first is by far the most common as a source of injury and death, mainly because of the great increase in recent years of diving activity associated with the offshore oil industry, which in Britain forms one of the most dangerous type of commercial employment.

Dysbarism or dysbaric illness or decompression illness (DI) are used as alternative terms that cover a broad range of complex pathophysiological conditions associated with decompression, while barotrauma describes the mechanical damage from gas released into the tissues.[10]

In diving, each 10 m depth of water increases the pressure by one atmosphere – 101 kiloPascals (kPa), equivalent to the pressure of a column of 760 mmHg – so that, in a non-rigid diving suit, the air supply has to be provided at the appropriate pressure relative to the working depth. This depth depends on the equipment used and is limited by legal constraints – for example, in Britain, dives of more than 50 m (164 ft) are not permitted using a nitrogen/oxygen mixture, a gas such as helium being mandatory.[13] Similarly, surface decompression is only allowed at less than this depth of 50 m (164 ft).

When air is supplied at increased pressure, the contained nitrogen (and, to a much lesser extent, carbon dioxide) will progressively dissolve in the plasma and tissue fluids, the amount being governed by Henry's law: *the solubility of a gas in a liquid is proportional to its partial pressure*, presented in 1803 by the English physician and chemist William Henry (1775–1836). This itself can produce nitrogen narcosis, a state resembling drunkenness in which orientation, judgement and rational behaviour may be diminished. This can occur at depths greater than 30 m. A more physical danger, however, is when a diver who has been at high pressure for long enough to have appreciable nitrogen dissolved in his tissues is returned too quickly to normal atmospheric pressure. The dissolved gas will then come out of solution, almost as champagne effervesces when the cork is released. Gas bubbles appear in the circulation, tissues and joint cavities, and can cause 'decompression sickness' with a wide range of clinical signs and symptoms.

Bubbles in the circulation can cause gas emboli that block small vessels and give rise to infarction, especially in the central nervous system, such as the spinal cord. In addition, such bubbles can interfere with the coagulation system, causing platelet aggregation and disseminated intravascular coagulation. Subcutaneous emphysema can appear as a result of gas under the skin.

Physical damage

When sudden, or too rapid, decompression occurs, there may also be physical damage from volume changes. The gas in body cavities expands markedly as the diver rises and, unless these can be progressively vented to the exterior, pressure effects from the contained gas will occur. Such effects may develop in the paranasal sinuses, if blocked, and even in the teeth, if small vacuoles of gas are trapped in the pulp cavities. The middle ear may also be involved and ruptures of the drum can occur. None of these lesions in themselves is likely to be fatal, however, unless the pain and disability interfere with performance – then drowning is the usual cause of death.

A more serious volume effect is in the thorax because, if the air in the lungs is not vented as the diver rises, the alveolar walls may be ruptured by the gas pressure. This leads to interstitial emphysema – air bursting through the respiratory membranes into the interalveolar, interlobular and interlobar septa. Bullae may appear on the pleural surface and, if these rupture, a pneumothorax is formed. Air may reach the mediastinum and track up the tissues to appear in the neck. Apart from a disabling pneumothorax, air can break into the lung capillaries and veins with the danger of air embolism to the left side of the heart, as it cannot move back down the pulmonary arteries. The filling of the left atrium and ventricle interrupts cardiac pump function and, if the volume is sufficient, can be fatal in itself.

Even though this does not occur in most cases of air entry, smaller volumes will be swept into the systemic arterial circulation and impact in the arterioles and capillaries of target organs, especially the myocardium, spinal cord and brain, causing microinfarcts, haemorrhagic necrosis and loss of function of vital tissues. This pulmonary barotrauma (PBT) is not necessarily confined to deep diving, and, in fact, the risk of PBT is highest in shallow water, because the ambient pressure doubles between 0 and 10 metres of sea water (msw) and the relative change in volume is maximal at that depth range.[1]

Many incidents occur to sporting divers, rather than to professionals, in relatively shallow water. The SCUBA diver is now a ubiquitous user of the seas, especially in the warmer, clearer waters of many parts of the world. The number of recreational divers worldwide is not known but is probably in the millions.[12] It is estimated that there are about 100,000 recreational divers in the UK who complete more than three million dives each year.[2] In 2009, according to the British Sub-Aqua Club (BSAC) annual incidence report, there were altogether 453 incidents serious enough to be reported, of which 381 took place in the UK including 14 fatalities.[14]

A project called 'Stickybeak' was commenced in 1972 in Australia and New Zealand to analyse diving deaths.[15] Altogether 207 recreational scuba diving deaths were recorded between 1972 and 1996.[16,17]

In 2006, in a first attempt to collect worldwide data on scuba diving fatalities, Divers Alert Network (DAN), in the USA, received notification of altogether 138 deaths. There were 75 deaths of recreational divers from the USA and Canada. DAN Europe reported the second highest total with 35 deaths, DAN Asia-Pacific reported 25 fatalities, DAN Latin America reported five fatalities, DAN Japan one fatality and DAN Southern Africa did not report any fatalities in 2006. Of the 75 USA or Canadian recreational divers 64 were male and 11 female. Fifty-nine (79 per cent) of these incidents occurred in the USA or Canada and 16 (21 per cent) occurred abroad. The highest rate of fatalities was seen in Florida (29 per cent) and California (19 per cent).[18]

The autopsy in dysbarism and barotrauma deaths

Many of the vast quantity of reports on this subject deal with the clinical effects. Most deaths associated with diving are caused by drowning, though dysbaric disablement may have caused or contributed to the drowning. The autopsy must be directed to investigating the drowning aspect (Chapter 16), and to excluding or confirming any evidence of dysbarism or barotrauma.

The autopsy should not begin until some expert advisers are present, including someone with detailed knowledge of the equipment. If the victim has died in hospital or in a decompression chamber, then obviously much original information will be lost, as no *in situ* examination of the suit and breathing apparatus is possible. In any event, as few forensic pathologists are likely to be expert in this specialized field, every effort should be made to have the attendance of a naval or commercial person who is an authority on the equipment being used at the time of the death. The importance of this was emphasized by the results of the analysis of the first 1000 incidents reported to the Australian Diving Incidence Monitoring Study (DIMS), commenced in 1989, showing that there were 426 equipment-associated incidents and 128 (30 per cent) of these had resulted in harm. It also showed that human error contributed to 87 per cent of the incidents reported.[19] The earlier mentioned 207 scuba diving fatalities of the Stickybeak Project contained 112 incidents involving equipment with 43 (37 per cent) of these being associated with the death of the diver.[15–17]

It has been recommended that the autopsy itself should be conducted in a decompression chamber in order to prevent the post-mortem dissipation of gas that must take place if the body is brought into atmospheric pressure. This is hardly likely to be a practical procedure except where the autopsy takes place under the aegis of armed-service or specialized commercial facilities, who have expert medical staff who are well versed in such procedures.

However, it must be recognized that the very act of decompression is likely to allow bubbles to form within the body, even if they were not there when death took place. This is an insurmountable difficulty for the pathologist unless, as just mentioned, the autopsy itself can be performed under pressure. Thus the finding of gas in the vessels and tissues has to be interpreted in the knowledge that they may be an artefact; part of the differentiation is quantitative, as a mass of froth distending the heart is unlikely to have accumulated post-mortem merely from the static fluid and tissues in the immediate vicinity, and is therefore more likely to have been brought there to form an 'airlock' by a vital circulation.

The autopsy should not begin – nor the body be undressed – until all necessary examination is made of the diving apparatus by an expert, including photography of the diving equipment. Full photography at every stage, and radiology/imaging of the head, neck, chest and abdomen as well as major joints is essential before any dissection is attempted. For chemical analysis of the lung contents, for example to determine the oxygen:nitrogen ratio, the toxicology laboratory in question ought to be consulted prior to the autopsy to guarantee the optimal sampling method.

Externally, attention should be paid to the skin colour. Hypothermia is sometimes an associated hazard of diving. Unfortunately, many bodies recovered from water have a bright pink colour that may be post-mortem in origin, much as refrigerated bodies often have a pink hue. In rare cases, a characteristic rash (cutis marmorata) on the thighs and torso can be observed as a dermal manifestation of decompression sickness.[12,20] Red linear marks may be seen in those who have suffered 'squeezes' inside a neoprene dry-suit when the external pressure has become excessive. Crepitance of the skin – usually of the head, neck and thorax – is an indication of barotrauma. The eardrums should be examined with an otoscope to detect any recent ruptures.

The brain should be removed before opening the body cavities, using a special technique to detect air in the cerebral arteries. Artery forceps should be placed on the middle cerebral, basilar and vertebral arteries before they are cut through; the brain should then be placed under water and the clamps removed to observe whether air bubbles escape from the cut ends of the vessels. The detection of air bubbles in the cerebral veins is of no significance, always being an artefact, as it is impossible to remove the calvarium without aspirating some air into the pial vessels. In any case, there is no way in which air in the arterial side of the cerebral circulation can penetrate the brain capillaries in sufficient volume to be visible in the cortical veins.

In the central nervous system, petechial haemorrhages may be seen in any part of the system, including the spinal cord. If the victim survives for a day or more, early infarcts may be seen. Histologically, ring-shaped haemorrhages around vessels may be seen in the white matter. In long-term survivors, living for some weeks, softening of the lateral and dorsal columns of the thoracic spinal cord may be seen if air emboli have impacted there.

Subcutaneous, mediastinal, retroperitoneal and subpleural emphysema must be sought. In the lungs, rupture of alveolar membranes allows air to track through the interstices from where it either enters the circulation or reaches the periphery of the lung to form subpleural bullae, or both. It can cross to the other lung via the hilum; in addition, local bronchial stenosis may trap air in a single lobe, causing a local distension.

The chest should be examined for pneumothorax, first by radiology/computed tomography (CT). If that is not possible, one can dissect an intercostal space down to the parietal pleura and visualize the lung directly underneath (if there is no pneumothorax) and observe its collapse when incising the pleura with the tip of a scalpel. However, the presence of pleural adhesions must be considered. Alternatively, the intercostal space can be punctured under a pool of water held in the lateral skin flap. Similarly, the heart should be examined radiologically for the presence of bubbles. If the air has emerged from the general tissue mass, it will have been conducted centrally by the venous drainage and so more air will be found in the right chambers than in the left side of the heart. If lung damage has occurred, then entry into the pulmonary venous system will bring it to the left side. It is hardly worth attempting to open the heart under a pericardium full of water, as froth in the chambers will be readily apparent if in sufficient volume to have caused death. Some authorities, however, advocate placing clamps on all the major thoracic vessels and the trachea before removing the thoracic pluck of organs. This is then placed under water and the clamps released to see if and from where air bubbles emerge.

Histologically, there are no particularly specific changes in spite of some claims (Fig. 24.1). Lipoid-containing tissues, such as adipose tissue and adrenal cortex, may show microbubbles with a foamy appearance. There may be fatty change in the liver, possibly from air emboli. In lungs in which barotrauma has taken place, oedema, patchy haemorrhage, torn alveoli and focal emphysema confirm the macroscopic findings. The myocardium may show small foci of necrosis.

Fat embolism may occur, both in post-descent shock and in decompression in both water and high altitude. Not only fat, but cellular bone marrow may be found in target organs such as lung, myocardium, brain and kidney. There is controversy over the origin of fat emboli in decompression states, some claiming that it is caused by air-bubble disruption of fat depot tissues, while others favour a more complex genesis involving a redistribution of blood lipids, inter-relating with fibrin production and disseminated intravascular coagulation.



Figure 24.1 A) Formalin-fixed brain of a scuba diving accident victim showing numerous intracerebral vacuoles. B) Haematoxylin & eosin stained section with vacuoles. C) Immunohistochemically stained CD31-positive endothelial cell lining the vacuolar wall and demonstrating that the vacuole is intravascular. However, it must be emphasized that these vacuoles can be generated when a corpse is released to the surface from great depths and thus does not establish proof of a vital phenomenon and the cause of death.[21]

References

1 Tetzlaff K, Thorsen E. Breathing at Depth: Physiologic and Clinical Aspects of Diving while Breathing Compressed Gas. *Clinics Chest Med* 2005;26(3):355–80.

2 British Thoracic Society guidelines on respiratory aspects of fitness for diving. *Thorax* 2003;58(1):3–13.

3 Boyle R. New pneumatical experiments about respiration. These experiments, made by that indefatigable benefactour to Philosophy, the Honourable Robert Boyle in order to bring some more light to the doctrine of respiration, as well as to minister occasion to inquisitive naturalists to make farther researches into the same, were by their noble author communicated to the publisher of these papers; who esteem'd it more convenient to make them a part of these tracts (they taking up the room but of a few sheets) than to publish them any other way. *Phil Trans* 1670;5(57–68):2011–31.

4 Boyle R. [New Pneumatical Experiments about Respiration. Continued]. *Phil Trans* 1670; 5(57–68):2035–56.

5 Calder IM. Dysbarism. A review. *Forensic Sci Int* 1986;30(4):237–66.

6 Triger AG. Memoir sur un appareil a air comprime par le placement des puit de mines at autres travaux, sous le eaux et dans les sables submerges. *Comptes rendus de l'Academie des Sciences* 1841;13:884–96.

7 Butler WP. Caisson disease during the construction of the Eads and Brooklyn Bridges: A review. *Undersea Hyperb Med* 2004;31(4):445–59.

8 Pol B, Watelle TJJ. Memoire sur les effets de la compression de l'air appliquee au creusement des puits a houille. *Ann D'Hygiene Publique et de Medecine Legale Ser. 2* 1854;1:241–79.

9 Bert P. *La pression Barométrique: Recherches de Physiologie Expérimentale*, 1st edn. Paris: G. Masson, 1878.

10 Marroni A, *et al.* Dysbaric illness. In: Mathieu D (ed). *Handbook of Hyperbaric Medicine*. Dordrecht: Springer, 2006, pp. 173–216.

11 Smith-Sivertsen J. The origin of intravascular bubbles produced by decompression of rats killed prior to hyperbaric exposure. In: *Fifth Symposium on Underwater Physiology*. 1972. Freeport, Bahamas: Bethesda, Md.: FASEB, 1976.

12 Vann RD, *et al.* Decompression illness. *Lancet* 2011;377(9760):153–64.

13 HSC. *Commercial diving projects offshore. Diving at Work Regulations 1997*. T.H.a.S. Executive, Editor. HSE Books, 1998, p. 47.

14 *National Diving Committee Diving Incidents Report – 2009*. Cumming B (ed). 2009, p. 45.

15 Walker D. *Report on Australian diving deaths: 1972–1993*. Melbourne, 1998.

16 Acott CJ. Recreational scuba diving equipment problems, morbidity and mortality: An overview of the Diving Incident Monitoring Study and Project Stickybeak. *SPUMS J* 2003;33(1):26–30.

17 Walker D. *Report on Australian diving deaths: 1994–1998*. Melbourne, 2002.

18 Pollock NW, *et al. Annual Diving Report – 2008 Edition*. Pollock NW (ed). Durham: Divers Alert Network, 2008, p. 139.

19 Acott CJ. Human error and violations in 1,000 diving incidents: a review of data from the Diving Incident Monitoring Study (DIMS). *SPUMS J* 2005;35(1):11–17.

20 Kalentzos VN. Images in clinical medicine. Cutis marmorata in decompression sickness. *N Engl J Med* 2010;362(23):e67.

21 Oehmichen M, Auer RN, König HG. Special physical trauma. In: *Forensic Neuropathology and Associated Neurology*. Berlin: Springer, 2006, p. 262.

This page intentionally left blank

CHAPTER 25

The Pathology of Sudden Death

- Introduction
- Sudden or unexpected deaths
- Sudden death from cardiac disease
- Coronary atherosclerosis
- Sites of coronary stenosis and occlusion
- Myocardial infarction
- Complications of myocardial infarction
- Cause of death in coronary insufficiency
- Sudden death in aortic valve disease
- Sudden death from the cardiomyopathies
- Death in old age – the senile myocardium
- Sudden death from rupture of an aneurysm
- Pulmonary thromboembolism
- Sudden death in epilepsy
- Sudden death in bronchial asthma
- Respiratory obstruction
- Haemoptysis
- Gastrointestinal haemorrhage
- Fatal abdominal catastrophes
- Genitourinary system
- The relationship between trauma and disease
- References

Introduction

Virtually all forensic pathologists deal not only with criminal, suspicious, accidental and suicidal deaths, but with a wide range of deaths from natural causes. Many of these are sudden, unexpected, clinically unexplained or otherwise obscure, even though there need be no unnatural element in their causation.

It is advantageous when such a large substrate of natural deaths is made available to forensic pathologists: the situation where they deal exclusively with trauma and crime is professionally unhealthy, as they become progressively more out of touch with morbid anatomy, and lose daily contact with disease processes and uninjured tissues and organs. Involvement with natural death means frequent professional intercourse with clinicians and non-forensic pathologists, with all the consequent benefits of cross-fertilization of knowledge and ideas. To work in a totally forensic vacuum is to lose touch with pathological and clinical reality, which is essential for a medico-legal expert to retain a sense of proportion and an awareness of contemporary medical advances (Fig. 25.25).

Another indispensable benefit of sustained experience in natural disease is the fact that some of the most difficult problems in criminal and litigious cases arise not out of gross, rapidly fatal, trauma, but in deaths where concurrent natural disease or complications after trauma lead to a fatal outcome. The assaulted victim that dies later from a stroke or the negligent minor accident that has a fatal pulmonary embolism – these can pose far greater difficulties over causation than a gunshot wound or a stabbing.

In this chapter no attempt is made to duplicate the detailed descriptions of disease processes provided in a score of illustrious textbooks of pathology, but a survey will be offered of the spectrum of causes of sudden or unexpected death as commonly encountered by forensic and 'coroner's' pathologists.

Sudden or unexpected deaths

The definition of a sudden death varies according to authority and convention. The World Health Organization (WHO) definition is of natural death within 24 hours from the onset of symptoms, but this is much too long for many clinicians and pathologists; some will only accept death within 1 hour from the onset of illness.[1] We have to also bear in mind that a death may appear sudden and unexpected to an outsider but need not have been so from the point of the pathological disease process. The deceased may have been symptomless and utterly unaware of his chronic disease or he may have had symptoms but interpreted them as harmless. Also, fear, lack of human contact or his own disposition may have prevented him mentioning symptoms to anyone, including a doctor.

In many jurisdictions, deaths may only be certified by an attending physician if he has seen the patient recently and is satisfied that the death was caused by a potentially lethal disease from which he was aware the patient suffered. The fact that, without autopsy, this physician is wrong in his belief in between 25 and 50 per cent of cases cannot concern us at the moment, but the relevance is that, where a clinical doctor cannot so certify, the death is usually reported for medico-legal investigation. In many countries such notifications form by far the largest proportion of medico-legal autopsies. Since the Shipman murders in the UK (the general practitioner, who killed no fewer than 215 patients between 1975 and 1998),[2] there has been more concern about the proper process. In 2012, some 227,721 deaths were reported to coroners in England and Wales, accounting for an estimated 46 per cent of all registered deaths and in 94,814 of which (42 per cent) a post-mortem was ordered.[3]

The description 'sudden' or 'unexpected' is not always accurate, as 'unexplained' is an equally common reason for medico-legal investigation. Here the clinician is unable to offer a cause for the death, though the patient was under medical care. Even after autopsy, the cause of death may still not be revealed and this problem of the obscure autopsy is discussed elsewhere.[4–7]

In sudden death, the immediate cause is almost always to be found in the cardiovascular system, even though topographically the lesion is not in the heart or great vessels. Massive cerebral haemorrhage, subarachnoid bleeding, ruptured ectopic pregnancy, haemoptysis, haematemesis and pulmonary embolism, for example, join with heart disease and aortic aneurysms to contribute most of the vascular system reasons for sudden, unexpected death.

Sudden death from cardiac disease

Ischaemic heart disease is easily the most common cause of sudden death in Western nations. The term is employed rather loosely and inaccurately, often being used as if it was synonymous with 'coronary atherosclerosis'. Certainly the latter is the largest contributor to ischaemic heart disease, but not to the exclusion of other conditions.

As a further complication of nomenclature, 'coronary atherosclerosis' or 'coronary atheroma' is the proper title of the common degenerative disease that causes most deaths, but the term 'coronary artery disease' is so ingrained into popular usage that it is accepted as synonymous with coronary atherosclerosis, even though there are other coronary diseases.

Ischaemic heart disease comprises:

- coronary atherosclerosis
- hypertensive heart disease
- aortic valve disease
- anomalies of the coronary circulation
- other coronary artery diseases, such as polyarteritis
- cardiomyopathic enlargement
- some congenital heart disease.

Coronary atherosclerosis

Sometimes called 'the Captain of the Men of Death', this is certainly the most frequent cause of sudden death in Western societies. The concepts of the pathogenesis of atherosclerosis have varied in the course of time. In 1815, Joseph Hodgson, a London surgeon, published a monograph on vascular disease and claimed that inflammation was the underlying cause of atherosclerotic lesions.[8,9] The incrustation theory in the pathogenesis of atherosclerosis was proposed by Karl von Rokytansky in 1853, the lipid hypothesis by Rudolf Virchow in 1856 and, again a causative role of inflammation and infection in the pathogenesis of atherosclerosis was proposed by Sir William Osler in 1908.[10–12] Without going into the rather complex details of the modern concepts of atherogenesis, as they are beyond the scope of this book, it can be summarized that, according to the present understanding, an initial insult (for example; chemical, mechanical or immunological) leads to endothelial dysfunction triggering a cascade of complex cellular inflammatory and immunological reactions.[13–16] These in turn lead to the formation of histologically demonstrable stages that can be classified, e.g. according to the American Heart Association (AHA) grading system as modified by Mahmoudi *et al.*, as follows:[16,17]

- Pathological intimal thickening – loose, lipid-rich, fibrous tissue. No lipid core.
- Fibrous cap atheroma – definite lipid core with a thick, sometimes multilayered, cap of fibrous tissue. Limited or patchy calcification. Lymphocytic infiltrates may be prominent, especially at the edge of cores.
- Thin fibrous cap atheroma – lipid core with a thin, sometimes inflamed, fibrous cap. <80 μm in thickness in the coronary, <200 μm in the carotid arteries.

- Plaque rupture – clear evidence of rupture of a fibrous cap and associated thrombus formation.
- Plaque erosion – ulceration of the endothelial lining with thrombus formation. Sometimes seen in early lesions, such as pathological intimal thickening.
- Fibrocalcific lesion – a lesion with fibrosis and large areas of calcification. This is a result of dystrophic calcification of lipid cores.
- Calcified nodule – heavily calcified lesions, probably one of the end stages of the atherosclerotic process.

The basic mechanism is stenosis or occlusion of one or more major branches of the coronary arteries by atheromatous lesions, or one of the complications of such a lesion. The severity of stenosis before death occurs is debatable: cardiac pathologists claim that at least 80 per cent of the normal lumen must be lost before myocardial necrosis occurs. Most forensic pathologists would admit to blaming coronary atheroma for death in autopsies where a significantly smaller percentage of the lumen was lost, when the symptomatology and circumstances were strongly suggestive. Areas of myocardial fibrosis and – rarely – even recent infarcts, may be seen in the presence of relatively small degrees of coronary atheroma. Part of the problem lies in quantifying the amount of stenosis at autopsy. Because of the empty vessels lacking the normal intraluminal blood pressure, the walls are lax, collapsed and unstretched. During life, the same lumen will be larger and only fixation at arterial pressure will retain a semblance of the original size. The pathologist sees all coronary arteries in the dead state, however, so the relative degree of stenosis is still a reliable observation, as both normal and diseased vessels can be compared, even if their absolute luminal size is incorrect.

Coronary atheroma may be focal, with irregular plaques that vary both in size and in stenosing effect from place to place. They may be few and localized, with a virtually normal lumen in the rest of the system. This means that every part of the major vessels must be examined at autopsy, with transverse cuts at no more than 3 mm intervals. It is unjustifiable to make a few cuts at wide intervals and claim that this provides a reliable estimate of the state of the coronary system. A coronary artery is like a chain – just as the latter is only as good as its weakest link, so a vessel is only as good as its narrowest point.

Two cuts, if even 0.5 cm apart, may pass either side of a grossly stenosing plaque or a thrombus. Opening the vessels lengthwise obviates this danger, but this is outweighed by the disadvantage of not being able to measure accurately the degree of stenosis by making frequent cross-cuts. A compromise is the best answer to this dilemma, as described in Chapter 1.

Plaques are often eccentric, leaving a crescentic residual lumen, but another variety of coronary atheroma is a more diffuse lesion, where the vessel is concentrically narrowed by a more longitudinal degeneration, forming a tube-like segment with a narrow, sometimes 'pin-hole' central lumen. The author (BK) has the impression that this is more common in younger victims and that such lesions seem less likely to be ulcerated and calcified. Both types of lesion are often found in the same patient and there is presumably no fundamental difference in their pathogenesis.

Complications in coronary atheromatous lesions

Ulcerated plaques

The simple endothelial thickening develops to involve the media and usually becomes infiltrated with lipids. While the covering endothelium remains intact, the danger to life is confined to the luminal reduction from the bulge of the enlarging plaque. When the fibroendothelial cap begins to break down under the pressure and erosion of the central necrosing process, the plaque may rupture into the lumen. This has several consequences, which may precipitate acute symptoms or even death.

First, a large plaque may suddenly disgorge its pultaceous contents into the lumen. This can mechanically block the vessel or seriously stenose it. Thrombosis may be precipitated at that spot by the slowed blood flow plus thrombogenic tissue elements. The cap of the plaque may be projected across the lumen, forming a sudden and perhaps complete occlusion. This will be more dangerous if the open end of the ruptured plaque faces 'upstream' into the direction of the blood flow, so that the intimal cap is lifted up, causing a valve-like obstruction. When the blood flow sweeps across the cap in the opposite direction, the cap will not be displaced, though the soft, grumous contents of the plaque will be washed downstream. Sometimes the flap can be seen in histological sections, though it is difficult to know if this is a processing artefact. It is best demonstrated directly at autopsy, when two cuts are joined longitudinally and the intima examined with a lens or low-power microscope.

The contents of the plaque may be washed downstream by the blood flow, eventually impacting in small branches and occluding them. These can be seen histologically using lipid stains and the multiple small infarcts that often ensue can be seen either in classical histological sections or, more readily, by enzyme, fluorescent or immunohistochemical techniques. They are probably responsible for many of the small fibrotic areas commonly seen in the myocardia of sufferers from long-standing coronary disease.

Haemorrhage

Haemorrhage often occurs within an atheromatous plaque, usually into the softened, necrotic centre. This 'subintimal haemorrhage' may give rise to a sudden reduction in the blood-carrying capacity of a coronary artery and cause sudden death. The source of the bleeding is somewhat controversial, but the best explanation is that it comes from rupture of small blood vessels in the periphery of a plaque. A normal coronary artery does not have a blood supply to the intima but, in the disorganization frequently associated with the distorted microanatomy of a diseased coronary artery, such vessels may lie within the intima and be eroded by extension of the degenerative process (Fig. 25.1).

Haemorrhages, both fresh and old, can often be demonstrated in histological sections of atheromatous plaques. It is reasonable to presume that such a bleed may be precipitated by some sudden rise in blood pressure from exertion or emotion, though, if a vessel is sufficiently eroded by atheroma, such a precipitation is not strictly necessary for such an event to take place.

The sudden release of blood into an atheromatous lesion can rapidly enlarge it and may raise the cap of the plaque towards the other side of the already stenosed lumen. It may even rupture the plaque: some subintimal haemorrhages may track circumferentially, causing a 'minidissection'. Subintimal haemorrhage as a factor in acute coronary occlusion was investigated many years ago by Patterson, who believed that they played a major part in coronary thrombosis.[18] In the same year, Wartmann demonstrated occlusion by subintimal haemorrhage without rupture of the overlying intima.[19] Though English and Williams doubted if haemorrhage could compress the lumen against arterial pressure,[20] other authors, including Davies and Pomerance believe that the haemodynamics within the coronary vessels are such that the pressure varies markedly from place to place, and that there may even be a contributing factor to subintimal haemorrhage by a suction effect in certain conditions.[21] Other authors, such as Drury, consider that the blood within the plaque is not caused by haemorrhage from mural vessels, but from blood percolating from the lumen of the coronary artery at the time of rupture of a plaque.[22] This seems a minority opinion, however, as many haemorrhages can be seen (some older ones containing haemosiderin) within plaques that have a perfectly intact overlying intima. Whatever the precise origin of the blood, it is clear that subintimal haemorrhage is a potent factor in rapidly reducing the available lumen of a coronary artery – and sometimes precipitating thrombosis by further stretching and damaging the overlying intimal cap.



Figure 25.1 Coronary artery with large partly calcified atheroma and fresh rupture.

Coronary thrombosis

The atheromatous plaque may not undergo these more dramatic changes, but progressive internal necrosis may erode the luminal surface and expose the fibrofatty contents. This loss of normal covering endothelium then forms a nidus for thrombus formation, which may gradually accrete in layers so further reducing the lumen or even occluding it, especially if a combination of lesions causes the plaque to expand at the same time as roughening the surface. Thus mural thrombus may completely block or severely narrow the residual lumen, with all the consequences of reduced blood flow to the distal myocardium.

A narrow lumen is by no means essential to the formation of thrombosis, as it may occur in the abnormally wide, virtually aneurysmal, coronary arteries sometimes seen in aged people. The lumen may be up to 1 cm wide yet be firmly thrombosed, presumably solely because of damage to the intima. Thrombosis often occurs in recanalized vessels, secondary thrombosis taking place after organization and re-establishment of a lumen through the previous block. Multiple coronary thromboses are by no means unusual. Many are post-infarct, the original thrombus causing myocardial necrosis and the resulting stasis in circulation, together with the thrombogenic effect of tissue damage leading to sluggish flow of readily coagulable blood.

It has also been noted that coronary thrombosis may be accompanied by thrombotic lesions elsewhere in the body. For example, a coronary thrombosis may be followed by a pulmonary embolus from thrombosed leg vein – and the converse may also occur in non-fatal pulmonary embolism. The coagulability of the blood, together with circulatory stasis, aided by immobility in bed, are obvious factors.

Sites of coronary stenosis and occlusion

The whole length of the coronary arterial system is not uniformly vulnerable to atheromatous lesions. First, the major trunks are most affected where they lie subepicardially, often in the fatty surface tissue. Once the arteries dip down into the myocardium, these more distal intramuscular branches become much less prone to significant atheroma, especially of the grumous, degenerative type, though intimal thickening may still be seen.

Second, there are sites of predilection in the three major arteries. The most common site of occlusion is in the first 2 cm of the anterior descending branch of the left coronary artery, which is more frequent than in the common trunk. The next most frequent site is in the right coronary artery, but here the thrombosis is more distal than in the left vessel, usually seen as the vessel courses around the right margin of the heart in the atrioventricular groove part-way between aorta and the beginning of the posterior descending branch.

The third most common place is the proximal part of the left circumflex artery, soon after the bifurcation from the common trunk. The latter is then the next most frequent site, in the short segment (sometimes absent) between the aorta and the birfucation into descending and circumflex branches. At autopsy, it is always necessary to transect the proximal part of both coronary arteries right up to the coronary ostia, as occlusion can sometimes be present in the first few millimetres.

Myocardial infarction

There is a different emphasis laid upon myocardial infarction (MI) by the forensic pathologist and by the clinician. To the latter, the clinical signs of chest pain and shock mean an infarct and certainly, a much higher proportion of patients who reach hospital beds do have MIs compared with those who are taken straight to the mortuary. Recently the Joint European Society of Cardiology/American College of Cardiology Committee for the Redefinition of Myocardial Infarction produced a consensus document examining the scientific and societal implications of a new definition for MI from seven points of view: pathology, biochemistry, electrocardiography, imaging, clinical trials, epidemiology and public policy.[23]

In the pathology of sudden death, overt infarcts are the exception, rather than the rule. The incidence in autopsy material from sudden deaths varies considerably, partly because of the different methods of demonstrating the muscle necrosis, but speaking of obvious naked-eye infarcts, the author (BK) would estimate that, in his material considerably less than one-quarter of deaths attributable to coronary atherosclerotic disease have MI. In Finnish autopsy material of the author (PS) the 5-year average (1987–1991) of infarcts among deaths due to coronary atherosclerotic disease was 13.5 per cent. The relevance of this observation in relation to the mechanism of sudden cardiac death is discussed later.

Almost all MIs are caused by atheromatous lesions and their complications. A few are the result of other types of coronary obstruction, such as polyarteritis, other vasculitides, embolism of various types, ostial occlusion by syphilis, severe aortic stenosis, some congenital anomalies of the coronary arteries or great vessels, dissecting aneurysms at the aortic root and tumour or sarcoidosis affecting the coronary vessels.

Most infarcts are caused by super-added coronary thrombosis, but even this statement needs further analysis. A proportion of infarcts have no demonstrable thrombus in the supplying vessel, but this proportion can be reduced by a more careful search. There is no doubt, however, that muscle necrosis can follow severe narrowing of the supplying vessel by subintimal haemorrhage, a ruptured plaque or simple severe stenosis from atheroma. In addition, grumous debris from a ruptured plaque can produce embolic occlusions with ‘microinfarcts’ in the distal myocardium. The fact that some thromboses are post-infarct has already been mentioned.[24]

It is said that the original lumen must be reduced to 20 per cent or less before the ischaemia in the distribution zone is sufficient to cause myocardial necrosis. Most pathologists with considerable experience of sudden death autopsies will, however, have numerous experiences of undoubted infarction in the absence of an 80 per cent stenosis. The embarrassing situation occasionally occurs where an infarct exists with virtually normal coronary arteries.

The contrary is much more common: the finding of complete thrombosis of a major vessel with no sign of infarction. In this case, either an effective collateral circulation provided an alternative blood supply – or the victim died before signs of infarction had time to develop.

There are several types of MI recognizable at autopsy:

- A laminar infarct in which the subendocardial region of much – or even all – of the left ventricle is involved, sometimes extending through half or more of the thickness of the wall. This is due to a reduction in perfusion pressure to the inner zones, as all the coronary supply comes from the epicardial surface. Laminar infarcts are the result of generalized stenosis in the major branches of the coronary vessels, but there is usually a second factor, in that a drop in blood pressure or the oxygenation of the blood compromises the already poor supply so that the outer zones of the ventricular wall consume the available oxygen and nutrients, leaving little for the inner zone. This is discussed further under hypertension and aortic stenosis.
- A regional or focal infarct is more common in pure coronary artery disease, and is caused by a localized occlusion or severe stenosis in a coronary artery. These are true MIs, as the definition of an infarct requires occlusion of the vascular supply, which strictly excludes some laminar infarcts when perfusion pressure or relative insufficiency is caused by hypertension, or aortic valve disease. The regional infarct is a topographically demarcated zone of muscle necrosis, the size and position depending on the site of vascular occlusion, though any collateral supply may modify these. Almost all infarcts are in the left ventricle. Wartmann and Hellerstein found that between 6 and 9 per cent involved the right ventricle and that 7 per cent involved the atria, though Cushing's figure was 17 per cent for atria. Most of these infarcts, however, were overlapping from infarcts in the left ventricle.[25,26]

The relative immunity of the right ventricle and atria is presumably because of the relatively thin walls, which do not require so much blood, do not have the perfusion gradient of the thick left ventricle and can more easily obtain oxygen and other constituents from the blood in the lumen of the ventricle. The presence of a conus artery, small branches to foci, such as to the sinus node, and the presence of anastomotic channels between the left circumflex and right coronary arteries must all contribute to the better survival of these areas. The site of a left ventricular infarct does not always correspond strictly to the site of the coronary occlusion or thrombus because of the presence of a collateral circulation.

It was also shown by Wartmann and Souders that many infarcts involve only certain layers of muscle, which cannot be supplied by a particular vessel.[27] There is obviously no simple explanation for the topography of a MI – this is further confirmed by the patchy nature of myocardial damage on microscopic study, as the alternate necrosis and survival of adjacent fibres or even segments of the same fibre cannot be explained solely by coronary perfusion.

The autopsy diagnosis of early myocardial injury and infarction

The autopsy demonstration of an acute lesion in the heart, such as an early MI, can have profound medico-legal implications. In a fatal traffic accident, or even rail or air crash, the proof of an acute disabling myocardial lesion in the driver may be vital in the investigation of the event and the apportionment of legal liability. In potentially criminal deaths, the presence of a recent infarct again may be relevant in causation or as a contribution to the death. It is thus important to make a full histological search for evidence of myocardial fibre damage, using all relevant methods available. Recent results in post-mortem magnetic resonance imaging (pmMRI) suggest that it may help to visualize early myocardial injury not visible to the naked eye at autopsy, and where available, can be used as supplement to conventional autopsy (Figs 25.2–25.4).[28–30]

The macroscopic appearances of MI are described with a considerable lack of uniformity in most pathology texts, partly because of the varying ages of infarct that the authors depict. The age of an infarct is notoriously difficult to establish in the human, as the onset of clinical symptoms, however dramatically abrupt, are often much later than the onset of the pathological lesion precipitated by a coronary occlusion. In animal experiments, a coronary vessel can be ligated at zero time and serial sacrifices made at different intervals to gain an accurate estimate of the age of the infarct.

In the human, the time of chest pain and shock cannot be used in a similar fashion. When a victim of coronary disease dies, for example 8 hours after the onset of acute symptoms, though one might expect an early infarct to be visible histologically or histochemically,



Figure 25.2 Post-mortem magnetic resonance imaging can serve as supplement to conventional autopsy to visualize very early ischaemic injury. T2-weighted cardiac short axis image (3-T pmMRI; Achiva, Philips Healthcare, Best, the Netherlands). The postero-lateral wall presents with an indistinct hypointense (dark) region without hyperintense (bright) subepicardial margin. The arrow represents the freshly ischaemic area without any oedematous reaction. (Reproduced by kind permission of Professor C. Jackowski.)



Figure 25.3 Post-mortem magnetic resonance imaging (3-T pmMRI; Achiva, Philips Healthcare, Best, the Netherlands) in acute infarction: T2-weighted cardiac short axis image. The lateral wall shows a local hypointense (dark) region with a hyperintense (bright) subepicardial margin representing the necrotic zone, oedema as well as cellular reactions (arrow). (Reproduced by kind permission of Professor C. Jackowski.)



Figure 25.4 Post-mortem magnetic resonance imaging (3-T pmMRI; Achiva, Philips Healthcare, Best, the Netherlands) in left ventricular hypertrophy and fibrotic scarring: T2-weighted cardiac short axis image. Hypertrophic left ventricle with thinned and scarred lateral wall (arrow). (Reproduced by kind permission of Professor C. Jackowski.)

not infrequently a demarcated yellow or tigroid area of necrosis is present, which must be several days old. Occasionally, in spite of long-lasting clinical symptoms the myocardium does not show any macroscopic or microscopic signs of injury whatsoever.

The following appearances are typical of the stages of MI, though marked divergences from this time scale are not uncommon:

- For the first 12–18 or even 24 hours, no definite naked-eye changes are visible. The first sign towards the end of this variable period is oedema of the affected area of muscles, which causes pallor as the swollen fibres squeeze the blood from the vessels that lie between them. The normal moist lustre of the cut surface becomes more granular and dull when cut by a sharp knife. Caution must be used with this feature, because if the scissors are used to cut even normal muscle, the crushed edges of the fibres will give a similar dry, matt appearance.
- From about the end of the first day progressively through the second and third, the area becomes better demarcated and turns yellow. With breakdown of the myocytes, streaks of red appear, being both dilated vascular channels and areas of interfibre haemorrhage. This gives a ‘tigroid’ appearance suggestive of tiger stripes across the area, though sometimes the yellow element is virtually uniform or the red streaks may fade after a few days.

Demarcation becomes more sharply apparent and there may be a red zone in the less damaged muscle around the periphery. The size of the infarct depends on the means with which it is visualized; the naked-eye size is less than the area detectable by classical histology and this in turn is smaller than that demonstrable by enzyme studies, where the more peripheral fibres are sick but potentially recoverable.

- After a few days, progressing through weeks, the infarct becomes softer and more friable, justifying the old name 'myomalacia cordis'. It is at this stage, from about the second or third day onwards, that ruptures occur into the pericardial sac. Some pathology textbooks are in error in stating that such cardiac rupture occurs in early infarcts.
- From the third week and later, the centre of the infarct becomes gelatinous, the colour fading to a translucent grey that often subsides below the level of the cut surface. This rather mucoid stage may still have old haemorrhage within it, but the stage of healing slowly develops and, during the next month or two, depending upon the size of the infarct, fibrosis replaces the dead muscle to form a scar. Even after this stage, there is often a narrow zone around the young fibrous tissue that shows muscle necrosis, though special staining or enzyme techniques may be needed to demonstrate this.

The laminar infarct goes through the same cycle of changes, but this is often less intense. Eventual fibrosis may be widespread but remains thin, often subendocardial, especially on the left ventricular aspect of the interventricular septum where a wide glistening sheet may obscure the underlying muscle. The apex also may show widespread fibrosis and all muscle may be replaced in this region, sometimes leading to a cardiac aneurysm on the free wall. Infarcts may be transmural, extending from epicardium to endocardium, or they may be confined to the inner zone. It is almost impossible to have an infarcted area confined to the outer subepicardial zone because of the topography of the coronary supply. The papillary muscles are usually involved, being particularly vulnerable to ischaemia as they are at the end of the line of coronary supply. The central part of the muscle may necrose and even rupture. Infarction usually spares the immediate subendocardial zone, the three or four most superficial layers of fibres surviving, even though they may show ischaemic damage. They presumably receive enough oxygen and nutrients from the ventricular blood to survive, though this does not seem to prevent deposition of mural thrombus over the infarcted area.

Microscopic appearances of myocardial injury and infarction

There are a vast number of publications on this subject dealing with morphological changes, classical histological methods, enzyme histochemistry, fluorescent studies, immunohistochemical methods and transmission and scanning electron microscopy. Only a brief summary can be offered here.

Morphological changes

There is marked variation from case to case, just as in the gross appearances. The same difficulties exist about assessing the time of onset and hence the age of the infarct. This may sometimes have considerable medico-legal importance, especially when cardiac disease may have caused a traffic or other transportation accident – and is sometimes relevant in criminal circumstances. In animal experiments, changes in myocardial fibres become apparent within 30 seconds of coronary ligation, the first change being a loss of glycogen as the cell shifts from aerobic to anaerobic respiration. This cannot be observed in human material, for obvious reasons. The first observable change is subjective and different pathologists given the same material will offer different opinions on whether or not ischaemic damage is visible. Some of the earliest changes are mimicked by autolysis, especially granularity of the cytoplasm. The infarcted area becomes swollen, so that the interfibre clefts become obliterated, and the overall appearance is pinker and more solid in routine sections. Care must be taken to assess sections of uniform thickness, as material from other laboratories may not conform to the observer's usual quality. Along with swelling, the cytoplasm becomes granular, the 'cloudy swelling' of the old texts.

Early morphological changes seen in light microscopy are unspecific: interstitial oedema, congestion and small haemorrhages. An overstretching of myofibres with a sarcomere length of about 2.5 mm is possible only when the fibre is injured.[31] In experimental infarction in the rat and the dog sarcomere, overstretching has been observed 15 minutes after coronary ligation.[32] Cellular infiltration is variable and neutrophil infiltration is seen in most infarcts during the first few days being replaced by a mononuclear response within 1 week or so.

Contraction bands, known also as myofibrillar degeneration, and coagulative myocytolysis, are commonly described in connection with different pathological conditions. The change signifies irreversible myocyte injury. Contraction bands are irregular, dense and in haematoxylin and eosin (H&E) staining eosinophilic transverse bands alternate with lighter staining granular zones in the myocyte, possibly firstly described by Smith in the periphery of MI.[33] These lesions have been observed in various forms of experimental heart muscle injury and have also been seen, e.g. in association with potassium deficiency, magnesium deficiency, in cases of malignant hyperthermia, in the hearts of drug addicts and in cases of sudden cardiac death (Figs 25.5, 25.6).[34–41]

They may also be seen after blunt trauma to the chest or even cardiopulmonary resuscitation, both where mechanical massage has been applied and especially where cardiac stimulants such as noradrenaline have been injected. In fact, catecholamines seem able to cause this fibre disruption, which may also appear during electrocution and other conditions of cardiac stress. In sections stained with H&E, pale areas in the fibre are common as a result of fibrocytolysis and the sarcolemma is often seen to be deficient at these sites. Although the change signifies fresh and irreversible myocyte injury and is more frequently observed in cardiac deaths, it is not specific to the cardiac death.



Figure 25.5 Contraction bands in myocardium (haematoxylin and eosin [H&E], original magnification ×500).



Figure 25.6 Contraction bands in fresh myocardial infarction (phosphotungstic acid-haematoxylin [PTAH], original magnification ×250).

Contraction bands are best seen by phosphotungstic acid-haematoxylin (PTAH) stain and all myocardial sections should be stained in this way as well as – or even in preference to – H&E. Phosphotungstic acid-haematoxylin stain does not reveal ischaemic damage at an earlier stage, but renders it far more obvious. Large areas can be scanned under low power of the microscope and the danger of missing abnormal areas is far less than with H&E. The striations become distorted and break up, forming either a general 'sandy' appearance or the striking 'contraction bands' where fragmentation occurs in transverse lines across the fibre. The contractile material aggregates into thicker, darker masses, sometimes like 'Chinese writing', at first within an intact sarcolemma, but later the cell membrane ruptures and the basophilic contents scatter extracellularly (Fig. 25.7).

Zonal lesions occur as a region of supercontraction of myocytes at the intercalated discs. These lesions have been observed both in the dog and in humans after haemorrhagic shock and the changes have been considered ubiquitous in, and pathognomonic for, hypovolaemic shock. These possibly reversible changes have been observed in experimentally induced shock in animals 15 minutes after the induction. The presence of catecholamines is also considered necessary.[42,43]

Fragmentation of myocardial fibres is, at least to some extent, practically always present in adult hearts and more frequently in the wall of the left ventricle.[44] Although it has generally been associated with post-mortem changes, it has also been shown to be more



Figure 25.7 Zonal lesions in haemorrhagic shock (H&E).



Figure 25.8 Fragmentation of myocardial fibres (H&E, original magnification ×250).

frequently seen in myocardial samples from sudden cardiac death victims. Early injury possibly increases the brittleness of myocardium, resulting in increased fragmentation of myofibres after the fixation and cutting process. This phenomenon has, however, no value as a positive marker of myocardial injury (Fig. 25.8).

Waviness of fibres was noted by Glogner, who saw corkscrew-shaped myofibres in the heart and skeletal muscle in some cases of beri-beri.[45] Similar patchy deformation of myofibres in a wavelike fashion was seen in association with fatty degeneration of the myocardium and in early and also more advanced human MI. It can be observed more frequently in the wall of the right ventricle in both cardiac deaths and non-cardiac deaths. It has no diagnostic significance as to the cause of death and it signifies only agonal injury.[46]

Later stages

The later stage of infarction follows the 18–24-hour period and, as by now macroscopic changes will be apparent, the histology is merely a confirmatory procedure. Even here, there is great variation in appearances, especially in cellular infiltration. There is a progressive degeneration of the fibres, best seen in longitudinal section. Eosinophila becomes stronger for a time until the internal architecture breaks down. The cellular oedema subsides and interfibre oedema takes over, separating the myofibres, a process that becomes more marked as the latter shrink and fragment.

Loss of nuclei is not an early phenomenon but, by the second to fourth days, the nuclei become hollow, shadowy and eventually ghost-like, though nuclear remnants can sometimes still be seen in completely necrotic infarcts. Cellular infiltration is variable and sometimes does not occur at all, again in contradiction to the established descriptions in most textbooks. In general, however, there is a neutrophil infiltration in most infarcts during the first few days, which subsides gradually and is replaced by a mononuclear response within 1 week or so. These are mainly macrophages clearing up the debris and fibroblasts coming in to lay down new collagen during repair.

By the end of the first week, disintegration of muscle fibres is well under way, and new capillaries and fibroblasts are appearing, though there are many exceptions to this timetable. In general, infarcts are older than most observers think, so that their age is usually underestimated. By the fourth week, depending upon the total size of the infarct – early fibrosis is evident but still with lacunae of necrotic, unrepaired muscle, which heals unevenly and slowly. From this point on there is a variable population of cells, leucocytes diminishing in favour of fibroblasts, macrophages and new vessels.

It is difficult, if not impossible, to date such an infarct even within weeks, and different parts of the same infarct may show quite different appearances. Only when sufficient time has elapsed for all the lesions to catch up with the end stages of firm fibrosis can one say that probably a minimum of about 3 months has elapsed – though again this is dependent on the size and other more imponderable factors, such as age and other concomitant disease.

Histochemical methods

In H&E staining, increased cytoplasmic eosinophilia is an early form of cellular injury partially resulting from increased binding of eosin by cytoplasmic proteins. At the pH conventionally used in staining, eosin is negatively charged. The binding may increase because of greater exposure of positively charged reactive sites along polypeptide chains after their denaturation. The loss of cytoplasmic basophilia usually reflecting detachment and scattering of polysomes from rough-surfaced endoplasmic cisternae is considered as another cause for the increased eosinophilia.

The intensity of eosinophilia increases, sometimes uniformly, but often in patches with advancing injury. It is earlier and more distinctly seen in H&E stained cryosections and can be enhanced by placing a green filter in the light path of the microscope. Patchy hyperchromasia can be observed in all kinds of deaths and therefore it is of limited diagnostic value. Care must be taken to exclude the occasional thickened areas made by cutting artefacts, which look pinker because of a greater depth of cytoplasm. These early changes are not usually visible in the first 8–12 hours after the (presumed) onset of infarction.

Acid fuchsin (AF) was suggested to be useful for demonstration of early MI in man or in animal experiments, but was found to be inconsistent and misleading.

Haematoxylin/basic fuchsin/picric acid stain (HBFP) was claimed to demonstrate early myocardial ischaemia and to be unaffected by post-mortem autolysis. In experiments with isolated cardiac myocytes in suspension made anoxic by complete oxygen deprivation, basic fuchsin was taken up by contracted or damaged myocytes, which, according to their morphology in suspension, revealed irregular contractions, but neither by undamaged nor necrotic myocytes. However, after the first promising reports, contradictory results started to accumulate and the method has been shown to produce inconsistent results and to be unreliable and non-specific and without value for diagnostic purposes.[47–49]

Fluorescent methods

Fluorescent methods have been applied to demonstrate early MIs and myocardial degeneration in animal experiments as well as in human heart, either by using a fluorescent dye, e.g. acridin orange to stain unfixed cryostat sections or paraffin sections, or utilizing the fluorescent properties of eosin in the H&E stained myocardium. Intravenously or intraperitoneally injected tetracycline has also been used in experimental infarction for demonstration of the perfused region in myocardium. Carle claimed that only hypereosinophilic cells autofluoresced, but Badir and Knight found that myocardium that had normal eosinophilic staining also fluoresced yellow in ultraviolet light; this has been confirmed by Saukko and Knight (Fig. 25.9).[50–52]



Figure 25.9 Bright yellowish eosin fluorescence of damaged myofibres (a) corresponding exactly with eosinophilia as seen in the H&E stained cryosection (b) of a fresh myocardial infarction.

Acridin orange stained cryosections of intact myocardium show golden brown fluorescence that turns into greenish fluorescence with increasing ischaemia time, whereas eosin fluorescence of normal myocardium in paraffin-embedded samples show olive-green fluorescence that turns into yellow in injured tissue. Post-mortem autolysis does not seem to have any significant effect on the fluorescence but the high percentage of wrong positive samples indicates that at least eosin fluorescence is obviously too sensitive an injury marker capable of demonstrating agonal ischaemic changes.

A major handicap common to all classical histochemical staining methods is that the basis of these colour reactions is poorly understood. Considering the possible legal implications, it is not reasonable to use such diagnostic methods for medico-legal purposes, when their diagnostic significance is, to say the least, questionable and one does not know for sure what the methods are actually measuring.

Enzyme histochemistry

After Rutenburg *et al.* had found large amounts of succinate dehydrogenase in the myocardium of various species using blue tetrazolium as hydrogen acceptor, this method was also applied to autopsy material and the inactivation of histochemically demonstrable succinate dehydrogenase was observed in human MI.[53] The enzyme histochemical methods became soon widely applied in animal experiments and also to diagnose early human MI in autopsy material. Various oxidative enzymes were demonstrated either by incubating thick myocardial slices in a medium containing a tetrazolium salt with or without exogenous substrate and coenzyme (macromethods) or to stain cryosections observed under the microscope (micromethods) (Figs 25.10–25.14). It was assumed that enzyme histochemistry might be, at least, a ‘semi-quantitative’ indicator of the actual biochemical activity of a given enzyme and, therefore, a scientifically more solid biochemical indicator of myocardial metabolism and injury than the previously discussed traditional histochemical methods. In all, the results between individual authors and laboratories have been extremely variable, suggesting that the situation is not that simple. Hiltunen *et al.* assessed the enzyme histochemical methods, used by the author (PS) in autopsy material, comparing the enzyme histochemical reaction with the actual biochemical acitivity of the enzymes in a global ischaemia model in



Figure 25.10 An infarct of the lateral wall of the left ventricle of between 5–10 hours; duration. It has been rendered visible by staining the heart slice with tripheryltetrazolium chloride, which colours the normal myocardium red by the activity of tissue dehydrogenases. The infarcted area remains unstained. The infarct is virtually transmural, though some subepicardial fibres survive; the papillary muscle is particularly vulnerable, being at the distal end of the coronary supply.



Figure 25.11 Enzyme histochemistry of early myocardial damage. This photomicrograph shows strong succinate dehydrogenase reaction in the myofibres adjacent to the endocardium and moderate decrease of reaction elsewhere suggesting early injury. (Original magnification ×100.)

an animal experiment.[46,54] The results pointed out that, although the enzyme histochemical methods have been named after the enzymes, the enzyme histochemical reactivity need not necessarily correlate with the actual biochemical activity of the enzyme at all, suggesting that other factors, such as the presence of auxiliary enzyme systems or other cofactors of the histochemical reaction, may be rate-limiting. This brings about the same dilemma as with the conventional histochemistry: unless the biochemical basis of any given enzyme histochemical method is thoroughly understood, it is precarious to use it for medico-legal purposes.



Figure 25.12 Fresh myocardial infarction with β-hydroxybutyrate dehydrogenase staining showing positive reaction in the myofibres adjacent to a larger vessel seen above as an empty space. The lower part of the picture shows infarcted myofibres with some lipofuscin but no enzyme reaction. (Original magnification ×160.)



Figure 25.13 The size of a myocardial injury depends upon the method used to display it. These are four serial sections of a heart from autopsy, stained in different ways. Haematoxylin and eosin stained cryosection (a) does not reveal any damage; the adjacent section (b) is stained for malate dehydrogenase activity, and shows strong and uniform reaction. Section (c) is stained for succinic dehydrogenase and reveals a varying degree of enzyme loss in almost all the section, the section (d) on the right stained for ß-hydroxybutyrate dehydrogenase activity reveals a slightly larger area of damage. (Original magnification ×100.)

Immunohistochemical methods

The advances in immunohistochemistry and good results in clinical pathology as well as the availability



Figure 25.14 Patchy loss of malate dehydrogenase reaction simulating early injury. In fact, the injury was caused by artificially prolonged agonal period due to respiratory treatment and cardiac pacing. It was equally well visible in H&E staining, emphasizing the necessity of control staining with conventional methods always when more sensitive methods are used.

of a great number of new antibodies have resulted in numerous publications reporting on potential markers of early myocardial injury in both animal experiments and autopsy material. As it has been shown that ischaemia damages cell membrane, contractile proteins, cytoskeleton and subcellular organelles of the myocardium relatively quickly, the search for better diagnostic methods has been directed to various components of the myofibre, e.g. basement membrane (collagen IV, fibronectin, laminin), cytoskeletal proteins (actin, desmin, alpha- and beta-tubulin), cell-matrix focal adhesion molecules (vinculin, talin), membrane-associated proteins (dystrophin, spectrin), terminal complement complex (C5b-9) and fatty acid binding protein (FABP), among many others. In spite of the plethora of publications, the results have been rather contradictory and/or their practicability difficult to assess due to shortcomings in test material or design.

In spite of better insights into the pathophysiology of myocardial injury, the practical problem as to its diagnostic significance as a cause of death has not changed: whenever myocardial injury has been detected, either macroscopically or by using whatever conventional or more sophisticated methods, *it does not necessarily prove that the injury is the cause of death, unless other causes of death have been excluded*. The rule-of-thumb is that the more sensitive methods are used the greater the probability that agonal period and autolytic changes may be difficult to differentiate from intravital changes.[55]

Complications of myocardial infarction

Ruptured heart

Ruptured heart is the most common cause of a haemopericardium and cardiac tamponade, the rupture always occurring through an infarct. The softened, necrotic muscle gives way from the internal pressure of the ventricular blood during systole, there being no equalizing rise in external pressure. Hypertension will increase the risk, but a more potent factor is a senile, soft myocardium, so that the elderly female is a common victim of a ruptured heart. This by no means excludes younger males if the infarct is extensive and transmural. The most common area for rupture is the more distal part of the free wall of the left ventricle. The septum occasionally ruptures and the consequent left–right shunt, whilst the patient survives, provides a classical diagnostic sign for the stethoscopes of clinicians.

The rupture does not take place in the early stages of a new infarct, but after a day or two when necrotic softening is well established. The blood usually tracks through tortuous channels between muscle bundles, rather than bursting a direct fistula from ventricle to pericardial sac. The infarcted area may not always be obvious, as the haemorrhagic patch may obscure it, but histologically the ragged tissues and the periphery may be seen to be necrosed.

Haemopericardium is the pathological condition found at autopsy and is not quite synonymous with ‘cardiac tamponade’, which is a clinical state caused by the progressive accumulation of blood within the closed pericardial sac. As the external pressure rises, the heart cannot fully expand in diastole to allow filling from the great veins. As input volume falls, so does stroke output. The venous drainage is dammed back so that congestion and cyanosis of the face and neck occur, until a fatal endpoint is reached (Figs 25.15, 25.16).

Mural thrombosis

Mural thrombosis almost inevitably occurs when an infarct is based upon the endocardium of the left ventricle. Though there is usually a thin layer of viable (though sick) cells immediately beneath the endocardium, they do not seem to prevent deposition of platelets and fibrin (Fig. 25.17).

The thrombus is often entwined between the muscular bands lining the distal ventricle, which aids its adherence. When extensive, the thrombus may fill the entire apical area of the ventricle. The layers nearest



Figure 25.15 Blood in pericardial sac shimmering through in cardiac tamponade.



Figure 25.16 A haemopericardium due to a ruptured infarction of the left ventricular anterior wall. The large blood clot caused death from cardiac tamponade.

the endocardium are naturally the oldest, and visible strata (lines of Zahn) are often visible. The youngest layers on the surface are less organized and more friable, so fragments tend to break off and form emboli that enter the arterial circulation, and can cause infarcts in kidney, brain, spleen and even the myocardium itself.



Figure 25.17 Large anteroseptal infarction with mural thrombosis.

Pericarditis

Pericarditis occurs with full-thickness (transmural) infarcts that form the most common cause of pericarditis in Western communities. The visceral pericardium becomes purple–red as a result of the infarct beneath, with a vascular blush on the surface. Granular fibrin deposit causes the surface to lose its glistening sheen, and strands of fibrin may link the visceral and parietal layers together. When healed, fibrous adhesions may form that can obliterate part or even all of the pericardial sac.

Myocardial fibrosis

Myocardial fibrosis has already been described, healed infarcts being replaced by dense collagen, as new muscle cannot be formed. Large plaques from healed infarcts can be anywhere in the left ventricle, depending on the vessel(s) that were occluded. The septum and the posterior wall are more common sites than the anterolateral wall, though the latter is by no means exempt. Often the fibrotic plaques are multiple or irregular, being scattered throughout the ventricular wall (Fig. 25.18).

According to a large autopsy study by Linzbach and Akuamoa-Boateng comprising over 7200 autopsies,



Figure 25.18 Extensive myocardial fibrosis occupying the interventricular septum and apex of the heart with severe occlusive disease of the anterior descending branch of the left coronary artery. Near the apex all the muscle has been replaced by scar tissue. This type of lesion is particularly prone to cause sudden death, as well as clinically apparent dysrhythmias, as the septal fibrosis interrupts the left bundle branch of the cardiac conducting system.

diffuse fibrosis, though commonly seen in elderly people, does not exist as a pure aging phenomenon. It is usually due to problems with the coronary circulation or the end result of past inflammatory processes.[56]

Cardiac aneurysms

Cardiac aneurysms occur where a large area of fibrosis replaces a previous transmural infarct, usually on the distal part of the free wall of the left ventricle. During systole, the cavity blood presses outwards onto the unsupported area and gradually herniates it into the pericardial sac. A saccular aneurysm develops and may undergo various changes, including calcification of the wall, adherence to the parietal pericardium or filling with laminated thrombus. The aneurysm wall is tough and fibrous and, though lacking in elasticity, almost never ruptures – again contradicting some of the dicta of pathology textbooks.

Cause of death in coronary insufficiency

Most sudden deaths from coronary insufficiency do not have MI, even when the most sophisticated techniques are employed for its detection. Neither do the majority have a coronary thrombosis, though severe coronary stenosis is by definition present.

The rare case of MI with only moderate or even minimal coronary atheroma has to be relegated to the realms of mystery in the present state of knowledge, unless some embolic cause can be found. Though spasm is certainly seen by clinicians when performing cardiac catheterizations or cardiac operations, it is very problematic as a morphological diagnosis at autopsy, for obvious reasons.

El-Maraghi and Sealye reported a case of an athletic 25-year-old male who had been hospitalized 15 months before his death because of chest pain and classic electrocardiogram (ECG) findings of an inferior wall infarction on the 4th day after admission. Twelve weeks after infarction on cardiac catheterization the coronary arteries were found to be normal. A year later, he had an episode of chest pain 24 hours before a sudden collapse and death. Post-mortem angiograms 16 hours after the death showed long, cylindrical narrowing of the middle third segment of the left anterior descending (LAD) artery and prominent segmental stenotic irregularities of the middle third of the right coronary artery (RCA), corresponding to puckering of the intimal layer by a series of circular ridges across the lengthwise opened vascular lumen at autopsy. The authors believed the findings to support the coronary spasm hypothesis due to the lack of other obvious explanations for the recurrent MI.[57] Roberts *et al.* found at autopsy a considerable fixed luminal narrowing in the major coronary arteries of three Prinzmetal's angina patients in whom severe spasm had been demonstrated during life.[58] They also found evidence that the narrowing observed at autopsy was a combination of fixed narrowing by atherosclerotic plaques and of that produced by superimposed spasm.

The degree of folding of the internal elastic lamina has been found to reflect the state of contraction *versus* relaxation of normal arteries.[59] Based on this observation, Mortensen *et al.* compared the degree of folding of the internal elastic lamina in the epicardial coronary arteries between 24 sudden unexpected deaths of persons with coronary heart disease (CHD) and 24 subjects dying suddenly from non-coronary causes.[60] They found that the mean percentage of folding of the internal elastic lamina in the distal part of the right coronary artery was statistically significantly higher in the CHD group than in the control subjects, whereas no such difference was found in the other investigated branches of the coronaries. It has also been claimed that coronary artery medial smooth muscle contraction bands may represent a post-mortem marker of ante-mortem coronary spasm.[61]

In most sudden 'coronary' deaths, the usual autopsy finding is of severe, long-standing stenosis sometimes with foci of complete occlusion from a ruptured plaque or a subintimal haemorrhage. There may often be partial thrombosis, in that a plaque or narrow segment may have mural thrombus that further narrows the lumen, though does not totally occlude it.

There is macroscopic and microscopic evidence of myocardial fibrosis in many of these cases. This may either be a large plaque of scar tissue at the site of a previous focal infarct or more diffuse fibrosis. There may be fibrosis subendocardially and in the papillary muscles. In many of these sudden deaths there is no naked-eye or even microscopic evidence of any new lesion in the coronary system or myocardium, so why do they die?

Death must be ascribed to a rhythmical defect, rather than loss of mechanical pumping power. Myocardium and especially the pacemaking and conducting system, is vulnerable to ischaemia and hypoxia. Disturbances of rhythm, from ectopic beats to atrial fibrillation through to ventricular fibrillation and cardiac arrest, may occur, as well as heart block and the many other clinical manifestations of ischaemic heart disease from whatever cause. In addition, many victims are hypertensive and left ventricular hypertrophy exacerbates their relative coronary insufficiency. Anyone with a heart weighing more than 450 g is a candidate for sudden death, with or without coronary artery stenosis.[62] The mechanism of this sudden type of death, where there is no large infarct, seems to be a state of electrical instability from chronic hypoxia, so that sudden stresses (such as exercise or emotion) can suddenly cause the arrhythmias mentioned above, though it must be said that death can occur without any of these factors while the victim is asleep or at rest. It is known that the myocardium is sensitive to catecholamines, this being a physiological response to intrinsic adrenergic hormones. Excess catecholamines given parenterally can cause arrhythmias and even contraction band damage to the myofibrils. Certain other drugs, such as organic solvents, can sensitize the myocardium to even physiological amounts of noradrenaline, leading to ventricular fibrillation and sudden death.

Those with fibrosis in the myocardium may have the additional risk of interruption of the conducting system, which may give some degree of heart block or defect in the spread of the contraction impulse, rendering them more prone to arrhythmias and arrest. This is especially so where a large fibrotic plaque occupies the interventricular septum, as here the left bundle branch penetrates to supply the apical region and may be strangled by dense fibrosis.

Where there is a recent coronary thrombosis, the absence of an infarct may mean that insufficient time has elapsed for it to become apparent, but of course the pumping efficiency will be compromised and the risks of electrical disturbance will already be operating, so that all the problems listed above exist. The other reason for lack of an infarct is an adequate collateral circulation but, even though necrosis is avoided, a new coronary occlusion can only further worsen the ischaemic and hypoxic state of the myocardium, with all the potential consequences of electrical instability.

If there is an infarct, then again all the above dangers exist, but there is the added liability of a loss of mechanical pumping function, which, with a large infarct, may be a substantial proportion of the whole cardiac output, leading to overt low-output failure during which sudden death can supervene at any time. In addition, the risks of sequelae of MI, such as rupture and embolism, are ever present.

The role of the conducting system in sudden cardiac deaths is one that is attracting increasing interest, especially as new histological and immunohistochemical techniques are becoming available. A revised sampling technique, described by Song *et al.*, uses longitudinal sectioning, reduces the workload and allows observation of continuity between different components of the cardiac conduction tissue.[63] It demonstrates the sino-atrial (SA) node, the atrio-ventricular (AV) node and the distal part of the His bundle and the bundle branches of the cardiac conduction system in 4–5 blocks. However, although a significant number of abnormalities can be recognized, it is usually difficult or impossible to relate morphology to function. The fact that an AV or SA node, or the bundle of His or its branches shows fibrosis or some other lesion, does not necessarily mean that this played any part in the death. It has been shown that the conducting system is remodelled with advancing age – and many deaths from obvious extracardiac causes reveal lesions in the conducting system when studied at autopsy.[64,65] Nevertheless, new knowledge now being accumulated about the conducting system may become useful in investigated sudden cardiac deaths, as it is obvious that a high proportion of these fatalities, which have no recent acute lesion demonstrable in the coronary arteries or myocardium, are due to arrhythmias and functional arrest, in which abnormalities of the propagation of the pacing impulse may be important. James has suggested that apoptosis, the programmed cell death, might be a logical explanation and responsible for histological abnormalities of the cardiac conduction system in sudden deaths due to progressive development of complete heart block and various arrhythmias.[66–68]

Hypertension may kill in a number of ways, such as by renal failure, ruptured aneurysm or cerebral haemorrhage, but here we are concerned with primary heart failure, a quite common cause of death.[69] During life, the clinical syndrome of 'cardiac asthma' or 'paraoxysmal nocturnal dyspnoea' is caused by pulmonary oedema from hypertensive left ventricular failure. The same oedema is a marked feature of the autopsy on fatal hypertensive heart disease.

Because there is an aetiological connection between hypertension and coronary atheroma, the two conditions are often present together in a victim of sudden death, making it difficult to separate the myocardial consequences of each component. Sufficient 'pure' deaths from hypertensive heart disease are available where there is no concurrent coronary disease, however, to establish the effect of the former on the myocardium. When the left ventricle has to work against a higher pressure in the systemic arteries, the muscle fibres hypertrophy. They cannot increase in number, but they increase in length and thickness, with irregularity and enlargement of nuclei. This fibre enlargement leads to increase in the mass of the left ventricle, the well-known 'concentric hypertrophy' of hypertension (Figs 25.19, 25.32, 25.33).[62,70]

If 360–380 g is taken as the upper limit of heart weight for an average size male, then hypertensive disease may produce hearts of 500–700 g. Hearts larger than this usually have some other cause, such as valvular disease or a cardiomyopathy. Though it is sometimes denied that hypertension can cause sudden death, most forensic pathologists would strongly disagree, all having performed numerous autopsies where no other reasonable explanation existed. The usual picture is of marked pulmonary oedema fluid running freely from the cut surfaces of the lungs because of a terminal failure of the left ventricle slightly prior to right ventricular arrest. This causes a rapid rise in pulmonary artery pressure and consequent transudation across the pulmonary alveolar membranes.



Figure 25.19 Concentric hypertrophy of the left ventricle in a person with cardiomegaly from hypertension. The slice has been stained with triphenyl tetrazolium chloride to reveal dehydrogenase activity; some mottled areas, especially in the septum, show pallor from reduced enzyme activity as a result of relative ischaemia of the increased muscle mass.

There may not always be evidence of hypertension in the often sparse history available at sudden death, but the presence of concentric hypertrophy in the absence of valve disease or a cardiomyopathy – together with characteristic changes in other vessels and organs, such as the kidney – is strong evidence of raised blood pressure. Sometimes the overall weight of the heart may be normal, yet there is relative left ventricular thickening; this again suggests hypertension. In the hearts of aged people, the usual atrophy – with tortuous surface vessels – may be concealed by a left ventricular hypertrophy, keeping the heart at normal weight.

The existence of hypertensive heart disease as a specific entity was strengthened by some investigations published by one of the present authors (BK) in 1973, in which it was shown that gross enzyme deficiencies exist in the inner part of the wall of the hypertrophied left ventricle.[71] This lesion is not specific to hypertension, but is seen whenever the left ventricle is enlarged, notably in aortic valve disease. In severe instances, the defect in dehydrogenase activity extends from endocardium almost to the epicardium, there being only a narrow zone of normal activity. In some ways this defect is similar to the 'laminar infarct' of coronary artery disease.

In pure hypertension and aortic valve disease, the cause is a relative ischaemia of the inner zone of the ventricular wall caused by insufficiency of coronary blood supply compared with the demands of the thickened ventricular mass. The reason for the laminar distribution is the anatomy of the coronary supply, graphically described by Farrer-Brown.[72,73] The various levels or strata of the ventricular wall have different arterial patterns. The subendocardial zone is supplied by arteries with many branching terminations that provide a profuse and concentrated blood supply. A second set of vessels passes straight through the ventricular wall without division – all the coronary supply coming, of course, from the epicardial surface. This set serves the papillary muscles and trabeculae carnae, while a third group tends to run circumferentially parallel and below the epicardium, giving branches both outwards and inwards.

Farrer-Brown found that the termination of these vessels were of two types, as they divided into arterioles and then capillaries. The direction of the tree-like branching in the subendocardial zone continued in the general line of the main artery. The area of myocardium supplied by these branches was small. This was in contrast to the pattern in the mid-zone of the wall, where the branches turned at an angle to the main artery and then divided to supply a much wider area of myocardium that was supplied by the terminal branch in the subendocardial zone. These anatomical differences suggest that the vessels in the mid-zone each have to supply a larger volume of muscle than in the other layers. This might well explain the greater vulnerability of this central zone to hypoxic changes, as indicated by reduced enzyme activity and the occurrence of laminar necrosis. In actual practice, the inner zone also suffers, apart from the immediate subendocardial layers, but the superficial subepicardial zone is almost always spared. The rationale of damage to the myocardium in hypertensive heart disease, as in aortic stenosis, would appear to be a relative coronary insufficiency. In pure coronary artery disease, part of a normal-sized myocardial mass is rendered ischaemic by localized reduction of blood flow by a coronary stenosis or occlusion, the resulting necrosis being distributed in a focal pattern according to the location of the block.

In hypertensive heart disease, normal coronary arteries attempt to supply a much larger muscle mass, so that there is the same imbalance between supply and demand. As there is no focal blockage, however, the resulting lesion is diffuse and the areas that suffer most are those in the mid- and inner zones, probably because of the microanatomy of the vessels described above. The same type of lesion may be seen in any severe sustained hypotensive episode of extracardiac cause, though the early onset of death in many of these will preclude the development of morphological evidence of laminar myocardial damage.

Sudden death in aortic valve disease

A similar situation exists with aortic valve disease in which stenosis rather than incompetence can lead to sudden death. Most of the lesions are primarily degenerative, the commonest being ‘idiopathic calcific aortic stenosis’, most often seen in elderly males. Aortic stenosis of rheumatic origin always affects the mitral valve before the aortic, so a solitary aortic lesion cannot be ascribed to rheumatism and is therefore of the primary degenerative type. Rheumatic valve disease is becoming rare, both with the decline in rheumatic fever and the frequency with which valve lesions are treated surgically at an earlier stage, before marked ventricular hypertrophy and its myocardial lesions are evident.

In the common calcific disease, the valve is thickened and rigid, with fusion of the commissures in most cases. There may be large, irregular excrescences on the cusps and in the sinuses behind. At a later stage, the whole valve may be an almost unrecognizable, chalky mass, with a lumen barely wide enough to admit a pencil. This type of valve may have been biscuspid from birth, a condition that undoubtedly encourages calcific degeneration. Many stenotic and apparently bicuspid valves are not truly bicuspid, however, but appear so because the degenerative process has destroyed or obliterated one of the commissures between the cusps. This may often be demonstrated by the fact that a trace of the commissure may still be seen, or by the fact that the two surviving cusps are not equal in size, the commissures being placed at 120° rather than 180°.

A tight aortic valve, from whatever cause, obstructs the outflow tract of the left ventricle and causes the muscle to hypertrophy in order to eject the same stroke volume through a narrower orifice. In addition, if there is associated regurgitation, further extra work has to be performed to attempt to throw out the refluxed blood (Fig. 25.20).

The effect of a severe aortic stenosis in relation to sudden death is to enlarge the left ventricle to sizes even greater than those seen in hypertension. Some of the biggest hearts (excepting some cardiomyopathies) are seen in aortic valve



Figure 25.20 Calcific aortic stenosis, a common cause of sudden unexpected death especially in older males. Marked left ventricular hypertrophy usually ensues, the large muscle mass becoming ischaemic, especially in the inner layers.

disease, reaching up to 800 g or – exceptionally – 1000 g. Another effect of a tight valve is to lower the perfusion pressure in the coronary arteries, which is made worse if there is also an element of regurgitation. It is the diastolic pressure in the proximal aorta that feeds the coronary supply, as during systole the contraction of the heart prevents flow in the intramural arteries. A less common effect may be the distortion of the coronary ostia by calcific masses in the sinuses of Valsalva and the wall of the root of the aorta, which can partly block the entry into the coronary vessels. The combination of a large myocardial mass and decreased coronary flow is often made worse by concomitant coronary atherosclerosis, so the propensity of victims of aortic valve disease to drop dead is considerable. Elderly males are the most frequent victims. Lesions of other heart valves seldom cause sudden death as an isolated cause, though the more chronic cardiac dysfunction – mainly congestive cardiac failure – caused by them may end life rather abruptly on occasions. Rheumatic mitral stenosis is one such lesion, but perhaps a more direct mitral cause of sudden death is the 'floppy' valve.[74,75]

Sudden death from the cardiomyopathies

There is a heterogenous group of diseases of myocardium associated with cardiac dysfunction known as the 'cardiomyopathies', which, though of mixed and often uncertain aetiology, have sufficient in common pathologically to merit a special identity. As they account for the second largest number of sudden deaths after coronary artery disease, i.e. about 10–15 per cent of all sudden deaths of cardiac origin, they are briefly described here, though specialized texts and papers on cardiac pathology should be consulted for details. The outstanding feature is a large heart in the absence of hypertension or valve lesions. The victims are usually young adults, partly because in older groups in which there is atherosclerotic coronary disease and also hypertension, these overlay the cardiomyopathy and make the diagnosis difficult or impossible. The only exception is if there is definite histological evidence or if the heart weight is excessive (over 700 g) in the absence of a valve defect. Cardiomyopathies are the most common cause of heart failure and are an important cause of death in children and adults. According to the Report of the 1995 WHO/International Society and Federation of Cardiology Task Force on the Definition and Classification of Cardiomyopathies, they are classified into the following main types: dilated, hypertrophic, restrictive and arrhythmogenic right ventricular cardiomyopathy.[76]

Dilated cardiomyopathy (DCM) is the most common cause of congestive heart failure. The annual incidence varies, depending on the diagnostic criteria, from two to eight cases per 100000. Around 30–40 per cent of them are familial (FDCM), but it may also be idiopathic, viral, immune or toxic, e.g. alcoholic. Idiopathic dilated cardiomyopathy (IDCM) is characterized by dilated ventricular chamber and reduced contractility without coronary, valvular or pericardial disease. Histology is non-specific; however, viral genome has been identified in 10–34 per cent of patients with DCM.

Hypertrophic (obstructive) cardiomyopathy was first described in medico-legal autopsy material by a London forensic pathologist, Donald Teare, in 1958.[77] Although he noted and described asymmetrical hypertrophy of the interventricular septum, so that a bulging pad of myocardium partly obstructed the left ventricular outflow tract, this cardiomyopathy is predominantly (75 per cent) a non-obstructive disease and, hence, hypertrophic cardiomyopathy (HCM) is now the preferred name. It is a primary sarcomere disorder characterized by left and/or right ventricular hypertrophy and, in most cases, inherited as a predominantly autosomal disease. It is caused by mutations of any of the genes encoding the proteins of the cardiac sarcomere.

Between 20 and 30 per cent are familial, and the condition may occur at any age from infancy to senility, though the majority of deaths occur in early middle age. The weight of the heart may range from a high normal at 400 g, to 800 g or even 1 kg. More striking than the total weight is the left ventricular preponderance, which is often maximum in the proximal septum, as described above.

Histologically the myocardium shows irregular-sized, large fibres with nuclear pleomorphism. Though once thought to be a rhabdomyoma or a hamartoma, or aberrant adrenergic tissue, the septal bulge usually shows a bizarre pattern of fibres, with loss of the orderly strata and replacement by a criss-crossing, confused architecture of muscle bundles (Fig. 25.21). Interstitial fibrosis is common, and – though there may be an increase in interstitial cellularity – inflammatory infiltrate is not seen, as it would be in an active myocarditis.

Restrictive cardiomyopathy is, according to the WHO report, 'characterized by restrictive filling and reduced diastolic volume of either or both ventricles with normal or near-normal systolic function and wall thickness. Increased interstitial fibrosis may be present'. It may be



Figure 25.21 Myofibre disarray in hypertrophic cardiomyopathy.

idiopathic or associated with other diseases such as cardiac amyloidosis, cardiac haemochromatosis or endocardial fibroelastosis with or without hypereosinophilia.

Arrhythmogenic right ventricular cardiomyopathy (ARVC) is a primary myocardial disorder characterized by progressive fibrofatty degeneration of right ventricular myocardium, arrhythmias and risk of sudden death. In addition to familial autosomal-dominant disease with variable penetrance and polymorphic phenotype, two autosomal-recessive forms of ARVC are known.

The WHO classification includes further two groups of cardiomyopathies:

- specific cardiomyopathies that are associated with specific cardiac or systemic (ischaemic, valvular, hypertensive, inflammatory, metabolic, general systemic, e.g. connective tissue or neuromuscular disorders) and
- unclassified cardiomyopathies, which do not fit readily in any group, e.g. fibroelastosis or isolated non-compaction of the ventricular myocardium (INVM), a rare disorder characterized by excessively prominent trabecular meshwork, ventricular arrhythmia and systemic embolism.

Myocarditis

Many infective diseases produce an acute myocarditis, which may be the immediate cause of death. A prime example is diphtheria, but this has virtually no forensic relevance. More important is 'isolated myocarditis', where the condition is primary and usually of unknown aetiology. Known by a variety of names, such as 'Fiedler's' or 'Saphir's' myocarditis, its incidence was said to be appreciable in victims of sudden death – and it was incriminated as the cause of accidents on the road and in the air that had been attributed to driver or pilot incapacity.[78] In forensic pathology some 30–40 years ago, it became a 'fashionable' diagnosis on rather equivocal histological criteria. It was then found that many victims of trauma where death was rapid and where cardiac incapacity could not possibly be a causative factor in the accident, also had foci of mononuclear cells in the myocardium.

Stevens and Ground, after finding six cases of myocarditis in 263 air pilots, when none of them could have been affected by a cardiac event, looked at a considerable number of other accident victims in circumstances in which disease was obviously unrelated to the trauma. They found about 5 per cent of young males had lesions otherwise histologically acceptable as 'myocarditis' and concluded that it was an unsafe diagnosis to use for the cause of death.[79] Their histological minimum criteria for acceptance was one focus of 100 or more cells or many foci of half that size. Groups of lymphocytes, especially subepicardial of 40 or fewer cells, were disregarded.

In Australia, Tongue *et al.* did similar studies, but used whole transverse sections of ventricles at up to 18 levels in each heart. Their results showed that the more extensive the search, the greater the number of foci discovered in deaths that had no circumstantial relation to a sudden cardiac death. Using 18 full sections, they found that 90 per cent of the accident victims had 'myocarditis' lesions and suggested that, if the search was extensive enough, it could probably be brought up to 100 per cent.[80,81]

The Dallas Classification System was proposed by eight cardiac pathologists in an attempt to provide the practicing pathologists with easily applicable and uniform criteria for the diagnosis of myocarditis in endomyocardial biopsies.[82,83] By this definition, the diagnosis of myocarditis can be made only if myocyte necrosis or degeneration or both are associated with an inflammatory infiltrate adjacent to the degenerating or necrotic myocytes. A semi-quantitation of the amount of inflammatory infiltrate was suggested as mild, moderate, or severe and its distribution characterized as focal, confluent or diffuse. The composition of inflammatory infiltrate, i.e. the presence of lymphocytes, neutrophils, eosinophils or giant cells, was suggested for differential diagnosis of the aetiology. According to Feldman and McNamara the Dallas criteria probably underestimate the true incidence of myocarditis.[84]

All death certificates with myocarditis recorded as the underlying cause of death in Finland from 1970 to 1998 (n = 639) were retrospectively collected for a study. All cases with cardiac autopsy samples and clinical data available (n = 142) were included in this study. The cardiac samples were re-examined for the presence of myocarditis by three experienced independent pathologists using the Dallas criteria. Histopathologically recognizable myocarditis was more common in paediatric patients than in adult patients (75 per cent versus 28 per cent, respectively, P = 0.001). Sex, type of autopsy (hospital versus medico-legal), or autopsy date (before or after 1987) did not affect the proportion of Dallas-positive myocarditis in this study. A tendency to over diagnose myocarditis on routine autopsies was particularly seen in those cases where the patients had died suddenly without any obvious cause.[85] The death certificate-based incidence of fatal myocarditis in this study was 0.46 per 100,000, and the histopathologically corrected incidence was 0.15 per 100,000 (Figs 25.22–25.24).[86]

Among the great variety of infectious agents, viruses have been considered as important cause of myocarditis. The molecular biological techniques such as polymerase chain reaction (PCR) and *in situ* hybridization have provided new diagnostic possibilities and viral genome has been detected both in myocardial biopsies as well as in autopsy material. However, the detection rate and the viruses identified have varied markedly according to the study.



Figure 25.22 Myocarditis cannot be diagnosed without microscopy but sometimes the macroscopic appearance of the myocardium may suggest an on-going pathological process. The pale, mottled and oedematous myocardial cut surface of a 2-month-old infant, who died suddenly after 4 days of fatigue, poor eating and drinking and vomiting but without fever, revealed a myocarditis in microscopy (see Fig. 25.23).



Figure 25.23 In all samples taken from the left ventricular wall, injury of myofibres is seen with rich infiltration of inflammatory cells consisting of lymphocytes, macrophages, plasmacells and eosinophile granulocytes.



Figure 25.24 Severe diffuse lymphocytic myocarditis with destruction of myocytes. (H&E, original magnification ×10.)

In our fatal myocarditis study with 40 patients (20 males and 20 females; median age, 49 years) with myocarditis that fulfilled the Dallas criteria and 12 subjects who had died accidentally serving as control, PCR and *in situ* hybridization assays were used for detection of viral genomes (adenovirus, cytomegalovirus, enterovirus, human herpesvirus 6, influenza A and B viruses, parvovirus B19 and rhinovirus) in heart samples. Viral nucleic acids were found in the hearts of 17 patients (43 per cent), including cytomegalovirus (15 patients), parvovirus B19 (four patients), enterovirus (one patient), and human herpesvirus 6 (one patient). In four patients, cytomegalovirus DNA was found in addition to parvovirus B19 or enterovirus genomes. No adenoviruses, rhinoviruses or influenza viruses were detected in this



Figure 25.25 Occasionally microscopy can reveal a malignant systemic disease such as intravascular large b-cell lymphoma showing large atypical lymphocytes, which immunohistochemically were proven to be B cells.

study of fatal myocarditis. In 67 per cent of the patients for whom PCR was positive for cytomegalovirus, *in situ* hybridization revealed viral DNA in cardiomyocytes. Only one of these patients was immunocompromised. In the control group, only human herpesvirus 6 (one subject) and parvovirus B19 (one subject) DNA were detected.[86,87]

It may be useful to remind ourselves that the presence of viral nucleic acids samples, i.e. PCR-positivity, is no proof of an active inflammatory process in the myocardium. Assuming that the sample is not contaminated and the virus is not carried by the blood cells (lymphocytes), it shows that the heart is infected but it does not yet prove that it is a myocarditis. Further localization of the virus genome within the myofibre using *in situ* hybridization and the fulfilment of the other morphologic diagnostic criteria of myocarditis allows the speculation on possible causalities.

In addition, drugs may cause myocarditis, either through direct toxic or immune-mediated mechanism.[88,89]

Probably, the position now to be accepted is that unless multiple, florid foci are found, with myofibril necrosis seen, using special stains if necessary, bland mononuclear foci that are purely interstitial and not involving muscle fibres must be disregarded. The presence of myofibre necrosis, however localized, would appear the most important confirmatory criterion. Where stenotic coronary artery disease exists, it can be difficult or impossible to differentiate the resulting cellularity, fibrosis and fibre necrosis from that of a myocarditis.

A disease process that may well have been underestimated in the pathology of sudden death is cardiac sarcoidosis. Unless routine histology is carried out on every sudden death, this diagnosis will be missed as will a considerable number of myocardial amyloidoses, which need special stains.[90]

Death in old age – the senile myocardium

In many autopsies on old persons, no specific lesions can be discovered that provide a clear cause of death. In the increasingly aged population of the developed nations, this problem becomes a more frequent task for the pathologist. The history of the mode of death then becomes particularly important, as it may give some clue as to which area of the indeterminate lesions should be given priority in deciding on a cause of death. For instance, if there is moderate coronary artery disease, then if the person died with sudden breathlessness or chest pain, rather than slowly fading away, more credence would be given to the coronary lesions. Many old people have good, patent coronary arteries, however, even if the walls may be calcified – if they did not have such good vessels, they probably would not have lived to 88 or 95 years, anyway.

Where nothing other than general senile atrophy of most organs is found and the history is unhelpful as to a specific mode of death, as long as the pathologist can exclude any unnatural cause, then it is quite legitimate to ascribe the death to ‘myocardial degeneration due to senility’. The WHO’s ICD-10 (International Statistical Classification of Diseases and Related Health Problems, Tenth Revision, Geneva 1992) provides a code for such a disease even though many cardiac pathologists seem reluctant to agree to its existence, wishing always to find some more specific disease process. In the authors’ view, senile myocardial degeneration is quite acceptable, given exclusion of other causes. Senile hearts are usually small, but hypertension may have enlarged the ventricles long ago and the residual effect of this may be to sustain the heart at a normal weight. More important is the appearance of the heart, which is brown on the surface and in the muscle and is flabby and soft. The thumb can be pushed into such muscle at autopsy without difficulty. The weight may be down to 300 g or even 250 g, if no previous hypertrophy has existed. A good indication of cardiac atrophy is the presence of tortuous coronary vessels on the epicardial surface, especially the anterior descending branches. These may meander markedly, as the myocardium has shrunk, the apex has contracted nearer the base and so the vessels have to corrugate to fit into the diminished space.

Microscopically, the myocardial fibres are uneven in size, there may be a fine, diffuse fibrosis, which is not ischaemic in origin and the nuclei of the myocytes have prominent clumps of lipofuscin pigment at their poles. Unfortunately, none of these features is diagnostic of the cause of death, as other old persons dying of quite unrelated causes, such as trauma, might have equally poor heart muscle.

The justification for considering that senile myocardial degeneration is a valid cause of death comes from the species life span of different animals. Even without lethal specific disease, each species has a fairly uniform life span, the human being some 70–90 years. No one lives to 150 years, so there must be some limiting factor; as cardiac function is the most immediate arbiter of survival, it seems reasonable to indict heart contractibility as the primary factor. All tissues age, but senility of the spleen or thumbs does not have the immediacy for life support possessed by the myocardium.

Sudden death from rupture of an aneurysm

The most frequent extracardiac cause for sudden death arising in the cardiovascular system is a rupture of an aneurysm, almost always of the aorta or a cerebral vessel. Aortic aneurysms are of three types, all capable of catastrophic rupture.

The atheromatous aneurysm

The atheromatous aneurysm is the most common and is seen mainly in the abdominal segment of the aorta.[91] Though atherosclerosis affects the whole length of the aorta, it is usually worse below the diaphragm, probably because of the haemodynamic effects of the larger branches that come off in this segment. Turbulence and 'Venturi' effects are known to localize the development of fatty streaks and atheromatous plaques, as they are seen first around the ostia of the intercostal vessels and become particularly severe at the major bifurcation into common iliac arteries. Though aneurysms can develop at any point in the aorta, most are below the diaphragm. Excepting dissecting aneurysms, however, any aneurysm in the thoracic segment is still more likely to be atheromatous than syphilitic, even though syphilis is virtually confined to the aortic arch. Most atheromatous aneurysms are fusiform or saccular, the bulge being either symmetrical about the axis of the vessel or more commonly bulging out more on one side than the other. Progressive destruction of the media by the fibrolipid degenerative processes of atherosclerosis leads to weakening of the aortic wall. Bulging caused by the continuous internal blood pressure begins, aided by the hypertensive tendencies of later life. The damage or complete destruction of the intima leads to platelet and fibrin deposition, so that mural thrombosis is laid down in the expanding aneurysm. This may partly or wholly fill the sac, being many centimetres thick in some instances, with well-marked stratification called the 'lines of Zahn'. The wall of the aneurysm may contain calcific fragments similar to the adjacent artery wall.

Most aneurysms remain intact throughout life and are found as incidental findings at autopsy. Naturally the incidence of ruptured aneurysms is greater in medico-legal autopsies by reason of the selective population of sudden deaths. When rupture occurs, the weakest point of the wall is penetrated by the contained blood and this usually leaks out into the retroperitoneal tissues, rather than free bleeding into the peritoneal cavity. The blood tracks behind the root of the mesentery and around the kidney. A large perirenal haematoma may form but, more often, the obvious site of bleeding is in the centre of the back of the abdomen. The diagnosis is usually quite obvious as soon as the autopsy begins for, as soon as the abdomen is opened and the intestine moved aside, a dark red mound may be seen projecting forwards over the lumbar spine, bulging at the root of the mesentery.

The development of a successful technique for the repair of many such arterial defects has reduced the death rate, though there is a substantial perioperative mortality, often because the patient is virtually moribund when the operation begins, or because gross calcification and degeneration of the remaining aortic wall makes it technically impracticable.

The dissecting aneurysm

Rupture of a dissecting aneurysm of the aorta is much less common than the atheromatous variety. It is still by no means an uncommon cause of sudden death, however, and is the second most frequent cause of a haemopericardium and cardiac tamponade. Whereas atheromatous aneurysms are usually in the abdomen, the dissecting aneurysm can span the whole length of the vessel from iliac artery to aortic valve, though the main effects are usually manifest in the thoracic segment.[92]

The basic lesion is a degeneration of the aortic media, the so-called ‘medionecrosis’. The thick elastic media becomes degenerate and cystic in the central layers, producing a vessel wall like a sandwich with a soft cleavage plane in the middle. This defect is of unknown aetiology and affects both the elastic and muscular elements of the media. It is relatively common over the age of 50, especially in males. Many aortas seen at autopsy have this degeneration, but no aneurysms, as they never develop because the blood fails to enter the potential cleavage space from the lumen of the aorta.

In most cases where a dissecting aneurysm has caused death, the blood has broken through from the lumen through a tear in an atheromatous plaque, which is a quite separate disease process existing in parallel with the medionecrosis. When blood enters the medial cleft under high arterial pressure, the two layers of the media are split apart and the dissection may rapidly travel both upwards and downwards in the aortic wall. The upper component may split its way around the arch and beyond the attachment of the pericardium. Here, just above the aortic ring, the dissecting haemorrhage often bursts through the remaining outer media and adventitia into the pericardial sac. This causes a massive haemopericardium and the cardiac tamponade described earlier in relation to ruptured MI. The distal extension may travel down to the iliac and even femoral arteries, sheathing them in blood. Rarely, in a patient who survives a dissection, the secondary lumen formed in the cleavage plane may rupture back into the main aortic lumen, thus forming a ‘double-barrelled’ aorta, a curiosity occasionally found at autopsy (Figs 25.26, 25.27).



Figure 25.26 A ‘double-barrelled’ aorta after survived aortic dissection.



Figure 25.27 Opening into the false lumen of a ‘double-barrelled’ aorta after survived aortic dissection.



Figure 25.28 Sudden unexpected death caused by a myxoma of the left atrium. The ball-shaped mucoid tumour impacted in the mitral valve during a postural change. No other cause of death was discernible.

Death usually occurs from cardiac tamponade, but some dissections do not burst into the pericardium. Here death is by a less obvious mechanism, which may be partly the sudden narrowing of the aortic lumen and pressure on the coronary ostia and roots of the coronary arteries. In persons under 50 years of age, there is a much less common alternative cause of medionecrosis, known as Erdheim’s degeneration. This is sometimes called ‘mucoid medial degeneration’ and is associated with Marfan’s syndrome, an inherited condition characterized by arachnodactyly and optic, aural and bony lesions. A recent systematic literature survey on causes of non-traumatic and spontaneous haemothorax by Janik *et al.* gives an overview of the various vascular disorders that may cause aortic dissection (Fig. 25.28).[93]

The syphilitic aneurysm

Syphilitic aneurysms are now uncommon, because of the relative rarity of tertiary lesions as treatment is available for the earlier stages of the disease. In some areas of the world, however, tertiary syphilis is not the rarity it has become in Europe and America.[94]

The syphilitic aneurysm of the aorta is almost always in the thoracic segment and usually in the arch. Syphilitic aortitis, which precedes an aneurysm, may be recognized in the lining of the thoracic and abdominal aorta by its irregular corrugated pattern, though admixture with atheroma can obscure the classical appearances. There tend to be sinuous linear folds, like coarse wrinkles, which have been likened to the bark of an oak tree. If the aorta dissected free of adherent connective tissue is held up to a strong light, 'Gough's test' may be applied, in which translucent windows can be seen in the media. When confluent, these weak patches allow the internal blood pressure to blow out an aneurysm and the syphilitic bulge can be the largest of all, sometimes almost filling the upper part of the chest. The wall is thin and fragile, and there may be several separate bulges from overlapping aneurysms.

Pressure may erode bronchi, oesophagus, pulmonary vessels, lung and even the thoracic cage. The latter may allow the aneurysm to become subcutaneous and, in former years, the external bursting of a pulsating chest tumour must have been a dramatic event. The usual mode of rupture is into the pleural cavity or into the oesophagus or bronchus, giving rise to a sudden, massive haematemesis or haemoptysis. Histologically, it may be impossible to confirm syphilitic aortitis, as the reactive phase of the disease may have been long burnt out, but the gross pathological appearances are diagnostic in themselves.

Fatal aneurysms of other vessels

Fatal aneurysms of other vessels are rare, apart from the cerebral arteries. Atheromatous bulges can occur on the iliac and femoral vessels, and sometimes in the mesenteric arteries. Polyarteritis nodosa can produce minianeurysms from the inflammatory process eroding the wall, but death is not caused by the direct effects of rupture, but by vascular problems in the coronary, renal and other arteries. Infective mycotic aneurysms are rare in civilian practice, as are traumatic arteriovenous fistulae, but are not uncommon in war casualties. Ishikawa *et al.* reported a rare disease-causing mutation in the endoglin gene constituting predisposition for pulmonary arteriovenous malformations (AVM). These may spontaneously rupture causing sudden death due to massive haemothorax. According to the literature, almost half of the AVMs in the lung are seen in hereditary haemorrhagic telangiectasia-patients (Osler–Weber–Rendu syndrome).[95]

Sudden death from ruptured cerebral aneurysm

The relationship of head and neck injury to subarachnoid haemorrhage (SAH) is discussed in Chapter 5, but here we are concerned solely with spontaneous rupture of an aneurysm of the circle of Willis at the base of the brain that account for the majority of spontaneous SAHs.[96] The mechanism of rupture is not known but may be due to degeneration of the aneurysmal wall by a chronic inflammatory process that increases its susceptibility to bleeding. The overall incidence of SAH varies between 6 and 8 per 100,000 persons per year in most Western countries, with significant regional differences, e.g. the incidence in Japan and Finland is about twice as high as in other parts of the world.[97–100]

This is one of the most common causes of death in young to middle-aged adults, if coronary disease is excluded. In females, who are relatively immune from coronary occlusion up to the fifth decade of life, ruptured berry aneurysm is proportionately much more common than in males. It is a useful rule-of-thumb, when presented with the sudden death of a female of child-bearing age, to consider a complication of pregnancy, self-poisoning, pulmonary embolism and SAH as the first choices.

Subarachnoid bleeding can cause virtually instantaneous death, even though the mechanism is obscure. Numerous cases have been described where a previously fit person was seen to collapse and was apparently already dead when attended by onlookers. There must be an element of cardiac arrest in these examples, caused by the sudden bathing of the brainstem in blood from a jet of arterial blood impinging on the base of the brain (Figs 25.29, 25.30). As with coronary disease, arterial spasm has been invoked as a cause of the sudden death in ruptured berry aneurysm, without any proof. Most cases of SAH have a much longer course, with clinical symptoms and signs allowing either surgical intervention or, often, spontaneous resolution.

We are by definition here, however, concerned with sudden or rapid fatalities. In the usual coroner's case, the victim is either found dead with no available history, or has died rapidly and inexplicably or has expired after suggestive symptoms like severe headache and rapid coma. Many die after physical or emotional exertion, especially sexual intercourse or strenuous sporting



Figure 25.29 A dense basal subarachnoid haemorrhage that caused rapid death. The blood clot filling the basal cisterns conceals a ruptured berry aneurysm of the circle of Willis; at autopsy, this must be removed under a stream of water, using careful blunt dissection to avoid further damage to the vessels.



Figure 25.30 Non-ruptured intracerebral berry aneurysm of the circle of Willis treated with coiling.

activity. Those that occur during or soon after some assault or altercation are dealt with in the chapter on head injuries (Chapter 5), and can pose a major forensic problem concerning causation.



Figure 25.31 Adrenal haemorrhage occurring several days after multiple injuries sustained in a traffic accident. There was no apparent abdominal injury. The haemorrhage is fresh and occupies the medulla, with the cortex stretched around the periphery.



Figure 25.32 A large recent intracerebral haemorrhage in a person with hypertension. The bleeding has originated in the region of the external capsule from a lenticulostriate branch of the middle cerebral artery, then broken through into the posterior horn of the lateral ventricle.



Figure 25.33 A massive pontine haemorrhage in a person with hypertension. The circumstances and the irregular distribution of the bleeding within the brainstem distinguish this primary haemorrhage from the secondary lesions seen in raised intracranial pressure. Sometimes a natural intracranial haemorrhage may precipitate an accidental fall or traffic accident, however, and the resulting head injury may make it more difficult to identify the nature of the brain haemorrhage.

At autopsy, the diagnosis of SAH is self-evident. As the usual point of bleeding is in the circle of Willis, the most dense haemorrhage will be over the base of the brain, especially in the basal cisterns. The blood usually spreads laterally and may cover the whole surface of the cerebral hemispheres, the hindbrain and down into the spinal canal. This will be bright red in a fresh bleed; if survival lasts a week or so, a brownish tinge will appear as the haemoglobin undergoes changes. Haemosiderin can be detected by Perls' stain after about 3 days.[101]

The detection of the source of the haemorrhage is sometimes difficult. An aneurysm is present in about 85 per cent of spontaneous SAHs, but the remainder reveal no aneurysm, even after an exhaustive search. This may be because of destruction of a small aneurysm at the time of rupture, but it is just as likely to be a leak from a vessel without an aneurysm, as a result of the existence of a point of weakness as described below.

A relatively rare cause of bleeding, especially in children, is the presence of a vascular malformation in the arterial system, such as an angioma, an arteriovenous anastomosis or an aberrant vessel in the meninges. Post-mortem angiography may be of assistance in tracing intracranial bleeding from natural lesions, as in trauma.[102,103]

Though berry aneurysms are often called 'congenital', they are not themselves present at birth, but a defect in the wall of a cerebral artery is probably present from late fetal life. The circle of Willis condenses out of an irregular embryonic meshwork of arteries over the base of the brain by unwanted vessels undergoing atrophy. Where these redundant vessels originally joined the surviving main arteries, a 'window' in the elastic and collagenous coat is left, usually at the junction of two vessels. This window is a weak point where rising blood pressure in adult life may begin to form a 'blow-out', a thin-walled aneurysm, which may be single or multiple. At a certain stage, any sudden extra rise in blood pressure or flow rate may rip the already tense sac, and cause extravasation of blood at full arterial pressure into the subarachnoid space. Where there is no aneurysm, it must be assumed that a weak point in a vessel wall has given way *ab initio*, without the prior formation of a sac.

The search for a small aneurysm at autopsy may be difficult because of the thick layer of blood clot that is trapped in the meninges and vessels. Blunt dissection should be used, employing the handle of a scalpel or the nose of a pair of forceps. The blood should be constantly washed away in a continuous stream of water. It is possible to inject water into one of the cut ends of a vertebral artery, having carefully tied or clamped the other vessel and the two cut terminations of the carotid arteries, to see where the water leaks from. The leaks are often multiple, however, from artefactual tearing of small vessels during autopsy removal of the brain. The search for an aneurysm is best carried out on the fresh unfixed brain, as formalin fixation hardens the blood clot so much that it cannot be removed without the danger of tearing the underlying vessel and any aneurysm. It is essential to carry out blunt dissection progressively in a continuous stream of water. The most frequent site of aneurysm rupture is the anterior communicating artery followed by the posterior communicating artery, the basilar artery, and the middle cerebral artery.[104,105] An aneurysm is sometimes on the cortical aspect of the artery and may be part-buried in the cerebral surface, making it hard to find. If the swelling (which may be completely collapsed at autopsy, especially when ruptured) is not seen on superficial examination of the circle of Willis, the vessels should be gently lifted away from the brain surface with a blunt elevator so that the underside can be inspected. Sometimes a buried aneurysm will rupture mainly into the cortex, causing a lesion that may be mistaken for an intracerebral haemorrhage. Berry aneurysms are frequently multiple and of varying size, from a few millimetres to several centimetres, though the usual diameter is of the order of 3–8 mm.

Pulmonary thromboembolism

This is discussed fully in Chapter 13, but here it is sufficient to emphasize that pulmonary embolism is the most underdiagnosed cause of death (Fig. 25.34).[106,107] The figures show that less than half the deaths shown at autopsy to have been caused by a pulmonary embolism were so diagnosed by the attending clinician. Paradoxically, many other presumed deaths from this condition were found at autopsy not to have been embolic. Thus the overall statistics are not so much in error – but in relation to the wrong victims!

Pulmonary embolism is more common with advancing age, with obese subjects and in the majority of instances there is a predisposing factor such as trauma, surgical operation, confinement to bed or immobility from another cause. Even prolonged sitting can lead to deep vein thrombosis, as was seen in persons sleeping in deckchairs in air-raid shelters in the Second World War and, more recently, it has been described as a hazard of travel-related venous thrombosis, particularly long air flights, although there is still uncertainty about the magnitude of the risk.[108,109]

A significant proportion, however, estimated by the author (BK) at up to 20 per cent, occur unexpectedly in the absence of any of these usual factors, making the legal problem of causation difficult. This is especially so in criminal cases where a high standard of proof has to be attained, rather than the balance of probabilities required for a civil action.



Figure 25.34 A rare cause of pulmonary embolism. Metastasing embryonal carcinoma + seminoma of the testis (a) and thrombosis attached to the wall of inferior vena cava due to metastases of the local lymphnodes (b) and (c) pulmonary metastasis (white arrow) and massive pulmonary embolism (white x).

Sudden death in epilepsy

Individuals suffering from epilepsy have a higher mortality rate compared with the general population.[110,111] Every coroner's pathologist or the equivalent in other jurisdictions, has experience of sudden deaths in epileptics, when no morphological lesion can be found at autopsy. Epileptics can die unexpectedly without being in status epilepticus – or indeed, not even in a typical fit. It is true that many such deaths are not witnessed to prove that no such fit occurred, but sufficient evidence exists to indicate that a rapid sudden death can certainly occur.

There are, of course, many deaths in epileptics where the mode is apparent, such as asphyxia during a fit in bed when the face is pressed into the pillow, and saliva and mucus form an airtight seal against the fabric around the nose and mouth. Epileptics also drown in the bathtub and suffer other traumatic deaths because of fits occurring when they are in some vulnerable position.

These causes apart, the victim of epilepsy seems to be able to die with no apparent immediate cause and the mechanism is obscure. It has been suggested that some massive cerebral electric discharge or neuron storm occurs, leading to cardiac arrest, but this is mere hypothesis. When all investigations have been completed (including toxicological screening for antiepileptic drug overdose), after an essentially negative autopsy, then the pathologist is justified in recording 'epilepsy' as an acceptable cause of death.

The autopsy should always include a search for bites on the tip and distal sides of the tongue, which suggest a fit. A careful examination of the brain is essential, to search for any cause of post-traumatic epilepsy. In some epileptics, without coronary stenosis, patchy myocardial fibrosis has been recorded and said to be the result of episodic hypoxia from apnoea during fits.[112] Based on the observation that Purkinje cells become labelled by plasma proteins in experimental blood–brain barrier (BBB) breakdown,[113] Ikegaya *et al.* investigated immunohistochemically the presence of fibrinogen-positive Purkinje cells in 50 sudden unexpected deaths. There were 24 subjects with and 26 without known history of epilepsy.[114] Regarding >30 per cent of fibrinogen-positive Purkinje cells as diagnostic limit indicating recent major BBB breakdown, they found that 22 of the 24 cases with high percentage of fibrinogen-positive Purkinje cells had a history of epilepsy. One of the two remaining high-fibrinogen subjects had unknown



Figure 25.35 Two fibrinogen positive Purkinje cells and three negative cells in a sudden unexpected death with a history of epilepsy. (Peroxidase-DAB-immunostaining, original magnification ×20.)

leucoencephalopathy and the other had essential hypertension. Only two of the low-fibrinogen cases had a history of epilepsy. The immunopositivity of Purkinje cells is not specific for epilepsy but can occur in any conditions causing BBB breakdown, most likely due to uptake of fibrinogen from the cerebrospinal fluid irrigating the cerebellar surface. The time interval needed for the protein accumulation in man is not known. It is probable that, in addition to fibrinogen, other plasma proteins can also be used as a marker and an auxiliary method in assessing the probability of epileptic seizures contributing to the cause of death in sudden unexpected deaths (Fig. 25.35).

Sudden death in bronchial asthma

Annual worldwide deaths from asthma have been estimated at 250,000.[115] Asthma is caused by both heritable and environmental factors and an acute asthmatic attack can be triggered by many allergens, such as pollen, dust, animal products, chemicals (drugs), and infectious agents or other factors such as cold or physical exercise.[116] As in epilepsy, sufferers from bronchial asthma may die suddenly and unexpectedly, without necessarily being in status asthmaticus or even in an acute asthmatic attack. The mechanism is obscure, but experience proves that such fatalities are not uncommon. In the 1960s in Britain, Australia and New Zealand, there was a striking increase in sudden deaths in asthmatics, in Britain by 45 per cent. It was assumed to have been due to the overuse of inhalers containing bronchodilators, except that data from Australia did not fit with this hypothesis.[117–122] These adrenergic drugs, used in excess, have a direct action upon the myocardium causing tachycardia, arrhythmias and ventricular fibrillation. Awareness among prescribing doctors rapidly reduced this danger but sudden deaths still occur, even when these substances are not used to excess.

The question of sudden death in asthma was discussed in a report of 11 deaths from Norway, where seven victims were found dead with an inhaler still clutched in their hands.[123] Overdosage of the substance appears to be common. The use of theophylline derivatives combined with sympathomimetic agents tends to accentuate the cardiotoxicity of the bronchodilators. Some of the deaths appeared to be in instances where the drug had been exhausted from the inhaler, but the propellant was still active. The authors considered that a number of factors contributed to death. Hypoxia and respiratory acidosis occur in asthma and increase myocardial irritability. Drugs such as theophylline and sympathomimetic agents can provide ventricular fibrillation.

According to the recent Global Initiative for Asthma (GINA) report on the ‘Global Strategy for Asthma Management and Prevention’, there is a possible increased risk of asthma-related death associated with the use of long-acting β_2-agonists in a small group of individuals. Because of this, long-acting β_2-agonists should not be used as monotherapy in asthma but only in combination with an appropriate dose of inhaled glucocorticosteroids.[115]

At autopsy little or nothing is found, except confirmation of the chronic asthmatic state (Fig. 25.36). On opening the chest cavity, the lungs are seen to fill the thorax, not collapsing as is usual and they have a pale spongy texture, forming stable pits when pressed with the fingers. The cut surface may reveal thick-walled prominent bronchi, often plugged with thick, clear mucus. This is not an explanation for the sudden collapse and death, however, and the mechanism remains obscure.

Adrenocortical atrophy was demonstrated in two children dying in status asthmaticus, both of whom had been treated since infancy with steroidal inhalers, short courses of oral or parenteral steroids, and steroidal skin preparations.[124] In a series of 11 sudden deaths from asthma in childhood, significant growth retardation was observed in 8 of the subjects. Viral respiratory infections were common associated findings.[125]



Figure 25.36 Cross section of a bronchus in sudden asthma death showing cell-laden mucus, folding of the soft tissues of the bronchial wall, thickening of the basement membrane and hypertrophy of the muscle. (H&E, original magnification ×10.)

Respiratory obstruction

Mechanical obstruction by foreign bodies is dealt with in Chapter 14, but some rapid – if not actually sudden – deaths can be due to fulminating natural disease.

Rupture of a retropharyngeal abscess ('quinsy'), when pus and necrotic material pour into the pharynx and larynx, is now a rare cause.[126,127] Diphtheria is also virtually unknown in advanced countries (five fatalities were reported in the UK between 1986 and 2008, all in unvaccinated patients), so that the toxaemia, a fatal myocarditis and the possibility of laryngeal obstruction from a detached pharyngeal membrane are rarely considered by most doctors.[128]

The fulminating epiglottitis caused by *Haemophilus influenzae* in children is a serious, potentially life-threatening condition. This is a major paediatric emergency and a paediatrician and anaesthetist should see any child with stridor of recent onset urgently. The gross infective oedema of the laryngeal entrance can lead to death within hours of onset of the illness, and may require rapid intubation or tracheostomy to save life. Since the introduction of the *Haemophilus influenzae* (Hib) conjugate vaccine in the UK in October 1992, there has been a dramatic reduction in the incidence of this infection.[129] In a retrospective review of 40 children presenting with epiglottitis to Alder Hey Hospital between December 1987 and January 2001, eight (20 per cent) presented after the introduction of the Hib conjugate vaccine. *H. influenzae* was isolated from blood cultures in 28 cases (70 per cent). In 12 of these children, *H. influenzae* type b was identified, seven prior to 1993 and five thereafter. Four of these five subjects presenting after introduction of the Hib vaccine were known to have been fully vaccinated. There were no deaths or any long-term sequelae.[130]

Haemoptysis

Now that pulmonary tuberculosis is less common and treatable in advanced countries, deaths from haemoptysis are rare, as most massive respiratory haemorrhages were from this cause. However, warning signals are now evident about a revival of tuberculosis, even in 'advanced' countries. Part of the return of this scourge is due to opportunist infection in human immunodeficiency virus (HIV)-infected persons, but aquired immunodeficiency syndrome (AIDS) apart, pulmonary tuberculosis seems to be on the march again, with worrying concerns about increasing resistance to the drugs, which revolutionized its treatment decades ago.[131]

Bronchial tumours rarely cause fatal haemoptyses, unless a large vessel is eroded; syphilitic aortitis perforating the aorta or other large vessel is now almost a matter of history.

The bleeding rarely causes death from exsanguination except where the aorta is eroded, but smaller bleeds may fill the air passages, and cause an asphyxial-type death or a 'vagal inhibition'-type death from sudden flooding of the larynx.

Gastrointestinal haemorrhage

Bleeding may take place at any point along the alimentary tract and though modern transfusion and resuscitatory methods make deaths unusual these days, some are seen in medico-legal practice when people living alone or otherwise remote from assistance, die without any medical intervention.

Bleeding from surgical operations in the mouth or pharynx, such as tooth extraction or tonsillectomy, rarely causes death, but can occasionally do so from blood and clot blocking the airways. In the oesophagus, a penetrating carcinoma may erode the aorta or other great vessel in the mediastinum, but the most frequent sources of bleeding are varices at the lower end, caused by the portal hypertension associated with hepatic fibrosis. It is often difficult to identify the varices at autopsy, as they have collapsed, but the absence of gastric or duodenal ulceration, and the congested, bluish vessels around the cardia often give away the lesion, especially in the presence of liver cirrhosis and splenomegaly.



Figure 25.37 Massive lethal bleeding from eroded vessels of a gastric ulcer.



Figure 25.38 Great distension of colon due to volvulus of sigmoid colon. Deceased found dead with history of abdominal pain.

Other causes of massive gastrointestinal bleeding are gastric and duodenal peptic ulcers, which can erode large vessels in their base. Acute erosions, though shallow, can produce considerable blood in the stomach and may require surgical resection. They are rarely the cause of lethal bleeding (Fig. 25.37).

Carcinoma of the stomach can reach a large size and the crater variety may perforate a major vessel to produce severe haemorrhage. Bleeding from the small intestine is rare, except in certain haemorrhagic diatheses. More common is bleeding from colonic lesions, such as carcinomas and ulcerative colitis. Polyps, sometimes malignant, may also give rise to melaena and even massive bleeding per rectum, though these are now rarely fatal unless medical intervention is delayed or absent.

Fatal abdominal catastrophes

Though usually surgical emergencies, some abdominal conditions go untreated because the victim is either a solitary person living alone with no opportunity to call for help, or declines to seek medical assistance. They may well be found dead with no history to suggest a cause of death.

Mesenteric thrombosis and infarction is one such condition. The thrombosis may in fact be an embolus, rather than a thrombosis *in situ*, the most common cause of both being atherosclerosis of the aorta and its mesenteric branches. The length of small intestine supplied by the vessel becomes dark and necrotic, and may involve almost the whole length of the jejunum and ileum. Even if precipitated by an embolus, much of the rest of the arterial system may then thrombose and, on cutting into the mesentery at autopsy, the cut ends of arteries may show plugs of firm ante-mortem thrombus. The gut will be blue–red or even almost black, with loss of the serosal lustre and a friable necrotic wall.

Strangulated intestine is yet another condition that may present as sudden or rapid death, where medical attention is lacking, and even sometimes when it is negligently offered (Fig. 25.38).

Hernias, both femoral and inguinal, and internal strangulation beneath fibrous bands in the peritoneal cavity, may all twist the intestine so that its blood supply is cut off, with subsequent necrosis. The gut above may develop ileus and become paralysed and dilated.

Caution is needed at autopsy to differentiate the dark red colour of loops of intestine due to post-mortem hypostasis from true infarction. Hypostasis is seen to be interrupted when the gut is stretched out, due to alternate dependent loops, whereas real necrosis is usually continuous and the serosa is dull and friable.

Fulminating peritonitis may be seen in a variety of causes, again leading to death if undiagnosed or untreated. Death from acute appendicitis and appendix abscess is now uncommon, but perforation of the colon through a diverticulum, whether inflamed or merely distended and eroded by faecoliths, is common.

Tearing of the senile gut where it is adherent to other structures, such as uterus or tube, can also lead to peritonitis, and a carcinoma (often difficult to differentiate macroscopically from chronic diverticulitis) may also lead to perforation with loss of intestinal contents into the peritoneum.

A perforated peptic ulcer, usually duodenal, leads to a chemical peritonitis. The autopsy appearances are straightforward, turbid fluid being found in the peritoneal cavity, which may show early inflammatory changes if the perforation occurred many hours previously. The perforation is most commonly found on the posterior surface of the duodenum.

Genitourinary system

There is very little in the urinary system that can give rise to a sudden or rapid death, but the female genital organs certainly make up for this. Complications of pregnancy are discussed elsewhere (Chapter 19), but it should be repeated here that ectopic pregnancy, usually in the tubes, can rupture with massive intraperitoneal haemorrhage. Induced abortions, unless under reputable medical control, are another source of death from haemorrhage, air embolism, perforation of vagina or uterus, infection and the use of toxic substances.

The relationship between trauma and disease

One of the most difficult problems in forensic medicine occurs when a death takes place in a person who has suffered trauma but who has either pre-existing natural disease or where some apparently natural disease has supervened after the trauma. The relative contributions of trauma and disease may then become an acute medico-legal problem (Fig. 25.31).

For example, the author (BK) conducted an autopsy on an elderly male of 82 years, previously in excellent health, who had been tied up and slightly injured by robbers of a sub-post office. Within 2 hours of release from his bonds the old gentleman became ill and then hemiplegic, dying of a massive cerebral haemorrhage shortly afterwards. The attackers were charged with homicide, in addition to robbery, but that charge was rejected by magistrates on the grounds that a cerebral haemorrhage could be a natural disease, unrelated to the assault. The prosecution obtained a private Bill of Indictment to circumvent the magistrates, and at the Crown Court the accused were convicted of manslaughter on the grounds that the physical and emotional stress of being assaulted and tied up probably (beyond reasonable doubt) led to an elevation of blood pressure that precipitated a cerebral haemorrhage in a previously fit person, within such a short time span.

This marginal case illustrates the problems that can occur when trauma and natural disease coexist in the same person. A common dilemma exists in relation to SAH from a ruptured berry aneurysm when there has been a head injury.

In autopsies when an injury has been sustained by a person with substantial natural disease, the following problems must be addressed:

- whether death was caused entirely by the disease and would have occurred irrespective of the injury
- whether death was caused entirely by the injury and would have occurred whether or not the disease was present
- whether the death was caused by a combination of these two processes.

In practical terms, the most common situations involve coronary artery disease, pulmonary embolism and SAH.

Coronary atherosclerosis

The disease has invariably been present for months or probably years before the traumatic episode, and it is therefore indisputably obvious that the trauma can have no relationship to the genesis of the disease – though relatives and some lawyers are often hard to convince on this point. Furthermore, unless there was a direct blow onto the front of the thorax, which could physically have damaged the heart surface and caused a direct traumatic lesion of the coronary system (by dislodging an atheromatous plaque – but see end of this section – causing a subintimal haemorrhage or precipitating a coronary thrombosis, a rare event), there is no way in which the injury can be accused of worsening the state of the coronary arteries. If the state of the coronary system was already poor, thus it could justifiably be claimed by the defence that death could have occurred at any time. The standard of proof in criminal cases is high and must be proved 'beyond reasonable doubt', whereas in civil disputes, only 'the balance of probabilities' must be attained.

As opposed to showing that the trauma directly worsened the physical state of the coronary vessels, it is easier to claim that the physical and emotional stress associated with the traumatic event caused increased demands upon a weakened heart and caused it to fail.

The adrenal response of 'fight or flight' may be invoked, it being accepted that released endogenous catecholamines such as noradrenaline can send a chronically hypoxic heart into ventricular fibrillation and arrest. There may even be morphological evidence in some cases, by the finding of contraction bands in the cardiac myofibrils, especially in the superficial subepicardial layers.

It is often an assessment of the circumstances, in addition to the autopsy findings, that decides a court's attitude to the relationship of trauma to disease.

Where a male who has had no previous cardiac symptoms drops dead immediately after some assault or strenuous activity, the court is more likely to assume an association than with some cardiac cripple, who has been hovering on the brink of heart dysfunction for a long time before the traumatic event.

The average jury is likely to decide that it would be too much of a coincidence for an assault to cause a male to drop dead on the spot, even if it was shown that his coronary artery stenosis had been there for several years. Much depends upon the individual circumstances, especially where there is only a short interval between the traumatic episode and death.

The strict test is: 'Would he have died when he did die if the assault had not taken place?' This is often unanswerable on medical grounds, but the court is entitled to take a common-sense view of coincidence in terms of immediacy in time and apply the 'beyond reasonable doubt' test to it.

The fact that a person is in a parlous state of health and might die from relatively minimal trauma is no defence in law, which states that 'an assailant must take his victims as he finds them'. In other words, it is immaterial whether the attacker knows that his victim is ill or not – if death results from an illegal act against him, the charge of homicide may stand. This dictum is not adhered to slavishly by public prosecutors, however, as it is a matter of practical politics whether a criminal prosecution can be maintained with any chance of success (using public funds), against an energetic defence that can show medically that the victim had such a degree of natural disease that he might have dropped dead spontaneously at any time. The prevalence of coronary disease is so widespread that a close association in time must be shown before any causal connection can be accepted. The actual death itself need not occur very soon after the assault, however, if it can be established that the latter could have precipitated an infarct in a myocardium already compromised by coronary stenosis. It is not only a blow or some physical trauma that may precipitate a MI or arrhythmia; as stated above, even the emotional upset that accompanies injury, or even the threat or fear of an injury, can lead to death. The blow may never actually be struck or it may fail to land, yet the threatened person may suffer a transient hypertension or tachycardia that may precipitate a subintimal haemorrhage, arrhythmia, or cerebral or subarachnoid haemorrhage that leads to death. Such an event, however, with little or no morphological evidence to be presented as evidence, has a poor chance of acceptance in court unless the circumstances are clear-cut. These cases pose a problem for police and pathologist, in that it may be difficult to decide whether to arrest and charge the potential culprit with a criminal offence.

A typical case was once seen by the author (BK) in which an elderly male was involved in an altercation with another, concerning parking a car. There was a scuffle, in which only trivial blows were exchanged, but one participant immediately developed chest pain and breathlessness, and soon died. The other was arrested, but as autopsy showed marked cardiac enlargement, extensive myocardial fibrosis and gross occlusive coronary atherosclerosis, the prosecution decided to offer no evidence and the charge was dropped, even though the answer to the 'acid test' of whether the victim would have been likely to die at that particular time had the altercation not taken place was probably in the negative.

In civil matters, considerable sums of money may hang upon such decisions by way of damages and insurance payments. Here the standard of proof is much lower, as the plaintiff only has to show that there was a 51 per cent or better chance of the association being present, rather than the much higher standard of criminal liability.

An actual example of the civil problems was a workman who was removing a truck wheel from his employer's vehicle with a wheelbrace. Under full pressure, the threaded stud in the hub suddenly snapped and he was thrown to the ground under the force of his own muscular effort. He was shocked and soon developed chest pain and died the next day. Autopsy revealed no fresh infarct, but there was longstanding left ventricular hypertrophy, myocardial fibrosis and stenosing coronary atheroma. The employer's liability was disputed, but eventually a compromise settlement was reached.

Recent very careful and statistically meticulous research on large cohorts, both in the USA and Germany, have shown an indisputable relationship between exertion and sudden cardiac death. Mittleman *et al.* investigated 1228 patients with acute MIs and showed that there was a sixfold increase in the incidence of infarction during or within 1 hour of heavy physical exertion, such as snow shovelling, jogging or sexual activity.[132] In Germany, Willich *et al.* researched 1194 patients with the same condition and showed a twofold increase in risk.[133] Both surveys showed that the risk was greater in those who were otherwise sedentary and that long-term moderate exercise was undoubtedly associated with a reduced risk of infarction.[134]

Several mechanisms were proposed for the increased risk during sudden severe exertion, including the splitting and dislodgement of an atheromatous plaque. It was also claimed that increased platelet activation occurred in sedentary people who suddenly exerted themselves. In an earlier publication, Siscovick *et al.* showed the same trend in primary cardiac arrest, exertion in otherwise sedentary persons increasing the risk, while habitual exercise protected.[135]

Subarachnoid haemorrhage

Subarachnoid haemorrhage is another difficult area in which trauma and natural disease interact. When a berry aneurysm on the cerebral arteries ruptures, the allegation is often made that some traumatic occurrence precipitated that event. The matter is discussed in Chapter 5, but to recapitulate here, the problem is to decide whether the trauma itself was a mechanical factor in causing the arterial blister to burst.

A rupture is a relatively common event without external trauma, this cause of death being well-known in young to middle-aged persons who are not indulging in any strenuous activity whatsoever. It is known to occur, however, during innocent activities, such as jogging, intercourse and sporting exertion, probably because of a transient rise in blood pressure and pulse rate. Once again, a potent element may be in the adrenal response, catecholamines pushing up the blood pressure. Thus when a ruptured aneurysm occurs during or shortly after a fight or altercation, it is arguable whether a mechanical blow to the head or merely the emotional stress of a dispute is the most potent factor in causing rupture. There has been much medical argument about the role of trauma in causing the rupture, as many would maintain that the aneurysm is so deep-seated within the skull that internal pressure from hypertension is far more likely to be the reason.

Certainly, where a small aneurysm a few millimetres in size breaks, it is difficult to accept that a blow could have caused a tear, but in the more exceptional cases of a large tissue-thin globule, then it is easier to accept that intracranial stresses may have played a significant part. The role of alcoholic intoxication – another hotly disputed aspect – has been discussed in Chapter 5. The legal problem is similar in berry aneurysm deaths to that in coronary disease. The time interval is naturally important, though in most instances, bleeding occurs immediately or soon afterwards.

Autopsy is not all that helpful in assessing the relative contribution of assault versus pre-existing disease. Unless the aneurysm is found to be large and fragile, the morphological findings are mainly of use in confirming the diagnosis, evaluating any injuries and excluding any other contributory disease. It used to be the usual practice in England and Wales not to prosecute assailants when an aneurysm was demonstrated at autopsy, though in Scotland and on the continent of Europe no such reluctance was evident. Following a case in Gibraltar in 1978, however, in which a British sailor was convicted of homicide after kicking another in a drunken brawl, the latter eventually dying of SAH from a ruptured aneurysm, such charges are now usually brought.[136]

Pulmonary embolism

The other major example of the interaction of trauma and natural disease is pulmonary embolism. This is discussed in Chapter 13, but is so important in medico-legal casework that the forensic aspects may be repeated here with advantage.

Deep vein thrombosis (DVT), almost always in the leg veins, is a common sequel to injury and consequent immobility. Virchow's triad of slowing of the circulation, local injury to vessel walls and increase in blood coagulability are the major factors, though DVT can occur in the absence of all three. When the leg is the site of the injury, it is more likely to occur in the ipsilateral limb, though it can occur contralaterally or bilaterally. The fact that a fatal embolus came from the contralateral limb when the other leg has been injured by no means rules out a causative element.

Pulmonary embolism typically occurs about 2 weeks after an injury or surgical operation, but the range of time during which a cause-and-effect mechanism operates can be anything from about 2 to 90 days. It becomes progressively more difficult to maintain a causative relationship, however, when the interval exceeds a few weeks.

Forensically, it is vital to show that the DVT post-dated the traumatic event, if an association is to be established. If a person suffers a fatal embolism a week after injury, yet histologically the DVT appears to be several weeks old, then obviously the injury could not have initiated the process. The embolus may, however, be much younger than the most distal part of the leg vein thrombosis (which may be as far down as the foot) as progressive proximal extension of a DVT undoubtedly occurs. It could still be argued, therefore, that although the original thrombosis ante-dated the injury, the latter encouraged extension and hence the eventual breaking off of an embolus. The case becomes weaker, however, than if the whole process was entirely subsequent to the traumatic event.

Histological dating of the embolus should always be undertaken, though it is less rewarding and more difficult than that of the leg vein thrombi, which must always be taken for microscopy with the vein wall intact. It is the thrombomural junction that gives the most information about the age of any thrombus. Thrombosis of the deep leg veins is far more common than pulmonary thromboembolism. In 100 consecutive coroner's autopsies, Knight and Zaini found 32 instances of DVT, but only 10 had pulmonary emboli, not all fatal.[137]

The legal problem, outlined in Chapter 13, is that though trauma, surgery and immobility are potent factors in the development of DVT, the latter condition frequently occurs in the absence of all three. Thus it is difficult to maintain that any traumatic event was the cause of a subsequent fatal pulmonary embolism, as many fatal emboli occur in the absence of trauma. In a series of coroner's and hospital autopsies, 25 per cent of fatal pulmonary emboli came 'out of the blue' in ambulant people who had no previous history of trauma or surgical operation.[137] Later, Knight and Zaini studied 38,000 autopsy reports and found that 10 per cent of deaths due to pulmonary embolism had no history of any predisposing factors.[138] The discrepancy in these proportions is caused by the variable standard of history reports and also by marked alterations in pathologist's reporting habits over the years – in fact, in the large series mentioned above, there was not a single fatal pulmonary embolism recorded in the 20 years from 1908 until 1928!

Even disregarding the dubious statistical value of such investigations, there can be no doubt that a significant proportion of fatal pulmonary emboli cannot be related to previous trauma. This provides a line of defence in those cases where the prosecution allege that a 'cause-and-effect' relationship exists between some criminal assault and death. It becomes a matter of law for the judge to decide whether he will let the issue go to the jury, and a matter of fact for the jury to decide whether this relationship can be 'beyond reasonable doubt' in circumstances where even conservatively, at least 10 per cent of pulmonary emboli are not related to trauma. Several court cases are within the author's (BK) experience in which quite different verdicts have been reached on essentially identical pathological evidence.

In civil cases, usually related to road traffic accidents or industrial personal injuries, the burden on the plaintiff is much lighter, as the 'balance of probabilities' test can be much more readily satisfied.

References

1 Goldstein S. The necessity of a uniform definition of sudden coronary death: witnessed death within 1 hour of the onset of acute symptoms. *Am Heart J* 1982;103(1):156–9.

2 Smith J. *The Shipman Inquiry, First Report*. 2002, p. 336.

3 *Coroners Statistics 2012 England and Wales*. London: Ministry of Justice, 2012, p. 40.

4 Moritz AR. Medical investigation of obscure and suspicious deaths in the interest of public safety. *Northwest Med* 1947; 46(11):Unknown.

5 Knight B. The obscure autopsy. *Forensic Sci Int* 1980;16(3): 237–40.

6 Cordner SM. Deciding the cause of death after necropsy. *Lancet* 1993;341(8858):1458–60.

7 Pollanen MS. Deciding the cause of death after autopsy – revisited. *J Clin Forensic Med* 2005;12(3):113–21.

8 Hodgson JA. *Treatise on the Diseases of arteries and Veins, Containing the Pathology and Treatment of Aneurisms and Wounded Arteries*. London:T Underwood, 1815.

9 Fye WB. A historical perspective on atherosclerosis and coronary artery disease. In: Fuster V, Topol EJ, Nabel EG (eds). *Atherothrombosis and Coronary Artery Disease*. Philadelphia: Lippincott Williams & Wilkins, 2005, pp. 1–14.

10 von Rokitansky C. *A Manual of Pathological Anatomy*. London: Sydenham Society, 1852, Vol. 4.

11 Virchow R. *Phlogose und Thrombose im Gefäßsystem*. Gesammelte Abhandlungen zur wissenschaftlichen Medicin. Frankfurt: Meidinger Sohn, 1856.

12 Osler W. Diseases of the arteries. In: Osler W (ed). *Modern Medicine: its Practice and Theory*. Philadelphia: Lea and Febiger, 1908, pp. 429–47.

13 Fuster V, *et al*. The pathogenesis of coronary artery disease and the acute coronary syndromes (1). *N Engl J Med* 1992;326(4):242–50.

14 Fuster V, *et al*. The pathogenesis of coronary artery disease and the acute coronary syndromes (2). *N Engl J Med* 1992; 326(5):310–18.

15 Kaperonis EA, *et al*. Inflammation and atherosclerosis. *Eur J Vasc Endovasc Surg* 2006;31(4):386–93.

16 Mahmoudi M, Curzen N, Gallagher PJ. Atherogenesis: the role of inflammation and infection. *Histopathology* 2007;50(5):535–46.

17 Stary HC. Natural history and histological classification of atherosclerotic lesions: an update. *Arterioscler Thromb Vasc Biol* 2000;20(5):1177–8.

18 Patterson JC. Capillary rupture with intimal haemorrhage as a causative factor in coronary thrombosis. *Arch Pathol* 1938; 25:474–87.

19 Wartmann WB. Occlusion of the coronary arteries by haemorrhage into their walls. *Am Heart J* 1938;15:459–66.

20 English JP, Williams FA. Haemorrhagic lesions of the coronary arteries. *Arch Intern Med* 1943;71:594–602.

21 Davies MJ, Pomerance A. *The Pathology of the Heart*. Oxford: Blackwell Scientific Publications, 1975.

22 Drury RA. The role of intimal haemorrhage in coronary occlusion. *J Pathol Bacteriol* 1954;67:207–15.

23 Myocardial infarction redefined – a consensus document of The Joint European Society of Cardiology/American College of Cardiology Committee for the redefinition of myocardial infarction. *Eur Heart J* 2000;21(18):1502–13.

24 Baroldi G, *et al*. Coronary occlusion: cause or consequence of acute myocardial infarction? *Clin Cardiol* 1990;13(1):49–54.

25 Wartmann WB, Hellerstein HK. The incidence of heart disease in 2000 consecutive autopsies. *Ann Intern Med* 1948;28:41–50.
26 Cushing EH. Infarction of the cardiac auricles. *Br Heart J* 1942;4:17–26.
27 Wartmann WB, Souders JC. Localisation of myocardial infarction with respect to the muscle bundles of the heart. *Arch Pathol* 1950;50:329–38.
28 Jackowski C, *et al.* Postmortem unenhanced magnetic resonance imaging of myocardial infarction in correlation to histological infarction age characterization. *Eur Heart J* 2006;27(20): 2459–67.
29 Jackowski C, *et al.* Magnetic resonance imaging goes postmortem: noninvasive detection and assessment of myocardial infarction by postmortem MRI. *Eur Radiol* 2011; 21(1):70–8.
30 Jackowski C, *et al.* Post-mortem cardiac 3-T magnetic resonance imaging: visualization of sudden cardiac death? *J Am Coll Cardiol* 2013;62(7):617–29.
31 Linzbach AJ, Linzbach M. [Cardiac dilatation]. *Klin Wochenschr* 1951;29(37–38):621–30.
32 Hort W. [Ventricular dilatation and muscle fiber extension as the earliest morphological finding in heart infarct]. *Virchows Arch Pathol Anat Physiol Klin Med* 1965;339:72–82.
33 Smith AJ. On the histological behaviour of the cardiac muscle in two examples of organization of myocardial infarct. *Univ Pennsylv Med Bull* 1904–05;17:227–34.
34 Baroldi G, *et al.* Myocardial contraction bands. Definition, quantification and significance in forensic pathology. *Int J Legal Med* 2001;115(3):142–51.
35 Karch SB, Billingham ME. The pathology and etiology of cocaine-induced heart disease. *Arch Pathol Lab Med* 1988; 112(3):225–30.
36 Arnold G, Fischer R. Myocardial ‘contraction bands’. *Hum Pathol* 1987;18(1):99–101.
37 Karch SB, Billingham ME. Myocardial contraction bands revisited. *Hum Pathol* 1986;17(1):9–13.
38 Rossi L, Matturri L. [Contraction bands in myocardial infarct: a histopathologic-clinical problem revisited]. *G Ital Cardiol* 1985;15(4):359–64.
39 Rajs J, Falconer B. Cardiac lesions in intravenous drug addicts. *Forensic Sci Int* 1979;13(3):193–209.
40 Falk E, Simonsen J. The histology of myocardium in malignant hyperthermia: a preliminary report of 11 cases. *Forensic Sci Int* 1979;13(3):211–20.
41 Fenoglio JJ, Jr, Irey NS. Myocardial changes in malignant hyperthermia. *Am J Pathol* 1977;89(1):51–8.
42 Martin AM, Jr, Hackel DB. An electron microscopic study of the progression of myocardial lesions in the dog after hemorrhagic shock. *Lab Invest* 1966;15(1 Pt 2):243–60.
43 Martin AM, Jr, *et al.* Mechanisms in the development of myocardial lesions in hemorrhagic shock. *Ann N Y Acad Sci* 1969;156(1):79–90.
44 Stamer A. Untersuchungen über die fragmentation und segmentation des herzmuskels. *Beitr Pathol* 1907;42:310–53.
45 Glogner, cited by Stamer (1907). *Virchows Arch Pathol Anat* 1903;171.
46 Saukko P. Evaluation of diagnostic methods for early myocardial injury in sudden cardiac deaths. *Acta Univ Oul*, 1983;D107; *Anat Pathol Microbiol* 17.
47 Edston E. Evaluation of agonal artifacts in the myocardium using a combination of histological stains and immunohistochemistry. *Am J Forensic Med Pathol* 1997;18(2):163–7.
48 Knight B. A further evaluation of the reliability of the HBFP stain in demonstrating myocardial damage. *Forensic Sci Int* 1979;13(3):179–81.
49 Leadbeatter S, Wawman HM, Jasani B. Further evaluation of immunocytochemical staining in the diagnosis of early myocardial ischaemic/hypoxic damage. Forensic Sci Int 1990; 45(1–2):135–41.
50 Carle BN. Autofluorescence in the identification of myocardial infarcts. *Hum Pathol* 1981;12(7):643–6.
51 Badir B, Knight B. Fluorescence microscopy in the detection of early myocardial infarction. *Forensic Sci Int* 1987;34(1–2):99–102.
52 Saukko P, Knight B. Evaluation of eosin-fluorescence in the diagnosis of sudden cardiac death. *Forensic Sci Int* 1989;40(3):285–90.
53 Rutenburg AM, Wolman M, Seligman AM. Comparative distribution of succinic dehydrogenase in six mammals and modification in the histochemical technic. *J Histochem Cytochem* 1953;1:66–81.
54 Hiltunen JK, Saukko P, Hirvonen J. Correlations between enzyme histochemical reactions and respective enzyme activities in global ischaemic rat hearts. *Br J Exp Pathol* 1985;66(6):743–52.
55 Saukko PJ, Pollak S. Histology. In: Jamieson A, Moenssens A (eds). *Wiley Encyclopedia of Forensic Science*. Chichester: John Wiley, 2009, pp. 1468–73.
56 Linzbach AJ, Akuamoa-Boateng E. [Changes in the aging human heart. I. Heart weight in the aged]. *Klin Wochenschr* 1973;51(4):156–63.
57 El-Maraghi NR, Sealey BJ. Recurrent myocardial infarction in a young man due to coronary arterial spasm demonstrated at autopsy. *Circulation* 1980;61(1):199–7.
58 Roberts WC, *et al.* Sudden death in Prinzmetal’s angina with coronary spasm documented by angiography. Analysis of three necropsy patients. *Am J Cardiol* 1982;50(1):203–10.
59 Svendsen E, Tindall AR. The internal elastic membrane and intimal folds in arteries: important but neglected structures? *Acta Physiol Scand Suppl* 1988;572:1–71.
60 Mortensen ES, *et al.* Evidence at autopsy of spasm in the distal right coronary artery in persons with coronary heart disease dying suddenly. *Cardiovasc Pathol* 2007;16(6):336–43.
61 Factor SM, Cho S. Smooth muscle contraction bands in the media of coronary arteries: a postmortem marker of antemortem coronary spasm? *J Am Coll Cardiol* 1985;6(6):1329–37.
62 Linzbach AJ. Herzhypertrophie und kritisches herzgewicht. *Klin Wochenschr* 1948;26(29–30):459–63.
63 Song Y, *et al.* A modified method for examining the cardiac conduction system. *Forensic Sci Int* 1997;86(1–2):135–8.
64 Song Y, *et al.* Age-related variation in the interstitial tissues of the cardiac conduction system; and autopsy study of 230 Han Chinese. *Forensic Sci Int* 1999;104(2–3):133–42.
65 Song Y, *et al.* Histopathological findings of cardiac conduction system of 150 Finns. *Forensic Sci Int* 2001;119(3):310–7.
66 James TN. Long reflections on the QT interval: the sixth annual Gordon K. Moe Lecture. *J Cardiovasc Electrophysiol* 1996;7(8):738–59.
67 James TN. Congenital disorders of cardiac rhythm and conduction. *J Cardiovasc Electrophysiol* 1993;4(6):702–18.
68 James TN. Normal and abnormal consequences of apoptosis in the human heart. From postnatal morphogenesis to paroxysmal arrhythmias. *Circulation* 1994;90(1):556–73.
69 Bikkina M, Larson MG, Levy D. Asymptomatic ventricular arrhythmias and mortality risk in subjects with left ventricular hypertrophy. *J Am Coll Cardiol* 1993;22(4):1111–6.

70 Linzbach AJ. [The muscle fiber constant and the law of growth of the human ventricles]. *Virchows Arch* 1950;318(5): 575–618.

71 Knight B. The myocardium in sudden death from hypertensive heart disease or aortic stenosis. *Med Sci Law* 1973;13(4):280–4.

72 Farrer Brown G. Nornal and diseased vascular pattern of myocardium of human heart. I. Normal pattern in the left ventricular free wall. *Br Heart J* 1968;30(4):527–36.

73 Farrer-Brown G. *A Colour Atlas of Cardiac Pathology.* London: Wolfe Medical Publications, 1977.

74 Catellier MJ, *et al.* Cardiac pathology in 470 consecutive forensic autopsies. *J Forensic Sci* 1990;35(5):1042–54.

75 Pounder DJ. Floppy aortic valve presenting as sudden death. *Forensic Sci Int* 1984;25(2):123–31.

76 Richardson P, *et al.* Report of the 1995 World Health Organization/International Society and Federation of Cardiology Task Force on the definition and classification of cardiomyopathies. *Circulation* 1996;93(5):841–2.

77 Teare D. Asymmetrical hypertrophy of the heart in young adults. *Br Heart J* 1958;20:1–8.

78 Saphir O. Myocarditis: general review with analysis of 240 cases. *Arch Pathol* 1942;33:88–99.

79 Stevens PJ, Ground KE. Occurrence and significance of myocarditis in trauma. *Aerosp Med* 1970;41(7):776–80.

80 Tonge JI, *et al.* Traffic crash fatalities. Injury patterns and other factors. *Med J Aust* 1972;2(1):5–17.

81 Tonge JI, *et al.* Traffic-crash fatalities (1968–73): injury patterns and other factors. *Med Sci Law* 1977;17(1):9–24.

82 Aretz HT. Myocarditis: the Dallas criteria. *Hum Pathol* 1987; 18(6):619–24.

83 Aretz HT, *et al.* Myocarditis. A histopathologic definition and classification. *Am J Cardiovasc Pathol* 1987;1(1):3–14.

84 Feldman AM, McNamara D. Myocarditis. *N Engl J Med* 2000; 343(19):1388–98.

85 Kytö V, *et al.* Diagnosis and presentation of fatal myocarditis. *Hum Pathol* 2005;36(9):1003–7.

86 Kytö V, *et al.* Incidence of fatal myocarditis: a population-based study in Finland. Am *J Epidemiol* 2007;165(5):570–4.

87 Kytö V, *et al.* Cytomegalovirus infection of the heart is common in patients with fatal myocarditis. *Clin Infect Dis* 2005;40(5): 683–8.

88 Ferris JA, Rice J. Drug-induced myocarditis: a report of two cases. *Forensic Sci Int* 1979;13(3):261–5.

89 Haas SJ, *et al.* Clozapine-associated myocarditis: a review of 116 cases of suspected myocarditis associated with the use of clozapine in Australia during 1993–2003. *Drug Saf* 2007; 30(1):47–57.

90 Fleming HA. Death from sarcoid heart disease: United Kingdom series 1971-1986, 300 cases with 138 deaths. In: Grassi C (ed). *Sarcoidosis and other Granulomatous Disorders.* Amsterdam: Excerpta Medica, 1988, pp. 19–33.

91 Moll FL, *et al.* Management of abdominal aortic aneurysms clinical practice guidelines of the European society for vascular surgery. *Eur J Vasc Endovasc Surg* 2011;41 Suppl 1:S1–S58.

92 Hagan PG, *et al.* The International Registry of Acute Aortic Dissection (IRAD): new insights into an old disease. *JAMA* 2000;283(7):897–903.

93 Janik M, *et al.* Non-traumatic and spontaneous hemothorax in the setting of forensic medical examination: a systematic literature survey. *Forensic Sci Int* 2014;236:22–9.

94 Tavora F, Burke A. Review of isolated ascending aortitis: differential diagnosis, including syphilitic, Takayasu's and giant cell aortitis. *Pathology* 2006;38(4):302–8.

95 Ishikawa T, *et al.* Pulmonary arteriovenous malformation causing sudden death due to spontaneous hemothorax. *Int J Legal Med* 2010;124(5):459–65.

96 Zacharia BE, *et al.* Epidemiology of aneurysmal subarachnoid hemorrhage. *Neurosurg Clin N Am* 2010;21(2):221–33.

97 Sarti C, *et al.* Epidemiology of subarachnoid hemorrhage in Finland from 1983 to 1985. *Stroke* 1991;22(7):848–53.

98 Broderick JP, *et al.* Intracerebral hemorrhage more than twice as common as subarachnoid hemorrhage. *J Neurosurg* 1993;78(2):188–91.

99 Linn FH, *et al.* Incidence of subarachnoid hemorrhage: role of region, year, and rate of computed tomography: a meta-analysis. *Stroke* 1996;27(4):625–9.

100 de Rooij NK, *et al.* Incidence of subarachnoid haemorrhage: a systematic review with emphasis on region, age, gender and time trends. *J Neurol Neurosurg Psychiatry* 2007;78(12):1365–72.

101 Perls M. Nachweis von eisenoxyd in gewissen pigmenten. *Virchows Arch Pathol Anat* 1867;39(1):42–8.

102 Karhunen PJ, Servo A. Sudden fatal or non-operable bleeding from ruptured intracranial aneurysm. Evaluation by post-mortem angiography with vulcanising contrast medium. *Int J Legal Med* 1993;106(2):55–9.

103 Ehrlich E, Farr T, Maxeiner H. Detection of arterial bleeding points in basilar subarachnoid hemorrhage by postmortem angiography. *Leg Med (Tokyo)* 2008;10(4):171–6.

104 Forget TR, Jr, *et al.* A review of size and location of ruptured intracranial aneurysms. *Neurosurgery* 2001;49(6):1322–5; discussion 1325–6.

105 Molyneux A, *et al.* International Subarachnoid Aneurysm Trial (ISAT) of neurosurgical clipping versus endovascular coiling in 2143 patients with ruptured intracranial aneurysms: a randomised trial. *Lancet* 2002;360(9342):1267–74.

106 Cameron HM, McGoogan E. A prospective study of 1152 hospital autopsies: I. Inaccuracies in death certification. *J Pathol* 1981;133(4):273–83.

107 Stein PD, Matta F. Acute pulmonary embolism. *Curr Probl Cardiol* 2010;35(7):314–76.

108 Philbrick JT, *et al.* Air travel and venous thromboembolism: a systematic review. *J Gen Intern Med* 2007;22(1):107–14.

109 Schobersberger W, Schobersberger B, Partsch H. Travel-related thromboembolism: mechanisms and avoidance. *Expert Rev Cardiovasc Ther* 2009;7(12):1559–67.

110 Nashef L, Ryvlin P. Sudden unexpected death in epilepsy (SUDEP): update and reflections. *Neurol Clin* 2009;27(4): 1063–74.

111 Rugg-Gunn FJ, Nashef L. Sudden unexpected death in epilepsy. In: Shorvon S, Pedley TA (eds). *Blue Books of Neurology*. Philadelphia: Saunders, 2009, pp. 211–40.

112 Falconer B, Rajs J. Post-mortem findings of cardiac lesions in epileptics: a preliminary report. *Forensic Sci* 1976;8(1):63–71.

113 Sokrab TE, *et al.* A transient hypertensive opening of the blood–brain barrier can lead to brain damage. Extravasation of serum proteins and cellular changes in rats subjected to aortic compression. *Acta Neuropathol (Berl)* 1988;75(6):557–65.

114 Ikegaya H, *et al.* Accumulation of plasma proteins in Purkinje cells as an indicator of blood–brain barrier breakdown. *Forensic Sci Int* 2004;146(2–3):121–4.

115 Global Initiative for Asthma (GINA). Global strategy for asthma management and prevention updated 2009. Medical Communications Resources Inc, 2010. www.ginasthma.org

116 Parsons JP, Mastronarde JG. Exercise-induced bronchoconstriction in athletes. *Chest* 2005;128(6):3966–74.

117 Speizer FE, *et al.* Investigation into use of drugs preceding death from asthma. *Br Med J* 1968;1(5588):339–43.
118 Inman WH, Adelstein AM. Rise and fall of asthma mortality in England and Wales in relation to use of pressurised aerosols. *Lancet* 1969;2(7615):279–85.
119 Macdonald JB, Seaton A, Williams DA. Asthma deaths in Cardiff 1963–74: 90 deaths outside hospital. *Br Med J* 1976;1(6024):1493–5.
120 Jackson RT, *et al.* Mortality from asthma: a new epidemic in New Zealand. *Br Med J Clin Res Ed* 1982;285(6344):771–4.
121 Gandevia B. Pressurized sympathomimetic aerosols and their lack of relationship to asthma mortality in Australia. *Med J Aust* 1973;1(6):273–7.
122 Stolley PD, Schinnar R. Association between asthma mortality and isoproterenol aerosols: a review. *Prev Med* 1978;7(4):519–38.
123 Morild I, Giertsen JC. Sudden death from asthma. *Forensic Sci Int* 1989;42(1–2):145–50.
124 Busuttil A. Adrenal atrophy at autopsy in two asthmatic children. *Am J Forensic Med Pathol* 1991;12(1):36–9.
125 Champ CS, Byard RW. Sudden death in asthma in childhood. *Forensic Sci Int* 1994;66(2):117–27.
126 Brook I. Microbiology and management of peritonsillar, retropharyngeal, and parapharyngeal abscesses. *J Oral Maxillofac Surg* 2004;62(12):1545–50.
127 Reynolds SC, Chow AW. Severe soft tissue infections of the head and neck: a primer for critical care physicians. *Lung* 2009;187(5):271–9.
128 Wagner KS, *et al.* Diphtheria in the United Kingdom, 1986–2008: the increasing role of *Corynebacterium ulcerans*. *Epidemiol Infect* 2010;138(11):1519–30.
129 Hargreaves RM, *et al.* Changing patterns of invasive *Haemophilus influenzae* disease in England and Wales after introduction of the Hib vaccination programme. *Br Med J* 1996;312(7024):160–1.
130 McEwan J, *et al.* Paediatric acute epiglottitis: not a disappearing entity. *Int J Pediatr Otorhinolaryngol* 2003;67(4):317–21.
131 Corbett EL, *et al.* The growing burden of tuberculosis: global trends and interactions with the HIV epidemic. *Arch Intern Med* 2003;163(9):1009–21.
132 Mittleman MA, *et al.* Triggering of acute myocardial infarction by heavy physical exertion. Protection against triggering by regular exertion. Determinants of Myocardial Infarction Onset Study Investigators [see comments]. *N Engl J Med* 1993;329(23):1677–83.
133 Willich SN, *et al.* Physical exertion as a trigger of acute myocardial infarction. Triggers and Mechanisms of Myocardial Infarction Study Group [see comments]. *N Engl J Med* 1993; 329(23):1684–90.
134 Curfman GD. Is exercise beneficial – or hazardous – to your heart? [editorial; comment] [see comments]. *N Engl J Med* 1993; 329(23):1730–1.
135 Siscovick DS, *et al.* The incidence of primary cardiac arrest during vigorous exercise. *N Engl J Med* 1984;311(14):874–7.
136 Knight B. Trauma and ruptured cerebral aneurysm. *Br Med J* 1979;1:1430–1.
137 Knight B, Zaini MR. Pulmonary embolism and venous thrombosis. A pattern of incidence and predisposing factors over 70 years. *Am J Forensic Med Pathol* 1980;1(3):227–32.
138 Knight B. Fatal pulmonary embolism: factors of forensic interest in 400 cases. *Med Sci Law* 1966;6(3):150–4.

CHAPTER 26

Forensic Dentistry for the Pathologist

- Introduction
- Bite marks
- Identification of the dead from the dentition
- Pink teeth
- References

Introduction

Forensic odontology – the application of dentistry to forensic problems – is a discipline in itself and requires special dental expertise not possessed by pathologists qualified only in medicine. It is therefore imperative that, wherever possible, problems involving the teeth and jaws are referred to a dentist at an early stage, preferably at the time of the original autopsy or other examination of the subject.

A number of different circumstances need to be taken into account in this respect, however. First, it has to be accepted that by no means all dentists are either interested or competent in forensic problems. It is the same with pathologists, anatomists or any other specialists, in that the lack of enough motivation and experience can make their participation in legal matters of little value. A forensic odontologist naturally provides the best expertise, as he is professionally involved in the subject and will have training or experience, or both, of dento-legal problems, even though few forensic odontologists are occupied full time in this super-speciality, most being teachers or researchers in some other branch of dental science.

In many parts of the world, there are no forensic odontologists available. In developing countries there may be no forensic dentists at all – or the only expert is in the medical school of the capital city, inaccessible to distant areas. Even in more advanced states, problems of distance and travel may make it impracticable to call an odontologist to examine the body *in situ*. Dental expertise may be made available later, if material is retained for examination for transmission to the expert. In yet other circumstances, many problems of availability, cost and the lack of perceived importance of the case may make it impossible to involve an odontologist at an early stage – or even at all. In all these instances the pathologists or other medico-legal doctors may have no choice but to handle the dental aspects as best they can, either in the initial stages or even throughout the investigation.

This chapter is meant to be nothing more than a guide for the doctor placed in this position and is certainly not intended to encourage pathologists to attempt to replace or dispense with a good odontological opinion. It cannot be sufficiently emphasized that, where the issues are serious, every effort should be made to obtain expert forensic dental assistance. The remainder of this chapter must be looked on solely as a 'first-aid primer' for cases in which the ideal investigation cannot be attained for one reason or another. If no expert dental advice can be obtained at the outset, then the pathologist should do all he can to assemble and preserve both detailed records and physical specimens, which can be examined later by a forensic odontologist, if one can be found further along the investigative pathway.

The assistance that dentistry can render falls into two broad headings:

- the interpretation of bite marks
- personal identification, either individually or in the context of mass disasters.

Bite marks

One of the two major interests of forensic odontologists is one that has direct relevance to pathologists in that it concerns the interpretation of trauma to the body surface. For the sake of completeness, however, mention must first be made of bite marks on inanimate objects, usually foodstuffs. This is mainly within the province of forensic science in the sense of 'criminalistics', where dental evidence is used to identify the perpetrators of a crime who happen to have left their teeth marks in some substance left at the scene. This rarely concerns forensic pathologists, except in the rare instance of their being asked by the police to examine an object, such as an apple or piece of cheese, to see if some obvious dental abnormality of a suspect could have caused the unusual bite mark.[1,2]

The doctor may also be asked how the bite mark may be best preserved until the object can be examined by a forensic odontologist at a later date. Where the substance is 'plastic', such as butter, cheese, lard, wax or chocolate, for instance, it should be stored in a refrigerator to prevent melting or gradual flowing. It should not be deep frozen, as this may cause brittleness and cracking. Forensic science advice should be taken if at all available. Fruit, especially apples, seems prone to be bitten at scenes of crime, and Marshall *et al.* recommend preservation in Campden solution, a metabisulphite fluid used for fruit bottling. Alternatively, 5 per cent acetic acid in 40 per cent aqueous formaldehyde solution can be used. Ordinary histological formalin is not satisfactory – nor is refrigeration, which allows the fruit to shrivel. Whatever preservation is recommended to the police, the object should be adequately photographed with the film plane at right angles to the bite and a scale placed in the focal plane (Fig. 26.2).[3,4] If appropriate, swabbing for saliva traces should be carried out (see below) and then the fruit preserved for future examination.

Returning to the human body, bites are relatively common, especially in cases of child abuse and in adult sexual assault (Fig. 26.1).[5–7] In the former, bites may be anywhere on the infant, favourite sites being the arms, hands, shoulders, cheeks, buttocks and trunk. In the author's (BK) experience almost all bites on small children have been inflicted by the mother, but this is by no means invariable in the generality of child abuse. A common excuse from the parents is that the infant was bitten by another sibling or by the family dog – and occasionally, this explanation may be true. Others may be self-inflicted.[8–10] It is therefore vital that the bite mark be properly examined to determine whether it is of a size consistent with adult dentition, or whether it is small enough to have come from another child – or is of a different shape, indicative of an animal.



Figure 26.1 Bite mark on baby's arm in a case of child abuse. The culprit was the mother. The teeth marks are deficient over one quadrant, the gap on the other side being smaller than usual.



Figure 26.2 Bite mark on the anterior side of the right lower leg of a 6-week-old infant inflicted by a 2.5-year-old child. Age of the injury 4 days.

The other common circumstances in which human bite marks occur are rape or other sexual offences. Here the pathologist will need to examine bites as part of the autopsy in a sexual murder – or even sometimes in live victims of an assault, if it is part of his duties to deal with clinical examinations or where no 'police surgeon' or forensic physician is available (Figs 26.3–26.5).

In this type of crime, bites may be sexually orientated or be distributed on any part of the body. Common sites are the breasts and nipples, but the neck, shoulders, thighs, abdomen, pubis and even vulva may be attacked. As noted in the chapter on sexual homicide, care must be taken to recognize that some so-called 'love bites', especially with suction petechiae, may be part of acceptable (if over-enthusiastic) sexual intercourse, but where real damage occurs, especially to breasts and nipples, then a violent or sadistic element is likely. An analysis of 778 bite marks by Freeman *et al.* showed that most bites occurred on the arm, followed by the breast. If broken down by gender, males were



Figure 26.3 Bite mark on the right breast of a 50-year-old female who died from strangulation during sexual assault. (Reproduced by kind Permission of Professor Cristina Cattaneo.)



Figure 26.4 Bite mark on a nipple during sexual assault. The injury is too small for any dental matching, but swabs of the bite may recover saliva and DNA that might provide the means to identify the assailant.

bitten on the arm more than females, and females were bitten on the breast more often than males. The data show patterns in location and number of bites that seem related to both the type of crime and the age of the victim.[7]

Bites may also be inflicted on police officers when attempting to arrest resisting offenders. They are also suffered in sporting events, especially football and some forms of wrestling, and during assaults when the victim manages to bite the assailant. In these instances bites may be inflicted anywhere, but the hands, fingers, nose, forearms, ears and even lips may be the targets.

Some bite marks are self-inflicted; falls onto the face or a fit may cause the tongue and lips to be badly bitten.



Figure 26.5 Bite marks made during a sexual assault. The mark on the left shows no specific features but its position is typical of a sexually orientated bite. The other shows central confluent petechiae and red bruising from suction and tongue pressure. There is a lower semicircular pale zone corresponding with the lower lip, but the striking feature is the group of linear abrasions at the top of the mark made by the upper incisors dragging across the skin as the jaw is closed. Both bites are surrounded by zones of diffuse bruising.

Other persons deliberately bite themselves, sometimes to fabricate injuries for a variety of motives ranging from gain to psychiatric disorder.[8–10] Multiple bite marks (especially of the suction type), which are seen on accessible areas of the shoulder and arms, raise the suspicion of self-infliction, especially in older children and teenage girls.

The nature of the bite mark

Though called a ‘bite mark’, some of the components of the application of the mouth to skin may not be from the actual teeth. The lips can transiently mark the skin if forcibly nipped, especially on children, though the marks are short-lived and rapidly fade in life, not persisting after death unless associated with petechiae. Suction can produce a crop of punctate haemorrhages, either small petechiae or larger ecchymoses merging into a confluent central bruise (see Fig. 4.21).

A human bite mark may present only a small part of the dental arcade, caused by the front teeth from canine to canine with an almost invariable gap at either side representing the separation of upper and lower jaw. A human bite is near circular or a shallow oval. A deep parabolic arch or a ‘U-shape’ can only be animal in origin.[11–15] The teeth may cause clear, separate marks or they may run into each other to form a continuous or intermittently broken line. As time passes, originally clear tooth marks spread out and blur, progressively losing their definition – though abrasions on the skin surface retain their shape until scabbed healing is complete.

Teeth marks may be abrasions, bruises or laceration – or a combination of any two or three. The clarity of a bite mark depends on a number of factors. If the contour of the part bitten is irregular or markedly curved, then only part of the dental arch may contact the tissues. If the bite is forcible, then extensive subcutaneous bruising may spread laterally and blur the outline. If the bite was inflicted many days before, then healing of abrasions and lacerations, and absorption of bruising will leave progressively less detail. Where teeth have been forcibly applied, the typical appearance is of two 'bows' with their concavities facing each other and a gap at each end. Within this may sometimes be suction petechiae, which are often present without teeth marks, in the so-called 'love bite'. They are caused by the firm application of the lips, which form an airtight seal against the skin, then a sucking action reduces the air pressure over the centre. This causes a shower of petechial haemorrhages to appear from rupture of small venules in the superficial layers of the subcutaneous tissues. If forcible, the petechiae are confluent and a frank bruise, or even haematoma develops. Added to this is pressure from the tongue, pushing the tissues against the palate. This type of lesion is most often seen on the side of the neck and on the breasts of women, either in love play or after a sexual assault. They are by no means rare in child abuse, however, and are sometimes self-inflicted. Such a suction lesion must be human in origin and the claim that one is caused by a household pet can be immediately discounted.

Bites may be inflicted by the teeth closing down on a relatively flat skin surface, but there is usually an element of indrawing into the mouth, so that the teeth close down onto a parallel-sided or elliptical block of skin. In sexual bites, especially of the breast or nipple, the tissue may be actually sucked into the mouth before the jaws close upon it. This will naturally affect the shape of the resultant bite mark when the skin is released and flattens out once more.

Occasionally, the bite mark may not be two opposing arches, but more linear in pattern. This is seen especially where the upper incisors are scraped down the skin, leaving a series of parallel tracks, sometimes several centimetres long.

The lower incisors may leave either a curved line of static marks, or a straight or interrupted line below the upper incisor scrapes, as the lower teeth dig in and anchor the skin whilst the upper teeth gouge downwards towards them, during the act of closing the mouth.

The major problem with bite marks is the identification of the perpetrator and hence the problem cannot really be tackled without the expertise of a dentist fully experienced in this specialist task. Unless the dentition has some really characteristic features, especially in the incisors and canines, then a non-dentist is a poor witness if the matter comes to a legal dispute. Some odontologists would claim that a bite mark can only be identified in a negative sense – that is, suspects can be excluded if their dentition is obviously incapable of inflicting the bite mark under investigation, but that no positive match can be claimed. Though many forensic odontologists would dispute this conservative claim, it is probably the best attitude for a pathologist involved in such a problem, unless there is some really spectacular and unique feature in the front teeth of a suspect.

Missing teeth, grossly displaced teeth and substantially damaged teeth may suggest a match with a person – or the mark may be quite inconsistent, which is helpful to the investigators if they eliminate a person or persons, especially in the restricted range of a family in which a child has been abused.

It is probably best for a pathologist to realize his limitations in this field, however, and to confine himself to taking the best physical evidence for later study by a forensic odontologist, where this is at all possible.

The investigation of a bite mark

As stated, every effort should be made to obtain the best evidence for future specialist examination. First, the bite mark should be carefully and fully photographed. If police facilities are to be used, the pathologist – as in other aspects of forensic pathology – should direct them as to the important features required. Often such photographers, though otherwise expert in the technical aspects of their craft, do not appreciate the problems that inadequate or inappropriate views can cause – especially at a later date, when experts reviewing the case and lawyers presenting it in court have to rely on photographs without the benefit of having seen the original lesions.

The photographs should be taken from several different angles, but especially from a directly perpendicular viewpoint, with the plane of the film at right angles to that of the lesion. Some police photographers persist in taking tangential shots that foreshorten the true shape. An accurate scale should always be adjacent to the lesion, as close as possible, but not impinging upon it or obscuring any detail. Specific rulers, such as those of the American Board of Forensic Odontology (ABFO), include two scales at right angles and a perfect circle at their intersection: this can help in correcting any distortion.[3]

Bites are often on a curved surface, such as the face, breast or arm, and thus can never be reproduced exactly on a flat surface, as there is bound to be slight foreshortening at the ends, but several views at slightly different angles can overcome this problem. Small lens apertures and short focal lengths will obviate the blurring that results from the lesion curving out of the focal plane. Too short a focal length will itself produce image distortion.

The lighting is important, as perpendicular lighting may lead to a flat rendering with no capture of detail. Side lighting may throw small irregularities into relief, especially if there are tooth indentations in the skin. Both monochrome and colour photographs should be taken, with particular attention to sharp focus and correct exposure. The use of infrared-sensitive film has been recommended to reveal occult bruising, but it also appears to demonstrate artefacts. The lesion should almost fill the camera frame in some shots to capture as much detail as possible, either by short lesion-to-camera distance or the use of long-focus lenses. More general, wider shots should also be taken, however, to orientate the bite mark in relation to anatomical landmarks. During photography, care should be taken not to heat up the skin by the close proximity of high-power tungsten lamps. These should be placed at a distance or used only for short periods. Flash illumination will obviate this danger of heating the skin, which can distort the bite mark.

When photography is completed, swabs of the bite should be taken to try to recover saliva. Though not always successful, this technique can be vitally important in helping to identify the perpetrator with DNA analysis. Sterile swabs are gently rubbed onto the bite – some experts recommend slightly moistening them first with water or saline. They should then be deep frozen unless dried and sent straight to the DNA laboratory.

Following photography and swabbing, there is usually little more that the pathologist can do in the absence of a dentist. If facilities are available and someone has the expertise, an impression or cast of the bite can be made.[16–18] This consists of laying a plastic substance over the bite mark, which then hardens, so as to produce a permanent negative cast of the lesion. It is usually made with a rubber- or silicone-based medium containing a catalytic hardener. Less satisfactory substances are water-based pastes, such as plaster of Paris, which are put on wet and allowed to dry before removal. These have the disadvantage of potential damage to the actual bite, if that is required for further evidential examination. Though it is unlikely that a pathologist will be able to carry out these procedures, it may be that a non-forensic dentist or a forensic scientist used to making casts of other evidence may be able to make satisfactory impressions that can then be preserved for later examination by an odontologist. Nowadays one can also envisage perfoming a 3D scan of the lesion in order to acquire a virtual 3D reconstruction of its shape and size.[17–21]

After autopsy, it is also possible for the whole area of skin carrying the bite to be removed and preserved in formalin for future examination. The shrinkage and distortion that are virtually inevitable, however, make these specimens of limited value for detailed tooth matching, though if good photographs with accurate scales are also available, they may be a useful addition to the dental evidence.

It is recommended that, as with all bruises and abrasions, the body be re-examined a few days after the first autopsy, as the appearances may be markedly enhanced. In a bite mark, faint or even absent original lesions may become more prominent, or even appear for the first time a day or two after death. The removal of skin carrying the lesion should be delayed if it is wished to see if this enhancement will occur, unless climatic conditions or lack of refrigeration would make this delay undesirable.

Matching the bite mark with the suspect's dentition

For a pathologist, this is such a specialist enterprise that it would rarely be attempted, unless there was no prospect whatsoever of a forensic dentist being available, even at a later date. As mentioned earlier, unless there is a striking dental feature in the bite mark or in the teeth of the suspect, the best that can be done is to try to exclude a limited number of potential assailants on the basis of lack of correspondence of their dentition with the bite mark. If neither mark nor teeth show any particular distinctive appearances, then even this should be avoided, without expert dental opinion. Where circumstances dictate that only the pathologist will ever be available to help the investigation, he should confine himself to the following routines:

- The teeth of those who are either suspected by the police or who had access to the victim should be examined. In most jurisdictions it is vital that fully informed consent should be obtained from the person beforehand. The doctor must explain what he intends doing and the reason for doing it. It must be made clear that this is to be done for the purposes of a legal investigation and that any information gained might be used as evidence – and that it is not related to diagnosis or treatment for the subject's own welfare.
- Any refusal must be a bar to any further action. Where children are concerned, usually in the setting of child abuse, the consent of the fully informed parents or guardian must be obtained. All such consent is preferably obtained in writing and many police forces have special forms for the purpose. If not written, then a dubious second best is getting oral consent; at least one witness to this must be obtained, if possible from independent persons other than relatives or police officers.

With consent, the dentition is then examined and the following points determined and recorded by diagram and writing. Photographs should also be taken if there is an issue of possible correspondence between the teeth and the bite – or where exclusion is legally important.

- The presence of full or partial denture – and, if so, were they worn at the time of the incident?
- The number of teeth in upper and lower jaw.
- A charting of any missing teeth, especially incisors and canines.
- An estimate of the bite overhang, or whether there is edge-to-edge occlusion or an undershoot projection of the lower teeth.
- Recording of any broken teeth or teeth with significant individual abnormalities; these must be charted and described.
- A record of any irregularity or marked variation in the cutting edge profile of any front teeth.
- An evaluation of the size and prominence of any teeth, especially in the canines and incisors and any developmental abnormalities, such as an extra interposed front tooth.
- Recording of any abnormality in the orientation of any tooth or teeth, such as twisting (rotation) in the anteroposterior tilting or double row of teeth. Gaps and irregular spacing are vital factors.

Though it is unlikely that a pathologist will have either the expertise or materials to make an impression of the bite, this might be attempted if no dental assistance of any kind is available – though the aid of a local dental practitioner would be useful in obtaining a wax or other bite registration. If this is impossible, then a bite impression into any available plastic substance might be attempted. The use of such substances as modelling clay, Plasticine, or beeswax might be better than nothing if some unique feature required demonstration. Finally, whether it be from visual inspection of the teeth or from comparison with a cast, an attempt should be made to compare the characteristics of the bite mark with the dentition of the suspect or suspects. It is assumed that an animal bite will have already been excluded by this stage.

This comparison can be performed in various ways, different odontologists having their own techniques. Where marked abnormalities exist in the teeth, these may be present in the bite mark if the affected teeth happen to have registered in the lesion. Some forensic dentists prefer to match photographs of the mark with photographs or tracings of the teeth, the former being printed to a 1:1 magnification. Tracings can be made from positive casts of a bite impression, inking the cutting edges of the front teeth and transferring these to transparent sheets, which can then be laid over the photographs to determine correspondence. Others use a negative photograph of the teeth laid over a positive photograph of the bite, again ensuring exact correspondence of magnification.

In a bite mark it is said that a tooth impression is better evidence than an absent mark – in other words, the presence of a tooth mark means that the tooth was actually in the jaw, whereas a gap in the injury could either mean that the tooth was missing or merely that the occlusal edge had not marked the skin, perhaps because of slight shortening, unevenness or wear. In all matching procedures between a bite mark and the suspect teeth, allowance must be made for distortion of the skin surface during the biting process and the angle of attack of the teeth. Again it is emphasized that exclusion is probably a much safer exercise than an allegation of positive matching, unless there is some unique feature in the dentition.

In practice, it is the six upper and six lower front teeth that give the most information. The canines may provide particular help when prominent and pointed. Premolars and molars are rarely useful, as might be expected from their lower profile and posterior position in the jaws.

Contrary to what people may think, adult and child bite marks can be difficult to distinguish from a quantitative perspective because of a large area of overlap in dimensions of chords and arcs of dentition.[22]

Identification of the dead from the dentition

The major contribution of forensic odontology is in the field of identification, especially in mass disasters, such as aviation and marine catastrophes.[23–28] In air crashes, dental investigation, along with DNA analysis, is the most successful single procedure leading to identification of mutilated and burned bodies, as the passenger manifest lists provide a circumscribed population for whom dental records can be obtained in the majority of cases.[29] In such disasters the involvement of dentists is imperative, but the size of the subject is far too large to be attempted in a book of this nature.

Apart from mass casualties, forensic odontology is frequently used in problems of individual identity that are the direct concern of the forensic pathologist, as accident, suicide and murder form the majority of such unidentified bodies (Fig. 26.10).

As with skeletal remains (of which dental evidence is part), discussed in Chapter 3, there are two prime avenues of investigation:

- general or reconstructive identity, which attempts to classify the unknown person by age, sex and race
- comparative methods, which confirm or exclude the personal identity of the individual against ante-mortem dental records.

Once again, the pathologist can only act for the dentist in a 'second-best' way, when no forensic odontological expertise is available. Unlike bite marks, the material is likely to be much more permanent and, wherever possible, the pathologist should retain photographs, chartings and even the actual dentition against the time when expert dental opinion might become available. When time presses in a criminal investigation, however, or where no dental help is ever likely to be forthcoming, then the pathologist has to do the best he can, though many special techniques such as radiology or tooth sections may be quite beyond his capabilities.

General or reconstructive identity

Unlike skeletal remains, the human origin of dental material is rarely in doubt. In badly decomposed or skeletalized bodies the jaws usually survive intact, though in dry skeletons, teeth may become loose and fall out, especially the single-rooted canines and incisors.

Even in fragmented bodies and skeletons, the jaw remnants and teeth are readily recognizable, even by lay persons. Where teeth have dropped out and been recovered independently of a body, they are still usually recognizable as human, as opposed to most domestic or farm animals. In countries where large primates exist, there may be some confusion, but this is a rare problem.

Having established the human origin, the next determination is sex and here teeth have a poor discriminating value, though the intact jaw is more helpful, as discussed in Chapter 3. Male teeth are usually larger, but this is generally unhelpful.

Girl's teeth tend to calcify and erupt earlier than boys. If the skeletal age is known, then more advanced tooth eruption in young persons is an indication of being female, though in these circumstances there are usually far better indicators of sex available elsewhere in the skeleton. Extraction of pulp tissue from a tooth, even up to many months after extraction or death, can provide sex determination via DNA.

Race is also a difficult criterion to determine from teeth. The best-known feature is the 'shovel-shaped' upper central incisors of Mongoloid groups. The posterior surfaces of these teeth have a depression centrally, with two marginal bars, causing the back of the tooth to appear like a coal shovel with turned-up edges. The feature is found mainly amongst Chinese, Mongols, Eskimos and Japanese, but is also found amongst non-Mongoloid races in lesser numbers. Some 91 per cent of Chinese, Japanese and Tibetans have such teeth, 95 per cent of Native Americans, 84 per cent of Eskimos, 46 per cent of Palestinian Arabs – and 90 per cent of Finns. It is rare amongst Negroids and Australian Aboriginals. In Caucasian groups, the lateral incisors in the upper jaw are usually smaller than the central, especially in females, a feature absent or less marked in Negroid or Mongoloid races. Caucasians also have long pointed canine roots, a feature not seen in Mongoloids. Enamel pearls, small nodules of enamel on the tooth surface, are much more frequent in Mongoloid teeth. Small nodules on the lingual surface of maxillary molars, called 'Carabelli's cusp', are most common in Caucasian races and rare in the other major racial groups.[30,31] The condition of bull-tooth or 'taurodontism' is most common in Mongoloid peoples: here the pulp cavity of molars is wide and deep, and the roots are fused and bent. A congenital lack of the third upper molar is most common in Mongoloids, but can occur in any race. Negroid races tend to have large teeth and often have more cusps on their molars, even up to eight, with two lingual cusps on the mandibular first premolars as an additional common finding.

The age of the person is one of the most useful findings disclosed by the teeth, especially in the first two decades of life. The sequence of deciduous or 'milk' teeth is well known, overlapping the appearance of the permanent dentition (Fig. 26.6). This is only an average timetable, however, and is modified by several factors, such as sex, race, diet, disease and climate. Again, dental expertise is needed to refine the accuracy of such estimations. The determination of age from fetal teeth is also a matter for embryologists or dentists with specialized knowledge of this period. After the third molar has erupted and the root apices are closed, in the third decade of life, then age determination becomes much more difficult. Much research has been expended in forensic odontology and the name of Gustafson is well known in this respect.[32–36]


(a)
Lower – 6–8 months
Upper – 9–12 months
Central incisor
Lateral incisor
Upper – 18–24 months
Canine
18–24 months
12–24 months
First molar
2–3 years
Second molar
(b)
Male
Female
6–7–8
6–7–8
7–8–9
7–8–9
C1
C1
L1
L1
10–11–13
C
C
10–11–12
9–10–12
8–10–11
1PM
1PM
10–11–13
2PM
2PM
9–11–12
5–6–7
1M
Upper
1M
5–6–7
11–13–14
2M
2M
11–12–14
17–21–25
3M
3M
17–21–25
Male
Female
6–6–7
5–6–7
7–8–8
C1
C1
6–7–8
L1
L1
10–11–12
C
C
9–10–11
9–11–12
9–10–12
1PM
1PM
10–11–13
2PM
2PM
9–11–12
5 – 6 – 7
1M
Lower
1M
5–6–7
11–12–13
2M
2M
10–12–13
17–21–25
3M
3M
17–21–25

Figure 26.6 (a) Dates of eruption of deciduous teeth (average times). (b) Times of eruption of permanent teeth; three dates are shown (years) for early, average and late eruption, rounded to the nearest year.

This method has been replaced by Lamendin's method that evaluates root dentine translucency, periodontopathy and tooth length (described in Chapter 3), as well as by methods that evaluate the reduction of the pulp chamber through X-rays.[37–47]

It seems pointless to rehearse these methods in advice to pathologists, however, as specialized techniques, equipment and knowledge are needed for these procedures. The standard textbooks on forensic odontology and original papers should be consulted for the details.

Returning to general features of age, obvious pointers are the state of the teeth in respect of wear, hygiene and colour, which may deteriorate with advancing age. Much depends upon the care with which they have been maintained, however, though marked occlusal attrition tends to go with increasing age, unless a rough diet has accelerated the wear. In Western Europe, gross occlusal attrition, sometimes down to gum level, is seen in old skeletal material. This usually indicates that the bones and teeth came from someone alive in the mid-nineteenth century or earlier, before modern milling methods removed abrasive stone dust from flour (Fig. 26.7).

Edentulous jaws also suggest advancing age but, especially in former years before more conservative dentistry, even young adults often had total tooth clearances for caries. Once the teeth have gone, there is a general atrophy of the alveolar margins, but this is a poor criterion of age because of the great variability in the time when teeth are lost.



Figure 26.7 Severe occlusal attrition in a jaw from the early nineteenth century. The crowns are worn down to expose the dentine by a rough diet that probably contained stone dust in the flour from contemporary milling methods.

Newer techniques for age estimation include the variation with age of racemization of amino acids, especially aspartic acid, but this is a very specialized area.[48–58]

Comparative identification from teeth

Establishing personal identity requires the matching of observed features with pre-existing dental records, the latter almost always obtained from previous diagnostic and therapeutic surveillance (although for people with no clinical ante-mortem data a comparative analysis of the dental profile can be performed if there is a good ante-mortem photograph with the subject smiling and thus showing part of the upper dental arch) (Fig. 26.8).[25–28,45,59–61] For this method to be applied, there must be:

- Some collateral evidence to indicate either who the unknown body might be, so that records can be sought.
- Alternatively, a circumscribed population must be searched for records that may match the unknown. Such a population may be the known passengers on an aircraft or ship or a cohort of missing persons maintained on some register. It is manifestly impossible to search a large population, such as a whole country or even a city. Attempts were made in Britain to computerize dental records from the National Health Service so that a wide search could be made, but the completeness and quality of data was such that the scheme was found to be impracticable.
- The unknown person must have had dental attention in the past. The dentist or hospital must be known; the records must be traceable and, when found, must contain sufficient clinical information to provide adequate identifying features. The recovery of dental radiographs is a most useful adjunct. Unfortunately, these criteria are not always satisfied.



Figure 26.8 Odontological comparison between periapical post-mortem X-rays (highlighted in red) and the ante-mortem orthopantomogram. Identification is based on corresponding features: the corresponding peculiar bridge 13-14-15 with two prosthetic premolars replacing one tooth; the presence of a crown on 12; the corresponding presence of a bridge on 24-25-26-27; the endodontic metal post on 25 and the presence of radio-opaque material close to the dental apex; the fillings on 23, 34, 35, 36 and 47; the crown on 45 and 46 joined by a metal extension. (Reproduced by kind permission of Professor Cristina Cattaneo.)

The dental records are needed to provide a description of the dentition and jaws at a date as late as possible before the finding of the body. Work may have been done on the deceased during life since the last record was made, if the person had been treated elsewhere and the information not recorded. Where a record does not conform to the dental state of a body who was expected to be a match, it is obvious that such discrepancies can be of two types:

1. If the record indicates some condition that is irreversible but which does not exist in the body, then that excludes matching. For example, if the record states that certain teeth have been extracted, yet they are still present in the jaws, then any hope of correspondence must be abandoned.
2. If fillings are present in the teeth, which are not shown in the records, then these may have been made later and not recorded. Of course, no discrepancies of point 1 must be present for those of point 2 to be acceptable.

Charting the teeth

In the absence of a forensic odontologist, the next best person to record the state of dentition of a dead body would naturally be a dental practitioner, to whom this task would be an everyday routine. The chart made by him could then be used for future reference in any identification procedure. This chapter is concerned with the imperfect yet sometimes inevitable circumstance where the pathologist is the only person available. Unfortunately, there are a host of different methods of charting the contents of the jaws, and, in spite of sustained efforts, no universal internationally accepted system has yet been adopted. For our purposes, any careful record of the number, position and state of the teeth made by a pathologist can be converted into whatever system of charting is required at a later stage.

Two main methods of recording data are in use: the first is a diagrammatic chart commonly used in large dental services such as the British National Health Service, seen in Figure 26.9. The other system uses a



Figure 26.9 Two of the many types of chart used for recording dental characteristics. The upper is the 'Odontogram' designed for Interpol. The chart displays each surface of each tooth, including the deciduous teeth. The lower chart is that used in the British National Health Service, which is a simpler design. In both charts the buccal aspects are at the top and bottom and the lingual sides of the teeth face each other centrally.



Figure 26.10 A short cut in excluding homicide. A skeleton was found buried in a suburban garden. Initial suspicions were allayed when the ramus of the mandible was seen to carry a bronze wire for attaching a spring to suspend the jaw from the skull. Police enquiries confirmed that the house had previously belonged to a member of the medical school teaching staff.



Figure 26.11 A mandible from a skeletalized body found in suspicious circumstances. Identity was established solely from dental features, such as the gold bridge and acrylic tooth on the right side of the jaw and the numerous amalgam fillings. Comparison of dental radiographs obtained from a hospital confirmed the correspondence. The jaw, with the prominent square symphyseal region, is typically male.

more pictorial representation of the teeth, so that all features can be recorded in a more exact topographical manner. Both systems, as well as many variants, have a notation that describes the position of the teeth, almost always in four quadrants, right upper, left upper, right lower and left lower. Unfortunately, there is considerable variation in the sequence of numeration, especially where the transition points from left to right, and from upper to lower are concerned, these being confusing and often not interchangeable. The pathologist need not concern himself too much with this problem, as his graphic representation can always be turned into whatever system of numeration is required at a later time. For example, if an unknown body has its teeth charted on one of the common diagrams and later the dental records of a potential 'identity' become available, the chart can be transposed into the same system as the clinical records. The notation derived from this can then be transmitted by telephone, fax, email or other form of communication, if the records are not available at the place where the body lies. This is particularly important in transportation fatalities such as air crashes, where the home base of the victims may be far removed from the scene of death.

On the diagrammatic or anatomical charts, each tooth is represented by a pictorial symbol that provides the same number of tooth surfaces as those on the same teeth in the mouth. The incisors and canines have four surfaces represented, while the premolars and molars have an additional facet, the occlusal surface. On these diagrams, the positions of fillings, crowns, caries and damage are marked, and, of course, missing teeth are deleted.

In charting the teeth, the pathologist needs good access to the mouth and this presents the first problem. Rigor mortis in a relatively fresh cadaver may make it impossible to open the mouth without great effort. Excessive force should not be used, especially leverage with a metal instrument, because of the danger of damaging the teeth. Where the rigor cannot be broken by sustained firm pressure on the chin – or where time prevents waiting for rigor to pass off – it may be necessary to extend the autopsy incision into a neck 'V' and dissect the skin off the lower part of the face, to gain access to the masseter and temporalis muscles, which can then be divided above their insertion into the mandible, to allow the jaw to become mobile. Care must be taken not to disfigure the face during this procedure.

When the body is decomposing, no rigor will be present. If badly rotted, then cosmetic considerations will not apply and more radical removal of the jaws may need to be performed. The same holds for badly burned bodies, where heat contraction of the facial muscles may make it impossible to open the jaws without dissecting away tissues. In both these instances, where identity is a prime consideration, both mandible and maxilla may need to be removed for retention and later examination. The mandible can be disarticulated at the temporomandibular joints and removed intact. The lower maxilla, comprising the tooth-bearing jaw, the palate and the inferior part of the facial skeleton, can be removed after the mandible has been taken. This is done by sawing horizontally across the maxilla at the level of the lower margin of the nasal aperture, taking care to saw above any tooth roots. After photography and charting, the jaws can be preserved in a freezer or, if cleaned of soft tissue, as dry bone. With modern DNA identification techniques, the need to keep some tissue for subsequent testing should be borne in mind. Naturally, the presence of any full or partial dentures or any other type of dental prosthesis will have been recorded and the prosthesis carefully retained for examination. Even edentulous persons may show signs of having worn dentures by the presence of pressure marks on gums or palate. Wherever possible, radiographs or computed tomography (CT) scans should be taken of the head of an unidentified body (as discussed in Chapter 3) where non-dental considerations apply, such as craniometry or frontal sinus visualization. At the same time, the radiographs may show unexpected foreign bodies in the head and some of these may have unique dental importance, such as broken drill, broken roots or congenital abnormalities, which may be matchable with clinical films, or a note in the ante-mortem records. Radiography has a special place in forensic odontology, but specialist techniques and knowledge are likely to lie outside the abilities of a pathologist (Figs 26.12, 26.13).



Figure 26.12 Post-mortem imaging using multislice computed tomography (CT) allows a quick overview on the dental status and is useful for the detection, localization and identification of any foreign objects in corpses by measuring radiodensities—referred to as Hounsfield units (HU). The figure shows high resolution CT of the dentition reconstructed in extended CT scale. Analysis of the restorative material yields to a 4000–9000 HU filling. (Reproduced by kind permission of Professor C. Jackowski.)



Figure 26.13 Volume rendering (VR) of the same data set as in Fig. 26.12 using a specialized VR preset for dental data sets allows colour encoding of different filling materials and visualization of the dentition in any desired projection. (Reproduced by kind permission of Professor C. Jackowski.)

When, by whatever means necessary, the dental arches have been made available for examination, the following features are sought and recorded on the chart:

- Extractions – whether recent or old – should be noted from the condition of the socket.
- Fillings – their number, position and composition.
- Artificial teeth – gold, porcelain or stainless steel.
- Other prosthetic work in the mouth, such as bridgework or braces.
- Crowned teeth.
- Broken teeth.
- Pathological conditions in teeth, jaws or gums.
- Congenital defects such as enamel pearls, Carabelli's cusps or ectopic teeth.
- Malpositioned teeth – rotated or tilted for example.
- The general state of care and hygiene including caries, plaque, tobacco staining and gingivitis.
- Racial pointers, such as shovel-shaped upper central incisors or multicusped molars.

When all available information has been discovered and entered on the chart, the process of comparison with any ante-mortem records can be made. Much will depend on the quality and the date of these records, which are frequently less detailed and exact than the autopsy charting. Allowance must be made for the clinical records to be substantially out of date on occasions, as mentioned earlier. The process of matching is again really the work of an experienced dentist, but the major task of checking the above list against the previous records can be carried out adequately in respect of missing teeth, filling, prostheses and major trauma and other anomalies (Fig. 26.11).

Anything on the clinical chart that is not represented in the actual jaws almost always excludes a matching – fillings cannot go away and extracted teeth cannot return, even though some remarkable feats of dental treatment now exist. The degree of correspondence that is acceptable for a positive match is a matter of common sense, and naturally other non-dental aspects must be taken into account – it is useless trying to claim a match on a female's dental characteristics if other information clearly indicates that the missing person was male. Finally, and at the risk of being over-repetitive, it must again be emphasized that, though the pathologist may be a collector of data and physical evidence, where the issues are vital (as in a homicide investigation), every effort must be made for the material to be evaluated by a forensic odontologist, even if the details have to be sent by air mail to another country.

Pink teeth

At autopsy on putrefied bodies, the teeth are sometimes seen to be a marked pink colour, especially near the gum line. Considerable research has been carried out into this interesting phenomenon and it is clear that the colour is the result of the dentine being stained by haemoglobin products.[62–71] It was once thought that carbon monoxide played a part in the colouration, but this has been disproved. Claims that the phenomenon is a pointer to an asphyxial death can be discounted, though possibly a very 'congestive' mode of death – albeit a very non-specific condition – encourages pinkness because of retention of blood in the pulp (Fig. 26.14).



Figure 26.14 Pink teeth of a decomposed body dumped in the countryside after death from narcotic overdose. No carbon monoxide was present in the body, the pinkness being caused by haemoglobin products staining the dentine. (Reproduced by kind permission of Professor David Whittaker.)

References

1 Marshall W, Potter J, Harvey W. Bite marks in apples – forensic aspects. *Criminol* 1974; 9:21–6.

2 Webster G. A suggested classification of bite marks in foodstuffs in forensic dental analysis. *Forensic Sci Int* 1982;20(1):45–52.

3 Hyzer WG, Krauss TC. The Bite Mark Standard Reference Scale – ABFO No. 2. *J Forensic Sci* 1988;33(2):498–506.

4 Wright FD. Photography in bite mark and patterned injury documentation – Part 2: A case study. *J Forensic Sci* 1998;43(4):881–7.

5 Jessee SA. Recognition of bite marks in child abuse cases. *Pediatr Dent* 1994;16(5):336–9.

6 Banaschak S, Brinkmann B. The role of clinical forensic medicine in cases of sexual child abuse. *Forensic Sci Int* 1999;99(2):85–91.

7 Freeman AJ, Senn DR, Arendt DM. Seven hundred seventy eight bite marks: analysis by anatomic location, victim and biter demographics, type of crime, and legal disposition. *J Forensic Sci* 2005;50(6):1436–43.

8 Anderson WR, Hudson RP. Self-inflicted bite marks in battered child syndrome. *Forensic Sci* 1976;7(1):71–4.

9 Sobel MN, Perper JA. Self-inflicted bite mark on the breast of a suicide victim. *Am J Forensic Med Pathol* 1985;6(4):336–9.

10 Warnick AJ, Biedrzycki L, Russanow G. Not all bite marks are associated with abuse, sexual activities, or homicides: a case study of a self-inflicted bite mark. *J Forensic Sci* 1987;32(3):788–92.

11 McCarty VO, Cox RA, Haglund B. Death caused by a constricting snake – an infant death. *J Forensic Sci* 1989; 34(1):239–43.

12 Lauridson JR, Myers L. Evaluation of fatal dog bites: the view of the medical examiner and animal behaviorist. *J Forensic Sci* 1993;38(3):726–31.

13 Murmann DC, *et al.* A comparison of animal jaws and bite mark patterns. *J Forensic Sci* 2006;51(4):846–60.

14 Shields LB, *et al.* Dog bite-related fatalities: a 15-year review of Kentucky medical examiner cases. *Am J Forensic Med Pathol* 2009;30(3):223–30.

15 Pomara C, *et al.* Cave canem: bite mark analysis in a fatal dog pack attack. *Am J Forensic Med Pathol* 2011;(32(1):50–4.

16 McKinstry RE. Resin dental casts as an aid in bite mark identification. *J Forensic Sci* 1995;40(2):300–2.

17 Martin-de las Heras S, *et al.* Computer-based production of comparison overlays from 3D-scanned dental casts for bite mark analysis. *J Forensic Sci* 2005;50(1):127–33.

18 Martin-de las Heras S, *et al.* Effectiveness of comparison overlays generated with DentalPrint software in bite mark analysis. *J Forensic Sci* 2007;52(1):151–6.

19 Evans S, Jones C, Plassmann P. 3D imaging in forensic odontology. *J Vis Commun Med* 2010;33(2):63–8.

20 Bush MA, Bush PJ, Sheets HD. Similarity and match rates of the human dentition in three dimensions: relevance to bitemark analysis. *Int J Legal Med* 2011;125(6):779–84.

21 Martin-de-Las-Heras S, Tafur D. Validity of a dichotomous expert response in bitemark analysis using 3-D technology. *Sci Justice* 2011;51(1):24–7.

22 Cattaneo C. (Personal communication). 2014.

23 Syrjanen SM, Sainio P. Forensic dentistry – recent development towards an independent discipline in modern dentistry. *Proc Finn Dent Soc* 1990;86(3–4):157–70.

24 Valenzuela A, *et al.* The application of dental methods of identification to human burn victims in a mass disaster. *Int J Legal Med* 2000;113(4):236–9.

25 De Valck E. Major incident response: collecting ante-mortem data. *Forensic Sci Int* 2006;159 Suppl 1:S15–9.

26 Hinchliffe J. Forensic odontology, Part 1. Dental identification. *Br Dent J* 2011;210(5):219–24.

27 Cattaneo C, Gibelli D. Identification. In: Siegel JA, Saukko PJ (eds). *Encyclopedia of Forensic Sciences*. Waltham: Academic Press, 2013, pp. 158–65.

28 Clement JG. Odontology. In: Siegel JA, Saukko PJ (eds). *Encyclopedia of Forensic Sciences*. Waltham: Academic Press, 2013, pp. 106–13.

29 Peschel O, Eisenmenger W. Airplane crashes and other mass disasters. In: Siegel JA, Saukko PJ (eds). *Encyclopedia of Forensic Sciences*. Waltham: Academic Press, 2013, pp. 188–92.

30 Hsu JW, *et al.* Logistic analysis of shovel and Carabelli's tooth traits in a Caucasoid population. *Forensic Sci Int* 1997;89(1–2): 65–74.

31 Hsu JW, *et al.* The effect of shovel trait on Carabelli's trait in Taiwan Chinese and Aboriginal populations. *J Forensic Sci* 1997;42(5):802–6.

32 Gustafson G. Age determination on teeth. *J Am Dent Assoc* 1950;41:45–50.

33 Gustafson G. *Forensic Odontology*. London: Staples Press, 1966.

34 Maples WR, Rice PM. Some difficulties in the Gustafson dental age estimations. *J Forensic Sci* 1979;24(1):168–72.

35 Metzger Z, Buchner A, Gorsky M. Gustafson's method for age determination from teeth—a modification for the use of dentists in identification teams. *J Forensic Sci* 1980;25(4):742–9.

36 Kashyap VK, Koteswara Rao NR. A modified Gustafson method of age estimation from teeth. *Forensic Sci Int* 1990;47(3):237–47.

37 Lamendin H, *et al.* A simple technique for age estimation in adult corpses: the two criteria dental method. *J Forensic Sci* 1992;37(5):1373–9.

38 Borrman H, *et al.* Inter-examiner variation in the assessment of age-related factors in teeth. *Int J Legal Med* 1995;107(4):183–6.

39 Kvaal SI, *et al.* Age estimation of adults from dental radiographs. *Forensic Sci Int* 1995;74(3):175–85.

40 Kolltveit KM, Solheim T, Kvaal SI. Methods of measuring morphological parameters in dental radiographs. Comparison between image analysis and manual measurements. *Forensic Sci Int* 1998;94(1–2):87–95.

41 Baccino E, *et al.* Evaluation of seven methods of estimating age at death from mature human skeletal remains. *J Forensic Sci* 1999;44(5):931–6.

42 Soomer H, *et al.* Reliability and validity of eight dental age estimation methods for adults. *J Forensic Sci* 2003;48(1):149–52.

43 Bosmans N, *et al.* The application of Kvaal's dental age calculation technique on panoramic dental radiographs. *Forensic Sci Int* 2005;153(2–3):208–12.

44 Brkic H, Milicevic M, Petrovecki M. Age estimation methods using anthropological parameters on human teeth-(A0736). *Forensic Sci Int* 2006;162(1–3):13–16.

45 Kvaal SI. Collection of post mortem data: DVI protocols and quality assurance. *Forensic Sci Int* 2006;159 Suppl 1:S12–S14.

46 Meinl A, *et al.* On the applicability of secondary dentin formation to radiological age estimation in young adults. *J Forensic Sci* 2007;52(2):438–41.

47 Landa MI, *et al.* Application of the method of Kvaal *et al.* to digital orthopantomograms. *Int J Legal Med* 2009;123(2):123–8.

48 Ogino T, Ogino H, Nagy B. Application of aspartic acid racemization to forensic odontology: post mortem designation of age at death. *Forensic Sci Int* 1985;29(3–4):259–67.
49 Masters PM. Age at death determinations for autopsied remains based on aspartic acid racemization in tooth dentin: importance of postmortem conditions. *Forensic Sci Int* 1986;32(3):179–84.
50 Ritz S, Schutz HW, Schwarzer B. The extent of aspartic acid racemization in dentin: a possible method for a more accurate determination of age at death? *Z Rechtsmed* 1990;103(6):457–62.
51 Ohtani S, Yamamoto K. Age estimation using the racemization of amino acid in human dentin. *J Forensic Sci* 1991;36(3):792–800.
52 Ohtani S, Yamada Y, Yamamoto T. Improvement of age estimation using amino acid racemization in a case of pink teeth. *Am J Forensic Med Pathol* 1998;19(1):77–9.
53 Ritz-Timme S, *et al*. 'Improvement' of age estimation using amino acid racemization in a case of pink teeth. *Am J Forensic Med Pathol* 1999;20(2):216–7.
54 Waite ER, *et al*. A review of the methodological aspects of aspartic acid racemization analysis for use in forensic science. *Forensic Sci Int* 1999;103(2):113–24.
55 Ritz-Timme S, *et al*. Age estimation: the state of the art in relation to the specific demands of forensic practise. *Int J Legal Med* 2000;113(3):129–36.
56 Ohtani S, Yamamoto T. Strategy for the estimation of chronological age using the aspartic acid racemization method with special reference to coefficient of correlation between D/L ratios and ages. *J Forensic Sci* 2005;50(5):1020–7.
57 Dobberstein RC, *et al*. Degradation of biomolecules in artificially and naturally aged teeth: implications for age estimation based on aspartic acid racemization and DNA analysis. *Forensic Sci Int* 2008;179(2–3):181–91.
58 Sakuma A, *et al*. Comparative analysis of aspartic acid racemization methods using whole-tooth and dentin samples. *Forensic Sci Int* 2012;223(1–3):198–201.
59 Blau S, *et al*. Missing persons-missing data: the need to collect antemortem dental records of missing persons. *J Forensic Sci* 2006;51(2):386–9.
60 Chomdej T, Pankaow W, Choychumroon S. Intelligent dental identification system (IDIS) in forensic medicine. *Forensic Sci Int* 2006;158(1):27–38.
61 Brown KA. Procedures for the collection of dental records for person identification. *J Forensic Odontostomatol* 2007;25(2):63–4.
62 Beeley JA, Harvey W. Pink teeth appearing as a post-mortem phenomenon. *J Forensic Sci Soc* 1973;13(4):297–305.
63 Kirkham WR, *et al*. Postmortem pink teeth. *J Forensic Sci* 1977;22(1):119–31.
64 Clark DH, Law M. Post-mortem pink teeth. *Med Sci Law* 1984;24(2):130–4.
65 Brondum N, Simonsen J. Postmortem red coloration of teeth. A retrospective investigation of 26 cases. *Am J Forensic Med Pathol* 1987;8(2):127–30.
66 Van Wyk CW. Pink teeth of the dead: 1. A clinical and histological description. *J Forensic Odontostomatol* 1987;5(2):41–50.
67 Ikeda N, *et al*. A scanning electron microscopy and electron probe X-ray microanalysis (SEM-EPMA) of pink teeth. *J Forensic Sci* 1988;33(6):1328–31.
68 van Wyk CW. Postmortem pink teeth. Histochemical identification of the causative pigment. *Am J Forensic Med Pathol* 1989;10(2):134–9.
69 Sainio P, *et al*. Postmortem pink teeth phenomenon: an experimental study and a survey of the literature. *Proc Finn Dent Soc* 1990;86(1):29–35.
70 Borrman H, Du Chesne A, Brinkmann B. Medico-legal aspects of postmortem pink teeth. *Int J Legal Med* 1994;106(5):225–31.
71 Campobasso CP, *et al*. Pink teeth in a series of bodies recovered from a single shipwreck. *Am J Forensic Med Pathol* 2006;27(4):313–6.

CHAPTER 27

Poisoning and the Pathologist

- Introduction
- The concept of the fatal dose
- Variations in published fatal poison concentrations
- The autopsy in suspected poisoning
- Poisoning deaths in hospital
- The collection of autopsy samples for toxicological analysis
- Containers for toxicology samples
- Preservatives in samples
- The site of sampling for toxicological analysis
- The technique of obtaining autopsy samples
- References

Introduction

Toxicology has a number of different aspects and, in such a huge subject, various specialists have different interests. The clinical toxicologist is most concerned with diagnosis and treatment of the living patient; the analytical toxicologist has the complex task of laboratory investigation; and the pathologist is concerned with evaluating poisons as a cause or a contribution to death. Though obviously linked, these various aspects are substantially different and few people can claim to be proficient in all three. As far as the pathologist is concerned, his main task is to exclude or confirm other non-toxic factors in the death. He has then to collect suitable samples for analysis and, when the laboratory results are available, to interpret them in the light of his knowledge of the history, clinical features and autopsy appearances.

The pathologist inevitably needs the expertise of the laboratory analyst and the latter's knowledge of the therapeutic, toxic and fatal levels of the substances under consideration. Such data must, however, be evaluated in the knowledge of other pathological and physiological conditions present, so that it is the pathologist, rather than the laboratory toxicologist, who should provide the final opinion upon the proximate cause of death. This does not always happen and some laboratory report forms may be seen that unequivocally – and unwisely – state that a particular drug *caused* the death.

Where, as so often happens, the toxic levels found at post-mortem are not in a potentially fatal or even toxic range, then the pathologist should seek the advice of a clinical toxicologist to determine whether any of the symptoms or signs during life may assist in deciding on the cause of death. As so often happens in forensic problems, the investigation of a fatal poisoning must be a co-operative effort, especially between pathologist and laboratory analyst. Even in apparently obvious cases, such as a blood saturation of 50 per cent carboxyhaemoglobin, it is not for the analyst to declare a definite cause of death, as the victim may also have had a fractured skull – but equally, the pathologist has an obligation to provide the laboratory with the best possible samples in the best possible condition, as well as good information about the circumstances of the case.

The concept of the fatal dose

Many persons, including some doctors, are under the firm misapprehension that, for most toxic substances, there are relatively constant quantities that will cause death. Not only the lay public, but lawyers, police, coroners and others assume that there is a more or less linear relationship between the amount of poison that enters the body, the resulting levels in blood and tissues and the degree of disability caused – the ultimate disability being death.

In addition, it is often thought that back-calculation from blood and tissue levels can arrive at a definite assessment of how much poison was originally administered. This aspect is of particular concern to coroners and similar officers, who have to decide on motive in potential suicides, where the magnitude of any overdose may assist in distinguishing between accident and self-administration.

The pathologist has his own difficulties in respect of 'the fatal dose', as quantitative results from the laboratory have to be matched against a knowledge of published blood and tissue levels for that substance in relation to its potential toxicity. Though numerous tables of toxic levels have been published, there is considerable variation between the levels recorded. Reasons for this are explored later. It is obvious that there is no 'fatal dose' in the sense of a single threshold concentration above which a person dies and below which he survives. Instead, there is a range of levels, the upper and lower margins of which vary from one authority to another, which encompasses most deaths – but even here there are many exceptions, instances being recorded where survival occurs well above the upper limit and death occurs below the lower margin.[1] In such cases, the task of the pathologist – which cannot always be satisfactorily discharged – is to evaluate all other non-toxicological data to see if they can modify the circumstances sufficiently to allow an acceptable explanation for the death. It is sometimes difficult to explain these concepts of great biological variation to lawyers and police officers, who expect more definite decisions, and might even feel that the pathologist is being evasive or obstructive.

The concept of the 'LD_{50}' is sometimes raised by the more knowledgeable lawyer, but this does not assist materially in any individual case. The LD_{50} is a device used by pharmacologists and toxicologists in a statistical sense in animal experiments. Over a large number of tests, it provides a toxic level at which half the animals will be expected to die. Though the indicative value in a general sense in comparing the toxicity of one substance against another, there is no way of knowing whether the human victim of poisoning lies at the upper or lower end of the classical bell-shaped curve that characterizes most biological responses.

Far more useful is the cumulative record of actual laboratory results from toxicology centres that deal with human poisoning, which progressively build up a large database of blood and tissue levels, and correlate these with records of the clinical state, toxic effects and fatal outcome.[2–5] Even here the variations are wide, as the many published tables testify, but at least general guidance can be obtained.

Variations in published fatal poison concentrations

In the many publications that offer therapeutic, toxic and lethal ranges for a wide variety of poisonous substances, there is considerable variation in the quoted levels. These can be a source of confusion and sometimes dismay to the pathologist who, even with the advice of his local toxicologist, may find it difficult to decide whether a death can justifiably be attributed to a particular drug or other toxic substance. Even if he can so satisfy himself, he may be subjected to keen questioning, interrogation, doubt or criticism from colleagues, coroners, police, lawyers and others, who have access to different versions of toxic and fatal levels. The ultimate challenge may come in a criminal court, where opposing counsel may openly defy the pathologist's interpretations in cross-examination.

Dr A.R.W. Forrest, Chemical Pathologist and Toxicologist at Sheffield's Royal Hallamshire Hospital (personal communication) points out some reasons for the variations found in such published data. He expresses the view that it is rather surprising that the order of disagreement is not greater, given the opportunities for disparity.

First, many of the published series are small, some being only individual case reports. Statistically, this is not a good foundation for establishing reference ranges, which are much better obtained from a database derived from the cumulative results of a large laboratory service, such as the British Home Office Forensic Science Service, which maintains a central computer store of all results from its laboratories.

Second, analytical techniques vary widely, both in method and accuracy.[1] The specificity varies from laboratory to laboratory so that there may be a lack of uniformity about what is actually being measured. For example, paracetamol may be measured by a non-specific method that picks up its metabolites as well as the native drug, which will then offer a different blood level in a fatal case from that found by more specific methods. In other words, one is not comparing 'like with like'.

Third, as discussed elsewhere in this chapter, the site of sampling may introduce wide errors. With some substances, a several-fold variation in concentration may be found between femoral vein and cardiac cavity blood.[6–8]

Last, errors occur because a 'fatal' level may be attributed to one substance without taking into account the level – or even the existence – of other toxic substances that the deceased may have taken, and of which the pathologist or analyst may not even have been aware. For example, newer drugs may be missed in a simple toxicological screen, but could well have contributed to the toxicological overload that caused the patient to die. In such a case, the level of the recognized drug would be blamed for the death, whereas in fact it may not have been a lethal dose in itself, though was recorded as such in any database or tables.

These facts highlight the dangers of limiting a request for analysis solely to the substance known or thought to have been taken. Often an efficient screen for other substances will reveal other unsuspected compounds, sometimes more toxic than the one originally suspected.

It has to be recognized, however, that, in many jurisdictions, the availability and expense of toxicological investigations may make it impossible to pursue a full analytical survey, especially if this is to be undertaken on a speculative basis rather than for quantification of a known or strongly suspected toxic agent. A full screen may only be practicable and justified in a suspected homicide, if laboratory facilities and fiscal support are severely restricted. In many countries homicide by poison is relatively rare and the funds to investigate accidental, suicidal and iatrogenic poisoning exhaustively may just not be available.

The autopsy in suspected poisoning

The autopsy in these circumstances can be amongst the most difficult of problems faced by a forensic pathologist – not in the technical procedure of the examination, but in the final evaluation of all the available information.

The nature of the poisoning autopsy in Western countries has changed dramatically since the last century, when poisoning was a common method of homicide. There has been a marked change in the nature of poisons used in murder, suicide and accident. The corrosives, heavy metals and alkaloids commonly ingested in former years became relatively easy to detect, either by gross autopsy appearances or by straight-forward analytical methods. Further refinements of toxicological techniques, instead of the old methods in which large samples had to be tested because of the insensitivity of laboratory tests, allow the detection of picogram quantities.

Acids, alkalis, phenols, arsenic, antimony and strychnine, for example, became easy to detect, and in the Western world these gave way to compounds that leave little or no gross, or even histological changes in the body. Most are pharmaceutical or agrochemical substances, active in low dose compared to the old ‘blockbuster’ poisons. As for the majority of drugs used in legitimate medical therapy, an added problem arises when low post-mortem levels are found – is this merely a therapeutic dose or the tail-end of a declining lethal dose?

In some parts of the world, such as South-east Asia, Africa and the Indian subcontinent, poisoning remains common and more physically damaging substances continue to be seen that leave obvious autopsy lesions. Some of these are described under the appropriate headings in the succeeding chapters, but in most poisonings the major function of the autopsy is to evaluate any other conditions present, both from trauma and natural disease – but also to collect suitable material for laboratory analysis. The proper retention of optimal samples, their correct preservation and dispatch to the toxicologist are of such fundamental importance that they are discussed in detail.

Poisoning deaths in hospital

A considerable proportion of those who die from suspected poisoning will have died in hospital, and it is of prime importance that the medical records be obtained and studied before the autopsy begins. Even if poisoning was not confirmed or even suspected by the clinicians treating the patient, later information may have come to the pathologist to raise this possibility. Whether known or not, the results of ante-mortem investigations may be of considerable use to the pathologist. If poisoning was known or suspected before death, there may well have been toxicological analyses performed and the results of these may be of great value.

Whether poisoning was suspected or not, there may still be ante-mortem blood or urine samples (taken for biochemical or haematological tests) stored in the hospital laboratory, which may be rescued for retrospective analysis. Such ante-mortem samples are likely to be of greater use than fluids drawn off at autopsy, because of sampling defects, post-mortem changes and because toxic levels are likely to have been higher during life, representing more accurately the maximum toxic concentrations.

In addition, many patients dying in hospital from drug overdoses will have indwelling catheters in place. It is the common practice for the nursing staff to remove these at death and discard the urine. If it is possible to establish a practice in the wards where such terminal urine samples are saved, valuable material for analysis can be obtained.

The collection of autopsy samples for toxicological analysis

The investigation of a death from suspected poisoning may stand or fall upon the correctness or otherwise of the sampling of fluids and tissues from the body.

Unsuitable samples, inadequate amounts, incorrect sampling sites, poor containers, inadequate preservation methods and delayed or unsatisfactory storage and transport to the laboratory may frustrate or distort proper analysis. The final outcome may be wrong, either in failing to detect a poison actually present, in measuring only part of that originally present or – in some cases – even producing falsely high results that then lead to an incorrect cause of death. Not only must samples be in the optimal condition, but the accompanying information from the pathologist to the analyst needs to be as accurate and comprehensive as possible, so that the most appropriate techniques are used, and allowance made for any interfering substances that may be present.

In decomposed bodies infested with maggots, and in the absence of tissues or fluids normally taken for toxicology, *Diptera* and other arthropods can be used as alternative specimens for toxicological analyses. This relatively new field of forensic entomology is called entomotoxicology.[9–13]

The time of sampling

It is obvious that the shorter the delay between death and the removal of samples, the better. Though some toxic substances, such as carbon monoxide, form stable compounds in the body, many others (especially volatile substances and some pharmaceutical products) will be broken down by post-mortem autolysis and decomposition. When an autopsy cannot be performed quickly after death, in terms of a few hours, then mortuary refrigeration is the first line of defence to slow up putrefactive and autolytic processes. If delay is foreseen, usually because of administrative problems in obtaining consent or authority for autopsy, it may be possible to obtain a sample of blood through the body surface, such as puncturing the femoral vein by needle and syringe. The blood can then be kept in optimal conditions, with preservative where needed, and perhaps with the serum or plasma separated from the cells to avoid haemolysis. Similarly, urine could be drawn off by catheter or even suprapubic puncture, unless strict regulations forbid this as anticipating autopsy permission.

In some jurisdictions, authority for autopsy may be particularly hard to obtain, from religious, financial or administrative reluctance. Where poisoning is suspected, permission may be granted only for external examination and sampling; here venous blood, urine and perhaps vitreous humour may have to suffice for all investigations.

Information supplied to the laboratory

When samples are submitted to the toxicologist, they should be accompanied by the best possible information relevant to the case. It is both counterproductive and an unprofessional discourtesy merely to record the personal details of the deceased and list the samples, with a terse demand such as ‘Any poisons?’ on the request form. Such a demand could legitimately be refused by the toxicologist, as it is quite inadequate information upon which he can be expected to function effectively and safely. The following information should be supplied and where necessary, supplemented by direct discussion either in person or by telephone:

- The personal details of the deceased, including age, sex and where thought relevant, the occupation (especially if in agriculture or industry).
- Brief details of symptoms, if any, and length of illness.
- The post-mortem interval before samples were obtained, and the actual date and time of sampling.
- The name, address and telephone number of the pathologist.
- A list of all samples provided, with an indication of the sampling site for each.
- The nature of any preservative in each of the samples.
- If there has been a delay in submitting or transporting the samples, a note of the condition under which they have been stored (for example, refrigeration or deep-freeze).
- Any special risk associated with the samples **must** be communicated to the laboratory. The most obvious are infective conditions, especially hepatitis B or C virus or human immunodeficiency virus (HIV) infection in the deceased, though other diseases such as tuberculosis, tetanus, anthrax, gas gangrene or any other bacterial or viral condition must also be specifically reported. In relation to hepatitis and HIV, even if these are not definitely confirmed, the toxicology laboratory must be told if the deceased was in a high-risk group, such as a drug addict. In many areas, including Britain, some toxicology laboratories will not accept samples from such high-risk groups until a blood sample has been screened for hepatitis B and HIV antibodies; if positive, they may decline to carry out the analysis or perform it only under strictly controlled conditions.

  Similar warnings must be given to the analyst if there is any possibility of certain harmful substances, such as radioactive isotopes or certain war gases, being present in the samples.

- When a death has criminal aspects, such as a murder or manslaughter, then the usual strict precautions must be taken for continuity of evidence. Each container must be carefully labelled and preferably countersigned by the pathologist. Some jurisdictions will require actual seals on the containers themselves or the package into which they are placed for transport, or both. Accompanying signed 'exhibit labels' with serial numbers corresponding exactly with numbers on the jars may be required. The containers must be given by the pathologist to a named person, usually the 'exhibits officer' of the police investigating team (or to forensic scientists if they attend the autopsy). The police officer must hand the samples personally to a member of the laboratory staff and a record of this chain of evidence must be kept, so that there can be no criticism levelled at anyone when the matter comes to court, raising doubts about the correct identity of the sample.

Containers for toxicology samples

There will be considerable local variation in the type of containers used for the collection and transmission of samples to the laboratory. Some laboratories will issue their own kits, an example being those provided by the Home Office Forensic Science Service in England and Wales. These consist of a plastic bag containing a sheet of instructions about the most suitable samples, together with a large plastic pot with tightly self-sealing lid for liver, a smaller one for stomach contents, several plastic or glass 30 ml universal containers for blood and urine, a small vial containing fluoride for blood-alcohol estimation and a sterile syringe and several needles. Variations of such kits may be provided by different laboratories, but the general nature of the containers is the same. An example of such a sampling kit used in Finland is shown in Figure 27.1. In other areas, the pathologist will provide the containers himself and they should conform to the following general specifications:

- They should either be new or, if previously used for other samples, have been rigorously cleaned and sterilized. Even when they are new, it is preferable for containers to be washed and sterilized before use unless the manufacturer's specifications clearly make this unnecessary. All containers must be chemically clean, not just apparently clean to the naked eye. This applies particularly to any rubber, plastic or other seal within the lid or cap, which may be a trap for any debris or even residue from a previous sample.



Figure 27.1 Toxicology sampling kit provided by the Forensic Toxicology Division of the Department of Forensic Medicine of the Hjelt-Institute, University of Helsinki, where all post-mortem toxicology samples from forensic autopsies in Finland are investigated. Recommended routine samples for post-mortem toxicology include: 1) 10 ml femoral vein blood into fluorided vial; 2) 20 ml femoral vein blood into a larger vial without fluoride; 3) 10 ml urine into fluorided vial; 4) 20 ml urine into a larger vial without fluoride; 5) 2 ml vitreous humour into a fluorided vial; 6) 20 g liver; 7) 20 g stomach contents.

- Blood should be collected in screw-capped universal containers of about 30 ml or, where less will suffice, in plastic-capped tubes of about 5 ml. Urine is best held in 30 ml universal containers, as is bile. Stomach contents may be retained in glass or plastic jars with a volume of at least 250 ml, the lid being either a tight screw-thread with a cardboard or plastic liner, and a self-sealing plastic top. Some laboratories require the stomach wall as well as all the contents, as toxic substances may be held in higher concentrations in the rugae and crypts of the mucosa, or even in the blood in the actual stomach wall. The size of the container may need to be larger if the organ itself is retained. Liver is usually required, preferably a piece weighing 50 g, rather than the whole organ. The total weight of the liver should be communicated to the laboratory if only part is sent. It may be preserved in a larger glass or plastic container. When the laboratory wishes the whole organ, this container needs to be large enough to hold about 3 litres. If only small samples are needed, such as vitreous humour or cerebrospinal fluid (CSF), bijou bottles of 5 ml capacity or small tubes of similar size, are needed.

  Intestinal contents, with or without the gut itself, can be placed in large jars or plastic pots, similar to those used for liver.

Plastic containers, especially polypropylene, are increasingly used and have the advantage of not smashing when dropped. Some analyses, however, may be affected by the plasticizer in either the container wall or the cap – cocaine is an example. The advice of the toxicologist with whom each pathologist normally collaborates should be sought in respect of his individual preferences for containers. Where lungs or other tissues are to be submitted for analysis for volatile substances, as in solvent abuse, it is important to collect promptly and seal tightly the tissue specimen into a glass container, with a teflon- or aluminium foil-lined lid, as soon as possible after the body has been opened.[14]

Preservatives in samples

Though many samples for analysis are best sent in their original state, others require additives to maintain them in optimum condition until they reach the laboratory. In addition to such preservatives, some require anticoagulants to keep the blood fluid. The prime example of sample preservations is that for blood alcohol, as improper care of samples may distort the original alcohol level in either an upward or downward direction. The usual preservative is sodium or potassium fluoride, which is essential if the sample is not to be analysed within a few hours of withdrawal from the body.

Errors caused by post-mortem changes before the sample is removed cannot be avoided. These are variable, depending partly on the conditions of the post-mortem environment and partly on the microbiological population of the corpse. In warm conditions, fermentation by yeasts and other alcohol-producing flora can produce appreciable quantities of alcohol: it has been reported that as much as 150 mg/100 ml have been generated within 24 hours after death.[15–20]

Once the blood or urine has been withdrawn from the body, however, further changes can be arrested by preservatives. It would seem that for general use, a concentration of 1–2 per cent of sodium or potassium fluoride is satisfactory. Fluoride should also be added to urine and vitreous humour if alcohol estimations are required. Cocaine and its metabolites are also labile *in vitro*, and fluoride should be added to samples submitted for analysis for this drug.

Cyanide may be formed in considerable quantities in plain blood samples, which are of little use for cyanide estimation. Fluoride should be added to such specimens, as well as for carbon monoxide (carboxyhaemoglobin) if the analysis is to be delayed. In all analyses for pharmaceutical drugs, two samples of blood should be submitted, one plain in large volume of at least 25 ml and another smaller sample in fluoride.

When insulin assay is required on a blood sample, special precautions should be taken. Haemolysis of the red cells releases enzymes which will reduce the S–S bonds in insulin and destroy its immunoreactivity, so the sample should be centrifuged as soon as it is obtained to separate the serum. A heparinized sample should also be taken for glycosylated haemoglobin estimation and fructosamine assay. Vitreous humour, blood and urine samples should be placed in fluoride and sent for glucose estimation, as well as tissue samples from around any putative injection site, together with a control tissue sample from a site elsewhere on the body where insulin is unlikely to have been recently injected.[8]

The site of sampling for toxicological analysis

It is now obvious that, in the past, serious errors were made in toxicological analyses from lack of care or consideration concerning the source of body-fluid samples. Significant variation can be found in the concentration of many substances depending on the place from which sampling was carried out. In life there may be variations when arterial as opposed to venous blood is used, as tissues may take up the compound from the arterial supply, the concentration then being lower in the venous return. Similarly, portal blood may have a substantially higher concentration of a substance that is being absorbed from the intestine, before it is extracted by passage through the liver. After death, most variation is caused by uneven destruction by enzymatic and microbiological activity – and by diffusion from sites of higher concentration. The barriers formed by living cell membranes break down after death and small molecules in particular may move easily through the tissues into vascular channels.

Post-mortem levels of many substances are unreliable because of this diffusion effect, making the interpretation of physiological components, such as sodium, potassium, calcium, glucose, urea and many others extremely difficult, if not impossible. Applying these facts to toxic compounds, the concentrations may vary considerably according to the sampling site. As an illustration, the Moorgate Tube disaster in London showed that blood-alcohol levels may vary widely between different sampling points. The driver of an underground train was killed, along with a number of passengers, but his body could not be recovered from the warm environment for several days. As it was obviously vital to know if drink had contributed to the accident, four samples were taken from various sites in the body. On analysis, a fourfold variation from between 20 and 80 mg/100 ml was obtained, presumably because of variable rates of putrefactive alcohol production, as there was no evidence to show that the driver had imbibed alcohol before death.[21]

Most research in respect of sampling variation has been directed at alcohol. One point of dispute, which is relevant even when post-mortem changes are minimal, is whether alcohol in the stomach can diffuse after death to neighbouring organs and produce a falsely elevated alcohol concentration in blood at those sites.

The relevance is clear, in that, if a person drinks alcohol immediately before death, there will be insufficient time for it to be absorbed. Thus ethanol remaining in the stomach after death cannot have contributed to his ante-mortem blood-alcohol level, and hence his cerebral function and consequent behaviour. If however, analysis of a sample of blood taken from the heart cavities is contaminated by post-mortem diffusion from the adjacent stomach, then a falsely high reading will be obtained, which may have serious legal implications, if the error is not appreciated.

Several workers have investigated this problem, with conflicting results. Gifford and Turkel introduced alcohol into the stomachs of cadavers and found that subsequent heart blood levels increased by 25–106 mg/100 ml.[22] They then compared femoral vein blood with heart blood voided into the pericardial sac in alcohol-positive autopsies and found that the concentration in the latter was higher. Plueckhahn and Ballard, however, criticized this work on the grounds that pericardial fluid alcohol was usually about 20 mg/100 ml higher than that in the heart or peripheral vessels.[23] Plueckhahn went on to instil alcohol into the stomach of cadavers, taking multiple site samples at times from 6 to 50 hours later. His results indicated that there was a significant diffusion of alcohol to the pericardial and pleural fluids, but that the increase was minimal in intraventricular heart blood.

Pounder and Yonemitsu carried out experiments with dead bodies in which they introduced a slurry containing alcohol, dextropropoxyphene and paracetamol into the trachea to simulate aspiration of stomach contents.[24] After a delay of 48 hours, an autopsy was carried out and drug concentrations measured in samples taken from various sites. While femoral vein blood remained clear of these substances, samples from vessels in the thorax showed up to 130 mg/100ml of alcohol with a mean of 58 in a pulmonary vein – and up to 1934 mg/l of paracetamol (mean 969), both obviously spurious due to post-mortem diffusion. This situation could have occurred from agonal regurgitation of stomach contents with recently swallowed drugs back into the air passages and shows the dangers of inappropriate sampling sites, with the femoral the place of choice.

Winek *et al.* have shown that, in the sampling practice of transthoracic needling, especially in cases of trauma where the gastrointestinal tract has been damaged, false elevations of blood alcohol can occur.[25] These workers used heart blood as their control, which itself seems suspect as a satisfactory autopsy sample.

For the reasons given above, *peripheral* vein blood should be used whenever possible, avoiding heart blood as a potential source of error for alcohol and presumably other easily diffusible substances.

The technique of obtaining autopsy samples

Blood

There are several ways of obtaining blood samples at autopsy and perhaps the most useful advice is what **not** to take. Blood should never be obtained from body cavities after evisceration, as it is almost certain to be contaminated with other body substances. The practice of scooping 'blood' – or more accurately, bloody fluid – from the paravertebral gutters or the pelvis is always unacceptable, as urine, intestinal contents, gastric contents, lymph, pleural and ascitic fluid and general tissue ooze will always find their way into such a sample and negate the reliability of analysis.

When a large haemothorax or haemopericardium is present, it may be grudgingly acceptable to use such blood or clot, if a clean sample is taken immediately on opening the chest, before any dissection or disturbance of organs is made. This is only second best to obtaining intravascular blood – and, in the case of alcohol and other diffusible substances, the results cannot be relied upon, as the sample may be contaminated by post-mortem diffusion from the stomach, as discussed in the preceding section. Carbon monoxide estimations may also be made on clean cavity blood, if nothing else is available, as sometimes happens in a badly incinerated body. As it is absorbed through the lungs, it cannot diffuse from the gastrointestinal tract to give a false result. Even so, it is a rare autopsy that cannot provide a small sample of blood from some peripheral vein, if enough care and persistence is used.

To return to the general state of affairs, the most satisfactory way of obtaining a venous blood sample is to dissect the femoral vein before the autopsy begins and tie the vessel off proximally before drawing blood. This is necessary to avoid drawing blood from the groin and abdominal region that may be subject to post-morten redistribution. Practice is required as, unlike a living patient, the vein is not usually palpable. Once the lumen is entered, 25 ml can usually be drawn off without trouble, though a slow flow may be improved by massaging the leg to drive blood proximally or the leg may be raised, if rigor allows. Though less satisfactory than a leg vein, for reasons discussed earlier, a neck vein can also be punctured through the skin, and even after death the jugular may sometimes be both visible and palpable, especially in congestive deaths. The subclavian vein can also be tapped.

When collecting blood samples by percutaneous puncture, some pathologists prefer to use a needle designed for aspirating samples from rubber-capped vials, rather than a needle meant for clinical aspiration or injection. The same needles can be used for collecting vitreous humour. An example of this type of needle is the Becton Dickinson purple-hubbed 16 gauge one-inch or a similar American equivalent.

In some jurisdictions, especially in countries where the system allows only a low autopsy rate, transcutaneous sampling is virtually the only post-mortem investigation possible and the doctors in these areas become adept at cadaver venepuncture. Many pathologists, the authors included, have been brought up to obtain blood samples during the actual performance of autopsy and this can be as satisfactory as external venepuncture, as well as saving the expense of a new syringe and needle every time. A common procedure after evisceration is to transect the femoral or external end of iliac near the brim of the pelvis, hold a container (such as the 30 ml universal) under the severed vein while the leg is elevated, or massaged, or both. Similarly, the subclavian vein may be transected and a container held under the cut within the upper part of the empty thorax. The arm is then elevated and massaged if necessary, to express blood into the container. Either of these methods will provide ample, clean, peripheral venous blood, though care must be taken to avoid any contamination from the body cavities. This initial collection should be transferred into one or more new tubes, with preservative added if appropriate, as the first receptacle will be soiled externally during the collection process.

An alternative method of collecting a venous sample, which always gives a copious flow of blood, is to incise the internal jugular vein during the initial stages of the autopsy. As soon as the main autopsy incision is made, the flaps of the neck skin can be dissected aside and the jugular exposed, if necessary by dividing the sternocleidomastoid muscle. As in the previous technique, a bottle can be held against the vein as it is transected and the flow collected directly into it. The blood may overflow into the pouch formed laterally by the reflected skin, which forms a reservoir where a considerable volume may collect. If the flow is scanty, it can be improved by raising and lowering the head, which will cause blood to return from the upper venous drainage areas.

Even more can be expressed by pressing on the chest, but here there is the potential disadvantage of forcing up blood through the superior vena cava from the heart, which may distort the value of alcohol and other drugs that may have diffused port-mortem from the stomach. Blood should not be taken from the heart cavities, the inferior vena cava or the portal or hepatic veins, as these may also give concentrations that are at variance with those in the peripheral vascular system. A full 30 ml of blood should be submitted to the laboratory wherever possible, together with a 5 or 10 ml fluorided sample.

Urine

Prior to, or in the absence of, an autopsy, urine can be obtained by catheter or suprapubic puncture with syringe and long needle. At autopsy it is usual to wait until evisceration has been carried out before dealing with the bladder. A sample can be obtained by puncturing the fundus with syringe and needle. Alternatively, the bladder can be stretched by pulling the fundus upwards with the fingers, then a sagittal incision made with a knife on the ventral surface, which must be free from blood soiling. The urine that wells out can be collected directly into a small container such as a 30 ml universal. If only a small amount is present, then the incision may have to be enlarged and the residual urine sucked out under direct vision, using a syringe without a needle.

Bile

With older analytical methods bile was useful for some analyses, such as those for morphine and chlorpromazine, which are concentrated by the liver and excreted into the gallbladder. Direct collection into a bottle is advised, as bile is usually too viscous to be sucked through a needle.

Cerebrospinal fluid

This is not often required for toxicological analysis, though it may be needed for microbiological and virological studies. If needed, it should be collected by lumbar or cisternal puncture, as in the living patient. It can be difficult or impossible to obtain in this way because of the lack of any intrathecal pressure.

The body should be turned on to its side before the autopsy begins and flexed as much as possible by an assistant. If an infant, it should be sat up and again flexed forwards to curve the spine as much as possible. A needle on a syringe should then be passed between two lumbar or lower thoracic spines, and stopped as soon as any penetration of the theca is felt. Moderate suction should be maintained on the syringe piston to compensate for the lack of internal pressure. Alternatively, the needle should be passed into the midline just below the occiput and advanced upwards until the skull is contacted just posterior to the foramen magnum. The needle is slightly withdrawn and re-advanced until it slips through the posterior part of the atlanto-occipital membrane into the basal cistern when CSF may be aspirated. It is of little use taking CSF from the bowl of the posterior fossa after the brain has been removed as the concentration of many substances is different in blood compared with the fluid, so blood contamination distorts any results. Clear CSF may, however, sometimes be obtained from the lateral ventricles, either by needle puncture or cutting down through the cortex.

Vitreous humour

This is sometimes useful, especially in bodies with appreciable post-mortem decomposition, as the fluid in the eye resists putrefaction longer than other body liquids. Vitreous fluid is also used for estimating the time since death (see Chapter 2) (see Fig. 2.35).

A puncture should be made through the sclera at the outer canthus with a fine-gauge needle. This should be placed as far laterally as possible, pulling the lid out, so that when released it returns to cover up the puncture mark for cosmetic reasons. The fluid should be sucked out by syringe, but it will often come only slowly because of its viscosity. If the best restoration is needed, water should be reinjected through the same needle to reinflate the globe, which tends to collapse on suction.

Stomach contents

As stated earlier, these can be collected directly into wide-mouth glass or plastic pot of at least 250 ml volume. To collect them, the exterior of the stomach should be washed clean of blood and other contamination, and pulled with attached organs to the edge of the dissecting board or sink. The greater curvature should be opened cautiously with large scissors, and the jar held underneath so that the contents flow directly into it (see Fig. 1.19). When most have been expressed, the greater curvature can be opened up fully and the gastric lining examined. Any further contents are scraped out and any powder, capsule or tablets picked off, and either added to the main jar or placed in a separate small container. Such focal deposits form a more concentrated sample for the laboratory. Any undissolved tablets or capsules should be carefully preserved, as the laboratory or a pharmacist may be able to identify them by their appearance and colour. After the mucosa has been examined, including that of the duodenum, the stomach wall can be dissected off. Some laboratories require this for their analysis, either added to the jar of contents or sent separately. The wishes of each individual toxicologist should be discovered in advance.

Intestinal contents

These are not routinely required for analysis unless some particular gastrointestinal poison is suspected, such as one of the heavy metals. Again, the toxicologist should be consulted. If required, both ends of the small gut should be ligated by string sutures at duodenum and ileum. The intestine is cut through at these points and stripped out by cutting through the mesentery in the usual way. The intact gut can be sent to the laboratory in a large container (such as that used for liver) or – if the mucosa needs to be examined first – it should be opened in a large clean tray. One suture can be cut and the contents milked from one end to the other into a suitable jar, the gut then being opened and sent with the contents to the laboratory. The large intestine and contents are rarely required, as most toxicology laboratories are not keen on handling and storing large volumes of faeculent material. In heavy-metal poisoning, such as arsenic and antimony, however, some analysis may be required.

Vomit

This is rarely collected at autopsy, unless a large quantity has been found in the air passages. However, vomit is not infrequently collected by ambulance crews and police at the scene of the illness or agonal event, and brought with the deceased to hospital or the mortuary. If thought relevant in a case of suspected poisoning, it should be properly contained, labelled and forwarded with other samples for toxicological examination.

Other fluids

Other fluids are rarely collected, but on occasions may be useful, especially if clean blood cannot be obtained. Pericardial fluid, synovial fluid, pleural effusion and ascitic fluid can be used for qualitative analysis to identify a range of substances, though these levels can rarely be related to established ranges of blood concentrations. They may be collected and transported in the same type of container and with the same preservatives as vitreous humour.

Analysis for volatile substances

In solvent abuse and deaths from gaseous or volatile substances, the toxic material may be isolated from a whole lung. As soon as the thorax is opened at autopsy, a lung is mobilized and the main bronchus tied off tightly with a string ligature. The hilum is then divided and the lung placed immediately into a glass container, which is sealed with a teflon- (polytetrafluorethylene) or aluminium foil-lined lid and sent as soon as possible to the laboratory. Ordinary plastic (polythene) bags are not suitable for this task, as they are permeable to volatile substances.

In collecting blood samples for volatile substances, plastic tubes or tube/syringe combinations of the ‘monovette’ type are unsuitable, as the concentration of such compounds as toluene or other solvents will decrease considerably over a few days in storage. Vials with a rubber septum as a seal are also unsuitable, as the volatile substance can escape through the rubber. Suitable tubes are made of glass with an aluminium foil-lined cap or a teflon liner. This type of tube is often used in laboratories for scintillation counting and can be employed for the collection of solvent samples. Such tubes should be available in any busy autopsy room where solvent abuse deaths may be handled. The tubes should be filled to the top to avoid loss of volatile substances into the head space and should be stored at 4°C, rather than being frozen solid.

Body tissues

Body tissues may be needed for some toxicological analyses. Liver is the most usual, as it concentrates many substances and their metabolites, which may then be recoverable long after the blood and urine levels have declined. Either the whole organ is saved or an aliquot of 50–100 g, according to the wishes of the particular laboratory. If only a part is retained, it should be taken from the periphery, away from major vessels and bile ducts.

Brain and kidney may sometimes be required and again a 50–100 g aliquot is usually sufficient. As with liver, the total original weight of the organ should be recorded and notified to the toxicologist.

Where a toxic substance may have been injected into the subcutaneous tissue or muscle, these tissues should be excised and submitted to the laboratory. The usual method of identifying the site is from a needle puncture mark, and a zone of skin and tissue should be removed circumferentially around this or an ellipse cut away, so that the defect can be sewn up on the body. A few centimetres in diameter around the mark is usually sufficient. The depth of the sampling depends on how deeply the needle track extends and may need to go into the underlying muscle. Radiography may assist in rare cases, as in the George Markov murder in London, where a political assassination was carried out by the introduction of a tiny sphere, presumably injected from an air weapon concealed in an umbrella.[26] The sphere, drilled out to carry a potent toxin, probably ricin, was located by X-ray at autopsy after a small skin puncture was found. Where an injection site is sampled, it is essential that a control area from a remote part of the body is also sent to the laboratory. It is usual to take this from a symmetrical zone on the contralateral side, but caution must be used, as in both drug dependence and insulin usage, alternate sides may be used at frequent intervals for injection, so another more remote site might be preferable.

The substances which may have been injected are numerous, but insulin, morphine, heroin, cocaine and other illicit drugs are most common.[27–37] In the notorious Coppolino case in the USA, products of succinylcholine (suxamethonium) were identified from around a needle track in the buttock of an exhumed body of a female, leading to the conviction of her anaesthetist husband for murder.

References

1 Ferner RE. Post-mortem clinical pharmacology. *Br J Clin Pharmacol* 2008;66(4):430–3.

2 Druid H, Holmgren P. A compilation of fatal and control concentrations of drugs in postmortem femoral blood. *J Forensic Sci* 1997;42(1):79–87.

3 Jones AW, Holmgren A. Concentration distributions of the drugs most frequently identified in post-mortem femoral blood representing all causes of death. *Med Sci Law* 2009;49(4):257–73.

4 Schulz M, *et al.* Therapeutic and toxic blood concentrations of nearly 1,000 drugs and other xenobiotics. *Crit Care* 2012;16(4):R136.

5 Launiainen T, Ojanpera I. Drug concentrations in post-mortem femoral blood compared with therapeutic concentrations in plasma. *Drug Test Anal* 2014;6(4):308–16.

6 Jones GR, Pounder DJ. Site dependence of drug concentrations in postmortem blood – a case study. *J Anal Toxicol* 1987;11(5):186–90.

7 Pounder DJ, Jones GR. Post-mortem drug redistribution – a toxicological nightmare. *Forensic Sci Int* 1990;45(3):253–63.

8 Jones GR. Postmortem specimens. In: Siegel JA, Saukko PJ (eds). *Encyclopedia of Forensic Sciences*. Waltham: Academic Press, 2013, pp. 270–4.

9 Goff ML, Lord WD. Entomotoxicology. A new area for forensic investigation. *Am J Forensic Med Pathol* 1994;15(1):51–7.

10 Gagliano-Candela R, Aventaggiato L. The detection of toxic substances in entomological specimens. *Int J Legal Med* 2001;114(4–5):197–203.

11 Introna F, Campobasso CP, Goff ML. Entomotoxicology. *Forensic Sci Int* 2001;120(1–2):42–7.

12 Tracqui A, *et al*. Entomotoxicology for the forensic toxicologist: much ado about nothing? *Int J Legal Med* 2004;118(4):194–6.

13 Gosselin M, *et al*. Entomotoxicology, experimental set-up and interpretation for forensic toxicologists. *Forensic Sci Int* 2011;208(1–3):1–9.

14 Skopp G. Postmortem toxicology: artifacts. In: Siegel JA, Saukko PJ (eds). *Encyclopedia of Forensic Sciences*. Waltham: Academic Press, 2013, pp. 292–9.

15 Nicloux M. Neoformation d' alcool ethylique dans le cadavre humain en voie de putrefaction. *Compte Rendu des Séances de la Societé de Biologie* 1936;121:975–8.

16 Wagner K. Über die veränderlichkeit des alkoholgehaltes von leichenblut und nicht steril aufbewahrten blutproben. *Dtsch Z ges gerichtl Med* 1936;26(1–3):276–92.

17 Corry JE. A review. Possible sources of ethanol ante- and post-mortem: its relationship to the biochemistry and microbiology of decomposition. *J Appl Bacteriol* 1978;44(1):1–56.

18 Lewis RJ, *et al*. Ethanol formation in unadulterated postmortem tissues. *Forensic Sci Int* 2004;146(1):17–24.

19 Ziavrou K, Boumba VA, Vougiouklakis TG. Insights into the origin of postmortem ethanol. *Int J Toxicol* 2005;24(2):69–77.

20 Kugelberg FC, Jones AW. Interpreting results of ethanol analysis in postmortem specimens: a review of the literature. *Forensic Sci Int* 2007;165(1):10–29.

21 Cox HJ, Rutter LF. Letter: Moorgate tube disaster: disputed alcohol findings. *Lancet* 1975;1(7914):1036–1.

22 Gifford A, Turkel M. Diffusion of alcohol through stomach wall after death. *JAMA* 1956;161:866–8.

23 Plueckhahn VD, Ballard B. Factors influencing the significance of alcohol concentrations in autopsy blood samples. *Med J Aust* 1968;1(22):939–43.

24 Pounder DJ, Yonemitsu K. Postmortem absorption of drugs and ethanol from aspirated vomitus–an experimental model. *Forensic Sci Int* 1991;51(2):189–95.

25 Winek CL, Jr, Winek CL, Wahba WW. The role of trauma in postmortem blood alcohol determination. *Forensic Sci Int* 1995; 71(1):1–8.

26 Musshoff F, Madea B. Ricin poisoning and forensic toxicology. *Drug Test Anal* 2009;1(4):184–91.

27 Koskinen PJ, *et al*. Importance of storing emergency serum samples for uncovering murder with insulin. *Forensic Sci Int* 1999;105(1):61–6.

28 Marks V. Murder by insulin. *Med Leg J* 1999;67(4):147–63.

29 Marks V, Richmond C. Kenneth Barlow: the first documented case of murder by insulin. *J R Soc Med* 2008;101(1):19–21.

30 Samuels A. Murder by insulin. *Med Leg J* 2008;76(1):34.

31 Marks V. Insulin murders. *Med Leg J* 2009;77(2):39–47.

32 Marks V. Murder by insulin: suspected, purported and proven – a review. *Drug Test Anal* 2009;1(4):162–76.

33 Maltby, J.R., *Criminal poisoning with anaesthetic drugs: murder, manslaughter, or not guilty.* Forensic Sci, 1975. 6(1-2): p. 91-108.

34 Bailey, D.N. and R.F. Shaw, *Cocaine- and methamphetamine-related deaths in San Diego County (1987): homicides and accidental overdoses.* J Forensic Sci, 1989. 34(2): p. 407-22.

35 Dyer, C., *Public inquiry hears how Shipman killed patients with diamorphine.* BMJ, 2001. **322**(7302): p. 1566.

36 Smith, J., *The Shipman Inquiry, First Report*. 2002. p. 336.

37 Pounder, D.J., *The case of Dr. Shipman*. Am J Forensic Med Pathol, 2003. 24(3): p. 219-26.

This page intentionally left blank

CHAPTER 28

Forensic Aspects of Alcohol

- Introduction
- Mode of action of alcohol
- Absorption of alcohol
- Elimination of ethanol
- Alcohol concentrations: units and various drinks
- Physiological effects of alcohol
- Modes of death in acute alcoholism
- Chronic alcoholism
- Methyl alcohol
- References

Introduction

Ethyl alcohol is the most commonly used drug in the world and has such numerous points of contact with medico-legal pathology that it has to be considered separately from all other substances. Its abuse is a prime factor in many accidents – transport, domestic and industrial – and the majority of homicides are catalysed by alcohol intake. It acts as an adjuvant to many other toxic substances, combining to cause a fatal outcome where often the other drug alone would not have caused death. The chronic abuse of alcohol leads not only to definite pathological changes in a number of target organs, but also contributes to deaths from neglect, hypothermia and burns.

This central role in forensic practice makes it imperative that a comprehensive knowledge of its metabolism and effects is held by every forensic pathologist, not only for an understanding of autopsy appearances, but to be able to assist investigative authorities to place the death into its alcoholic context.

Mode of action of alcohol

Ethanol is a small molecule that is easily miscible with water and therefore quickly diffuses through the whole of the aqueous compartment of the body.

There are slight variations in the intracellular concentration in different tissues – for instance, the red blood cells contain somewhat less alcohol than plasma, so that a whole-blood concentration is slightly less than that in separated plasma or serum. Most serous fluids are in equilibrium, however, though Plueckhahn claims that pleural and pericardial fluids have a higher concentration than that of plasma.[1]

The aqueous humour of the eye is in equilibrium with blood, as is cerebrospinal fluid, given sufficient time for equilibration.

It is said above that alcohol disperses rapidly through the aqueous compartment and this excludes the adipose tissues, as ethanol is almost insoluble in fat. This fact has important practical significance, as people with large fat stores will produce a higher blood-alcohol level for a given intake of alcohol than persons of the same weight who are lean, as the aqueous compartment is smaller. This is particularly relevant to females, who, by virtue of their **panniculus adiposus**, may develop blood-alcohol concentrations at least 25 per cent higher than males of the same body weight after similar drinks. This must be allowed for in all calculations that attempt to relate blood-alcohol levels to intake of drink.

The behavioural effect of alcohol is caused by its action on brain cells and is a function of the concentration in the blood, the alcohol readily passing the blood–brain barrier to bathe neurons via the cerebral extracellular fluid. The action of alcohol is entirely depressant, a fact not always appreciated by those who observe the apparent excitant effect of drinking. Alcohol acts on neural cells in a way similar to hypoxia, reducing their activity. In lower concentrations, this action is confined to the more specialized and sensitive cells of the cerebral cortex, leaving lower brain functions relatively unaffected. The consequent depression of these higher areas releases their inhibitory tone and thus ‘takes the brakes off’ more primitive and unrestrained behaviour. This was aptly described by Thomas de Quincey (1785–1859) when he wrote that 'sobriety disguiseth man'!

With increasing concentrations of ethanol, progressively lower levels of brain function are depressed and, when the vital centres in the midbrain and medulla are affected, there is a danger of fatal cardiorespiratory failure. Alcohol also causes changes in the heat regulatory mechanism, both centrally and by a vasomotor effect. Generalized vasodilatation occurs, especially in the skin, which may lead to marked heat loss and dangerous hypothermia. There is an increase in heart rate with low concentrations but, when alcohol levels approach the dangerous ranges in excess of 300 mg/100 ml, bradycardia may develop. A slight and inconstant increase in blood pressure may occur, more often in the systolic level, which increases the pulse pressure between systolic and diastolic. There is no evidence to support the contention that alcohol dilates the coronary arteries and claims that it causes dilatation of cerebral arteries (and thus worsens intracranial haemorrhage) are also equivocal. Alcohol also has a diuretic effect and, when combined with large quantities of fluid, as in excessive beer drinking, may lead to electrolyte disturbances. In healthy test subjects short-term alcohol administration causes transitory hypoparathyroidism, accounting, at least in part, for the transient hypocalcaemia, hypercalciuria and hypermagnesiuria. In alcoholic patients especially hypomagnesaemia is common.

Absorption of alcohol

For all practical purposes, it may be assumed that the only route of absorption of alcohol is by mouth as, although it can be inhaled, situations where this occurs must be rare indeed. One case is known to the author (PS), in which a male suffering from a tumour of the base of the tongue, probably causing difficulties in swallowing, had instilled fruit brandy rectally via a plastic tube using a pump, and dying as the result of acute alcohol poisoning.

Almost as soon as the alcohol is swallowed, it begins to be absorbed into the blood – and as soon as that blood reaches the liver, the alcohol begins to be eliminated. Therefore the blood level (and hence the brain concentration) is a dynamic balance between absorption and elimination, the peak determining the maximum behaviour effect. Such a balance is often represented graphically by the 'blood-alcohol curve', which indicates the intensity and duration of physiological effects.

Ethanol is capable of being absorbed by any part of the gastrointestinal canal, but in practice this is confined to the stomach and upper small intestine, as only a little alcohol remains to pass through the wall of the ileum or colon. When alcohol is taken with food, however, there seems to be a deficit in the amount absorbed, as some never appears in the bloodstream. Most of the alcohol is metabolized by the liver, and less than 10 per cent is excreted in breath, sweat, and urine.[2] When absorption is slow, more may be destroyed by the liver directly from the portal blood, never surviving to enter the systemic circulation. Owing to a thinner mucosa, a better blood supply and a larger surface area, the upper small intestine – the duodenum and jejunum – has the maximum capacity for absorption, compared with the gastric mucosa. This has practical implications, as drink taken by mouth will be absorbed more quickly when:

- a gastrectomy or gastroenterostomy has been carried out previously, as the drink will pass rapidly through to the upper small intestine
- the stomach is empty, as fluid will pass through the pylorus with almost no delay.

Conversely, when the stomach contains food, the drink will be held up until digestion has proceeded sufficiently for the contents to be released into the duodenum.[3] A fatty meal will slow this process down even more and milk feed also has a marked delaying effect. Obviously some absorption will still occur in the interim via the gastric mucosa, but not at the same high rate as in the duodenum and jejunum. As well as delaying emptying, a full stomach will retard absorption by mixing with the alcohol and physically reducing its access to the gastric lining where transit into the blood takes place.

Another factor in the speed of absorption is the concentration of the alcohol.[4–8] A strength of about 10–30 per cent is thought to be optimum for rapid absorption, which is met (in an empty stomach) by sherry or port wine, or spirits diluted with a 'mixer', such as gin and tonic or whisky and soda.[9] It is also said that carbonated drinks (those containing dissolved carbon dioxide, such as champagne, tonic or soda water, or lemonade) hasten absorption. However, Ploutz-Snyder *et al.* demonstrated using magnetic resonance imaging (MRI) that gastric gas volumes vary markedly with the carbonation level of the ingested beverage and when total gastric content increases, fluid emptying is retarded.[10]

According to Roine in the fasted state, concentrated beverages produce equal or higher BACs than diluted beverages, whereas the opposite is true when alcohol is consumed with or soon after a meal.[7] Very strong drink slows the rate of transfer into the bloodstream. Neat spirits or liqueurs, which may be in excess of 40 per cent alcohol, cause:

- pyloric spasm and hence retarded emptying into the duodenum
- irritation of the gastric lining, forming a barrier of mucus, which slows absorption
- reduced gastric motility, which also retards emptying.

Given an empty stomach and an optimum concentration of alcohol, most of the drug will have entered the bloodstream between 30 and 90 minutes after drinking. According to research by Wilkinson *et al.*, the average times to reach peak blood concentration were 22, 40, 55 and 60 minutes after drinking 11, 22, 36 and 45 g of alcohol in a bolus of similar volumes.[11]

It has been calculated that 98 per cent of alcohol drunk would be absorbed within 10 minutes if it went straight into the small intestine – most of the delay is due to hold-up in the stomach. Rates vary greatly among different people and even in the same person at different times, irrespective of food being taken, but an acceptable mean time would be that 60 per cent of the imbibed alcohol would be absorbed within 60 minutes and 90 per cent within 90 minutes.

Food in the stomach can, however, at least double these times and a large fatty meal can delay total absorption for a number of hours. This has an important effect on the dynamic state between absorption and elimination, as the rate of the latter is relatively constant (see below) and can therefore deal with the slow delivery of alcohol from the portal blood so effectively that the peak of the BAC is low – indeed the curve becomes a long shallow curve instead of a sharp hillock. Where there is a legal threshold for blood alcohol in relation to driving, the taking of food can easily cause one person who has had a large meal to remain well under this limit, whereas another person who drank the same amount at the same time may rapidly exceed the threshold if he drank on an empty stomach. Incidentally, the same effect can occur, notwithstanding food, where a male and female drink the same amount, as described earlier.

Some drugs will affect absorption rates, by modifying the speed of stomach emptying.[12] Atropine, chlorpromazine, tricyclic antidepressants, procyclidine, amphetamines, morphine, antidiarrhoea compounds, codeine, methadone, heroin, pethidine, etc., will delay gastric transit, whilst the antiemetics cisapride and metoclopramide, as well as the antibiotic erythromycin, will hasten stomach emptying.

Elimination of ethanol

Almost all alcohol is detoxified by the liver, only 2–10 per cent being excreted unchanged. This means that a heavy drinking session places a great metabolic burden upon the liver and is the cause of hepatic damage after long-standing drinking. The elimination mechanism is an oxidation of alcohol by liver enzymes, through acetaldehyde to acetate. The first stage is performed by the enzyme alcohol dehydrogenase but, as the second stage is much more rapid, little acetaldehyde has time to accumulate. The acetic acid is rapidly oxidized further to carbon dioxide and water. Some may also be broken down by a microsomal oxidase system.

The rate of elimination is of crucial importance to the shape of the BAC, the height of its peak and to the duration of the alcoholaemia. It is also central to any attempts at retrospective calculations of blood, breath or urine levels, as discussed later. Whereas the rate of absorption is variable and is affected by a number of factors, the speed of detoxification in the liver is much more constant and relatively independent of external influences. This is not to say that it is fixed and immutable, even in the same person at different times, but it is capable of reasonable approximation. Much experiment and research has been devoted to this topic and the results, though variable, lie within a fairly narrow band. A recent meal may increase the rate of alcohol elimination (AER). According to Ramchandani *et al.* the AER showed a significant average 45 per cent increase following the meal, regardless of composition, compared with that following fasting. They considered food-induced increases in hepatic blood flow and in the activity of alcohol-metabolizing enzymes as probable mechanisms for the increased alcohol elimination rate.[13]

Holford reviewed 11 different studies and found average rates varying between 12.6 and 26.8 mg/100 ml/h.[14] Neuteboom and Jones looked at levels in 1300 drivers stopped by the police, and calculated rates between 12 and 38 mg/100 ml/h in 95 per cent of subjects.[15] Several had rates over 48 mg/100 ml/h. The AER appeared to increase as the net blood concentration increased, for which several explanations are possible.

As a generalization, it has traditionally been assumed that blood alcohol declines, after the peak is reached, at a rate of around 15 mg/100 ml/h; however, many factors influence this rate and there is considerable individual variation.[9] Holford suggested that this should be raised to 18.7 mg/100 ml/h.[14] This applies to healthy adults who are not habituated drinkers, and includes light to moderate drinkers and those 'binge drinkers' who may indulge heavily but intermittently. The enormous number of publications on alcohol must be consulted for details of the range of variation, but basically, elimination can vary from about 12 to 27 mg/100 ml/h.

Taking the mean as around 18 mg, a male of average size can therefore destroy about 9 g alcohol/h, with a range variation of between 7 and 16 g. In the UK, a 'unit' of alcohol contains 8 g of ethyl alcohol, which is used by the Department of Health and several of the medical Royal Colleges in the UK when recommending sensible limits for alcohol intake.[9] A 'unit' or standard alcoholic drink of 8 g is contained (approximately) in half a pint of beer, one single measure of spirits, or a standard glass of table wine.[9]

The habituated drinker, the 'chronic alcoholic', can eliminate far faster than the average person, at least until he suffers severe liver damage in the later stages of his addiction. Though there is some controversy about the experimental evidence, workers such as Bonnichsen have shown that the rate is greater in older people, at higher blood-alcohol levels, and in habituated drinkers.[16] The rate in the latter may be in excess of 40 mg/100 ml/h and work at Lion Laboratories in Wales, who manufacture equipment for breath testing, have found rates over 50 mg/100 ml/h in chronic alcoholics.

Between 90 and 98 per cent of ingested alcohol is removed from the blood by the liver, leaving a small residue to be excreted unchanged by the kidneys, lungs, sweat, salivary and mammary glands. The ethanol in glomerular filtrate is in equilibrium with plasma, but as water is absorbed in the renal tubules, the urine concentration is higher than the blood level at the time of filtration, the ratio being approximately 123:100. This means, for example, that the legal limit for driving in Britain of 80 mg/100 ml blood is taken to be 107 mg/100 ml in urine.

Unfortunately, it is obvious that, except in the highly unlikely circumstances of ureteric catheterization, the urine concentration can never accurately represent the blood concentration at any given time. The blood concentration is almost never static, but is either rising or falling, so the amount of alcohol in the glomerular filtrate is also constantly varying. It is being mixed in the bladder, however, with previously filtered urine and will also have that which is filtered later added to it, until the bladder is emptied – so it can only provide an average concentration for the time between two micturitions. An added error is that urine produced before drinking began (and which was therefore alcohol-free) may have already been in the bladder and will dilute the alcoholic urine. In countries, where urine is used for drink-driving testing, the subject is instructed by the police to empty his or her bladder before collection is made over the subsequent hour, in order to avoid the dilution factor.

Breath is now used by many jurisdictions to measure alcohol intake, either as a screening test before blood is taken for analysis, or as an evidential method instead of blood or urine. There is still some controversy over the scientific accuracy of this method, but usually the results are so high that errors are immaterial – or in marginal results, more accurate blood testing is indicated.

Alveolar air at 37°C is in equilibrium with the pulmonary capillary plasma alcohol, the ratio being about 2300:1, volume to volume, for blood as against breath.[17] There is some dispute as to the true ratio, which lies somewhere between 2100 and 2400. If sufficiently deep exhalation is made to drive out dead-space air, then the collected sample can be analysed to give a measure of the blood alcohol, though slight errors occur if there is incomplete elimination of dead-space air and a drop in temperature as the air travels through the dead space. In most countries using evidential breath testing, however, the offence is not in having a breath-alcohol level in excess of an equivalent blood level, but in having excess alcohol in the breath. This obviates defence ploys that would attempt to throw scientific doubt on the relationship between the two concentrations.

Alcohol concentrations: units and various drinks

The concentration (often called the 'level') of alcohol in blood, urine and breath is expressed by a variety of metric units, which may lead to some confusion. The index most widely used for blood, urine and other body fluids is the weight of alcohol per volume of diluent – for example, milligrams per hundred millilitres (mg/100 ml). The expression 'decilitre' may be used instead of 100 ml (mg/dl). In some countries in continental Europe, alcohol concentration is expressed as 'per mille', which is grams per litre (g/l), equivalent to milligrams per millilitre (mg/ml). Elsewhere, especially in the USA, a 'percentage' system is common, but can be ambiguous as it does not intrinsically state whether the percentage is volume/volume, volume/weight, weight/weight or weight/volume. Unless otherwise stated, it is assumed to be a weight/volume.

Breath is almost universally measured as micrograms per hundred millilitres (μg/100 ml). The matter of weight and volume is important in respect of alcohol concentrations. The specific gravity of alcohol is 0.79, the compound being appreciably lighter than water. In alcoholic drinks, the manufacturer's description and labelling is almost always 'volume/volume' (v/v), but physiological calculations are made via the weight of alcohol in a given volume of body fluid (w/v). Therefore, especially for stronger alcoholic drinks, a conversion has to be made. For example, many spirits, such as whisky, may be labelled as 40 per cent v/v, but this would be only about 32 per cent weight/volume. For weak drinks, such as beer, it is hardly worth correcting the 4 per cent v/v, as calculations have a far greater intrinsic error from other factors.

Approximate strengths of common drinks are as follows (all v/v):

- beer, lager, stout: 3–5 per cent
- cider (variable): 5 per cent
- table wines (unfortified): 9–12 per cent
- fortified wines (sherry, port, vermouth): 18–20 per cent
- spirits (brandy, gin, whisky, rum, vodka): 37–42 per cent
- liqueurs (variable): 15–55 per cent.

The practice of using 'units of alcohol' has become popular in recent years, not so much for calculating concentrations, but for approximate estimates of intake, in relation to excessive drinking and the long-term medical consequences of alcohol consumption. A 'unit' (in the UK 8 g ethyl alcohol) is very approximately delivered by 'one drink', where this is either a half pint of beer, one glass of table wine or one small measure of spirits. However, the amount of alcohol in one 'unit' or 'standard alcoholic drink' varies worldwide, and so do the recommendations for sensible limits for alcohol intake.[9] For example, it has been recommended that males should not exceed about 21 units per week and females 14, to avoid the risk of liver damage.[18] Several observational studies have associated moderate alcohol consumption (up to one drink a day for females and up to two for males) with a decreased risk for coronary heart disease. Thomsen compared the degree of atherosclerosis in the coronary arteries and the aorta in a cohort of alcoholics (n = 441) and non-alcoholic controls (n = 255) who underwent a medico-legal autopsy and observed a significantly lower degree of atherosclerosis in the coronary arteries in alcoholic males and elderly females, while the opposite was found in young females.[19] A recent systematic review and meta-analysis of 63 included studies, and totalling 1686 participants, has provided further indirect support for a protective effect of alcohol.[20]

Calculation of blood levels from drink taken and the converse

The most important statement in this respect is to stress the utter unreliability and inaccuracy of attempting back-calculations in either direction. Only gross approximations can be achieved and no pretence at accuracy must be offered. In this book, we are not concerned with the controversial problems of trying to estimate blood or breath levels in living vehicle drivers at some time prior to an accident or other event, but with similar problems that can arise in fatal cases, especially in relation to drink and driving. In both criminal and civil disputes, evidence is often sought as to the alcoholic state of the deceased at some material time, based on calculations made from blood or urine alcohol analyses taken at autopsy. Less often, aviation, railway, diving and industrial fatalities may present the same potential problem. Criminal proceedings may arise because of alleged reckless driving on the part of another, when the drunken state of the deceased victim may offer some defence. In civil matters, often involving insurance companies, a significant blood-alcohol level may be used as contributory negligence.

Whatever the reason, the pathologist must offer interpretations of alcohol levels found at autopsy with caution, especially where retrospective calculations are requested. Less often, the pathologist may be asked what blood or urine levels might be expected at a certain time (for example, at the time of death) given a description and timetable of alcoholic drinks taken by the deceased. The same cautions against overprecise calculations must be offered here. In calculating approximate blood levels from a knowledge of the drink taken, there are several methods in use: either the well-known 'Widmark factor' or other calculations, which are really modifications or simplifications of the Widmark technique.

Widmark, in 1932, produced his well-known formula for calculating the total amount of alcohol in the body, from which knowing the body weight and assuming equilibration throughout the water compartment, the blood-alcohol level could be derived.[21,22]

The Widmark equation is:

$$A = r \times p \times C_o$$

or

$$r = A/(p \times C_o)$$

where A is the total body alcohol (g), C_o the extrapolated concentration of alcohol in blood, p the body weight in kilograms and r is Widmark's factor, which is 0.68 in males and 0.55 in females. The sex difference is due to the different fat:water ratios, males having about 54 per cent and females 44 per cent water partition by weight.

Much research and modification of Widmark's factors has been carried out. Hume and Fitzgerald claimed that the use of body water distribution was too complex.[23] Gullberg and Jones have published data on a re-evaluation of the Widmark equation, in which they claim to be able to estimate from a single blood-alcohol determination, the amount of alcohol consumed, within an error of about ± 20 per cent.[24] Pounder and Kuroda claim that the use of vitreous fluid (which is sometimes used in decomposed or damaged bodies in place of blood) to predict the blood-alcohol concentration, is too variable to be of practical use.[25]

A useful approximate calculation, derived from Widmark, is that an intake of 0.2 g of alcohol per kilogram body weight is likely to result in a blood-alcohol concentration in males of about 25 mg/100 ml.

The following facts are of use:

- The average rate of decline of blood alcohol after the peak of the curve is reached, may be taken as about 15 mg/100 ml/h.
- The weight of alcohol imbibed may be calculated from knowledge of the v/v strength of the liquor and the amount taken. For example, if a 'double' British measure of 40 per cent v/v whisky is drunk, then 15 ml will contain (40 × 0.8) = 32 per cent alcohol w/v in 15 ml = 4.8 g.
- The weight of alcohol/kg body weight is calculated.
- A ratio of 0.2 g alcohol/kg body weight will produce a blood level of approximately 25 mg/100 ml in a male, assuming an empty stomach.
- In females, the level so produced may be 20–25 per cent higher.
- If only beer is drunk, the peak will be considerably less, sometimes only 50 per cent that produced from wine or spirits.
- Drinking during or after a meal markedly flattens the BAC.

Physiological effects of alcohol

The pathologist is frequently asked in either written opinions or in court testimony to give an estimate of the behavioural state of a victim at a certain level of blood alcohol or after having taken a specified amount of drink. Though he is usually not qualified as an expert on alcoholism in any clinical sense, he will be a medical practitioner with general knowledge and some personal experience of alcoholic behaviour, from his pre-pathology years. He thus can give a general opinion to assist the court, but unless he has special experience of the matter, he should not extend himself into detailed clinical expositions, which are the province of the psychiatrist with an interest in alcoholism, a police surgeon or an accident and emergency officer, all of whom deal frequently with drunken patients. A general level of knowledge can be offered to the lawyer, police or court, however, especially in respect of the usual level of capability and consciousness at different blood-alcohol levels (Table 28.1).

The list in Table 28.1 is probably 'worst case' in nature, as many people show less effects at given blood levels. Females are usually more affected at lower levels, though the 'world record' for survival

Table 28.1 General spectrum of behaviour (mg/100 ml of alcohol in blood)

Above 30	Impairment of complex skills such as driving
30–50	Definite deterioration in driving ability
50–100	Objective signs such as loquaciousness, progressive loss of inhibitions, laughter and some sensory disturbance
100–150	Slurred speech, unsteadiness, possible nausea
150–200	Obvious drunkenness, nausea, staggering gait
200–300	Stupor, vomiting, possibly coma
300–350	Stupor or coma, danger of aspirating vomit
Over 350	Progressive danger of death from respiratory centre paralysis

may be a woman who survived a blood alcohol of 1510 mg/100 ml.[26] Many drivers stopped by the police at random road blocks in Australia had blood levels over 500 mg/100 ml.

Modes of death in acute alcoholism

Death from alcoholic poisoning is not uncommon and can occur at blood-alcohol levels in excess of about 300 mg/100 ml. Most frequently, alcohol poisoning is attributed to chronic alcoholism as unaccustomed drinker rarely reaches lethal BAC. Epidemiological studies on alcohol poisoning mortality have shown considerable variation in lethal BAC and in part of the subjects death has been attributed to even lower concentrations than 300 mg/100 ml.[27–31] Death can be caused either by the direct depressive effects upon the brainstem, mediated via the respiratory centres – or through secondary events such as aspiration of vomit. As discussed in Chapter 14, the use of 'aspiration of vomit' as a cause of death must be used with great caution unless there is ante-mortem eyewitness evidence. The major exception to this proviso is in acute alcoholism, where if copious inhalation of stomach contents right down to the secondary bronchi is confirmed, then in the absence of significant natural disease, injury or other toxicity, a high blood-alcohol level may reasonably be incriminated as the probable cause. Many such fatalities occur during police custody, when considerable outcry, publicity and disciplinary investigations are the usual outcome.

Drunken persons are often involved in fatal trauma, which may be of many types. The majority of homicides are triggered by the aggressive behaviour engendered by alcohol. Road accidents, either caused by drunken drivers (often upon themselves) or by drunken pedestrians walking into traffic, are commonly related to alcoholic vulnerability. Falls are extremely frequent and often fatal. Drunken persons may fall down stairs or steps and suffer head injuries. Falls from high places are less common, but do occur from drunken carelessness or unsteady gait – exemplified by the notorious inquest on Helen Smith in Leeds in 1982.

Death from burns or carbon monoxide poisoning may occur in drunken persons who smoke when intoxicated. A common scenario is for a drunk to go to bed and fall asleep while smoking, the cigarette igniting the bedclothes. Sometimes, a gas, electric or kerosene heater may be knocked over during drunken staggering, which again starts a fatal fire.

Drowning is seen occasionally, especially in river or dockland areas. A typical happening is for a drunken sailor to return to his ship late at night, and fall from a bridge or gangway into the water. Death is sometimes not caused by drowning, but by sudden vagal cardiac arrest from the shock of hitting cold water or having cold water suddenly flood the pharynx and larynx. The drunken state seems to sensitize the victim to such vasovagal shock, perhaps because of the marked cutaneous vasodilatation encouraged by alcohol. The author (BK) has seen a number of such tragedies in Cardiff dockland, including a sailor and his female companion, who both fell off the ship after partying.

Chronic alcoholism

The pathological features of this condition are extensive and can only be surveyed briefly here. In this context, chronic alcoholism refers to the steady, regular abuse of drink, rather than intermittent 'binge' drinking, which gives the tissues time to recover between bouts of acute alcoholism.

At autopsy, there may be signs of general neglect and malnutrition, but many chronic alcoholics are obese or even oedematous, the latter because of chronic heart failure. The specific lesions are in the liver, heart and brain, though they may be difficult to identify as unequivocally caused by alcohol. The early stages of liver damage cause fatty change, usually with enlargement. The normal weight, according to the sex and build, is between 1300 and 1600 g, but a fatty liver may be well in excess of 2000 g. The surface is pale and greasy, though this may not be a uniform change, especially in early or less severe cases. Patchy yellowish areas may be visible within normal hepatic parenchyma.

If the abuse continues, then the fatty change may eventually give way to fibrosis, the liver surface becoming rippled beneath its capsule. Such cirrhosis is fairly fine, with nodules of the order of 5–10 mm in diameter. In the later stages the liver becomes smaller and contracts to a hard, greyish-yellow block of only 800–1200 g.

Without a history of long-term alcohol abuse, it is difficult or impossible to be definite about the aetiology purely on autopsy appearances, though suspicion may be strong. A similar liver may develop as a sequel to hepatitis – and less often as an end result of certain dietary or metabolic defects. The spleen may be enlarged and firm, and portal varices may be present at the gastro-oesophageal junction, but these are both manifestations of portal hypertension and do not assist in determining the precise aetiology of the hepatic fibrosis. A useful index of liver damage and the progression or remission of alcoholic impairment is the level of the enzyme gamma-glutamyl transpeptidase in the serum. Normal levels are less than 36 units, whereas liver damage can elevate this by a factor of many times. Alcoholic cardiomyopathy is certainly a real entity and can be diagnosed clinically. Whether it can be definitely identified on histological appearances alone is a matter of dispute. The heart is enlarged and shows patchy fibrosis with a variable mixed cellular infiltrate, hypertrophy of muscle fibres, patchy necrosis, hyalinization, oedema and vacuolization. Nuclear enlargement and polymorphism complete the range of changes, but none of these are specific, being found in hypertensive heart disease, coronary stenosis and other types of myocarditis. Combined with a definite history of chronic alcoholism, however, these relatively non-specific changes can be ascribed to alcohol if other causes can be excluded (see also Chapter 25). More specific myocardial damage has been caused by cobalt added to commercial beers and several outbreaks are on record.[32,33] Systemic fat embolism has also been recorded in victims of alcoholic fatty liver. Microinfarcts in myocardium and brain are possible, though this aspect has so far been rather neglected in research. Fat stains are not usually employed in routine investigations and it is not known how the victims of a fatty liver compare with control subjects in respect of diffuse target organ embolism.

Methyl alcohol

Methyl alcohol or methanol is a colourless, highly flammable liquid. It is a water-soluble alcohol with a slightly sweet taste and odour. It is a common industrial solvent used as a synthetic precursor and in a variety of commercial products such as windshield washing fluids, deicing solutions, antifreeze, paint removers, and picnic fuels. Small amounts of methanol are present as congeners in some fermented alcoholic beverages.[34–36]

Endogenous blood-methanol concentrations are about 1.5 mg/l, and urinary formic acid concentrations are about 12–17 mg/l.[37,38] Heavy drinking of alcohol (ethanol) blocks the oxidation of endogenous methanol because alcohol dehydrogenase is engaged with ethanol metabolism, resulting in accumulation of methanol both endogenous and exoneous from beverage-related congeners.[35]

Methanol is rapidly absorbed from the gastrointestinal tract and oxidised, mainly by alcohol dehydrogenase into formaldehyde and then by aldehyde dehydrogenase to highly toxic formic acid, which causes severe metabolic acidosis. The lethal dose varies greatly (100–200 ml in adults), but ingestion of 30 ml is potentially lethal, whereas blindness may occur with as little as 10 ml ingestion.[37] The central nervous system, retina and the optic nerve and the basal ganglia, in particular the putamen, appear to be sensitive to injury in methanol poisoning (Figs 28.1, 28.2). Exposure to methanol usually occurs through suicidal, accidental or alcoholism associated ingestion of the above mentioned commercial products. Epidemic methanol intoxications have been reported in association with manufacturing of illicit beverages using methanol in place of ethanol. Recently, Beno *et al.* reported a homicidal methanol poisoning in a child.[39]



Figure 28.1 Massive fresh intracerebral haemorrhage in a 45-year-old alcoholic due to acute methanol poisoning and putamen necrosis after ingestion of methanol-containing windscreen fluid.



Figure 28.2 Cystic degeneration of putamen on both sides as a sequel of bilateral putamen necrosis. A 52-year-old alcoholic who 11 years earlier had suffered from acute methanol poisoning after ingestion of methanol-containing windscreen fluid.

References

1 Plueckhahn VD, Ballard B. Factors influencing the significance of alcohol concentrations in autopsy blood samples. *Med J Aust* 1968;1(22):939–43.

2 Cederbaum AI. Alcohol metabolism. *Clin Liver Dis* 2012; 16(4):667–85.

3 Gentry RT. Effect of food on the pharmacokinetics of alcohol absorption. *Alcohol Clin Exp Res* 2000;24(4):403–4.

4 Lolli G, Rubin M. The effect of concentration of alcohol on the rate of absorption and the shape of the blood alcohol curve. *Q J Stud Alcohol* 1943;4:57–63.

5 Roine RP, *et al*. Effect of concentration of ingested ethanol on blood alcohol levels. *Alcohol Clin Exp Res* 1991;15(4):734–8.

6 Roine RP, *et al*. Comparison of blood alcohol concentrations after beer and whiskey. *Alcohol Clin Exp Res* 1993;17(3): 709–11.

7 Roine R. Interaction of prandial state and beverage concentration on alcohol absorption. *Alcohol Clin Exp Res* 2000;24(4):411–2.

8 Roberts C, Robinson SP. Alcohol concentration and carbonation of drinks: the effect on blood alcohol levels. *J Forensic Leg Med* 2007;14(7):398–405.

9 Rajendram R, Hunter R, Preedy V. Alcohol: absorption, metabolism, and physiological effects. In: Caballero B (ed). *Encyclopedia of Human Nutrition*, 3rd edn. Waltham: Academic Press, 2013, pp. 40–9.

10 Ploutz-Snyder L, *et al*. Gastric gas and fluid emptying assessed by magnetic resonance imaging. *Eur J Appl Physiol Occup Physiol* 1999;79(3):212–20.

11 Wilkinson PK, *et al*. Pharmacokinetics of ethanol after oral administration in the fasting state. *J Pharmacokinet Biopharm* 1977;5(3):207–24.

12 Lennernas H. Ethanol-drug absorption interaction: potential for a significant effect on the plasma pharmacokinetics of ethanol vulnerable formulations. *Mol Pharm* 2009;6(5):1429–40.

13 Ramchandani VA, Kwo PY, Li TK. Effect of food and food composition on alcohol elimination rates in healthy men and women. *J Clin Pharmacol* 2001;41(12):1345–50.

14 Holford NH. Clinical pharmacokinetics of ethanol. *Clin Pharmacokinet* 1987;13(5):273–92.

15 Neuteboom W, Jones AW. Disappearance rate of alcohol from the blood of drunk drivers calculated from two consecutive samples; what do the results really mean? *Forensic Sci Int* 1990; 45(1–2):107–15.

16 Bonnichsen R. Oxidation of alcohol. *Q J Stud Alcohol* 1966; 27:554–60.

17 Wigmore JG. Breath alcohol. In: Siegel AJ, Saukko PJ, Houck MM (eds). *Encyclopedia of Forensic Sciences*. Waltham: Academic Press, 2013, pp. 313–17.

18 Alcohol and the heart in perspective. Sensible limits reaffirmed. A Working Group of the Royal Colleges of Physicians, Psychiatrists and General Practitioners. *J R Coll Physicians Lond* 1995;29(4):266–71.

19 Thomsen JL. Atherosclerosis in alcoholics. *Forensic Sci Int* 1995;75(2–3):121–31.

20 Brien SE, *et al*. Effect of alcohol consumption on biological markers associated with risk of coronary heart disease: systematic review and meta-analysis of interventional studies. *Br Med J* 2011;342:d636.

21 Andreasson R, Jones AW. Erik M.P. Widmark (1889–1945): Swedish pioneer in forensic alcohol toxicology. *Forensic Sci Int* 1995;72(1):1–14.

22 Friel PN, Logan BK, Baer J. An evaluation of the reliability of Widmark calculations based on breath alcohol measurements. *J Forensic Sci* 1995;40(1):91–4.

23 Hume DN, Fitzgerald EF. Chemical tests for intoxication: what do the numbers really mean? *Anal Chem* 1985;57(8): 876A–878A, 882A, 884A passim.

24 Gullberg RG, Jones AW. Guidelines for estimating the amount of alcohol consumed from a single measurement of blood alcohol concentration: re-evaluation of Widmark's equation. *Forensic Sci Int* 1994;69(2):119–30.

25 Pounder DJ, Kuroda N. Vitreous alcohol is of limited value in predicting blood alcohol [see comments]. *Forensic Sci Int* 1994;65(2):73–80.

26 Johnson RA, Noll EC, Rodney WM. Survival after a serum ethanol concentration of 11/2%. *Lancet* 1982;320(8312):1394.

27 Poikolainen K. Alcohol poisoning mortality in four Nordic countries. In: *The Finnish Foundation for Alcoholic Studies*. Forssa, 1977.

28 Lahti RA, Vuori E. Fatal alcohol poisoning: medico-legal practices and mortality statistics. *Forensic Sci Int* 2002;126(3):203–9.

29 Jones AW, Holmgren P. Comparison of blood-ethanol concentration in deaths attributed to acute alcohol poisoning and chronic alcoholism. *J Forensic Sci* 2003;48(4):874–9.

30 Jones AW, Holmgren P. Urine/blood ratios of ethanol in deaths attributed to acute alcohol poisoning and chronic alcoholism. *Forensic Sci Int* 2003;135(3):206–12.

31 Lahti RA, *et al*. Under-recording of ethanol intoxication and poisoning in cause-of-death data: causes and consequences. *Forensic Sci Int* 2011;212(1–3):121–5.

32 Kesteloot H, *et al*. An enquiry into the role of cobalt in the heart disease of chronic beer drinkers. *Circulation* 1968;37(5):854–64.

33 Alexander CS. Cobalt-beer cardiomyopathy. A clinical and pathologic study of twenty-eight cases. *Am J Med* 1972;53(4): 395–417.

34 Greizerstein HB. Congener contents of alcoholic beverages. *J Stud Alcohol* 1981;42(11):1030–7.

35 Jones AW, Lowinger H. Relationship between the concentration of ethanol and methanol in blood samples from Swedish drinking drivers. *Forensic Sci Int* 1988;37(4):277–85.

36 Kruse JA. Methanol and ethylene glycol intoxication. *Crit Care Clin* 2012;28(4):661–711.

37 Moffat AC, Osselton D, Widdop B (eds). *Clarke's Analysis of Drugs and Poisons*. London: Pharmaceutical Press, 2004, p. 1235.

38 Drummer OH. Alcohol congeners and the source of ethanol. In: Siegel AJ, Saukko PJ, Houck MM (eds). *Encyclopedia of Forensic Sciences*. Waltham: Academic Press, 2013, pp. 318–22.

39 Beno JM, *et al*. Homicidal methanol poisoning in a child. *J Anal Toxicol* 2011;35(7):524–8.

This page intentionally left blank

CHAPTER 29

Carbon Monoxide Poisoning

- Causes of carbon monoxide poisoning
- The autopsy in carbon monoxide poisoning
- Blood analysis
- References

Causes of carbon monoxide poisoning

After alcohol and some pharmaceutical drugs, carbon monoxide (CO) poisoning is probably the most common toxic condition to be met with in routine forensic pathology.[1] The widespread introduction of natural gas (which contains no CO) as a replacement for 'coal gas' as a heating fuel has removed a major source of the poison. Monoxide still provides lethal dangers in many other ways, however. It is produced whenever fossil fuels are incompletely oxidized to carbon dioxide and, because of its great affinity for haemoglobin, even low concentrations can be cumulative.

There are a vast number of publications on CO toxicity, both in an environmental and industrial context. Once again, this discussion is confined to the pathologist's involvement in fatalities. A body coming to autopsy with suspected (or sometimes unsuspected) CO poisoning, will have suffered that toxic condition by the following means.

Motor vehicle exhaust gases

Since the replacement of coal gas (containing up to 7 per cent monoxide) with natural gas, a major means of suicide has been removed.[2] 'Putting the head in the gas oven' was the most common form of self-destruction in Britain and many other countries until this changeover. In 1961 in the UK, for example, there were 2711 suicides and 1014 accidental deaths from CO. Since then, suicides have obtained CO to kill themselves from the internal combustion engine.[3] Petrol (gasoline) engines produce up to 5–7 per cent CO in their exhaust fumes, and more if the engine is idling, defective or improperly tuned. Diesels produce far less monoxide than petrol engines. Normally, the exhaust pipe vents the gases into the atmosphere, where it may contribute to considerable low-level monoxide contamination in large cities, such that policemen on traffic duty may have up to 10 per cent saturation of their haemoglobin. When the exhaust fumes are confined to a small space, then a dangerous or lethal level can build up in a short space of time. It is calculated that a 1.5 litre petrol engine, idling in a closed single garage, can produce a lethal concentration in the atmosphere within 10 minutes.

Some suicides will merely sit in the garaged car with a window open and allow the gas to overtake them. More commonly, some device is fitted to pipe the gas into the interior of the car and this may be done outside a garage, often in a remote parking spot. The flexible tube from a vacuum cleaner seems a favourite means, though ordinary hose-pipe, pushed inside the tail-pipe and led in through a window, is a common alternative.

Most modern cars that run on petrol are fitted with a catalytic converter markedly decreasing the CO exhaust emissions and converting the three main pollutants in exhaust fumes: CO, unburned hydrocarbon and oxides of nitrogen. The first two undergo catalytic combustion and the last is reduced back to nitrogen.

Apart from suicide, accidental poisoning sometimes occurs in relation to internal combustion engines. A mechanic or car owner may work on a vehicle in a closed garage, especially in cold weather, and be overcome by monoxide before he is able to remove himself from the danger. The insidious nature of the toxic effects may make him unaware of the supervening stupor and coma.[4,5]

Carbon monoxide can also affect drivers of a moving vehicle, usually because of a defective exhaust system, which allows gas to percolate through the floor or engine bulkhead into the interior. Rarely, a strong following wind blows the external exhaust gas into the open doors of a van or truck. Another motoring cause is a leak in the heat exchanger in those vehicles that use a direct air supply from around the exhaust manifold to provide passenger heating.

In aircraft – usually light planes with the engine immediately adjacent to the cockpit – a leakage of exhaust gas from the motor compartment can lead to disablement of the pilot and death from a crash rather than from fatal toxicity. The same applies to those road-vehicle drivers who are overcome by the gas to an extent that makes them incapable of driving safely. The differential diagnosis in survivors is between CO and alcohol, as the clinical symptoms of both are quite similar at one stage of the toxic process.

Deaths have also been reported in 'scuba' divers, whose air cylinders have been contaminated with CO during refilling from faulty petrol-driven compressors.[6]

Domestic appliances

Domestic heating appliances can produce CO in addition to the usual dioxide from a restriction of their air supply, so that incomplete combustion of the fuel takes place. The fuel can be natural gas, which, though itself free from monoxide, is only partially oxidized from some defect of design, maintenance, or patency of the exhaust flue. Solid-fuel boilers used for central heating may have some restriction of air entry or a partial blockage of the chimney system. Paraffin (kerosene) heaters may burn with inadequate oxygen ingress and any other form of hydrocarbon fuel appliance can malfunction so that part of the products of combustion are monoxide.

The author (BK) has dealt with several deaths that occurred because the faulty installation of natural-gas fires led to absent or inadequate ventilation, causing monoxide to back-diffuse into living rooms. Gas appliances, especially water heaters, are one reason why the bathroom is such a dangerous place. Apart from the extra hazards of electricity, a bath for drowning, wet surfaces for slipping, tablets in the cabinet and sharp instruments such as razor blades, the small-sized room and the frequent installation of a gas water heater or 'geyser' makes this room a frequent locus for unnatural death. Blockage of the exit or 'flue' pipe is a common fault, sometimes from bad installation or because it becomes blocked by soot or by birds' nests.

Structural fires

A common cause of monoxide deaths arises from structural fires in houses and other buildings. As described in Chapter 11, the majority of deaths in house conflagrations are caused not by burns, but by inhalation of smoke. These fatalities are largely caused by CO poisoning, though other lethal gases such as cyanide, phosgene and acroleins are partly responsible. Many victims of house fires die remote from the flames, and may be overcome in different rooms or even on different floors, the monoxide percolating considerable distances and killing persons either asleep or trapped elsewhere in the building.

Industrial processes

Many industrial processes may lead to monoxide poisoning, especially in iron and steel works, where producer gas and water gas are deliberately formed and stored as part of the manufacturing process. Water gas can contain up to 40 per cent CO and in former days was added to town gas for the domestic supply, which greatly enhanced its monoxide content. Many other industrial processes, such as the Mond method of nickel production, use CO, as well as the universal danger of any heating process producing the gas during combustion. In coal-mining, CO is one of the gases that presents a constant threat; it escapes from the coal seams themselves but is also produced from the frequent small fires that smoulder in the recesses of the mines.

Incomplete combustion

Incomplete combustion of a gas flame from any gaseous fuel can produce CO. Where such a flame impinges on a cold metal surface or where that surface is coated with soot, partial oxidation of the fuel supply leads to monoxide production. In appliances fuelled from the common butane or propane cylinder sources, as in caravans, camper vans and boats, maladjustment or restriction of ventilation can lead to slow but insidious production of monoxide. Deaths of whole families have occurred under such circumstances, as they are exposed overnight to slow accumulation of CO from refrigerators and other appliances.

The autopsy in carbon monoxide poisoning

As always, an adequate history may give the clue to the cause of death. Where the circumstances are obvious, such as a death in a car with a tube leading from the exhaust, the pathologist's attention will be directed towards CO from the outset. There are many other circumstances, however, in which the history may be obscure, and only the vigilance of the pathologist and his staff will pick up the possibility of this type of toxicity. In fact, many a case has first been recognized by the mortuary technician who commented on the colour of the skin or tissues. A number of fatal monoxide poisonings have already been certified as 'natural causes' by uncritical clinicians (especially in general practice) when in fact CO poisoning, either suicidal or accidental, was the true reason for the death. Failure to examine the body fully is the usual cause, as the pink colouration may only be noticeable in the areas of postural hypostasis not normally visible in a body in bed, though the sides and back of the neck are reasonably accessible even to cursory examination. The author (BK) recollects at least one suicide where the relatives placed the body back in bed and had it certified as 'coronary thrombosis' by an unsuspecting family doctor.

At autopsy the most striking appearance of the body is the colour of the skin, especially in areas of post-mortem hypostasis (Fig. 29.1). The classical 'cherry-pink' colour of carboxyhaemoglobin is usually evident if the saturation of the blood exceeds about 30 per cent. Below this, familiarity and good lighting are needed and below 20 per cent, no colouration is visible. As these low concentrations are rarely fatal, however, little is lost. Sometimes, darker cyanosis tends to mask the skin colour, but the margins of the hypostasis and the internal tints are usually apparent.

When the victim is anaemic, the colour may be faint or even absent because insufficient haemoglobin is present to display the colour. In racially pigmented victims the colour may obviously be masked, though may still be seen on the inner aspect of the lips, the nail-beds, tongue, and palms and soles of the hands and feet. It is also seen inside the eyelids, but rarely in the sclera.

Rarely, there may be blistering of the skin of dependent areas, such as the calves and buttocks, and around wrists and knees, similar to the so-called 'barbiturate blisters'.[7] These are not specific to CO toxicity and are the result of cutaneous oedema in any profound coma where there is total immobility and lack of venous return from muscle movement. As most CO deaths are relatively rapid, such blisters are rare. Internally the most noticeable feature is again the colour. Blood and muscle will be pink as a result of carboxyhaemoglobin and carboxymyoglobin (Fig. 29.2). In relatively low concentrations, in poor light and in some artificial lighting in autopsy rooms, the cherry-pink colour may be difficult to see. It can be enhanced by diluting the blood with water against a white background, as in a porcelain sink or an enamel scale-pan, when the pinkness will be more evident. The pinkness of hypothermia or refrigeration is a different colour. Unfortunately, some pathologists have a red-colour visual impairment, which makes it difficult for them to differentiate between subtle changes in redness, so laboratory analysis is always required for objective confirmation and quantification of the monoxide concentration. Other suggestive indications of CO are that, when tissues are placed in formol saline for preservation of histology, they do not decolourize as quickly as normal tissues and remain pink for a long period. If CO poisoning is suspected at autopsy, a quick test is to add a few drops of blood to some 10 per cent sodium hydroxide solution on a white tile or in a tube against a white background. The normal blood will immediately become brownish-green but, if significant monoxide is present, the colour will remain pink, as no methaemoglobin is formed. One has to



Figure 29.1 Cherry-pink hypostasis of toenails in carbon monoxide poisoning.



Figure 29.2 Cherry-pink hypostasis of the muscles of the chest in carbon monoxide poisoning.

bear in mind though, that unlike adult blood, fetal blood up to the age of 6 months is more resistant to alkali and the colour change can take hours to develop. Another simple test, mentioned in 1857 by Hoppe, is to take 3 ml blood into a test tube and dilute it with 6 ml tap water and to heat it for a short while with care in a water bath. Carbon monoxide blood turns brick red whereas control blood becomes greyish-brown.[8] However, these crude tests are not recommended as an alternative to proper analysis.

Other signs at autopsy are non-specific. Pulmonary oedema is usually present. The author (BK) has the impression that the white matter of the brain remains unusually firm and that the whole brain after removal from the skull keeps its shape better, being rather stiff and rigid. This may be caused either by oedema or by some minimal fixation change in the brain tissue.

None of these rather idiosyncratic tests can replace proper laboratory investigation, however. Blood should be taken for analysis in the usual way, preferably from a peripheral vein. In contrast to most toxicological investigations, even foul samples can still be useful for carboxyhaemoglobin estimations. Heart blood, blood from body cavities and even from bone marrow when the bones are split open, can still provide valid material for estimating the percentage of haemoglobin converted to carboxyhaemoglobin. It is the ratio of haemoglobin to the carboxy-type that is required, rather than an absolute concentration in the blood, so virtually any blood-containing fluid will provide this answer. When a body has been badly damaged by fire, fluid blood may be hard to obtain, so that any sanguineous body fluid or bone marrow can be added as a preservative.

There are no other autopsy features in acute deaths, which form the majority seen by forensic pathologists. Where survival occurs there are a number of neurological lesions that follow severe CO exposure. Necrosis and cavitation of the basal ganglia in the brain, notably the putamen and globus pallidus, has been known for well over a century. Within about 5 days, histological changes occur here, with ‘gitterzellen’ scavenging cellular debris, the foam cells and microglia presenting an appearance characteristic of tissue breakdown in the central nervous system. There may also be damage in the substantia nigra of the brainstem. In delayed deaths, petechiae and ring-shaped haemorrhages may occur in the cerebral white matter. All these changes, together with the clinical symptomatology, are exhaustively described in neurological publications.

Tiny focal necroses have been described in the myocardium in delayed deaths from this cause, and similar lesions were described by Korb and David even in acute deaths.[9] However, Fineschi *et al.* in their human study on 26 fatal acute CO poisonings and further 45 victims of fatal head trauma as controls, were unable to confirm any morphology specific to CO intoxication but concluded that morphologic lesions described in CO intoxication are most likely due to adrenergic stress following reoxygenation, rather than a direct action of CO or related anoxia on myocardial cells.[10] Fracasso *et al.* reported increased immunohistochemical expression of myocardial fibronectin in 24 of 26 subjects of lethal CO poisoning. The increased fibronectin expression was predominantly localized in the right ventricle.[11]

Acute myocardial infarction has been reported after acute CO exposure and relative hypoxia, rarely even with normal coronary arteries, but probably more frequently in the presence of pre-existing coronary disease.[12–14]

Blood analysis

Carbon monoxide has an affinity for haemoglobin that is between 200 and 300 times greater than oxygen. Therefore, even small concentrations of monoxide in the inspired air will progressively displace oxygen from the erythrocytes and this will lower the oxygen-carrying capacity of the blood. It was formerly thought that all the toxic properties of CO lay in this hypoxic action, but more recently it has been shown to interfere with other ferroproteins such as myoglobin and various enzymes including members of the cytochrome family.

The major effect is undoubtedly the reduction in oxygen transport and, for this reason, it is the percentage saturation of the total available haemoglobin that is important rather than an absolute quantity of carboxyhaemoglobin in the blood. Anaemic persons will not show the external cherry-pink colour if insufficient haemoglobin is available for the monoxide component to become visible. It is the residual non-combined haemoglobin still available for oxygen transport that is important in maintaining life. For example, an anaemic person with only 8 g/100 ml of haemoglobin having four of those occupied with CO (50 per cent saturation) is in much worse a state than a person with a total of 14 g of which four are monoxide-occupied. There are many tables available that relate saturation levels to the clinical symptoms. There is a wide margin of variation in these, as there is with lethal levels.

Broadly speaking, the saturation levels found in fatal cases reflect both the physical state of the victim and the rapidity with which the poisoning took place. Robust, healthy adults under 60 years of age rarely die at saturation level under 50–60 per cent unless the concentration of CO in the inspired air was so great that death occurred before gas exchange in the lungs was able to progress sufficiently to enter all available monoxide into the red cells. Death may then supervene with post-mortem saturation levels of as low as 40 per cent. Where absorption is slow and life persists longer (for there seems to be a relationship between air concentration of monoxide and length of survival), autopsy samples may show 80 per cent saturation.

Old people may die at relatively low concentrations, such as 30 per cent and, in some cases, no other cause can be found when the carboxyhaemoglobin level is only 25 per cent. This may be the result of anaemia, so that there is less reserve for oxygen carrying when part of the haemoglobin is occupied by monoxide. In many cases, the senile myocardium is already in a fragile state and any extra hypoxia will cause it to fail. Infants also seem to die at relatively low levels, perhaps because their higher respiration rate allows a more rapid absorption. The variation in fatal concentrations is wide and quite irregular. This is best exemplified when two or more victims have died together in the same environment. The carboxyhaemoglobin concentrations of bodies lying alongside each other can sometimes be totally different, even in persons of the same age group and physical health. Any disease process can contribute to death at lower monoxide concentrations. Coronary artery disease, respiratory insufficiency and other debilitating conditions allow death to occur earlier, when the toxic level is still relatively low. Conditions that are worsened by hypoxia, such as myocardial insufficiency or obstructive airway disease, are particularly potent. In addition to disease, any separate toxic state is additive, such as hypnotic drugs or alcohol.

Modern analytical methods include non-dispersive infrared spectrophotometry and gas chromatography. Carboxyhaemoglobin is stable and can be detected even in putrefied bodies a long time after death, as long as sophisticated laboratory techniques are used. Monoxide cannot enter a body post-mortem to any significant extent. Bodies burnt after death do not absorb any monoxide and thus a significant level (more than 10 per cent) in a body from a fire means that respiration must have been proceeding whilst the conflagration was in progress. As emphasized in Chapter 11, the converse is often not true, in that deaths from rapid fires, especially flash fires caused by petrol, for example, may have no carboxyhaemoglobin in the blood.

The possibility of carboxyhaemoglobin being formed in the blood post-mortem has been investigated as a possible source of error by Kojima *et al*. They concluded that the interpretation of carboxyhaemoglobin saturation in the blood would not be affected significantly by the post-mortem formation of CO, and that body cavity fluids should not be used for CO determination.[15–17]

A minor source of local carboxyhaemoglobin and myohaemoglobin is gunshot wounds, where the propellant gases (which are rich in the compound) are blown into the wound from contact or short-range discharges. The tissues absorb monoxide, especially around the entrance wound. It has been claimed that this is a way of differentiating the entrance from the exit wound, but in fact the whole track of the missile(s) may be sheathed in a zone of monoxide transfer into blood and muscle from a near-discharge, though theoretically there should be a gradient of concentration from one end of the track to the other (see Chapter 8).

Many other war, military and terrorist circumstances are associated with exposure to CO. Large quantities are released from the firing of guns and, in enclosed spaces, can become a hazard. Detonation of explosives in places where there is little ventilation also allows monoxide to accumulate and it may persist long after the physical dangers of the explosion have passed.

References

1 Varma DR, Mulay S, Chemtob S. Carbon monoxide: from public health risk to painless killer. In: Ramesh CG (ed). *Handbook of Toxicology of Chemical Warfare Agents*. San Diego: Academic Press, 2009, pp. 271–92.

2 Kreitman N. The coal gas story. United Kingdom suicide rates, 1960–71. *Br J Prev Soc Med* 1976;30(2):86–93.

3 Bowen DA, *et al*. Carbon monoxide poisoning. *Forensic Sci Int* 1989;41(1–2):163–8.

4 Raub JA, *et al*. Carbon monoxide poisoning – a public health perspective. *Toxicology* 2000;145(1):1–14.

5 Guzman JA. Carbon monoxide poisoning. *Crit Care Clin* 2012;28(4):537–48.

6 Austin CC, *et al*. Carbon monoxide and water vapor contamination of compressed breathing air for firefighters and divers. *J Toxicol Environ Health* 1997;52(5):403–23.

7 Myers RA, Snyder SK, Majerus TC. Cutaneous blisters and carbon monoxide poisoning. *Ann Emerg Med* 1985;14(6):603–6.

8 Hoppe F. Über die einwirkung des kohlenoxydgases auf das hämatoglobin. *Virchows Arch Pathol Anat Physiol Klin Med* 1857;11:288–9.

9 Korb G, David H. [Fluorescent microscopy and electronoptic studies on the myocardium in rats after poisoning with illumination gas]. *Dtsch Z Gesamte Gerichtl Med* 1962;52:549–57.

10 Fineschi V, *et al*. Myocardial findings in fatal carbon monoxide poisoning: a human and experimental morphometric study. *Int J Legal Med* 2000;113(5):276–82.

11 Fracasso T, *et al.* Immunohistochemical expression of fibronectin and C5b-9 in the myocardium in cases of carbon monoxide poisoning. *Int J Legal Med* 2011;125(3):377–84.

12 Ebisuno S, *et al.* Myocardial infarction after acute carbon monoxide poisoning: case report. *Angiology* 1986;37(8):621–4.

13 Marius-Nunez AL. Myocardial infarction with normal coronary arteries after acute exposure to carbon monoxide. *Chest* 1990;97(2):491–4.

14 Mokaddem A, *et al.* [A rare cause of myocardial infarction: carbon monoxide intoxication]. *Tunis Med* 2004;82(3):320–3.

15 Kojima T, *et al.* Postmortem formation of carbon monoxide. *Forensic Sci Int* 1982;19(3):243–8.

16 Kojima T, Yashiki M, Une I. Experimental study on postmortem formation of carbon monoxide. *Forensic Sci Int* 1983;22(2–3):131–5.

17 Kojima T, *et al.* Production of carbon monoxide in cadavers. *Forensic Sci Int* 1986;32(2):67–77.

CHAPTER 30

Organophosphorus Poisoning

- Introduction
- Paraquat poisoning
- Organophosphorus pesticides
- References

Introduction

In the last half-century numerous structurally different organophosphorus compounds (OP) have been synthesized, of which more than 100 different OPs are used as insecticides.[1,2] This has revolutionized the farming methods throughout the world. The World Health Organization (WHO) has classified pesticides (based primarily on the acute oral and dermal toxicity to the rat) from class Ia (extremely hazardous) to class III (slightly hazardous) and then 'active ingredients unlikely to present acute hazard'. Most class-I technical grade pesticides are banned or strictly controlled in the regulated industrialized world, but not in developing countries, where class-I pesticides are freely available in places that do not have the resources for their safe use.[3]

The developing nations (who in terms of area of land usage and proportion of the population who work on that land, are numerically greatest at risk) suffer most and this is sometimes exacerbated by the less stringent controls and less safe working methods that exist in those countries.[4,5]

The potent chemicals used in agriculture may harm persons by accidental exposure, either during their application to crops, or due to incorrect or careless storage. Another major source of human poisoning is through self-administration, when the easily available substances are used for suicide. According to a conservative estimate by Gunnell *et al.* there are around 260,000 deaths from pesticide self-poisonings worldwide each year, accounting for about 30 per cent of suicides globally.[6] Deaths from unintentional OP poisoning are less common and homicidal use of pesticides is rare but has also been raported.[7–11]

For example, in Sri Lanka from 1975 to 1980, an average of 13,000 patients with acute pesticide poisoning were admitted annually to government hospitals of whom approximately 1000 died each year.[12] In 2002–2009 pesticide poisoning was the third most common suicide method in Taiwan.[13] In 2011 there were altogether 1757 deaths in Sri Lanka due to self-administered OP poisoning, i.e. 46.6 per cent of all suicides.[14]

The main dangers from agricultural chemicals lie in the pesticides, especially OP compounds, such as parathion and herbicides, such as paraquat.

Paraquat poisoning

Paraquat is a herbicide that is sprayed on unwanted weeds and other vegetation before planting crops. It is absorbed by the foliage and rapidly kills the plant, but is inactivated when in contact with the soil, so cannot harm the seeds or young plants that are placed in the same ground a short time later. Paraquat (and the less popular diquat) are dipyridyl compounds, paraquat chemically being 1,1′-dimethyl-4,4′-bipyridinium. It is produced commercially as a brownish concentrated liquid of the dichloride salt at 10–30 per cent strength, under the trade name Gramoxone and, for horticultural use, as brown granules called Weedol at about 5 per cent concentration.

Toxicity occurs almost exclusively through ingestion, though some cases are reported where inhalation through spraying has led to a fatal outcome. A suicide from intravenous injection of paraquat has been reported by Fernandez *et al.*[15]

Only about 5 per cent of the substance is absorbed orally.[16,17] Poisoning usually occurs either by deliberate self-ingestion of the liquid concentrate, or by accidental drinking from unmarked or incorrectly marked bottles. It is said that one swallowed mouthful of Gramoxone will almost always be fatal and certainly 5 ml has caused death. The estimated minimum lethal dose is about 1 g.[18] The decanting of the concentrate from the original manufacturer's containers leads to many accidental deaths. Because of the relatively high cost, paraquat is often taken from the large containers and kept in lemonade or other soft drink bottles. Such decanting is illegal in some countries such as the Republic of Ireland, because of the dangers of unlabelled bottles. Unsuspecting people, especially children, then take a drink from such bottles and immediately suffer the effects of the potent toxin.

Paraquat in concentrated form, is irritant to all epithelial tissues. The lips, mouth, pharynx and oesophagus are superficially eroded, though there is nothing like the dangerous structural damage of strong acids or alkalis. The major danger of paraquat is to the lungs and liver. The lungs are affected mainly by direct aspiration, either as the irritative substance is swallowed or by regurgitation from the stomach during vomiting.

Of that absorbed through the gastrointestinal tract, the major danger is to the liver, where paraquat causes a centrilobular necrosis, with giant mitochondria and crystalline inclusion bodies seen on electron microscopy. In the kidney, renal failure may develop within 2–3 days from diffuse tubular damage.

The striking lesion, almost characteristic of paraquat, is in the proliferative damage to the lungs.[19–21] If rapid death from acute hepatorenal failure does not occur, either because of low dosage or energetic clearance of the residual poison, then progressive lung damage may still lead to death within the next 2 weeks. When paraquat reaches the distal air spaces, diffuse pulmonary oedema and haemorrhages occur, followed by stimulation of the alveolar lining cells. Prior to this, in the first day or two, there is damage to the pneumocytes with vacuolation, desquamation and necrosis. A hyaline membrane is often visible. The mechanism appears to be that paraquat reacts with tissue elements to produce peroxides, including hydrogen peroxide, which is responsible for the damage, which can be worsened by oxygen therapy.

Within a few days repair begins, the mesenchymal interstitial cells and the alveolar lining cells dividing rapidly and filling the alveoli. Both granular and membranous pneumocytes (types I and II) are involved. Within the first week, gas exchange begins to suffer as the air spaces become occluded by mononuclear cells forming rounded-up 'fibroblasts'. If survival continues, the alveoli begin to fibrose, with reticulin and collagen being laid down to form a rigid, stiff lung.[22,23]

The autopsy in paraquat poisoning

There may be ulceration around the lips and mouth from escape of paraquat concentrate. The mucosa of the mouth may be reddened or desquamated, and the oesophagus may show worse changes, including casts of shed epithelium. None of these changes is by any means inevitable, however, and the upper gastrointestinal tract may be normal.

Similarly, the stomach may show erosion and patchy haemorrhages, or may be unremarkable. The liver may show pallor or mottled fatty change to the naked eye. It is unusual for any gross charges to be visible. Other organs show no specific changes, apart from the lungs; the kidneys may reveal cortical pallor if there is renal failure.

If the victim has lived a week or more, then the lungs may reveal typical changes in that they are large and stiff, keeping their shape when removed from the chest. There may be a fibrinous pleurisy and sometimes slight bloody pleural effusions. The cut surface reveals oedema and patchy haemorrhage, though this may have subsided in cases that survive for some time. The main appearances are microscopic and, unless the history is known, the lung may be mistaken for a diffuse pneumonia. The author (BK) saw a homicide by paraquat, in which the victim was in hospital for 2 weeks with a presumptive diagnosis of 'virus pneumonia', until a confession revealed the true cause of the lung changes. Samples required at autopsy, apart from full histology, include the usual blood samples, urine, stomach contents, lung and liver.

In most instances, the relative slowness of the death allows the diagnosis to be made on history and clinical grounds, so that ante-mortem toxicology is usually well documented.

Toxicology interpretation

A fatal outcome is usually associated with plasma paraquat concentrations greater than 0.2 mg/l at 24 h after ingestion and 0.1 mg/l at 48 h after ingestion. However, individual response is variable and some subjects with much higher concentrations have recovered.[24–26] Scherrmann *et al.* measured urine paraquat concentrations in 53 patients. All patients with urine paraquat concentrations of less than 1 mg/l within 24 h of overdose survived, whereas patients with urine paraquat concentrations of more than 1 mg/l had a high probability of death.[27] Paraquat is excreted over a long period and can be detected in urine at autopsy many days after ingestion. Concentrations in excess of 0.07 mg/l have been found 26 days later.[16,28]

The concentrations found on analysis after autopsy naturally depend upon the dose taken and the time that has elapsed since ingestion. On the first day, ranges from 0 to 63 mg/l (average 15) have been found in the blood, with urine levels of 20–1210 mg/l (average 462). Seven days later, the blood level comes down to an average of 0.8 mg/l with 4.5 in the urine. Two to three weeks after ingestion, the blood concentration averages 0.5 and the urine level 0.6 mg/l.[16]

Organophosphorus pesticides

Used in huge quantities throughout the world, these substances cause thousands of deaths in southern Asia, Africa and elsewhere. The major example is parathion, with malathion and dichlorvos used far less extensively. These chemicals act on insects and other arthropods by inhibiting cholinesterase and their toxic effects on man are caused by the same mechanism.

Parathion (nitrostigmine) is extremely toxic and can be absorbed through the skin, conjunctivae, lungs and gut. Because of the inhibitory effect on plasma and erythrocyte cholinesterases, acetylcholine builds up at neuromuscular junctions and other neurotransmitter sites, resulting in hyperexcitability of both voluntary and involuntary muscle.

Other OP compounds include malathion, which is much less toxic than parathion and is used more in horticulture; dithion, diazinon, hexaethyltetraphosphate (HETP), tetraethylpyrophosphate (TEPP), octamethylpyrophosphamide (OMPA) and demeton are other pesticides of this group.

Toxic signs and symptoms appear when the cholinesterase level drops to 30 per cent of its normal activity. Fatalities begin to occur after the ingestion of 125–175 mg, though ingestion of much larger amounts can be survived. Death can occur in less than an hour after ingestion, though usually several hours elapse in those who are not going to survive.

Autopsy appearances are more helpful than with many other compounds, in that parathion is dissolved in a kerosene base, which can often be detected by its smell. A greenish colouring agent is often added to the commercial products. The stomach therefore may be seen to contain an oily, greenish scum. The gastric mucosa may be haemorrhagic, though this is too non-specific to be of much use, as is the common finding of haemorrhagic pulmonary oedema.

The author (BK), when practising pathology in South-east Asia, noted a useful diagnostic sign in some less modern mortuaries that were infested with flies and bluebottles. When these insects alighted on an opened cadaver at autopsy, many fell dead or dying onto the autopsy table when the case in progress was a parathion poisoning.

Toxicology interpretation

Post-mortem toxicology is usually conclusive in acute poisoning. The substance resists post-mortem autolysis well and can be recovered from putrefied bodies. The range of blood parathion concentrations in fatal cases may be from 0.5 to 34 mg/l with an average of 9.0. Urinary excretion ranges from 0.4 to 78 mg/l with an average of 10 mg/l. The liver may contain from 0.1 to 120 mg/kg, averaging 11.[16]

Malathion is much less toxic but deaths certainly occur given a greater dose. The estimated lethal dose is about 60 g.[29] Because Malathion has been used for a long period of time and different manufacturing processes have been used, a range of impurities have been reported in all end-use products, some of which are more toxic than malathion.

Jadhav *et al.* studied the post-mortem distribution of malathion in lungs, liver, kidneys, spleen, brain, heart, blood, muscles, urine and gastric contents in six suspected suicidal poisonings. The quantitative analysis was performed using high performance liquid chromatography. Malathion concentration in blood varied between 175 and 517 mg/l.[30]

Zivot *et al.* reported a suicide of an 80-year-old female who ingested malathion mixed with a fruit drink. She presented with symptoms of cholinergic crisis, which after initial improvement progressively deteriorated with respiratory and renal failure, and she died 12 days after hospital admission. The ante-mortem blood malathion level was 23.9 mg/l. Post-mortem toxicological analysis revealed still greatly reduced cholinesterase activity.[31] Thompson *et al.* described a fatal suicide by malathion, where the average post-mortem blood concentration was 1.8 mg/l using gas chromatography-mass spectrometry (GC-MS).[32]

Pannell *et al.* assessed the characteristic features of deaths associated with malathion in South Australia over a 20-year period. A total of five cases were found, in each of which exposure to malathion had been intentional. In four cases malathion had been ingested and in one case death had resulted from an intravenous injection of insecticide. Ingestion of large volumes of malathion was associated with contamination of the mortuary due to post-mortem regurgitation in at least one case. In one subject with evidence of sublethal levels of benzodiazepines, methadone, opiates and tricyclic antidepressants and alcohol, malathion concentration in blood was 0.34 mg/l. In another subject the ante-mortem malathion concentration in blood was 5.5 mg/l. They further observed that the analysis of a blood sample with sodium fluoride preservative resulted in a malathion concentration of 0.1 mg/l, whereas the concentration in an unpreserved sample was 1.1 mg/l.[33]

Other pesticides and insecticides include chlorinated compounds such as aldrin, lindane and dieldrin. Other types include the carbamates (opxymyl, landrin and aldicarb), dinitrophenols, pyrethrum and derris. The phenolic pesticides include dinitro-orthocresylphosphate (DNOC) and dinitrobutylphenol. None of these has any specific autopsy features and the diagnosis rests upon the history, circumstances, and post-mortem analysis of blood, urine and liver.

References

1 Kwong TC. Organophosphate pesticides: biochemistry and clinical toxicology. *Ther Drug Monit* 2002;24(1):144–9.

2 Worek F, *et al.* Diagnostic aspects of organophosphate poisoning. *Toxicology* 2005;214(3):182–9.

3 WHO. *The WHO recommended classification of pesticides by hazard and guidelines to classification: 2009.* Geneva: WHO, 2010.

4 Bull D. *A Growing Problem: Pesticides and the Third World Poor.* Oxford: OXFAM; Supplier, Third World Publications, 1982.

5 Thundiyil JG, *et al.* Acute pesticide poisoning: a proposed classification tool. *Bull World Health Organ* 2008;86(3):205–9.

6 Gunnell D, *et al.* The global distribution of fatal pesticide self-poisoning: systematic review. *BMC Public Health* 2007;7:357.

7 Stephens BG, Moormeister SK. Homicidal poisoning by paraquat. *Am J Forensic Med Pathol* 1997;18(1):33–9.

8 Book RG. Homicidal poisoning by paraquat. *Am J Forensic Med Pathol* 1998;19(3):294–5.

9 Daisley H, Simmons V. Homicide by paraquat poisoning. *Med Sci Law* 1999;39(3):266–9.

10 Ozdemir C, *et al.* Homicidal poisoning by injection of methidathion: the first ever report. *Hum Exp Toxicol* 2009;28(8):521–4.

11 Sakunthala Tennakoon DA, Karunarathna WD, Udugampala US. Carbofuran concentrations in blood, bile and tissues in fatal cases of homicide and suicide. *Forensic Sci Int* 2013;227(1–3):106–10.

12 Van der Hoek W, *et al.* Pesticide poisoning: a major health problem in Sri Lanka. *Soc Sci Med* 1998;46(4–5):495–504.

13 Chang S-S, *et al.* The impact of pesticide suicide on the geographic distribution of suicide in Taiwan: a spatial analysishttp://dx.doi.org/10.1186/1471-2458-12-260

14 Sri Lankan Police Services. *Mode of suicides*. 2011.

15 Fernandez P, *et al.* A fatal case of parenteral paraquat poisoning. *Forensic Sci Int* 1991;49(2):215–24.

16 Baselt RC. *Disposition of Toxic Drugs and Chemicals in Man*, 8th edn. Baselt RC (ed). Foster City: Biomedical Publications, 2008, xviii.

17 Conning DM, Fletcher K, Swan AA. Paraquat and related bipyridyls. *Br Med Bull* 1969;25(3):245–9.

18 Moffat AC, Osselton D, Widdop B (eds). *Clarke's Analysis of Drugs and Poisons*, 3rd edn. London: Pharmaceutical Press, Vol. 2. 2004.

19 Torre C, *et al.* Lung morphology in experimental acute paraquat poisoning. SEM observations. *Am J Forensic Med Pathol* 1984;5(2):125–9.

20 Schultek T, Markwalder C. [Morphology of a paraquat poisoning]. *Z Rechtsmed* 1985;94(4):317–24.

21 Harsanyi L, Nemeth A, Lang A. Paraquat (gramoxone) poisoning in south-west Hungary, 1977–1984. Toxicological and histopathological aspects of group intoxication cases. *Am J Forensic Med Pathol* 1987;8(2):131–4.

22 Agarwal R, *et al.* Experience with paraquat poisoning in a respiratory intensive care unit in North India. *Singapore Med J* 2006;47(12):1033–7.

23 Beligaswatte AM, *et al.* An outbreak of fatal pneumonitis caused by contamination of illicit alcohol with paraquat. *Clin Toxicol (Phila)* 2008;46(8):768–70.

24 Scherrman JM, *et al.* [Acute paraquat poisoning: prognostic and therapeutic significance of blood assay]. *Toxicol Eur Res* 1983;5(3):141–5.

25 Kala M. Pesticides. Moffat AC, Osselton D, Widdop B (eds). *Clarke's Analysis of Drugs and Poisons*, 3rd edn. London: Pharmaceutical Press, pp. 202–26.

26 Dinis-Oliveira RJ, *et al.* Acute paraquat poisoning: report of a survival case following intake of a potential lethal dose. *Pediatr Emerg Care* 2006;22(7):537–40.

27 Scherrmann JM, *et al.* Prognostic value of plasma and urine paraquat concentration. *Hum Toxicol* 1987;6(1):91–3.

28 Beebeejaun AR, Beevers G, Rogers WN. Paraquat poisoning-prolonged excretion. *Clin Toxicol* 1971;4(3):397–407.

29 Baer KN. Malathion. In: Wexler P (ed). *Encyclopedia of Toxicology*, 2nd edn. New York: Elsevier, 2005, pp. 3–5.

30 Jadhav RK, *et al.* Distribution of malathion in body tissues and fluids. *Forensic Sci Int* 1992;52(2):223–9.

31 Zivot U, Castorena JL, Garriott JC. A case of fatal ingestion of malathion. *Am J Forensic Med Pathol* 1993;14(1):51–3.

32 Thompson TS, *et al.* Case study: fatal poisoning by malathion. *Forensic Sci Int* 1998;95(2):89–98.

33 Pannell M, *et al.* Death due to malathion poisoning. *J Clin Forensic Med* 2001;8(3):156–9.

CHAPTER 31

Poisoning by Medicines

- General considerations
- Autopsy appearances
- Results of laboratory tests
- Analgesics
- Paracetamol
- Antidepressant drugs
- The benzodiazepines
- The phenothiazines
- The barbiturates
- Insulin poisoning
- References

General considerations

In most countries, especially those with advanced economies and relatively sophisticated medical services, poisoning with medicinal compounds is common.[1–5] In many such countries, poisoning with therapeutic substances exceeds deaths from other types of toxic agents, especially in suicidal and accidental poisoning (Fig. 31.1).

This is explained by the ease of access of such substances, whether they are obtainable from a doctor on prescription or on demand across the counter of a pharmacy. Where state-sponsored health services exist, the cost to the recipient may be minimal or absent and this ease of access contributes to opportunities for self-poisoning, whether it be deliberate self-destruction, suicidal gestures or accidental ingestion – the latter especially in children. Unfortunately, overprescribing or the supply of too great a quantity of drugs at one time allows excessive stocks of drugs to be easily available to the public.



Figure 31.1 Vomit at the mouth and nostrils with coloured particles suggestive of tablet residues. Toxicological analysis confirmed poisoning by codeine and paracetamol.

Though only a minority of victims of medicinal poisoning fail to recover, there are still an appreciable number of deaths. These come to the attention of the investigative authorities and hence to pathologists. The autopsy investigation of a fatality from a therapeutic substance can be difficult, for a number of reasons:

- The nature of the substance may be uncertain or unknown.
- There may be more than one such substance involved.
- There may be a delay between ingestion and death sufficient to allow blood, urine and tissue concentrations to decline below fatal, toxic or even therapeutic levels.
- Analysis may be difficult to arrange because of lack of facilities.
- Information about fatal levels may be unobtainable.
- Most medicinal poisons leave virtually no characteristic features at autopsy, so diagnosis depends upon laboratory findings.
- Post-mortem changes may make analysis difficult, inaccurate or impossible.
- Where death is delayed after taking the substance, none may be recoverable from the stomach (which has emptied) or even from the intestine.
- The original substance may be rapidly metabolized into one or more breakdown products, adding to difficulties in identification and interpretation.

Autopsy appearances

The lack of characteristic autopsy appearances is often very frustrating for the pathologist. Unless there is an indicative or suggestive history as to which drug was taken – a matter for the investigators in respect of circumstances and recovery of containers – then an autopsy may have to be performed 'blind'. Where no significant morphological lesions can be discovered, then a full toxicology screen must be considered, which in some jurisdictions may be difficult or impossible to obtain, or be extremely expensive.

The majority of modern medicinal substances are, by design, bland and non-irritant to the tissues and gastrointestinal tract. Most of those met with in forensic practice are taken orally and, though the active constituents may be potent in their pharmacological effect on target organs and tissues, the medicine will cause no erosion or damage to the alimentary tract. Thus little or no physical evidence can be obtained from a gross or even microscopic examination of the gastrointestinal tract or other organs. Much of the physical bulk of modern tablets or capsules is merely the vehicle for introducing the active component into the body and is thus unlikely to have any adverse effect.

When a medicinal compound causes death, the mode of death is most often some form of cardiorespiratory failure, often secondary to depressive effects on the central nervous system. This mode of death causes only non-specific changes discernible at autopsy, which are usually of no use in indicating the basic reason for the death. Acute congestive cardiac failure, pulmonary oedema, sometimes cerebral oedema, generalized organ congestion, scattered petechiae on serous membranes – none of these is of any real use to the pathologist, who has to rely on the results of toxicological analysis for a definitive answer.

There are some therapeutic substances, which, though not the cause of specific lesions, may suggest themselves from their autopsy appearances. An example is the widespread membrane ecchymoses sometimes seen in aspirin poisoning. This could not in any way be sufficient to provide a legally acceptable cause of death, however, unless absolutely reliable circumstantial evidence existed, together with the finding of a large bolus of undissolved tablet remnants in the stomach. Even then it might be contested that the substance was not aspirin – or not aspirin alone – unless analytical confirmation was obtained.

Results of laboratory tests

As discussed in Chapter 27, the investigation of fatal poisoning is a collaborative investigation between pathologist and toxicologist. The autopsy excludes, confirms or evaluates any trauma or natural disease, and provides suitable material for analysis. The toxicology laboratory conducts the technical assays, and produces qualitative and quantitative results. The toxicologist/analyst interprets those results to the pathologist, by providing an indication of the therapeutic, toxic and fatal ranges of concentrations in various body fluids and tissues, and by pointing out problems such as decline from post-ingestion survival, conversion to metabolites and many others. The pathologist then collates this information with his own knowledge of the history and autopsy findings to offer the best interpretation of the investigation for judicial authorities. Most problems arise either because the information about the medicine (especially if it is newly developed or where its toxicity is low) is incomplete in terms of toxic blood and tissue levels – because post-ingestion survival has allowed the originally lethal levels to have subsided to therapeutic or even lower limits.

The ranges of post-mortem drug concentrations published in the literature are often wide due to uncertainty of dosage, variation in post-ingestion survivals, wide individual biological variation, and other potential sources of variation because of differences in post-mortem interval, post-mortem drug redistribution and chemical changes due to decomposition, varying post-mortem procedures such as the sampling site, specimen handling and the analytical method applied, all of which together make it impossible to lay down strict thresholds between therapeutic, toxic and fatal concentrations.[6–8] Reference data compilations do not always state whether blood or plasma has been used as matrix for analysis. Osselton *et al.* noted that out of 92 papers concerned with methods for the analysis of drugs in blood only 12 presented results from the analysis of whole blood.[9]

In some jurisdictions samples may be routinely retained without any initial suspicion of intoxication and frozen for possible later analysis. Holmgren *et al.* investigated the stability of 46 drugs in post-mortem femoral blood as well as the possible influence of potassium fluoride in vitreous humour stored for 1 year at −20°C. In femoral blood five substances; ethanol, desmethylmianserin, 7-amino-nitrazepam, tetrahydrocannabinol (cannabis; THC) and zopiclone showed a decrease in the concentration whereas the concentrations of two substances; ketobemidone and thioridazine increased. However, they considered that the changes were not of such an order that they would affect the interpretation in normal forensic casework. In vitreous humour there were significantly lower concentrations for ethanol and zopiclone in the samples without potassium fluoride after storage for 1 year.[10]

Different types of data compilations have been used as reference concentrations when estimating the probability of a given drug concentration measured post-mortem having caused the death. Schulz *et al.* published a compilation of therapeutic and toxic blood concentrations comprising nearly 1000 drugs and other xenobiotics.[3] They used the following clinical categories for grouping analytical data: 1) therapeutic: blood-plasma concentrations observed following therapeutically effective doses; no or only minimal side-effects (drugs); 'normal': concentrations associated with no or only minimal toxic effects (other xenobiotics). 2) Toxic: blood-plasma concentrations that produce toxicity/clinically relevant side-effects/symptoms. 3) Comatose-fatal: blood-plasma (comatose) concentrations and whole blood (fatal) concentrations reported to have caused coma and death, respectively. As the authors point out: "*whether published data for deaths refer to levels measured ante-mortem or post-mortem (femoral or heart blood) is, however, often unknown*."

A different approach to compile reference values for post-mortem toxicology was taken by Jones and Holmgren. They used highly sensitive and specific methods to determine the concentrations of drugs in femoral blood from 24876 forensic autopsies in Sweden. They presented the top-25 drugs identified in femoral venous blood representing all causes of death, their structural formula, limit of quantitation of the analytical method, number of occurrences, mean and median concentrations as well as upper 90th, 95th and 97.5th percentiles.[11]

A compilation of fatal and control concentrations of 83 drugs in post-mortem femoral blood was compiled by Druid and Holmgren based on Swedish toxicology data obtained under standardized conditions regarding sample site, sampling technique, analytical methods and sample storage and treatment. The data were collected from cases where the cause of death was: A) certified intoxication by one substance alone; B) certified intoxication by more than one substance and/or alcohol; and C) certified other cause of death without incapacitation due to drugs. The concentrations were compared with blood concentrations detected in suspected drugged drivers (D), and with previously published fatal and therapeutic concentrations.[12]

As in Sweden, in Finland all post-mortem forensic toxicology samples are analysed in one laboratory at the Department of Forensic Medicine of Hjelt Institute, University of Helsinki. The medico-legal autopsy rate in Finland is relatively high. In 2012 there were altogether 9982 medico-legal autopsies, i.e. 19.3 per cent of all deaths. In about 6500 cases of these a forensic toxicological analysis was undertaken and the samples underwent screening and quantification analysis for legal and illicit drugs and poisonous substances. In order to evaluate the general applicability of the concentration data by comparison with the Jones and Holmgren study, Launiainen and Ojanperä utilized the Finnish database with the analysis results from altogether 57903 post-mortem femoral venous blood samples taken during the 11-year study period between January 1st, 2000 and December 31st, 2010. The study provides reference data to aid interpretation of drug concentrations by listing the normal (median) and elevated concentrations of 129 drugs in femoral venous blood (Table 31.1). The authors concluded that the median post-mortem concentrations give an idea of the 'normal' post-mortem concentration range and the upper percentile concentrations indicate possible overdose levels. Furthermore, the study demonstrates that using clinical therapeutic ranges in plasma to interpret post-mortem toxicology results would commonly lead to misjudgement of a normal post-mortem concentration as a lethal level.[13]

The advantage of the above referred more recent compilations of post-mortem drug concentrations, in comparison to the earlier ones, is that they are based on much larger autopsy cohorts, better standardized sampling and can therefore assumed to give more reliable results, which facilitates the interpretation. Wherever possible, the advice of the forensic or analytical toxicologist should be taken about each case.

What is offered in the remainder of this chapter is a digest of information about such potentially lethal levels, culled from a variety of sources.

The choice of substances is arbitrary, but represents the most common medicines seen in suicidal and accidental poisoning.

Analgesics

Aspirin (acetylsalicylic acid) and salicylates

Aspirin is the most widely used therapeutic drug, being analgesic, antipyretic and anti-inflammatory. It was formerly very common as an agent of self-poisoning,

Table 31.1 Concentration distribution in post-mortem (PM) femoral blood and proportion of fatal poisonings for 129 drugs

	Drug	Cases N	LOQ mg/l	PM mean mg/l	PM median mg/l	PM upper percentiles mg/l			Therapeutic range in plasma[a] mg/l	Proportion of fatal poisonings %	PM blood/ plasma relationship[b]
						90th	95th	97.5th			
1	Acebutolol	85	0.25	11	0.84	25	86	100	0.2–2	20	1
2	Alprazolam	940	0.02	0.09	0.05	0.20	0.30	0.40	0.005–0.05	13	1
3	Aminophenazone, 4-methyl	330	2/3[c]	25	15	58	82	103	10[d]	1	1
4	Amiodarone	125	0.5	3.4	1.8	7.7	11	15	1–2	1	1
5	Amitriptyline	1589	0.1	1.5	0.40	2.9	5.5	8.8	0.05–0.3	27	1.3
6	Amlodipine	313	0.006	0.10	0.07	0.20	0.26	0.34	0.003–0.015	3	4.5
7	Amphetamine	565	0.04	0.91	0.28	2.1	3.7	6.2	0.02–0.1	12	2.8
8	Atenolol	415	0.2	1.3	0.64	2.6	4.6	6.9	0.1–1	6	1
9	Betaxolol	124	0.003	0.22	0.10	0.31	0.41	0.43	0.005–0.05	2	1.9
10	Biperiden	30	0.1	0.20	0.10	0.30	0.30	0.66	0.05–0.1	0	1
11	Bisoprolol	3633	0.01	0.12	0.05	0.17	0.26	0.43	0.01–0.1	1	1
12	Bupivacaine	49	0.2	1.2	0.40	1.6	3.0	4.3	0.5–1.5	0	0.80
13	Buprenorphine	671	0.0002	0.0033	0.0012	0.0058	0.0093	0.022	0.0005–0.005	45	1
14	Caffeine	22125	1/3[c]	4.0	3.0	7.5	10	13	4–10	0	0.75
15	Carbamazepine	1482	1/0.3[c]	7.9	6.2	13	19	27	2–8	2	1
16	Carvedilol	134	0.003	0.05	0.02	0.08	0.13	0.43	approx 0.02–0.15	0	1
17	Celiprolol	105	0.03	2.1	0.28	2.7	5.2	6.9	0.05–0.5	6	1
18	Cetirizine	99	0.001	0.41	0.10	0.92	1.9	2.9	approx 0.02–0.3	0	1
19	Chlordiazepoxide	1714	0.2	1.4	0.70	3.5	5.2	7.6	0.4–3	1	1
20	Chloroquine	47	0.2	12	1.3	43	62	69	0.02–0.5	15	2.6
21	Chlorpromazine	246	0.05	1.0	0.30	2.2	3.9	6.5	0.03–0.1	11	3.0
22	Chlorprothixene	519	0.1	1.7	0.30	3.0	5.2	9.0	0.02–0.3	18	1
23	Citalopram	3542	0.1	0.97	0.40	1.4	2.4	5.3	0.05–0.11	4	3.6
24	Clonazepam	77	0.01	0.06	0.03	0.10	0.20	0.31	0.02–0.08	5	1
25	Clozapine	445	0.1	2.5	1.1	4.4	8.9	17	0.35–0.6	13	1.8

(Continued)

Table 31.1 (Continued) Concentration distribution in post-mortem (PM) femoral blood and proportion of fatal poisonings for 129 drugs

	Drug	Cases N	LOQ mg/l	PM mean mg/l	PM median mg/l	PM upper percentiles mg/l			Therapeutic range in plasma[a] mg/l	Proportion of fatal poisonings %	PM Blood/ plasma relationship[b]
						90th	95th	97.5th			
26	Codeine	1903	0.02	0.72	0.16	1.8	3.2	5.1	0.03–0.25	23	1
27	Cyclizine	48	0.005	1.1	0.30	1.2	2.1	6.0	0.1–0.25	2	1.2
28	Desmethyldiazepam	9459	0.02	0.21	0.10	0.50	0.70	1.0	0.2–0.8	0	0.13
29	Dextromethorphan	54	0.1	0.69	0.40	1.6	2.2	2.8	0.01–0.04	15	10
30	Dextropropoxyphene	249	0.1	6.5	2.6	12	17	38	0.05–0.3	59	8.7
31	Diazepam	7404	0.02	0.17	0.09	0.4	0.6	0.8	0.1–2	0	0.90
32	Diclofenac	20	0.3/0.5	2.5	1.3	6.6	7.1	8.5	0.5–3	0	1
33	Diltiazem	315	0.1	2.5	0.30	1.8	7.9	22	0.03–0.13	9	2.3
34	Diphenhydramine	57	0.005	0.35	0.20	0.80	0.90	0.96	0.05–0.1	0	2.0
35	Dixyrazine	52	0.003	0.70	0.10	1.8	3.9	6.4	approx 0.3	42	0.33
36	Donepezil	102	0.003	0.23	0.20	0.41	0.49	0.60	approx 0.03–0.075	0	2.7
37	Doxepin	678	0.05	2.4	0.60	6.7	12	15	0.01–0.2	42	3.0
38	Duloxetine	109	0.01	0.37	0.14	0.64	1.1	2.4	0.03–0.12	8	1.2
39	Ephedrine	156	0.04	0.66	0.21	1.1	1.6	3.1	0.02–0.2	2	1.1
40	Ethylmorphine	71	0.02	0.44	0.10	1.3	2.6	2.8	0.3–0.6	6	0.33
41	Etoricoxib	55	0.5	3.5	1.2	4.2	5.5	6.8	1.3–3.6	0	0.92
42	Fentanyl	419	0.0001	0.012	0.0058	0.023	0.040	0.061	0.001–0.01[e]	12	1
43	Flecainide	101	0.2	4.7	1.9	9.8	19	23	0.4–0.8	18	2.4
44	Fluconazole	275	0.1	6.3	3.8	15	23	28	approx 1–5	0	1
45	Fluoxetine	649	0.2	0.80	0.50	1.6	2.5	3.6	0.12–0.5	3	1
46	Fluvoxamine	79	0.03	2.6	0.70	7.7	11	21	0.06–0.23	13	3.0
47	Furosemide	294	0.1	2.6	0.90	5.5	9.5	16.7	2–5	0	0.45
48	Gabapentine	135	1	29	11	60	103	157	approx 0.5–6	8	1.8

(Continued)

Table 31.1 (Continued) Concentration distribution in post-mortem (PM) femoral blood and proportion of fatal poisonings for 129 drugs

	Drug	Cases N	LOQ mg/l	PM mean mg/l	PM median mg/l	PM upper percentiles mg/l			Therapeutic range in plasma^a mg/l	Proportion of fatal poisonings %	PM Blood/ plasma relationship^b
						90th	95th	97.5th			
49	Galantamine	44	0.01	0.21	0.11	0.38	0.46	1.1	appr. 0.03–0.06	0	1.8
50	Glimepiride	177	0.01	0.31	0.03	0.26	0.61	1.2	0.09–0.5	1	0.33
51	Haloperidol	94	0.003	0.05	0.01	0.06	0.29	0.40	0.005–0.017	5	1
52	Hydroxycarbamazepine	475	5/3^c	27	22	52	66	92	10–35	0	1
53	Hydroxychloroquine	165	1	14	10	30	35	52	–0.1	14	100
54	Hydroxyzine	159	0.2	0.80	0.30	1.6	2.8	5.3	0.05–0.1	16	3.0
55	Ibuprofen	379	10	26	19	45	62	89	15–30	0	1
56	Indomethacin	9	0.5	1.2	1.1	1.6	1.7	1.8	0.3–1	0	1.1
57	Ketamine	118	0.1	1.1	0.50	2.2	4.1	6.3	1–6	1	0.50
58	Ketoprofen	80	0.3	3.2	1.3	5.7	7.6	16	approx 3.7	0	0.34
59	Labetalol	62	0.01	0.20	0.09	0.30	0.45	1.2	0.03–0.18	0	1
60	Lamotrigine	338	1/0.5^c	5.7	3.8	12	18	25	3–14	4	1
61	Levetiracetam	105	3	26	15	55	76	94	10–40	1	1
62	Levomepromazine	1602	0.1	0.99	0.40	1.9	3.2	5.0	0.005–0.025	23	16
63	Lidocaine	2391	0.1	0.81	0.40	1.8	2.8	4.1	1.5–5	0	0.27
64	Lithium	165	0.5	3.2	2.0	6.3	9.4	13	4–8	7	0.50
65	Lorazepam	802	0.01	0.06	0.03	0.10	0.20	0.30	0.08–0.25	0	0.38
66	MDMA	57	0.04	0.76	0.30	2.1	3.5	4.0	0.1–0.35	0	1
67	Melperone	161	0.05	1.5	0.40	3.3	9	14	0.03–0.1	32	4.0
68	Meprobamate	20	10	74	28	121	159	434	5–10	5	2.8
69	Mesoridazine	85	0.2	0.75	0.50	1.3	1.6	2.7	0.15–1	0	1
70	Metformin	1376	1	15	6	36	69	110	0.1–1	6	5.5
71	Methadone	207	0.05	0.59	0.40	1.3	1.8	2.2	0.1–0.5	43	1

(Continued)

Table 31.1 (Continued) Concentration distribution in post-mortem (PM) femoral blood and proportion of fatal poisonings for 129 drugs

	Drug	Cases N	LOQ mg/l	PM mean mg/l	PM median mg/l	PM upper percentiles mg/l			Therapeutic range in plasma[a] mg/l	Proportion of fatal poisonings %	PM blood/ plasma relationship[b]
						90th	95th	97.5th			
72	Methamphetamine	51	0.04	1.7	0.18	1.2	2.2	25	–0.1	10	1.8
73	Metoclopramide	681	0.05	0.21	0.10	0.4	0.6	0.7	0.05–0.15	0	1
74	Metoprolol	2078	0.05	0.96	0.20	1.1	2.0	5.0	0.035–0.5	2	1
75	Mianserin	387	0.05	0.37	0.20	0.70	0.97	1.9	0.015–0.07	7	2.9
76	Midazolam	172	0.02	0.14	0.07	0.40	0.54	0.84	0.04–0.1	2	1
77	Mirtazapine	2179	0.05	0.49	0.20	0.80	1.7	2.9	0.03–0.08	6	2.5
78	Moclobemide	135	0.1	15	1.9	41	61	120	0.3–1.0	13	1.9
79	Morphine	1094	0.02	0.20	0.07	0.37	0.67	1.1	0.01–0.1	4	1
80	Naproxen	202	10	43	33	78	100	120	20–50	1	1
81	Nifedipine	43	0.2	0.31	0.10	0.46	0.69	0.89	0.025–0.15	2	1
82	Nitrazepam	37	0.05	0.13	0.06	0.30	0.42	0.50	0.03–0.1	11	1
83	Olanzapine	1127	0.05	0.41	0.20	0.60	1.1	2.2	0.02–0.08	5	2.5
84	Orphenadrine	284	0.1	0.95	0.30	1.6	3.5	6.2	0.1–0.2	4	1.5
85	Oxazepam	6277	0.02	0.28	0.07	0.7	1.2	1.9	0.2–1.5	0	0.35
86	Oxcarbazepine	71	0.3	1.2	0.60	2.4	4.0	5.3	0.4–2	1	1
87	Oxycodone	1259	0.02	0.34	0.10	0.50	0.84	1.7	0.005–0.1	8	1
88	Paracetamol	3100	5/10[c]	32	15	62	110	190	10–25	2	1
89	Paroxetine	326	0.004	0.81	0.24	1.4	2.2	3.8	< 0.01–0.05	18	4.7
90	Perphenazine	283	0.01	0.08	0.01	0.08	0.18	0.36	0.001–0.02	2	1
91	Pethidine	46	0.1	0.50	0.30	0.90	1.1	1.9	0.1–0.8	2	1
92	Phenazepam	20	0.03	0.13	0.09	0.20	0.22	0.41	0.02–0.04	0	2.1
93	Phenobarbital	7	10	29	30	44	49	52	10–30	0	1
94	Phenylpropanolamine	65	0.05	0.49	0.14	0.98	1.4	2.5	0.1–0.5	0	1

(Continued)

Table 31.1 (Continued) Concentration distribution in post-mortem (PM) femoral blood and proportion of fatal poisonings for 129 drugs

	Drug	Cases N	LOQ mg/l	PM mean mg/l	PM median mg/l	PM upper percentiles mg/l			Therapeutic range in plasma[a] mg/l	Proportion of fatal poisonings %	PM blood/ plasma relationship[b]
						90th	95th	97.5th			
95	Phenytoin	37	10	14	13	22	25	31	5–15	0	1
96	Pholcodine	73	0.2	0.37	0.19	0.80	1.0	1.5	approx 0.07–0.2	3	1
97	Pregabalin	380	0.2	15	8.0	35	52	96	2–5	12	1.6
98	Promazine	339	0.1	4.5	1.2	11	19	26	0.01–0.05	42	24
99	Propofol	299	0.1/0.5[c]	2.5	1.3	5.0	8.2	11	approx 2–8	1	0.65
100	Propranolol	1078	0.02	1.8	0.13	5.4	11	16	0.02–0.3	15	1
101	Pseudoephedrine	127	0.05	0.81	0.24	1.5	2.4	3.6	0.5–0.8	0	0.48
102	Quetiapine	505	0.2	0.62	0.90	13	30	44	0.1–0.5	18	1.8
103	Quinine	322	0.2	3.5	1.0	4.7	23	34	1–7	3	1
104	Risperidone	622	0.002	0.014	0.004	0.029	0.044	0.086	approx 0.006	1	1
105	Rivastigmine	56	0.003	0.03	0.01	0.05	0.08	0.12	0.008–0.02	2	1
106	Ropivacaine	44	0.1	0.90	0.70	2.1	2.4	2.9	–1.5[f]	0	1
107	Salicylic acid	733	5/3[c]	48	11	83	150	430	20–200	2	0.55
108	Sertraline	445	0.1	0.55	0.30	1.0	1.7	2.3	0.05–0.25	5	1.2
109	Sildenafil	44	0.03	0.41	0.10	0.44	0.53	4.3	approx 0.05–0.5	2	1
110	Sitagliptin	68	0.01	0.61	0.36	1.3	2.1	2.8	0.05–0.38	0	1
111	Sotalol	120	0.25	2.8	2.0	5.5	8.1	11	0.5–3	1	1
112	Sulpiride	95	0.02	4.2	1.1	7.5	23	33	0.05–0.4	18	2.8
113	Temazepam	6283	0.02	0.34	0.09	0.90	1.4	2.3	0.02–0.15	2	1
114	Tetrahydrocannabinol	347	0.001	0.005	0.002	0.008	0.013	0.024	0.005–0.01	0	0.40
115	Theophylline	52	10	25	15	34	88	107	8–15	4	1
116	Thioridazine	283	0.1	1.3	0.70	2.9	4.3	5.3	0.1–2	6	1
117	Tizanidine	107	0.003	0.12	0.02	0.27	0.48	0.90	approx 0.015	7	1

(Continued)

Table 31.1 ***(Continued)*** Concentration distribution in post-mortem (PM) femoral blood and proportion of fatal poisonings for 129 drugs

	Drug	Cases N	LOQ mg/l	PM mean mg/l	PM median mg/l	PM upper percentiles mg/l			Therapeutic range in plasma[a] mg/l	Proportion of fatal poisonings %	PM blood/ plasma relationship[b]
						90th	95th	97.5th			
118	Topiramate	56	1/3[c]	16	8.8	21	27	40	2–10	2	1
119	Tramadol	1581	0.1	3.1	0.90	6.50	13	21	0.1–1	18	1
120	Trazodone	58	0.2	2.1	0.40	4.7	9.6	20	0.7–1	7	0.57
121	Trimethoprim	419	1	3.7	2.3	6.7	9.3	13	1.5–2.5	0	1
122	Trimipramine	248	0.1	1.1	0.60	2.4	3.4	4.7	0.01–0.3	19	2.0
123	Valproic acid	956	1/3[c]	51	28	75	110	230	40–100	2	0.70
124	Venlafaxine	824	0.1	3.7	0.60	5.7	17	33	0.1–0.4	17	1.5
125	Verapamil	174	0.1	2.1	0.35	5.9	9.7	13	0.02–0.25	16	1.4
126	Warfarin	425	0.5	0.81	0.70	1.1	1.6	2.4	1–3	0	0.70
127	Zolpidem	287	0.1	0.59	0.30	1.4	2.0	2.9	0.08–0.15	19	2.0
128	Zopiclone	2577	0.02	0.34	0.10	0.8	1.5	2.4	0.01–0.05	13	2.0
129	Zuclopenthixol	171	0.001	0.10	0.05	0.20	0.30	0.58	0.004–0.05	3	1

LOQ: limit of quantification; MDMA: 3,4-methylenedioxymethamphetamine.

[a–f] see original paper. Reproduced with kind permission of Launiainen T, Ojanperä I. Drug concentrations in post-mortem femoral blood compared with therapeutic concentrations in plasma. *Drug Test Anal* 2014;6:308–316. (doi: 10.1002/dta.1507. [Epub ahead of print]) both accidental in children and suicidal in adults. In Britain in the last two decades, its use as a self-poisoning agent has declined remarkably, so that fatalities are now rarely seen.

The therapeutic dose is usually 325–975 mg, that is, 1–3 tablets. Rarely, persons with an aspirin hypersensitivity may become ill or even die after therapeutic doses, suffering urticaria, angioneurotic oedema, hypotension, vasomotor disturbances and laryngeal and glottal oedema.

Patients on long-term salicylate therapy for arthritic or rheumatic diseases may take 3–5 g/day and slowly reach blood concentrations which would be in the lethal range if caused by acute overdoses. Those on 3 g/day have blood levels varying between 44 and 330 mg/l.[14]

Apart from deaths caused by hypersensitivity, death in an adult is unlikely with the ingestion of fewer than about 50 tablets, that is, about 16 g.[15] The blood concentration (measured as total salicylate), from a medicinal dose of 975 mg, ranges from about 30 to 100 mg/l (with a mean of 77) 2 hours after ingestion. There is a rapid fall to around 25 mg/l some 8 hours later.[16]

At autopsy, aspirin is one of the few medicines that may cause some gross abnormalities, though they are not particularly specific. Externally there is nothing to see, unless vomiting has taken place, when dark or even red, bloody gastric contents may be expelled. Rarely, there may be some haemorrhagic manifestations in the form of skin petechiae.

Internally, the stomach may still contain a mass of fused, unabsorbed tablets. These tend to start dissolving and then aggregate into a grey or dirty-white mass if a large number (several hundred) have been swallowed. The gastric mucosa may be eroded by the irritative, acidic substance. This may be localized in the stomach or spread widely across the fundus and cardia. The lining may be dotted with acute erosions, sometimes causing bleeding that may amount to a frank haematemesis. Black altered blood may lie in the stomach and pass into the intestine to form a melaena if survival is long enough. Mucosal petechiae and ecchymoses in the stomach, without actual erosive destruction, may be seen as part of a haemorrhagic result of the anticoagulant action of aspirin. Similar petechiae may be spread through other organs and especially serous membranes, particularly on the parietal pleura and epicardium. Even single tablets may cause a small ulcer if they stick to the stomach lining – this is sometimes seen incidentally at autopsy in non-poisoning cases, where a tablet has been swallowed shortly before death.

Post-mortem toxicology requires the usual samples of blood, urine, stomach contents and liver. The mass of aspirin in the stomach may remain for several days in life, forming a partly insoluble concretion that may retard the absorption of the drug. This is why it is always worth washing out the stomach of a live victim, as a large proportion of the aspirin may be removed before it can cause systemic effects. With the advent of soluble aspirin or effervescent preparations, this aspect is lost as no such insoluble bolus forms. At autopsy, part of such a mass can be sent for analysis, whilst quick 'spot' tests can be carried out on another part. Such quick chemical confirmation may be performed in the autopsy room itself, by using a 10 per cent solution of ferric chloride. If a small quantity is added to a urine sample or to the surface of the tablet mass, an immediate purple–blue colour suggests aspirin. This is by no means specific, but is merely suggestive. If negative, however, then aspirin can be virtually discounted. These are only rapid screening methods and by no means replace proper laboratory analysis.

Toxic blood levels (measured as total salicylate) begin at about 300–500 mg/l, though both death and survival are consistent with far higher or lower levels.[3] Blood concentrations in fatal cases may range from about 60 to 7300 mg/l, some authorities suggesting that 500 mg/l is an average minimum level. The liver concentration in fatalities varies from 2.5 to 1000 mg/kg and urine salicylate from 20 to 1350 mg/l, emphasizing the wide levels that are compatible with life.[17] Salicylates have a rather slow clearance rate from the blood, the half-life being up to 1 day in some massive overdoses. Salicylates may exhibit post-mortem redistribution.[15]

Paracetamol

Paracetamol is also known as acetominophen, *N*-acetyl-*p*-aminophenol or 49-hydroxyacetanilide. It is an analgesic and antipyretic, without the anti-inflammatory properties of aspirin, for which it is often used as an alternative because of the lack of gastric irritation.

In wide use, especially in combination with other drugs such as codeine and dextropropoxyphene, paracetamol is one of the most common agents in self-induced poisoning by medicinal products. It is used alone in therapeutic doses of up to 500 mg. Overdoses of 20 g or more are potentially lethal, but much less is needed in combination with other drugs, such as propoxyphene. Paracetamol is a potent liver poison, as a small proportion is converted by the liver enzyme 'P450' (microsomal mixed function oxidase) into a toxic compound, probably *N*-acetyl-*p*-benzoquinone. Normally, glutathione and other sulphydryl compounds detoxify this substance, but in overdose, these are exhausted and the toxic agent causes a profound centrilobular hepatic necrosis. The concurrent administration of other drugs, such as phenobarbitone or phenytoin in epileptics or chronic alcoholism, activate the P450 enzyme and worsen the toxicity through this mechanism.

At autopsy there is nothing specific to observe in the gastrointestinal tract. In massive overdosage, there can rarely be rapid death from a direct depressive action on the central nervous system, but most deaths are delayed 2–4 days while liver failure develops. At autopsy, the liver may be enlarged, but is often under the normal weight of 1500 g. It may be pale yellow or tan, or the damage may be only visible histologically, when a centrilobular necrosis is seen. Renal changes in the form of tubular necrosis may also be present and occasionally myocardial fibre damage may be visible histologically.

Analytically, the therapeutic range of plasma concentrations 6 hours after a 324 mg dose is 2–6 mg/l, though some records claim peak levels of up to 25 mg/l. The plasma half-life is a guide to hepatotoxicity, it being dangerous to have a half-life of more than 2 hours at a level of 300 mg/l at 4 hours after ingestion.[15] Typical blood levels in overdoses when at least 10–15 g have been taken are 100–400 mg/l, with an average around 250. The urine may contain 150–800 mg/l, but all levels depend on dose and survival time. Paracetamol may exhibit post-mortem redistribution.

The inclusion of other drugs, especially dextropropoxyphene (and, of course, alcohol), may markedly reduce the level needed for a fatal outcome. Paracetamol was the most frequently detected substance in a compilation of post-mortem femoral blood concentrations of drugs based on a selection of 15800 samples sent to the Department of Forensic Chemistry in Linköping, Sweden, during 1992–95.[12] In their series of 139 fatal intoxications with paracetamol in combination with other drugs and/or alcohol, the median concentration of paracetamol was 170 mg/l (range 90–320).

Antidepressant drugs

The tricyclic antidepressants are frequently involved in self-poisoning, partly associated with the type of patient for whom they are prescribed.

Amitriptyline, dothiepin, doxepin and trimipramine have additional sedative properties. Those with little or no sedating action include protriptyline, nortriptyline, imipramine, clomipramine, iprindole, lofepramine, desipramine and butriptyline.

Tetracyclic antidepressants include maprotiline and mianserin. Other types include the monoamine oxidase inhibitors, which are well known to have dangers related to the concurrent ingestion of other drugs and foods, especially those with sympathomimetic action and tyramine content, such as rich cheese, yeast extracts, red wine and beans. Dangerous hypertension may ensue with the risk of cerebrovascular haemorrhage. Drugs of this class include phenoxypropazine, tranylcypromine, isocarboxazid and phenelzine.

Reis *et al.* published a compilation of reference concentrations of 15 antidepressant drugs based on a detailed analysis of femoral blood samples from 8591 medico-legal autopsies in Sweden between 1992 and 2005. The postmortem data (n = 2737) comprised the following groups: Group A (n = 330) certified deaths involving intoxication with a single antidepressant drug; Group B (n = 864) certified deaths involving intoxication with more than one drug and/or with a significant concentration of ethanol; Group C (n = 1800) were certified other causes of deaths under circumstances not involving incapacitation by drugs. These groups were compared with a therapeutic drug monitoring material (Group T; n = 16809).[18]

The benzodiazepines

These widely used drugs are employed for their sedative and tranquillizing effects. A large number of both 1,4- and 1,5-benzodiazepines are available, divided into short-acting, intermediate-acting and long-acting compounds.

Long-acting benzodiazepines include: flurazepam, nitrazepam, diazepam, ketazalam, chlordiazepoxide, clobazam, chlorazepate, medazepam and alprazolam. Intermediate-acting benzodiazapines include: loprazolam, lormetazepam, temazepam, flunitrazepam, lorazepam, bromazepam and oxazepam. A short-acting benzodiazepine is triazolam.

The phenothiazines

This group of tranquillizer drugs includes: haloperidol (butyrophenone), chlormethiazole, chlorpromazine, fluphenazine, diphenylbutylpiperidine, promazine, trifluoperazine and prochlorperazine.

The autopsy appearances are non-specific and toxicology may resolve any diagnostic problems if the death has occurred fairly soon after ingestion – which may often not be the case, when history and ante-mortem investigations can provide the only answer.

The barbiturates

The massive problem posed by therapeutic administration of barbiturates until about 30 years ago has largely abated in countries with a responsible medical profession, which voluntarily refrained from the prescription of these drugs except where specifically indicated. Their use as sleeping tablets and general soporific sedative agents led to widespread abuse, so that at one time they were easily the most common agent of drug addiction. The development of non-barbiturate hypnotics, such as the benzodiazepines, helped to remove the need for the older and more lethal compounds.

Barbiturates exist in many forms, the best classification (which relates to their degree of toxicity) being their speed of action:

- Long-acting barbiturates: barbitone, phenobarbitone and phenytoin, which is still prescribed for epilepsy.
- Intermediate-acting barbiturates: amylobarbitone, sodium amytal, pentobarbitone, allobarbitone, butobarbitone and pentobarbitone.
- Short-acting barbiturates: hexobarbitone, cyclobarbitone, secobarbital and thiopentone.

Much lower blood levels will be found in fatal poisonings in the short-acting group as death may occur more quickly from the usual mode of action, a central depression of the respiratory centres. The author (BK) has knowledge of a death within 20 minutes of taking a massive overdose of secobarbital (Seconal).

At autopsy, the signs are of general cardiorespiratory failure, with often a cyanotic, congestive appearance. Though non-specific, probably the congested lungs in acute barbiturate poisoning are more intense than in any other condition. These organs may be almost black and the whole venous system is engorged with dark, deoxygenated blood. There may be ‘barbiturate blisters’ on dependent parts of the skin surface, especially buttocks, backs of thighs, calves and forearms, though as discussed in the chapter on carbon monoxide poisoning, these blisters are common to all states of deep coma.



Figure 31.2 Damage to the lips and face from regurgitation of gastric contents. This was a suicide from sodium amytal, the very alkaline poison being mixed with altered blood from the eroded gastric mucosa.

Internally there may be local signs of erosion from the drug itself. The gastric mucosa may be badly damaged from the alkaline attack of drugs such as sodium amytal which, being the sodium salt of a weak organic acid, hydrolyses in the stomach. The fundus may be thickened, granular and haemorrhagic. The cardia and lower oesophagus may be eroded from reflux and, if the victim regurgitates, then black, altered blood may appear at the nose and mouth (Fig. 31.2).

The capsules of certain barbiturates also leave characteristic traces in the mouth, oesophagus and stomach. The colour varies with the manufacturer, but the turquoise-blue of sodium amytal capsules may stain the stomach contents and even be visible through the wall of the intestine when the abdomen is opened. Other pigmented gelatine capsules can be red, yellow or blue. As with so many other drugs, combination with alcohol greatly increases the dangers of a fatality.

Restrictions to prescribe barbiturates in Britain, Australia, Norway, and Sweden resulted in fall of deaths from these drugs.[19,20]

Insulin poisoning

Formerly a rarity, death from parenteral administration of insulin is now not uncommon. The Beverley Allitt case in Britain in 1991 showed that multiple deaths can occur, especially where medical or nursing staff are concerned, as well as those in proximity to diabetics, as both groups may have access to insulin.[21]

Another change is the relative ease with which analysis of body fluids and tissue can be carried out now, compared with the great technical difficulties of only a few years ago, so that fewer such deaths may be missed from lack of reliable insulin assays.

Fatal insulin toxicity may be accidental, suicidal or homicidal.[22–32] The accidental fatalities are usually examples of medical error, mostly from misreading the label on the box or ampoule. A former student of the author (BK), on the fourth day of her first intern post, gave ten times the dose of insulin to a patient during a pituitary function test, by wrongly assuming that the stated number of units written on the box were the total ampoule contents, instead of being the strength per millilitre.

Suicide by insulin is not uncommon; the author (BK) has seen it given into a saline drip by a doctor and also injected into the abdominal wall by a non-diabetic who stole it from her diabetic neighbour's refrigerator.

As stated, homicide and attempted homicide have given rise to some notorious cases, both in the UK and the USA. In one case known to the author (PS), a previously healthy 48-year-old male was delivered unconscious to the emergency unit because of a suspicion of decompression sickness. The treatment was aborted as the patient was found to be hypoglycaemic (nadir serum glucose 0.3 mmol/l) and treatment and diagnostics of hypoglycaemia commenced. Serum samples drawn at admittance were stored frozen, whereby it was possible to show retrospectively that, while the concentration of insulin in serum was high (75 mU/l, increasing further to over 240 mU/l in the next few hours), concentration of C-peptide was low (below detection limit of 0.1 nmol/l) at the hypoglycaemic stage, suggesting that the patient had received exogenous insulin somehow, and the police were informed. Due to severe hypoglycaemic brain damage, the patient remained in a vegetative state for 2 months before dying of multiorgan failure. Circumstantial evidence obtained during the ensuing criminal investigation was considered by the court to prove the patient's wife (a nurse) guilty of murder.[27]

Insulin is, of course, inactive orally and has to be given by injection to perform its hypoglycaemic effect. At autopsy, where either from the circumstances or the finding of needle marks, insulin is a possibility, peripheral blood samples and skin and underlying tissue from the injection site should be carefully preserved, together with control skin from another site.

The fine needles usually used by diabetics may leave virtually no mark on the skin. The author (BK) has tested some such needles on cadaver skin and found that, often, the mark cannot be seen immediately after withdrawal, unless a small vessel has been damaged.

Although insulin has been recovered many days, even weeks, after death, the sooner the better as far as collecting samples is concerned. Serum should be separated from red cells and the former frozen until sent to the analysts, unless whole blood can be sent straight away. Skin and tissue samples should either be frozen or kept in the refrigerator – not fixed. Porcine or bovine insulin can be detected as such but, if therapeutic insulin is of human origin, then it cannot be distinguished on analysis from the patient's own insulin. As well as immunoassay of the insulin itself, the measurement of C-peptide, produced on a one-to-one basis by the pancreas, assists in distinguishing endogenous from exogenous insulin. All such interpretations are a matter for specialists in this field, upon whose advice the pathologist must rely.

Attempting to prove insulin-induced hypoglycaemia by measuring glucose levels in human post-mortem fluids is impracticable, due to the unreliability of such estimations after death. Vitreous humour is recommended as the matrix of choice for estimation of ante-mortem glucose metabolism.[33,34] The glucose concentration in vitreous humour tends to decrease in the early post-mortem period, and then stabilises.[33,35] Therefore, low vitrous glucose level does not necessarily indicate ante-mortem hypoglycaemia.[33] This initial drop in glucose concentration corresponds to a steeper rise in lactate concentration.[35]

Traub, Coe and more recently Hess *et al*. suggested that the assessment of glucose metabolism has to be based on a combination of glucose and lactate levels.[36–39] However, other authors have postulated that the use of the sum value of glucose and lactate does not add any further information but, moreover, could lead to an overestimation of fatal cases, such as diabetic ketoacidosis.[35,40,41]

References

1 Centers for Disease Control and Prevention. Unintentional poisoning deaths – United States, 1999–2004. *Morb Mortal Wkly Rep* 2007;56:93–6.

2 Muazzam S, *et al*. Differences in poisoning mortality in the United States, 2003–2007: epidemiology of poisoning deaths classified as unintentional, suicide or homicide. *West J Emerg Med* 2012;13(3):230–8.

3 Schulz M, *et al*. Therapeutic and toxic blood concentrations of nearly 1,000 drugs and other xenobiotics. *Crit Care* 2012;16(4):R136.

4 Murphy SL, Xu J, Kochanek KD. Deaths: Final Data for 2010. *National Vital Stat Rep* 2013;61(4):167.

5 Centers for Disease Control and Prevention. Number of Deaths From Poisoning, Drug Poisoning, and Drug Poisoning Involving Opioid Analgesics – United States, 1999–2010. *Morb Mortal Wkly Rep* 2013;62(12):20.

6 Ferne, RE. Post-mortem clinical pharmacology. *Br J Clin Pharmacol* 2008;66(4):430–43.

7 Linnet K. Postmortem drug concentration intervals for the non-intoxicated state – a review. *J Forensic Leg Med* 2012;19(5):245–9.

8 Jones GR. Interpretation of results. In: Siegel JA, Saukko PJ (eds). *Encyclopedia of Forensic Sciences*. Waltham: Academic Press, 2013, pp. 243–8.
9 Osselton MD, Hammond MD, Moffat AC. Distribution of drugs and toxic chemicals in blood. *J Forensic Sci Soc* 1980;20(3): 187–93.
10 Holmgren P, *et al*. Stability of drugs in stored postmortem femoral blood and vitreous humor. *J Forensic Sci* 2004;49(4):820–5.
11 Jones AW, Holmgren A. Concentration distributions of the drugs most frequently identified in post-mortem femoral blood representing all causes of death. *Med Sci Law* 2009;49(4): 257–73.
12 Druid H, Holmgren P. A compilation of fatal and control concentrations of drugs in postmortem femoral blood. *J Forensic Sci* 1997;42(1):79–87.
13 Launiainen T, Ojanpera I. Drug concentrations in post-mortem femoral blood compared with therapeutic concentrations in plasma. *Drug Test Anal* 2014;6(4):308–16.
14 Gupta N, Sarkissian E, Paulus HE. Correlation of plateau serum salicylate level with rate of salicylate metabolism. *Clin Pharmacol Ther* 1975;18(3):350–5.
15 Baselt RC. *Disposition of Toxic Drugs and Chemicals in Man*, 8th edn. Baselt RC (ed). Foster City: Biomedical Publications, 2008, xviii.
16 Hollister LE, Kanter SL. Studies of delayed-action medication. IV. Salicylates. *Clin Pharmacol Ther* 1965;6:5–11.
17 Rehling CJ. Poison residues in human tissues. *Prog Chem Toxicol* 1967;3:363–86.
18 Reis M, *et al*. Reference concentrations of antidepressants. A compilation of postmortem and therapeutic levels. *J Anal Toxicol* 2007;31(5):254–64.
19 Mann JJ, *et al*. Suicide prevention strategies: a systematic review. *JAMA* 2005;294(16):2064–74.
20 Sarchiapone M, *et al*. Controlling access to suicide means. *Int J Environ Res Public Health* 2011;8(12):4550–62.
21 Hunt J, Goldring J. The case of Beverley Allitt. *Med Sci Law* 1997;37(3):189–97.
22 Sturner WQ, Putnam RS. Suicidal insulin poisoning with nine day survival: recovery in bile at autopsy by radioimmunoassay. *J Forensic Sci* 1972;17(4):514–21.
23 Hansch CF, De Roy G. An extraordinary case: suicide with insulin in a grave dug by the victim himself. *Z Rechtsmed* 1977;79(4):319–20.
24 Haibach H, Dix JD, Shah JH. Homicide by insulin administration. *J Forensic Sci* 1987;32(1):208–16.
25 Lutz R, *et al*. Insulin injection sites: morphology and immunohistochemistry. *Forensic Sci Int* 1997;90(1–2):93–101.
26 Kernbach-Wighton G, Puschel K. On the phenomenology of lethal applications of insulin. *Forensic Sci Int* 1998;93(1):61–73.
27 Koskinen PJ, *et al*. Importance of storing emergency serum samples for uncovering murder with insulin. *Forensic Sci Int* 1999;105(1):61–6.
28 Marks V. Murder by insulin. *Med Leg J* 1999;67(Pt 4):147–63.
29 Batalis NI, Prahlow JA. Accidental insulin overdose. *J Forensic Sci* 2004;49(5):1117–20.
30 Marks V, Richmond C. Kenneth Barlow: the first documented case of murder by insulin. *J R Soc Med* 2008;101(1):19–21.
31 Samuels A. Murder by insulin. *Med Leg J* 2008;76(1):34.
32 Marks V. Murder by insulin: suspected, purported and proven – a review. *Drug Test Anal* 2009;1(4):162–76.
33 Forrest AR. ACP Broadsheet no 137: April 1993. Obtaining samples at post mortem examination for toxicological and biochemical analyses. *J Clin Pathol* 1993;46(4):292–6.
34 Boulagnon C, *et al*. Post-mortem biochemistry of vitreous humor and glucose metabolism: an update. *Clin Chem Lab Med* 2011;49(8):1265–70.
35 Zilg B, *et al*. Postmortem identification of hyperglycemia. *Forensic Sci Int* 2009;185(1–3):89–95.
36 Traub F. [Method for the detection of lethal glucose metabolism disorders in the corpse (diabetes mellitus and hypoglycemia)]. *Zentralbl Allg Pathol* 1969;112(4):390–9.
37 Coe JI. Postmortem chemistries on human vitreous humor. *Am J Clin Pathol* 1969;51(6):741–50.
38 Coe JI. Postmortem chemistry of blood, cerebrospinal fluid, and vitreous humor. *Leg Med Annu* 1977;1976:55–92.
39 Hess C, Musshoff F, Madea B. Disorders of glucose metabolism – post mortem analyses in forensic cases: part I. *Int J Legal Med* 2011;125(2):163–70.
40 Palmiere C, Mangin P. Postmortem chemistry update part I. *Int J Legal Med* 2012;126(2):187–98.
41 Palmiere C, *et al*. Is the formula of Traub still up to date in antemortem blood glucose level estimation? *Int J Legal Med* 2012;126(3):407–13.

CHAPTER 32

Death from Narcotic and Hallucinogenic Drugs

- Introduction
- Morphine and other opioid drugs
- Toxicological results
- Methadone
- Cocaine
- Designer drugs
- References

Introduction

The consumption of illicit drugs is a growing threat to the health of people worldwide. The first international convention on narcotic drugs: the Single Convention on Narcotic Drugs adopted by the UN in 1961, together with the Convention on Psychotropic Substances of 1971 and the UN Convention against Illicit Traffic in Narcotic Drugs and Psychotropic Substances of 1988, constitute the legal basis for the international co-operation to address the world drug problem.

In the UK the term 'illicit drugs' is used to describe drugs that are controlled under the *Misuse of Drugs Act 1971* (MDA), where drugs are listed as Class A, B or C under schedule 2 of the Act, depending on the harm they cause. For example, Class A drugs cause the most harm and include cocaine, ecstasy, heroin, magic mushrooms, methadone, methylamphetamine and injectable amphetamine and lysergic acid diethylamide (LSD); Class B drugs include amphetamine, barbiturates, cannabis and, since April 2010, synthetic cathinone derivatives including mephedrone, as well as, since 13th June 2012, pipradrol related compounds including desoxypipradrol (2-DPMP) and diphenylprolinol (D2PM); and Class C includes drugs include anabolic steroids, tranquillisers, ketamine, benzodiazepines and, since December 2009, over 140 synthetic cannabinoids, as well as piperazines (such as benzylpiperazine; BZP) and gamma-butyrolactone (GBL).[1] These substances are discussed solely from the point of view of the pathologist dealing with fatal cases.

Drugs of dependence may be absorbed orally, by intravenous, subcutaneous or – rarely – intramuscular injection, by smoking, or by nasal sniffing. The routine at autopsy, in respect of obtaining samples for toxicological analysis, is altered according to the route of administration. As mixing of drugs and addition of non-narcotic drugs is common, it is the usual practice to take a wide range of samples even if the primary route is known with some degree of certainty. For example, an addict dying 'on the needle' where intravenous injection is obvious, will still have stomach contents taken for investigation. The standard samples should be taken, as described in a previous chapter, comprising several samples of venous blood (one with fluoride), stomach and contents, liver and urine. In some circumstances, additional samples such as bile, cerebrospinal fluid and vitreous humour may be taken, as well as brain or kidney. The great advances in the analytical techniques allow the analysis of drugs also in other biological samples, such as saliva, sweat and hair. Hair analysis can also provide evidence of long-term exposure to drugs (weeks, months or years), because most drugs, if not all, incorporate in hair and are relatively stable.[2,3] At least 50 mg of hair should be collected, cutting about a pencil thickness of strands of hair as close to the skin as possible from the back of the head, dried and stored in aluminium foil, envelope or a plastic tube at room temperature.[3]

When the drug has been injected, then an ellipse of skin around the injection mark, extending down through the subcutaneous tissue to the muscle, should be excised, along with a control area of skin from another non-injected site. These should be refrigerated, not fixed in formalin, until delivery to the laboratory can be arranged. Full histology should always be taken, especially if drugs have been injected, as foreign substances may be discovered as embolic particles, especially in the lungs. Pulmonary granulomata are well-known histological features of 'mainlining' addicts taking impure drugs intravenously, as the lung capillaries filter out coarse particulate matter used to dilute the active narcotic.[4–13] Talc (hydrous magnesium silicate; $Mg_3Si_40_{10}[OH]_2$) is particularly prone to form granulomata, sometimes with foreign body giant cells.[14,15] Under polarized light, doubly refractile particles may be seen in the centre of the reactive nodules. Sometimes, strands of cotton may form foreign bodies, derived from the cloth strainer used to filter particles crudely from the drug solution before injection. Also inhaled talc acts as a pulmonary irritant and foreign body granulomas have been reported in abusers sniffing drugs.[16–18]

Siderophages were also claimed to be increased in these lungs, compared with healthy young adult controls. However, Lockemann and Püschel, studying lungs stained for iron with reaction, found conflicting results in two large series and conclude that the pathognomonic value of these cells in drug takers is uncertain.[19]

If drugs may have been taken by the nasal route, such as cocaine and heroin, then dry swabs from each nostril should be taken.

Morphine and other opioid drugs

Morphine is the major representative of the general group of opioids, which comprise natural opium and a whole series of chemically related derivatives. They may be taken orally or injected and several, such as crude opium and heroin – may be absorbed by inhaling smoke. Morphine itself is poorly absorbed from the gastrointestinal tract; heroin can be taken via the nasal mucosa.

The group consists of opium, morphine, heroin (diacetyl morphine), codeine (dimethyl morphine), dihydrocodeine, etorphine, methadone, papaverine, pethidine, dipipanone, dextromoramide, dextropropoxyphene, pentazocine, cyclazocine, diphenoxylate, buprenorphine, tramadol, fentanyl and many more.

Autopsy appearances

The autopsy findings in deaths from all these drugs are relatively non-specific. Toxicological analysis and expert interpretation of the results are necessary for the proper elucidation of the deaths, but certain features can be useful pointers. The first is the presence of injection marks (Fig. 32.1). When fresh, they look just like any other needle mark commonly seen from therapeutic or diagnostic procedures. They are commonly on the arms, either in the classical position in the antecubital fossa on the front of the elbow, or into one of the prominent veins of the forearms or dorsum of the hand. The left side is favourite as most people are right-handed, but in habitual users, sclerosis of the veins may lead to the arms being used randomly. The veins of the dorsum of the foot may be used when the hands and arms have become unusable because of thrombosis and scarring. Less common sites are in the thighs but here, as with the abdominal wall, the injections may be subcutaneous, rather than intravenous. This mode of injection is known as 'skin-popping' and can lead to areas of subcutaneous sclerosis, fat necrosis, abscesses and, if the injections are deeper into the muscle, to chronic myositis.[20–22] Other external signs may be tattoos, often bizarre and connected with the drug subculture (Fig. 32.2). One specific type of tattooing



Figure 32.1 Fresh injection marks on the arm of a drug addict.



Figure 32.2 Tattoo inside the lower lip of a narcotic drug dealer.

consists of numerals such as '3' and '5' referring to the 3rd and 5th letters of the English alphabet C and E, which stand for cocaine and 'eater', a drug abuser who takes drugs orally. Numbers '8' and '13' stand for the 8th and 13th letter, H for heroin and M for marijuana. The numbers '99.9' and '999' mean 'very pure heroin.'[23]

Where chronic addiction has taken its toll, the body may be emaciated, dirty and show signs of infection, especially in the form of skin ulceration. Rarely, there may be necrosis or even loss of phalanges from thrombotic or septic emboli. Old injection marks, sometimes with associated bruising, may be found, the bruising undergoing the usual spectrum of colour changes if not recent. The veins may show overlying fibrosis where phlebitis has occurred, or old venous thrombosis with firm cord-like vessels under the skin.

Where sudden death has occurred in habituated addicts, there may be gross pulmonary oedema, with a plume of froth exuding from the mouth or nostrils, suggestive of drowning. As Polson *et al.* point out, this may cause some confusion when the victim is found dead in a bathroom, a common venue (along with toilets) for drug administration.[24] This pulmonary oedema is sometimes a striking feature of rapid death in those who are habituated to opioid drugs, especially heroin. It does not seem to occur in novices to the habit, who tend to die in a different way, from a sudden primary cardiac arrest. The oedema may be blood-tinged, again causing confusion with drowning. The cause is not known, but is often attributed to some 'allergic' phenomenon, a rather unsatisfactory explanation. It has been claimed that it sometimes may be caused by adulterants in the drugs, such as quinine, but this is doubtful.

The death may be so rapid that the needle may still be found in the vein when the body is discovered, often in a public lavatory or sometimes in the presence of other addicts, who may then be charged with criminal offences in relation to the death as well as with possessing and using illicit drugs.

There are no other more specific autopsy appearances. Though clinically, a constricted pupil is a prominent sign of morphine administration, after death, any kind of pupil alteration may occur. They may remain small, dilate, or become quite unequal – this applies to any form of death, so no specificity exists for opioid poisoning.

Among new recruits to drug dependence, some die at the first injection of a parenteral dose of heroin or morphine. The mode of death appears to be a cardiac arrest following an arrhythmia and ventricular fibrillation, but no morphological signs can be found. It may be related to sensitization of the myocardium to catecholamines by the drug, the excitement and apprehension being similar to the triggers that seem to cause sudden death from falling into cold water or having a criminal abortion.

The other aspect of autopsies on drug-dependent victims is the risk of infection to pathologist and mortuary staff. Addicts form a high-risk group for both hepatitis B and C, human immunodeficiency virus (HIV) and acquired immunodeficiency syndrome (AIDS). The way in which such autopsies are dealt with in different jurisdictions must vary widely, but it is common practice for HIV and hepatitis testing to be carried out prior to autopsy, unless the policy of the particular autopsy service is to accept all cases with appropriate safety techniques.[25] The analytical laboratory must be informed of any high-risk samples being sent to them, and some will be reluctant to handle blood or tissue samples with positive serology. The pathologist may well refuse to carry out an autopsy on a suspect body until a negative result has been returned on a sample of blood taken (with adequate precautions) from the femoral vein. If positive for hepatitis B or C virus, and especially if the victim shows any signs of hepatic involvement such as jaundice, then many pathologists would decline to carry out a full autopsy unless there are pressing reasons. In that case, scrupulous safety precautions must be taken (see Chapter 1).

In relation to AIDS and HIV positivity, opinions and practices vary widely in the present state of knowledge. It seems obvious that the HIV virus is not in the same category of infectivity as hepatitis. Though autopsies on patients dying of clinical AIDS are routinely performed, there is a difference in the potential risk of a literally 'cold' autopsy being performed on a hospital death after a day or two in the mortuary refrigerator, compared with the urgent activities of a forensic pathologist who may be called upon to conduct an autopsy on a still-warm corpse within a few hours of a suspicious death. However, as mentioned in Chapter 1, HIV may remain viable for many days after death.

Toxicological results

As with all deaths from toxic substances, the interpretation of laboratory analytical results may present considerable difficulties. There may be a long delay between the administration of the drug and death, during which time the blood, urine and even tissue levels may decline, or even disappear. Many drugs break down rapidly in the body and their metabolites may be the only recognizable products of their administration. In some cases, data on lethal blood levels may be imperfectly known and great variations in personal susceptibility may make the range of concentrations found in a series of deaths so wide as to be rather unhelpful.

As mentioned above, some persons die rapidly after the first episode of taking a 'normal' dose of a drug because of some ill-understood personal idiosyncrasy and here quantitative analysis may not assist.

Where habituation and tolerance has developed, drug users may have concentrations in their body fluids and tissues far higher than lethal levels published for non-habitués. In general, the great usefulness of toxicological analysis is both qualitative and quantitative. The former will show what drugs have been taken in the recent past; the length of time that drugs or their metabolites persist in different fluids and tissues varies widely.

The quantitative analysis can be useful, especially when the results reveal high levels – into the toxic or lethal ranges. These ranges are usually obtained anecdotally from surveys of large numbers of deaths but, as stated, can differ in terms of minimum and maximum values from different laboratories. The problems of idiosyncratic sensitivity and tolerance cause such published ranges to act only as a general yardstick and deaths that occur outside the ranges (usually off the lower end) cannot be excluded from having been caused by the drug in question if other factors may have been involved. Such factors include the presence of other drugs or alcohol, or both, delayed death and abnormal sensitivity.

Thus the analysis is not the final arbiter of the cause of death, although it is a highly important component of the whole range of investigation. The pathologist has the duty to correlate and interpret all known facts. He must fit the circumstances, the presence of natural disease, trauma and other toxic substances with the laboratory findings, to arrive at the most reasonable cause of death.

The advice of the toxicology laboratory is vital in this process, especially in relation to known lethal ranges and the significance of metabolites, but the analysts should not become the sole arbiter of the cause of death.[26–32]

Methadone

Methadone has come to be used primarily as a treatment for established heroin dependency, but unfortunately appears to substitute one form of addiction for another, albeit somewhat less lethal, though experience in Scotland has shown that deaths from methadone may exceed those from heroin, whose use it was intended to supplant.[33] Its clinical uses are as an analgesic more powerful than morphine, with the advantage that it is almost as potent by oral administration as by injection. It has strong and often undesirable sedative properties, however, and is virtually as addictive as the other opioids.

Many deaths occur from its misuse, when obtained either legitimately for the replacement of heroin dependency or on the large illegal market. Most deaths follow oral administration and appear to be due to lack of tolerance, in the absence of which even 50 mg may be lethal, though some recipients appear to die at the outset of the replacement treatment.[34] According to Caplehorn and Drummer relatively low therapeutic concentrations of benzodiazepines may increase the risk and contribute to methadone toxicity by increasing upper airway obstruction.[35,36]

In post-mortem samples, the liver has the highest concentration. The fatal levels found on analysis overlap those found in persons on maintenance doses for heroin replacement, making interpretation difficult. The blood levels published by Manning *et al.* in 10 fatal cases showed: blood: mean 1.0 mg/l (range 0.4–1.8); liver: mean 3.8 mg/l (range 1.8–7.5); bile: mean 7.5 mg/l (range 2.9–18.0); and brain: mean 1.0 mg/l (range 0.5–1.4).[37] In another series comprising 50 adult deaths analysed by Milroy and Forrest, where methadone poisoning was given as the sole cause of death, the mean methadone concentration was 0.58 mg/l (median, 0.44; range, 0.08–2.7).[38]

Hallucinogens

Few of the hallucinogenic drugs are primary causes of death, but some may lead to traumatic deaths because of the abnormal behaviour of the person who is under their influence. For example, the victim of a LSD 'trip' may be under the impression that he can fly and thus project himself from a high window. Some drugs, however, may have direct toxic effects, though, as with so many drugs of dependence, the autopsy findings are negative or totally non-specific.

Phencyclidine

Chemically this is 1-(1-phenylcyclohexyl) piperidine hydrochloride, known as PCP or 'angel dust' among many other nicknames. It is often used in combination with other drugs of addiction.[39–49] A number of deaths have been reported from its use, a variety of modes including hyperthermia, intracranial haemorrhage and high output cardiac failure.

Phencyclidine is excreted in the urine for a long time after ingestion and autopsy samples may be positive for up to 1 week.

Lysergic acid diethylamide

The well-known LSD, which takes its acronym from the German 'lysergsäurediäthylamid', is a powerful hallucinogenic which is not fatal in itself, as mentioned above. It is an indole alkaloid derivative, of which other members are psilocybin and psieocin, contained in the Mexican mushroom (*Psilocybe mexicana*).[50–53]

Mescaline, obtained from the cactus *Lophophora williamsii* of central America, is chemically trimethoxyphenethylamine, again not in itself a lethal substance.

Cannabis

Cannabis, with all its various names in different parts of the world, has at least six active chemical constitutents, the most important of which is one of the tetrahydrocannabinols. Though its effects are a matter of controversy, there seems to be general agreement that used alone, it cannot be blamed for a single death. Proof of the intake of cannabis can be obtained from analysis of urine, blood, and swabs from lips and fingers.

The amphetamines

Now rarely used in reputable medical practice because of the undesirable side-effects, the amphetamine group of drugs was formerly employed for the abolition of fatigue and for the suppression of appetite. Methylamphetamine sulphate and dexamphetamine were the commonest analogues of amphetamine itself and are still widely available on the illicit market. Death is uncommon from overuse of the amphetamines alone. At autopsy there are no specific findings, apart from the rare possibility of a cerebral or subarachnoid haemorrhage from the induced hypertension.

Toxicology data suggests that after a therapeutic dose of 10 mg, the blood concentration at 2 hours is about 0.035 mg/l. After 30 mg, a peak plasma level of about 0.11 mg/l was observed at 2–5 hours, declining to 0.084 mg/l at 4.5 hours. Chronic abusers consuming large amounts may have blood levels of up to 2–3 mg/l. In the rare fatalities, there is a wider range of blood levels at autopsy, from 0.5 to 41 mg/l (average 8.6), depending on the size of the overdose and the time until death. Liver levels of 474 mg/kg (average 30) and high urine excretion, ranging from 25 to 700 mg/l, with an average of 237 mg/l, are common.

Methylenedioxymethamphetamine or 'ecstasy'

In recent years, new derivatives of amphetamine have appeared in the drug abuser's pharmacopoeia, though the substances have been available for medical use for many years. The most commonly encountered is MDMA (3,4-methylenedioxymethamphetamine), known as 'ecstasy', 'XTC' or 'ADAM'. Others of the groups are MDA (methyl 3,4-methylenedioxyamphetamine) and MDM (*n*-methyl-MDA). MDMA or 'ecstasy' was developed as long ago as 1914 and for some time had a role in psychotherapy as a consciousness-altering agent. It is now widely used as an illegal hallucinogenic drug, and though deaths have been few, they are now being reported from both the USA and Britain. The author (BK) conducted an autopsy on the first fatality in the British Isles, in a male who swallowed a considerable supply on being challenged by the police. There were no autopsy signs apart from a marked generalized cyanotic congestive state and the diagnosis was made purely on toxicological evidence.

Since the first edition of this book, MDMA deaths have increased markedly due to its ubiquitous availability to young people, especially at 'rave' parties: hyperthermia, dehydration and myocytolysis are some of the potentially fatal consequences.[54–67]

Cocaine

Along with heroin, cocaine and its associated drugs like 'crack' form the core of the hard-drug problem, from which fatalities are likely to arise. As cocaine is rapidly destroyed when given orally, it is usually taken by injection or sniffed. A fatality has been reported from absorption from administration via the rectum.[68] This is in addition to some deaths in which cocaine smugglers have died after packets of the drug hidden in their alimentary tract have broken, causing a massive overdose.[69–73] In India, cocaine has been used by means of urethral instillation and may also be used in the vagina by prostitutes.

In areas where cocaine usage is common, a significant proportion of fetal deaths are associated with the narcotic. In a series reported in New York by Morild and Stajic in 1990, of 103 fetal deaths, toxicology revealed cocaine in 64.[74] The study suggested that fetal death, abruptio placentae and abortion were caused by maternal use of the drug.

Death has been recorded by as little as 20–30 mg being applied to the nasal mucosa, but 1 g taken by mouth may not be lethal. As with other narcotics, marked habituation and tolerance occurs in chronic users, making estimates of dangerous dose levels difficult to forecast. Intravenous doses are of the order of 100 mg, a common lethal dose being 10 times greater, though far larger amounts can be tolerated by habitual users. Absorption via the nasal mucosa is less effective and larger doses are needed for the same effect than when used parenterally. Though ulceration and even perforation, of the nasal septum in chronic users is mentioned in most standard texts, they are extremely rare lesions.

Death may occur with considerable rapidity in cocaine overdose or hypersensitivity. It may be quite sudden, from cardiac arrest, in first-time users.[75–77]

At autopsy, there are no specific features. The pulmonary oedema often seen in heroin deaths is not present with cocaine, though the mode of death is also a dysrhythmia. The diluent used in ‘cutting’ the drug for street sale may be found in the injection sites, the regional lymph nodes, in the lungs and in other organs.[17] Adulterants may be similar to those used with heroin and include talc, starch, quinine, lactose and dextrose. Particles of cocaine itself may also be found as microemboli. Strychnine has been used because of its bitter taste, like quinine. Deliberate poisoning by a supplier has been known by either increasing the strychnine content or by supplying pure cocaine or heroin, leading to a massive overdose.

Cocaine is an excitant and stimulator of the autonomic nervous system. Sudden dramatic rises in blood pressure can occur, sometimes to over 300 mmHg and cerebral haemorrhage is a possible complication of this acute hypertension.[78,79]

As with the opioids, autopsy may reveal complications of the septic methods used for injection, apart from the already stated risks of virus infection, such as hepatitis and HIV. In former years, in New York and California, transmission of malaria was a well-known problem amongst those who shared syringes and needles – indeed, one suggestion for the use of quinine as a diluent, was as a treatment for the *Plasmodium*.

Pyogenic infections are most common, with phlebitis and distant embolic abscesses occurring. The injection sites may ulcerate, there can be regional lymphadenitis, but more serious sequelae that may be fatal include endocarditis. This can affect any heart valve, including those on the right side, which are not usually affected in post-rheumatic endocarditis. Many organisms are involved, mainly haemolytic and non-haemolytic streptococci, *Streptococcus faecalis*, *Staphylococcus aureus* and *Pseudomonas aeruginosa* andsome fungi. Post-mortem blood cultures frequently show such a mixed flora from contamination that isolation of the true causative organism may be difficult, but a heavy predominant growth may be significant.The advice of a microbiologist should be enlisted in assessing the relevance of a positive blood culture.

Any drug used intravenously, if it has particulate matter admixed, such as starch or talc, may cause foreign-body granulomata in the lungs, when the undissolved components are filtered out in the pulmonary capillary bed. Such granulomata are characteristic of intravenous drug abusers – when viewed under a polarizing microscope, refractile elements may be easily visualized.

As cocaine is so commonly used by sniffing, swabs should always be taken from each nostril using a plain cotton-wool swab. An unused swab should be sent to the laboratory as a control. The full range of blood, urine, stomach contents, liver and vitreous samples should routinely be taken at autopsy. Blood levels in fatal cases vary widely, but typical ranges extend from 1 to 21 mg/l, with a mean of 5.3 mg/l.[80,81]

The presence of cocaine and its metabolites in forensic samples need not always be attributed to abuse because as an effective local anaesthetic and vasoconstrictor it is used clinically in ear,nose and throat and eye surgery.[82]

Designer drugs

The term ‘designer drug’ is used for psychoactive compounds, i.e. stimulants, hallucinogens, and empathogens, which have been synthesized in the purpose to circumvent legislative control and intended for recreational use.[32] Substances such as MDMA, ‘ecstasy’ and MDA were among the first such drugs. According to Iversen *et al.* now more than 200 novel psychoactive drugs have been reported in Europe, with 73 added in 2012 and additional compounds encountered every week in 2013.[83] New classes of illicit drugs that have appeared on the market include 2,5-dimethoxy amphetamines, 2,5-phenylamines, b-keto amphetamines (cathinones), phencyclidines, piperazines, pyrrolidinophenones, fentanyls, piperidines, and tryptamine derivatives.[42–44,46,49,67,83–108] Also various synthetic cannabinoids mixed with herbal substances have increased dramatically in the illicit drug market. Due to the illicit nature of the manufacture usually very little is known about these substances when they enter the market posing therefore a serious health risk to consumers and presenting a continuous challenge to forensic toxicologists and the judiciary.

References

1 Reitox National Focal Point. *2012 National report: United Kingdom (2011 data) TO THE EMCDDA*. Davies C, *et al*. (eds). 2012, p. 258.

2 Skopp G, Potsch L, Moeller MR. On cosmetically treated hair – aspects and pitfalls of interpretation. *Forensic Sci Int* 1997; 84(1–3):43–52.

3 Kintz P. Value of hair analysis in postmortem toxicology. *Forensic Sci Int* 2004;142(2–3):127–34.

4 Krainer L, Wishnick SD, Berman E. Parenteral talcum granulomatosis – a complication of narcotic addiction. *Lab Invest* 1962;11(8):671–4.

5 Wendt VE, *et al*. Angiothrombotic pulmonary hypertension in addicts. 'Blue velvet' addiction. *JAMA* 1964;188:755–7.

6 Butz WC. Pulmonary arteriole foreign body granulomata associated with angiomatoids resulting from the intravenous injection of oral medications, e. g. propoxyphene hydrochloride (Darvon). *J Forensic Sci* 1969;14(3):317–26.

7 Siegel H. Human pulmonary pathology associated with narcotic and other addictive drugs. *Hum Pathol* 1972;3(1):55–66.

8 Kalant H, Kalant OJ. Death in amphetamine users: causes and rates. *Can Med Assoc J* 1975;112(3):299–304.

9 Robertson CH, Jr, Reynolds RC, Wilson JE, 3rd. Pulmonary hypertension and foreign body granulomas in intravenous drug abusers. Documentation by cardiac catheterization and lung biopsy. *Am J Med* 1976;61(5):657–64.

10 Davis LL. Pulmonary 'mainline' granulomatosis: talcosis secondary to intravenous heroin abuse with characteristic x-ray findings of asbestosis. *J Natl Med Assoc* 1983;75(12):1225–8.

11 Kringsholm B, Christoffersen P. Lung and heart pathology in fatal drug addiction. A consecutive autopsy study. *Forensic Sci Int* 1987;34(1–2):39–51.

12 Passarino G, *et al*. Histopathological findings in 851 autopsies of drug addicts, with toxicologic and virologic correlations. *Am J Forensic Med Pathol* 2005;26(2):106–16.

13 Dettmeyer RB, *et al*. Widespread pulmonary granulomatosis following long time intravenous drug abuse – a case report. *Forensic Sci Int* 2010;197(1–3):e27–30.

14 Bainborough AR, Jericho KW. Cor pulmonale secondary to talc granulomata in the lungs of a drug addict. *Can Med Assoc J* 1970;103(12):1297–8.

15 Hopkins GB, Taylor DG. Pulmonary talc granulomatosis. A complication of drug abuse. *Am Rev Respir Dis* 1970; 101(1):101–4.

16 Hollinger MA. Pulmonary toxicity of inhaled and intravenous talc. *Toxicol Lett* 1990;52(2):121–7; discussion 117–9.

17 Oubeid M, *et al*. Pulmonary talc granulomatosis in a cocaine sniffer. *Chest* 1990;98(1):237–9.

18 Johnson DC, Petru A, Azimi PH. Foreign body pulmonary granulomas in an abuser of nasally inhaled drugs. *Pediatrics* 1991; 88(1):159–61.

19 Lockemann U, Pueschel K. Siderophages in the lung of drug addicts. *Forensic Sci Int* 1993;59(2):169–75.

20 Graham CA, McNaughton GW, Crawford R. 'Popping': a cause of soft tissue sepsis in chronic drug abusers. *Eur J Emerg Med* 1999;6(3):259–61.

21 Milroy CM, Parai JL. The histopathology of drugs of abuse. *Histopathology* 2011;59(4):579–93.

22 Iyer S, Subramanian P, Pabari A. A devastating complication of 'skin popping'. *Surgeon* 2011;9(5):295–7.

23 Borokhov A, Bastiaans R, Lerner V. Tattoo designs among drug abusers. *Isr J Psychiatry Relat Sci* 2006;43(1):28–33.

24 Polson CJ, Green MA, Lee M. *Clinical Toxicology*, 3rd edn. London: Pitman Medical, 1983.

25 Burton JL. Health and safety at necropsy. *J Clin Pathol* 2003; 56(4):254–60.

26 Osselton MD. Drugs of abuse; postmortem blood. In: Siegel JA (ed). *Encyclopedia of Forensic Sciences*. Oxford: Elsevier, 2000, pp. 646–50.

27 Kalasinsky KS, *et al*. Blood, brain, and hair GHB concentrations following fatal ingestion. *J Forensic Sci* 2001;46(3):728–30.

28 Engelhart DA, Jenkins AJ. Detection of cocaine analytes and opiates in nails from postmortem cases. *J Anal Toxicol* 2002; 26(7):489–92.

29 Gaulier JM, *et al*. Analytical aspects of volatile substance abuse (VSA). *J Forensic Sci* 2003;48(4):880–2.

30 Drummer OH. Postmortem toxicology of drugs of abuse. *Forensic Sci Int* 2004;142(2–3):101–13.

31 Drummer OH. Recent trends in narcotic deaths. *Ther Drug Monit* 2005;27(6):738–40.

32 Fu S, Stojanovska N. Designer drugs. In: Siegel JA, Saukko PJ (eds). *Encyclopedia of Forensic Sciences*. Waltham: Academic Press, 2013, pp. 36–44.

33 Seymour A, Black M, Oliver JS. Drug related deaths in the Strathclyde region of Scotland, 1995–1998. *Forensic Sci Int* 2001;122(1):52–9.

34 Drummer OH, *et al*. Methadone toxicity causing death in ten subjects starting on a methadone maintenance program. *Am J Forensic Med Pathol* 1992;13(4):346–50.

35 Caplehorn JR, Drummer OH. Methadone dose and post-mortem blood concentration. *Drug Alcohol Rev* 2002;21(4):329–33.

36 Caplehorn JR, Drummer OH. Fatal methadone toxicity: signs and circumstances, and the role of benzodiazepines. *Aust N Z J Public Health* 2002;26(4):358–62; discussion 362–3.

37 Manning T, *et al*. Evaluation of the Abuscreen for methadone. *J Forensic Sci* 1976;21(1):112–20.

38 Milroy CM, Forrest AR. Methadone deaths: a toxicological analysis. *J Clin Pathol* 2000;53(4):277–81.

39 Burns RS, *et al*. Phencyclidine – states of acute intoxication and fatalities. *West J Med* 1975;123(5):345–9.

40 Noguchi TT, Nakamura GR. Phencyclidine-related deaths in Los Angeles County, 1976. *J Forensic Sci* 1978;23(3):503–7.

41 Corales RL, Maull KI, Becker DP. Phencyclidine abuse mimicking head injury. *JAMA* 1980;243(22):2323–4.

42 Graeven DB, Sharp JG, Glatt S. Acute effects of phencyclidine (PCP) on chronic and recreational users. *Am J Drug Alcohol Abuse* 1981;8(1):39–50.

43 Brunet BL, *et al*. Toxicity of phencyclidine and ethanol in combination. *Alcohol Drug Res* 1985;6(5):341–9.

44 Poklis A, *et al*. Phencyclidine and violent deaths in St. Louis, Missouri: a survey of medical examiners' cases from 1977 through 1986. *Am J Drug Alcohol Abuse* 1990;**16**(3–4):265–74.

45 Casari C, Andrews AR. Application of solvent microextraction to the analysis of amphetamines and phencyclidine in urine. *Forensic Sci Int* 2001;120(3):165–71.

46 Mozayani A, *et al*. A multiple drug fatality involving MK-801 (dizocilpine), a mimic of phencyclidine. *Forensic Sci Int* 2003; 133(1–2):113–7.

47 Pestaner JP, Southall PE. Sudden death during arrest and phencyclidine intoxication. *Am J Forensic Med Pathol* 2003; 24(2):119–22.

48 Cox D, *et al.* Distribution of phencyclidine into vitreous humor. *J Anal Toxicol* 2007;31(8):537–9.

49 deRoux SJ, Sgarlato A, Marker E. Phencyclidine: a 5-year retrospective review from the New York City Medical Examiner's Office. *J Forensic Sci* 2011;56(3):656–9.

50 Lee RE. A technique for the rapid isolation and identification of psilocin from psilocin/psilocybin-containing mushrooms. *J Forensic Sci* 1985;30(3):931–41.

51 Keller T, *et al.* Analysis of psilocybin and psilocin in Psilocybe subcubensis Guzman by ion mobility spectrometry and gas chromatography-mass spectrometry. *Forensic Sci Int* 1999; 99(2):93–105.

52 Kamata T, *et al.* Liquid chromatography-mass spectrometric and liquid chromatography-tandem mass spectrometric determination of hallucinogenic indoles psilocin and psilocybin in 'magic mushroom' samples. *J Forensic Sci* 2005;50(2):336–40.

53 Anastos N, *et al.* The determination of psilocin and psilocybin in hallucinogenic mushrooms by HPLC utilizing a dual reagent acidic potassium permanganate and tris(2,2'-bipyridyl) ruthenium(II) chemiluminescence detection system. *J Forensic Sci* 2006;51(1):45–51.

54 Fineschi V, Masti A. Fatal poisoning by MDMA (ecstasy) and MDEA: a case report. *Int J Legal Med* 1996;108(5):272–5.

55 Rutty GN, Milroy CM. The pathology of the ring-substituted amphetamine analogue 3,4-methylenedioxymethylamphetamine (MDMA, 'Ecstasy'). *J Pathol* 1997;181(3):255–6.

56 Fineschi V, *et al.* Adam (MDMA) and Eve (MDEA) misuse: an immunohistochemical study on three fatal cases. *Forensic Sci Int* 1999;104(1):65–74.

57 Gill JR, *et al.* Ecstasy (MDMA) deaths in New York City: a case series and review of the literature. *J Forensic Sci* 2002;47(1):121–6.

58 De Letter EA, *et al.* Immunohistochemical demonstration of the amphetamine derivatives 3,4-methylenedioxymethamphetamine (MDMA) and 3,4-methylenedioxyamphetamine (MDA) in human post-mortem brain tissues and the pituitary gland. *Int J Legal Med* 2003;117(1):2–9.

59 Lua AC, *et al.* Profiles of urine samples from participants at rave party in Taiwan: prevalence of ketamine and MDMA abuse. *Forensic Sci Int* 2003;136(1–3):47–51.

60 De Letter EA, *et al.* Interpretation of a 3,4-methylenedioxymethamphetamine (MDMA) blood level: discussion by means of a distribution study in two fatalities. *Forensic Sci Int* 2004;141(2–3):85–90.

61 Kalasinsky KS, Hugel J, Kish SJ. Use of MDA (the 'love drug') and methamphetamine in Toronto by unsuspecting users of ecstasy (MDMA). *J Forensic Sci* 2004;49(5):1106–12.

62 Concheiro M, *et al.* Determination of MDMA, MDA, MDEA and MBDB in oral fluid using high performance liquid chromatography with native fluorescence detection. *Forensic Sci Int* 2005;150(2–3):221–6.

63 Han E, *et al.* The prevalence of MDMA/MDA in both hair and urine in drug users. *Forensic Sci Int* 2005;152(1):73–7.

64 De Letter EA, *et al.* Postmortem distribution of 3,4-methylenedioxy-N,N-dimethyl-amphetamine (MDDM or MDDA) in a fatal MDMA overdose. *Int J Legal Med* 2007; 121(4):303–7.

65 Pilgrim JL, Gerostamoulos D, Drummer OH. Deaths involving MDMA and the concomitant use of pharmaceutical drugs. *J Anal Toxicol* 2011;35(4):219–26.

66 Russell MJ, Bogun B. New 'party pill' components in New Zealand: the synthesis and analysis of some beta-ketone analogues of 3,4-methylenedioxymethamphetamine (MDMA) including betak-DMBDB (beta-ketone-N,N-dimethyl-1-(1,3-benzodioxol-5-yl)-2-butanamine). *Forensic Sci Int* 2011; 210(1–3):174–81.

67 Chen C, *et al.* Increases in use of novel synthetic stimulant are not directly linked to decreased use of 3,4-methylenedioxy-N-methylamphetamine (MDMA). *Forensic Sci Int* 2013; 231(1–3):278–83.

68 Doss PL, Gowitt GT. Investigation of a death caused by rectal insertion of cocaine. *Am J Forensic Med Pathol* 1988;9(4):336–8.

69 Gherardi R, *et al.* A cocaine body packer with normal abdominal plain radiograms. Value of drug detection in urine and contrast study of the bowel. *Am J Forensic Med Pathol* 1990;11(2):154–7.

70 Rouse DA, Fysh R. Body packing presenting as sudden collapse. *Med Sci Law* 1992;32(3):270–1.

71 Stichenwirth M, *et al.* Suicide of a body packer. *Forensic Sci Int* 2000;108(1):61–6.

72 Koehler SA, *et al.* The risk of body packing: a case of a fatal cocaine overdose. *Forensic Sci Int* 2005;151(1):81–4.

73 Bruck S, *et al.* [Atypical 'body packing syndrome' – a case report]. *Arch Kriminol* 2006;218(1–2):35–43.

74 Morild I, Stajic M. Cocaine and fetal death. *Forensic Sci Int* 1990;47(2):181–9.

75 Tardiff K, *et al.* Analysis of cocaine-positive fatalities. *J Forensic Sci* 1989;34(1):53–63.

76 Karch SB. Introduction to the forensic pathology of cocaine. *Am J Forensic Med Pathol* 1991;12(2):126–31.

77 Rump AF, Theisohn M, Klaus W. The pathophysiology of cocaine cardiotoxicity. *Forensic Sci Int* 1995;71(2):103–15.

78 Mittleman RE, Wetli CV. Cocaine and sudden 'natural' death. *J Forensic Sci* 1987;32(1):11–19.

79 Davis GG, Swalwell CI. The incidence of acute cocaine or methamphetamine intoxication in deaths due to ruptured cerebral (berry) aneurysms. *J Forensic Sci* 1996;41(4):626–8.

80 Baselt RC. *Disposition of Toxic Drugs and Chemicals in Man*, 8th edn. Baselt RC (ed). Foster City: Biomedical Publications, 2008, xviii.

81 Pilgrim JL, Woodford N, Drummer OH. Cocaine in sudden and unexpected death: a review of 49 post-mortem cases. *Forensic Sci Int* 2013;227(1–3):52–9.

82 Bailey KM, *et al.* Cocaine detection in postmortem samples following therapeutic administration. *J Anal Toxicol* 2009; 33(8):550–2.

83 Iversen L, White M, Treble R. Designer psychostimulants: pharmacology and differences. *Neuropharmacology* 2014;87:59–65.

84 Balikova M. Nonfatal and fatal DOB (2,5-dimethoxy-4-bromoamphetamine) overdose. *Forensic Sci Int* 2005; 153(1):85–91.

85 da Costa JL, *et al.* Chemical identification of 2,5-dimethoxy-4-bromoamphetamine (DOB). *Forensic Sci Int* 2007;173(2–3):130–6.

86 Jankovics P, *et al.* Detection and identification of the new potential synthetic cannabinoids 1-pentyl-3-(2-iodobenzoyl) indole and 1-pentyl-3-(1-adamantoyl)indole in seized bulk powders in Hungary. *Forensic Sci Int* 2012;214(1–3):27–32.

87 Andreasen MF, *et al.* A fatal poisoning involving Bromo-Dragonfly. *Forensic Sci Int* 2009;183(1–3):91–6.

88 Cottencin O, Rolland B, Karila L. New designer drugs (synthetic cannabinoids and synthetic cathinones): review of literature. *Curr Pharm Des* 2014;20(25):4106–11.

89 Kesha K, *et al.* Methylenedioxypyrovalerone ("bath salts"), related death: case report and review of the literature. *J Forensic Sci* 2013;58(6):1654–9.

90 Zawilska JB, Wojcieszak J. Designer cathinones – an emerging class of novel recreational drugs. *Forensic Sci Int* 2013; 231(1–3):42–53.

91 Gregg RA, Rawls SM. Behavioral pharmacology of designer cathinones: a review of the preclinical literature. *Life Sci* 2014; 97(1):27–30.

92 Hull MJ, *et al*. Postmortem urine immunoassay showing false-positive phencyclidine reactivity in a case of fatal tramadol overdose. *Am J Forensic Med Pathol* 2006;27(4):359–62.

93 de Boer D, *et al*. Piperazine-like compounds: a new group of designer drugs-of-abuse on the European market. *Forensic Sci Int* 2001;121(1–2):47–56.

94 Antia U, *et al*. Pharmacokinetics of 'party pill' drug N-benzylpiperazine (BZP) in healthy human participants. *Forensic Sci Int* 2009;186(1–3):63–7.

95 Westphal F, *et al*. Structure elucidation of a new designer benzylpiperazine: 4-bromo-2,5-dimethoxybenzylpiperazine. *Forensic Sci Int* 2009;187(1–3):87–96.

96 Abdel-Hay KM, *et al*. Differentiation of methylenedioxybenzylpiperazines (MDBP) by GC-IRD and GC-MS. *Forensic Sci Int* 2010;195(1–3):78–85.

97 Abdel-Hay KM, *et al*. Differentiation of methylenedioxybenzylpiperazines (MDBPs) and methoxymethylbenzylpiperazines (MMBPs) By GC-IRD and GC-MS. *Forensic Sci Int* 2011;210(1–3):122–8.

98 Abdel-Hay KM, DeRuiter J, Randall Clark C. GC-MS and GC-IRD studies on the six ring regioisomeric dimethoxybenzoylpiperazines (DMBzPs). *Forensic Sci Int* 2013; 231(1–3):54–60.

99 Sauer C, *et al.* Acute poisoning involving the pyrrolidinophenone-type designer drug 4'-methyl-alpha-pyrrolidinohexanophenone (MPHP). *Forensic Sci Int* 2011;208(1–3):e20–5.

100 Westphal F, *et al*. Spectroscopic characterization of 3,4-methylenedioxypyrrolidinobutyrophenone: a new designer drug with alpha-pyrrolidinophenone structure. *Forensic Sci Int* 2011;209(1–3):126–32.

101 Ojanpera I, *et al*. Blood levels of 3-methylfentanyl in 3 fatal poisoning cases. Am J Forensic Med Pathol 2006;27(4):328–31.

102 Coopman V, *et al.* LC-MS/MS analysis of fentanyl and norfentanyl in a fatality due to application of multiple Durogesic transdermal therapeutic systems. *Forensic Sci Int* 2007;169(2–3):223–7.

103 Thompson JG, *et al*. Fentanyl concentrations in 23 postmortem cases from the hennepin county medical examiner's office. *J Forensic Sci* 2007;52(4):978–81.

104 Ojanpera I, *et al*. An epidemic of fatal 3-methylfentanyl poisoning in Estonia. *Int J Legal Med* 2008;122(5):395–400.

105 Lafreniere NM, Watterson JH. Detection of acute fentanyl exposure in fresh and decomposed skeletal tissues. *Forensic Sci Int* 2009;185(1–3):100–6.

106 Lafreniere NM, Watterson JH. Detection of acute fentanyl exposure in fresh and decomposed skeletal tissues part II: the effect of dose-death interval. *Forensic Sci Int* 2010;194(1–3):60–6.

107 Palmer RB. Fentanyl in postmortem forensic toxicology. *Clin Toxicol (Phila)* 2010;48(8):771–84.

108 Sato S, *et al.* Studies on 1-(2-phenethyl)-4-(N-propionylanilino) piperidine (fentanyl) and related compounds VII. Quantification of alpha-methylfentanyl metabolites excreted in rat urine. *Forensic Sci Int* 2010;195(1–3):68–72.

This page intentionally left blank

CHAPTER 33

Corrosive and Metallic Poisoning

- Introduction
- Cyanide
- Corrosive acids, alkalis and phenols
- Oxalic acid and oxalate salts
- Ethylene glycol poisoning
- Metallic poisons
- References

Introduction

Toxicology is a vast subject, most of it concerned with the nature, occurrence, symptomatology, biochemistry, mode of action and treatment of a wide range of poisonous substances. Many forensic medicine textbooks, especially those from Asia, devote a major part of their text to all these aspects of hundreds of toxic substances, many of which are seldom – if ever – encountered by a pathologist in most parts of the world. As the autopsy appearances of most poisons are non-specific, it seems fruitless to offer a repetitive catalogue, and therefore the descriptions selected here refer to some of those that either have specific features or are encountered more often. This chapter describes the autopsy appearances in a range of poisons that can broadly be classed as 'corrosive', even if this is not necessarily their main lethal mode of action. In addition, several toxic heavy metals will be discussed, again from the point of view of autopsy findings and relevant toxicological laboratory findings.

Cyanide

Cyanide is a relatively common poison, both in suicide, accident and, occasionally, homicide.[1–8] It forms part of lethal toxicity of many fires in buildings, where smoke inhalation kills the majority of victims, rather than burns (Chapter 11). Although the autopsy diagnosis of acute cyanide poisoning is rarely in doubt, toxicological analysis may be difficult to interpret because of both the destruction and production of cyanide in the dead body and even in stored blood samples awaiting analysis. Acute cyanide poisoning is most often self-administered (70 per cent in one series), in which case usually the sodium or potassium salt is swallowed. It may be accidental or industrial, in which case either salts may be involved, or it may be the free gas liberated from some commercial process. Seeds of fruits, such as apricots, peaches and plums contain toxic cyanogenic glycosides, such as amygdalin. Severe poisonings have been reported after the ingestion of apricot seeds (*Prunus armeniaca*). Almonds, particularly the bitter almond variety (*P. amygdalus amara*) produces fruit with seeds containing high amounts of amygdalin. Hydrolysis of amygdalin in the digestive tract can release hydrocyanic acid and lead to cyanide poisoning.[9–12]

Homicidal poisoning is rare, except for the mass homicides, such as the Jonestown cult ('People's Temple') massacre in Guyana, or the use of cyanide as a weapon of war and in the Holocaust (Zyklon B) as well as against civilians in the Middle East.[13–18] It has also been used for judicial execution in the gas chamber (1924–1999) in parts of the USA.

Cyanide acts only as free hydrogen cyanide and therefore swallowed salts need to meet either water or gastric acid before liberating hydrocyanic acid, a process that takes only a few seconds. The fatal dose of cyanide is small, of the order of 150–300 mg, which allowed it to be used as hidden suicide pills by prominent Nazis at the end of the Second World War. Recovery has been recorded from far greater doses of potassium cyanide.[19] Much depends on the purity of cyanides, as they tend to decompose in storage and old samples may contain only half the weight as active cyanide.

Autopsy findings in cyanide poisoning

Cyanide acts by linking with the ferric iron atom of cytochrome oxidase, preventing the uptake of oxygen for cellular respiration. Cyanide cannot combine directly with haemoglobin, but can do so through the intermediary compound methaemoglobin. Cyanides are moderately corrosive through their alkaline nature, causing local tissue damage that is unrelated to their more general toxicity via enzyme inhibition.

Externally there can be wide variations in the appearance. Traditionally, the hypostasis is said to be brick-red, due to excess oxyhaemoglobin (because the tissues are prevented from using oxygen) and to the presence of cyanmethaemoglobin. Many descriptions refer to a dark pink or even bright red skin, especially in the dependent areas, which can be confused with carboxyhaemoglobin. The few cases seen by the authors have shown a marked dark cyanotic hypostasis, perhaps caused by lack of oxygenation of the red cells by paralysis of the respiratory muscles. There may be no other external signs apart from the colour of the skin and possibly black vomit around the lips.

There may be a bitter almond-like smell of cyanide about the body, though it is well known that many persons cannot detect this, the ability being a sex-linked genetic trait. This may be of importance to pathologists and mortuary staff, as corpses dead of cyanide poisoning can present a health hazard.[20–22] A former colleague of the author (BK) became ill and was temporarily disabled shortly after conducting an autopsy on a suicide who had swallowed a massive amount of potassium cyanide. Presumably he had inhaled hydrogen cyanide from the stomach contents when examining the viscera.

Internally the tissues may also be bright pink caused by the oxyhaemoglobin that cannot be utilized by the tissues – which is probably more common than the presence of cyanmethaemoglobin. The stomach lining may be badly damaged and can present a blackened, eroded surface, by altered blood staining the stripped mucosa (Fig. 33.1). This is mainly because of the strongly alkaline nature of the hydrolysed sodium or potassium salts of cyanide; hydrogen cyanide itself causes no such damage. In less severe cases, the stomach lining will be streaked with dark red striae, where the rugae have been eroded while leaving the intervening folds relatively unharmed. The stomach may contain frank or altered blood from the erosions and haemorrhages in the walls. If the cyanide was in dilute solution, there may be little damage to the stomach, apart from pinkness of the mucosa and perhaps some petechial haemorrhages. There may also be undissolved white crystals or powder, with the bitter almond-like smell of cyanide mentioned above.

As death is usually rapid, little of the contents will have passed into the intestine. The oesophagus may be damaged, especially the mucosa of the lower third, though some of this may be a post-mortem change from regurgitation of the stomach contents through the relaxed cardiac sphincter after death. The other organs show no specific changes and the diagnosis is made by history, smell and the reddish colour of the internal tissues, and often skin.



Figure 33.1 Haemorrhagic gastric mucosa in cyanide poisoning.

Toxicological analysis

The usual blood, stomach contents, urine and any vomit should be submitted to the laboratory, taking particular care that the samples present no hazard to those packing, transporting or unpacking them. The laboratory should be warned in advance that a possible cyanide case is coming their way. When in doubt as to the appropriate collection and preservation of samples one should seek advice from the laboratory where the toxicological analysis is going to take place.

It is important to get the samples to the laboratory as soon as possible (in terms of days) to avoid the spurious formation of cyanide in stored blood samples.[23,24]

When Ballantyne experimented adding cyanide to human blood to produce concentrations in the range typical of those found in fatal acute cyanide poisoning, changes in concentrations were measured periodically over 3 months at different storage temperatures (c. 20°C, 4°C, and −20°C); he found that concentrations decreased at all temperatures during the first week. After this time fluctuations in concentrations varied with storage temperature. Changes were least marked at −20°C and maximum in specimens when stored at room temperature. In control samples of blood without added cyanide, *in vitro* production of cyanide occurred at −20°C. Based on these findings he suggested that blood with a low cyanide content should be stored at 4°C, but blood with a high cyanide content is best kept at −20°C to reduce transformation.[25]

McAllister *et al.* tested the effect of sodium fluoride to minimize the post-mortem instability of cyanide in blood samples by comparing both treated and control blood samples from 14 autopsied fire victims over a 25–30 day period. Cyanide concentrations in the treated and control samples were measured between 9 and 11 days post-treatment and between 25 and 30 days post-treatment. The samples treated with 2 per cent sodium fluoride showed a substantial reduction in blood cyanide variability over a 25–30 day period when compared to control samples, with concentrations very close to the starting concentrations, while untreated samples showed significant increases. Based on the findings of this study, they recommended that 2 per cent sodium fluoride be added to blood samples from fire victims to reduce potential instability due to bacteriological activity.[26]

The amount found on analysis naturally depends on the amount taken and the time between administration and death. Though the latter is usually measured in minutes, low dosage – or treatment – may allow survival for hours or even days.

Assuming that no spurious cyanide is formed, any significant amount found is evidence of cyanide ingestion, which in itself is abnormal and presumably confirmatory evidence of poisoning. However, Karhunen *et al.* have reported a case in which post-mortem burning of a homicide victim led to a blood cyanide level of 10 mg/l, presumably due to passive diffusion of cyanide through body cavities opened by the fire.[27]

Typical blood levels in one series of fatal cases following ingestion of the poison range from 1 to 53 mg/l, with an average of 12 mg/l. The spleen always has the highest tissue concentration, presumably because it contains so many red cells; in the same series, the spleen level was between 0.5 and 398 mg/l, with a mean of 44 mg/l.[28] In a recent series Rhee *et al.* reported 21 deaths due to cyanide intoxication by oral ingestion. The concentration ranges (mean ± SD) of cyanide in heart blood, peripheral blood and gastric contents were 0.1–248.6 mg/l (38.1 ± 56.6 mg/l), 0.3–212.4 mg/l (17.1 ± 45.1 mg/l) and 2.0–6398.0 mg/kg (859.0 ± 1486.2 mg/kg), respectively. The ranges of the heart/peripheral blood concentration ratio and gastric contents/peripheral blood concentration ratio were 0.3–10.6 (mean 3.4) and 3.4–402.4 (mean 86.0), respectively. From the difference of cyanide concentration and the concentration ratio of cyanide in different types of post-mortem specimens, the possibility of the post-mortem redistribution of cyanide and death by oral ingestion of cyanide could be confirmed.[29]

Corrosive acids, alkalis and phenols

Corrosive poisons were formerly common suicidal agents, though they are now relatively rare in Western countries, probably because of the ease of obtaining less painful substances. In some parts of the world, mineral acids are still often used for homicide, assault ('vitriol-throwing') and suicide. In Malaya (Malaysia), reagents used in rubber production, such as formic and acetic acids, were often taken as a means of self-destruction by young females, especially Tamil rubber workers.

In Britain, acids and alkalis are now almost unknown as agents of death. Even the occasional use of sulphuric 'battery acid' as a weapon of assault rarely causes death. The phenolic corrosives, however, such as carbolic acid and lysol, are occasionally encountered as suicidal agents. Toxicologically, none of these presents much problem, as the damage is often structural rather than poisonous, unless the victim survives long enough to have complications such as renal failure or chest infections. All the corrosive substances have the following features in common:

- There may be spillage of the fluid on the exterior of the body, corroding the skin in a pattern which may be helpful in reconstructing the posture of the victim at the time of drinking the substance. The lips may be burnt, and trickle and splash marks may run from the mouth down the chin, neck and chest. The pattern of burns at the mouth may sometimes indicate the shape of the container from which the poison was drunk, as the wide brim of a cup may mark the cheeks, while a bottleneck may sit more cleanly in the mouth. If the person was standing or sitting, then these runnels of fluid may pass down the chin onto chest and abdomen. If lying, then they may run across the face and cheeks and pass to the back of the neck. Further spillage may come from the nostrils due to spluttering and gagging. The hands may also be affected if the hands are instinctively brought up to the face.
- The interior of the mouth may be eroded, and the tongue swollen or shrivelled, according to the nature of the corrosive agent. The pharynx, larynx

and oesophagus are all eroded, and if survival lasts more than a few minutes the glottis area may become oedematous. Spillage into the larynx and air passages may allow the respiratory mucosa to be damaged, and aspiration of liquid or vapour into the lungs can cause rapid pulmonary oedema and haemorrhages.

- The lower oesophagus and stomach rapidly become damaged, with discolouration, desquamation and sometimes perforation. Attempts at passing a stomach tube may themselves penetrate the softened wall of the oesophagus or stomach. If survival lasts long enough, some corrosive may pass through to damage the small intestine, but this is rare because of the time factor and spasm of the pylorus.
- All may cause death by pulmonary oedema from spillage into the lungs; if survival lasts a day or more, then a fulminating bronchopneumonia may be the terminal event.

The different corrosive agents have different actions on soft tissues, which can sometimes be differentiated by appearance and smell, though the mineral acids are not all that different (Fig. 33.2). The phenolic compounds can usually be detected by smell alone. Strong acids act by dehydrating the tissues, coagulating the proteins and converting haemoglobin to haematin.

Sulphuric acid, in concentrated form, is extremely corrosive and produces great heat in contact with water or tissues. The tissues are grey to black, rather dry and dehydrated. They may actually be charred into a blackened crust by the generated heat. The gastric lining may be grey, dark brown or black, or mixtures of all colours, depending upon the amount of altered blood in each part. Perforation may occur.

The oesophagus and stomach may be grey and swollen, depending on the amount of acid and the amount of food already in the stomach. The tongue may be grey or black and distorted.

Nitric acid is similar, but has a brownish-yellow cast to its mucosal damage. There may be yellow or brown sharp-edged patterns on the skin burns of the face, with the usual trickle marks coming down from the corners of the mouth. Yellow fumes may arise from the stomach contents if a considerable quantity is present. The internal appearances are of yellowish-brown sloughing, though perforation seems less common than with sulphuric acid.

Hydrochloric acid has similar effects, especially on mucous membranes, but is not so injurious to intact skin as sulphuric and nitric acids. The stomach may be converted into a slimy, softened mass and can perforate. The colour is greyish to black, depending on the amount of altered blood (Fig. 33.3).

Sodium hydroxide in concentrated form is also a corrosive, but soft, slippery slime is the characteristic appearance and feel to tissues damaged by caustic soda. The colour is dirty white to grey.

Phenol and lysol are also damaging and affect the tissues in much the same way as acids and alkalis. Carbolic acid (pure phenol) tends to stiffen the tissues and bleach them so that hard, cracked, whitish surfaces are seen on the face and skin. Internally, the same stiffness is noted in the oesophagus and stomach. Lysol is a soapy solution of phenol and cresols. It discolours the tissues a brownish purple, but is otherwise similar to phenol in its action (Fig. 33.4).



Figure 33.2 Occupational accident where a glass container with 100 litres of chlorosulphuric acid was broken and poured down onto one of the workers causing extensive burns of the face and chest.



Figure 33.3 Corrosion of larynx, oesophagus (a) and stomach (b) in suicidal ingestion of concentrated hydrochloride acid with alcohol.



Figure 33.4 Skin burns on a victim of lysol suicide. The trickle pattern makes it obvious that the victim was either standing or sitting erect when drinking the fluid.

Oxalic acid and oxalate salts

These are not so corrosive as the mineral acids, but are poisonous and often act quickly, death occurring within minutes or the hour, from shock or hypocalcaemia. The acid is locally corrosive, but also has a systemic effect that may well be fatal even if the local damage is non-lethal.

At autopsy, if an appreciable amount of either the white crystals or a strong solution has been swallowed, the local effect is a bleaching, the mucosa of mouth, pharynx and oesophagus being white, though local haemorrhage can streak this with red. The stomach contains altered blood from the damaged mucosa and is dark brown or black from acid haematin, the wall studded with acute erosions. Calcium oxalate crystals may be seen in the stomach contents or in scrapings from the mucosa.

In those who have survived the acute phase, death may be caused by abnormalities of the muscle function (including the myocardium) from the hypocalcaemia, caused by the precipitation of body calcium as insoluble calcium oxalate. More common is renal failure, death occurring 2–10 days later. The renal tubules suffer necrosis, primarily in the proximal convoluted tubules. This is not caused by the presence of calcium oxalate crystals, though these can be demonstrated histologically in the kidney.

Ethylene glycol poisoning

Though in no sense a corrosive poison, ethylene glycol has certain features in common with oxalate poisoning and is so common relative to death from mineral acids that it cannot be omitted. The glycols are used widely as antifreeze agents in motor engines and as solvents in industry, so they are easily available. Because of their chemical inclusion in the alcohol group, they are abused as a source of intoxication, as well as being accidental, suicidal and rarely homicidal agents.[30–32] The compounds involved are ethylene, diethylene, propylene and hexylene glycols. These do not have the same toxic effects (in fact, propylene glycol is virtually non-toxic), but ethylene glycol is the most commonly encountered. When drunk in excess of 100–200 ml, it is almost certain to be fatal unless specific treatment is given, such as dialysis and competition with alcohol.

The first effects resemble drunkenness, but this passes into coma and death often within the first day. The glycol is metabolized in the body, a small but significant amount (about 1 per cent) being converted to oxalic acid, via the process glycol–glyoxal–glycolic acid–formic acid–glyoxylic acid–oxalic acid.

At autopsy there is no local damage, but widespread precipitation of the sheaf-like doubly refractile crystals of calcium oxalate into the tissues can be rendered visible microscopically by the use of polarized light or by confocal laser scanning microscopy (Fig. 33.5).[33–36] For a long time it was a matter of controversy whether this crystal deposition is the cause or merely a side-effect of the lethal action of glycols. However, recent studies have shown that the accumulation of calcium oxalate monohydrate (COM) crystals in kidney tissue produces renal tubular necrosis that leads to kidney failure.[30,34,37]

There may be cerebral oedema and a chemical meningoencephalitis. In the kidney there is a tubular



Figure 33.5 Birefringent calcium oxalate crystals in kidney in ethylene glycol poisoning as seen in polarized light under a microscope.

necrosis similar to that in oxalate poisoning, and the crystals can be seen in the interstitial tissues and the tubules. Diffuse liver damage can also occur.

The primary hyperoxalurias (PH I, II and III), are a rare group of autosomal recessive disorders, which involve the overproduction of oxalate.[38–40] Pien *et al.* reported about a rare case of a patient who, because of recurrent episodes of nausea, vomiting and signs of dehydration, had been admitted to hospital and each time was found to have lactic acidosis. On the first admission, glycolic acid was detected in his blood and he was diagnosed as having ethylene glycol intoxication. Only at the third admission, 2 years later, when the possibility of an underlying metabolic disorder was considered, a deficiency of complex I in the mitochondrial oxidative phosphorylation was detected.[41] Quite the opposite was the outcome of the case reported by Woolf *et al.* where recurrent vomiting, lethargy, and metabolic acidosis in a previously healthy 6-month-old child led to extensive search for an inborn error of metabolism. Tests performed on blood and urine specimens collected while the child was not acutely ill yielded normal results. Only when tests were performed while the child was acutely ill, during the third hospitalization, led to the correct diagnosis of intentional ethylene glycol poisoning. Ethylene glycol was detected in two bottles of formula intended for consumption by the infant. There was not enough evidence to identify the perpetrator; however, the babysitter, whose work schedule paralleled the onset of illness was discharged.[42]

Laboratory analysis in ethylene glycol poisoning

The blood levels naturally depend on the time that has elapsed since ingestion. It is usually greater than 300 mg/l and the average is as high as 2400 mg/l in samples taken before the second day. The brain may contain from 300 to 4000 mg/kg and the urine from 600 to 10000 mg/l, with a mean of 5700 mg/l.[28]

Metallic poisons

There is a whole range of metallic poisons, most of them from the upper reaches of the Periodic Table, accounting for their usual description as ‘heavy metals’. The vast majority of toxic effects come from environmental and occupational poisoning, both chronic and acute. Acute poisoning by suicide, accident and homicide is becoming much less common, both because of the availability of other toxic agents, and because of greater awareness and controls on the environmental and industrial hazards of heavy metals. In former years, especially the nineteenth century, heavy-metal poisoning was common in homicide, but is now rarely seen in Western countries, mainly because they are now known to be easily detectable.

As the subject is dealt with in great detail by so many textbooks and monographs, only one such poison – arsenic – will be discussed, together with a mention of any significant differences with other metals.

Arsenic

A constituent of all animal tissue, arsenic is the twelfth most abundant element on earth. This emphasizes the need for strict controls when making analysis for arsenic in human fluids or tissues, as the excretion of a healthy person on a diet rich in fish (especially shellfish) can exceed that seen in chronic arsenical poisoning. Similarly, where an exhumation is performed after allegations of poisoning, full control samples of soil and grave water must be taken to ensure that arsenic found in the body could not have arisen from local contamination (Chapter 1).

Arsenic metal is not poisonous, only its compounds. These interfere with cellular respiration by combining with the sulphydryl groups of mitochondrial enzymes, especially pyruvate oxidase and certain phosphatases. Arsenic has a particular target in vascular endothelium, accounting for the many lesions caused by increased permeability, tissue oedema and haemorrhage, especially in the alimentary canal.

Arsenical poisoning may arise from the ingestion of arsenious oxide, a tasteless white powder – from copper, sodium and potassium arsenites, arsenates of lead and calcium, arsenic sulphides and gaseous arsine (confined to industry). In forensic practice, the rare cases of arsenic poisoning are now usually from arsenious oxide or one of the arsenites.[43–47]

Arsenical poisoning may be acute or chronic, the latter being the presentation of most environmental and occupational toxicity. Suicides are obviously invariably acute, whereas the uncommon homicidal cases may be either acute or chronic.

Fatal dosages in arsenical poisoning

If taken on an empty stomach, especially in solution, only about 150 mg may be fatal, but usually some 250–300 mg are needed as a minimum lethal dose. Much larger quantities have been survived and there is some evidence that tolerance to arsenic can be attained. With large doses, much may be vomited. Death can be rapid – within hours from ‘shock’ and cardiorespiratory failure – or may be delayed for many days, when hepatorenal failure is the mode of death. In chronic poisoning, no lethal dosage can be indicated, as if the ingestion exceeds the small normal excretion rate, then a cumulative build-up of arsenic will occur.

Autopsy findings

In acute poisoning the findings may be minimal, if death occurs within hours. There may be some mild irritation of the upper gastrointestinal tract, such as reddening of the gastric mucosa, especially along the top edges of the rugae. The description of 'red velvet' has been applied to some stomach linings in acute arsenic poisoning. There may be mucus coating and granules of the poisonous agent may be trapped on the lining – a reason for sending both contents and stomach wall for analysis, as in most suspected poisonings of any type. The intestines are usually normal in acute poisoning.

The only other lesion commonly seen is subendocardial haemorrhage on the left ventricular wall. This, of course, is a common finding in any severe shock condition when sudden hypotension occurs. It is seen in any gross injury, with loss of blood volume, blood pressure and neurogenic shock. Head injuries and raised intracranial pressure are other conditions in which these lesions are prominent (Chapter 13). The phenomenon can be rapid, the author (BK) having seen them in the victims of military air crashes where the heart was avulsed from its base at the moment of impact. One of the best descriptions of subendocardial haemorrhages was given by Sheehan in 1940 in obstetrical catastrophes.[48,49] The haemorrhages are situated on the upper part of the interventricular septum and on the opposing papillary muscles. The most severe the author (BK) has ever seen was in a massive suicidal overdose of arsenious oxide, where the haemorrhages were actually raised blood-filled blisters under the endocardium. These suggested the true diagnosis before analysis was carried out, albeit with an element of speculative good luck.

In chronic arsenical poisoning, the picture is quite different, though unless some suggestive history or circumstantial evidence is available, the diagnosis may be extremely difficult. As many a clinician has discovered to his chagrin in the past years, many a chronic arsenical poisoning has been misdiagnosed as a gastroenteritis.

Part of forensic mythology surrounds the alleged preservation of corpses dying from arsenic poisoning. This has been endlessly discussed, but there is no real evidence that it is true. A more likely explanation is that the dehydration from diarrhoea in chronic poisoning retards the usual moist putrefaction.

Externally there may be a diffuse abnormality of the skin, with a dry, scaly, hyperkeratotic surface. Clinically, there is a 'rain-drop' punctate pigmentation, but this may not be apparent after death unless really marked. It is more common in skin flexures and over the forehead and neck. There may be some hair loss. Puffy thickening and oedema of the face has been described, suggestive of myxoedema.

Internally the stomach may be normal or may show a chronic gastritis with thickening of the mucosa and subserous coats. Mucus formation may be noticeable and there may be a patchy inflammatory redness of some of the rugae. Sometimes there is a haemorrhagic gastritis with acute and chronic erosions. The small intestine is dilated and generally reddened, with thickened mucosa, the whole picture being of a non-specific congestion oedema so commonly seen in any enteritis.

There is rarely any mucosal ulceration. The contents may be copious and fluid, the usual description of 'rice-water' being applied. The large intestine may show minimal changes or be normal: the contents may be fluid and similar to the small bowel. The liver may reveal fatty change or more severe necrosis, sometimes at the periphery of the lobule. Severe liver damage may be associated with externally apparent jaundice. The kidney is damaged in chronic toxicity, there being non-specific tubular necrosis. The myocardium may also show myofibril damage, interstitial collection of cells and sometimes fatty degeneration.

Toxicology sampling and analytical results

In acute poisoning, the major requirement is the stomach and contents, and preferably the small intestine, tied off at each end. Blood, urine and liver should also be taken (Table 33.1).

Table 33.1 Levels in acute arsenious oxide poisoning from 49 fatalities

	Range	Average
Blood (mg/l)	0.6–9.3	3.3
Liver (mg/kg)	2.0–120	29
Kidney (mg/kg)	0.2–70	15
Spleen (mg/kg)	0.5–62	8.8
Brain (mg/kg)	0.2–4.0	1.7

From Rehling C.J. Poison residues in human tissues. In: Stolman A. (ed). *Progress in Chemical Toxicology*. New York: Academic Press, 1967, pp.363–86.

In chronic poisoning, especially if the diagnosis is not firmly established from circumstantial and gross autopsy findings, a much wider range of samples is needed:

- blood from peripheral veins
- stomach and contents
- small intestine and contents
- sample of large bowel contents
- urine
- bile
- liver
- kidney
- nail clippings or whole nails
- hair samples – whole length of at least 20 hairs, including roots.

Arsenic levels in blood are elevated only for a short time following absorption, unless exposure is continuous. The highest concentrations of arsenic are found tissues rich in sulphydryl (SH-) groups, such as skin, hair and nails. Typical levels of arsenic found in healthy persons unexposed to extra amounts over and above that normally (but variably) present in their environment are as follows: urine: 5-50 μg/l; blood: 0.5–2 μg/l; liver: <60 μg/kg (dry weight); nails: <10^3 μg/kg (dry weight).[28,50,51]

It was formerly thought that it took a week or two for ingested arsenic to find its way into the keratinized tissues such as hair and nails. More sensitive analytical techniques have, however, shown that it can appear there within hours of ingestion by mouth. The explanation was originally offered that arsenic was rapidly secreted into sweat, and spread to the hair and nails by surface diffusion. This has recently been disproved by neutron activation analysis and the mechanism remains obscure. The test for estimating the timing and duration of arsenic administration by analysing different lengths of the hair shaft has thus been vindicated. Arsenic can remain stored in keratin for several years after administration ceases.

Antimony

Antimony is similar to arsenic in many respects. Apart from industrial exposure, the usual vehicle of poisoning is 'tartar emetic', antimony potassium tartrate. This has been used suicidally and homicidally, as well as in some accidental deaths. The pathology and toxicology are similar to that of arsenic, the fatal dose of the tartrate emetic in an adult being about 1 g, though there is much inter-individual variability, so the minimal lethal dose is not a particularly useful concept, as with many other poisons. Occupationally unexposed people have either zero or not more than 1 μg/l of antimony in their body fluids and tissues.[52]

Baselt quotes a case of acute poisoning from antimony trichloride where the following concentrations (in mg/l or mg/kg) were found on analysis: blood: 4–6; liver: 45; kidney: 32; bile: 404.[28]

Thallium

Though other heavy metals have declined in forensic importance over the past century, thallium has several times been used homicidally in recent years, sometimes for multiple poisonings. Thallium is used as a rat killer and widely employed in industry, especially in glass manufacture. It has curious aspects in relation to forensic pathology, in that it can be seen radiologically in the intestine and deposited in the liver, so in the rare event of a pathologist suspecting thallium poisoning, X-rays of the body should be taken before autopsy. The other unique aspect is that it is probably the only homicidal agent to be confirmed after cremation. In the Young case in Britain in 1971, where two people died and several others were non-fatally poisoned by Young, thallium was detected retrospectively in the ashes of one of his victims.[53]

The fatal dose is somewhere about 1 g, depending upon the type of thallium compound employed, as there are several different salts available, such as the acetate, sulphate or nitrate. The estimates vary from 6 to 40 mg/kg body weight, with an average of about 12 mg/kg.

Autopsy appearances are variable and non-specific, but pallor and streaking of a pale, degenerate myocardium have been recorded. Hair loss is one of the clinical signs that arouses suspicion of thallium poisoning, as it was formerly used as a depilatory. This effect begins about 1 week after administration, but may not be noticeable for twice that time. Large tufts tend to come away, rather than a general thinning. Loss of the outer third of

Table 33.2 Levels in acute arsenious oxide poisoning from 49 fatalities

	Range	Average
Blood	0.5–11	4.0
Brain	3–15	7.8
Urine	1.7–11	5.2
Kidney	6–20	11
Liver	5–29	15

Baselt RC. *Disposition of Toxic Drugs and Chemicals in Man*. Foster City: Biomedical Publications, 2008.[28]

the eyebrows is said to be a significant sign, though these are also the areas that are lost in hypothyroidism.

Examination of the roots of surviving hairs may show a black coating, caused not by the thallium itself, but by an excess of melanin. Liver necrosis and renal tubular necrosis are non-specific findings in those who survive for some time.

References

1 Pasi A, Morath M, Hartmann H. [Cyanide poisoning: forensic toxicology observations in the study of 54 cases of fatal poisoning]. *Z Rechtsmed* 1985;95(1):35–43.

2 Fernando GC, Busuttil A. Cyanide ingestion. Case studies of four suicides. *Am J Forensic Med Pathol* 1991;12(3):241–6.

3 Padwell A. Cyanide poisoning. Case studies of one homicide and two suicides. *Am J Forensic Med Pathol* 1997;18(2):185–8.

4 Froldi R, Cingolani M, Cacaci C. A case of suicide by ingestion of sodium nitroprusside. *J Forensic Sci* 2001;46(6):1504–6.

5 Musshoff F, *et al*. Cyanide fatalities: case studies of four suicides and one homicide. *Am J Forensic Med Pathol* 2002;23(4):315–20.

6 Gill JR, Marker E, Stajic M. Suicide by cyanide: 17 deaths. *J Forensic Sci* 2004;49(4):826–8.

7 Zhu BL, *et al*. [Two suicide fatalities from sodium cyanide ingestion: differences in blood biochemistry]. *Chudoku Kenkyu* 2004;17(1):65–8.

8 Musshoff F, Kirschbaum KM, Madea B. An uncommon case of a suicide with inhalation of hydrogen cyanide. *Forensic Sci Int* 2011;204(1–3):e4–7.

9 Sayre JW, Kaymakcalan S. Cyanide poisoning from apricot seeds among children in central Turkey. *N Engl J Med* 1964;270:1113–5.

10 Shragg TA, Albertson TE, Fisher CJ, Jr. Cyanide poisoning after bitter almond ingestion. *West J Med* 1982;136(1):65–9.

11 Akyildiz BN, *et al*. Cyanide poisoning caused by ingestion of apricot seeds. *Ann Trop Paediatr* 2010;30(1):39–43.

12 Nader R, *et al*. Child cyanide poisoning after ingestion of bitter almonds. *Clin Toxicol (Phila)* 2010;48(6):574–5.

13 The Guyana tragedy – an international forensic problem. *Forensic Sci Int* 1979;13(2):167–72.

14 Thompson RL, Manders WW, Cowan WR. Postmortem findings of the victims of the Jonestown tragedy. *J Forensic Sci* 1987;32(2):433–43.

15 Heyndrickx A, Heyndrickx B. Management of war gas injuries. *Lancet* 1990;336(8725):1248–9.

16 Wong SH. Challenges of toxicology for the millennium. *Ther Drug Monit* 2000;22(1):52–7.

17 Greenfield RA, *et al*. Microbiological, biological, and chemical weapons of warfare and terrorism. *Am J Med Sci* 2002;323(6):326–40.

18 Bismuth C, *et al*. Chemical weapons: documented use and compounds on the horizon. *Toxicol Lett* 2004;149(1–3):11–18.

19 Uitti RJ, *et al*. Cyanide-induced parkinsonism: a clinicopathologic report. *Neurology* 1985;35(6):921–5.

20 Andrews JM, *et al*. The biohazard potential of cyanide poisoning during postmortem examination. *J Forensic Sci* 1989;34(5):1280–4.

21 Forrest AR, Galloway JH, Slater DN. The cyanide poisoning necropsy: an appraisal of risk factors. *J Clin Pathol* 1992;45(6):544–5.

22 Nolte KB, Dasgupta A. Prevention of occupational cyanide exposure in autopsy prosectors. *J Forensic Sci* 1996;41(1):146–7.

23 Curry AS. Cyanide poisoning. *Acta Pharmacol Toxicol (Copenh)* 1963;20:291–4.

24 Curry AS. *Poison Detection in Human Organs*, 2nd edn. American lecture series. Springfield: Charles C. Thomas, 1969.

25 Ballantyne B. Changes in blood cyanide as a function of storage time and temperature. *J Forensic Sci Soc* 1976;16(4):305–10.

26 McAllister JL, *et al*. The effect of sodium fluoride on the stability of cyanide in postmortem blood samples from fire victims. *Forensic Sci Int* 2011;209(1–3):29–33.

27 Karhunen PJ, Lukkari I, Vuori E. High cyanide level in a homicide victim burned after death: evidence of post-mortem diffusion. *Forensic Sci Int* 1991;49(2):179–83.

28 Baselt RC. *Disposition of Toxic Drugs and Chemicals in Man*, 8th edn. Baselt RC (ed). Foster City: Biomedical Publications, 2008, xviii.

29 Rhee J, *et al*. Distribution of cyanide in heart blood, peripheral blood and gastric contents in 21 cyanide related fatalities. *Forensic Sci Int* 2011;210(1–3):e12–15.

30 Porter WH. Ethylene glycol poisoning: quintessential clinical toxicology; analytical conundrum. *Clin Chim Acta* 2012;413 (3–4):365–77.

31 Armstrong EJ, *et al*. Homicidal ethylene glycol intoxication: a report of a case. *Am J Forensic Med Pathol* 2006;27(2):151–5.

32 Leth PM, Gregersen M. Ethylene glycol poisoning. *Forensic Sci Int* 2005;155(2–3):179–84.

33 Raekallio J, Jaaskelainen AJ, Makinen PL. The simple demonstration of calcium oxalate crystals in kidneys of victims of ethylene glycol poisoning. *J Forensic Sci* 1967;12(2):238–40.

34 Pomara C, *et al*. Calcium oxalate crystals in acute ethylene glycol poisoning: a confocal laser scanning microscope study in a fatal case. *Clin Toxicol (Phila)* 2008;46(4):322–4.

35 Takahashi S, *et al*. Brain death with calcium oxalate deposition in the kidney: clue to the diagnosis of ethylene glycol poisoning. *Leg Med (Tokyo)* 2008;10(1):43–5.

36 Wollersen H, *et al*. Oxalate-crystals in different tissues following intoxication with ethylene glycol: three case reports. *Leg Med (Tokyo)* 2009;11 Suppl 1:S488–90.

37 McMartin K. Are calcium oxalate crystals involved in the mechanism of acute renal failure in ethylene glycol poisoning? *Clin Toxicol (Phila)* 2009;47(9):859–69.

38 Cochat P, Rumsby G. Primary hyperoxaluria. N Engl J Med 2013;369(7):649–58.

39 Falk N, *et al*. Primary hyperoxaluria type 1 with systemic calcium oxalate deposition: case report and literature review. *Ann Clin Lab Sci* 2013;43(3):328–31.

40 Worcester EM, *et al*. A test of the hypothesis that oxalate secretion produces proximal tubule crystallization in primary hyperoxaluria Type I. *Am J Physiol Renal Physiol* 2013; 305(11):F1574–84.

41 Pien K, *et al*. An inherited metabolic disorder presenting as ethylene glycol intoxication in a young adult. *Am J Forensic Med Pathol* 2002;23(1):96–100.

42 Woolf AD, *et al*. Intentional infantile ethylene glycol poisoning presenting as an inherited metabolic disorder. *J Pediatr* 1992; 120(3):421–4.

43 Bradwell D. Reconstruction of an arsenic poisoning. *J Forensic Sci* 1963;8(2):295–302.

44 Cross JD, Dale IM, Smith H. A suicide by ingestion of a mixture of copper, chromium and arsenic compounds. *Forensic Sci Int* 1979;13(1):25–9.

45 Quatrehomme G, *et al*. Acute arsenic intoxication: forensic and toxicologic aspects (an observation). *J Forensic Sci* 1992; 37(4):1163–71.
46 Hinwood AL, *et al*. Exposure to inorganic arsenic in soil increases urinary inorganic arsenic concentrations of residents living in old mining areas. *Environ Geochem Health* 2004;26(1):27–36.
47 Lech T, Trela F. Massive acute arsenic poisonings. *Forensic Sci Int* 2005;151(2–3):273–7.
48 Sheehan HL. Subendocardial haemorrhages in shock. *Lancet* 1940;235(6088):831–2.
49 Sheehan HL. The pathology of obstetric shock. *J Obstet Gynaecol* 1940;47:218–31.
50 Stoeppler M, Vahter M. Arsenic. In: Herber RFM, Stoeppler M (eds). *TraceElement Analysis in Biological Specimens*. Amsterdam: Elsevier, 1994, pp. 291–320.
51 National Research Council. *Arsenic in Drinking Water*. Washington: National Research Council, 1999.
52 Braithwaite R. Metals and anions. In: Moffat AC, Osselton MD, Widdop B (eds). *Clarke's Analysis of Drugs and Poisons*. London: Pharmaceutical Press, 2004, pp. 259–78.
53 Johnson H. R v Young - murder by thallium. *Med Leg J* 1974;42(3):76–90.

CHAPTER 34

Deaths from Organic Solvents

- Volatile substance abuse
- Substances used in abuse
- The autopsy on fatal solvent-abuse victims
- References

A wide range of organic compounds used in industry and in the home as solvents may cause injury or death, especially when used carelessly or for improper purposes. Other organic substances, often gaseous, can also be fatal when used or abused in the same circumstances.

Volatile substance abuse

Volatile compounds such as diethyl ether, chloroform and nitrous oxide have been deliberately inhaled for recreational purposes since the early 19th century.[1,2]

On a more global scale this phenomenon arose, spontaneously and independently, in several parts of the world in the 1960s. It consists of deliberately inhaling a variety of substances, especially organic solvents, in order to achieve a distortion of consciousness. The effects vary from a state resembling alcoholic intoxication through euphoria (sometimes of an erotic nature) and distortion of perception, to actual hallucinations. The practitioners of this activity are predominantly, though by no means exclusively, male and most are between the ages of about 14 and 22 years, though again there are a few beyond either end of this age range. The majority of deaths occur in solitary users, some 70 per cent being reported by Anderson *et al.* as having happened when the young person was alone.[3] Sniffing can certainly be a group activity, however, as is seen in schools and even the streets of some cities.

At first, the most common substance inhaled was a toluene-based adhesive and therefore the name 'glue-sniffing' soon became attached to the habit, though in fact many substances now used are not adhesives. Although (like the sexual asphyxias, with which there is some cross-relationship) the ratio of deaths to non-fatal escapades is relatively small, the large number of children and young people who indulge in the habit means that a considerable death toll occurs annually.

The usual method of abuse is for a quantity of the solvent or other chemical to be placed in a plastic bag – which may be any kind from a large black polythene garbage sack to a used potato-crisp packet. The open end is then placed against the nose and mouth, and the air inside re-breathed. The warmth of the hand holding the bag, as well as the warm breath, encourages vaporization of the solvent, which enters the tidal air stream and is absorbed through the pulmonary membranes into the blood. When the substance is not a viscous glue, it may be placed on a handkerchief or rag, and inhaled direct as a pad over the nose and mouth.[4,5]

When gaseous substances are abused, they may be introduced directly into the mouth or nose. A common variety is butane or propane, taken from either a large cylinder used for camping, heating and cooking, or from the small ampoule cylinders sold for refilling gas cigarette lighters. Others are used directly from pressurized aerosol cans, including pain-relieving sprays used for the relief of muscular conditions. Yet again, sniffing may be attained by merely inhaling directly from the neck of a container. Tins, jerry-cans and the petrol-fillers of motor vehicles may be used in this way. Some fire extinguishers contain an organic bromine derivative which is also abused for inhalation. This has a particular propensity for sensitizing the myocardium to catecholamines.

Dangers of solvent abuse

Sudden death

The major cause of death appears to be sudden cardiac arrest, following an arrhythmia.[6–8] Any of the solvents appears to have the ability to sensitize the myocardium to the action of catecholamines, such as noradrenaline. Any sudden 'flight-or-fight' stimulus, even some considerable time after sniffing solvents, has the ability to precipitate ventricular fibrillation and hence sudden death. An instance seen by the author (BK) involved a youth whose habit was to steal fire extinguishers from trains parked in sidings and inhale the bromine-based contents. Having been in trouble with the police before, he took fright on seeing a constable approaching, though in fact the officer was merely walking his dog. The boy ran from his group of friends and did not reappear, being found dead in some bushes some time later, though he had not 'sniffed' that day. The autopsy and toxicology were negative, apart from residual traces of organic substance in his blood.

In addition to this physiological mechanism, actual myocarditis can occasionally occur, as in a 15-year-old girl who dropped dead while inhaling from the petrol tanks of vehicles. At autopsy all that the author (BK) could find was a florid, diffuse interstitial myocarditis with minimal myofibril necrosis.

Chemical effects

The mechanical means of obtaining concentrated solvent vapour is in itself dangerous. Persistent rebreathing can produce hypoxia and hypercapnia, which is additive to the toxic effects of the solvent itself. When large plastic bags are used, the abuser sometimes places his head within the bag and this risks the dangers of rapid death from plastic bag asphyxia (Chapter 14). It is difficult to know if some of these cases are at least partially instances of erotic hypoxia, the effects of both oxygen lack and the hallucinogenic effect of the solvent combining to give both sexual pleasure and a heightened risk of death.

Another potent risk is vomiting while the effects of the solvent incapacitate the victim sufficiently to prevent his reflexes from protecting or clearing his glottis or air passages. The usual warning must be given, however, about uncritically accepting the finding of gastric contents in the air passages at autopsy. This may well have been an agonal regurgitation in a victim who was dying of the common cardiac (ventricular fibrillation) effect of solvents on the myocardium. This has medico-legal relevance in that a fellow abuser or even some other bystander may be accused of failing to render assistance in clearing the air passages, when in fact this was the effect, rather than the cause of death. This is not to say that aspiration of vomit cannot be the cause of death, as in alcoholic intoxication, but the autopsy finding should be backed up with some circumstantial evidence that it occurred before the agonal period.

Physical danger

When gaseous substances are used, such as butane or propane from cylinders, or propellants from aerosol cans, a physical danger is added to the chemical effects. The gases are commonly directed or sprayed into the open mouth while inhalation is performed. The release of high-pressure gas causes rapid cooling by the 'refrigerator effect' and the impact of this on the palate, pharynx and larynx may cause a reflex cardiac arrest.[9,10] The author (BK) has dealt with two such cases, one in a school yard, where the users of small propane refuellers virtually dropped dead in the presence of other youths. The mechanism of this phenomenon is disputed, but freezing of the sensitive pharyngolaryngeal area is surely a parallel to the sudden deaths seen when cold water enters the nasopharynx in sudden immersion deaths.

Danger to long-term users

Long-term users can suffer liver damage, typical of halogenated hydrocarbon exposure, with fatty change in the liver and sometimes associated renal damage.[1,3,6,11–13]

Substances used in abuse

Toluene

Toluene is one of the most widespread hydrocarbons in the environment as it occurs naturally in crude oil, natural gas deposits and in emissions from volcanoes and forest fires.[14] Toluene was one of the first substances recognized as giving rise to 'glue-sniffing', as it is the solvent for many adhesives. It is an aromatic petrol hydrocarbon used widely in industry as a solvent and thinner for adhesives and paints. It resembles benzene in many of its properties, another substance that can be used in solvent inhalation. Toluene can cause acute and chronic intoxication in industrial situations. Exposure to relatively high concentrations in the air, between 10,000 and 30,000 ppm can cause drunkenness, mental confusion and coma within a few minutes.[15,16]

In non-fatal toluene abuse, blood levels of 0.3–7.0 mg/l were measured by Bonnichsen *et al.*, with urine excretion of up to 5 mg/l.[17] Those with blood concentrations of 1.0–2.5 mg/l showed some sign of intoxication, while half of those between 2.5 and 10 mg/l were admitted to hospital with marked symptoms. Those who were unconscious or dead had blood levels in excess of 19 mg/l. Nomiyama and Nomiyama found blood levels of between 50 and 80 mg/l in three fatalities.[18] Baselt quotes a fatal range of between 10 and 48 mg/l with an average of 22 mg/l toluene in blood for fatalities, the average in the lung being 12 mg/kg and in the brain 47 mg/kg. Brain damage has been reported in long-term abusers, with electroencephalographic changes, encephalopathy and occasional cerebral atrophy.[11,19–21]

Petrol (gasoline), xylene and benzene

These closely resemble toluene in behaviour, though benzene is said to be more potent in causing intoxication. Xylene is a mixture of *o*-, *m*- and *p*-dimethylbenzene in which the *m*-isomer predominates.[22] As with toluene and most other solvents, they can burn the skin if left in contact with it for some time. Bux *et al.* investigated the effect of post-mortem petrol exposure on skin in 18 corpses with exposure times between 10 min and 24 h. They observed the earliest onset of skin changes within 2 h of exposure consisting of swelling and wrinkling with detachment of the upper layers of the skin appearing histologically as non-vital acantholyses located in the prickle-cell layer with formation of intra-epidermal bullae.[23] Byard *et al.* observed unusual facial markings in a series of gasoline inhalation deaths, where death had occurred while the victim was lying in bed sniffing gasoline from a can held to the face. The mouth and nose had been pressed firmly against the can by the weight of the head leaving circular impressions on the faces of each of the victims providing an autopsy marker that assisted in clarifying the details of the fatal episodes.[24]

Martinez *et al.* reported a sudden death of a 51-year-old male after inhaling gasoline vapours from an accidental leak while supervising the repairs of the telephone lines in a manhole near to a gas station. Extensive blistering and peeling of skin were observed on the skin of the face, neck, anterior chest, upper and lower extremities, and back. The internal examination showed a strong odour of gasoline, particularly in the respiratory tract. The gasoline concentration in different tissues was as follows: heart blood: 35.7 mg/l; urine: not detected; vitreous humour: 1.9 mg/l; liver: 194.7 mg/kg; lung: 147.6 mg/kg; and gastric content: 116,6 mg/l (2.7 mg total).[25]

Carnevale *et al.* described a case of death of a 25-year-old male who was assumed to have accidentally ingested gasoline while attempting to unload it from a tank with a f1exible plastic tube. Gasoline was found in various organs and body fluids but not in the urine. The concentrations were: heart blood: 51.5 mg/l; liver: 663 mg/l; lung: 457 mg/l; brain: 44.2 mg/l; and kidney: 51.5.[26]

The odour threshold for benzene has been reported as 1–5 ppm in air, and the current threshold limit value in the workplace is 0.5 ppm (1.6 mg/m^3).[16] In chronic exposure, benzene can cause bone-marrow depression and fatal aplastic anaemia, but this is not a feature of the shorter exposures in solvent abuse.

Dichloromethane (methylene chloride) and 1,2-dichloroethane (ethylene dichloride)

These are found in paint strippers and, as these solvents, in many other products. One used for abuse is the solvent for typewriter correction fluids.[27,28] Several accidental dichloromethane fatalities have been reported by various authors in the forensic literature.[29–34]

Butane and propane

These have been mentioned earlier, being used direct from pressurized containers. They are light hydrocarbons, being the upper fractions of oil distillation.

Fluorocarbons

These are the substances now blamed for having the worst effect on the ozone layers of the upper atmosphere. They were widely used as refrigerants and propellants in aerosol containers. It is in this latter role that they are widely abused for euphoric and hallucinatory effects. The various compounds are numbered, rather than named, two fluorine atoms being incorporated into molecules that otherwise resemble carbon tetrachloride. Those used for propellants are FC-11 and FC-12.

A similar compound incorporating bromine instead of fluorine is used as a fire extinguisher, as is carbon tetrachloride itself. The first reported death due to intentional inhalation of fluorocarbons involved a 15-year-old boy and was published by Baselt and Cravey.[35] In 1970, Bass published a series of 110 sudden deaths, including many from fluorocarbons.[36] As mentioned earlier, these substances sensitize the myocardium to circulating catecholamines. The range of blood concentrations in fatal cases in respect of FC-12 is 0.6–12 mg/l, with a mean of 3.0 mg/l and for FC-11, 1.2–32 mg/l, with a mean of 12 mg/l. In the lung, FC-12 may be present at levels of 0.9–134 mg/kg, with a mean of 33 mg/kg; for FC-11 the corresponding figures are 5.8–94 mg/kg, with a mean of 43 mg/kg.[16]

Carbon tetrachloride

Carbon tetrachloride is a clear, colourless, non-flammable, volatile liquid with a characteristic, sweet odour. The odour threshold in water is 0.52 mg/l and in air > 10 ppm.[37] It was formerly widely used as a degreaser, dry-cleaner and fire extinguisher, but now mostly in the production of chlorofluorocarbons (CFCs) and other chlorinated hydrocarbons. Carbon tetrachloride is quite toxic, though it (unwisely) used to be used in human pharmacy to treat intestinal worms. As little as 3–5 ml can be fatal.[16] Much of its toxicity is industrial, but it has also been used in suicide and solvent abuse. Chronic exposure can cause liver and renal damage, worsened by the simultaneous use of alcohol. Addiction can occur, even from initial exposure during industrial use.

As with most halogenated hydrocarbons, the liver suffers from exposure to tetrachloride. There is a centrilobular necrosis, usually preceded by fatty change if the poisoning is low level and lasting. In fatal cases there may well be virtually total acute yellow atrophy. The liver damage is markedly worsened by a high alcohol intake. Renal changes consist of a tubular necrosis and diffuse fatty degeneration in the cortex.

Post-mortem blood levels vary greatly, but a fatal case has been recorded with a concentration of 260 mg/l.[38] Korenke and Pribilla found tissue levels at autopsy 1 week after inhalation of 142 mg/kg in the liver and 39 mg/kg in the lung.[39]

Other halogenated hydrocarbons

Other halogenated hydrocarbons have similar effects to carbon tetrachloride, but the level of toxicity varies with the number of chlorine atoms in the molecule. The ascending order of danger is methyl chloride, trichlormethane, chloroform and carbon tetrachloride. Others include trichlorethylene, used widely in both anaesthesia (Trilene) and in dry-cleaning. Several other similar compounds have been the cause of fatalities in industry as well as in solvent abuse. The pathological features are similar in most of them, the effects being on the central nervous system in acute massive overdose, whether by ingestion or inhalation, and upon the liver and kidneys in more chronic intoxications.

The autopsy on fatal solvent-abuse victims

The scene should be visited if possible, though it is rare to find the body there, as strenuous resuscitation and removal by ambulance is always a prime consideration in children and young persons found apparently dead. The paraphernalia of sniffing may be seen in its original state.

At autopsy, the clothing should be examined, even though it has almost always been removed for resuscitation attempts. Any soiling with adhesive or solvent stains should be detected and, though volatile, should be kept for forensic science investigation. The best means is to pack them as soon as possible in a glass container with a teflon- or aluminium foil-lined lid to retain any vapour.

Externally, the face should be inspected for any signs of chronic or recent solvent abuse. The act of holding a bag against the lower face, often contaminating it with glue or solvent, may leave skin lesions.[24] These can be red erythematous pimples or actual excoriations from the irritant action of the solvent. The lesions may become infected or scratched, becoming crusted. The rest of the autopsy may be unrewarding from the point of view of gross pathology. Rarely, there may be a fatty liver from long-standing damage from the solvent, especially the halogenated hydrocarbons. Full samples for histological examination should be taken to determine the state of the myocardium, liver and brain. More immediate is the need to obtain samples for analysis.

Vigorous resuscitation, including mouth-to-mouth and chest compression, together with mechanical ventilation and oxygen administration, will obviously blow off much of the solvent in the lungs. If it has already been absorbed, however, some will come back into alveolar air from the lung tissue and the sensitivity of the head-space gas chromatography used for its detection is often sufficient to identify the substance, which can also be detected in blood and tissues.

Blood samples should be taken in the usual manner, including a tube with fluoride for alcohol, which is sometimes also present. A lung should be taken intact for the laboratory. It was formerly the practice to aspirate air from the trachea before removal of viscera, using a 50 ml syringe, which was then sealed and sent to the laboratory. This is impracticable, and the best method is to open the pleural cavity and pass a string ligature round the hilum of a lung, pulling it tight to occlude the main bronchus. This is then drawn tight and the hilum transected. In actual fact, little is lost if the lung is cut off without this procedure, as long as it is put straight into a glass container with a teflon- or aluminium foil-lined lid without delay and without squeezing out the contained air.

A urine sample, and unfixed tissue from liver and brain should also be supplied to the toxicology laboratory, though local discussion should be made to determine the requirements of each laboratory.

References

1 Flanagan RJ, Streete PJ, Ramsey JD. Volatile substance abuse. In: *United Nations International Drug Control Programme Technical Series*. Vienna, UNODC, 1997.
2 Defalque RJ, Wright AJ The short, tragic life of Robert M. Glover. *Anaesthesia* 2004; 59(4):394–400.
3 Anderson HR, Macnair RS, Ramsey JD. Deaths from abuse of volatile substances: a national epidemiological study. *Br Med J Clin Res Ed* 1985;290(6464):304–7.
4 Williams JF, Storck M. Inhalant abuse. *Pediatrics* 2007;119(5): 1009–17.
5 Ghodse H, *et al.* Trends in UK deaths associated with abuse of volatile substances, 1971–2008. Report. London: International Centre for Drug Policy, St. George's University of London, 2010, xiii.
6 Flanagan RJ, *et al.* An introduction to the clinical toxicology of volatile substances. *Drug Saf* 1990;5(5):359–83.
7 Adgey AA, Johnston PW, McMechan S. Sudden cardiac death and substance abuse. *Resuscitation* 1995;29(3):219–21.
8 El-Menyar AA, El-Tawil M, Al Suwaidi J. A teenager with angiographically normal epicardial coronary arteries and acute myocardial infarction after butane inhalation. *Eur J Emerg Med* 2005;12(3):137–41.
9 Albright JT, *et al.* Upper aerodigestive tract frostbite complicating volatile substance abuse. *Int J Pediatr Otorhinolaryngol* 1999; 49(1):63–7.
10 Cvetkovski S, Dietze P. The incidence and characteristics of volatile substance use related ambulance attendances in metropolitan Melbourne, Australia. *Soc Sci Med* 2008;66(3):776–83.
11 Complications of chronic volatile substance abuse. *Lancet* 1988;2(8608):431–2.
12 Ramsey J, *et al.* An introduction to the practice, prevalence and chemical toxicology of volatile substance abuse. *Hum Toxicol* 1989;8(4):261–9.
13 Cairney S, *et al.* The neurobehavioural consequences of petrol (gasoline) sniffing. *Neurosci Biobehav Rev* 2002;26(1):81–9.
14 Rushton L, Cameron K. Selected organic chemicals. In: Holgate ST, *et al.* (eds). *Air Pollution and Health*. London: Academic Press, 1999, pp. 813–38.
15 Longley EO, *et al.* Two acute toluene episodes in merchant ships. *Arch Environ Health* 1967;14(3):481–7.
16 Baselt RC. *Disposition of Toxic Drugs and Chemicals in Man*, 8th edn. Baselt RC (ed). Foster City: Biomedical Publications, 2008, xviii.
17 Bonnichsen R, Maehly AC, Moeller M. Poisoning by volatile compounds. I. Aromatic hydrocarbons. *J Forensic Sci* 1966;11(2):186–204.
18 Nomiyama K, Nomiyama H. Three fatal cases of thinner-sniffing, and experimental exposure to toluene in human and animals. *Int Arch Occup Env Health* 1978;41(1):55–64.
19 Ron MA. Volatile substance abuse: a review of possible long-term neurological, intellectual and psychiatric sequelae. *Br J Psychiatry* 1986;148:235–46.
20 Chadwick OF, Anderson HR. Neuropsychological consequences of volatile substance abuse: a review. *Hum Toxicol* 1989;8(4):307–12.
21 Garland EL, Howard MO. Volatile substance misuse: clinical considerations, neuropsychopharmacology and potential role of pharmacotherapy in management. *CNS Drugs* 2012; 26(11):927–35.
22 Moffat AC, Osselton D, Widdop B (eds). *Clarke's Analysis of Drugs and Poisons*. London: Pharmaceutical Press, 2004, pp. 1706–7.
23 Bux R, Stengel PD, Schnabel A. Dermal lesions after post mortem petrol-exposure. *Forensic Sci Int* 2006;163(1–2):115–8.
24 Byard RW, Chivell WC, Gilbert JD. Unusual facial markings and lethal mechanisms in a series of gasoline inhalation deaths. *Am J Forensic Med Pathol* 2003;24(3):298–302.
25 Martinez MA, Ballesteros S, Alcaraz R. Reporting a sudden death due to accidental gasoline inhalation. *Forensic Sci Int* 2012;215(1–3):114–20.
26 Carnevale A, Chiarotti M, De Giovanni N. Accidental death by gasoline ingestion. Case report and toxicological study. *Am J Forensic Med Pathol* 1983;4(2):153–7.
27 Wodka RM, Jeong EW. Cardiac effects of inhaled typewriter correction fluid. *Ann Intern Med* 1989;110(1):91–2.
28 Wodka RM, Jeong EW. Myocardial injury following the intentional inhalation of typewriter correction fluid. *Mil Med* 1991;156(4):204–5.
29 Winek CL, Collom WD, Esposito F. Accidental methylene chloride fatality. *Forensic Sci Int* 1981;18(2):165–8.
30 Kim NY, Park SW, Suh JK. Two fatal cases of dichloromethane or chloroform poisoning. *J Forensic Sci* 1996;41(3):527–9.
31 Goulle JP, *et al.* Fatal case of dichloromethane poisoning. *J Anal Toxicol* 1999;23(5):380–3.
32 Takeshita H, *et al.* Postmortem absorption of dichloromethane: a case study and animal experiments. *Int J Legal Med* 2000; 114(1–2):96–100.
33 Fechner G, *et al.* Fatal intoxication due to excessive dichloromethane inhalation. *Forensic Sci Int* 2001;122(1):69–72.
34 Zarrabeitia MT, *et al.* Accidental dichloromethane fatality: a case report. *J Forensic Sci* 2001;46(3):726–7.
35 Baselt RC, Cravey RH. A fatal case involving trichloromonofluoromethane and dichlorodifluoromethane. *J Forensic Sci* 1968;13(3):407–10.
36 Bass M. Sudden sniffing death. *JAMA* 1970;212(12):2075–9.
37 WHO. Carbon tetrachloride. In: *International Programme on Chemical Safety II. Series*. Geneva: World Health Organization, 1999.
38 Cravey RH. *Disposition of Toxic Drugs and Chemicals in Man*. Baselt RC (ed). Foster City: Biomedical Publications, 1978.
39 Korenke HD, Pribilla O. [Suicide by single inhalation of carbon tetrachloride (CCl4), with resulting leukoencephalopathy]. *Arch Toxikol* 1969;25(1):109–26.

This page intentionally left blank

Appendix: Council of Europe Committee of Ministers Recommendation No. R (99) 3

- Recommendation No. R (99) 3 of the committee of ministers to member states on the harmonisation of medico-legal autopsy rules
- Principles and rules relating to medico-legal autopsy procedures
- Appendix to recommendation No. R (99) 3

Recommendation No. R (99) 3 of the committee of ministers to member states on the harmonisation of medico-legal autopsy rules*

(Adopted by the Committee of Ministers on 2 February 1999 at the 658th meeting of the Ministers' Deputies)

The Committee of Ministers, under the terms of Article 15.*b* of the Statute of the Council of Europe,

Considering that the aim of the Council of Europe is to achieve a greater unity between its members;

Having regard to the principles laid down in the Convention for the Protection of Human Rights and Fundamental Freedoms and, in particular, the prohibition of torture or inhuman or degrading treatment or punishment, and the right to life;

Conscious that it is normal practice for autopsies to be carried out in all Council of Europe member States to establish the cause and manner of death for medico-legal or other reasons or to establish the identity of the deceased;

Considering the importance of compensation for victims and families in criminal and civil proceedings;

Underlining the need for investigation, description, photographic documentation and sampling during medico-legal autopsy to follow primarily medical and scientific principles and simultaneously consider legal requirements and procedures;

Conscious that the increasing mobility of the population throughout Europe and the world, as well as the increasing internationalisation of judicial proceedings, require the adoption of uniform guidelines on the way autopsies are to be carried out and on the way autopsy reports are to be established;

Considering the Council of Europe Agreement on the Transfer of Corpses (European Treaty Series No. 80) and having regard to the difficulties often experienced by the receiving country when a dead body is repatriated from one member state to another;

Aware of the importance of proper autopsy procedures, in particular with a view to bringing to light illegal executions, and murders perpetrated by authoritarian regimes;

Underlining the need to protect the independence and impartiality of medico-legal experts, as well as to make available the necessary legal and technical facilities for them to carry out their duties in an appropriate way and to promote their training;

Considering the importance of national quality control systems to ensure the proper performance of medico-legal autopsies;

---

* When this recommendation was adopted, the Representatives of Denmark and the Netherlands, in application of Article 10.2c of the Rules of Procedure for the meeting of the Ministers' Deputies, reserved the right of their Governments to comply or not with paragraph 2 (scope of the recommendation) of the present recommendation.

When this recommendation was adopted, the Representative of Germany, in application of Article 10.2c of the Rules of Procedure for the meeting of the Ministers' Deputies, reserved the right of his Government to comply or not with paragraph 2 f and h of the present recommendation.

Underlining the need to strengthen international co-operation with a view to the progressive harmonisation of medico-legal autopsy procedures at a European level;

Having regard to Recommendation 1159 (1991) on the harmonisation of autopsy rules adopted, at its 43rd Ordinary Session, by the Parliamentary Assembly of the Council of Europe;

Having regard to the Model Autopsy Protocol of the United Nations, endorsed by the General Assembly of the United Nations in 1991;

Taking into account the 'guide on disaster victim identification' adopted by the International Criminal Police Organisation (Interpol) General Assembly in 1997,

1 Recommends the governments of member states:
  - **(i)** to adopt as their internal standards the principles and rules contained in this recommendation;
  - **(ii)** to take or reinforce, as the case may be, all appropriate measures with a view to the progressive implementation of the principles and rules contained in this recommendation;
  - **(iii)** to set up a quality assurance programme to ensure the proper implementation of the principles and rules contained in this recommendation.

2 Invites the governments of member states to inform the Secretary General of the Council of Europe upon his or her request of the measures taken to follow up the principles and rules contained in this recommendation.

Principles and rules relating to medico-legal autopsy procedures

Scope of the recommendation

1 In cases where death may be due to unnatural causes, the competent authority, accompanied by one or more medico-legal experts, should where appropriate investigate the scene, examine the body and decide whether an autopsy should be carried out.

2 Autopsies should be carried out in all obvious or suspected unnatural death, even where there is a delay between causative events and death, in particular:
  - **a** homicide or suspected homicide;
  - **b** sudden, unexpected death, including sudden infant death;
  - **c** violation of human rights such as suspicion of torture or any other form of ill treatment;
  - **d** suicide or suspected suicide;
  - **e** suspected medical malpractice;
  - **f** accidents, whether transportational, occupational or domestic;
  - **g** occupational disease and hazards;
  - **h** technological or environmental disasters;
  - **i** death in custody or death associated with police or military activities;
  - **j** unidentified or skeletalised bodies.

3 Medico-legal experts must exercise their functions with total independence and impartiality. They should not be subject to any form of pressure and they should be objective in the exercise of their functions, in particular in the presentation of their results and conclusions.

Principle I – Scene investigation

A *General principles*

1 In case of obvious or suspected unnatural death, the physician who first attended the dead body should report to the competent authorities, the latter deciding whether an examination should be carried out by a qualified medico-legal expert or by a physician familiar with medico-legal examination.

2 Particularly in cases of homicide or suspicious death, medico-legal experts should be informed without delay and, where appropriate, go immediately to the place where the body is found and have immediate access there. In this respect, there should be an adequate structure of co-ordination among all persons involved and, in particular, among judicial bodies, medico-legal experts and police.

B *Examination of the body*

1 Role of the police

The following tasks, among others, should be carried out by police officers:
  - **a** record the identities of all persons at the scene;
  - **b** photograph the body as it is found;
  - **c** make sure that all relevant artifacts are noted, and that all exhibits, such as weapons and projectiles, are seized for further examination;
  - **d** in agreement with the medico-legal expert, obtain identification of the body and other pertinent information from scene witnesses, including those who last saw the decedent alive, where available;
  - **e** protect the deceased's hands and head with paper bags, under the control of the medico-legal expert;
  - **f** preserve the integrity of the scene and surroundings;

2 Role of the medico-legal expert

The medico-legal expert should without delay:

- **a** be informed of all relevant circumstances relating to the death;
- **b** ensure that photographs of the body are properly taken;
- **c** record the body position and its relation to the state of the clothing and to the distribution pattern of rigor mortis and hypostasis, as well as the state of *post-mortem* decomposition;
- **d** examine and record the distribution and pattern of any blood stains on the body and at the scene, as well as other biological evidence;
- **e** proceed to a preliminary examination of the body;
- **f** except where the body is decomposed or skeletal, note the ambient temperature and deep-rectal temperature of the body, and estimate the time of death by recording the degree, location and fixation of rigor mortis and hypostasis, as well as other findings;
- **g** make sure that the body is transported and stored in a secure and refrigerated location in an undisturbed state.

Principle II – Autopsy physicians

Medico-legal autopsies should be performed, whenever possible, by two physicians, of whom at least one should be qualified in forensic pathology.

Principle III – Identification

In order to ensure that proper identification of the body is carried out in accordance with the disaster victim identification guide adopted by the General Assembly of Interpol in 1997, the following criteria should be considered: visual recognition, personal effects, physical characteristics, dental examination, anthropological identification, fingerprints and genetic identification.

1 Visual identification

Visual identification of a body should be carried out by relatives or persons who knew and have recently seen the decedent.

2 Personal effects

A description of clothing, jewellery and pocket contents should be recorded. These may assist correct identification.

3 Physical characteristics

Physical characteristic should be recorded through an external and an internal examination.

4 Dental examination

Where appropriate, the examination of teeth and jaws should be carried out by a dentist with medico-legal experience.

5 Anthropological identification

Whenever human material is skeletised or in an advanced stage of decomposition, an anthropological identification should be carried out, if necessary.

6 Fingerprints

Where appropriate, fingerprints should be taken by police officers. A close collaboration should exist between all experts involved.

7 Genetic identification

Where appropriate, genetic identification should be carried out by an expert in forensic genetics.

It is appropriate to take biological samples from the deceased in order to assist genetic identification. Measures should be taken in order to avoid contamination and guarantee appropriate storage of biological samples.

Principle IV – General considerations

1 Medico-legal autopsies and all related measures must be carried out in a manner consistent with medical ethics and respecting the dignity of the deceased.

2 Where appropriate, the closest relatives should be given an opportunity to see the corpse.

3 Before beginning the autopsy, the following minimum rules should be applied:

- **a** record the date, time and place of autopsy;
- **b** record the name(s) of the medico-legal expert(s), assistant(s) and all other persons present at the autopsy with indication as to the position and role of each one in the autopsy;
- **c** take colour photographs or video, where appropriate, of all relevant findings and of the dressed and undressed body;
- **d** undress the body, examine and record clothing and jewellery, verify the correspondence between injuries on the body and clothing;
- **e** where appropriate, take X-rays, particularly in cases of suspected child abuse, and for identification and location of foreign objects.

4 Where appropriate, before beginning the autopsy, body orifices should be appropriately swabbed for the recovery and identification of biological trace evidence.

5 If the decedent was hospitalised prior to death, admission blood specimens and any X-rays should be obtained as well as hospital records.

Principle V – Autopsy procedures

I external examination

1 The examination of the clothing is an essential part of the external examination and all findings therein are to be clearly described. This is especially important in those cases where the clothing has been damaged or soiled: each area of recent damage must be described fully and relevant findings are to be related to the site of injuries on the corpse. Discrepancies in such findings are also to be described.

2 The description of the body following an external examination must include:

 a age, sex, build, height, ethnic group and weight, nutritional state, skin colour and special characteristics (such as scars, tattoos or amputations);

 b post-mortem changes, including details relating to rigor and post-mortem hypostasis – distribution, intensity, colour and reversibility – and putrefaction and environmentally induced changes;

 c findings on a primary external inspection and description which, if required, include sampling of stains and other trace evidence on the body surface and a reinspection after removal and cleaning of the body;

 d inspection of the skin of the posterior surfaces of the corpse;

 e description and careful investigation of the head and the facial orifices includes: colour, length, density and distribution of hair (and beard); nasal skeleton; oral mucosa, dentition and tongue; ears, retro-auricular areas and external meati; eyes: colour of irises and sclerae, regularity and appearance of pupils, sclerae, conjunctivae; skin (presence and absence of petechiae to be described); if fluids have been evacuated from facial orifices, their colour and odour;

 f neck: checking for excessive mobility, presence and absence of abrasions, other marks and bruising (including petechiae) over the entire circumference of the neck;

 g thorax: shape and stability; breasts; aspect, nipples and pigmentation;

 h abdomen: external bulging, pigmentation, scars, abnormalities and bruising;

 i anus and genitals;

 j extremities: shape and abnormal mobility, abnormalities; injection marks and scars; palmar surfaces, finger and toe nails;

 k material findings under fingernails.

3 All injuries, including abrasions, bruises, lacerations and other marks have to be described by shape, exact measurement, direction, edges, angles and location relative to anatomical landmarks. Photographs should be taken. Bite marks shall be swabbed, and casts made where necessary.

4 Signs of vital reaction around wounds, foreign particles inside wounds and in their surroundings and secondary reactions, such as discolouration, healing and infections must also be described.

5 The investigation of cutaneous and sub-cutaneous bruising may require local skin incision.

6 Where appropriate, specimens from wounds must be removed for further investigations, such as histology and histochemistry.

7 All signs of recent or old medical and surgical intervention and resuscitation must be described. Medical devices must not be removed from the body before the intervention of the medico-legal expert.

8 A decision has to be taken at this stage as to the strategies of investigation and the necessity of documentation by X-rays and other imaging procedures.

II internal examination

A General

1 All relevant artifacts produced by the dissection and from sampling procedures, must be documented.

2 All three body cavities – head, thorax and abdomen – must be opened layer by layer. Where appropriate, the vertebral canal and joint cavities should be examined.

3 Examination and description of body cavities include: an examination for the presence of gas (pneumothorax), measurement of volume of fluids and blood, appearance of internal surfaces, intactness of anatomical boundaries, external appearance of organs and their location; adhesion and cavity obliterations, injuries and haemorrhage.

4 The demonstration and dissection of the soft tissues and musculature of the neck have to be components of all medico-legal autopsies (see the paragraph concerning special procedures).

5 All organs must be examined and sliced following established guidelines of pathological anatomy. This includes opening of all relevant vessels, for example, intracranial arteries, sinuses, carotid arteries, coronary arteries, pulmonary arteries and veins, aorta and vessels of the abdominal organs, femoral arteries and lower limb veins. Relevant ducts have to be dissected, for example, central and peripheral airways, biliary ducts and ureters. All hollow organs

have to be opened and their content described by colour, viscosity, volume (samples should be retained, where appropriate). All organs have to be sliced and the appearance of the cut surface described. If injuries are present, the dissection procedure may have to vary from the normal one: this should be appropriately described and documented.

6 All internal lesions and injuries must be precisely described by size and location. Injury tracks must be described in order to include their direction as regards the organ anatomy.

7 The weight of all major organs must be recorded.

B Detailed

1 *Head*

- **a** Before opening the skull, the periosteum must be scraped off in order to display or exclude any fractures.
- **b** The head examination procedure must allow the inspection and description of the scalp, external and internal surfaces of the skull and of the temporal muscles.
- **c** The thickness and appearances of the skull and sutures, the appearances of the meninges, the cerebrospinal fluid (CSF), the wall structure and contents of cerebral arteries and sinuses must be described. The description of the bones must also include an examination of their intactness, including the connection between the skull and the first two vertebrae.
- **d** In obvious or suspected head injury (for example, if a detailed examination is required or if autolysis or putrefaction is present) fixation of the whole brain is recommended before its dissection.
- **e** Middle ears must be always opened and nasal sinuses where indicated.
- **f** The soft tissue and skeleton of the face is dissected only in relevant cases, using a cosmetically acceptable technique.

2 *Thorax and neck*

The opening of the thorax must be performed using a technique which allows the demonstration of the presence of pneumothorax and the inspection of the thorax walls, including the postero-lateral regions. *In situ* dissection of the neck must display the details of its anatomy.

3 *Abdomen*

The opening procedure of the abdomen must allow an accurate examination of all layers of the walls, including the postero-lateral regions. *In situ* dissection is necessary in certain cases, particularly for the demonstration of injury tracks and evacuation of fluids. Dissection of organs should observe anatomical continuity of systems, where possible. The whole intestine must be dissected and its contents described.

4 *Skeleton*

- **a** The examination of the thoracic cage, the spine and the pelvis must be part of the autopsy procedure.
- **b** Where appropriate traumatic deaths need a precise dissection of the extremities, possibly complemented by X-ray examination.

5 *Special procedures*

- **a** If there is any suspicion of neck trauma, the brain and thoracic organs are to be removed prior to the dissection of the neck, to enable detailed dissection to take place in a bloodless field.
- **b** If there is a suspicion of air embolism, pre-autopsy radiology of the thorax must be performed. The first stage of the autopsy in such a case must be a careful partial opening of the thorax and dislocation of the lower three-quarters of the sternum with the subsequent opening of the heart under water, allowing the measurement and sampling of escaping air or gas.
- **c** For the demonstration of particular injury patterns, deviation from the normal procedure of dissection has to be accepted, provided that such procedures are specifically described in the autopsy report.
- **d** The dissection in traumatic deaths must include a full exposure of the soft tissues and musculature on the back of the body. The same procedure must be applied to the extremities (so called ‘peel-off’ procedure).
- **e** In suspected or overt sexual assaults, the sexual organs are to be removed *en bloc* together with the external genitalia, rectum and anus, before they are dissected. Relevant swabs of orifices and cavities must be taken prior to this procedure.

6 *Sampling*

The scope of the sampling procedure is to be case-dependent. However, the following minimum rules should be applied:

- **a** in all autopsies, the basic sampling scheme includes specimens from the main organs for histology and peripheral blood sampling (such as for alcohol and drug analyses and genetic identification), urine and gastric contents. All blood samples must be peripheral blood and not heart or thoracic;

- **b** if the cause of death cannot be established with the necessary degree of certainty, sampling includes additional specimens and fluids for metabolic studies and thorough toxicology. This includes blood, vitreous humour, CSF, bile, hair samples and further relevant tissues;
- **c** if death is related to physical violence, sampling includes the injuries, for example to determine wound age and any foreign materials in the wounds;
- **d** if reconstructions are desirable, the removal of bones and osseous compartments may become necessary;
- **e** if identification is the predominant aim, the removal of jaws and other bones may be necessary;
- **f** if strangulation or the application of physical force to the neck is suspected or diagnosed, the entire neck structures, musculature and neurovascular bundles must be preserved for histology. The hyoid bone and the laryngeal cartilages must be dissected very carefully;
- **g** biological samples must be collected in tightly closed jars, properly preserved and placed under seal and transported to the laboratory in perfect safety;
- **h** certain specimens and fluids need to be sampled in a special way and analysed without delay.

7 *Release of the body*
After a medico-legal autopsy has been carried out, medico-legal experts should ensure that the body is returned in a dignified condition.

Principle VI – Autopsy report

1 The autopsy report is as important as the autopsy itself, as the latter is of little value if the findings and opinions of the medico-legal expert are not communicated in a clear, accurate and permanent document. The autopsy report should be an integral part of the autopsy procedure and be drafted carefully.

2 The report should therefore be:

- **a** full, detailed, comprehensive and objective;
- **b** clear and comprehensible not only to other doctors, but also to non-medical readers;
- **c** written in a logical sequence, well-structured and easy to refer to in various sections of the report;
- **d** be in a legible and permanent form, with hard paper copy even if it is retained in electronic storage;
- **e** be written in a discursive 'essay' style;

3 When drafting an autopsy report, the following minimum content should be included:

- **a** legal preface to fulfil statutory requirements, if needed;
- **b** serial number, computer retrieval coding and International Classification of Disease Code (ICD) code;
- **c** full personal details of deceased (including name, age, sex, address and occupation) unless unidentified;
- **d** date, place and time of death, where known;
- **e** date, place and time of autopsy;
- **f** name, qualifications and status of medico-legal expert(s);
- **g** persons present at the autopsy and their function;
- **h** name of the authority commissioning the autopsy;
- **i** person(s) identifying the body to the medico-legal expert;
- **j** name and address of the medical attendant of the deceased;
- **k** a synopsis of the history and circumstances of the death, as given to the medico-legal expert by the police, judges, relatives or other persons, as well as information contained in the file, where available;
- **l** description of the scene of death, if attended by the medico-legal expert; reference should be made to the provisions contained in Principle I above;
- **m** external examination; reference should be made to the provisions of Principle V above;
- **n** internal examination by anatomic systems, together with a comment on every organ. Reference should be made to the provisions of Principle V above;
- **o** a list of all samples retained for toxicology, genetic identification, histology, microbiology and other investigations should be included; all such specimens should be identified and attested by the medico-legal expert according to the legal system of the state concerned, for continuity of evidence;
- **p** results of ancillary investigations, such as radiology, odontology, entomology and anthropology should be included, when such results are available;
- **q** one of the most important parts of the autopsy report is the evaluation of the significance of the accumulated results by the medico-legal expert. After termination of the autopsy, evaluation is usually provisional because later findings and

later knowledge of other circumstantial facts can necessitate alteration and modification. Medico-legal experts must interpret the overall findings so that the maximum information and opinion can be offered. Also questions that have not been raised by the competent authority must be addressed if they could be of significance;

r based on the final interpretation, the cause of death (in the International Classification of Disease should be given. Where several alternatives for the cause of death exist and the facts do not allow a differentiation between them, the medico-legal expert should describe the alternatives and, if possible, rank them in order of probability. If this is not possible, then the cause of death should be certified as 'Unascertained';

s the report should be finally checked, dated and signed by the medico-legal expert(s).

4 The date of the autopsy and the date of the provisional report should never be more than a day or two apart. The date of the autopsy and the date of the final report should be as close together as possible.

Appendix to recommendation No. R (99) 3

Specific procedures (selected examples)

1 *Constriction of neck (hanging, manual and ligature strangulation)*

The examination of the scene where the body was found is extremely important: for example the presence of a chair or similar platform; fastening of the strangulation device; technique of tying of the knot; adhesive taping of hands and objects for trace evidence:

- Strangulation marks: depth, width, intermediate rings, direction, suspension point, raised ridges of skin, zones of hyperaemia, presence of duplicate strangulation marks; further specific neck injuries: dried excoriations due to slippage of the implement, marks due to textile weave pattern and structure, distribution of petechiae in the skin, bruising, scratch marks, blisters in the strangulation mark.
- Bleeding from facial orifices. Differences in widths of the pupils, localization of hypostasis, presence and distribution of congestion.
- Injuries due to convulsions, defensive injuries, injuries due to being held forcibly.

Dissection of the soft tissues, of the musculature and of the organs of the neck in a bloodless field is essential.

2 *Drowning/Immersion*

Note carefully the following findings: foam at the mouth, cutis anserina, maceration, mud and algae, lesions due to water animals, injuries due to surroundings (for example rocks and ships), loss of nails, skin, localization of livor mortis.

Technique: sampling of gastric contents, precise description of the lungs (weight, measurement, extent of emphysema), sampling, lung fluid, liver and other tissues, for the possible demonstration of diatoms and other contaminants.

If required, sampling of drowning medium (for example river, bath water) should be carried out.

3 *Sexually motivated murder*

The inspection and documentation of the scene of crime, e.g. relative to the injury pattern, is especially important. All injuries must be photographed together with a scale. If required, the body surfaces must be investigated under UV light and taped. Search for and sampling of foreign biological material must include pubic hairs and secretions on the body surface as for instance originating from bites. Such material must be preserved carefully for DNA investigation and protected against contamination. 'En bloc' dissection of the genital organs is strongly recommended. It is also necessary to proceed to the careful removal and sampling of material under the fingernails and control hairs.

4 *Death from child abuse and neglect*

State of nutrition and general care, thorough description and documentation of external injuries and scars, thorough examination for bone fractures (X-ray), must be evaluated.

Consider the removal of a variety of tissues: for example all injuries, regional lymph nodes in malnutrition, endocrine organs, immuno-competent tissues, specimens from different parts of the intestine.

5 *Infanticide/still-birth*

Special techniques of dissection are necessary to expose the falx cerebri and the tentorium cerebelli; describe the site of caput succedaneum; remove all fractures 'en bloc'; investigate all bone centres of ossification (size and presence). Special care is to be applied to the thoracic organs: degree of inflation of the lungs, flotation test 'en bloc' and 'en detail'. However, the limitations of the flotation test must be appreciated. All malformations must be described. As regards abdominal organs, gas content of the intestine must be investigated. The umbilical cord and the placenta must be subject to morphological and histological examination.

6 *Sudden death*

A subdivision into three main categories relative to the further strategy after gross examination is useful:

- **a** findings that obviously explain the sudden occurrence of death (for example haemopericardium, aortic rupture). Cases belonging to this category can usually be regarded as sufficiently solved;
- **b** findings that could explain the death but allow other explanations. Cases belonging to this category necessitate the exclusion of, for example,. poisoning and possibly histological proof of recent or chronic alterations relative to the cause of death;
- **c** findings are either nil/minimal or do not explain the occurrence of death. Cases belonging to this category will usually require extensive further investigations.

This is especially so with sudden infant death cases. In such cases a more comprehensive investigative scheme is essential.

7 *Shooting fatalities*

The following should be carried out:

- – extensive account on the scene of the incident, of weapons involved, of types of bullets, of sites of 'environmental' damage, of cartridge cases and of relative positions of persons involved;
- – thorough examination of the clothing and description of relevant damage and careful sampling;
- – thorough investigation and documentation of any blood (splashes) on the body surfaces (including clothing and hands);
- – precise description of bullet entry and exit wounds relative to anatomical landmarks and distances from the soles of the feet and bullet tracks within the body;
- – description of any impression marks of the muzzle;
- – excision of uncleaned skin specimens surrounding entry and exit wounds;
- – X-ray before and/or during autopsy (where necessary);
- – determination of bullet tracks and their direction(s);
- – final determination of direction(s) of fire, of the succession of shots, of intra-vital occurrence, of the victim's position (s).

8 *Death caused by explosive devices*

- **a** As well as evaluating the cause of death, autopsy is essential to assist in reconstructing the nature of the explosion and identifying the type and maker of the explosive device, especially in aircraft sabotage or other terrorist actions.
- **b** Full X-ray of the body must be made to detect and localise any metallic objects, such as detonator components, which may lead to the identification of the explosive device.
- **c** The pattern of injury may indicate that the dead person was a perpetrator of the explosion, for example maximum injury in the lower abdominal region suggests that he or she carried the device on his or her lap during a premature explosion.
- **d** At autopsy, all foreign objects in the tissues, identified on X-rays, must be carefully preserved for forensic examination.
- **e** Samples of tissues, clothing, etc., must be retained for chemical analysis to identify the type of explosive.

9 *Blunt and/or sharp force injuries*

The following should be carried out:

- – examination of the weapons or objects that are possibly involved (especially their dimensions);
- – extensive examination and inspection of clothing (including damage, stains);
- – careful dissection and description of all tracks (layer by layer) including their dimensions and weapon-related traces, signs of vitality.

10 *Fire Deaths*

The following should be carried out:

- – examination of remains of clothing, – specific types and shapes of skin combustions;
- – search for heat-related alterations and peculiarities;
- – demonstration/exclusion of fire accelerants.;
- – search for signs of vitality: carbon monoxide, HCN, soot inhalation, skin lesions.

11 *Suspicion of intoxication (General Outlines)*

11.1 Where anatomical findings do not reveal a cause of death and/or there is vague suspicion of poisoning, basic sampling should include peripheral blood, urine, stomach contents, bile, liver and kidney.

11.2 If specific suspicion arises, sampling should be group-related as follows:

- – hypnotics, sedatives, psycho-active drugs, cardiac drugs and analgesics, pesticides: as aforementioned under (11.1);
- – drugs of abuse: as aforementioned under (11.1) and additionally cerebrospinal fluid, brain tissue, injection marks, hairs;
- – volatile fat-soluble substances such as fire accelerant and solvents: as aforementioned under (11.1) and in addition: blood from left

ventricle, brain tissue, subcutaneous fat tissue, lung tissue, clothing;

- nutritional intoxication: as aforementioned under (11.1) and in addition: intestinal contents, if possible taken from 3 different sites;
- suspicion of chronic intoxication (heavy metals, drugs, pesticides etc.) as aforementioned under (11.1) and in addition: hairs (tufts), bones, fat tissue, intestinal contents.

12 *Decomposed bodies*

The presence of decomposition does not remove the need for a full autopsy.

Radiological examination will exclude bony injury, the presence of foreign bodies, for example bullets.

Toxicological studies (particularly estimation of alcohol concentrations) should be carried out but interpreted with great caution.

This page intentionally left blank

FORENSICS

KNIGHT'S Fourth Edition
Forensic Pathology

The fourth edition of **Knight's Forensic Pathology** continues to be the definitive international resource for those in training and in practice, covering all aspects of the medico-legal autopsy, including the cause and time of death, interpretation of wounds and every other facet of the investigation of a fatality.

The contents are intended to lead the pathologist – and in some countries, the non-pathologist – through the procedures needed in the examination of a body found under obscure, suspicious or even criminal circumstances.

Although police procedures and the habits of pathologists may vary from country to country, the philosophy and techniques presented in this book offer a guide to good practices that can be modified according to local circumstances.

In this new edition the text has been thoroughly updated and is complemented by the addition of over 200 new colour illustrations. It maintains the praised tradition of clarity and readability established since Prof. Bernard Knight's first edition was published in 1991, with an emphasis on the practical application of knowledge and research findings and the avoidance of over-interpretation.

WITH VITALSOURCE® EBOOK

- download the ebook to your computer or access it anywhere with an internet browser
- search the full text and add your own notes and highlights
- link through from references to PubMed

K18576
ISBN: 978-0-340-97253-3
90000
9 780340 972533
www.crcpress.com

CRC Press
Taylor & Francis Group
an informa business
www.crcpress.com

6000 Broken Sound Parkway, NW
Suite 300, Boca Raton, FL 33487
711 Third Avenue
New York, NY 10017
2 Park Square, Milton Park
Abingdon, Oxon OX14 4RN, UK

Death Investigation

Death Investigation

An Introduction to Forensic Pathology for the Nonscientist

Ann Bucholtz

ELSEVIER

AMSTERDAM • BOSTON • HEIDELBERG • LONDON
NEW YORK • OXFORD • PARIS • SAN DIEGO
SAN FRANCISCO • SINGAPORE • SYDNEY • TOKYO
Anderson Publishing is an imprint of Elsevier

Acquiring Editor: Sara Scott
Editorial Project Manager: Marisa LaFleur
Project Manager: Punithavathy Govindaradjane
Designer: Russell Purdy

Anderson Publishing is an imprint of Elsevier
225 Wyman Street, Waltham, MA 02451, USA

Copyright © 2015 Elsevier Inc. All rights reserved.

No part of this publication may be reproduced or transmitted in any form or by any means, electronic or mechanical, including photocopying, recording, or any information storage and retrieval system, without permission in writing from the publisher. Details on how to seek permission, further information about the Publisher's permissions policies and our arrangements with organizations such as the Copyright Clearance Center and the Copyright Licensing Agency, can be found at our website: www.elsevier.com/permissions.

This book and the individual contributions contained in it are protected under copyright by the Publisher (other than as may be noted herein).

Notices
Knowledge and best practice in this field are constantly changing. As new research and experience broaden our understanding, changes in research methods or professional practices, may become necessary. Practitioners and researchers must always rely on their own experience and knowledge in evaluating and using any information or methods described herein. In using such information or methods they should be mindful of their own safety and the safety of others, including parties for whom they have a professional responsibility.

To the fullest extent of the law, neither the Publisher nor the authors, contributors, or editors, assume any liability for any injury and/or damage to persons or property as a matter of products liability, negligence or otherwise, or from any use or operation of any methods, products, instructions, or ideas contained in the material herein.

Library of Congress Cataloging-in-Publication Data

Bucholtz, Ann.
Death investigation / Ann Bucholtz.
pages cm
ISBN 978-1-4557-7437-1
1. Dead–Identification. 2. Forensic pathology. I. Title.
RA1055.B83 2014
614'.1–dc23
2013038466

British Library Cataloguing in Publication Data
A catalogue record for this book is available from the British Library

ISBN: 978-1-4557-7437-1

For information on all Anderson publications visit our website at
http://store.elsevier.com

Printed and bound in the United States of America

14 15 16 17 18 10 9 8 7 6 5 4 3 2 1

ELSEVIER
Book Aid International
Working together
to grow libraries in
developing countries
www.elsevier.com • www.bookaid.org

Dedication

To my son, Lucas Hartsough, a source of constant encouragement and inspiration. To my editor, Sherrie Saint, for her friendship and patience. Thank you to my family and colleagues for their contributions of photos and data.

Digital Assets

Thank you for selecting Anderson's *Death Investigation*. To complement the learning experience, we have provided a number of online tools to accompany this edition. Two distinct packages of interactive digital assets are available: one for instructors and one for students.

Please consult your local sales representative with any additional questions.

FOR THE INSTRUCTOR

Qualified adopters and instructors need to register at the this link for access: **http://textbooks.elsevier.com/web/manuals.aspx?isbn=9781455774371**

- **Test Bank** Compose, customize, and deliver exams using an online assessment package in a free Windows-based authoring tool that makes it easy to build tests using the unique multiple choice and true or false questions created for *Death Investigation*. What's more, this authoring tool allows you to export customized exams directly to Blackboard, WebCT, eCollege, Angel and other leading systems. All test bank files are also conveniently offered in Word format.
- **PowerPoint Lecture Slides** Reinforce key topics with focused PowerPoints, which provide a perfect visual outline with which to augment your lecture. Each individual book chapter has its own dedicated slideshow.
- **Instructor's Guides** Design your course around customized learning objectives, discussion questions, and other instructor tools.

FOR THE STUDENT

Students will need to visit this link in order to access the ancillaries below. http://www.elsevierdirect.com/companion.jsp?ISBN=9781455774371

- **Self-Assessment Question Bank** Enhance review and study sessions with the help of this online self-quizzing asset. Each question is presented in an interactive format that allows for immediate feedback.
- **Case Studies** Apply what is on the page to the world beyond with the help of topic-specific case studies, each designed to turn theory into practice and followed by interactive scenario-based questions that allow for immediate feedback.

CHAPTER 1

History of Death Investigation

Learning Objectives

- Differentiate the roles of a forensic pathologist versus a hospital pathologist in the performance of autopsies.
- Compare and contrast the coroner system versus a medical examiner system.
- Identify and review the death investigation system in your state. Demonstrate knowledge of the state laws for reportable deaths in your jurisdiction.
- Compare the list of reportable deaths in the Model Post-Mortem Act to the laws in your state. Discuss the additions and deletions and the impact you think they might have for death investigations.
- Discuss the works of Washing Away of Wrongs and what impact it had on the beginnings of death investigation.
- Describe the benefits and drawbacks to professional certification in an area of expertise, such as forensic pathology, forensic nursing, death investigator, or criminalist.

Key Terms

Locard's exchange principle
Center for Disease Control
Alphonse Bertillon
Model Postmortem Act
Coroner
Medical examiner
Forensic pathologist
Hospital pathologist

Chapter Summary

In this chapter we discuss some of the historical origins of forensic medicine, criminalistics, and the coroner system. Also discussed are the multiple supporting organizations that provide credentialing, networking, and continuing education opportunities. The basis of laws regarding death investigation in the United States are examined, which are centered on the 1954 Model Postmortem Act in which suspicious, unusual, or unnatural deaths are investigated to provide information for prosecution, accurate determination of death, and protection of the public against health hazards.

INTRODUCTION

Forensics, derived from the word "forum," refers to the application of various fields of science and medicine in the resolution of legal proceedings. The beginnings of forensic science were crude and rudimentary but formed the basis of areas of research and progress to modern-day use of lasers, sophisticated laboratory equipment to identify particles and drug identification, and computerization to improve response time to locate the answers to questions asked by investigators, some in near real time. This chapter reviews the historical beginnings of forensic medicine and its parallel in criminalistics, contrasts the **coroner** and **medical examiner** investigation systems, as well as provides insight into governing bodies for accreditation, certification, and licensure.

MANDATES, JURISDICTION, AND LAWS

Forensic science has its origins in early China and was documented in an early transcript of text, *Washing Away of Wrongs* by Sung Tz'u written in 1248. He was a criminal affairs officer who wrote the book based on personal experiences. Within the text he described a scenario of a local village murder by a sickle used to harvest grain. The murderer was unknown and the investigator had each farmer bring their tools to the village to be examined. It was noted that flies were attracted to one particular sickle. This was apparently due to adherent tissue and blood on the tool and ended with the farmer admitting to the crime. The story has roots for the basis of forensic entomology with its observation of the relevance of insects and their relationship to the cycle of death. He described handling of male corpses by local men of low social standing and the female corpses were managed by local midwives.

The early Greeks performed anatomical dissections in an attempt to understand the workings of the body and organ relationships. However, it wasn't until the late 18th century when a book written by Giovanni Morgagni that described autopsy dissections with descriptions of disease processes that they gained acceptance in the West. This served as a framework in the late 19th century for Dr. William Osler, the acclaimed physician and educator, supporting the autopsy as a great teaching method for physicians to learn about their patient's disease and to see for oneself the disease process. His work and influence served as the basis for medical training that still is in existence today. The period after World War II showed extensive interest in autopsies, and most were done in the hospital setting to gain knowledge about the effectiveness of new treatments, as well as learn about the disease itself. Hospital autopsies were done for approximately 50% of deaths.

In 1954 the United States passed the **Model PostMortem** Act, which outlined general classes of deaths that need to be further investigated and certified by a government body rather than a **hospital pathologist** or treating physician (Figure 1.1). This act was used as a framework for each state to develop its own particular laws regarding death investigation. The act outlines reporting of all violent deaths; unusual, unnatural, or suspicious deaths; all prison deaths; and any death thought to represent a public health hazard. Over the years, each state has modified their laws to adapt to advances in the medicolegal system, but for the most part they read as they were originally written and reflect these guidelines.

Today, it is estimated that hospital autopsies are done in less than 10% of hospital deaths. The decline is related to multiple influences, including the deleted



1954 Model Postmortem Examinations Act

Section 4. [Deaths To Be Investigated.] The Office of Post-Mortem Examinations shall investigate all human deaths of the types listed herewith:
(a) Violent deaths, whether apparently homicidal, suicidal, or accidental, including but not limited to deaths due to thermal, chemical, electrical or radiational injury, and deaths due to criminal abortion, whether apparently self-induced or not;
(b) Sudden deaths not caused by readily recognizable disease;
(c) Deaths under suspicious circumstances;
(d) Deaths of persons whose bodies are to be cremated, dissected, buried at sea, or otherwise disposed of so as to be thereafter unavailable for examination;
(e) Deaths of inmates of public institutions not hospitalized therein for organic disease;
(f) Deaths related to disease resulting from employment or to accident while employed;
(g) Deaths related to disease which might constitute a threat to public health.

Outlined purpose by the Commissioners:
The purpose of the Model Post-Mortem Examinations Act is to provide a means whereby greater competence can be assured in determining causes of death where criminal liability may be involved.

Drafted by the
NATIONAL CONFERENCE OF COMMISSIONERS ON UNIFORM STATE LAWS, 1954
http://babel.hathitrust.org/cgi/pt?id=mdp.39015082088835;view=1up;seq=3

FIGURE 1.1
The 1954 Model Post-Mortem outlined the recommended state mandated reporting of cases to a central investigative agency for adoption of individual state laws.

requirement by the Joint Commission of American Hospitals (their accrediting body) for a minimum autopsy rate and reimbursement to the hospital for this service, as well as improved radiologic methods for patient evaluation [4]. The interesting finding, however, is autopsies discover 22–33% findings that were not previously known even with the current technology [4]. They provide answers to families and further understanding to medical science, but unfortunately continue to decline in the hospital community.

Caseloads for medical examiners and coroner offices continue to increase as the population increases. With shortages of **forensic pathologists** and limited tax-based funds, death investigation offices must limit autopsies performed to those mandated by law. This creates a void for hospitals and families wishing for answers. Hospital pathologists rarely perform them, and in modern hospitals, morgues are no longer included as an essential area of the laboratory department. Those autopsies not falling under jurisdiction of the state's death investigation laws require signed family permission to proceed. State laws even outline the family members who may give this permission, usually following the order of spouse, adult children, parents of the deceased, adult siblings, a legal guardian, and then the individual charged with the disposition of the remains.

In the situation of religious objections and deaths falling under the jurisdiction of the death investigator, an autopsy may proceed without family permission. However, it is best for public relations to work with the family and try to abide by their wishes or perform the autopsy within their religious constraints if at all possible. This may require a rabbi to be present during the procedure, collection of all body fluids to return with the body, or particular religious practices to be performed before or after the procedure. Muslim and Jewish religions request burials prior to sundown of the day of death if at all possible. Some religions forbid embalming. Some families request no autopsy because they wish to have an open casket and viewing of the decedent. With education about the procedure, they can be reassured that the incisions will be done in locations that will not preclude viewing, embalming, and open-casket funerals if the body was not damaged extensively by trauma prior to the autopsy. Objections can be overcome with meaningful conversations between the family and the death investigator or pathologist.

There is no universal body governing the death investigation system at a national level, and each state performs death investigations differently from its neighboring state. Many deaths reported to a death investigation office involve sudden death due to unknown mechanism. They represent natural diseases not previously or well documented prior to death, or the treating physician may be unavailable to sign for a patient with a well-documented history. Generally, there is a time limit in which a death certificate needs to be filed with a local health department after death. For this reason, the medical examiner serves as a resource to fill these gaps. The pathologist can issue meaningful causes of death based on medical records and external examination of the body without the need for an internal examination and full autopsy.

The local health department is the governing body that filters all death certificates to the National Bureau of Vital Statistics. They review and numerically code the causes of death into categories so that trends in causes may be recognized to adjust surveillance, prevention, and treatment practices. The local health department also issues burial or cremation permits to funeral homes after a valid death certificate is filed. They supply copies of death certificates, which are usually public record and can be obtained by anyone. The 1992 Model State Vital Statistics Act and Regulations serves as a template for each state to model their vital records practices and can serve as a reference to answer unusual questions when completing a death certificate [12].

The coroner system has been in existence since organized colonization began in 1492 when the concept was imported with the settlers from England. The first medical examiner office was established in New York City in 1918, and it was the first government division of its kind in the United States [5]. They were also responsible for the first toxicology laboratory in 1918 [5]. The first chief medical examiner in the New York office was Dr. Charles Norris. This was followed by New York University establishing the first department of forensic medicine in 1933.

The **Center for Disease Control** maintains a list of the medical examiner and coroner jurisdictions within the United States, shown in Figure 1.2 [2].


MEDICAL EXAMINER AND CORONER JURISDICTIONS IN THE UNITED STATES - 2002
DC
State ME, no coroners
District ME, no coroners
County ME, no coroners
State ME, mixed county ME and Coroners
State ME, coroners in every county or district
Mixed ME and Coroners
Coroners in every county or district
CDC

FIGURE 1.2
This map illustrates the various combinations of coroner and medical examiner system jurisdictions within the United States.
Source: Published by the Center for Disease Control.

HISTORY OF CRIMINALISTICS

Parallel to the development of forensic medicine and autopsies, the world of criminalistics was also developing and spurring forward the science of evaluating evidence and tracking criminals. **Alphonse Bertillon** was a French law enforcement officer in the late 19th century who performed research in anthropometry, which is a study of physical characteristics of a person that make him or her unique. His study involved recording measurements of various body regions, such as forearms, trunks, ears, fingers, and faces, to differentiate one person from another (Figure 1.3). This had applications for differentiating criminals from each other, because the usual method had been for station police officers at the entrance to the jail to make visual identifications, which were sometimes inaccurate. The main purpose was to separate repeat-offender prisoners from first offenders. At the time, it was a huge scientific advancement and was thought to be reliable until the early 20th century when it failed to differentiate a case of twins. Although these particular measurements were eventually found to be unreliable, they formed the basis for the science of biometrics that utilizes a similar idea of individualizing characteristics but includes more detailed,


Lèvres
Hauteur naso-labiale
Proéminence
Bordure
Épaisseur
Défaut d'adhérence
Particularités
- Bouche -
Dimension
Particularités
Particularités
Synthétiquement
Dentition
Menton
Inclinaison
Hauteur
« Largeur »
Particularités
Particularités
Contour général de la tête
vue de profil
Profil fronto-nasal
Profil naso-buccal
Synthétiq!
Hauteur cranienne
Particularités craniennes
Contour général de la tête
vue de face
1° Synthétiquement
2° Analytiquement
État graisseux

A

FIGURE 1.3
(A) Various physical characteristics used by Alphonse Bertillon in his research on anthropometry.



FIGURE 1.3, cont'd
(B) An example of the type of measurements he performed to characterize individuals. It shows a striking similarity to our current method of figuring stature from femur bone lengths.
Source: http://www.nlm.nih.gov.

patterned relationships, such as iris scans, fingerprints, and facial-recognition software used in security programs.

Another notable hallmark in criminalistics was the work of Edmond Locard in the early 20th century. He too was a Frenchman but with a background in medicine and law. He became interested in forensics during his studies and eventually formed the first criminalistics laboratory in Lyon, France, in 1910. He is best known for **Locard's exchange principle**, which states that whenever two items come into contact they exchange material between them. This is the principle used to recover evidence and particular trace evidence on the body or other items in a crime scene and link it to the individual who left it. The importance of this principle is that no scene is without trace evidence; it is the job of the investigator to locate it and collect it. Locard was also extremely interested in fingerprints, and through his work in microscopy, he detailed characteristics of them that are used today in fingerprint identification. He is generally considered the first criminalist.

In 1923, August Vollmer, chief of the Los Angeles, CA, Police Department, established the first American crime laboratory. The second crime laboratory was established in 1929 by Calvin Goddard (well known for his work in ballistics) at Northwestern University in Chicago, IL.

Coroners

Coroners are elected officials and in most jurisdictions the only credentials required for being placed on the ballot are a high school diploma and a voter registration card. Medical, science, or law enforcement background is not required. In some jurisdictions, the position has been combined with the sheriff position to decrease administrative overheads. In this case, sworn law enforcement deputies may rotate through the positions of death investigator and not be specifically trained in death-scene evaluations. There can be a public question of conflict of interest when investigations cross into departmental operations. Other jurisdictions utilize a separate department with a chief coroner and deputy coroners. Coroner positions may also be linked to local funeral homes as experienced personnel in dealing with the dead.

The history of the word “coroner” originates in England from the word “crowner,” a tax collector for the dead. In old England, coroners were given the task of investigating any local event that might result in revenue for the Crown. Death was a potential source of money, and suicides, fires, shipwrecks, and others all were levied taxes or goods were confiscated by the Crown as fines. After the conquest of the Normans, the countryside continued to kill Normans. To discourage this, a heavy fine was levied against a community in which a Norman was found dead. It became the job of the coroner to determine the origin of the dead person, and they largely assumed the person was a Norman and levied the tax unless someone could prove the decedent was English. This tax levy was known as “murdrum'” and became the origin of the word “murder” [1]. The concept of coroners and sheriffs was brought to the United States with the colonists when it was initially settled. It spread throughout the United States as colonies developed and the need for investigation and management of the dead became a necessity.

The United States varies from state to state in a mixture of medical examiner and coroner jurisdictions and combinations thereof [2]. Because coroners are not physicians, they are unable to perform autopsies. This is contracted to forensic pathologists who supply a cause of death to the coroner. The coroner then has the legal ability to certify the cause and manner of death on the death certificate. Most times, the coroner will agree with the cause of death, but if not, he or she may place any cause on the certificate or rule the manner as he or she wishes. Being a political position can have some bearing on this decision and is a potential downfall of the coroner system. Most times the job is performed justly and accurately in conjunction with the science of the autopsy in mind. In some jurisdictions, mainly ones where the position is combined with the sheriff department, the coroner is also a law enforcement officer with the ability to carry a weapon. Strict coroner office personnel are generally unarmed.

The chief coroner serves as an administrator and leader of the office for death investigations. Most times, he or she hires additional lay persons, many with a medical or law enforcement background, as deputy coroners who are responsible for day-to-day investigations. Because these positions are based on the county divisions of a community, a coroner's office can be a small operation. The deputy coroner may have a varied job description, including crime scene investigation, preparation of death certificates, body transport, and autopsy assistance.

Medical examiners

Medical examiners are forensic pathologists with education as a medical doctor (either an M.D. or D.O.), completion of at least 4 years of anatomic pathology (5 years if also trained as a clinical pathologist), and at least 1–2 years of subspecialty training in forensic medicine. In total, approximately 13–15 years of training after high school is needed to become a forensic pathologist.

Medical school includes the study of basic medical science, including pharmacology, pathology, biochemistry, human physiology, and anatomy, as well as patient care and skills necessary for the practice of medicine. Following medical school, medical students enter a residency program where they specialize in an area of interest. The residency begins with a general year that previously was known and perceived by the public as an internship with continued responsibility and in-depth learning of the specialty over at least 3 years (family medicine, internal medicine) to surgery and pathology (5 years). Because the study of medicine has become so complicated, large branches of medicine have subspecialized into even smaller groups, such as cardiology (internal medicine), head and neck (surgery), and forensic medicine (pathology).

There are a couple of clinical forensic medicine programs in the United States that are areas of subspecialization within emergency medicine but these are not common. Currently in the United States, there are approximately 500–600 board-certified forensic pathologists and 30–40 in training each year [3]. Unfortunately, the number training is less than the greater number of pathologists who are retiring, and there is a projected severe shortage as the number of pathologists continues to age and retire. Even though the number of hospital pathologists performing autopsies has greatly declined, the number of medicolegal autopsies continues to increase as the population increases.

A medical examiner office is typically under the direction of a chief medical examiner who reports to a board of supervisors, state legislature, or the department head of the public health department. Under the chief may be an additional forensic pathologist. Current recommendations are the performance of

250 autopsies per year and no more than 350 per year per forensic pathologist. In large population cities, more than 7,000 deaths are reported to a medical examiner office with at least 4,000–4,500 cases accepted for jurisdiction. Not all cases accepted are necessarily autopsied and may be certified by history or external examination. The autopsy rate is generally at least 60% and more commonly greater than 70–75% depending on staffing and workload. At 4,000 cases, more than 10 pathologists are needed to comply with the accreditation standards. It is clear that even by present-day availability there is a shortage of forensic pathologists and current training will be inadequate to meet future society's needs.

Notable forensic pathologists

Milton Helpern was the second chief medical examiner of the New York City medical examiner office. His support of research and teaching led to many forensic pathologists to later become chief forensic pathologists in other locations, spreading the concept of forensic medicine throughout the United States.

Dr. Thomas Noguchi is a modern-day pathologist who is best known as the "coroner of the stars" and formed the basis of the TV show "Quincy." This notoriety and positive portrayal of death investigations improved the public's perception of the science of forensic medicine. Present-day TV shows similarly dramatize the work of crime scene investigators (CSIs), criminalistics, autopsies, and courtrooms. These shows are not totally realistic but have raised an awareness of the science to most households. The negative side is the "CSI effect," in which juries expect similar results on cases presented to them even though the real forensic science does not support many of the concepts dramatized nor operate under the same time and money constraints as TV laboratories.

Medicolegal death investigators

Medicolegal death investigators serve as observation personnel and key assistants to the forensic pathologist at scenes. It is not possible for the forensic pathologist to visit all scenes and observe the body as it was found. It would be ideal, but just not possible. Death investigators are trained personnel with skills in observation, photography, and social skills to deal with the public during difficult situations. Their backgrounds are diverse and a cross-section of skills is helpful in any office. Some investigators have a funeral home background as funeral directors, others are emergency medical personnel, nurses, retired law enforcement officers, or physician assistants.

The ability to speak to physicians and understand medical terminology is an essential skill. Rudimentary photography skills are also very useful, as well as basics in evidence recovery and management. The ability to explain medical findings to families in lay language and serve as an intermediary between the pathologist and family is essential. Report writing skills, including grammar, are also necessary. Formal education can vary from a high school education to graduate school. Most offices now will not hire an investigator without a college degree. They are also not eligible for board certification via the American Board of Medicolegal Death Investigators (ABMDI) without at least an associate's degree. The ability to become a good death investigator resides more on the personality of the person than a particular degree or level of education. Many of the skills are learned on the job or through various continuing-education and certification courses. They generally work on a shift basis and are available to receive death calls 24 hours a day. In some offices, the death investigator also serves as a body transport team. In others, removals from the scene are contracted to local removal services or funeral homes. Typically, medicolegal death investigators are unarmed and do not serve as law enforcement officers unless they are part of a sheriff–coroner system.

PROFESSIONAL AND CERTIFYING AGENCIES IN THE UNITED STATES

American Board of Pathology

The American Board of Pathology [6] is the body that certifies a pathologist in general anatomic and clinical pathology and its various subspecialties including forensics. Other subspecialties include surgical pathology, cytology, hematopathology, pediatric and neuropathology, among others. There are rules about the prequalifications necessary to apply for certification, including successful completion of a residency in pathology, a valid medical license, a minimum number of 50 autopsies performed, and exposure to subspecialties to ensure general competence in general diagnoses. It includes a substantial application fee and attendance at a testing station in Florida where the exams are given in computerized format.

Anatomic examination includes a written, image recognition, and microscopic examination done over one and a half days. Clinical pathology has a similar three-part exam over an additional one and a half days. To qualify for forensic pathology certification, anatomic pathology certification must be attained. Clinical pathology is not necessary to qualify for forensic pathology certification, but it may be necessary to run a lab and is useful when evaluating toxicology and microbiology results. The forensic pathology exam is a written exam in addition to a combined image exam that includes microscopic exams; it is completed in one day. Most jobs for forensic pathologists require board certification within a certain period of the hire date or may require it prior to being hired. Board certification is desired for court testimony and is used to establish a basis for basic level of competence in the field. The exams are difficult and are usually offered once or twice per year, which can lead to difficulties in one's career if they are not passed successfully.

Some pathologists perform forensic exams and are not board certified but may be prohibited from performing homicides, child deaths, or complicated autopsies because of it. Forensic exams are also sometimes performed by general hospital pathologists with no additional training in rural areas.

Since 2006, the American Board of Pathology has instituted a mandated continuing-education program called MOC (Maintenance of Certification) that requires recertification in each area every 10 years by demonstration of approved ongoing continuing education. Those certified prior to that have grandfathered certificates not needing this requirement.

Forensic pathology has been recognized by the American Board of Pathology as a subspecialty since 1959. The board has a request form available for confirmation on the board certification status of each member who has applied for certification, which can be confirmed by a form and fee for those doing background checks on pathologist applicants.

American Board of Medicolegal Death Investigators

The American Board of Medicolegal Death Investigators (ABMDI) [7] was established in 2005 as an organization to ensure basic skills and knowledge as a death investigator. There are two levels of certification: an entry level that requires on-the-job experience and completion of a written exam and skill checklist, and an advanced level, which requires a minimum of an associate's degree and more extensive work experience, as well as completion of the basic level of certification. The examination and principles of the certification were established by seasoned death investigators who contributed extensively to the NIJ publication of *Death Investigation: A Guide for the Scene Investigator*, as well as a training manual with the same title. The certification process allows members to state their credentials in court with a basis for national standards as a background.

National Association of Medical Examiners

The National Association of Medical Examiners (NAME) [8] is a national professional organization that was established in 1966. It encompasses not only physician medical examiners as members, but also includes an affiliate membership of medicolegal death investigators and administrators who support and supply knowledge to the process of quality death investigations in the United States. Members can participate in an annual continuing-education meeting for maintenance of licensure and board certification for both medical examiners and death investigators. It operates via presentation of numerous scientific papers of current events and studies important to furthering forensic science and death investigations. They also sponsor a voluntary accreditation program in which an office is evaluated regarding policies, procedures, and performance of quality death investigations as outlined by a multilevel checklist and evaluated by a visiting forensic pathologist. Successful completion allows certification for five years.

In addition to the peer-reviewed accreditation process, NAME is actively supporting periodic routine quality assurance reviews of autopsy reports and findings as a means to ensure basic evaluation of quality documents supplied to the public and judicial system.

American Academy of Forensic Sciences

American Academy of Forensic Sciences (AAFS) [9] is a large diverse organization representing the various aspects of forensic science applications and the law. It was established in 1948 and includes all divisions of criminalistics, anthropology, dentists, attorneys, forensic pathologists, physicists, engineers, and others interested in furthering the science and practices. It sponsors a yearly educational meeting with the presentation of 700–800 scholarly papers to peers in the various specialties. Because of the large diverse membership, it allows sharing of research and ideas across specialties and decreases barriers to advancing research. Membership requirements include recommendations from current members, as well as completion of qualifications established by each subsection of the organization.

American College of Forensic Examiners Institute

The American College of Forensic Examiners Institute (ACFEI) [10] is a relatively new organization and is composed of a diverse group of specialists within forensic investigations. They support a credentialing process through an online course and issue a certificate of completion for criminal investigators, forensic nurses, forensic social workers, and forensic accountants. They support a yearly summit meeting for the presentation of papers by various backgrounds within these forensics specialists.

International Association of Coroners and Medical Examiners

The International Association of Coroners and Medical Examiners (IACME) [11] is an international body that encompasses both coroners and forensic pathologists to foster communication and further quality death investigations to aid the public and law enforcement. The group supports the development of state coroners associations, which offer continuing-education classes, as well as an opportunity to standardize practices throughout the state across jurisdictional lines. The international group also offers a yearly continuing-education meeting and an office accreditation process that if satisfactorily completed is valid for five years.

PHYSICIAN LICENSURE

Physicians undergo a general licensure examination process called the United States Medical License Exam (USMLE). It is given in three steps with the first two completed in medical school and the third in the first or second year of residency. Upon successful completion, an unrestricted medical license is issued in the state of the residency rather than the state where medical school was completed. After the initial licensure, other states generally recognize the presence of a license and will issue their license to an applicant in good standing if he or she meets all the qualifications. Each state will have various pass scores required on the USMLE, and letters of good standing from each state the applicant has a current medical license with, which means no malpractice claims, problems with hospital credentials, felonies or arrests, etc. Application for licensure in another state also requires submission of transcripts from college, medical school, and letters of recommendation, and is quite paper-intensive. To aid some of this, the Federation of State Medical Boards has an affiliated agency called Federal Credentialing Verification Service (FCVS) where all these documents may be submitted for verification from their source as a one-time submission. Any further requests from these documents can be supplied from FCVS at a much faster turnaround, and the recipients of the documents can be assured they are true copies of originals. This service also includes an online application process for some state licensure applications and can be used as part of background checks for job applications and credentialing for hospital privileges.

REFERENCES

[1] History. The Coroners' Society of England & Wales. Retrieved from http://www.coronersociety.org.uk/history. [July 2013].

[2] Hickman M, et al. Medical Examiner and Coroners' Offices, 2004. US Dept of Justice, NCJ 216756. Retrieved from http://www.bjs.gov/content/pub/pdf/meco04.pdf. [July 2013].

[3] Hanzlick R, et al. Selecting Forensic Pathology as a Career: A Survey of the Past with an Eye on the Future. Am J Forensic Med Pathol 2008;29(2):114–22. Retrieved from PubMed.gov, http://www.ncbi.nlm.nih.gov/pubmed/18520476. [July 2013].

[4] Rosenbaum G, et al. Autopsy Consent Practice at US Teaching Hospitals: Results of a National Survey. Arch Intern Med 2000;160(3):374–80. Retrieved from http://archinte.jamanetwork.com/article.aspx?articleid=485226. [July 2013].

[5] History of the Office of Chief Medical Examiner. New York City Office of the Chief Medical Examiner; 2013. Retrieved from http://www.nyc.gov/html/ocme/html/about/about.shtml. [July 2013].

[6] Examination Information. The American Board of Pathology; 2013. Retrieved from http://www.abpath.org/. [July 2013].

[7] American Board of Medicolegal Death Investigators. Retrieved from http://abmdi.org/. [August 2013].

[8] National Association of Medical Examiners. Retrieved from https://netforum.avectra.com/eweb/DynamicPage.aspx?WebCode=LoginRequired&Site=NAME. [August 2013].

[9] American Academy of Forensic Sciences. Retrieved from http://aafs.org. [August 2013].

[10] American College of Forensic Examiners Institute. Retrieved from http://www.acfei.com/. [August 2013].

[11] International Association of Coroners and Medical Examiners. Retrieved from http://www.theiacme.com/home2.html. [August 2013].

[12] Taylor P (chairperson). Model State Vital Statiscs act and Regulations; 1992. US Dept of Health and Human Services. Retrieved from www.cdc.gov/nchs/data/misc/mvsact92b.pdf. [October 2013].

CHAPTER 2

Death Scene Investigation

Learning Objectives

- Apply what you know about making death notification to family members from the point of them answering the door to answering common questions they may ask you. Write out your responses and practice them with a colleague or classmate.
- Outline three ways to ensure quality death investigation and standardize your individual practices.
- Propose two methods of peer review that might be useful for death investigator practices.
- Prepare a simple reminder checklist for overall scene investigation to review prior to leaving a scene and arriving at the office.

Key Terms

Quality assurance
Peer review
Chain of custody
Next of kin
Notification

Chapter Summary

This chapter deals with how the death scene investigator approaches the problem of retrieval of the decedent while properly handling the family and the preservation of evidence on and around the body. A scene is a three-dimensional area that needs to be evaluated to assist in the collection of evidence and properly documenting the scene using photographs. This allows a snapshot view for the pathologist and other investigators to later review so the proper conclusions can be reached in cause and manner determination. It is also the first time the investigator will interact with the **next of kin** and many times law enforcement, so it is important that he or she is organized, systematic, and courteous. Family members can be distraught and not at their best, so it is best to have documents ready to leave with them for contact information and instructions on the process so they can later refer to it. This process of investigation is a one-shot deal and can never be duplicated to the level that it is on the initial visit. It is important for the investigator to consider a differential cause of death using observations, document key features, and resist being closed-minded with preconceived notions. An investigation is a fluid process, and as it progresses, small details may be the necessary key to properly determine the cause of death.

INTRODUCTION

The responsibility of death scene investigation varies across the United States. In some locations it may largely fall upon the coroner office, medical examiner office, or a combined coroner–medical examiner system. In some jurisdictions, the coroner office has been joined with a law enforcement department forming a joint sheriff–coroner division. These investigations involve working with multiple different jurisdictions and office policies. It is important for the death investigator to be aware of basic protocols at all death scenes and be able to adapt to other agency requirements.

The body itself is generally under the jurisdiction of the coroner/medical examiner, but the scene generally is under jurisdiction of the corresponding law enforcement agency (which may be a city police department or sheriff office). Some evidentiary materials overlap into both jurisdictions, so it is important to cooperate during the investigation process. Good death investigation means working as a team within a scene so that evidence in and around a body can be preserved so both cause and manner of death may be determined. Law enforcement often conducts witness interviews, collects crime materials, and takes photographs. Death investigators excel at understanding body changes with death, evaluation of wounds, and relationship of the body to surrounding materials relevant to determine cause of death.

Case Study

A 32-year-old male was found dead in bed during a welfare check after he failed to appear at work. Officers responding to the scene noted a secure residence and no obvious trauma. Because of the age and circumstances, the death was reported to the medical examiner's office. The responding death scene investigator obtained the usual intake demographics from the patrol officers (the only ones who responded to the scene). The officers reported no weapons; the residence was in order and no drug paraphernalia was found. Body examination by the death investigator showed a young male, normal body habitus, without injuries or evidence of drug use. The home was of normal temperature, the refrigerator contained food, and there was no obvious cause of death. Pictures were obtained of the decedent from multiple views in the room. Photos of the medicine cabinet and living areas were obtained. Upon opening the closet, the investigator noted four unmarked brown plastic bottles on the shelf with an insulin syringe, which he photographed and confiscated. An autopsy examination showed no anatomic cause of death with normal heart, slightly heavy lungs, and normal brain. Cause of death was pending further investigation. Six weeks later, after review of organ biopsies (microscopic examination) and a toxicology report negative for the routinely tested substances, the cause of death was still undetermined. The pathologist noted the brown bottles and syringe in the scene photos and consulted the toxicologist. Some substances are not detected during a routine toxicology examination and the materials were sent to a reference laboratory. Huge levels of anabolic steroids were detected in the toxicology. They were not previously detected because steroids are a naturally occurring material in the body and require special testing procedures to determine if they are used illicitly as a body-building effort. The cause of death was certified as "drug intoxication due to anabolic steroid use" and the manner of death as "accident."

Without the observation powers of the death investigator, the proper cause of death may not have been determined, resulting in an "undetermined" cause and manner of death. Subtle findings and routine evaluation of a decedent by a seasoned death investigator is extremely helpful to both the forensic pathologist and law enforcement to routinely document necessary findings and differentiate artifacts from potential relevant findings important in determining the cause of death. The death investigator needs to be accompanied by law enforcement when he or she is looking around the scene, not only for safety but also for jurisdiction to do so. In some states, the only jurisdiction a death investigator may have is that surrounding the body and he or she is not allowed to search within the residence or property. This death investigation jurisdiction usually extends to medications in the name of the decedent and to those items immediately surrounding them. It is important that the investigator collects these medications at the time as well as information for locating next of kin, because he or she cannot return to the scene after leaving it. Law enforcement will not be able to reenter either without a search warrant or family consent. Any items removed can be returned to the family with the body, but not having something needed or discarded by family will make the case much more complicated.

REVIEW OF LITERATURE

Death investigations are performed by individuals with various levels of expertise, experience, and training. Death investigators may have limited experience with dead bodies, crime scenes, anatomy, medical background, or trauma.

The National Academy of Sciences in their report to the National Institute of Justice in 2009 noted this disparity and has recommended it be addressed for a more uniform approach to death investigations across the United States. They cite that various perspectives and backgrounds of individuals are conducting these investigations, from the lay investigator with little or no training in some regions, to criminalists or crime scene investigators specifically trained in scene evidence recovery. The concern by the report is that inexperience and various policies, procedures, and focuses of the investigation may lead to bias with inappropriate convictions or acquittals [2]. This document reviews each area of the evidentiary process and concludes with recommendations for future improvement of the forensic science field. This document has proven important for advancement of grant funding as well as public awareness of issues faced by many departments. It has been the spearhead of accreditation of medical examiner/coroner offices and forensic laboratories, as well as individual certification and **quality assurance** programs.

Quality assurance programs take multiple forms and may involve subscriptions to accrediting bodies. Some examples are sets of case studies reviewed and submitted for grading, unknown lab samples sent to a central laboratory for grading with required results in an acceptable range to "pass," **peer review** of entire files by others within the office with a similar job description, and continuing-education requirements to maintain certification. Some offices also conduct public surveys of service satisfaction that may factor in yearly evaluations and salary adjustments. Other offices seem to be moving toward database tracking of number of cases per investigator, laboratory scientist, or pathologist, with turnaround times for completion to monitor satisfactory performance.

The American Board of Medicolegal Death Investigators is a governing body associated with the National Association of Medical Examiners and has developed a certification process to ensure basic knowledge of entry- and advanced-level death investigators in an attempt to create a basic uniformity in investigative procedures [3]. The certification process involves demonstrating a physical skill set to a forensic pathologist, as well as investigative procedures of various basic death scenarios with a written examination. Advanced certification requires a college degree and an additional written examination. Certification does not imply that errors will not be made; however, it might raise the basic level of investigations to a national baseline. Part of the maintenance of certification is a continuing-education requirement that helps ensure that the relationship to peers for informal assistance and awareness of advancing technology is maintained.

Because of the wide backgrounds and exposure to training, the National Institute of Justice published a guide to aid death investigators in basic knowledge of the process and collection of the necessary data. This guide, *Death Investigation: A Guide for the Scene Investigator*, can aid the investigator who rarely does death investigations or needs assistance [1].

The National Association of Medical Examiners has instituted an accreditation program that is maintained by forensic pathologists peer-reviewing the operation of both medical examiner and coroner offices within the United States [4]. The process involves an entire review of an office involved in death certification to ensure that minimum standards are being met and that the workload is manageable. The checklist used is available to the public and is helpful when reviewing current office policies and procedures to make sure they have been updated to current standards elsewhere. Also available are autopsy performance standards, which can help guide basic case management and provide direction, as well as serve as a quality assurance standard.

Equipment for scene evaluation has become more sophisticated. Although paper, pencil, and tape measures are still used, sophisticated computer programs can now render scene diagrams based on these measurements. Other instruments include a variation on the surveyor's tripod computing distances outdoors and recording them to drop into the computer program. Many can work on three dimensions, which can save hours processing the scene. However, they are complicated devices and require upfront training and routine use to remain proficient. These devices are also extremely expensive and most medical examiner offices cannot afford to purchase them.

PRESERVATION OF EVIDENCE

The first arriving officer is in charge of the scene until a higher-level investigator arrives. The first officer prevents disturbance of the body and isolates any witnesses so they may be interviewed by the death investigator and/or detective. In homicide scenes, yellow tape is usually placed to prevent free movement in and out of the scene. When arriving at these types of scenes, a scribe noting the name, time of entry, and exit will be at the perimeter and is a good place for the investigator to check in to notify officers of his or her arrival.

Other scenes may be more relaxed and lack the tape or scribe with only a single or pair of patrol officers waiting for the investigator's arrival. It is best for him or her to check in with the officers and gain a basic understanding of the situation prior to entry into the area of the dead body. This is extremely important, as sometimes there is evidence that may be stepped on and damaged just past the officers. They can relay information about resuscitative efforts and how the body was found.

With gunshot deaths, it is always a safe practice to secure the hands by placing brown paper bags over them prior to transport. This allows closer examination later for areas of soot or gunshot residue collection if necessary. It is best to secure the bags with tape rather than rubber bands as the bands create the false impression of a ligature on the wrists. Companies also make special paper-type bags that secure with a light string.

To protect against loss, any large quantities of money on the decedent should be counted with a witness, photographed, then placed into an envelope and sealed with initials of both parties on the envelope. Jewelry, even if it appears not especially valuable, may have sentimental value to a family, and needs to be documented via photographs at the scene. Things on the body are best left there and removed at the time of examination. This allows the pathologist to assess any patterned indentations or marks and correlate them with the jewelry that was in place. It also allows the jewelry to be released to the proper next of kin after that is established either at the funeral home or at the office. On occasion a next of kin will request that the jewelry be removed from the decedent prior to the body being transported to the office. If they are insistent on it, it needs to be photographed and written down on a personal effects form and have the family member sign for it along with a law enforcement officer as a witness. Examples of property forms are located in the Appendix.

Upon leaving a residence, the law enforcement officer will secure the house and lock it. Cars may need to be towed to an impound lot. Travel bags or belongings may need to accompany the decedent or be impounded by the police if they are not in a secure position.

Medications with the name of the decedent or ones in their possession need to be collected and removed from the location where the body was found. This gives the investigator valuable information about what diseases they were being treated for, pain medication use, whether they were being taken as prescribed, and the name of the physician treating the decedent to obtain medical history and possibly next of kin. Most medical examiner offices have a form to be filled out regarding medications (Figure 2.1). It is used to document the medication including the Rx number, date prescribed, medication prescribed, how many pills were dispensed and how many were left, prescribing physician, and the



DATE ____________

MEDICATIONS LOG

ML# ____________

NAME ____________

ITEM# ______ PRESCRIPTION# ____________ MEDICATION ____________

PHARMACY ____________ PHONE# ______ DOCTOR ______

DATE FILLED ____________ NUMBER REMAINING ______ NUMBER ISSUED ______

COMMENTS/DOSAGE ____________

ITEM# ______ PRESCRIPTION# ____________ MEDICATION ____________

PHARMACY ____________ PHONE# ______ DOCTOR ______

DATE FILLED ____________ NUMBER REMAINING ______ NUMBER ISSUED ______

COMMENTS/DOSAGE ____________

ITEM# ______ PRESCRIPTION# ____________ MEDICATION ____________

PHARMACY ____________ PHONE# ______ DOCTOR ______

DATE FILLED ____________ NUMBER REMAINING ______ NUMBER ISSUED ______

COMMENTS/DOSAGE ____________

ITEM# ______ PRESCRIPTION# ____________ MEDICATION ____________

PHARMACY ____________ PHONE# ______ DOCTOR ______

DATE FILLED ____________ NUMBER REMAINING ______ NUMBER ISSUED ______

COMMENTS/DOSAGE ____________

ITEM# ______ PRESCRIPTION# ____________ MEDICATION ____________

PHARMACY ____________ PHONE# ______ DOCTOR ______

DATE FILLED ____________ NUMBER REMAINING ______ NUMBER ISSUED ______

COMMENTS/DOSAGE ____________

ITEM# ______ PRESCRIPTION# ____________ MEDICATION ____________

PHARMACY ____________ PHONE# ______ DOCTOR ______

DATE FILLED ____________ NUMBER REMAINING ______ NUMBER ISSUED ______

COMMENTS/DOSAGE ____________

FIGURE 2.1

Example of a medication log form to inventory medications recovered from a decedent. Seized medications should be promptly inventoried, then discarded by the office protocol.

pharmacy information. Medications are discarded after they are documented and not returned to the family. Medications should not be discarded down the sink and usually require burning through biohazard companies or law enforcement disposal.

Scattered remains can present their own difficulty. This is seen in traffic, airplane, and train accidents where body tissues may be scattered over terrain. It can be especially challenging to collect if more than one decedent is involved. In that case it is best to make a diagram and label the tissues in separate bags. The main section of the residual body can form in one case number and the main section of other(s) can be in other separate body bags. Identification is going to be challenging in these types of cases, so attention to detail for teeth, jewelry, and personal effects will aid the identification and separation of tissues. If possible names are known, search for any local law enforcement prints or records (many have lists of tattoos as well), which will assist with the timely identification and **notification** of the family. If a circumstantial identification is known, it may be necessary to enlist the family to aid the identification process. The family can be informed that remains with the name of their member have been found and the process is beginning for identification to verify it is that person. They may have information for locating dental or medical records or knowledge of identifying scars, marks, or tattoos.

PHOTOGRAPHING THE DEATH SCENE

One of the hardest parts of photographing a death scene is keeping the photos straight, going from one scene to the next, and not having an opportunity to download them from the camera. It helps to become systematic in the photographic process and routinely repeat the same views and add additional views showing other pertinent details.

One suggestion to divide the photos among cases is to photograph a 3 × 5 card or small dry-erase board with the address location (or GPS coordinates), photographer last name, date, and case number, if it has been assigned. Alternatively, a separate SD card can be utilized for each case. Another photo that is useful is of the front of the house showing the location number so that it can be linked to a file. Some of the newer digital cameras allow programming of the filename so that the photographer's initials can form part of the photo file and verify who took the photos.

Photographing a death scene is basically documenting what the investigator sees on a walkthrough of a residence, into a room, and around a body. Rather than randomly taking photos, it is best to be systematic beginning with the front door and moving to the entrance of the room where the body is located with a view from the doorway. An overall view should be obtained from all four corners of the room where the decedent is located. This can be difficult in confined spaces like a bathroom and may need to be modified to using two or three views depending on the circumstances.

Following overall views, medium range and closer views of the body from sides, top, and bottom should be done if possible. Back and front views need to be done. Close-ups of any valuables are important to document their presence in case they are lost at some point or were not present on the body.

Relationships of the body to any objects or surfaces that may have created any injuries noted on the body are useful. The location of knives and knife stands, and presence of blood on them, is important in stabbings. If a gun is located, its position in relationship to the decedent is important, prior to moving it. Handling a gun requires a certain amount of knowledge of firearms, and law enforcement officers can assist with its examination and making it safe as it is secured as evidence. With revolvers, the cylinder should be photographed as it is ejected from the firing position. In semiautomatic handguns, photos of the cartridge and presence of bullets in the chamber and magazine need to be noted. All weapons need to have their serial numbers and both sides photographed after they are made safe. It is useful also to photograph the barrel end of a weapon to document presence or absence of blowback of tissue, blood, or foreign materials into the end of the weapon (again, be sure the weapon has been made safe and emptied of all bullets before doing this).

The surrounding surfaces that may be disturbed by moving the body or by the transport gurney need to be secured and photographed. This will also allow an entry and exit of the body from the scene. The sooner this can be done, the easier it will be to process the remainder of the scene and speed up the process. Preservation of the body as soon as reasonably possible will assist the later examination by the pathologist. By allowing the death investigator and/or pathologist to view the body may add insight into what type of death it is, and aid what photographs or investigation needs to follow. It is important that if the weapon, such as a knife, arrow, etc., is still embedded in the decedent, if possible the investigator needs to leave this weapon in the decedent and just secure it to the body. Any ligatures around the neck need to be left in place to allow the pathologist to view and remove these items. The investigator should disturb the surface of the decedent as little as possible.

After the body is photographed, it can be examined with photographs of any necessary valuables, injuries, or underlying evidence, then the body can be secured for transport. After the body is removed, it is important to photograph the surface where the body was resting. Photographing and securing any new pertinent evidence may be needed at this point using information gleaned from the external examination. The location of medications in relation to the body, bullet strikes, surrounding surfaces, the interior of a vehicle, etc. all need to be photographed as part of the scene investigation process and possible later review.

EVIDENCE COLLECTION TECHNIQUES

Whole books and treatises are written about evidence collection. Here some basic rules of thumb will be discussed that can easily be remembered. It is best to know crime lab technicians' recommendations and use them as a definitive resource because they are the ones doing the actual testing. If an investigator has something unusual, he or she should give them a call and ask them how it would best be collected.

On routine things, if it is a wet specimen, it needs to be collected onto something so it can dry since wet specimens deteriorate and may become unusable. So a wet blood spot needs to be collected with a cotton applicator (basically a large Q-tip) and placed into a specimen container to protect it and later dry. Wet clothing needs to be left on the body and removed during the autopsy. Clothing is usually placed into brown paper bags for transport and into a biohazard transport bag to prevent external contamination seeping through. As soon as possible, clothing needs to be hung to air dry in an area where the items will not be cross-contaminated by people passing by. Most departments have a clothing drying room with separate lockers per case, or special air-drying cabinets. When the clothing is dry, it can be placed into brown paper bags and stored. During the process of drying, each case must be marked with the name and case number to prevent mix-ups.

Dry specimens have more options and depend on the object. Basically, choose the smallest size container based on the size of the specimen, without stuffing it tightly. Guns, knives, and hazardous things like syringes have specialty boxes or plastic containers for secure transport, and to prevent injuries to others who unwittingly handle the contents.

Tape ligatures, gags, plastic wrap, and trash bags

These items present a collection issue because they will stick to the inside of a paper bag or plastic. The cut or torn ends need to be preserved during removal to use as a potential match for a recovered roll of tape. Tape also has potential for fingerprints and vast collection of trace evidence from the scene when it was placed on the decedent (Figure 2.2). Photograph the gag or ligature from the front, sides, and back, if possible, to document its placement. To remove it, use a scalpel (protect the underlying skin with the edge by a ruler or clean scalpel handle slipped under) or a scissor at a point away from the tape edges. Pull the edge of the tape back and document the underlying skin or gag within a mouth and how deeply it was embedded in the skin. The ligature can then be gently removed using forceps and dropped into a pizza or gun box for transport to the lab.

Plastic-wrapped bodies can also be treated similarly but the container for transport may need to be larger, such as a clean banker or file box. Again, fingerprints may be on the layers of plastic as it was applied, so gentle handling is needed. If the top/bottom or inside/outside are difficult to differentiate, discrete small marks can be made with an indelible marker.

Trash bags are also extremely good for fingerprints and need to be handled carefully in areas where there are ties or the edges used to place it over the decedent's



FIGURE 2.2
(A) The variety of tape that may be characteristic in an investigation to link a suspect to a decedent's death. (B) Tape can be difficult to package because it is sticky, therefore it is best placed inside a box rather than a paper bag if at all possible. (C) The margins of the tape tear can be characteristic and also could be the location of fingerprints. It is important when handling tape evidence to cut it off away from ends or areas where evidence may be best retrieved [5].

body parts. It is best to cut the bag with scissors to open it, leaving the tie intact. It can be laid out for photographs if necessary on a clean sheet then dropped into a brown paper bag for transport. Any questions about how to handle a unique piece of evidence is best managed by calling the crime laboratory where it will be submitted and asking for advice. It makes the processing much easier if they are involved and it is submitted correctly.

Each specimen needs to be labeled properly before removal from the site of collection. In a controlled environment, this can be done with adhesive labels run off on the computer and attached to the outside of the receptacle. These labels typically include the agency case number, name of the decedent, and current date. In the morgue situation it includes the pathologist name in charge of the case, or in law enforcement, the agency name. Below this information, the type of specimen, time collected, and initials of the person collecting it can be written.

For permanent storage, all evidence must be sealed prior to storage to ensure that it has not been tampered with or cross-contaminated. Special evidence tape is used for this purpose.

Occasionally law enforcement will request a sexual assault exam at the scene. It is best to contact the forensic pathologist who will conduct the exam for direction on how to proceed. If it is evident that the decedent has been sexually assaulted, it is a good practice to contact the forensic pathologist on-call and have him or her respond to the scene since swabs collected by the investigator may not withstand scrutiny in court.

CHAIN OF CUSTODY

A **chain of custody** is a form listing any seized evidence in sequence and noted in the same fashion as the identifying marks on the packaging (Figure 2.3). At the bottom of the form is a place for the signature of the person who collected the evidence and turned it over to the next person, who then is in charge of the material. It basically forms a branching tree so the origin of the results can be traced to the person who originally collected it from the site of the crime or from the body. If at any point the chain is broken, the evidence can become inadmissible to court and useless. To prevent any confusion as to which item is which the terminology used on the packaging (e.g., "bullet from head," or item 16 jeans) must match the description on the form.



CHAIN OF CUSTODY

DATE ____________ ML # ____________

NAME ____________ AGENCY/# ____________

FROM TO

____________ ____________TIME ________ DATE ________
____________ ____________TIME ________ DATE ________
____________ ____________TIME ________ DATE ________

FIGURE 2.3
A chain of custody serves as written documentation of each person who has handled a piece of evidence from its site of origin to its final storage destination. It links the piece of evidence to a produced report regarding the evidence, how and where it is stored and its location prior to the evidence being heard in court. It is important that each person linking the evidence to the next person be intact to verify that custody has been maintained and the evidence not tampered or contaminated.

MEDICOLEGAL DEATH INVESTIGATOR SCENE RESPONSE

Types of deaths requiring response

Obviously, it is best if a death investigator can respond to all death scenes, including hospital deaths, and depending on the jurisdiction, the death investigator may be serving the dual service of investigator and body removal. Each jurisdiction is designed slightly different and may utilize law enforcement for information to a varying degree. Also a variable is the body removal service, and whether it is supplied by the office or by a contract service. If it is the office, it may be a crew who does the removal service or it may be done by the death investigator.

In those instances where the death investigator is not the removal person, latitude in judgment or department policy will dictate scene response. Acute deaths where scene response is usually required are those including death in custody, firearm deaths, children, fire deaths, high-profile officials or visitors, aircraft, hangings, and suspicious deaths where law enforcement requests assistance or something seems unusual. Obviously, daytime response is much easier and should approach 100% on these types of deaths, but after-hours or weekend response may become an issue due to financial constraints or shortage of manpower.

Investigation briefcase

Death investigation is getting more sophisticated every day. Many have found durable laptop computers with roving Internet linkage to greatly expedite input into the office database directly from the scene, allowing real-time information to be relayed, as well as freeing the investigator to move to the next scene if need be. With digital photography, photographs can be downloaded and sent to the pathologist to be reviewed over a secure web line.

Even if the office is more basic, a laptop computer can be a real boost to an office. This allows the investigator to enter a case into the template and print it when he or she returns or upload it into the server. A paperless office can consist of a case file folder (much like a chart folder) on a server containing subfolders with the paper documents and one for the photos. It is also possible to have medical records transmitted in PDF format via a general investigator mailbox. Hospitals or doctor offices can do this from their paperless system or via paper directly onto a fax machine. Many copy machines now have the ability to convert paper to PDF-type files. Another useful item is a portable scanner or printer in case a form needs to be printed or if there are documents at the scene that need to be copied but may not be able to be seized by the death investigator (e.g., suicide notes).

Even with these sophisticated abilities, an investigator is going to need a pad of paper to record proper name spelling, date of birth, date and time of death, medications, medical history, who found the decedent, exact address, and next of kin information. An office might find it useful to utilize card form that is easily written on and can be placed into a pocket. There are examples of paper forms for retrieving the necessary intake information in the Appendix.

A digital camera is a must. It is useful to learn the various settings on the camera and practice its use so the investigator is able to adapt to various scenarios. A few difficult situations are those in rain or snow because the flash will reflect off the droplets. Photographing a body inside a motor vehicle is difficult because the investigator can be seen in the reflection of the window. Another is darkness with difficult lighting because the flash is not able to compensate using typical settings. It may be necessary to go manual and use a tripod to allow the aperture to remain open longer. Decomposed bodies in dark backgrounds are also challenging.

Other supplies needed are bags to collect and seal medications or large amounts of money, evidence collection bags of various sizes, lots of gloves, and clean collection instruments like forceps in a sealed clean pouch, paper towels, hand sanitizer, business cards, office brochures, or contact information.

Equipment list

The following is a handy list of items that are good to have when responding to a death scene:

- Camera
- Gloves
- Evidence bags
- Spare SD card and batteries for camera
- Business cards
- Small tablet for note taking
- Sudden Unexplained Infant Death Investigation (SUIDI) forms
- Chain of custody forms
- Paper case form (in case computer is not working)
- Clean forceps for evidence collection
- Pocket knife
- Body identification bracelet or tag
- Black magic markers
- Extra pen
- Hand sanitizer
- Paper towels
- Small biohazard bags and one or two large bags
- Multifunction pocket tool
- Flashlight
- Cut-resistant gloves
- EMT scissors to cut through ligatures, seat belts, etc.

Response vehicle equipment

The response vehicle should serve as a resource for restocking the briefcase and for holding items not commonly used. Typical things that should be stored in the vehicle are:

- Safety vest and flares for roadway scenes
- Body bags: regular, infant; heavy-duty with straps; extra large
- Extra body tags/bracelets
- Personal protective equipment (mask, coveralls, shoe covers, hair covers or ball cap)
- Tape measure
- Extra gloves
- Extra evidence bags and biohazard bags
- Small tarp
- Small shovel
- Pruning shears/bolt cutter
- Rope
- Bottled water
- Bug-collecting equipment (plastic containers with holes in lids, cat food, and large aquarium net or small butterfly net)
- Extra batteries for camera/flashlight
- Backup point-and-shoot camera

The response vehicle needs to reliably start, have a full gas tank before each shift, and be properly maintained, including routine cleaning inside and out. It is a good practice to keep a can of some type of sanitizing spray so that the investigator can spray the bottom of his or her shoes prior to getting into the vehicle at the scene. This will decrease cross-contamination to the vehicle or to other scenes that follow that day. It is also a good practice to wipe down the camera after every scene to make sure there are no biohazards on the camera equipment. Keeping an extra set of clothing including shoes inside the vehicle is helpful in cases where the investigator has become contaminated and has to discard his or her clothing at the scene.

MEDICAL AND SOCIAL HISTORY

The reporting party, such as roommate, spouse, or family member, may have some information about the current or past health of the decedent or his or her habits. It is important to ask about any current complaints, drinking, drug use, smoking, occupation, recent hospitalizations or visits to the doctor, and prescription medication use. Family history, including sudden death or other ill family members, may also be important. Pertinent observations, such as antacid use, over-the-counter medication use, examination of the trash, alcohol bottles, drug residue, etc., are important to include in the report. Even the presence or absence of a secure residence is an important finding, as are the circumstances the decedent was found (e.g., witnessed collapsed, welfare check, routinely returning to residence, etc.). The name of a treating physician is important to routinely request medical records. If it is an older individual, the death may have been expected and that physician may be willing to sign a death certificate if the death appears natural without trauma.

With decomposed bodies, law enforcement officers may know if fingerprints are available for identification verification. It may be efficient to explore with the family or a physician if the decedent had recent X-rays that might be used to confirm identification or if the decedent used a dentist.

NOTIFICATION OF NEXT OF KIN

Death notification to family or close friends of the decedent is not the easiest part of the job for death investigators. Many of the deaths are sudden and family members may be shocked, angry, or have some feelings of guilt or regret. Families are not at their best during these trying times. Violence, sudden collapse, threats, or just intense grief with apparent lack of cooperation may erupt. It is important to always have a situational awareness in case the situation deteriorates.

Notification is best made in person. If personally done, coworkers should be aware of the investigator's location or a coworker or law enforcement officer should accompany him or her to the site of notification. With the transient society we live in, many times this is not personally possible if the next of kin lives a distance away. It may be necessary to activate their local law enforcement agency to notify them and have them call for details. State law usually indicates the order of next of kin notification, which can be in the order of spouse, father, mother, siblings, and children. Obviously not all of them need to be notified, but the closest next of kin needs to be located for further demographic information, final disposition details, medical history, etc.

WRITTEN REPORT FORMATS

The written report should contain a concise summary of the course of events that surrounded the time of death. It needs to be grammatically correct, spell checked, and have a logical flow of information. Saying too much and being overly interpretive is as bad as or worse than leaving out pertinent information. It is best to utilize a framework for each report so information within it can be located quickly to answer pertinent questions (Figure 2.4).

CASE FLOW

Steps in the process of how a body is handled and paperwork flow can be office-dependent. However, all offices have certain aspects in common, and it is helpful to understand this process so it can be explained to a decedent's family members or an outside agency.



Initial Written Report Format

Case #:
LAST NAME, First Name

Response date & time:
Information source:
Circumstances of death:
Past medical history:
Treating physician
Medications:
Identification:
Notification
Body Exam: rigor, livor, body position, areas of trauma

Report Amendments
Update identification confirmation if needed
Final Disposition: Funeral home, relative authorizing release, date released
Follow up history or investigation information

FIGURE 2.4
Summary of key topics needed in every report. Other information can be added within these areas to summarize the course of events.

How does a case come to the attention of an investigator?

State law mandates reporting certain cases by anyone having the knowledge of a death within the statutes. In summary, these include all unnatural, suspicious, or unusual deaths, and those posing a public health hazard. Various smaller categories exist within the law and will clarify the general description. Each office will have a policy on which cases require a scene response and which cases may be managed over the phone. A rule of thumb is all traumatic deaths dead at a scene, those with no attending physician, and those under suspicious circumstances like drug use require a response. Those found outside a residence, inside a vehicle, or if the officer at the scene needs assistance are also common response scenes. Older persons (usually over 70–75 years) or those dying in a hospital are not as high priority to respond and visually view the body. Children dead at a scene should have a response, and, if possible, children dead in a hospital without trauma, medical history, or those with trauma not related to motor vehicle accidents should have a scene response by the investigator or law enforcement to assess the home situation and photography.

Basically, a call comes from outside the office to say there is a death in a particular location. Depending on who makes the call—a dispatcher, a patrol officer, an adjacent county investigator/coroner—will reveal more or less information. Sometimes all that is communicated is an address and request for an investigator to respond. This means the investigator has to be ready for anything from a child, to a homicide, to skeletal remains, to a buried body, to a traffic accident, etc. The response briefcase and vehicle need to be prepared to address questions law enforcement may have and to deal with all these scenarios. The vehicle needs to always be restocked when the previous investigator has returned to the office and used something from the vehicle. Periodic inventory needs to be done to ensure the vehicle and briefcases are stocked.

Other times, the caller may state that the decedent is older with no evidence of foul play or trauma and is under the current care of a physician. Office policy will guide the investigator if a scene response is needed in these types of cases.

Scene response is not something delayed by multiple distractions. When the call comes, the investigator should be organized to respond out the door within five minutes. Many times, officers are being held up at the scene of death while other response calls come to their department. Roads may be closed, trains stopped, or airports closed until the body is removed and the scene is cleared. It is important for the investigator to take the direct route and be timely.

GPS systems are highly advised to not only get the investigator there by the most direct route, but also in remote areas, GPS coordinates can be used for recording on the paperwork as the site of death. Getting to a scene may be complicated by backed-up traffic due to the scene. The local police department dispatch may be able to assist and recommend the best route into the scene, which may mean going to an exit and up the wrong way on a closed road, or to request a police escort. Dispatch can also pass a call to the officer at the scene and let the investigator talk to him or her directly if the investigator is lost or having difficulty. Many times the officer will post a flare or park a unit at a turnoff to guide others in.

What does an investigator do when he or she arrives?

An officer will be at the scene when the investigator arrives and he or she is the first point of contact for information. If the scene is a homicide, there will be a sign-in process to enter the scene and proceed beyond the yellow tape. A detective will escort the investigator in and brief him or her. The investigator should pay attention to areas on the floor and the small flags adjacent to items of evidence so as not to disturb them. Entry into a scene like this requires use of gloves and shoe covers at a minimum. The investigator should follow the lead of the detective who meets him or her, and not pick things up and look at them until the investigator is briefed. Before removing anything, the investigator should ask if it has been photographed and documented. The detective will do a walk-through and explain the case and areas of importance. There is no need to photograph or document anything until this is complete. The investigator should ask about logistics and if there is a clear path to the body. He or she should begin to formulate a plan for approaching the body, as well as what items will be needed to preserve and answer the questions law enforcement officers may have. The investigator should consider the amount of time and when he or she needs to call for body removal service. The investigator wants to be at the scene the shortest amount of time possible (in case there is another scene response) and does not want to wait on the arrival of the body removal service after the body is in the body bag. He or she should begin to fill out the paperwork demographics with the information that is known. In addition, he or she should gather the materials needed to examine the body, including being prepared to protect the hands with brown paper bags, photograph the body, put on the identification band for the body, and have a plan for placement of the body into a body bag. Sealing the bag in the presence of law enforcement documents that the bag has not been breached prior to it being opened by morgue personnel.

How does the investigator start gathering the info?

The scene information will tailor the various specific pieces of information that need to be documented. All scenes get the basic information of demographics, what happened, overall photographs, and examination of the body for rigor, livor, and gross documentation of injuries. Specific documentation of each injury will be documented by the doctor, but some evaluation needs to be made to assess if the injuries are matching the scenario that law enforcement has provided. Discrepancies need to be communicated to them and it should be decided together how best to proceed. It may require the forensic pathologist to respond if law enforcement needs information to proceed. The body needs to be checked for weapons so they may be removed and given to law enforcement prior to transport. The body always needs to be placed on its back to transport so as not to distort the facial features. Wrapping the body in a sheet will minimize the amount of blood welling up in the bag and soaking the clothing, especially for gunshot and stab wounds.

How does the investigator get the body to the office?

Some offices have investigators do their own transport. Other offices have employees in a separate unit do the transport, or in combination with the investigator as an assistant. Other options include local transport services under contract that typically also transport for funeral homes.

What happens to the body when it gets to the office?

The body is logged into the system. Office policy will determine if the body can be prepared for an autopsy or if the bag must remain sealed until the autopsy begins. It is possible to X-ray the body through the bag without opening it, which is helpful in homicides. If the bag can be opened, the property and clothing may be removed and documented on routine cases. Other offices keep the bag closed until the time of the autopsy and all is documented at that time. Height and weight are recorded.

What happens during the autopsy?

The forensic pathologist will take notes about property, weight, and height, and examine the body for injuries. All will be recorded for later transition into a written report. Some cases may be certified only on external examination based on history and observations from the examination. X-rays may be used to examine the body for trauma, enlarged heart, pneumonia, or foreign objects. Toxicology and DNA sampling is obtained on most bodies. Fingerprints are also obtained for retention in the office file as well as a copy forwarded to law enforcement to close records. Using these observations, the doctor will determine if he or she can certify a cause of death upon exam only or decide if an autopsy needs to be done.

An external exam usually takes 15–30 minutes depending on the extent of injuries. A routine autopsy for a natural death or drug intoxication death requires an hour or two to complete. Homicides or complicated cases take generally at least two hours and can extend up to six hours. Child abuse cases can be multistaged over a couple of days and an estimated date for release of the body to the family needs to be coordinated with the pathologist.

What does the investigator do when he or she returns to the office?

The investigator needs to begin a report and enter the demographic data needed into the database, transfer the photographs from the camera to a disk/computer system, and coordinate with the pathologist and morgue staff regarding the case for potential autopsy, need for X-rays, etc. If the office is operating within an online death certificate system, it usually falls to the investigator to begin the data entry for its completion. Generally, this includes the name, date, time, and location of death and time of injury if known. The pathologist will document the cause and manner. It is helpful to chat with the pathologist about his or her findings so they can be relayed to the family. Medications from the decedent need to be counted, recorded, and prepared for discard and should not lie about the office.

What happens after the autopsy?

It is good practice to contact the next of kin after the exam or autopsy to relay the cause of death and findings. If the cause and manner are pending toxicology or further investigation, it is a good time to ask the family further questions needed by the pathologist and about medical history, or gather other information needed to determine the manner of death. The family can be given a time estimate for completion of the cause and manner and the process for them to receive reports, amended death certificates, etc.

How does the body get back to the family?

A family will generally ask how to get the decedent back and this topic is easily addressed during the call made by the investigator after the autopsy/exam. It is a great opportunity to request their funeral home of choice and relay that the decision needs to be made as soon as possible. If families cannot make a decision due to conflicts or are unable to afford a funeral home, it is good to be aware of social services available.

What happens at the funeral home?

It is always a good idea to get the family funeral home choice relayed to the office in writing and verify that the decision was made by the family member who has the authority to do so. Sometimes families do not communicate well and conflicts will become apparent. It is important the office depends on the person with the legal authority and have proof of this to avoid having to assume the cost of transport to another funeral home.

The appropriate funeral home or their transport company will arrive at the office to retrieve the body. It is important that all clothing and personal effects be released with the body. Verification of the personal property, valuables, and identity of the decedent with signatures on all forms is required before the body may leave the building. Visually checking the name on the identification band on the decedent and the case number, by both the morgue personnel/investigator and the funeral home personnel, is imperative to prevent the wrong body being released. It is even more imperative if there is more than one decedent with the same last name.

Valuables and large amounts of money need to be counted and verified plus signed for before release. The office will have a paperwork system to deal with the property and body release (Figure 2.5).

What happens with the paperwork?

Most offices still maintain some form of paper file. Many offices are converting to a paperless office at least to some degree so many reports are present in both formats. A file generally includes standard documents for the investigative report, pathologist report, copy of death certificate, requests for copies of the reports, fingerprints, backup X-ray and photo disks, property, and body release forms. Other information such as chain of custody or medical records may be included. Files are generally filed by case numbers.

How does the family or agencies get copies of the paperwork or file contents?

Each office will have a policy regarding release of documents based on what has been deemed public record by state law. The county or state attorney representing the office usually assists with making decisions about unusual requests like review boards. In most states, the completed death certificate is public record and anyone may retrieve a copy from the health department. Releasing cause and manner information over the phone to press and other entities not related to next of kin may need supervisor approval or need to be referred to the law enforcement agency public information officer/detective in sensitive cases.

State law also may mandate that copies of certain reports, such as homicides, be relayed to particular agencies such as the county or state attorney. Each state varies whether the autopsy report is considered public record and released to all requestors. Knowledge and understanding of this policy needs to be reviewed in



PROPERTY RECEIPT

Date: ____________________
Name of Deceased: ____ Case # ___________________

PROPERTY: Received

Amount			Total	Received
$ 0.01	x ______	=	0.00	______
$ 0.05	x ______	=	0.00	______
$ 0.10	x ______	=	0.00	______
$ 0.25	x ______	=	0.00	______
$ 0.50	x ______	=	0.00	______
$ 1.00	x ______	=	0.00	______
$ 2.00	x ______	=	0.00	______
$ 5.00	x ______	=	0.00	______
$ 10.00	x ______	=	0.00	______
$ 20.00	x ______	=	0.00	______
$ 50.00	x ______	=	0.00	______
$ 100.00	x ______	=	0.00	______
	Total	=	0.00	______

Checks:	Amount	Received
______________	$______	______
______________	$______	______
______________	$______	______
______________	$______	______

Signature, Person releasing property

Witness

Signature, Person receiving property

Date / Time By

Print Name

Relationship to the decedent (Mortuary, Family, Etc.)

FIGURE 2.5
Basic property documentation form. The articles of clothing and personal effects can be listed and the money itemized. At the bottom are signature areas for those releasing and then receiving the property so that a chain of custody is maintained.

the procedure manual or state law regarding which documents may be released and to whom. Photographs from the autopsy are similar in their status and are not generally released to the press due to their sensitive nature and invasion of privacy. In high-profile cases, the press frequently will seek them under the First Amendment. In Florida, the Earnhardt Family Protection Act, also known as the Earnhardt Law, was passed in response to the press wishing access to the autopsy photos of Dale Earnhardt, Sr., who died during the Daytona 500 auto race. The Florida law states that autopsy photos, videos, and audio recordings are confidential and should not be released without a judge's approval. Failure to comply with the law is a felony punishable by a $5,000 fine. A surviving spouse, parent, or child may view the photos and the medical examiner or other state agencies may utilize them in the course of their duties without the judge's permission, but the identity of the decedent must remain confidential. Other states have adopted similar restrictions. Families may request to see the autopsy photos. This can be traumatic for them to review, and whenever possible, the investigator needs to explore what answer they are seeking to see if the question can be answered in some other fashion.

Attorneys commonly request copies of autopsy and toxicology reports and possibly photos. Office policy needs to outline the procedure for this. A good practice is for the request to be submitted in writing on company letterhead with the request outlining which documents they wish to obtain. There may be fees associated with this request and those will need to be communicated to them. Occasionally they will submit a subpoena or a *duces tecum*, which outlines a request for the entire record, including investigative reports, toxicology, worksheets, chain of custody, and internal documents that form the file. Many offices exclude reports from outside agencies (e.g., medical records, police reports) as they were not generated by the coroner/medical examiner office and should be retrieved from the originating source. It is best if the chief coroner or medical examiner outlines which documents are to be included in each type of request (*duces tecum*, subpoena, letter request) and approve any outlying ones. This list can be preapproved by the office attorney to make sure it is in compliance with state laws.

The length of time to completion of an autopsy report will vary based on a number of factors. It can be dependent on information from the crime laboratory, further investigation, confirmation of the identity of the decedent, toxicology results, medical records, and review of microscopic tissue biopsies that need review by the forensic pathologist. It is generally at least one month for a report and can extend to six months or even a year depending on the workload and the difficulties of the case. It is best not to promise an exact date, but to have the families or other interested parties call back at intervals.

Case Study

A call comes to the office requesting an investigator to respond to a possible suicide at 399 Harbor Street in your local jurisdiction. Upon arriving at the scene, the investigator is met outside the residence by a patrol officer and a detective. They relate that a 25-year-old male was found by a friend on the patio of the decedent's residence. He was found sitting in a chair with a gun on his lap beside his right hand. EMS was called, documented a gunshot wound to the head, and moved him to the ground, but he was unable to be resuscitated. The officers state he had recently been found to be having an affair with his wife's best friend, had been accused of embezzling money from the office where he worked, and was being investigated by undercover police for drug trafficking.

The death investigator asks the usual demographics, including name, age, date of birth, next of kin, time of pronouncement, when he was last seen alive, how he was identified, as well as the detective's name and contact information. The family has not arrived outside the residence and the investigator inquires about the whereabouts of the wife. Further questioning can be about the ownership of the gun, where it was stored, where the ammunition was stored, how long he had the gun, how familiar he was with gun usage, was he right- or left-handed, and what prompted the friend to come visit.

At this point, it is time for the investigator to consider calling for transport so they will arrive about the time she is ready to place the body in the bag. The investigator has a fully stocked briefcase including a working camera, gloves, brown paper bags, and body bag with a seal to carry to the patio for the examination. This is the best time for her to put two pairs of gloves on before entering. It is also helpful for her to snap the baseline photo of the location on a white board as well as the house number before proceeding inside the house. She should place booties on her feet to prevent tracking blood back through the house, and it is also a good time to ensure her hair is confined and all necessary clothing protection is in place.

The detective then escorts the investigator to the patio for the survey. The decedent is visible lying on the ground next to a metal chair and a large pool of blood is at the base of the chair and under the decedent's head. The pool of blood at the base of the chair contains a peripheral fine spray of blood spatter. The gun is lying on an adjacent picnic table and has been made safe by the patrol officer upon his arrival. According to the detective, the 9-mm handgun had an empty chamber and empty magazine. Blowback is visible within the barrel of the weapon. The gun had been stored in a case in an upstairs bedroom and the case was found open on the bed. A new box of ammunition was on the dresser and showed a single missing bullet in the package. A receipt for the ammunition was lying beside the box and dated the previous day.

The investigator proceeds to photograph the scene from four points around the decedent, followed by midrange views of the top and sides of the body. Photos of the gun on the table, including serial number and blood transfer on the barrel, need to be documented. Midrange views need to be obtained of the blood spray at the base of the chair. Photos of the decedent's hands showing any soot deposition, as well as mid- and close-range views of the gunshot wound need to be documented. Valuables including necklaces and rings need to be visible in the photos. It is always helpful and courteous for the investigator to assist law enforcement with any photos they may need during this process.

Before touching the body, it is good for the investigator to pull out brown paper bags and tape so she can secure these in place before handling the body. As they are slipped on, it is a good time to examine the hands for injuries. Handling the arms also gives information about the rigor, body warmth, and livor. Before getting gloves bloody, it is good to assess livor on the torso, and assess the chest and remainder of the body for any other injuries. Pockets can be patted for identification, wallets, potential weapons, and drugs. It is good practice to pat the pockets before putting hands into them. This will avoid the investigator being stuck by needles or any other sharp objects that might be in the pockets. The last step is to make a close examination of the head including the eyes for petechiae, the mouth for injuries, and the neck. The goal is to differentiate entrance and exit wounds, if possible, and note any other injuries. If entrance and exit wounds are unable to be determined by the investigator, it is better to be noncommittal. The presence of soot or a muzzle abrasion in this type of case will let the detective know it was a contact or near-contact wound. If an exit wound is identified, the detective will want to try to locate the expended bullet, if possible. So it will be necessary to palpate the scalp to locate it. The wounds should never be probed. If the face is distorted by trauma, it is helpful for the investigator to ask law enforcement to check for availability of fingerprints on file for confirmation of identity.

Officers may be willing to assist rolling the body to view the back so both parties can obtain photos. Or it can be done when removal arrives to help move the body into the bag. Either way, photographing the body when it is rolled onto

Continued

the side is a good way to not only document the back for injuries, but also note any jewelry pendants that are on the back of a necklace, and the ground under the decedent. If the blood is flowing freely, a towel can be used to wrap around the head and contain the mess. An open body bag can be tucked under the body while on its side and when it's rolled back it will be within the inside of the bag ready for transfer to a gurney and removal. The identification band can be attached and any related property can be contained in the bag. At this point, bloody gloves can be peeled off and placed in the bag, or a small biohazard bag in the briefcase.

It is time to photograph the gun case and ammunition box, as well as search for a note or medications related to the decedent. As the house is surveyed, items used to date the last known alive point are noted including cellphone texts, etc. The investigator gathers this information and inquires about the notification of the wife. The detective has already spoken to her and told her of the husband's death via phone. She is en route to the residence.

Removal service has arrived and is ready to remove the body to the office. The investigator assists with logistics of escorting them to the decedent and ensures the bag is sealed. The detective has boxed the firearm and the ammunition and ejected casing. A bullet was not located. After the body has exited the scene, the ground around the body can be photographed.

The body arrives at the morgue and is logged in by the personnel. A head X-ray is obtained through the body bag and a projectile is noted. The forensic pathologist is briefed and it is decided the autopsy will be done in two hours. The detective is called and notified that the bullet is present in the head and the pathologist is doing an autopsy in two hours. The detective has confirmed a previous arrest record and fingerprints are on file if needed. The wife is located at the residence phone and the investigator makes contact to confirm notification and obtain psychological history.

The pathologist confirms the contact gunshot wound of the head and findings consistent with suicide. Toxicology specimens are obtained and sent to the laboratory. Fingerprints are also obtained during the autopsy and ready to be sent to law enforcement for confirmation of identity. The investigator scans and arranges to email them or deliver them to law enforcement for positive identification.

The investigator calls the wife and notifies her of the cause of death and answer her questions. Other family members inquire about clean up and the investigator refers them to cleaning services in the community that deal with such matters. They inquire how to obtain a death certificate and the investigator relays that it will be given to them at the funeral home. The family supplies the name of the funeral home and the investigator requests that the funeral home send that authorization to the office and the decedent can be released with property and valuables.

The investigator completes the written report, downloads the photos, and records any medications to finalize the investigation. Follow-up information is usually placed onto addendum reports.

RESOURCES

Many state crime laboratories and the FBI publish an evidence handling manual. Here are a few helpful versions:

Missouri. http://www.mshp.dps.missouri.gov/MSHPWeb/Publications/Handbooks-Manuals/documents/SHP-145.pdf.

Texas: Physical Evidence Handbook. http://www.txdps.state.tx.us/CrimeLaboratory/documents/PEHmanual.pdf.

FBI: Handbook of Forensic Services. http://www.fbi.gov/about-us/lab/handbook-of-forensic-services-pdf/view.

Schoebel PJ, Weiss S. Photography of medicolegal and forensic autopsies. Evidence Technology Magazine 2009;10–13:28.

Body diagrams. http://www.afmes.mil/index.cfm?pageid=resources.autopsy_diagrams.

REFERENCES

[1] National Medicolegal Review Panel. Death Investigation: A Guide for the Scene Investigator. Technical update. National Institute of Justice; 2011. Retrieved from https://ncjrs.gov/pdffiles1/nij/234457.pdf. [16 August 2013].

[2] National Research Council of the National Academies. Strengthening Forensic Science in the United States. National Academies Press; 2009. Retrieved from http://www.nap.edu/catalog.php?record_id=12589. [22 August 2013].

[3] American Board of Medicolegal Death Investigators. Retrieved from http://abmdi.org/. [23 August 2013].

[4] NAME Accreditation Checklist 2009-2014. National Association of Medical Examiners Inspection and Accreditation Documents. Checklist and Autopsy Standards. Retrieved from https://netforum.avectra.com/eweb/DynamicPage.aspx?Site=NAME&WebCode=PubIA. [23 August 2013].

[5] Pressure Sensitive Tape. Missouri State Highway Patrol. Retrieved from http://www.mshp.dps.missouri.gov/MSHPWeb/PatrolDivisions/CLD/TraceEvidence/tape.html. [16 August 2013].

CHAPTER 3

Death Certification

Learning Objectives

- Distinguish cause of death from a manner of death and give examples of each.
- Identify a cause of death that might need further investigation and outline the reasoning why it would need to be investigated, as well as the questions that would need to be asked to determine if jurisdiction would be needed.
- Discuss the purpose of a death certificate and its role in vital statistics and final affairs of the decedent.
- Research the state laws for the definition of a fetus, age of viability, and live birth in your state. Discuss what impact this determination has for the proper certification format (i.e., birth certificate with death certificate versus fetal death certificate).
- Illustrate an example of a therapeutic misadventure and questions that need to be answered to differentiate an accidental manner versus a known complication for a natural disease.

Key Terms

Manner of death
Cause of death
Fetus
Live birth
Therapeutic misadventure

Chapter Summary

Death certification is an important document for families to resolve estates, as well as a means to monitor public health trends and prevention of death. It is important to distinguish causes of death from mechanisms of death, as well as have an understanding of key investigative issues used to distinguish the manner of death. Death investigators usually serve as a final safeguard of questionable causes of death to prevent unreported cases to the death investigation system and serve as a reference for vital records departments and families. It is important to have a working knowledge of causes of death that may have an underlying accidental, suicidal, or homicidal manner.

INTRODUCTION

Death certification is a process of establishing an official cause of death for official purposes. Certificates are completed by a treating physician, by coroners, or by medical examiners (Figure 3.1). State law determines who will be eligible for



U.S. STANDARD CERTIFICATE OF DEATH

LOCAL FILE NO.

STATE FILE NO.

NAME OF DECEDENT ____
For use by physician or institution

To Be Completed/ Verified By:
FUNERAL DIRECTOR:

1. DECEDENT'S LEGAL NAME (Include AKA's if any) (First, Middle, Last)
2. SEX
3. SOCIAL SECURITY NUMBER
4a. AGE-Last Birthday (Years)
4b. UNDER 1 YEAR: Months | Days
4c. UNDER 1 DAY: Hours | Minutes
5. DATE OF BIRTH (Mo/Day/Yr)
6. BIRTHPLACE (City and State or Foreign Country)
7a. RESIDENCE-STATE
7b. COUNTY
7c. CITY OR TOWN
7d. STREET AND NUMBER
7e. APT. NO.
7f. ZIP CODE
7g. INSIDE CITY LIMITS? ☐ Yes ☐ No
8. EVER IN US ARMED FORCES? ☐ Yes ☐ No
9. MARITAL STATUS AT TIME OF DEATH ☐ Married ☐ Married, but separated ☐ Widowed ☐ Divorced ☐ Never Married ☐ Unknown
10. SURVIVING SPOUSE'S NAME (If wife, give name prior to first marriage)
11. FATHER'S NAME (First, Middle, Last)
12. MOTHER'S NAME PRIOR TO FIRST MARRIAGE (First, Middle, Last)
13a. INFORMANT'S NAME
13b. RELATIONSHIP TO DECEDENT
13c. MAILING ADDRESS (Street and Number, City, State, Zip Code)

14. PLACE OF DEATH (Check only one: see instructions)

IF DEATH OCCURRED IN A HOSPITAL:
☐ Inpatient ☐ Emergency Room/Outpatient ☐ Dead on Arrival

IF DEATH OCCURRED SOMEWHERE OTHER THAN A HOSPITAL:
☐ Hospice facility ☐ Nursing home/Long term care facility ☐ Decedent's home ☐ Other (Specify):

15. FACILITY NAME (If not institution, give street & number)
16. CITY OR TOWN , STATE, AND ZIP CODE
17. COUNTY OF DEATH
18. METHOD OF DISPOSITION: ☐ Burial ☐ Cremation ☐ Donation ☐ Entombment ☐ Removal from State ☐ Other (Specify):____
19. PLACE OF DISPOSITION (Name of cemetery, crematory, other place)
20. LOCATION-CITY, TOWN, AND STATE
21. NAME AND COMPLETE ADDRESS OF FUNERAL FACILITY
22. SIGNATURE OF FUNERAL SERVICE LICENSEE OR OTHER AGENT
23. LICENSE NUMBER (Of Licensee)

To Be Completed By:
MEDICAL CERTIFIER

ITEMS 24-28 MUST BE COMPLETED BY PERSON WHO PRONOUNCES OR CERTIFIES DEATH

24. DATE PRONOUNCED DEAD (Mo/Day/Yr)
25. TIME PRONOUNCED DEAD
26. SIGNATURE OF PERSON PRONOUNCING DEATH (Only when applicable)
27. LICENSE NUMBER
28. DATE SIGNED (Mo/Day/Yr)
29. ACTUAL OR PRESUMED DATE OF DEATH (Mo/Day/Yr) (Spell Month)
30. ACTUAL OR PRESUMED TIME OF DEATH
31. WAS MEDICAL EXAMINER OR CORONER CONTACTED? ☐ Yes ☐ No

CAUSE OF DEATH (See instructions and examples)

32. **PART I.** Enter the chain of events--diseases, injuries, or complications--that directly caused the death. DO NOT enter terminal events such as cardiac arrest, respiratory arrest, or ventricular fibrillation without showing the etiology. DO NOT ABBREVIATE. Enter only one cause on a line. Add additional lines if necessary.

Approximate interval: Onset to death

IMMEDIATE CAUSE (Final disease or condition ---------> resulting in death) a.____ ____
Due to (or as a consequence of):

Sequentially list conditions, if any, leading to the cause listed on line a. Enter the **UNDERLYING CAUSE** (disease or injury that initiated the events resulting in death) **LAST**

b.____ ____
Due to (or as a consequence of):
c.____ ____
Due to (or as a consequence of):
d.____ ____

PART II. Enter other significant conditions contributing to death but not resulting in the underlying cause given in PART I

33. WAS AN AUTOPSY PERFORMED? ☐ Yes ☐ No
34. WERE AUTOPSY FINDINGS AVAILABLE TO COMPLETE THE CAUSE OF DEATH? ☐ Yes ☐ No

35. DID TOBACCO USE CONTRIBUTE TO DEATH?
☐ Yes ☐ Probably
☐ No ☐ Unknown

36. IF FEMALE:
☐ Not pregnant within past year
☐ Pregnant at time of death
☐ Not pregnant, but pregnant within 42 days of death
☐ Not pregnant, but pregnant 43 days to 1 year before death
☐ Unknown if pregnant within the past year

37. MANNER OF DEATH
☐ Natural ☐ Homicide
☐ Accident ☐ Pending Investigation
☐ Suicide ☐ Could not be determined

38. DATE OF INJURY (Mo/Day/Yr) (Spell Month)
39. TIME OF INJURY
40. PLACE OF INJURY (e.g., Decedent's home; construction site; restaurant; wooded area)
41. INJURY AT WORK? ☐ Yes ☐ No
42. LOCATION OF INJURY: State: City or Town:
Street & Number: Apartment No.: Zip Code:
43. DESCRIBE HOW INJURY OCCURRED:

44. IF TRANSPORTATION INJURY, SPECIFY:
☐ Driver/Operator
☐ Passenger
☐ Pedestrian
☐ Other (Specify)

45. CERTIFIER (Check only one):
☐ Certifying physician-To the best of my knowledge, death occurred due to the cause(s) and manner stated.
☐ Pronouncing & Certifying physician-To the best of my knowledge, death occurred at the time, date, and place, and due to the cause(s) and manner stated.
☐ Medical Examiner/Coroner-On the basis of examination, and/or investigation, in my opinion, death occurred at the time, date, and place, and due to the cause(s) and manner stated.

Signature of certifier:____

46. NAME, ADDRESS, AND ZIP CODE OF PERSON COMPLETING CAUSE OF DEATH (Item 32)
47. TITLE OF CERTIFIER
48. LICENSE NUMBER
49. DATE CERTIFIED (Mo/Day/Yr)
50. **FOR REGISTRAR ONLY**- DATE FILED (Mo/Day/Yr)

To Be Completed By:
FUNERAL DIRECTOR

51. DECEDENT'S EDUCATION-Check the box that best describes the highest degree or level of school completed at the time of death.
☐ 8th grade or less
☐ 9th - 12th grade; no diploma
☐ High school graduate or GED completed
☐ Some college credit, but no degree
☐ Associate degree (e.g., AA, AS)
☐ Bachelor's degree (e.g., BA, AB, BS)
☐ Master's degree (e.g., MA, MS, MEng, MEd, MSW, MBA)
☐ Doctorate (e.g., PhD, EdD) or Professional degree (e.g., MD, DDS, DVM, LLB, JD)

52. DECEDENT OF HISPANIC ORIGIN? Check the box that best describes whether the decedent is Spanish/Hispanic/Latino. Check the "No" box if decedent is not Spanish/Hispanic/Latino.
☐ No, not Spanish/Hispanic/Latino
☐ Yes, Mexican, Mexican American, Chicano
☐ Yes, Puerto Rican
☐ Yes, Cuban
☐ Yes, other Spanish/Hispanic/Latino (Specify) ____

53. DECEDENT'S RACE (Check one or more races to indicate what the decedent considered himself or herself to be)
☐ White
☐ Black or African American
☐ American Indian or Alaska Native (Name of the enrolled or principal tribe) ____
☐ Asian Indian
☐ Chinese
☐ Filipino
☐ Japanese
☐ Korean
☐ Vietnamese
☐ Other Asian (Specify)____
☐ Native Hawaiian
☐ Guamanian or Chamorro
☐ Samoan
☐ Other Pacific Islander (Specify)____
☐ Other (Specify)____

54. DECEDENT'S USUAL OCCUPATION (Indicate type of work done during most of working life. DO NOT USE RETIRED).
55. KIND OF BUSINESS/INDUSTRY

REV. 11/2003

FIGURE 3.1

The U.S. Standard Certificate of Death. It serves as the template for each state to adopt their death certificate in compliance with their state laws. The majority of states and the jurisdictions within them have progressed to online death certification, which appears similar to this format [4].



MEDICAL CERTIFIER INSTRUCTIONS for selected items on U.S. Standard Certificate of Death

(See Physicians' Handbook or Medical Examiner/Coroner Handbook on Death Registration for instructions on all items)

ITEMS ON WHEN DEATH OCCURRED

Items 24-25 and 29-31 should always be completed. If the facility uses a separate pronouncer or other person to indicate that death has taken place with another person more familiar with the case completing the remainder of the medical portion of the death certificate, the pronouncer completes Items 24-28. If a certifier completes Items 24-25 as well as items 29-49, Items 26-28 may be left blank.

ITEMS 24-25, 29-30 – DATE AND TIME OF DEATH

Spell out the name of the month. If the exact date of death is unknown, enter the **approximate** date. If the date cannot be approximated, enter the date the body is found and identify as **date found**. Date pronounced and actual date may be the same. Enter the exact hour and minutes according to a 24-hour clock; estimates may be provided with "Approx." placed before the time.

ITEM 32 – CAUSE OF DEATH (See attached examples)

Take care to make the entry legible. Use a computer printer with high resolution, typewriter with good black ribbon and clean keys, or print legibly using permanent **black** ink in completing the CAUSE OF DEATH Section. **Do not abbreviate** conditions entered in section.

Part I (Chain of events leading directly to death)

•Only **one** cause should be entered on each line. Line (a) **MUST ALWAYS** have an entry. **DO NOT** leave blank. Additional lines may be added if necessary.

•If the condition on Line (a) resulted from an underlying condition, put the underlying condition on Line (b), and so on, until the full sequence is reported. **ALWAYS** enter the **underlying cause of death** on the lowest used line in Part I.

•For each cause indicate the best estimate of the interval between the presumed onset and the date of death. The terms "unknown" or "approximately" may be used. General terms, such as minutes, hours, or days, are acceptable, if necessary. **DO NOT** leave blank.

•The terminal event (for example, cardiac arrest or respiratory arrest) should not be used. If a mechanism of death seems most appropriate to you for line (a), then you must always list its cause(s) on the line(s) below it (for example, cardiac arrest **due to** coronary artery atherosclerosis *or* cardiac arrest **due to** blunt impact to chest).

• If an organ system failure such as congestive heart failure, hepatic failure, renal failure, or respiratory failure is listed as a cause of death, always report its etiology on the line(s) beneath it (for example, renal failure **due to** Type I diabetes mellitus).

•When indicating neoplasms as a cause of death, include the following: 1) primary site *or* that the primary site is unknown, 2) benign or malignant, 3) cell type *or* that the cell type is unknown, 4) grade of neoplasm, and 5) part or lobe of organ affected. (For example, a primary well-differentiated squamous cell carcinoma, lung, left upper lobe.)

•Always report the fatal injury (for example, stab wound of chest), the trauma (for example, transection of subclavian vein), and impairment of function (for example, air embolism).

PART II (Other significant conditions)

•Enter all diseases or conditions contributing to death that were not reported in the chain of events in Part I and that did not result in the **underlying cause of death**. See attached examples.

•If two or more possible sequences resulted in death, or if two conditions seem to have added together, report in Part I the one that, in your opinion, most directly caused death. Report in Part II the other conditions or diseases.

CHANGES TO CAUSE OF DEATH

Should additional medical information or autopsy findings become available that would change the cause of death originally reported, the original death certificate should be amended by the certifying physician by **immediately** reporting the revised cause of death to the State Vital Records Office.

ITEMS 33-34 - AUTOPSY

•33 - Enter "Yes" if either a partial or full autopsy was performed. Otherwise enter "No."

•34 - Enter "Yes" if autopsy findings were available to complete the cause of death; otherwise enter "No". Leave item blank if no autopsy was performed.

ITEM 35 - DID TOBACCO USE CONTRIBUTE TO DEATH?

Check "yes" if, in your opinion, the use of tobacco contributed to death. Tobacco use may contribute to deaths due to a wide variety of diseases; for example, tobacco use contributes to many deaths due to emphysema or lung cancer and some heart disease and cancers of the head and neck. Check "no" if, in your clinical judgment, tobacco use did not contribute to this particular death.

ITEM 36 - IF FEMALE, WAS DECEDENT PREGNANT AT TIME OF DEATH OR WITHIN PAST YEAR?

This information is important in determining pregnancy-related mortality.

ITEM 37 - MANNER OF DEATH

•Always check Manner of Death, which is important: 1) in determining accurate causes of death; 2) in processing insurance claims; and 3) in statistical studies of injuries and death.

•Indicate "Pending investigation" if the manner of death cannot be determined whether due to an accident, suicide, or homicide within the statutory time limit for filing the death certificate. This should be changed later to one of the other terms.

•Indicate "Could not be Determined" **ONLY** when it is impossible to determine the manner of death.

ITEMS 38-44 - ACCIDENT OR INJURY – to be filled out in all cases of deaths due to injury or poisoning.

•38 - Enter the exact month, day, and year of injury. Spell out the name of the month. **DO NOT** use a number for the month. (Remember, the date of injury may differ from the date of death.) Estimates may be provided with "Approx." placed before the date.

•39 - Enter the exact hour and minutes of injury or use your best estimate. Use a 24-hour clock.

•40 - Enter the general place (such as restaurant, vacant lot, or home) where the injury occurred. **DO NOT** enter firm or organization names. (For example, enter "factory", **not** "Standard Manufacturing, Inc.")

•41 - Complete if anything other than natural disease is mentioned in Part I or Part II of the medical certification, including homicides, suicides, and accidents. This includes all motor vehicle deaths. The item **must** be completed for decedents ages 14 years or over and may be completed for those less than 14 years of age if warranted. Enter "Yes" if the injury occurred at work. Otherwise enter "No". An injury may occur at work regardless of whether the injury occurred in the course of the decedent's "usual" occupation. Examples of injury at work and injury not at work follow:

Injury at work	**Injury not at work**
Injury while working or in vocational training on job premises	Injury while engaged in personal recreational activity on job premises
Injury while on break or at lunch or in parking lot on job premises	Injury while a visitor (not on official work business) to job premises
Injury while working for pay or compensation, including at home	Homemaker working at homemaking activities
Injury while working as a volunteer law enforcement official etc.	Student in school
Injury while traveling on business, including to/from business contacts	Working for self for no profit (mowing yard, repairing own roof, hobby)
	Commuting to or from work

•42 - Enter the complete address where the injury occurred including zip code.

•43 - Enter a brief but specific and clear description of how the injury occurred. Explain the circumstances or cause of the injury. Specify **type of gun** or **type of vehicle** (e.g., car, bulldozer, train, etc.) when relevant to circumstances. Indicate if more than one vehicle involved; specify type of vehicle decedent was in.

•44 -Specify role of decedent (e.g. driver, passenger). Driver/operator and passenger should be designated for modes other than motor vehicles such as bicycles. Other applies to watercraft, aircraft, animal, or people attached to outside of vehicles (e.g. surfers).

Rationale: Motor vehicle accidents are a major cause of unintentional deaths; details will help determine effectiveness of current safety features and laws.

REFERENCES

For more information on how to complete the medical certification section of the death certificate, refer to tutorial at http://www.TheNAME.org and resources including instructions and handbooks available by request from NCHS, Room 7318, 3311 Toledo Road, Hyattsville, Maryland 20782-2003 or at www.cdc.gov/nchs/about/major/dvs/handbk.htm

REV. 11/2003

FIGURE 3.1, cont'd



Cause-of-death – Background, Examples, and Common Problems

Accurate cause of death information is important
•to the public health community in evaluating and improving the health of all citizens, and
•often to the family, now and in the future, and to the person settling the decedent's estate.

The cause-of-death section consists of two parts. **Part I** is for reporting a chain of events leading directly to death, with the **immediate cause** of death (the final disease, injury, or complication directly causing death) on line a and the **underlying cause** of death (the disease or injury that initiated the chain of events that led directly and inevitably to death) on the lowest used line. **Part II** is for reporting all other significant diseases, conditions, or injuries that contributed to death but which did not result in the underlying cause of death given in **Part I**. **The cause-of-death information should be YOUR best medical OPINION.** A condition can be listed as "probable" even if it has not been definitively diagnosed.

Examples of properly completed medical certifications

CAUSE OF DEATH (See instructions and examples)

32. **PART I.** Enter the chain of events--diseases, injuries, or complications--that directly caused the death. DO NOT enter terminal events such as cardiac arrest, respiratory arrest, or ventricular fibrillation without showing the etiology. DO NOT ABBREVIATE. Enter only one cause on a line. Add additional lines if necessary.

Approximate interval: Onset to death

IMMEDIATE CAUSE (Final disease or condition ---------> resulting in death)
a. Rupture of myocardium — Minutes
Due to (or as a consequence of):

Sequentially list conditions, if any, leading to the cause listed on line a. Enter the **UNDERLYING CAUSE** (disease or injury that initiated the events resulting in death) **LAST**
b. Acute myocardial infarction — 6 days
Due to (or as a consequence of):
c. Coronary artery thrombosis — 5 years
Due to (or as a consequence of):
d. Atherosclerotic coronary artery disease — 7 years

PART II. Enter other significant conditions contributing to death but not resulting in the underlying cause given in PART I
Diabetes, Chronic obstructive pulmonary disease, smoking

33. WAS AN AUTOPSY PERFORMED? ☒ Yes ☐ No

34. WERE AUTOPSY FINDINGS AVAILABLE TO COMPLETE THE CAUSE OF DEATH? ☒ Yes ☐ No

35. DID TOBACCO USE CONTRIBUTE TO DEATH?
☒ Yes ☐ Probably
☐ No ☐ Unknown

36. IF FEMALE:
☒ Not pregnant within past year
☐ Pregnant at time of death
☐ Not pregnant, but pregnant within 42 days of death
☐ Not pregnant, but pregnant 43 days to 1 year before death
☐ Unknown if pregnant within the past year

37. MANNER OF DEATH
☒ Natural ☐ Homicide
☐ Accident ☐ Pending Investigation
☐ Suicide ☐ Could not be determined

CAUSE OF DEATH (See instructions and examples)

32. **PART I.** Enter the chain of events--diseases, injuries, or complications--that directly caused the death. DO NOT enter terminal events such as cardiac arrest, respiratory arrest, or ventricular fibrillation without showing the etiology. DO NOT ABBREVIATE. Enter only one cause on a line. Add additional lines if necessary.

Approximate interval: Onset to death

IMMEDIATE CAUSE (Final disease or condition ---------> resulting in death)
a. Aspiration pneumonia — 2 Days
Due to (or as a consequence of):

Sequentially list conditions, if any, leading to the cause listed on line a. Enter the **UNDERLYING CAUSE** (disease or injury that initiated the events resulting in death) **LAST**
b. Complications of coma — 7 weeks
Due to (or as a consequence of):
c. Blunt force injuries — 7 weeks
Due to (or as a consequence of):
d. Motor vehicle accident — 7 weeks

PART II. Enter other significant conditions contributing to death but not resulting in the underlying cause given in PART I

33. WAS AN AUTOPSY PERFORMED? ☒ Yes ☐ No

34. WERE AUTOPSY FINDINGS AVAILABLE TO COMPLETE THE CAUSE OF DEATH? ☒ Yes ☐ No

35. DID TOBACCO USE CONTRIBUTE TO DEATH?
☐ Yes ☐ Probably
☒ No ☐ Unknown

36. IF FEMALE:
☐ Not pregnant within past year
☐ Pregnant at time of death
☐ Not pregnant, but pregnant within 42 days of death
☐ Not pregnant, but pregnant 43 days to 1 year before death
☐ Unknown if pregnant within the past year

37. MANNER OF DEATH
☐ Natural ☐ Homicide
☒ Accident ☐ Pending Investigation
☐ Suicide ☐ Could not be determined

38. DATE OF INJURY (Mo/Day/Yr) (Spell Month): August 15, 2003

39. TIME OF INJURY: Approx. 2320

40. PLACE OF INJURY (e.g., Decedent's home; construction site; restaurant; wooded area): road side near state highway

41. INJURY AT WORK? ☐ Yes ☒ No

42. LOCATION OF INJURY: State: Missouri City or Town: near Alexandria
Street & Number: mile marker 17 on state route 46a Apartment No.: Zip Code:

43. DESCRIBE HOW INJURY OCCURRED:
Decedent driver of van, ran off road into tree

44. IF TRANSPORTATION INJURY, SPECIFY:
☒ Driver/Operator
☐ Passenger
☐ Pedestrian
☐ Other (Specify)

Common problems in death certification

The **elderly decedent** should have a clear and distinct etiological sequence for cause of death, if possible. Terms such as senescence, infirmity, old age, and advanced age have little value for public health or medical research. Age is recorded elsewhere on the certificate. When a number of conditions resulted in death, the physician should choose the single sequence that, in his or her opinion, best describes the process leading to death, and place any other pertinent conditions in Part II. If after careful consideration the physician cannot determine a sequence that ends in death, then the medical examiner or coroner should be consulted about conducting an investigation or providing assistance in completing the cause of death.

The **infant decedent** should have a clear and distinct etiological sequence for cause of death, if possible. "Prematurity" should not be entered without explaining the etiology of prematurity. Maternal conditions may have initiated or affected the sequence that resulted in infant death, and such maternal causes should be reported in addition to the infant causes on the infant's death certificate (e.g., Hyaline membrane disease **due to** prematurity, 28 weeks **due to** placental abruption **due to** blunt trauma to mother's abdomen).

When **SIDS** is suspected, a complete investigation should be conducted, typically by a medical examiner or coroner. If the infant is under 1 year of age, no cause of death is determined after scene investigation, clinical history is reviewed, and a complete autopsy is performed, then the death can be reported as Sudden Infant Death Syndrome.

When processes such as the following are reported, additional information about the etiology should be reported:

Abscess
Abdominal hemorrhage
Adhesions
Adult respiratory distress syndrome
Acute myocardial infarction
Altered mental status
Anemia
Anoxia
Anoxic encephalopathy
Arrhythmia
Ascites
Aspiration
Atrial fibrillation
Bacteremia
Bedridden
Biliary obstruction
Bowel obstruction
Brain injury
Brain stem herniation
Carcinogenesis
Carcinomatosis
Cardiac arrest
Cardiac dysrhythmia
Cardiomyopathy
Cardiopulmonary arrest
Cellulitis
Cerebral edema
Cerebrovascular accident
Cerebellar tonsillar herniation
Chronic bedridden state
Cirrhosis
Coagulopathy
Compression fracture
Congestive heart failure
Convulsions
Decubiti
Dehydration
Dementia (when not otherwise specified)
Diarrhea
Disseminated intra vascular coagulopathy
Dysrhythmia
End-stage liver disease
End-stage renal disease
Epidural hematoma
Exsanguination
Failure to thrive
Fracture
Gangrene
Gastrointestinal hemorrhage
Heart failure
Hemothorax
Hepatic failure
Hepatitis
Hepatorenal syndrome
Hyperglycemia
Hyperkalemia
Hypovolemic shock
Hyponatremia
Hypotension
Immunosuppression
Increased intra cranial pressure
Intra cranial hemorrhage
Malnutrition
Metabolic encephalopathy
Multi-organ failure
Multi-system organ failure
Myocardial infarction
Necrotizing soft-tissue infection
Old age
Open (or closed) head injury
Paralysis
Pancytopenia
Perforated gallbladder
Peritonitis
Pleural effusions
Pneumonia
Pulmonary arrest
Pulmonary edema
Pulmonary embolism
Pulmonary insufficiency
Renal failure
Respiratory arrest
Seizures
Sepsis
Septic shock
Shock
Starvation
Subdural hematoma
Subarachnoid hemorrhage
Sudden death
Thrombocytopenia
Uncal herniation
Urinary tract infection
Ventricular fibrillation
Ventricular tachycardia
Volume depletion

If the certifier is unable to determine the etiology of a process such as those shown above, the process must be qualified as being of an unknown, undetermined, probable, presumed, or unspecified etiology so it is clear that a distinct etiology was not inadvertently or carelessly omitted.

The following conditions and types of death might seem to be specific or natural but when the medical history is examined further may be found to be complications of an injury or poisoning (possibly occurring long ago). Such cases should be reported to the medical examiner/coroner.

Asphyxia
Bolus
Choking
Drug or alcohol overdose/drug or alcohol abuse
Epidural hematoma
Exsanguination
Fall
Fracture
Hip fracture
Hyperthermia
Hypothermia
Open reduction of fracture
Pulmonary emboli
Seizure disorder
Sepsis
Subarachnoid hemorrhage
Subdural hematoma
Surgery
Thermal burns/chemical burns

REV. 11/2003

FIGURE 3.1, cont'd



FUNERAL DIRECTOR INSTRUCTIONS for selected items on U.S.

Standard Certificate of Death (For additional information concerning all items on certificate see Funeral Directors' Handbook on Death Registration)

ITEM 1. DECEDENT'S LEGAL NAME
Include any other names used by decedent, if substantially different from the legal name, after the abbreviation AKA (also known as) e.g. Samuel Langhorne Clemens AKA Mark Twain, **but not** Jonathon Doe AKA John Doe

ITEM 5. DATE OF BIRTH
Enter the full name of the month (January, February, March etc.) Do not use a number or abbreviation to designate the month.

ITEM 7A-G. RESIDENCE OF DECEDENT (information divided into seven categories)
Residence of decedent is the place where the decedent actually resided. The place of residence is not necessarily the same as "home state" or "legal residence". Never enter a temporary residence such as one used during a visit, business trip, or vacation. Place of residence during a tour of military duty or during attendance at college is considered permanent and should be entered as the place of residence. If the decedent had been living in a facility where an individual usually resides for a long period of time, such as a group home, mental institution, nursing home, penitentiary, or hospital for the chronically ill, report the location of that facility in item 7. If the decedent was an infant who never resided at home, the place of residence is that of the parent(s) or legal guardian. **Never** use an acute care hospital's location as the place of residence for any infant. If Canadian residence, please specify Province instead of State.

ITEM 10. SURVIVING SPOUSE'S NAME
If the decedent was married at the time of death, enter the full name of the surviving spouse. If the surviving spouse is the wife, enter her name prior to first marriage. This item is used in establishing proper insurance settlements and other survivor benefits.

ITEM 12. MOTHER'S NAME PRIOR TO FIRST MARRIAGE
Enter the name used prior to first marriage, commonly known as the maiden name. This name is useful because it remains constant throughout life.

ITEM 14. PLACE OF DEATH
The place where death is pronounced should be considered the place where death occurred. If the place of death is unknown but the body is found in your State, the certificate of death should be completed and filed in accordance with the laws of your State. Enter the place where the body is found as the place of death.

ITEM 51. DECEDENT'S EDUCATION *(Check appropriate box on death certificate)*
Check the box that corresponds to the highest level of education that the decedent completed. **Information in this section will not appear on the certified copy of the death certificate. This information is used to study the relationship between mortality and education (which roughly corresponds with socioeconomic status). This information is valuable in medical studies of causes of death and in programs to prevent illness and death.**

ITEM 52. WAS DECEDENT OF HISPANIC ORIGIN? *(Check "No" or appropriate "Yes" box)*
Check "No" or check the "Yes" box that best corresponds with the decedent's ethnic Spanish identity as given by the informant. Note that "Hispanic" is not a race and item 53 must also be completed. Do not leave this item blank. With respect to this item, "Hispanic" refers to people whose origins are from Spain, Mexico, or the Spanish-speaking Caribbean Islands or countries of Central or South America. Origin includes ancestry, nationality, and lineage. There is no set rule about how many generations are to be taken into account in determining Hispanic origin; it may be based on the country of origin of a parent, grandparent, or some far-removed ancestor. Although the prompts include the major Hispanic groups, other groups may be specified under "other". "Other" may also be used for decedents of multiple Hispanic origin (e.g. Mexican-Puerto Rican). **Information in this section will not appear on the certified copy of the death certificate. This information is needed to identify health problems in a large minority population in the United States. Identifying health problems will make it possible to target public health resources to this important segment of our population.**

ITEM 53. RACE *(Check appropriate box or boxes on death certificate)*
Enter the race of the decedent as stated by the informant. Hispanic is not a race; information on Hispanic ethnicity is collected separately in item 52. American Indian and Alaska Native refer only to those native to North and South America (including Central America) and does not include Asian Indian. Please specify the name of enrolled or principal tribe (e.g., Navajo, Cheyenne, etc.) for the American Indian or Alaska Native. For Asians check Asian Indian, Chinese, Filipino, Japanese, Korean, Vietnamese, or specify other Asian group; for Pacific Islanders check Guamanian or Chamorro, Samoan, or specify other Pacific Island group. If the decedent was of mixed race, enter each race (e.g., Samoan-Chinese-Filipino or White, American Indian). **Information in this section will not appear on the certified copy of the death certificate. Race is essential for identifying specific mortality patterns and leading causes of death among different racial groups. It is also used to determine if specific health programs are needed in particular areas and to make population estimates.**

ITEMS 54 AND 55. OCCUPATION AND INDUSTRY
Questions concerning occupation and industry must be completed for all decedents 14 years of age or older. This information is useful in studying deaths related to jobs and in identifying any new risks. For example, the link between lung disease and lung cancer and asbestos exposure in jobs such as shipbuilding or construction was made possible by this sort of information on death certificates. **Information in this section will not appear on the certified copy of the death certificate.**

ITEM 54. DECEDENT'S USUAL OCCUPATION
Enter the usual occupation of the decedent. This is not necessarily the last occupation of the decedent. Never enter "retired". Give kind of work decedent did during most of his or her working life, such as claim adjuster, farmhand, coal miner, janitor, store manager, college professor, or civil engineer. If the decedent was a homemaker at the time of death but had worked outside the household during his or her working life, enter that occupation. If the decedent was a homemaker during most of his or her working life, and never worked outside the household, enter "homemaker". Enter "student" if the decedent was a student at the time of death and was never regularly employed or employed full time during his or her working life. **Information in this section will not appear on the certified copy of the death certificate.**

ITEM 55. KIND OF BUSINESS/INDUSTRY
Kind of business to which occupation in item 54 is related, such as insurance, farming, coal mining, hardware store, retail clothing, university, or government. DO NOT enter firm or organization names. If decedent was a homemaker as indicated in item 54, then enter either "own home" or "someone else's home" as appropriate. If decedent was a student as indicated in item 54, then enter type of school, such as high school or college, in item 55. **Information in this section will not appear on the certified copy of the death certificate.**

NOTE: This recommended standard death certificate is the result of an extensive evaluation process. Information on the process and resulting recommendations as well as plans for future activities is available on the Internet at: http://www.cdc.gov/nchs/vital_certs_rev.htm.

REV. 11/2003

FIGURE 3.1, cont'd

its completion depending on the circumstances the decedent is found in. This chapter discusses the various portions of the death certificate, definitions of terms used in death certification, and tips for surveillance of problem death certificates.

DEFINITION AND PURPOSE

A death certificate serves two main purposes: as a public document registering an official cause of death that allows estates to be closed and financial matters to be resolved, and as a vital record document in which national statistics are derived and monitored for public health trends for prevention of disease or health hazards. The document consists of demographic information such as official name, date of birth, address, social security number, parents' names, and location of death (Figure 3.2). The next main area consists of the cause and manner of death, as well as particulars of an accidental or unnatural cause of death. Community treating physicians may sign death certificates on their patients if they die of natural causes such as heart or lung disease, strokes, etc. All unnatural causes of death such as falls, suicides, drug intoxications or homicides must be certified by either a forensic pathologist/medical examiner or a coroner depending on the state law requirement. To prevent unnatural deaths from being missed or not examined by authorities, in many jurisdictions death certificates are monitored by the coroner or medical examiner office for causes that may be unnatural.



TYPE/PRINT
IN
PERMANENT
BLACK INK
FOR
INSTRUCTIONS
SEE HANDBOOK

CERTIFICATE OF DEATH

STATE FILE NUMBER

NAME OF DECEDENT:
For use by physician or Institution

DECEDENT

1. DECEDENT'S NAME *(First, Middle, Last)*
2. SEX
3. DATE OF DEATH *(Month, Day, Year)*
4. SOCIAL SECURITY NUMBER (of Deceased)
5a. AGE – LAST BIRTHDAY (Years)
5b. UNDER 1 YEAR: MOS. DAYS
5c. UNDER 1 DAY: HOURS MIN.
6. DATE OF BIRTH *(Month, Day, Year)*
7. BIRTHPLACE *(City and State or Foreign Country)*
8. WAS DECEDENT EVER IN U.S. ARMED FORCES? 1 ☐ Yes 2 ☐ No
9a. PLACE OF DEATH *(Check only one)*
HOSPITAL: 1 ☐ Inpatient 2 ☐ ER/Outpatient 3 ☐ DOA
OTHER: 4 ☐ Nursing Home 5 ☐ Residence 6 ☐ Other *(Specify)*
9b. FACILITY NAME *(If not institution, give street and number)*
9c. CITY, TOWN, OR LOCATION OF DEATH
9d. COUNTY OF DEATH
10. MARITAL STATUS—Married, Never Married, Widowed, Divorced *(Specify)*
11. SURVIVING SPOUSE *(If wife, give maiden name)*
12a. DECEDENT'S USUAL OCCUPATION *(Give kind of work done during most of working life. Do not use retired.)*
12b. KIND OF BUSINESS/INDUSTRY
13a. RESIDENCE – STATE
13b. COUNTY
13c. CITY, TOWN OR LOCATION
13d. STREET AND NUMBER OR RURAL LOCATION
CENSUS TRACT
13e. INSIDE CITY LIMITS? 1 ☐ Yes 2 ☐ No
13f. ZIP CODE
14. WAS DECEDENT OF HISPANIC ORIGIN? (Specify Yes or No—If yes, specify Cuban, Mexican, Puerto Rican, etc.) ☐ Yes 0 ☐ No
Specify, if yes:
15. RACE—American Indian, Black, White, etc. *(Specify)*
16. DECEDENT'S EDUCATION *(Specify only highest grade completed)*
Elementary/Secondary (0-12) College (1-4 or 5+)

PARENTS

17. FATHER'S NAME *(First, Middle, Last)*
18. MOTHER'S NAME *(First, Middle, Maiden Surname)*

INFORMANT

19a. INFORMANT'S NAME *(Type/Print)*
19b. RELATIONSHIP TO DECEASED
19c. MAILING ADDRESS *(Street and Number or Rural Route Number, City or Town, State, Zip Code)*

DISPOSITION

20a. METHOD OF DISPOSITION
1 ☐ Burial 2 ☐ Cremation 3 ☐ Removal from State
4 ☐ Donation 5 ☐ Other *(Specify)* ____________
20b. PLACE OF DISPOSITION *(Name of cemetery, crematory, or other place)*
20c. LOCATION—City or Town, State
21a. SIGNATURE OF FUNERAL DIRECTOR ▶
21b. LICENSE NUMBER OF FUNERAL DIRECTOR
21c. SIGNATURE OF EMBALMER ▶
21d. LICENSE NUMBER OF EMBALMER
22a. NAME AND ADDRESS OF FUNERAL HOME
22b. LICENSE NUMBER OF FUNERAL HOME

FIGURE 3.2
The top portion of the death certificate showing the required information that needs to be completed. The majority of this portion of the death certificate is completed by the funeral home when the family arrives to make arrangements. The investigator is largely responsible for originating the name, date, time and location of death, and location of where the death occurred. The forensic pathologist completes the cause and manner and how the injury occurred.

CAUSE OF DEATH

Cause of death is a medical description or diagnosis describing why someone is dead. Common causes of death are often abbreviated forms of medical terms (Figure 3.3). It is helpful to have a basic understanding of common medical diagnoses, anatomy and physiology to evaluate death certificates and converse

Common Medical Abbreviations	
AFIB	Atrial Fibrillation
ALS	Amyotrophic Lateral Sclerosis
AMI	Acute Myocardial Infarct
ASCVD	Atherosclerotic Cardiovascular Disease
Asp	Asphyxia
AVM	Arteriovenous Malformation
BFT	Blunt Force Trauma
c	with
CA	Cancer
CAD	Coronary Artery Disease
CABG	Coronary Artery Bypass Graft
CHD	Congenital Heart Disease
CHF	Congestive Heart Failure
CNS	Central Nervous System
CP	Cerebral Palsy/Chest Pain
CRF	Chronic Renal Failure
CT	Computerized Tomography (type of xray)
CV	Cardiovascular
CVA	Cerebrovascular Accident
DM	Diabetes Mellitus
DVT	Deep Vein Thromobosis
Dz	Disease
ESRD	End Stage Renal Disease
ETOH	Ethanol (alcohol)
GSW	Gunshot Wound
HTN	Hypertension (Hypertensive)
ICD	Implantable Cardioverter Defibrillator
ICH	Intracranial or Intracerebral
IHD	Ischemic Heart Disease
MI	Myocardial Infarction
MRI	Magnetic Resonance Imaging
MRSA	Methicillin Resistant Staphylococcus Aureus
Mult	Multiple
MVA	Motor Vehicle Accident
MVP	Mitral Valve Prolapse
(P)	Pending
RA	Rheumatoid Arthritis
s	without
SAH	Subarachnoid Hemorrhage
SDH	Subdural Hemorrhage
SIDS	Sudden Infant Death Syndrome
SUIDI	Sudden Unexplained Infant Death Investigation
URI	Upper Respiratory Infections
UTI	Urinary Tract Infection

FIGURE 3.3
A list of common abbreviations that will be encountered by the death investigator.

with physicians, nurses and emergency medical personnel. Common examples include:

- Myocardial infarction (heart attack)
- Acute intracerebral hemorrhage (stroke)
- Atherosclerotic cardiovascular disease (generalized hardening of the arteries)
- Chronic obstructive pulmonary disease (emphysema and chronic bronchitis)

The cause area has three lines—a, b, c—with each line followed by the term "due to." Vital records do not require that all three lines are completed, but a pathological cause must be listed somewhere within these lines, not just a physiologic one (Figure 3.4). Physiologic causes are, for example, cardiac arrest, hemorrhage, cardiac arrhythmia, respiratory arrest, and renal failure. All these mechanisms of death have an underlying pathologic cause that needs to be listed to be accurate and acceptable.

Here is an example where inaccurate information is supplied and will result in the doctor being called:

a. Cardiac arrest

If this had been certified as the following it would have been approved:

a. Cardiac arrest *due to*
b. Myocardial infarction

Note if placed in the reverse order it would not read properly and would be inaccurate. Since everyone dies of cardiac arrest (i.e., heart stopping), it could also have simply been completed as

a. Myocardial infarction



MEDICAL CERTIFI-
)N WITHIN 48
IS.

INSTRUCTIONS
I OTHER SIDE

CAUSE OF DEATH

28. PART I. Enter the diseases, injuries, or complications that caused the death. Do not enter the mode of dying, such as cardiac or respiratory arrest, shock, or heart failure. List only one cause on each line.

Approximate Interval Between Onset and Death

IMMEDIATE CAUSE (Final disease or condition resulting in death) → a. ______

DUE TO (OR AS A CONSEQUENCE OF):

Sequentially list conditions, if any, leading to immediate cause. Enter UNDERLYING CAUSE (Disease or injury that initiated events resulting in death) LAST

b. ______

DUE TO (OR AS A CONSEQUENCE OF):

c. ______

DUE TO (OR AS A CONSEQUENCE OF):

d.

PART II. Other significant conditions contributing to death but not resulting in the underlying cause given in Part I.

29a. WAS AN AUTOPSY PERFORMED?
1 ☐ Yes 2 ☐ No

29b. WERE AUTOPSY FINDINGS AVAILABLE PRIOR TO COMPLETION OF CAUSE OF DEATH?
1 ☐ Yes 2 ☐ No

FIGURE 3.4
(A) Demonstrates the three lines available to certify the cause of death. Not all three lines are necessary but at least one line must include a pathological cause of death.



TENNESSEE DEPARTMENT OF HEALTH

CERTIFICATE OF DEATH

STATE FILE NUMBER

TYPE/PRINT IN PERMANENT BLACK INK FOR INSTRUCTIONS SEE HANDBOOK

NAME OF DECEDENT: For use by physician or Institution

DECEDENT

1. DECEDENT'S NAME *(First, Middle, Last)*
2. SEX
3. DATE OF DEATH *(Month, Day, Year)*
4. SOCIAL SECURITY NUMBER (of Deceased)
5a. AGE — LAST BIRTHDAY (Years)
5b. UNDER 1 YEAR MOS. DAYS
5c. UNDER 1 DAY HOURS MIN.
6. DATE OF BIRTH *(Month, Day, Year)*
7. BIRTHPLACE *(City and State or Foreign Country)*
8. WAS DECEDENT EVER IN U.S. ARMED FORCES? 1 ☐ Yes 2 ☐ No
9a. PLACE OF DEATH *(Check only one)*
HOSPITAL: 1 ☐ Inpatient 2 ☐ ER/Outpatient 3 ☐ DOA
OTHER: 4 ☐ Nursing Home 5 ☐ Residence 6 ☐ Other *(Specify)*
9b. FACILITY NAME *(If not institution, give street and number)*
9c. CITY, TOWN, OR LOCATION OF DEATH
9d. COUNTY OF DEATH
10. MARITAL STATUS—Married, Never Married, Widowed, Divorced *(Specify)*
11. SURVIVING SPOUSE *(If wife, give maiden name)*
12a. DECEDENT'S USUAL OCCUPATION *(Give kind of work done during most of working life. Do not use retired.)*
12b. KIND OF BUSINESS/INDUSTRY
13a. RESIDENCE — STATE
13b. COUNTY
13c. CITY, TOWN OR LOCATION
13d. STREET AND NUMBER OR RURAL LOCATION
CENSUS TRACT
13e. INSIDE CITY LIMITS? 1 ☐ Yes 2 ☐ No
13f. ZIP CODE
14. WAS DECEDENT OF HISPANIC ORIGIN? (Specify Yes or No—If yes, specify Cuban, Mexican, Puerto Rican, etc.) ☐ Yes 0 ☐ No
Specify, if yes:
15. RACE—American Indian, Black, White, etc. *(Specify)*
16. DECEDENT'S EDUCATION *(Specify only highest grade completed)*
Elementary/Secondary (0-12) College (1-4 or 5+)

PARENTS

17. FATHER'S NAME *(First, Middle, Last)*
18. MOTHER'S NAME *(First, Middle, Maiden Surname)*

INFORMANT

19a. INFORMANT'S NAME *(Type/Print)*
19b. RELATIONSHIP TO DECEASED
19c. MAILING ADDRESS *(Street and Number or Rural Route Number, City or Town, State, Zip Code)*

DISPOSITION

20a. METHOD OF DISPOSITION
1 ☐ Burial 2 ☐ Cremation 3 ☐ Removal from State
4 ☐ Donation 5 ☐ Other *(Specify)* ______________
20b. PLACE OF DISPOSITION *(Name of cemetery, crematory, or other place)*
20c. LOCATION—City or Town, State
21a. SIGNATURE OF FUNERAL DIRECTOR ▶
21b. LICENSE NUMBER OF FUNERAL DIRECTOR
21c. SIGNATURE OF EMBALMER ▶
21d. LICENSE NUMBER OF EMBALMER
22a. NAME AND ADDRESS OF FUNERAL HOME
22b. LICENSE NUMBER OF FUNERAL HOME

REGISTRAR

23. REGISTRAR'S SIGNATURE ▶
24. DATE FILED *(Month, Day, Year)*

CERTIFIER

25a. PHYSICIAN — To the best of my knowledge, death occurred at the time, date, and place, and due to the cause(s) and manner as stated.
1 ☐ SIGNATURE AND TITLE OF PHYSICIAN ▶
25b. LICENSE NUMBER
25c. DATE SIGNED *(Month, Day, Year)*
26a. MEDICAL EXAMINER — On the basis of examination and/or investigation, in my opinion, death occurred at the time, and place, and due to the cause(s) and manner as stated.
2 ☐ SIGNATURE AND TITLE OF MEDICAL EXAMINER ▶
26b. LICENSE NUMBER
26c. DATE SIGNED *(Month, Day, Year)*

PHYSICIAN OR MEDICAL EXAMINER EXECUTING CERTIFICATE MUST COMPLETE AND SIGN MEDICAL CERTIFICATION WITHIN 48 HOURS.

27. NAME AND ADDRESS OF CERTIFIER (PHYSICIAN OR MEDICAL EXAMINER) *(Type/Print)*

CAUSE OF DEATH

SEE INSTRUCTIONS ON OTHER SIDE

28. PART I. Enter the diseases, injuries, or complications that caused the death. Do not enter the mode of dying, such as cardiac or respiratory arrest, shock, or heart failure. List only one cause on each line.

Approximate Interval Between Onset and Death

IMMEDIATE CAUSE (Final disease or condition resulting in death) ⟶ a. ______________
DUE TO (OR AS A CONSEQUENCE OF):
Sequentially list conditions, if any, leading to immediate cause. Enter UNDERLYING CAUSE (Disease or injury that initiated events resulting in death) LAST
b. ______________
DUE TO (OR AS A CONSEQUENCE OF):
c. ______________
DUE TO (OR AS A CONSEQUENCE OF):
d.

PART II. Other significant conditions contributing to death but not resulting in the underlying cause given in Part I.
29a. WAS AN AUTOPSY PERFORMED? 1 ☐ Yes 2 ☐ No
29b. WERE AUTOPSY FINDINGS AVAILABLE PRIOR TO COMPLETION OF CAUSE OF DEATH? 1 ☐ Yes 2 ☐ No
30. MANNER OF DEATH
1 ☐ Natural 5 ☐ Pending Investigation
2 ☐ Accident
3 ☐ Suicide 6 ☐ Could not be Determined
4 ☐ Homicide
31a. DATE OF INJURY *(Month, Day, Year)*
31b. TIME OF INJURY M
31c. INJURY AT WORK? 1 ☐ Yes 2 ☐ No
31d. DESCRIBE HOW INJURY OCCURRED
31e. PLACE OF INJURY—At home, farm, street, factory, office building, etc. *(Specify)*
31f. LOCATION (Street and Number or Rural Route Number, City or Town, State)

BIRTH NO. ______________

PH-1659
REV. 2-93

RDA 1399

B

FIGURE 3.4, cont'd

(B) Shows the five options for manner of death that are available in most states. "Natural" is the only box that may be certified by private treating physicians. The remaining boxes are to be used only by coroner/medical examiner offices.

It could then be approved by vital records immediately. Many states have mandates for how long a death certificate may be outstanding and unsigned by a private physician. Burials cannot occur without a valid death certificate signed by a physician to allow the proper burial or cremation permits to be issued by vital records departments. It is helpful to review your state law requirements for death certificates and death reporting to the coroner/medical examiner office, and have the laws pertaining to your state readily available for reference.

MANNER OF DEATH

Manner of death is in one of five classifications: natural, accident, suicide, homicide, or undetermined. Some states have an additional category called **therapeutic misadventure** when the death is related to a medical intervention. Private physicians are only allowed by state law to certify natural deaths. The other manners of death are reserved for the coroner or forensic pathologist. It is not always easy to make a distinction to a medical certainty between two or more manners, and in that instance, undetermined is used. In most jurisdictions this classification is used less than 5% of the time.

The distinction between accident, suicide, and homicide is based largely on the concept of intent of an action that caused the death.

INFORMATION NEEDED FOR COMPLETION

It is important to obtain specific information for the death certificate at the time of the investigation, such as the decedent's legal name and proper spelling and date of birth; date and time of death pronouncement; location of death; date, time, and location of incident; home address; next of kin; and social security number if known. Medical history, medications, and physicians are also useful information to be obtained or seized. See Figure 3.5.

INVESTIGATION OF PROBLEMATIC DEATH CERTIFICATES

As part of the certification process, many states are progressing to electronic (online) death certification. This is a wonderful advancement, as it allows data to be transmitted easily between agencies and speeds up the process. It also allows death investigators to review death certificates for problematic causes of death and allow investigations to move forward more promptly. The following causes are common ones that should be further investigated by reviewing medical records and/or discussing the cause with the signing physician.

Pneumonia

Pneumonia can cause death alone or as a complication of multiple other illnesses, including trauma, and is a symptom of health department reportable diseases. When this is the listed cause, it is best to speak with the signing



DATE RPTD.

RPTD. BY

TRANSPORT

TIME RPTD. /

TIME COMPLT. /

FIELD AGENTS /

DOCTOR

INVESTIGATOR

COUNTY PROCEDURE DATE FORENSIC ANTHRO DENTIST

CASE NUMBER

NAME FN MI LN

ALIAS M S W D OCC

ADDRESS CITY STATE ZIP

DOB AGE RACE SEX S.S.N.

HT (cm) (inches) WT (kg) (lbs) HC EC

NOK FN LN *REL* PHONE

ADDRESS CITY STATE NOTIFIED Y N

ID (MEANS & NAME)

LOCATION FOUND

REASON ME CASE

MED. HX

MEDS.

AGENCY CASE # OFFICER

INJURY LOCATION WORK Y N

DATE TIME DRIVER PASSENGER PEDESTRIAN

WHERE DID DEATH OCCUR? HOSP. ER OR INPT AT SCENE UNKNOWN

LSA DATE TIME LOC. BY

FD. DATE TIME LOC. BY

PRN. DATE TIME LOC. BY

FUNERAL HOME BY RELATION

PHOTOS: OME ID Y N EXAMINATION OME Y N AGENCY Y N

FINGERPRINTS: PALMS FOOT RADIOGRAPHS

RELEASED BY RECEIVED BY

FIGURE 3.5
An example of an office intake sheet that after completed will contain the information necessary to complete the demographic and injury sections of a death certificate. The cause and manner of death are determined following examination by the forensic pathologist. Examples of intake sheets can be found in the Appendix.

Case Study

A young male is found with a gunshot wound to his head in a room and a gun nearby on the floor. The cause of death is gunshot wound to the head. However, the manner of death depends on the scenario. One scenario might be that the gun was picked up by a five-year-old child and the gun went off, striking the decedent. In that instance, a five-year-old child would have little knowledge of firearms and the manner would be accidental. Another scenario could be the decedent was shot during a home invasion and the manner of death would be homicide. A third scenario is the gun was placed by the decedent against his head and the manner would be suicide.

The intent is the important distinction to determine the manner. In suicide, the intent is directed against one's self with a willingness to die due to the action. Homicide is the intent and willful action to take another person's life. Accident is where there was no intent to hurt someone but the action resulted in death. The determination of manner by the coroner/medical examiner is distinct from a judicial sense of determining this. Legal definitions may vary and allow the judicial system to impart manslaughter and various degrees of homicide (e.g., first degree, second degree, third degree) based on circumstances of the investigation.

If a gun is used to cause injury to another person, many factors will be needed to determine intent. In the first scenario, the age of the child, the child's knowledge of guns including any formal training, the mental capacity of the child to determine right from wrong, and the child's statements as to how the injury occurred will all need to be understood to make the best judgment for the manner. Normal development reasoning of right and wrong should be accomplished by six to eight years old. Even so, the legal system may bring homicide charges regardless of the determination on the death certificate since they use different criteria than the criteria used by medicine. They also have divided the homicide category into involuntary manslaughter, voluntary manslaughter, first-degree murder, second-degree murder, and third-degree murder. The court system will take multiple factors into account, including previous juvenile offenses, the type of injury, and the heinous nature of the crime, to decide whether the child is tried as an adult or a juvenile. Children have been sentenced to life in prison, and some as young as 13 years old tried as an adult. If the scenario is complex and multifactorial, an undetermined manner should be considered for the death certificate and the courts can decide what charges, if any, are required.

physician and rule out trauma, such as a head injury, motor vehicle accident, fall, or an unexpected illness in a previously healthy person.

Brain hemorrhage

Brain hemorrhages can be of various types and are commonly listed as intracerebral hemorrhage, subdural hemorrhage, subarachnoid hemorrhage, cerebral hemorrhage, or stroke. Some of these can occur due to underlying disease such as hypertension (high blood pressure), or to falls or minimal trauma, especially if the person is on blood thinners (anticoagulants). The distinction is important to make to properly certify the cause and manner of death. It may mean that survivors receive certain benefits if the death is certified as an accident.

The easiest way to begin to sort out the manner is to retrieve the emergency responder report for symptoms the decedent was experiencing, emergency department notes, and CT or MRI scan reports of the brain. It must be noted, however, that a body of literature exists as to the large number of missed diagnoses via these test results. When in doubt, the decedent may need to be physically examined externally for signs of injury, as well as performing an examination of the brain for the site of origin of the hemorrhage. In general, basal ganglia, intracerebellar, or brainstem hemorrhages can be seen commonly in hypertension. Subdural hemorrhages should be considered accidental in origin until further information is obtained. Subarachnoid hemorrhages may be due to natural or accidental origin and may depend on scene investigation or medical history. Distribution of scalp injuries with brain injuries may also aid in distinguishing accidental, homicide, or natural manners of death.

Fractures (hip, rib, spine, osteoporotic, pathological)

Fractures are most commonly due to falls and most need to be reported to the death investigator for evaluation and jurisdiction determination. Factors used to determine if the death is due to accident or natural disease with underlying health problems can be difficult. These factors include the time duration between the incident and death, the mechanism causing death (e.g., pneumonia, pulmonary embolus, myocardial infarction, aspiration of food, decubitus ulcers, sepsis), and if the decedent had a previously active lifestyle that never returned to a normal state following the incident. Some offices make an arbitrary timespan (e.g., six to eight weeks following injury) for these complications to occur due to the accident versus the preexisting underlying disease processes. Basically, each case must be investigated and evaluated on an individual basis.

Other factors that may explain why the fracture occurred with minimal trauma (sitting down, being turned in bed) are osteoporosis (a loss of calcium in bone due to aging) or underlying metastatic bone cancer. Either of these may cause bones to be weak and brittle. Depending on the investigation, the manner may be ruled as a natural manner of death.

Falls

Falls and accidental deaths should be suspected or investigated in alcoholics, the elderly, or those with bruises over bony prominences like the knees, elbows, ribs, and chest, or deformity of the arms or legs, especially shortening and external rotation of a leg. It may require X-rays and/or an autopsy examination to distinguish the cause of death.

Remote motor vehicle accidents, gunshot wounds, or head injuries

Some patients experience a head or spinal injury and survive many months with deficits, eventually dying of a natural disease such as pneumonia, sepsis, or other infection. It is important to recognize these cases so that the death certificate is certified properly and any remaining evidence (old bullets) may be recovered. The bullet may serve as crucial evidence to relate a gun to the injury.

There is no statute of limitations in any U.S. state, so if the perpetrator can be linked to the death, he or she may be charged with homicide. In some states, the original charge of assault may be upgraded to murder if the death is linked to the original injury.

The injury may be very remote and the circumstances of the injury (location, jurisdiction, dates, how it occurred) may not be easily found in medical records, as most hospitals only keep their records for seven years before destroying them. The family can serve as a valuable resource in locating this information, so that follow-up with any necessary law enforcement agencies can be done. It is helpful to obtain recent hospital discharge summaries, X-ray reports, and more recent progress notes from care facilities to evaluate the extent of the injuries and relationship to the original injury. Basically, if the final disease process is related to the original injury, the cause of death is viewed as a complication of the injury regardless of interval. This is where the difficulty lies—finding the connection to the injury as well as defining the disease process resulting in death. The thought process involves whether the decedent's life was shortened by the injury or the life was significantly altered from the way it existed before the accident.

Seizures

Seizures are due to an irregularity of the brain's electrical current causing abnormal movements and breathing. They may result in sudden death. Seizures can also be a pathologic disease process with an unknown etiology. They can be a symptom of another disease, a final terminal death event, alcohol or drug withdrawal, or previous injury to the brain. Because the diagnosis is nonspecific, most of these death certificates need to be investigated further or examined at the office for a possible autopsy.

Children

Pediatric death certificates need to be scrutinized closely for causes that may need to be evaluated through an autopsy or at least external examination by the forensic pathologist. There may be infectious causes that have not been defined by hospitalization, putting fellow family members or the community at risk for a preventable outbreak, a previous injury with a prolonged survival period, ingestion of substances, or injuries or neglect by caregivers or as wards of the state. Conversations with the reporting party may help elicit the information necessary to determine if jurisdiction needs to be enforced.

Miscarriages

Fetal deaths can be very confusing. It is best to review your current state law definition of a fetal death, age of viability, and birth definition. In general, fetal deaths are usually defined as those under 20 weeks' gestation and 350 grams in weight (this may vary slightly depending on your state).

Live births are those with the infant taking a breath and/or having a heartbeat. Some states add pulsations of the umbilical cord to indicate live birth. If the infant has any of these, it requires both a birth certificate and death certificate. The birth certificate will be completed by the delivering physician, and the death certificate can be completed by the forensic pathologist or coroner.

Fetal death certificates also exist for those cases where there was no sign of life before or after 20 weeks of gestation. The complicated distinction comes if the infant is of the age of viability (>20 weeks gestation and/or 350 grams) and there is an incidence of trauma (homicide or accident), drug use of the mother, or other complication resulting in early delivery. Then, the actual age of the **fetus** can be important, and is assessed not only on the weight or computed gestational age, but also by examination parameters by the forensic pathologist, such as foot length, hand length, body weight and length, examination of the placenta, toxicology testing of the fetus, etc. It may be necessary to access the maternal prenatal and delivery records, including toxicology and culture results, to aid the investigation of the death of the fetus. If the mother is living, access to her records can be challenged as a privacy issue. Because the lives of the fetus and mother are so intertwined, it is usually granted but must be recognized if problems arise or state laws prohibit access.

Therapeutic abortion death certificates may also be reviewed routinely by the death investigator. The death investigator needs to be knowledgeable about the state laws governing the gestational age and weight with which they may legally occur.

Children of mixed heritage and race are generally classified by the race of the mother. This was decided by the Standards for Classification of Federal Data on Race and Ethnicity in 1989. It is a statistical fact only; it is not meant to be dogmatic and is only used as a general guideline.

On a similar topic of difficult questions on a death certificate is the gender. On infants it is determined by the internal genitalia. On those seeking transgender, it is usually decided based on the birth certificate classification unless a legal proceeding has been done by the courts to convert the gender designation. In any of these questions, the local health department can update and advise specific issues.

CREMATION AUTHORIZATIONS

Many states require death certificates to be reviewed by the coroner or medical examiner office to evaluate the causes of death for potential causes that were not previously reported for jurisdiction. The review is done to identify causes where the certificate implies an unnatural cause of death or public health hazard falling under the death investigation laws. Prior to authorizing these deaths for cremation or transportation out of the country, any discrepancies need to be clarified by obtaining medical records or conversing with the certifying physician for particulars on the cause of death.

REFERENCES

[1] Hanzlick R, editor. Cause of Death Statements and Certification of Natural and Unnatural Death. College of American Pathologists; 1997. Retrieved from https://netforum.avectra.com/temp/ClientImages/NAME/8c58e7e9-b2fa-44a9-8d1b-3085cd14bf25.pdf. [August 2013].

[2] Hanzlick R. Cause of Death Tutorial. Fulton County Medical Examiner; 1996. Retrieved from http://www.fultoncountyga.gov/cause-of-death-tutorial. [August 2013].

[3] National Vital Statistics System. Center for Disease Control and Prevention. Retrieved from http://www.cdc.gov/nchs/nvss.htm. [August 2013].

[4] National Death Certificate. US standard certificate of death; 2003. Center for Disease Control and Prevention. Retrieved from http://www.cdc.gov/nchs/data/dvs/death11-03final-acc.pdf. [August 2013].

CHAPTER 4

Time of Death

Learning Objectives

- Discuss the factors used to estimate the time of death.
- Illustrate by examples what observations need to be recorded by the investigator to assist with determining the time of death.
- Explain the general methods used to collect insects for entomology consultation.
- Discuss the environmental conditions that can alter the timeline for estimating the time of death.
- Discuss the types of observations of plants at an outdoor scene that may aid estimations for the time of death.

Key Terms

Livor
Rigor
Adipocere
Instar
Mummification
Saponification

Chapter Summary

In this chapter the various physiologic changes that occur within the body during and after death are discussed. These changes proceed through a progression of changes that can be used to estimate the time of death. These parameters are only an estimate and are highly dependent on temperature, body habitus, and other environmental factors. The assessment factors each follow a continuum that needs to be recorded by the investigator prior to the body being removed from the death site. When taken as a whole, these values and investigative information are used to make the best time determination in an unwitnessed death. Various investigative observations may be helpful to add more information concerning the postmortem interval as well as the decedent's lifestyle. Collection of insects, plants, and photographs may be necessary in some cases to aid this determination.

INTRODUCTION

With death, multiple body mechanisms fail and cause various body changes that are used to estimate time of death and the position of the body. This chapter discusses the physiology of these body changes and how these changes can be utilized in a death investigation.

PHYSIOLOGY OF DEATH

In its normal state, the body's heart is beating, circulating blood throughout the tissues, and the lungs exchange carbon dioxide waste for fresh oxygen. Oxygen is then used to maintain the cellular energy state of the body through the use of energy packets called ATP (adenosine triphosphate). When a packet is depleted it is converted to a low-energy state called ADP (adenosine diphosphate) and is in need of oxygen to reform into renewed ATP. ATP is necessary to run multiple microscopic cellular components that maintain the status quo of internal cell versus external cell concentrations of various minerals, enzymes, amino acids, fats, glucose, etc. Without ATP, all the functions of the body's cells fail, causing them to die, which is called **necrosis** in the living body and **autolysis** when cell death occurs after death.

Death is usually defined by individual state law, but in general, includes the cessation of both respiration and cardiac activity. Since the advent of advances in medicine with extended life support, most states have included guidelines as to what constitutes brain death. It was necessary to do so since medicine is now able to maintain someone on artificial respiration for a prolonged period, allowing respiration and cardiac activity to proceed without meaningful brain function. Respiration and cardiac functions are largely centered in the primitive area of the brainstem, whereas critical thinking and awareness are centered in the cortex. It is possible to lose the majority of the cortex and maintain the primitive cardiac and respiratory functions. It is also possible to appear to have no cortical function and be locked in, but unable to communicate in a verbal fashion. The stringent criteria used to pronounce brain death were developed to recognize these differences and make an accurate determination prior to removing life support.

Rigor

Rigor mortis, commonly known as **rigor**, is the postmortem muscle stiffening of the body. It is created because the lack of oxygen to the cells results in lower levels of ATP in the body. ATP is needed for muscle cells to maintain their delicate balance of various chemicals, including calcium used for muscle contraction. The lack of ATP causes the body cells to leak calcium around muscle fibril bundles. This allows the muscle fibrils to bind by cross-linking, resulting in the muscle contracting (i.e., setting) in its present position. ATP is needed to restore the calcium equilibrium, but without oxygen, the muscle bundles bind but are unable to reset [1]. The body remains in the muscular contraction state it was in at the time of death. With death, the body will assume a position of relaxation toward gravity or the object it is resting on.

The muscle bundles will maintain the contraction for a period of time until the muscle fibrils begin to deteriorate, releasing the cross-linking. Contraction is first detected in the smaller muscles of the face or hands and then extends to larger muscles of the arms and legs where it remains the longest. It eventually passes and the muscles will become relaxed, first noted in the small muscles then proceeding to the larger ones. The amount of muscle mass a person has will increase the duration or strength of the rigor (e.g., a body builder has more prolonged rigor than a tiny elderly woman or baby). Also, exercise just prior to the time of death will cause the rigor to begin more rapidly because of the already depleted ATP within the body.

Descriptive terms used are **full rigor**, **easily broken rigor**, and **absent rigor**. Full rigor is seen at the height of muscle rigidity, and at average household temperatures it occurs about six to eight hours after death. In the early postmortem state and after the peak period it is described as easily broken. Eventually as the body progresses toward a state of early decomposition, it will become absent. It is also absent in the immediate period following death. Full rigor lasts three to four hours in a normal adult, but this depends on a number of factors, including the ambient (surrounding) temperature if in an outdoor environment, a building, a car, a residence, or the shade of a tree. Another factor is the amount of body fat or clothing insulating the body. Environmental heat has the same effect and cooling decreases the rate of decomposition onset. A body that is moved then placed inside a body cooler wrapped in blankets and wearing heavy clothing will continue to decay because of the insulating properties of the clothing and blankets from the cooler air.

Moving a body also affects the determination of the time interval. In the movement process, small bundles are broken and may reset their cross-links or they may break prematurely, which disturbs the postmortem time estimate. The best time to assess rigor is prior to the body being moved. It is important to assess and note the extent of rigor, body warmth, livor, and environmental temperature prior to the body being placed into a body bag.

Livor

Livor mortis, commonly known as **livor**, is the postmortem settling of blood. When the heart stops beating the blood no longer circulates, causing it to pool within the capillaries and small vessels closest to gravity. Because of the cellular disruption, clotting then begins. In the early postmortem interval, the blood will remain liquid, and if the body is moved, the blood will partially realign in the new position of gravity. This pattern is useful to determine if a body was moved prior to its being seen by the death investigator.

If a body is viewed by the investigator with anterior lividity but lying on its back, then the body had initially collapsed in the face-down position. There are many explanations why the body may have been moved. It may be done by the person who discovered the body to assess the decedent's condition; emergency medical or law enforcement personnel; or perpetrators of a potential crime. For transport, the majority of bodies are placed on their back inside the body bag so they may assume a posterior lividity pattern in addition to the initial one. It is helpful to make note of livor routinely at the autopsy and review photographs of how the body was positioned at the death scene.



FIGURE 4.1
(A) Generalized lividity over the back of someone found lying on his back. (B) When the skin is pressed in the early postmortem period, the lividity will dissipate and appear pale in the pressure area.

Lividity is not usually uniformly present on the side of gravity. In areas where the body has been resting against an object, lividity is prevented due to the pressure on the surface. It will be seen as a pale area surrounded by pink (Figure 4.1). An example would be an infant found face down in a crib. He or she will demonstrate lividity anteriorly and can have pale areas on a cheek or over the face and mouth areas. When discovered, a caregiver usually moves the baby and resuscitative efforts are begun. Lividity may then begin to change posteriorly and the blanched pale areas will begin to fade. It is very important to photograph the infant's face upon arrival since sometimes the lividity can change rapidly and the pale areas may not be visible later.

The liquid condition of the blood remains for the first three to four hours following death and becomes relatively fixed in position after six to eight hours. Following that, it will no longer move from the initial position. Terms to describe lividity are **blanchable** and **fixed lividity**. Blanchable refers to the early postmortem period where pressure applied by the investigator's hand will dispel the blood in an area of dependent livor and appear uniformly pale, then slowly return to pink. Eventually, the lividity becomes fixed into place and unable to be displaced by applied pressure.

Factors affecting the onset of lividity include the condition of circulation at the period near death. Some people die slowly with the heart gradually assuming a slow heartbeat and the body will begin to pool blood in the peripheral extremities and back prior to death.

Livor may have different colors. Usually it is light pink, and with time assumes a dusky pink. When a body is placed in a cold refrigerator or in an outside cold environment, it becomes bright pink. Bright pink is also seen with carbon monoxide and cyanide poisoning. Poisons such as potassium chlorate, phosphorus, and nitrites give a brown-colored lividity. Hydrogen sulfide gives a bluish-green coloration.

Case Study

A body is found in a field lying on her back with the legs and arms flexed at the elbows and knees. The decedent was noted to have left-side livor. The rigor was present throughout the body and the livor was fixed on the left torso. A gunshot wound was noted of the left scalp.

These findings indicate the body has been moved. Rigor assumes the position of gravity and upward flexion of the extremities is not consistent with the death occurring at that site. Fixed lividity on one side of the body is also inconsistent with the body being on her back at the time of death, confirming the body was moved. The body was in the position for a period of at least six to eight hours or longer prior to being placed into the field where it was found.

Temperature

Environmental temperature has a large effect on the progression of postmortem change. Heat causes rigor and livor to pass through their respective stages more rapidly, and cold slows the progression. Direct sunlight with an environmental temperature over 100 °F will result in the onset of decomposition within a matter of a couple of hours. Cold, such as snow, will slow the onset of decomposition initially until thawing begins. Cold can result in freezer burn–type areas where the body has rested on the ground.

Decomposition

Without preservation a body will deteriorate and progress into an advanced postmortem state. If the body is exposed to the sunlight and air, it progresses more rapidly than if it were buried or within water [4]. This is partially related to the added benefit of insects and carnivores. Insects infest a body in an orderly fashion and particular subspecies are related to the locality within the United States. Generally, flies are the first infesters and they may lay their eggs on fresh bodies. Flies are especially attracted to areas of injury.

The first stage of decomposition is venous marbling (Figure 4.2). This occurs when the blood decomposes within the vascular system and produces brown vessel arborization on the skin. This is followed by red-green discoloration of the skin with fluid-filled skin blebs of decomposition fluid. Rupture of capillaries within the mouth and nose cause oozing of thick dark-red decomposition fluid. The body then progresses to black-green discoloration with subcutaneous gas formation containing hydrogen sulfide gas. This is most pronounced in the face, torso, and genitalia with distortion of facial features.

Skin slippage is evident with glove formation of the hands and feet where actual sheets of skin peel from the body (Figure 4.3). The hand glove can be used to obtain fingerprints to aid identification. The easiest way to do this is to place the entire glove or, if fragmented, the fingertips over the investigator's gloved hand and roll the fingertips onto the ink and put them onto the fingerprint cards. It



FIGURE 4.2
One of the early stages of decomposition called venous marbling, which is caused by decomposing blood within the vascular tree.



FIGURE 4.3
The beginning of skin slippage and filling of skin blebs by noxious-smelling decomposition fluid.

may take multiple attempts to get a good print. The decomposed hands may be greasy with decomposition fluid and the tips can be blotted with alcohol swabs. Wiping or scraping can destroy the print ridges or tear the skin, so the cleaning needs to be done gently.

The subcutaneous blistering and fluid accumulation along with the skin slippage occurs because the bacteria are breaking down the body fat and proteins into by-products that produce foul-smelling gases, including hydrogen sulfide and methane, which bloat the body. This accumulates inside the body as well as within the skin. The skin begins separating and the fluids accumulate under the skin and drain onto the ground. The blistering makes some mistakenly think the skin has been burned, but this is not true. The decomposition fluid is watery, red-brown, and the early novice investigator may think it is frank blood. Decomposition fluids tend to be more watery or have a mucous slimy quality. Blood when decomposed appears more as a tarry black material. Distension of the genitalia, widening of the anus, and even expulsion of the bowel occurs as a result of the decomposition, and is not necessarily a sign of trauma. Sexual assault swabs can be obtained in these cases, but the bacteria may render the results unable to be interpreted.

Mummification is another decomposition process that occurs in hot, arid environments where the body is partially protected from the sun and the air is blowing across the body and drying it. In this process the skin shrinks and becomes leather-like with a dry, musty smell. Because of the shrinkage, the facial beard may appear to grow and nails lengthen when in reality it is an artifact due to drying. Internal examination will show dried, shrunken organs and no residual body fluids. Identification becomes a challenge because the hands are dried and prints are unavailable. The hands can be processed using various techniques like sodium hydroxide rehydration or soaking the hands in a soap solution to soften them and reinflate the fingertips to allow for fingerprints. When the tips are able to be manipulated, a needle and syringe containing formalin, water, or tissue builder can be inserted under the skin to gently inflate and expand the wrinkles from the surface. The fingertips may need to be gently massaged to distribute the fluid under the surface. It is important not to overinflate the surface since it distorts the fingerprint ridges.

Saponification is a process of decomposition in cold, wet environments, such as cold lakes, rivers, or basements, and is called **adipocere** (Figure 4.4). It is a form of soap formation by chemically changing the composition of the body fat. The surface of the skin appears chalky white and, when extensive, the skin and soft tissue crumble like plaster. Bodies found in lakes after many years can still retain extensive skin surface with this appearance.

Mold formation occurs in closed environments such as caskets or closets where the body is protected from insects. The mold forms a micro environment within the closed space and the body can be relatively well preserved for years after death.

The postmortem interval to reach either wet decomposition or mummification varies and it can be difficult to assign a definite time. A common estimate is one



FIGURE 4.4
Adipocere formation of the skin and subcutaneous tissue is a form of decomposition found in cold, wet environments.

week in the open air equals two weeks in water, equals eight weeks underground. Skeletal remains are usually devoid of tissue by six months with scavenger activity. The bones will retain odor for at least a year depending on the environment. Recovery of scattered skeletal remains due to animal scavenging can be challenging but may follow terrain features or animal travel routes [3].

There are multiple tales associated with death. One is that the fingernails grow after death, but this is merely an illusion due to shrinkage of the skin on the fingertips due to dehydration. The beard and hair have also been said to grow after death, but the same skin shrinkage accounts for this apparent change. Some are afraid to open the eyes or ask if viewing the eyes will reflect what they last saw and this cannot be done. The eyes work with a complex system integrated with brain activity to register what is seen and our vision of objects are not visible within the eye.

POSTMORTEM CARNIVORE ACTIVITY

Wild and domestic animals including mammals and birds will feed upon a human cadaver. Exposed areas, such as face and hands as well as bloody areas, are prime focus areas. Large carnivores will also select the large muscle mass



FIGURE 4.5
(A) A typical area of carnivore activity centered around the mouth of a decedent. (B) Loss of flesh from the upper extremity and chest on a decedent from exposure to wild animal activity. Flesh and muscle areas exposed outside of clothing are common sites.

areas of the thighs, legs, and abdomen. This can make identification challenging and may necessitate dental comparison for identity. See Figure 4.5 for examples.

POSTMORTEM INSECT LIFE CYCLE

The first insects to attack a body are flies, usually blowflies. Blowflies are present in the environment to approximately 52 °F [2]. The flies are very orderly in their development from eggs to first through third **instar** stages, to pupa, then hatching as a mature fly. The cycle varies in length depending on the warmth of the environment, but generally in warm weather it takes 8 to 10 days to reach pupa stage (Figure 4.6). As the flies are feeding on the body, various beetles and other insects also feed on the remains (Figure 4.7). Collection and preservation of insects at the point when the body is discovered can allow a forensic entomologist to give an estimate of the postmortem interval. This collection is not always necessary but may be needed in suspected homicides. Because the insects feed on the body, they can be ground and liquefied for a qualitative drug screen if no other fluids or tissue is available.

EMBALMING

Embalming is the practice of removing the blood from the vascular system and replacing it with formalin. In doing so, the evaluation of lividity and rigor are


The blow fly life cycle has six parts: the egg, three larval stages, the pupa, and adult.
130 hours
22 hours
At 70 degrees F, each stage in a blow fly's life takes a known amount of time to complete...
143 hours
27 hours
23 hours
A
B
C
D

FIGURE 4.6
(A) The typical life cycle of a blowfly as it matures from a maggot to a full-grown fly. (B, C) It passes through three enlarging cycles of maggots called instars and pupae. (D) The adult blow fly is capable of laying eggs on decomposing tissue to repeat the cycle.
Source: Cleveland Museum of Natural History, http://www.nlm.nih.gov/visibleproofs/galleries/technologies/blowfly.html.

no longer able to be assessed. The embalming procedure involves incisions at the base of the neck to localize the carotid artery and jugular vein. Incisions are also made in the right and left groins to utilize the femoral arteries and veins. Formalin is pumped into the arterial system, which diffuses into the soft tissue, preserving it (Figure 4.8). As it is pumped, the vascular blood is drained via the venous system. The trunk is preserved by inserting a trocar, puncturing the organs, removing body fluids, and replacing them with formalin. Embalming basically removes or contaminates all the body fluids that would be used for toxicology, and the punctures of the organs inhibit making some pathologic diagnoses. For this reason, forensic examinations are best done prior to embalming.



FIGURE 4.7
Other insects will also attack the body. This photo illustrates the irregular waxy abrasions seen secondary to roaches, which were commonly present at the scene.

A body having undergone an autopsy can still be viewed by the family and have an open-casket funeral. The incisions are made in areas covered by clothing or the casket materials. Embalming is done using the same vessels but localized internally. Cavity work is not necessary because of their removal during the autopsy.

Bruises may become more apparent after death especially in dependent areas due to increased lividity, as well as in nondependent areas where the paleness may make them more visible. Sometimes there will be no bruise visible, but after being in the morgue cooler overnight, the bruising will develop either by blanching the surrounding skin or increasing the blood in the area via the blood settling during livor. In some cases it can be useful to review the surface of the body for evaluation of development of a patterned contusion. It is also important to note that some bruises can “disappear” due to lividity, so it is good to photograph visible injuries at the scene for later evaluation. This is especially important in cases of child abuse, in-custody deaths, and homicidal blunt-force trauma.

INVESTIGATIVE TECHNIQUES TO NARROW TIME OF DEATH

Unless it is a witnessed collapse, establishment of a time of death is only an estimate plus or minus hours. If the decedent suddenly collapsed and resuscitative efforts were initiated, the point at which no respiratory or cardiac activity is present can be verified and the person pronounced dead. To make the latter determination, EKG pads are attached and in some jurisdictions require either a physician or EMS guidelines to make that determination. In cases of obvious cause of death (e.g., severe head injuries or body deformities) an office practice



FIGURE 4.8
(A) The typical embalming incision closed by suture and wax at the base of the neck. Other areas that may be used are the groins to perfuse the legs with formalin under pressure. (B) An embalming trochar site for evacuation of the internal food and waste material to slow down the rate of decomposition. Embalming formalin solution is then pumped through the trochar into the torso to promote preservation of the remains.

may be in place to assign a time of death at the arrival of the first law enforcement officer, the coroner, or medical investigator. It is usually formally recorded in the report as the "time of death is (*date*) at ___ hours" and recorded in military time. Also note it is very confusing to use a time such as 1/14/2014 at 00:00 hours. This type of data recording is confusing to decide if the time is unknown, or being established at midnight on the 13th or 14th. To avoid the confusion it is better to record the time as 1/13/2014 at 1159 hours or as 1/14/2014 at 0001 hours. Time of death is important because it can determine by a few minutes whether certain benefits may be bestowed on the family and estate of the decedent.

Clues inside a residence that may be helpful to estimate time of death are food freshness dates in the refrigerator, calendar markings, mail delivery dates, earliest newspaper outside a door, blood glucose monitors for last recorded date, diaries, phone messages, and medical diaries.

In some cases the body may be found with little information and warrant extreme investigation as to how long the person may have been dead. In those cases, pocketed receipts or phone logs may be valuable. Other methods may include collection of insects or noting foliage that has grown or is absent under the body. Details on the receipts may also be useful to understand the lifestyle of the person, previous locations, or what he or she was purchasing. If the interval is relatively short, many stores have video surveillance cameras with recordings that can be reviewed to determine acquaintances near the time of death.

Collection of insects is best coordinated with a forensic entomologist. A basic understanding is needed to collect two types of samples: one living and one preserved. It is best to collect various stages of all the species seen on the body and divide them between the two types of containers. The living ones need to be collected with a food supply and slightly moist with an air supply so they can survive transit. This is most easily done in a plastic container with small holes in the lid and a small chunk of cat food placed in the bottom with a couple drops of water so as not to drown the specimens. If live flies are present, it is also useful to have a small net to capture some of them in addition to sampling the various stages of maggots and beetles. The preserved samples need to have a similar spectrum of insects collected into a separate closed container filled with isopropyl (rubbing) alcohol. Both are submitted to a forensic entomologist for study. The entomologist will examine the preserved specimens to make an assessment of the types of insects, as well as determine what point is their life cycle. If need be, the living specimens can be used to raise a similar stage in the life cycle under similar weather conditions to get a time estimate.

Plants under a decedent may also give a clue. If the grass is dead, the body has been lying on the grass for some time; if yellow, less time. Some plants only grow certain times of the year and their presence under the body can give an idea of when that occurred in that particular climate. It is helpful to use local botanists and entomologists to assist since they are most knowledgeable of the local climate and plant/insect conditions. If none is available and it seems time of death is going to be an extremely important issue, the surrounding environment within 10, 20, and 30 feet can be documented photographically as well as the 360° view of the area under the body once it is removed. Close-up photographs of plants and vegetation can then be submitted when a botanist is located.

Loose plants or seed pods not appearing indigenous to the area can also be important evidence to collect. They may have been transferred to the scene by the decedent or a potential perpetrator. DNA of plants can be as unique as human DNA and seed pods have been traced to a single tree location.

REFERENCES

[1] King M. Tetany and Rigor Mortis; 2013. Retrieved from The Medical Biochemistry Page, http://themedicalbiochemistrypage.org/muscle.php. [August 2013].

[2] Bass W. Outdoor Decomposition Rates in Tennessee. Boca Raton, FL: CRC Press; 1997.

[3] Gleason M. Search for Human Remains. Search and Rescue Tracking Institute; 2008. Retrieved from http://www.sarti.us/sarti/files/SearchForHumanRemains.pdf. [August 2013].

[4] Vass A. Beyond the Grave—Understanding Human Decomposition. Microbiol Today 2001;28:190. Retrieved from http://www.academia.dk/BiologiskAntropologi/Tafonomi/PDF/ArpadVass_2001.pdf. [August 2013].

CHAPTER 5

Autopsy Procedure

Learning Objectives

- Outline the different personal protective equipment items used in death investigation and associate them with the purpose they serve to protect the investigator and the evidence being collected.
- Compare and contrast the Virchow and Rokitansky evisceration techniques and discuss the advantages of each.
- Recognize the various sites to obtain blood for toxicology and discuss the advantages and disadvantages of each.
- Demonstrate with a camera photographing an object from a distance, midrange and close-up views. Note the importance of adding a point of reference to identify the close-up view location.
- Demonstrate with a camera photographing with and without a ruler and at various angles in the relationship of the camera to the object (shallow angle, 90° angle, greater than 90° angle). Note the distortion of the object by the various angles and why it is important to maintain 90°.

Key Terms

PPE
N-95 mask
Bite-mark ruler
Virchow technique
Rokitansky technique
Trace evidence
Vitreous
Femoral blood
Subclavian blood

Chapter Summary

The best autopsies are those where a routine pattern of data collection is obtained and recorded. By performing each autopsy systematically, it allows subtle pathologic changes to be noted easily. Each case may require special modifications to answer a particular question, but the majority of data is obtained in this systematic fashion. This chapter discusses methods of recording the data and routine and special procedures used for dissection and specimen collection. These beginning techniques will serve as a basis to adapt them to a particular case to answer desired questions for determining the cause of death.

INTRODUCTION

The purpose of an autopsy is to systematically dissect and view the organs and their relationships to determine a cause of death. This chapter will discuss the various evidence collection procedures, how an autopsy is performed, and special techniques that may be required to answer specific questions resulting from the injuries or disease process.

PERSONAL PROTECTIVE EQUIPMENT (PPE)

The purpose of protective equipment during an autopsy is to decrease the potential health hazards to those in the room and prevent transmission of those biohazards outside the room to clean office areas. Under the Center for Disease Control Guidelines, all patients and decedents are to be handled by universal precautions. This means that all decedents' body fluids are considered infectious for potential transmission of HIV, hepatitis, and other infectious organisms. To prevent this transmission, those exposed to potential hazards need to wear protective personal equipment.

At a scene investigation, where there is potential for contamination of personal clothing or to prevent contamination of the scene for DNA and evidence collection, the following items should be worn:

- Shoe covers
- **Mask** (**N-95** particulate type mask)
- Clean lab coat or disposable jumpsuit
- Disposable gloves

In the morgue where splash and aerosol contamination occur, the following items need to be worn (Figure 5.1):

- Eye protection (goggles, face shields, safety glasses with side shields)
- Surgical gown or jumpsuit over scrubs
- Shoe covers
- Mask (N-95 particulate type mask)
- Disposable gloves, normally two pairs over one another



FIGURE 5.1
(A) The personal protective equipment advised during an autopsy. (B) A face shield may be used instead of goggles to prevent eye and face splashes.

Visitors not in direct contact with the body may wear street clothes but put a washable or disposable cover over them during observation. Other items required are eye protection, mask, shoe covers, and gloves if handling any biohazardous materials.

Disposable items should be discarded in proper biohazard receptacles prior to exiting the contaminated area, whether it is a scene or the autopsy suite. Sharps, such as syringes or blades, collected at a scene need to be transported in proper evidence containers to prevent injury to others. Medications need to be collected into vinyl evidence pouches and sealed to prevent spilling and contamination of work surfaces. These evidence pouches are marked with the decedent's name, date and time of collection, location, and initialed by the collecting agent.

Trash disposal from a morgue area is placed into biohazard (red or orange) bags inside transmittal receptacles (barrels) and disposed of through biohazard companies. Each state has guidelines as to the number of days the materials can be held inside a facility and how items are to be handled. Most biohazard companies can provide guidance on the particular state guidelines. Needles and scalpels must be placed into special sharps containers and discarded separately from routine trash. Needles are never recapped and discarded. No biohazard trash, including gloves, should go into a routine trash dumpster. Noncontaminated trash, such as packing boxes, can be recycled or placed into routine dumpsters if they do not have biological fluid contamination.

Linen services also must comply with a certain level of biological safety codes for scrubs and towels used in a morgue. These items may have extensive fluid contamination and need to be transported inside impervious bags. State laws may govern needed laundering standards and add cost to potential contracts.

Work surfaces are usually divided into clean and dirty areas. Paperwork that may be in the morgue area needs to remain in the clean areas if at all possible. Many morgues have become paperless to decrease the cross-contamination to other areas within the office. Useful paperless forms include those for toxicology, chain of custody, investigation reports, and weight sheets, which can be viewed and completed on a computer inside the morgue area. Food, drink, and smoking are not allowed in biohazard areas.

BODY ADMISSION TO THE MORGUE

The body is considered evidence and needs to follow similar procedures of evidence transfer. This includes documentation of body removal from the scene, including transportation person, date, and time. When the body arrives at the morgue, it needs to be signed in with identification of name, location removed from, date, time, and person delivering the decedent. To protect property and valuables inside the body bag, it is good practice to seal all body bags until they are opened at the time of the autopsy by morgue staff (Figure 5.2). It is difficult at scenes to always note in a report all jewelry or money that may be on the decedent. This procedure protects all parties, including the decedent from unnecessary loss



FIGURE 5.2
Examples of numbered plastic seals that can be used to secure the zipper on a body pouch to prevent tampering and secure the body as evidence.

of valuables, which can also become a liability for the office, law enforcement, or the transport company. All large quantities of cash should be counted by two parties and documented in writing prior to it being secured in a safe or transferred with the decedent.

A useful method to secure valuables and money is with a plastic-sealing machine (Figure 5.3). The valuables and money can be secured within the bag and sealed so it is visualized and secured, preventing biohazard materials from spilling in the safe, onto desks, or during transfer to funeral homes and families. The investment in a high-quality machine is well worth the offset of liability with fines from OSHA or loss of valuables in transit. The Appendix contains some examples of paper versions of property sheets.

Body admission includes logging the decedent into the office database, which begins with the official designation of a coroner or medical examiner case number. Some office policies assign this in the field, but others require



FIGURE 5.3
Plastic vacuum-sealed property that allows easy viewing and verifying of the contents for release to an agency or family.

physical presence of the body for admission numbers. Accurate demographic data entry is extremely important because this sets the stage for multiple articles of paper, toxicology, X-rays, photographs, labels, and transfer of information outside the office including the death certificate. Verification of spelling of the official name as it should appear on the death certificate, date of birth, date and time of death, and location of death are minimum facts that need to be entered. If the decedent's name is unknown or he or she is unrecognizable (trauma, decomposition), office policy will dictate how this type of case should be entered into the database. An example is "Unidentified #_____" or "Doe #_____." This especially applies to traffic accident victims, burned decedents, skeletal remains, and decomposed or other severely traumatized individuals. The pathologist will advise what type of identification method will be necessary, such as prints, dental records, or anthropology consultation (Figure 5.4).



FIGURE 5.4
A simple identification band that can be placed on the ankle of the decedent either at the time of the autopsy or at the scene. It should include a case number and name of the decedent, and is useful to verify the identity of the body at the time it is released to the funeral home.

Admission also includes a body weight. This may need to be verified or updated after undressing the decedent and removing extraneous materials such as water, extra clothing, or heavy scene items. Height also needs to be recorded and is obtained from the heel of the foot (from a leg that is not fractured) to the top of the head.

Funeral homes will frequently call and ask if the decedent is "viewable." They are referring to the viewing of a body at a funeral or by family. In traditional viewings, this is usually done from the decedent's right side with viewing of the right face and with the left hand placed over the right hand on the covering blanket. The ability to view a body is a difficult question to answer. Funeral homes have many skills to reconstruct a person's face with makeup and even wax when there is extensive trauma. If the person is decomposed or partially skeletonized on the face it may not be possible to view the body in the traditional sense but families may still want to see their relative. It is best for the investigator to be helpful if possible, but also somewhat hesitant to make that decision.

X-ray procedures

X-rays are done with the decedent still in the body bag and the clothing intact. Bullets can get entangled in clothing and it is important to know how many projectiles arrived with the decedent. X-rays can also help the investigator locate hazards such as needles and knives, personal effects, and even shadows of wallets.

The number and which X-ray views are done depend on the type of case. Homicides and unidentified and decomposed bodies get a typical trauma panel, which includes anterior and lateral head views, anterior views of the chest, and abdomen and pelvis views past the hips. If there are wounds or known prostheses of extremities, those are added. This panel allows an overview of the entire body devoid of extremities showing teeth restorations, spine alignment, and skull and rib contours. A trauma panel can also be useful in traffic accidents. In some offices where traffic accident victims receive an external exam only, X-rays can be useful to demonstrate critical fractures. It is difficult to do lateral views of the torso because of its position on a morgue tray, which makes it harder for

X-ray penetration. If the search for a bullet is becoming difficult, or multiple gunshot wounds are evident, X-rays can be helpful because they give a third dimension to locate the projectile.

Infant protocols are similar to adult trauma panels except the whole body is routinely X-rayed including extremities. Because more subtle findings are being sought, the infant needs proper alignment to view the extremities. The arms need to be positioned down by the side of the infant, preferably palm upward to view the arms with little rotation of the forearm bones. Medical-care appliances can obscure findings, and in questionable cases, the X-rays may need to be repeated after the appliances are removed by the pathologist. In some cases, sections of healed or recent fractures may need to be excised and X-rayed to better document evidence of healing for dating purposes.

If a gunshot wound is thought to be a result of suicide, a localized view of the area can be done, usually a head or chest X-ray as needed. If the decedent is decomposed, however, it is best to do a complete trauma panel to assure that other gunshot wounds are not missed due to the compromised assessment abilities.

Dental examination X-rays usually require a different X-ray system than the usual body X-ray system. Most modern dentists now use a digital system with digital sensor probes attached to a laptop for visualization and recording the images. The beauty of digital images is the ease with which they can be emailed from the decedent's dentist to the forensic odontologist for comparison to postmortem images. This greatly speeds up the identification process rather than transmission of film images through couriers or mailing.

Current X-ray technology is changing. Film X-ray use is basically obsolete and transition has been made to digital X-rays. Whole-body digital X-ray scanners and CT and MRI scanning now exist for forensic use. These technologies allow images of three-dimensional reconstructions of bullet and knife trajectories, as well as research into application of radiology for a "virtual autopsy." This concept involves high-quality X-rays to document internal injuries, and in some cases, can be used in lieu of a traditional autopsy (e.g., for religious objections or mass disasters). As more offices obtain these technologies, their use will no doubt expand into more applications. Because the decedents are not moving and radiation exposure to the patient is not a consideration, the technology can be less sophisticated, and, in turn, have lower costs than traditional patient instruments. Many times the technology can be obtained secondhand as hospitals upgrade and discard older equipment, and at a much lower cost than cutting-edge equipment.

Photography at the autopsy

The main purpose of photographs is to serve as a permanent record of injuries and injury patterns and for identification purposes. A second purpose is for documentation of clothing and personal effects should a question arise about their loss.

Scene photography is useful to document the position of the body in relationship to its surroundings. When arriving at a scene it is useful for the investigator to begin a series of photographs using an index card with the location, date, and his or her last name. To verify the location, photos of identifying landmarks, such as a street sign or house number, are useful to separate multiple cases on the camera.

Similar documentation separating cases on the camera for autopsies are useful. It can begin with the identifying tag/bracelet on the body and include a photo of the number assigned to that body. The photographic documentation continues upon opening the body bag. Overall, general photographs of the entire body from the sides and top are done prior to removing the clothing. This documents how the body is received at the time of the examination. Close-ups of gunshot wounds are done prior to the clothing being removed. Any necessary evidence from the surface of the body is also retrieved and documented.

The body is then undressed and washed. Overalls, plus more detailed photographs are then obtained (Figure 5.5). At this point it is useful to begin with a close-up view of the face from the mid-neck to the top of the head on a clean background. This can be very useful to verify that the case number corresponds to the face associated with that case number in case there is any mix up of bodies. A photograph with that case number included is also good documentation. Each field of view should include a slight overlap with the previous view taken so there are no missing elements documented. Photographs are taken at right angles (i.e., 90° angle) from the surface of the body to prevent distortion [2]. The following views are standard photographs:

- Overall views from the top and both sides, and possibly the back prior to undressing/washing.

After undressing and washing:

- Identification photograph with and without number, from top of head to mid-neck.
- Overhead of torso from mid-neck to upper thighs.
- Overhead of upper thighs to feet.
- Side view of head to mid-neck, both right and left.
- Side view of mid-neck to thighs, both right and left.
- Side view of thighs to feet, both right and left.
- Back of head to mid-neck.
- Back of torso from mid-neck to base of buttocks.
- Back of legs from buttocks to feet.
- Back and top of feet and hands.
- Midrange photos: These views are used to localize injuries that will require close-up views. They help to localize where on the body the following close-up view will be photographed.
- Close-ups: Any bullet wounds, clean and dirty, with and without scale.
- Any patterned injuries or those related to death, with and without scale.



Correct view at 90 degree angle between the camera lens and the surface being photographed. The ruler needs to be located at the level of the injury or structure being photographed, not above or below the plane of view.

Both of these views are incorrect as they are either greater than or less than 90 degrees. Either direction will cause distortion of the image. The importance is to insure that any ruler measurements taken from a photograph are true and representative of the injury or item being photographed. The circles on the bite mark ruler should have equal measurements in the horizontal and vertical plane when viewed in the photograph.

FIGURE 5.5
(A) Demonstrates what happens to the photographed view of an injury or object if the camera is not at a right angle to the object. The purpose of the ruler in the photograph is to substantiate and reproduce the size of an injury or object. (B) A standard photography ruler used during an autopsy and at scenes to document items in two dimensions.

- Collected evidence prior to being placed into a container and sealed (it is helpful to include the identifying label that will be affixed to the container).
- Front and backs of the hands in homicides.

A standard scale used in forensic photo documentation is an ABFO (American Board of Forensic Odontologist) **bite-mark ruler**. It was developed to use on bite-mark wound documentation but has since become the standard photographic reference used in all wounds. It has become so because of three features: it is shaped in a right angle so it gives simultaneous two-dimensional documentation of an injury pattern; it has a gray and white scale to document standard gray and white coloration; and it has circles on the surface to document that the photo was taken at a true right angle from the wound, which prevents misinterpretation of measurements and characteristics.

EVIDENCE COLLECTION DURING AN AUTOPSY

The type of evidence collected during an autopsy is individualized to the type of case and evidentiary requirements determined by the forensic pathologist and investigating law enforcement agency. Common types of evidence collection techniques will be discussed here. Much of the evidence is collected from the hands, and prior to cleaning or collecting it is proper procedure to photograph the front and backs of the hands and nails. The hands of the decedent should never be handled without gloves to prevent transfer of DNA. If **trace evidence**, gunshot residue, or DNA is going to be collected, it is best practice to handle the hands only with a fresh pair of gloves for each hand and minimize contact with the hands until these collections are complete. Sometimes officers wish to perform fingerprints at the scene. It will need to be weighed whether the fingerprint can be done with minimal impact on further collections (digitally on clean screen, inkless fingerprint ink, etc.). The order of collection of materials from the hands after the bags are removed is gunshot residue, DNA swabs, trace evidence, and then fingernail clippings. It is good to bivalve the brown bags so one hand has a clean surface to rest on while working on the other hand between specimen types. To keep the bags sorted, the outside of the brown bag can be marked right and left when the body bag is opened, so when each are passed off to be packaged, there is no confusion.

Gunshot residue collection

Gunshot residue is usually collected using a special kit. There are two major types of kits available depending on the crime lab being used. Both kits require the same precautions and are applied to the backs of the right and left hands separately at the thumb, web of the thumb, and first finger.

Fingernail clippings

Fingernail clippings are usually collected in homicides where there was a physical connection between the victim and assailant. It is hopeful that the debris under the nails would yield DNA linking the two near the time of death. Prior to clipping the nails, it is important to note their condition for evidence of tearing or loss of acrylic nails. The clippings are easily collected into cone-shaped filter papers separately and placed into individual envelopes. Clean clippers and gloves are changed between hands to prevent cross-contamination. It is important to clip only the nail and prevent contamination with the decedent's blood because that can overwhelm the miniscule quantity of assailant DNA that might be present.

Trace evidence

Trace evidence is minute fragments of debris, fibers, hair, vegetation, paint chips, and the like adherent to the body. Paint chips, plastic, and glass fragments are useful in pedestrian motor vehicle accidents, especially a hit and run where the suspect vehicle is unknown. These small fragments may be the necessary evidence to identify a suspect car and link it to the decedent. The other types of materials, such as hairs, fibers, or vegetation, can be useful in a discarded body homicide where very little is known about a suspect or crime scene. These small details may be all that links a suspect to the decedent, especially if the materials are particularly characteristic or embedded within wounds or blood. These fragments are easily collected into a cone-shaped filter paper and sealed inside an envelope.

To sort out foreign hairs from the decedent's hairs, it is useful for the laboratory to receive known head, eyebrow, and/or pubic hairs as exemplars for comparison. These are best retrieved as pulls rather than cuts so as to include the hair roots. They are collected from three to five different regions of the scalp or pubic area to get a general sampling and are placed into a cone-shaped filter paper and sealed inside an envelope.

DNA swabs

With the advances in DNA technology, minute amounts of DNA can be recovered from contact between the victim and assailant. It is best to target areas not overwhelmed from the victim's blood to try to recover this type of DNA. Areas to consider retrieving it are the neck, breasts, thighs, fingertips, and outer labia/penis.

To collect these, packages of sterile cotton swabs and a small cup of sterile saline are used. It is preferable to dry them after collection in a swab dryer available from forensic supply companies.

These collections are done after the hand collections and before the body is washed or handled. The sterile cotton swabs are dipped in the saline and rolled over the upper edge of the cup to remove the excess water. The swab is rolled over the desired surface and placed into the dryer, marked at the edge for the site of collection. A second swab is rolled over the previously dampened area and combined with the previous collection. This is called the wet–dry technique. The first swab loosens any epithelial cells adherent to the skin, which are then picked up by the second dry swab. This procedure is repeated for the desired collection areas. When the swabs are dry, they are packaged in envelopes or small collection boxes, labeled, and released to law enforcement through the chain of custody.

Sexual assault

Sexual assault kits are usually standardized by each state crime laboratory and are available from them or law enforcement (Figure 5.6). It is advisable to have at least two available in the office at all times but may require more depending on the number of cases the office performs weekly. Within the kit are swabs for collection from multiple sites. The order of collection begins with oral swabs with attention to crevices along the gumline and teeth. One swab is rolled onto the accompanying glass slide and marked with the case number and "oral." This is followed by pubic hair combings onto a half-folded paper and includes the comb with the paper into the envelope. This is followed by vaginal swabs that are placed into a swab drying rack to dry prior to packaging. It is necessary to get good views of each orifice to prevent contamination. Generally, a minimum of four swabs is needed for each orifice, as the amount of sperm may be in small numbers. Each location where swabs are to be obtained should be preceded by a change of exam gloves to prevent any cross-contamination. Photographs of traumatized areas can be obtained at the same time as the exam and is easiest if there is a photographer present to assist. After the vaginal exam, swabs can be obtained from the inner or anterior thighs if secretions are visualized. These can be added to the kit in plain, white envelopes and marked by case labels. Anal swabs are obtained next by separating the buttock cheeks to directly view the anal opening for insertion. This is important to prevent contamination from any posterior drainage from the vagina onto the surrounding buttocks. Just as for the oral and vaginal specimens, a single swab is used to prepare a glass slide by rolling it over the surface and labeling it with the case number or site. It is important to keep all the swabs separate and thoroughly dry them before packaging. All items labeled then are placed back into the box and sealed.



FIGURE 5.6
(A, B) Items in a sexual assault kit. These kits are available from law enforcement and are standardized for the crime laboratory.

Toxicology specimen collection

The types of toxicology specimens tested will be determined by the forensic pathologist and the forensic toxicologist. The quality of the specimens is determined by the condition of the body as well as the skill of the person retrieving them.

The specimens commonly retrieved for an external examination only include **vitreous,** peripheral blood, and urine if available. A clean syringe should be used between each specimen type and the specimen placed directly into the tube/jar and immediately labeled with the patient's name, specimen type, date, time, and initials of the person drawing it (Figure 5.7).

Specimens drawn during an autopsy include vitreous, **femoral blood**, urine (if available), liver tissue (right lobe, about 30 g), and gastric sampling. Brain tissue and head hair are emerging as desired specimens in some cases and, depending on the laboratory, they may be standard collections.

Vitreous is useful as a means of quantifying alcohol and verifying a blood-alcohol level, especially if the decedent received medical intravenous fluids, which dilute blood specimens. They also lag behind blood-alcohol metabolism and



FIGURE 5.7
An example of a toxicology sampling kit for the various specimens on each decedent. It is helpful to have these kits set up for each autopsy to prevent missing a specimen.



FIGURE 5.8
A diagram depicting the location to obtain vitreous from the eye. The eye is a hollow ball filled with the clear viscous fluid. As the fluid is removed with the syringe and needle, the eye will collapse.

may give a look back in time at a higher level prior to death. For this purpose, vitreous should be placed into a preservative (gray top) tube. Vitreous is also useful to determine predeath electrolytes as postmortem blood is not useful for this purpose. Vitreous glucose is especially useful to evaluate deaths where there has been a history of diabetes mellitus. A small drop can be used in a personal glucometer to evaluate the level. Postmortem, the vitreous glucose value drops quickly to zero, and evaluation upon admission to the morgue can prove useful after the eyes are evaluated for hemorrhages and petechiae. For electrolyte testing, vitreous needs to be placed into a nonpreservative tube (usually a red top, without gel). Vitreous is obtained by placing a 16g needle attached to a syringe or vacutainer into the eye sclera and withdrawing the clear viscous fluid. Total volume from both eyes is usually less than 5ml and can easily be divided between the two specimens, red-top tube followed by gray-top tube.

Femoral blood

Peripheral blood is the desired specimen, as it is thought to reflect most accurately what the brain and body was experiencing at the time of death. More central blood (i.e. heart blood and even **subclavian blood**) is closer linked to the absorption areas from the arms, neck, or small intestines. In these areas the blood has not passed through the liver or kidneys where drugs are metabolized to a more inactive chemical structure or metabolized to their active structure and quantified values may be less accurate. It is preferred to obtain blood from the most distal area if possible. If it is necessary to encourage blood into the iliac vessels, it is best if milked from the legs proximally rather than from the inferior vena cava. See Figure 5.9.

It is difficult to obtain blood from the femoral system of infants. Cardiac blood is typically used to obtain toxicology, metabolic screens, and cultures. Motor vehicle victims also can have scant femoral blood, but usually one tube can be obtained. The remainder of the specimen can be cardiac blood as needed. Cavity blood should be used only as a last resort because it can be contaminated from the stomach contents and yield inaccurate quantification results. This is especially a hazard in blind sticks for cardiac and subclavian samples in external exams. If it is necessary, the right pleural cavity is preferred since it is furthest from the stomach.

Evisceration techniques

The body is opened using a Y-shaped incision with the upward branches beginning at the top of each shoulder and the stem of the Y extends through the mid-abdomen to the symphysis bone. The branches of the Y are done to protect the viewing area of the neck and chest for the funeral and visitation. If an open shirt or low-cut blouse/dress is used in the casket, the autopsy incisions will not be visible. A midline incision can be devastating for this reason. This technique also spares the neck, which is also visible. For the removal of the chest plate and neck organs the skin is reflected upward to the lower jaw. European countries have a different style and may use a midline chest with extension of the Y branches onto each side of the neck, but in the United States this is not done.

An evisceration technique refers to methods of organ removal from the torso. There are two basic techniques of organ removal from the body: Virchow and Rokitansky styles (Figure 5.10). Each has useful applications, and the method used depends on the style preferred by the pathologist or particular questions that may need to be answered during the examination.

The **Rokitansky technique** is a block style that allows the organs to be evaluated in relationship to their interconnections such as vasculature or ducts. Disadvantages to removing the organ cavity as a whole are the bulkiness of working with the mass of tissue, as well as being heavy and messy. The Appendix contains a photographic overview of the autopsy procedure.

The **Virchow technique** utilizes an organ-by-organ approach that uses the natural retraction of the body itself and allows the connections to be viewed for the majority of cases. It is usually faster, and makes handling the organs alone much easier than block removal. The blood drains naturally into the cavity and prevents a large degree of mess to clean up.


Intracranial Veins
External Jugular Vein
Internal Jugular Vein
Subclavian Vein
Internal Thoracic Vein
Axillary Vein
Cephalic Vein
Brachial Vein
Intercostal Vein
Basilic Vein
Median Cubital Vein
Thoracoepigastric Vein
Radial Vein
Median Antebrachial Vein
Ulnar Vein
Inferior Epigastric Vein
Deep Palmar Arch
Superficial Palmar Arch
Palmar Digiti Veins
Inferior Thyroid Vein
Left Brachiocephalic Vein
Superior Vena Cava
Azygos Vein
Inferior Vena Cava
Hepatic Vein
Hepatic Sinusoids
Portal Vein
Splenic Vein
Renal Veins
Superior Mesenteric Vein
Inferior Mesenteric Vein
Abdominal Vena Cava
Testicularis Vein
Common Iliac Vein
Internal Iliac Vein
External Iliac Vein
External Pudendal Vein
Deep Femoral Vein
Great Saphenous Vein
Accessory Saphenous Vein
Femoral Vein
Superior Genicular Veins
Popliteal Vein
Inferior Genicular Veins
Great Saphenous Vein
Smal Saphenous Vein
Anterior Tibial Vein
Posterior Tibial Vein
Deep Plantar Veins
Dorsal Venous Arch
Dorsal Digital Veins

FIGURE 5.9
An anatomical chart of the venous system. Note the locations of the right and left subclavian vessels, the femoral veins, and the distal internal iliac veins. These are locations where blood is commonly withdrawn for toxicology sampling.

DDR
40
1821
KARL FREIHERR v ROKITANSKY
1804
1878
S 1.50
REPUBLIK ÖSTERREICH
A
B

FIGURE 5.10
(A) Photo commemorating the work of the German pathologist, Dr. Rudolf Virchow. (B) Photo commemorating the work of the Austrian medicolegal anatomist, Dr. Karl Rokitansky. Both contributed to anatomical pathology through their evisceration techniques.

If necessary, a modified Rokitansky technique can be done if a specific area needs to be visualized such as the vasculature of the heart and lungs. The chest can be removed as a block and the remainder of the individual organs via the Virchow method.

Prior to any organ removal or even toxicology specimens, it may be necessary to measure fluids that have accumulated within the pleural or abdominal cavities. This is done by using a ladle to dip each area separately into a measuring device for quantification (Figure 5.11). If large amounts of blood are estimated, it is best to keep the right pleural cavity and not discard it until toxicology is obtained. Cavity blood can be used to perform qualitative assessments and then quantification performed on a single femoral specimen if that is all that is available.

The order of organ removal is based on the traditional teaching of heart removal with draining of blood into the pericardium and chest cavity, releasing the "vascular seal." After the heart is removed, the cranium can then be removed. This order prevents blood from being suctioned into the cranial cavity while the skull is being removed and creating artifact hemorrhage on the brain with misinterpretation of the finding. After the brain is removed, the neck may be examined. This order allows blood to not only drain into the chest cavity, but also from the skull, which in essence creates a bloodless field in the neck vasculature. The finding of hemorrhage of the neck muscles in asphyxial strangulations can be very subtle, and knowledge that it is a bloodless field adds credence that the finding is a real one and not an artifact. It is also important to



FIGURE 5.11
(A) The instrument setup for the removal of organs from the trunk. Each pathologist will have special instruments they like available such as hemostats or special scissors. (B) The instrument setup for removal of the brain. The saw is not immersible in water and must only be scrubbed on the blade portion.

retain the skin over the surface of the neck until this final step because the pooling of blood from removal of the chest plate and underlying subclavian/azygous vessels can stain the neck muscles, creating the same distortion. In some cases of asphyxia, the hyoid and thyroid cartilage bones may be intact and the only finding will be hemorrhage. If a technician is assisting the pathologist, it is important to notify them of any hemorrhagic findings prior to the removal of the cranium or the neck organs for the pathologist to view in situ. Intravenous catheter insertion into the jugular veins can result in therapeutic hemorrhage into the neck musculature but needs to be evaluated in situ by the pathologist to make that determination.

Virchow organ removal follows a systemic order. The heart is removed by incising the vessels near the pericardium on the underside of the heart followed by the pulmonary artery and aorta. Each lung is removed by incising through the medial hilum, which frees it from the trachea and vasculature. The right lung will have three lobes and the left will have two lobes. The small and large bowel is removed next and usually can be discarded into the organ return bag if there are no gross abnormalities. The liver is removed by snipping along the diaphragmatic border and cutting its connection from the central vascular/bile duct region. The spleen is usually free floating in the left-upper quadrant and easily cut from its vascular pedicle. The adrenal glands rest on the super and medial portions of each kidney and can be excised for the pathologist, or if the pathologist is prosecting, incised in situ for evaluation. A thin incision can be made on the outer edge of each kidney, which will begin to free the surface membranous capsule. Forceps can be used to strip away the fat and connection tissue and its vascular pedicle will be visualized medially and cut. The bladder and internal female genitalia are identified in the pelvis. The bladder is freed from the symphysis of the pelvis with blunt dissection or scissors. It is important to note the course of the femoral arteries along the rim of the pelvis bilaterally and avoid them during the removal. By using the knife/scissors and staying medial to them with blunt dissection, the sides of the organs (including the ovaries, which will lie near the vessels) will be released. Posteriorly, the organs lie on top of the rectum, which is usually not needed, and if excised causes abundant drainage from the cavity into the bag and casket. Blunt or scissor dissection is useful to free the organs from the rectum. By remaining inside the pelvis and not putting excessive traction on the bladder or uterus, an incision can be made front to back without placing a gaping opening onto the perineum.

The only remaining organs are the esophagus/stomach with pancreas, aorta, and trachea. An incision is made transversely above the vessel bifurcation into the right and left iliac vessels. Each diaphragm is then excised along their contours to the midline. A transverse incision is made through the trachea, esophagus, and great vessels as they exit from the arch of the aorta. It is important to not put too much traction on the arch as the subclavian arteries will snap under the clavicles, making it difficult to embalm the arms and head. The trachea can be used for traction because the remaining tissue is excised away from the spine to the transverse vascular incision near the pelvis.

The Rokitansky technique is basically the Virchow technique from the point of the transverse incision across the vessels of the pelvis, followed by the incision near the clavicles, both diaphragms. The entire organ block can be excised off the spine and given to the pathologist. They may wish the bowel removed prior to the block being excised.

The head is examined by making a continuous incision from behind each ear over the vertex of the head remaining behind a line drawn over the top from ear canal to canal. It is important to not get the incision too far forward since it will be seen in the casket if the person has very little hair, and if the incision is too far posterior it can make reflecting the anterior portion for visualization of the skull extremely difficult or actually split down the top of the head. This is especially difficult if the head is edematous, so care must be taken to not force the skin too quickly. Using blunt dissection and small incisions, the scalp is loosened anteriorly to fold the top and anterior portion over the forehead. The posterior flap is easier to use the scalpel to reflect downward. Photographs may be needed at this point depending on the case. Temporalis muscles are present on the right and left sides of the head that need to be incised downward to make a path for the saw. The saw cut is made about 3 cm above the brow ridge anteriorly and slightly below the occipital protuberance posteriorly. To avoid a totally circular skull cap resulting, these two horizontal lines are offset onto a notch area on both sides of the head so that the skull rests on a shelf. From the beginning, it is helpful to draw a line using the scalpel to follow with the saw. The oscillating saw is relatively safe to the naïve handler as the cutting edge vibrates to create the cut, rather than incising. To give life to the saw it is important to lift and press rather than push the cutting margin in a linear path.

After the circular cuts are made, a skull key can be inserted and turned to begin the separation of the edges and pry it open. If blood is visualized, the pathologist should be notified prior to proceeding. It will be necessary to use scissors to cut the anterior dura margin then insert a hand to support the brain while the skull cap is removed by the other hand. This will prevent tearing of the brain from the brainstem. Photographs may be necessary of any blood or other abnormalities, and while this is being prepared, the brain needs to be supported so it doesn't separate at the brainstem. The brain is then anteriorly lifted gently from the base of the skull and the nerve connections are snipped close to the skull. As the posterior brain is approached the dura forms a shelf under which lies the cerebellum and brainstem. It is important to incise the shelf along each edge where it connects the skull, which will free the posterior fossa and allow visualization of the brainstem. It is important to note any separation of the brainstem from the cortex and inform the pathologist. Reaching with scissors as far into the foramen as possible, the spinal cord is cut from the remaining portion and the brain should lift out to be weighed. The brain is normally very soft and should be kept separate from other organs for the pathologist to evaluate. The dura lining the skull and cap needs to be removed for evaluation of any underlying skull fractures. The pathologist will wish to view both the skull cap as well as the removed dura. If hemorrhage is present on the dura, the pathologist may wish to remove it and take microscopic sections. The head is left open until the neck dissection is complete and the pathologist has given permission for it to be closed. Closure is accomplished by placing the skull cap in place, returning the skin to the normal anatomic position, and tacking with the normal thread. It may be helpful to put some paper towels inside the cranium to absorb blood draining from the face. Some offices cover the head with a bag to prevent extensive leakage.

The neck organs remain and are discussed later under special techniques for tongue removal. The cavities are then dried from accumulated blood and evaluated for fractures that are documented. How to document fractures is also discussed in the "Special Techniques" section.

RECORDING AUTOPSY DATA

Many offices are going to a paperless system and records are kept in an online file for each case. Some of the databases are quite sophisticated, but even a dedicated folder on the office server for each case will suffice. Each folder can contain a subfolder for photos, investigative reports, a chain of custody, an autopsy weight sheet, an autopsy report, and medical records.

External examinations may have their own form that may include only a handwritten diagram or fill-in form depending on the office protocol. An example of one is found in the Appendix.

Records generated during an autopsy include a weight sheet, diagrams, and a chain of custody for any evidence leaving the building, and a toxicology request form. A weight sheet includes an area for each of the major organ systems to record the weight, and areas for the pathologist to record specific findings for dictation. See the Appendix for an example of a weight sheet.

Each organ is weighed individually in grams and the weight recorded on the autopsy record sheet. The pathologist may also have the assistant record various findings throughout the dissection. When weighing the heart, it is important to expunge blood from the chambers so an accurate weight can be recorded, or the weight can be repeated after the heart chambers are opened and drained by the pathologist. Recording volumes from body cavities, bladder, and stomach will require using a ladle to transfer the fluids into a measuring device, usually a 1 L container. It is also possible to measure urine and cavity fluid volumes by weight as 1 ml approximates 1 g in weight. This is useful for estimating clotted blood or volume of fluids within hollow organs by weighing the organ with the liquid intact, emptying the liquid, then reweighing the organ. The difference in weights will give the volume of liquid.

The following is a summary of materials generated during an autopsy or examination.

Cut box or tissue container

This is a small biopsy container filled approximately halfway with formalin and used by the pathologist to retain biopsies for potential microscopic examination.

Some pathologists utilize this container plus “cut in” the biopsies directly to histology containers as they are performing the dissections.

Cassettes for histology

Cassettes are small plastic cages that hold the biopsy specimens for histology. They are labeled with the office case number and begin with 1 or A, a sequential sequence to differentiate one from the next. These cassettes are transferred to a histology department in formalin. They are then placed through a processing machine to infuse the biopsies with preservative. This process usually requires an overnight cycle. The cassettes are removed from the cage and embedded by the histologist into paraffin, which can be cut into very thin slices and placed onto microscopic slides. The slides undergo a series of staining procedures to outline the cells for the pathologist to review under the microscope. If the specimens are sent outside the building, they will require a chain of custody outlining the number of cassettes sent for each case. Formalin is considered a carcinogen and the transfer container should be one that will not leak, placed inside a plastic bag inside a cooler for the courier.

Retention of brain for later dissection

In some cases, the pathologist will wish to retain the entire brain for formalin fixation, later dissection, and review. It may require transfer to a neuropathologist for dissection. The brain is removed, weighed, and placed into a 15–20% formalin solution (a higher concentration than normal because of its higher water content). It will require a container large enough to cover the surface with formalin, usually at least a gallon-size container one-quarter to half full with formalin. The brain is lowered into the formalin and secured to the top by a string around the brainstem or floated inside a hairnet to prevent flattening by resting on the bottom of the container. It usually requires 7 to 10 days for the brain to be “fixed” and ready for dissection. If the brain is bisected, fixation will occur much quicker. The pathologist will require cassettes for obtaining biopsies from the fixed brain for microscopic review. Cases where the brain may be retained for fixation are child abuse, brain tumors, degenerative disorders of the brain, or unusual brain trauma. Some offices retain all brains for later review. This has begun to fall into disfavor by families who wish all the remains returned to them. In some jurisdictions, retained organs must be disclosed to families and permission sought for the disposal.

Toxicology specimens

Each toxicology laboratory will have individual requirements for specimens. It is important that the specimens be labeled with the correct labels and type of specimen, as well as sealed inside the appropriate transfer container to the lab (a box or biohazard bag) at the end of each case, and before the next case is begun to prevent confusion of specimens. It is a good time to verify that the correct labels were placed onto the specimens and that each specimen is labeled correctly. Requisitions for the laboratory may be required to be completed prior to the transfer.

DNA specimen

DNA specimens collected on FTA (fast technology for analysis) cards and in the special envelopes need to be labeled and are usually stored in the freezer. The FTA material serves as a preservative to stabilize the DNA on the card and allows them to be stored at room temperature [1]. Some offices air dry them and place them in the case file. It is important that they be completely dry before packaging or they may mold in a case file and become unusable. Labels need to be placed directly on the specimen and outside envelope for identification.

Genetic screen

Genetic screens are collected on the laboratory version of an FTA-type card. It is important they be labeled and the requisition be completely filled out or the laboratory will not complete the testing. They are usually air dried and placed into a mailing envelope without special handling necessary. Notes within the case file of the date it was mailed are helpful.

Cultures

After the specimens have been placed into their appropriate media containers for transfer to the lab and labeled, they should be stored in the refrigerator until the courier arrives to take them to the microbiology laboratory. They must be accompanied by a completed requisition outlining the specimen types and tests requested or they will not be accepted by the laboratory. They should not remain in the refrigerator for transfer to the laboratory after the workday. Transfer should occur in a biohazard bag inside a cooler with an ice pack to prevent deterioration during the courier run.

Evidence

Homicide evidence is generally transferred directly to the agency that has attended the autopsy at the end of the dissection. It is helpful to the pathologist signing over the evidence to the officer to have it orderly laid out, in the order on the chain of custody, and to have each item labeled on the paperwork with the exact working on the item's container. Each item can be verified by both parties and placed into a brown paper bag for the officer to transfer to the laboratory. Unless the medical examiner/coroner has a drying cabinet, bloody clothing items are placed into individual brown paper bags, then into a biohazard bag. This will prevent any contamination to the evidence or transfer of biohazardous material to the inside of the officer's vehicle. It should be directly transferred to the evidence handling area and checked in for refrigerated storage and drying, and to ensure a tight chain of custody.

Discard policy

Obviously all this material cannot be held indefinitely and must be sorted into those items pending litigation where they might be needed to those that are no longer needed for case evaluation. Each office will have its own policy based on

Table 5.1 Storage Periods

Item	Time Period
DNA cards	Indefinitely
Toxicology specimens	2 years after receipt of report
Gross formalin fixed tissues	1 year
Tissue paraffin blocks	10 years
Tissue microscopic slides	Indefinitely
Homicide specimens	5 years

local politics, case backlogs, and accreditation requirements. Homicide tissue and toxicology are usually held at least five years. Cases of unidentified remains also need to be retained longer than "usual" cases, which are generally held one year after completion. According to the National Association of Medical Examiner's Accreditation Standards the storage periods shown in Table 5.1 are recommended.

Some evidence, such as bullets and ligatures from suicides, tend to accumulate at the coroner/medical examiner office. Law enforcement rarely is interested in these items unless there is an investigative issue that arises. It is advised that a routine periodic assessment inventory of these types of evidence be performed and the investigating agency be contacted with a list of items that pertains to them. They can be informed of the type of evidence and request a disposition on each item.

All clothing and personal effects need to be released to the family or their designee, such as a funeral home, at the time or prior to the body being released. It is important that the property only be released to the person who has a right to it and many times this is the person making the funeral arrangements rather than someone who is randomly appearing at the office requesting personal effects. Most times this is best handled at the funeral home. Because families can disagree on which funeral home the body is to be released to, it is important for the death investigator to be cognizant of the next of kin available. Their rights to personal effects and designation depend on the order precedence in the state law sequence (usually spouse, adult children, parents, siblings). It is best to have the desired funeral home designation on a form signed by the appropriate designee to avoid dealing with a verbal release to the wrong funeral home.

CLOSING THE BODY

Organs are generally not retained and are returned to the body cavity for release with the body. A heavy-duty trash bag with biohazard markings is best. It needs to be heavy duty enough so when the funeral home lifts it out for embalming, it does not rupture. For this reason, any medical-care appliances such as endotracheal tubes should not be put in the organ bag.

The Y-shaped incision is closed with heavy-duty white-cotton string and a tissue needle, both of which can be obtained from funeral home supply companies.

Some offices just tack the trunk closed at intervals and others sew the cavity closed with a continuous overhand "baseball" stitch and tie off the ends when done. The latter is the most helpful and prevents leakage of cavity fluids during the body transfer to a funeral home. It is disastrous if the body bag breaks during transfer and accumulated fluids flow onto personnel. Clothing is best placed into a biohazard trash bag and closed with attached name and case labels and placed inside the body bag with the decedent. This prevents the clothing from getting separated during the body release. Valuables are generally kept separate from the clothing and body in an office safe and need to be retrieved. The body needs to be signed over to the funeral home transport person and a separate form for property, including documented valuables, needs to be signed (see the Appendix). It is important that large amounts of money be counted by the receiving personnel.

SPECIAL TECHNIQUES

The following are special techniques that can be applied.

Turning a body over from face up to face down

It may be necessary to turn a body completely over for obtaining spinal fluid or documenting numerous injuries over the back or lower extremities. This can be very difficult depending on the size of the decedent. Body mechanics will greatly assist. Put a generous amount of soap on each side of the decedent lying face up on the table. Slide the decedent to one side and extend the arm closest to the center of the table over the top of the head. Grasp the opposite shoulder and thigh to rotate the decedent toward the center. As the body is rolled, the upward arm will act as a fulcrum and pivot the decedent over face down. The arm can then be lowered and the decedent lifted by the shoulders onto a shoulder block under the chest.

Spinal fluid collection

Equipment needed for spinal fluid collection includes bactericidal soap, spinal needle (in children a vacutainer may be used), 10 cc syringe, sterile needle, and a collection tube (red-top tube without gel and no preservatives).

The easiest method is to have the decedent face down with the shoulders propped on a block and head downward, hyperextending the vertebra of the neck. It is important the head is in alignment with the spine. The base of the skull is palpated just above the posterior vertebral process and a pressure mark is made by the nail (through a glove). The area is scrubbed vigorously with the bactericidal soap and the gloves are changed. The spinal needle is attached to the syringe and inserted between the skull and vertebral body into the cisternal space around the base of the brain under the dura of the posterior fossa. During the insertion, it is important to put gentle suction on the syringe until there is a slow filling of clear to slightly bloody fluid. Cerebral spinal fluid (CSF) is generally colorless with the consistency of water. After obtaining 5–10 cc, the needle is withdrawn and changed to a regular sterile needle for insertion into the red-top tube. If possible, it is best to clean the top of the tube prior to the needle insertion to remove contaminants. It is then ready for labeling and transfer to the laboratory.

Posterior neck dissection

The purpose of this procedure is to look for fractures on the posterior portions of the vertebral bodies of the neck that are not visualized from the anterior view after the neck organs were removed. A posterior neck dissection is performed with the decedent face down in the same position as for spinal fluid collection. A vertical incision is made over the cervical spine extending into the upper thoracic spine and made in the midline. It needs to be long enough to incise the underlying muscles away from the spine to visualize the bony structures and assess the area for hemorrhage and fractures.

Anterior neck dissection

In cases of suspected strangulation, the pathologist will perform an anterior layer neck dissection. It is done after the organs have been removed from the trunk and the brain has been removed from the skull. This allows blood to drain from the neck in both directions and create a bloodless field. The diagnosis of strangulation can be made from hemorrhage in the neck muscles with or without fractures of the hyoid bone, thyroid, or tracheo-laryngeal cartilages. So, it is important that blood not pool on the muscles and create artifacts. Usually strangulation is associated with petechiae of the face or eyes, which is the clue that care needs to be taken not to dissect the skin above the clavicles. To protect the muscles at the level of the clavicles that become exposed during removal of the chest plate, a towel can be laid over the muscles to absorb any blood.

The dissection proceeds with dissection of the neck skin away from the surface of the muscles. Photographs are taken at each stage of the dissection with a ruler needed if there are areas of hemorrhage. After the muscles are exposed and photographed, each muscle will be dissected away and laid so the undersurface is viewed and documented for any hemorrhage. This will create a fanlike image of the muscles of the neck. After this documentation, the pathologist will remove the tongue and the usual neck organs. Photographs will be needed of fractures of the hyoid, thyroid cartilage, or hemorrhagic areas over the anterior spine. It is always important when removing the neck organs in routine cases to not put too much pressure on the delicate bones and create fractures.

Removal of the eyes

This procedure is done to look for periorbital and retinal (internal) hemorrhage, usually in child abuse cases. The object is to preserve the eye for confirmation of clinician documentation of retinal hemorrhages. This involves a twofold approach by removing the orbital plates from inside the skull and gently excising along the margins between the globe and the orbital bone, preserving the eyelids and the optic nerve as it enters the skull. It is then placed into a small cup of formalin, making sure to mark each eye separately with a label. The pathologist will dissect the eye after it is fixed.

Removal of the inner ears

Removal of the inner ears is done to look for an inner ear infection. It is performed by making a triangular wedge–shaped cut inside the skull over the sphenoid ridge. This can then be decalcified and reviewed microscopically.

Removal of the spine to view the spinal cord

The purpose of looking at the spinal cord is usually to confirm its integrity, which would correlate with the ability to continue moving. Other reasons to view the cord are to evaluate for subdural hemorrhage, tumors, or degenerative disorders. To view the spinal cord, it is necessary to remove the anterior vertebral bodies in a wedge shape beginning in the cervical spine of the neck and extending to the lower back. The cut is made inside the body cavity at ~45° angle to the spine. It can then be pried off using the skull key to reveal the intact dura. The dura is opened, and the spinal cord is evaluated for integrity or other abnormalities. It can be very difficult to observe the upper portion of the cervical spine where it connects with the skull. Special instruments will be needed to insert through the foramen magnum and release the spinal nerves so that a portion of the cord can be removed with the lower portion.

Removal of bullets embedded in bone

Not uncommonly, bullets need to be retrieved from thick bone. This is made more difficult if they are small caliber or are in small fragments. Obviously, the goal is to retrieve it without distorting the rifling grooves. If possible, it is helpful to have two different views of X-rays of the area, an anterior and a lateral view. The anterior view gives detail of how superior/inferior it is as well as how far left/right. The lateral view will give an idea of how front to back it is. This allows a more directed cut. Sometimes the entrance in the bone can be palpated. To avoid hitting the bullet, it is best to give the area at least a 1–2 cm rim and, using the bone saw, extricate the bone where the bullet is lodged. This can be very time consuming and trying. The skull key can be used to break the bone away from the bullet. If it is unclear if the bullet is located in the bone, it is easiest to just X-ray the fragment and, if necessary, the body.

Examination of legs for thromboemboli

Some pathologists routinely examine the lower legs as a source for thromboemboli to the lungs. The thought behind this is to identify which of the extremities is the source, especially if one had trauma and the other did not. The pathophysiology behind why a thromboembolism forms is related to stagnated blood flow due to immobilization or coagulation abnormalities. All or part of the clot formed in the leg or pelvis will become mobile then entangled in the lung vessels.

The decedent must be face down to look at the popliteal and upper leg veins. Incisions are made over the backs of both legs in the midline from the lower thigh onto the lower legs. The muscles are bisected and dissection to the vessels is done to view their lumens. Microscopic sections of the veins may be obtained.

Catheterization of the neck vessels to evaluate for a ruptured intracranial vessel

This procedure is normally considered in cases of a boxing-type injury or punch to the jaw and someone suddenly drops to the ground dead. This is a highly suggestive scenario of a lacerated vertebral artery where it crosses into the skull from the neck or along the path of the basilar artery. Internal findings show extensive subarachnoid hemorrhage over the brain, usually centered on the basilar brain. It can be very difficult to locate the tear after the brain is removed, as it may be cut during the removal process or be miniscule.

The procedure requires a vascular catheter, syringe, contrast material, and X-ray capability. It is done after the usual organs have been removed from the trunk and before the head is opened. The vascular catheter is threaded through the vertebral artery, which is located at the base of the neck as one of the branches from the subclavian artery, and tied in place to obstruct the artery from any backflow of contrast. A 20 cc syringe of intravenous contrast is then slowly injected into the artery and a series of lateral X-rays of the head are obtained to look for leakage of contrast within the skull. If uncertain of the extravasation, the catheter can be left in place and the head opened, but the skull cap not removed to support the brain. This way, the basilar brain can be observed during a repeat injection through the catheter to see any leakage from the basilar artery vasculature. A syringe of water can then be slowly injected to locate the rupture.

If the vertebral artery can't be catheterized, the carotid artery can be attempted to show a rupture through retrograde flow. Sometimes neither method works and the pathologist is left with an acute subarachnoid hemorrhage. Fixing a brain with subarachnoid hemorrhage worsens the situation because the blood becomes very stiff. The easiest method to locate vascular abnormalities, such as a berry aneurysm or vascular malformation, is to remove the arachnoid membranes and run the basilar brain under water to view the Circle of Willis. This requires time and patience so as not to tear the delicate vasculature.

Subcutaneous dissections for demonstration of subcutaneous hemorrhage

This is usually done to demonstrate the location and extent of bruises in the subcutaneous tissue that may not be well visualized from looking at the skin. Contusions are bleeding into the fat of the skin and may extend into the underlying muscle. By dissecting between these layers, this can be better visualized. Typically, it is done in child abuse cases over the anterior and posterior torso, extending onto the buttocks and legs, looking for the presence and extent of inflicted injuries. Skin biopsies can be taken from these areas for microscopic evaluation and lend information about the timeframe they occurred in.

Tongue removal with the neck organs

The tongue is removed to gain a good view of the posterior mouth, upper airway, and mouth. It is dissected to look for intramuscular hemorrhage associated with seizures, or to evaluate trauma that might be obstructing the airway.

The hazard of removing the tongue and neck organs is damage to a carotid artery, making embalming of the face more difficult. Another hazard is nicking the anterior neck skin, which creates a huge hole in an area visible in a casket, and will require repair (referred to as a buttonhole). A couple of key points of the dissection will make it easier and decrease the possibility of this occurring. To give the prosector (person doing the dissecting) plenty of visualization of the field the top horns of the Y incision can be extended to the top of the shoulder or even slightly posteriorly toward the back. An extra inch at that location will give more flexibility into the chest flap as it is stretched upward to view the base of the mandible. To prevent buttonholes, the fold should be in the retraction hand and the blade in the other hand pointed downward toward the muscle. The skin should be dissected away from the neck muscles until the submandibular salivary glands and edge of the mandible are in view. Holding the chest flap and fold in the retraction hand, the blade of the knife is inserted along the inner edge of the mandible upward into the mouth, dissecting along the inner edge of the mandible to loosen the base of the tongue. When the back angle of the jaw is reached, using scissors pointed to the inner-edge medially, the remaining muscle is cut down to the cervical spine. This is a key spot to avoid clipping the vessels that are very close by. After this, the scissors are inserted in the mouth, clipping any residual membranes and muscles holding the tongue in place. Then, by reaching into the mouth from the neck, the tongue is retracted downward so it is free and will release when the neck is dissected. Returning to the neck and using a scalpel, the right and left margins should be gently dissected, keeping the blade parallel and pointed medially along its length. This will keep the blade free of the vessels within their membranes along the lateral edge. Both sides of the neck muscles should be worked until it comes free. Care should be taken to not fracture the hyoid bone by pressing inward on the upper neck tissue. The tongue should be attached to the upper neck organs as well as the hyoid bone, epiglottis, thyroid cartilage, and tracheo-laryngeal cartilages.

Counting ribs or the spine for fractures

This seems like it should be straightforward, however, it is easy to get confused by the normal contours of the bones being obscured by blood and muscle tissue. It is easiest to locate the first rib on either side of the chest, which is located directly under the clavicle, and trace its course to the back to the spine, which is T1 (thoracic vertebra 1). This can be done consecutively along the sides of each pleural cavity to count locations of the rib fractures. **Anterior** is defined as from the anterior axillary fold extending anteriorly; **posterior** is from the posterior axillary fold extending posteriorly to the spine and lateral under the armpit. These location distinctions are important as they give an indication of how the force was applied to the chest. The intercostal spaces are named for the rib directly above the space and similar injuries to these areas are recorded.

Finding the ribs and tracing them posteriorly from T1 downward or upward will also assist in documenting a fractured spine. As a quick reminder, there are 7 cervical vertebra followed by 12 thoracic vertebra then 5 lumbar ones before the spine connects to the sacrum at the pelvis. The first through tenth ribs connect via cartilage to the sternum anteriorly leaving the eleventh and twelfth ribs floating along the posterior chest.

Airplane, train, and pipeline fatalities

The focus of this type of investigation is twofold. One is to identify and determine the cause of death of the persons who died during the accident, and two is to aid investigators to determine why the accident occurred. The focus of the latter is to identify the engineer, pilot, and crew to determine their cause of death and obtain toxicology samples. The National Transportation Safety Board (NTSB) is the regulatory agency and has a protocol for routine collection of toxicology from the pilot/engineer and the copilot/train crew (called brakemen or conductor). The kit comes in a Styrofoam packing box and is obtained directly from the NTSB prior to the autopsies. It includes a detailed explanation of all the specimens required that must be obtained during the autopsy and the specimen collection devices.

REFERENCES

[1] FTA® Technology. National Forensic Science Technology Center; 2013. Retrieved from www.nfstc.org/pdi/Subject03/pdi_s03_m04_02_d.htm. [October 2013].

[2] Schoebel P, Weiss S. Photography of Medicolegal and Forensic Autopsies. Evidence Technology Magazine 2009;7(3):10–3, 28.

CHAPTER 6
Identification

Learning Objectives

- Compare and contrast the three most common ways to confirm identity of a decedent. Include the positive and negative aspects for each method.
- Discuss the process of identification of skeletal remains by both nuclear and mitochondrial DNA. Include the family members who could supply a test sample for each.
- Illustrate by a flow diagram how you might attempt to identify an unknown decomposing body of a person who was transient and died in your jurisdiction.
- Compare the NCIC versus the NAMUS organizations for potentially identifying an unknown decedent. Discuss who may enter the data and who may view it, as well as data types entered.

Key Terms
Edentulous
Premortem
Postmortem
PCR
Mitochondria
Nucleus
CODIS
NAMUS
IAFIS
NCIC

Chapter Summary

Identification is a very important part of a death investigation because it is the initial premise upon which the remainder of the investigation follows. The wrong identity has severe repercussions and can lead to civil lawsuits and at a minimum bad press and embarrassment, if identities of two decedents are confused. Verification of a properly identified body is also important. It is good to have two people, the funeral home personnel and in turn to the family, visually confirm the identification tag on the body and obtain signatures on the release forms by both parties. There are multiple scientific modalities available to achieve a positive identification, but the key is usually finding material to connect the decedent with a known identity and then next of kin.

INTRODUCTION

Proper identification of a decedent has many implications. It ensures that the death certificate was issued on the proper person and his or her estate and affairs may be closed with certainty. In the age of extensive identity theft, it allows us to verify scientifically who the decedent is, which also will trigger the closure of various files regarding that identity, including social security benefits, outstanding warrants, FBI and state law enforcement files, bank accounts, and various estate documents. Proper identification allows the death certificate to be linked with the birth certificate to prevent unauthorized used for identity theft. This linkage is provided automatically via the 1992 Vital Statistics Act [17].

Paperwork in and around the body is a start for an investigation but it can easily be placed in the decedent's possession or previously created by the decedent as part of a new identity. More scientific means are necessary to verify the person's identity.

In addition, it is important to protect the decedent and his or her family from potential identity theft. Victimizers surf obituaries for information about funeral times to break into the residence or lift mail and credentials and create fraudulent claims against the estate [4]. When the death certificate is filed, the funeral home practice is to gather the social security number and notify the Social Security Administration Office or a family member can notify them as well. The Social Security Administration Office maintains a Death Master File that credit agencies and financial institutions can use as a resource to prevent using the decedent's credentials [3]. The Social Security Administration Office, Veteran's Administration, car or house insurance, and unions or workplaces may serve as financial resources for the family to check for death benefits to aid them in final disposition.

For identification, it obviously requires two parts, either of which can be problematic. It requires being able to obtain a piece of data from the decedent and to be able to locate a record of that type of data somewhere to compare it to. As we discuss the various methods to make identification, helpful hints will be given to deal with either issue.

FINGERPRINTS

Fingerprints are the fastest, least-expensive means to verify an identity and clear various law enforcement records (Figure 6.1). They are easily obtained and transmitted electronically either by scanning the prints in high resolution or by actually photographing the fingertips (the image has to be inverted to compare as it is a mirror image of an actual fingerprint). Portable electronic fingerprint scanners are also available to transmit the image directly to law enforcement for verification.

Integrated Automated Fingerprint Identification System

The FBI has maintained a fingerprint identification system called Integrated Automated Fingerprint Identification System (IAFIS; a.k.a. AFIS) since 1999. **AFIS** contains fingerprints obtained directly by the FBI, as well as those submitted by various law enforcement agencies, and contains over 56 million criminal record prints and 250 million civilian prints. It operates 24 hours a day, 365 days a year. From the time of submission for a criminal record check, results are able to be reported back to an agency usually within minutes to one hour. The rapid turnaround allows law enforcement to connect fugitives with



FIGURE 6.1
Fingerprinting a decedent in full rigor or following postmortem changes (e.g., decomposition, mummification, or "washerwoman" hands) can be a challenge.

the appropriate law enforcement agency. The current system is able to search for latent prints (prints left at crime scenes), as well as fingerprints associated with known persons. The system can also provide various identifying characteristics including height, weight, hair and eye color, and tattoos. It is currently unable to identify or store palm prints [6].

The next generation of identification by the FBI will be called Next Generation Identification (NGI). This will vastly expand the identification capabilities and includes biometric identification (including facial recognition), photographic documentation of tattoos and other identifying marks, and expanded fingerprint capabilities including latent and palm prints [7]. Biometrics is becoming an important parameter for another modality of identification beyond fingerprints. The study of biometrics includes iris scanning, facial recognition software, voice comparison, ear scanning, and multiple other individual characteristics, and is expanding rapidly. Unfortunately, retinal scanning technology does not appear to work for identification after death. Further research will need to be completed on all areas of biometrics and their applications to decedents.



FIGURE 6.2
(A) Dried, wrinkled hands due to mummification of an unknown decedent. The hands were processed using a sodium hydroxide technique to soften and inflate the skin of the hands. (B) The fingertips after four days of this process were able to produce readable fingerprints for comparison (see appendix for procedure).

Most states contain statutes pertaining to obtaining fingerprints of the dead and forwarding them to the respective state law enforcement agency. This serves at least two purposes: to verify the identity on all decedents and clear the clutter out of the law enforcement database.

The problems with getting prints from decedents are:

- Decomposition
- Mummification
- "Washerwoman" hands
- Skeletal remains

Each of these **postmortem** changes present challenges but has potential solutions, including rehydration procedures and subcutaneous inflation by embalming fluid (Figure 6.2). The appendix has procedures that may prove helpful to restore prints on mummified or washerwoman hands. However, in some cases, prints will not be feasible and other methods for identification will be needed.

Locating prints for comparison

Prints are available in various databases for comparison. If someone has a criminal record, he or she can be located in a local law enforcement file or FBI file (**IAFIS**). Other noncriminal files of prints are available as part of criminal record checks for various government jobs. Jobs or situations that can require prints are physicians, lawyers, teachers, police, military and security jobs, corrections officers, various financial and banking institutions, applications for firearms permits and dealerships, various medical personnel, and, in some states, those seeking social welfare benefits. These may need to be accessed separately during a search.

Immigrations and Customs Enforcement (ICE), a division of U.S. Department of Homeland Security, keeps a separate database of individuals crossing the border or with customs infarctions. They accept prints in a scanned format and can search through their database as an additional resource. The United States does not require fingerprints to obtain a passport. However, a passport is linked to various photo identification items that may have a fingerprint such as a driver's license. Since August 2007, passports contain integrated chips within the back cover. The information on the chip contains the same information as the back cover with a digitalized photograph used to biometrically match the holder to the passport using facial recognition [5].

Not every state requires a fingerprint (usually thumb) as part of an application for a driver's license. At this point, California, Colorado, Georgia, and Texas retain a database as well as Honolulu County, Hawaii [1]. The lack of this information seems to have been challenged as an invasion of individual privacy laws and expansion of fingerprints on driver's licenses in many states has been struck down over the years.

Banks requiring a thumbprint for check cashing by nonaccount holders reportedly do so to deter check fraud and they do not have their own database. Their recommended practice is to scan the thumbprint on the back of the check as part of their electronic record and to serve as a natural deterrent for check fraud. If fraud occurs, the check with the print can be given to law enforcement for follow-up. It was conceived by the Texas Bankers Association, and since its inception in 1982, banks and financial institutions have seen at least a 50% reduction in check fraud [2].

Case Study

***Sun Times* Article: Fingerprint for Driver's License Comes Back to Haunt Man Wanted for 1994 Shooting** For an interesting case in which driver's license fingerprinting helped identify a criminal assuming a fake identity, go to http://www.suntimes.com/news/crime/13955879-418/fingerprint-for-drivers-license-comes-back-to-haunt-man-wanted-for-1994-shooting.html.

DENTAL IDENTIFICATION

When unidentified remains are received at the death investigation office and fingerprint identification is not helpful, full body X-rays including anterior and lateral X-rays of the head can be done looking for medical-care appliances and the presence of dental restorations. In addition to the tooth amalgams, implants, root canals, and faint outlines of ceramic caps can be seen. Any of these items can be characteristic in their configuration in a particular location to make identification possible. The challenge is knowing the person had restorations done but being unable to find the **premortem** X-rays for that person to make the positive identification.

For true John/Jane Doe decedents, missing person reports can be scanned for someone missing with the physical features of height, weight, approximate age, gender, and any identifying scars or tattoos. Families or employer health plans are the best source for the location of the premortem dentist. If that person is located, it is hopeful the X-rays have not been purged or the practice dissolved and the location of records unknown. If they are located, the comparison can be relatively rapid especially if the pre- and postmortem records are digital and can be emailed to the dentist at his or her practice. He or she compares the morphology of the outlines of the restorations in a particular location to those in the premortem X-rays. Depending on the interval between the two, there may have been additional dental work done that does not appear on the premortem X-rays and the dentist may also rely on tooth root structure to add further certainty to the identification. See Figure 6.3.

Dental consultation is not helpful in cases where the person is **edentulous** and wearing dentures. Most dentures have no identifying marks in them to aid



FIGURE 6.3
(A) Postmortem X-ray of the dental restorations of an unknown decedent. The investigator found a possible name of the decedent and located the dentist who provided antemortem (before death) X-rays to the forensic odontologist (B). The intricate pattern of restorations in matching teeth locations provides a positive identification.

identification, although some dental offices now have a serial number and/or the dentist's name somewhere on the dentures. The root structures are removed with the teeth, resulting in only uncharacteristic ridges along the mandible and maxilla. Rarely, the wearer may carve something in the plastic portion that characterizes the denture. Dental associations have been discussing the possibility of embedding an identifier within the denture mold as it is constructed and would resemble the serial numbers attached to medical care prostheses. However, this has not been accepted by the dentists or their association as a reasonable practice. Partial denture plates may be more characteristic and are attached to residual teeth within the mouth so dental consultation will be helpful in those cases.

An interesting comment by a forensic dentist is that they can sometimes identify other dentist's work just by observing the quality and characteristics of restorations. In poorly done restorations (as is done in poor countries) the restoration morphology may give clues to direct the investigation. All unidentified bodies need to have a dental chart and consultation done prior to the release for a county burial.

If the premortem X-rays are film, it may require the investigator to drive to get them or a delivery company to mail them overnight. It is always good advice to families who have someone who goes missing to hold onto a hairbrush or toothbrush and store it in a paper bag for possible DNA, and to gather any dental and medical records to hold onto in case the person is later found.

Sometimes the only record available is paper dental charts. These can be helpful or not depending on the quality of the recordkeeping. Sometimes errors are recorded that may cause the inability to make a positive identification or even confuse the issue more.

A circumstantial or supportive finding can be photos of the person showing a dental exposing smile. Some individuals have characteristic gaps or superimposed teeth patterns that may be characteristic and can assist investigators to search for further information to confirm a positive identification. This finding can be helpful in skeletal remains to narrow possible matches.

MEDICAL APPLIANCES

Prosthetic medical appliances like knees, hips, surgical plates, and many implants, including breast implants, have brand and serial numbers embedded on the surface. When the item is implanted the manufacturing company is notified of the name of the person and his or her demographic information, and it is filed with the surgical appliance serial number. It can be a relatively easy match between the identification on the appliance to a name and last known location by contacting the manufacturer or locating the information in a medical chart where it is also recorded. Pacemakers also have similar model and serial numbers that can be traced through the manufacturer (Figure 6.4). Whenever an embedded pacemaker is in place, even on an identified decedent, recording of



FIGURE 6.4
(A) A pacemaker with the embossed manufacturer and serial number that can be used to locate the name of the person to whom it was implanted. (B) The surface of a breast implant imprinted with the manufacturer and serial number as another example.

the information via photograph can prove useful. In newer models, pacemaker function can be verified by clinicians in the early postmortem period and may require the assistance of a cardiologist.

SKELETAL STRUCTURES

One of the most characteristic skeletal structures that is said to be as good as a fingerprint is the outline of the frontal sinuses of the skull. In the past, anterior skull X-rays were common to evaluate for head injuries as well as assessment for sinus infections. This view is rarely done today because of more advanced imaging techniques. It is important to screen bodies for prosthetic devices that can be characteristic in their positioning and provide possible manufacturing information to aid identification (Figure 6.5).

CT and MRI scans are very detailed images of bones and internal structures on cross-sections or longitudinal sections, but are not usually helpful to compare bone outlines or even internal structures. The other issue is the modality of an X-ray needs to be compared to the modality of another X-ray and most death investigator offices do not have CT or MRI technology available.

DNA

DNA is a certain way to make identification. For this reason, DNA blood samples are held on most individuals examined by most coroner/medical examiner offices. The DNA is usually isolated from nuclei within the white cells of the blood specimen and not the red cells (they do not contain nuclei), but can be retrieved from any cells containing nuclei, such as skin or muscle. Obtaining DNA from a decedent can be a challenge depending on the status of the remains.



FIGURE 6.5
(A) The remains of the tibia of a decedent burned in a house fire and the metal plate is visible on the bone. (B) A postmortem X-ray obtained from the decedent to compare to (C), which is the antemortem X-ray of a potential identity. Note the placement of the screws and their position to one another, which allowed for a positive identification to be made.

Pure skeletonized remains are the most difficult because they have been subjected to environmental changes and time that causes the DNA to deteriorate and at a minimum decrease in volume. In addition, the putrefaction introduces bacterial DNA, which can overwhelm the small quantity of the unidentified person's DNA that remains during the amplification process in the laboratory.

DNA comparison is similar to dental comparison in that it can be retrieved from a decedent but the location of a match to a missing identity is not always easy. Other questions include: Has there been a chain of custody to an item from a known identity or relative's blood specimen so if a match is made it is a valid assumption? Is the DNA of a missing person in the system so a potential match is possible? Not all missing person's DNA is placed into the system or even available. Some families do not even realize the person is missing or have access to the items necessary to provide DNA to law enforcement. Missing persons can be homeless or runaways and links to known identities blurred by distance from next of kin.

To find a premortem DNA result is highly unusual unless the unidentified decedent had been convicted of a felony and it was retrieved as part of the usual law enforcement process. It's becoming increasingly helpful that most children now have DNA kit and fingerprint collection programs for parents at the children's schools. The military also maintains a DNA database on enlisted



FIGURE 6.6
The state of Missouri instituted DNA procurement from all felon offenders in 2005 and submitted them to CODIS. Even with a large backlog of samples and short duration of the data input, note the drastic rise in the number of hits linking the entered DNA to other crime scenes.
Source: [16].

personnel. Each state has passed laws of convicted crimes (usually homicides, sexual assaults, burglaries, assaults) in which submission of a DNA sample is mandatory into the state's DNA database (Figure 6.6). Many states and law enforcement officials have requested to expand this sampling to other or even all convicted offenses or during any arrest, which might include a DUI. Some feel this is overstepping the boundaries of privacy and protests against this extent of sampling have been raised. The concern is not only the privacy of the arrest, but the ability of other government agencies or even private agencies to access the DNA and gain knowledge about preexisting DNA sequences for risk of diseases or other abnormalities. The extent of law enforcement and judicial reach for this material is an interesting ethical debate for solving crimes versus privacy.



Crime Scene DNA
Which of the two potential suspects was at the scene and left DNA evidence?

Suspect 2 was the one who left DNA at the scene along with the victim DNA. For a successful match, all the DNA bands of the suspect should be at the crime scene. Missing bands means the match is not complete and another suspect is more likely. The more suspects at the scene, the more complicated the bands are to sort between contributors.

FIGURE 6.7
DNA subjected to electrophoresis with an example of comparison of recovered crime scene DNA to potential suspects and the victim.

The FBI received over 1 million profiles into the CODIS database for a total of over 9 million profiles in 2012 with over 150,000 investigated crimes aided by the information (Figure 6.7), most of which were within the state where the information was submitted [14]. The number of wrongly convicted felons who have been found innocent through the Innocence Project's postconviction DNA program is estimated at over 300 [15]. The latter is a positive bonus to the routine addition of the DNA to the database.

DNA samples from unidentified decedents can be compared to a mother and father to make identification (Figure 6.8). This can open another social issue that the reported father is not a DNA match but the mother is. Investigators have to be prepared to deal with this event in case the results come back in that fashion.



Paternity testing
Which of the two potential male DNA patterns match the child?

Male 1 matches the child and is most likely the father (of these 2 sets of DNA). The child inherits half its DNA from the mother and half from the father.

Each DNA location to check for matches was chosen because it has a specific frequency within the population. By computing the frequency of each of the male matches to the child, an overall match specificity can be determined. If the computation result shows the match occurs in 1 in 500 males to that child, it is less specific than a match of 1 in 1 million of the male to the child.

FIGURE 6.8
DNA subjected to electrophoresis as an example of paternity testing. The same type of methodology can be used to match an unknown decedent to the parents if their DNA is available.

If the father is not available, mitochondrial DNA from any family members from the maternal lineage will carry the decedent's DNA in the **mitochondria** of his or her X chromosome. Performance of mitochondrial DNA testing is more expensive than conventional nuclear DNA testing and costs between $1,000 and $1,500 per specimen. So in most cases there are at least three specimens: the unidentified and two maternal relatives.

Human DNA is largely the same among all of us and contains small repeating sequences that make each of us unique, called **polymorphisms**. It is these small repeating sequences called **short tandem repeats (STRs)** that are isolated within the laboratory and amplified by a procedure called **polymerase chain reaction (PCR)**. PCR basically acts as a copy machine making more copies of the isolated DNA. These short tandem repeats are then separated out by a process called **electrophoresis**. Each of the STRs has a particular charge reflecting its size and types of amino acid components. When they are placed onto a gel plate, these small pieces of DNA will move along the current and spread out in a particular linear pattern based on this charge. They can be identified by the various combinations of patterns of the STRs using up to 13 standard probes. Each STR has a particular statistical incidence in the population. By identifying key STRs a statistical incidence can be determined. Comparing the patterns from two individuals using statistics, a value can be computed for the match and the likelihood of this match occurring elsewhere in the random population. A match of 1 in 500 means the DNA comparison was not very unique and within every 500 persons there will be a match. A value of 1 in 1 billion is a high degree of probability that the DNA is a match and only 1 in 1 billion persons will have the same match.

Because of this amplification procedure to retrieve enough DNA to work with in a laboratory, even a small amount of contamination by another source, such as mishandling without gloves, sneezing on a sample, or bacterial contamination, can render a sample useless. For this reason, it is important not to eat, drink, spit, sneeze, or handle evidence without gloves or a mask. Mixed DNA from multiple sources can be very challenging for the laboratory to render a meaningful result. An example is a sexual assault by multiple perpetrators. During the isolation, multiple STRs will be isolated and the challenge comes from figuring out which STR belongs to which perpetrator and determining a meaningful statistical incidence.

In poorly preserved specimens or those yielding low DNA, such as dried bone or teeth, nuclear DNA will be present in small quantities and another specimen is desired. Mitochondria are small cellular organelles with each cell containing between 1 to 10,000 mitochondria and one **nucleus** (Figure 6.9). Mitochondria contain DNA inherited from our mothers (maternal DNA) and each maternal relative will have related mitochondrial DNA. Testing on these samples can yield a result that will relate the decedent to the maternal family but is not as specific as nuclear DNA because all maternal relatives will be a match. It is more expensive and time consuming so it is used only if the nuclear DNA specimens are not useable or available.

CIRCUMSTANTIAL

Circumstantial identification may be necessary in some cases where fingerprints are not available or a more scientific method is not available or financially feasible. The process will utilize the pathologist, the investigator, the resources available, and the scene findings. A 90-year-old woman found unresponsive in her secure residence may be allowed to be identified circumstantially or require



Nuclear DNA is inherited from parents, ½ from the mother and ½ from the father.

Mitochondria are located in the cytoplasm of the cell and are present in large numbers in each cell. They act as power houses for the cell and only contain DNA from the mother and her maternal relatives.

FIGURE 6.9
Nuclear versus mitochondrial DNA.

review of a chest or other X-ray by the physician as additional data to make identification without further consultation. In a similar but different situation, if the 90-year-old woman was found in the desert after wandering away from her home or care center, more diligence would be needed to confirm the identity.

UNIDENTIFIED

Sometimes, after searching for any and all the above categories, a decedent remains unidentified. At the time of this writing, more than 40,000 decedents in the United States remain as Jane or John Does and were buried or cremated without an identify [13]. In any single year, medical examiner/coroner offices handle over 4,000 unidentified remains, which after one year, more than 1,000 remain nameless [9]. The problem is not only the return of the remains to the families but also to follow up on crime leads and determine a final disposition of the remains. As technology advances, old cases, previously known as Does, have the technology available to identify some of them or advance the investigation. These are known as cold cases and whole squads of law enforcement have been created to assist with solving crimes related to them. These squads review available evidence and circumstances for materials that may be subjected to improved scientific methods to aid information about identity or suspected perpetrators.

PROCEDURES FOR IDENTIFYING THE BODY

It is important the body has identification tags or bracelets directly attached to prevent confusion of bodies in the morgue. The best method is for the investigator to attach this identification directly at the scene prior to the body bag being closed and sealed as part of the chain of custody. By marking the body with an identifying bracelet, the morgue personnel and pathologist can be assured the body matches the case intake information in the database and was not confused in transit. Some removal companies arrive with more than one decedent at a time and it would be easy to mix the identities if safeguards are not used. If the body is at a hospital, it is important that medical personnel begin the chain of custody by identifying the body to their medical file for the arriving investigator. A hospital identification band should be on the body prior to its removal by the transport company or investigator. A second bracelet signifying acceptance into the coroner/medical examiner office should be placed on the body in addition to the hospital identification.

Plastic identification bracelets placed on an ankle are unobtrusive, durable, and do not interfere with evidence collection from the hands. They are also hidden and funeral homes usually leave them in place for the same reason so bodies removed from the coroner/medical examiner will have a chain of custody through them to the grave. It protects all parties involved from the scene and back to the family. These bracelets can be left slightly loose to remove socks but tight enough so they do not slip off the ankle. They are marked with permanent markers so blood, water, and fluids do not remove the name. Two bracelets can be hooked together for obese decedents if necessary. It is useful if the bracelets are a different color than the ones used by the local hospitals to signify it as originating from the coroner/medical examiner. If the identity is not known, the body can be marked with "unidentified" and the case number or the address/location where he or she was found. When identification is made, the initial bracelet is not removed but instead a second bracelet is added with the identified name and case number. Toe tags are less desirable for a few reasons. Largely, they are paper and can tear and are not waterproof, allowing body fluids to imprint over the information. A tag adherent to the toes can come off, and after it is off, the identity may be in question.

A safeguard to sort out a possible confusion is to always take an identification photograph of the face at the scene as well as a cleaned face, preferably with and without its associated case number, which can be shown to a family member if needed. Good photos of tattoos, especially if they are characteristic, can also be used to differentiate bodies. Overall, photos can also be a good safeguard and backup for sorting out bodies in the morgue and comparing the photos to scenes.

Combined DNA Index System

The Combined DNA Index System (**CODIS**) is an FBI database that stores DNA profiles from multiple sources. It includes the DNA results from crime scenes (called the forensic index) and those offenders convicted of violent crimes (called the offender index). Input into the database comes from local levels that flow to state-level crime laboratories and eventually to the national level at the

FBI. This allows communication of DNA profiles across state lines for solving crimes and linking them to potential offenders.

The crime scene data that is entered has not been a subject of invasion of privacy but the volume of data has vastly increased the need for more DNA scientists and automation. The offender index also places stress on the already taxed system because of the desire for inclusion of more offenders' DNA profiles to aid in solving crimes. Offender crimes subject to mandatory collection vary from state to state as well as the rules for collection. Some of the questions that arise are: When will the collection take place, upon arrest or conviction? Before or after appeals? Who will perform the collections? Which offenses qualify for the collection? Does it require a court order? It quickly becomes complicated, and the list of offenses qualifying for collection can be very detailed. The National Institute of Justice published an article discussing some of these issues entitled "Collecting DNA from Arrestees: Implementation Lessons" with a map showing the various state differences [12].

There is no doubt that the database is helpful to linking crimes between jurisdictions, as well as being responsible for solving cold cases with few leads. It has also been responsible for freeing those wrongly convicted via a DNA match to other offenders.

National Crime Information Center

The National Crime Information Center (**NCIC**) database by the FBI has many subfiles, including types of crimes for development of statistics regarding various violent crimes, where the crime is committed and assists with targeting and fighting crimes in particular areas through resource allocation [10].

Within the NCIC is a missing person database and an unidentified person database. This information is available only to law enforcement and the data must be entered by law enforcement personnel. The intake forms for both subfile databases are quite extensive and time consuming. The concept is that comparison of the two data files may give clues to potential identification of an unidentified person so that confirmation testing can be done. The data includes usual demographic information such as height, weight, hair and eye color, tattoo descriptions, and last known location or found location. For decedents it has a modified dental chart system to be entered. It is a cumbersome system and can yield large numbers of potential matches that then need to be narrowed one by one. Probably the biggest obstacle is the inability of public and death investigator access to search for potential matches based on clothing or other information that may be with the decedent [8].

National Missing and Unidentified Persons System

Because of the obstacles with the NCIC, the National Institute of Justice (NIJ) has sponsored a parallel database that is freely open to the public to search through hundreds of cases of found decedents, called the National Missing and Unidentified Persons System (**NAMUS**). NAMUS allows families, law enforcement, and coroners/medical examiner offices to easily enter searchable fields in the missing person portion of the system and will also accept photographs to be uploaded (Figure 6.10). Coroner/medical examiner offices have similar searchable fields and allow a distinction between a public area and a hidden area for confidential information, such as X-rays, dental X-rays, and information about the circumstances of death. The NIJ has volunteers of dentists, forensic anthropologists, and forensic artists to assist. The NIJ will also perform free DNA testing of relatives or remains.

Skeletal remains can be digitally photographed and the forensic artists have software programs to render facial contours from the skull structure that can be posted. If DNA has been done it will also include that information. Photos of characteristic clothing/personal effects, such as logos on ball caps or T-shirts, eyeglasses or watches, and tattoos, can all be posted in the public section. There are groups of community volunteers who routinely screen the website and try to provide the submitting parties with potential matches they may have found. It is proving extremely useful in the quest to locate next of kin and connect them with their deceased relative.

They have recently added a section for death investigators to post identified but unclaimed decedents where next of kin was not able to be located. This should also prove useful to aid the quest of unification.



An example of information that may be placed into the National Institute of Justice website, National Missing and Unidentified Persons System. This information may be viewed by the public as they search for their missing. [www.namus.gov]

Estimated age	Adult - Pre 80
Minimum age	50 years
Maximum age	70 years
Race	White
Ethnicity	
Sex	Female
Weight (pounds)	Cannot Estimate
Height (inches)	65, Estimated
Body Parts Inventory (Check all that apply)	
☑	All parts recovered
Notes on body parts recovered:	
A portion of the maxilla and a phalange were not recovered.	
Body conditions:	
Not recognizable - Decomposing/putrefaction	
Probable year of death	2013
Estimated postmortem interval	4 Weeks

FIGURE 6.10
An example of information that may be placed into the NIJ website, National Missing and Unidentified Persons System. This information may be viewed by the public as they search for their missing person [9].

HOW TO FIND NEXT OF KIN

This can be challenging and sometimes harder than making the identification of the decedent. Cell phones can sometimes help lead to finding next of kin by looking in the contact list for “Mom,” “Dad,” “Aunt Polly,” etc. Even if the person isn’t the closest next of kin they may have information on how to reach them. If computers are on, similar contact lists may be present in email programs. Investigators can look for address books, employer identification cards, or health insurance cards. Employers may have someone listed in their files for whom to contact in case of emergency. Similar contact information may be present in hospital admission files or dental/doctor offices. Social media can also lend clues to finding next of kin. Arrest records may also list next of kin or friends who know where they may be located. Personal papers at the residence or letters may also be clues. It is important to collect any of these papers at the scene and document the collected items in the report. There may be no opportunity to return to the residence once the investigator has left the scene. Personal papers may seem like a trivial bit of information but they can be invaluable in locating next of kin. Basically, imagination and fortitude may be necessary to find them to make death notification.

HOW TO MAKE DEATH NOTIFICATION

Notification to the next of kin is not easy. It is uncomfortable because we are inflicting painful emotions on others and it also brings forth personal feelings about death and our own morbidity. Families can react differently from extreme sadness to anger and striking out.

Good practices for making notification are doing it in pairs in case the investigator needs backup due to a family member collapsing or to assist with a more aggressive encounter. As a death investigator, a good practice is to be accompanied by law enforcement at the location. If a law enforcement member is doing notification, the assist can come from the death investigator or a chaplain. Most departments have a volunteer group of chaplains for such occasions who are on call and available 24 hours a day. Similarly, law enforcement will have volunteer translators available if needed to assist with multiple different language barriers.

It is best to make notification in person. Before beginning with the bad news it is important to verify the person is related to the decedent. If the family member lives a distance away and the notification cannot be made in person, a local law enforcement agency or death investigation unit can usually assist. It may be necessary for the investigator to be on standby to answer questions directly. Phone notifications can be done, but it is good to make sure the family member has a friend or other family members nearby in case of a medical emergency.

It is best to make the notification as soon as possible after the incident and identification is confirmed. Confirmation may require a boss at a worksite, a family member, fingerprint confirmation in motor vehicle accidents, or any of the methods noted earlier. It is important that the family receive the notification prior to being told by bystanders or the press. Most offices have a policy that names are not released to the press until notification has been made. However, the press can be very resourceful in high-profile cases. In cases where the identity is not yet officially confirmed but is pretty certain, family members can be notified that someone matching, for example, Bob's description in his car and with his identification was involved in a motor vehicle accident and is dead. Once official confirmation is made, the family can be called back. The family will usually have many questions at that point and the investigator should answer the best he or she can and leave contact information.

The words used to make the notification are also important. It is important to use direct, plain language to tell the next of kin the family member is dead. Words such as "he/she passed on" or "is no longer with us" are confusing and have been shown to delay the grieving process. It is best for the investigator to be invited inside the residence and asked to sit down. A good beginning is for the investigator to state that there is bad news about the husband, wife, etc. …, Bob or Sally. It is good to mention the person's name when referring to the death rather than use the words "body" or "decedent." This intro to the news is important as it warns the family member of what is coming and also confirms the husband's or wife's name to ensure the notification is being made to the right person. It is best to pause a moment while all this sinks in.

The next line needs to include the words "dead" or "he/she died," so there is no misunderstanding about the outcome of the event [11]. An example: "Bob was driving down highway 127 when he was in a motor vehicle accident and died at the scene." The family member may ask if is certain, and this is where the degree of confirmation of identity needs to be mentioned. He or she will have other questions, such as "How did it happen?" "Where is he now?" It may be necessary to arrange transportation for him or her to a hospital or to call another family member to stay with the individual. This is where a chaplain can be very helpful as he or she will have further comforting words and have time to spend with the family member. It is best to have arrived in separate vehicles so this can transpire.

A couple of questions an investigator has to be prepared to answer are "Did they suffer?" and Why them, why today?" An appropriate response to those questions can be difficult, but in most cases, the investigator can relieve some stress by saying the injuries were extensive and it doesn't appear that he or she suffered. As for why that particular day, this is very difficult and we ponder it every day. All we know is when it is our time, there is very little that can be done to reverse it. Many times, two people can be in the same situation and only one dies and there is no logical reason why that might be true. Or the person has a long-standing chronic disease and on a particular day suddenly dies.

The next of kin also may ask if he or she can see the decedent at the morgue. Each office policy and even state laws will vary in making that determination. Most offices try to discourage visitation and would prefer family members see the decedent in better circumstances at the funeral home for their grieving process.

It is helpful to leave contact information about the investigating officer and agency, as well as for the death investigator. Many offices have developed a pamphlet of frequently asked questions to answer what happens next and what does the family need to do. The pamphlet needs to include information about personal effects, the need to select a funeral home, and the phone and address of the office. If no family members are at a residence, this information can be left at the scene in case they come to the residence after notification.

REFERENCES

[1] Fazzalaro J, Cohen R. Submission of Fingerprints for Drivers Licenses. Office of Legislative Research, Connecticut General Assembly; 2001. Reviewed from http://www.cga.ct.gov/2001/rpt/2001-R-0858.htm. [August 2013].

[2] Thumbprint Signature Program. Indiana Bankers Association. Reviewed from http://www.indianabankers.org/displaycommon.cfm?an=1&subarticlenbr=16#Whatis. [August 2013].

[3] Social Security Administration's Death Master File (DMF). National Technical Information Service, US Dept of Commerce. Reviewed from http://www.ntis.gov/products/ssa-dmf.aspx. [August 2013].

[4] ITRC Fact Sheet 117. Identity Theft and the Deceased: Prevention and Victim Tips. Identity Theft Resource Center. Reviewed from http://www.idtheftcenter.org/artman2/publish/c_guide/Fact_Sheet_117_IDENTITY_THEFT_AND_THE_DECEASED_-_PREVENTION_AND_VICTIM_TIPS.shtml. [August 2013].

[5] The U.S. Electronic Passport. Bureau of Consular Affairs, U.S. Department of State. Reviewed from http://travel.state.gov/passport/passport_2498.html. [August 2013].

[6] Integrated Automatic Fingerprint System. Federal Bureau of Investigation. Reviewed from http://www.fbi.gov/about-us/cjis/fingerprints_biometrics/iafis/iafis. [August 2013].

[7] Fingerprints & Other Biometrics: Next Generation Identification. Federal Bureau of Investigation. Reviewed from http://www.fbi.gov/about-us/cjis/fingerprints_biometrics/ngi. [August 2013].

[8] National Crime Information Center. Federal Bureau of Investigation. Reviewed from http://www.fbi.gov/about-us/cjis/ncic. [August 2013].

[9] National Missing and Unidentified Persons System. Office of Justice Programs, US Dept of Justice. Reviewed from http://www.namus.gov/. [August 2013].

[10] Strategies and Available Resources for Use in Solving Unidentified Deceased Person Cases. Florida Dept of Law Enforcement, Medical Examiner Commission. Reviewed from http://www.fdle.state.fl.us/Content/getdoc/5de72e76-be9b-4e4e-b225-ed61087bf27e/MEC-Strategies-and-Current-Available-Resources.aspx. [August 2013].

[11] "In person, In time", Recommended Procedures for Death Notification. Crime Victim Assistance Division, Iowa Department of Justice; 1992. Reviewed from http://www.nationalcops.org/downloads/in_person.pdf. [August 2013].

[12] Samuels J, et al. Collecting DNA from Arrestees: Implementation Lessons. NIJ Journal 2012;(270). National Institute of Justice, US Dept of Justice. Reviewed from https://www.ncjrs.gov/pdffiles1/nij/238484.pdf. [August 2013].

[13] Ritter N. Missing Persons and Unidentified Remains: The Nation's Silent Mass Disaster. NIJ Journal 2007;(256). National Institute of Justice, US Dept of Justice. Reviewed from http://www.nij.gov/journals/256/missing-persons.html. [August 2013].

[14] CODIS Combined DNA Index System, brochure 2012. Federal Bureau of Investigation Laboratory Services. Reviewed from http://www.fbi.gov/about-us/lab/biometric-analysis/codis/codis_brochure. [August 2013].

[15] DNA Exonerations Nationwide Fact Sheet. The Innocence Project; 2010. Retrieved from http://www.innocenceproject.org/Content/DNA_Exonerations_Nationwide.php. [August 2013].

[16] DNA Profiling. Missouri State Highway Patrol. Reviewed from http://www.mshp.dps.missouri.gov/MSHPWeb/PatrolDivisions/CLD/DNAProfiling/DNAProfiling.html. [August 2013].

[17] Taylor P (chairperson). Model state vital statistics act and regulations. Center for Diseases Control; 1992. Retrieved from www.cdc.gov/nchs/data/misc/mvsact92b.pdf. [October 2013].

CHAPTER 7

Blunt-Force Trauma

Learning Objectives

- Outline the features of the four types of blunt-force injuries.
- Illustrate the features of an incision and laceration and label the characteristic differences.
- Outline injuries that are commonly seen on a driver and those seen on a front-seat passenger.
- Recognize common injuries seen on pedestrians and contrast those with bodies dumped by the side of the road after death. Apply what you have learned about postmortem changes as well as types of injuries.
- Identify common types of evidence that may need to be recovered, as well as photographs and information that may need to be retrieved or observed in investigations of death from a traffic accident.

Key Terms

Blunt-force injury
Abrasion
Contusion
Ecchymoses
Laceration
Incision
Fracture
Undermining
Avulsion
Dicing wounds
Pillars
Pathologic fracture

Chapter Summary

It is important to recognize the characteristics of blunt-force injuries to distinguish and accurately describe report notations. Use of proper terminology ensures proper communication of the type of injury seen and how it was produced. Good documentation of patterned injuries with and without scales will allow potential impact sights to be compared to potential instruments used to create the injuries, locate a potential vehicle, or determine how the injury occurred. Toxicology specimens can be challenging to obtain in these cases but it is important information as contributing causes or for prevention and statistical purposes.

INTRODUCTION

Blunt-force trauma definitions form the basis to describe many of the injuries seen in forensics. Blunt-force injuries are very common and are seen in varying degrees on most decedents, whether from a terminal fall, a previous injury, or as the acute cause of death. It is important to learn the proper terminology so the wounds are documented accurately. A pathologist uses these descriptions to make opinions about how the injuries occurred, what instruments were used

Case Study

Police were called after an elderly gentleman was found by his wife lying on the ground in his backyard. Surrounding the head area was a small pool of blood. When an officer called it in to the office, he mentioned bruises on the hands. Upon arriving at the scene, the death investigator noted a moderately sized elderly man lying on the ground adjacent to a backyard concrete bench. The clothing was appropriately positioned and not in disarray and he was wearing slip-on shoes, one of which was lying approximately two feet from the body. A pool of blood approximately 12 in. in diameter was seen under the head area. On the right side of the head behind the ear was a 1 in. laceration. The facial area showed two black eyes but no other trauma to the mouth or lower face. The hands showed small purple-red "old age bruises" seen with thin parchment skin. No fractures were noted of the extremities and no weapons were noted nearby with blood on them.

An autopsy examination was done and showed no rib, spine, or pelvic fractures. Severe atherosclerosis (hardening of the arteries) was seen in the coronary arteries and in the aorta. Examination of the head showed the laceration with an underlying depressed fracture of the skull (i.e., the skull was actually pushed inward putting pressure on the brain). The surface of the right and left brain was covered by a layer of blood between the surface of the brain and the dura. The brain showed a bruise over the left side of the cortex and over the base of the left frontal lobes. The thin, delicate bones over the surface of the eyes were fractured.

The pathologist concluded the laceration occurred during a fall, most likely against the concrete bench, resulting in the laceration, underlying skull fracture with subdural bleeding, and contrecoup contusions of the brain. The position of the bruising on the brain on the opposite side of the laceration is a contrecoup contusion seen in fall injuries. Inflicted trauma during an assault would have resulted in bruising on the same side as the laceration and fracture.

The cause of death was certified as "blunt-force trauma of head due to fall" with a contributing cause of "atherosclerotic cardiovascular disease." The mechanism of why he fell is unknown and could be related to a poor fit of the slippers, loss of balance, or from a cardiac event.

to inflict the trauma, the position of the decedent when the injuries occurred, and whether they occurred before or after death. All these questions are asked of a pathologist during testimony, as well as by law enforcement personnel during their investigation to correlate with the interpretation of evidence retrieved at the scene. The best way to gain expertise in the interpretation of injuries is to coordinate with law enforcement findings and use the knowledge of patterned injuries in known circumstances with the application to unknown death circumstances.

DEFINITIONS

Blunt-force injuries are defined as those where a force is applied to the surface of the body or where the body comes into contact with a surface causing an injury. It can be very important to recognize various patterns created by these surfaces or forces to aid the interpretation of how an injury occurred. An example is a cylindrical item, such as a pipe, striking the body, which creates a parallel pattern of the bruise. Another important notation is the location of the injury on the body. If a bruise is on the knees, it could be interpreted as due to a fall or it could also be seen in front-seat occupants of motor vehicle accidents where the knees strike the front panel.

There are four major injuries that need to be defined within this category: abrasions, contusions, lacerations, and fractures. It is important to master the definitions of these injuries and apply them correctly to a particular injury because the definition purveys how the injury occurred. This is especially important in the distinction of a laceration (created by a blunt object) versus an incision (created by a sharp object). The interpretation and/or pattern of the injury can direct the scope of an investigation.

The mechanism of death is defined by what physiologic function failed and caused the death. In blunt-force trauma injuries it is related to shock, usually from blood loss or brain–spinal cord disruption. These result from fractured bones resulting in blood loss by tearing blood vessels, lacerating vital organs, or causing the inability to exchange oxygen.

When certifying a death related to blunt-force trauma the basic question should always be: Why is the person dead? The degree of injury should match a lethal mechanism and, if not, further investigation is needed to explain the death either at the autopsy, toxicology, or scene investigation.

Abrasion

An **abrasion** is a scrape on the skin causing a loss of the superficial layers of the skin. It is created by a force sliding across the skin or the skin sliding across a surface (Figure 7.1). An example of the first instance is a tree branch creating a scratch on someone's arm while he or she is trimming a tree. An example of the second instance is when someone slides his or her knee across a carpet creating a rug burn. Because it is a superficial injury, it is described in two dimensions: length and width. It is also described by its color: yellow-tan, red-brown, or yellow-brown. An example of an abrasion description is the following: over the left forearm is a curvilinear red-brown 5 × 0.3 cm abrasion. The description includes a location, shape, color, measurement (in two dimensions), and the type of injury.

Abrasions can be patterned or have characteristic appearances due to the objects creating them (Figures 7.2–7.4). Common examples are brush-burn abrasions, gravel imprints, and specific objects such as bumpers or grills from the front of cars or muzzle imprints from guns.

Abrasions may have directionality depending on how the force is applied. At the site of origin, the skin is superficially sheared and can be piled up or with small skin tags where the force ends. This isn't always very important, but may help the observer differentiate two types of wounds if they overlap due to multiple mechanisms of injury interplaying at the same time.

As an abrasion heals, the edge of the wound tends to dry and become heaped up. The skin margin may appear slightly increased pink or white as the pigment repairs. Abrasions may also occur postmortem due to loss of the superficial layer of skin but will appear waxy yellow and with drying will be a light red color.



FIGURE 7.1
(A) A classic premortem abrasion with dark red-brown coloration and may be a rug burn. (B) A postmortem injury showing the waxy, smooth surface and adherent superficial skin fragment to one margin.



FIGURE 7.2
A brush-burn abrasion with large areas of superficial skin scraped from the surface. It is created by the body sliding across a surface or a surface sliding across the skin. It is commonly known as "road rash" because it is seen in accidents with pedestrians, bicyclists, and motorcyclists as the body is projected over the road surface.



FIGURE 7.3
(A) A woven-pattern abrasion on the back of a man crushed in a grinding machine. (B) The grinding wheel with the corresponding woven pattern on the cement.



FIGURE 7.4
An interrupted-pattern abrasion on a leg that matches the stitching of the pant leg. This demonstrates why the clothing is important to receive with the body to aid the interpretation of injuries.

Contusion

A **contusion** is commonly known as a bruise. It is created by a force being applied to the skin causing rupture of the small blood vessels and bleeding into the tissue under the skin surface (Figure 7.5). The color of the contusion (bruise) can vary with its thickness, location, and how long it has been present. The colors of the bruise change due to the breakdown of the blood into its iron components and



FIGURE 7.5
A recent contusion seen on an alcoholic after a therapeutic paracentesis, a procedure where a needle is inserted in the abdomen to withdraw ascites fluid. Contusions are subcutaneous collections of blood. They are more extensive with minor trauma in those people with a bleeding disorder or in alcoholics.

usually start in the red-purple range, transitioning to a green-yellow then yellow-brown coloration. How long it takes to transition can vary from one person to another, the thickness of the bruise, and its location, so it really cannot be accurately determined to a specific date or time. Dating is somewhat helpful to give a basis of injuries occurring over an extended period of time with evidence of healing of bruises. In decedents, biopsies of bruises can be performed and dated microscopically to a range of days.

Bruises may also be patterned. A classic example is that of a steering wheel or seatbelt imprint seen on the chest of a driver of a motor vehicle. Other patterns can be created by cylindrical objects such as bats, pipes, flashlights, batons, or rebar.

Bruises are three dimensional, however, it is difficult to assess the depth based on only observation of the skin surface. Most times contusions are described in two dimensions: length and width. A typical description of a contusion is as follows: over the mid-chest is an irregular, blue-purple, 5 × 4 cm contusion. The description includes the location, shape, color, size, and identifies the injury as a contusion.



FIGURE 7.6
An ecchymoses or old-age purpura commonly seen in the elderly with minimal trauma.

Interpretation of brain contusions is helpful in distinguishing if a head injury was created by an inflicted trauma or resulted from a fall. With patterned contusions, accurate measurements, photographs with scales, or even tracings can prove useful to link injury to a suspected force that created the bruise.

It is helpful to subclassify the superficial contusions commonly seen in the elderly on the back of the arms and hands and call them **ecchymoses** (Figure 7.6). These are typically superficial and pink-brown with irregular margins, and may result in tears of the skin. As a human ages, the skin becomes thin and fragile and can result in these injuries with minimal trauma.

Laceration

Lacerations are actual tears of the skin that result when the force being applied exceeds its elastic ability to stretch, causing it to tear (Figure 7.7). Its ability to stretch depends partially on the surface the skin is covering, such a cavity like the abdomen versus the firm stretching over the skull and face. Skin over the abdomen has the ability to stretch more than skin over the skull. When a force is applied to the skin over a local area it can exceed the stretching ability and cause the skin to tear.

A laceration is characterized by irregular margins with small strands of tissue connecting the edges of the wound. The margin of the laceration will contain an abrasion or contusion. These wounds have three dimensions: length, width, and depth. An example description is as follows: on the left hip is a T-shaped 6 × 4 × 2 cm laceration with bone and muscle seen in the depths of the wound.

It is important to distinguish lacerations from sharp-force wounds because the mechanism that creates each of them is different. If the wound is a laceration, the object is some sort of blunt instrument, versus an incised wound that is created by a sharp-edged object. The distinction is made by examining the margins



FIGURE 7.7
(A) The characteristics of a laceration with tissue bridging between the edges of the wound with irregular and abraded margins. (B) In contrast, an **incision** has smooth margins without tissue bridging or marginal abrasion.

and tissue between the edges of the wound. A laceration will have abraded margins with small pieces of tissue extending between the edges (called tissue bridging), and an incised or stab wound will have a smooth margin that extends into the depths due to the cutting by the instrument.

An **avulsion** is a subtype of laceration where the tear has created a flap of skin that is able to be lifted from the underlying muscle or bone (Figure 7.8A). Many times there will be a small shelf or beveled edge on the more pointed margin, which is the site where the injury began as the flap was created.

Another term used for lacerations is **undermining**. This description is used for skull injuries where the force is applied causing a pocket to form under the skin but it does not create a flap as seen with an avulsion (Figure 7.8B).

Fractures

The fourth term used in describing blunt-force injuries is **fractures** (Figure 7.9). The amount of force needed to fracture a bone depends on the bone, the age of the person, and the presence or absence of underlying disease affecting



FIGURE 7.8
(A) An avulsion where a flap of skin has been sheared off, an injury most commonly located on the head where the skin is stretched tightly against the skull. (B) Depicts undermining where a segment of skin is lifted from the underlying skeletal structure forming a pocket. It is commonly seen on the skull but may also be seen on the chest, buttocks, or over the large bones of the legs.



FIGURE 7.9
An X-ray of the lower legs in a pedestrian struck by a motor vehicle. Note the fractures of both legs just below knee level where the legs came in contact with the bumper of the vehicle.

the strength of the bone. Younger people have more elastic or durable bone than the elderly. A thin bone requires less force than a thicker, weight-bearing bone (e.g., rib versus femur). The presence of a bone disease, such as calcium loss (osteoporosis), infection of the bone (osteomyelitis), or a tumor that has spread to bone (metastasis), weakens the bone and allows it to fracture with minimal force that normally would not create a fracture in most people (called a **pathologic fracture**).

Fractures may be open where the bone ends extend through a skin laceration. The risk with open fractures even with prompt treatment is complications by infection, which may result in a medical amputation. Conversely, closed fractures are where the skin surface has remained intact and result in fewer complications.

Skull fractures may be linear or depressed. Linear describes a line fracture with the edges abutting against each other. Depressed is where the fractured bone is pressed inward and tears the underlying brain tissue.

A basilar skull fracture is one where the bottom, thick portion of the skull is fractured. This area is a vital region protecting the brain from the mouth/nasal area and the vital brain/respiratory centers contained in the brainstem.

The risk with fractures is the resulting tears of underlying tissues from the jagged bone margins. Life-threatening tears may occur in the heart, lungs, liver, spleen, large arteries or veins, brain, or spinal cord. The fractures may not be immediately fatal especially rib fractures, and can result in chest pain leading to poor inspiration of air and pneumonia. Tears in lung tissue can result in blood or air accumulating in the pleural cavities and poor oxygen exchange. Superficial tears of the surface membranes (capsules) of the spleen or liver can result in slow internal bleeding.

DOCUMENTATION OF INJURIES

Injuries are documented via direct visualization first with collection of any necessary trace evidence adhering to the skin followed by washing the skin surface to best outline any patterned injuries and measure them. Patterned injuries need accurate descriptions so that if a proposed weapon or surface is presented, it can be ruled in or out as the causative material.

Photographs include overalls, medium view, and close-ups with and without a scale. A medium view including the ruler is helpful so that the close-up view can have good detail and yet locate the injury on the body. If possible, it is always good to include a reference such as an ear, side of mouth or nose, a thumb, etc.

A right-angle ruler is best so that a scale is located in both dimensions of the injury. It is important to take the photo at a right angle to the plane of the injury so that there is no distortion to the wound measurements in the photo. The ruler should be placed so that one edge is parallel to the longest dimension of an injury and placed near the skin surface or level to the injury if it is a curved surface. A case number placed on one margin of the ruler is necessary for proper documentation.

Patterned injuries and toolmarks

Patterned injuries are extremely important in forensics. The patterns can be used to reconstruct the number and how the injuries occurred. Multiple accurate photographs with scales can be the best illustration to demonstrate in court and identify a suspect weapon at a later date. It may be helpful to trace a particular pattern onto clear plastic. This can be signed over to law enforcement as evidence and easily used to compare to various suspect objects with 1:1 comparison. An example is to trace patterned injuries on the skin of a hit-and-run pedestrian and compare them to the front of suspect motor vehicles. Grill injuries or particular hood ornamentation can be very characteristic.

Toolmarks can leave characteristic grooves on soft cartilage that can be matched to suspect weapons. Bone may also contain toolmarks from saw marks. These characteristic markings can be compared through expert databases of various types of cutting instruments. Because removal by medical saws creates their own toolmarks, it is important to excise a wide area around the evidentiary portion so that it is obvious to the comparing laboratory as the suspect area. It is usually preserved frozen to prevent distortion by drying or dehydration.

Coup versus contrecoup

Head injuries or blood surrounding or within the brain are common. The pattern of the skin versus the internal injuries allows for the distinction of inflicted trauma from an assault versus injuries due to fall versus bleeding due to a natural stroke. Many times the decedent is found down on the ground following an unwitnessed event.

Coup and contrecoup terminology is used when referring to head injuries. Coup injuries are defined as a force applied to one side of the head resulting in same sided brain injuries, with or without skull fractures. These injuries are consistent with inflicted trauma rather than falls. Contrecoup injuries are ones with an injury on one side of the scalp and brain injuries on the opposite side and are seen in fall injuries. This phenomenon occurs because of the way forces are transmitted through the skull and brain.

The same phenomenon does not apply to sidedness of subdural hematomas, blood accumulating between the brain and dura lining the internal skull. Subdural hematomas occur due to rupture of small veins and are not influenced by these forces. Either a fall or inflicted trauma may result in a subdural hematoma of either side of the skull.

The location of the injury on the head is also important to make the distinction between a fall versus an inflicted trauma. Classically, injuries above a hat brim are more consistent with inflicted trauma and below the hat brim more consistent with a fall. However, objects within a scene need to be evaluated for potential of inflicting the trauma. For example, some curbs or benches may result in injuries above the hat level depending on the mechanics of the fall. In interpretation of injuries, all information from the scene, autopsy, or medical findings need to be considered to make the distinction. This topic will be discussed more fully in Chapter 10.

MOTOR VEHICLE ACCIDENTS

Motor vehicle accidents are the most common cause of blunt-force injuries. Some questions that arise with them are:

- Was the person alive at the time of the accident or did the person die of an underlying natural disease?
- Were the injuries fatal instantly or did a potential delay in medical treatment affect the outcome?
- Who was the driver versus the passenger? Are the patterns of their injuries able to assist with their placement inside the vehicle? Were seatbelts in use?
- What were the underlying contributing events that may have caused the accident to occur?
- Are there underlying diseases that might contribute to the death or mortality after medical treatment? The underlying health of an individual may be used in the insurance computation of a settlement.
- Are there product or road safety concerns that need to be reported to prevent further accidents?

To answer these questions, a complete autopsy may be necessary. Documentation of the injuries via photographs and accurate descriptions of the injuries aids in the reconstruction of how the accident occurred. The collection of evidence on the surface of the body and clothing is necessary on pedestrian hit-and-run accidents to aid with linking a suspect vehicle to the decedent. An internal examination can verify the extent of injuries, underlying health and disease states, and accurate visualization of vessels for toxicology specimens. Utilizing

Case Study

Two occupants from a motor vehicle accident were discovered inside a vehicle by a passerby. One occupant was pronounced dead at the scene and transferred to the medical examiner's office. She was seated in the driver's seat with facial injuries, but investigators determined her description matched the driver's license demographics. The other occupant was alive and resuscitated. She had severe head injuries, underwent surgery, and was on life support at a local hospital. Relatives were at the bedside daily. The decedent was autopsied and released to a local funeral home where parents claimed she was not their daughter. Further investigation revealed the decedent was actually the daughter of the family sitting by the bedside and the hospitalized woman was the daughter of the family who thought their daughter was dead.

this multipronged approach leads to the most accurate determination of death for coordination with scene investigation findings.

Pertinent scene observations include seatbelt use, body position in vehicle when found, air bag deployment, type and position of the vehicle, skid marks, and witness statements about the event. With many motor vehicle deaths, bodies are deformed by their injuries and visual identification of the decedent with comparison to a driver's license photo is potentially erroneous. It is not uncommon for people to carry false identification or borrow a friend's vehicle. This makes it important to verify the identity of a battered decedent or even injured person via fingerprints, identifying scars, marks, or tattoos. Many states have thumbprints on driver's licenses that can be used for identification. Criminal records and resulting prints may also be used to verify the identity of a decedent and release the body to the next of kin with that identity. If prints are not available, dental identification may need to be done, especially in the severely injured.

Anatomy of a vehicle

SEATBELTS

Seatbelts are described as two-, three-, or four-point restraint systems. Two-point restraints are typical lap belts where there are two attachment points to the vehicle. Three-point restraints are the lap and shoulder harness typical in modern vehicles where there are the two lap belt attachments and the third point where the shoulder harness attaches to the roof area of the vehicle. Four-point restraints are found in race cars and pilot seats of airplanes and have two shoulder attachments in addition to the two lap belt attachments.

Seatbelts were first placed into cars in the 1930s by physicians who noted the increased safety this provided during car crashes. The idea of a restraint system had been patented in 1885 by Edward Claghorn of New York and consisted of ropes and hooks to secure the person to the car. The modern-day seatbelt was the idea of a Swede, Nils Bohlin, and consisted of a three-point restraint. Manufacturers lagged in endorsing the idea, and the Volvo was one of the first to utilize restraints routinely in vehicles and they were offered as an option in some Ford and Chrysler models in the mid-1950s. In 1959, Volvo included Bohlin's idea of a three-point restraint in their vehicles. But it wasn't until 1964 that most U.S. car manufacturers placed front seat lap belts in the vehicles. In 1965, European car manufacturers followed suit and included required front lap belts. By 1965, all 50 U.S. states required cars to be equipped with front lap belts. Two years later they were required in the rear seats as well [3].

Enforcement in wearing seatbelts varies from state to state. In some states, law enforcement operates under primary enforcement, which means failure to wear a seatbelt can allow them to issue a citation based solely on the failure to wear one while driving. In other states, it falls under secondary enforcement and the officer must stop someone for some other violation, such as speeding, to issue the citation for failure to comply with the seatbelt law. Surveys from 2011 show that in primary enforcement states, 88% of people wear seatbelts, whereas in secondary enforcement states, approximately 75% wear seatbelts [1]. Proper seatbelt usage is estimated to save thousands of lives each year, especially at highway speeds.

The purpose of seatbelts is to keep the person inside the vehicle, as well as help them decelerate, decreasing injury. They are designed to stretch with the impact and allow the person to move forward in the seat, even as much as 10 in. Knowing this, it is important to comfortably sit as far from the steering wheel to safely operate the vehicle and prevent impact with the stationary portions of the vehicle. Seatbelts, like any safety equipment, may fail and proper evaluation by the traffic investigator will assist in that determination. Seatbelts are rated to withstand thousands of pounds of force. During an accident, the webbing will stretch and leave wrinkles along the area of greatest stretch, which will allow the investigator to know if the seatbelt was in use during the impact. To differentiate a torn belt versus a cut belt, the margins of the tear can be evaluated for the stretch with frayed margins versus a clean cut made during extrication [2].

CAR SEATS

Tennessee was the first state to require child car seat use in vehicles in 1978. All states require children to be restrained by a restraint system, and for children less than four years old this is a federally approved car seat. In children four to six years of age, the child can be in a restraint car seat or seatbelt, which will vary from state to state [1]. All states require, at a minimum, that all children three or younger, weighing less than 40 pounds, or less than 40 inches tall, be secured in child restraint systems while traveling in motor vehicles. Most states also specifically require that child restraint systems meet applicable Federal Motor Vehicle Safety Standards [1].

AIRBAGS

Airbags consist of a plastic bag inside the steering wheel or dashboard for front-seat occupants and were placed into vehicles in the late 1980s and early 1990s. They were designed to decrease a front-seat occupant's contact with the steering wheel, windshield, or dashboard, and in turn decrease the severity of injuries. They were found to be very effective in this endeavor and were added to side doors to decrease injuries during side impacts. Some vehicles are now equipped with head sidewall bags called curtain bags and are located at the top of doors to decrease impacts to the head. All airbags are designed to be used in conjunction with seatbelts and are not to be used alone as primary restraints.

They are deployed via sensing triggers that set off a chemical reaction that releases nitrogen gas that fills the bag like an air pillow. For the front compartment bags, the sensors are located in the front bumper and set to deploy during a front impact. Other sensors may be in the seats or seatbelt fasteners. For side compartment bags, the sensors are located in the doors. Airbags may not deploy in some impacts if the vehicle contacts the object at an angle or in such a way that the sensors are not triggered. Airbags are ejected from their storage compartment with force and can create abrasions and contusions of the upper torso and face. In the very young and old, the force is enough to cause substantial injuries or fractures. For this reason, children should ride in the seat with the airbag switched off or occupy the rear seat where they do not deploy. Infant car seats should be rear facing to prevent injury to the child.

TEMPERED GLASS AND LAMINATED WINDSHIELDS

The type of glass used in motor vehicles is designed to decrease sharp edges and cutting ability by the breaking of glass that occurs during an accident. The front glass is composed of two thin sheets of glass laminated over a piece of clear plastic. During an impact, a strike by an object will cause the glass to fracture in a radiating pattern from the site of impact, but prevents protrusion of the object through the windshield and cutting tissue. This is a site that can be useful in the collection of hair or DNA to assist with positioning of occupants or the site of impact from a pedestrian. The head is a common site of impact with the windshield and results in superficial lacerations, contusions, or abrasions located on the forehead or scalp. See Figure 7.10.

Side and rear windows are tempered glass that is designed to shatter into small ⅛ to ½ in. irregular sharp shards of glass. These pieces have the ability to superficially cut the skin but not usually to the degree of a large slicing fragment of glass. The pattern produces characteristic dicing wounds, which may assist in positioning the occupants in the vehicle. It is useful to recognize these wounds in those where the position of an occupant is known so that the knowledge can be applied to those investigations where the occupants' locations are unknown or they are ejected. It is helpful for the investigator to have cut-proof



FIGURE 7.10
(A) Classic **dicing wound** injuries appearing as small Y-shaped superficial lacerations of the skin and result from the small shards of glass projected onto the skin from the side or rear glass windows of vehicles as they shatter (C). The sidedness of the dicing wounds can assist with placement of the occupants within the vehicle as seen in this ride sided passenger (B).

gloves on underneath normal latex gloves when dealing with motor vehicle accidents. It keeps him or her from being cut on the glass or getting the small pieces embedded in the skin. They are excellent to wear under latex gloves not only for protection from cutting or sticking, but they also offer a barrier so that when the investigator has to change latex gloves multiple times at a messy scene, the gloves go on and off with ease. They also add a little bit of warmth in colder climates.

PILLARS

When reviewing accident reports certain terms will be used to describe the vehicle. **Pillars** refer to the posts supporting the roof. The A pillar is the one nearest the hood, surrounding the windshield at the front of the doors. The B pillar is the one behind the driver and front passenger doors supporting the mid-region of the roof. The C pillar is the one surrounding the rear window or rear door in a hatchback. See Figure 7.11 for a diagram.

Skid marks

Skid marks are the black marks left on the pavement when the brakes are suddenly applied and the vehicle is still moving. Law enforcement investigators can measure the length of the skid marks to the site of impact and estimate the speed



FIGURE 7.11
The locations of the pillars supporting the roof and doors of a vehicle. Accident reports received from law enforcement will reference these points as areas of impact by the occupants during a motor vehicle accident.

the vehicle was moving when the accident occurred. Obviously skid marks are harder to evaluate on the pavement due to decreased friction caused by wet, icy, or oil slippery surfaces.

A vehicle operating on the road is governed by physics and is a mass (M = vehicle) moving at a certain speed (V = velocity) and possesses kinetic energy (KE). It follows the law of kinetic energy:

$$KE = \tfrac{1}{2}MV^2$$

This means that the amount of kinetic energy it possesses is not related to the mass of the object as it is to the velocity (or speed) it is moving. With a crash, the kinetic energy is absorbed by the vehicle and the occupants and the surface it impacts. Much of the kinetic energy is absorbed by the crushing and tearing of the metal and components. Cars are designed to buckle and crush in various areas to absorb the energy. However, they do have a point where they exceed the crush points and more energy is available to create injury on the occupants. The degree of energy depends on the speed and how much dissipation can be absorbed by the object the vehicle strikes. If it is another vehicle, the vehicles will share the combined energy. If it is a stationary object like a cement wall, all the energy is absorbed by the vehicle and occupants.

Driver

It is helpful to observe the characteristic injuries seen on drivers even in single-vehicle accidents. It will help to identify them in cases where the occupants' positions are unknown. Injuries seen on ejected occupants are usually a combination of occupant- and pedestrian-type injuries.

Injuries to be noted in determining driver versus a passenger are seatbelt impressions, steering wheel impressions, airbag injuries, dashboard injuries, pedal injuries, and dicing wound injuries.

Seatbelt abrasions seen with drivers are diagonal abrasions or contusions beginning at the base of the left neck and crossing over the mid-chest to the right hip where it meets a horizontal abrasion or contusion across the pelvic area usually below the umbilicus (belly button) (Figure 7.12). This is assuming it is worn properly and the shoulder harness is not tucked under the armpit.

With the advent of airbags, steering wheel abrasions are uncommon. Airbags deploy when there is front bumper impact. They may still be seen if the airbag does not deploy either due to failure or the impact did not trigger them. The abrasions may be partial curved contusions or abrasions usually encircling the middle chest. Internal injuries include anterior and lateral rib fractures.

Even with the use of airbags and seatbelts, the occupants can move forward with the impact in addition to the intrusion of the interior compartment resulting in compression of the legs. The dashboard may put stress on the upper legs fracturing the femur, hip, and/or pelvis. The driver's feet can get entangled in the pedals causing fractures of the lower legs or ankles. Literature descriptions of pedal



FIGURE 7.12
(A) An example of the shoulder harness pattern seen in the driver of a motor vehicle. Note the abrasion at the base of the left neck coursing diagonally across the chest toward the right hip corresponds to the belt hooking to the right of the decedent. Contrast this with (B), which shows the shoulder harness pattern of an occupant. The opposite diagonal pattern beginning at the base of the right neck coursing toward the left hip corresponds to the buckle located there. This photo also shows the lap belt imprint over the lower pelvic region.

impressions can be seen on the soles of the shoes, especially during severe braking. It is good to photograph the soles of shoes to document the presence or absence of any pedal impressions.

The impact may cause breakage of the side tempered glass with the fractured pieces striking the skin on the side closest to the glass. Most times impact on the opposite site of a compartment is too far for dense impact by glass fragments. Glass impact causes characteristic superficial small wavy lacerations and abrasions likened to chicken feet. This information is very helpful to position occupants and is noteworthy during an investigation.

Passenger/occupant

Occupants have fewer patterned injuries than drivers. Front-seat passengers may have airbag injuries if there is a front-end impact. Side window tempered glass can be seen on the right torso and face. Shoulder harness abrasions extend from the base of the right neck diagonally across the chest to the left hip where it is buckled. Due to the proximity to the dashboard, femur fractures with deformity of the thigh may be seen.

Back-seat passengers may exhibit right- or left-side dicing wounds and shoulder harness abrasions depending on their respective position in the vehicle to the breaking glass. Sometimes passengers and drivers may be unrestrained and become ejected, partially ejected, or their position jumbled within the compartment. It is important to look for any patterned injuries and dicing wounds and review the accident report to try to position them to aid in the identification of the driver. DNA collection and head hair samples may aid the accident investigator. Good photographs depicting the injuries with and without scales from above, side, and back will provide additional information and justification of findings for possible court testimony.

Compression or mechanical asphyxia

Compression of the torso or neck by collapse of the roof, front-end compression, or an upside-down vehicle with belted occupants all can impinge on the chest and the ability of a person to breathe (Figure 7.13). Autopsy examination shows a paucity of injuries and usually congestion of the head and neck.



FIGURE 7.13
A heavy object compressing the torso or upper body resulting in the inability to expand the chest and exchange air.

Petechiae within the eyes may or may not be present. The best evidence for this diagnosis is the scene photographs showing the position of the decedent within the compartment. The head and neck may also be flexed or hyperextended, further inhibiting exchange of oxygen. Scene photos can mean all the difference in these cases.

Pedestrians

When pedestrians come in direct contact with a vehicle, there may be transfer of paint, fractured plastic particles, and imprints of the vehicle onto the clothing and skin of the decedent or injured person. The scene along the path of the impact will contain a mixture of body fluids and possible materials from the vehicle. When the vehicle is examined, blood, hair and tissue from the decedent/injured can also be found in the crevices or under the vehicle [4]. During medical treatment, clothing may be cut away and left at the scene or discarded in hospitals. It is important to confiscate clothing as evidence, especially in hit-and-run accidents.

Speed at the time of impact can be estimated from skid patterns prior to impact. The speed of the vehicle, type of vehicle (high or low rise, slanted or flat hood), and height of the individual all play a role in the series of events that follow the impact. The height of the person determines his or her center of gravity. It is located near the waist in an adult, which has a higher center relative to the ground than a child does (Figure 7.14). For this reason, children are usually carried on the front of a vehicle until it slows when they fall in front of it and are then run over. Adults can be knocked down and run over at slow speeds. More commonly, an adults struck at speeds less than 35 mph will fracture his or her legs on the bumper then slide onto the hood, striking the windshield. As the vehicle slows, the person slides off the side. At faster speeds the legs are fractured and the person is lifted to the roof of the vehicle and may fly over the top to drop onto pavement. Other vehicles may then run over the injured person. In large-mass, flat-front vehicles, the adult and child will impact the front and be carried along then drop under the vehicle as it slows.

Pedestrians can also be struck by side mirrors that project outward on delivery or pickup trucks and may create only upper torso or head injuries. Other pedestrians may be struck only by a vehicle's front edge and have isolated one-sided injuries depending on which way he or she was facing at the time of impact. These glancing blows can result in fatal injuries depending on how the pedestrians are impacted and ejected to the side. Injuries not only can occur from the impact with the vehicle but also by the impact of the person with the ground.

Injuries peculiar to pedestrians are leg bumper injuries and grill injuries (Figure 7.15). Bumper injuries occur when the car bumper impacts usually the lower leg. The height of this fracture is important because it is the height of the front end of the vehicle at the time of impact and needs to be measured at the time of autopsy (Figure 7.9). It is measured from the sole of the foot to the mid-portion of the lower-leg deformity. Other important measurements



Pedestrian struck at lower speeds. Bumper injuries will correspond to the height of the bumper at the time of impact. Note the bumper dips downward with braking. After the initial impact, the person strikes the head on the hood or windshield and with braking, slides off the side of the hood onto the pavement.

Pedestrian struck at higher speeds. Here the pedestrian will be struck by the front of the vehicle but is swept upward to strike the roof and land behind the vehicle or be swept over the top entirely to land behind.

FIGURE 7.14
Diagram of impact of a car with a pedestrian [5].

are any patterned injuries on the torso, buttocks, or backs of the legs. In living victims, the height is difficult to obtain. The height of the front end of a vehicle decreases when the brakes are applied and can corroborate or dispute the statement given. The bumper height will vary from vehicle to vehicle and needs to be documented in the investigative report while at the resting state.

Collection of evidence

Toxicology for alcohol determination as well as prescription and illicit drugs is useful to obtain on all traffic victims. This is especially important if the positioning of each of the occupants is unknown and the identity of the driver is



FIGURE 7.15
(A) Typical bumper fractures of the legs seen in pedestrians struck by a motor vehicle. The injuries may occur on one or both legs during an impact. (B) A patterned contusion over the back of a decedent that corresponds to the tire imprint as the decedent was run over by a motor vehicle.

questioned. This information is used for prosecution and civil litigation for factors influencing outcome of injuries or the cause of the accident. Underlying diseases and health of decedents is also important to document because civil settlements are based on life expectancy and lifetime earnings. Pain and suffering are also factored in, and those who die instantly usually receive less than those who live for an interval with a period of potential awareness. For these reasons, a complete autopsy will aid retrieval of specimens to ensure accurate information is used to form an opinion.

The best specimens for toxicology are obtained from the femoral artery/vein of the groin and vitreous specimens. Femoral specimens are preferable to subclavian or chest specimens because they can be contaminated with gastric contents resulting in false elevations of measured values. It is not uncommon for the diaphragms and stomach/esophagus to rupture spilling freshly ingested food into a pleural cavity. When drawing subclavian or heart specimens it is easy to get the needle into the cavity contaminating the blood with ingested alcohol rather than metabolized alcohol that might be present. If someone goes to a party, drinks a beer, and immediately drives with a fatal traffic accident, the freshly ingested single beer would likely have a blood alcohol of less than 0.02 mg/dl in the blood, which would be under the legal limit. But if collected from a contaminated pleural cavity, the specimen would be over the legal limit of 0.08 mg/dl, and the person erroneously determined to be driving under the influence.

A verification test of blood alcohol is usually determined by doing a vitreous (ocular) fluid level. Since it is protected from the body cavities and contamination factors, it is a useful adjunct to a blood alcohol test. The value determined in the vitreous runs slightly higher (1.2× higher) than blood and also lags behind a blood value. So a value of 1 mg/dl in blood is equal to 1.2 mg/dl in vitreous, and the person is said to be at a steady state where ingested quantity is equal to excretion. As the person quits drinking, the blood value will drop and the vitreous value will remain slightly higher, lagging behind in its excretion.

Besides toxicology, other surface evidence may be useful to an investigation. Surface evidence is most important in pedestrian impacts because the materials can link the injured to a particular vehicle. Paint chips, glass fragments, car parts, and patterned imprints can all be useful in the investigation (Figure 7.16). Databases exist for comparison of these articles of trace evidence and can aid the identification of the suspect vehicle. Small pieces of plastic from headlamps may contain portions of the VIN number to further narrow the suspect pool and need to be collected as evidence. When the list is obtained, each car can be inspected



FIGURE 7.16
(A) Paint chips collected from the clothing and wounds on a pedestrian motor vehicle accident. The red color corresponds to the outward color of the vehicle and the gray corresponds to the underlying primer coat near the metal. (B) A microscopic examination of a paint chip showing the layers of paint on a vehicle [6].

for damage corresponding to the victim's injuries. Suspect vehicles can then be impounded and inspected for decedent tissue or DNA in vehicle crevices.

Clothing may have imprints of front ends of vehicles and so it should be removed without cutting and photographed front and back. Investigators may wish to impound the clothing and, if so, it should be packaged separately in brown paper bags then signed over with a chain of custody. Photographic documentation of injuries is imperative in pedestrian accidents. In hit-and-run accidents it may prove useful to trace patterned grill or bumper injuries using a clear plastic sheet over the patterned area and tracing with a permanent marking pen. The top/bottom and right/left should be documented so it can be coordinated with any photographs. The tracing can be useful to law enforcement investigators in looking for a matching vehicle.

Work and farm related

Work- and farm-related blunt-force injuries usually involve a piece of machinery, electrical malfunction, or natural disease. It is important to determine a site of risk to prevent injury to other workers. Occupational safety is usually involved in the investigation if it occurs in a workplace. It is important to document the type of clothing and if the person was wearing proper standard apparel. Clothing may become entangled in machinery and it is important to photograph it on the decedent, as well as spread out for documentation of the front and back. Gloves, helmets, and safety shoes are also important to note. Safety harness use, proper attachment to the person, and the stationary object also need to be noted or inquired about. An autopsy examination will add information about an underlying natural disease that may have contributed to the cause, as well as full toxicology to answer a question of impairment.

Trains

Train accidents usually involve two types of deaths: ones in which the person is within a vehicle and one involving a pedestrian. There are rare mass disaster train derailments which follow a mass disaster protocol of locating the engineer and conductor of the train to determine their cause of death and toxicology status to aid determining how they influence the cause of a derailment. Because of the mass, the resulting injuries are usually quite extensive whether within a vehicle or a pedestrian. Train investigations usually include train investigators who will assist in relaying information from the engineer and conductor. Most passenger and freight trains are now equipped with front-end cameras with real-time videos that can be reviewed, corroborating the engineer's account and also providing important information about the train's speed, whistle, and position of the victim or vehicle. It is very helpful in determining the manner of death and whether the victim dies as a result of accident, suicide, or homicide. Review of the video can greatly assist in this determination. The train engineers can give an estimate for approximately how long it takes to stop the train and how far it goes before it comes to a complete stop. The investigator needs to inquire how many train cars are attached and the approximate weight the train is pulling. There is some urgency to the investigation because the trains are usually stopped in both directions while the investigation is being conducted.

Death certification and report writing

Information needed for proper completion of the death certificates includes the date and time of the accident, the place of the accident (highway/road, farm field, residence, etc.), and the circumstances surrounding the death, the time of death pronouncement, or the time law enforcement arrived at the scene on cases where death was obvious. Pertinent circumstances that need to be communicated directly at the time of death include the position within the vehicle (driver, passenger, ejected occupant, pedestrian), seatbelt use, presence or absence of skid marks, estimated speed, weather conditions at the time of the accident, and evidence of possible impairment (liquor bottles or drug paraphernalia). Some cases may even require certain product model numbers to relate to the Product Safety Commission (helmets, vehicle or machinery models, safety equipment in use). In the case of farm or train accidents, information about how the decedent was behaving before the accident and details of how he or she was found are relevant to certifying the cause and manner of death. All of this information is needed by vital statistics and eventually forms part of the national statistics for accident prevention.

It is possible to achieve suicide via a motor vehicle. Contents of the vehicle should be searched for potential suicide notes. The absence of braking with resultant skid marks can be a clue, as well as veering purposefully into oncoming traffic. Semi-tractor trailers as a target are commonly used in this method and drivers of the rigs can relay useful information about how the driver was acting prior to the impact. Many times a suicide manner is difficult to prove to a certainty and they may be ruled undetermined or accidental depending on the toxicology and the opinion of the pathologist.

Death prior to the impact and a resulting natural cause of death is also possible. In these cases, the individual will have few to no external injuries and an internal examination will show an absence of lacerations, fractures, or internal bleeding that would occur if death were caused by a motor vehicle. There may be findings of coronary artery disease, stroke, or other natural diseases that can impair operation of a motor vehicle. It is important to rule out a high neck spine fracture because these injuries can result from “whiplash” at impact with minimal internal findings. The latter manner of death would be accidental. Compression asphyxia should also be considered in cases with minimal to no internal injuries.

Homicide is also important to rule out. Decedents, even those apparently severely injured, found along the side of the road or those lying on train tracks are not necessarily dead by what would seem the obvious cause. It is important to note all scene information and make sure it is consistent with the suspected cause. A pedestrian struck by a motor vehicle should have lower-leg fractures versus a person beaten then dumped by the side of the road. It is important to look for gunshot wounds in those with severe head wounds. X-rays may be a useful adjunct for that purpose.

Literature review

Numerous case studies in the literature exist with photos of various patterned injuries that continue to change as new instruments evolve. Much of the older literature regarding traffic accidents is useful even today. New safety measures have been instituted with side and front airbags, improved side-rail design, and retraction of the motor downward to prevent intrusion into the compartment.

Probably the biggest area of research is the amount of force needed to create various lethal injuries. This is a common question in court but is difficult to answer due to the variations of the human body and its interaction with the force that was applied. Much of the research has been done either with simulator models of the human body or animals. Neither of these are true representations of the decedent to answer the question accurately.

REFERENCES

[1] National Highway Traffic Safety Administration. Summary of Vehicle Occupant Protection Laws. 10th ed; 2011. Retrieved from http://www.nhtsa.gov/staticfiles/nti/pdf/811648.pdf. [August 2013].

[2] Virginia Commonwealth University. Tips and Crash Investigation. Transportation Safety Training Center. Retrieved from http://www.vcu.edu/cppweb/tstc/tips. [August 2013].

[3] History of Seatbelts in the US. Bisnar|Chase Personal Injury Attorneys. Retrieved from http://www.bestattorney.com/defective-seatbelts/history.html. [August 2013].

[4] Lucas J. Forensic Investigation: Motor Vehicle Accidents and Motor Vehicle-Pedestrian Accidents. Medscape; 2012. Retrieved from http://emedicine.medscape.com/article/1765532-overview#a30. [August 2013].

[5] Spitz WU. Essential Postmortem Findings in the Traffic Accident Victim. Arch Pathol 1970, Dec.90(5):451–7.

[6] Paint. Missouri State Highway Patrol. Retrieved from http://www.mshp.dps.missouri.gov/MSHPWeb/PatrolDivisions/CLD/TraceEvidence/paint.html. [August 2013].

CHAPTER 8

Gunshot Wounds

Learning Objectives

- As an investigator, you arrive at a homicide scene of a gunshot victim and the detective asks you to obtain a fingerprint for identification. Apply what you know about the various types of evidence that may need to be retrieved and discuss how you think this might affect further evidence gathering.
- Outline the types of photographs you as an investigator would need to obtain when responding to a gunshot wound suicide death.
- Apply what you have learned about gunshot wound deaths and list the information about the gun or bullets that the pathologist will ask the investigator and needs to be included in the report. Discuss why this information may be needed to plan for the examination.
- Contrast the scene features of a homicide gunshot victim to those of a suicide victim.
- Analyze and list the features of a gunshot victim that should not be included in an investigator's report.

Key Terms

Caliber
Gauge
Wadding
Bullet
Casing
Cylinder
Magazine
Gunshot residue
Kinetic energy

Chapter Summary

Gunshot wound investigations can be very detailed requiring notation of multiple pieces of evidence and evaluation of this evidence with witness statements. It is best to consider suggestive statements of accident, suicide, or homicide as only one piece of the puzzle and evaluate the body's relationship to the location the gun was found, trajectory, and pathologist's range of fire estimation to make the best judgment for manner of death. It is important to include the type and caliber of weapon within the report so the pathologist can utilize this information during the examination. Photographic documentation of the scene is invaluable and should include the usual overall photos from multiple perspectives of the decedent and the relationship to the gun if present. Mid-range and close-up photos of visible injuries and clothing are also important. Surroundings rooms, vehicle compartments, or involved areas are also useful in the scene reconstruction of shooter versus victim, or if self-inflicted. After the body is removed, photographic documentation of the surface the body was resting on is also needed. Consultation from homicide detectives, pathologist response, or blood-spatter experts can be useful to direct the investigation.

INTRODUCTION

To talk about gunshot wounds requires basic knowledge about the general types of guns and terminology used to describe the various parts that compose them. There are three main categories of guns: handguns, rifles, and shotguns. The basic premise of all guns is the discharge of a projectile down a tube (barrel) using a controlled explosion created by gunpowder. In this chapter we will discuss the various types of guns, ammunition used, the wounds created, range of fire, evidence collection, scene documentation, and how the scene information is used to determine manner of death.

TERMINOLOGY

- *Handgun:* A handheld weapon that varies from low to high velocity depending on the capability of that gun's barrel diameter corresponding to **caliber**, barrel length, and type of ammunition used.
- *Rifle:* A high-velocity weapon utilizing larger amounts of gunpowder and a longer barrel to achieve greater accuracy, as well as more complete burning of the powder and of which the barrel diameter is described by caliber.
- *Shotgun:* A high-velocity weapon that utilizes shot shells rather than bullets as projectiles and is usually described by **gauge** rather than caliber.
- *Barrel:* The tube that gives the projectile directionality and allows the gun to achieve its maximum velocity.
- *Cartridge:* The complete "bullet" that contains the true lead bullet on the tip, with or without an overlying jacket, and a **casing**, which holds the gunpowder, primer, and bullet in alignment.
- *Bullet:* The lead portion of the cartridge that leaves the end of the barrel (muzzle) when the gun is fired.
- *Casing:* The spent portion made of a cartridge that is discarded after firing. It is usually made of brass or steel and remains in the **cylinder** of revolvers or can be ejected to the side in semi-automatic weapons.
- *Projectile:* A generic term used to describe anything exiting a weapon. In wounds created by guns it is typically the lead bullet, but in some weapons, such as a dart gun or handmade ammunition, it made be atypical.
- *Shotgun shell:* A term used to describe the equivalent of a cartridge but used only in a shotgun. Contains the lead shot as well as the gunpowder, **wadding**, and primer. When all the contents are expended it is called a shot case.
- *Shot:* The round balls composing the lead portion of a shotgun shell. These can vary in size from 9.14 mm to 1.3 mm. In general, the larger the number the smaller the size of the ball. As an example, 0 or 00 size is much larger than 7 size shot. Smaller shot is influenced more by aerodynamics and air friction and flies accurately a shorter distance than larger, heavier shot. In summary, the smaller the number on the shot, the larger the diameter and the fewer number of shot per shotgun shell.

- *Wadding:* A disc composed of cork or cardboard used to separate the shot from the gunpowder and creates a more efficient explosion by containing the gas in the gunpowder area of the shot shell.
- *Power piston:* A plastic form of wadding that lines the inside of the shotgun shell and serves the same purpose as the cardboard discs. In addition, it is designed to keep the shot together, creating more accuracy at the target and less fouling of the barrel by less contact with the lead.
- *Gunpowder:* The material that creates the power behind propelling the **bullet** from the gun. There are three main types: cylinder, ball, and flake. Ball powder is smaller and more aerodynamic, allowing it to penetrate clothing and other intermediate targets much easier than flake powder, which has a greater surface area. Cylinder powder has intermediate properties.
- *Primer:* A volatile explosive material that comes in contact with the firing pin and precipitates the ignition of the gunpowder explosion.
- *Perforation versus penetration:* Perforation describes a wound that enters an organ and passes through it. Penetration describes an entrance of a wound into an organ or body cavity and usually no exit. These terms tend to be used interchangeably.
- *Rifling:* The spiraled tooling inside the barrel of a rifle or handgun that puts a spin on the bullet projectile and is gun specific. The gun barrel is created from a tube of steel that is then bored out to a machine to create these characteristic grooves which will vary in spacing and depth. Most guns have a right-twisting spiral as viewed from the shooter's perspective looking down the barrel. The exception are handguns manufactured by Colt which are left twist.
- *Lands:* The raised portions of the rifling inside the barrel of a gun that create markings on the soft lead bullet as it travels down the barrel (Figure 8.1). These markings are gun specific and allow a projectile to be matched to a particular rifled weapon.
- *Grooves:* The depressed areas inside the gun barrel of a handgun or rifle that create the bullet markings on the projectile and allow guns to be matched to the recovered projectile (see Figure 8.1).
- *Caliber:* The diameter measurement inside the barrel between two lands and is measured in millimeters for most weapons.
- *Gauge:* Reflects the diameter of the barrel of a shotgun and is determined by the number of lead balls that can fit in the diameter of the shotgun barrel that equal 1 pound. In the instance of a 12-gauge shotgun, the barrel diameter is 0.73 mm and it would require 12 balls of that diameter to equal 1 pound.
- *Choke:* A mechanism on a shotgun that is used to prevent scatter of the pellets. They come in different degrees from modified cylinder to variants of modified to full choke. According to DiMaio, they do not affect the pattern distribution of shotgun pellets seen in ranges of fire less than 10 ft [1].
- *Firing pin:* The portion of the trigger that strikes the primer at the base of the bullet causing ignition of the gunpowder. The firing pin is located on the tip of the hammer inside the firing chamber. The pattern created on the bullet casing base can also be characteristic and add information about the specific weapon.



FIGURE 8.1
Lands form the raised portions inside the barrel of a handgun or rifle. Between the lands are valleys called grooves. Each gun has a characteristic land and groove pattern creating the rifling on a bullet as it travels down the barrel. It is this rifling that allows a bullet to be matched to a particular weapon.

- *Centerfire:* The primer being located in the center portion at the base of the bullet casing.
- *Rimfire:* The primer being located in a circular rim at the periphery of the base of the bullet casing.
- *Ejector:* Each gun needs a method to extrude the expended bullet casing/cartridge and move the next active bullet into firing position. This can be done manually in bolt- or lever-action rifles or by sliding the racking mechanism on a shotgun. In semi-automatic handguns and rifles, the mechanism is automatically done after firing with the ejection of the casings either right or left depending on the particular weapon. In revolvers, the bullet casing remains within the cylinder but the cylinder rotates whenever the hammer or trigger are pulled during the firing action.
- *Trigger:* The mechanism that fires the bullet from the chamber in all guns. Pulling it toward the handgrip will cause the trigger to be cocked and ready for release to fire the bullet.
- *Stock:* The wooden or plastic portion of a rifle or shotgun used to steady the gun against the shoulder during firing.
- *Handgrip:* The handle portion of a handgun used to encircle the base of the gun for the hands to steady it for firing.

TYPES AND ANATOMY OF GUNS

There are three main categories of guns: handguns, rifles, and shotguns. Handguns differ from rifles in the barrel length, which affords more efficient burning of gunpowder and in most cases a higher velocity to the bullet projectile. Shotguns differ largely in the anatomy of the projectile used.

Other terminology used to discuss guns is the velocity of the weapon, which largely determines the **kinetic energy** released into the target and the damage created by the surrounding shock waves by this release. Handguns generally have lower velocities in the range of 800 to 1,400 ft/sec. Rifles impart velocities of 1,100 to 3,300 ft/sec with centerfire having higher velocities than rimfire ones. Shotguns are intermediary but generally in the 1,100 to 1,200 ft/sec range.

The amount of energy released and damage created follows the standard kinetic energy formula of general physics:

$$KE = \tfrac{1}{2}MV^2$$

where M corresponds to the mass of the bullet (in turn related to the caliber of the weapon) and V corresponds to the velocity of the bullet, which is squared. The formula reads: *The kinetic energy released is equal to one-half the product of the mass of the bullet multiplied by the velocity squared*. This means that the mass of the bullet is not the largest determining factor in the amount of damage. The kinetic energy is largely related to the velocity achieved. So a high-velocity weapon has more destructive energy than a low-velocity weapon. The formula shows the importance of small increases in velocity have more effect on the amount of kinetic energy than increasing the amount of mass.

The velocity is largely dependent on the amount of gunpowder resulting in a greater explosion. The efficiency of the explosion is influenced by the length of the barrel. The mass of the bullet may not change the amount of kinetic energy as significantly as changing the velocity does, but after a point, only so much gunpowder can be used and the next item to be increased is the mass. As the velocity of the weapon increases in high-powered rifles it becomes necessary to use jacketed ammunition otherwise the velocity may melt the bullet inside the gun and cause it to damage the gun. By placing a hard metal over the lead it protects it and has the added benefit of creating a secondary projectile that can separate into another path. The real damage from the gunshot, however, is not just the immediate path of the bullet but the damage it produces in a temporary cavity around it as the kinetic energy is released.

The main parts of a revolver are the hammer, trigger, cylinder, cylinder latch, grip, and barrel and extractor rod. A revolver can hold five or six bullets in the cylinder and is loaded or unloaded by pressing the cylinder latch (Figure 8.2). The cylinder will rotate outward and used or unused bullets are removed by pressing the extractor rod into the cylinder. The gun can be reloaded; then the cylinder is rotated back into place and is ready to fire again. Many modern revolvers are able to be fired without first pulling the hammer back, which is referred to as



FIGURE 8.2
(A) A typical revolver. (B) The cylinder containing a maximum of six bullets that has been rotated outward to reload or empty.

double action, meaning that pulling the trigger back also cocks the hammer and in the second motion will fire the projectile. The bullet then exits down the barrel, which usually is usually 2 to 8 in. long. The longer the barrel, the more accurate the bullet is able to be on its target depending on the skill of the marksman. The expended cartridge will remain under the hammer until the trigger is pulled once again. This allows an investigator to faintly mark the cylinder with a pen then disengage and rotate the cylinder out to establish the number of expended bullets and their positions within the cylinder, as well as their relationship to the firing pin. It is important to document this information photographically and within the body of the report. There are two main manufacturers of revolvers: Smith & Wesson and Colt. Modern Smith & Wesson revolver *cylinders* rotate to the left (counterclockwise) and have a right-hand twist to the *rifling*. Colt revolvers have cylinders that rotate to the right (clockwise) and have a left-hand twist to the rifling [2]. The rifling notation on a recovered bullet is an important one and can help identify the manufacturer of the suspect weapon without having to wait for the crime lab.

The components of a semi-automatic handgun are similar to a revolver with the biggest difference being the bullet reloading mechanism (Figure 8.3). The components of a semi-automatic handgun include the hammer, trigger, **magazine**, slide, grip, and barrel. The magazines vary in the capacity of bullets they can hold and may depend on state gun control laws. Some states have been known to restrict magazines to as few as seven bullets. The magazine slides into and snaps into the base of the handgrip. To rack a bullet into the chamber requires the slide mechanism to be pulled back toward the handgrip. The magazine contains a spring in the base to move bullets automatically into the firing chamber as they are spent or during the racking of the slide. During the firing process, the gun uses some of the spent energy to move the slide toward the grip, which mechanically discharges the spent cartridge out the side of the barrel, allowing



FIGURE 8.3
(A) A semi-automatic handgun with the magazine ejected from the handgrip of the weapon. With the magazine out of the weapon, it may still not be safe to handle until any live rounds are ejected from the chamber and it has been cleared (B).

the next bullet to move into place by the spring-loaded mechanism. The slide moves automatically after each trigger pull until the magazine is empty.

It is important before examining a weapon at the scene to make sure the firing chamber is empty prior to extensive examination. The magazine is first removed, then the slide is manually racked toward the grip to eject any bullets in the firing chamber. It is important to keep fingers off the trigger and the muzzle away from surrounding people to prevent injury from an accidental discharge. This is called making the gun safe and all examination of weapons needs to follow the protocol of ensuring that all bullets have been removed from the firing chamber prior to packaging, photographing, or examination. Gun etiquette includes packaging and handing from one person to another with the open firing chamber visible.

Rifles are also bored weapons, meaning they impart rifling on the bullet projectiles. The components of a rifle are the barrel, trigger, stock, firing chamber, bolt or lever action (some are semi-automatic as well), and magazine within the stock. Bolt-action rifles are the most common and are seen in hunting rifles. The bolt is a hand-rotating mechanism that moves the next bullet from the storage magazine into the firing position within the chamber. Lever action is the type seen in BB or pellet guns as well as in TV westerns. These involve a lever near the trigger that ejects a cartridge or, in the case of BB guns, loads the next bullet into place. There are semi-automatic rifles such as AK47 and machine guns that utilize mechanisms similar to semi-automatic handguns to load bullets into the firing chamber from a magazine. Magazines vary in size on these weapons and can hold many more bullets than the semi-automatic handgun.

Shotguns are composed of a single or double barrel (side by side or over and under) and a stock, which also contains the magazine, trigger, and a pump-action mechanism. They are smooth bored and contain no rifling. They fire by placing a cartridge into the firing chamber and can also be loaded with cartridges from the magazine that can be racked into the chamber by sliding the pump mechanism. The gun is fired from the shoulder by pulling the trigger. Reloading is accomplished by racking back the pump mechanism on the barrel, which ejects the spent cartridge and loads the next cartridge. Some shotguns are breakaway and each shell cartridge must be hand loaded into the firing chamber.

ANATOMY OF BULLETS AND PROJECTILES

Bullet cartridges fired from a rifled weapon are uniformly composed of a lead bullet, gunpowder, primer, and bullet casing to hold it all together (Figure 8.4). Upon the hammer firing pin coming in contact with the primer (either centerfire or rimfire), the gunpowder ignites, causing the controlled explosion and separation of the bullet from the casing. As the bullet exits the barrel, burned and



FIGURE 8.4
(A) Cross-section of a projectile with the lead bullet at the top of the photo and the casing at the bottom, which contains the gunpowder. (B) Various caliber bullet projectiles from rifle (left) to handgun (right).

unburned gunpowder and hot gases including carbon monoxide are expelled into the surrounding environment. The degree of efficiency of this burning will depend on the length of the barrel. The barrel's length, its distance from the victim, and the amount and type of gunpowder in the casing will determine how much is seen on the skin and clothing of the victim.

Handgun bullets vary in design from jacketed to unjacketed lead bullets, as well as design differences described as hollow points or fully jacketed. Jackets describe a surface coating over the lead usually composed of copper, brass, or lightweight steel, and occasionally plastic material. The jacket serves to protect the inside of the barrel from damage at higher velocities and will separate from the lead portion upon impact, creating a secondary projectile and increasing the damage rendered. Rifling from the inside of the barrel will be seen on the jacket rather than the lead portion so it is important to locate that portion when doing scene or autopsy retrieval. The jacket is less dense than the lead portion of the bullet when viewed on X-ray but is still visible.

Rifle cartridges are similar to handgun ones but are largely jacketed ammunition due to the high velocity. The majority of cartridges are larger than handgun ammunition (except .22 caliber) and contain a larger amount of gunpowder. Due to the high velocity and design, rifle projectiles shatter upon impact into small fragments. This makes gun comparison by rifling to residual fragments very difficult. Screening X-rays will show small dusty particles of lead along the trajectory path, described as the "snowstorm effect." The long tube of the rifle also allows nearly complete combustion of the gunpowder, and gunpowder deposition near wounds or clothing is minimal to nearly absent even in contact or near-contact distances. Because of the high velocity, tissue destruction is extensive. Depending on the distance of the shot, the wound may appear as a typical wound with a small to moderate entrance containing a marginal abrasion with extensive release of the energy causing huge gaping exit wounds. See Figure 8.5 for examples.

Shotgun cartridges are composed of a plastic or paper cylinder containing multiple pellet projectiles, separated from the gunpowder in the base by a second piece of plastic called a power piston, or by circular cardboard/cork/felt wadding, gunpowder, primer, and brass base (Figure 8.6). When fired, the pellets and wadding/power piston are expelled from the cartridge down the barrel of the shotgun. Because the inside of the shotgun is smooth bore, no markings are made on the wadding, power piston, or pellets. Each pellet has the ability to penetrate the body and cause internal damage. The smaller the diameter of the pellet, the larger the number inside the cartridge and vice versa. Large pellets, namely 00 buckshot, utilize eight individual pellets inside a cartridge and each are about the size of a 9-mm bullet. Shotguns are extremely lethal as one shot of a cartridge with 00 buckshot is equivalent to eight shots from a handgun. The small pellets are commonly referred to as birdshot because they are frequently used in bird hunting. The scattering of the small pellets over a distant shot allows the hunter to bring down small birds in a single shot. These X-ray opaque shot



FIGURE 8.5
(A) X-ray showing a single bullet within the skull that appears as a radiodense irregular object. (B) X-ray of a rifle wound that has only fine small bullet fragments visible that are nearly impossible to recover. This is the classic "snowstorm effect" seen with rifle wounds. (C) X-ray of a shotgun wound of the head with buckshot pellets.



FIGURE 8.6
(A) A shotgun cartridge loaded with buckshot. It also demonstrates the empty casing that is the portion that may be recovered at a scene. (B) In contrast, a cartridge loaded with birdshot. Note the much smaller size of the shot pellets and larger number of them that are contained within the cartridge.

pellets are easily seen on X-ray, however, the plastic or cardboard wadding is not visualized. The wadding or plastic piston will give an indication of the gauge of the shotgun based on its diameter and the pellets need to be recovered whenever possible. In small birdshot pellet wounds, the pellets are difficult to locate and representative samples can be obtained and the whole number seen on X-ray is not necessary. In fewer pellet numbers such as 00 buckshot, all the projectiles from the victim should be recovered.

ENTRANCE VERSUS EXIT

All entrance wounds have one thing in common: a marginal abrasion (Figure 8.7). When a gun is shot the bullet projectile contacts the skin and scrapes off the margins of the wound as it enters. If the wound is nearly straight on, the abrasion around the margin will be concentric. If the bullet enters at an angle the wound will be oval with the scraping portion being along the margin toward the muzzle of the gun. As the angle to the body surface gets shallower, the bullet can actually graze across the surface, tearing the skin, and may or may not enter the body. In graze wounds the margins will be lacerated with small pointed margins pointing in the direction from which the bullet came (Figure 8.8). The shelf abrasion on the margin will also be in the direction the bullet enters.



A typical contact entrance wound with soot, muzzle imprint, and marginal abrasion.

Inner circle = marginal abrasion

Middle circle = soot deposition

Hexagon = muzzle imprint with site mark

FIGURE 8.7
Contact gunshot wound showing marginal abrasion, soot deposition and a faint muzzle imprint.



FIGURE 8.8
A graze wound creates a long laceration because the bullet is skimming along the surface of the body. The top (superior) margin has a crescent marginal abrasion with multiple pointed edges along the margin pointing from the direction from which the bullet came. The arrow in the photo depicts the direction of bullet travel.

An exit wound can appear round, or as a small or large laceration, or as a small slit in the skin (Figure 8.9). There is common belief that the largest wound is usually the entrance, which is untrue. The size of the wound is not related to entrance or exit. Exit wounds are characterized by the absence of a marginal abrasion rather than size. Usually no soot is able to reach an exit wound.

Occasionally there will be an abrasion near or somewhat surrounding the exit wound. This abrasion usually looks atypical from the usual marginal abrasion or other marginal abrasions associated with other gunshot wounds seen on the body. It is helpful to count the number of projectiles seen on X-ray and compare them to the number of typical entrance wounds seen on the body. This comparison may assist the investigator or pathologist in making the distinction that the funny-looking wound is actually an exit wound. The location where it is located may also assist in making the distinction. These funny-looking abrasions are usually located in an area of elastic (bra, waistband of pants, or underwear), band of a hat, back brace, etc., or in the area resting against the floor, wall, or chair back, and are called shored exit wounds (Figure 8.10). Examination of the clothing may also assist to look for outward tears, but usually they are soaked by blood and very difficult to assess and aid in this determination.



FIGURE 8.9
A laceration and typical appearance of an exit wound. They can vary greatly in size depending on the velocity of the weapon and release of kinetic energy.



FIGURE 8.10
A shored exit wound. Note the central laceration surrounded by a wide slightly irregular abrasion. The entrance wound was a classic wound with soot and the decedent was sitting in a recliner when he shot himself. The bullet was recovered in the back of the chair.

RANGE OF FIRE

As the gun is fired, burned and unburned gunpowder and hot gases exit the muzzle (Figure 8.11). The distance the end of the barrel is from the victim as well as any objects between the two, and the type of gun, ammunition, and gunpowder will determine whether the gunpowder gets deposited on the skin or clothing. The further the distance, the less likely it will come in contact with either. Wounds are usually described in terms of hard contact, near contact, intermediate, distant, or indeterminate.

HANDGUN AND RIFLE WOUNDS

In hard-contact wounds the gun is firmly against the body and causes all the outpouring of the muzzle to enter the wound. On the torso this means the hot gases, including carbon monoxide from the burning gunpowder, enter the subcutaneous tissue and muscle causing a bright-red discoloration of the muscle (Figure 8.12). This is called the carboxyhemoglobin effect. The gunpowder residue is deposited within the depths of the wound and burning may be seen



FIGURE 8.11
A gun firing showing the flame, smoke, bullet, and gunpowder exiting the muzzle of the gun. It is the distance of the muzzle to the skin that will result in the pattern of the wound and the distribution of soot [5].



FIGURE 8.12
A hard-contact wound of the head with the central entrance wound containing a marginal abrasion, soot, and searing on the margins of the wound, and distortion by a large stellate tear. The tearing is caused by the gun discharging in contact with the skin and the hot gases escaping into the tissue between the skin and the skull.

along the wound margins. In handgun wounds the marginal abrasion will be seen with a full or partial muzzle imprint and stellate tears are evident on head wounds. Rifle wounds will show a marginal abrasion, but due to the large velocity, there may be extensive tissue destruction and it is more difficult to identify. Soot deposition can get deposited onto the surface of the skull or even the underlying dura membrane in a gunshot wound of the head.

In near-contact wounds, the distance from the muzzle to the skin can vary from nearly in contact (Figure 8.13) to a couple of inches away. In this scenario, the gases have the ability to diffuse from the end of the weapon and there will be less tissue destruction than hard contact. The marginal abrasion will be apparent but a muzzle imprint will be absent. Soot deposition will be apparent around the margin of the wound and be small to quite apparent depending on the weapon (Figure 8.14). Soot is greasy, black material but can easily be washed from the surface, so it should be evaluated prior to the body being cleansed. Soap should be avoided when cleansing the areas near gunshot wounds so as not to remove the soot and it can be captured photographically.

Intermediate wounds are ones extending usually from 12 in. to arm's length from the muzzle of the weapon. Because of the increased distance, the gases and much of the gunpowder have the ability to burn or diffuse. However, some gunpowder may reach the skin and burn into the surface causing powder tattooing (a.k.a. stippling), which appears as pin-dot red abrasions on the skin at the margin of the wound (Figure 8.15). The closer the muzzle is to the skin, the denser the



FIGURE 8.13
A loose contact wound with soot deposition on the skin surrounding the entrance wound and a partial muzzle abrasion on one margin.



FIGURE 8.14
(A) A near-contact wound of a rifle showing only a very small amount of soot deposition due to the efficiency of the longer barrel. It does show the typical marginal abrasion characterizing it as an entrance wound. (B) The corresponding exit wound with the massive release of kinetic energy causing severe destruction of the head.



FIGURE 8.15
An intermediate range wound with stippling, also known as powder tattooing. It represents small particles of gunpowder seared onto the skin creating the punctate red-brown abrasions. Many times the particles of gunpowder can be seen in the depths of the wound. The separation of the stippling from the margin of the wound was created by the hairline of the decedent, which prevented the gunpowder from reaching the skin. Clothing may also create the same type of barrier.

tattooing, and it may be mixed with soot. As the distance increases, the tattooing becomes lighter and more scattered. Because tattooing is embedded in the skin it does not wash off readily, and if necessary, small particles can be retrieved using the pointed edge of a clean scalpel and collecting them onto a filter paper.

It is important for the prosecutor to measure length and width of the densest area where the tattooing is present, disregarding outliers, and to photograph this with the usual right-angle bite-mark ruler. If the gun is recovered, the range of fire can be estimated by reproducing the pattern of stippling by test-firing the weapon in the laboratory onto white cloth.

Distant wounds are those where the end of the gun is far enough away for neither the gases nor the gunpowder to reach the victim and it will show only the entrance wound with its marginal abrasion and absence of soot or stippling. Indeterminate-range wounds describe entrance wounds where the skin shows a marginal abrasion with the absence of soot or stippling. It has the same appearance as a distant wound but there is an intermediate target that may have precluded the presence of either soot or stippling being deposited and visualized on the skin (Figure 8.16). A typical scenario for an intermediate target is clothing, a car door/window, or house door/window that is between the muzzle and



FIGURE 8.16
An entrance wound with the typical marginal abrasion but lacking soot or stippling. The range of fire is indeterminate and can represent a distant wound or one where the soot or stippling was unable to reach the wound because of clothing or some other intermediate target.

the victim, causing the gunpowder to be deposited elsewhere or filtered out prior to reaching the skin.

Clothing typically does not distort the bullet path to a significant degree unless it is a bulletproof vest or other substantial item. Gunfire through a car/house door or window will distort the pathway and cause the bullet to begin to tumble, resulting in an atypical entrance wound and marginal abrasion. The wound appears wider and irregular and is usually surrounded by other small irregular abrasions created by secondary projectiles from the doors or windows themselves. Depending on the scene investigation, it may aid determining the order of particular wounds. For example, if someone is initially shot through a door window creating the atypical wound and the window is shattered, no longer forming a barrier, or the door is opened, the wounds that follow will have their typical marginal abrasion and lack of secondary projectiles.

Gunshot wounds to the head have particular characteristics that gunshot wounds in other locations do not have. The skin of the head is stretched tightly over the skull. In hard-contact wounds, the hot gases have only the area between the skin and skull to escape into and may exceed the stretching ability of the skin. This can cause it to tear into large stellate (starlike) lacerations with a central entrance wound containing a marginal abrasion. In near-contact wounds, this may not occur to the same extent because of the ability of the gas to escape. Typical soot deposition patterns previously described will be the same depending on the range of fire. The skull also has unique capabilities due to its particular anatomy of being formed as an inner and outer table (layer). With an entrance gunshot wound to the head, it will enter the skull as a punched-out appearance externally with a wider chipped margin internally. This process is called internal beveling and denotes the entrance site. As the bullet exits the skull, the opposite occurs with the punched-out area internally and chipped margin externally (called external beveling). This unique property confirms the directionality in those wounds with soft tissue and skin overlying them, as well as forms a method to determine the entrance and directionality of a gunshot wound even on skeletal remains. See Figure 8.17 for examples.

Gunshot wounds to the ears, nose, scrotum, hands, and feet will appear different than gunshot wounds to other locations. Skin stretched over cartilage on the nose and ears tears more like a laceration and the presence of a marginal abrasion is more difficult to assess. Calloused hands and feet also have similar atypical appearances. The scrotum contains loose skin with multiple folds and will not have the usual marginal abrasion seen in other locations. Skin folds due to obesity or breasts in a bra can also create unusual wounds with partial marginal abrasions/soot/stippling on one fold and the entrance on another fold inches away, but when the gun was fired the two margins were in close proximity.

Gunshot wounds in decomposed bodies are very difficult to locate especially if they are purging fluids obscuring blood pooling on the adjacent floor or ground.



FIGURE 8.17
These photographs depict beveling of the skull and can aid in the determination of the direction of fire. The beveling is created by the unique anatomy of the skull, which is formed by an inner and outer table. (A) The entrance wound on the external portion of the skull with soot deposition around the edge. (B) The corresponding internal beveling on the internal table on the other side of the entrance wound. (C) The bullet then passes through the brain tissue and approaches the internal table on the other side of the skull where its exit appears punched out internally. (D) The external beveling seen on the other side of the skull as the bullet passes outward then through the skin.

Maggot activity can further complicate identification of wounds. Surrounding scene findings or investigative information such as a missing wallet or vehicle, an empty wallet lying on a bed, bloody footprints, or an unsecure residence should all heighten the suspicion for foul play. X-rays of decomposed bodies are recommended to prevent missing bullets and their associated wounds.

Severely obese people and small-caliber wounds, especially .22- and .25-caliber, tend to have very small entrance wounds that can seal closed with very little surrounding blood. These wounds usually measure less than ¼ in. in diameter and may be hidden in body creases. Small droplets of blood on clothing or holes in clothing may be the only clue that can be confirmed with X-rays.

SHOTGUN WOUNDS

The appearance of a shotgun wound is going to change dramatically depending on the distance the muzzle is from the skin. In contact wounds the entrance will range in diameter from ~¾ in. to 1 in., and contain a smooth contoured marginal abrasion and absence of pellets around the margin to the wound because all the discharge has entered the wound (Figure 8.18). Soot can usually be seen in the depths although in a minimal amount.

As the muzzle increases in distance, the wound will enlarge reaching up to ~1 in. to 1¼ in. in diameter, and continue to have a marginal abrasion but gain small scalloped margins along the internal border. This is created as the pellets begin to disperse and is commonly called a cookie-cutter margin. The spreading of the pellets begins about 3–4 ft from the muzzle of the gun.

As the muzzle gets further away, the shot pellets disperse more widely and begin to form satellite entrance wounds around the main entrance wound (Figure 8.19). The major wound will become less distinct and is jagged along the margins. The pattern of the main spread of pellets is important to document via vertical and horizontal measurements, as well as photographically with a right-angle ruler. This pattern can be reproduced in the crime lab to give an estimate of range of fire.



FIGURE 8.18
A contact shotgun wound to the head showing the wide marginal abrasion on the residual skin margin and minimal soot deposition. Note the severe destruction of the cranium.



FIGURE 8.19
A distant shotgun wound with a large central laceration from the large number of birdshot pellets entering the wound, and a peripheral ring of multiple pellet wounds showing they have started to separate. Measurement of the width and length distribution of the peripheral pellets aids in the determination of the range of fire by the firearms division of the crime laboratory if the weapon is recovered.

The wadding will also play a role in the wound appearance and assist with determining range (Figure 8.20). The power piston has a unique quality after it is fired as it goes through transition from a tube to the cup opening into three or four petals, then the petals will bend back onto the base of the cup. At close range, the wadding will enter the wound along with the pellets and in the plastic form will not create any distortion to the wound. At 1–3 ft from the muzzle, the petals have begun to open and will create rectangular abrasions in a cross pattern on the margin of the wound. Shotguns with .410-gauge utilize power pistons with only three petals. Those cartridges using the cardboard variety will show no distortion to the margin of the wound until a further distance when they start to float to the side where they create small irregular to semi-oval abrasions. This usually occurs at distances greater than 5 ft. Otherwise, the wadding tends to enter the wound in distances less than 5 ft.



FIGURE 8.20
(A) The plastic wadding from a shotgun wound that contains four plastic petals. (B) The corresponding wound with the margin of the wound containing a rectangular abrasion due to the margins of the petals starting to open, which can aid the estimation of the range of fire.

According to DiMaio, sawing off the shotgun to aid concealment or the presence of choke has not been shown to alter these range estimations until the distance is greater than 10 ft from the muzzle to the victim [1].

TEST-FIRING THE WEAPON

If the weapon is found, the best determination of range is to fire it in the laboratory setting and create various soot/stippling patterns at known distances using the same gun and ammunition. The patterns are usually performed onto white cloth or ceiling tiles so they can be compared to residue photographed on the skin/clothing to estimate the range of fire more accurately. This description needs a preface to court testimony that the estimate given by the witness is only an estimate and that the best determination is done by the above procedure.

REPORT DOCUMENTATION

Gunshot wounds are documented describing the size of the wounds measuring the diameter of the wound, presence or absence of a marginal abrasion, and soot or stippling. The general location of the wound is described then measured either from the sole of the foot or the top of the head. If the wound(s) is/are on the side of the head, the ear canal can form a useful landmark and document a trajectory path. The best location of the measurement depends on the scenario. If the person was thought to be standing, the sole of the foot would be most helpful to reconstruct the scene, especially if there is an exit wound and alignment with the trajectory of its recovery is going to be used, or if the site of recovery is still in question. If the person is sitting in a car or on a piece of furniture, an additional measurement from the base of the buttocks may be useful for the pathologist to document. Also noted is right or left of midline with the midline being defined as a line drawn down the center of the body from the nose to the navel or down the spine.

Next is a description of the path of the bullet and what it passes through, including soft tissue and bone landmarks.

This is followed by a site of recovery or exit wound description. Exit wounds are easy to measure at the outset of an autopsy, but sites of recovery have to wait until the bullet is located. Measurements sometimes get overlooked or are not easily obtained because of their location, but they should be attempted if possible. This aids the documentation of the trajectory, and more information about the degree of upward or downward movement of the bullet as well as the side-to-side movement. For the most part, larger-caliber bullet trajectory is in a straight line and it is the body or body parts that are distorted to create that trajectory in relation to the muzzle of the gun. The positioning of the two parties cannot be determined by the trajectory, rather only that the muzzle had to be on the side of the entrance; what the two parties were doing at the time of the shooting is unknown except to witnesses. The abilities of the person after he or she was shot are hard to say to any certainty unless a bullet involves the spinal cord or extensive destruction within the brain. Cases of injured with severe wounds of the heart, lungs, major vessels, and liver have been known to run city blocks because of residual oxygen reaching the brain to maintain consciousness. The location the body is found may not indicate where the initial confrontation occurred.

Also of note is the need to qualify within the report and remind the jury during testimony that the numbers associated with multiple gunshot wounds are done for clerical reasons only and do not signify or imply the order in which they occur. For later testimony, it is best to be organized about assigning these numbers and is helpful to start at the head and work down the neck, torso, and extremities systematically. Some people assign numbers to each entrance and exit. Others assign numbers to the entrance wounds and letters to the exit wounds. Either way, it is helpful to denote the number/letter after the initial set of clean photos with/without scale next to the wound and in the report. When the photos get presented at court it is much easier to sort out a particular one with this added documentation. Many times the photos are taken out of context or order in their presentation and it can be very easy to become confused. It also allows attorneys and juries to align your report with the photos.

A body diagram with the gunshot wounds numbered corresponding to their respective entrance and exit wounds is also very useful to include as part of the report. Many times photos can be excluded due to their prejudicial nature of the trauma and the wounds become difficult to explain to a lay jury without this assistance.

The following is an example of a gunshot wound description for an autopsy report:

> Gunshot wound
>
> Entrance wound: There is an entrance wound on the left upper chest measuring 45 in. from the sole of the left foot and 6 in. left of midline. The ¼ × ¼ in. wound is surrounded by a concentric marginal abrasion without soot or stippling.
>
> Path of the wound: The bullet enters the chest through the left fourth intercostal space, passes through the left upper lobe of lung, aorta, and is recovered in the right middle lobe of lung.
>
> Site of recovery: A 1 × 1 × 0.6 cm lead bullet is recovered in the right middle lobe of lung at approximately 40 in. from the sole of the left foot and 3 in. right of midline. The bullet is collected and labeled as "bullet, right lung." The path of the wound is left to right, downward, and slightly front to back.

When describing trajectories or wound descriptions, it is from the decedent's point of view and his or her right or left, front or back rather than the observer's perspective.

EVIDENCE COLLECTION

Gunshot wound cases present their own set of special evidence collection. It is important that the terminology used in the autopsy report to describe a particular piece of evidence corresponds to the wording on the container and the chain of custody so there is no confusion. It is also helpful to include photographic documentation of each piece of evidence with a patient label, the specific notation, the date and time collected, as well as a two-dimensional (bite-mark) ruler in the photo. Each piece of evidence should have its own notation on the chain of custody and be signed over from the person retrieving the evidence usually to a law enforcement representative. He or she can then transmit the evidence to the evidence locker/crime lab for evaluation and sign it over to them for storage. A chain of custody should reflect the fewest number of handlers of the evidence as possible to ensure that it was handled promptly to its storage or laboratory destination.

Bullets are never collected using metal instruments as popularly seen on TV. This has the hazard of creating artifact striations or distorting the ones present. Typically they are collected using fingers (wearing latex gloves) and placed in plastic containers or paper envelopes after being photographed. It is best not to wash them as the surface may contain trace debris such as pavement from ricochet wounds or fragments of clothing that may aid the investigation. To prevent cross-contamination within the morgue, they should only be placed on clean towels or filter papers that can also be included in the packaging to prevent damage/absorb surface blood. They are wrapped, labeled, and sealed with the seal initialed, dated, and timed.

Paper and plastic wadding and shotgun pellets are similarly handled as bullets. It is important to measure the diameter of the plastic or paper wadding, whichever is recovered, and include a ruler in the photo of these items.

GUNSHOT RESIDUE

The usual evidentiary procedure for a decedent with gunshot wounds is to transport the decedent with brown paper bags secured over the hands. This assists the evaluation of the hands during autopsy and prevents blood from contaminating the hands as it accumulates within the bag. One of the pieces of evidence first obtained after removing the bag is to acquire materials for a **gunshot residue** (GSR) kit (Figures 8.21 and 8.22). Gunshot residue is not needed in all cases and is usually worthless if the decedent lives for a period of time in the hospital or the hands have been extensively handled. If it is going to be obtained it is most useful in the immediate period after the shooting occurred and can be obtained from the victim as well as suspects. It needs to be understood, however, that gunshot residue can be easily transferred from handling the weapon, touching the decedent in areas that have residue on them, or transferred to the decedent if he or she is in a closed space where a gun was fired. Interpretation of the results can be challenging.

Gunshot residue testing is performed using scanning electron microscopy to look for the typical round spheres of gunpowder and testing for the by-products of expended gunpowder/primer materials of lead, barium, and antimony via



FIGURE 8.21
(A) The typical grip used to handle a weapon. When it is fired the residue will be deposited on the top part of the hand closest to the firing mechanism. (B) The hand of the decedent with adherent soot deposition on the hand after firing a weapon.



FIGURE 8.22
The stub type of gunshot residue (GSR) collection techniques. One edge of the stub is the lid to the vial and the other edge is sticky to pick up any adherent particles. It should only be handled with gloves. Each kit comes with two marked stubs/vials, one for the left hand and one for the right hand. Using the correct stub, it is blotted over the thumb, web of the thumb, and onto the first finger in the area where residue would be deposited following use of the gun or in the area of gunfire [4].

flameless atomic absorption with coupled plasma spectrophotometry. Both must be positive to a significant level to call it a positive test [3]. Before beginning the collection, it is important to wear a clean set of gloves and not touch the decedent in any areas except the hands. The hands of the decedent should not be handled prior to obtaining the test so as not to smear the particles from one area to the testing site.

Gunshot residue kits are of two types. One is a set of metal buttons containing adhesive and secured in a plastic vial. The other type is a cotton swab with clear nitric acid liquid in a vial accompanying the kit. The liquid is used to moisten the swab and swipe the swab along the suspected areas of each hand. It is important to verify or mark each hand vial separately with the appropriate right-hand and left-hand designation. A neutral may accompany the kit and it is to be opened and set on the clean counter while performing the test collection. This allows a background check of the environment to rule out a false-positive result. The swabs (or buttons) are swiped or dabbed along the surface of the forefinger, web of the thumb, and the thumb in areas where blowback from the gunpowder may come to rest if the person were holding a gun in the shooting position (Figures 8.21 and 8.22). For many years gunshot residue testing was not done because the interpretation is difficult and may lead to false accusations by the uninformed, and naïve interpretation of the results. Many times the kit is obtained on homicide or suicide cases to appease defense attorneys or the public that all was done to answer their questions rather than aid the scientific evaluation of the course of events during a shooting.

DNA AND FINGERPRINTS

Decedent DNA sampling onto an FTA card or filter paper can be immensely helpful in reconstructing a scene and blood spatter, especially in cases of multiple decedents or the possibility of the perpetrator leaving blood or other DNA material at the scene. Fingerprints of the decedent are equally useful for this reason as a known exhibit to rule out those from the other unknowns either on surfaces or a potential weapon. Fingerprints can also be used to confirm the identity of the decedent if prints are available in a known database by local law enforcement, FBI, Homeland Security, or Customs (ICE). By entering the confirmed identity of the deceased into the system, it allows the database to reflect current data and to close outstanding warrants.

ESSENTIAL SCENE DOCUMENTATION

The scene investigation findings can be very important in determining the manner of death especially in the single gunshot wound scenario. Some of the items to photograph and make note of in the report is the body position, location of the weapon in relation to the body, position of casings, bullet holes in walls or ceilings, and blood spatter in relationship to the body. Also critical to the evaluation is witness statements and if they match what the scene is demonstrating to the investigator.

Upon arrival, overall views of the body in relation to its surroundings from the corners of the room or at least three or four circumferential views of the scene are standard. If there are areas of the site where the gun safe, ammunition, or gun bag were kept or found those are also photo worthy. Photos of any medications, alcohol use, or notes are also useful. The body position needs to be photographed with note of the weapon in position to it. Include overall, medium, and close-up views of the weapon in the position it was found in if possible. Sometimes it has been moved by emergency medical personnel or law enforcement in an attempt at medical intervention. If that is the case, photograph the gun as it is being made safe for storage. Be sure to include the serial number, position of expended cartridges in the cylinder of a revolver, or the presence of live rounds in the chamber of a semi-automatic.

Location of expended casings should also be noted because it gives an indication of the weapon in relation to the proposed trajectory. It is helpful to take medium and close-up photos of the hands prior to covering them with paper bags to demonstrate any soot deposition or blood spatter. Medium and close-up photos of visible wounds or external clothing is also helpful. After the body is moved, blood can continue to saturate clothing and make the visibility of soot deposition difficult. As the body is being rolled to be placed into the body bag, this is a good time to quickly photograph the back and the amount of blood on the floor under the decedent. Prior to leaving, it is good to take an overall shot of the site where the body was positioned.

Blood spatter is usually projected in the area around the gunshot wound site and tissue with blood can extend across the room, car, or outside location. Blood spatter from gunshot wounds shows a high-velocity fine mist appearance. Larger round to oval blood droplets are low velocity and are not due to the gunshot wound itself unless the victim was able to move around after the shooting occurred. Blood oozing from the wound tends to follow the path of gravity and streak downwards from the site. An aberrant pattern in relation to the current position of the body and the dried blood may indicate the body was moved prior to the investigator's arrival.

Casings from a semi-automatic gun largely eject to the right. Because they are cylinders they may roll or bounce and become somewhat difficult to locate, especially if others have entered the scene. These need to be handled carefully so as not to smear any fingerprints that might be adherent to the surface. The easiest way to pick them up is to use a pen or pencil and insert it inside the casing to lift it into the proper envelope/bag.

Expended bullets outdoors, especially if they are small caliber, are very difficult to locate. Lead is not usually detected with even sensitive metal detectors, but they may be useful to locate casings. Inside a residence, expended bullets are easier to locate in ceilings, doors, or walls. It may be necessary to cut sections of drywall or wood away to retrieve them and it may be easiest to transmit the section to the laboratory for retrieval rather than risk damage to the striations. It may require dismantling surfaces to retrieve them, so having tools accessible in the response vehicle is a good idea. Expended bullets are best collected and placed in small envelopes or plastic containers. Wrapping in paper ensures they do not protrude through the envelope and become contaminated, allows absorption of blood, and pads the surface of the soft lead from damage during storage.

The report should also include the make, serial number, and caliber of the weapon, as well as the number of spent and unspent cartridges in the gun or scene. In multiple gunshot wounds, it is helpful to provide that information to the pathologist prior to autopsy. If multiple weapons are involved, the exact weapon may not be known but generalities of rifle versus handgun or shotgun are useful pieces of information for them.

All items collected from a scene need to be logged into a chain of custody by the collecting investigator and signed over to the property clerk at the evidence storage facility. Many times items directly on the surface of the body are transported with it to be collected at autopsy. It can be signed over at that time by the pathologist to the law enforcement investigator with other articles of evidence. It is helpful if the appearance of the body at the scene is disturbed as little as possible until evaluated by the pathologist. This means no wiping or washing of the wound, removal of clothing, or probing of wounds. Obviously, some disturbance will occur during resuscitative efforts, but it is helpful if emergency personnel can preserve evidence such as holes in clothing or make incisions, vascular attempts, and the like at sites away from wounds.

SUICIDE VERSUS ACCIDENT VERSUS HOMICIDE

The determination of the manner of death in a shooting depends on many factors in addition to the trajectory and estimation of the range of fire and number of gunshot wounds. It is possible to commit suicide with multiple self-inflicted gunshot wounds as well as walk around after nonlethal injuries creating a bloody scene. It is important to keep an open mind when evaluating gunshot wound scenes and evaluate each piece of the puzzle to come to the best determination. When in doubt, treat it as a homicide investigation until the information can be best evaluated by autopsy, toxicology, and witness statements.

Witness accounts may lend information about the recent state of mind of the decedent including health, social, or financial concerns, as well as knowledge of safe gun operation and gun storage. Information that the gun is normally in a gun safe or gun bag implies that certain purposeful actions needed to be undertaken to utilize it on oneself or fire accidentally. The more knowledge one has, the less likely the shooting occurred accidentally. Recent breakups with significant others, loss of job or home, depression including use of antidepressants, or excessive alcohol use all factor into the decision. Notes left at the scene are helpful but may not be totally indicative of a particular action or even when the person was writing the note. Helpful photographs of scene information, such as putting out keys, wills, and personal papers, are useful to indicate purposeful action against oneself. It is always good to take each piece of information systematically, but keep an open mind as families can alter scenes in attempts to make a suicide appear as accidents or homicides or vice versa. Motives for either can be financial, including insurance policies or inheritances. If something is not adding up, follow the instinct to hold the scene if possible until the pathologist can view the body or further information can be obtained from other witnesses or family members. Toxicology results may be necessary to confirm or deny their statements and add information about state of mind.

Russian roulette provides its own challenges as to manner of death. Russian roulette involves the use of a revolver in which a single cartridge is placed into the cylinder with the other chambers filled with empty casings. The cylinder is then spun so the location of the active cartridge is unknown. It may then be passed around or held by a single individual while pulling the trigger at oneself. If it does not fire a bullet, it will be spun again and passed or held usually to the head and fired. Eventually odds prevail and the gun goes off. This scenario commonly occurs during alcohol and/or drug use. Some would call this shooting an accident because of the muddled state of mind by the alcohol use. However, most pathologists call it suicide from the point of view that a person knows that pointing a gun to one's head and pulling the trigger can result in a lethal outcome. The willingness to perform the act is interpreted as a willingness to die and purposefully take one's life. Most are called suicide or occasionally undetermined manner of death.

Case Study

A 30-year-old male was found shot in the hallway of his residence after neighbors called 911 with complaints of shots fired. Upon arrival, police found the young male lying on his back with a 9-mm gun lying beside him. The door to the residence was open. The death investigator was called to the scene and noted gunshot wounds of the left clavicle and one to the right upper back. Abundant blood was present on the clothing where the body was lying in a pool of blood. The door did not have evidence of breakage or being forced open. His wallet was lying on the table in the hallway and the house was in order. Brown paper bags were secured over the hands and he was transported to the morgue for examination.

Head, chest, and abdomen X-rays were performed through the unopened body bag by morgue personnel. No bullets were visible on X-ray. Examination of clothing by the pathologist showed no gross soot on the shirt in the front or back. The shirt was torn near the left clavicle in a slit pattern with frayed threads evident on the outside of the shirt. Examination of the left clavicle wound showed a laceration without surrounding soot or stippling. The right upper back wound showed an oval marginal abrasion with the abrasion located at the 3 o'clock position and fine dusty stippling on the right shoulder in an area of 3 × 3 inches. Internal findings included a trajectory through both lungs and the left subclavian artery with 750 ml of blood in each pleural cavity. The pathologist certified the cause of death as “gunshot wound of chest” and manner as a homicide. The range of the wound was intermediate (arm's length, depending on the caliber of weapon) and the trajectory was right to left, back to front, and nearly horizontal.

MULTIPLE GUNSHOT WOUNDS

Multiple gunshot wound homicides can be very time consuming, especially the search for small-caliber bullets or the sheer number of wounds. It is best to approach these cases with full-body X-rays and have the X-rays available at the autopsy during the search for retrieval of the bullets and the trajectory. Bullets may cross paths and become very confusing.

Some pointers that may help to speed up retrieval of multiple bullets and sort out the trajectories include utilizing an autopsy diagram to draw the location of each entrance and exit wound with an assigned number or letter. Photographing the body with these designations marked on the skin adjacent to the wounds by a black felt marker will greatly aid dictation, transmission of information to law enforcement, and also be useful for later testimony. As a mentor mentioned, it is rare that internal examination will tell you which wound is entrance or which is an exit. The internal examination allows the investigator to link entrances to exits and delineate their path through the body. But the entrance and exit need to be decided to at least a high probability prior to opening the cavities. A chart to record the standard measurements for these types of cases can be found in the Appendix. This ensures systematic recording of each wound easier and dictating the report later. An assistant to record information on the chart is invaluable.

It is also very difficult to link entrance wounds and paths of multiple gunshot wounds with the organs removed from the body. It is best to try to link these up while the organs are within the cavity in their anatomical positions and, if at all possible, to note the trajectory paths during each layer of dissection from the skin and muscle to the bony landmarks to internal organs and paths through them. The initial autopsy has one chance at making certain determinations that can never be retrieved after certain alterations are made so the primary prosecutor has the best view to record this data.

Another useful trick is making a paper copy of the digital X-ray so that as each bullet is recovered its designation can be noted on the paper and the focus can turn to the unretrieved bullets. With more than a couple of bullets in a particular body area, it can quickly get confusing. Yellow sticky notes can even be used to obscure the ones found, further highlighting the ones still needing to be retrieved.

If possible, it greatly assists law enforcement, lawyers, and the lay public if trajectory rods are used to delineate the path from entrance to exit while the decedent is in the customary anatomic position. It should be noted that rods should never be inserted into the body prior to its being opened as they can create a new trajectory path. It is also very difficult with intersecting trajectories to determine the proper trajectory with each wound without viewing the internal organ pathways. Bony landmarks will be helpful in guiding the metal or wooden rods and are best utilized at the end of the autopsy after the bullets are retrieved and trajectories understood.

REFERENCES

[1] DiMaio V. Gunshot Wounds. New York: Elsevier; 1985.

[2] DiMaio V, Dana S. Handbook of Forensic Pathology. Boca Raton, FL: Taylor & Francis; 2007.

[3] Trimpe M. FBI Law Enforcement Bulletin: the Current Status of GSR examinations. The Federal Bureau of Investigation; 2011. Retrieved from http://www.fbi.gov/stats-services/publications/law-enforcement-bulletin/may_2011/The%20Current%20Status%20of%20GSR%20Examinations. [August 2013].

[4] GSR Collection. Instructions for Collecting Gunshot Residue (GSR) kit. Texas Department of Public Safety Crime Laboratory; 2010. Retrieved from http://www.txdps.state.tx.us/internetforms/Forms/LAB-17A.pdf. [August 2013].

[5] Gun Firing. Gunshot Residue. Missouri State Highway Patrol. Retrieved from http://www.mshp.dps.missouri.gov/MSHPWeb/PatrolDivisions/CLD/TraceEvidence/gunshotResidue.html. [August 2013].

CHAPTER 9
Sharp-Force Injuries

Learning Objectives

- Compare three features that distinguish hesitation wounds from defense wounds.
- Identify three features that characterize hesitation wounds.
- List the characteristics of a stab wound, incised wound, and laceration.

Key Terms

Exsanguination
Hesitation wound
Incision
Laceration
Stab wound
Defense wound

Chapter Summary

Sharp-force injuries are time consuming to examine, usually because they are in large numbers requiring meticulous measurements and documentation of each wound. This is hypothesized to result from the inability of these wounds to immediately incapacitate the victim. Unless the stab wound is to the head or spine, the decedent has the ability to continue to breathe and move, causing blood spatter, and usually resulting in death due to blood loss. Delayed complications from stab wound victims who survive can include pneumonia, wound infection, peritonitis, or brain death due to hypoxia.

Investigation techniques important to stab wounds include photographs of blood spatter in relation to the decedent and patterned hand, foot, or shoe prints. The position of the decedent at the scene is also important to document, as well as his or her physical proximity to a suspect knife, all knife holders/drawers, knives in dishwashers, etc. Attempts at clean up or containment of blood should also be noted.

It is important to secure the clothes of both the victim and on any suspects where it is important to look for transfer of blood or other evidence. It is useful to lay out the clothing on a clean papered surface to document these items for posterity.

Sharp-force injuries resulting from suicide are largely based on scene investigation findings and mental health history. Families and previous medical records can prove invaluable in making the distinction regarding manner of death.

INTRODUCTION

Sharp-force injuries are ones caused by knives or other cutting instruments or materials. This category of injuries includes chopping wounds and glass wounds. This chapter will begin with a discussion of the parts of a knife and the documentation needed to record the injuries and rule in or out various knives as the potential weapon. Various evidence procedures as well as the mechanisms of death will also be discussed.

ANATOMY OF A KNIFE

Most knives have a single cutting edge and a dull edge. An occasional knife will have a double cutting edge and create slightly different appearing wounds. The injuries knives create can vary in their dimensions, which may assist differentiating one weapon from another as being more consistent with the injuries on a body. To communicate accurately, some basic terminology of a knife needs to be understood (Figure 9.1).

- *Blade:* The blade is the cutting portion of a knife and is tapered to a point, through a belly (mid) region before connecting to the handle. The length of a knife is measured from the tip to the beginning of the handle.
- *Spine:* The spine is the dull edge of the blade of the knife. This edge is the portion that gives the knife thickness as compared to the tapered cutting edge.
- *Ricasso:* At the handle portion of the blade is a blunt, thicker portion called the ricasso that gives the blade strength at the junction. If the blade enters to this level it will give the wound a squared-off margin.
- *Guard or "hilt":* A feature not seen in every knife is a guard, occasionally referred to as a hilt, which is derived from its counterpart in a sword. It is a dull piece of metal that projects at right angles from the handle and blade and serves as a protective device preventing the hand from sliding down onto the blade during use.



FIGURE 9.1
Depicts the terminology used to describe various parts of a knife [1].

- *Handle:* The handle forms the grip area of the knife. It can be smooth or rough in texture, and contain a handhold grip or not. It may contain fingerprints if the surface has not been smeared or if the surface is not rough.
- *Butt:* The butt of a knife refers to the base of the handle opposite the tip. It may not leave sharp-force injuries but can be used as a blunt weapon leaving blunt-force injuries.

Each portion of the blade can leave particular characteristics to narrow the potential pool of weapons that may have created particular **stab wounds**. This forms the basis of the necessary documentation that needs to be recorded during autopsy. DNA testing in and around the handle for areas of blood transfer is usually sought, as well as fingerprints on the surface or handle.

AUTOPSY DOCUMENTATION

Sharp-force injuries are a general category to include all injuries created by a sharp edge. The wounds have smooth margins and lack bridging tissue between the margins. Within this category are stab wounds and incised wounds (Figure 9.2). Stab wounds are deeper than they are long, and incised wounds are commonly known as slashing injuries or **incisions** (surgical incisions can be an example) and measure longer than they are deep.

It is important to review the distinction between **lacerations** and sharp-force injuries. Lacerations contain abraded margins, have small strands of tissue extending between the edges of the wound, and tend to have irregular margins. This distinction and correct terminology is very important because a laceration is associated with blunt impacts, not knives. Sharp-force injuries have smooth margins, lack tissue bridging, and are not typically surrounded by contusions or abrasions. This distinction is important to aid the search for the correct weapon.



FIGURE 9.2
(A) A stab wound that enters the trunk of a decedent. (B) An incision is longer than it is deep, forming a slashing injury.

MEASUREMENTS

Sharp-force injury wounds are measured in three dimensions: length, width, and depth. The length of the wound is created by the cutting margin of the blade and depends on not only the specific knife but also how far it was inserted. As a knife is inserted and withdrawn, the edge of the wound is cut. The wound can actually be much longer than the width of the blade because of this cutting motion (Figure 9.3). The width of the wound corresponds to the thickness of the blade. A single-edged blade will have a square margin corresponding to the dull edge of the blade. The cutting edge will correspond to the acute angle portion of the wound. The length of the wound will vary due to the cutting as the blade is inserted or withdrawn. The depth of the wound is only a rough estimate of the length of the blade due to compression of the body as a knife is inserted and will also depend on how deeply the knife is placed.

The width and length of the wound is best estimated by reapproximating the edges of the stab wound (Figure 9.4). The margins gape apart due to



FIGURE 9.3
Diagram of a stab wound.



FIGURE 9.4
(A) The measurement of the dull edge of the knife that corresponds to the width of the wound when the edges have been reapproximated. (B) The edges of a stab wound reapproximated and held in place with tape to demonstrate the width of the wound.

the inherent elasticity of the skin called Langer's lines. While the wound is reapproximated, it is useful to characterize the angles of the wounds to determine if the wound is single or double edged. It is important to evaluate each of the wounds for potential abrasions created by the handle or guard of the knife. It is useful to look at multiple wounds to get a sense of the type of weapon used by comparing one to another, as well as to determine if the wounds appear to be caused by a single weapon or different ones.

The square margin of a wound is created by the spine of the blade and the acute angle is created by the cutting edge. If the blade has been inserted all the way to the handle and a ricasso is present, both margins may appear square. These characteristics should be noted in the description of each wound along with the dimensions and approximate location on the body.

The depth of the wound is an approximation and is done while the decedent is lying on his or her back in the anatomic position and the organs are located mostly posterior. Obviously, most people are not in this position when the incident occurs. However, this is the standard that has been adopted by pathologists for documenting all injuries. Wounds should not be deeply probed with a large instrument or finger until the wound track can be identified internally. A thin delicate probe can be used to get a depth from the skin to the surface of the cavities and identify a general direction of the wound path. It can be very difficult to line up wound paths after the surface skin has been reflected due to the elasticity and also the disturbance of the anatomy. Gathering the depth data is best done before the organs have been removed or moved around during the initial inspection.

An example of a stab wound description is as follows:

> Stab wound #1: There is a stab wound of the right upper chest measuring 71 in. from the sole of the right foot and 3 in. right of the midline. With reapproximation, the wound measures 2 in. long × 1/8 in. wide with a square margin superiorly and acute angle inferiorly. The wound passes into the chest through the right anterior second rib, incising the right upper lobe of the lung and ascending aorta. The path of the wound is right to left, downward, and slightly front to back. The estimated depth of penetration is 4 in.

Incised wounds are commonly known as slashing injuries or cuts. They are longer than deep but can also be life threatening when overlying major blood vessels. The location of these injuries can assist with the manner of death or add information about how the injuries occurred. When incised wounds are present on the anterior wrists, antecubital fossae, and isolated neck, a question of self-intent may be raised. Self-inflicted wounds may contain surrounding superficial wounds looking like curved abrasions on the arms, neck, abdomen, or legs. These are called **hesitation wounds** and are thought to be a test of the weapon and ability to inflict the final incision to end life. The wound depths need to be evaluated to note major blood vessel involvement. Many times the vessels retract



FIGURE 9.5
Numerous healed self-inflicted cutting injuries of both forearms.

under the muscle upon cutting and make this challenging. Scenes of self-inflicted incised wounds can be very bloody and need to be evaluated carefully so as not to miss a homicide incident.

Serrated blades are sometimes used and the depth of the wound will show no distinction from a smooth-edged knife. An indication that one was used is seen at the margin of a wound where fine, curved parallel abrasions may appear that correspond to the distance between the teeth of the serration.

Healed self-inflicted cutting scars can be seen on decedents and may reflect an underlying psychiatric issue pertinent to death (Figure 9.5). These are best documented photographically. Previous medical records documenting suicidal ideation, antidepressant use, or psychiatric illness are useful to determine a manner of death if the cause is related to drug intoxication rather than a cutting injury.

If the incised wounds are located on the backs of the arms or on the legs, they are consistent with defensive wounds as the injured is trying to ward off an attack. This is an important thing to note, as it means a person was conscious at the time of at least some of the inflicted sharp-force injuries. This is commonly brought up in court testimony.

COLLECTION OF EVIDENCE

The importance of collecting a knife is not only to preserve the evidence of the object itself but also the evidence that may be adhering to it, and to protect anyone from injury during its transport and storage. For this reason a sturdy box is useful (Figure 9.6). Companies actually make knife storage boxes but if none are available, a clean pizza box or gun or rifle box can be used. If all else fails, the knife can be placed into a large brown paper bag then a large box until it can be properly stored. Not only does the blade need to be protected but also the handle. Fingerprints may be retrievable. Even on blades that appear clean, the handle can be removed and blood located in the grooves of the handle or between the handle and the metal insertion into it, and can be used to link the knife to the victim.

Occasionally, the scene of the crime has been cleaned prior to it being located. Because sharp-force injuries are usually bloody, blood can become entrapped in tiles, baseboards near floors, behind door knobs, and in various other cracks. The amount of blood needed for a match is very small due to DNA technology. Location of the crime is important to determine a link between a suspect and the victim, as well as to establish law enforcement jurisdiction for investigation. Usually, the location of the crime determines who will prosecute unless they waive the jurisdiction to the one that contains the body. For comparison purposes, it is important to obtain a known DNA sample of each victim to link to a possible crime site or weapon.


INCHES
LABORATORY APPARATUS, FURNITURE
SCIENTIFIC INSTRUMENTS & CHEMICALS
VWR Scientific Products

FIGURE 9.6
A knife should be secured for safe transport and handled as little as possible before it is processed by the laboratory. Special transport boxes are available that secure a knife in place and prevent injury by the blade.

Sometimes the knife has been left in the decedent either by their own hand or by a perpetrator. The knife should not be removed prior to its location being examined by a physician (in the alive or dead victim). The grip area needs to be protected from smudging of prints and can be covered by a brown paper bag and secured in place by tape or string at the bottom of the bag. This allows adequate photography to be done and the knife handled in a clean environment to preserve prints and trace evidence adherent to the knife. It is usually not difficult to remove or dislodge the knife, and it should be handled in areas not usually gripped, such as the butt of the knife, sparing the handle as much as possible. It is then placed into a flat box and secured for evaluation by the laboratory.

Documentation of the clothing includes laying out each item and demonstrating the knife injuries through the surfaces if present. Many times the clothing is very bloody and these areas are difficult to visualize. It is useful to have white filter paper available to lay under the clothing defects and also to utilize pointers to show them more clearly. The clothing needs to be adequately dried in a clothing dryer prior to long-term storage in sealed brown paper bags that are then usually placed into bankers boxes. After photographing, the items can be placed into brown paper bags for short-term storage and transferred to the drying room. It may take a few days to adequately dry saturated clothing, and the interior of the drying cabinet is lined on the bottom by absorbent paper to contain draining blood from the clothing.

HESITATION WOUNDS

In self-inflicted injuries from sharp force, the decedent or injured person may have scattered superficial wounds appearing like scratches. They may be located at the margin of a major incised wound or located elsewhere on the body. Common locations are the wrists, forearms, abdomen, or neck (Figure 9.7). It is thought to be a testing of the sharpness of the blade and how much pain is



FIGURE 9.7
Two common locations for hesitation wounds to be located: superficial abrasions/incised wounds on (A) the forearm and (B) side of the neck.

associated with the cutting prior to a fatal wound being inflicted. The locations, as well as the number of superficial wounds, help distinguish these wounds from **defense wounds**, or those inflicted by another party.

DEFENSE WOUNDS

Defense wounds are those stab or incised wounds inflicted by another person on the victim and are characterized by being located on the arms or legs as they are being used to ward off knife blows. They are usually on the backs (posterior) of the arms, on the backs of the hands, or on the palms if the knife is grabbed (Figure 9.8). They may be located on the lower legs as they are raised to keep someone away from the vital head, neck, or torso areas.

SURGICAL INCISIONS

Surgical incisions have the same appearance as many stab wounds and the mechanism by which they are created is the same. It is important that medical personnel adequately document any changes made to the skin during resuscitation attempts and place them in the medical record (Figure 9.9). After death, all medical care appliances including chest tubes and thoracotomy sites need to be left intact. If at all possible, any medical intervention should avoid sites of previous stab or gunshot wound injury so that a forensic pathologist can adequately evaluate wounds in the event of the patient's death. If a wound is altered in some fashion, it is advisable to photograph it prior to alteration if at all possible and, at a minimum, document the description in the medical record. Otherwise,



FIGURE 9.8
A defense wound of the arm. They are also commonly seen on the posterior arms and hands as the arms are used to ward off the knife or the knife is grabbed by the hands.



FIGURE 9.9
An incision made by medical personnel to insert a chest tube into the side of the chest. It is important for medical personnel to document resuscitative attempts such as this and leave medical care items in place to differentiate these efforts from homicidal injuries.

Case Study

The office received a call regarding a decedent found dead on the bed of his residence. Upon arriving, the investigator noted a thin, middle-age male dressed in pajama bottoms lying on the bed with a cooking pot beside the bed on a newspaper. An outstretched arm was extended over the top of the pot, which contained about 500 ml of coagulated blood. The house was secure upon the officer's arrival and he had been called by the son of the decedent during a welfare check. Antidepressant medications were on the kitchen counter and multiple personal papers were lying orderly on the kitchen table, including a life insurance policy and driver's license. The son related that his father had lost his job approximately six months previously and was in jeopardy of losing his home due to financial difficulties. Examination of the body showed a deep incision of the right wrist including the area of the vessels to the hand. Superficial cuts were seen over the right antecubital fossa and to the right neck. A bloody kitchen knife was lying on the bed beside the decedent.

it is nearly impossible for the forensic pathologist to testify about the origin of these wounds and may require the clinician to appear in court testimony.

OTHER INSTRUMENTS

Knives are the most common instrument inflicting sharp-force injuries and vary in length, width, serrated or smooth, and single or double edge. Measuring and characterizing the various sizes of the wounds may lend some ability to rule in or out various blades. It should be remembered that when a knife is thrust to its deepest length, it may measure slightly longer than the blade length due to compression of the skin, fat, and body cavities. If a knife is presented to the pathologist for evaluation, it is helpful to make a rough diagram of its appearance and provide measurements within the file and for later testimony.

Other instruments causing sharp-force injuries include machetes, scissors, ice picks, forks, etc. These types of instruments will result in different patterns of the wounds from the usual and typical knife wounds in that they may be paired, appear more as punctures, or, in the case of a machete, have chop-wound qualities or even both entrance and exit wounds if it is thrust through the body. See example in Figure 9.10.

Chopping wounds from hatchets, swords, and axes will show qualities of both sharp and blunt impact depending on the sharpness of the cutting edge. The margins of the wound will be abraded due to the thickness of the instrument, and the destruction of bone will be more severe due to the greater energy dispersed in the wound. Gaping wounds of muscle, bone, and skin will be apparent.

Glass wounds, especially laminated windshields and house windows, can also lead to an abraded sharp-force injury due to the thickness of the glass and its blunt margins. The depths of the wound will show sharp margins of muscle



FIGURE 9.10
(A) A stab wound from a single-edged knife that shows the square margin (left) created by the dull edge of the knife and the acute angle (right) created by the cutting edge. (B) The wound's margins gape due to the elastic fibers of the skin (called Langer's lines). This photo also contains a patterned abrasion adjacent to the wound created by the guard of the knife. (C) Patterned stab wounds created by a Phillips-head screwdriver. (D) A stab wound from a flat-head screwdriver.

and vessels. Glass injuries can occur in the armpit or mid-arms if a window is broken, and cut edges injure the arm as it is reached or thrust through. An occasional case is an intoxicated individual who cannot find his or her keys to the residence and attempts to break a window to gain entrance, but results in gaping sharp-force injuries and dying outside the window.

MANNER OF DEATH

Most commonly, the manner of death from sharp-force injuries is either suicide or homicide. Occasionally, accidental deaths may result from unusual circumstances. The investigative information is the key to determining the manner and the presence or absence of hesitation-type wounds. The latter must only be one part in the distinction because some perpetrators inflict superficial wounds to coerce a victim to tell them information or to facilitate cooperation. Suicide notes, evidence of preparation to prevent a mess such as pots to catch draining blood, protective sheets or towels, and history of depression all support a diagnosis of suicidal intent. Someone found outside, blood trails through the crime scene, lack of depression, wider distribution, and the numbers of wounds all support a diagnosis of homicide. In either instance the weapon may be nearby or not. Pots of water, bathtubs of water, or watery blood in the sinks should also be evaluated. Some individuals commit suicide in bathtubs of water so the vessels will dilate and they will bleed faster and also so as not to make a mess. Other times bloody residue can mean the perpetrator cleaned blood off him- or herself or the weapon prior to leaving. Many times the person will have multiple and quite numerous sharp-force injuries and documentation of each wound can be quite laborious. A chart is in the Appendix to assist with recording the various measurements in an orderly fashion.

The usual mechanism of death is blood loss (**exsanguination**), which takes some period of time. The period of time someone survives even from fatal wounds depends on many factors. The number of fatal wounds, which organs are involved, and the underlying health and age of the decedent all play a role in the rate someone dies or collapses. Some victims have been known to run city blocks or even slowly deteriorate in front of witnesses. Since death is not immediate with stab wounds, the number of wounds inflicted by a perpetrator usually increase as the victim keeps moving or fighting during the confrontation. Depending on the size and location of the wounds with exposure of vessels outside of the body cavities will result in how much blood is present at the scene. Arterial blood spatter can be seen as periodic arcs of fine blood spray. Venous bleeding tends to be seen as a pattern of falling droplets.

A rare but occasional mechanism of death is an air embolus. This occurs in arterial stab wounds where the artery is exposed to the air. As blood is attempting to be pumped through the arterial wound incision, air is mixed with the blood causing a “gap” in circulation. Exactly how this causes death is speculation. The appearance of air in the vasculature is very difficult to see grossly or microscopically unless it is a large bolus and may not be appreciated at autopsy.

Another mechanism by which stab wounds can cause death is via compromise of the airway either by a wound directly to the tracheobronchial tree within the mouth or blood draining into the airway from other wounds. This can be sometimes seen as aspirated blood into the more peripheral areas of the lungs. Obstruction of the airway may also be seen as coughed blood onto walls or surroundings.

Delayed deaths from stab wounds can result from the sequelae of blood loss resulting in hypoxic brain injuries (loss of oxygen to the brain and resulting brain death) and infectious complications either via pneumonia, peritonitis (infection within the abdominal cavity), or within the stab wound itself. I have seen at least one death of necrotizing fasciitis (severe sloughing and infection of the skin and muscle) due to a sutured stab wound by a food-contaminated knife. The wound later became infected and inadequately treated, resulting in death.

Examination of a suspect/perpetrator should include photos of the arms and hands to demonstrate any injuries during the confrontation. This person may also have palmar injuries where the hand slipped down from the handle onto the cutting edge during the wielding of the knife. Suspect clothing is also important to document for spatter and droplets from the victim. Bottoms of shoes can be especially important for matching of a sole tread to any track areas at the scene, and also to document the presence or absence of blood. Victim DNA may be recovered from any of these items. It is important to look for discarded clothing in trash bins, burn piles, laundry hampers, or dumpsters. Some items may be located in the washer in an attempt to obscure the evidence. If bleach has been used on areas of spatter, DNA retrieval can be difficult, but consultation from the crime lab may be helpful.

Suicide by sharp-force injury is more common in countries where guns are regulated. They can appear as dramatic injuries with large gaping incised wounds of the neck or as multiple incisions over the arms and wrists. Occasionally they are single stab wounds to the chest or abdomen but are usually multiple. Hesitation wounds or healed areas of self-inflicted cuts are helpful to distinguish suicide over homicidal injuries. Suicidal neck wounds may show an upward deviation to one margin as the knife is drawn across by the opposite hand, and can be deep with visualization of the trachea and multiple sawed cuts over the anterior spine in the depths. Suicidal arm wounds are usually multiple and can be placed vertically or horizontally over large vascular sites. Rarely, hesitation wounds have been seen on the legs or backs of the knees.

Suicidal wounds of the abdomen are rarely seen but may show the adjacent superficial wounds and a deep penetrating wound with or without the knife still in place. Similarly, suicidal stab wounds of the head are seen and usually have the knife still in the skull. Stab wounds of the chest can be single or multiple and, in one instance of multiple stab wounds, a depressed man was witnessed to place the knife on his chest, and ram the knife into the chest multiple times by running into a wall, removing it, and repeating the process.

REFERENCE

[1] Fisher J. Knife Anatomy, Parts, Names, Components, Definitions, Terms. Jay Fisher-World Class Knifemaker; 2013. Retrieved from www.jayfisher.com/Knife_Anatomy_Parts_Names_Definitions.htm#Knife_Anatomy_1. [August 2013].

CHAPTER 10

Sudden Death in Adults

Learning Objectives

- The pathologist hands you, the investigator, a death certificate stating the decedent died of a myocardial infarction due to coronary artery thrombosis. It is the investigator's job to call the family with the cause of death after autopsies are completed. Apply what you have learned about this cause of death and sketch the key features in layman's terms to explain it to the family over the phone.
- List three common causes of death on a death certificate submitted for cremation that would require further investigation and why.
- Review the list of reportable deaths for your state. Formulate three standard general questions you need to routinely ask a physician reporting a death from a hospital to determine if you should take coroner/medical examiner jurisdiction of the decedent or let him or her sign the death certificate.
- A death occurs in a heavy-equipment construction site and you, the investigator, need to respond to the scene to evaluate and photograph. What three items of personal safety gear would you make sure are in the response vehicle before leaving the office?

Key Terms

Atrophy
Proximal
Distal
Aneurysm
Cardiac valve
Myocardium
Alveolus
Thrombus
Embolus
Jaundice
Epi-
Sub-
Hypo-
Hyper-

Chapter Summary

This chapter discusses numerous common natural causes of death that may be seen in the coroner/medical examiner office. Many of these natural diseases also are impacted by drug use or may occur in a work environment. It requires investigative input to make the distinction of a natural death from an unnatural one in many circumstances. Drug levels are helpful but require interpretation in light of the decedent's underlying renal and liver function, as well as a specimen type and underlying pathological diseases. Also discussed are environmental causes of death with investigative documentation that can assist to make the diagnoses.

INTRODUCTION

Sudden death in adults can range from a natural disease such as a heart attack or can be related to drugs or an environmental incident causing sudden collapse. In this chapter we will discuss common natural diseases that can cause sudden death, as well as environmental and drug-related causes that may contribute to or directly cause death.

NATURAL CAUSES OF DEATH

This is a huge category of pathological processes. Only the most common causes will be discussed here. To keep organized, it is easiest to divide this section into organ systems. A quick review of the anatomy and physiology is also given for each organ system.

Cardiovascular

ANATOMY AND PHYSIOLOGY

The heart is divided into four chambers: right atrium, right ventricle, left atrium, and left ventricle. Each chamber is separated by a valve that controls the flow of blood through the heart based on its beating contractions. The tricuspid valve is located between the right atrium and right ventricle, and the pulmonic valve controls the blood flow out of the right heart into the pulmonary arteries. Blood flows through the pulmonary arteries into the right and left lungs. Oxygenated blood returns to the heart via the pulmonary veins. It enters the left atrium and passes into the left ventricle through the mitral valve. Blood flows out of the left ventricle through the aortic valve into the aorta and general venous circulation where it takes the oxygenated blood to the muscles and tissues. Oxygen reaches the cells of the tissues via capillaries and exchanges it for carbon dioxide. Deoxygenated blood returns to the heart via veins from the extremities and tissues into the right atrium. See Figure 10.1.

The aorta is the large vessel lying over the spine carrying oxygenated blood from the heart throughout the body. It is especially prone to acceleration/deceleration injuries from traffic accidents at the ligamentum arteriosum in the arch of the aorta within the chest. This area serves as a fetal structure that closes at birth, but is a weak attachment point for the heart. With sudden stopping, such as in a motor vehicle accident, the heart will act as a pendulum continuing forward with the momentum. This point of attachment is the common site of large lacerations and bleeding into the chest.

In the **distal** region (near the pelvis), the aorta divides into the right and left iliac arteries. These vessels then form the right and left femoral arteries in the groin to supply oxygen to the legs. The return from the legs enters into the right and left femoral veins to the right and left iliac veins then the inferior vena cava (Figure 10.2).

Blood also enters the inferior vena cava from the gastrointestinal tract where nutrients and swallowed medications are absorbed from the small intestine. Blood flows through the liver where nutrients are metabolized and by-products are prepared for excretion. Medications that were absorbed from the intestine are metabolized into active compounds or converted into inactive compounds. This phenomenon is called first-pass metabolism and it is important for the interpretation of toxicology results and the collection of specimens for toxicology. If the


A
Location of the heart
B Heart Exterior
Superior vena cava (from upper body)
Right pulmonary arteries (to right lung)
Right pulmonary veins (from right lung)
Right atrium
Right coronary artery
Inferior vena cava (from lower body)
Right ventricle
Aorta (to body)
Pulmonary artery
Left coronary artery (behind pulmonary artery)
Left pulmonary arteries (to left lung)
Left pulmonary veins (from left lung)
Left atrium
Left anterior descending artery (coronary artery)
Left ventricle
A
A
Location of the heart
B Heart Interior
Superior vena cava (from upper body)
Right pulmonary arteries (to right lung)
Aortic valve
Right pulmonary veins (from right lung)
Right atrium
Tricuspid valve
Inferior vena cava (from lower body)
Pulmonary valve
Right ventricle
Aorta (to body)
Pulmonary artery
Left pulmonary arteries (to left lung)
Left pulmonary veins (from left lung)
Left atrium
Mitral valve
Left ventricle
Septum
Direction of blood flow
B

FIGURE 10.1
The (A) exterior and (B) interior heart anatomy, as well as the blood flow through the heart chambers and vessels.


Intracranial Veins
External Jugular Vein
Internal Jugular Vein
Subclavian Vein
Internal Thoracic Vein
Axillary Vein
Cephalic Vein
Brachial Vein
Intercostal Vein
Basilic Vein
Median Cubital Vein
Thoracoepigastric Vein
Radial Vein
Median Antebrachial Vein
Ulnar Vein
Inferior Epigastric Vein
Deep Palmar Arch
Superficial Palmar Arch
Palmar Digiti Veins
Inferior Thyroid Vein
Left Brachiocephalic Vein
Superior Vena Cava
Azygos Vein
Inferior Vena Cava
Hepatic Vein
Hepatic Sinusoids
Portal Vein
Splenic Vein
Renal Veins
Superior Mesenteric Vein
Inferior Mesenteric Vein
Abdominal Vena Cava
Testicularis Vein
Common Iliac Vein
Internal Iliac Vein
External Iliac Vein
External Pudendal Vein
Deep Femoral Vein
Great Saphenous Vein
Accessory Saphenous Vein
Femoral Vein
Superior Genicular Veins
Popliteal Vein
Inferior Genicular Veins
Great Saphenous Vein
Smal Saphenous Vein
Anterior Tibial Vein
Posterior Tibial Vein
Deep Plantar Veins
Dorsal Venous Arch
Dorsal Digital Veins

FIGURE 10.2
The circulatory system. Note the locations of the subclavian vein and femoral veins, which are common sites of toxicology specimen collections. It is helpful to note their locations in relationship to easily palpable bone landmarks for orientation on a decedent.

specimen is obtained from the inferior vena cava prior to passing through the liver or from the heart, quantitative results may be skewed from the actual systemic value obtained from a peripheral specimen. This first-pass metabolic phenomenon is the reason for obtaining femoral blood for toxicology testing.

The heart muscle is supplied by oxygenated blood through the coronary arteries, which originate in the aorta just above the aortic valve. The right coronary artery supplies the anterior, lateral, and posterior right ventricle. The left main coronary artery originates from the aorta just above the aortic valve then almost immediately divides into the left anterior descending coronary artery, which supplies the anterior and lateral left ventricle, and into the left circumflex coronary artery, which supplies the lateral and posterior left ventricle. These vessels are very small caliber and easily blocked by clots or cholesterol deposits (Figure 10.3).

The heart beats synchronously to perform as an efficient pump. The beats are controlled by an electrical current that originates in the right atrium and spreads throughout the right and left ventricles. The current is recorded by an electrocardiogram (ECG), and in the majority of the living, is called normal sinus rhythm (NSR). With decreased oxygen to the heart cells, they can become


A
Coronary artery (supplies blood and oxygen to heart muscle)
Coronary artery
Heart muscle
B
Healthy heart muscle
Blood clot blocks artery
Blocked blood flow
Plaque buildup in artery
Dead heart muscle

FIGURE 10.3
Graphic depiction of what happens during a myocardial infarction, or heart attack. The coronary artery becomes narrowed either by atherosclerosis or coronary artery spasm resulting in blood clotting and further obscuring the lumen. The loss of blood flow becomes critical to the heart cells (**myocardium**), and with lack of prolonged oxygen, they die, resulting in failure of the cardiac pump.

irritable and the electrical pattern becomes disturbed, resulting in rhythms that can be rapidly fatal (e.g., ventricular tachycardia or ventricular fibrillation). Because it is an electrical phenomenon, there are no anatomic findings at autopsy to confirm an arrhythmia. However, the underlying pathology may be present to precipitate one and that can be documented.

ATHEROSCLEROSIS OR ARTERIOSCLEROTIC CARDIOVASCULAR DISEASE

The most common cause of death in the modern world is blockage of the coronary artery vessels of the heart or arterial vessels in the body by cholesterol and fatty deposits. This process is called atherosclerosis, arteriosclerotic cardiovascular disease (ASCVD), or hardening of the arteries (Figure 10.4). It involves deposition


A Normal artery
Artery wall
Normal blood flow
Artery cross-section
B Narrowing of artery
Abnormal blood flow
Plaque
Narrowed artery
Plaque

FIGURE 10.4
Atherosclerosis of an arterial wall. The deposit is composed of inflammation, fibrin, fatty deposits, and eventually calcium, causing the inner lumen to narrow. Small blood clots become adherent and may totally occlude blood flow downstream.

of the fatty material along the inner wall of the vessel. This invites inflammation and breakdown of the underlying arterial wall with resulting **aneurysm** formation (bulging of the arterial wall due to weakness of the muscular component), and further accumulation of lipid blocking the lumen or blood clot adhering to the damaged wall with total blockage of blood flow (thrombosis). Blockage of oxygenated blood to an organ causes the cells of that organ to die (called an infarct or necrosis). Heart attacks are called myocardial infarction in medical terminology. The blockage of a coronary artery by a clot (usually adherent to an atherosclerotic plaque) (Figure 10.3) is called coronary artery thrombosis and can be a cause of sudden death due to abnormal heart arrhythmias. Risk factors for atherosclerosis include obesity, poor diet, diabetes, and family history.

Atherosclerosis can also result in blockage of blood flow to the legs resulting in peripheral vascular disease. Signs of this include brown discoloration of the skin on the lower legs and loss of hair. In the distal aorta near the branches to the legs, atherosclerosis can cause an abdominal aortic aneurysm (AAA) to form, which can suddenly rupture causing death by internal bleeding. An aortic aneurysm can be surgically treated to prevent rupture by placing a clothlike vascular graft reinforcement within the lumen. Similar graft material can be used to repair blockage to the femoral arteries in peripheral vascular disease (Figure 10.5).

Atherosclerosis of the heart is treated by stent placement (small tubes of metal mesh) placed within the coronary arteries. This usually requires dilation of the coronary vessel (coronary angioplasty) during cardiac catheterization, a procedure performed using a large intravenous catheter inserted in the groin. This dilation is somewhat risky because the coronary artery may burst, causing bleeding inside the pericardial sac, and sudden death or bleeding. Bleeding may also occur from the groin insertion site. Another treatment for cardiac atherosclerosis is coronary artery bypass graft surgery (CABG), where a length of vein is surgically removed from the leg then attached to the aorta and sutured distal to a coronary artery blockage (bypassing the blockage) to allow oxygenated blood to reach the heart cells. Lack of oxygen to the myocardial cells causes chest pain, referred to as angina, many times treated with nitroglycerin tablets that dilate the coronary arteries, allowing blood to flow around a blockage. See Figure 10.6 for examples of procedures.

VALVULAR HEART DISEASE

The valves may become narrowed by aging, from a disease like rheumatic heart disease, or because they were congenitally malformed, resulting in valvular stenosis. This process may occur in any of the valves but is most common in the mitral or aortic valves. Narrowing of the valve causes more workload for the heart to get blood past the narrowing. Valves may also become incompetent from other disease processes. Incompetence occurs when the edges do not close completely, resulting in backflow of blood during cardiac pumping. This backflow is called regurgitation and can lead to heart failure because of the constant inefficiency of the outflow process. Heart failure results in blood backing up in all the organs trying to return venous blood to the heart. The result is blood and


A
Aorta exiting heart
Thoracic aorta
Heart
Artery to kidney
Abdominal aorta
A
B
Thoracic aortic aneurysm
C
Abdominal aortic aneurysm
B
Descending Thoracic Aneurysm
Endovascular Surgery

FIGURE 10.5
(A) The two forms of aneurysms that commonly form in the aorta due to atherosclerosis. The bulging outward occurs due to the inner pressure on the weakened arterial wall. The size of the aneurysm becomes critical after a maximum dimension of 6 cm, and is at high risk of rupture into the abdominal cavity causing sudden death. (B) These are repaired by vascular graft material within the lumen. http://www.nhlbi.nih.gov/health/health-topics/topics/arm/types.html

fluid accumulating in the lungs, which eventually causes blood to accumulate in the liver, and fluid in the extremities, which is seen as swelling of the ankles (peripheral edema). Valves can be repaired during open-heart surgery similar to CABG procedures.

HYPERTENSION

High blood pressure puts increased stress on the heart and strain on the vessels due to increased workload (Figure 10.7). If not controlled by medication, this causes the heart to enlarge and outgrow its blood supply. The myocardium becomes irritable and is prone to an arrhythmia and infarction. Increased


A
Location of the heart
B
Internal mammary artery graft (artery relocated from chest wall)
Vein graft (vein removed from the leg) is stitched to the aorta and coronary artery
Blockage in coronary artery
Artery graft is stitched to the coronary artery
Heart
Coronary arteries
Note: Arrows show the direction of blood flow through the grafts to the coronary arteries
A
Coronary Angioplasty
Catheter with balloon
Alternative site
Inflated balloon compresses the plaque
Catheter insertion site
B

FIGURE 10.6
Depictions of the various cardiovascular procedures that are commonly performed [12].


A
Coronary arteries located on the surface of the heart
Coronary arteries
B
Catheters
Coronary artery
Closed stent
Plaque
Expanded stent
Balloon
Narrowed artery
Closed stent around balloon catheter
Plaque
Artery cross-section
C
D
Stent widened artery
Compressed plaque
Increased blood flow
Stent
Widened artery
Compressed plaque
C
A
Electrodes inserted into vein leading to heart
Electrodes in heart
Implantable defibrillator inserted under skin
Right atrium and ventricle
B
Pacemaker
Electrodes in heart
D

FIGURE 10.6, cont'd


Main complications of hypertension
Brain stroke
Vision loss
Hypertensive retinopathy
Heart attack
Blood vessel damage
Atherosclerosis
Kidney
failure

FIGURE 10.7
Hypertension (high blood pressure) is a systemic disease. The elevated arterial pressure puts an increased workload on the heart, kidneys, and vessel walls, and is a risk factor for renal disease, myocardial infarction, and strokes [12].

blood pressure can also lead to ruptured vessels, resulting in strokes or bleeding internally from ruptured aneurysms. Elevated blood pressure also causes damage to kidneys and can decrease renal function for excretion of waste from the blood.

MYOCARDITIS AND BACTERIAL ENDOCARDITIS

The heart is susceptible to viral and bacterial infections. The most common bacteria result from intravenous drug use or as sequelae of Streptococcus infection resulting in rheumatic fever. Symptoms of myocarditis are vague and include generalized muscle aches, mild shortness of breath, and, possibly, intermittent fever. If the cause of the fever or source of the infection is not well documented, it may be necessary to take jurisdiction of the case to aid the public health department to trace exposed contacts.

Bacterial endocarditis is inflammation and bacterial growth on the **cardiac valves** causing their destruction (Figure 10.8). The risk factor for this disease is intravenous



FIGURE 10.8
Bacterial endocarditis is composed of bacterial colonies growing on the surface of the heart valves and destroying their surface. The bacterial colonies are friable and may break off, causing colonies to grow in distant organs, as well as occlude blood flow with necrosis. Risk factors are intravenous drug use, long-term intravenous therapy, and dental procedures [12].

drug use with dirty needles. It is occasionally seen in hospitalized patients requiring long-term intravenous therapy. If the person has an underlying history of rheumatic heart disease or structurally abnormal valves, the risk of contracting endocarditis is even greater, and may occur following a dental cleaning. Bacteria within the blood settle on the surface of the valve followed by the body's inflammatory response, which basically dissolves the valve. The patient presents with severe respiratory distress due to fluid accumulation in the body, a new onset heart murmur, and poor heart function. It is associated with a high morbidity and mortality.

DISSECTION OF THE AORTA

Dissection of the aorta may occur in young or older adults. It is more common in patients with a history of hypertension because of the added stress it places on the aorta. It is also seen in a genetic disorder of young males with Marfan's Syndrome, a connective tissue disorder. A dissection occurs when intravascular blood enters the wall of the aorta and separates the layers until it ruptures into a body cavity and exsanguination occurs. Occasionally, it may rupture back into the lumen of the aorta and the patient will live until further bleeding occurs from the weakened wall. The tear most commonly begins in the arch of the aorta and extends distally into the thoracic region. Occasionally, it will also dissect **proximally** and around the coronary arteries, causing sudden occlusion of them or rupture into the pericardial sac. It can similarly extend into the carotid arteries and result in a stroke. Symptoms include pain in the back between the shoulder blades prior to the collapse.

CARDIOMYOPATHY

Cardiomyopathy is a group of diseases of the heart muscle cells causing the heart to assume an enlarged or dilated chamber size, resulting in decreased pumping efficiency and heart failure (Figure 10.9). A dilated cardiomyopathy is related to chronic alcohol use. Other types are restrictive cardiomyopathy, where deposits of material are present within the myocardium, causing poor contractile function. Hypertrophic cardiomyopathy is an extremely large heart, two to three times the normal size, with resulting susceptibility to arrhythmias. Except for alcohol-related cardiomyopathy, these can have a genetic predisposition and follow-up by surviving family members with a cardiologist is recommended.

FIGURE 10.9 Contrasts the changes of hypertrophic cardiomyopathy with dilated cardiomyopathy and their appearance to a normal-size heart. Some of the etiologies of the cardiomyopathies are family related and follow-up with a cardiologist is advised [12].


Heart Muscle Diseases
Myocarditis
Inflammation of heart muscle
Hypertrophic cardiomyopathy
Thickened heart muscle
Dilated cardiomyopathy
Weakened heart muscle
Enlarged ventricle

Respiratory

ANATOMY AND PHYSIOLOGY

The main function of the lungs is the exchange of oxygen and carbon dioxide for efficient healthy cell functions (Figure 10.10). The air enters the respiratory system via the mouth or nose and flows past the epiglottis and vocal cords to enter the trachea. The lower airway divides into the right and left main stem bronchi, then bronchioles, and, finally, the **alveoli.** It is within the alveoli where the capillaries of the blood are in very close proximity to the inhaled oxygenated air and the


A
Nasal cavity
Mouth
Epiglottis
Larynx
Trachea
Pleura
Left lung
Ribs
Alveoli fill lungs
Bronchial tubes (airways) within lung
Diaphragm
A
B
Bronchioles (tiny airways)
Alveoli
Carbon dioxide (CO_2)
Oxygen (O_2)
Pulmonary artery (blood from heart)
Alveoli (cross-section)
C
Air space
CO_2
O_2
Alveolar wall
Capillaries
O_2
CO_2
Capillaries network surrounding alveoli
Pulmonary vein (blood to heart)
B

FIGURE 10.10
(A) Anatomy and (B) physiology of the lung. Note the relationship of the lung capillaries to the alveolar spaces for efficient oxygen exchange.

waste carbon dioxide can diffuse from the blood into the alveoli for exhalation. The lung alveoli look very similar to a sponge with the small outlines formed by the capillary walls. Spaced throughout the lung tissue (parenchyma) are small bronchioles that convey the air to and from the alveoli from the larger airways. The more alveoli, the greater ability the oxygen/carbon dioxide exchange, because of the increased surface area the gases come into contact with the blood supply.

Deoxygenated blood enters the lungs via the pulmonary arteries and oxygenated blood returns to the left heart via the pulmonary veins. These large vessels along with the main stem bronchi are located in the hilum of each lung. The right lung has three lobes (right upper, middle, and lower) and the left lung two lobes (left upper and left lower). The easy way to remember this is that the heart occupies the left lung cavity and needs to have fewer lobes than the right.

Because of the close interrelationship of the heart and lungs, heart disease results in lung disease and vice versa. Pulmonary edema (fluid on the lungs) is a common secondary symptom of heart disease (Figure 10.11). Disease states can exist at any level of the respiratory anatomy and result in decreased oxygenation of the blood. Blockage of the posterior mouth or upper airway will cause an inability for the gases to enter and leave the lungs. An example of this is a bolus of food. The smaller airways may become blocked by mucous, swelling by inflammation, or food. Oxygen exchange can become inhibited at the alveolar level by inflammation, fluid, or disease. An example would be pneumonia or cancer. If blood flow is decreased to the lungs or the number of red cells carrying the oxygen is decreased (anemia or blood loss), oxygen-carrying capacity to the body will decrease. Examples of decreased blood flow would include a pulmonary **embolus** where a clot is blocking the vessel or hemorrhage from trauma.



FIGURE 10.11
Pulmonary edema decreases the efficiency of oxygen exchange because the alveoli are filled with watery fluid. The origin of the fluid is commonly heart failure with inefficient pumping or fluid overload due to renal or liver disease.

CHRONIC OBSTRUCTIVE PULMONARY DISEASE

Chronic obstructive pulmonary disease (COPD) is a pathology term describing both emphysema and chronic bronchitis (Figure 10.12). It is a disease process usually resulting from smoking, which causes enlargement of the airspaces (emphysema) and/or excess mucus production with inflammation of the bronchi (chronic bronchitis). Both result in decreased ability to exchange oxygen and the patient experiences shortness of breath, as well as being prone to pneumonia and increased risk of cancer.

PNEUMONIA

Pneumonia is an infection within the lungs that can be acquired by breathing in the infectious organism, spreading to the lungs during a septic event from another primary source, or inhaling food or saliva (Figure 10.13). Whatever the origin, all result in the alveolar air spaces becoming blocked by inflammation,


A Normal Lungs
Bronchioles (tiny airways)
Trachea (windpipe)
Airways
Right lung
Left lung
Alveoli (air sacs)
Detailed view of lung cross-section
B Lungs With COPD
Bronchioles lose their shape and become clogged with mucus
Walls of alveoli are destroyed, forming fewer larger alveoli
Detailed view with COPD

FIGURE 10.12
Describes the changes associated with COPD. The destruction of alveoli (emphysema) and abundant bronchial mucous (chronic bronchitis) decreases the efficiency of oxygen exchange and can eventually make the person oxygen dependent and eventually is terminal.


A
Location of lungs and bronchial tubes
Trachea (windpipe)
Bronchial tube
Right lung
Left lung
B
Normal bronchial tube
Bronchial tube lined with a thin layer of mucus
Bronchial tube wall
(Bronchial tube in cross-section)
C
Bronchial tube with bronchitis
Bronchial tube with increased amount of mucus
Inflamed bronchial tube wall
A
Alveoli Changes in Lung Diseases
Pneumonia
Healthy
Emphysema
Fluid and blood cells in alveoli
Alveolar walls thickened by edema
Alveolar membranes break down
B

FIGURE 10.13
(A) Bronchitis may also occur in patients without COPD and is an infection of the bronchi with abundant mucous resulting in coughing and shortness of breath, usually with fever. (B) Pneumonia is the spread of infection into the lung alveoli where the bacteria or viruses cause an inflammatory response. Both result in decreased efficiency of oxygen exchange and shortness of breath. Pneumonia is a common cause of death, either primary or as a complication of some other disease process.

mucus, and debris with decreased oxygenation of the blood. Pneumonia is a common complication of traumatic injuries, such as falls resulting in fractured ribs or hips, as a result of assaults or motor vehicle accidents. It can rapidly cause death in or outside the hospital. Whenever a primary diagnosis of pneumonia is the only cause on a death certificate, it should be evaluated by the investigator and be further investigated for any non-natural risk factor that would result in the death being certified as an accident, homicide, or suicide. The death certificate may come to the investigator's attention via the health department vital records, funeral home, or as an authorization for cremation. Prior to permits being given for burial or cremation, the information will need to be determined either via speaking with the treating physician or obtaining medical records.

PULMONARY THROMBOEMBOLISM

A pulmonary thromboembolism is a blood clot that has lodged in the pulmonary arteries, causing obstruction to the outflow of deoxygenated blood from the heart to the lungs. The mechanism of death is sudden right-sided heart failure (Figure 10.14). A pulmonary **thrombus** is one that forms directly within the pulmonary artery rather than travel there. A pulmonary embolus is one that forms elsewhere, becomes dislodged, and travels to the lungs where it becomes an obstruction. The distinction is difficult and usually the term pulmonary thromboembolism is used to describe either origin of the clot.

The importance for the death investigator is the underlying cause of why such a clot should form. Risk factors for thromboemboli include obesity, immobility, and trauma. The trauma may be minimal or massive resulting in bed rest. Other causes of immobility can be recent surgery, especially of an extremity, which would



FIGURE 10.14
Pulmonary thromboembolism is a result of blood clots blocking the pulmonary arterial blood flow from the heart into the lungs (B). The clots usually originate in the legs (thrombophlebitis) or the pelvis and migrate to the lungs (A). The lungs are able to inhale and exhale, but the exchange of gases at the alveoli is inhibiting without constant blood flow. The person presents with sudden onset of shortness of breath and chest pain. Risk factors are patients who are bedridden from trauma, those with a clotting disorder, immobile patients, or those with poor leg circulation.

make it reportable in some state law statutes. Pulmonary thromboemboli can also be sporadic, with no underlying trauma, but have familial clotting factors that increase the risk. This diagnosis is suspected by clinicians when a patient presents with sudden onset of shortness of breath, decreased oxygen concentration in the blood, and sudden collapse. Tests done by clinicians to make this diagnosis include a ventilation perfusion scan (a positive test is one where there is ventilation but no perfusion of the lung, called a VQ mismatch) or Doppler studies of lower extremities to determine the presence of vascular clots. The importance for an investigator is to recognize that this diagnosis may have resulted from trauma and will usually require evaluation by the pathologist to determine the cause and manner of death. Many times this results in an autopsy to confirm the presence of the pulmonary thromboembolism and may require dissection of the extremities to determine the site of origin. Sometimes the entire clot has moved to the lungs and no longer resides within the legs; other sources of these clots include the pelvis or pelvic organs. Occasionally, a vascular catheter or nidus will be present within the pulmonary artery causing the clot to form directly under the same set of risk factors.

PULMONARY HYPERTENSION

Pulmonary hypertension is high blood pressure isolated only to the lungs and is caused by cardiac disease or by abnormalities of the pulmonary arteries. It can progress to eventual heart failure and death. It is not usually a reportable case to a death investigation department unless there is a therapeutic misadventure in its treatment that causes death (Figure 10.15).


A
Recipient aorta and pulmonary arteries remain
Heart is cut so diseased heart can be removed
B
Recipient aorta and pulmonary arteries remain
Sutures used to attach donor heart
Donor (transplanted) heart in place
A

FIGURE 10.15
Transplantation of the heart, lungs, or heart–lung transplant together are not uncommon and may be the only treatment available for some patients. (A) The incisions made by the transplant team to remove a heart and insert in a recipient.


A
Main airway and vessels are cut to remove the diseased right lung
Recipient:
Main airway
Pulmonary artery
Pulmonary veins
Heart
Location of the lungs and heart in the body
B
Healthy donor (transplanted) lung in place
Stitches used to connect donor (transplanted) lung to recipient's main airway and blood vessels
B

FIGURE 10.15, cont'd
(B) The incisions made to recover and implant lungs for transplantation. It is helpful to understand these procedures when donor teams are requesting organs from decedents falling under the jurisdiction of the death investigator.

Liver

ANATOMY AND PHYSIOLOGY

The liver is an important organ to detoxify chemicals and medications; assist with metabolism of fats, sugars, and proteins to basic building blocks; and aid digestion via bile secretions. It is an extremely vascular organ and sensitive to low blood flow in periods of shock, but has regenerative properties to heal itself to some extent. If toxic materials accumulate within the liver or it is frequently exposed to abuse, it will fail or scar, decreasing its efficiency, which can lead to death. Signs of liver failure or disease are yellow discoloration of the skin or whites of the eyes (**jaundice**), accumulation of liquid in the abdominal cavity (ascites), and swelling of the feet and hands (edema). Because blood returning to the heart from the lower torso and gut must filter through the liver first, scarring can cause increased pressure in the venous system, resulting in enlargement of small vessels within the esophagus and stomach (varices) that can easily bleed, sometimes massively, resulting in death.

CIRRHOSIS

The scarring that forms in the liver is called cirrhosis and many times results from alcoholism, hepatitis B or C, or abnormal accumulation of minerals such as copper. Cirrhotic patients who die at home are usually reported to the death investigator because the scene can show large areas of blood loss. The cirrhosis inhibits drug excretion and routine medications can accumulate causing death by drug intoxication or combined with alcohol use. The scarring also causes increased pressure to develop in the portal vein and backup of blood into the esophageal and splenic veins. The esophageal veins can become greatly dilated causing rupture and massive bleeding via vomiting or from the rectum (Figure 10.16).

Liver failure occurs when the liver has shut down and is no longer able to keep up with the body's needs. The liver may be necrotic or cirrhotic. The decedent turns bright yellow and may require dialysis if the cause is thought to be reversible. Causes of liver failure include acetaminophen overdose, extended periods of low blood pressure, hemorrhage, or end-stage cirrhosis from alcohol use or hepatitis. When this type of case comes to the attention of the death investigator, it will need questioning as to the underlying etiology of the failure to determine if it falls within the jurisdiction of the office. Many times, the initial event occurred some days prior, and admission blood specimens may be needed from the hospital laboratory to evaluate a drug screen.

Easy bruisability is frequently seen in those with liver disease because the liver is the site of production of the blood-clotting factors. With cirrhosis and other diseases of the liver, production of these proteins will be lacking. Some of the factors require vitamin K to produce them, and in the past, vitamin K was commonly given to cirrhotic patients who were bleeding in an attempt to correct the deficit. Minimal trauma, even medically induced, can result in huge contusions or oozing from wounds. This bleeding can also extend to minimal brain trauma resulting in intracranial hemorrhage from a minor fall. The fall can be remote from the time of death or recent. Any bruising about the head or chest should alert the investigator to have the body further evaluated by the forensic pathologist.

Not all those with cirrhosis have jaundice of the skin or eyes. Other disease states that can affect coagulation include fatty change within the liver, which is also seen in alcoholics, chronic hepatitis, or an inherited condition due to lack of a particular coagulation factor. The liver is a common site of metastatic tumors



Liver, Gallbladder, Pancreas and Bile Passage

Esophageal Varices

Liver
Gallbladder
Right and left hepatic ducts
Cystic duct
Common hepatic duct
Bile duct
Accessory pancreatic duct
Pancreatic duct
Minor duodenal papilla
Major duodenal papilla
Tail of pancreas
Body of pancreas
A
Duodenum
Head of pancreas
Esophageal varices
Esophagus
Liver with cirrhosis
Portal vein
B
Stomach

FIGURE 10.16
(A) Relationship of the liver to the stomach, pancreas, and blood flow to esophagus. With cirrhosis of the liver, the scarring causes increased venous pressure and blood backs up into the portal vein system, resulting in an enlarged spleen and enlarged veins in the esophagus called varices (B). The varices may rupture causing massive internal bleeding and death.

to spread from the primary origin within the bowel, pancreas, lung, ovary, or breast, and may also exhibit jaundice.

HEPATITIS

There are multiple kinds of hepatitis, but A, B, and C are the most common. Hepatitis A is contracted by fecal oral contamination, usually of food by someone who has the disease. It is a relatively short-lived illness with jaundice and a low-grade fever, but communicable. Long-term disease and chronic carrier states are not seen in hepatitis A. The person may feel sick with these low-grade symptoms, but will recover without treatment. The importance in making the diagnosis is to prevent the spread of the disease and distinguish it from other types of hepatitis or causes of jaundice.

Hepatitis B and C are caused by different viruses than A and are both associated with acute and chronic liver disease. They are acquired through intravenous drug use or exposure to body fluids, either via blood or sexual contact. Hepatitis B and C are associated with chronic hepatitis and cirrhosis, which can lead to liver failure. Hepatitis B has immunizations available to prevent transmission but hepatitis C does not. Either hepatitis B or C may remain only as an acute disease without progressing to a chronic state, but C commonly does become chronic. All types of hepatitis are reportable to the health department for tracing contacts to prevent further transmission.

LACERATION

The capsule of the liver is tense and easily lacerated by direct blows or compression of the overlying ribs, which is commonly seen in motor vehicle accidents. Occasionally CPR during resuscitation can lacerate the liver as well because of the compression of the ribs. Since the liver is very vascular, a laceration can lead to internal bleeding. In the postmortem state, blood may ooze from a superficial laceration, but is usually a lower quantity than that seen in motor vehicle accidents.

Gastrointestinal tract

ANATOMY AND PHYSIOLOGY

The gastrointestinal tract includes the esophagus, stomach, and small and large intestines. Food enters the mouth where chewing decreases the size of the food particles to be swallowed. The tongue moves the food to the back of the mouth where the epiglottis closes over the airway protecting it from inhalation. The food passes down the esophagus to the stomach where it is mixed with acid and further decreased in size for better absorption. It passes through the pyloric valve into the duodenum where pancreatic digestive enzymes are added. The small intestine is the site of absorption of the food nutrients and drugs taken orally. The first part of the intestine is called the jejunum followed by the ileum. By the time the food reaches the lower ileum, it is still a thick liquid, and passes through the ileocecal valve into the ascending colon, followed by the transverse colon, then the descending colon and rectum. The large bowel is the site of water reabsorption and does not absorb nutrients. See Figure 10.17.


GI
Mouth
Esophagus
Diaphragm
Diaphragmatic Hiatus
Lower Esophageal Sphincter (AKA cardiac sphincter)
From portal vein
Blood IN
Liver
Spleen
Exocrine Pancreas
Stomach
OUT
to Portal Vein
Gastric Artery IN
Gall Bladder
To portal vein
Duodenum
Pyloric Sphincter
Mesenteric Arteries
Jejunum
Ileum
Terminal ileus
Ileococcal valve
Cecum
Colon
to rectum and anus

FIGURE 10.17
Outlines the relationship of the gastrointestinal tract to the liver and absorption of nutrients. It is important to understand the relationship of the blood flow from the small intestine to the liver. Orally ingested medications are absorbed into the blood from the small intestine and many undergo metabolic changes in the liver to active or inactive compounds. This is the first-pass phenomenon. The blood then goes to the heart before becoming systemic. If toxicology specimens are retrieved in the blood from the heart or the blood from the gut, the quantitative values may not be representative of systemic values and be artificially high.

BLEEDING

Bleeding may occur anywhere within the tubular system but most commonly from the esophagus, stomach, or duodenum. Causes of bleeding from the esophagus are most commonly dilated veins (varices) from a cirrhotic liver. The veins become greatly distended with cirrhosis and even the process of eating may erode off the surface epithelium, exposing the vein to rupture and massive bleeding.

Bleeding may also occur from gastric erosions over a large surface area. This type of bleeding is less dramatic but can also be a result of chronic alcohol use.

Gastric or duodenal ulcers are craters that form in the lining of the stomach/duodenum that can erode downward into an artery or vein causing massive bleeding. They may also perforate through the stomach or intestinal wall, leaking gastric acid and food into the sterile peritoneal cavity, resulting in peritonitis. After a ruptured esophagus, stomach, intestine, or appendix, peritonitis will rapidly occur and the situation is life threatening unless the rupture is repaired.

An obstruction of the bowel may also cause peritonitis. It can be a twisted bowel, some internal blockage such as a tumor or polyp, foreign material, or an incarcerated hernia where the bowel is pinched in the hernia sac. Sudden death may follow if not medically treated. Signs of blockage include distended abdomen without decomposition, early decomposition changes over the abdomen even in the early postmortem period, and, if bleeding has occurred, dark, tarry feces on the buttocks or clothing.

Occasionally abdominal aortic aneurysms may erode into the lumen of the intestines and cause massive bleeding out the anus. Most of these cases might not be a death investigation case, other than they die suddenly at home with large areas of blood that concerns detectives, or the person is without a treating physician.

Endocrine abnormalities

ANATOMY AND PHYSIOLOGY OF THE PANCREAS

The pancreas is the site of manufacture of multiple digestive enzymes and insulin for the metabolism of sugars (glucose). The digestive enzymes enter the duodenum along with bile through the common bile duct. This duct can become blocked by gallstones and cause the enzymes to be released into the pancreatic tissue resulting in self-digestion of the tissue. The intestines have checks and balances to prevent this, but tissues such as the pancreas and peritoneum do not, which causes pancreatitis and peritonitis. Pancreatitis can also occur in alcoholics without a blockage by gallstones. Long-term pancreatitis can cause a loss of digestive enzymes and insulin, the other product of the pancreas. Insulin is necessary to usher glucose into the cells where it can be used by the metabolic machinery for energy production. Without insulin, glucose remains in the bloodstream and is able to reach high levels, resulting in diabetes mellitus.

DIABETES MELLITUS

Diabetes mellitus takes two forms: type I (insulin dependent) and type II (medication dependent). The pathology is the same in both types, and the only variation is how quickly the glucose can get out of control (Figure 10.18). In type I it can be very rapid within a few hours, and type II usually is a more chronic elevation. However, both can result in a condition called diabetic ketoacidosis.


Healthy
Insulin
Insulin receptor
Glucose
GLUT4
Type I Diabetes
Insulin
Insulin receptor
Glucose
GLUT4
Type II Diabetes
Insulin
Insulin receptor
Glucose
GLUT4

FIGURE 10.18
Contrasts the cellular differences of type I and type II diabetes. Insulin is produced by the islet cells of the pancreas and is necessary for glucose to enter cells where it is utilized for energy production. In type I the pancreatic islet cells are destroyed and there is not enough insulin to escort the glucose into the cell. In type II, the body is able to produce insulin but in decreased amounts for the demand, and the cell receptors are resistant to it so the glucose is not able to enter the cell. Both types I and II result in elevated blood glucose.

Because insulin is needed for glucose to enter the cell for the metabolic machinery, if glucose is not available to it, the machinery goes to its backup plan. It begins to inefficiently metabolize fats and proteins within the cell to generate energy. This creates products called ketones and acids, which alter the body's delicate acid-base balance. Electrolyte abnormalities will develop and be seen predominately as rising potassium in the blood. This can reach lethal levels with cardiac arrest.

Testing for glucose levels is easily done by diabetics using a home glucometer and adjusting insulin levels to prevent the acidosis. The same testing can be done in decedents, but on vitreous looking for the elevated glucose. Diabetic ketoacidosis is usually suggested with postmortem vitreous glucose values greater than 400 mg/dl. Testing for ketones is easily done using urine dipsticks and looking for the excreted ketones and excreted glucose when it reaches very high levels. These products are associated with the early symptoms of diabetes, which are increased thirst and frequent urination.

Too much insulin and low blood glucose can also result in a lethal outcome. This occurs if the person takes the insulin but doesn't eat or takes too much insulin in relationship to the intake of food. Blood glucose needs to be above 60 for the brain cells to maintain consciousness. This is why paramedics give a bolus of glucose upon finding someone unconscious. If the unconsciousness is due to low glucose, the patient can have rapid reversal of symptoms. Postmortem, a low glucose is impossible to diagnose because the vitreous glucose normally begins to drop immediately upon death, and if already at a low level to begin with, it will be 0 at a postmortem reading. However, if the premortem glucose was 800 mg/dl, testing will show it to still be elevated postmortem, depending on the estimated interval between death and testing.

Diabetes is a risk factor for other diseases that can result in sudden death, including atherosclerotic cardiovascular disease, peripheral neuropathy resulting in injuries to feet and hands, ulcers of the legs and feet from poor circulation, impaired vision, cardiac disease, and strokes. In type I any small infection can precipitate ketoacidosis.

ANATOMY AND PHYSIOLOGY OF THE THYROID GLAND

The thyroid gland is responsible for how rapidly metabolic machinery works in the body. It tends to equilibrate cell machinery over days to weeks rather than making minute-to-minute changes. Thyroid gland diseases rarely cause sudden death.

ANATOMY AND PHYSIOLOGY OF THE PITUITARY

The pituitary, in conjunction with the hypothalamus in the brain, controls the thyroid, adrenal, and growth hormones, as well as the production of eggs or sperm by the ovaries and testes, respectively. It also secretes an antidiuretic hormone, controlling the water balance of the kidneys by increasing water reabsorption, and making the urine more concentrated.

Diabetes insipidus is a disease commonly confused with diabetes mellitus. However, it is a totally different disease caused by an abnormality in the antidiuretic hormone system within the pituitary, or within the kidneys, where the hormone acts. This abnormality results in large quantities of water being excreted and excess urination. Therefore, the relationship to the symptoms of early diabetes mellitus are increased thirst (polydypsia) and increased urination (called polyuria). The blood sugar in diabetes insipidus is normal and there is no risk for ketoacidosis.

Renal abnormalities

ANATOMY AND PHYSIOLOGY OF THE KIDNEYS

The kidneys are the filtering machine of the body and sort out the by-products of cellular metabolism that are no longer useful from the ones needed to maintain homeostasis (balance) of the cell processes. The kidneys excrete harmful products of protein metabolism, and yet retain a level of blood protein that is healthy for water balance (Figure 10.19). They also maintain electrolyte balance by excreting any excess materials not needed, such as excess salt, calcium, or potassium that may be ingested. Some useful products are normally reabsorbed, including glucose. A disease affecting the kidneys will affect this delicate balance of filtering, which can create electrolyte abnormalities resulting in disturbance of water balance or cardiac arrhythmias. Renal failure is the term used to describe this electrolyte abnormality due to damage to the filtering mechanism of the kidneys. The kidneys also dispose of protein waste, which is monitored by blood tests for urea and creatinine values. Renal failure can be acute or slow in onset, termed chronic. Acute failure can occur with sudden blood loss damaging the microscopic structures responsible for the filtration, called glomeruli. Chronic renal failure results from diseases such as diabetes mellitus or atherosclerosis.

Nervous system

ANATOMY AND PHYSIOLOGY OF THE BRAIN AND SPINAL CORD

The brain is responsible for conscious thoughts, control of movement through the spinal cordand primitive nonconscious things such as respiration, cardiac activity, swallowing, and movement of food through the gastrointestinal tract (Figure 10.20). It is possible to lose large areas of the cortex where consciousness resides and still maintain respiratory and cardiac functions. This is declared as brain death. The brain works much like an electrical circuit with the "wires" between different areas insulated from cross-communication by a material called glial tissue. The neurons are the main cellular structures with the wires formed by delicate strands of neural tissue extending from them. To consciously move the arm, it requires a group of these wires to form a tract and extend from the brain to the spinal cord and eventually to the arm. Disruption anywhere along this tract can impair the conscious movement. The spinal cord is composed of thousands of the wires forming tracts extending from the brain to all body functions, including the organs and muscles. Branches off the spinal cord occur at all levels. Disruption of the spinal cord in the neck affects all functions below the neck—movement of the arms and legs—with the possibility of respiration affected, depending on the level of the transection. In contrast, a disruption in the lower spinal cord at the waist will only affect the legs and bladder function with cardiac and respiratory activity intact.

The nervous system includes the brain, spinal cord and its coverings, and skull. Any of these layers may become involved by disease processes. From the outer


Basic steps in urine formation
Blood flow
Afferent arteriole
Efferent arteriole
① Filtration
Renal corpuscle
Nephron
② Reabsorption (solutes, water)
Peritubular capillaries
③ Secretion (additional wastes)
Renal tubule
④ Excretion
A
Continuous ambulatory peritoneal dialysis
Capillary network of peritoneal membrane
Dialysis fluid into cavity
Peritoneal cavity
Fluid plus waste drained out
Movement of waste products from capillaries into peritoneal cavity
B
Vein
Artery
Blood from Dialysis Machine
Blood to Dialysis Machine
Graft
C

FIGURE 10.19
(A) The efficiency of the microstructures within the kidney called glomeruli and tubules. Their job is to filter the blood and rid the body of excess water, minerals, electrolytes, and other by-products to maintain a steady-state balance. (B) If the kidneys fail, these materials accumulate and can cause death. Treatment is via peritoneal or (C) hemodialysis, which operates as artificial kidneys.


The meninges of the brain
Skull
Superior sagittal sinus
Arachnoid villus
Periosteal layer
Meningeal layer
Dura mater
Subdural space
Arachnoid mater
Subarachnoid space
Pia mater
Gray matter
White matter
Brain
Blood vessel
Falx cerebri
A
Brain
Sensory receptor
Dorsal root ganglion
Sensory neuron
Spinal cord
Motor neuron
Peripheral nerve
Motor nerve ending
B

FIGURE 10.20
(A) The relationship of the dura to the brain and skull. Note the subdural and epidural spaces, which are sites of potential hematomas. (B) The relationship of the brain to coordination of movement. Single nerve fibers extend from the brain to the lower portions of the spinal cord, then to the muscles. Interruption of the tract in its course from the brain, spinal cord, or nerve fibers to the muscle can affect the ability to control movement.

table of the skull inward, the layers progress from bone, to dura, then to brain or spinal cord tissue. Between the nervous tissue and the dura is a potential space called the subdural space (**sub-**, meaning below). Between the dura and the skull is a small potential space called the epidural space (**epi-**, meaning above).

A filmy layer of nearly clear membrane lies directly on the brain called the arachnoid with a potential space called the subarachnoid space. Trauma is the most common cause of pathology within the nervous system and can manifest as bleeding in any of the potential spaces or even into the brain or spinal cord tissues themselves.

INTRACRANIAL HEMORRHAGE

This is a general term that encompasses different pathologies and describes any type of bleeding within the skull. When seen on a death certificate not issued by the coroner/medical examiner, it requires further investigation to define which of the pathologies it is, and to determine if it is an unnatural death. This will require the admission medical records including the emergency personnel report, admission history and physical, as well as CT/MRI scan reports. Depending on this information, it may require the body to be brought to the office for examination. Sometimes it can be very difficult from the history to differentiate whether a coexistent pathology resulted in a fall or the fall resulted in the pathology. Examination of the brain by the pathologist may be necessary to sort out the findings.

Intracerebral hemorrhage usually refers to a stroke (Figure 10.21). A stroke results from a blockage of blood flow to an area of the brain by a clot and results in necrosis (cell death). It can also result from a ruptured capillary vessel, with bleeding into the brain tissue, causing swelling and cell death. Risk factors for a stroke include hypertension and atherosclerotic cardiovascular disease and all the risk factors that have been mentioned for either of those.

Subdural hemorrhages are blood accumulations between the dura membrane and the surface of the brain. The origin of this blood is ruptured veins that extend across this space and is caused by acceleration/deceleration injuries. Bleeding occurs more commonly if the brain is **atrophied** (shrunken, usually due to aging or disease), which stretches these veins. Subdural hemorrhages commonly occur in alcohol-related deaths, as well as the elderly, and can occur from a standing height or even minimal trauma, leaving few surface skin features of the underlying hemorrhage. It can present with symptoms of slowly decreasing consciousness with or without an episode of witnessed trauma. It is easily diagnosed by internal examination of the skull or a clinical CT/MRI scan. Occasionally an intracerebral hemorrhage can rupture through the cortex and extend into the subdural space. Examination of the inner skin surface (called the galea) may also aid the differentiation by locating a contusion not previously seen externally. Skull fractures not previously appreciated may also be identified with an internal exam and corroborate an accidental manner of death.

Contusions of the brain are actual bruises to the brain tissue. They typically occur on the tips of the brain or in areas directly underlying blows to the skull. They are usually focal contusions involving only the surface of the cortex and


Embolus (blood clot) in cerebral artery blocks blood flow to part of the brain
Location of brain tissue death
Brain
Cerebral arteries within brain
Direction of blood flow
Blood clot breaks off (embolus) from plaque buildup in carotid (neck) artery
Embolus blocking blood flow
Brain tissue death
A
Brain Stroke
Ischemic Stroke
Hemorrhagic Stroke
Blockage of blood vessels; lack of blood flow to affected area
Rupture of blood vessels; leakage of blood
B

FIGURE 10.21
The difference between an ischemic and hemorrhagic stroke. A stroke results from lack of oxygen to the brain tissue resulting in cell death (necrosis). In ischemic strokes (figure B on the left) the stroke is due to a blockage of the blood flow by atherosclerosis or a clot causing the brain to die. In hemorrhagic strokes (figure B on the right) blood vessels rupture, causing bleeding into the brain as well as disrupting oxygen supply. A hemorrhagic stroke can rupture into the subdural space and result from natural disease, which may need to be distinguished from a subdural hematoma due to trauma.

not the deeper white matter seen with strokes. Contusions can heal and result in yellow tan scars that can become seizure foci.

Coup contusion is the term used to describe bruises directly underlying an inflicted injury or blow to the skull (Figure 10.22). The force is transmitted directly to the brain parenchyma causing rupture of the surface blood vessels. A small overlying subarachnoid hemorrhage may also be present. In these injuries, the brain injury will be in the same location as the skin injury, plus/minus a skull fracture. Homicidal manner needs to be excluded with these injuries.

Contrecoup contusions are injuries that occur on the opposite site of the skin injury and are due to a fall injury. As the person falls and strikes their head on the ground, the bruise will be created on the skin. The force of the fall is transmitted to the brain tissue, which strikes the opposite internal portion of the skull creating the brain contusion. Occasionally, a small contusion will also be seen on the side of the fall, but the majority of the hemorrhage will be opposite. A skull fracture may result from the fall and will be located on the side contacting the ground. These types of brain injuries have an accidental manner of death. All things need to be considered from the scene, however. It is possible to get a contrecoup contusion from a fall after someone is struck on the head and received a coup contusion.

Subarachnoid hemorrhages are ones within the delicate membranes covering the surface of the brain parenchyma. These do not cause death by volume accumulation like subdural hemorrhages, but by the presence of blood creating irritability of the electrical system. This is thought to affect the respiratory/cardiac centers. The etiology can be an underlying natural disorder or an inflicted injury by a blow to the lower face causing a rupture of a vertebral artery. Natural causes of death include a ruptured Berry aneurysm or a ruptured arteriovenous malformation (AVM). Occasionally strokes may extend into the subarachnoid space. A Berry aneurysm is a sacular area of one of the arteries at the base of the brain caused by a weakness of the arterial muscular wall. Ruptures of aneurysms or AVMs can be precipitated during spells of elevated blood pressure or rupture spontaneously. Either may have symptoms of headaches and occasionally seizures. Berry aneurysms may run in families and survivor follow-up for screening is recommended. See Figure 10.23.

Epidural hemorrhages are arterial bleeds located between the dura and the skull with resulting pressure on the brain. The arterial bleeding originates from a skull fracture lacerating a communicating artery lining the internal skull. These bleeds occur rapidly with sudden deterioration in consciousness. If the skull fracture communicates externally through the skin, the epidural hemorrhage will be minimal due to drainage. The distinction of the epidural hemorrhage from a subdural one is important for defining the etiology of the fracture and the underlying manner associated with it.



FIGURE 10.22
(A) A contrecoup contusion where the fall results in external trauma on one side of the skull and brain injuries on the opposite side. (B) A coup contusion where the injury site is on the same side and many times underlying the site of impact, and is due to inflicted trauma from a weapon. Injuries below the hat brim suggest accidental origin and those above the hat brim (C) suggest nonaccidental origin. Investigation of how the injury occurred is very useful to make the distinction.


Cerebral Aneurysm
Saccular aneurysm
Fusiform aneurysm
A
Aneurysm in cerebral artery breaks open, causing bleeding around the brain
Pressure of blood on brain causes brain tissue death
Brain
Cerebral arteries within brain
Bleeding caused by broken open aneurysm
Brain tissue death
B

FIGURE 10.23
Common locations of small aneurysms that occur in the brain. Their thin walls may rupture resulting in subarachnoid hemorrhage and sudden death.

Seizures are a result of a disturbance of the brain's electrical system causing irregularities with symptoms of altered awareness of the surroundings, possibly a movement disturbance, and loss of bowel or bladder control. Some patients with seizures have a previous history of trauma and others have no known trauma but have experienced seizures for many years (idiopathic seizures). It is possible to die of a seizure disorder. The underlying mechanism causing death is not clear since death is not always a result of aspiration of food or continuous seizures (called status epilepticus). Patients with chronic seizures may not be compliant with medications or have breakthrough poorly controlled seizures, even on medications. Toxicology will add information about the decedent's medication compliance. The diagnosis is made by excluding other causes of death and finding low levels of seizure medication. Occasionally the levels will be therapeutic, but may have the history of breakthrough seizures. There are usually no brain findings in the idiopathic type. Hemorrhage within the tongue is occasionally seen, but not diagnostic of a seizure disorder, as any mechanism resulting in the tongue being between the teeth will result in the muscular bleeding. Old brain injuries can be an etiology for a seizure disorder, and if documented to a previous injury, can result in an accidental or homicidal manner. Idiopathic seizures have a natural manner. It is important to identify the type of seizure medication and perform a medication count for information about compliance. It may be difficult to locate information about a remote injury and the family may be the best source to locate the medical record documentation.

Seizures can also be a symptom associated with other disease states such as drug intoxication or a brain neoplasm. Witnesses may describe a seizure as part of a terminal event but their presence does not necessarily indicate a seizure disorder.

MENTAL ILLNESS AND SUDDEN DEATH

Those with mental illness diagnoses have a myriad of potential causes of death and many will need to be examined and evaluated by the coroner/medical examiner office. The mental illness can precipitate an overdose of medication, either intentionally or accidentally. Other suicide methods, including cutting, gunshot wounds, hangings, etc., may have an underlying psychological history.

In cases of no obvious causes of death in a mentally ill person, underlying natural disease may have precipitated death, such as pneumonia or sepsis. Ingestion of foreign substances can cause bowel obstruction or perforation, or even death due to ingestion of materials contaminated by botulism organisms from dirt or other foreign materials.

Many of the psychiatric medications, namely the tricyclic antidepressants and the antipsychotics, affect the thermoregulatory centers of the brain [7]. Mentally ill patients taking their medications are prone to hyperthermia and sudden collapse in hot environments. The drug levels can be therapeutic values and there are no diagnostic signs at autopsy. Scene findings will include elevated body temperature, which may be difficult to assess in a homeless person found outside in a hot environment. The diagnosis will then become one of excluding other causes.

DELAYED DEATHS DUE TO BRAIN INJURIES

This category includes multiple etiologies of brain injuries, including birth injuries, delayed traffic injuries, delayed gunshot wounds, and basically any hypoxic injury. Many of these patients become confined to care centers or are wards of the state. The reason for the underlying brain injury may be buried in medical records that deal with the multiple chronic natural illnesses resulting from the brain injury. These include aspiration pneumonia, urinary tract infections with sepsis, decubitus ulcers, contractures, seizures, or even failure to thrive. Many times a patient's body structure is distorted, making it difficult to place into body bags. It may be necessary to wrap him or her in a plastic shroud and sheet.

The challenge is to determine the underlying etiology of the brain injury and determine if it falls within the jurisdiction of the coroner/medical examiner to issue a death certificate, or if it is a natural cause of death, allowing the attending physician to sign the certificate. There may be issues of care the person received, necessitating at least a scene response to evaluate the condition of the surroundings and body to make the best decision. Photo documentation is advised to communicate the findings to the forensic pathologist or an investigating agency. Adult protective services may have been involved in the death, and communication can be initiated with them, as well as the appropriate law enforcement division, if necessary.

NEOPLASMS

Patients dying of known previously diagnosed tumors are not usually within the jurisdiction of the death investigator unless they die at home and the physician is not available or hospice arrangements have not been made. Occasionally unknown neoplasms are diagnosed by a forensic pathologist. Some may be massive necrotic neoplasms of the face or breast with large ulcerations not previously treated. Other times the findings may be more subtle, with only internal masses that have usually spread (metastasized) from the initial (primary) site. One question many families has is whether the tumor in the decedent puts them or the decedent's offspring at risk for similar malignancy. The best response is to have the family seek evaluation by their family physician after they have received a copy of the autopsy report. The physician can use this information to best decide how to proceed and counsel them medically.

Some neoplasms may have a link to previous employment and families are requesting autopsies for pathologic diagnosis to receive compensation. It will depend on state law and individual office policy whether these fall under the coroner/medical examiner jurisdiction. An example is mesothelioma, which is commonly associated with asbestos exposure. Employment history where this exposure occurs includes plumbing, ship building, and construction. The development of the neoplasm occurs many years after the exposure, and an exposure does not necessarily result in development of a neoplasm.

Neoplasms of the brain can be either primary (they originate solely within the brain and rarely spread elsewhere) or a metastatic spread from a primary neoplasm elsewhere. Common neoplasms that spread to the brain are breast, lung cancers, or melanoma. In either benign or malignant lesions, the neoplasms can put pressure on various locations of the brain and result in personality, behavior, or movement disorders; seizures; or decreased levels of consciousness as the disease progresses. Primary brain tumors include glioblastomas, astrocytomas, meningiomas, pituitary adenomas, or spinal cord ependymomas.

Some neoplasms present with obstruction of the kidney or bowel with abdominal distention, weight loss, or even bile duct obstruction, resulting in jaundice or severe pain due to pancreatitis. Some neoplasms and metastatic disease to lymph nodes cause obstruction of the ureters and the onset of renal failure.

Hospice patients and those with previous do not resuscitate (DNR) directives may die at home and come to the attention of the death investigator if the paperwork was not completed or the physician is not available to sign the death certificate. There may also be allegations of overmedication by a caregiver as an assisted suicide. In some states, assisted suicide is legal but in the majority it is not. These cases will need to be evaluated on a case-by-case basis by consultation with the forensic pathologist.

Infectious disease

State health departments publish a list of reportable diseases requiring follow-up for exposed contacts, preventive treatment, and prevention of widespread epidemics, such as the one for California shown in Figure 10.24. They also do reporting to the Center for Disease Control in Atlanta where nationwide trends are evaluated. For epidemiological purposes, they may require blood or other frozen preserved tissue biopsy material to perform identifying procedures. Hospital laboratories usually notify health departments of an organism identified from the list, however, as a death investigator it is also a good idea to confirm notification for the pathologist. They may request this tissue, which can be coordinated through the pathologist.

Epidemiological studies are important to prevent an outbreak of a disease from spreading through the community, state, nationally, or even internationally. A study locates vectors carrying the disease and treats or eradicates them to prevent spread. It also allows coordination of proper treatment regimes for exposed family members, medical personnel, and those who have contracted the disease.

Establishing a cause of death due to an infectious disease involves culturing various fluids and tissues in a microbiology lab to determine the infectious agent. This means the necessary biological materials must be acquired during the autopsy procedure, placed into the appropriate transport container required by the laboratory, and promptly transported to the lab for proper procedure and handling. The laboratory can have standards requiring that it be processed within a necessary time so prompt attention is required. It can take up to five days for results to be obtained in routine bacterial or viral cultures, and up to six weeks in fungal or tuberculosis cultures.

Many patients who die of an infectious disease may show minimal or no external findings on examination. The one clue is they tend to decompose more quickly than what the environment or circumstances would predict. There may be vague history of not feeling well, cough, and possible fever. There may be publicized outbreaks in the community. To prevent transmission to the investigator



Title 17, California Code of Regulations (CCR) §2500, §2593, §2641.5-2643.20, and §2800-2812 Reportable Diseases and Conditions*

§ 2500. REPORTING TO THE LOCAL HEALTH AUTHORITY.

- **§ 2500(b)** It shall be the duty of every health care provider, knowing of or in attendance on a case or suspected case of any of the diseases or condition listed below, to report to the local health officer for the juridiction where the patient resides. Where no health care provider is in attendance, any individual having knowledge of a person who is suspected to be suffering from one of the diseases or conditions listed below may make such a report to the local health officer for the jurisdiction where the patient resides.
- **§ 2500(c)** The administrator of each health facility, clinic, or other setting where more than one health care provider may know of a case, a suspected case or an outbreak of disease within the facility shall establish and be responsible for administrative procedures to assure that reports are made to the local officer.
- **§ 2500(a)(14)** "Health care provider" means a physician and surgeon, a veterinarian, a podiatrist, a nurse practitioner, a physician assistant, a registered nurse, a nurse midwife, a school nurse, an infection control practitioner, a medical examiner, a coroner, or a dentist.

URGENCY REPORTING REQUIREMENTS [17 CCR §2500(h)(i)]

✆ ! = Report immediately by telephone (designated by a ♦ in regulations).

† = Report immediately by telephone when two or more cases or suspected cases of foodborne disease from separate households are suspected to have the same source of illness (designated by a ● in regulations.)

FAX ✆ ✉ = Report by electronic transmission (including FAX), telephone, or mail within one working day of identification (designated by a + in regulations).

= All other diseases/conditions should be reported by electronic transmission (including FAX), telephone, or mail within seven calendar days of identification.

REPORTABLE COMMUNICABLE DISEASES §2500(j)(1)

Acquired Immune Deficiency Syndrome (AIDS) (HIV infection only: see "Human Immunodeficiency Virus")

FAX ✆ ✉ Amebiasis

Anaplasmosis/Ehrlichiosis

✆ ! Anthrax, human or animal

FAX ✆ ✉ Babesiosis

✆ ! Botulism (Infant, Foodborne, Wound, Other)

Brucellosis, animal (except infections due to *Brucella canis*)

✆ ! Brucellosis, human

FAX ✆ ✉ Campylobacteriosis

Chancroid

FAX ✆ ✉ Chickenpox (Varicella) (only hospitalizations and deaths)

Chlamydia trachomatis infections, including lymphogranuloma venereum (LGV)

✆ ! Cholera

✆ ! Ciguatera Fish Poisoning

Coccidioidomycosis

Creutzfeldt-Jakob Disease (CJD) and other Transmissible Spongiform Encephalopathies (TSE)

FAX ✆ ✉ Cryptosporidiosis

Cyclosporiasis

Cysticercosis or taeniasis

✆ ! Dengue

✆ ! Diphtheria

✆ ! Domoic Acid Poisoning (Amnesic Shellfish Poisoning)

FAX ✆ ✉ Encephalitis, Specify Etiology: Viral, Bacterial, Fungal, Parasitic

✆ ! *Escherichia coli*: shiga toxin producing (STEC) including *E. coli* O157

† FAX ✆ ✉ Foodborne Disease

Giardiasis

Gonococcal Infections

FAX ✆ ✉ *Haemophilus influenzae,* invasive disease (report an incident of less than 15 years of age)

✆ ! Hantavirus Infections

✆ ! Hemolytic Uremic Syndrome

FAX ✆ ✉ Hepatitis A, acute infection

Hepatitis B (specify acute case or chronic)

Hepatitis C (specify acute case or chronic)

Hepatitis D (Delta) (specify acute case or chronic)

Hepatitis E, acute infection

Influenza, deaths in laboratory-confirmed cases for age 0-64 years

✆ ! Influenza, novel strains (human)

Legionellosis

Leprosy (Hansen Disease)

Leptospirosis

FAX ✆ ✉ Listeriosis

Lyme Disease

FAX ✆ ✉ Malaria

✆ ! Measles (Rubeola)

FAX ✆ ✉ Meningitis, Specify Etiology: Viral, Bacterial, Fungal, Parasitic

✆ ! Meningococcal Infections

Mumps

✆ ! Paralytic Shellfish Poisoning

Pelvic Inflammatory Disease (PID)

FAX ✆ ✉ Pertussis (Whooping Cough)

✆ ! Plague, human or animal

FAX ✆ ✉ Poliovirus Infection

FAX ✆ ✉ Psittacosis

FAX ✆ ✉ Q Fever

✆ ! Rabies, human or animal

FAX ✆ ✉ Relapsing Fever

Rickettsial Diseases (non-Rocky Mountain Spotted Fever), including Typhus and Typhus-like Illnesses

Rocky Mountain Spotted Fever

Rubella (German Measles)

Rubella Syndrome, Congenital

FAX ✆ ✉ Salmonellosis (Other than Typhoid Fever)

✆ ! Scombroid Fish Poisoning

✆ ! Severe Acute Respiratory Syndrome (SARS)

✆ ! Shiga toxin (detected in feces)

FAX ✆ ✉ Shigellosis

✆ ! Smallpox (Variola)

FAX ✆ ✉ *Staphylococcus aureus* infection (only a case resulting in death or admission to an intensive care unit of a person who has not been hospitalized or had surgery, dialysis, or residency in a long-term care facility in the past year, and did not have an indwelling catheter or percutaneous medical device at the time of culture)

FAX ✆ ✉ Streptococcal Infections (Outbreaks of Any Type and Individual Cases in Food Handlers and Dairy Workers Only)

FAX ✆ ✉ Syphilis

Tetanus

Toxic Shock Syndrome

FAX ✆ ✉ Trichinosis

FAX ✆ ✉ Tuberculosis

Tularemia, animal

✆ ! Tularemia, human

FAX ✆ ✉ Typhoid Fever, Cases and Carriers

FAX ✆ ✉ *Vibrio* Infections

✆ ! Viral Hemorrhagic Fevers, human or animal (e.g., Crimean-Congo, Ebola, Lassa, and Marburg viruses)

FAX ✆ ✉ West Nile virus (WNV) Infection

✆ ! Yellow Fever

FAX ✆ ✉ Yersiniosis

✆ ! OCCURRENCE of ANY UNUSUAL DISEASE

✆ ! OUTBREAKS of ANY DISEASE (Including diseases not listed in **§ 2500**). Specifiy if institutional and/or open community.

HIV REPORTING BY HEALTH CARE PROVIDERS § 2641.5-2643.20

Human Immunodeficiency Virus (HIV) infection is reportable by traceable mail or person-to-person transfer within seven calendar days by completion of the HIV/AIDS Case Report form (CDPH 8641A) available from the local health department. For completing HIV-specific reporting requirements, see Title 17, CCR, § 2641.5-2643.20 and http://www.cdph.ca.gov/programs/aids/Pages/OAHIVReporting.aspx

REPORTABLE NONCOMMUNICABLE DISEASES AND CONDITIONS §2800–2812 and §2593(b)

Disorders Characterized by Lapses of Consciousness (§2800-2812)

Pesticide-related illness or injury (known or suspected cases)**

Cancer, including benign and borderline brain tumors (except (1) basal and squamous skin cancer unless occurring on genitalia, and (2) carcinoma in-situ and CIN III of the Cervix) (§2593)***

LOCALLY REPORTABLE DISEASES (If Applicable):

---

* This form is designed for health care providers to report those diseases mandated by Title 17, California Code of Regulations (CCR). Failure to report is a misdemeanor (Health & Safety Code §120295) and is a citable offense under the Medical Board of California Citation and Fine Program (Title 16, CCR, §1364.10 and 1364.11).

** Failure to report is a citable offense and subject to civil penalty ($250) (Health and Safety Code §105200).

*** The Confidential Physician Cancer Reporting Form may also be used. See Physician Reporting Requirements for Cancer Reporting in CA at: www.ccrcal.org.

CDPH 110a (revised 10/03/2011)

FIGURE 10.24

A list of reportable diseases for the state of California [13]. Each state will have its own list and can be found on the public health website.

or morgue staff, it is always advisable to utilize a mask, gloves, and personal protective equipment as outlined in office policy. Because microorganisms can adhere to surfaces, it is best to not place personal effects, medication vials, etc. directly on the office desk, but to contain them within plastic/paper bags. The scene response bag may need to be cleaned after being carried into this type of environment.

Fractures

Fractures commonly result from trauma, but in some instances the amount of force imposed is minimal. Either mechanism can result in a fracture that shortens a patient's life due to complications. Common complications of fractures are pneumonia, urinary tract infections, decubitus ulcers (bedsores), or sepsis (bacteria within the bloodstream). Pathological fractures result when bones involved by metastatic neoplasms have weakened the bone structure by the replacement with cancer cells. Osteoporosis is the loss of calcium and bone structure usually seen in older females. The bones weaken to the point that the body weight itself may cause compression fractures especially of the vertebra. Hip or arm fractures may also result from either type of pathology. Fractures in these underlying diseases may result from suddenly sitting, turning in bed, etc., and are not ruled accidental in origin rather usually certified as a natural manner of death.

Environmental

Environmental deaths are largely based on scene photographs, scene investigation, and the lack of an anatomical cause of death. There may be contributing information obtained from toxicology that places the person at risk within the environment, such as acute alcohol or drug intoxication.

Disorders of body temperature

Normal body temperature is 95–100 °F (~35–38 °C) measured via a core body temperature (rectal). Normal body temperature is needed for cell functions and metabolism to proceed at a normal rate. If the core (internal) body temperature decreases, cell functions slow, and eventually deplete their oxygen storage and restoration capabilities. Lowering body temperature during transplantation and cardiac surgery is used therapeutically to decrease the rate of metabolism and cell processes.

HYPOTHERMIA

Hypothermia is defined as a core body temperature below 95 °F or 35 °C [15]. Prolonged exposure to cold will be lethal and is commonly seen in alcoholics in snowy environments. The rate this occurs depends on the environmental temperature including the wind chill factor, degree of skin exposure, body habitus, and the presence of clothing. If the body or clothing is wet, the rate heat evaporates from the skin will increase, lowering core temperature more rapidly. The very young, the elderly, and thin individuals usually have less body mass and fat, and are more susceptible to environmental temperatures. Symptoms of hypothermia include confusion and disorientation, which can be compounded by alcohol and drug use. As the hypothermic state continues, the person experiences a period of vasodilation and flushing, causing him or her to shed clothing even though he or she may be extremely hypothermic. This is referred to as paradoxical undressing, meaning a person undresses when he or she should be putting more clothing on. Cases of acutely intoxicated individuals being found in the snow at the bottom of the steps to their residence are not uncommon. There may be a surrounding trail of their possessions as they made their way to shelter. The degree of intoxication may be a moderate level of 0.2 to 0.3 mg/dl, which is not uncommonly seen in chronic alcoholics.

It should also be noted that resuscitative attempts of individuals, especially the young, found in extremely cold water may result in successful return to consciousness with few long-term complications. This is because the sudden drop in body temperature is similar to those simulated in the hospital environment during surgery. Children have been known to survive being submerged in icy waters up to 20 minutes.

Frostbite is freezing of the skin, which occurs at −40°F [7]. Skin exposed to temperatures or wind chill at this temperature is subject to freezing within a few minutes depending on circulation, dampness, and clothing factors. The nose, cheeks, fingers, and toes are most prone. Symptoms include tingling, numbness, and paleness, followed by redness and blistering. The final stage is permanent skin damage and necrosis, which appears red-black in prone areas (the person has to live for it to become apparent). Frostbite is an initial symptom of extreme cold exposure that will progress to death if shelter is not sought immediately.

Autopsy findings in hypothermia are minimal and not diagnostic. Usually it is determined by the absence of trauma, such as a body found frozen or extremely cold in a cold environment. Peculiar brown hemorrhagic spotlike hemorrhages can be seen in the gastric mucosa and are called Wischnewski ulcers, but are not diagnostic. Bright-red discoloration of livor is also seen in cold exposure and is commonly seen in bodies stored in refrigeration overnight. Areas lying in contact with the snow or ground may have a pinkish red discoloration or yellow parchment skin slippage.

Investigative materials needed to make the diagnosis are weather and wind chill readings from the time of the decedent's exposure. If the person was inside the residence, notations of the thermostat reading and functionality of the heat and power sources are factors that need to be documented. Observations of food frozen on the counter or frozen pipes are also good to note and photograph. If the death occurred in a vehicle, the presence of gas and notation of the ignition are important findings. In the far north, some persons rely totally on wood heat so these findings may not be totally indicative of the cause of death but secondary to another cause of death. In those cases, carbon monoxide poisoning should be considered in the differential of a person with bright-red livor and found frozen inside the residence or vehicle.

HYPERTHERMIA

Hyperthermia is defined as a core body temperature above 100°F (~38–40 °C) [14]. Fever is also defined as a temperature greater than 100°F but the mechanism creating a fever is internal derangement of the fever center by bacterial toxins, viruses, or other pyrogens that reset the body thermostat to a higher level. Hyperthermia is caused by environmental temperatures causing the body heat regulation system to be unable to compensate and the normal heat loss mechanisms are exceeded causing the internal body temperature to rise. This results in increasing cell metabolism that adds to body heat production, depleting reserves, and finally succumbing to cell death.

Heat-related illnesses fall into a continuum to death by hyperthermia if not remedied. This continuum includes heat cramps, heat exhaustion, and heat stroke. Heat cramps are the mildest and are symptoms of muscle cramps due to lack of salt and water. If there is continued exposure to heat with no replacement of salt and water, it will progress to heat exhaustion with symptoms of headache, nausea, weakness, and pale moist skin. If not treated with fluids, it will progress to heat stroke, which includes absence of sweating, hot skin, and elevated body temperature. Heat stroke can be fatal. Due to the inability to establish physical symptoms except elevated body temperature at death, these deaths are included in the general category of hyperthermia.

Autopsy findings of individuals exposed to extreme heat generally show advanced decomposition. There are no specific findings associated with hyperthermia. The autopsy is done to document the extent of underlying pathology to rule out a cause of death that occurred with secondary decomposition versus death due to environmental heat exposure. Decomposed bodies also present challenges in obtaining toxicology, including vitreous. If vitreous is available, a sodium, creatinine, and urea can be done by the laboratory to evaluate the degree of dehydration, which would contribute findings to the diagnosis of hyperthermia.

Investigative documentation of the house and body temperature can also be helpful. Infrared thermometers can be extremely useful to assist with this. Many times first responders open the doors and windows of closed environments and this distorts air temperature readings. Infrared readings of the walls, floor, or area under the body can be done with this equipment. They can be obtained from local hardware stores relatively inexpensively. The position of the body needs to be photographed, as well as cooling mechanisms such as fans and air conditioners and power to them. If the power was discontinued, it is important to note the date that was done, and by whom, as it may prove to be a civil liability. Examination of the refrigerator food contents with their expiration dates may give an indication of the postmortem interval. In some cases of recluses or lack of family, there can be a long interval between the time of death and the decedent's discovery. Again, weather conditions are easily researched from the Internet and form an important part of the investigative report in hyperthermic deaths.

The cause of death in temperature-related deaths is usually accidental. Occasionally they are natural deaths with the heat as a contributing factor. The degree of this interaction between natural and accidental is a difficult assessment and largely rests with the pathologist weighing the degree of natural disease against the environmental exposure. Toxicology can play an extremely important role in making the diagnosis both from knowing the alcohol and drug levels to the degree of dehydration.

Tricyclic antidepressants affect the thermoregulatory center of the brain and persons taking these medications are at increased risk for hyperthermia. Illicit drugs that increase the body metabolism, such as amphetamines and cocaine, also pose an increased risk [8].

Malignant hyperthermia is a rare condition where a patient under or shortly after anesthesia experiences a sudden increase in body temperature that may be fatal if not treated promptly. It has genetic predisposition and occurs in response to halothane or succinylcholine used during surgery. In some states this may become a death investigation case falling under the auspice of sudden death under anesthesia or surgery. It is important to obtain anesthesia, surgical, and nursing notes from the period around the incident and during surgery. An autopsy will show a dry surgical site and knowledge of the notes will describe the course of events. There is a genetic and muscle biopsy test available to make the diagnosis in other family members to prevent a fatal outcome for them, and this should prompt the investigator to encourage them to seek genetic counseling [1].

WORKPLACE CAUSES OF DEATH

Workplace injuries are common and range from moving vehicle or equipment injuries to fires and electrical injuries (Figure 10.25). Approaching a scene in a work environment requires the investigator to be vigilant to hazards toward him- or herself and other rescue workers. It is important to prevent further injuries to other workers as they return to work, or even to the public. Puncture-proof shoes or boots and use of safety equipment in hardhat areas are important to prevent self-injury. Situational awareness as the investigator approaches the decedent cannot be overstressed.

Electrocution can be a subtle finding that is easily missed depending on the voltage of the electrical line. In high voltage, the damage can be quite dramatic and approach that of lightning injuries. Workers on high-voltage power lines can actually have their clothes charred or thrown off the body. A hot power line can be a hazard to approaching rescue workers and the death investigator. Depending on the voltage, the current can arc to nearby objects. Downed power lines can also occur during motor vehicle accidents, which in the dark are difficult to see.

If the decedent was in the process of using power tools in the area of power lines, electrical boxes, or in a shop, or near a pool of water with electricity, then electrocution should be considered. Signs of potential electrocution include



FIGURE 10.25
The clothing received from a worker who died on duty. It is important to note serial numbers and photograph safety equipment from multiple angles to document their integrity or sites where they may have failed.

burned clothing; subtle findings of raised, chalky, slightly burned callous areas of the hands or feet; or no findings if the person was in a pool of water. Small burn areas may be located on clothes, hands, or the soles of the shoes or boots. Typically, the electrical charge enters the hands, travels across the torso, and exits the feet where the person was grounded (Figure 10.26). It is the transfer of the charge across the heart that results in a lethal cardiac arrhythmia and death.

Understanding electrocution injuries requires some basic knowledge of electricity and flow of current. Electricity is the flow of charged particles usually from a positively charged source to a negatively charged one. Current applies this principle to the flow of the particles along a conductive material like a wire and the intensity is measured in amperage. There are two kinds of current—direct current (DC) and alternating current (AC)—that refers to how current is flowing over time. Direct current is one where the flow is constant over time in one direction with a classic example of a battery providing power to a car or flashlight. Alternating current is one where the flow waxes and wanes over time much like a wave in the ocean and is the common type seen in house current. Amperage is the amount of current flow and is the most important factor in electrocutions.



FIGURE 10.26
(A) The pathway electricity follows through a body if the line is touched by a hand. (B) An electrical burn. Clues that the death may be electrically related are downed power lines, extension cords especially near water, open power boxes, or recent electrical work done on a residence. Examination may show burns on the hands or gloves from the wires (C) and exit burns on the soles of the shoes (D).

Voltage is the measure of the force of the current. The third factor involved is the amount of resistance to the conduction of the electricity.

The skin has the greatest resistance to the flow of current in a body. If the skin is dry it has a high degree of resistance. However, if the skin is wet the current flows easily. The ability of current to pass through the remainder of the body is related to our high content of water. It tends to flow from the point of contact with the wire through the body and exit where the body touches the ground. Generally, it follows the most efficient and shortest path. This is the reason high-voltage workers can work on power lines. There is no risk of electrocution if they are not grounded. However, if a malfunction occurs and they suddenly are grounded through their bucket, then electrocution will occur.

Low-amperage wounds (i.e., less than 1 A) crossing the path of the heart cause death by ventricular fibrillation, which leaves no anatomic finding when viewed during autopsy. The only sign may be the small burns from arcing of the wire at the entrance or the charred burn at the exit wound. Higher-amperage wounds (i.e., greater than 1 A) can cause death via the burns themselves in addition to the fibrillation.

Lightning

Lightning deaths occur in persons working or doing recreational activities outdoors. Being located near electrical lines or water is a risk factor for a strike to occur. The strike usually occurs onto an object extending into the air and is transmitted onto the person nearby. Fishing poles, flag poles, metal buildings, etc. are all subject to strikes. The injuries are very similar to high-voltage electrical injuries with clothes burning and being ripped from the body (Figure 10.27). Death is from cardiac and respiratory arrest due to sudden depolarization of the heart by the current from the lightning bolt. When in a thunderstorm, the most secure place to seek shelter is inside a vehicle because it is grounded and will protect those inside from arcing [9].



FIGURE 10.27
Lightning injury. The pink arborization is a classic lightning injury, sometimes referred to as a Lichtenberg figure. (Used with permission from Dr. John Hunsaker. Photo credit: Daryl Hodge.)

Burns and explosions

Fires can take many forms, from slow-burning smoldering ones with extensive smoke, to sudden explosions. Either form can be lethal. With a higher concentration of oxygen, the fire burns more efficiently, creating more heat. In a closed environment such as a building, the fire consumes the internal oxygen and produces a rising level of noxious gases, largely carbon monoxide. Contents may also be burning and plastics, foam, other synthetic fabrics, and rubber produce cyanide as a by-product, which can also build up and be inhaled. Cyanide can be more lethal than carbon monoxide [2,3,4]. Sudden explosive fires, such as exploding gas tanks on vehicles that result in a compartment fire, occur so suddenly that death results from inhalation of superheated gases rather than living for a period of time and inhaling the carbon monoxide or the cyanide by-products (Figure 10.28).

Blunt force and crushing injuries

These are the most common injuries encountered in the workplace. They can occur from falls from a height, entanglement of clothing in rollers and belts, objects swinging or falling on the worker, or being run over or crushed by moving machinery. The injuries are similar and described like motor vehicle injuries with



FIGURE 10.28
Soot in the trachea and lower airway due to smoke inhalation. Carbon monoxide or cyanide from the burning materials are usually greatly elevated and may cause the muscle, blood, and livor to appear unusually bright red.

contusions, abrasions, and lacerations being the key terms. The worksite safety officer and Occupational Safety and Health Agency (OSHA) need to be notified of any workplace fatalities so they may conduct an investigation to prevent further injuries to other workers. They can provide investigative data regarding faulty electrical materials and dysfunction of safety equipment or machinery.

It is important to photograph the presence of the body as it was found, if possible, and any suspected items that might have caused the injuries. If the injuries are patterned and a suspected area of the tool or machinery is suspected of causing it, photographic documentation is important, if not a hazard to the investigator. Particular attention is needed for tread marks, and presence of safety equipment including boots, gloves, helmets, and coveralls. Any harnesses or other items that may have safety issues also need to be photographed on and off the body. OSHA may wish to obtain these items for further inspection and a transfer with a chain of custody will be needed.

Autopsy photographs need to include overall, medium, and close-up views of any patterned injuries with and without scales. Toxicology is important to evaluate impairment as a contributing factor for the injury to occur. Sedatives, alcohol, or drug use can impair reaction time as well as attentiveness to detail.

Cave-ins can be hazardous to an investigator and the presence of trained rescue response workers can assist with the body recovery and photography if needed. It is important to be aware of the worksite hazards and follow experts' direction at the site while still preserving and documenting the evidence if possible.

Because worksites can be a location of homicides, inflicted blunt-force injuries should always be considered while evaluating the scene. Blunt objects lying nearby should be observed for blood and tissue. The injuries on the body should be consistent with the degree of suspected force that created them. An example is a body thought to be a fall to the floor from standing height should not have crushing head injuries, unless some object inflicted them. It could be an object on a chain or an object impacted on the head by a person. It is very difficult to determine if someone was pushed off a building versus falling, but careful scene documentation, including measurements from the edge of the building and estimates of the height of the fall, will be helpful if further investigation of that scenario is warranted by witness statements. These types of measurements can be obtained by new electronic instruments used by law enforcement, construction personnel, or even surveyors. Handheld models can be purchased and are something to keep on the wish list for documentation of these scenes, as well as traffic accidents, mass fatalities, and train deaths.

DRUG AND ALCOHOL CAUSES OF DEATH

Drug intoxication

Interpretation of drug levels need to take into account the underlying health of the person, the types of drugs, the values reported, the sample site the value was determined from, and the presence of underlying liver or renal disease. The values



FIGURE 10.29
(A) A small example of the pills that may be present at a scene and require the investigator to seize them as evidence. They are routinely counted and documented on a log prior to destruction. (B) The scene of an alcoholic with numerous liquor bottles, which can be stored by some in the hundreds within a residence.

can be artificially elevated by poor specimen type or storage, abnormal drug excretion, or a phenomenon called postmortem redistribution. The latter term refers to release of a drug from its site of action inside a cell of an organ back into the blood after death. Quantification is typically performed on blood and, depending on the site of collection, can be greatly altered in its value. A site where it commonly occurs is the heart, lungs, and liver. Types of drugs prone to redistribution are the antidepressants, amphetamines, and digoxin [10] (Figure 10.29). In cases of altered liver or renal disease, the patients usually must take lower dosages of medications because of their impaired metabolism and excretion. Parent and metabolic products may accumulate in the blood with the appearance of a possible suicide when the value may be related to an underlying natural disease process. Mental health information and family history may assist in making the distinction.

Alcohol related

Alcohol values are relatively straightforward in their determination in the laboratory via gas chromatography. In all states acute alcohol intoxication is determined at 0.08 g of alcohol/100 ml of blood or higher. The value can be artificially lowered by infusion of intravenous fluids from resuscitative efforts or passage of time. An improperly drawn specimen via a blind stick from a pleural cavity can give an artificially elevated value by contamination from the esophagus or stomach contents. To prevent misinterpretation of values, the vitreous alcohol analysis is usually performed as a parallel evaluation of the blood alcohol. The vitreous alcohol normally lags behind the blood value and is protected from dilution by intravenous fluids. It normally runs approximately 1.2 times higher than a blood alcohol, so a conversion factor is needed to convert to a blood value. How people act during acute alcohol intoxication is widely variable and can range from aggressive to passive.

A Caveat for the Medical Witness: Advice Regarding Testimony about Alcohol Intoxication

Excerpt from *The Pathology of Homicide* ***by Dr. Lester Adelson***

Given equal degrees of tolerance and health, most persons respond more or less similarly to ethanol insofar as their physical abilities and capacities are concerned. Thus, the pathologist can state authoritatively that a sufficiently elevated blood-alcohol level hampers proper muscular coordination, interferes with the ability to judge distance correctly, increases reaction time, impairs visual and auditory acuity, and leads to deterioration in insight, judgment, and critical faculties.

On the other hand, the emotional and personality responses of a specific person after he had consumed more than a “little” alcohol can be prognosticated in guarded fashion only on the basis of *repeated* previous observations of this conduct and comportment under similar conditions. Even then, one must remember that the same person *can* react differently to the same exogenous factors (i.e., amount of alcohol, type of occasion and company) as a result of differences in endogenous conditions, such as mood and emotional status.

Thus, the physician *cannot* state positively, solely on the basis of a specific blood-alcohol concentration, that the subject was mean, combative, and hostile, *or* that he was affable, pleasant, and affectionate.

Source: Adelson, L. (1974). *The Pathology of Homicide*. Springfield, IL: Charles C. Thomas, p. 896 [11].

Other alcohols may be identified while searching for ethanol, the common alcohol found in beer, wine, and other liquor. Methanol is a solvent and sometimes used as a pesticide that can be ingested. It is fatal in small volumes and can be detected during an alcohol screen. It may also be an ingredient in embalming fluids, which can contaminate vitreous fluid determinations.

Ethylene glycol is a sweet-tasting liquid forming a large component of antifreeze. If ingested, it can give feelings of euphoria similar to ethanol intoxication but can be lethal if ingested in a quantity of at least 3–4 oz. It may be seen as an accidental poisoning in alcoholics or as a means of homicidal or suicidal poisoning.

Isopropyl alcohol, commonly known as rubbing alcohol, may also be lethal if ingested in large quantities and will give symptoms of inebriation as well as potential coma. It is not as lethal as ethylene glycol or methanol. It is more commonly seen on toxicology lab reports in conjunction with ketones consistent with a chronic alcoholic ketoacidosis picture where the body is breaking down fats and proteins because of distorted insulin use in alcoholics.

Prescription medications

Every medication is a potential poison in a large enough quantity. Over-the-counter medications are justified as such because they have a very wide margin of safety and it requires large amounts of them to become intoxicated or for lethal levels to be achieved. Prescription medications are regulated because they have lower margins of safety and, to prevent access, they require a doctor's prescription to obtain them. Which category a medication is placed into is determined by premarketing testing used by the Food and Drug Administration (FDA).

The Drug Enforcement Agency (DEA) classifies all narcotics and determines their level of safety and regulates physicians who prescribe them. Narcotic prescriptions require a DEA number issued to a physician for it to be filled by a pharmacy. The number allows the DEA to monitor physician prescription practices.

Individual pharmacies or even pharmacy chains can provide lists of prescribed medications for a patient that were filled at their establishment and will include the name of the drug, date filled, amount, and prescribing physician. This information can be helpful in sorting out manner and for locating medical records.

Some of the common drugs encountered that are commonly lethal are cardiac medications, antidepressants, pain medications, and antipsychotics. These classes of drugs cause death by inhibiting respiration or disrupting cardiac activity. Combining these drugs can have additive effects that can be further accentuated by the addition of alcohol or illicit drug use. Each drug may be in a therapeutic or sublethal range, but when in combination, they may cause death. In many cases of drug intoxication they become another class of deaths where the diagnosis is one of exclusion. Scene findings of open pill containers, spilled pills, and mental history can all play a part in sorting out the many factors needed to determine the cause and manner. The testing laboratory usually provides some direction as to interpretation of the reported value. There are also multiple resources available in a toxicology text for interpretation of data for individual postmortem drug levels.

Illicit drug use

Illegal drug use has multiple complications including the social issues of addiction, which can lead to criminal activity or impaired judgment, placing the person at risk for homicides or accidental causes of death. Other risks include natural diseases such as hepatitis or bacterial endocarditis from injections, or talc lung from injecting drugs "cut" with talc as part of the processing. Drug use also poses risks to fetuses and children.

COCAINE

Cocaine is a derivative of coca leaves, a plant that is native to South America, then imported via drug traffickers. It comes in two forms: a powder that can be inhaled or injected, or a rock called "crack" that can be smoked. Its physiologic effects on the body are increased blood pressure and heart rate due to its properties of vasoconstriction. It may cause periods of paranoid psychoses or delirium that are not necessarily associated with a particular drug level. It can precipitate cardiac arrest, especially in those with underlying cardiac disease and intracranial hemorrhage, due to its vasoconstrictive properties.

OPIUM

Opium is derived from the opium poppy that is native to many parts of the world, as well as being able to be grown in the United States. It is harvested from the pod that forms after the petals have fallen away. The internal sap of the pod is collected and dried. This sap is the precursor to heroin, morphine, codeine, and oxycodone. It has legal medicinal uses, as well as being available via the black market in any of these forms. Heroin is available as a brown or white powder that can be smoked or inhaled or injected, known as mainlining, which is the most potent method of use. In this form it can also be found as impure black tar, which is a black rock material that is melted and injected. Morphine is the derivative form detected in the laboratory and is the same compound detected if it originates from a hospital source. The illicit form may contain detectable by-products that were used to cut the heroin or contain a metabolic form called acetylmorphine. Codeine and oxycodone are common prescription medications that patients can become addicted to. Combined use with alcohol or over use with other prescription medications can be lethal.

Methadone is a synthetic opioid used to treat opiate-addicted patients because of its long duration of action. It is synthesized in medical pharmacy laboratories for prescription use for detoxification and slow withdrawal of narcotics to relieve patient symptoms of withdrawal. It can be given in oral form or injected, and usually requires the patient to receive his or her dose at intervals from a methadone clinic. It has pain-relieving benefits similar to morphine and can be used for chronic pain relief as well. It too can be abused, and if prescribed in oral form, can be overingested, leading to overdose.

METHAMPHETAMINE

Methamphetamine (meth) is a manufactured material in homegrown labs. These labs pose a particular hazard to the investigator and the community. They contain multiple volatile, explosive, and corrosive hazards with harmful by-products. Full protective equipment use, including an air pack, will be necessary to investigate these scenes. Hazmat units usually survey the scene and make it safe of explosives prior to the investigator being admitted. The body may have hazardous chemicals on the skin requiring multiple body bags and the use of a chemical-resistant outer layer. Heavy-duty chemical-resistant gloves may be necessary to handle the decedent and any evidence that needs to be removed. The Environmental Protection Agency (EPA) has published a manual on cleanup and handling of contaminated scenes within a meth lab [5].

Because of these toxic issues, children raised in these environments and suddenly found unresponsive or deceased need to be evaluated for ingestion or inhalation of these toxic chemicals.

The National Alliance for Drug Endangered Children has authored a flow diagram of medical evaluation of children exposed to a drug lab environment, as well as their symptoms, which would prove useful in evaluating a decedent within the same environment [6].

DESIGNER DRUGS

New drugs are being synthesized continuously and, because of the way they are manufactured, are able to stay ahead of laws and enforceability by law enforcement. One example is bath salts, a designer drug derived from a plant, Catha edulis, grown in Africa and the Arabian Peninsula where it is known as khat. The plant derivatives are modified chemically to form synthetic cathinones. These will be seen in a toxicology screen as MDPV, mephedrone, and methylone, but are not routinely detected on testing and must be requested from referral labs. They have stimulant properties similar to cocaine and amphetamines but include hallucinations and cravings similar to LSD. Deaths have been linked to its use via repeated highs, cutting, paranoia, and leaping off buildings. It affects the brain's neurotransmitters and stimulates the cardiovascular system, causing sudden death from cardiac arrest or edema within the brain. The term bath salts has no relationship to how this drug is produced, but packaging is marked with that label to avoid detection by law enforcement. It is also known as insect repellant and plant food and the package marked "not suitable for consumption." It is relatively cheap and used via smoking, injecting, or snorting, and comes in powder, pill, or tablet form.

Synthetic marijuana is marketed in foil packages marked "Spice," "Incense," or "Puff Puff." It is derived from herbs and sprayed with chemicals to mimic the active ingredients in marijuana. Since it does not have the compounds found in cannabis, it will not give a positive drug screen for THC, the active component. The effects are similar to cannabis but include paranoia that may be long lasting or even precipitate a psychotic breakdown and death. Drug screens for synthetic cannabis are difficult because manufacturers change the chemical structure to avoid law enforcement detection. The testing targets the synthetic cannabinoid structure used in the manufacture of the chemicals but must be specifically requested from a reference laboratory.

Basic principles of toxicology testing

ELECTROLYTES

Electrolytes on decedents usually include testing for sodium, chloride, creatinine, urea, and glucose. In the living, these tests can be done on the blood. However, with death, the mechanisms that keep these items in balance inside and out of the cell are disrupted and the blood testing results in artificially elevated or distorted results if tested. The best example is potassium levels. In the living, this value is tightly regulated by the body to a normal range of 3.5–5 mEq/L circulating in the blood but is much higher inside the body's cells. With death, the cell membrane is no longer regulated and the high content inside the cell diffuses out into the blood, causing blood values to increase to values that, if interpreted, would be lethal.

The other elements noted above have similar issues with their pre- and postmortem values if performed on blood specimens. For this reason, vitreous (fluid removed from the eye) is the specimen of choice. This specimen has a lower cell concentration and is not subjected to these same rapid changes seen within blood specimens. Even so, the potassium will slowly rise and bacteria within the fluid will slowly lower the glucose value. The sodium, urea, and creatinine will remain relatively steady and be used to assess for dehydration. Extremely elevated glucose values seen with diabetics in lethal ketoacidosis will lower but remain higher than normal for the postmortem interval. For a quick bedside interpretation, a diabetic glucometer can be used for a quantified estimate of the glucose value in the vitreous and can be done quickly upon admission to the morgue. In the same fashion, a dipstick of the diabetic urine can reveal the presence of ketones.

ENZYME-LINKED IMMUNABSORBENT ASSAY (ELISA)

This method utilizes antibodies that produce a color change to determine the presence of a substance and a positive result. Urine drug screening by this methodology is cost effective and useful for presumptive identification of drugs or their by-products. It utilizes antibodies similar to the ones we have in our blood to fight infection. These molecules have particular chemical structures much like a jigsaw puzzle piece. The drug for which it is a match will fit directly into the piece exactly, and after doing so, will emit a change of color at a particular wavelength that can be detected by the instrument. This is an inexpensive and rapid method to screen for particular broad classes of drugs and the test is considered a qualitative test. To confirm the identity and quantify the amount of the drug, further testing can then be done by more sophisticated instrumentation. If the screen is negative, further time-consuming testing can be avoided. A positive result in this method must be confirmed by another methodology because the antibody match is not specific. In some cases, the antibody puzzle piece can fit in a similar drug antigen piece, not exactly, but enough so that the emission of light can occur and turn the result positive when it is actually negative. This is called cross-reactivity. These cross-reactive antigens create a false-positive result. All laboratory tests have an innate level of false-positive and false-negative results attached to them. The key to a good analysis method is to minimize both, and yet gather the true positives in the largest percentage. For these reasons, most laboratories confirm positive test results and quantify the amount via gas chromatography–mass spectrometry. See Figure 10.30 for examples.

GAS CHROMATOGRAPHY–MASS SPECTROMETRY (GC-MS) OR LIQUID CHROMATOGRAPHY–MASS SPECTROMETRY

These two methods are used by most laboratories to confirm the identification of a drug or substance by its chemical structure (Figure 10.31). The testing is performed by comparing the multiple chemical structures in a specimen to a library of known structures and the instrument is able to give an accurate quantification. Specimens are usually performed in duplicate to confirm values before reporting a result. Major law decisions may be made by these test results, and the values need to have the best validity and reproducibility as possible by the laboratory.



```
Quality        : 99
ID             : COCAINE
```

A

FIGURE 10.30
(A) Sample results of a specimen submitted for confirmation of a drug screen. Here you see the instrument emission pattern of the unknown (the top pattern) matches the library pattern of cocaine (seen in the lower pattern).



FIGURE 10.30, cont'd
(B, C) Specimens submitted for volatiles. The patterns match those of the library patterns of gasoline and diesel. This information can be useful in arson determinations and is done on the air that accumulates the fumes within an airtight container (called headspace analysis). Clothing or other items to be submitted for this testing are usually placed in new paint cans and sealed. The air is extracted through a pinhole made in the lid and injected into the instrument.
Courtesy of Dr. Craig Chatterton



FIGURE 10.31
(A) Gas chromatography–mass spectrophotometer. (B) Liquid chromatography–mass spectrophotometer. Both instruments are used in toxicology testing.

REFERENCES

[1] Metterlein T, et al. In-vitro Contracture Testing for Susceptibility to Malignant Hyperthermia: Can Halothane be Replaced? Eur J Anaesthesiol 2011;28(4):251–5. doi:10.1097/EJA.0b013e32833ed06c. Retrieved from http://www.ncbi.nlm.nih.gov/pubmed/20827211, http://www.ncbi.nlm.nih.gov/pubmed/15114203. [August 2013].

[2] Rochford R. Hydrogen Cyanide: New Concerns for Firefighting and Medical Tactics. Fire Engineering, PBI Performance Products, Inc e-newsletter; 2009. Reviewed from http://www.fireengineering.com/articles/2009/06/hydrogen-cyanide-new-concerns-for-firefighting-and-medical-tactics.html. [August 2013].

[3] Cyanide Compounds. Technology Transfer Network - Air Toxics Web site. 74-90-8, United State Environmental Protection Agency; 2009. Reviewed, from http://www.epa.gov/ttnatw01/hlthef/cyanide.html. [August 2013].

[4] An introduction to Indoor Air Quality (IAQ): Carbon Monoxide (CO). Environmental Protection Agency; 2013. Reviewed from http://www.epa.gov/iaq/co.html. [August 2013].

[5] Environmental Protection Agency. Guidelines for methamphetamine lab cleanup. Retrieved from http://www.epa.gov/osweroe1/meth_lab_guidelines.pdf.

[6] National Guidelines for Medical Evaluation of Children Found in Drug Labs. National Alliance for Drug Endangered Children; 2013. Reviewed from http://www.nationaldec.org/user_files/18918.pdf. [August 2013].

[7] Thurlow D. The Weather Notebook, 40 Below; 2001. Reviewed from http://www.weathernotebook.org/transcripts/2001/02/07.html. [August 2013].

[8] Rampulla J. Hyperthermia & Heat Stroke: Heat-Related Conditions. Healthcare of Homeless Persons; 2012. Reviewed from http://www.nhchc.org/wp-content/uploads/2012/02/Hyperthermia.pdf. [August 2013].

[9] Cooper M. Lightning Injuries. Medscape Reference; 2012. Reviewed from http://emedicine.medscape.com/article/770642-overview#aw2aab6b2b2. [August 2013].

[10] Yarema MC, Becker CE. Key Concepts in Postmortem Drug Redistribution. Clin Toxicol (Phila) 2005;43(4):235–41. Reviewed from http://www.ncbi.nlm.nih.gov/pubmed/16035199. [August 2013].

[11] Adelson L. The Pathology of Homicide. Springfield, IL: Charles C. Thomas; 1974.

[12] Heart and Vascular Diseases Health Topics. National Institute of Health: National Heart, Lung and Blood Institute; 2013. Reviewed from http://www.nhlbi.nih.gov. [August 2013].

[13] Reportable Infectious Diseases for California. California Department of Public Health; 2011. Retrieved from http://www.cdph.ca.gov/HealthInfo/Documents/Reportable_Diseases_Conditions.pdf. [August 2013].

[14] Bouchama A, Knochel J. Heat Stroke (Review article). N Engl J Med 2002;346:1978–88. doi:10.1056/NEJMra011089. Reviewed from http://www.nejm.org/doi/full/10.1056/NEJMra011089. [August 2013].

[15] Brown D, et al. Accidental Hypothermia (Review article). N Engl J Med 2012;367:1930–8. doi:10.1056/NEJMra1114208. Reviewed from http://www.nejm.org/doi/full/10.1056/NEJMra1114208. [October 2013].

CHAPTER 11

Sudden Death in Children

Learning Objectives

- A baby with no external evidence of trauma is dead in a local hospital emergency department. You, as the investigator, respond to the hospital to examine the child and meet with the family. Outline three common questions you would expect the family to ask and potential answers to those questions.
- Outline at least five specific materials the pathologist may need to complete a baby autopsy.
- A call comes to the office that a baby is dead at home in a very remote location from the office. An officer is on the line asking for help to photograph the decedent in the residence. Outline at least five key photographs that will be essential for him or her to take and forward to the office.
- A doctor is calling to report the death of a baby in the operating room for surgical correction of transposition of the great vessels. You, as the investigator, take the call and need to determine if the case falls under the jurisdiction of the office. Outline three key questions you will need to ask to make that determination.

Key Terms

Babygram
Co-sleeping
Skeletal survey
Cyanotic
Meconium
Hematoidin
Fetus
Neonate
Infant

Chapter Summary

This chapter discusses the various common natural diseases causing deaths in infants and children, as well as nonaccidental trauma and specific issues related to fetal deaths. Autopsy procedures for children are usually modified to answer specific questions to determine cause and manner of death. Investigations require attention to detail to assist the pathologist to make the best determination.

INTRODUCTION

Sudden death in children requires methodical observation, photographs, and systematic questioning of the caretaker(s) to establish the series of events that led to the child's death. Subtle findings can be the key to the determination of the cause and manner of death (Figure 11.1). The process to determine a cause



FIGURE 11.1
Depicts how each level of information is needed to determine the cause and manner of death.

of death is a multistep approach in gathering the necessary information for the pathologist to come to the best conclusion.

INVESTIGATION TECHNIQUES

Depending on the scenario, many times the child has been removed from the site of death during resuscitative efforts, and will be pronounced dead at a hospital. The hospital generally notifies law enforcement, but if they have not done so, it should be done. The local agency will have resources available to check for previous involvement at the residence by law enforcement and child protective services (CPS). Also, entry into a residence by death investigator personnel may not be possible without a search warrant or advisable without law enforcement participation, especially in cases of suspected inflicted injuries.

Each state has an infant death protocol checklist that needs to be completed. The Appendix has examples of the death investigation checklists from Arizona and California. These checklists allow uniform information documentation to ensure that all aspects of the investigation are reviewed with the caretakers. It begins with the usual demographics of the family, caretakers, and child, including dates of birth, addresses, and occupations. It is important to establish the time the child was found and time he or she was last noted to be alive and to determine what occurred in between. The interview covers feeding habits including types of formula, how it is mixed, solid foods, and when the child last ate; recent illnesses; birth history; past medical history including immunizations; doctor, urgent care, and hospital visits; illnesses in the residence; sleep habits; observation of the sleep environment; and where the child was found unresponsive.

Examination of the crib should begin with photographing it as it is first observed followed by examining the underlying layers of bedding. Toys or other objects in the crib should be examined for possible leakage of stuffing contents. Details of small or soft foreign objects within the crib should be noted. Thermostat settings



FIGURE 11.2
Examples of scene reenactment where a doll is used to recreate the course of events immediately before and after the child was found unresponsive. It may generate useful information concerning the airway or position within the sleep environment that cannot be discovered at autopsy.

in the house, as well as the location the child was found, also are noted. Particular questioning should be centered to the time period when the child was last seen alive and details regarding how, where, why, and by whom he or she was found.

Near the conclusion of the interview, it is recommended that a scene reenactment be performed if the family is willing to participate (Figure 11.2). This process involves using a small doll or even a stuffed animal that may be present at the scene. The caretaker who placed the **infant** in its sleep environment repositions the doll in that position with attention to detail for location of the arms, airway, and face up, face down, or on his or her side. The caretaker who found the infant then positions the infant how he or she was found with similar documentation. Photographs are taken during each stage of the reenactment for review by the pathologist. Notation is made of emesis or other food material in the sleep environment. An investigator should also document the softness of the surface the child was resting against. Children can typically raise their head at two months old and roll over at approximately four months, sit at six months, crawl at nine months, and walk at one year. Prior to four months, they may not be able to maintain a clear airway from fluffy or pillow-type surfaces that can partially obscure their airway. The ability to raise the head at two months may allow them to reposition but not maintain the airway for a prolonged period. The fluffy surface may also bunch around the airway, obscuring it. These milestones are approximations, and if a child is born prematurely or has a developmental disorder, he or she will be delayed in acquiring them.

In some instances, the caretakers will report the infant was **co-sleeping** with adults and/or other children. The same type of information needs to be documented as to last known positions of the parties while the child was alive, followed by the position he or she was found. Risk factors for co-sleeping include obesity (breasts obscuring the airway of the infant breast feeding); drug or alcohol use, which may further hamper the caretaker's awareness of the surroundings or deepen his or her sleep; and multiple people in the bed.

AUTOPSY PROCEDURE

Many times only preliminary information is available to the pathologist at the time of autopsy. The initial scene information just described may be only partially completed. It may take time to contact the treating pediatrician or obtain hospital records. For this reason, the autopsy examination is more extensive than for adults.

The usual procedure is to perform a total body X-ray (**babygram**), including anterior and lateral views of the head, and at a minimum screening X-rays of the extremities and ribs (Figure 11.3). Any questionable areas may need coned-down views to better visualize the contours of the bones and joints looking for subtle or healing fractures. All fractures are of concern, especially if they were not previously documented by hospital personnel. Fractures are evaluated by the extent and location, as well as the caretaker's explanation of how they happened. Mismatches are clues that further investigation is needed. This may require high-resolution X-rays and evaluation by pediatric radiologists, which may only be available at a hospital



FIGURE 11.3
Typical babygram X-rays that are done during the course of an infant death investigation. They assist with screening for acute and healing skeletal fractures. If the child was evaluated at the hospital, the technology is of higher quality and the results reviewed by a radiologist. Evaulation of those studies may also prove useful.

radiology department. Findings of acute fractures are seen as small chips off corners of joints or as curved lines through the skull, or long bones of the upper or lower extremities. Healing fractures appear as raised irregular areas along the margins of the normal bones and need to be differentiated from a tumor. Findings on MRI scans include blood within the cranial cavity or evidence of swelling. Hospitals also have the ability to perform **skeletal surveys** where the body of a child can be screened for both acute and healing injuries and the X-rays read by the radiologist. These are extremely helpful in aiding the distinction between accidental and nonaccidental trauma. Reports of all the X-rays are important for the pathologist to have available for review, including copies of the hospital X-rays.

The external examination, X-rays, and scene information will direct the pathologist as to what needs to be done next. Overall photographs, including the usual medium and close-up photos with and without a scale, of any injuries are documented. It is important to photographically document the child with all medical treatment in place so any artifacts can later be explained if needed. External examination also needs to include an accurate weight after all medical appliances are removed. Body length is confirmed. Other measurements taken include head, chest, and abdominal circumferences, and crown (top of head) to rump (to base of buttocks fold) length. Circumferences are best done with a flexible tape measure without stretch. A head circumference is measured around the head like a hatband at the mid-forehead encircling the widest part of the back of the head. Chest circumference is measured around the chest at the nipples level. Abdominal circumference is measured around the abdomen at the navel level. Crown to rump length is done from the top of the level head to the bottom crease of the buttocks. Crown to heel length is done from the top of the level head to the sole of a foot without crossing over the torso. All are recorded in inches or centimeters, whichever is standard protocol of the office. (Photographic descriptions of baby measurements can be found in the Appendix.)

If the child's death appears accidental (e.g., motor vehicle or drowning) without suspected inflicted trauma, a standard autopsy without special studies can be done. The purpose is solely to establish a cause of death and rule out aberrant traumatic findings that might otherwise be missed.

If the child's death appears in the range of natural or unknown death but not traumatic, it follows the state protocol and includes cultures and genetic screening, and a full autopsy including biopsies for microscopic review by the pathologist. Cultures from a pediatric autopsy include obtaining a nasopharyngeal swab culture for viral pathogens. This is done by inserting a special nylon-tipped swab in the nostril and, upon removal, placing in special red liquid media called Hank's medium (normally supplied by the public health laboratory). The vial needs to have the decedent's name, date and time collected, and identify it as a nasopharyngeal swab. A requisition form needs to accompany the specimen to the laboratory and include the demographic identification, physician and contact information, specimen type, date and time collected, and test ordered. The specimen needs to be delivered to the viral laboratory within a couple of hours after it is obtained, and definitely before the end of the workday.

Bacterial cultures include spinal fluid, blood, and lung cultures. The same procedure used for viral cultures is used to label each specimen and completion of a bacterial culture requisition form. Spinal fluid can be obtained from either of two locations. One method is via the lumbar region of the lower back where it is performed in the living. The child is positioned in a fetal position, which widens the space between vertebral bodies and assists with the passage of the needle into the space. Another method to obtain the fluid is to position the child face down with the head draped over the side of an autopsy block, which will separate the vertebral body spaces for entry of the needle. The needle is passed into the cisterna magna located at the base of the skull where it joins the spine. In either location, it is important to clean the skin thoroughly with soap to remove skin contaminants. (Special autopsy procedures relevant to infants can be found in the Appendix.)

Blood cultures are obtained from heart blood. To decrease contamination, it is best to obtain the blood from the aorta or pulmonary artery, furthest from the intestinal bacteria. Three to 10 ml of blood is placed into a transfer media bottle(s) obtained from the microbiology laboratory. The rubber stopper is covered by a plastic lid and the surface is sterile if not previously opened or handled.

Lung cultures are obtained by using a microbiology swab that has a transfer media in the tube. A slit is made in the lung tissue and the swab is placed into the slit opening then replaced into the tube for transfer to the laboratory. Some pathologists sear the surface of the lungs or the cardiac vessels prior to obtaining the lung and bacterial cultures. These surfaces are sterile unless they have been touched by gloved hands, so the searing may not be necessary if the cultures are obtained promptly upon opening the chest cavity and pericardium.

Full toxicology sampling is performed next with retrieval of blood, urine if present, and bile. The pathologist will usually retain liver and brain tissue as needed for additional submission. Genetic screening consists of a commercially available filter paper requisition, upon which small samples of blood are placed, and then air-dried before mailing back to the commercial laboratory. These screens are not as comprehensive as the initial neonatal screen, but they do check for the common diseases that can cause death after the first few days of life.

The autopsy routinely includes an evaluation of the large vessels entering and leaving the heart to establish a congenital heart defect. This is best done if the heart and lungs are removed together to confirm proper vascular connections. The remaining organs can be removed organ by organ if attention is paid to their proper anatomic relationships. Gastric contents need to be retained for possible toxicology testing. The bowel contents need to be noted.

The head is examined next with photos of any scalp injuries documented. The exterior skull is evaluated for fractures and expanded sutures. In the first two to four weeks of life the skull is extremely malleable and may be opened by cutting through the sutures and opened "eggshell fashion." After the skull is further calcified it is best to use the typical saw pattern and remove the skull cap. There should be an absence of blood over the surface or extreme swelling. It is helpful to photograph the brain prior to removal followed by the internal skull. The dura needs to be removed from the basilar skull and the cranium to verify the absence of fractures. After the brain is examined and there is an absence of blood, the vitreous fluid may be obtained for toxicology. In children this can be a very small quantity and the testing limited to sodium, creatinine, and urea (all on one panel in the laboratory), or if a higher priority is on the glucose, that can be done instead. Some pathologists retain and fix all children's brains to cut later. In this instance, a container of formalin will be needed, and each department has a procedure on how it will be suspended, cut, and for final disposition of the remains.

The neck, removal of the tongue, and evaluation of the posterior pharynx is very important to look for obstruction by objects, food, and evaluate the palate and tonsils. The airway is evaluated as well as the neck muscles to verify a lack of hemorrhage that might be present suggesting an asphyxial death.

The cavity is then dried to evaluate the inner surfaces of the ribs to look for fractures. The spine and pelvis are similarly evaluated. The spine can be removed for better evaluation of the spinal cord. This is made by making cuts through the anterior vertebral bodies in a linear fashion using the bone saw at a 45° angle to the side of the vertebral bodies. The cut is extended from the neck to the lumbar region and can be lifted off, exposing the underlying dura and spinal cord.

In nonaccidental trauma cases, the dissection becomes a bit more intense because there are questions concerning the ages of any visible injuries. Skin biopsies are taken of these areas for microscopic evaluation. If possible, the face and hands should be spared so the family may have a visitation after the autopsy. Generally, the autopsy begins with a skin dissection only and the muscle layers are left intact. This allows evaluation and documentation of any hidden injuries that might appear externally on the skin surface. This technique also can be repeated down the back and buttocks. It is especially important to perform a skin dissection if the child is dark skinned, which makes visualization of injuries more difficult than in pale-skinned children.

Other special procedures in nonaccidental trauma are the forfeiture of vitreous fluid, so the eyes are removed instead for evaluation of intraocular hemorrhage, which may be associated with head injuries among other causes. The inner ears may also be sampled looking for inner-ear infections. Any sites of rib or long-bone fractures are removed, photographed, possibly X-rayed, and sampled microscopically for dating of the fracture.

FOOD

The type of food the child last ate, the amount of formula, and the time of the last feeding are all important to the evaluation of cause of death and confirming caretaker accounts of what has transpired. This can take a critical turn if the child appears undernourished. It becomes imperative to inquire exactly how the formula was mixed, the volumes the infant was consuming, and how often the feedings were occurring, as well as any natural or solid foods that were being attempted. If the child is older, the kinds of foods he or she was served, amounts, frequency, and documentation of unusual feeding practices may be in order. Observations of other children in the household may also hold clues for the etiology of the undernourished decedent. Questioning should also center on the quantity and types of stools, how often diapers are changed, etc.

Any hospital admissions or evaluations by physicians or other healthcare workers need to be obtained for the pathologist to review. Birth records and genetic screenings need to be obtained for any congenital issues that might contribute to poor weight gain, also known as failure to thrive. A detailed growth chart is necessary to evaluate these children. Weight and height measurements can be found in emergency room records and records of visiting nurses and pediatrician offices. Growth charts depict multiple curved lines upward over time with the age of the child plotted on the x axis and the weight on the y axis. The curves are divided into percentiles ranging from 5% to 95%. These graphs normally show progressive weight gain in a curvilinear fashion falling no lower than the initial percentile curve on the graph established at birth. For example, if a premature infant's initial weight and height measurements place him at the 5% curve, his first checkup at two weeks should show growth at least at the level of the 5% curve, if not above. If it is level or dropping, feeding practices need to be explored and the child followed more closely. By plotting each of these weights over time, and including the one obtained at the time of the autopsy, it can give further indication of progression or lack of progression. If the weight varies over time with different caretakers or hospital admissions, then feeding practices by the caretaker(s) need to be questioned further. Postmortem electrolytes are also important for the evaluation of an undernourished infant or child.

FOREIGN OBJECTS

Children commonly put things in their mouths or other orifices that may obstruct the airway, create a nidus of infection, or perforate the gastrointestinal tract. An example is swallowing a toothpick that punctures the stomach or bowel causing peritonitis. Common airway obstructions are caused by coins, hot dogs, pieces of toys, candy, or items of food they are not able to reduce to a smaller bolus for swallowing. The item becomes lodged at the back of the tongue at the opening to both the trachea and the esophagus. This vulnerable location can result in the inability to swallow the item or cough and dislodge it. Coughing requires enough air behind the blockage to exhale during the cough. This is the reason a finger sweep of the mouth is used to dislodge any blockage freeing the airway. The Heimlich maneuver in adults is one where a bear hug is done to the mid-abdomen with a thrust in the upper abdomen to dislodge the obstruction. In babies, the Heimlich is performed face down supporting the head in the hand with a swift blow between the shoulder blades. Symptoms of a blockage are the inability to talk or cry with raspy breathing and a panicked look of the face.

ILLNESS

Probably the most common symptoms related by caregivers is the child was experiencing a stuffy nose, slightly decreased appetite, was fussier than usual, but sometimes they relate no change in behavior or activity. The symptoms may be mild or nonspecific and may even have been passed as teething or just the beginning of a cold. The interval between symptoms and death may be very short because children can succumb to bacterial infections and sepsis rapidly. Fever is difficult for many parents to assess and a temperature may not have been taken. If other family members have been recently ill, the probability of the death being related to an infection is much higher.

MEDICAL HISTORY

Infectious diseases are also more common in children who have not been immunized. Some families resist immunizations and relate that they feel they cause disease and death. The risk from not being immunized is much higher than the risk of being immunized, and all facets of modern medical care continue to recommend them on a scheduled basis. Immunization history and locations they were obtained should also be a part of the investigative report. It also may reflect on the parents' attentiveness to the needs of the children with routine evaluations by medical personnel. Immunizations are available free or at little cost at local health departments. County hospitals also have indigent health clinics for routine care, as well as emergency departments for sick children if finances are an issue.

Birth and prenatal history is important because it can give an indication of possible exposure in utero to toxins, drugs, or alcohol, which may affect organ formation and result in congenital anomalies, or symptoms of drug withdrawal. Alcohol use in utero can lead to fetal alcohol syndrome, a disease characterized by hyperactivity, behavior and cognitive disorders, and structural abnormalities of the heart, kidneys, and characteristic facial abnormalities. The amount of alcohol that can be ingested without injury to the **fetus** is unknown [1]. Fetuses who succumb in utero, or infants who die and the mother is found to be under the influence of drugs or alcohol, are usually reported to the coroner/medical examiner investigator. Generally, the case is accepted if the infant is of the age of viability as established by state law. It is difficult for charges to be brought about in this situation, but documentation and confirmation of the drug use can have repercussions for the care of other children living in the household and allow social services to take a more active role in the family dynamics.

Drug use in pregnancy is similar to alcohol use and is associated with cognitive, behavior, and seizure disorders, and withdrawal complications including death and structural abnormalities of organs. Death can occur in utero and lead to a miscarriage. Many times the mother presents due to lack of movement of the fetus, bleeding, or a spontaneous abortion. Drug screens are routinely checked and, if positive, law enforcement may be notified, especially if it occurs late in the pregnancy. If the child has been dead for a few days, the fetus/infant will be macerated, which is a form of decomposition. It is difficult to obtain blood in these cases to perform toxicology. **Meconium** is a great sample for testing and is nearly always available. Meconium is the thick, dark, tarry stool that a child expels in the early days of life. It accumulates in the fetal digestive tract during development through ingestion of amniotic fluid containing by-products of development and reflects the close proximity of fetal and maternal circulation intercommunication. The meconium begins forming about 12–15 weeks in the pregnancy and testing will reflect drug use through the last four to five months of the pregnancy. Head hair samples can also be evaluated and a qualitative result of positive or negative for illicit drugs can be reliably performed. In some states, law requires mandatory meconium testing on all infants. In others, it is done only if there is a positive maternal drug screen at birth or during the pregnancy.

Infants may survive pregnancy and the early newborn period but exhibit any number of symptoms, including seizures, brain disorders, and structural abnormalities of the heart or other organs, which will vary to some extent with the drug used [2]. Marijuana use during pregnancy can also result in learning disorders and behavior problems. Cigarette smoking and drug or alcohol use in pregnancy can result in a higher risk for sudden infant death. Since meconium is only present in the infant's system for the first week after being born, historical information from records will be needed. If acutely exposed to illicit or prescription medications, it will show in routine samples of blood or other tissues. Head hair can also be a useful specimen to retain as it will reflect a longer period of exposure.

Breast feeding will also transfer drugs to the infant. Nearly all drugs have the ability to be excreted into the milk and may exhibit symptoms in the infant. Drugs such as methadone will cross into the milk but may also have some calming effects on an opioid-addicted infant as well as to prevent withdrawal. The problem occurs if the amount in the infant is too high and causes respiratory suppression. **Neonates** and fetuses have less efficient drug metabolic pathways of the liver or renal excretion of drugs than adults. This decreased efficiency lasts at least the first couple of months of an infant's life and is more prolonged in premature infants. The result is the inability to rid an infant's body of the continued ingestion of drugs and may reach toxic levels depending on the dosage and the pharmacologic properties of the drug [3,4].

NATURAL DISEASE

Infections and sepsis

Bacterial organisms causing infant and child sepsis vary with the age of the child. In the neonatal period, *E. coli*, Streptococcal organisms, and Hemophilus influenza organisms predominate. Older infants are more prone to *Staphylococcus aureus, Neisseria meningitidis*, Klebsiella, Pseudomonas, and Streptococcus species [6]. Depending on the immunization status, other organisms may be encountered. Some organisms operate through their actual presence in a tissue and cause inflammation. Children will have the typical symptoms including fever, cough, mucus, elevated white blood cell count, etc., as seen with pneumonia. Other organisms operate through production of a toxin that is released by the organism into the tissue and causes rapid death by hypotension and shock with little chance of the body to mount a brisk inflammatory response. Some infants are slow to mount an inflammatory response and an organism can quickly overpower the compensatory mechanisms of the infant, leading to septic shock. See Figure 11.4 for an example of changes associated with meningitis.

If treated with antibiotics in the emergency room, postmortem cultures will most likely be negative for growth due to the antibiotics inhibiting their growth in the laboratory. It is important the hospital laboratory complete any culture specimens received to establish the identity of the organism. Some hospitals routinely cancel testing upon death and discard the specimens. Prompt attention is needed to inquire about the types of labs ordered and


Meningitis
Skull
Blood vessel
Arachnoid mater
Subarachnoid space
Pia mater
Arachnoid mater
Subarachnoid space
Pia mater
Gray matter
White matter
Brain
Clear colorless cerebrospinal fluid
Normal
Milky cerebrospinal fluid containing neutrophils and bacteria
Meningitis

FIGURE 11.4

The changes associated with meningitis, which is usually a bacterial infection of the meninges within the brain. Meningitis can be rapidly fatal and family members may need to be treated.

speak to the laboratory directly and request continuation of the testing for the pathologist and/or the specimens so that the pathologist can send them for testing.

Cardiac

Structural abnormalities of the heart and great vessels are a reflection of fetal circulation. Because the lungs are not aerated in utero, blood flow to them is bypassed by a connection from the pulmonary artery to the aorta. This connection is called the ductus arteriosus and normally closes during the first week of life. Nutrients enter the fetus through the umbilical vein, which connects to the vasculature near the liver to be delivered to the heart and circulated. Blood returns via the umbilical arteries through the placenta to the maternal circulation.

CONGENITAL HEART DISEASE

This term describes any one of various structural abnormalities of the heart. They can range from a simple atrial septal defect that is an opening between the two atrial chambers and is easily repaired (Figure 11.5). They can also be complex transpositions of all the vessels with abnormal blood flow patterns, which can be lethal or life threatening. These abnormalities occur during the early fetal life at approximately 8–12 weeks gestation (called the period of embryogenesis) when the fetal development of internal organs is at its peak. After the organs are formed, the remainder of pregnancy is basically a continuation of building on this framework.


A Normal heart
Pulmonary artery (to lungs)
Oxygenated blood flow in left heart
Aorta (to body)
Right atrium
Deoxygenated blood flow in right heart
Right and left ventricles
A
B Heart with atrial septal defect
Left atrium
Atrial septal defect
Right atrium
Mixing blood from left (oxygenated) and right (deoxygenated) atria

FIGURE 11.5
(A) An atrial septal defect, which is a communicating opening between the two atria and is not a life-threatening heart defect.


A Normal heart
Pulmonary artery (to lungs)
Aorta (to body)
Oxygenated blood flow in left heart
Right atrium
Deoxygenated blood flow in right heart
Right and left ventricles
B Hearts with ventricular septal defects
Mixing blood from left *(oxygenated)* and right *(deoxygenated)* ventricles
Ventricular septal defect
Right ventricle
Pulmonary artery
Left ventricle
Mixing blood from left *(oxygenated)* and right *(deoxygenated)* ventricles
Alternate location of ventricular septal defect
B
A Normal heart
Pulmonary artery (to lungs)
Aorta (to body)
Oxygenated blood flow in left heart
Right atrium
Deoxygenated blood flow in right heart
Right and left ventricles
C
B Heart with tetralogy of Fallot
Increased outflow in aorta
Partial obstruction (stenosis) of right ventricular outflow (to lungs) and pulmonary valve
Ventricular septal defect
Thickened right ventricle (hypertrophy)

FIGURE 11.5, cont'd
(B) A ventricular septal defect, which is an opening between the two ventricles. Depending on the size this can be more serious because of the shunting of blood from the left side of the heart to the right ventricle. (C) A defect called Tetralogy of Fallot, a cyanotic congenital heart abnormality composed of four major defects.

The heart is formed into its adult four chambers with vascular connections via a series of twisting and folding of the cardiac tubular structure. It is during this twisting and folding that the major congenital heart abnormalities occur. Smaller abnormalities such as the atrial or ventricular defects occur due to lack of growth of various membranes later in development or due to blood flow abnormalities. Some of these flow abnormalities are a result of persistent fetal circulation and retention of the structures to bypass blood from the lungs (patent ductus arteriosus, or PDA). These flow abnormalities may exist due to structural abnormalities making them necessary to sustain life. If the circulations of oxygenated and deoxygenated blood are mixed it results in a **cyanotic** (blue baby) heart disease, and is more critical than those infants who can maintain normal oxygen status.

Occasionally these diagnoses are missed during the routine assessment of infants prior to discharge from the hospital or even by pediatricians in the outpatient setting. Clues include poor feeding, decreased growth and development, and respiratory difficulties. Other times, the case may come to the attention of the death investigator after a failed surgery and mandatory reporting of operating room deaths. In these cases, it is important to gain some insight into the severity of the abnormality, as well as if anything unexpected happened during the surgical procedure (e.g., laceration of a major vessel unexpectedly or malfunction of bypass machine) to contribute to the death requiring it to be assessed by the pathologist. Many times because it is a natural disease, it can be certified by the clinician. On the other hand, if there are issues concerning the quality of homecare or potential inflicted trauma, it needs to be admitted to the office for further evaluation.

VIRAL MYOCARDITIS

Viral myocarditis is the result of a virus infecting the heart resulting in inflammatory cells responding and causing muscle cell damage. This can be a focal abnormality or involve a large portion of the heart. Death is related to the amount of heart muscle damaged and the cell damage, causing a fatal arrhythmia and sudden death. Symptoms include shortness of breath due to pulmonary edema, chest pain or epigastric pain, and malaise (flulike symptoms). Organisms that are the most common causes include influenza, adenovirus, Coxsackie virus, Cytomegalovirus, and Mycoplasma. Other infectious organisms including parasites (toxoplasmosis) or fungi may also cause a myocarditis. Underlying immunosuppression is not necessary to acquire myocarditis but is more common among patients with low white blood cell counts. It is more common in older children and young adults or the immunosuppressed of any age.

RHEUMATIC HEART DISEASE

Rheumatic heart disease results as an immunologic response to a previous group A beta hemolytic Streptococcal infection. The person may relate a severe sore throat, usually within the previous month to six weeks, which was not treated with antibiotics. A low percentage of these cases (<1%) develop rheumatic fever and, of those, about 40% develop cardiac complications called rheumatic heart disease. This is an autoimmune disease where the body attacks the heart muscle and surface cells destroy the myocardium and damage the valves. Acute rheumatic heart disease may cause death from irritation of the conduction system with fatal arrhythmia. More commonly there are sequelae many years later of valvular heart disease resulting in the need for surgical valve replacement.

Respiratory

Pneumonia is a common cause of death in children of all ages, especially if they have an underlying disease such as brain damage, severe seizures, cardiac disease, or underlying respiratory diseases such as cystic fibrosis. Commonly bacterial in origin, it causes filling of the alveolar air spaces by acute inflammation (pus) that inhibits diffusion of oxygen through the airspaces into the alveolar capillaries for distribution to the remainder of the body. It can be community acquired from inhalation or as a result of aspiration of food. It can also be a symptom of spread from another site through the bloodstream or it can spread from the lungs into the bloodstream creating septic shock. Pneumonia in children can be rapidly fatal via sepsis and may not have large infiltrates in the lungs due to the septic shock and death before the body can respond with inflammatory cells.

Viral pneumonia may also result in severe respiratory symptoms. The location of the pathology is different with the inflammatory response occurring in the alveolar walls increasing the diffusion properties into the capillaries, or from swelling and inflammation of the small parenchymal bronchioles. The body responds with proteinaceous and fibrin deposition within the alveolar, which also affects the oxygen saturation. The viral infection can become complicated by a secondary bacterial infection that overwhelms the host and is lethal.

ASTHMA

Asthma is an acute airway obstructive disorder caused by an environmental trigger, for example, allergies or cold air. This results in an inflammatory response by eosinophils, which also cause a mast cell response (Figure 11.6). This combined inflammation causes the release of histamine, which further increases the inflammatory response with mucus secretion and bronchoconstriction, sending the breathing into a downward spiral. The mucus within the airways allows air to enter into the alveoli, but during attempts to exhale, the narrowed bronchi collapse inward and are blocked by the mucus. This causes air to be present within the lungs but unable to get out. Eventually no further air can enter, and as the oxygen is depleted in the alveoli, the patient becomes short of breath. This will get progressively worse without treatment until the child collapses into respiratory arrest. The treatment is epinephrine products to dilate the bronchi and allow exchange of air. As air reenters the alveoli, enough pressure beyond the obstruction will enable coughing to dislodge the mucus plugs.


A
B Normal Airway
C During Asthma Symptoms
Muscle
Airway wall
Airways
Lungs
Narrowed airway (limited air flow)
Tightened muscles constrict airway
Inflamed/ thickened airway wall
Mucus
Muscle
Airway wall
Airway x-section
Thickened airway wall
Muscle
Mucus

FIGURE 11.6
Shows the changes associated with asthma. The narrowed bronchioles cause shortness of breath with wheezing or coughing symptoms.

CYSTIC FIBROSIS

Cystic fibrosis is an inherited disease in which the child lacks an enzyme product that results in abnormally thick mucus and pancreatic secretions (Figure 11.7). This causes frequent lung infections and poor digestive functions with bowel obstructions and pancreatitis. This diagnosis is not usually a reportable case to a death investigator unless there is an underlying issue with medical care or abuse.

Case Study

A 10-year-old girl with a history of asthma requiring frequent use of an inhaler and emergency room visits for exacerbations went home for lunch, which was without incident. She was late returning to school and arrived short of breath and wheezing when she suddenly collapsed. Resuscitative efforts described stiff lungs after intubation. Autopsy findings showed hyperexpanded lungs that met in the midline over the heart and were very fluffy upon palpation. Sectioning of the lungs showed numerous mucus plugs throughout the parenchyma and collapse of the fluffy parenchyma upon dissection. Microscopic evaluation showed the typical findings of the small bronchi with intraluminal mucus strands, as well as surrounding mast cells and eosinophils in large numbers (not normally seen). The cause of death was certified as acute asthma, and manner of death as natural.


Cystic Fibrosis
Thick, sticky mucus blocks airway
CFTR gene
Chromosome 7
Thick, sticky mucus blocks pancreatic and bile ducts

FIGURE 11.7
Cystic fibrosis is a disease characterized by thick mucus that plugs the airways and pancreas.

Neuromuscular disorders

Down's syndrome is an inherited disorder composed of an additional X chromosome and is frequently called Trisomy 21. The result is varying degrees of mental retardation with those who may function at basic jobs to those with severe deficits and are wards of the state. These individuals may also have underlying cardiac disease that makes them susceptible to sudden cardiac death. In later years, those with Down's may exhibit early onset dementia and require care in a facility. Whether the case is within the jurisdiction of the coroner/medical examiner will vary with the circumstances surrounding the death and will need to be decided on a case-by-case basis.

Hydrocephalus is swelling of the brain's ventricular spinal fluid compartment. This accumulation of fluid expands outward, compressing the cortex and white matter against the skull, which damages it. If not treated early, the child may have irreversible brain damage. Treatment is relatively easily completed by threading a vascular-sized catheter from the ventricular system in the brain, through the subcutaneous tissue of the neck, and draining excess fluid into the peritoneum. This is called a ventriculo-peritoneal shunt (VP shunt). The diameter of the catheter is small and may become clogged with sudden onset of repeat hydrocephalus and deterioration of consciousness.

Occasionally, hydrocephalus will present in the differential diagnosis of head injuries in a child due to a sudden onset in increased head circumference. The cause of hydrocephalus is a blockage in the spinal fluid flow dynamics and can result from a cyst, congenital abnormality, or tumor. An autopsy examination will rule out a traumatic origin and may require assistance from a neuropathologist for the underlying natural cause.

Cerebral palsy is a cognitive, behavioral, and neuromuscular disorder as a result of hypoxic-ischemic injury in utero or as a result of prematurity. The degree of brain injury varies on the degree of injury and varies from severely debilitated children who are vegetative, to those with various learning disorders. An investigator may become involved in these cases due to living conditions or because of a medical issue that required it to be reported.

Metabolic disorders

The most common metabolic disorders are screened for at birth and submitted to the state health agency. Typically these results can be found in the pediatrician's records. Occasionally they will need to be obtained from the screening agency. The initial screening is done for common diseases determined by each state [5].

Diabetes mellitus commonly presents in children and young adults. It is typically type I diabetes and the first symptom can be diabetic ketoacidosis. The initial diagnosis may be at the time of death. The child will have been experiencing the typical symptoms of polyuria, polydypsia, and feelings of lack of energy, but may not have sought medical treatment.

Fatty acid oxidative disorders are inherited diseases due to lack of an enzyme in the metabolic breakdown of fats. This results in accumulation of the fats in the liver and can cause death. The accumulation of by-products can require a period of time and the diagnosis missed on the initial newborn screening. It is one of the causes of death screened for in the sudden death of an infant. When the diagnosis is made, families should be offered genetic counseling. Dietary restrictions in some metabolic pathways may prevent further symptoms and death.

Neoplasms

Occasionally undiagnosed neoplasms may cause death in children. These can range from brain tumors, leukemias, bone/soft tissue tumors, or solid tumors of the internal organs. Children with previously documented neoplasms are rarely seen in a coroner/medical examiner investigation, unless there were issues with them receiving medical care. Cases of holistic medicine use or refusal of care based on religious grounds have occasionally received widespread press and may fall under the jurisdiction of a coroner if documentation of the disease is needed.

Acquired diseases

Ingestion of poisons/medications is always a concern in sudden death of children. Toddlers especially may find pills on the floor or within reach or on counters. Because some items can appear as candy to a child or due to their oral fixation at that age, they can ingest them and parents not know. Part of a scene assessment is noting the location of parent's medications and cabinet locks for securing cleaning products and insecticides. The diagnosis may not be suspected until evaluation of gastric contents or the results of toxicology are known. If it is prescription medication, especially sedatives, parent-assisted ingestion should be considered. The easiest way to give this medication to kids is through a bottle, therefore confiscation of a bottle and its contents should be done as part of all infant death scenes. Bottles need to be secured in an upright position so they do not leak during transit. It is important to only handle the outside of the bottle with gloves, as it may become important to fingerprint the bottle to determine who last fed the infant. Another source of contamination can be a dried formula container that can also serve as a drug stash. Small quantities spilled within the milk powder can be enough to severely affect an infant. Inspection of milk containers and the preparation of formula can be an extremely important part of a death scene investigation.

Anaphylaxis is a severe allergic response to an ingested food, bee stings, or even skin surface application of an irritant. In anaphylaxis, the first instance the child or adult is exposed to the allergic material will result only in a relatively mild response of the body. However, it is this initial introduction that creates a memory in the body for a severely heightened response at the next exposure, which can be lethal prior to emergency response. If the severe allergy is known, it can be treated by immediate injection of epinephrine, which can be carried as an epi-pen. Because these cases are sudden, unexpected, and generally accidental in nature, they are reported and certified by the coroner/medical examiner office. Important scene documentation includes the person's statements just prior to their collapse, as well as findings by emergency response teams and witness statements about the course of events. They may document that the child was stung by a bee or consumed peanuts or shellfish, common anaphylactic agents.

Anaphylaxis is modulated by the body through mast cells and immunoglobin E found in particular white cells. The latter value can be quantified if needed. Autopsy findings can include sites of a bee sting or possible food in the stomach, swelling of the airway including the epiglottis, or mucous plugs within the small bronchi, similar to what is seen in an acute asthma attack. It is a good practice for the investigator to review the food and areas surrounding the child who dies to see if they contain the items that they are allergic to.

Case Study

An 8-year-old girl with known allergies to peanuts went to a week-long summer camp away from home. Counselors and nurses were aware of the allergy. During dinner she took a bite of a chocolate crispy treat containing peanuts. She immediately discarded the bite but almost immediately began having symptoms of anaphylaxis. She had no epi-pen with her and she died before resuscitative efforts could support her.

Public health notifications

In pediatric infectious diseases it is extremely important to notify the public health department of the organism identified to prophylactically treat other family members or children in the home or school to prevent an outbreak. Even though these people may be asymptomatic, they may be in a period where the organism is quiescent but can produce disease if certain environmental and body parameters are present. The health department can trace contacts and provide surveillance and public announcements if needed to prevent further deaths. The local health department will perform the notifications to the Center for Disease Control (CDC), which follows national trends. Either department may request frozen tissue or blood to perform subtype species analysis for epidemiological studies and further characterize the pathogen. Since there are no diagnostic findings always notable at the time of autopsy in infectious diseases, it might be prudent to routinely hold frozen tissue biopsies on key organs such as the heart, lungs, brain, and liver in case it is requested. These frozen samples may also be useful for genetic analysis of inherited diseases. Formalin-fixed tissue biopsies that are routinely held are usually unsuitable for either purpose.

Congenital and genetic counseling

In deaths related to an underlying genetic disease, it is useful to have pediatric counselors or genetic counselors available to families to answer their questions regarding familial risk factors and for future pregnancies. Some diseases have easily obtained laboratory tests available to screen the family members for the disease. In metabolic diseases they may be treated by dietary restrictions. A list of counselors can be very helpful for suggestions over the phone or may be included in a referral letter citing the cause of death as genetically related.

NONACCIDENTAL TRAUMA

Patterned injuries are one of the keys to evaluating inflicted trauma. Patterned abrasions matching belts, flyswatters, electrical cords, etc. help distinguish a nonaccidental cause of death from accidental injuries. Varying ages of injuries, locations, patterns, and internal findings are all used to make the diagnosis. When observing a child dead in the emergency department or at a residence, it is important to evaluate the skin surfaces and look for trauma, but especially patterned injuries. The object responsible for the injuries may be located nearby or discarded in trash bins as a means to hide the evidence. It is also good to note the caretaker history about how the child came to be in medical care and if the story is plausible with the degree of injury. This usually requires investigation at the site of injury and careful recording of carpet padding, wall trauma, toys, or whatever else might have resulted in the injuries noted by medical personnel.

Markings from belts are flexible and may only partially match along curved body surfaces as they wrap across the skin. The pattern on a belt, such as weaving, stitching, snaps, or the buckle, may be imprinted as contusions or abrasions. The width of the injury will nearly match the width of that portion of a belt and will help to narrow the confiscated items as evidence. Electrical cords leave thin, narrow, parallel abrasions/contusions with a central parallel line corresponding to the central trough on the cord. Plugs may also create partial or full imprints.

Cable cords create curved abrasions and contusions matching the diameter of the cord, which may be formed into a loop. Toys such as swords, bubble wands, tent poles, etc. all can be used as instruments for punishment and may leave characteristic imprints on the skin. The objects used for punishment many times are nearby and may not even be obscured as they are used frequently.

Irons and hair curling irons may also leave patterned burns. Immersion of hands, feet, or buttocks in hot water will leave water-level burns as a ring in a glove- or sock-type pattern. In immersion of the buttocks into hot water, the line will appear around the seat area of the buttocks. If the story is the child got into a bath without assistance, then it is not consistent, as the feet should also contain similar burn injuries at a depth of the water. It is important to document hot water temperature and length of time for the water to reach the highest temperature from the suspected faucet. If the immersion was in a bath tub, the time it takes to fill the tub and reach a scalding temperature is also important to note.

Genitalia are also areas that need to be carefully evaluated for trauma. Many times the period of risk is near the time of potty training, and sitting on the toilet for long periods may leave ulcers on the skin or burns may be inflicted to the genitalia as punishment for wet clothing. Sexual assault may also be a motive, so careful photography of the genitalia at the time of autopsy is good documentation for later questions. If trauma is present, penile and vaginal DNA swabs need to be obtained.

Severe spankings or a “whooping” may result in bruising of the buttocks with severe subcutaneous bruising into the fat within the buttocks. In dark-skinned children and in children with a thick layer of fat, this can be difficult to see. A subcutaneous dissection of the skin over the back and buttocks can demonstrate the extent of hemorrhage and assist visualization of patterns not seen well on the surface skin. Other gray-brown discolorations can be seen on the lower sacrum and are called Mongolian spots. They are not contusions, and when incised, the underlying skin will be normal without hemorrhage.

Sometimes hand or finger marks can be seen across the back, arms, or face. In acute injuries, DNA swabs may be considered to link the possible suspect with the patterned injury. It is important that all of the injuries be documented with and without rulers in the photographs and good measurements of the size of these patterned injuries be documented by the pathologist for the potential ability to match the injury to the person or an object. See Figure 11.8 for examples.

Contusions anywhere on the abdomen, but especially near the umbilicus, are highly suspicious for inflicted trauma until proven otherwise. The thin layer of fat and abdominal muscles of infants and children are not sufficiently strong enough to withstand a fist or kick to the surface without resulting in internal damage (see Figure 11.8B). This can result in lacerations of the liver or spleen and internal



FIGURE 11.8
(A) Patterned abrasion on the scalp and the corresponding toy was found nearby. The scalp and torso contained multiple similar abrasions. (B) A large contusion of the abdomen. Internally there may be extensive hemorrhage from a lacerated liver or there may be a ruptured small bowel with peritonitis. A young child has thin abdominal fat and not fully developed abdominal muscles to withstand a blow to the abdomen.

bleeding. The mid-abdomen is particularly vulnerable to a punch as the force forces the duodenum–proximal jejunum and pancreas against the spine causing it to lacerate. The bleeding may be minimal but the loss of integrity of the lumen of the bowel or the leakage of digestive enzymes into the sterile peritoneal cavity rapidly leads to peritonitis and death if not immediately surgically repaired.

Other clues to suspected nonaccidental trauma are the distribution of contusions over the body (Figure 11.9). Bruises over bony prominences such as the knees, elbows, chin, and forehead can be associated with falls, especially in active kids or toddlers learning to walk. They would not be expected in a bedridden child, one confined to a wheelchair, or immobile infants. So the distribution of injuries needs to be assessed with the developmental milestones as well as the mobility of the child. Areas of great concern are protected areas not exposed to normal childhood bumps and scrapes, such as between the shoulder blades and the neck, lower back, abdomen, chest, cheeks, or forearms. Other areas such as the frenulum, the small piece of membrane that attaches the lips to the gums, should be an area not usually associated with accidents but may be torn with slaps across the mouth or forceful feeding or even aggressive intubation. Loss of teeth or gum lacerations should also be assessed carefully with regard to the offered mechanism of how it happened for plausibility, as well as visual assessment of other obvious injuries in conjunction with it. See Figures 11.10 and 11.11.


Accidental Trauma
Nonaccidental Trauma

FIGURE 11.9
Classic distribution differences of accidental versus nonaccidental injuries. It is important to correlate the scenario with the pattern, extent, and distribution of injuries to make the best assessment of how the injury may have occurred.



FIGURE 11.10
(A) Faint contusion of the scalp; when reflected there is a large linear skull fracture (B).



FIGURE 11.11
(A) A diffuse axonal injury is basically a shearing of the neuron extensions from the body of the neuron cell. This occurs during acceleration/deceleration injuries and may not show gross bleeding or obvious abnormalities on autopsy. The finding is a microscopic one. Fatal head injuries in infants and children may result in bleeding within the brain tissue (contusion), subarchnoid or subdural hemorrhages. (B) A review of the anatomy of the location of those injuries in their respective layers of brain tissues.

Extent and duration of injuries

Common court questions are: When did the fatal inflicted injury happen? Is this a single or repeated injury over time? Would earlier medical treatment have resulted in a different outcome? These questions are difficult to answer with current scientific methods available to forensics. A good general response to the medical therapy question is the sooner medical treatment is sought in care of trauma, the outcome is usually better. In some cases the injuries are so extensive that medical treatment probably would not have changed the outcome. Earlier social intervention prior to the fatal trauma would have improved the outcome.

When the injuries happen is also a very difficult question to answer. At best, it can be estimated within a range of days, not hours or a specific time unless it was a witnessed event. The estimates are made via skin biopsies and biopsies of injured sites, such as a ruptured bowel, subdural hematoma, or sampling of fractures. As hemoglobin in bruises breaks down, it releases the cellular iron that is absorbed by macrophages. Special microscopic staining procedures can demonstrate the presence of these macrophages. As the iron changes its configuration it develops a different morphology and can be seen as yellow pigment on slides called **hematoidin**. This can also be noted grossly on skin bruises as the green-yellow coloration they assume with healing. This all occurs over a continuum with the hematoidin appearing at approximately 4–5 days and the hematoidin at 8–10 days after injury. This is not an exact science and, depending on the depth and extent of a bruise, it may take slightly longer or shorter. Multiple studies have determined that gross appearance of bruises is not a good indicator of age of the injuries and dating them via observation is not valid [8].

Dating of fractures is also variable because the underlying nutrition of the child and continuous injury over the site causing repeated fractures and hemorrhages all distort the healing and making an exact determination of the injury date difficult.

CHILDREN LEFT IN VEHICLES

There has been a bit of press over the past few years regarding children left in their car seats while caretakers went shopping, or forgotten in the backseat when the caretaker arrived at work and had not dropped off the child at daycare. Even though the temperatures outside a vehicle may only be 80°F, the temperatures inside a vehicle parked in the sun can reach over 120°F in 60 minutes if the windows are closed. This is due to the radiant energy being absorbed into the dashboard, seats, and other objects, then heating the compartment via conduction and convective currents [7]. The trunk has also been utilized to contain children while parents go shopping, go to a friend's house or bar, or go to work. Temperatures inside the trunk may also become similarly excessive.

Scene investigation of this type of death is similar to other heat-related deaths. Core body temperature or infrared temperature of the child and compartment are important scene findings. Also document if the child was restrained in a car seat as well as efforts of the child to escape, if any. Also the presence of liquids or food left for the child (or children) is important to photograph and document. Even though in some instances this is seen as an accidental death, in other jurisdictions it has been successfully prosecuted as child abuse or neglect and associated with prison sentences. Children left in a hot car may be showing early decomposition changes and will continue to rapidly decompose even though they are refrigerated at the morgue. It is important to photograph a child as completely as possible for the pathologist to review for possible additional injuries. Electrolytes, full toxicology, and stomach contents will be important documentation to note and substantiate that hyperthermia was the cause of death.

FETUSES AND HOME BIRTHS

Intrauterine demise occasionally comes to the attention of the investigator if there was maternal trauma from a motor vehicle accident or assault, demise while in prison or as a ward of the state, or maternal drug use. The autopsy is done to determine fetal gestational age and to note congenital or placental abnormalities for a cause of death. For this determination, the placenta will need to be obtained for examination by the forensic pathologist. Many times the hospitals discard the placentas, so prompt attention will be required.

Home births, sometimes in the toilet, or discarded infants in an attempt to hide the birth will need to be examined by the forensic pathologist. If it can be found, the placenta needs to be collected as well. All items surrounding the birth or infant are also needed and should be photographed as found at the scene. Questions asked by law enforcement include whether it was a live birth, age of viability, how long the fetus/infant lived, if it was a live birth, etc. These can be very complicated, especially if the infant was buried or is decomposed. DNA of the fetus may be helpful to link parentage and should be held on the fetus/infant.

Skeletal remains of infants can be minimal or appear as partial bones due to the large amount of cartilage present. Recovery of child and infant skeletal remains can be challenging and experienced anthropology consultation may be needed.

SUDDEN DEATH WITH NO CAUSE IDENTIFIED

Not uncommonly, observed findings aggregated in the evaluation of an infant or child death may not clearly point to a single cause or even a single manner of death (Figure 11.12). Sometimes there may be findings of a microorganism only present in one culture and not others, or the organism identified may be either a pathogen or a contaminant, or the scene may have included co-sleeping. There may be no way to differentiate the exact cause resulting in an "undetermined" cause and manner. Other times a head injury may have been caused either accidentally or by inflicted homicide, or just plain poor judgment on the part of the caregiver. Failure to seek medical therapy may play into the determination or it may be unable to be determined exactly how the injury occurred. In this case the cause of death is relatively obvious—blunt-force trauma of the head—but the manner uncertain and therefore called undetermined.


Cause of Death in Kids
Natural Disease
Accidents
Homicides
Suicides
Infection
Congenital
SIDS
Blunt Force
Asphyxia
Poisoning
Blunt Force
Asphyxia
Drugs or Poisons
Gunshot Wounds
Gunshot Wounds
Asphyxia
Drugs

FIGURE 11.12
Diagram of the broad causes of death that fall within the four major manners of death. SIDS (Sudden Infant Death Syndrome) is now known as SUID (Sudden Unexplained Infant Death) and may be ruled undetermined or natural manner of death depending on the investigation and pathologist viewpoint.

There is obviously pressure to make decisions by attorneys, families, and law enforcement, but it must also be remembered that the science and forensic judgment may only support a certain level of certainty. The bottom line is "do no harm" and call only what you can support and defend. Many times the greatest punishment may already have been rendered with the loss of one's child.

REFERENCES

[1] Fetal Alcohol Spectrum Disorders. Centers for Disease Control and Prevention, National Center on Birth Defects and Developmental Disabilities, Division of Birth Defects and Developmental Disabilities; 2011. Retrieved from http://www.cdc.gov/NCBDDD/fasd/facts.html. [August 2013].

[2] Illegal Drug Use and Pregnancy. John Hopkins University, Health Library. Retrieved from http://www.hopkinsmedicine.org/healthlibrary/conditions/adult/pregnancy_and_childbirth/illegal_drug_use_and_pregnancy_85,P01208/. [August 2013].

[3] Choonara I. Drug Metabolism in the Neonate. J Arab Neonatal Forum 2005;2:1–4. Retrieved from http://www.fmhs.uaeu.ac.ae/neonatal/iss003/p1.pdf. [August 2013].

[4] Gardiner S. Drug Safety in Lactation. Medsafe, New Zealand Medicines and Medical Devices Safety Authority, Publications; 2001. Retrieved from http://www.medsafe.govt.nz/profs/puarticles/lactation.htm. [August 2013].

[5] About Newborn Screening: Conditions Screened by State. Baby's First Test; 2013. Retrieved from http://www.babysfirsttest.org/newborn-screening/states. [August 2013].

[6] Santhanam S. et al. Pediatric Sepsis. Medscape; 2013. Retrieved from http://emedicine.medscape.com/article/972559-overview#aw2aab6b2b3. [August 2013].

[7] Heat: A Major Killer. National Weather Service, Office of Climate, Water, and Weather Services; 2013. Retrieved from http://www.nws.noaa.gov/os/heat/index.shtml. [August 2013].

[8] Vanezis P. Interpreting Bruises at Necropsy. J Clin Pathol 2001;54:348–55.

CHAPTER 12

Asphyxia

Learning Objectives

- Compare and contrast the ligature furrow of a suicidal hanging to a homicidal ligature. List two key features for each.
- Differentiate petechiae from Tardieu spots and include their locations and underlying causes.
- A call comes to the office for the investigator to respond to a man dead at a residence. Upon entering the scene, the house is noted to be full of piles of empty liquor bottles and you are directed to the bathroom. There you note a man lying over the edge of the tub empty of water. Outline three key questions and five photographs that are needed to properly investigate the scene.

Key Terms

Anoxia
Hypoxia
Asphyxia
Positional asphyxia
Compression asphyxia
Strangle
Choke hold/blood choke/sleeper hold
Tardieu spots
Adipocere
Carbon monoxide
Cyanide

Chapter Summary

This chapter discusses multiple methods resulting in hypoxia and potentially life-threatening events. Hangings are most commonly suicide but also require vigilance by the investigator to not overlook ligature strangulation. Manual strangulations and choke hold-type injuries can be subtle and have few external findings. Asphyxial deaths due to noxious gases require vigilance for safety, as well as documentation to provide the information to determine which gas was present in the environment that caused the death. Inhalation injuries are very difficult to document through toxicology and have few autopsy findings, so the cause of death largely depends on scene information. Photographic and written information will greatly assist a forensic pathologist with these differential diagnoses.

INTRODUCTION

Asphyxia results when a process causes a lack of oxygen to the brain, unconsciousness, and death. **Anoxia** is the total lack of oxygen, and **hypoxia** is a decreased level of oxygen to the brain and vital organs. Common causes of asphyxia include hanging, strangulation, drowning, or mechanical causes like compression of the chest or **positional asphyxia**. An extended period of hypoxia can result in brain death.

Case Study

A 39-year-old man was the single occupant and driver in a motor vehicle accident. According to officers and witnesses, the car was traveling at a high rate of speed when the man lost control of it on an area of wet pavement, flipped the car, and crashed it upside down into a light pole. Upon arrival he was found trapped and pinned in the vehicle, strapped into the driver's seat. The roof of the vehicle had collapsed down to the level of the steering wheel. The decedent was pinned between the seat and steering wheel with his head flexed toward his chest and the roof pushing onto his back. The jaws of life were used to open the compartment. Pry bars were needed to extricate him from the position he was in. Examination at the scene and by the pathologist showed no fractures of the torso or extremities. His face was intensely congested and the sclera mildly hemorrhagic. An autopsy examination showed no fractures or internal injuries. The brain, neck, and spine were free of injury. The cause of death was certified as compression asphyxia due to motor vehicle accident, and the manner of death as accidental.

HANGING

Hanging is a combination of a ligature around the neck and the body in a position of either partial or full suspension. It does not require the body to have the ligature tight and totally compressing the neck, falling from a height (like a judicial hanging), nor free suspension. It can occur in any position by something encircling the neck and the person leaning forward. Children can accidently become entangled in window blind strings or crib toys hanging from the edge of the crib railing, or they can become wedged between pieces of furniture while in suspension.

Hanging with a noose can occur in a sitting, standing, kneeling, or full suspension position. The ligature can be fashioned from a rope, curtain, tow strap, shoestring, sheet or shirt, belt, electrical cords, necklace, posey restraint, or even a pacifier string. The knots forming the ligature range from a simple overhand knot to a full hangman's noose. The classic hangman's noose is used by some but a simple sliding overhand-type knot is more common. A hangman's noose was actually a scientific phenomenon with the number of coils depending on the weight of the condemned, as well as the type of the rope to be used. The weight of the condemned was also used to calculate the distance of the drop through the trapdoor to prevent decapitation. The position of the knot behind the ears aided the fracture of the cervical spine.

Fractures of the neck in suicidal hangings are rarely seen, as most are done from a short-distance fall. Petechiae are also rarely seen. An internal examination will show a compression area of the tissues but rarely any hemorrhage or fractures of the hyoid or thyroid cartilage.

Sometimes one ligature fails and will be hanging in a nearby location while a different one is found on the body. It is important to note where the items may have originated, especially if the hanging occurs in prison. Prisoners usually do not have access to shoestrings or belts and may fashion a noose from bed sheet strips hung from an overlying bunk. The same findings need to be observed if the decedent is a patient in a psychiatric ward. Usually these patients are relieved of belts and shoestrings especially if they are on suicide watch. Those who wish to commit suicide can be quite focused and creative in achieving their goal. Depressed prisoners and patients need close observation if they are suddenly having improved positive feelings, because it may indicate a resolve to perform the final act rather than true progress toward recovery. Drug intoxication may be a part of the findings in a toxicology test.

The mechanism of death is usually compression of the blood flow to or from the head, rather than obstruction of the airway or fracture of the spinal column (Figure 12.1). This is usually a reflection of physics. The head alone weighs about 10 lbs. The amount of force required to obstruct venous flow (blood flowing from the head) is approximately 7 lbs and the amount to obstruct arterial flow to the brain is approximately 11 lbs. This is because the walls of arteries contain a thick muscular layer that is lacking a vein. The trachea supporting the airway is even stronger due to its presence of cartilage and requires approximately 20 lbs of pressure to collapse it. A fracture of the spine will require a larger degree of force, and usually one with acceleration/deceleration, such as the drop that occurs in a judicial hanging.



FIGURE 12.1
Human throat including veins, bones, and organs.

As the noose tightens around the neck, it will first obstruct the jugular veins followed by the arteries. With unconsciousness, the head will collapse and contribute to the obstruction of blood flow by further placing weight on the neck. Depending on how the force and noose are applied will result in the presence or absence of petechiae. Petechiae within the eyes are created by the rupture of capillaries. One way to think of this is by compression of the venous return to the heart and continued arterial blood flow into the brain, causing increased pressure on the small vessels, which finally rupture, creating the petechiae.

Externally, a typical suicidal hanging furrow abrasion shows upward deviation to one or both ears or the back of the head depending on the knot placement (Figure 12.2). The furrow should match the suspected ligature in pattern and dimension. In some areas, the furrow may be wider than the ligature due to sliding upward as the suspension is occurring.

Ligature as evidence

If the decedent is obviously dead, there is no need to remove the ligature around the neck, and it should be left in place for examination by the forensic pathologist. If it has been removed, it should be placed into an evidence envelope, sealed, and submitted with the body for examination. Many of the ligatures will fray when they are cut. When multiple loops are used, it can be difficult to reapproximate the ligature for later duplication and examination.

Remember, each piece of evidence should be retained so that it can be reproduced as the original whenever necessary. The easiest way to do this with a ligature is to use wide masking tape or duct tape and take a length approximately 6 in. long. Slide this under the binding with the sticky side toward the loop of the ligature then fold over the tape so that it forms a sealed edge with a small



FIGURE 12.2
(A) Ligature abrasion showing upward deviation, and (A & B) ligature abrasion patterns.



FIGURE 12.3
Ligature removed from a hanging victim. Note how the ligature is removed from the neck away from the site of the knot so that the knot is preserved as evidence.

tab extending from the margin. Cut through the middle of the tape and the loops of the ligature so that each cut edge has an adherent length of doubled-over tape. For each area of the ligature with its own separate loop, such as the one securing it to the fixed beam and the one surrounding the neck, each tab can be marked "A," "B," etc. to differentiate the connections. This technique also works on homicide cases for bindings at wrists, ankles, or body wraps. The area where ligatures are cut should be distant from any knots so they are preserved (Figure 12.3). Knots should not be unwrapped as a means to remove the ligature. Sometimes tape will not stick and strings on either side of the cut will suffice.

SEXUAL ASPHYXIA

Some hanging scenes will appear very different from the moment an investigator enters them. These are sexual asphyxia scenes where there may be an intricate asphyxia mechanism with pulleys, bondage mechanisms, or even a simple noose. These are nearly always males who may be dressed in woman's clothing or underwear. Cross-dressing and pornography seem to be a part of the fantasy that occurs. Sex toys may be lying about as well. Drug use may or may not be a part of the scenario. It is written that asphyxia and oxygen deprivation heightens sexual gratitude, therefore the reason some individuals participate in the behavior.

The bondage and asphyxial apparatus is associated with escape mechanisms, such as keys or releases for ropes, which may still be clutched in the hands or dropped on the floor out of reach. The problem usually arises due to the loss of consciousness and being physically unable to release the mechanism or some miscalculation about the release. Either results in the asphyxia going too far, total loss of consciousness with further oxygen deprivation, and death. If a noose mechanism is used it usually has some type of padding like a towel or scarf between the noose and the skin to protect the person's neck. The penis is many times exposed or the underwear is disarranged. High heels, bras, pantyhose, bows, leather outfits, or items encircling the penis are commonly seen.

Sometimes individuals suddenly collapse during masturbation or sexual relations. The increased heart rate and blood pressure can precipitate a cardiac event with arrythmias or even a ruptured aneurysm. The risk for cardiac events is increased with a history of cardiac disease and drugs for erectile dysfunction. They are contraindicated but may be used anyway and should be inquired about during investigation in to the medical history when death occurs in this situation. It is not uncommon for a sex partner to not be aware that the decedent is taking erectile dysfunction drugs. Sex toys or hand-carved items may be lying next to or attached to someone collapsed with underwear and pants in disarray. There might be a computer with pornography displayed or signs of drug use. It is a good practice for the investigator to eject a DVD from the TV or computer, in the presence of law enforcement, to document pornographic movies.

A female dying during sexual intercourse is less common than a male dying. If the female is young, and especially if she is, or has recently been pregnant, oral sex with inflation of the vagina by air can cause an air embolus to enter the vascular area of the placental surface. This is a very rare occurrence, but questions concerning the activities during the sexual relations may need to be asked during the investigation.

Case Study

A 55-year-old man with a history of coronary artery bypass surgery was found sitting in pajamas in a chair at a desk in his residence. The family related they came home and found him in that position. He had recently been complaining of back pain and increased chest pain, usually relieved by nitroglycerin. The investigator at the scene noted no trauma and there was a mid-sternotomy scar on the chest consistent with the history of a bypass graft surgery. The only unusual finding was a plastic dry cleaning bag attached to the big toe and threaded up through the pajama bottoms. Also noted was a disposable plastic glove on one hand. When the investigator inquired from the family about the bag on the toe they said it was not unusual and he rigged this bag to help with his back pain. Upon admission to the office and removing the clothing for examination, it was noted the plastic bag was fashioned into a strip, tied around the big toe on one end and encircling the testes on the other, forming a tight bondage. Review of the scene photographs showed a computer on the desk where the decedent was sitting. Postmortem toxicology was positive for moderate levels of cocaine use. The death was certified as atherosclerotic cardiovascular disease with the contributing factor cocaine use. The combination of drugs with the heart disease and probable masturbation led to a significant cardiac event.

SUICIDE NOTES

Many suicide deaths are not accompanied by suicide notes. It is estimated they are found in 40% of suicide deaths and are seen more commonly left by females than males. The presence or absence of a note is not always helpful as many are wandering, reminiscent memories that may be open to interpretation. Others, however, may spell out last wishes or give good-byes to family members or friends. Some are vengeful. Whatever their content, their location can be important, and they need to be recovered as evidence. It is best to place a note inside a clear plastic envelope. This allows the note to be photocopied or scanned and easily shared with other agencies, plus it contains body fluids and retains any fingerprints on the surface should that prove necessary to test.

STRANGULATION

Homicidal strangulation may occur from a ligature or by arms or hands. The term **strangle** is defined as to choke to death by compressing the throat with something (e.g., a hand or rope). Some people commonly use "strangulation" for all ligature deaths and others reserve it for homicidal-type injuries.

Homicidal ligature strangulations externally vary from suicidal hangings by their position of the ligature furrow (Figure 12.4). Homicidal ones have a horizontal pattern partially or fully encircling the neck and lack the upward deviation to the



FIGURE 12.4
Ligature furrow from a homicidal ligature strangulation. Notice the horizontal pattern with absence of upward deviation toward the ears or chin seen in suicidal hangings.

side or back of the head seen in suicidal hangings. The ligature may be removed by the perpetrator and no longer with the body when it is found, so accurate dimensions of the furrow may help to narrow the suspect weapon. A crossover point or garrotte may also be used to tighten the ligature and leave a secondary pattern. Common homicidal ligatures are wires, ropes, leather bands, or clothing items such as pantyhose, underwear, socks, or shirts.

Manual strangulation involves using the arms or hands. This type of injury can leave obvious, faint, or no injuries to the external neck (Figure 12.5). Occasionally


A
METRIC
B
THYROID GLAND
EPIGLOTTIS
HYOID BONE
THYROID CARTILAGE
CRICOID CARTILAGE
THYROID GLAND
THYROID VEINS
TRACHEA
C
D

FIGURE 12.5
(A) Finger impressions on anterior neck from a manual strangulation. (B) Anatomy of the neck showing the relationships of the thyroid cartilage (Adam's apple) and the superior hyoid bone. Either may be fractured in manual strangulation. (C) Fractured hyoid bone: note the angulation of the curved bone on the right as well as the bilateral hemorrhage at typical sites of fracture. (D) Depiction of manual strangulation.

the pattern will duplicate outlines of fingers. Petechiae may be florid, minimal, or absent. Circumstances of how the body is found may be the biggest clue that this diagnosis may be possible. This should be considered as a potential cause in dumped bodies, female decedents, lover quarrels in residences, bodies in alleys, or bodies found out in the open with no obvious injuries. The decedent may be found dressed or naked, but note should be made of any necklaces or clothing bands at the neck by good photographs at the scene. The diagnosis is made by finding hemorrhage of the anterior and/or lateral muscles of the neck. Because the muscles are easily bathed in blood early in the autopsy, this can obscure this finding, therefore the neck is usually examined last to create a bloodless field.

CHOKE HOLDS

Choke holds previously were used by law enforcement to subdue a suspect. The mechanism of application is usually from the rear of the suspect with the upper arm on one side of the neck and the forearm on the other with the crook of the elbow at the front of the neck (Figure 12.6). By application of one hand on the other and compressing the arm inward, it puts pressure on both carotid arteries and jugular veins, causing the subject to collapse. The practice is no longer used by law enforcement because it resulted in a number of deaths either by prolonged application or fractures of the airway.



FIGURE 12.6
(A) Young boys performing a choke hold. (B) The choke hold is a commonly used move in wrestling and cage fighting. (C) Depiction of jugular veins and carotid arteries and their relationship to the trachea and areas of potential compression.

Choke holds have seen a resurgence in popularity with cage fighting and are easily seen on TV and the Internet. These tactics are also taught in the military. The terms **blood choke** or **sleeper hold** are sometimes used to describe it as well. The findings in a death associated with these can be subtle and only have focal hemorrhage in the strap muscles of the neck, or they can have fractures of the hyoid bone or even the midline thyroid cartilage.

MECHANICAL ASPHYXIA

Mechanical asphyxia includes both compression asphyxia and positional asphyxia. **Compression asphyxia** results when some mechanical device compresses the chest or abdomen, inhibiting movement of the diaphragm and lack of oxygen–carbon dioxide gas exchange. Common causes include motor vehicle accidents where the occupant is compressed between the steering wheel and the seat, or industrial accidents where the decedent's torso may become entrapped in the machinery or between two vehicles. The findings include abrasions or compression areas seen on the skin and intense congestion, petechiae (Figure 12.7A,B), or hemorrhagic spots above the compressed area. Hemorrhages may be seen in the sclera (white portions of the eye) and face. The way to envision the physiology is a garden hose with the water on being run over by a vehicle. The hose portion between the faucet and the tire will expand and eventually



FIGURE 12.7
(A & B) Petechiae in the upper and lower conjunctivae of the eyelids as well as on the sclerae (white portion of the eyeball). (C) Tardieu spots seen in areas of dependent livor and commonly seen in lower extremities of hanging victims.

rupture. In the case of compression asphyxia, the ruptures are seen in the capillaries rupturing and creating the small hemorrhages on the skin, called **Tardieu spots** (Figure 12.7C). These spots are not diagnostic of compression asphyxia and only indicate increased vascular pressure with resultant rupture. Tardieu spots can also be seen in the lower legs and feet of a fully suspended hanging victim or in an extremity lying over the arm of a chair.

Positional asphyxia is more subtle and where the position of the body itself causes the impairment of oxygen exchange (Figure 12.8). Note the difficulty in taking deep breaths if your head is flexed with the chin near the chest or if the head is tilted far back. Either direction decreases the ability to exchange oxygen. Another method to produce impaired oxygen exchange by position is if the weight of the body is largely resting on the diaphragm, such as being in an upside-down position. A person's natural instinct is to remove him- or herself from this position if he or she is not in some way impaired.

Examples of impairment include alcohol, drugs, senility, or entrapment by obesity or weakness of the legs or arms. Common examples resulting in positional asphyxia are alcoholics falling off the toilet and becoming entrapped between the toilet and the wall, reaching for something behind a washer or refrigerator and becoming entrapped, or being suspended upside down in a motor vehicle accident with the roof collapsed onto the occupants. An autopsy examination may show minimal to no findings. The key to the diagnosis is awareness by the scene investigator and photographs of the decedent showing the compressed head-to-chest or hyperextension position. Toxicology may give additional clues by revealing acute alcohol or drug intoxication. A medical history investigation can include impaired mobility through use of a cane or even wheelchair. It's not uncommon for a nursing home patient to partially fall out of a chair or wheelchair and becoming asphyxiated by the strap used to hold him or her in the chair.

DROWNING

Drowning is a common situation where a body is found in water but has no diagnostic findings at autopsy. This is referred to as a diagnosis of exclusion, which means other diseases have been excluded as the cause of death, and the only finding is the decedent found within a water environment. It is possible to commit suicide by drowning oneself, as well as to drown in a very shallow amount of water. Older textbooks discuss finding hemorrhaging in the middle ears, water in the sinus cavities, or heavy lungs as those associated with drowning. However, many times these findings are negative, or, even if present, the significance is unknown because they can be seen in other causes of death. After death, water can passively gain entrance to the sinuses, hemorrhage of the ear canals can be seen in other causes of death unrelated to drowning, and heavy lungs are nonspecific. Light, fluffy lungs are also seen in drowning cases and thought to represent a period of spasm of the epiglottis preventing water from entering the lung tissue.


Inhalation
Exhalation
Compromised inhalation with lung trauma
Intercostal muscles
Air flow
Lungs
Ribs
Diaphragm
Air flows into lungs due to increased lung volume following contraction of diaphragm and intercostal muscles
Air expelled from lungs due to relaxation of diaphragm and intercostal muscles
When trauma to the lung occurs, and intrathoracic pressure is increased, lung expansion becomes compromised
A



FIGURE 12.8
(A) Diagram depicting normal breathing and the effects of lung trauma as well as the role of the diaphragm and intercostal muscles in moving air into and out of the chest. (B) Positional asphyxia where extension of the neck and head posteriorly as well as weight on the chest prevents proper respiratory chest expansion for exchange of oxygen/carbon monoxide.

Diatoms are small microscopic particles found in bodies of water and historically have been related to the diagnosis of drowning when found in quantities within the lung tissue. This too is not thought to be diagnostically significant. Salt concentrations in blood were also thought to be significant in seawater drownings. This too has not been found to be diagnostically significant.

Scene findings important to establish are witness accounts describing the course of events as to how the person came to be in the water. Information about ability to swim, environmental conditions (ice, darkness, from shore or a boat, while crossing an ice surface), alcohol use, etc. are all useful. Examination of the decedent may show swimming attire, street clothes, or heavy outdoor clothing.

Suicide may also be a motive in unwitnessed events. Some can be quite dramatic with cinder blocks attached to the feet and the hands bound. It is important to treat these cases as a possible homicide until further background information can be obtained.

Artifacts associated with drowning include washerwoman effect of the hands and feet. This appears as washed-out wrinkling of the hands and feet similar to that seen in living persons. The skin is very fragile and easily damaged so it needs to be protected during transit since fingerprints may be needed for identification. The extensive wrinkling is challenging and patience is required to get good fingerprints. This may require subcutaneous injection by water, formalin, or a tissue builder (used by funeral homes in embalming) to remove the wrinkling. Blotting and wrapping the hands in towels also helps to remove some of the water. See the Appendix for a method for obtaining fingerprints from washerwoman hands.

Body submersion is associated with delayed decomposition but it depends on the water temperature for how quickly a body will precede through the decomposition stages. Initially, the body sinks as water fills the cavities and clothing. As subcutaneous gas formation begins with putrefaction, the body will rise to the surface and assumes the "dead man float" position. This is best described as face down with the hands, face, and legs curved downward into the water, and the lower back at the surface. This position explains fish and crustacean postmortem activity of the distal extremities as they rake along the bottom of a river. Other injuries that can occur are propeller injuries. These are difficult to assess if they occur pre- or postmortem as the blood leaches from the wounds. The lack of blood and vital reaction can make them very pale to visual inspection for making the distinction of them occurring after death or being the cause of death. The length of time for a body to surface will vary with the amount of air in the lungs and body fat, how much clothing the person is wearing, water temperature, and if the person becomes entrapped within rock crevices or underwater obstructions and currents.

Submersion in ice water can preserve a body for many years. The body acquires a special type of decomposition called **adipocere** where the fatty portions become saponified and partially calcified. Adipocere can appear as a damp cheese-like texture to a crumbly dried plaster texture. I can relate a case of a snowmobiler crossing a partially frozen lake that collapsed and the body remains were recovered six years later with an intact torso and organs. The exposed areas showed skeletal exposure with usual decompositional slippage. The areas of preservation were the ones protected from direct exposure by a heavy layer of clothing. The adipocere was very dry and crumbly, requiring a saw to enter the torso cavity.

NOXIOUS GASES

Carbon monoxide

Carbon monoxide is a tasteless, odorless, colorless gas, which means someone can be exposed and not realize he or she is in an environment of increased concentration. Smokers inhale carbon monoxide with levels up to 7–10%. Carbon monoxide preferentially binds to hemoglobin in blood, causing displacement of oxygen from the red cells and resulting in tissue deprivation of oxygen. The tissues most affected by high levels of carbon monoxide are ones with high oxygen demand: the brain and heart. Levels are measured as a percentage of the total hemoglobin in the blood.

Neurologic symptoms of carbon monoxide exposure are progressive confusion, disorientation, and eventually coma with death. Cardiac symptoms include progressive exercise intolerance, shortness of breath, chest pain, cardiac arrythmias, and collapse. Fatal levels are usually encountered greater than 35% up to 70% depending on the underlying health of the individual and length of exposure. Children have a higher metabolic rate and are more susceptible than adults. There have been reported cases of sudden deaths in infants thought to be "crib death" only to have the adults in the house succumb to carbon monoxide poisoning within days after. It is an important consideration in any environment where there is vehicle exhaust in a closed environment, or a wood-burning stove, furnace, or fire item is in use.

Suicide via carbon monoxide poisoning commonly involves either the exhaust being attached to the vehicle compartment by a hose, an obstruction within the tail pipe exhaust system, or the vehicle running inside a closed space. See Figure 12.9.

Other methods are charcoal barbecue grills ignited in a closed space such as a vehicle or small room. To increase the concentration capability, the suicidal



FIGURE 12.9
(A) Car exhaust showing hose connecting to interior compartment. (B) Noting the amount of fuel registering on the car dash is an important investigation notation as well as (C) the position of the keys in the ignition and whether the car was found in the 'on' or 'off' position.

person will utilize tape, towels, or plastic along door or window openings. When a vehicle is used, it is important to note the position of the key in the ignition, amount of gas in the tank, and body position inside the car. It is helpful to look for receipts for charcoal briquettes, grill, hose, or tape items used during the process. Because of the heat generated from the car exhaust and the grill, many of these decedents will be decomposed or have extensive skin slippage. There may also be a component of drug intoxication that may account for a lower than expected carbon monoxide level.

Cyanide

Cyanide is colorless but does exhibit an odor of burned or bitter almonds detectable by 60–80% of the population. The remaining 20–40% do not have the genetic trait and cannot smell it. Cyanide can be inhaled or ingested and is lethal in high concentrations within 10 minutes and estimated to be 35 times more toxic than carbon monoxide [2]. It acts upon cellular metabolic pathways (electron transport system) by irreversibly binding to the iron within the body and inhibiting an enzyme called cytochrome C. This system is important in the utilization of oxygen within a cell and formation of ATP, the cellular energy packets needed for cell functions. Like carbon monoxide, it affects high metabolic organs (brain and heart) most and has similar symptoms of disorientation, chest pain, and sudden collapse. This binding can be very rapid with sudden death, and is the basis of cyanide ingestion portrayed in spy novels.

Cyanide has no common household uses but may be present in the environment in low levels from car exhaust. Industrial uses include fumigation, electroplating, and metal ore harvesting. Both carbon monoxide and cyanide exhibit bright red livor. It has a history of being used in the execution chamber and, in those situations, the concentration is very high, requiring the surface of the body to be hosed down prior to transport to decrease exposure to investigative personnel.

Hydrogen cyanide is also a component formed in burning plastics and manmade materials, and may be a cofinding to carbon monoxide in those succumbing in a house or factory fire.

Hydrogen sulfide

Hydrogen sulfide gas has shown an increasing trend as a method of suicide. Internet how-to postings have been linked to heightened awareness by the public, as well as the easy availability of materials to create it. The websites encourage proposed enlistees to post a note on the door or window to warn responders to beware of the toxic hydrogen sulfide gas. Other warning signs to note are empty buckets or chemical bottles seen through a car or door window. At that point, hazmat needs to respond to deal with the situation and prevent injury to others.

The online recipes actually direct the user in a step-by-step process of mixing the materials, as well as provide the signs and party-hosting suggestions. The chemicals used to make the hydrogen sulfide are easy to find and include toilet and bathroom cleaners (the acid portion) combined with bath salts, pesticides, or detergents (the base portion) [4].

CAVES, FREEZERS, TANKER CAR, OR SILO ASPHYXIA

Deaths in closed environments are hazards to investigators until they are understood. It is important in these situations that all safeguards be utilized to protect the safety of rescue and investigative personnel, as well as to prevent further injuries after the decedent is removed. Unlike a noxious gas, these environments can kill a person by a lack of oxygen in the environment causing an immediate anoxia with rapid collapse. In tanker cars, there may be nitrogen gas present; its presence alone is not lethal because it is present in the air we breathe where it is mixed with oxygen. In a tanker car, it is a closed environment and pure nitrogen may be used to empty the car rendering the environment oxygen deprived [1]. Typically, it is a repair worker who enters the tanker to repair something and suddenly collapses. Other workers may enter in an attempt to render aid and also succumb.

Typically our environment contains 20% oxygen and 78% nitrogen [1]. As concentrations of oxygen decrease, it causes increased work for the heart, which responds by an increasing heart rate and the lungs compensate by increasing the respiratory rate. If the oxygen concentration continues to decrease, the person becomes confused and disoriented, eventually collapsing. This occurs over time if the oxygen concentration slowly decreases. However, if the person drops into a nitrogen-rich environment with low to no oxygen, the effects will be immediate.

Silo asphyxia can also occur due to nitrogen production by the plant material from a recently filled silo. The nitrogen gas is heavier than air and will settle into the base just above the plant material and form a brown haze. The plant material can also form a carbon dioxide-rich environment after a recently filled silo [2]. Workers in these environments should be wary of entering the silo and at a minimum wear a safety harness with a second safety rope attached, as well as have two people outside the silo to extricate the worker if necessary.

Grain bins filled with grain are also hazardous without safety equipment because the dust can disorient the farmer/worker. The grain can collapse and form an unstable crater, creating a situation of mechanical asphyxia [3]. The grain dust is extremely flammable and can ignite and cause explosions.

Freezers and refrigerators have the same properties of being a closed environment where the exchange of oxygen may be impaired due to the environmental concentration. Typically, this occurs to children who may climb into discarded appliances as a hiding place only to lose consciousness and later be found dead. Occasionally, freezers or sealing boxes may be used to confine a prisoner by an abductor. Storage of these appliances or discards are placed facing a wall so the door is unable to be opened.

Caves can have pockets of lethal gases or even low oxygen saturation and also cause death. Other mechanisms are cave-ins where small rooms are created, which can lead to eventual hypoxic environments. This is why in mining accidents there is an urgency to obtain a shaft to trapped miners to pipe in fresh air and replenish the environment.

PHOTOGRAPHIC DOCUMENTATION

In many asphyxia deaths, there is a potential risk to investigative and rescue personnel. It is imperative that the environment be rendered safe prior to entry. Hazmat may be in attendance and can monitor these situations and verify the status of the scene. The history of what transpired prior to the victim collapsing is important to document, as well as any findings monitored by hazmat. Photographs of the position of the decedent and receipts for purchase of gas-forming materials are relevant to determine an intentional event versus an accidental one. Noting the color of livor at the scene is also important. Photographs of the labels of the chemicals used will aid the determination of the identification of the produced or ingested substance. It is a good practice for the investigator to obtain any type of detergent information that the hazmat team may have used on the decedent to wash away any contamination. This is helpful to the pathologist, as he or she needs to also let the toxicology lab know what was used in the event that there is cross-contamination of tissues and/or blood.

SUICIDE VERSUS ACCIDENT

In some cases it can be difficult to determine the manner of death, especially in carbon monoxide deaths. For instance, was the charcoal grill in the room to produce heat on a cold night, resulting in an accidental death, or was it an intentional act to produce the gas? Scene findings are the key to making these distinctions.

The presence or absence of the ligature and the pattern of its furrow on the neck also give an indication of the course of events. If the ligature is absent, it could have been removed by rescue personnel or the family. If the pattern is suggestive of a horizontal pattern, it is more consistent with it being absent due to it being a homicide and removed by the perpetrator.

REFERENCES

[1] Hazards of Nitrogen Asphyxiation Safety Bulletin. U.S. Chemical Safety and Hazard Investigation Board; 2003. Retrieved from http://www.csb.gov/assets/1/19/SB-Nitrogen-6-11-031.pdf. [August 2013].

[2] Upright Silo Safety. University of Maine Cooperative Extension Publication. Bulletin #2305; 2002. Retrieved from http://umaine.edu/publications/2305e/. [August 2013].

[3] Safety and Health Topics: Grain Handling. Occupational Safety and Health Administration, US Dept of Labor. Retrieved from https://www.osha.gov/SLTC/grainhandling/. [August 2013].

[4] Hydrogen Sulfide Suicide Trend-First Responder Safety Update; 2010. Central Florida Intelligence Exchange, Bulletin No. 10-09-31. Retrieved from http://www.hazmatfc.com/incidentReports/statsTrends/Documents/Hydrogen%20Sulfide%20Suicide%20Incidents.pdf. [August 2013].

CHAPTER 13

Special Circumstances

Learning Objectives

- Compare and contrast at least three ways that embalming and cremation alter the body for further investigation.
- A detective from the local agency calls and says a family has accused a caretaker of poisoning their loved one with rat poison containing arsenic. He has investigated and feels there may be some validity to the accusation. The body has been embalmed and buried at the local cemetery. He is asking what the chance of recovery of information might be, as well as what the procedure might be for an autopsy. Outline five items to discuss with the pathologist to return the phone call with further information.

Key Terms

Cremation
Embalming
Exhumation
Conflict of interest
Lethal injection

Chapter Summary

In this chapter various investigation situations are discussed, as well as possible solutions for difficult removals. Also discussed are postmortem disposition issues and scene investigation for in-custody deaths. The various modalities of organ and tissue donation are presented that will provide insight for how it will affect the death investigation in determining the cause and manner of death.

INTRODUCTION

This chapter will discuss multiple unusual, but not necessarily uncommon, death situations an investigator may encounter. The study of these situations prior to actually encountering them or similar situations will give a springboard to troubleshoot for solutions for a body removal or investigation technique. The knowledge will also help the investigator to answer general questions by law enforcement or family members.

CREMATED REMAINS

The **cremation** process involves burning a body at greater than 1,400–1,800°F over a period of two to three hours to reduce the body to ash [1]. At that point, even



FIGURE 13.1
(A) A typical plastic container cremated remains may be stored in. (B) Usually it is lined by a plastic bag to contain the ashes. Identifying tags may be present within the ash remains. It is helpful to X-ray the box prior to opening it to determine if the box contains human identifying materials.

large bones will be brittle and broken but have intact small pieces. Crematoriums generally pass the residual bones through a grinder to also reduce them to fine ash. These cremated remains are then packaged in an urn picked by the next of kin or packaged in a plastic bag inside a square plastic box (usually about 12 × 10 × 5 in.), as shown in Figure 13.1. Inside each box is usually a metal identification tag and the outside usually contains identifying marks. These cremated remains can be stored by the next of kin, buried (with a permit), or scattered (may require a permit). Cremated remains can be shipped, but requirements by the shipping company and local laws may vary and should be verified by each locality. Airlines also ship cremated remains but preauthorization may be required, as well as copies of the death certificate, cremation permit, and any other forms required by Homeland Security or Customs if international [2]. It is best to check with all agencies before assuming remains can be transported and received.

Occasionally these remains are found in a residence, on church steps, or abandoned in other public places. They then fall upon the medical examiner to give final disposition. The issues revolving around this is to confirm whether the remains are human, the identity of the remains, and if there is next of kin who would claim the remains. To make these determinations, it requires the aid of an anthropologist to review the remains to answer at least the first three questions. Many times X-rays may assist with the identification of human artifacts like metal clothing clips or snaps, surgical clips, or hopefully the identification band inside the urn. DNA is destroyed and not able to be retrieved from remains heated to this temperature.

Most house fires approach 750–1,100°F and are not able to reduce adult human remains to the level of incineration seen in a crematorium retort. If an accelerant is used and the fire is stoked over a period of time, a greater percentage of the body can be reduced to ash. The torso is the greatest mass, therefore, even if it is greatly charred on the outside, the majority of the organs and even body fluids may be able to be collected. Infants contain a smaller mass and have little bone and may result in complete incineration at this temperature.

The investigative aspects of these cases will take some true detective work to track down where the deceased originated from and finding next of kin. County tax records may give a clue for a owner who may know information about renters if the remains are found within a building. Discarded remains in public places are very difficult to identify. Remains without identifiers are similar due to lack of clues and very little scientific data to work with.

Disposition of the remains may require assistance from the local county social services agency, which may take control of the disposition for county burial or to assist a family that has no means to make final arrangements. Each state or county has an indigent burial program to assist families with limited means. Public fiduciary or lawyers may close estates where there is no next of kin or appointment of an executor. Power of attorney appointments end at the time of death.

It is important that all county burials falling under the coroner/medical examiner office follow a protocol with a proper chain of custody to the cemetery/funeral home. In addition, the remains should be tagged with identifying wristbands and documentation provided in the investigator's report of the burial plot number. If the policy for disposition of indigents is cremation, it is important that identification measures be undertaken prior to the cremation to ensure the identity of the person, as all information will be gone after.

Cremation authorizations require a permit issued by the local health department, a signed valid death certificate, and, in many states, permission of the coroner or medical examiner that the cause of death is not a reportable case to their office. The latter is hopefully a safeguard to prevent reportable deaths from unnatural causes or homicides to go unreported and investigated.

BURIED BODIES

Clandestine graves are usually associated with a criminal nature as an attempt to dispose of remains in a way they will not be discovered for a period of time, if ever. These cases usually have a great amount of press appeal, especially if they are thought to be associated with a serial killer or have been buried in a noteworthy fashion within a wall, backyard, or basement. John Wayne Gacy was a serial killer of the 1970s in Chicago. He was a contractor and would lure young men to his residence with a promise of work, kill them by strangling them. and then bury them in his crawlspace. Twenty-nine bodies were recovered and a severe stench emanated from the basement. The bodies were in various states of decay and were covered with lime.

Buried bodies decompose much slower than those exposed to air or water, due to lack of exposure to carnivores and insects (Figure 13.2). The rate is further slowed



FIGURE 13.2
(A) A partially skeletonized decedent found in a remote area. (B) After removal to the office screening X-rays of the remains inside the body bag with the clothing intact are helpful to screen for projectiles, knives, or sharp objects. (C) The X-rays may also reveal the presence of dental restorations, which are confirmed upon examination of the maxilla (D). (E) Photography of all property including brands and labels is helpful and important to reference in the file for follow-up phone calls, screening the missing person data-bases, and in case the clothing gets separated from the skeletal remains or is lost over time. Anthropology consultation will assist with sex, race, approximate age, and stature using the skull (F), femur, and grooves on the symphysis pubis (G).

if the body is wrapped in protective plastic or a tarp. Sometimes the perpetrator will utilize lime or other materials that decelerate the decomposition rate [3]. It also depends on how deeply the body is buried, as a very shallow grave may not deter carnivores to a great extent. Indications of a grave site include disturbed plant flora, either dead, newly growing, or in some fashion not matching surrounding plants. The area is usually depressed inward and concave due to the body decomposing and shrinking over time, collapsing the overlying dirt.

Recovery of buried remains can be assisted by a local anthropologist or even archaeologist. If none is available, there may be a member of law enforcement or a fellow death investigator with a particular interest or experience with the recovery of buried remains. Initial recovery can begin with shovels, but as materials become evident, smaller trowels and brushes may be needed. It is best to begin at the periphery of the sunken area and work across the surface with gentle shovel digging. It is helpful to have various-size screens to pan the removed dirt looking for expended cartridges, bullets, teeth, or personal effects. If the remains are relatively fresh or largely intact but decomposed, the recovery is much easier than skeletal remains. In either case the dirt under the body can yield useful clues and should be screened as well, looking for any objects. If the decedent was shot while in the grave or on the ground, the expended bullets may have exited into the ground under the body and can still be recovered.

Case Study

Skeletal remains were discovered by construction crews digging a pathway for a new water canal in a rural county. The remains were extricated from their grave by a local archaeologist and sent to the forensic pathologist for examination. X-rays showed no large bullet fragments within the residual skeletal, but small fragments of lead were seen adherent to the internal skull. Gross examination showed an entrance gunshot wound at the back of the left side of the head with internal beveling. An exit wound was noted on the right temporal scalp, which was the portion lying downward in the grave. When the pathologist inquired where the underlying dirt was from that area, he was told the local archaeologist had recovered it for teaching as it showed a perfect outline of the head within the dirt. When it was returned and the dirt X-rayed, a large bullet was visualized and recovered. It was sent to the crime laboratory for comparison to the ballistics database (Integrated Ballistics Database, or IBIS).

FBI and ATF units are working with gun manufacturers to develop a database of each new manufactured gun and record its serial number with the individual rifling of the lands and grooves as gun fingerprints. This would allow the gun to be traced throughout its lifetime, including who it was sold to and what crimes might be related to one another. The FBI and crime laboratories compile the ballistic characteristics of expended bullets/casings/cartridges into a database and can link them to other crimes committed using the same weapon. This has been made possible because of the increased ability of computers to utilize and compare digital images and scan through thousands of images quickly to make comparisons. The only missing link is to use this information and tie it to a particular weapon rather than just a class of guns. Evidence is typically categorized by similarities within a group called class characteristics (e.g., 9-mm handgun) based on the gun's weight and measurements. Individual markings on the bullet or jacket created by the lands and grooves create individual characteristics that can link a particular bullet to a particular gun. The future database would utilize these individual characteristics to improve crime solving.

EMBALMED BODIES

Embalming is the process of replacing body fluids with formalin as a means of preservation. The embalming fluid is a mixture of 18–35% formalin with multiple coloring agents and glutaraldehyde, which is then mixed with water in a small pump apparatus and injected into the arterial system. Different coloring agents are used depending on the desired end result color of the skin. The blood is drained from the body as the formalin mixture is pumped into the arterial system under pressure. The base of the neck is the site of the usual arterial puncture, which is later sutured and glued closed to prevent leakage. Other areas where incisions can be made to improve preservation are the groins or armpits, especially if there is extensive trauma and poor perfusion. The trunk is the next area embalmed by inserting a large suction trocar needle into the organs and removing any feces, fluids, and food in the stomach. The formalin preserves the body's cells by changing the chemical structure of the cellular proteins, which decreases the ability of bacteria to utilize them and in turn slows decomposition.

Bodies being shipped may require higher formalin concentrations and special permits. International shipping usually requires authorization by a physician that the body contains no known infectious disease. Bodies can be shipped to a medical examiner/coroner without embalming or authorization but are usually placed into sealed metal shipping containers similar to caskets but more durable. These containers prevent leakage of biohazardous body fluids or exposure to pathogens as long as the container is intact, however, they are heavy and bulky, and it is difficult to remove a body because of the deep sides.

FROZEN BODIES

Frozen bodies are difficult to maneuver and transport because their position is not malleable. If possible, the goal is to get the body inside a body bag and transport it to the office where it can be slowly thawed for evaluation. If the body will not fit inside a body bag due to its position, it may be necessary to wrap the body in a plastic shroud or tarp for transport. Usually these bodies require an autopsy and retrieval of toxicology, and until the surface and organs are thawed, this is not possible. The length of time to thaw will depend on the body size and the amount of clothing. It may be possible to cut away any thick layers of clothing if the cause is not suspicious. This will greatly shorten the necessary time interval. Use of small portable heaters blowing across the surface and letting the decedent remain at room temperature overnight (an entire weekend is too long, however) will also shorten the defrosting time. If it is the weekend, the body should be placed into the cooler and can be monitored for thawing during a weekday while personnel are present to observe its progress. If prompt identification is imperative, handheld hair dryers can be used to loosen the upper extremities at the shoulders and elbow to retrieve the necessary prints. A fully frozen body can take up to two to three days to defrost. The skin will assume a yellow parchment decomposition pattern as it thaws and dries.

DISMEMBERED REMAINS

Bodies are dismembered usually to dispose of them more easily, to hide their identification, to slow down the investigation, and occasionally to send a message by delivery of a body part. A body can be found in any degree of dismemberment from a single extremity like a finger, head, or torso, to a nearly complete body with only a single item missing. The greater the dismemberment, the greater the challenge to discover a cause of death, the identity of the decedent, and to find a perpetrator. The location the body part is found will result in a huge grid search of the surrounding area to determine if further body parts can be located.

The environment surrounding the body part site needs to be photographed as it is found and after the body part is removed. This will document the amount of blood loss at the site and help determine if it is the location the dismemberment occurred. Special attention should be paid to shoe and vehicle tracks leading to and from the scene. Any surrounding clothing or personal effects that might be related should be examined for identification clues and collected. If the body part is in a plastic or paper bag/box, it should be carefully handled to retain the surface for possible fingerprinting. Trace evidence on the found body part may be the key in linking an eventual suspect with the decedent and include items such as carpet fibers, saw marks, and hairs. Small body parts should be placed in brown paper bags then inside a body bag for transit. They should be handled as little as possible. Larger body parts can be transported as usual.

Recovered torsos and heads should be X-rayed according to the usual trauma panel for suspicious deaths. Recovery of bullets or identification of orthopedic hardware can be the key to the investigation moving forward. Body amputation sites of the dismemberment require close-up detailed photography to demonstrate any tool marks or skin injuries to aid in the identification of the instrument used (Figure 13.3). After photography, the dismemberment site needs to be excised and preserved by freezing rather than formalin fixation. Databases exist for comparison of these tool markings on bone to potential class characteristics of particular instruments if not individual characteristics to compare to a recovered saw or tool. Obviously the morgue saw will create similar saw marks on the excised margins, so to prevent confusion, they should be marked with an "X" across the excision margin. Dr. Symes at the University of Tennessee has done extensive research on this topic and standardized much of the terminology used to describe these types of cut marks [6].

ENTOMBED REMAINS

Disinterment is removal of bodies from the grave where they have been buried for a length of time. This process can also be referred to as **exhumation**. The removal requires authorization from the family or a court order from a judge plus a permit from the health department in the jurisdiction where the body



FIGURE 13.3
Tool markings that are present on a dismemberment site on a vertebral body. It is important that they be photographed and preserved for possible comparison to a recovered instrument.

is buried. Bodies are disinterred for a number of reasons, including wanting to bury the person in another location or the burial of a second person in the same burial plot, which is allowed in some locations with the stipulation that the one closest to the surface meet all the burial depth requirements. Cremated remains may also be buried in the same burial plot.

Court-ordered exhumations are done if there is a question of the identity of the person in the plot or for further criminal investigation. If the family is not willing to sign for the exhumation, the judge will want to hear a compelling argument as to the purpose of the investigation and what scientific findings will be sought during the examination. Following the authorization, a disinterment permit will be issued by the health department to the cemetery.

Cemeteries keep detailed records of burial plots with each one denoted by a number on an emblem embedded at one end of the plot. Their assistance will be needed to locate the proper plot prior to beginning any digging. The cemetery map and records need to be reviewed by the person in charge of the exhumation to ensure the proper location and chain of custody to the morgue.

Disinterment requires the use of backhoes to open the grave and remove the first few feet of soil. This is followed by hand shoveling to unearth the casket and expose the perimeter for lifting.

Some caskets are buried with a surrounding plastic liner or concrete vault. This preserves the exterior of the casket and prevents cave-ins over time, and makes it easier to unearth a casket. Depending on the water table of the cemetery, some caskets can be under water for periods of time and lose structural integrity, exposing the remains.

Depending on the purpose of the exhumation, the casket and contents may be removed to the coroner/medical examiner office for examination, or in the case of a reburial, transported to its new location. If the casket is no longer usable, a new one will be needed for the remains to be reburied. The condition of the remains will depend on the soil at the burial site, the type of casket and the presence of a liner or vault, the quality of the embalming, the condition of the body at the time of embalming, and the period of time that has elapsed.

To open the lid of a casket, a casket key is needed and can be borrowed from a funeral home. This key is like a small crank that fits into a small opening at the head end of the casket. A body that has been enclosed in an intact casket for an extended period (five to seven years or longer) in good soil conditions and embalming is strikingly recognizable and intact upon the initial opening of the lid. The body may be covered by areas of mold and have a yellow waxy appearance. The inside of the coffin actually forms a micro-environment, keeping the organisms in balance due to the low oxygen level, lack of sunlight, and relatively uniform environmental temperature. However, upon opening the lid, decomposition will occur rapidly with the skin becoming flaccid and green-black discoloration beginning. It is important to collect evidence and photographs quickly after opening the lid. Internal organs will show the usual embalming trocar artifacts and shrinkage. Calcified areas will retain their architecture better longer than soft tissues like the spleen or gastrointestinal tract.

FAMILIES REPORTING POISONING OR MURDER

It is not uncommon for a family member to call the coroner/medical examiner office and an investigator be faced with him or her accusing another family member of having poisoned or murdered the decedent and the case had gone unreported. The decedent may already have been examined (hopefully autopsied with toxicology) or never even been seen by the office. The motive is purported to be for monetary or emotional gain. This is a difficult position because the body may be buried at the time of the report. If the body is not buried or embalmed, the response is much easier and it can be brought to the office for examination and toxicology. If it was examined already, it is best to immediately call the funeral home and put a hold on embalming, burial, or cremation until the death investigator can speak with the attending pathologist. Most state death investigation laws give the investigator the power to take control of the remains as a suspicious death even under family protest. It may be the person in control of making the arrangements who the other family member is accusing. This can become a very sensitive issue and needs to be handled carefully. The family member calling should be directed to the proper law enforcement to voice his or her concerns. Law enforcement will then call the office to verify information and usually will speak with family members. Depending on the information obtained, the investigator may examine the scene for a potential poisoning. It is best to make sure a pill count and identification is done on all medications submitted with the decedent.

The investigation that is associated with the case will help direct what type of poison was used. Some poisons are not easily detected on routine toxicology screens and need to be targeted for diagnosis. It is best to obtain hair samples and fingernail clippings since long-term poisoning, such as arsenic, can be deposited and identified in these samples. Full toxicology is recommended in an effort to answer the questions of the investigation.

Other times families will note elder abuse or lack of care of the decedent as causing the death, sometimes with underlying monetary gain. This is a very difficult determination in the elderly. Many times they have severe underlying cardiac or respiratory disease, general debilitation, or diabetes mellitus, which makes them prone to lying in bed. It can be very difficult in a home-care situation to prevent bedsores (decubitus ulcers) that in some cases can become massive. In these cases where there are medical community or family concerns, the best course of action is to bring the case to the office for review by the pathologist and include photographs with scales of any ulcers, and a general evaluation of the body for cleanliness, height, weight, etc. In cases where the death investigator goes to a scene and there is a concern of negligent care, it is important to note the condition of the sleeping environment, food conditions, and to confiscate all the decedent's medications.

ORGAN AND TISSUE DONATION

Cases falling under the jurisdiction of the coroner/medical examiner are many times young individuals with few underlying diseases, making their organs desirable for transplantation into other individuals. Older decedents may also qualify for donation depending on their health and cause of death. Each state will have outlined the procedure for approaching the family for this donation [5]. Throughout the United States there are nonprofit companies representing eye donation, organ donation, and tissue donation, all separate companies, and each reviewing a case for potential donation. Organ donation requires that the person is still alive and usually is on a ventilator at the time of brain death. Brain death is determined by a standard protocol of two separate evaluations of the decedent by neurologists demonstrating with a physical exam that there is only brainstem function but a lack of awareness and upper cortical function. A negative drug screen for narcotics and a flat EEG (brainwave scan) is needed to declare brain death. The center for cardiac and respiratory function only requires brainstem function but not higher cortical function where consciousness and awareness of surroundings is present.

After someone is declared brain dead, the family may be approached for their desire to contribute the organs to someone else on the list awaiting a transplant. In some states, the medical examiner/coroner is to be contacted prior to the family to review the case and evaluate the needs of the pathologist as to which organs will be needed to certify the cause of death. The pathologist may place certain restrictions as to which organs may be harvested. Most times toxicology samples need to be requested and acquired prior to the donation. Laboratory specimens for blood and urine are usually held on all patients five to seven days after admission (depending on each hospital's policy) and should be requested as well. In some states this request will require a subpoena from the office to the hospital to acquire them. Admission specimens are valuable because they reflect the toxicology status prior to any blood transfusions or dilution by intravenous fluids. These specimens may also be desired by the donation team because they also reflect the best specimens to test for possible infectious diseases that might be transmitted to the potential recipient. The transplant list is searched for a suitable match based on the blood and HLA (histocompatibility) testing of the decedent and the recipient. If the coroner/medical examiner and family have said yes, the donation may proceed with the organs being removed. The request for organs can include heart, lungs, liver, kidneys, pancreas, and small bowel.

Eye donation follows the same procedure of permission. The request is for the cornea portion of the eye but the extraction needs to be performed during the first 24 hours after death because the cells in the eye are very sensitive to drying and deterioration. During this donation, the entire eye may be removed, or at a minimum the cornea portion of it. The vitreous that is normally present will not be present after the donation unless the donor team obtains it during the harvesting procedure. The vitreous will need to be transmitted from them to the medical examiner/coroner office via a chain of custody. If the coroner/medical examiner obtains the vitreous prior to the harvest, it wrinkles the cornea and renders it unsuitable for transplantation.

Tissue donation is also done following the same permission procedure and performed on decedents within the first 24–48 hours after death. Usual requests are for tendons, arteries, veins, bone, or heart valves. This can also take the form of a request for research and other tissues, including internal organs or extremities and head and neck tissue. Harvesting these tissues destroys the ability of the pathologist to retrieve toxicology specimens, so blood and urine need to be obtained from the femoral vessels and transferred under chain of custody to the office. In cases of requests for heart valves, the pathologist will need to have past cardiac history and the scene investigation findings to assess whether the heart is needed intact for evaluation. He or she may deny donation if the valves are needed for the determination of a cause of death. Requests for valves are approved more stringently on a case-by-case basis. Removal of the heart valves also removes the proximal coronary arteries at the takeoff from the aorta where significant atherosclerosis and variants can occur that may cause death. The residual donated tissue is generally evaluated by a cardiac pathologist provided by the donation company. They will generate a report from the cardiac pathologist that can be supplied to the medical examiner/coroner office. However, the evaluation will not include this vital area since that removal is performed by a technician prior to the cardiac pathologist seeing it. This area can be the key to the cause of death. To wait and hope for a positive toxicology as a cause of death may result in the real cause of death being overlooked. There are many potential causes of death in a case but only *one* real cause of death, and it is the job of the forensic pathologist to render an opinion to the best of his or her ability about the cause. This conflict between donation and retention of organs can lead to strife between the organ procurement agency and the coroner/medical examiner office.

SPECIAL REMOVALS

Some bodies are either very messy or difficult to remove from the position of death. Decomposed bodies have smelly fluids in skin blebs and surrounding them, and maggots and insects may be present. These cases need some care to get the body into a body bag without splashing fluids on clothes. It is helpful to cover the body with a sheet and tie it in place if possible. Position the stretcher with a body bag over the top, grab the body by an arm, and slide it into the bag. If it is necessary to get the outside of the bag dirty by placing it on the floor or ground, it will be necessary to have a second bag nearby to place the decedent in. The body bags are not impermeable and can leak through a cloth zippered area, and lightweight bags tear very easily. The insects also seem to be ingenious in their escaping bags, even in refrigeration. Double bagging may be necessary even inside heavy-duty bags.

Distant removals over rough ground can be done with heavy-duty body bags that have sown-in handles. Depending on the weight, two to four people may be necessary, one on each corner, to remove it to a stretcher that can then be placed inside the removal vehicle. These same bags are useful if there are fragments of glass or metals that may penetrate the usual bag, such as in motor vehicle and airplane accidents.

Decedents positioned in a car are similar to those sitting in a chair. If it is a bloody situation, a sheet, towel, or whatever is available over the front of the decedent will protect everyone as the person is moved. The stretcher can be placed adjacent to the vehicle with the body bag over the top, an arm grasped, and twist the body as if the person was getting out of the vehicle with the legs toward the bottom end of the bag. The body can then be maneuvered onto the stretcher without having to lift it.

Decedents totally or partially in bed are relatively easy as they can be slid directly onto the stretcher that has the bag over the top.

Babies and children dead at a scene or hospital room can be an emotional situation as the parents are nearby. It is important to be as respectful of their feelings as possible and also be cognizant that hospital staff is also very sensitive to this situation. If at all possible, ask the family to step outside while placing the child in a body bag, and wrap a sheet over the top of the body bag. The child can then be lifted onto the usual stretcher and covered, or small infants can be placed into a small basket. When placed into the removal vehicle, the child's body can be transferred onto a stretcher. It is important to have support from law enforcement during the removal phase because families can be very emotional and a scenario may develop that can become threatening. Again, situational awareness is very important at all scenes, but especially with children involved.

Hangings can be challenging because they have all or at least a portion of their weight on the noose. It will take more than one person for the removal and usually, but no more than three. One person will need to use the bolt cutters or knife to cut the noose and the one or two other people to support the decedent under the arms. The decedent's own body weight can be used to ease him or her into an adjacent body bag. It is best to cut the noose in the mid-region, and if duct tape is nearby or in the investigator bag, to encircle the proposed cut site first then cut in the middle of the tape to prevent fraying of the ends (see Chapter 12). A similar approach can be used at the point where it is attached to the suspension point (beam, tree limb, closet rod) and cut again at the circled tape. The entire noose needs to be submitted with the body for the pathologist to review. In cases where the decedent is decomposed, it can be useful to take a body bag and put the decedent's feet in it, have someone else hold the body bag, and have someone zip the bag up all the way until the head is covered inside the bag. Cut the noose and slip it inside the bag. This keeps the mess to a minimum.

Bodies in lakes, rivers, or canals are water soaked and placing a bag in the water does not work. If this is common in your jurisdiction, special mesh tarps can be used to float the decedent on top of the water and lift the body out into a bag. Because huge amounts of water are in and on the body, the bag will become water logged, therefore either two bags are necessary or a heavy-duty one. It is also advisable to take clear photos of the face and any identifying tattoos. These bodies will rapidly decompose once out of the water, with the body not being able to be viewed or the tattoos obscured and unavailable for identification. The hands should be evaluated for possible prints at the same time because they will slough and the surface becomes like gloves of skin. If possible, prior to removing the body from the water, photograph the decedent in the water. The photographs do not have to be taken underwater.

PRISONERS AND EXECUTIONS

Removals from a jail, penitentiary, or even at a law enforcement arrest scene present some unique hurdles. Entrance into a jail or penitentiary requires photo identification, usually a driver's license and an office identification. If the investigator's office is one that allows carrying firearms or knives on the job, those will need to be checked at the admission window. It is important to take stock of all pens, pencils, and other objects an investigator has on his or her person and ensure they are taken back out so they are not made into shivs by other prisoners. The jail or prison personnel will have cleared an entry and exit point from the site of admission to the body and back and will escort the investigator through the building to the site. The other prisoners have usually been placed in lockdown to prevent any issues. It is important for the investigator to show up in full uniform and not casual clothes.

If the death occurs at a law enforcement arrest scene, the situation can be quite volatile and it is important to be cognizant of surrounding bystanders. Tensions may be running high among law enforcement and the community, so it is important to be organized, systematic, and gather the needed data for removing the body as soon as possible. Many times after the body is gone from sight, tensions will start to abate. There may be multiple agencies attending the scene as well as multiple high-ranking officials, depending on the situation. Most agencies have a protocol for in-custody deaths that calls for an outside law enforcement agency to investigate to prevent a question of **conflict of interest**. The coroner/medical examiner office may also have a policy that a forensic pathologist responds to these scenes with the death investigator. It is important for the death investigator as an additional representative from an outside agency to be diligent about photographing the scene, the decedent, any restraints used, and aspects of the scene related to how the person was initially found. If he or she was found hanging in a cell, the noose needs to be photographed and the point of suspension. If the decedent became unresponsive in the back of a patrol car, his or her position in the car needs to be known and appropriate measurements taken, especially if it was the floorboard area. Any emesis, pills, or clothing needs to be photographed, and necessary items collected. Special attention for photographs of the head, neck, and upper extremities are in order. If restraints are still in place at the time of the investigator's arrival, they need to be left in place and the decedent transported as-is to the office. If the death occurred in an interview or restraint room, then overall photographs of the entire scene from multiple vantage points need to be taken, as well as the usual medium and close-up views.

If an officer was involved during an altercation during the arrest, he or she may not be willing to discuss it with the investigator and request a lawyer or union representative be present during any statements. The outside agency will be able to assist the death investigator with obtaining the information needed to relay to the pathologist for evaluation. Most times the outside agency also attends the autopsy to confer with the pathologist. The case is worked like a homicide with full-body X-rays, dirty and clean photographs, evidence collection, and a full autopsy with toxicology.

In executions, the decedent will usually be in the execution chamber. Sometimes the prison has placed the person into a body bag and has cleared the chamber.



FIGURE 13.4
(A) The gas chamber used by the state of Arizona. (B) The gurney used for lethal injections [4].

In those cases, it is important to do site photography of the body to document any injuries or absence of them. In other cases, the decedent may still be strapped to the execution table with IVs attached. Photographs are obtained, followed by closing all the intravenous bag valves and placing them into the bag with the decedent, including empty bags. Most executions are now done by **lethal injection** but in the past, the gas chamber with hydrogen cyanide gas was another method used (Figure 13.4a). Because the gas is toxic and deposits are formed on the skin surface, the body was hosed down prior to removal in two body bags to prevent diffusion of the gas into the cooler or removal vehicle. Other states used to perform death by firing squad, hanging, or electrical chair, but these have been deemed cruel and heinous punishment and no longer used.

Lethal injection is accomplished by intravenously injecting a barbiturate to induce sleep followed by a neuromuscular blocking agent, such as succinylcholine or pancuronium, which causes paralysis of skeletal and smooth muscles including the diaphragm (Figure 13.4b). This is followed by potassium chloride to cease heart function. The person is then monitored for death and pronounced by medical personnel at the scene. The execution is usually witnessed by invited members such as law enforcement, lawyers, and family members.

DEATH IN THE LINE OF DUTY

A topic that many of us dread are those of personnel dying in the line of duty, including law enforcement officers, firemen, and military personnel. These can be someone known to personnel within the office. Many times they are in uniform, which can make it even more difficult. All clothing and items on the body at the time of death need to remain on the decedent as any other case. Guns may be removed or any other hazards such as shock grenades. If bullets have penetrated gun magazines, they also need to be removed. Bullet-proof vests and clothing need to remain on the body or brought to the autopsy for examination.

These deaths are usually accompanied by an escort of officers. Most times it is after the autopsy and at the time of release and will include a color guard and full police escort to the funeral home. Sometimes, especially in deaths of police officers, they will wish to maintain a guard status by the decedent. This may require the chief coroner or medical examiner to authorize outside personnel to remain in the building after hours. Sometimes a compromise can be reached by the guard outside the door and draping of the body bag with a flag. These bodies should be placed into heavy-duty bags and sealed to prevent any type of alteration while awaiting autopsy. The forensic pathologist on call should be contacted to see if he or she would like to go to the investigation scene or hospital to lend support from the department.

These cases can be very difficult technically and emotionally. Typically, a detective and the agency's photographer not well known to the decedent will attend the autopsy and that fact verified before attendance. The issue of conflict of interest should be addressed early, and if there are any doubts, the investigator's supervisor and/or forensic pathologist needs to be consulted. Many times multiple officers and the officer's upper management may want to participate in the investigation. This can get political, yet privacy of the decedent and the ability to focus on the job needs to be a high priority. Too many people attending an autopsy can be very distracting to the pathologist. It may be necessary to arrange extra personnel to meet with the pathologist in a conference room area after the completion of the autopsy to review findings. Press calls may inundate the investigator and his or her supervisor may be able to assist with a press statement. It is easiest to direct press personnel to the law enforcement public information officer for any information. This prevents "leaking" sensitive information unknowingly about the investigation. Typically law enforcement, chaplains, or military superiors will make or greatly assist with notification in these cases. It is a good idea to keep a new packaged flags within the office for this purpose.

DEATH OF OFFICE PERSONNEL OR FAMILY MEMBERS

This also can be a very difficult scene investigation and follow-through within the office. It usually requires involvement of the investigator's supervisor and/or the chief coroner/medical examiner. To avoid issues of cover-ups and conflict of interest, the body may need to be transported to another office. If the decedent is known to morgue personnel, the body may not be able to be housed within the office and will require early intervention to make these decisions. This will largely depend on the scenario and course of events that transpired leading to the death. Homicide, suicide, accidental, or even natural deaths can be suspicious just because of the knowledge of the personnel involved in the death investigation. If the investigation is managed by the office, the file will need to have restricted access to protect privacy. Any family-related personnel should be given time off until the body is released to a funeral home. Full toxicology should be retained and sent to the laboratory, as well as photographs of any injuries. If the decision is made to manage the case within the office, morgue personnel will need to be on a volunteer basis depending on the identity of the decedent and his or her relationship to the office.

DISASTER SITUATIONS

Each jurisdiction has its own capabilities to deal with a certain number of casualties in a short period of time. The number of casualties can vary and will depend on the maximum occupancy of the morgue cooler and personnel who are available. When that is exceeded, it can be a disaster regardless of size. If the cooler can only handle 2 bodies and a bus accident kills 10, the situation suddenly becomes an immediate issue and will require acquisition of resources. Large offices can deal with these fluctuations and a disaster for them may be a single incident greater than 50 decedents.

The role of the investigator is to have knowledge of the office capabilities and, when exceeded, to contact a supervisor for assistance with coordination of further resources. Sometimes local funeral homes' refrigerators can be utilized or, in larger numbers of deaths, refrigerated semi-trucks can be acquired. Federal resources are also available through the Federal Emergency Management Agency (FEMA), National Transportation Safety Board (NTSB), or even military bases with their Grave's Registration Service. State coroner or adjacent medical examiner systems will also lend assistance and have contingency plans that can be initiated.

Knowledge about what is available is usually within each jurisdiction's procedure manual or through participation in mock drills. It is important to get feedback about the drills so faulty areas can be addressed within a department. The types of disasters that need preparation vary widely from aircraft or train accidents to weapons of mass disaster, including bombs and chemical or biological agents. The investigator may be the first called and enter the area to assess the issue. It is important in these deaths to remember the principles of protection of oneself and responding personnel to prevent further injury by exposure to continued hazards.

Key issues for evaluating decedents in these situations are identification, connecting dismembered remains and their personal effects for eventual return to the family, establishing a cause of death, and aiding investigation techniques to determine the cause of the incident. This may require marking the scene into grids with extensive documentation. This will take a large amount of time, so perimeter safeguards will be necessary to prevent intrusion by press or inquisitive onlookers. Families worried about their next of kin may inundate the phone capabilities of the office. Volunteers may be needed to record contact information and phone numbers. Resources such as body bags, gloves, and biohazard bags may be depleted, so contingency plans will be needed to enlist supplies. Entire courses on mass disaster management are available and further training may be necessary for the investigator to be best prepared.

REFERENCES

[1] Cremation FAQ. National Funeral Directors Association; 2013. Retrieved from http://nfda.org/planning-a-funeral/cremation/160.html#hot. [August 2013].

[2] Transport of Cremated Remains. Cremation Association of North America; 2012. Retrieved from http://www.cremationassociation.org/?page=Transport. [August 2013].

[3] Schotsman EM, et al. Effects of Hydraged Lime and Quicklime on the Decay of Buried Human Remains Using Pig Cadavers as Human Body Analogues. Forensic Sci Int 2012;217(1-3):50–9. doi:10.1016/j.forsciint.2011.09.025. Epub 2011 Oct 24. Retrieved from http://www.ncbi.nlm.nih.gov/pubmed/22030481. [August 2013].

[4] Arizona Death Penalty History. Arizona Department of Corrections; 2013. Retrieved from http://www.azcorrections.gov/adc/history/History_DeathPenalty.aspx. [August 2013].

[5] State Organ Donation Legislation. US Dept of Health & Human Services; 2011. Retrieved from http://www.organdonor.gov/legislation_micro/. [August 2013].

[6] Symes S, et al. Knife and Saw Toolmark Analysis In Bone: A Manual Designed for the Examination of Criminal Mutilation and Dismemberment. Symes-National Institute of Justice Grant #2005-IJ-CX-K016/ National Forensic Academy/Forensic Science Foundation; 2010. Retrieved from http://www.crime-scene-investigator.net/KnifeAndSawToolmarkAnalysisInBone.pdf. [August 2013].

Appendix



CHAIN OF CUSTODY

Decedent's Name: ______________________________

Coroner Case Number: ______________

Date of Death: ______________

Receipt of the following items is acknowledged (list each item):

1. ______________________________
2. ______________________________
3. ______________________________
4. ______________________________
5. ______________________________
6. ______________________________
7. ______________________________
8. ______________________________
9. ______________________________
10. ______________________________

Signature of person/agency receiving: ______________________

Print Name: ______________________________

Signature of person releasing: ______________________

Print Name: ______________________________

Date and time of exchange: ______________________

Date and time returned: ______________________

Reason: (optional) ______________________

FIGURE A.1
Two examples of chain of custody intake forms or worksheets.



CHAIN OF CUSTODY

DATE ____________ ML # ____________

NAME ____________ AGENCY/# ____________

FROM TO

____________ ____________TIME ______ DATE ______

____________ ____________TIME ______ DATE ______

____________ ____________TIME ______ DATE ______

FIGURE A.1, cont'd



CASE #

DATE / TIME

Death Investigator:

DECEASED NAME LAST FIRST MI SEX

DEC. ADDRESS

CITY/ST ZIP PHONE

AGE DOB RACE HGT WGT HR EYES

DRIVERS LIC.# STATE SSN# MARITAL STATUS VET.

OTHER ID AKA

SCARS MARKS TATOOS

IDENTIFIED BY RELATIONSHIP

DECEASED DENTIST ADDRESS PHONE #

DATE OF DEATH TIME OF DEATH DEATH PRONOUNCED BY

PLACE OF DEATH ADMISSION DATE/TIME

DEC. FOUND BY DATE/TIME

INCIDENT LOCATION DATE/TIME

AMBULANCE RESPONSE ☐ YES ☐ NO COMPANY PHONE

NEXT OF KIN DOB RELATIONSHIP

ADDRESS CITY STATE ZIP PHONE #

NOTIFIED: DATE/TIME NOTIFIED BY

NEXT OF KIN DOB RELATIONSHIP

ADDRESS CITY STATE ZIP PHONE #

NOTIFIED: DATE/TIME NOTIFIED BY

INVESTIGATING AGENCY AGENCY CASE NUMBER

INVESTIGATING OFFICERS PHONE #

MVA-POSITION ON VEHICLE RESTRAINT

AIR BAG DEPLOYED M/C, BICYCLE HELMET

CHILD RESTRAINT EJECTED

DECEASED TRANSPORTED TO: ☐ OFFICE ☐ MORTUARY HOLD ☐ YES ☐ NO

MORTUARY CITY PHONE

AUTHORIZED BY RELATIONSHIP

PERSONAL PROPERTY TAKEN LOCATION

SEAL # SEALED BY AGENCY

VEH. LIC. # & STATE AGENCY STORED VEH.

PRIMARY CARE PHYSICIAN CONTACT #

PMHx:

MEDS:

AUTOPSY X-RAYS DENTAL FINGERPRINTS PHOTO

COUNTY CREMATION COUNTY BURIAL PA REFERRAL DATE

FIGURE A.2
Two examples of investigative report forms.



DATE RPTD.

RPTD. BY

TRANSPORT

TIME RPTD. /

TIME COMPLT. /

FIELD AGENTS /

DOCTOR

INVESTIGATOR

COUNTY PROCEDURE DATE FORENSIC ANTHRO DENTIST

CASE NUMBER

NAME FN MI LN

ALIAS M S W D OCC

ADDRESS CITY STATE ZIP

DOB AGE RACE SEX S.S.N.

HT (cm) (inches) WT (kg) (lbs) HC EC

NOK FN LN *REL* PHONE

ADDRESS CITY STATE NOTIFIED Y N

ID (MEANS & NAME)

LOCATION FOUND

REASON ME CASE

MED. HX

MEDS.

AGENCY CASE # OFFICER

INJURY LOCATION WORK Y N

DATE TIME DRIVER PASSENGER PEDESTRIAN

WHERE DID DEATH OCCUR? HOSP. ER OR INPT AT SCENE UNKNOWN

LSA DATE TIME LOC. BY

FD. DATE TIME LOC. BY

PRN. DATE TIME LOC. BY

FUNERAL HOME BY RELATION

PHOTOS: OME ID Y N EXAMINATION OME Y N AGENCY Y N

FINGERPRINTS: PALMS FOOT RADIOGRAPHS

RELEASED BY RECEIVED BY

FIGURE A.2, cont'd

DATE MEDICATIONS LOG ML#

NAME

ITEM# PRESCRIPTION# MEDICATION
PHARMACY PHONE# DOCTOR
DATE FILLED NUMBER REMAINING NUMBER ISSUED
COMMENTS/DOSAGE

ITEM# PRESCRIPTION# MEDICATION
PHARMACY PHONE# DOCTOR
DATE FILLED NUMBER REMAINING NUMBER ISSUED
COMMENTS/DOSAGE

ITEM# PRESCRIPTION# MEDICATION
PHARMACY PHONE# DOCTOR
DATE FILLED NUMBER REMAINING NUMBER ISSUED
COMMENTS/DOSAGE

ITEM# PRESCRIPTION# MEDICATION
PHARMACY PHONE# DOCTOR
DATE FILLED NUMBER REMAINING NUMBER ISSUED
COMMENTS/DOSAGE

ITEM# PRESCRIPTION# MEDICATION
PHARMACY PHONE# DOCTOR
DATE FILLED NUMBER REMAINING NUMBER ISSUED
COMMENTS/DOSAGE

ITEM# PRESCRIPTION# MEDICATION
PHARMACY PHONE# DOCTOR
DATE FILLED NUMBER REMAINING NUMBER ISSUED
COMMENTS/DOSAGE

FIGURE A.3
Medications log sheet for documenting decedents medications prior to disposal.



Agency
Detective
Agency Case Number:

UNIDENTIFED PERSON WORKSHEET

Case No. ____________________

Name			DOB:
Est. Age Yrs.	Sex Male// Female // Unknown	Date of Death	
Location Found		Date of Examination	Time hours

Clothing	
Body Length inches	Body Weight pounds
Nourishment Normal // Thin // Obese	Body Preservation Good // Decomposed// Skeletal
Body Length inches	Body Weight pounds
Hair Color and Length Gray // Brown// Black//Blonde // Red Balding ____ cm.	Head & Neck Beard: Brown // Black // Gray Stubble or _____cm Moustache: Tattoos
Eyes Blue// Brown // Hazel // Indeterminate	
Teeth Natural: Restorations: Yes or No Edentulous	Dentures: Yes or No Full Partial
Trunk—Anterior Tattoos:	Trunk—Posterior Tattoos: Scars:
Upper Extremities Tattoos:	Lower Extremities Tattoos:
Jewelry	Toxicology Samples Taken Vitreous/ Urine / Blood/ Liver / Muscle

MANNER OF DEATH

NATURAL ☐
ACCIDENT ☐
SUICIDE ☐
HOMICIDE ☐
UNDET. ☐
PENDING ☐

CAUSE OF DEATH

(a)____________________
DUE TO or as a consequence of:
(b)____________________
DUE TO or as a consequence of:
(c)____________________

OTHER SIGNIFICANT CONDITIONS:
____
____
____

NOTES:

Dental	Y	NA	Fingerprints	Y	NA
Anthro	Y	N	Photos	Y	N
X-rays	Y	N	NCIC NAMUS	Y Y	N N

____________________ ____________________
signature *date*

Identified by:
Prints
Dental
DNA
ID DATE:
Released:

FIGURE A.4
Unidentified person worksheet.



DATE ______

ML # ______

NAME ______

PERSONAL EFFECTS RECEIPT

CLOTHING

MEN	WOMEN
HAT ______	HAT ______
COAT ______	COAT ______
SHIRT ______	BLOUSE ______
PANTS ______	SKIRT/PANTS ______
SUIT ______	DRESS ______
UNDERSHIRT ______	BRA ______
UNDERSHORTS ______	PANTIES ______
SOCKS ______	STOCKINGS ______
SHOES ______	SHOES ______
BELT ______	BELT ______
OTHER ______	OTHER ______

KEYS ______

☐ WALLET ______ ☐ PURSE/HANDBAG ______ ☐ CHECKBOOK ______

CONTENTS ______

JEWELRY

WATCH ______

RINGS ______

EARRINGS ______

GLASSES ______

NECKLACES ______

BRACELETS ______

OTHER ______

MONEY

BILLS		COINS	
$100	______	$1.00	______
50	______	.50	______
20	______	.25	______
10	______	.10	______
5	______	.05	______
1	______	.01	______

TOTAL ______

OTHER ______

SEALED IN BODY BAG ☐

NO PROPERTY ☐

TRANSPORT ______

VERIFIED ______

DATE ______ TIME ______

RELEASE OF PERSONAL EFFECTS

PROPERTY	RECEIVED BY	RELEASED BY	DATE/TIME

FIGURE A.5
Two examples of (A) personal effects receipt and more generic (B) property receipt.



PROPERTY RECEIPT

Date: ____________________

Name of Deceased: ____ Case # ____________________

PROPERTY: ____ Received ________

Amount			Total	Received
$ 0.01 x	______	=	0.00	______
$ 0.05 x	______	=	0.00	______
$ 0.10 x	______	=	0.00	______
$ 0.25 x	______	=	0.00	______
$ 0.50 x	______	=	0.00	______
$ 1.00 x	______	=	0.00	______
$ 2.00 x	______	=	0.00	______
$ 5.00 x	______	=	0.00	______
$ 10.00 x	______	=	0.00	______
$ 20.00 x	______	=	0.00	______
$ 50.00 x	______	=	0.00	______
$ 100.00 x	______	=	0.00	______
		Total =	0.00	______

Checks:	Amount	Received
______________	$______	______
______________	$______	______
______________	$______	______
______________	$______	______

Signature, Person releasing property

Witness

Signature, Person receiving property

Date / Time By

Print Name

Relationship to the decedent (Mortuary, Family, Etc.)

FIGURE A.5, cont'd



Per ARS §36-2293, completion of this form is required for any death investigation of children younger than 12 months of age.

Page 1 of 4 (rev. 3/17/10)

Infant Death Investigation Checklist

Arizona Report Form, Version 1.0

Mail or fax completed forms to:
County Office of the Medical Examiner
(fax numbers at the bottom of this page)
Arizona Department of Health Services
(fax: 602-542-1843)

CHILD

Name:
SSN:
Home Address:
Incident Address:
Date of Birth:
Date of Death:
Estimated Time of Death:

MOTHER OR CAREGIVER #1

Name:
Other Names Used:
SSN:
Address:
DL#:
Date of Birth:
Other States Where Resided:
Telephone (include area code):
Smoker? ☐ No ☐ Yes
Evidence/History of Substance Use? ☐ No ☐ Yes ☐ Last 24 Hours ☐ Unknown

FATHER OR CAREGIVER #2

Name:
Other Names Used:
SSN:
Address:
DL#:
Date of Birth:
Other States Where Resided:
Telephone (include area code):
Smoker? ☐ No ☐ Yes
Evidence/History of Substance Use? ☐ No ☐ Yes ☐ Last 24 Hours ☐ Unknown

CAREGIVER AT TIME OF DEATH (if other than parent)

Name:
Other Names Used:
SSN:
Address:
DL#:
Date of Birth:
Other States Where Resided:
Telephone (include area code):
Smoker? ☐ No ☐ Yes
Evidence/History of Substance Use? ☐ No ☐ Yes ☐ Last 24 Hours ☐ Unknown
Relationship to child:
How long cared for child:

CAREGIVER(S) AT TIME OF DEATH INFORMATION

1. Primary Caregiver
Column 1:
Secondary Caregiver
Column 2:

One Two
☐ ☐ Biological parent
☐ ☐ Adoptive parent
☐ ☐ Step parent
☐ ☐ Foster parent
☐ ☐ Mother's partner
☐ ☐ Father's partner
☐ ☐ Grandparent
☐ ☐ Sibling
☐ ☐ Other relative
☐ ☐ Friend/Neighbor
☐ ☐ Unknown
☐ ☐ Daycare Provider
    ☐ Licensed
    ☐ Unlicensed
☐ ☐ Other Specify:

2. Caregiver(s) age in years
One Two
___ ___ # years
☐ ☐ Unknown

3. Caregiver(s) Sex:
One Two
☐ ☐ Male
☐ ☐ Female
☐ ☐ Unknown

4. Caregiver(s) employment status:
One Two
☐ ☐ Employed
☐ ☐ Unemployed
☐ ☐ On disability
☐ ☐ Stay-at-home
☐ ☐ Retired
☐ ☐ Unknown

5. Caregiver(s) substance use history
One Two
☐ ☐ No
☐ ☐ Yes
☐ ☐ Unknown

If yes, check all that apply
☐ ☐ Alcohol
☐ ☐ Cocaine
☐ ☐ Marijuana
☐ ☐ Methamphetamine
☐ ☐ Opiates
☐ ☐ Prescriptions
☐ ☐ Over the counter
☐ ☐ Unknown
☐ ☐ Other, Specify:

6. Caregiver(s) have prior child death:
One Two
☐ ☐ No
☐ ☐ Yes
☐ ☐ Unknown

If yes, cause(s)
Check all that apply
☐ ☐ Abuse #___
☐ ☐ Neglect #___
☐ ☐ Accident #___
☐ ☐ Suicide #___
☐ ☐ SIDS #___
☐ ☐ Unknown #___
☐ ☐ Other #___

MEDICAL EXAMINERS OFFICE FAX NUMBERS

Apache	**(520) 243-8610**
Cochise	**(520) 452-1011**
Coconino	**(928) 679-8798**
Gila North/South	**(520) 243-8610**
Graham	**(520) 243-8610**
Greenlee	**(520) 243-8610**
La Paz	**(520) 243-8610**
Maricopa	**(602) 506-1546**
Mohave	**(928) 505-5889**
Navajo	**(520) 243-8610**
Pima	**(520) 243-8610**
Pinal	**(520) 243-8610**
Santa Cruz	**(520) 243-8610**
Yavapai	**(928) 771-3504**
Yuma	**(928) 336-7319**

FIGURE A.6
(A) Infant death investigative form from Arizona.



Per ARS §36-2293, completion of this form is required for any death investigation of children younger than 12 months of age.

Page 2 of 4 (rev. 3/17/10)

Infant Death Investigation Checklist

Arizona Report Form, Version 1.0

Mail or fax completed forms to:
County Office of the Medical Examiner
(fax numbers at the bottom of page 1)
Arizona Department of Health Services
(fax: 602-542-1843)

Incident State:	**Was 911 or local emergency number called?**	**CPR performed before EMS arrived?**	**During resuscitation was child:**	**EMS responded to scene?**	**Child's activity at time of incident, check all that apply:**	**Total number of deaths at incident event:**
☐ Arizona ☐ Other, Specify **Incident County:**	☐ N/A ☐ No ☐ Yes ☐ Unknown	☐ N/A ☐ No ☐ Yes ☐ Unknown	☐ Injured ☐ Shaken ☐ Jostled ☐ Other, specify:	☐ N/A ☐ No ☐ Yes ☐ Unknown	☐ Sleeping ☐ Playing ☐ Working ☐ Eating ☐ In vehicle ☐ Unknown ☐ Other Specify:	Children (Ages 0-18): Adults: ☐ Unknown

What led someone to check on the infant? ______________________________

Who was in the home when the child was found? ______________________________

Describe child's appearance when found:	**No**	**Yes**	**Unknown**	**Describe/specify location:**	**First Assessed by:**
Discoloration around face/nose/mouth	☐	☐	☐		☐ EMS
Secretions (foam, froth)	☐	☐	☐		☐ ER
Skin discoloration (livor mortis)	☐	☐	☐		☐ PD
Pressure marks (pale areas, blanching)	☐	☐	☐		
Rash or petechiae (small, red blood spots on skin, membranes, or eyes)	☐	☐	☐		
Marks on body (scratches or bruises)	☐	☐	☐		
Infant moved prior to being found	☐	☐	☐		

Time frame information:

_____ **Time Found** _____ **Last Seen Alive** _____ **Time Police Called** **Call Type** ☐ **911** ☐ **Regular** ☐ **Other, specify:** _____

_____ **Last Feeding Time** **Person Calling** _____

What did the child feel like when found? (check all that apply)

☐ **Sweaty**
☐ **Limp, flexible**
☐ **Other, Specify:**
☐ **Warm to touch**
☐ **Rigid, stiff**
☐ **Cool to touch**
☐ **Unknown**

Surface body temperature:

Temperature at hospital:

SUFFOCATION/ASPHYXIA

A. **Type of Event**

☐ Suffocation, go to **B**.
☐ Strangulation, go to **C**.
☐ Choking, go to **D**.

B. If suffocation/asphyxia, action causing event:

☐ Sleep-related (e.g. bedding, overlay, wedged)
☐ Covered in or fell into object, not sleep related
☐ Plastic bag
☐ Dirt/Sand
☐ Unknown
☐ Other, Specify:
☐ Confined in tight space
☐ Refrigerator/freezer
☐ Toy chest
☐ Automobile
☐ Trunk
☐ Unknown
☐ Other, Specify:
☐ Swaddled in tight blanket, not sleep related
☐ Wedged into tight space, but not sleep related
☐ Asphyxia by gas
☐ Unknown
☐ Other, Specify:

C. If strangulation, object causing event:

☐ Clothing
☐ Blind cord
☐ Car seat
☐ Stroller
☐ High chair
☐ Belt
☐ Rope/string
☐ Leash
☐ Electrical cord
☐ Automobile power window or sunroof
☐ Unknown
☐ Other, Specify:
☐ Person

D. If choking, object causing choking:

☐ Food, Specify:
☐ Toy, Specify:
☐ Balloon
☐ Other, Specify:
☐ Unknown

OTHER CIRCUMSTANCES OF INCIDENT – ANSWER RELEVANT SECTIONS

DID DEATH OCCUR WHILE CHILD SLEEPING OR IN A SLEEPING ENVIRONMENT? ☐ **No** ☐ **Yes**

A. **INCIDENT** sleep place:			If adult bed, What type?		C. Child put to sleep:	D. Child found:
☐ Crib	☐ Playpen	☐ Car seat/Stroller	☐ Twin	☐ King	☐ On back	☐ On back
☐ Bassinette	☐ Couch	☐ Unknown	☐ Full	☐ Unknown	☐ On Stomach	☐ On Stomach
☐ Adult bed	☐ Chair	☐ Other, Specify:	☐ Queen	☐ Other, Specify:	☐ On side	☐ On side
☐ Waterbed	☐ Floor				☐ Unknown	☐ Unknown
					By Whom:	By Whom:

E. Was there a crib, bassinette, or port-a-crib in home for child? ☐ No ☐ Yes ☐ Unknown

F. **USUAL** sleep place:			If adult bed, what type?		G. **USUAL** sleep position:	H. Child in new or different environment?
☐ Crib	☐ Playpen	☐ Car seat/Stroller	☐ Twin	☐ King	☐ On back	☐ No
☐ Bassinette	☐ Couch	☐ Unknown	☐ Full	☐ Unknown	☐ On Stomach	☐ Yes
☐ Adult bed	☐ Chair	☐ Other, Specify:	☐ Queen	☐ Other, Specify:	☐ On side	☐ Unknown
☐ Waterbed	☐ Floor				☐ Unknown	

FIGURE A.6, cont'd



Per ARS §36-2293, completion of this form is required for any death investigation of children younger than 12 months of age.

Page 3 of 4 (rev. 3/17/10)

Infant Death Investigation Checklist

Arizona Report Form, Version 1.0

Mail or fax completed forms to:
County Office of the Medical Examiner
(fax numbers at the bottom of page 1)
Arizona Department of Health Services
(fax: 602-542-1843)

CIRCUMSTANCES when child found:

Child's airway was:

☐ Unobstructed by person or object
☐ Fully obstructed by person or object
☐ Partially obstructed by person or object
☐ Unknown

Child's position most relevant to death:

☐ On top of
☐ Under
☐ Between
☐ Wedged into
☐ Pressed into
☐ Fell or rolled onto
☐ Tangled in
☐ Unknown
☐ Other, Specify:

With what objects or persons? Check all that apply:

☐ Adult
☐ Child(ren)
☐ Animal(s)
☐ Blanket
☐ Pillow
☐ Comforter
☐ Mattress
☐ Bumper pads

☐ Waterbed mattress
☐ Air mattress
☐ Pillow-top mattress
☐ Crib rail
☐ Couch
☐ Car seat/stroller
☐ Stuffed toy
☐ Chair, Type:

☐ Clothing
☐ Cord
☐ Plastic bag
☐ Wall
☐ Unknown
☐ Other, Specify:

Child sleeping on same surface with person(s) or animal(s)? Check all that apply:

☐ With adults: Number: _____ Adult obese: ☐ No ☐ Yes ☐ Unknown Alcohol/Drugs? ☐ No ☐ Yes
☐ With other child(ren): Number: _____ Child(ren)'s ages:
☐ With animal(s): Number: _____ Type(s) of animals:
☐ Unknown ☐ Number Unknown

What food/liquids was the child fed in the last 24 hours?	**No**	**Yes**	**Unknown**	**Quantity** (Specify type & brand, if applicable)
Breast milk (one/both sides, length of time)	☐	☐	☐	ounces
Formula (brand, water source – ex. Similac, tap water)	☐	☐	☐	ounces
Was the formula mixed according to directions?	☐	☐	☐	
Cow's milk	☐	☐	☐	ounces
Water (brand, bottled, tap, well)	☐	☐	☐	ounces
Other liquids (juices, teas)	☐	☐	☐	ounces
Solids, specify:	☐	☐	☐	ounces
Other, specify:	☐	☐	☐	ounces

Was a new food introduced in the 24 hours prior the child's death?
☐ No ☐ Yes ☐ Unknown If yes, describe:

Was the child last placed to sleep with a bottle?
☐ No ☐ Yes ☐ Unknown **How was formula prepared:**

Was the bottle propped on object while feeding?
☐ No ☐ Yes ☐ Unknown If yes, what object used?

What was the quantity of liquid (in ounces) in the bottle?

Did the death occur during: ☐ Breastfeeding ☐ Bottle feeding ☐ Eating solid foods ☐ Not during feeding

RECENT MEDICAL HISTORY

Source of medical information:
☐ Mother/primary care giver ☐ Family ☐ Doctor ☐ Medical records ☐ Other healthcare provider ☐ Other, Specify:

In the 72 hours prior to death, did the child have: (check all that apply)

	No	**Yes**	**Unknown**		**No**	**Yes**	**Unknown**
Fever	☐	☐	☐	Diarrhea	☐	☐	☐
Excessive sweating	☐	☐	☐	Difficulty breathing	☐	☐	☐
Weakness or sleeping more than usual	☐	☐	☐	Cough/wheezing	☐	☐	☐
Fussiness or excessive crying	☐	☐	☐	Apnea (stopping breathing)	☐	☐	☐
Decrease in appetite	☐	☐	☐	Cyanosis (turned blue/gray)	☐	☐	☐
Vomiting	☐	☐	☐	Seizures or convulsions	☐	☐	☐
Choking	☐	☐	☐	Other, Specify:			

In the 72 hours prior to death, was the child injured or did child have any other condition(s) not mentioned?
☐ No ☐ Yes If yes, describe:

In the 72 hours prior to the death, did the child receive any vaccinations, medications, or exposure to any chemicals?
(Please include any home remedies, herbal medications, prescription medicines or over-the-counter medications including "cough, cold medicine")
☐ No ☐ Yes If yes, describe/list:

Any recent visit to a medical provider?
☐ No ☐ Yes If yes, When? Doctor/Facility: Why?

FIGURE A.6, cont'd



Per ARS §36-2293, completion of this form is required for any death investigation of children younger than 12 months of age.

Page 4 of 4 (rev. 3/17/10)

Infant Death Investigation Checklist

Arizona Report Form, Version 1.0

Mail or fax completed forms to:
County Office of the Medical Examiner
(fax numbers at the bottom of page 1)
Arizona Department of Health Services
(fax: 602-542-1843)

HEALTH INFORMATION

Child's Primary Care Physician: **Phone: ( )** **Last Visit: When?** **Why:**

Allergies: **Birth defects:**

Medications:

Has the child been immunized? ☐ **No** ☐ **Yes** ☐ **Unknown** **Date of last immunization:**

Immunizations current? ☐ **No** ☐ **Yes** ☐ **Unknown** **If immunized within the last 30 days, specify type:**

Does the child use any home monitors? ☐ **No** ☐ **Yes** **Type/Brand:**

If Yes, was child on home monitor at time of death? ☐ **No** ☐ **Yes**

Anyone else in household or other contacts (e.g. daycare) recently ill? ☐ **No** ☐ **Yes**

Family history of genetic/inheritable disease(s)? ☐ **No** ☐ **Yes, Specify:**

BIRTH INFORMATION

Birth place (home, hospital name and location):

Birth complications? ☐ **No** ☐ **Yes** **If yes, specify:**

Gestational Age ☐ **Unknown** _____ **weeks**	**Birth Weight:** ☐ **Unknown** _____ **grams** _____ **pounds/ounces**	**Multiple Birth?** ☐ **No** ☐ **Yes, #**_____	**# of prenatal visits** ☐ **Unknown** **#** _____	**Month of first prenatal visit** **Specify 1-9:** _____ ☐ **Unknown** ☐ **None**

During pregnancy, did mother (check all that apply):

☐ Smoke tobacco
☐ Use illicit drugs
☐ Experience intimate partner violence
☐ Child born drug exposed
☐ Heavy alcohol use
☐ Child born with fetal alcohol effects or syndrome
☐ Misuse OTC or prescription drugs

☐ During pregnancy, did mother have medical complications/infections? (check all that apply) Specify type, if known

	Type		Type
☐ Lung Disease	_____	☐ Preterm Labor	_____
☐ Heart Disease	_____	☐ Premature Rupture Membrane	_____
☐ Blood Disorder	_____	☐ Vaginal Bleeding	_____
☐ Infectious Disease	_____	☐ Diabetes Mellitus	_____
☐ Familial Genetic Disorder	_____	☐ Other	_____

Were there access or compliance issues related to prenatal care?

☐ No
☐ Yes
If yes, check all that apply:
☐ Unknown

☐ Lack of money for care
☐ Limited or no health insurance coverage
☐ Lack of transportation
☐ Lack of child care
☐ No phone

☐ Religious objections to care
☐ Cultural differences
☐ Unwilling to obtain care
☐ Did not know care needed
☐ Other, specify:

SCENE DOCUMENTATION

Photos of Death Scene Taken? ☐ **No** ☐ **Yes**

Property Seized? ☐ **No** ☐ **Yes** **What Agency Seized Property?**

Formula? ☐ **No** ☐ **Yes** **Bottles/Contents?** ☐ **No** ☐ **Yes** **Bedding?** ☐ **No** ☐ **Yes** **Crib?** ☐ **No** ☐ **Yes**

Other, Specify:

Was there an open CPS case with child at time of death? ☐ **No** ☐ **Yes** ☐**Unk**

Was the child ever placed outside of the home prior to death? ☐ **No** ☐ **Yes** **Date of Placement:**

Were any siblings placed outside of the home prior to this child's death? ☐ **No** ☐ **Yes** **Date of Placement:**

PERSON COMPLETING FORM

Name (please print or type):

Agency:

Telephone: ( ) **Fax: ( )** **Date:**

Signature: **Date Signed:**

ADDITIONAL COMMENTS: **(Include information about additional caregivers/supervisors or circumstances. Attach additional pages as necessary)**

FIGURE A.6, cont'd



U.S. DEPARTMENT OF HEALTH AND HUMAN SERVICES
Centers for Disease Control and Prevention
Division of Reproductive Health
Maternal and Infant Health Branch
Atlanta, Georgia 30333

CDC

Sudden Unexplained Infant Death Investigation
SUIDI
Reporting Form

INVESTIGATION DATA

Infant's Last Name: ______ Infant's First Name: ______ Middle Name: ______ Case Number: ______

Sex: ______ Date of Birth: ______ Age: ______ SS#: ______

Race: ☐ White ☐ Black/African Am. ☐ Asian/Pacific Isl. ☐ Am. Indian/Alaskan Native ☐ Hispanic/Latino ☐ Other

Infant's Primary Residence:

Address: ______ City: ______ County: ______ State: ______ Zip: ______

Incident Address: ______ City: ______ County: ______ State: ______ Zip: ______

Contact Information for Witness:

Relationship to deceased: ☐ Birth Mother ☐ Birth Father ☐ Grandmother ☐ Grandfather

☐ Adoptive or Foster Parent ☐ Physician ☐ Health Records ☐ Other Describe: ______

Last: ______ First: ______ M.: ______ SS#: ______

Address: ______ City: ______ State: ______ Zip: ______

Work Address: ______ City: ______ State: ______ Zip: ______

Home Phone: ______ Work Phone: ______ Date of Birth: ______

WITNESS INTERVIEW

1 **Are you the usual caregiver?**

☐ No ☐ Yes

2 **Tell me what happened:**

______

3 **Did you notice anything unusual or different about the infant in the last 24 hrs?**

☐ No ☐ Yes Specify: ______

4 **Did the infant experience any falls or injury within the last 72 hrs?**

☐ No ☐ Yes Specify: ______

5 **When was the infant LAST PLACED?**

Date: ______ Military Time: ___ : ___ Location (room): ______

6 **When was the infant LAST KNOWN ALIVE(LKA)?**

Date: ______ Military Time: ___ : ___ Location (room): ______

7 **When was the infant FOUND?**

Date: ______ Military Time: ___ : ___ Location (room): ______

8 **Explain how you knew the infant was still alive.**

______

9 **Where was the infant - (P)laced, (L)ast known alive, (F)ound** (write **P**, **L**, or **F** in front of appropriate response)**?**

☐ Bassinet	☐ Bedside co-sleeper	☐ Car seat	☐ Chair
☐ Cradle	☐ Crib	☐ Floor	☐ In a person's arms
☐ Mattress/box spring	☐ Mattress on floor	☐ Playpen	☐ Portable crib
☐ Sofa/couch	☐ Stroller/carriage	☐ Swing	☐ Waterbed
☐ Other - describe:			

FIGURE A.6
(B) Sudden Unexplained Infant Death Investigation form



WITNESS INTERVIEW (cont.)

10 **In what position was the infant LAST PLACED?** ☐ Sitting ☐ On back ☐ On side ☐ On stomach ☐ Unknown
Was this the infant's usual position? ☐ Yes ☐ No What was the usual position? ☐

11 **In what position was the infant LKA?** ☐ Sitting ☐ On back ☐ On side ☐ On stomach ☐ Unknown
Was this the infant's usual position? ☐ Yes ☐ No What was the usual position? ☐

12 **In what position was the infant FOUND?** ☐ Sitting ☐ On back ☐ On side ☐ On stomach ☐ Unknown
Was this the infant's usual position? ☐ Yes ☐ No What was the usual position? ☐

13 **Face position when LAST PLACED?** ☐ Face down on surface ☐ Face up ☐ Face right ☐ Face left

14 **Neck position when LAST PLACED?** ☐ Hyperextended (head back) ☐ Flexed (chin to chest) ☐ Neutral ☐ Turned

15 **Face position when LKA?** ☐ Face down on surface ☐ Face up ☐ Face right ☐ Face left

16 **Neck position when LKA?** ☐ Hyperextended (head back) ☐ Flexed (chin to chest) ☐ Neutral ☐ Turned

17 **Face position when FOUND?** ☐ Face down on surface ☐ Face up ☐ Face right ☐ Face left

18 **Neck position when FOUND?** ☐ Hyperextended (head back) ☐ Flexed (chin to chest) ☐ Neutral ☐ Turned

19 **What was the infant wearing?** *(ex. t-shirt, disposable diaper)* ☐

20 **Was the infant tightly wrapped or swaddled?** ☐ No ☐ Yes - describe: ☐

21 **Please indicate the types and numbers of layers of bedding both over and under infant (not including wrapping blanket):**

Bedding UNDER Infant	None	Number	Bedding OVER Infant	None	Number
Receiving blankets			Receiving blankets		
Infant/child blankets			Infant/child blankets		
Infant/child comforters (thick)			Infant/child comforters (thick)		
Adult comforters/duvets			Adult comforters/duvets		
Adult blankets			Adult blankets		
Sheets			Sheets		
Sheepskin			Pillows		
Pillows			Other, specify:		
Rubber or plastic sheet					
Other, specify:					

22 **Which of the following devices were operating in the infant's room?**
☐ None ☐ Apnea monitor ☐ Humidifier ☐ Vaporizer ☐ Air purifier ☐ Other - ☐

23 **In was the temperature in the infant's room?** ☐ Hot ☐ Cold ☐ Normal ☐ Other - ☐

24 **Which of the following items were near the infant's face, nose, or mouth?**
☐ Bumper pads ☐ Infant pillows ☐ Positional supports ☐ Stuffed animals ☐ Toys ☐ Other - ☐

25 **Which of the following items were within the infant's reach?**
☐ Blankets ☐ Toys ☐ Pillows ☐ Pacifier ☐ Nothing ☐ Other - ☐

26 **Was anyone sleeping with the infant?** ☐ No ☐ Yes

Name of individual sleeping with infant	Age	Height	Weight	Location in relation to infant	Imparement (intoxication, tired)

27 **Was there evidence of wedging?** ☐ No ☐ Yes - Describe: ☐

28 **When the infant was found, was s/he:** ☐ Breathing ☐ Not Breathing
If not breathing, did you witness the infant stop breathing? ☐ No ☐ Yes

Page 2

FIGURE A.6, cont'd

WITNESS INTERVIEW (cont.)

29 **What had led you to check on the infant?** ☐

30 **Describe the infant's appearance when found.**

Appearance	Unknown	No	Yes	Describe and specify location
a) Discoloration around face/nose/mouth				
b) Secretions (foam, froth)				
c) Skin discoloration (livor mortis)				
d) Pressure marks (pale areas, blanching)				
e) Rash or petechiae (small, red blood spots on skin, membranes, or eyes)				
f) Marks on body (scratches or bruises)				
g) Other				

31 **What did the infant feel like when found?** *(Check all that apply.)*

☐ Sweaty ☐ Warm to touch ☐ Cool to touch ☐ Limp, flexible ☐ Rigid, stif ☐ Unknown

☐ Other - specify:

32 **Did anyone else other than EMS try to resuscitate the infant?** ☐ No ☐ Yes

Who? Date: Military time: :

33 **Please describe what was done as part of resuscitation:**

34 **Has the parent/caregiver ever had a child die suddenly and unexpectedly?** ☐ No ☐ Yes

Explain:

INFANT MEDICAL HISTORY

1 **Source of medical information:** ☐ Doctor ☐ Other healthcare provider ☐ Medical record ☐ Family

☐ Mother/primary caregiver ☐ Other:

2 **In the 72 hours prior to death, did the infant have:**

Condition	Unknown	No	Yes	Condition	Unknown	No	Yes
a) Fever				k) Apnea (stopped breathing)			
h) Diarrhea				e) Decrease in appetite			
b) Excessive sweating				l) Cyanosis (turned blue/gray)			
i) Stool changes				f) Vomiting			
c) Lethargy or sleeping more than usual				m) Seizures or convulsions			
j) Difficulty breathing				g) Choking			
d) Fussiness or excessive crying				n) Other, specify:			

3 **In the 72 hours prior to death, was the infant injured or did s/he have any other condition(s) not mentioned?**

☐ No ☐ Yes - describe:

4 **In the 72 hours prior to the infants death, was the infant given any vaccinations or medications?** ☐ No ☐ Yes

(Please include any home remedies, herbal medications, prescription medicines, over-the-counter medications.)

Name of vaccination or medication	Dose last given	Date given Month	 Day	 Year	Approx. time (Military Time)	comments:
1.						
2.						
3.						
4.						

FIGURE A.6, cont'd

INFANT MEDICAL HISTORY (cont.)

5 **At any time in the infant's life, did s/he have a history of?**

Medical history	Unknown	No	Yes	Describe
a) Allergies *(food, medication, or other)*				
b) Abnormal growth or weight gain/loss				
c) Apnea *(stopped breathing)*				
d) Cyanosis *(turned blue/gray)*				
e) Seizures or convulsions				
f) Cardiac (*heart*) abnormalities				

6 **Did the infant have any birth defects(s)?** ☐ No ☐ Yes

Describe:

7 **Describe the two most recent times that the infant was seen by a physician or health care provider:**
(Include emergency department visits, clinic visits, hospital admissions, observational stays, and telephone calls)

	First most recent visit	Second most recent visit
a) Date		
b) Reason for visit		
c) Action taken		
d) Physician's name		
e) Hospital/clinic		
f) Address		
g) City		
h) State, ZIP		
i) Phone number		

8 **Birth hospital name:** Discharge date:

Street address:

City: State: Zip:

9 **What was the infant's length at birth?** inches or centimeters

10 **What was the infant's weight at birth?** pounds ounces or grams

11 **Compared to the delivery date, was the infant born on time, early, or late?**

☐ On time ☐ Early - how many weeks? ☐ Late - how many weeks?

12 **Was the infant a singleton, twin, triplet, or higher gestation?**

☐ Singleton ☐ Twin ☐ Triplet ☐ Quadrupelet or higher gestation

13 **Were there any complications during delivery or at birth?** *(emergency c-section, child needed oxygen)* ☐ Yes ☐ No

Describe:

14 **Are there any alerts to the pathologist?** *(previous infant deaths in family, newborn screen results)* ☐ Yes ☐ No

Specify:

FIGURE A.6, cont'd

INFANT DIETARY HISTORY

1 **On what day and at what approximate time was the infant last fed?**

Date: ☐ Military Time: ☐ :

2 **What is the name of the person who last fed the infant?** ☐

3 **What is his/her relationship to the infant?** ☐

4 **What foods and liquids was the infant fed in the last 24 hours** (include last fed)**?**

Food	Unknown	No	Yes	Quantity (ounces)	Specify: (type and brand)
a) Breast milk (one/both sides, length of time)					
b) Formula (brand, water source - ex. Similac, tap water)					
c) Cow's milk					
d) Water (brand, bottled, tap, well)					
e) Other liquids (teas, juices)					
f) Solids					
g) Other					

5 **Was a new food introduced in the 24 hours prior to his/her death?** ☐ No ☐ Yes

If yes, describe *(ex. content, amount, change in formula, introduction of solids)*

6 **Was the infant last placed to sleep with a bottle?** ☐ Yes ☐ No - if no, skip to question **9** below

7 **Was the bottle propped?** (i.e., object used to hold bottle while infant feeds) ☐ No ☐ Yes

If yes, what object was used to prop the bottle? ☐

8 **What was the quantity of liquid (in ounces) in the bottle?** ☐

9 **Did the death occur during?** ☐ Breast-feeding ☐ Bottle-feeding ☐ Eating solid foods ☐ Not during feeding

10 **Are there any factors, circumstances, or environmental concerns that may have impacted the infant that have not yet been identified?** *(ex. exposed to cigarette smoke or fumes at someone else's home, infant unusually heavy, placed with positional supports or wedges)*

☐ No ☐ Yes

If yes, - describe: ☐

PREGNANCY HISTORY

1 **Information about the infant's birth mother:**

First name: ☐ Last name: ☐

Middle name: ☐ Maiden name: ☐

Birth date: ☐ SS#: ☐

Street address: ☐ City: ☐ State: ☐ Zip: ☐

How long has the birth mother been at this address? Years: ☐ Months: ☐

Previous Address: ☐

2 **At how many weeks or months did the birth mother begin prenatal care?** ☐ No parental care ☐ Unknown

Weeks: ☐ Months: ☐

3 **Where did the birth mother receive prenatal care?** *(Please specify physician or other health care provider name and address.)*

Physician/provider: ☐ Hospital/clinic: ☐ Phone: ☐

Street address: ☐ City: ☐ State: ☐ Zip: ☐

FIGURE A.6, cont'd



PREGNANCY HISTORY (cont.)

4 **At how many weeks or months did the birth mother begin prenatal care?** ☐ No ☐ Yes
(ex. high blood pressure, bleeding, gestational diabetes)

Specify: ☐

5 **Was the birth mother injured during her pregnancy with the infant?** *(ex. auto accident, falls)* ☐ No ☐ Yes

Specify: ☐

6 **During her pregnancy, did she use any of the following?**

	Unknown	No	Yes	Daily		Unknown	No	Yes	Daily
a) Over the counter medications					d) Cigarettes				
b) Prescription medications					e) Alcohol				
c) Herbal remedies					f) Other				

7 **Currently, does any caregiver use any of the following?**

	Unknown	No	Yes	Daily		Unknown	No	Yes	Daily
a) Over the counter medications					d) Cigarettes				
b) Prescription medications					e) Alcohol				
c) Herbal remedies					f) Other				

INCIDENT SCENE INVESTIGATION

1 **Where did the incident or death occur?** ☐

2 **Was this the primary residence?** ☐ No ☐ Yes

3 **Is the site of the incident or death scene a daycare or other childcare setting?** ☐ Yes ☐ No - If no, skip to question **8**

4 **How many children (under age 18) were under the care of the provider at the time of the incident or death?** ☐

5 **How many adults (age 18 and over) were supervising the child(ren)?** ☐

6 **What is the license number and licensing agency for the daycare?**

License number: ☐ Agency: ☐

7 **How long has the daycare been open for business?** ☐

8 **How many people live at the site of the incident or death scene?**

Number of adults (18 years or older): ☐ Number of children (under 18 years old): ☐

9 **Which of the following heating or cooling sources were being used?** *(Check all that apply)*

- ☐ Central air
- ☐ A/C window unit
- ☐ Ceiling fan
- ☐ Electric baseboard heat
- ☐ Gas furnace or boiler
- ☐ Electric furnace or boiler
- ☐ Electric space heater
- ☐ Electric (radiant) ceiling heat
- ☐ Wood burning fireplace
- ☐ Coal burning furnace
- ☐ Kerosene space heater
- ☐ Window fan
- ☐ Open window(s)
- ☐ Wood burning stove
- ☐ Floor/table fan
- ☐ Unknown
- ☐ Other - specify: ☐

10 **Indicate the temperature of the room where the infant was found unresponsive:**

☐ Thermostat setting ☐ Thermostat reading ☐ Actual room temp. ☐ Outside temp.

11 **What was the source of drinking water at the site of the incident or death scene?** *(Check all that apply.)*

☐ Public/municipal water ☐ Bottled water ☐ Well ☐ Unknown ☐ Other - Specify: ☐

12 **The site of the incident or death scene has:** *(check all that apply)*

- ☐ Insects
- ☐ Pets
- ☐ Peeling paint
- ☐ Rodents or vermin
- ☐ Mold growth
- ☐ Dampness
- ☐ Visible standing water
- ☐ Odors or fumes - Describe: ☐
- ☐ Smoky smell *(like cigarettes)*
- ☐ Presence of alcohol containers
- ☐ Presence of drug paraphenalia
- ☐ Other - specify: ☐

13 **Describe the general appearance of incident scene:** *(ex. cleanliness, hazards, overcrowding, etc.)*

Specify: ☐

Page 6

FIGURE A.6, cont'd

INVESTIGATION SUMMARY

1 **Are there any factors, circumstances, or environmental concerns about the incident scene investigation that may have impacted the infant that have not yet been identified?**

2 **Arrival times**

	Military time
Law enforcement at scene:	:
DSI at scene:	:
Infant at hospital:	:

Investigator's Notes

1 **Indicate the task(s) performed**

☐ Additional scene(s)? (forms attached)
☐ Materials collected/evidence logged
☐ Notify next of kin or verify notification
☐ Doll reenactment/scene re-creation
☐ Referral for counseling
☐ 911 tape
☐ Photos or video taken and noted
☐ EMS run sheet/report

2 **If more than one person was interviewed, does the information differ?** ☐ No ☐ Yes

If yes, detail any differences, inconsistencies of relevant information: *(ex. placed on sofa, last known alive on chair.)*

INVESTIGATION DIAGRAMS

1 **Scene Diagram:**

2 **Body Diagram:**



FIGURE A.6, cont'd

SUMMARY FOR PATHOLOGIST

Case Information

1 **Investigator information** Name: ☐ Agency: ☐ Phone: ☐

	Date	Military time
Investigated:		:
Pronounced dead:		:

2 **Infant's information:** Last: ☐ First: ☐ M: ☐ Case #: ☐

Sex: ☐ Male ☐ Female Date of Birth: ☐ Age: ☐

Race: ☐ White ☐ Black/African Am. ☐ Asian/Pacific Islander
☐ Am. Indian/Alaskan Native ☐ Hispanic/Latino ☐ Other: ☐

1 **Indicate whether preliminary investigation suggests any of the following:**

Section	Yes	No	
Sleeping Environment	☐	☐	Asphyxia *(ex. overlying, wedging, choking, nose/mouth obstruction, re-breathing, neck compression, immersion in water)*
	☐	☐	Sharing of sleep surface with adults, children, or pets
	☐	☐	Change in sleep condition *(ex. unaccustomed stomach sleep position, location, or sleep surface)*
	☐	☐	Hyperthermia/Hypothermia *(ex. excessive wrapping, blankets, clothing, or hot or cold environments)*
	☐	☐	Environmental hazards *(ex. carbon monoxide, noxious gases, chemicals, drugs, devices)*
	☐	☐	Unsafe sleep condition *(ex. couch/sofa, waterbed, stuffed toys, pillows, soft bedding)*
Infant History	☐	☐	Diet (*e.g., solids introduced, etc.*)
	☐	☐	Recent hospitalization
	☐	☐	Previous medical diagnosis
	☐	☐	History of acute life-threatening events *(ex. apnea, seizures, difficulty breathing)*
	☐	☐	History of medical care without diagnosis
	☐	☐	Recent fall or other injury
	☐	☐	History of religious, cultural, or ethnic remedies
	☐	☐	Cause of death due to natural causes other than SIDS *(ex. birth defects, complications of preterm birth)*
Family Info	☐	☐	Prior sibling deaths
	☐	☐	Previous encounters with police or social service agencies
	☐	☐	Request for tissue or organ donation
	☐	☐	Objection to autopsy
Exam	☐	☐	Pre-terminal resuscitative treatment
	☐	☐	Death due to trauma (injury), poisoning, or intoxication
Investigator Insight	☐	☐	Suspicious circumstances
	☐	☐	Other alerts for pathologist's attention

Any "Yes" answers above should be explained in detail (description of circumstances):

☐

Pathologist

2 **Pathologist information** Name: ☐

Agency: ☐ Phone: ☐ Fax: ☐

FIGURE A.6, cont'd



EXTERNAL EXAMINATION WORKSHEET

Case No. ____________________

Name			
Age Years	Sex Male// Female	Date of Death @ hours	
Place of Examination		Date of Examination	Time hours

Clothing Indoor // Outdoor // Pajamas // Underwear// Diaper/// None	
Body Length inches	Body Weight pounds
Nourishment Normal // Thin // Obese	Body Preservation Good // Decomposed// Early Decomposition
Postmortem Lividity Posterior, Anterior Fixed, Blanchable Inferior Warm, Cold	Postmortem Rigidity Full: Upper/Lower Ext. & Jaw Easily Broken Absent
Hair Color and Length Gray // Brown// Black//Blonde Balding ___ cm.	Head Trauma: Brd brn/blk/gr: stubble/ ___cm// Mstach
Eyes Blue// Brown // Hazel /// cm. ++ // -- petechiae //hemorrhages	Ears/Nose/Mouth Trauma:
Teeth Natural: Good // Poor // Moderate Edentulous // + or -- Dentures	Neck Trauma:
Trunk—Anterior No trauma // see diagram Tattoos:	Trunk—Posterior No trauma // see diagram Tattoos: Scars: See dictation
Upper Extremities No trauma // see diagram Tattoos:	Lower Extremities No trauma // see diagram// Tattoos: _____ Edema
Genitalia Normal Male // Normal Female	Toxicology Samples Taken Vitreous/ Urine / Blood: Fem or Subclav

MANNER OF DEATH

- **NATURAL** ☐
- **ACCIDENT** ☐
- **SUICIDE** ☐
- **HOMICIDE** ☐
- **UNDET.** ☐
- **PENDING** ☐

CAUSE OF DEATH

(a)____

DUE TO or as a consequence of:

(b)____

DUE TO or as a consequence of:

(c)____

OTHER SIGNIFICANT CONDITIONS:

____

____

____

NOTES:

Place of Death: Scene /// Residence //// Hospital _____________
PMHx: HTN //// COPD /// DM /// MI //// CABG //// CA ________
MVA: driver // occupant// pedestrian
GSW: head // chest// abdomen
Xrays:
Cavity Blood: Chest Abdomen

________________________ ________________________

signature *date*

ETT: **Mouth**
NG: **nose// mouth**
Defib Pads:
Ant / L Lat / Back
EKG: **Torso // Ext**
IV: **Hand**
Antecub:
Groin:
Subclav

IO: **R / L Leg**
Foley:
Chest Tube: **R // L**

FIGURE A.7
External examination worksheet.

Case # HEIGHT

Decedent: WEIGHT

ORGAN (weight gms)		Comments
HEART:	RV	TCV
	LV	PV
	IVS	MV
	LAD	AV
	RCA	GREAT VESSELS:
	LC	
LUNGS:		Pleural Cavities:
Right		Right
Left		Left
NECK ORGANS:		
THYMUS:		
SPLEEN:		
Lymph Nodes:		
LIVER:		
Gall Bladder		
ADRENALS:		
PANCREAS:		
KIDNEYS:		
Right		
Left		
PELVIC ORGANS:		
Uterus F O	Urine: (Color / Vol)	
GI TRACT:	Appendix (Y/N)	Abdominal Fat
Abd. Cav.	Gastric Contents:	
MUSCULOSKELETAL:	Rib Fx: L ant.	R ant.
	L lat.	R lat.
	L post.	R post.
BRAIN:		
TOX:	Other:	FOC
Vit		CC
Blood: fem sub		AC
Urine		CR
Liver		CH
		WEIGHT IN GRAMS

FIGURE A.8
Worksheet for recording data at the time of the autopsy.

STAB WOUNDS

	# 1	# 2	# 3	# 4	# 5	# 6	# 7	# 8	# 9	# 0
BODY SITE										
DISTANCE WOUND										
Top of Head **[H]** Right Foot **[RF]** Left Foot **[LF]**										
Right Midline **[RML]**										
Left Midline **[LML]**										
SIZE OF WOUND										
LENGTH										
WIDTH										
MARGINS										
Square (SQ) Acute (A)										
DEPTH OF WOUND										
DIRECTION										
F ->B **B->F** ↑↓ **L ->R** **R ->L**										
ORGANS & FRACTURES										

FIGURE A.9
Notation of stab wounds worksheet.

GUNSHOT WOUNDS

	#	#	#	#	#	#	#	#	#	#
BODY SITE										
Entrance vs. Exit										
Connections										
DISTANCE WOUND										
Top of Head **[H]** Right Foot **[RF]** Left Foot **[LF]**										
Right Midline **[RML]**										
Left Midline **[LML]**										
SIZE OF WOUND										
Length x width										
MARGINS										
Marginal Abrasion										
Soot										
Stippling										
Projectiles										
DIRECTION										
F ->B **B->F** ↑ ↓ **L ->R** **R ->L**										
ORGANS & FRACTURES										

FIGURE A.10
Notation of gunshot wounds worksheet.

Infant Measurements:	
	Head circumference: Measure around the widest part of the head at the level of the forehead.
	
Measured at the level of the nipples.	Measured at the level of the umbilicus.
	Crown-Rump length: Measure from the top of the head to the bottom crease on the buttocks.
	Crown-Heel Length: Measure from the top of the head to the sole of the heel of the foot.

FIGURE A.11
How to obtain various measurements an infant.

Pictoral Overview of an Autopsy	
	Opening of the body with a Y shaped incision. The upper chest flap is reflected upward to the neck then eventually to the base of the chin to examine the torso and neck organs.
	Removal of the chest plate to gain entry into the chest cavity
	The open chest and abdomen.

FIGURE A.12
Overview of an autopsy.

	Evaluation of the chest cavity for accumulations of fluid which will need to be measured for quantity.
	Evaluation of the abdominal cavity for accumulations of fluid. They will need to be measured for quantity.
	The organs are removed separately, weighed and dissected. Here are the right and left lungs and heart with thoracic aorta.

FIGURE A.12, cont'd

	The abdominal organs have been removed and individually dissected looking for pathological processes to contribute to death.
	Biopsies of the organs are placed in the plastic cases for submission to histology in a jar of formalin.
	
Histology places the plastic cassettes through a series of chemical processes to dehydrate and preserve the specimens. They are then cut into very thin slices and placed onto glass slides, stained and dried. They are then ready for microscopic review by the pathologist.	

FIGURE A.12, cont'd

	The scalp is opened by an incision behind the ears and extends over the crown of the head.
	The anterior portion is slowly reflected to the forehead and the posterior portion is reflected downward to the back of the head.
	A reciprocating saw is then used to cut an incision in the skull to the brain and cranial cavity may be examined.

FIGURE A.12, cont'd

	The skull cap is sawed around the top of the head with a step at each side to prevent it from becoming circular. The skull is pried off with the T bar to reveal the underlying brain.
	The brain is removed from the cranium with careful examination of the spinal cord.
	The interior portion of the skull is examined before and after the dura lining is removed.

FIGURE A.12, cont'd

	The dura lining is stripped away from the interior skull to examine the bone structures more closely for fractures.
	Examination of the neck is last. Here the skin has been dissected upward to the chin and from the muscles. Normal is this uniform brown color.
	The neck organs are removed and dissected apart looking for fractures of the hyoid bone or thyroid cartilage. The airway is opened and inspected for evidence of obstruction.

FIGURE A.12, cont'd

	Residual organ tissue is returned to the body cavity to be released with the body to the funeral home.
	The body is sutured closed. Note the incisions and suture lines are in areas that would not preclude an open casket.
	The head is sutured closed. The funeral home will reassembled the skull and wax the suture lines. By combing the hair over the incision it will not be visible in the casket.

FIGURE A.12, cont'd

Removal of the eyes :



Incisions are made through the orbital plates using the oscillating saw. The plates are removed to loosen the soft tissue around each of the globes, being careful to not incise the eyelids. The eyelids can then be dissected away from the area surrounding the anterior globe. The small muscles on either side of the globe will need to be snipped away to release the globe from the orbital canal.

FIGURE A.13
Overview of removal of certain body parts.

Removal of the internal ear canals:



Wedges of bone at 45 degree angles are incised into the basilar skull over the internal ear canal. The fragments will require decalcification prior to review in microscopic sections.

FIGURE A.13, cont'd

Removal of the spinal cord:	
	The anterior portion of the vertebral canal must be removed to reveal the underlying spinal cord. A 45 to 60 degree angle incision is made along the edge of the spine.
	The wedge of bone is lifted off revealing the dura and cord.
	The dura is opened and the cord is able to be removed by snipping the small nerves along the margins.

FIGURE A.13, cont'd

Cerebrospinal Fluid Tap



The skin is cleansed with bactericidal soap then a syringe is inserted at the base of the skull into the brain. Clear fluid should be obtained with gentle suciton on the syringe.

FIGURE A.13, cont'd

REHYDRATING MUMMIFIED HANDS FOR FINGERPRINT IDENTIFICATION

(Used with permission Pima County Forensic Science Center, Tucson, AZ)

A. 3% Sodium Hydroxide (NaOH) Solution preparation:

This solution creates HEAT. To prevent spillage, add the sodium hydroxide SLOWLY to the water.

- 60 grams of NaOH (usually in pellet form)
- 2 liters of water (tap water or saline)
- Slowly dissolve the NaOH pellets by adding them into a gallon size container
- Let the solution cool overnight, uncovered. Ready to use the following AM.

Makes 2 liters of the 3% NaOH solution which is enough for a single application.

B. Soaking procedure:

- Disarticulate the hands at the wrist.
- Soak the hands in the 2 liters of 3% NaOH solution. Best if place the pads downward in the container as the hands will float.
- Monitor the hands for suppleness and pliability for next 24-48 hrs. Check frequently after the first 24 hrs to prevent over processing.
- While checking, rinse the hands of debris from the pads and resoak if unable to open from clenched position.
- At the point of suppleness of the pads as well as the hand, remove hands from solution and wrap in a towel and let dry for 24-48 hours.
- After the hands are no longer slick and are pliable they are ready to be printed.
- For best results, use black fingerprint ink applied sparingly to a fingerprint slab. Apply the ink to the finger pads using the slab or roller. Print the fingers onto a card. This process may need to be repeated at various intervals to obtain the best prints, allowing the hands to remain wrapped in the towel between attempts.

PROCEDURE FOR OBTAINING PRINTS ON WASHERWOMAN HANDS

1. The day before the autopsy, take a small tub and rest each hand on one so they are located out of the water in the bag.
2. Wrap the hands in a thick towel. It is important to keep the hands from resting in the body bag as it will keep the hands wet.
3. The next morning, massage Goop (usually found at car part stores) into the fingers of the decedent.
4. Use a clean towel to wipe off the Goop. The process of rubbing on the Goop and taking it off may need to be done a couple of times.
5. Using an ink roller, roll a thin layer of ink on the fingertips and print as usual.

ON BEING A WITNESS

1. Make definite arrangements with the attorney who is asking you to testify as to the time and place for the meeting, and whether it is a court or a defense interview. Subpoenas for deposition will state the time and place. Even though you have a subpoena for court, call the attorney prior to going to court to verify the time and place. Wait outside the courtroom until you are called.
2. Become familiar with courtroom proceedings prior to appearing as a witness. Listen and observe some trials either in person or on TV.
3. The witness will be sworn in by the court personnel; the judge will direct you to the correct person. He or she will verify your name and title and you will be sworn in. State “I do” clearly and confidently so the jury can hear.
4. You should wear neat, conservative clothing. Plain, dark colors or small prints are best. For women, a nice dress, suit, or jacket with skirt or pants, minimal makeup, and a small purse. For men, a suit jacket with trousers and a dress shirt with a tie. Your shoes should be neat. Your first impression with the jury is important. You are on a job interview with 12 prospective bosses. Remember you aren’t there to impress them with style, you are there to be believable.
5. Try to relax on the witness stand. There is water there for your use if you need it.
6. A witness’ testimony is for the benefit of the jury and the court rather than the spectators, attorneys, or judge. Face the jury when testifying. You can face the attorney when he or she is questioning you, and when you reply, shift your attention and body to answer to the jury.
7. Give information to the jury in an air of assurance but do not be arrogant.
8. If you need to refresh your memory, you may bring notes and/or reports to court and utilize them. If you need a moment to locate the passage, state that you need a moment to refer to your notes to answer the question.
9. Be prepared. Review the report and record prior to going to court. Recall what your statements were during pretrial interviews and make notes of them during or after to refer to prior to going to trial. Review your resume so that you can recite your credentials concisely. Always take a copy of a current resume to trial and to a pretrial interview or deposition.
10. A witness should always be courteous and not argumentative. It is the attorney’s job to see if he or she can get you riled. Don’t let it happen.
11. A witness should always be attentive and interested in what is being said in the courtroom. Do not appear bored or that the questions are tedious. Many times questions are asked and re-asked. Be prepared to state that you have answered the question previously. The court may make you give the answer again; remember what you say and repeat the same words exactly.
12. You are there to give the jury the facts so they can make a decision. Put yourself in a layman’s shoes who may have no medical or police knowledge. Help the jury understand the facts without talking down to them. Try to remain neutral in your comments so you are not prejudiced for the defense or prosecution. You aren’t there to judge the accused, only to give facts and to represent the decedent or victim.

13. Keep your voice clear. Refrain from using phrases or abbreviations that a juror might not know or understand, and if you must use them, give a very concise explanation of the term in your response.
14. Be direct in your answers. Don't beat around the bush entirely, but give yourself some room if the going gets tough. Don't paint yourself into a corner. Beware of words like "always" or "never." Try to stay away from quantifying with percentages and use general phrases like "more often than not," etc. Attorneys also will take your answer and repeat it back to you changing the wording slightly. Beware!! Repeat it so you can stand behind the statement and in the terms you testified to.

Glossary

abrasion A scrape on the skin causing a loss of the superficial layers of the skin.

adipocere Decomposition of the body in cold, wet environments.

Alphonse Bertillon French law enforcement officer from the late 19th century who performed research in anthropometry.

alveolus Primary unit for gas exchange in the lungs.

aneurysm Bulging of the arterial wall due to weakness of the muscular component.

anoxia A total lack of oxygen in the body.

asphyxia Process causing lack of oxygen to the brain and resulting in unconsciousness and death.

atrophy Loss of muscle or flesh gradually due to lack of use.

avulsion Subtype of laceration in which the tear has created a flap of skin that is able to be lifted from the underlying muscle or bone.

babygram X-ray showing fractures or developmental abnormality of an infant's skeletal system.

bite-mark ruler Standard scale used in forensic photo documentation, helping to prevent misinterpretation of measurements and characteristics.

bullet Small (usually round or elongated) piece of metal used as a projectile in a firearm.

caliber The diameter measurement inside the gun barrel between two lands (usually measured in millimeters).

capital punishment Legal sentencing of a person to death as the result of a crime.

carbon monoxide Tasteless, odorless, colorless gas that is poisonous to humans.

cardiac valve Valve located in the heart located between the chambers and outflow tracts to control the flow of blood.

car pillars Posts supporting the roof of a car.

casing The spent portion of a cartridge that remains inside the cylinder of the gun or is discarded after firing and is usually made of brass or steel.

cause of death Medical description or diagnosis determining why someone is dead, expressed in medical terminology.

Center for Disease Control U.S. federal agency the goal of which is to maintain public health and prevent and control disease.

chain of custody A form listing any seized evidence and listing in a sequential fashion those who have handled or processed it to insure the integrity from the site of origin to its final storage and/or results in report format.

co-sleeping Infants sleeping close to, or in the same bed as, adults or other children.

compression asphyxia Inhibition of the movement of the diaphragm by compression of the chest or abdomen, resulting in lack of gas exchange.

CODIS Combined DNA Index System; an FBI database that stores DNA profiles from multiple sources, including results from crimes scenes and from offenders convicted of violent crimes.

components of air The chemical makeup of air, including nitrogen, oxygen, water vapor, argon, and carbon dioxide.

conflict of interest Situation occurring when the private interests and official responsibilities of a person may clash.

contusion A bruise created by a force being applied to the skin causing the rupture of small blood vessels and bleeding into the tissue under the skin surface.

coroner Elected officials with the legal ability to certify the cause and manner of death on the death certificate.

cremation Burning of a body at greater than 1,400–1,800 °F over a period of two to three hours to reduce the body to ash.

cyanide Colorless toxin that is lethal in high concentrations.

cyanotic Commonly referred to as "blue baby," in which the circulations of oxygenated and deoxygenated blood are mixed.

cylinder Rotating part of a revolver that contains multiple chambers for cartridges to align with the barrel for firing.

defense wounds Stab wounds or incisions that are inflicted by another person on the victim and are characterized by being located on the arms or legs.

dicing wounds Small, superficial cuts on the skin, often caused by shards of glass.

distal Region of the body away from the midline. An example is the hand is distal to the elbow.

edentulous Without teeth.

embalming The process of replacing the body fluids with formalin as a means of preservation.

embolus Detached blood clot transported through circulation.

epi Prefix indicating "outer."

exhumation Removal of a body from the grave where it has been buried for a length of time.

exsanguination Blood loss.

femoral blood Blood found in the femoral vein, which moves blood from the legs to the heart.

fetus An unborn being in the later stages of development.

forensic pathologist Board-certified examiner who performs autopsies as part of the medical examiner or coroner office.

fracture Breaking of a bone due to blunt force.

gauge The inner diameter of a shotgun barrel, expressed as the number of lead balls that will fit in the barrel and make a pound.

gunshot residue Burnt and unburnt particles left behind from the firing of a gun.

hemoglobin Part of the blood containing iron and carrying oxygen through the body.

hemosiderin/hematoidin Colored intracellular pigment caused by the breakdown of hemoglobin from red cells seen on microscopic examination.

hesitation wound Superficial wounds that look like curved abrasions, often surrounding self-inflicted wounds and thought to be tests of a weapon.

hospital pathologist Physician specialized in anatomic pathology working in a hospital who can perform basic autopsies (often deaths that are more likely to be disease related rather than trauma).

hyper Prefix indicating "over."

hypo Prefix indicating "below."

hypoxia A decreased level of oxygen in the body.

IAFIS Integrated Automated Fingerprint Identification System; FBI-sponsored fingerprint identification system that contains fingerprints obtained directly by the FBI and those submitted by various law enforcement agencies.

incision Cut of the skin caused by force applied to the skin by a sharp object. Generally, and that is longer than it is deep (often referred to as slashing injury or as a surgical incision).

infant Very young child.

instar Enlarging cycle of maggots (occurs three times in the life cycle of a blow fly).

jaundice Yellow discoloration of the skin or whites of the eyes.

kinetic energy The energy possessed by an object in motion.

laceration Tear of the skin as a result of a force being applied that exceeds the skin's elastic ability to stretch.

lethal injection Intravenous injection of a barbiturate that induces sleep followed by a neuromuscular-blocking agent such as succinylcholine or pancuronium that causes paralysis of skeletal and smooth muscles including the diaphragm. Potassium chloride is also injected.

live birth Defined as an infant who takes a breath or has a heartbeat upon being born.

livor The postmortem settling of blood

Locard's exchange principle Principle developed by Edmond Locard stating that two items coming into contact with each other will exchange material between them.

macerated Reddening, loss of skin, and feature distortion of a fetus due to retention in the uterus.

magazine Supply chamber of a gun that holds bullets.

manner of death Identification of the way a person died, using one of the following classifications: natural, accident, suicide, homicide, or undetermined.

meconium Thick, dark, tarry stool that a child expels in the early days of life.

medical examiner Forensic pathologist with education as a medical doctor, completion of four years of anatomic pathology, and at least one to two years of subspecialty training in forensic medicine who performs autopsies and has jurisdiction.

mitochondria Small cellular organelles containing DNA.

Model Postmortem Examinations Act The 1954 law outlining the recommended state-mandated reporting of cases to a central investigative agency for adoption of individual state laws.

mummification Decomposition of the body in hot, arid environments in which the body is partially protected from the sun and the air blowing across the body dries it out.

myocardium Muscle layer of the heart.

N-95 mask Mask designed with a very close facial fit used to help control the spread of germs.

next of kin Person or persons who are most closely related to the deceased.

NAMUS National Missing and Unidentified Persons System; National Institute of Justice database that may be viewed by the public as they search for their missing relative.

NCIC National Crime Information Center; FBI database that includes many subfiles including types of crimes for development of statistics regarding various violent crimes and where they are committed, as well as a missing persons database and an unidentified persons database. Available only to law enforcement.

neonate Newborn child.

notification Process of informing next of kin of a death. This is best if done in person, but others should be made aware that the notification is occurring, or a law enforcement officer should also be in attendance.

nucleus Membrane-enclosed organelle performing the information and administrative function of a cell.

pathologic fracture Fracture caused by minimal force applied to weakened bones by osteoporosis or tumor. The amount of force applied would not usually fracture healthy bones.

PCR Polymerase chain reaction, which makes copies of isolated DNA.

peer review Evaluation of content or services by other experts in the field.

positional asphyxia The impairment of oxygen exchange caused by the position of the body.

postmortem After death.

PPE Personal protective equipment; gear worn or used during autopsy to decrease the potential health hazards to those in the room and prevent transmission of biohazards outside the room to clean areas of the office.

premortem Before death.

proximal Located near the center of the body. An example is the elbow is proximal to the hand.

quality assurance Program to monitor the accuracy of and satisfaction with work done by medical examiner/coroner offices. May involve graded case studies or lab samples, peer reviews, and public surveys.

rigor The postmortem muscle stiffening in the body.

Rokitansky technique Style of autopsy developed by Dr. Karl Rokitansky that utilizes a block approach and allows organs to be evaluated in relationship to their interconnections, such as vasculature or ducts.

saponification A soap formation on the body occurring during decomposition in some environments and is due to a chemical change to the composition of body fat.

skeletal survey Scanning the body of a child for acute and healing injuries using a series of X-rays.

stab wound A sharp-force injury that is deeper than it is long.

sub Prefix indicating "lower" or below.

subclavian blood Blood found in the subclavian vessels, is located under the clavicles and represents blood to and from the arms.

therapeutic misadventure Possible additional category of manner of death, meaning and is used when a death is related to a medical intervention.

thrombus Blood clot that forms at the site where it obstructs the vascular lumen.

trace evidence Minute fragments of debris, fibers, hair, vegetation, paint chips, etc. that adhere to the body.

undermining Circumstance in which a segment of skin is lifted from the underlying skeletal structure, forming a pocket.

Virchow technique Style of autopsy developed by Dr. Rudolf Virchow that utilizes an organ-by-organ approach, relying on the natural retraction of the body itself.

vitreous Thick, transparent substance that fills most of the eye and is useful for toxicology, electrolyte and glucose evaluation by the laboratory.

wadding Material used to keep gas behind the projectile of a gun the gunpowder separate from the pellets in a shotgun shell.

Index

Note: Page numbers followed by *f* indicate figures, *t* indicate tables and *b* indicate boxes

A

A pillar, 136, 136*f*
AAA. *See* Abdominal aortic aneurysm
AAFS. *See* American Academy of Forensic Sciences
Abbreviations, for death certification, 47*f*
Abdominal aortic aneurysm (AAA), 199
ABMDI. *See* American Board of Medicolegal Death Investigators
Abrasions, 123
  directionality of, 123
  at entrance wound, 157, 158*f*
  at exit wounds, 159, 160*f*
  healing of, 123
  patterned, 123, 124*f*, 125*f*
  with seatbelts, 137, 138*f*
  steering wheel, 137
  types of, 123, 124*f*
  with windshield impact, 135, 135*f*
Absent rigor, 59
Accidental death
  brain hemorrhage and, 52
  on death certification, 50
  falls and, 53
  fractures and, 53
  from gunshot, 176–177
  with sharp-force injuries, 190–191
Accidental trauma, in children, 273*f*
ACFEI. *See* American College of Forensic Examiners Institute
Adipocere, 63, 64*f*, 291
Adrenal glands removal, 87
Air embolus, with sharp-force injuries, 190
Airbags, 134–135
Airplane fatalities, autopsy for, 98
Alcohol related death, 241–242, 241*f*, 242*b*
Alveoli, 206–207, 206*f*
American Academy of Forensic Sciences (AAFS), 13
American Board of Medicolegal Death Investigators (ABMDI), 12, 18
American Board of Pathology, 11–12
American College of Forensic Examiners Institute (ACFEI), 13
Anaphylaxis, in children, 269, 269*b*
Anatomic examination, 11
Aneurysm, 198–199, 200*f*
Anterior neck dissection, 94
Anthropometry, 5–7, 6*f*
Aorta, 194
  dissection of, 204–205
Asphyxia, 279–296
  carbon monoxide, 292–293, 292*f*
  case study for, 280*b*
  caves, freezers, tanker car, or silo, 294–295
  choke holds, 287–288, 287*f*
  cyanide, 293
  drowning, 289–291
  hanging, 280–283
  hydrogen sulfide, 293–294
  introduction to, 279–280
  mechanical, 288–289, 288*f*, 290*f*
  with motor vehicle accidents, 139–140, 139*f*
  photographic documentation of, 295
  sexual, 283–285, 284*b*
  strangulation, 285–287, 285*f*, 286*f*
  suicide notes, 285
  suicide *vs.* accident, 295
  summary for, 279
Asthma, 265, 266*f*
Atherosclerosis, 198–199, 198*f*, 200*f*, 201*f*
Atrial septal defect, 262, 262*f*
Attorneys, report release to, 36
Autolysis, 58
Autopsy, 71–98
  body admission to morgue, 73–79, 74*f*, 75*f*
  of children, 254–257, 254*f*
    measurement for, 339*f*
  closing of body, 92–93
  events after, 33
  evidence collection during, 79–89
    DNA swabs, 80–81
    evisceration techniques, 84–89, 85*f*, 86*f*
    femoral blood, 83–84, 85*f*
    fingernail clippings, 79–80
    gunshot residue collection, 79
    sexual assault, 81, 81*f*
    toxicology specimen collection, 82–83, 82*f*, 83*f*
    trace evidence, 80
  gunshot wound description for, 171
  history of, 2
  in hospitals, 2–3
  introduction to, 71
  of multiple gunshots, 177–178
  open-casket funeral after, 67
  overview of, 340*f*
  performance standards for, 18
  personal protective equipment for, 72–73
  photography at, 76–79, 78*f*
  process of, 19
  recording data for, 89–92
    brain retention for dissection, 90
    cassettes for histology, 90, 340*f*
    cultures, 91
    cut box or tissue container, 89–90
    discard policy, 91–92, 92*t*
    DNA specimen, 91
    genetic screen, 91
    homicide evidence, 91
    toxicology specimens, 90
  release of, 34–36
  religious objections to, 3–4
  of sharp-force injuries, 181, 181*f*
  special techniques for, 93–98
    airplane, train, and pipeline fatalities, 98
    anterior neck dissection, 94
    bullet removal from bone, 95

Autopsy *(Continued)*
    counting ribs or spine for fractures, 97–98
    eye removal, 94–95
    inner ear removal, 95
    leg examination for thromboemboli, 95–96
    neck vessel catheterization, 96
    posterior neck dissection, 94
    spinal fluid collection, 93–94
    spine removal, 95
    subcutaneous dissections, 96–97
    tongue removal with neck organs, 97
    turning body over from face up to face down, 93
  summary of, 71
  time to completion of, 36
  X-ray procedures for, 32–33, 75–76
Avulsion, 128, 129*f*

B

B pillar, 136, 136*f*
Babygram, 254–255, 254*f*
Bacterial endocarditis, 203–204, 204*f*
Barrel, 148
Basilar skull fracture, 130
Bite-mark ruler, 78*f*, 79
Bladder removal, 87
Blade, 180, 180*f*
Blanchable lividity, 60
Blood
  decomposition of, 63
  from gunshot wounds, 175
  for infant death investigation, 256
  livor, 59–61, 60*f*
  for toxicology tests, 82
Blood spot, collection of, 23
Blowflies, time of death and, 65, 66*f*
Blunt-force trauma, 121–146, 239–240
  abrasion, 123, 124*f*, 125*f*
  case study for, 122*b*
  contusion, 125–127, 126*f*, 127*f*
  death certification and report writing, 145–146
  definitions for, 122–130
  documentation of, 130–132
    coup *vs.* contrecoup, 131–132
    patterned injuries and toolmarks, 131
  fractures, 128–130, 129*f*
  introduction to, 121–122
  laceration, 127–128, 128*f*, 129*f*
  motor vehicle accidents, 132–146
    airbags, 134–135
    car seats, 134
    case study for, 132*b*
    compression or mechanical asphyxia, 139–140, 139*f*
    driver, 137–138, 138*f*
    evidence collection for, 141–144, 143*f*
    passenger/occupant, 138–139
    pedestrians, 140–141, 141*f*, 142*f*
    photography of, 132–133
    pillars, 136, 136*f*
    questions with, 132
    scene observations for, 133
    seatbelts in, 133–134
    skid marks, 136–137
    tempered glass and laminated windshields, 135–136, 135*f*
  summary of, 121
  trains, 144–145
  work and farm related, 144
Body
  arrival at office of, 32
  morgue admission of, 73–79, 74*f*, 75*f*
  procedures for identifying, 112–115
    CODIS, 113–114
    NAMUS, 114–115, 115*f*
    NCIC, 114
  return to family of, 33
  transport of, 19
  turning over from face up to face down, 93
Bone, bullet removal from, 95
Brain
  anatomy and physiology of, 220–223, 222*f*
  contusion of, 127, 223–225
  death of, 58
  removal of, 86–87, 86*f*, 88–89, 90, 340*f*
Brain hemorrhage, on death certification, 52–53
Bronchioles, 206–207, 206*f*
Bruises. *See also* Contusion
  postmortem, 67
  subcutaneous dissections for, 96–97
Brush-burn abrasion, 124*f*
Bullets, 148
  anatomy of, 154–157, 154*f*
  collection of, 171
  discard policy for, 92
  locations of expended, 175
  photography for, 77
  remote, 53–54
  removal from bone, 95
  X-rays for, 75–76
Bumper injuries, 140–141, 142*f*
Burial, death certification and, 48
Buried bodies, 299–302, 300*f*, 301*b*
Burns, 239, 239*f*, 271
Butt, 180*f*, 181
Buttonhole, 97

C

C pillar, 136, 136*f*
CABG. *See* Coronary artery bypass graft surgery
Caliber, 149
Car parts, for motor vehicle accident evidence, 143–144, 143*f*
Car seats, 134
Carbon monoxide, asphyxia with, 292–293, 292*f*
Carboxyhemoglobin effect, 160–162, 161*f*
Cardiac valves, 203–204, 204*f*
Cardiomyopathy, 205, 205*f*
Cardiovascular death, 194–205
  anatomy and physiology for
    aorta, 194
    circulatory system, 194, 196*f*
    coronary arteries, 197
    gastrointestinal tract and, 194–197
    heart, 194, 195*f*
    normal sinus rhythm, 197–198
  atherosclerosis, 198–199, 198*f*
    aneurysm with, 198–199, 200*f*
    peripheral vascular disease with, 199
    treatment of, 199, 201*f*
  cardiomyopathy, 205, 205*f*
  in children, 262–265
    congenital heart disease, 262–264, 262*f*
    myocarditis, 264
    rheumatic heart disease, 264–265
  dissection of aorta, 204–205
  hypertension, 201–203, 203*f*
  myocarditis and bacterial endocarditis, 203–204, 204*f*
  valvular heart disease, 199–200
Carnivore activity, postmortem, 64–65, 65*f*

Cartridges, 148
  rifle, 155, 156*f*
  shotgun, 155–157, 157*f*
Case flow, 29–38
  autopsy, 32–33
    events after, 33
  body transport, 32
  case notification, 30–31
  case study for, 36*b*
  at funeral home, 34
  information gathering, 32
  office arrival of body, 32
  return of body, 33
  on return to office, 33
  scene arrival, 31–32
Casings, 148, 174, 175
Cassettes for histology, 90, 340*f*
Cause of death
  brain hemorrhage and, 52–53
  on death certification, 46, 46*f*, 47–50, 47*f*
Center for Disease Control, medical examiner and coroner jurisdictions with, 4, 5*f*
Centerfire, 150
Cerebral hemorrhage. *See* Brain hemorrhage
Cerebral palsy, 268
Cerebral spinal fluid collection, 93–94, 347*f*
Certification, for death investigators, 18
Certifying agencies, 11–13
Chain of custody
  documents for, 315*f*
  for evidence, 25, 25*f*
Children, death certification for, 54
Choke, 149
Choke holds, 287–288, 287*f*
Chopping wounds, 189
Chronic obstructive pulmonary disease (COPD), 208, 208*f*
Circulatory system, 194, 196*f*
Circumstantial identification, 111–112
Cirrhosis, 213–215, 214*f*
Clinical forensic medicine programs, 9
Clinical pathology, 11
Closed environments, asphyxia in, 294–295
Clothing
  after autopsy, 92–93
  bullets and, 165
  collection of, 23
  discard policy for, 92
  gunshot wounds and, 159
  for motor vehicle accident evidence, 144
  with sharp-force injuries, 186
Cocaine, 243–244
Codeine, 244
Combined DNA Index System (CODIS), 108*f*, 109, 113–114
Compression asphyxia, 139–140, 139*f*, 288–289, 288*f*
Contrecoup injuries, 131–132, 225
Contusion, 125–127, 126*f*
  of brain, 127, 223–225
  on children, 271–272, 272*f*, 273*f*, 274*f*
  colors of, 125–126
  dating of, 125–126
  dimensions of, 126
  ecchymoses, 127, 127*f*
  patterns of, 126
  with windshield impact, 135, 135*f*
COPD. *See* Chronic obstructive pulmonary disease
Coronary angioplasty, 199, 201*f*
Coronary arteries, 197
  blockage of, 198–199, 198*f*
Coronary artery bypass graft surgery (CABG), 199, 201*f*
Coroner system, 4, 8–9
  jurisdictions of, 4, 5*f*, 8–9
Coroners, 8–9
  death certification by, 46, 46*f*, 50
Co-sleeping, 253–254
Coup injuries, 131–132, 225, 226*f*
Cremation, 297–299, 298*f*
  authorizations for, 55, 299
  death certification and, 48
  disposition after, 299
Crib examination, 252–253, 253*f*
Crime lab technician, evidence collection for, 22–23
Criminalistics, history of, 5–11, 6*f*
Crushing injuries, 239–240
CT scanning, 76
Cultures, 91
Cut box, 89–90
Cut-proof gloves, 135–136
Cyanide, 293
Cystic fibrosis, 266–267, 267*f*

D

D pillar, 136, 136*f*
Dead man float position, 291
Death, physiology of, 58–64
  case study for, 61*b*
  decomposition, 61–64, 62*f*
  livor, 59–61, 60*f*
  rigor, 58–59
  temperature, 61
Death certification, 41–46
  for blunt-force trauma, 145–146
  with blunt-force trauma, 123
  burial and cremation and, 48
  case study for, 52*b*
  cause of death, 47–50, 47*f*
  cremation authorizations, 55
  information needed for completion, 50, 51*f*
  online system for, 33, 50
  problematic, 50–55
    brain hemorrhage, 52–53
    children, 54
    falls, 53
    fractures, 53
    miscarriages, 54–55
    pneumonia, 50–52
    remote motor vehicle accidents, gunshot wounds, or head injuries, 53–54
    seizures, 54
  purpose of, 17–18
  release of, 34
  sections of, 46, 46*f*
  summary of, 41
  template for, 42*f*
  time limit for, 4
Death in line of duty, 312
Death Investigation: A Guide for the Scene Investigator, 12, 18
Death investigators. *See also* Medicolegal death investigators
  abbreviations for death certification, 47*f*
  certification for, 18
  death notification process, 116–118
  at death scene, 16
  experience of, 17
Death notification, 29
  laws for, 29
  process for, 116–118
Death scene investigation, 15–40
  case flow, 29–38
  case study for, 16*b*, 36*b*
  equipment for, 18
  evidence
    chain of custody for, 25, 25*f*
    collection techniques for, 22–25
    preservation in, 18–21

Death scene investigation *(Continued)*
  for gunshot wounds, 174–175
  introduction to, 16–17
  literature review for, 17–18
  medical and social history, 28–29
  by medicolegal death investigator, 26–28
    equipment list for, 27
    investigation briefcase for, 26–27
    response vehicle equipment for, 28
  notification of next of kin, 29
  personal protective equipment at, 72
  photographing, 21–22, 77
  responsibility of, 16
  summary of, 15
  written report formats, 29, 30*f*
Decomposed bodies
  gunshot wounds to, 165–166
  identification of, 29
  photography of, 27
  X-rays for, 75–76
Decomposition
  fingerprints and, 102, 102*f*
  first stage of, 61, 62*f*
  fluids with, 63
  mold formation, 63
  mummification, 63
  postmortem, 61–64
  saponification, 63, 64*f*
  skin slippage, 61–63, 62*f*
  temperature and, 61
Defense wounds, 187, 187*f*
Dental examination X-rays, 76, 104–105, 104*f*
Dental identification, 99, 104*f*
Dentures, 104–105
Depressed fracture, 130
Designer drugs, 245
Diabetes mellitus, 217–219, 218*f*, 268
Diabetic ketoacidosis, 268
Dicing wound, 135–136, 135*f*
Diffuse axonal injury, 274*f*
Digital X-rays, 95–96
Disaster situations, 313–314
Discard policy, 91–92, 92*t*
Disinterment, 303–305
Dismembered remains, 303, 304*f*
Disposable items, from autopsy, 73
Dissection of aorta, 204–205
Distant wounds, 160
  with handgun or rifle, 164–165, 164*f*
  with shotgun, 167, 168*f*
DNA sampling
  for autopsy, 32–33
  for gunshot wounds, 174
  for identification, 106–111, 108*f*, 109*f*, 110*f*
  in NAMUS, 115
  obtaining, 106–107
  for sharp-force injuries, 185
  specimens for, 91
  storage periods for, 92*t*
DNA swabs, 80–81
Down's syndrome, 267
Driver, in motor vehicle accidents, 137–138, 138*f*
Drowning, 289–291
Drug intoxication, 240–241, 241*f*
  autopsy for, 33
Dry specimens, collection of, 23

E

Ear scanning, 101
Earnhardt Family Protection Act, 34–36
Easily broken rigor, 59
Ecchymoses, 127, 127*f*
Edentulous, 104–105
Ejector, 150
Electrocution, 235–237, 237*f*
Electrolytes
  for toxicology testing, 245–246
  vitreous for, 82–83
ELISA. *See* Enzyme-linked immunosorbent assay
Embalmed bodies, 302
Embalming, 65–67, 68*f*, 302
Endocrine abnormalities, 217–219
  diabetes mellitus, 217–219, 218*f*
  pancreas, 217
  pituitary, 219
  thyroid gland, 219
Entombed remains, 303–305
Entrance wounds, 157, 158*f*
  documentation of, 169–170
  with multiple gunshots, 177–178
Environmental deaths, 232
Enzyme-linked immunosorbent assay (ELISA), 246, 247*f*
Epidural hemorrhages, 225
Ethylene glycol, 242
Evidence
  autopsy collection of, 79–89
    DNA swabs, 80–81
    evisceration techniques, 84–89, 85*f*, 86*f*
    femoral blood, 83–84, 85*f*
    fingernail clippings, 79–80
    gunshot residue collection, 79
    sexual assault, 81, 81*f*
    toxicology specimen collection, 82–83, 82*f*, 83*f*
    trace evidence, 80
  chain of custody for, 25, 25*f*
  collection of
    for crime lab technician, 22–23
    for death scene investigation, 22–25
    for gunshot wounds, 171
    hair, 80
    for motor vehicle accidents, 141–144, 143*f*
    for sharp-force injuries, 185–186, 185*f*
    techniques for, 22–25
  for homicide, 91
  preservation of, 18–21
Evisceration techniques, 84–89, 85*f*, 86*f*
Executions, 310–311, 311*f*
Exhumation, 303–304
Exit wounds, 159, 159*f*, 160*f*
  documentation of, 170
  with multiple gunshots, 177–178
Explosions, 239, 239*f*
Exsanguination, 190
External exam, 33
  forms for, 89, 335*f*
Eye donation, 307
Eye removal, 94–95, 347*f*

F

Falls
  brain hemorrhage and, 52
  contrecoup, 131–132
  on death certification, 53
  fractures and, 53
Family, death notification to, 116–117
Family members, death of, 312–313
Farm-related blunt-force trauma, 144
Fatty acid oxidative disorders, 268
Federal Credentialing Verification Service (FCVS), 13–14
Female genitalia removal, 87
Femoral blood
  autopsy collection of, 83–84, 85*f*
  for toxicology tests, 82
Fetal death certificates, 54–55
Film X-rays, 95–96
Fingernails, clipping collection of, 79–80

Fingerprints
  for autopsy, 32–33
  from guns, 174
  from hand glove, 61–63
  for identification, 100–103, 101*f*
    case study for, 103*b*
    IAFIS, 100–102, 103
    ICE, 103
    locating comparisons, 103
    NGI, 101
    problems with obtaining, 102, 102*f*
  from knives, 185, 186
  with mummification, 63
Firing pin, 149
First-pass metabolism, 194–197
Fixed lividity, 60
Flies, infestation by, 61, 65, 66*f*
Fluid measurement, 86, 86*f*, 340*f*
Forensic index, of CODIS, 113–114
Forensic pathologists
  death certification by, 4, 46, 46*f*, 50
  medicolegal death investigators and, 10–11
  notable, 10
Forensic science, 1–2
  mandates, jurisdiction, and laws, 2–4
Formalin
  for brain retention, 90
  for cut box or tissue container, 89–90
  for embalming, 65–67, 68*f*, 302
Four-point restraint systems, 133
Fractures, 128–130, 129*f*
  counting ribs or spine for, 97–98
  on death certification, 53
  posterior neck dissection for, 94
  risk with, 130
  of skull, 130
  sudden death due to, 232
Frostbite, 233
Frozen bodies, 302
Full rigor, 59
Funeral home
  death certification completion by, 46, 46*f*
  events at, 34
  viewable at, 75

G

Gas chamber, 310–311, 311*f*
Gas chromatography-mass spectrometry (GC-MS), 246–247, 249*f*
Gastric sampling, for toxicology tests, 82
Gastrointestinal tract, 215–217
  anatomy and physiology of, 215, 216*f*
  bleeding of, 216–217
Gauge, 149
GC-MS. *See* Gas chromatography-mass spectrometry
Gender, of miscarriages, 55
Genetic screens, 91
  in infant death investigation, 256
Glass fragments, for motor vehicle accident evidence, 143–144, 143*f*
Glass impact, 138
Glass wounds, 189–190
GPS systems, 31
Graze wounds, 157, 158*f*
Grooves, 149, 150*f*
GSR. *See* Gunshot residue
Guard, 180, 180*f*
Gunpowder, 149
Guns
  collection of, 23
  examination of, 153
  photography of, 22
  types and anatomy of, 18–21
Gunshot deaths
  evidence preservation with, 19
  photography of, 22
  remote, 53–54
  suicide *vs.* accident *vs.* homicide, 176–177
  X-rays for, 75–76
Gunshot residue (GSR), 172–173, 172*f*, 173*f*
  collection of, 79, 173, 173*f*
  kits for, 173, 173*f*
  testing of, 172–173
Gunshot wounds, 147–178
  case study for, 177*b*
  DNA and fingerprints for, 174
  entrance *vs.* exit, 157–159, 158*f*, 159*f*, 160*f*
  essential scene documentation for, 174–175
  evidence collection for, 171
  handgun and rifle, 155, 156*f*, 160–166
    to cartilage, 165
    to decomposed bodies, 165–166
    distant, 164–165, 164*f*
    hard-contact, 160–162, 161*f*
    to head, 165
    intermediate, 162–164, 163*f*
    near-contact, 162, 163*f*
    in obese people, 166
  introduction to, 148
  multiple, 177–178
  range of fire and, 160, 161*f*
  report documentation for, 169–171
  shotgun, 167–169, 167*f*, 168*f*, 169*f*
  summary of, 147
  terminology for, 148–150
  test-firing weapon, 169
  worksheet for, 338*f*

H

Hair, trace evidence collection of, 80
Handgrip, 150
Handgun, 23–24, 148
  bullets for, 155
  wounds with, 160–166
    to cartilage, 165
    to decomposed bodies, 165–166
    distant, 164–165, 164*f*
    hard-contact, 160–162, 161*f*
    to head, 165
    intermediate, 162–164, 163*f*
    near-contact, 162, 163*f*
    in obese people, 166
Handle, 180*f*, 181
Hanging, 280–283
  body removal, 309
  with ligatures, 282–283, 282*f*, 283*f*
Hard-contact wounds, 160
  with handgun and rifle, 160–162, 161*f*
  with shotgun, 167, 167*f*
Head
  examination of, 88–89, 340*f*
  gunshot wounds to, 165, 166*f*
  in infant death investigation, 256–257
Head injuries
  coup *vs.* contrecoup, 131–132
  remote, 53–54
Heart
  anatomy and physiology of, 194, 195*f*
  formation of, 264
  removal of, 87, 340*f*
  transplant of, 211*f*
Heart attack. *See* Myocardial infarction

Height, 75
Hepatitis, 215
Heroin, 244
Hesitation wounds, 183–184, 186–187, 186*f*
Hilt, 180, 180*f*
Histology, cassettes for, 90, 340*f*
History of death investigation, 1–14
Hit and run, evidence in, 80, 140
Home births, 275–276
Homicide
  autopsy for, 33
  on death certification, 50
  discard policy for, 91–92, 92*t*
  evidence for, 91
  from gunshot, 176–177
    multiple, 177–178
  with motor vehicle, 145–146
  photography for, 77
  with sharp-force injuries, 190–191
  strangulation, 285–287, 285*f*, 286*f*
  X-rays for, 75–76
Hospital pathologist, autopsies by, 2, 3
Hospitals, autopsy in, 2–3
Hydrocephalus, 267–268
Hydrogen sulfide, 293–294
Hypertension, 201–203, 203*f*
Hyperthermia, 234–235
Hypothermia, 232–233

I

IACME. *See* International Association of Coroners and Medical Examiners
IAFIS. *See* Integrated Automated Fingerprint Identification System
ICE. *See* Immigrations and Customs Enforcement
Identification, 99–120
  circumstantial, 111–112
  dental, 99, 104*f*
  DNA for, 106–111, 108*f*, 109*f*, 110*f*
  fingerprints for, 100–103, 101*f*
    case study for, 103*b*
    IAFIS, 100–102, 103
    ICE, 103
    locating comparisons, 103
    NGI, 101
  introduction to, 99–100
  medical appliances for, 105–106, 106*f*
  next of kin, 116
  procedures for body, 112–115
    CODIS, 113–114
    NAMUS, 114–115, 115*f*
    NCIC, 114
  skeletal structures for, 106, 107*f*
  summary of, 99
  unidentified, 112
Identification band, 74–75, 75*f*, 112–113
Iliac vessels, 83–84, 85*f*
Illicit drug use, 243–245, 259–260
Immigrations and Customs Enforcement (ICE), 103
Immunization, 259
Incision, 128*f*, 181, 181*f*
  defense wounds, 187, 187*f*
  location of, 184
  measurement of, 183–184
  self-inflicted, 183–184, 184*f*
  surgical, 187–188, 188*f*
Indeterminate wounds, 160
Infant protocols, 252
  investigative sheets for, 323*f*
  for X-rays, 76
Infectious disease, 230–232, 231*f*
  in children, 259–262, 261*f*
Inner ear removal, 95, 347*f*
Insect life cycle, postmortem, 65, 66*f*, 67*f*
Insects, collection of, 69
Intake sheet, 50, 51*f*
Integrated Automated Fingerprint Identification System (IAFIS), 100–102, 103
Intermediate wounds, 160
  with handgun or rifle, 162–164, 163*f*
Internal beveling, 165, 166*f*
International Association of Coroners and Medical Examiners (IACME), 13
Interrupted-pattern abrasion, 125*f*
Intracerebral hemorrhage, 223, 224*f*. *See also* Brain hemorrhage
Intracranial hemorrhage, 223–228, 224*f*
Intracranial vessel, ruptured, neck vessel catheterization for, 96
Intrauterine demise, 275
Investigation briefcase, 26–27
Investigative report sheets, 317*f*
Iris scanning, 101
Isopropyl alcohol, 242

J

Jewelry
  after autopsy, 92–93
  at death scene, 19
  plastic vacuum-sealed bag for, 74, 74*f*
  property receipt for, 34, 35*f*
Joint Commission of American Hospitals, autopsies and, 2–3
Jurisdiction
  for coroners and medical examiners, 8–9
  for forensic science, 2–4

K

Kidneys, 220, 221*f*
Kinetic energy, 24, 151
Knee implants, for identification, 105–106
Knives
  anatomy of, 180–181, 180*f*
  collection of, 23, 185, 185*f*
  photography of, 22

L

Labeling, of evidence, 24
Lacerations, 127–128, 128*f*
  avulsion, 128, 129*f*
  with exit wounds, 159, 159*f*
  fracture through, 130
  with graze wounds, 157, 158*f*
  of liver, 215
  margins of, 127–128
  sharp-force injuries compared with, 181
  undermining, 128, 129*f*
  with windshield impact, 135, 135*f*
Laminated windshields, 135–136, 135*f*
Lands, 149, 150*f*
Langer's lines, 182–183
Laws
  for death definition, 58
  for death notification, 29
  for forensic science, 2–4
Leg bumper injuries, 140–141, 142*f*
Leg examination for thromboemboli, 95–96
Lethal injection, 310–311, 311*f*
Licensure
  for forensic pathologists, 11–13
  for physicians, 13–14
Ligatures
  collection of, 23, 24*f*
  discard policy for, 92
  hanging with, 280–283, 282*f*, 283*f*
  homicidal, 285–286, 285*f*

Lightning, 238, 238*f*
Linear fracture, 130
Linen services, 73
Liquid chromatography-mass spectrometry, 246–247, 249*f*
Live births, 55
Liver, 212–215
  anatomy and physiology of, 212–213
  cirrhosis, 213–215, 214*f*
  hepatitis, 215
  laceration, 215
  removal of, 87
Liver tissue, for toxicology tests, 82
Livor, 59–61, 60*f*, 61*b*
Locard's exchange principle, 7–8
Lungs
  anatomy and physiology of, 206–207, 206*f*
  in infant death investigation, 256
  removal of, 87, 340*f*
  transplant of, 211*f*

M

Maintenance of Certification (MOC), 12
Malignant hyperthermia, 235
Mandates, for forensic science, 2–4
Manner of death, 50
  brain hemorrhage and, 52–53
  on death certification, 46, 46*f*, 50
  from sharp-force injuries, 190–191
Manual strangulation, 286–287, 286*f*
Measurement worksheet, 336*f*
Mechanical asphyxia, 288–289, 288*f*, 290*f*
Medical appliances, for identification, 105–106, 106*f*
Medical examiner office, 4, 5*f*, 8–10
Medical examiners, 9–10
  death certification by, 46, 46*f*
Medical history, 28–29
  for sudden death in children, 259–260
Medications
  collection of, 73
  at death scene, 19–21, 20*f*
  log for, 319*f*
Medicolegal death investigators, 10–11
  death scene response by, 26–28
  equipment list for, 27
  investigation briefcase for, 26–27
  response vehicle equipment for, 28
  types of death requiring response by, 26
Meningitis, 260–261, 261*f*
Mental illness, 228
Metabolic disorders, 268
Methadone, 244
Methamphetamine, 244–245
Methanol, 242
Miscarriages, on death certification, 54–55
Missing person database, within NCIC, 114
Mitochondria, 110
Mitochondrial DNA
  nuclear DNA *vs.*, 111, 112*f*
  testing of, 110
MOC. *See* Maintenance of Certification
Model Post-Mortem, 2, 3*f*
Mold formation, 63
Money
  after autopsy, 92–93
  at death scene, 19, 73–74
  plastic vacuum-sealed bag for, 74, 74*f*
  property receipt for, 34, 35*f*
Morgue
  body admission to, 73–79, 74*f*, 75*f*
  personal protective equipment at, 72, 72*f*
  trash disposal from, 73
Morphine, 244
Motor vehicle accidents, 132–146
  airbags, 134–135
  car seats, 134
  case study for, 132*b*
  compression or mechanical asphyxia, 139–140, 139*f*
  driver, 137–138, 138*f*
  evidence collection for, 141–144, 143*f*
  passenger/occupant, 138–139
  pedestrians, 140–141, 141*f*, 142*f*
  photography of, 132–133
  pillars, 136, 136*f*
  questions with, 132
  remote, 53–54
  scene observations for, 133
  seatbelts in, 133–134
  skid marks, 136–137
  tempered glass and laminated windshields, 135–136, 135*f*
  X-rays for, 75–76
MRI scanning, 76
Mummification, 63
  fingerprints and, 102, 102*f*
Murder, families reporting, 305–306
Myocardial infarction, 197*f*
Myocarditis, 203–204, 205*f*, 264

N

NAME. *See* National Association of Medical Examiners
NAMUS. *See* National Missing and Unidentified Persons System
National Association of Medical Examiners (NAME), 12, 18
National Bureau of Vital Statistics, 4
National Crime Information Center (NCIC), 114
National Missing and Unidentified Persons System (NAMUS), 114–115
National Transportation Safety Board (NTSB), 98
Natural death
  autopsy for, 33
  brain hemorrhage and, 52
  on death certification, 50
  fractures and, 53
NCIC. *See* National Crime Information Center
Near-contact wounds, 160
  with handgun or rifle, 162, 163*f*
  with shotgun, 167, 167*f*
Neck dissection
  anterior, 94
  posterior, 94
Neck organs, removal of, 97, 340*f*
Neck vessel catheterization, for ruptured intracranial vessel, 96
Necrosis, 58
Neoplasms, 229–230
  in children, 268
Nervous system, 220–230
  brain and spinal cord anatomy and physiology, 220–223, 222*f*
  delayed deaths due to brain injuries, 228–229
  intracranial hemorrhage, 223–228, 224*f*
  mental illness, 228
  neoplasms, 229–230
Neuromuscular disorders, in children, 267–268

Next Generation Identification (NGI), 101
Next of kin
  identification of, 116
  notification of, 29
NGI. *See* Next Generation Identification
Nonaccidental trauma, in children, 270–275
  extent and duration of injuries, 274–275
Normal sinus rhythm (NSR), 197–198
Notification
  of death, 29
    laws for, 29
    process for, 116–118
  of next of kin, 29
NSR. *See* Normal sinus rhythm
NTSB. *See* National Transportation Safety Board
Nuclear DNA, mitochondrial DNA *vs.*, 111, 112*f*
Numbered plastic seals, 73–74, 74*f*

O
Obesity, gunshot wounds and, 166
Offender index, of CODIS, 113–114
Office personnel, death of, 312–313
Online system, for death certification, 33, 50
Opium, 244
Organs
  after autopsy, 92
  donation of, 306–308
  in infant death investigation, 256
  removal of, 86–87, 86*f*, 340*f*
  weights of, 89
Osteomyelitis, bone fracture and, 128–130
Osteoporosis, 53
  bone fracture and, 128–130
Oxycodone, 244

P
Pacemakers, for identification, 105–106, 106*f*
Pancreas, 217
Passenger/occupant, in motor vehicle accidents, 138–139
Paternity testing, electrophoresis of DNA for, 109, 110*f*
Pathologic fracture, 128–130
Pathological cause, for death certification, 48, 48*f*
Patterned injuries
  in children, 270–271
  documentation of, 131
  in motor vehicle accidents
    of driver, 137–138, 138*f*
    of passenger/occupant, 138–139
PCR. *See* Polymerase chain reaction
Pedestrians, in motor vehicle accidents, 140–141, 141*f*, 142*f*
Pediatric death certification, 54
Penetration, 149
Perforation, 149
Periorbital hemorrhage, 94–95
Peripheral blood, for toxicology tests, 82
Personal effects receipt, 321*f*
Petechiae
  with mechanical asphyxia, 288–289, 288*f*
  with motor vehicle accidents, 139–140
Photography
  of asphyxia, 295
  at autopsy, 76–79, 78*f*
  of blunt-force trauma, 130
  camera for, 27
  of death scene, 21–22, 77
  of dismembered remains, 303, 304*f*
  for infant death examination, 252–253, 253*f*, 255
  of motor vehicle accidents, 132–133
  in NAMUS, 115
  release of, 34–36
  for sharp-force injuries, 186
  for surgical incisions, 187–188
  of tape and ligatures, 23, 24*f*
Physicians
  death certification by, 46, 46*f*, 48
  licensure for, 13–14
  natural death and, 50
Physiological cause, for death certification, 48, 48*f*
Physiology of death, 58–64
  decomposition, 61–64, 62*f*
  livor, 59–61, 60*f*
  rigor, 58–59
  temperature, 61
Pillars, 136, 136*f*
Pipeline fatalities, autopsy for, 98
Pituitary, 219
Plants, time of death and, 69
Pneumonia, 50–52, 208–210, 209*f*, 265
Poisoning, families reporting, 305–306
Poisons, lividity and, 60
Polymerase chain reaction (PCR), 111
Polymorphisms, 111
Positional asphyxia, 289, 290*f*
Posterior neck dissection, 94
Postmortem abrasion, 124*f*
Postmortem redistribution, 240–241
Postmortem X-rays, 104, 104*f*
Power piston, 149
Premortem abrasion, 124*f*
Premortem DNA sample, 107–108
Premortem X-rays, 104, 105
Prescription medications, 242–243
Primer, 149
Prisoners, 309–310
Professional agencies, 11–13
Projectile, 148, 154–157, 154*f*
Property receipt, 34, 35*f*, 321*f*
Prosthetic devices, for identification, 106, 107*f*
Pseudostippling, 135*f*
Pulmonary edema, 207, 207*f*
Pulmonary embolus, 207, 210
Pulmonary hypertension, 211
Pulmonary thromboembolism, 210–211, 210*f*
Pulmonary thrombus, 210

Q
Quality assurance programs, 17

R
Race, of miscarriages, 55
Range of fire, gunshot wounds and, 160, 161*f*
Religious objections, to autopsy, 3–4
Renal abnormalities, 220, 221*f*
Reportable diseases, 231*f*
Respiratory death, 206–211
  anatomy and physiology for, 206–207, 206*f*, 207*f*
  asthma, 265, 266*f*
  case study for, 266*b*
  in children, 265–267
  COPD, 208, 208*f*
  cystic fibrosis, 266–267, 267*f*
  pneumonia, 208–210, 209*f*, 265
  pulmonary hypertension, 211
  pulmonary thromboembolism, 210–211, 210*f*

- Response vehicle equipment, 28
- Retinal hemorrhage, 94–95
- Revolvers, 151–152, 152*f*
  - photography of, 22
- Rheumatic heart disease, 264–265
- Ribs
  - counting for fractures, 97–98
  - in infant death investigation, 257
- Ricasso, 180, 180*f*
- Rifle, 23–24, 148, 153–154
  - cartridges for, 155, 156*f*
  - wounds with, 160–166
    - to cartilage, 165
    - to decomposed bodies, 165–166
    - distant, 164–165, 164*f*
    - hard-contact, 160–162, 161*f*
    - to head, 165
    - intermediate, 162–164, 163*f*
    - near-contact, 162, 163*f*
    - in obese people, 166
- Rifling, 149
- Rigor, 58–59, 61*b*
- Rimfire, 150
- Road rash, 124*f*
- Rokitansky method, 84, 86, 86*f*
- Ruler
  - for blunt-force trauma, 130–131
  - for photography, 77, 78*f*
- Ruptured intracranial vessel, neck vessel catheterization for, 96
- Russian roulette, 176

S

- Saponification, 63, 64*f*
- Scattered remains, at death scene, 21
- Seatbelts, 133–134, 138*f*
- Seizures, 227–228
  - on death certification, 54
- Self-inflicted wounds, 183–184, 184*f*
- Semi-automatic handguns
  - components of, 152–153, 153*f*
  - photography of, 22
- Sepsis, in children, 260–262, 261*f*
- Sexual asphyxia, 283–285, 284*b*
- Sexual assault exam, 24–25, 81, 81*f*
- Sharp-force injuries, 179–192
  - autopsy documentation for, 181, 181*f*
  - case study for, 188*b*
  - defense wounds, 187, 187*f*
  - evidence collection for, 185–186, 185*f*
  - hesitation wounds, 183–184, 186–187, 186*f*
  - introduction to, 180
  - knife anatomy, 180–181, 180*f*
  - lacerations compared with, 181
  - manner of death from, 190–191
  - measurements of, 182–184
    - depth, 183
    - length, 182, 182*f*
    - width, 182–183, 182*f*
  - other instruments for, 188–190, 189*f*
  - summary of, 179
  - surgical incisions, 187–188, 188*f*
- Shock, with blunt-force trauma, 123
- Short tandem repeats (STRs), 111
- Shot, 148
- Shotgun, 23–24, 148, 154
  - cartridges for, 155–157, 157*f*
  - wounds with, 167–169, 167*f*, 168*f*, 169*f*
- Shotgun shell, 148
- Side mirrors, 140
- Skeletal remains
  - of infants, 276
  - in NAMUS, 115
- Skeletal structures, for identification, 106, 107*f*
- Skid marks, 136–137, 140
- Skin blebs, filling of, 62*f*
- Skin slippage, 61–63, 62*f*
- Skull
  - fractures of, 130
    - in children, 273*f*
    - coup, 131
  - gunshot wounds to, 165, 166*f*
- Slashing injuries. *See* Incision
- Social history, 28–29
- Social Security Administration Office, Death Master File of, 100
- Soot deposition
  - with hard-contact wounds, 160–162, 162*f*
  - on head wounds, 165
  - with near-contact wounds, 162, 163*f*
- Special removals, 308–309
- Spinal cord
  - anatomy and physiology of, 220–223, 222*f*
  - spine removal for, 95, 347*f*
- Spinal fluid collection, 93–94, 347*f*
- Spine
  - counting for fractures, 97–98
  - of knife, 180, 180*f*
  - removal of, 95, 347*f*
- Spleen removal, 87
- Stab wounds, 181, 181*f*
  - air embolus with, 190
  - airway compromise with, 191
  - defense wounds, 187, 187*f*
  - delayed death with, 191
  - description of, 183
  - diagram of, 182*f*
  - photography of, 22
  - worksheet for, 337*f*
- Standards for Classification of Federal Data on Race and Ethnicity, 55
- Steering wheel abrasions, 137
- Stent placement, 199, 201*f*
- Stock, 150
- Storage periods, 91–92, 92*t*
- Strangulation, 285–287, 285*f*, 286*f*
  - anterior neck dissection for, 94
- Stroke. *See* Intracerebral hemorrhage
- STRs. *See* Short tandem repeats
- Subarachnoid hemorrhage, 225, 227*f*. *See also* Brain hemorrhage
- Subclavian blood, 83–84
- Subcutaneous dissections, 96–97
- Subcutaneous hemorrhage, 96–97
- Subdural hematomas, 131
- Subdural hemorrhage, 223. *See also* Brain hemorrhage
- Sudden death
  - in adults, 193–250
    - introduction to, 193–194
    - summary of, 193
  - alcohol related, 241–242, 241*f*
  - blunt force and crushing injuries, 239–240
  - body temperature disorders, 232–235
  - burns and explosions, 239, 239*f*
  - cardiovascular, 194–205
    - anatomy and physiology for, 194–198, 195*f*, 196*f*, 197*f*
    - atherosclerosis, 198–199, 198*f*, 200*f*, 201*f*
    - cardiomyopathy, 205, 205*f*
    - dissection of aorta, 204–205
    - hypertension, 201–203, 203*f*
    - myocarditis and bacterial endocarditis, 203–204, 204*f*
    - valvular heart disease, 199–200
  - in children, 251–278
    - acquired diseases, 268–270
    - autopsy procedure for, 254–257, 254*f*

Sudden death *(Continued)*
    broad causes of, 276*f*
    cardiac, 262–265
    congenital and genetic counseling, 270
    fetuses and home births, 275–276
    food in, 257–258
    foreign objects, 258
    illness, 259
    infections and sepsis, 260–262
    introduction to, 251–252, 252*f*
    left in vehicles, 275
    medical history, 259–260
    metabolic disorders, 268
    neoplasms, 268
    neuromuscular disorders, 267–268
    no cause identified, 276–277
    nonaccidental trauma, 270–275
    public health notifications, 270
    respiratory, 265–267
    summary of, 251
  drug intoxication, 240–241, 241*f*
  endocrine abnormalities, 217–219
    diabetes mellitus, 217–219, 218*f*
    pancreas, 217
    pituitary, 219
    thyroid gland, 219
  environmental, 232
  fractures, 232
  gastrointestinal tract, 215–217, 216*f*
  illicit drug use, 243–245
  infectious disease, 230–232, 231*f*
  investigation techniques for, 252–254
  lightning, 238, 238*f*
  liver, 212–215, 214*f*
  natural causes of, 194
  nervous system, 220–230
    brain and spinal cord anatomy and physiology, 220–223, 222*f*
    delayed deaths due to brain injuries, 228–229
    intracranial hemorrhage, 223–228, 224*f*
    mental illness, 228
    neoplasms, 229–230
  prescription medications, 242–243
  renal abnormalities, 220, 221*f*
  reporting of, 4
  respiratory, 206–211
    anatomy and physiology for, 206–207, 206*f*, 207*f*
    COPD, 208, 208*f*
    pneumonia, 208–210, 209*f*
    pulmonary hypertension, 211
    pulmonary thromboembolism, 210–211, 210*f*
  workplace causes of, 235–240, 236*f*, 237*f*
Suicide
  with carbon monoxide, 292–293, 292*f*
  on death certification, 50
  discard policy for, 92
  by drowning, 289, 291
  from gunshot, 176–177
  by hanging, 280–281, 282, 282*f*
  with hydrogen sulfide, 293–294
  with motor vehicle, 145
  with sharp-force injuries, 190–191
  X-rays for, 76
Surgical incisions, 187–188, 188*f*
Surgical plates, for identification, 105–106
Suspected strangulation, anterior neck dissection for, 94
Synthetic cathinones, 245

T

Tape, collection of, 23, 24*f*
Tardieu spots, 288*f*
Temperature
  decomposition and, 61
  disorders of, 232–235
    hyperthermia, 234–235
    hypothermia, 232–233
  postmortem, 61
Tempered glass, 135–136, 135*f*
Test-firing weapon, 169
Tetralogy of Fallot, 262, 262*f*
Therapeutic abortion death certificates, 55
Therapeutic misadventure, on death certification, 50
Three-point restraint systems, 133
Throat, 281*f*
Thromboemboli, leg examination for, 95–96
Thyroid gland, 219
Time of death, 57–70
  embalming and, 65–67, 68*f*
  introduction to, 57
  investigative techniques for, 67–69
  physiology and, 58–64
    decomposition, 61–64, 62*f*
    livor, 59–61, 60*f*
    rigor, 58–59
    temperature, 61
  postmortem carnivore activity, 64–65, 65*f*
  postmortem insect life cycle, 65, 66*f*, 67*f*
  summary of, 57
Tissue
  container, 89–90
  donation of, 306–308
Tissue microscopic slides, storage periods for, 92*t*
Tissue paraffin blocks, storage periods for, 92*t*
Toe tags, 113
Tongue removal, 97, 257
Toolmarks, documentation of, 131
Toxicology sampling
  for autopsy, 32–33
  collection for, 82–83, 82*f*, 83*f*
  electrolytes, 245–246
  ELISA, 246, 247*f*
  GC-MS for, 246–247, 249*f*
  in infant death investigation, 256
  liquid chromatography-mass spectrometry for, 246–247, 249*f*
  for motor vehicle accidents, 141–143
  specimens for, 90
  storage periods for, 92*t*
Trace evidence, 79, 80
Traffic accidents. *See* Motor vehicle accidents
Train fatalities
  autopsy for, 98
  blunt-force trauma of, 144–145
Transplant, of heart and lungs, 211*f*
Trauma panel, 75–76
Trigger, 150
Trisomy 21, 267
Two-point restraint systems, 133

U

Unclaimed decedents, in NAMUS, 115
Undermining, 128, 129*f*
Undetermined death
  of children, 276–277
  on death certification, 50
Unidentified person database, within NCIC, 114
Unidentified remains, 112
  at autopsy, 74–75

  discard policy for, 91–92, 92*t*
  worksheet for, 320*f*
  X-rays for, 75–76
United States Medical License Exam (USMLE), 13–14
Unnatural death, on death certification, 46, 46*f*
Urine, for toxicology tests, 82
U.S. Standard Certificate of Death, 42*f*
USMLE. *See* United States Medical License Exam
Uterus removal, 87

V

Valuables. *See* Jewelry; Money
Valvular heart disease, 199–200
Vehicles
  anatomy of
    airbags, 134–135
    car seats, 134
    pillars, 136, 136*f*
    seatbelts, 133–134
    tempered glass and laminated windshields, 135–136, 135*f*
  children left in, 275
Venous marbling, 61, 62*f*
Venous system, 85*f*
Ventricular septal defect, 262, 262*f*
Virchow method, 84, 86*f*, 87
Vitreous
  in infant death investigation, 257
  location to obtain, 82–83, 83*f*
  for toxicology tests, 82

W

Wadding, 149, 168, 169*f*, 171
Washerwoman hands
  drowning and, 291
  fingerprints and, 102, 102*f*, 351
Washing Away of Wrongs, 2
Weight sheet, 89
Wet specimens, collection of, 23
Wet-dry technique, 80–81
Witness, 352–353
Workplace causes of death, 235–240, 236*f*, 237*f*
Work-related blunt-force trauma, 144
Woven-pattern abrasion, 125*f*
Written report formats, 29, 30*f*

X

X-rays, 104, 104*f*, 105
  for autopsy, 32–33, 75–76
  dental, 76, 104–105, 104*f*
  of fractures, 129*f*
  for infant death investigation, 254–255, 254*f*
  technology for, 95–96

Y

Y-shaped incision, 84, 340*f*
  closing of, 92–93, 340*f*

Third edition

KNIGHT'S
Forensic Pathology



Pekka Saukko • Bernard Knight

KNIGHT'S
Forensic Pathology

Those who have dissected or inspected many bodies have at least learned to doubt, while those who are ignorant of anatomy and do not take the trouble to attend to it, are in no doubt at all.

Giovanni Morgagni 1682–1771
The Father of Morbid Anatomy

**Taceant colloquia. Effugiat risus. Hic locus est
ubi mors gaudet succurrere vitae.
(Let conversation cease. Let laughter flee.
This is the place where death delights to help the living.)**

Latin proverb

Seldom say never – seldom say always!

Forensic proverb

Third Edition

KNIGHT'S Forensic Pathology

Pekka Saukko Dr.med.univ. (Vienna), Dr.Med.Sci., Specialist in Forensic Medicine, Dr.h.c.
Professor and Head, Department of Forensic Medicine, University of Turku, Finland

Bernard Knight CBE, MD, DM (Hon), BCh, MRCP, FRCPath, FHKCPath, DSc (Hon), LLD (Hon), PhD (Hon), DMJ (Path), Barrister of Gray's Inn
Emeritus Professor of Forensic Pathology, University of Wales College of Medicine, UK
Formerly Consultant Forensic Pathologist to the Home Office, UK

HODDER
ARNOLD
PART OF HACHETTE LIVRE UK

First published in Great Britain in 2004 by Hodder Arnold,
part of Hachette Livre UK
338 Euston Road, London NW1 3BH

http://www.hoddereducation.com

© 2004 Edward Arnold (Publishers) Ltd

All rights reserved. No part of this publication may be reproduced or transmitted in any form or by any means, electronically or mechanically, including photocopying, recording or any information storage or retrieval system, without either prior permission in writing from the publisher or a licence permitting restricted copying. In the United Kingdom such licences are issued by the Copyright Licensing Agency:
Saffron House, 6–10 Kirby Street London EC1N & 8TS.

Whilst the advice and information in this book are believed to be true and accurate at the date of going to press, neither the author[s] nor the publisher can accept any legal responsibility or liability for any errors or omissions that may be made. In particular (but without limiting the generality of the preceding disclaimer) every effort has been made to check drug dosages; however it is still possible that errors have been missed. Furthermore, dosage schedules are constantly being revised and new side-effects recognized. For these reasons the reader is strongly urged to consult the drug companies' printed instructions before administering any of the drugs recommended in this book.

British Library Cataloguing in Publication Data
A catalogue record for this book is available from the British Library

Library of Congress Cataloging-in-Publication Data
A catalog record for this book is available from the Library of Congress

ISBN: 978 0 340 76044 4

5 6 7 8 9 10

Commissioning Editor: Serena Bureau
Development Editor: Layla Vandenbergh
Project Editor: Anke Ueberberg
Production Controller: Deborah Smith
Cover Design: Stewart Larking

Typeset in 10/12.5 AGaramond by Charon Tec Ltd., A Macmillan Company
Printed and bound in India

What do you think about this book? Or any other Arnold title?
Please send your comments to feedback.arnold@hodder.co.uk

Contents

Preface to the third edition *vi*
Preface to the second edition *vii*
Preface to the first edition *viii*

1 The forensic autopsy 1
2 The pathophysiology of death 52
3 The establishment of identity of human remains 98
4 The pathology of wounds 136
5 Head and spinal injuries 174
6 Chest and abdominal injuries 222
7 Self-inflicted injury 235
8 Gunshot and explosion deaths 245
9 Transportation injuries 281
10 Abuse of human rights: deaths in custody 301
11 Burns and scalds 312
12 Electrical fatalities 326
13 Complications of injury 339
14 Suffocation and 'asphyxia' 352
15 Fatal pressure on the neck 368
16 Immersion deaths 395
17 Neglect, starvation and hypothermia 412
18 Deaths associated with sexual offences 421
19 Deaths associated with pregnancy 431
20 Infanticide and stillbirth 439
21 Sudden death in infancy 451
22 Fatal child abuse 461
23 Deaths associated with surgical procedures 480
24 Dysbarism and barotrauma 488
25 The pathology of sudden death 492
26 Forensic dentistry for the pathologist 527
27 Poisoning and the pathologist 541
28 Forensic aspects of alcohol 552
29 Carbon monoxide poisoning 560
30 Agrochemical poisoning 566
31 Poisoning by medicines 570
32 Death from narcotic and hallucinogenic drugs 577
33 Corrosive and metallic poisoning 585
34 Deaths from organic solvents 595

Appendix 1 Technical methods *600*
Appendix 2 Council of Europe Committee of Ministers Recommendation No. R (99) 3 *610*

Index *618*

Preface to the third edition

It is pleasant to record that the second edition of *Forensic Pathology* consolidated the international reputation of the original book as one of the foremost manuals of forensic pathology in the English language. This new third edition generally follows the same successful pattern, but there are some significant differences.

The editorship is being transferred to Professor Pekka Saukko and this volume is the product of the collaboration with the original author. As with previous editions, the text has undergone a complete revision to update where necessary and add new material where relevant. A major change is the extensive use of colour to replace original monochrome illustrations and in numerous new illustrations, including micrographs. More than 300 colour illustrations have been added, of which 175 are completely new from the archives of both the Cardiff and Finnish institutes, and others. Another major improvement has been in the reference material where both corrections and numerous additions have been made. 'Further reading' is intended for those readers who do not have access to electronic libraries and to offer an overview of the literature on a particular topic.

The new edition maintains the philosophy of evidence-based forensic pathology with emphasis on the avoidance of over-interpretation, which regrettably still leads to instances of miscarriage of justice.

It is hoped that the new edition of this well-established textbook, with its emphasis on practical procedures and common-sense evaluation of autopsy findings, will continue to be of assistance to forensic pathologists all over the world.

Pekka Saukko
Bernard Knight

Preface to the second edition

The most gratifying reception accorded in many parts of the world to the first edition of this book has led to the need for an updated version less than five years later. No radical changes have been made in the format, but like an airliner during its periodic major service, every part has been scrutinised and replaced where it has become outdated or defective. In addition, new material has been added where appropriate.

Forensic pathology, unlike its sister discipline forensic science, does not change quickly or have dramatic developments such as the current DNA revolution. Indeed, because its base is the interpetation of autopsy findings, forensic pathology still rests largely on the principles of morbid anatomy founded in the nineteenth century and earlier. However, this is not to say that it remains fossilised in the era of Virchow – new findings and techniques appear constantly, albeit at a measured pace compared with other disciplines. The most useful of these advances have been incorporated into this new edition.

In particular, the sections on child abuse, head injuries and traumatic subarachnoid haemorrhage have been amended or supplemented. Sixty new illustrations have been incorporated, and another area of attention has been the references and recommended reading, as there were some textual citations not listed in the first edition – and very many more have been added. However, the literature is now so vast, both in forensic journals and scattered profusely throughout other specialist publications, that it is futile to try to capture all of even the most seminal papers, which now need computerised and other modern library techniques for their retrieval.

One of the many reviewers of the previous edition complained that many of the references were old, but I make no apology for this. The value of a publication is in its content, not in its date, as Harvey's *De Motu Cordis* and Morgagni's *De Sedibus* clearly demonstrate! Some of the most valuable papers in forensic pathology were written decades or even a century ago; the critical writings of Moritz, Shapiro, Adelson, Helpern, Gonzales, Polson – right back to Taylor and Tardieu in the nineteenth century – are examples of careful observation and logical thinking which some modern pathologists, given to overinterpretation, would benefit from studying.

The critical attitude to every autopsy finding has been maintained in this new edition. A number of recent criminal trials and Appeals have emphasised the vital need for expert medical witnesses to be totally objective in their interpretation of physical findings. To quote from the new (1996) *Practice Guidelines* of the Policy Advisory Board in Forensic Pathology of the British Home Office: 'The evidence should be objective: speculation should be avoided. Unwarranted conclusions can never be defended. The role of the expert witness is not to provide the evidence which supports the case for the Crown nor for the defence, unless that opinion is objectively reached and has scientific validity.' Perhaps, in the interests of justice, an additional new forensic aphorism should be on the frontispiece: 'If you can't prove it, don't claim it!'

Bernard Knight
1996

Preface to the first edition

This is a textbook of forensic *pathology*, not forensic *medicine*. Though there is a considerable overlap, forensic medicine includes medical jurisprudence, the legal aspects of medical practice and many ethical matters, none of which are found – nor are intended to be found – in these pages.

Such topics have marked geographical limitations, as a result of legal, ethnic, cultural, and even religious variations from place to place. Even within the British Isles it is almost impossible to write a single book on medical jurisprudence that can do equal justice to the different legal systems of England and Wales, Scotland and Ireland.

The subject matter of this volume has no such geographical constraints, as it is solely concerned with the examination of the dead body for medicolegal purposes. Even in this limited sphere, police procedures and the habits of pathologists will vary considerably with country and with resources, but it is hoped that the routines, techniques and philosophy offered in this book will offer a guide to good practice that can then be modified according to local circumstances.

The contents are intended to lead the pathologist – and in some countries, the non-pathologist – through the procedures that are needed in the examination of a body found under obscure, suspicious, or frankly criminal circumstances.

In developed countries with sophisticated medicolegal systems, such autopsies will be performed only by forensic pathologists or by histopathologists with considerable experience, but in many areas of the world – especially the developing countries – lack of manpower and resources as well as considerations of distance and facilities mean that almost any doctor may be called upon to perform medicolegal examinations. For both of these classes of medical men and women this book aims to act as a guide and a source of reference.

The subject matter follows a fairly conventional pattern, but the treatment of each topic is designed to offer practical advice linked with a philosophical approach that leads the doctor to analyse and question the interpretations drawn from physical findings.

All too often, dogmatic opinions are derived from an unsound factual base, learned from lectures or textbooks that repeat previous dogma with little sense of critical evaluation. In some parts of the world forensic pathology is learned by rote from teachers who studied it themselves in the same fashion, and who have little or no practical experience in the hard schools of mortuary or witness-box. I hope that this book will at least stimulate trainee forensic pathologists to think twice, question and disagree – not least about some of the material in the following pages.

Some conventions have been discarded in the format of this book. The author feels that it is disruptive for ease of reading to have every line clogged with references to other authors, except where essential to the topic under discussion. Thus most references have been consolidated into groups, placed at the end of the appropriate sections in each chapter. In addition to actual references, there are many suggestions for further reading on the same topic. It is quite impossible to be comprehensive in offering relevant titles, as the amount published on forensic matters is now overwhelming, several hundred new titles appearing each month. A representative selection is offered, much of it quite recent – these papers themselves will then offer a relevant bibliography, so that the topic can be followed in almost geometric progression.

There is no discussion of forensic serology, as this is now a discipline of its own. Similarly, the toxicology is confined to a detailed consideration of the pathologist's role in obtaining samples and interpreting the results from the analytical laboratory. Though the most common poisons are discussed, this is purely from the autopsy aspect. Like serology, toxicology is now a vast subject that stands independently and it seems futile merely to scratch the surface in a text devoted to forensic morbid anatomy.

Another departure from the conventional text is that concise reminders of the forensic anatomy of important regions are given, adjacent to the topic under discussion. Many pathologists learned their anatomy a long time ago and it can be useful before an autopsy, or writing the report, or appearing in court, to have a quick refresher about the relations of the aortic arch to the second rib or the exact structure of the laryngeal cartilages. Illustrations in forensic textbooks are traditionally profuse and often spectacular. The only justification for a photograph is that it instructs, however, rather than entertains or shocks. This book uses photographs only where a relevant point is displayed, with a full caption that stands alone without having to refer to the text.

Many line drawings are used, as the author feels that they often get the message across better than a photograph, which of necessity contains irrelevant and perhaps distracting features. Similarly, many books are replete with anecdotal cases; these can be valuable, but often are more intriguing than useful. The space devoted to these can usually be put to better use and they are employed sparingly in this text.

Where the pronoun 'he' is used throughout this book, it is intended that the word 'she' is equally applicable, unless obviously inappropriate from the context.

Finally, an Appendix is offered with basic reference material on weights, sizes, temperatures, conversion tables and other useful facts. Histological and histochemical techniques relevant to forensic needs are given in detail.

Bernard Knight
1990

This page intentionally left blank

CHAPTER 1

The forensic autopsy

- Autopsy standards 1
- Types of autopsy 2
- The procedure for a forensic autopsy 2
- Examination of the scene of death 4
- Property, clothing and identification 8
- The use of the history of the case 9
- Precautions regarding potential infective conditions 10
- The autopsy: external examination 11
- The autopsy: internal examination 16
- Examination of organs 23
- Examination of the brain 28
- Ancillary investigations 29
- Autopsy radiology 31
- Forensic photography 32
- The autopsy report 33
- Post-mortem artefacts 36
- Exhumation 36
- The autopsy on the putrefied corpse 39
- Resuscitation artefacts at autopsy 40
- Mass disasters – the role of the pathologist 41
- The obscure autopsy 44
- References and further reading 47

Though 'necropsy' is semantically the most accurate description of the investigative dissection of a dead body, the word 'autopsy' is used so extensively that there is now no ambiguity about its meaning.

The term 'post-mortem examination' is a common alternative, especially in Britain, where its meaning is never in doubt. Unfortunately, it suffers from a lack of precision about the extent of the examination, for in some countries many bodies are disposed of after external examination without dissection.

The forensic investigation of deaths was introduced relatively early from the requirements of the judicial system. The earliest known forensic dissections took place in Italy, probably in the middle of the thirteenth century, at the University of Bologna. The first one was recorded by William of Saliceto, a surgeon and a teacher on the medical faculty there. He lived from 1210 to 1277 and in his book *Surgery* he mentioned a case examined in about 1275. The principles of the modern medico-legal investigation were developed based on the codes of the sixteenth century Europe: the Bamberg Code in 1507, the Caroline Code in 1532 and later the Theresian Code in 1769. The hospital or clinical autopsy became meaningful first after the introduction of modern concepts of pathogenesis of diseases by Carl von Rokitansky (1804–1878) and cellular pathology by Rudolf Virchow (1821–1902). Further development of medico-legal autopsy has been greatly influenced by the judicial system adopted, the main emphasis in most countries being in the detection and investigation of criminal and other unnatural or unexpected deaths.

AUTOPSY STANDARDS

Discussions about the quality of the autopsy started at the beginning of the nineteenth century. The Austrian decree of 1855 included, in its 134 paragraphs, very detailed instructions as to the performance of medico-legal autopsies. The idea of quality control and quality assurance, first introduced into industrial production of goods in the twentieth century, found its way into medicine later via laboratory medicine. Although regional and national differences in this respect are huge and the pace of progress varies, there is need for standards in specialist education, continuing professional development, harmonization of investigative procedures and quality systems leading perhaps eventually to some form of accreditation of individuals and institutions.

In addition to the national measures to create guidelines and to harmonize the medico-legal autopsy, there has been an increasing international interest in achieving harmonized and internationally recognized rules on the way autopsies should be carried out. In 1991, the General Assembly of the United Nations endorsed the Model Autopsy Protocol of the United Nations. The European Council of Legal Medicine (ECLM) document 'Harmonisation of the Performance of the Medico-Legal Autopsy' was adopted by the General Assembly in London 1995. The latter document served largely as basis for the Pan-European Council of Europe – *Recommendation No. R (99) 3 On the Harmonisation of Medico-Legal Autopsy Rules and Its Explanatory Memorandum* – which was adopted by the Committee of Ministers in February 1999 (see Appendix 2, p. 610). Although the document is a 'recommendation' by nature, it has legal implications, because Council of Europe member countries have to implement these principles into their national legislation.

TYPES OF AUTOPSY

Though medical conventions and legal systems vary considerably from country to country, there are generally two main types of autopsy:

- The **clinical** or **academic autopsy** is one in which the medical attendants, with the consent of relatives, seek to learn the extent of the disease for which they were treating the deceased patient. In most jurisdictions this type of autopsy should not be held to determine the nature of the fatal disease because, if this was unknown to the physicians, the death should have been reported for medico-legal investigation.
- The **medico-legal** or **forensic autopsy**, which is performed on the instructions of the legal authority responsible for the investigation of sudden, suspicious, obscure, unnatural, litigious or criminal deaths. This legal authority may be a coroner, a medical examiner, a procurator fiscal, a magistrate, a judge, or the police, the systems varying considerably from country to country.

In most systems the permission of the relatives is not required, as the object of the legal investigation would be frustrated if the objections of possibly guilty persons could prevent the autopsy.

In many jurisdictions the medico-legal autopsy is often further subdivided into:

- those held on apparently non-criminal deaths, such as accidents, suicides, deaths from sudden natural causes, or associated with medical and surgical treatment, industrial deaths, and so on
- the truly forensic autopsy held on suspicious or frankly criminal deaths, usually at the instigation of the police. These deaths comprise murder, manslaughter, infanticide and other categories that vary in different jurisdictions.

The type of pathologist that deals with these categories also varies from place to place but, as the systems are so diverse, there is little point in discussing the details. What is much more important is that whichever pathologist tackles each type of case, he or she should be trained and experienced in that particular field. Unfortunately, either from lack of staff and resources or because the system is deficient, medico-legal autopsies – especially of major criminal cases – are frequently performed by pathologists inexperienced in forensic procedures.

Another serious defect in many countries is the separation of those who practise forensic pathology from those who profess to teach it in universities. It is impossible to be a credible and convincing teacher unless one has continuing practical experience of the subject.

Even more unfortunate is the performance of medico-legal autopsies by doctors who have no training in pathology at all. Though lack of resources make this a widespread and inevitable practice in many developing countries, the same regrettable practice is seen in some parts of Europe, the Americas and elsewhere. This is to the detriment of the high standard of expertise that is vital for the support of law enforcement and the administration of justice. A poor opinion is often worse than no opinion at all, as in the latter case, the legal authorities will at least be aware of the deficiency in their evidence, rather than be misled by the often dogmatic inaccuracies of an inexperienced doctor.

THE PROCEDURE FOR A FORENSIC AUTOPSY

Though the actual performance of an autopsy is fairly uniform whatever the nature of the death, there are a number of associated matters that vary according to the circumstances. For example, the procedural precautions required in a murder are not necessary in a sudden natural death, and the dissection in a criminal abortion or fatal rape is different from that upon a drowned body.

There are, however, many facets of the autopsy that are common to every death. These will be discussed in turn here, though the full significance of each item is discussed in detail in other chapters.

The objectives of an autopsy

- To make a positive identification of the body and to assess the size, physique and nourishment.
- To determine the cause of death or, in the newborn, whether live birth occurred.
- To determine the mode of dying and time of death, where necessary and possible.
- To demonstrate all external and internal abnormalities, malformations and diseases.
- To detect, describe and measure any external and internal injuries.
- To obtain samples for analysis, microbiological and histological examination, and any other necessary investigations.
- To retain relevant organs and tissues as evidence.
- To obtain photographs and video for evidential and teaching use.
- To provide a full written report of the autopsy findings.
- To offer an expert interpretation of those findings.
- To restore the body to the best possible cosmetic condition before release to the relatives.

Preliminaries to an autopsy

Before the body is even approached, a number of preliminaries are necessary.

AUTHORIZATION AND CONSENT

A medico-legal autopsy is carried out at the behest of the appropriate authority. The pathologist must not begin his examination until he is satisfied that such authority has been issued in respect of that particular death. The means of delivering such authority will vary from place to place: it may be a written document, a verbal or telephoned message, or a tacit standing arrangement.

Where two official organizations are involved, it must be clear who has the premier right to order an autopsy. For example, in England and Wales, the police may request a pathologist to examine a body externally at the scene of death, but the right to order an autopsy is the sole prerogative of the coroner. Though in serious incidents he or she should take the advice of the Chief of Police regarding the choice of a pathologist, the final decision remains that of the coroner.

As stated earlier, in a medico-legal autopsy the relatives are not consulted for their consent to autopsy, as such permission cannot be withheld. As a matter of courtesy it is usual to inform them before the autopsy is carried out unless the circumstances are too urgent. In most cases, however, a relative will have attended to identify the body before the examination begins. Pathologists should be cautious about performing autopsies where the authorization or consent aspects are not clear. It sometimes happens that a ‘consent document’ for a hospital death has been obtained but the case has later been reported for medico-legal investigation. The pathologist should not then proceed under the ‘consent’ authority until the coroner or other official has decided whether to order his own autopsy (perhaps using another pathologist). If that official decides not to proceed, then usually the consent document becomes valid once more.

Permission for the retention of material from an autopsy (ranging from small fluid samples to the entire body, if necessary) is usually covered in a medico-legal case by the original authority issued for the examination. There is, however, considerable variation in the legal aspects of tissue and organ retention in different countries, and each pathologist must become fully conversant with local regulations.

In the legislation controlling the English coroner, it is not only permissible, but also obligatory, for the pathologist to retain any tissue that may assist in the further investigation of the death.

However, the coroner (or procurator fiscal in Scotland) has only a negative power to forbid the use of tissues or organs for purposes other than the investigation of the death, and so cannot give positive consent for the use of these for transplantation, teaching or research; such permission must be obtained from the relatives, if the coroner does not object, under the Human Tissue Act 1961 and the forthcoming Human Tissue Act 2005.

Who may be present at an autopsy

Once again, each nation or state has different legislation and regulations on the conduct of medico-legal examinations. Though it is pointless to try to survey these, it must be emphasized that every pathologist must learn and abide by the laws applicable to his or her position.

Often the relatives of the deceased person, or an accused person, must be informed of the place and time of the autopsy so that they may be represented by a lawyer or doctor acting on their behalf. In some jurisdictions, including Britain, there is nothing that specifically forbids the relatives attending in person and the authors have had several experiences of this nature. It is open to the pathologist to refuse to conduct the autopsy if he objects to their presence.

In many homicides, a second autopsy is performed by another pathologist acting on behalf of the defence lawyers representing the accused person. This usually takes place at a later date, after the accused has been charged and granted legal representation, but sometimes the second pathologist will attend the original autopsy. This is quite in order and is more valuable than a later exploration of extensively dissected and autolysed tissues.

The permission for such attendance is granted by the coroner, medical examiner, or equivalent legal authority. The first pathologist should grant his colleague every courtesy and facility in the expectation of similar behaviour when the roles are reversed.

Others entitled to be present naturally include the officials or deputies of the department ordering the autopsy – for example, a coroner, magistrate or judge. The police, including their technical teams, are also present if the death is criminal or suspicious. Whether other doctors and medical students are allowed depends upon the wishes of the official commissioning the examination. When the deceased has been under medical care before death, it is almost invariable practice to allow – and indeed encourage – the physician to be present, as he has the best knowledge of the medical history.

In a criminal or suspicious case, the pathologist should try to limit the number of those present to a minimum. Not only is there a greater risk of loss of confidentiality, but sheer physical numbers, especially of large policemen, can make the mortuary overcrowded. This hampers movement, causes distraction, and adds to the risk of infection and contamination, especially with the present concern about the various forms of hepatitis (B, C, D, E), tuberculosis and human immunodeficiency virus (HIV) infectivity. No one should be present merely as a casual observer, not even senior police officers not directly involved in the investigation. With the increased sophistication and complexity of forensic and police procedures, more and more people cram into the mortuary, cluttered with cameras, videos, recorders, scene-of-crime kits and so on, until there is hardly room for the pathologist to move.

Whoever is present at an autopsy on a criminal or suspicious death should be listed and named by the pathologist on the autopsy report.

EXAMINATION OF THE SCENE OF DEATH

In homicide, suspected homicide, and other suspicious or obscure cases, the pathologist should visit the scene of the death before the body is removed.

Once again, local practice varies but any doctor claiming to be a forensic pathologist should always make himself available to accompany the police to the locus of the death. This duty is often formalized and made part of a contract of service for those pathologists who are either full-time or substantially involved in assisting the police. In England and Wales, the 'Home Office Pathologists' are permanently on call for such visits and in many other jurisdictions, such as the medical examiner systems in the USA, and the European State and University Institutes of Forensic Medicine, there is usually a prearranged duty roster for attendance at scenes of death. The function of an experienced forensic pathologist at the scene of death is generally to assess the environment, the local circumstances, and the position and the condition of the body. In a large proportion of instances crime can rapidly be excluded in favour of accident, suicide or even natural causes. This is a most useful and cost-effective function, as a spurious murder investigation involving perhaps scores of police, many vehicles and other expensive public facilities, may be disbanded promptly when the pathologist recognizes innocent circumstances.

The pathologist should always have appropriate equipment ready to take to a scene investigation at a moment's notice. Further equipment may be carried if autopsies have to be carried out in places where good mortuary facilities are not available. Most forensic pathologists carry a 'murder bag' in their car and though every expert has his own choice of equipment, the following is a reasonable inventory:

- waterproof apron and rubber gloves
- thermometer, syringes and needles, sterile swabs
- autopsy dissection set, including handsaw
- cutting needles and twine for body closure
- swabs and containers for blood and body fluids
- formalin jars for histological samples
- plastic bags, envelopes, paper, spare pen and pencil
- printed body charts for recording external injuries
- hand lens, electric torch, mini-tape recorder
- camera, usually 35 mm single-lens reflex with electronic flash. The recent advent of compact digital cameras or digital video cameras with the facility to take still pictures has made instant reviewing possible.

The thermometer can be either a long chemical mercury type, reading from 0 to 50°C, or the more modern electronic digital variety with a probe carrying a thermocouple. The amount of equipment varies with the facilities likely to be available. In developed countries there are likely to be good mortuary facilities available in a hospital or municipal mortuary and the police forces will have extensive scenes-of-crime expertise with photography, specimen containers and so on. In developing countries and the more remote areas of other states, the pathologist may have to be virtually self-sufficient in respect of both crime investigation and the subsequent autopsy.

In addition to medical kit, the experienced forensic pathologist will always have appropriate clothing such as rubber boots and rain- or snow-wear ready to hand for any call.



FIGURE 1.1 *The scene of a rape-homicide. The attending pathologist must record the posture, state of clothing and general relationship of the victim to the surroundings, but limit the examination at the scene to avoid any interference with the vital process of obtaining trace evidence. Rectal temperatures should not be taken until all swabs are completed, usually in the mortuary. Temperatures can be taken in the ear or deep nostrils, though with severe head injuries (as here) even this must be done with care.*

When at the scene of death, the pathologist's actions are dictated by the particular circumstances. Much will depend upon the availability or otherwise of police and forensic science assistance. In Britain, for example, several teams converge on a scene of crime, including photographers and video operators, and Scene of Crime Officers (SOCOs) whose function is to collect trace evidence. Scientists from the nearest forensic laboratory often attend with their police liaison officers, as well as fingerprint officers and, of course, the investigating officers from the Criminal Investigation Department.

Where no such backup is available, the pathologist must try to collect trace evidence himself, but he should remain within the limits of his own expertise.

The pathologist should accept the instructions of police officers in relation to the approach to the body so as to preserve the immediate environment as much as possible. Out-of-doors access is often limited to a single pathway marked by tapes, and in a building a track to the corpse is usually pointed out by the detective in charge.

The doctor should not touch anything unnecessarily and certainly not smoke or leave any object or debris of his or her own. Increasingly, those visiting the scene of a crime are given disposable overalls and overshoes to wear, so that fibres, hairs and so on from the visitor are not spuriously transferred to the scene.

If a forensic doctor has to act both as pathologist and clinical medico-legist or 'police surgeon' (that is, examining live victims or suspects), he or she must change clothing or wear a new set of protective garments to avoid transferring trace evidence, such as fibres or hairs, from victim to suspect.

The pathologist should observe a great deal, but do very little. He or she should note the position of the body in relation to nearby objects and establish the plan of the premises if indoors. A sketch or his own photograph is sometimes useful, and some pathologists use a Polaroid, digital or video camera for instant recording of the death scene.

Any obvious cause of death should be observed, and any blood pools or splashes noted in relation to the position of the corpse. The shape of such splashes should be observed,

FIGURE 1.2 *Scene of a homicide-suicide where the locus of bodies should be widely marked off by tape to restrict access, and the actual body protected by a shelter from the weather and unauthorized onlookers.*



FIGURE 1.3 *At a scene of crime, the position of the body at the time of an assault can sometimes be clarified by observing the direction of blood splashing that may have been thrown off a weapon or blood-stained hands. Blood striking vertically causes round or crenellated circles, while blood hitting at an angle is lance-shaped with the narrow end facing the direction of travel. There is often a preceding drop of blood in advance of the major splash, forming an 'exclamation mark' stain.*

as blood striking perpendicularly to a surface leaves a circular mark, whilst that landing obliquely is pear-shaped, with the sharper end towards the direction of flight.

When photographs have been taken of the body in its original position, the pathologist then approaches it, after checking with the investigating officers that it is appropriate for him to do so. Close examination can be made and the skin felt to assess temperature. The eyes, neck and hands can be examined and where necessary, clothing gently moved aside to look at the throat or upper chest. Any relevant findings should be photographed by the police before further disturbance.

If forensic scientists or scene of crime officers require any samples at this stage, their wishes must be respected. They may want to 'tape' the body, that is, press adhesive tape across the skin and clothing to capture any loose hairs and fibres. The body can then be moved to look at the sides and undersurface, again with caution so that no weapon, other object or trace evidence is disturbed. No set routine can be advised, as each case has its own individual aspects. The prime object is to assess the whole scene while causing the least disturbance to the body and clothing before the scientific teams have finished their tasks.

Estimating the post-mortem interval at the scene

The last sentence above raises the matter of estimating the time since death. The problem is fully discussed in Chapter 3, but has relevance here in relation to the pathologist's actions at the scene of death.

The general warmth or coolness of the hands and face can be assessed by touch, and the degree of rigor mortis felt by gently testing the limbs. The ambient (environmental) temperature must be taken as soon as possible after the discovery of the body, preferably by police scene of crime officers who usually arrive at the locus before the pathologist. The ambient temperature should be taken as near to the body as possible, as microenvironments can exist, even inside buildings or rooms. Information should be sought as to how much disturbance of the ambient temperature might have occurred, such as opening doors and windows, or turning fires or central heating on or off, so that some idea of post-discovery distortions of temperature can be estimated later. The insertion of a thermometer into the rectum at this stage in the investigation, as advocated by some textbooks, is controversial.

At a scene of death, this usually means either pulling down trousers or pants, and otherwise disturbing clothing, often in cramped and ill-lit places, frequently out in the open. It also risks contaminating the rectum and perineum, by introducing seminal fluid from the anal margin into the rectum, making subsequent examination of that area (and taking swabs for semen) of reduced value. As so many violent crimes now have sexual or homosexual overtones, the practice of taking rectal temperatures at the scene should be performed only if the forensic scientists or police scene of crime officers are satisfied that trace evidence from the clothing, swabs from the vulva, vagina and anus, etc., can be obtained satisfactorily before rectal thermometry is performed.

In other words, a cost–benefit analysis must be made at the scene, to decide if the difficulties of taking a rectal temperature are worth the small potential advantage of an earlier measurement. In many cases, where the body has obviously been there long enough for the core temperature to have reached ambient – or where other circumstantial evidence has indicated that the time of death is known to a greater degree of accuracy that can be hoped for by thermometry – then nothing is lost by postponing the procedure until the body arrives at the mortuary for autopsy, which, in British practice, is usually directly after the body is moved from the scene.

If the autopsy is to be delayed for many hours owing to difficulties with transport or lack of facilities, then much more must be done at the scene and temperature measurements are justified.

An alternative is to use a place other than the rectum. The axilla and mouth give low readings, which cannot reliably be correlated with the deep temperature because of variable exposure to the air temperature. More useful is the auditory meatus or nostril, the thermometer or thermocouple probe being inserted as deeply as possible. Reliable, reproducible readings can be obtained from these sites, which have the great advantage of being easily accessible without moving clothing, as well as not being required for swabbing to investigate possible sexual assaults. The use of temperatures to attempt to calculate the post-mortem interval is discussed fully in Chapter 3.

When the pathologist has made the best examination possible in the circumstances, his next function is to ensure that the corpse is removed to the mortuary for autopsy with the least disturbance and loss of evidence. He should supervise the removal himself or at least delegate the duty to another person whom he knows is careful and competent. Each hand should be enclosed in a bag, secured at the wrist by adhesive tape or string. A similar bag should be placed over the head. The packaging medium may vary, but generally paper bags are recommended.

The body should be placed gently in a ‘body-bag’, which has a zip closure, or moved on to a large, new plastic sheet, at least 2 metres square. If a sheet is used, the edges should be wrapped over the body and secured with adhesive tape. The object of the exercise is to retain any loose objects, hairs and fibres that may be adhering to the body or the clothing. The sheet or bag is taken by the forensic laboratory after the body is removed in the mortuary so that they may screen it for trace evidence. The transport of the body is the responsibility of the police or other agency such as the coroner or his officer. The body in its plastic wrapping should be placed in a rigid fibreglass ‘shell’ or ordinary coffin, and taken by hearse, van or police transport to the chosen mortuary.

Physical damage during the removal should be avoided as much as possible, though in difficult or inaccessible sites this is easier said than done. In fires, the body may be seriously damaged before or during recovery, sometimes because its presence is not suspected in the smoke-filled, often waterlogged, debris of a conflagration. The author (BK) has experience of such a scene where firemen walked over two bodies for several hours before it was realized that they were buried under burnt furniture and other debris. Handling brittle, charred, bodies can easily cause the splits at joints that may mimic ante-mortem injuries (see Chapter 12).

In summary, the function of a pathologist at any scene of suspicious death is to observe the situation, to conserve any fragile evidence, to supervise the removal of the body and offer an opinion, based on experience, about the nature of death where this can reasonably be done. He is not there to act as a latter-day Sherlock Holmes, voicing unsubstantiated theories on non-medical matters, nor attempting to overinterpret the situation from the flimsiest of facts. The pathologist is part of a team of specialists, all experts in their own field, and it is as a member of such a cooperative, coordinated group that his best contributions can be made.

PROPERTY, CLOTHING AND IDENTIFICATION

Whether or not the pathologist has been to the scene of a death, he should take notice of the clothing and other property of the body upon which he is to carry out an autopsy. This applies not only to every criminal or suspicious death, but also to many traffic and industrial accidents, as well as to the victims of falls from a height, drowning and so on.

In many instances, there will be no opportunity to examine the clothed body in the mortuary: if death has occurred in hospital or in an accident department, the clothing may have been removed before transfer to the mortuary. The pathologist should make a permanent request that a body from any traffic accident, or other case where trauma was the provisional cause of death, should be brought to the mortuary without having the clothing removed by police or nursing staff – unless of course the victim was still alive on arrival at hospital, and undressing was performed before attempted resuscitation or treatment. As a second best, the removed clothing should accompany the body to the mortuary so that it can be examined, if necessary, for damage, stains and other evidence. Unfortunately, such clothing is frequently destroyed before it can be seen.

The mortuary staff should be trained to regard clothing and property as important items of evidence, and a system should be established to retain, identify and store these, both from the evidential aspects and for the safety of valuables. The contents of the pockets, documents, keys and other items all assist in identification. Though primarily the task of the police, the pathologist will sometimes have an interest in this aspect. The clothes themselves, the style, fabric, colour and labels all assist in identity.

In trauma deaths, the injuries on the body should be matched up with damage on the clothing. Tears, slashes, stab wounds and especially firearm wounds in the clothes must be compared with the position of external lesions on the body, making allowance for movement and displacement during life. Some self-inflicted wounds may be confirmed by the non-alignment of the clothing damage with the injuries (see Chapter 8).

Blood, seminal, vaginal and other body secretions may be found on the clothing, and though this is primarily the responsibility of the forensic science laboratory, the pathologist may be the first or only person to detect their presence. In firearm deaths, gunshot residues on the clothing may be vital evidence about the range of the discharge and the identity of the ammunition.

In traffic fatalities, tearing of the clothes, grease marks, road dirt, broken lamp or windscreen glass, and even metallic or paint fragments from the vehicle may all assist in reconstructing the event and in identifying the unknown vehicle in a ‘hit-and-run’ tragedy.

Other objects associated with the body that may be helpful include medicines, which may assist in determining the nature of the disease from which the deceased had suffered, for example, amyl nitrite or insulin. In some suicides, empty drug or poison containers may be with the body. Other helpful artefacts include such items as hearing aids, syringes, external pacemakers and inhalers. The clothing must be removed carefully and, especially in criminal or suspicious cases, the pathologist should supervise and assist the mortuary technician, especially as some technicians are not always aware of the importance of clothing in the reconstruction of events.

If the body is not bleeding or otherwise fouled, it is best to remove clothing in the usual way by pulling over the head and limbs, unless this might interfere with any injuries or soiling. If rigor is intense or if there is blood on the face or hands, it may be advisable to cut off some or all of the clothing. This should be done after consultation with the forensic scientists, if they are present, so that the cuts will be made where they will least interfere with later laboratory examination. In any event, cuts should avoid passing through pre-existing damage or staining of the garments. Each item of the clothing should be placed separately into a paper bag to allow them to ‘breathe’.

Identification of the body

The identification of an unknown body is a major forensic exercise, and is fully discussed in Chapter 4. Here, however, we are concerned with the formal recognition of the subject of an imminent autopsy. Before a pathologist makes any examination (and certainly before he begins any mutilating dissection), it is essential that he ensures that the corpse before him is indeed the correct person.

In every medico-legal case, some responsible person must have identified the body. This is usually a relative or close friend of the deceased person, who looks at the face of the body and verbally certifies to a police officer, mortuary attendant or doctor that it is indeed ‘John Smith’. Where the body is burned beyond recognition, mutilated or putrefied, attempts at identification must be made by showing the relative documents, or items such as clothing or jewellery.

In non-criminal cases, such as sudden deaths and most accidents and suicides, the continuity of identity is carried on by a label or tag attached to the body by the police officer, nursing staff or mortuary attendant, which carries the name, address, serial number and other relevant details. This label may be tied firmly to a toe, or a durable wrist or ankle bracelet may be used. Some mortuaries write the name on the leg with an indelible marker, but this can be smudged or obscured during autopsy.

The pathologist should always satisfy himself of the identity by comparing the documents authorizing the autopsy with the toe label or bracelet. The details should agree and, if they do not, he should not proceed with the autopsy until the discrepancy is cleared up, if necessary by calling back the police officer or even the relative to make absolutely sure of the identity.

Many mistakes have been made in the past, with adverse publicity, embarrassing enquiries and even legal consequences. Autopsies on the wrong person, incorrect causes of death, relatives attending the wrong funeral and even cremation of the wrong body are regularly reported as a result of laxity in identification. To avoid confusion, the body should always be labelled as soon as it arrives in the mortuary. Labels on shrouds become detached and those on refrigerator doors are unreliable, as other parties (such as night porters) may shift occupants around without the knowledge of the pathologist or regular mortuary staff.

Some large mortuaries use special means of identity. One known to the authors has an automatic camera fitted in the ceiling of the mortuary entrance. Every new body wheeled in is photographed on its trolley with a serial number prominently displayed on a board placed across the upper chest, so that the face appears with the record number to resolve any later discrepancy.

In serious cases such as homicide, the pathologist must not rely on second-hand evidence of identity such as a toe label. Before the autopsy, someone must verbally confirm to him that the body they are both then viewing is 'John Smith'. This person must be either a relative or the police officer to whom a relative has already formally identified the corpse.

The pathologist must record in his autopsy report the date, time and particulars of the person identifying the body to him, so that 'continuity of evidence' is ensured for legal purposes, which cannot successfully be challenged by the defence at a subsequent trial.

THE USE OF THE HISTORY OF THE CASE

As in clinical medicine, the history of the deceased 'patient' or victim is a vital and indispensable part of the investigation. The extent to which it should influence the pathologist in coming to a decision as to the cause of death, however, is more controversial, as is discussed below.

In medico-legal autopsies – compared with hospital 'clinical' cases – the history is often scanty, absent or misleading. If a person has been found dead, having had no previous medical attendant, there may be virtually no information at all. In criminal deaths, the person who knows most about the death may well be the perpetrator, who naturally may remain silent or give a distorted, misleading or totally false account of the circumstances. The forensic pathologist then often has to contend with a scanty or incorrect history.

Even when a story is given in good faith by relatives, the medical facts are often distorted because of incomplete knowledge and understanding. It may be further warped by transmission by a police officer or other non-medical person, so that only a garbled history reaches the pathologist. The latter should attempt to supplement deficiencies in information by further requests to the commissioning authority, such as the coroner or the police. Wherever possible, the pathologist should try to contact the doctor who may have treated the deceased in the recent past. In the urgency of forensic work, however, frequently at night or weekends, the autopsy may have to proceed without any additional history.

Though more detail may be obtained afterwards, the course of the autopsy might well have been different if such knowledge was available beforehand. For example, the author (BK) once performed an autopsy on a coal miner with no history other than a knowledge of his occupation and chronic chest disease. Autopsy revealed sufficient cardiopulmonary disease to account for death and the body was released for burial. It was not until the following day that the police in the rural area where the man had died, tardily produced the information that both an empty bottle of sleeping tablets and a suicide note had been found with the body. Paradoxically, the history is often less important in violent deaths where the wounds are self-evident, though a good description of the circumstances may assist in interpreting the direction of injuries, the nature of the weapon and other aspects.

In most autopsies the history directs the pathologist to the appropriate ancillary investigations, as should have happened in the case described above. Some pathologists have in the past advocated that the autopsy should be performed 'blind', so that the history does not prejudice the opinion of the pathologist. This is patently impracticable, for every autopsy would then have to be totally comprehensive, including such techniques as the removal of the spinal cord in every case, and all possible ancillary investigations, such as toxicology, microbiology, virology, radiology, diatoms, histology and so on, as there would be no means of knowing what was necessary and what was irrelevant. Apart from the intolerable burden of work, the expense of such an approach would be prohibitive, if applied to all autopsies.

A particular difficulty often arises in relation to bodies returned to a home country after death in a foreign state.

The problems vary greatly with the degree of both pathological and administrative sophistication of the foreign country. Where these are poor, then the problems of obtaining a good – or even any – history may be great, even after attempts at using international police or diplomatic channels.

Sometimes, a 'doctor-to-doctor' approach by telephone or fax may be the best way of obtaining information. Even a cause of death from the foreign country may be either unobtainable or so vague (such as 'heart failure') as to be useless. Previous autopsies may be incomplete, of poor quality, or even fraudulent, such as finding a stitched skin incision but no underlying dissection of organs. Several surveys of such problem autopsies have been published, with a plea for some kind of International Death Certificate (Green 1982; Leadbeatter 1991).

Difficulties arise when objective autopsy findings are scanty or even absent. The pathologist then has the dilemma of choosing between a cause of death based on a subjective knowledge of the alleged history (which may be wrong) or admitting that the cause of death is unascertained.

This problem, fully discussed by Leadbeatter and Knight (1987), is by no means uncommon. For example, sufferers from epilepsy or asthma are known to die suddenly and unexpectedly, an autopsy usually revealing no adequate morphological cause for their death. Another prime example is the sudden infant death syndrome, discussed in Chapter 21, where by definition there are no significant autopsy lesions and the history is usually essentially barren.

In hypothermia where the patient is warmed up in hospital but dies in a day or two, there may be nothing to find at autopsy, yet there is firm clinical history of a rectal temperature of 26°C. Moving to more forensic cases, a body may be recovered from a river after clothing and a suicide note have been found on the bank – yet at autopsy there may be no visible evidence of drowning whatsoever.

In these cases, should the pathologist – in the absence of objective evidence of hypothermia or drowning – decline to offer a cause of death and perhaps be accused of being obstructive or perverse? Or should he certify 'hypothermia' or 'drowning', and perhaps be challenged in court by a lawyer who claims that the pathologist relied only on hearsay and has no objective evidence to offer?

The best course is for the pathologist, if he feels that the history is sufficiently strong, to give the most likely and reasonable cause of death, but make it clear in his discussion in the autopsy report that this opinion is based on a consideration of the circumstances and is not a dogmatic statement of the kind that could be offered if the victim was shot through the brain. Where a summary of the history prefaces the autopsy report, the pathologist should be careful to indicate what is 'hearsay' as far as he is concerned. Thus he should not say 'The deceased was struck on the head by two men', but 'I was told that the deceased was struck on the head by two men'.

As is discussed later, the autopsy report should not be merely a bald recital of the anatomical findings, but should have a final commentary that includes a 'differential diagnosis' where the cause of death is not clear cut, as well as a justification for the eventual opinion or an admission that there is no way of deciding between alternative possibilities.

The main difficulty arises with the actual 'cause of death' phraseology, which will be entered into the legal and national records in the format required by the World Health Organization. This gives no opportunity to express preferences or give explanations but, on the 'best-guess' principle, the pathologist can do no more than enter his most reasoned choice or, with legitimate honesty, state that the cause is 'undetermined'.

PRECAUTIONS REGARDING POTENTIAL INFECTIVE CONDITIONS

Many forensic situations involve drug abusers and persons with promiscuous sexual behaviour, where the statistical risk of HIV and hepatitis infection is markedly greater than in the general autopsy population. This poses a risk to pathologists, mortuary staff, police and laboratory staff who may deal with post-autopsy samples. A great deal has been written about such risks but no consensus has yet been reached, though an excellent survey has been published by the Royal College of Pathologists (1995).

One school maintains that all autopsies should be carried out with total precautions against infective risks, so that it does not matter what case is handled. However, this is almost impossible to achieve in a busy coroner or medical examiner practice and does not solve the problem of possibly infected material being sent out to other laboratories.

A more common regime is to carry out pre-autopsy testing for HIV and hepatitis, using blood from a femoral needle puncture. The result can often be returned within hours, when a decision may be made as to how to handle the autopsy – or even whether to abandon it, if the risk–benefit aspect is high. More usually, a positive result will result in the autopsy being carried out with special care, additional protective clothing, visors, masks and metal gloves, with restriction of access to observers, choice of more senior technicians and warnings sent to laboratories liable to handle samples.

In this respect, hepatitis is more of a risk than HIV infection. However, so far, about 100 health-care workers have acquired HIV infection from definite occupational exposure (Sidwell *et al.* 1999) and one pathologist is known to have become infected from autopsy work (Johnson *et al.* 1997). Also three morticians in the USA have possibly contracted occupation-related HIV positivity.

The time for which a corpse remains potentially contagious with HIV is variable. Infectious virus has been recovered from liquid blood held at room temperature for 2 months and virus in high concentrations has been found to remain viable for 3 weeks (Cao *et al.* 1993). Bankowski *et al.* (1992) found 51 per cent survival of virus in plasma and monocyte fractions from infected cadavers up to 21 hours post-mortem. Other series found survival in corpses from 18 hours to 11 days after death. Virus has been recovered from the spleen after 14 days post-mortem. Refrigeration seems to make little difference to viability. Douceron *et al.* (1993) cultured blood and effusions from refrigerated bodies and obtained viable virus up to 16 days post-mortem and concluded that there was no safe maximum time at which corpses ceased to be an infective risk. In industrialized countries, it has become standard to offer post-exposure prophylaxis after significant percutaneous exposure to blood or tissues of HIV patients.

Other infections, such as tuberculosis, hepatitis viruses, anthrax, plague, Creutzfeldt–Jakob, Marburg, Green Monkey diseases, etc., are usually the subject of specific health and safety regulations, which vary from country to country.

THE AUTOPSY: EXTERNAL EXAMINATION

In contrast to the 'clinical autopsy' performed to evaluate natural disease, the importance of the external examination is far greater in the forensic case, especially in deaths from trauma. In the latter, the medico-legal value of the external description may be paramount, as it is often from the outer evidence that inferences may be made about the nature of the weapon, the direction of attack and other vital aspects. Thus the forensic pathologist must spend all the time that is necessary in a careful evaluation of the body surface and not be too impatient to wield the knife mainly to seek material for histology, which is more justified in the purely clinical autopsy.

The routine for external examination will naturally vary according to the nature of the case but certain general principles apply. The following procedure is a useful baseline and may be adjusted according to personal preference. Variations in criminal cases to accommodate the needs of the investigating and scientific teams are mentioned later.

- After identification and removal of any clothing, the race and gender are noted. The apparent age is assessed in children by size and in adults by changes in skin and eyes, such as the loss of skin elasticity, senile hyperkeratosis, Campbell de Morgan spots, senile purpura and arcus senilis. Hair colour, tooth loss and arthritic changes are also obvious signs of ageing. The apparent age should be compared with the alleged age and enquiries made about any obvious discrepancy, in case it is the wrong body, an error which plagues most autopsy rooms from time to time.
- The body length is measured from heel to crown (in infants, more detailed measurements are described later). Ensure that the attendant does not take the 'undertaker's height' from toe to crown, as due to the plantar flexion of rigor, this can be a considerable number of centimetres more than the live standing height.

  It should also be appreciated that the post-mortem height may differ from the known living height by several centimetres. There are several opposing causes of variation, which do not necessarily cancel each other.



FIGURE 1.4 *External examination must note every feature; here there is obvious abdominal distension in a battered child with facial bruising. The intestine had been ruptured by a blow, and oxygen administered by the ambulance crew escaped to distend the peritoneal cavity.*

For example, muscle flaccidity allows joints to relax, unless rigor is present, but intervertebral discs appear to shrink, allowing shortening.

- The body weight in kilograms is measured if facilities are available; if not, it should be estimated. The weight of infants must always be measured. The general nutrition and physique is assessed in terms of obesity, leanness, dehydration, oedema, emaciation, and so on.
- The state of cleanliness, personal hygiene, hair and beard length, toenail and fingernail state, and urinary and faecal soiling is noted. Any parasitic infestation, such as fleas or lice, is combated before proceeding.
- The general skin colour is noted, especially hypostasis (discussed at length in Chapter 2). Congestion or cyanosis of the face, hands and feet is sought. Localized discoloration, especially unilateral in a limb, suggests arterial embolism or incipient gangrene. Pink or brownish pink patches over the large joints may indicate hypothermia (Chapter 17). Other abnormal colours include the brownish hue of methaemoglobinaemia in some poisonings, the bronze speckling of clostridial septicaemia and the dark red of cyanide that somewhat resembles the cherry-pink coloration of carboxyhaemoglobin. Naturally racial pigmentation will modify the ease with which abnormal skin coloration can be seen.
- Congenital deformities of any type are recorded, from talipes equinovarus to spina bifida, from a naevus to extra toes.
- Acquired external marks may be important for identification purposes or in relation to past injuries and disease. Tattoos, circumcision, amputations, surgical scars, old fracture deformities and scars of injuries, burns or suicidal attempts on the wrist and throat are noted. These are discussed further in Chapter 3. Increasingly, artefacts – both external and internal – arise from resuscitation attempts and must be carefully distinguished from original trauma. This emphasizes the importance of the history, to determine whether cardiopulmonary resuscitation was attempted by trained or untrained persons.
- The hands should be carefully examined for such signs as old and new injuries, defence wounds, bruised knuckles and electrical marks. The latter are often insignificant and difficult to see unless the rigor of flexed fingers is overcome, either by force or even cutting the flexor tendons at the wrist.
- Vomit, froth or blood may be present at the mouth and nostrils, and faeces and urine may have been voided. This must be correlated with the degree of post-mortem decomposition, which often leads to purging of fluids from orifices; most forensic pathologists have had the experience of being called by the police to the scene of ‘a fatal haemorrhage’, to discover only bloody fluid being purged by gases from a decomposing corpse.

Vaginal discharge or bleeding is noted and the ears examined for leakage of blood or cerebrospinal fluid. Post-mortem ejaculation of semen from the external



FIGURE 1.5 *Post-mortem artefacts on the body of a homicide victim. These are due to defibrillator paddles applied in a hospital casualty department.*

meatus is of no significance and can be seen in any type of death. It was shown by Mant (1984) not to be associated with sexual activity immediately before death. It is not particularly associated with asphyxial deaths, as sometimes stated.

- The degree of rigor mortis is assessed by flexing the arms and legs to test the resistance. The significance of this and hypostasis is discussed in Chapter 2.
- Recent injuries (other than scars already noted) are carefully examined. In fact this part of the autopsy is often the most significant element of forensic cases. Injuries may be conveniently recorded in the mortuary by marking them on printed body diagrams. The forms can be secured on a clipboard and the data later transcribed into a written description for the autopsy report. The original diagrams should be retained, as their production may be demanded in court if there is controversy about any particular injury.

All traumatic lesions should be clearly differentiated into abrasions, bruises, lacerations, incised wounds, burns and so on, according to the definitions given in Chapter 4. The shape and condition of the margins of each injury should be described where appropriate. It must be meticulously measured in terms of length, breadth, orientation to the axis of the body and the position with reference to surface anatomical landmarks. For example, a knife wound of the thorax might be described as follows, using ordinary language to explain any medical terms:

> A stab wound was present on the left upper chest, placed obliquely, with the inner end lower than the upper outer end. The wound was 20 mm in length, which extended to 22 mm when the edges were opposed. The maximum width at the centre was 4 mm. The centre of the wound was just below the line joining the nipples, being 6 cm from the midline, 7 cm from the left nipple and 18 cm below the centre of the left clavicle (collar bone). The wound was 132 cm above heel level and was elliptical in shape, with the inner lower end slightly more sharply cut than the rather blunt upper end. The wound was shelved in a downwards direction, with subcutaneous tissue visible along the inside of the upper edge.

This description, along with police photographs, will convey an excellent impression of the wound at any future date, including at the trial, which may be many months later. The position of the injury is related to obvious anatomical points and the height above the ground may have relevance if the stature of the victim and assailant, and the angle of attack, become legal issues. On the scalp, the occiput and the tip of the ear can be used as reference points, together with the vertex and the centre line of the head. On the face, the obvious landmarks are the eyebrows, nasion, tip of nose, lips, point of chin and angle of jaw. Where large areas of abrasion or bruising are present, similar measurements of lesion size are needed, but more general descriptions of position may be sufficient, such as ‘covering the external aspect of the left thigh’ or ‘extensive bruising 23 cm by 18 cm on the right side of the chest extending from axilla to costal margin’.

Where widespread burns are present, an estimate of the total area using the ‘Rule of Nine’ should be made, as described in Chapter 11.



FIGURE 1.6 *Full external examination is vital, including the interior of the mouth. Here a large number of amylobarbitone capsules offer a presumptive cause of death, though analytical confirmation is still required.*

Other injuries, such as firearm wounds, are described in the same manner, being careful not to clean off any powder residues or other trace evidence before the forensic scientists have collected their samples.

With head injuries, the scalp is examined in its original condition first and any trace evidence collected. Then any clotted blood that frequently obscures the injuries can be gently removed, using a sponge and water. After this stage has been studied, it is usually necessary to shave off hair carefully around the wounds, so that the full extent of the lacerations and especially the state of their margins can be assessed and photographed. This shaving is best carried out with a scalpel fitted with a new blade, the blade being kept almost parallel with the surface to avoid making false cuts. The procedure should be carried out by the pathologist himself and not delegated to a mortuary technician. In this way any artefactual cuts can be recognized as such and not misinterpreted as part of the original wound.

■ The eyes must be examined carefully, especially to detect petechial haemorrhages on the outside of the eyelids, conjunctivae and sclera. Though these do not necessarily indicate an asphyxial process, such petechiae require an explanation. Petechiae should also be sought behind the ears and in the skin of the face, especially around the mouth, chin and forehead. Care must be taken to differentiate these fine petechiae from the more coarse intradermal blood spots often seen across the shoulders or upper chest, which are caused by post-mortem hypostasis in a body with marked agonal venous congestion – especially when that surface of the body has been dependent. Haemorrhages in postural hypostasis are of no diagnostic significance, as true ante-mortem bleedings can never be differentiated from those that commonly develop after death.

The size of the pupils is rarely useful, as rigor in the iris musculature can produce any degree of constriction, which may be unequal on either side (see Chapter 2). False eyes, contact lenses, lens opacity and other defects are to be noted. It is not possible to evaluate the degree of visual acuity during life from any type of post-mortem examination – though obviously a



FIGURE 1.7 *(a, b) Typical examples of the many anatomical diagrams available for the recording of external findings at autopsy.*

significant defect such as a cataract or a large vitreous haemorrhage is likely to affect vision.

- The mouth may reveal foreign bodies, drugs, damaged teeth, injured gums and lips (especially the ruptured frenulum of child abuse), and the bitten tongue of epilepsy or blows on the jaw. Dentures should be identified and removed before autopsy. Gastric contents in the mouth need not indicate ante-mortem regurgitation, as discussed in Chapter 14, but should be noted. Dried powder on the lips may suggest the recent taking of medicaments or poisons; corrosion of the mouth, lips and chin may be seen in irritant poisons. Bleeding from mouth, nostrils, or ears must be recorded, and later investigated as to source from internal examination. Frothy fluid, sometimes blood-tinged, may be seen issuing from the mouth or nostrils, or both, in drowning and from pulmonary oedema due to a variety of causes. Froth is sometimes pink or frankly blood-tinged. This has no particular significance unless gross, as in drowning, sudden infant death and other conditions with marked pulmonary oedema; rupture of small pulmonary or even pharyngeal vessels can add a little blood to colour the foam.



FIGURE 1.8 *Examination and photography of injuries; after full preliminary examination and forensic sampling, the area is cleaned, shaved if necessary, and photographed with a scale adjacent to the injuries.*



FIGURE 1.9 *Where there are numerous similar lesions, it assists the clarity of the autopsy report if numbers used during photography match those listed in the autopsy protocol.*



FIGURE 1.10 *Scene of crime officers recovering trace evidence from hands before a homicide autopsy. The pathologist must offer the rest of the team every facility to complete their work before he begins his dissection.*

- The external genitals require careful examination, as does the anus. The state of the latter can be misleading, as a widely open, patulous anus is often seen post-mortem, due to flaccidity of the sphincter. The inner mucosa is often visible through the orifice. This is also the case in infants and children, and a diagnosis of sexual abuse must not be assumed without other corroborative evidence such as fresh mucosal tears or swabs positive for semen.

  The 'funnel-shaped' anus, beloved of traditional textbooks as a sign of chronic homosexual activity, is such an extreme rarity that its true existence is doubtful. A funnel shape is a normal anatomical variant, the anus being set deeply between the buttocks, sometimes with a commissure of skin above it, making the approach seem even deeper. The alleged 'shiny, silvery hyperkeratinized skin of the habitual pederast' is also of little diagnostic value as scratching from chronic irritation, often associated with haemorrhoids, viral infections or threadworms, may lead to the same appearance. The only reliable criteria are fresh tears and old scars, as well as mucocutaneous eversion, though even these can arise from severe chronic constipation (see also Chapter 18).

  Examination of the vulva and vagina is made to exclude obvious injury and disease, unless the nature of the case suggests some sexual interference, when a far more detailed examination and a special autopsy technique is carried out (Chapter 18). Routine examination of the male genitals usually need only extend to general inspection of the penis, glans and scrotum, with palpation of the testes. Circumcision should be noted, as (rarely) it may assist in identification.

THE AUTOPSY: INTERNAL EXAMINATION

The dissection in a forensic case is basically similar to any other autopsy, with variations according to the nature of the death and the needs of the particular investigation, whether it be a criminal case, a civil dispute or an accident investigation.

There are a number of manuals devoted to the performance of an autopsy (see Ludwig 2002 or Knight 1996, for example) as well as one for the instruction of mortuary technicians (Knight 1984). Only an outline of the technique is offered here for those unaccustomed to examining the dead who may have autopsies thrust upon them by circumstances. In addition, special forensic procedures are described, though these are also discussed in each of the chapters devoted to the various types of injury and death. The autopsy on infants is dealt with in Chapters 20–22.

The usual incision is an almost straight line from laryngeal prominence to pubis, deviating to avoid the umbilicus. The upper end of this incision should not be prolonged above the larynx, as even a high-necked shroud will then fail to hide the subsequent suture line from relatives.

Another common method is to cut from behind each ear to a point above the manubrium and continue downwards in a 'Y-shape'. This is often done in infants and wherever it is desired to avoid disfiguring the front of the neck. In the USA in particular, the Y-incision is favoured or even a deep 'U-shape' carried across the upper chest.

In strangulation, hanging, and any condition where the larynx might be damaged, the Y-incision is to be preferred, as the skin of the upper neck can then be dissected off the mandible and raised clear to give a wide approach to the neck structures. Here, the incision should not be made until the skull-cap and brain have been removed, to avoid the congestive artefactual haemorrhages in the neck structures, described by Prinsloo and Gordon (1951), which can be confused with true ante-mortem trauma. Gordon *et al.* (1988) have further suggested that the brain be removed first in all autopsies so that abnormal odours can be detected before being swamped by the smell from the opened abdominal cavity.

The Y-incision is also required when dissection of the face is necessary, to look for deep bruising or bony damage. In fact the whole face can be dissected off completely from the skull and replaced with little effect upon the cosmetic result, if careful dissection is employed. The Y-incision in the neck is made continuous with the transverse scalp incision, joining these behind each ear, so that the anterior neck and facial skin can be removed in entirety.

Returning to the autopsy in general, the primary incision should be shallow over the neck to avoid cutting underlying structures, especially the trachea. The thorax can be cut down to the sternum, but care must be taken over the abdomen, where a light cut is made, sufficient to incise only skin and fat. A small puncture should then be made in the peritoneum and a finger inserted to lift it away from the intestines. The knife is then used to cut outwards along the length of the abdomen, to avoid penetrating the intestines.

The incision for access to the skull is made from behind each ear, meeting over the crown of the head. It is well to keep this posterior to the actual vertex, again to make the stitching less obvious, especially where the hair is scanty or absent. With abundant hair – and especially in children – the hair should be wetted and then combed backwards and forwards from a transverse parting made in the line of the prospective incision. Hair is not then severed and can be combed back later to cover the stitching.

Exposing the body cavities

The skin, subcutaneous tissues and fat are flayed off laterally from the main incision, taking care not to let the edge or point of the knife come through the skin, especially in the neck area, where repair can be unsightly. The tissues are taken back to the lateral edge of the neck and to the outer third of the clavicles. Over the thorax, the tissues, including pectoral muscles, are flayed off to the midaxillary line in the upper part and even further posteriorly towards the costal margin.



FIGURE 1.11 *Autopsy incisions: (a) standard midline, (b) 'V-shape' and (c) subclavicular.*

The anterior abdominal wall is similarly separated. This can be done either in two stages, first stripping back the skin and fat to expose the muscles – or the full thickness of skin, fat and muscle can be reflected together. The muscle must be cut from the costal margin and, if thick fat overlies, then some transverse relieving incisions can be made on the peritoneal surface of the lower abdominal wall, taking care not to come through to the skin.

Opening the thorax

The thorax is opened by first disarticulating both sternoclavicular joints. This is carried out by moving the shoulder tip with one hand, to identify the joint capsules. The point of a knife is then introduced vertically and cut laterally in a half-circle to separate the joints. If they are ankylosed, which often occurs in old age, then the clavicles can be cut through at the end of the next operation. This consists of the severing of the ribs and can be performed either with a handsaw or a rib shears. In children and many adults, the costal cartilages may be cut through with a knife, though this provides a rather narrow exposure of the chest contents. In infants, the soft cartilage can easily be divided with a scalpel: in older bodies, a stout knife should be kept for the purpose to save blunting the knife that is needed for organ dissection. Often the first rib has to be sawn through, even though the remainder are cut with a knife.

When a saw is used, the ribs are cut through lateral to the costochondral junctions from a point on the costal margin to the sternoclavicular joints or nearby. If a saw is used, it must be kept at a low angle to avoid the tip lacerating the underlying lung, especially if there are pleural adhesions. When the sternum and medial rib segments are free, the section is lifted and dissected away from the mediastinum, keeping the knife close to the bone to avoid cutting the pericardium. The sternal plate is examined for fractures or other lesions before it is put aside: damage caused by the considerable trauma of resuscitatory cardiac massage is frequently found at this point.

The whole of the thorax and abdomen is now open for inspection. The degree of inflation of the lungs should be assessed, noting complete or partial collapse, emphysema, overdistension and any asymmetry of inflation.

If a pneumothorax has been suspected beforehand, a post-mortem radiograph is the best confirmation. Alternatively, the chest wall can be punctured in the mid-axillary line after filling the reflected skin with water to observe if bubbles escape. This test is rarely successful and cannot succeed if there is a patent communication between the pleural cavity and the bronchial tree. If there is a marked tension pneumothorax, the hiss of escaping air may be heard when the tip of the knife penetrates the intercostal muscles and parietal pleura. The pleural cavities are inspected for adhesions, effusions, pus, blood, fibrin and even gastric contents.

Examining the abdomen

The abdomen is then inspected, though ascites, faeculent fluid, pus and blood may already have escaped on first opening the peritoneal cavity.

The omentum may show inflammation or fat necrosis. When moved aside, the loops of bowel are inspected for any abnormality, especially infarction, peritonitis and the distension of ileus. Beware of mistaking post-mortem hypostasis for the necrosis of mesenteric embolism or strangulated bowel. Though the dark colour may be similar, hypostasis usually has irregular segments when the gut is stretched out, whereas infarction occupies one continuous section – and if well established, the bowel wall will be lustreless and friable.

The bowel is gently moved aside to look at the posterior part of the abdomen: a retroperitoneal haemorrhage from a ruptured aorta may be visible, or an aneurysm itself.



FIGURE 1.12 *The minimum instruments needed for performing an autopsy. Any further items may be useful but not essential.*

The collection of body fluid samples

In a large proportion of forensic autopsies and virtually every one with criminal connotations, samples of blood and other body fluids and tissues are needed for laboratory examination. In relation to sexual offences, the taking of swabs and other samples is described in Chapter 18. Where blood and other fluids are required for toxicological, biochemical, microbiological and serological investigations, they are usually collected at the early stages of the autopsy (see Chapter 27).

The site of collection depends on the nature of the test. When samples for toxicological analysis are required, considerable care should be employed in sampling; this is more fully discussed in Chapter 27.

It is not advisable to use visceral blood for sampling, especially for small molecule substances that can easily diffuse after death; these include alcohol and many pharmaceutical products. Though older textbooks advocate the use of heart blood as a convenient source of samples, it may be contaminated by post-mortem diffusion from the stomach and intestine. After death, the cellular barrier of mucosa and serous membranes breaks down, and substances in the stomach, intestine and air passages can migrate to other organs in the main thoracoabdominal cavity, causing a false rise of the true ante-mortem blood level.

Pounder (1985; see Chapter 27) found that a slurry containing alcohol and paracetamol, placed in the trachea after death to resemble gastric contents, gave rise to appreciable concentrations of those substances in blood samples taken from thoracic vessels, whereas femoral blood remained uncontaminated.

For substances such as carboxyhaemoglobin this does not matter, but alcohol is the prime example of a potential source of error if visceral blood is collected. The better choices for collection sites are:

- by needle and syringe puncture of the femoral vein before the autopsy dissection begins. This requires practice but, in adults, 20 ml can usually be aspirated without trouble. This is the method of choice if only an external examination is possible.
- from the subclavian or external iliac veins after the body has been eviscerated. By holding a small container under the cut end of a subclavian vein and raising the arm, blood can be collected directly. If the flow is slow, the arm can be massaged towards the shoulder. Similarly – and preferably if volume is required – by cutting across the iliac veins at the brim of the pelvis, a container can be dropped into the pelvis with its mouth under the vein and blood massaged into it by firm pressure moved up the inner thigh. As all these containers will be soiled externally, the blood should be decanted into a fresh tube for transmission to the laboratory.
- when the skin is dissected off the neck, the internal jugular vein is exposed, especially if a sternomastoid muscle is divided and pulled aside. When cut, a copious flow of blood is usually obtained, which can be collected directly into a container. The only disadvantage of this method is that if the blood wells



FIGURE 1.13 *White shining fat droplets (chylomicrons) in mesenterial lymphatic vessels suggesting postprandial state.*



FIGURE 1.14 *Toxicology kit issued by the home office forensic science laboratories. Contained in a plastic bag are a large liver tub, a smaller stomach tub, two universal (30 ml) containers, one rubber-capped fluoride vial for blood alcohol, and a syringe and two needles.*

up from the thoracic inlet via the superior vena cava, heart blood is likely to be admixed, with the possible errors mentioned earlier. If the blood is collected from the upper segment of the jugular, then blood from the head is collected: this flow can usually be stimulated by raising and lowering the head during collection.

Samples for serology, microbiology and for analysis for substances such as carboxyhaemoglobin, which are not absorbed from the gastrointestinal tract, can be collected from any blood vessel, but blood should never be scooped up from the general body cavity after evisceration, as this can be contaminated with any leakage from other structures, such as gastric or bowel contents, mucus, urine, pus or serous fluids.

Blood for microbiological culture has traditionally been taken from the heart but there is no particular merit in this as opposed to peripheral blood. If an infective endocarditis is suspected, it is best to open the heart later with a sterile scalpel and excise the mitral or aortic valve cusps or vegetations for direct culture. Otherwise, blood for culture for a suspected septicaemia is taken from a peripheral vein.

Urine can be collected by catheter before autopsy or even by suprapubic puncture with a syringe and long needle. However, it is usually obtained after the abdomen is opened, but before the organs are removed. If the bladder is full, the fundus is penetrated, and urine collected either by syringe or directly into a container. If almost empty and contracted, the fundus is gripped and pulled upwards so that it stretches, then is incised and the contents removed by syringe. Care should be taken not to contaminate the urine with blood.

The removal of vitreous humour and cerebrospinal fluid may be required for toxicology or for attempts at estimating the time since death by the potassium content (see Chapter 2). Vitreous humour must be aspirated with care if any reliable results are to be attained. A fine hypodermic needle attached to a 5 ml syringe is inserted into the outer canthus of the globe after pulling the eyelid aside. When released, the lid will cover the small puncture mark, hiding any sign of interference. The needle should be entered into the centre of the globe to avoid aspirating material near the retina, which has a markedly different chemical composition due to shreds of detached retina entering the aspirate. The fluid should be sucked off slowly and gently, and as much taken as possible to obtain a mixed fluid: both eyes should be used, as they often differ somewhat in their chemical composition. After withdrawing vitreous, the globes can be re-inflated with water, to improve the cosmetic appearance of the eyes.

Cerebrospinal fluid may be obtained in the same way as in living patients, by passing a needle into the theca between the lumbar spines. A baby can be held upright by an assistant in a fully flexed position; an adult must be pulled into flexion whilst lying sideways on the autopsy table. An alternative technique is to perform a cisternal puncture through the atlanto-occipital membrane.

As there is no pressure within the theca in a cadaver, the fluid must be actively aspirated: sometimes all attempts at obtaining fluid by external puncture fail. The only course then is to try to puncture the ventricles through the exposed brain surface when the skull is opened. Attempting to obtain clear cerebrospinal fluid from the interior of the skull after removal of the brain is generally useless: though blood-stained fluid can be centrifuged to clarity, its chemical composition is then unreliable.

Removal of the viscera

After the body cavities have been inspected, the organs are removed *en bloc* by a modified Rokitansky procedure, more accurately described as Letulle's method. First, the intestine is removed, as follows.

The omentum is lifted upwards to expose the coils of small intestine. The uppermost part of the jejunum is identified, where it passes retroperitoneally to join the termination of the duodenum. Here the mesentery is perforated with the knife and the gut cut through. If it is essential to retain the duodenal/gastric contents or the small intestinal contents, two string sutures may be passed through the hole and tied before cutting the gut between them, but little contents are lost if this is not done. The intestine is stripped out by cutting along the mesentery near the attachment with the bowel until the ileocaecal valve is reached.

The caecum is then mobilized medially using manual traction with minimum use of the knife, to avoid puncturing the lumen. When the hepatic flexure is reached, the omentum is pulled downwards to draw the transverse colon tense against the mesocolon, which is cut through, taking care not to open the adjacent stomach. The splenic flexure is then pulled medially and downwards, and the descending and sigmoid colon separated from the posterior abdominal wall. The upper rectum is cut across, though some pathologists merely lay the gut outside the body, leaving the sigmoid and rectum attached.

Removing the neck structures

To make the removal of the neck structures easier, a block 10–15 cm high should be placed under the shoulders of the cadaver. This allows the head to fall back and thus extends the neck. This should be done gently, as with all handling of the body, to avoid the well-known 'undertaker's fracture', which is a subluxation of the lower cervical spine due to tearing of the intervertebral disc at about C6–C7. This can be misinterpreted as an ante-mortem injury, especially if the other common artefact of haemorrhage over the anterior longitudinal ligament of the cervical spine is present (Prinsloo and Gordon 1951). The neck structures are then freed by passing a knife under the skin of the upper neck until it enters the floor of the mouth. The knife is then run around the inside of the mandible to free the tongue. The tissues at the back and sides of the pharynx are divided, and the tonsillar area cut through. Fingers are then passed up behind the mandibular symphysis to grasp the tongue, which is then drawn down, the remaining tissues behind the larynx being divided to release the neck structures. This should be done as far lateral as possible, so that the carotids can be removed with the laryngeal structures. It is now advisable to look into the pharynx and glottis before any further disturbance, to see if any obstruction, bleeding or other abnormality is present in the upper airway.

Removal of the thoracic contents

The subclavian bundles of vessels and nerves are divided by passing the knife from inside the thorax around the medial ends of the clavicles and first ribs to release the trachea and oesophagus. With gentle traction, the neck structures are held up and pulled caudally, whilst carefully clearing all attachments to the thoracic spine with the knife, taking care to keep the blade on the bone and not stray anteriorly to damage oesophagus or aorta.

Traction should be minimal and, as soon as the thorax is entered, the hand should move from the neck structures to place two fingers under the upper lobes of the lungs, lifting them and the mediastinum as the knife clears the midline structures down to the diaphragm. If the neck structures are pulled too hard by using them as a handle to drag out the thoracic viscera, they may be ripped off. In addition, the descending aorta may suffer transverse intimal tears from traction, which resemble the genuine 'ladder tears' seen in many traffic accidents (Chapter 9).

Pleural adhesions may prevent clean removal of the lungs. If there are only a few, they can be cut through. If the whole pleural cavity is obliterated by adhesions, they may be pulled away by making a cleavage plane with the hand and stripping them off. Sometimes (especially in industrial chest disease and old tuberculosis) the adhesions are dense, tough or even calcified. Removal of the lung may then be achieved by running a knife down the whole length of the parietal pleura over the inner anterior aspect of the ribs, and forcing a hand through the slit to form a cleavage plane to force the parietal pleura off the intercostal muscles and ribs.

Removal of the abdominal organs

When the chest organs are free, they are laid back in the thorax and the diaphragm incised. One hand should pull the liver and spleen medially, putting the left leaf of the diaphragm on the stretch, while the knife cuts it through laterally, near the costal margin. The cut curves posteriorly under the organs to reach the spine, where it must cut through the cruciate ligaments, then passes caudally behind the kidney, which is mobilized forwards.

The knife cut then curves up over the psoas muscle and ends at the brim of the pelvis. The same is done on the opposite side, the operator moving around the body if necessary. The chest organs are then lifted and gently pulled forwards to carry the abdominal viscera towards the feet. Any resistance is usually due to incompletely severed cruciate ligaments, which must be transected.

Eventually the organs will lay inverted across the pubis, secured only by the iliac vessels and ureters, which are cut through and the whole pluck of viscera taken away to the dissecting bench where running water and good illumination must be available.

Removal of the pelvic organs

The treatment of the pelvic contents depends on the type of case. Where the presumed cause of death is unrelated to pelvic lesions, then in men the bladder may be opened widely and the mucosa and trigone inspected before the prostate is incised for examination. The testes are pushed upwards through the inguinal canals, which are widened with the knife. In women, the ovaries are incised and the tubes examined from above before the uterus is sliced in the midline from fundus to cervix.

A more thorough examination of either gender may be made by enucleating the pelvic contents. The knife is passed circumferentially around the pelvic bowl after pulling the bladder away from the pubis. When the walls are free, the knife cuts through below the prostate and then through the lower rectum to allow the pelvic organs to be lifted out. In women the ovaries and tubes are mobilized forwards and the knife passed around the wall of the pelvic bowl, then in front of and below the bladder. The vault of the vagina and rectum is transected, freeing the whole contents. In cases where sexual interference or abortion is suspected, a special technique described in Chapter 19 is employed.

Removing the brain

Attention is then turned to the head. The scalp is incised across the posterior vertex from a point behind the ear to the corresponding place on the other side. Where a Y-incision is used on the neck, the limbs of the Y may be continued right across the scalp, especially if a face dissection is necessary.

The tissues are reflected forwards to the lower forehead and back to the occiput. The deep scalp tissues may peel off by traction, but often require touches of the knife to free them. Bruising is sought and, where head injuries are present or suspected, the scalp should be reflected right back to the nape of the neck, paying particular attention to the tissue behind and below each ear where injuries causing vertebrobasilar artery damage occur. Where there are facial injuries, the skin of the face may be peeled back from the jaw line and downwards from the forehead, restoration being excellent if care is taken not to perforate the facial skin during removal.



FIGURE 1.15 *Angled saw-cuts for removal of skull-cap to avoid slippage during reconstruction.*

The skull is sawn through, using either hand or power tools. The line of the cut should not be along a circumference, as it is then impossible to reconstitute the head without unsightly sliding of the calvarium. There should be an angled removal, with a horizontal cut from forehead to behind the ears joined by a second, which passes diagonally upwards at a shallow angle over the occipitoparietal area. Care must be taken not to place this posterior saw-cut too vertically (and thus anteriorly) on the skull, or the brain may be damaged by forcing its removal through too narrow an aperture.

The calvarium is then removed by leverage after complete cutting through. A mallet and chisel should not be used in forensic autopsies, even to ensure that the dura is kept intact. The risk of extending or even causing fractures by the use of excessive hammering is too great merely to justify an unmarked dural membrane. A cut dura is easily recognized as such by any competent pathologist. What is more important is to inspect the surface of the exposed dura and brain and assess any oedema, bleeding or inflammatory conditions that may be present. The skull-cap is carefully inspected for fractures and the dura peeled off the inside to study the inner skull surface.

To remove the brain, the dura is incised around the line of skull removal and two fingers slipped beneath each frontal lobe. With gentle traction the frontal lobes are lifted to expose the optic chiasma and anterior cranial nerves. The falx may have to be cut to free the brain, then a scalpel or blunt-pointed bistoury is passed along the floor of the skull to divide the cranial nerves, carotid arteries and pituitary stalk until the free edges of the tentorium are accessible. A cut is made along each side of the tentorium, following the line of the petrous temporal bones to the lateral wall of the skull. Continuing with traction on the brain, but being careful not to impact the upper surface against the posterior saw-cut, the knife severs the remaining posterior cranial nerves and then passes down into the foramen magnum to transect the spinal cord as far down as can be reached. The hand is now slid under the base of the brain, which is rotated backwards for removal, any attached dura being severed where necessary. The brain is taken into a scale pan and weighed before either fixation or dissection.

The floor of the skull is now examined and the basal dura stripped out with a strong forceps to reveal any basal fractures. Discarded dental forceps can be useful for this purpose. The venous sinuses are incised to search for thrombosis. Where appropriate – and always in infants – the petrous temporal bones are sawn, chiselled or cut with bone forceps to examine the middle and inner ears for infection.

Removal and examination of the spinal cord

It is not an invariable routine to remove the spinal cord at autopsy unless there are indications that some lesion may be present. Where there is the slightest possibility of damage to the vertebral column, its blood vessels or the contents of the spinal canal, however, there should never be any hesitation in extending the autopsy to include this area.

There are several methods of removing the cord and for full details, the texts of Ludwig (2002) or Knight (1983) should be consulted. Briefly, there are two main approaches to the spinal canal, the anterior and posterior.

In the anterior method, the vertebral bodies are removed after complete evisceration of the body, by sawing through the pedicles by a lateral cut down each side. The advantages are that the body need not be turned over on to its face and an extensive dorsal incision is avoided, which requires subsequent repair. The author finds this method more laborious, however, especially in the thoracic region where the heads of the ribs make the approach difficult.

The more usual posterior approach requires a midline incision from occiput to lumbar region, the paraspinal muscles being reflected along with subcutaneous tissues. Two parallel saw-cuts are then made down the length of the spine to divide the right and left laminae, and to give access to the spinal canal. This is best done with an electric oscillating saw, taking care not to cut so deeply that the spinal dura is penetrated. The strip of bone may be dissected off from below upwards to expose the spinal canal.

The cuts should be placed sufficiently lateral to allow the cord to be removed without difficulty. When the canal is exposed, the dura is examined for haemorrhage, infection or other abnormalities, then removed – still within its dural sheath – by transecting the nerve roots and dural attachments, and peeling it out progressively from below upwards. The dura is then carefully opened with forceps and scissors to examine the cord itself. It can be fixed in formalin, as with the brain, before cutting, or dissected immediately and samples taken for histology. Crushing, infarction, infection, haemorrhage and degeneration are the main lesions in a forensic context. The empty spinal canal must be carefully examined for disc protrusions, tumours, fractures, haemorrhage dislocations and vertebral collapse.

Where in any autopsy spinal damage is suspected, a good preliminary test is to slide the hands under the back of the eviscerated body on the autopsy table and lift the dorsolumbar spine upwards, whilst watching the interior vertebral bodies. If a fracture or dislocation is present, abnormally acute angulation will be seen, instead of smooth bending. The cervical spine can be tested by manual manipulation. If suspicious angulation is seen, a slice can be taken along with the anterior spine, through the vertebral bodies and discs, with an electric or handsaw. This will reveal the interior of the spine and exhibit any crushing, haemorrhage, or torn disc spaces: if one of these is found, the cord must always be removed.

EXAMINATION OF ORGANS

Examination of viscera

The thoracic and abdominal viscera are laid on a cutting bench at a convenient height and under good illumination. Ample washing water should be available from a flexible pipe, to flush the tissues as dissection proceeds. Some pathologists maintain that this should not be done, as the water can have an effect on the quality of subsequent histological sections, but this has recently been disproved (Cotton and Stephenson 1988). In any case, the vastly inferior naked-eye examination that results if blood is not removed at frequent intervals greatly outweighs any unsubstantiated objections about the more exquisite details of cell structure, especially as in most forensic autopsies the gross appearances are usually far more important.

The viscera should be laid so that the tongue faces the pathologist, with the aorta upwards. The same sequence of examination should be carried out whatever the nature of the case, so that a fixed routine will ensure that nothing is left undone.



FIGURE 1.16 *The two approaches to the spinal canal for the removal of the spinal cord at autopsy.*

The neck structures

The tongue is examined for disease and injuries, including bites suggesting blows in the jaw or epilepsy. The tongue should be sliced to detect deep haemorrhages sometimes seen in strangulation. Such haemorrhage is seen mostly at the sides and centre of the mid-part of the tongue. Gross congestion, which may be due to either pressure on the neck or to other congestive modes of death, is usually in the posterior part of the tongue. The tonsils and pharyngeal walls are inspected.

The glottis is examined for mechanical or infective obstruction, and the hyoid and thyroid horns palpated for fractures. The oesophagus is opened with large (20 cm) blunt-nosed scissors, which along with a very sharp 10–15 cm bladed knife and a long-bladed 'brain knife', are the most useful tools for performing an autopsy.

The carotid arteries on each side are opened, including the bifurcations and sinuses. If necessary, the upper portions of the carotids are explored in the body itself and followed to the base of the skull. If thrombosis is suspected, the intracranial part should be examined in the cavernous sinus.

Returning to the neck structures, the thyroid should be sliced and inspected, then the oesophagus opened almost to the cardia of the stomach and any suspect material such as capsules, tablets or powder retained for analysis.

The scissors are then passed down the posterior line of the larynx and trachea to the carina. If pressure on the neck of any type, such as strangulation, is suspected, then special examination should be made, as described in Chapter 14.

The trachea and main bronchi should be inspected for disease and obstruction. Gastric contents are often found, but the significance of this is discussed in Chapter 13 – it should not be assumed that ante-mortem aspiration has occurred merely from the presence of gastric contents in the air passages.

The lungs

The lungs are then removed, after careful examination of their external surfaces for patchy collapse, emphysema, petechiae and so on. Almost every autopsy will reveal a few petechiae, especially around the hilum and in the interlobar fissures. Their significance is also discussed in Chapter 13.

The lungs are removed from the thoracic pluck by passing a long-bladed knife (such as a brain knife) under the hilum with the blunt edge upwards. The knife is settled in the correct position before turning the sharp edge upwards to cut through the hilum. Before doing this it may be necessary to remove adhesions over the diaphragm and to cut through the pulmonary ligament, a thin sheet of tissue that ties the inferior medial edge of the lower lobe to the mediastinum.

As the hilum is being cut, the pathologist must notice if any embolism is visible within the pulmonary arteries. It has happened that such an embolism has slid out and been washed unnoticed down the sink. Some pathologists insist on opening the main pulmonary trunk and even right ventricle before removing the lungs, to seek a saddle embolus. This is not necessary, as any large embolus will be readily visible on examining the heart and the lungs in the usual sequence.

Both lungs are taken off and the hilum inspected before being laid aside for cutting. The lung should be weighed before cutting, as appreciable oedema fluid can run away during dissection. Then each is laid with the hilum down on the dissecting board, the opportunity being taken during handling to evaluate weight and oedema, as well as emphysema.

The lung is held on the upper surface by the left hand of the operator (or by an interposed sponge) and the organ cut across in the sagittal plane from apex to base with the large brain knife, held parallel to the board. This produces an anteroposterior slice, the lower medial part carrying the hilum. The cut surfaces can now be opened like a book and the surface examined for oedema, tumour, pneumonias, infarction, trauma and so on. The smaller bronchi must be inspected for such signs as mucosal thickening, infection and blockage. The smaller pulmonary arteries may reveal thrombosis or embolism that was not visible in the larger vessels.

INFLATING THE LUNGS WITH FORMALIN

In some medico-legal autopsies, especially in industrial lung disease such as pneumoconiosis or asbestosis, one or both lungs need to be inflated with formalin for fixation before cutting. This preserves the shape and histology in excellent condition, but delays examination for at least several days. It is carried out by holding or tying a cannula into the bronchus while 10 per cent formol saline is perfused through a tube from a reservoir held about 1 metre above the lung. The lung is then left in a bath of formalin covered with a formalin-soaked cloth to prevent drying.

The heart and great vessels

There are almost as many ways of examining the heart as there are pathologists, and each operator must decide upon the method that appeals most. In this summary there is no space for discussion of post-mortem angiography, which is moving from the field of research and special interest into routine use. A common and practical routine for examining the heart is described here.

First, the organ mass minus the lungs is rotated so that the lower end now faces the pathologist. The scissors are passed into the cut end of a common iliac artery and passed right up to the aortic arch and around to a few centimetres above the aortic valve, staying outside the reflection of the pericardium. The interior of the aorta is studied, especially for the degree of atheroma and for any aneurysms or trauma. The inferior vena cava is opened from its lower end into the liver. The organ pluck is then turned over so that the heart is uppermost. The pericardium is inspected externally for fluid and blood tamponade, then opened widely with scissors. The heart is delivered through the incision and inspected externally for pericarditis, adhesions, discoloration of an underlying infarct and cardiac aneurysms, for example. In a child, the thymus would be inspected and dissected off at this stage.

The heart is then removed by holding it up with the left hand so that its attachment is tensed against the other organs. A long knife, such as a brain knife, is then passed horizontally across at the reflection of the pericardium, cutting through the root of the aorta and other great vessels just above the atria.

The now-detached heart is washed externally and placed in the anatomical position on the dissecting board, with the apex facing the operator and the anterior surface upwards. It should not be weighed until all the contained blood and clot is removed. The general size, shape and ventricular preponderance should be noted. Any dilatation or thickening of the pulmonary conus should be noted as an index of right ventricular hypertrophy, especially if striae of transverse muscle fibres are seen crossing the conus.



FIGURE 1.17 *Incisions for opening the heart at autopsy. (a) The right atrium is slit with an incision (1) to join the vena cava to the appendage; a cut parallel to the interventricular septum is made on the anterior wall of the right ventricle (2) passing up through the pulmonary conus. (b) These cuts are joined through the tricuspid valve (3). (c) The heart is reversed and the left atrium opened by a cut (4) joining pulmonary veins. (d) On the anterior wall a cut (5) is made parallel to the septum through the mitral valve and joined by (6) which passes through the aortic valve.*

The right atrium is then opened by introducing the scissors into the inferior vena cava and cutting across to the atrial appendage. The interior of the atrium is examined and the septum and tricuspid valve inspected.

The interventricular septum is then identified externally by the vessels running down the outside. With a knife a cut is made about 15 mm to the right of and parallel to the septum, over the right ventricle. This should be deep enough to enter the lumen, but not enough to cut the posterior wall. The scissors are now introduced into the cut and run up through the pulmonary conus and into the pulmonary artery until they meet the transected end. They are also extended downwards to the apex of the ventricle. The scissors are now put in midway down this linear cut and passed outwards at right angles, guided by the fingers of the left hand passed into the tricuspid valve from the opened atrium. The whole of the right side of heart is now open and displayed. It should be washed out and the endocardium and valve examined.

A similar routine is now employed on the left side. The scissors are introduced into a pulmonary vein and passed horizontally across to an opposite vein, thus opening the atrium. Fingers are introduced down through the mitral valve to estimate its size and detect any stenosis.

The heart is then restored to the anatomical position and a cut made again parallel to the septum, but on the left side, going deeper as the ventricle is thicker. Guided by the fingers still in the mitral valve, the cut is extended upwards through that valve and out at the top of the atrium.

A finger is now passed up the outflow tract to the aortic valve to estimate its size. Then the scissors are passed up at the side of the mitral valve, and the aortic valve and aortic stump opened. The whole heart is now open and can be washed out and weighed.

Various estimates of the normal heart weight exist and vary considerably (see the Appendix 1). It has been related to gender and body weight, though this is not altogether sound, as a fat person of moderate stature does not have a heart weight comparable with a large muscular person unless there is associated hypertension. This controversial matter cannot be pursued here, but as a rule of thumb the author (BK) accepts up to 380 g as normal in an adult man of average build.

After weighing, the endocardium and valves are examined, then the coronary arteries. Once again, controversy exists about methods of opening the coronary vessels, but the weight of opinion now lies almost universally with those who cut serial interrupted cross-sections with a knife, rather than open them longitudinally with small scissors. The disadvantages of lengthwise opening are that percentage assessment of stenosis or the recognition of total occlusion cannot be made once the vessel is flapped open, as restoring the cut edges can never reproduce the original conditions. In addition, the tip of the scissors may dislodge thrombus or an intimal flap. Cutting across the vessels allows an estimate of the percentage stenosis. It is admitted that this may not be the size of the lumen during life when normal blood pressure is operating, but the same disadvantage applies to longitudinal opening. An estimate of luminal size is relatively constant, however, in that the collapsed abnormal can still be compared with the collapsed normal.

The coronaries are therefore cut across at frequent intervals. Before the first cut, the ostia are examined for congenital variations (which are frequent) and for obstruction. The left coronary artery is then cut across from the epicardial surface, starting as close to the ostium as possible, as occlusion and severe stenosis can occur very near the origin. Serial cuts are then made at intervals of not more than 3 mm, first into the common trunk, then following the left circumflex laterally until the vessel becomes too small, usually when it dips down from the epicardium to become intramuscular. The anterior descending branch is then followed down the front of the septum almost to the apex.

Turning to the right coronary artery, the proximal segment is cut back from the point where the right ventricle was opened, transecting the artery in its mid-part. The cuts are made back to the aorta, then the distal segment is followed laterally until it becomes the posterior descending branch. During this process, the dominance of right versus left vessels is noted.

Difficulty arises where severe calcification exists, as the knife either fails to cut through the artery or shatters it because of the excessive force required. The lumen is crushed and the percentage stenosis is difficult or impossible to assess. Scissors may be used to exert more force than a knife, but the only real solution is to decalcify the vessels. Except for research purposes, it must be admitted that the days or even weeks of delay occasioned by decalcification provide a formidable deterrent for the busy coroner's pathologist unless the issues involved are important. Post-mortem angiography is the other alternative, though where autopsy caseloads are high, this can be difficult to arrange.

Once the coronary arteries have been examined, the myocardium can be studied more closely. One useful technique is the intramural or 'sandwich' cut through the thickness of the left ventricle. This is easier when there is some ventricular hypertrophy, but can be carried out in any heart. The heart is placed open on the cutting board, with the endocardium downwards. A long knife such as a brain knife is passed carefully into the cut edge of the left ventricle and sliced right through the muscle, keeping equidistant between endocardium and epicardium. The myocardium can then be opened out like a book, showing the interior with any infarcts or fibrotic plaques. If histological blocks through the entire wall are needed it is best to take these before slicing the heart as described, otherwise a full-thickness block will be hard to obtain. Some pathologists make a series of transverse heart slices about 8–10 mm thick, starting at the apex, before opening the heart. This displays the distal myocardium wall, but cannot expose the proximal part, as examination of the coronary arteries would then be compromised.

Examining the abdominal organs

The remaining organs are laid on the dissecting surface in the anatomical position, with the liver and stomach away from the pathologist, and the anterior surface upwards.

The stomach is opened and, if there is any question of requiring the contents for analysis, a suitable container should be ready. The stomach is washed externally with a stream of water and a small cut made in the greater curvature. If the contents are to be saved, this can best be done with the edge of the stomach projecting over the raised cutting board or over the edge of the sink, so that the container can be held underneath. The contents are allowed to run into the container, then the greater curvature is opened widely with scissors, and any remaining contents drained or scraped out. If powder or other substance is adherent to the mucosa, this can be scraped off and added to the container, or kept in a separate tube for analysis.

Some laboratories require the stomach wall to be retained for analysis as well as the contents. This can be done after the organ has been fully opened and the lining examined. If the contents are not required – or when they have been collected – the organ is opened up from cardia to pylorus along the greater curvature. The lining is washed and inspected. The scissors are now passed through the pylorus around the duodenum until they meet the point where the gut was detached earlier. The gall bladder may be squeezed to demonstrate the patency of the bile ducts. In some few cases, bile may be required for analysis, as in morphine or chlorpromazine overdose.

The adrenals are examined next, the right one being on top of its kidney, the left being on the medial side. If the right kidney is taken in the left hand and lifted against the weight of the liver, a single cut into the stretched tissues between liver and kidney will transect the adrenal. The left is buried in the tissue between pancreas, spleen and kidney. The amount of cortical lipoid and the absence of bleeding or other abnormality is noted in each gland.

The spleen is removed by cutting through its pedicle and is sliced after weighing. The pancreas lies under the stomach and should be cut lengthwise from the curve of the duodenum to its tail lying against the splenic hilum.

The kidneys are exposed by incising their capsules, often after a thick layer of perirenal fat is traversed. The kidneys can usually be peeled out of their capsules unless these are adherent.

The renal vessels were examined when the aorta was opened, but can be re-examined at this stage and the ureters inspected. The organs can be detached at their hilum and weighed, then cut lengthwise to inspect the interior. The width of the cortex is important, being about 1 cm in a



FIGURE 1.18 *Collecting stomach contents at autopsy. The exterior of the stomach is washed free from blood and the viscera moved to overhang the dissecting board. A chemically clean receptacle is held beneath the greater curvature while the latter is opened with scissors and the contents allowed to drain out. The stomach is then opened, the mucosa inspected and any adherent material scraped into the container. The stomach wall should then be dissected off and added to the contents if the laboratory is able to deal with tissue analysis.*

healthy subject. The granularity of the surface and the clarity of the corticomedullary junctions is assessed, as well as the size of the renal pelvis.

The small intestine may have been examined at the earlier stage of removal, but can be inspected now. It is not usual to open the whole length of the gut in a forensic autopsy unless there is any particular indication to do so, though ideally this should always be carried out.

EXAMINATION OF THE BRAIN

After weighing, a decision has to be made whether to examine the brain immediately – the so-called 'wet-cutting' – or to suspend it in formalin until fixed, a process which takes at least several weeks. The advantage of fixation is, of course, that the firmness of the tissue allows thinner and more accurate knife-cut sections to be taken, as well as better histological preservation. Where neurological issues are involved, either traumatic or from natural disease, it is almost mandatory for the brain to be fixed before cutting. Even the impatience of the investigative authorities can usually be overcome if the advantages of a higher standard of opinion are explained.

The technique of brain fixation is well known, but to summarize briefly, the brain is suspended in a container of 10 per cent buffered formalin, the volume being at least 5 litres and preferably 8. The brain is removed with the dura leaving the parasagittal bridging veins and falx intact and suspending the brain in an upright position by the falx. An alternative method is to pass a thread or metal paperclip under the basilar artery and tie it to a support across the mouth of the container, so that the vertex is clear of the bottom.

In the majority of autopsies there is no real need for fixation if no cerebral lesions are either expected or apparent on external examination of the brain. Here, 'wet-cutting' is sufficient, though if any unexpected lesions are found, the process can be stopped and the slices of brain fixed by placing them in a large volume of formalin, on cotton wool pads, to prevent distortion.

One lesion is better examined in the unfixed state, though the brain may be suspended later; this is subarachnoid haemorrhage. It is easier to wash away fresh, unfixed blood with a stream of water and blunt dissection than the hardened blood that develops during formalin fixation. Further details are given in Chapters 5 and 25.

Whether the brain is examined 'wet' or fixed, the sequence is the same. The weight is first considered, the normal for a young male adult being between about 1300 and 1450 g, the female equivalent being around 100 g less. More details are given in Appendix 1. It should be noted that formalin fixation adds about 8 per cent to the original weight.



FIGURE 1.19 *A brain suspended in formalin for fixation before cutting. The tank is specially made of fibreglass, being cubical for stacking with a lid (not shown). There are lugs moulded into the sides to hold the suspensory strings, which support the brain by means of a paperclip hooked under the basilar artery. There should be sufficient fluid to allow the brain to float clear of the bottom of the receptacle.*

The brain is first examined for surface abnormalities, which in forensic practice usually means haemorrhage. This is dealt with in Chapter 5, but suffice to say here that meningeal bleeding is one of the most important lesions in forensic pathology, be it extradural, subdural or subarachnoid. This means that examination of the cerebral vessels, especially the arteries of the circle of Willis and the vertebral vessels, is vital – especially in the search for berry aneurysms. The general symmetry of the brain is then noted as well as any depression of the cortex from skull or meningeal masses. An estimate of cerebral oedema is made, partly from the weight, but mainly from flattening of the gyri, filling of the sulci and evidence of hippocampal herniation through the tentorial aperture. In lesser degree this may be seen as grooving of one or both unci, though a normal slight anatomical groove is often present. True uncal herniation is marked and often discoloured as a result of incipient infarction. Similarly, herniation or coning of the cerebellar tonsils through the foramen magnum must be distinguished from the common anatomical pouting of many tonsils: true pressure coning is often discoloured by local infarction. After careful inspection of the basal vessels and the exterior of the brain, and palpation for any fluctuant masses under the cortex such as internal haemorrhage, abscesses or cystic tumours, the organ is cut.

The first cut should be made through the cerebral peduncles using a long, broad-bladed knife to separate the cerebrum from the brainstem and cerebellum. The cerebellum is then held in one hand with the cut stem upwards.



FIGURE 1.20 *An alternative method of suspension is to leave the falx intact and use it to suspend the brain base down in formalin.*

This is examined to assess the substantia nigra and aqueduct, as well as to note any primary or secondary haemorrhage, the latter often being due to raised intracranial pressure. The cerebellum and pons are then cut down vertically and opened like a book to display the fourth ventricle, dentate nuclei and the interior of the cerebellum. The lower pons and medulla can be further sectioned transversely or longitudinally.

The cerebral hemispheres are then placed base down on the cutting block and serial sections made in the coronal plane from the frontal lobes back to the occiput. The sections should be about 1 cm thick and each should be slid into a sequential place in rows along the cutting board so that orientation is preserved. Cuts should be made with careful but bold sweeps of the knife as erratic sawing motions will leave an irregular surface on each section, which obscures a good view. Cutting a fresh brain is less satisfactory than cutting a firmer fixed brain, especially if there is any post-mortem autolysis or softening as in a dead ischaemic brain after mechanical ventilation.

ANCILLARY INVESTIGATIONS

A wide range of samples may need to be taken either before, during or after the gross examination is completed. The nature of such ancillary investigations naturally depends upon the nature of the death, the history and the interests of the pathologist.

Microbiology

Though more common in clinical autopsies than forensic work, culture samples for ‘bacteriology’, virology and (rarely) fungi may be needed. Either plain swabs or swabs immersed in a transport medium can be employed for sampling a wide variety of sites at autopsy. Alternatively, tissue samples may be collected in sterile containers and this is the usual method for virological culture of lung and brain, for example. Blood cultures may be desired, and it is best to take blood with a sterile needle and syringe from a large vessel, such as the femoral vein, before starting the autopsy with its attendant inevitably widespread contamination with putrefactive organisms. Alternatively, blood can be taken from a freshly opened heart chamber using sterile instruments.

In all autopsy investigations, unless cultures are performed soon after death, there is often widespread contamination by organisms that travel rapidly through the dead tissues, especially from the gastrointestinal tract. It requires the expertise of an experienced microbiologist to advise on what is significant in the subsequent growth in the laboratory.

Toxicology

This has already been mentioned and is further discussed in the later chapters of this book but, as far as the collection of specimens is concerned, it may be repeated here that sampling is extremely important if reliable analytical results are expected. Blood, urine, stomach contents, organs (especially liver), intestinal contents, cerebrospinal fluid, bile and ocular fluid may be required.

The containers in which specimens are collected must be chemically clean to a very high standard. They are often supplied by the laboratory that will carry out the analyses. For example, the Home Office Forensic Science Service in Britain supply a kit containing two large plastic tubs with lids, several universal containers, fluoride tube, syringes and needles, together with instructions as to type and quantity of sample needed for various tests.

The pathologist should submit a form with the samples indicating the analyses required, the personal details of the deceased person, a brief history with details of suspected toxic substances, and a statement as to whether the subject was known to suffer from any infective condition, including hepatitis or HIV infection.

Histology

In most autopsies and inevitably in all criminal or litigious cases, the pathologist will need to carry out a histological examination on a range of tissues, even if only to exclude the possibility of some occult natural disease. The Royal College of Pathologists as well as the 1999 Council of Europe recommendation on the harmonization of medico-legal autopsy recommend that histology be taken from every autopsy. This advice should be followed wherever possible, even though in some medico-legal autopsies, the cost of such techniques may provide difficulty if the coroner or other commissioning authority declines to fund the procedure. It is customary to retain samples of liver, spleen, kidney, heart, lung, thyroid, adrenal, pancreas, muscle and brain as a minimum. Where there are indications to examine other parts of the body, these are retained in addition to the routine tissues. The tissues are either sampled by taking relatively large pieces at autopsy (which are later trimmed down to size) or by cutting blocks of a standard size (such as 20 × 12 × 5 mm) at the time of autopsy.

The tissue is placed in a large volume of buffered formol–saline and allowed to fix for at least several days before processing. The volume of fixative should be six times the total volume of tissue: it is all too common to see a mass of tissue squeezed into a small container, barely covered with formalin, half-fixed and even semi-dried. There are many specialized procedures also in use at present, such as histochemistry, fluorescent microscopy and immunohistochemical examination; these are used especially in the pathology of sudden death where evidence of early myocardial infarction is sought. This is discussed in the chapter on sudden natural death (Chapter 25).



REQUEST FOR TOXICOLOGICAL ANALYSIS

Name Age

Post Mortem No Date of P.M.

Date of Death Pathologist

SPECIMENS SUBMITTED: Blood Urine Liver

Stomach contents Kidney

Intestines Brain

OTHER SPECIMENS

Any infective conditions suspected

ANALYSIS REQUIRED

BACKGROUND INFORMATION:

FIGURE 1.21 *Sample request form for toxicological analysis.*

AUTOPSY RADIOLOGY

The details of radiological findings are discussed in each appropriate chapter, particularly in relation to child abuse, gunshot wounds, identification and dentistry. In general, radiology is similar to photography in the autopsy room, though it requires more bulky apparatus, and someone to operate the equipment and process the films.

The quality of radiographic assistance available will vary widely from none to the most sophisticated techniques, even including computed tomography and even, in very few centres, magnetic resonance imaging (MRI).

The main difference is usually whether the autopsy is carried out in the mortuary of a well-equipped hospital where there is radiographic apparatus, radiographers to use it and radiologists to read the films – or whether the autopsy is performed in some remote public mortuary or in makeshift premises far from clinical facilities.

In many developing countries, radiography may be scarce for living patients let alone corpses, and the same standard of assistance for the pathologist cannot be expected. In larger, more affluent countries, remoteness may be the problem; here mobile equipment is available and sometimes used by forensic pathologists. There are small, portable X-ray kits that can be carried in two suitcases, and can function from an ordinary domestic power supply or from a portable petrol generator. In many instances a mortuary will have a small portable machine, sometimes one discarded from clinical use. This can be wheeled into position when needed, and films and technical assistance obtained from the nearest hospital, which is often adjacent.

For isolated organs and tissues, cabinet-type radiographic equipment is available, which can be used without the assistance of trained radiographers.

Where there is a large forensic institute, then full radiological facilities with the staff and equipment to operate and process plates will be available at all times. Where research projects involving radiology, such as post-mortem coronary angiography, are being carried out, there will usually also be ample facilities for routine use.

The stage at which radiology is employed in an autopsy will vary according to the individual circumstances, but is likely to be after the external examination is complete, but before dissection begins. Straight radiographs for bony injury are not often required, as the skeleton can be inspected directly by dissection in major trauma. The exception is child abuse, where, as fully described in Chapter 22, a full skeletal survey is needed before autopsy. Indeed, many forensic and paediatric pathologists would consider radiology essential in all infants who did not die of some obvious disease.

Suspected air embolism, pneumothorax, barotrauma, gunshot and explosive deaths should have radiological examination before the autopsy, and when a traumatic subarachnoid haemorrhage is suspected, vertebral artery angiography might be necessary, as described in Chapter 5.

Mutilated remains, especially those from mass disasters, may need to be X-rayed, as may victims from fires where the external damage makes dissection difficult. Where bombs or explosive devices are involved, it is essential to have radiographs to detect any parts of the mechanism that are embedded in the tissues.

Though the films are usually taken before the autopsy begins, some lesions may be better demonstrated on isolated



FIGURE 1.22 *Radiography is essential before some autopsies. Here it is being used to X-ray a gunshot wound of the chest.*

organs or structures. In child abuse, the callus of old fractures of posterior ribs may be better visualized on X-ray if the chest cage is dissected out, and radiographs taken without the soft tissues and the obscuring structures of sternum and anterior ribs. Similarly, a block of upper cervical spine may better reveal fractures of transverse processes carrying the vertebral artery, or a larynx may show fractures of the hyoid or thyroid cornuae more clearly when they are X-rayed outside the body.

FORENSIC PHOTOGRAPHY

Many forensic pathologists take their own photographs of both scenes of death and of autopsy appearances. Others rely on professional photographers such as the police and hospital medical photographers.

The standard of expertise amongst some doctor photographers is excellent, and their pictures grace many lectures and textbooks. It is to the more inexpert camera operators that these few general tips are offered.

The type of camera most favoured is the 35 mm single-lens reflex, of which there is now a vast range available, in all grades of sophistication and price. Some means of exact focusing is essential (either automatic or split-screen, for example) as picture sharpness is of prime importance.

The type of lens is a matter of personal choice, as some will prefer interchangeable lenses of various focal lengths. The standard 50 mm is most useful, but for scenes of crime or taking a full-length shot of a body in cramped conditions, a wide-angle lens of 28 or 30 mm is needed. A longer focal length of up to about 80 mm can be useful for close-up pictures of small lesions, but telephoto lenses of 100–200 mm are not required, though extension tubes, some with lenses, can be obtained for macrophotography.

Many pathologists, including the authors, prefer to combine lenses into a single variable-focus ‘zoom’ lens of 28–80 mm range. This saves time spent in changing lenses, and the image resolution of good-quality equipment is virtually indistinguishable from fixed focal length lenses.

Illumination is usually by electronic flash now often an integral part of the camera body, and the use of automatic thyristor control means that no complicated calculations about range are needed. For very close-range work, a flash attached to the camera may be unsatisfactory, so an extension cable is a useful and cheap accessory to keep the flashgun at a distance. Alternatively, the flash can be ‘bounced’ off the ceiling in the autopsy room or a ‘ring-flash’ around the lens used to avoid camera shadow.

Some will prefer tungsten light rather than flash, though this is more cumbersome unless a fixed station is installed in the autopsy room for taking photographs of organs. It is impracticable to use floodlights at the autopsy table or at a scene.

The type of film depends on the nature of the illumination. Speeds of 100 or 200 ASA are more than adequate for most flash work, though 400 ASA is now frequently used. Some keen medical photographers carry a separate camera body loaded with high-speed 1000 ASA film for special circumstances.

Ultraviolet (UV) and infrared sensitive film has been used to demonstrate surface lesions that are not visible to the human eye. It has been claimed that occult bruising can be revealed by UV photography, such as in child abuse, but care must be taken and experience gained to eliminate artefactual false positives.

Most doctors will want transparencies for projection at lectures, which can be made into prints, either colour or monochrome. If prints are specifically wanted for black and white publication in books or journals, it is better to take them originally on monochrome film, as colour negatives do not provide quite the same quality reproduction in black and white.

Some pathologists use Polaroid cameras either alone or together with conventional film. The advantage of instant prints is that a record of the scene of death can be obtained before the autopsy is carried out, and any findings checked back against the original surroundings. For example, if some linear mark is seen on the leg at autopsy, the pathologist can immediately refer to his Polaroid prints to check whether that leg had been resting on some object. Again, where multiple injuries exist, their number, position and size can be checked when writing the autopsy report, without waiting days or even longer for the police album to arrive. Correlation of wounds with blood splashes may also be useful. Such Polaroid pictures can be duplicated and even turned into transparencies, but it is preferable to have a conventional camera for these purposes.

Recent advances in electronics are revolutionizing photography, and have wide application and potential for forensic and autopsy work. Electronic cameras of varying grades of sophistication, resolution and cost, can now instantly store images on a small internal ‘memory stick’ or CD-ROM, which can then be viewed immediately on a computer VDU or printed on a colour laser printer. These images can be manipulated in many ways to enlarge sections or correct colour balance, sent via modems to distant locations, or incorporated within textual material and reports. At present, good resolution can still be obtained more cheaply with silver-based film stock but this situation is changing in favour of the digital photography. Alternatively, photographs and slides can be electronically scanned within minutes, the optical image being digitized into electronic storage for similar manipulation.

All electronic images can also be stored on CD-ROM or DVD equipment, which offers huge storage and retrieval capacities for record-keeping and educational display purposes. In addition, single frames from video camera recordings can be captured as still pictures and electronically stored.

In relation to the actual photography, a marked improvement in the pictorial quality can be achieved with a little care in composition. At scenes of death the viewpoint is often limited and the surroundings have to be photographed as they exist, without modification. The camera position can, however, usually be chosen to cut out as much extraneous background as possible. In the autopsy room, considerable improvement can be made by using the optimum viewpoint and by modifying the background. Many photographs are spoiled by having irrelevant and distracting objects in the background such as observers, buckets, boots and the other extraneous paraphernalia of the autopsy room. The picture frame should be filled as completely as possible with the object under display. A close shot should be taken to limit the irrelevant margins though, where necessary, anatomical landmarks should be included to orientate the viewer. The camera should be at right angles to the lesion being photographed, whenever possible. Tangential shots may foreshorten the required feature and, where size needs to be displayed, may distort both shape and length because of the foreshortening. A ruler or special white adhesive tape with centimetre markings should be placed very near the lesion or wound to provide a size reference.

Where a feature is obscured or insignificant, it may be pointed out by a probe or finger held in the appropriate position. Where part of the picture area consists of the metal or porcelain autopsy table or dissection bench, allowance should be made in exposure, as these very reflective areas may give a false reading in the light meter of the camera and thyristor of the flashgun.

If a full length or half shot of a body is required, an untidy background may be avoided by turning a mobile or rotatable table so that a blank wall forms the backdrop. If this is not possible, assistants can hold up a sheet behind the table to screen the distant confusion.

When photographing viscera, the camera should be near enough for the frame to be almost completely filled by the required object. The shot should be vertical to the lesion and it is often necessary either to place the dissecting board on the floor, or for the photographer to stand on a stool or some elevation to gain the required height.

Where isolated organs are being photographed, they should be placed on a green or blue cloth, such as a discarded operating gown. White can be used, though it may affect the exposure meter if much is visible around the periphery. The organ should be placed on the cloth in one movement and not moved thereafter, otherwise a wet dark stain will obtrude on the green or blue background. The organ should not be oozing blood onto its surface or onto the background. It should be dabbed with a dry cloth or sponge just before the photograph is taken to remove shiny wet highlights.

Ideally a special stage for organs should be used, such as a glass-topped table with a coloured (usually green) background set sufficiently far below the glass to be out of focus. Tungsten lights can be used to advantage on such a fixed stage.

THE AUTOPSY REPORT

Equally important as the autopsy itself is the report that the pathologist provides for whoever commissioned the examination. An autopsy is of little value if the findings and opinion of the forensic pathologist are not communicated in the most lucid and helpful way. The report is an integral part of the procedure and should receive as much attention as any physical procedure in the autopsy room. Unfortunately, some pathologists treat the process of making a report in a somewhat cavalier manner, which diminishes the expertise that they may otherwise possess.

The autopsy report is a permanent record of the findings and is especially vital for medico-legal purposes, when every word may be dissected in a court of law months or even years afterwards, and when all recollection of the examination has been driven from the mind of the pathologist by hundreds of subsequent autopsies. In a clinical autopsy in a hospital, the dissection may be demonstrated and discussed at the time with the interested physician. However, the report of a forensic autopsy becomes a legal document of possibly vital significance, and every effort must be made at the time to make it as comprehensive and useful as possible.

The form of the autopsy report

Reports fall into two main types described below, and local practice and indeed legislation may determine which is used, irrespective of the wishes of the pathologist. The choice is, however, often dictated by the nature of the case.

- A free-style ‘essay’, which usually adheres to a conventional sequence, but leaves the pathologist free to expand on various aspects according to his estimate of their importance. This type is usually used in criminal deaths and cases in which litigation is likely. It has the advantage that any part of the autopsy can be expanded without constraint; also the form of the report can be turned into a legal statement or a deposition for the court with little alteration.

- A printed proforma, in which the various sections of the examination and organ systems are already set out by title, leaving blank spaces for the insertion of the findings. The advantage includes the fact that this 'shopping list' acts as an *aide-mémoire* to those pathologists who do not conduct large numbers of autopsies – and also the non-medical recipient is more able to follow the set pattern of the report. One disadvantage is that the spacing prevents flexibility of description unless the proforma is large, when much of the space may be left blank. Also there is rarely enough space at the end of the form for an expansive discussion and opinion about the preceding factual findings. This type of form is commonly used for non-litigious autopsies – for example, the usual coroner's cases of sudden death and suicide.

Concentrating upon the more serious cases, the report, whatever the format, must contain certain information in some logical order. Consecutive numeration, computer codings and other administrative aspects are naturally conditioned by local practice, but the following matters must be catered for in all autopsy reports, though not necessarily in this sequence:

- Full personal details of the deceased subject, unless unidentified. This includes the name, gender, age, occupation and address.
- The place, date and time of the autopsy.
- The name, qualifications and status of the pathologist.
- Persons present at the examination.
- Usually, the authority commissioning the autopsy.
- A record of who identified the body.
- The name and address of the deceased subject's regular (or last) medical attendant.
- The date and time of death, where known.
- The history and circumstances of the death. The inclusion of this on the actual autopsy protocol may not be permitted in some jurisdictions as it is hearsay evidence, but unless expressly forbidden it should be included, as it remains a record for the pathologist's own files. It also justifies his eventual cause of death in those cases where the morphological findings are scanty or even absent, as his conclusions will be strongly influenced by his pre-knowledge of the mode of death. When the autopsy report is converted to a statement or deposition for legal use, this history may be omitted by those legal authorities responsible for transcribing the document.
- External examination.
- Internal examination.
- A list of specimens and samples retained for further examination. Those handed to other agencies, such as the forensic science laboratory, should be formally identified by means of serial numbers and the name of the person to whom they were handed.
- The results of further examinations such as histology, microbiology, toxicology and serology. When the main report is issued soon after the autopsy, these will not yet be available and a supplementary report will be necessary.
- A summary of the lesions displayed by the autopsy (often coded for departmental computer retrieval).
- Discussion of the findings, if necessary in the light of the known history.
- An opinion as to the definite or most likely sequence of events leading to the death.
- A formal cause of death, in the format recommended by the World Health Organization, suitable for the completion of a death certificate.
- The signature of the pathologist.

The 'external examination' should record those details described earlier in the chapter, the major items being:

- The height, weight and apparent state of nutrition.
- The presence of natural disease such as oedema, abdominal swelling, cutaneous disease, senile changes, etc.
- Identifying features such as skin colour, tattoos, scars, congenital or acquired deformities, dentures, eye colour and hair colour. When identity is an issue, naturally this section will be greatly expanded.
- The presence of rigor, hypostasis, decomposition and abnormal skin coloration. Body and ambient temperature should be recorded where appropriate, with calculations concerning the estimated range of times since death, though this aspect may well be deferred until the final 'Summary and Conclusions'.
- The condition of the eyes, including petechiae, arcus senilis, pupil size, and the condition of iris and lens.
- Condition of mouth and lips, including injuries, teeth and presence of foreign material.
- Condition of external genitals and anus.
- Listing and description of all external injuries, recent and old.

The internal examination records all abnormalities, usually in a conventional sequence such as:

- Cardiovascular system: heart weight, any dilatation, ventricular preponderance, congenital defects, the pericardium, epicardium, endocardium, valves, coronary arteries, myocardium, aorta, other great vessels and peripheral vessels.

- Respiratory system: external nares, glottis, larynx, trachea, bronchi, pleural cavities, pleura, lungs (including weight) and pulmonary arteries.
- Gastrointestinal system: mouth, pharynx, oesophagus, peritoneal cavity, omentum, stomach, duodenum, small and large intestine, liver (weight), pancreas, gall bladder and rectum.
- Endocrine system: pituitary, thyroid, thymus and adrenals.
- Reticuloendothelial system: spleen (weight) and lymph nodes.
- Genitourinary system: kidneys (weight), ureters, bladder, prostate, uterus, ovaries and testes.
- Musculoskeletal system: skull, spine, remaining skeleton and musculature where necessary.
- Central nervous system: scalp, skull, meninges, cerebral vessels, brain (weight), middle ears, venous sinuses and spinal cord (when examined).

The timing of the report

As with the format, there are two schools of practice in this respect. One advocates the issue of as full a report as possible on the gross findings as soon as the autopsy is completed, usually within a day or two. Obviously this can only be a preliminary, provisional report, as it may have to be modified (sometimes radically) by the results of ancillary investigations that may take days or weeks to return. Virological cultures, for instance, may take up to 6 weeks before a growth can be reported.

In a large proportion of forensic cases, however, especially those due to violence, the gross findings are unlikely to be substantially amended by ancillary investigations, though the possibility must always be left open until data have been gathered in.

The other philosophy will delay any report (except perhaps a provisional oral opinion) until everything is to hand, when a single final document is provided.

Whichever course is adopted, one aspect is vital to both. The descriptive facts must be recorded at or immediately after the completion of the autopsy. It is vital that no significant interval – certainly no more than few hours – be allowed between the physical performance of the examination and the setting down of the objective findings. The words ‘setting down’ are chosen carefully as the report may be handwritten or typed, or may be dictated to a secretary or into a tape recorder or other audio system. What is vital is that it is not consigned to the pathologists’ memory for a few days, even reinforced by notes written on scraps of paper.

In Britain and many other jurisdictions, the court may demand to see any contemporaneous notes and even tapes from a tape recorder. Any diagrams, notes or rough drafts must be preserved for production on demand of the judge, coroner or advocates in court. Where the report is dictated (either to a secretary or into a tape recorder), then the first typed (or word-processed) draft constitutes the ‘original report’, along with any contemporaneous notes including body sketches.

The use of printed body sketches can be a very useful aid in the autopsy room. Many versions exist from the simple front and back views of the whole body used in clinical neurology to multiple sketches portraying every possible view of the body surface. Separate diagrams are available for the male and female perineum, and for the different body proportions of infants. Used on a clipboard these diagrams can be most useful, especially where there are multiple injuries, or large areas of burns or abrasions. Each lesion can be drawn in, with a measurement noted alongside each and distances from anatomical landmarks recorded. The data from the sketches can be transposed to written form at the end of the examination.

Discussion and conclusions in an autopsy report

Some pathologists, usually those not normally concerned with criminal and litigious cases, claim that an autopsy report should be a bare recitation of the physical findings, with no discussion or interpretation of the significance of those findings. In the authors’ opinion, this is an abdication of the pathologist’s responsibility because, especially in criminal deaths, it is these conclusions that are of most interest and use to the investigating officers, lawyers and courts.

After the detailed description of the external and internal appearances, a short resumé should be offered of the major positive findings and their relationship to the cause of death. In many cases this will be obvious, as in a gunshot wound of the head. Matters such as the probable type of weapon, the range, the direction and the likely rapidity of death, however, should also be discussed.

When the findings are less clear cut, or are multiple, then the alternatives should be discussed, giving a differential diagnosis of the cause of death and detailing the possible sequence of events. If it is possible, a ranking order of probability of the various alternatives can be offered. Time of death and the limitations of accuracy in this particular case should be set out when the issue is relevant to the investigation. What is really required is as full an interpretation as possible, without venturing into the undesirable fields of unwarranted speculation or Sherlock Holmes style of over-interpretation, which was the bane of forensic pathology in former years and is still practised too much even today, to the detriment of the good reputation of the speciality.

POST-MORTEM ARTEFACTS

Forensic pathology can only be learned by experience but no account would be complete without drawing attention to common artefacts found at autopsy, which can mislead the pathologist with insufficient forensic experience and even lead to a miscarriage of justice.

Some of the 'classic' mistakes were described many years ago by Shapiro (1954) and Moritz (1942), but each generation of pathologists discovers them a new – or what is worse, fails to discover them. Most artefacts are described in the various chapters dealing with specific lesions, but a reminder of some of the most important is given here:

- The pancreas is one of the first organs to undergo autolysis, because of the proteolytic enzymes within it. The autolysed tissue is often haemorrhagic and can easily be mistaken for acute pancreatitis, though histology will rapidly resolve the problem.
- Patches of haemorrhage, sometimes quite large and confluent, can occur in the tissues behind the oesophagus in the neck. These lie on the anterior surface of the cervical vertebrae and are caused by distension and leakage from the venous plexuses that lie in this area. They were described well by Prinsloo and Gordon (1951) and are sometimes known by this name. Their importance lies in confusion with deep neck bleeding in strangulation (and sometimes with spurious neck fractures), which is why the skull should be opened before the neck in any suspected strangulation or hanging, to release the pressure in the neck veins before handling the tissues.
- Autolytic rupture of the stomach can occur post-mortem in both child and adult, described by John Hunter in the eighteenth century. This so-called 'gastromalacia' appears as a slimy brownish black disintegration of the fundus with release of the stomach contents into the peritoneal cavity. Sometimes, the left leaf of the diaphragm is also perforated through a ragged fenestration, with escape of gastric contents into the chest.
- Heat fractures of the bones, either skull plates or long bones, may be seen in victims of severe fires, but are not evidence of ante-mortem violence. Also in conflagrations, the 'heat haematoma' within the burned skull can resemble an extradural haemorrhage of ante-mortem origin. The site is often at the vertex or occiput; however, unlike the usual parietal haemorrhage, there is no fracture line crossing the middle meningeal artery, the usual cause of a true extradural bleed. The frothy brown appearance of the false clot, together with heating effects in the adjacent brain, should indicate the true diagnosis. Shrinkage of the dura due to heat may cause it to split, with herniation of the brain tissue into the extradural space. Severe burns of the body surface may lead to heat contractures of the limbs with tears over joints such as the elbow. These must not be confused with ante-mortem lacerations or incised wounds.
- The bloating, discoloration and blistering of a putrefying body must not be misinterpreted as disease on injury. Blisters are quite unlike those of burns and dark blackish areas of discoloration must be distinguished from bruising. The latter can be difficult and incision into the tissues to seek blood in the dermis is advised. Histological sections may help but, where a body is badly decomposed, special stains for blood traces in the histological sections may assist, such as alpha-glycophorin to detect red cell envelopes. However, often it is quite impossible to differentiate the discoloration of decomposition from true bruising.
- Blood or bloody fluid issuing from the mouth may be due to putrefaction, even if the body surface is not overtly decomposed. If the lungs and air passages are discoloured and filled with sanguineous liquid, then this must be taken to be cause of the purging from the mouth and nostrils.
- Dark red discoloration of the posterior part of the myocardium is usually due to post-mortem gravitational hypostasis, not early infarction. Similarly, segmental patches of dark red or purple discoloration of the intestine is hypostasis, not infarction. The latter tends to be a single continuous length, the serosa being dull and the gut wall friable.
- Large petechiae or ecchymoses, sometimes with raised blood blisters, are often seen in the dependent skin of persons who have died a congestive death or where the upper part of the body has been hanging down after death. The usual place where these are seen is over the front of the upper chest and across the back of the shoulders, though in dependent heads the face may be shot with haemorrhages.
- Resuscitation artefacts are of increasing importance to the forensic pathologist and are discussed later.

EXHUMATION

Exhumation is the retrieval of a previously buried body for post-mortem examination. This is usually followed by a first autopsy or a re-autopsy following new information. The term 'exhumation' is usually applied to the removal of a body buried in a legitimate fashion in a cemetery or graveyard ('inhumation'), rather than the recovery of an uncoffined, clandestinely buried victim of a suspicious death. The latter is really a true 'scene of crime' and the pathologist should treat it as such.

Exhumations are required for one of the following reasons:

- Where all or part of a graveyard has to be moved for some development of the ground. Often no special examination of each body is made unless there is some historical or anthropological interest.
- Where some civil legal matter needs to be investigated, such as personal injuries for insurance or civil litigation for negligence – usually after a road, industrial or other accident.
- Where new information or substantiated allegations arise to suggest that a death was due to criminal action, either from injury or poison.
- In ancient or historical circumstances to investigate either the individual or a series of individuals for academic interest. A number of such investigations have been carried out on medieval and later inhumations in England, to study disease patterns and nutritional states in old populations – though many of these have been from dry vaults, rather than earth burials.

The legal procedures authorizing an exhumation do not concern us here, as they vary greatly from country to country. In all jurisdictions, however, there must be strict safeguards to identify the grave and the coffin, so that no mistake can be made. The grave must be positively identified by the cemetery authorities by reference to plans and records: an official must personally point out the grave to be opened.

Traditionally, exhumations are carried out at dawn but, except to avoid spectators and publicity, there is no real need to stumble about in a dark cemetery before first light. A better plan is for the grave to be dug down to just above coffin level by a mechanical digger or workmen on the previous day so that, the following morning, the police, coroner, pathologist and others can arrive in time to see the final exposure of the coffin. The coffin nameplate must be cleaned and read to confirm the identity, and, if possible, the funeral director who carried out the original burial should be present to identify the coffin and the plate.

If there is a suspicion of poisoning, samples of earth should have been taken from the surface of the grave, from other parts of the cemetery and from immediately above the coffin. When the coffin has been removed, further samples should be obtained from the sides and beneath the coffin, but these matters will usually be attended to by forensic scientists.

When the coffin is lifted to the graveside it is as well for the lid to be loosened a little by slackening the holding screws or prising the lid loose. This allows foul gases to escape into the open air, rather than in the mortuary. The coffin is then transported to the mortuary; if it is in a bad state of decay, it may have to be supported on a rigid base such as a trestle, or placed inside an extra large coffin or fibreglass shell. Excess earth and mud should be removed before transportation to avoid excessive fouling of the autopsy room. Where criminal action is suspected or has been alleged, a full photographic record must be kept (usually by the police) of every stage from identification of the grave to the findings during the autopsy.

At the mortuary, the coffin lid should be completely removed and the contents again identified, if possible by the funeral director who originally buried the body. He can again confirm the coffin plate, but also identify the internal coffin fittings, such as fabrics and shroud. When the body has not been buried for too long, he may be able to identify the features of the corpse from personal knowledge.



FIGURE 1.23 *Exhumation: a police officer making the final approach to the coffin. A metal cassion is lowered to protect the gravesides. The grave must be identified by the cemetery superintendent.*



FIGURE 1.24 *Exhumation: when the coffin is exposed it must be identified by the funeral director and the coffin plate checked. If death from poisoning is suspected, samples of earth from above, below and the sides of the coffin as well as from a distant part of the cemetery must be taken, together with a sample of any grave water.*



FIGURE 1.25 *Following exhumation, the body is transported to a mortuary for full autopsy. The former practice of autopsy in inadequate premises near the cemetery is no longer justified. Here the original rotted infant coffin is placed within a new coffin for transit.*

If poisoning is suspected, samples of the shroud, coffin trimming and any loose material such as packing or fluid should be retained for analysis. The body is then removed, undressed and a full autopsy carried out, as far as the condition of the body allows. Putrefaction, adipocere and mummification complicate the examination – sometimes, all three may be present in the same body.

The pathologist is sometimes asked by the authorities or by lawyers whether a proposed exhumation is worth carrying out, because of doubts about the usefulness of the result. Certainly the balance between the potential advantages must be weighed against the cost, publicity and distress to relatives that might be caused. In general, however, it is surprising how much information may be gained even when the body has been buried for many months or even a few years. Much will depend on the actual environment of the grave: a gravel or sandy soil, especially in an elevated position, will allow a body to remain in a much better state of preservation than one in the waterlogged loam of a valley. The author (BK) has seen burials only 20 years old with empty coffins containing silt, but no soft tissue or even bones (due to a constantly rising and falling water table) in an area of acidic peat.



FIGURE 1.26 *When the coffin is first opened in the mortuary, the coffin fitting and fabrics should again be identified by the funeral director, as well as the body and its clothes, if they can be recollected. This infant has been buried for 3 years. The upper part of the coffin has leaked, allowing liquid mud to cover and substantially destroy the head.*

Even negative information gained at exhumation, such as the absence of alleged or suspected fractures, may be of considerable legal value. Some poisons, especially heavy metals, may persist for many years in a buried body and be detectable at exhumation. Even some organic chemicals may survive for a long time; barbiturates have been found after 7 years in a buried body. In all cases of suspected poisoning, it is vital that ample control samples are taken from the grave and its surroundings, to avoid the later accusation that any abnormal substances found were environmental artefacts or were unassociated with the corpse.

THE AUTOPSY ON THE PUTREFIED CORPSE

In forensic work, decomposed bodies are commonplace, especially in warm climates. Though the value of an autopsy is progressively reduced as the state of putrefaction advances, no short cuts should be taken by the pathologist merely because of the unpleasant nature of the examination. However bad the condition of the corpse, every effort should be made to carry out the autopsy as near to the usual routine as possible. It is often surprising – as with an exhumation – how much information can be gained. The interior of the body is often far better preserved than the outward appearances would suggest, so a policy of defeatism that leads to a skimped examination should never be adopted.

Externally, putrefaction hides bruising to a variable degree, the greenish black coloration of the skin masking the usual features of contusion. Abrasions, lacerations, incised wounds and gunshot wounds may, however, survive severe degrees of decomposition. Loss of bloody fluid from the mouth and nostrils (the so-called ‘purging’) is often mistaken by public, police and even some doctors as evidence of haemorrhage, but loss of serous, bloody or frothy fluid from any body orifice is common in the advanced stages of putrefaction.

Peeling and slippage of skin may hide some abrasions, though they may be visible when the desquamated epidermis is removed and the underlying skin examined. Marks around the neck from the tissues swelling with gas and becoming embedded in a collar have been mistaken for strangulation.

Where maggot or other insect infestation is present, some may be taken for expert entomological examination to help in assessing the post-mortem interval, as described in Chapter 2. As stated above, the external examination should be conducted as near as possible to the routine for a fresh body, and the back and perineum not neglected because of physical difficulties in handling the body.

Identity may be a problem when the facial features are too bloated for visual recognition. The usual procedures described in the next chapter may be employed where necessary. Fingerprints may be required by the police to assist in identity, but decomposition may seriously destroy the fingertips. These may become swollen and desquamate, or may shrivel and become leathery. Several methods of restoring the amputated tips have been described: some recommend a simple method of immersing the tips in 20 per cent acetic acid for 28–48 hours, when the shrivelling will swell to normal size. Others recommend immersion in glycerine.

Internally, much will depend on the state of decay. The abdominal and chest organs may be in a better state of preservation than the exterior. The subcutaneous tissues may be distended and crepitant with gas, as may be the swollen abdomen. Judicious penetration of the peritoneum with the tip of knife may be needed to release the pressure of gas. The technique of lighting the escaping methane with a burning newspaper may be spectacular and sometimes near explosive, but does little to reduce the smell and is not to be recommended.

Examination of the organs follows the usual pattern, modified according to state of putrefaction. The heart may be limp and discoloured, with haemolysis staining of the endocardium and vessels. The coronary arteries are often very well preserved, especially if atheromatous or calcified, or both. Ante-mortem thrombi may persist even after the muscle is semiglutinous. The larynx may be discoloured, but the hyoid and thyroid horns can be examined for fractures and may need to be X-rayed. It may be difficult to detect antemortem bleeding at the fracture sites. Fractures elsewhere in the skeleton naturally persist and may require radiography for their detection, as may foreign objects such as bullets.

The brain often decomposes early, and all too often is merely a pinkish-grey paste within the dura. Gross lesions like a large meningeal or intracranial haemorrhage may survive for examination, but the trauma of removing the calvarium and attached dura may seriously damage a semifluid brain. In Belgium, where exhumations are common due to the very low primary autopsy rate, a technique was developed in the University of Gent whereby the head of a decomposed body was removed from the body and deep frozen until solid. The head was then cut across in the coronal plane with a band-saw, leaving the brain in two halves within the cranium. These were then immersed in a large volume of formalin until fixed, when they could be removed in a relatively solid state for examination.

Internally, the detection of true subcutaneous bruising may be very difficult due to the discoloration of putrefaction. Histology is often highly unsatisfactory because of cellular lysis and degeneration; stains for haemoglobin may help in revealing focal collections of lysed blood, but are often diffusely positive even in control areas. Claims have been made for staining for glycophorin A to detect red cell envelopes, as opposed to diffuse haemolysis (Kibayashi *et al.* 1993).

RESUSCITATION ARTEFACTS AT AUTOPSY

In recent years, the advent of effective, but often aggressive and invasive, resuscitation procedures has made the task of the pathologist more difficult. At autopsy, injuries and abnormalities are now often found that could be due to terminal and even post-mortem resuscitatory measures. Where the pathologist is made aware of these, he can often exclude the damage being due to non-resuscitatory injury, though even when he is informed of the procedures they can still mask or mimic more sinister trauma. When he is not made aware – or such information cannot be made available – then the difficulties of interpretation are compounded.

There are now many publications describing resuscitation artefacts, including the review of Leadbeatter and Knight (1988). The following are the main categories of damage, for which the pathologist must always be alert:

- Bruising of the anterior chest wall, haemorrhage into the subcutaneous tissues and pectoral muscles, fractures of the sternum, fractures of the ribs, haemothorax, bruised lung, lacerated lung, pericardial haemorrhage, and even fractured dorsal spine, following energetic external cardiopulmonary resuscitation (CPR). Thoracic cage fractures are rare in children, however, because of the pliability of the ribs and costal cartilages, but it cannot be denied that they sometimes occur. The differentiation is naturally of vital interest where child abuse is being alleged.

  Internally all types of damage to the heart may occur, including ruptured atria and even ventricles, septal rupture and valve damage. The great vessels can suffer severe trauma, as described in the now extensive publications on resuscitation artefacts. Fat and bone marrow emboli in the pulmonary vessels have also been reported after cardiac massage (Mason 1993).

  Petechiae in the eyes and intra-ocular haemorrhages can occur after CPR, as well as after violent sneezing or coughing; they are well known to occur during whooping cough.
- Bruising of the face and neck, finger marks and nail marks on the face and neck, and damage to the lips and inner gums from mouth-to-mouth resuscitation, when the face and neck have been gripped by hands. Damage to lips, gums, teeth and pharynx can occur from the introduction of an artificial airway or endotracheal tube, especially in difficult, hurried emergency situations.

  Injuries to the larynx, even including fracture of the hyoid and thyroid cornuae, can occasionally occur from these procedures, which are difficult to distinguish from manual strangulation if the circumstances are obscure.
- Puncture marks for venepuncture may be confused with injection marks in drug dependence. The introduction of intravenous cannulae into veins in the neck may cause large haematomata and more diffuse bleeding into the tissues alongside the larynx.

Similar bruising may occur around puncture sites in the arms and groin. Intracardiac injections leave marks on the chest wall and may lead to a slight haemopericardium. The effects of injected noradrenaline and electrical defibrillation on the histological appearance of the myocardium are well recorded, with contraction bands being the most obvious artefacts which can be mistaken for pre-existing myocardial ischaemia.

- Damage to the mouth, palate, pharynx and larynx can occur from attempts to introduce a laryngoscope or airway. Even fracture of the mandible has been caused in this way. In infants, even digital clearance of the pharynx can cause mucosal damage. Damage to the pharyngeal mucosa may cause bleeding, which can seem sinister to police or relatives; this may be mixed with the fluid of pulmonary oedema to produce copious pink, bloody froth, seen in a number of cases, including sudden infant death syndrome.
- Electric defibrillator pads make marks on the chest, though these are usually easy to interpret, except where there is an unusual shape. Defibrillators and injected β-adrenergic catecholamines such as noradrenaline can, however, cause widespread histological damage to the myocardium, consisting of coagulation necrosis and contraction bands, which can be confused with infarction or electrocution. When both defibrillation and catecholamines have been used to resuscitate, the myocardial changes are even more marked (Karch 1987).
- During the Heimlich manoeuvre to clear an airway obstruction, rupture of the oesophagus, stomach and intestines have been reported. The oesophagus can be perforated by an incorrectly inserted airway. In the abdomen, external cardiac massage may cause ruptured stomach, ruptured liver, and damage to spleen and pancreas.
- Gastric contents in the air passages may have reached there by spontaneous agonal regurgitation or by pumping the chest and upper abdomen during resuscitation attempts. This makes the finding of vomit in the larynx and trachea of even less significance as a cause of death, as discussed in Chapter 14.
- The administration of oxygen by mask or tube may cause damage, as can overenergetic mouth-to-mouth resuscitation. Ruptures of oesophagus and lung have occurred, and other types of barotrauma include ruptured stomach and intestine. Where a pre-existing gut lesion exists, the administered gas may escape into the abdomen. The diagnosis of a pre-existing pneumothorax may be impossible where forced ventilation has been administered.
- In the central nervous system, subarachnoid haemorrhage has been described after external cardiac massage, and from hyperextension of the neck to pass an airway or perform mouth-to-mouth resuscitation. The forced posture can tear the vertebral arteries, making another source of confusion for the forensic pathologist in this difficult area of potential trauma to the neck (Chapter 5).
- Myocardial and pulmonary bone marrow embolism has been reported following cardiac massage (Dziecol *et al.* 1992).
- Retinal haemorrhages, classically a sign of raised intracranial pressure and of head injury, have also been described in whooping cough and after CPR.
- Miscellaneous artefacts of which every pathologist should be aware include: skin maceration from a body lying in urine, kerosene, etc., post-mortem burns from adjacent radiant heat or hot-water bottles; and petechiae and larger haemorrhages in the face from postural hypostasis.

MASS DISASTERS – THE ROLE OF THE PATHOLOGIST

With the exception of the more dramatic murders, the activity which focuses most public attention on the work of forensic pathologists is the mass disaster. Unfortunately, such tragedies are becoming more common with the increase in terrorism, the expansion of travel facilities and the larger size of passenger aircraft. Recent years have seen a tragically frequent need for the expertise of mass disaster teams, following such events as the Zeebrugge and Estonian ferry capsizes, football tragedies like Ibrox Park, Heysel, Moscow and Hillsborough, crush tragedies at Mecca, and numerous massive aircraft crashes, such as Tenerife, Air India, Japan, Lockerbie and most recently the terror attacks in the USA. Mass disaster management is a discipline in itself and only the briefest summary can be offered here, together with useful references at the end of the section.

Forward planning

Many pathologists will thankfully spend their entire careers without having to participate in a major mass disaster; a commonly accepted definition is the death of more than 12 victims in a single event. No one can predict when such a tragedy might occur, however, as typified by the 1988

Pan Am sabotage, when almost 300 bodies fell out of the sky on a quiet and unsuspecting Scottish village. It is thus essential that every forensic institute, department and individual pathologist should make some forward provision for such an eventuality. In Britain, the Royal College of Pathologists (1990) have published a useful booklet on the role of the pathologist in these disasters.

In most advanced countries each region now has a Mass Casualty Plan covering medical and hospital services, fire service and police. This is often very detailed, covering every aspect of transfusion, drugs, casualty transport, emergency surgery and anaesthesia. The plans are clinically orientated, but often completely ignore provision for the dead – or they have some cursory statement at the end such as 'Mortuary accommodation will be provided' with obviously no thought given to how several hundred corpses are to be accommodated and examined. Though clinical planning is, of course, vital – especially in rail disasters, multiple motorway crashes and urban bomb outrages – it has to be appreciated that, in many air crashes, there are few if any survivors, and that all the clinical planning may be redundant, leaving a massive and unprepared crisis in relation to the dead.

It is therefore essential that forensic pathologists should ensure that, in the area for which they are responsible, there is cooperative preplanning that includes adequate provision for collection, accommodation, examination and disposal of large numbers of dead victims. Naturally the pathologist is usually in no position to do this alone, but he is often the person with the most foresight and professional knowledge to act as the stimulus and catalyst between the major agencies responsible for overall planning. These are usually the police and the local health administration. When a Mass Casualty Plan does exist, but has serious omissions in respect of dealing with the dead, or where no such plan exists, the forensic pathologist should energetically stimulate the responsible authorities into making a comprehensive plan. This entails a series of meetings to identify danger areas in the region (such as airports, motorways, railways and military installations), and to discuss potential buildings for temporary mortuaries, the provision of materials such as markers, plastic bags and labels, which may be needed in large quantities at a few hours' notice. Communications between such groups as police, pathologists, mortuary and laboratory technicians, radiographers, and dentists also need to be established in advance. The expertise of international funeral directors with experience in mass disaster fatalities is invaluable.

The objects of pathological investigation in mass disasters are:

- to retrieve and reconstruct bodies and fragmented bodies decently
- to establish personal identity
- to conduct autopsies on some or all of those bodies
- to establish the cause of death in some or all, especially air crew and drivers, and to assist in reconstructing the cause of the disaster
- to obtain material for toxicological analysis (especially alcohol and carbon monoxide) where appropriate
- to seek evidence of the cause of the disaster from autopsy examination, such as bomb or detonator fragments that may be embedded in the bodies.

Outline of necessities in mass disaster planning

PROVISION OF PATHOLOGISTS AND OTHER STAFF

Depending upon the scale of the tragedy, it may be necessary to recruit other pathologists to assist. In large cities, there may be sufficient persons with expert forensic knowledge, but elsewhere, hospital pathologists may be able to assist; forensic pathologists from a distance may also volunteer. It has to be remembered that a really large disaster may need many days or even weeks of work, and therefore personnel may be unavailable for the whole period. In addition, whatever the degree of willingness and unselfish devotion offered by doctors and all other staff, the physical and especially psychological stresses of this harrowing work mean that strictly limited periods of work should be imposed. Apart from the deleterious effect upon the doctor, the standard of work declines dramatically with fatigue and therefore it is in the interests of the investigation – as well as of the pathologists – that sufficient staff be recruited. This may, however, be easier said than done. One person must be in overall charge of the investigation. Usually a senior police officer has the ultimate responsibility, but the medical aspects should be firmly under the control of a senior pathologist, though he must delegate extensively to avoid being swamped by less important tasks and thereby being rendered totally inefficient. Again, all these aspects are modified by the scale of the disaster. Proper facilities for meals, rest and washing must be established, and again forward planning is essential for these mundane, but vital, features. Forensic dental and radiological expertise will be run independently by their own specialists, but there must still be a nominal chief in the form of the senior pathologist who acts as overall coordinator and arbiter of medical matters.

When a disaster, almost always an aircraft crash, occurs in some remote place or abroad where there are no satisfactory forensic or pathological services, it is the usual practice for a team from the country of origin of the aircraft – or a volunteer team arranged at governmental level – to fly to the scene and provide expertise to the local authorities.

In many advanced countries, especially Britain, the armed services have permanent aviation pathologists who deal with all service aircraft crashes anywhere in the world and who are often available to deal with, or attend as advisers, any civil air disaster.

PROVISION OF MORTUARY FACILITIES

Most hospital mortuaries and even larger public mortuaries have limited storage capacity for bodies, and even smaller provision for performing simultaneous autopsies. It must also be appreciated that the normal business of a mortuary has to continue even through a mass disaster, so the massive increase in work is an addition to, not a substitution for, the normal handling facilities. Where more than about ten bodies are involved, most mortuaries cannot cope with these problems, especially when it has to be remembered that some of the corpses may have to be retained for considerably longer periods than usual if identification cannot be made rapidly. Thus external facilities will have to be provided in some temporary accommodation. When the disaster is a long distance from the regular mortuary, transport and other logistic considerations may make it imperative to store and examine the bodies nearer to the crash site. Again forward planning is essential to identify hangars, storehouses, empty factories, halls and other buildings near potential danger spots such as airports. Whenever possible, all bodies should be taken to one site, as the separation of identification sites is a recipe for inconvenience, delay and mistakes. It is sometimes necessary, especially in remote regions, to set up tented mortuaries, but this is a last resort as facilities cannot be laid on with the same degree of efficiency. Where the crash is totally remote, it is usual for the authorities or the armed services to bring out the dead by helicopter or other transport to an urban site. A prime example was the Mount Erebus crash in Antarctica, where the dead were flown back to New Zealand. If a warehouse, or factory or building of similar size, can be used, certain minimum facilities are needed. Good electric lighting, portable lights for close inspection, and power points for radiographic equipment and electric instruments are required. Adequate piped water, and washing and toilet facilities are essential. If any of these is deficient, then portable generators and water tankers must be supplied by the armed services or the police. Telephone and, if possible, telex and fax facilities should be available for the input of identifying data.

In hot climates, or in the summer in temperate climates, body refrigeration is vital, not only for the decent preservation of the dead but for retention of tissues awaiting identification. If a disaster is too large to be handled in the usual mortuary, then some form of cooling is required. The renting of refrigerated trucks used for the transport of foodstuffs is the usual answer and, again, preplanning is necessary to discover sources of such facilities. Sometimes portable air-conditioning units can be installed in part of the mortuary, if this is sufficient to cool the storage area to an acceptable level. In disasters where there are both living and dead victims, the mortuary should be sited away from the clinical facilities or screened in some way to avoid the distressing sight of bodies arriving being visible to survivors or their relatives, and the press.

The temporary mortuary should be large enough for the expected load, and the area to be used for examinations and autopsies should not be too congested. No one should be allowed in who does not have direct business there, no matter of what eminence or rank. Security of admission should be tight, this being the responsibility of the police. Flooring should be waterproof and capable of being hosed down. It can be protected against blood, mud and burned fragments by covering with polythene from large rolls. Tables for examination can be wooden trestles, covered with polythene. These should be in rows one metre apart, with 2 metres between rows.

Retrieval of bodies

This is the task of the police or armed services, but must be carried out in a manner approved by the forensic identifying team. It is essential that every body is first certified as dead by a doctor at the scene. Often, volunteer casualty surgeons may be the first medical persons at the scene, whose primary duty is to rescue living survivors and to confirm death in the remainder.

Each body or fragment should be flagged with a sequential and unrepeatable serial number and marked on a grid plan, being photographed *in situ* wherever possible. It is then bagged and taken with its numbered label to the mortuary. Different teams will have different methods of dealing with the logistics of handling data and, increasingly, this is being performed on either microcomputers or on terminals linked to a central computer. The police have responsibility for these aspects, as they collect and record the clothing and personal belongings that play such an important part in personal identification.

Either the same serial number is used from the recovery stage or a different ‘pathology’ number is begun in the mortuary, which must be matched up with the previous serial number. Everything that has come from that body, including clothing, wallets, rings, teeth and jewellery, must carry the same number.

The pathologist and lay assistants undress the clothed bodies, and dictate a description of what is found as accompanying artefacts. The clothes are stored in strong paper



FIGURE 1.27 *Temporary coffins used to transport victims of the m/s Estonia disaster from the archipelago to the autopsy facility.*

bags to avoid the fungal growth that inevitably appears on damp fabric kept in plastic bags.

Many items will have been found loose at the site, but they must all be tagged and an attempt made to relate them to a nearby body, though this is obviously fraught with error. The objects found on a body are recorded on an inventory form and a separate form (usually the Interpol document) used for the purely medical and anatopathological aspects. The latter data are acquired by meticulous and systematic external examination, followed by an internal autopsy if this is to be carried out.

Whether or not an autopsy is to be performed on some or all of the victims will depend upon facilities, availability of pathologists, the legal direction and the system prevailing in the particular country. The wishes of the legal authority, such as coroner, judge, medical examiner or police, will be the deciding factor in determining how many victims are subjected to autopsy. The pathologist should exert his influence where there is reluctance to sanction any autopsies, emphasizing the benefit to the crash investigators of autopsy data on key victims. Pathology findings may often be of use – it has even been claimed that victims can be separated into smokers and non-smokers by finding 'smoker cells' in the lungs (Reiter and Risser 1994).

As mentioned, the aircrew or other persons in charge of a vehicle or train should always have a full examination and analysis of body fluids as part of the accident investigation. Full photography of the clothing and bodies should be taken, and then all physical features such as height, weight, gender, race, colouring, scars, tattoos and deformities must be recorded. The forensic dental examination is then carried out on those bodies where obvious identity cannot be established by non-medical or dental means.

Radiological examination will almost always be required to assist in identification from osteological features and dental aspects – and perhaps also to seek foreign bodies that may assist in accident reconstruction, such as metal fragments blown upwards into the thighs and buttock in a hold explosion in an aircraft bomb – or even parts of the bomb or detonator itself, more especially in land-based terrorist attacks.

Toxicology should be taken as extensively as possible, even from some of those bodies that are not to have an autopsy. The data acquired from this painstaking work is then forwarded to the police bureau who have been collecting personal data from the records and relatives of the victims, and efforts are made to match the two sets of data. This is increasingly being performed by computer, and many efforts have been made by international agencies such as Interpol to set up universally compatible systems so that data can be acquired and exchanged electronically via telephone systems and modems from any part of the world.

In 1990, the Royal College of Pathologists published a definitive guide for pathologists to the problem of mass disasters, which is strongly recommended as a standard set of procedures.

THE OBSCURE AUTOPSY

Several surveys in various countries have shown that where a physician offers a cause of death without the benefit of autopsy findings, the error rate is of the order of 25–50 per cent, even in deaths in hospital. Thus the value of an autopsy in improving the value of death certificates is undoubted, but it still has to be conceded that the autopsy is by no means infallible in revealing the true cause of death. Estimates of the frequency with which autopsies fail to deliver an adequate or even any cause of death vary from pathologist to pathologist, as well as with definitions of what type of case a is included in such series. For example, the sudden infant death syndrome (SIDS) could be considered to provide 'negative autopsies', in that by definition, no significant findings are discovered.

Even excluding SIDS, there is probably at least a 5 per cent 'failure rate' in autopsy series from large medical centres and forensic pathology departments. This rate will also vary according to the habits, personality and seniority of the pathologists involved. Contrary to what might be expected, a higher rate of negative conclusions will originate from older and more experienced pathologists than from juniors. The younger pathologist is often uneasy about failing to provide a cause of death, feeling that it reflects upon his ability, whereas the more grizzled doctor, enjoying the security of tenure and equality with – or even seniority over – his clinical and legal colleagues, is less inhibited in his admissions of ignorance when the cause of death remains obscure.

These 'obscure autopsies' are more common in the younger age group. Even apart from SIDS, many autopsies on infants, especially neonates, are less than satisfactory in terms of definite morphological lesions discoverable in the autopsy room or the laboratory. The deaths often have a biochemical or hypoxic basis and, though inferences can be made from the clinical history, even expert paediatric pathologists have to make do with minimal or even absent findings in a significant proportion of cases. In teenagers and young adults, up to the age of about 35 years, there is a higher proportion of negative autopsies than in the older group, which provides the vast majority of the autopsy workload. An example is the obscure syndrome seen in East Asia, where Thai construction workers in Singapore suddenly die with no demonstrable pathological cause, similar cases occurring in China, Japan and Hong Kong.

This preponderance in the young may carry an inherent fallacy, even though there may be an absolute increase in the incidence of obscure fatal causes. The young adult does not have the almost universal overlay of degenerative cardiovascular disease that is seen in the older group. Thus it is probable that the same occult disease processes occur in that older group as in the young, but as the latter do not have other lesions that can be grasped (usually quite legitimately) as a valid cause of death, then nothing presents itself to the pathologist. For example, on one autopsy table might be the body of a man of 22 who dropped dead shortly after taking part in a football match. There may be no adverse medical history, the gross examination revealed nothing abnormal and subsequently full histology with special stains, full toxicological screening, and microbiological and virological studies, were unrewarding. No cause of death can be extracted from these negative findings and the case must be recorded as 'unascertained' – or, as Professor Alan Usher of Sheffield points out, as 'unascertainable', if the pathologist is feeling particularly omnipotent!

On the next table in the autopsy room, however, may be a man of 60 who has been found dead with no available history. On examination he is found to have 60 per cent stenosis of the anterior descending branch of his left coronary artery, but no recent or old damage to the myocardium. Histology may well be performed, with no further information obtained. The cause of death is likely to be recorded as 'coronary artery disease' by most pathologists, yet he might well have died from the same obscure cause as the young man, but because he has just sufficient arterial degenerative disease to prove fatal, the latter is accepted as the most likely cause of death. This feeling of disillusion may be reinforced by the presence on the third autopsy table of another man of 60 who has been killed by a firearm, yet who has 80 per cent stenosis of all three coronary vessels, this obviously having played no part in the death.

Whatever the philosophical aspects of this problem, the practical difficulty remains of the pathologist's course of action when faced with negative findings in an autopsy.

At the end of the gross examination in the autopsy room, as the depressing realization increases that nothing significant has been found, further action will depend partly upon the facilities available to the pathologist, especially in relation to toxicological, biochemical, microbiological, virological and histological laboratory service.

Before proceeding further to review the dissection, attention must be paid to obtaining adequate samples for ancillary investigations. In many cases, especially where the history alerts the experienced pathologist that this might be a difficult case – and usually always in young people – samples of blood, urine and stomach contents will have been taken as routine during the removal and first dissection of the viscera.

If a blood sample has not already been taken, it should now be obtained, preferably from a peripheral vein such as the axillary or femoral to avoid contamination from the now empty trunk cavities. If urine was not retained from the bladder, a few drops may still be found in that opened organ by suction with a syringe. Stomach contents may well have been lost, but the liver can be retained for toxicological analysis. It might be useful to take vitreous humour if urine and stomach contents have been lost.

Some blood may be used for inoculation of blood culture bottles and swabs can still be taken for microbiological investigations. If a lung infection is possible, then either a few grams of lung tissue can be removed into a sterile jar, or swabs can be taken from peripheral bronchi or from the lung parenchyma itself. As the surface of all cut organs will have been contaminated during the first dissection, cuts should be made into the surface of the lung using a new sterile scalpel so that relatively fresh tissue is obtained for culture. At the same time, a cube of lung – or other organ if desired – should be taken into a sterile container for virus studies.

Before tissue for histology is taken, a full review of the more vital parts of the dissection should be reviewed. Even in younger victims the first area to be studied again is the coronary system, and in older obscure deaths it is essential to re-examine these vessels. Although the coronaries should have been transected at short intervals (not more than 3 mm apart) on the first examination, it is prudent to retrace each vessel carefully from the aortic origin distally, looking again at each cut segment and, where the interval appears too large, to make further intermediate cuts. In addition, it may be wise to join the segments longitudinally between cuts, in case a small isolated thrombus is lurking in the lumen. This should be done for common left trunk, anterior descending branch, left circumflex and right coronary artery.

This review of the coronary system sometimes pays dividends, especially in the middle-aged group that at first sight appears to have good coronary vessels. A tiny segment may be occluded or severely stenosed over a distance of only 2 or 3 mm, either by pure atheroma or by a subintimal haemorrhage, ruptured plaque or a localized thrombosis. If nothing is found, then after a quick review of the valves and great vessels, the myocardium can be sliced more extensively and a number of representative blocks taken for histology, to seek a myocarditis or some obscure cardiomyopathy.

The other organs should be examined again, the pulmonary arteries being scrutinized for pulmonary emboli in the smaller branches. This is rarely productive, but the author (BK) has on several occasions found multiple small emboli in more peripheral lung vessels, although whether these were a valid cause of death was debatable. The brain should be looked at once more, with special attention being paid to the basal arteries. These should be opened with coronary scissors and the dissection carried up into the middle cerebral arteries where they lie in the Sylvian fissures. It is also always worthwhile looking in the carotid arteries in the neck, though these should always be opened routinely at the first dissection from the aorta to a point just distal to the carotid sinuses; even the difficult area above this at the base of the skull has provided some surprises in the past. It is a place rarely examined, except by neuropathologists, but forensic pathologists should add it to their 'repertoire', as occasionally total thrombotic occlusion may be found, especially following some undisclosed neck injury.

When a complete review of the gross pathology has proved fruitless, then a full histological survey is required, especially of the myocardium. Special stains such as phosphotungstic acid-haematoxylin, dehydrogenase enzyme histochemistry (which requires unfixed, frozen sections), acridine-orange fluorescence stains and any other technique that the pathologist favours. Admittedly, where no cardiomegaly or coronary artery stenosis is present, the chances of finding an abnormality are slight, but an isolated myocarditis is an outside chance.

Toxicology may be difficult and expensive if there is no cause to suspect any particular drug or poison. A screen for unknown substances can be time consuming for the laboratory, which means a large expense to public funds. An alcohol estimation and a screen for acidic and basic substances, however, though not comprehensive, can at least exclude most common poisons. Microbiology and virology rarely point to a previously unsuspected fatal disease process unless the patient had clinical signs and symptoms before death.

When all the results are available, which may take several weeks (especially in the case of virus cultures), the case must be reviewed and an honest opinion offered as to whether any positive findings are sufficient to have caused death. In the experience of the authors, these ancillary investigations more often provide no help, than the times when they offer some assistance, but they must be carried out whenever possible in order to exclude such causes and to prevent allegations that the death was not investigated as fully as it should have been.

If at the end of the process no cause of death is apparent, then the appropriate investigating authority must be informed that no opinion can be offered in the present state of medical and scientific knowledge. It can be added, however, that the absence of injuries, evidence of poisoning, lethal infection or well-recognized natural disease is in itself significant negative evidence in that it confirms what the deceased did not die of, and the assumption is then that the balance of probabilities is that it was natural causes, rather than some unnatural external event.

There must be complete honesty on the part of the pathologist and a readiness to admit that the cause of death cannot be determined. The use of some meaningless euphemism such as 'heart failure' or 'cardiorespiratory arrest' is pointless and merely confuses the issue for non-medical persons such as police or magistrates. As mentioned above, there is a tendency on the part of some younger pathologists or histopathologists who rarely become involved in medicolegal cases to assume some unwarranted disease process or to attribute significance to insignificant findings. A **mode** of death is useless in lieu of a **cause** of death, so is the dangerous practice of using some agonal event such as 'inhalation of vomit' where there is no eyewitness confirmation of such an event taking place during life. It is also useless and positively dangerous to guess at some totally unprovable process, such as 'vagal inhibition', 'reflex cardiac arrest' or 'suffocation', just because these conditions are thought to leave no traces and therefore a death with no traces must be due to such a cause. This is illogical thinking and has led to several miscarriages of justice in the past, as well as to far more family anguish.

As the pathologist increases in experience and maturity, he or she is more ready to concede that he cannot find a cause of death, and this is far more satisfactory. In forensic work, this is not 'abrogating responsibilities' but being objective, sensible and just. There is no point in producing a speculative cause of death if that cannot be substantiated in later court evidence or legal statements. It is, of course, quite justifiable and indeed, part of the pathologist's responsibilities, to discuss the range of possible causes with the authorities responsible for investigating the death, but to be dogmatic about a single cause where the grounds for such a decision are tenuous does not help anyone and can lead to unfortunate consequences.

REFERENCES AND FURTHER READING

Adelson L. 1953. Possible neurological mechanisms for sudden death with minimal anatomical findings. *J Forensic Med* **1**:39–42.

Adelson L. 1974. *The pathology of homicide*. Thomas, Springfield.

Annegers JF, Coan SP. 1999. Sudep: overview of definitions and review of incidence data. *Seizure* **8**:347–52.

Asnaes S, Paaske F. 1980. Uncertainty of determining mode of death in medico-legal material without autopsy – a systematic autopsy study. *Forensic Sci Int* **15**:3–17.

Ball J, Desselberger U, Whitwell H. 1991. Long-lasting viability of HIV after patient's death. [letter] *Lancet* **6**:63.

Bankowski MJ, Landay AL, Staes B, *et al.* 1992. Postmortem recovery of human immunodeficiency virus type 1 from plasma and mononuclear cells. Implications for occupational exposure. *Arch Pathol Lab Med* **116**:1124–7.

Boukis D. 1986. Repeat autopsies on corpses from abroad. A futile effort? *Am J Forensic Med Pathol* **7**:216–18.

Bowen DA. 1966. The role of radiology and the identification of foreign bodies at postmortem examination. *J Forensic Sci Soc* **6**:28–34.

Braden G. 1975. Aircraft type crash injury investigation of a commuter train collision. *Aviat Space Environ Med* **46**:1157–60.

Brown T, Delaney R, Robinson W. 1952. Medical identification in the noronic disaster. *JAMA* **148**:621.

Buck N, Devlin HB, Lunn JN. 1988. *The report of a confidential enquiry into perioperative deaths. Perioperative deaths*, vol 39. Nuffield Provincial Hospitals Trust, London.

Cameron JM, Grant JH, Ruddick R. 1973. Ultra-violet photography in forensic medicine. *J Forensic Photogr* **2**:9–14.

Cameron HM, McGoogan E, Clarke J, Wilson BA. 1977. Trends in hospital necropsy rates. *Br Med J* **18**:1577–80.

Cameron HM, McGoogan E, Watson H. 1980. Necropsy: a yardstick for clinical diagnoses. *Br Med J* **11**:985–8.

Campling EA, Devlin HB, Lunn JN. 1990. *Gynaecology and the national confidential enquiry into perioperative deaths*. Royal College of Surgeons, London, pp. 466–7.

Camps FE. 1953. *Medical and scientific investigations in the Christie case*. Medical Publications, London.

Camps FE. 1972. Exhumation. *Criminologist* **7**:736.

Cao Y, Ngai H, Gu G, Ho DD. 1993. Decay of HIV-1 infectivity in whole blood, plasma and peripheral blood mononuclear cells. *AIDS* **7**:596–7.

Carpenter R, Dorn J, Hopkins B, *et al.* 1986. *Multiple death disaster response*. National Funeral Directors Association, Milwaukee, WI.

Clark DH. 1986. Dental identification problems in the Abu Dhabi air accident. *Am J Forensic Med Pathol* **7**:317–21.

Clark MA. 1981. The value of the hospital autopsy. Is it worth the cost? *Am J Forensic Med Pathol* **2**:231–7.

Clark MA. 1981. Applications of clinical laboratory tests to the autopsy: a practical guide for specimen collection. *Am J Forensic Med Pathol* **2**:75–81.

Claydon SM. 1993. The high risk autopsy. Recognition and protection. *Am J Forensic Med Pathol* **14**:253–6.

Copeland AR. 1986. Accidental non-commercial aircraft fatalities: the 7-year Metro-Dade county experience from 1977–1983. *Forensic Sci Int* **31**:13–20.

Cordner SM. 1985. The role of the second post-mortem examination. *Med Leg J* **53**:24–8.

Corwell WS. 1956. Radiography and photography in problems of identification. *Med Radiogr Photogr* **32**:34–40.

Cotton DW, Stephenson TJ. 1988. Impairment of autopsy histology by organ washing – a myth. *Med Sci Law* **28**:319–23.

Couch S, Noguchi TT, Wright J. 1981. Demonstrative evidence developed at the autopsy. *Am J Forensic Med Pathol* **2**:135–8.

de Craemer D. 1994. Postmortem viability of human immunodeficiency – implications for the teaching of anatomy. [letter] *N Engl J Med* **331**:1315.

Dodds JP, Nardone A, Mercey DE, *et al.* 2000. Increase in high risk sexual behaviour among homosexual men, London 1996–8:cross sectional, questionnaire study. *Br Med J* **320**:1510–11.

Donoghoe MC, Stimson GV, Dolan KA. 1989. Sexual behaviour of injecting drug users and associated risks of HIV infection for non-injecting sexual partners. *AIDS Care* **1**:51–8.

Douceron H, Deforges L, Gherardi R, *et al.* 1993. Long-lasting postmortem viability of human immunodeficiency virus: a potential risk in forensic medicine practice. *Forensic Sci Int* **60**:61–6.

Drake W, Lukash L. 1978. Reconstruction of mutilated victims for identification. *J Forensic Sci* **23**:218–30.

Durigon H. 1988. *Pathologie medico-legale*. Masson, Paris.

Durigon M, Ceccaldi PF, Renard J. 1983. Catastrophes et identifications: role des differentes structures. [Role of foreign physicians in the identification of catastrophy victims.] *Med-Armees* **3**:2524.

Dzieciol J, Kemona A, Gorska M, *et al.* 1992. Widespread myocardial and pulmonary bone marrow embolism following cardiac massage. *Forensic Sci Int* **56**:195–9.

Eckert WG. 1980. Catastrophes et morts collectives. Recent american experiences in mass deaths. *Am J Forensic Med Pathol* **1**:77–9.

Eckert WG. 1982. Fatal commercial air transport crashes, 1924–1981. Review of history and information on fatal crashes. *Am J Forensic Med Pathol* **3**:49–56.

Eckert WG. 1983. The untapped resource; the forensic and general autopsy. [editorial] *Am J Forensic Med Pathol* **4**:293.

Eckert WG. 1985. The disinterred body: do it right the first time. *Am J Forensic Med Pathol* **6**:5–6.

Enbom M, Sheldon J, Lennette E, *et al.* 2000. Antibodies to human herpesvirus 8 latent and lytic antigens in blood donors and potential high-risk groups in Sweden: variable frequencies found in a multicenter serological study. *J Med Virol* **62**:498–504.

Eriksson A, Krantz KP, Lowenhielm CG, *et al.* 1984. A device which allows dictation of the autopsy report during the autopsy. *Am J Forensic Med Pathol* **5**:279–82.

Evans KT, Knight B. 1986. Forensic radiology (see Notes). *Br J Hosp Med* **36**:14–20.

Fairburn G, McDonald K. 2000. Increased high risk sexual behaviour in homosexual men. Clarity may have been lost through including too much information. *Br Med J* **321**:1532.

Fatteh A. 1978. Exhumation, autopsy, second autopsy. *Leg Med Annu* 151–63.

Fatteh AV, Mann GT. 1969. The role of radiology in forensic pathology. *Med Sci Law* **9**:27–30.

Federal Emergency Management Agency. 1987. *Medical and emergency preparedness for disaster management: preventive medicine and public health aspects*. NATO-JCMMG, Study #4. Washington, DC.

Gee DJ. 1975. Radiology in forensic pathology. *Radiography* **41**:109–14.

Geller SA. 1990. HIV and the autopsy. [editorial] *Am J Clin Pathol* **94**:487–9.

Geller SA. 1990. The autopsy in acquired immunodeficiency syndrome. How and why [see comments]. *Arch Pathol Lab Med* **114**:324–9.

Gerber SR, Adelson L, Johnson L. 1956. The role of photography in the coroners office. *Med Radiogr Photogr* **32**:15–18.

Ghanem I. 1988. Permission for performing an autopsy: the pitfalls under Islamic law. *Med Sci Law* **28**:241–2.

Gilliland MG, McDonough ET, Fossum RM, *et al.* 1986. Disaster planning for air crashes. A retrospective analysis of delta airlines flight 191. *Am J Forensic Med Pathol* **7**:308–16.

Goldberg D, Scott G, Weir M, *et al.* 1998. HIV infection among homosexual/bisexual males attending genitourinary clinics in scotland. *Sex Transm Infect* **74**:185–8.

Goldman L. 1984. Diagnostic advances v the value of the autopsy. 1912–1980. *Arch Pathol Lab Med* **108**:501–5.

Goldman L, Sayson R, Robbins S, *et al.* 1983. The value of the autopsy in three medical eras. *N Engl J Med* **308**:1000–5.

Gonzales M, Halpern MH, Umberger CJ, Vance M. 1954. *Legal medicine and toxicology*, 2nd edn, vol. 64. Appleton Century Crofts, New York.

Gopinath C, Thuring J, Zayed I. 1978. Isoprenaline-induced myocardial necrosis in dogs. *Br J Exp Pathol* **59**:148–57.

Gordon I, Shapiro HA, Berson SD. 1988. *Forensic medicine; a guide to principles*, 3rd edn. Churchill Livingstone, Edinburgh.

Green MA. 1982. Sudden and suspicious deaths outside the deceased's own country – time for an international protocol. *Forensic Sci Int* **20**:71–5.

Gresham GA, Turner AF. 1979. *Post mortem procedures*. Wolfe Medical Publications, London.

Hartveit F, Karwinski B, Giertsen JC. 1987. Changes in autopsy profile – 1975 and 1984. *J Pathol* **153**:91–8.

Health Services Advisory Committee. 1991. *Safe working and prevention of infection in clinical labotories*. HMSO, London.

Heath Services Advisory Committee. 1991. *Safe working and the prevention of infection in the mortuary and postmortem room*. HMSO, London.

Hill IR. 1986. Toxicological findings in fatal aircraft accidents in the United Kingdom. *Am J Forensic Med Pathol* **7**:322–6.

Hirsch CS. 1971. The format of the medicolegal autopsy protocol. *Am J Clin Pathol* **55**:407–9.

Hollander N. 1987. Air crash disaster planning. [letter] *Am J Forensic Med Pathol* **8**:183–4.

Hunt AC. 1967. Instant photography in forensic medicine. *Med Sci Law* **7**:216–17.

Hunter J. 1772. *On the digestion of the stomach after death*. Philosophical Transactions of the Royal Society of London, Chapter 62, pp. 447–52. Royal Society of London, London.

Janssen W. 1984. *Forensic histopathology*. Springer Verlag, Berlin.

Jay GW, Leestma JE. 1981. Sudden death in epilepsy. A comprehensive review of the literature and proposed mechanisms. *Acta Neurol Scand Suppl* **82**:1–66.

Johnson HRM. 1969. The incidence of unnatural deaths which have been presumed to be natural in coroners' autopsies. *Med Sci Law* **9**:102–7.

Johnson MD, Schaffner W, Atkinson J, *et al.* 1997. Autopsy risk and acquisition of human immunodeficiency virus infection: a case report and reappraisal. *Arch Pathol Lab Med* **121**:64–6.

Kalichman SC. 1999. Psychological and social correlates of high-risk sexual behaviour among men and women living with HIV/AIDS. *AIDS Care* **11**:415–27.

Karch SB. 1987. Resuscitation-induced myocardial necrosis. Catecholamines and defibrillation. *Am J Forensic Med Pathol* **8**:3–8.

Kenyon CD. 1988. Identification and repatriation following major air disasters. *Forensic Sci Int* **36**:223–30.

Kibayashi K, Hamada K, Honjyo K, *et al.* 1993. Differentiation between bruises and putrefactive discolorations of the skin by immunological analysis of glycophorin A. *Forensic Sci Int* **61**:111–17.

Knight B. 1980. The obscure autopsy. *Forensic Sci Int* **16**:237–40.

Knight B. 1980. *Discovering the human body*. Lippincott & Crowell, New York.

Knight B. 1982. *Lawyer's guide to forensic medicine*. Heinemann Medical Books, London.

Knight B. 1983. *The coroner's autopsy*. Churchill Livingstone, London.

Knight B. 1984. *The post-mortem technician's handbook*. Blackwell Scientific Publications, Oxford.

Knight B. 1985. *Pocket picture guide to forensic medicine*. Gower Medical Publishing, London.

Knight B. 1988. A model medico-legal system. *Forensic Sci Int* **39**:1–4.

Knight B. 1996. *Simpson's forensic medicine*, 11th edn. Edward Arnold, London.

Koelmeyer TD, Beer B, Mullins PR. 1982. A computer-based analysis of injuries sustained by victims of a major air disaster. *Am J Forensic Med Pathol* **3**:11–16.

Kuller L, Lilienfeld A, Fisher R. 1966. Sudden and unexpected death in young adults: an epidemiological study. *JAMA* **198**:248–52.

Kunnen M, Thomas F, Van de Velde E. 1966. Proceedings of the British association in forensic medicine. Semi-microradiography of the larynx on post-mortem material. *Med Sci Law* **6**:218–19.

Landefeld CS, Chren MM, Myers A, *et al.* 1988. Diagnostic yield of the autopsy in a university hospital and a community hospital. *N Engl J Med* **318**:1249–54.

Langan Y, Nashef L, Sander JW. 2000. Sudden unexpected death in epilepsy: a series of witnessed deaths. *J Neurol Neurosurg Psychiatry* **68**:211–13.

Lawrence RD. 1985. Inaccuracy of measuring wounds on autopsy photographs. *Am J Forensic Med Pathol* **6**:17–18.

Leadbeatter S. 1986. Semantics of death certification. *J R Coll Physicians Lond* **20**:129–32.

Leadbeatter S. 1991. Deaths of British nationals abroad – a 10-year survey. *Forensic Sci Int* **49**:103–11.

Leadbeatter S, Knight B. 1987. The history and the cause of death. *Med Sci Law* **27**:132–5.

Leadbeatter S, Knight B. 1988. Resuscitation artefact. *Med Sci Law* **28**:200–4.

Lechat MF. 1976. The epidemiology of disasters. *Proc R Soc Med* **69**:421–6.

Leestma JE, Kalelkar MB, Teas SS, *et al.* 1984. Sudden unexpected death associated with seizures: analysis of 66 cases. *Epilepsia* **25**:84–8.

Leestma JE, Hughes JR, Teas SS, *et al.* 1985. Sudden epilepsy deaths and the forensic pathologist. *Am J Forensic Med Pathol* **6**:215–18.

Leestma JE, Annegers JF, Brodie MJ, *et al.* 1997. Sudden unexplained death in epilepsy: observations from a large clinical development program. *Epilepsia* **38**:47–55.

Li L, Zhang X, Constantine NT, *et al.* 1993. Seroprevalence of parenterally transmitted viruses (HIV-1, HBV, HCV, and HTLV-I/II) in forensic autopsy cases. *J Forensic Sci* **38**:1075–83.

Ludwig J. 2002. *Handbook of autopsy practice*, 3rd edn. Humana Press, Totowa, New Jersey.

Macdonald N, Evans B. 2000. Increased high risk sexual behaviour in homosexual men. There is no evidence for a decreased incidence of HIV infection. *Br Med J* **321**:1531–2; discussion 1532.

Mant AK. 1984. *Taylor's principles and practice of medical jurisprudence*, 13th edn. Churchill Livingstone, London.

Mason J. 1993. Resuscitation artefacts, including bone marrow. *Forensic medicine: an illustrated reference*. Chapman & Hall, London, pp. 39–42.

Mason JK. 1962. *Aviation accident pathology: a study of fatalities*. Butterworth, London.

Mason JK. 1962. The pathology of unsuccessful escape in flight. *Med Sci Law* **2**:124–30.

McCurdy WC. 1987. Postmortem specimen collection. *Forensic Sci Int* **35**:61–5.

McGarry P. 1967. A quick, simple method of removal of the spinal cord. *Arch Pathol* **83**:333–5.

Moritz A. 1942. *The pathology of trauma*. Lea & Febiger, Philadelphia.

Moritz AR. 1956. Classical mistakes in forensic pathology. *American Journal of Clinical Pathology* **26**:1383–92.

Morley AR. 1988. Value of the autopsy. *Assoc Clin Pathol News* **Spring issue**.

Nolte KB, Dasgupta A. 1996. Prevention of occupational cyanide exposure in autopsy prosectors. *J Forensic Sci* **41**:146–7.

Nolte KB, Taylor DG, Richmond JY. 2002. Biosafety considerations for autopsy. *Am J Forensic Med Pathol* **23**:107–22.

Peacock SJ, Machin D, Duboulay CE, *et al.* 1988. The autopsy: a useful tool or an old relic? *J Pathol* **156**:9–14.

Polson CJ, Marshall TK. 1975. *The disposal of the dead*, 3rd edn. English University Press, London.

Polson CJ, Gee D, Knight B. 1985. *Essentials of forensic medicine*, 4th edn. Pergamon Press, Oxford.

Pounder DJ. 1985. Natural disaster potential and counterdisaster planning in Australia. *Am J Forensic Med Pathol* **6**:347–57.

Prinsloo I, Gordon I. 1951. Post-mortem dissection artefacts of the neck and their differentiation from ante-mortem bruises. *S Afr Med J* **25**:358–61.

Puschel K, Lieske K, Hashimoto Y, *et al.* 1987. HIV infection in forensic autopsy cases. *Forensic Sci Int* **34**:169–74.

Puschel K, Lockemann U, Schneider V, *et al.* 1992. HIV-1 prevalence among drug deaths in major cities of central and northern europe. *Forensic Sci Int* **57**:57–62.

Reiter C, Risser D. 1994. Experience with the cytological demonstration of smoker cells in the identification of disaster victims illustrated by the findings concerning the Lauda Air airliner crash near Bangkok. *Forensic Sci Int* **66**:23–31.

Royal College of Pathologists. 1990. *Major disasters, the pathologist's role*. Royal College of Pathologists, London.

Royal College of Pathologists. 1993. *Guidelines for postmortem reports*. Royal Collage of Pathologists, London.

Royal College of Pathologists. 1995. *HIV and the practice of pathology; report of a working party of the Royal College of Pathologists*. Royal College of Pathologists, London.

Rutherford WH, de Boer J. 1983. The definition and classification of disasters. *Injury* **15**:10–12.

Saukko P. 1984. [Autopsy in Scandinavia.] *Beitr Gerichtl Med* **42**:339–41.

Saukko P, Pollak S. 2000. Postmortem examination: procedures and standards. In: Siegel JA, Saukko PJ, Knupfer GC (eds), *Encyclopedia of forensic sciences*. Academic Press, San Diego/San Francisco/New York/Boston/London/Sydney/Tokyo, Vol. 3, pp. 1272–5.

Schmidt G, Kallieris D. 1982. Use of radiographs in the forensic autopsy. *Forensic Sci Int* **19**:263–70.

Schultz TC. 1987. Simple method for demonstrating coronary arteries at postmortem examination. *Am J Forensic Med Pathol* **8**:313–16.

Shapiro H. 1954. Medicolegal mythology; some popular forensic fallacies. *J Forensic Med* **1**:144–69.

Sidwell RU, Green JS, Novelli V. 1999. Management of occupational exposure to HIV – what actually happens. *Commun Dis Public Health* **2**:287–90.

Simpson CK. 1965. *Taylor's principles and practice of medical jurisprudence*, 12th edn. J. & A. Churchill, London.

Skinner M. 1987. Planning the archaeological recovery of evidence from recent mass graves. *Forensic Sci Int* **34**:267–87.

Solheim T, van den Bos A. 1982. International disaster identification report. Investigative and dental aspects. *Am J Forensic Med Pathol* **3**:63–7.

Stevanovic G, Tucakovic G, Dotlic R, *et al.* 1986. Correlation of clinical diagnoses with autopsy findings: a retrospective study of 2,145 consecutive autopsies. *Hum Pathol* **17**:1225–30.

Stevens PJ. 1962. The medical investigation of fatal aircraft accidents. *Med Sci Law* **2**:101–9.

Stevens PJ. 1968. The pathology of fatal public transport aviation accidents. *Med Sci Law* **8**:41–8.

Stevens PJ, Tarlton S. 1963. Identification of mass casualties experience in four civil air disasters. *Med Sci Law* **3**:154–68.

Stewart TD (ed.). 1970. *Personal identification in mass disasters*. Smithsonian Museum. National Museum of Natural History, Washington, DC.

Sturt RH. 1988. Ver Heyden de Lancey lecture on a medico-legal matter. The role of the coroner with special reference to major disasters. *Med Sci Law* **28**:275–85.

Svendsen E, Hill RB. 1987. Autopsy legislation and practice in various countries. *Arch Pathol Lab Med* **111**:846–50.

Tedeschi LG. 1980. Future of the autopsy: a redelineation. *Am J Forensic Med Pathol* **1**:1034.

Titford M, Cumberland G. 1986. Forensic histotechnology: autopsy tissues and public issues. *J Histotechnol* **9**:263.

Tough SC, Green FH, Paul JE, *et al.* 1996. Sudden death from asthma in 108 children and young adults. *J Asthma* **33**:179–88.

Underwood JC, Slater DN, Parsons MA. 1983. The needle necropsy. *Br Med J Clin Res Ed* **286**:1632–4.

van den Bos A. 1980. Mass identification: a multidisciplinary operation. The Dutch experience. *Am J Forensic Med Pathol* **1**:265–70.

Vanezis P, Sims BG, Grant JH. 1978. Medical and scientific investigations of an exhumation in unhallowed ground. *Med Sci Law* **18**:209–21.

Waldron H, Vickerstaffe L. 1977. *Intimations of quality: antemortem and postmortem diagnoses*. Nuffield Provincial Hospitals Trust, London.

Wren C, O'Sullivan JJ, Wright C. 2000. Sudden death in children and adolescents. *Heart* **83**:410–13.

Wright RK, Tate LG. 1980. Forensic pathology. Last stronghold of the autopsy. *Am J Forensic Med Pathol* **1**:57–60.

CHAPTER 2

The pathophysiology of death

- Types of death 52
- The indications of death 53
- Hypostasis 55
- Rigor mortis 60
- Putrefaction 64
- Formation of adipocere 70
- Mummification 72
- Post-mortem damage by predators 73
- The entomology of the dead and post-mortem interval 76
- Estimation of the time since death by body cooling 78
- Stomach emptying as a measure of time since a death 83
- The use of vitreous humour chemistry in timing death 88
- Post-mortem chemistry 89
- References and further reading 90

Most of the discussion concerning the definitions of death belongs to the field of legal medicine and even that of ethics, rather than forensic pathology. Notwithstanding this, a quick review of this complex problem is appropriate here, as when we come to describe the various post-mortem phenomena, some appreciation is necessary of the zero point from which such changes are timed.

TYPES OF DEATH

It is conventional to describe two types of death:

- somatic death, in which the person irreversibly loses its sentient personality, being unconscious, unable to be aware of (or to communicate with) its environment, and unable to appreciate any sensory stimuli or to initiate any voluntary movement. Reflex nervous activity may, however, persist, and circulatory and respiratory functions continue either spontaneously or with artificial support so that the tissues and cells of the body, other than those already damaged in the central nervous system, are alive and functioning.
- cellular death, in which the tissues and their constituent cells are dead – that is, they no longer function or have metabolic activity, primarily aerobic respiration.

Cellular death follows the ischaemia and anoxia inevitably consequent upon cardiorespiratory failure, but it is a process rather than an event, except in the exceptionally rare circumstance of almost instantaneous total bodily destruction, such as falling into molten metal or a nuclear explosion. Even fragmentation of a body by a bomb does not kill all cells instantly.

Different tissues die at different rates, the cerebral cortex being vulnerable to only a few minutes' anoxia, whereas connective tissues and even muscle survive for many hours, even days after the cessation of the circulation.

Brain death

Without trespassing too far into clinical medicine, it may be further noted that somatic death is virtually equated with brain death. When the higher levels of cerebral activity are selectively lost, either from a period of hypoxia, trauma, or toxic insult, the victim will exist in a 'vegetative state'. Here the survival of the brainstem ensures that spontaneous breathing will continue and therefore cardiac function is not compromised. The victim can remain in deep coma almost indefinitely – certainly for years – though debilitating complications such as postural skin necrosis, muscle contractures, and secondary chest infections may well shorten life. Such vegetative patients are not considered 'dead' by most standards, though there is a faction of the medical profession who claim that, because of the irreversible loss of their awareness of themselves and the world around them, they can no longer be considered 'human beings'.

As they are not on life-support machines, however, there is nothing short of euthanasia that can be done about their condition. Attitudes are changing, however, as evidenced by the case of Tony Bland, who declined into a persistent vegetative state, with functioning respiration, after hypoxia caused by crush asphyxia during the Sheffield Hillsborough football disaster. After several years in this persistent vegetative state, his family obtained the consent of the courts in 1993 to allow nutrition to be withdrawn and natural death to supervene.

It is another matter when brain death spreads below the tentorium. When the brainstem (specifically the midbrain, pons and upper medulla) suffers neuronal damage, the loss of the 'vital centres' that control respiration, and of the ascending reticular activating system that sustains consciousness, cause the victim not only to be irreversibly comatose, but also to be incapable of spontaneous breathing. Without medical intervention, hypoxic cardiac arrest inevitably follows within minutes and then the usual progression of 'cellular death' ensues. This invariably occurred in the past, before the advent of sophisticated devices that allowed the support of respiration after spontaneous function has ceased. Because of continued oxygenation, the heart continues to function, though it has been pointed out by Pallis (1983) that the vast majority of brainstem-dead patients suffer a cardiac arrest within 48–72 hours, even when adequately oxygenated.

This then is the state of 'brainstem death', and almost all doctors and most jurisdictions now accept that, once irreversible damage to the brainstem has been proved, the patient is 'dead' in the somatic sense. They are, however, not yet dead in the cellular sense and it is through this 'physiological window' that the spectacular advances in cadaver donor transplant surgery have been made.

MEDICO-LEGAL ASPECTS OF BRAIN DEATH

In relation to forensic pathology and criminal procedure, these matters have now a largely historical relevance in that several decades ago a number of fatal assaults were defended in court on the basis that the original head injuries led to the victims being placed on life-support machines that were later disconnected when brainstem death was diagnosed. The defence was that the assailant did not 'kill' the victim, because 'death' was caused by the action of the doctors switching off the machine. Several judicial decisions have disposed of this defence, however, as it was accepted, first, that death was diagnosed by the doctors before discontinuing artificial ventilation and, second, that the criminal act that initiated the train of events was not remote enough to avoid culpability for the death.

THE INDICATIONS OF DEATH

Here the signs of somatic death are considered, as those of cellular death are manifested by post-mortem changes, to be discussed in later sections. When cardiorespiratory arrest occurs, brain function ceases within seconds as a result of the collapse of cerebral blood pressure and consequent cortical ischaemia. Within minutes, this loss of brain function becomes irreversible. The actual number of minutes for which total anoxia will cause cortical damage is controversial; it was formerly held that 3 minutes was sufficient, but this time has been extended to 7 or 9 minutes. Even much longer times of total hypoxia, such as immersion under water, has been survived without brain damage. In these cases, an element of hypothermia is usual, which reduces the oxygen needs of the tissues. Thus 20 or even 40 minutes of hypoxia has been claimed as not leading to brain damage. All that can be said is that the period is very variable and that 3–4 minutes of cardiac arrest or failure of respiratory gas exchange carries the risk of cortical damage, even though three or four times this period may sometimes be survived without ill-effects.

- Unconsciousness and loss of all reflexes occurs, and there is no reaction to painful stimuli. Rarely, there may be post-mortem coordinated muscle group activity for up to one hour after death, possibly due to surviving cells in the spinal cord (Nokes *et al.* 1989).
- Muscular flaccidity occurs immediately upon failure of cerebral and cerebellar function. All muscle tone is lost, though the muscles are physically capable of contraction for many hours.



FIGURE 2.1 *The fate of a body after death.*

- Eye signs include loss of the corneal and light reflexes leading to insensitive corneas and fixed, unreactive pupils. Though the iris responds to chemical stimulation for hours after somatic death, the light reflex is lost as soon as the brainstem nuclei suffer ischaemic failure. The pupils usually assume a mid-dilated position, which is the relaxed neutral position of the pupillary muscle, though they may later alter as a result of rigor. There may be a marked difference in the degree of dilatation of each pupil, but this has no significance as a diagnostic sign either of a brain lesion or of drug intoxication. In conditions such as morphine poisoning, where the pupils may be contracted during life, death may allow this to persist or the pupils may dilate to the 'cadaveric position'.

In addition to irregular size, the pupils may lose their circular shape after death as a result of uneven relaxation. This is usually easy to differentiate from the more obvious irregularity caused by ante-mortem abnormality of the iris. The eye globe tension decreases rapidly, as it is dependent upon arterial pressure for its maintenance. The eyeball feels progressively softer within minutes and the cornea soon loses its normal glistening reflectivity because of laxity and failure of lachrymal moistening. Normal tension was measured by Nicati in 1894, who found that it halved at death, fell to as low as an eighth in 30 minutes, and was nil by 2 hours after death. The eyelids usually close, but this is commonly incomplete, the flaccid muscles failing to produce the full occlusion that occurs in voluntary closure. Where the sclera remains exposed, two yellow triangles of desiccated discoloration appear on each side of the cornea within a few hours, becoming brown and then sometimes almost black, giving rise to the name 'tache noire'.

When viewed with an ophthalmoscope, the retina provides one of the earliest positive signs of death. This is the well known 'trucking' of blood in the retinal vessels, when loss of blood pressure allows the blood to break up into segments, similar to trucks in a railway train. This phenomenon occurs all over the body, but only in the retina is it accessible to direct viewing.

The test is not easy to carry out, as the retina of a corpse seems far more difficult to visualize than in a living person. Many observers have described the agonal and early post-mortem appearances of the retina, though some of their accounts are rather contradictory and of little practical value, especially when they attempt to use them to estimate the time since death. Most observers – for example, Kervorkian (1956, 1961) and Salisbury and Melvin (1936) – confirm that the blood flow slows and becomes irregular in density before breaking up into segments. This was apparent within 15 minutes of death as assessed by other means. Kervorkian claimed that colour changes in the retina were closely related to the post-mortem interval. Tomlin believed that segmentation was more indicative of cerebral death than cessation of the circulation, and agreed with others in accepting that 'trucking' was of grave prognostic significance.

One of the best investigations into the phenomenon was by Wroblewski and Ellis (1970), who studied retinal and corneal changes at death in 300 patients. About a third of the total exhibited trucking, most of them within an hour of death. Part of the difficulty in



FIGURE 2.2 *Post-mortem change in the eye, the so-called 'tache noire'. These are brown areas of scleral drying caused by failure of the lids to close after death.*

examining the remainder was that clouding of the cornea occurred in 75 per cent of patients within 2 hours of death. They concluded that segmentation was a purely post-mortem change and any intravascular movement of blood, however irregular, was an indication for continued resuscitation.

- Cessation of the heart beat and respiratory movements was the primary marker of death until the advent of mechanical cardiorespiratory support as it led to immediate ischaemia and anoxia of all other tissues. Determination of cardiac arrest may be made by prolonged auscultation of the chest to exclude heart sounds though, as in life, a feeble heartbeat may be muffled by a thick chest wall. The electrocardiograph is unchallengeable in confirming cardiac arrest.

  Respiration is more difficult to confirm, especially in deep coma such as barbiturate poisoning, and prolonged listening with a stethoscope over the trachea or lung fields is necessary. All archaic procedures such as saucers of water on the chest, feathers before the nostrils and tourniquets around the fingers are only of historical interest.

The mode versus the cause of death

Confusion often arises, especially among students and younger doctors, about the distinction between the **mode** of death and its **cause**. This is particularly important in relation to the documentary certification of deaths, but the same confusion sometimes occurs among pathologists, especially those who are not habitually involved in medico-legal cases.

The mode of death refers to an abnormal physiological state that pertained at the time of death: for example, 'coma', 'congestive cardiac failure', 'cardiac arrest' and 'pulmonary oedema'. These offer no information as to the underlying pathological condition and should not be used as the definitive cause of death unless further qualified by the more fundamental aetiological process.

In most cases, the mode is unhelpful and immaterial in describing and understanding the cause of death, and some modal terms are quite useless, such as 'syncope' or 'cardio-respiratory failure'. Even 'bronchopneumonia' is such a common terminal event in numerous diseases that, used alone, it conveys no information about why the patient died. The British Registrar General has recently requested that it should be omitted from death certificates, the basic condition being preferable and sufficient for statistical purposes.

In addition to the mode and cause of death, here is also the **manner** of death, which is not really a medical decision. Manner refers to the circumstantial events, such as 'homicide, suicide, accident or natural cause' and is a legal or administrative categorization.

The recommendations of the World Health Organization, as given in its publication *The medical certification of death*, should be followed to improve both the comprehension and statistical accuracy of the cause of death. Even this booklet is inconsistent with the practice of certification in many advanced countries, in that it requests the doctor to enter the 'manner' of death (for example, homicide, accident or suicide) which, for example in the UK, is the prerogative of the legal authorities after full investigation (see Leadbeatter and Knight 1987).

POST-MORTEM CHANGES OF FORENSIC IMPORTANCE

To the forensic pathologist a number of post-mortem changes are of interest and potential usefulness, mainly in relation to the estimation of the post-mortem interval, possible interference with the body, and an indication of the cause of death.

HYPOSTASIS

Post-mortem hypostasis is known under a variety of older names, such as 'lucidity', 'staining' or 'cogitation', but the current title is most suitable as it indicates the cause. Hypostasis occurs when the circulation ceases, as arterial propulsion and venous return then fail to keep blood moving through the capillary bed, and the associated small afferent and efferent vessels.

Gravity then acts upon the now stagnant blood and pulls it down to the lowest accessible areas. The red cells are most



FIGURE 2.3 *Blotchy post-mortem hypostasis, forming in the early hours after death. The patchy disposition has no significance and this usually sinks down and becomes confluent in the most dependent areas within a few more hours.*

affected, sedimenting through the lax network, but plasma also drifts downwards to a lesser extent, causing an eventual post-mortem 'dependent oedema', which contributes to the skin blistering that is part of early post-mortem decay.

The arrival of erythrocytes in the lower areas is visible through the skin as a bluish red discoloration, 'hypostasis'. It often begins as blotchy patches on both lateral and dependent surfaces, but also on the upper surfaces of the legs, especially thighs. These soon coalesce and slide down to the lowest areas.

The distribution of hypostasis

The pattern of hypostasis depends on the posture of the body after death. It is most common when the deceased body is lying on its back, with the shoulders, buttocks and calves pressed against the supporting surface. This compresses the vascular channels in those areas, so that hypostasis is prevented from forming there, the skin remaining white. When the body lies for a sufficient time on the side or face, the hypostasis will distribute itself accordingly, again with white pressure areas at the zones of support.

If the body remains vertical after death, as in hanging, hypostasis will be most marked in the feet, legs and to lesser extent in the hands and distal part of the arms. In addition to pallor of the supporting areas, any local pressure can exclude hypostasis and produce a distinct pattern in contrast to the discoloured area. Examples include the irregular linear marks made by folds in rumpled bedlinen, the pattern of fabric from coarse cloth, the pressure of tight belts, brassière straps, pants' elastic and even socks. According to Bonte *et al.* (1986), when electrocution takes place in water (usually a bathtub), the hypostasis is sharply limited to a horizontal line corresponding to the water level.



FIGURE 2.4 *Post-mortem hypostasis in the normal distribution. The pale areas are the result of pressure against a hard supporting surface.*



FIGURE 2.5 *Post-mortem hypostasis in a death from hanging. The discoloration of the skin is in the legs and hands, due to the vertical posture after death.*

The colour of hypostasis

The usual hue is a bluish red, but variation is wide. This depends partly on the state of oxygenation at death, those dying in a congested, hypoxic state having a darker tint as a result of reduced haemoglobin in the skin vessels. This is an unsure indicator of the mode of death, however, and no reliance can be placed on a cyanotic darkening of the hypostasis to indicate a hypoxic death in the sense of 'asphyxia'. Many natural deaths from coronary or other disease have markedly dark hypostasis. Often the colour of the hypostasis varies from area to area on the same body. Sometimes a rim of lighter colour may be seen along the margin of the lower darker area and sometimes there is a definite contrast between a bluish zone and a pink margin. This may appear and change as the post-mortem interval lengthens. Often the whole area of hypostasis is pink or bright red. When death has been due to hypothermia or exposure to cold in the agonal period, such as drowning, the colour may assist in confirming the cause of death; again this is relatively non-specific because bodies exposed to cold after death (especially in mortuary refrigeration) may turn pink after an initial stage of normal bluish-red tint.

The mechanism is not understood, but is obviously a result of oxyhaemoglobin forming at the expense of the darker reduced haemoglobin. This is understandable in hypothermia, where the reduced metabolism of the tissues fails to take up oxygen from the circulating blood, but its frequent formation in the post-mortem period is difficult to explain.

Several researchers have investigated the colour of hypostasis in relation to time since death. Schuller *et al.* (1987) noted an increasing paleness between 3 and 15 hours post-mortem, measuring this as a change in wavelength from 575 nm at 3 hours at an average rate of 2 nm per hour. Vanezis (1991) has used tristimulus colorimetry to study colour changes and secondary shifting of hypostasis, and claimed that there is a linear relationship between the fading colour and time during the first 2 hours after death, following which changes are unpredictable. Inoue *et al.* (1994) have also described measurement of hypostatic colour as a measure of time since death.

It may sometimes be noticed that originally bluish hypostasis becomes pink along the upper part of the horizontal margin, the lower parts remaining dark, so a quantitative change probably occurs, the haemoglobin being more easily re-oxygenated where the erythrocytes are packed less densely in the upper layers of hypostasis.

Other changes in the colour of hypostasis are more useful. The best known is the 'cherry-pink' of carboxyhaemoglobin, which is a unique colour and is often the first indication to the pathologist of carbon monoxide poisoning. Cyanide poisoning is said to have its own characteristic dark blue–pink hue, but it is really an index of the congested, cyanotic, mode of death and, if the pathologist was not already aware of the potential cause from the history – and perhaps the odour of cyanide – it is doubtful whether hypostasis would be a primary indication of the nature of the death. The hypostasis may be a brownish red in methaemoglobinaemia and may be various shades in aniline and chlorate poisoning. In deaths from septic abortions where *Clostridium perfringens* is the infecting agent, a pale bronze mottling may sometimes be seen on the skin, though this is not confined to the areas of hypostasis.

Skin haemorrhages, varying in size from small petechiae to large blotches and even palpable blood blisters may develop in areas of hypostasis. The most common place is the back of the shoulders and neck, though they may appear on the front of the chest, even on a body lying on its back. They are more common in cyanotic, congestive types of death and become more pronounced as the post-mortem interval lengthens. Their importance is in not being mistaken for the so-called signs of 'asphyxia'. They appear in the most gross form when a body dies or is left with the head downwards: the confluent petechiae and ecchymoses may be so marked that they virtually blacken the face and neck.

The timing and permanence of hypostasis

Too much has been claimed in the past for the usefulness of hypostasis as an indicator of the time of death and post-mortem disturbance of the body. The phenomenon appears at a variable time after death – indeed, it may not appear at all, especially in infants, old people or those with anaemia. It may be so faint as almost to escape detection.

Hypostasis can appear within half an hour of death or it may be delayed for many hours. Its variability is such that it is useless for any estimation of the time since death. It is claimed that hypostasis can sometimes be observed in the living if the heart action is failing or if venous return is impaired by the immobility of deep coma. The latter is certainly associated with skin blistering caused by dependent oedema.

Once hypostasis is established, there is controversy about its ability to undergo subsequent gravitational shift. If the body is moved into a different posture, the primary hypostasis may either:

- remain fixed
- move completely to the newly dependent zones or
- be partly fixed and partly relocated.

Thus if a corpse is found with the hypostasis in an obviously inappropriate distribution related to the present posture, it must have been moved after death. This fact may



FIGURE 2.6 *Extensive confluent skin haemorrhages may occur within the dependent hypostasis. They worsen as the post-mortem interval lengthens and must not be taken to indicate so-called 'asphyxia'.*

have important significance in the investigation of criminal deaths, such as the return of the culprit or some other person to the scene. It may also migrate either partly or completely, however, thus negating its diagnostic usefulness. Older theories about 'fixation' of the staining after a certain time are not tenable, as there is no constant interval when this occurs.

Mallach (1964) analysed data including onset, confluence, maximum intensity, displacement and shifting, taken from publications between 1905 and 1963. These are summarized in Table 2.1, 'thumb pressure' meaning displacement by thumb pressure. Table 2.2 shows the variable opinions on hypostasis culled from standard textbooks.

A considerable amount of research has been devoted to the investigation of clotting of post-mortem blood, its subsequent lysis and inhibition of coagulation by fibrinolysins, but this cannot be translated into practice. Formerly, it was held that if a body had remained in its original posture for a certain minimum length of time, the blood would coagulate in the hypostatic areas, so that secondary shifting could not then occur if the body was moved. This is not true in the majority of instances, as there may be partial or complete secondary gravitation at any time – at least, until true staining of the tissues due to haemolysis begins as part of early decomposition, which is not until the second or third day in temperate conditions.

Suzutani *et al.* (1978) examined 430 bodies by pressure on hypostatic areas, finding that the colour could not be squeezed out in 30 per cent where death had occurred 6–12 hours previously. More than 50 per cent were fixed after 12–24 hours and no fading occurred in 70 per cent of those dead for more than 1–3 days. However, in a significant number, hypostasis was still mobile for at least 3 days.

Fechner *et al.* (1984) found no linear relationship between fixation and time of death and also observed variations in fixation according to storage temperatures.

TABLE 2.1 *Hypostasis related to the time of death (hpm) as derived from previous literature*

Stage	Mean	Standard deviation	Limits	
			Lower	Upper
Beginning	0.75	0.5	0.25	3
Confluence	2.50	1.0	1.00	4
Maximum	9.50	4.5	3.00	16
Thumb pressure	5.50	6.0	1.00	20
Complete shifting	3.75	1.0	2.00	6
Incomplete shifting	11.00	4.5	4.00	24

TABLE 2.2 *Time of onset of hypostasis as stated by previous authors*

Reference	Onset	Maximum
Adelson	30 min–4 h	8–12
Polson, Gee, Knight	30 min–2 h	6–12
Spitz and Fisher	2–4 h	8–12
Taylor (ed. Simpson)	0 h	12
Taylor (ed. Mant)	1 h	12
Gradwohl (ed. Camps)	20–30 min	6–12
Glaister, Brash	–	8–12
DiMaio	30 min–2 h	8–12
Sydney Smith	0 h	12
Mant	0 h	12
Gordon and Shapiro	'few' h	12

Hypostasis in other organs

Just as blood settles in dependent skin, so it does in other tissues and organs. The importance in forensic autopsy work is the differentiation of organ hypostasis from ante-mortem lesions. In the intestine, dependent loops of jejunum and ileum may be markedly discoloured and mislead the inexperienced pathologist into suspecting mesenteric infarction or strangulation. This hypostasis is discontinuous, however, revealing interrupted segments when the gut is laid out. Often loops in the pelvis are worst affected, because of their lower position.

The lungs almost always show a marked difference in colour from front to back, the anterior margins being pale and the posterior edges lying in the paravertebral gutters being dark blue. This is often accompanied by an obvious difference in fluid content, congestion and oedema being more marked posteriorly. The myocardium often shows a dark patch in the posterior wall of the left ventricle that must not be mistaken for early infarction.

One of the most important hypostatic artefacts is haemorrhage behind the oesophagus at the level of the larynx. This has many times been confused with the trauma of strangulation, but the true nature was best investigated by Prinsloo and Gordon (1951). Areas of congestion developing into haemorrhage appear in the loose tissues on the back of the oesophagus lying on the anterior longitudinal ligament of the cervical spine. They may be prominent, sufficient to produce actual haematomas. They arise in the veins and venous plexus on the front of the spine, and can be avoided in cases of strangulation and suspected strangulation by draining the neck of blood before starting the dissection. This can be achieved either by removing the brain first or by opening the chest and incising the great veins in the superior mediastinum.

Differentiation between hypostasis and bruising

This is rarely a problem in fresh bodies, but when decomposition begins the two conditions become blurred. In fresh material the appearance of hypostasis is of a regular, diffuse engorgement of the surface vessels, the colour varying between purple–red and bright pink. The density varies from place to place but there are no sudden changes in colour nor any sharply circumscribed areas as occurs in bruising. As mentioned above, in the early stages of hypostasis there may be mottled blue areas, which later coalesce. This mottling is unlikely to be confused with bruising by any but the most inexperienced pathologist. The position in dependent areas is also characteristic, giving a generally horizontal orientation. Bruises may be anywhere on the body, are often discoid or have an irregular margin, but rarely cover a large area with uniform density – and do not have a horizontal margin. Abrasions may be topographically associated with a bruise, but not with hypostasis. When there is difficulty in differentiating between the two – usually where there is racial pigmentation or really deep, cyanotic hypostasis that obscures possible bruises – the classic test is to incise the suspect area to see if the underlying blood is intravascular (hypostasis) or infiltrating the tissues outside the vessels (contusion).



FIGURE 2.7 *White patches within the hypostasis on the face merely indicate pressure against the supporting surface after a face-down position. As in this case, they are usually post-mortem and are not indicators of suffocation.*

Fresh bruises may also be swollen and slightly raised above the surface. If a post-mortem pressure mark (such as from a belt or tight clothing) crosses an area of hypostasis, there will be a pale bloodless zone, but a bruise will not be affected. Hypostasis is in the most superficial layer of the dermis and any exuded blood can be wiped or washed away from the incised surface. A bruise is often deeper in the skin or underlying tissues and is fixed, being infiltrated through the tissues outside the ruptured vessels. An exception is intradermal bruising, but this is usually patterned or linear and rarely can be confused with hypostasis. Histological examination may be necessary finally to decide the matter.

When post-mortem autolysis has developed, the diffusion of haemolysed blood from vessels makes the differentiation between hypostasis and bruising difficult and eventually impossible. Even histological examination may be of little help when the tissues become markedly degenerate.

RIGOR MORTIS

Unlike hypostasis, the stiffening of the muscles after death has some relevance in determining the post-mortem interval. It has been known since antiquity that immediately after death there is general muscular flaccidity, usually followed by a period of partial or total rigidity, which in turn passes off as the signs of decomposition appear. The timing of this sequence of events is so variable, however, that it is a poor indicator of the time since death. The usual range of times when rigor appears can be summarized as follows.

- The flaccid period immediately after death is variable, but commonly extends to between 3 and 6 hours before stiffening is first detected, depending on environmental temperature and other factors. Rigor is first apparent in the smaller muscle groups, not because it begins there, but because the smaller joints, such as the jaw, are more easily immobilized. The sequence of spread of rigor is also variable but tends to affect the jaw, facial muscles and neck before being obvious in the wrists and ankles, then the knees, elbows and hips.

  The usual method of testing is by attempting to flex or extend the joints, though the whole muscle mass itself becomes hard, and finger pressure on the quadriceps or pectorals can also detect the change. The onset of rigor may be markedly accelerated or retarded by the factors mentioned below, so that stiffness may develop within half an hour of death (even excluding cadaveric spasm) or may be postponed almost indefinitely. Some subjects, usually infants, the cachectic and the aged, may never develop recognizable rigor mortis, mainly because of the feebleness of their musculature.
- Rigor spreads to involve the whole muscle mass, again within a variable period but in ‘average’ conditions it might be expected to reach a maximum within 6–12 hours. This state then remains constant until the muscle mass begins to undergo autolysis, which releases rigor gradually at a stage before overt post-mortem changes are visible externally, except perhaps for a commencing discoloration of the lower abdominal wall.

  The duration of full rigor may be 18–36 hours, until it begins to fade in roughly the same order of muscle groups as it appeared. However, there are many exceptions to this rather misleading generalization.

Factors affecting the timing of rigor mortis

As a chemical process, the speed of onset and the duration of rigor is modified by temperature. The colder the environment the slower the process and vice versa. In near freezing conditions rigor will be suspended almost indefinitely. The author (BK) has attended a scene outdoors in winter where the body was quite flaccid one week after death, rigor developing rapidly as soon as the corpse was brought into the comparative warmth of the mortuary. Conversely, hot weather or tropical conditions can speed up the whole cycle so that rigor appears within an hour or even less. Total stiffness develops rapidly, then fades during the first day as decomposition supervenes.

The other modifier of the speed of onset of rigor is physical activity shortly before death. As will be seen when the



FIGURE 2.8 *Full rigor mortis 12 hours post-mortem.*

physicochemical basis of the phenomenon is discussed, the availability of glycogen and adenosine triphosphate in the muscle is a crucial element in rigor formation. Muscular exertion affects the interaction of these substances and hastens the onset of rigor. Cadaveric spasm, dealt with later, may well be an extreme variant of this accelerated rigor.

In view of the wide range of times at which the various stages of rigor appear and fade, it is a poor determinant of the time since death, compared with estimations of body temperature. Niderkorn's early work (1874) on 113 bodies showed a range of 2–13 hours for rigor to be complete, the main cluster being from 3 to 6 hours after death, a shorter period than would be accepted now. Mallach (1964) compiled a table from 150 years of published data, which suffered from gross variation in observer methodology (Table 2.3).

The following is a reasonable 'spot check' for use in average temperate conditions:

- If the body feels **warm** and is **flaccid**, it has been dead less than 3 hours.
- If the body feels **warm** and is **stiff**, it has been dead from 3 to 8 hours.
- If the body feels **cold** and is **stiff**, it has been dead from 8 to 36 hours.
- If the body feels **cold** and is **flaccid**, it has been dead more than 36 hours.

This crude estimate should never be used as a definitive statement in legal proceedings, as it is only meant as a rough guide 'on the spot'.

Rigor mortis in other tissues

Rigor occurs in all muscular tissues and organs, as well as the skeletal muscles. The iris is affected so that ante-mortem constriction or dilatation is modified. The rigor may be unequal in each eye, making the pupils unequal, confirming the fact that the post-mortem position is an unreliable indicator of toxic or neurological conditions during life.

In the heart, rigor causes the ventricles to contract, which may be mistaken by the inexperienced pathologist for left ventricular hypertrophy; this can be excluded by measuring the total weight, estimating the relative size of the left side, measuring the ventricular thickness (admittedly a rough guide) and – where the issue is important – by dissection and differential weighing of the two ventricles.

Rigor in the dartos muscle of the scrotum can compress the testes and epididymis which, together with the contraction of muscular fibres in the seminal vesicles and prostate, may lead to post-mortem extrusion of semen from the urethral meatus. This has been wrongly attributed to sexual activity and orgasm just before death in cases where a defence of provocation against a homosexual advance has been put forward. Mant showed that many corpses dying from a variety of causes have seminal fluid either at the meatus or in the penile urethra (Mant 1953, 1967; Mant and Furbank 1957). It is also said, without much foundation, that deaths from hanging and 'asphyxia' are commonly associated with post-mortem seminal emission.

Rigor in the erector pili muscles attached to the hair follicles can cause a pimpling or 'goose-flesh' appearance with elevation of the cutaneous hairs. This may have given rise to the persistent myth that the beard grows after death, though an additional explanation is that post-mortem desiccation and shrinkage of the skin allows the hair stubble to appear more prominent.

Studies by Krompecher and Bergerioux (1988) have shown that rigor also sets in more quickly in deaths from electrocution – and that it passes off more rapidly.

The biochemistry of rigor mortis

Though this has little direct forensic relevance apart from the association of the early onset of rigor with muscular

TABLE 2.3 *Time course of cadaveric rigidity as stated by previous literature*

		Hours post-mortem				
		Limits of 95.5 per cent probability (2s)		Variations		
Rigor phase	Mean with standard deviation(s)	Lower limit	Upper limit	Lower limit	Upper limit	Number of publications evaluated
Delay period	3 ± 2	–	7	< ½	7	26
Re-establishment possible	Up to 5	–	–	2	8	–
Complete rigidity	8 ± 1	6	10	2	20	28
Persistence	57 ± 14	29	85	24	96	27
Resolution	76 ± 32	12	140	24	192	27

exertion, the muscle chemistry of the phenomenon has been studied in great detail.

Szent-Gyorgi (1947) discovered that the essential contractile substances in muscle were the two proteins actin and myosin, arranged in interdigitating filaments. They form a loose physicochemical combination called 'actomyosin', which is physically shorter than the two substances uncombined (Hanson and Huxley 1955). If energy is supplied to the latter pair, the subsequent combination contracts. This energy is obtained by the splitting off of a phosphate complex from adenosine triphosphate (ATP) which then becomes adenosine diphosphate (ADP) (Erdos 1943). The free phosphate then engages in a phosphorylation reaction that converts glycogen to lactic acid, high energy being released in the process. Some is used to resynthesize the ATP from ADP, by the donation of a phosphate group from creatine phosphate; the remainder goes to activate the actin–myosin reaction.

In addition to supplying energy, ATP is responsible for the elasticity and plasticity of the muscle. The lactic acid is leached away back into the bloodstream and is returned to the liver for reconversion into glycogen. All these reactions are anaerobic and can continue after death, albeit in a distorted form.

In life there is a fairly constant concentration of ATP in the muscular tissues, there being a dynamic balance between utilization and resynthesis. At death, however, the ADP to ATP reaction ceases and the triphosphate is progressively diminished, with lactic acid accumulating. After a variable period, depending on temperature and the amount of ATP remaining, the actin and myosin become rigidly linked into a rigid, inextensible gel, with consequent stiffening of the muscle (see Bate-Smith and Bendall 1947; Forster 1964).

The resynthesis of ATP is dependent upon the supply of glycogen, which is depleted by vigorous activity before death; this explains the rapid onset of rigor in these circumstances. Normally there appears to be an initial period soon after death when the ATP level is maintained or even increased as a result of phosphate liberation by glycogenolysis.

Rigor is initiated when the ATP concentration falls to 85 per cent of normal, and the rigidity of the muscle is at maximum when the level declines to 15 per cent (see Bate-Smith and Bendall 1949).

Gross effects of rigor mortis

There has been some controversy over whether rigor only stiffens the muscles or actually shortens them. Sommer, as long ago as 1833, claimed that muscles contracted after death and the changes were actually known as 'Sommer's movements'. There have always been semi-apocryphal tales of corpses moving in the mortuary and there seems little doubt that, if a limb happens to be poised in unstable equilibrium on the edge of a tray or table, the developing tension may occasionally cause it to spring off as rigor supervenes. The author (BK) has seen athetoid writhing of the foot of a corpse, which lasted for 40 minutes, more than an hour after death.

There seems to be no doubt that some shortening does occur, but the noticeable effects are slight because both flexor and extensor muscle groups oppose each other across most limb joints. Bate-Smith and Bendall (1949) decided that shortening only occurred when there had been marked depletion of glycogen by activity before death, but Forster (1964) was of the opinion that, when a muscle was under some tension, it did shorten. His experiments showed that when the muscle was unloaded there was no change in length when rigor set in. Forster further showed that a high environmental temperature and poisons that increase muscle tone, such as parathion, lead to more shortening during rigor.

When fully established, rigor is 'broken' by forcible movements of the limbs or neck, then it will not return, a phenomenon utilized daily by mortuary staff and undertakers when preparing a body for a coffin. If rigor is still developing, it will continue in the new posture of the limbs after they have been stretched. 'Breaking' fully established rigor is an accurate description, as the rigid, inelastic fibres are physically ruptured – sometimes tearing the muscle insertions from the bone. Rarely, rigor can assist in showing that a body has been moved between death and discovery. If an arm or leg is found projecting into free space without support, in a posture that obviously could not have been maintained during primary post-mortem flaccidity, then it must have been rolled over or otherwise moved. In these cases, a simple restorative movement (after the scene has been fully examined) can usually indicate the original attitude quite simply.

Conversely, it can never be assumed that the posture of rigor in which a body is found was that which obtained at the time of death, as any amount of movement during the period of primary flaccidity will not be mirrored in the subsequent rigor.

Cadaveric spasm

This topic has received a disproportionate amount of notice in textbooks compared with its practical importance. No doubt this is because of its curiosity value rather than its usefulness. Cadaveric spasm is a rare form of virtually instantaneous rigor that develops at the time of death with no period of post-mortem flaccidity.

Krompecher (1994), a major authority on rigor mortis, is extremely sceptical about the existence of true cadaveric



FIGURE 2.9 *Cadaveric spasm, an instantaneous form of rigor, in the victim of a fall into water. The victim was recovered within a short time (as can be seen from the absence of skin maceration) but had grass from the river bank firmly clutched in the hand.*

spasm, but many forensic pathologists claim to have seen such a phenomenon far too soon after death for it to be normal rigor mortis. The authors retain a healthy scepticism about the controversy, believing that most cases are misreported because of errors or uncertainties about the true time of death, so that early normal rigor could have supervened. However, one or two cases within BK's experience seem to be genuine enough to be remarkably early for true rigor.

It seems confined to those deaths that occur in the midst of intense physical and/or emotional activity, though how the latter can lead to instant post-mortem rigor is quite inexplicable. It presumably must be initiated by motor nerve action, but for some reason there is a failure of the normal relaxation. The phenomenon usually affects only one group of muscles, such as the flexors of one arm, rather than the whole body.

It was shown in the earlier section on the biochemistry of rigor that marked depletion of glycogen stores in the muscle by violent exertion immediately before death can hasten the onset of muscular rigidity. Most cases of cadaveric spasm occur in similar circumstances and it was said to be particularly common on the battlefield amongst soldiers slain in combat. In the civilian sphere it is most often seen in persons who fall into water or drop some distance down a precipitous slope such as a cliff. They may clutch at some nearby object, such as grass or shrubs, in an effort to break their fall and such material may be found held tightly in their fingers, even when the body is examined within a few minutes.

Another possibility, more common in detective fiction than in practice, is the gripping of a pistol with the finger still tightly flexed on the trigger, as evidence of true suicide rather than a 'planted' weapon in a homicide where an attempt has been made to simulate self-shooting. The chances of this actually being encountered by a pathologist are less than once in several professional lifetimes.

If found in the victim of drowning, or of a slide from a height, it has some value in confirming that the person was alive at the time of the fall, thus excluding the post-mortem disposal of an already dead body. Of course the body must be examined before ordinary rigor might be expected to have developed, or the presence of cadaveric spasm cannot then be assumed.

HEAT AND COLD STIFFENING

At extremes of temperature the muscles may undergo a false rigor. In extreme cold, well below zero, once the intrinsic body heat is lost, the muscles may harden because the body fluids may freeze solid – as in the commercial or domestic preservation of meat in a freezing cabinet. The temperature has to be below –5°C for cold stiffening to occur and is usually much lower. Part of the apparent stiffness is also due to solidification of the subcutaneous fat. When the body is warmed up, true rigor may supervene, though it may fail to appear as a result of intracellular damage caused by cell membranes being punctured by ice crystals.

Heat applied to the body also causes stiffness of the muscles, as the proteins of the tissues become denatured and coagulated as in cooking. The degree and depth of change depends on the intensity of the heat and the time for which it was applied. At autopsy the muscles may be shrivelled and desiccated, even carbonized on the surface. Beneath this there is a zone (which may be total) of brownish-pink 'cooked meat' and under that, if the process has not penetrated, normal red muscle. Marked shortening occurs, causing the well-known 'pugilistic attitude' of a burned body. This is because of the greater mass of flexor muscles compared with extensors, which forces the limbs into flexion and the spine into opisthotonus. These changes are purely post-mortem and are no indication of burning during life, as similar distortions occur during cremation.

POST-MORTEM DECOMPOSITION

Hypostasis and decomposition occur relatively soon after death when somatic death has occurred, but cellular death is incomplete. As discussed earlier, death is a process not an event and, while the cells of some tissues are still alive and even capable of movement (such as fibroblasts, leucocytes and muscle), others are dying or dead. The process of decomposition begin in some cells while others are still alive, and this overlap continues for several days in temperate climates.

Decomposition is a mixed process ranging from autolysis of individual cells by internal chemical breakdown to tissue autolysis from liberated enzymes, and external processes introduced by bacteria and fungi from the intestine and outer environment. Animal predators, from maggots to mammals, can be included in the range of destruction. Decomposition may differ from body to body, from environment to environment, and even from one part of the same corpse to another. Sometimes one portion of a corpse may show leathery, mummified preservation whilst the rest is in a state of liquefying putrefaction.

In addition, the time scale for decomposition may vary greatly in different circumstances and climates, and even in the same corpse: the head and arms may be skeletalized, whilst the legs and trunk, perhaps protected by clothing or other covering, may be moderately intact. All permutations may be found, making it even more difficult to estimate the probable time since death.

Within the general description of ‘decomposition’ there are several subclasses, which, as just stated, may merge into each other or may be uniform throughout the same cadaver. Most unembalmed bodies undergo putrefaction, in which the tissues become moist and gas-ridden, and eventually liquefy down to the skeleton.

Alternatives are dry decomposition, termed mummification, or a conversion to waxy substances, called adipocere; rarely, tannin occurs by the action of acid, protein-precipitating fluids in the anaerobic conditions of a peat bog. In some stillbirths an aseptic autolysis of a fetus dead *in utero* is known as maceration.

PUTREFACTION

The usual process of corruption of the dead body begins at a variable time after death, but in an average temperate climate may be expected to begin at about 3 days in the unrefrigerated corpse.

Even in temperate zones there can be a wide range of ambient temperatures, from below freezing to near blood heat. In the tropics, far higher temperatures are commonplace, but in high latitudes or elevations, deep-freeze conditions can keep decomposition at bay indefinitely, as in the case of modern discoveries of prehistoric mammoths and medieval Esquimaux. It is therefore futile to attempt to construct a timetable for the stages of decomposition, except to point out salient markers for an undisturbed body in an ‘average’ indoor environment of about 18°C in temperate climates. From this approximate baseline the pathologist must then extrapolate for local variations appropriate to his climatic and geographical conditions.

Sequence of putrefactive changes

Whatever the time scale, the general order of corruption is similar, though the degree of advancement may vary between different areas of even the same corpse.

Usually the first external naked-eye sign is discoloration of the lower abdominal wall, most often in the right iliac fossa where the bacteria-laden caecum lies fairly superficially. Direct spread of organisms from the bowel into the tissues of the abdominal wall breaks down haemoglobin into sulphaemoglobin and other pigmented substances. This discoloration spreads progressively over the abdomen, which in the later phase begins to become distended with gas.



FIGURE 2.10 *Moderately early changes of decomposition, showing gaseous distension of scrotum and abdomen, and skin slippage and blistering in dependent areas. This was after about one week since death, but the changes vary greatly with environmental temperatures.*

At about this time, more generalized spread of bacteria begins to discolour the more moist tissues, which often comprise those dependent areas that show hypostatic coloration and oedema. The face and neck become reddish, and begin to swell. The putrefactive bacteria, which largely originate in the intestines and lungs, spread most easily in fluid so they tend to colonize the venous system, haemolysing the blood that stains the vessel walls and adjacent tissues. This gives rise to 'marbling', a branching outline of arborescent red, then greenish pattern in the skin, seen most clearly on the thighs, sides of the abdomen, and chest and shoulders. This stage may be about one week in the 'baseline' timetable, where the corpse is in air at 18–20°C.

At or even before the stage of marbling, skin blisters may appear, at first on the lower surfaces of trunk and thighs where hypostatic oedema has loaded the tissues with fluid. The upper epidermis becomes loosened, the so-called 'skin-slippage' giving rise to large, fragile sacs of clear, pink or red serous fluid. These may become so large that they are pendulous and soon burst, leaving areas of slimy, pink epidermis. Where this skin change occurs in hairy parts, such as scalp, axilla and pubis, the hair becomes detached and will slide off on slight pressure. Gas formation will now become marked, with increased tension in the abdomen.

The scrotum and penis may swell up to remarkable size and the neck and face will become grotesquely bloated, making visual identification difficult or impossible. The pressure may cause the eye globes and tongue to protrude.

Purging of urine and faeces may occur due to the intra-abdominal pressure and, occasionally, a uterine prolapse may be extruded. There are recorded instances of pregnant women having a macabre post-mortem 'delivery' of the fetus, from the same cause. Bloody fluid, which is tissue liquefaction stained by haemolysis, may leak from any orifice, especially the mouth, nostrils, rectum and vagina. By this stage, some 2–3 weeks may have elapsed since death.

To the inexperienced, this may suggest evidence of some lethal haemorrhage and many pathologists have been called to a scene of 'crime' because of the understandable concern of an investigating police officer that such bloody purging may be evidence of a violent mode of death. Pressure inside the chest due to gas formation in the abdomen may expel air, so that the fluids of decomposition in the trachea and bronchi may be blown into a bloody froth from the mouth and nostrils.

After several weeks, the reddish-green colour of the skin may deepen to a dark green or almost black, but there is marked variation in this aspect. Heavy maggot infestation will almost certainly have supervened except in winter conditions, and the destruction of skin by innumerable maggot holes and sinuses gives better access to other bacteria that may invade from the environment. The maggots secrete a proteolytic enzyme that speeds up the destruction of the tissues, in addition to the direct loss from the voracious appetites of these predators. Skin slippage causes shedding of the outer layers of the fingers and toes, making identification by fingerprints more difficult. Finger- and toenails last longer than the surrounding skin, but they too become loose and eventually fall out. Skin slippage may allow tattoos to become more visible and colourful for a time until the moist underlying dermis itself decomposes.

Internally, decomposition proceeds more slowly than at the surface. It is often quite surprising how valuable an



FIGURE 2.11 *Post-mortem decomposition of about 2 weeks' duration in water in a summer temperature. There is 'marbling' of the skin where breakdown products of haemoglobin have stained the venous channels.*

autopsy on a putrefying corpse can be, as the internal organs may be in far better condition than the exterior would suggest. Organs putrefy at markedly different rates. The lining of the intestine, the adrenal medulla and the pancreas autolyse within hours of death, yet the prostate and uterus may still be recognizable in a partially skeletalized body a year later. The brain soon becomes discoloured, being a soft pinkish-grey within a week and liquefying within a month. Meningeal haemorrhage and haematomata persist well, but apart from some tumours, non-haemorrhagic lesions in the brain substance vanish quite early.

The heart is moderately resistant, and examination of the coronary arteries for the degree of atheromatous stenosis may be well worthwhile for many months, though staining of the vessel walls by haemolysis makes recognition of mural thrombosis difficult. Complete occlusion by firm ante-mortem



FIGURE 2.12 *Post-mortem decomposition showing putrefactive changes in the face, arms and trunk after one week in a warm room. The illustration shows the contrast sometimes seen between one part of the body and another, as the legs are hardly affected. The face, neck and hands are swollen with gas, and the clothing is stained by leaking skin blisters. The tongue is protruding because of gas pressure from the tissues below. Death was due to carbon monoxide poisoning caused by faulty installation of a room heater.*



FIGURE 2.13 *Almost complete destruction of the facial soft tissues by maggots. Post-mortem time about 2 weeks in a centrally heated apartment.*

thrombus persists well. The heart may show a curious white granularity on the epicardial and endocardial surfaces, seen either during putrefaction or even on exhumation after a long interval. The nodules are a millimetre or less in size and are often called 'miliary plaques'. They were investigated by Gonzales *et al.* (1954) who found that microscopically they consisted of calcium and soapy material. The origin is obscure, but they seem to be confined to the heart and to be some degenerative product of the cardiac tissue.

In obese people, the body fat (especially perirenal, omental and mesenteric) may liquefy into a translucent, yellow fluid that fills the body cavities between the organs, and makes autopsy even more difficult and unpleasant.

Later putrefactive changes lead to the breakdown of the thoracic and abdominal walls, often hastened by the perforations of maggots and sometimes larger predators, such as rats and dogs. In some tropical countries, such as India and Sri Lanka, bodies left in the open are attacked by many animals, including monitor lizards, and in other parts of the world the indigenous fauna all contribute to the natural cycle that returns the body fats and proteins to the food chain.

After several months, the softer tissues and viscera progressively disintegrate, leaving the more solid organs, such as uterus, heart and prostate, together with the ligamentous and tendinous tissues attached to the skeleton. Often some areas of skin persist, especially where protected by clothing or under the body against the supporting surface. Much depends upon the environment, as a corpse in the open air will suffer far more from rain, wind and especially animal predators, compared with one in a locked room.

Eventually, the body will be reduced to a skeleton, but for some time, ligaments, cartilage and periosteal tags will survive. The season of year and the location will make a great difference to the time scale of skeletalization: a body dying outdoors in the late autumn will 'survive' longer through the cold winter and spring than one dying in the early summer. The effects of animal predators are profound in terms of removing soft tissues from the bones. In broad terms, a corpse outdoors in a temperate climate is likely to be converted to a skeleton carrying tendon tags within 12–18 months, and to a 'bare-bone' skeleton within 3 years; there are, of course, numerous exceptions, depending mainly on the local environment. In closed conditions indoors, a body may never skeletalize, often being converted to a dried, partly putrefied, partly mummified shell.

Decomposition in immersed bodies

The old rule-of-thumb that bodies decay twice as fast in air as in water is grossly inaccurate, but emphasizes the slower rate of decomposition of immersed corpses. Though in mortuary practice 'drowners' are generally regarded as being the major source of offensively rotten bodies, this is usually because discovery and recovery is far later than in deaths on dry land. Water, in fact, slows up putrefaction, mainly because of the lower ambient temperature, and protection from insect and small mammal predators.

The water also affects the usual processes of decay in that the epidermis becomes macerated and eventually detached, as described in the Chapter 16. Gas formation is the reason



FIGURE 2.14 *Bloating of face and effusion of blood-tinged fluid from the nostrils and mouth. A body recovered from water, post-mortem time approximately 11 days.*



FIGURE 2.15 *Marine predation in a body after 3 months in the North Sea. The victim was from an oil rig and had floated on the surface in a life jacket. Much of the skin has been removed by crustaceans, and the arm muscles by larger fish who have cleaned out most of the body cavity.*



FIGURE 2.16 *Adipocere formation in a body after 3 months in the sea. Subcutaneous fat has been released from crustacean bites on the skin and has been converted into adipocere, which has been rolled by wave action within the clothing to form ovoid masses.*

for the inevitable flotation of an unweighted body, though the time of reappearance at the surface is extremely variable and certainly does not follow the speculative timetable of the older textbooks. The usual posture of a freely floating body is face down, as the head is relatively dense, and does not develop the early gas formation in the abdomen and thorax. This lower position favours fluid gravitation and hence more marked decomposition, so that the face is often badly putrefied in an immersed body, making visual recognition difficult or impossible at an early stage. As stated, temperature is the major determinant of the rate of putrefaction. Though it is usually claimed that the nature of the water in respect of sewage, for instance, is important, it is a minor factor as most of the micro-organisms responsible for decay come from the alimentary canal and respiratory passages of the body itself.

Decomposition in buried bodies

The rate of decay of bodies buried in earth is much slower than of those in either air or water. In fact the process of putrefaction may be arrested to a remarkable degree in certain conditions, allowing exhumations several years later to be of considerable value. In this respect the prospect of an exhumation should never be dismissed on the grounds that because of the lapse of time, it is bound to be worthless. It may turn out to be of little value, but this cannot be anticipated, and not infrequently the condition of the body may be surprisingly good.

The speed and extent of decay in interred corpses depends on a number of factors. If the body is buried soon after death, before the usual process of decay in air begins, putrefaction is less and may never proceed to the liquefying corruption usually inevitable on the surface. A lower temperature, exclusion of animal and insect predators, and lack of oxygen are important factors. Although most bacteria originate in the intestine, there is less access for secondary invaders and the restriction of oxygen inhibits aerobic organisms. If the body is rotting before burial then, although the process slows down, it will still severely damage the corpse, as enzymatic and bacterial growth have had initial encouragement from a higher ambient temperature and free access of air, thereby producing conditions in which secondary



FIGURE 2.17 *Decomposition in a body buried in a shallow grave for 6 months (see Figure 1.2). The soil had collapsed into cavities around the corpse, partly due to the weight of tractors passing over it. This allowed access to flies and discovery by a dog. The body is partly putrefied, but has some adipocere.*

invaders (including anaerobes) can continue their work in a good culture medium that is already partly liquefied by the earlier stages.

Deep burial, as in the usual cemetery interment, preserves the corpse better than the shallow grave seen in some concealed homicides. The deep burial is colder (except in extremely cold weather), it excludes air better and, unless waterlogged, is not directly affected by rain.

The nature of the soil is not directly relevant except in its drainage and aeration properties. Heavy clay will exclude air and, if well above the water table, will exclude percolating surface water. By contrast, light sandy soil may allow access of both air and rainwater, but will drain more effectively. The soil factor is less important than the topography in which it lies – in a valley floor or below the water table, waterlogging is inevitable, but on a well-drained hillside the grave may remain relatively dry.

Another factor that aids the preservation of legitimately buried corpses is the coffin. Though modern coffins are often of wooden laminate or chipboard, which rapidly disintegrates when wet, any kind of coffin helps to exclude water and air for a time. A substantial, sound jointed coffin may last for years and the modern rarity of a sealed metal liner can keep a body in an excellent state of preservation for a long time.

A major factor that helps to slow decomposition is, of course, the absence of animal predation in burials. Again, if a corpse is buried before insect eggs are laid, the profound effect of maggot infestation is avoided. Rodents and larger mammals can only reach shallow burials, and in deep interments the coffin has to be breached before even the limited fauna of that stratum can gain access.

As in all putrefaction, it is unrealistic to try to construct a timetable for the stages of decay in burials. The permutations of factors mentioned above make it impossible, especially where adipocere formation takes place, as described below. The author (BK) has exhumed a chapel cemetery in the waterlogged peat of a Welsh valley and found not a trace of body, even skeleton, in graves with headstones confirming death only 20 years previously. By contrast, other bodies elsewhere were perfectly recognizable – and a standard autopsy could be carried out – one and a half years after death.

When bodies are buried in coffins in vaults, rather than in earth, then again there can be a variable rate of decay. Some bodies may develop adipocere, others may wholly or partly mummify.

There are many publications on this subject, mainly derived from the examination of historical sites or church crypts that have had to be cleared. The subject is of considerable interest but of limited forensic relevance.

FORMATION OF ADIPOCERE

An important and relatively common post-mortem change is the formation of adipocere, a waxy substance derived from the body fat. The name was given to it by Fourcroy in 1789, being derived from 'adipo' and 'cire', to indicate its affinity with both fat and wax. In most instances the change of adipocere is partial and irregular, though occasionally almost the whole body may be affected. In small amounts, adipocere is more common than usually thought in buried or concealed corpses. It is caused by hydrolysis and hydrogenation of adipose tissue, leading to the formation of a greasy or waxy substance if of recent origin. After months or years have passed, adipocere becomes brittle and chalky. The colour can vary from dead white, through pinkish, to a grey or greenish-grey. The substance itself is off-white, but staining with blood or products of decomposition can give it the red or greenish hues. The smell was accurately described by WED Evans (1962, 1963a, b) as being 'earthy, cheesy and ammoniacal'.

The chemistry of adipocere has been studied extensively. It contains palmitic, oleic and stearic fatty acids together with some glycerol, though the latter may have been leached out in older adipocere. These form a matrix for remnants of tissue fibres, nerves and muscles, which give some slight strength to the fats (see Mant and Furbank 1957). Crystals with radial markings can be found in the adipocere. Body fat at the time of death contains only about half of 1 per cent of fatty acids, but in adipocere, this may rise to 20 per cent within a month and more than 70 per cent in 3 months.

The formation of adipocere, as an alternative to total putrefaction, requires certain environmental conditions. A body left exposed in air, unless the conditions are conducive to mummification, will undergo moist putrefaction if the temperature remains above about 5–8°C. In burials, immersion in water, and in incarceration in vaults and crypts, adipocere often forms to a greater or lesser extent.

It is usually taught that moisture is necessary for the process, and it is undoubtedly a fact that most adipocere formation occurs in immersed bodies and those in wet graves and damp vaults. Numerous cases have been described, however, in which dry concealment also led to adipocere formation and here it must be assumed that the original internal body water was sufficient for the hydrolysis to proceed.

It is said that some warmth is necessary for adipocere formation, but the process seems to occur even in deep



FIGURE 2.19 *Conversion of facial and orbital fat into adipocere after several months in water. There is also a penetrating wound on the forehead, obviously ante-mortem from the healing margins. The body was eventually identified by obtaining hospital radiographs of the person suspected of being the victim; these matched post-mortem radiographs in respect of the injury and frontal sinus outlines.*



FIGURE 2.18 *Complete conversion of a body to adipocere. The body was recovered from a deep lake 8 years after disappearing in a boating accident during a heavy storm.*



FIGURE 2.20 *Almost complete conversion of an infant's body to adipocere. The body was exhumed after 3 years' burial and was found to consist of a hollow shell of stiff adipocere with the skeletal elements loose within.*



FIGURE 2.21 *Adipocere formation in body left in dry sewer tunnel for about 2 years. External water is not necessary for adipocere formation, as body fluids may be sufficient hydrolysis of fat.*

graves and in cold water. Early activity by anaerobes such as *Clostridium perfringens* assist in the reaction, as the bacteria produce lecithinase which facilitates hydrolysis and hydrogenation (see Mant 1967). Such bacteria need some warmth in the initial stages to reproduce and metabolize and Mant suggests that rapid cooling soon after death, such as by immersion in water, may actually retard the formation of adipocere.

The frequency with which adipocere forms may be gauged by the observations of those who have exhumed old cemeteries and vaults, as well as the victims of wartime slaughter (see Evans 1963a; Mant 1967; Polson *et al.* 1975; Evans 1963a). The latter found that over half the occupants of dry vaults had some adipocere. It was present in 63 per cent of women and 45 per cent of men.

The importance of adipocere formation

The process is more than a biochemical curiosity as, once it is formed, adipocere may persist for decades or even centuries. The usual dissolution of putrefaction is replaced by a permanent firm cast of the fatty tissues and, although distorted compared to the immediate post-mortem shape, it allows the form of the body and sometimes even of the facial features to be retained in recognizable form. Injuries, especially bullet holes, may be preserved in a remarkable fashion (Mant 1967). Though adipocere mainly affects the subcutaneous fat, it may also preserve the omental, mesenteric and perirenal adipose deposits; in addition, organs containing fat through pathological or degenerative processes may be preserved by adipocere forming in their parenchyma.

The time required for the production of adipocere has been a matter of controversy. The old authors claimed that 3–12 months were required, and Casper (1862) suggested 6 months, but it is obvious that the process can occur much faster than this.

There seems little reason to doubt that hydrolysis of body fat begins soon after death, as crystals of fatty acids have been found in infant bodies lying in water for only a week. This process is usually overtaken by liquefying putrefaction, however, which allows the fat, especially in obese persons, to collect as extracellular pools and pockets of triglycerides in the body cavities.

If the putrefactive process is slowed by burial or immersion, then hydrolysis and hydrogenation can outpace putrefaction. In addition, adipocere formation actually inhibits putrefaction, as the increasing acidity of tissues and the dehydration caused by the consumption of water in hydrolysis slow the growth and spread of the usual putrefactive organisms. The point at which adipocere becomes visible to the naked eye varies greatly, but it has been observed as early as 3 weeks, though 3 months is a more typical period. Adipocere is often mixed with the other forms of decomposition. Even within a coffin or other place of sequestration, there may be several different 'mini-environments'. One end of the body may be putrefied or skeletalized, whilst other parts may be mummified or in adipocere. Certain areas tend to develop adipocere, such as the cheeks, orbits, chest, abdominal wall and buttocks. Only rarely is the face preserved well enough by adipocere to be genuinely recognizable, as disintegration of the eye globes and shrinkage of the tissues around the nose and mouth obscure the most characteristic features.

MUMMIFICATION

The third type of long-term change after death is mummification, a drying of the tissues in place of liquefying putrefaction. Like the other modes of decomposition, this can be partial and can coexist with them in different areas of the same body. It is, however, more likely than the others to extend over the whole corpse.

Mummification can only occur in a dry environment, which is usually, but not exclusively, also a warm place. Mummification can occur in freezing conditions, partly because of the dryness of the air and partly because of the inhibition of bacterial growth. The most widely known forms of mummification are those in hot, desert zones. The process of artificial mummification practised for millennia in Egypt was an imitative process founded on the natural mummification of bodies in predynastic times. The essential requirement for mummification is a dry environment, preferably with a moving air current. If sterility of the tissues can be attained, as in a newborn baby, then putrefaction is held at bay whilst drying occurs. The appearances of mummification display desiccation and brittleness of the skin, which is stretched tightly across anatomical prominences such as the cheekbones, chin, costal margin and hips. The skin is discoloured (usually being brown), though secondary colonization by moulds may add patches of white, green or black.

The skin and underlying tissues are hard, making autopsy dissection difficult. The condition of the internal organs is variable, depending partly on the length of time since death. They may be partly dried, partly putrefied – and adipocere is not uncommon. In fact, slight adipocere formation is common in mummification, and perhaps the two are related in that the utilization of body water to hydrolyse fat in turn helps to dehydrate the tissues. The major factor, however, is evaporation from the surface in dry conditions.

Like adipocere, facial recognition may be possible in some instances, though the shrunken distortion and loss of eyes and full lips considerably alter the features. Mummification is likely to occur in temperate climates when the body is left undisturbed in a dry, warm place. These include closed rooms and cupboards, haylofts, attics and beneath floorboards. Because concealment favours mummification, a number of these bodies are hidden homicides – one of the best known being the 'Rhyl mummy' in North Wales, when a strangled woman was concealed in a cupboard for many years, whilst her pension continued to be claimed. Other instances are where a natural death has been concealed for some purpose. The author (BK) has also seen two deaths in hay barns, where the corpses were undisturbed for over a year.

Most experienced forensic pathologists are familiar with the mummified fetus or newborn infant, concealed in domestic circumstances, such as a house loft, where complete mummification has taken place. With small bodies such as these, evaporation is faster and more complete, and may extend



FIGURE 2.22 *Mummification in a man dead in a locked room for 10 weeks. The corpse is dry and leathery, with very little moist putrefaction.*

to all organs, especially as there would have been no invasion of putrefactive micro-organisms from the gut.

The timing of mummification is not well documented, as most mummified corpses have been concealed so well that discovery does not occur until long after the process has reached its maximum effect. It certainly takes some weeks and the early stages are often mixed with a degree of putrefactive change, especially in the internal organs.

After complete drying has taken place, the body may remain in that state for many years. Eventually, mould formation and physical deterioration progress, the dried tissues becoming split and powdery and gradually disintegrating. This process is usually hastened by animal predation. Even in the shelter of a barn or house, moths, beetles, mice and rats will wreak damage on the corpse. It will eventually skeletalize, though tough, leathery shreds of skin, tendon and ligament may persist for many years. Mummification allows major injuries to be preserved, though as in the putrefied body, the detection of bruises and abrasion may be difficult or impossible to differentiate from discoloration, artefacts and fungal damage. The stiff tissues can be softened for better examination and histology, by soaking in a 15 per cent solution of glycerine for several days (see Evans 1962).

POST-MORTEM DAMAGE BY PREDATORS

Animal predation is part of the natural food chain, which returns the proteins, fats and carbohydrates of dead bodies



FIGURE 2.23 *The mummified body of an absconder from a mental hospital who was found a year later in a hay barn. The dry environment had inhibited wet decomposition.*



FIGURE 2.24 *Extensive mould formation and lack of putrefactive changes in a child who accidentally locked himself in a box and asphyxiated. The body was not found for 6 weeks.*



FIGURE 2.25 *Loss of all soft tissues of head and neck, in areas not covered by clothing, by post-mortem animal predation.*



FIGURE 2.26 *Post-mortem rat bites of the orbit. Such injuries are – not unnaturally – often regarded with suspicion by the police. The complete absence of bleeding or reddening of the wound margins, as well as the unlikely shape and situation of the injury, make its post-mortem origin obvious.*

to other animals, some of it passing back to the vegetable kingdom through soil nutrition. All types and sizes of animal are involved, the largest seen by the author (BK) being a 'near-miss' by a Malayan tiger, who dragged a sleeping soldier from his tent. Most animal damage is more mundane, the beasts varying from ants to foxes, and from bluebottles to monitor lizards. Foxes can drag parts of a body away to a distance of at least 2 miles.

The type of predation varies greatly with geography, season, and whether the dead body is indoors or out in the open. If it is lying in the countryside, large predators will cause prompt and severe damage, even complete destruction being possible in a short time. In temperate countries, foxes and dogs form the main agents, and the body may be dismembered and scattered over a wide area, especially if advancing putrefaction makes disarticulation easy. If corpses are in inland waters, damage from water rats and fish is possible, as well as attacks from dogs and foxes, if the body lies exposed on the bank of a river or a lake.

The type of damage from canine and rodent predators is usually obvious, as the local removal of large amounts of flesh is usually accompanied by evidence of teeth marks. Rats and cats leave a crenated edge to fairly clean-cut wounds, the post-mortem nature of which is obvious from the lack of bleeding or an inflamed marginal zone. Mice rarely attack bodies, but may help to remove the dried, crumbling tissue of a mummified corpse. The most active tissue removers are maggots, the larval stage of bluebottles (*Calliphora*) and flies (*Musca*). The use of the life cycle in timing death is dealt with elsewhere, but here we are concerned with their destructive effects on corpses. In temperate zones their activity is seasonal, but in hot countries their predatory work is ever present. The adult insects lay eggs on the fresh corpse (or even on a debilitated live victim), choosing wounds or moist areas such as the eyelids, lips, nostrils and genitalia. Once skin decomposition begins, the eggs can be deposited anywhere. The eggs hatch in a day or so, and several cycles of maggot develop, shedding their cases at intervals, depending on the species.



FIGURE 2.27 *A body recovered from the Baltic Sea with numerous superficial skin defects on the face and neck due to post-mortem predation, probably by the crustacean Saduria entomon, shown in the inserted picture with a smaller shrimp in the middle.*



FIGURE 2.28 *A post-mortem animal bite that was mistaken for a criminal assault. The old lady was found locked in with a cat, having died from a gastric haemorrhage. The wound has not bled, the margins are not reddened and tooth crenations can be seen round its edge.*

The maggots are voracious and energetic, first exploring the natural passages, such as mouth and nostrils, then burrowing into the tissues. They secrete digestive fluids with proteolytic enzymes that help soften the tissues, burrowing beneath the skin, and making tunnels and sinuses that hasten putrefaction by admitting air and access to external micro-organisms. Successive waves of eggs are laid, producing new generations of maggots. Eventually, loss of tissue and drying make the host cadaver unattractive to egg-laying insects, and the later stages of decomposition become free from maggots.

Beetles and many other types of insect and arthropod join in the destruction, but one particular insect must be mentioned. This is the ant, which can attack the body soon after death before putrefaction begins. A common place for ant attack is around the eyelids, lips and on the knuckles. The lesions are superficial ulcers with scalloped, serpiginous margins. They can be mistaken for ante-mortem abrasions, but their position, margins and lack of bleeding or inflammatory changes usually make them easily recognizable. Shapiro, however, has documented cases where extensive linear ant lesions have resembled ligature abrasions around the neck (Shapiro *et al.* 1988).

Tropical ants can devour tissues to a considerable extent and, although stories of soldier ants reducing horses to skeletons within minutes are apocryphal, predation by large numbers of insects can be extensive.

In water, all manner of aquatic animals can mutilate immersed bodies, as well as land mammals if the corpse is in shallow water or grounded on a mudbank or the beach. Large fish can be totally destructive, especially in tropical waters, but even in temperate seas severe damage can occur. Some of the victims of the Air India aircraft disaster near Ireland in 1985 were ravaged by sharks. Large gouges from the wound edges, punctures from teeth and extensive tissue loss, even with fractures of large bones such as the femur, characterize shark attacks.

Smaller fish can wreak severe damage, the prime example being piranhas, though many species will devour both fresh and decomposing bodies. Crustaceans are also predatory and can remove circular areas of skin to expose the subcutaneous fat, which may detach inside the clothing to form masses of adipocere. Birds also cause damage, usually to the dead, though crows may mutilate live lambs. The habits of carrion birds, such as the vulture, are well known, but smaller birds will inflict injury on exposed bodies, especially when putrefaction softens the tissues.

All animal predation varies in appearance according to the size and shape of the teeth or jaws of the predator, but all such post-mortem injuries have features in common. There is no bleeding apart from the minute quantity actually in the vessels of the damaged part, and certainly no active haemorrhage into the wound margins. Naturally, there is no oedema or reddening of the edges as might be seen in an ante-mortem wound earlier than the perimortal period. Crenation of the edges is a useful guide where small rodents or other animals are involved, though large carnivores can make totally irregular tears in the tissue. Some animals, such as dogs and foxes, may leave punctured wounds adjacent to the damaged edge where sharp teeth have penetrated. On bones, the incisor teeth of rodents and larger carnivores can leave parallel gouges, which must not be mistaken for illicit human activities. In domestic surroundings, pets may inflict drastic post-mortem injuries if they are locked in with a dead person. Dogs and cats can cause injuries that puzzle those, such as the police, who are unaware of the possibility. Complete decapitation by Alsatian dogs has been seen by both of the authors, as well as genital injury.

THE ENTOMOLOGY OF THE DEAD AND POST-MORTEM INTERVAL

This is a highly specialized subject and, when the issue of time since death is important, such as a criminal investigation, it is essential that, wherever possible, the pathologist has the assistance of an entomologist with forensic experience. As in forensic toxicology and serology when serious medico-legal issues are at stake, there is no place in forensic entomology for the 'occasional expert' who dabbles in the subject when the opportunity arises. Having said this, it is helpful to know sufficient about the topic to recognize when expert help is required, and to understand what information and specimens need to be obtained.

The rationale of forensic entomology is that after death invasion of an unprotected body by sarcosaprophagous insects and other small fauna comes in successive waves. Different species of arthropods colonize the corpse at different periods after death. In addition, some species (including the most common blowflies) pass through complex life cycles that can be used to determine at least the minimum time since death by studying the stage of maturation of the insects. The science is inexact and is modified by a number of factors, both climatic and geographical, but in expert hands can sometimes yield useful information about the date of death at a period when other indicators have ceased to function. These methods have been used since the middle of the eighteenth century, but Megnin placed forensic entomology on a sound basis with his publication of *La faune des cadavres* in 1894. There are now a substantial number of publications on the subject, though most of them need specialist zoological knowledge for the interpretation of the species involved and their complicated maturation cycles. It is essential that the entomologist has the fullest possible information about the nature of the environment in which the body was found and, if possible, he should visit the scene himself. It is also vital to have accurate data on the weather, especially the ambient temperature of the area during the period in which the body had been lying there, as the maturation times of insects (especially blowflies) are markedly altered by climatic conditions.

The most common insect found on relatively fresh corpses is the blowfly, a colloquial name for a group of flying insects of the order **Diptera**, with almost worldwide distribution. They mainly comprise the bluebottles, the greenbottles and the housefly. There are numerous species, with variations in life cycles that are altered by climatic conditions. The bluebottle (*Calliphora*) is the most common, especially *Calliphora vicina* Robineau–Desvoidy (*Calliphora erythrocephala* Meigen), the most frequent invader of dead flesh. These are large, bristly flies about 6–14 mm long, with iridescent blue abdomens.

They do not fly in the dark and thus eggs are laid only in daylight. This means that a corpse found at night or in the morning with eggs upon it, almost certainly died the previous day. Bluebottles rarely fly in winter, but may do on fine days, though when the temperature is below 12°C they are unlikely to lay eggs. Rain is also a marked deterrent to egg-laying, except in the case of the **Sarcophagidae**. Bluebottles prefer fresh rather than decayed carrion and lay their eggs soon after death, which may be of medico-legal significance. Indeed, they may lay eggs on the living, especially when the victim (man or animal) is debilitated or wounded. A single bluebottle may lay up to 300–2000 eggs in clusters of

30–150. The eggs are laid on moist areas, such as the eyelids, canthi of the eyes, nostrils, lips, mouth, genitals and anus. If there are any open wounds or weeping abrasions, these may also be colonized. The eggs are yellow and banana-shaped, about l.7 mm in length.

The many tables and diagrams available for the succession of sarcosaprophagous insects on corpses must be read in the knowledge that the environment, especially the temperature, makes a marked difference to the time span of the larval and pupal stages. As Nuorteva *et al.* (1967) state:

> Crimes do not occur under experimental conditions and standardized food supplies. Flies, as medico-legal indicators, must therefore be used in conjunction with the records of meteorological conditions existing at the time subsequent to the presumed crime.

Thus the following examples, mainly taken from Glaister and Brash's (1937) account of the notorious Ruxton murder, must be read with this caution firmly in mind – and wherever possible, the pathologist must enlist the aid of an experienced entomologist.

Adult bluebottles will begin to lay eggs about 4–5 days after emergence from pupation. Eggs will not hatch at temperatures below 4°C, but they will develop at 6–7°C. The time from laying to hatching is 8–14 hours, depending on the temperature.

The first maggot stage (first 'instar') tries to penetrate the tissues or enter any nearby body cavity such as the mouth or wounds. Maggots have powerful proteolytic enzymes that aid dissolution of the tissues and facilitate penetration. The first larval instar persists for another 8–14 hours, then the outer skin is shed and the second larger instar feeds for another 2–3 days.

After a final moult, the third instar spends about 6 days on the body before leaving it to migrate some distance to hide in the ground or under some other cover (even a carpet) to pupate. The pupa is a brown leathery capsule in which the insect metamorphoses into the winged fly after about 12 days. The new bluebottle emerges and leaves the empty pupa case behind, ready to begin the cycle over again, which thus lasts about 18–24 days from egg to adult. The greenbottle (*Lucilla caesar*) and the sheep maggot fly (*Lucilla sericata*) have life histories that are similar to that of the bluebottle.

The common house fly (*Musca domestica*) is different in that, unlike the bluebottles, it prefers to lay its eggs on already decomposed flesh, though it is more attracted to garbage and manure than to cadavers. The eggs are much smaller and white rather than yellow. Hatching time is 8–12 hours, the first instar at about 36 hours, the second instar at 1–2 days and the third at about 3–4 days. Pupation lasts up to 7 days, less in warm weather. The whole cycle is thus about 14 days at about 22°C, though again it must be emphasized that variations in ambient temperature make considerable differences to the speed of maturation. A table by Busvine (1980) shows that the total cycle length varies from 9 days at 40°C to 32 days at 16°C.

Entomologists have constructed tables of variation in larval length according to age and temperature; expert knowledge and strict identification of the species is needed before definite opinions upon minimum times since cadaver death are offered. Some of the times quoted above were taken from the extensive entomological work performed on the Ruxton case in 1935, but do not correspond to the cycle periods published by Kamal in 1958. The total maturation times that he found in experimental conditions at 22°C are much longer, being 14–25 days (average 18) for *Calliphora vicina*.

In many of the published cases where *Calliphora* have assisted in the estimate of the time since death, it is an assessment of the age of larvae that is made from their size. Of course this can only be a minimum estimate, especially if mixed generations are present as a result of successive waves of flies laying eggs at different times. As already said, however, bluebottles do not favour decomposed tissue for oviposition, so egg-laying is likely to cease within a couple of days of death. If pupa cases are seen either on or near the body, then any larvae present may be from later waves – even second- or third-generation insects.

In addition to maggots on the body, other fauna in the soil beneath a corpse leave the area and a reduction in the number of species of normal soil insects may be a marker for the site of a body, even for some time after the latter has been removed. The minimum population of arthropods under a corpse is reached after about 2 months; it then revives, but with quite a different range of insects from the original inhabitants. The absence of eggs or maggots on a body may sometimes be of use, as it may indicate that a body has been in a sheltered place inaccessible to flies, even if it was later moved out. Where a body has been buried, even a shallow covering of soil may protect it from oviposition; where part of the body protrudes, this may well be the focus of maggot infestation.

Different types of insects invade the body after the moist, putrefaction stage that is associated with blowfly maggots has passed. At different seasons, different insects may be prevalent so that the finding of say, **Phoridae** and **Sphaerocerdiae** in Europe would suggest that the body had been there in the summer months. Larder beetles (*Dermestes*) may arrive 3–6 months after death; house moths may attack dried tissues such as mummies and can dispose of keratin such as hair and beard. Beetles (*Coleoptera*) are late arrivals and are usually found in dried or adipocerous corpses. These and many more are related more to season than time, so again the considered opinion of an expert is necessary. The absence of insects in certain climates may indicate that death took place in the winter months when no active colonization was occurring.

Collection of material for entomological study

To the practising forensic pathologist, the main concern in this context is the careful collection and dispatch of specimens to an entomologist with forensic experience.

First, the entomologist needs to know all available facts about the environment in which the body was found – preferably he should visit the locus himself if the matter is of legal importance. He should be told the temperature of the maggot mass and ambient temperature around the time the body was found. If no actual temperature measurements were taken by the pathologist at the scene – and even if they were – local records should be obtained from the nearest meteorological centre. Without this information the probable maturation rate cannot be estimated. The nature of the locus should be described, in terms of vegetation, trees and undergrowth if outdoors. Where maggots are present, some should be placed live in a tube and, if there is delay in transit to the entomology laboratory, a fragment of meat should be included for food. Any adult flies, other insects and eggs should also be collected without preservative.

In addition, some maggots, adults, pupae, empty pupa cases and eggs should be sent after fixation. They can be placed directly into 80 per cent alcohol, but preferably in three parts 80 per cent alcohol with one part glacial acetic acid. Even better is Pimple's fluid, which is six parts 35 per cent formalin, two parts glacial acetic acid, 15 parts 95 per cent alcohol and 30 parts water. Formol saline 10 per cent (as used for histological fixation) should not be used.

If there are different insects on the body, they should be placed in separate tubes – especially if they are alive – as some may devour the others before they reach the laboratory.

Whatever is sent should be labelled or numbered according to a key that records where on the body they were found. If outdoors, the soil beneath the body should be sampled and, where a full cycle has occurred, pupae or cases should be obtained by shallow trenching in radii around the body.

When the body has been recovered from water, any insects or crustaceans should be recovered. Body parasites may occasionally be useful. Fleas and lice can survive total immersion for some hours, but the advice of an entomologist should be sought if parasites are found on an immersed body to determine the minimum survival time of that particular species under the existing circumstances.

DETERMINATION OF TIME SINCE DEATH

ESTIMATION OF THE TIME SINCE DEATH BY BODY COOLING

Though the study of the rate of cooling of the dead human body is essentially an exercise in physiology, its potential use in determining the time since death have made it the most frequent topic for research in forensic medicine.

For more than one and a half centuries, papers have been published devoted to refining the problem further, which has obvious and important connotations in the investigation of criminal deaths. Unfortunately, the vast amount of labour in this direction has not been rewarded by comparable improvements in accuracy because of the permutations of factors that defeat exact calculation of the post-mortem interval. The history of this research is in itself extensive (Knight 1988) but a few cardinal points might be mentioned here to mark the various phases of investigation.

Though the fact that a dead body becomes progressively colder after death has naturally been known since earliest times, scientific measurements were first published in the nineteenth century. Dr John Davey in 1839 recounted experiments with dead soldiers in Malta and Britain, using a mercury thermometer. Though this pioneer made no practical contribution to the problem, some of his comments are remarkably pertinent across a gap of more than 150 years:

> Much judgement, however and nice discrimination may be requisite on the part of the medical man, in appreciating the circumstances likely to modify temperature, so as to enable him when called upon for his opinion (of the time of death), to give one which will be satisfactory to the legal officers – and to himself – on reflection.

These cautionary words are just as applicable nowadays when, unfortunately, some doctors offer a time of death with a confidence often inversely proportional to their experience. In 1863, Taylor and Wilkes wrote a classic paper which introduced many of the current concepts, such as the initial temperature plateau, the core temperature, heat gradient and the effect of insulation. Taylor was, of course, Alfred Swaine Taylor of Guy's Hospital, author of the textbook that remained the definitive work on forensic medicine for almost a century. Later in the nineteenth century, Rainy of Glasgow first applied mathematical concepts to the problem and produced a formula for calculating the time of death. He also pointed out that Newton's Law of Cooling did not apply to the human body. In 1887, Womack first used centigrade units, though his use of the now familiar temperature graphs was anticipated by Burman in 1880.

In this century, the most quoted papers were those by De Saram in Ceylon (De Saram *et al.* 1955; De Saram 1957), who published careful and detailed measurements of control cases obtained from executed prisoners. His data are still being studied and reworked. The names Fiddes and Patten are known to all those interested in this subject as, in 1958, they produced a paper that was a classic, as Taylor's had been in the previous century. Using repeated temperature measurements they devised a percentage cooling method and explored complex theoretical aspects, such as the 'infinite cylinder' model, for the human body.

Marshall and his collaborators dominated the publications in the 1960–1970 period, with papers that explored in depth the mathematical aspects and confirmed the double exponential or 'sigmoid' shape of the rectal cooling curve. In the last decade or so, many more papers and new techniques have been produced, with computer assistance increasingly used. Amongst these, Henssge and Madea in Germany have been predominant. Microwave and infrared thermography have been explored and the physics and mathematics of body cooling probed in such depth that often the scientist in the research group has difficulty in explaining the concepts to his medical collaborator. In spite of all this activity, practical methods of determining the time of death continue to lack accuracy. Though some recent publications offer firm advice and describe methods, they can do no more than provide a 'time bracket' of probability within which death is thought to have occurred.

Post-mortem cooling

Except where the environmental (ambient) temperature remains at or even above 37°C, the human body will cool after death. A uniform, homogeneous laboratory 'body' will cool according to Newton's Law of Cooling, which states that the rate of cooling is proportional to the difference in temperature between the body surface and its surroundings. Graphically represented, this will display the curve of a single exponential expression, not a straight line. A human body does not obey Newton's Law, though the size of the discrepancy varies according to several factors. When death occurs, heat transfer within the body through the circulation ceases. Metabolic heat production, occurring mainly in the muscles and liver, does not cease uniformly and some heat generation continues for a variable time. As soon as the supply of warmed blood ceases with cardiac arrest, the skin surface immediately begins to lose heat. The rate is variable because of clothing, posture and shielding against the supporting surface and, of course, the environmental temperature.

The centre or 'core' of the body cannot begin to cool until a 'temperature gradient' is set up by the cooling at the skin surface. As the tissues are poor heat conductors, this gradient takes a variable time to become established and therefore a thermometer placed near the core (usually in the rectum) will not register a fall for some time. This is the well-known 'plateau', which forms the upper flattened or slightly sloping part of the double exponential curve when



FIGURE 2.29 *Cooling curves: the Newtonian single exponential curve (a) does not occur in practice, except on the surface of the body. Because of the variable plateau (c), the true curve for deep core temperature (b) assumes a double exponential shape.*



FIGURE 2.30 *Diagrammatic representation of some variables in body cooling curves: (a) average body, (b) obese body, (c) heavily clothed body, (d) thin body, (e) naked body, (f) hypothermic body and (g) febrile body.*

rectal temperatures are measured. If skin temperatures are used, as in some of the nineteenth century research, no plateau is found, and, using cranial temperatures taken through the nose, ear or skull, the plateau is less, as the core is nearer the surface.

The central part of the cooling curve approximates to Newtonian principles, being fairly straight or only a shallow curve. As the temperature differential between the body and environment approaches zero, the graph again flattens off into a lower shelf. Unlike the laboratory body, the human body rarely reaches the ambient temperature unless the latter is at or near freezing. This is probably because enzyme and bacterial action starts during early decomposition and, much as a compost heap warms up, the temperature may actually rise a few days after death.

The typical rectal cooling curve then, is a 'sigmoid' shape or 'double exponential' curve. The part that is of use in forensic medicine is the central section showing the steepest fall. Theoretically, if one assumes that the body temperature at the time of death was 37°C, then finding the point on this section corresponding to the measured rectal temperature should allow extrapolation back to the 37°C point which is at zero on the time scale, thus giving the post-mortem interval.

Unfortunately, a number of variables make this attractive proposition impossible to attain in practice. Not only are there variables, but the variables themselves often vary during the period before the body is discovered and examined. For example, the ambient temperature may change markedly – perhaps several times – and often this may not be known to the examiner. Even opening doors and allowing draughts to play on the body will have profound effects on the cooling curve, which cannot be detected or corrected retrospectively.

Factors affecting the cooling curve

INITIAL BODY TEMPERATURE

This cannot be assumed to be 37°C and in fact is incapable of ever being measured in retrospect. Not only is there a difference between the rectal, liver, brain, axillary, mouth and skin temperatures in the living person, but the absolute values vary slightly from person to person and from time to time, even in health.

If the oral temperature is taken to be 37°C, then that in the axilla will be several degrees lower and that in the rectum at least one degree higher. There is a diurnal variation of almost 1°C, the temperature being lowest between 0200 and 0600 and highest between 1600 and 1800. Strenuous exercise raises the temperature by up to 3°C, which persists for up to 30 minutes after returning to rest.

When there is illness or trauma, much wider variations occur, which again are impossible to detect retrospectively. In febrile illness from micro-organisms or parasitic infections, the temperature may be 4 or 5°C higher. In the forensic context, infected wounds or a septic abortion are obvious examples. Cerebral (especially pontine) haemorrhage may also cause hyperthermia, as may some drug reactions. It is traditionally stated in many textbooks that asphyxia and strangulation cause agonal hyperthermia, but there is very little hard evidence for this, apart from anecdotal opinions passed from one author to another. One explanation may be that a homicide victim struggling desperately for life against strangulation will generate muscular heat as in any violent exercise, irrespective of an asphyxial mode of death.

At the other end of the scale, hypothermia is common even in temperate winters. Many victims of criminal assault may be left exposed before death and their temperature may be as much as 10°C lower than normal.

As virtually all methods and formulae for calculating the time of death depend upon the body temperature being 37°C, even a slight variation can introduce a fundamental error.

THE BODY DIMENSIONS

The temperature gradient, which drives cooling, varies with the mass of the body and the surface area as well as with the conducting properties of the tissues. Some more complex calculations correct for mass:surface area ratio by means of nomograms (for example, those served by Henssge), but these can only be an approximation. The height and weight of the body must be known, which is often impossible at the scene of discovery. The amount of subcutaneous and abdominal fat will affect the insulating properties and hence the temperature gradient, but there is no way of assessing or correcting accurately for obesity. Oedema and dehydration both have a marked effect because of the high specific heat of water (see James and Knight 1965). In general, a thin person cools more quickly because of both the mass:surface area ratio and the lack of fatty insulation. Children have a larger surface area for a given body weight.

POSTURE

The loss of heat from the skin that drives the temperature gradient is affected by the access of air to the skin and the opportunity for radiation and convection. A body curled into a fetal position will expose much less surface than one in an extended, spread-eagled posture. Another factor is the amount of skin resting on the supporting surface and the nature of that surface. A body lying full length on its back will lose heat by conduction faster than one resting semi-prone, though radiation and convection may be facilitated.

A body on a metal mortuary tray will cool more quickly than one lying on straw.

CLOTHING AND COVERINGS

All too obvious is the effect of external insulation by clothing or other coverings, even a hat. Radiation is a minor pathway for heat loss because of the low biological temperatures involved, but convection and conduction are markedly reduced by coverings. Even more confusion may be added when coverings actually contribute heat, such as an electric blanket left on after death. A duvet or 'continental quilt' will markedly retard cooling and in fact will accelerate decomposition to a considerable degree. Wet clothing will accelerate cooling, compared with dry coverings, because of the uptake of heat for evaporation.

THE AMBIENT TEMPERATURE

This is, of course, the major factor in cooling and, as was said at the outset, a body will not cool after death if the temperature of the environment is higher than the nominal 37°C, in fact, it may warm up. This may be climatic and seasonal, as in large areas of the world, not necessarily in the tropics. It may also be due to local heating, usually in dwellings or other buildings. This includes radiant heat from fires left burning near the body after death, electric blankets, or death in a house or vehicle fire. Where a victim dies in a warm bath then the whole cooling process is grossly distorted, the opposite of when immersion takes place in the cold water of baths, rivers, lakes or the sea.

AIR MOVEMENT AND HUMIDITY

Most skin cooling takes place by convection and conduction with the adjacent air as the transporting medium. In still conditions, a layer of warm air clings to the skin, especially if clothed or hairy, blocking the temperature differential. Any air movement brings fresh cooler air into contact with the skin and encourages the gradient from the core. The humidity is a less active factor, but damp air conducts heat more readily than dry. A body in a small space will cool more slowly than one exposed to the open air, as transfer of heat to the small volume of air will reduce the temperature differential.

THE MEDIUM AROUND THE BODY

This is usually air, but when it is water or (rarely) another fluid, skin cooling is far more effective. A body immersed in water, especially the moving water of a river or the sea, will rapidly lose heat, as is all too familiar during life when fatal hypothermia can occur within minutes in a cold sea. It is commonly stated that cooling is less rapid in contaminated water (such as sewage) than in clean water, but this is hard to believe, given the same temperature for each type of medium. As mentioned above, death in the warm water of a bathtub reduces the cooling rate – and may even elevate the temperature, making any attempt at estimating the time of death futile.

HAEMORRHAGE

It is traditional to say that severe haemorrhage shortly before death causes more rapid cooling. As the estimation of the time of death is fraught with such inaccuracy, it is difficult to see how this opinion can have been derived. The volume of blood lost will reduce the mass of the body, but only in a minimal fashion. It may be that terminal bleeding may cause a shutdown of cutaneous circulation in an effort to maintain blood pressure and that this might encourage the early formation of the temperature gradient – but such vasoconstriction would relax immediately at death and play no part in post-mortem cooling.

Methods of measuring body temperature

Estimation of temperature by touching with the hand is a useful first manoeuvre when at the scene of a death. A hand placed on the forehead, face or exposed hand may give a first impression of whether death occurred recently or not. Even if these exposed areas are cold, feeling inside the clothing to touch the chest, abdomen or axilla may detect some heat, as may sliding a hand under the body where it is in contact with the supporting surface. These crude methods are combined with an estimate of rigor mortis to provide a preliminary screening of a recent, as opposed to a remote, time of death. Though conditions vary enormously, a body indoors will feel cold on exposed areas in 2–4 hours and in protected areas after some 6–8 hours. The traditional method of taking the post-mortem temperature is by placing a mercury thermometer in the rectum. This must be a chemical thermometer (not a clinical instrument) or thermocouple, ideally reading from 0 to 50°C. The tip must be inserted to at least 10 cm above the anus, the instrument preferably having most of its gradations still visible when *in situ*. It should be left in place for several minutes for the reading to stabilize before being recorded. Where possible, it should be left *in situ* for multiple readings at intervals, though in operational circumstances (especially in criminal deaths) this may be difficult to arrange. There is considerable controversy about when such measurements should be carried out. It is often recommended that a doctor at the scene of death should measure the rectal temperature at once but logistic difficulties exist. Many cases where estimation of the time of death



FIGURE 2.31 *Measuring the rectal temperature at the scene of a murder. This should be done only after forensic procedures such as rectal swabbing have been completed. Normally the temperature should be taken at the mortuary where removal of clothing can be carried out with full photographic and forensic science monitoring. In this case the body was unclothed at the scene and the circumstances did not warrant rectal swabbing.*

is important are criminal or suspicious deaths. These will often be associated with at least the possibility of sexual or homosexual assaults, and it may not be practicable to interfere with clothing in the perineal area or to contaminate the anal and vaginal region before full trace evidence procedures are carried out, usually by police scene of crime officers or forensic scientists, which may include adhesive taping of the clothing and skin, and the retention of underclothes for seminal stains, etc.

To wrestle with tight clothing, perhaps at night, in inclement weather and in confined spaces, and to try to introduce a thermometer into the rectum in these circumstances might ruin vital evidence of more importance than the admittedly uncertain calculations about time of death. However, many pathologists and police teams do carry out this manoeuvre as a routine, but each pathologist must decide in every individual case, whether it is preferable to wait until the body is taken to the mortuary where proper, controlled undressing is possible.

This applies where pathology and criminalistic expertise is readily available, but it is acknowledged that in less ideal circumstances, when no such expertise is likely to appear within a few hours (if at all), then some doctor at the scene should take a temperature. The procedure must be tailored to the individual circumstances but where there is a possibility of sexual interference, the rectum (and vagina) should be avoided until after full swabbing for semen and other examinations are completed. Alternatives are to use the axilla, deep nasal passage or external ear for the insertion of a thermometer.

The technique of introducing a mercury or ‘rototherm’ thermometer through a stab wound in the abdomen to measure liver temperature is never justified. It inevitably leads to blood contamination of the skin and clothing and also leads to intraperitoneal bleeding that might be confused with existing internal injuries.

More modern measuring devices include thermocouples, which register temperature accurately with minimum stabilization time. They may be part of a compact electronic instrument, which has a digital readout, or they may be connected to a computerized recorder that can analyse several other sites at regular intervals (see Morgan *et al.* 1988). Microwave thermography of brain and liver (see Al-Alousi *et al.* 1986, 1994) and infrared monitoring of skin temperature are at present research tools that may lead to practical devices in the future.

The use of thermometry in estimating the post-mortem interval

In spite of the great volume of research and publications already mentioned, accuracy in estimating the time since death from temperature remains elusive. The old rule-of-thumb was that the temperature fell at about 1.5°F/hour, something under 1°C/hour. Another rule-of-thumb was that the fall in °C from 37°C, plus three (to arbitrarily allow for the plateau), was equal to the time since death in hours. For example, if a rectal temperature was found to be 32°C, then 37 − 32 + 3 gave a post-mortem interval of 8 hours. The only confidence that one could place in these methods was that they were almost always wrong and that, if the answer happened to be correct, it was by chance rather than science! To hope for a linear fall was against all the principles of heat loss alluded to earlier. The first method took no account of the ‘plateau’ when rectal temperatures were used. This upper part of the double exponential curve is of variable length. If the body has been dead for some hours, serial temperature recordings fail to identify it, as the measurements begin on the steeper part of the curve, but where thermometry is begun soon after death, there is a variable flat area at the top of the sigmoid graph.

The length of the plateau has been discussed by several authors (see Shapiro 1965; Nokes *et al.*1985). Shapiro in particular has drawn attention to the invalidation of many formulae by the unknown length of the plateau. He claims that this can be as much as 4 hours ‘and is possibly considerably longer’. Marshall and Hoare (1962) admit that the plateau may be as long as 5 hours. The plateau is the result of the lag in conducting heat from the core to the skin that is caused by the insulating properties of human tissue. This delays the establishment of the temperature gradient that must be in operation along the radius of the 'infinite cylinder', which is the model for the human body, before the core can begin to lose heat to the exterior. There may also be a small element of continuing heat production in the liver and musculature, as a number of investigators (including the first) noted that the body temperature could actually rise soon after death. As the length of the plateau is unknown in any particular case when there is a delay in starting measurements, most methods begin within this inbuilt inaccuracy.

At the lower end of the sigmoid curve, measurements again become almost useless, as when the temperature is within about 4°C of the environment, the rate of cooling becomes so slow that it provides no separation in time (see Fiddes and Patten 1958). Another empirical rule-of-thumb was devised by James and Knight (1965) to include variation in ambient temperature. The fall from 37°C was multiplied by a factor of 1, 1.25, 1.5, 1.75 or 2 for ambient temperatures of 0, 5, 10, 15 or 20°C, respectively, to give the time since death in hours. As another linear method, this was doomed to inaccuracy and was found to provide too short a post-mortem interval, though the authors emphasized that it was meant to be modified in each case by an appreciation of all other factors such as physique and clothing.

Nomogram method

At present one of the most useful practical guides is the nomogram published by Henssge. Based on conventional calculations such as those of De Saram and Marshall and backed up by a great volume of experimental data, Henssge has produced a method which can be carried out either by a simple computer program or by a nomogram. Adjustments are built in for body weight, ambient temperature, dry or wet clothing, still or moving air, or still or flowing water. The result is given within different ranges of error, with a 95 per cent probability of the true time of death falling within these ranges, which vary from 2.8 hours each side at the best estimate, down to 7 hours at worst. As with most methods, the difficulties arise in estimating the strength of the variable factors. It also cannot allow for variation of these factors over time, especially changes in ambient temperatures during the period before the body was examined. Henssge and Madea have recently refined their method to reduce the standard deviation of their nomograms so that the confidence range becomes smaller, by a whole battery of methods not dependent on temperature, such as electrical stimulation of muscle and the reaction of the eye pupils to drugs.

Another graphical method is that developed by Al-Alousi (1987) in Glasgow. In addition to his publications on microwave thermography, Al-Alousi has published a simple method based on rectal temperatures. He has constructed cooling curves for both naked and covered bodies, using the concept of 'temperature ratios'. The accompanying cooling curves may be used from a knowledge of the rectal temperature, ambient temperature and whether or not the body surface was covered. Again no correction is made for body size, posture or other variables, but the author claims that such factors made little difference to the standard errors, which he gives as shaded errors on each side of his graphs.

Multiple-site serial measurement methods

In an effort to reduce or eliminate the effect of the external variables when calculating the post-mortem interval, Morgan *et al.* (1988) have developed models using multiple sites in the body for temperature estimations. These are then taken serially at frequent intervals over a period using highly sensitive thermocouples and computerized data acquisition, and calculation, which is miniaturized sufficiently for use at scenes of crime.

The method also attempted to use the deep ear canal and nasal passages for temperature measurements, which avoids the problems of perineal contamination that occur when the rectum is used at scenes of death. The results were not encouraging, but recently French workers have revived the ear method, with claims of relative success. These methods have not been in routine use for sufficiently long to evaluate their operational accuracy.

STOMACH EMPTYING AS A MEASURE OF TIME SINCE A DEATH

With one exception, this controversial topic could be dismissed summarily as being quite irrelevant. For many years pathologists have argued over the reliability of the state of digestion of gastric contents as an indicator of the time between the last meal and death, the leading case in modern times being that of Truscott in Canada. There is now almost a consensus that with extremely circumscribed exceptions, the method is too uncertain to have much validity.

The original hypothesis was founded on the belief that food spent a fairly uniform time in the stomach before being released into the duodenum. In addition, it was claimed that its physical state was progressively altered by gastric juices and movements so that its appearance and volume was a measure of the time since it had been swallowed. Therefore, if the time of the last meal was known from circumstantial evidence, the time of death could be estimated.



FIGURE 2.32 *Henssge's nomogram method for estimating the time since death from a single rectal temperature, where the environmental temperature is below 23°C. (From Henssge* et al. *2002.)*

The nomogram expresses the death time (t) by: $\dfrac{T_{\text{rectum}} - T_{\text{ambient}}}{37.2 - T_{\text{ambient}}} = 1.25 \exp(Bt) - 0.25 \exp(5Bt)$; $B = -1.2815 \, (\text{kg}^{-0.625}) + 0.0284$

The nomogram is related to the chosen standard, that is, naked body extended lying in still air. Cooling conditions differing from the chosen standard may be proportionally adjusted by corrective factors of the real body weight, giving the corrected body weight by which the death time is to be read off. Factors above 1.0 may correct thermal isolation conditions and factors below 1.0 may correct conditions accelerating the heat loss of a body.

How to read off the time of death

1. Connect the points of the scales by a straight line according to the rectal and ambient temperature. It crosses the diagonal of the nomogram at a special point.
2. Draw a second straight line going through the centre of the circle, below left of the nomogram and the intersection of the first line and the diagonal.

The second line crosses the semicircles, which represent the body weights. At the intersection of the semicircle of the body weight the time of death can be read off. The second line touches a segment of the outermost semicircle. Here can be seen the permissible variation of 95 per cent.

Example: temperature of the rectum 26.4°C; ambient temperature 12°C; body weight 90 kg. Result: time of death 16 ± 1.8 h. Statement: the death occurred within 13.2 and 18.8 (13 and 19) hours before the time of measurement (with a reliability of 95 per cent).

Note: if the values of the ambient temperature and/or the body weight (see 'corrective factors') are called into question, repeat the procedure with other values that might be possible. The range of death time can be seen in this way.

Empiric corrective factors of the body weight

Dry clothing/ covering	In air	Corrective factor	Wet through Clothing/covering wet body surface	In air/water
		0.35	Naked	Flowing water
		0.50	Naked	Still water
		0.70	Naked	Moving air
		0.70	1–2 thin layers clothing	Moving air
Naked	Moving	0.75		
1–2 thin layers clothing	Moving	0.90	2 or more thicker clothing	Moving air
Naked	Still	1.00		
1–2 thin layers clothing	Still	1.10	2 thicker layers clothing	Still air
2–3 thin layers clothing		1.20	More than 2 thicker layers clothing	Still air
1–2 thicker layers clothing	Moving or still	1.20		
3–4 thin layers clothing		1.30		
More thin/thicker layers clothing	Without influence	1.40		
		1.80		
Thick bedspread + clothing combined		2.40		

Note: for the selection of the corrective factor of any case, only the clothing or covering of the lower trunk is relevant.
Personal experience is needed; nevertheless, this is quickly achieved by consistent use of the method.

Requirements for use

- No strong radiation (for example, sun, heater, cooling system).
- No strong fever or general hypothermia.
- No uncertain[*] severe changes of the cooling conditions during the period between the time of death and examination (for example, the place of death must be the same as where the body was found).
- No high thermal conductivity of the surface beneath the body.[†]

[*] Known changes can be taken into account: a change of the ambient temperature can often be evaluation (for example, contact the weather station); use the mean ambient temperature of the period in question. Changes by the operations of the investigators (for example, take any cover off) since finding the body are negligible: take the conditions before into account!

[†] Measure the temperature of the surface beneath the body also. If there is a significant difference between the temperature of the air and the surface temperature, use the mean.



Figure 2.33 *Henssge's nomogram method for estimating the time since death from a single rectal temperature, where the environmental temperature is above 23°C. (From Henssge* et al. *2002.)*

The nomogram expresses the death time (t) by: $\frac{T_{\text{rectum}} - T_{\text{ambient}}}{37.2 - T_{\text{ambient}}} = 1.11 \exp(Bt) - 0.11 \exp(10Bt);\ B = -1.2815\ (\text{kg}^{-0.625}) + 0.0284$

The difference between this nomogram and that for ambient temperatures up to 23°C concerns only the relative length of the 'post-mortem plateau'. It is shorter in higher ambient temperatures (above 23°C) than in lower ones (that nomogram: up to 23°C). This nomogram for higher ambient temperatures was developed according to the data from De Saram, which were obtained in ambient temperatures between 27 and 32°C. These data show a relatively shorter length of the 'post-mortal plateau' than our own data of body cooling in lower ambient temperatures. Our own practical experience of the cooling of bodies in high ambient temperatures and therefore in using this nomogram, is small. It is recommended that the same permissible variation of 95 per cent as given in the nomogram for lower ambient temperatures is taken.



FIGURE 2.34 *Cooling curves for estimation of the post-mortem interval. In Al-Alousi's 'temperature ratio' method, the graphs above are used as follows. Assume that the body temperature (rectal) is 36.6°C at the time of death (T_b). Measure the environmental and rectal temperatures at the time of examination (T_r and T_e). Then the 'temperature ratio' is $T_r - T_e/T_b - T_e$. This ratio is then found on the vertical scale of the rectal graph, using either the graph for 'naked' or 'covered' as appropriate. The time since death is the point on the lower scale where a perpendicular falls from the point on the graph where a horizontal line meets it from the temperature ratio level. The shaded area indicates the limits of a 68 per cent probability at that particular point. For example, if the rectal temperature is 23.4°C and the air temperature 19°C, then the temperature ratio is 0.25. If the body is naked, then this gives 18 hours as the time since death, with a margin of plus 2.5 hours and minus 5 hours. (Reprinted with permission from Al-Alousi LM, Anderson RA. 1986. Microwave thermography in forensic medicine.* Police Surgeon, ***30****:30–42.)*

It was assumed that the physiological process of digestion of an 'average' meal lasted some 2–3 hours. This is based on the consumption of a test meal of gruel, however, hardly a representative example of a modern mixed diet. Moreover, the subjects of experimental work were healthy and presumably free from sudden stress during the experiments. More elaborate descriptions of digestion times of various foods have been drawn up, but they are of dubious value. As an example of the great variations offered, Modi (1957) gives 4–6 hours for a meat and vegetable meal and 6–7 hours for a farinaceous meal. Adelson (1974) stated that the stomach begins to empty within 10 minutes of swallowing, that a 'light' meal leaves the stomach by 2 hours, a 'medium' meal takes 3–4 hours and a large, heavy meal takes 4–6 hours. He noted that the head of an 'ordinary' meal usually reached the ileocaecal valve between 6 and 8 hours after ingestion. All these values, however, are subject to considerable variation.

More modern methods of investigation have used radioisotope techniques and have shown some interesting facts. When a solid meal is eaten and water drunk with it, the water leaves the stomach quickly irrespective of the nature or calorific content of the solid part. However, calorific liquids stay longer in the stomach (Brophy *et al.* 1986). The emptying rate also increases with the weight of the meal, as long as the calorific content remains constant. If the latter is increased, then the pyloric opening is delayed. Further work by Moore *et al.* (1984) again emphasized the marked variability of emptying times, even in normal circumstances.

The following factors frustrate the use of gastric emptying as a measure of time since death:

- Digestion may continue for some time after death.
- The physical nature of a meal has a profound effect on emptying time: the more fluid the consistency, the faster the emptying. Liquids entering an empty stomach pass through without any appreciable pause.
- The nature of the food modifies emptying time, notably fatty substances, which markedly delay the opening of the pylorus. Strong alcohol, such as spirits and liqueurs, also irritate the mucosa and tend to delay emptying.
- Importantly, any nervous or systemic shock or stress, mediated through the parasympathetic (vagus) system, can slow or stop gastric motility and digestive juice secretion as well as holding the pylorus firmly closed.

The intestine, as opposed to the stomach, may increase its motility with psychogenic upsets, as noted by De Saram in his autopsies on hanged criminals.

The state of digestion, as opposed to the volume and exit of food from the stomach, is almost impossible to assess. Variations in the type of food eaten make vast differences to the dissolution rate. Hard objects, such as nuts and seeds, resist digestion and may even be voided intact *per rectum*, whereas soft carbohydrates can liquefy almost immediately. The size and dispersion of particles is crucial, including the amount of chewing and admixed saliva. The efficiency of the teeth and gastric acid, enzymes and motility are also of prime importance, as is the amount of liquid either in the original food or drunk during the meal. Fat and oil in the meal slow up pyloric opening, and all these variables make it impossible to time the rate of digestion.

One of the most important factors in the forensic context is the effect of a physical or mental shock or stress during the digestion process. As stated, this can completely inhibit digestion, gastric motility and pyloric opening. The author (BK) recalls a victim of a traffic accident who lived in a coma for a week after a mortal head injury. At eventual autopsy, the large volume of gastric contents looked as fresh as if it had just been swallowed.

Even if one accepts an 'average' gastric transit time of an 'average' meal as being of the order of 2–3 hours, the assumption that death took place within this time can only be valid if the death was quite sudden and unexpected, with no stressful prodromal event. For example, if an unsuspecting person was suddenly shot or run down without warning and died almost immediately, then one can assume that the undisturbed physiological processes of digestion – albeit with its many variables – had taken place. If, however, a domestic dispute or a developing altercation culminated in a strangling or stabbing, the antecedent stresses would almost certainly affect gastric function and render invalid any interpretation of the condition of stomach contents at autopsy.

What is valid is the nature of the last meal, which may be helpful in establishing the time of death. If it was known to the investigators that the deceased person ate a certain type of meal at a certain time, whether it be chicken curry or green beans, the identification of such food in the stomach would be persuasive evidence that he died after taking that food and that it was his final meal, before any other substantial food of a different type was taken.

THE USE OF VITREOUS HUMOUR CHEMISTRY IN TIMING DEATH



FIGURE 2.35 *Obtaining vitreous humour for analysis. The lids should be retracted and the needle introduced near the outer canthus, so that the hole will be covered when the lids are released. Fluid should be withdrawn slowly, keeping the tip of the needle in the centre of the globe to avoid dislodging the retina. Water can be reintroduced through the needle to restore the tension in the globe for cosmetic reasons.*

This topic has been the subject of considerable research in forensic medicine over the last 30 years. It has never gained sufficient acceptance to become a routine tool, remaining a controversial procedure in spite of the large number of reports that now exists.

The most common chemical estimation performed on the vitreous fluid in the context of the post-mortem interval is that of potassium. There is a marked and progressive rise in the potassium concentration after death, the controversy revolving around whether this rise is simply linear or whether it is biphasic. The degree of confidence is also in dispute and the effect of variable factors is another contentious matter (see works by Coe, Sturner, Lange and Madea). First, the potassium values from either eye often differ, sometimes by a considerable amount. The sampling methods are then critical, as small or marginal samples vary greatly; if aspiration is forcible or from too near the retina, cellular fragments distort the values, because the potassium reaches the vitreous by leaching out from the retina. The effect of temperature changes post-mortem is also undoubtedly important. In addition, different analytical techniques used to estimate the potassium give different results, the older flame photometric methods producing a different range of values compared with modern selective-electrode procedures.

With all these variables, it is little wonder that different authors suggest widely different standard errors, varying from 1–7 hours to 26 hours either side of the true time of death. In addition, the errors seem much greater in persons dying of chronic illnesses, with nitrogen retention, compared with sudden deaths, presumably because of the premortal electrolyte disturbances in patients with metabolic disorders.

The rise in infants seems much faster than in adults – yet another variable – though in both adults and children the most potent influencing factor seems to be the postmortem body temperature. The most popular calculation for estimating the time since death from vitreous potassium is that devised by Sturner, in which post-mortem interval $=7.14 \times$ potassium concentration (mEq/l) -39.1. This seems most satisfactory when the body has lain in an ambient temperature of not more than 10°C (50°F). The 95 per cent confidence limit during the first day is likely to be at least 4.7 hours either side of the true time and probably greater. Taking a sample from one eye at a later time than the first to attempt to calculate the rate of rise does not seem to add any accuracy to a single estimation method (see Adjutantis and Coutselenis 1972).

Hypoxanthine estimation in vitreous humour has also been used to attempt to time death, but more often as a marker of hypoxia. The results are not convincing, but there is an accumulating literature on the subject, more recent contributions being Madea *et al.* (1994) and also Rognum *et al.* (1991).

POST-MORTEM CHEMISTRY

The analysis of physiological chemical constituents of the body, as opposed to toxic substances, is often useful in investigating deaths from metabolic and biochemical disturbances.

Unfortunately, the concentration of many natural chemical substances in the dead body is rapidly distorted by post-mortem autolysis. Cell membranes become permeable to small molecules soon after the cells suffer ischaemic or anoxic damage, and agonal changes themselves may grossly alter the biochemical environment, even in the few minutes of the dying process. Thus both terminal and early post-mortem changes may render many of the analyses that are commonplace in clinical practice of little value – and indeed, quite misleading – when applied to body fluids obtained at autopsy. Some substances are more stable, however, and when results are carefully interpreted, considerable information can be obtained. Urea and creatinine are stable post-mortem, with little variation even up to 100 hours after death, so the diagnosis of ante-mortem nitrogen retention is quite reliable. The normal urea nitrogen range found in post-mortem serum is from 4.9 to 5.5 mmol/l, creatine being from about 70.7 to 212.2 μmol/l.

In the context of post-mortem chemistry the work of John Coe is best known in forensic pathology and his writings should be consulted for detailed information. Another very useful source is Madea, especially for vitreous fluid. The vitreous humour is much to be preferred to blood for post-mortem chemical analyses. Although still influenced by temperature changes, the vitreous is far less contaminated by body autolysis and is remote from the large organs and blood vessels of the abdominothoracic cavity.

There is a large body of literature on vitreous potassium, much of it centred around the controversy over the *in vivo* concentration of potassium, which can naturally rarely be measured directly in healthy persons, and the slope of the regression graph for relating potassium levels with post-mortem interval.

After death, intracellular potassium leaches from the retina through the now permeable cell membranes, into the vitreous body, naturally with an uneven distribution depending on the distance from the wall of eyeball (which is why all or a substantial proportion of the fluid should be withdrawn for analysis, to obtain a mean level). If fragments of retina are aspirated by the syringe, due to excessive suction, then a falsely elevated potassium measurement will be obtained.

Differences in the recommended regression gradient are observed between various workers: Madea states that 0.19 mmol/l/hour should be used, whereas Sturner claims 0.14 is preferable. The literature should be consulted for details (as in the 2002 book by Hennsge *et al.*); it is also pertinent to note that the methods of analysis can make a difference to the calculations. Generally speaking, the vitreous potassium method is of most use after the first 24–36 hours, when other methods have ceased to have application. Although the errors are great, some information can be derived for up to 100 hours post-mortem.

Caution must be used when interpreting results, as different analytical techniques provide different values. For instance, in relation to electrolytes, Coe and Apple (1985) state that flame photometric methods yield values about 5 mmol/l less for sodium, 7 mmol/l less for potassium and 10 mmol/l less for chloride, compared with more modern specific electrode methods. Electrolyte concentration differences between left and right vitreous humor samples were studied by Pounder *et al.* (1998) in 200 medico-legal autopsies using an ion-specific electrode system. Between-eye concentration differences of sodium and chloride were tolerable using this methodology, whereas differences in potassium, even in biochemically nonputrefied cases (potassium <15 mmol/l), were 0–2.34 mmol/l (0–21.8 per cent of mean) averaging 0.37 mmol/l (3.3 per cent), thus undermining the usefulness of vitreous potassium in estimation of time of death.

In relation to other vitreous electrolytes, the concentration of sodium and chlorides decrease after death, while potassium rises. The latter can be used as a check on the reliability of the others, as if potassium is <15 mmol/l, then the sodium and chloride concentrations may be acceptable. Chlorides decrease at less than 1 mmol/l/h and sodium by about 0.9 mmol/l/h, so the loss of this and sodium is insignificant in the first few hours, differing from potassium, which rises appreciably.

With the analysis of glucose in autopsy material, five different methods yielded five different results, presumably because interfering substances were included in varying amounts.

Returning to vitreous electrolytes, in mmol/l measured by flame photometry (in mmol/l), sodium >155, chloride > 135 and urea >40 is a reliable indication of ante-mortem dehydration. When sodium and chloride are normal but the urea exceeds 150, a diagnosis of uraemia is acceptable. These values can be distinguished from post-mortem decomposition, in which sodium is <130, chloride <105 and potassium >20.

In relation to glucose, a common problem is the autopsy diagnosis of uncontrolled diabetes and of hypoglycaemia. The vitreous glucose usually falls after death and can reach zero within a few hours. In 6000 analyses, Coe (1973) found that a vitreous glucose of more than 11.1 mmol/l was an invariable indicator of diabetes mellitus. The agonal or post-mortem rise in blood sugar is not reflected in the vitreous concentrations. In relation to hypoglycaemia, a vitreous glucose of less than 1.4 mmol/l was taken by Sturner *et al.* (1972) to be an indication of a low ante-mortem blood sugar, but others feel that whatever the concentration, no reliable interpretation can be made. In hypothermia there is also an elevated vitreous glucose, but never greater than 11.1 mmol/l.

REFERENCES AND FURTHER READING

Adelson L. 1974. *The pathology of homicide*. Thomas, Springfield.

Adelson L, Sunshine I, Rushforth NB, *et al.* 1963. Vitreous potassium concentration as an indicator of the post mortem interval. *J Forensic Sci* **8**:503–10.

Adjutantis G, Coutselinis A. 1972. Estimation of the time of death by potassium levels in the vitreous humour. *Forensic Sci* **1**:55–60.

Al-Alousi LM. 1987. *The post-mortem interval: a study of the postmortem cooling rate*. University of Glasgow, Glasgow.

Al-Alousi LM. 2002. A study of the shape of the post-mortem cooling curve in 117 forensic cases. *Forensic Sci Int* **125**:237–44.

Al-Alousi LM, Anderson RA. 1986. Microwave thermography in forensic medicine. *Police Surgeon* **30**:30–42.

Al-Alousi LM, Anderson RA, Land DV. 1994. A non-invasive method for postmortem temperature measurements using a microwave probe. *Forensic Sci Int* **64**:35–46.

Al-Alousi LM, Anderson RA, Worster DM, *et al.* 2002. Factors influencing the precision of estimating the postmortem interval using the triple-exponential formulae (TEF). Part I. A study of the effect of body variables and covering of the torso on the postmortem brain, liver and rectal cooling rates in 117 forensic cases. *Forensic Sci Int* **125**:223–30.

Ambrosi I, Carriero F. 1965. Hypostasis in the internal organs: histological aspects. *J Forensic Med* **12**:8–13.

Anonymous. 1963. Case of John David Potter (editorial). *J Forensic Med* **31**:195.

Balasooriya BA, St. Hill CA, Williams AR. 1984. The biochemistry of vitreous humour. A comparative study of the potassium, sodium and urate concentrations in the eyes at identical time intervals after death. *Forensic Sci Int* **26**:85–91.

Bate-Smith E, Bendall J. 1947. Rigor mortis and adenosine triphosphate. *J Physiol* **106**:177.

Bate-Smith E, Bendall J. 1949. Factors determining the time course of rigor mortis. *J Physiol* **110**:47.

Bendall J. 1960. *Post mortem changes in muscle*, vol. 3. Academic Press, London.

Benecke M. 1997. [Collecting insects, spiders and crustaceans for criminal forensic study.] *Arch Kriminol* **199**:167–76.

Betz P, Lignitz E, Eisenmenger W. 1995. The time-dependent appearance of black eyes. *Int J Legal Med* **108**:96–9.

Bohnert M, Weinmann W, Pollak S. 1999. Spectrophotometric evaluation of postmortem lividity. *Forensic Sci Int* **99**:149–58.

Bonte W, Sprung R, Huckenbeck W. 1986. [Problems in the evaluation of electrocution fatalities in the bathtub.] *Z Rechtsmed* **97**:7–19.

Borrman H, Du Chesne A, Brinkmann B. 1994. Medico-legal aspects of postmortem pink teeth. *Int J Legal Med* **106**:225–31.

Bray M. 1984. The effect of chilling, freezing, and rewarming on the postmortem chemistry of vitreous humor. *J Forensic Sci* **29**:404–11.

Brophy CM, Moore JG, Christian PE, *et al.* 1986. Variability of gastric emptying measurements in man employing standardized radiolabeled meals. *Dig Dis Sci* **31**:799–806.

Brown A, Marshall TK. 1974. Body temperature as a means of estimating the time of death. *Forensic Sci Int* **4**:125–33.

Brown A, Hicks B, Knight B, *et al.* 1985. Determination of time since death using the double exponential cooling model. *Med Sci Law* **25**:223–7.

Burton JF. 1974. Fallacies in the signs of death. *J Forensic Sci* **19**:529–34.

Busvine JR. 1980. *Insects and hygiene*, 3rd edn. Chapman & Hall, London.

Campobasso CP, Introna F. 2001. The forensic entomologist in the context of the forensic pathologist's role. *Forensic Sci Int* **120**:132–9.

Campobasso CP, Di Vella G, Introna F. 2001. Factors affecting decomposition and Diptera colonization. *Forensic Sci Int* **120**:18–27.

Camps FE. 1959. Establisment of time since death – a critical assessment. *J Forensic Sci* **4**:73–6.

Casper JL. 1862. *Handbook of forensic medicine*, 3rd edn. Engl transl. G W Balfour. New Sydenham Society, London.

Catts E, Goff M. 1992. Forensic entomology in criminal investigations. *Annu Rev Entomol* **37**:253–8.

Chowduri S, Chatterji PC, Banerjee SP. 1970. Histological study of liver tissue with regard to determining time of death. *J Indian Acad Forensic Sci* **9**:19–23.

Coe JI. 1969. Postmortem chemistries on human vitreous humor. *Am J Clin Pathol* **51**:741–50.

Coe JI. 1973. Further thoughts and observations on postmortem chemistry. *Forensic Sci Gaz* **5**:26.

Coe JI. 1974. Postmortem chemistry: practical considerations and a review of the literature. *J Forensic Sci* **19**:13–32.

Coe JI. 1974. Postmortem chemistries on blood with particular reference to urea nitrogen, electrolytes, and bilirubin. *J Forensic Sci* **19**:33–42.

Coe JI. 1977. Postmortem chemistry of blood, cerebrospinal fluid, and vitreous humor. *Leg Med Annu* **1976**:55–92.

Coe JI. 1989. Vitreous potassium as a measure of the postmortem interval: an historical review and critical evaluation. *Forensic Sci Int* **42**:201–13.

Coe JI. 1989. Postmortem chemistry of blood and vitreous humour in pediatric practice. In: Mason J (ed.), *Paediatric forensic medicine and pathology*. Chapman and Hall, London, pp. 191–203.

Coe JI. 1993. Postmortem chemistry update. Emphasis on forensic application. *Am J Forensic Med Pathol* **14**:91–117.

Coe JI, Apple FS. 1985. Variations in vitreous humor chemical values as a result of instrumentation. *J Forensic Sci* **30**:828–35.

Conference of Medical Royal Colleges and their Faculties in the United Kingdom. 1976. Diagnosis of brain death. *Br Med J* **2**:1187–8.

Contostavlos DL. 2001. Commentary on: Ely SF, Hirsch CS. Asphyxial deaths and petechiae. *J Forensic Sci* 2000; **45**(6):1274–7. *J Forensic Sci* **46**:1261.

De Letter EA, Piette MH. 1998. Can routinely combined analysis of glucose and lactate in vitreous humour be useful in current forensic practice? *Am J Forensic Med Pathol* **19**:335–42.

Department of Health and Social Security. 1983. *Code of practice on cadaveric organs for transplantation*. Her Majesty's Stationery Office, London.

Dervegie A. 1840. *Medicine-legale*. Baillière, Paris.

De Saram GS. 1957. Estimation of the time of death by medical criteria. *J Forensic Med* **4**:47–57.

De Saram GS, Webster G, Kathirgamatamby N. 1955. Postmortem temperature and the time of death. *J Crim Law Criminol Police Sci* **1**:562–77.

Devgun MS, Dunbar JA. 1986. Biochemical investigation of vitreus: applications in forensic medicine, especially in relation to alcohol. *Forensic Sci Int* **31**:27–34.

Eastham RD. 1971. *Biochemical values in clinical medicine*, 4th edn. John Wright, Bristol.

Easton AM, Smith KG. 1970. The entomology of the cadaver. *Med Sci Law* **10**:208–15.

Eliakis F. 1965. Determination of the hour of death by estimation of inorganic phosphorus content of the cerebro-spinal fluid. *Ann Med Leg* **45**:366–71.

Ely SF, Hirsch CS. 2000. Asphyxial deaths and petechiae: a review. *J Forensic Sci* **45**:1274–7.

Enticknap JB. 1960. Biochemical changes in cadaver sera in fatal acute heart attacks. *J Forensic Med* **7**:135–42.

Erdos T. 1943. Rigor, contracture and ATP. *Stud Ins Med Chem Univ Szeged* **3**:51–6.

Erzinclioglu YZ. 1983. The application of entomology to forensic medicine. *Med Sci Law* **23**:57–63.

Erzinclioglu YZ. 1989. Entomology, zoology and forensic science: the need for expansion. [editorial] *Forensic Sci Int* **43**:209–13.

Erzinclioglu YZ. 1989. Protocol for collecting entomological evidence. *Forensic Sci Int* **43**:211–13.

Evans WED. 1962. Some histological findings in spontaneously preserved bodies. *Med Sci Law* **2**:155–60.

Evans WED. 1963a. Adipocere formation in a relatively dry environment. *Med Sci Law* **3**:145–8.

Evans WED. 1963b. *The chemistry of death*. Thomas, Springfield.

Farmer JG, Benomran F, Watson AA, *et al.* 1985. Magnesium, potassium, sodium and calcium in post-mortem vitreous humour from humans. *Forensic Sci Int* **27**:1–13.

Fatteh A. 1966. *Estimation of time of death by chemical changes*. Commonwealth of Virginia, Office of Chief Medical Examiner, Virginia, pp. 163.

Fechner G, Koops E, Henssge C. 1984. [Cessation of livor in defined pressure conditions.] *Z Rechtsmed* **93**:283–7.

Fekete JF, Kerenyi NA. 1965. Postmortem blood sugar and blood urea nitrogen determinations. *Can Med Assoc Journal* **92**:970–74.

Fiddes F, Patten TA. 1958. Percentage method for representing the fall in body temperature after death. *J Forensic Med* **5**:2–15.

Findlay AB. 1976. Bone marrow changes in the post mortem interval. *J Forensic Sci Soc* **16**:213–18.

Fisher P. 1946. *Mechanism of death in the absence of postmortem evidence of disease or trauma. (seminar presentation)*, Department of Legal Medicine, University of Harvard, 22 October, 1946.

Foerch JS, Forman DT, Vye MV. 1979. Measurement of potassium in vitreous humor as an indicator of the postmortem interval. *Am J Clin Pathol* **72**:651–2.

Forman DT, Butts J. 1980. Electrolytes of the vitreous humor as a measure of the postmortem interval. *Clin Chem* **26**:1042–6.

Forster B. 1963. The plastic and elastic deformation of skeletal muscle in rigor mortis. *J Forensic Med* **10**:91–110.

Forster B. 1963. The contractile deformation of skeletal muscle in rigor mortis. *J Forensic Med* **10**:133–47.

Forster B. 1964. The plastic, elastic and contractile deformation of the heart muscle in rigor mortis. *J Forensic Med* **11**:148.

Gallois Montbrun FG, Barres DR, Durigon M. 1988. Postmortem interval estimation by biochemical determination in bird muscle. *Forensic Sci Int* **37**:189–92.

Gamero Lucas JJ, Romero JL, Ramos HM, *et al.* 1992. Precision of estimating time of death by vitreous potassium – comparison of various equations [see comments]. *Forensic Sci Int* **56**:137–45.

Gantner GE, Sturner W, Caffrey PR, *et al.* 1962. Ascorbic acid levels in the postmortem vitreous humor. *J Forensic Med* **9**:156–61.

Garrett G, Green MA, Murray LA. 1988. Technical method – rapid softening of adipocerous bodies. *Med Sci Law* **28**:98–9.

Glaister J, Brash J. 1937. *Medicolegal aspects of the Ruxton case*. Livingstone, Edinburgh.

Goff ML, Odom CB. 1987. Forensic entomology in the Hawaiian islands. Three case studies. *Am J Forensic Med Pathol* **8**:45–50.

Goff ML, Omori AI, Gunatilake K. 1988. Estimation of postmortem interval by arthropod succession. Three case studies from the Hawaiian Islands. *Am J Forensic Med Pathol* **9**:220–5.

Gonzales TA, Helpern M, Vance M. 1954. *Legal medicine and toxicology*, 2nd edn, vol. 64. Appleton Century Crofts, New York.

Gotouda H, Takatori T, Terazawa K, *et al.* 1988. The mechanism of experimental adipocere formation: hydration and dehydrogenation in microbial synthesis of hydroxy and oxo fatty acids. *Forensic Sci Int* **37**:249–57.

Grassberger M, Reiter C. 2002. Effect of temperature on development of the forensically important holarctic blow fly *Protophormia terraenovae* (Robineau-Desvoidy) (Diptera: Calliphoridae). *Forensic Sci Int* **128**:177–82.

Green MA, Wright JC. 1985. Postmortem interval estimation from body temperature data only. *Forensic Sci Int* **28**:35–46.

Green MA, Wright JC. 1985. The theoretical aspects of the time dependent Z equation as a means of postmortem interval estimation using body temperature data only. *Forensic Sci Int* **28**:53–62.

Haglund WD, Sperry K. 1993. The use of hydrogen peroxide to visualize tattoos obscured by decomposition and mummification. *J Forensic Sci* **38**:147–50.

Hanson J, Huxley H. 1955. The structural basis of contraction in striated muscle. *Symp Soc Exp Biol* **9**:228–64.

Hansson L, Uotila U, Lindfors R, *et al.* 1966. Potassium content of the vitreous body as an aid in determining the time of death. *J Forensic Sci* **11**:390–4.

Hellerich U, Bohnert M, Pollak S. 2001. [Hypostasis-induced changes in the breast area.] *Arch Kriminol* **207**:162–9.

Henry JB, Smith FA. 1980. Estimation of the postmortem interval by chemical means. *Am J Forensic Med Pathol* **1**:341–7.

Henssge C. 1988. Death time estimation in case work. I. The rectal temperature time of death nomogram. *Forensic Sci Int* **38**:209–36.

Henssge C, Madea B, Gallenkemper E. 1985. [Determination of the time of death – integration of various partial methods.] *Z Rechtsmed* **95**:185–96.

Henssge C, Madea B, Gallenkemper E. 1988. Death time estimation in case work. II. Integration of different methods. *Forensic Sci Int* **39**:77–87.

Henssge C, Knight B, Krompecher T, *et al.* 1995. *The estimation of the time since death in the early postmortem period*. Edward Arnold, London.

Henssge C, Althaus L, Bolt J, *et al.* 2000. Experiences with a compound method for estimating the time since death. II. Integration of non-temperature-based methods. *Int J Legal Med* **113**:320–31.

Henssge C, Knight B, Krompecher T, *et al.* 2002. *The estimation of the time since death in the early postmortem period*, 2nd edn. Arnold, London.

Henssge C, Wang H, Hoppe B. 2002. Light microscopical investigations on structural changes of skeletal muscle as artifacts after postmortem stimulation. *Forensic Sci Int* **125**:163–71.

Hill EV. 1941. Significance of dextrose and nondextrose reducing substances in postmortem blood. *Arch Pathol* **32**:452–6.

Hiraiwa K, Ohno Y, Kuroda F, *et al.* 1980. Estimation of postmortem interval from rectal temperature by use of computer. *Med Sci Law* **20**:115–25.

Hughes WM. 1965. Levels of potassium in the vitreous humour after death. *Med Sci Law* **5**:150–6.

Inoue M, Suyama A, Matuoka T, *et al.* 1994. Development of an instrument to measure postmortem lividity and its preliminary application to estimate the time since death. *Forensic Sci Int* **65**:185–93.

Introna F, Jr, Campobasso CP, Di Fazio A. 1998. Three case studies in forensic entomology from southern Italy. *J Forensic Sci* **43**:210–14.

Jaafar S, Nokes L. 1994. Examination of the eye as a means to determine the early postmortem period: a review of the literature. *Forensic Sci Int* **64**:185–9.

Jaffe F. 1962. Chemical postmortem changes in the intraocular fluid. *J Forensic Sci* **7**:231.

James RA, Hoadley PA, Sampson BG. 1997. Determination of postmortem interval by sampling vitreous humour. *Am J Forensic Med Pathol* **18**:158–62.

James WR, Knight B. 1965. Errors in estimating the time of death. *Med Sci Law* **5**:111–16.

Jit I, Sehgal S, Sahni D. 2001. An indian mummy: a case report. *Forensic Sci Int* **117**:57–63.

Johnston W, Villeneuve G. 1897. On the medicolegal applications of entomology. *Montreal Med* **26**:81–8.

Joseph AE, Schickele E. 1970. A general method for assessing factors controlling postmortem cooling. *J Forensic Sci* **15**:364–91.

Kamal AS. 1958. Comparative study of thirteen species of sacrosaprophagous Calliphoridae Sarcophagidae (Diptera). 1 Bionomics. *Ann Entomol Soc Am* **51**:261–71.

Kevorkian J. 1956. The fundus oculi and the determination of death. *Am J Pathol* **32**:1253–67.

Kevorkian J. 1961. *The eye in death*. Ciba Symposia, London.

Kevorkian J. 1961. The fundus oculi as a postmortem clock. *J Forensic Sci* **6**:261.

Knight B. 1968. Estimation of the time since death: a survey of practical methods. *J Forensic Sci Soc* **8**:91–6.

Knight B. 1979. The putrefied body. *Br Med J* **1**:1300–1.

Knight B. 1988. The evolution of methods for estimating the time of death from body temperature. *Forensic Sci Int* **36**:47–55.

Kominato Y, Harada S, Yamazaki K, *et al.* 1988. Estimation of postmortem interval based on the third component of complement (C3) cleavage. *J Forensic Sci* **33**:404–9.

Komura S, Oshiro S. 1977. Potassium levels in the aqueous and vitreous humor after death. *Tohoku J Exp Med* **122**:65–8.

Krompecher T. 1994. Experimental evaluation of rigor mortis. VIII. Estimation of time since death by repeated measurements of the intensity of rigor mortis on rats. *Forensic Sci Int* **68**:149–59.

Krompecher T, Bergerioux C. 1988. Experimental evaluation of rigor mortis. VII. Effect of ante- and post-mortem electrocution on the evolution of rigor mortis. *Forensic Sci Int* **38**:27–35.

Kuehn LA, Tikuisis P, Livingstone S, *et al.* 1979. Body cooling after death. *J Can Soc Forensic Sci* **12**:153–63.

Kuehn LA, Tikuisis P, Livingstone S, *et al.* 1980. Body cooling after death. *Aviat Space Environ Med* **51**:965–9.

Kulshrestha P, Chandra H. 1987. Time since death. An entomological study on corpses. *Am J Forensic Med Pathol* **8**:233–8.

Kulshrestha P, Satpathy DK. 2001. Use of beetles in forensic entomology. *Forensic Sci Int* **120**:15–7.

Lange N, Swearer S, Sturner WQ. 1994. Human postmortem interval estimation from vitreous potassium: an analysis of original data from six different studies. *Forensic Sci Int* **66**:159–74.

Langford AM, Pounder DJ. 1997. Possible markers for postmortem drug redistribution. *J Forensic Sci* **42**:88–92.

Langley RL. 1994. Fatal animal attacks in North Carolina over an 18-year period. *Am J Forensic Med Pathol* **15**:160–7.

Lasczkowski G, Riepert T, Rittner C. 1993. [Viewing the criminal site in unusual cadaver evidence: concealment, identification, determining time of death and reconstruction.] *Arch Kriminol* **192**:1–11.

Leadbeatter S, Knight B. 1987. The history and the cause of death. *Med Sci Law* **27**:132–5.

Leahy MS, Farber ER. 1967. Postmortem chemistry of human vitreous humor. *J Forensic Sci* **12**:214–22.

Leclercq M, Tinant-Dubois J. 1973. Entomologie et medicine legale. [Entomology and forensic medicine: dating of a death.] *Bull Med Legal Tox* **16**:251–5.

Lie JT. 1967. Changes of potassium concentration in the vitreous humor after death. *Am J Med Sci* **254**:136–43.

Lord WD, Burger JF. 1983. Collection and preservation of forensically important entomological materials. *J Forensic Sci* **28**:94–144.

Lorenzen GA, Lawson RL. 1971. A possible new approach for determining the postmortem interval by sperm motility. *J Crim Law Criminol* **62**:560–3.

Lothe F. 1964. The use of larval infestation in detemining time of death. *Med Sci Law* **4**:113–16.

Lucy D, Aykroyd R, Pollard M. 2001. Commentary on: Munoz JI, Suarez-Penaranda JM, Otero XL, Rodriguez-Calvo MS, Costas E, Miguens X, Concheiro L. A new perspective in the estimation of postmortem interval (PMI) based on vitreous. *J Forensic Sci* **46**:1527–8.

Lundquist F. 1956. Physical and chemical methods for estimating the time since death. *Acta Med Leg Soc* **9**:205–13.

Lyle H, Cleveland F. 1956. Determination of time since death by heat loss. *J Forensic Sci* **1**:11–24.

Madea B, Henssge C. 1990. Electrical excitability of skeletal muscle postmortem in casework. *Forensic Sci Int* **47**:207–27.

Madea B, Henssge C, Honig W, *et al.* 1989. References for determining the time of death by potassium in vitreous humor. *Forensic Sci Int* **40**:231–43.

Madea B, Herrmann N, Henssge C. 1990. Precision of estimating the time since death by vitreous potassium – comparison of two different equations. *Forensic Sci Int* **46**:277–84.

Madea B, Kaferstein H, Hermann N, *et al.* 1994. Hypoxanthine in vitreous humor and cerebrospinal fluid – a marker of postmortem interval and prolonged (vital) hypoxia? Remarks also on hypoxanthine in SIDS. *Forensic Sci Int* **65**:19–31.

Madea B, Kreuser C, Banaschak S. 2001. Postmortem biochemical examination of synovial fluid – a preliminary study. *Forensic Sci Int* **118**:29–35.

Mallach HJ. 1964. Zur Frage der Todeszeitbestimmung. [Definition of the time of death.] *Berlin Med* **18**:577–82.

Mant AK. 1953. Factors influencing changes after burial. In: Simpson K (ed.), *Modern trends in forensic medicine*. Butterworth, London.

Mant AK. 1967. Adipocere. In: Simpson K (ed.), *Modern trends in forensic medicine*, 2nd edn. Butterworth, London.

Mant AK, Furbank R. 1957. Adipocere – a review. *J Forensic Med* **4**:18–22.

Marshall TK. 1960. *The cooling of the body after death*. University of Leeds, Leeds.

Marshall TK. 1962. Estimating the time of death. *J Forensic Sci* **7**:210–21.

Marshall TK. 1965. Temperature methods of estimating the time of death. *Med Sci Law* **5**:224–32.

Marshall TK. 1969. The use of body temperature in estimating the time of death and its limitations. *Med Sci Law* **9**:178–82.

Marshall TK, Hoare F. 1962. Estimating the time of death – the rectal cooling after death and its mathematical representation. *J Forensic Sci* **7**:56–81.

Mason J, Klyne W, Lennox B. 1951. Potassium levels in the CSF after death. *J Clin Pathol* **4**:231.

Maxeiner H, Winklhofer A. 1999. [Eyelid petechiae and conjunctival hemorrhage after cardiopulmonary resuscitation] *Arch Kriminol* **204**:42–51.

Megnin P. 1894. *La faune des cadavres*. Gauthier-Villars, Paris.

Modi JP. 1957. *Medical jurisprudence and toxicology*. Tripathi, Bombay, India.

Mole RH. 1948. Fibrinolysin and the fluidity of blood postmortem. *J Pathol Bacteriol* **60**:413–19.

Moore JG, Christian PE, Brown JA, *et al.* 1984. Influence of meal weight and caloric content on gastric emptying of meals in man. *Dig Dis Sci* **29**:513–19.

Morgan C, Nokes LD, Williams JH, *et al.* 1988. Estimation of the post mortem period by multiple-site temperature measurements and the use of a new algorithm. *Forensic Sci Int* **39**:89–95.

Morovic-Buda KA. 1965. Experiences in the process of putrefaction in corpses buried in earth. *Med Sci Law* **5**:403.

Munoz JI, Suarez-Penaranda JM, Otero XL, *et al.* 2001. A new perspective in the estimation of postmortem interval (PMI) based on vitreous. *J Forensic Sci* **46**:209–14.

Munoz-Barus JI, Suarez-Penaranda J, Otero XL, *et al.* 2002. Improved estimation of postmortem interval based on differential behaviour of vitreous potassium and hypoxantine in death by hanging. *Forensic Sci Int* **125**:67–74.

Myskowiak JB, Doums C. 2002. Effects of refrigeration on the biometry and development of *Protophormia terraenovae* (Robineau-Desvoidy) (Diptera: Calliphoridae) and its consequences in estimating post-mortem interval in forensic investigations. *Forensic Sci Int* **125**:254–61.

Nanikawa R, Tawa N, Saito K. 1961. Chemical studies on adipocere formation: revaluation of the saponification theory. *Jap J Legal Med* **15**:258–64.

Nauman HN. 1959. Postmortem chemistry of the vitreous body in man. *Arch Ophthalmol* **62**:356–63.

Nicati S. 1894. Loss of eye tension as a sign of death. *Med Rec* **45**:4801.

Niderkorn PF. 1874. Rigor mortis. *Br Med J* **1**:303–4.

Nokes LD, Brown A, Knight B. 1983. A self-contained method for determining time since death from temperature measurements. *Med Sci Law* **23**:166–70.

Nokes LD, Hicks B, Knight BH. 1985. The post-mortem temperature plateau – fact or fiction? *Med Sci Law* **25**:263–4.

Nokes LD, Hicks B, Knight B. 1986. The use of trachea temperature as a means of determining the post-mortem period. *Med Sci Law* **26**:199–202.

Nokes LD, Barasi S, Knight BH. 1989. Case report: co-ordinated motor movement of a lower limb after death. *Med Sci Law* **29**:265.

Nuorteva P. 1974. Age determination of a blood stain in a decaying shirt by entomological means. *Forensic Sci* **3**:89–94.

Nuorteva P. 1977. *Sarcosaprophagous insects as forensic indicators*. In: Tedeschi CG, Eckert WG (eds), *Forensic medicine*. W. B. Saunders, Philadelphia, vol. II.

Nuorteva P, Isokoski M, Laiho K. 1967. Forensic entomology. *Ann Entomol Fenn* **33**:217–20.

Ohya I. 1994. [Some findings of the lung in medicolegal autopsy cases.] *Nippon Hoigaku Zasshi* **48**:379–94.

Osuna E, Garcia-Villora A, Perez-Carceles MD, *et al.* 1999. Vitreous humor fructosamine concentrations in the autopsy diagnosis of diabetes mellitus. *Int J Legal Med* **112**:275–9.

Osuna E, Garcia-Villora A, Perez-Carceles M, *et al.* 2001. Glucose and lactate in vitreous humor compared with the determination of fructosamine for the postmortem diagnosis of diabetes mellitus. *Am J Forensic Med Pathol* **22**:244–9.

Pallis C. 1983. *ABC of brain death*. British Medical Association, London.

Polson CJ, Marshall TK. 1975. *The disposal of the dead*, 3rd edn. English Universities Press, London.

Polson CJ, Gee D, Knight B. 1975. *The essentials of forensic medicine*, 4th edn. Pergamon Press, Oxford.

Pounder DJ, Carson DO, Johnston K, *et al.* 1998. Electrolyte concentration differences between left and right vitreous humor samples. *J Forensic Sci* **43**:604–7.

Pounder DJ, Stevenson RJ, Taylor KK. 1998. Alcoholic ketoacidosis at autopsy. *J Forensic Sci* **43**:812–16.

Prinsloo I, Gordon I. 1951. Post-mortem dissection artefacts of the neck and their differentiation from ante-mortem bruises. *S Afr Med J* **25**:358–61.

Ramu M, Robinson AE, Camps FF. 1969. The evaluation of post-mortem blood sugar levels and their correlation with the glycogen content of the liver. *Med Sci Law* **9**:23–6.

Rognum TO, Hauge S, Oyasaeter S, *et al.* 1991. A new biochemical method for estimation of postmortem time. *Forensic Sci Int* **51**:139–46.

Roll P, Rous F. 1991. Injuries by chicken bills: characteristic wound morphology. *Forensic Sci Int* **52**:25–30.

Rossi ML, Shahrom AW, Chapman RC, *et al.* 1994. Postmortem injuries by indoor pets. *Am J Forensic Med Pathol* **15**:105–9.

Salisbury CR, Melvin GS. 1936. Ophthalmoscopic signs of death. *Br Med J* **1**:1249–51.

Schleyer F. 1963. Determination of the time of death in the early post-mortem interval. In: Lundquist F (ed.), *Methods of forensic science*. Interscience Publishers, John Wiley and Sons, New York, pp. 253–93.

Schleyer F. 1975. Leichenveränderungen. Todeszeit-bestimmung im früh-postmortalen Intervall. In: Müller B (ed.), *Gerichtliche Medizin*. Springer-Verlag, Berlin.

Schuller E, Pankratz H, Liebhardt E. 1987. [Colorimetry of livor mortis.] *Beitr Gerichtl Med* **45**:169–73.

Scott KS, Oliver JS. 2001. The use of vitreous humor as an alternative to whole blood for the analysis of benzodiazepines. *J Forensic Sci* **46**:694–7.

Sellier K. 1958. Determination of the time of death by extrapolation of the temperature decrease curve. *Acta Med Leg Soc* **2**:279–301.

Shapiro HA. 1950. Rigor mortis. *Br Med J* **2**:304.

Shapiro HA. 1954. Medico-legal mythology; the time of death. *J Forensic Med* **1**:144–69.

Shapiro HA. 1965. The post-mortem temperature plateau. *J Forensic Med* **12**:137–41.

Shapiro HA, Gordon I, Benson SD. 1988. *Forensic medicine – a guide to principles*, 3rd edn. Churchill Livingstone, Edinburgh.

Shattock FM. 1968. Injuries caused by wild animals. *Lancet* **2**:412–14.

Shikata I. 1958. On the mortality of the leucocyte and the time lapse after death. *Jap J Legal Med* **12**:227–31.

Simonsen J, Voigt J, Jeppesen N. 1977. Determination of the time of death by continuous post-mortem temperature measurements. *Med Sci Law* **17**:112–22.

Smith KGV. 1973. *Forensic entomology*. In: Smith KGV (ed.), *Insects and other arthropods of medical importance*. British Museum of Natural History, London.

Smith KGV. 1986. *A manual of forensic entomology*. British Museum of Natural History, London.

Stephens RJ, Richards RG. 1987. Vitreous humor chemistry: the use of potassium concentration for the prediction of the postmortem interval. *J Forensic Sci* **32**:503–9.

Sturner WQ. 1963. The vitreous humour: postmortem potassium changes. *Lancet* **1**:807–8.

Sturner WQ, Ganter G. 1964. The postmortem interval. A study of potassium in the vitreous humor. *Am J Clin Pathol* **42**:137–41.

Sturner WQ, Dowdey AB, Putnam RS, *et al.* 1972. Osmolality and other chemical determinations in postmortem human vitreous humor. *J Forensic Sci* **17**:387–93.

Suzuki S. 1987. Experimental studies on the presumption of the time after food intake from stomach contents. *Forensic Sci Int* **35**:83–117.

Suzutani T, Ishibashi H, Takatori T. 1978. [Studies on the estimation of the postmortem interval. 2. The postmortem lividity (author's transl).] *Hokkaido Igaku Zasshi* **52**:259–67.

Szent-Gyorgyi A. 1947. *Chemistry of muscular contraction*. Academic Press, New York.

Tagliaro F, Bortolotti F, Manetto G, *et al.* 2001. Potassium concentration differences in the vitreous humour from the two eyes revisited by microanalysis with capillary electrophoresis. *J Chromatogr A* **924**:493–8.

Takatori T, Ishiguro N, Tarao H, *et al.* 1986. Microbial production of hydroxy and oxo fatty acids by several microorganisms as a model of adipocere formation. *Forensic Sci Int* **32**:5–11.

Takatori T, Gotouda H, Terazawa K, *et al.* 1987. The mechanism of experimental adipocere formation: substrate specificity on microbial production of hydroxy and oxo fatty acids. *Forensic Sci Int* **35**:277–81.

Takeichi S, Wakasugi C, Shikata I. 1984. Fluidity of cadaveric blood after sudden death: part I. Postmortem fibrinolysis and plasma catecholamine level. *Am J Forensic Med Pathol* **5**:223–7.

Takeichi S, Tokunaga I, Hayakumo K, *et al.* 1986. Fluidity of cadaveric blood after sudden death: Part III. Acid-base balance and fibrinolysis. *Am J Forensic Med Pathol* **7**:35–8.

Taylor A, Wilkes D. 1863. On cooling of the human body after death. *Guy's Hosp Rep* 180–211.

Tomlin PJ. 1967. 'Railroading' in retinal vessels. *Br Med J* **3**:722–3.

Tough SC, Butt JC. 1993. A review of fatal bear maulings in alberta, canada. *Am J Forensic Med Pathol* **14**:22–7.

Trujillo O, Vanezis P, Cermignani M. 1996. Photometric assessment of skin colour and lightness using a tristimulus colorimeter: reliability of inter- and intra-investigator observations in healthy adult volunteers. *Forensic Sci Int* **81**:1–10.

Tsunerari S, Oho S, Sasaki S, *et al.* 1975. Histopathological studies on the changes of the postmortem cornea. *Jpn J Legal Med* **29**:298–303.

Vain A, Kauppila R, Humal LH, *et al.* 1992. Grading rigor mortis with myotonometry – a new possibility to estimate time of death. *Forensic Sci Int* **56**:147–50.

Valenzuela A. 1988. Postmortem diagnosis of diabetes mellitus. Quantitation of fructosamine and glycated hemoglobin. *Forensic Sci Int* **38**:203–8.

Van den Oever R. 1976. A review of the literature as to the present possibilities and limitations in estimating the time of death. *Med Sci Law* **16**:269–76.

Vanezis P. 1991. Assessing hypostasis by colorimetry. *Forensic Sci Int* **52**:1–3.

Vass AA, Barshick SA, Sega G, *et al.* 2002. Decomposition chemistry of human remains: a new methodology for determining the postmortem interval. *J Forensic Sci* **47**:542–53.

Webb PA, Terry HJ, Gee DJ. 1986. A method for time of death determination using ultrasound – a preliminary report. *J Forensic Sci Soc* **26**:393–9.

Wroblewski B, Ellis M. 1970. Eye changes after death. *Br J Surg* **57**:69–71.

CHAPTER 3

The establishment of identity of human remains

- Characteristics useful in identifying the dead 99
- Identification of skeletalized remains 106
- The determination of sex 108
- Estimation of stature from skeletal remains 114
- Estimating the subject's age from skeletal structures 116
- Determination of race from skeletal remains 122
- Personal identity from skeletal material 123
- The dating of skeletal remains 126
- Photosuperimposition techniques for identification 128
- Reconstruction of the facial appearance from the skull 128
- References and further reading 129

The identity of the dead is an essential part of post-mortem examination, for various reasons. These include:

- the ethical and humanitarian need to know which individual has died, especially for the information of surviving relatives
- to establish the fact of death in respect of that individual, for official, statistical and legal purposes
- to record the identity for administrative and ceremonial purposes in respect of burial or cremation
- to discharge legal claims and obligations in relation to property, estate and debts
- to prove claims for life insurance contracts, survivor's pensions, and other financial matters
- to allow legal investigations, inquests and other tribunals, such as those held by coroners, procurators fiscal, medical examiners, judges and accident enquiries to proceed with a firm knowledge of the identity of the decedent
- to facilitate police enquiries into overtly criminal or suspicious deaths, as the identity of the deceased person is a vital factor in initiating investigations.

The establishment of identity has many facets, some of which have no medical content, such as the recognition of clothing, documents and personal property. Some aspects, though primarily the responsibility of the police, have a medical content, including identification of fingerprints and personal property such as hearing aids, spectacles, medicines, trusses and surgical prostheses. False dentures have such central importance that they will be considered in the section on odontology.

Identification from anatomical and medical features comprises two major aspects:

- The establishment of certain broad groupings, such as sex, stature, race and age. These may be determined solely from the available bodily remains, though corroboration may be obtained from other evidence. An obvious example would be sex determination from clothing and jewellery, though even this may no longer be absolutely reliable.
- Comparison of the remains with ante-mortem information and records from those thought to be the victims, which restricts the method by making it dependent upon the existence or availability of such comparable material.

The establishment of identity may be required upon:

- **Intact fresh corpses.** Here visual recognition, directly or by photography, may be made. Hair colour, skin pigmentation, scars and tattoos can be examined without difficulty.
- **Decomposed corpses.** Many surface features may be partially or wholly lost, but more information can be obtained than from a skeleton. Direct measurement of body height, for example, may be possible, as well as

serological investigations and organ abnormalities, such as past surgical intervention, may be found.

- **Mutilated and dismembered corpses.** Depending on the degree of mutilation and the amount of tissue missing, identification may be hampered. If the remains are fresh, facts such as racial pigmentation may be determined, but direct measurement of stature may be impossible. Selective mutilation in some homicides may be deliberately directed at frustrating identification, such as the removal of teeth and finger-pads.
- **Skeletalized material.** If all soft tissues are absent, identity depends solely on osteological examination and measurements and the recognition of any pathological or anatomical abnormalities in bone.

CHARACTERISTICS USEFUL IN IDENTIFYING THE DEAD

Facial appearance

Even in perfectly fresh bodies, recognition may be difficult because of alterations in the features caused by death. It is a common occurrence in mortuary viewing rooms for a close relative, even a parent or spouse, to have doubts about – or even to deny or mistakenly agree to – the identity of the deceased person. Though distress and emotion play a part, changes in the features may be profound. Hypostasis, contact flattening, oedema, muscle flaccidity and pallor may all combine to distort the face. Recognition in the living is partly a dynamic process, aided by facial muscle tone and especially eye contact and movement, all of which are absent in the corpse.

Eye colour

In the fresh corpse, eye colour corresponds with the living state, but it quickly deteriorates. Loss of intraocular tension and clouding of the cornea develops progressively within a few hours, making the iris harder to observe. Collapse of the front of the globe occurs within a day or two and, with developing decomposition, all irises tend to darken to brown. It is unsafe to depend on eye colour as a criterion of identity later than a few days following death – or even much sooner where environmental conditions hasten decomposition.

Skin pigmentation

In undamaged, unputrefied bodies, the major ethnic differences in skin pigmentation are obvious, though the slight melanin increase of the misnamed 'yellow' races of Asia may be impossible to differentiate from Mediterranean or Middle Eastern races. The onset of deathly pallor and post-mortem hypostasis is more profound than slight variations between sunburnt White people, northern Asians or Semitic races. When putrefaction sets in, skin slippage progressively removes the pigmented layers and eventually pigmentation becomes unavailable as a marker of identity, though histologically melanin may still be visible in the basal layer of any surviving epidermis.

Burnt bodies may also lose pigmented skin, either by heat destruction or by deposition of soot and other combustion products on the surface, though it is rare for this to be so complete as to obscure all evidence of pigmentation.

Hair colour

The head, pubic and axillary hair is one of the most resistant identifying features, sometimes lasting millennia in favourable environments. The original colour may, however, alter after burial, becoming a brownish-red or 'foxy' colour within as short a time as 3 months. The colour may be obscured by dirt or staining and expert treatment (usually by a biologist or museum technologist) may be required to restore the original colour. The possibility of deliberate chemical coloration or bleaching before death may have to be considered and again expert chemical analysis in a forensic science laboratory may be needed to confirm or eliminate this if the hair colour conflicts with other positive evidence of identity.

Hair structure

This is more the province of the forensic biologist or anthropologist, but factors such as whether the hair ends have been cut or are naturally pointed may sometimes have importance in identity. Racial features exist, Negroid head hair being dark and having a spiral twist with a flattened, elliptical cross-section. Mongoloid hair is less pigmented and is straight with a cylindrical cross-section. Caucasian hair is round or ovoid in cross-section, but shows great variation in colour and morphology compared with the other two major ethnic groups. Though head hair in Caucasians is round to ovoid in section, eyebrow hair tends to be triangular and pubic hair flattened. Where a hair root is present, blood grouping and other serological criteria can be determined. Grouping of the shafts of hairs has been repeatedly attempted and success claimed by some workers. The cells of the hair root can give a DNA profile and mitochondrial DNA (mtDNA) has been detected even in a sample from a single hair shaft.

Microscopic examination of the hair can assist in determining the species, if not human. Human hair has broad groupings when viewed microscopically. However, the topic of individual identity from hair is now the province of forensic biologists, and has a specialism and literature of its own.

Tattoos

Deliberate ornamentation of the skin by introducing pigments under the epidermis has been practised for millennia and in all parts of the world. The word 'tattoo' comes from the Polynesian '*ta tau*', meaning 'to mark'. Some races such as the Ibans of Sarawak may be tattooed over much of their body surface, but many men and some women in most countries have localized tattoos, which can be of considerable assistance in identification. Many different pigments are used, as well as more unusual substances such as soot or gunpowder. The colour is pricked into the upper dermis with a sharp instrument, usually a needle used manually, or by an electric vibrator.

Once under the outer skin, the material persists for a long time. Colours such as blue, green or red may be scavenged by tissue cells and leached into the lymphatic system after a number of years or decades. Black pigments, usually carbon particles in the form of Indian ink, are so resistant as to be virtually lifelong, though some may be transported to regional lymph nodes. Thus an original pattern of different colours may fade differentially over years, the black areas standing out in strong relief.

The patterns are so diverse as to defy classification, though much has been written on the subject. From the point of view of identity, tattoos may be useful in both a general sense and for comparison with potential victims. The general applications require a knowledge of ethnic, national, cultural, religious and social practices, so that the tattoo can be assigned to some particular group of people. In Western society, the popularity of tattooing changes from time to time. Former statements that tattoos are seen mostly in the 'lower social classes' have little current validity, though it is obvious that bankers and parsons are less likely to sport tattoos than seamen and truck drivers. It is also now totally anachronistic to claim that most women with tattoos are prostitutes, though the nature and position of the tattoo is obviously relevant.

Certain tattoos have had particular significance such as a number, often '13', inscribed inside the lower lip of drug pushers or the bluebird on the extensor surface of the web of the thumb in homosexuals. The latter design is now so common as to be of little significance.

Tattoos are of most use when individual enough to be compared with known designs on a missing person. The design is often supplemented by actual names, though these are mostly forenames rather than family names. Designs are by no means unique and a professional tattooist may turn out hundreds of identical decorations, so names are a bonus when trying to achieve identity.

Initials may be used, but these can be misleading due to the use of nicknames and diminutives, such as 'B' for Bill, rather than William. In general, men have the names of girls on their tattoos, but initials are usually their own. Conversely, women with tattoos almost always display the names of sweethearts, rather than their own. Some tattoos may be numbers or unadorned names, the most tragic examples being those from Nazi concentration camps during the last war.



FIGURE 3.1 *Individualistic tattoos may assist the identification of unknown persons.*

The photography, distribution and matching of tattoos is police business, but the pathologist's duty is to make them accessible and clear to the police. Where decomposition has set in, tattoos may be obscured by wrinkled, peeling epidermis, but often this can be wiped off to reveal tattoos that are more vivid than on fresh skin. Once the tissues become green and slimy, then the pattern progressively vanishes, but early decomposition is no barrier to recognition. Where skin pigmentation may hide a design, skin slippage may actually enhance the clarity, especially of the weaker colours like blue, red and green. Attempts at the deliberate removal of tattoos are common, either from regret at having disfigured the body during youthful or drunken euphoria, or to remove evidence of identity. Many methods have been used, from surgical excision to scarification with sandpaper and from caustic soda to electrolysis. All methods depend upon damage to the epidermis and dermis, with consequent inflammation and scar formation. The tattoo can certainly be removed, but always by replacing it by a cicatrix to a greater or lesser extent, which will itself indicate that something pre-existed at that site.

It has been suggested (PA Edwards, personal communication) that the chemical nature of tattoo pigments might be used in identification. Although all manner of substances have been used to tattoo, most tattooists use black pigments containing carbon, green pigments containing potassium dichromate and red pigments containing mercuric chloride. Others use aniline-based dyes, so that microextraction and analysis in a forensic science laboratory might confirm or exclude the tattoo having been executed by a particular artist in the locality.

Finger, palm, foot and lip prints

The science of fingerprints, their classification, retrieval from records and methods of recording lie in the domain of police procedure, and, as with tattoos, the pathologist's role is merely to facilitate the taking of prints by police officers. Sometimes when a strange print is found at a scene of crime, the police may wish to take the fingerprints of doctors who visited the locus to eliminate them from their enquiries and there is obviously nothing objectionable about this. Indeed, some forensic pathologists who habitually assist the police leave their prints on file so that they are permanently available for exclusion. When called to a scene of death, the doctor should take care to avoid handling objects and furniture to reduce the need for such laborious screening of prints.

The doctor need know nothing about fingerprints except for his own interest, though it is as well to be prepared for the inevitable questions – no two fingerprints have ever been found to be identical and even identical twins have different prints. However, some recent claims point out that some prints are so similar that the criteria usually accepted as proof of congruence may not be sufficient. Police usually attend the mortuary to take full sets of fingerprints in the usual way by rolling ink on to the finger-pads and pressing the pulps against record cards.

The pathologist may help when there is strong rigor present, by either forcing the flexed fingers back or even by slitting the flexor tendons, though this has the danger of fouling the fingers with blood.



FIGURE 3.2 *Shoulder region of a decomposed body recovered from the sea showing a tattoo with Cyrillic letters (Д, К, Б, Ф) and a flag with a star and hammer and sickle suggesting a connection with the Russian Baltic Fleet.*

When the body is putrefied, the doctor can again assist by removing desquamated casts from the fingers for the police. These may need to be preserved or hardened up so that the decaying tissue does not lose further definition from the ridges that form the prints. The skin may be placed in formalin, alcohol or glycerine solution, especially where maceration in an immersed body has caused swelling and blurring of the epidermis. An alternative is immersion in 20 per cent aqueous acetic acid for 2–8 hours. Rarely, a criminal may attempt to obliterate his fingerprints by scarring the fingerpads. To be effective, this must be drastic enough to damage the underlying dermis and the consequent cicatrices will be more obvious than the original prints. Surgical grafting of skin from elsewhere on the body has been reported as a means of removing fingerprints, but again the result is self-evident proof of nefarious intent.

As with fingerprints, the skin pattern of palms, soles and even lips are said to be unique and have been used in identification, but again this is really police business. The pattern of veins on the back of hands is also said to be characteristic to one individual.

Identifying scars

These can be important in the identification of unknown bodies, even when some degree of putrefaction exists. The author (BK) used a cholecystectomy scar and scars of old surgical incisions on the legs to identify the body of a homicide victim submerged in a river for 6 weeks and many other cases are on record where scars provided similar vital information. Probably the best known instance is the Crippen case of 1910 in which much forensic controversy was generated over the distinction between a surgical scar and a skin crease on a piece of abdominal wall.

Scars on the skin may arise from any previous injury that has breached the epidermis, as superficial injuries to the upper layer of skin will heal without a trace. Where the dermis has been entered, healing occurs by organization of the plug of blood clot and/or granulation tissue, as described in Chapter 4. If the wound is narrow, such as that inflicted by a surgical instrument, sharp knife, razor or glass, then if the edges are kept together, especially by stitches or dressings, the resulting scar will be narrow and insignificant. Gaping or infection will widen the scar and obviously larger lacerations or burns will result in similarly greater scarring. In relation to identification, scars are of use only if those thought to be the victims are known to have similar scars, both in nature and position. The specificity of scars varies greatly, as many people may have appendicectomy scars, and many women have had hysterectomies or other gynaecological operations that leave lower abdominal scars. As always, scar evidence must be taken in conjunction with all other details of identity, but where a cicatrix is unusual or even unique in nature or position, its value is greatly enhanced.

Turning to traumatic scars other than surgical, the pathologist may be able to recognize the cause, which can assist in identity. Naturally the vast majority of non-surgical scars are the result of accidental trauma and where family, friends, photographs or medical records indicate the existence of specific scarred sites on the body, then confirmation of identity may be greatly assisted or confirmed.

Some scars are deliberately produced as part of some ethnic or religious tradition, such as the facial scars in some African tribes, as well as deformed or perforated ear lobes or lips. Regrettably, another class of scars is becoming more common in many parts of the world, due to physical torture; this is dealt with in Chapter 10. Linear scars, cicatrices of burns, keloid overgrowth (especially in negroid races), hyperpigmentation or depigmentation and other persistent lesions may assist in identity in the appropriate circumstances. Much depends on the accuracy of the information concerning the person thought to be the victim; relatives are notoriously vague and inaccurate about medical matters and frequently confuse different surgical operations, thus misleading the investigators about scars. Sometimes surgical scars may be almost invisible. The author (PS) once worked as surgical assistant in a private hospital where one of the surgeons used to perform appendicectomy (in non-acute cases) through a 1 cm wide incision, closing the wound, for cosmetic reasons, with subcutaneous catgut sutures. Most of these wounds healed with virtually no scar whatsoever, unless the person had a tendency to keloid formation. Wherever possible, old hospital records or the notes of a family physician should be obtained.

The old scars of wrist- or throat-slashing indicate previous attempts at suicide. Large areas of scarring on the trunk or limbs that have parallel grooves and marginal extensions suggest severe brush lacerations, probably from a traffic accident. Knife stab wounds may scar in an elliptical fashion, sometimes even with a blunt and a sharp end indicating the position of a single-edged blade. Bullet wound scars may persist – and in 1989, became a matter of political controversy over the identity of Nazi war prisoner Rudolf Hess, who was alleged to have been an imposter because he had no scar from an old rifle bullet wound through the chest. Burns may provide good evidence of identity, especially if they are widespread cicatrices that may have been quite noticeable during life. Many scars on the fronts of the lower legs may indicate the repeated stumblings of a chronic alcoholic, who frequently walks into or falls over furniture.

The age of scars

The age of a scar is very difficult to assess and, once it becomes mature, no change will occur for the rest of the person's life. When a linear wound is inflicted, be it a surgical operation or a knife slash, the edges become mechanically strong within a week, assuming that no infection or haematoma develops. The wound is brownish red at this stage and remains vascular for several months, depending upon its width. The pinkness of contained blood vessels gradually fades and a narrow surgical incision may be white by 4–6 months. The avascular collagen tends to shrink for a year or so, but is white–silver after a year and remains in this state indefinitely. These times are variable depending on the nature of the skin, its pigmentation and the part of the body involved. Where a wound crosses a skin crease that is frequently flexed or extended, it tends to gape and widen, the subsequent scar following suit.

Histology does not contribute much to the examination of scars, except to confirm that a skin mark actually is a scar. Stains for collagen or elastin may confirm the discontinuity in the dermis. Scars do not carry hair follicles, sweat glands or sebaceous glands, though an occasional accessory skin structure may be present as a result of the inclusion of a viable fragment of original skin in an irregular wound – or where surgical repair has detached or invaginated a piece of the margin.

Occupational stigmata

Formerly given prominence in most textbooks, distinctive physical marks of occupation have decreased in incidence and importance. They are still of use in certain areas, but local knowledge of occupations and industries is required. The Victorian days of pen callosities in clerks and shoemaker's kyphosis have gone, but many other occupations have their stigmata, though most are relatively nonspecific. The best known is the 'blue scar' of coal-miners, an involuntary tattoo caused by dust entering small lacerations on the hands and face. Some miners and quarrymen also have small facial scars due to rock splinters scattered during blasting. Steel workers and foundry men may have tiny burn scars on exposed areas from the spattering of hot metal. In more general terms, examination of the hands will indicate whether the deceased was a manual worker or involved in more sedentary occupations. Cuts, scars, callosities and hyperkeratosis of the hands are obvious indicators of rough work.

Internally, black, dust-laden lungs – with or without pneumoconiosis – points to mining, as coal trimmers no longer exist as dock workers. Thickened, pearly plaques on the parietal pleura and diaphragm are caused by exposure to asbestos, though in recent years the widespread use of this substance in so many industries makes it less helpful in identifying the occupation.



FIGURE 3.3 *Careful external examination may yield evidence that can assist identification. The small 'blue scar' on this forehead establishes that the deceased had been a coal-miner; coal dust enters small lacerations and remains visible after healing. Virtually every coal-worker has such marks on hands or face.*

The stature of an intact body

The stature of a corpse is not necessarily exactly that of the person measured during life. In the mortuary, care must be taken to measure the body from heel to crown, and not to accept the mortuary attendant's or funeral director's 'coffin measurement', which is made from toe to crown. Because of the usual plantar flexion of the foot, this latter height may be as much as 10 cm longer than the heel–crown length.

The height of a dead body may differ from the height during life in either direction, being slightly longer or shorter, though lengthening is much more common. In addition, the measured height may change a little at different periods after death. Because of the complete loss of muscle tone in the first stage of flaccidity, relaxation at large joints, such as the hip and knee, together with the lost tensioning effect of paraspinal muscles on intervertebral discs, the body may lengthen by up to 2–3 cm. Rigor mortis may then replace the muscle tone, shortening the body and tending to flex the legs a little. When rigor passes off and decomposition sets in, joints become lax. Loss of tension in the intervertebral discs tends to shorten the spinal column and hence the total height by a centimetre or so. According to Trotter and Gleser (1958, 1977), the average increase is about 2–5 cm. The errors in getting a really accurate post-mortem length include the difficulty of locating the measuring device exactly at the heel and the crown of the head, as well as fully extending the limbs, spine and neck of a body in rigor.

Determination of sex in non-skeletalized bodies

This is usually obvious and rarely presents problems. The issue of intersex and hermaphroditism is so rare as to be discounted in most forensic practice, except in some areas, such as South-east Asia, where deliberate transsexualism in men, aided by surgical intervention to feminize the genitalia and breasts occurs more frequently. Where this problem arises, expert advice must be sought. In general, the external genitalia remain recognizable until a late stage of putrefaction. In addition, breasts and general body shape, as well as the pattern of pubic hair, reveal the sex. Female pubic hair usually grows low on the abdomen, the upper margin being a horizontal or semicircular edge above the mons veneris. The male pattern rises more in the centre line, sometimes as far as the umbilicus. There are, however, always exceptions to these generalizations. The presence or absence of circumcision should be noted, as it may help in identification of certain ethnic and religious groups such as Jews and Muslims. Naturally it is of assistance here in eliminating only those where the prepuce is present, as many men of other religions are circumcised.

Clothing, hair length, hair style, hair coloration, earrings and other jewellery are no longer the reliable guide to sex that they once were. In certain cultures and religions there are obvious criteria that can assist in the determination of sex, but these are rarely needed as the more apparent anatomical differences can be used. Where putrefaction is advanced, examination of the internal pelvic organs may still reveal unequivocal evidence of sex. Internal viscera are often in better condition than the outside of the body. The uterus is the organ in the body most resistant to decomposition, though the prostate is also quite persistent.

Where almost total dissolution exists, then radiology of the pelvis or the criteria used in skeletal assessment can be used. Cytological examination of cell nuclei may indicate sex where only tiny fragments are available – such as tissue found on a road or rail vehicle where impact with a body is suspected. Usually it is the species rather than the sex that is the first consideration, and this is done by species-specific serology. When sex is to be determined, much depends on the state of preservation. When stained microscopic smears can be prepared or when tissue can be processed for histological sections, then sex-indicating nuclear chromatin may provide a definitive test. The ‘drumsticks’ of polymorphonuclear leucocytes, and the marginal chromatin masses or ‘Barr bodies’ in epithelial cells, such as the buccal mucosa, may indicate the sex, but in decomposed material this may be impossible.

The recent remarkable developments in cytogenetics and DNA analysis now give additional powerful tools in sexing and determining the human origin of sub-anatomical fragments, which will partly or wholly replace the older techniques mentioned above.

Other more recent techniques include counting the sex material within the nucleus stained with a fluorescent dye and viewed with ultraviolet light; this may be performed on neurones in a brain smear or in cells from the kidney.

Age of non-skeletalized bodies

Determining the personal age of a corpse is far harder than determining its sex. Ageing a living person can be difficult and a wide margin of error exists, especially as age advances, so the same exercise in a corpse can be expected to be even less exact. Where the body is relatively intact, the usual criteria known to the man in the street are applied to make a general estimate. Hair colour is of general applicability, though every one knows of someone whose hair is grey at 25 or someone who is dark haired at 70. The loss of elasticity in the skin, its thinness and hyperkeratosis and its red Campbell de Morgan spots are indicators of senility. These days teeth are less useful than in the past from the point of view of extractions, clearance, full dentures and oral hygiene, but the general impression remains. The objective determination of age from tooth attrition is a matter for a specialist forensic odontologist (see Chapter 26).

The eyes are useful, in that a grey or white ring around the pupil – the ‘arcus senilis’ – is rarely seen below 60 years. In infants and children, the height and weight may be compared with standard tables, but developmental defects, disease and malnourishment may introduce considerable errors. Internally, the evolution of degenerative changes such as arterial atherosclerosis and arthritis, may give a general impression, but personal variation is so great that it offers little more than a distinction between ‘young’ and ‘old’. Where a distinction has to be made in a double death between two people of markedly different ages, however, then these generalities may be of considerable use. Up to the age of about 20–25, teeth, ossification centres and epiphyseal fusion are good indicators, but these are described in the section on skeletalized material.

Recent research, aimed mainly at skeletalized bodies but available for any corpse, is the determination of the racemization ratio of amino acids in teeth, as the preponderance of laevo- and dextro-compounds appears to be a function of personal age.

In addition, the Gustafson technique on teeth, described later, is also applicable to a non-skeletalized body, if ageing is important.

Racial and ethnic characteristics

Much of the identification of race depends on common knowledge and recognition of various ethnic traits, and is not primarily a medical problem. Everyone can recognize the deep pigmentation of a West African the epicanthic folds of the Mongoloid races, the red-haired Celt and the pale blond common in Scandinavia. There is a wide and almost continuous range of biological variability, however, not only because of extensive ethnic interbreeding, but also because of marked variations even within a coherent racial group.

In the intact or only partially decomposed body, the following factors may be used as pointers to ethnic classification, but the non-specificity of most of these must always be borne in mind:

- Clothing, ornaments and other associated objects. A vast catalogue can be assembled (such as the string around the wrist in Hindus), but it must be borne in mind that other races may adopt these through choice, marriage or deception.
- Hair texture, style and length and beards. Examples are the hair of the Sikh, the beard of the orthodox Jew, the crinkly hair or 'peppercorn' (clumped growth) of some Negroids, the multiplaiting of Rastafarian West Indians, the straight black hair of Asians and the ginger hair most common in Celtic people. With affected styles and convincing modern coloration and texture alteration, however, these features can be most misleading. Forensic science techniques may be needed to detect and identify bleaching and dyeing changes in hair.
- Physical artefacts include penile and vulval circumcision, nose and ear piercing, lip perforation, tribal facial scars, and earlobe distension in East Africans and some tribes in Sarawak. More bizarre forms, such as neck-stretching by rings, are now rare. Tattoos (mentioned elsewhere) may have an ethnic basis, as in the Ibans of Sarawak.
- Facial appearance is, of course, a major criterion with the high cheek bones and epicanthic folds of the Mongoloid peoples, and the prognathism and nasal differences in Negroid peoples. So many intermediate forms exist, however, such as the Slav and the Polynesian, that only the classic groupings can be identified with confidence.
- Body size gives rise to the same uncertainty, especially as racial differences have lessened with better nutrition in some groups. It is obvious, however, that Japanese are generally smaller than northern Europeans and that in Negroid bone structure the femora are proportionately longer and less curved than those of other races. Teeth are discussed later, but the concave upper central incisors of the Mongoloid races can be helpful on occasions, though they are not absolutely specific.

Finally, skin pigmentation can obviously differentiate the Negroid races from the other main groups, though again there is a continuous range of skin colour. To a lesser extent the slighter melanin content of the skin of Mongoloid races is recognizable, but merges into the variable tints of Semitic, Asian and Mediterranean peoples.

It may well be that, in the near future, genetic DNA studies will revolutionize this aspect of identification. They are also likely to do the same for personal identification.

Identification by DNA characteristics

One of the most revolutionary advances in identification in recent years is the so-called 'DNA profiling or fingerprinting'. This is a technique devised by Alec Jeffreys of Leicester University, in which virtually unique sequences of bases in the DNA strands of chromosomes are used to compare one blood or tissue sample with another, and to investigate genetic relationships. The details of the technique are complex and require highly specialized reagents and apparatus. The method needs highly trained forensic scientists for its application to medico-legal problems. All that the pathologist needs is a basic knowledge of the principles of the technique and how it can be applied in a forensic context.

The deoxyribonucleic acid (DNA) that forms genetic material is composed of two strands of sugar and phosphate molecules that are twisted into a double helix, which is bound together by links formed from adenine and thymine and cytosine and guanine. Each helical twist has ten such links, like rungs on a twisted ladder. A single DNA molecule may have millions of such links and the permutations of the bases in each adjacent link create the genes, the segments of the DNA that carry genetic information. A gene consists of a segment containing some hundreds or thousands of links, but separating these discrete genes are segments that seem to have no genetic function, being redundant. There is about a metre of

DNA in each human nucleus, but only 10 per cent is used for genetic coding, the rest being redundant. Of these silent segments (sometimes called 'stutters'), there may be 200–14 000 repeats of each identical sequence on each DNA strand.

During investigations into a specific gene (that for synthesizing myoglobin), Jeffreys found that the adjacent redundant segments varied greatly in base sequence, but that they were constant for a given individual and that they were transmitted from parents in a regular fashion. In other words, they formed a 'signature' that was virtually unique for every individual person, except identical (uni-ovular) twins, in whom they must be the same as they share the same DNA in the fertilized ovum. The chance of two persons sharing the same sequence is, according to Jeffreys, about one in a million billion. Even among siblings, the chances are only one in ten thousand billion.

To identify the redundant segment (often called the 'minisatellite' or 'hypervariable regions'), a minute amount of human tissue containing nuclear material is required. A small volume of blood containing leucocytes is sufficient, or a semen sample, pulp from a tooth or a hair with some sheath cells at the root. The DNA from the contained nuclear material is broken up into fragments by enzymes called 'restriction endonucleases' that cleave the DNA strands at predetermined spots. The fragments are then separated by gel electrophoresis, which spreads the fragments into bands, transferred to nylon or nitrocellulose sheets and subjected to a 'DNA probe'. This is a single strand of DNA labelled with radioactive phosphorus-32. This latches on to the separated minisatellite fragments and – by microradiography – the position of each band is rendered visible on an X-ray plate.

The end result is a series of parallel bars, similar in appearance to the 'bar code' printed on goods in a supermarket. However, more recently the bar pattern from multilocus probes has been supplemented or replaced by simpler patterns from single-locus probes, though the principles remain the same. From the presence of different bars in given positions, comparisons can be made with other samples, so this is a classic forensic technique of comparison. The test is useless without something to be compared with, but the blood on a weapon in the possession of a suspect can be matched with virtually complete confidence against the blood of the victim. Seminal fluid in the vagina of a victim of a murder/rape can be matched against the blood DNA pattern of a suspect – there is no need to match semen against semen, as all the DNA in a given person must, by definition, be identical. A few hair roots found on a blunt instrument in the possession of a suspect from a murder can be matched against the autopsy blood sample. In sexual crime cases, a great advantage of DNA testing over conventional blood-group secretor tests is that DNA can distinguish between mixed semen and vaginal fluids from a swab, which can confuse or negate blood-group techniques.

Another wide medico-legal use is in paternity testing where, unlike blood group, haptoglobin and enzyme tests, a positive identity of parents can be made, rather than a mere exclusion. Every bar in the 'bar-code' must have come from either mother or father, half the number from each. In testing, the coding is made from child, mother and father. The bars in the child's code are first matched with those in the mother's pattern. The remaining bars then must correspond with those from the father – if not, he cannot be the father.

SAMPLES REQUIRED FOR DNA TESTING

Although amplification techniques, such as polymerase chain reaction (PCR), etc., now allow minute samples to be tested, the larger the sample, the better the chance of a successful DNA test.

Post-mortem material is inferior to live blood and tissue for DNA fingerprinting if any significant post-mortem change has proceeded enough to break down nuclear chromatin. Plain blood samples should be taken, however, though leucocytes may have already disintegrated. Some 5 ml of blood is taken into an EDTA tube, which extracts metallic ions and not only prevents clotting, but inhibits enzymes in blood or micro-organisms, which may break down DNA during storage. The best material is said to be muscle or the spleen and, if decomposition is advancing, the bone marrow is recommended. At least 0.5 g of tissue should be cut from the parenchyma of an organ and placed in a small plastic tube with no fixative or preservative. This should be frozen at −20°C if there is likely to be the slightest delay in transmission to the laboratory.

In sexual offences associated with homicide, as much material as can be obtained from the vagina should be collected, either fluid by pipette or multiple swabs from vagina, rectum and mouth. These again should be frozen if there is more than a few hours delay in transit to the laboratory (see also Appendix 1).

IDENTIFICATION OF SKELETALIZED REMAINS

One of the classic problems of forensic pathology, the identification of a whole or partial skeleton, involves techniques and expertise that span a number of disciplines from anatomy to radiology, from archaeology to dentistry. It often overshadows the equally important need to identify intact or decomposed corpses, but the disproportionate amount of space occupied by skeletal identification in most textbooks can be partly justified by the fact that bones can survive for decades, centuries or millennia, so that the cumulative reservoir of material is vast. As was observed in relation to intact bodies, the procedure for identifying bony remains falls into two distinct sections:

- allotting the bones to general categories based on absolute criteria concerning species, race, sex, stature, age and date
- comparative studies, where the remains are matched against ante-mortem data derived from those people who might be potential victims.

The general categorization of skeletal remains

When objects thought to be skeletal remains are found, the following questions need to be asked and, where possible, answered:

- Are they bones?
- Are they human bones?
- What is the sex?
- What is the stature?
- What is the race?
- What is the age?
- How long have they been dead and/or concealed?
- What was the cause of death?

Are the remains actually bones?

This question is not as facetious as it may seem, as untrained persons may provide objects that falsely resemble bones. The author (BK) has been offered shaped stones, plastic and even hard wood, which were thought to be bones. The mistake is even more common when these objects are mixed with undoubted bones, usually animal in origin, which may be found buried or mingled with rubble.

Recognition is usually easy, by the shape, texture and especially weight of the objects. Greater difficulty may be experienced when simulated human 'bones' are found, such as the 'radius' brought to the author (BK). This originated from a medical student's anatomical skeleton and was made from plaster coated with a plastic polymer. Visually it was indistinguishable from a real bone, but the abnormal lightness indicated the true nature.

Are the bones of human origin?

The recognition of species is important, but deciding on a human origin is usually easy, unless marked fragmentation has occurred. Many animal bones are found by the general public and police who are not qualified to decide whether they are human. Extensive rebuilding programmes and the renovation and demolition of old sites reveal many caches of bones, but in the authors' experience the majority are of animal origin, often originating from butchers' debris.



FIGURE 3.4 *All bones are not human – and not all 'bones' are bones. The smaller bones are animal, but the central 'radius' is from an ersatz student skeleton, made from plastic material, but thought by the police to be evidence of a criminal death.*

First, the size is assessed and many small, slender bones excluded on obvious grounds. Even a turkey thigh cannot be mistaken for a metatarsal, nor a beef rib for human. The gross anatomy is then studied, and even if the pathologist makes no pretensions to being a comparative anatomist, the majority of intact animal bones can be recognized from their lack of correspondence to any human bone. Difficulties arise with smaller bones from some animals, especially the hands and feet, where digits, metatarsals and metacarpals require careful study to distinguish them from the human. Several errors have been made in respect of bear paws, which closely resemble the human hand.

When bones are incomplete or fragmentary, the problems escalate rapidly. If the ends of longer bones are present, then their non-human shape may be more readily determined, but cylindrical segments of the central shaft have little in the way of distinguishing features, apart from size. Burnt bone fragments offer similar problems, added to which is the possibility of heat distortion and shrinkage.

The advice of an anatomist is needed in such cases, preferably one with forensic experience and enthusiasm for the project. Unfortunately, every anatomist is not necessarily an osteologist and it may be more effective for the bone to be examined by a pathologist who has both enthusiasm and the relevant reference books.

Histological examination may offer a species differentiation – or at least to exclude a human origin. The Haversian architecture is different in many animals, but the few specialist papers on this subject must be consulted for details.

Where the animal species is relevant to the enquiry, then a veterinary or comparative anatomist must be consulted. If the bones are too fragmentary to provide any anatomical data, then serological investigations must be attempted. These depend on species-specific proteins being extracted from the bone into solution where they can be tested against specific antisera prepared by immunizing animals (usually rabbits) against a range of animal proteins, usually derived from blood. Thus the test is essentially seeking plasma constituents within the bone, the recognition being carried out by techniques such as electrophoresis or gel diffusion. DNA can now identify human tissue, if not the alternative species.

The drawback of such serological tests is that they cannot be applied to bones that no longer have extractable proteins, and these include burnt or cremated bone and bone that has been dead for some years. The length of time for which identifiable protein persists is variable, but a negative result is usually to be expected after 10 years following death, though DNA techniques may be more sensitive.

THE DETERMINATION OF SEX

The accuracy of determination of the sex of skeletal remains varies with the age of the subject, the degree of fragmentation of the bones and biological variability (Table 3.1).

Particularly when studying the skull and pelvis, a subjective impression by the experienced observer defies complete analysis, yet objective measurement may be no more accurate: in other words, the processes comprise morphological traits versus morphometry. The determination of sex is statistically the most important criterion, as it immediately excludes approximately half the population whereas age, stature and race each provide points within a wide range of variables. Obvious sex differences do not become apparent until after puberty, usually in the 15–18-year period, though specialized measurements on the pelvis can indicate the sex even in fetal material. Sex and age are linked, especially where body size and weight are concerned. Similarly, race confuses sexing, for example, the size of the supraorbital ridges in a normal negroid female may exceed those in the average Caucasian male.

TABLE 3.1 *Pfitner's table of bodily dimensions in the female compared with the male (per cent of male dimensions). The common generalization that the female is 94 per cent of the male size varies in different areas of the body*

Stature	93.5	Arm length	91.5
Head breadth	98.0	Sitting height	94.5
Face breadth	94.0	Head circumference	96.0
Face height	90.0	Head height	96.0
Head length	95.5	Leg length	93.0

The accuracy of sexing is hard to estimate, as various loading factors exist. Krogman comments that he scored 100 per cent accuracy using the whole skeleton, 95 per cent on pelvis, 92 per cent on skull, 98 per cent on pelvis plus skull, 80 per cent on long bones and 98 per cent on long bones plus pelvis. He admitted, however, that, as most anatomy department material has a sex ratio of about 15:1 in favour of men, marked bias could be introduced by assigning all doubtful bones to the male category.

Stewart records that, for the whole skeleton, one can expect a 90–95 per cent success rate and for the skull alone only 80 per cent, but, if the mandible is also present, this rises to 90 per cent (Hrdlicka 1939). In general, adult female skeletal measurements are about 94 per cent that of the male of the same race, but different measurements may vary from 91 to 98 per cent.

The skull

The following features develop after puberty and are modified by senility, so are applicable only between about the 20th and the 55th year. Age as well as race has a profound effect.

- **General appearance.** The female skull is rounder and smoother than the rugged male.
- **Size.** Male skulls are larger, with an endocranial volume some 200 ml greater.
- **Muscle ridges** are more marked in male skulls, especially in occipital areas where larger muscles are



FIGURE 3.5 *Anatomical landmarks of the skull.*

attached to the nuchal crests and in temporal areas for larger masseter and temporalis muscles.

- **Supraorbital ridges** are more marked in male skulls and may be absent in female. The glabella (central forehead eminence above the nose) is small or absent in the female, and prominent in the male, though this is a poor discriminant.
- **Mastoid process.** This is larger in male skulls (see Hoshi).
- **Frontal and parietal eminences.** These are more prominent in female skulls, which resemble the shape in an infant more than in a male.
- **Palate.** This is larger and of a more regular U-shape in men. The smaller female palate tends to be parabolic.
- **Orbits** are set lower on the face in the male skull, with more square and less sharp edges (especially upper edge) than the female.
- **Nasal aperture.** This is higher and narrower in the male skull and has sharper edges. The nasal bones are larger and project further forward to meet at a more acute angle than in the female.
- **Forehead.** This is high and steep in the female skull, with a more rounded infantile contour than the male.
- **Teeth** are smaller in the female skull, molars usually having four cusps. The male often has a five-cusp lower first molar.
- **Zygomatic process.** The posterior ridge projects back beyond external auditory meatus in the male skull. The zygomatic arches bow outward more than the female, where they remain more medial.
- **Mandible.** This is large in the male skull, with a squarer symphysis region. Female jaws are more rounded and



FIGURE 3.6 *Two recovered and reassembled skeletons. After cleaning, the bones should be laid out in correct anatomical position, to gain an approximate direct measure of the stature, allowing as well as possible for lost soft tissue. The upper skeleton, obviously male, shows the frequent loss of small hand and foot bones, but no injuries. The lower remains, from a hidden 40-year-old homicide, reveal that the body was sawn into six sections, there being cuts above the knees and through spine, scapula and humeri.*



FIGURE 3.7 *Frontal view of male and female skull. The male (left) is larger, more massive and has heavier eyebrow ridges. The chin is squarer and the mandible heavier, The female has relatively larger height orbits, a smoother cranium, and fuller frontal and parietal eminences.*



FIGURE 3.8 *A typical male skull, with a sloping forehead and prominent occipital ridges for large muscle attachment. Probably the best male feature is the large mastoid process; also, the zygomatic process extends well behind the auditory meatus.*



FIGURE 3.9 *A typical female skull, from a murder victim hidden for 40 years in a cave. The cranium is high, round and smooth with insignificant ridges for muscle attachment. The mastoid is tiny, one of the best discriminants. The post-zygomatic ridge does not continue behind the auditory meatus and there are no supraorbital ridges. The chin is round and smooth.*

project less at the anterior point. The vertical height at the symphysis is proportionately greater in the male. The angle formed by the body and the ramus is more upright in the male, being less than 125°. The condyles are larger in the male skull, as is the broader ascending ramus, and there is a more prominent coronoid process.

These sex variations represent the 'typical' White and, to a great extent, Asian skull. There is considerable overlap, especially in subjects from the Indian subcontinent, where osteological sex differences are much less marked. The criteria set out above exclude prepubertal and senile persons, and are less valid for those outside the 20–55 age group. For methods of sexing by discriminant function analysis, the work of Giles and Elliot (1963) should be consulted. In recent years craniometry has been applied to sexing the skull and multiple accurate measurements between discrete anatomical points have been used to produce discriminant function analysis. The papers of numerous authors must be consulted for details of this sophisticated and difficult technique that is accurate in 83–88 per cent of cases. The frequency of correct sexing is no greater than more subjective methods, but commands a greater degree of confidence level in respect to its accuracy.

Sex characteristics in the pelvis

The post-pubertal female pelvis is wider and shallower than the rather upright male girdle to allow for the passage of the fetus during childbirth. Though as always there is an overlap of the appearance and measurements in the least characteristic individuals, the usual variations are sufficient to allow sexing of the adult pelvis to be made with about a 95 per cent confidence rate (see work by Genovés). In the pelvis, unlike the skull, there are differences, albeit subtle, in immature (even fetal) pelves that allow sexual differentiation. The following features provide the most useful criteria. One must not be used in isolation, however; as many as possible must be assessed together. Sex features are independent of each other and one may even contradict the other in the same pelvis. It is often a first subjective impression by an experienced eye that determines the answer, though where the sex differences are slight, careful measurements may be needed to resolve the problem.

As in the skull, the male pelvis is more rugged because of the attachment of stronger muscles. It stands higher and more erect than the smoother, flatter, female pelvic girdle. The subpubic angle, measured at the medial intersection of two lines drawn along the best approximation of the lower border of both inferior pubic rami, approaches 90° in the female pelvis, but usually about 70° in the male.

This is often a subjective measurement, however and depends in turn upon the shape of the pubic bone itself. When the line of the inferior ramus is projected medially and intersected with a horizontal line laid across the upper border of the superior ramus, the reverse size of angle is seen, the male being wider than the female.

The body of the pubic bone, the block lateral to the symphysis, tends to be triangular in shape in the male, whilst the female pubis is more rectangular (Phenice 1969; Iscan and Derrick 1984). Certain sexual variations in the pubis have been used by Phenice. In the female these are:

- a bony ridge ('ventral arc') running down the ventral surface from the pubic crest
- a concavity of the lower margin of the inferior pubic ramus immediately lateral to the lower border of the symphysis
- a ridge of elevated bone on the medial aspect of the ischiopubic ramus, immediately lateral to the symphysis; in the male this area is broad and flat.



FIGURE 3.10 *Sex differences in the human pelvis. The most noticeable features are the narrower suprapubic angle and the higher iliac blades in the male pelvis.*

The 'ischiopubic index' devised by Washburn may be helpful, in which the pubic length (×100) is divided by the ischial length. The measurements must be carefully made, the pubic length being from the plane of the symphysis to the reference point in the acetabulum and the ischial length being from the same point to the most distal edge of the ischium. The reference point is the site of fusion of the three elements of the immature innominate bone, usually marked by a notch in the articular surface of the acetabulum (Schultz 1937). If the ischiopubic index (in White races) is less than 90, the pelvis is male; if over 95, it is female. The acetabulum is larger in the male, being an average of 52 mm in diameter, compared with 46 mm in the female. The male joint cup also faces more laterally than that of the female, which tends to look more forward. Naturally, acetabular size is related to that of the femoral head, which will be considered later. The greater sciatic notch is an important criterion, being deep and narrow in the male, wide and open in the female. The angle formed by the margins approaches closer to a right angle in the woman than it does in the man. Harrison (1968) and Hrdlicka (1939) both felt that the greater sciatic notch was one of the best discriminants for sex, the latter claiming a 75 per cent success rate using this criterion alone.

The obturator foramen is somewhat ovoid in the male, but triangular in the female. The pre-auricular sulcus, which marks the attachment of the anterior sacroiliac ligament, lies just lateral to the sacroiliac joint and is usually well marked in women but often absent in males. The pelvic inlet, looked at from above, is more circular in the female, the male being heart-shaped as a result of the protrusion of the sacrum into the posterior brim (Greulich and Thomas 1938). A number of other pelvic 'indices' have been devised by various authors (see, for example, the work of Turner, Greulich and Thomas, Caldwell and Molloy, Straus, and Derry).



FIGURE 3.11 *The greater sciatic notch is narrower in the male innominate bone.*

Sex characteristics in the sacrum

The sacrum is functionally part of the pelvis and shares in its sex variations. The female sacrum is wide and has a shallow curve, again related to the larger pelvic canal for childbirth. It is shorter in the female and the curve is limited almost entirely to that distal part below the centre of the third sacral vertebra. The male sacrum may have more than five segments, which is rare in the female. The curve in the male is continuous down the whole bone and there may even be a slight forward projection of the coccyx. Fawcett (1938) compared the transverse diameter of the first sacral vertebra (CW) with that of the base of the sacrum (BW). The formula CW × 100/BW averaged 45 in the male and 40 in the female. Kimura (1982) has developed a 'base wing index', where the relative widths of the wing and base provide discriminant function coefficients for sex determination.

Sexing from the long bones

The femur is the most useful, its length and massiveness themselves being significant. There is, as usual, considerable overlap of all long-bone sex characteristics, but Brash's series showed that the maximum (oblique) length in the male femur was around 459 mm, while that of the female was only 426 mm. Other figures from Pearson and Bell (1917) suggested mean values of 447 mm for men and 409 mm for women. Using the trochanteric oblique length, they suggested a range of 390–405 mm for women and 430–450 mm for men, though there was the usual overlap in the middle. Race and nutrition (which is related to the era and the place in which the samples were obtained) must be allowed for in such measurements.



FIGURE 3.12 *The variation in shape of the male and female sacrum. The female is broader and more triangular.*

TABLE 3.2 *Dwight's table for sexing from humeral and femoral head diameters (in mm)*

	Vertical humeral	Transverse humeral	Vertical femoral
Female	42.67	36.98	43.84
Male	48.76	44.66	49.68
Difference	6.09	5.68	5.84

TABLE 3.3 *Pearson and Bell's table for the 'mathematical sexing of the femur'. The area of uncertainty extends in increasing degrees of confidence outwards from the central column to the more definite limits on each side. Measurements are given in millimetres*

	Male	Male or female	Female
Vertical diameter of head	>45.5	43.5–41.5	<41.5
Popliteal length	>145	114–132	<106
Bicondylar width	>78	74–76	<72
Oblique trochanteric length	>450	405–430	<390

The size of the femoral heads is claimed to be a better discriminant of sex, the vertical diameter being said by Pearson and Bell to be greater than 45 mm in the male and less than 41 mm in the female, though again there is an overlap in the distribution curves around the 43 mm size (Table 3.2). Maltby (1917), however, measured 43–56 mm in the male and 37–46 mm in the female. Femoral head size is part of Pearson's 'mathematical sexing of the femur', which incorporates several measurements (Table 3.3). Dwight (1904) studied the size of both femoral and humeral heads, claiming that they were more useful than bone length. Once again, discriminant function sexing has been carried out, using a number of measurements. Details should be sought in the work of Black and of Iscan and Miller-Shaivitz.

Another sex trait in the femur is the angle that the shaft makes with the vertical. Because the pelvis is relatively wider in the female, the shafts have to slope more to converge at knee level, so that the condyles at the lower end of

TABLE 3.4 *Long-bone lengths (mm) in White men and women of different stature*

Men							Women						
Humerus	**Radius**	**Ulna**	**Stature**	**Femur**	**Tibia**	**Fibula**	**Humerus**	**Radius**	**Ulna**	**Stature**	**Femur**	**Tibia**	**Fibula**
295	213	227	1530	392	319	318	263	193	203	1400	363	284	283
298	216	231	1552	398	324	323	266	195	206	1420	368	289	288
302	219	235	1571	404	330	328	270	197	209	1440	373	294	293
306	222	239	1590	410	335	333	273	199	212	1455	378	299	298
309	225	243	1605	416	340	338	276	201	215	1470	383	304	303
313	229	246	1625	422	346	344	279	203	217	1488	388	309	307
316	232	249	1634	428	351	349	282	205	219	1497	393	314	311
320	236	253	1644	434	357	353	285	207	222	1513	398	319	316
324	239	257	1654	440	362	358	289	209	225	1528	403	324	320
328	243	260	1666	446	368	363	292	211	228	1543	408	329	325
332	246	263	1677	453	373	368	297	214	231	1556	415	334	330
336	249	266	1686	460	378	373	302	218	235	1568	422	340	336
340	252	270	1697	467	383	378	307	222	239	1582	429	346	341
344	255	273	1716	475	389	383	313	226	243	1595	436	352	346
348	258	276	1730	482	394	388	318	230	247	1612	443	358	351
352	261	280	1755	490	400	393	324	234	251	1630	450	364	356
356	264	283	1767	497	405	398	329	238	254	1650	457	370	361
360	267	287	1785	504	410	403	334	242	258	1670	464	376	366
364	270	290	1812	512	415	408	339	246	261	1692	471	382	371
368	273	293	1830	519	420	413	344	250	264	1715	478	388	376

Modified by Krogman and Iscan (1986) from Hrdlicka (1939).

the femur sit horizontally on the tibial plateau. Thus when a female femur is seated on its condyles on a flat surface, the angle the shaft makes with that surface is of the order of 76°, while a male bone is more upright, the angle being around 80°. The angle of the neck on the shaft of the femur (the 'collodiaphyseal angle') was studied by Godycki (1957), the results suggesting that a bone with an angle of less than 40° had an 85 per cent chance of being male, while if the angle exceeded 50°, there was a 75 per cent chance of it being from a female (Table 3.4).

Most workers have worked with dry bone specimens; when methods using fresh bone are used, allowance must be made for articular cartilage where relevant. For example, the vertical diameter of a femoral head is 3 mm less in the dried specimen.

Sex determination from other bones

The sternum may be helpful in that the length of the manubrium in the female may equal or exceed half the length of the body, while the manubrium of the male is less than half the body length (Table 3.5). This was claimed in the nineteenth century by Hyrtl, but was denied by Krogman and by Dwight. The latter claimed that the ratio of manubrium: body was 52:100 in women and 49:100 in men, a poor discrimination. However, the method has been rehabilitated by Iordanidis (1961), who alleged a success rate of 80 per cent using the sternum alone. Stewart and McCormick (1983) used a radiographic technique and claimed total accuracy in stating that a sternal length of less than 121 mm must be female and over 173 mm must be male.

TABLE 3.5 *Sex determination from the sternum. Mean (range) lengths of manubrium and sternal body (mm)*

	Male	**Female**
Manubrial length	51.7 (41–73)	48.4 (39–61)
Body length	95.4 (74–122)	78.6 (59–95)
Combined length	147 (131–180)	127 (107–140)

Taken from Jit *et al.* (1980) North Indian population.

The scapula has been studied extensively, but mostly in relation to age. There are relatively poor sex variations in the vertical diameter of the glenoid cavity: the threshold, according to Dwight, is 36 mm, those smaller being female. Iordanidis made an extensive study of scapular measurements and concluded that scapular height was the best discriminant, the male usually being greater than 157 mm, the female less than 144 mm.

The humerus, radius and ulna yield little helpful sexing evidence, apart from overall size. The presence of a perforated olecranon fossa at the lower end of the humerus occurs more often in females and more commonly on the left side, there being a 3.7:1 ratio compared with males. Godycki studied this and other characteristics of the arm bones as sex determinants, but their value is poor.



FIGURE 3.13 *Determination of sex of femur by angulation of the shaft. The condyles are set on a flat surface and the angle of the shaft measured. Because of the greater tilt caused by the relatively wider pelvis, the female angle is usually less than 80°.*

There are many reports on sexing from limb and girdle bones and the best approach seems to be a multiple assessment using the data for discriminant function analysis.

Evidence of pregnancy from the skeleton

More accurately, parturition causes some changes in the pelvis as a result of the local trauma of childbirth, which is reinforced by multiple pregnancies. These include 'pubic scars' from the tearing of tendon insertions and periosteum around the pubic bone. The dorsal pubic surface and the pre-auricular sulcus are best indicators, but most authorities agree that it is not possible to determine the number of births from osteological appearances. The papers of Angel and of Ullrich are most useful in this respect.

ESTIMATION OF STATURE FROM SKELETAL REMAINS

When a full skeleton is available, then obviously direct measurement of the correctly assembled bones will give the original height within a few centimetres. Allowance has to be made during assembly, however, for the loss of cartilage in joint spaces and especially for missing intervertebral discs. The accuracy achieved with direct measurement is not great, in that even with an intact body there can be a lengthening of up to 2.5 cm compared with the live height. The skeleton needs scalp and heel soft tissue thickness added – and with the obvious uncertainty about the cumulative allowances for disc thickness and joint cartilage, it is unrealistic to expect accuracy of less than about 4–8 cm compared with the living height.

When incomplete skeletal material is available, calculations have to be made on the basis of one or more bones. Where possible, all available bones should be used and a consensus of results assessed, though the accuracy derived from different bones varies and the result from – say, a femur – is more reliable than that from an ulna. The descending order of usefulness is: femur, tibia, humerus, radius.

Many formulae have been constructed for the determination of stature from the length of long bones. The following cautions must be appreciated before they are used:

- The tables were constructed from differing ethnic groups and at different times, so that racial and nutritional factors introduce significant variations. The table most appropriate to the bones under investigation should be used, though by definition the exact provenance of these bones may be unknown, even including their ethnic origins.
- There is a marked sex difference in stature estimation and ageing of the person also reduces stature relative to long bone length. Trotter and Gleser (1958) found in 855 bodies that there was a 1.2 cm loss of height for each two decades of age over the age of 30, a loss of height equivalent to about 0.6 mm a year after the fourth decade. The same investigation showed that the length of the cadaver was about 2.5 cm longer than the known height during life. The maximum stature (at least in American men) was found in 1951 to be reached at the age of 23 years, a change from earlier estimates in which the peak was found to occur between 18–21 years of age.
- The bone lengths must be measured in exactly the same way as that used by the author of the tables.
- Old dry bones are slightly shorter than recent material, even when one excludes the loss of articular cartilage. Telkkä (1950) stated that 2 mm must be deducted from the length of fresh bone before the calculation is made, as most tables are based on dried skeletons. These differences, however, are slight compared with the greater errors likely if incorrect measuring methods are employed.
- There are inbuilt errors, which are expressed in the formulae. These standard errors are given as 'plus or minus' a certain figure, which applies only when the length of the bone is near the mean of the usual range of length for that particular bone. When the bone is near the extremes of the range (that is from a very tall or very short person), then the standard deviation must be doubled in order to stay within the same range of confidence of accuracy. The same holds good if the tables used are not from the same ethnic group as those

TABLE 3.6 *The stature tables of Trotter and Gleser. The upper table represents their original 1952 figures, the lower their modification of 1977, as quoted by Krogman and Iscan (1986)*

Male Whites	**Male Negroes**
Stature = 63.05 + 1.31 (femur + fibula) ± 3.63 cm	Stature = 67.77 + 1.20 (femur + fibula) ± 3.63 cm
Stature = 67.09 + 1.26 (femur + tibia) ± 3.74 cm	Stature = 71.75 + 1.15 (femur + tibia) ± 3.68 cm
Stature = 75.50 + 2.60 fibula ± 3.86 cm	Stature = 72.22 + 2.10 femur ± 3.91 cm
Stature = 65.53 + 2.32 femur ± 3.94 cm	Stature = 85.36 + 2.19 tibia ± 3.96 cm
Stature = 81.93 + 2.42 tibia ± 4.00 cm	Stature = 80.07 + 2.34 fibula ± 4.02 cm
Stature = 67.97 + 1.82 (humerus + radius) ± 4.31 cm	Stature = 73.08 + 1.66 (humerus + radius) ± 4.18 cm
Stature = 66.98 + (humerus + ulna) ± 4.37 cm	Stature = 70.67 + 1.65 (humerus + ulna) ± 4.23 cm
Stature = 78.10 + 2.89 humerus ± 4.57	Stature = 75.48 + 2.88 humerus ± 4.23 cm
Stature = 79.42 + 3.79 radius ± 4.66	Stature = 85.43 + 3.32 radius ± 4.57 cm
Stature = 75.55 + 3.76 ulna ± 4.72	Stature = 82.77 + 3.20 ulna ± 4.74 cm

Female Whites	**Female Negroes**
Stature = 50.12 + 0.68 humerus + 1.17 femur + 1.15 tibia ± 3.51 cm	Stature = 56.33 + 0.44 humerus – 0.20 radius + 1.46 femur + 0.86 tibia ± 3.22 cm
Stature = 53.20 + 1.39 (femur + tibia) ± 3.55 cm	Stature = 58.54 + 1.53 femur + 0.96 tibia ± 3.23 cm
Stature = 53.07 + 1.48 femur + 1.28 tibia ± 3.55 cm	Stature = 59.72 + 1.26 (femur + tibia) ± 3.28 cm
Stature = 59.61 + 2.93 fibula ± 3.57 cm	Stature = 59.76 + 2.28 femur ± 3.41 cm
Stature = 61.53 + 2.90 tibia ± 3.66 cm	Stature = 62.80 + 1.08 humerus + 1.79 tibia ± 3.58 cm
Stature = 52.77 + 1.35 humerus + 1.95 tibia ± 3.67 cm	Stature = 72.65 + 2.45 tibia ± 3.70 cm
Stature = 54.10 + 2.47 femur ± 3.72 cm	Stature = 70.90 + 2.49 fibula ± 3.80 cm
Stature = 54.93 + 4.74 radius ± 4.24 cm	Stature = 64.67 + 3.08 humerus ± 4.25 cm
Stature = 57.76 + 4.27 ulna ± 4.20 cm	Stature = 75.38 + 3.31 ulna ± 4.83 cm
Stature = 57.97 + 3.36 humerus ± 4.45 cm	Stature = 94.51 + 2.75 radius ± 5.05 cm

White males	SE	**Black males**	SE
3.08 Humerus + 70.45	4.05	3.26 Humerus + 62.10	4.43
3.78 Radius + 79.01	4.32	3.42 Radius + 81.56	4.30
3.70 Ulna + 74.05	4.32	3.26 Ulna + 79.29	4.42
2.38 Femur + 61.41	3.27	2.11 Femur + 70.35	3.94
2.52 Tibia + 78.62	3.37	2.19 Tibia + 86.02	3.78
2.68 Fibula + 71.78	3.29	2.19 Fibula + 85.65	4.08
1.30 (Femur + Tibia) + 63.29	2.99	1.15 (Femur + Tibia) + 71.04	3.53
1.42 Femur + 1.24 Tibia + 59.88	2.99	0.66 Femur + 1.62 Tibia + 76.13	3.49
0.93 Humerus + 1.94 Tibia + 69.30	3.26	0.90 Humerus + 1.78 Tibia + 71.29	3.49
0.27 Humerus + 1.32 Femur+ 1.16 Tibia + 58.57	2.99	0.89 Humerus – 1.01 Radius + 0.38 Femur + 1.92 Tibia + 74.56	3.38

White females	SE	**Black females**	SE
3.36 Humerus + 57.97	4.45	3.08 Humerus + 64.67	4.25
4.74 Radius + 54.93	4.24	3.67 Radius + 71.79	4.59
4.27 Ulna + 57.76	4.30	3.31 Ulna + 75.38	4.83
2.47 Femur + 54.10	3.72	2.28 Femur + 59.76	3.41
2.90 Tibia + 61.53	3.66	2.45 Tibia + 72.65	3.70
2.93 Fibula + 59.61	3.57	2.49 Fibula + 70.90	3.80
1.39 (Femur + Tibia) + 53.20	3.55	1.26 (Femur + Tib) + 59.72	3.28
1.48 Femur + 1.28 Tibia + 53.07	3.55	1.53 Femur + 0.96 Tibia + 58.54	3.23
1.35 Humerus + 1.95 Tibia + 52.77	3.67	1.08 Humerus + 1.79 Tib	3.58
0.68 Humerus + 1.17 Femur + 1.15 Tibia + 50.122	3.51	0.44 Humerus – 0.20 Radius + 1.46 Femur + 0.86 Tibia + 56.33	3.22

All lengths are in centimetres, valid only for Americans between 18 and 30 years of age. Femur and tibia are maximum lengths. SE, standard error.

being estimated. Krogman indicated that a 95 per cent confidence rate applies only if twice the standard error is accepted each side of the favoured height – in an average man, this means a latitude of over 12 cm, which is too great to be of much use in identification.

Of the many available systems of calculation, those of Trotter and Gleser are most widely used, being based on Caucasian and Negroid Americans from the 1950s (Table 3.6). Older tables include those of Rollet whose measurements of French people were later reworked by Manouvrier and

TABLE 3.7 *Pearson's (1899) regression tables for calculating stature from dried long bones*

S = 81.306 + 1.880 Femur	S = 72.844 + 1.945 Femur
S = 70.651 + 2.894 Humerus	S = 71.475 + 2.754 Humerus
S = 78.664 + 3.378 Tibia	S = 74.774 + 2.352 Tibia
S = 85.925 + 3.271 Radius	S = 81.224 + 3.343 Radius
S = 71.272 + 1.159 (F + T)	S = 69.154 + 1.126 (F + T)
S = 71.441 + 1.220 F + 1.080 T	S = 69.561 + 1.117 F + 1.125 T
S = 66.855 + 1.730 (H + R)	S = 69.911 + 1.628 (H + R)
S = 69.788 + 2.769 H + 0.1958	S = 70.542 + 2.582 H + 0.2818
S = 68.397 + 1.030 F + 1.557 H	S = 67.435 + 1.339 F + 1.027 H
S = 67.049 + 0.913 F + 0.600 T	S = 67.467 + 0.782 F + 1.120 T

TABLE 3.9 *Telkkä's table for calculating stature of Finnish men and women*

Men	SE	Women	SE
169.4 + 2.8 (Humerus – 32.9)	5.0	156.8 + 2.7 (Humerus – 30.7)	3.9
169.4 + 3.4 (Radius – 22.7)	5.0	156.8 + 3.1 (Radius – 20.8)	4.5
169.4 + 3.2 (Ulna – 23.1)	5.2	156.8 + 3.3 (Ulna – 21.3)	4.4
169.4 + 2.1 (Femur – 45.5)	4.9	156.8 + 1.8 (Femur – 41.8)	4.0
169.4 + 2.1 (Tibia – 36.6)	4.6	156.8 + 1.9 (Tibia – 33.1)	4.6
169.4 + 2.5 (Fibula – 36.1)	4.4	156.8 + 2.3 (Fibula – 32.7)	4.5

by Pearson and quoted in a review by Hrdlicka (1939). Pearson allowed a standard addition of 2.5 cm to compensate for the difference between dead and living height (Table 3.7). More modern tables include those of Dupertuis and Hadden (1951) and Trotter and Gleser (1958), from American subjects. The latter used casualties from World War II and later from the Korean War to construct their tables (Table 3.8). Other calculation systems include Breitinger (1937; Germans), Telkkä (Finns) (Table 3.9), Allbrook (1961; African Negroids and English), Shiati (1983; Chinese), Mendes-Correa (1932; Portuguese) and Stevenson (1929; Chinese). Modern critics of the accuracy of the estimation of stature from long bones include Wells (1959), who suggested that even the preferred method of Trotter and Gleser has less accuracy than is generally acknowledged.

Estimation of stature from bones other than the major limb bones is far more inaccurate. Measuring the spinal column (from the tip of the odontoid to the bottom of the fifth lumbar vertebra) has been used by Krogman and by Dwight; Fully and Pineau (1960) used the spine plus a long bone. Tibbetts (1981), in his more modern study on the spine, measured 23 individual vertebrae and produced a regression formula for both men and women. However, the results were far superior when long bones were used. Others have employed the clavicle (Jit and Singh 1956) and the scapula (Olivier 1969).

The use of fragmentary bones and those immature bones from which the epiphyses have been lost have been studied, the survey by Krogman and Iscan being the best account of the techniques employed by researchers such as Steele and McKern (1969) and Muller (1935). The estimation of the heights of infants and fetuses is even more difficult when working with skeletal material, as substantial parts of these bones may be detached and missing because of non-fusion of epiphyses and non-appearance of ossification centres. Mehta and Singh (1972) have specifically addressed this problem, as well as others summarized by Krogman and Iscan (1986).

ESTIMATING THE SUBJECT'S AGE FROM SKELETAL STRUCTURES

The age of the subject at death is usually more important than the stature and rivals the sex as the most vital indication

TABLE 3.8 *Dupertuis and Hadden's (1951) tables for estimating stature from bones. The length of the bones (measured in centimetres according to the authors' criteria) is multiplied by the factor in the table and added to the constant in the right hand column to give the body length (cm)*

Men	cm	Women	cm
2.238 (Femur)	+ 69.089	2.317 (Femur)	+ 61.412
2.392 (Tibia)	+ 81.688	2.533 (Tibia)	+ 72.572
2.970 (Humerus)	+ 73.570	3.144 (Humerus)	+ 64.977
3.650 (Radius)	+ 80.405	3.876 (Radius)	+ 73.502
1.225 (Femur + Tibia)	+ 69.294	1.233 (Femur + Tibia)	+ 65.213
1.728 (Humerus + Radius)	+ 71.429	1.984 (Humerus + Radius)	+ 55.729
1.422 (Femur) + 1.062 (Tibia)	+ 66.544	1.657 (Femur) + 0.879 (Tibia)	+ 59.259
1.789 (Humerus) + 1.841 (Radius)	+ 66.400	2.164 (Humerus) + 1.525 (Radius)	+ 60.344
1.928 (Femur) 0.568 (Humerus)	+ 64.505	2.009 (Femur) + 0.566 (Humerus)	+ 57.600
1.442 (Femur) + 0.931 (Tibia) + 0.083 (Humerus) + 0.480 (Radius)	+ 56.006	1.544 (Femur) + 0.764 (Tibia) + 0.126 (Humerus) + 0.295 (Radius)	+ 57.495

of identity. The estimation of skeletal age falls into various groups, which have marked differences in both method and accuracy. In general, the greater the personal age the less the confidence quotient. There are many publications on the subject, many of them arising from archaeological rather than forensic interest, as the age structure of a skeletal population is of great interest to social anthropologists and historians.



FIGURE 3.14 *Osteometric board for accurate measurement of bone length. There is a central slot in the headboard to accommodate the tibial head spines.*

The fetus and young infant

It is more usual to have to estimate fetal and neonatal age on the intact dead body, rather than the skeleton, as the immature bones are so easily dispersed, lost and destroyed compared to the more robust bones of older subjects. Both in archaeology and forensic pathology, however, such fetal and immature remains are sometimes present.

The major dating indices are the appearance of ossification centres in growing cartilage but, as stated above, these are rarely available in dried bones as the cartilage disintegrates within weeks or months and small ossification centres – both in diaphyses and epiphyses – rarely survive. The bones have to be examined with the cartilage still attached to offer much hope of ageing the remains. Radiology may provide more information than visual inspection.

Specialized books such as the classics by Fazekas and Kosa, Krogman and Iscan, and by Stewart and the numerous papers and monographs on the subject (a selection of which are listed at the end of this chapter) must be consulted where fetal issues are complex and important. Once again the help of interested anatomists and radiologists can be invaluable, especially as biological variation poses a constant trap for the inexperienced who slavishly follow printed tables without the knowledge to appreciate their limitations. Stewart has



FIGURE 3.15 *Dimensions of dried bones for estimations of stature (Trotter and Gleser, Dupertuis and Hadden). The right side bone is used for preference.* ***Femur:*** *With the bone lying anterior surface upwards, the maximum length is measured from the medial condyle to the most proximal part of the head.* ***Tibia:*** *Maximum length between tip of medial malleolus and face of lateral condyle. The intercondylar eminence is not included.* ***Humerus:*** *Maximum overall length from the posterior margin of the trochlea to the upper edge of the head.* ***Radius:*** *From the tip of the styloid process to the head, lying with the posterior surface upwards. All bones should be measured either with an osteometric board or, if one is not available, on a flat bench with the maximum lengths taken between two vertical, parallel boards placed in contact with the bone ends. If the bones are not dry, but have articular cartilage in place, the following should be subtracted from the measured length before applying the formulae (Boyd and Trevor): radius and humerus 3 mm each, tibia 5 mm and femur 7 mm.*

produced a useful nomogram that relates fetal femoral length to crown–rump length and hence to approximate gestational age. Teeth are discussed in Chapter 26. Fazeka and Kosa's book is particularly useful to the pathologist (as bone lengths, etc. are directly related to fetal and infant age), as are the profuse illustrations.

Skeletal age in the child and young adult

There is no break in the methods used for the fetus and small infant and the older child and young adult. The appearance of ossification centres is complete by around 5 years and after this stage the fusion of epiphyses acts as a calendar up to the age of about 25, when the medial clavicular epiphysis is usually the last evidence of such fusion.

Lists and diagrams such as those shown here are the usual method of tracing the maturity of the skeleton. Several cautionary points must be appreciated and where possible the advice of a radiologist be obtained if there are important issues at stake. The paper by McKern and Stewart gives a valuable commentary on personal variation in skeletal age determination (Table 3.10).

- Maturity is not synonymous with calendar age. There are both sexual, racial, nutritional and other biological variations.
- Females are almost always in advance of males, and maturity tends to be accelerated in hotter climates, though the latter may be tempered by nutritional disadvantages.
- There is a marked range of closure dates in epiphyseal union, and the year suggested in some charts is merely the midpoint of that range.
- Union is a process, not an event. It may be different radiologically from gross inspection; it may also be slow in completion, so that it may be difficult to pinpoint a date that is needed to refer to published data. An example is the one that is usually the last to fuse, the medial end of the clavicle, which may slowly close during any period from about 18 to 31 years. Finally, as emphasized by Krogman and Iscan, multiple criteria of skeletal age should be used, dependence not being placed upon any single measurement.

Skeletal ageing in later years

The eruption of the third molar teeth and the fusion of the last epiphysis occurs approximately in the middle of the third decade. This is a watershed in skeletal dating, as the more objective markers of age are almost all on the younger side of this time. From around 25 years until old age, there are no dramatic events such as tooth eruption or the appearance of ossification centres. There are more subtle changes available for specialized interpretation, but the general decline through middle age to senility prevents assessment of age to within the nearest half-decade.

The major advances in this difficult period have been the use of the pubic symphysis and sternal ribs and the radiology of cancellous bone. However, dental technology may further refine the assessment of age.

Pubic symphysis and age

The opposing faces of the two pubic bones have been extensively studied by Todd (1920, 1921), by McKern and Stewart (1957) and by Gilbert and McKern (1973), who related the changing topography of the symphyseal faces to age. The technique is complex and requires bones that are free of cartilage, but not so eroded by drying and damage that the surface features are blurred.

ASSESSMENT OF AGE FROM THE MALE PUBIC SYMPHYSIS

As always, the details given in the original publications should be studied and practice gained by examining bones of known age. The method as originally devised by Todd has been radically modified by McKern and Stewart so that the technique is now the most useful in assessing the age of post-mature material. It must be noted that their method applies only to males and was not applied to female material until the work of Gilbert and McKern.

In summary, the face of the symphysis is analysed by reference to three 'components', each being scored on a scale of 6. In component I, the dorsal half of the face is assessed on a scale of 0–5; in component II, the ventral half is assessed; and in component III, the whole surface is considered in relation to different criteria to the preceding two stages.

Component I (the dorsal plateau) is scored as follows:

- 0: dorsal margin absent
- 1: slight margin formation appears in the middle third of the dorsal border
- 2: dorsal margin extends along whole dorsal border
- 3: grooves filled in with resorption of ridges to form an early plateau in the middle third of the dorsal demiface
- 4: te plateau, still with vestiges of billowing, extends over most of the dorsal demiface
- 5: billowing vanishes and the surface of the demiface becomes flat and slightly granular.

TABLE 3.10 *Time of appearance of major ossification centres*

(a) Healthy Caucasian boys

Birth
Calcaneus
Talus
Femur, distal
Tibia, proximal
Cuboid
Humerus, head

2 months
Capitate
Hamate
Lateral cuneiform

3 months
Femur, head
Capitulum
Tibia, distal

6 months
Fibula, distal

7 months
Humerus, greater tuberosity
Radius, distal

10 months
Triquetrum

11 months
Third finger–first phalanx
First toe–second phalanx

12 months
Second finger–first phalanx
Fourth finger–first phalanx
First finger–second phalanx

13 months
Third toe–first phalanx
Second metacarpal
Medial cuneiform

14 months
Fourth toe–first phalanx
Second toe–first phalanx
Fifth toe–second phalanx

15 months
Third metacarpal
Second toe–second phalanx
Fifth finger–first phalanx

16 months
Fourth toe second phalanx
Fourth metacarpal

18 months
Second finger–second phalanx
Third finger–second phalanx
Fourth finger–second phalanx
Fifth metacarpal

20 months
First toe–first phalanx
Middle cuneiform

21 months
Third finger–third phalanx
Fourth finger–third phalanx
Navicular of foot
Fifth toe–first phalanx

22 months
First metacarpal
First metatarsal

23 months
First finger–first phalanx

2 years
Fifth finger–second phalanx
Lunate

2 years, 2 months
Second metatarsal

2 years, 5 months
Second finger–third phalanx
Fifth finger–third phalanx

2 years, 11 months
Third metatarsal
Fibula, proximal

3 years, 1 month
Femur, great trochanter
Patella

3 years, 3 months
Fourth metatarsal

3 years, 4 months
Fifth toe–third phalanx

3 years, 7 months
Third toe–third phalanx
Fourth toe–third phalanx

3 years, 8 months
Fifth metatarsal
Second finger–third phalanx

3 years, 10 months
Radius, proximal

4 years, 2 months
Multangulate majus

4 years, 4 months
Navicular, hand

4 years, 8 months
Multangulate minus

5 years+
Humerus, medial epicond
Ulna, distal
Fifth toe–second phalanx

(b) Healthy Caucasian girls

Birth
Calcaneus
Talus
Femur, distal
Tibia, proximal
Cuboid
Humerus, head

2 months
Capitate
Hamate
Lateral cuneiform

3 months
Femur, head
Capitulum
Tibia, distal

4 months
Humerus, greater tuberosity

6 months
Fibula, distal
Radius, distal

7 months
First toe–second phalanx
Third finger–first phalanx
Fourth finger–first phalanx

8 months
Second finger–first phalanx
First finger–second phalanx
Third toe–first phalanx

9 months
Third toe–second phalanx
Fourth toe–first phalanx
Medial cuneiform

10 months
Second metacarpal
Second toe–second phalanx
Fourth toe–second phalanx
Third metacarpal
Second toe–first phalanx
Triquetrum

11 months
Fourth metacarpal
Fifth finger–first phalanx

12 months
Fourth finger–second phalanx
Third finger–second phalanx

13 months
Fifth metacarpal
Second finger–second phalanx

14 months
First metacarpal
First toe–first phalanx
Fifth finger–first phalanx
Third finger–third phalanx
Fourth finger–third phalanx
Navicular of foot
Middle cuneiform
First metatarsal

15 *months*
First finger–first phalanx
Fifth finger–second phalanx

17 months
Second finger–third phalanx
Fifth finger–third phalanx

19 months
Second metatarsal

21 months
Fifth toe–third phalanx

22 months
Third metatarsal

23 months
Patella

2 years
Lunate
Third toe–third phalanx
Fourth toe–third phalanx
Fibula, proximal
Femur, greater trochanter

2 years, 2 months
Second toe–third phalanx
Fourth metatarsal

2 years, 5 months
Fifth metatarsal

2 years, 8 months
Multangulate majus

2 years, 9 months
Humerus, medial epicon

3 years
Radius, proximal
Multangulate minus

3 years, 2 months
Navicular, hand

4 years, 6 months
Ulna, distal

5 years+
Fifth toe–second phalanx

After Francis and Werle (1939).

Component II (the ventral rampart) is scored as follows:

- 0: no ventral bevelling
- 1: ventral bevelling only at the superior end of the ventral border
- 2: bevelling extends along whole ventral border
- 3: ventral rampant starts as bony extensions from either or both extremities
- 4: extensive rampart, but still gaps, especially on the upper two thirds of the ventral border
- 5: complete ventral rampart.

Component III (symphyseal rim) is scored as follows:

- 0: no symphyseal rim
- 1: partial dorsal rim visible, usually at the upper end of the border; it is round, smooth and elevated above the surface
- 2: complete dorsal rim with beginnings of ventral rim, which starts at no particular site
- 3: complete circumferential symphyseal rim, enclosing a finely grained, slightly undulating surface
- 4: the rim begins to break down, no longer smooth but sharply defined. Some lipping on ventral edge
- 5: further breakdown of rim, especially along superior ventral edge. Rarefaction of symphyseal face. Disintegration and erratic ossification of ventral rim.

In practice, a three-figure score is made from evaluation of each component and added together. For example, component I = 3, component II = 4, component III = 1. Thus the score is 3 + 4 + 1 = 8 and by reference to the tables, the age suggested is between 24 and 28.

Since the work of Gilbert and McKern, a method has been offered to assess age in both males and females. Stewart has pointed out that, although Todd felt that the same criteria could be applied to females, there was risk of overestimation of age in women because pelvic trauma during parturition could deform the dorsal border of the symphysis in a manner likely to mimic age changes.

The other limitation of the method is that the upper limit is 50 years, so that a large segment of the range is not considered. Also the scoring is naturally subjective, depending on the experience and training of the observer. In spite of these drawbacks, the method remains the most useful ageing technique for post-mature males.

Gilbert and McKern established standards for females in 1973. The same three components are used, but the description of the symphyseal faces is different. Details must be sought in the original publications or in Krogman and Iscan's invaluable book. Gilbert concluded that, if the male criteria were used for females, the age assessment would be underestimated by about a decade, as the female pubis reaches full maturity about 10 years later than the male.

Several tests of the accuracy of this method have been made by Suchey (1979) and Meindl *et al.* (1985). There have been many reports on the subject, but it would seem that Todd's system remains the most accurate. Overall accuracy obtained by experienced observers lies in the range of 5–7 years around the true age.

The sternal rib methods

The costochondral junction has been studied by a number of physical anthropologists using different techniques. Michelson (1934) found that calcification in the first costal cartilage did not occur under 11 years and that after 16 years, males calcified much more quickly until 66, when the sexes again became uniform. Iscan and Loth (1986) made detailed studies of the shape of the rib end adjacent to the cartilage and constructed complex criteria for age-related changes. The original publications must be consulted for details as well as more recent developments such as those by Loth, Iscan and Sheuerman (1994).

Skull sutures and age

The use of skull suture fusion as an index of age has had a chequered history, beginning in the first century AD with a comment by Celsus. It is now generally discredited, except in the most broad terms.

It is common knowledge that most adults have at least part of their suture lines closed and that this tends to become more widespread as age increases. There are many exceptions and the rate of closure is not linear with time. This generality can be useful when skull fragments are found, as any visible fusion will at least indicate that the skull came from a mature individual, as it is unlikely below the age of 20 (Brothwell).

The claims of Dwight (1890), Parsons and Box (1905) and Todd and Lyon (1924, 1925) (who stated that sagittal fusion began at 22 and was complete by 35) for the use of fusion as an ageing tool, have been refuted by Singer (1953), Cobb (1952), McKern and Stewart (1957) and Genovés and Messmacher (1959). McKern and Stewart found that 25 per cent of 18-year-old males had begun closure of their sagittal sutures and that by 31–40 years, 90 per cent had some fusion. Yet many had no fusion at considerably older ages. Since these criticisms were made, much further work has been carried out, recorded by Krogman and Iscan's book in its 1986 edition. They concluded from the accumulated evidence of many publications that suture closure is not affected by sex, race or right/left differences. Only endocranial fusion must be studied, as that on the outer side is far more erratic. Even so, determination of age from suture closure is unsafe: they feel that in the 20–50 age range, it may be possible to



FIGURE 3.16 *A guide to the age of epiphyseal union in the major centres. The commencement and completion of union takes several years. The table is only a guide for male subjects (female slightly earlier) in non-tropical climates; the two dates are partial and complete union (years).*

Head of femur	16–19	Acromion	17–19
Greater trochanter	16–19	Distal femur	17–20
Lesser trochanter	16–19	Proximal tibia	17–19
Head of humerus	16–23	Proximal fibula	16–21
Distal humerus	13–16	Distal tibia	16–19
Medial epicondyle	16–17	Distal fibula	16–19
Proximal radius	14–17	Metatarsals	15–17
Proximal ulna	14–17	Iliac crest	18–22
Distal radius	18–21	Primary elements pelvis	14–16
Distal ulna	18–21	Sternal clavicle	23–28
Metacarpals	14–17	Acromial clavicle	18–21

place a skull within the correct decade only, older material being even more variable.

The basisphenoid synchondrosis cannot be included in this class, as its fusion is a relatively reliable indicator of a minimum age of about 20 years. The metopic suture, between the two halves of the frontal bone, usually closes at about 2 years of age, but occasionally persists into adult life.

Radiology can also assist in the determination of age, from the internal structure of the cancellous bone and cortical thickness of the head of the humerus, for example. Schranz (1959) developed a combination of external visual examination and radiographic features, indicating that the head of the humerus was a better determinator than the corresponding part of the femur. He produced a list of criteria that helped to age a skeleton from about 15 years of age up to one in excess of 75. This was pursued by Nemeskeri and later by him in conjunction with Acsadi (Acsadi and Nemeskeri 1970), to include the proximal parts of both humerus and femur, taking into account the radiological thinning of the cortex and the progressive rarefaction of the apex of the medullary cavity in the head of the bone. The original papers or their full synopsis in Krogman and Iscan's book must be consulted for details.

Histological structure has also received attention and remodelling of Haversion systems seem potentially useful



FIGURE 3.17 *The interpretation of cranial suture closure as an index of age is fraught with error. This person was 23 of age and, as would be generally expected, no segments of fusion are shown on the exterior of the skull.*



FIGURE 3.18 *Degenerative disease can assist in providing a general estimate of age, or at least exclusion of younger age groups. This grossly arthritic humerus assisted in distinguishing the near-skeletalized bodies of a 66-year-old man and his 22-year-old son.*

for the estimation of personal age. Eriksson and Westermark (1990) have claimed that amyloid inclusions in the choroid plexus can be used as a simple technique.

Chemical methods for assessing personal age lie partly within the field of forensic dentistry, such as the racemization of amino acids in teeth. This has also been applied to bone and depends upon the progressive conversion with advancing age of aspartic acid from the dextro- to the laevo-isomer (Ohtani 1994; Ritz *et al.* 1994).

DETERMINATION OF RACE FROM SKELETAL REMAINS

This is more difficult than any of the preceding investigations, partly because racial traits are not so marked and partly because so much ethnic mixing has taken place, especially in the large-scale immigrations into Europe and North America in recent years.

As usual, those at the extreme ends of the osteological range present little difficulty, as Brothwell (1972) remarks when comparing Eskimos with Australian Aboriginals. Unfortunately, there is a large proportion of racially neutral skeletal material and also some that presents apparently classical racial features but turns out to be totally atypical, so providing a quite incorrect diagnosis. The following criteria are offered, but the usual warnings about dogmatic opinions are even more important in this field.

There are three main racial groups: Caucasian, Mongoloid and Negroid. All others are derived from these and skeletally cannot be distinguished, though when archaeologists and anthropologists are working within a major race, there may well be local criteria that can distinguish racial subgroups with varying degrees of confidence. Most work has been performed in North America and thus most available data are derived from Caucasian and Negroid Americans, and Native Americans.

The skull offers the best evidence on racial origins; Krogman and Iscan claimed that race can be determined in 90–95 per cent of cases. The mandible is excluded from this, apart from the teeth, which will be dealt with in another chapter. It may be mentioned here, however, that one of the most useful pointers to a Mongoloid skull is the present of posteriorly concave, ‘shovel-shaped’, upper incisors, which may be grooved on the rear surface. These were found by Hanihara (1967) to be present in up to 93 per cent of Japanese, 85 per cent of Chinese and 68 per cent of Eskimos, being absent in Caucasians and occurring in only up to 15 per cent in Negroid Americans.

The wide zygomatic arches that give the typical high-cheekboned features of the Mongoloid races can sometimes produce a skull in which, uniquely, the transverse facial width is greater than the width of any other part of the head. Krogman provides a useful table (Table 3.11), outlining the major racial differences in the skull. Elsewhere he subdivides the Caucasian group into its three main subgroups: Nordic, Alpine and Mediterranean. He points out once again that these describe the ‘stereotypes’ of each group and that there is an extensive grey zone of more neutral characteristics. Subjects in the Negroid group tend to be long headed (dolichocephalic) and broad headed (brachycephalic) in the Mongoloid group, with the whole range occuring in the Caucasian group. The Negroid orbit is lower and wider, compared with the higher, rounder eye socket of the Mongoloid. The Negroid nasal aperture is wide, and the prognathism of the lower face and jaw relatively marked.

There are racial differences in the pelvis, but specialized measurements as described by Todd and Lindala (1928) must be made in order to detect these. Iscan suggests that a 79–83 per cent success rate can be achieved in differentiating between Caucasian and Negroid subjects (see References and further reading). The long bones offer some assistance, especially the femur. This is straighter in Negroid groups, the anteroposterior bowing being less. Together with other long bones, especially those of the lower limb, Negroid bones are longer than those of Caucasian or Mongoloid skeletons, even for equal total body length, the leg proportions being greater. The radius and tibia are relatively longer (Table 3.12). Several writers offer various indices of relative bone lengths, such as those of Modi (1957), Munter (1936) and Schultz (1937). The scapula has been extensively studied, but seems a poor discriminator of race.

TABLE 3.11 *General racial features in the skull (after Krogman 1939)*

Feature	White ('Caucasoid') (excluding Alpine)	Negroid	Mongoloid
Height of skull	High	Low	Medium
Length of skull	Long	Long	Long
Breadth of skull	Narrow	Narrow	Broad
Breadth of face	Narrow	Narrow	Wide
Height of face	High	Low	High
Sagittal contour	Rounded	Flat	Arches
Nasal opening	Narrow	Wide	Narrow
Orbital opening	Angular	Rectangular	Rounded
Lower nasal margin	Sharp	Troughed	Sharp
Nasal profile	Straight	Slanted down	Straight
Palatal shape	Narrow	Wide	Medium

PERSONAL IDENTITY FROM SKELETAL MATERIAL

After the general groups of race, sex, stature and age have been investigated, the bones must be examined for any idiosyncratic features that give them a personal identity. This is invariably a matter of matching up such feature(s) with known pre-existing conditions, and depends upon a potential match being available. Circumstances are infinitely variable and the ways in which this suspected matter comes to the examiner's knowledge are legion. Sometimes there may be one 'good bet' and, indeed, the potential identity may be virtually certain from the circumstances, the anatomical confirmation being almost a formality. In

TABLE 3.12 *Selected anthropometric dimensions (mm) in White and Black* Americans*

	Men				Women			
	White		Black		White		Black	
	Mean	SD	Mean	SD	Mean	SD	Mean	SD
Body								
Stature	1706	60.5	1744	60.8	1597	78.1	1586	64.9
Total arm length	760	30.2	798	41.2	695	38.1	713	32.7
Upper arm length	333	16.4	340	21.9	302	22.8	303	15.6
Forearm length	249	12.4	269	15.0	225	16.7	237	14.7
Hand length	187	9.3	199	12.3	172	11.3	179	10.2
Leg length (anterior supine)	938	40.0	984	49.1	871	51.2	892	41.8
Thigh length	497	24.3	515	27.5	461	31.6	467	24.9
Lower leg length	376	19.8	401	23.7	352	25.8	365	19.8
Foot length	244	11.9	256	13.9	215	13.6	231	11.8
Bi-iliac breadth	292	16.9	270	16.5	287	22.5	267	24.7
Bi-spinous breadth	246	17.2	227	18.1	242	25.1	220	22.5
Head								
Maximum length	188	7.5	193	6.1	182	6.5	186	7.7
Maximum breadth	154	6.5	149	6.1	145	5.6	144	6.2
Auricular height	120	5.1	124	5.3	118	5.3	120	4.8
Face								
Bizygomatic breadth	139	6.7	139	6.1	130	7.0	132	8.7
Mandibular breadth	110	7.4	109	8.7	103	8.9	105	11.9
Interocular breadth	33	3.5	35	2.7	31	2.8	34	2.3
Total morphological height	122	9.7	125	7.6	113	9.5	116	11.6
Upper face height	69	6.3	71	5.6	66	6.2	67	4.5
Nasal height	54	4.7	52	4.8	52	3.8	50	4.4
Nasal breadth	35	3.7	43	3.7	32	4.9	40	4.1

*From Todd and Lindala (1928). Compiled by Krogman and Iscan (1986).



FIGURE 3.19 *Identification of a homicide victim, buried for almost 2 years in a garden, was achieved by matching this callus from a previous femoral fracture, with the medical notes and radiographs obtained from a hospital. The shape and size of the callus, together with the osseous spur due to muscle traction, was identical to follow-up films taken during life.*



FIGURE 3.20 *Identification of a skeletalized body was achieved by matching this callus from a previous ulnar fracture, with the medical notes and radiographs obtained from a hospital. The shape and size of the callus, was identical to follow-up films taken during life.*

other cases there may be a list of hundreds of potential cases to search through in the hope of finding a match.

Individual characteristics may be of two main types.

- Anatomical shapes that can be matched by radiology, measurement or other means. Examples would be frontal sinus comparison, craniometry and radiological bone architecture.
- Discrete abnormalities such as healing fractures, metal prostheses, bone disease or congenital defects. Some artefacts, such as drill holes or wire, may immediately indicate that the bone is an anatomical specimen.

Anatomical matching depends upon accurate and detailed information about the living subject who is thought to correspond with the skeleton. Such information is usually radiographic and is derived from clinical records. The examples par excellence are dental charts and radiographs obtained from the dentist of the potential match; this is discussed in Chapter 26. Where skull films are available from ante-mortem sources, identity can be almost assured. The lateral view of a head can be matched with similar views taken of the skull, and both obvious anatomical landmarks compared and cranial measurements taken. The matter is further discussed later in relation to radiology, but the profile of the pituitary fossa as well as various intracranial diameters can rapidly exclude a match. In fact, a cursory glance can often confirm that the two skulls are dissimilar; making a positive correlation takes more time and requires accurate orientation of the radiographs.

Frontal sinus identification

This has been extensively studied since Schuller suggested the technique in 1921, as it is particularly useful in mutilated or burnt bodies, such as those from mass disasters like air crashes. The sinuses are well protected from all but the most extreme damage and are unique in that – as first pointed out



FIGURE 3.21 *Personal identity of this almost skeletalized fire victim was established from this healed callus on the tibia, the site of a well-documented fracture several years before death.*

by Poole in 1931 – no two persons (not even identical twins) have the same profile of these air spaces. They appear in the second year of life and increase in size for the first two decades. They are absent in about 5 per cent of persons and unilateral in another 1 per cent. For the sinuses to be used, an ante-mortem anteroposterior skull radiograph must be available, the most common source being from a previous hospital admission or examination, usually for a head injury. The cadaver skull or head must be X-rayed in exactly the same orientation and degree of enlargement, so that some superimposition technique can be employed. The 'forehead–nose' position was recommended by Schuller (1943), with the tube axis positioned level with the supraorbital margins. The scalloped upper margins of the sinuses are used for comparison, these being smaller and more numerous in the female. Asherson's thesis of 1965 recommends using the Caldwell occipitomental plane for the radiographs, used clinically for investigation of the nasal sinuses. This is preferable to the Wallers occipitofrontal view and the two projections are not necessarily identical in terms of sinus profile. Asherson recommends outlining the sinus shape in black ink on the film or tracing it onto a sheet of paper. Turpin and Tisserand (1942) projected their films on to a cardboard screen and cut out a template, weighing these from both ante- and post-mortem films to determine whether they were identical. Computed tomography of the sinuses is recommended by Reichs (1993).

Other radiological methods of comparing identity include matching of hand and wrist films, matching the profile and structure of the first rib and clavicle, and the craniometric methods of Sassouni (1959) and of Voluter (1959). The methods must be sought in either the original papers or surveys such as the textbook by Evans and Knight (1983). However, in general, it may be said that, wherever ante-mortem X-rays are available, especially of skull, thorax, hip or shoulder, then radiological comparisons of the dead material can almost always exclude an identity and, in many circumstances, can confirm it.



FIGURE 3.22 *The facial and cranial skeleton is unique to every person. If ante-mortem radiographs can be obtained for the person likely to be the victim, matching of the frontal sinus pattern can provide absolute identification. This body, which was washed up on the beach, was eventually matched with hospital radiographs through the sinus pattern seen at the top edge of the picture.*

THE DATING OF SKELETAL REMAINS

One of the issues in identity, as well as in estimating the time since death, is the date (as opposed to the age) of human bones. A knowledge of the time of death, measured in years, decades or even centuries, can assist the investigating authorities considerably. In fact, where skeletal remains are shown to be of considerable antiquity, no investigation at all is required, as even if the death was criminal, the culprit may long since have died. This threshold of investigative interest lies at around 70 years and material older than this may be of concern only to historians and archaeologists.

It is the marginal cases that present difficulties, especially as the methods of dating in this period are so approximate. For example, the skeleton shown in Figure 3.6 was discovered 41 years after the woman had been murdered. When the police went searching for the suspected killer, they found that he had died peacefully 3 years before the discovery, of coronary disease – thus qualifying for the 'perfect murder'.

The major problem in dating bones is that the environment is far more potent than time in changing the state of the bone. In Wales, a historic country where a spectrum of skeletal material has been found dating back some 18 000 years, frequent opportunities present for examining bones from many periods and many conditions of environment. Some Roman or even Bronze Age material, which had been concealed in dry sand dunes or in well-drained ancient burial mounds, appeared almost as pristine as an anatomical demonstration skeleton. On the other hand, modern material buried in coffins in graves marked with headstones only 20 years old have completely vanished because acidic, peaty water repeatedly eluted the bone as the water table in marshy ground rose and fell. An even more striking demonstration of the effect of local conditions was the observation that some limb bones buried vertically in a rock fall in a cave were in excellent condition at the upper ends, yet the lower parts were totally eroded where they had been surrounded by damp rubble.

These facts emphasize that vast errors can be made in dating bone merely by the gross morphological appearances and – as is so often the case – the less experienced the examiner, the more dogmatic his incorrect opinions are likely to be. The following schedule can therefore be nothing more than a rough guide, which must be modified where possible, by a knowledge of the environment in which the bones lay. Certain physicochemical tests are of assistance, but even these are themselves dependent on the environment, with the exception of radiochemical tests that are of little value in the period of forensic concern.

Physical appearance

Recent bones will have soft tissue remnants adhering, in the form of tendon and ligament tags, especially around the joint ends. Periosteum may be visible as fibrous material closely adherent to the shaft surface. Cartilage may also be present on articular surfaces. The time for which these remnants persist is variable, according to the conditions in which the bone has been left. Animal predators may rapidly remove all soft tissue and cartilage, sometimes within days or weeks. If the body has been left in a protected place, such as a vault or closed building, then dried tissue can remain for many years. In temperate climates, bodies left out in the open usually become substantially skeletalized within the first year, though tendon tags and periosteum may survive for 5 or more years. If a body dies in the autumn, then the preservation is likely to be longer through the colder winter months than if it died in the spring or summer.

After all soft tissue has vanished, recent bones may still be differentiated from old material by the density and feel of the bone. For a variable period, depending on storage conditions, a bone will feel slightly greasy to the fingers for several years, sometimes up to a decade if kept indoors. It will also feel heavy compared with older skeletal material because of the preservation of the organic stroma. On sawing a recent bone, it will be hard (especially the shafts of limb bones such as the femur) and will be uniform through the whole thickness. A smell of burning organic tissue will be obvious if vigorous sawing produces heat. In an old bone, the loss of the collagenous stroma will lighten the bone and make it easier to cut. The outer cortex and – to a lesser extent – the zone around the marrow cavity, will lose the stroma first, so a 'sandwich' effect may be seen in which a central ring of hard collagenous bone is layered on each side by a zone of more porous, crumbling material. This is not seen in less than several decades – and sometimes centuries – unless the bone has been exposed to the sun and other elements. The fragile, brittle appearance of old bones is usually first apparent on the ends of long bones, adjacent to the joints, such as the tibial plateau or the greater trochanter of the femur. This is often because the outer layer of compact bone is thinner there than in the shaft, so that the soft cancellous bone of the extremities is more readily exposed. This occurs within a few decades if the bone has been outside, but may not develop for a century in protected material. The aged cortex will feel rough and porous and, in really old material, can be crumbled or pitted with a fingernail.

Another factor that markedly affects the rate of decay of bones is the size and type of the bone itself. Whilst thick, dense bone, such as femoral or humeral shaft, may last for centuries, smaller and thinner items may disintegrate rapidly. Skull plates, tarsal and carpal bones, digits and the thin bones of the facial skeleton will rot more quickly, as will the small bones of fetuses and infants.

Physical tests

In parallel with the physical appearance of the sawn bone, fluorescence in ultraviolet light can be a useful preliminary test. If a shaft is cut across and inspected in the dark under ultraviolet light, such as that from a Wood's lamp, recent bone will shine with a silvery-blue tint right across the whole section. As the bone ages, the outer rim will cease to fluoresce and this will progressively deepen towards the centre. As with visual and tactile examination, a similar zone will work its way outwards from the marrow cavity until only a thin sandwich-filling will survive. This then fragments and eventually vanishes so that all the cut surface is non-fluorescent. The time that this process takes is variable, but total loss of ultraviolet fluorescence takes somewhere of the order of at least 100–150 years to complete. Other physical tests have been described, including density and specific gravity measurements, ultrasonic conduction and thermal behaviour when heated under special conditions. All these criteria depend on the loss of organic stroma and the development of a calcified matrix with a porous structure.

Serological and chemical tests

Positive tests for the presence of haemoglobin may be obtained for a variable time on either the bone surface or powdered bone, this being partly dependent on the sensitivity of the technique. Using the dye-peroxide methods (benzidine is most sensitive, but is now proscribed by Health and Safety regulations, so that the less satisfactory Kastel–Meyer test must be used), positive results may be obtained up to about 100 years.



FIGURE 3.23 *Fluorescence of bone in ultraviolet light as a function of time since death. A freshly sawn cross-section of a dense bone such as femoral shaft is to be preferred. Up to several decades after death the whole cut surface fluoresces a bluish colour (a). From 3 to 80 years, greatly depending upon the environmental conditions, the outer zone and the zone around the marrow cavity progressively lose fluorescence (b). After a century or more, the residual fluorescence contracts to a narrowing central sandwich (c) before vanishing completely in the second century. Other methods of attempted dating include microscopic examination. Yoshino* et al. *(1991) claim that microradiography and electron microscopy reveal vacuoles in compact bone left in soil for 5 or 6 years.*

Serological activity lasts only a short time in bones exposed to the weather. Bone powder eluted with weak ammonia and vacuum concentrated, may give a positive reaction with antihuman sera, such as Coombs reagent, for only about 5–10 years – again depending greatly on the environmental conditions.

The recent development of DNA techniques has led to both bone and bone marrow being used to produce profiles for identification. There seems to be a wide range of times during which this is successful. The author (BK) dealt with a case where DNA testing was successful after 8 years' burial, but other more recent skeletons did not yield such success. However, far older archaeological material has given DNA profiles, so, at present, the DNA criteria cannot be used for dating.

Chemical testing seeks to measure the degradation of the proteinous stroma, so knowing the total nitrogen and amino acid content can be useful. Fresh compact bone contains about 4.5 per cent nitrogen, which progressively diminishes with time. If a bone contains more than about 4 per cent nitrogen, it is unlikely to be older than 100 years, but if it has 2.5 per cent or less, it is likely to be older than 350 years.

Estimation of the racemization of amino acids in teeth (laevo/dextro proportions) is being used to determine age, and there is some evidence that it also changes linearly with post-mortem interval. Its use on skeletal structures other than teeth is being investigated.

Residual protein can be converted to its constituent amino acids by prolonged heating in 6 M hydrochloric acid. The digest can then be analysed, either by autoanalytical methods or by two-dimensional chromatography. Fresh bone contains about 15 amino acids, mostly derived from collagen. Glycine and alanine are predominant, but proline and hydroxyproline are more specific markers for collagen. The latter two tend to vanish in about 50 years (as always, depending on the storage environment), so they are useful markers for the time threshold of forensic relevance. The other amino acids diminish over the succeeding scores and hundreds of years, so that a bone containing only four or five amino acids is likely to be relatively ancient. Glycine persists for millennia, being found in palaeolithic material.

Paradoxically, the methods available for archaeologists to use on ancient skeletal remains are proportionately more accurate, but of little or no use in forensic science. The radiocarbon test, which measures the loss of carbon-14 after death, cannot be applied to material less than a couple of centuries old, as the loss of radioactive carbon, which has a half-life of



FIGURE 3.24 *Graphical summary of the criteria for estimating the approximate date of human skeletal remains.*

well over 5000 years, is too small to be measured in the half-century or so that interests the forensic pathologist.

Another radioisotope technique is the subject of current research at Aberdeen University, where Maclaughlin-Black *et al.* (1992) are measuring radiostrontium in skeletal remains, the principle being that pre-1945 bones should be free of endogenous strontium-90, derived from nuclear weapons and atmospheric tests, which was at a maximum in the environment in the early 1960s. The possibility exists that atmospheric contamination with other isotopes laid down in bone from dated tests and nuclear accidents may provide a profile that could bring forward the latest date during which the person must have been alive.

PHOTOSUPERIMPOSITION TECHNIQUES FOR IDENTIFICATION

Where potential candidate(s) for the identity of a skull are known to the investigating authority and photographs taken during life are available, a well established technique used for identification is ‘photosuperimposition’. In this method, photographs of the skull are taken in exactly the same orientation in three planes as the available photograph. These are then enlarged to exactly the same dimensions as the photograph, and either the negative or a positive print is made on transparent film. This is then laid over the photograph and adjusted in an attempt to match up the major anatomical landmarks such as nasion, supraorbital ridges, angle of the jaw, nasal aperture, external auditory meatus and, especially, teeth. The actual anatomical markers will depend on what is visible, in frontal, lateral or oblique views. The test is mainly an exclusory one, in that, if the match cannot be made, then the skull is not that of the person in the photograph. If the match is good, even excellent, then the two could be the same person, though the standard of proof is low unless some individualistic feature, such as a distinct dental character, is apparent.

The photofit method has been used for many years, one of the most familiar examples being that reproduced in many forensic textbooks, of the skull and face of the wife of Dr Buck Ruxton, a notorious murder in 1935 investigated by Glaister and Brash in Scotland.

A more modern variant of the photosuperimposition technique is with the use of video cameras where two images, one of the photograph and the other of the skull, are mixed on one video display unit. By altering the camera angles and the degree of magnification of the images, superimposition can be tested quickly without the need for laborious photographic processing. This method was used in 1994 to identify a number of the 12 victims of the notorious ‘House of Horror’ in Gloucester. This is a rapidly developing field of forensic interest, where even the relatively poor-quality images from security cameras can be matched with suspects.

RECONSTRUCTION OF THE FACIAL APPEARANCE FROM THE SKULL

The reconstitution of the visage from the skeletal base has been a goal for workers in many different fields in recent years. The advantages of such a technique are obvious as, when a skull is discovered one prime method of identification would be a reliable reconstruction of the face, so that direct recognition could be obtained from relatives, friends and photographic records.

The first methods were as much artistic as scientific and depended to a great extent on the sculpturing ability of the operator. Gerasimov (1971) was a Soviet pioneer of this method, though much of his work was archaeological and historical, rather than forensic.

The method depends on a pre-knowledge of the usual tissue thickness at a multitude of points on the normal skull, an anatomical exercise that now has quite a large database. Modelling clay is laid on to the unknown skull in layers corresponding to these standard thicknesses, then more imaginative modelling added to ‘humanize’ the basic shape. The obvious defects in this technique are the lack of knowledge about eyes, lips, nose, ears and head hair, all of which contribute greatly to individual characteristics. Similar methods have been used by graphic artists, rather than sculptors, who use their portraiture talents to create a face on the two-dimensional base provided by the skull profile, plus a knowledge of tissue thicknesses at many anatomical points. Additional information has been provided on tissue thicknesses by radiography of heads.

The method was used with success in the 1988 investigation of the murder of Karen Price in Cardiff. Skeletalized after being buried for 8 years in a carpet beneath a garden, medical artist Richard Neave rebuilt her face upon a skull with sufficient accuracy for its display on public television to be recognized by her parents.

Recently, considerable progress has been made by the use of computer graphic techniques, both in drawing reconstituted heads and in gathering tissue thickness data (Vanezis *et al.* 1989). Some devices are mechanical, measuring the profile of the skull with a device that converts angles and distances into digital data. More recently, a combination of video and laser equipment has allowed 20 000 measurements to be taken and stored within 30 seconds. The data from an unknown skull are then electronically 'clothed' with standard soft tissues from the memory bank and modified on screen to produce various images. These can be rotated electronically so that various profiles can be seen. A variety of stored eyes, ears and noses can be added, and any feature altered almost instantaneously to give a viewer a number of opportunities to recognize the missing person. As with so many techniques in forensic medicine and science, the technology is one for super-specialists at present, but the forensic pathologist should be aware that such methods exist and are increasing in availability and accuracy.

REFERENCES AND FURTHER READING

Acsadi G, Nemeskeri J. 1970. *History of human life span and mortality.* Akademiai Kiado, Budapest.

Allbrook D. 1961. The estimation of stature in British and East African males; based on tibial and ulnar bone lengths. *J Forensic Med* **8**:15–28.

Angel JL. 1919. The bases of paleodemography. *Anthropology* **30**:425–38.

Angel JL, Suchey JM, Iscan MY, *et al.* 1986. Age at death from the skeleton and viscera. In: Zimmerman MR, Angel JL (eds), *Dating and age determination in biological materials.* Croom Helm, London, pp. 179–220.

Asala SA. 2001. Sex determination from the head of the femur of South African whites and blacks. *Forensic Sci Int* **117**:15–22.

Asala SA. 2002. The efficiency of the demarking point of the femoral head as a sex determining parameter. *Forensic Sci Int* **127**:114–18.

Asherson N. 1965. *Identification by frontal sinus prints: a forensic medicine pilot survey.* HK Lewis, London.

Baccino E, Ubelaker DH, Hayek LA, *et al.* 1999. Evaluation of seven methods of estimating age at death from mature human skeletal remains. *J Forensic Sci* **44**:931–6.

Barbet JP, Houette A, Barres D, *et al.* 1988. Histological assessment of gestational age in human embryos and fetuses. *Am J Forensic Med Pathol* **9**:40–4.

Berg S. 1963. *The determination of bone age.* In: Lundquist F (ed.), *Methods in forensic science*. Interscience Publications, New York, pp. 231–52.

Black TK. 1978. A new method for assessing the sex of fragmentary skeletal remains: femoral shaft circumference. *Am J Phys Anthropol* **48**:227–31.

Boström K. 1973. Identification from roentgenograms of sinus frontalis and sella turcica. *Proceedings of Fifth Meeting Scandinavian Society of Forensic Medicine.*

Boucher BJ. 1957. Sex differences in the fetal pelvis. *Am J Phys Anthropol* **15**:581–600.

Boyd JD, Trevor J. 1953. Problems in reconstruction. In: Simpson CK (ed.), *Modern trends in forensic medicine*. Butterworth, London.

Breitinger E. 1937. Zur Berechnung der Körperhöhe aus den langen Gliedmassenknochen. *Anthropol Anz* **14**:249–74.

Brothwell D. 1972. *Digging up bones*, 2nd edn. British Museum, London.

Brown TC. 1950. Medical identification in the Noronic disaster. *Fingerprint Ident Mag* **6**:3–12.

Burnham JT, Preston Burnham J, Fontan CR. 1976. The state of the art of bone identification by chemical and microscopic methods. *J Forensic Sci* **21**:340–2.

Caldwell WE, Molloy HC. 1933. Anatomical variations in the female pelvis. *Am J Obstet Gynecol* **26**:479–505.

Castellano MA, Villanueva EC, von Frenckel R. 1984. Estimating the date of bone remains: a multivariate study. *J Forensic Sci* **29**:527–34.

Cattaneo C, Smillie DM, Gelsthorpe K, *et al.* 1995. A simple method for extracting DNA from old skeletal material. *Forensic Sci Int* **74**:167–74.

Cattaneo C, Craig OE, James NT, *et al.* 1997. Comparison of three DNA extraction methods on bone and blood stains up to 43 years old and amplification of three different gene sequences. *J Forensic Sci* **42**:1126–35.

Cattaneo C, DiMartino S, Scali S, *et al.* 1999. Determining the human origin of fragments of burnt bone: a comparative study of histological, immunological and DNA techniques. *Forensic Sci Int* **102**:181–91.

Cattaneo C, Ritz-Timme S, Schutz HW, *et al.* 2000. Unidentified cadavers and human remains in the EU: an unknown issue. *Int J Legal Med* **113**:N2–3.

Cheevers LS, Ascensio R. 1977. Identification by skull superimposition. *Int J Forensic Dent* **4**:14–16.

Christie AL. 1949. Prevalence and distribution of ossification centres in the newborn infant. *Am J Dis Child* **77**:355–61.

Cobb WM. 1952. Skeleton. In: Lansings AL (ed.), *Cowdry's problems of ageing.* Williams & Wilkins, Baltimore.

Colonna M, Pesce Delfino V, Introna F, Jr. 1980. [Identification by superimposition of the skull on face photography using television: experimental application of a new method.] *Boll Soc Ital Biol Sper* **56**:2271–7.

Colonna M, Introna F, Jr, Potente F, *et al.* 1984. Computer-aided skull-face superimposition by analytical procedures. *Acta Med Leg Soc Liege* **34**:139–49.

Culbert W, Law F. 1927. Identification by comparison of accessory nasal sinuses and mastoid processes. *J Am Dent Assoc* **88**:1634.

Davidson WM. 1960. Sex determination: diagnostic methods. *Br Med J* **4**:1901–7.

Derry DE. 1909. Note on the innominate bone in the determination of sex. *J Anthropol* **43**:266–76.

Derry DE. 1924. On the sexual and racial characters of the ilium. *J Anat* **4**:71–83.

Dixon AD. 1956. Postmortem persistence of sex chromatin. *J Forensic Med* **3**:161–8.

Dixon AD. 1957. Sex determination of human tissues from cell morphology. *J Forensic Med* **4**:11–17.

Dodd BE. 1985. DNA fingerprinting in matters of family and crime [news]. *Nature* **318**:506–7.

Dupertuis CW, Hadden JA. 1951. On the reconstruction of stature from long bones. *Am J Phys Anthropol* **9**:15–54.

Dutra F. 1944. Identification of person and determination of cause of death from skeletal remains. *Arch Pathol* **38**:339.

Dwight T. 1889. The sternum as an index of sex, height and age. *J Anat Physiol* **24**:527–35.

Dwight T. 1890. The closure of the sutures as a sign of age. *Boston Med Surg J* **122**:389–92.

Dwight T. 1904. The size of the articular surfaces of the long bones as characteristic of sex. *J Anat* **4**:19–32.

Earls J, Hester R. 1967. Tattoed sailors: Sociopscychological correlates. *Milit Med* **132**:48.

Eckert W. 1985. The forensic investigation of Josef Mengele [editorial]. *Am J Forensic Med Pathol* **6**:187.

Eckert WG, Teixeira WR. 1985. The identification of Josef Mengele. A triumph of international cooperation. *Am J Forensic Med Pathol* **6**:188–91.

Eckert WG, Willey LR, Blakeslee DJ. 1986. Identification by identi-kit composite from skull appearance. Combined efforts of the anthropologist, forensic pathologist, and criminal investigators. *Am J Forensic Med Pathol* **7**:213–15.

Eliakis C. 1967. Estimating height from the measurement of long bones. *Ann Med Leg* **212**:251–4.

Eliakis EC, Iordanidis PJ. 1963. Determination of sex from the medullary indices of long bones. *Am Med Leg* **43**:326–9.

Eriksson L, Westermark P. 1990. Amyloid inclusions in choroid plexus epithelial cells. A simple autopsy method to rapidly obtain information on the age of an unknown dead person. *Forensic Sci Int* **48**:97–102.

Evans KT, Knight B. 1983. *Forensic radiology*. Blackwell Scientific Publications, Oxford.

Ezra M, Cook SF. 1957. Amino-acids in fossil bone. *Science* **126**:8–86.

Facchini F, Pettener D. 1977. Chemical and physical methods in dating human skeletal remains. *Am J Phys Anthropol* **47**:65–70.

Fawcett E. 1938. Sexing of the human sternum. *J Anat* **72**:633–7.

Fazekas G, Kosa F. 1978. *Forensic foetal osteology*. Akademiai Kiado, Budapest.

Flecker H. 1942. Time of appearance and fusion of ossification centers as observed by roentgenographic methods. *Am J Roentgenol* **47**:97–105.

Francis GC, Werle PP. 1939. The appearance of centers of ossification from birth to 5 years. *Am J Phys Anthropol* **24**:273–86.

Fukushima H, Hasekura H, Nagai K. 1988. Identification of male bloodstains by dot hybridization of human Y chromosome-specific deoxyribonucleic acid (DNA) probe. *J Forensic Sci* **33**:621–7.

Fully G, Pineau H. 1960. Detemination de la stature an moyen du squelette. *Ann Med Leg* **40**:3–11.

Garn SM. 1958. The sex difference in tooth calcification. *J Dent Res* **37**:561–72.

Gatliff BP. 1984. Facial sculpture on the skull for identification. *Am J Forensic Med Pathol* **5**:327–32.

Gatliff BP, Snow CC. 1979. From skull to visage. *J Biocommun* **6**:27–30.

Genovés S. 1954. The problem of sex of fossil hominids. *J R Anthropol Inst* **84**:131–6.

Genovés ST, Messmacher M. 1959. *Valor de los patrones tradicionales para la determinacíon del edad por me las suturas craneos mexicanos. Serie anthropol. No. 7.* Cuadernos de Instit de Hist., Mexico City, Mexico, Vol. 7, pp. 7–53.

George RM. 1987. The lateral craniographic method of facial reconstruction. *J Forensic Sci* **32**:1305–30.

Gerasimov MM. 1971. *The face finder*. Lippincott, Philadelphia.

Gilbert BM, McKern TW. 1973. A method for aging the female os pubis. *Am J Phys Anthropol* **38**:31–8.

Giles E, Elliot O. 1963. Sex determination by discriminant function analysis of crania. *Am J Phys Anthropol* **21**:53–68.

Gill GW. 2001. Racial variation in the proximal and distal femur: heritability and forensic utility. *J Forensic Sci* **46**:791–9.

Glaister J, Brash J. 1937. *The medicolegal aspects of the Ruxton case.* Livingstone, Edinburgh.

Godycki M. 1957. Sur la certitude de determination se sexe après le femur, le cubitus et l'humerus. *Bull Mem Soc Anthrop Paris* Serie **10**:405–10.

Graves WW. 1922. Observations of age changes in the scapula: a preliminary note. *Am J Phys Anthropol* **5**:21–3.

Greulich WW. 1960. Value of X-ray films of hand in human identification. *Science* **1341**:155–62.

Greulich WW, Pye SI. 1959. *Radiographic atlas of the skeletal development of the hand and wrist*, 2nd edn. Stanford University Press, Stanford.

Greulich WW, Thomas H. 1938. The dimensions of the pelvic inlet of 789 white females. *Anat Rec* **72**:45–51.

Greulich WW, Thomas H. 1939. A X-ray study of the male pelvis. *Anat Rec* **75**:289–99.

Hanihara K. 1967. Racial characteristics in the dentition. *J Dent Res* **46**:923–6.

Harrison R. 1968. In: Camps F (ed.), *Gradwohl's legal medicine*, 2nd edn. John Wright, Bristol.

Hellman H. 1929. Racial characteristics in the human dentition. *Am Phil Soc* **67**:157–74.

Herrman L. 1953. Fingerprints and twins. *J Forensic Med* **1**:101–5.

Hill A. 1939. Fetal age assessment by centers of ossification. *Am J Phys Anthropol* **24**:251.

Hoshi, H. 1962. Sex differentiation in the shape of the mastoid process in norma occipalis and its importance to sex determination of the human skull. *Okajima's Folia Anat Jpn* **38**:309–17.

Howard JD, Reay DT, Haglund WD, *et al.* 1988. Processing of skeletal remains. A medical examiner's perspective. *Am J Forensic Med Pathol* **9**:258–64.

Hrdlicka A. 1920. Shovel-shaped teeth. *Am J Phys Anthropol* **3**:429.

Hrdlicka A. 1939. *Practical anthropometry*. Wistar Institute Press, Philadelphia.

Hunt EE, Gleiser I. 1955. The estimation of the age and sex of pre-adolescent children from bones and teeth. *Am J Phys Anthropol* **13**:479–87.

Iordanidis P. 1961. Determination du sexe par les os du squelette (atalas, axis, clavicle, omoplate, sternum). *Ann Med Leg* **41**:28–91.

Iscan MY, Derrick K. 1984. Determination of sex from the sacroiliac; a visual assessment technique. *Fla Sci* **47**:948.

Iscan MY, Loth SR. 1986. Determination of age from the sternal rib in white males: a test of the phase method. *J Forensic Sci* **31**:122–32.

Iscan MY, Miller-Shaivitz P. 1984. Discriminant function sexing of the tibia. *J Forensic Sci* **29**:1087–93.

Iscan MY, Miller-Shaivitz P. 1984. Determination of sex from the tibia. *Am J Phys Anthropol* **64**:53–7.

Iscan MY, Loth SR, King CA, *et al.* 1998. Sexual dimorphism in the humerus: a comparative analysis of Chinese, Japanese and Thais. *Forensic Sci Int* **98**: 17–29.

Iscan MY, Steyn M. 1999. Craniometric determination of population affinity in South Africans. *Int J Legal Med* **112**:91–7.

Iten PX. 1987. Identification of skulls by video superimposition. *J Forensic Sci* **32**:173–88.

Jantz RL. 2001. Cranial change in americans: 1850–1975. *J Forensic Sci* **46**:784–7.

Jedrzejowska ZK. 2001. Craniometry and mathematical calculations as a method for viscero-cranium profile determination. *Forensic Sci Int* **117**:145–51.

Jit I, Singh S. 1956. Estimation of stature from the clavicles. *Indian J Med Res* **44**:137–55.

Jit I, Jhingan V, Kulkarni M. 1980. Sexing the human sternum. *Am J Phys Anthropol* **53**:217–24.

Keen J. 1950. A study of the differences between male and female skulls. *Am J Phys Anthropol* **8**:65.

Keen JA. 1950. Sex differences in skulls. *Am J Phys Anthropol* **8**:479–87.

Kerley ER. 1965. The microscopic determination of age in human bone. *Am J Phys Anthropol* **23**:149–63.

Kerley ER. 1969. Age determination of bone fragments. *J Forensic Sci* **14**:59–67.

Kim MA, Bier L. 1972. Identification and location of the y body in interphase by quinacrine and giemsa. *Humangenetik* **16**:261–5.

Kimura K. 1982. Base wing index for sexing the sacrum. *J Anthropol Soc Nippon* **90**(Suppl):153–62.

Knight B. 1969. Methods of dating skeletal remains. *Med Sci Law* **9**:247–52.

Knight B. 1985. The examination of skeletal remains. In: Wecht C (ed.), *Legal Medicine Annual*, 1985 edn. Praeger Scientific, New York.

Knight B, Lauder I. 1967. Practical methods of dating skeletal remains: a preliminary study. *Med Sci Law* **7**:205–8.

Knight B, Lauder I. 1969. Methods of dating skeletal remains. *Hum Biol* **41**:322–41.

Kobayashi K. 1964. Estimation of age at death from pubic symphysis for prehistoric human remains in Japan. *Zinruig Zassi* **72**:1–16.

Kobayashi R, Nakauchi H, Nakahori Y, *et al.* 1988. Sex identification in fresh blood and dried bloodstains by a nonisotopic deoxyribonucleic acid (DNA) analyzing technique. *J Forensic Sci* **33**:613–20.

Koelmeyer TD. 1982. Videocamera superimposition and facial reconstruction as an aid to identification. *Am J Forensic Med Pathol* **3**:45–8.

Konigsberg LW, Hens SM, Jantz LM, *et al.* 1998. Stature estimation and calibration: Bayesian and maximum likelihood perspectives in physical anthropology. *Am J Phys Anthropol Suppl* **27**:65–92.

Krogman WCA. 1939. A guide to the identification of human skeletal material. *FBI Law Enforcement Bull* **8**:3.

Krogman WCA. 1946. The skeleton in forensic medicine. *Proc Inst Med* **16**:154.

Krogman WCA, Iscan MY. 1986. *The human skeleton in forensic medicine*, 2nd edn. Thomas, Springfield.

Loth SR, Iscan MY, Scheuerman EH. 1994. Intercostal variation at the sternal end of the rib. *Forensic Sci Int* **65**:135–43.

Lundy JK. 1985. The mathematical versus anatomical methods of stature estimate from long bones. *Am J Forensic Med Pathol* **6**:73–6.

Maclaughlin-Black SM, Herd RJ, Willson K, *et al.* 1992. Strontium-90 as an indicator of time since death: a pilot investigation. *Forensic Sci Int* **57**:51–6.

Mall G, Graw M, Gehring K, *et al.* 2000. Determination of sex from femora. *Forensic Sci Int* **113**:315–21.

Mall G, Hubig M, Buttner A, *et al.* 2001. Sex determination and estimation of stature from the long bones of the arm. *Forensic Sci Int* **117**:23–30.

Maltby J. 1917. Some indices and measurements of the modern femur. *J Anat* **52**:363–82.

Mann RW. 1998. Use of bone trabeculae to establish positive identification. *Forensic Sci Int* **98**:91–9.

Manouvrier L. 1893. Le determination de la taille après les grand os des membres. *Mem Soc Anthropol Paris* **4**:347–402.

Maresh MM. 1940. Paranasal sinuses from birth to adolescence. *Am J Dis Child* **60**:55–78.

Mayler J. 1935. Identification by sinus prints. *VA Med Mon* **62**:517–19.

McBride DG, Dietz MJ, Vennemeyer MT, *et al.* 2001. Bootstrap methods for sex determination from the os coxae using the ID3 algorithm. *J Forensic Sci* **46**:427–31.

McCormick WF. 1980. Mineralization of the costal cartilages as an indicator of age: preliminary observations. *J Forensic Sci* **25**:736–41.

McCormick WF. 1981. Sternal foramena in man. *Am J Forensic Med Pathol* **2**:249–52.

McCormick WF, Nichols MM. 1981. Formation and maturation of the human sternum. I. Fetal period. *Am J Forensic Med Pathol* **2**:323–8.

McKeehan HE. 1970. The restoration of desiccated cadaveric fingers for the purpose of identification. *J Forensic Sci Soc* **10**:115.

McKern TW, Stewart TD. 1957. *Skeletal age changes in young American males, analyzed from the standpoint of identification.* Headq. QM Res & Dev Command, Natick, MA.

Mehta L, Singh HM. 1972. Determination of crown-rump length from fetal long bones: humerus and femur. *Am J Phys Anthropol* **36**:165–8.

Meindl RS, Lovejoy CO, Mensforth RP, *et al.* 1985. A revised method of age determination using the os pubis, with a review and tests of accuracy of other current methods of pubic symphyseal aging. *Am J Phys Anthropol* **68**:29–45.

Mendes-Correa AA. 1932. La taille des portugais d'après des os longes. *Anthropology (Prague)* **10**:268–72.

Messmer JM, Fierro MF. 1986. Personal identification by radiographic comparison of vascular groove patterns of the calvarium. *Am J Forensic Med Pathol* **7**:159–62.

Michelson N. 1934. The calcification of the first costal cartilage in whites and negroes. *Hum Biol* **6**:543–57.

Miller KW, Budowle B. 2001. A compendium of human mitochondrial DNA control region: development of an international standard forensic database. *Croat Med J* **42**:315–27.

Modi JP. 1957. *Medical jurisprudence and toxicology*. Tripathi, Bombay.

Montanari GD, Viterbo B, Montanari GR. 1967. Sex determination of human hair. *Med Sci Law* **7**:208–10.

Moore KL, Barr ML. 1955. Smears from the oral mucosa in the detection of chromosomal sex. *Lancet* **2**:57–8.

Moss JP, Linney AD, Grindrod SR, *et al.* 1987. Three-dimensional visualization of the face and skull using computerized tomography and laser scanning techniques. *Eur J Orthod* **9**:247–53.

Müller G. 1935. Zur Bestimmung der Länge beschädigter Extremitätenknochen. *Anthropol Anz* **12**:70–2.

Munter AH. 1936. A study of the lengths of long bones of the arms and legs in man, with special reference to Anglo-Saxon skeletons. *Biometrika* **28**:84–122.

Myers JC, Okoye MI, Kiple D, *et al.* 1999. Three-dimensional (3-D) imaging in post-mortem examinations: elucidation and identification of cranial and facial fractures in victims of homicide utilizing 3-D computerized imaging reconstruction techniques. *Int J Legal Med* **113**:33–7.

Nagamori H, Ohno Y, Uchima E, *et al.* 1986. Sex determination from buccal mucosa and hair root by the combined treatment of quinacrine staining and the fluorescent feulgen reaction using a single specimen. *Forensic Sci Int* **31**:119–28.

Navani S, Shah JR, Levy PS. 1970. Determination of sex by costal cartilage calcification. *Am J Roentgenol Radium Ther Nucl Med* **108**:771–4.

Nemeskeri J, Harsanyi L, Acsadi G. 1960. Methoden zur Diagnose des Lebensalters von Skelettfunden. *Anthropol Anz* **24**:70–95.

Niyogi S. 1971. A study of human hairs in forensic work. *J Forensic Sci* **16**:176.

Norris SP. 2002. Mandibular ramus height as an indicator of human infant age. *J Forensic Sci* **47**:8–11.

Oettle AC, Steyn M. 2000. Age estimation from sternal ends of ribs by phase analysis in South African blacks. *J Forensic Sci* **45**:1071–9.

Ohtani S. 1994. Age estimation by aspartic acid racemization in dentin of deciduous teeth. *Forensic Sci Int* **68**:77–82.

Ohtani S, Matsushima Y, Kobayashi Y, *et al.* 2002. Age estimation by measuring the racemization of aspartic acid from total amino acid content of several types of bone and rib cartilage: a preliminary account. *J Forensic Sci* **47**:32–6.

Olivier G. 1969. *Practical anthropology*. Thomas, Springfield.

Olivier G, Pineau H. 1958. Determination de l'age du foetus et de l'embyon. *Arch Anat Pathol* **6**:21–8.

Parsons FG, Box CR. 1905. The relation of the cranial sutures to age. *J R Anthropol Inst* **35**:308.

Pearson FG. 1920. Sex differences in the skull. *J Anthropol* **54**:58–65.

Pearson K. 1914. On the problem of sexing osteometric material. *Biomedicine* **10**:479–87.

Pearson K. 1926. On the coefficient of racial likeness. *Biometrika* **18**:105.

Pearson K, Bell JA. 1917. A study of the long bones of the English skeleton. 1. The femur. In: *Drapers Co Res Mem*. Biomedicine, Series X. University of London, London, Chapter 14.

Perper JA, Patterson GT, Backner JS. 1988. Face imaging reconstructive morphography. A new method for physiognomic reconstruction. *Am J Forensic Med Pathol* **9**:126–38.

Pesce Delfino V, Colonna M, Vacca E, *et al.* 1986. Computer-aided skull/face superimposition. *Am J Forensic Med Pathol* **7**:201–12.

Phenice TW. 1969. A newly developed visual method of sexing the os pubis. *Am J Phys Anthropol* **30**:297–301.

Pounder DJ. 1984. Forensic aspects of aboriginal skeletal remains in Australia. *Am J Forensic Med Pathol* **5**:41–52.

Rao NG, Pai LM. 1988. Costal cartilage calcification pattern – a clue for establishing sex identity. *Forensic Sci Int* **38**:193–202.

Reichs KJ. 1993. Quantified comparison of frontal sinus patterns by means of computed tomography. *Forensic Sci Int* **61**:141–68.

Reynolds E. 1945. The boney pelvic girdle in early infancy: a roentgenometric study. *Am J Phys Anthropol* **3**:321–54.

Reynolds E. 1947. The boney pelvis in prepubertal childhood. *Am J Phys Anthropol* **5**:165–200.

Rhine JS, Campbell HR. 1980. Thickness of facial tissues in American blacks. *J Forensic Sci* **25**:847–58.

Rhine JS, Moore CE. 1982. *Facial reproduction tables of facial tissue thicknesses of American caucasoids in forensic anthropology.* Maxwell Museum, Albuquerque.

Rho YM. 1985. Importance of examination of the clothed victim. Fingerprint identification of assailant from skin fragment on knifing victim's clothing. *Am J Forensic Med Pathol* **6**:19–20.

Richardson L, Kade H. 1972. Readable fingerprints from mummified or putrefied specimens. *J Forensic Sci* **17**:325–8.

Ritz S, Turzynski A, Schutz HW. 1994. Estimation of age at death based on aspartic acid racemization in non-collagenous bone proteins. *Forensic Sci Int* **69**:149–59.

Ross AH, Konigsberg LW. 2002. New formulae for estimating stature in the balkans. *J Forensic Sci* **47**:165–7.

Ross AH, Jantz RL, McCormick WF. 1998. Cranial thickness in American females and males. *J Forensic Sci* **43**:267–72.

Sanders CF. 1966. Sexing by costal cartilage calcification. *Br J Radiol* **39**:233–7.

Sassouni V. 1959. Cephalometric identification: a proposed method of identification of war dead by means of roentgenographic cephalometry. *J Forensic Sci* **4**:1–10.

Scammon RE. 1937. Two simple nomograms for determining the age and some of the major external dimensions of the human foetus. *Anat Rec* **68**:221–32.

Scheuer L. 2002. Application of osteology to forensic medicine. *Clin Anat* **15**:297–312.

Schranz D. 1959. Age determination from the internal structure of the humerus. *Am J Phys Anthropol* **17**:273–8.

Schuller A. 1921. Das Röntgengramm der Stirnhöhle. *Monatsschr Ohrenheilkd* **55**:1617–20.

Schuller A. 1943. Note on the identification of skulls by X-ray pictures of the frontal sinuses. *Med J Aust* **1**:554–6.

Schultz A. 1937. Proportions, variability and asymmetry of the long bones of the limbs and clavicles in man and apes. *Hum Biol* **9**:281–328.

Sen NK. 1962. Identification by superimposed photographs. *Int Crim Police Rev* **162**:284–6.

Sharif R, Chandra H. 1972. Histological differentiation as to the origin of bones. *J Indian Acad Forensic Sci* **2**:23–30.

Shiati M. 1983. Estimation of stature by long bones of Chinese male adults in South China. *Acta Anthropol Sinica* **2**:80–5.

Simpson E, Henneberg M. 2002. Variation in soft-tissue thicknesses on the human face and their relation to craniometric dimensions. *Am J Phys Anthropol* **118**:121–33.

Singer R. 1953. Estimation of age from cranial suture closure; a report on its unreliability. *J Forensic Med* **1**:52–9.

Snow CC, Williams J. 1971. Variation in premortem statural measurements compared to statural estimates of skeletal remains. *J Forensic Sci* **16**:455–64.

Snow CC, Gatliff BP, McWilliams KR. 1970. Reconstruction of facial features from the skull: an evaluation of its usefulness in forensic anthropology. *Am J Phys Anthropol* **33**:221–8.

Snow CC, Hartman S, Giles E, *et al.* 1979. Sex and race determination of crania by calipers and computer: a test of the Giles and Elliot discriminant functions in 52 forensic science cases. *J Forensic Sci* **24**:448–60.

Steele D. 1970. *Estimation of stature from fragments of long limb bones.* In: Stewart T (ed.), *Personal identification in mass disasters.* National Museum of Nature History, Washington DC, pp. 85–7.

Steele DG, McKern TW. 1969. A method for assessment of maximum long bone length and living stature from fragmentary long bones. *Am J Phys Anthropol* **31**:215–27.

Stephan CN. 2002. Facial approximation: globe projection guideline falsified by exophthalmometry literature. *J Forensic Sci* **47**:730–5.

Stevenson PH. 1929. On racial differences in stature long bone regression formulae with special reference to stature reconstruction formulae for the Chinese. *Biometrika* **21**:303–18.

Stevenson PM. 1924. Age order of epiphyseal union in man. *Am J Phys Anthropol* **7**:53–93.

Stewart JH, McCormick WF. 1983. The gender predictive value of sternal length. *Am J Forensic Med Pathol* **4**:217–20.

Stewart TD. 1948. Medicolegal aspects of the skeleton. *Am J Phys Anthropol* **6**:315–21.

Stewart TD. 1952. *Hrdlicka's practical anthropometry*, 4th edn. Wistar Institute, Philadelphia.

Stewart TD. 1957. Distortion of the pubic symphyseal surface in females and its effect on a determination. *Am J Phys Anthropol* **15**:9.

Stewart TD. 1959. Bear paw remains closely resemble human bones. *FBI Law Enforcement Bull* **28**:18.

Stewart TD. 1962. Anterior femoral curvature; its utility for race determination. *Hum Biol* **34**:4–57.

Stewart TD. 1968. Evaluation of evidence from the skeleton. In: Camps F (ed.), *Gradwohl's legal medicine*, 2nd edn. John Wright, Bristol, p. 425.

Stewart TD. 1968. Subject: skull sutures and age. In: Camps F (ed.), *Gradwohl's legal medicine*, 2nd edn. John Wright, Bristol, p. 132.

Stewart TD. 1979. *Essentials of forensic anthropology: especially as developed in the United States.* Thomas, Springfield.

Stewart TD, Trotter M. 1954. *Basic readings on the identification of human skeletons: estimations of age.* Wenner-Gren Foundation for Anthropological Research, New York.

Steyn M, Iscan MY. 1998. Sexual dimorphism in the crania and mandibles of South African whites. *Forensic Sci Int* **98**:9–16.

Steyn M, Iscan MY. 1999. Osteometric variation in the humerus: sexual dimorphism in South Africans. *Forensic Sci Int* **106**:77–85.

Straus WL. 1927. The human ilium: sex and stock. *Am J Phys Anthropol* **11**:1–28.

Suchey JM. 1979. Problems in the aging of females using the os pubis. *Am J Phys Anthropol* **51**:467–70.

Suzuki K, Tsuchihashi Y. 1970. New attempt of personal identification by means of lip print. *J Indian Dent Assoc* **42**:8–9.

Swift B, Lauder I, Black S, *et al.* 2001. An estimation of the post-mortem interval in human skeletal remains: a radionuclide and trace element approach. *Forensic Sci Int* **117**:73–87.

Teixeira WR. 1982. Sex identification utilizing the size of the foramen magnum. *Am J Forensic Med Pathol* **3**:203–6.

Teixeira WR. 1985. The Mengele report. *Am J Forensic Med Pathol* **6**:279–83.

Telkkä A. 1950. On the prediction of human stature from long bones. *Acta Anal* **9**:103–17.

Thomas H, Greulich WA. 1940. A comparative study of male and female pelves. *Am J Obstet Gynecol* **39**:56–62.

Thompson DD, Galvin CA. 1983. Estimation of age at death by tibial osteon remodeling in an autopsy series. *Forensic Sci Int* **22**:203–11.

Thomsen JL. 1977. Sex determination of severely burned bodies. *Forensic Sci* **10**:235–42.

Thomsen JL. 1979. Y-chromosome bodies in brain and kidney: the normal variation and an unexpected finding in sudden infant death syndrome. *Med Sci Law* **19**:104–7.

Tibbets GL. 1981. Estimation of stature from the vertebral column in American blacks. *J Forensic Sci* **26**:715–23.

Tobias PV. 1953. The problem of race determination. *J Forensic Med* **1**:113–23.

Todd TW. 1920. Age changes in the pubic bone. *Am J Phys Anthropol* **3**:285–334.

Todd TW. 1921. Age changes in the pubic bone I–IV. *Am J Phys Anthropol* **4**:407.

Todd TW, Lindala A. 1928. Dimensions of the body; whites and American negroes of both sexes. *Am J Phys Anthropol* **12**:35–119.

Todd TW, Lyon DW. 1924. Endocranial suture closure; its progress and age relationship. Part I. *Am J Phys Anthropol* **7**:325–84.

Todd TW, Lyon DW. 1925. Cranial suture closure; its progress and age relationship. Part II. *Am J Phys Anthropol* **8**:23–5.

Todd TW, Lyon DW. 1925. Cranial suture closure; its progress and age relationship. Parts III–IV. *Am J Phys Anthropol* **8**:47–71, 149–68.

Trotter M, Gleser GC. 1958. A re-evaluation of the estimation of stature based on measurements of stature taken during life and on long bones after death. *Am J Phys Anthropol* **16**:79–88.

Trotter M, Gleser GC. 1977. Corrigenda to 'estimation of stature from long limb bones of American Whites and Negroes', American Journal Physical Anthropology (1952). *Am J Phys Anthropol* **47**:355–6.

Turner W. 1886. The index of the pelvic brim as a basis of classification. *J Anat Physiol* **20**:125–43.

Turpin R, Tisserand M. 1942. Etude correlative de sinus. *C R Soc Biol* **136**:203–10.

Tyler MG, Kirby LT, Wood S, *et al.* 1986. Human blood stain identification and sex determination in dried blood stains using recombinant DNA techniques. *Forensic Sci Int* **31**:267–72.

Ubelaker DH. 2001. Artificial radiocarbon as an indicator of recent origin of organic remains in forensic cases. *J Forensic Sci* **46**:1285–7.

Ubelaker DH, Volk CG. 2002. A test of the phenice method for the estimation of sex. *J Forensic Sci* **47**:19–24.

Ullrich H. 1975. Estimation of fertility by means of pregnancy and childbirth alterations at the pubis, ilium and sacrum. *Ossa* **2**:23–39.

Vanezis P, Blowes RW, Linney AD, *et al.* 1989. Application of 3-D computer graphics for facial reconstruction and comparison with sculpting techniques. *Forensic Sci Int* **42**:69–84.

Voluter G. 1959. The 'V' test. *Radiol Clin Basel* **28**:1–32.

Wahl J, Graw M. 2001. Metric sex differentiation of the pars petrosa ossis temporalis. *Int J Legal Med* **114**:215–23.

Walker GF. 1976. The computer and the law: coordinate analysis of skull shape and possible methods of postmortem identification. *J Forensic Sci* **21**:357–66.

Warren MW, Schultz JJ. 2002. Post-cremation taphonomy and artifact preservation. *J Forensic Sci* **47**:656–9.

Washburn S. 1948. Sex differences in the pubic bone. *Am J Phys Anthropol* **6**:199–298.

Wells LH. 1959. Estimation of stature from long bones; a reassessment. *J Forensic Med* **6**:171–7.

Wescott DJ. 2000. Sex variation in the second cervical vertebra. *J Forensic Sci* **45**:462–6.

Wescott DJ, Moore-Jansen PH. 2001. Metric variation in the human occipital bone: forensic anthropological applications. *J Forensic Sci* **46**:1159–63.

Williamson MA, Nawrocki SP, Rathbun TA. 2002. Variation in midfacial tissue thickness of African-American children. *J Forensic Sci* **47**:25–31.

Wiredu EK, Kumoji R, Seshadri R, *et al.* 1999. Osteometric analysis of sexual dimorphism in the sternal end of the rib in a West African population. *J Forensic Sci* **44**:921–5.

Yoder C, Ubelaker DH, Powell JF. 2001. Examination of variation in sternal rib end morphology relevant to age assessment. *J Forensic Sci* **46**:223–7.

Yoshino M, Kimijima T, Miyasaka S, *et al.* 1991. Microscopical study on estimation of time since death in skeletal remains. *Forensic Sci Int* **49**:143–58.

Yoshino M, Miyasaka S, Sato H, *et al.* 1987. Classification system of frontal sinus patterns by radiography. Its application to identification of unknown skeletal remains. *Forensic Sci Int* **34**:289–99.

CHAPTER 4

The pathology of wounds

- Definition of a wound 136
- Mechanism of wounding 136
- Classification of wounds 137
- Forensic anatomy of the skin 137
- Abrasions 138
- Contusions or bruises 143
- Kicking 149
- Lacerations 150
- Blunt penetrating injuries 153
- Incised wounds 153
- Dating of wounds by histology and histochemistry 166
- Survival period after wounding 169
- References and further reading 171

DEFINITION OF A WOUND

A wound or injury can best be defined as 'damage to any part of the body due the application of mechanical force'. Some jurisdictions have a legal definition of a 'wound', which usually requires the integrity of the body surface to be breached. As this obviously excludes bruising and damage to deep organs, it is unrealistic in a medical sense, but there is always some legal alternative, such as 'causing serious bodily harm', which covers any injury to any tissue or organ. Other jurisdictions grade wounds not by their physical nature, but by the perceived risk to life or health of the victim; this can be an extremely difficult prognostic exercise.

MECHANISM OF WOUNDING

The human body is constantly subjected to mechanical forces during the normal course of life, varying from unceasing gravitational forces to the forceful impacts of a sporting contest. The body usually absorbs such forces either by the resilience and elasticity of its soft tissues or the rigid strength of its skeletal framework. It is only when the intensity of the applied force exceeds the capability of the tissues to adapt or resist that a wound or injury occurs.

The intensity of the force obeys the usual laws of physics, in that the force varies directly with the mass of the 'weapon' and directly with the **square** of velocity of impact. Of course, the weapon can be anything, including the body itself, as is often seen in the violent deceleration of a fall or in a traffic accident.

The well-known formula: kinetic energy $= \frac{1}{2}$ mass $\times$ velocity^2, means that a one kilogram brick pressed against the scalp will cause no injury, but the same brick thrown against the head at a velocity of 10 m/s may smash the skull. This principle is relevant not only in relation to blunt injury and firearm missiles, but also to stab wounds, as is discussed later.

Another factor of importance is the area over which the force acts. If a plank of wood is struck against the skin, the damage to the tissues will be far greater if the narrow edge is used, than if the impact is from the flat surface. Obviously, the force derived from the same mass and velocity is applied over a smaller area, thus delivering a greater impact to any given unit of tissue. This again is relevant to stab wounds, as all the kinetic energy of a moving knife is concentrated into the tiny area of the tip of the blade; the same energy delivered by the large surface area of a cricket bat might not even cause a bruise.

The effect of excessive mechanical forces on the tissues of the body can cause compression, traction, torsion, and tangential (shear) and leverage stresses. The resultant damage depends not only on the type of the mechanical insult but also on the nature of the target tissue. For instance, violent compression (as in an explosion) may do little harm to muscle, but may rupture lung or intestine, while torsion may leave adipose tissue unaffected, yet cause a spiral fracture in a femur.

The transfer of kinetic energy from the relative movements of the body and the weapon is the source of damage to the tissues. If the attacking object comes to rest in the tissues, then all its kinetic energy must have been transferred. A bullet which passes clean through the tissues thus fails to exchange all its energy into trauma production, which is the reason for the illegal 'dumdum' or more recent, explosive-tipped bullets, the object of which is to expand the missile and prevent its exit from the body, so increasing its 'stopping power' (see Chapter 8). If such energy transfer can be slowed down or spread over a wider area, then the intensity of force applied to the tissues per unit of time is less. This is part of the function of a seatbelt in a vehicle crash, where the stretching of the belt fabric extends the time of energy exchange and the considerable area of the belt surface is a preferable alternative to transferring all the kinetic energy via a few square centimetres of forehead against the windscreen.

Other ways in which the transfer of kinetic energy may be modified is in moving the body in the direction of the force. When a car strikes a pedestrian, that proportion of the momentum of the car that is used in projecting the victim along the road is not then available for damaging the tissues.

Similarly, if a boxer 'rides the punch', he is reducing the differential velocity between his head and his opponent's fist, as well as extending the time over which energy transfer occurs. With a high-speed impact, such as a bullet and – to a lesser extent a stab or violent blow – the inertia of the victim's body prevents any significant loss of energy transfer by movement. If the force does not strike in a linear fashion, but leads to a tangential impact – as in a glancing blow causing a 'graze' – then only part of the kinetic energy is transferred and the damage will be proportionately less.

CLASSIFICATION OF WOUNDS

This is quite arbitrary, but when writing medical reports (especially for legal purposes) it is essential that every doctor should use a standardized nomenclature when describing wounds. All too often reports are seen – especially from clinicians who are not used to medico-legal work – where 'laceration', 'incised wound' and 'abrasion' are used loosely, the accompanying descriptions making it obvious that no clear distinction between them was appreciated by the doctor.

Wounds may also be categorized by the motivation of their infliction, such as 'suicidal or accidental' (the 'manner' index of the WHO International Classification of Disease, ICD E-codes), but a pathologist should classify them by their appearance and the method of causation, such as 'laceration' or 'incised wound'. The most useful classification is:

- Abrasions – colloquially 'grazes or scratches'.
- Contusions – colloquially 'bruises'.
- Lacerations – colloquially 'cuts or tears'.
- Incised wounds – colloquially 'cuts', 'slashes' or 'stabs'.

FORENSIC ANATOMY OF THE SKIN

As most wounds involve the body surface, a reminder of the structure and nomenclature of the skin and subcutaneous tissues is appropriate. Most superficial is the keratinized dead layer of cells, the stratum corneum, which varies greatly in thickness from one part of the body to another. That on the soles and palms is the thickest, while that on protected areas such as the scrotum and eyelids measures



FIGURE 4.1 *Types of injury to the skin.*

only a fraction of a millimetre. This has forensic relevance in the amount of injury that is needed to penetrate the skin and allow bleeding from the underlying tissues.

The living layers of the skin combine with the horny layer to form the epidermis, which has no blood vessels in its thickness. The epidermis is generally corrugated, the under surface by papillae that dip into the dermis. The degree of undulation also varies greatly from place to place, the thinner skin tending to have a flatter junction between dermis and epidermis. The dermis (or 'corium') consists of mixed connective tissue carrying the skin adnexae, such as hair follicles, sweat glands and sebaceous glands. It has a rich network of blood vessels, nerves and lymphatics, and has numerous nerve endings of various types for tactile, pressure and heat sensing. The lower zone of the dermis has adipose tissue and – depending on the site in the body – deep fascia, fatty tissue and muscle will form strata below the skin itself.



FIGURE 4.2 *General structure of skin.*

ABRASIONS

An abrasion is the most superficial of injuries and, in the most restrictive of definitions, is one that does not penetrate the full thickness of the epidermis. Thus the pure abrasion does not bleed, as blood vessels are confined to the dermis. Because of the corrugated nature of the dermal papillae, however, many abrasions enter the corium and bleeding commonly occurs.

Another definition (all of which are arbitrary) would describe an abrasion as a superficial injury to 'the skin', which would allow penetration of the upper dermis rather than only the epidermis, so that bleeding would fall within the definition.

Abrasions are known in lay terms as 'scratches' or 'grazes', though the former usually indicates a linear mark and the latter a 'brush' abrasion caused by wider tangential impact. Where these brush abrasions are the result of scraping contact with the ground, the lay term is a 'gravel rash'. There are many causes of abrasions, which are common everyday lesions, especially in children whose legs are rarely free from some scratches and bruises. Any contact that rubs across the epidermis and removes the keratinized layer and underlying cells will cause that area to become discoloured and moistened by exuded tissue fluid, even if bleeding does not occur from abraded dermal papillae.

When death ensues soon afterwards, the abrasion becomes stiff, leathery and of a parchment-like brown colour as a result of the drying of the moist exposed surface. This is classically seen, for example, in the ligature mark of hanging or strangulation. It is impossible to tell whether a superficial abrasion occurred immediately before or after



FIGURE 4.3 *Simple abrasion of the skin caused by an almost perpendicular impact of the head against the ground. There is only slight tangential scuffing though most abrasions have some element of sideways contact that damages the epidermis.*

death if there was insufficient time for any inflammatory reaction to occur at the margins. Post-mortem abrasions are common, especially after autopsy when the body is re-examined, because mortuary instruments and the moving of bodies into refrigerators and coffins can often make marks. These abrasions commonly appear yellow and translucent, and are absolutely devoid of any colour change at the edge.

Tangential or brush abrasions

Most abrasions are caused by a lateral rubbing action rather than vertical pressure. Where this tangential component is marked, the direction of the force can often be determined by tags of epidermis dragged to the terminal end of the abrasion. For example, in the 'brush abrasion', which is common in childhood falls and pedestrian accidents, the skidding of the body across a rough surface scrapes linear furrows across the skin. Strands and tags of epidermis may be peeled along these furrows to the further end where contact ceased. Visual examination, using a lens if necessary, can indicate the direction of movement of the body. Similarly, if a victim is struck a glancing blow with a rough object such as a stone or brick, similar epidermal tags may indicate the direction of the blow.

The same type of grooved abrasions can be caused when a victim is dragged along the ground, either in a vehicular accident or by an assailant. It may be important, though difficult, to attempt to differentiate such drag marks as being ante-mortem or post-mortem, a problem which is discussed in another chapter.

Crushing abrasions

Where the impact is vertical to the skin surface, no scraping or tangential marks occur. Instead the epidermis is crushed and an imprint of the impacting object is stamped on the surface. If the impact is substantial and the area of contact small,



FIGURE 4.4 *A linear abrasion or 'graze', confined to the upper layers of the skin. The tangential direction of impact of the weapon was from above downwards (along the longitudinal axis of the upper arm), as can be determined by the shreds of epidermis peeled towards the lower end.*



FIGURE 4.5 *Determination of the direction of impact in an abrasion caused by a tangential force. The epidermal tags raised by the impact tend to pile up at the distal end.*



FIGURE 4.6 *'Brush abrasion' or 'grazes' caused by tangential contact of a moving body with a rough surface. Although most are seen in traffic accidents from contact with the road surface, this example is from a murdered woman dropped down a mine shaft. There are grazes running in two directions at right angles, indicating that she must have struck the wall twice, in different postures.*



FIGURE 4.7 *Brush abrasion from skidding contact with the road surface during a drunken scuffle. The lesion is partly abraded and partly bruised. The direction of movement can be discerned, as the scratches begin more abruptly and deeply near the ruler, and tail off superficially at the opposite edge.*

a punctured wound will be made, but otherwise a crushed abrasion will occur. The lesion is slightly depressed below the surface unless an underlying bruise or local oedema bulges the tissues. These abrasions are the ones that most clearly reproduce the pattern of the injuring object. An example



FIGURE 4.8 *Drag marks on the back of a murder victim. Death was caused by a stab wound of the front of the chest – the body was pulled along the ground for a short distance, obviously in the direction of the feet, as the scratch near the waist is deeper near the feet end and tails off at the opposite end.*



FIGURE 4.9 *Abrasions in manual strangulation. The area is more extensive than is usually seen in such circumstances. The large area of superficial damage to the epidermis is caused by sliding movements of the assailant's hands, the area having become dried and leathery during the post-mortem interval. The smaller marks are fingernail scratches.*

would be the marks of a vehicle radiator on a pedestrian victim or the pattern of a floor grid on to which a person has fallen. If the impact is forcible, then the dermis may also be injured: an area of bruising may underlie the abrasion.

Fingernail abrasions

These are important because of their frequency in assaults – especially child abuse, sexual attacks and strangulation. Often associated with focal bruises, fingernail abrasions are most often seen on the neck, the face, the upper arms and the forearms. They may be linear scratches if the fingers are dragged down the skin, or short, straight or curved marks when the skin is gripped in a static fashion. As women tend to have longer, sharper fingernails than men, they are naturally more often associated with causing such abrasions. A victim resisting a sexual or other attack may rake her nails down her assailant's face, causing linear, parallel scratches that may be several millimetres wide and placed a centimetre or two apart. The expected pattern may be fragmentary, however, as is often seen on the neck when a victim of either manual or ligature strangulation attempts to tear away the attacking fingers or cord. These marks are usually vertical, as opposed to the more random marks that may be inflicted by the nails of the assailant in manual strangulation.

The upper arms are a frequent site for gripping and restraint, both in adult assaults and child abuse. Bruising is most common, but fingernail marks may be superimposed. Static fingernail abrasions may be straight or curved, often about half to one centimetre long. The direction of curvature must be interpreted with care if one wishes to decide which way the hand was held at the time of infliction.

Although it is natural to assume that the concavity of the mark indicates the orientation of the fingertip, experiments by Shapiro *et al.* (1962) have shown that this is often not the case. Because the skin is put under lateral tension when it is indented by the nails, it may distort, so that when the tension is released the elasticity of the skin causes it to return to its original position, carrying the nail mark with it. The curve may then reverse to form either a straight line or a convexity. The shape of the free edge of the fingernail also affects the mark, as pointed nails are more likely than those with straight edges to give these paradoxical results. Once again, the pathologist has to be wary of incorrect interpretation when, for instance, deciding if nail marks on a neck were made by hands approaching from the front or passing around the back of the neck. However, personal experiments with the Shapiro *et al.* contention have shown that it by no means always applies.

Patterned abrasions

Formerly it was often claimed that abrasions retained the pattern of the impacting object more accurately than other injuries such as bruises and lacerations. Though abrasions undoubtedly do preserve such patterns well, many of the examples were not in fact true abrasions, but were intradermal bruises, mentioned in the next section.



FIGURE 4.10 *Extensive abrasion of the knees and shins, in a drunk who stumbled amongst furniture before dying of a head injury. The damaged skin has exuded tissue fluid, which has dried post-mortem to produce the dark, leathery appearance.*



FIGURE 4.11 *Patterned abrasion of the forehead. The victim was struck on the head in a public house with a heavy glass ashtray, the bottom of which had embossed concentric circles moulded into the glass.*



FIGURE 4.12 *Abrasions and intradermal bruising on the forehead of a swimming bath attendant. He was found drowned when there were no witnesses, but the spacing of the marks exactly matched the ridged tiles at the edge of the bath, so it was presumed that he had slipped and struck his head before falling unconscious into the water.*

Patterned injuries occur when the force is applied at or near a right angle to the skin surface, rather than with the skidding impact of a graze. If a weapon with a patterned surface strikes the skin – or the body falls against a patterned surface – the abrasion of the epidermis follows the ridges of the object if it has a profile of varying height. Not only may the epidermis be damaged, but the skin may be compressed into the cavities of the pattern, with consequent capillary damage leading to an intradermal bruise. Probably the best example of this is seen when a motor tyre passes over the skin, leaving a pattern where the skin has been squeezed into the grooves of the rubber tread.

There is little point in trying to list all the possible patterns that can be distinguished in abrasions on a body, but a few



FIGURE 4.13 *Patterned abrasions from the back edge of a serrated 'Rambo' knife. Measurements and photographs with a scale should always be obtained to assist in the identification of the weapon.*



FIGURE 4.14 *Patterned abrasion on forehead due to falling down steps onto a metal grid. Here the abrasions are not produced by tangential force, but imprinted directly by impact at a right angle to the skin.*

have particular medico-legal significance. In former years the honeycomb grid of a motor-vehicle radiator provided many examples of patterned abrasions, but changes in vehicle design have relegated these to historical interest. There may still be projections on vehicles that cause damage, but these are more likely to inflict bruises and lacerations. The muzzle of a firearm can imprint an abrasion on the skin, which is of importance in that it confirms that the discharge was contact in nature. Impact against ribbed ceramic tiles in a bathroom or swimming bath may assist in reconstructing unwitnessed events. Blows from a weapon with a recognizable surface may help to identify that weapon, such as a plaited rope or leather whip, or a solid object with an embossed pattern. Abrasions from objects with a recurring pattern, such as bicycle chain used in gang fights, or a serrated knife, can readily provide a clue to the nature of the weapon.

Post-mortem abrasions

Unlike post-mortem bruises, artefactual abrasions are common. They may have been inflicted after death from a variety of causes, including dragging a corpse or buffeting in moving water. Some post-mortem animal injuries also resemble abrasions such as insect bites, especially by ants.

Other damage may be caused following autopsy. As the post-mortem interval increases, so the skin becomes more fragile. Even the normal procedures of post-autopsy reconstruction and handling in the mortuary may cause dermal damage, especially after washing with hot water. If the pathologist returns for a later examination, or if he is retained to perform a second autopsy for the defence, the appearances should be checked with the original description or photographs, if some injuries suggest a post-mortem origin.

CONTUSIONS OR BRUISES

Although often combined with abrasions or lacerations, a pure bruise lies beneath an intact epidermis and consists of an extravascular collection of blood that has leaked from blood vessels damaged by mechanical impact. An extravasation of blood that is (arbitrarily) larger than a few millimetres in diameter, is usually termed a 'bruise' or 'contusion'. This size overlaps the older and now little used term 'ecchymosis', which is really a small bruise.

Even smaller is the 'petechial haemorrhage', which is the size of a pin head or less. Both ecchymoses and petechiae are not usually caused by direct mechanical trauma and are often seen on serous membranes and conjunctivae as well as on skin. However, moderate pressure, impact or, especially, suction on the skin can produce a patch of localized petechiae.

Bruises are caused by damage to veins, venules and small arteries. Capillary bleeding would be visible only under a microscope and even petechiae originate from a larger order of blood vessel than a capillary.

The word 'bruise' usually implies that the lesion is visible through the skin or present in the subcutaneous tissues, whilst a 'contusion' can be anywhere in the body, such as the spleen, mesentery or muscles. The two words are often interchanged at random, however, though 'bruise' is to be preferred when a doctor gives reports or evidence to a non-medical audience.

Intradermal bruises

These are important but rarely mentioned in most texts. The usual bruise from a blunt impact is situated in the subcutaneous tissues, often in the fat layer. When viewed through the overlying corium and epidermis, the bruise is somewhat blurred, especially at the edge. When a bruise is made by impact with a patterned object, however, the haemorrhage may be far more sharply defined, if it lies in the immediate subepidermal layer. The amount of blood is relatively small, but because of its superficial position and the translucency of the thin layer that overlies it, the pattern is distinct.

Such bruises are especially likely to occur when the impacting object has alternating ridges and grooves, as the skin will be forced into the grooves and be sharply distorted. Intradermal bleeding will occur here and the areas in contact with the raised ridges may remain pale, as the pressure forces the blood from the small vessels. A good example is that of a motor tyre running across the surface. Impacts from whips with patterned thongs may also show the same phenomenon, as do the ribbed rubber soles of 'trainer' shoes.

Factors affecting the prominence of a bruise

Several factors influence the apparent size and prominence of a bruise and, because of these, it is not possible to be dogmatic about the amount of force needed to produce any given bruise.

- As it is a leakage of blood from a vessel, there must be sufficient space outside that vessel for free blood to accumulate. This explains the ease with which bruising appears in lax tissues such as the eye socket or scrotum and its rarity in the sole of the foot or palm of the hand, where dense fibrous tissue and restrictive fascial planes prevent accumulation of blood. Because of the greater volume of soft subcutaneous tissue in fat people, they



FIGURE 4.15 *Intradermal bruising showing the pattern of rubber soles of 'trainer' shoes on the neck and T-shirt of a homicide victim.*

tend to bruise more easily than thin ones, other factors being equal (such as vessel fragility and senile changes).

- The apparent prominence of a bruise beneath the skin varies with the amount of blood in the extravasation. The size of the haemorrhage depends partly, but not entirely, on the intensity of the injuring force. The size and density of the vascular network varies from place to place and the amount of damage that a given blow causes to local blood vessels is partly a matter of chance.
- Resilient areas, such as the abdominal wall and buttocks, bruise less with a given impact than a region where underlying bone acts an anvil with the skin between the bone and the inflicting force. The head, chest and shins are examples.



FIGURE 4.16 *Multiple bruises on the trunk of a victim of child abuse. The bruises are of the 'fingertip' type, caused by heavy prodding by adult fingers. The child died of a ruptured liver.*

- The depth at which the bruise is placed affects the apparent severity. A bruise may be placed superficially in the dermis to form the well-patterned intradermal bruise mentioned in the previous section; here, a minute amount of blood will be obvious. Most bruises are in the subcutaneous tissues above the deep fascia and will therefore be fairly obvious, but others can be confined below deeper fascial membranes so that the free blood has to be viewed through the skin and underlying adipose tissue. For a given size of extravasation, this bruise will be less prominent. Some bruises are confined to deep fascial compartments and never become visible without dissection.
- For a given impact, the volume of blood lost into the tissues can depend upon the fragility of the blood vessels and the coagulability of the blood. In old persons, vessel fragility may be extreme and a large bruise may develop from the slightest of knocks. Children tend to bruise more easily than adults, presumably because of the softer tissues and the smaller volume of protecting tissue that overlies the vessels. Any bleeding diathesis resulting from disease, a toxic condition, or certain medication, will also retard the normal clotting process that heals the breach in the bleeding vessels. Those with scurvy and chronic alcoholics bleed easily but, in contrast, certain people (such as boxers) seem able to avoid bruising from blows that would severely damage other people.
- It is common knowledge among lay people, as well as doctors, that a bruise may 'come out' – that is, become more prominent with the passage of hours or days. This is partly caused by continued bleeding from the ruptured vessels, but mainly by percolation of free blood from its origin deeper in the tissues upwards towards the epidermis. Another factor may be haemolysis, when the freed haemoglobin is able to stain the tissues in a more diffuse way and become more noticeable than intact red blood cells. This latter mechanism is certainly the reason not only for the well-known post-mortem phenomenon of bruises becoming more prominent after death, but of new bruises appearing later where none was visible at an autopsy performed soon after death. This is further considered in the chapter on post-mortem changes, but is repeated here because of the importance of recognizing the differences in appearance that can occur between two autopsy examinations spaced a few days apart. The second, usually for a defence opinion, may find new bruises not recorded by the first pathologist, but if the phenomenon of delayed appearance is appreciated, potential disputes may be avoided.



FIGURE 4.17 *Patterned abrasion and intradermal bruising of the face during a fatal armed robbery. The watchman was struck in the face by an assailant wearing a hard-corded driving glove with a coarse-weave pattern.*

Movement of bruises

A bruise may appear at a different place on the surface from the point of impact. When the bruise is superficial, especially intradermal bruising, the lesion appears immediately – or at least rapidly – and is at the point of infliction. When blood extravasates in the deep tissues, however, it may take time to reach the surface (if it ever does), and this may be some distance away because of deflection and obstruction by fascial planes and other anatomical structures.

In addition, bruises may move under gravity. The most frequent example is a bruise or a bleed under a laceration on the upper forehead. If the victim survives for at least some hours, then the subcutaneous haemorrhage can slide downwards over the eyebrow ridge and appear in the orbit, to give a ‘black eye’, which might be misinterpreted as direct trauma. Similarly a bruise of the upper arm or thigh may surface lower down around the elbow or knee.

Alteration of bruises with time

As already mentioned, bruises often become more prominent some hours or days after infliction because red cells or haemoglobin diffuse closer to the translucent epidermis. There is another temporal series of changes in bruises in the living person, this being part of the healing process. Fresh extravasation of blood is obviously dark red, though when viewed through the skin this may be purple or almost black in appearance. In racially pigmented victims, a bruise may sometimes be undetectable from the surface, apart from swelling caused by a haematoma and tissue oedema.

With the passage of time, the haematoma breaks down under the influence of tissue enzymes and cellular infiltration. The red-cell envelopes rupture and the contained haemoglobin undergoes chemical degradation, which causes a sequence of colour changes. The haemoglobin is broken down into compounds including haemosiderin, biliverdin and bilirubin, which lead the colour changes through a spectrum of purple to bluish brown, to greenish brown to green to yellow, before complete fading.

A small skin bruise in a healthy young adult might be expected to pass through all these stages and vanish in about a week, but there is a tendency to overestimate the length of time needed as shown by Roberts (1983), who observed that ‘love bite’ bruises in sexual offences could become yellow and vanish within a couple of days. Langlois and Gresham (1991) reviewed the literature on this subject, indicating the wide variation in opinion. They also made careful photographic records of the macroscopic appearance of bruising on 89 subjects, aged between 10 and 100 years. They concluded that the most significant change was the appearance of a yellow colour (in persons less than 65 years of age), which indicated that the bruise could not be less than 18 hours old. Blue, purple and red did not assist in



FIGURE 4.18 *Kicking and stamping injury to the face. The nose is bruised from a kick and the patterned rubber sole of the shoe has imprinted intradermal bruising on the forehead. It is essential to obtain accurate photographs and measurements of the shoe-tread pattern, to allow identification of the footwear.*

dating bruises; brown was held to be a mixture of colours and was not considered as useful.

In the present authors' experience, it is impossible to comment on the age of a bruise less than 24 hours since infliction, except to say that it is 'fresh', as no visible changes occur in that time.

It is not practicable to construct an accurate calendar of these colour changes, as was done in older textbooks, as there are too many variables for this to be reliable. These include:

- the size of the extravasation – changes begin at the margin and a larger bruise will take a longer time to be absorbed. A large old bruise may contain all the colours possible – from purple in the centre to yellow at the edges
- the age and constitution of the victim. Aged persons may not heal their bruises at all and carry them for the remainder of their lives



FIGURE 4.19 *Extensive bruising of the face due to hitting, kicking and stamping 6 days earlier. The victim had multiple fractures of the facial bones, bilateral serial rib fractures and a tension pneumothorax.*

- a personal idiosyncrasy in the rapidity with which such changes occur in any one person, including coagulation defects.

Even histological examination is unreliable in the accurate dating of bruises, as is discussed later in this chapter. The appearance of stainable iron, in the form of haemosiderin, however, does not usually appear within the first 2 or 3 days, though Simpson suggests that it may be found as early as 24 hours. In meningeal haemorrhage, it seems to appear from around 36 hours.

Haematoidin, another breakdown product of blood pigment, can appear in old bruises and haematomas after the first week.

Though an absolute date cannot therefore be placed upon a bruise, the following observations are legitimate.

- If a bruise appears fresh over all its area, with no observable colour change, it is unlikely to have been inflicted more than about 2 days before death, except in old persons.
- If the bruise has any green discoloration, it was inflicted not later than 18 hours before death (Roberts 1983; Langlois and Gresham 1991).



FIGURE 4.20 *Bruises from a beating with a broom handle. They are approximately parallel and several, especially the lowermost, show a double 'tram-line' appearance typical of the impact of a round or square-section rod. The pressure in the centre compresses the vessels so that they do not bleed.*

- If several bruises (of roughly comparable size and site) are present and are of markedly different colours, then they could not have been inflicted at the same time. This is particularly important in suspected child abuse, where intermittent episodes of injury have important diagnostic significance.

Bruising of special significance

Certain types of bruise and bruises at particular sites have a specific significance. Clusters of small discoid bruises of about a centimetre in diameter are characteristic of fingertip pressure from either gripping or prodding. These groups are often seen in child abuse, when an adult hand grips the infant by a convenient 'handle'. Once called 'sixpenny bruises' from their size, the lesions are commonly seen on the forearms or upper arms of the child, or sometimes around the wrist or ankle, though they can occur on the abdomen. Similar bruises from fingertips may be seen on the neck of children or adults in manual strangulation, though there is often additional diffuse bruising caused by a sliding grip on the neck.



FIGURE 4.21 *Suction marks in the left breast of a 22-year-old homicide victim, who was killed by manual and ligature strangulation.*

When the skin surface is struck by a rod or rectangular sectioned object such as a cane or lath, the consequent bruising may be of the 'tram-line' or 'railway line' type. This appears as two parallel lines of bruising with an undamaged zone in the centre. The mechanism of this double line is that the weapon sinks into the skin on impact so that the edges drag the skin downwards and the traction tears the marginal blood vessels. The centre compresses the skin, which, in the absence of underlying bone, causes little or no damage to the vessels. When the momentary impact is released, blood flows back into the injured marginal zones and leaks into the tissues. Impact from broom handles, narrow planks and wood or metal rods can all cause this characteristic lesion.

As with abrasions, bites can result in bruises; this is dealt with in Chapter 26. It might be noted here that the so-called 'love bites' are often bruises, with or without associated abrasions, being a shower of small petechial lesions caused by oral suction on the skin.

The common 'black eye' is dealt with under 'Head injuries' in Chapter 5, but again it is worth repeating that not all black eyes are true bruising from a blow in the orbit. Some are from fractured orbital roofs and others are the result of gravitational movement of a forehead injury.

A bruise below the ear in a death from subarachnoid haemorrhage needs careful examination of the upper cervical spine and basilo-vertebral arteries, again as discussed under 'Head injuries' in Chapter 5.



FIGURE 4.22 *Formation of 'tram-line' bruising from the application of a rectangular or cylindrical object.*



FIGURE 4.23 *A black eye (peri-orbital haematoma) of a live victim from a direct fist blow, which has also bruised the bridge of the nose and lacerated the corner of the eye (sutured).*

KICKING

The shod foot may leave a patterned bruise on the body, most often on the abdomen or chest, though it may be recognizable on the neck or face. A glancing kick is more likely to cause scuffed abrasions and bruising, and a kick from a toecap, a curved abrasion or even laceration. A vertical stamping action may imprint an intradermal bruise corresponding to the sole pattern, especially in these days of rubber 'trainer' shoes. As with a motor tyre, the skin can be forced into the slots in the sole, creating an accurate pattern of superficial bruising. There may also be more diffuse deep bruising if the impact is severe, but this is less useful in delineating an identifiable sole pattern.

Kicking has become increasingly common with the increase in violence and vicious hooliganism in society. The heavy footwear fashionable among some of the least responsible citizens adds to the severity of the lesions.

Though most kicking injuries end up in hospital casualty departments, an increasing number reach the pathologist. Not all victims are drunken youths, as many assaults upon old people by intruders and muggers involve severe kicking.

Obviously, most kicks are delivered with the victim already lying or sitting on the ground, having been brought there by some other means of violence, including pushing, tripping and fist punches. Once prostrate, the 'boot is put in' towards the most convenient targets, which tend to be the concavities of the body. The loin, the groin, the neck and the face are often attacked, and – when the victim assumes a 'fetal position' on his side for protection – swings may be taken into the abdominal area. As an alternative to swinging kicks, the foot may be brought vertically down on the prone victim, the heel being the most damaging part, rather than the toecap. A grinding motion can also be added, which may tear the skin and cause ragged lacerations.

Yet another variant is standing on the body or actually jumping onto it with one or both feet. The chest is the most common target for this practice and fractured ribs or sternum, a flail chest and cardiac injuries can result.

The major characteristic of most kicking injuries is the severity of bruising and underlying damage. Even if the toecap does not cause lacerations, there may be large haematomata and intramuscular contusions from heavy kicks. Abdominal and thoracic viscera can be ruptured and the genitalia are also vulnerable, especially the scrotum and sometimes urethra.

A common danger with kicking to the face is fracture of either (or both) mandible and maxilla, nasal bones and zygoma, though the cranial vault is seldom fractured and kicks to the vertex of the head seem less common. With such facial injuries, death may occur from filling of the pharynx and air passages with blood. A kick on one side of the face can completely detach the lower maxilla – with the upper dental arch and palate – from the rest of the maxilla. A unilateral kick of the jaw can fracture both rami of the mandible, there being no necessity for kicks on either side.

Post-mortem bruising and other artefacts

It is possible to cause what appears to be a bruise by deliberate violence to a dead body, but the amount of force



FIGURE 4.24 *A footmark imprinted in superficial bruising on the back. There is another partial mark at waist level, both being made by stamping with the flat of a foot through thin clothing, rather than by swinging kicks.*



FIGURE 4.25 *Bruising of the interior of the lip from a blow in the mouth. The lip has been impacted on the underlying teeth, but not sufficiently hard to cause a laceration.*

required is great. As there is no internal pressure in the small vessels that have to be ruptured, bleeding is a passive ooze rather than an active extravasation, so the size of the haemorrhage is slight in relation to the amount of effort expended. Thus, post-mortem skin bruising is of little practical significance to the pathologist – in most instances he can be reassured that new or more obvious bruising apparent when he returns several days later for a second examination of a body is genuine. Post-mortem abrasions are common, especially after a first autopsy and additional handling of the body in the mortuary, but these procedures rarely produce artefactual bruises.

More important than dermal artefacts are spurious bruises inside the body. Especially in congestive deaths, such as pressure on the neck, the venous system may be engorged at death and a number of artefactual haemorrhages may occur. One particularly important area described fully elsewhere is the neck, in which collections of blood between the oesophagus and cervical spine may simulate bruising from manual strangulation. These were fully investigated by Prinsloo and Gordon (1951) and, where neck trauma is suspected, it is advisable to remove the brain before dissecting the neck region to allow drainage of the engorged venous plexuses that give rise to the artefact. This phenomenon appears to be related to the post-mortem interval and is more likely to arise if there is a delay in autopsy.

LACERATIONS

The third major type of blunt injury is the laceration, in which the full thickness of the skin is penetrated.

Lacerations differ from incised wounds in that the continuity of the tissues is disrupted by tearing rather than clean slicing, but the distinction is often blurred because some lacerations are caused by jagged projections ripping into the skin in much the same manner as a blunt knife or axe.

Unless great force is used, most lacerations require a firm base to act as an anvil for the skin and underlying tissue to be pinned against. It is unusual for a blunt impact to lacerate the abdomen or buttock, but the scalp, shins, shoulder, face and – to a lesser extent – the thorax, are all prone to lacerated injury. Where a soft area such as buttock, thigh, calf or forearm is lacerated, the lacerating agent is either a projecting point or edge, or a completely blunt object is pulled obliquely against the tension of the skin until it tears. Because of the crushing and tearing components of a laceration, there is usually associated abrasion and bruising,



FIGURE 4.26 *Laceration of the eyebrow with surrounding bruising. The wound is stellate as a result of crushing against the underlying bone. The victim fell from a low cliff on to rocks. The sea has washed away the original bleeding.*

though these may be minimal if the lacerating force acts at right angles to the surface.

The scalp offers the best example of a laceration, as the skin and subcutaneous tissue lie over the bony platform of the skull and are crushed against it when the force impacts. In fact, scalp lacerations can resemble incised wounds, because this ‘sandwich effect’ is so pronounced that a blow from a blunt instrument can cleanly split the tissues against the skull, leaving a linear wound that appears to the inexperienced to be a knife or chopper cut.

A laceration can be distinguished from an incised wound by:

- the bruising and crushing of the margins, though this may be a very narrow zone, requiring inspection through a lens
- the persistence of tissue strands across the interior of the wound, including fascial bands, vessels and nerves. In a wound from a sharp weapon these are divided
- the absence of a sharply linear injury in the underlying bone, especially if it is the skull. A knife or axe is likely to chip or score the base of the wound
- if the area is covered with hair, as on the scalp, intact hairs will survive to cross the wound; an incised injury would divide them.

A flat impact may cause a laceration, especially on the scalp. If the head falls to the ground or is hit by a wide, flat weapon, the skin and subcutaneous tissues are compressed



FIGURE 4.27 *Multiple homicidal lacerations of the scalp. The unusual shape is difficult to interpret, but they were caused by a claw hammer. Two are triangular, the upper and lower show tissue bridges because of the gap between the two claws.*



FIGURE 4.28 *Laceration of the scalp from a 30 cm long heavy torch (insert). The skin over the shoulders is reddish due to first- and second-degree burns. The victim was hit on the head while sleeping in bed, after which the husband poured petrol over the body and set it on fire.*

on the anvil of the skull and may split sideways, often with a zone of surrounding bruising.

Other lacerations are caused by the impact of an edged object, be this a rod, a brick, the edge of a kerbstone or the wing mirror of a vehicle. Though the impact may be virtually perpendicular to the skin surface, there is usually some tangential element and this can cause one edge of the wound to differ from the other. Where there is a glancing element, one edge will be relatively clean-cut, whereas the other will be ripped away from the first, suffering more tearing of the margin and often showing undercutting of the edge. If the impact is significantly asymmetrical, then this undercutting may be pronounced enough to form a flap of skin and underlying tissue, which is peeled off the underlying bone or deep fascia.

In extreme forms, this produces a 'flaying injury', where a large area of skin and subcutaneous tissue is rolled off a limb, almost always by the rotary action of a revolving motor wheel. A similar injury can occur on the scalp again from a rotating wheel – though a similar 'scalping' lesion can be caused by traction from hair being trapped in machinery. This was formerly a common industrial accident and was the reason for the 'snood' hairnet being worn by women factory workers during the last war.

Patterned lacerations

Lacerations do not reproduce the shape of the injuring agent nearly as well as do abrasions and intradermal bruises. As with



FIGURE 4.29 *Homicidal lacerations of the scalp penetrating the skull. Although some of the injuries resemble incised wounds, their margins are crushed, and hairs and tissue strands cross the injuries. The damage was probably inflicted with a metal rod with sharp edges.*



FIGURE 4.30 *Crushing impact of a blunt object on skin supported by bone, such as scalp on skull. The skin is sandwiched between weapon and bone and this causes a lacerated split that has bruised margins and bridges of hair and tissue in the wound.*



FIGURE 4.31 *A healing shallow laceration of the forehead, about one week after infliction. The base of the injury has filled with granulation tissue and the surrounding skin shows puckering due to contraction of the central scab.*

skull fractures, the magnitude of the force needed to cause a blunt tearing of skin leads to blurring of the impact shape, often with radiating or totally irregular tearing. Sometimes the shape is recognizable and probably the best example is a hammer blow to the head. A circular face may punch out a circle or an arc of a circle, which may also be reproduced in an underlying depressed skull fracture. The exact size of the hammer face may not be accurately reproduced in the laceration, which may be slightly larger than the hammer.

Kicks may cause lacerations, especially if a heavy boot with a hard toecap is used. These tend to be tangential and may peel up a flange of tissue. They can be clean-cut and are sometimes mistaken for knife wounds. Stamping injuries are more likely to cause abrasions and bruises than lacerations, unless the violence is extreme. A heavy focal blow may cause a linear or a stellate laceration, the latter radiating out from the focus of impact. The surface may be abraded and the surrounding tissue deeply bruised, so the final lesion is complex.

Firearm wounds are a special form of laceration and will be dealt with separately.

BLUNT PENETRATING INJURIES

These 'puncture wounds' are a hybrid between lacerations and incised wounds, and have more of the features of the latter. Such injuries can occur from metal spikes, wooden stakes, garden or farm forks, and a variety of vehicular and industrial accidents. They are occasionally seen in homicides or suicides when weapons like screwdrivers are used as daggers. The interpretation of such skin wounds can be difficult, as in the 'Yorkshire Ripper' cases, when some small stellate stab wounds were thought to have been caused by a Phillips-type screwdriver. A number of fatal wounds, some of them homicidal, have been caused by chisels, usually very sharp woodworking tools with one face of the edge ground to a straight line. The edges of the chisel are squared off and the resulting skin defect may be rectangular.

When a blunt spike is driven through the skin, there will be inversion and abrasion of the edges, though the former may vanish if the weapon has been withdrawn. Foreign material such as rust, dirt or splinters may be left in the wound, and must be carefully preserved for forensic examination if the weapon has not been recovered.

INCISED WOUNDS

Injuries caused by sharp objects are classified as 'incised' wounds, though the nomenclature is again somewhat confused. Some authors make these a subcategory of lacerations and, when the weapon is relatively blunt (as in some axe or spike injuries), there may be sufficient crushing and bruising of the wound margins to make differentiation between incised and lacerated wounds difficult.



FIGURE 4.32 *Transection of a body into two halves at waist level. The victim jumped from a high-rise building and landed on a fence.*

The term 'incised wound' usually covers all types of injury from, for example, a knife, sword, razor, glass or sharp axe – though some writers would make stab wounds a separate category, reserving incised wounds for injuries that are longer than they are deep. These semantic variations are not important in themselves, but can lead to confusion in medical and autopsy reports, as well as in oral testimony if the doctor fails to clarify his meaning. The essential feature of all incised wounds is the clean division of the skin and underlying tissues so that the margins are almost free from any damage. Microscopically there is always a narrow zone of injury, but this is minimal compared with the tissue destruction caused by blunt injury. Healing is affected, as well as the extent of subsequent scarring.

Cuts or slashes

When an incised wound is longer than it is deep, it may be referred to as a 'cut' or 'slash', though a 'cut' may also be used by lay persons to describe a laceration. Such slashes when inflicted by knife, sword, razor, cleaver, parang, machete, panga, broken glass or bottle, are typical of a fight, when the assailant strikes out with a swiping action, rather than the thrust of a stabbing attack. They are common in gang fights and bar-room brawls and the weapon may be swung at arm's length in a horizontal arc so that if it contacts a body it will slice the skin and tissues as it passes by. They are also seen in suicidal injuries, usually on the wrist or throat. The characteristics of any given wound are a matter of a chance and relative positions. The slash may be deeper at the entry end or the exit point, though it seems true that many such injuries tend to dig in near the point of first contact and become progressively more shallow as the wound approaches the distal end. There may be a superficial 'tail', a shallow scratch, running out of the termination of the slash, as the weapon rises out of the wound and is drawn across the skin surface before leaving the body altogether.

There is a tendency among advocates to visualize a fight as a static confrontation and to attempt to reconstruct events as if the two participants were standing still, the assailant merely moving his arm. This is an unrealistic interpretation, as all fights are dynamic, with constant relative movement of the bodies and limbs of both parties. Therefore any relative angles and depths of contact between the victim and the weapon can occur and overinterpretation and simplification should be avoided.

Slashed wounds are less dangerous than stabs, as the relative shallowness of the wounds is less likely to affect vital organs – especially as the arms and face are the common targets. The rib cage and skull protects the chest organs and



FIGURE 4.33 *Homicidal slashed wounds caused by knife; the length is greater than the depth, unlike stab wounds. The long tails are due to the knife rising from the skin, thus indicating the direction of the slash.*



FIGURE 4.34 *A knife slash of the back showing regular scratches along the margin. This was inflicted with a 'Rambo' knife, which has deep serrations along the back edge that have somehow marked the skin on withdrawal.*

brain and the more vulnerable abdomen is seldom the target for a swung knife. Wounds of the neck are the most dangerous and are discussed below. Bleeding is the most serious complication of any slashed wound, though it will be external and more amenable to immediate treatment than the hidden internal bleeding of a stab wound.

A particular form of slashed wound arises from 'glassing', that is, the use of a broken drinking glass or bottle as a weapon. The glass may sometimes be broken prior to the attack, to produce edges that are exquisitely sharp. There may also be spikes of glass, which can inflict deep, almost stab wounds. Where, more commonly, a glass or bottle is used as a blunt instrument, it may shatter on impact with a victim's head, and the resulting injuries may both be blunt and incised.

Stab wounds and penetrating injuries

These are of major importance in forensic pathology, as they are extremely common in homicide. In Britain, stabbing with a knife is easily the most frequent mode of murder and manslaughter, primarily in domestic disputes and street violence. A stab wound is an incised wound that is deeper than it is wide. Though many penetrate only the skin and subcuta- neous tissues, those seen by forensic pathologists are most often fatal, having entered vital deep structures. Several aspects of this important topic need discussion.

THE NATURE OF STABBING WEAPONS

Knives are the weapons most frequently involved and their physical characteristics are important in shaping the wound. A pathologist called upon to examine a knife that may have been used in an assault should note and measure:

- the length, width and thickness of the blade
- whether it is single or double-edged
- the degree of taper from tip to hilt
- the nature of the back edge in a single-edged knife (for example, serrated or squared-off)



FIGURE 4.35 *A stab wound and the inflicting knife. The wound is slightly shorter than the width of the blade at the depth of penetration because of sideways gaping and the contractile elasticity of the skin.*

- the face of the hilt guard adjacent to the blade
- any grooving, serration or forking of the blade
- most importantly, the sharpness of the edge and especially of the extreme tip of the blade.

Other knife-like weapons include scissors, chisels, swords, open razors and sharp tools of many kinds, including deliberately modified tools such as sharpened screwdrivers. Larger cutting instruments such as axes, choppers, parangs, machetes and pangas and agricultural implements such as shears, bill-hooks, hay-knives and many others have been used as stabbing weapons when used by the point rather the long edge.

Spiked instruments come in many forms, from icepicks to hay-forks, from case-openers to fire-irons. The appearances of their wounds vary with the physical nature of the implement. Some weapons are exquisitely sharp and the wounds made by them exhibit extremely fine division of the tissues. To razors and razorblades may be added surgical and craft knives, often with a disposable blade, together with carpet and general utility and hobby tools, such as the 'Stanley' knife. Equally sharp is broken glass and sometimes porcelain. Both sheet glass and smashed glass utensils can provide edges that equal or exceed surgical scalpels in their cutting ability.

A common weapon in a bar-room fight is a smashed beer tankard, which when held by the intact handle provides a formidable weapon for both slashing and stabbing. Smashed china, such as cups and mugs, can also provide sharp cutting edges. The external glaze can project, if the fracture line is oblique, producing a glass-like edge. From personal experiment, the author (BK) has shown that broken china can easily slice through the full thickness of skin and thus validate a defence that injuries were the result of falling on a broken mug.



FIGURE 4.36 *Two knife wounds in the back. The wounds have a sharper lower edge compared to a rounder upper edge, due to a one-edged blade.*

THE CHARACTERISTICS OF A STAB WOUND

The surface and internal appearances of a stab wound allow the pathologist to offer an opinion upon:

- the dimensions of the weapon
- the type of weapon
- the taper of the blade

- movement of the knife in the wound
- the depth of the thrust
- the direction of the thrust
- the amount of force used.

Dimensions of the weapon

The dimensions of the knife may be a vital part of the investigation of a homicide when the weapon has been removed from the scene by the assailant. The pathologist can sometimes assist the investigators by telling them, within limits, what size and type of knife to seek. When suspect weapons are recovered, his inspection of them may indicate whether or not they are consistent with having caused the wounds in question. As always in forensic medicine, however, caution must be employed and the cardinal sin of overinterpretation avoided.



FIGURE 4.37 *A stab wound gapes across its width and shortens in length, especially when across skin or muscle planes.*

The length of the wound should be measured to the nearest millimetre as it lies undisturbed on the skin. In most instances the wound will have gaped across the centre, to form a long ellipse. The extent of gaping will depend on the anatomical situation, for example, over joints or in the axilla or groin, and whether the axis of the stab is in line with or across the tension of Langer's lines or underlying muscle bundles.

When the edges are gently opposed, the length of the wound may then extend slightly and should be measured again in this position, which more accurately approximates to the length when the blade was *in situ*.

An important additional factor, however, must always be taken into account because, when the knife is withdrawn the elasticity of the skin causes it to retract, making the wound smaller than when the blade was *in situ*. This mechanism may be amplified by contraction of the underlying muscles, which, if at right angles to the axis of the wound, may cause the wound to shorten from end to end, while gaping more widely at the centre. Using wound measurements to predict the size of the knife blade, one must take into account the other matters discussed below, such as movement of the blade in the wound, the taper of the blade and the depth of penetration.

Type of weapon

The type of blade usually refers to whether it had a single or double cutting edge. Most knifes have a single sharp edge, the back edge being blunt or otherwise machined. A few dagger-like weapons have both edges ground to sharpness,



FIGURE 4.38 *Multiple stabs on the back from the same knife, showing differing shapes and sizes.*



FIGURE 4.39 *A stab wound showing a unilateral 'fish-tail' split caused by the blunt back edge of the knife blade. This is sometimes bilateral due to tearing of the tissues. The other end of the wound is pointed due to the cutting edge of the blade.*



FIGURE 4.40 *Multiple stab wounds from the same knife, showing variations in the size and shape of the injuries. With multiple injuries, it is advisable to number each to facilitate easy reference in the autopsy report and when giving evidence in court.*

some have only the distal part of the back of the blade sharpened. On inspecting the skin wound, the pathologist frequently finds that both ends of the defect appear sharply cut, coming to a fine 'V-point' at the extremities. Unfortunately, this does not necessarily indicate that a knife with two sharp edges was used, as the skin often splits behind the blunt edge to produce a symmetrical appearance.

If, however, there is an obvious difference between one sharply pointed end and a rounded or even square-cut opposite extremity, then it can be said with some confidence that a single-edged knife was employed.

A knife with a thick blade that is squared off to a flat surface on the edge opposite the cutting edge, may sometimes be identified from the wound, where a definite double right-angled end to the skin defect is apparent. The skin may split back slightly from each of these corners, forming the so-called 'fish-tail' appearance.

Where a knife with a serrated back edge has been used, such as is found on some boy scout or other Bowie-type knives (or the recently fashionable 'Rambo' weapons), the back edge of the wound may be torn or ragged and – on some occasions where the knife has entered very obliquely – serrated abrasions may be seen on the skin adjacent to the end of the wound.

If the knife has been plunged into the full extent of the blade, then there may be a hilt bruise or abrasion on the skin surrounding the wound. This may even reproduce the pattern of the guard at the base of the hilt, if there is one. Careful photography, sketches and measurements are needed to capture the exact outline of such a mark, which are, admittedly, unusual.

Taper of the blade

The taper of the blade is naturally related to wound size. If a tapered blade is inserted to 4 cm, then the length of the wound (ignoring skin retraction for the moment) will be that of the width of the blade at that level. If the taper continues to the 8 cm level, then the wound will be correspondingly longer. Only when the blade edges become parallel will the wound size remain constant for further penetration of the knife.

Movement of the knife in the wound

Movement of the knife in the wound can result in loss of evidence as to the size of the blade, but can also add other information. Where a knife is stabbed directly into the body and withdrawn along the same track then, within the limits discussed above, the size of the wound will indicate the minimum width of the blade at the maximum depth of penetration.

If, however, the knife is 'rocked' in the wound, the skin defect will be enlarged, sometimes considerably. The term 'rocking' means a leverage or angulation in the plane of the wound, so that the cutting edge extends the incision. This rocking can occur either by the knife being actively moved in the wound by the assailant – or by the body moving relative to the knife – or by a combination of the two.

It is sometimes a misapprehension among both doctors and (especially) lawyers, that stabbings and other assaults occur in static circumstances, with the victim standing in the anatomical position. Directions of wounds are all too often interpreted as if the only movement came from the hand of the assailant, whereas in most fatal assaults the



FIGURE 4.41 *A slashed facial wound from a knife, showing undercutting or 'shelving' on the edge nearest the mouth, indicating the angle of the knife relative to the surface. The tailed nature of the lower end also indicates that that knife was drawn downwards across the face.*



FIGURE 4.42 *Forcible stabbing can indent the body surface so that deep structures can be injured that appear to be beyond the reach of the knife.*

victim bends, turns and twists, and the assailant often follows with similar gyrations. Thus a knife that is thrust into the body may itself move or the body may move against it before it is withdrawn.

This relative movement may extend the wound in a linear fashion, as described above or there may be twisting of the blade in the wound. In the latter case, the resulting skin incision may be V-shaped or totally irregular. Rarely, a single stab may produce multiple skin wounds, such as a tangential stab of the arm, which passes through the superficial tissues and then re-enters the chest wall. Another instance is a stab through a female breast where, especially if the breast is sagging, the knife can pass right through the edge before re-entering the thorax.

Depth of the thrust

The depth of a stab wound may be important in attempting to assess the length of a missing weapon. Again there are pitfalls to be avoided. First, if a knife is driven in up to the hilt, the depth of the wound as measured at autopsy may be greater than the true length of the blade. This is common in the abdomen and to a lesser extent in the chest, because the impact of a forceful stab may momentarily indent the abdominal or chest wall so that the tip of the knife penetrates tissues that apparently should have been out of reach. This is particularly so when the hilt guard of the weapon impinges on the skin. For example, the author (BK) has seen the tip of a broken knife embedded in a thoracic spine, where the distance from that tip to the anterior skin wound was less than the length of the blade when recovered.

As with direction, discussed below, the pathologist must also allow for differences in the position of internal organs as measured at autopsy in a supine body, compared with their position in the living body, often in the upright posture. Such variations in the *in vivo* distance from the skin wound to the organs penetrated must be taken into account when assessing the depth of a wound. In the chest and abdomen, visceral relationships vary with the stage of respiration. The lower ribs move upwards and laterally, and increase the distance between the skin and deeper structures.

Direction of the thrust

The direction of a stab wound is often a matter of contention in homicides, especially as trial lawyers (and their medical advisers) sometimes tend to overinterpret the facts when trying to reconstruct the scene of the fatal assault.

As mentioned above, a stabbing incident is often moving and dynamic, and the victim is rarely in a static, anatomical position. For example, a wound that enters the upper part of the left side of the chest and travels steeply downwards, is not inevitably the result of the killer being taller or situated above the victim, using a downward blow. The victim could equally well have been bending or crouching, the knife then entering on a horizontal plane relative to the floor. All that the pathologist can do is to determine the direction of the wound relative to the axis of the body – it is then a



FIGURE 4.43 *Multiple stab wounds from the same knife. Although those at the bottom left are obviously square-ended, the more central ones are almost equally sharp at the extremities – illustrating the dangers of being too dogmatic about describing a missing knife to the investigators.*



FIGURE 4.44 *Homicidal stab wounds misdiagnosed by an attending doctor as 'haematemesis or epistaxis'. The lower right wound clearly shows evidence of a single-edged blade. The wound in the left axilla is V-shaped because of the twisting knife.*

matter of non-medical evidence to relate that to the posture of the victim when struck.

Determination of the direction relies on both the appearance of the skin wound and the track in the deep tissues. Where a knife penetrates the skin with the plane of the blade at appreciably less than a right angle to the surface, the wound is often 'undercut', being shelved so that subcutaneous tissue is visible below one edge of the wound. Where the knife is plunged in obliquely, but the plane of the blade remains perpendicular to the surface, no such shelving can be seen at the sides of the wound though it may just be visible at the end of the wound.

More information about direction comes from careful examination of the track of the stab wound. This is an anatomical exercise during autopsy, the layers of tissue being examined in sequence from the surface downwards and damage to deep structures and organs compared with the position of the surface wound. For example, a stab wound of the chest may lie below the left nipple. Dissection of the subcutaneous tissues and muscles may reveal that the defect in the chest wall lies in the sixth intercostal space and that, inside the thorax, the right ventricle of the heart has been transfixed, and that there is a wound in the diaphragm that terminates in the liver just to the right of the midline. This information obviously indicates that the direction of the wound was downwards and from left to right. Similar deductions can be made for all other sites, but caution must be exercised, as mentioned earlier, in allowing for the change in position of organs in the supine post-mortem posture compared with the erect, living state. A thorough knowledge of surface anatomy is required, especially of the thorax, as well



FIGURE 4.45 *Multiple homicidal knife wounds, all inflicted with the same weapon. This shows the marked variation in wound size from the same knife, caused by rocking and twisting movements of either weapon or victim.*

as diagrams of the position of internal organs mapped out in relation to surface markers; samples of such diagrams are given in this book.

Attempts have been made to delineate the track of a stab wound before dissection either by filling the defect with a radio-opaque fluid before taking X-rays, or by filling with a plastic or even metallic substance that will harden to form a cast. In practice, these methods appear to have little advantage over careful dissection. When radio-opaque liquids or pastes are used, there is often leakage from the stab wound into the thoracic or abdominal cavities, leading to a confusing radiological picture. Recently, magnetic resonance imaging (MRI) has been used to visualize the wound track, but such facilities are rarely available for dead victims.

Estimation of the degree of force used in stabbing

The amount of force required to inflict any given stab wound is often a matter of extensive debate in criminal trials. The prosecution naturally gains from showing that a stabbing was inflicted with 'considerable force', sometimes even using pejorative terms such as 'violent' or 'frenzied'. This tends to confirm the intention to stab, whereas the defence proposition is often that the victim inadvertently fell or was pressed against a weapon held passively by the accused. An expert medical witness has difficulty in replying to the almost inevitable question by counsel: 'What amount of force was necessary to cause this wound, doctor?'

Assessment of force is subjective and cannot be quantified in any satisfactory way that is meaningful to the court. Physical units such as dynes/cm^2, even if they can be measured, mean nothing to a judge and jury. The only measure that the medical witness can offer is a broad grading, based on common sense knowledge, such as 'slight pressure', 'moderate force', 'considerable force' and perhaps 'extreme force', the latter being reserved for exceptional cases where the knife has impacted in dense bone, penetrated the skull, or left a marked bruised impression of the hilt guard on the skin. A number of investigators, including the author (BK), have carried out measurements on the force needed to inflict stab wounds, both in animal, cadaver and surrogate tissues. The usual method is to attach some type of dynamometer or transducer to a knife, which records the maximum force applied during penetration, preferably with the duration of impact.

From this work, the following useful generalizations can be made.

- Apart from bone or calcified cartilage, the tissue most resistant to knife penetration is the skin (Knight 1975), followed by muscle where large muscle bundles underlay the fascia.
- The sharpness of the extreme tip of the knife is the most important factor in skin penetration. The cutting edge of the knife, once the tip has penetrated, is of relatively minor importance.
- The speed of approach of the knife is particularly important in achieving penetration. A knife held against the skin, then steadily pushed, requires far more force to penetrate than the same knife launched against the skin like a dart. As in blunt injury, this is an example of the physical law that requires that the force varies directly not with the mass of the weapon, but also with the square of the velocity.
- Stretched skin is easier to penetrate than lax skin. The chest wall, where skin tends to be intermittently supported by underlying ribs, is relatively easy to puncture with a sharp knife as the skin and tissues are stretched over intercostal spaces in the manner of a drum membrane.
- Though the thick skin of the palms and soles is much tougher than on the rest of the body, the variation in resistance of the rest of the skin to a sharp knife is of little importance compared with other factors. Similarly, the skin of the aged, or of women, is not appreciably less resistant to a sharp point than that of men or young persons.
- When a knife-point impacts against skin, the latter dimples and resists until penetration suddenly occurs. The tension developed in the stretched skin appears to act as an ‘elastic reservoir’ and, when the threshold of resistance is exceeded, the knife ‘falls’ through the subcutaneous tissues without any further force being imparted to it unless impeded by bone or cartilage. Thus no additional effort is needed by the assailant to achieve deep or even full penetration up to the hilt. It is sometimes incorrectly claimed by the prosecution that a deep stab wound must imply extreme force or continued pushing after penetration. This is not so and experiments have shown that once penetration occurs, it is difficult or even impossible to prevent deep penetration because of the suddenness of the breakthrough.
- When the knife penetrates the skin rapidly, for example, if the body falls or runs on to the blade, the knife does not need to be held rigidly in order to prevent it being pushed backwards. Its inertia, if the tip is sharp, is quite sufficient to hold it in place while the body spears itself on the blade.



FIGURE 4.46 *A stab wound of the centre of the chest. Although each end of the wound is identical, the weapon was a single-edged kitchen knife. The end of the wound adjacent to the back of the blade has split making it impossible to say if a single- or double-edged knife was used. The sternum beneath was penetrated to reach the heart, so considerable force must have been used.*

It has been wrongly argued against a defence of falling or running onto a knife, that the hilt would have had to have been supported against, for example, the hip of the person holding the knife to immobilize it against the advancing body. Experiments have shown that this theory is invalid.

Uncalcified cartilage, especially that in the costal cartilages of young and middle-aged persons, is easily penetrated by a sharp knife, though naturally more force is required than if the blade passed through an intercostal space. Calcified rib and bone provide a much more resistant barrier, but a forceful stab from a strong, sharp knife can easily penetrate rib, sternum or skull. Firm tissues like myocardium, liver and kidney are easily traversed by all but the most blunt of weapons, and their resistance is far less than that of cartilage or skin.

INJURIES BY WEAPONS OTHER THAN KNIVES

The general features of injuries from knives apply equally to other sharp objects that cause incised and stab wounds. Razors and broken glass have extremely sharp edges so that, when applied tangentially or at a small angle to the skin, undercutting may be a marked feature. The wound may appear as a shallow slice which bleeds profusely and, in a hairy area such as the scalp, it will reveal cut hair bulbs on the shelved surface. Deliberate wounds with razors or sharp knives may exhibit patterns or even words; these may occur in gang fights or sadistic homicides.

Glass can be employed as a cutting weapon, again typically in bar fights or gang vendettas, where a broken bottle may be beld by the neck or a smashed beer tankard by the handle.



FIGURE 4.47 *Three wounds from a single stab with a knife, which was in place when the body was discovered. The knife had entered obliquely through the inner side of the right breast, emerged into the cleavage and re-entered the mid-line. If the knife had not been in situ, interpretation could have been more difficult.*



FIGURE 4.48 *Homicidal stab wounds of the throat and head showing the pleomorphism of injuries caused by the same knife. The wound under the chin is V-shaped caused by twisting of the weapon; the large throat wound consists of several superimposed thrusts and over the manubrium there is a 'tail' caused by the tip of the knife slipping out of the wound on withdrawal.*



FIGURE 4.49 *Multiple homicidal stab and incised wounds inflicted with various kitchen utensils.*



FIGURE 4.50 *A wound over the eyebrow caused by impact from a broken drinking glass. Although this location is commonly the site of laceration from blunt blows, this injury is sharp-edged and has unbruised margins, indicating that it is an incised wound. There is an associated abrasion from non-cutting contact and there is bleeding into the upper eyelid, probably from gravitational seepage from the wound.*

Official estimates in Britain suggest that between 3400 and 5400 offences occur annually in which glass is used as a weapon. Surveys in London and Bristol by Shepherd *et al.* (1990a) and Hocking (1989) showed that bar drinking glasses were the most common weapons, and that 75 per cent of these were from straight-sided pint glasses. Unexpectedly, this research showed that most of the glasses were intact until thrown or thrust at the victim – they had not been smashed prior to the assaults. Most of these non-fatal injuries were to the face. The fragility of these glasses varies greatly from manufacturer to manufacturer, so that there can be a sixfold difference in their propensity to smash on impact.

Though these formidable weapons are usually used for slashing, long slivers of glass can act – sometimes inadvertently – as stabbing agents. The sliver may break off and remain in a deep wound, which may be overlooked if the entry is small.

As many casualty surgeons have learned to their cost – or to the cost of their medical protection society or medical insurers – glass is almost invariably radio-opaque, even though this is either unknown or even denied by the doctor. Numerous civil actions for negligence have occurred – though usually in non-fatal circumstances – but, on occasion, the first person to find a deep fragment of glass in a vital position has been a forensic pathologist.

As mentioned earlier, broken china and porcelain, as from a smashed cup, mug or plate, may have a sharp edge on the exposed glaze and can easily cause a slashed wound.

INJURIES FROM SCISSORS

Stabbing by a pair of scissors is not uncommon and is seen most often in domestic circumstances where a woman uses a weapon upon her husband or consort which is both familiar and near to hand. The appearances of the wound will



FIGURE 4.51 *Incised wounds, which in spite of their large size are typical of those inflicted by a sharp-edged weapon rather than a crushing laceration. The instrument was a butcher's cleaver.*



FIGURE 4.52 *Various profiles made by scissors stabbed through the skin. The cross shapes are caused by blade screws or rivets; the one on the right is a full penetration of one blade of an open pair of scissors, the other blade impinging flat on the skin.*

differ according to whether the scissors were used open or closed. If open and one blade is stabbed into the victim, then the appearances will be virtually indistinguishable from a knife wound. Some modern scissors, however, have a two-part blade in which a steel cutting edge is riveted to a carrier continuous with the handles. This may produce a stepped wound that may show a notch or variation in linearity in the margin of the stab wound.

More characteristic is the wound produced when both blades of a closed pair of scissors are plunged through the skin. Some scissors have a double-sharp point, but most domestic, tailors' or dressmaking scissors are fairly blunt at the tips when closed, so considerable force is needed to drive them through the skin – tending to work against a defence of an accidental movement against a passively held weapon.

The skin wound made by closed scissors is typically shaped like a flat 'Z' or the usual impressionist sign for a flash of lightning. The offset of the two blades gives this shallow zig-zag pattern, which is unmistakable when present. Some scissors, however, especially long narrow ones in which the blades close almost completely over one another, may not reproduce this appearance and the wound may look more like that from a thick knife. Sometimes, there are small lateral splits in the wound centre from a projecting hinge screw.

DEFENCE WOUNDS

In assaults of any kind, the natural reaction of the victims is to protect themselves. The limbs used for protection can themselves be injured and these defence wounds may be of considerable medico-legal significance, as they indicate that the victim was conscious, at least partly mobile and not taken completely by surprise. Defence wounds can be sustained from attacks by fists, feet and blunt or sharp instruments. The classic position for them is on the forearms and hands, which are instinctively raised to protect the eyes, face and head. Other defence injuries may be inflicted on the thighs, when attempts are made to shield the genitals.

With attacks from blunt instruments or fists, bruises are the hallmark of defence attempts. They are common on the outer sides of the forearms, the wrists, the backs of the hands and knuckles. The size and shape of the bruises naturally depends upon the attacking object. Abrasions may accompany the bruises but the latter are more common. Fractures of the carpal bones, metacarpals and digits may occur. If the arm is held in front of the face, the inner (palmar) side of the forearm may also receive blows. There may also be defence bruises and abrasions on the thigh, as blows or kicks aimed at the lower part of the body cause the victim, especially men, to protect the genitals. The leg may be brought across the other or the thigh raised, so that its outer side may receive blows or kicks.

The most obvious defence injuries are seen in knife attacks, as the victim often attempts to ward off the thrusts by seizing the weapon. When the fingers are closed around the blade, its withdrawal cuts across the flexures of the phalanges, slicing through the skin and perhaps tendons, or sometimes all four fingers. This may be seen in one, any, or even all of the three sets of flexures.



FIGURE 4.53 *Multiple homicidal stab wounds by closed scissors.*



FIGURE 4.54 *Defence injuries: bruising on the back of the hand in an attempt to fend off a blunt instrument in this case a metal poker that was used to inflict fatal head injuries. Such injuries confirm that the victim was conscious and active during the attack, and that it was not made covertly while the victim was unaware.*

The other typical knife defence wound is in the web between the base of the thumb and index finger, when the blade is grabbed in an attempted pincer action. Other knife wounds can be on the backs of the hands or fingers from non-grasping movements trying to ward off the weapon. Defence wounds from knives are often sharply sliced, as the blade is drawn across the tightly applied skin. They are often markedly 'shelved', with loose flaps of skin and copious bleeding.

Defence wounds also occur in firearms injuries, where an arm is raised in a desperate attempt to shield the trunk or head from the blast. This accounts for some shooting deaths where there is an entrance and an exit wound in (often) the upper arm, the missile(s) then repenetrating the trunk.

DATING OF WOUNDS BY HISTOLOGY AND HISTOCHEMISTRY

There are many publications on this subject, as it is a favourite topic for research. As with time of death, it can be an important matter in forensic medical investigations to determine whether a wound found at autopsy was inflicted before or after death and, if inflicted ante-mortem, how long before death it was sustained.

Unfortunately, as with so many problems, biological variability introduces a wide margin of uncertainty, so that a range of probabilities can be offered, but never a definite time interval. Much of the experimental work has been performed on animals and the results are not transferable to man – a common defect in all animal work. The smaller



FIGURE 4.55 *Defence wound on the back of the hand from trying to ward off the knife.*



FIGURE 4.56 *Typical defence injuries in a victim of a knife attack. In grasping the blade to deflect it, there have been cuts across the palmar surfaces of the finger joints and a slash between the thumb and forefinger, together with a cut at the base of the thumb.*

the animal, the more rapid the tissue scavenging and reparative changes: more primitive animals have far greater powers of regeneration than man, both in wounds and in regrowing organs and even limbs.

The changes will also vary according to the size of a wound, the type of wound (bruise, abrasion, incision or laceration), the tissue (epidermal or mesodermal), whether there is infection and the age and health of the victim.

The subject is complex and often contradictory and the following schedule of events is offered only as a guideline. The original papers should be consulted if any particular criterion is to be followed; histological appearances, including fluorescence studies may be backed up by histochemical and biochemical assays. The sequence of changes in bruises is far less distinct than in abrasions or lacerations and histology is much less helpful. The most useful criterion in a bruise is probably Perl's reaction for haemosiderin, which becomes positive about 3 days after infliction – though some workers claim an earlier appearance, even down to 12 hours. Haemolysis of red blood cells is irregular and patchy, many intact cells being seen in some bruises after many days, so their rupture and ghosting cannot be used as an index of age.

Chronological histological changes after wound infliction

30 MINUTES–4 HOURS

Margination of polymorph leucocytes in dilated small vessels may occur, a feature which is often completely absent. It is also not a reliable sign of ante-mortem infliction, as



FIGURE 4.57 *Defence wounds of hand in attempts to ward off an assault with a meat cleaver.*

leucocytes may congregate for many hours after death, especially in skin and around aspirated material in the lung.

Some extravascular emigration may begin at the end of this period, but a significant number of polymorphs usually delay for many more hours. Polymorphs tend to appear earlier in the subcutaneous fat than in the upper dermal layers. Basophilic 'mast cells' lose their granules. Fibrin appears in the wound within a few minutes, but this also occurs in post-mortem injuries.

4–12 HOURS

Leucocyte infiltration is likely to be more definite, still mostly polymorphs, but some mononuclear cells as well. A scanty mixed population of lymphocytes and poorly differentiated 'monocytes' appears, usually after 12 hours. Tissue oedema and swelling of vascular endothelium occurs. In small wounds involving the skin, the start of epithelial regeneration may be seen at the sides at the level of the basal layer of epidermis.

12–24 HOURS

Leucocytes tend to demarcate the area of the wound by forming a marginal palisade. The polymorph response declines and the macrophage and mononuclear cell population increases from now on. Removal of necrosed tissue begins, with macrophages evident and a basophilic tinge to the ground substance. Mitoses are visible in fibroblasts from about 15 hours. The epidermis begins to spread across the surface of the scab and down the sides of a cut into the wound.

24–72 HOURS

Leucocyte infiltration reaches a peak at about 48 hours; repair begins concurrently with many fibroblasts appearing, but rarely before 72 hours. New capillaries then begin to bud from vessels, the vascular, infiltrated stroma becoming 'granulation tissue'.

3–6 DAYS

Repair is proceeding apace: collagen begins to form and giant cells may be visible around necrotic debris and foreign matter. The epidermis is actively growing if the wound involves the surface: in animals, it grows laterally at about 200 μm/day. Haemosiderin becomes stainable from about the third day onwards, if there is a bruise or any bleeding into the wound, but is often not obtainable by Perl's reaction until the fifth day even though some claim it can appear on the first or second day.

10–15 DAYS

Cellular reaction subsides in small wounds. Vascularity decreases and the cell population drops, especially leucocytes. Fibroblasts are most active, with collagen being laid down. The epidermis becomes thin and flat, but no papillae ('rete pegs') are reformed for many weeks. Elastic fibres are scarce for a long time and less than in adjacent undamaged tissue.

TWO WEEKS TO SEVERAL MONTHS, DEPENDING ON SIZE AND OTHER FACTORS

Consolidation of the healing tissue continues. The inflammatory response has vanished, unless the wound has become infected. Collagen and elastin increase and a vascular scar is formed, which gradually becomes more dense and avascular. The epithelium remodels and dermal papillae reappear unless the wound is wide and irregular. Skin adnexae do not reappear in the scar unless islands of viable skin survive within the wound area.

Histochemical changes in injured tissues

Histochemical and immunohistochemical methods have been studied widely in recent years, again mainly on animals, the transfer to the human situation being suspect in some cases. A wide variety of markers have been claimed as reliable for both the differentiation between ante-mortem and post-mortem injuries and for dating of ante-mortem wounds.

Electrolytes, such as sodium, zinc, magnesium and calcium, serotonin, esterases, glycophorin A and especially histamine have been used for this purpose.

Mainly as a result of the pioneering work of Jyrki Raekallio in Finland, the histochemical sequence of events in wounds has been actively pursued in recent years. Some techniques need frozen sections, others can be carried out on fixed tissue. Estimations of histamine or serotonin are usually 'tube' methods, rather than microscopic, though some fluorescent techniques have been developed. Betz and his co-workers have also published extensively on the immunohistochemistry of wound dating.

At the present time these methods still remain mainly in the realm of the research laboratory, apart from a few enthusiasts who employ them in casework. For the histochemical novice, it would be unwise to put such procedures into evidence without first gaining extensive experience of control material. Experience emphasizes that strictly standard conditions are required for the production of such histochemical sections, the end result depends largely on laboratory procedures – 'change your technician and you change the answer'.

A list of standard procedures for some of these reactions is given in Appendix 1.

The following are some of the histochemical wound changes described by Raekallio and others:

- In a wound through the skin surface there is a central zone 0.2–0.5 mm wide that will become necrotic and in which enzyme activity rapidly decreases. This may be termed 'negative vital reaction'. Immediately beyond this layer, is a 0.1–0.3 mm zone of reaction and eventual repair, where a number of enzymes and other substances become increased in concentration during the reparative process, compared to the normal level in the areas outside the wound. Enzymatically, this can be called 'positive vital reaction', as no such zone develops in a post-mortem wound.
- Within one hour after injury, esterases and adenosine triphosphatase increase in the positive zone. At around 2 hours, aminopeptidase activities increase and, at 4 hours, acid phosphatase activity increases. Alkaline phosphatase activity is delayed another hour or so though, of course, all these times are relative and subject to the usual biological variability.
- Where death occurs at some stage of this process, the enzyme pattern is 'frozen' at that point and post-mortem changes do not substantially alter the reactions within a few days after death, especially if autolysis is kept at bay by refrigeration. Senility, severe illness and cachexia, as well as widespread multiple injuries, may distort the usual pattern by reducing the ability to produce these reparative enzymes. In contused wounds, the reactions are less useful than in cutaneous injuries, as the damage is more diffuse and there are no definite 'zones'.

  In all wounds, lack of reaction cannot be taken as indisputable proof of a post-mortem origin, though, if the opposite occurs, positive increase in the outer zone must only be the result of a vital reaction. Other enzymes have been used for wound dating: the review by Janssen (1984) in his authoritative book on forensic histology should be consulted for details, as well as the work of Betz.
- Tissue cathepsins are said to increase almost immediately if the stroma is damaged, being demonstrable within 5–10 minutes. Two other substances are of use in establishing that wounds are ante-mortem and giving some idea as to their age. Both are produced during the inflammatory response that accompanies tissue damage – histamine and serotonin (5-hydroxytryptamine). They tend to be complementary to the enzymes, as they appear soon after infliction, within the hour or so before adenosine triphosphatase and esterases become detectable.

  These vasoactive amines appear in maximum concentration about 10 minutes (serotonin) and 20–30 minutes (histamine) after wounding. One of the first demonstrations of this forensic aid was by Fazekas and Varagos-Kis (1965), who showed that a ligature mark in hanging revealed increased serotonin; presumably the hanging was atypical and the victim took 10 minutes to die which is rather unusual. For the employment of the test in human autopsy work, about 2 grams of skin freed from subcutaneous fat are sampled, together with a similar control sample from a nearby normal area of skin from the same corpse. This is to allow for the markedly different amounts found in different people and, indeed, in the same persons at different times.

  To establish that a wound was ante-mortem rather than inflicted after death, the level of histamine in the wound must be at least 50 per cent greater than the control sample – and, for serotonin at least, twice the concentration of the control skin.

SURVIVAL PERIOD AFTER WOUNDING

A pathologist is often asked either by police during an investigation, or by counsel at trial, what was the probable interval between the fatal injuries and death? A supplementary query is how long would the victim have been active, even if still alive?

These are extremely difficult questions to answer, as a number of variables enter the estimation. The doctor should never give a dogmatic answer, unless the nature and severity of injuries are obviously incompatible with continued life or activity.

A person who has his brainstem destroyed by a penetrating injury, or his aortic arch completely transected, will be inactive and clinically dead almost immediately. It would not necessarily be the case if his frontal lobes were damaged or his abdominal aorta was crushed by a railway wheel. Extraordinary instances of survival in both these latter instances are on record.

An opinion should always err on the side of caution in expressing opinions on this subject, as victims can do far more than might be expected after injury. The author (BK) once dealt with a homicide in which the victim was stabbed through the heart, yet ran more than a quarter of mile before collapsing. A wound in the left ventricle can partly seal itself by the contraction of the muscle around the defect and collapse may only occur when sufficient blood has leaked into the pericardium to form a tamponade. Wounds of the right ventricle are often more rapidly fatal as, although the pressure of contained blood is less, the thinner wall is not so effective in preventing the leak.

Head injuries can present many paradoxical instances of prolonged survival, depending partly on what part of the brain is injured. As mentioned, frontal lobes seem remarkably resistant to damage and it is often the generalized head impact, rather than focal damage to this area, that causes most harm. For example, a Finnish man who committed suicide made a home movie of himself firing a pistol into his brain. There was immediate collapse but, just at the end of the 4-minute film, the victim opened his eyes and raised his head, finally dying some uncertain time after the spool ran out.

In the more usual stabbing, head injury, cut throat or shooting, the pathologist must try to assess the nature and severity of the physical damage, and relate that to the age, health and environment of the victim. This is naturally an imprecise exercise. A senile old lady, or someone with severe cardiac or respiratory disease, is less likely to survive multiple injuries for as long as a robust young person – though if the nature of the injury is grossly life-threatening, these factors will make little difference.

A cut artery will lose blood faster than a vein of the same general size, especially if it is only partly severed so that it cannot retract. Other factors, such as the possibility of air embolism occurring in a cut jugular vein, might alter the usual pattern of expected events. The heart is less vulnerable than great thoracic vessels in many stab wounds, as mentioned above. Many wounds of the ventricles are survivable. The author (BK) has twice been warned by police of an imminent autopsy on victims admitted for emergency surgery – only to hear later that, thankfully, they had walked out of the hospital after a successful operation. One had a through-and-through stab wound of the left ventricle that transfixed the heart from front to back.

Where a wound has transected a major coronary artery, then prolonged survival is unlikely, as is one that interrupts a major branch of the conducting system. Other than injuries to the brain or to a large blood vessel, most other injuries can rarely be declared to have caused sudden death or rapid loss of function. In criminal cases, it may be a point of some importance to decide whether the victim could have continued fighting, have run away, have resisted, or even have inflicted injuries on someone else before collapsing and dying. It is difficult to swear that at least some activity was not possible in the great majority of instances. In the adrenaline response of 'fight or flight', the shock element of pain is greatly suppressed – many soldiers have been quite unaware of having sustained severe or lethal wounds until they notice the blood or the battle is over. Thus the usual 'shock' effect may be damped down considerably in an assault and only the sheer physical and haemodynamic sequelae of the injury will eventually lead to a slowing down, then collapse and death. In the interval, injured victims may be able to perform normal physical activity, sometimes to an astonishing degree, albeit followed by sudden deflation of their capacity for exercise.

As in most aspects of forensic medicine, it is unwise of the doctor to be too definite about these matters – the old forensic aphorism 'Seldom say never – seldom say always' is even more true here than usual.

Most issues of this nature revolve around periods of a few minutes, the perimortal or agonal time when few morphological signs are available. The more sophisticated enzyme and serotonin techniques mentioned elsewhere in this chapter may give some clue about the survival period, but are rarely unequivocal enough to be used as hard forensic evidence. If survival is longer, then both gross and histological changes of 'vital reaction', such as thrombosis, inflammation, infection and healing may be useful, but they usually require hours or even days of survival to appear.

The accepted wisdom of wound dating is that polymorph leucocytes begin to appear in wounded tissue within a few minutes, but it has been shown that this can happen even several hours after death, as all leucocytes do not become immobile with cardiac arrest. A good, conventional inflammatory response must be a vital reaction, however, though several hours survival is needed for it to be convincing. The author (BK) has seen a dramatic red flare caused by post-mortem burning at least 30 minutes after undoubted death from strangulation.

Another problem with differentiating 'ante-mortem' from 'post-mortem' injuries is the definition of the moment of death. Again, lawyers, judges and coroners tend to assume that death is an **event**, whereas, in reality, it is a **process** (Chapter 2). Though in most criminal or accidental deaths the moment of death is conventionally – and reasonably – taken to be the moment of cardiac arrest, and thus collapse of blood pressure and cerebral circulation, the cells of the body are still alive and remain so for a variable time – only minutes in the case of neurones, but leucocytes and muscle cells survive for many hours, and connective tissue cells, such as fibroblasts, for days. Thus, it is unreasonable to expect dramatic changes within minutes in skin wounds, etc., until progressive hypoxia alters biochemical processes and enzyme activity. Leucocytes may be motile for more than 12 hours and can aggregate around chemotactically active material, such as gastric contents aspirated into the air passages. This makes the 'vital reaction' a dubiously valid phenomenon in the perimortal period. Much more research is needed into the histology, histochemistry and biochemistry of the perimortal period to clarify these issues, but in the mean time, less dogmatic reliance must be held upon the old criteria of 'ante-' and 'post-' mortem phenomena and the 'vital reaction'.

REFERENCES AND FURTHER READING

Adams VI, Hirsch CS. 1989. Venous air embolism from head and neck wounds. *Arch Pathol Lab Med* **113**:498–502.

Ali TT. 1988. The role of white blood cells in post-mortem wounds. *Med Sci Law* **28**:100–6.

Betz P. 1994. Histological and enzyme histochemical parameters for the age estimation of human skin wounds. *Int J Legal Med* **107**:60–8.

Betz P. 1995. Immunohistochemical parameters for the age estimation of human skin wounds. A review. *Am J Forensic Med Pathol* **16**:203–9.

Betz P, Nerlich A, Wilske J, *et al.* 1992. Comparison of the solophenyl-red polarization method and the immunohistochemical analysis for collagen type III. *Int J Legal Med* **105**:27–9.

Betz P, Nerlich A, Wilske J, *et al.* 1992. The time-dependent rearrangement of the epithelial basement membrane in human skin wounds – immunohistochemical localization of collagen IV and VII. *Int J Legal Med* **105**:93–7.

Betz P, Nerlich A, Wilske J, *et al.* 1992. Time-dependent appearance of myofibroblasts in granulation tissue of human skin wounds. *Int J Legal Med* **105**:99–103.

Betz P, Nerlich A, Wilske J, *et al.* 1992. Time-dependent pericellular expression of collagen type IV, laminin, and heparan sulfate proteoglycan in myofibroblasts. *Int J Legal Med* **105**:169–72.

Betz P, Nerlich A, Wilske J, *et al.* 1993. The immunohistochemical localization of alpha 1-antichymotrypsin and fibronectin and its meaning for the determination of the vitality of human skin wounds. *Int J Legal Med* **105**:223–7.

Betz P, Nerlich A, Tubel J, *et al.* 1993. The time-dependent expression of keratins 5 and 13 during the reepithelialization of human skin wounds. *Int J Legal Med* **105**:229–32.

Betz P, Nerlich A, Tubel J, *et al.* 1993. Localization of tenascin in human skin wounds – an immunohistochemical study. *Int J Legal Med* **105**:325–8.

Betz P, Nerlich A, Wilske J, *et al.* 1993. Analysis of the immunohistochemical localization of collagen type III and V for the time-estimation of human skin wounds. *Int J Legal Med* **105**:329–32.

Betz P, Nerlich A, Wilske J, *et al.* 1993. Immunohistochemical localization of collagen types I and VI in human skin wounds. *Int J Legal Med* **106**:31–4.

Betz P, Nerlich A, Wilske J, *et al.* 1993. The time-dependent localization of ki67 antigen-positive cells in human skin wounds. *Int J Legal Med* **106**:35–40.

Betz P, Lignitz E, Eisenmenger W. 1995. The time-dependent appearance of black eyes. *Int J Legal Med* **108**:96–9.

Biddinger PW. 1987. Postmortem wound dehiscence. A report of three cases. *Am J Forensic Med Pathol* **8**:120–2.

Bohnert M, Baumgartner R, Pollak S. 2000. Spectrophotometric evaluation of the colour of intra- and subcutaneous bruises. *Int J Legal Med* **113**:343–8.

Byard RW, Gilbert JD, Brown K. 2000. Pathologic features of fatal shark attacks. *Am J Forensic Med Pathol* **21**:225–9.

Camps FE. 1952. Interpretation of wounds. *Br Med J* **2**:770–4.

Fatteh A. 1966. Histochemical distinction between antemortem and postmortem skin wounds. *J Forensic Sci* **11**:17–27.

Fatteh A. 1971. Distinction between antemortem and postmortem wounds: A study of elastic fibers in human skin. *J Forensic Sci* **16**:393–6.

Fazekas IG, Viragos-Kis E. 1965. [Free histamine content in the groove caused by hanging as an *in vivo* reaction.] *Dtsch Z Gesamte Gerichtl Med* **56**:250–68.

Fernandez P, Bermejo AM, Lopez Rivadulla M, *et al.* 1994. Biochemical diagnosis of the intravital origin of skin wounds. *Forensic Sci Int* **68**:83–9.

Green MA. 1978. Stab wound dynamics – a recording technique for use in medico-legal investigations. *J Forensic Sci Soc* **18**:161–3.

Grellner W, Madea B, Kruppenbacher JP, *et al.* 1996. Interleukin-1 alpha (IL-1 alpha) and n-formyl-methionyl-leucyl-phenylalanine (FMLP) as potential inducers of supravital chemotaxis. *Int J Legal Med* **109**:130–3.

Gupta SM, Chandra J, Dogra TD. 1982. Blunt force lesions related to the heights of a fall. *Am J Forensic Med Pathol* **3**:35–43.

Hamdy M, May K, Flanagan W, *et al.* 1961. Determination of the age of bruises in chicken broilers. *Poultry Sci* **40**:787–9.

Henn V, Lignitz E, Philipp KP, *et al.* 2000. [Morphology and phenomenology of death by kicking (II).] *Arch Kriminol* **205**:65–74.

Hernandez-Cueto C, Luna A, Lorente JA, *et al.* 1987. Study of cathepsin A, B and D activities in the skin wound edges. Its application to the differential diagnosis between vital and postmortem wounds. *Forensic Sci Int* **35**:51–60.

Hernandez-Cueto C, Luna A, Villanueva E. 1987. Differential diagnosis between vital and postmortem wounds: ions as markers. *Adli Tip Derg* **3**:14.

Hiss J, Hirshberg A, Dayan DF, *et al.* 1988. Aging of wound healing in an experimental model in mice. *Am J Forensic Med Pathol* **9**:310–12.

Hocking MA. 1989. Assaults in south east London. *J R Soc Med* **82**:281–4.

Hou Jensen K. 1969. Some enzyme conditioned vital reactions in the initial phase of wound healing and their medico-legal significance. *Dan Med Bull* **16**:305–8.

Hunt AC, Cowling RJ. 1991. Murder by stabbing. *Forensic Sci Int* **52**:107–12.

Janssen W. 1984. *Forensic histopathology*. Springer Verlag, Berlin.

Kibayashi K, Hamada K, Honjyo K, *et al.* 1993. Differentiation between bruises and putrefactive discolorations of the skin by immunological analysis of glycophorin A. *Forensic Sci Int* **61**:111–7.

Knight B. 1975. The dynamics of stab wounds. *Forensic Sci* **6**:249–55.

Kosa F, Kurucz E. 1986. Immuno-histochemical reactions with monoclonal antileukocyte antibodies in vital injuries. *Acta Med Leg Soc (Liege)* **36**:176–90.

Laiho K. 1967. Immunohistochemical studies on fibrin in vital reactions. *Acta Med Leg Soc (Liege)* **20**:187–91.

Laiho K. 1998. Myeloperoxidase activity in skin lesions. I. Influence of the loss of blood, depth of excoriations and thickness of the skin. *Int J Legal Med* **111**:6–9.

Laiho K. 1998. Myeloperoxidase activity in skin lesions. II. Influence of alcohol and some medicines. *Int J Legal Med* **111**:10–2.

Langlois NE, Gresham GA. 1991. The ageing of bruises: a review and study of the colour changes with time. *Forensic Sci Int* **50**:227–38.

Logoida DM. 1959. Assessment of survival after trauma, by the leucocyte counts in the capillary network of internal organs. *Sud-Med Ekspert* **4**:5–13.

Maeno Y, Takabe F, Mori Y, *et al.* 1991. Simultaneous observation of catecholamine, serotonin and their metabolites in incised skin wounds of guinea pig. *Forensic Sci Int* **51**:51–63.

Mason JK. 1965. The importance of the histological examination in death from accidental trauma. *Med Serv J Can* **21**:316–25.

Maxeiner H. 1998. 'Hidden' laryngeal injuries in homicidal strangulation: how to detect and interpret these findings. *J Forensic Sci* **43**:784–91.

McCausland IP, Dougherty R. 1978. Histological ageing of bruises in lambs and calves. *Aust Vet J* **54**:525–7.

Muir R, Niven J. 1935. The dating of contusions. *J Pathol Bacteriol* **41**:183–8.

Niu WY, Hu JZ, Zhang XM. 1991. A new staining method for constriction marks in skin. *Forensic Sci Int* **50**:147–52.

Njau SN, Epivatianos P, Tsoukali Papadopoulou H, *et al.* 1991. Magnesium, calcium and zinc fluctuations on skin induced injuries in correlation with time of induction. *Forensic Sci Int* **50**:67–73.

Ohshima T. 2000. Forensic wound examination. *Forensic Sci Int* **113**:153–64.

Ojala K. 1967. Histochemical and morphological of vital reactions in muscle wounds. *Acta Med Leg Soc (Liege)* **20**:193–4.

Ortiz-Rey JA, Suarez-Penaranda JM, Da Silva EA, *et al.* 2002. Immunohistochemical detection of fibronectin and tenascin in incised human skin injuries. *Forensic Sci Int* **126**:118–22.

Presswalla FB. 1978. The pathophysics and pathomechanics of trauma. *Med Sci Law* **18**:239–46.

Prinsloo I, Gordon I. 1951. Postmortem dissection artefacts of the neck and their differentiation from ante-mortem bruises. *S Afr Med J* **25**:358–61.

Quan L, Fujita MQ, Zhu BL, *et al.* 2000. Immunohistochemical distribution of c-reactive protein in the hepatic tissue in forensic autopsy. *Forensic Sci Int* **113**:177–82.

Rabinovitz A. 1956. Medicolegal conclusions on the form of the knife used based on the shape of the stab wounds received. *J Forensic Med* **6**:160–5.

Raekallio J. 1960. Enzymes histochemically demonstrable in the earliest phase of wound healing. *Nature* **188**:235–45.

Raekallio J. 1963. Histochemical distinction between antemortem and postmortem skin wounds. *J Forensic Sci* **9**:107–10.

Raekallio J. 1966. Enzyme histochemistry of vital and postmortem skin wounds. *J Forensic Medicine* **13**:85–90.

Raekallio J. 1967. Application of histochemical methods to the study of traffic accidents. *Acta Med Leg Soc (Liege)* **20**:171–8.

Raekallio J. 1970. *Enzyme histochemistry of wound healing*. Gustave Fischer Verlag, Stuttgart, Germany.

Raekallio J. 1972. Determination of the age of wounds by histochemical and biochemical methods. *Forensic Sci* **1**:3–16.

Raekallio J. 1980. Estimation of time in forensic biology and pathology. An introductory review. *Am J Forensic Med Pathol* **1**:213–18.

Raekallio J, Makinen PL. 1966. Histamine content as a vital reaction: experimental investigation. *Zacchia* **41**:273–84.

Raekallio J, Makinen PL. 1969. Serotonin content as vital reaction. I. Experimental investigation. *Zacchia* **5**:587–94.

Raekallio J, Makinen PL. 1970. Serotonin and histamine contents as vital reactions. II. Autopsy studies. *Zacchia* **6**:403–14.

Ritz-Timme S, Eckelt N, Schmidtke E, *et al.* 1998. Genesis and diagnostic value of leukocyte and platelet accumulations around 'air bubbles' in blood after venous air embolism. *Int J Legal Med* **111**:22–6.

Roberts R. 1983. Sexual offences. In: *Rape – The new police surgeon supplement.* A. P. S. G. B., Northampton,UK.

Robertson I, Hodge PR. 1972. Histopathology of healing abrasions. *Forensic Sci* **1**:17–25.

Robertson I, Mansfield RA. 1957. Antemortem and postmortem bruises of the skin – their differentiation. *J Forensic Med* **4**:2–10.

Sato Y, Ohshima T. 2000. The expression of mrna of proinflammatory cytokines during skin wound healing in mice: a preliminary study for forensic wound age estimation (II). *Int J Legal Med* **113**:140–5.

Sevitt S. 1970. Reflections on some problems in the pathology of trauma. *J Trauma* **10**:962–73.

Shapiro HA, Gluckman J, Gordon I. 1962. The significance of the nail abrasion of the skin. *J Forensic Med* **9**:17–19.

Shepherd JP, Price M, Shenfine P. 1990. Glass abuse and urban licensed premises. [letter] *J R Soc Med* **83**:276–7.

Shepherd JP, Shapland M, Pearce NX, *et al.* 1990. Pattern, severity and aetiology of injuries in victims of assault. *J R Soc Med* **83**:75–8.

Shepherd JP, Huggett RH, Kidner G. 1993. Impact resistance of bar glasses. *J Trauma* **35**:936–8.

Simpson CK. 1979. *Forensic medicine*, 8th edn. Edward Arnold, London.

Spitz WU, Petty CS, Fisher RS. 1961. Physical activity until collapse following fatal injury by firearms and sharp pointed instruments. *J Forensic Sci* **6**:290–6.

Strauch H, Wirth I, Taymoorian U, *et al.* 2001. Kicking to death – forensic and criminological aspects. *Forensic Sci Int* **123**:165–71.

Takamiya M, Saigusa K, Aoki Y. 2002. Immunohistochemical study of basic fibroblast growth factor and vascular endothelial growth factor expression for age determination of cutaneous wounds. *Am J Forensic Med Pathol* **23**:264–7.

Teare RD. 1960. Blows with the shod foot. *Med Sci Law* **1**:429–36.

Thoresen SO, Rognum TO. 1986. Survival time and acting capability after fatal injury by sharp weapons. *Forensic Sci Int* **31**:181–7.

Thornton RN, Jolly RD. 1986. The objective interpretation of histopathological data: an application to the ageing of ovine bruises. *Forensic Sci Int* **31**:225–39.

Torre C, Varetto L. 1985. Sem study of dermal surface. A new approach to forensic traumatology. *Am J Forensic Med Pathol* **6**:256–70.

Torre C, Varetto L, Mattutino G. 1986. Dermal surface morphology in wound healing. An experimental scanning electron microscope study. *Am J Forensic Med Pathol* **7**:337–43.

Wang D, Zhu J. 1992. Localization and quantification of the nonspecific esterase in injured skin for timing of wounds. *Forensic Sci Int* **53**:203–13.

Watson AJ. 1978. *Kicking, karate and kung-fu.* In: Mason JK (ed.), *Pathology of violent injury*. Edward Arnold, London.

Wilson EF. 1977. Estimation of the age of cutaneous contusions in child abuse. *Pediatrics* **60**:750–2.

Zhong FC, Zhen ZJ. 1991. Localization and quantification of histamine in injured skin as parameters for the timing of wounds. *Forensic Sci Int* **51**:163–71.

CHAPTER 5

Head and spinal injuries

- Injury to the scalp 174
- Facial injuries 178
- Falls 180
- Fractures of the skull 181
- Forensic anatomy of the brain membranes 189
- Extradural haemorrhage 190
- Heat haematoma 192
- Subdural haemorrhage 192
- Subarachnoid haemorrhage 196
- Forensic implications of brain membrane haemorrhage 198
- Ruptured berry aneurysm and trauma 198
- Subarachnoid haemorrhage and alcohol 199
- The rapidity of death in subarachnoid haemorrhage 199
- Rotational trauma to the head and upper neck: basilovertebral artery injury 200
- Head injuries in boxers 204
- Cerebral injuries 204
- Histological diagnosis of early cerebral hypoxia 212
- Secondary brainstem lesions 213
- Spinal injuries 214
- References and further reading 216

Of all regional injuries, those of the head and neck are the most common and most important in forensic practice. Adelson (1974) gives these sound reasons for this dominance of head injuries:

- The head is the target of choice in the great majority of assaults involving blunt trauma.
- When the victim is pushed or knocked to the ground, he often strikes his head.
- The brain and its coverings are vulnerable to degrees of blunt trauma that would rarely be lethal if applied to other areas.

A sound practical understanding of the neuropathology of trauma is more essential to the forensic pathologist than any other aspect of his subject, as head injuries provide the major contribution to death in assaults, falls and transportation accidents.

INJURY TO THE SCALP

The scalp is often, though by no means invariably, damaged in trauma that causes injury to the underlying skull and brain. The usual range of abrasions, contusions and lacerations may be inflicted, though a modifying factor is the presence of hair, which may deflect a tangential blow or partly cushion a direct impact.

When an injury is visible on the forehead, the back of the neck, the lower temple or on a bald area, the examination is no different from elsewhere on the body. In hair-covered areas, care must always be taken at autopsy to palpate the scalp in any case in which there is a possibility of injury, otherwise abrasions, swelling, bruising and even lacerations may be missed. When a lesion is found or suspected, the hair must be carefully shaved away to expose the scalp for further examination and photography.

Forensic anatomy of the scalp

Superficially, the skin carries hair follicles, sebaceous glands and sweat glands. The skin is attached to the aponeurosis (see below) by vertical strands of fibrous tissue that break up the subcutaneous layer into pockets filled with fat. The blood vessels and nerves lie in this layer, above the epicranial aponeurosis (formerly called the ‘galea aponeurotica’). This is a dense sheet of fibrous tissue that lies in the deep layer of the scalp over the whole cranium. It is really a flattened tendon uniting the frontal and occipital bellies of the occipitofrontalis muscle.

Deep to the aponeurosis is a thin layer of loose connective tissue that separates it from the pericranium, which is the exterior periosteum of the skull, the dura being the internal counterpart. Some veins traverse all the layers from the superficial fascia to the pericranium, and go on to penetrate the skull and communicate with the intracranial venous sinuses, thus forming a route for meningitis and sinus thrombosis from infected injuries of the scalp.

Abrasion of the scalp

Brush abrasions are less common than in other sites because of the protective effect of the hair, which also tends to prevent or blur the patterned effect of less severe impacts. Impact abrasions from a perpendicular force are imprinted as usual on to the scalp, though again the intervening hair may reduce the severity. Unless the hair is carefully removed at autopsy, with a sharp scalpel or razor, and care taken not to cause artefactual cuts, lesser degrees of abrasion will inevitably be missed.



FIGURE 5.1 *Anatomy of the scalp.*

Bruising of the scalp

Bruising may be difficult to detect until the hair has been removed. Marked swelling is a common feature of extensive bruising, as the liberated blood cannot extend downward because of the rigidity of the underlying skull. However, this subsides, or at least diffuses, after death. Commonly, a severe head injury leads to a thick, swollen, indurated layer of blood beneath the scalp, which may extend over a wide area. The blood is sometimes below the aponeurosis, the tough fascial layer of the scalp, but is more often between this and the epidermis.

Blood may also be present beneath the pericranium, the periosteum that is closely applied to the outer surface of the skull. This is often seen in head injuries in infants, usually in association with skull fractures, as the source of the blood is from the fracture line itself. The close attachment of the pericranium to the suture lines in infants may sharply circumscribe the extent of the bleeding.

In addition to frank bleeding beneath the scalp, marked oedema may occur after injury and the layers of the scalp may be greatly swollen and thickened by a jelly-like infiltration of tissue fluid.

As will be discussed under ‘black eye’, bleeding under the scalp may be mobile, especially under gravity. Thus a bruise or haematoma under the anterior scalp may slide downwards within hours – even minutes – to appear in the orbit,



FIGURE 5.2 *A laceration of the scalp caused by a blow from an iron bar. The edges are crushed and bruised, with strands of connective tissue and hairs crossing the gap, indicating that it was not caused by a sharp-edged weapon.*



FIGURE 5.3 *Lacerations of the scalp from an iron bar. The margins are bruised and the scalp tissue is extruding in places. The generally parallel direction of the five wounds indicates that the assailant probably delivered the blows in rapid succession with little change of orientation between weapon and head.*



FIGURE 5.4 *Stellate laceration of the scalp caused by a heavy blow with a piece of timber. The support of the underlying skull has caused the tissues to split widely. At autopsy, full clearance of the hair must be made to allow detailed examination and photography.*



FIGURE 5.5 *Wounds from a metal poker superficially resembling incised cuts, but having edges and tissue bridges within the wounds.*

simulating a black eye from direct trauma. Similarly, a temporal bruise may later appear behind the ear, suggesting primary neck impact. As with bruises elsewhere, those under the scalp may be obvious immediately after infliction – or their appearance may be delayed, either during life or as a post-mortem phenomenon. They may first become evident, or much more prominent, some hours – or even a day or so – after death. This is caused either by movement of the liberated blood through tissue planes or by haemolysis spreading outwards to stain the subcutaneous tissues, making it always advisable to return to examine the body a day or two following the autopsy.

The shape of an inflicting weapon or object is poorly reproduced on the scalp, again due to the padding effect of the hair. Where the scalp is free of hair, as in the upper forehead or bald areas, all traumatic lesions are similar to elsewhere on the body, with the exception that blunt impact may cause very sharply defined lacerations.

Laceration of the scalp

Lacerations of the scalp bleed profusely, and dangerous and even fatal blood loss can occur from an extensive scalp injury if it is not checked by treatment. The most gross injury is avulsion of a large area of scalp, which can be torn from the head, thereby exposing the aponeurosis or skull. This may happen if the hair becomes entangled in machinery, as was formerly not uncommon in women working in factories. A more common cause nowadays is a traffic accident, where a rotating vehicle tyre comes into contact with the head, causing a 'flaying' injury similar to that seen on limbs.

Scalp injuries may bleed profusely **even after death**, especially if the head is in a dependent position. A post-mortem injury to the head may bleed considerably if inflicted soon after death and these facts may sometimes cause confusion about the ante-mortem or post-mortem nature of the wound, or about the length of time of survival following the injury. There is no reliable way of resolving this difficulty.

Lacerations of the scalp may reproduce the pattern of the inflicting object, even though a random splitting is so common. Severe blows from shaped objects such as hammers or heavy tools may reproduce the profile of the weapon totally or in part. A circular-faced hammer may punch a circle in the scalp, but more often only an arc of a circle is seen. In such cases, the position of the edge that digs in most deeply may give an indication of the angle of the blow. There may be a depressed fracture of the underlying skull of the same shape and size, though the interposition of the dense scalp may cause the skull defect to be slightly larger than the weapon. A depressed fracture in these circumstances is not inevitable, however, and one or more linear fractures may radiate from the impact site.



FIGURE 5.6 *Deep linear incised wounds due to a heavy, sharp cleaver. The depth of penetration varies, the large wound overlying extensive skull fractures. The wounds on the neck are due to light contact with the edge of the same blade.*

A major problem in scalp injuries is the differentiation between incised wounds and lacerations from blunt injury.

The scalp is the best example of a surface tissue lying over an unyielding bony support. Violent compression will crush the scalp against the underlying skull, so a blow from a blunt rod-like weapon may split the skin and underlying tissues in a sharply demarcated fashion, which may appear remarkably like a slash from a sharp instrument. Close examination, using a lens if necessary, will show that this blunt laceration has:

- bruised margins, even though this zone may be narrow
- head hairs crossing the wound, which have not been cut
- fascial strands, hair bulbs and perhaps small nerves and vessels in the depths of the wound.

Scalp injuries from falls

It is vital for the pathologist to appreciate that falls on to a flat surface, or a blow from a wide, flat object such as a plank or paving stone, may sometimes leave no external mark whatsoever on the exterior of the head, but commonly such an injury will cause a ragged split which may be linear, stellate or quite irregular.

Such injuries on the back point of the head are commonly caused by falling, especially in inebriated victims. Falls backwards against a ridge, such as a wall or pavement kerb, may cause a transverse laceration, which may be undercut and partly detached from the underlying bone so that a flap of scalp is loosened from the skull.

Falls usually injure the occipital protuberance, the forehead or the parietotemporal areas. Injuries on the vertex



FIGURE 5.7 *Sliced incised wound of the scalp, from a large knife. The wound is markedly undercut, turning a wide flap of scalp. The clean edges, with a lack of any abrasion or bruising, indicate the sharpness of the weapon.*

should always raise the suspicion of assault, as it is unusual to fall upon the top of the head, even from a considerable height. Occasionally, a fall backwards that just happens to reach a vertical surface, such as a wall or piece of furniture, can cause damage to the top of the head, but there is then usually an obvious grazing component to the lesion.

FACIAL INJURIES

Damage to the face is common, but unless gross, with skeletal damage, is rarely fatal in itself unless it leads to bleeding into the air passages. It is often ancillary to fatal cranial damage, or it may be the route by which severe trauma reaches the brain.

The usual range of injuries may be present externally, but all degrees of underlying damage may also occur in the facial skeleton. Because of the complex contours of the face, the various prominences of chin, nose, cheekbones, eyebrows, ears and lips may intercept impacts, with consequent characteristic damage. The eyebrow is particularly vulnerable, being exposed during falls and blows. A blunt impact on the brow often splits the skin and may cause an underlying frontal fracture that can involve the orbital margin.

The distal part of the nose is flexible and often escapes serious damage, though abrasion is common. The bony bridge of the nose is often fractured, which may be detected by movement and crepitus during external palpation – and by dissection at autopsy. Bleeding in the nose is more important than structural damage, as profuse haemorrhage in an unconscious victim may pass back through the posterior nares into the throat and cause fatal airway obstruction.

The maxillae and mandible may be fractured by direct blows and again cause dangerous intra-oral bleeding from associated soft-tissue damage. A heavy blow or kick to one side of the jaw can cause ipsilateral, bilateral or even contralateral fractures. Gross injury to the face, seen in kicking and some transport accidents, may actually detach the facial skeleton from the base of the skull. The lower part of the maxilla, carrying the palate and upper teeth, may be completely separated from the rest of the skull. At autopsy, the best view of the facial skeleton may be gained by dissecting the whole facial skin upwards from the neck incision and reflecting it as far as the orbits, if necessary. Good restoration can be achieved as long as the skin is not penetrated by the knife.

Injuries to the mouth and lips are very common in 'beating-up' incidents, including child abuse. The lips may be bruised or lacerated, much of the damage arising from compression of the lips against the teeth or bony gums. Lacerations on the gingival aspect of the lips may often be exactly matched with the edges of teeth and, as discussed in Chapter 22, rupture of the frenulum inside the upper lip of a child is virtually pathognomonic of a sideswipe across the mouth, if damage from clumsy and forceful attempts at introducing a feeding bottle, dummy or airway can be excluded.



FIGURE 5.8 *Facial injuries caused by kicking. The upper lip is split and the maxilla fractured on that side. The face and orbital region is grossly swollen and bruised. Death was caused by blockage of the air passages by blood.*

Kicking

Kicking of the face is regrettably common and again the prominences suffer most. Bruising, laceration and fractures may result from kicking under the side of the jaw: similar lesions occur on the maxillary area and the eyebrows. Patterned abrasions from boot soles may be seen or crescentic marks from toecaps. Brush abrasions from glancing kicks may be present on the cheeks or forehead as the sole of the shoe scrapes across the skin. It is uncommon to suffer a 'pure' black eye from a kick without other facial injuries, such as scuffed abrasion on the cheekbones, or marks on the brows or bridge of the nose. Teeth may be loosened, broken or detached by both kicks and heavy punches and black eyes and fractures of the nose are common. A kick on the side of the jaw may cause bilateral jaw fractures or even a single contralateral fracture.

It may be difficult or impossible to differentiate in every case, between injuries (especially to the face) caused by kicks



FIGURE 5.9 *Black eye from a direct impact into the orbit from a punch. This is the third mechanism of production of a periorbital haematoma, the others being a fracture of the anterior base of the skull and a frontal scalp wound.*



FIGURE 5.10 *Black eye as a result of gravitational seepage of blood downwards from a forehead injury. The woman was struck with a rock on the frontal area and eyebrow, blood then descending during the few hours of coma before death occurred.*

and those from blows from a blunt object. Toecap marks are not all that common, especially since the more flexible rubber 'trainer' shoes have become almost universal footwear.

In stamping, there is the chance that the sole pattern may leave an imprint, but a swing from a toe may leave a non-specific abrasion, bruise or laceration. It may be that the severity of the injury, including underlying bone damage, may be a better indication of a kick than the shape of the injuries, as the force delivered by a swinging foot at the end of a muscular leg is greater than that from a fist.

Black eyes

The usual periorbital haematoma or 'black eye' is usually caused by a direct punch or kick into the eye-socket, but the pathologist must always consider the several alternative explanations. A black eye may be the result of:

- direct violence, which may or may not be associated with abrasion or laceration on the upper cheek, eyebrow, nose or other part of the face
- gravitational seepage of blood beneath the scalp from a bruise or laceration on or above the eyebrow. Survival and at least a partially upright posture of the head must have been maintained for at least some minutes, usually longer, between the time of injury and death. When the scalp lesion is high up on the frontal region, this time will probably be measured in hours
- percolation of blood into the orbit from a fracture of the anterior fossa of the skull. This is often from a contrecoup injury caused by a fall on to the back of the head, leading to secondary fracture of the paper-thin bone of the orbital roof. It is invariably associated with contrecoup contusion of the frontal lobes of the brain, as described later in this chapter.

A simple fall onto the face on a flat surface does not usually cause a black eye, as the prominences of the eyebrow, cheekbone and nose prevent damage to the orbit.

Damage to the ear

The external ear often suffers from blows to the head and is an obvious target in child abuse. Bruising and laceration of



FIGURE 5.11 *Bilateral black eyes caused by leakage of blood into the orbits through comminuted fractures in the floor of the anterior fossa. This homicide victim was struck on the head with a shovel and survived for some days. Brain tissue is escaping from the nostrils through basal skull fractures.*



FIGURE 5.12 *The production of a black eye: (1) A direct blow into the orbit. (2) An injury to the front of the scalp, draining down over the supraorbital ridge. (3) A fracture of the base of the skull (direct or contrecoup) allowing meningeal haemorrhage to escape through the orbital roof.*

the pinna is obvious on examination and – in severe trauma – the root of the ear may be detached from the head, usually by a tear at the posterior margin where the ear joins the head. Where gross damage is present, especially with partial avulsion of the pinna, kicking must be considered.

The ear may be bitten and even partly detached, a fate which occasionally is suffered by the nose. In such cases the advice of a forensic odontologist may be invaluable, as teeth marks may form vital evidence.

FALLS

Falls are extremely common, the severity not necessarily being directly related to the distance that the person falls. Many people die after falling from a standing position, yet others sometimes survive a fall of many metres.

Falls from a standing position can occur if a person is drunk, from an assault, during illness (such as a fit or faint) and for many other reasons. Death can follow from a head injury, especially onto the back of the head. An occipital scalp laceration or a fracture of the skull is not necessary for cerebral damage (often frontal contrecoup) to occur. There may also be a subdural or (less often) an extradural haemorrhage, the latter more common from a fall on to the side of the head.

The vexed question of head injury from falls in children is discussed in Chapter 22, but here it may be stated that, although fatal head injury from a fall usually requires a drop of a number of feet, there are well-authenticated instances of skull fractures and brain damage from trivial falls, including some medically witnessed falls from tables and settees. The experimental work of Weber (see Chapter 22) showed that the skulls of small infants could be fractured against a variety of floor surfaces from passive falls of only 34 inches. It is thus invalid for medical witnesses to claim it **cannot** happen, as even one authenticated case creates a precedent. In adults, fractures have certainly occurred from falls onto very hard surfaces from only a foot or so. One such case was a drunk lying on concrete; equally drunken friends attempted to lift him but allowed his head and shoulders to fall back from about half-sitting position, causing occipital fracture.

Falls in old people very frequently cause fractures of the post-cranial skeleton – especially the neck of femur – though ribs, arms and pelvis may also suffer. Osteoporosis is the major reason for the large number of such injuries from falls. More than 47 000 fractured femora occur each year in Britain, with a 25 per cent mortality rate, mainly from subsequent pulmonary embolism or bronchopneumonia.

Falls from a height

Falls from a considerable height, usually from a building, are common in suicide and in some accidents, especially to children. Occasionally deaths from a high fall may be homicidal, again especially in children.

When a person falls or jumps from a height, the trajectory is downwards and outwards, and the distance that the body strikes the ground from the jumping point is variable. Goonetilleke (1980) has published some research on how far from the wall a body is likely to land. Much depends on whether the victims fell passively from near the wall or projected themselves outwards at the top. The body may fall whilst maintaining the same orientation to the ground, but usually turns and twists in an unpredictable manner, the amount of alteration of posture partly depending upon the height of the fall and so the time available for turning. This means that the body may strike the ground in a number of different attitudes – and may also strike some obstruction part of the way down, making interpretation of injuries difficult.

The primary impact is usually the site of the most severe injury, but this is not always the case, as it may strike two areas simultaneously, such as the head and shoulder – or it may bounce or ricochet so that two or more major impacts occur in quick succession. The amount of kinetic energy acquired during the fall has to be fully expended by the time the body comes to rest so that, if only one impact occurs, it is likely to be more damaging than a series of lesser impacts, such as a bouncing, rolling strike.

If the body falls on to the head, there is likely to be a massive fracture, often (but not always) a scalp laceration and possibly extrusion of brain. Both vault and base can fracture and sometimes the base is driven down over the cervical spine, the latter projecting into the posterior fossa. The latter injury is, however, more common with high falls onto the feet when the impact is transmitted up the spinal column and the upper vertebrae – together with a ring of bone around the foramen magnum – are intruded into the skull, causing the classic 'ring fracture' of the occipital bone. Where the fall is onto the feet, the deceleration stress can break the axial skeleton at a number of points. The legs can be broken at any point, at tibial or femoral level, often bilaterally. The femoral necks can be snapped off, the hip joints can dislocate and over-ride, or the pelvis may fracture. The latter is often through the sacroiliac joints, the upward force (or more accurately, downward force of the body on to the legs) driving the sacrum down as a wedge into the pelvis.

If the lower limbs and pelvic girdle remain intact, the transmitted force may then fracture the spine, often at mid- or upper thoracic level.

Where the fall occurs onto the side of the body, any combination of injuries can occur. Multiple rib fractures, shoulder girdle or arm fractures, lacerations of back, buttocks or limbs and severe abdominal injuries can occur, with consequent internal lesions, such as rupture of the liver, lungs, heart or spleen.

In falls from high-rise buildings, the injuries can be extreme, as in a suicide from the twentieth floor seen by the author (BK), where the victim fell onto a fence and was completely transected at waist level.

It must also be remembered that biological and circumstantial variability allows for some remarkable escapes from falls; some persons, including children, have fallen from great heights yet have virtually walked away unscathed. Once again, it is very unwise to over-interpret the relationship between observed injuries and the likely length of the fall.

FRACTURES OF THE SKULL

Forensic anatomy

The cranium and facial bones are laid down from membrane in fetal life. The anterior fontanelle closes functionally between 9 and 26 weeks after birth, though is not tightly sealed until about 18 months. The posterior fontanelle closes between birth and 8 weeks of age. Suture lines close by interdigitation during childhood and osseous fusion occurs irregularly at variable dates during adult life.

The adult cranium consists of two parallel tables of compact bone called the 'diploë', the outer being about twice the thickness of the inner. They are separated by a central zone of soft cancellous bone, which is often misnamed the diploë. This zone is interrupted at suture lines and vanishes where the bone becomes particularly thin, especially in the floor of the skull.

The cranium varies in thickness in adults and varies from place to place, thin plates being reinforced by stronger buttresses, such as the petrous temporal, the greater wing of the sphenoid, the sagittal ridge, the occipital protruberance and the glabella. This tensile architecture of the skull has been well described and illustrated by Rowbotham (1964). The more vulnerable thin areas lie in the parietotemporal, lateral frontal and lateral occipital zones.

The average frontal and parietal thickness in a young male is between 6 and 10 mm. The thinnest area is in the temporal bone, where it may be only 4 mm, while in the occipital bone in the midline it may be 15 mm or even more. The thickness of the skull is sometimes an issue in courtroom propositions about the special vulnerability of a victim but, unless it is abnormally thin, such theorizing has little forensic relevance as it is well known that fatal brain damage can often occur with an intact skull. It has even been claimed that a thin skull is less likely to fracture,


Emissary vein
Scalp
Pericranium
Thicker outer table
Diploë
Cortical vein
Thinner inner table
Meningeal artery
Dura
Venous sinus
Pia mater
Cerebral artery
Subarachnoid space
Arachnoid mater
Arachnoid granulation
Brain
Falx

FIGURE 5.13 *Forensic anatomy of skull and meninges.*

as it is more flexible and can return to normal after distortion without cracking; this is certainly true of the skulls of infants. This may be irrelevant when assessing intracranial damage, however, which is the major issue in head injuries.

It is rarely the skull fracture itself that is a danger to life, but the concomitant effect of transmitted force upon the cranial contents. The presence of a skull fracture is, however, an indication of the severity of the force applied to the head and it is uncommon for a head injury that is sufficiently severe to crack the skull not to cause some intracranial effect, even if it is only transient concussion, though, once again, there are many remarkable exceptions to this generalization.

In skeletal material, fractures of the skull are often seen and the differentiation between ante-mortem injury and post-mortem damage can sometimes be difficult or even impossible in the absence of any soft tissues. Artefactual damage to a skull may be caused during recovery or exhumation, and even stones in the soil can cause erosion and even cracking of the softened, degenerate bone after long burial. Zuo and Zhu (1991) have described scanning electron microscopic details of microfractures and collagen damage, which can differentiate ante- from post-mortem injury, but these are unlikely to assist in old decayed material.


Cranium
Extrusion
Extrusion
Intrusion

FIGURE 5.14 *The 'struck hoop' illustration of impact on the skull. There is a momentary deformation, with the area of impact bending inwards and compensatory bulging elsewhere. This sets up stresses in the inner and outer tables.*

The mechanics of skull fracture

This subject has been extensively studied in living animals, isolated human heads and dried skulls. For details, the writings of Gurdjian, Webster and Lissner (1949, 1950), Weber (1984) and Rowbotham (1964) should be consulted;

a concise summary has also been provided by Shapiro *et al.* (1988). These and other workers have shown that:

- When the skull receives a focal impact there is momentary distortion of the shape of the cranium, the extent of which may be surprisingly large, though transient. Infant skulls, which are more pliable and have flexible junctions at suture lines, may distort much more than the more rigid skulls of adults. The area under the point of impact bends inwards and, as the contents of the skull are virtually incompressible, there must consequently be a compensatory distortion or bulging of other areas – the well-known 'struck hoop' analogy.

  Both these intruded and extruded areas can be the site of fracturing if the distortion of the bone exceeds the limits of its elasticity.
- When the skull is deformed, compression occurs on the concavity of the curved bone and tension (tearing) forces on the convexity. If the latter exceed the elastic threshold, then fracturing takes place. Thus the inner table will fracture where the skull is indented and the outer table will fracture at the margins of the deformed area. If the forces are great enough, a depressed comminuted fracture will occur.
- In the more common circumstance of a wider impact from a blunt injury, the deformation of the skull is less localized but, where the force is sufficient, fractures can still occur from the same mechanism of exceeding the elastic limits. The fractures may be remote from the area of impact, following lines of structural weakness – or may extend from the area of impact, or even commence at a distance and run back to the impact site.



FIGURE 5.15 *The skull is more susceptible to traction forces than compression, so that convexities tend to fracture during the distortion of the 'struck hoop'.*

By using skulls coated with a brittle varnish, Gurdjian showed that stress lines developed in the cranium when it was struck and that these corresponded with the fractures that occurred with heavier impacts.

Blows in certain areas of the skull constantly give rise to fractures in specific localities – for instance, impact on the upper temporal or parietotemporal areas cause fissured fractures running obliquely downwards across the temporal area. If heavier, another fracture line tends to run obliquely contralaterally across the vault of the skull.

A heavy impact on the side or top of the head often leads to the vault fracture running into the base of the skull, usually across the floor of the middle cranial fossa along the anterior margin of the petrous temporal bone, to enter the pituitary fossa. In major injuries, this fracture line may often cross the floor of the skull completely to form a 'hinge fracture', separating the base of the skull into two halves. These fractures do not start at the point of impact unless there is also local



FIGURE 5.16 *Linear fracture of the posterior fossa, due to a fall on the occiput. The fracture typically crosses the thinner bone, avoiding the central buttress and ends near the foramen magnum.*

depressed fracturing; they are initiated at a distance due to the compensatory deformation, but usually run back towards the impact site.

When the frontal area is struck, the usual course for a linear fracture is vertically down the forehead, turning around the orbital margin to run backwards across the floor of the anterior fossa, perhaps into the cribiform plate or air sinuses, or both. A blow or fall onto the occiput may produce a fracture that typically passes vertically or obliquely downwards just to the side of the midline of the posterior fossa, commonly reaching the foramen magnum. In addition, the contrecoup element of an occipital fall may cause fractures of the orbital plates in the anterior fossa, as a result of transmitted force through the brain itself, though the mechanism is not fully understood.

- When severe local impact causes focal and general deformation, a combination of depressed fractures and radial fracture lines may form a 'spider's-web' pattern.
- When the focal impact is severe, the depressed fracture may follow the actual shape of the impacting object, such as a hammer-head. The shape may follow only that part of the object that drives into the skull – for example, the circular head of the hammer may strike at an acute angle, so only a semicircle of bone will be punched inwards, the opposite edge sloping downwards from an irregular crack.

  The deepest part of the depression will indicate where the weapon first struck; there may be 'terracing' of the margins. The author (BK) has seen a recent instance where a victim was struck with a hammer through a thin plastic bag enveloping the head. Parallel terracing cracks had opened for a fraction of a second during the blow, sufficient to trap lines of plastic into the multiple defects in the outer table. Where the impact is from a narrow edge or ring, only the outer table may be fractured, being punched into the softer centre without depression of the inner table.
- The presence of hair and scalp markedly cushions the effects of a blow, so that a far heavier impact is required to cause the same damage, compared to a bare skull. The pattern and nature of the skull fractures are, however, the same. It should be noted that the interposition of scalp and hair may slightly alter the dimensions of the skull lesion from a focal blow. For example, the padding effect of the scalp may add a few millimetres in diameter to the depressed fracture caused by a hammer, compared with the actual measured diameter of the hammerhead.
- Where two or more separate fractures occur from successive impacts and meet each other, the sequence of injuries may be determined by 'Puppe's rule', which is really eponymous common sense. The later fracture will terminate at (that is, not cross) the earlier fracture line, which naturally interrupts the cranial distortion which precedes fracturing (Figure 5.17).



FIGURE 5.17 *Diagram to illustrate Puppe's rule for the sequence of fractures. The course of a later fracture will be interrupted by an earlier pre-existing fracture line.*

Types of skull fracture

Arising from the mechanisms described above, it is conventional to classify skull fractures as follows.

LINEAR FRACTURES

These are straight or curved fracture lines, often of considerable length. They either radiate out from a depressed zone, or arise under or at a distance from the impact area, from bulging deformation. They may involve the inner or outer table, but commonly traverse both.

Depending on the stress contours of that part of the skull and the localization of the impact, they may occur anywhere in the skull, but are especially common in the weak unsupported plates. The temporal, frontal, parietal and occipital plates may all carry single or multiple linear fractures. They may extend downwards into the foramen magnum, across the supraorbital ridges, or into the floor of the skull. A common basal linear fracture is one that passes across the floor of the middle fossa, often following the petrous temporal or greater wing of the sphenoid bone into the pituitary fossa. This frequently continues symmetrically across the other middle fossa separating the base of the


(a)
b)
(c)
Secondary fracture in anterior fossa floor
Transverse 'hinge' fracture
Ring fracture around foramen magnum
(d)

FIGURE 5.18 *Types of skull fracture: (a) linear fracture; (b) 'spider's-web' fracture; (c) depressed fracture; and (d) base fractures.*



FIGURE 5.19 *Linear fractures of the skull in child abuse. Blunt impact near the vertex has caused a double fracture to run down the parietal bone and continue into the temporal area, the course of the fracture being determined by lines of stress and weakness in the skull. The central burr-hole was for the surgical evacuation of a subdural haemorrhage.*

skull into two halves, usually being caused by a heavy blow on the side of the head; this lesion was sometimes called the 'motorcyclist's fracture' for obvious reasons. Linear fractures may follow a horizontal course around the skull, usually from one temporal area to the other via the occiput rather than around the front.

In children and young adults, a linear fracture may pass into a suture line and cause a 'diastasis' or opening of the weaker seam between the bones. This is most often seen in the sagittal suture between the two parietal bones, but the interfrontal line of weakness left by the earlier fusion of the metopic suture can also reopen under mechanical stress. In infants, especially in the child abuse syndrome, a linear fracture of a parietal bone may reach the sagittal suture and continue across it into the opposite plate. The continuation may be direct or may be 'stepped', so that the two fractures are not in line. This appearance usually means a blow or fall onto the vertex, and the two fractures may be simultaneous but not continuous, explaining the 'stepping'.

RING FRACTURES

These occur in the posterior fossa around the foramen magnum and are most often caused by a fall from a height onto the feet. If the kinetic energy of the fall is not absorbed by fractures of the legs, pelvis or spine, the impact is transmitted up the cervical spine. This may be rammed into the skull, carrying a circle of occipital bone with it.

POND FRACTURES

This is merely a descriptive term for a shallow depressed fracture forming a concave 'pond'. It is more common in



FIGURE 5.20 *Pond fracture.*



FIGURE 5.21 *Comminuted skull fracture with depression of the central area. This could also be termed a 'pond fracture' in that there is an ovoid depressed zone with radiating linear fractures. The head was struck with a heavy piece of wood along the line of the depressed area.*

the more pliable bones of infants and, indeed, a depression can occur in the absence of a fracture akin to the distortion produced by squeezing a table-tennis ball.

MOSAIC OR SPIDER'S-WEB FRACTURES

As already described, a comminuted depressed fracture may also have fissures radiating from it, forming a spider's-web or mosaic pattern. The degree of actual depression may be minimal or even absent.

DEPRESSED FRACTURES

Focal impact causes the outer table to be driven inwards and, unless absorbed in the diploë, the inner table will also usually be intruded into the cranial cavity with all the dangers of direct damage to the contents. Even sharp-edged weapons, such as heavy knives and axes, which may cause a clean-cut defect externally, usually split and deflect flaps downward from the inner table.

With axes and heavy cutting weapons such as swords, there is a characteristic lesion in the bones, whether skull or elsewhere. The initial impact slices cleanly through the bone on one edge, often burnishing the bone to an ivory-like gloss. The rebound removal of the weapon is at a slightly different angle, either from deliberate intent, or from relative movement between bone and blade. This cracks off an irregular fragment of bone of the opposite face so that the residual defect has one smooth and one rough edge. It is often seen in historical and archaeological material from battles or massacres.

The force required to cause fractures of the skull

Unlike less reliable subjective estimates of the force required to cause other injuries, objective quantitative measurements have obtained for adult skull fractures. Again, the publications of Gurdjian, Webster and Lissner should be consulted for detailed information. The following useful facts arise from their investigations:

- The tensile strength of the adult skull is of the order of 100–150 p.s.i., the compressive strength varying from



FIGURE 5.22 *A depressed fracture of the skull from a blow with a heavy club hammer. The defect is wedge shaped with a curved anterior border caused by the hammer striking at an angle. The depression is concentrically terraced, with the lowest fragments lacerating the surface of the brain.*

5000 to 31 000 p.s.i. (Gurdjian *et al.* 1949). A simple fissured fracture of the skull can be sustained by walking into a fixed obstruction (Kerr 1954). This requires a force of about 5 foot-pounds (73 N). Fast running into an obstruction produces about 70 ft-lb (1020 N). Falling to the ground from an erect posture also develops at least 60 ft-lb (873 N) and can easily produce skull fractures. A small stone or golf ball weighing about 100 g (4 oz) may also cause a linear fracture when thrown with moderate force against the temporal region (Graham and Lantos 2002).

- The adult head weighs between 3 and 6 kg (7–14 lb), averaging 4–5 kg (10 lb). When falling through about one metre (3 ft), so that the frontal area strikes a hard surface, impact energy of about 35 ft-lb (510 N) develops. This can cause one or two linear fractures or a mosaic fracture (Gurdjian *et al.* 1950).
- Only a small additional amount of energy above that needed to cause a single crack is required to produce multiple fractures.

In spite of these experimental data, it must never be forgotten that, like all biological phenomena, great variation is encountered and skull fractures, though they may be caused by as little as 5 ft-lb (73 N), may be absent when the impact exceeds 90 ft-lb (1314 N). The area of the skull struck, the thickness of the skull, scalp and hair, the direction of the impact and other imponderables, all affect the outcome.

As further discussed in Chapter 22, Weber carried out experiments in which he dropped the bodies of dead infants from a fixed height of only about 85 cm (34 inches) onto various hard and soft surfaces. A high proportion sustained skull fractures, both of the parietal and occipital areas, some of them crossing suture lines.



FIGURE 5.23 *Springing of the sagittal suture of the skull of an infant. Though there was no skull fracture, the suture line has widened after a fall that caused a subdural haemorrhage.*



FIGURE 5.24 *Diastasis or 'springing' of the sagittal suture of a young adult who fell from a height onto the vertex of his head. The opening of the interparietal suture has extended anteriorly along the line of weakness of the fused metopic suture between the two halves of the frontal bone.*



FIGURE 5.25 *Post-mortem diastasis of the sutures as an artefact due to freeze-up of the brain simulating intra-vital skull fracture.*



FIGURE 5.26 *A 'hinge' fracture of the base of the skull where the fracture line runs from side to side across the floor of the middle cranial fossa, passing through the pituitary fossa in the midline, following the course of least structural resistance. The victim was a young pedestrian who was hit by a car and then sustained secondary injuries by striking the left side of the head on the ground. This injury is common in road accidents and is sometimes called the 'motorcyclist's fracture'.*

Dangers of fractures of the skull

It has been emphasized that, in the majority of cases, the significance of a fractured skull is an indicator of a substantial insult to the head, with possible injury to the vital contents, rather than the fracture itself being a danger to life.

There are occasions, however, when the fracture itself has dangerous sequelae. The most common is when the crack passes through an embedded meningeal artery, causing a meningeal haemorrhage, which is considered later. A depressed fracture may impinge upon the brain and its membranes, and bone fragments may lacerate or penetrate the brain tissue.

TRAUMATIC EPILEPSY

A late effect of a depressed skull fracture may be 'traumatic epilepsy'. This is of great medico-legal significance, especially in the field of civil litigation where an accident or assault may result in lifelong neurological disability for which very large monetary compensation may be awarded.

Traumatic epilepsy usually manifests as tonic and clonic fits, which may be difficult to differentiate from idiopathic epilepsy, if the injury occurred in early life. When fits begin within weeks, or a year or two of a major head injury in a mature person who had never had fits before, the diagnosis is easier, but all cases need expert neurological examination. There must have been a substantial head injury, usually with a depressed fracture impinging on the underlying cortex, often in the parietotemporal area. The epilepsy appears usually within a range of a few weeks to up to 2 years. It is more common in open head injuries when infection has occurred, or when a spicule of bone has penetrated the meninges, as the mesodermal scarring of the cortex that results is more likely to irritate the brain than the astrocytic reaction found in closed head injuries.

INFECTION FOLLOWING SKULL FRACTURE

Other complications may occur, even in the absence of depression or comminution. The most common is infection of the meninges, or the development of a brain abscess, or both. Infection can gain access via skull fractures:

- by direct spread through a compound fracture, especially where there is a contaminated scalp injury;
- by spread from the nasal cavity when a fracture of the cribriform plate has allowed communication with the anterior fossa. This fracture is not uncommon as part of ‘contrecoup’ lesions, described later. Sometimes the cribriform plate is ruptured by objects entering a nostril and carrying infected material into the cranium: the author (BK) has seen two such fatalities, one from an umbrella ferrule and another from a dirty bamboo garden cane. Another case was seen by PS where a suicide attempt was made with a small calibre pistol. The bullet penetrated the right temple and went through the skull just above the anterior cranial fossa, which was fractured and caused a leakage of the cerebrospinal fluid through the nose. The victim recovered well but, in spite of prophylactic treatment with antibiotics, died one year later from purulent meningitis.
- by spread from fractures that involve a paranasal sinus, such as the frontal or ethmoid, or from the mastoid air cells or middle ear cavity. Basal fractures may allow these spaces, which communicate with the infected outside environment, to reach the meninges, especially when the latter are torn by the traumatic event. A history of leakage of cerebrospinal fluid from the nose or ear must alert both clinician and pathologist to the possibility of communicating basal fractures. In any autopsy on a suspected head injury, however slight, care must be taken to remove the dura from the interior of the vault and base so that a close inspection for fracture lines can be made.

INTRACRANIAL INJURIES

The contents of the skull are the most fragile of the vital organs, necessitating their enclosure in the strong bony box of the cranium. Damage may occur either to the neural tissues or to the rich vasculature that surrounds and penetrates those tissues.

FORENSIC ANATOMY OF THE BRAIN MEMBRANES

The pachymeninges consist of the dura mater and the leptomeninges, the arachnoid and the pia mater (see Figure 5.13). The **dura** is formed of two layers of tough collagenous tissue, the outer of which is firmly attached to the skull and acts as its internal periosteum. The inner layer merges with the arachnoid, so that in reality there is no true subdural space, only a potential cleavage plane.

The dura forms the falx and tentorium, and the cranial venous sinuses run within it. Branches of the meningeal arteries course over and through its substance. The dura is penetrated by bridging veins, especially along the vertex and at the tips of the temporal lobes, also to a lesser extent at the frontal and occipital poles, as well as by random vessels elsewhere. Polypoid invaginations of the dura penetrate the inner walls of the venous sinuses, especially the sagittal sinus, to form the ‘arachnoid granulations’.

The **arachnoid** is a thin, vascular meshwork that is intimately applied to the inner surface of the dura by means of the ‘boundary layer’ so that no subdural space exists in normal conditions, though their junction is so tenuous that they are easily split apart. Sheaths of arachnoid follow vessels into the brain as they penetrate into the neural surface. These vessels and thin strands of connective tissue anchor the brain within the subarachnoid space. This is filled with cerebrospinal fluid and the width of the space varies from less than a millimetre in the young to a centimetre or more in the old, in whom cerebral atrophy has developed. This means that the anchoring strands and the bridging vessels are longer and more vulnerable to shearing and rotatory stresses. Even though anatomically in the subarachnoid space, rupture of these bridging vessels often manifests itself in the subdural space.

The **pia** is not a true membrane, but a surface feltwork of glial fibres that are inseparable from the underlying brain.

EXTRADURAL HAEMORRHAGE

Also known as 'epidural haemorrhage', bleeding between the inner surface of the skull and the dura mater is the least common of the three types of brain membrane haemorrhage. According to Rowbotham (1964), only about 3 per cent of head injuries have an epidural haemorrhage large enough to be of surgical significance; a similar figure of between 1 and 3 per cent was recorded by Tomlinson (1970). Of the 635 fatal head injuries investigated by Adams (see References and further reading) in Glasgow, 10 per cent had extradural haemorrhages. The mortality rate, even with surgical intervention, averages about 11 per cent under the age of 20 years, rising to between 18 and 40 per cent in later life.

The dura is closely applied to the interior of the skull, forming the endocranium or periosteum. It is so tightly applied to the base of the skull that, except in the posterior fossa, extradural bleeding does not occur over the skull floor. In the vault there is a potential space between the dura and the bone, which can be separated by both arterial and – less often – venous leakage. Most extradural haemorrhages are associated with fractures of the skull, but about 15 per cent occur in intact skulls (McKissock 1960). According to Harwood-Nash *et al.* (1971), the incidence in children without a fracture is only 1 per cent, though Adams found that half the children with extradural bleeds in his series of over 600 fatal head injuries had no fracture. About 10 per cent of extradural haemorrhages are associated with subdural haemorrhages. Bilateral epidural haemorrhages are rare, but have been recorded.

The usual site is unilateral in the parietotemporal area, caused by rupture of a branch of the middle meningeal artery where the latter is transected by a fracture line. The posterior branch of this vessel is most commonly involved as it courses diagonally backwards across the squamous temporal bone on the lateral wall of the cranium. The anterior (frontal) branch is rarely the source of bleeding, occurring only twice in Rowbotham's series of 33 cases. The vessel usually lies in a deep osseous groove in the first part of its course. It has been claimed that almost all ruptures occur where the artery is completely roofed over in a bony tunnel so that it is unable to escape damage from a fracture, but observation does not confirm this contention.

Leakage of the high-pressure arterial blood strips back the underlying dura with progressive accumulation of a haematoma, which can reach a volume of several hundred millilitres and cover an appreciable part of the hemicranium. Adams suggests that a minimum volume of 35 ml is needed before clinical signs are apparent, though other writers suggest 100 ml is usually the minimum associated with fatalities.

In the less common occipital and frontal sites, smaller branches of meningeal arteries may be involved or the bleeding may be from torn venous sinuses, in which case there need not be a fracture. When bleeding is venous, the haematomas rarely reach a large size as the pressure is insufficient to tear back much of the dura.

The clinical signs of an epidural haemorrhage are classically those of a 'lucid' or 'latent' interval, as there may be recovery from the initial phase of concussion (see below) before sufficient blood accumulates to cause raised intracranial pressure and consequent relapse into unconsciousness. This classic picture is so frequently absent, however, that no diagnostic reliance can be placed upon it. The coma from the increasing space-occupying lesion formed by the bleed may follow the period of concussion without a break so that there is no temporary phase of recovery. Only 27 per cent of McKissock's series showed the classic history.



FIGURE 5.27 *Formation of an extradural haemorrhage.*



FIGURE 5.28 *A large temporoparietal extradural haemorrhage. The under surface of the scalp on the right shows bruising at the point of impact. There was a linear fracture of the skull passing through the right middle meningeal artery.*

The latent interval may be of variable duration and, as just noted, may not occur if either concussion is prolonged or other brain damage coexists. Half an hour may be enough for the formation of a significant arterial haematoma, though some slow bleeds have taken more than a day to become clinically apparent. In Rowbotham's series, the range was from 2 hours to 7 days, but most were apparent after 4 hours.

More recent investigations using computed tomography, quoted by Adams, suggest that the old concept of worsening clinical symptoms being caused by the progressive accumulation of blood is incorrect, as computed tomograms show that the major volume of blood may appear soon after the injury and that, as with many space-occupying lesions, clinical signs result from other factors, such as cerebral oedema or diffuse neuronal injury.

Medico-legal considerations of extradural haemorrhage

A medico-legal danger is that a victim may be discharged from the care of a doctor or hospital casualty department when he recovers from his transient concussion only to deteriorate and perhaps die at home; negligence may then be alleged against the unsuspecting doctor. Unfortunately, even when the diagnosis is made, the results of surgical intervention are not good, there being a fatal outcome in more than half the cases operated on. Part of the reason for this poor prognosis is that many victims of extradural haemorrhage also have other damage such as cerebral contusion.

When a victim of a head injury recovers from concussion and then lapses into coma within the first 24 hours, the differential diagnosis is between an extradural or subdural haemorrhage, or cerebral fat embolism, especially if there is other skeletal damage. At autopsy the lesion is self-evident, as most haematomas lie in the temporal or parietal areas, and are opened when the usual saw-cut is made to remove



FIGURE 5.29 *An extradural haemorrhage in the posterior fossa. This is an unusual site for this type of lesion, as most occur in the temporal or parietal area as a result of tearing of the middle meningeal artery. In this case a fracture line passed down the posterior fossa towards the foramen magnum, but no bleeding point could be identified.*



FIGURE 5.30 *A fresh extradural haemorrhage in the temporoparietal area from a fracture crossing the middle meningeal artery. About 85 per cent of such haemorrhages are associated with skull fractures.*



FIGURE 5.31 *Fire victim with extensive defect of the carbonized skull showing reddish-brown 'heat haematoma' on the inner surface of the skull and shrunken brain with brain tissue oozing out through a split in the dura.*

the calvarium. If in the posterior fossa, the dark blood is seen through the raised dura. Wherever it is situated the dimensions and approximate volume should be measured and an estimate made of the inward projection. The brain surface will be flattened or otherwise distorted if the haematoma is of significant size and may have given rise to the usual appearances of raised intracranial pressure, described later. The midline of the brain may be shifted laterally if the bleed is large.

Extradural haemorrhage is never a 'contrecoup' injury, this being purely a cerebral tissue lesion.

HEAT HAEMATOMA

One well-known artefact mimics an extradural haemorrhage. When a head has been exposed to severe external heat sufficient to burn the scalp and perhaps the skull, blood may be extruded from the diploë and venous sinuses into the extradural space to produce a 'heat haematoma'.

The mechanism is obscure, but may be the result of blood being 'boiled' from the diploic layer of bone through emissary veins, or shrinkage of the brain may aspirate blood from the skull. The false haematoma is brown and friable, and the adjacent brain shows hardening and discoloration from the heat.

The importance of the artefact is that it may be mistaken for a true epidural bleed from a head injury, and may mislead the pathologist and investigators into thinking that the fire was started criminally to cover up a fatal assault. As most instances are seen in conflagrations in buildings, there is often a significant level of carboxyhaemoglobin in the body if the death occurred when the fire was in progress. This should be of the same concentration in the heat haematoma as in the peripheral blood; if the victim suffered a head injury before the fire started, then there should be little or no carboxyhaemoglobin in the haematoma.

SUBDURAL HAEMORRHAGE

Bleeding beneath the dura is much more common than extradural haemorrhage. It is also proportionately less often associated with a fractured skull, but in absolute numbers far more fractured skulls cover subdural than extradural haemorrhages. The Glasgow series of 635 fatal head injuries described by Adams included 18 per cent of subdural haematomata.

The lesion is traditionally classified into three types: the acute, the subacute and the chronic. It is unhelpful to subdivide the acute type, however, and only acute and chronic haemorrhage need be considered.

Subdural haemorrhage can occur at any age, but is common at both extremes of life. It is one of the major causes of fatal child abuse and the rediscovery of that syndrome by Caffey (1946) consisted of an association of subdural haemorrhage with long bone fractures. In old people they commonly exist in a chronic form and can be mistaken either for 'strokes' or for senile dementia. The condition is always due to trauma and there is probably no such entity as 'spontaneous subdural haematoma'. Even in states of vascular fragility, such as in senility and in bleeding diatheses, some minimal trauma must precipitate the bleeding even if it was too trivial to be recorded in the history. It is almost certain that minor subdural bleeds, insufficient to give rise to any neurological or clinical symptoms or signs other than a transient headache, occur with the trivial knocks of everyday life. Only when the bleeding is extensive enough to become either a cortical irritant or a space-occupying lesion (probably between 35 and 100 ml) does it become clinically apparent. Of course, many subdural haemorrhages exist in combination with both subarachnoid bleeding and with cerebral damage, making its contribution to the overall symptomatology impossible to assess.

As with the extradural haematoma, the position of a subdural can never be interpreted as a 'contrecoup' lesion and is thus of no use in differentiating a blow from a fall.

Acute subdural haemorrhage

This is a common sequel to any substantial head injury, and the presence or absence of a fracture is immaterial except as an indicator of trauma to the head. Unlike extradural bleeding, a fracture plays no part in the pathogenesis of the haemorrhage, which arises from torn communicating veins that traverse the subdural space between the cortical vessels and the dural sinuses. Less often the sinuses themselves give rise to the haemorrhage.

Naturally in an open head injury or when comminuted fractures penetrate the membranes and perhaps the brain itself, subdural bleeding is merely part of a complex that includes subarachnoid bleeding, and cerebral laceration and contusion.

The lesion is often pure, however, being associated with a closed head injury where the only other signs may be scalp bruising – or even nothing at all, as blunt impacts may leave no signs in the scalp, externally or internally, and no skull fracture.

The latter situation is probably the explanation in most of the cases formerly attributed to shaking of the infant. Many paediatricians and pathologists have enthusiastically adopted the shaking aetiology when there was no overt sign of impact (or sometimes even where there was such evidence!) to such an extent that it is frequently proffered as the favoured diagnosis. However, the concept of the shaken-baby subdural has been strongly challenged recently, as it has been shown that the shearing force (required to rupture subdural vessels) is of the order of 50 times less in shaking than in impact (Duhaime *et al.* 1987). Thus it is very probable that perhaps the majority of allegedly shaken babies have, in fact, had an occult head impact, which has not left any signs on the scalp, subscalp tissues or skull.



FIGURE 5.32 *Formation of a subdural haematoma.*

Subdural bleeding arises from shear stresses in the upper layers of the cerebrum, which moves the communicating veins laterally sufficiently to rupture their junctions at either the cortical veins or the sinus surfaces. It is very rarely possible to identify the bleeding points. Subdural bleeding is most often over the lateral surface of a cerebral hemisphere, high up in the parasagittal area.

As with most intracranial damage, the mechanical cause is a change of velocity of the head, either acceleration or deceleration, almost always with a rotational component. Where a blunt impact strikes the skull, the subdural bleed need not be situated directly under the impact area – it need not even be on the same side of the head. It is sometimes tempting to attribute a localized subdural to either a 'coup' or to a 'contrecoup' effect (see below), but this is an unsafe interpretation. In addition, a subdural haemorrhage – unlike an epidural – is quite mobile. Lesions that have obviously originated high on the parietal area commonly drain down under gravity and cover the whole hemisphere, with a large accumulation in the middle and anterior fossas, and even through the tentorial opening into the posterior fossa.

The haemorrhage may remain fluid or may clot into a firm mass: both modes are commonly present. If the bleeding is relatively slight, then a 'thin-film' subdural may be found. If the thickness of blood is less than a few millimetres, it cannot be claimed to be a space-occupying lesion, even if the area covered is quite large, as the cerebrospinal fluid in the adjacent subarachnoid compartment can be displaced sufficiently to accommodate an equivalent volume of blood.

Again, Adams suggests that, as in any intracranial space-occupying lesion, a minimum volume of about 35 ml is required to cause neurological signs, though other writers prefer a larger volume, such as 100 ml.

Whether this film of fresh blood is a sufficient irritant to cortical activity – as it undoubtedly is in a subarachnoid haemorrhage – to be a danger to life, is uncertain. It is difficult to claim that a thin layer of blood in the subdural



FIGURE 5.33 *Chronic subdural haemorrhage in an old person. Brown liquid escaped from the encapsulated lesion adherent to the meninges leaving a gelatinous outer membrane, as seen. The surface of the right cerebral hemisphere is stained brown from old altered blood and there is some compression of the hemisphere with a midline shift to the left. There was no history of a head injury and no significant neurological deficit.*

space is the sole cause of death, but almost inevitably the force that caused the bleeding will also have had a deleterious effect on the brain tissue, even if this is macroscopically occult such as diffuse axonal damage.

As with the extradural haemorrhage, there may be a latent interval before clinical signs and symptoms appear. After the almost inevitable concussion, which may be very brief, the victim may recover, then relapse into deepening stupor and coma when intracranial pressure rises as the subdural bleeding proceeds. Associated brain damage may, however, cause uninterrupted coma from the time of injury.

When there is a lucid interval, this may be longer than the average 4 hours of the faster arterial bleeding of the epidural haemorrhage. In fact, there is no upper limit to this interval, as the acute subdural haemorrhage merges into the chronic condition, which may recur after weeks or even months. In severe acute bleeds, as are commonly encountered in criminal cases, such intervals tend to be short or non-existent.

Chronic subdural haematoma

This lesion is most often found in old people, frequently as an incidental finding at autopsy where death was caused by some unrelated condition.

The gross appearance varies with age; recent lesions up to several weeks old are tan or red-brown with a gelatinous membrane covering the surface. The contents are thick but liquid and may have areas of redder, more recent bleeding. An older haematoma, up to months or even a year old, is firmer, with a tough membrane around both surfaces, resembling a rubber hot water bottle filled with jelly or oil. The contents are liquid and may be brown or even straw coloured. Sometimes the interior may be much firmer and variegated in colour due to bleeds of different ages. Loculation is common, with different coloured fluids or ooze in each locule. The underlying brain will be depressed if the haematoma is large (more than 50–100 ml), and is often stained brown or yellow from altered haemoglobin.



FIGURE 5.34 *A chronic subdural haemorrhage discovered as an incidental finding at an autopsy on an old person dying of an unrelated cause. The blood was brown and gelatinous, but there was no membrane.*

Many such subdural bleeds in old people are small and obviously gave rise to no neurological abnormality; the mere finding of such a small lesion at autopsy should not be used to provide a cause of death, which should be sought elsewhere in the body. Some subdurals are substantial, however, reaching a volume of 100–150 ml. They may still have been asymptomatic, but others give rise to neurological symptoms that may have been ascribed to some other pathological cause. Examples are 'strokes', when unilateral signs were thought to be caused by a cerebral thrombosis or haemorrhage; disordered behaviour of the old person may have been blamed upon senile confusion or dementia, whereas in fact a space-occupying haematoma was really responsible.

The chronic haematoma may become large and press down on the cerebral hemisphere sufficiently to dent and distort the surface. This may progress, as does the large acute haemorrhage, to cause signs of hippocampal and cerebellar tonsillar herniation and all the attendant dangers to the vital centres in the brainstem. The chronic haematoma arises from the acute lesion, which, after an interval, becomes sheathed in a capsule of connective tissue. The haematoma may eventually absorb, it may remain dormant at the same size, or it may enlarge at any later date.

The mechanism of the enlargement is controversial. One common explanation, which seems the most reasonable, is that it occurs from repeated further bleeding, perhaps from new blood vessels that penetrate the mass as part of the healing process. The other theory involves osmosis, said to operate because the centre of the haemorrhage commonly liquefies, forming a haemorrhagic fluid that osmotically attracts into it the cerebrospinal fluid from outside the capsule, which acts as a semipermeable membrane.

The first mechanism seems more likely, as areas of fresh bleeding are often found inside a substantial haematoma but, whatever the cause, the final effect is a worsening of the space-occupying effect.

The dating of a subdural haemorrhage

An estimation of the date of onset of a subdural haematoma may have considerable forensic significance, especially if the lesion is obviously mature. There may have been one or more episodes of trauma on record, any of which may have criminal or civil connotations and the opinion of the pathologist will be sought to relate or to eliminate the lesion found from the potential causative event.

For example, in one of the author's cases an old lady was struck on the head by intruders and died several weeks later. At autopsy, a large chronic subdural haematoma was the main finding, but the defence sought to show that the haematoma must have been present before the assault by claiming that the woman's confused behaviour over the previous year was caused by the pre-existing intracerebral lesion. Furthermore, in accidents of any type, there may be doubt about whether the subdural haematoma arose as a result of the injury, or whether a pre-existing lesion caused unsteadiness that may have precipitated the accident.

Unfortunately, in spite of several claims to reliable methods of dating subdural haematomata, such estimations are of doubtful value, partly because repetitive bleeding results in varying ages within the same haematoma.

A subdural haematoma gradually changes from dark red to a brownish colour, first being apparent not before 5 days and sometimes not obvious for 10–12 days (Crompton 1971, 1985).

Reaction to subdural bleeding begins within a few hours of onset, when cellular infiltration begins from the dural surface. A delicate 'neomembrane', histologically composed of thin-walled capillaries and fibroblastic granulation tissue, grows from the periphery to cover the outer (dural) surface of the clot during the next few days and weeks. If no further enlargement occurs, this capsule becomes more and more fibrous, though rarely does it completely absorb the haematoma by fusing with the outer capsule. According to Crompton, the presence of a membrane firm enough to be picked off with forceps makes the subdural haemorrhage at least 12 days old.

Although claims have been made for accurate dating of subdural haematomas by histological criteria (Munro and Merritt 1936), these cannot be depended upon, especially after a few months, as there is considerable personal variation in healing rates. Also, because of the frequency of repeated subsequent fresh bleeding, attempts at estimating the date of the original bleed are unrealistic. As they are of some use as an approximate guide to age, Munro and Merrit's histological criteria are summarized briefly here:

- Fibroblasts appear at the margin of the clot within 36 hours and in 4 days the neomembrane adjacent to the dura is a few cells thick. From 5 to 8 days, the membrane becomes well established and fibroblasts migrate from it into the clot.
- By 8 days the membrane is 12–14 cells thick and is visible to the naked eye. From a few days after onset, there is progressive red-cell lysis and after 5 days haemosiderin-laden phagocytes are present, which may be stained by Perl's reaction.
- From 11 days the clot is subdivided by strands of fibroblasts. By 15 days a membrane is also present on the under surface of the clot and the outer neomembrane is half to one-third the thickness of the dura itself. By day 26 it equals the thickness of the dura, but the inner membrane is still only half as thick.



FIGURE 5.35 *Subarachnoid haemorrhage from a tiny berry aneurysm (arrow) of the right middle cerebral artery.*

- Between 1 and 3 months the membrane has lost many fibroblast nuclei and is becoming hyaline. By 6–12 months the membrane becomes thick and fibrous, resembling the dura itself.

A number of later writers have pointed to marked variations in this chronological scheme. Within the first couple of months large sinusoidal vessels appear in the newly formed connective tissue.

From gross appearances, a rough guide is that brown colour changes occur between the first and second week, when a discrete surface membrane becomes obvious. After a month or so a firm capsule develops, forming a cystic cavity containing dark brown, watery fluid. According to Munro, liquefaction of the contents does not occur in less than 3 weeks. Some haematomas remain solid with an organizing blood clot within, often with areas of fresher haemorrhage of different ages.

When a substantial subdural bleed has occurred, the underlying cerebral cortex may be infarcted, caused by either a natural infarct having bled through the arachnoid into the adjacent subdural space or, more often when there has been a head injury, the pressure of the haematoma on cortical blood vessels (Crompton 1971, 1985).

SUBARACHNOID HAEMORRHAGE

The third type of brain membrane bleeding is even more common than subdural haemorrhage, but has a mixed aetiology. Whenever there is damage to the cortex, there will be some degree of subarachnoid bleeding, so all penetrating injuries of the brain, as well as many blunt injuries that give rise to extradural or subdural haemorrhage, will be associated with traumatic subarachnoid bleeding.

It is not common, though not unknown, for traumatic subarachnoid bleeding to occur as a pure lesion where there is no cortical contusion, no neck injury, no deep brain lesion and no other membrane haemorrhage. Slight subarachnoid bleeding probably occurs very frequently after a moderate impact upon the head (as with slight subdural bleeding), but as the vast majority of such victims survive, no autopsy evidence is forthcoming. The increased sensitivity of medical imaging techniques, especially nuclear magnetic resonance, can demonstrate such minor bleeds which hitherto went undetected.

The other complicating issue with subarachnoid bleeding is that it frequently occurs as a result of natural disease, especially rupture of vascular malformations of several types. When trauma is also present, the complex association of either the trauma precipitating the rupture or a rupture causing a fall or other accident leading to the trauma, has to be considered. This is discussed in a later paragraph.

Although the pathology of subarachnoid haemorrhage is of prime forensic importance, because of the relationship to ruptured berry aneurysm, much of the description is offered in the chapter on sudden natural death (Chapter 25), and only the interaction between trauma and this type of bleeding is discussed here.

Appearances and mechanism of formation

The appearance of subarachnoid haemorrhage caused by trauma varies greatly according the nature and extent of the



FIGURE 5.36 *An extensive basal subarachnoid haemorrhage arising from a traumatic tear of a basilovertebral artery caused by a blow on the side of the neck.*

injury. Where it is secondary to laceration of the brain or extensive cortical contusion, then its localization and severity depend upon the primary injury. Where it arises from a blunt impact, with or without other membrane bleeding or cortical bruising, its position is not a good localizing sign. Once again, its position cannot be interpreted in the same way as contrecoup contusion of the cortex, though some pathologists use its position to claim that a head injury was sustained either from a fall or from a blow to a mobile head; this is unjustified. Although where the circumstances are known, the meningeal bleeding may be seen in the correct location, this is fortuitous and is equally often sited elsewhere.

Blood in the subarachnoid space mixes with the cerebrospinal fluid, which dilutes it, makes it less ready to clot and allows more mobility. Thus bleeding high over the cerebral hemispheres readily slides down to cover the brain and enter the basal skull fossae, but usually not in a concentration sufficient to form a thick clot. The sulci tend to collect more blood, especially in the insula. Unlike those with subdural bleeding, survivors from subarachnoid haemorrhages rapidly dispose of the blood. Haemolysis turns the cerebrospinal fluid a xanthrochromic yellow and, within weeks, the blood is gone. There may be some residual brown or yellow staining of the pia or arachnoid, similar to that seen when a slight dural bleed leaves its signature on the inner surface of the dura. A positive Perl's reaction for haemosiderin can develop within 36 hours and may remain for months or even years, even after macroscopic discoloration of the membranes has vanished.



FIGURE 5.37 *Cerebral arteries ('circle of Willis') and common sites for aneurysms.*

This forms a trap for those attempting to date both subdural and subarachnoid haemorrhage in infants, as the common bleeding arising from head-moulding during childbirth may leave a positive haemosiderin reaction for at least a year. Thus if a suspected child abuse head injury occurs in the first months of life, histological attempts to date the bleeding by Perl's reaction may be affected by residual haemosiderin from parturition.

Bleeding in the subarachnoid space is caused by the same mechanism as that in the subdural space, as shear stresses and rotational movements of the brain, described in a later section, shear or rupture the bridging veins that leave the cortex and penetrate the arachnoid en route for the large draining veins and sinuses that lie in the dura. In addition, small cortical arteries may contribute much of the leakage. Where laceration, contusion or infarction of the cortex is present, bleeding will come from cortical veins and small arteries directly into the subarachnoid space. It may also arise from intracerebral bleeding breaking out through the cortex. The subarachnoid haemorrhage allegedly caused by damage to the vertebral arteries near the foramen magnum will be discussed under spinal injuries.

The relevance of a subarachnoid haemorrhage in causing death may be difficult to decide, though this is of more importance in the natural variety caused by a ruptured aneurysm.

In head injuries, death is far more likely to be the result of the other concomitant associated injuries to the brain substance than to a moderate amount of blood in the subarachnoid space.

In the uncommon instances when a substantial subarachnoid haemorrhage seems to be the only sequel of a fatal head injury it must be accepted as the cause of death, though cerebral oedema and microscopic diffuse axonal injury should be excluded as competitors even though this exclusion may be difficult or impossible when death follows rapidly after injury. It is indisputable, however, that sudden death can occur from massive natural subarachnoid haemorrhage in the absence of any traumatic lesions so, by analogy, the pure traumatic bleed – if severe enough – cannot be excluded as a sole cause.

Death can be remarkably rapid when a profuse haemorrhage occurs into the subarachnoid space. The mechanism is not understood, but seems to be confined to those cases where the brainstem is suddenly exposed to a large volume of blood bathing the brainstem in the posterior fossa, usually from a ruptured aneurysm or from a torn basilar or vertebral artery. Numerous instances of victims virtually dropping dead are on record, though many more exhibit the familiar signs of headache, neck stiffness, vomiting and progressive failure of consciousness, before dying at a variable period after the haemorrhage.

FORENSIC IMPLICATIONS OF BRAIN MEMBRANE HAEMORRHAGE

Because of its common occurrence, certain medico-legal problems associated with bleeding into the brain membranes must be considered.

First, the latent or ‘lucid’ interval in both extradural and subdural haemorrhage may lead to civil suits for negligence where a doctor – usually in a hospital emergency department – discharges an apparently well patient who later dies at home or is readmitted **in extremis.** The clinical aspects cannot be considered here, but suffice to say that it is highly unlikely that such patients would not have suffered concussion, albeit transient. Radiology of the skull is not mandatory if the clinical indications are not present, but failure to X-ray can be a legal impediment for the defence. A subdural haemorrhage is commonly present with an intact skull, though this is uncommon with extradural bleeding.

As already mentioned, the dating of subdural haematomas may be crucial in both criminal and civil cases when it is being either maintained or denied that a particular episode of head injury causes the haematoma. Dogmatic adherence to any accurate histological dating regimen is unjustified, though broad distinctions in terms of days, weeks or months may be justified.

The possibility of a previous bleed being the precipitating factor in some later accidental injury, which then caused further bleeding, must be kept in mind.

Using a membrane haemorrhage to localize an impact can be subject to over-interpretation. An extradural haematoma is almost invariably on the same side as the blow, but because of the distortion of the skull described earlier, the fracture that traverses the meningeal artery can be some distance from the point of impact. Using Gurdjian’s work, however, a reasonable estimate of the zone can be offered.

Where subdural or subarachnoid bleeding is concerned, it can be misleading to offer dogmatic opinions about the nature and position of the impact, unless there is scalp or skull damage. Though sometimes it is clear from the presence of a scalp injury that the haemorrhage is either ‘coup’ or ‘contrecoup’, there are so many exceptions when the bleeding is unrelated to the site of the blow, that a firm opinion is not justified.

RUPTURED BERRY ANEURYSM AND TRAUMA

A major cause of medico-legal problems is the association of trauma and subarachnoid haemorrhage from a ruptured ‘berry’ aneurysm. The pathology of the latter is described in another chapter, but here we are concerned with the allegations that an injury led to rupture of a pre-existing aneurysm.

Several variations of this scenario exist. Most commonly, an assault is rapidly followed by the signs of subarachnoid bleeding and subsequently death. Occasionally death may be extremely rapid, as previously described. The question of causation then arises, the prosecution claiming that the head injury mechanically ruptured the aneurysm. Whether this is actually so is virtually beyond absolute proof. Aneurysms of the circle of Willis are remote from the skull surface and lie deeply protected under the buffer provided by the mass of the brain. However, it is hard to deny that a heavy blow to the head, jaw or neck could not rupture, split or weaken the fragile wall of a large, thin-walled aneurysm, but when the bleeding comes from a tiny sessile bulge the evidence is not so convincing.

The complicating factor is that most assaults occur in 'fight or flight' conditions in which both aggressor and victim are physically and emotionally active, so that the adrenal response is likely to be present. Muscle tone, heart rate and blood pressure are increased by catecholamines, and it is likely that raised internal blood pressure in a weak aneurysm is a far more potent reason for rupture than a blow on the head.

A second possibility is that a person with an already spontaneously leaking aneurysm may have a rapidly developing neurological or even behavioural abnormality that leads him into conflict with another person, or into a dangerous physical position, such as a fall or traffic accident. If all this occurs over a short period of time, autopsy may not be able to distinguish the sequence of events and the aneurysmal rupture may be blamed on the trauma instead of the reverse. This may have profound civil as well as criminal legal consequences.

SUBARACHNOID HAEMORRHAGE AND ALCOHOL

A factor that is often said to increase the chance of rupture is alcohol, though there is no objective proof of this claim. A high blood alcohol is said to facilitate bursting of an aneurysm because it dilates cerebral blood vessels, increases cerebral blood flow and raises blood pressure.

The latter is not true because alcohol does not raise systolic pressure, though the pulse pressure – the difference between systolic and diastolic – may widen. The fibrous wall of an aneurysm is incapable of dilating, neither can the major basal arteries do so to any appreciable degree, as they possess little muscle in their walls. The pharmacological evidence that alcohol has any significant effect on the cerebral circulation is extremely weak. There is no evidence that alcohol is associated with completely natural subarachnoid haemorrhage from a ruptured aneurysm, though intense physical activity, such as sport or coitus, certainly does predispose to rupture.

Where alcohol and ruptured berry aneurysm are concerned, a more likely explanation is that the association is coincidental – as most altercations resulting in 'flight, fight and fisticuffs' are catalysed by alcohol. Many of the cases of ruptured aneurysm and violence occur within and on the pavements outside bars and clubs, where a high blood alcohol is virtually inevitable – but not necessarily causative.

The other aspect of alcohol is that it may cause or contribute to unsteadiness, a fall or some other traumatic event, which itself might lead to rupture of a fragile aneurysm. Ataxia and hypotonia are a feature of acute drunkenness and, together with the aggressive behaviour and alcoholic environment of most physical violence, seem sufficient to account for their circumstantial association.

THE RAPIDITY OF DEATH IN SUBARACHNOID HAEMORRHAGE

The immediacy of death is sometimes surprising, especially in association with trauma. It is general clinical experience that the victim of a spontaneous rupture of a berry aneurysm suffers a severe headache, neck stiffness and vomiting, which may resolve or which may progress over hours or days to coma and death. Sudden death is certainly the exception in these clinical cases – but these are from a hospital population, which, by definition, excludes the rapid deaths that reach the mortuary rather than the wards.

In forensic practice, much more rapid demise is not uncommon. For example, the author (BK) recollects that as two men involved in a violent argument in a public house emerged through the outer doors, one struck the other a heavy blow on the head. The victim fell to the ground and never moved again, being certified dead a few minutes later. At autopsy, a typical fresh subarachnoid bleed from a ruptured aneurysm was displayed.

The amount of blood present in most subarachnoid haemorrhages, from whatever cause, often seems insufficient to constitute a space-occupying lesion, especially as, unlike subdural bleeding, it is able to diffuse more widely over the brain and displace cerebrospinal fluid into the spinal theca. The total volume may be considerable, however, and where survival for some hours has occurred, then the typical appearances of raised intracranial pressure may be seen at autopsy, though some of this may be contributed by progressive cerebral oedema.

Most rapid deaths exhibit substantial bleeding into the basal cisterns at autopsy, the brainstem and cranial nerve roots being bathed in a thick layer of blood and clot. As blood in the subarachnoid space seems irritant even in small quantities, it seems possible that such sudden irrigation of the medulla may lead to a rapid cardiorespiratory failure. Where the haemorrhage appears less extensive, the mechanism of death is more obscure.

Crompton points out the sensitivity of cerebral arterioles during surgical operations, when a slight touch upon the cortex leads to blanching spasm of the vessels. Subarachnoid bleeding is undoubtedly irritant and a possible reason for the sudden collapse and death is a widespread vascular spasm, which may have an effect on vital centres in the brainstem.

ROTATIONAL TRAUMA TO THE HEAD AND UPPER NECK: BASILOVERTEBRAL ARTERY INJURY

During the last few years it has been recognized that blows to the side of the neck and/or head can give rise to fatal subarachnoid bleeding. This has been attributed to tearing or dissection of a vertebral artery, allowing blood to track along the upper part of the vessel and enter the cranial cavity where the artery penetrates the dural membrane at the foramen magnum.

The evolution of this concept of traumatic subarachnoid bleeding is interesting. Originally, it was thought that most cases had a fracture of the transverse process of the first cervical vertebra, thus damaging the artery contained in the tunnel-like foramen in this bone – indeed, it was often called the ‘CV-One syndrome’.

The hypothesis was that a blow to the side of the neck caused deep injury, usually manifested by skin bruising and bleeding into the muscles deep in the upper neck. This same injury was considered to fracture the transverse process and lead to tearing or dissection of the wall of the contained vertebral artery; blood then tracked upwards and medially to penetrate the dura and emerge inside the subarachnoid space of the posterior cranial fossa to cause a fatal haemorrhage.

Soon cases were being described with no such atlas vertebra fracture, but it was still accepted that mechanical forces, especially of a tilting and rotational nature, could damage the vertebral artery within the foramina of the upper cervical spine and lead to the same dissecting lesion, and hence to fatal subarachnoid haemorrhage. Until very recently, this was the theory – which is still strongly held by many pathologists – that satisfied the aetiological needs of this injury.

However, though it is likely that this classical mechanism does account for some of the deaths, there are several problems with universal acceptance of the hypothesis:

- Many pathologists – including the authors – find it hard to believe that a tiny dissection of a small artery like the vertebral artery – a lesion which often needs serial microscopic sections to confirm – could allow the torrent of blood necessary to enter the cranial cavity and produce a massive haemorrhage (sometimes well in excess of 100 ml) which may cause death within minutes.
- Several instances of a damaged vertebral **vein** have been reported in association with subarachnoid haemorrhage. Because of the very much lower intravascular pressure in a vein compared with an artery, the possibility of this causing a massive intracranial bleed by percolation through the dural fenestration is even less credible than in the case of the artery.
- Increasing numbers of cases are being described with positive evidence of a blow on the side of the neck or head and a large fatal subarachnoid haemorrhage, but with completely intact vertebral arteries.

Thus, if sudden tilting and rotational forces acting on the upper spine and head can lead to subarachnoid haemorrhage without damage to the vertebral vessels, then the causative link is destroyed. Even where vertebral damage is demonstrable, this may be merely a **concomitant** event, the mechanical forces which primarily led to subarachnoid haemorrhage by direct injury to intracranial vessels also having caused the vertebral artery damage. In other words, the two lesions may in some cases – or for all we know, every case – be a **parallel** phenomenon, not a **cause-and-effect** situation. There may well be a further concomitant effect, in that direct occult brain damage, manifested later by diffuse axonal injury, is the major cause of cerebral dysfunction, both the subarachnoid haemorrhage and the vertebral artery lesion (if there is one) being merely markers of a heavy impact.

In these deaths – and certainly where no lesion at all is discernible in the upper spinal vessels – we need to look elsewhere for an explanation of the subarachnoid bleeding.

Occasionally, this is quite obvious and is situated in the intracranial vertebrobasilar vessels. For example, the author (BK) has seen a wide split in the wall of a vertebral artery **within** the posterior cranial fossa, and another where the vertebral artery was totally avulsed and transected at the internal side of the dural perforation. Both these cases arose as a result of trauma to the side of the neck, and both had a massive subarachnoid haemorrhage with no damage to vessels outside the cranium.

Bostrom, Helander and Lindgren (1992) published details of two cases of rupture of the posterior inferior cerebellar artery due to blunt basal head trauma, and proposed that the term ‘traumatic subarachnoid haemorrhage’ be abandoned and replaced by the nature and localization of the bleeding site.

The demonstration of intracranial bleeding from the vertebrobasilar system is difficult, as the very process of opening the skull at autopsy and removing the brain, however carefully performed, inevitably causes vascular damage. These artefacts cannot be distinguished from original bleeding points due to ante-mortem trauma.

The use of post-mortem angiography by the injection of radio-opaque constrast medium into the lower vertebral and carotid arteries has not lived up to its original claims. There is almost always diffuse leakage of contrast medium from apparently artefactual defects, and localization of true bleeding points is often obscured by a haze of contrast opacity. However, occasionally the method reveals a specific leak, usually within the posterior cranial fossa.

The original descriptions of and claims for vertebral artery damage as the cause of traumatic subarachnoid haemorrhage were published by Cameron and Mant (1972), Coast and Gee (1984), Contostavlos (1971, 1995), Simonsen (167, 1976) and others. Leadbeatter (1994) drew attention to the problems of a universal cause-and-effect relationship; Contostavlos (1995) refuted these claims, but did not satisfactorily dispose of the concomitant hypothesis. Pathologists, both from their dissection experience and reading of the literature must make up their own minds on the matter, but should make a critical evaluation of the practicality of a massive subarachnoid bleed appearing, sometimes within minutes, from a tiny dissection of a small artery outside the dural membrane.

As many pathologists still adhere to the original concept of a subcranial vertebral artery causation for traumatic subarachnoid haemorrhage (and in a small number of instances, the evidence is persuasive), the topic is further pursued here, with the over-riding qualification that most traumatic massive meningeal bleeds are due to intracranial causes consequent upon a tilting, rotatory impact upon the head and/or neck, with or without concomitant damage to a vertebral vessel.



FIGURE 5.38 *The origin and course of the vertebral arteries. They arise from the subclavian arteries at the level of the sternoclavicular joints and ascent via the foramina in the transverse process.*

Forensic anatomy

The two vertebral arteries arise from each subclavian artery in the region behind the sternoclavicular joints. Each artery ascends behind the common carotid to reach the transverse process of the sixth cervical vertebra. It enters the foramen in that process and passes upwards through each similar foramen until it emerges from the upper edge of the second (axis) vertebrae. The artery then bends laterally and enters the final foramen in the atlas vertebrae. Emerging on the upper surface, the artery bends back and medially around the superior articular process, and penetrates the posterolateral aspect of the atlanto-occipital membrane and the underlying spinal dura and arachnoid, emerging on the lateral side of the spinal canal just below the foramen magnum. Both arteries then ascend and converge on the ventral surface of the medulla and pons to fuse in the midline to become the basilar artery. Each vertebral artery is often of markedly different size.

Autopsy appearances

With the caveats expressed earlier, the possibility of vertebral artery trauma, concomitant or otherwise, should always be borne in mind when an external bruise is seen on the side of the neck of the victim of a fatal assault. A blow from a fist, foot or blunt weapon may land in the region between the angle of the jaw to the side of the back of the neck, the area below the ear being the most common place to find an injury.

There may be no external sign at all, but on dissection of the neck, a subcutaneous or deep bruise may be found. Unfortunately, this is an area that is not routinely dissected at autopsy, the usual incision for the removal of the neck organs being too far anterior to reveal many of these injuries, which usually lie in the strong neck muscles. This is probably why the syndrome was not recognized until a few years ago – and also an explanation why so many subarachnoid haemorrhages were said to be due to a berry aneurysm that could not be found because the bursting had destroyed it. No doubt a number of subarachnoid bleeds are due to rupture of non-aneurysmal vessels or to an aneurysm too small to find, but equally, unrecognized head trauma, with or without vertebral artery damage, must have accounted for some of the remainder.

In some autopsies, there is no external neck injury and the cause of death is unknown until the cranium is opened, and a fresh subarachnoid haemorrhage discovered. A decision then needs to be made whether to remove the brain to search for a ruptured berry aneurysm – or begin specialized techniques to seek a rupture of a vertebral artery (described below). If there is a history of assault or other trauma, as opposed to a presumed natural death, then particular methods should be employed. The two avenues are not mutually exclusive, as long as the pathologist is aware of his objectives. The vessels can be clamped off at the base of the brain and the brain removed for a search for an aneurysm or other bleeding-point without spoiling the other techniques.

Mechanism of vertebral artery trauma

When a head is rapidly rotated by a blow that lands at the junction of the head and the neck, there may be a sudden lateral rocking (tilting sideways) at the atlanto-occipital joint, accompanied by rotation of the head. There may also be an element of hyperextension or hyperflexion, the whole episode forming a complex pattern of sudden abnormal movement at the atlanto-occipital junction. It may be that the unexpected impact may allow more unrestrained rotation and angulation of the head, due to absence of anticipatory muscle tensing in the large paravertebral and sternomastoid musles; this may be exacerbated by alcoholic intoxication causing slow protective responses, as most of such episodes occur during altercations related to drinking sessions.

The mechanics are not fully understood and probably differ from case to case but, whatever the mechanism, the vertebral artery can become damaged either:

- in the canal within the first cervical vertebra (whether or not the transverse process is fractured)
- just below the axis, in the space between the transverse processes of the axis and atlas
- as it emerges from the exit of the canal in the atlas to penetrate the spinal dura just below the foramen magnum
- probably much more frequently within the subarachnoid space above the foramen magnum or even higher in its course towards the confluence with the basilar artery – and even the basilar itself. The type of damage is usually a tear or dissection of the wall of the vertebral artery.

Vertebral artery damage was originally said to allow blood to track under arterial pressure within the adventitia and to appear in the subarachnoid space after the vessel has penetrated the dura and arachnoid, though, as discussed above, the likelihood seems slight of these minute lesions allowing the large volume of blood seen in most subarachnoid haemorrhages to flow through the small periarterial window in the dura.



FIGURE 5.39 *Most vulnerable points for trauma to the vertebral arteries: (1) at penetration of dura; (2) at exit from atlas transverse process; (3) in osseous canal in atlas.*

Autopsy demonstration of basilovertebral artery damage

When circumstantial evidence suggests a subarachnoid haemorrhage following trauma or where a bruise is seen on the side of the neck, vertebral artery damage should be suspected, then confirmed or eliminated. The first intimation that it may have occurred may be when the skull-cap is removed and a subarachnoid haemorrhage is discovered.

If the view is taken that most subarachnoid haemorrhage following upper neck trauma is due to intracranial vascular damage, then logically it is unnecessary to use time-consuming and laborious procedures which slow up the completion of the case. In many such deaths, there will be no lesion in the upper cervical spine or extracranial vertebral arteries and even if there is, it is likely to be a concomitant lesion, occurring synchronously, but with no cause–effect relationship with the intracranial vessel rupture.

However, there may be academic satisfaction in demonstrating the concomitant neck lesion, even if it played no role in producing the subarachnoid haemorrhage. In such a case, when the deceased has been in a fight or had some violence applied to the side of his neck, the same routine should be employed.



FIGURE 5.40 *The first cervical ('atlas') vertebra viewed from above to show the foramina in the transverse processes through which the vertebral arteries pass.*

Different pathologists have different procedures, but the following would be a reasonable method of investigation:

- Radiographs of the upper cervical region, both anteroposterior and lateral, should be taken as these may (rarely) reveal a fracture of the transverse process of the atlas vertebra. Such a fracture is, however, present in only a minority of vertebral artery injuries – and even when present, straight X-rays may not reveal it.
- Post-mortem angiograms should be taken if facilities exist. There are several methods of performing these. The lower neck is carefully dissected to reach the origins of the vertebral arteries. The best method is to open the subclavian vessels and identify the ostia of the vertebrals, which are the first (most medial) branches of the subclavian arteries. These can be cannulated and contrast media injected, one side at a time, while cervical and skull radiographs are taken. This method tends to fill many intracranial vessels and produce a confused, blurred picture.

  More satisfactorily, the brain should be carefully lifted from the skull and, as soon as the basilar artery is accessible, it should be clamped off with surgical forceps and/or ligated and the brain completely removed as usual after the basilar artery has been transected just above the clamp. Alternatively, each vertebral artery can be clamped or ligated in its terminal course. The angiogram is now performed, either by perfusing up one vessel and forcing contrast medium back down the other via the clamped basilar, or by consecutive injections on either side. Only sufficient medium to fill the system should be introduced to avoid spillage from small branches which obscure the films. The object is to detect any significant leakage from a vertebral vessel in its upper course, usually within the foramen of the atlas or just outside the atlanto-occipital membrane or within the spinal theca.
- As by definition, there will have been a substantial subarachnoid haemorrhage, this sometimes makes it difficult to identify and ligate the basilar or vertebral vessels. The brain should be minutely examined for berry aneurysms or other vascular malformations as, if they are present (and ruptured), then further investigation of vertebral artery damage is pointless. Assuming no such bleeding point is found, the upper cervical region is dissected to determine whether the vertebrals have been injured. When no X-ray or angiographic facilities exist, this is the only method available.

The upper cervical spine should be exposed by a posterior approach, which is continued up to meet the transverse scalp incision. The spine should be freed from the surrounding muscles, taking care to detect and record any muscular bruising in the vicinity. It should then be sawn through at about C4 level or lower.

The occipital bone should then be cut through on each side from the transverse skull saw-cut and prolonged down on each side of the foramen magnum, and then across the clivus to release the central part of the floor of the posterior fossa, carrying the foramen magnum and attached upper spine. Alternatively, using a power saw with a wedge-shaped blade, a square may be cut out of the floor of the posterior fossa to detach the spinal block. If possible, X-rays should be taken of the detached portion, as it may be possible to see a fracture of the transverse process of the atlas better than in the intact body.

The block of bone removed should then be decalcified by prolonged immersion in a large volume of 10 per cent formic acid.

After a week, the spine will be soft enough to slice with a scalpel, so that the lateral parts of the transverse processes can be shaved away, taking care not to get near the arterial foramina. The block is then returned to fresh decalcifying fluid for a further week.

Once the bone has been softened enough to be cut easily by a sharp knife, the transverse processes can be further shaved down on each side to the level of the foramina, so exposing the artery in its whole course. Both sides should be so dissected, the last stages being taken deeper and deeper with extreme care to remove the lateral walls of the canals without damaging the underlying vessel. Naturally, the crucial area is in the upper one or two vertebrae, but though laborious, this method provides the most elegant and convincing demonstration.

Specimens should be taken of any obvious or suspicious breach in the wall for histological examination. The usual type of damage is either a frank tear of the intima and media, or a dissection that allows blood to track through the adventitia.

The papers by Vanezis, Simonsen, and Cameron and Mant, among others, should be consulted for further details of the recommended procedures, but the above is a practical approach to demonstrating vertebral artery lesions. Once again, the relationship must be assessed of any tiny dissection, to the volume of blood found in the cranial meninges – and a decision made as whether this is more likely to be a concomitant injury to intracranial vessels rather than a solitary external vertebral artery lesion.

HEAD INJURIES IN BOXERS

It has become increasingly apparent in recent years that persons who indulge in boxing are at risk of both acute and chronic damage to their brains. In some countries, including parts of Scandinavia, both professional and amateur boxing is banned for this reason. The acute injuries are less common but occur during or soon after the fight itself. A number of boxers have died in the ring or after removal to hospital and, in these fatalities, by far the most common lesion is a subdural haemorrhage. Extradural bleeding almost never occurs, because boxing injuries rarely cause skull fractures. Occasionally a subarachnoid haemorrhage may occur in rare cases where a berry aneurysm is present.

Much attention has been paid to the chronic changes in boxers' brains, which are very common and give rise to what is generally known as the 'punch-drunk' syndrome. It appears that the length of time for which a boxer has been involved in fighting is more important than the number of serious traumatic events he has suffered. It is a cumulative process and many episodes of minor head injury add up to produce the typical lesions described in the now extensive publications on the subject.

There are both anatomical and microscopic lesions in such brains, both in professionals and amateurs exposed over a number of years. The clinical symptoms do not concern the pathologist, but they are explained by the morphological abnormalities. Grossly affected brains may show some cortical atrophy and slight hydrocephalus; the septum pellucidum is characteristically perforated with enlargement of the cavum and tearing of the septal leaves. The fornices and adjacent corpus callosum may be thinned or torn, and throughout the brain substance there may be scars and patches of gliosis. Neurones are lost from the cerebellum and the substantia nigra, the latter often losing pigment.

Another change that has intrigued neuropathologists is the development of an Alzheimer's-like condition, with neurofibrillary tangles throughout the cerebral cortex and brainstem, though no senile plaques are present.

CEREBRAL INJURIES

Though bleeding or infected scalp injuries, depressed fractures, meningitis and substantial meningeal haemorrhage can themselves cause death, in most fatal head injuries it is damage to the substance of the brain itself that is lethal.

In medico-legal practice it is sometimes difficult to convince lawyers that, in most instances, a victim does not die of a simple fractured skull, but that the fracture is evidence only of a substantial head injury, being a 'marker' for concomitant brain damage, which was the real lethal lesion. Similar problems of communication exist with a fracture of the hyoid bone in strangulation, lay persons often being under the misapprehension that a broken hyoid is a mortal injury, instead of merely being an inconstant marker of pressure on the neck.

The neuropathology of brain damage is a large and complex subject, the more subtle varieties requiring both specialist techniques for demonstration and expert knowledge for interpretation. The textbooks of Graham, Adams and Leestma are recommended for detailed description and discussion of cerebral trauma.

The mechanisms of production of some traumatic lesions are matters of conflicting theories, but the forensic pathologist still has to be aware of the general principles of causation in order to offer some interpretation of the injuries.

As always, caution has to be employed, as both the pathological and clinical manifestations of a head injury may appear to be at variance with the degree of force applied to the head. There is a wide range of lesions from a given insult to the head and it is dangerous to be too dogmatic in theorizing about the magnitude of an injury that gave rise to the demonstrable lesions.

It is similarly unwise to hypothesize too firmly about what clinical features must have occurred when the head injury was sustained – for example, quite severe head



FIGURE 5.41 *Mechanical events that contribute to primary brain injury. (Reproduced from* Greenfield's Neuropathology, *7th edn, 2002 by kind permission of Arnold.)*

injuries have been known to be unaccompanied by concussion, while other apparently slight damage has often been followed by prolonged unconsciousness even ending in death. The well-known aphorism of Munro (1938) must be kept in mind that: 'Any type of head injury can give rise to any type of intracranial damage.'

The mechanism of brain damage

The brain may be injured in the following ways:

- by direct intrusion, either by a foreign object such as a penetrating weapon, bullet or other missile – or fragments of skull in a compound fracture where the skull is disrupted. In these open wounds the mechanism of the damage to the brain is obvious, though of course it may be compounded by the second type of injury described below
- by deformation of the brain in closed head injuries. Here the mechanism of injury is complicated and variable, with several competing theories of causation that have been put forward since the eighteenth century (Ledran 1751, Morgagni 1761). A public debate was held in 1766 in Paris, where rival theories of coup and contrecoup brain damage were hotly defended at the Academy of Surgeons.

The brain is almost incompressible and purely axial impact may give rise to little or no damage. It is extremely rare, however, for an impact not to impart some rotatory movement and it seems agreed that this component is the main culprit in causing brain damage. What is now clear is that no actual blow or fall need be suffered by the head to cause severe and even fatal brain damage. It is the change in velocity – either acceleration or deceleration – with a rotational rather than solely axial element, that leads to damage. The surface of the head need never contact any hard object or surface, though recent research indicates that the quantum of energy delivered by impact is of a far greater order of magnitude that non-impact violence, which lessens the former conviction that shaking, as in child abuse, is a common and potent mechanism in the production of intracranial damage.

In most head injuries – notably traffic accidents and falls – there is marked deceleration of the moving head on contact with a fixed surface but, in many criminal and combat injuries, the head is accelerated by a blow. In either case the initial sudden change in velocity is applied to the scalp and skull, the latter then transmitting the change to the brain via the anatomical suspensory system within the cranium. This system is slightly flexible and consists of the falx and tentorium, which divide the cranial cavity into three major compartments; these contain the two cerebral hemispheres, the cerebellum and the brainstem. When violent relative movements take place between the brain and the dura, forming the partitions of the cranium, the cerebral tissue can become damaged against both the sharp edges and the flat surface of these membranes. In addition, vessels traversing the subdural and subarachnoid spaces can be torn by such relative movements, especially in old people where cerebral atrophy may have widened these spaces.

Among the competing theories of impact brain damage are:

- the rotational shear force theory
- the pressure gradient theory
- the vibration theory
- the transmitted wave force theory
- the brain displacement theory
- the skull deformation theory.

These hypotheses overlap and most are correct in some aspect. Because experiments on primates and mechanical models have been pursued vigorously in recent years, it is now widely accepted that there are marked pressure changes within the cranium on impact (Yanagida *et al.* 1989). When a head falls against the ground, pressure momentarily increases at the impact point but falls to a negative value diametrically opposite. As these suction or cavitation effects are more damaging to neural and meningeal tissue than pressure, this is good evidence for claiming that contrecoup damage is largely a result of this vacuum effect.

The actual physical disruption of cerebral tissue is caused, according to both Gurdjian and Holbourn, by one or more of the following processes:

1 compression of the constituent units, by their being forced together
2 tension of the units, which pulls them apart
3 sliding or 'shear' strains, which move adjacent strata of tissue laterally. The usual homely example is given of a pack of playing cards being displaced, so that each card slides upon its neighbour.

Transient deformation of the skull almost certainly contributes to brain damage (Rowbotham 1964). The area of the skull beneath an impact becomes momentarily depressed even if it does not fracture and therefore may impinge on the underlying brain causing compression, as in 1, above. This is responsible for the typical cone-shaped contusions on the cortex, with the base at the surface, as the impact – possibly via short-lived oscillations of decreasing amplitude – injures the cortex and passes a diminishing force down into the deeper layers.

Simultaneously, other areas of the skull must bulge outward to accommodate the deformation – the so-called 'struck-hoop' action – when it is suggested that a 'rarefaction' remote from the impact may cause tension damage, as in 2, above.

More important is 3, being laminar deformity or 'shear stress' caused by the angular rotation of the head. As the head is pivoted on the first cervical vertebra, almost any impact on jaw, face or cranium will produce an angular momentum, the acceleration being conveyed first to the skull.

Alternatively, if the head is moving and is suddenly arrested, then the skull will decelerate first and the momentum of the brain will cause it to continue in motion, again almost certainly with some rotatory component.

In either the deceleration or acceleration mode, the skull and brain cannot change their velocities simultaneously and the brain will speed up or slow down only by virtue of the restraint provided by the dural septa and the configuration of the interior of the skull. In other words, the brain is either retarded or set into motion secondarily by the skull, especially by the dural septa and the bony prominences.

This restraint will occur first – and with maximum effect – on the most superficial layers of the cortex. These in turn will drag on the next deepest layer and so on until the difference in velocity is equalized – but this will have been at the expense of laminar tearing of the cerebral tissue and its associated blood vessels. In addition to this shearing damage, the brain may be forced against the sharp edge of the tentorial opening and the lower edge of the falx, causing damage to the base of the cerebrum, the corpus callosum and the brainstem. Impact against the side wall of the skull and against the falx may cause diffuse contusion of the cortex. The cerebellum tends to suffer less damage, as it is much smaller and lighter than the cerebrum and there is less room for relative movement in the more tightly enclosed posterior fossa. The configuration of the interior of the cranium is thought to be partly responsible for the common localization of cerebral damage at the tips and undersurface of the frontal and temporal lobes. The rough floor of the anterior fossa, the sharp edge of the wing of the sphenoid and the massive bar of the petrous temporal bone are in contrast to the smooth inner surface of the vault of the skull.

Cerebral contusion

When either linear or, more often, laminar stresses are applied to the cortex, this soft tissue may disrupt. Part of the injury is directly upon the neurocellular structure, but damage to vessels is an important component. If the cortex still retains its shape, but is bruised and swollen, this constitutes 'contusion'. A greater degree of disruption, sufficient to produce macroscopic tearing, is termed 'laceration', but the difference is only one of degree. In gross head injuries, such as crushing, missile wounds and other major penetration, the degree of laceration may lead to partial or even complete extrusion of the brain from the cranial cavity.

In the usual type of cortical contusion seen in a closed head injury, the cortex is blue or red from haemorrhage, though if survival has lasted for some time, there may be added discoloration from associated cortical infarction. The haemorrhage may be diffuse or may be punctate and is often a mottled purplish red when confined to the cortex. Extension into the underlying white matter tends to be pure red in fresh lesions. The lesion is often wedge-shaped, with the base on the surface, tapering away into the deeper layers.

Cerebral laceration

Laceration of the cortex is an extension in severity of contusion in which mechanical separation of the tissue can be seen. When widespread, but relatively superficial, the cortex appears to have a 'red velvet' appearance, which becomes progressively more tattered as the severity increases.

When it is even more severe, the cerebral surface becomes fissured, fragments of cortex may detach and deep lacerations run into the depths of the hemisphere, sometimes reaching even the deep ganglia or ventricles. There may be deep haemorrhage and – especially in the frontal and temporal lobes – the lacerations may be continuous with areas of traumatic haemorrhage. In cerebral lacerations and most contusions, the pia mater and often the arachnoid are torn, so that blood from damaged cortical vessels leaks into the subarachnoid and even subdural spaces. The corpus callosum is commonly torn, especially at its posterior end. This must be distinguished from damage caused by clumsy removal of the brain at autopsy (as must tears of the cerebral peduncles), but when genuine, may represent either a guillotine effect of the free lower edge of the falx or differential lateral movement of one hemisphere relative to the other, again because of unilateral restraint by the falx. Lacerations and contusions are most often found in those areas of the brain where the cortex is most likely to come into contact with irregularities in the internal profile of the skull. The undersurface of the temporal lobes and the orbital surface of the frontal lobes suffer most often.

Traumatic intracerebral haemorrhage

Substantial areas of haemorrhage, either infiltrating the brain tissue or forming actual haematomas, are common in severe head injuries. Some are primary, occurring at the time of impact or soon afterwards; others are secondary and caused by changes in intracranial pressure or bleeding into infarcts caused by vascular damage. These are all seen more often since artificial ventilation has been available, as victims of severe head injuries now survive longer so that there is time for secondary lesions to become apparent.

In the cerebral hemispheres, deep haemorrhage can be caused by coup or contrecoup mechanisms (see below) and may be situated anywhere within the hemispheres. They may rupture into the ventricular system or through the overlying cortex. In some severe contrecoup lesions, there may be large haematomas in one or both frontal lobes with overlying cortical contusion and laceration. These may rupture through the cortex into the meningeal spaces, forming what is sometimes called a ‘burst lobe’. Such haemorrhages sometimes pose a problem for the pathologist when they occur in older subjects, especially those with hypertension and perhaps cerebral atherosclerosis. When a scalp injury is present – and perhaps even a fractured skull – it may be difficult to decide if a head injury (such as a fall) was responsible for the cerebral haemorrhage, or whether a sudden ‘stroke’ caused by a natural cerebral haemorrhage resulted in the fall. The problem is discussed further in the chapter on natural death, but briefly, the presence of left ventricular (cardiac) hypertrophy, a history of hypertension and the site of the (usually solitary) haemorrhage tends to point to a natural bleed. This is especially so if the large size of the lesion seems inconsistent with the degree of head injury sustained. Hypertensive lesions tend to be in the thalamus, external capsule, pons and cerebellum, and are more often occipital than frontal or temporal. Having said that, on occasions it can be impossible to differentiate the two conditions.

Primary brainstem haemorrhage

Secondary brainstem bleeding is dealt with under ‘cerebral oedema’ so here we are concerned with haemorrhage that occurs at the time of injury. As mentioned above, hypertensive haemorrhages not associated with trauma can occur in the midbrain, especially the pons. These tend to be large, explosive lesions that greatly swell the pons and disrupt the central part of the stem, usually with a ragged rim of white matter around the periphery. Traumatic haemorrhage in the brainstem is often a well-circumscribed lesion, sometimes rounded, which lies laterally in the tegmentum, the shape of the midbrain being undistorted (unlike a secondary bleed into an elongated stem).

The typical site is between the aqueduct and the outer end of the substantia nigra. Primary stem haemorrhages are usually associated with occipital impacts and the victim is often unconscious from the time of the injury, as opposed to the lucid interval and gradual decline of those who suffer secondary stem lesions because of a developing cerebral oedema or space-occupying meningeal haematoma.

Coup and contrecoup damage

Whatever the underlying mechanics of cerebral damage, one aspect is of considerable practical importance to the pathologist. When a mobile head is struck with an object, the site of maximum cortical contusion is most likely to be beneath or at least on the same side as the blow. This is the so-called ‘coup’ lesion. When a moving head is suddenly decelerated, as in a fall, though there might still be a ‘coup’ lesion at the site of impact, there is often cortical damage on the opposite side of the brain – the ‘contrecoup’ lesion.

The mechanism of the ‘coup’ and ‘contrecoup’ injuries has long been debated – at least since the time of the famous Paris meeting of 1766. The controversy has been continued, especially by Courville (1942) and by Holbourn (1943), but no satisfactory resolution has been agreed though the work on intracranial pressures by Yanagida *et al.* seems to provide proof that a ‘vacuum’ occurs at the contrecoup site.

The following practical points should be considered:

- There may be no coup damage at all, only contrecoup.
- There need be no fracture of skull, even in the presence of severe coup and contrecoup lesions.
- The most common site for contrecoup injury is in the frontal and temporal lobes. It is often at the tips and on the undersurface of these lobes, and may be symmetrical, if a fall on the occiput has occurred.
- In temporal or parietal impacts, the contrecoup lesions are likely to be diametrically opposite on the


Scalp injury
(fracture) –
brain damage
(a)
May suffer
secondary fracture
Temporal and
frontal contusion
Scalp injury
(fracture)
(b)

FIGURE 5.42 *(a) 'Coup' brain damage to fixed head. (b) 'Contrecoup' brain damage to moving (decelerated) head.*



FIGURE 5.43 *(a) Typical contrecoup injury to the tips of the frontal and temporal lobes of a brain. The victim was pushed over in a brawl and fell backwards, striking his occiput and causing a small scalp laceration (b). There was no contusion to the posterior part of the brain.*

contralateral surface of the brain, but exact geometrical correspondence is not necessarily present.

- It is virtually unknown for a fall on the frontal region to produce occipital contrecoup. This is thought to be due to the anatomical configuration of the floor of the cranium, but the reasons are by no means understood.
- In a temporal impact, the contrecoup damage may be not be on the contralateral hemisphere, but on the opposite side of the ipsilateral hemisphere from impact against the falx cerebri.
- The degree of contrecoup damage may be severe, sufficient to cause blood-filled cavitation in the deep cortex and underlying white matter, especially in the frontal lobes and tips of the temporal lobes.

- With severe frontal contrecoup from a fall on the occiput, the transmitted force may be sufficient to fracture the thin bone of the floor of the anterior fossa. Such cracks in the roofs of the orbits may allow meningeal haemorrhage to seep into the orbits and appear as 'black eyes'. In assaults where a fall has occurred, care must be taken not to attribute such periorbital bleeding to direct punches.
- Though contrecoup contusion is classically caused by deceleration of a falling head, it can also occur when a **fixed** head is struck. If the victim is already lying on the ground or against some other unyielding surface, a heavy blow on the upper side may cause typical contrecoup lesions either in the contralateral temporal or parietal cortex, or against the falx on the inner side of the ipsilateral lobe. In these circumstances, there is often coup damage as well. No external scalp injury need be visible.
- The interpretation of contrecoup lesions is most reliable in the form of cortical contusions or lacerations. Meningeal haemorrhage, either subdural or subarachnoid, may also arise in association with a contrecoup lesion, but its diagnostic value is virtually nil compared with cortical damage when interpreting a falling or fixed head injury. Where no associated cortical contusion is present, it is quite unsafe to rely upon a unilateral meningeal haemorrhage as an indicator of the type of head injury.

Concussion

Concussion is a clinical, not a pathological entity, but the pathologist must consider it, as it is related to intracranial lesions and he is often questioned about it in court proceedings. Concussion, according to Wilson (1946), is 'a disorder of cerebral function which follows immediately upon the impact of a force to the head'. A more full definition is offered by Trotter (1914): 'a transient paralytic state due to head injury which is of instantaneous onset, does not show any evidence of structural cerebral injury and is always followed by amnesia from the actual moment of the accident'.

Some neurologists would also include post-concussion symptoms within the definition of concussion, even in the absence of initial coma, following a head injury. There may also be evidence of depressed medullary function, which can affect cardiorespiratory action. Denny-Brown and Russell (1941) showed that the rate of change of velocity of the head was important in producing concussion, which rarely developed if the speed threshold was less than ~8.5 m/s (28 ft/s).

It is an extremely common, but not inevitable, sequel to any significant mechanical insult to the brain. Though in general terms its duration is loosely related to the severity of the injury, there are many exceptions. Gross skull and brain damage have occurred with little or no apparent concussion, though concussion may be so transient that the subject may not even fall to the ground. Relatively minor head injuries have given rise to prolonged unconsciousness so, once again, it is most unwise to be dogmatic about retrospective estimates of concussion.

There is considerable controversy about the cause of concussion, from the unacceptable 'traumatic neurosis' on the one hand (which cannot be true) to claims for the inevitable demonstration of physical lesions on the other.

Courville (1953) has discussed the condition in depth and there seems to be no reason to doubt that some mechanical process does temporarily disrupt the function, if not necessarily the structure, of the neuronic apparatus. Changes in the nucleus and cytoplasm of neurones, the composition of the cerebrospinal fluid and in the electroencephalograph have all been inconstantly reported (see 'Diffuse neuronal and axonal injury' below).

True concussion may last for seconds or minutes. If prolonged unconsciousness extends into hours, days or longer, then there is likely to be some structural brain damage. Occasionally what appears to be simple concussion proves to be fatal, causing respiratory paralysis, though at autopsy no significant lesions are found.

Where a victim of 'simple' concussion dies of some incidental non-neurological condition, autopsy usually reveals no macroscopic damage, though sometimes there is slight cerebral oedema and scattered non-specific petechial haemorrhages may be found. There seems to be a connection between concussion and rotatory movements of the head, which are usually responsible for obvious structural damage because, when a head is fixed before impact, loss of consciousness may not occur. The classic example is trapping of a head against a wall or being jammed between buffers.

That shear stresses are instrumental in causing neurone damage seems confirmed by the frequency in which concussion occurs in boxing contests, where a blow on the jaw is the ultimate in producing a rotational movement of the cranium.

Concussion may be followed by a 'post-concussion state' characterized by headaches, unsteadiness and anxiety. This seems a genuine phenomenon, though it has been pointed out that it may be overlain by a 'compensation syndrome' whilst civil litigation is in progress over responsibility for the accident, which often clears up rapidly once the claim is settled.

Retrograde amnesia is almost inevitably associated with concussion, though, like concussion itself, it may be so transient as to escape notice. A protective mechanism, it seems to be caused by loss of sensory input before the latter is transferred to permanent memory storage in the brain.

Though commonly only of minutes' duration, it can extend to several days before the head injury. Though there is often a later recovery of much of this lost period, the memory of events immediately before the incident rarely returns, which may fortuitously be a protective device. Concussion has been attributed to several causes, including the undoubted vasomotor disturbances that take place after a head injury. Another theory is the impaction of the brain into the foramen magnum or tentorial opening, but the most acceptable hypothesis is 'diffuse neuronal injury'.

DIFFUSE NEURONAL AND AXONAL INJURY

According to Graham *et al.* (2002), diffuse brain damage exists in four principal forms: diffuse vascular injury, diffuse axonal injury, hypoxic brain damage and diffuse brain swelling. Diffuse vascular injury consists of multiple small haemorrhages throughout the brain and is virtually restricted to patients, who die within 24 h, whereas the latter three are encountered in patients who survive long enough to reach the hospital. Recent research and new immunohistochemical methods have shown that traumatic axonal injury is much more common than previously realized, and that axons can also be diffusely damaged by other processes than head injury. Therefore, Geddes *et al.* (2000) suggested new definitions of the terminology to get rid of the incoherent use of terms in the literature:

- Axonal injury (AI) is a non-specific term referring to damage to axons of any aetiology.
- Traumatic axonal injury (TAI), is a damage to axons caused by trauma, which may vary from small foci of axons to more widespread brain damage, diffuse TAI is the most severe form of traumatic axonal damage (originally termed 'DAI').
- Diffuse axonal damage (DAI), first described as a clinicopathological syndrome of widespread axonal damage throughout the brain, including the brainstem, should not be used as a term without reference to the aetiology, because axonal injury may be caused by other pathological processes.

Experimental work has suggested that diffuse axonal injury is primarily a non-impact rotational acceleration–deceleration phenomenon, deformation by stretching probably being the most significant factor. A low level of injury causes transient changes in the permeability of the axolemma, gradually leading to ionic changes, accumulation of fluid and axonal swelling and eventually, with an increasing grade of injury, to intracellular Ca^{2+} accumulation, proteolysis and collapse of the cytoskeleton.

The disruption of axons leads to bulbous and clubbed 'retraction balls or globes' on the axons in the cerebral hemispheres, cerebellum and brainstem. Disturbance of axonal transport causes accumulation of substances in damaged fibres, that can be demonstrated immunohistochemically. At present, β-amyloid precursor protein (βAPP) is considered to be the most reliable indicator of axonal damage, revealing axonal injury within 2–3 hours of the insult, whereas it takes about 12–18 hours for axonal bulbs to become visible on routine or silver stains. However, one should keep in mind that βAPP is not specific to head injury but is an indicator of derangement of fast axonal transport, which has also been demonstrated in other pathological conditions.

It is preferable to examine the brain after proper fixation, usually after 10–14 days in 4 per cent buffered formaldehyde and, where possible, consultation with a neuropathologist with experience in forensic practice. Due to the diffuse nature of the axonal injury, extensive and systematic sampling is essential, as the diagnostic yield is directly related to the number of blocks taken. In addition to any obvious focal pathology, the minumum set of samples should include corpus callosum and parasagittal posterior frontal white matter, splenium of the corpus callosum, deep grey matter to include posterior limb of the internal capsule, cerebellar hemisphere, midbrain including the decussation of superior cerebellar peduncle, and pons including superior or middle cerebellar peduncles. In addition to these, it may also be advisable to include corpus callosum and parasagittal anterior frontal white matter and temporal lobe including hippocampus (Geddes *et al.* 2000).

Retraction globes are most numerous in the corpus callosum, the superior peduncles, the parasagittal white matter, the medial lemnisci and the corticospinal tracts, but can be seen anywhere in the white matter. The retraction globes or axonal bulbs have been shown to lose positive staining for βAPP after about a week but to persist in adjacent varicose axons up to 30 days. After some weeks in those who survive long enough, clusters of microglia, presumably part of a repair process, congregate at the site of ruptured axons. These are best seen in 20 μm thicker sections stained with cresyl violet. One problem with the microscopic evidence of both microglial clusters as well as diffuse axonal injury (as demonstrated by βAPP expression), is that neither of them is specific as a marker for trauma: retraction globes may also be seen around the periphery of natural lesions such as cerebral infarcts and haemorrhages and microglial clusters have been reported in viral/HIV encephalitis, previous global hypoxia and fat embolism. Geddes *et al.* (2000) conclude in their excellent review that 'the demonstration of traumatic axonal damage is likely to be of limited use in most forensic situations, except perhaps to confirm that there has been a head injury'.


Normal
Oedematous
Normal weight (<1500g)
Palpable sulci
Rounded gyri
Normal hippocampal gyrus and uncus
Normal cerebellar tonsil
Increased weight (>1500g)
Flattened gyri
Filled sulci
Grooved uncus, Swollen hipocampal gyrus
Herniated cerebellar tonsil
Midline shift if oedema is unilateral

FIGURE 5.44 *Signs of cerebral oedema.*

Cerebral oedema

Swelling of the brain tissue may be a local phenomenon around almost any lesion, be it contusion, laceration, tumour or infarct, but here we are more concerned with generalized oedema. Swelling of the brain is extremely common after a substantial head injury, especially in children. Though it is an almost inevitable accompaniment of almost all intracerebral damage as either a local or general phenomenon, it can occur as the sole abnormality – and not infrequently prove fatal, particularly in young victims.

Oedema may well be related to diffuse neuronal injury and to concussion itself. It is the most common cause of raised intracranial pressure, being seen more often than localized space-occupying lesions such as haematomas and tumours, though of course these often coexist with cerebral oedema.

As with concussion, its cause is obscure and hence is the source of considerable controversy. The amount of fluid in the brain increases and the total weight may increase by at least 100 grams, mainly in the white matter. The site of the excess fluid is obscure, as the cut brain surface does not appear wet as do connective tissues elsewhere in an oedematous body. It was formerly thought that there was no true extracellular space in neural tissue and that the fluid must therefore be intracellular, but electron microscopic studies have revealed an extracellular compartment, which is much wider in the white matter (up to 80 nm) than in the grey matter (up to 20 nm), which explains the preference of oedema for the white matter.

The autopsy features of cerebral oedema are readily recognized. On removing the calvarium, the dura is stretched and tense, the brain bulging through the first incision in the membrane. The gyri are pale and flattened, and the sulci filled, giving the normally corrugated cerebral surface a smoothness that can easily be felt at autopsy. The cut surface is pale and, especially in children, the ventricles may be reduced to slits by the swelling of the adjacent white matter.

Severe cerebral oedema causes the larger volume cerebral hemispheres to press down upon the tentorium and herniate through the midbrain opening. The hippocampal gyrus may impact in the opening, lesser degrees causing grooving of the unci. Both these effects may lead to haemorrhage and necrosis at the sites of pressure, especially where the sharp edge of the tentorium cuts into the cerebral tissue. The tonsils of the cerebellum may be impacted or 'coned' into the foramen magnum, and sometimes are forced down into the upper part of the spinal canal. The pathologist must be careful not to mistake the normal anatomical grooving that often exists around the cerebellar tonsils for 'coning'. There should be other signs of brain swelling and true tonsillar herniation will show discoloration or even necrosis of the ischaemic, trapped tissue.

Cerebral oedema may be the only intracranial abnormality found at autopsy after a substantial head injury has occurred. This seems to be more commonly found in children and, in the absence of any other demonstrable lesions, the cause of death has to be attributed to this swelling of the brain, compressing the vital centres in the brainstem.



FIGURE 5.45 *Tonsillar herniation as a consequence of lumbar puncture in a patient with increased intracranial pressure. The pressure gradient has forced the cerebellar tonsils into foramen magnum and caused compression of the brainstem and patient's death. (Reproduced by kind permission of Professor H Kalimo.)*

Obviously, many other cases of cerebral oedema resolve either spontaneously or with treatment, so that fortunately no opportunity arises to prove its existence by post-mortem examination. Such oedema is, however, not infrequently found during surgical exploration for a meningeal haemorrhage, the latter sometimes being presented though often only brain swelling is demonstrated.

Cerebral oedema may be self-potentiating, in that once it begins as a result of direct brain trauma, the consequent rise in intracranial pressure then impairs the venous return from the intracranial sinuses. The pressure is insufficient to restrict the arterial inflow, so further congestion and swelling occur. This may lead to worsening cerebral hypoxia and oedema to the stage of actual cerebral infarction and brain death – again, a distressing common syndrome seen especially in child victims of head injuries, usually from road accidents.

In addition to mechanical damage, cerebral oedema can be caused or worsened by hypoxia. Many head injuries may be associated with damage to other parts of the body, such as the thorax – and because the airway may be compromised in many unconscious victims, there may be an element of hypoxia in a considerable proportion of cases of cerebral oedema. Capillary permeability may be increased in a number of states, leading to weakening of the so-called 'blood–brain barrier' formed by the capillary endothelium and basement membrane, together with the astrocyte footplates. Cerebral oedema, either traumatic or hypoxic, can develop with surprising rapidity, especially in children. Macroscopic evidence of brain swelling can be seen at autopsy in cases where the interval between trauma or onset of hypoxia and death was less than one hour.

Several methods are available to reverse oedema, including hyperventilation, which acts by providing full oxygenation and reducing the peripheral carbon dioxide tension, thus causing constriction of arterioles and a reduction in brain volume and transudation.

HISTOLOGICAL DIAGNOSIS OF EARLY CEREBRAL HYPOXIA

Unfortunately for the pathologist, most of the hypoxic conditions seen in forensic practice cause death too quickly for any recognizable histological changes to develop. Acute deaths from strangulation, suffocation and choking occur within minutes or less, even excepting the sudden vasovagal type of cardiac arrest.

There are, however, occasions when a longer period of survival occurs after an acute hypoxic episode and in some of these there may be the opportunity to detect histological changes in the central nervous system. Probably a minimum of 2–4 hours of survival is necessary for unequivocal changes to be observed, though some neuropathologists claim to detect signs after as little as 1 hour. More cautious investigators prefer 4 hours as the minimum. A short post-mortem interval is a considerable advantage in searching for these changes, as they are subtle and can be overlaid by post-mortem autolysis, even if the latter is slight.

It may be helpful to seek the assistance of a neuropathologist in detecting or confirming the relatively minor changes seen in a brain affected by hypoxia, but with experience, a good knowledge of the normal appearances and a laboratory that is able to turn out constantly good-quality sections and uniform staining, any forensic pathologist can build up a considerable expertise in this localized aspect of neuropathology. The parts of the brain most suitable for seeking evidence of hypoxic damage are the hippocampus (especially Sommer's area), the cerebellar folia, the globus pallidus in the basal ganglia, and the boundary zones of the cerebral cortex where the grey matter is most vulnerable because it lies at the terminal reaches of the arterial supply (for example, at the occipitotemporal junction where the watershed between middle and posterior cerebral arteries lies). The third and fourth cortical layers are best for displaying the histological changes of hypoxia.

The following is a summary of the stages and changes that may be seen using different staining methods. The brain should be prefixed by suspension in formol saline for several weeks, though if this is impossible, small blocks should be wet-cut from the target areas of the brain mentioned above and immediately fixed in a large volume of formalin.

Stage 1

The earliest change is microvacuolation in the neurone cytoplasm, which may be seen in 2–4 hours. The cell outline remains smooth and its size is normal but, internally, small vacuoles appear in the cell body, and the proximal parts of the axon and dendrites. There may be a slight eosinophilia in haematoxylin and eosin stains and a violet colour in Luxol Fast Blue.

The microvacuolar change is said to begin earlier in small neurones and last for a shorter time, being present for up to 4–6 hours after insult in large cells and 2–4 hours in cerebellar Purkinje cells, though these times are arbitrary.

Stage 2

In the next stage, more prolonged hypoxia causes distortion in the shape of the neurones, the cell body becoming shrunken and staining darker with aniline dyes. The Nissl granules become fine and are dispersed more widely throughout the cell. Some vacuoles remain, the cytoplasm shows marked eosinophilia in haematoxylin and eosin, and is bright blue to mauve in Luxol Fast Blue stain. The nucleus becomes triangular and may be placed eccentrically in the cell body. The nucleolus becomes obscured and the nucleus stains a darker blue than normal with Luxol Fast Blue. This change is seen after up to 6 hours survival or later in large cells.

Stage 3

The ischaemic cell stage, described last, becomes worse during the following day or two if survival continues. The cell shrinks further, becoming narrow and tapered in many cases. Eosinophilia and blueness when stained with Luxol Fast Blue persists, but small spherical or irregular bodies begin to adhere to the exterior of the cell membrane. These incrustations persist longer than the remnants of the cytoplasm, which vanish, leaving the bare nucleus. The dark, shrunken nucleus becomes more apparent and survives for a number of days before karyolysis occurs.

Stage 4

Homogenizing cell damage is best seen in the Purkinje cells, in which the cytoplasm is uniformly eosinophilic with no Nissl granules. The nucleus stays dark and triangular until it vanishes and leaves a pale 'ghost' of the cell body with a vague perimeter.

There are parallel changes in the glial elements as well as in the neurones. From 4 to 12 hours after a hypoxic insult there may be an increase in the number of astrocytes around damaged neurones. There is a proliferation of astrocytes (which show mitoses) some 4–6 days later if the patient survives. This is most noticeable in the cerebellum and persists for 10–14 days. Fibrous astrocytes proliferate, but not the oligodendroglia. Microglia transform into rod cells, which may lie at right angles to the edge of the cortex, radially in the hippocampus and in the molecular layer of the cerebellar cortex. A later stage of cerebral hypoxic damage is the accumulation of lipid droplets and scavenging of myelin. Groups of microglia around dead neurones (neuronophages) may be obvious even at lower powers of the microscope.

SECONDARY BRAINSTEM LESIONS

When severe brain swelling (or a space-occupying lesion such as a large subdural or extradural haematoma) causes raised intracranial pressure above the tentorium, amongst the possible sequelae is compression of the midbrain against the free edge of the tentorium. This may be unilateral, causing grooving of a cerebral peduncle (called 'Kernohan's notch') associated with subpial petechial haemorrhages and often hemiplegia. When symmetrical, the oedema forces the undersurface of the cerebrum against the tentorium so that the hippocampal gyrus is squeezed into the opening. This elongates the midbrain in an anteroposterior direction as well as grooving the uncus and, in extreme cases, infarcting part of the parahippocampal gyrus. In addition, the distortion stretches, and compresses the paramedian and nigral vessels that supply the midbrain, leading to haemorrhages and infarcts in the upper pons and midbrain. Damage to cranial nerves and to the circulation of the cerebrospinal fluid may be added complications. The calcarine cortex on the medial aspect of the occipital lobe may be infarcted by the posterior cerebral artery being trapped around the edge of the tentorium by the cerebral herniation.

Secondary lesions are almost exclusively midline or paramedian haemorrhages, or haemorrhagic necrosis placed centrally in the upper pons and midbrain, though some may be obliquely placed in the substantia nigra. They may be difficult to distinguish from primary brainstem haemorrhages that arise at or soon after the original head injury – the secondary lesions tend to obscure the primary, rather than the converse. In children, the typical stem haemorrhages may not be present as in adults, but instead the medulla oblongata may be buckled or kinked due to fixation of the upper spinal cord by the denticulate ligaments (see work by Crompton).

SPINAL INJURIES

The spine and head should be thought of as part of the same system in relation to trauma. In recent years, a closer association – both skeletal and neurological – has been acknowledged between the two structures. For instance, interruption of ascending fibres in the cervical cord has been shown to be associated with neuronal chromatolysis in the brainstem and Spicer and Strich have shown that haemorrhage into spinal root ganglia may be associated with head injury. Electroencephalographic changes have been shown to occur in half the victims of cervical spine whiplash injury.

Though all segments of the spine are vulnerable to trauma, the cervical part holds the most interest for the forensic pathologist, mainly because of its close association with head injuries and vehicular accidents. The upper two cervical vertebrae provide most of the rotational movement of the head, whilst the lower neck allows flexion and extension. Violent force applied to the head tends to damage those parts of the neck corresponding with this functional distinction. Spinal damage may be caused by compressional, hyperflexion and hyperextension stress.

Compression damage

This occurs when the victim falls from a height either onto his feet or his head, though in the latter case, head injuries may overshadow damage to the spine, as well as absorbing most of the impact.

When a person falls a long distance onto the feet, the kinetic energy of the deceleration may be absorbed by fractures of the feet, legs and pelvis, but can be transmitted up the spinal column. This can be fractured at one or more points, or the force may cause the upper cervical spine to impinge on the base of the skull and cause a 'ring fracture' around the foramen magnum as the spine is rammed into the posterior fossa.

A fall onto the head may also cause the 'burst atlas' injury, where the impact of the occipital condyles in an axial direction wedge the superior atlantal articulating facets apart and split the ring of the vertebra. The posterior arch can also be fractured in hyperextension by compression between the occiput and the posterior spine of the axis.

Compression fractures of vertebral bodies may occur, most commonly in the lower dorsal and upper lumbar zone, particularly T12 and L1. There is less chance of spinal cord injury compared with the angulation injuries described below, unless posterior extrusion of a disc or backward displacement of fragments of a disrupted vertebral body occurs.

Hyperflexion and hyperextension injury

Of the two, hyperextension is much more dangerous in causing spinal damage, possibly because flexion is protected by contraction of the strong posterior neck muscles, whereas the weak anterior longitudinal ligament is incapable of preserving the integrity of the cervical spine during hyperextension. In frontal or rearward motor vehicle crashes, which comprise 80 per cent of accidents, there is usually a hyperflexion and hyperextension component to the spines of the occupants, though head restraints and seatbelts restrict the range of movement.

Where a car undergoes violent frontal deceleration, the subject's head will swing down into hyperflexion and, unless restrained, will then strike the fascia or windscreen, and rebound into hyperextension.

When the vehicle is struck from the rear, the head will fly into hyperextension first unless a head-rest is available; such collisions often then smash the vehicle into the one in front, when a deceleration hyperflexion takes place.

Whatever the cause, a whole range of lesions can follow, both in the cervical, and to a lesser extent into the thoracic and lumbar segments. Bleeding into the surrounding muscles,



FIGURE 5.46 *Crushing of a thoracic vertebral body with disintegration of the adjacent disc following a violent hyperflexion in a car driver sustaining a deceleration injury. These lesions are best displayed at autopsy by cutting a longitudinal slice down the anterior aspect of the spinal column with an electric saw.*

rupture of the anterior longitudinal ligament, and tearing of intervertebral discs and of the annulus fibrosus may occur.

Nerve roots may be torn or compressed, and the spinal canal may be narrowed, distorted or even almost obliterated by fracture dislocations of the vertebrae. Compression, ischaemia, haemorrhage and even pulping of the spinal cord is the most serious complication. In older persons with cervical spondylosis, further narrowing of the canal by trauma may cause neurological effects that would not occur in younger subjects.

The most common part of the spine to be injured is the region of the upper two cervical vertebrae. In a series of fatal motor car accidents reported by Mant (1978), 35 per cent of passengers and 30 per cent of drivers suffered cervical spine damage. Of these the most common was a dislocation of the atlanto-occipital joint and Mant claims that one-third of all victims of fatal motor vehicle accidents suffer this lesion, even though it is often undetected at autopsy. The mechanism of fracture of the atlas is said to be an axial impact via the head, when the occiput is held rigidly in line with the spine by contracted neck muscles. This most frequently occurs when the vertex of the lowered head violently strikes the windshield of a decelerating vehicle. Fracture or dislocation of the atlas or fracture of the odontoid of the axis can all occur from this type of impact. Hyperextension injuries tend to force the vertebral body forwards and, if there is significant displacement, the arch is intruded into the spinal canal with the consequent risk of cord damage. In addition, hyperextension – especially in the presence of cervical cord enlargement – can cause the ligamentum flavum to corrugate and intrude into the anterior part of the spinal canal to impinge upon the cord. When the injury is due to hyperflexion, dislocation of a vertebra causes it (or its fragments) to tilt backwards, again compromising the lumen of the spinal canal.

Dislocation of cervical vertebra can occur under many conditions. An anterior dislocation can be caused by a fall onto the back of the head and a unilateral dislocation is common when a head strikes a windscreen. Posterior dislocation may be caused by blows to the jaw or face that jolt the head backwards with a hyperextension element. Falling onto the face, especially from a height (such as down a staircase), is a likely cause. Fracture of the odontoid peg of the axis can occur from a variety of violent movements of the head on the neck, and is sometimes associated with fracture of the skull or mandible. Where gross injury to the spinal column is inflicted – such as a relatively high-speed motor vehicle or railway accident – the cord may be transected by a guillotine action of the two displaced fragments. This is most often seen on the upper or mid-thoracic region, from direct impact or gross 'whiplash' effects. The thoracic aorta at this level is often torn at the point where the descending arch meets the spine, even in the absence of a spinal fracture.

Damage to the cervical spine in hanging is rarely seen in the usual suicidal hangings in which sudden death is caused by carotid compression or – much less often – asphyxia. The drop in such cases is small or even absent, the subject merely slumping his weight against the neck restraint. Spinal damage can occasionally occur, however and the author has seen a fractured neck when a heavily built soldier stepped from a lavatory seat with the rope attached to the overhead cistern.

Judicial hanging with a long drop causes a severe fracture dislocation (rather than fracture) of the cervical spine, often with complete severance of the two fragments and transection of the spinal cord. Where such hanging is carried out with the knot of the suspension point beneath the chin, a violent hyperextension is produced that often fractures the axis and dislocates it from the third cervical vertebra. With a heavy person and a long drop, there may be complete decapitation.



FIGURE 5.47 *Crushing and transection of the lower spinal cord following a hyperflexion fracture of the lower thoracic vertebrae. The spinal cord ends at about the lower border of the first lumbar vertebra, the cauda equina occupying the remainder of the lumbar spinal canal. This injury occurred several years before death, and the dura is constricted and adherent to the remnants of the cord. At autopsy the cord and its membranes should be pinned out and fixed for a proper examination to be made.*

Spinal cord injury

Most damage to the spinal cord arises from intrusion of some part of the spinal column into the canal, be it bony fragments or displacement, ligamentum flavum, disc annulus or extruded nucleus pulposum.

There may be bleeding into the space outside the spinal dura causing a space-occupying lesion in the canal that can compress the cord, or bleeding may occur within the dura, either from ruptured vessels or from haemorrhage in the cord itself. Damage to the cord may also occur in the absence of any apparent intrusion into the canal, in a manner similar to that seen in the brain in closed head injuries without a fracture. Haematomyelia and oedema may develop without any obvious mechanical defect at that level in the spinal column. Such injuries must be attributed to some momentary collision of the cord against the wall of the canal or a transient deformity of the profile of the canal that did not exceed the threshold for either fracture, dislocation or ligament rupture of the vertebral column.

The damage in the cord may extend for several segments above and below the point of impact. A haemorrhage within the cord tends to occupy the central grey matter more than the white columns, because of the softer and more vascular nature of the former tissue. Infarction of the cord can occur either in association with contusion, or because the local blood supply – often the anterior spinal artery – has been damaged.

An originally firm cord may undergo liquefaction (‘myelomalacia’) over several days or even longer, with progressive worsening of neurological symptoms.

REFERENCES AND FURTHER READING

Adams JH. 1982. Diffuse axonal injury in non-missile head injury. *Injury* **13**:444–5.

Adams H, Mitchell DE, Graham DI, *et al.* 1977. Diffuse brain damage of immediate impact type. Its relationship to ‘primary brain-stem damage’ in head injury. *Brain* **100**:489–502.

Adams JH, Graham DI, Murray LS, *et al.* 1982. Diffuse axonal injury due to nonmissile head injury in humans: an analysis of 45 cases. *Ann Neurol* **12**:557–63.

Adams JH, Graham DI, Gennarelli TA. 1983. Head injury in man and experimental animals: Neuropathology. *Acta Neurochir Suppl (Wien)* **32**:15–30.

Adams JH, Doyle D, Graham DI, *et al.* 1984. Diffuse axonal injury in head injuries caused by a fall. *Lancet* **2**:1420–2.

Adams JH, Doyle D, Graham DI, *et al.* 1985. Microscopic diffuse axonal injury in cases of head injury. *Med Sci Law* **25**:265–9.

Adams JH, Doyle D, Graham DI, *et al.* 1985. The contusion index: a reappraisal in human and experimental non-missile head injury. *Neuropathol Appl Neurobiol* **11**:299–308.

Adams JH, Doyle D, Graham DI, *et al.* 1986. Gliding contusions in nonmissile head injury in humans [published erratum appears in *Arch Pathol Lab Med* 1986 Nov;**110**:1075]. *Arch Pathol Lab Med* **110**:485–8.

Adams JH, Doyle D, Graham DI, *et al.* 1986. Deep intracerebral (basal ganglia) haematomas in fatal non-missile head injury in man. *J Neurol Neurosurg Psychiatry* **49**:1039–43.

Adams JH, Doyle D, Ford I, *et al.* 1989. Diffuse axonal injury in head injury: definition, diagnosis and grading. *Histopathology* **15**:49–59.

Adams JH, Doyle D, Ford I, *et al.* 1989. Brain damage in fatal non-missile head injury in relation to age and type of injury. *Scott Med J* **34**:399–401.

Adams JH, Graham DI, Gennarelli TA, *et al.* 1991. Diffuse axonal injury in non-missile head injury. *J Neurol Neurosurg Psychiatry* **54**:481–3.

Adams JH, Corsellis JA, Duchen LW. 1992. *Greenfield's neuropathology*, 5th edn. Edward Arnold, London.

Adams JH, Jennett B, McLellan DR, *et al.* 1999. The neuropathology of the vegetative state after head injury. *J Clin Pathol* **52**:804–6.

Adams JH, Graham DI, Jennett B. 2000. The neuropathology of the vegetative state after an acute brain insult. *Brain* **123**(Pt 7):1327–38.

Adams JH, Graham DI, Jennett B. 2001. The structural basis of moderate disability after traumatic brain damage. *J Neurol Neurosurg Psychiatry* **71**:521–4.

Adelson L. 1974. *The pathology of homicide*. Thomas, Springfield.

Blumbergs PC, Jones NR, North JB. 1989. Diffuse axonal injury in head trauma. *J Neurol Neurosurg Psychiatry* **52**:838–41.

Bostrom K, Helander CG, Lindgren SO. 1992. Blunt basal head trauma: rupture of posterior inferior cerebellar artery. *Forensic Sci Int* **53**:61–8.

Bromilow A, Burns J. 1985. Technique for removal of the vertebral arteries. *J Clin Pathol* **38**:1400–2.

Caffey J. 1946. Multiple fractures in the long bones of infants suffering from chronic subdural haematoma. *Am J Radiol* **56**:163–73.

Cameron JM, Mant AK. 1972. Fatal subarachnoid haemorrhage associated with cervical trauma. *Med Sci Law* **12**:66–70.

Casson IR, Siegel O, Sham R, *et al.* 1984. Brain damage in modern boxers. *JAMA* **251**:2663–7.

Coast GC, Gee DJ. 1984. Traumatic subarachnoid haemorrhage: an alternative source. *J Clin Pathol* **37**:1245–8.

Contostavlos DL. 1971. Massive subarachnoid hemorrhage due to laceration of the vertebral artery associated with fracture of the transverse process of the atlas. *J Forensic Sci* **16**:40–56.

Contostavlos DL. 1995. Isolated basilar traumatic subarachnoid hemorrhage: an observer's 25 year re-evaluation of the pathogenetic possibilities. [letter; comment] *Forensic Sci Int* **73**:61–74.

Corsellis JA, Bruton CJ, Freeman Browne D. 1973. The aftermath of boxing. *Psychol Med* **3**:270–303.

Courville CB. 1942. Coup-contre coup mechanism of craniocerebral injuries: some observations. *Arch Surg* **45**:19–43.

Courville CB. 1953. *Commotio cerebri*. San Lucas Press, Los Angeles.

Courville CB. 1964. *Forensic neuropathology*. Callaghan and Co, Mundelein.

Critchley M. 1957. Medical aspects of boxing particularly from a neurological standpoint. *Br Med J* **1**:357–62.

Crompton MR. 1971. Brain stem lesions due to closed head injury. *Lancet* **1**:669–71.

Crompton R. 1985. *Closed head injuries*. Edward Arnold, London.

Dalgaard J. 1957. Brain injuries as a cause of oesophagogastroduodenal ulceration. *J Forensic Med* **4**:110–27.

Dawson SL, Hirsch CS, Lucas FV, *et al.* 1980. The contrecoup phenomenon. Reappraisal of a classic problem. *Hum Pathol* **11**:155–66.

Deck JH, Jagadha V. 1986. Fatal subarachnoid hemorrhage due to traumatic rupture of the vertebral artery. *Arch Pathol Lab Med* **110**:489–93.

Denny-Brown D. 1945. Cerebral concussion. *Physiol Rev* **25**:296–325.

Denny-Brown D, Russell WR. 1941. Experimental cerebral concussion. *Brain* **64**:93–164.

Dowling G, Curry B. 1988. Traumatic basal subarachnoid hemorrhage. Report of six cases and review of the literature. *Am J Forensic Med Pathol* **9**:23–31.

Duhaime AC, Gennarelli TA, Thibault LE, *et al.* 1987. The shaken baby syndrome. A clinical, pathological, and biomechanical study. *J Neurosurg* **66**:409–15.

Duhaime AC, Alario AJ, Lewander WJ, *et al.* 1992. Head injury in very young children: mechanisms, injury types, and ophthalmologic findings in 100 hospitalized patients younger than 2 years of age. *Pediatrics* **90**:179–85.

Edherg S, Angrist A. 1967. Intra-cranial pressure changes following impact of human cadaver heads. *J Forensic Sci* **12**:60–8.

Editorial. 1973. Boxing brains. *Lancet* **2**:1064–5.

Farag AM, Franks A, Gee DJ. 1988. Simple laboratory experiments to replicate some of the stresses on vertebro-basilar arterial walls. An investigation of possible mechanisms of traumatic subarachnoid haemorrhage. *Forensic Sci Int* **38**:275–84.

Fell DA, Fitzgerald S, Moiel RH, *et al.* 1975. Acute subdural hematomas. Review of 144 cases. *J Neurosurg* **42**:37–42.

Flamm ES, Demopoulos HB, Seligman ML, *et al.* 1977. Ethanol potentiation of central nervous system trauma. *J Neurosurg* **46**:328–35.

Ford R. 1956. Basal subarachnoid haemorrhage and trauma. *J Forensic Sci* **1**:117–26.

Freytag E. 1963. Autopsy findings in head injuries from blunt forces: statistical evaluation of 1367 cases. *Arch Pathol* **75**:74–80.

Garfield J. 2002. Acute subdural haematoma in a boxer. *Br J Neurosurg* **16**:96–9; discussion 99–101.

Geddes JF, Whitwell HL, Graham DI. 2000. Traumatic axonal injury: practical issues for diagnosis in medicolegal cases. *Neuropathol Appl Neurobiol* **26**:105–16.

Geddes JF, Hackshaw AK, Vowles GH, *et al.* 2001. Neuropathology of inflicted head injury in children. I. Patterns of brain damage. *Brain* **124**:1290–8.

Geddes JF, Vowles GH, Hackshaw AK, *et al.* 2001. Neuropathology of inflicted head injury in children. II. Microscopic brain injury in infants. *Brain* **124**:1299–306.

Gennarelli TA. 1983. Head injury in man and experimental animals: clinical aspects. *Acta Neurochir Suppl (Wien)* **32**:1–13.

Gennarelli TA. 1993. Mechanisms of brain injury. *J Emerg Med* **11**(Suppl 1):5–11.

Gennarelli TA, Graham DI. 1998. Neuropathology of the head injuries. *Semin Clin Neuropsychiatry* **3**:160–175.

Gennarelli TA, Thibault LE. 1982. Biomechanics of acute subdural hematoma. *J Trauma* **22**:680–6.

Gennarelli TA, Thibault LE, Adams JH, *et al.* 1982. Diffuse axonal injury and traumatic coma in the primate. *Ann Neurol* **12**:564–74.

Gennarelli TA, Thibault LE, Tipperman R, *et al.* 1989. Axonal injury in the optic nerve: a model simulating diffuse axonal injury in the brain. *J Neurosurg* **71**:244–53.

Gentleman SM, McKenzie JE, Royston MC, *et al.* 1999. A comparison of manual and semi-automated methods in the assessment of axonal injury. *Neuropathol Appl Neurobiol* **25**:41–7.

Goonetilleke UK. 1980. Injuries caused by falls from heights. *Med Sci Law* **20**:262–75.

Graham DI. 2001. Paediatric head injury. *Brain* **124**:1261–2.

Graham DI, Adams JH. 1971. Ischaemic brain damage in fatal head injuries. *Lancet* **1**:265–6.

Graham DI, Adams JH. 1972. *The pathology of blunt head injuries.* In: Critchley M (ed.), *Scientific foundation of neurology*. Heinemann Medical Publications, London.

Graham DI, Lantos PL (eds). 2002. *Greenfield's neuropathology*, 7th edn. Arnold, London/New York/New Delhi.

Graham DI, McLellan D, Adams JH, *et al.* 1983. The neuropathology of the vegetative state and severe disability after non-missile head injury. *Acta Neurochir Suppl (Wien)* **32**:65–7.

Graham DI, Lawrence AE, Adams JH, *et al.* 1988. Brain damage in fatal non-missile head injury without high intracranial pressure. *J Clin Pathol* **41**:34–7.

Graham DI, Ford I, Adams JH, *et al.* 1989. Fatal head injury in children. *J Clin Pathol* **42**:18–22.

Graham DI, Clark JC, Adams JH, *et al.* 1992. Diffuse axonal injury caused by assault. *J Clin Pathol* **45**:840–1.

Graham DI, McIntosh TK, Maxwell WL, *et al.* 2000. Recent advances in neurotrauma. *J Neuropathol Exp Neurol* **59**:641–51.

Graham DI, Raghupathi R, Saatman KE, *et al.* 2000. Tissue tears in the white matter after lateral fluid percussion brain injury in the rat: Relevance to human brain injury. *Acta Neuropathol (Berl)* **99**:117–24.

Gurdjian ES, Webster JE. 1958. *Head injuries*. Churchill, London, UK.

Gurdjian ES, Webster JE, Lissner HR. 1949. Studies on skull fracture with particular reference to engineering factors. *Am J Surg* **78**:736–42.

Gurdjian ES, Webster JE, Lissner HR. 1950. The mechanism of skull fracture. *Radiology* **54**:313–39.

Harris LS. 1991. Postmortem magnetic resonance images of the injured brain: effective evidence in the courtroom. *Forensic Sci Int* **50**:179–85.

Harwood-Nash CE, Hendrick EB, Hudson AR. 1971. The significance of skull fractures in children. A study of 1,187 patients. *Radiology* **101**:151–6.

Hijdra A, Vermeulen M, van Gijn J, *et al.* 1984. Respiratory arrest in subarachnoid hemorrhage. *Neurology* **34**:1501–3.

Holbourn AH. 1943. Mechanics of head injuries. *Lancet* **245**:438–41.

Huelke DF, O'Day J, Mendelsohn RA. 1981. Cervical injuries suffered in automobile crashes. *J Neurosurg* **54**:316–22.

Imajo T. 1996. Diffuse axonal injury: its mechanism in an assault case. *Am J Forensic Med Pathol* **17**:324–6.

Imajo T, Kazee AM. 1992. Diffuse axonal injury by simple fall. *Am J Forensic Med Pathol* **13**:169–72.

Imajo T, Roessman U. 1984. Diffuse axonal injury. *Am J Forensic Med Pathol* **5**:217–22.

Imajo T, Challener RC, Roessmann U. 1987. Diffuse axonal injury by assault. *Am J Forensic Med Pathol* **8**:217–19.

Jafari SS, Maxwell WL, Neilson M, *et al.* 1997. Axonal cytoskeletal changes after non-disruptive axonal injury. *J Neurocytol* **26**:207–21.

Jafari SS, Nielson M, Graham DI, *et al.* 1998. Axonal cytoskeletal changes after nondisruptive axonal injury. II. Intermediate sized axons. *J Neurotrauma* **15**:955–66.

Jamieson KG, Yelland JD. 1968. Extradural hematoma. Report of 167 cases. *J Neurosurg* **29**:13–23.

Johnson CP, Lawler W, Burns J. 1993. Use of histomorphometry in the assessment of fatal vertebral artery dissection. *J Clin Pathol* **46**:1000–3.

Johnson CP, How T, Scraggs M, *et al.* 1994. The poor biomechanical response of the vertebral artery applied longitudinal force. *J Pathol* **Suppl**:234.

Johnson DL, Boal D, Baule R. 1995. Role of apnea in nonaccidental head injury. *Pediatr Neurosurg* **23**:305–10.

Johnson J. 1969. Organic psychosyndromes due to boxing. *Br J Psychiatry* **115**:45–53.

Johnson P, Burns J. 1995. Extracranial vertebral artery injury – evolution of a pathological illusion? [letter; comment] *Forensic Sci Int* **73**:75–8.

Kaur B, Rutty GN, Timperley WR. 1999. The possible role of hypoxia in the formation of axonal bulbs. *J Clin Pathol* **52**:203–9.

Kerr D. 1954. *Forensic medicine*, 5th edn. A. & C. Black, Edinburgh, p. 114.

Knight B. 1979. Trauma and ruptured cerebral aneurysm. *Br Med J* **1**:1430–1.

Kubo S, Kitamura O, Orihara Y, *et al.* 1998. Immunohistochemical diagnosis and significance of forensic neuropathological changes. *J Med Invest* **44**:109–19.

Leadbeatter S. 1994. Extracranial vertebral artery injury – evolution of a pathological illusion? [see comments] *Forensic Sci Int* **67**:33–40.

Leadbeatter S. 1995. Letter to editor. *Forensic Sci Int* **73**:78–9.

Ledran H. 1751. *Observatis des chirurgies*. Osmont, Paris.

Leestma JE. 1988. *Forensic neuropathology*. Raven Press, New York.

Li L, Smialek JE. 1994. The investigation of fatal falls and jumps from heights in Maryland (1987–1992). *Am J Forensic Med Pathol* **15**:295–9.

Lindenberg R. 1955. Lesions of the corpus callosum following blunt mechanical trauma to the head. *Am J Pathol* **31**:297–301.

Lindenberg R, Freytag E. 1957. Morphology of cerebral contusions. *Arch Pathol* **63**:23–6.

Lindenberg R, Freytag E. 1960. The mechanism of cerebral contusions: a pathologic-anatomic study. *Arch Pathol* **69**:440–4.

Lindenberg R, Freytag E. 1970. Brainstem lesions characteristic of traumatic hyperextension of the head. *Arch Pathol* **90**:509–15.

Lindsay KW, McLatchie G, Jennett B. 1980. Serious head injury in sport. *Br Med J* **281**:789–91.

Lundberg GD. 1985. Brain injury in boxing. *Am J Forensic Med Pathol* **6**:192–8.

Madro R, Chagowski W. 1987. An attempt at objectivity of post mortem diagnostic of brain oedema. *Forensic Sci Int* **35**:125–9.

Maloney AFJ, Whatmore WJ. 1969. Clinical and pathological observations in fatal head injuries: a five year survey of 173 cases. *Br J Surg* **56**:23–30.

Mansell PW, Hunt AC. 1968. Major head injuries in fights and brawls. *Med Sci Law* **8**:181–7.

Mant AK. 1978. Injuries and death in motor vehicle accidents. In: Mason JK (ed.), *Pathology of violent injury*. Edward Arnold, London.

Mant AK. 1993. Injuries and death in motor vehicle accidents. In: Mason JK (ed.), *Pathology of violent injury*, 2nd edn. Edward Arnold, London.

Marek Z. 1981. Isolated subarachnoid hemorrhage as a medicolegal problem. *Am J Forensic Med Pathol* **2**:19–22.

Marlet JM, Barreto Fonseca JdP. 1982. Experimental determination of time of intracranial hemorrhage by spectrophotometric analysis of cerebrospinal fluid. *J Forensic Sci* **27**:880–8.

Martland MS. 1928. Punch drunk. *JAMA* **91**:1003–5.

Mawdsley C, Ferguson SR. 1963. Neurological disease in boxers. *Lancet* **2**:795–7.

McCormick WF. 1980. The relationship of closed-head trauma to rupture of saccular intracranial aneurysms. *Am J Forensic Med Pathol* **1**:223–6.

McCrory P. 2002. Boxing and the brain. Revisiting chronic traumatic encephalopathy. *Br J Sports Med* **36**:2.

McKissock H. 1960. Extradural haemorrhage; observations on 125 cases. *Lancet* **2**:167–74.

Missliwetz J. 1995. Fatal impalement injuries after falls at construction sites. *Am J Forensic Med Pathol* **16**:81–3.

Mitchell DE, Adams JH. 1973. Primary focal impact damage to the brainstem in blunt head injuries. Does it exist? *Lancet* **2**:215–18.

Miyazaki T, Kojima T, Chikasue F, *et al.* 1990. Traumatic rupture of intracranial vertebral artery due to hyperextension of the head: reports on three cases. *Forensic Sci Int* **47**:91–8.

Moar JJ. 1987. Traumatic rupture of the cervical carotid arteries: an autopsy and histopathological study of 200 cases. *Forensic Sci Int* **34**:227–44.

Morgagni J. 1761. *De sedibus et causis morborum per anatomen indagatis.* Typographia Academia, Lovanii.

Moritz AR. 1942. *Pathology of trauma*. Lea & Febiger, Philadelphia.

Munro D. 1938. *Cranio-cerebral injuries*. Oxford University Press, Oxford.

Munro D, Merritt HH. 1936. Surgical pathology of subdural haematoma. Based on a study of 105 cases. *Arch Neurol Psychiatry* **35**:64–78.

Oehmichen M. 1994. Brain death: neuropathological findings and forensic implications. *Forensic Sci Int* **69**:205–19.

Oehmichen M, Raff G. 1980. Timing of cortical contusion. Correlation between histomorphologic alterations and post-traumatic interval. *Z Rechtsmed* **84**:79–94.

Oehmichen M, Eisenmenger W, Raff G, *et al.* 1986. Brain macrophages in human cortical contusions as indicator of survival period. *Forensic Sci Int* **30**:281–301.

Oehmichen M, Meissner C, Schmidt V, *et al.* 1999. Pontine axonal injury after brain trauma and nontraumatic hypoxic-ischemic brain damage. *Int J Legal Med* **112**:261–7.

Oehmichen M, Theuerkauf I, Meissner C. 1999. Is traumatic axonal injury (AE) associated with an early microglial activation? Application of a double-labeling technique for simultaneous detection of microglia and ai. *Acta Neuropathol (Berl)* **97**:491–4.

Oehmichen M, Ochs U, Meissner C. 2000. Histochemical characterization of cytotoxic brain edema. Potassium concentrations after cerebral ischemia and during the postmortem interval. *Exp Toxicol Pathol* **52**:348–52.

Oehmichen M, Meissner C, Konig HG. 2001. Brain injury after survived gunshot to the head: reactive alterations at sites remote from the missile track. *Forensic Sci Int* **115**:189–97.

Oppenheimer DR. 1968. Microscopic lesions in the brain following head injury. *J Neurol Neurosurg Psychiatry* **31**:299–306.

Povlishock JT. 1992. Traumatically induced axonal injury: pathogenesis and pathobiological implications. *Brain Pathol* **2**:1–12.

Povlishock JT. 2000. Pathophysiology of neural injury: therapeutic opportunities and challenges. *Clin Neurosurg* **46**:113–26.

Povlishock JT, Christman CW. 1995. The pathobiology of traumatically induced axonal injury in animals and humans: a review of current thoughts. *J Neurotrauma* **12**:555–64.

Raisanen J, Ghougassian DF, Moskvitch M, *et al.* 1999. Diffuse axonal injury in a rugby player. *Am J Forensic Med Pathol* **20**:70–2.

Roberts AH. 1970. *Brain damage in boxers*. Pitman Medical, London.

Root I. 1992. Head injuries from short distance falls [see comments]. *Am J Forensic Med Pathol* **13**: 85–7.

Rowbotham OF. 1964. *Acute injuries of the head*, 4th edn. Churchill Livingstone, Edinburgh.

Royal College of Physicians of London. 1969. *Report on the medical aspects of boxing*. Royal Collage of Physicians of London, London.

Schellhas KP, Latchaw RE, Wendling LR, *et al.* 1980. Vertebrobasilar injuries following cervical manipulation. *JAMA* **244**:1450–3.

Schellinger PD, Schwab S, Krieger D, *et al.* 2001. Masking of vertebral artery dissection by severe trauma to the cervical spine. *Spine* **26**:314–19.

Shapiro HA, Gordon I, Benson SD. 1988. *Forensic medicine – a guide to principles*, 3rd edn. Churchill Livingstone, Edinburgh.

Sheffield EA, Weller RO. 1980. Age changes at cerebral artery bifurcations and the pathogenesis of berry aneurysms. *J Neurol Sci* **46**:341–52.

Sherriff FE, Bridges LR, Sivaloganathan S. 1994. Early detection of axonal injury after human head trauma using immunocytochemistry for beta-amyloid precursor protein. *Acta Neuropathol (Berl)* **87**:55–62.

Simonsen J. 1967. Fatal subarachnoid haemorrhage in relation to minor head injuries. *J Forensic Med* **14**:146–55.

Simonsen J. 1976. Massive subarachnoid haemorrhage and fracture of the transverse process of the atlas. *Med Sci Law* **16**:13–6.

Simpson RH, Berson DS, Shapiro HA. 1985. The diagnosis of diffuse axonal injury in routine autopsy practice. *Forensic Sci Int* **27**:229–35.

Skold G. 1985. Injuries to pathologically changed cervical vertebrae. *Am J Forensic Med Pathol* **6**:163–6.

Smith DH, Chen XH, Xu BN, *et al.* 1997. Characterization of diffuse axonal pathology and selective hippocampal damage following inertial brain trauma in the pig. *J Neuropathol Exp Neurol* **56**:822–34.

Smith DH, Nonaka M, Miller R, *et al.* 2000. Immediate coma following inertial brain injury dependent on axonal damage in the brainstem. *J Neurosurg* **93**:315–22.

Somerville A. 1961. Subarachnoid haemorrhage due to trauma without visible external injury. *Med Sci Law* **2**:67–9.

Spicer EJ, Strich SJ. 1967. Haemorrhages in posterior-root ganglia in patients dying from head injury. *Lancet* **2**:1389–91.

Spillane JD. 1962. Five boxers. *Br Med J* **2**:1205–6.

Storey PB. 1969. The precipitation of subarachnoid haemorrhage. *J Psychosom Res* **13**:175–82.

Strassman G. 1949. Formation of haemosiderin and haematoidin after traumatic and spontaneous cerebral haemorrhages. *Arch Pathol* **47**:205–10.

Strich SJ. 1961. Shearing of nerve fibres as a cause of brain damage due to head injury: a pathological study. *Lancet* **2**:443–7.

Strich SJ. 1970. Lesions in the cerebral hemispheres after blunt head injury. *J Clin Pathol Suppl R Coll Pathol* **4**:166–71.

Strich SJ. 1976. Cerebral trauma. In: Blackwood W, Corsellis JAN (eds), *Greenfield's neuropathology*, 3rd edn. Edward Arnold, London, pp. 327–60.

Symonds CP. 1940. Concussion and contusion of the brain. In: Brock (ed.), *Injuries of the skull, brain and spinal cord*. Baillière, London.

Symonds CP. 1962. Concussion. *Lancet* **1**:1–5.

Tatsuno Y, Lindenberg R. 1974. Basal subarachnoid hematomas as sole intracranial traumatic lesions. *Arch Pathol* **97**:211–5.

Terespolsky PS. 1972. Post-traumatic epilepsy. *Forensic Sci* **1**:147–65.

Thiagaraj D, Ming T, Cyn A. 1983. Patterns of injury in deaths due to falling from heights. *Proc First Asian Pacific Congr Legal Med*, p. 399.

Tomei G, Spagnoli D, Ducati A, *et al.* 1990. Morphology and neurophysiology of focal axonal injury experimentally induced in the guinea pig optic nerve. *Acta Neuropathol (Berl)* **80**:506–13.

Tomlinson BE. 1970. Brain-stem lesions after head injury. *J Clin Pathol Suppl R Coll Pathol* **4**:154–65.

Trotter W. 1914. Concussion. *Br J Surg* **2**:271–91.

Vanezis P. 1979. Techniques used in the evaluation of vertebral artery trauma at post-mortem. *Forensic Sci Int* **13**:159–65.

Vanezis P. 1984. *Vertebral artery trauma.* Medical Faculty, University of Bristol, Bristol.

Vanezis P. 1986. Vertebral artery injuries in road traffic accidents: a post-mortem study. *J Forensic Sci Soc* **26**:281–91.

Vanezis P. 1989. *Pathology of neck injury*. Butterworths, London.

Vanezis P, Chan KK, Scholtz CL. 1987. White matter damage following acute head injury. *Forensic Sci Int* **35**:1–10.

Voigt GE. 1981. Small hemorrhages in the brain stem. A sign of injury? *Am J Forensic Med Pathol* **2**:115–20.

Wang H, Duan G, Zhang J, *et al.* 1998. Clinical studies on diffuse axonal injury in patients with severe closed head injury. *Chin Med J (Engl)* **111**:59–62.

Weber W. 1984. Experimentelle Untersuchungen zu Schädelbruchverletzungen des Säuglings. [Experimental studies of skull fractures in infants] *Z Rechtsmed* **92**:87–94.

Wilkinson AE, Bridges LR, Sivaloganathan S. 1999. Correlation of survival time with size of axonal swellings in diffuse axonal injury. *Acta Neuropathol (Berl)* **98**:197–202.

Wilson JV. 1946. *The pathology of traumatic injury.* Livingstone, Edinburgh.

Yamashima T, Friede RL. 1984. Why do bridging veins rupture into the virtual subdural space? *J Neurol Neurosurg Psychiatry* **47**:121–7.

Yanagida Y, Fujiwara S, Mizoi Y. 1989. Differences in the intracranial pressure caused by a 'blow' and/or a 'fall' – an experimental study using physical models of the head and neck. *Forensic Sci Int* **41**:135–45.

Zhang X, Niu W. 1993. A study of enzymohisto-chemistry of cerebral cortical injury. *Forensic Sci Int* **59**:19–24.

Zuo ZJ, Zhu JZ. 1991. Study on the microstructures of skull fracture. *Forensic Sci Int* **50**:1–14.

CHAPTER 6

Chest and abdominal injuries

- Forensic anatomy 222
- Injuries to the chest wall 223
- Haemorrhage and infection in the chest 224
- Pneumothorax 225
- Injuries of the lungs 226
- Injuries of the heart 226
- Haemopericardium and cardiac tamponade 228
- Injuries to great vessels 228
- Foreign bodies in the gut 232
- Injuries to the pelvis and pelvic organs 233
- Complications of abdominal injury 233
- References and further reading 233

The major categories of wound previously described can be inflicted on any part of the body. In forensic practice certain areas are particularly vulnerable or have special medico-legal significance. Head injuries are so important that they have been discussed in a special chapter, but here consideration will be given to other regions, especially the chest and abdomen.

CHEST INJURIES

Damage can be sustained to either the chest wall or to the contents.

FORENSIC ANATOMY

The most important aspect is the relationship of the visceral contents to external landmarks. This is best described by reference to diagrams, where the relationship of pleural cavities, lungs, heart, mediastinum and diaphragm is depicted. It should be appreciated that, from the forensic aspect, the spleen and most of the liver and stomach are thoracic organs in that they lie largely beneath the costal margin, and are vulnerable to both stabbing and blunt injury to the chest.

Penetrating injuries, especially by knife to the lower lateral wall of the thorax, may enter the peritoneal cavity as well as


Common carotid artery
Internal carotid artery
External carotid artery
Hyoid bone
Internal jugular vein
Thyroid cartilage
Cricoid cartilage
Trachea
Apex of lung
Subclavian artery
Left lung
Right lung
Heart
Male nipple level
Lower edge of lung
Lower edge of lung
Lower limit of pleural cavity
Lower limit of pleural cavity
Structures of the thorax and neck
1
2
3
4
5
6
7
8
9
10
1
2
3
4
5
6
7
8
9
10

FIGURE 6.1 *Surface anatomy of heart, lungs and neck structures.*

the pleural spaces, perforating the diaphragm en route. The stomach, being largely within the rib cage, may often be penetrated. The common stab wounds of the heart may also include diaphragmatic and upper abdominal injuries. A knife can enter the front of the lower thorax, pass through either or both ventricles, and exit through the pericardial surface of the diaphragm to enter the upper surface of the liver. The orientation of the heart is often not appreciated after it is removed as an isolated organ, as the tendency is to visualize it as hanging with the apex downwards. In fact, it sits flat on the diaphragm on the lateral edge of the right ventricle, with the inferior vena cava passing immediately downwards into the abdomen.

INJURIES TO THE CHEST WALL

Respiration is dependent on the integrity of the rigid chest wall and, if the expansion is prevented or severely limited, then air entry will be correspondingly diminished. The integrity can be compromised either by severe mechanical failure of the rib cage or by penetration of the pleural cavities.

Fractures of ribs are common, but do not greatly embarrass respiration unless:

- they are so numerous that they prevent expansion of the thorax
- broken ends penetrate the pleura and lungs
- pleural and muscular pain limit respiratory effort.

Where many bilateral fractures are present, especially on the anterolateral sides of the thorax, the condition of 'flail chest' may be present, usually with multiple fractures of some ribs and sometimes with added fracture(s) of the sternum. As a result of loss of rigidity of the chest cage, attempts at expanding the thoracic volume during inspiration are impaired. The loose section is sucked inwards during inspiration, this clinical sign being known as 'paradoxical respiration'. Dyspnoea and cyanosis may develop and extreme degrees of flail chest are rapidly incompatible with life because of progressive hypoxia.

The flail chest is caused by frontal violence, most often sustained in motor vehicle accidents – where the victim is thrown against the steering wheel or fascia – or in stamping assaults, where the shod foot is violently applied to the supine body. In any substantial chest injury, broken rib ends may be displaced inwards, the jagged tips ripping the parietal and visceral pleura. This may cause a pneumothorax or a haemothorax, or both, from penetration of the lungs, with the formation of a bronchopleural fistula. In gross chest injuries there may be compound fractures of ribs that allow a pneumothorax to form from external communication with the atmosphere, but this is rare in civil practice, though common in battle casualties.



FIGURE 6.2 *Anterior view of trunk showing surface relations of heart and aorta.*

Rib fractures are most often seen in the anterior or posterior axillary lines caused by falls onto the side. The upper ribs are less often fractured, except by direct violence from kicking, heavy punching or traffic accidents. The fracture sites almost always show bleeding beneath the periosteum or the parietal pleura if the fractures occurred during life – though it must be admitted that (rarely) undoubted ante-mortem fractures may be totally bloodless, whereas some post-mortem cracks may exhibit slight oozing from the marrow cavity into the adjacent tissues. Attempts at resuscitation, especially external cardiac massage, now provide a common cause for extensive rib fractures (up to 40 per cent) and make the task of the pathologist much more difficult when trying to differentiate original trauma from the effects of enthusiastic first aid (Leadbeatter and Knight 1988). Bleeding may or may not be seen in these resuscitation fractures and, as the attempts at revival are, by definition, perimortal in timing, it is often impossible to say if they were immediately ante-mortem or post-mortem.

As the bracing action of adjacent intercostal muscles may conceal any mobility of the ribs when being examined at autopsy, it is a useful procedure to slit all the intercostal muscles with a knife when chest injury is suspected to allow any mobility to be detected more easily. In the osteoporosis of senility and some diseases, the ribs may be so fragile as to be breakable by finger pressure. Allowance must be made for this fragility in interpreting the cause of the fractures.



FIGURE 6.3 *Extensive abrasions and deformity of the chest in a man found by the roadside. All his ribs and sternum were fractured, resulting in a 'flail chest'. It was thought to be a road accident until bovine hairs were found on his clothing. He had been crushed by a bull and then tossed over the field wall.*



FIGURE 6.4 *Extensive bruising of the chest caused by kicking and stamping, resulting in multiple rib and sternal fractures. Over the left costal margin there is a pattern suggestive of the sole and heel of a shoe.*

In infants, especially victims of child abuse, rib fractures are common and may be an important diagnostic sign of abuse in doubtful cases. Where a small infant is squeezed from side to side, as when adult hands are clamped in each axilla or lower on the lateral sides of the chest, the hyperflexion can easily break ribs in their posterior segments, usually near their necks. The ribs are levered against the transverse processes of the vertebrae by excessive anterior flexion, which explains the tendency to fracture in the paravertebral gutter. Fresh fractures will be obvious, both on radiography and at autopsy. Within about 2 weeks (though this is very variable), callus will form and be visible both on X-ray and by direct post-mortem inspection. It is extremely difficult to date such callus.

It is said by paediatricians and radiologists that anterior rib fractures are rare in infancy other than from child abuse; though this is probably generally correct, care must be taken to exclude bony injury from the now almost universal attempts at resuscitation (even though infant ribs are very pliable). In very young infants, the possibility of older fractures dating back to birth injury cannot be dismissed, though again these are rare.

The sternum may be fractured by stamping or other frontal impacts, but far more force is necessary than with ribs. If posterior displacement of a fragment occurs, the underlying heart or great vessels may be severely damaged.

HAEMORRHAGE AND INFECTION IN THE CHEST

Any injury to the chest wall or lung surface that breaches blood vessels and the pleural lining can lead to a haemothorax. Intercostal and, less often, mammary arteries can bleed into the pleural cavities, but most massive haemorrhage comes from large vessels in the lung or mediastinum. The lung hilum can be torn or penetrated by stabs wounds. Another obvious source of a haemothorax is the heart itself, though there must also be a defect in the pericardial sac before the blood can reach the chest cavity. Several litres of blood may accumulate in the chest, either as liquid or clot, or usually a mixture of both. Death may occur from loss of circulating blood volume, even if there is relatively little external bleeding.

Many intrathoracic haemorrhages may be fatal with virtually no external blood loss, a fact that the police often find



FIGURE 6.5 *Penetrating stab wound of chest, which has traversed the lung. The blade has passed through the upper lobe, crossed the interlobar fissure and re-entered the lower lobe. Death was caused by a haemothorax from severed branches of the pulmonary vessels within the lung.*

hard to credit if there is little blood at the scene of a fatal stabbing. A knife that passes obliquely into the chest through intercostal muscles may puncture a great vessel or heart chamber, allowing a fatal cardiac tamponade or haemothorax, yet the valve-like overlap of the tissues after withdrawal of the blade may seal up the external wound almost completely and prevent significant bleeding, especially as the blood inside the chest is not under any appreciable pressure.

The same may apply to a gunshot wound, where bleeding can be virtually absent if the wound is uppermost after death. Where the body lies above the wound, of whatever type, then considerable post-mortem gravitational leakage can take place.

Whatever the source of the bleeding, post-mortem haemorrhage can add very considerably to the volume found in the chest at autopsy. Due to the great variability of post-mortem coagulation – and subsequent lysis – much of the blood found at autopsy may not have been there at the moment of death. It is impossible to quantify this additional leakage in retrospect, but the ever-present possibility makes it unwise to be dogmatic about the amount of blood loss prior to death.

Infection following a chest wound is uncommon in forensic practice, as most deaths occur from haemorrhage within a relatively short time before infective sequelae have time to be established. Where survival is longer, then effective medical care usually prevents secondary infection. However, cellulitis, pleural inflammation and even empyema may supervene, especially where some dirty weapon is used, or where clothing or other foreign material has been carried into the wound. Infection may be of many types, but staphylococci, *Proteus*, coliforms and *Clostridium perfringens* are commonly found on culture.

PNEUMOTHORAX

There are three types of pneumothorax:

1. a simple type where a leakage through the pleura allows air to enter the pleural cavity, but where the communication rapidly closes. The lung partly collapses, but if death does not supervene the air is soon absorbed. If the communication remains open, then a bronchopleural fistula ensues with air in the pleural cavity but, as it is not under pressure, like type 2, it will not bubble out when the autopsy 'water test' is attempted. Radiology is then the best means of demonstrating the air in the pleural cavity.
2. when the leak in the pleura (or rarely the chest wall) has a valve-like action, air is sucked into the pleural cavity at each inspiration, but cannot escape on expiration. This pumping action leads to a 'tension pneumothorax', which causes complete collapse of the lung onto its hilum and a shift of the mediastinum to the opposite side. It is this type of pneumothorax that may be demonstrated at autopsy by penetrating an intercostal space under water, though radiology is a much better method of detection of all types of pneumothorax.
3. when an injury of the chest wall communicates with the pleural cavity, a 'sucking wound' may form with direct passage of air from the exterior. This type is most often seen in military surgery, and may be complicated by haemorrhage and infection.

A common traumatic cause of pneumothorax is a stab wound of the chest that allows direct communication with the exterior, though usually the layered skin and intercostal muscles closes the track when the weapon is withdrawn. The knife often enters the lung, however, so that air can enter the pleural cavity from the bronchi.


Subpleural abscess or tuberculous cavity
Punctured chest wall
Torn pleural adhesion
Blast injury
Punctured lung
Burst emphysematous bulla
Barotrauma (decompression)

FIGURE 6.6 *Common causes of pneumothorax.*

Natural disease can also cause a pneumothorax, which can lead to sudden death. Common causes are a ruptured emphysematous bulla, a tuberculous lesion at the lung periphery, or a tear at the site of a fibrous pleural adhesion. This may initially appear suspicious, as in a case seen by the author (BK) in which a teenage boy bent down to tie a shoelace and fell dead. At autopsy the only finding was a pneumothorax that had been caused by a single pleural adhesion that had torn the visceral pleura. This illustrates the fact that sometimes a pneumothorax can cause sudden unexpected death, presumably via some vagal cardioinhibitory mechanism.

INJURIES OF THE LUNGS

Bruising of the lungs is common in both open and closed chest injuries. Any substantial impact on the chest can contuse the lung surface or deeper parts. This may be beneath the area of impact or 'contrecoup' damage on the opposite surface. Deceleration injuries are seen in falls and traffic accidents, most commonly along the posterolateral surfaces where a vertical line of subpleural bruising occurs, often in the paravertebral gutter. The outline of ribs may be imprinted in lines of contusion on the pleural surface of the lungs. Bruising may be so severe as to form subpleural blood blisters, which may rupture to release blood or air into the pleural cavities.

In all severe chest injuries the central parts of the lung may show bleeding, sometimes sufficient to form actual haematomas with breakdown of lung tissue. Osborn describes 'pincer contusions' of the lung, where the expanded lower margins of the lungs become trapped in the narrow costophrenic angles.

Laceration of the lung can occur in blunt injuries and even lobes or parts of a lobe may be detached. The hilum may tear and the pulmonary ligament below the hilum is a frequent site of haemorrhage. Vessels in the hilum (especially pulmonary veins) or those more peripherally, may be ripped, causing severe intrapleural or mediastinal haemorrhage. In children, lung injuries can occur without fracturing of the ribs, because of the greater elasticity of the latter and the ability of the chest wall to deform.

Penetrating injuries of the lungs are common, usually from stabbing by knives. The wounds may end in the lung parenchyma or in large vessels, or may be 'through-and-through' injuries that emerge to cause further damage to the heart or great vessels. They assist the pathologist by delineating the track and the direction of the stabbing, but due allowance must be made for the marked variation in topography during inspiration, compared with the collapsed state seen at autopsy.

Blast injury is dealt with elsewhere, but the lungs are the most vulnerable organs to this type of injury due to their large tissue–air interface.

INJURIES OF THE HEART

The heart is vulnerable to both penetrating and blunt injuries. A common form of homicide is a stab wound of the chest which penetrates the heart. The entry point may be anywhere over the praecordium or adjacent areas if the angulation of the track is sufficient. Sometimes the sternum is penetrated by a forceful blow that reaches the underlying heart, but most stab wounds enter via the intercostal spaces, or through a rib or costal cartilage.

Rarely, an upward stab from the abdomen reaches under the costal margin to penetrate the diaphragm. The right ventricle is often injured by a stab wound as it presents the largest frontal area, but the anterior interventricular septum and the left ventricle are also vulnerable. A shallow stab wound may enter the myocardium and not reach the lumen of the ventricle. In such a case there may be little disability unless a coronary vessel is severed, which may either cause death from myocardial insufficiency (if a major artery is transected) or cardiac tamponade.

More often – especially in the right ventricle – the knife passes into the cavity. In the thin right ventricle this usually



FIGURE 6.7 *Even a small penknife can inflict a fatal wound. This injury was caused by a boy to a police officer when the latter was apprehending him for some minor offence. Though the blade was only about 6 cm long, this is sufficient to enter alongside the sternum and puncture the ventricular wall.*

leads to copious bleeding into the pericardial sac even though the intraventricular pressure is relatively low because of the inability of the thin wall to close the defect by muscle overlap and contraction.



FIGURE 6.8 *Stab wound penetrating the pericardium (reflected upwards) with a wound in the corresponding point on the heart. Death was caused by cardiac tamponade from leakage of blood from the ventricular lumen.*

In the left ventricle, the contraction of the layered thick wall may partly or wholly seal the wound, and bleeding can be slight. It is, however, more common for persistent bleeding to occur and, if the drainage from the pericardial wound is less than the leakage from the ventricle, eventually a tamponade will develop. These variables make it impossible to calculate how long the victim was able to carry on with his activities, often a matter of dispute at a criminal trial. In general, wounds in the right ventricle are more dangerous than in the left because of the absence of the muscular 'self-sealing' effect.

Many stab wounds of the heart are transfixing or 'through-and-through' injuries, the knife entering one wall and emerging through another. If the left ventricle carries both wounds, the rapidity of bleeding may still not be torrential. Some of these wounds pass downwards and transfix the heart, then exit through the lower wall of the right ventricle and pass on via the diaphragm to end in the liver.

Blunt injuries of the heart are seen in civilian practice mainly in traffic accidents, falls from a height and in stamping assaults, though any heavy impact (including a punch) can cause fatal damage. There are usually multiple rib and sometimes sternal fractures, with or without a flail chest. Occasionally there can be heart damage in an intact chest cage, especially in a child with a pliable thorax. Fatal blunt damage of the heart may occur, however, without a mark on the skin of the thorax nor damage to the bony chest cage. The cardiac injuries are usually on the front of the organ, especially to the right ventricle, though posterior bruising and laceration can occur if the heart is compressed against the thoracic spine, as in stamping assaults and steering wheel impacts.

All degrees of damage can occur, from mere epicardial bruising to lacerations that open the ventricular lumen widely.



FIGURE 6.9 *Ruptured interventricular septum as a result of impact on the front of the chest. The septum can tear without damage to the outer walls of the heart.*

Internal damage to the heart may be present, without external signs of injury to either the heart or the external chest wall. The interventricular septum may be ruptured as a sole lesion, the mechanics of which seem obscure. In gross injuries, such as aircraft crashes, the whole heart may be avulsed from its root, to be found lying loose in the thorax. Histological damage, especially contraction band necrosis, can be found even when there is no macroscopic abnormality. A comprehensive review of cardiac contusions has been made by Sagall (1971).

HAEMOPERICARDIUM AND CARDIAC TAMPONADE

Bleeding into the pericardial sac may occur from the surface or the cavities of the heart, or from the intrapericardial segments of the roots of the great vessels, particularly the aorta and pulmonary artery. Most causes of haemopericardium are from natural disease, such as a ruptured myocardial infarct or a ruptured dissecting aneurysm of the aorta (Chapter 25), but it is not an uncommon sequel to injury to the chest. When the damage has been caused by a stab that has perforated the pericardial sac, bleeding can escape into the pleural cavities, mediastinum or even abdomen if the diaphragm is penetrated. Death may occur from sheer blood loss if the haemorrhage can escape from the confines of the pericardium, but another common lethal condition is 'cardiac tamponade'.

In the tamponade, blood accumulates in the pericardial sac faster than it can escape, either because the bleeding rate exceeds the drainage or because the exit hole in the pericardium becomes blocked by blood clot. In cases where the bleeding is from a contusion or laceration of the heart, there is no escape route from the sac. When sufficient blood accumulates, the pressure in the pericardial sac increases and begins to prevent the passive filling of the atria during diastole. The cardiac output falls, as does the systemic blood pressure and the venous pressure rises. If unrelieved, death will follow, though the time that this takes is variable and almost impossible to calculate retrospectively on pathological findings. It has been stated (Moritz 1942) that about 400–500 ml of blood is sufficient to cause death, though this seems a greater volume than is usually seen in tamponades. Where trauma to the heart co-exists, it is difficult to apportion the relative contribution to death of the tamponade as opposed to the other injuries.

INJURIES TO GREAT VESSELS

The most vulnerable vessel is the aorta, which most commonly suffers injury in deceleration trauma from both road and air accidents, as well as from falls from a height. When the thorax is suddenly decelerated, the heart – being relatively mobile in the chest – attempts to continue in the original direction. This causes severe traction on the root of the heart, and a common sequel is complete or partial rupture of the aorta in the descending part of its arch. In falls from a height, Fiddler (1946) claims that the lesion is the result of the abdominal and thoracic viscera being forced caudalwards by the abrupt deceleration when landing on the feet or buttocks. Tannenbaum and Ferguson (1948), however, postulate that the mechanism is a sudden rise in intra-aortic pressure. Lasky (1974) has reviewed the biomechanics of impact injury of the aorta.



FIGURE 6.10 *The usual site of rupture of the aorta in deceleration injury.*

According to Fiddler, rupture occurs almost constantly at a point 1.5 cm distal to the attachment of the ligamentum arteriosum, the remnant of the ductus. The lower thoracic aorta is closely bound to the anterior longitudinal ligament on the front of the dorsal spine, until it reaches the termination of the arch, where it curves forwards. This appears to be the weak point and transection occurs at this level, sometimes so cleanly that it looks like a surgical incision. The tear is annular and at right angles to the axis of the aorta. Sometimes, there may be multiple parallel intimal tears near the main transection, the so-called 'ladder-rung tears'. In deceleration trauma, these incomplete tears, which affect only the intima and inner media, may be found without major transection; where death is delayed, false aneurysms and dissections may be diagnosed on aortograms.

The pulmonary artery is much less vulnerable to blunt trauma than the aorta but, in stamping assaults and steering



FIGURE 6.11 *Complete transection of the aorta in the distal part of the arch. The victim was a car driver who suffered a severe deceleration impact. There is also some slight pulmonary bruising; the lungs are asthmatic.*

wheel impacts, it may be damaged by depressed rib cage and sternal fractures. The pulmonary artery and vein branches may also be damaged in the root of the lung, where hilar tears are not uncommon. The great vessels are often involved in penetrating injuries, notably stab wounds. Stabs of the upper part of the chest may pass directly into the arch of the aorta, especially on the right side of the sternum. Here even a shallow injury may reach the aorta and the authors have seen several cases in which a short-bladed penknife has caused death in this way.

Stabs that are either too high, or are directed too laterally to puncture the chambers of the heart may penetrate the ascending aorta or the pulmonary artery. If the wound is below the reflection of the pericardium, a haemopericardium and perhaps cardiac tamponade may result. Other stab wounds may injure the heart valves or may enter the root of the lung to penetrate the large primary branches of the pulmonary artery or veins, causing gross bleeding into the corresponding pleural cavity or the mediastinum.

ABDOMINAL INJURIES



FIGURE 6.12 *Surface anatomy of liver, stomach and heart.*

As with the thorax, the damage caused by blunt and penetrating trauma of the abdomen depends upon the location of the injury. In addition, the large area of the anterior abdomen occupied by the intestine provides a target for perforation with consequent chemical or infective peritonitis.

Open or penetrating wounds need little description, as they follow the characteristics of stab-like injuries in general. The liver, and especially the spleen, may bleed extensively, causing a haemoperitoneum. The intestine and mesentery are the other major targets, wounds often being multiple, because of the overlapping nature of the coils and their mesentery. The stomach, being partially protected by the rib margin, is less often penetrated from the abdomen, but is not uncommonly involved in chest stabbings that pass downwards through the diaphragm. The kidneys are rarely stabbed except from a thrust in the back.

Closed or blunt injury to the abdomen is common from both accidents and assault. Impact on the abdomen by a car steering wheel was more common before the widespread use of safety-belts and air-bags and still occurs in severe deceleration accidents. The liver, intestine, spleen and mesentery are most vulnerable. Crushing between two vehicles, or between a vehicle and a wall is another mechanism for abdominal trauma, and may also be seen in railway and industrial accidents where squeezing between two opposing surfaces occurs. In homicides, assaults and child abuse, kicking, stamping and heavy punching can also cause blunt injury to the abdomen.

Whatever the mechanism of infliction, the following features may be present:

- Bruising of the abdominal wall, both of the skin and the underlying muscles, is often (but by no means



FIGURE 6.13 *Posterior view of trunk to show surface relations of organs.*



FIGURE 6.14 *Injury or rupture of intestine or mesentery in violent blow to the upper central abdomen. Because of its small size and the thin abdominal wall, the infant duodenum is especially vulnerable.*

invariably) seen in abdominal trauma. Where subcutaneous bleeding is profuse it may track from the initial area of impact to become more diffuse and may cover a large area of abdominal wall, especially in the lower segment. Blood may track down the inguinal canal and appear in the scrotum or labia.

More often there are discrete bruises on the abdominal skin, associated in some instances with surface abrasions. Kicks will usually leave scuffed abrasions if tangential, unless protected by clothing. Fingertip or knuckle bruises may be seen, especially in child abuse. In infants, bruises may be seen on the sides of the abdomen where adult fingers have forcibly gripped or lifted the child, though these are more common in the axillary line of the chest.

Severe or fatal intra-abdominal injury may be present, however, without any mark on the skin. This can occur if clothing protects or if a blunt impact is applied over, a relatively large surface. In child abuse, for example, the liver, mesentery or duodenum can be ruptured with no external sign whatsoever.

- Extensive bleeding into the peritoneal cavity, usually from rupture of a solid viscus or bleeding from the mesentery.
- Bruising or rupture of the stomach and diaphragm. The stomach is less vulnerable than the intestines, but may be lacerated by a heavy blow in the upper abdomen, especially when full of food or fluid.
- The intestine and its mesentery are frequently damaged in abdominal trauma. Extensive bruising of the gut and its vascular mesentery may occur, mainly from being crushed against the prominent lumbar vertebrae in the midline. The duodenum and jejunum are particularly vulnerable to transection from being compressed against the spine, especially in children, where a heavy blow in the central or upper abdomen can cut through the third part of the duodenum almost as cleanly as a scalpel. Laceration of the mesentery is not uncommon both in traffic accidents and assaults. The same mechanism of compression against the lumbar spine causes bruising and tearing of the central parts of the mesentery, which usually occurs towards the intestinal margin of the membrane. Multiple fenestrations may be seen, presumably because folds of mesentery overlie each other and are injured when in apposition.

Severe and intractable bleeding can occur in circumstances where surgical treatment is often not offered because the condition is unrecognized. Kicks and punches in the abdomen may be sustained by drunken persons who may be apparently unaware of the seriousness of their injuries until collapse and death supervene perhaps hours later.

In a case seen by the author (BK), a man was involved in a fight and then allegedly assaulted the police. He was forcibly restrained and may have been struck in the abdomen by a knee. He remained apparently well, though drunk, in a police cell for more than 5 hours, before collapsing and dying on his way to the lavatory, never having complained of any abdominal pain. Autopsy revealed several litres of blood in his peritoneal cavity, which had escaped from several large tears in the mesentery. Similar bleeding from mesenteric lacerations has been seen in abused infants,



FIGURE 6.15 *Laceration of the spleen following lower chest impact during a road traffic accident.*



FIGURE 6.16 *Abdominal wall bruising with fatal intraperitoneal haemorrhage from a ruptured mesentery. There is also a large haematocele from a gang attack in which repeated kicking occurred.*

where the thin abdominal wall provides little protection from blows on the abdomen.

Injury to the mesentery may damage local arteries without causing severe bleeding, but may occlude or thrombose them, with infarction of the bowel as a consequence. Perforation may be delayed for a day or two and in children and old people there need not be the dramatic symptoms of the onset of peritonitis that is usually seen in clinical surgical practice.

The colon is rarely injured unless the abdominal injury is gross. One well-known lesion is rupture of the rectum or sigmoid by a high-pressure air hose being placed in or near the anus as a practical joke.

- Rupture of the spleen is a common surgical emergency after trauma but may be first found at autopsy if undiagnosed, or if death occurs from lack of speedy surgical treatment, or if other injuries made recovery impossible. An enlarged spleen is more vulnerable and more fragile than a normal organ. Malaria, glandular fever and other infections increase the risk of rupture. The ‘stiletto’ dagger was specifically designed in medieval Italy for puncturing the enlarged malarious spleen by an upward blow under the left costal margin.

The spleen can be damaged either from impact on its surface or from traction on its pedicle. The rupture may be immediate or may be delayed if a large subcapsular haematoma and underlying tear are held intact for a time by the capsule. This delay can last for a number of days or even weeks.

- Rupture of the liver is also a common lesion following serious abdominal trauma, such as fall from a height or a crush injury between two wagons. It is seen especially in traffic accidents, either from impact of the driver on the rim or centre of the steering wheel or by the unrestrained passenger being thrown against the fascia. A pedestrian can also suffer a ruptured liver either as a primary impact from a vehicle or as secondary damage from being thrown to the ground.

A more recent cause of liver injury is enthusiastic external cardiac massage. Even if death has already taken place, there may still be a significant amount of blood oozing from the liver tears into the peritoneal



FIGURE 6.17 *Complete bisection of the liver in a high-speed deceleration during a traffic accident. The abdomen of the driver was hurled against the steering wheel as he was projected through the windscreen.*

cavity. Moritz (1942) has described six varieties of hepatic laceration, but such a differentiation is of little practical use. The liver may show one or more linear cracks, most often on the convex upper surface, which may be of any severity from superficial subcapsular tears to complete transection of the organ. Not infrequently, several roughly parallel tears are seen on the upper surface, obviously from the same type of mechanical stress. The surface lacerations may extend deeply into the liver and may even appear on the opposite surface. Occasionally, there may be internal tears that do not communicate with the surface. As in the spleen, a subcapsular haematoma can reach a large size before bursting into the peritoneal cavity, causing a delay in collapse or death.

Infants readily suffer liver damage from trauma and it is a well-known component of the child abuse syndrome. Liver tears can occur during the process of birth, particularly in breech presentation.

- Injuries to the kidney. Being deeply situated at the back of the abdomen in the paravertebral gutter, the kidneys are rarely damaged by frontal trauma, but may be involved in kicks or heavy blows to the loin. Traffic impacts, mainly in pedestrians, can damage the kidney, but kicking is another cause of this rather uncommon injury. When a victim is lying on the ground, a swinging boot can conveniently enter the slightly raised arch between the rib margin and hip, where the kidney is situated.

Perirenal haemorrhage is much more common than damage to the actual organs themselves, but when they are injured, all grades of damage from comminuted pulping through transection to shallow surface lacerations may be seen. Like the mesentery and spleen, damage to vessels may lead to post-injury infarction. The suprarenal vessels can be damaged by impact and, statistically, the right suprarenal artery is more often involved in traffic accidents in Britain because the direction of traffic tends to favour lesions on that side. It is, however, difficult to differentiate direct trauma to the suprarenal vessels from the common post-stress haemorrhages, often bilateral, of the Waterhouse–Frederichsen type. These occur quite commonly a few days after any trauma, surgical operation or infection, and are rarely diagnosed by clinicians (Knight 1980) (see Chapter 13).

FOREIGN BODIES IN THE GUT

Though not usually a feature of trauma, foreign bodies and material are not infrequently found in the alimentary system in forensic practice, both clinically and at autopsy.

Disorders of the mental state may lead to extraordinary numbers of objects being swallowed, which may be present anywhere from mouth to anus, but especially in the stomach. Betz *et al.* (1994) describe two such deaths, where, in one, 2000 cm^3 of debris, including broken glass, was in the alimentary tract; the other suffered intestinal obstruction due to ingestion of a large quantity of his own hair.

Similar aberrations may lead to insertion of foreign objects into the rectum, urethra, bladder and vagina. The authors have seen large objects of various types, e.g. potatoes in the rectum, lengths of broom handle and wood in the colon (one penetrating the liver) and a banana and a beer can in the vagina. Sexual perversions, masturbation and heterosexual or homosexual activities may account for these, as well as frank mental abnormality.

In recent years, the smuggling of narcotics through ports and airports has commonly been accomplished by 'body-packing', the drugs being concealed in condoms, which are then either swallowed or, less often, inserted into the rectum or vagina. Deaths have occurred in these body-packers, usually by rupture of a package within the gut, so that a massive dose of heroin or cocaine is released with all the attendant toxic effects. Rarely, the mass of illicit material may cause intestinal obstruction, leading to a surgical emergency, which the carrier does not wish to be investigated, for obvious reasons.

INJURIES TO THE PELVIS AND PELVIC ORGANS

The bony pelvis suffers a variety of fractures and dislocations in severe trauma:

- Where great pressure is applied to the front of the abdomen or pubic area – as in running over by a vehicle wheel – the pelvis may be splayed open, the symphysis parting and one or both sacroiliac joints becoming dislocated.
- An impact from the side may shatter the superior and, less often, the inferior pubic ramus, and again dislocate the sacroiliac joint on that side.
- A fall from a height onto the feet may transmit the force up the legs either to dislocate the hips or even to drive one or both femoral heads through the acetabulum. If the hip joints remain intact, the pelvic girdle may crack and again the sacroiliac joints may be sheared apart.
- A kick or heavy fall onto the base of the spine may fracture the coccyx or sacrum.

The pelvic organs with the exception of the bladder are generally protected from all but the most severe trauma. When it is full, the bladder can be ruptured by heavy blows or kicks on the lower abdomen. The empty bladder is rarely injured by blunt trauma. The male urethra is also vulnerable to direct trauma, such as falling astride a solid object like a gate, or being kicked in the crutch, both of which compress the urethra against the undersurface of the pubis.

The external genitals may suffer injury, apart from the sexual assaults discussed in Chapter 18. The scrotum is vulnerable to severe bruising, especially from kicks: a large haematocele may develop. Scrotal and vulval injuries can occur from falling astride an object or in traffic accidents. Impact of a bicycle wheel between the legs is one such cause.

COMPLICATIONS OF ABDOMINAL INJURY

The most common fatal sequel to intra-abdominal trauma is haemorrhage from any of the contained organs. The spleen and mesentery tend to bleed most copiously and quickly, though even here there can be a delay of many hours before serious symptoms are obvious – and, in the case of a subcapsular laceration of the spleen, the time can be far longer. The liver tends to ooze more slowly unless a major injury opens a large vessel or an extensive area of hepatic tissue.

The mesentery contains numerous blood vessels that are not covered by parenchymatous tissue as in the liver or spleen, so bleeding is usually brisk from significant tears – although, as illustrated by the case described above, even this injury can lead to delayed death.

Because all bleeding in the abdomen, unless it is from a wound of the aorta, takes time to accumulate, restriction of the victim's activity immediately after the injury need be minimal or absent unless there are other factors involved. It is never safe for a pathologist to declare that rapid immobility must have ensued, unless there are other gross injuries.

As mentioned in relation to intrathoracic bleeding, some of the blood found at autopsy within the peritoneal cavity may have accumulated there after death, adding to the true ante-mortem volume.

In spite of common surgical experience, even severe intra-abdominal injuries leading to bleeding need not necessarily be painful, especially in the commonly associated circumstance of the victim being under the influence of alcohol.

Perforation of the gastrointestinal canal is another serious complication of trauma, though often death ensues from the totality of injuries before infection can become established. As in natural perforated peptic ulcer, penetration of the stomach or duodenum will cause a chemical peritonitis that can be a cause of severe and immediate shock – perhaps a major factor in a rapid death. Rupture of the small or large intestine is less damaging but, if survival continues, will inevitably lead to generalized peritonitis unless vigorously treated. Open wounds of the abdomen, including stabbing, will introduce organisms from the outside into the peritoneal cavity. In addition to infection, trauma to the intestine may cause an intractable ileus; if the pancreas is damaged, there may be widespread fat necrosis in the mesentery and omentum.

REFERENCES AND FURTHER READING

Adams JE, Davis GG, Heidepriem RW, 3rd, *et al.* 2002. Analysis of the incidence of pelvic trauma in fatal automobile accidents. *Am J Forensic Med Pathol* **23**:132–6.

Albrektsen SB, Thomsen JL. 1989. Detection of injuries in traumatic deaths. The significance of medico-legal autopsy. *Forensic Sci Int* **42**:135–43.

Betz P, van Meyer L, Eisenmenger W. 1994. Fatalities due to intestinal obstruction following the ingestion of foreign bodies. *Forensic Sci Int* **69**:105–10.

Bowen DA. 1970. A survey of injuries to the liver and spleen in forensic autopsies. *J Forensic Med* **17**:12–19.

Canfield TM. 1969. Suicidal gunshot wounds of the abdomen. *J Forensic Sci* **14**:445–52.

Cohle SD, Hawley DA, Berg KK, *et al.* 1995. Homicidal cardiac lacerations in children. *J Forensic Sci* **40**:212–18.

Cotton JM, Cooke JC, Monaghan MJ. 2000. Forensic echocardiography: a case in point. *Echocardiography* **17**:193–4.

Darok M, Beham-Schmid C, Gatternig R, *et al.* 2001. Sudden death from myocardial contusion following an isolated blunt force trauma to the chest. *Int J Legal Med* **115**:85–9.

Davis C. 1963. Spontaneous rupture of the stomach. *Arch Surg* **32**:170–6.

Denton JS, Kalelkar MB. 2000. Homicidal commotio cordis in two children. *J Forensic Sci* **45**:734–5.

Fiddler J. 1946. *The pathology of traumatic injury.* Livingstone, Edinburgh.

Frazer M, Mirchandani H. 1984. Commotio cordis, revisited. *Am J Forensic Med Pathol* **5**:249–51.

Gunther WM, Symes SA, Berryman HE. 2000. Characteristics of child abuse by anteroposterior manual compression versus cardiopulmonary resuscitation: case reports. *Am J Forensic Med Pathol* **21**:5–10.

Hale HW. 1965. Pulmonary contusions. *J Trauma* **5**:647–52.

Knight B. 1980. Sudden unexpected death from adrenal haemorrhage. *Forensic Sci Int* **16**:227–9.

Lasky I. 1974. *Human aortic laceration due to impact.* In: Wecht C (ed.), *Legal medicine annual.* Appleton Century Crofts, New York.

Leadbeatter S, Knight B. 1988. Resuscitation artefact. *Med Sci Law* **28**:200–4.

Lloyd RG. 1982. Delayed rupture of stomach after blunt abdominal trauma. *Br Med J Clin Res Ed* **285**:176.

Loop FD, Hofmeir G, Groves LK. 1971. Traumatic disruption of the aortic valve. *Cleveland Clin Q* **38**:187–94.

Mackintosh AF, Fleming HA. 1981. Cardiac damage presenting late after road accidents. *Thorax* **36**:811–13.

Maron BJ, Poliac LC, Kaplan JA, *et al.* 1995. Blunt impact to the chest leading to sudden death from cardiac arrest during sports activities. *N Engl J Med* **333**:337–42.

McCormick GM, 2nd, Young DB. 1995. Spontaneous rupture of the spleen. A fatal complication of pregnancy. *Am J Forensic Med Pathol* **16**:132–4.

Menzies RC. 1978. Cardiac contusion: a review. *Med Sci Law* **18**:3–12.

Moritz AR. 1942. *The pathology of trauma*. Lea & Febiger, Philadelphia.

Murphy GK. 1985. A single fatal penetrating chest wound from shattered wind-blown glass. *Am J Forensic Med Pathol* **6**:332–5.

Noon GP, Boulafendis D, Beall AC, Jr. 1971. Rupture of the heart secondary to blunt trauma. *J Trauma* **11**:122–8.

Ormstad K, Rajs J, Calissendorff B, *et al.* 1984. Difference between in vivo and postmortem distances between anterior chest and heart surface. A combined autopsy and in vivo computerized tomography study. *Am J Forensic Med Pathol* **5**:31–5.

Orr CJ, Clark MA, Hawley DA, *et al.* 1995. Fatal anorectal injuries: a series of four cases. *J Forensic Sci* **40**:219–21.

Ortmann C, Pfeiffer H, Brinkmann B. 2001. Immunohistochemical alterations after intravital and post-mortem traumatic myocardial damage. *Int J Legal Med* **115**:23–8.

Osborn GR. 1943. Findings in 272 fatal accidents. *Lancet* **245**:277–84.

Puffer P, Gaebler M. 1991. [Traumatic diaphragmatic rupture in a forensic medicine autopsy sample.] *Beitr Gerichtl Med* **49**:149–52.

Sagall EL. 1971. Contusion of the heart: medical and legal considerations. In: Wecht C (ed.), *Legal medicine annual.* Appleton Century Crofts, New York.

Simonsen J. 1983. Injuries sustained from high-velocity impact with water after jumps from high bridges. A preliminary report of 10 cases. *Am J Forensic Med Pathol* **4**:139–42.

Stajduhar-Djuric Z. 1960. Penetrating wounds of the ascending aorta and heart. *J Forensic Med* **7**:147–52.

Tannebaum I, Ferguson JA. 1948. Rapid decelaration and rupture of the aorta. *Arch Pathol* **45**:503–5.

Teresinski G, Madro R. 2001. Pelvis and hip joint injuries as a reconstructive factors in car-to-pedestrian accidents. *Forensic Sci Int* **124**:68–73.

CHAPTER 7

Self-inflicted injury

■ Suicidal injuries 235
■ Self-inflicted injuries other than suicide 240
■ References and further reading 243

Injuries that are deliberately self-inflicted are common and their examination is a frequent task for both pathologists and clinical forensic practitioners. These events consist of suicide, attempted suicide and suicidal gestures, the latter lacking the intention to kill though death may inadvertently ensue. In addition, there is non-suicidal self-inflicted trauma, as described below.

One of the most difficult decisions that can face pathologists, medical examiners and legal authorities, such as coroners, is the differentiation between homicide, suicide, accident and other self-inflicted injury. Though it is not the legal function of a pathologist to attribute motive, his experience and training are often the factors that lead the official authority to make a decision as to the classification of the manner of death or injury. One such situation is fatal auto-erotic activities, described in Chapter 15.

In addition, when a pathologist is assisting the police in the early stages of a death investigation, his opinion and decision about the manner of the death may be crucial in initiating or aborting a homicide investigation – an onerous decision which may have serious and expensive consequences if wrong. It is therefore a most important function of the forensic pathologist to decide on the evidence of a death scene and subsequent autopsy whether murder, suicide or accident is the most likely explanation.

Self-inflicted injury, when not suicidal, is often not fatal and the pathologist is usually not consulted unless he also includes clinical forensic medicine in his work. The pathologist may, however, be asked for his opinion, as he is a specialist in trauma and may be able to provide the most useful opinion available. In other cases, self-inflicted injury, which the victim did not intend to be fatal, may end in death from a variety of causes and thus the pathologist will be directly involved.

SUICIDAL INJURIES

This discussion is confined to physical trauma, self-poisoning being considered later in the book.

Suicides may injure themselves in many different ways, some bizarre in the extreme. The pathologist must always be alert to the possibility that such injuries are not true suicides, but some manifestation of peculiar practices that have taken a course unintended by the victim. A prime example is masochistic asphyxia, which is still sometimes mistaken for suicide (Chapter 15). Even more serious is the homicide that appears to be a suicide, though the reverse also occurs.

Suicides, apart from poisoning, may use one (or even more) of the following methods, though the list is by no means exclusive:

- stabbing and cutting
- firearms and explosives
- jumping from a height
- jumping into water
- burning
- suffocation, e.g. plastic bag
- hanging and strangulation
- electrocution
- road and railway injuries.

Most of these modes are discussed in the appropriate chapters.

Suicidal knife wounds

Many incised and stab wounds are self-inflicted, either from motives of self-destruction, from mental aberrations or deliberately for some form of gain. These must be differentiated from each other, and from accidental and homicidal wounding.

Sometimes the distinction may be difficult and even impossible, but the experience of the forensic pathologist is paramount in assisting investigative agencies to come to the correct conclusion. Suicide, attempted suicide and suicidal gestures commonly employ cutting weapons as the means of injury. There are certain features that are quite reliable pointers to these motives, though they are by no means infallible:

- Suicidal knife wounds favour certain 'sites of election', which are predominantly the throat, the wrists and the front of the chest. As with most violent methods, cut throat and chest stabbing is predominantly seen in men – though cutting wrists is not uncommon in women.
- Suicidal wounds are typically multiple, often being characterized by a number of preliminary trial cuts, called 'tentative incisions'. These are most often seen on the throat and wrists, where the person often makes a series of shallow incisions, presumably hesitating while gaining courage to make a final decisive cut. In many suicidal attempts the subject abandons this method after a few trial incisions and uses some other method of self-destruction. Although the presence of tentative incisions is strong presumptive evidence of suicide, exceptions do occur, and the pathologist must take all other aspects of the scene into account before giving an opinion to the investigators. In fact, the almost absolute statements of some older textbooks that tentative incisions must indicate suicide, is to be disregarded. The author (BK) has dealt with two recent murders in which 'typical' suicidal injuries were present on wrist or throat causing considerable doubt to the investigators until other factors clarified the situation.
- A suicidal cut throat usually has these trial incisions; there may be only one or two, or there may be scores of trial cuts. If successful, there will be one or more deep incisions superimposed, which may destroy some of the previous shallow cuts. The classical description of the cut throat is of incisions starting high on the left side of the neck below the angle of the jaw, which pass obliquely across the front of the neck to end at a lower level on the right. This assumes that the victim is right-handed, the obliquity being reversed in a left-handed person. The cuts are said to be deeper at their origin, becoming shallower as they cross the throat, tailing off into surface cuts at the extremity.

  This description, though hallowed by repetition in many textbooks, is often incorrect and many cut throats have horizontal cuts that show no variation in depth at either end. Most suicides appear to raise the chin to provide better access to the throat, so that the skin is stretched when cut. This tends to cause straight-edged incisions, rather than the jagged cut (the so-called 'dentele' toothed incision) seen when a knife is drawn over loose skin. Throwing back the head moves the carotid bundle under the protection of the sternomastoid muscles and, if the cuts are confined to the centre of the front of the neck, only the larynx or trachea may be damaged, rather than large blood vessels.

  Death from a cut throat depends on the nature and extent of local damage to the neck. Severe haemorrhage



FIGURE 7.1 *Sites of election in violent suicide.*



FIGURE 7.2 *Homicidal cut throat, showing single slash with no tentative cuts. Clean-cut edges with no sign of repetitive strokes, severing muscles, larynx and some large vessels.*

from the jugular veins, or less often the carotid arteries, may lead to death from exsanguination. If the larynx or trachea is opened, then even relatively minor haemorrhage from local vessels may cause blockage of the airways by blood and clot, though many slashed air-passage victims survive. A rare cause of death is air embolism, caused by aspiration into cut jugular veins while standing or sitting with the neck at a higher level than the thorax. The possibility that the victim of a cut throat may have died from some unrelated cause must always be borne in mind. Many suicides either use multiple methods of suicide to ensure success – or may abandon the pain of a cut throat for some other mode, such as poison or a fall from a height.



FIGURE 7.3 *Gaping laceration in front of neck of a mental patient, who on leave from a psychiatric hospital, had used a frame saw to commit suicide (see also Figure 7.4).*



FIGURE 7.4 *Back of neck showing marks of the saw teeth around the laceration and medulla at the bottom (arrow). Mental patient who, on leave from a psychiatric hospital, had used a frame saw to commit suicide (see also Figure 7.3).*

- Deliberate cutting of the wrists is rarely effective as the sole method of suicide, but it is a common injury. Many suicides from other causes are seen at autopsy to have scars on the wrists from previous unsuccessful attempts or gestures. The usual site is on the flexor surface at the level of the skin flexion creases. As with the neck, there may be a number of shallow tentative incisions, but commonly several deep gashes are made without trial cuts. The left wrist is the more common target, because of right-handed dominance (86 per cent in men, 93 per cent in women).

As with the neck, there is a tendency for the victim to hyperextend the wrist before making the cut, which causes the radial artery to slip into the shelter of the lower end of the radius. The knife cuts may then miss major blood vessels and merely divide flexor tendons, though many cuts are too shallow to cause anything



FIGURE 7.5 *Homicidal cut throat, simulating a suicide. There are several apparently 'tentative cuts', but the deep penetrating central laceration and adjacent stab wound is atypical. The face is congested and shows some petechiae from prior pressure on the neck.*



FIGURE 7.6 *Suicidal cut throat. The wounds are horizontal, rather than the more common sloping-down from left to right in a right-handed person. The numerous 'tentative cuts' are the hallmark of self-infliction, though there are rare exceptions. The larynx has been entered and death was due to aspiration of blood into the air passages. The great vessels in the neck were undamaged.*



FIGURE 7.7 *Numerous self-inflicted cuts on the wrist, as part of a futile suicide attempt. Most of these attempts fail and the person turns to another method of self-destruction.*

but superficial damage. Most cut wrists are but an accompaniment to other more effective methods of self-destruction. Once again, the presence of tentative cuts, though very significant, cannot be unquestioningly accepted as an exclusion of homicide.

- Suicidal injuries of the chest are almost always stab wounds. Sometimes linear incised cuts are made over the precordium or more widely over the front of the chest; these may be multiple, parallel and sometimes criss-cross, but rarely do any serious damage. Stab wounds are usually over the left side of the chest where common knowledge places the heart, but they may be alongside the sternum or even on the right side. The wound is often single, but multiple wounds are not uncommon. Though naturally a series of severe wounds always raises the presumption of homicide, many undoubted suicides can inflict a number of injuries upon themselves, each potentially fatal. The author (BK) has seen a suicide in a doctor, where eight severe knife wounds of the lower chest had created a large external defect and detached a portion of liver.

  Suicidal knife wounds are not often made in the abdomen, though they do occur, sometimes to the extent of disembowelling. The author (PS) has seen a suicide of a person, who removed several meters of the gut through a single and relatively small incision before dying of exsanguination. There is usually frank mental abnormality present in these cases, which merge into the self-mutilation described below.
- Stab wounds of the neck are uncommon in suicide, but are recorded (such as those described by Gee and Watson 1989, where actual transfixion of the neck was achieved).



FIGURE 7.8 *Knife wounds of wrists in a suicidal attempt. Even though these are more severe than usually seen, no damage to the radial arteries was effected and death was the result of a subsequent cut throat. The victim was a woman of 31, unusual in that cut wrists and throat are much more common among men.*



FIGURE 7.9 *Suicidal stab wound of heart. The front of the chest is one of the suicidal sites of predilection; multiple stabs do not exclude self-infliction.*

- The position of the clothing in suicidal knife wounds is equivocal. It is more common for the self-stabber to lift the garments to expose the area of chest or abdominal skin to be attacked, but exceptions are common and the point has little diagnostic significance.

Suicidal firearm wounds

The characteristics of gunshot wounds are fully discussed in Chapter 8 but, as far as suicide is concerned, the following salient features may be repeated:

- Women rarely shoot themselves. In Britain, a shot woman is a murdered woman until proved otherwise, though – as always – exceptions do occur, especially in communities where firearms are commonplace, such as farming or hunting areas.
- The weapon must always be present.
- The range must be within arm's length, depending upon the nature of the weapon and excluding some mechanical device to fire the gun. The pathologist may be asked if a dead person could have reached the trigger of a rifle or long shotgun, which may have been placed against the neck, head or chest. Having first established that the entry wound was close contact, the length of the gun from muzzle to trigger can be measured and compared with the distance from wound to tip of finger. It must be remembered, however, that the length of the limb after death, especially if rigor is present, is not necessarily the same as in life when mobile joints and muscles may have allowed a slightly longer reach than that measured after death. Allowance must also be made for lateral or other flexion of the trunk, and mobility of the shoulder girdle before declaring dogmatically that the victim could not have fired the gun and therefore did not shoot himself.
- Sites of election are the temple, the neck, the mouth and the chest. Suicides rarely shoot themselves in the eye or abdomen. The lifting of clothing to expose bare skin, usually in the chest, is very variable, and has even less significance in differentiating suicide from homicide or accident than in knife wounds.
- Shooting in anatomically inaccessible sites cannot be suicide.
- It is not true that suicides always shoot themselves in the head on the same side as their dominant hand.
- It is difficult to differentiate homicide from accident, even though the circumstances may be suggestive. The distance of discharge may be beyond arm's reach in both, the weapon may be missing in both, inaccessible sites may be shot in both and sites of suicidal election may not be used in both.



FIGURE 7.10 *A combination of two suicide methods, by firearm and hanging. The man had stood on a stool with a noose around his neck and then shot himself through the forehead. The entrance wound is seen in the forehead (white arrow) and the double ligature mark around the neck shows ecchymoses on the ridge between the two furrows (black arrow).*

Suicide by submersion

This is a common mode of self-destruction, in both men and women. It has a marked geographical variation as a favoured method of self-destruction, naturally depending on the availability of water – it is relatively infrequent in Egypt, but very common in the west of Ireland.

Either large bodies of water, such as rivers, lakes or seas may be used – or the bathtub. The pathology of immersion deaths are dealt with in Chapter 16, but the following features will assist identifying suicides:

- Other means of self-destruction may also be present, such as drug overdose: in baths, associated electrocution is not uncommon, especially in the former West Germany (Bonte 1983).
- Suicide notes may or may not be present, but those who kill themselves usually remove top clothes, hats and spectacles that may be left on the river bank; as usual, exceptions are commonplace.
- Other injuries on the body may be the result of agonal or post-mortem damage in the water.

Suicide by burning

Heat injuries are dealt with in Chapter 11, but suicide from burns has recently increased in Western countries (where it was formerly almost unknown), though in Asia it has always been relatively common. The spread to the West followed political self-martyrdom modelled on that practised by some Vietnamese protesters. There are no particular medical features to distinguish suicide from accident or homicide, this being a circumstantial matter. It is almost invariable, however, for some container of inflammable accelerant to be within reach. The myth of 'spontaneous combustion' is discussed in Chapter 11.

Suicide by 'asphyxia'

The pathology is described in Chapters 14 and 15, but the following facts are pertinent to suicide:

- The masochistic or sexual asphyxias must be carefully distinguished from homicide and suicide. Some asphyxial deaths with sexual aspects appear to be suicidal in nature – or at least, the inevitability of a fatal outcome must have been apparent to the victim (Knight 1979).
- Hanging, though not usually truly asphyxial, is a common mode of suicide, especially (though not exclusively) in men. It is also common as a sequel to homicide, especially in domestic murders, where the perpetrator often commits suicide by this means.
- Plastic bag suicide is increasing in incidence, the means being universally available.
- Suicidal ligature strangulation is not uncommon and sometimes causes difficulty in differentiation from murder. The winding of several turns of ligature and the tying of multiple knots is still consistent with suicide, even though it is hard to understand how, in some cases, death appears to have been caused by reflex cardiac arrest rather than the more florid 'asphyxial' mode of death.

  Sometimes a stick or other object is inserted under a ligature and twisted to tighten the cord against the neck. This is called a 'Spanish windlass', the stick becoming jammed against the body to prevent the tightened ligature from becoming loose once the twisting is completed. Though usually suicidal, this device is sometimes used for murder.

Jumping from a height

'Precipitation' – jumping from a height – is another mode of suicide where the circumstances rather than the autopsy findings determine the motivation. It may sometimes be possible to deduce, by measuring the distance from the jumping point to where the body strikes the ground, the fact that the victim must have actively projected himself outwards rather than fallen close to the wall or cliff face. Some experiments on this aspect have been carried out (Goonetilleke 1980). The injuries may be variable, depending on the attitude of the body when striking the ground, contact with obstacles during the fall and the height of the drop.

Head injuries are common and are described in Chapter 5. If the fall is onto the feet, damage may occur at any point from the ankles to the skull. The legs may fracture, the hip joints may impact, the pelvis may split, the spine may be fractured (especially vertebral body compression, hyperflexion or hyperextension lesions), or the base of the skull may be imploded as a ring fracture.

It is extremely difficult, to the point of impossibility, to deduce the height of the fall from the nature and severity of the injuries, as was evident from the medical testimony in the Helen Smith inquest in Leeds in 1982.

Some persons will be killed from a fall from a standing height, whilst other may make remarkable escapes without injury from a very high fall. The rare survivals in falls from a great height – usually when some cushioning effect, such as snow, exists – may still defy mechanical explanation.

SELF-INFLICTED INJURIES OTHER THAN SUICIDE

Two main classes exist: those where some abnormality of mind leads the victim to mutilate his body – and those in which deliberate injuries are inflicted for motives of gain. Those caused by mental aberration are usually bizarre in either their multiplicity or their site.

Some mentally disordered persons may inflict hundreds of small wounds upon themselves, which may be additional to the actual cause of death, if death has taken place. Forensic physicians, such as police surgeons, may be called upon to examine living victims of this type.

The arms may be covered with scores of parallel superficial incisions from a knife, razor or broken glass. These may cross each other in groups and again are more frequent on the non-dominant side, usually the left. Small stabs may be made on the chest or temples. In a case seen by the author (BK), there were more than 200 knife-point stabs on each temple and the centre of the forehead. Another well-recognized syndrome is self-mutilation of the genitals, almost invariably by men. Paranoid schizophrenics, often with a strong religious flavour to their delusions, are known to attack themselves in this manner. The penis, scrotum and testes may be removed, and death from intractable haemorrhage can follow. In one of the cases illustrated, there was also perforation of the eyeballs and 40 stab wounds on the top of the head, as well as a complete circumferential cutting of the throat, all with the same blunt scissors that performed the castration. The forensic implications arose from



FIGURE 7.11 *Complete self-amputation of the scrotum and penis with scissors.*



FIGURE 7.12 *Self-mutilation thought by the police to be a bizarre homicide. The genitals have been amputated, the throat cut through 360°, the eyeballs punctured and the scalp stabbed many times, all with scissors. The dead man had paranoid delusions of a religious nature.*

the initial suspicions of the police that a sadistic homicide had taken place.

Self-inflicted injuries, usually non-fatal unless some complication has arisen, may be motivated by some form of gain. The most common is fabrication of injuries to simulate an assault, either to divert attention from the person's own theft or to arouse sympathy. Fabricated accidental injuries are usually a form of malingering, as in the armed forces, or in fraudulent attempts to obtain compensation. In other cases, the 'victim' may claim that a specific person assaulted them, from motives of hate or spite. Others may injure themselves and then waste police time by insisting on a futile search for a non-existent assailant, the motive often being impossible to discover, even by a psychiatrist.

Though these matters are usually seen by the clinical forensic physician, the pathologist may be asked for an opinion where no other medico-legal doctor is available, or if death supervenes. The so-called 'Münchausen syndrome' consists of repeated simulations of illness or the infliction of repeated minor injuries, with the object of gaining admission to hospital, or obtaining medical care and attention.

The following features assist in the recognition of self-inflicted incised injuries:

- The cuts are usually superficial and rarely any danger to life, unless they become infected. Occasionally, they may penetrate the full thickness of the skin, but not in sensitive areas like the face.
- The incisions are regular, with an equal depth at origin and termination, unlike more serious wounds that tend to be deeper at the start and tail off to the surface.
- The cuts are usually multiple and often parallel. They avoid vital and sensitive areas like the eyes, lips, nose and ears, usually being drawn on the cheeks and jaws, temples and forehead, sides of the neck, chest, shoulders, arms and backs of hands and thighs. This is inconsistent with an attack by another person, as the victim is unlikely to stand still to allow these multiple delicate and uniform injuries to be carefully executed.
- In right-handed persons, most of the injuries are on the left side, especially the sides of the face and left hand.
- When the incisions are made on areas covered by clothing, the relevant garments may show either no cuts or cuts that do not match the injuries in position or direction.



FIGURE 7.13 *Self-inflicted scissors injury around the full circumference of the neck.*



FIGURE 7.14 *Self-inflicted injury in an attempt to produce an excuse during shop-breaking. Surprised by the police, he cut himself with broken glass to claim that he had been assaulted by the robbers whilst trying to defend the premises. There were similar shallow, straight cuts on the other side of the face and on the backs of the hands.*


Avoids eyes, nose, mouth and ears
Parallel uniformly shallow cuts (more on left side)
Mostly on back or palm of least dominant hand
Left
Right
Forehead, neck, jaw and cheek (more on left side)

FIGURE 7.15 *Characteristics of non-fatal self-inflicted injuries.*



FIGURE 7.16 *Cuts on the backs of the hands in the man shown in Figure 7.14. He was right handed and most of the shallow incisions are on the left hand.*

In summary, the whole range of injuries and surrounding circumstances may suggest to the experienced pathologist that the lesions do not constitute a genuine assault. This diagnosis may be virtually immediate on first looking at the 'victim' and may be almost intuitive after some experience – though this is of little use when giving legal testimony, when every opinion has to be backed up by hard fact and reasoned opinion.



FIGURE 7.17 *Self-inflicted injury in the living. The 'victim' alleged that he had been attacked and robbed. The superficial, uniform, mostly parallel scratches avoid the eyes, nose and mouth.*



FIGURE 7.18 *Extensive self-inflicted cuts on the chest. The youth persistently claimed to the police that he had been attacked, but the cuts in his shirt were horizontal. He later confessed, explaining that he wanted to get his father's sympathy over some domestic crisis.*

The so-called 'Münchausen syndrome' and the 'Münchausen syndrome by proxy' lie within the realm of the forensic psychiatrist, but a pathologist or clinical forensic physician may be called upon to confirm – or even first detect – that the injuries are self-inflicted.

The Münchausen syndrome refers to adults who injure themselves or feign signs of illness, in order to gain medical attention and often admission to hospital. They can be a plague to casualty departments until recognized. More sinister is the Münchausen syndrome by proxy, where a parent will repetitively injure her child – occasionally fatally – to gain the same attention from doctors and medical facilities. The relationship with child abuse, of which it is a variety, must be recognized.

REFERENCES AND FURTHER READING

Anderson WR, Hudson RP. 1976. Self-inflicted bite marks in battered child syndrome. *Forensic Sci* **7**:71–4.

Asher R. 1951. Munchausen's syndrome. *Lancet* **1**:339–40.

Bonte W. 1978. [Ritual finger amputations. A contribution on the diagnosis of intentional self mutilation using an axe]. *Arch Kriminol* **162**:17–22.

Bonte W. 1983. Self-mutilation and private accident insurance. *J Forensic Sci* **28**:70–82.

Bonte W, Rudell R. 1978. [Accident or planned self mutilation? Probability of accidental injuries during chopping]. *Arch Kriminol* **161**:143–52.

Carney MW. 1978. Self-inflicted bleeding and bruising. *Lancet* **1**:924–5.

Dotzauer G, Iffland R. 1976. Self-mutilations in private-accident-insurance cases. *Z Rechtsmed* **77**:237–88.

Eckert WG. 1977. The pathology of self-mutilation and destructive acts: a forensic study and review. *J Forensic Sci* **22**:242–50.

Faller-Marquardt M, Ropohl D, Pollak S. 1995. Excoriations and contusions of the skin as artefacts in fictitious sexual offences. *J Clin Forensic Med* **2**:129–35.

Fanton L, Schoendorff P, Achache P, *et al.* 1999. False rape: a case report. *Am J Forensic Med Pathol* **20**:374–7.

Gaillard Y, Pepin G. 1998. Case report of an unusual use of lidocaine during episodes of self mutilation. *J Forensic Sci* **43**:235–8.

Gatter K, Bowen DA. 1980. A study of suicide autopsies 1957–1977. *Med Sci Law* **20**:37–42.

Gee DJ, Watson A. 1989. *Lecture notes in forensic medicine*, 5th edn. Blackwell Scientific Publications, Oxford.

Gibbon KL. 1998. Munchausen's syndrome presenting as an acute sexual assault. *Med Sci Law* **38**:202–5.

Goonetilleke UK. 1980. Injuries caused by falls from heights. *Med Sci Law* **20**:262–75.

Greenspan GS, Samuel SE. 1989. Self-cutting after rape. *Am J Psychiatry* **146**:789–90.

Guarner J, Hanzlick R. 1987. Suicide by hanging. A review of 56 cases. *Am J Forensic Med Pathol* **8**:23–6.

Halprin KM. 1966. The art of self-mutilation. I. Neurotic excoriations. *JAMA* **198**:777.

Halprin KM. 1966. The art of self-mutilation. II. Delusions of parasitosis. *JAMA* **198**:1207.

Harris CN, Rai K. 1976. The self-inflicted wrist slash. *J Trauma* **16**:743–5.

Jordan FB, Schmeckpeper K, Strope M. 1987. Jail suicides by hanging. An epidemiological review and recommendations for prevention. *Am J Forensic Med Pathol* **8**:27–31.

Karger B, DuChesne A, Ortmann C, *et al.* 1997. Unusual self-inflicted injuries simulating a criminal offence. *Int J Legal Med* **110**:267–72.

Kleiner GJ. 1984. *Suicide in pregnancy*. John Wright, Bristol.

Knight B. 1979. Fatal masochism – accident or suicide? *Med Sci Law* **19**:118–20.

Knight BH. 1968. Two cases of self-inflicted injuries in the living. *Med Sci Law* **8**:264–6.

Kohr RM. 1990. Suicide by chloroform ingestion following self-mutilation. *Am J Forensic Med Pathol* **11**:324–8.

König H. 1996. [Discrimination of sharp injuries produced in order to feign assaults and such of real cases]. In: Saternus KS, Kernbach-Wighton G (eds), *Research in Legal Medicine*. Schmidt-Römhild, Lübeck.

Koops E, Puschel K. 1990. [Self-mutilation and autophagia.] *Arch Kriminol* **186**:29–36.

Leslie J, Taff ML, Patel I, *et al.* 1984. Self-inflicted ocular injuries. A rare form of self-mutilation. *Am J Forensic Med Pathol* **5**:83–8.

Peschel O, Betz P, Eisenmenger W. 1997. Self-mutilation with needles. *Med Sci Law* **37**:175–8.

Pollak S, Saukko P. 2000. Clinical forensic medicine. Self-inflicted injury. In: Siegel JA, Saukko PJ, Knupfer GC (eds), *Encyclopedia of Forensic Sciences*. Academic Press, San Diego, San Fransisco, New York, Boston, London, Sydney, Tokyo.

Püschel K, Hildebrand E, Hitzer K, *et al.* 1998. [Self-mutilating hand and finger injuries among physicians suspected of insurance fraud]. *Versicherungsmedizin* **50**:232–40.

Riepert T, Schneider P, Urban R. 1999. [Self-injury or attempted murder – analysis of an unusual case.] *Arch Kriminol* **203**:19–26.

Rothschild MA, Raatschen HJ, Schneider V. 2001. Suicide by self-immolation in Berlin from 1990 to 2000. *Forensic Sci Int* **124**:163–6.

Shiono H, Takaesu Y. 1986. Suicide by self-inflicted stab wound of the chest. *Am J Forensic Med Pathol* **7**:72–3.

Sneddon I, Sneddon J. 1975. Self-inflicted injury: a follow-up study of 43 patients. *Br Med J* **2**:527–30.

Tsunenari S, Idaka T, Kanda M, *et al.* 1981. Self-mutilation. Plastic spherules in penile skin in Yakuza, Japan's racketeers. *Am J Forensic Med Pathol* **2**:203–7.

Zlotnick C. 1999. Antisocial personality disorder, affect dysregulation and childhood abuse among incarcerated women. *J Pers Disord* **13**:90–5.

CHAPTER 8

Gunshot and explosion deaths

- The mechanics of missile injury 245
- Types of weapon 246
- Wounds inflicted by a smooth-bore shotgun 249
- Wounds from rifled weapons 258
- Exit wounds 267
- Firearm damage to internal organs 270
- Estimating the range of discharge 270
- Airgun injuries 271
- Humane (veterinary) killers and industrial 'stud-guns' 272
- Rubber and plastic bullets 274
- Deaths from explosion 274
- References and further reading 277

Though the majority of missile wounds are caused by firearms, other devices such as crossbows, captive-bolt guns, air weapons and even catapults can launch lethal projectiles. In the bombing deaths now so commonly associated with terrorism, missile fragments cause more deaths than the blast effects, so, overall, an understanding of projectile trauma is essential.

THE MECHANICS OF MISSILE INJURY

With the exception of deceleration injuries, all mechanical trauma, whether punching, stabbing or kicking, is caused by the transfer of energy from an external moving object to the tissues and nowhere is this more obvious than in shooting. For damage to occur, some or all of the kinetic energy of the missile has to be absorbed by the target tissues, where it is dissipated as heat, noise and mechanical disruption. When a missile passes completely through soft tissues, it may retain much of its original kinetic energy and fail to transfer any appreciable amount to the tissues, which may remain relatively intact apart from the immediate bullet track. If the latter is in a limb muscle, there may be no serious effects if major blood vessels are not involved, though the same track in brain, lung or heart may prove fatal.

To ensure transfer of energy to the tissues, some missiles are especially designed or modified to slow up or stop within the body. Soft-headed bullets will flatten on impact and some are designed to fragment. The 'dumdum' bullet, which has a scored nose, and the military missile with an air-cavity within the tip are intended to splay open on impact to increase the 'braking' or deceleration effect, and transfer more energy for disruption. Explosive-tipped bullets, such as those used in the assassination attempt on President Reagan, are not designed to cause damage by the tiny detonation, but drastically to deform the missile to cause maximum deceleration. Weapons designed to be fired in confined spaces, such as those for combating hijack attempts in an aircraft, may be of relatively low velocity and have a deceleration feature incorporated to ensure the absence of an exit wound, and thus limited travel of the missile to avoid puncture of the pressurized passenger cabin.

The trajectory of the missile also determines how much and how fast its energy is given up to the target. Shotgun pellets are spherical, so the orientation of impact is not relevant, but all conical bullets may acquire an erratic course in the tissues. They may tumble end-over-end, especially when nearing the limit of range; they may 'wag' or 'yaw' from side to side of their axial trajectory; the base may rotate around the axis, with the tip remaining on the straight path; and they may 'precess' or 'nutate' with complex spiral or circular movements about the axis.

Whatever the deviation, it offers more contact between the projectile and the tissues, allowing more transfer of energy and thus greater tissue damage. The amount of kinetic energy possessed by a projectile accords to the familiar formula of half the product of the missile mass and the square of its velocity. Modern military science takes advantage of the squaring of the velocity to develop weapons that have a missile of small mass but exceedingly high velocity to provide the maximum kinetic energy for tissue damage.

The mode of injury depends on the velocity of the missile. Relatively slow projectiles are those travelling at up to the speed of sound in air (340 metres/second or 1100 feet/second), which of course includes all non-explosively propelled missiles like crossbow bolts and air-rifle pellets, as well as most revolver bullets. These mechanically thrust aside the tissues along a track only slightly wider than the missile. The tissues are lacerated or crushed, secondary damage occurs from rupture of blood vessels and other structures, and secondary and tertiary damage is caused by displaced bone and cartilage fragments.

Above the speed of sound in air, a missile passing through tissue sends a shock wave of compression ahead of the laceration track, this wave being propagated at about the speed of sound in water (1500 metres/second or 4800 feet/second). Though this wave lasts only for a brief period, it raises the tissue pressure to extreme values, up to thousands of kilopascals. In tissues like brain, liver and muscle, this can cause severe disruption within a wide zone around the bullet track, and can be propagated down hollow fluid-containing vessels to cause distant vascular damage.

High-velocity projectiles produce yet another phenomenon, that of cavitation. The missile accelerates the molecules of the tissues adjacent to the track, so that they continue to move centrifugally outwards even after the missile has travelled onwards. This forms a cavity around the track that is far wider than the diameter of the projectile. It reaches a maximum size within milliseconds and then pulsates with decreasing amplitude so that a fusiform cavity rapidly follows in the wake of the bullet. When the bullet stops or leaves the organ, the cavity rapidly subsides, but the track of damage persists in a tubular zone much wider than the actual missile. In high-velocity bullets from military weapons – for example, 980 metres/second (3185 feet/second) this cavitation effect is the most damaging mechanism; in addition to the physical damage, the near-vacuum sucks infected dirt and clothing fibres into the depths of the wound (Owen-Smith 1981). Solid organs such as brain and liver are affected more than spongy matrices like lung. Those tissues that contain most water are most severely damaged by penetrating missiles and high-velocity missile damage is proportional to the specific gravity of the tissue injured.

In most of the shooting cases seen by forensic pathologists, death will have occurred rapidly but, where it is delayed, secondary damage from infarction, local necrosis of muscle and organs, and infection must always be borne in mind. High-velocity weapons in particular can cause vascular damage at a distance from direct trauma, stretching and thrombosis, leading in turn to ischaemic lesions such as infarcts.

TYPES OF WEAPON

The nature of firearm wounds varies considerably with the type of weapon employed. A general knowledge of the main features of the various types of gun in common use is essential, though there is no need for the pathologist to master the unnecessary mass of detail on firearm construction offered by some forensic medicine textbooks. Indeed, much of this is solely the province of the firearms examiner, not the doctor. The inordinate amount of detail sometimes provided is perhaps symptomatic of the fascination which firearms hold for many men – but rarely women.

In the context of wounding, guns are of two main types.

The smooth-bore weapon or 'shotgun'

A shotgun consists of one or more metal barrels of relatively wide diameter, which are smooth on the inner surface. They fire a variable number of spherical lead shot (pellets), which emerge from the end (muzzle), from where they gradually diverge in the form of a long, narrow cone. Exceptionally, a shotgun may fire a few large projectiles or even a single slug, but these are rarely met with in forensic practice, the usual load of pellets totalling scores or hundreds. Special types of projectile are described later. A shotgun often has two barrels, either side by side or 'up-and-under'. One barrel may be parallel sided (the 'cylinder') and the other slightly tapered towards the muzzle (the 'choke'). The latter will produce a narrower cone of shot and this affects estimates of range derived from the size of the wound. There are several gradations of choke, such as 'improved cylinder', 'modified choke', 'half-choke' and 'full-choke'.

Some modern weapons have the facility for removing one particular type of barrel and replacing it with another degree of choke. Modern accessories can convert a cylinder barrel to a choke barrel – for example, variable choke such as Poly-Choke, Kutts Compensator and Weaver-Choke are available, especially in the USA.



FIGURE 8.1 *Types of smooth-bore weapon.*



FIGURE 8.2 *Relative calibre of common weapons.*

Another typically American modification is the ability to fire a single projectile through the smooth bore. A number of devices intended for hunting are available, but they may be involved in a human fatality. One of the older types is the solid round ‘pumpkin ball’ or the Brenneke rifled slug, but more recent devices include the Foster rifled slug and the French Blondeau, which is a dumb-bell-shaped projectile.

Shotguns come in two main sizes, which determine the nature of the wound. The first is the ‘twelve-bore’, usually called ‘twelve-gauge’ in North America, which has a diameter of about 19 mm or 0.738 inches. The other is the smaller ‘four-ten’, usually single-barrelled with a diameter of 10.6 mm or 0.410 inches.



FIGURE 8.3 *Various types of ammunition. From the right, there are two twelve-bore shotgun cartridges, .22 rifle, .38 automatic pistol and .45 revolver bullets and two military rifle shells. On the left is a cannon shell, which is unlikely to be encountered in civilian forensic pathology.*



FIGURE 8.4 *Types of weapon and ammunition.*

SHOTGUN AMMUNITION

The ammunition for the shotgun is a cartridge made of a cardboard or plastic cylinder fitted into a metal base. This carries a percussion detonator that is struck by the spring-loaded firing pin when the trigger is pulled. The cartridge contains a charge of propellant, above which are ‘wads’ or pistons of felt, and cardboard or plastic discs, or both. Above these is the charge of shot, which varies greatly in number and size, finally covered by a card or plastic disc.

This description is of the old, classical cartridge but modern ammunition has a variety of devices incorporated into the cartridge to improve efficiency and accuracy. These include the Power Piston, a proprietary name for one of a class of cartridges which holds the shot inside a polythene cup and which itself may contribute to the wound at short range. Other modern cartridges may have plastic granules as a filler between the shot; this brightly coloured material may be found inside the wounds.

Tampering with the contents of cartridges may markedly alter the spread and other characteristics of the shot and hence the resulting wound. The shot may be fused into a mass by pouring paraffin wax or even molten pitch into the cartridge. The cardboard or plastic cylinder may be partly cut through at the level of the wads, so that, on firing, the upper part of the casing is blown out to restrain the divergence of the pellets.

The propellant has also changed in recent years, so that the old black gunpowder has been largely replaced by cleaner explosives that do not produce the same volume of soot and unburnt propellant, which may be deposited in and around the close-range wound.

‘Country’ guns

In developing countries, in some rural and poor areas of other countries, in subversion and terrorism, and sometimes in juvenile hands, weapons and ammunition may be ‘home-made’. These are common in India, where the name ‘country gun’ is well understood; they are also made in Sri Lanka and other Asian areas, but may be encountered anywhere.

The author (BK) had experience of such weapons in the terrorist campaign in Malaya in the 1950s, where crude weapons were made in the jungle from pieces of water-pipe attached to roughly carved wooden stocks, with a primitive firing mechanism. The guns were muzzle-loaded with black powder and the projectiles were often wood-screws, nuts and bolts and irregular fragments of metal or even stones.

In civilian practice in Britain, two similar weapons have been seen, both made by juveniles out of electrical conduit pipe, using potassium chlorate–sugar propellant. In one, the user was killed when the device exploded; the other one successfully propelled a small screwdriver across several fields to (slightly) injure a cow.

Terrorists in Northern Ireland have also manufactured some of their own weapons, but these were relatively sophisticated, being made in clandestine but well-equipped workshops.

The problem for the pathologist with such guns is that few of the criteria to be described apply to the injuries, especially where random, irregular missiles such as wood-screws are employed. Local knowledge and experience are essential for the interpretation of these wounds.

The rifled weapon

Handguns, rifles, air rifles and military weapons differ from shotguns in that they fire one projectile at a time through a thicker barrel that has spiral grooves machined on its inner surface. The elevations between the grooves are the ‘lands’, which grip the bullet as it passes down the barrel and give it a rotatory movement. This has a gyroscopic effect that increases the stability of the bullet’s trajectory and hence the accuracy.

Handguns, which cause over 50 per cent of all homicides in the USA, comprise the revolver and the automatic pistol. The revolver has a rotating cylinder carrying a variable number of shells, which are brought into the firing position one by one, each time the trigger is pulled. The revolver has a low muzzle velocity of the order of 500 feet/second (150 metres/second). The ‘automatic’, more accurately called a ‘self-loading’ pistol, has its shells in a spring-loaded magazine, each spent round being ejected and a new one positioned by means of the gas pressure developed at each discharge. The muzzle velocity may be 1000–1200 feet/second (300–360 metres/second).

Rifles are long-barrelled guns that may be single-shot, bolt-loaded or self-loading and used for hunting, target-shooting or for military purposes. Military weapons come in a vast range of types, most of them now either ‘self-loading’, which means that the trigger has to be pulled for each shot – or truly ‘automatic’, when the weapon will continue to fire while the trigger is depressed until the magazine is empty. The muzzle velocity varies greatly, from 1500 to 5000 feet/second (450–1500 metres/second).

AMMUNITION FOR RIFLED WEAPONS

The variety of types of rifled ammunition is even greater than the range of weapons designed to fire them, but all conform to a general pattern. There is a metal cylinder, closed at one end, which is the ‘shell’ or cartridge, carrying a percussion detonator in the base, either centrally or peripherally. The shell is loaded with explosive propellant such as nitrocellulose and the bullet is firmly clamped into the open end. The bullet may be composed of a variety of metals, often compound. A lead core may be covered in a nickel or steel jacket, but there are many other variations. The detonator may contain elements such as barium, bismuth mercury or antimony.

Both shotgun and rifled weapon ammunition have a common purpose when detonated – to produce large volumes of hot gas under pressure that expel the bullet or shot from the barrel. One gram of black powder produces about 3000 ml and nitrocellulose produces some 13 000 ml of gas, which consists of carbon dioxide, monoxide, nitrogen, hydrogen sulphide, hydrogen, methane and many other substances, all at high temperatures.

WOUNDS

Though the construction and performance of weapons is of vital interest to the forensic firearms examiner, the relevance to the pathologist is concentrated in those aspects which affect the nature of the wound:

- whether the weapon is smooth-bore or rifled;
- if rifled, the muzzle velocity of the weapon;
- the nature of the projectile(s);
- the nature of the propellant;
- the degree of choke, if any;
- the range of discharge;
- the angle of discharge.

WOUNDS INFLICTED BY A SMOOTH-BORE SHOTGUN

The following constituents of the cartridge emerge on the discharge of a shotgun and all may contribute to the wound:

- lead pellets
- soot in the form of smoke and debris
- unburnt and burning propellant particles
- flame and hot gases under pressure
- carbon monoxide
- wads – either felt, cardboard or plastic
- detonator constituents
- fragments of the cartridge case.

When a shotgun is fired, a compact mass of shot emerges from the muzzle and then begins to disperse, the divergence increasing progressively as the distance lengthens. A tongue of flame and hot gas follows the shot. High pressure and temperature exists just outside the muzzle, but this rapidly expands and cools. This gas is composed of oxides of nitrogen, carbon dioxide, hot air and other compounds, but the one of interest to the pathologist is carbon monoxide. Soot from the combustion of propellant is expelled, along with some flakes or grains of propellant that may be still burning. The wads are also expelled, their nature depending upon the type of cartridge. Some modern ammunition may contain other devices that may contribute to the wound.

Chemical traces of the elements in the detonator or percussion cap cannot be seen, but may be vital laboratory evidence, where barium, antimony and other metals can be recovered on analysis or by means of the scanning electron microscope. Fragments of the cartridge case may also be ejected, especially if it has been tampered with, as described earlier.

The most important deduction that a pathologist is asked to make is the estimation of the range of discharge of the gun, as this may substantially influence the distinction between accident, suicide and homicide. The appearance of the wound is greatly modified by variation in range and it is convenient to describe them in terms of increasing range of discharge.

Shotgun contact wound

SHAPE

Where the muzzle is placed tightly against the surface of the abdomen, thorax, limb or neck, the consequent wound will



FIGURE 8.5 *Variation in appearance of a shotgun wound at increasing range of discharge: 1(a), split wound from contact over bone; 1(b), usual round contact wound; 2, close but not contact range up to about 30 cm (variable); 3, 'rat-hole' wound from 30 cm to about a metre (variable); 4, satellite pellet holes appearing over a metre; 5, spread of shot increases, central hole diminishes; 6, uniform spread with no central hole over about 10 m. All these ranges vary greatly with barrel choke, weapon and ammunition.*

be single and circular, of a size approximately equal to the bore of the weapon, though a .410 wound may be smaller because of the relatively greater effect of elastic contraction of the skin. The edges of the wound may be crenated by individual shot, but usually this feature is not noticeable.

SOILING AND BURNING

In a tight contact wound, the skin forms a seal around the muzzle, preventing much escape of hot gas and soot, so that soiling and burning are minimal or absent. The recoil, which takes the muzzle away from the skin, may, however, loosen the seal and, if the muzzle is not pressed firmly, flame, gas and soot may escape sideways and affect the skin in the immediate vicinity. Where clothing is interposed between the muzzle and skin, soot is much more likely to escape sideways and may be found in each layer of fabric, as well as on the underlying skin. The cloth may be singed at the edge of the hole and there may be a ring of burning around the skin wound.

MUZZLE IMPRESSION

There may be a muzzle impression in a tight contact wound made by firm mechanical pressure or impact of the metal rim against the skin. Many textbooks quite wrongly attribute this to 'recoil', though of course recoil takes the muzzle away from the skin, not towards it. The true explanation of a muzzle mark is either that the assailant physically kept the weapon pressed hard against the skin or – more often – that the subcutaneous expansion shortly to be described, lifts the skin forcibly up against the muzzle. A muzzle mark is a most useful indication to the pathologist of a contact wound. Actual bruising can occur around the muzzle imprint, though this is more likely to be the result of deep contusion from the effects of the blast. Rarely, a double-barrelled weapon may make a ring-like mark adjacent to the entry wound.



FIGURE 8.6 *Soot-soiling of hand that had grasped a shotgun barrel.*

CARBON MONOXIDE

Carbon monoxide in the gases combines with haemoglobin and myoglobin to give a pink coloration to the interior of the wound track and adjacent tissues. This diminishes in concentration along the track, but can still be present in its depths – and even at an exit wound, if there is one. The presence of carboxyhaemoglobin and myoglobin has been advocated as a test for distinguishing the exit from the entrance wound, especially where decomposition has blurred the morphological appearances. This test must be used with caution, though if quantitative measurements are made it can still be a valid exercise.

CONTACT WOUNDS OVER BONE

When the wound is made over a site with underlying bone, the wound may have a different appearance. Especially in



FIGURE 8.7 *Homicidal firearm wound with a twelve-bore shotgun. The wound shows a clear muzzle impression, the barrel having been pressed against the skin at discharge. There is almost no smoke soiling, the muzzle having forced a firm seal against the thin shirt and skin.*

the scalp, but also over the back of the neck, sternum, shoulder, hip and other areas where the soft tissue lies thinly over bone, the large volume of discharge gases cannot dissipate, as they can into the abdomen, chest, or mass of muscle. When the gas is forced through the skin, it is reflected back by the underlying hard layer and momentarily raises a dome of skin and subcutaneous tissue. This is rammed back against the muzzle to increase the pressure of contact further, sometimes producing a muzzle mark. When the gas volume is large, as with a twelve-bore gun, this dome may then split, causing a cruciate, stellate or ragged wound, with skin flaps. This is less likely with a .410 because the cartridge is smaller, but it can occur, as of course it can with rifled weapons.

The close discharge of a shotgun

When the muzzle is held near the skin, but not actually in contact with it, a number of helpful signs are produced. Once again the appearance is naturally modified by clothing, which must always be carefully preserved and subjected to forensic scientific examination. Where clothing is present, then it will trap most, but not necessarily all, of the soot and powder grains. It will reduce the flame effects, though if the fabric is ignited even momentarily, this can diffusely scorch the skin.

Assuming that the body surface is uncovered, a close discharge – one between actual contact and about 15 cm (6 inches) – is likely to show the following features:

- Singeing of hairs around the wound, unless the skin is hairless. The fine downy hairs of the trunk and limbs may be burnt away, though this is unlikely with dense, long, head hair. Where the distance is greater, the keratin of the hair may melt with the flame and then solidify on cooling, causing a 'clubbed' appearance of the hairs because of rounded bulges at the tips.
- Burning of the skin, unless protected by head hair. There may be a wide flare or narrow rim of hyperaemia or even blistering from the flame of incandescent gas blown from the muzzle.



FIGURE 8.8 *Suicidal firearm wound from a twelve-bore shotgun. The wound shows a muzzle impression with soot soiling, the double-barrelled shotgun having been pressed against the skin at discharge.*



FIGURE 8.9 *Firm contact wound from a twelve-bore shotgun. The clothing has prevented any soot soiling, but there are minor peripheral abrasions from impact of a belt. As the abdomen was distensible, the gas expansion has not caused splitting of the skin at the wound edges.*



FIGURE 8.10 *Contact wound from a twelve-bore shotgun fired through clothing. There is some abrasion of the wound edges, but no irregularity from the close-packed pellets, which have not begun to disperse. The clothing has protected the skin from smoke and powder soiling. The circular wound indicates discharge at right angles to the body surface.*

- The tissues within and around the wound may be cherry-pink from absorption of carbon monoxide.
- There will be 'smoke soiling' or 'soot staining' of the skin, from carbon deposition. This spreads more widely than powder tattooing, but does not carry as far as the heavier propellant grains. This effect is much less or even absent with modern 'clean' propellants.

  This soot or smoke soiling is easily washed off the skin, and care must be taken at autopsy to obtain all photographs and trace samples before allowing the bloodstains to be washed from the body. Tattooing will not wash off, though adherent unburnt propellant may be physically detached from the tiny burns during any washing or swabbing process.
- Burning, partly burnt and unburnt propellant flakes and grains may pepper the surrounding of the wound. As stated above, these carry further than smoke staining, but usually spread over a smaller area. The incandescent particles cause small burns on the skin, but the unburnt flakes (such as nitrocellulose) may be seen as small glistening particles on the skin, sometimes coloured.
- The wound will be circular if the weapon is held at right angles to the skin and elliptical if slanted, often with undercut edges on one side. Depending partly on the size of the pellets, 'nibbling' or crenation of the edge may be seen, though this is usually imperceptible in close discharges. The edge of the wound will be blackened and there will be soot in the exposed tissues. There may be annular bruising around the wound and distant bruising a few centimetres away as a result of tissue damage from the entry of gases. Other bruises or abrasions may be seen in the vicinity from objects such



FIGURE 8.12 *Suicidal twelve-bore shotgun wound. The entrance is in one of the 'sites of election', in the neck, and the circular smoke fouling indicated a close or even contact discharge.*



FIGURE 8.11 *Close-range twelve-bore shotgun wound of the head. This homicidal discharge was made through thick layers of fabric, which has filtered out any smoke or powder soiling. However, there is a wide zone of skin burning due to the muzzle gases. The wound is oval due to the downward angulation of the weapon.*

as buttons or buckles being hurled against the skin by the gas pressure.

- Any felt or cardboard wads or plastic cups from the cartridge will be within the depths of the wound.



FIGURE 8.13 *Suicidal twelve-bore shotgun wound. The entrance is one of the 'sites of election', in the neck (see Figure 8.14).*

Short- to mid-range shotgun discharge

From about 15 cm (6 inches) to 2 m (6 feet), considerable variation occurs in the appearance of the wound. The shorter range will provide a similar picture to that of close discharge, but the soot soiling diminishes and over 20–40 cm it may vanish. Powder tattooing near the wound periphery may persist for somewhat further than this.

At the upper end of this range the edges of the wound will become crenated and scalloped, especially with larger shot. This is sometimes called the 'rat-hole' or 'rat-nibbling' from its resemblance to rodent teeth marks. From 2 m upwards, the number of satellite pellet holes will progressively increase around the main wound.

It must be emphasized that these are useful generalizations, but that marked variations occur between different weapons, different barrels of the same weapon and different ammunition fired from the same gun. Only test firing can give a measure of the length of the flame, the distance and pattern of soot staining and powder tattooing, the beginning of pellet spreading and the distance over which the wads are projected. As a rough rule-of-thumb, which is often incorrect, hair singeing occurs over the first 30 cm (1 foot), soot staining can be seen for the first half-metre (20 inches) and a single large hole persists for at least 1 m (3 feet).

Mid- to distant-range shotgun wounds

Here, test firing is even more vital for an estimate of range, as the variation is great. The choke as opposed to cylinder barrel on the same gun will provide different appearances at



FIGURE 8.14 *Suicidal contact entrance wound in the neck. One barrel of a double-barrelled shotgun was used, the unfired barrel causing a muzzle mark (see Figure 8.13).*



FIGURE 8.15 *Suicidal twelve-bore shotgun wound. Not all such wounds are circular – this one has torn a large defect in the chest wall because of its tangential orientation. The smoke smudging is extensive, having overshot and been deflected from the wound interior. The precordium is another site of election for suicidal shooting.*



FIGURE 8.16 *Characteristic capital 'X'-shaped bruise caused by opening up of the plastic cup containing the shotgun pellets and surrounding the circular entrance wound from a homicidal short-range discharge.*

the same range. Once beyond 2 m, there will be no burning or smoke staining, rarely will there be powder tattooing and the presence of the wads will be variable. Sometimes the latter fall away within 2 m, but they can sometimes be found in a wound up to 5 m distant. Often the wad takes a lower trajectory and may strike the body below the shotgun wound. It may penetrate the skin, causing a second lacerated wound or it may only bruise the skin. Some of the plastic cup devices now used open up in flight to form a square-edged star or capital 'X' shape. This can strike the skin at or near the shotgun wound and produce a characteristic bruise or abrasion of a similar shape. The spread of pellets, which usually begins at a metre or two range, increases progressively, the central 'rat-hole' diminishing at the same rate.

There is an old (and extremely inaccurate) rule-of-thumb which states that the diameter of the spread in inches is roughly equal to the range in yards (metric: one-third of the spread in centimetres equals the range in metres). This of course applies to a circular wound or the narrow diameter of an oblique elliptical wound; it is of no use other than a quick first check to indicate if suicide can be excluded, but expert examination and test-firing are essential.

At distant ranges, beyond 6–10 m, the central hole may shrink to nothing. There will naturally be no wad injuries, no smoke, flame or tattooing, and no way of determining range except to say that it must be within the maximum discharge distance of that particular weapon, which may be 30–50 m. At such ranges the shot will not be lethal and the pellets, if they penetrate the skin, will lie just in the subcutaneous tissues. Death may occur, however, from an unlucky shot in the eye or from natural disease precipitated by pain and shock.

The direction of a shotgun injury

It has already been stated that, where the discharge has been at right angles to the body surface, the shape of the wound will be symmetrical and circular. A shotgun blast traces out a shallow cone from the muzzle and simple geometry demands that where this cone intersects a plane (the skin), a circle will result only when the cone is at 90° to the plane. In all other positions an ellipse will be traced out, its elongation increasing as the angle between them decreases. This pattern applies not only to the pellet spread but to soot deposition and provides a ready indication of the direction. In addition to the surface features, the internal wound assists in orientating the discharge:

- The wound edges may be shelved, the tissues being undercut below the margin distal to the origin of the



FIGURE 8.17 *Shotgun wound from a twelve-bore weapon. The circular outline indicates that the discharge was perpendicular to the skin surface. The central hole was caused by the entry of a confluent mass of shot, though there were no wads in the wound. The diameter of the peripheral pellet pattern was about 12 cm, which suggests that, approximately, the range was about 4 m. Test firing must always be carried out, however, to obtain a more exact estimate. Whatever the actual range, it is clear that it could not be suicidal.*



FIGURE 8.18 *Homicidal close-range shotgun wound from a twelve-bore weapon.*

discharge. The appearances are similar to those seen in some knife wounds, where an oblique stab leaves tissue visible at one edge and undercut on the other. In firearm wounds this is better seen in injuries from a single rifled projectile than from the more diffuse mass of shotgun pellets, but is still sometimes apparent in the latter.

- The track of the wound in the deep tissues can be established and this line projected backwards to indicate the discharge direction relative to the body. Again, a missile from a rifled weapon usually gives a clearer picture than those from a shotgun, but a general estimate can be obtained from a knowledge of the positions of the surface wound and the mass of pellets. Examination of a radiograph may be of more assistance that the laborious search from pellets at autopsy. Whatever the type of missile(s), considerable deviation caused by deflection by bone and other tissues can occur, so that the final resting place of the projectile may be far off the initial track. Thus the actual path through the tissues before ricochet must be established, if possible.

Other features of shotgun wounds

- Exit wounds are uncommon in the trunk as the energy possessed by each pellet is small because of its tiny size and the relatively low muzzle velocity of the weapon. The 'four-ten' will almost never exit and even the twelve-bore rarely causes a through-and-through wound of the adult chest or abdomen. The pellets often penetrate the distal chest wall, but are held up beneath the skin of the further side of the trunk. Commonly a bruise may be seen in the deep tissues of the frustrated exit site and lead shot may be felt under the skin, which is tough enough to prevent the final exit phase.

  In the head, neck and limbs, and in children and small thin adults, the twelve-bore commonly causes an exit wound which may be extremely large and ragged, with gross tissue destruction exposed. One of the most common is that seen when a twelve-bore is discharged suicidally into the mouth; this may disrupt the head, and expel most of the brain through a massive skull and scalp defect – the so-called 'burst head'.
- The internal track is more diffuse than that caused by a rifled weapon, though where the discharge is contact or close, the compacted mass of shot travels as a unit



FIGURE 8.19 *Pellet injuries from a distant twelve-bore shotgun discharge. The range was about 25 m and the shot lies just under the skin. Death was caused by coronary heart disease, cardiac arrest being precipitated by the shock of injury.*



FIGURE 8.20 *Tangential shotgun wound of face. The edge of the dispersal cone of pellets and gas has ploughed through the cheek, and removed the ear. The facial bones and base of the skull were fractured.*



FIGURE 8.21 *Shelving and undercutting of entry wound in oblique discharge.*

for some distance into the tissues before dispersing. In general, the internal damage caused by a shotgun is diffuse and is caused by direct mechanical disruption by the gas and shot, which enter at relatively low velocity. There is no cavitation effect as is seen in high-velocity injuries, the tissue being physically smashed by the impact of a heavy load of pellets and, in the case of near discharges, by the large volume of hot propellant gases.

- Secondary damage is caused by the mass of pellets striking bone and releasing fragments that then act as secondary missiles, damaging adjacent tissues and sometimes emerging to form exit wounds. These may sometimes cause confusion to inexperienced observers, including police officers, who may wrongly suspect multiple shots or the use of some other type of weapon.
- Wad wounds can be caused by the non-metallic contents of a shotgun cartridge. These can vary from trivial bruises to fatal lacerations. The latter may occur when a blank cartridge is discharged at close range, the wad and accompanying gas breaching the body surface. As mentioned earlier, the new devices now often used in shotgun ammunition may cause characteristic wounds, such as the square cruciate mark from the wings of the opened plastic cup which contains the shot. Felt and plastic wads travel a variable distance from the gun muzzle, depending on many factors, such as the type of cartridge, the amount of propellant load and the nature of the wads. The wads fall away much more quickly than the lead shot because of their low weight and high air resistance. At contact and close ranges



FIGURE 8.22 *A tangential shotgun wound of the side of the chest. When the victim was first found it was not appreciated that he had been shot. The discharge passed under the slightly abducted arm, injuring the upper arm as well as the thorax. Though most of the shot passed to the rear of the victim, some were found in the pleural cavity.*



FIGURE 8.23 *Radiography should be carried out before autopsy in all deaths from firearms. The extent of dispersal of shot can be assessed – as in this film – and, in single bullet injuries, the position and possible fragmentation can be detected in order to assist in recovering the missile.*

they will almost always enter the wound and should be recovered at autopsy in order to assist in identifying the type of ammunition.

Beyond a metre or two, the wad may drop sufficiently to miss the main wound and strike the skin at a lower point. From 2 to 5 m, the wads may or may not strike the body, and further than this distance it is almost certain that the wads will fall to the ground. As with all variables associated with firearm wounds, however, it is essential for test firing to be performed wherever possible. The pathologist should not be dogmatic or impracticably precise about distances, but offer a bracket of reasonable probability.

- Tangential wounds can offer considerable difficulty in recognition to the inexperienced observer. Some pathologists, as well as clinicians and police officers, have attributed certain wounds to knives or blunt injuries, when in fact they have been gunshot wounds. The shallow cone of a shotgun discharge may pass any part of the body so that the central axis is clear of the tissues, but the periphery strikes the body surface tangentially. The most common position is probably the side of the chest, in the lower axilla. If the arm is raised it may escape damage, but sometimes an opposing injury is seen on the chest wall and inner part of the upper arm. Another area is the side of the face, where a glancing gun blast may gouge the face and perhaps carry away an ear.

The appearance of the wound depends, of course, on the range and the depth to which the cone of shot and gas penetrates. On the side of the chest, a large elliptical area may be ripped from the surface to expose underlying muscle and ribs. If a close discharge, then the nature of the injury will be clear from the usual burning and soiling of the muzzle gases, but a more distant shot may cause a clean wound that can give rise to doubt about causation. Radiography will usually reveal lead shot in the tissues, unless the contact is extremely superficial.

In the chest – even if shot penetration is minimal – severe damage to the pleura and lungs may occur from the impact, and death may occur from a haemothorax with or without lung laceration or contusion. When the side of the head is hit, shattering of skull or facial bones can occur and intracranial damage is common, even though no metallic projectiles enter the cranium. Rifled weapons can also cause tangential wounds and some features of skidding across the surface and re-entry wounds have been mentioned earlier. There is not usually the wide gouging of tissue seen in smooth-bore injuries, but the glancing passage of a high-velocity missile can open up a severe longitudinal laceration. The lateral transfer of energy can cause severe internal damage in both chest and skull, even though the missile does not enter the cavities. The skull may be extensively fractured, with widespread underlying damage, and in the absence of any projectile and a deficient knowledge of the circumstances, some such injuries have erroneously been ascribed to blunt trauma.



FIGURE 8.24 *Lead pellets and felt cartridge wads from a twelve-bore shotgun wound. It is important to recover at least a sample of pellets and the wads so that the type of cartridge can be identified.*



FIGURE 8.25 *Pellet injuries from a distant twelve-bore shotgun discharge (see also Figure 8.26). The child had been walking behind a hunter carrying a shotgun on his shoulder, the barrel pointing down. When the hunter was ducking to avoid branches of a tree the shotgun was triggered by a branch.*

WOUNDS FROM RIFLED WEAPONS

Injuries from rifled weapons vary greatly according to the velocity of the projectile, as discussed at the beginning of this chapter, but there are some characteristics common to all types. Unlike shotguns there is only one missile in each discharge, though an automatic weapon may well cause multiple wounds in close succession which impact upon the same area of the body. Occasionally, because of some defect in the weapon, two bullets may be fired at once, or a fragment of metal may detach from cartridge, barrel or bullet, so that two missiles may strike simultaneously; this is described later.

Contact wounds

When a weapon is fired in contact with the skin, the appearances can vary according to whether the muzzle was firmly pressed against the surface so as to form a tight seal – or whether it was merely held in loose contact, so that the backward jerk of recoil can permit a small gap to appear. Yet another permutation is when clothing is interposed between the muzzle and the skin.

When a rifled weapon is held firmly against the body surface during discharge, the resulting wound is in many respects similar to that from a shotgun. A twelve-bore wound



FIGURE 8.26 *Pellet injuries puncturing the oesophagus and both lungs (see also Figure 8.25).*



FIGURE 8.27 *Hunting accident in which the man was hit by four pellets from a distant twelve-bore shotgun discharge. Pellet no. 1 punctured the abdominal skin and was found in the subcutaneous fat; pellet no. 2 bruised the right wrist; pellet no. 3 penetrated the chest wall and was found in the pericardial fat tissue without any injury to the heart; pellet no. 4 hit the corner of the left eye and travelled through the left cerebral hemisphere, causing death.*

is usually much larger, but a .410 can closely resemble a large-calibre rifled weapon injury. Over deep soft tissues, such as the limbs, abdomen, neck and usually chest, the wound will be small and circular. There will be burning and blackening of the immediate wound edges, but if the seal between muzzle and skin is tight, there will be little or no sideways escape of flame and soiling unless clothing is interposed.



FIGURE 8.28 *Suicidal contact wound with muzzle mark from a 9 mm pistol (see also Figure 8.29 for corresponding exit wound).*



FIGURE 8.29 *Suicidal exit wound from a 9 mm pistol (see also Figure 8.28 for corresponding entrance wound).*



FIGURE 8.30 *Numerous tears in the lips due to expansion of muzzle gases from a 9 mm pistol fired in the mouth.*

Within the wound, there will be some flecking with soot in the tissues, the amount varying with the 'cleanliness' or otherwise of the particular ammunition. Most rifled weapon ammunition is 'clean', compared with many shotgun cartridges, so that soot may be absent altogether. There is usually an areola of hyperaemia that extends beyond the diameter of the muzzle and carbon monoxide will be absorbed by the haemoglobin and myoglobin in the vicinity of the skin wound and in the deeper track. There may be bruising, sometimes extensive, though this is rarely symmetrical and is often absent. The expansion of the tissues by gas entry tends to force the skin even harder against the end of the barrel and a 'muzzle imprint' may be formed. In rifled weapons, especially handguns, there are more features at the end of the barrel than in shotguns, so complex imprints may be made of foresights and mechanisms for self-loading in 'automatics'.



FIGURE 8.31 *Slightly deformed full-jacketed bullet in the middle of the cone-shaped exit wound on top of the skull. Homicidal entrance wound under the chin.*

If the contact wound is over a bony support, especially the skull, then the same phenomenon occurs as in shotgun wounds. The muzzle gases entering the subcutaneous tissues cannot expand by displacing adjacent soft structures and are reflected from the bone to raise a dome of gas that often splits the entry hole. This results in a linear, cruciate or stellate tear that may well destroy the original puncture. As the volume of gas produced is usually less than that formed by the large mass of propellant in a twelve-bore shotgun cartridge, the tear is smaller – though the charge in some older rifles and sporting guns may be comparable.

When the contact is loose, burning and soiling in the immediate vicinity of the muzzle may occur – again modified as in the case of shotguns, by the interposition of clothing between muzzle and skin. The fabric allows a lateral passageway for diffusion of soiling, as the muzzle cannot make such a good seal as against skin.

If the skin of the gun hand remains in firm contact with the weapon steel for a longer period of time, rust stains may develop as seen in Figure 8.34. In experiments carried out by Ulrich and Zollinger (2001) in the living as well as corpses, the formation of rust stains depends on the firmness of the contact, humidity of the skin and the environment, contact time and the state of the weapon surface. The shortest period of time necessary for the formation of rust under the most favourable circumstances, as reported by Ulrich and Zollinger, was 135 minutes for a corpse and 27 minutes for a living person.



FIGURE 8.32 *Wrist of a homicide victim, who had raised her left hand to ward off the attack, showing a 'clean' exit wound of a full-jacketed bullet in the middle and soot-soiled entrance wound beneath it.*

Blow back into the barrel – 'back spatter'

Contact wounds – and also close-range discharges – may cause blood and tissue fragments to enter the muzzle, sometimes penetrating for several centimetres, this being called 'back spatter'. There appears to be a momentary suction effect after the pressure of the gas blast subsides, possibly as a result of rapid relative cooling in the barrel. This seems to aspirate material into the muzzle and pieces of skin, hair and adipose tissue have been found inside the weapon. Sometimes blood and tissue may soil the hand or arm of the person firing the gun, a matter of considerable significance in forensic science.



FIGURE 8.33 *Intravital CT scan of a 23-year-old male who in the course of a 'Russian roulette' shot himself in the right temple with a .357 calibre Magnum revolver. Extensive injury of the cranium and brain with several X-ray positive particles probably due to the disintegration of the bullet. (From the files of the Department of Radiology of Turku University Hospital reproduced by kind permission of Professor M Kormano.)*



FIGURE 8.34 *Rust stains on the gun-hand of a suicide corresponding to the shape of the grip.*

Close-range wounds

When there is a short distance between the muzzle and body surface, the appearances of the wound will vary accordingly to the type of ammunition used. The wound



FIGURE 8.35 *A firm contact discharge against tissue overlying bone (such as the skull) causes gas to rebound from the rigid base. This raises a dome under the skin that can split to give a ragged entrance wound. This effect is by no means invariable.*



FIGURE 8.36 *Suicidal contact wound in the neck (arrow) from a 7.62 calibre rifle with destruction of the head.*

will almost invariably be circular as the tearing due to gas intrusion is unlikely to occur. The wound edges may be inverted, but at close range the rebounding gases may level up or even evert the margins. As will be described in medium-range wounds, there will be an abrasion collar.

Burning

Modern propellant produces less flame than the black powder of older shotgun cartridges, but within a few centimetres of bare skin there is likely to be burning of the skin with singeing of hairs. Even where hairs are not destroyed, they may be 'clubbed', that is, the keratin melts at the tip and resolidifies as a tiny blob. Hyperaemia around the wound is usual and some bruising can occur, which may be more evident as the post-mortem interval increases.



FIGURE 8.37 *Atypical slit-like exit wound of a homicidal firearm wound from a hunting rifle with entrance wound in the back.*

It is sometimes claimed that the flame effects extend from the muzzle a distance equal to the length of the barrel, but the truth of this rule-of-thumb is doubtful, though it may be a very rough approximation.

Soot or smoke soiling and powder tattooing

Though most propellant is now 'clean', some soot may be seen around the wound. In addition, there will be tiny burns from specks of incandescent propellant, the so-called 'powder tattooing'. These may pepper the vicinity of the entry hole in a roughly symmetrical pattern, which may assist in



FIGURE 8.39 *Entrance wounds from a 7.65 calibre automatic pistol in the forehead and right side of the face (arrow) of a homicide victim, with soot soiling.*



FIGURE 8.38 *Entrance and exit wounds.*

determining the angle of impact. Particles of propellant carry further than smoke, so tattooing around the entrance wound in the absence of soot indicates a greater distance. The soot rarely carries more than 15 cm (6 inches) from a pistol, whereas powder grains will travel 30–45 cm (12–18 inches).

These distances are approximate and can be doubled for a rifle compared with a handgun. The length of the barrel is another variable and a rule-of-thumb for pistols in this respect states that the distance from which powder residues can reach the skin is about twice the length of the barrel. It must be emphasized once again that test firing is essential for any hope of accuracy.

'Fouling' refers to tiny lesions around the entry wound caused by fragments of metal expelled by the discharge. These come either from the surface of the missile or from the interior of the barrel. Friction between the bullet and the rifling may gouge off pieces of lead, jacket, or barrel steel and hurl them at the skin, where they become embedded. These particles, like powder burns, will not wipe off at autopsy, whereas soot soiling can easily be removed with a damp sponge. Even fragments of the shell case may become detached and blown out of the barrel.

Minute flakes of unburnt explosive or inert filler may land on the same area of skin; these tend to glisten and may be orange or blue, depending on the manufacturer. It is important that a forensic scientist or police scene of crime officer has the opportunity to retrieve these before the wound is washed. If no such person is available, the pathologist should swab the area with a water-damped plain swab, or preferably cut out the skin around the wound and preserve it unfixed (refrigerated if necessary). These specimens should be sent for expert forensic examination, as they may indicate the nature of the ammunition and may be matched to that in the possession of a suspect. As with contact wounds, carboxyhaemoglobin and myoglobin will be present in the wound track in diminishing concentrations as the range increases.

The estimation of range is dealt with later, but here it is again emphasized that until test firing is carried out with a similar weapon and ammunition, only an approximate estimate can be offered from the appearances of the wound.

Medium-distance wounds

Unlike the shotgun, once the discharge of a rifled weapon is greater than a metre, there is nothing to indicate increasing range, until perhaps the erratic trajectory of extreme distance suggests maximum range. From perhaps less than half a metre to up to several kilometres the entry wound of a high-velocity rifled weapon appears the same. The typical appearance of the entry wound has been likened to that caused by 'driving a dirty pencil through the skin'. The central aperture is circular and may be inverted – that is, the margins are driven inwards by the passage of the missile – though this feature is often absent.

The size of the hole is rarely equal to the diameter of the missile and therefore the calibre of the weapon cannot instantly be determined by inspection of the wound – in spite of the apparent ease with which television drama doctors and detectives can instantly spot 'a thirty-two' or a 'thirty-eight'. When the bullet strikes the skin, the latter is stretched for a minute fraction of a second until penetration occurs, so that the missile perforates expanded skin. Immediately after entry, the skin undergoes elastic recoil and the resulting hole is usually smaller than the diameter of the bullet unless the range is so close that gas entry – or gas rebound – contributes to the size of the defect.

The abrasion collar

The skin immediately around the central hole is discoloured, the so-called 'abrasion collar'. This may be only a narrow rim or may be equal in width to the central defect. The collar is due to the inversion of the skin during penetration by the missile so that the sides of the bullet are 'wiped' by a tiny tube of skin, the epidermis of which is abraded by heat and friction.

The width of the abrasion collar is determined by the degree of inversion and hence the length of the skin tube. The collar is caused by friction and heat as the missile chafes the skin.



FIGURE 8.40 *Close-range pistol entrance wound. The eyelid and lower forehead show tiny burns from propellant flakes landing on the skin. The eyes are blackened by fractures of the floor of the anterior fossa.*



FIGURE 8.41 *Multiple entry wounds from a military self-loading weapon. The wounds are in line and approximately evenly spaced. Each is a typical entry, with an inverted appearance and an abrasion collar. There were massive exit wounds on the back, caused by .303 bullets from a Bren gun used by a Malayan patrol.*



FIGURE 8.42 *Entrance of a .22 rifle bullet at a few inches range. There is slight smoke soiling around the wound, which has a well-marked abrasion collar. In fact, two shots were fired in quick succession through the same hole, which is slightly ovoid because of the non-congruence of the two shots (see Figure 8.49).*



FIGURE 8.43 *Entrance of a .22 rifle bullet in a shooting accident.*

In addition to the true abrasion collar, there is often a slightly wider circle of peeled keratin, where the stratum corneum of the skin is raised to form a slightly frayed edge around the entry wound. This appears due to mechanical separation of the outer layer, due to the impact of the bullet knocking the deeper layers down away from the keratinized surface.

The grease ring

The inner edge of the abrasion collar may be black, as a result of heating effects and to the rubbing-off of dirt, lubricating oil, or grease and metal particles from the bullet. This is often called the 'grease ring' or 'ring of dirt', and may be absent if the missile was clean.

There may also be bruising around the wound from mechanical damage to adjacent subcutaneous blood vessels,



FIGURE 8.44 *Entrance wound in the back of a rifle bullet fired from across a room. There is thus no burning or soiling, and only minimal bruising at the margins of an almost circular inverted entry.*

but no other features, apart from the keratin ring, are present in the surrounding skin. No burns, soot or powder can be found beyond a variable distance that will not exceed a metre in the case of a rifle, and half that distance with a handgun.

Extreme trajectory wounds

Over most of their flight path, rifled weapon missiles maintain a fairly constant attitude. Soon after emergence from the muzzle, the bullet may 'precess', with the tip on the axis of travel and the base rotating in a diminishing circle about the axis. This soon settles down and causes no observable difference in the contact wound. For most of the distance of travel, the bullet remains steady, with only minor variations from axial stability. When the extreme range is approached, however, the reduced velocity allows instability of the flight path. The bullet begins to wobble and yaw, and may even tumble, that is, turn end-over-end. If the missile strikes the body in this phase, the impact may be sideways or even backwards, as well as being in an irregular lateral motion. A bullet striking sideways may leave an almost rectangular entry wound. The wound will then be similarly irregular, and there may be difficulty in recognizing it as a firearm wound or in differentiating it from a laceration caused by other means.

The direction of discharge

As with smooth-bore weapons, a close range discharge may provide information about the angle of the shot because of the geometry of any smoke soiling, powder tattooing, or burns on the skin. An impact at right angles will produce a circular zone of discoloration on the skin, while an oblique angle will result in an elliptical mark, the length of which increases as the angle decreases. As rifled weapons produce relatively little soiling except at close range, this clue is of less assistance than with shotguns.



FIGURE 8.45 *Disintegration of the head of a young female terrorist in the Malayan emergency from a single bullet entering the external auditory meatus. The weapon was a F-N rifle with a high muzzle velocity; the impact of the missile on the base of the skull instantly converted the kinetic energy into a virtual explosion.*

Again as with smooth-bore guns, the edges of the wound may be shelved or 'undercut' when the discharge enters at an oblique angle. Tissue may be seen in the floor of the wound at one side, which indicates the direction from which the bullet came. Muscular contractions may distort this picture, however and it is not always present, though minute inspection (using a lens if necessary) may reveal shelving in the deeper layers of the skin rather than in the tissues below. More useful is the shape of the abrasion collar, which will be asymmetrical if the bullet enters at an angle, even through the central hole often remains circular. The other means of determining direction, which is not usually available with shotguns, is the trajectory between entrance and exit wounds. These can be joined and projected in direction of approach to indicate the site of discharge. Two important conditions attach to this interpretation, however:

- If the bullet strikes a solid object, either bone or even a firm organ, it may be diverted within the body to exit well off the original trajectory.
- The posture of the victim's body at the instant of impact must be taken into account. It is too often assumed, especially by lawyers, that all persons are injured – in whatever fashion – whilst standing passively in the 'anatomical position'. Nothing is further from the truth, as people, especially in conditions of fight, fright or flight, may be moving or dodging in a variety of postures, which change by the second. For example, in one of the author's (BK) cases, a woman accidentally shot by a police officer had the anterior entrance wound much higher than the exit in her back. This did not mean that she was shot from above, but that she was leaning forward when the bullet hit her. Much more bizarre examples occur from time to time, such as another case seen by the author (BK) in which a puzzling high-angle wound in the chest was later proved to have been fired from an upstairs window as the victim was knocking on the front door below.

Bullet wounds in bone

Where a bullet passes through bone, especially the thin bone of the skull, the well-known pattern of 'cratering' can usually be seen, though there are exceptions. Using the cranium as the best example, the initial contact of the missile punches a clean hole through the outer table of the skull. Where the bullet emerges internally, the inner table is then unsupported and a cone-shaped plug is detached, forming a crater that is appreciably larger than the external hole. If the bullet traverses the cranium and penetrates the opposite side, the same pattern occurs, this time with the small hole on the inner table and the crater on the outside. In addition to these penetrating defects, there are often fissured, sometimes comminuted, fractures running away from the central holes.

However, though this is the classical picture, a number of exceptions have been reported in the literature, where the cratering has been reversed or is otherwise atypical (Bhoopat 1995).

A shotgun usually destroys a large area of the skull, but similar shelving may be seen on the edges of bone fragments if a bolus of shot strikes the bone. Individual pellets rarely penetrate, but the massive cranial damage from close range of contact shotgun discharges is largely the result of the rapid and violent increase in intracranial pressure caused by the entry of a large volume of gas, as well as the bolus of shot and wads.



FIGURE 8.46 *Bullet entrance wound, showing the removal of a wide area of skin for forensic examination, the hair having already been removed and preserved before photography. The autopsy incision around the wound is wide, to include any discharge residue and burned skin. The shape of the incision is obviously asymmetrical, to indicate the orientation of the sample after removal from the body.*

Where several bullets have struck the cranium, the sequence of shots can usually be determined using Puppe's rule, which is applicable to any multiple blunt force causing skull fractures. Madea and Staak (1988) have developed this rule in relation to bullet injuries: the test depends on the observations of the fracture lines either when they intersect each other or when they intersect a cratered lesion, so that one can determine which crack or defect must have been formed first.

Where bones other than skull are hit by a bullet or shot, comminuted fractures are frequent and may be the cause of extensive secondary injury. Part of the kinetic energy of the missile is transferred to the bone and fragments may be violently displaced into the adjacent tissues. They may be extruded from the body altogether, leaving secondary exit wounds in the skin. These may give rise to difficulty in interpretation, as both lay persons and doctors may mistake them for lacerated or even stab wounds, unrelated to the firearm incident. Fractures of bone from gunshot impact may be of any variety, and radiography is necessary to detect and orientate fragments of bone and differentiate them from missiles and missile fragments.



FIGURE 8.47 *The entrance wound of a bullet into a skull. Externally the defect is clean-cut and slightly ovoid because of the oblique impact of the missile. Internally, the inner table of the cranium is cratered, the bevel being caused by lack of support from the diploë. The exit hole on the opposite side of the skull showed a reversal of this pattern, with the cratering on the exterior surface.*

EXIT WOUNDS

When a gunshot wound completely traverses the part of the body struck, an exit wound will result.

Shotgun exit wounds

When smooth-bore weapons are involved, the residual energy of the individual pellets (which have a small mass and a relatively low initial velocity) is usually insufficient for them to emerge through the wider parts of the body, such as the chest and abdomen. Wounds of the limbs, neck and head may well be 'through-and-through' with a twelve-bore shotgun and occasionally, though rarely, with the small 'four-ten'. The range has an effect on the possibility of a shotgun exit wound, as contact or close-range discharge will allow the compacted mass of shot to act like a single bolus – in addition to which, the large volume of intruded gas assists in disrupting the tissues and clearing a path for the missiles, especially in the head. A shotgun blast into the mouth may well remove much of the back of the head as an exit wound, but this is in part caused by the explosion of the cranium by the gas, the so-called 'burst head', which can occur in any gunshot wound of the head, whether into the mouth or elsewhere.



FIGURE 8.48 *Cone-shaped exit wound of the calvarium, with radial fractures in left parietal bone.*

The appearance of a shotgun exit wound is totally random, depending on the anatomical part injured and the addition of any bone or tissue fragments blown out in the discharge. Typically, it is a jagged, irregular laceration with everted edges that exposes deep tissues and comminuted bone fragments beneath. A shotgun injury of the chest or abdomen often just fails to exit on the opposite side, because the toughest obstruction, other than bone, is the skin. It is not uncommon to be able to palpate lead shot under the skin in the contralateral position after it has traversed the body and been trapped by the skin.

As a contact shotgun discharge may produce a large, ragged, entrance wound, this may resemble the exit wound, if present. Differentiation is usually simple, however, because of the burning and soiling present around the entrance. It has been said that the presence of carbon monoxide in the tissues marks the entrance wound, even in decomposed bodies, but carbon monoxide can in fact be detected right through a close shotgun discharge, though the concentration should be greater near the entrance.



FIGURE 8.49 *The exit wounds in the fatality shown in Figure 8.42. The two bullets have diverged inside the head from their common entrance wound and emerged separately. The exit wounds are typically stellate, everted and clean. With small-calibre missiles, such as a .22, there is often no exit wound, but here the small head and thin skull provide less resistance to complete traversing.*



FIGURE 8.50 *Atypical slit-like exit wound of a 7.65 cal. bullet (see also Figure 8.39).*

Exit wounds from rifled weapons

As stated above, many wounds from rifled guns are 'through-and-through', especially from high-velocity military weapons. The muzzle velocity is important in determining whether a single bullet will completely traverse the body. A high-velocity missile (of the order of 800 metres/second or 3000 feet/second) is likely to pass right through the body unless it strikes a large bony structure like the spine, large limb bone or base of the skull. As discussed at the beginning of the chapter, this may be inefficient in terms of wounding capability, as much of the kinetic energy fails to be transferred to the tissues to cause damage, although the cavitating effects of a high-speed missile in vital tissues may be extremely damaging. Much modern military ammunition consists of a small bullet with a large propellant charge to provide maximum muzzle velocity. This, by the familiar physics equation, provides substantial kinetic energy. The bullet is designed to fragment on impact, so that all the energy is transferred and an exit wound may not occur. In some shootings of this nature the pathologist may have difficulty in retrieving any metallic missile material, even after identifying it radiographically, as the fragmentation may reduce the bullet to granules and dust. If the missile does not strike bone or cartilage, it is likely to emerge on the other side of the body, even through the thickness of the chest or abdomen. Of course, in many cases where bone is penetrated (especially the skull or ribs), the bullet will still emerge, but this is considered below.

If a fairly intact bullet emerges, not having been seriously deformed or fragmented, the exit wound is likely to be a small everted defect, either circular or with torn edges. The classical description is of a stellate wound, with triangular skin flaps at the margin, where the bullet has pushed out against unsupported skin. Many wounds may be cruciate or linear slits, however, and others are as circular as the entrance wound, which can give rise to some difficulty in interpretation.

It is naturally important to confirm the direction of the shot, but where a bullet has come from any distance between half a metre and near the extreme range of the weapon, then both entrance and exit wounds can look remarkably similar. There will be no burning or soiling to indicate the entry and identification will depend upon the close examination of the margins of the wounds. Where the entry was covered by clothing, fibres of fabric may have been driven into the wound, which can never occur at the exit.

Though the exit is usually everted, this may not occur if the skin is supported at the moment of penetration. A firm brassière band or an elasticated trouser waistband can press on the skin and prevent eversion, as can a plaster or fibreboard wall, if the victim was leaning against it. In these instances, there may even be a spurious 'abrasion collar', which is really caused by the emerging bullet slamming the wound periphery against the resisting surface. In difficult cases the pathologist or a deputy should examine clothing and the scene, to see if there are any such factors that will help in arriving at a definite answer as to direction.

Usually, the abrasion collar and frayed keratin ring of the entrance wound will be of diagnostic significance, as it is



FIGURE 8.51 *Typical exit wound from a 9 mm bullet. The wound in the scalp is everted, stellate and quite clean, the missile having been wiped by its passage through the tissues.*



FIGURE 8.52 *Exit wound of a 9 mm pistol fired into the mouth.*



FIGURE 8.53 *Exit wound of the bullet responsible for the wound seen in Figure 8.46, showing the classical everted, split edges, with no soiling of the surrounding skin.*

absent in the exit wound, except as detailed above. Occasionally, however, the abrasion collar of the entrance wound is merely a narrow rim that needs close inspection to detect. Where the bullet has struck bone or fragmented, the exit wound may be of any size or shape, and may be multiple. If bone is shattered, pieces can be driven out through the skin, causing wounds that may be mistaken for lacerations from blunt or even incised weapon violence. Where the bullet has hit bone within the body, the bullet may emerge sideways causing a longer or otherwise distorted exit wound.

Of the many bizarre findings in gunshot wounds, re-entry can pose some problems. One case seen by the author had two entrance and one exit wounds, with a single bullet in the body. The victim had been standing against a wall when shot from the front: the bullet emerged through his back, ricocheted from the wall and re-entered his body.

Penetration of two parts of the body is quite common, a single missile causing several wounds. The most usual is a through-and-through wound of the arm or leg, the bullet then re-entering the abdomen or chest. Placing the limb in the appropriate position immediately clarifies the situation and can considerably aid an estimation of direction.

Glancing or tangential rifled weapon wounds

Though the large gaping wounds caused by a glancing blast from a shotgun are rarely seen with rifled weapons, some strange wounds can occur. A bullet may strike the body surface at a shallow angle, enter and then re-emerge some distance away, having travelled superficially under the skin. Within the skull, a missile may enter, follow the internal curve of the calvarium and exit some distance away. Cases are on record of such wounds causing relatively little damage, having traversed the meninges, rather than the brain substance.

When the body surface is irregular, such as the breast, buttocks or groin, several re-entries and exits can take place.



FIGURE 8.54 *Diversion of trajectory of bullet on striking bone. The secondary effects can be more damaging than those from the missile.*

In these instances, extensive bruising may mislead examiners into assuming that some blunt injury has occurred, if the firearm nature of the wound is overlooked.

A bullet striking at a small angle with the surface may follow the curvature of the skull or a rib and emerge some distance away after having made a track in the subcutaneous tissues. Alternatively, a bullet can pass tangentially across the surface, causing a linear graze or even a laceration, which may lead to great difficulties in interpretation if the circumstances are unknown. Gunshot wounds in the axilla or across the side of the thorax may gape widely, looking quite unlike a firearm injury to an unsuspecting medical examiner.

FIREARM DAMAGE TO INTERNAL ORGANS

This may be of any nature, but broadly falls into two categories:

- Contusion and laceration from low-velocity impact. Where a mass of shotgun pellets and gas strike tissues or an organ the damage is simple mechanical disruption, with widespread haemorrhage from local vessels. Similar, though less extensive, damage is likely from a low-velocity rifled bullet or slug, which pushes the tissues apart as it ploughs through an organ or muscle. Secondary damage can occur from fragmentation of bone or bullet, which produces further traumatizing missiles within the tissues. The danger to life that ensues naturally depends upon the target tissues – a clean wound through the thigh may cause only temporary disability, whereas the same wound through heart or brain may well be rapidly fatal.
- High-velocity missiles produce disproportionate damage relative to their diameter because of cavitation effects, described at the beginning of the chapter. This is particularly damaging in solid organs, such as the brain and liver. The track may be many times wider than the diameter of the bullet, and may consist of pulped and haemorrhagic tissue left behind by the pulsating cavitation effect caused by the lateral transfer of energy as the missile passes through.

ESTIMATING THE RANGE OF DISCHARGE

This is one of the most important aspects of the interpretation of firearm wounds. Though guidelines can be offered, it cannot be emphasized too strongly that every weapon and batch of ammunition will vary, so that medical opinion must always defer to the results of test firing with the same gun and similar shells. Allowance must also be made for the effect of interposed clothing.

Rifled weapons

TIGHT CONTACT OVER SOFT TISSUES

- Possible muzzle impression.
- Circular hole with abrasion collar.
- Bruising.
- Local reddening from heat and monoxide.
- Little or no surface burning.
- Little or no propellant soiling or powder tattooing.

TIGHT CONTACT OVER UNDERLYING BONE

- Split or cruciate wound.
- Local reddening and monoxide.
- Bruising.
- Little or no surface burning or propellant soiling.
- Abrasion collar partly lost on skin tags.

DISCHARGE FROM LESS THAN 15 CM (6 INCHES)

- Circular hole with abrasion collar.
- Flame burn on surrounding skin.
- Burnt hairs.
- Soot and smoke soiling (depending on ammunition).
- Small punctate burns from propellant tattooing.
- Unburnt propellant flakes.
- Little or no monoxide in tissues.

DISCHARGE FROM 15 TO 30 CM (6 TO 12 INCHES)

- No soot, but perhaps powder tattooing, depending on barrel length.

- No monoxide.
- Rarely, flame burns.

DISCHARGE FROM MORE THAN 40–60 CM (16–24 INCHES)

- Circular hole with abrasion collar.
- No burning, soiling, burnt hairs or monoxide.

FAR DISTANT DISCHARGE AT LIMIT OF RANGE

- Larger, irregular hole with irregular abrasion rim caused by tumbling bullet.
- No other features.

Smooth-bore shotguns

TIGHT CONTACT DISCHARGE OVER SOFT TISSUES

- Single circular wound about diameter of muzzle.
- Smooth margin.
- Often muzzle imprint.
- Blackened edge.
- No surrounding smoke soiling unless clothing allows leakage.
- Deep bruising.
- Pink tissues.
- Wads in wound.

TIGHT CONTACT DISCHARGE OVER SKULL OR BONY AREA

As last type, but wound may be ragged and split from gas rebound.

DISCHARGE WITHIN A FEW CENTIMETRES

- Circular wound, unless oblique discharge.
- Smooth or slightly crenated margin.
- No satellite pellet holes.
- Surrounding soot soiling.
- Punctate powder burns.
- May be unburnt powder flakes.
- Burning of surrounding skin.
- Burnt hairs.
- Pink monoxide in tissues.
- Wads in wound.

DISCHARGE FROM 30 CM (12 INCHES)

- Circular ‘rat-hole’ wound with nibbled margins.
- No satellite pellet holes.
- Soot soiling may persist.
- Powder tattooing present.
- Little or no monoxide.
- Still burning of skin and hairs.
- Wads in wound.

DISCHARGE FROM 1 TO 5 M (39 TO 195 INCHES)

- Central ‘rat-hole’ wound.
- Satellite pellet holes around periphery.
- No burning.
- No soot.
- Maybe slight tattooing at 1 m.
- No monoxide.
- Wads not in wound at upper part of this range.

DISCHARGE OVER 5 M (195 INCHES)

- Diffuse pellet pattern.
- Probably no central hole.
- No burning, soot, tattooing, monoxide, no wads.

All the foregoing data are very variable, being dependent upon the individual weapon and ammunition. Test firing must be used to validate the pathological interpretation.

AIRGUN INJURIES

Air rifles and pistols produce wounds that have some of the characteristics of both shotguns and explosive rifled weapons. The missile is single and fired through a rifled barrel, but is small and resembles a shaped (waisted) shotgun pellet.

The muzzle velocity is relatively low, but some more sophisticated rifles, such as the German Weirauch, can produce more than 12 foot-pounds of energy and the pellet can easily penetrate a wooden door – and the human skull.

Two calibres are common, the .177 and the .22 inch, the latter naturally being the more dangerous. The .177 can, however, penetrate the thin temporal bone of a child. Wounds from an air weapon are rarely fatal except when the head is struck – and children are the usual victims. The pellet can enter the skull and traverse the whole width of the brain, but never produce an exit wound, being usually found in the contralateral meninges. The track may be surprisingly wide for such a low-velocity missile.

Apart from fatal head wounds, a number of eye injuries occur from airguns, the pellet lodging within the globe, the orbit or the adjacent air-sinuses. Radiology is obviously of prime importance in locating the missile, prior to surgical removal.



FIGURE 8.55 *Track through a child's brain made by a .177 inch air-rifle pellet (arrowed). Although a relatively low-velocity missile, the track is much wider than the pellet from lateral transfer of kinetic energy.*

There are no particular features of an air weapon wound, as, of course, there are none of the heat, powder or soot effects of an explosive gun. The entry wound is small, but may show an abrasion ring. There is never an exit wound, unless the tissue traversed is extremely narrow.

HUMANE (VETERINARY) KILLERS AND INDUSTRIAL 'STUD-GUNS'

Explosive weapons of a specialized type are used in abattoirs and by veterinary surgeons to dispatch large animals.



FIGURE 8.56 *Airgun pellet in brain tissue.*



FIGURE 8.57 *Radiography can assist in locating a missile before autopsy, so that random searching does not cause instrument damage to the delicate striation pattern used for weapon identification. Here there is a lead pellet in the occipital lobe, with a bone defect in the extreme front of the skull.*

They may be of the 'captive-bolt' type, which consists of a metal rod, the distal end of which is propelled for a few centimetres from the muzzle of the weapon by a blank cartridge inserted in a chamber behind the proximal end. The captive bolt inflicts a clean, penetrating injury, about 5 cm deep, which can be mistaken for a stab-like injury.

Another variety consists of a metal barrel on the distal end of which is a heavy flange, which is placed against the head of the animal. A cartridge carrying a 0.31 inch (8 mm) bullet is inserted into the proximal end of the barrel and a firing pin struck with a mallet. The injuries from this resemble a contact wound from a conventional weapon, though the base of the flange may have embossed concentric circles to prevent slipping, which may produce an unusual patterned imprint on the skin surrounding the wound.

Another type is the Webley veterinary pistol, which is of .32 calibre and is virtually identical with a conventional gun. Humane killers may cause injuries on humans either accidentally or suicidally, homicide being rare. The nature of the weapon will almost always be apparent from the circumstances, including the presence of the weapon. Death may be delayed due to complications, as in one case seen by the author (BK) where a farmer died of tetanus after accidentally shooting himself in the knee with a humane killer.

Devices used in industry and especially the building trade, are similar to humane killers. These are the 'stud-guns' used



FIGURE 8.59 *Suicidal contact wound from a humane veterinary killer (see also Figure 8.60).*



FIGURE 8.58 *A relatively unusual photograph in Britain, in that the suicide is of a woman and an automatic pistol is used. Note the massive haemorrhage on the floor, which illustrates the possible extent of post-mortem bleeding.*



FIGURE 8.60 *Defect of the right frontal bone (arrow) from a humane veterinary killer (see also Figure 8.59).*

for driving a hardened metal pin or threaded stud into masonry, or other wood or metal structures as a rapid and convenient means of attachment. An explosive cartridge, often of .22 calibre, is used to drive a piston that acts as a hammer on the pin or stud. Many accidents and the occasional suicide have occurred from these tools, which resemble a long pistol, with a flat faceplate attached to the muzzle for pressing against the structure. Some accidents occur because the guns are used on relatively flimsy partitions, and the stud traverses the structure and flies on to injure or kill someone on the other side.

RUBBER AND PLASTIC BULLETS

A relatively recent innovation in firearms is the use by police and security forces of projectiles for riot control. Originally rubber bullets were used, being compressed into smooth-bore weapons. These have been abandoned in Britain in favour of 'baton rounds', more commonly known as 'plastic bullets'. They have been used in large quantities in Northern Ireland, some 43 000 having fired up to 1985. These projectiles have not yet been used in the mainland of Britain, though many police forces hold stocks. Elsewhere in the world, they are used extensively for riot control.

The baton round is a solid cylinder of polyvinylchloride 38 mm in diameter and 10 cm long, weighing 135 g. When fired from a smooth-bore weapon it has a muzzle velocity of about 250 km/hour and an effective range of 50–70 m. It should not be fired at a person under about 20 m range. It is used to disperse riots and discourage stone-throwers by striking them sufficiently hard to cause pain and bruising, but no serious injury. The bullet is about the same weight as a cricket ball, but travels twice as fast as the best bowler could deliver it. In Britain, the bullets were made by Pains-Wessex-Schermuly, but later by Brocks Fireworks and also by the Ministry of Defence. Many injuries and some deaths have been reported from their use. Fractures of the face and skull, eye damage including blinding, broken ribs and limbs, and contusions of liver, lung and spleen have occurred.

Police are instructed to fire at the lower half of the body, to avoid the more serious injuries arising from hitting the head or chest. The death rate is said to be 1/18 000 rounds fired, compared with rubber bullets which had a mortality rate of 1/4000 rounds.

DEATHS FROM EXPLOSION

Deaths from the effects of explosive substances or devices occur in both civil and 'military' circumstances, though the latter now include a considerable proportion of terrorist activities rather than conventional wars. Civil tragedies are usually industrial, as in individual incidents in mines and quarries, or on a larger scale, such as the detonation of chemical stores, ships or factories.

The nature of explosive trauma

Several different factors cause injury following an explosion, and the relative importance of each varies considerably with the type of detonation. For example, pure blast effects are far more important with high-explosive projectiles designed for purely military use than with the home-made terrorist bombs, the lethality of which may be primarily caused by flying fragments. Death and injury from explosives is caused by:

- blast effects
- impact of projectiles derived from the explosive device
- impact from surrounding objects and debris impelled by the explosion
- burns from hot gas and incandescent objects
- secondary injuries from falling masonry, beams and furnishings dislodged by the explosion.

A blast consists of a wave of compression passing rapidly through the air – or water in the case of a submarine explosion, such as a mine. The velocity of the shock wave depends on the distance from the epicentre, being many times the speed of sound at the start, but rapidly decreasing as it spreads out. The compression wave is followed by a transient zone of low pressure (below atmospheric), so that a rapid double change in pressure is suffered by the body. The magnitude of the blast varies with the energy released and also with the distance from the epicentre, the intensity obeying the inverse square law. With all but powerful military high explosives, the blast effects of most terrorist devices fall off so rapidly with distance that only those in the immediate vicinity will suffer severe damage from blast. Not uncommonly, this type of victim is the bomb-setter himself, when a premature detonation occurs.

A blast causes the most damage at an interface between tissues in contact with the atmosphere, which is why the lung usually suffers the most. About 100 lb/inch^2 (690 kPa) is the minimum threshold for serious damage to humans. The shock wave can pass through solid, homogeneous tissues such as liver and muscle, causing little or no damage, but in the lung there is marked variation in density between the alveolar walls and the contained air so that damping of the shock wave occurs and energy is absorbed, with disruptive effects.

There is controversy about whether pulmonary damage occurs from direct transmission of the shock wave through the thoracic wall, or through the oronasal orifices and air passages. In any event, the autopsy signs are of subpleural patchy haemorrhages, often in the line of the ribs, intrapulmonary haemorrhage and bullae at the lung margins. The air passages may be filled with bloody froth causing airway obstruction and hypoxia in addition to the primary damage.

Microscopically the alveolar walls can be shredded by the acceleration and consequent tearing of the air-sac wall when the shock waves traverses the lung. Desquamated alveolar and bronchial epithelium is seen lying free. Large areas of haemorrhage are seen, with either the alveolar pattern still visible or the architecture completely disorganized. Pulmonary haemorrhage in explosive incidents is often not caused solely by the blast, but may be from direct impact on the chest from flying objects, aspiration of blood from nasopharyngeal injuries and from bleeding following aspiration of stomach contents.

The ear may suffer severe damage from a blast, but this is not easily discernible at autopsy. Clinical examination and testing (obviously in the living) reveals many lesions, but these are of little relevance to the pathologist.

The gastrointestinal system suffers from the effects of a blast because, like the lung, it contains air and gases, and is thus not a uniform medium for transit of the shock wave. Once again haemorrhage is the most common lesion, usually small foci of the order of a centimetre in size. They may form circumferential bands around the intestine or may be confined to the serous coat as focal haemorrhages. The caecum and colon are more often injured than the ileum, jejunum and stomach, probably because they are larger and often contain more gas. Occasionally ruptures of the gut occur if the blast is violent and the victim in near proximity.

Victims of explosions in water suffer a reverse order of gastrointestinal to lung damage. The former is more common and may be manifested as haemorrhages under the serous coats and mucosa. Perforations may occur and, in survivors, peritonitis is not uncommon. The perforations are often multiple and in any part of the intestine. Lung damage is less common in water and some instances may be caused by impact transmitted up through the diaphragm.

Missile injuries in explosions

It is again emphasized that unless a sophisticated high-explosive military device is involved, or if the victim is virtually adjacent to a lower energy terrorist bomb, blast effects will rarely be the sole cause of death. The body will, however, be vulnerable to impact from solid fragments originating from the bomb casing or a container or conveyance, such as a car in which the bomb was concealed. Fragments of metals, from tiny splinters to large chunks or sheets, will be projected at high speed. The smaller ones will not travel more than a few metres, but larger, heavier pieces can fly over considerable distances and can cause serious or fatal injuries in just the same way as projectiles from a firearm. In the open, debris is scoured away, including dust and dirt, which can impinge on the body to injure and discolour it. At autopsy the body may appear pigmented from this dust blasting, the clothing causing a shadow effect similar to bathing suit protection from sunburn. A more common appearance is a 'peppering' as a result of the numerous small missiles causing bruises, lacerations and abrasions. The lacerations are often puncture wounds, of varying size and depth. Burns may also discolour the body, especially those areas unprotected by clothing. Flash burns from the bomb itself only affect those nearby unless the device is massive, though singeing of hair and eyebrows is not uncommon. Other burns may be caused by ignition of clothing, or by the building or vehicle catching alight from the bomb effects –or from gas or petrol ignition.

A massive bomb, or one where the victim is virtually on top of the device, may totally disrupt the body and fling unidentifiable pieces over a wide area. Alternatively, part of the body may be totally destroyed, sometimes the remainder of the victim being remarkably intact. The legs may be blown off or the abdomen disrupted, or the hands and arms torn away. In terrorist attacks these effects may be seen in the person who was planting the bomb or carrying it to the place chosen for detonation. A premature explosion, sometimes during the act of setting the timer, may cause these localized injuries.

The pathologist may be able to assist in reconstructing the events, as localized severe trauma obviously indicates the relative position of the bomb and the victim at the time of detonation. If the lower legs are destroyed, then the person was standing near the device that lay on the ground. Punctured wounds and bruises on the front of the thighs and trunk will indicate that he was facing the bomb. If the thighs, pelvic region and abdomen are damaged, the bomb may have been carried on the lap – and if the hands, chest and face are the most affected areas, the deceased may have been bending over the device.

The autopsy in explosion deaths

The salient features have already been described and much of the autopsy is directed at listing the injuries, as in any other trauma death. The interpretation outlined above, however, may be most important for the investigators.

There are some more specific matters in an explosion death which the pathologist must bear in mind. Firstly, trace evidence may be vital to the forensic scientists and bomb experts, who are trying to trace the maker of a terrorist device. X-rays should be taken of all bodies before autopsy to identify any radio-opaque objects. Not only will this assist in detecting lethal missiles not visible from the surface, but it may reveal small metal objects that form part of the bomb mechanism, such as small springs or contacts from the timer or detonator. These may be invaluable in allowing the experts to recognize the handiwork of a particular bomb-maker or terrorist group. Such radiography may also reveal the unexpected, which in the past has included a bullet, the victim having been blown up after death from shooting. Even prior to radiography, there may be much that the pathologist has to do. Though many explosion victims are relatively intact, where extensive disruption has occurred, the fragments have to be collected and sorted out in the mortuary.



FIGURE 8.61 *Localized injury by an explosive device. The soldier picked up an apparently 'dud' smoke shell, which then detonated. He lived for some weeks, the injury having partly healed, though part of the face and skull were destroyed.*

A major initial problem is to discover how many bodies are represented and to try to allot the correct fragments to the right individuals. Where there are a number of victims and a large pile of small fragments, this task may be difficult or impossible, but it is naturally of paramount importance to determine how many victims are involved and to determine the sex of each. This is largely an anatomical exercise, akin to the sorting of multiple skeletal remains. Careful identification of all recognizable structures, such as prostate, uterus, breasts, scalp, eyes, for example, is needed in addition to more gross sorting of limb and trunk fragments. Radiology may again assist in matching contained skeletal structures, but much of



FIGURE 8.62 *Numerous wounds and peppering by debris projected in a terrorist bomb blast. Blast injuries occur only in close proximity to the device – most injury is caused by flying projectiles. (Reproduced by kind permission of Professor TK Marshall.)*



FIGURE 8.63 *Anterior aspect of a man who had constructed an explosive device using dynamite. The device probably detonated prematurely, the blast disrupting the head and abdominal region.*

the debris accumulated after a large explosion consists mainly of skin and attached tissues.

In spite of the most thorough police search of the scene, considerable proportions of some bodies are never recovered, having been disrupted into tiny fragments and mixed with the masonry and other debris of the bomb site. The collected fragments have to be washed clean from the inevitable dirt that coats them and sorted into groups by anatomical similarity. Non-human tissue is discarded, as animal material is not uncommonly admixed. The completed piles of tissue are then resorted by any apparent similarity, such as racial pigmentation, hair colour and sex. Limbs and large joints are then sorted, allotting them to left and right from anatomical considerations.

The difficulties of such a task was emphasized by Professor TK Marshall, whose experiences in Northern Ireland make his writings on the subject the definitive guide to such tragedies. In one of his incidents, eight victims were accounted for, when a single penile fragment forced the inevitable conclusion that there were in fact nine victims, not eight, though no other recognizable part of this ninth man was ever discovered. He had presumably been the bomb-carrier and had been completely disintegrated.

REFERENCES AND FURTHER READING

Adelson L. 1984. Bullet embolism with radiologic documentation. A case report. *Am J Forensic Med Pathol* **5**:253–6.

Aguilar JC. 1983. Shored gunshot wound of exit. A phenomenon with identity crisis. *Am J Forensic Med Pathol* **4**:199–204.

al Alousi LM. 1990. Automatic rifle injuries: suicide by eight bullets. Report of an unusual case and a literature review. *Am J Forensic Med Pathol* **11**:275–81.

Amatuzio JC, Coe JI. 1981. Homicide by exploder ammunition. *Am J Forensic Med Pathol* **2**:111–13.

Anonymous. 1968. Nail-gun injuries. *Br Med J* **1**:462.

Betz P, Pankratz H, Penning R, *et al.* 1993. Homicide with a captive bolt pistol. *Am J Forensic Med Pathol* **14**:54–7.

Bhoopat T. 1995. A case of internal beveling with an exit gunshot wound to the skull. *Forensic Sci Int* **71**:97–101.

Black AM, Burns BD, Zuckerman S. 1942. Wounding mechanism of high velocity missiles. In: Pugh WS (ed.), *War medicine*. F. Hubner & Co, New York.

Breitenecker R. 1969. Shotgun wound patterns. *Am J Clin Pathol* **52**:257–62.

Brissie RM, Collum ES. 1980. Shotgun wounds: multiple probes and shielding effects as adjuncts to determining position of the decreased at time of injury. *J Forensic Sci* **25**:528–32.

Callender GR. 1943. Wound ballistics; mechanism of production of wounds by small bullets and shell fragments. *War Med* **3**:337–45.

Clark MA, Micik W. 1984. Confusing wounds of entrance and exit with an unusual weapon. *Am J Forensic Med Pathol* **5**:75–8.

Clark MA, Smith TD, Fisher RS. 1981. Russian roulette with an exploding bullet. A case report. *Am J Forensic Med Pathol* **2**:167–9.

Coe JI. 1982. External beveling of entrance wounds by handguns. *Am J Forensic Med Pathol* **3**:215–19.

Coe JI, Austin N. 1992. The effects of various intermediate targets on dispersion of shotgun patterns. *Am J Forensic Med Pathol* **13**:281–3.

Conradi SE. 1982. New aluminum-jacketed ammunition: The case of the ‘invisible’ jacket. *Am J Forensic Med Pathol* **3**:153–5.

Copeland AR. 1985. Concepts in survival from lethal handgun wounds. *Am J Forensic Med Pathol* **6**:175–9.

Cragg J. 1967. Nail-gun fatality. *Br Med J* **4**:784–5.

Dada MA, Loftus IA, Rutherfoord GS. 1993. Shotgun pellet embolism to the brain. *Am J Forensic Med Pathol* **14**:58–60.

de la Grandmaison GL, Brion F, Durigon M. 2001. Frequency of bone lesions: an inadequate criterion for gunshot wound diagnosis in skeletal remains. *J Forensic Sci* **46**:593–5.

DiMaio VJ. 1981. Penetration and perforation of skin by bullets and missiles. A review of the literature. *Am J Forensic Med Pathol* **2**:107–10.

DiMaio VJ, Copeland AR, Besant Matthews PE, *et al.* 1982. Minimal velocities necessary for perforation of skin by air gun pellets and bullets. *J Forensic Sci* **27**:894–8.

Dixon DS. 1984. Pattern of intersecting fractures and direction of fire. *J Forensic Sci* **29**:651–4.

Eckert WG. 1981. Exploding bullets. A hazard to the victim, physician, and investigator [editorial]. *Am J Forensic Med Pathol* **2**:103–4.

Eisele JW, Reay DT, Cook A. 1981. Sites of suicidal gunshot wounds. *J Forensic Sci* **26**:480–5.

Elsayed NM. 1997. Toxicology of blast overpressure. *Toxicology* **121**:1–15.

Freytag E. 1963. Autopsy findings in head injuries from blunt forces: statistical evaluation of 1367 cases. *Arch Pathol* **75**:74–80.

Geurin PF. 1960. Shot-gun wounds. *J Forensic Sci* **5**:294–9.

Glattstein B, Zeichner A, Vinokurov A, *et al.* 2000. Improved method for shooting distance estimation. Part III. Bullet holes in cadavers. *J Forensic Sci* **45**:1243–9.

Goonetilleke UK. 1976. A stud (cartridge) gun suicide (a case report). *Med Sci Law* **16**:181–4.

Green GS, Good R. 1982. Homicide by use of a pellet gun. *Am J Forensic Med Pathol* **3**:361–5.

Guileyardo JM, Cooper RE, Porter BE, *et al.* 1992. Renal artery bullet embolism. *Am J Forensic Med Pathol* **13**:288–9.

Gulmann C, Hougen HP. 1999. Entrance, exit, and reentrance of one shot with a shotgun. *Am J Forensic Med Pathol* **20**:13–16.

Hawley DA, Pless JE, Palmer H. 1987. Tumbling abrasions. Injuries from ricocheting bullets. *Am J Forensic Med Pathol* **8**:229–32.

Hudson P. 1981. Multishot firearm suicide. Examination of 58 cases. *Am J Forensic Med Pathol* **2**:239–42.

Hunt AC, KonVanda M. 1962. The patterns of injury from humane killers. *Med Sci Law* **2**:197–202.

Jacob B, Huckenbeck W, Daldrup T, *et al.* 1990. Suicides by starter's pistols and air guns. *Am J Forensic Med Pathol* **11**:285–90.

James WR. 1962. Fatal air rifle pellet wound of the brain. *Med Sci Law* **2**:153–4.

Janssen W, Kulle KJ, Gehl A, *et al.* 2001. [Unintentional gunshot during police intervention.] *Arch Kriminol* **207**:1–11.

Janssen W, Miyaishi S, Koops E, *et al.* 1996. [Gunshot fatalities in connection with hunting and hunting rifles – causes, prevention and expert evaluation.] *Arch Kriminol* **197**:1–15.

Johnson GC. 1985. Unusual shotgun injury. Gas blowout of anterior head region. *Am J Forensic Med Pathol* **6**:244–7.

Jones AM, Graham NJ, Looney JR. 1983. Arterial embolism of a high-velocity rifle bullet after a hunting accident. Case report and literature review. *Am J Forensic Med Pathol* **4**:259–64.

Kage S, Kudo K, Kaizoji A, *et al.* 2001. A simple method for detection of gunshot residue particles from hands, hair, face, and clothing using scanning electron microscopy/wavelength dispersive X-ray (SEM/WDX). *J Forensic Sci* **46**:830–4.

Karger B, Stehmann B, Hohoff C, *et al.* 2001. Trajectory reconstruction from trace evidence on spent bullets. II. Are tissue deposits eliminated by subsequent impacts? *Int J Legal Med* **114**:343–5.

Kleiber M, Stiller D, Wiegand P. 2001. Assessment of shooting distance on the basis of bloodstain analysis and histological examinations. *Forensic Sci Int* **119**:260–2.

Knight B. 1982. Explosive bullets: a new hazard for doctors [editorial]. *Br Med J Clin Res Ed* **284**:768–9.

Lee KA, Opeskin K. 1995. Gunshot suicide with nasal entry. *Forensic Sci Int* **71**:25–31.

Madea B, Staak M. 1988. Determination of the sequence of gunshot wounds of the skull. *J Forensic Sci Soc* **28**:321–8.

Marshall T. 1988. A pathologist's view of terrorist violence. *Forensic Sci Int* **36**:57–67.

Marshall TK. 1976. Deaths from explosive devices. *Med Sci Law* **16**:235–9.

Marshall TK. 1978. Violence and civil disturbance. In: Mason JK (ed.), *The pathology of violent injury.* Edward Arnold, London.

Marshall TK. 1978. The investigation of bombings. In: Wecht C (ed.), *Legal medicine annual 1979*. Appleton Century Crofts, New York.

McCorkell SJ, Harley JD, Cummings D. 1986. Nail-gun injuries. Accident, homicide, or suicide? *Am J Forensic Med Pathol* **7**:192–5.

Menzies RC, Scroggie RJ, Labowitz DI. 1981. Characteristics of silenced firearms and their wounding effects. *J Forensic Sci* **26**:239–62.

Millar R, Rutherford WH, Johnson S, *et al.* 1975. Injuries caused by rubber bullets: a report on 90 patients. *Br J Surg* **62**:480–6.

Milroy CM, Clark JC, Carter N, *et al.* 1998. Air weapon fatalities. *J Clin Pathol* **51**:525–9.

Murphy GK. 1980. The study of gunshot wounds in surgical pathology. *Am J Forensic Med Pathol* **1**:123–30.

Oehmichen M, Meissner C, Konig HG. 2000. Brain injury after gunshot wounding: morphometric analysis of cell destruction caused by temporary cavitation. *J Neurotrauma* **17**:155–62.

Opeskin K, Cordner S. 1990. Nail-gun suicide [see comments]. *Am J Forensic Med Pathol* **11**:282–4.

Ornehult L, Eriksson A. 1987. Accidental firearm fatalities during hunting. *Am J Forensic Med Pathol* **8**:112–19.

Owen-Smith MS. 1981. *High velocity missile wounds*. Edward Arnold, London.

Petty CS. 1966. Firearms and the forensic pathologists. American Society of Clinical Pathologists. *Council on Forensic Pathology Meeting*. Commission on Continuing Medical Education, Washington.

Petty CS. 1969. Firearms injury research: the role of the practicing pathologist. *Am J Clin Pathol* **52**:227–81.

Petty CS, Hauser JE. 1968. Rifled shotgun slugs, wounding and forensic ballistics. *J Forensic Sci* **13**:114–23.

Pollak S, Ropohl D, Bohnert M. 1999. Pellet embolization to the right atrium following double shotgun injury. *Forensic Sci Int* **99**:61–9.

Quatrehomme G, Iscan MY. 1997. Bevelling in exit gunshot wounds in bones. *Forensic Sci Int* **89**:93–101.

Quatrehomme G, Iscan MY. 1998. Analysis of beveling in gunshot entrance wounds. *Forensic Sci Int* **93**:45–60.

Quatrehomme G, Iscan MY. 1998. Gunshot wounds to the skull: comparison of entries and exits. *Forensic Sci Int* **94**:141–6.

Rao VJ, May CL, DiMaio VJ. 1984. The behavior of the expanding point 25 ACP ammunition in the human body. *Am J Forensic Med Pathol* **5**:37–9.

Ratanaproeksa O, Hood I, Mirchandani H. 1988. Single gunshots with multiple entrances. *Am J Forensic Med Pathol* **9**:212–14.

Rocke L. 1983. Injuries caused by plastic bullets compared with those caused by rubber bullets. *Lancet* **1**:919–20.

Rosenhead J. 1985. Plastic bullets – a reasonable force? *New Scient* **17**:26–7.

Rothschild MA, Liesenfeld O. 1996. Is the exploding powder gas of the propellant from blank cartridges sterile? *Forensic Sci Int* **83**:1–13.

Shaw J. 1972. Pulmonary contusion in children caused by rubber bullets. *Br Med J* **4**:764–5.

Smith OC, Berryman HE, Lahren CH. 1987. Cranial fracture patterns and estimate of direction from low velocity gunshot wounds. *J Forensic Sci* **32**:1416–21.

Spitz WU, Wilhelm RM. 1970. Stud gun injuries. *J Forensic Med* **17**:5–11.

Stahling S, Karlsson T. 2000. A method for collection of gunshot residues from skin and other surfaces. *J Forensic Sci* **45**:1299–302.

Steindler R. 1983. The case of the mysterious dum-dum bullet. *Am J Forensic Med Pathol* **4**:205–6.

Steindler RA. 1982. An expanding .25 ACP bullet. *Am J Forensic Med Pathol* **3**:119–21.

Stephens BG. 1983. Back spatter of blood from gunshot wound observations and experimental simulation. *J Forensic Sci* **28**:437–9.

Stone IC. 1992. Characteristics of firearms and gunshot wounds as markers of suicide. *Am J Forensic Med Pathol* **13**:275–80.

Subke J, Haase S, Wehner HD, *et al.* 2002. Computer aided shot reconstructions by means of individualized animated three-dimensional victim models. *Forensic Sci Int* **125**:245–9.

Thali MJ, Kneubuehl BP, Dirnhofer R, *et al.* 2001. Body models in forensic ballistics: reconstruction of a gunshot injury to the chest by bullet fragmentation after shooting through a finger. *Forensic Sci Int* **123**:54–7.

Thali MJ, Kneubuehl BP, Zollinger U, *et al.* 2002. The 'skin-skull-brain model': a new instrument for the study of gunshot effects. *Forensic Sci Int* **125**:178–89.

Thali MJ, Kneubuehl BP, Zollinger U, *et al.* 2002. A study of the morphology of gunshot entrance wounds, in connection with their dynamic creation, utilizing the 'skin-skull-brain model'. *Forensic Sci Int* **125**:190–4.

Torre C, Varetto L, Ricchiardi P. 1986. New observations on cutaneous firearm wounds. *Am J Forensic Med Pathol* **7**:186–91.

Ulrich U, Zollinger U. 2001. [Development of rust stains on the skin due to contact with a gun.] *Arch Kriminol* **208**:32–41.

Warren MW, Falsetti AB, Kravchenko II, *et al.* 2002. Elemental analysis of bone: proton-induced x-ray emission testing in forensic cases. *Forensic Sci Int* **125**:37–41.

Zuckerman S. 1940. Experimental study of blast injuries to the lung. *Lancet* **2**:219–24.

CHAPTER 9

Transportation injuries

- The dynamics of vehicular injury 281
- Pattern of injury of vehicle occupants 282
- The effect of seatbelts 287
- The vulnerability of children in vehicles 289
- Injuries to motorcyclists 290
- Injuries to pedal cyclists 291
- Injuries to pedestrians 291
- Cause of death in traffic accidents 295
- Suicide and homicide by motor vehicle 297
- Railway injuries 297
- References and further reading 298

Injuries and fatalities occur in all forms of transportation but numerically road traffic accidents account for the great majority worldwide. In developed countries, they are the most common cause of death below the age of 50 years, and in young men this trend is even more marked. The pattern of injury, fatal and otherwise, varies considerably depending upon whether the victim is a vehicle occupant, a motorcyclist, a pedal cyclist or a pedestrian.

THE DYNAMICS OF VEHICULAR INJURY

A number of elementary physical facts help to explain the complex pattern of traffic injuries, especially those sustained by the occupants of a vehicle.

- Tissue injury is caused by a change of rate of movement. A constant speed, however rapid, has no effect whatsoever as is evident from space travel or the rotation of the earth. It is the change of rate that is traumatic – that is, acceleration or deceleration.
- Change of rate is conveniently measured in 'gravities' or 'G forces'. The amount that a human body can tolerate depends greatly on the direction in which the force acts. Deceleration of the order of 300 G can be sustained without injury and even 2000 G can be survived for a short time, if it acts at right angles to the long axis of the body. The frontal bone may resist 800 G without fracture and the mandible 400 G, as can the thoracic cage.
- During acceleration or deceleration the tissue damage produced will depend upon the force applied per unit area, just as a sharp knife penetrates more easily than a blunt one used with the same force. If a car driver is brought to rest from 80 km/hour by striking 10 cm^2 of his head on the windscreen frame, the damage will be vastly more severe than if the same decelerative force was spread over 500 cm^2 of a safety belt.
- Between 60 and 80 per cent of vehicular crashes (either into a fixed structure or into another vehicle) are frontal, causing violent deceleration. Another 6 per cent are rear impacts, which accelerate the vehicle and its occupants. Of the remainder, about half are sideswipes and the rest 'roll-overs'.
- In the common frontal impact, there is never instant arrest of the vehicle, even when it runs into a massive, immovable structure. The vehicle itself deforms from the front so that there is always a deceleration distance and time, albeit small. In fact, much of the manufacturers' design research now goes into making deliberate provision for the crumpling or 'concertinaing' of the front and rear of the car, leaving a central rigid cell that comprises the passenger compartment. The object is to extend the stopping distance and time, so that the G value acting on the occupants is reduced.
- The value of the G forces can be calculated from the formula: $G = C(V^2)/D$, where V is velocity in km/hour, D is the stopping distance in metres after impact, and C is a constant 0.0039. (If V is in mph and D is in feet, C becomes 0.034.) For example, if a car



FIGURE 9.1 *Major points of injury to an unrestrained driver of a vehicle in deceleration impact.*

travelling at 80 km/hour runs into a stone wall that it penetrates for 25 cm, plus 50 cm crumpling of the front of the car, the deceleration would amount to about 33 G. If an occupant was rigidly belted into his seat (a practical impossibility), he would also suffer the same deceleration, which would be survivable. If, however, he was unrestrained, he would continue forwards momentarily at 80 km/hour and suffer massive G forces, the magnitude of which would depend on his deformation stopping distance (a few centimetres of tissue compression) when he struck the internal car structures in front of him.

PATTERN OF INJURY OF VEHICLE OCCUPANTS

The type of vehicle (other than motorcycles) in theory makes little difference to the mechanism of injury, but most statistical surveys divide them into cars and light vans under 1.5 tonnes, on the one hand and heavier vehicles, such as trucks and buses, on the other, though the latter have different features more akin to passenger aircraft.

Heavy goods vehicles naturally suffer less than cars and light vans in crashes because of their far greater mass and strength, and also due to their height above the ground. Structural damage from impact with other smaller vehicles is less and often sustained below the level of the driver. Given smaller deceleration forces, however, the cab occupants are vulnerable to the same injury patterns.

Light vans are virtually identical to cars with respect to the front-seat occupants. In fact they may be more at risk, as modern vans tend to be flat-fronted and thus have little or no 'crumple' potential to increase the stopping time. Concentrating on cars, the most common vehicular casualty, the pattern of injury varies according to the position of the occupant.



FIGURE 9.2 *Facial lacerations from a shattered windscreen in an unrestrained driver. The toughened glass breaks into small fragments, which produce the characteristic 'sparrow-foot' marks. The laceration on the forehead was made by the windscreen rim.*

The driver

Numerous investigations have been made by road research organizations and car manufacturers using dummies and actual corpses, together with sophisticated recording equipment and high-speed cinematography. These have established a detailed picture of the sequence of events in automobile crashes. When the most common event – frontal impact – occurs, the unrestrained driver first slides forwards so that his legs strike the fascia/parcel-shelf area, and his abdomen or lower chest contacts the lower edge of the steering wheel. The body then flexes across the steering wheel and begins to rise. The heavy head goes forwards, and there is flexion of the cervical and thoracic spines. The upward and forward component causes the head to strike the windscreen, the upper windscreen rim or the side pillar. The windscreen is often perforated by the head or face, and the whole body may be ejected through the broken glass, to land on the bonnet or even on the roadway ahead.

Another factor causing injury is the intrusion of structural parts into the passenger compartment. Though modern cars are designed to maintain a rigid central passenger compartment, if the impact is gross, the engine or front-wheel assembly may be forced back into the seating area, intruding upon the driver. Similarly, the roof or front corner pillar (the so-called 'A'-frame) may cave in on top of the driver.

One effect of column, engine, or gearbox intrusion may be to force the floor up and backwards against the driver's feet and legs. The control pedals also take part in intrusion, and, in the usual desperate braking and declutching, the reflex pressure of feet on rising pedals and floor may cause transmitted force up the legs and into the pelvic girdle. The steering column was formerly a more dangerous item for intrusion, being forced back to 'stab' or crush the driver's chest or abdomen. Modern design has reduced this danger by making the column telescopic, hinged or otherwise collapsible, but injuries still occur – sometimes from the wheel itself breaking and penetrating the chest. Additionally, the door may burst open and the driver, if unrestrained, ejected sideways onto the road, especially in a crash that has a roll-over component.



FIGURE 9.3 *Ring fracture around the foramen magnum caused by an impact on the crown of the head in a car driver, who lost the control of his vehicle and crashed into a tree.*

In a rear impact, the driver is violently accelerated and, if no rigid head restraint is fitted to the seat, severe hyper-extension of the neck occurs, often followed by the sequence of deceleration events when the car is cannoned into the vehicle or other obstruction in front, causing the popular, if inaccurate name of 'whiplash'.

In side impacts, the injuries depend upon the amount of intrusion of the driver's door and side panels. Restraint devices can offer no protection, though modern vehicles usually have strengthened side-impact bars built within the doors.

This range of traumatic events can produce the following lesions in drivers not wearing seatbelts or protected by airbags:

- Impact against the fascia can cause abrasions, lacerations and fractures of the legs around knee or upper shin level.
- Pressure of feet on the floor, especially when it is intruded by the engine, can cause fractures anywhere from foot to femur. The leg can also be injured by violent contact with the fascia or dashboard and the hip joint may be dislocated posteriorly. Not uncommonly the pelvis is fractured, often at one or both sacroiliac joints. In Mant's (1978) series of 100 driver fatalities there were 22 pelvic injuries and 31 of the lower limb.
- Impact of the abdomen and chest against the steering wheel may cause severe internal injuries, usually rupture of the liver (50 per cent) and, less often, spleen (36 per cent). There may be bruising of the skin surface, but this is often absent even in the presence of



FIGURE 9.4 *When vehicle structures impinge on the occupants even belt restraints offer little protection. The engine, front suspension, roof and 'A' frame are frequent intruders.*



FIGURE 9.5 *Bruising, laceration and bilateral leg fractures of a car driver in a frontal impact.*



FIGURE 9.6 *Facial injuries in a car driver unrestrained by a seatbelt. Following a deceleration impact his face struck the windscreen, causing the typical small cuts from broken safety glass and lacerations of the temple from striking the windscreen rim or 'A' frame.*

severe internal injuries. Laceration of the skin is rare unless the steering wheel snaps and penetrates the trunk. Other steering-wheel lesions include bruising of the lungs, fractured ribs and sternum, cardiac contusion and haemothorax or pneumothorax or both. Almost 70 per cent of Mant's series had broken ribs.

- Upper limb injuries are less common but may occur from transmitted force through gripping the steering wheel or from impact against the windscreen, pillars, intrusive roof, bonnet or ground when held up in a reflex protective position. Only 19 per cent of Mant's series had arm injuries.
- The most obvious injuries are often those to the face and head as a result of projection against and ejection through, the windscreen. The unrestrained driver rises and flexes forwards so that his forehead and skull are likely to contact the upper rim of the windscreen, leading to lacerations. The face frequently suffers multiple cuts from contact with the shattered safety glass. In most European vehicles the glass is of the toughened, not laminated, variety and, when broken, it shatters into small cubes with relatively blunt edges. These still cause superficial lacerations, often in short 'V-shaped' or 'sparrow-foot' patterns. In themselves they are not a danger to life, but indicate an impact sufficient to hurl the driver on or through the glass. Damage to the eyes is common.
- The impact against the windscreen rim or corner pillar – or after ejection – can cause any type or degree of head injury, including scalp laceration, fractured skull, intracranial haemorrhage or brain damage. In Mant's series there were 42 skull fractures in 100 drivers. This was less than in the front-seat passengers, a figure at variance with Eckert's (1959) series of 300 in the USA, where drivers suffered twice as many head injuries as the passenger, though it is not stated how many accidents were to vehicles occupied only by the driver.
- Hyperflexion of the cervical spine when the head swings can cause fractures or dislocation. There is often a double component in that the hyperflexion of deceleration is followed by a rebound hyperextension when the head strikes an obstruction in front. Rear impacts also cause the double 'whiplash' effect, as already mentioned.

One injury that is frequently overlooked at autopsy is the atlanto-occipital dislocation, which Mant found in a third of his series. Other fractures can occur anywhere in the cervical spine, often at about C5–6. Seatbelt restraint cannot prevent cervical spine damage, though a rigid head restraint can reduce injuries resulting from hyperextension. The thoracic spine is less often damaged, but in unrestrained drivers the same 'whiplash' effect can fracture or dislocate the upper dorsal spine, often around T5–6–7.



FIGURE 9.7 *Mixed injuries in a restrained car driver from a head-on collision. Death was caused by ruptured aorta.*



FIGURE 9.8 *Ruptured aorta in which car occupant, unrestrained by seatbelt, suffered severe deceleration. Aorta has torn in the usual place, the distal arch where the curve of the vessel meets the thoracic spine.*

- A more common thoracic injury associated with deceleration is the ruptured aorta. It may be associated with a severe whiplash effect on the thoracic spine, as the aorta is tethered to the anterior surface of the vertebrae where the distal arch joins the straight descending segment. Probably the most common reason for aortic rupture, however, is the ‘pendulum’ effect of the heart within the relatively pliable thoracic contents. When the thorax is violently decelerated, the heavy cardiac mass attempts to keep moving ahead and may literally pull itself off its basal mountings, the most rigid part of which is the aorta. Separation takes place at the point where the aorta is attached to the spine at the termination of the arch.

  The appearance of the aortic rupture is often of a clean-cut circular break, almost as sharp as if it had been transected with a scalpel. Sometimes there are additional transverse intimal tears adjacent to the main rupture, the so-called ‘ladder tears’, as they can resemble the rungs of a ladder. These may be present when no actual rupture has occurred and may be found as an incidental finding at autopsy. Sometimes they are deep enough to allow a local dissection of blood to seep into the intima, when death has not been virtually instantaneous. Rarely, a major dissection may lead to delayed death some hours or even days later. Ruptured aorta is a common lesion in traffic accidents – in a two-car crash, the author (BK) has seen three transected aortas among the four fatalities.

  The frequency of such tears is common enough for a warning always to be offered to the autopsy prosector not to use undue force on the neck and thoracic structures when removing the organ pluck from the body. Rough handling during this stage can produce artefactual ladder tears in the aorta.
- Other chest injuries can be caused by impact with the steering wheel, ejection through the windscreen or impact with the road. There may be bruising or laceration on the chest from the steering wheel, though padding, collapsible columns, less fragile wheels, airbags and seatbelts have reduced the incidence of this formerly common lesion. Beneath the skin, sternal and rib fractures are common, though fatal visceral injuries can occur without rib fractures in young people because their ribs are more pliable.
- The heart may be damaged even in the absence of external marks or thoracic cage fractures. Bruising of the epicardium and underlying myocardium is not uncommon and the posterior surface may be damaged from impact against the spine. In high-speed impacts, the heart may be completely avulsed from its base and be found lying loose in the chest. Less severe degrees of damage may lacerate the ventricles or atria, and cause gross haemorrhage. Coronary artery thrombosis has been described following contusion over a coronary artery. Penetrating injuries from sternum, ribs or external objects may lacerate the heart directly. Subendocardial haemorrhages on the left side of the interventricular septum and opposing papillary muscles are not a sign of impact, but an index of catastrophic hypotension. They are also seen in head injuries; they can occur within the space of a few beats, as the author (BK) has seen these prominent lesions in an avulsed heart after a military aircraft crash.
- The lungs are frequently injured, either from stabbing by fractured ribs penetrating the pleura or from blunt

impact. The latter often leads to a line of bruising down the posterior part of the lung where it lies in the paravertebral gutter. There may be air bullae or blood blisters under the pleura overlying the bruised areas and a pneumothorax or haemothorax may result. The interior of the lung may be pulped even in the presence of an intact visceral pleura, from transmitted force or massive variations in intrathoracic pressure during the impact. The lung often shows areas of bleeding under the pleura, which may be from direct contusion, from aspiration of blood from other damaged areas of lung or from blood sucked down the air passages from injuries in the nose or mouth.



FIGURE 9.9 *Penetration of the wrist and chest by a wooden component of a bus seat. The victim drove his car at speed into a bus and part of the resulting debris penetrated his left ventricle.*

- The major abdominal injury is a ruptured liver, which may be damaged in any part. A common lesion is central tearing of the upper surface, which may extend deeply and even transect the organ. Less serious damage is often seen in the form of shallow, sometimes multiple, parallel tears on the upper surface of the right lobe. Subcapsular tears can occur with the formation of a subcapsular haematoma, which can rupture later. The spleen also shows shallow tears in some accidents, often around the hilum; in rare cases, it may be avulsed from the pedicle. The mesentery and omentum often show bruising and, rarely, there is laceration and fenestration sufficient to cause a lethal haemorrhage.
- Ejection injuries are common, and lethal in both driver and passengers. This is particularly likely to happen in roll-over accidents. Much research has been pursued by manufacturers to develop anti-burst door locks, which have improved safety. Where there has been considerable distortion of the vehicle frame, however, nothing can prevent the doors from opening or even being torn off. It has been shown by Moore and Tourin's study (1954) at Cornell that ejection injuries followed steering-column lesions as the second most frequent type of trauma and, if a victim was ejected, there was a fivefold greater chance of dying than if he was retained in the vehicle. Moore and Tourin found that when doors burst open a third of the car occupants were ejected.

  Almost any kind of injury, usually multiple, may be sustained after ejection, either from contact with the road surface or (in a significant proportion) from being struck by other vehicles, especially on motorways.



FIGURE 9.10 *Large subcapsular haemorrhage of the liver in a driver who struck the rim of the steering wheel during severe deceleration. Such subcapsular lesions can remain intact for hours or even days, then rupture into the abdominal cavity.*



FIGURE 9.11 *Anterior tear through the full thickness of the liver; there is also a haemorrhage around the suspensory ligament. The victim was a car driver who was impacted against the steering wheel in a frontal crash.*

The front-seat passenger

In Western countries, far more drivers than passengers are killed or injured, but this reflects the fact that a high proportion of cars contain only a driver – a third in Mant's series. In countries with a lower ratio of vehicles to population the converse is true and indeed many accidents are due to gross overcrowding of passenger vehicles. The pattern of injuries is similar to that of the driver, but this position in the car is even more dangerous, as indicated by the title of a safety film made by the French Michelin Tyre Company – *La place du mort*.

Though there is no steering wheel to impact into the chest, its absence also denies the slight protection offered to the driver in reducing the collision with the windscreen, perhaps by giving him something to brace against. Another factor may be that the driver gives his attention constantly to the road and so has momentary warning of an impending crash, compared with the passenger who may be oblivious of imminent disaster and fail to 'brace up' ready for the impact. This may explain the greater number of skull fractures and brain damage in unrestrained passengers in Mant's series, the percentages being 55 per cent and 42 per cent, compared with 64 per cent and 53 per cent, respectively. However, these figures were compiled before seatbelts and airbags became commonplace or even mandatory.

Rear-seat occupants

Before the more widespread use of front seatbelts – now mandatory in many countries – it was thought that the rear-seat position was fairly safe, as indeed it is compared with the front seats.

When the widespread use of seatbelts dramatically reduced the deaths and serious injuries amongst front-seat occupants, the dangers of the back seats became much more obvious. One series showed that 49 per cent of rear-seat passengers in car crashes sustained serious or moderately serious injuries. Campaigns and legislation similar to the previous crusade were waged on behalf of the rear-seat occupants, and the use of these has now become mandatory in Britain and some other countries.

During violent deceleration, unrestrained occupants in the rear are projected forwards and strike the back of the front seats, including head-rests where fitted. They may be thrown over the seats, striking and adding further injuries to the front-seat occupants and may even be ejected through the windscreen, which is broken by them or by the people in front.

In roll-over accidents, they share in the general trauma of being churned inside the passenger compartment, when multiple injuries can occur from contact with fitments, such as mirrors, door handles and window winders. Design changes have reduced these hazards by making handles smoother or countersunk and mirrors that easily snap off their mountings. Ejection is another common cause of death and serious injury in rear-seat occupants, a wide range of head, chest and limb injuries being seen.

THE EFFECT OF SEATBELTS

As stated, many countries now have legislation making the wearing of front and rear seatbelts mandatory. Where no laws exist, persuasion seems to have little effect, in spite of the fact that it is uncontested that their use reduces deaths and serious injury by a factor of 20–25 per cent, as seen in the Australian experience in Victoria and New South Wales. A similar reduction was attained in Britain after the introduction of mandatory laws. Not only did the death rate drop substantially, but facial injuries and especially eye damage was dramatically reduced.

Seatbelts are now almost all of the lap-strap and shoulder diagonal type, the so-called 'three-point attachment belt'. The simple lap-strap is now fitted only in aircraft, where it is really only of token effectiveness. Most car belts are now of the 'inertia-reel' type, which allow slow movement but jam at a sudden tug. The advantage, apart from the comfort, is that they automatically tighten up around the body, as a slack belt is not only less effective but can actually constitute a danger. More complex restraints, such as double shoulder harness and crotch strap, are fitted only in light aircraft, gliders and racing cars. Though far more effective, their use would be socially unacceptable in ordinary road vehicles, as would head-band restraints, which are almost the only way of preventing hyperflexion damage to the cervical spine.

The various forms of strap restraints act by:

- Holding the occupant back against the seat, so that forward projection against the steering wheel, windscreen and corner 'A' frame is prevented. The head, though still subject to hyperflexion, is prevented from smashing through the glass and the body cannot be projected through the screen onto the bonnet or roadway. The belt cannot cope with backward intrusion of the engine, floor, roof or corner pillar if those structures reach the occupant sitting in the original seat position. The effectiveness of the belt is also dependent on the secure fixation of the seat to the vehicle floor.
- The belt restrains the occupants within the vehicle in the event of a door bursting, as ejection greatly increases the risk of death or serious injury. A belt is relatively ineffective in a side impact, except in that it reduces injuries from ejection. It has been reported, however, that head injuries were fewer in restrained victims of side-swipes, though the reason is not clear.

  It has been claimed (mainly in insurance disputes) that seatbelts can worsen this sort of injury by holding the occupant in more dangerous proximity to the intruding impact. There would seem few occasions, however, in which even the unrestrained occupant could voluntarily escape from any significant degree of sudden lateral intrusion from a speeding vehicle.
- Extending the deceleration time and distance by substantial stretching of the belt fabric, which may lengthen by many centimetres during a violent arrest. To be effective the belt must be held tightly against the body to get the maximum restraint, either by adjusting the buckle or using an inertia reel. The belt should never be used again, as it cannot stretch further and may break on the next application of tension.
- Spreading the area of application of deceleration forces. As stated earlier, the body has to absorb whatever G forces are applied to it, as calculated by the $G = C(V^2)/D$ equation. If these are absorbed by a focal impact covering a few square centimetres over the skull, fatal injury may well ensue. The same deceleration diffused against the thorax and abdomen by 500 cm^2 of belt may leave no injury or merely surface bruising.



FIGURE 9.12 *Types of seatbelt restraint: (a) simple lap-strap (dangerous to aorta), (b) diagonal only (can slip underneath), (c) diagonal plus lap-strap (usual car type), and (d) shoulder harness (used in aircraft and racing cars).*

Seatbelt injuries

There is no doubt that seatbelts can themselves cause injury, occasionally of considerable severity. This was one of the arguments of the vociferous anti-seatbelt lobby that opposed legislation in several countries, but it is largely illogical, because an impact that causes seatbelt injuries would almost invariably have caused even worse injuries or death if no seatbelt had been worn.

Another invalid criticism of restraints was that they impede escape from a burning vehicle. Fires involving passenger car crashes are, however, quite rare. A report by Bako *et al.* (1970) from Canada showed that, of 1297 vehicle fatalities, only 24 were from burns, a mere three in passenger cars.

Incorrectly adjusted or positioned straps such as a twisted belt, which reduces the area of contact, can increase the danger of injury. Loose straps allow the body to move relative to the belt before sudden restraint occurs, decreasing the distance between the passenger and facing structures.

Where the person is too small for the harness, such as a child or a small woman, the body may slide from under the strap – the so-called 'submarining' – or it may act as a garrotte around the neck. Some women find that the diagonal strap compresses the breast even in normal use, so that the greatly increased tension during deceleration is likely to injure the gland.

Pregnant women also have problems with belts but, although uterine and fetal injuries have been recorded in accidents, the incidence is relatively low and without the belt the consequences would have been as bad or probably worse.

Injuries from seatbelts can vary from the trivial to the fatal. Bruising is the most common and may be seen either under the diagonal or the transverse component of the three-point belt. It is more common with the single aircraft-type lap-strap because of the smaller area of pressure. Bruising may occur in the abdominal or chest wall, but the dangerous lesions are visceral. The abdominal contents suffer most, especially from single lap-straps. Rupture of the mesentery, or the small or large intestine, usually occurs from acute flexion over a lap-strap. The full bladder can be ruptured as can the caecum. The abdominal aorta can be crushed and the lumbar spine suffer a compression fracture or be dislocated through a disc in the midlumbar region. The posterior arch, pedicles or transverse processes may also be damaged.

The diagonal strap usually prevents serious abdominal injury as it prevents hyperflexion, but it may contribute to thoracic injury. Bruising of the skin and underlying muscles and fractures may accompany a broken clavicle or sternum where the belt crosses them. Several authors (listed at the end of this section) have made detailed studies of seatbelt injuries.

Airbags

In recent years, the use of airbags has spread from only the most expensive vehicles to many standard production cars. The device consists of a large fabric bag, which is normally folded into the steering-wheel hub in the case of the driver position and into the fascia in front of the front-seat passenger.

A sensitive deceleration device triggers the ignition of sodium azide, a solid and highly toxic explosive propellant, which is converted in milliseconds to nitrogen gas. The deploying airbag can reach speeds up to over 300 km/h (>200 mph). Deflation is also rapid, so that residual car control and escape from the vehicle is not impeded.

The inflated bag is designed to interpose itself between the occupant and the frontal structures of the passenger cabin, to cushion the impact and prevent forceful contact and hyperflexion.

In addition to the life-saving capabilities, airbags can also cause serious and even fatal injuries either by the airbag itself or the module cover overlying it in the steering wheel or in the fascia on the passenger side. Injuries can be inflected at any stage of the deployment process, depending on the posture and possible objects between the occupant and the deploying airbag or the module cover. They vary from facial bruising, partial or complete amputation of fingers to dislocated and fractured arms or cervical spine and fatal head injuries. Eye injuries are common and range from mild corneal abrasions and chemical burns from contact with unburned sodium azide or the alkaline byproducts of combustion, which are released into the passenger compartment, to globe rupture from blunt trauma or perforation by interposed objects.

THE VULNERABILITY OF CHILDREN IN VEHICLES

This is a particular problem with several aspects. Many countries have brought in laws to protect children in cars because of their special vulnerability.

First, it is an understandable, but highly dangerous, indulgence for adults to allow small children to travel unrestrained in the front seat of a car. Some parents even allow them to stand gripping the fascia edge immediately below the windscreen, an invitation to facial and eye damage even in minor accidents. The seating of a child on the mother's lap is hazardous, as on violent deceleration either mother and child pitch against the windscreen – or the child flies out of the arms of a belt-restrained mother. The close proximity to the fascia and windscreen causes many deaths and facial injuries, especially to the eyes.

Adult-secured seatbelts will not properly accommodate a child (or even a small adult), because the fixation point on the door pillar is too high even if the straps can be shortened sufficiently to be made tight. The diagonal may pass across the throat and, unless special drop-plates are fitted to the door pillars, the restraint is often worse than useless.

Though some European countries already forbid children under 14 years to travel in front seats, the medical profession in Britain campaigned for similar legislation, as they had done for motorcyclists to wear helmets many years before.

As discussed above, a similar campaign has been successfully waged for rear-seat restraints for children and adults. Banished from the front, children were thought to be safe in the back of the car, but many have died and far more have been injured from being projected against the seat backs, front passengers and internal fitments. Special seats secured on top of the regular seating are required and, for a baby, the cot must be lashed down with equally robust restraints. In 1988, legislation was introduced into the British Parliament to make compulsory the restraint of children in rear seats: from 1991, this law also became applicable to adults.

INJURIES TO MOTORCYCLISTS

Though there are fewer motorcycles than four-wheeled vehicles, especially in developed countries, the rate of injury and death amongst motorcyclists is far higher than among car drivers. For example, in England and Wales in 1989 there were more deaths amongst male motorcyclists between the ages of 16 and 24 than with comparable car drivers (343 compared with 323) even though the ratio of motorcycles to cars is very small in Britain. In the 25–44 age group, 192 motorcyclists died compared with 381 car drivers.

The two extremities of the body suffer most in motorcycle accidents, though Larsen and Hardt-Madsen's analysis in Denmark in 1988 also showed high injury rates for chest and abdomen.

- Because the rider inevitably falls to the ground, head injuries are common and often severe, causing 80 per cent of deaths according to Bothwell (1962). Though crash helmets are mandatory in most countries, the severity of the impact often defeats the protective effect of the helmet.

  Impact with the road surface or another vehicle at speed causes skull fractures at any part of the head, but often temporoparietal. A common complication is a basal skull fracture, especially a 'hinge' fracture. This transverse crack across the floor of the skull, crossing the petrous base or behind the greater wing of the sphenoid bones through the pituitary fossa to the opposite side, has also been called 'the motorcyclist's fracture'.

  Another type is the ring fracture around the foramen magnum in the posterior fossa caused by an impact on the crown of the head. The neck suffers quite often and Mant found cervical spine fractures in over a quarter of his series. Brain damage may be severe, even with a helmet in place. Cortical contusion and laceration, sometimes contrecoup, may be gross enough to cause brain tissue to extrude through compound fractures of the skull. In Mant's series of motorcyclists, 60 per cent had skull fractures and almost 80 per cent had brain damage.
- The legs are often injured, either by primary impact with another vehicle or fixed road structures, or by becoming trapped by part of the motorcycle frame. Lacerations, friction burns and fractures – often compound – are common. Mant recorded leg or pelvic fractures in 55 per cent of his cases.
- Any part of the body may suffer injury, but less often than the extremities. Falling from the machine, especially at speed, can cause rib fractures and visceral damage, especially rupture of the liver and spleen.
- An injury common with motorcycles is the 'tail-gating' accident, where a rider drives into the back of a truck so that the machine passes underneath, but the head of the motorcyclist impacts upon the tail-board. Decapitation may occur in the most extreme cases, but severe head and neck injuries are almost inevitable.



FIGURE 9.13 *Severe brush abrasions or 'friction burns' in a motorcyclist, who came off his machine and skidded across the road surface.*



FIGURE 9.14 *Pulmonary contusions in a motorcyclist, who collided with a truck and was hurled into a signpost. Death was caused by a cranial fracture and multiple injuries of the internal organs.*



FIGURE 9.15 *A pedestrian struck by the front of a car may be projected forwards or lifted onto the vehicle.*

Trucks in many countries must now have strong bars fitted at the rear to prevent this 'tail-gating', which may also happen to motor cars, the rear of the truck smashing into the windscreen and driver.

Safety helmets act both by providing a rigid barrier against impact, which depends partly on the shock absorbing padding within the helmet and by providing a smooth surface, which is designed to skid across the road surface, thus lengthening the stopping distance and time to reduce the G force of deceleration. Their strength is designed to be finite to control the rate of deceleration but in massive impacts seen at high speeds the helmet may be penetrated or the head and brain damaged by the transmission of blunt force. Crash-bars are another safety measure on motorcycles, being fitted in front of the engine to project on each side and protect the legs if the machine falls over. Unless extremely strong, however, such bars can themselves trap the legs if they bend backwards on impact.

INJURIES TO PEDAL CYCLISTS

These form a less severe counterpart of motorcycle lesions, as the pedal cycle has the same instability but far lower speeds. Once again, head injuries figure largely in accidents, as the height above the ground is considerable and the rider suffers from the passive fall, added to by any forward motion or projection from impact by a motor vehicle. Helmets are now worn by many cyclists and naturally afford considerable protection.

Other injuries are from the primary impact from a striking vehicle, which may hit the rider around thigh, hip or chest level. Secondary damage to the shoulder, chest and arm may occur from striking the ground, when friction grazes are common. (A unique injury, though not fatal, was entrapment of the leg between wheel spokes with compression of the soft tissues of the calf, when the leg penetrated the wheel.)

INJURIES TO PEDESTRIANS

Worldwide these are easily the most common road fatalities, probably accounting for more than 50 per cent of the third of a million road deaths each year. In the densely populated areas of the globe where vehicles are greatly outnumbered by people, such as Southern Asia, parts of Africa, and the Middle East and Central America, pedestrian casualties form a significant part of the total mortality.

Most pedestrians are struck by motor cars or trucks, and the type of vehicle makes a difference to the dynamics of the impact, which – unlike injuries to vehicle occupants – is an **acceleration** not a **deceleration** process.

Primary injuries are caused by the first impact of the vehicle on the victim, while secondary injuries are caused by subsequent contact with the ground. Some writers also use the term 'tertiary injuries' to describe the impact with the ground, reserving 'secondary' for additional contact with the vehicle, as when the pedestrian is hurled up against the windscreen. The usual sequence of events is as follows:

- The height of the car bumper bar ('fender') is well below the centre of gravity of the adult pedestrian, which lies in the abdominal region. Thus the first impact tends to knock the legs from under the victim and rotate them towards the oncoming vehicle. Depending on the profile of the front of the car, the struck pedestrian is either thrown forwards in the direction of travel if the bonnet-front is high and blunt – or scooped up onto the bonnet top, as with many slope-fronted modern vehicles.
- If thrown forward, secondary injuries will be suffered as a result of striking the ground, as well as the primary impact on legs and often the hips. If the car speed is appreciable (anything over 20 km/hour is sufficient), the body can be thrown into the air or knocked down flat with a severe impact. The secondary injuries may fracture the skull, ribs, pelvis, arm or thigh.

A further hazard is being run over by the vehicle if the victim is projected directly in front. Sometimes he may be dragged by the under-belly of the car, and seriously soiled and injured, perhaps appearing at the rear if the vehicle does not stop quickly. Many impacts are on the front corner of the car and the pedestrian may then be knocked diagonally out of the path of the car. If thrown into the centre of the roadway, the person can be run down by a different vehicle overtaking in another lane or by one coming in the opposite direction on a single carriageway.

- If scooped up, the victim will land on either the bonnet or against the windscreen or corner-supporting pillar (the 'A' frame). The flat bonnet usually does relatively little damage, though linear abrasions, brush grazes, or friction burns may be seen. Violent contact with the windscreen, especially the rim or side pillars, is the most frequent cause of severe head injury from primary impact.

  Scooping-up can occur at speeds as low as 23 km/hour (about 15 mph; below 19 km/hour the body will usually be projected forwards). If the speed is high, the victim can be thrown up onto the car roof, sometimes somersaulting so that the head strikes the roof. He can then slide or be flung right over the back of the car, landing behind it in the roadway. This is more likely to happen if the car does not brake, but literally drives from under the body.
- In most cases, the scooped pedestrian falls or is flung off on one side of the car or the other, again to suffer secondary injuries in the road and perhaps be run over by another vehicle. The usual pattern of events is that, at the instant of contact – or even slightly before – the driver will apply the brakes violently. The scooped-up victim will acquire the speed of the car by the time he lands on the bonnet, but then the vehicle decelerates. As the adhesion to the shiny surface is small, the newly acquired velocity of the body will cause it to slide off the front of the car as the latter brakes. The victim then hits the ground in front of the car, sustaining secondary injury – and may even be run over during the residual motion of the vehicle before it finally stops.
- In a high-speed impact, which may be anything over 50 km/hour (31 mph), the body can be flung high in the air and for a considerable distance, either to the side or in the path of the car – or even backwards over the roof. In general, the severity of the injuries – both primary and secondary – will be the more severe the higher the speed.

It is impossible to estimate the speed of impact from the nature of the injuries. These can be fatal even at slow speeds of the order of 10 km/hour (6 mph), yet occasionally high-speed impacts can produce only minor damage. In Ashton's (1975, 1978) series half the deaths occurred at speeds less than 48 km/hour (30 mph).



FIGURE 9.16 *At speeds of over 23 km/hour (15 mph) a pedestrian can be 'scooped up' onto a car, suffering head injuries against the windscreen. He may then fall off sideways or – at higher speeds – be thrown over the roof.*


Body attains velocity = V
Initial car velocity = V
1. Scooping-up
Velocity still V
Projected forward
Decelerates: velocity now $V - x$
2. Violent braking
Still decelerating velocity = $V - 2x$
Decelerated to velocity zero
Decelerates to velocity $V - 3x$ but still moving
4. Running over

FIGURE 9.17 *Sequence of events when a carried pedestrian is projected forwards during braking.*

In child victims, although the general pattern of injuries is similar, their shorter height and smaller weight affects the mechanics of impact. The primary contact is higher up their body, so they tend to be hit forwards rather than rotated upwards, though many do become scooped up onto the bonnet. Children tend to be projected further by impact and may be hurled in



FIGURE 9.18 *Primary injury to a pedestrian struck by a car. There is damage to both legs at about the same level, with a compound fracture of the right leg. These are sometimes called 'bumper fractures'. The height of the injuries above heel level should always be measured at autopsy.*

the air at lower speeds than with adults. They are also more prone to be run over by reversing vehicles, especially trucks, as they often play between parked vehicles and – being small – are less visible to the driver. Recent safety measures on trucks include audible reversing warnings that are automatically linked to the gear-shift lever.

- When a pedestrian is struck by a larger vehicle, such as a van, truck or bus, the initial point of impact is higher and may cause primary damage to pelvis, abdomen, shoulder-girdle, arm or head. Because of the profile of these vehicles, there is no scooping-up effect, and the victim is usually projected forwards to suffer secondary damage from road contact and sometimes to be run over.
- The nature of pedestrian injuries reflects these dynamic effects.

The most common trauma is to the legs, some 85 per cent of pedestrian casualties having lower limb injuries. Abrasions and lacerations to the upper shin and knee area are typical of car bumper contact, and fractures of the tibia and fibula, often compound, are so common that they are present in a quarter of fatalities, according to Eckert. The femur is fractured less often, but is no rarity. The midshaft may be broken or the head may be driven into the acetabulum, together with a fractured pelvis. In children, because of their small stature, the femur may be fractured by the low bumper bar. At autopsy, the skin of the lower legs should be incised to seek deep bruising, as the clothing often protects the surface from obvious marking.

When a bumper (fender) strikes a leg, the tibia is often fractured in a wedge-shaped manner; the base of the wedge indicates the direction of the impact (often from behind), the front of the wedge pointing away from the side of contact.



FIGURE 9.19 *Abrasions and laceration at knee level in a pedestrian struck by a car bumper. Their anterior position indicates that the victim was facing the vehicle at the moment of contact, but this may be a last-instant turn during final awareness of the car's proximity.*

If the leg is weight-bearing at the time of the impact, the tibial fracture tends to be oblique, whereas if not stressed, as when being lifted during walking, the fracture line is often transverse. When both shins are damaged, the level may be different on each side; this indicates that the person was moving at the time, with one leg raised in walking or running. Sometimes the level of injury appears too low for the normal bumper height of most cars, but this may indicate that the vehicle was braking violently at the moment of impact, going down on its suspension as the front wheels decelerated or locked, unless dip compensators were fitted.



FIGURE 9.20 *Injuries caused by being run over by a bus. The large rotating wheel has 'flayed' the right leg, stripping the skin and subcutaneous tissues from the muscles. The passage of the adjacent double wheel over the abdomen has extruded the intestines through the perineum.*

Because of impact with the windscreen, pillars and roof, together with secondary contact with the ground, the head is the next most frequently damaged region – and the one which leads to most causes of death. Any type of injury may be sustained, as described in Chapter 5. Traffic accidents are the most frequent cause of skull fracture, especially of the base. Fractures of chest, arm and pelvis and injuries to the abdomen follow in frequency. Often the injuries are concentrated on one side, usually on the opposite side to the point of primary impact, because the body was thrown down onto the road. Because of rotation and the variable posture from being thrown off the car structure, however, the injuries are often widespread and may show no particular pattern.

Soft tissue injuries are common and, apart from abrasions, bruises and lacerations, muscle laceration and crushing can occur. A characteristic lesion from running-over, as opposed to knocking-down, is the 'flaying' injury, where a rotating motor wheel tears the skin and muscle from a limb or head. The rotatory effect against a fixed limb may strip off almost all tissue down to the bone. When a wheel passes over the abdomen or pelvis, multiple parallel striae or shallow lacerations may occur near the contact area because of ripping tension in the skin.

When a wheel passes over the pelvis, abdomen or head, there may be great internal damage with little surface injury. The weight of a large vehicle can virtually flatten a head, crushing the cranial vault. Often the brain is extruded through scalp lacerations, as may be the intestine through an abdominal wound. The pelvis may flatten out when run over, the symphysis or superior rami breaking, and one or both sacroiliac joints becoming detached. Any type of intra-abdominal injury may occur from ruptured liver and spleen to perforated intestine, lacerated mesentery and fractured lumbar spine. In the chest, ribs, sternum and thoracic spine may fracture, and heart and lung damage occur from crushing or laceration from jagged ribs. A 'flail chest' is sometimes produced when a heavy wheel runs across the supine body, breaking all the ribs on each side in the anterior axillary line.

Patterned injuries may be important, in that they can assist the police in identifying a vehicle in a 'hit-and-run' accident. The most common is a tyre pattern outlined in intradermal bruising and these should be measured carefully and photographed. These marks are usually caused by the skin being forced into the grooves of the tyre tread, the edge of the raised rubber tracing out the pattern. The elevated parts do not leave bruises, but may imprint dirt on the skin.

Paint fragments and glass shards are also trace evidence that must be carefully retained, as the forensic laboratory may be able to identify the make and model of vehicle involved, and match the fragments when a suspect car is examined.

Parts of the vehicle may leave patterned imprints on the skin, such as headlamps, mirrors or other components. Safety regulations for manufacturers have now almost eliminated the dangerous devices such as bonnet mascots, projecting door handles and non-flexible mirrors that used to adorn older cars. Metallic and plastic objects may still be found in the tissues from time to time, however; the author (BK) has recovered a door handle from the interior of the liver and a chromium bonnet insignia from a cerebral hemisphere. Any such artefacts must be preserved for the police in cases in which the identity of the vehicle is not known.

In Britain, where traffic drives on the left side of the road, it is more common for pedestrians to be struck on the right side as they walk off the pavement. Many, however, are struck facing the vehicle, from turning during last-minute awareness, and some are hit from behind.



FIGURE 9.21 *A patterned injury in a pedestrian struck by a truck. The circular bruise and abrasion over the front of the shoulder are from a headlamp rim. There is also a well-demarcated imprint around the left eye from some other projection on the vehicle.*



FIGURE 9.22 *Primary pedestrian injury. The pattern is caused by the bumper bar striking the leg. The height from the heel should always be measured for the police to compare with the vehicle – though during extreme braking, many vehicles will dip down at the front, thus lowering their bumper height.*

These factors will all affect the distribution of injuries, but it is too hazardous to try to reconstruct unwitnessed events in any detail from a study of the injuries. Suprarenal haemorrhage is more common in the right gland than the left after a traffic injury in Britain (Johnson, unpublished communication), but this observation must be modified by the fact that many such haemorrhages occur several days after the trauma and are usually the result of general systemic effects, rather than direct impact.

CAUSE OF DEATH IN TRAFFIC ACCIDENTS

In gross injuries this is often obvious, as in the crushed head with extrusion of brain or rupture of the aorta. Often multiple injuries make it difficult to decide which was the most serious and mortal lesion, but in such cases it is quite acceptable to use the term ‘multiple injuries’, preferably listing several of the most lethal.

When death occurs on the road or soon afterwards, there is usually macroscopic evidence of gross musculoskeletal or organ damage, severe haemorrhage, blockage of air passages from blood, or traumatic asphyxia from fixation of the chest caused by crushing some part of a vehicle.

Delayed death can be caused by continuing bleeding, secondary haemorrhage, renal failure from hypotension and/or extensive muscle damage, fat embolism, local infection, chest or other systemic infections, myocardial or cerebral infarction and other sequelae discussed in Chapter 13.

The presence of natural disease is always an important consideration in all transportation deaths, as a possible cause or contribution to the accident. In pedestrians, a sudden collapse



FIGURE 9.23 *Intradermal bruising on the forehead of a live boy who was found wandering in the street with amnesia for recent events. He had been struck by a 'hit-and-run' car, which left identifiable tyre marks on the skin. An astute casualty officer had a photograph taken as the marks faded in a few hours.*

in the roadway may lead to fatal injuries when a vehicle comes along – or even a dead body being run over by the next car.

Similarly, defects in sight or hearing may have contributed to the accident, though this is almost never detectable at autopsy, unless there are gross corneal or lens abnormalities. Of course, the possibility of drug or alcohol intoxication in the pedestrian victim must always be considered.

Where drivers or pilots are concerned – or even shipmasters – the presence of disease or intoxication may be a vital element, with both civil and criminal connotations possible.

Generally speaking, sudden natural disease does not often cause road vehicles to go out of control, as there seems to be a sufficient warning in most instances of cardiac or cerebral disablement, to allow the driver to pull over and stop.

Even the regular medical checks on older drivers legally enforced by some countries are no warranty that sudden collapse will not occur the very next day. The same applies to air pilots, as the VC-10 crash at London Airport proved some years ago, when the hypertensive pilot with coronary artery disease collapsed on take-off after an altercation with his co-pilot.

Schmidt *et al.* (1990) analysed 39 deaths at the wheel in Germany and found that 97 per cent had cardiovascular disease and 90 per cent had coronary heart disease. This was confirmed in a more recent retrospective study covering a 15-year time period in Munich, Germany, ranging from 1982 until 1996. Ischaemic heart disease was the underlying cause of death in 113 (84%) of the 147 natural deaths at the wheel. Morild (1994) found that 14 of 133 traffic deaths in Norway had died of natural disease, again predominantly coronary atherosclerosis.

The autopsy on a road traffic death

The autopsy is in general identical to the usual procedure, but with special attention to the following points:

- As criminal proceedings against a driver may follow, legal matters such as identity of the body and continuity of evidence must be assured, as discussed in Chapter 1.
- The body should be seen clothed, if brought dead to the mortuary or hospital, so that injuries can be matched against soiling and damage to the garments. Often this is not possible, especially if temporary survival allowed admission to a hospital or accident department, but where practicable the clothing should be preserved and examined by the pathologist. In any event, the clothes should be retained by the police for submission to the forensic science laboratory, usually when criminal proceedings are likely.
- Blood samples must be retained for blood grouping and now perhaps even 'DNA fingerprinting' in case a 'hit-and-run' vehicle is found with blood or tissue traces upon it. Sometimes hair samples may be required for the same purpose. Where death occurs within 12 or even 24 hours of the time of the accident, blood analysis for alcohol is essential, whether in the driver or pedestrian (see Chapter 28). Where possible, screening for drugs of dependence and common medicinal substances that might have caused drowsiness should be carried out. In combination with alcohol, even low levels of sedative, hypnotic and antihistamine drugs may be relevant in the causation of an accident. In certain cases, where leakage of carbon monoxide is suspected, the circumstances will suggest analysis of the blood for carboxyhaemoglobin concentration.
- The external examination, as in all trauma deaths, is vital and should be detailed, accurate and fully recorded. The height of major or patterned injuries above heel level must be noted, in order to compare these against dimensions of a vehicle. Patterned injuries must be photographed with a scale in view. Any foreign bodies or particles, either in the clothing, hair, on the skin or in the wounds, must be carefully retained for forensic science examination, especially in a 'hit-and-run' accident, where the identity of the vehicle may be vital.

All types of trace evidence may be found by a pathologist, from paint flakes and glass debris (which may be traced to a certain make, age, type and even individual vehicle) to parts of the vehicle structure. In past years, the author (BK) has retrieved a Renault door handle from inside a liver and an Austin bonnet insignia from within a brain.

- A full autopsy must be carried out, not merely a catalogue of injuries. The presence of any natural disease is relevant, especially if it might have contributed to the accident, either by causing a driver to lose control or ability to drive, or a pedestrian to exercise proper caution or behaviour in the roadway. Old and recent cardiac and cerebral lesions are particularly important, as is any evidence of a fit, such as a bitten tongue, or old meningeal adhesions over cortical damage. It is almost impossible to assess visual acuity at autopsy, but obvious lesions such as lens opacities must be noted. Similarly, it is virtually impossible to give any opinion on acuity of hearing from autopsy findings unless there is a gross neurological abnormality in the auditory tract.

SUICIDE AND HOMICIDE BY MOTOR VEHICLE

There is little that the pathologist can contribute to the elucidation of motivation in traffic accidents, as it is circumstantial and sometimes forensic-laboratory evidence that is more likely to reveal a non-accidental cause. Homicidal traffic deaths are rare, though the author (BK) has been involved in one incident where racial hatred led to the running-down of youths of one ethnic group – and another where a man repeatedly crashed the near-side of his own car in an effort to kill his passenger (his wife). There are no specific pathological features that can assist, except that the incident is likely to occur at relatively high speed, without braking effects. The victims of homicide by other means – or persons rendered unconscious first – may be deliberately placed in motor vehicles which are then crashed, preferably with a subsequent fire. The author (BK) dealt with one such case where a husband placed the body of his strangled wife in his car and secretly pushed it over the edge of a mountain road. Unfortunately (for him), he left the ignition key in the 'off' position. This faking of a vehicular 'accident' to conceal homicide is by no means unknown, the author (BK) being involved in another case where a police officer disposed of the body of his wife who died in suspicious circumstances, by crashing her car and smashing the windscreen with a hammer to add to the effect.

In such circumstances, the pathologist's role is to match the injuries with a traffic accident, to detect any which are atypical. For instance, focal depressed fractures of the skull of the type caused by a weapon are unusual in a car occupant unless there was a localized intrusion of the vehicle roof. The ante-mortem nature of the injuries should be demonstrated, though this is not always possible. When there is a fire, some evidence of ante-mortem burns, soot inhalation or carbon monoxide absorption should be sought, though – as mentioned in Chapter 11 – some flash petrol fires may kill before any monoxide is absorbed. Where the victim was unconscious though not dead, no such differentiation is possible. Full analysis for alcohol and stupefying drugs must be made if there is any suspicion.

Attempts at deliberate self-destruction by the use of a motor vehicle are said to be not uncommon (Selzer and Payne 1962), though this is difficult to prove in most cases. Once again, the evidence is more likely to be based on circumstantial rather than medical evidence – a matter for the investigating authorities rather than the pathologist. Driving at speed into the path of an oncoming truck or into a solid obstruction at the roadside are the methods employed, though it is hard to prove in the absence of definite evidence. It has been said that the imprint of the accelerator pedal on the undersurface of the shoe may be an indication, though this can never be the only indication. A witnessed lack of other causative factors may offer some corroboration, but this is police business, not pathology.

RAILWAY INJURIES

These are not uncommon, especially in countries with many 'level crossings' (called 'grade crossings' in the USA), where a public road crosses a railway track with either no barrier at all or with only a flimsy lifting pole. Many vehicles are struck each year by passing locomotives.

Few rail passengers are killed or injured in moving trains compared with accidents to railway staff and to other types of accident on railway property. Track workers may be run down and some die from electrocution from overhead cables. The pathology of all these is no different from accidents elsewhere, the interest lying in the occupational epidemiology and preventive aspects.

One worrying development in recent years is the malicious damage caused to trains, either by placing objects on the tracks, which may cause a derailment, or the dropping of objects from bridges. The author (BK) has conducted an autopsy on a driver killed by a concrete block dropped from a bridge, which smashed through the windshield of his cab.

The other fairly common railway fatality is the suicide who lays himself in front of an approaching train. Decapitation is the most common injury and the obvious features are the local tissue destruction, usually with grease, rust or other dirt soiling of the damaged area.

The usual search for alcohol and other drugs must be made, as suicides often employ multiple methods to ensure self-destruction. As well as lying down before a locomotive,



FIGURE 9.24 *Amputation of the right arm and bruising of the face and chest in a pedestrian struck by a passing locomotive.*

another common method of suicide in large cities is to jump from the subway platform of an underground 'tube' or 'metro' system. Here injuries are sometimes complicated by high-voltage electrical lesions, as the typical traction voltage of an electric railway is in excess of 600 volts.

REFERENCES AND FURTHER READING

Ahmed M. 1978. Motorcycle spoke injury. *Br Med J* **2**:401.

AMA Committee on Medical Aspects of Automotive Safety. 1963. Automobile safety belts during pregnancy. *JAMA* **221**:20–1.

Anonymous. 1977. Safety of children in cars [leading article]. *Br Med J* **1**:2.

Anonymous. 1979. Motorcycle and bicycle accidents [special correspondent]. *Br Med J* **1**:39–41.

Anonymous. 1979. Pedestrian accidents [special correspondent]. *Br Med J* **1**:101–4.

Ashton SJ. 1975. The cause and nature of head injuries sustained by pedestrians. *2nd Conference of Biomechemical Serious Trauma*, Lyon, France.

Ashton SJ, Mackay GM. 1978. Pedestrian injuries and death. In: Mason JK (ed.), *The pathology of violent injury.* Edward Arnold, London.

Baik S, Uku JM, Joo KG. 1988. Seat-belt injuries to the left common carotid artery and left internal carotid artery. *Am J Forensic Med Pathol* **9**:38–9.

Baker SO. 1979. Motor vehicle occupant death in young children. *Pediatrics* **64**:860–5.

Baker SP, Spitz WU. 1970. Age effects and autopsy evidence of disease in fatally injured drivers. *JAMA* **214**:1079–88.

Baker SP, Spitz WU. 1970. An evaluation of the hazard created by natural death at the wheel. *N Engl J Med* **283**:405–9.

Bako G, Mackenzie WC, Smith ES. 1970. What is the risk of being burned in a motor vehicle crash? A survey of crash fatalities in alberta. *J Traffic Med* **4**:20–4.

Bothwell PW. 1962. The problem of motor cycle accidents. *Practitioner* **188**:475–6.

Burke DC. 1973. Spinal cord injuries and seatbelts. *Med J Aust* **2**:801–6.

Buttner A, Heimpel M, Eisenmenger W. 1999. Sudden natural death 'at the wheel': a retrospective study over a 15-year time period. 1982–1996. *Forensic Sci Int* **103**:101–12.

Byard RW, Green H, James RA, *et al.* 2000. Pathologic features of childhood pedestrian fatalities. *Am J Forensic Med Pathol* **21**:101–6.

Christian MS. 1975. Non-fatal injuries sustained by back seatbelt passengers. *Br Med J* **1**:320–2.

Christian MS. 1976. Non-fatal injuries sustained by seatbelt wearers: a comparative study. *Br Med J* **2**:1310–12.

Clarke J, Milroy C. 1993. Pedestrian injuries and death. In: Mason JK (ed.), *Pathology of trauma*, 2nd edn. Edward Arnold, London.

Copeland AR. 1991. Pedestrian fatalities. The metropolitan dade county experience, 1984–1988. *Am J Forensic Med Pathol* **12**:40–4.

Cunningham K, Brown TD, Gradwell E, *et al.* 2000. Airbag associated fatal head injury: case report and review of the literature on airbag injuries. *J Accid Emerg Med* **17**:139–42.

Davis GG, Alexander CB, Brissie RM. 1997. A 15-year review of railway-related deaths in Jefferson County, Alabama. *Am J Forensic Med Pathol* **18**:363–8.

Denaner RM, Fitchett VH. 1975. Motorcycle trauma. *J Trauma* **15**:678–81.

DiMaio DJ. 1971. A survey of sudden unexpected deaths in automobile drivers. *Proc 3rd Int Assoc Accident Traffic Med*, pp 75–80.

Eckert W. 1959. Traumatic pathology of traffic accidents; review of 302 cases. *J Forensic Sci* **4**:3–20.

Eckert WB. 1977. *Transportation injuries.* In: Tedeschi L, Eckert WB (eds), *Forensic medicine*. Saunders, Philadelphia.

Edland SF. 1971. The suicide crash. *Proc 3rd Int Assoc Accident Traffic Med*, pp 81–3.

Fisher P. 1965. Injury produced by seatbelts: report of two cases. *J Occup Med* **7**:211–16.

Foster GR, Dunbar JA, Whittet D, *et al.* 1988. Contribution of alcohol to deaths in road traffic accidents in Tayside 1982–6. *Br Med J Clin Res Ed* **296**:1430–2.

Gadd CC. 1966. The use of a weighted impulse criterion to estimating injury hazard. *Proc Tenth Stapp Car Crash Conference*. Society of Automotive Engineers, New York, p. 164.

Gissane W, Bull JP. 1964. Motorway fatalities. *Br Med J* **1**:75–6.

Gissane W, Bull JP, Roberts B. 1970. Sequelae of road injuries. *Injury* **1**:195–200.

Goldberg BA, Mootha RK, Lindsey RW. 1998. Train accidents involving pedestrians, motor vehicles, and motorcycles. *Am J Orthop* **27**:315–20.

Guichon DM, Myles ST. 1975. Bicycle injuries: one-year sample in Calgary. *J Trauma* **15**:504–6.

Hall RR, Fisher AJ. 1972. The influence of car frontal design on pedestrian trauma. *Accid Anal Prev* **4**:47–51.

Hamilton JB. 1968. Seat belt injuries. *Br Med J* **2**:485–6.

Harruff RC, Avery A, Alter-Pandya AS. 1998. Analysis of circumstances and injuries in 217 pedestrian traffic fatalities. *Accid Anal Prev* **30**:11–20.

Hawley DA, Clark MA, Pless JE. 1995. Fatalities involving bicycles: a non-random population. *J Forensic Sci* **40**:205–7.

Hendrickx I, Mancini LL, Guizzardi M, *et al.* 2002. Burn injury secondary to air bag deployment. *J Am Acad Dermatol* **46**:S25–6.

Hotz GA, Cohn SM, Popkin C, *et al.* 2002. The impact of a repealed motorcycle helmet law in Miami-Dade county. *J Trauma* **52**:469–74.

Huelke DF, Chewin WA. 1968. *The energy-absorbing steering column*. Highway Safety Research Institute, Ann Arbor, Michigan.

Huelke DF, Davis RA. 1969. *A study of pedestrian fatalities in Wayne County, Michigan*. University of Michigan, Ann Arbor, Michigan.

Huelke DF, Gikas PW. 1967. Ejection – the leading cause of death in automobile accidents. *Conf Proc Soc Automative Eng*, New York.

Huelke DF, Gikas PW. 1968. Causes of death in automobile accidents. *JAMA* **203**:1100–3.

Huelke DF, Kaufer H. 1975. Vertebral column injuries and seat belts. *J Trauma* **15**:304–18.

Huelke DF, Sherman HW. 1971. Automobile occupant ejection through the side door glass. *Conf Proc Soc Automative Eng*, Detroit.

Huff GF, Bagwell SP, Bachman D. 1998. Airbag injuries in infants and children: a case report and review of the literature. *Pediatrics* **102**:e2.

Jamieson KG, Kelly D. 1973. Crash helmets reduce head injuries. *Med J Aust* **2**:806–9.

Jenkins J, Sainsbury P. 1980. Single-car road deaths – disguised suicides? *Br Med J* **281**:1041.

Jones AM, Bean SP, Sweeney ES. 1978. Injuries to cadavers resulting from experimental rear impact. *J Forensic Sci* **23**:730–4.

Kamdar BA, Arden GR. 1974. Road traffic accidents fatalities – a review of 142 post-mortem reports. *Postgrad Med J* **50**:131–6.

Karger B, Teige K, Buhren W, *et al.* 2000. Relationship between impact velocity and injuries in fatal pedestrian-car collisions. *Int J Legal Med* **113**:84–8.

Kelsch G, Helber MU, Ulrich C. 1996. [Craniocerebral trauma in fall from bicycles – what is the effect of a protective helmet?] *Unfallchirurg* **99**:202–6.

Knight B. 1976. An unnecessary risk to children. *Br Med J* **1**:180.

Larsen CF, Hardt Madsen M. 1988. Fatal motorcycle accidents in the county of Funen (Denmark). *Forensic Sci Int* **38**:93–9.

Lee WB, O'Halloran HS, Pearson PA, *et al.* 2001. Airbags and bilateral eye injury: five case reports and a review of the literature. *J Emerg Med* **20**:129–34.

Lifschultz BD, Donoghue ER. 1994. Deaths due to forklift truck accidents. *Forensic Sci Int* **65**:121–34.

Mackay GM. 1969. Some features of traffic accidents. *Br Med J* **4**:799–801.

Mackay GM. 1975. One engineer's view of human injury. *Injury Br J Accident Surg* **9**:179–83.

Mant AK. 1978. Injuries and death in motor vehicle accidents. In: Mason JK (ed.), *The pathology of violent injury* (and 2nd edition, 1993). Edward Arnold, London.

Mason MA. 1988. Restraining infants in cars. *Br Med J* **296**:1345–6.

McCarrol JR. 1962. Fatal pedestrian automotive accidents. *JAMA* **180**:127–30.

McCarthy M, Gilbert K. 1996. Cyclist road deaths in London 1985–1992: drivers, vehicles, manoeuvres and injuries. *Accid Anal Prev* **28**:275–9.

McDonald QH. 1979. Children's car seat restraints: when top-tether straps are ignored, are these restraints safe? *Pediatrics* **64**:848–55.

Moore J, Tourin B. 1954. *Study of automotive doors opening under crash conditions.* Cornell University, New York.

Morild I. 1994. Traffic deaths in western Norway. A study from the county of Hordaland 1986–1990. *Forensic Sci Int* **64**:9–20.

Morton J. 1968. The suicide driver. *Traffic Saf* **68**:37–40.

Mouzakes J, Koltai PJ, Kuhar S, *et al.* 2001. The impact of airbags and seat belts on the incidence and severity of maxillofacial injuries in automobile accidents in New York state. *Arch Otolaryngol Head Neck Surg* **127**:1189–93.

Murphy GK. 1976. Death on the railway. *J Forensic Sci* **21**:218–26.

Ostrom M, Eriksson A. 2001. Pedestrian fatalities and alcohol. *Accid Anal Prev* **33**:173–80.

Pearlman JA, Eong KG, Kuhn F, *et al.* 2001. Airbags and eye injuries: epidemiology, spectrum of injury, and analysis of risk factors. *Surv Ophthalmol* **46**:234–42.

Petersen PJ, Petty CS. 1962. Sudden natural death among automobile drivers. *J Forensic Sci* **7**:274–7.

Rowe BH, Rowe AM, Bota GW. 1995. Bicyclist and environmental factors associated with fatal bicycle-related trauma in Ontario. *Can Med Assoc J* **152**:45–53.

Schmidt P, Haarhoff K, Bonte W. 1990. Sudden natural death at the wheel – a particular problem of the elderly? *Forensic Sci Int* **48**:155–62.

Selzer ML, Payne CE. 1962. Automobile accidents, suicides and unconscious motivation. *Am J Psychiatry* **119**:237–44.

Sevitt S. 1968. Death after road traffic accidents. *Med Sci Law* **8**:271–87.

Sevitt S. 1968. Fatal road accidents: injuries, complications and cause of death. *Br J Surg* **55**:481–4.

Sevitt S. 1973. Fatal road accidents in Birmingham: times to death and their causes. *Injury* **4**:281–93.

Shennan J. 1973. Seat belt syndrome [letter]. *Br Med J* **4**:786.

Simpson K. 1960. The interpretation of the surface pattern of vehicular injuries. *Med Sci Law* **1**:420–8.

Smith WS, Kaufer H. 1969. Patterns and mechanisms of lumbar injuries associated with lap seat belts. *J Bone Joint Surg Am* **51**:239–54.

Solheim K. 1964. Pedestrian deaths in Oslo traffic accidents. *Br Med J* **1**:81–3.

Transport and Road Research Laboratory. 1974. *Pedestrian injuries*. Department of the Environment, London.

Van der Linden WJ. 2002. Dislocated fracture of the mandibular condylar process after airbag deployment: report of a case. *J Oral Maxillofac Surg* **60**:113–15.

Whent P. 2000. Rail accident investigation. In: Siegel JA, Saukko PJ, Knupfer GC (eds), *Encyclopedia of forensic sciences*. Academic Press, San Diego, San Francisco, New York, Boston, London, Sydney, Tokyo, vol 1, pp. 42–47.

Wilks PM. 1967. Safety in car design. *Proc R Soc Med* **60**:955–8.

Wolf RA. 1962. The discovery and control of ejection in automobile accidents. *JAMA* **180**:220–2.

Wyatt JP, Martin A, Beard D, *et al.* 2001. Pedestrian deaths following collisions with heavy goods vehicles. *Med Sci Law* **41**:21–5.

CHAPTER 10

Abuse of human rights: deaths in custody

■ Evidence of fatal physical abuse 301
■ Extrajudicial execution 305
■ Death in custody 305
■ References and further reading 308

Regrettably, abuse of human rights is so widespread on a global scale that some reference must now be made in forensic pathology texts to the physical manifestations of torture. It is stated by Amnesty International (2001) that in a third of the member states of the United Nations torture of one kind or another is practised, in spite of them being signatories to United Nations resolutions banning these atrocities. According to Amnesty International's worldwide report on torture based on a 3-year investigation (2000), currently more than 150 countries routinely torture people compared with 98 countries in their previous report in 1984.

Although most torture does not result in death, there are sufficient cases of physical abuse of human rights that progress to fatality that a number of organizations offer expertise when any alleged case needs to be investigated, usually calling upon forensic pathologists to assist them in such circumstances. These include Amnesty International (based in London), Physicians for Human Rights (PHR), the Medical Foundation for the Treatment of Victims of Torture (London) and many others.

EVIDENCE OF FATAL PHYSICAL ABUSE

In many instances the autopsy appearances of fatal abuse are no different from those by any other homicide, and the confirmation of lethal torture must depend upon circumstantial and other corroborative evidence, which is no concern of this book. For example, if a political detainee is kicked to death, the physical findings may be identical to those of a murder by kicking in a street crime. Similarly, head injuries, shooting and suffocation may show no variation from the same modes of death outside a political context.

Certain features may arouse suspicion or provide definite evidence that the death had political overtones. The word 'political' is used in a wide sense as many abuses of human rights are not directed or even condoned by higher levels of government, though often there is an indifference to being informed about such activities. Many instances of illegal death and injury are perpetrated by the military or the security forces – and even here, the level of command that directs or condones the abuse varies greatly. In general, the civil police and the regular prisons are usually not the perpetrators of gross abuse, though there are many exceptions. It tends to be the armed forces, clandestine security police, and special detention camps that are most often guilty of torture and illegal executions.

One of the features that characterizes torture and abuse is that the victim is usually either in detention or some form of custody, or is temporarily in the power of the authorities, even if that means that soldiers have just burst into a private house. All deaths in custody – discussed later in the chapter – should be examined with care, as much to ensure that the guardians are cleared of any suspicion of ill-treatment as to discover any ill-treatment itself. The fatal event may be quite different from the non-fatal abuse, as a victim who is beaten may be disposed of by shooting. As in all forensic work, the pathological investigations can only be part of the overall enquiry, another example of cooperation and teamwork between all disciplines.

One of the major differences – and great problems – in the investigation of torture and abuse of civil rights is that the authorities in the state where it occurred may be totally uncooperative and, indeed, wholly hostile to impartial enquiry. It is through respected international agencies, such as the Red Cross, Amnesty International and Physicians for Human Rights, that pathologists have the best chance of being allowed access to the relevant material, and the organizations mentioned above are willing to undertake or assist legitimate investigations anywhere in the world.

One particular problem associated with human rights abuse is the frequent long delay before being able to examine the victim. In the living, they may have been detained for months or years after the ill-treatment, or may have been exiled or in hiding before they have the opportunity to be seen by an impartial medical observer, by which time acute injuries will have healed, bruises absorbed and wounds and burns scarred over. In the dead, long-term post-mortem changes are common: the body may have been buried and exhumed before examination.

Even skeletal material is all that is sometimes available, as in the 'lost children' of Argentina or in the killing fields of Uganda. Problems of identification are often difficult. Contemporary photographs of injuries are often of poor quality and the facilities for autopsy are primitive in some of the less developed countries. When the suspicion, lack of cooperation and often open hostility of the local authorities is added, the task for the visiting pathologist is formidable indeed.

The following types of injury may confirm or arouse suspicion of torture, though, as stated, virtually any type of injury can be inflicted deliberately to extract information, punish or degrade the victims or to exterminate them. Repetition of a particular injury, such as 'tramline' bruises from beating, is suspicious, because in ordinary assaults and homicides such excessive and perhaps regularly placed repetitive lesions would be unusual.

- Beating is one of the most common forms of torture and can take many forms, varying both with the weapon used and the part of the body injured. Blows both to the head and to other parts of the body were present in all the cases reported by Hougen (1988). Unless severe and repeated, beating is not often the sole cause of death, though this can occur from haemorrhage, sepsis, injured internal organs, or from sheer exhaustion and pain in an already debilitated victim. The blows may be inflicted by fist or foot, but are more often applied with a weapon. The use of a whip or lath-like instrument is common, but metal or wooden bars, clubs, batons, rifle butts or belts may be used. More recently, lengths of plastic hosepipe or tubing have come into favour in some parts of the world.

Many of these produce a characteristic skin lesion, namely a single- or double-edged linear bruise. The bruise may be a line of confluent petechial haemorrhages or a continuous mark of red skin. The 'tramline' bruise is a double line of parallel marks with a pale unbruised zone between them, caused by the impact of a rectangular or circular-sectioned object. This is described in more detail in Chapter 4.

The bruising may be intradermal, when it reproduces the pattern of the weapon well. If a leather whip with, for example, plaited thongs, is struck against the skin, the pattern may be imprinted clearly on the skin.



FIGURE 10.1 *A scar about one year after the original injury. The female victim was shot while escaping from an East African concentration camp. The wound was opened surgically and healed imperfectly with keloid formation. The other surgical incision is of more recent origin. Such scars will remain unaltered for life, apart from possible increase in the keloid formation.*



FIGURE 10.2 *Recent bruising inflicted within the previous 2 days, from blows by lengths of plastic tubing about 15 mm wide. The injuries show parallel 'tramlining' typical of impact from a cylindrical weapon. The assailants were vigilantes administering a punishment beating to an alleged collaborator in a Middle Eastern country.*

Buckles on belts and other recognizable artefacts may occasionally be useful in identifying the weapon. Where the bruising is deeper, no such pattern is likely. The skin may be broken, causing abrasions or lacerations and, if the full thickness is breached, healing will cause scars, which may even be recognizable as 'tramlines'.

Repeated beating leaves multiple marks, which though overlapping and often criss-crossing, may have a generally similar orientation that indicates that the attacker stood in a relatively fixed position to the victim. For example, lashing across the back may leave marks running from top right to bottom left, suggesting that a right-handed perpetrator stood to the left of the victim.

The use of a multi-thonged whip, such as a 'cat-o'nine-tails' will leave a series of marks, again generally in the same orientation. The thongs tend to be narrow and may cause linear marks with tramlining. There may be metal tags or knots on the end of each thong, which can cause focal damage. The back is the most frequent target, but whipping and beating may be applied to the buttocks, thighs, front of chest, breasts and abdomen, lower legs, soles of the feet, and even perineum and genitals.

Beating of the soles of the feet with canes or rods is a torture rooted in antiquity and this so-called 'falanga' may leave relatively little to see, even though it is extremely painful and debilitating. The tough tissue and thick fascial planes of the foot do not readily reveal bruising, though it may be found on deep dissection in victims who have been killed by some other means.

If injuries were inflicted months before examination, little or nothing may be found unless the skin was broken, when scarring will have taken place. Sometimes, however, faint red lines may be seen in pale-skinned people and in those with appreciable racial melanin pigment there is often hyperpigmentation along the lines of injury. Where severe damage has been caused and sometimes where there is scar tissue, depigmentation may be seen.

- Burns are unfortunately common and may be either the actual cause of death or visible as recent or scarred evidence of previous torture. All kinds of burns may be suffered. The author (BK) has seen extensive burns from molten rubber dripped onto victims from motor tyres suspended overhead, hot irons applied to skin, ignited kerosene-soaked rags wrapped around limbs and numerous burns from cigarettes pressed into the skin. Knowledge of local practices, such as the burning motor tyre 'necklace', can help identify burns in typical sites. Where molten liquids have been dripped from above onto a bound-up victim, there may be shadow areas that indicate the direction of contact, which makes any innocent explanation highly unlikely. In survivors, scarring occurs in all but the most superficial burns, and may lead to large, unsightly cicatrized areas. In victims of African origin, large keloids may form, and further complicate the damage and attempts at surgical treatment.
- Cutting and stabbing may be inflicted with a variety of weapons, but wounds from knives and bayonets are most common in the context of torture and extrajudicial execution. The features are identical to



FIGURE 10.3 *Scars from beating with a thin metal rod in an East African torture camp. Though more than a year old, the 'tramline' nature of one of the scars is outlined in keloid.*



FIGURE 10.4 *Keloid scars from extensive burns during torture. The elderly lady was tied to a chair and a burning motor tyre suspended over her. The shadowed area between the breasts indicates the downward trickle of molten burning rubber. Her face was also extensively scarred.*



FIGURE 10.5 *The scar of a bayonet stab wound inflicted many months earlier in a Ugandan torture camp. Though scars are usually of little help in interpreting the cause of the injury, here the elliptical shape of the original stab wound can still be seen as a keloid scar and even the sharp upper end of the blade edge, as opposed to blunter lower end.*

those described in Chapter 4. The site on the body may be anywhere, but the chest and upper arms seem to be favourite targets. The scars of old stab wounds, such as those from a bayonet, may still be recognizably elliptical many months or years after infliction.

- Clubbing and blunt injury is extremely common, either to cause death or as a form of abuse. It is sometimes dispensed almost casually, as when guards lay about themselves with rifle butts against the inmates of detention camps. Again the features are non-specific and are described in the chapter on wounding. The head is the most common target, but the legs and knees are also often struck. Blows on the back or side of the neck can be particularly lethal from vertebrobasilar artery damage (Chapter 5).
- Deaths from suffocation and drowning are not common, though non-fatal practices of this kind are well-known methods of abuse. Repeated dipping of the victim's head under water or even foul liquid such as sewage is called 'submarining', and may cause drowning, air-passage occlusion or a later pneumonia. Enveloping the head in an opaque plastic bag is more a means of disorientation than physical torture, but partial suffocation by similar means may eventually prove fatal.
- Electrical torture is common and well documented. Either mains voltage of 110 or 240 V is used – which carries the risk of fatal cardiac arrhythmia as well as local burning – or a magneto delivering high voltage, which is painful but not lethal. The latter will not leave any significant skin marks, as the amperage is so low.

  The later demonstration of electrical injury is difficult, as healed lesions have few characteristic features. The acute injuries which may cause burns and death are described in Chapter 12. Karlsmark and his co-authors have made a special study of the pathology of electrical torture. The current may be applied anywhere, but the genitals are sites favoured by torturers, especially the penis and scrotum. The female nipples are also targets.



FIGURE 10.6 *Extensive keloid scars following deliberate burning of a 16-year-old student in an East African concentration camp. An electric hot plate was pressed against his neck and kerosene-soaked rags were ignited on his arm.*

- Injuries to the ears can rarely be demonstrated at autopsy, but a favourite torture is the 'telefono', consisting of repeated slapping of the sides of the head by the open palms of the assailant. This may rupture the tympanic membranes and injure the inner ear.

- Suspension is a common torture, though again not often fatal in itself. If the victim is seen relatively soon after the ordeal then abrasions, bruises and chafing marks may be found at ligature sites, usually on legs, arms and sometimes genitals.
- Shooting is not a method of torture in the accepted sense, but is a common means of execution or of non-fatal punishment, such as the 'knee-capping' perpetrated in Northern Ireland, where opponents and suspected traitors are shot either through the knee joint or the lower thigh.
- Sexual abuse is also common and in women, rape – sometimes multiple – may leave physical signs as described in Chapter 18.

Medical examiners of alleged victims of torture must be careful not to misinterpret non-torture lesions as evidence of abuse, as such lapses will be seized upon by opponents wishing to discredit the medical opinion, either for political or immigration reasons. Forrest's guide (Forrest *et al.* 1995) lists most of these, which include innocent occupational, sporting or other accidents, tribal marks, skin infections, variations in pigmentation, traditional scarification, healing marks, stretch marks, etc.

EXTRAJUDICIAL EXECUTION

Many hundreds of thousands – indeed probably millions – of victims have been assassinated in recent years by governmental agencies acting quite outside the legal system. Because of ethnic origin, tribal feuds or political views, whole sections of populations have 'disappeared' on a scale sometimes amounting to genocide as in Rwanda, Cambodia, Bosnia and Kosovo. It is common knowledge that these disappearances are usually explained by murder, either on a mass scale or by continuous individual or group extermination by 'extermination squads'. Specific instances are not the concern of a textbook, but as recent years have shown, severe excesses have taken place in most continents leading to several forensic exercises directed towards identification of victims and proving methods of torture.

When vanished people have been presumed to have been killed by troops or security agencies, the evidence is usually very late in coming to light, so that forensically, much of the work consists of skeletal identification and investigations into causes of death. Where the bodies have decomposed or skeletalized, shooting or head injuries may be the only mode of death to leave any telltale evidence on exhumation. Autopsy examination may resemble mass-disaster procedures where there are large numbers of victims. The talents of odontologists and anthropologists, and the techniques of archaeology may be needed in such cases, as described by Clyde Snow in relation to the 'lost children' of Argentina or more recently in Bosnia and Herzegovina, Croatia and Kosovo. The vast numbers of skeletal remains in the Lowero triangle of Uganda have so far had no such attention.

DEATH IN CUSTODY

The occurrence of death while a person is either in the custody of the police, or the inmate of a prison, raises public interest and emotions that require careful handling and investigation. There is often an immediate complaint or rumour of ill-treatment by the relatives or the media. A meticulous autopsy is a necessary part of the investigation needed to dispel – or sometimes confirm – allegations that an act of commission or omission on the part of the custodians has led to, or contributed to, the death. This applies in all countries and has no relationship to the preceding section, when political issues may be suspected as a cause of the death. The two aspects are not always totally separate, however, as countries with excellent human rights records have sometimes been suspected of occasional lapses of standards where custodial deaths are concerned.

Most of the cases dealt with by a forensic pathologist will concern civil police forces and the regular prison service. Many countries, including Britain, have strict legislative rules that make all deaths in custody, whether police or prison, reportable for medico-legal investigation by the appropriate law officer (the coroner in England and Wales), in addition to a searching internal enquiry by officers from a different police force (e.g. in Finland the National Bureau of Investigation).

An autopsy will inevitably be held, regulations in UK making this a case for an accredited forensic pathologist. It is sometimes helpful if the pathologist visits the scene of the death, especially if it was caused by hanging or some form of mechanical trauma.

There are several situations in which death may occur in custody. The deceased may die during or soon after arrest by police officers, as there is often a struggle in which the offender is resisting arrest, sometimes violently. It may be a physical struggle, especially when police officers are attempting to control or overpower a resisting offender. In these situations, the use of so-called personal defence sprays has increased, as they have been shown to be very effective in incapacitating an aggressor. They cause acute ocular irritation, lachrymation, conjunctivitis, blepharospasm and extreme discomfort. Most of these sprays contain *o*-chlorobenzylidene malononitrile (CS), 2-chloroacetophenone (CN), oleoresin capsicum (OC), or a combination of these ingredients as the active agent. Capsacain (8-methyl-*N*-vanillyl-6-nonenamide) is a neurotoxin component of cayenne pepper. It stimulates excitatory afferent sensory neurones, causes hypothermia, neurogenic inflammation and pain, followed by subsequent desensitization. Although these sprays have been considered to be relatively safe, unexpected deaths have been reported after the exposure to oleoresin capsicum (OC) spray devices. Pepper spray has been suspected to induce bronchoconstriction. Chan and co-workers (2002) tested the effect of (OC) spray inhalation on respiratory function in 35 healthy subjects by itself and combined with restraint but could not find evidence of hypoxaemia or hypercapnia in either group. OC exposure did not result in abnormal spirometry, hypoxaemia, or hypoventilation when compared to placebo in either sitting or prone maximal restraint position. In another study on clinical toxicity of OC, in Kansas, Watson *et al.* (1996) reported on 81 emergency department patients who had been investigated after exposure to OC. Ocular burning and redness were the most common presenting symptoms. None of the patients required hospitalization due to OC toxicity. Corneal abrasions and respiratory symptoms occurred in seven and six patients, respectively. In case of death after OC exposure, a thorough autopsy, with ancillary investigations, including complete histology and toxicological analysis with assessment of the circumstances and symptomatology, is necessary to assess whether the exposure to OC spray has been causative, contributory, or unrelated to death.

On other occasions, the offender may threaten police officers with a knife, gun or blunt weapon, and the police have to subdue him either by sheer physical force – truncheons or riot sticks – or by the use of firearms. The most common event is the arrest of a drunken offender and this poses extra problems, discussed below. Other drugs, such as cocaine, cannabis, amphetamine and hallucinogens, rather than opiates such as morphine, heroin and barbiturates, may also be involved.

The physical overpowering of a suspected offender poses definite risks to health and life, and has been the subject of numerous controversial enquiries and litigation in many countries. The police usually outnumber the offender, sometimes by a considerable margin, but even a one-to-one struggle can be dangerous for either party. The following risks exist, though the list is by no means comprehensive.

- Traumatic asphyxia may occur where several policemen fall upon a resisting subject to overpower him. The author (BK) has dealt with several deaths where a number of large police officers piled on top of a prisoner fighting maniacally, to apply handcuffs. When they got up, the man was not breathing and died in hospital shortly afterwards. Death was caused by traumatic asphyxia, the weight of the men on top of him causing chest compression and prevention of respiratory movements. The appearances are described in Chapter 14.
- Arm-locks or neck-holds applied by police officers to resisting persons are other causes of deaths during arrest. These have been particularly notorious in the USA, where police officers have been trained to apply neck-holds as a form of restraint, but similar deaths have been seen elsewhere. The arm-lock is applied either from behind or with the head of the offender tucked under the police officer's arm against his waist. The dangers are compression of the front or sides of the neck, and death can occur either from reflex cardiac arrest or cerebral ischaemia during carotid compression, or asphyxia from airway obstruction, though the latter is unlikely as the sole mechanism. According to American writers such as Reay and Eisele (1982, 1986), there are two types of neck-hold – the 'bar arm control' and the 'carotid sleeper'. The former is alleged to be more dangerous; the officer's forearm is pulled across the front of the larynx to occlude the airway. The carotid sleeper uses the two sides of the 'V' formed by the flexed upper and lower arm to compress the carotids and produce transient cerebral ischaemia. Both varieties are dangerous, however, as there is the ever-present hazard of reflex cardiac arrest from vagal stimulation from the carotid sinus and sheath, as well as the potential danger of neck traction and hyperextension causing subarachnoid haemorrhage from vertebrobasilar artery damage.
- Postural (positional) asphyxia has been reported to have caused sudden deaths in persons after the use of the 'hogtie', 'hobble' or prone maximal restraint and even in situations where a person has been placed in a prone position in the rear compartment of a police car. In an experiment with healthy subjects, the restraint position resulted in a restrictive pulmonary function pattern but did not cause clinically relevant changes in oxygenation or ventilation. It has been postulated that the hogtie restraint position by itself does not cause respiratory compromise to the point of asphyxiation but other factors, e.g. acute intoxication by alcohol or drugs, are responsible for the sudden deaths of individuals placed in this position.
- Blunt injury may occur from the use of fist, arm or leg – or the use of a weapon such as a truncheon, riot stick or pistol butt. During a struggle, usually with one or more police officers who are attempting to subdue a fighting offender, injuries may be received by either side. All types of blunt injury may be sustained, some potentially fatal and these are discussed in Chapter 4. Head injuries may occur during a scuffle from falls either against the ground, or against a wall or other

obstruction. A heavy punch in the face may cause nasopharyngeal bleeding that can block the air passages, especially in a person affected by alcohol. A blow on the side of the neck can cause reflex cardiac arrest or a subarachnoid haemorrhage from vertebrobasilar vascular damage.

A backward blow from the point of an elbow can be damaging, if it strikes the face, neck or abdomen. Kicking and stamping are unusual, but not unknown, in custodial deaths. A blow in the abdomen can also be serious if delivered with sufficient force. Though in an adult a fist blow is not very likely to cause serious harm, it can in a slighter young person. The use of the elbow, knee or a head butt can deliver extreme force, especially from a fit, muscular police officer, as well as from an offender.

The author (BK) has seen fatal intraperitoneal bleeding amounting to three litres in a drunken man arrested after a scuffle with two police officers, in which there were allegations that one struck or fell on the man with his knee. Several hours later the prisoner collapsed and at autopsy there were several large tears in the mesentery.

Alcohol is a frequent cause of death in custody. Not only is it the major factor in provoking aggression and violent resistance, with the consequences mentioned above, but it can have other effects which lead to death while in the care of the police. Acute alcoholic poisoning, described more fully in Chapter 28, may lead to death while the victim is thought to be 'sleeping it off' in a police cell. When blood alcohol levels rise to above 350 mg/100 ml there is an increasing risk of coma and central respiratory depression. Although most responsible police forces have standing orders about placing drunken prisoners in the semiprone position and observing them at frequent intervals, a quiet drunk may still slip into irreversible coma and respiratory arrest.

At lower blood alcohol levels there is still the risk of aspiration of vomit and choking on gastric contents. Though drunken prisoners are placed in the safest posture for drainage, they can still vomit and choke when unobserved, between visits by the often busy police station officers. At autopsy, caution must be observed before ascribing death to aspiration of vomit, as this is a common agonal phenomenon in deaths from other causes. Where an otherwise healthy person dies with a high blood alcohol concentration in these circumstances, however, gross blocking of the trachea and bronchi with vomit forms one of the most convincing arguments for acceptance of aspiration as the cause of death if no other factors can be identified.

Alcohol also contributes to accidents during custody, especially head injuries, which come about because of falls to the ground, falls down steps and stairs, and being run over by traffic, as a result of the ataxia and incoordination of the drunken state. Falls onto a hard surface are often on the occiput and the frequent finding of frontal and temporal contrecoup brain damage at autopsy is good evidence of a deceleration injury rather than an assault with a weapon.

Some falls may occur during custody or in transit from the site of arrest to the police station – others have happened before arrest, but the ill-effects and death may become manifest during the stay in the police cell, when the police are often blamed either for allowing or causing the injury – or for not summoning or providing urgent medical attention. Drugs, especially those causing excitement, such as amphetamine, cocaine or hallucinogens, may also lead to physical damage, but alcohol remains by far the most common.

Drugs are commonly available within prisons and overdose or hypersensitivity deaths are occasionally seen amongst prisoners, as they are in the outside world.



FIGURE 10.7 *Suicidal hanging in a prison cell. This is an infrequent but regular tragedy, which, in spite of strenuous efforts by prison officers and designers of cells, occurs because of the determination of the prisoner to defeat the safeguards. The belt used as ligature has been removed and lies on the bed.*

- Suicide in custody is not uncommon, and often leads to accusations and recriminations from the relatives over lack of supervision. There has recently been a spate of such deaths in Britain, especially amongst young offenders on remand awaiting trial. It is such a well-recognized hazard of custody that most police forces deprive the prisoner of any objects, such as belts, braces (suspenders), cord or even bootlaces, that could be used to hang himself in his cell. In addition, the police cell may be specifically designed to avoid any convenient suspension points, such as hooks, bars or even internal door handles. In spite of these precautions, prisoners regularly manage to find some means of killing themselves. Strips of bedding material, sleeves of clothing and handkerchiefs have all been used for self-suspension. As described in Chapter 14, hanging can be successfully accomplished by traction on the neck at low levels and need not occur from high suspension points, so prisoners have killed themselves by attaching ligatures to bed-heads, chairs and other unlikely objects in the cell.

  Accusations that apparent suicidal hangings were in reality homicides by the custodians can usually be resolved by the autopsy showing no signs of bruising, abrasions or a struggle. It would seem impossible to hang a conscious person against his will without leaving some signs of restraint. The proposition that the hanging was a ligature strangulation is usually disproved by the rising angle of the ligature mark, which most commonly sets under the angles of the jaw and has a defect in the skin mark where the suspension point pulls the ligature away from the surface. A homicidal strangulation usually encircles the neck and a cross-over point is often seen. The level is lower, nearer the horizontal (Chapter 14).

  Where a true hanging mark is caused by a ligature with a slip-knot, there may also be a full circle of skin abrasion and compression. If the suspension point is low, as might happen in a cell using a doorknob or a bed-frame, then the direction of pull can be oblique. If the body also leans over against the direction of pull, the resultant mark can be virtually horizontal and, unless the situation is fully assessed – preferably by a visit to the scene with the body *in situ* – confusion can occur, as with the controversy over the death of Rudolph Hess in 1988, whilst an inmate in Berlin's Spandau prison.
- Death may be from purely natural causes, usually cardiovascular in origin, which happened to have occurred during detention. It must be admitted, though it is almost impossible to provide objective proof, that the emotional and sometimes physical upset of being arrested and confined may have affected the blood pressure and heart rate sufficiently, by an adrenaline response, to have precipitated an acute cardiac crisis in the presence of severe pre-existing disease.

  The presence of diabetes, epilepsy, asthma or other diseases that can potentially cause sudden or unexpected death should be sought by medical history and autopsy appearances (Chapter 25).

REFERENCES AND FURTHER READING

Amnesty International. 2001. *Amnesty international report 2001*. Amnesty International, London.

Billmire DF, Vinocur C, Ginda M, *et al.* 1996. Pepper-spray-induced respiratory failure treated with extracorporeal membrane oxygenation. *Pediatrics* **98**:961–3.

Blaauw E, Vermunt R, Kerkhof A. 1997. Deaths and medical attention in police custody. *Med Law* **16**:593–606.

Bloom AI, Zamir G, Muggia M, *et al.* 1995. Torture rhabdomyorhexis – a pseudo-crush syndrome. *J Trauma* **38**:252–4.

Bork K, Nagel C. 1997. Long-standing pigmented keloid of the ears induced by electrical torture. *J Am Acad Dermatol* **36**:490–1.

Brkic H, Strinovic D, Kubat M, *et al.* 2000. Odontological identification of human remains from mass graves in croatia. *Int J Legal Med* **114**:19–22.

Bro Rasmussen F, Henriksen OB, Rasmussen OV, *et al.* 1982. [Aseptic necrosis of bone following phalanga torture.] *Ugeskr Laeger* **144**:1165–6.

Brown L, Takeuchi D, Challoner K. 2000. Corneal abrasions associated with pepper spray exposure. *Am J Emerg Med* **18**:271–2.

Busker RW, van Helden HP. 1998. Toxicologic evaluation of pepper spray as a possible weapon for the Dutch police force: risk assessment and efficacy. *Am J Forensic Med Pathol* **19**:309–16.

Chan TC, Vilke GM, Neuman T. 1998. Reexamination of custody restraint position and positional asphyxia. *Am J Forensic Med Pathol* **19**:201–5.

Chan TC, Vilke GM, Clausen J, *et al.* 2002. The effect of oleoresin capsicum 'pepper' spray inhalation on respiratory function. *J Forensic Sci* **47**:299–304.

Copeland AR. 1984. Deaths in custody revisited. *Am J Forensic Med Pathol* **5**:121–4.

Corovic N, Durakovic Z, Zavalic M, *et al.* 2000. Electrocardiographic changes in ex-prisoners of war released from detention camps. *Int J Legal Med* **113**:197–200.

Dalton V. 1999. Death and dying in prison in Australia: national overview, 1980–1998. *J Law Med Ethics* **27**:210, 269–74.

Epstein RJ, Majmudar PA. 2001. Pepper spray in the eye. *Ophthalmology* **108**:1712–13.

Fernandez M, Pissiota A, Frans O, *et al.* 2001. Brain function in a patient with torture related post-traumatic stress disorder before and after fluoxetine treatment: a positron emission tomography provocation study. *Neurosci Lett* **297**:101–4.

Fitzpatrick JJ. 1984. Role of radiology in human rights abuse. *Am J Forensic Med Pathol* **5**:321–5.

Forrest D. 1995. The physical after-effects of torture. *Forensic Sci Int* **76**:77–84.

Forrest D, Knight B, Hinshelwood G, *et al.* 1995. A guide to writing medical reports on survivors of torture. *Forensic Sci Int* **76**:69–75.

Frost R, Hanzlick R. 1988. Deaths in custody. Atlanta city jail and Fulton county jail, 1974–1985. *Am J Forensic Med Pathol* **9**:207–11.

Fruehwald S, Frottier P, Eher R, *et al.* 2000. Prison suicides in Austria, 1975–1997. *Suicide Life Threat Behav* **30**:360–9.

Giles HG, Sandrin S. 1992. Alcohol and deaths in police custody. *Alcohol Clin Exp Res* **16**:670–2.

Gniadecka M, Danielsen L. 1995. High-frequency ultrasound for torture-inflicted skin lesions. *Acta Derm Venereol* **75**:375–6.

Goldfeld AE, Mollica RF, Pesavento BH, *et al.* 1988. The physical and psychological sequelae of torture. Symptomatology and diagnosis [published erratum appears in *JAMA* 1988 Jul 22–29;**260**(4):478]. *JAMA* **259**:2725–9.

Goldney RD. 1993. Deaths in custody. *Med J Aust* **159**:572–3.

Gordon E, Knight B. 1985. *Uganda: evidence of torture*. Amnesty International, London.

Granzow B, Puschel K. 1998. [Fatalities during imprisonment in Hamburg 1962–1995.] *Arch Kriminol* **201**:1–10.

Hiss J, Kahana T. 1996. Medicolegal investigation of death in custody: a postmortem procedure for detection of blunt force injuries. *Am J Forensic Med Pathol* **17**:312–14.

Hougen HP. 1988. Physical and psychological sequelae to torture. A controlled clinical study of exiled asylum applicants. *Forensic Sci Int* **39**:5–11.

Jandoo R. 1987. Human rights abuses and the medical profession. *Forensic Sci Int* **35**:237–47.

Johnson HR. 1982. Deaths in police custody in England and Wales. *Forensic Sci Int* **19**:231–6.

Karch SB, Stephens BG. 1999. Drug abusers who die during arrest or in custody. *J R Soc Med* **92**:110–13.

Karlsmark T, Thomsen HK, Danielsen L, *et al.* 1984. Tracing the use of electrical torture. *Am J Forensic Med Pathol* **5**:333–7.

Kirschner RH. 1984. The use of drugs in torture and human rights abuses. *Am J Forensic Med Pathol* **5**:313–15.

Lacroix JS, Buvelot JM, Polla BS, *et al.* 1991. Improvement of symptoms of non-allergic chronic rhinitis by local treatment with capsaicin. *Clin Exp Allergy* **21**:595–600.

Lanphear BP. 1987. Deaths in custody in Shelby county, Tennessee, January 1970–July 1985. *Am J Forensic Med Pathol* **8**:299–301.

Lee RJ, Yolton RL, Yolton DP, *et al.* 1996. Personal defense sprays: effects and management of exposure. *J Am Optom Assoc* **67**:548–60.

Levine LJ. 1984. The role of the forensic odontologist in human rights investigations. *Am J Forensic Med Pathol* **5**:317–20.

Levine M. 1998. Deaths in police custody. *Med Leg J* **66**:97–108.

Lifschultz BD, Donoghue ER. 1991. Deaths in custody. *Leg Med* 45–71.

Lok V, Tunca M, Kumanlioglu K, *et al.* 1991. Bone scintigraphy as clue to previous torture [letter] [see comments]. *Lancet* **337**:846–7.

Luke JL, Reay DT. 1992. The perils of investigating and certifying deaths in police custody. *Am J Forensic Med Pathol* **13**:98–100.

Macdonald HA. 1998. Possible idiosyncratic reaction to OC spray. *N Z Med J* **111**:327.

Mercy JA, Heath CW, Jr., Rosenberg ML. 1990. Mortality associated with the use of upper-body control holds by police. *Violence Vict* **5**:215–22.

Mirzaei S, Knoll P, Lipp RW, *et al.* 1998. Bone scintigraphy in screening of torture survivors. *Lancet* **352**:949–51.

Mirzaei S, Knoll P, Keck A, *et al.* 2001. Regional cerebral blood flow in patients suffering from post-traumatic stress disorder. *Neuropsychobiology* **43**:260–4.

Missliwetz J, Denk W. 1991. [Maltreatment by police officers?] *Arch Kriminol* **187**:1–12.

Morrison S. 1996. Custodial suicide in Australia: a comparative study of different populations. *Med Sci Law* **36**:167–77.

Norfolk G, Cartwright J. 1996. Deaths in police custody are being analysed retrospectively. *Br Med J* **312**:911.

Patel F. 2000. Custody restraint asphyxia. *Am J Forensic Med Pathol* **21**:196–7.

Patel V. 1996. Deaths in police custody. *Br Med J* **312**:56.

Petersen HD, Rasmussen OV. 1992. Medical appraisal of allegations of torture and the involvement of doctors in torture. *Forensic Sci Int* **53**:97–116.

Pollanen MS, Chiasson DA, Cairns JT, *et al.* 1998. Unexpected death related to restraint for excited delirium: a retrospective study of deaths in police custody and in the community. *Can Med Assoc J* **158**:1603–7.

Primorac D, Andelinovic S, Definis-Gojanovic M, *et al.* 1996. Identification of war victims from mass graves in croatia, bosnia, and herzegovina by use of standard forensic methods and DNA typing. *J Forensic Sci* **41**:891–4.

Rainio J, Hedman M, Karkola K, *et al.* 2001. Forensic osteological investigations in Kosovo. *Forensic Sci Int* **121**:166–73.

Rainio J, Lalu K, Penttila A. 2001. Independent forensic autopsies in an armed conflict: investigation of the victims from Racak, Kosovo. *Forensic Sci Int* **116**:171–85.

Rasmussen OV. 1990. Medical aspects of torture. *Dan Med Bull* **37**(Suppl 1):1–88.

Rasmussen OV, Lunde I. 1980. Evaluation of investigation of 200 torture victims. *Dan Med Bull* **27**:241–3.

Rasmussen OV, Skylv G. 1992. Signs of falanga torture [letter]. *Lancet* **340**:725.

Reay DT. 1998. Death in custody. *Clin Lab Med* **18**:1–22.

Reay DT, Eisele JE. 1982. Death from law enforcement neck holds. *Am J Forensic Med Pathol* **3**:253–8.

Reay DT, Eisele JE. 1986. Law enforcement neck holds. *Am J Forensic Med Pathol* **7**:177–87.

Reay DT, Hazelwood RR. 1970. Death in military police custody and confinement. *Milit Med* **135**:765–71.

Reilly CA, Crouc DJ, Yost GS, *et al.* 2001. Determination of capsaicin, dihydrocapsaicin, and nonivamide in self-defense weapons by liquid chromatography-mass spectrometry and liquid chromatography-tandem mass spectrometry. *J Chromatogr A* **912**:259–67.

Reilly CA, Crouch DJ, Yost GS. 2001. Quantitative analysis of capsaicinoids in fresh peppers, oleoresin capsicum and pepper spray products. *J Forensic Sci* **46**:502–9.

Richmond PW, Fligelstone LJ, Lewis E. 1988. Injuries caused by handcuffs [see comments]. *Br Med J* **297**:111–12.

Ross DL. 1998. Factors associated with excited delirium deaths in police custody. *Mod Pathol* **11**:1127–37.

Ruttenber AJ, Lawler-Heavner J, Yin M, *et al.* 1997. Fatal excited delirium following cocaine use: epidemiologic findings provide new evidence for mechanisms of cocaine toxicity. *J Forensic Sci* **42**:25–31.

Savnik A, Amris K, Rogind H, *et al.* 2000. MRI of the plantar structures of the foot after falanga torture. *Eur Radiol* **10**:1655–9.

Skinner M. 1987. Planning the archaeological recovery of evidence from recent mass graves. *Forensic Sci Int* **34**:267–87.

Skylv G. 1992. The physical sequelae of torture. In: Basoglu M (ed.), *Torture and its consequences: current treatment approaches.* Cambridge University Press, Cambridge.

Smith CG, Stopford W. 1999. Health hazards of pepper spray. *N C Med J* **60**:268–74.

Snow CC, Levine L, Lukash L, *et al.* 1984. The investigation of the human remains of the 'disappeared' in Argentina. *Am J Forensic Med Pathol* **5**:297–9.

Steffee CH, Lantz PE, Flannagan LM, *et al.* 1995. Oleoresin capsicum (pepper) spray and 'in-custody deaths'. *Am J Forensic Med Pathol* **16**:185–92.

Stover E, Nightingale EO. 1985. The medical profession and the prevention of torture. *N Engl J Med* **313**:1102–4.

Tedeschi LG. 1984. Human rights and the forensic scientist. *Am J Forensic Med Pathol* **5**:295–6.

Tedeschi LG. 1984. Methodology in the forensic sciences. Documentation of human rights abuses. *Am J Forensic Med Pathol* **5**:301–3.

Thomsen AB, Eriksen J, Smidt-Nielsen K. 1997. [Neurogenic pain following Palestinian hanging.] *Ugeskr Laeger* **159**:4129–30.

Thomsen AB, Eriksen J, Smidt-Nielsen K. 2000. Chronic pain in torture survivors. *Forensic Sci Int* **108**:155–63.

Thomsen JL. 2000. The role of the pathologist in human rights abuses. *J Clin Pathol* **53**:569–72.

Thomsen JL, Helweg Larsen K, Rasmussen OV. 1984. Amnesty International and the forensic sciences. *Am J Forensic Med Pathol* **5**:305–11.

Tunca M, Lok V. 1998. Bone scintigraphy in screening of torture survivors. *Lancet* **352**:1859.

Vesaluoma M, Muller L, Gallar J, *et al.* 2000. Effects of oleoresin capsicum pepper spray on human corneal morphology and sensitivity. *Invest Ophthalmol Vis Sci* **41**:2138–47.

Watson WA, Stremel KR, Westdorp EJ. 1996. Oleoresin capsicum (cap-stun) toxicity from aerosol exposure. *Ann Pharmacother* **30**:733–5.

Zollman TM, Bragg RM, Harrison DA. 2000. Clinical effects of oleoresin capsicum (pepper spray) on the human cornea and conjunctiva. *Ophthalmology* **107**:2186–9.

CHAPTER 11

Burns and scalds

- Heat injury 312
- Classification of the severity of burns 312
- Moist thermal damage – scalds 313
- Burns from dry heat 314
- Gross appearances at autopsy 315
- Spurious 'wounds' in burns 316
- Ante-mortem versus post-mortem burns 317
- Fumes and fires 319
- Inhalation of soot 322
- Atypical localized burning and 'spontaneous combustion' 323
- References and further reading 324

Damage to the tissues arising from the application of heat is commonly encountered in forensic pathology and sometimes provides a challenging problem in the distinction between ante-mortem and post-mortem burning, which may have serious criminal aspects.

HEAT INJURY

This may arise following a defect in body temperature control or, more commonly, from the external application of heat. Mammalian tissues can survive only within a relatively narrow range of temperatures, approximately 20–44°C.

When external heat is applied, the extent of damage depends upon:

- the applied temperature
- the ability of the body surface to conduct away the excess heat
- the time for which the heat is applied.

The temperature/time relationship is important, for it is sometimes forgotten that relatively low temperatures, even as little as 44°C, can cause damage if sustained long enough. This is attested by many negligence lawsuits concerning unconscious patients burned by forgotten hot-water bottles.

The degrees of thermal damage were investigated by Moritz and Henriques (1947), who found that the lowest temperature that would cause damage was 44°C, though it required no fewer than 5 hours before a burn appeared. Only 3 seconds was needed, however, if the object was at 60°C.

Radiant heat can also cause severe damage, as is obvious from overexposure to sunlight or artificial sunlamps. The long-term effects also include malignant changes, now more important because pollution-induced changes in the stratosphere are allowing more ultraviolet radiation to reach the earth's surface. In forensic practice it is more often seen when an old or disabled person falls unconscious within close range of a gas, electric or coal fire, those areas of skin unprotected by clothing becoming burned, often to a blistered state. It can be difficult or impossible to tell how much of such a condition is ante-mortem or post-mortem, as the presence of reddening and blistering cannot always be depended on as criteria of vital infliction. Mottled pigmentation and reddening of the fronts of the legs (erythema ab igne) is a familiar sign in those addicted to sitting before an open fire.

CLASSIFICATION OF THE SEVERITY OF BURNS

An arbitrary, but useful, classification is used (mainly for surgical purposes) to denote the severity of both burns and scalds. The older six-stage classification of Dupuytren has given way to Wilson's three-stage nomenclature:

- **First degree:** erythema and blistering without loss of dermis. There is capillary dilatation and transudation of fluid into the tissues, causing swelling. A split may occur in the epidermis to form a blister with an upper cap of pale skin enclosing fluid, surrounded by a zone of hyperaemia. If small (<1 cm) this blister may resorb, otherwise it will burst, leaving a reddened base. A first-degree burn will heal without scarring.

- **Second degree:** destruction of the full thickness of skin. The epidermis is coagulated or charred, and a central zone of necrotic tissue is surrounded by first-degree burns or a zone of hyperaemia, or both. The central necrosis sloughs in due course and the epidermis grows in from the margins. The injury cannot heal without scarring, which usually contracts during the healing process, causing puckering and distortion of the surface.
- **Third degree:** destruction of deeper tissues below the skin. This can be of any severity, from damage to subcutaneous fat to loss of muscle, bone and even a whole limb.



FIGURE 11.1 *The 'Rule of Nines' for calculating the area burned. It does not apply to infants whose body proportions are different from adults. About 60 per cent surface burns can be survived by children and young people up to 20 years of age but this rapidly decreases with advancing age.*

The area involved is traditionally estimated by the surgical 'Rule of Nines', which is sufficient for prognostic purposes, though for the pathologist a more precise anatomical description of the areas burned is essential for his autopsy report.

If the burns are widespread, then large areas of skin may be damaged and functionless. A large area involved may be more dangerous to life than a deeper, more localized burn. It is generally considered that 30–50 per cent involvement of the total body surface is incompatible with survival. Old people can die at considerably lower percentages than this, while children appear more resistant.

MOIST THERMAL DAMAGE – SCALDS

A 'scald' refers to tissue damage from hot liquids, usually water. Other hot fluids include oils, molten rubber, other liquid chemicals and steam. Molten metals are usually at such a high temperature that the results are similar to dry burns. The water scald is a common domestic accident, especially to children and old people, that group at the extremes of life who are vulnerable to so many types of accident.

A scald, unless from some superheated oil, does not cause charring, carbonization or singeing of surface hairs, as does dry heat. It resembles a first-degree dry burn (see later) in



FIGURE 11.2 *First- and second-degree burns on the right thigh and scrotum of a 5-year-old diabetic child, who had been treated by a quack, who had promised the parents to cure the child by hot baths. Death was caused by the untreated diabetes.*

that there is reddening, desquamation and blistering, but the shape of the scald tends to be different. There is usually a sharply demarcated edge, corresponding to the limits of contact of the fluid. If due to immersion in hot water, such as a bath, there will be a horizontal fluid level, though this may be made irregular by splashing. When tipped or splashed, the hot liquid runs under gravity so that trickle patterns may be seen, which may enable the medical examiner to determine the posture of the victim when scalded.

The intensely red base of a severe scald may at first be covered by wrinkled, macerated epidermis. The scalded skin may swell and exude serum. Infection may supervene but where the burns are extensive, death usually results from the systemic effects of shock, fluid and electrolyte disturbance, and secondary chest infections. The severity of a scald depends on the duration of contact with the skin, as well as the temperature. When hot water is splashed, tipped or thrown, it has only a momentary contact, falling away under gravity. The large surface area allows rapid cooling, so damage must occur in a short time, which necessitates the temperature being high if severe damage is to be caused. Often the water is boiling, especially in the kitchen accidents that, sadly, occur to children with such regularity. The interposition of clothing may have two opposite effects; it may protect the underlying skin from the hot liquid, especially if poorly permeable, but it may also hold the hot liquid in contact with the skin for a longer time, especially if the fabric is absorbent.



FIGURE 11.3 *Scalds or wet burns in a child accidentally left in a hot bath while her mother went to answer the telephone. This illustrates that time, as well as temperature, is a factor in causing heat damage to skin. The child died some days later from an intercurrent chest infection.*

The appearance of scalds may resemble dry burns except for the distribution and the fact that, if due to immersion, the severity of the skin damage is usually uniform over the whole of the burnt area up to the sharply demarcated margin. When hot or boiling water has been poured or splashed onto the body, the worst scalds will be at the area of initial contact where the fluid was hottest, but decrease in severity as the cooling liquid runs away. In children who pull containers of hot liquid down on themselves, the scalds tend to be on the face, neck, chest and arms, with ‘shadow areas’ of undamaged skin in the axillae and on the back.

BURNS FROM DRY HEAT

More common than scalds, burns due to dry heat may be caused by high temperature applied to the body surface by conduction or radiation. Convection is merely a variant of conduction in this respect; as hot gas impinges on the surface, the molecules transfer their high energy in a similar fashion to the direct contact of a hot solid.

Radiation causes damage through the conversion of infrared frequencies into thermal heat on absorption at the



FIGURE 11.4 *A burn on the inner sides of each upper thigh in a young woman. These are suggestive of the application of a hot-water bottle in an attempt at resuscitation after a criminal abortion. The victim died of air embolism following the use of a Higginson syringe.*

skin interface. As with scalds, the tissue damage is a function of temperature and time. A warm water-pipe will cause a burn if left long enough in contact with the same area of skin, but the vast majority of dry burns are due to high temperatures acting for a shorter time.

Where the time is extended beyond that needed for initial burning, the tissues may be charred, carbonized or completely destroyed, as in cremation.

The severity of dry burns

The Wilson classification of severity of burns is given above, with three degrees according to the depth of tissue damage:

- Erythema leads to redness and swelling of the skin. Blisters may form either within the thickness of the epidermis or at the epidermal–dermal junction.
- Destruction of the full thickness of the skin, which may be total or incomplete. If epidermal structures survive, such as the deeper parts of hair follicles, then epithelialization may occur from islands within the burned area. If not, slow coverage with more probability of extensive scarring will occur from invasion of epidermis at the periphery.
- Destruction of subcutaneous tissues, such as fat, muscle and even bone, is the most serious grade of burning, though, as mentioned elsewhere, it may be less dangerous to life than larger areas of more superficial burns.



FIGURE 11.5 *Keloid tissue (dense collagenous overgrowth) more often follows burns than other injuries. It is especially prevalent and profuse in negroid persons. This East African youth was tortured in a political camp with hot metal and burning kerosene, resulting months later in exuberant keloid.*

GROSS APPEARANCES AT AUTOPSY

The body may present a wide range of damage from mere reddening over wide areas to almost total cremation, in which a search may have to be made at the scene of the fire to collect or even discover the remnants.

Usually, where leathery coagulation or charring has not occurred, ante-mortem burns will be reddened and often blistered. The latter have a marginal red zone of variable width, usually 5–20 mm across. Blisters may be present either in the main burn or as islands beyond the periphery. Most ante-mortem blisters will have a bright red base when burst and an erythematous areola. The whole of the burned area may form one large blister or be a coalescence of blisters. These are usually collapsed at autopsy, so that sheets and shreds of white epidermis lie across an angry red base.

Where the burns are more severe, the skin may be stiffened, yellow–brown and leathery, a half-way stage to actual carbonization. Drying after death of areas that were weeping serum leads to a stiff, parchment-like surface. Post-mortem heating and deposition of smoke may mimic or overlie the ante-mortem appearances, the surface often being blackened by soot deposition.

Hair is singed or completely burnt away in severe burns. In lesser degrees it may survive and the ends of the hairs may be ‘clubbed’. Here the keratin melts at the distal end nearest the heat, then resolidifies on cooling, forming a terminal blob on the shaft like an unlit match. Eyelashes, eyebrows, pubic, axillary and general body hair may all suffer this scorching. Where skin has actually ignited, the subcutaneous fat acting as a fuel, black brittle masses will occupy the tissues merging into cooked, dry muscle beneath, which in turn grades into more moist and normal-looking soft tissue at greater depths. Beneath burns of any degree, the deeper tissues may be affected, especially muscle, which becomes pale, brownish and obviously ‘part-cooked’. This is often a post-mortem phenomenon caused by the dead body remaining in a heated environment and such cooked muscle may



FIGURE 11.6 *Second and third degree burns and singeing of hair on a suicide who doused himself with petrol and set himself to fire.*

extensively underlie normal skin, which shows no evidence of ante-mortem burning, especially if protected by clothing. It is the general high temperature of the environment over a relatively long period which produces this 'parboiled' appearance, similar to the cooking effect of a slow oven.

Where heat has been intense and continuous, all soft tissue down to bone may be consumed and the bone itself may be blackened. The most extreme stage is conversion of the bone to brittle greyish-white splinters, sometimes with loss of skeletal structures, leading to absent feet, hands or limbs. It is rare for the whole body to be completely consumed, even in deliberate cremations, but only a fraction of the original body mass may remain, often almost inseparable from the burned surroundings. Where much smoke has been generated, as in most house fires, the skin will be discoloured where exposed. Sharply demarcated areas of soot deposition may coincide with burning from hot gas. Even the thinnest layer of clothing may protect completely from both these effects.

Muscle contractures are common where substantial heat has reached the body. This is almost always a post-mortem occurrence, as deep-heating effects sufficient to cook muscle are incompatible with life. The muscle becomes shortened by dehydration and protein denaturation. The flexors, being bulkier than the extensors, contract more and force the limbs into a position of general flexion, the so-called 'boxer's' or 'pugilistic' attitude. Contraction of the paraspinal musculature often causes a marked opisthotonos. Froth, often pink-stained, may appear at the mouth and nostrils as a result of pulmonary oedema caused by heat irritation of the air passages and lungs. The tongue frequently protrudes and may be scorched.



FIGURE 11.7 *Dead bodies in fires pose a problem for pathologists and investigators. Death was shown to have occurred after the fire began from soot in the lungs and carboxyhaemoglobin in the blood. There were no ante-mortem burns and there was a high blood-alcohol concentration.*

SPURIOUS 'WOUNDS' IN BURNS

Heated skin contracts markedly and splits often appear. This may lead inexperienced observers (such as police) to suspect that ante-mortem wounds have been inflicted, the fire being used to cover up a criminal offence. These splits may be anywhere, but are especially seen over extensor surfaces and joints, as well on the head. Some, especially those at elbows and knees when the limbs are flexed across brittle skin, are caused by firemen handling the body during recovery.

The possibility of true wounds being present must always be kept in mind, as many homicides have been concealed in fires. The false split will show no bleeding in the deeper tissues and its position is usually suggestive. The differentiation may be difficult or even impossible, however, especially when severe heat damage in the area makes examination of the underlying tissue impracticable.



FIGURE 11.8 *Heat flexures of the limbs, part way towards the 'pugilistic attitude' formed when the arms are raised higher. The elbows, knees and wrists are strongly flexed because muscle contraction is stronger in the flexor groups. The victim was the captain of a Russian ship who set fire to his cabin during a bout of heavy drinking.*

The other major false lesion is the 'heat haematoma' in the extradural space. When severe heat is applied to the cranium, a mass of blood resembling a true extradural haematoma may form between the skull and the dura. This may arise either from venous sinuses or be virtually 'boiled' out of the diploic space in the skull through emissary venous channels. The blood is spongy from gas bubbles and tawny or chocolate brown. The exterior of the skull overlying the haematoma is usually charred and the scalp burnt away. If it is a purely post-mortem phenomenon, the heat haematoma will have a similar level of carboxyhaemoglobin to the blood, whereas if it was an ante-mortem lesion sustained before the fire began, it will be free from monoxide, as discussed in more detail below. Where the heat is intense the spurious haematoma may be outside a grossly shrunken dura, which compresses the brain into a cooked mass. The dura may split under the tension and allow brain tissue to ooze out into the large space within the cranium, where it may form a mass of frothy paste (Kondo and Ohshima 1994). These changes may be present without a haematoma, but the latter is often present. In the absence of a skull fracture, other than one due to heat, this haematoma should not be ascribed to trauma.

ANTE-MORTEM VERSUS POST-MORTEM BURNS

In severe conflagrations, either in buildings or vehicles, the terminal state of the body often does not reflect the condition at the time of death. Indeed, many deaths will have occurred before any heat reaches the body, death being caused by the inhalation of smoke. It may be difficult or impossible for the pathologist to determine the extent of ante-mortem damage if the ensuing fire later reaches the body and causes post-mortem burning. The exposed skin surface may be reddened in both ante-mortem and post-mortem burns, the classical distinction of a 'red flare' or 'vital reaction' being unsafe as an index of infliction before death. The author (BK) has seen several cases of undoubted post-mortem burns, one at least 30 minutes after fatal strangulation, where an extensive 'red flare' was caused during attempts at disposal of the body by fire.

Blisters can form post-mortem, but are pale yellow unless on scorched skin. There is rarely a red base or erythematous areola, though this sign cannot be depended upon absolutely. The contained fluid is thin and clear. Traditionally most authors claim that differentiation can be made between an ante-mortem and a post-mortem blister by an analysis for protein and chloride in the fluid. The blister formed in life is said to contain more protein and chlorides, but no absolute figures are offered and the authors have yet to meet a pathologist who does this as a routine. One suspects that the test is another of the apocryphal procedures that have been handed down from textbook to textbook without verification.

Most useful of all in fatalities is the presence of carbon monoxide in the circulating blood and carbon particles in the air passages and lungs, and this is dealt with in the section on inhalation of fumes. They do not necessarily prove that any burns were ante-mortem, but that the victim was still alive when the fire was in progress, which is not the same conclusion. The extradural heat haematoma may be investigated in a different way to determine its time of origin. If it is a true traumatic lesion produced before the fire began, it should contain no carboxyhaemoglobin. A spurious heat haematoma is formed from blood that will contain carboxyhaemoglobin if the victim has absorbed this gas during the fire. It must be appreciated, however, as



FIGURE 11.9 *Substantial destruction of the body by fire. The upper half of the victim has virtually vanished, including skeletal structures, leaving the lower part intact. The gas stove was ignited with a match after a delay while gas was escaping, causing a near-explosion that consumed the upper part of the body, the fat burning with clothing acting as a 'wick'. Such events have given rise to the myth of 'spontaneous combustion'.*



FIGURE 11.10 *Post-mortem injuries caused by heat simulating head injuries. The fire service were concerned about an apparent preconflagration assault, but such skin splits are commonly seen as a result of heat contracture of the tissues. The scalp on the top of the head has been burned through and the skull is charred. Beneath this is a spurious 'heat haematoma', sometimes confused with a traumatic extradural haemorrhage.*



FIGURE 11.11 *Post-mortem burns in a victim recovered from a house fire. Note the raised arms caused by heat contractures and the complete protection against burning afforded by clothing on the legs. There is extensive skin splitting on the chest.*

discussed below, that not all persons alive during a fire accumulate carboxyhaemoglobin in their blood.

If there is carboxyhaemoglobin absorption, then the heat haematoma will also yield it on analysis. The use of this test, again related in most classical texts, is, however, extremely limited.

FUMES AND FIRES

The majority of fatal dry burns in civilian practice occur in conflagrations in buildings, rather than in vehicles or aircraft. In many of these tragedies death is not caused by burns, but to inhalation of fumes produced by the combustion of the building structure and contents. Indeed, most burns seen by forensic pathologists are post-mortem, either because the victim was already dead from smoke inhalation or because severe post-mortem burning obliterates the lesser degrees of burns present up to the moment of death.

Death from inhaling fumes may be caused in several ways:

- Thermal damage to the air passages and lungs from the direct effect of hot gases. At autopsy the tongue, pharynx and especially glottis may be scorched, lesser degrees causing a greyish-yellow blanching of the mucosa. The interior of the larynx, trachea and main bronchi may be thickened and blanched, or reddened and inflamed, if the temperature is too low actually to burn the lining.



FIGURE 11.12 *It can be difficult or impossible to differentiate between ante-mortem and post-mortem burns when they are sustained near to the time of death. Here the blister with no erythema at the base could either be post-mortem or ante-mortem, as reddening of the margins and adjacent skin can occur for at least an hour after death. It is preferable to call doubtful lesions 'peri-mortal'.*



FIGURE 11.13 *Post-mortem smoke soiling and superficial burns on the leg of a house-fire victim who died of smoke inhalation. Note the complete protection of the skin, which had been covered only by a sock.*



FIGURE 11.14 *Post-mortem burn on the arm and chest caused by a hot-water bottle being left over the heart in an attempt at resuscitation. The lesion is sharp-edged, there is no erythematous margin, and the surface is brown and leathery from post-mortem drying.*



FIGURE 11.15 *Larynx of a house-fire victim showing heat blanching of the epiglottis and glottal entrance from breathing hot gas. The lower cut end of the trachea shows copious soot-containing mucus, also indicating respiration during the fire.*



FIGURE 11.16 *A small bronchus from a fire victim, showing histological evidence of soot deposition, together with desquamation of the epithelium and plugging with cellular debris. (Van Gieson; original magnification ×10.)*

Heat effects on the pharynx and epiglottis can occur post-mortem through passive percolation of hot gas through the open mouth. The lungs usually respond to heat damage by marked pulmonary oedema, though this is often present in fire victims even when the inhalation of hot gas has been insufficient to cause visible damage to the bronchial tree.

Carbon monoxide poisoning is an important aspect of most fires – indeed it is the major or even sole cause of death in many victims of conflagrations, especially in house fires. When any combustible material burns in air, most of the carbon in organic material, such as timber, fabric and furnishings, is converted to carbon dioxide. Carbon monoxide is also produced, however, and, where the access of oxygen is limited or exhausted by the ongoing combustion, larger volumes of the monoxide are produced. Slow, smouldering fires with little flame are likely to produce more monoxide, as with burning bedclothes and mattresses. At the other extreme, rapid flash fires with flames fanned by moving draughts and those involving volatile fuels, such as petrol or kerosene, produce relatively little monoxide – though much depends upon the free access of air.

In many house fires, where the seat of the fire is originally remote from the victim, death may occur from carbon monoxide poisoning long before the flames reach the body.



FIGURE 11.17 *Charred body at the scene of fire showing the 'pugilistic attitude' and post-mortem skin splits on the chest.*

A person may be asleep in an apartment or house, and die without ever waking if large volumes of monoxide creep through the rooms. Burns are often post-mortem in such cases and, where extensive charring occurs, the differentiation between ante-mortem and post-mortem damage may be impossible.

It is often a comfort for bereaved relatives to be told that their loved ones were either already dead or unconscious before the agony of burning reached them, and the pathologist may be able to emphasize this at any inquest or inquiry. Unfortunately, where the bodies are found in positions obviously indicating escape or concealment, such an explanation loses its conviction – though even then it may well be that coma from monoxide poisoning overtook them before burning began.

The pathology of carbon monoxide is dealt with in another section of this book, but it may be repeated here that the autopsy signs are primarily that of a cherry-pink coloration of the skin, blood and tissues. Where smoke staining or extensive charring has occurred, there may be little skin to examine, though there is usually some in a protected position under the body. The blood and tissues usually have the characteristic colour but, when the person is anaemic or exsanguinated, this may be hard to detect. A high saturation with monoxide is usually unmistakable at autopsy, though sometimes certain types of artificial light in the autopsy room, such as some fluorescent tubes, make the cherry-pink colour difficult to confirm. The colour may be better seen if blood is diluted with water against a white background, such as a porcelain autopsy table or sink. Nothing replaces laboratory analysis of a sample, however, and this must be done in



FIGURE 11.18 *The finding of a body in a burnt-out car is always suspicious, but is usually accidental or suicidal. Radiography should always be carried out to exclude firearm injuries. Carboxyhaemoglobin levels are often low or even absent in a rapid flash gasoline fire; this makes the diagnosis of being alive during the fire difficult, especially when there may also be little soot to foul the air passages.*

every case of death from fire, irrespective of the subjective appearance of the skin, blood and tissues.

The saturation of haemoglobin with carbon monoxide varies greatly from one fatal case to another. Many variable factors exist such as the concentration in the atmosphere, the time of exposure and local changes in oxygen content. When carbon monoxide is the sole cause of death, a blood saturation of at least 40 per cent is required, except in old and debilitated persons where deaths have been reported at 25 per cent. Many fatalities will display 50–60 per cent saturation, though levels in general are less than in pure carbon monoxide poisoning, such as car exhaust suicides or industrial exposure, where concentrations of up to 80 per cent may occur. In fires, additional factors such as other toxic fumes and reduction of the atmospheric oxygen may operate, resulting in death at lower carboxyhaemoglobin concentrations.

Yoshida *et al.* (1991) published data from 120 house-fire victims in Japan, in which only nine people had carboxyhaemoglobin (HBCO) concentrations below 10 per cent, the range being from 1 to 95 per cent saturation. Of 31 victims in whom cyanide analyses were made, two had high cyanide and low HBCO.

The variability of monoxide poisoning may be illustrated by the fact that two bodies lying side by side in a burned house may have widely differing blood saturations – indeed, sometimes one victim may have a zero blood monoxide saturation. Children often have much lower levels than adults in the same situation, but even two adults may differ in their carboxyhaemoglobin concentrations, the explanation being unclear. Local variations in draughts, levels above the floor and respiration rates may account for these anomalies.

Carbon monoxide in the blood is a valuable indicator that the victim was alive after the fire began. Where a dead body is disposed of by arson no absorption can take place, as the gas can gain entry only through the pulmonary interface. Thus the presence of more than a smoker's level of 5 per cent saturation of the blood with carboxyhaemoglobin means that breathing occurred after the fire began. It is vital, however, to appreciate that the converse is not true. **The fact that a body in a fire does NOT have carboxyhaemoglobin in the blood does NOT mean that they must have been dead before the fire began.** The records of all forensic departments have examples of this occurrence and therefore it is illogical – and sometimes legally dangerous – to draw the unwarranted inference that such a victim must have been already dead before the fire began, however common the generalization may be. In rapid flash fires, especially where gasoline or kerosene are involved, the monoxide level is more likely to be low or even negative, than in the slower conflagration with restricted access of oxygen that occurs in a burning building.

Toxic substances in fumes

In recent years it has been appreciated that a number of toxic substances other than carbon monoxide may be present in the fumes from fires. Cyanides are predominant and the blood of fire victims may often be shown to have high levels of this toxic compound. Nitric oxide, phosgene and other more complex substances may be liberated, especially when modern plastic polymers are burned. Furnishings, upholstery, paints, lacquers, varnishes and actual structural components are increasingly made from polystyrene, polyurethane, polyvinyl and other plastic materials. These are particularly liable to generate toxic gases when ignited (Anderson *et al.* 1981, 1982).

Caution must be employed when interpreting the analysis of cadaver blood for cyanide, as this substance can be produced in significant concentration by post-mortem decomposition. Particular care must be taken in preservation of samples, which should have fluoride added, and in ensuring there is no delay before analysis so that further decomposition is kept to a minimum. Where cyanides, oxides of nitrogen and other toxic substances are inhaled during a fire, carbon monoxide is inevitably absorbed as well. It then becomes difficult to apportion the relative blame for the death among these different toxic agents – and where there are also ante-mortem burns, the differentiation may be impossible. If the pathologist considers that he cannot identify any ante-mortem burns, then the most logical cause of death is 'inhalation of smoke'. If vital burns are present then, according to the circumstances, these can be given as the cause of death, with or without the addition of 'carbon monoxide or smoke inhalation'.

INHALATION OF SOOT

As well as the inhalation of carbon monoxide, victims in a fire usually breathe in carbon particles present in the sooty smoke. Once again this is more pronounced in a building fire than a vehicle blaze, though there are many exceptions. The combustion of timber floors, roofs, furniture, and the fabric of furnishings and carpets produces large volumes of dense black smoke. Every pathologist attending the scene of a house fire is aware of the thick layer of soot than clings to every surface and may hang in fronds from the ceilings. It is little wonder that such material suspended in the air finds its way into the respiratory passages of the victims.

As a marker of ante-mortem inhalation, it is almost as useful as carbon monoxide. Soot particles may enter the open mouth of a corpse, stain the tongue and pharynx, and may even passively reach the glottis. No significant amount can pass the vocal cords and enter the trachea after death, however, so carbon in the lower respiratory tract is a certain



FIGURE 11.19 *Soot in the tracheal mucus, a sign of breathing while the fire was in progress. Though soot can passively reach the glottis after death if the mouth is open, it cannot reach the lower air passages in any significant quantity. Histology of the smaller bronchi offers complete proof of active respiration.*



FIGURE 11.20 *Soot in oesophagus of a house-fire victim indicating respiration during the fire.*

indicator of breathing during the fire. Histological demonstration of soot in the more peripheral bronchi, out as far as the terminal bronchioles, is absolute proof of such respiratory function. The carbon is usually mixed with mucus adherent to the tracheal and bronchial walls because of heat irritation of the mucosa. Often there is swallowed soot and mucus in the stomach, and again this is evidence of life during the smoky phase of the fire.

ATYPICAL LOCALIZED BURNING AND 'SPONTANEOUS COMBUSTION'

Some very strange instances of fatal burning occur and most experienced forensic pathologists have recollections of apparently inexplicable cases.

A human body may sometimes burn away almost completely, yet the surrounding fire damage is minimal. These almost invariably occur near a hearth or open fire-grate or chimney. The burning may be confined to the body, its clothing, and a narrow zone of floor or carpet. The author (BK) has seen a circumscribed hole burned through a hearthrug and the floorboards beneath, with an ashed body lying in the space under the floor. He also remembers a pair of undamaged house slippers, with feet still within, the legs burned off at ankle level and no remaining body above, apart from ashed material lying on the adjacent floor. Both these deaths occurred in front of a fireplace with an open chimney.

It seems extraordinary that virtually a whole adult body can be consumed, including the skeleton, with minimal surrounding fire damage, but many such cases are on record and have helped to substantiate the myth of 'spontaneous human combustion'.

Experiments carried out many years ago by Professor David Gee (personal communication) indicated that body fat can burn slowly, using the clothing as a 'wick', similar to a candle flame.

Most cases have in common the fact that there was a source of ignition in an open fire and a chimney which can provide a constant updraught – and often the victims are alcoholics. Though it is not suggested that alcohol plays any part in the burning process, the confusion, instability and lack of judgement which goes with inebriation may well precipitate the ignition process.

As indicated above, the myth of 'spontaneous combustion' is one which refuses to go away, as endless unsubstantiated reports, and newspaper, magazine and television features have continued to fascinate a credulous public ever since Charles Dickens included a description of a case in his novel *Bleak House*.

Numerous allegations have been made of people bursting into flames as they walk down the street, but as yet, no photographs or film has been produced; in fact, the majority of the retrospective claims for this phenomenon have been of bodies next to some source of ignition and where alcohol was involved – as indeed was Dickens' original example.

REFERENCES AND FURTHER READING

Anderson RA, Harland WA. 1982. Fire deaths in the Glasgow area: III. The role of hydrogen cyanide. *Med Sci Law* **22**:35–40.

Anderson RA, Watson AA, Harland WA. 1981. Fire deaths in the Glasgow area: I. General considerations and pathology. *Med Sci Law* **21**:175–83.

Anderson RA, Watson AA, Harland WA. 1981. Fire deaths in the Glasgow area: II. The role of carbon monoxide. *Med Sci Law* **21**:288–94.

Ballantyne B. 1977. In vitro production of cyanide in normal human blood and the influence of thiocyanate and storage temperature. *Clin Toxicol* **11**:173–93.

Bohnert M, Rost T, Faller-Marquardt M, *et al.* 1997. Fractures of the base of the skull in charred bodies – post-mortem heat injuries or signs of mechanical traumatisation? *Forensic Sci Int* **87**:55–62.

Bohnert M, Schmidt U, Perdekamp MG, *et al.* 2002. Diagnosis of a captive-bolt injury in a skull extremely destroyed by fire. *Forensic Sci Int* **127**:192–7.

Brown RF. 1978. Injuries by burning. In: Mason JK (ed.), *The pathology of violent injury.* Edward Arnold, London.

Bull JP. 1963. Burns. *Postgrad Med J* **39**:717–25.

Bull JP. 1971. Revised analysis of mortality due to burns. *Lancet* **2**:1133.

Cattaneo C, DiMartino S, Scali S, *et al.* 1999. Determining the human origin of fragments of burnt bone: a comparative study of histological, immunological and DNA techniques. *Forensic Sci Int* **102**:181–91.

Curry AS, Price DE, Rutter ER. 1967. The production of cyanide in post mortem material. *Acta Pharmacol Toxicol Copenh* **25**:339–44.

Dyer RF, Esch VH. 1976. Polyvinyl chloride toxicity in fires. Hydrogen chloride toxicity in fire fighters. *JAMA* **235**:393–7.

Eckert WG, James S, Katchis S. 1988. Investigation of cremations and severely burned bodies. *Am J Forensic Med Pathol* **9**:188–200.

Gerling I, Meissner C, Reiter A, *et al.* 2001. Death from thermal effects and burns. *Forensic Sci Int* **115**:33–41.

Gormsen H, Jeppesen N, Lund A. 1984. The causes of death in fire victims. *Forensic Sci Int* **24**:107–11.

Hill IR. 1986. The immediate problems of aircraft fires. *Am J Forensic Med Pathol* **7**:271–7.

Karlsmark T, Aalund O, Danielsen L, *et al.* 1988. The occurrence of calcium salt deposition on dermal collagen fibres following electrical injury to porcine skin. *Forensic Sci Int* **39**:245–55.

Katcher ML. 1981. Scald burns from hot tap water. *JAMA* **246**:1219–22.

Kojima T, Nishiyama Y, Yashiki M, *et al.* 1982. Postmortem formation of carbon monoxide. *Forensic Sci Int* **19**:243–8.

Kondo T, Ohshima T. 1994. Epidural herniation of the cerebral tissue in a burned body: a case report. *Forensic Sci Int* **66**:197–202.

Levine B, D'Nicuola J, Kunsman G, *et al.* 1996. Methodologic considerations in the interpretation of postmortem carboxyhemoglobin concentrations. *Toxicology* **115**:129–34.

Lokan RJ, James RA, Dymock RB. 1987. Apparent post-mortem production of high levels of cyanide in blood. *J Forensic Sci Soc* **27**:253–9.

Matsubara K, Akane A, Maseda C, *et al.* 1990. 'First pass phenomenon' of inhaled gas in the fire victims. *Forensic Sci Int* **46**:203–8.

Moritz AR, Henriques FC. 1947. Studies of thermal injury: the relative importance of time and surface temperature in the causation of cutaneous burns. *Am J Pathol* **23**:695–704.

Noguchi TT, Eng JJ, Klatt EC. 1988. Significance of cyanide in medicolegal investigations involving fires. *Am J Forensic Med Pathol* **9**:304–9.

Quatrehomme G, Bolla M, Muller M, *et al.* 1998. Experimental single controlled study of burned bones: contribution of scanning electron microscopy. *J Forensic Sci* **43**:417–22.

Richards NF. 1977. Fire investigation – destruction of corpses. *Med Sci Law* **17**:79–82.

Rothschild MA, Raatschen HJ, Schneider V. 2001. Suicide by self-immolation in Berlin from 1990 to 2000. *Forensic Sci Int* **124**:163–6.

Sajantila A, Strom M, Budowle B, *et al.* 1991. The polymerase chain reaction and post-mortem forensic identity testing: application of amplified D1S80 and HLA-DQ alpha loci to the identification of fire victims. *Forensic Sci Int* **51**:23–34.

Schmidt P, Musshoff F, Dettmeyer R, *et al.* 2001. [Unusual carbon monoxide poisoning.] *Arch Kriminol* **208**:10–23.

Schuberth J. 1997. Gas residues of engine starting fluid in postmortem sample from an arsonist. *J Forensic Sci* **42**:144–7.

Schwerd W, Schulz E. 1978. Carboxyhaemoglobin and methaemoglobin findings in burnt bodies. *Forensic Sci Int* **12**:233–5.

Sigrist T. 1999. ['Crow's feet wrinkles' as a sign of preserved consciousness.] *Arch Kriminol* **203**:103–7.

Soares-Vieira JA, Billerbeck AE, Iwamura ES, *et al.* 2000. Post-mortem forensic identity testing: application of PCR to the identification of fire victim. *Sao Paulo Med J* **118**:75–7.

Strom CM, Rechitsky S. 1998. Use of nested PCR to identify charred human remains and minute amounts of blood. *J Forensic Sci* **43**:696–700.

Sweet DJ, Sweet CH. 1995. DNA analysis of dental pulp to link incinerated remains of homicide victim to crime scene. *J Forensic Sci* **40**:310–14.

Teige B, Lundevall J, Fleischer E. 1977. Carboxyhaemoglobin concentrations in fire victims and in cases of fatal carbon monoxide poisoning. *Z Rechtsmed* **80**:17–21.

Yoshida M, Adachi J, Watabiki T, *et al.* 1991. A study on house fire victims: age, carboxyhaemoglobin, hydrogen cyanide and hemolysis. *Forensic Sci Int* **52**:13–20.

Zhu BL, Ishida K, Quan L, *et al.* 2001. Post-mortem urinary myoglobin levels with reference to the causes of death. *Forensic Sci Int* **115**:183–8.

CHAPTER 12

Electrical fatalities

- Physical factors 326
- Electrical considerations 327
- Effects upon muscle 328
- Mode of death 329
- The cutaneous electric mark 329
- Patterned electric marks 332
- Metallic traces in electrical marks 332
- Internal appearances 333
- Histological appearances 333
- Electrocution in the bathroom 333
- Suicide by electricity 334
- Homicide by electricity 334
- References and further reading 337

The passage of a substantial electrical current through the tissues can cause skin lesions, organ damage and death. This injury is commonly called ‘electrocution’, though some would use this term only if death occurs. Fatalities are usually accidental, in both a domestic and industrial environment. Suicides from electricity have increased in recent years, especially in Germany. Homicide is rare but is recorded and, in the USA, electricity has again become a means of judicial execution.

PHYSICAL FACTORS

The severity of tissue damage ‘including death’ is directly related to a number of physical factors, which include current, voltage, resistance and time. For biological damage to occur, the body must be incorporated into an electrical circuit, so that there is a passage of electrons through the tissues. A mere accumulation of electrons in the form of a static charge can do no harm; scientists in the ball of a Van de Graaf static generator may be at a potential of more than a million volts (V), but experience nothing other than their hair standing on end. Similarly, a person outdoors in a thunderstorm may accumulate a high charge from the capacitance effect of an overhead cloud but, unless the insulation of the air breaks down to allow a lightning strike at or near the person, no ill-effects will occur.

In electrocution there must be a pathway for electrons across part of the body which, in fatal cases, contains vital structures. The current enters at one point (most often a hand being used to hold, touch or manipulate some electrical device) and then leaves the body at an exit point, usually to the earth or the neutral conductor of the electricity supply. The pathway of the current will depend mainly on the relative resistance of various potential exit points. It tends to take the shortest route between entry and best exit, irrespective of the varying conductivity of different internal tissues. If a person places a finger on a 240 V conductor while standing with damp shoes on a wet concrete floor, then an appreciable current will pass from hand to feet, with possibly fatal results. If, however, the person is standing on a carpeted upstairs wooden floor, the poor earth return will allow only a small current to flow and all that may be suffered is a painful muscular spasm.

In another variant of the upstairs scene, should the neutral wire of the supply be touching the skin of the same finger a few centimetres away from the live conductor, a severe local burn may occur but no danger to life, because the high resistance through the feet to earth will prevent any significant current flow passing through the thorax.

Should the person upstairs happen to be turning a bath tap with the other hand, the contact with the opposite finger would allow a current to pass to earth via the tap and metal water-pipes from hand to hand across the thorax – an extremely dangerous position.



FIGURE 12.1 *Pathways of current in electrocution.*

The pathologist is concerned with fatal electrocution and three major events may occur, which are a threat to life:

- The most common is the passage of a current across the heart, usually when a hand is brought into contact with a live conductor, and the body is earthed either through the feet or the opposite hand. It has been claimed that the most dangerous is contact with the right hand and exit through the feet, as this causes the current to pass obliquely along the axis of the heart. Compared with the other variables of voltage, skin resistance and time, this hypothesis seems immaterial, though this route increases the current across the heart by a factor of 1.5–2.5 compared with left-hand entry. The fatal process is a cardiac dysrhythmia, usually a ventricular fibrillation ending in asystole.
- Less often, the passage of a current across the chest and abdomen may lead to respiratory paralysis from spasm of the intercostal muscles and diaphragm.
- Rarely, the current passes through the head and neck, usually in circumstances when the head of a worker on overhead power lines comes into contact with the conductor. In such instances, there may be a direct effect on the brainstem so that cardiac or respiratory centres are paralysed.

It is commonly said that tolerance can be gained to electric shock and that professional electricians often work on live 240 V conductors with impunity. It seems more likely that expectation of a shock decreases sensitivity, but only for brief contacts, less than would be required for physiological or structural damage.

ELECTRICAL CONSIDERATIONS

Electrons are moved around a circuit by the 'potential difference' between two points, which may be looked upon as the 'pressure' of the electricity, measured in volts (V). The number of electrons flowing constitutes the 'current', analagous to the volume of electricity and is measured in amperes, though in the present discussion, milliamperes (mA) are more relevant to biological effects. The tissues also have 'resistance' to the electrical flow. There is a mathematical relationship between potential difference, current and resistance – the well-known Ohm's law – in which the current varies directly with the voltage and inversely with the resistance. This law has considerable relevance to biological electrical damage.

Alternating and direct current

In spite of the folklore of electricians there is no doubt that direct current (d.c.) is less dangerous than alternating current (a.c.); a current of 50–80 mA a.c. can be fatal in seconds, whereas 250 mA d.c. for the same time is often survived. Alternating current is four to six times as likely to cause death, partly because of the 'hold-on' effect described below, which is the result of tetanoid muscle spasm and prevents the victim from releasing the live conductor.

Alternating current is also much more likely than direct current to cause cardiac arrhythmias. The passage of a.c. at 100 mA for only one-fifth of a second is likely to cause ventricular fibrillation and arrest. High amperage d.c. (above 4 A) may even cause an arrhythmic heart to revert to sinus rhythm, as in medical defibrillation.

The usual frequency of a.c. is 50 cycles/second (cps), though some American and European systems run at 60 cps. Alternating current between 40 and 150 cps is most dangerous in terms of ventricular fibrillation, and regrettably the usual mains supply lies in the centre of this range. Above 150 cps, fibrillation is progressively less likely as the frequency increases: at 1720 cps the heart is 20 times less likely to fibrillate than at 150 cps.

Current

The degree of damage to the tissues is proportional to the actual quantity of electricity flowing through them. This quantity is expressed by the number of electrons per unit time and strictly speaking should be measured in 'coulombs', which is the product of amperes and seconds, though amperes are usually accepted as an index of the current flow. According to Ohm's law, current depends on the applied voltage, the resistance of the tissue and, for tissue damage, the time for which the current is flowing.

In forensic pathology, we are concerned with fatal electrocution and, as most deaths are the result of cardiac dysrhythmias, the most important measure of current is that which leads to acute heart failure. Estimates vary among authors, but it is generally considered that the passage of 50–80 mA across the heart for more than a few seconds is likely to cause death. The most that can be tolerated voluntarily by most people is 30 mA applied to the hand, which results in painful muscle contractions. Consciousness is likely to be lost at about 40 mA and, as stated, currents sustained for some seconds at over 50–80 mA carry a substantial risk of death.

Voltage

To produce a potentially fatal current across the chest, a certain minimum voltage must be applied to the skin surface. As the latter has a relatively high resistance (see below), Ohm's law dictates that an appreciable voltage is required to produce the 50 mA or so needed for ventricular fibrillation. Most fatalities occur with the domestic voltage of 240, though the common alternative in parts of the USA and Europe of 110 V is still lethal in many instances.

It is uncommon to encounter deaths at less than 100 V, mainly because there are few sources of supply between 110 V and the 12 V or 24 V used in vehicle electrical systems. These are almost always innocuous, though Polson (1963) has reported a fatality at 24 V in a man pinned beneath an electrical vehicle for several hours. That case emphasizes the importance of the time element in electrical injury. Extremely high voltages, such as those encountered in power transmission systems and in electronic equipment, may paradoxically be safer on some occasions, as the shock may physically fling the subject off the conductor, thus reducing the contact time below the threshold for cardiac damage.

Resistance

The major barrier to an electrical current is the skin, which has a far higher resistance than internal tissues. That is why skin electric burns occur, as the resistivity causes energy transfer from the electron flow to the skin. Once inside the dermis, the semi-fluid cytoplasm, and especially the vascular system filled with electrolyte-rich fluid, passes the current through the body quite easily. The resistance of skin varies greatly according to the thickness of the keratin-covered epidermis; that on the soles and finger-pads is greater than the thin skin elsewhere. The average resistance is between 500 and 10 000 ohms for areas other than the horny hand and foot pads, which may offer 1 million ohms resistance when dry.

A more potent factor is the dryness or dampness of the skin, which greatly affects its resistance. While dry palm skin may have a resistance of the order of 1 million ohms, when wetted this may fall to only 1200 ohms. Jellinek (1932) found the horny skin of a workman to have a dry resistance of from 1 to 2 million ohms; Jaffe (1928) stated that sweating could reduce skin resistance from 30 000 to 2500 ohms. When the current begins to pass, there is a further marked drop in resistance, as a result of electrolytic changes in the skin, which may fall to only 380 ohms. Thus for a fixed voltage, such as the mains supply of 240 V, the resultant current will be far greater if the skin is wet from sweating or external moisture. This emphasizes the dangers of bathrooms and using electrical equipment in damp surroundings. Where alternating current is concerned (as in most forensic cases), resistance is replaced by 'impedance', but this is not relevant to the pathological aspects.

EFFECTS UPON MUSCLE

One effect of electricity that has practical implications is the spasm that occurs in skeletal muscle if the current reaches between 10 and 40 mA at 50 cps. When, as most often happens, the entry point is in the hand, the stronger flexor muscles of the arm go into spasm and cause a 'hold-on' effect. This means that any object being held in the hand is involuntarily clenched and, as it is likely to be the faulty electrical appliance or a wire, the object cannot be released and the current thus continues to flow. This adds to the time element and progressively worsens the risk of both cutaneous burns and the risk of cardiac or respiratory arrest. Tingling may be felt in the skin with a current of only 1 mA and 'hold-on' can begin at a current as low as 9–10 mA.

MODE OF DEATH

As already stated, most deaths from electricity are from cardiac arrhythmias, usually ventricular fibrillation ending in arrest. This is caused by the passage of current through the myocardium, especially in the superficial epicardial layers and possibly across the endocardium. The current has a profound effect directly upon the myocardial syncytium, the possible dislocation of the pacemaking nodes and conducting systems being ill-understood. When death occurs from cardiac arrest, the body remains either pale or only slightly congested, the autopsy appearances being unhelpful apart from the presence of any external electrical marks.

The second (and far less common) mode of death is respiratory arrest, in which the passage of current through the thorax causes the intercostal muscles and diaphragm to go into spasm, or become paralysed. In either case, respiratory movements are inhibited and a congestive–hypoxic death occurs. The brainstem is affected rarely, when the current enters through the head. Either cardiac arrest or respiratory paralysis can then supervene.

Many electrical deaths are not observed, the person being found dead later, so that the mode of death is unknown. Sometimes the witnessed mode of death is hard to explain on physiological grounds, in that there appears to be a delay (often some minutes in duration) between the shock and the death. In the interval, the victim may be conscious and even apparently recovering. It is difficult to know why a sudden cardiac arrest should take place after the current is switched off, but presumably some fundamental damage has been caused on an intracellular level to cardiac or neural tissue.

Finally, when discussing the mode of death, it must always be remembered that non-electrical trauma is quite common. In a series reported by Bissig (1960), some 15 per cent of cases had injury from falls and other associated trauma. In industrial accidents and when working on power lines, victims of shock may be thrown from a height, or suffer violent muscular spasms that may lead to fractures and other serious injury.

THE CUTANEOUS ELECTRIC MARK

The point of contact on the body surface may leave skin lesions, which are either called 'electrical burns' or 'electrical marks', though the term 'Joule burn' is gaining in popularity. These are the sites of entry of the current, but another mark or marks may also appear where the body was earthed or 'grounded'. It must be emphasized here that fatal electrocution may occur with no skin mark whatsoever, making the diagnosis entirely dependent upon the circumstances of the death. An extreme example is electrocution in the bath, when the large surface area for entry plus the low skin resistance caused by the water abolishes the possibility of a focal burn.



FIGURE 12.2 *(a) Firm contact electric mark, and (b) spark burn across air gap.*

An electrical mark may not be externally obvious, as the current can be applied to the genitals, anus or abdomen in sexual perversions or through the mouth, especially in children. Infants may place a live plug between their lips and sustain electrical burns on the tongue or buccal mucosa, which may not be readily apparent on external examination at autopsy.

When a current passes, there may or may not be a visible lesion, depending upon:

- the density of the current passage in terms of skin area and
- the conductivity, usually varying with the moisture content.

The skin lesion is a thermal burn from heating of the epidermis and dermis as the current passes. Theoretically, the heat generated can be determined from the formula $GC = C2R/4.187$, where GC is the heat in gram calories per second, C is the current in amperes and R the resistance in ohms. If the electron flood passes through a relatively wide area, then the resistance per unit area is small (especially if the skin is damp) and thus the heating effect is proportionately diminished. For example, a person resting the palm of the hand on a flat metal plate which is electrified will pass a far



FIGURE 12.3 *Firm contact electric marks on a fingertip. Two blisters have been formed by the heat of local skin resistance; they have collapsed on cooling.*

smaller current per square centimetre of skin than another touching the plate with the tip of a finger. The first is likely to have no demonstrable lesions, while the second will have a blistered burn or a keratinized nodule, depending on the firmness of the contact.

The temperature in the tissues directly under the contact point can easily reach 95°C. Tissue damage can occur within 25 seconds when the temperature reaches a mere 50°C. The focal electric mark is largely a thermal burn and even some of the histological features to be described later, which were once thought to be peculiar to the electrical current, are now generally ascribed to thermal effects. There are some features, however, which are characteristic of an electrical cause.



FIGURE 12.4 *Firm contact blister and adjacent spark burn from 240 V mains supply. The victim was holding a faulty electric drill. There were no other marks on the body.*

- When the skin has been in firm contact with an electrical conductor, the passage of the current through the high skin resistance heats up the tissue fluids and produces steam. This may split the layers of the epidermis or the epidermal–dermal junction and produce a raised blister. This may rupture if the current continues or if the area is relatively large.

  When the current ceases, the blister cools and collapses, giving the familiar appearance seen at autopsy. The collapsed blister is often annular, producing a raised grey or white ring with an umbilicated centre. The mark sometimes reproduces the shape of the conductor, especially where this is a linear wire or a shaped metal object. Where the tip of a wire or rod is at right angles to the skin, a focal pit is created, sometimes penetrating quite deeply into the skin.
- Where the contact is less firm, so that an air gap (albeit narrow) exists between skin and conductor, the current jumps the gap as a spark. In dry air 1000 V will jump several millimetres and 100 kV about 35 cm. This is at extremely high temperatures (about 4000°C), as in the sparking plug of a petrol engine, and causes the outer skin keratin to melt over a small area. On cooling, the keratin fuses into a hard brownish nodule, usually raised above the surrounding surface, the so-called ‘spark lesion’.
- In many electrical burns these two types are combined, as a result of movement of the hand or body against the conductor and sometimes because of irregularity of the shape of the conductor. Where the time has been prolonged, the voltage is high, or the conductor is large, the burn may be correspondingly severe with large areas of peeled blistered skin, charred keratin, and a mixture of hyperaemia, deep scorching and shed epidermis.



FIGURE 12.5 *Collapsed blisters and a spark burn from holding a faulty power tool.*



FIGURE 12.6 *Multiple electrical burns on a hand, with blisters showing the typical pale raised margins and areas of peeling epidermis. There is a blackening from metallization as the current was passing for several hours; the victim was an electrician who fell into an air-conditioning plant.*

- A characteristic feature of the electric mark, which is the most useful indicator of the nature of the lesion, is the common occurrence of an areola of blanched skin at the periphery. Presumably because of arteriolar spasm from the direct effects of the current on vessel-wall musculature, the pallor survives death and is virtually pathognomonic of electrical damage. Often there is a hyperaemic border outside the blanching, though reddening may also be seen inside the pale zone, as the outermost rim of the heated burn area. Occasionally, an alternating spectrum of blister-reddening-pallor-reddening can be observed centrifugally from the centre of the lesion. When the burn is linear, such as that from a bare wire pressed against the skin, the 'areola' takes the form of a pale zone parallel to the central burn.
- When the marks are minimal, all that may be seen are tiny white discs representing minute flat blisters where the epidermis has split, but no reddening or areola has formed – or at least, has not persisted until the time of autopsy. These can be hard to find and, as they are likely to be present on the palmar surface of the hands (the usual site from grasping an electrical appliance), the strong flexion of rigor mortis may bring the fingers down to the palms, so obscuring any lesions. It is essential in all autopsies to examine the flexor surface of the fingers by forcible breaking of the rigor – and, where electrocution is a possibility, minute inspection of the hands must be carried out, even if the flexor tendons at the wrist have to be cut to release the rigor clenching of the fingers.
- In high-voltage burns, such as those sustained from high-tension grid transmission cables, where the voltage is in the multi-kilovolt range, sparking may occur over many centimetres. This can cause multiple spark lesions giving rise to a 'crocodile-skin' effect. Both linesmen and copper thieves working on high pylons may suffer non-electrical injuries from being thrown to the ground, or they may sustain gross charring burns or even limb fractures from both direct electrical energy and the muscle spasm caused by a massive bolt of electricity.
- Earthing or 'grounding' lesions are not often seen, but should be looked for on the contralateral hand and on the feet. The lesions may be similar, though less severe. In a case seen by the author (BK), in which a workman pushed a metal wheelbarrow over a live cable lying in a pool of water, the entry burns were on the hands, but on the soles of both feet the electrical burns matched the metal studs in his boots where the current earthed through damp socks and leather.

  In another case, a homicide in a bath, there were no entry burns but the current went to earth by contact of the breasts with the metal taps.
- When the current has flowed for an appreciable time, even at a domestic voltage of 240, the effects may be severe. Charring and more extensive peeling and blistering of skin may occur, with deep muscle damage and cooking of the tissues. This is partly because of the fact that the initial damage lowers skin resistance so that progressively more current flows and therefore more burning and necrosis follows.

Much of this damage seen at autopsy may have occurred post-mortem, if death from cardiac arrest occurs early in the event and, where the victim is alone, there is no one to remove his body from the source of the current. It has been



FIGURE 12.7 *Multiple burns from high-voltage (multi-kilovolt) supply lines of the grid system. The appearance is sometimes called 'crocodile skin' and is caused by arcing of the current over a considerable distance. The victim was a boy who went bird-nesting amongst the switch gear of a power station.*



FIGURE 12.8 *Reconstruction of a fatal electrocution. While replacing a bulb a workman dropped dead, even though the light was not illuminated. The circuit had been improperly 'wired through' – that is, the switch had been placed in the neutral wire, instead of the live. The porcelain holder was broken so that his little finger touched the brass base of the bulb, thus completing the circuit across the chest to the other hand, which held an earthed base-plate. The only electrical mark was on the little finger.*

conclusively shown by Polson and others that post-mortem burns can be inflicted on a dead body, the appearances being similar in terms of blistering and burning, though the red flare of 'vital reaction' will be absent if death has occurred some time before.

PATTERNED ELECTRIC MARKS

As with many other injuries, a pattern of the shape of the causative object may sometimes be identified. When the electrical conductor is a wire, a linear burn may occur. The shape and spacing of electrical plugs or contacts may be seen, and faulty electrical equipment may impress its shape into the skin. These marks may be useful when the pathologist tries to reconstruct the events – and indeed, may indicate for the first time that the death was caused by electricity, when the unwitnessed events are particularly obscure.

As electric shock and burns are commonly seen in torture victims in abuse of human rights, a pattern may be useful in determining what object was used and give evidence of deliberate repetition. The deliberate use of a male-pin plug connected to the mains supply, then pressed against the skin, may give a series of regularly spaced marks, consisting of hyperaemia, blistering, areola formation or even charring.

METALLIC TRACES IN ELECTRICAL MARKS

When a current passes from a metal conductor into the body, a form of electrolysis occurs so that metallic ions are embedded in the skin and even in the subcutaneous tissues. This occurs with both d.c. and a.c. because of the combination of metallic ions with tissue anions to form metallic salts. These may be invisible to the eye, but detectable by chemical, histochemical and spectrographic techniques. They persist for some weeks during life and resist a moderate amount of post-mortem change. Where gross they may be observed directly on the skin, and where copper or brass conductors are involved a bright green imprint may be obvious. Where an electric arc forms, vaporized metal may be deposited on the skin, often extensive enough to be visible to the naked eye. In high-voltage contacts, the skin of a wide area may be brown or greyish, partly from heat effects, but partly from metallization.

Recently, using the scanning electron microscope, it has become possible to see tiny globules of molten metal on the skin at and near an electrical mark, deposited there by the almost inevitable 'mini-arcing' that accompanies any electrical contact. Chemical tests for metallic deposits include that devised by Adjutantis and Skalos (1962), which is a simple touch-test using elution on strips of filter paper. Copper, iron, aluminium, zinc or nickel are dissolved in nitric or hydrochloric acid, and the solution tested with a variety of simple but specific reagents.

INTERNAL APPEARANCES

In fatal electrocution, gross findings in the internal organs may be absent and even histological changes are a matter of controversy. Because the internal tissues are largely aqueous and contain conductive electrolytes, the current pathway is usually too diffuse to cause thermal damage. The absence of visceral damage is made up for by physiological and functional abnormalities, mainly in muscle and nervous tissue.

The usual mode of death is cardiac arrhythmia leading to ventricular fibrillation and arrest. In these deaths there is little to find at autopsy apart from the skin lesions. It is claimed that epicardial petechiae may occur, but these are too non-specific to be of any use. The body is either pale or only slightly congested, in contrast to the **few** deaths that occur from respiratory paralysis.

In the latter group the intercostal muscles and diaphragm go into spasm or are paralysed, which leads to marked congestion and cyanosis of the face, with similar changes in the lungs. There may be some petechiae on the pleura, though this again is such a non-specific finding as to be unhelpful as a diagnostic sign. At autopsy, the usual signs of a congestive death are found, with dark blue–red post-mortem hypostasis.

A number of other signs of electrocution have been claimed, but they are rarely confirmed by personal experience. These include intracerebral petechiae, which are probably part of the general congestive state in respiratory paralysis.

HISTOLOGICAL APPEARANCES

These are rather controversial, as some changes formerly claimed to be specific for electrical lesions have been shown to be thermal.

The skin mark consists of vacuolation in the epidermis and sometimes dermis, caused by the gas spaces from the heated tissue fluids splitting the cells apart. The affected tissues become more eosinophilic. The cap of epidermis may be detached and raised into a blister, with a large space beneath. The cells of the epidermis are often elongated, with the nuclei of the lower layers orientated and horizontally stretched; this was once claimed to be an electromagnetic effect, but the same appearance can be seen in purely thermal burns and in hypothermic lesions.

Changes in the brain have been described, even when the cause of death was cardiac. Focal petechial haemorrhages, spaces around small blood vessels and tears in white matter have been described. Electron microscopy reveals a variety of changes, especially in the nuclei of skin cells, which are deformed with clumped chromatin. Janssen (1984) has compiled a review of electrical histological lesions in his book on forensic histology, but it seems evident that there is little that is absolutely pathognomonic of electrical as opposed to purely thermal burns.

Histochemical reactions for metallization can also be carried out, though, again, metals can be transferred into the skin by purely thermal means if hot metallic objects are pressed against the skin.

Scanning electron microscopy appears to be the best way of distinguishing between electrical and thermal damage, as the punctate nature of the deposition and the possibility of chemical analysis by electron microprobes offer a sophisticated means of identifying the metallic deposit. Internal organs reveal no true diagnostic lesions of electricity. The wavy appearance of the myocardial fibres and their fragmentation may be suggestive, but by no means diagnostic. Contraction bands within the fibres, especially of a 'bark-like' appearance, have been described but, again, are non-specific, though they are often seen in the subepicardial myocardium after resuscitation that includes electrical defibrillation. However, they are identical to catecholamine effects on the myocardium and so may not be electrical in origin.

ELECTROCUTION IN THE BATHROOM

The bathroom is a common site for electrical tragedies. Accidents, suicides and even homicides occur there because of its vulnerability to electrical shock. The bathroom is electrically the most dangerous place in a house as there is a moist atmosphere, ample water, good earthing through metal taps and pipes, and a wet, unclothed body – all of which are conducive to low electrical resistance and hence high tissue currents. Accidents are common, usually as a result of the careless use of electrical appliances, such as hairdryers and room heaters. Most European countries have strict regulations about electrical installations in bathrooms because of the danger. In Britain, no wall switch is permitted for the light, a ceiling switch operated by an insulating cord being mandatory. No power sockets are allowed except for a shaver socket which incorporates a step-down transformer



FIGURE 12.9 *Homicidal electrocution in the bath. An electric heater was dropped into the water with the wire to the earth terminal deliberately disconnected. The 240 V supply entered the body diffusely through the water and completed the circuit by earthing through contact with the breasts against the metal taps, leaving electrical marks on the skin.*



FIGURE 12.10 *Suicide by electricity. Both wrists were wired in this fashion to a 240 V supply socket, the circuit being completed from arm to arm across the chest.*

with a low maximum current output. In spite of this, people unwisely use extension leads or plug into light sockets to operate a variety of appliances.

SUICIDE BY ELECTRICITY

There has been a remarkable increase in the number of suicidal electrocutions in recent years, especially in the bath. Bonte *et al.* (1986) have described an increasing number of cases in the former West Germany, drawing attention to the unusual demarcation of post-mortem hypostasis in such deaths, where the water level during electrocution appears to limit the subsequent appearance of the hypostasis. Various circuit arrangements are made by suicides in baths: these range from the pulling of an electrical appliance into the water to complex connections to metal soap dishes and wiring up contacts on the body. There may even be arrangements to break the circuit when the bathroom door is opened to safeguard those who find the body. The circumstances are rarely in doubt except that some less sophisticated cases may be difficult to differentiate from the many other accidents that occur in bathrooms. Rarely, other more bizarre deaths associated with electricity occur, as seen in Figure 12.11.

HOMICIDE BY ELECTRICITY

Homicide is occasionally committed by electricity, the author (BK) having dealt with two such incidents and his co-author (PS) with one. The first took place in the bath and provided good illustrations of the electrical aspects of fatal shock. A young woman was found dead in her bath, slumped forwards in a kneeling position with one breast resting against a chrome tap. The left arm was trailing over the edge of the bath, in which was the usual level of water plus an electric fan-heater immersed near the feet. The heater was connected by a long cable to a 240 V 13 A socket in an adjacent bedroom. Significantly, the third 'earth' wire had been deliberately disconnected from the earth pin inside the plug. Subsequent forensic tests showed that the enamel lining of the metal bath was an excellent insulator so that earthing of the current through the bath water could only occur via the chrome waste pipe. The circuit was completed, however, with fatal results, by the woman falling (or being pushed) against the tap, so that she sustained an electrical burn on the breast. She also had another typical burn on the inside of her left arm near the axilla, where the insulating enamel of the bath ceased at the turned-over edge. Forensic tests showed that there was a progressive gradient of voltage down the bath from over 200 V near the heater to virtually zero near the earthed waste pipe. The current had preferentially taken a course



FIGURE 12.11 *(a) The deceased man had electrical marks on his fingers and lips, which were stained green from metallization from the brass fittings of the table lamp. (b) In addition, he had a metal comb resting over a large electric burn on his abdomen, also wired up to the lamp socket. No circumstantial evidence of suicidal intent could be discovered and some masochistic exercise was suspected.*

through the victim's body from feet to exit through breast and arm, rather than through the higher resistance of the fresh water.

It was also shown that, when the earth safety wire was reconnected, the voltage at the top of the bath fell to negligible levels, even though the fuse did not blow. The woman's husband, after several denials, eventually confessed to dropping the heater into the bath – and also to borrowing a book from the public library the previous day entitled *The do-it-yourself home electrician!*

The other homicide, which could not be proved for lack of evidence or a confession, concerned the wrapping of bare electric wires around a woman's neck. The wire was thick 30 A cooker cable with 40 cm of insulation stripped except for the extreme tips. The woman's husband, a professional electrician, provided the unlikely explanation that he was using this to test his electric shaver!

The third homicide went first undetected as the perpetrator, the husband of the victim, had staged it as an accident. The wife was supposed to have been ironing in the kitchen early one morning and been electrocuted by a faulty cord of the iron, the water-pipe of the sink providing the contact to the earth. In addition to the SOCs, an electrician, but not the pathologist, was called to the scene to investigate the faulty device, but nothing suspicious was detected. Ironically, in spite of the clumsy way in breaking the insulation of the cord and leaving only a couple of millimetres of the naked wire visible, a picture of the faulty cord and iron landed in a textbook for electricians, pointing out the dangers of faulty household appliances. At autopsy the only finding was an electrical burn on the chest. Eight years later, when the husband was in detention in the course of an investigation due to a stolen money transport, he wrote a very detailed confession of the murder of his wife. He had attached two copper electrodes to an extension cord and, while the wife was asleep, pressed them to her chest. In court, in spite of the withdrawal of his confession, he was sentenced to a long imprisonment. Several details, which came out in the course



FIGURE 12.12 *Electrical burn around the neck from a mains wire being held against the skin. The typical pale areola and peeled skin blistering can be seen. There was suspicion of homicide, but it could not be proved.*



FIGURE 12.13 *The fern-like, arboresque pattern seen over the shoulders and chest in a victim of lightning stroke. Although this is always mentioned in descriptions of lightning deaths, it is seen only in a small minority of cases.*

of the criminal investigation, implied, although it was never proven, that the man had first attempted to kill his wife by feeding her diazepam tablets without her knowledge, and when this had failed, electrocuted her. It is hindsight and fruitless to contemplate what might have happened if the pathologist had been to the scene. The lesson of the case is, however, that if electrocution is suspected, it certainly is worthwhile to take a look at the scene of death.

In tropical and subtropical countries deaths from lightning are not uncommon and, even in higher latitudes, occasional tragedies occur where numbers of people are killed or injured in single episodes. An example was at the Ascot race meeting in 1955. The physics of a lightning strike are complex and not fully understood. Gigantic voltages and amperages are involved when a highly charged thundercloud discharges via a huge arc to the ground.

Lightning deaths cannot be other than accidental and provide no real problems for the forensic pathologist. Occasionally the nature of the death may be uncertain if a dead body is discovered in the open with no marks upon it, but usually there will be reports of a lightning strike nearby and artefacts, such as torn and scorched clothing and magnetized metallic objects in the pockets, may assist in explaining the event.

It is well known that injury from lightning is capricious and unpredictable. Two people can stand side by side during a flash and one may be mutilated and killed while the other is unharmed. The physical damage in fatal cases can vary from virtually nil to gross burning, fractures and tissue destruction. Cutaneous marks may be present, the well-known ‘fern-like’ or ‘arboresque’ pattern, also referred to as ‘Lichtenberg’ figures (because of their similarity to the pattern described by a German physicist, Georg Christoph Lichtenberg, in 1777) being much less common than the standard texts suggest. Irregular red marks, often linear first-degree burns, may follow skin creases, especially if damp from sweating. These marks may be many inches long and generally follow the long axis of the body towards the ground. Frank blistered or charred burns are also present in some cases.

An excellent picture of the Lichtenberg figures was taken by Domart and Garet, published in the *New England Journal of Medicine* in 2000, showing a 54-year-old man struck by lightning. With the exception of numbness and paraesthesia of the left shoulder, flank and leg, he felt well on the arrival at the emergency department. The serum creatine kinase and myoglobin concentrations were slightly elevated. After a 24-hour observation period, the patient was sent home and two days later, on a follow-up visit, the fern-leaf pattern of marks had disappeared.

The clothing may be torn off and this can sometimes raise the suspicion of foul play if the lightning aspect is obscure. The clothing is typically ripped open as if by an internal explosion, and belts and boots may be similarly ruptured. Metal objects in the pockets may be fused or magnetized, as may be metal buttons and tooth fillings. Burns on the skin may be adjacent to metal objects in or on the clothing.

There is often a smell of singeing or burning about the body and its clothing. The hair may be scorched and there is often a head injury, caused either by the lightning strike itself or by falling to the ground.

REFERENCES AND FURTHER READING

Adjutantis G, Skalos S. 1962. The identification of the electrical burn in cases of electrocution by the acro-reaction test. *J Forensic Med* **9**:101–4.

Anders S, Matschke J, Tsokos M. 2001. Internal current mark in a case of suicide by electrocution. *Am J Forensic Med Pathol* **22**:370–3.

Arden GB, Harrison S, Lister J. 1956. Lightning accident at ascot. *Br Med J* **2**:1450–3.

Arnold R, Giebe W, Winnefeld K, *et al.* 2002. [An initially unexplained death during prison sentence. Diagnostic verification by atomic absorption spectrometry.] *Arch Kriminol* **209**:14–19.

Bailey B, Forget S, Gaudreault P. 2001. Prevalence of potential risk factors in victims of electrocution. *Forensic Sci Int* **123**:58–62.

Bissig H. 1960. Über Niederspannungsunfälle. *Elektromedizin* **5**:154–60.

Bonte W, Sprung R, Huckenbeck W. 1986. [Problems in the evaluation of electrocution fatalities in the bathtub.] *Z Rechtsmed* **97**:7–19.

Bornstein FP. 1962. Homicide by electrocution. *J Forensic Sci* **7**:516–17.

Critchley M. 1934. Neurological effect of lightning and electricity. *Lancet* **1**:68–70.

Domart Y, Garet E. 2000. Images in clinical medicine. Lichtenberg figures due to a lightning strike. *N Engl J Med* **343**:1536.

Dutra FR. 1981. Electrical burns of the skin. Medicolegal investigation. *Am J Forensic Med Pathol* **2**:309–12.

Eriksson A, Ornehult L. 1988. Death by lightning. *Am J Forensic Med Pathol* **9**:295–300.

Harrison SH, Arden GP. 1957. Electrical burns. *Br J Clin Pract* **10**:117–20.

Holder JC. 1960. An unusual method of attempted suicide. *Med Leg J* **28**:41–3.

Jacobsen H. 1997. Electrically induced deposition of metal on the human skin. *Forensic Sci Int* **90**:85–92.

Jaffe RH. 1928. Electrical injury. *Arch Pathol* **5**:837–70.

Janssen W. 1984. Injuries caused by electricity. In: *Forensic histopathology*. Springer, Berlin.

Jellinek S. 1932. *Elektrische verletzungen*. Barth, Leipzig.

Klintschar M, Grabuschnigg P, Beham A. 1998. Death from electrocution during autoerotic practice: case report and review of the literature. *Am J Forensic Med Pathol* **19**:190–3.

Lee WR, Zoledziowski S. 1964. Effects of electric shock on respiration in the rabbit. *Br J Ind Med* **21**:135–48.

Marcinkowski T, Pankowski M. 1980. Significance of skin metallization in the diagnosis of electrocution. *Forensic Sci Int* **16**:1–6.

Mellen PF, Weedn VW, Kao G. 1992. Electrocution: a review of 155 cases with emphasis on human factors. *J Forensic Sci* **37**:1016–22.

Moncrief JA, Pruitt BA, Jr. 1971. Hidden damage from electrical injury. *Geriatrics* **26**:84–5.

Morgan EW. 1958. Atrial fibrillation and subdural haematoma associated with lightining strike. *N Engl J Med* **259**:956–9.

Pasetti M, Viterho B. 1965. Ultrastructural modifications in the skeletal muscles of electrocuted mice. *Med Sci Law* **5**:29–36.

Perper J. 1977. *Electrical injuries*. In: Wecht C (ed.), *Legal medicine annual 1976*. Appleton Century Crofts, New York.

Pierucci G, Danesino P. 1980. The macroscopic detection of metallization in the latent current mark. *Z Rechtsmed* **85**:97–105.

Polson CJ. 1963. *Essentials of forensic medicine*. Pergamon Press, Oxford.

Polson CJ, Gee DJ, Knight B. 1985. *Essentials of forensic medicine*, 4th edn. Pergamon Press, Oxford.

Puschel K, Brinkmann B, Lieske K. 1985. Ultrastructural alterations of skeletal muscles after electric shock. *Am J Forensic Med Pathol* **6**:296–300.

Puschel K, Lockemann U, Bartel J. 1995. Postmortem investigation of serum myoglobin levels with special reference to electrical fatalities. *Forensic Sci Int* **72**:171–7.

Robinson DW, Nasters F, Forrest WJ. 1965. Electrical burns an analysis and review of 33 cases. *Surgery* **57**:385–90.

Shaw D, York-Moore ME. 1957. Neuropsychiatric sequelae of lightning strike. *Br Med J* **2**:1152–4.

Somogyi E, Rozsa G, Toro I, *et al.* 1967. Electron microscopic observations on the epidermis of the electrocuted skin of rats. *Med Sci Law* **7**:152–5.

Thomsen HK, Danielsen L, Nielsen O, *et al.* 1981. Early epidermal changes in heat- and electrically injured pig skin. I. A light microscopic study. *Forensic Sci Int* **17**:133–43.

Thomsen HK, Danielsen L, Nielsen O, *et al.* 1981. Early epidermal changes in heat- and electrically injured pig skin. II. An electron microscopic study. *Forensic Sci Int* **17**:145–52.

Torre C, Varetto L. 1986. Dermal surface in electric and thermal injuries. Observations by scanning electron microscopy. *Am J Forensic Med Pathol* **7**:151–8.

Werne AH. 1923. Death by electricity. *NY State Med J* **118**:498–502.

Wright RK, Davis JH. 1980. The investigation of electrical deaths: a report of 220 fatalities. *J Forensic Sci* **25**:514–21.

Zhang P, Cai S. 1995. Study on electrocution death by low-voltage. *Forensic Sci Int* **76**:115–19.

CHAPTER 13

Complications of injury

■ Haemorrhage 339
■ Infection 340
■ Pulmonary embolism 340
■ Fat and bone marrow embolism 343
■ Adult respiratory distress syndrome 345
■ Renal failure following trauma 345
■ Disseminated intravascular coagulation 345
■ Air embolism 346
■ Subendocardial haemorrhage 348
■ Sudden death from suprarenal haemorrhage 349
■ References and further reading 349

Serious bodily injury, from whatever cause, may either lead to virtually instantaneous death from destruction of vital organs and structures, or may cause delayed death from complications of the original injury. This delay may be short, as in torrential haemorrhage or acute respiratory failure, or it may be progressively longer, stretching into hours, days, weeks or even years. For example, the author (BK) dealt with a death in which a glider crash 15 years previously had to be implicated as the sole reason for the death, as the victim suffered a fractured spine, a paraplegia, paralysed bladder and recurring ascending urinary infection leading to death in renal failure from bilateral pyelonephritis.

Many even more delayed deaths can be found in the records of most experienced forensic pathologists. As long as a direct chain of events can be traced from the injury to the death, then the former must be considered to be the basic cause, a fact which may have profound legal implications both for civil compensation and criminal responsibility. Some of the most difficult problems in forensic pathology – and some of the most arduous testimony and cross-examination in court – concern deaths from which post-traumatic complications are disputed as being causative factors.

HAEMORRHAGE

Bleeding may occur externally through lacerations and incised wounds or via natural passages, such as the bronchi and trachea, oronasal passages, ears, vagina, urethra or rectum. Internal bleeding comprises contusions, which are leakages of blood into tissue spaces from rupture of vessels and free bleeding into body cavities, notably the pericardium, peritoneum, pleura and cranium.

The volume varies greatly, from the tiny petechiae of ruptured venules to the massive amounts seen in a ruptured aorta. As a primary cause of death it is not only the total volume that is lethal, but the rapidity and the site of the bleeding. When the leakage is slow the body can compensate for the loss of a far greater volume, both by adjustment of the vascular bed and by restoration of the blood volume by transfer from other aqueous compartments.

As to site, it is obvious that a small quantity of bleeding into the brainstem is likely to be lethal, whereas the same volume exuded into the pleural cavity would be of little consequence. Bleeding usually begins at the time of injury, though there is often a momentary delay at the instant of infliction. When a sharp blade cuts the skin, it is a matter of common observation that the blood may hesitate for a second or so before welling out. This is caused by transient spasm of local vessels from the stimulus of the injuring object. Bleeding then continues until normal haemostasis plugs the vessels.

In some injuries involving arteries, the musculoelastic vessel may retract and its wall invaginate, so that an almost immediate seal prevents copious haemorrhage. Occasionally even gross injuries, such as the amputation of a limb by a railway wheel, may be almost devoid of significant bleeding, because the crushing effect may combine with arterial wall retraction to seal the cut vessel effectively. It can sometimes be more dangerous partly to transect an artery than to divide it completely, as retraction cannot then take place. Failure of haemostasis is a haematological matter, but may have medico-legal connotations if an injury (which includes a surgical procedure) is performed on someone who has a haemorrhagic diathesis either from natural disease, or from therapeutic anticoagulant treatment, such as heparin or warfarin.

Delayed bleeding may be seen in a number of conditions. In trauma, especially traffic accidents, organs, such as the liver, spleen or (sometimes) lung, may be injured within their capsules or covering membranes, which initially remain intact. A good example is a subcapsular haematoma of the liver, which may be large and grow even larger as continued bleeding strips more capsule from the parenchymal surface. Eventually, the blister may rupture and the now unrestrained bleeding area can pour into the peritoneal cavity. Trauma can also weaken the wall of an artery or vein, leading to a false aneurysm, which can later rupture. An arteriovenous fistula can also form and later burst.

Infections can also develop in trauma sites and involve vessels in the vicinity, so that an abscess or cellulitis can secondarily lead to severe haemorrhage when the vessel wall is eroded. This is rare except among poorly treated accident or battle casualties, as are mycotic aneurysms that result from infected emboli impacting in a branch of an artery and causing local septic necrosis.

It is sometimes difficult to know how much of a haemorrhage found at autopsy may be accounted for by post-mortem bleeding. There is little doubt that the volume may increase after death, but, except in serous cavities, such as the pleura and peritoneum, or externally from the body surface, in most cases this is a small proportion of that which leaked under arterial pressure during life, due to the tissue pressures opposing passive bleeding.

However, a haemothorax from a ruptured aorta may amount to several litres and much of this may be in the form of a large shaped clot. A clot can form post-mortem, so its presence cannot be taken as an index of *in vivo* formation, but the source of the bleeding will usually be obvious and any post-mortem addition will not affect the interpretation. Copious external bleeding can continue after death, especially from the scalp, particularly if the head is dependent after death.



FIGURE 13.1 *Massive intra-abdominal bleeding from a subcapsular haematoma of the liver due to blunt abdominal trauma.*

INFECTION

Infection used to be so common after open wounds that it was the norm rather than the exception. Prior to the introduction of sulphonamides and antibiotics, many criminally inflicted wounds, which in themselves were not a danger to life, became fatally infected so that an assault became a homicide. This illustrates the fallacy of comparing murder rates in the last century with today, as the survival rate because of rapidly available ambulance and resuscitation services, blood transfusion, emergency operations and antibiotics is vastly greater now than in former times, when even a trivial injury was often fatal.

The types of post-traumatic infection are legion and vary greatly from country to country. Purulent wound infection from Gram-positive cocci, Gram-negative bacilli, anaerobes, such as *Clostridium perfringens*, and other more common organisms, is the most frequent, but in some countries tetanus and anthrax are common dangers. The whole matter is one of clinical microbiology, and the main forensic relevance is to prove a chain of causation between the original injury and a death from intercurrent infection. There may be medico-legal issues involved, such as failure to give or delay in giving antibiotic cover, which can have both civil and criminal legal consequences. A criminal assault that ends in death because of a neglected infection does not exonerate the perpetrator from all responsibility, even though there has been a *novus actus interveniens* in the form of defective medical treatment.

PULMONARY EMBOLISM

This is a most important topic in forensic pathology, as the medico-legal implications of a fatal pulmonary embolus are common and profound. Pulmonary embolism is the most underdiagnosed cause of death where no autopsy is performed; it has been estimated that, in the USA – and probably elsewhere – less than half of fatal pulmonary emboli are recognized clinically.

As with infection, an originally non-lethal injury may end in death because of venous thrombosis and pulmonary embolism, making what might be a simple accident or a common assault into a grave legal issue. The victims of many forms of trauma are at risk from pulmonary embolism because:

- Tissue trauma increases the coagulability of the blood for several weeks, the peak being between one and two weeks.
- Injury to the tissues, especially the legs or pelvic region, may cause local venous thrombosis in the contused muscles or around fractured bones.
- The injury may confine the victim to bed, either because of general shock and debility (especially in old people) or because the trauma itself necessitates recumbency, as in head injuries, severe generalized trauma or injury affecting the legs. In either case, recumbency leads to pressure on the calves and immobility causes reduced venous return and stasis because of lessened muscular massage of the leg veins. The common result is thrombosis of the deep veins of the legs, which can extend proximally into the popliteal and femoral vessels, forming a dangerous source of venous thromboemboli. Small emboli may break off and impact in more peripheral branches of the pulmonary arteries, sometimes causing pulmonary infarcts that may be precursors of a massive embolus that impacts in the major lung vessels and causes rapid death.

At autopsy, such large emboli are readily visible and can usually be easily distinguished from post-mortem clot. The latter is dark red, soft and jelly-like, with a shiny, glistening surface. It is often separated into ‘chicken-fat’ plasma clot and dark red-cell clot by sedimentation after death. When pulled out of the vessels it forms a cast of the branches, albeit shrunken by clot retraction. It is less evident in peripheral branches and, when the lung is sliced post-mortem, clot does not pour out of cut small vessels.

Conversely, ante-mortem embolus (especially if a number of days old) is firm, though brittle and has a dull, matt, striated surface from fibrin lamination. Older thrombus tends to be greyish-red and varies in colour from place to place. Although it may appear to be a cast of the large vessel in which it is impacted, it may often be unravelled to form a long length that obviously originated in a leg vein. Side branches, or the stumps thereof, may be seen that do not correspond to the branches of the pulmonary artery in which they lie.

Post-mortem clot may be adherent to the ante-mortem embolus and sometimes forms a sheath around it, so that the true nature is obscured unless a careful examination is made. On cutting the lung with a knife, ante-mortem emboli may be seen in the more peripheral vessels, often standing up slightly ‘proud’ above the surface, like toothpaste coming from a tube.

The importance of the differentiation between ante-mortem emboli and post-mortem clot is emphasized, as the legal issues hanging upon the unequivocal diagnosis may be very important. Histological confirmation of an ante-mortem origin must be made if there is any doubt. Pulmonary infarction does not occur from fatal massive pulmonary embolism, as death is too rapid. There may be infarcts present in the lungs but these must be caused by previous smaller emboli, at least a day earlier and probably much longer.

Medico-legal aspects of pulmonary embolism

Pulmonary embolism is the most underdiagnosed condition in British death certification, frequently being unsuspected as the cause of death by clinicians. Several investigations into the medico-legal aspects have been made (Knight 1966; Knight and Zaini 1980; Zaini 1981) and the peak incidence at about 2 weeks after trauma confirmed. In Knight’s survey, more than three-quarters of the victims had predisposing factors such as injury, surgical operation or immobility in bed, but the remaining 20 per cent were ambulant and apparently healthy. This has important medico-legal implications because, if fatal pulmonary embolism can strike an appreciable proportion of the population who have not suffered one of the recognized predisposing factors, then the cause–effect relationship after trauma is weakened. If the standard of proof in criminal trials must be ‘beyond reasonable doubt’, then the fact that up to 20 per cent of pulmonary embolism deaths have not followed trauma or immobility must surely remove the cause–effect relationship from near-certainty to mere probability, which is sufficient for a civil decision, but not for a criminal conviction. This is a legal matter for the judge, however, who may or may not let the matter go to the jury – and if it does, for the jury to decide. There is marked variation in these decisions from case to case.

After the lung appearances have been examined and pulmonary embolism confirmed, the source of the embolus must be sought. In almost all cases this will be found in the vessels draining into the femoral veins, though rarely pelvic vessels are involved (usually in relation to pregnancy or abortion). Here pelvic veins may be thrombosed, with extensions into the iliac system and exceptionally into the inferior vena cava. An even more rare source is from jugular thrombosis, sometimes seen as extensions of intracranial venous sinus thrombosis. Axillary and subclavian vein thrombosis is equally unusual, the legs accounting for the vast majority of emboli.

In the usual leg vein thrombosis, various autopsy techniques are available to seek the site of obstruction. Extensive dissection is favoured by some, in which the femoral vein is exposed through a skin incision, this being continued distally as far as necessary to find the residual thrombosis. Of course, after a massive pulmonary embolus, by definition a large part of the source thrombus has been detached and therefore the pathologist has to search further distally to find the remnants. This makes dissection an extensive and disfiguring process, so alternative techniques can be used.

Zaini found that many thrombi begin far distally, even in the dorsum of the foot. He used a flexible wire with a blunt terminal knob (a Bowden cable from a bicycle brake) inserted down the femoral vein until it was arrested, then cut down from the skin at that point to examine the peripheral veins. Alternatively, transverse or longitudinal incisions can be made into the calf of the leg to examine the deep veins. The soleus and gastrocnemius muscles are transected to view their contained veins, but often the thrombus is found in the interosseous veins between tibia and fibula. If ageing of the thrombus is attempted histologically, then it should not be expressed from the vein, but the vein should be taken out with adjacent muscle, as it is the junction between thrombus and vein wall that offers the most information about the maturity of the thrombus.

Dating of pulmonary emboli and deep vein thrombi

As discussed above, it can be a matter of considerable medico-legal importance to know if a pulmonary embolus arose prior to, or subsequent to, some traumatic event. A major difficulty is that the embolus may be the most recent addition to an extending venous thrombosis that is considerably older.

It is also difficult to use histological criteria to date the free embolus from the lungs, as it is the thromboendothelial junction that provides the most information. The best method, therefore, is to examine the residual thrombus, almost always in the leg veins, to see if the oldest part could have formed as far back in time as the suspected traumatic event. For this, the vein wall with the contained thrombus is required. A segment of thrombosed vein, if necessary with adjacent muscle, should be dissected out of the leg. The presence of thrombus will have been confirmed prior to removal by transverse cuts across the calf or thigh muscles containing the veins. Sometimes the original site of thrombosis may be as far distal as the dorsum of the foot.

The thrombus-containing vein is processed in the usual way and subjected to various histological stains. Though accuracy about dating is impossible, the following is a useful scheme to provide at least an approximate idea of the duration of thrombosis in the section of vein under study – remembering always that other segments or other veins may have thrombi of different dates.

- Platelet and red-cell appearances give no useful information. Red cells begin to haemolyse between 24 and 48 hours to form amorphous masses, but many intact red cells survive for weeks.
- Using phosphotungstic acid-haematoxylin stain (PTAH), fibrin can be seen as purplish strands on the first day, but they aggregate into small masses with a meshwork of thicker strands and sheets by 4 days. After 2 weeks, the fibrin becomes more deeply purple stained, but begins to be absorbed by about the twenty-fifth day. Using Martius Scarlet Blue stain (MSB), the early pink fibrin strands become fringed by scarlet in about a week.
- Endothelial proliferation is most useful in the first week, as buds begin to arise from the vessel wall about the second day and proliferate during the first week. Clefts lined by endothelium are seen around the periphery of the thrombus against the vein wall. Artefactual contraction caused by fixation shrinkage must be excluded by seeking endothelial nuclei. These endothelial buds anchor the thrombus to the vein wall, and represent the first stage of healing and recanalization. They are usually noticeable by about the fourth day when they begin growing into the fibrin mass and breaking it up into compartments.
- Collagen fibres do not appear for about 5–10 days, often much later. Fibroblasts may be seen as early as 2 or 3 days, but tend to appear towards the end of the first week and reach a maximum at 2 or 3 weeks, reaching a maximum at about 4 weeks. Elastic fibres appear late, not before 28 days and often much later. They reach their maximum density in about 2 months, mainly in the walls of recanalizing vessels.
- Haemosiderin, blue granules demonstrated by Perl's reaction, may be seen by the end of the first week and reach a maximum in 3 weeks. It does not seem to be present as early in thrombi as in extravascular haemorrhages, such as bruising or meningeal bleeding, where it can be seen in 2 or 3 days.
- Capillaries begin to appear on the second day as endothelial buds, but do not contain red cells until about 2 weeks. Over the next 3 months, substantial canalization occurs by widening and merging of these channels. The full lumen may be restored within 6–12 months, but endothelial thickening and haemosiderin deposits in the vein wall may form permanent evidence of a former thrombus.
- Leucocytes, both polymorph and mononuclear, are inconsistent markers; sometimes they do not appear at all. Polymorphs may be seen within the first day – sometimes in profusion – but they vanish rapidly, often by the next day when mononuclears take their place.

- Covering of the thrombus surface by endothelium is rapid and may begin on the first day and be complete within a few days. Various authors have given 24–72 hours as the time required. Naturally, the size of the thrombus surface is a variable factor. Also, only sections taken where the thrombus does not fully fill the vein lumen will provide an opportunity for observing the endothelial covering.

FAT AND BONE MARROW EMBOLISM

Another important sequel to trauma – fat embolism – is the subject of considerable controversy about the source of the lipoid; this does not, however, detract from the autopsy significance of its detection.

A great deal has been written about the pathophysiology of fat embolism and it is now evident that it is not just a simple extrusion of marrow or adipose tissue material by mechanical trauma. The work of Sevitt (1962), Bergentz (1961), Edland (1971), Ellis and Watson (1968), Buchanan and Mason (1982), and many others must be studied for detailed accounts of the suggested pathogenesis.

Wherever the fat comes from, embolism is most often seen after injury to bone or fatty tissue. In simplistic terms, where skeletal structures containing fatty marrow are damaged or where subcutaneous fat is compressed or lacerated, fat globules commonly appear in the pulmonary capillaries – and where they are numerous they somehow leak through the lungs into the systemic circulation where they can cause severe disability or death from impaction in vital organs, such as brain, kidney or myocardium. Not only fat, but cellular haematopoietic tissue from bone marrow, can be liberated into the venous system and reach the lungs.

The clinical manifestations of fat embolism depend on the volume of fat reaching the lungs. If substantial, ventilatory problems can ensue because of vascular obstruction and pulmonary oedema. The most dramatic symptoms occur, however, with systemic fat embolism when globules reach the brain and cause a range of neurological abnormalities, usually coma and death from brainstem involvement.

There is usually a delay between trauma and cerebral fat embolism while fat builds up in the lungs, so that a 'lucid interval' occurs, which may be confused clinically with the development of an extradural or subdural haemorrhage. Sevitt stated that of patients with multiple bone fractures, no fewer than 45 per cent had pulmonary fat emboli and 14 per cent had cerebral embolism.

Fat embolism is also associated with burns, barotrauma, soft tissue injury, osteomyelitis, diabetes, surgical operations on fatty tissues (especially mastectomy), septicaemia, steroid therapy, acute pancreatitis and the fatty liver of alcoholism, though fractures remain the most potent cause of the condition. In burns, there is some doubt whether pulmonary fat embolism is a true ante-mortem process, or whether fat can be melted out of tissues and organs in the perimortal period. Mason's (1968) experience in rapid air-crash fires was that fat embolism was not present, but Sevitt's hospital series revealed embolism in 47 per cent of deaths from burns.

Pulmonary fat embolism

After trauma, fat commonly appears in the lungs and can be demonstrated there histologically in the majority of cases of fractures and injury to fatty parts of the body such as the buttocks. Indeed, Lehman and Moore (1927) showed that half of a series of non-trauma deaths had histological evidence of fat in the lungs. Mason found fat in the lungs of 20 per cent of his series of non-trauma deaths, but emphasized that quantitatively the amount was small in contrast to that found in cases of fatal trauma. He used a simple scale for assessing the histological severity of embolism as seen in Oil Red-O frozen sections of lung:

- Grade 0: no emboli seen
- Grade 1: emboli found after some searching
- Grade 2: emboli easily seen
- Grade 3: emboli present in large numbers
- Grade 4: emboli present in potentially fatal numbers.

In systemic fat embolism, no such grading is possible; they are either absent or scanty, or they are abundant.

In most instances, pulmonary fat embolism is merely a phenomenon and not a clinical syndrome and the difference between the two seems closely related to the amount of fat impacted in the lung vessels. When clinically manifest it appears as acute respiratory insufficiency, the incidence being up to 2 per cent in long bone fractures and as much as 10 per cent in multiple fractures, especially with pelvic injuries. In small to moderate amounts, fat in the lungs gives rise to no disability, but large amounts, easily seen by a cursory glance at any field of a fat-stained histological section, give rise to acute respiratory distress. Marked pulmonary oedema is the pathological marker for this syndrome, but caution must be employed, as cerebral fat embolism can also cause pulmonary oedema by its effect upon the brain.

Systemic fat embolism

Here the fat penetrates the lung capillaries and appears in the major circulation, so that it can be carried to any organ or structure, including the skin, where it can cause petechial-like



FIGURE 13.2 *Pulmonary fat embolism (Oil Red-O frozen section of lung; original magnification ×20).*



FIGURE 13.3 *Pulmonary bone marrow embolism (van Gieson staining, original magnification ×10).*

lesions. Systemic fat embolism is the fatal manifestation, except where pulmonary loading is so great that it causes respiratory distress. The brain, kidneys and myocardium are the most vulnerable target organs, the brainstem being the one that is most likely to lead to death from impaction of fat globules in its capillaries.

Autopsy findings in fat embolism

When fat is released through the lungs into the systemic circulation, a number of target organs and tissues exhibit abnormalities demonstrable at autopsy, either by gross or histological examination.

Petechial haemorrhages are the typical lesion, caused by the impaction of fat droplets in small venules. These may be seen in the skin of any part of the body, but especially over the front of the chest and on the face and eyelids. Internally they can be widespread but are classically seen in the white matter of the brain, both cerebral and cerebellar hemispheres, as well as the brainstem. Microscopically, when frozen sections are stained by Oil Red-O or other fat stain, the cerebral petechiae will show a central fat globule or globules, and others will be visible without haemorrhage.

In the myocardium, fat may be seen in the interfibre capillaries and in the kidney glomeruli may be stuffed with stained fat. There can be fat in the retina and in the optic nerve, which, in survivors, can cause visual impairment.

Fat embolism is markedly underdiagnosed, both clinically and at autopsy. The more often and the more thoroughly it is sought, the more often it is found. Mild to moderate degrees of pulmonary fat embolism, without systemic overspill, however, must not be given as a cause of death unless there are corroborative clinical features.

Bone marrow embolism

Bone marrow embolism is almost wholly a pulmonary phenomenon, as only in quite exceptional circumstances can cellular material penetrate the lung capillaries. It is quite common in association with fractures of long bones or in multiple bone injuries, though again the frequency with which it is seen is directly related to both awareness and the thoroughness of the search. Where marrow is found, the degree of fat embolism is usually substantial. The common concurrence of fat and cellular embolism is strong evidence of a marrow source for embolic fat, as pointed out by Mason, who found marrow cells in 81 per cent of his cases that had a grade 2 or more lung loading with fat, on a scale of 0–4. According to both Sevitt and Mason, the finding of both substantial fat and marrow emboli in the lungs is definite evidence of ante-mortem infliction of any discovered trauma. For these elements to reach the lungs there must be a competent circulation, albeit for a short time after the trauma.

With the possible exception of burns, any injury inflicted after cessation of effective cardiac function cannot transmit fat or marrow to the pulmonary capillary bed. This is therefore a useful forensic marker on some occasions, such as differentiating between ante-mortem and post-mortem fractures in a body recovered from water. Systemic embolism is not seen in rapid deaths following trauma: there is an interval averaging 24 hours before lung percolation takes place.

Foreign body embolism

A number of other objects may be found as emboli during forensic autopsies and histology. The lung granulomata of



FIGURE 13.4 *Small foreign body granuloma with giant cells and birefringent particles as seen in polarized light in the lung of a drug addict (HE, original magnification ×20).*

talc, etc., seen in the lungs of intravenous drug users, are emboli from contaminants introduced into the venous system by syringe and needle. Shotgun pellets and bullets may enter the circulation via tissue damage and embolize to various sites including coronary arteries. In fat and bone marrow embolism, even fragments of bone and cartilage have been found as emboli in the lungs.

Amniotic fluid embolism is discussed elsewhere.

ADULT RESPIRATORY DISTRESS SYNDROME

Following severe lung injury, such as gross impact upon the thorax or blast injury from explosion, or from aspiration of gastric contents, infections, toxins, systemic shock, irritant gases, near-drowning and many other causes, the lung epithelium may suffer 'diffuse alveolar damage'. Clinically the victim may suffer marked dyspnoea and progressive respiratory failure, becoming hypoxaemic. Pathologically the lungs show a stiff oedema that progresses to a rigid, infiltrated lung if survival is long enough. At autopsy the lungs are hard and retain their shape after removal, having a 'dry-oedema' appearance, being almost double in weight in some instances.

Histologically the initial changes are shedding of type I pneumocytes with intra-alveolar exudates, the formation of hyaline membrane and patchy alveolar haemorrhage. This destructive phase is then replaced after a few days with a proliferative stage, when type II pneumocytes begin to fill the alveoli and a mononuclear response infiltrates the interstitial areas. The alveolar proliferation organizes, if survival continues, and eventual pulmonary fibrosis may seriously incapacitate the half who survive. A typical progression is seen in paraquat poisoning, though here there are virtually no long-term survivors.

A condition that is similar to the appearances of adult respiratory distress syndrome is the so-called 'respirator lung', which develops when a patient dies after an appreciable period of mechanical ventilation. It may appear within a few days, but usually supervenes after many days or weeks on a ventilator. The gross appearances are of a stiff, rigid lung, which, though heavy, does not usually appear obviously oedematous. Microscopically, proteinaceous fluid and a mixture of proliferative cells may be seen in the alveoli.

RENAL FAILURE FOLLOWING TRAUMA

Known for many years, this is a common sequel to extensive muscle damage or to burns that affect considerable areas of skin, as well as from certain poisons. It was formerly ascribed most often to 'acute tubular necrosis', but recent experimental work has thrown some doubt upon this as an accurate clinicopathological entity. When muscle is crushed, severely torn or otherwise rendered ischaemic, where extensive burns are suffered, or where poisons, such as mercuric salts or carbon tetrachloride are given, destruction of the renal tubular epithelium may be seen.

Unfortunately for histological diagnosis, a similar change occurs during post-mortem autolysis. In burns and muscle damage, the tubules may also be blocked with brown casts of myoglobin and these two changes of distal tubular necrosis and casts were thought to cause the profound oliguria or anuria often associated with trauma and burns. In biopsy as opposed to autopsy material, however, the tubular damage has been found to be minimal and the casts may be a sequel to reduced filtration rather than to tubular damage, so the validity of 'acute tubular necrosis' as an explanation of renal failure following trauma has been questioned. The true mechanism is still obscure, but may well involve the juxtaglomerular apparatus and the renin–angiotensin system, as well as disseminated intravascular coagulation effects on the glomeruli.

DISSEMINATED INTRAVASCULAR COAGULATION

The importance and frequency of this condition has been increasingly recognized in recent years, as it may follow a whole range of traumatic, infective and other acute events. Widely known as 'DIC', it has a number of other names indicating that it is a consumption coagulopathy associated with the blood clotting mechanism.

In DIC there is an abnormal activation of the coagulation process within the blood vessels caused by a wide variety of factors related to the blood itself, the vessel walls and to blood flow. Damaged tissue from trauma and burns can trigger thromboplastin-initiated coagulation: entry of tissue cell elements, especially from erythrocytes, brain and placenta are particularly potent. Particulate matter such as micro-organisms or microemboli of all types (including fat and air emboli, especially those from decompression) can precipitate coagulation via factor XII. Vascular endothelial damage and stasis of blood flow can have a similar effect.

Whatever the causes – and they are extremely complex – fibrinogen is consumed and fibrin precipitated in vessels, leading to both vascular obstructive effects and to a haemorrhagic diathesis from depletion of the coagulation system. Platelets are also consumed, adhering to the fibrin thrombi. Fibrinolysis is activated and there is a dynamic contest between intravascular coagulation and its removal.

After death there can be post-mortem fibrinolysis (Mole 1948), which lessens the ease with which fibrin deposits can be detected: staining techniques are also an imperfect method of visualizing the fibrin, so that a careful search must be made in autopsy histology for fibrin remnants. Lungs, kidney, liver and adrenals are the most likely organs to yield positive results.

Microvascular obstruction, leading sometimes to frank infarction as well as reduced function, together with bleeding, form the major dangers of DIC in a forensic context.

AIR EMBOLISM

Most examples of air embolism have a medico-legal significance as the entry of air into the circulation usually comes about as a result of trauma, sometimes surgical or therapeutic, from barotrauma or from criminal intervention.

Air embolism consists of an interruption of the circulatory system by bubbles of air (or other gas) that gain access to the circulation, usually through the venous side. It is an ‘airlock’, familiar to plumbers and owners of diesel engines, where the normal flow of liquid through tubes is wholly or partially blocked by air.

In the animal body the major disability is in the heart, as air is compressible and the contractions of the heart fail to move on the bolus of gas, being designed to pump an incompressible liquid. The air must enter on the venous side to be sucked towards the heart, causing pulmonary air embolism. The air usually remains in the right side of the heart, pulmonary trunk and arteries, and in the pulmonary vessels, rarely emerging on the pulmonary vein side. Death is usually immediate, but can be delayed by up to about 2 hours.

In the surgical context, aspiration of air into neck veins may occur while operating on the head or neck (especially thyroid and neurosurgical operations) with the patient in a sitting position. When the atria are below any breach in a vein, there is a suction effect that can draw in air; this can also happen in suicidal or homicidal cut throat. Refilling of a therapeutic pneumothorax has also led to fatal air embolism, either because the lung is punctured or an adhesion has torn the visceral pleura. In either case air under pressure may enter an exposed vein.

Some accidents have arisen during transfusion or infusion, and may form the basis for a medical negligence action. Now that flexible, collapsible fluid or blood containers are widely used the danger is less, but where rigid bottles are still used, the need for a vent tube may allow air to enter the connecting tubing when a bottle is allowed to empty completely. This in itself is innocuous, but if a fresh bottle is then connected, the new flow will drive all the air in the tubing into the vein.

Even more dangerous is the practice of connecting pressurized air or oxygen to the vent in order to hasten the transfusion speed: if the bottle is allowed to empty, gas under pressure enters the vein.

Arterial air embolism is rare, but can occur in lacerations of the lungs, refilling of an artificial pneumothorax or in some forms of barotrauma where the lung is ruptured in a diver who ascends too rapidly from a great depth. The ‘bends’ are also a type of gas embolism, in which dissolved nitrogen appears in gaseous form in the blood. This is caused by a sudden release of pressure on the return of a diver to atmospheric conditions after being supplied with air at high pressure. Death can be the result of air locks in the cerebral vessels or of ventricular fibrillation from coronary air embolism (Moore and Braselton 1940).

Criminal abortion accounted for many deaths from air embolism in former years (and still does in some parts of the world), from the insufflation of the uterus by a Higginson syringe (Chapter 19). Though therapeutic abortion by suction aspiration of the uterine contents is an extremely safe procedure, several somewhat inexplicable deaths have occurred from air embolism. The mechanism is obscure but may have been caused by muscular rebound of the uterus sucking air into the cervix. Some homicides, including ‘mercy killings’ committed by doctors, have been caused by deliberate injection of air into peripheral veins. The volume of air needed to cause fatal embolism has been hotly debated for years, but no real consensus has emerged, estimates varying from 10 to 480 ml (Polson 1963). If the volume of the right side of the heart is accepted as the minimum space that has to be filled, about 100 ml would appear to be a reasonable volume. In the rare event of air gaining access to the arterial system, presumably much less would be required to be effective; it would have to be introduced into a carotid artery to be of much danger, as this is the only way it could gain access to the cerebral circulation. To reach the coronary vessels – always mentioned in books, but virtually never seen – the blood would have to enter the pulmonary veins to reach the root of the aorta via the left side of the heart. Virtually all of the few cases of arterial air embolism have arisen in relation to dysbarism, where bubbles have either been generated within the vessels by decompression, or have entered the arterial system in the lungs from tears in the lung tissue.

Certainly air injected into a limb artery would do no harm at all, especially as most of the gas is likely to be absorbed very rapidly by the tissues. Thus the ingenious plot in Dorothy L Sayer's novel, *Unnatural Death*, where 'a hypodermic of air was injected into an artery' would have failed on two counts: site and volume!

The autopsy in suspected air embolism

When the circumstances indicate the possibility of fatal air embolism, special precautions must be taken over the autopsy. A pre-autopsy chest radiograph must be taken, as this is by far the best way of demonstrating air in sufficient quantities to be fatal. A chest radiograph is also essential in any kind of barotrauma as it may also indicate a pneumothorax, a lesion so often the cause of air embolism.

Almost the only mechanism of death is 'pump failure' of the right side of the heart. Air fills the great veins, right atrium and right ventricle, causing a froth that cannot be pumped on by the heart in systole because air is compressible. It is unlikely that air will penetrate the pulmonary capillaries in any quantity, unless some vascular shunts are present, so froth is unlikely to be seen in the left side of the heart, except in dysbarism.

Following radiography – in place of it, as second-best – the body must be carefully inspected for any tissue swelling, especially in the upper thorax and neck region, where crepitant gas bubbles may form surgical emphysema from leakage from lung damage or pneumothorax, or both, in dysbarism.

The head should be dissected first, not to detect air bubbles in the cortical veins, as almost every textbook erroneously states, but to look for air in the cerebral arteries. Descriptions and photographs of air segments in the cerebral veins are part of the mythology of forensic pathology, handed on uncritically from one book and one author to another. There is no way in which air bubbles can reach the pial veins on the brain surface. They cannot get there via the venous system, as there is no way in which they could struggle against the flow in the jugular veins, pass through the complex arrangement of intracranial venous sinuses retrograde to the circulation and dispose themselves over the cortical surface. Neither can they reach the same veins by penetrating the capillary bed of the brain, in the rare instances of arterial air embolism. As was demonstrated almost 30 years ago, these bubbles are artefacts and can be seen in many routine autopsies where there can be no question of air embolism.

The basal arteries should be inspected for air, however, which can reach them during episodes of dysbarism where air gains access to the arterial system in the lungs during decompression. The calvarium is removed gently and the dura opened. The brain is carefully lifted and small artery forceps clamped on the intracranial part of both internal carotid arteries and vertebral arteries. The vessels are then cut below these before the brain is removed from the skull in the usual manner. The whole pluck can then be submerged in water and the ends of the vessels watched for escaping bubbles when the clamps are removed.

The thorax is opened in the fashion appropriate for the detection of a pneumothorax, with puncture of an intercostal muscle beneath a pool of water supported by the reflected skin flap. This is done on each side, remembering that a positive result can only be expected in a **tension** pneumothorax.

The abdomen should next be examined, especially where air may have gained access through the uterus. The intestines should be gently displaced and the mesenteric veins examined for air bubbles. The inferior vena cava, the common iliac veins and the various pelvic veins should be scrutinized, and, if necessary, opened under water by pouring water into the opened abdominal cavity.

The sternum and costal cartilages are then removed carefully, preferably keeping the manubrium and upper ribs intact at this stage to avoid damage to the great vessels in the thoracic inlet. The superior vena cava should be inspected for bubbles. The pericardium is opened and the right and left ventricles punctured under water.

Bajanowski *et al.* (1998, 1999) consider that an aspirometer has to be used for the detection, measurement and storage of gas originating from the heart ventricles. It should be filled completely with distilled water containing two drops of Tween 80 to reduce the surface tension of the water to prevent adherence of small air bubbles to the wall of the aspirometer. Subsequently the gas should be analysed by gas chromatography and the results assessed according to the criteria defined by Pierucci and Gherson (1968, 1969) before the diagnosis 'air embolism' is justified.

If air embolism substantial enough to have caused death is present, frothy blood will be quite evident oozing from



FIGURE 13.5 *An aspirometer should be used to recover air from the heart ventricles for subsequent analysis by gas chromatography.*



FIGURE 13.6 *Leucocyte and platelet accumulation around an empty space, 'air bubble' in blood, considered by some authors as evidence of venous air embolism. (Reproduced by kind permission of Professor E Lignitz.)*

the ventricular lumen, almost invariably the right. If this is apparent, however, it will almost certainly already have been seen on the pre-autopsy radiograph.

If there has been a considerable delay between death and autopsy, the air can dissipate, presumably dissolving into the tissues. Any degree of decomposition of the body negates a diagnosis of air embolism, because of the production of gases of putrefaction.

SUBENDOCARDIAL HAEMORRHAGE

A striking feature of many forensic autopsies, especially on victims of severe trauma, is the presence of well-marked haemorrhage under the endocardium of the left ventricle. This is often so striking as to provide an indication of some catastrophic event shortly before death.

Though the haemorrhages have been described since the last century, they were specifically studied in the 1930s by Sheehan in cases of abortion and acute haemorrhage associated with pregnancy; they were formerly known as 'Sheehan's haemorrhages'.

The lesions are seen in the left ventricle, on the interventricular septum, and on the opposing papillary muscles and adjacent columnae carneae of the free wall of the ventricle. The haemorrhages are flame-shaped and confluent, not petechial, and tend to occur in one continuous sheet rather than patches. The bleeding is in a thin subendocardial layer, but when severe may actually raise the endocardium into a flat blister that can be palpable on the smooth septum. The mechanism of production is obscure, but they are commonly seen in the following circumstances:

- After sudden, profound hypotension, either from severe blood loss or from 'shock' in the widest sense.
- After intracranial damage, from head injuries, cerebral oedema, surgical craniotomy or large intracranial tumours. Sudden intracranial decompression also seems to be associated with subendocardial bleeding.
- Obstetric catastrophes seem particularly prone to produce these haemorrhages, as found by Sheehan. Death from ante-partum or post-partum haemorrhage, ruptured ectopic gestation, abortions of various types and ruptured uterus often reveal these lesions.
- Various forms of poisoning, especially acute heavy-metal toxicity, particularly arsenic. The most profound subendocardial haemorrhages ever seen by the author (BK) were in a massive suicidal poisoning with arsenious oxide: the endocardium was raised into a large blood blister on the interventricular septum.

The haemorrhages can appear extremely rapidly, within a few heart beats. The author (BK) has seen well-marked lesions in a heart that was avulsed from its base during the crash of a military aircraft, obviously causing virtually instantaneous death. The common factor seems to be sudden hypotension and it has been suggested that, if the intraventricular pressure drops precipitously, the existing blood pressure in the coronary system is then unsupported across the endocardium by an equal pressure within the ventricular lumen, so that rupture of the superficial vessels occurs. There are flaws in this theory, one being the common incidence in intracranial lesions. Experimental work in goats has shown that prior vagotomy prevents the occurrence of subendocardial haemorrhages, suggesting that the phenomenon is mediated by the autonomic nervous system. To support this hypothesis, they are known to be part of Virchow's triad of 'pulmonary oedema, gastric erosions and subendocardial haemorrhage' seen in head injuries and cases of raised intracranial pressure.

SUDDEN DEATH FROM SUPRARENAL HAEMORRHAGE

Though not common, haemorrhage into the adrenal glands is a well-recognized terminal event, usually after some trauma to the body not related to direct injury to the suprarenal vessels themselves.

Originally these haemorrhages were thought to be confined to meningococcal septicaemia in children, the lesion being called the 'Waterhouse–Friderichsen syndrome'. It is now recognized that adrenal haemorrhage is part of a general response to stress, of which meningococcal infection is only one of a wide range.

In a recent 5-year period, the author (BK) found 16 cases of 'adrenal apoplexy' (to give it its old name) in the autopsy records of a forensic pathology service that performed 4890 autopsies in that period, giving an incidence of about 0.3 per cent.

Of these 16 cases, more than half (9) were bilateral. There were more male than female subjects, probably because of the greater amount of trauma in men. Three were infants, all with meningococcal infections.

None of the adult cases was diagnosed or even suspected clinically. Most were traffic accidents, the remainder being post-operative, other trauma or poisoning, together with several cases of hypertension and chronic renal failure. The most frequent common denominator was trauma, whether that trauma was direct injury or surgical trauma. The sudden collapse and rapid death usually occurred a few days after the trauma, varying from 2 to 21 days.

At autopsy one or both of the adrenal glands are found to be swollen, sometimes to the size of a large walnut (3–5 cm) the cortex being tightly stretched around a large haematoma occupying the medulla. The haemorrhage is usually dark red and fairly fresh, though occasionally an area of brown bleeding indicates a previous episode.

The late Professor Hugh Johnson, of St Thomas' Hospital, London, collected between 150 and 200 autopsy cases of suprarenal haemorrhage (unpublished) and considered that they fell into six main groups:

- Trauma of all types. Johnson was of the opinion that the predominance of right-sided gland haemorrhages was a result of the frequency of right-sided impacts on pedestrians in Britain because of the side of traffic flow.
- Perinatal, newborn or stillborn infants, especially when they were breech births or had fetal anoxia.
- Infancy and childhood, especially meningococcal and disseminated intravascular coagulation.
- Infective and post-operative septicaemia, often with Gram-negative organisms. Sometimes there was direct surgical trauma to the gland, as in gastric surgery.
- Tumour: haemorrhage into a secondary deposit or invasion of adrenal vasculature.
- Thrombosis of central vein with adrenal infarction.

REFERENCES AND FURTHER READING

Adams V, Guidi C. 2001. Venous air embolism in homicidal blunt impact head trauma. Case reports. *Am J Forensic Med Pathol* **22**:322–6.

Adkins RB, Foster JH, O'Saile D. 1962. Experimental study of the genesis of fat embolism. *Ann Surg* **156**:515–27.

Allardyce DB. 1971. The postmortem interval as a factor in fat embolism. *Arch Pathol* **92**:248–53.

Bajanowski T, West A, Brinkmann B. 1998. Proof of fatal air embolism. *Int J Legal Med* **111**:208–11.

Bajanowski T, Kohler H, DuChesne A, *et al.* 1999. Proof of air embolism after exhumation. *Int J Legal Med* **112**:2–7.

Bergentz SE. 1961. Studies on the genesis of post-traumatic fat embolism. *Acta Chir Scand* **282**:1–72.

Beyer A. 1979. Shock lung. *Br J Hosp Med* **21**:248–52.

Bonnell H, French SW. 1982. Fatal air embolus associated with pneumatosis cystoides intestinalis. *Am J Forensic Med Pathol* **3**:69–72.

Bowen DA, McKim Sycamore E. 1976. Traumatic air embolism. *Med Sci Law* **16**:56–8.

Buchanan D, Mason JK. 1982. Occurrence of pulmonary fat and bone marrow embolism. *Am J Forensic Med Pathol* **3**:73–8.

Bunai Y, Yoshimi N, Komoriya H, *et al.* 1988. An application of a quantitative analytical system for the grading of pulmonary fat embolisms. *Forensic Sci Int* **39**:263–9.

Butler BD, Hills BA. 1985. Transpulmonary passage of venous air emboli. *J Appl Physiol* **59**:543–7.

Cebelin MS, Hirsch CS. 1980. Human stress cardiomyopathy. Myocardial lesions in victims of homicidal assaults without internal injuries. *Hum Pathol* **11**:123–32.

Chau KY, Yuen ST, Wong MP. 1995. Seasonal variation in the necropsy incidence of pulmonary thromboembolism in Hong Kong. *J Clin Pathol* **48**:578–9.

Chau KY, Yuen ST, Wong MP. 1997. Clinicopathological pattern of pulmonary thromboembolism in chinese autopsy patients: comparison with caucasian series. *Pathology* **29**:263–6.

Dada MA, Loftus IA, Rutherfoord GS. 1993. Shotgun pellet embolism to the brain. *Am J Forensic Med Pathol* **14**:58–60.

Edland J. 1971. Post-traumatic fat embolism. In: Wecht C (ed.), *Legal medicine annual*. Appleton Century Crofts, New York.

Ellis HA, Watson AJ. 1968. Studies on the genesis of traumatic fat embolism in man. *Am J Pathol* **53**:245–51.

Erhen J, Nadvornik F. 1963. The quantitative demonstration of air embolism. *J Forensic Med* **10**:45–8.

Fineschi V, Centini F, Mazzeo E, *et al.* 1999. Adam (MDMA) and eve (MDEA) misuse: an immunohistochemical study on three fatal cases. *Forensic Sci Int* **104**:65–74.

Flute PT. 1970. Coagulation and fibrinolysis after injury. *J Clin Pathol Suppl R Coll Pathol* **4**:102–9.

Freiman DG. 1965. Frequency of pulmonary thromboembolism in man. *N Engl J Med* **24**:1278–82.

Gottlieb JD, Ericsson JA, Sweet RB. 1965. Venous air embolism: a review. *Anesth Analg* **44**:773–9.

Gresham GA, Kuzynski A, Rosborough D. 1971. Fatal fat embolism following replacement arthroplasty for transcenvical fractures of the femur. *Br Med J* **2**:617–18.

Guileyardo JM, Cooper RE, Porter BE, *et al.* 1992. Renal artery bullet embolism. *Am J Forensic Med Pathol* **13**:288–9.

Hamilton PJ, Stalker AL, Douglas AS. 1978. Disseminated intravascular coagulation: a review. *J Clin Pathol* **31**:609–19.

Hartveit F, Lystad H, Minken A. 1968. The pathology of venous air embolism. *Br J Exp Pathol* **49**:81–6.

Havig O. 1977. Deep vein thrombosis and pulmonary embolism. An autopsy study with multiple regression analysis of possible risk factors. *Acta Chir Scand Suppl* **478**:1–120.

Irniger W. 1962–3. Histological determination of the age of thromboses and embolisms. *Virchows Arch A Pathol Anat Histopathol* **236**:220–37.

Jackson CD, Gerendyke RM. 1965. Pulmonary and cerebral fat embolism after closed-chest cardiac massage. *Surg Gynecol Obstet* **120**:25–8.

Janssen W. 1967. [On the pathogenesis and forensic evaluation of brain hemorrhages following cerebral air embolism.] *Dtsch Z Gesamte Gerichtl Med* **61**:62–80.

Johnson HR. 1973. Delayed air embolism. *Forensic Sci* **2**:375–7.

Jörgensen L. 1964. Experimental platelet and coagulation thrombi. *Acta Pathol Microbiol Scand Sect A Pathol* **62**:189–223.

Kerner T, Fritz G, Unterberg A, *et al.* 2003. Pulmonary air embolism in severe head injury. *Resuscitation* **56**:111–15.

King P. 1970. Fat embolism syndrome. *Med J Aust* **2**:1190–1.

Knight B. 1966. Fatal pulmonary embolism: factors of forensic interest in 400 cases. *Med Sci Law* **6**:150–4.

Knight B. 1980. Sudden unexpected death from adrenal haemorrhage. *Forensic Sci Int* **16**:227–9.

Knight B, Zaini MR. 1980. Pulmonary embolism and venous thrombosis. A pattern of incidence and predisposing factors over 70 years. *Am J Forensic Med Pathol* **1**:227–32.

Knight L, Velentine EH. 1962. Spontaneous bilateral adrenal haemorrhage. *JAMA* **14**:1312.

Lau G. 1995. Pulmonary cartilage embolism: fact or artefact? *Am J Forensic Med Pathol* **16**:51–3.

Lehman EP, Moore RM. 1927. Fat embolism including experimental production without trauma. *Arch Surg* **14**:621–6.

Lequire VS. 1959. A study on the pathogenesis of fat embolism based on human necropsy material and animal experiments. *Am J Pathol* **35**:999–1003.

Levy V, Rao VJ. 1988. Survival time in gunshot and stab wound victims. *Am J Forensic Med Pathol* **9**:215–7.

Lignitz E, Lignitz G, Puschel K. 1995. [Lung embolism as the cause of death in legal medicine.] *Versicherungsmedizin* **47**:203–7.

Loehry CA. 1966. Pulmonary emboli in young adults. *Br Med J* **1**:1327–8.

Mackay DG. 1965. *Disseminated intravascular coagulation: an intermediary mechanism of disease.* Hoeber, New York.

Malhotra MS, Wright HC. 1960. Air embolism during decompression under water. *J Physiol* **151**:32–5.

Mason JK. 1968. Pulmonary fat and bone marrow embolism as an indication of ante-mortem violence. *Med Sci Law* **8**:200–6.

Melinek J, Livingston E, Cortina G, *et al.* 2002. Autopsy findings following gastric bypass surgery for morbid obesity. *Arch Pathol Lab Med* **126**:1091–5.

Mole RH. 1948. Fibrinolysin and the fluidity of the blood postmortem. *J Pathol Bacteriol* **60**:413–17.

Moore RM, Braselton CW. 1940. Injections of air and of carbon dioxide into a pulmonary vein. *Ann Surg* **112**:212–18.

Morell MT, Dunhill MS. 1968. The postmortem incidence of pulmonary embolism in a hospital population. *Br J Surg* **55**:5–10.

Nordstrom M, Lindblad B. 1998. Autopsy-verified venous thromboembolism within a defined urban population – the city of Malmo, Sweden. *APMIS* **106**:378–84.

Pierucci G. 1985. [Post-mortem diagnosis of gas embolism.] *Pathologica* **77**:145–55.

Pierucci G, Gherson G. 1968. [Experimental study on gas embolism with special reference to the differentiation between embolic gas and putrefaction gas.] *Zacchia* **4**:347–73.

Pierucci G, Gherson G. 1969. [Further contribution to the chemical diagnosis of gas embolism. The demonstration of hydrogen as an expression of 'putrefactive component'.] *Zacchia* **5**:595–603.

Polson CJ. 1963. *Essentials of forensic medicine*. Pergamon Press, Oxford.

Rappaport H, Raum M, Horrell JB. 1951. Bone marrow embolism. *Am J Pathol* **27**:407–43.

Robertson H. 1938. A clinical study of pulmonary embolism. *Am J Surg* **16**:3–21.

Rouse DA, Hargrove R. 1992. An unusual case of gas embolism. *Am J Forensic Med Pathol* **13**:268–70.

Sandritter W, Staeudinger M, Drexler H. 1980. Autopsy and clinical diagnosis. *Pathol Res Pract* **168**:107–14.

Sanz P, Reig R, Borras L, *et al.* 1988. Disseminated intravascular coagulation and mesenteric venous thrombosis in fatal amanita poisoning. *Hum Toxicol* 7:199–201.

Sevitt S. 1962. *Fat embolism*. Butterworth, London.

Sevitt S. 1970. Thrombosis and embolism after injury. *J Clin Pathol* **23**:86–90.

Sevitt S. 1973. Coronary thrombosis following injury and burns. *Med Sci Law* **13**:185–91.

Sevitt S, Gallagher N. 1961. Venous thrombosis and pulmonary embolism: a clinico-pathological study in injured and burned patients. *Br J Surg* **48**:475–81.

Shapiro HA. 1965. Death from delayed air embolism. *J Forensic Med* **12**:3–7.

Shapiro HA, Robertson JK. 1962. The significance of blood in the pleural cavity observed after death. *J Forensic Med* **9**:5–8.

Simpson JG, Stalker AC. 1973. Disseminated intravascular coagulation. In: Douglas (ed.), *Clinics in haematology*, vol. 2. W. B. Saunders, Philadelphia.

Simpson K. 1959. Fat embolism. *J Forensic Med* **6**:19–22.

Slater DN. 1988. Bone marrow emboli [letter]. *Am J Forensic Med Pathol* **9**:357–8.

Stalker AC. 1978. Issue: disseminated intravascular coagulation. In: Mason JK (ed.), *Pathology of violent injury*. Edward Arnold, London.

Stamatakis JD, Kakkar VV, Lawrence D, *et al.* 1978. The origin of thrombi in the deep veins of the lower limb: a venographic study. *Br J Surg* **65**:449–51.

Start RD, Cross SS. 1999. Acp. Best practice no 155. Pathological investigation of deaths following surgery, anaesthesia, and medical procedures. *J Clin Pathol* **52**:640–52.

Stein PD, Henry JW. 1995. Prevalence of acute pulmonary embolism among patients in a general hospital and at autopsy. *Chest* **108**:978–81.

Suzuki T, Ikeda N, Umetsu K, *et al.* 1984. Pulmonary fat embolism as an ante-mortem reaction in traumatic immediate death. *Med Sci Law* **24**:175–8.

Suzuki T, Ikeda N, Umetsu K. 1987. Pulmonary bone marrow embolic phenomena. Antemortem reactions in traumatic immediate death. *Am J Forensic Med Pathol* **8**:283–6.

Thali MJ, Yen K, Plattner T, *et al.* 2002. Charred body: virtual autopsy with multi-slice computed tomography and magnetic resonance imaging. *J Forensic Sci* **47**:1326–31.

Timperley WR. 1978. Disseminated intravascular coagulation in forensic pathology. *Med Sci Law* **18**:108–16.

van Ieperen L. 1985. Gas embolism as a cause of death. *Am J Forensic Med Pathol* **6**:240–3.

Voigt J. 1966. Adrenal lesions in medico-legal autopsies. *J Forensic Med* **13**:3–15.

Williams G. 1956. Experimental studies in arterial ligation. *J Pathol Bacteriol* **72**:569–74.

Wilson D, Cooke EA, McNally MA, *et al.* 2001. Changes in coagulability as measured by thrombelastography following surgery for proximal femoral fracture. *Injury* **32**:765–70.

Zaini MRS. 1981. *Medicolegal aspects of pulmonary embolism.* Medical Faculty, University of Wales, Cardiff.

Zaitoun AM, Fernandez C. 1998. The value of histological examination in the audit of hospital autopsies: a quantitative approach. *Pathology* **30**:100–4.

CHAPTER 14

Suffocation and ‘asphyxia’

- The nature of ‘asphyxia’ 352
- Mechanical ‘asphyxia’ 353
- The classic signs of ‘asphyxia’ 353
- Suffocation 357
- Smothering 358
- Choking 361
- Traumatic ‘asphyxia’ 363
- Postural ‘asphyxia’ 365
- References and further reading 365

Though traditionally every textbook of forensic medicine has a chapter entitled ‘Asphyxia’, it is a partial misnomer, as many of the conditions described under this heading are not truly asphyxial in nature. It is difficult to find a succinct alternative, however, unless each subcondition is described individually – and some deaths have a mixed aetiology. The conventional title is therefore retained in this book, though it is emphasized that ‘asphyxia’ is both inappropriate and inaccurate when applied to many of the mechanisms of death formerly ascribed to this cause.

THE NATURE OF ‘ASPHYXIA’

Common usage has led to the term ‘asphyxia’ being equated with ‘lack of oxygen’, though etymologically the word means ‘absence of pulsation’. Interestingly – if fortuitously – this original sense is sometimes more accurate in certain deaths associated with pressure on the neck, where cardiac arrest – certainly a prime reason for absence of pulsation – is the fatal mechanism, rather than hypoxia.

Reverting to the usual meaning of asphyxia, a whole series of disturbances can lead to lack of oxygen. The basic purpose of respiration is to convey atmospheric oxygen to the peripheral tissue cells. Anything that interferes with oxygen transfer can be called ‘asphyxia’, though other terms such as ‘hypoxia’ or ‘anoxia’ are more accurate, and should be preferred. The following conditions may legitimately be considered to be defects in the chain of respiration and hence are examples of asphyxia:

- Absence or reduction of oxygen tension in the external atmosphere, such as reduced barometric pressure or replacement of oxygen by an inert gas, such as nitrogen or carbon dioxide.
- Obstruction of the external respiratory orifices, as in smothering or gagging.
- Blockage of the internal respiratory passages, at either pharyngeal, laryngeal, tracheal or bronchial level.
- Restriction of the respiratory movements of the thorax, preventing the inspiration of air through patent respiratory passages, as in the so-called ‘traumatic asphyxia’ or in paralysis from brainstem or cord damage, or the use of curare-like drugs.
- Disease of the lungs that prevents or reduces gaseous interchange. Extensive pneumonia, pulmonary oedema, adult respiratory distress syndrome, diffuse fibrosis and many other conditions may lead to hypoxia, but these are rarely of forensic concern.
- Reduction in cardiac function leading to impairment of the circulation of oxygenated blood may be considered as a type of ‘asphyxia’, sometimes called ‘stagnant anoxia’. Again, the condition is rarely relevant to forensic problems.
- A reduced ability of the blood to transport oxygen can also be thought to be asphyxial in nature, such as severe anaemias and the replacement of the oxygen-combining power of haemoglobin by carbon monoxide.
- Finally, an inability of the peripheral tissue cells to utilize the oxygen delivered to them by the bloodstream is seen in conditions such as cyanide poisoning, where the cytochrome-oxidase enzyme systems are inactivated.

Several schemes of classification of asphyxia have been devised, such as those of McIntyre (1969) and Shapiro (1988).

MECHANICAL 'ASPHYXIA'

The usual relevance of asphyxia in a forensic context is in mechanical asphyxia, rather than some of the internal conditions mentioned above, which are more likely to arise as a result of natural disease or toxic conditions.

The normal oxygen content of blood varies according to the age and health of the subject. Young to middle-aged adults have almost complete saturation of their arterial blood with oxygen, at a level of 90–100 mmHg (12–13.5 kPa), whilst persons over 60 may drop to between 60 and 85 mmHg (8–10 kPa). These normal values in the younger group may be contrasted with those sufferers from mild hypoxia of about 60 mmHg (8 kPa), and those in severe to fatal hypoxia when oxygen tension falls to between 40 and 20 mmHg (5–3 kPa).

Unfortunately for pathologists, post-mortem analysis of oxygen levels in the blood is of no value in the retrospective diagnosis of hypoxia, as changes soon after death rapidly distort the distribution of gases and make the results meaningless.

Definition of terms

A number of different names have been used to describe the various types of mechanical 'asphyxia', some of which are confusing or inexact:

- **Suffocation** is a general term used to indicate death from deprivation of oxygen, either from lack of the gas in the breathable environment or from obstruction of the external air passages.
- **Smothering** is more specific, in that it indicates blockage of the external air passages, usually by a hand or soft fabric. A variety of suffocation may be called **gagging** where fabric or adhesive tape occludes the mouth to prevent speaking or shouting. While the nasal passages remain patent, air can enter, but later blockage by mucus or oedema may lead to death.
- **Choking** refers to blockage of the upper airways by some foreign body, but is also used for manual strangulation.
- **Throttling** refers to strangulation, usually by hand, the word rarely being applied to ligature strangulation.
- **Strangulation** is the most specific term, indicating the use either of the hands or a ligature as a means of applying external pressure to the neck. **Garrotting** has been used for ligature strangulation, but more accurately refers only to a Spanish method of judicial execution. Other methods exist in various parts of the world, such as the Indian technique of pressing a flexible stick or 'lathi' across the front of the neck.
- **Mugging** originally meant the application of pressure to the neck by means of an arm crooked around from the rear, but more recent American usage has widened the term to mean any kind of robbery with violence. More recently still the **arm-lock** has been used as means of restraint by law enforcement officers, sometimes with fatal results.

As an aside, in some deaths during arrest, usually where a violent struggle occurs between several police officers and a drunken or drugged offender, the death of the latter occurs where no neck or chest pressure can be implicated. Though the mechanism is obscure and impossible to demonstrate objectively at autopsy, it has been provisionally ascribed to a catecholamine-induced cardiac arrhythmia from an exaggerated adrenal response.

As most of these victims are given energetic cardiopulmonary resuscitation, any markers of this catecholamine effect, such as contraction-band necrosis in the myocardium, cannot be differentiated from resuscitative artefacts.

THE CLASSIC SIGNS OF 'ASPHYXIA'

For many years the autopsy diagnosis of an asphyxial death was made by reference to a set of findings that have come to be known as the 'classic signs of asphyxia'. Unfortunately, it is now quite clear that most of these signs are so non-specific that little reliance can be placed on them in the absence of other confirmatory evidence. They are scathingly referred to by Lester Adelson (1974) as the 'obsolete diagnostic quintet'.

In many cases of undoubted fatal hypoxia these signs are absent and, conversely, they are often present in some degree in conditions that can be shown to be non-hypoxic in origin. The major difficulty for the pathologist is that 'asphyxia' cannot reliably be equated with 'hypoxia'. There are no truly distinctive autopsy signs of pure hypoxia and most of the alleged criteria are caused by factors other than a lack of oxygen.

To confuse the issue further, some apparently hypoxic states lead to sudden or rapid death before there is time for oxygen lack to take effect, such as often happens when a victim enters a space devoid of oxygen, has the trachea suddenly blocked by food or has a plastic bag pulled over the head.

Each of the 'classic features' must be looked at in depth.

Petechial haemorrhages

These are small pin-point collections of blood lying in the skin, the sclera or conjunctivae and under thoracic serous membranes such as the pleura or pericardium. They vary in size from a tenth of a millimetre to about two millimetres. If larger than this, they are more accurately called 'ecchymoses'.

Petechiae are often known as 'Tardieu's spots', but this eponym should be restricted to those lying in the visceral pleura, where they were described by the Parisian Professor Ambroise Tardieu in 1866, in the bodies of infants who he claimed had been 'overlain'. A further common error is to attribute the petechiae to the rupture of **capillaries**, whereas they actually emanate from small venules – capillary bleeding would be invisible to the naked eye.

Petechiae are caused by an acute rise in venous pressure that in turn causes overdistension and rupture of thin-walled peripheral venules, especially in lax tissues, such as the eyelid, and in unsupported serous membranes, such as the pleura and epicardium. It is traditionally claimed that hypoxia of the vein wall is an added factor, but there is no experimental proof of this conjecture, which seems unlikely considering the rapid formation of these lesions when venous pressures rise; for example, petechiae can appear almost instantly after violent sneezing or coughing before any hypoxia is possible.

Petechiae are seen most often in the face and eyes of victims of compression of the neck or fixation of the chest. In the former, where strangulation by either hand or ligature has occurred, occlusion of the jugular veins prevents venous drainage from the head, whilst almost always allowing the arterial supply to continue via the more deeply placed and much less compressible carotid and vertebral arteries. There is a rapid rise in venous pressure in the head, leading to engorgement of the veins. The consequences are swelling of the tissues, both from an increase in intravascular volume and from rapid transudation of fluid into the tissues, followed by showers of petechial haemorrhages in unsupported areas, such as the skin of the upper eyelids, the forehead, the skin behind the ears, the circumoral skin, and the conjunctivae and sclera of the eye. The same venous engorgement often leads to frank bleeding from the nasal mucosa and the external auditory meatus.

In the internal tissues and organs, petechiae are most often seen on serous membranes in the thorax, where the presence of a body cavity leads to lack of support for the superficial venules and hence predisposes to rupture when venous pressure rises. They are almost never seen in the peritoneal serosa and it has been postulated that, in the chest, attempts at breathing against a closed airway may lead to a sudden extreme decrease in intrapleural pressure causing petechiae in the same way as suction on the skin can cause a shower of pin-point haemorrhages. As described by Tardieu, petechiae in the thorax are often seen on the visceral pleura, especially in the interlobar fissures and around the hilum.

Petechiae are also common on the surface of the heart, especially on the epicardium around the atrioventricular groove, particularly on the posterior surface, though these have been shown to appear or worsen as a post-mortem phenomenon. In infants and children, the thymus or thymic remnants may show numerous petechiae. It is claimed that in the sudden infant death syndrome these are confined to the cortex, whereas in other 'asphyxial' conditions they are scattered throughout the gland; this is doubtful.

Petechiae are rarely seen in the parietal pleura or the peritoneum except in haemorrhagic diatheses. In the brain, petechiae occur in the white matter and there may be larger patches of bleeding in the subarachnoid space where superficial vessels have ruptured because of acute venous engorgement. The same mechanism often produces profuse petechiae and ecchymoses under the scalp. In regard to the scalp, caution must be observed as numerous haemorrhages can be caused as a common autopsy artefact during the reflection of the scalp flaps.



FIGURE 14.1 *Petechial haemorrhages in the eye in manual strangulation. There are also some petechiae on the facial skin.*



FIGURE 14.2 *Scleral haemorrhages in manual strangulation. These are larger than the usual petechiae, but the latter are present inside the lower lid.*

Petechiae may also disappear with lengthening post-mortem interval. Betz *et al.* (1994) have shown that in putrefaction and freshwater immersion, conjunctival petechiae may vanish.

THE SIGNIFICANCE OF PETECHIAE

A number of factors cause difficulty in the interpretation of petechial haemorrhages. First, there is no doubt that both cutaneous and visceral petechiae, especially the latter, can both appear and enlarge as a post-mortem phenomenon. Gordon and Mansfield (1955) have shown that the presence and number of petechiae is a function of the post-mortem interval, in common with other haemorrhagic artefacts such as those found behind the larynx by Prinsloo and Gordon (1951).

Posture also has an effect on the appearance of haemorrhages. They are commonly seen, along with larger ecchymoses, on the front or back of corpses who have died from a variety of causes in which mechanical asphyxia is absent. They are often present in normal post-mortem hypostasis, especially where the mode of death was congestive as in many types of natural heart disease. Their appearance in the hypostatic areas is also time-related, the longer the post-mortem interval, the more likely – and more prominently – they are to occur.



FIGURE 14.3 *Subpleural petechial haemorrhage – the true 'Tardieu spots' – in manual strangulation. These are no longer considered to be specific for 'asphyxia' and a few petechiae can frequently be found in many autopsies unassociated with asphyxia.*

Where some abnormal posture is present – such as the deceased being slumped out of bed or otherwise found with the head lower than the body – marked congestion, cyanosis and petechial haemorrhages are common.

Occasionally the abnormal posture may have occurred during life, such as in overdose victims, drunks and senile persons, who have fallen into a position with the upper part of the body lowermost. This may embarrass respiration and contribute to death and the ante-mortem component may be difficult or impossible to distinguish from post-mortem accentuation of the congestive-petechial appearances.

Another problem in the autopsy interpretation of petechiae is that not all punctate lesions in the pleura are petechiae. Zaini and Knight (1982) showed that many such apparent petechiae were either intravascular venous pools, subpleural microbullae or pigment foci.

In summary, petechial haemorrhages are highly unreliable indicators of an asphyxial process, taking this to mean a hypoxic state. They are the result of venous engorgement, usually from mechanical obstruction of venous return to the heart – or in the thorax, from attempts to inspire against a blocked airway. Petechiae and ecchymoses are common non-specific autopsy findings and many are post-mortem in origin, especially in dependent positions. They



FIGURE 14.4 *Dense confluent skin haemorrhages in the face of an old lady who had slipped from her bed and was found with her head on the floor and her legs on the bed. The signs of this 'postural asphyxia' may well have been accentuated by post-mortem worsening of the hypostatic haemorrhages.*

may occur in many non-asphyxial states and, in the lungs, some petechiae can be found in the interlobar fissures and around the hilum in most routine autopsies.

Conversely, in some types of death where oxygen deprivation is to be expected (such as drowning, plastic-bag suffocation and entering an atmosphere devoid of oxygen), petechiae are seldom demonstrable.

The most significance must be placed on facial and ocular petechiae, because showers of pin-point haemorrhages in the eyelids, conjunctivae, sclera and facial skin require urgent explanation unless the body was face down or head down.

Congestion and oedema

The next 'classic' sign of asphyxia is congestion. This is even more non-specific than petechiae and once again is the result of obstructed venous return. When the neck is compressed, the face, lips and tongue become swollen and reddened. The true colour change of congestion is usually darkened by the onset of cyanosis. Internal organs also become congested and in strangulation this is most notable in the tongue, pharynx and larynx above the level of venous obstruction. In pressure on the chest, failure of respiratory movements cause an intense rise in venous pressure, accompanied by cyanosis.

Congestion is often associated with tissue swelling if the venous obstruction continues. The oedema is the result of rapid transudation through capillary and venule walls, again mainly a function of back pressure in the venous system. Hypoxia of the vascular endothelium is alleged to allow increased permeability, but generalized hypoxia from other causes does not produce the tissue swelling seen in strangulation.

Tissue fluid also escapes rapidly into the brain in strangulation that continues for even a few minutes, though here the well-known effect of hypoxia might be an added factor. Pulmonary oedema, causing excess fluid to enter the alveoli, is often found in hypoxic deaths. Here the mechanism is more obscure, but is probably a combination of hypoxia and raised pulmonary vessel pressure. In strangulation, froth may sometimes be so profuse as to emerge from the mouth and nostrils – yet in other throttlings, it may be absent. Pulmonary oedema is such a common and non-specific phenomenon in a whole range of fatal conditions that it has little diagnostic significance.

Cyanosis

The colour of blood depends upon the absolute quantity of oxyhaemoglobin and reduced haemoglobin present in the erythrocytes. The normal pink colour of well-oxygenated skin may change to purple or blue when oxygen is lacking – indeed, the word 'cyanosis' is derived from the Greek, meaning 'dark blue'. Cutaneous cyanosis, however, depends on the absolute amount of reduced haemoglobin, rather than the proportion of reduced haemoglobin to oxyhaemoglobin. It is not apparent in marked anaemia, even if the ratio of oxyhaemoglobin to reduced haemoglobin is low. There must be at least 5 g of reduced haemoglobin per 100 ml blood before cyanosis becomes evident, irrespective of the total amount of haemoglobin.

In the common forensic event of constriction of the neck, cyanosis almost invariably follows congestion of the face, as venous blood containing much reduced haemoglobin after perfusing the head and neck is dammed back and becomes more blue as the blood accumulates. If and when the airway becomes blocked, then impaired oxygenation in the lungs leads to a diminution in the oxygen content of arterial blood. This will lead to a darkening of all organs and tissues, and will accentuate the cyanosis of the face. This does not happen in the first phases of strangulation, however, and depends on complete or substantial occlusion of the airway, or restriction of the respiratory excursions of the chest.

Cyanosis produced during life may be partly or wholly overshadowed by hypostasis, which may be a deep purple or blue, and may be mistaken for true cyanosis – indeed, some pathologists refuse to use 'cyanosis' in respect of the dead, claiming that it cannot reflect the ante-mortem situation.

'Engorgement of the right heart and fluidity of the blood'

Descriptions of an abnormal fluidity of the blood seen at autopsy in asphyxial deaths are part of forensic mythology and can be dismissed with little discussion. Post-mortem clotting in the heart and venous system is a most erratic process, as is the eventual dissolution of those clots by the action of fibrinolytic enzymes (Mole 1948). It is irrelevant in the diagnosis of asphyxia.

Engorgement of the chambers of the right side of heart and the great veins is also a non-specific autopsy observation, useless as a marker of an asphyxial process. Any type of congestive death, including primary heart failure from many diseases, leads to terminal engorgement of the right ventricle and atrium as part of the generalized rise in venous and intracardiac pressure.

The autopsy diagnosis of 'asphyxia'

Thus there are no specific autopsy findings for 'asphyxia', taking this in its hypoxic sense. As stated earlier, the so-called ‘classic signs’ have been well described by Adelson (1974) as the ‘obsolete diagnostic quintet’. He goes on to observe that ‘the co-existence of these findings, in themselves, does not prove that death resulted from mechanical asphyxia. All these phenomena are non-specific and are in no way peculiar to this mode of death. Inasmuch as they are observed frequently in deaths arising from unquestioned natural disease, they are of no value in proving that death resulted from mechanical asphyxia’.

Other salutary cautions on the significance of ‘asphyxial signs’ may be found in the important publications of Gordon and Turner (1951), Camps and Hunt (1959), Shapiro (1953) and Swann and Brucer (1949).

It is impossible to make a post-mortem diagnosis of acute hypoxia by measuring the blood gases, as rapid changes after death – and indeed agonal changes – make analysis worthless. Only by a careful assessment of the history and circumstances of the death, exclusion of other causes and a cautious evaluation of the signs described above can any conclusion be reached. Most important of all is the finding of a cause for airway obstruction or other local trauma, such as prolonged pressure on the neck or chest, obstruction of the airways, postural causes or occlusion of the external respiratory orifices.

It cannot be emphasized too strongly that the mere finding of any of the non-specific features, such as congestion and petechiae, without firm circumstantial or preferably physical evidence of mechanical obstruction of respiration, is quite insufficient to warrant a speculative diagnosis of asphyxia. If such collateral evidence is not forthcoming, then the cause of death must be left undetermined.

Histological and biomechanical diagnosis of anoxia/‘asphyxia’

Many attempts have been made to find markers of hypoxia, anoxia and ‘asphyxia’ by means of laboratory techniques, including histology, histochemistry and various biochemical methods. Although many claims have been made for their usefulness, the fact that such tests are virtually never put forward in criminal or civil litigation makes it self-evident that they are not reliable.

This is hardly surprising, given the vague and contentious nature of the ‘asphyxial’ condition, where the mechanisms are diverse and even the nomenclature is unstandardized. If the target for research is narrowed down to severe hypoxia at a tissue or cellular level, then perhaps more success might be expected, by being able to demonstrate cellular damage by one or more of the great battery of techniques now available. However, even this limited objective is not yet attained with the degree of reliability required for legal purposes. The extensive strangling, drowning and gassing of legions of small animals may have produced many theses and papers, but has had no practical impact upon a long-standing problem in forensic pathology. Cell death, especially in neurones or myocytes, due to ischaemic/hypoxic damage is the most common focus for research, but the problem in a forensic context is that a considerable period of hypoxia – usually a minimum of many minutes or even hours – is needed before changes can be detected, even in experimental circumstances. In human autopsy material, the ever-present post-mortem and agonal changes interfere with the subtle early signs of hypoxic damage.

Histological changes in the lung and also chemical markers in blood or vitreous, such as hypoxanthine, have been claimed to indicate generalized hypoxia, but the application of such techniques in routine practice has not been fruitful.

SUFFOCATION

Although not a specific term, suffocation usually refers to a death caused by reduction of the oxygen concentration in the respired atmosphere, formerly called a ‘vitiated atmosphere’. It is less often used to include smothering or choking. Reduction of atmospheric oxygen may occur in a wide variety of situations. Decompression, such as cabin failure of aircraft at high altitudes, causes a dramatic fall in the partial pressure of oxygen and hence reduced penetration of the gas through the alveolar wall. Other factors, however, such as the direct effects of a partial vacuum and often mechanical trauma from the near-explosive situation may overshadow the hypoxic aspects.

More common is the reduction of oxygen in the atmosphere by physical replacement by other gases, or chemical changes such as combustion. In fires, the loss of respirable air may be a potent factor in causing death, though other complications, such as the presence of toxic gases such as carbon monoxide, cyanide and many other poisonous substances liberated by the burning of plastics, may cause death more quickly than pure hypoxia. Carbon dioxide, which though not itself poisonous, is irrespirable and may accumulate in fires, and in wells and shafts in limestone. In former years, vagrants sleeping for warmth near limekilns were sometimes suffocated by this heavy gas creeping over them.

Carbon dioxide is also the cause of deaths in a more modern agricultural setting – the grain silo. Here, many tons of grain are stored in gas-tight towers; the seed produces carbon dioxide that settles to the bottom of the tower. When a blockage occurs in the gravity discharge, farm workers may enter the tower to clear the obstruction. Although safety precautions demand venting before the men enter, some workers still suffer a sudden death on encountering an atmosphere rich in carbon dioxide.

A similar hazard exists in ships' tanks or other industrial metal chambers, in which oxygen is replaced by nitrogen. This happens because the damp steel walls become rusty and use up much of the contained oxygen in forming ferric oxides. In all these deaths associated with replacement of oxygen with an inert gas, rapid death is common before hypoxia can have had any physiological effect. For example, the author (BK) has dealt with two deaths in which seafarers entered closed ships' tanks and virtually fell dead off the entry ladder. The presumed mechanism, which was far too quick to be hypoxic, was considered to be some overstimulation of the chemoreceptor system, leading to a parasympathetic 'vasovagal' cardiac arrest.

Even where death was not witnessed as sudden, the 'classic signs' of asphyxia are almost always absent. In domestic circumstances, death may be seen where a heating apparatus has removed oxygen from the atmosphere in the absence of ventilation. Though oxides of carbon are usually formed, a kerosene or natural gas appliance may kill from pure hypoxia, especially where left burning all night in a small room where the occupants lie sleeping. The effect may be accentuated by the victims having blocked up cracks in the doors and windows to keep out draughts. An open wood or coal fire does not present the same hazard, as it requires a flue or chimney in order to burn. In all such deaths, carbon monoxide poisoning must first be excluded by blood analysis, as it is a common accompaniment to lack of oxygen, especially as the reduction in oxygen availability tends to make the heat source produce progressively more monoxide than dioxide during combustion.

In a different variety of hypoxic death, persons – especially children – may asphyxiate by being confined in a small airtight space. Examples include boxes and discarded refrigerators; the danger of the latter is so well known that in Britain it is illegal to dump a refrigerator in a place with public access, unless the self-locking handle is rendered inoperative.

In all such 'hypoxic' deaths (though some are patently due to vasovagal cardio-inhibitory mechanisms) it is very rare to find any petechial haemorrhages, as these are mainly the result of venous obstruction, which is absent in these circumstances. In the true hypoxic deaths, there may be congestion and cyanosis, though even these are often absent and the autopsy findings are essentially negative.

SMOTHERING

This term refers to death from mechanical occlusion of the mouth and nose, though sometimes 'suffocation' is used to include this class of death. The smothering agent is usually fabric, an impervious sheet or a hand, though occasionally (especially in industrial accidents) a mobile solid, such as sand, mud, grain or flour may be responsible for blocking the air passages. In the 1966 Aberfan disaster in South Wales, more than 140 victims – almost all children – were smothered when semi-liquid coal slurry from a collapsing mine tip swept over their school.

In smothering, death may occur either by the occluding substance pressing down upon the facial orifices, or by the passive weight of the head pressing the nose and mouth into the occlusion. Deliberate homicide is seen usually in the old, the debilitated and in infants. It is extremely difficult to prove homicide from objective findings.

In relation to infants, the matter will be further discussed in the chapter on sudden infant death syndrome, but it is essential to appreciate that the smothering of babies, whether intentional or accidental, is both rare and difficult to prove. The so-called 'classic signs' of asphyxia, for what they are worth, are rarely present in proven suffocation – and as intrathoracic petechiae are common in undoubted 'cot deaths', these signs cannot therefore be accepted in isolation as evidence of suffocation.

Pressure marks on the face can rarely be distinguished from post-mortem postural changes, where circumoral and circumnasal pallor is caused merely by passive pressure of the dependent head after death, preventing the gravitational hypostasis from entering these areas.

Even where the head is found supine, variation in colour is still common on the face, with contrasting white and pink patches, which usually change as the post-mortem interval lengthens. Unless there are bruises or abrasion on the cheeks, around the mouth, lips or lesions within the lips or mouth, it is dangerous to overinterpret mere colour variations from



FIGURE 14.5 *Smothering from a towel being tied over the face. Death was contributed to by head injuries, also inflicted by the aged husband, who died within a few hours of natural causes from hypertensive heart disease.*

alterations in the amount of blood in the facial capillary bed, which is almost always a post-mortem phenomenon.

Even a confession from the mother is not always reliable – cases are on record where a mother has falsely confessed to smothering her child to rationalize the inexplicable events of a true sudden infant death syndrome fatality.

A similar situation exists with the elderly, who may be victims of a 'mercy killing', often a euphemism for the exhaustion of patience of long-suffering caring relatives. A pillow placed over the face of a sleeping octogenarian leaves no signs, **unless a struggle develops**, when protracted attempts at respiration against obstruction may lead to congestion, cyanosis and sometimes facial and conjunctival petechiae.

'Overlaying' of infants

This alleged condition has an ancient pedigree, being mentioned in the Old Testament. In Chapter III of the First Book of Kings, Solomon has to adjudicate between two women who both claim the same child, as the other infant was 'overlain'. This event, some 3000 years ago, has been mentioned at intervals through history, as in Wales in AD 1188, when Giraldus Cambrensis records that the Lord punished a woman for preventing her husband joining the Third Crusade, by causing her infant son 'to be overlain in the night'.

When an infant was found dead in the morning in the maternal bed (as separate cots or cribs are a relatively modern invention), it was assumed that the mother had turned over onto the baby in her sleep and suffocated it. When infants began to be placed in cots, the deaths continued unabated and it seems obvious that most of these were victims of the sudden infant death syndrome (SIDS). Whether or not overlaying really exists is doubtful and seems incapable of proof, given that any infant found dead in bed with no physical signs at autopsy could, by definition, be a SIDS.

The recent marked decline in numbers of SIDS in Britain has coincided with a campaign to discourage mothers from putting their infants to sleep face down – but, as yet, no definite cause-and-effect relationship has been proved, so any consequent strengthening of the 'overlaying' hypothesis cannot be substantiated.

Plastic bag suffocation

Although an increasingly common form of suicide in Britain, plastic bag suffocation may also be homicidal or accidental. In all these types, the essential mechanism is that a hood of impervious substance, usually polythene or other plastic, is placed over the head down to neck level. The plastic is usually in the form of an open-ended bag, either transparent or a 'supermarket' shopping bag.

Although many suicides tie the open end of the bag around their neck with cord or a tie, this is not necessary for a fatal result. Indeed, even flat sheets of polythene have killed infants when placed on the face. The mechanism is not understood, as it was formerly but erroneously thought to be the result of the clinging effect of static electricity.

Plastic bag suffocation can be rapid and leave no signs whatsoever. In the author's (BK) series of accidental, suicidal and three homicidal deaths from plastic bags, not one had any petechial haemorrhages or, indeed, any signs of 'asphyxia' at all, the faces being pale and uncongested. In another case, a person was convicted of murder by plastic bag, yet was only arrested after a spontaneous confession 6 weeks after an autopsy that had revealed no signs whatsoever of an asphyxial cause of death. As with hypoxic atmospheres, it seems that the mechanism of death in plastic-bag facial occlusion is some rapid cardio-inhibitory mode, rather than a purely hypoxic process. This conclusion is strengthened by the causes mentioned above, where flat sheets of plastic, not bags, have killed infants by clinging to the face, which of necessity must have been rapid deaths.

At autopsy, unless the bag is still present, these cases can present great difficulty. In fact, as in the homicide mentioned above, unless a confession or other corroborative evidence is forthcoming, the pathologist may never even know that he has dealt with an occult suffocation. Where the bag



FIGURE 14.6 *Plastic bag suicide. The bag is sometimes tied around the neck, as in this case, but this is not necessary for a fatal outcome. The deaths are not asphyxial in the hypoxic sense; facial congestion and petechiae are almost always absent.*



FIGURE 14.7 *Plastic bag suicide, with an open bag placed loosely over the head. As usual there are no congestive petechial signs in the face.*

is still in place, a search must be made for other indications of suicide, such as drug analysis and futile injuries, such as slashed wrists. Masochistic activities, described later in this chapter, are sometimes, though not often, associated with plastic bag suffocation.

It is sometimes said that moisture seen inside the bag indicates that it was put on during life, the water being from respiration. It is rare for this to be an important issue, as placing a bag on a corpse’s head would seem excessively unusual; in any event, the test is invalid, as evaporation from the skin, nose and mouth can produce beads of moisture inside, whether the victim is dead or alive.

Autopsy signs of suffocation

Where smothering is suspected, local signs must be sought to try to substantiate pressure on the face. Such signs include bruising around the mouth, chin and nose, though these are rarely seen except in the more violent incidents. Pressure of the lips on the teeth or dentures may cause the buccal surfaces to be bruised or abraded, though lacerations are rare unless a blow has been administered. It must be remembered that as small infants and many old people have no teeth, these injuries are less likely. The dangers of accepting areas of facial pallor as ‘pressure marks’ when the face shows post-mortem hypostasis has already been mentioned. In the early stages of post-mortem discoloration of the skin, variable colouring may not be truly ‘hypostatic’ as mottling and patchy variation is common due to uneven vasodilatation after death. It takes some time for gravity to pull cutaneous blood down to lower levels.

Smothering may occur accidentally where a person who is incapacitated from one of a variety of causes lies face down on a surface that is impervious to air. Drunkenness, epilepsy, drug overdose, coma or stupor from natural disease, may lead to this. Though it has long been proved in connection with ‘cot death’ that woven fabrics of most types can still admit enough air to support quiet respiration when placed over the mouth and nose, fabric that becomes saturated with saliva, nasal mucus or vomit may form an impervious seal that ceases to allow the passage of air. The weight of the inert head also distorts the nose and presses the nostrils and mouth so hard against a mattress or pillow that this adds to the airway stenosis.

In these instances, congestion and cyanosis are common, but when the body is examined after death, some of these findings may be postural and hypostatic in nature. As always, however, it must be recognized that skin haemorrhages often appear post-mortem in dependent hypostasis.

Gagging

Smothering may also occur where a pad or gag is fixed over the face, as sometimes happens in robbery with violence. A householder, caretaker or night-watchman may be tied up and silenced by having a scarf, tie or other fabric tied around his face. At first this admits air, but when it becomes progressively soaked with saliva or mucus it may become impervious and lead to an asphyxial death, again usually without any petechiae in the face or eyes.

A similar situation arises when a gag is thrust into the mouth to silence a watchman or security officer. Another variant is adhesive tape applied over the mouth. Though the nasal airway may originally be quite patent, any later obstruction from oedema and mucus, or movement of the gag backwards into the nasopharynx, may cause an unforeseen death and turn a robbery charge into a homicide.

CHOKING

This term refers to blockage of the internal airways, usually between the pharynx and the bifurcation of the trachea. Death can be the result of pure hypoxia from occlusion of the airway, when all the attendant signs of congestion, cyanosis and perhaps petechiae may be present, usually where the victim struggles to breathe for an appreciable period. As described below, however, a large proportion of deaths occur suddenly before any possible hypoxic manifestations have time to take effect; these fatalities must be caused by neurogenic cardiac arrest, either purely neurogenic or accelerated by excess catecholamine release from the adrenaline response.

Causes of choking include the following.

Foreign bodies

Objects such as gags, dummies, small toys, table-tennis balls and a multiplicity of objects may be placed in the mouth and inhaled, usually by children and the mentally retarded. Occasionally adults will do the same, accidentally or by design; an example of the latter was a suicide seen by the author (BK), who died (without any asphyxial signs whatsoever) by pushing a closed pill-bottle into his pharynx.

Dentures and haemorrhage

False teeth (especially partial plates), extracted large teeth, blood clots, and frank haemorrhage following dental or ear, nose and throat operations such as tonsillectomy.

Acute obstructive lesions

Lesions of the glottis or larynx, such as the oedema of acute hypersensitivity (including insect stings), irritant vapours, inhalation of hot gas and acute infective conditions. The most dangerous of the latter is diphtheria or *Haemophilus influenzae* epiglottitis in children, which is a medical emergency sometimes requiring an immediate tracheostomy to relieve the airway obstruction. At autopsy, great thickening of the epiglottis and aryepiglottic folds by jelly-like oedema and inflammatory tissue will be found occluding the entrance to the larynx.



FIGURE 14.8 *Impaction of an extracted molar tooth in the larynx. Though now uncommon with modern dental and anaesthetic practices, it can still happen in less satisfactory circumstances. Blood clot from dental extraction, tonsillectomy, and other ear, nose and throat surgery can also block the airway.*

Food material

This is an important topic, as the cause of death 'aspiration of vomit' is used too often without real justification. Food



FIGURE 14.9 *Blockage of the larynx by a complete small orange in a mentally disturbed patient. The fruit had just been swallowed and was not regurgitated from the stomach. The face was pale and death was rapid, unaccompanied by symptoms of choking.*

may be drawn into the larynx either as it is being taken down from the mouth in the act of swallowing, or it may be regurgitated from the stomach.

- The first instance is rarely misinterpreted, as whole undigested food may be found in the air passages and there is usually a history of death taking place while eating. Though most commonly encountered in old persons and the mentally disturbed, it can occur in any age group. A notable example was the so-called 'café coronary' syndrome, which received considerable publicity in the USA some years ago. The most frequent victims were well-nourished businessmen, who died suddenly and unexpectedly during a meal with no signs of respiratory distress or any of the 'classic signs of asphyxia'. Initially thought to be coronary heart disease, autopsy revealed a bolus of food, often steak, lodged in the pharynx or larynx. In any choking on food, the bolus can be quite large, such as a whole pancake, a whole tangerine or masses of meat, fruit or vegetable. Senile persons in retirement homes and mentally retarded children in institutions are also vulnerable. In such fatalities, the history and mode of death gives no hint of a hypoxic mechanism. Many cases have been observed where the victim merely sits back in their chair, dead – the mode clearly being cardiac arrest, presumably from overactivity of the parasympathetic nervous system from stimulation of the laryngeal or pharyngeal mucosa – the so-called 'vasovagal reflex' or 'reflex cardiac inhibition'.



FIGURE 14.10 *Blockage of the larynx by meat. The victim was an old person with senile dementia who gulped food and who eventually died suddenly without asphyxial signs from reflex cardiac arrest.*

- The finding of gastric contents in the air passages is by no means as significant as the presence of freshly swallowed food. First, difficulties can arise in distinguishing gastric contents from fresh food material if digestion of the former has not proceeded far – which is not always a function of the time since the last meal, as any physical or psychological disturbance can retard or completely halt digestion. The history, if available, is a better guide, unless the material is obviously partly or wholly digested. In cases of doubt, the smell and acid reaction to pH indicators may be useful.

Gastric contents are commonly found in the larynx, trachea and bronchi at autopsy when no other evidence of aspiration exists, and when there is a clear and unconnected cause of death. Knight (1976) found that no less than a quarter of a series of 100 consecutive autopsies on both adults and children contained some gastric contents in the air passages, and Pullar (1984) observed that this was a low figure compared with his series. These findings were obviously caused in the great majority of cases by agonal or post-mortem spillage.

Gardner (1958) described experiments in which barium was placed in the stomachs of recently dead patients while still in bed in the hospital wards. When X-rays were taken after they were first moved to the mortuary and thence into the autopsy room, most had barium in their tracheobronchial tree, confirming that overspill was common as a post-mortem phenomenon. Even histological evidence of leucocyte clustering around foci of gastric contents deep in the bronchi was shown by Gardner to be an early post-mortem event, not a 'vital reaction'. Leucocyte migration in the skin up to 16 hours post-mortem was demonstrated by Ali (1986).

Almost the only definite evidence of aspiration of gastric contents is either reliable witnessed observation during life or the histological finding of an advanced 'vital reaction' with infection, necrosis and a definite inflammatory reaction. This is a relatively late change and cannot be seen where death occurred within a few hours of aspiration. Finding a few foci of leucocytes around a bronchiole is of no evidential use. There is therefore no reliable method of distinguishing agonal or even early post-mortem overspill from true vital aspiration, unless clinical or other witnessed evidence is available. In most instances, it is not justifiable for a pathologist to claim that death was caused by inhalation of stomach contents without such confirmatory evidence. Unfortunately, where other lesions are absent or unconvincing at autopsy, especially in the sudden infant death syndrome, many pathologists use the presence of gastric contents in the air-passages as the primary and often the only cause of death. This unwarranted assumption may have distressing consequences, both in the field of medical negligence, deaths in custody and especially in the sudden infant death syndrome, where mothers may be misled into thinking that some negligence on their part in failing to observe vomiting, may have caused the death.

The only circumstance where a firmer opinion may be held is in acute alcoholism, though even here certainty is usually elusive. Where an undoubtedly drunken person (usually with a blood alcohol of at least 150 mg/100 ml) is found dead with massive blockage of his air passages by copious gastric contents and where other causes of death can be excluded by autopsy, then it might be reasonable to assume that regurgitation may have killed him, especially if there is other evidence of external vomit on the clothing or immediate surroundings. However, it is not an autopsy diagnosis to be made lightly.

TRAUMATIC 'ASPHYXIA'

This condition is unfortunately misnamed, as the word 'traumatic' could equally be applied to hanging or strangulation. It is well recognized now, however, as meaning mechanical fixation of the chest, and is important both because of its frequency in accidents and because it provides the most extreme demonstration of the 'classic signs' of asphyxia.

Whereas other types of mechanical asphyxia may cause obstruction of air entry into the lungs, 'traumatic asphyxia' acts by restricting respiratory movements and thus prevents inspiration. It was termed 'traumatic' because gross mechanical forces are usually the reason for the fixation of the thoracic cage. Traumatic asphyxia occurs in two main conditions:

- The chest and usually the abdomen are compressed by an unyielding substance or object, so that chest expansion and diaphragmatic lowering are prevented. Burial in earth following the collapse of an excavation is a common cause and may kill workmen even if their heads remain above the fallen soil. Similarly, burial in grain, sand, coal or minerals, may have the same effect, and is usually encountered in industrial, marine or agricultural accidents. An avalanche in a silo, hopper, or other large-scale storage container may bury the worker up to neck level and, unless rescue is rapid, asphyxia will prove fatal. Similar restriction of chest movement may be caused by the victim being pinned under an overturned vehicle, or by falling timber or masonry. Many fatalities have occurred on farms, especially in hill country, by the toppling of a tractor, pinning the driver underneath. Protection in the form of a 'roll-bar' over the driving position or the provision of a rigid cab on a tractor was specifically designed to avoid such accidents.
- Crushing in crowds also leads to traumatic asphyxia, and this has caused some mass disasters, the largest probably being in Mecca. Most of the football-ground tragedies such as Bolton, Ibrox Park (1971), Lima (1964), Hillsborough (1989) and the Heisl Stadium in Belgium (1986) have been the result of crushing in crowds out of control. A similar mechanism led to 173 deaths in wartime London, when a panic on the stairs of Bethnal Green underground station, used as an air-raid shelter, caused the crowd to fall on those beneath.

Other forms of chest crushing arise from trapping between a vehicle and a wall, or between the buffers of two railway trucks.

Individual cases of traumatic asphyxia can occur when one person allows the whole weight of his body to fall upon another for a protracted period. This may happen in sexual intercourse, especially when one or both parties are incapacitated by drink or drugs.

Features of traumatic asphyxia

The appearances just mentioned are the hallmark of traumatic asphyxia and in no other condition, apart from postural dependency, is the degree of congestion and cyanosis so marked. When the chest is fixed, the face, neck and shoulders down to the thoracic inlet are grossly discoloured. Sometimes this colour is more red than purple. It can extend lower than the clavicles, Polson *et al.* (1985) being of the opinion that it often reaches down to the level of the third rib.

The conjunctivae are grossly congested and haemorrhagic. Rather than the petechiae seen in pressure on the neck, the conjunctivae and sclera may be so engorged with blood that the haemorrhagic tissue actually bulges out through the lids, completely obliterating the whites of the eyes. The face, lips and scalp may be swollen and congested, being dotted with petechiae and ecchymoses. There may be copious bleeding from the ears and nostrils. The whole picture is commonly an exaggeration of the appearances seen in slow death from manual strangulation, but local injury is absent and the signs extend down to or beyond the root of the neck. Where the compression has been caused by pinning under a solid object – as opposed to soil, sand or squeezing in a crowd – there may be local bruises and abrasions from the weight of a vehicle or heavy beam, but these are unrelated to the margin of the congestive–haemorrhagic zone.

Internally, the congestion is less marked than on the surface, but the lungs are usually dark and heavy and may well have subpleural petechial haermorrhages, the true ‘Tardieu spots’. The right heart and all the veins above the atria are markedly distended. There may be injuries to the chest wall from the trauma of the fixating object.

It is not clear why there should be such gross venous congestion, but it is usually explained rather unconvincingly by the failure of the pulmonary circulation consequent upon the cessation of the normal expansion and collapse of the pulmonary vasculature. Shapiro suggested that the pressure on the chest forces blood back into the great veins and, as the venous valves in the subclavian vessels prevent displacement into the arms, the extra volume is forced up the valveless jugular system to congest the head and neck.



FIGURE 14.12 *Gross conjunctival haemorrhages in traumatic asphyxia. The victim was a workman who was buried up to his chest in an avalanche of ash.*



FIGURE 14.11 *Traumatic asphyxia showing gross congestion of confluent petechial haemorrhages of the face and parts of the shoulders. The victim had been buried up to the axillae in an avalanche of iron ore in a factory bunker.*



FIGURE 14.13 *Traumatic asphyxia showing gross congestion of the face and red blood-tinged froth exuding from the nostrils and mouth. The victim had lost the control of the tractor he was driving, fell out of the cab and was compressed under the overturned vehicle.*

POSTURAL ASPHYXIA

Closely allied to traumatic asphyxia is the so-called 'postural asphyxia', whose description as a separate entity is quite recent. When a person remains in a certain position for an extended time, either due to being trapped, or being in a drunken or drugged state, there may be a mechanical impediment to adequate respiratory movements. In addition, the normal venous return to the heart may be impaired.

Such positions usually entail inversion, either of the whole body or of the upper half; the syndrome and the pathophysiology are described well by Madea (1993), though most forensic pathologists will have had experience of such situations from time to time.

Persons who have been trapped upside down or even only in a 'jack-knife' position, with the upper half of their body bent acutely downwards from the waist, may have such impairment of their respiratory movements that they become hypoxic and suffer marked disturbance of their circulatory system, especially the venous return to the heart.



FIGURE 14.14 *Postural asphyxia in an inebriated man attempting to climb through a fanlight window. His feet slipped from the sill and he was unable to make sufficient respiratory movements against the weight of his body. Note the marked difference in congestion and cyanotic lividity between his two hands, the face and lower hand being discoloured at least partly from post-mortem hypostasis.*

The author (BK) has seen two cases in which a victim has become stuck whilst trying to climb through the upper part of a window, one as a thief, the other in trying to get into a house without his key. Others have been seen where, in a state of drunkenness or other disability, they have slipped out of bed, so that their head and shoulders are on the floor, with the legs and pelvis still at a higher level on the bed. These may also suffer the same disturbance of respiratory movements, which when prolonged may lead to death.

Inversion may occur during torture: crucifixion has an element of postural asphyxia. In the case of inverted crucifixion, as in the death of St Peter, it would be the major factor, as inspiration would be impeded by the weight of abdominal viscera upon the diaphragm.

REFERENCES AND FURTHER READING

Adelman HC. 1988. Asphyxial deaths as a result of aspiration of dental appliances: a report of three cases. *J Forensic Sci* **33**:389–95.

Adelson L. 1974. *The pathology of homicide: a vade mecum for pathologist, prosecutor and defense counsel.* W. B. Saunders, Philadelphia.

Ali TT. 1986. *Post-mortem autolytic changes in skin and the role of white blood cells*. Medical Faculty, University of Leeds, Leeds.

Bell MD, Rao VJ, Wetli CV, *et al.* 1992. Positional asphyxiation in adults. A series of 30 cases from the Dade and Broward County Florida medical examiner offices from 1982 to 1990. *Am J Forensic Med Pathol* **13**:101–7.

Betz P, Penning R, Keil W. 1994. The detection of petechial haemorrhages of the conjunctivae in dependency on the postmortem interval. *Forensic Sci Int* **64**:61–7.

Brinkmann B, Püschel K. 1981. [Histomorphological alterations of lung after strangulation. A comparative experimental study (author's transl).] *Z Rechtsmed* **86**:175–94.

Brinkmann B, Püschel K, Bause HW, *et al.* 1981. [Death by obstructive asphyxia: the pathophysiology of respiration and hemodynamics (author's transl).] *Z Rechtsmed* **87**:103–16.

Brinkmann B, Fechner G, Püschel K. 1984. Identification of mechanical asphyxiation in cases of attempted masking of the homicide. *Forensic Sci Int* **26**:235–45.

Bullock MJ, Diniz D. 2000. Suffocation using plastic bags: a retrospective study of suicides in ontario, canada. *J Forensic Sci* **45**:608–13.

Bywaters EG, Beal D. 1941. Traumatic asphyxia. *Br Med J* **1**:427–8.

Camps FE, Hunt AC. 1959. Pressure on the neck. *J Forensic Med* **6**:116–36.

Collins KA. 2001. Death by overlaying and wedging: a 15-year retrospective study. *Am J Forensic Med Pathol* **22**:155–9.

Ely SF, Hirsch CS. 2000. Asphyxial deaths and petechiae: a review. *J Forensic Sci* **45**:1274–7.

Flobecker P, Ottosson J, Johansson L, *et al.* 1993. Accidental deaths from asphyxia. A 10-year retrospective study from Sweden. *Am J Forensic Med Pathol* **14**:74–9.

Fred HL, Chandler FW. 1960. Traumatic asphyxia. *Am J Med* **29**:508–11.

Gardiner EE, Newberry RC, Keng JY. 1990. Avian vitreous humor concentrations of inosine, hypoxanthine, xanthine, uric acid, uracil and uridine as influenced by age and sex: their relevance as indicators of ante-mortem hypoxia. *Forensic Sci Int* **47**:123–7.

Gardner AN. 1958. Aspiration of food and vomit. *Q J Med* **27**:227–42.

Gordon I. 1976. Medicolegal aspects of rapid deaths initiated by hypoxia and anoxia. In: Wecht C (ed.), *Legal medicine annual 1975*. Appleton Century Crofts, New York.

Gordon I, Mansfield RA. 1955. Subpleural, subpericardial and subendocardial haemorrhages: a study of their incidence at autopsy and of the spontaneous development after death of subepicardial petechiae. *J Forensic Med* **2**:31–50.

Gordon I, Turner R. 1951. Deaths from rapid anoxia. *Am Med Assoc Arch Pathol* **2**:316.

Haddix TL, Harruff RC, Reay DT, *et al.* 1996. Asphyxial suicides using plastic bags. *Am J Forensic Med Pathol* **17**:308–11.

Haugen RK. 1963. The café coronary. *JAMA* **186**:142–4.

Hood I, Ryan D, Spitz WU. 1988. Resuscitation and petechiae. *Am J Forensic Med Pathol* **9**:35–7.

Hunt AC, Camps FE. 1962. Plastic bag deaths. *Br Med J* **1**:378–9.

Keil W, Kondo T, Beer GM. 1998. Haemorrhages in the posterior cricoarytenoid muscles – an unspecific autopsy finding. *Forensic Sci Int* **95**:225–30.

Knight B. 1976. The significance of gastric contents in the air passages. *Forensic Sci Int* **14**:398–402.

Luke J. 1971. The pathology, diagnosis and certain medical-legal aspects of death by homicidal smothering in adults. In: Wecht C (ed.), *Legal medicine annual 1971*. Appleton Century Crofts, New York.

Madea B. 1993. Death in a head-down position. *Forensic Sci Int* **61**:119–32.

McIntyre J. 1969. The classification of asphyxia. *Br J Hosp Med* **2**:1113–15.

Mole RH. 1948. Fibrinolysin and the fluidity of the blood postmortem. *J Pathol Bacteriol* **60**:413–17.

Morita M, Tabata N. 1988. Studies on asphyxia: on the changes of the alveolar walls of rats in the hypoxic state. II. The hypoxic state produced by carbon dioxide and methane gases. *Forensic Sci Int* **39**:257–62.

Ogden RD, Wooten RH. 2002. Asphyxial suicide with helium and a plastic bag. *Am J Forensic Med Pathol* **23**:234–7.

O'Halloran RL, Lewman LV. 1993. Restraint asphyxiation in excited delirium [see comments]. *Am J Forensic Med Pathol* **14**:289–95.

Plum F, Posner JB, Hain RF. 1962. Delayed neurological deterioration after anoxia. *Arch Intern Med* **110**:18–25.

Pollanen MS. 2001. Subtle fatal manual neck compression. *Med Sci Law* **41**:135–40.

Polson CJ, Gee DJ. 1972. Plastic bag suffocation. *Z Rechtsmed* **70**:184–90.

Polson JK, Gee D, Knight B. 1985. *Essentials of forensic medicine*, 4th edn. Pergamon Press, London.

Ponka JL, Lam CR. 1948. Effect of asphyxia on blood coagulation in dogs. *Proc Soc Exp Biol Med* **68**:334–6.

Prinsloo I, Gordon I. 1951. Postmortem dissection artefacts of the neck and their differentiation from ante-mortem bruises. *S Afr Med J* **25**:358–61.

Pullar P. 1984. Mechanical asphyxia. In: Mant AK (ed.), *Taylor's medical jurisprudence*, 13th edn. Churchill, London.

Purdue B. 1992. An unusual accidental death from reverse suspension [see comments]. *Am J Forensic Med Pathol* **13**:108–11.

Rao VJ, Wetli CV. 1988. The forensic significance of conjunctival petechiae. *Am J Forensic Med Pathol* **9**:32–4.

Reay DT, Howard JD, Fligner CL, *et al.* 1988. Effects of positional restraint on oxygen saturation and heart rate following exercise. *Am J Forensic Med Pathol* **9**:16–18.

Reay DT, Fligner CL, Stilwell AD, *et al.* 1992. Positional asphyxia during law enforcement transport [see comments]. *Am J Forensic Med Pathol* **13**:90–7.

Schleyer F. 1963. On adventitial haemorrhages of the thoracic blood vessels. *J Forensic Med* **10**:3–5.

Schmunk GA, Kaplan JA. 2002. Asphyxial deaths caused by automobile exhaust inhalation not attributable to carbon monoxide toxicity: Study of 2 cases. *Am J Forensic Med Pathol* **23**:123–6.

Shapiro H. 1975. Asphyxia. In: Gordon I, Shapiro H (eds), *Forensic medicine: a guide to principles*. Churchill Livingstone, London.

Shapiro H. 1988. Asphyxia. In: Gordon I, Shapiro H, Berson S (eds), *Forensic medicine: a guide to principles*, 3rd edn. Churchill, Edinburgh.

Shapiro HA. 1953. Is asphyxia a pathological entity recognizable at post-mortem? *J Forensic Med* **1**:65–8.

Shapiro HA. 1955. Tardieu spots in asphyxia. *J Forensic Med* **2**:1–4.

Simpson CK. 1943. Traumatic asphyxia. *Lancet* **2**:309–10.

Sturner WQ, Sullivan A, Suzuki K. 1983. Lactic acid concentrations in vitreous humor: their use in asphyxial deaths in children. *J Forensic Sci* **28**:222–30.

Swann HE. 1960. Occurrence of pulmonary oedema in sudden asphyxial deaths. *Am Med Assoc Arch Pathol* **69**:89–93.

Swann HE. 1964. The development of pulmonary oedema during the agonal period in sudden asphyxial deaths. *J Forensic Sci* **9**:360–4.

Swann HE, Brucer M. 1949. Cardiorespiratory and biochemical events during rapid anoxic death: fulminating anoxia. *Tex Rep Biol Med* **7**:511–16.

Swann HE, Brucer M. 1949. Cardiorespiratory and biochemical events during rapid anoxic death: obstructive anoxia. *Tex Rep Biol Med* **7**:593–9.

Tamaki K, Sato K, Katsumata Y. 1987. Enzyme-linked immunosorbent assay for determination of plasma thyroglobulin and its application to post-mortem diagnosis of mechanical asphyxia. *Forensic Sci Int* **33**:259–65.

Tardieu A. 1855. Memoire sur la mort par suffocation. *Ann Hyg Pub Med Leg (Series 11)* **6**:371–82.

Zaini MR, Knight B. 1982. Sub-pleural petechiae and pseudo petechiae. *J Forensic Sci Soc* **22**:141–5.

CHAPTER 15

Fatal pressure on the neck

- Mechanism of death in pressure on the neck 368
- Manual strangulation 371
- Strangulation by ligature 379
- Arm-locks and 'mugging' 383
- Hanging 383
- The sexual asphyxias: autoerotic or masochistic practices 389
- References and further reading 392

This provides one of the most complex and controversial areas of 'asphyxial' deaths, as the mechanism is uncertain and the frequency of such deaths makes them a common problem for both forensic pathologist and jurist.

Pressure on the neck may arise from manual strangulation, ligature strangulation, hanging, direct blows, arm-locks and a variety of accidental lesions, such as entanglement with cords or falling onto the neck.

Strangulation was formerly thought to be a pure asphyxia as a result of 'cutting off the air' by occlusion of the airway during the constriction of the neck. Since the end of the nineteenth century, however, it has been recognized that the rapidity of death in many cases made it impossible for hypoxia to be the sole or even major cause. Many victims died almost immediately and exhibited none of the so-called 'classic' signs of asphyxia.

Others, though showing these signs, still died too quickly for it to be reasonably argued that lack of oxygen had proceeded to a fatal stage. It was common knowledge that most people could hold their breath for over a minute and that some pearl divers could be physically active and yet not breathe for at least 3 minutes, so the much more rapid onset of death seen in many cases required further explanation.

MECHANISM OF DEATH IN PRESSURE ON THE NECK

A number of anatomical and physiological factors must be considered in analysing the effects of pressure on the neck.

Airway occlusion

This may occur either from direct compression of the larynx or trachea, or from a lifting of the larynx so that the pharynx is closed by the root of the tongue being pressed against the soft palate and roof of the mouth. The latter explanation is far more likely, as the strong cartilages of the larynx will resist all but the most extreme compression. Various experiments have been attempted to quantify the force needed to close the airway and blood vessels, but it is difficult to translate the often conflicting results to the degree of violence actually used in fatal events. For example, Brouardel (1897) calculated that the force needed to close the trachea was of the order 15 kg, far more than that required to occlude the blood vessels.

Occlusion of the neck veins

This factor is almost solely responsible for the appearance of the 'classic' signs of congestion, cyanosis, oedema and petechiae above the line of constriction. The external jugular system is most vulnerable, but any significant pressure encircling the neck will also obliterate the lumen of the internal jugular system, causing a rapid rise in venous pressure in the head, especially if the carotid arteries are still patent, which is usually the case. Brouardel's experiments suggest that a ligature with a tension of 2 kg blocks the jugular return; Reuter (1933) found an even lower figure.



FIGURE 15.1 *Causes of mechanical asphyxia.*



FIGURE 15.2 *Possible effects of pressure on the neck: (A) carotid sinus reflex leading to cardiac arrest; (B) jugular venous compression leading to cyanosis and petechiae; (C) carotid artery compression leading to unconsciousness; and (D) airway obstruction leading to hypoxia.*

Compression of the carotid arteries

This is much less common than venous occlusion, as the higher internal pressure of the carotid arteries resists occlusion and they are situated much more deeply. The carotids are largely obscured by the sternomastoid muscles. If bilateral occlusion of the carotids is achieved, almost immediate unconsciousness will ensue, as the supply of arterial blood to the brain by the vertebral circulation is insufficient to maintain cortical function, which depends mainly upon the anterior and middle cerebral arteries that arise from the carotid supply. Occlusion of the vertebral arteries by neck compression seems virtually impossible despite some claims to the contrary.

If the carotid circulation is totally occluded for an unremitting period of 4 or more minutes, then irreversible cerebral damage may occur. The time for this to happen is variable and the minimum has been disputed for many years, but the consensus of opinion is that permanent brain damage is very unlikely if the supply has been cut off continuously for less than 4–5 minutes. Total recovery has often been recorded after total ischaemia of considerably longer than this, even in normothermic conditions, with 9–14 minutes being quoted. Where the body has been subjected to low temperature, far longer times have been recorded, including an anecdotal case of a boy falling into the cold water of a Scandinavian harbour and being totally submerged for 40 minutes, with total recovery of cardiac and cerebral function.

Nerve effects

Pressure on the baroreceptors situated in the carotid sinuses, the carotid sheaths and the carotid body, can result in bradycardia (slowing of the heart), or in total cardiac arrest. This is an example of the physiological mechanism that monitors and adjusts blood pressure and heart rate.

This mechanism acts through a reflex arc in which the afferent (sensory) nerve impulses arise in the carotid complex of nerve endings, but not – as is sometimes alleged – in the vagus nerve trunk itself.

These impulses pass up to the brain via the glossopharyngeal nerves to the tenth nucleus in the brainstem, then return via the vagus (efferent) supply to the heart and other organs. This reflex arc acts through the parasympathetic side of the autonomic nervous system and is independent of the main motor and sensory nerve pathways. It is often claimed, admittedly without much concrete evidence, that fear, apprehension, struggling and possibly the effect of drugs such as alcohol, may heighten the sensitivity of this vagal mechanism. The release of catecholamines during such adrenal responses may well sensitize the myocardium to such neurogenic stimulation.

The vagal reflex has profound implications in relation to pressure or blows on the neck. Sometimes called 'vagal inhibition', 'vasovagal shock' or 'reflex cardiac arrest', the rapid onset of heart stoppage may antedate any evidence of congestive or 'asphyxial' signs, causing death immediately or within seconds, or at any time thereafter.

It is a matter of some dispute as to whether this reflex can cause immediate cardiac arrest or whether there has to be a period of marked slowing of the heart with negligible cardiac output – or whether an arrhythmia such as ventricular fibrillation precedes such an arrest. Probably any combination can occur, but it is an indisputable fact that collapse and apparent death can occur immediately on the application of pressure to the neck. Overstimulation of nerve endings in the carotid sinus or adjacent arterial sheath may be brought about by direct pressure from fingers, or from a ligature during strangulation or hanging – or from a blow directed at the side of the neck. Severe pain, such as a blow on the larynx or genitals, may also trigger a 'vagal response'.

THE FREQUENCY OF VAGAL CARDIAC ARREST

Though different authors vary in the proportion of such deaths that they attribute to reflex cardiac arrest, they all admit to the existence of such a mechanism. In the author's (BK) own series of fatal pressure on the neck from a variety of causes, the 'classical signs', denoting vascular and perhaps sometimes airway obstruction, were present in slightly less than half the cases. The remaining deaths presented with an absence of congestion, cyanosis and petechiae, the pale faces indicating that cardiac arrest had taken place before the congestive signs had time to appear.

One aspect which is uncertain – and virtually incapable of experimental proof in humans – is whether vagus-mediated cardiac arrest can be spontaneously reversible. Where an arrhythmia leads to arrest, resuscitation by cardiac massage or direct current electrostimulation has an excellent chance of revival – though in most forensic situations, such assistance is often lacking or too late.

However, it is not known whether cardiac arrest caused by the vasovagal reflex, can spontaneously revert to normal rhythm some minutes later – or whether it inevitably leads to death if no timely resuscitation is offered. This may have forensic relevance, as the author (BK) has been involved in several cases where pressure on the neck has lead to a comatose, but heart-beating victim, who later dies on artificial ventilation from irreversible brain damage. In the absence of medical data, the problem then arises as to whether the brain damage was caused by prolonged carotid artery occlusion from neck pressure – or was the result of a momentary neck pressure which caused reflex cardiac arrest, with spontaneous reversion to normal rhythm more than five minutes later, by which time irreversible cerebral damage had occurred.



FIGURE 15.3 *Classical features of strangulation when cardiac arrest is delayed.*

Medico-legal aspects

This phenomenon has considerable legal as well as medical significance, as sudden death from 'vagal inhibition' can occur with total unexpectedness even with relatively slight pressure to the neck. Keith Simpson and Polson recorded cases many years ago in which a soldier at a dance playfully 'tweaked' his partner's neck and was mortified to see her drop lifeless to the floor. Many such cases are on record and every forensic pathologist of any experience has examples in his own records. Where it can be shown that the death occurred rapidly and without prolonged manual gripping of the neck, the defence may be raised that neither death nor serious injury was contemplated by the accused. It would be much harder to establish this lack of intent if the grip was maintained long enough to lead to florid congestion and petechiae in the face.

A combined mechanism of injury and the duration of neck compression

It is important to remember that the cardiac arrest mode of death may be mixed with the congestive–petechial mode in that, though the first stages of pressure may continue for long enough for congestive–asphyxial signs to appear (perhaps a minimum of 15–30 seconds), a change in grip may then allow the fingers to impinge on the carotid structures and lead to reflex cardiac arrest. Thus the progression of the pure 'asphyxial' process may be abruptly terminated at any point along its pathway to death by the superimposition of 'vagal inhibition', so that the intensity of the congestive changes may be of any degree in any given death.

The duration for which pressure must be maintained is often a contentious issue in criminal trials, as the 'inadvertent squeeze' which causes rapid vasovagal cardiac arrest is likely to be viewed as less culpable than a prolonged, unremitting gripping of the throat.

It is virtually impossible to measure the average minimum time of gripping that will produce congestion, cyanosis and petechiae from venous occlusion. As so often is the case in forensic medicine, animal experiments are useless for this purpose and obviously few cases of strangulation homicide are ever reliably witnessed, especially by some dispassionate observer with a stopwatch! Even in non-fatal cases – which incidentally, can produce far more florid examples of facial and eye haemorrhages than deaths – there is almost never any independent, accurate measurement of the time for which the neck was compressed.

It has been arbitrarily suggested that 15–30 seconds is probably the minimum period which will give rise to petechiae in the eyelids, conjunctivae and facial skin, but this really is 'picking a figure from the air', with little scientific justification.

Some years ago, the British Home Office and the Royal College of Pathologists set up a small working party to study this problem, composed of several experienced forensic pathologists and a respiratory physiologist – but the project was soon abandoned because of a total lack of reliable data.

Though it is easy to demonstrate that facial congestion develops within a few seconds of total jugular occlusion, petechiae – the only lasting sign after the venous return is re-opened – do not appear as quickly from neck pressure. However, they can occur from sudden, transient rises in venous pressure, such as sneezing or coughing – whooping-cough is a well-known example – and during the Valsalva experiment of forcibly trying to expire against a closed glottis. Eye petechiae and retinal haemorrhages can also occur during the chest compression of energetic cardiac massage during resuscitation.

CAUSES OF REFLEX CARDIAC ARREST

Vagal inhibition of the heart from stimulation of the carotid neural complex may occur in any form of pressure on the neck, but is much more common in manual strangulation than with a ligature, hanging excepted. Fingers seem more prone to dig deeply and find the structures under the anterior edge of the sternomastoid muscle. Perhaps the movements of the fingers, especially during the shifting postures of a struggle, more readily impinge upon the carotid bifurcation than the more static position of a ligature.

The majority of hangings, however, present with a pale face, free from congestive–haemorrhagic signs.

This seems to be caused by the more precipitate impact of the noose on the carotid structures when the victim's weight abruptly bears down, though Polson favoured actual carotid occlusion and hence cerebral ischaemia as the common cause of death in hanging. The scarcity of carotid intimal damage in suicidal hangings does not favour this view.

Blows to the throat

Another cause for sudden cardiac arrest is a blow to the neck or throat. This is the basis of the so-called 'commando punch' and some of the oriental martial arts also contain this in their repertoire – often forbidden because of its potential lethality. The edge of the hand is brought forcibly across the side of the neck or the front of the larynx.

Direct violence to the carotid region naturally causes gross stimulation of the afferent nerve endings. Blows directly to the larynx indirectly stimulate the sinus region or the laryngeal sensory nerve endings may themselves trigger the cardio-inhibitory reflex.

It is well known that the hypopharynx and larynx are particularly sensitive to stimulation, which accounts for the sudden deaths from impaction of food in the larynx, or from the flooding with cold water that causes some sudden immersion deaths. The testicles and uterine cervix also have a similar reputation for leading to sudden cardiac death, if unexpectedly overstimulated, especially when the myocardium is presensitized by catecholamines released by fear or emotion.

MANUAL STRANGULATION

A common method of homicide, manual strangulation is most often encountered when the physical size and strength of the assailant exceeds that of the victim. It is most commonly seen in domestic homicides when a husband kills his wife, in sex-related murders when the victim is again a woman, and in child killings, when the killer is an adult. Manual strangulation is rarely committed by a woman except on a child and a man rarely kills another man of equal physique.

Autopsy appearances in manual strangulation

The autopsy findings fall into two groups, namely, the local signs of violence, and the signs of the mechanism of death, where discernible.

- Bruising on the neck is the result of the assailant's attack, whereas abrasions may be from either victim or



FIGURE 15.4 *Classical manual strangulation with fingernail marks and abrasions on the neck, congestion of the face, slight protrusion of the tongue and bleeding from the nose.*



FIGURE 15.5 *Bruising on the neck and jaw margin in manual strangulation. Separate bruises along the jaw are due to high finger pressure – where a larger area of abrasion or bruising is present in this region, consideration must be given to pressure from an arm-lock.*

assailant. The bruises are mainly discoid, but may run together into larger areas of confluent bruising. The discoid marks are from finger-pads and are about 1–2 cm in size, though where the fingers skid across the skin surface, longer, irregular marks may occur, especially along the jaw margins. The bruises tend to cluster at the sides of the neck, often high up under the angles of the jaw. Some may overlap the jaw line and trespass on the chin, but others can be lower on the neck spreading down to the inner ends of the clavicles.

As a result of the shifting grip, often caused by the struggles of the victim, bruising can be anywhere, even at the posterolateral sides of the neck, and on the upper chest over the sternum and collar bones. Some may be seen in the grooves on either side of the larynx, over the anterior edge of the sternomastoid. They are also common over the prominence of the larynx and at the level of the cricoid.

As in most of the cases seen by a pathologist, death will have taken place at or about the time of the attack, most bruises will be fresh, being dark red or purple. Some may be so severe as to form actual superficial haematomas raised slightly above the skin surface. Bruises may often be seen in an asymmetrical pattern, with just one or two on one side of the neck, and a larger group on the opposite side. This may well suggest that a thumb was applied on one side and a group of fingers on the other; this may well be correct, but is not necessarily so and may be fortuitous if a shifting grip caused several reapplications of fingers.

It is sometimes tempting to use such asymmetrical grouping to decide 'handedness', that is to suggest that one bruise on the right side of the victim's neck and a group on the left means that a right-handed assailant gripped from the front. The grouping may not be genuine, however, and because it can be fortuitous, it cannot be definitely determined that it was the right hand nor that it was not placed around the neck from the back. Overinterpretation must be avoided, as in all fields of forensic medicine and 'Sherlock Holmesian' opinions as to the handedness, size of hand, and orientation of attacker and victim in strangulation must be suitably restrained if both justice and the credibility of pathologist are to be preserved.

- Abrasions on the neck: scratches may be caused by the assailant or the victim, usually from fingernails. As with bruising, rough finger-pads (especially from a male hand on the delicate skin of a female neck) may abrade the epidermis and underlying bruises may be overlain by diffuse abrasions, again often seen along the margin of the jaw line.

Linear scratches are the hallmark of fingernails and, when a woman strangles a child, the often longer nails of the woman may leave obvious marks. Whether male or female, the scratches are of two types: when the pressure is static, straight or curved marks up to a centimetre in length are made; when the nails skid down the skin, linear lines may result, sometimes several centimetres in length.

A static nail mark is often semi-lunar in shape, but caution must be used in interpreting the posture of the hand from this shape. Though it would seem obvious that the concavity of the mark should face the finger-pad, experiments by Shapiro *et al.* in 1962 showed that the converse may be true. This is caused by fixation of the skin at the centre where the nail digs in, with escape at the margins, so that when the traction relaxes, the mark appears inverted, with the convexity facing the finger-pad. However, experiments by others, including the author (BK), show that this phenomenon is by no means invariable and often the marks are the result of the nails being applied in the expected direction.

Scratches are the result of the victim's attempts at pulling away the strangling hand. As most victims are women, the nails may be long and the scratches more severe than those from the assailant, which are often absent altogether. These defence scratches may run in parallel lines from grouped fingers and run in a vertical direction in the long axis of the neck, though they are often random.

In the autopsy on a strangled victim it is good practice to take fingernail scrapings or clippings for full forensic science investigation. These should be preserved and labelled so that each clipping or scraping is individually identified – or failing that, at least the left- and right-hand material should be kept separate. Skin fragments or blood under these nails may provide blood typing or DNA characteristics that can be matched to an alleged assailant – and other valuable trace evidence, such as hairs and fibres might be trapped in a torn fingernail – though admittedly, the number of occasions when such evidence has been gained is extremely small.

The alleged assailant should always be examined medically to correlate any injuries that may have been inflicted on him by the fingernails of the victim, such as facial or hand scratches. If he is examined soon after the offence, his own fingernail scrapings should be taken, especially if the victim has neck abrasions, so that comparison studies can be made between any debris found and the tissue types of the victim.

Internal appearances in manual strangulation

Internally, the bruises described above may be visible to a greater or lesser extent in the tissues of the neck. Often they are quite superficial and are confined to the dermis, but some may be visible to an appreciable depth in the muscles and other structures in the neck.

The platysma muscle may be bruised, but the sternomastoid and the deeper strap muscles that run vertically along the larynx may show patchy bleeding, not always corresponding exactly to the position of surface bruises. They may contain infiltrated blood or even frank haematomata, especially the sternomastoid.



FIGURE 15.6 *Manual strangulation with bruising from the assailant and fingernail abrasions from the victim. The face is pale as a result of rapid vasovagal cardiac arrest before congestive signs could develop.*

At autopsy, it is essential to release the blood in the venous system before dissecting the neck to avoid or reduce artefactual haemorrhages that can occur in the region. It may be easiest to reflect the scalp and remove the brain before dealing with the neck, to release venous engorgement. Alternatively, after the skin of the neck has been carefully flayed off in a wide 'V' incision, the internal jugular vessels can be incised before any further manipulation to release the venous pressure, but removal of the skull is preferable.

Radiography of the neck may be carried out before any dissection to determine the state of the cervical spine and the laryngeal cartilages, though the author (BK) has never found this to be particularly helpful, preferring to X-ray the isolated larynx before dissection.

When examination of the deep neck structures begins, careful removal of the overlying tissues layer by layer is required, seeking genuine haemorrhage as each set of muscles is exposed. There may be bruising into the thyroid capsule and into any of the strap muscles. The vascular bundles must be handled carefully and the large veins opened with scissors. The carotids can be opened *in situ*, or after the laryngo-oesophageal pluck has been removed.



FIGURE 15.7 *Manual strangulation, showing scattered bruises from the fingers of the assailant, but also a pattern of abrasions under the chin and below the larynx, caused by the nails of the victim whilst attempting to pull off the strangling fingers.*



FIGURE 15.9 *Abrasion and bruising in manual strangulation. The face is pale, indicating a rapid sudden death; much of the skin damaged is directly over the position of the underlying carotid sinus.*



FIGURE 15.8 *Illustration of the need for all doctors to be observant and vigilant. This lady was seen in bed by a family doctor and pronounced a 'heart attack' victim. Later examination revealed facial congestion, fingernail marks on the neck and the impression of her necklace on the skin by strangling hands.*



FIGURE 15.10 *Mucosal haemorrhages in the interior of the larynx immediately below the vocal cords, in manual strangulation. This is a common finding and the mechanism is uncertain. It can occur as here – in the absence of generalized congestive–petechial changes – and appears to be caused by local trauma.*

Spurious bleeding behind the larynx

Bleeding over the front and sides of the larynx is usually genuine, if the venous pressure has been released beforehand, but great caution must be employed in interpreting bleeding behind the larynx and pharynx.

In any autopsy, substantial haemorrhage may be seen over the posterior surface of the oesophagus and on the anterior longitudinal ligament of the cervical spine. This is a common post-mortem artefact, described fully by Prinsloo and Gordon (1951) and sometimes known by their name. In the absence of any other neck lesions, especially bleeding in the lateral and anterior parts of the neck, no reliance can be placed on this haemorrhage. It tends to develop more as the post-mortem interval lengthens and even releasing the venous pressure in the neck by removal of the brain, or opening the jugulars early, does not ensure its absence. To avoid the Prinsloo and Gordon artefact, a special technique of dissecting the neck is recommended by Shapiro (1988). Another artefact in the neck, much easier to recognize as false, is ‘banding’ of the oesophagus, especially when the tissues are congested. These bands are pale areas in the mucosa caused by post-mortem hypostasis being prevented from settling by the external pressure of adjacent anatomical structures, including parts of the larynx, trachea and aortic arch. Banding is common in routine non-trauma autopsies, but has been misinterpreted by inexperienced pathologists as evidence of strangulation.



FIGURE 15.11 *Dissection of the neck in a victim of manual strangulation. There are extensive areas of bleeding in the strap muscles, the lower part of the larynx and on the submandibular gland and jaw margin. Removal of the brain before dissection of the neck reduces the risk of artefactual haemorrhages in this region.*



FIGURE 15.12 *Artefactual post-mortem haemorrhage on the posterior surface of the oesophagus in a natural death. This was fully described by Prinsloo and Gordon, and is a reason for draining the blood from the venous system of the head and neck before beginning to dissect.*

Forensic anatomy of the larynx

The larynx consists of a large 'V'-shaped thyroid cartilage, which has a prow-like prominence anteriorly and is open at the back. Below this is the smaller cricoid cartilage, which is narrow at the front, but expands posteriorly to occupy the lower part of the space left by the open thyroid cartilage.

At the upper margin of the posterior wing of the thyroid on each side, are the superior horns or 'cornuae', which are connected by the thyrohyoid membrane to the greater horns of the hyoid bone which lies immediately above.



FIGURE 15.13 *The forensic anatomy of the larynx. The hyoid and thyroid bones fracture either from direct lateral compression, or from traction from the thyrohyoid membrane when it is compressed.*

The hyoid bone lies at the root of the tongue, and consists of a central horizontal 'body', to which are attached two long 'greater horns', which sweep backwards and slightly upwards above the upper margin of the thyroid cartilage and superior horns. The hyoid often has natural joints, sometimes even with synovium, which lie at the junction of the body with the greater horns.

There are two lesser horns on the upper surface of the body that have no forensic anatomical significance. The hyoid calcifies at variable times: the body is usually calcified, but the horns may calcify irregularly, both in space and time. In teenagers and young adults they are usually cartilaginous and the joints mobile. In middle and later life, the hyoid and thyroid horns calcify and become more brittle. The cricoid cartilage is a modified upper tracheal ring but can also become partly calcified as age increases; no meaningful ages can be placed on any calcification, but traumatic fractures can occur at any time except in children and most teenagers, in whom fractures are rare.

Injury to the larynx

During manual strangulation the larynx may become damaged in various ways. The pressure is mainly bilateral, so that the sides of the larynx are squeezed. Particularly vulnerable structures are the four 'cornuae' or horns, which protect backwards to maintain the patency of the airway around the glottis. Lateral pressure of the fingers can displace any of the



FIGURE 15.14 *The hyoid bone.*

four horns inwards, either by direct pressure or by pressure on the thyrohyoid membrane, which then drags the horns medially. In young persons, the horns are so pliable that they return to their normal position on release of the pressure but, variably beyond the third decade, they may be sufficiently calcified to fracture.

The appearance of a fractured horn is of a loose or even flapping termination. The horn usually displaces medially, but is held by the thyrohyoid ligament. At autopsy it is advisable to cut down this ligament carefully between thyroid cartilage and hyoid to destroy the 'splinting' effect that may support a broken horn. As will be discussed later, however, there will be a haemorrhage at the fracture site that will make the lesion obvious. In the case of the hyoid, care must be taken not to misinterpret a natural joint as a fracture. These are more medial than the usual site of fracture, which is likely to be within a centimetre of the tip. The jagged edge of the fracture line may be exposed, especially in an older person with a brittle horn. Radiography before dissection is an excellent way of confirming a fracture, identifying natural joints and detecting any other fractures in the thyroid or cricoid cartilage.

Though the hyoid bone has received most attention in publications as being the marker of violence to the larynx, in fact the thyroid horns are far more vulnerable. Simpson (1985) found that, in 25 successive deaths from manual strangulation, there were 22 fractures of thyroid horns but only one fractured hyoid. Though this ratio is not typical of the experience of most pathologists, there is no doubt that the superior horn of the thyroid is much more fragile and more vulnerable than the greater horn of the hyoid bone. Although fractures of the horns are more common with advancing age, they can on rare occasions be found even in teenagers. Care must be taken, however, not to confuse mobility at natural joints with a fracture (Evans and Knight 1982).

Conversely, undoubted severe violence to the neck in older persons does not necessarily cause horn fractures. The frequent persistence of joints at the base of the greater horns of the hyoid may allow movement and so avoid fractures when compressed. The cricoid and the main ala of the thyroid cartilage may be cracked, but this is an index of much greater pressure from strangling fingers. The plates may break in a spiral or oblique fashion and the cricoid may crack anteriorly through the narrow bridge rather than at the wider posterior plate. Fractures of these larger areas are also found in direct blunt violence such as punching, kicking or arm-locks, often as part of general severe damage and disruption of the entire larynx.

Significance of laryngeal fractures

Laryngeal cornual fractures are, of course, merely indicators of pressure applied to the neck and are not themselves relevant in terms of a threat to life. This is sometimes misunderstood by laymen, especially police and lawyers, who have been misled by the importance that pathologists attach to the finding of a fractured horn into thinking that the injury itself is a significant contribution to the death.

Such fractures, if proved to be genuine, are certainly significant in proving the application of violence to the neck, but certain precautions must be observed in their interpretation. The sole finding of a fractured horn, where there is no other injury to the skin, subcutaneous tissues, muscles or rest of the larynx is of little value unless there is firm circumstantial evidence of violence to the throat.

When a fracture of a laryngeal horn is found, it must first be proved to be ante-mortem in origin. Post-mortem fractures undoubtedly occur, either from mishandling the body during transit or from incorrect autopsy techniques – though the frequency of the latter has been overestimated.

It is certainly possible to damage the larynx post-mortem by allowing the neck to fall against a hard surface or sharp edge during removal from the place of death, or during handling in the mortuary. Such damage, however, is more likely to occur to the laryngeal plate of the thyroid cartilage or to the cricoid, rather than to the laterally placed horns, though these can be broken. Damage at autopsy is usually caused by an inexperienced pathologist or autopsy-room technician, especially when forensic expertise is lacking. Clumsy removal of the tongue and neck structures can break the thyroid or hyoid cornuae, especially in old persons where they are calcified and brittle and when any natural joints are ankylosed.

This may be one justification for radiography before autopsy, but probably the danger of artefactual breakage has been overestimated, especially where a gentle removal technique is employed.

Proof of ante-mortem laryngeal fracture

This must be obtained by demonstrating haemorrhage at the fracture site. It is usually obvious to the naked eye and can be confirmed histologically. Sometimes the bleeding is prominent, with a blood bleb under the periosteum or perichondrium at the fracture line, and the broken end of a calcified horn may be palpable and even slightly crepitant. Where no macroscopic evidence of bleeding is found, careful histology of the fracture site will almost always reveal some red-cell extravasation, but this evidence is of less value because microscopic – and even slight macroscopic – oozing can occur from a post-mortem fracture of a horn. Bleeding is therefore a 'one-way' criterion: if there is no haemorrhage, the fracture must be post-mortem, but if there is a small bleed, then the lesion can be either ante-mortem or post-mortem. Naturally the findings must be taken in conjunction with other evidence of neck injury and, if there are surface bruises, scratches, muscle bleeding, intralaryngeal and tongue haemorrhage, then a minimal bleed at a fractured horn can be accepted as probably ante-mortem.

Conversely, it must again be emphasized that the solitary finding of a fractured laryngeal horn, even with slight associated bleeding, is not in itself sufficient evidence of ante-mortem trauma to the neck.

Other causes of fractured laryngeal horns

The hyoid and thyroid horns can be broken other than by manual strangulation. Ligature strangulation and hanging can certainly cause these lesions, though not as often as manual throttling. Direct violence can also break the cornuae, but usually only as part of more diffuse laryngeal damage. A punch or kick in the throat can disrupt the larynx and break the horns as part of general damage. Even wide, blunt pressure can fracture the horns, however, such as an arm-lock from behind squeezing the larynx against the cervical spine. It has been said that such direct violence from the front tends to splay the fractured horns laterally, whereas in manual strangulation the horn tends to fall inwards – but this is too tenuous a claim to be of much practical value.

In accidents, the larynx can be damaged. In falls, the larynx is usually protected by the prominences of the chin and chest, but if the fall is onto a ridged object, such as gate or chair-back, then a focal impact can injure the throat. The author (BK) has seen a death in a housebreaker, who slipped when trying to climb through a sash window. He fell with his throat across the top of the window-frame and died – presumably of a vagal cardiac arrest – being found suspended by his neck next morning with fractures of the laryngeal cartilages.

Other laryngeal injuries in strangulation

Other injuries to the larynx include splitting of the ala of the thyroid cartilage, often either in the midline or obliquely across the left or right plate. This may be part of a violent strangulation, seen by Green (1973) in 12 per cent of his series – but is more often seen in blows to the front of the neck, either by fist or the edge of the hand, or a kick or any other kind of substantial trauma directed at the front of the neck.

The cricoid cartilage, a circle shaped like a signet ring that lies below and partly within the thyroid cartilage, may also be fractured by manual throttling when pressure is applied rather lower than usual. Again, this cartilage tends to break either across the front midline or obliquely. Though an uncommon injury, a severe displacement of a broken cricoid – especially if accompanied by mucosal tearing and bleeding – may project backwards into the airway and cause a partial obstruction.

The interior of the larynx may also show indications of pressure on the neck. This usually takes the form of haemorrhage into the mucosal lining and is most often seen immediately below the vocal cords. Bleeding may be intense here, but its cause is obscure. It can occur with no other damage to the cartilages of the larynx and it is then hard to equate it with direct physical pressure as it lies on the protected inner surface.

Similar, but less intense, haemorrhage is sometimes seen on the surface of the epiglottis, which more often shows a shower of petechial haemorrhages if the death was not sudden.

Such haemorrhage inside the larynx is often a bright, fiery red, unlike the dark cyanotic discoloration that is seen in the pharynx, root of tongue and larynx in congestive–asphyxial deaths, and is caused by obstructed venous return rather than direct trauma. At autopsy the base of the tongue should always be sliced, as deep haemorrhages may be present, usually at the sides of the tongue, deep congestion being more central or across the whole posterior part of the tongue.

Damage to the carotid arteries

Though the sudden 'vagal inhibition' type of death caused by pressure on the baroreceptors of the carotid sinus and sheath is quite common, it is unusual to find anatomical confirmation of injury to these structures.

There may be deep haemorrhage in the neck tissues surrounding or adjacent to the bifurcation of the common carotid artery, but this is often absent in these cases of cardiac arrest – and conversely, such bleeding may be found in the slow 'asphyxial' deaths, as part of the generalized diffuse bleeding into the tissues.

Rarely, careful dissection of the carotid arteries may reveal an intimal tear or bleeding into the walls of the vessels at or near the carotid sinus. A delicate technique is required and artefactual damage must be carefully excluded, especially that from the point of scissors used to slit open the artery. Such tears are more often found when a forcible impact or a more focal pressure has been applied, such as from a thin ligature that can cut deeply and abruptly into the neck, especially in hanging. Generally, little or no morphological confirmation is to be expected in the cardiac arrest type of death, following pressure on the neck. The diagnosis is one of exclusion, based on the absence of any congestive–cyanotic–petechial appearances, together with some circumstantial history of sudden death whilst pressure is being applied to the neck.

As already mentioned, one problem is that pressure may be maintained for long enough – perhaps a minimum of 15–30 seconds – to produce these signs, yet not cause death, but death then supervenes abruptly because a vagus-mediated cardiac arrest is superimposed on the early asphyxial mode. In the absence of any structural damage to the carotid apparatus, autopsy cannot differentiate between the two mechanisms and only the history (which is rarely available for obvious reasons) can assist in interpreting the sequence of events.

STRANGULATION BY LIGATURE

Pressure on the neck may be effected by constricting all or part of the circumference of the neck by a ligature. This is sometimes called 'garrotting', though strictly this refers to the tightening of a noose around the neck by twisting a rod within the ligature, a form of judicial execution once employed in Spain, from which also comes the description of the twisting device as a 'Spanish windlass'. This method had a refinement in which the back of the neck was forced against a sharp spike which penetrated the spinal cord.

In forensic practice, if hanging is excepted as a separate entity, most ligature strangulations are homicidal. Some are suicidal and a few accidental, usually in children.

The nature of the ligature

The ligature may consist of a wide variety of objects, some not obviously suitable for the purpose, yet effective in causing death. Cords, wires, ropes and some belts are strong and relatively thin, so that they tend to cut deeply into the neck if the tension is great. Softer fabrics, however, in the form of scarves, ties, towels, stockings, tights and even strips of bed-linen may be used and may cause some problems in interpretation if they are removed from the scene before the investigation begins. The ligature may be applied as one turn around the neck – or even less, as homicides have been perpetrated by the assailant pulling a U-shaped ligature against the front and sides of the neck, while standing at the back. Even a flexible rod, such as bamboo cane or – in India – a flat 'lathi', can act as a ligature if the two ends are forcibly pulled back from behind against the front of the throat.



FIGURE 15.15 *Ligature mark from a nylon scarf. Although the fabric was broad, the tension bands from the tightly stretched material have produced a definite line that could be mistaken for a cord or wire.*



FIGURE 15.16 *Ligature strangulation with a generally horizontal course for the two strands of cord that diverge from the skin at the back of the neck.*

In the majority of cases, however, the ligature is crossed over itself after passing a full circle around the neck – and several turns may be wound around, secured with one or more knots. These multiple turns are not uncommon in



FIGURE 15.17 *Fracture of the left laryngeal horn (arrow) with haemorrhage. The body was recovered from a lake based on the confession of the perpetrator. Further findings were haemorrhage in the fractured cricoid cartilage, bruising on the neck and petechiae in the conjunctivae and larynx.*



FIGURE 15.18 *Typical appearance of congested, cyanosed forehead, with multiple petechiae in the skin, in a woman strangled manually and by ligature. Circular bruising probably due to knuckle blows. The scarf tied around the neck initially suggested only ligature strangulation.*



FIGURE 15.19 *In the case shown in Figure 15.18. When the scarf was removed, typical bruises and abrasions of manual strangulation were seen in addition to the ligature mark.*

suicide, where two, three, or even more circles are wound around, often with complex knots. The presence of these more complicated ligatures by no means confirms homicide – in fact they are more common in suicide, where the determined victim is eager to succeed. The ligature may be tightened even further by means of the 'Spanish windlass' mentioned above, which consists of some rod-like object, which may be a ruler, stick or screwdriver inserted between the ligature and the skin, and twisted around several times. The rod may be held in position by being wedged under the chin or against the shoulder or chest. This device may be seen in either homicides or suicides.

The ligature mark

The appearance at autopsy naturally depends on the nature and texture of the ligature. When there is a pronounced pattern, such as the weave of a cord or the plaiting of a thong, the same pattern may be imprinted into the skin. In homicide, where the ligature has been removed by the killer, such a pattern may be of great value in tracing its origin. When a fabric has been used, such as a scarf or towel, the marks on the neck are more difficult to interpret. A broad, flat band may leave no mark whatsoever, but it usually leaves one or more linear marks on the skin of the neck, often discontinuous. These may fade if the body is not seen soon after death and if the surface has not been abraded.

A fabric ligature may leave a sharply defined mark, which may be misinterpreted as being caused by a narrow cord or wire. The reason for this is that when a broad piece of cloth is tightly stretched, one or more bands appear that are under greater tension than the rest. It is these that mark the skin, and no sign may be left that a wider area was lying on either side of the most tensed band. These marks are usually less well demarcated at the edges than a cord or rope, but can cause confusion.

When the ligature is still in position when the body is examined, it may appear to be deeply embedded in the skin, sometimes almost out of sight, and on removal a deep groove may be seen in the skin. This embedding may be accentuated by oedema of the tissues, especially above the ligature, which initially may not have been applied so tightly. The swelling can continue to develop to some



FIGURE 15.20 *Self-strangulation by ligature, with three turns around the neck and a complex knot. There was no doubt from the circumstances that the deceased man had deliberately killed himself with this telephone cord, but the mechanism of apparent vasovagal death before any congestive changes could appear remains obscure.*

extent even after death, accentuating the depth of the groove. Presumably some passive transudation of tissue fluid continues even after the circulation has stopped. In suicides, multiple turns and knots may have been applied and obviously, the degree of tightness as seen later at autopsy could not have been present during the application of the ligature, otherwise incapacity would have been so rapid that the process could not have been completed. In such cases, it is remarkable how often the mode of death still seems to be of the non-asphyxial cardiac arrest type. It might be expected that vagal stimulation could not have occurred once the expected static position was attained with the completion of ligation – but experience indicates otherwise, the mechanism remaining obscure.

The skin mark may remain red, especially if the ligature was of softer material such as cloth, but cords, ropes and wires tend to abrade the surface, which later becomes yellow or brown and parchment-like. This is seen particularly in hanging, when the friction and chafing may be greater.



FIGURE 15.21 *Ligature strangulation by means of a 'Spanish windlass'. A penknife has been thrust through the knot to twist the ligature tight.*

The stiff, brownish-yellow appearance occurs post-mortem and tends to become more pronounced as the interval lengthens after death. The mark may be slightly wider, narrower or the same width as the actual ligature, depending partly upon how deeply it cut into the skin. There is often a narrow zone of reddened hyperaemia at either margin of the mark. This used to be taken to indicate that the ligature must have been applied during life – though by analogy with the spurious 'vital reaction' sometimes seen as a post-mortem development at the margin of burns (see Chapter 11), this sign is of doubtful reliability. Experiments by Pollak (personal communication) confirm this by the production of similar marginal reddening by applying ligatures soon after death – it seems to be due to lateral displacement of blood from the squeezed area immediately below the ligature.

THE POSITION OF THE LIGATURE MARK

The geometry of the mark is important in interpreting the fatal events. In strangulation, unlike hanging, the mark tends to encircle the neck horizontally and at a lower level. Typically it crosses immediately above or below the prominence of the


[redacted] CONSTABULARY
Ligature from [redacted]
Removed by Dr. [redacted]
at 1.30 a.m. 14/5/ 6[redacted]
Ends cut at point below right ear

FIGURE 15.22 *At autopsy on a victim of ligature strangulation, the ligature should be cut well away from the knot, if one is present. The knot should never be untied, but preserved for forensic examination. If the ligature is in danger of unravelling, it should be tied at two places and divided between these points. (Reproduced with permission from Robert Hale Publishers.)*

larynx and passes back to the nape of the neck. In homicide, where a single turn is used, there is often a cross-over point where the two ends of the ligature mark overlap. This may be at the front, side or back of the neck, depending on the relative positions of assailant and victim.

When a knot is tied, it may leave a mark on the skin and, of course, if multiple loops are present, some or all of these will be represented on the skin. Unless the killer is pulling upwards, the mark will not be seen to rise nor will there be a gap in the mark at the highest point, as seen in most hangings.

In the later section on hanging, the point will be made that sometimes a hanging mark may resemble a ligature mark, but the converse is almost unknown.

Other signs of local injury in ligature strangulation

There may be scratches on the neck, but these are usually caused by the attempts of the victim to pull away the ligature. Fingernail marks, sometimes linear and vertical, may be present as in manual strangulation, but not focal abrasions or bruises. Internally there may be superficial haemorrhage under the ligature mark, though this is often minimal. Depending on the force with which the ligature was applied, there may be deep damage in the muscles of the neck, but this tends to be less than in manual strangulation. Similarly, there may be laryngeal injury, but less severe than from pressure from the hands. The hyoid bone and thyroid horns may be fractured, especially where the ligature rides at the level of the thyrohyoid ligament, but damage to the laryngeal cartilages is much less common than in manual strangulation. Gonzales found in 24 fatal manual strangulations, four hyoid fractures but nine thyroid and cricoid fractures. In 25 deaths from manual strangulation, Simpson found only one hyoid fracture but 22 with thyroid horn fractures. It is rare for the main thyroid plate or the cricoid to be fractured unless gross violence was applied with excessive pressure by a strong ligature. Uncommonly, a narrow wire may be used, the so-called 'cheese-cutter' method. Here, strong pressure over a small area – such as that delivered by a piano wire – may actually lacerate the skin, and even cut into the deeper tissues and cartilages.

Where much bruising and abrasion is seen, especially if scattered and away from the actual ligature mark, then the possibility of a combination of manual and ligature strangulation must be considered. This is not uncommon, the handling of the throat either preceding or accompanying the application of the ligature. Fractures of the laryngeal structures may be caused by this element, rather than the associated ligature. A deeply sunken narrow ligature applied with force may damage the carotid arteries and focal injury to the intima may rarely be found on careful dissection.

The mode of death in ligature strangulation

The mode of death is more often the 'classic asphyxia' picture than in manual strangulation, where sudden cardiac death is common before congestive–petechial changes have time to occur. The contrast in the appearance of the skin immediately above and below the ligature mark is often striking, with pale skin below, and a puffy, oedematous, congested, cyanotic and haemorrhagic surface above. Petechiae may abound in the eyelids, conjunctivae and facial skin, and there may be bleeding from the ear and nose. This is by no means invariable, and many ligature strangulations die rapidly from vagal reflex cardiac arrest before any congestive signs have had time to appear.

This can occur in both homicide and suicide and, as mentioned earlier, the mechanism is obscure, especially where the victim – bent on self-destruction – has been able to complete multiple loops around his neck and tie several knots before dying.

Accidental ligature strangulation – which may be actual hanging if the body weight is thrown wholly or partially upon the ligature – is seen in the tragedies than occur to young children, who may become entangled in blind or curtain cords, usually when their cot or playpen is left too near a window.

ARM-LOCKS AND 'MUGGING'

The original meaning of 'mugging' has now been confused by its application, especially in North America, to any form of robbery with violence. The term strictly means throttling by pressure from an arm held around the throat. The attack is usually made from behind, the neck being trapped in the crook of the elbow. Pressure is then exerted either on the front of the larynx, or at one or both sides by the forearm and upper arm. The mechanism is further discussed in Chapter 10, as an arm-lock (or 'choke-hold') is a method of restraint used by police officers for law enforcement, but it is rapidly losing favour because of the number of inadvertent fatalities due either to 'asphyxia' or to reflex cardiac arrest. Following several fatalities during police arrests in the early 1990s, the Association of Chief Police Officers in Britain have issued recommendations that arm-locks be avoided during the restraint of violent prisoners.

The autopsy features are those of ligature strangulation with a broad object, in that signs may be minimal. Some diffuse abrasion may be seen, especially along the margin of the jaw or lower face, sometimes over a considerable area, caused by the friction of the forearm. Internally there may be diffuse bruising, but this again may be slight or even absent. The larynx may also escape damage, though if it is pressed backwards against the spinal column the thyroid horns and even the hyoid may fracture (see also Chapter 10).

HANGING

Hanging is a form of ligature strangulation in which the force applied to the neck is derived from the gravitational drag of the weight of the body or part of the body.



FIGURE 15.23 *Typical posture in hanging with the suspension point rising to the ear, tilting the head to the opposite side. The tongue is projecting because of upward pressure on the larynx and root of the tongue. There are no congestive appearances. As a slip-noose was used, the rope is in contact with the skin throughout the full circumference of the neck.*

Judicial hanging

The modern form of judicial execution is unrelated to the usual suicidal hangings seen in routine forensic practice, as it depends upon severe mechanical disruption of the neck structures. Until the nineteenth century judicial hanging in Britain was carried out even more barbarically by 'ordinary' hanging, where the victim was strangled at the end of a rope by his own weight. At the infamous Tyburn execution site near the present Marble Arch in London, tens of thousands were dispatched, the usual method being the placing of a rope noose around the neck of the condemned person, who stood on a cart or ladder. This support was then removed leaving the victim suspended. Some contemporary accounts suggest that many died with little further movement, but this was not the case for a considerable number and it was not unusual for the victims' relatives to pull on the victims legs to shorten the agony. It appears to have been a desire to increase the rapidity with which death occurred that 'improvements' were made, principally the use of a drop effected suddenly by means of a trapdoor. The use of a drop required the placing of the 'knot' – really a brass eyelet and rubber washer – under the left ear where it was less likely to be pulled over the head than at the occiput, a traditional site. The aim was that, when the rapidly falling body was suddenly arrested, the cervical spine would be dislocated resulting in traction on the spinal cord with consequent spinal cord or brainstem disruption. Exhumation of persons executed by this method shows that fracture was not usual but post-mortem accounts of findings indicate that cervical spine dislocation – occurring at various levels – was common with resulting cord or brainstem damage. However, the effects do seem to be variable with decapitation occurring at drop heights, which, in others, judging by contemporary descriptions of the execution, appear not even to have caused rapid unconsciousness. Though cerebral function presumably ceased immediately on cord or brainstem damage, the heart usually continued to beat, sometimes for up to 20 minutes until hypoxia caused arrest.

Suicidal and accidental hanging

Apart from the now rare 'lynching', hanging is almost always suicidal or accidental, the former being by far the most common. Hanging has many features in common with ligature strangulation. Death is, however, more often caused by reflex cardiac arrest from pressure on the carotid structures. Many more victims of hanging are found to have pale faces, rather than the congested, haemorrhagic appearance of the slower asphyxial type of death. James and Silcocks (1992), in a 15-year survey of hangings in Cardiff, found congestive–petechial features in 27 per cent, being related to the completeness of suspension.

Polson suggested that the usual pale face in hanging is caused by cerebral ischaemia from bilateral occlusion of the carotid arteries rather than a vasovagal effect, though this seems incapable of proof. In either event, the death can be taken to be rapid if no asphyxial signs are present.

Methods of hanging

Most hangings are self-suspension. This may be carried out by a wide variety of methods, but a typical method of self-suspension is to attach a thin rope to a high point such as a ceiling beam or staircase. The lower end is formed into either a fixed loop or a slipknot, which is placed around the neck while the intending suicide stands on a chair or other support. On jumping off or kicking away the support, the victim is then suspended with all or most of his weight upon the rope.



FIGURE 15.24 *Suicidal hanging with the feet flat on the floor. The deceased man stepped off the low stool, but the stretching of the cloth ligature prevented total suspension. Many suicidal hangings are successful at much lower levels, such as doorknobs and bed headboards.*

The many variations of this involve either the ligature or the height of suspension. Wires, string, pyjama cords, belts, braces (suspenders), scarves, neckties, stockings and numerous other devices may be used, depending on availability. In prison or police custody considerable ingenuity may be employed to defeat the efforts of the custodians to remove anything that could be used for self-destruction: shoelaces, stockings and torn bed-sheets have been used in prison cells.



FIGURE 15.25 *Suicidal hanging by means of a necktie. The deceased man had suspended his neck from a hook on the back of a door by tying two neckties together. The hook had pulled out and he was found on the floor. Note the pale, uncongested face, indicating rapid cardiac arrest.*



FIGURE 15.26 *Hanging deaths in children are very rare. This 7-year-old boy took his leave from his playmates and hanged himself from a bedpost under their very eyes.*



FIGURE 15.27 *Hanging with a fixed knot in the cord, so that there is a segment of skin free from the mark where the cord rises towards the knot. This was part of the common murder–suicide pattern in a domestic homicide.*

Suspension is often not high enough to keep the victim's feet clear of the floor. Commonly, when the person steps from his support, the stretch in the ligature rope is sufficient to allow the feet to reach the ground, but this by no means prevents a fatal outcome. The weight of the upper part of the body leaning into the noose is often more than enough to cause death. Successful hanging can occur from low suspension points, where the person is merely slumped with part of his weight into the ligature. Hanging can take place from doorknobs, bedposts and any other convenient low securing point. The body may be merely slumped against the door or bed or chair, with the legs and buttocks supported on the floor, so that only the weight of the chest and arms is contributing to the fatal pressure within the noose. One 'hanging' seen by the author (BK) was successfully achieved by merely leaning the neck into the shallow curve of a low clothesline stretched between two posts in a garden.

It is unusual for a suicidal hanging to be sufficiently violent for damage to the cervical spine to occur as the length of drop is usually too short. Only occasionally will a person jump from a roof or other high place with a rope around his neck – here severe injury can occur, even decapitation if the



FIGURE 15.28 *This inmate had torn up a sheet and attached both ends to a water tap (not shown) and is leaning into the loop in sitting position with sparing of the back of the neck.*

rope is strong enough. More often the jump will be from an attic trapdoor or a tree, sufficient to damage the vertebrae or atlanto-occipital joint. The author (BK) once saw a fractured cervical spine when a heavily built soldier jumped off a lavatory seat after securing a rope to the overhead cistern, but this is unusual.



FIGURE 15.29 *A deep hanging mark showing the high position under the chin rising to the back of the neck. The spiral weave of the rope is clearly imprinted in the skin. The dark tint of the face is racial, not congestive.*



FIGURE 15.30 *A perfectly horizontal mark around the neck in a man who hanged himself from a staircase. A slipknot was used, which tightened so that the usual rising line of a hanging mark did not occur, illustrating the dangers of assuming that the usual is invariable.*

The hanging mark

The mark on the neck in hanging can almost always be distinguished from ligature strangulation. The circumstances will usually indicate the fact of hanging, but sometimes the rope will break or become detached, and the deceased will be found lying with a ligature around his neck. There may then be doubt as to whether he was hanged or strangled. Obviously a search of the locus for a suspension point and signs of rope attachment will be the task of the investigators.

The hanging mark almost never completely encircles the neck unless a slipknot was used, which may cause the noose to tighten and squeeze the skin through the full circumference of the neck. In most instances the point of suspension is indicated by a gap in the skin mark, where the vertical pull of the rope leaves the tilted head to ascend to the knot and thence to the suspension point. This gap is usually seen at one or other side of the neck or at the centre of the back of the neck. Much less often it is under the chin. The knot itself may be impressed into the skin, especially if at the side of the head, above the gap where the anterior mark begins.

The hanging mark, the features of which resemble those described earlier in strangulation, is usually deepest at the side diametrically opposite the suspension point where the maximum load-bearing occurs. Like ligature strangulation,



FIGURE 15.31 *A hanging mark showing the plaited imprint of a six-strand cable. There is a central line of abrasion, within a zone of pallor caused by vascular compression, outside which is a narrow band of hyperaemia. The mark is horizontal due to leaning forwards.*

the mark may be abraded, brown and dried to a parchment-like consistency after death. There may be a narrow red zone either above or below (or both sides) the ligature mark. This is not an indicator of vital reaction, as explained in relation to ligature strangulation, but is due to displacement of blood laterally from under the zone of maximum pressure.

THE POSITION OF THE HANGING MARK

The hanging mark is situated higher on the neck than in strangulation, usually being directly under the chin anteriorly, passing round beneath the jawbones and rising up at the sides or back of the neck to the usual gap under the knot.

An exception may be seen where the suspension point is low and part of the body is supported. For example, the victim may sit or slump on a chair, bed or floor with the rope attached to a point only slightly above neck level. Then the pull on the rope is almost at right angles to the axis of the body when the latter slumps away, so that the resulting mark may be almost horizontal and set at a lower level than usual on the neck. In such cases, if the body is cut down before investigators arrive, it may be much more difficult to distinguish hanging from strangulation, a fact which has been argued in more than one criminal trial or controversial death, such as that of Rudolf Hess in Spandau Prison, Berlin in 1987.

On rare occasions, hanging will take place with the suspension point at or above the point of the chin with the rope cutting into the back of the neck. Where the rope passes across the jaw margins to a knot in front of the face, the mechanism of death is somewhat obscure as the laryngeal region suffers little or no compression. Fatalities, however, certainly do occur, presumably as there is still opportunity for pressure on the carotids.



FIGURE 15.32 *The position of the hanging mark on the neck. (a) Usual position with fixed noose and high suspension point. The mark rises high to a gap. (b) If a slipknot is used, the tightness of the deeply impressed loop tends to find the smallest circumference on the neck, and may be lower and more horizontal. (c) If the suspension point is low and the subject leans away, the mark can be horizontal.*

Autopsy appearances in hanging

Apart from the appearances of the hanging mark, there are some other features to note. First, post-mortem hypostasis



FIGURE 15.33 *The back of the victim in Figure 15.31, showing tying of the wrists. This does not indicate a homicide, unless the ligature could not have been self-applied. Some persons bent on self-destruction will try to ensure that they do not attempt to rescue themselves. A suicide note was left in this case.*



FIGURE 15.34 *Suicidal hanging with the rope in a frontal position. Even though the larynx cannot be compressed, death is due to pressure on the carotid arteries and sinuses. The face is pale, with no so-called 'asphyxial' signs.*

will occur in the legs and hands if the body has been in the vertical position for at least a few hours. When the body is cut down and laid horizontal for a considerable time, some or all of this appearance may flow back into the usual pattern.

Petechial haemorrhages are the exception rather than the rule, most series reporting them in approximately 25 per cent of cases. Such petechiae appear to occur more frequently in incomplete suspension but are frequently present in the absence of significant congestion. Congestion itself is far less usual than a pale face.

In the neck tissues there may be surprisingly little to find with an absence of laryngeal fracture or strap muscle haemorrhage being a common finding, especially if a soft ligature has been used. However, the literature suggests that an average figure for the incidence of soft tissue haemorrhage would be about 20–30 per cent of cases and for laryngeal fractures approximately 35–45 per cent of cases. Fractures of both the hyoid and thyroid may be seen.

Damage to the intima of the carotid arteries, often in the region of the sinuses, may sometimes be found on careful dissection. In hangings with an unusually long drop, severe disruption of the larynx can be found.

Mechanism of hanging

There are a number of mechanisms by which hanging may cause death, which may act independently or in concert. These include: stretching of the carotid sinus causing reflex cardiac arrest; occlusion of the carotid (and possibly vertebral) arteries; venous occlusion; airway obstruction resulting from pushing the base of the tongue against the roof of the pharynx or from crushing of the larynx or trachea; and finally spinal cord–brainstem disruption.

Whilst hanging shares some features with manual strangulation, the majority of victims of hanging are seen with pale faces rather than the congested, haemorrhagic appearance associated with the slower death resulting from pressure on the neck. This probably reflects a different mechanism, with reflex cardiac arrest and carotid occlusion more prevalent in hanging than in strangulation. Such mechanisms cause death rapidly, with unconsciousness resulting from bilateral carotid occlusion 3–11 seconds after the application of circumferential pressure.

However, the precise interplay of different mechanisms, which themselves appear only partially dependent on the completeness of suspension and the location of the noose, is impossible to determine from the pathological findings alone.



FIGURE 15.35 *Hanging by frontal suspension. A leather noose has been used so that compression has occurred round the whole periphery of the neck. The imprint of the metal ring on the jaw is well seen.*

Accidental and homicidal hanging

Though most hangings are suicidal, accidental hangings occur from two main causes. The first is entanglement in ropes or cords; this is relatively uncommon, and is usually seen in infants and children. The straps of a baby harness, used to support or restrain an infant, have led to death on a number of occasions, the child becoming entangled in leather or plastic reins when no adult was present. Any other cords may present a similar hazard, as in several cases seen by the author (BK), where infants standing in a cot near the bedroom window became entangled in a noose formed by the control cords hanging from a nearby blind or curtain.

On rare occasions, similar tragedies have befallen adults in factories, farms or ships, where a trip or fall has precipitated the victim head-first into machinery or structures, where ropes or cords have caused hanging or strangulation.

More commonly, a totally different situation causes fatal hanging or strangulation, almost exclusively in men and most often in young men, which is described in the next section.

Homicidal hanging is very rare, outside abuse of human rights and 'lynching'. For one individual to hang another, there must be either a disparity in their size and strength – or the victim must be drugged, drunk or otherwise incapacitated by fear, illness or senility. For a conscious, presumably unwilling, victim to be hanged by another, there will inevitably be signs of resistance, such as grip bruises on the arms due to restraint, or signs of binding the arms, wrists or legs.

THE SEXUAL ASPHYXIAS: AUTOEROTIC OR MASOCHISTIC PRACTICES

Though not all of this group are hangings or strangulations, this well-recognized phenomenon is conveniently considered here. The sexual asphyxias occur almost exclusively in men and only a few reports exist of women indulging in this dangerous habit, though Byard *et al.* (1990) have been able to contrast the death scenes in the two sexes, indicating that males tend to use more apparatus, whilst females are usually found naked with only a ligature in evidence.

The age of the male victims can vary widely, but is most often seen in young to middle-aged adults. The deaths that occur are obviously a small proportion of the total incidence of this strange practice. A fatal outcome is usually because of some failure of the equipment and this emphasizes the accidental nature of most of these deaths.

Features of the sexual asphyxias

The basic mechanism of the sexual asphyxias is the production of cerebral hypoxia, which in some men appears to produce hallucinations of an erotic nature.

This hypoxia is most often achieved by constriction of the neck by a ligature, which can be voluntarily tightened to produce vascular obstruction and perhaps airway stenosis. It would seem reasonable to think that vascular obstruction, either by blocking venous return – or even carotid flow – to the brain was the most likely explanation, as this would occur early. The production of cerebral hypoxia by anoxaemic anoxia through airway narrowing would surely be painful, distressing and slow in onset – hardly features which persons intent on self-gratification would welcome.

Some autoerotic procedures use other means of hypoxia, such as anaesthetic agents and a variety of volatile substances, tapering into 'solvent abuse', discussed elsewhere (Chapter 34). Whatever the mechanism, when cerebral hypoxia occurs with its attendant erotic sensations, progressive loss of voluntary control as consciousness fades allows the constrictive device to slacken, so that the subject recovers. As some fatal cases show clear evidence of repeated previous escapades, it is obvious that the mechanism usually functions quite successfully and that death was the result of some unforeseen complication.

A common practice is to place a fixed noose around the neck, so that compression will cease as soon as muscular tension on the free end is relaxed. This free end may be passed down the front or back to be fastened to the ankles, so that by extending the legs, the noose around the neck is



FIGURE 15.36 *Hanging in circumstances which suggest a sexual–masochistic motive. The young man showed no signs of previous depression or suicidal tendency. He was found naked, with arms and legs tied together with wire. Though homicide was suspected at first, the bonds were loose and easily self-applied. No satisfactory explanation was forthcoming.*



FIGURE 15.37 *A hanging in which it was not clear if there was a true sexual–masochistic element. The victim was suspended by electric cable from an attic trapdoor with his face plastered with surgical tape and the wrists tied together. Homicide could be excluded. In some deaths with an undoubted sexual element, the means used would inevitably lead to a fatal outcome, so there seems to be an overlap between masochism and suicide.*



FIGURE 15.38 *Fatal sexual asphyxia in an engineer with a rubber fetish. He was found dead connected to a dental anaesthetic machine, with a rubber face mask strapped on over a rubber teat in the mouth. Bizarre pornographic material devoted to dentistry was in the vicinity. (Figure reproduced by kind permission of Dr S Leadbeatter.)*

tightened. Compression may also be attained by passing the rope over a support and hanging a weight on the end to produce tension.

Other men may secure the end to an overhead support and achieve constriction by slumping against the pull of the rope. In these and similar cases, it is difficult to understand how death can be avoided once consciousness is lost, but evidence of repetition on previous occasions indicates that enough voluntary control must be retained to allow the person to retrieve the situation after obtaining his erotic satisfaction.

Similar hypoxia may be produced by placing the head in a plastic bag, by pushing the head into a confined space, by postural contortions (often associated with bondage) that constrict the airway, or a host of other ingenious methods. One case seen by the author (BK) deliberately constructed a large sack made from impervious material, into which he crawled to attain his hypoxia. Certain features of these deaths make them fairly easy to differentiate from suicides, a distinction which is important, though some cases are impossible to separate from deliberate attempts at self-destruction (Knight 1979).

Bondage is common, with sometimes elaborate and bizarre methods of restriction. The wrists and ankles may be tied together with cord, wire, chains, padlocks or handcuffs, for example, and it is vital for the investigators to ensure



FIGURE 15.39 *A presumed instance of sexual asphyxia. The deceased was naked and had enveloped himself in a large impervious bag, which he had made himself. It seemed impossible for him to save himself once unconsciousness had occurred, but there appeared to be no suicidal tendencies in the history.*

that such bondage could have been secured by the deceased himself to exclude the possibility of homicide, usually by a heterosexual or homosexual partner involved in the ritual.

The bonds may be sexually orientated, with straps around the crutch or constricting the genital organs. In cases seen by the author (BK), one had made a metal sheath for the penis that was padlocked in place and another clamped the penis within a metal shackle.

Masks and gags may be in place, again a manifestation of restraint. The mouth may be sealed by adhesive plaster and the eyes blindfolded. Rubber or leather often features in the masks, which may have eye-slits or completely envelope the face. Transvestism is common, female attire being worn either overtly or under male clothing. False breasts and nipples may be fabricated or brassières padded with cloth. This is a common phenomenon, however, without sexual asphyxia, as any coroner's autopsy service will reveal some men (often elderly) as hidden transvestites, wearing female underclothing beneath their suits. Fetishism is often seen, especially rubber or shiny plastic or leather. Female wigs and make-up are sometimes encountered, though the syndrome does not seem to be overtly associated with homosexual activity.

Pornographic literature is often within view and may be spread around the body at the scene of death. The act is sometimes performed before a mirror and masturbation is common. The mere emission of semen found at autopsy does not confirm sexual activity in itself, however, as post-mortem discharge of semen from the meatus is common in any type of death, not only in asphyxia (as used to be commonly alleged by standard textbooks). Occasionally, lewd writings are left near the body and even upon the body surface. The author (BK) has seen one where obscene graffiti were written with a ball-pen on the abdomen and around the glans penis.

Perhaps more importantly, overt suicide notes are never present, helping to distinguish the cases from definite self-destruction. Another important piece of evidence against suicide is the fact that, in some neck ligatures, the rope may be padded by fabric to avoid leaving a telltale mark on the neck – an act incompatible with an intention of suicide.



FIGURE 15.40 *A classical sexual asphyxia where the deceased has used a dog collar round the neck (removed before photography), the chain passing down to the ankles, which provide temporary traction. The common features of rubber fetishism and penile bondage were present.*

Rarely, autoerotic gratification may be achieved by the application of electric current, usually low voltage applied to the genitals. Electrical faults, such as in a transformer, may lead to a fatal outcome.

Medico-legal aspects of the sexual asphyxias

Though all these features make the true nature of the death clear to the medical examiner, it can sometimes be difficult



FIGURE 15.41 *A sexual asphyxia from a buckled belt applied tightly to the neck and a metal shackle on the penis. Obscene phrases were written on the glans and abdomen.*

to convince the police, the coroner or judge – and especially the relatives – that death was accidental. The stigma still attached to suicide and the revulsion felt at the perverted sexual element may cause the relatives to prefer homicide as the cause. The judicial authorities often lean towards suicide, especially when they are unaware of the existence of this strange syndrome of the masochistic or sexual asphyxias. The doctor is often the only person able to explain the relatively common occurrence of this phenomenon and assist in reaching the correct conclusion. It has to be admitted, however, that in a small minority of these deaths, it seems inevitable that the victim must have been aware of the fatal outcome, as the mechanics of the asphyxia are such that no escape could have been foreseen. In these instances the circumstances are such that a mixed motivation must have existed. For example, hanging by the neck in free suspension from a tree or from the trapdoor of an attic is a situation from which escape is impossible, even though sexual attributes such as nudity, bondage and masking were present (Knight 1979).

Where the victim is young, motivation is again less clear. Youths of 12 or 14 years are sometimes found hanged, usually without the secondary sexual or bizarre attributes listed above. There is usually nothing in the history to suggest suicide, and quite often the coroner or other legal authority will decide that death was due to 'experimenting with ropes', sometimes alleging that it followed watching lynching in cowboy films on television. It is probable that most of the obscure deaths are also associated with aberrant sexual activity, even if more positive evidence is lacking. Recognition of the true nature of most of these deaths is vital for the medical examiner, as spurious homicide investigations may be initiated if they are misinterpreted. More commonly a false suicide verdict may result, which can have financial implications in respect of life insurance. A mistaken belief in suicide may be preferred by some families, however, rather than the shame of a publicised sexual aberration.

REFERENCES AND FURTHER READING

Adelson L. 1962. Possible neurological mechanisms for sudden death with minimum anatomical findings. *J Forensic Med* **9**:10–16.

Anscombe AM, Knight BH. 1996. Case report. Delayed death after pressure on the neck: possible causal mechanisms and implications for mode of death in manual strangulation discussed. *Forensic Sci Int* **78**:193–7.

Bockholdt B, Maxeiner H. 2002. Hemorrhages of the tongue in the postmortem diagnostics of strangulation. *Forensic Sci Int* **126**:214–20.

Bohnert M, Faller-Marquardt M, Lutz S, *et al.* 2001. Transfer of biological traces in cases of hanging and ligature strangulation. *Forensic Sci Int* **116**: 107–15.

Bowden KM. 1962. The larynx. *J Forensic Med* **9**:10–16.

Brinkmann B, Koops E, Wischhusen F, *et al.* 1981. [Compression of the neck and arterial obstruction (author's transl).] *Z Rechtsmed* **87**:59–73.

Brouardel P. 1897. *La pendaison, la strangulation, la suffocation, la submersion.* Baillière, Paris.

Byard RW, Bramwell NH. 1988. Autoerotic death in females. An underdiagnosed syndrome? *Am J Forensic Med Pathol* **9**:252–4.

Byard RW, Hucker SJ, Hazelwood RR. 1990. A comparison of typical death scene features in cases of fatal male and autoerotic asphyxia with a review of the literature. *Forensic Sci Int* **48**:113–21.

Byard RW, Hucker SJ, Hazelwood RR. 1993. Fatal and near-fatal autoerotic asphyxial episodes in women. Characteristic features based on a review of nine cases. *Am J Forensic Med Pathol* **14**:70–3.

Camps FE, Hunt AC. 1959. Pressure on the neck. *J Forensic Med* **6**:116–36.

Cooke CT, Cadden GA, Hilton JM. 1988. Unusual hanging deaths. *Am J Forensic Med Pathol* **9**:277–82.

Danto BL. 1980. A case of female autoerotic death. *Am J Forensic Med Pathol* **1**:117–21.

DiMaio VJ. 2000. Homicidal asphyxia. *Am J Forensic Med Pathol* **21**:1–4.

Ditto EWD. 1981. Electrocution during sexual activity. *Am J Forensic Med Pathol* **2**:271–2.

Duflou JA, Lamont DL, Knobel GJ. 1988. Homicide in Cape Town, South Africa. *Am J Forensic Med Pathol* **9**:290–4.

Emson HE. 1983. Accidental hanging in autoeroticism. An unusual case occurring outdoors. *Am J Forensic Med Pathol* **4**:337–40.

Evans KT, Knight B. 1982. *Forensic radiology*. Blackwell Scientific Publications, Oxford.

Ford R. 1957. Death by hanging of adolescents and young adult males. *J Forensic Sci* **2**:171–4.

Gonzalez TA. 1933. Fractures of the larynx. *Arch Pathol* **15**:55–62.

Gordon I, Shapiro HA, Taljaard JJ, *et al.* 1976. Aspects of the hyoid-larynx complex in forensic pathology. *Forensic Sci* **7**:161–70.

Green MA. 1973. Morbid anatomical findings in strangulation. *Forensic Sci* **2**:317–23.

Grellner W, Benecke M. 1997. The quantitative alteration of the DNA content in strangulation marks is an artefact. *Forensic Sci Int* **89**:15–20.

Harm T, Rajs J. 1981. Types of injuries and interrelated conditions of victims and assailants in attempted and homicidal strangulation. *Forensic Sci Int* **18**:101–23.

James R, Nasmyth-Jones R. 1992. The occurrence of cervical fractures in victims of judicial hanging. *Forensic Sci Int* **54**:81–91.

James R, Silcocks P. 1992. Suicidal hanging in Cardiff – a 15-year retrospective study. *Forensic Sci Int* **56**:167–75.

Kennedy NM, Whittington RM, White AC. 1995. Suicide by self-strangulation whilst under observation. *Med Sci Law* **35**:174–7.

Khokhlov VD. 2001. Calculation of tension exerted on a ligature in incomplete hanging. *Forensic Sci Int* **123**:172–7.

Knight B. 1979. Fatal masochism – accident or suicide? *Med Sci Law* **19**:118–20.

Koops VE, Puschel K. 1983. Obstruction of the carotid arteries and upper airway by manual strangulation. In: Holczabek W (ed.), *Beiträge zur gerichtlichen medizin*. Verlag Franz Deuticke, Vienna, vol. XLI.

Kornblum RN. 1986. Medical analysis of police choke holds and general neck trauma. *Trauma* **27**(Part I):760; **28**(Part II):13–64.

Kunnen K, Thomas F, Van der Velde E. 1966. Semimicroradiography of the larynx. *Med Sci Law* **6**:218–19.

Leth P, Vesterby A. 1997. Homicidal hanging masquerading as suicide. *Forensic Sci Int* **85**:65–71.

Lew EO. 1988. Homicidal hanging in a dyadic death. *Am J Forensic Med Pathol* **9**:283–6.

Litman RE, Swearingen C. 1972. Bondage and suicide. *Arch Gen Psychiatry* **27**:80–5.

Luke JL, Reay DT, Eisele JW, *et al.* 1985. Correlation of circumstances with pathological findings in asphyxial deaths by hanging: a prospective study of 61 cases from Seattle, WA. *J Forensic Sci* **30**:1140–7.

Mallach HJ, Pollak S. 1998. [Simulated suicide by hanging after homicidal strangulation.] *Arch Kriminol* **202**:17–28.

Maxeiner H. 1998. 'Hidden' laryngeal injuries in homicidal strangulation: how to detect and interpret these findings. *J Forensic Sci* **43**:784–91.

Michalodimitrakis M, Frangoulis M, Koutselinis A. 1986. Accidental sexual strangulation. *Am J Forensic Med Pathol* **7**:74–5.

Minyard F. 1985. Wrapped to death. Unusual autoerotic death. *Am J Forensic Med Pathol* **6**:151–2.

Muller E, Franke WG, Koch R. 1997. Thyreoglobulin and violent asphyxia. *Forensic Sci Int* **90**:165–70.

Perper JA, Sobel MN. 1981. Identification of fingernail markings in manual strangulation. *Am J Forensic Med Pathol* **2**:45–8.

Pollanen MS. 2001. Subtle fatal manual neck compression. *Med Sci Law* **41**:135–40.

Prinsloo I, Gordon I. 1951. Postmortem dissection artefacts of the neck and their differentiation from ante-mortem bruises. *S Afr Med J* **25**:358–61.

Rajs J, Thiblin I. 2000. Histologic appearance of fractured thyroid cartilage and surrounding tissues. *Forensic Sci Int* **114**:155–66.

Reay DT, Eisele JW. 1982. Death from law enforcement neck holds. *Am J Forensic Med Pathol* **3**:253–8.

Reay DT, Holloway GA, Jr. 1982. Changes in carotid blood flow produced by neck compression. *Am J Forensic Med Pathol* **3**:199–202.

Resnick H. 1972. Eroticised repetitive hangings: a form of selfdestructive behaviour. *Am J Psychother* **26**:4–8.

Reuter F. 1933. *Lehrbuch der gerichtlichen Medizin.* Urban and Schwarzenberg, Berlin.

Rogde S, Hougen HP, Poulsen K. 2001. Asphyxial homicide in two Scandinavian capitals. *Am J Forensic Med Pathol* **22**:128–33.

Rothschild M, Maxeiner H. 1992. [How extensive can injury of the larynx in self-choking be?] *Arch Kriminol* **189**:129–39.

Seabourne A, Seabourne G. 2001. Suicide or accident – self-killing in medieval England: series of 198 cases from the eyre records. *Br J Psychiatry* **178**:42–7.

Shapiro H. 1988. *Strangulation*. In: Gordon F, Shapiro H, Berson S (eds), *Forensic medicine: a guide to principles*, 3rd edn. Churchill, Edinburgh.

Shapiro HA, Gluckman J, Gordon I. 1962. The significance of the nail abrasion of the skin. *J Forensic Med* **9**:17–19.

Simonsen J. 1988. Patho-anatomic findings in neck structures in asphyxiation due to hanging: a survey of 80 cases. *Forensic Sci Int* **38**:83–91.

Simpson CK. 1985. *Forensic medicine*, 9th edn. Arnold, London.

Sivaloganathan S. 1985. Catheteroticum. Fatal late complication following autoerotic practice. *Am J Forensic Med Pathol* **6**:340–2.

Spence MW, Shkrum MJ, Ariss A, *et al.* 1999. Craniocervical injuries in judicial hangings: an anthropologic analysis of six cases. *Am J Forensic Med Pathol* **20**:309–22.

Thomas JE. 1969. Hyperactive carotid sinus reflex and carotid sinus syncope. *Mayo Clin Proc* **44**:127–39.

Walter PF, Crawley IS, Dorney ER. 1978. Carotid sinus hypersensitivity and syncope. *Am J Cardiol* **42**:396–403.

Wesselius CL, Bally R. 1983. A male with autoerotic asphyxia syndrome. *Am J Forensic Med Pathol* **4**:341–4.

Wright RK, Davis J. 1976. Homicidal hanging masquerading as sexual asphyxia. *J Forensic Sci* **21**:387–9.

Yada S, Tsugawa N, Uchida H. 1972. Demonstration of thyroglobulin in the heart blood in fatal cases of strangulation. *Acta Crim Jpn* **38**:60–8.

CHAPTER 16

Immersion deaths

- Signs of immersion 395
- Estimation of duration of immersion 396
- Death from natural causes before entering the water 397
- Natural death whilst in the water 397
- Injuries sustained before entering the water 398
- Injuries sustained in the water 398
- Deaths from immersion other than drowning 399
- Death from drowning 401
- The autopsy signs of drowning 402
- Chemical changes in the blood in drowning 404
- Histological changes in drowning 405
- Diatoms and the diagnosis of drowning 406
- References and further reading 408

Many corpses are recovered from water, but not all have drowned. Of those that have drowned, pathological proof is often difficult or even impossible to obtain. The autopsy diagnosis of drowning presents one of the major problems in forensic medicine, especially when there is delay in recovering the victim.

Bodies retrieved from water may have:

- died from natural disease before falling into the water
- died from natural disease while already in the water
- died from injury before being thrown into the water
- died from injury while in the water
- died from effects of immersion other than drowning
- died from drowning.

All the above may show signs of immersion on examination, but this is rarely helpful, other than confirming that they had indeed been in water. It does not assist in differentiating the mode of death.

SIGNS OF IMMERSION

- Maceration of the skin begins within minutes in warm water, such as death in a bathtub, but in cold water is visible after a variable time, the minimum probably being 4 or 5 hours depending upon temperature. Polson's (1962) experience suggests a much longer time, from 12 to 48 hours, but sodden skin on the hands can undoubtedly occur much earlier than this.

  The first signs tend to be on areas with an appreciable keratin layer (such as the fingertips, palms, backs of the hands and later the soles) where the surface becomes wrinkled, pale and sodden – the so-called 'washerwoman's skin', for obvious reasons. Areas protected by clothing develop these changes later than exposed parts so that the hands usually reveal more marked maceration than the feet during the first few days.

  After prolonged immersion, wide areas of skin assume the same appearance, especially where the stratum corneum is thick or naturally creased, such as the extensor surface of knees and elbows. After some days in warmer water and up to several weeks in cold, the thick keratin of hands and feet becomes detached and eventually peels off in 'glove and stocking' fashion. The nails and hair become loosened at about the same time. Problems of obtaining fingerprints in such circumstances are dealt with later.
- Cutis anserina – or 'goose-flesh' – is a common finding in immersed bodies, but is related to cold rather than warm water. The erector pilae muscles attached to each hair follicle can contract in any type of death and cause a generalized pimpling of the skin. It is often stated that rigor mortis can produce this goose-flesh appearance, but this is doubtful, as rigor does not shorten muscles appreciably. From whatever cause, however, agonal contraction of the erector pilae is common and in immersed bodies has no diagnostic significance.

- The distribution of post-mortem hypostasis is also of no value in immersed bodies. According to Bonte *et al.* (1986), electrocution in the bath seems cause the margin of hypostasis to correspond with the horizontal line of the water level (see Chapter 12). It is usual for most corpses to float or hang in the water with buttocks uppermost, and the head and limbs hanging down, but water movements often roll the body constantly unless in a placid lake or wide river. Other corpses may float upon the back, and gravitational staining of the skin may therefore be in any pattern if the body is subject to frequent changes or posture. The hypostasis of bodies from cold water is frequently pink, but this has no diagnostic value. The reddish colour is caused by the presence of unreduced oxyhaemoglobin in the superficial blood vessels and is the result of cold, whether ante-mortem or post-mortem. It may be seen in any body taken from a mortuary refrigerator or found in a cold environment, irrespective of immersion. In immersion, however, it does not have the typical distribution over extensor surfaces and large joints, nor the rather dusky tinge that is seen in true ante-mortem hypothermia.
- Mud, coal-slurry, oil, silt or sand may be present on or in the body, as well as other artefacts such as seaweed, water weed, algae and small aquatic animal life of many types. Mud may be adherent to the whole body surface and clothing, or may be retained in the hair, mouth, nostrils, ears and other more protected sites. In appropriate circumstances, such deposits should be retained for scientific examination, if they might help establish where the body has travelled from in marine or riverine waters. Sand may be found deep in the respiratory passages and stomach, especially if the body has been rolled by the waves on a beach. Such deep penetration is not evidence of live aspiration. Where a body is decomposed and partly skeletalized, molluscs may colonize the bones. The author (BK) has had several cases recovered from the sea where mussels and barnacles filled the eye sockets and other crevices of the skull.



FIGURE 16.1 *The diagnostic problems associated with bodies recovered from the water. In a death such as this, where a body is left by the falling tide, it may be difficult or even impossible to prove drowning, especially if the post-mortem period is long.*

ESTIMATION OF DURATION OF IMMERSION

This is another difficult problem and one that is often too dogmatically answered by doctors with insufficient experience to appreciate the potential errors. The over-riding variable factor is water temperature, which has the most effect upon decomposition. Water pollution has little to do with speed of putrefaction, as most of the decomposing organisms come from the gut of the body itself.



FIGURE 16.2 *Waterlogged skin ('washer-woman's hands') after 2 weeks' immersion in a temperate climate. Fingerprints can still be obtained from hands like these, with appropriate techniques.*

When a body falls into water in average temperate climates, the following is an approximate guide to timing, in conjunction with the other usual signs, such as rigor:

- if no wrinkling of the finger-pads is present, less than a few hours
- wrinkled fingers, palms and feet, progressively from half a day to 3 days
- early decomposition, often first in the dependent head and neck, abdomen and thighs: 4–10 days
- bloating of face and abdomen with marbling of veins and peeling of epidermis on hands and feet, and slippage of scalp: 2–4 weeks
- gross skin shedding, muscle loss with skeletal exposure, partial liquefaction: 1–2 months.

These times may be reduced or exceeded by wide margins according to animal predation, climatic changes and bodily build.



FIGURE 16.3 *Waterlogged skin after one week's immersion in a cold climate.*



FIGURE 16.4 *Peeling of the epidermis in a 'stocking' fashion after a few weeks' immersion. The rate at which such changes occur is so variable, because of environmental factors, that no timetable can be offered to attempt to date death. In a temperate-zone summer, this stage would require at least 2 weeks and probably much longer.*

DEATH FROM NATURAL CAUSES BEFORE ENTERING THE WATER

This is relatively uncommon, but does occur. The victim may suffer one of the many causes of sudden natural death, most commonly a cardiovascular catastrophe, in circumstances where he involuntarily falls into the water. The last such instance dealt with by the author (BK) was a man returning to his yacht in a rubber dinghy, alone and in the dark. The dinghy was found empty and a search recovered the body, autopsy revealing a well-established myocardial infarct with no evidence of drowning, though the latter is never conclusive. Other instances have involved persons collapsing from natural disease while on boats, a canal tow-path or a river bank.

Of course, in the absence of witnesses it is difficult to separate such cases from those who first fall into the water and then suffer a natural death. The autopsy must be directed towards identifying the pathological lesions and to excluding, as far as is possible, any evidence of drowning.

NATURAL DEATH WHILST IN THE WATER

As discussed above, it may well be impossible to determine whether a person recovered from the water, with a potentially fatal natural disease, suffered this before or after immersion. Because of the problems (to be described later) of positively diagnosing drowning, it is difficult to exclude this as either the primary or contributory cause in someone with a lethal disease.

Cardiovascular disease is the most common reason for death in the water. A pre-existing condition may be exacerbated either by the physical exertion of swimming or struggling, or by the effects of cold. The common belief that swimming after a heavy meal is dangerous probably has some basis in fact, because of circulatory changes such as the 'splanchnic shunt'. When an acute cardiac episode occurs, such as sudden myocardial insufficiency or an arrhythmia, death may follow either from the cardiac lesion itself, or from drowning because of sudden physical incapacity.

INJURIES SUSTAINED BEFORE ENTERING THE WATER

The disposal of a murdered corpse in water is by no means uncommon, as it provides a convenient means of concealing the body, of transporting it from the scene of the crime by means of currents in river or sea, and – if discovery is delayed – of preventing identity by post-mortem decay and damage. Occasionally, accidental or suicidal injuries may be inflicted on a person before he or she enters the water. In marine, air or (rarely) road transport accidents, the victims may be injured or killed before entering the water. Persons falling from docks, bridges or ships may strike masonry or solid obstructions before hitting the water. Suicides may suffer in the same way or in exceptional circumstances, may stab themselves or cut their throats in a position where they fall into water immediately afterwards.

Whatever the means, the difficulties for the pathologist are the same, in that he must try to differentiate them from injuries sustained in the water before death occurs – and from post-mortem injuries. Often this is an impossible task, as such injuries are sustained perimortally, so that the time span involved is far too short for any of the usual criteria of ante-mortem infliction to be applied.

When the nature of the injuries is such that they could not have occurred in water, the issue is clear. Burns, missile wounds, the effect of explosions (other than compression injury) and patterned injuries may be incompatible with infliction in water, and must therefore be related to the effects of a previous assault or some accident on board ship or aircraft.



FIGURE 16.5 *Tying of the legs in a body removed from the water is suspicious, but not absolute proof of foul play. Some suicides who are good swimmers deliberately tie their legs to prevent instinctive self-preservation. In this illustration, however, the bonds were used to secure a heavy weight after homicide.*

INJURIES SUSTAINED IN THE WATER

As stated, this category is often impossible to differentiate from injuries inflicted before entering the water. Trauma in the water is common, as both an ante-mortem and a post-mortem phenomenon. Before drowning or another mode of death can supervene, the victim may be washed by waves or current against any kind of obstruction, from bridge pier to wharf, from rocks to weirs. Contact with the rough bottom of a river or a stony beach is another common cause of trauma. Damage from boats, ship's propellers, and marine or animal predators is frequent.

The issue usually becomes one of attempting to distinguish injuries sustained during life from those after death. Water complicates the problem by washing away surface bleeding from open injuries. A laceration inflicted during life will, however, usually show some bleeding into the tissues under the margins of the wound, at least until post-mortem decomposition blurs the appearances. Many decomposed bodies from water reveal green or black areas under the skin, especially in the scalp. It can be difficult or impossible to decide whether these are areas of altered blood, or merely autolytic changes. Even histological examination is often unhelpful in this respect. A similar problem exists with bruises in a decomposed body, which are often mimicked by discoloured areas of putrefaction. Post-mortem damage from animal predators is common in water and is discussed in the chapter on post-mortem changes.



FIGURE 16.6 *Decomposed head and fractured skull of a person, who disappeared in the autumn before the river was covered with ice. The injuries have possibly been caused post-mortem by the ice packs when the body surfaced in the spring.*

In cold climates, if a body enters the cold water in late autumn, the gas formation due to putrefaction may be so slow that the sea, lake, or river will be covered with ice before the body surfaces and this takes place first in the spring when the ice is melting. In rivers, additional injuries may occur if the body gets pinned down between moving ice blocks.

Internally, there is no particular problem distinct from the examination of injured bodies in general, until post-mortem decomposition begins to obscure the appearances. This is more common in immersed bodies because of the frequent prolonged delays before the body is discovered. Bodies that have been suspended in shallow water may bear post-mortem damage from being dragged against the bottom. A common posture is with the head, hands and knees hanging downwards, so that these areas (especially the backs of the hands) may suffer extensive abrasions against a rough stone or gravel bottom.



FIGURE 16.7 *Marine predator injuries on a body from the sea. The circular defects in the skin are probably made by crustaceans such as crabs.*



FIGURE 16.8 *Post-mortem injury to the back of the hand in a drowned person. Bodies usually hang suspended in the water with the back upwards and the knees, head and arms hanging down. In shallow water these areas may be dragged against the bottom, causing injuries similar to those shown here.*

Damage from the propellers of ships and smaller boats is common in commercial waterways and where pleasure craft abound. The screw of a large vessel may inflict serious damage – even dismemberment – on a body, but more characteristic is that caused by a small, high-speed propeller, such as an outboard motor or the out-drive of a motor cruiser. These injuries are becoming more common with the increase in water-skiing, and the number of other small pleasure boats on rivers, lakes and off beaches. The characteristic lesions are parallel wounds set a few centimetres apart, often of a sliced, undercut incised nature, usually on the head or back.

DEATHS FROM IMMERSION OTHER THAN DROWNING

Irrespective of natural disease or injury, some persons who die after falling into water do not drown, in the accepted physiological sense. The great problem for the pathologist is that, even in true drowning, there may be no autopsy signs, especially if any appreciable delay has occurred before recovery or autopsy, or both. Therefore it may be difficult or impossible for him to say whether a death is a true drowning or one from the non-drowning mechanisms. All that can then be offered is that death was due to 'immersion' – and even then such a diagnosis is usually one reached by exclusion of natural disease, trauma or toxic conditions, using hearsay circumstantial evidence to arrive at a pathological diagnosis. This is why drowning and immersion deaths present one of the most difficult problems for the forensic practitioner.

In certain circumstances, death may be extremely rapid after falling into water, there being insufficient time for drowning to occur. The typical occasion is familiar to any forensic pathologist with a harbour or dockside within his area. A seaman (often the worse for drink) returns to his ship at night, misses the gangway and falls into the water. The night-watchman immediately raises the alarm and the victim is pulled from the water within a minute or two, but is dead. At autopsy, none of the typical signs of drowning are present.

Other witnessed accidents of a similar nature are relatively common, in which rapid, almost instantaneous death must be presumed, in circumstances where true drowning can be excluded by history and lack of autopsy findings. The mechanism must be attributed to a reflex cardiac arrest, of a type similar to 'vasovagal inhibition', which is discussed elsewhere. Powerful stimulation of sensitive nerve endings can induce sudden overactivity of the parasympathetic system, inducing



FIGURE 16.9 *The bifurcation of the trachea and main bronchi at autopsy on a body recovered from a beach. The air passages are full of sand, but this is not proof of vital aspiration of water, as foreign material can enter the bronchi by passive percolation after death.*

bradycardia and triggering cardiac arrest via the tenth cranial nerve nucleus and its vagal outflow. The afferent arc of this reflex varies from case to case, but is probably either:

- sudden immersion in cold water, causing intense stimulation of cutaneous nerve endings. Alcohol is known to potentiate such effects, perhaps by the general vasodilation of skin vessels – which would make the contrast with cold water all the more severe – and possibly by some central effects on the vasomotor centre
- sudden entry of cold water into the pharynx and larynx, and perhaps nasal passages can produce powerful stimulation of nerve endings in the mucosa. A bolus of water entering the trachea can also cause reflex cardiac arrest before there is time for airway insufficiency to have any effect.

As with any reflex cardiac arrest, there will be nothing to find at autopsy, a situation that forces this diagnosis to be speculative and based on the circumstances and exclusion of other conditions. Another mechanism that is often postulated as a cause of non-drowning immersion death is 'laryngeal spasm', leading to a hypoxic death from closure of the airway. The evidence for such a condition is tenuous, as such closure would have to operate for many minutes for hypoxia to kill, all the time keeping the larynx closed to prevent entry of water. Cyanosis is an uncommon feature of immersion deaths and in its absence it is difficult to see how laryngeal spasm could be differentiated from 'dry-lung drowning' or vasovagal cardiac arrest, the latter being a more reasonable diagnosis in those found dead after rapid recovery from the water.

Deaths in the bathtub

Fatalities in the bathroom are common, from a variety of causes, some unconnected with immersion. For example, Schmidt and Madea (1995) reported no fewer than 215 deaths in bathtubs from their Cologne Forensic Institute in 13 years, including 11 homicides.

Many suicides take place in the bathroom, from slashing of the throat or wrists, in or out of the bath. The bathroom cabinet or cupboard commonly holds razors for cutting and medicinal poisons for overdose. Electricity is more likely to be fatal in wet surroundings and a number of self-killings from electricity occur in the bathroom. Accidents include falls on slippery, wet floors or bath lining, with hard ceramic surfaces to cause head injuries.

Where gas appliances are used to heat water, the risk of carbon monoxide toxicity from faulty equipment is greater, as is also the case with electrical appliances such as hair-dryers, heaters and other devices. Although most countries have strict regulations about the electrical supply in bathrooms, people often defeat these safety measures by various means. Natural deaths from many causes may occur in the bathroom, but epileptics having unsupervised baths may have a fit and fall or drown.

Even homicide may be committed in bathrooms, by almost any means, but also from electricity and forcible immersion. The notorious multiple murders of 'The Brides in the Bath' perpetrated by George Joseph Smith early this century were probably accomplished by sudden pulling of the feet of the three women, so that their heads slid under the water. There is now a considerable literature about death in the bathtub, and all deaths in these circumstances must be investigated with particular care.



FIGURE 16.10 *Death in the bath is not uncommon and always requires careful investigation. In this case, the water is blood-stained, due to a suicidal cut throat after committing murder.*

DEATH FROM DROWNING

During the past five decades, views on the mechanism of drowning have undergone a radical change and perhaps the pendulum of opinion has swung a little too far. Until the researches stimulated by the Second World War, when large numbers of seamen and airmen were exposed to the risks of cold water, the classic view of drowning was that the victim was plunged into an airless medium and died of lack of oxygen. Following the experiments of Swann and many others (see below and references and further reading), it was recognized that, in animals, fluid and electrolyte disturbances had a major role in causing acute myocardial failure. The hypoxic element was relegated to such a secondary role that some commentators on drowning seemed to ignore the fact that the victims may have suffered 10 or more minutes without drawing a single breath of air. This criticism by no means disputes the undoubted role of fluid and electrolyte changes in drowning, but the effects of hypoxia must be considered in parallel when discussing the pathophysiology of drowning. The biochemical findings in the experimental animals did not seem to be matched by constant changes in human subjects and, in delayed and near-drowning victims, the electrolyte changes in aspiration have been shown to differ considerably from those in experimental animals.

A number of investigators long before Swann showed that blood and plasma were radically affected by drowning. In 1902, Carrara used specific gravity and other methods to demonstrate marked dilution of left heart blood in freshwater drowning and its absence in seawater, work repeated by Planck the following year with similar density techniques. Freimuth in 1955, however, used such specific gravity methods and found similar differences in non-drowning deaths.

The classical work of Swann and his colleagues (Swann *et al.* 1947; Swann and Spafford 1951) and others was conducted on conscious dogs imprisoned in cages and immersed totally under water – which, as pointed out by Crosfill (1956), does not accurately reflect human drowning, in which submersion is intermittent at first, prolonging the process and altering the physiological effects. In summary, the findings of Swann were that in freshwater drowning there was a massive absorption of water through the alveolar membranes, which could amount to 70 per cent of the original blood volume within 3 minutes. This haemodilution caused a relative anaemia and myocardial hypoxia, as well as rapid overloading of the cardiac capacity by hypervolaemia. It was also suggested that haemolysis of red cells released potassium, a powerful myocardial toxin – yet in dogs, unlike man, sodium is the main electrolyte in the erythrocyte. In fact, because of the hypoxia and haemodilution, there was a fall in plasma potassium and sodium, which led to early ventricular fibrillation in dogs that did not occur in seawater. Such fibrillation is said to be rare in man (Rivers *et al.* 1970).

In seawater the hypertonic medium caused a withdrawal of water from the plasma into the lungs and a rise in plasma sodium concentration. This was less deleterious to heart function and helped to explain the longer survival time in seawater immersion.

Pulmonary oedema developed in both types of aqueous medium but was slight and inconstant and, where abnormal, rapidly returned to normal. Death in freshwater typically took some 4–5 minutes, whilst seawater drowning was delayed for 8–12 minutes. Occasional instances have been reported of remarkably long periods of total submersion in the sea, always in cold water where oxygen uptake is reduced: these periods may exceed 20 minutes, and at least one authenticated survival exceeded 40 minutes.

Modern commentators on the researches of Swann, such as Giamonna and Modell (1967), have pointed out the inconsistencies between animal and human responses, and emphasized the role of hypoxaemia as a result of interference with the blood–air interface in the alveoli. This once again indicates the dangers of transposing the results of animal experiments to man and poses the question of how many dogs died in vain.

THE AUTOPSY SIGNS OF DROWNING

At autopsy much depends on the delay, both in recovering the body from the water and in starting the post-mortem examination. Where a considerable period has elapsed between death and retrieval of the body, the positive signs of drowning progressively fade. Depending on temperature, a period of several days in the water is likely to minimize most changes and, once significant putrefaction has occurred, then (apart from the controversial diatom tests) there is little hope of finding positive signs of drowning.

Even when a fresh body is recovered, delay in performing the autopsy reduces the amount of evidence. The author (BK) has seen several drowned bodies soon after retrieval in which a large plume of froth has been present at the mouth, yet when commencing the autopsy several hours later, such froth had vanished and was present only in the deeper air-passages.



FIGURE 16.11 *Froth exuding from the mouth of a drowned person. Froth disappears with increasing post-mortem interval, though it persists in the internal air-passages for a much longer time.*

Froth in the air passages

The positive signs of drowning, as opposed to mere immersion, are scanty and not absolutely specific. The most useful, has just been mentioned – the presence of frothy fluid in the air passages – which in fresh bodies, often exudes though the mouth and nostrils, sometimes in the form of a plume. The froth is oedema fluid from the lungs, and consists of a proteinaceous exudate and surfactant mixed with the water of the drowning medium. It is usually white, but may be pink or red-tinged, because of slight admixture with blood from intrapulmonary bleeding. It is similar in appearance to the oedema of left ventricular failure that is commonly seen in deaths from cardiac disease such as hypertension, though some drownings exhibit a column of



FIGURE 16.12 *Red-tinged froth exuding from the nostrils of a drowned person.*



FIGURE 16.13 *Frothy fluid in the trachea and main bronchi of a person who was first strangled and subsequently fell or was thrown into sea and drowned.*

froth that is rarely, if ever, seen in natural pulmonary oedema. The froth extends into the trachea, main bronchi and smaller air passages. The lungs themselves in such cases will inevitably be waterlogged, and frothy fluid will exude from the bronchi when the lung is squeezed and from the cut surfaces when they are sectioned with a knife.

Unfortunately, although such oedema can be taken as diagnostic when combined with the appropriate circumstances and lack of other lethal pathology, the absence of waterlogging by no means excludes true drowning. The so-called 'dry-lung drowning' is not uncommon, in which the lungs appear normal in all respects, presumably because all the aspirated water has been absorbed through the alveolar walls into the plasma.

It has been suggested that this is more likely to occur if cardiac arrest takes place after removal from the water or if laryngeal spasm supervenes to prevent further water entry, so that continued circulatory function is able to clear away intra-alveolar fluid into the plasma. This theory, however, often fails to conform to the available facts of the drowning episode.



FIGURE 16.14 *Not all froth around the mouth is from drowning. This lady died in bed from hypertensive heart disease with profuse pulmonary oedema.*

Copeland (1985) measured lung weight in non-drowning deaths and deaths from salt-water and freshwater drowning. There was no significant difference in the weights of the last two, though 10–20 per cent of undoubted drownings were 'dry-lung' cases with no excess weight. Generally, the weights of a lung in drowning were around 600–700 g, whilst the non-drowned were in the 370–540 g range – though there was a considerable overlap in the two groups. The lung weights were also studied by Kringsholm *et al.* (1991) who claimed that the duration of submersion is related to lung weight. They found that 7 per cent of cases were 'dry-lung drownings' with a combined lung weight of less than a kilogram. In the remainder, the average weight of both lungs was 1411 g, compared to 994 g in controls. This was where the body was in the water less than 24 hours. After this, lung weight decreased, but pleural transudate increased. By combining the weight of lungs and transudate, more than 75 per cent of the cases lay between 1000 and 2200 g, up to 30 days.

Overinflation of the lungs

Apart from generalized waterlogging, the lungs may be markedly overinflated, filling the thoracic cavity when the sternum is removed. The normally bare area over the heart may be covered and the lungs may bulge upwards, meeting in the midline to obliterate the anterior mediastinum. The texture is rather pale and crepitant, superficially resembling that shown in asthma – for the same reasons. The older name for this condition is 'emphysema aquosum'. True pre-existing emphysema may partially mimic the distension of drowning, but in the latter, bullae are never present. The oedema fluid in the bronchi blocks the passive collapse that normally occurs at death, holding the lungs in the inspiratory position. In addition, there is often an element of over-distension caused by the valvular action of the bronchial obstruction – again similar to asthma. In drowning this may be sufficient to mark the lateral surfaces of the lungs with the impression of the ribs, leaving visible and palpable grooves after removal of the organs from the thorax. This may be one of the most valuable positive signs of drowning to be gained at autopsy.

There may be some areas of intrapulmonary haemorrhage, which give the red tinge to the oedema fluid. These areas are seldom large or intense, and the general oedema and distension tend to minimize their prominence. Some may lie near the pleural surface and can be seen as rather blurred blotches on the exterior of the lung, the blurring being partly the result of spreading haemolysis. There are almost never subpleural petechial haemorrhages in drowning, apart from the few non-specific spots that can be found in the fissures and around the hilum in virtually every autopsy, no matter what the cause of death.



FIGURE 16.15 *Overinflation of the lungs (emphysema aquosum) in drowning with overlapping of the anterior margins and haemorrhages in the right middle lobe.*



FIGURE 16.16 *A typical plume of froth from the mouth of a recently drowned boy. This will vanish as the post-mortem interval extends.*

Other organs in drowning

There are no other reliable autopsy changes in drowning. The heart and great veins have often been said to be 'dilated and engorged with fluid blood, especially the right side', but this is such a subjective and non-specific finding as to be useless, meriting no further consideration.

Many pathologists have for centuries claimed that the blood remains more fluid in drowning, and the physiological researchers of this century have confirmed the haemodilution in freshwater drowning. As a gross sign at autopsy, however, it is totally subjective and unreliable.

The stomach may contain watery fluid or even foreign material from the water, such as silt, weed or sand, but this cannot be accepted as a positive aid to the diagnosis. Many undoubted drownings show no water in the stomach, yet other cases in which a dead body was immersed reveal copious water in the stomach. The limiting factor is the tone in the oesophagus and cardiac sphincter, not the drowning process. The same applies to foreign materials in the trachea. Haemorrhage into the middle ears has been postulated as a positive sign of drowning, but in the author's (BK) own experience, it is totally unreliable. It can occur in any type of death where drowning can be definitely excluded, yet in classic instances of drowning, such bleeding may be absent. It has been said to be related to the depth to which the body sinks because of the hydrostatic pressure within the ear, but even this does not accord with the experience of most pathologists (Niles 1963).

CHEMICAL CHANGES IN THE BLOOD IN DROWNING

Because of the marked haemodilution that occurs in freshwater drowning and the electrolyte shifts in salt-water drowning, it is reasonable to expect that chemical analyses of the plasma should provide reliable evidence of drowning. Unfortunately, these theoretical hopes have not been realized in practice, mainly because of the biochemical chaos that occurs soon after death from any cause, in which the ability of live cell membranes to partition fluid and electrolytes is rapidly lost. Gettler (1921) published results of analyses of chloride content from the left and right sides of the heart, suggesting that the haemodilution from freshwater drowning would differentially reduce the plasma concentration on the left side, a difference of 25 mg/100 ml being significant. Salt-water drowning was said to produce the opposite effect. Gettler's claims have often been refuted and they are now no longer accepted. It has been shown that post-mortem changes in blood chloride concentrations occur irrespective of drowning and that the rate of change may be different on each side of the heart. Even the differentiation between freshwater and seawater drowning was discredited by the work of Durlacher *et al.* (1953), who found no reliable changes in sodium, potassium and chloride concentration. Similar results were found by Fuller (1963).

Electrolyte measurements in surviving victims of near-drowning showed no regular pattern, according to Rivers *et al.* (1970). Moritz (1944) attempted to use magnesium



FIGURE 16.17 *Bilateral haemorrhages within the petrous temporal bones in drowning. Though claims have been made for the usefulness of this observation, its occurrence seems random, sometimes being present in non-drowning and absent in proven drowning.*



FIGURE 16.18 *Suicide in the bath. The head was enveloped in a plastic bag and an (unused) electrocution device was also present, illustrating the frequent presence of alternative methods in suicide.*

as a similar marker in drowning, but the unreliability of such analyses has prevented their being used as a routine procedure. Once again, the hazards of extrapolating the results of animal experiments to humans is highlighted by these results, as even other mammals like dogs have quite different responses to the same environmental changes.

Other chemical substances have been used as markers of drowning, such as strontium. Azparren *et al.* (1994) claim that differences in the strontium concentration of blood from left and right heart are always greater than 75 μg/l in seawater drowning.

HISTOLOGICAL CHANGES IN DROWNING

Much has been written about both light and electron microscopy of the lungs in immersion deaths, especially in continental Europe. The accounts are confusing, however, and sometimes contradictory, the consensus of opinion being that such changes are inconstant and unreliable.

Much of the work has tried to confirm histologically the genuineness of 'emphysema aquosum' in both fresh and decayed bodies, but the dilatation and rupture of the terminal air spaces can occur not only as a result of drowning, but of passive immersion in water deeper than 4 m. Dilatation of the alveoli, thinning of the walls and compression of the capillaries are easy to observe, but the significance is always ambiguous. Reh (1976) classified such lungs on the basis of reticulin fibres, but Heinen and Dotzauer (1973) showed similar changes in undrowned material. Janssen (1984) has reviewed the subject and concludes that though histological evidence may be helpful and indicative, it is never probative.

The number of macrophages in the alveoli, adjusted to the size of the alveoli where distended, was studied by Betz *et al.* (1993), who claimed a diagnostic usefulness of the method as long as no autolytic changes were present.

The weight of the spleen has been used by Haffner *et al.* (1994) as a diagnostic marker in drowning. Compared with other modes of 'asphyxia', about an 18 per cent reduction in weights and spleen–liver ratios was recorded, with a suggestion that stress, hypoxia, alcohol and cooling were responsible.

The skin changes in maceration are also well recorded, and some have been claimed to have use in dating the period of immersion (Okros 1938; Dierkes 1938). Schleyer (1951) is pessimistic on the reliability of such histological criteria.

The early formation of adipocere can be detected microscopically after 3–4 weeks; this is dealt with in the chapter on post-mortem changes.

DIATOMS AND THE DIAGNOSIS OF DROWNING

Few topics in forensic pathology have given rise to so much argument as the use of diatoms in the diagnosis of drowning. Revenstorf in 1904 was the first to attempt to use diatoms as a test for drowning, though he stated that Hofmann in 1896 was the first to discover them in lung fluid. An excellent review of the diatom controversy was published by Peabody in 1980.

The basic premise is that when a live person is drowned in water containing diatoms (microscopic algae with a silicaceous exoskeleton), many diatoms will penetrate the alveolar walls and be carried to distant target organs such as brain, kidney, liver, and bone marrow. After autopsy, samples of these organs can be digested with strong acid to dissolve the soft tissue, thus leaving the highly resistant diatom skeletons to be identified under the microscope. Alternatively, blood can be used to seek the organisms.

When a dead body is deposited in water or when death in the water is not due to drowning, then, although diatoms may reach the lungs by passive percolation, the absence of a beating heart prevents circulation of diatoms to distant organs.

The great advantage of the diatom test, if it was reliable, would be that a positive diagnosis of drowning could be



FIGURE 16.19 *The principle of the diatom test for drowning. When a dead body enters the water, diatoms cannot progress further than the lungs.*

made even in the frequently putrefied bodies that are recovered, where no hope of anatomical recognition of drowning is possible. In addition, evidence of the site of the drowning might be obtained from the ecological typing of the diatoms, especially in relation to salt-water or freshwater locations.

Meticulous attention to technique must be employed at autopsy to recover suitable samples of tissue, which must not be contaminated by the body surface or instruments, before digestion is commenced. (Technical details are given in Appendix 1.)

Diatoms belong to the class of plants known as *Diatomaceae* and consist of a box or 'frustule' composed of two valves that fit together to enclose the cytoplasmic contents. They have either radial symmetry ('centric' diatoms) or are elongated ('pennate' diatoms). The valves are highly complex in shape and are extremely resistant to decay, fossil diatoms from Jurassic times being abundant. The floor of the oceans have an area of 11 million square miles of thick diatomaceous ooze and upraised beds on land may be hundreds of feet thick, which emphasizes the vast amount of potential contaminant available.



FIGURE 16.20 *Diatoms seen under dark-ground illumination (original magnification ×350). These are from fresh water. There are at least 10 000 different types and, where identification of locus of likely origin is required, the help of a biologist with expert knowledge is essential.*



FIGURE 16.21 *Scanning electron micrograph of a diatom (original magnification ×4000, 20 kV).*

There are at least 10 000 species, and the identification of the various types is a matter for an experienced botanist or biologist, but the following general classification is useful: 'oligohalophilic' diatoms live in freshwater with a salinity less than 0.05 per cent, and 'mesohalophilic' and 'polyhalophilic' diatoms live in brackish water and seawater with a salinity higher than 0.05 per cent.

The critics of the diatom test point to certain problems:

- Diatoms are ubiquitous, being present in soil, water supplies and in the air. Many commonly used minerals, such as kieselguhr, are largely fossil diatoms. Manufactured substances like board-chalk and abrasives – even toothpaste – contain diatomaceous raw materials. Mant, however, examined the filters of the air-conditioning system of Guy's Hospital in London and found no diatoms taken from the city atmosphere.
- Though entry into the body is thought to be mainly through the lungs, there seems no reason why they cannot penetrate the intestinal lining, and gain access to the bloodstream and hence any body tissues.
- Certain foods, notably shellfish, contain vast quantities of diatoms that may enter the circulation and reach the tissues.
- Examination of the tissues of both animals and man reveal the presence of diatoms when the cause of death is other than drowning. Schellmann and Sperl (1979) found them in the tissues of 15 out of 16 non-drowned bodies, but other workers found no diatoms in 33 out of 34 bodies, including two drownings.

Foged (1983) made a detailed investigation into drowned and non-drowned bodies in Denmark, and concluded that the diatom test was quite invalid. He quoted many references both for and against the reliability of the technique, and no doubt the controversy will continue. It seems probable that there may be a quantitative difference between the numbers of diatoms recovered from the tissues in drowning and non-drowning deaths, and a careful analysis of the species identification in relation to the locus and circumstances of the death may be useful. At the present time the diatom test should be used only as an indicative aid and not as legal proof of drowning. Recently, other water organisms have been advocated as tests for drowning, including soft-bodied protozoa and crustaceans.

Japanese workers have used other methods to digest autopsy tissues to seek diatoms because it has been shown that strong acid digestion markedly reduces the yield. The new methods introduced for diatoms, such as enzymatic and detergent digestion, allowed soft-bodied microscopic organisms to be recovered and claims for better specificity for drowning have been made (Matsumoto and Fukui 1993; Funayama *et al.* 1987, 2001). Chinese workers have claimed that the spectrofluorophotometric detection in the lungs of chlorophyll derived from plankton is diagnostic, but it is not clear how this can be differentiated from plankton passively entering the lungs after death (Qu and Wang 1992).

REFERENCES AND FURTHER READING

Auer A, Mottonen M. 1988. Diatoms and drowning. *Z Rechtsmed* **101**:87–98.

Azparren J, de la Rosa I, Sancho M. 1994. Biventricular measurement of blood strontium in real cases of drowning. *Forensic Sci Int* **69**:139–48.

Betz P, Nerlich A, Penning R, *et al.* 1993. Alveolar macrophages and the diagnosis of drowning. *Forensic Sci Int* **62**:217–24.

Bhaskar GR. 1965. Diatoms in cases of drowning. *J Indian Acad Forensic Sci* **4**:2–6.

Bonilla-Santiago J, Fill WL. 1978. Sand aspiration in drowning and near drowning. *Radiology* **128**:301–2.

Bonte W, Sprung R, Huckenbeck W. 1986. [Problems in the evaluation of electrocution fatalities in the bathtub.] Probleme bei der Beurteilungen von Stromtodesfällen in der Badewanne. *Z Rechtsmed* **97**:7–9.

Bray M. 1985. Chemical estimation of fresh water immersion intervals. *Am J Forensic Med Pathol* **6**:133–9.

Budnick LD. 1984. Bathtub-related electrocutions in the United States, 1979 to 1982. *JAMA* **252**:918–20.

Budnick LD, Ross DA. 1985. Bathtub-related drownings in the United States, 1979–81. *Am J Public Health* **75**:630–3.

Byard RW, Lipsett J. 1999. Drowning deaths in toddlers and preambulatory children in South Australia. *Am J Forensic Med Pathol* **20**:328–32.

Carrara M. 1902. Electrolytes and osmotic pressure in drowning. *Vrtlschr Gericht Med* **24**:236–40.

Chiaraviglio E, del Carmen, Wolf AV. 1963. Diagnosis of drowning. *Arch Pathol* **75**:337.

Copeland AR. 1985. An assessment of lung weights in drowning cases. The metro Dade County experience from 1978 to 1982. *Am J Forensic Med Pathol* **6**:301–4.

Copeland AR. 1986. Homicidal drowning. *Forensic Sci Int* **31**:247–52.

Copeland AR. 1987. Suicide by drowning. *Am J Forensic Med Pathol* **8**:18–22.

Coutselinis A, Boukis D. 1976. The estimation of Mg^{2+} concentration in cerebrospinal fluid (C.S.F.) as a method of drowning diagnosis in sea water. *Forensic Sci* **7**:109–11.

Crosfill JW. 1956. Mechanism of drowning. *Proc R Soc Med* **49**:1051–4.

Davis JH. 1961. Fatal underwater breath holding in trained swimmers. *J Forensic Sci* **6**:391–6.

Davis JH. 1986. Bodies found in the water. An investigative approach. *Am J Forensic Med Pathol* **7**:291–7.

Devos C, Timperman J, Piette M. 1985. Deaths in the bath. *Med Sci Law* **25**:189–200.

Dierkes K. 1938. Über die Histologie der Waschhaut. *Dtsch Z Gesamte Gerichtl Med* **30**:262.

Durlacher S, Freimuth H, Swan H. 1953. Blood changes in man following drowning. *Arch Pathol* **56**:454–60.

Durwald W. 1964. Elektrotodesfälle in der Badewanne. *Arch Kriminol* **134**:164–71.

Foged N. 1983. Diatoms and drowning – once more. *Forensic Sci Int* **21**:153–9.

Fornes P, Pepin G, Heudes D, *et al.* 1998. Diagnosis of drowning by combined computer-assisted histomorphometry of lungs with blood strontium determination. *J Forensic Sci* **43**:772–6.

Foroughi E. 1971. Serum changes in drowning. *J Forensic Sci* **16**:269–82.

Fukui Y, Hata M, Takahashi S, *et al.* 1980. A new method for detecting diatoms in human organs. *Forensic Sci Int* **16**:67–74.

Fuller RH. 1963. The clinical pathology of human near-drowning. *Proc R Soc Med* **56**:33–8.

Funayama M, Aoki Y, Sebetan IM, *et al.* 1987. Detection of diatoms in blood by a combination of membrane filtering and chemical digestion. *Forensic Sci Int* **34**:175–82.

Funayama M, Mimasaka S, Nata M, *et al.* 2001. Diatom numbers around the continental shelf break. *Am J Forensic Med Pathol* **22**:236–8.

Gardner E. 1944. Death in the bathroom. *Med Leg Criminol Rev* **12**:180–95.

Geertinger P, Voigt J. 1970. Death in the bath. A survey of bathtub deaths in Copenhagen, Denmark, and Gothenburg, Sweden, from 1961 to 1969. *J Forensic Med* **17**:136–47.

Gettler AO. 1921. A method for the determination of death by drowning. *JAMA* **77**:1650–2.

Giammona ST, Modell JH. 1967. Drowning by total immersion. Effects on pulmonary surfactant of distilled water, isotonic saline, and sea water. *Am J Dis Child* **114**:612–16.

Goldhahn RT. 1977. *Scuba diving deaths; a review and approach for the pathologist.* In: Wecht C (ed.), *Legal medicine annual 1976*. Appleton Century Crofts, New York.

Gooden BA. 1972. Drowning and the diving reflex in man. *Med J Aust* **59**:583–7.

Gordon I. 1972. The anatomical signs in drowning. A critical evaluation. *Forensic Sci* **1**:389–95.

Gruspier KL, Pollanen MS. 2000. Limbs found in water: investigation using anthropological analysis and the diatom test. *Forensic Sci Int* **112**:1–9.

Haffner HT, Graw M, Erdelkamp J. 1994. Spleen findings in drowning. *Forensic Sci Int* **66**:95–104.

Heinen M, Dotzauer G. 1973. [The lung of a drowned person.] *Beitr Gerichtl Med* **30**:133–41.

Hendey NI. 1973. The diagnostic value of diatoms in cases of drowning. *Med Sci Law* **13**:23–34.

Holden HS, Crosfill JW. 1955. The significance of foreign bodies in the alveoli of the apparently drowned. *J Forensic Med* **2**:141–50.

Hurlimann J, Feer P, Elber F, *et al.* 2000. Diatom detection in the diagnosis of death by drowning. *Int J Legal Med* **114**:6–14.

Jääskeläinen A. 1967. Diatomenbefunde in Wasserleichen. *Dtsch Z Gesamte Gerichtl Med* **61**:41–7.

Janssen W. 1984. *Forensic histopathology.* Springer, Heidelberg, Germany.

Karkola K, Neittaanmaki H. 1981. Diagnosis of drowning by investigation of left heart blood. *Forensic Sci Int* **18**:149–53.

Knight B. 1981. Immersion or drowning? *Br Med J* **282**:1340–1.

Kobayashi M, Yamada Y, Zhang WD, *et al.* 1993. Novel detection of plankton from lung tissue by enzymatic digestion method. *Forensic Sci Int* **60**:81–90.

Koseki T. 1969. Investigations on the bone marrow as a material in the diatom method diagnosing of death from drowning. *Acta Med Biol* **16**:88–90.

Kringsholm B, Filskov A, Kock K. 1991. Autopsied cases of drowning in Denmark 1987–1989. *Forensic Sci Int* **52**:85–92.

Kvittingen TD, Naess A. 1963. Recovery from drowning in fresh water. *Br Med J* **1**:1315–16.

Lucas J, Goldfeder LB, Gill JR. 2002. Bodies found in the waterways of New York City. *J Forensic Sci* **47**:137–41.

Ludes B, Coste M, North N, *et al.* 1999. Diatom analysis in victim's tissues as an indicator of the site of drowning. *Int J Legal Med* **112**:163–6.

Matsumoto H, Fukui Y. 1993. A simple method for diatom detection in drowning. *Forensic Sci Int* **60**:91–5.

Mikami Y. 1959. Experimental study and practice on the detection of vegetable planktons in the bone marrow of the drowned dead body. *Acta Med Okayama* **13**:259–67.

Modell JH. 1968. The pathophysiology and treatment of drowning. *Acta Anaesthesiol Scand Suppl* **29**:263–79.

Modell JH. 1971. *Drowning and near-drowning.* Thomas, Springfield, USA.

Modell JH. 1978. Biology of drowning. *Annu Rev Med* **29**:1–8.

Modell JH, Davis JH. 1969. Electrolyte changes in human drowning victims. *Anesthesiology* **30**:414–20.

Monantay NK, Rao RD. 1964. The diagnosis of death from drowning with particular reference to 'diatom method'. *J Indian Acad Forensic Sci* **3**:21–7.

Moritz AR. 1944. Chemical methods for the determination of death by drowning. *Physiol Rev* **24**:70–88.

Mueller WF. 1969. Pathology of temporal bone hemorrhage in drowning. *J Forensic Sci* **14**:327–36.

Niles NR. 1963. Haemorrhage in the middle ear and mastoid in drowning. *Am J Clin Pathol* **40**:281–4.

Ohlsson K, Beckman N. 1964. Drowning – reflections based on two cases. *Acta Chir Scand* **128**:327–31.

Okros S. 1938. Annähernde Bestimmung der Todeszeit aus dem Hautzustand. *Dtsch Z Gesamte Gerichtl Med* **29**:497.

Pachar JV, Cameron JM. 1993. The diagnosis of drowning by quantitative and qualitative diatom analysis. *Med Sci Law* **33**:291–9.

Peabody AJ. 1980. Diatoms and drowning – a review. *Med Sci Law* **20**:254–61.

Peabody AJ. 1986. *Drowning cases: a protocol for their submission*. CRE, Aldermaston.

Pearn J. 1985. Pathophysiology of drowning. *Med J Aust* **142**:586–8.

Pearn J, Nixon J. 1977. Bathtub immersion accidents involving children. *Med J Aust* **64**:211–13.

Pearn JH, Brown JD, Wong R, *et al.* 1979. Bathtub drownings: report of seven cases. *Pediatrics* **64**:68–70.

Pollanen MS. 1998. Diatoms and homicide. *Forensic Sci Int* **91**:29–34.

Polson CJ. 1962. *Essentials of forensic medicine.* Pergamon Press, Oxford.

Qu J, Wang E. 1992. A study on the diagnosis of drowning by examination of lung chlorophyll(a) of planktons with a spectrofluorophotometer. *Forensic Sci Int* **53**:149–55.

Reh H. 1976. [About the problem of 'lungs in drowning' (author's transl).] *Z Rechtsmed* **77**:219–21.

Rivers J, Orr G, Lee H. 1970. Electrolytes in near-drowning. *Br Med J* **2**:157–60.

Rushton DG. 1961. Drowning – a review. *Med Leg J* **29**:90–8.

Schellmann B, Sperl W. 1979. [Detection of diatoms in bone marrow (femur) of nondrowned (author's transl).] *Z Rechtsmed* **83**:319–24.

Schleyer F. 1951. Zur Histologie der Waschhaut. *Dtsch Z Gesamte Gerichtl Med* **40**:680.

Schmidt P, Madea B. 1995. Homicide in the bathtub. *Forensic Sci Int* **72**:135–46.

Schmidt P, Madea B. 1995. Death in the bathtub involving children. *Forensic Sci Int* **72**:147–55.

Schneider V. 1985. [Electrocution in the bathtub.] *Arch Kriminol* **176**:89–95.

Schwar TG. 1972. Drowning: its chemical diagnosis. A review. *Forensic Sci* **1**:411–17.

Schwerd W, Lautenbach L. 1960. Mord mit elektrischem Strom in der Badewanne. *Arch Kriminol* **54**:126–49.

Sidari L, Di Nunno N, Costantinides F, *et al.* 1999. Diatom test with soluene-350 to diagnose drowning in sea water. *Forensic Sci Int* **103**:61–5.

Spitz W, Schneider V. 1964. The significance of diatoms in the diagnosis of death by drowning. *J Forensic Sci* **9**:11–18.

Sturner WQ, Balko A, Sullivan J. 1976. Magnesium and other electrolytes in bovine eyeballs immersed in sea water and other fluids. *Forensic Sci* **8**:139–50.

Swann HG. 1956. Mechanism of circulatory failure in fresh water and sea water drowning. *Circ Res* **4**:241–2.

Swann HG, Spafford NR. 1951. Body salt and water changes during fresh and sea water drowning. *Tex Rep Biol Med* **9**:356–62.

Swann HG, Brucer M, Moore C, *et al.* 1947. Fresh water and sea water drowning: a study of terminal cardiac and biochemical events. *Tex Rep Biol Med* **5**:423–37.

Terazawa K, Takatori T. 1980. Isolation of intact plankton from drowning lung tissue by centrifugation in a colloidal silica gradient. *Forensic Sci Int* **16**:63–6.

Thomas F, Van Hecke W, Timperman J. 1961. The detection of diatoms in the bone marrow. *J Forensic Med* **8**:142–4.

Thomas F, Van Hecke W, Timperman J. 1962. [Medicolegal diagnosis of death by submersion by demonstration of diatoms in the marrow of the long bones.] *Ann Med Leg (Paris)* **42**:369–73.

Timperman J. 1962. The detection of diatoms in the marrow of the sternum. *J Forensic Med* **9**:134–6.

Timperman J. 1969. Medico-legal problems in death by drowning. Its diagnosis by the diatom method. A study based on investigations carried out in Ghent over a period of 10 years. *J Forensic Med* **16**:45–75.

Timperman J. 1972. The diagnosis of drowning. A review. *Forensic Sci* **1**:397–409.

Trubner K, Püschel K. 1991. [Fatalities in the bathtub.] Todesfälle in der Badewanne. *Arch Kriminol* **188**:35–46.

CHAPTER 17

Neglect, starvation and hypothermia

- General features of neglect and starvation 412
- Medico-legal problems 414
- Injury caused by cold: hypothermia 414
- The 'hide-and-die' syndrome 418
- Deaths from exposure 419
- Local injury due to cold: frostbite 419
- References and further reading 420

Though, tragically, starvation is one of the most widespread scourges of our planet, we are here concerned with individual neglect with which starvation is often associated, either as a potentially criminal act or as a manifestation of self-neglect. As with so many conditions, the extremes of life are most affected, rather than the middle years. Infants and children are at the mercy of their parents or guardians for the provision of care and sustenance. The old are prey to senile dementias and other disorders of the mind, as well as often being devoid of spouse or caring relatives – or sometimes even the financial means to stay warm and adequately fed.

Many countries have legislation designed to protect children, on the basis that they are totally dependent upon adults for the necessities of life. In Britain, the Children Act places a responsibility upon parents, guardians or the community to care for children. The minimum requirements laid down by law are the provision of food, clothing, shelter and education. Unfortunately, these requirements are evaded in spite of official supervision and, from time to time, scandals explode in the public eye when a child has died, not from physical abuse, but from sheer neglect.

Voluntary organizations, such as the National Society for the Prevention of Cruelty to Children (NSPCC) were founded in the nineteenth century to combat the widespread neglect of children consequent upon the population explosion of the Victorian industrial revolution. Their present-day role, however, has changed radically so that now most of their efforts are directed against physical, sexual and mental abuse, rather than starvation and neglect. Notwithstanding this change of emphasis, deaths still occur from deliberate or negligent lack of provision of proper care and nutrition of children. In general – though there are many exceptions – nutritional neglect and physical battering tend to be mutually exclusive. The abused child is usually well nourished and the emaciated child is usually uninjured.

Neglect and starvation are not synonymous, but are so often closely associated that the two conditions are usually considered together. When fatal, they may come to the attention of the pathologist either as a potentially criminal death or, when self-inflicted, in the usual course of coroners' or similar enquiries. Rarely, victims will starve from being isolated in some catastrophe, such as a mining incarceration or shipwreck, but these days a more common occurrence is a hunger strike or voluntary fast for some political or similar motive.

GENERAL FEATURES OF NEGLECT AND STARVATION

The obvious and outstanding appearance is of emaciation caused by an inadequate intake of food. A minimum of about 1500–1900 calories is needed to maintain body weight in active adults. Life is threatened when more than 40 per cent of the original body weight has been lost, though the speed of loss is relevant. Total deprivation of food will obviously kill faster than a severe reduction. Total lack of food is likely to cause death in about 50–60 days as long as adequate water is available, but this depends on weather and temperature as well as the original fitness – and fatness – of the individual. Deprivation of water will kill in about 10 days – or less in higher ambient temperatures.



FIGURE 17.1 *Death from neglect and hypothermia in an old woman. The discoloration of the feet and hands was cyanotic.*



FIGURE 17.2 *Fatal neglect and starvation in an infant. The limbs are emaciated, the abdomen scaphoid and the head appears relatively large. The back shows extensive pressure ulceration. The sunken eyes and cheeks from malnutrition and dehydration constitute the 'Hippocratic facies'.*

In the numerous cases of fatal and non-fatal starvation seen at the end of the 1939–45 war in Nazi concentration camps, two main types were seen. These were the 'dry' type, in which there was emaciation, but only leg oedema, with a body weight up to half the normal. Alive, these showed marked hypotension, feeble pulse and cyanosis. The other 'wet' group had marked oedema of face, trunk and limbs, with ascites and pleural effusions. The oedema of hypoproteinaemia is caused by protein being diverted to produce energy when carbohydrate and fat are grossly deficient in the diet. In some victims, the skeleton accounted for 50 per cent of the total body weight, instead of the usual 15 per cent.

Other features are secondary to this nutritional deficiency, such as intercurrent infections, avitaminoses, skin disorders and nutritional oedema. Dehydration, hypothermia and actual necrosis of the extremities are the most severe manifestations that contribute to death.

Most fatally neglected infants are under one year of age. At autopsy great care must be taken to measure, not estimate, the full indices of size and weight. Crown–heel, crown–rump, head diameter, foot length and exact weight must be measured accurately, so that comparison may be made with standard paediatric percentile growth charts, consonant with age, birth weight, sex and race.

The diameter of limbs at major landmarks such as wrists and ankle should be measured with a flexible tape. Photographs should be taken in all major views, using colour to record skin tints and lesions, as well as the general aspect of the emaciated body. The words 'cachexia', 'emaciation' and 'marasmus' are all synonymous as used today, though 'marasmus' is confined to the description of infant victims. The so-called 'Hippocratic facies' is not confined to the emaciation of neglect, as cachexia from any cause – such as an obstructive carcinoma of the oesophagus – can give rise to the same appearance. The skin of the face is stretched tightly across the cheekbones, the cheeks are sunken and the lines of the jaw are obtrusive. The eyes are deeply sunken from loss of orbital fat, though dehydration may contribute to this manifestation.

On the trunk the ribs are prominent, with concavities in the intercostal spaces and sunken supraclavicular fossae. The abdomen is of the classical 'scaphoid' shape, being concave from costal margin to iliac crests, the latter sticking up like wings. The limbs are almost skeletal from loss of fat and muscle, and the head may appear deceptively large by contrast with the narrowed neck.

The skin surface may present differing appearances according to the length of time that nutritional loss has been suffered and the qualitative defect in the diet, especially of certain vitamins. The skin may be pale, lustrous and semi-translucent, with an almost blue tinge in infants, partly as a result of the loss of subcutaneous fat. It may also be coarse and rough, however, with flaking hyperkeratosis, though this is more often seen in aged persons, partly as a result of senile changes. Pigmentation, either diffuse or of a punctate nature, is sometimes seen.

Dehydration is a common feature, especially in infants and may be the major contribution to death. The skin is dry and wrinkled and, when pinched between the fingers, remains ridged because of loss of subcutaneous fat and fluid. The fontanelles may be depressed from loss of pressure of cerebrospinal fluid. In chronic starvation, hypoproteinaemia can lead to oedema, though this is rarely seen in forensic practice. In famines it may be widespread, associated with other nutritional disorders such as kwashiorkor.

Skin infections are common, partly as a result of nutritional loss of resistance to infections and partly because of neglect in care and hygiene, especially in infants. Pressure sores on buttocks, heels and spine may occur in both infants and old people who are lying inert because of weakness, and, in infants, urine dermatitis and lack of any skin care after defecation worsens these. Sores may be seen on any pressure or friction points, such as the elbows, knees, shoulders and occiput. Apart from pressure areas, any part of the skin surface may develop infected lesions, which often crust over after partial healing. Sores on the lips, blepharitis and conjunctivitis may also occur. The hair is dry and brittle, sometimes becoming depigmented and even gingery with chronic malnutrition.

Internally, the same loss of adipose tissue will be evident both subcutaneously and in the internal fat stores, such as the omentum, mesentery and perirenal area. The organs will be small (except the brain) and it is therefore important to weigh the major viscera to compare them with standard tables for sex and age. Organ atrophy will be more apparent in old people, but the problem then exists of distinguishing weight loss caused by nutritional defects from the usual senile atrophy. The differentiation is one of degree, as chronic starvation can reduce organs to unusually low weights. More specific internal signs will include an empty gut, which may be gas-filled and translucent from stomach to colon. Any faeces in the rectum are likely to be inspissated, especially if there has been fluid restriction and dehydration. Faecoliths may ulcerate the intestinal lining. In infant starvation, however, the stools may be fluid and offensive unless dehydration was severe. The gall bladder is distended in starvation if there has been no recent meal to stimulate emptying. The tongue may be thickly coated, but this is such a non-specific finding that it is of no practical use.

MEDICO-LEGAL PROBLEMS

In infants there may sometimes, if rarely, be physical abuse associated with neglect, so radiography prior to autopsy is essential – in fact the whole procedure must be conducted on the lines indicated for the 'battered child' (Chapter 22). In both children and adults, a major problem is cause and effect, especially where some pathological disease process is found. Did a cancer lead to cachexia or is it an incidental finding? Did pulmonary tuberculosis cause the emaciation or was the infection secondary to the nutritional deficiency? The relevance of diseases such as diabetes, Addison's disease, chronic infections and neoplasms must be evaluated. Particularly important in children are familial metabolic diseases that may be associated with failure to thrive and frank emaciation.

Where death from a wasting condition is alleged to be the result of malnutrition, either from wilful withholding of food or from indifference about its provision, a defence may be raised against criminal prosecution that the condition was caused by a natural disease. Indeed, such a claim may be true on occasions. Both the prosecution and defence medical advisers must undertake a thorough investigation using all anatomical, histological and biochemical means at their disposal to discover any such metabolic or pathological cause for fatal wasting, before attributing the death to sheer malnutrition.

INJURY CAUSED BY COLD: HYPOTHERMIA

Until about 40 years ago, injury and death from the effects of low temperature was thought to occur almost exclusively among those subjected to extremes of climate out of doors. Mountaineers, polar explorers and those exposed in some disaster on sea or land were considered to be the prime candidates for frostbite and 'freezing to death'. Only after some noteworthy medical publications, such as those by



FIGURE 17.3 *Hypothermia in a woman of only 56. She lived in extreme squalor, with no heating and broken windows, even though she had been a state registered nurse. The knees, hands and feet showed hypothermic discoloration as well as dirt.*

Emslie-Smith (1958), Duguid *et al.* (1961) and others, was it generally appreciated that hypothermia was a common and widespread danger in temperate climates and indoors. Recognition was rapid and Special Committees of both the Royal College of Physicians and the British Medical Association produced reports on hypothermia in the 1960s.

As in so many other conditions, the aged and the infants are most vulnerable, especially as the condition is insidious and may not be suspected in time by those more active persons who are the potential guardians of those at the two extremes of life.



FIGURE 17.4 *A death from hypothermia showing brownish-pink discoloration over the hip and elbow.*

Factors involved in hypothermia

LOW ENVIRONMENTAL TEMPERATURE

No precise figures can be given in degrees Celsius for temperatures potentially dangerous to life, as other factors and the personal vulnerability of different individuals vary considerably. Certainly the air temperature need be nothing like as low as was thought in former years, when profound frost was considered essential for the production of lesions. Air temperatures below 10°C are probably low enough to cause hypothermia in vulnerable persons, but air movements such as external wind or internal draughts will make things worse by markedly increasing the rate of body cooling. Damp conditions, especially of clothing, will also aid cooling from the latent heat of evaporation.

AGE AND PHYSIQUE

As stated, the elderly and the young are at greatest risk. The old person may have poor musculature and a lack of mobility, thus depressing heat production from muscular activity. Often thin, there may be a lack of insulating subcutaneous fat. Poor thyroid function is common, especially in old women, and is discussed below. Cerebral dysfunction – often from degenerative arterial disease – may lead to poor central heat regulation, a disinclination to move around, and apathy concerning personal nutrition, heating and general well-being. Depression and mental illness are not uncommon, as in the early cases reported by Emslie-Smith and by Duguid *et al.*

In infants, the body mass is small and the surface area:mass ratio large, so that heat is lost more easily. In small infants, there is naturally complete dependence on others in regard to clothing and environment.

HYPOTHYROIDISM

Myxoedema, either occult or obvious, is an important factor in hypothermia. Many elderly women have a thyroid deficiency and this is a potent factor in vulnerability to cold. The majority of victims are women over 70 and the environmental conditions in which thyroid dysfunction is a factor may be little below optimum. Cases were first reported in the 1950s by Marquand, soon followed by the paper of Angel and Sash (1960). In hypothyroid subjects, certain drugs may have a deleterious effect by precipitating hypothermia, even when the environment is relatively normal. Imipramine, chlorpromazine and diazepam are particularly hazardous. Barbiturates, phenothiazines and alcohol are also dangerous in this respect.

LACK OF FOOD, ADEQUATE CLOTHING AND INDOOR HEATING

These are factors that may be social or financial, but are often related to the depressed, apathetic state of many old people, especially those with cerebral atherosclerosis. Cause and effect are often hard to separate, as the effects of cold may bring on or worsen mental sluggishness and confusion.

The manifestations of hypothermia

The clinical manifestations are not the concern of the forensic pathologist, though when unsuspected before autopsy the history may give a clue to the fatal process.

It is sometimes claimed that hypothermia in the elderly never occurs unless there is some predisposing disability, such as cerebrovascular disease, hypothyroidism, alcoholism or diabetes, for instance. This seems too restrictive an attitude, though in general is probably true. The rectal temperature is used as the measure of severity in hypothermia. Between 37°C and 32°C there are no ill-effects beyond the normal subjective feeling of being cold, with shivering and constriction of blood vessels.



FIGURE 17.5 *Frostbite of the knuckles after being left unconscious during winter in Wales. It does not require Arctic temperatures to cause tissue damage or death.*

When the core temperature falls further below 32°C to 24°C, there is dulling of consciousness, a fall in respiration and heart rate, and a lowering of blood pressure. If maintained without relief, death will ensue and recovery is rare if the rectal temperature falls below about 26°C, though one remarkable case reported by Laufman (1951) recovered after falling to 18°C, albeit with severe mutilating frostbite.

Autopsy findings in hypothermia

There may be no signs whatsoever at autopsy in a death from hypothermia and thus the history may be all-important. The usual difficulties then arise as to how much the pathologist is entitled to rely upon hearsay evidence – as opposed to the objective findings of his own examination – when deciding on a cause of death. This is more fully discussed in the first chapter of this book.

Hypothermia, like some cases of epilepsy, asthma and drowning, provides some of the more difficult pathological dilemmas when there are slight, non-specific or absent autopsy findings. When a victim of hypothermia has been admitted to hospital and 'warmed-up', death may supervene at any time up to a few days later. In such circumstances the autopsy may reveal no positive findings. The skin changes will almost certainly be absent, but intra-abdominal signs may persist.

In a classical death from hypothermia the body will usually be that of an old person – almost half the Royal College of Physicians' series was over 65 years of age; most will be women. The exterior of the body may present suggestive



FIGURE 17.6 *Bright red discoloration of the cheeks and nose from hypothermia. The victim suffered from mitral stenosis (where malar flush is one of the clinical signs) and was in bed in an unheated room during a Welsh winter. The tissues of the nose were virtually necrotic, amounting to actual frostbite.*

signs of hypothermia, in that patches of pink to brownish-pink discoloration may be seen in certain areas. They are most often present over extensor surfaces and large joints, such as the outer sides of the hips, the elbows and the knees, and less often on the flanks and face.

The colour is similar to that seen in bodies exposed in cold water or in severe outdoor cold – and to the post-mortem pinkness that often develops in mortuary refrigerators. In hypothermia, however, the distribution over the large joints is distinctive, in addition to the pinkness of hypostasis. There may be pink patches on the cheeks, chin and nose, especially in victims who already had impaired cardiac function, such as the 'malar' flush of mitral stenosis. The slight brownish tinge often seen in the pinkness and the rather indefinite blurred edges of the patches suggest that some haemolysis may have occurred, perhaps in the early post-mortem period as well as during the terminal stages of life. The colour is presumably due to persistent oxyhaemoglobin in the skin capillaries, which, because of the low metabolic activity of the cold tissues, fail to take up the delivered oxygen. Pooling of blood in surface vessels from the breakdown of normal vasomotor control allows this unreduced haemoglobin to show through the skin. Why a normally coloured body placed after death in a mortuary refrigerator should also become pink has never been satisfactorily explained.

In addition to pink areas of skin, the extremities may be cyanosed or they may be white. Sometimes the feet are blue to the ankles, above which is pale. The hands may show blueness of the fingers or nail beds. Oedema may be seen, most often in the feet and lower legs, but many of the victims of hypothermia already have pre-existing congestive cardiac failure. Rarely there may be blistering of the skin, usually in dependent parts such as the buttocks, backs of thighs and



FIGURE 17.7 *Fatal child neglect. The infant has extensive skin ulceration and was underweight. Death was the result of an intercurrent chest infection.*



FIGURE 17.8 *This infant died of neglect, hypothermia and frostbite, having been left in an unheated farmhouse bedroom, the cardboard box that acted as a cot having crystals of frozen urine in the bedclothes. After death the child was dropped down the farm well in this sack with a brick as a weight.*

upper arms. This may or may not be in pink areas and seems to be caused by skin oedema which then breaks down.

The face, especially of an elderly woman, may show appearances suggestive of myxoedema or hypothyroidism, with coarsening of the features, puffy eyelids and loss of eyebrow hair. Internally there may be nothing specific to note, even if the external skin changes are obvious. Signs of pre-existing disease are common, especially if one subscribes to the view that hypothermia in the elderly never occurs in the absence of systemic disease. Degenerative arterial disease, senile myocardial degeneration, hypertension, chronic renal lesions and obstructive airways disease are common. More specific lesions are considered below.

ACUTE GASTRIC EROSIONS

In the authors' view, these are found much more often than pancreatitis. The stomach mucosa is frequently studded with numerous shallow ulcers, the floor of each containing a dark brown plug of altered blood. Frank haematemesis is rare, but the stomach contents sometimes contain dark acid-affected blood.

ACUTE PANCREATITIS

This is the lesion most often quoted in textbooks, but is present in less than half the deaths from proven hypothermia. It may have been diagnosed before death from an increase in serum amylase activity. The most obvious feature may be areas of stiff, yellow, fat necrosis when the pancreas is sectioned at autopsy. There may be adjacent areas of fat necrosis in the omentum and mesentery. Haemorrhage into the gland may occur, but caution has to be employed here, as post-mortem autolysis of this organ commonly gives a haemorrhagic appearance in many other modes of death seen at autopsy. Histologically, necrosis, leucocyte infiltration and fat necrosis may be confirmed in some instances, but in others the pancreas, even if haemorrhagic, yields little information on microscopy.



FIGURE 17.9 *Gastric mucosa from a hypothermia death showing numerous acute erosions.*

PULMONARY OEDEMA

This is common, but as it is such a common finding in any death from cardiac failure, its diagnostic value in hypothermia is almost nil.

PERIVASCULAR HAEMORRHAGES

These have been described in the brain, especially in the walls of the third ventricle, but again they are not particularly specific, especially in an autopsy population that has a high incidence of cerebrovascular disease. Sludging of blood in peripheral vessels may occur, partly from cold agglutinins. This contributes to skin oedema and necrosis, though peripheral vasoconstriction is the main cause of the infarction of frostbite. Microinfarcts are common in many organs in hypothermia, presumably from cold agglutinins blocking small vessels. Deep vein thrombosis in the legs and pulmonary embolism are occasionally found, but again cause and effect is hard to establish.

It is said that the good preservation of tissues when examined histologically is characteristic of hypothermia, as autolysis is retarded by the low temperature. In the experience of the authors, this claim is not justified.

THE 'HIDE-AND-DIE' SYNDROME

There is a peculiar aspect to some cases of hypothermic death in that it is associated with the victim undressing and hiding away from sight. The subject is usually an old person, man or woman. When found dead (usually, but not always at home), the body may be partly or even totally naked, even though the environment is cold. In addition, the victim may have burrowed his or her way into some corner or cupboard, or alternatively pulled down furniture and household articles into a heap on top of the body. In fact, the house may be in such a state of disorder that when the police break in and find a corpse amongst such chaos they may naturally suspect a homicide and robbery.

The author (BK) has seen old people who have crawled into small cupboards, the bottom of wardrobes, under low shelves, and into corners of pantries and outhouses. They have been found under piles of books pulled from a bookcase, or hidden under a mound of old clothes, newspapers and other debris.

The signs of hypothermia are usually present and the problem then arises as to whether the victim became hypothermic first, which led to mental confusion that caused the strange behaviour, or whether – as a result of some mental aberration, perhaps related to senility or other cerebral episode – they began behaving abnormally, including shedding their clothes and so became fatally hypothermic.

Though some geriatricians claim that hypothermia is almost always precipitated by some natural illness, including cerebral vascular episodes, the experience of most pathologists is that it is not common to find definite lesions of such predisposing factors at autopsy.

Biochemical markers of hypothermia have been investigated, and catecholamines appear in the blood and then urine in the early stages, but then decline, as the adrenals become exhausted (Hirvonen and Huttunen 1995). There is a variation in the adrenaline:noradrenaline ratio, all these changes being manifestations of stress induced by low temperature.



FIGURE 17.10 *Frostbite of the foot from the infant shown in Figure 17.8. The distal part of the foot is infarcted and a line of separation has appeared between the distal slough and the rest of the limb.*



FIGURE 17.11 *Frostbite on left auricle of a man who, heavily intoxicated by alcohol, left for home at night in the Arctic winter, but lost his way at −40°C and was found dead the following day.*

DEATHS FROM EXPOSURE

Fatal hypothermia can occur in healthy adults, as well as infants and old people. This is caused by purely environmental conditions, which need not be extreme. One common group, especially in more northern countries, is the inebriated person who becomes exposed to even moderate cold. The typical circumstances are a person who gets drunk and either falls asleep outdoors in his drunken state or sustains some accident – such as a fall or even mild head injury – which incapacitates him for long enough for him to become hypothermic. Alcohol seems to have a secondary effect, apart from causing incapacity and immobility. Its vasodilating effect on skin allows heat loss to be more rapid and in higher concentrations it may have a direct action on the heat-regulating centres. Apart from drunken victims, many other classes of person may fall prey to hypothermia. Hill-walkers, climbers, yachtsmen and dinghy-sailors, swimmers, and other classes of sportsmen and women can become cold and exhausted. Every year sees deaths and rescue escapades in the hill country of Britain, even when the weather is far from Arctic in severity. Naturally the risks in colder countries and at high altitudes almost anywhere in the world are much greater. For the pathologist, the features are similar to domestic hypothermia, but there may be the added lesions of frostbite.

LOCAL INJURY DUE TO COLD: FROSTBITE

There are a number of different clinical lesions caused by the effect of prolonged cold on the extremities. ‘Immersion foot’ and ‘trench foot’ refer to damp cold damage, whereas ‘frostbite’ is caused by dry conditions below zero. In the context of forensic pathology, they may be found in victims of fatal hypothermia, but rarely kill in themselves unless tissue necrosis becomes infected. Severe damage with sloughing and separation of toes, or part of the foot is likely to be seen only in survivors or victims of some catastrophe on sea or mountainside, but the author (BK) has seen one case where a neglected infant was left in a urine-soaked cot at temperatures below zero for many days. When it died of a mixture of hypothermia and chest infection, the parents placed it in a sack with a brick and dropped it down a well. On recovery of the body, separation of the necrotic distal part of a foot was seen, with a red zone of inflammatory tissue on the proximal margin. Frostbite may affect only the skin or may extend deeply into the underlying tissues. Lesser degrees are reversible, but infarction and necrosis may ensue if the blood supply is cut off by vasoconstriction, sludging and thrombosis, for a sufficient time.

REFERENCES AND FURTHER READING

Angel J, Sash Z. 1960. Hypothyroidism and exposure to cold. *Br Med J* **1**:1855–9.

Benecke M, Lessig R. 2001. Child neglect and forensic entomology. *Forensic Sci Int* **120**:155–9.

Bray M. 1984. The eye as a chemical indicator of environmental temperature at the time of death. *J Forensic Sci* **29**:396–403.

Davis JH, Rao VJ, Valdes-Dapena M. 1984. A forensic science approach to a starved child. *J Forensic Sci* **29**:663–9.

Denmark LN. 1993. The investigation of beta-hydroxybutyrate as a marker for sudden death due to hypoglycemia in alcoholics. *Forensic Sci Int* **62**:225–32.

Duguid H, Simpson R, Strowers J. 1961. Exposure to cold. *Lancet* **2**:1213–19.

Elias AN, Gwinup G. 1982. Glucose-resistant hypoglycemia in inanition. *Arch Intern Med* **142**:743–6.

Emslie-Smith D. 1958. Hypothermia. *Lancet* **2**:492.

Fieguth A, Gunther D, Kleemann WJ, *et al.* 2002. Lethal child neglect. *Forensic Sci Int* **130**:8–12.

Fitzgerald FT. 1980. Hypoglycemia and accidental hypothermia in an alcoholic population. *West J Med* **133**:105–7.

Hirvonen J. 1976. Necropsy findings in fatal hypothermia cases. *Forensic Sci* **8**:155–64.

Hirvonen J. 2000. Some aspects on death in the cold and concomitant frostbites. *Int J Circumpolar Health* **59**:131–6.

Hirvonen J, Huttunen P. 1982. Increased urinary concentration of catecholamines in hypothermia deaths. *J Forensic Sci* **27**:264–71.

Hirvonen J, Huttunen P. 1995. Hypothermia markers: serum, urine and adrenal gland catecholamines in hypothermic rats given ethanol [see comments]. *Forensic Sci Int* **72**:125–33.

Hirvonen J, Lapinlampi T. 1989. Plasma and urine catecholamines and cerebrospinal fluid amine metabolites as hypothermia markers in guinea-pigs. *Med Sci Law* **29**:130–5.

Kelsey RM, Alpert BS, Patterson SM, *et al.* 2000. Racial differences in hemodynamic responses to environmental thermal stress among adolescents. *Circulation* **101**:2284–9.

Knight B. 1976. Forensic problems in practice. XI. Injury from physical agents. *Practitioner* **217**:813–18.

Kortelainen ML, Huttunen P, Lapinlampi T. 1990. Urinary catecholamines in hyperthermia-related deaths. *Forensic Sci Int* **48**:103–10.

Kreyburg L. 1946. Tissue damage due to cold. *Lancet* **1**:338–40.

Laufman H. 1951. Hypothermia. *JAMA* **147**:1201–12.

Mant AK. 1964. Some port-mortem observations in accidental hypothermia. *Med Sci Law* **4**:44–7.

Mimasaka S, Funayama M, Adachi N, *et al.* 2000. A fatal case of infantile scurvy. *Int J Legal Med* **114**:122–4.

Molnar G. 1946. Survival of hypothermia by men immersed in the ocean. *JAMA* **131**:1045–50.

Ortmann C, Fechner G, Bajanowski T, *et al.* 2001. Fatal neglect of the elderly. *Int J Legal Med* **114**:191–3.

Paton BC. 1983. Accidental hypothermia. *Pharmacol Ther* **22**:331–77.

Sadler DW, Pounder DJ. 1995. Urinary catecholamines as markers of hypothermia. *Forensic Sci Int* **76**:227–30.

Steinhauer JR, Volk A, Hardy R, *et al.* 2002. Detection of ketosis in vitreous at autopsy after embalming. *J Forensic Sci* **47**:221–3.

Tanaka M, Tokudome S. 1991. Accidental hypothermia and death from cold in urban areas. *Int J Biometeorol* **34**:242–6.

Teresinski G, Buszewicz G, Madro R. 2002. The influence of ethanol on the level of ketone bodies in hypothermia. *Forensic Sci Int* **127**:88–96.

Wedin B, Vanggaard L, Hirvonen J. 1979. 'Paradoxical undressing' in fatal hypothermia. *J Forensic Sci* **24**:543–53.

Wolf DA, Aronson JF, Rajaraman S, *et al.* 1999. Wischnewski ulcers and acute pancreatitis in two hospitalized patients with cirrhosis, portal vein thrombosis, and hypothermia. *J Forensic Sci* **44**:1082–5.

Young AJ, Castellani JW. 2001. Exertion-induced fatigue and thermoregulation in the cold. *Comp Biochem Physiol A Mol Integr Physiol* **128**:769–76.

Zhu BL, Oritani S, Ishida K, *et al.* 2000. Child and elderly victims in forensic autopsy during a recent 5 year period in the southern half of Osaka city and surrounding areas. *Forensic Sci Int* **113**:215–18.

CHAPTER 18

Deaths associated with sexual offences

■ External findings in fatal sexual assaults 421
■ Internal examination 424
■ Interpretation of minimal findings 425
■ Tests for semen 426
■ Homosexual offences 428
■ Further reading 429

The examination of living victims of sexual assaults is the province of the forensic physician or 'police surgeon', in places where such doctors exist. In many countries, any physician may be asked by the police to examine the victim of an alleged sexual offence, but this difficult and onerous task in the living victim is outside the experience of many pathologists – though in some jurisdictions, this function is combined with that of the forensic pathologist.

In this book, attention will be confined to those cases in which a sexual assault leads to death, almost always rape and homicide. Regrettably, a significant proportion of non-domestic homicides are associated with sexual offences, death occurring either because the woman rejects the sexual approaches or because a sadosexual motive colours an intended murder. The most common mode of killing is either pressure on the neck, head injuries, or, less often, stabbing. In some instances death may be the result of violence associated with the sexual activities themselves, especially in child victims when pelvic trauma may be the immediate cause of death. In this chapter, only the sexual aspects are discussed, as other modes of violent death are covered elsewhere.

EXTERNAL FINDINGS IN FATAL SEXUAL ASSAULTS

As with most forensic autopsies, a meticulous external examination is as important – and usually more important – than the internal dissection. The study of the body surface in sexual assaults is similar in both the living and dead and may be divided into general appearances and those of the perineum. The whole body surface should be searched for sexually orientated injuries.

Mouth and lips

Bruises may be found on the lips and especially inside on the buccal surfaces, from rough kissing. The lips may have been forced back on to the edges of the teeth, causing abrasions, bruises and even laceration of the buccal surface. Swabs should be taken from the mouth in every case before substantial manipulation for examination, to seek evidence of seminal fluid from oral penetration. Though such swabs rarely yield a positive result as to the presence of spermatozoa, modern analytical methods may be able to detect other components of the seminal fluid or the presence of male epithelial cells.

Bites

Other bruises may be found on the neck, shoulders, breasts and buttocks from oral suction or biting. These are somewhat euphemistically termed 'love bites' and may range from minor lesions inflicted from enthusiastic passion to mutilating bites of a sadistic nature.

Suction lesions may comprise a circular or oval area of bruising, in which the damaged zone consists of many small intradermal petechial haemorrhages caused by sucking the skin into the mouth, the reduced air pressure rupturing the small vessels. There may be semilunar marks at the periphery from the lips, and there may be associated teeth indentations or abrasions. Such suction marks are often seen at the sides of the neck, below the ears, on the upper shoulder, and on the upper part of the breasts and around the nipples.

Actual bites may accompany suction marks or may be independent. The characteristics are described in Chapter 26, but the main features are abrasions or bruises matching the dental arches, often with discrete marks from each tooth. These may be linear if the teeth are scraped down the skin in closing the jaws. They may be superficial or deep enough to penetrate the skin as lacerations. The latter are especially common at the nipples in sexual assaults, and the nipple and part of the areola may even be partly or wholly amputated.

In sexual homicides, it is essential to obtain expert forensic odontological advice, if at all possible. In any event, photographs and measurements must be taken of these injuries and, if practicable, a cast of any teeth indentations for later comparison. Before any handling of the lesions, swabs should be taken of the surface in an effort to recover saliva, which – if the assailant was a 'secretor' – may be tested for blood-group-specific substances.



FIGURE 18.1 *Sexual assaults are sometimes associated with extreme violence, often of a sadistic nature. Here, rape has been followed by severe head injury from the large rock seen near the central gutter of this back lane.*

General bruising and abrasion

Apart from bruises that may be associated with the fatal assault, such as throat or head injuries, some bruises are indicative of the sexual motivation. The breasts are often manually squeezed and manipulated, causing discoid bruises of 1–2 cm on any part, especially around the nipples. Linear abrasions, usually from fingernails, may also be present. Bruises may also be seen on the thighs and buttocks, from struggles to achieve intercourse. Both the outer and inner sides of the thighs may be bruised and scratched: a typical area is the inner aspect of the upper thigh, where the legs are manually forced apart. There may be bruising around the anus from fingers opening the buttock cleft to achieve either anal or posterior vulval penetration.

Where the assault takes place on a hard or uneven surface, bruises and abrasions may be seen on the back, especially the shoulders and buttocks. If outdoors, there may be marks from stones or sticks and remnants of vegetation, such as leaves, and grass and green staining may be adherent to the skin, together with earth or dirt. Examination of the clothing is usually a function of the forensic scientist ('criminalist'), but when the pathologist examines the body *in situ*, he will naturally note damage, disarray and foreign material on the garments.



FIGURE 18.2 *In fatal rape the pathologist must note at the scene, or at the mortuary, the position and condition of clothing and presence of foreign material on the skin. Full cooperation with scene of crime officers or forensic scientists is vital in collecting trace evidence.*

Other general injuries

The hands should be carefully examined, as in all assaults. The fingernails, especially the often longer and manicured nails of younger women, may be broken from a struggle. Occasionally, there are hairs or fibres trapped in nail splits, which may have come from the assailant or his clothing. At autopsy, the nails should be cut closely to the junction with the fingers and all parings carefully collected for forensic laboratory examination. It is rarely necessary to collect those from each finger in individual packets, but each hand should be identified separately. Some pathologists or scientific officers prefer to scrape out the space under each nail with a pointed orange-stick or toothpick, carefully retaining any debris. The reason for this interest, especially in sexual assault victims, is that they may have scratched their assailants and have blood, or even skin parings, under the nails that can be identified as to blood group or individually specific DNA characteristics.

Signs of head injury and throttling are dealt with elsewhere, but some fatal trauma may be sexually orientated, especially knife injuries. Sadistic cutting or stabbing may be inflicted on sexually significant areas, especially the breasts, buttocks, perineum and lower abdomen. The vulva itself may be mutilated. These may be slashes or deeply penetrating stabs, often multiple and indeed numerous. They may be arranged in a pattern or may be mutilating, as when whole breasts are amputated. Decapitation is sometimes performed and ritual acts may be performed, with objects placed in definite sites near the body. The notorious 'Jack the Ripper' murders in London in 1888 exhibited the arrangements of disembowelled organs and this type of mutilation is another feature of some sadistic sexual homicides. Intestine or uterus may be removed, either through abdominal wounds or manually through the vagina. General injuries may be continuous with genital trauma, as in knife or broken bottle wounds of the abdomen and perineum.



FIGURE 18.3 *Multiple superficial abrasions from undergrowth and ground debris on the back of the victim of rape. This is an indication of pressure of the unclothed body on the ground. There is a ligature mark around the neck with a cross-over point visible.*

Genital injuries

Once the pathologist has examined all the external general injuries, attention should be turned to the perineum. As with the clinical examination of sexual offences, a set routine should be used, as the incorrect order may lose valuable forensic evidence.

The vulva and anus should be inspected externally and laceration, swelling, bruising, bleeding and discharge noted. Any blood or suspected semen stains anywhere on the body or clothing should be sampled either by the pathologist or by the forensic scientist or scene of crime police officer. The pubic hair should be examined for foreign material, hairs, vegetation and dried seminal stains, and samples of hair and combings taken. The hair may be combed using a fine comb with the base of the teeth packed with cotton-wool to trap any loose fibres. Dried stains on hair may be cut away and placed in clean folded paper in an envelope, or plastic bag for transit to the laboratory. The vulval labia may show clear signs of trauma, especially in children. In forcible rapes, especially in young persons, there may be external signs of perineal tears, with laceration of the margin of the vaginal introitus or anus, sometimes causing a complete rip between the two orifices.

Caution must be used in interpreting the degree of dilatation of the anus in a dead body, as the sphincter can become patulous and wide open as a normal post-mortem change. Unless the dilatation is very marked, the sole finding of an open anus in the absence of abrasion, bruising, or semen is difficult to sustain as proof of anal penetration. This applies



FIGURE 18.4 *Some homicides have obvious sexual connotations even if there is no genital interference. This circle of stab wounds is centred on a breast.*

to children as well as adults; in fact, post-mortem dilatation of the anus is particularly noticeable in children.

Once external examination and assessment has been made, samples should be taken for forensic biological testing, for the presence of semen and venereal infection, as well as samples for DNA profiling, which may be able to distinguish between any semen present and the vaginal secretions. If any fluid is running from the vulva or anus, it should be picked up with clean pipettes and preserved in the smallest available tube, to prevent drying from evaporation. Then cotton-wool swabs on sticks (ensuring that those used for semen detection are plain swabs, not those containing albumin or other media) should be used to take the following samples by touching gently on to the mucosal surfaces:

- the interior of the vulval labia and around the vaginal orifice
- the margins and interior of the anus
- the mid-vagina, using a speculum or broad handle of a dissecting forceps to part the lower vaginal walls gently to allow the swab to reach the area without contamination from the lower vagina
- the upper vagina, cervix and posterior fornix, again using a spatulate instrument to open the canal to give access to the swab. If more fluid contents are seen higher in the vagina, either now or during the later dissection, they should be recovered by pipette.



FIGURE 18.5 *Fresh bleeding and mucosal abrasion on the lower wall of the vagina in a sexual assault associated with fatal head injuries in an old lady.*

After samples are taken, the interior of the anus, vulva and vagina, as far as can be seen from the exterior, should be examined. Lacerations, abrasions, bruises and bleeding may be evaluated, though they can be seen in more detail at dissection. The presence and condition of a hymen is noted, with any evidence of recent tearing. Where injuries are gross, especially in children, fistulae between the vagina and the rectum or even peritoneal cavity may be seen. There may be extrusion of intestine.

INTERNAL EXAMINATION

The order of the autopsy may be determined by the nature of the death. The fatal injuries, such as strangulation or head



FIGURE 18.6 *Stab wounds (arrows) in the vaginal wall of a homicide victim (U, uterus).*

injuries, may be dealt with first or the pelvic region may command prime attention. The autopsy incision should be similar to that described for the examination of deaths associated with pregnancy, with an incision circumscribing the perineum, removal of the anterior part of the pelvic bones and the extraction of all the pelvic organs in continuity from ovaries to vulva and anus. This block of tissue is then dissected separately. Before this is done, the bladder should first be emptied of urine (either by catheter or through a small incision in the fundus) and the fluid retained for toxicological analysis, especially for alcohol.

The vagina should be opened with large scissors, the track of the cut depending on the assessment of any injuries seen on external examination. If there are tears or bruises in the vulva or vagina, the cut should be orientated to avoid them wherever possible; the anus is later dealt with in a similar way. The vagina is laid open to the posterior fornix and all injuries carefully examined and photographed. The cervix and uterus are examined in the same way.

Injuries may be of all types, from mere reddening or swelling to complete disruption of the vaginal canal. This may occur in small children from sheer brutality of penetration, especially if there is gross disproportion between the adult penis and infantile canal. It may also occur from instrumental injury, as it is by no means uncommon for deliberate incised wounds to be made. The author (BK) has seen abdominal knife wounds carried over the pubis into the vagina in a murdered prostitute; another murder–rape was found to have a broken milk bottle high in the vagina, to the potential hazard of the examining fingers. Vaginal injuries, especially by instrument, may continue up into the abdominal cavity, either via the posterior fornix or lateral vaginal walls. This will have been examined through the abdominal autopsy incision before removal of the pelvic organs.

INTERPRETATION OF MINIMAL FINDINGS

As in clinical forensic practice, there is little difficulty in interpreting gross sexual interference, but problems arise when only minimal evidence is present in a death (traumatic or otherwise) where the circumstances suggest some sexual offence or activity. In such cases, the following questions need to be answered, in the light of all the available findings at the end of the autopsy and ancillary investigations:

- Is there any evidence of sexual intercourse at any time – that is, absence of virginity as determined by an intact hymen? This does not exclude sexual activity short of penetration and technically rape can occur from even the minimal passage of a glans between the labia, which does not affect the hymen. Old intercourse may be assumed from healed hymenal tears with epithelialized ‘carunculae myrtiformes’ at the margins, though the prolonged use of tampons and manual manipulation can also tear a hymen. Evidence of previous pregnancy, such as abdominal striae, old damage to the cervix and breast changes are almost incontrovertible evidence of previous sexual intercourse.
- Is there evidence of recent sexual intercourse? A recently ruptured hymen, with swelling, a raw unepithelialized edge and bleeding may be found, though admittedly it is relatively uncommon except in children and previously virginal young persons. The labia may be red and



FIGURE 18.7 *External genitals of a live 8-year-old girl, a victim of repeated sexual abuse by an adult living in the neighbourhood. The lack of intact hymen, reddened and larger than normal orifice of the vagina as well as thickened skin and ulcers perianally (not shown) are in keeping with abuse.*



FIGURE 18.8 *Extensive bleeding from inner lacerations of the vaginal walls in a fatal rape. Blood is pooling in the posterior part of the vaginal canal. A full autopsy dissection is required, keeping the perineum en bloc with the genital tract to display any injuries and to exclude natural disease as a contribution to the bleeding.*

inflamed with slight oedema of the vaginal introitus if it is the first episode, or if there is disproportion between an adult man and a young person, even in voluntary sexual connection. The presence of semen on swabs is the best evidence, though with the use of condoms it may be absent. After vasectomy, though no sperms will be present, chemical and enzyme tests for semen remain positive. The presence of venereal disease, especially gonorrhoea, is presumptive evidence of intercourse, though it can be contracted other than by sufficient penile penetration to constitute rape.

- If recent intercourse has taken place, was it by force? This may be all too obvious in the presence of gross injury, especially in small children. Where vaginal or rectal tearing has occurred, or where there is obvious abrasion, bruising or laceration of the vulva, anal margins or perineum, then this can hardly be compatible with voluntary intercourse. The possibility of sexually motivated injury without actual penile penetration must be considered when no semen can be recovered, as equally severe damage can be caused by digital or instrumental trauma. All kinds of foreign objects can be forcibly introduced into the vagina and rectum, and are not infrequently employed by sadistic and perverted killers. The author (BK) has seen candles, bottles, a banana, broken glass and knives introduced into the vagina, and broom-handles and potatoes lying in the rectum.

  Where injury is relatively slight and confined to hyperaemia and oedema of the vaginal or anal entrances – and where abrasion and bruising of the vulva is slight (even including fingernail scratches), although the presumption is that intercourse was by force, the possibility still exists that it was voluntary though overenthusiastic, unless, of course, the victim was a small child.

TESTS FOR SEMEN

In countries with sophisticated forensic science or police laboratories, the pathologist will not be called upon to carry out the actual techniques for the detection of seminal fluid. His role is to be a careful collector of the original samples at autopsy and, to some extent, to be able to interpret the results for the benefit of the police and the courts. He should be conversant with the general principles of the tests and aware of any potential shortcomings. In places where forensic science facilities are deficient or their availability may be delayed, the pathologist may have to conduct the more simple tests himself and the technical details are given in Appendix 1. The detection of semen depends upon the following methods:

- Naked-eye and lens recognition is a screening method which may identify suspicious stains on clothing, skin and pubic hair. Liquid semen leaking from the vagina or anus may be obvious, though leucorrhoeic vaginal discharge may be mistaken for seminal fluid. Dried seminal stains are stiff and rather silvery, depending upon the nature and colour of any fabric they may be upon. On the skin they flake off readily and can easily be lost if not carefully lifted with a blade or needle into a container. Dried stains on hair should be retrieved by cutting away the clump on which they lie. Suspect smears on skin may be collected by gentle rubbing with a plain cotton-wool swab that has been moistened with water or saline. All material should be examined as soon as possible after collection.
- Examination under ultraviolet light causes seminal stains to fluoresce a bluish-silver, but many other biological fluids and vegetable juices give false-positive



FIGURE 18.9 *Rape and buggery of a small girl who was then strangled. The vulva has a slight posterior tear and there is a large vaginal tear internally, the canal being filled with blood. The anus is widely ripped, especially posteriorly. Swabs were positive for semen in both orifices.*



FIGURE 18.11 *Extensive bruising from fingers during a multiple anal and vaginal rape. Though penetrated by several men in a short space of time, the anus shows no injury.*



FIGURE 18.10 *A chronically dilated anus in an habitual passive homosexual. After death any anus can appear open and patulous, but this example is too large to be accepted as within normal limits. It also has keratinized, chronically abraded margins.*



FIGURE 18.12 *The anus of a girl who has suffered penetration. The sphincter is overdilated, there is slight tearing of the anal margin, and some epidermal tags have been abraded from the surface. However, this degree of dilatation in a dead subject should not be used as the sole indication of buggery, as the post-mortem anus can be patulous in quite innocent circumstances.*

results. Many detergents, such as washing powders, also produce a confusing background fluorescence. The method is a useful screening process but cannot be used as definitive evidence of the presence of semen. Areas that fluoresce, especially on fabric, should be outlined to identify them for more specific testing.

- Enzyme reactions are valuable, and though not absolute proof, are strong presumptive evidence of the presence of semen. They depend on detecting high concentrations of acid phosphatase originating in prostatic secretion. Acid phosphatase activity in semen is 500–1000 times greater than in any other normal bodily fluid. Also, vaginal fluid contains endogenous acid phosphatase showing considerable variation in activity depending on various factors, which complicates the interpretation of the findings. There are several methods of detecting phosphatase, including a rapid commercial 'spot' test, which should not be used as hard evidential proof.
- Immunological methods, where animal antihuman semen sera are set up against extracts of the stain. These techniques can only be used by trained laboratory staff.

Prostate-specific antigen (PSA, p30) is a glycoprotein produced by the prostatic gland and is found in seminal plasma, male urine and blood, but not in any tissues or fluid of the female body. A positive PSA finding is a reliable indicator of semen regardless of the presence of spermatozoa or elevated acid phosphatase level. Simple and sensitive methods have been developed for analysis of the presence of PSA.

Other serological techniques may be able to determine the blood group of the semen if the ejaculator was one of the 80 per cent of the population who are 'secretors' – those who pass blood-group antigens into their saliva, sweat and semen. A problem for the forensic serologist is the admixture of semen with biological fluids from the victim, in the form of vaginal secretion and blood, but this is a complex technical matter that is usually outside the remit of the forensic pathologist, though he needs to be aware of the potential difficulties.

Recent developments have now added the DNA technique to the armamentarium of the forensic biologist; this is a remarkable advance, especially in sexual offences, as the previous problems of blood group and enzyme typing caused by the admixture of semen and vaginal secretion can now be solved in many instances. The sensitivity of detection and identification has also been enormously enhanced by amplification techniques, such as PCR (polymerase chain reaction). Y-chromosome short tandem repeat (STR) markers have been succesfully used to analyse mixed stains with a male component.

- Until recent years, the only absolute proof accepted by the courts was the demonstration of spermatozoa in stain extracts and it remains the best evidence, though some of the sophisticated laboratory techniques such as serological and DNA identification are now equally reliable. One modern problem in using spermatozoa retrieval is the widespread and increasing incidence of vasectomy as a method of male contraception, so the seminal fluid contains no sperm; this also occurs naturally in azoospermic men. The phosphatase and some serology tests are unaffected by vasectomy. Fluorescent *in situ* hybridization (FISH) has been suggested as a sensitive and specific test for the detection of male epithelial cells in the post-coital vagina up to one week. Y-chromosome-positive epithelial cells have been identified in vaginal swabs even in cases with no ejaculation.

HOMOSEXUAL OFFENCES

As with heterosexual offences, the cause of death in fatal cases is almost always some form of general trauma, such as strangulation or head injuries. Homosexual activity, however, may be a parallel event; it is a fact that some of the most violent homicides seen by pathologists are among male homosexuals. In addition, quite a number of fatal altercations arise because a heterosexual man becomes violent when importuned by a homosexual.

The pathologist's attention will almost always be directed to the anal region of the passive participant, as the other partner or assailant is rarely dead, and any examination will be carried out by a police surgeon or clinical doctor. The examination of the victim follows closely on that for a female subject of rape, in that general injuries are sought first – including the one that caused death – together with any sexually orientated marks such as scratches anywhere on the body, but especially down the back, on the buttocks or on the thighs. Bruising around the anus and in the cleft of the buttocks is significant, especially if discoid finger bruises are seen. The anus should be inspected and the warning given earlier about the degree of dilatation in corpses should be heeded. Though most marked in children, a patulous anus can be seen in any adult post-mortem. Unless it is grossly dilated, an open anus cannot be used in isolation as an index of homosexual penetration. In recent or forcible anal intercourse, especially by a large penis upon a 'virgin' or young person, the margins of the anus may be reddened, sometimes abraded, and occasionally torn, especially in a child. There might be some eversion of the lower rectal mucosa through the sphincter. In gross anal 'rapes', especially on a young person, there may even be severe perineal tearing. At autopsy, swabs must be taken from the anal margin, and deeper in the anus and rectum. Mouth swabs should also always be taken. The presence of blood or lubricant should also be sought.

The classic description of the chronic passive homosexual has been passed down from textbook to textbook over the years, but is a rarity. The so-called 'funnel anus' is usually an anatomical variant. Some men and women have a deeply set anus as an anatomical variant, sometimes with a bridge of skin dorsally across the cleft of buttocks. This causes the anus to appear as if it was at the bottom of a funnel, but has no significance. The other classic feature was said to be silvery thickening of the skin outside and at the margins of the anus – but this is often due to chronic scratching from pruritis, rather than from prolonged friction during homosexual activities. In life, a lax anus, prolapsed mucosal rim and thickened anal margin may well be genuine signs to the experienced clinical eye, but at autopsy only acute damage and the presence of semen or lubricant is of much evidential value.

FURTHER READING

Allard JE. 1997. The collection of data from findings in cases of sexual assault and the significance of spermatozoa on vaginal, anal and oral swabs. *Sci Justice* **37**:99–108.

Allen M, Saldeen T, Gyllensten U. 1995. Allele-specific HLA-DRB1 amplification of forensic evidence samples with mixed genotypes. *Biotechniques* **19**:454–63.

Berg SP. 1955. A new method for testing for seminal stains. *Crim Pol Rev* **11**:53–7.

Carracedo A, Beckmann A, Bengs A, *et al.* 2001. Results of a collaborative study of the ednap group regarding the reproducibility and robustness of the Y-chromosome STRs DYS19, DYS389 I and II, DYS390 and DYS393 in a PCR pentaplex format. *Forensic Sci Int* **119**:28–41.

Clery JM. 2001. Stability of prostate specific antigen (PSA), and subsequent Y-STR typing, of *Lucilia (Phaenicia) sericata (Meigen)* (Diptera: Calliphoridae) maggots reared from a simulated postmortem sexual assault. *Forensic Sci Int* **120**:72–6.

Collins KA, Bennett AT. 2001. Persistence of spermatozoa and prostatic acid phosphatase in specimens from deceased individuals during varied postmortem intervals. *Am J Forensic Med Pathol* **22**:228–32.

Concheiro L, Carracedo A, Guitian F. 1982. The use of scanning electron microscopy in the examination of seminal stains. *Forensic Sci Int* **19**:185–8.

Costa MJ, Tadros T, Tackett E, *et al.* 1991. Vaginocervical cytology in victims of sexual assault. *Diagn Cytopathol* **7**:337–40.

Crouse CA, Ban JD, D'Alessio JK. 1993. Extraction of DNA from forensic-type sexual assault specimens using simple, rapid sonication procedures. *Biotechniques* **15**:641–4, 646, 648.

Dahlke MB, Cooke C, Cunnane M, *et al.* 1977. Identification of semen in 500 patients seen because of rape. *Am J Clin Pathol* **68**:740–6.

Davies A. 1978. Evaluation of results from tests performed on vaginal, anal and oral swabs received in casework. *J Forensic Sci Soc* **17**:127–33.

Davies A, Wilson E. 1974. The persistence of seminal constituents in the human vagina. *Forensic Sci* **3**:45–55.

Department of Health. 1988. *Diagnosis of child sexual abuse.* HMSO, London.

Dziegelewski M, Simich JP, Rittenhouse-Olson K. 2002. Use of a Y chromosome probe as an aid in the forensic proof of sexual assault. *J Forensic Sci* **47**:601–4.

Enos WF, Beyer JC. 1978. Spermatozoa in the anal canal and rectum and in the oral cavity of female rape victims. *J Forensic Sci* **23**:231–3.

Enos WF, Beyer JC. 1980. Prostatic acid phosphatase, aspermia, and alcoholism in rape cases. *J Forensic Sci* **25**:353–6.

Enos WF, Beyer JC. 1981. The importance of examining skin and hair for semen in sexual assault cases. *J Forensic Sci* **26**:605–7.

Gabby T, Winkleby MA, Boyce WT, *et al.* 1992. Sexual abuse of children. The detection of semen on skin. *Am J Dis Child* **146**:700–3.

Gill P, Jeffreys AJ, Werrett DJ. 1985. Forensic application of DNA 'fingerprints'. *Nature* **318**:577–9.

Hochmeister MN, Budowle B, Rudin O, *et al.* 1999. Evaluation of prostate-specific antigen (PSA) membrane test assays for the forensic identification of seminal fluid. *J Forensic Sci* **44**:1057–60.

Hooft P, van de Voorde H. 1988. In vitro changes in human spermatozoa exposed to gastric juice: laboratory findings as a support for forensic practice. *Z Rechtsmed* **101**:41–4.

Hooft P, van de Voorde H. 1992. Evaluation of the modified zinc test and the acid phosphatase test as preliminary screening methods in sexual assault case material. *Forensic Sci Int* **53**:135–41.

Hooft PJ, van de Voorde HP. 1997. Bayesian evaluation of the modified zinc test and the acid phosphatase spot test for forensic semen investigation. *Am J Forensic Med Pathol* **18**:45–9.

Jimenez-Verdejo A, Osuna E, Garcia-Olivares E, *et al.* 1994. Study of the enzymatic activity of GGT, LDH, PAP and PSA in semen stains: application to age calculation. *Forensic Sci Int* **68**:7–15.

Keil W, Bachus J, Troger HD. 1996. Evaluation of MHS-5 in detecting seminal fluid in vaginal swabs. *Int J Legal Med* **108**:186–90.

Kind SS. 1964. The acid phosphatase test. In: Curry AS (ed.), *Methods of forensic science*. Interscience, London, Vol. 3, pp. 267–87.

Maher J, Vintiner S, Elliot D, *et al.* 2002. Evaluation of the biosign PSA membrane test for the identification of semen stains in forensic casework. *N Z Med J* **115**:48–9.

Nicholson R. 1965. Vitality of spermatozoa in the endocervical canal. *Fertil Steril* **16**:758–64.

Paparo GP, Siegel H. 1979. Histologic diagnosis of sodomy. *J Forensic Sci* **24**:772–4.

Poyntz FM, Martin PD. 1984. Comparison of p30 and acid phosphatase levels in post-coital vaginal swabs from donor and casework studies. *Forensic Sci Int* **24**:17–25.

Reade DJ. 1985. Early investigations of sexual assault. *Police Surg* **April**:424.

Roberts REI. 1984. Sexual offences. In: McClay W (ed.), *Rape. The new police surgeon*. Association of Police Surgeons of Great Britain, Northampton, pp. 65–81.

Rupp JC. 1969. Sperm survival and prostatic acid phosphatase activity in victims of sexual assault. *J Forensic Sci* **14**:177–83.

Sato I, Sagi M, Ishiwari A, *et al.* 2002. Use of the 'SMITEST' PSA card to identify the presence of prostate-specific antigen in semen and male urine. *Forensic Sci Int* **127**:71–4.

Schiff AF. 1969. Modification of the Berg acid phosphatase test. *J Forensic Sci* **14**:538–44.

Schiff AF. 1975. Sperm identification – acid phosphatase test. *Med Trial Tech Q* **21**:467–74.

Sibille I, Duverneuil C, Lorin de la Grandmaison G, *et al.* 2002. Y-STR DNA amplification as biological evidence in sexually assaulted female victims with no cytological detection of spermatozoa. *Forensic Sci Int* **125**:212–16.

Simich JP, Morris SL, Klick RL, *et al.* 1999. Validation of the use of a commercially available kit for the identification of prostate specific antigen (PSA) in semen stains. *J Forensic Sci* **44**:1229–31.

Soukos NS, Crowley K, Bamberg MP, *et al.* 2000. A rapid method to detect dried saliva stains swabbed from human skin using fluorescence spectroscopy. *Forensic Sci Int* **114**:133–8.

Steinman G. 1995. Rapid spot tests for identifying suspected semen specimens. *Forensic Sci Int* **72**:191–7.

Takatori T, Sasaki T. 1980. Isolation of spermatozoa in vaginal contents by centrifugation in a colloidal silica gradient. *Forensic Sci Int* **15**:61–5.

Toates P. 1979. The forensic identification of semen by isoelectric focusing of seminal acid phosphatase. *Forensic Sci Int* **14**:191–214.

Vihko P, Mattila K, Ehnholm C. 1981. Radioimmunoassay of human prostate-specific acid phosphatase. A sensitive and specific assay for semen detection in forensic medicine. *Am J Clin Pathol* **75**:219–20.

Willott GM, Allard JE. 1982. Spermatozoa – their persistence after sexual intercourse. *Forensic Sci Int* **19**:133–54.

Willott GM, Crosse MA. 1986. The detection of spermatozoa in the mouth. *J Forensic Sci Soc* **26**:125–8.

Zarrabeitia M, Amigo T, Sanudo C, *et al.* 2002. A new pentaplex system to study short tandem repeat markers of forensic interest on X chromosome. *Forensic Sci Int* **129**:85–9.

CHAPTER 19

Deaths associated with pregnancy

■ Deaths associated with abortion 431
■ The autopsy in abortion deaths 435
■ Amniotic fluid embolism 436
■ References and further reading 437

Though not usually a forensic problem, deaths associated with pregnancy (other than criminal abortions) are intensively investigated in a number of countries. In Britain, the Department of Health has had an ongoing ‘Confidential Enquiry into Maternal Deaths’ running for many years, which publishes valuable reports at 3-yearly intervals that have helped to clarify both the clinical and pathological aspects of the problem.

The pathologist has an important role in furthering the understanding of the causes of death in pregnancy and after childbirth. A good autopsy is essential, with full histological examination and other ancillary investigations where necessary. Only in this way can the full range of causes of death be recognized, especially amniotic fluid embolism, which is a histological diagnosis.

To give an example of the range of fatal conditions that occur in association with pregnancy, the following causes are taken from the ‘Confidential Enquiry’ from Britain published in 1998, the figures referring to death during pregnancy and within 6 weeks of parturition in the years 1994–1996. Altogether 376 deaths were reported to or identified by the enquiry in the UK during that period. Of the 376, there were 134 (36 per cent) direct and 134 (36 per cent) indirect maternal deaths. The number of underlying causes of death of the direct maternal deaths is shown in Table 19.1.

According to a recent estimation, about 26 million legal and 20 million illegal abortions are carried out yearly throughout the world. Forensic pathological interest in pregnancy revolves almost exclusively around deaths associated with abortion, either criminal or legally induced. The term ‘therapeutic abortion’ is used in many countries, including Britain, where there is no abortion on demand, as in some countries. The description ‘legal termination of pregnancy’ is a wider definition for all but illegal (that is, criminal) abortions. The autopsy investigation of deaths from legal abortions has much in common with that into fatalities associated with surgical and anaesthetic procedures.

TABLE 19.1 *Number of direct maternal deaths by cause, United Kingdom 1994–1996*

Cause of death	*n*	Percentage
Thrombosis and thromboembolism	48	35.8
Hypertensive disease of pregnancy	20	14.9
Amniotic fluid embolism	17	12.7
Early pregnancy deaths*	15	11.2
Sepsis	14	10.4
Haemorrhage	12	9.0
Genital tract trauma	7	5.2
Anaesthesia	1	0.7
Total	134	100.0

* Ectopic pregnancy, spontaneous abortion, or termination of pregnancy, before 24 weeks' gestation.

DEATHS ASSOCIATED WITH ABORTION

Though in many countries medical termination of pregnancy (‘therapeutic abortion’) is legal, a large area of the world still prohibits any form of abortion, either totally or except for the preservation of life of the pregnant woman. Even in those states where legal termination is possible, criminal abortions are still carried out, albeit on a small scale.

The reasons for this survival are varied, but are either because of restrictive grounds for legally available termination or to some sections of society that do not wish to avail themselves of the legal provisions. Whatever the cause, criminal abortion is associated with a considerable risk of both morbidity and mortality, especially in countries with a lower level of medical and social care.

Legal termination of pregnancy

When carried out with proper facilities, legal abortion has an extremely low mortality rate, being less than the mean death rate associated with pregnancy. The usual methods are vacuum aspiration, dilatation and curettage, or hysterotomy in later pregnancy. A few deaths are reported from time to time, the causes including:

- pulmonary embolism from leg vein thrombosis
- mishaps associated with anaesthesia
- disseminated intravascular coagulation and cerebral damage (including 'butterfly' haemorrhagic infarction in the basal ganglia) when abortion was induced by intrachorionic injection of hypertonic saline or glucose after the twelfth week (Cameron and Dayan 1960)
- air embolism following vacuum aspiration – only two cases have been reported and the mechanism is obscure, one theory being that 'elastic rebound' of the aspirated uterus sucked air into the cavity
- bleeding or infection, which failed to respond to treatment.

Death from illegal abortion

This has a much wider range of causes. The risks vary according to the skill, experience and facilities of the abortionist. When this is carried out by a doctor with aseptic and antiseptic methods, together with antibiotic cover if needed, the risk may be small compared with the crude methods of a lay person using makeshift instruments. The most common methods together with the associated dangers to health and life are as follows.

INSTRUMENTAL INTERFERENCE

The intention is to disturb the pregnancy sac so that, once damaged, it will be expelled by uterine contractions. This usually consists of dilatation of the cervical canal, which in itself also tends to dislodge the pregnancy. All manner of instruments have been used, from surgical dilators to bicycle spokes. A favourite in the hands of paramedical abortionists is the bougie or stiff catheter. When used by doctors or nurses with anatomical knowledge and sterile instruments, the risk is small, but lay persons often have no idea of the relationship of uterus to vagina. The instrument is then often pushed into the posterior fornix in the misguided belief that the cervix lies axially with the vagina. The vault of the vagina can be perforated and the instrument may even be passed through coils of intestine as far as the liver. Penetration of the lower or mid-vagina can also occur. If the cervix is entered, then the canal may be punctured and the instrument emerges through the side.

The external os may be badly injured by repeated, clumsy attempts to introduce too thick an object into the undilated canal. If successfully passed into the cavity of the uterus, it may be pushed right up through the fundus, again to damage the contents of the peritoneal cavity.

The dangers of such instrumentation are bleeding and infection. Perforation of the wall of vagina or uterus may cause severe bleeding, which may be internal or external. Sepsis can supervene in the peritoneal cavity or pelvic tissues either directly from a dirty instrument or from transfer of vaginal, skin or bowel organisms.

Another less common danger of the use of instruments (including syringes) is cervical shock. The mere act of dilating the cervix with an instrument in an unanaesthetized patient may trigger a vagal reflex, the efferent pathway being via the parasympathetic nervous system, causing a cardiac arrest. This is known to be a more potent mechanism in states of fear, apprehension and nervous tension, which obviously will apply to many candidates for a criminal abortion.

INSUFFLATION OF AIR

In Europe, this is becoming more of historical interest, but occasional cases still occur. A rubber pump, usually a Higginson enema syringe, is used to introduce fluid under pressure into the cavity of the uterus. This strips the chorionic sac from the wall of the uterus, exposing the placental bed. If sufficient detachment is achieved, then abortion will occur. It was formerly a popular method of abortion, both by women themselves and by abortionists. The main danger – part from the usual risks of bleeding and infection from damage to the tissues by the stiff nozzle – was air embolism, and in the first half of this century it was a major cause of abortion deaths. The intention was to introduce a fluid such as water–soap solution or disinfectant through the cervix by means of the syringe nozzle, the other end, which carried a one-way valve, being dipped in a receptacle of the fluid.

As the level in the receptacle dropped, the inlet tube rose above the surface and the syringe began to inject air instead of fluid, often as soapy foam. In addition to this danger, unless the bulb of the pump was primed with fluid before use, the first ejection would be the appreciable volume of air



FIGURE 19.1 *The sudden unexpected death of a woman of child-bearing age should always arouse the consideration of a complication of pregnancy. This woman insufflated her uterus with a Higginson syringe and had time to clean up the equipment before collapsing with air embolism. This photograph was taken before the British Abortion Act of 1967, as such events are now uncommon.*



FIGURE 19.2 *Burns from a hot-water bottle on the inner side of the upper thigh in an attempt to resuscitate the victim of a criminal abortion who died from air embolism.*

contained in the empty syringe, which in itself was enough to cause a fatal embolism. Under the considerable pressure available from the instrument (as much as 28 cm of mercury according to Teare 1958), this air was forced into the exposed vascular channels of the placental bed and from there into venous sinuses and pelvic veins to cause cardiac embolism.

Though this occurred almost immediately in most instances, some delay was possible – perhaps because contained air was further squeezed by contraction of the uterus. Some victims were able to leave the premises of an abortionist and survive for up to 2 hours or more before the embolism occurred (Simpson 1951). The addition of various substances, such as phenol, formalin, alcohol and turpentine, to the fluid introduced a toxic element, and in some cases these fluids were extruded into the peritoneal cavity through the uterine tubes, causing a chemical peritonitis.

DILATATION OF THE CERVIX

Another crude method was to introduce a 'tent' into the cervical canal. This was a strip of substance that absorbed water and became greatly enlarged, such as *Laminaria digitale* or slippery elm (*Ulmus fulva Michx*). These vegetable materials are hard and compact when dehydrated, so that a strip about 3–8 cm long could be slid into the cervix. When water was absorbed from the surrounding tissues, the cervical canal became widely dilated and abortion might take place. The risks were perforation of the cervix and also infection, especially if the strip tore into the tissues. The substances used, often crude vegetable material, could be the source of infecting micro-organisms including anaerobes.

PHYSICAL VIOLENCE

Women anxious to lose their pregnancy have resorted to extremes of physical activity and even violence in efforts to dislodge the fetus. Frenzied exercise, horse-riding and severe purging with laxatives were usually ineffective, and some unfortunate women went on to seek violent treatment from husbands or consorts. Punching and kicking of the abdomen were most common, and death from visceral rupture, such as liver, spleen or intestine, has been reported. Ironically, the uterine contents were usually undisturbed.

SYRINGE ASPIRATION

The suction method most often used in therapeutic abortion has also come to be used for illegal operations, mainly by medical or nursing personnel. A large syringe attached to a catheter or length of plastic tubing can produce suction within the uterus sufficient to rupture the chorionic sac and precipitate abortion. The method is safe as long as aseptic methods are used, though, if evacuation is incomplete, some products of conception may be left behind that can form a nidus for infection.

INTRAUTERINE INFECTION

Whatever method is used to evacuate the uterus, the risk of haemorrhage or sepsis is always present. Where an instrument, tent or syringe is used, any remaining fragments of placenta or other products of conception may form a substrate for infection. The organisms involved in sepsis are varied, the most dangerous being non-haemolytic



FIGURE 19.3 *Septic, necrotic uterus following an instrumental criminal abortion. The endometrium, containing some retained products of conception, is chocolate brown and foul-smelling, the predominant organism on culture being* Clostridium perfringens.

streptococci and *Clostridium perfringens*, though coliforms and staphylococci may also be responsible.

The uterus becomes swollen, spongy and discoloured. The serosal surface seen at autopsy may be brownish – especially in clostridial infections – and the endometrium may be ragged, foul-smelling and even purulent. Signs of septicaemia may develop with an enlarged, soft spleen, prominent lymph nodes and hepatorenal failure. The kidneys may show bilateral cortical necrosis in extreme cases. In clostridial septicaemias there may be a characteristic bronze coloration of the skin. This may have a mottled or 'raindrop' appearance.

THE USE OF DRUGS AND CHEMICALS

A wide variety of substances, applied locally or taken by mouth, have been used since time immemorial to induce miscarriage. Some have a sound pharmacological basis, others are dangerous, and yet more lie in the realms of folk medicine. Substances applied locally include phenols and Lysol, mercuric chloride, potassium permanganate, arsenic, formaldehyde and oxalic acid. All have their own dangers, both from local corrosion and systemic effects if absorbed. A necrotic pseudomembrane may form in the vagina and severe damage to the cervix may also ensue.

Potassium permanganate was a substance that appeared during the last war and persisted for some years, 650 cases being reported up to 1959, though only a few were fatal. It can cause local necrosis in the vagina and, if absorbed, can have fatal systemic effects including renal failure. Permanganate can cause profuse vaginal bleeding from necrosis, which may give the impression that abortion is threatened and lead an unsuspecting doctor to carry out a curettage. 'Utus paste' is a mixture of soap, myrrh resinoid and potassium iodide, and was used earlier in the century for legitimate abortions, but soon became popular with the criminal abortionist. Another similar product containing elemental iodine, is 'Interruptin'; both were used for late abortions and the induction of labour when the fetus was dead. These pastes are squeezed into the cervical canal through an applicator and the halogen component acts as an irritant which causes eventual expulsion of the chorionic sac. Used medically, they are relatively safe (Barns 1967; Berthelsen and Ostervaard 1959), but fatalities can occur from air or fat embolism or from the toxic effects of absorption.

Substances taken by mouth or injection are legion. The old classification into 'ecbolics' and 'emmenagogues' is now quite redundant and most of the lists of substances are of historical interest only, as their efficacy is either nil or the dose needed to produce abortion is perilously near the fatal level. These include pennyroyal, tansy, rue, savin, laburnum, colocynth, aloes, castor oil, nutmeg, hellebore, cantharides, cotton root, wintergreen and turpentine. Many of these may cause purging, gastrointestinal irritation and general illness if taken in quantity, but have no specific action whatsoever on the uterus. There are other substances that have more chance of causing uterine contractions, though many of them are effective only on a late pregnancy, not at the usual time of 1–3 months when most abortions are sought.

Quinine can be dangerous, as the dosage required for any effect on the uterus is likely to cause cinchonism. Ergometrine has been known from ancient times to lead to abortion, though like most drugs its effectiveness is greater later in pregnancy. Excess dosage may cause peripheral vascular spasm and gangrene. Its availability to doctors and mid-wives is similar to pituitary extract, oestrogens, and – more recently – prostaglandins. Heavy metals, particularly lead, were used for abortion in the past. Plasters coated with a lead compound 'diachylon' were scraped to recover the metallic substances and ingested. Though abortion sometimes occurred, illness and death from acute and subacute lead poisoning was more common; this method has also become of historical interest only. It has been well said that most substances that


Damage to viscera
Fundal perforation (haemorrhage and peritonitis)
Sepsis to bloodstream
Air embolism
Infected endometrium and placenta
Pelvic thrombo-phlebitis
Uterine perforation
Toxic effects of soap, disinfectants, permanganate and other chemicals
Cervical perforation (haemorrhage)
Posterior fornix perforation (haemorrhage)
Vaginal perforation (haemorrhage)
Cervical shock (sudden cardiac arrest)
Instrumental interference

FIGURE 19.4 *Dangers of a criminal abortion.*

are successful in killing the fetus are likely to kill the mother as well.

A wide variety of medical substances have been used for abortion, including aminopterin, steroids, antimitotic drugs, such as vincristine and ergocornine, and other cytotoxic drugs used in malignant diseases. Even monoamine oxidase inhibitors have been reported as abortifacients. In all these, the autopsy findings in fatal cases will be non-specific or negative, and the history and toxicology provide virtually all the available evidence.

THE AUTOPSY IN ABORTION DEATHS

Where a death in pregnancy or the puerperium occurs, every effort should be made to obtain an autopsy, even if the death does not fall within the usual category of death reportable for medico-legal investigation. When a criminal abortion is suspected, then virtually every jurisdiction will require necropsy.

The usual full autopsy is performed, but a number of additional measures are required, varied to suit the particular circumstances. The fullest possible history is required and, where the death has taken place under medical care, a prior discussion with the clinician is vital. A careful external examination must be carried out, noting especially:

- Abnormal coloration of the skin, such as in the bronzing of clostridial septicaemia and the jaundice of liver damage.
- Signs and duration of pregnancy, such as abdominal swelling and breast changes.
- Signs of injury, including bruising or abrasion of the vulva from instrumentation, and vaginal bleeding. Burns on the abdomen or inner sides of the upper thighs may indicate efforts at resuscitation by hot-water bottles when a woman has suddenly collapsed during an illegal abortion.
- The vagina should be examined for signs of recent or current pregnancy, and attempted or successful recent abortion. Any fluid should be removed by pipette to be examined for soap and chemicals, such as antiseptics. A swab should be taken for microbiological culture.
- Where any possibility of air embolism is considered, pre-autopsy radiology of the chest and abdomen must be performed. Some pathologists would consider this obligatory in any death associated with pregnancy, as it is the best method of detecting air embolism by visualizing air bubbles in the heart, great veins in the thorax, inferior vena cava, peritoneal cavity and – possibly – pelvic veins. In the few centres where MRI or computed tomography is available for autopsy material, this may greatly increase the chance of detecting air in the vessels.

Where radiology is not possible, air must be sought by dissection methods, which are not so reliable. The thorax is opened carefully, making sure that removal of the costal cartilages and sternum does not damage the underlying mediastinum or open any of the veins at the thoracic inlet. The cardiovascular system is first examined for the presence of air. The classic method, discussed elsewhere in this book, is to open the heart chambers *in situ* under water poured into the pericardial sac. Escaping bubbles are then said to be indicative of air embolism, though the technique is by no means as reliable as past authors have claimed. In fact, if the post-mortem interval is short, in terms of a few hours, then any fatal air embolism will almost always be quite apparent from the frothy contents of the right ventricle when it is opened in the usual way. Appreciable delay allows absorption of air, as can be proved by the failure to find air in the heart on dissection, even after radiology has clearly indicated its presence. Of course, where any degree of decomposition has set in, which may be on the first day after death in hot countries, gases of putrefaction completely negate any chances of proving air embolism.

Before the organs are disturbed, the great veins of the abdomen should be inspected for bubbles, then the pelvic veins. The uterus itself may be crepitant and bubbles may be seen under the serosal surface or even under the parietal peritoneum of the pelvis. On opening the uterus, gas bubbles may be evident in the wall or placental bed, but this is later in the examination. The usual instructions in most forensic textbooks for opening the head first, carefully removing the calvarium and minutely inspecting the cerebral veins for air bubbles, can be totally disregarded, as this is yet another



FIGURE 19.5 *Ruptured tuba in (ectopic) pregnancy. Death due to massive intraperitoneal haemorrhage. (Reproduced by kind permission of Professor E Lignitz.)*



FIGURE 19.6 *Fetus and placenta in the abdominal cavity after ruptured tubal (ectopic) pregnany. Death due to massive intraperitoneal haemorrhage. (Reproduced by kind permission of Professor E Lignitz.)*

example of forensic mythology repeated from one book to the next, without critical evaluation. As discussed in Chapter 13, air embolism cannot occur in the cerebral veins and it was proved many years ago that air bubbles in those veins are artefacts caused by removing the calvarium.

The thorax and upper abdomen should be examined as usual, with particular attention to signs of infection. Blood cultures, and peritoneal and other swabs should be taken as indicated by the circumstances.

The pelvic organs should be removed *en bloc*, as in the examination of fatal rape victims. The lower end of the abdominal incision is carried on each side around the labia and into the cleft of the buttocks to meet beyond the anus. The dissection is taken along the superior pubic rami, which are then carefully sawn through a few centimetres laterally to the symphysis on each side, the cuts being continued down through the inferior rami. The central block of bone is removed and the perineal incision dissected deeply, so that the vagina, rectum and anus, uterus, tubes and ovaries can be lifted out in continuity, and removed for detailed dissection. The vagina is carefully opened along one side to avoid overrunning any midline injuries. Abrasions, bruises, lacerations and any foreign material are noted in the vagina, and any samples kept for chemical or microbiological testing. Any abnormality of the cervix is noted, especially instrument marks, such as forceps or volsellum teeth. The state of dilatation of the cervical canal is noted and the uterus opened, again keeping away from the midline if possible. The colour, size and texture of the uterus is noted, and the state of the interior is naturally vital. If the chorionic sac is still present, its integrity and the attachment to the deciduae are noted. If a fetus is present, this is examined separately for maturity and damage.

If no fetus is present, products of conception are sought and the state of the placental bed noted. Infection, bleeding and air crepitancy are all sought, and the appropriate ancillary investigations made. The tubes are then opened and any foreign fluid collected. The ovaries are examined and the state of any corpus luteum recorded. Finally, extensive histological specimens are taken from all organs and special stains employed where necessary, such as those for seeking amniotic squames in lungs and other organs. Blood, urine, liver and stomach contents are retained for analysis, should this be indicated.

AMNIOTIC FLUID EMBOLISM

Some deaths associated with childbirth or pregnancy are caused by the entry of amniotic fluid into the maternal circulation. The fluid contains fetal squames, lanugo, lipoid from the vernix, meconium, cells from chorion and amnion, and other cellular detritus. The solid elements are usually impacted in the lung capillaries, but rarely have been found in the systemic circulation, including embolization into the kidney, liver and brain. In addition to the solids, the actual fluid itself (which is naturally undetectable histologically) is blamed for the 'allergic' response that may cause such profound collapse, leading to death. Amniotic fluid embolism is also one of the most potent causes of disseminated intravascular coagulopathy, mentioned also in Chapter 13.

A variety of causes exist apart from the pelvic trauma of parturition, including rupture of the uterus, but instrumental interference late in pregnancy may also allow opening of the sinuses in the placental bed with consequent escape of amniotic fluid. Further details of the causes and mechanisms must be sought in obstetric works, but from the autopsy point of view, it is important both to bear the possibility in mind and to have techniques that will reveal the embolism after autopsy. The diagnosis is histological and depends upon identifying the squames detached from the fetal epidermis, which float freely in amniotic fluid. These can be seen in ordinary haematoxylin and eosin stained sections of the lung, but are much better visualized and a greater yield obtained if special staining methods are used, as described in Appendix 1. Fibrin deposition in many organs may occur as a result of the disseminated intravascular coagulation and careful search for this must be made, using fibrin stains. Immunohistochemical techniques have also been used in the lung sections to demonstrate human keratin-, meconium- and amniotic fluid-derived mucin as well as isolated trophoblastic cells in deaths due to AFE (amniotic fluid embolism) syndrome.

REFERENCES AND FURTHER READING

Adebahr G. 1969. [The forensic value of findings in the cadaver.] *Beitr Gerichtl Med* **25**:44–50.

Anonymous. 1999. Abortion in fact: levels, trend and patterns. In: *Sharing responsibility: women, society and abortion worldwide.* Alan Guttmecher Institute, New York, pp. 25–31.

Attwood HD. 1956. Fatal pulmonary embolism by amniotic fluid. *J Clin Pathol* **9**:38–46.

Baekgaard T. 1969. [Penalties for criminal abortion.] *Ugeskr Laeger* **131**:1069–70.

Barns H. 1967. Therapeutic abortion by means of soft soap pastes. *Lancet* **2**:825.

Benson MD, Kobayashi H, Silver RK, *et al.* 2001. Immunologic studies in presumed amniotic fluid embolism. *Obstet Gynecol* **97**:510–14.

Berthelsen H, Ostervaard E. 1959. Techniques and complications in therapeutic abortion. *Dan Med Bull* **6**:105–10.

Bowen DA. 1967. Medical investigation in cases of sudden death. *Br Med J* **2**:33–6.

Bowen DA. 1980. Criminal abortion. Fact or fiction? *Am J Forensic Med Pathol* **1**:219–21.

Breitenecker L, Husslein H. 1968. [Expert testimony as proof of previous pregnancies.] *Wien Klin Wochenschr* **80**:937–42.

Cameron J, Dayan A. 1960. Association of brain damage with therapeutic abortion induced by amniotic fluid replacement; report of two cases. *Br Med J* **1**:1010.

Cera G, Fruttero A, Rua S, *et al.* 1992. Flow cytometric studies in spontaneous abortions. Applications in the medico-legal practice. *Forensic Sci Int* **54**:167–75.

Cimbura G. 1967. Studies of criminal abortion cases in Ontario. *J Forensic Sci* **12**:223–9.

Davies S. 2001. Amniotic fluid embolus: a review of the literature. *Can J Anaesth* **48**:88–98.

Dayan AD, Cameron JM, Phillipp E. 1967. Fatal brain damage associated with therapeutic abortion induced by amniocentesis: report of one case. *Med Sci Law* **7**:70–2.

De Gennaro F. 1969. [Criminal abortion. A clinical case and medicolegal aspects.] *Minerva Ginecol* **21**:1002–5.

Demol R, Vandekerckhove D, Thiery M. 1968. [Various 'traps' in diagnosing pregnancy reactions.] *Med Leg Dommage Corp* **1**:282–9.

Eckert WG. 1985. The writings of Sir Bernard Spilsbury: Part II. *Am J Forensic Med Pathol* **6**:31–7.

Eliakis E, Coutselinis A. 1971. [Identification of meconium by the determination of acid phosphatase and spectrophotometric analysis.] *Med Leg Dommage Corp* **4**:163–8.

Fineschi V, Gambassi R, Gherardi M, *et al.* 1998. The diagnosis of amniotic fluid embolism: an immunohistochemical study for the quantification of pulmonary mast cell tryptase. *Int J Legal Med* **111**:238–43.

Garland IW, Thompson WD. 1983. Diagnosis of amniotic fluid embolism using an antiserum to human keratin. *J Clin Pathol* **36**:625–7.

Gastmeier G, Klein A, Falk H. 1969. [Contribution to inverse soap poisoning.] *Dtsch Z Gesamte Gerichtl Med* **65**:96–102.

Gerchow J, Schewe G. 1970. [Legal theory of value assessment and medical aspects of the need to protect the beginning of life.] *Beitr Gerichtl Med* **27**:61–71.

Holzer FJ. 1973. [Abortion using a bicycle pump on the mistress and unusual suicide of a blind man.] *Beitr Gerichtl Med* **30**:187–96.

Hunt AC. 1960. Amniotic fluid embolism. *J Forensic Med* **7**:74–7.

Huntington K. 1976. Forensic gynaecology. *Practitioner* **216**:519–28.

Huxley AK, Sibley MA. 1998. Alleged forgery of sonography report leads to elective abortion of late 23 week-old fetus. *J Forensic Sci* **43**:218–21.

Inoue H, Takabe F, Maeno Y, *et al.* 1989. Identification of fetal hemoglobin in blood stains by high performance liquid chromatography. *Z Rechtsmed* **102**:437–44.

Janssen W. 1967. [On the pathogenesis and forensic evaluation of brain hemorrhages following cerebral air embolism.] *Dtsch Z Gesamte Gerichtl Med* **61**:62–80.

Kenyeres I. 1976. [Various problems concerning maternal mortality during pregnancy.] *Morphol Igazsagugyi Orv Sz* **16**:120–5.

Khong TY. 1998. Expression of endothelin-1 in amniotic fluid embolism and possible pathophysiological mechanism. *Br J Obstet Gynaecol* **105**:802–4.

Kobayashi H, Ooi H, Hayakawa H, *et al.* 1997. Histological diagnosis of amniotic fluid embolism by monoclonal antibody TKH-2 that recognizes neuac alpha 2–6galnac epitope. *Hum Pathol* **28**:428–33.

Kocsis I, Argay I, Toth G. 1972. [Course of disease in an unconscious patient causing several problems.] *Morphol Igazsagugyi Orv Sz* **12**:209–11.

Kopecny J, Martincik M, Chalupa M, *et al.* 1970. [Induction of abortion using high doses of oxytocin.] *Cesk Gynekol* **35**:118–19.

Kumar GP, Kumar UK. 1994. Estimation of gestational age from hand and foot length. *Med Sci Law* **34**:48–50.

Kumar KU, Pillay VV. 1996. Estimation of fetal age by histological study of kidney. *Med Sci Law* **36**:226–30.

Kurucz E, Kosa F, Monostori E, *et al.* 1984. A new method in criminology: use of ELISA to detect AFP on different materials with monoclonal anti-alpha-fetoprotein. *Z Rechtsmed* **93**:117–21.

Lewis G. 2001. *Why mothers die. Report on confidential enquiries into maternal deaths in the United Kingdom 1997–1999.* RCOG Press, London.

Lewis G, Drife JO, Botting BJ, *et al.* 1998. *Why mothers die: report on confidential enquiries into maternal deaths in the United Kingdom 1994–1996.* TSO, London.

Lorente Acosta JA, Lorente Acosta M, Villanueva Canadas E. 1998. [The physician and medicine in the new penal code.] *Med Clin (Barc)* **111**:222–5.

Lunetta P, Penttila A. 1996. Immunohistochemical identification of syncytiotrophoblastic cells and megakaryocytes in pulmonary vessels in a fatal case of amniotic fluid embolism. *Int J Legal Med* **108**:210–14.

Mallach HJ, Pfeiffer KH. 1978. [The importance of air embolism as a primary and secondary cause of death.] *Med Welt* **29**:1391–6.

Marcinkowski T, Przybylski Z. 1968. [Teratoma as a cause of unjustified suspicion of abortion.] *Patol Pol* **19**:135–8.

Möttönen M, Isomäki AM. 1971. Amniotic fluid embolism, diagnosed by a new method. *Med Sci Law* **11**:35–7.

Nishio H, Matsui K, Miyazaki T, *et al.* 2002. A fatal case of amniotic fluid embolism with elevation of serum mast cell tryptase. *Forensic Sci Int* **126**:53–6.

Ohi H, Kobayashi H, Terao T. 1993. [A new histologic diagnosis for amniotic fluid embolism by monoclonal antibody TKH-2 that recognizes mucin-type glycoprotein.] *Nippon Sanka Fujinka Gakkai Zasshi* **45**:464–70.

Patel F. 1993. Artefact in forensic medicine. Fetal congenital abnormality. *Am J Forensic Med Pathol* **14**:212–14.

Rees PO. 1970. A case of poisoning by Epsom salt. *J Forensic Sci Soc* **10**:91–4.

Richard T, Rappolt MD, Sr. 1970. Clinical observation: apparent antagonism of ergotamine on the gravid uterus by LSD-25. *Eur J Toxicol* **3**:138–9.

Ronnau H, Wille R. 1980. [Psychological complications following abortion.] *Beitr Gerichtl Med* **38**:21–4.

Rosenzweig E, Stajduhar-Caric Z, Milicic D, *et al.* 1970. [Incidence of uterine perforations in criminal abortions.] *Rad Med Fak Zagrebu* **18**:221–4.

Russell DH. 1968. Law, medicine and minors. I. *N Engl J Med* **278**:35–6.

Schwerd W. 1965. The detection of soap abortions. In: Curry AS (ed.), *Methods of forensic science*, vol. 4. Interscience Publishers, London.

Shapiro HA. 1966. The diagnosis of death from delayed air embolism. *Acta Med Leg Soc (Liege)* **19**:207–11.

Simpson K. 1951. Air embolism. *Med Leg J* **19**:81–5.

Teare D. 1958. Death in criminal abortion. *Med Leg J* **26**:132–4.

Tesar J, Klir P, Doskocilova L. 1977. [Demonstration of neonatal blood.] *Soud Lek* **22**:9–11.

Toner PG. 1992. *The role of the histopathologist in maternal death. Maternal mortality – the way forward.* Royal College of Obstetricians and Gynecologists, London, Chapter 10.

Uszynski M, Zekanowska E, Uszynski W, *et al.* 2001. Tissue factor (TF) and tissue factor pathway inhibitor (TFPI) in amniotic fluid and blood plasma: implications for the mechanism of amniotic fluid embolism. *Eur J Obstet Gynecol Reprod Biol* **95**:163–6.

Zakharova OA, Bakshinskaia RE. 1968. [Mortality significance of acute renal insufficiency in criminal abortion.] *Sud Med Ekspert* **11**:18–20.

CHAPTER 20

Infanticide and stillbirth

- Stillbirth 439
- Functions of the pathologist in infanticide 440
- Definition of 'live birth' and 'separate existence' 442
- Concealment of birth 442
- The autopsy on a suspicious death of a newborn infant 442
- Infanticide by omission to offer proper care 445
- Proof of a separate existence 445
- Estimation of maturity 448
- References and further reading 449

Historically, infanticide has by no means always been a crime, and has been practised as a social and economic necessity since the dawn of humanity. The pathologist, however, has to deal with the practicalities of infanticide as they exist today. Though legal definitions vary among different countries, the medical concept of infanticide is uniform, being the deliberate killing of a newborn infant by the mother. In England and Wales, infanticide was not accepted as a legal entity in the criminal law until 1922. Before then all child killing was murder – and the convicted mother was liable to be sentenced to death until the Infanticide Act, which was re-enacted in a more satisfactory form in 1938 (see account by Kellett 1992).

In many other countries there is no specific infanticide legislation – even Scotland did not adopt the English statute, having a separate crime of 'child murder', but long before 1922 that country had held a more enlightened attitude towards the mentally stressed mother. In Japan, Funayama *et al.* (1994) have described cases of multiple, repeated infanticides by five mothers.

This book generally avoids territorial legal comparisons, but the foregoing facts serve to illustrate that the killing of a young child by the mother is a well-recognized medical and psychiatric phenomenon that distinguishes it from other types of homicide. The penalties should therefore be different and there is a profound responsibility laid upon the forensic pathologist called to examine such infants, to investigate the death with particular caution.

The substance of infanticide that has relevance to the pathologist is well set out in the English Infanticide Act 1938 (Section 1):

> Where a woman by any wilful act or omission causes the death of a child being under the age of 12 months, but at the time the balance of her mind was disturbed by having given birth or the effect of lactation, she may be dealt with as if she had committed manslaughter.

It should be noted that:

- Only the mother can benefit from this alternative to murder – not the father or any other person.
- The child has to be less than a year old, though in fact the majority of infanticides occur within hours or even minutes of birth.
- It has to be a 'child' – that is, a person with a separate existence living independently fully outside the mother's body.
- It must have died because of a wilful (deliberate) act of omission or commission.

All these provisos have an effect on the pathologist's task. Even in those jurisdictions where there is no formal infanticide legislation, there is usually recognition that the acts of a woman soon after childbirth, often in adverse conditions, are different from common murder.

STILLBIRTH

To clarify later definitions, a stillbirth is defined in English law and, from a medical point of view no doubt has a broadly similar description in other jurisdictions. In England and Wales, a baby is stillborn if after 24 weeks' gestation, 'it did not at any time after being completely expelled from its mother, breathe or show any other sign of life'. Theoretically, this is a medically unsatisfactory definition, as it could be alive when its head was born but die



FIGURE 20.1 *Newborn baby with umbilical cord and placenta, abandoned in a car park. It was wrapped in a curtain and though the head was in a plastic bag no signs of suffocation nor of live birth could be detected. The mother was never identified.*

before completion of expulsion, and therefore legally be a stillbirth. However, in practice this would be rare, as most stillbirths either die *in utero* or during the earlier stages of parturition. Stillbirths occur in about one in every 18 legitimate pregnancies in Britain, and are more frequent in illegitimate births and socially disadvantaged families.

FUNCTIONS OF THE PATHOLOGIST IN INFANTICIDE

To assist in identifying the mother, if she is unknown

Newborn infants found dead (especially in clandestine circumstances) are not necessarily the victims of infanticide. Those stillborn or dying naturally or from unintentional lack of care may be hidden or abandoned, a minor crime in Britain called ‘concealment of birth’. The autopsy, as well as artefacts discovered with the body, such as bags, blankets and newspapers can assist to a greater or lesser degree in the police search for the mother.

The apparent ethnic group of the child will be disclosed and blood grouping can be performed, which may assist by eliminating or helping to confirm the consanguinity of any putative mother. In the future, DNA profiling will add greatly to identification. The appearance of the cut end and any ligation of the umbilical cord (see below) may help to decide whether the birth was one where medical, nursing or only amateur attention was available. In spite of these clues, most abandoned newborn corpses fail to be linked to the mother, delay in discovery making both identification and evidence of live birth unattainable.



FIGURE 20.2 *Full-term newborn found wrapped in a blanket inside a shopping bag in a refuse container. The cord had been cut with a sharp instrument, but the child was not washed or fed. The lungs showed no positive evidence of respiration.*

To estimate the maturity of the child

Though any newborn infant, whatever the length of gestation, can be the victim of infanticide if born alive, it is obviously relevant to this issue if the fetus is too immature to have survived birth. In another context [Infant Life (Preservation) Act 1929, concerning child destruction], the age of viability in English law was taken as 28 weeks’ gestation, though this has now been reduced to 24 weeks as even younger fetuses can now survive with intensive medical support. If a child is shown to be that premature, there is a strong presumption that it would not long survive a birth away from medical attention.

To determine whether or not the child was stillborn and whether it had a separate existence

There is a presumption in English law that all infants are stillborn and, when a woman is charged with infanticide, the burden of proof is upon the prosecution to demonstrate that the child had a separate existence. Adelson (1974) states that the same legal situation exists in the USA, and gives the following useful and interesting commentary:

> Unless the pathologist has incontrovertible criteria of post-natal survival, e.g. well-expanded lungs, food in the stomach or vital reaction in the stump of the umbilical cord, he is legally bound not to diagnose live birth. Convictions for infanticide have been set aside when there has been any doubt whatsoever that the child was born alive. Many courts have pushed this proposition to the extent that the State has been given the burden of proving that the baby was born alive beyond any



FIGURE 20.3 *A stillborn child concealed by the mother after birth. The injuries around the neck were viewed with suspicion by the police, but are the result of fingernails being used in an attempt to assist self-delivery in an unattended birth.*

> possible doubt rather than beyond any reasonable doubt, the latter being the general level of proof required in a criminal prosecution.

Herein lies the most difficult task for the pathologist, one which has given rise to considerable controversy in forensic pathology.



FIGURE 20.4 *A putrefied newborn infant disposed of in a plastic bag in the countryside. There is no hope of determining whether it was live or stillborn with this degree of post-mortem decomposition. There was a strip of fabric knotted around the neck, but it is impossible to decide if that was related to the death, if the child was not stillborn.*



FIGURE 20.5 *A decomposed newborn infant found in a rubbish dump.*

To determine whether its death was due to natural causes or to any act of omission or commission

Where the pathologist claims to have proved separate existence (or at least, live birth), he has an additional burden in that he must show that death occurred from an act of commission or omission, The 'wilful' aspect is a matter for the lawyers, but it is for the pathologist either to demonstrate lethal injuries or to prove that some lack of care led to the death – often an impossible task. There is a considerable burden upon the investigating authorities when finding a hidden newborn infant if they wish to pursue an infanticide charge.

First, they must find the mother – often another impossible task. Then the pathologist must prove live birth, which is often impossible, especially in a decomposed body. To prove a separate existence is even more difficult and is rarely a purely medical decision. The firm diagnosis of death from wilful inattention is equally hard to make.

It is small wonder that only a small proportion of suspicious neonatal deaths ever reach the court – where few women are convicted, and those who are, rightly receive lenient and sympathetic treatment, usually consisting of probation and psychiatric support.

DEFINITION OF 'LIVE BIRTH' AND 'SEPARATE EXISTENCE'

There is no definition of live birth in English law, except by inference from the defined 'stillbirth', given earlier. Using the live birth as the converse of a stillbirth, the infant should have attained the gestational age of 24 weeks, but this is not a factor in 'separate existence' with which live birth is almost synonymous.

A child with a 'separate existence' would be an infant that had issued forth from its mother irrespective of its gestational age, and who breathed or showed any other signs of life after being completely expelled from the maternal passages – though the child could still be attached to the placenta within the mother. This is almost synonymous with a live birth, though medically all would agree that a child that was crying lustily, but with a foot still in the vagina, was undoubtedly live born even though it did not satisfy the legal criteria of a 'separate existence'.

Viability

Yet another medical and legal concept is that of viability, which is the potential ability of an infant to survive after birth. An immature fetus may be born alive, but be incapable of maintaining an independent existence. Naturally the stage of gestation at which this occurs varies not only with the condition of the particular fetus, but also with the state of medical knowledge and the facilities available at the relevant time and place.

In English law, a period of 24 weeks is fixed for the onset of viability, for the purposes of the Infant Life (Preservation) Act, 1929.

CONCEALMENT OF BIRTH

Mentioned earlier, this is a relatively minor crime in most jurisdictions and is basically an offence against registration, and perhaps public decency, in that the body of an infant is neither notified to the authorities nor accorded a proper burial or other form of disposal. The crime is the hiding of the body to conceal the fact of birth. It does not depend at all on live birth, separate existence or viability, and the law is not concerned about the cause of death or whether it was stillborn. One problem is the stage of gestation at which the 'child' becomes noticed by the law – obviously an early abortion is of no concern to anyone, except the family.

Though not specified in relation to concealment of birth, English law takes no regard of products of conception under 24 weeks' gestation. In a judicial decision (*R* v *Matthews*), it was held that a charge of concealment of birth could not be sustained at an age where the law did not require the (still)birth to be registered.

Whatever the legal ramifications, the forensic pathologist is not infrequently asked to examine dead infants in which he can neither prove live birth nor a wilful act that might have caused death. The only remaining charge, if he can show an age above that of viability, is 'concealment of birth'. This is the end result of the discovery of most decomposed babies, in the minority where the mother can be traced.

THE AUTOPSY ON A SUSPICIOUS DEATH OF A NEWBORN INFANT

A number of important matters need specific attention, over and above the usual meticulous autopsy procedure on any infant.

The coverings and any other associated articles with the infant must be examined and retained. Though this is mainly police business, the pathologist usually has the task of unwrapping the baby – often in a decomposed and offensive state – from the coverings of newspaper, plastic bags, rags or blankets. He must recover any foreign material or objects that may assist in the identification of the mother when the disposal has been clandestine.

When the baby has been found in a house or other building, he may need to visit the scene, preferably with the child still *in situ*. Numerous cases are on record of the infant being in a lavatory pan and, if there are head injuries or drowning, the circumstances must be evaluated.

The external examination is, as always, important. It is vital to assess the degree of putrefaction because if it is in any way decomposed, it will almost certainly be impossible to determine whether live birth had occurred. Decomposition must be distinguished from intrauterine maceration, as the latter is definite proof of stillbirth. If death occurred within 2–3 days before expulsion from the uterus, the appearances may be fairly normal, apart from general softening and histological evidence of general cellular autolysis.

When it has been dead for many days, the macerated fetus is usually a brownish-pink, rather than the greenish hue of putrefaction. The surface is slimy, blistered, desquamating and sometimes almost jelly-like. The joints are grotesquely loose and the cranial plates may be virtually detached beneath the scalp. Their over-riding, radiologically seen as 'Spaulding's sign', is characteristic, so that the head is shapeless. Rarely, a macerated fetus – which is normally sterile – may become infected if not expelled after the membranes rupture; it will then be born in a putrefied state.

External examination will next be directed at the cord and placenta, if present. The latter must be measured and weighed to estimate the maturity and any abnormalities, such as placental infarcts, noted as possible reasons for fetal death. The cord is important as an indicator of separate existence, if survival has been for an appreciable period. Even where early putrefaction renders evaluation of breathing impossible, vital signs in the cord may indicate live birth if survival reached 24–48 hours. Until this period, no evidence of cord separation is reliable, but after a day or so, a ring of reddening appears around the base of the cord and adjacent abdominal skin. This becomes more marked in the succeeding few days as the cord dries and shrivels, detachment taking place between 5 and 9 days. As most infants die or are killed within hours of birth, however, these signs are rarely of much practical use.

The severed end of the cord should be examined, as it may indicate whether the cord had been broken or actually cut. This is occasionally important if death is the result of head injuries and the defence on behalf of the accused mother claims that the child fell to the ground head first during a precipitate delivery. The length of the cord must be measured, especially if the placental segment is available, so that the distance from the vulva to the floor can be calculated. The average cord length is about 50 cm, but more than twice this length is not uncommon, as are much shorter ones. Naturally, if a ligature is present it indicates either the attendance of a professional or at least knowledgeable person, but this is rare in these cases. The severed end may be examined in the hand, but may also be floated out in water, to better study the detail of the detachment. Morris and Hunt (1966) conducted experiments on cords and determined that they could easily be broken by hand traction. A broken cord can show a clean transverse termination, but is usually ragged. If cut by a sharp instrument such as knife or scissors the cut may be clean, but may also be ragged if the instrument is blunt.

If the baby is examined as found, either at the scene or undisturbed in wrappings, it should be noted if the cord was coiled around the neck. Although it is usually unsafe to claim that death during delivery was from pressure on the neck from the cord, the fact must be noted and evaluated along with all other findings.

The skin may still have vernix caseosa present. This is not a useful observation but, if none is present, it may indicate that the child had been washed, which suggests survival for some time after birth.

Measurements are vital for an estimate of maturity. Weight, crown–heel, crown–rump, head circumference, and foot length are required.

Abnormalities incompatible with continued life may be obvious, such as anencephaly, severe spina bifida or abdominal ectropion. It is, however, often unsafe to assume that actual live birth, as legally defined, could not have taken place.

Injuries are obviously of prime importance as evidence of the 'act of commission', though most newborns seen by the pathologist will be free of such trauma. The types of injury perpetrated by distraught mothers are numerous:

- Strangulation presents the usual features of bruises and abrasions on the neck, though these may be minimal. The classical features of facial congestion, cyanosis, oedema and petechiae may be present, but are often absent, presumably because of the ease with which the vulnerable infant dies. Abrasions on the neck, however, may also be caused by the frantic efforts of the mother to deliver herself, leaving finger-nail marks on the infant's neck. A ligature may be used, which may still be in place. Again caution must be employed, as the fact of some object around the neck, though suggestive,



FIGURE 20.6 *Remains of a newborn infant, who was born during a weekend when the mother, a schoolgirl, was alone in her room in a boarding-school. After the birth she wrapped the child in a plastic bag. The following day she left for home and tried to burn the body in a stove but when that did not succeed she buried the partly burned body in a snowdrift where it was later found by a dog.*



FIGURE 20.7 *Definite infanticide, the child having fully respired before having this severe incised wound of the neck made with a kitchen knife.*

is not absolute proof of strangulation unless corroborative evidence of congestive and petechial signs in the face or skin, and tissue damage beneath the ligature is demonstrated. The explanation has been advanced in the past that a cloth ligature around the neck was an attempt to assist self-delivery by the woman in an obstructed labour.

- Smothering is almost impossible to prove, as the infant will almost never show conjunctival petechiae or other signs that may be seen in strangulation. Only if excessive pressure is applied, so that marks are left on the lips and face, can any evidence be retrieved. These must be definite intradermal or deep bruises, abrasions or marks within the lips and mouth – and not shadowy, vague variations in post-mortem staining. The arguments about criteria of suffocation in infants are further discussed in Chapter 14. Choking by the internal obstruction of the pharynx by various materials has been described in old reports, but it is excessively uncommon these days.
- Cutting and piercing is well known as a means of infanticide. Stabbing with scissors, either in the chest or neck, has been seen or even cutting the throat with a blade. The defence may be offered that the wounds were inflicted accidentally during frenzied efforts by the mother to cut the umbilical cord. Though not seen in Europe, deliberate infanticide has been described in India by clandestine stabbing by a long needle or pin into the spine, fontanelle, eye, or nose.



FIGURE 20.8 *A putrefied newborn infant with a scarf knotted tightly around the neck. (Reproduced by kind permission of Professor E Lignitz.)*

- Head injuries are relatively common. The mother may throw the child to the floor, or dash its head against a wall or other obstruction, sometimes by swinging it by the legs. This mode of death is similar to child abuse in older infants. The defence may be raised that the child fell to the ground, either from the mother's arms, but especially during a precipitate birth from the standing or crouching position. Though this defence sounds like a desperate excuse, the author can attest – no doubt in common with all doctors who have practical experience of childbirth – that some deliveries, especially in multiparous women, can occur with considerable speed and force. This is why the length of the cord needs to be measured, as it is obviously an effective brake on such a descent. There is no doubt, however, that cords have broken during precipitate birth, a reason for a careful inspection of the severed ends at every autopsy.

  The lavatory pan has special significance in this respect, as many unexpected births have taken place whilst the woman is sitting on the toilet. A common story is that the pregnant woman, often a teenage girl – is unaware that she is pregnant and goes to the toilet under the misapprehension that she has stomach pain from constipation. There is no doubt that some naive girls are genuinely ignorant of their gravid condition, and are shocked and devastated to the point of blind panic when a baby emerges into the pan.

  The question may then arise as to whether fatal head injuries on the infant can be accounted for by the descent into the lavatory. It is unlikely to produce the severe fracturing sometimes seen – and falling to the



FIGURE 20.9 *Frozen newly born infant found in a freezer by the children of the family. The child and placenta were packed and frozen in separate plastic bags, the umbilical cord is still attached. The family had moved twice after the birth of the child.*

floor in a precipitate delivery is also unlikely to produce fatal damage. Much depends on the severity and nature of the scalp and skull injury, and although it cannot be said that it is impossible for a fatal head injury to be caused in this way, it must be a rare event. Minor fractures of the parietal bones may occur in natural delivery if there is excessive head moulding. These are usually unassociated with internal brain or meningeal damage, and naturally there is no associated scalp damage.

- Drowning is another unusual form of infanticide, but is more often a way of disposing of an already dead child, either stillborn, a natural death or the victim of some other mode of infanticide. It may take place in any form of water, from a washbasin to the open sea. Most often the mother will use a household receptacle such as bowl, bucket or bath, but the infant may be taken out and disposed of in any source of open water, where delay in recovery may add decomposition to the pathologist's difficulties. In a recent case seen by the author (BK), the young parents admitted that the child was live born. After some hours, they wrapped the infant in a blanket with a brick and dropped it into a river. The partial remains, largely converted to adipocere, were recovered some 3 months later, there obviously being no prospect of offering any opinion upon either live birth or the cause of death. The only objective, but equivocal evidence, was the recovery of diatoms from the femoral bone marrow, which resembled those in the river water. Returning to the lavatory pan once again, cases are on record where the birth into the toilet led not to head injuries, but to drowning.

INFANTICIDE BY OMISSION TO OFFER PROPER CARE

This is both rare and almost outside the province of the pathologist's examination. If the infant is older than newborn, then deliberate starvation will leave obvious signs, but the proof of lack of care immediately after birth will be a matter of witnesses and clinical opinion. The only possible signs which the autopsy might reveal would be hypothermia (Chapter 17), and obstruction of the air passages by mucus or amniotic fluid.

PROOF OF A SEPARATE EXISTENCE

Strictly speaking, the pathologist can never demonstrate evidence of a separate existence in the English legal sense of complete expulsion from the mother, but it is usually taken to mean proof of live birth, specifically the attainment of breathing air. In the slightly older child the presence of food in the stomach would obviously prove a separate existence, but most autopsies are upon the recently newborn.

Changes in the cord have already been mentioned, but are of no use in the immediate post-partum period. Polson *et al.* (1985) make mention of the presence of 'extraneous material' in the deeper (secondary) bronchi as evidence of a stillbirth, on the grounds that, if this material, such as soil or sand, gained entry after respiration had commenced, the air in the deeper areas of the lung would prevent its ingress. The practicality of this appears suspect.

The unequivocal demonstration of breathing in a newborn infant is fraught with difficulty. Along with the estimation of the time of death, it has probably provoked more discussion, printed words and controversy than any other topic in forensic medicine. The controversy revolves around the 'hydrostatic test' on the lungs, in which it has been claimed since medieval times that, if the lungs float in water, then the infant breathed. There are modifications of technique, but this is the thrust of the claim. The authors' attitude must be stated at the outset: the test is of limited value, whatever modifications are made and it can at best be a suggestive pointer, but never a definitive test in itself.

There are too many recorded instances when control tests have shown that stillborn lungs may float and the lungs from undoubtedly live-born infants have sunk, to allow it be used in testimony in a criminal trial. Even one such failure negates the whole history of the test and the authors are saddened to contemplate the number of innocent women who were sent to the gallows in previous centuries on the testimony of doctors who had an uncritical faith in this crude technique. As this is such an important issue and one that is still contested today, the words of the late Professor Polson may be recalled from his notable textbook:

> The test was suspect even in 1900 and requires no detailed discussion, because it is now known to have no value. The lungs of the live-born, even those who have been known to live for days, may sink [Dilworth 1900; Randolph 1901] and those which float are not necessarily those of live-born infants . . . . It is therefore pointless to apply the hydrostatic test, which will impair the material for other and more important investigations.

Before dismissing the test so absolutely, there are some points both for and against its use as part of the feeble armamentarium that the pathologist has in determining this vital issue. First, the slightest degree of post-mortem decomposition immediately negates any interpretation of the flotation test. As so many potential infanticides are found hidden, buried or submerged, decomposition is more the rule rather than the exception, so the test cannot even be considered in a large proportion of cases. Even when obvious putrefaction with gas formation is not apparent, slight decomposition will still begin to produce gas on a microscopic scale from the second unrefrigerated day in temperate surroundings – and much earlier in hot climates. In recent years the advent of resuscitation attempts make the evaluation of breathing even more difficult or even impossible. The use of mouth-to-mouth revival, external cardiac massage and the administration of oxygen, completely negate any of the already fragile tests for respiration in a newborn infant.

On the positive side – assuming fresh tissue – the floating of the whole pluck of thoracic organs in water makes one tend to accept that respiration had taken place. This means that the attached heart, mediastinum and neck structures are also buoyed up by the lung – but in this case, it is almost invariable that the lungs are sufficiently aerated for this to be obvious on naked-eye inspection.

This is about the total extent of the usefulness of the hydrostatic test. The complicated instructions offered in many textbooks concerning cutting the lung into lobes and then into pieces, squeezing them with knife blades and even pressing them underfoot on the mortuary floor before floating them, all smatter of black magic and are a complete waste of time. Worse, they can simulate a false sense of scientific validity and even to an eventual miscarriage of justice.

The best way of seeking proof of respiration is to look at, to feel and to listen to the lungs. The lungs of a stillbirth are dark, small, heavy and liver-like, even though they may still float. They lie contracted against the mediastinum, though when the body is intact they must still fill the thoracic cavity, as the pliable rib cage pulls inwards and the diaphragm rises to eliminate the free space in the chest. Though this fact is seldom considered, it must be obvious that there can be no free space in the pleural cavities until the thorax is opened at autopsy. As soon as this is done, air enters the pleural sacs and the lungs then appear much smaller than the expanded chest cavity than is seen when the sternal plate is removed.



FIGURE 20.10 *A positive finding in a baby whose body was abandoned after death. Respiration had occurred but, on examination of the cranium, a tear in the tentorium was found with an adjacent meningeal haemorrhage, presumably caused by excessive moulding of the head during precipitate delivery.*

Unrespired lungs appear smaller than those that have breathed for a significant time, though there is a continuous range of expansion. According to Polson *et al.* (1985), unrespired lungs weigh something of the order of one-seventieth of the body weight; when aeration begins, the lung weight increases because of the increased vascular volume and become about one-thirty-fifth of the body weight. This seems at variance with actual measurements at autopsy as the combined weight of both lungs in an infant of average birth weight is about 40 g and, although there is a fairly wide variation between individuals, no combined lung weights approach 85 g, which would be one-thirty-fifth the weight of a 3000 g baby.

The texture of an unrespired lung is rubbery and uniform, with no paler, crepitant areas at the margins, which tend to be sharply angled. On slicing, the interior is uniform in colour and texture, being moist and resembling stiff strawberry jelly. On rubbing a small piece between the fingers close to one's ear, no crepitation is heard.

The lung that has respired will change quantitatively from the above appearances depending on the length of time and the depth to which breaths have been taken. Feeble or brief respiration will affect only the margins, whilst more robust or prolonged breathing may lead to total expansion. Even a single good breath can unfold some of the fetal pulmonary tissues – and of course, resuscitation, whether by mouth-to-mouth, chest compression or administration of oxygen, will actively inflate the lungs, dead or alive. Even ordinary handling of the dead baby may aspirate air into the lungs. Fully respired lungs will be obvious on inspection. The organs are pink or mottled, the medial edges overlapping the mediastinum and part of the pericardium, though not as fully as in the older neonate. The weight is greater, but not as much as recorded by Polson and colleagues, as described above. The edges of the lung, including the interlobar fissures, are more rounded by the expansion, compared with the angular margins of the unrespired organ.

The major change is in the colour and texture. It may be pink all over the surface or there may be patches of darker atelectasis under the pleura. The lung is spongy and resembles the familiar adult tissue. On cutting, the aerated texture is apparent, and on holding a piece to the ear, typical crepitance is heard on rubbing gently between the fingers.

The problem arises with the minimally respired lung, where the changes are intermediate between the two extreme states described above. The anterior margin best shows partial expansion, the areas such as the lingula, anterior diaphragmatic margin and the medial edge of the lower lobe sometimes being pinker and more expanded than the posterior parts. The most sensitive criterion is the ear crepitance test, but it is all a matter of degree as to whether the pathologist is impressed enough – having excluded any possibility of decomposition or resuscitation artefact – to consider that significant respiration has occurred.

Any doubts must be resolved in the direction of no breathing and, even in doubtful instances when the pathologist decides – on balance – that respiration has occurred, he should convey his uncertainty in the body of his report. As to the corroborative role of the flotation test, if performed, when the whole chest pluck floats, the descriptions of the lungs given above will usually indicate clearly that the lungs had breathed. A sinking lung will never correspond with a pink crepitant appearance, but what appears to be a dark, fetal lung may float. The test unfortunately tends to mislead more in one direction than the other, in that almost all lungs float irrespective of their appearance. To repeat the advice of Lester Adelson, whose experience and clarity of expression makes his voice one of the most respected in forensic pathology:

> Unless the pathologist has incontrovertible criteria of post-natal survival, e.g. well-expanded lungs, food in the stomach or vital reaction in the stump of the umbilical cord, he is legally bound not to diagnose live birth. Convictions for infanticide have been set aside where there was any doubt whatsoever that the child was born alive. Many courts have pushed this proposition to the extent that the state has been given the burden of proving that the baby was born alive beyond any possible doubt rather than beyond any reasonable doubt, the latter being the general level of proof required in a criminal prosecution.

Histological appearances of newborn lungs

Histology is not as helpful as might be expected in the problem of demonstrating the onset of breathing. It was formerly thought that the shape of the alveoli and the height of the lining epithelium would indicate whether they had been expanded by the passage of air, but this has proved to be a disappointing exercise. According to Shapiro (1977), the height of the epithelium and the shape of the alveoli are more a measure of fetal maturity than respiration at birth. The lung parenchyma develops in the fetus as a branching ramification of the trachea and at an intermediate stage – around 800 g body weight or 4 months' gestation – appear as gland-like structures with a cuboidal or columnar cell lining. The evolution to the thin-walled adult-type alveolus is complete before full term, or when the fetal weight is about 2500 g. The alveolar spaces may be found substantially distended even in fetuses who could not have breathed air, such as the one described by Shapiro that was found free in the maternal abdomen after rupture of the uterus. No intra-alveolar epithelium was visible and the lung could not be distinguished histologically from that of a child that had breathed.

Other authors have described the maturation of the fetal lung (Kuroda *et al.* 1965; Parmentier 1962; Ham and Baldwin 1941) and it is undisputed that fully expanded alveoli can be present before full term, even in infants who have not inspired air. After the fifth month, the glandular nature of the air sacs of the lumen are filled with amniotic fluid. In fact, there is evidence that amniotic fluid may be produced by the nascent pulmonary lining, because it is present even in cases of congenital bronchotracheal atresia. When breathing starts, the alveoli further enlarge, and the fluid is partly expelled through the bronchi and partly absorbed back into the pulmonary circulation. Ham (1950) and Shapiro (1947) point out that the finding of open alveoli with no cuboidal or columnar epithelium means that the fetus has passed the two-thirds stage of its maturation process, not that it has respired air.

Further proof is found in the histological appearance of sequestrated parts of lung tissue in infants, which were not connected to the bronchial system but which still showed alveolar ducts and alveoli (Potter and Buhlender 1941; Potter 1952). Fetal lung transplanted into the anterior chamber of an animal eye also developed alveoli with terminal bronchioles (Waddell 1949). Post-mortem handling has also been incriminated for the entry of air into fetal lungs. Apparently respired alveoli have been found in lung sections from a dead infant taken from the uterus of a dead mother.

Janssen (1977) agrees that resuscitation will lead to post-mortem aeration of the lungs, but claims that such artificial respiration cannot cause the alveoli of stillborn neonates to be perfectly and uniformly aerated. Against this view, however, is the undoubted patchy appearance of the lung expansion of many infants who have undoubtedly breathed for some time, so it is difficult to see how the two situations could ever be differentiated. Janssen's statement about the histological appearances is reasonable:

> According to the present level of knowledge and possibilities for examination, ventilation of the lungs alone cannot be taken as a certain indication of a live birth. Under various circumstances, lungs originally aerated can become devoid of air: conversely, the lungs of stillborn neonates can appear aerated. It is not possible to be certain in all cases.

In general, an infant who has breathed strongly for some time – probably hours in most cases – will have lungs that histologically resemble the older child with full, uniform, expansion of alveoli. In many infants who undoubtedly have lived and breathed for an appreciable time, however, there may be only patchy expansion, which corresponds to the uneven aeration seen macroscopically under the pleural surface. The difficulty arises when paradoxical appearances are seen, examples of which are illustrated in many textbooks. Thus an undoubted stillbirth may reveal quite extensive alveolar expansion, whilst a baby that unequivocally lived for some time may show totally collapsed air sacs.

In medico-legal work, though it is quite in order to refer to the usual state of affairs, when a criminal trial is in progress, the standard of proof is 'beyond reasonable doubt' and the well-documented exceptions just mentioned (as with the flotation test) make it unsafe to be dogmatic over a histological opinion.

ESTIMATION OF MATURITY

This is a necessary part of the autopsy, both as matter of record of the size and presumed age of the infant, but also as a legal requisite in those jurisdictions that require proof of viability before either stillbirth can be recorded or a charge of infanticide brought.

First, it must be accepted that – as at any time of life – morphological measurements are by no means infallible indicators of chronological age. Personal variations are compounded by sex, race and nutritional factors to prevent accuracy. The time of appearance of ossification centres is no longer as uniform as once thought. As with so many biological conditions, there is the typical 'bell-shaped curve' of probability, so that though most subjects will lie in the large central zone, there will be a progressively diminishing number at each extreme of the graph. It should be remembered that a female infant is usually at least 100 g less in weight at full term than the male, though individual differences in either sex can be far larger than this statistical variation. Twins, even those going to full term, are each lighter than a singleton child. The full-term singleton fetus, at **40 weeks' gestation**, will have the following vital specifications, subject to the above cautions:

- a weight of between 2550 and 3360 g
- crown–heel length of 48–52 cm
- crown–rump length of 28–32 cm
- head circumference of 33–38 cm
- the ossification centre in the lower end of the femur will almost always be present, being about 6 mm in diameter
- lanugo is absent or present only over the shoulders; head hair is about 2–3 cm long
- the testes are palpable in the scrotum; the vulval labia closes the vaginal opening
- the umbilicus is midway between xiphisternum and pubis
- there is dark meconium in the large intestine
- an ossification centre in the upper end of the tibia will be present in 80 per cent of full-term infants. The length of finger and toenails is an unreliable guide. More detailed information may be obtained from obstetric and paediatric texts.

At 36 weeks, the crown–heel length is about 45 cm and the weight around 2200 g. There will probably be ossification centres in the cuboid and capitate bones, often in the lower end of the femur and perhaps also in the upper end of the tibia.

At 28 weeks, the fetus is likely to be about 900–1100 g in weight, have a crown–heel length of 35 cm, a crown–rump length of 23 cm, and a foot length of 8 cm.

The old Haase rule-of-thumb for fetal age and size was that, up to the twentieth week, the length in centimetres was the square of the gestation period in (lunar) months. Beyond the twentieth week, the length in centimetres divided by five represents the age in months.

Examination of the ossification centres may be performed radiographically, which requires the advice of a radiologist, as the time of appearance may not be synchronous with visual identification of the centres. At autopsy it is usual to seek them directly, as follows: at the knee, the leg is flexed and a lengthwise cut made over the patella. The bones are pushed forwards through the cut, and transverse



FIGURE 20.11 *The pluck of thoracic organs from a known stillbirth in hospital. The lungs are firm and heavy with no crepitation when squeezed. Margin portions of lung floated in water, however, demonstrating the fallacy of the 'flotation test'.*



FIGURE 20.12 *Fetal maturity: up to the twentieth week the length of the fetus in centimetres is approximately the square of the age in months (Haase's rule).*

slices made with a knife through the cartilage of the lower end of the femur. If the ossification centre is revealed, the cuts should continue through plain cartilage above it until the diaphyseal centre is reached. This is to avoid mistaking the lower margin of the diaphyseal bone for the separate epiphyseal centre. The upper end of the tibia is then dealt with in a similar way.

In the foot, a cut is made in the axis of the limb up between the third and fourth toes into the ankle joint, to seek the cuboid bone. The talus and calcaneum can be entered by cuts across the upper dorsum of the foot when the latter is plantar-flexed. The centre in the calcaneum appears at about 7 months' gestation, that in the talus at about 7 months', and the cuboid at full term.



FIGURE 20.13 *Fetal maturity: by Haase's rule this 18 cm crown–heel fetus is about 4.5 months old.*



FIGURE 20.14 *Fetal maturity: this infant is 30 cm crown–heel length, which is approximately 6 months' gestation, as the length in centimetres beyond the fifth month is about five times the age in months.*

In assessing skeletal age in the fetus, the reference book of Fazekas and Kosa (1978) is invaluable. Other non-osseous methods of estimating maturity exist, such as the progressive development of surfactant-producing alveolar type II cells in fetal lungs (Betz *et al.* 1992).

REFERENCES AND FURTHER READING

Adelson L. 1974. *Pathology of homicide.* Thomas, Springfield.

American Academy of Pediatrics. 2001. Distinguishing sudden infant death syndrome from child abuse fatalities. *Pediatrics* **107**:437–41.

Betz P, Nerlich A, Wilske J, *et al.* 1992. Determination of fetal age by immunohistochemical estimation of surfactant-producing alveolar type II cells. *Forensic Sci Int* **53**:193–202.

Buris L, Torocsik I, Poczkodi S. 1979. Is the aeration of the lungs a reliable sign of live birth? *Z Rechtsmed* **83**:303–12.

Byard RW, James RA, Zuccollo J. 2001. Potential confusion arising from materials presenting as possible human remains. *Am J Forensic Med Pathol* **22**:391–4.

Castellana C, Kosa F. 1999. Morphology of the cervical vertebrae in the fetal-neonatal human skeleton. *J Anat* **194**:147–52.

Dilworth T. 1900. The flotation test. *Br Med J* **2**:1567.

Driever F, Dettmeyer R, Madea B. 2001. [Forensically relevant unexpected delivery after unrecognized or denied pregnancy.] *Arch Kriminol* **208**:174–81.

Fazekas G, Kosa F. 1978. *Forensic fetal osteology.* Akademiai Kiado, Budapest.

Ferreira GF, Rega RM, Mandarim-De-Lacerda CA. 1990. Allometry of hepatic weight growth in human staged fetuses. *Arch Ital Anat Embriol* **95**:223–8.

Funayama M, Ikeda T, Tabata N, *et al.* 1994. Case report: repeated neonaticides in Hokkaido. *Forensic Sci Int* **64**:147–50.

Gordon I, Shapiro H, Berson S (eds). 1988. *Forensic medicine: a guide to principles*, 3rd edn. Churchill Livingstone, London.

Ham A. 1950. *Histology*. Lippincott, Philadelphia, pp. 448–96.

Ham A, Baldwin K. 1941. A histological study of the development of the lung with particular reference to the development of the alveoli. *Anat Rec* **81**:369–79.

Janssen W. 1977. *Forensic histopathology.* Springer, Heidelberg.

Kellett RJ. 1992. Infanticide and child destruction – the historical, legal and pathological aspects. *Forensic Sci Int* **53**:1–28.

Kuroda S, Nagamori H, Ebe M, *et al.* 1965. Medicolegal studies on the fetus and infant with special reference to the histological characteristics of the lungs of liveborn and stillborn infants. *Tohoku J Exp Med* **85**:40–54.

Kuroki Y, Dempo K, Akino T. 1986. Immunohistochemical study of human pulmonary surfactant apoproteins with monoclonal antibodies. Pathologic application for hyaline membrane disease. *Am J Pathol* **124**:25–33.

Morris JF, Hunt AC. 1966. Breaking strength of the umbilical cord. *J Forensic Sci* **11**:43–9.

Oehmichen M, Gerling I, Meissner C. 2000. Petechiae of the baby's skin as differentiation symptom of infanticide versus sids. *J Forensic Sci* **45**:602–7.

Parmentier R. 1962. L'aeration neonatale due poumon. *Rev Belg Path Med Exp* **29**:121–244.

Perdekamp MG, Bohnert M, Ropohl D. 2000. [Discovery of externally unremarkable case of homicide of an infant.] *Arch Kriminol* **206**:160–7.

Polson C, Gee D, Knight B. 1985. *Essentials of forensic medicine*, 3rd edn. Pergamon Press, London.

Potter E. 1952. *Pathology of the fetus and newborn.* Year Book Publishers, Chicago.

Potter E, Bohlender G. 1941. Intra-uterine respiration in relation to the development of the fetal lung. *Am J Obstet Gynecol* **42**:14–22.

Randolph C. 1901. The flotation test for live birth. *Br Med J* **1**:146.

Shapiro H. 1947. The limited value of microscopy of lung tissue in the diagnosis of live and still birth. *Clin Proc* **6**:149–58.

Shapiro HA. 1977. Microscopy of human fetal lung and the diagnosis of postnatal respiration. In: Wecht C (ed.), *Legal medicine annual 1976*. Appleton Century Crofts, New York.

Tabata N, Morita M, Azumi J. 2000. A frozen newborn infant: froth in the air-passage after thawing. *Forensic Sci Int* **108**:67–74.

Waddell W. 1949. Organoid differentiation of the fetal lung: a histologic study of the differentiation of mammalian fetal lung *in utero* and in transplants. *Arch Pathol* **47**:227–47.

Yamauchi M, Usami S, Ikeda R, *et al.* 2000. Medico-legal studies on infanticide: statistics and a case of repeated neonaticide. *Forensic Sci Int* **113**:205–8.

Zhu BL, Maeda H, Fukita K, *et al.* 1996. Immunohistochemical investigation of pulmonary surfactant in perinatal fatalities. *Forensic Sci Int* **83**:219–27.

Zhu BL, Ishida K, Fujita MQ, *et al.* 2000. Immunohistochemical investigation of a pulmonary surfactant in fatal mechanical asphyxia. *Int J Legal Med* **113**:268–71.

Zhu BL, Ishida K, Quan L, *et al.* 2000. Immunohistochemistry of pulmonary surfactant apoprotein A in forensic autopsy: reassessment in relation to the causes of death. *Forensic Sci Int* **113**:193–7.

CHAPTER 21

Sudden death in infancy

- Definition of the sudden infant death syndrome (SIDS) 451
- Incidence of sudden infant death 451
- Factors influencing the risk of SIDS 452
- The case history in sudden infant death 453
- The scene of death and external findings 453
- Autopsy appearances 454
- Histological findings in SIDS 455
- Theories of causation 455
- The SIDS autopsy 456
- Medico-legal problems in cot deaths 456
- Addresses of counselling organizations 457
- References and further reading 457

This distressing condition has a variety of names and abbreviations. The one now most generally accepted is the 'sudden death in infancy syndrome', often shortened to (and pronounced as) 'SIDS'. An older title was 'SUD', standing for 'sudden unexpected death', but this in itself did not denote the infant connotations. Colloquially, SIDS is known as 'cot death' in Britain and 'crib death' in North America.

DEFINITION OF THE SUDDEN INFANT DEATH SYNDROME (SIDS)

Following one of the international conferences on the condition (held in Seattle in 1969) the following useful definition of the syndrome was proposed by Beckwith and is now generally accepted: 'the sudden death of any infant or young child which is unexpected by history and in whom a thorough necropsy fails to demonstrate an adequate cause of death'. Other definitions have been proposed later, e.g. the definition by the National Institute of Child Health and Human Development (NICHD) in 1989 emphasizing the necessity of the scene of death examination, and a three-tiered definition by Beckwith 1992 in Sydney, during the Second SIDS International Conference, dividing the SIDS into three different categories according to the age, the occurrence of similar deaths in siblings or other close relatives, and the presence of petechial haemorrhages and inflammatory lesions or other abnormalities found during the autopsy. The 'Stavanger definition', proposed during the Third SIDS International Conference in Stavanger, Norway 1994, lays stress on the importance of the investigation of the circumstances of death: sudden death in infancy unexplained after review of the clinical history, examination of the circumstances of death and post-mortem examination. However, when put to the vote during a subsequent SIDS Global Strategy Meeting in Stavanger, the original definition from 1969 received the most votes.

INCIDENCE OF SUDDEN INFANT DEATH

Until recent years, national death statistics were totally unreliable in providing data on the incidence of SIDS, as the nomenclature was confused, and the certifying habits of different pathologists and clinicians were extremely variable. According to a recent review by Rognum (1999), the percentage of sudden deaths in infancy that are diagnosed by various authors as pure SIDS varied between 2.5% and 70%. This situation still applies in many countries, especially those where high infant mortality from many causes overshadows sudden infant deaths. In advanced countries, the progressive and often dramatic reduction in total infant mortality since the beginning of the century has eliminated many infective, nutritional and congenital diseases to the point where the 'law of diminishing returns' has flattened out the mortality curve to a low level. Until 1990, there was little evidence that the SIDS rate had changed significantly for centuries or even millennia, so the pre-1990 straight-line incidence of SIDS became a far greater proportion of the total infant deaths compared with the early years of this century. In many advanced countries, SIDS is still the most common single cause of infant mortality after the perinatal period.

Until about 1990, Britain had a SIDS rate of about 2 per 1000 live births, but the risk varied considerably in various sections of the population. Golding *et al.* (1985) give a comprehensive table in their book of known variations in worldwide incidence before the recent dramatic decline. For example, in the USA there was an overall rate of 2.3/1000, though again this varies considerably from place to place, and among different ethnic and social groups. In Chicago the rate in 1969 was 3.4 compared with 1.4 in upstate New York in 1974. There is far more variation amongst ethnic groups in the USA, the rate being much higher among non-White infants. In Nebraska, for instance, the rate was 1.9/1000 Whites and 5.9/1000 in non-Whites. There is other evidence, however, that social differences are the predominant factor rather than any intrinsically ethnic cause.

As noted above, in Britain and several other European countries the SIDS rate has dropped remarkably in the past few years. In France there was a stagnation for post-neonatal mortality between 1979 and 1993 followed by a sharp decrease to 2/100 in 1995. In England and Wales there was a 69% fall in the sudden infant death rate between 1988 and 1992 from 2.01 to 0.63 and further down to 0.3 in 2000 (see Table 21.1).

The cause for this is obscure. It almost coincides with a vigorous publicity campaign by the Department of Health and the Foundation for the Study of Infant Deaths, which advocated sleeping babies on their back, not on the face and in avoiding overheating and smoking near the baby, as well as exhortations to seek medical advice whenever the infant was unwell.

However, the fall slightly antedated this campaign, so that the contribution of sleeping position, etc., to the decline is not fully understood, though there is other evidence from The Netherlands that recommendations about sleeping supine favourably affects the death rate. However, these same years have shown a series of very mild winters, which may also be a factor.

TABLE 21.1 *Infant mortality rates (per 1000 live births) in England and Wales in 1996–2000*

Infant mortality	1996	1997	1998	1999	2000	No.
Stillbirth	5.4	5.3	5.3	5.3	5.3	3203
Infant (under 1 year)	6.1	5.9	5.7	5.8	5.6	3399
Early neonatal (under 1 week)	8.6	8.3	8.2	8.2	8.2	1760
Neonatal (under 4 weeks)	4.1	3.9	3.8	3.9	3.9	2335
Post-neonatal (4 weeks–1 year)	2.0	3.0	1.9	1.9	1.8	1064
SIDS underlying cause (4 weeks–1 year)	0.6	0.5	0.4	0.4	0.3	203

Source: Office for National Statistics, Health Statistics Quarterly 05, Spring 2000.

FACTORS INFLUENCING THE RISK OF SIDS

Age

The age range in which sudden infant death occurs follows the usual ‘bell-shaped curve’ of most biological phenomena. As the Seattle definition stated, the ends of the curve lie at 2 weeks and 2 years, but these boundaries are far too wide for the great majority of victims. The peak incidence occurs at around 3 months and the time bracket of 2–7 months will encompass most cases. It is rare after 9 months, but deaths can occur well into the second year which, by all the criteria, can only be called ‘cot deaths’.

Similarly, a few small infants die unexpectedly and inexplicably before the first month, but it must be accepted that true SIDS is not a condition of the neonatal period. There is almost always a gap between the deaths that must be attributed as being a sequel to birth, and those that suddenly occur subsequently in babies who have apparently weathered that dangerous period successfully. It is obvious, however, that such an absolute distinction cannot be made, as premature and underweight infants have a higher risk of SIDS, and some perinatal deaths are indistinguishable from SIDS in that autopsy may reveal the same negative findings.

Sex

There is a slight but definite sex bias in the syndrome, showing the usual slight weighting against the male infant, which is a common feature of many conditions and at all ages. Most surveys have shown a ratio of 1:1.3 or thereabouts, with an excess of male infants. Some other investigations, however, have indicated equal numbers and one survey actually showed a slight excess of girls.

Twinning

There is a marked excess of deaths in a member of a twin pair as opposed to singletons. Figures have varied in different surveys, but the risk is at least twofold. In the author’s (BK) own hospital district (South Glamorgan), where a total birth survey is maintained, some years ago the increased risk was five times that for single babies. The reason for the excess among twins lies partly in the fact that physically disadvantaged infants, such as premature births and those of low birth weight are at greater risk; these two factors are often present in twins. There is no difference in incidence between identical or binovular twins. There have been at least ten reports of both twins having died of SIDS on the same day, and obviously reported cases are but a small fraction of those occurring. Some pathologists, almost exclusively in the USA, claim that simultaneous death in twins is indicative of homicide, but this view is not generally accepted.

Seasonal incidence

There is a marked seasonal variation in SIDS, the excess occurring in the colder, wetter months in temperate zones. In Europe and North America, most SIDS die between October and April, whilst in Australasia the monthly incidence is reversed. In tropical and subtropical zones, no clear pattern emerges, partly because many of the countries in these latitudes are relatively underdeveloped so have both high infant mortality, and often death certification and statistical records of lesser accuracy. SIDS undoubtedly occurs in the tropics, however, but the incidence is often swamped by that of more obvious disease. Returning to temperate zones, many efforts have been made to relate SIDS to changes of temperature and the incidence of respiratory infections in the community. The results are conflicting, but there seems little doubt that respiratory infections are a precipitating trigger in SIDS.

Social class and housing

This is not the place to expand upon the social epidemiology of cot death, but there is ample evidence that lower levels of social disadvantage, as measured by occupation and housing quality, are strongly related to the incidence of SIDS. It is difficult to reconcile these epidemiological factors with the numerous pathological theories and the few facts concerning the aetiology of sudden infant death.

THE CASE HISTORY IN SUDDEN INFANT DEATH

The history is usually brief and remarkably similar from case to case. The infant is either quite well on the preceding day or (in about half the victims) has trivial symptoms, usually of upper respiratory infection or a bowel upset. Even these symptoms may be overstated, as the history is of necessity taken retrospectively from distraught parents trying to rationalize the tragedy.

The story usually records that the infant was put to sleep in the evening and was found dead in the morning when a parent first visited it. Alternatively, the baby was given an early morning feed when it appeared well, but was later found dead in its sleeping place. Most infants are found dead in the first half of the day, before mid-morning. A minority die (or are found dead) in the afternoon and evening. Death can be rapid and silent. Though most victims die unobserved, the author's (BK) experience can confirm that a number of cases indicate that an infant observed to be quite well at a given moment can be found dead within 5 minutes, and cases are on record of SIDS occurring in hospital and even in a physician's arms.

THE SCENE OF DEATH AND EXTERNAL FINDINGS

The scene of the death is rarely available for examination in its original state. When found, the child is naturally either rushed to a doctor or a hospital, or an ambulance team arrives and attempts resuscitation, again usually hurrying to a hospital casualty department.

When found, a few children have slight oedema fluid exuding from the mouth. This may sometimes be blood-tinged, and frank bleeding – apparently from a congested mouth or pharyngeal vessel – is occasionally seen.

Stomach contents may be present in the mouth, nostrils or on the face, but this must not be assumed to be a cause of death (from aspiration), as is discussed below. The hands of the child are often found to be clenched around fibres from the bedclothes, as if there were spasmodic agonal grasping movements.

Some children are found under the bedclothes, even huddled upside down at the foot of the cot. Again, this has no significance, as thousands of healthy infants habitually sleep in this way without suffering SIDS.

A number of infants have been found moist with sweat and even with a raised body temperature. The significance of this is not known, but part of the recent preventative advice given in Britain, is to avoid overwrapping and overheating.

There are no external findings of significance. The face may be pale or slightly cyanosed or congested: there are no petechial haemorrhages in the face or eyes. The posture at death is not necessarily relevant, even if the initial sleeping position is important in the aetiology – some are found face down and may have a pallid area around the mouth and nose where pressure has prevented post-mortem hypostasis from settling. This develops after death and on no account must be misinterpreted as a pressure mark indicating suffocation.

AUTOPSY APPEARANCES

These have given rise to much controversy over the years. Essentially the gross findings are nil, almost by definition. If any significant pathological lesion is found on naked-eye examination, the death ceases to be a true SIDS, and is categorized as whatever lesion was discovered. The proportion of 'explained' cot deaths varies greatly with the pathologist, though this variation is more in relation to microscopic than gross findings. Of all babies found dead in their sleeping place, that is, 'cot deaths', most will be true SIDS, but a few will have a significant pathological condition. The relative proportions of these two subsets varies from pathologist to pathologist. Many would accept that about 15 per cent reveal some pathological lesions at autopsy, though this is not to say that those lesions – sometimes slight – were a factor in the death. For example, some mild congenital heart lesion or the presence of Down's syndrome is occasionally revealed, but this is not to say that they were causative. Thus almost all SIDS are cot deaths, but not all cot deaths are SIDS.

The external appearances have already been discussed and are essentially negative, apart from inconstant froth at the lips and nostrils, and fibres sometimes clenched in the fists. The length, weight and other physical measurements are of no direct relevance, though naturally they must always be carefully recorded as in any other infant autopsy, for it may transpire that the death was not a typical SIDS.

Internally, the findings are again non-specific in a typical SIDS. A large number of reports now exist on the microscopy, microbiology and biochemistry of the syndrome, but no diagnostic criteria have yet been confirmed. The following naked-eye features may be present at autopsy:

- Petechial haemorrhages on the visceral pleura.
- Petechial haemorrhages in the thymus gland.
- Petechiae or larger ecchymoses on the epicardial surface of the heart, especially posteriorly. These petechiae have been the subject of intense controversy since they were first described in infant deaths by Tardieu in 1855, but they are almost certainly agonal in origin. One explanation suggests that they are the result of forced inspiratory efforts against a closed airway, the latter being either from laryngeal spasm or from a collapsed pharynx in hypotonic infants, but neither of these hypotheses has been substantiated. Petechiae in the thorax are found in about 70 per cent of true SIDS infants. Thymic haemorrhages are often prominent, the organ being studded with both petechiae and larger ecchymoses: it has been claimed recently that in SIDS as opposed to mechanical suffocation, the haemorrhages are in the thymic cortex, rather than the medulla, but few pathologists accept this.



FIGURE 21.1 *Subpleural haemorrhages – the original 'Tardieu spots'. These are far more pronounced than those seen in adult lungs, being taken from a case of SIDS, in which 70 per cent of cases exhibit these lesions.*

- Gastric contents, usually milk-curds, in the air passages. All too often this has been used by some pathologists as the definite cause of death, but there is no evidence that it is the reason for the death. It is either an agonal regurgitation or even a post-mortem phenomenon. In a series of 100 consecutive autopsies, including adults and children, the author (BK) found gastric contents in greater or lesser amount in no less than 25 per cent of cadavers, almost all of which had quite satisfactory pathological lesions to account for death. This aspect is discussed in more detail in Chapter 14.
- Respiratory infections in the form of inflamed laryngeal or tracheobronchial mucosa are not common, but are macroscopically evident in some SIDS victims. If the infection is severe enough to produce pus and especially if there are obvious inflammatory changes in the lung parenchyma, then the death is removed from the SIDS category into a fatal chest infection group. The finding of minimal 'inflammatory' cells on microscopy must be viewed with caution. Some pathologists undoubtedly lay too much emphasis on sparse or small collections of leucocytes in the peribronchial zones. In control infants, small foci of lymphocytes are common and can

be disregarded. It is usually the lung histology that causes the variations in the proportions of 'cot deaths' that are classified as true 'SIDS'.
- Pulmonary oedema is common, though usually moderate in intensity. The surface of the lungs often shows patchy sublobular partial collapse, with areas of blue lung alternating with better-aerated pink zones.

In some infants dying unexpectedly, abnormalities such as Down's syndrome, congenital heart disease or other chronic systemic disease are found. The problem then is to decide whether the death should be ascribed to 'SIDS' or to the obvious disease, even though there is no evidence that such a disease should have suddenly caused death. There is a natural temptation to use an established lesion to explain the death, especially as both doctors and parents tend to be less unhappy with a specific disease process than with the rather nebulous diagnosis of 'SIDS'.

In most cases, however, there is no real reason why an infant with Down's syndrome, perfectly well one night, should be found dead the following morning – and many relatively mild (and often previously undiagnosed) congenital defects similarly are unlikely to cause death in such an abrupt manner. It is probably more logical to assume that SIDS has occurred in a child with Down's or a septal defect, or whatever. It may be accepted that this defect may be one factor among the many involved in SIDS, and therefore it is probably reasonable to enter 'SIDS' in Part I of the certificate and add the other lesion in Part II, as a contributory cause.

HISTOLOGICAL FINDINGS IN SIDS

Again a huge and controversial topic, there have been numerous papers on the microscopic appearances in SIDS. Much of this is pure research material and is often irreproducible by other workers.

Most interest has focused on the lung changes and especially evidence of pulmonary inflammation. The frequency with which positive findings are made depends upon the criteria threshold of the observer, as mentioned earlier. Peribronchiolar cell infiltration is the main finding and some workers claim to find an abnormal cellular response in the majority of SIDS material. Others, more used to the less equivocal appearances in adults, fail to attach significance to marginal increases in cell population in the peribronchial zone.

Many of the other findings are inconstant and claimed by a variety of researchers. For example, Richard Naeye (1973) supported his hypothesis of chronic hypoxia by finding thickened pulmonary artery walls, gliosis in the brainstem, retention of brown fat in the adrenals and abnormalities in the carotid body. Changes in the myocardium, adrenals, parathyroids and liver have all been described, but have either not survived critical assessment, appear incompatible with clinical and epidemiological data, or fail to be reproducible in subsequent investigations.

THEORIES OF CAUSATION

Since the mid-1970s more than 5000 articles have appeared concerning sudden infant death and one now needs review papers, such as those published by Valdes-Dapena, merely to keep up with mainstream research. Theories include allergy to cow's-milk proteins, house-mite allergy, deliberate suffocation, spinal haemorrhages, botulism, calcium deficiency, selenium deficiency, biotin deficiency, vitamin E deficiency, vitamin C deficiency, vitamin D deficiency, thiamine deficiency, hypoglycaemia, hypothyroidism, magnesium deficiency, carbon monoxide poisoning, carbon dioxide poisoning, overlaying, pharyngeal hypotonia, nasal obstruction, tracheobronchitis, respiratory syncytial virus, prolonged sleep apnoea, deficient or abnormal pulmonary surfactant, cardiac conduction defects, sodium overload in feeds, narrow foramen magnum, hyperthermia, hypothermia, influenza infection, metabolic enzyme defects, immunodeficiency, hypogammaglobulinaemia and many others.

In 1989 and again in 1994, press publicity in the UK drew considerable attention to claims that fungal growth on certain antiflammable chemicals used on cot mattress covers produced gases containing arsenic and antimony, and some chemical analyses showed that antimony could be demonstrated in some SIDS tissues. However, a causative link has not been proven and the theory fails to fit the epidemiology – especially as SIDS has been occurring for hundreds and probably thousands of years before mattress covers existed. Reports of cot deaths can be found in sources as ancient as the Old Testament and twelfth century Welsh literature.

In the 1970s and early 1980s, one hypothesis gained widespread favour and was beginning to gain general acceptance. This was the claim that some infants, with poor respiratory drive, suffered from exaggeration of the normal periods of apnoea that all infants have during sleep. A complex mechanism was built up in which progressive hypoxia and failure to respond adequately to hypercapnia and hypoxia drove the sleeping infant into a descending spiral of hypoxia–apnoea–hypoxia, which ended in bradycardia and cardiac arrest. Respiratory infections, sleep, and nasal obstruction contributed to an acute-on-chronic state of hypoxia, which histological findings claimed to substantiate.

This attractive theory was largely deflated, however, when prospective studies of infants with sleep apnoea and other respiratory problems were found to have no greater risk of SIDS than normal controls. The theory led to a great popularity of apnoea alarms, which parents of subsequent children following a SIDS loss have insisted on using. There is no evidence that they have any beneficial effect, other than reassurance of the parents; indeed, in some instances, the stress of waiting for the alarm to sound and the many false alarms, have led to marital problems.

In the present state of knowledge, it seems that SIDS is the final common pathway that leads to death in infants who have been compromised by a number of deleterious factors, which have to come together in one baby at one time in order to summate to a fatal outcome. The factors may be quite different in each case, but all manifest themselves in terminal acute cardiorespiratory failure.

Some of the factors are known such as sleep, which depresses the brainstem, and virus infections – especially of the respiratory tract – which provide a viraemia, reduce oxygenation and may narrow the effective airway lumen by mucus and exudate. Other factors are 'constitutional', in that many SIDS victims are physically compromised in some way, often since fetal life, being premature and of low birth weight (though most SIDS are neither of these). Other factors from the long list given above may operate in certain circumstances, such as botulism which may be relevant in some 5 per cent of SIDS in California.

It is thus futile to search for 'the cause' of cot death, as there is no single cause, but a galaxy of factors that vary from death to death, though the mediating terminal mechanism appears to be the same.

One of the most difficult aspects is the failure of pathological explanations to be compatible with epidemiological findings. It has been shown that non-specific health-care improvements reduce the incidence of SIDS, such as in the excellent ante-natal and post-natal services of countries such as Finland and Holland, which have the lowest SIDS rates – and the Sheffield project, where it was shown that the strongest factor in reducing incidence was the use the family made of the health services.

As far as the pathologist is concerned, his function is to perform a meticulous autopsy, to exclude any overt natural disease or injuries, and to offer sympathetic advice to those parents who want an explanation of the syndrome in comprehensible lay terms. There are several highly proficient counselling charities in Britain, the USA and other countries, who can provide literature and direct help to parents – and who also usually support most of the ambitious research schemes now operating.

THE SIDS AUTOPSY

The routine for an autopsy on a sudden infant death follows that for any infant and is little different from that in suspected child abuse. Indeed, exclusion of child abuse is a prime consideration as, although there is no aetiological connection between the two conditions, sometimes occult abuse – or sometimes genuine accident – may present as a 'cot death'. Some pathologists, both forensic and paediatric, insist on a whole-body radiological survey before commencing the autopsy and, where such facilities exist, this is a wise precaution. Full measurements of the infant are essential, as in all paediatric autopsies, to monitor the size-for-age of the child and to compare it with centile graphs, provided the birth weight is known.

The gross examination is the standard meticulous scrutiny of all external surfaces, orifices and organs. A full histological survey is vital, with even more blocks being taken than may be the norm for many forensic pathologists. The lungs in particular should be extensively sampled and six blocks is a bare minimum for these organs. In addition to histology, swabs should be taken from the major air passages and the lung parenchyma for microbiological culture, and heart blood may also be cultured. The middle ears should always be opened and a swab taken if infection is suspected. A separate piece of lung should be sent for virological culture. Where there has been any history of gut upset before death, a sample of ileal contents should be cultured. It has to be said that the return on such microbiological and virological studies is poor in terms of positive findings, both because of the post-mortem interval and because many of the micro-organisms found may be indistinguishable from commensals or post-mortem contaminants.

Similarly, by the very definition of SIDS, significant histological findings are absent. If a definite pathological lesion capable of causing death is discovered, the case is removed from the SIDS category and classified according to the disease process discovered. The problem arises when 'significant' or 'definite' has to be defined, as the criteria threshold of different pathologists varies considerably, especially where the diagnosis of an inflammatory condition in the lungs is concerned.

MEDICO-LEGAL PROBLEMS IN COT DEATHS

Differentiating SIDS from external suffocation

This is the oldest problem in cot death and one that is virtually insoluble on purely pathological grounds. The signs of infant suffocation are usually nil and the signs of SIDS are nil, so in a completely negative autopsy no reliable criteria exist. The presence of intrathoracic petechiae has little or no diagnostic value, in spite of one recent report that claims to distinguish SIDS from mechanical suffocation by the confinement of petechiae to the thymic cortex in SIDS. In any event, they are usually absent in known suffocation, such as those caused by a plastic bag over the head, yet some 70 per cent of SIDS have serosal petechiae.

In Britain, there are about 1000 cot deaths each year and probably up to 10 000 in the USA. The majority of these were found dead with the face uncovered, and in a posture where the mouth and nose are not obstructed. No one believes that all these children have been smothered by their parents; therefore, as petechiae are valueless for differentiation, it is not possible for an autopsy to state or even suggest that any particular child has been suffocated. This naturally presupposes the absence of facial bruising, scratching or other positive signs that would immediately remove the case from the SIDS category.

It is possible for circumstantial or other non-medical history to suggest or confirm deliberate suffocation, though this is extremely rare and not the concern of the pathologist. A caution must be offered about maternal confessions of smothering, however, as several instances are known where such a confession has proved totally false, the desperately bereaved woman in her grief and recrimination deluding herself in order to rationalize an inexplicable tragedy.

Multiple sudden infant deaths

Again, these pose a formidable problem for pathologist, paediatrician and investigating authority. Statistically, a mother will suffer a second cot death in her family every quarter of a million births, but a number of families are reported where three or even four siblings have died inexplicably. There is always the possibility of foul play in such circumstances, though some familial metabolic or other genetic disease – albeit obscure – is more likely. Even where no trace of the latter can be detected by the most exhaustive medical investigations, if the autopsies reveal no positive evidence of mechanical suffocation or other demonstrable cause of death, the pathologist cannot then substantiate any allegation of mechanical suffocation. He can – and should – express his concern to the investigating authorities but, if their investigations produce no corroborative evidence, it is pointless for him to continue to support a hypothesis that cannot be substantiated by any pathological evidence.

Counselling of parents

Many families, primarily the mother, have an intense desire to know why their baby died, a need that is often unfulfilled by any official contacts, such as with a coroner. Once any legal processes are complete, there is no reason why a pathologist should not meet and offer explanations to the parents of a child upon whom he has performed an autopsy. Often an earlier line of counselling is provided by a paediatrician, but some mothers wish to talk to the pathologist. Both Adelson (1974) and Knight (1983) have advocated that the pathologist should make himself readily available for this purpose, though some pathologists shelter behind an imaginary legal barrier to avoid what should be an ethical obligation.

ADDRESSES OF COUNSELLING ORGANIZATIONS

- The Foundation for the Study of Infant Deaths, Artillery House, 11–19 Artillery Row, London, SW1P 1RT, UK (Tel.: General enquiries: +44 020 7222 8001; 24-hour helpline: +44 020 7233 2090; Fax: +44 020 7222 8002). http://www.sids.org.uk/
- National Sudden Infant Death Syndrome Resource Center (NSRC), 2070 Chain Bridge Road, Suite 450, Vienna, VA 22182, USA (Tel.: (703) 821 8955; Fax: (703) 821 2098). sids@circlesolutions.com
- SIDS International (SIDSI). http://www.sidsinternational.minerva.com.au/

REFERENCES AND FURTHER READING

Adelson L. 1974. *The pathology of homicide: a vade mecum for pathologist, prosecutor and defense counsel.* W. B. Saunders, Philadelphia.

Althoff H. 1980. *Sudden infant death syndrome*. Gustav Fischer Verlag, Stuttgart.

American Academy of Pediatrics. 2001. Distinguishing sudden infant death syndrome from child abuse fatalities. *Pediatrics* **107**:437–41.

Arnestad M, Andersen M, Vege A, *et al.* 2001. Changes in the epidemiological pattern of sudden infant death syndrome in southeast Norway, 1984–1998: implications for future prevention and research. *Arch Dis Child* **85**:108–15.

Arnestad M, Vege A, Rognum TO. 2002. Evaluation of diagnostic tools applied in the examination of sudden unexpected deaths in infancy and early childhood. *Forensic Sci Int* **125**:262–8.

Bartholomew SE, MacArthur BA, Bain AD. 1987. Sudden infant death syndrome in south east Scotland. *Arch Dis Child* **62**:951–6.

Bass M, Kravath RE, Glass L. 1986. Death-scene investigation in sudden infant death. *N Engl J Med* **315**:100–5.

Bergman AB. 1972. Unexplained sudden infant death. *N Engl J Med* **287**:254–5.

Bergman AB, Beckwith RE, Rae CO (eds). 1969. *Sudden infant death syndrome. Proceedings of the Second International Conference, Seattle 1969.* University of Washington Press, Seattle.

Bergman AB, Ray CG, Pomeroy MA, *et al.* 1972. Studies of the sudden infant death syndrome in King County, Washington. 3. Epidemiology. *Pediatrics* **49**:860–70.

Betz P, Hausmann R, Eisenmenger W. 1998. A contribution to a possible differentiation between sids and asphyxiation. *Forensic Sci Int* **91**:147–52.

Bonser RS, Knight BH, West RR. 1978. Sudden infant death syndrome in Cardiff, association with epidemic influenza and with temperature – 1955–1974. *Int J Epidemiol* **7**:335–40.

Boulloche J, Mallet E, Basuyau JP, *et al.* 1986. The value of serum IgE assay in milk aspiration and the sudden infant death syndrome. *Acta Paediatr Scand* **75**:530–3.

Bowden KS. 1953. Sudden or unexpexted deaths in infancy. *J Forensic Med* **1**:19–27.

Byard R, Krous H. 1999. Suffocation, shaking or sudden infant death syndrome: can we tell the difference? *J Paediatr Child Health* **35**:432–3.

Byard RW, Beal SM. 2000. Gastric aspiration and sleeping position in infancy and early childhood. *J Paediatr Child Health* **36**:403–5.

Byard RW, Krous HF (eds). 2001. *Sudden infant death syndrome: problems, progress and possibilities*. Arnold, London.

Camps FE, Carpenter RJ (eds). 1972. *Sudden and unexpected deaths in infancy. Proceedings of the Cambridge Symposium.* John Wright, Bristol.

Cecchi R, Bajanowski T, Kahl B, *et al.* 1995. CMV-DNA detection in parenchymatous organs in cases of SIDS. *Int J Legal Med* **107**:291–5.

Coombs RR, McLaughlan P. 1982. The enigma of cot death: is the modified-anaphylaxis hypothesis an explanation for some cases? *Lancet* **1**:1388–9.

DeSa DJ. 1986. Isolated myocarditis as a cause of sudden death in the first year of life. *Forensic Sci Int* **30**:113–17.

Dettmeyer R, Kandolf R, Schmidt P, *et al.* 2001. Lympho-monocytic enteroviral myocarditis: traditional, immunohistological and molecular pathological methods for diagnosis in a case of suspected sudden infant death syndrome (SIDS). *Forensic Sci Int* **119**:141–4.

Durigon M, Caroff J, Derobert L. 1971. [Pulmonary histology in 123 suspicious or sudden deaths in infants under one year of age.] *Med Leg Dommage Corp* **4**:287–93.

Emery JL. 1983. The necropsy and cot death [editorial]. *Br Med J Clin Res Ed* **287**:77–8.

Emery JL. 1986. Families in which two or more cot deaths have occurred. *Lancet* **1**:313–15.

Ferris JA. 1972. The heart in sudden infant death. *J Forensic Sci Soc* **12**:591–4.

Ferris JA. 1973. Hypoxic changes in conducting tissue of the heart in sudden death in infancy syndrome. *Br Med J* **2**:23–5.

Ferris JA, Aherne WA, Locke WS, *et al.* 1973. Sudden and unexpected deaths in infants: histology and virology. *Br Med J* **2**:439–42.

Fleming PJ, Gilbert R, Azaz Y, *et al.* 1990. Interaction between bedding and sleeping position in the sudden infant death syndrome: a population based case-control study [see comments]. *Br Med J* **301**:85–9.

Forsyth KD, Weeks SC, Koh L, *et al.* 1989. Lung immunoglobulins in the sudden infant death syndrome. *Br Med J* **298**:23–6.

Freed GE, Meny R, Glomb WB, *et al.* 2002. Effect of home monitoring on a high-risk population. *J Perinatol* **22**:165–7.

Froggatt P, James TN. 1973. Sudden unexpected death in infants. Evidence on a lethal cardiac arrhythmia. *Ulster Med J* **42**:136–52.

Froggatt P, Lynas MA, Marshall TK. 1971. Sudden unexpected death in infants ('cot death'). Report of a collaborative study in Northern Ireland. *Ulster Med J* **40**:116–35.

Gardner PS. 1972. Viruses and the respiratory tract in sudden infant deaths. *J Forensic Sci Soc* **12**:587–9.

Golding J, Limerick S, McFarlane A. 1985. *Sudden infant death.* Open Books, Shepton Mallet.

Gruenwald P, Hoang NM. 1960. Evaluation of body and organ weights in perinatal pathology. I. Normal standards derived from autopsies. *Am Clin Pathol* **34**:247–53.

Guilleminault C, Heldt G, Powell N, *et al.* 1986. Small upper airway in near-miss sudden infant death syndrome infants and their families. *Lancet* **1**:402–7.

Guntheroth WG. 1973. The significance of pulmonary petechiae in crib death. *Pediatrics* **52**:601–3.

Hanzlick R. 2001. Pulmonary hemorrhage in deceased infants: baseline data for further study of infant mortality. *Am J Forensic Med Pathol* **22**:188–92.

Harrington C, Kirjavainen T, Teng A, *et al.* 2002. Altered autonomic function and reduced arousability in apparent life-threatening event infants with obstructive sleep apnea. *Am J Respir Crit Care Med* **165**:1048–54.

Hatton F, Bouvier-Colle MH, Blondel B, *et al.* 2000. [Trends in infant mortality in France: frequency and causes from 1950 to 1997.] *Arch Pediatr* **7**:489–500.

Hollander N. 1988. Beta-endorphin in the brainstem, pituitary, and spinal fluid of infants at autopsy: relation to sudden infant death syndrome. *Forensic Sci Int* **38**:67–74.

Iwadate K, Doy M, Ito Y. 2001. Screening of milk aspiration in 105 infant death cases by immunostaining with anti-human alpha-lactalbumin antibody. *Forensic Sci Int* **122**:95–100.

James TN. 1968. Sudden death in babies: new observations in the heart. *Am J Cardiol* **22**:479–506.

Kariks J. 1988. Cardiac lesions in sudden infant death syndrome. *Forensic Sci Int* **39**:211–25.

Kato I, Groswasser J, Franco P, *et al.* 2001. Developmental characteristics of apnea in infants who succumb to sudden infant death syndrome. *Am J Respir Crit Care Med* **164**:1464–9.

Kelly DH, Shannon DC. 1982. Sudden infant death syndrome and near sudden infant death syndrome: a review of the literature, 1964 to 1982. *Pediatr Clin North Am* **29**:1241–61.

Knight B. 1972. Legal and administrative problems in the 'cot death syndrome'. *J Forensic Sci Soc* **12**:581–3.

Knight B. 1983. *Sudden death in infancy: the cot death syndrome.* Faber and Faber, London.

Koch LE, Biedermann H, Saternus KS. 1998. High cervical stress and apnoea. *Forensic Sci Int* **97**:1–9.

Koehler SA, Ladham S, Shakir A, *et al.* 2001. Simultaneous sudden infant death syndrome: a proposed definition and worldwide review of cases. *Am J Forensic Med Pathol* **22**:23–32.

Krous HF, Nadeau JM, Silva PD, *et al.* 2002. Infanticide: is its incidence among postneonatal infant deaths increasing? An 18-year population-based analysis in California. *Am J Forensic Med Pathol* **23**:127–31.

Ladham S, Koehler SA, Shakir A, *et al.* 2001. Simultaneous sudden infant death syndrome: a case report. *Am J Forensic Med Pathol* **22**:33–7.

Langlois NE, Ellis PS, Little D, *et al.* 2002. Toxicologic analysis in cases of possible sudden infant death syndrome: a worthwhile exercise? *Am J Forensic Med Pathol* **23**:162–6.

Lie TJ, Rosenberg H, Erikson E. 1976. Histopathology of the conduction system in the sudden death syndrome. *Circulation* **53**:3–8.

Lundemose JB, Lundemose AG, Gregersen M, *et al.* 1990. Chlamydia and sudden infant death syndrome. A study of 166 SIDS and 30 control cases. *Int J Legal Med* **104**:3–7.

Maron BJ, Fisher RS. 1977. Sudden infant death syndrome (SIDS): cardiac pathologic observations in infants with SIDS. *Am Heart J* **93**:762–6.

Marshall TK. 1972. Epidemiology of cot deaths: the Northern Ireland study. *J Forensic Sci Soc* **12**:575–9.

Mitchell EA, Thompson JM. 2001. Parental reported apnoea, admissions to hospital and sudden infant death syndrome. *Acta Paediatr* **90**:417–22.

Naeye RL. 1973. Pulmonary arterial abnormalities in the sudden-infant-death syndrome. *N Engl J Med* **289**:1167–70.

Naeye RL. 1980. Sudden infant death. *Sci Am* **242**:56–62.

Norvenius SG. 1987. Sudden infant death syndrome in Sweden in 1973–1977 and 1979. *Acta Paediatr Scand Suppl* **333**:1–138.

Oehmichen M, Gerling I, Meissner C. 2000. Petechiae of the baby's skin as differentiation symptom of infanticide versus sids. *J Forensic Sci* **45**:602–7.

Ogbuihi S, Zink P. 1988. Pulmonary lymphatics in SIDS – a comparative morphometric study. *Forensic Sci Int* **39**:197–206.

Opdal SH, Rognum TO, Torgersen H, *et al.* 1999. Mitochondrial DNA point mutations detected in four cases of sudden infant death syndrome. *Acta Paediatr* **88**:957–60.

Oyen N, Markestad T, Skaerven R, *et al.* 1997. Combined effects of sleeping position and prenatal risk factors in sudden infant death syndrome: the Nordic Epidemiological SIDS Study. *Pediatrics* **100**:613–21.

Parish WE, Barrett AM, Coombs RR, *et al.* 1960. Hypersensitivity to milk and sudden death in infancy. *Lancet* **2**:1106–10.

Peterson DR, Beckwith JB. 1973. Magnesium deprivation in sudden unexpected infant death. *Lancet* **2**:330.

Polak JM, Wigglesworth JS. 1976. Letter: Islet-cell hyperplasia and sudden infant death. *Lancet* **2**:570–1.

Protestos CD, Carpenter RG, McWeeny PM, *et al.* 1973. Obstetric and perinatal histories of children who died unexpectedly (cot death). *Arch Dis Child* **48**:835–41.

Rasten-Almqvist P, Eksborg S, Rajs J. 2000. Heart weight in infants – a comparison between sudden infant death syndrome and other causes of death. *Acta Paediatr* **89**:1062–7.

Raven C, Maverakis NH, Eveland WC, *et al.* 1978. The sudden infant death syndrome: a possible hypersensitivity reaction determined by distribution of IgG in lungs. *J Forensic Sci* **23**:116–28.

Richards ID, McIntosh HT. 1972. Confidential inquiry into 226 consecutive infant deaths. *Arch Dis Child* **47**:697–706.

Rintahaka PJ, Hirvonen J. 1986. The epidemiology of sudden infant death syndrome in Finland in 1969–1980. *Forensic Sci Int* **30**:219–33.

Rognum TO (ed.). 1995. *Sudden infant death syndrome, new trends in the nineties*. Scandinavian University Press (Universitetsforlaget AS), Oslo.

Rognum TO. 1999. [Crib death or cot death in the nordic countries. A forensic pathologist's point of view.] *Ugeskr Laeger* **161**:6612–18.

Sadler DW. 1998. The value of a thorough protocol in the investigation of sudden infant deaths. *J Clin Pathol* **51**:689–94.

Saternus KS, Koebke J, von Tamaska L. 1986. Neck extension as a cause of SIDS. *Forensic Sci Int* **31**:167–74.

Sawaguchi T, Fujita T, Sawaguchi A, *et al.* 2000. The epidemiological study on registered cases of sudden infant death syndrome (SIDS) in Tokyo: examination of the effect of autopsy on diagnosis of SIDS and the mortality statistics in Japan. *Forensic Sci Int* **109**:65–74.

Simson LR, Jr, Brantley RE. 1977. Postural asphyxia as a cause of death in sudden infant death syndrome. *J Forensic Sci* **22**:178–87.

Sinclair-Smith C, Dinsdale F, Emery J. 1976. Evidence of duration and type of illness in children found unexpectedly dead. *Arch Dis Child* **51**:424–9.

Southall DP. 1983. Identification of infants destined to die unexpectedly during infancy: evaluation of predictive importance of prolonged apnea and disorders of cardiac rhythm or conduction. *Br Med J* **286**:1092–6.

Steinschneider A. 1972. Prolonged apnea and the sudden infant death syndrome: clinical and laboratory observations. *Pediatrics* **50**:646–54.

Steinschneider A, Weinstein SL, Diamond E. 1982. The sudden infant death syndrome and apnea/obstruction during neonatal sleep and feeding. *Pediatrics* **70**:858–63.

Sturner WQ. 1971. Some perspectives in 'cot death'. *J Forensic Med* **18**:96–107.

Sturner WQ, Dempsey JL. 1973. Sudden infant death: chemical analysis of vitreous humor. *J Forensic Sci* **18**:12–19.

Summers CG, Parker JC, Jr. 1981. The brain stem in sudden infant death syndrome. A postmortem survey. *Am J Forensic Med Pathol* **2**:121–7.

Sunderland R, Emery JL. 1981. Febrile convulsions and cot death. *Lancet* **2**:176–8.

Urquhart GE, Grist NR. 1972. Virological studies of sudden, unexplained infant deaths in Glasgow 1967–70. *J Clin Pathol* **25**:443–6.

Urquhart GE, Logan RW, Izatt MM. 1971. Sudden unexplained death in infancy and hyperimmunization. *J Clin Pathol* **24**:736–9.

Urquhart GE, Izatt MM, Logan RW. 1972. Cot death: an immune-complex disease? *Lancet* **1**:210.

Valdes-Dapena M. 1977. Sudden unexplained infant death, 1970 through 1975 an evolution in understanding. *Pathol Annu* **12**(Pt 1):117–45.

Valdes-Dapena M. 1982. The pathologist and the sudden infant death syndrome. *Am J Pathol* **106**:118–31.

Valdes-Dapena M. 1985. Are some crib deaths sudden cardiac deaths? *J Am Coll Cardiol* **5**:113B–17B.

Valdes-Dapena M. 1986. Sudden infant death syndrome. Morphology update for forensic pathologists – 1985. *Forensic Sci Int* **30**:177–86.

Valdes-Dapena MA. 1973. Editorial: Sudden, unexpected and unexplained death in infancy – a status report – 1973. *N Engl J Med* **289**:1195–7.

Valdes-Dapena MA. 1980. Sudden infant death syndrome: a review of the medical literature 1974–1979. *Pediatrics* **66**:597–614.

Variend S, Pearse RG. 1986. Sudden infant death and cytomegalovirus inclusion disease. *J Clin Pathol* **39**:383–6.

Vawter GF, McGraw CA, Hug G, *et al.* 1986. An hepatic metabolic profile in sudden infant death (SIDS). *Forensic Sci Int* **30**:93–8.

Wedgwood RJ, Benditt EP (eds). 1963. *Sudden death in infancy. Proceedings of the 1963 Seattle Conference.* United States Department of Health and Welfare, Bethesda.

CHAPTER 22

Fatal child abuse

- General aspects of child abuse 461
- Modes of death in child abuse 462
- The range of injuries in child abuse 462
- Surface bruising 462
- Skeletal damage in child abuse 464
- Bone diseases and infant fractures 468
- Head injury in child abuse 469
- Visceral injury in child abuse 472
- Damage to eyes, ears and mouth 472
- Burns in child abuse 474
- Bite marks in child abuse 474
- Other injuries in child abuse 474
- The autopsy in child abuse 475
- References and further reading 476

There is now a vast collection of publications on the child abuse syndrome, including international journals devoted to the topic. Most of this interest concerns the clinician, as child abuse is now a major concern in paediatrics. When no intervention is offered, an abused child has up to a 10 per cent risk of having eventually fatal injuries, so unfortunately the forensic pathologist will be involved in this tragic problem from time to time. This chapter will deal solely with the physical manifestations of the child abuse syndrome as seen at autopsy, though naturally these will in large measure coincide with the non-fatal injuries seen by clinicians.

GENERAL ASPECTS OF CHILD ABUSE

Though the modern phase of recognition of the syndrome dates only from the middle decades of this century, almost all the classical features were described by Tardieu in 1860 (see Knight 1986). In 1946, Caffey published his well-known first paper and, from then on, an avalanche of articles led to the present intense awareness of the problem that throws into stark contrast the apparent unawareness of the medical profession during the previous century.

Though definitions are variable, it can be said that the ‘child abuse syndrome’ (also known as the ‘battered baby’ or ‘non-accidental injury in childhood’) exists when an infant or child suffers repetitive physical injuries inflicted by a parent or guardian, in circumstances that exclude accident. Most of the fatal victims are young, more than two-thirds being under 3 years of age (Kempe *et al.* 1963; Lauer *et al.* 1974; Brown 1976; Helfer *et al.* 1977).

The syndrome includes, of course, psychological and sexual abuse, but the forensic pathologist can only be concerned with physical damage, some aspect of which has led to death. Though all homicides of children are ‘child abuse’ in the broad sense, the term is usually reserved for a fatal outcome in those who have suffered repetitive ill-treatment, though admittedly some cases span the borderline between chronic injuries and a single episode of trauma.

The definition of ‘child abuse’ is itself controversial, as what is unacceptable now may well have been considered valid and even desirable discipline in Victorian times. However, serious physical injury must be wrong, irrespective of societal attitudes.

Even so, for a pathologist to label an injury as ‘child abuse’ or ‘non-accidental injury (NAI)’ is to be rather pejorative and judgemental, so perhaps ‘adult-induced injury’ might be a more neutral description, which leaves decisions as to motivation to those who possess a wider picture of the whole circumstances. Having said that, the more gross forms of injury are self-evidently ‘abuse’ but, in lesser degrees of trauma, it may be impossible to differentiate deliberate battering from inexpert rough handling, albeit contributed to by exasperation, panic or even attempts at resuscitation.

Though it is vital to recognize non-fatal child abuse, because of the need for intervention to prevent the 60 per cent recurrence rate and 10 per cent mortality rate, it can be almost as tragic to falsely accuse and/or convict parents or guardians where the injuries were non-culpable.

There has sometimes been perhaps some excess of zeal on the part of paediatricians, radiologists, accident surgeons and pathologists to overinterpret injuries and scenarios that had an alternative and less sinister explanation. Though it is natural and vital for doctors to protect children and their siblings, medical opinion has to remain free from emotive bias and be confined within the bounds of what can be proved in each individual case, or injustice may be done. Some years ago, a situation developed where even innocent parents were afraid to take their accidentally injured child to a doctor, for fear of the euphemism 'non-accidental injury' being applied.

MODES OF DEATH IN CHILD ABUSE

The majority of deaths are caused manually, either by hitting or beating with the hands, shaking, throwing, dropping and – less often – by burning or suffocation. It is exceptional for death to be caused by the impact of a blunt instrument, though non-fatal bruises from beating with a strap, for instance, are sometimes seen. Shooting, strangling and stabbing are characteristic of classical homicide, which is distinct from the child abuse syndrome.

The most common mode of death is head injury. Next in frequency is rupture of an abdominal viscus, leaving a wide range of miscellaneous injuries to account for the small remainder.

THE RANGE OF INJURIES IN CHILD ABUSE

Concentrating on autopsy findings, the various types of trauma will be described, though many will not in themselves have caused or even contributed to death. Their recognition is none the less vital as, at the end of the examination, they may well be the decisive factors that may distinguish an accident from deliberate maltreatment.

SURFACE BRUISING

One of the classic aphorisms in the study of child abuse was stated by the forensic pathologists, Cameron, Johnson and Camps (1966), who said: 'The skin and bones tell a story which the child is either too young or too frightened to tell.'



FIGURE 22.1 *Multiple fingertip bruises on the chest and abdominal wall of an infant left with a male babysitter. The child was ill on the mother's return and died during admission to a hospital casualty department (see also Figures 22.4 and 22.5).*

Skin bruising is the most common injury and may be seen almost anywhere on the child's body. There are, however, certain sites of predilection which help to strengthen the diagnosis of abuse:

- Bruising around the limbs, especially the wrist and forearms, upper arms, thighs and – in small infants – around the ankles. These places form convenient 'handles' for an adult to grip the child. In the small infant the lower leg bruises may indicate that the child has been held by the leg or ankle in order to swing it – and may be associated with head injuries. The older child, as an adult, may be gripped by the upper arms in order to be shaken.
- The buttocks are a frequent site of bruising from hand smacks or beating with a strap. Bruises on the thigh are less common, but on the outer side may signify slaps and on the inner, possible sexual interference.



FIGURE 22.2 *Bruising of wrist and back of the hand after maltreatment by mentally ill mother (see also Figures 22.3 and 22.6).*



FIGURE 22.3 *Bruising of upper extremity after maltreatment by mentally ill mother (see also Figures 22.2 and 22.6).*

- The face is often bruised, especially the cheeks and mouth area, from slaps, which may also be present on the forehead and ears. Associated damage to the mouth and eyes is common. Bruising of the scalp is harder to see because of the hair, but is often part of deeper head injury.
- Bruises on the chest, abdomen and neck are usually from finger pressure rather than slaps or blows. Those on the abdomen and lower chest may be associated with deep visceral injury. Bruises may be of any size or type, but a common variety in child abuse is the small discoid lesion about 1–2 cm in diameter; these were once called 'sixpenny bruises' from the size of coinage at that time. These are caused by impact or pressure from the finger-pads of adults, and may be seen in groups around the limbs and on the neck, chest or abdomen.



FIGURE 22.4 *Injuries found at autopsy of an infant left with a male babysitter showing a generalized haemoperitoneum.*

Bruises from slapping or punching may be larger and irregular. Occasionally, a partial or even almost whole handprint may be seen outlined in bruises on the buttocks or trunk.

The age of bruises is an important issue in child abuse because:

- The observed age may be at variance with the history given by a parent, so increasing the suspicion of a non-accidental event.
- Bruises of different ages indicate episodes of injury at different times, one of the hallmarks of child abuse that usually continues over a period.

Though it is impossible to be accurate about the absolute age of a bruise, those of markedly different colours cannot have been inflicted during the same episode. The interpretation of patterns and the ageing of bruises are more fully considered in Chapter 4, but any bruise with yellow coloration must be more than 18 hours since infliction.



FIGURE 22.5 *The infant shown in Figures 22.1 and 22.4 showing a full-thickness tear extending through the liver. Rupture of an abdominal viscus is the second most common mode of death in child abuse, head injury being the most frequent.*

SKELETAL DAMAGE IN CHILD ABUSE

This is the second part of the aphorism about battered children as, both clinically and pathologically, diagnosis is largely a radiological matter. Just as a whole-body survey is needed in the live victim, so it is essential before an autopsy on a suspected fatal case of child abuse. Some pathologists would recommend a radiological skeletal survey on all infants prior to autopsy if they had not been under constant clinical care for some well-recognized natural disease. This would include all sudden infant deaths but, because of lack of facilities and finance, many pathologists have to confine their requests for such extensive radiology to those deaths in which there was some possibility of abuse, though this decision may lead to injuries being missed.

The range of skeletal injuries seen in child abuse is wide and there are very extensive publications on the subject, including at least one textbook by Cameron and Rae (1975) and a section on the radiology by Evans and Knight (1981).

Worlock *et al.* (1986) compared fractures in 35 abused children with 826 controls and found that the abused were all under 5 years old, whereas 85 per cent of the others were more than 5 years. The abused infants were more likely to have multiple fractures, and to have bruising of the head and neck. Rib fractures were almost confined to abused children, when major chest trauma was excluded. Spiral fractures of the humeral shaft were more common, though classical chipped metaphyses were uncommon. They concluded that one in eight infants under 18 months of age with a fracture had been abused.

The following is a summary of the more important bony lesions.

Fractures of the skull

Skull fractures are common in fatal child abuse, often in association with intracranial haemorrhage, usually subdural, though numerically less than half of infants with subdural haematomata have skull fractures (Harwood-Nash *et al.*). He found that of 4465 childhood head injuries, 1187 had skull fractures, but that there was little correlation with neurological signs and intracranial damage, subdural haemorrhage (SDH) being twice as frequent in the non-fracture cases.

Fractures have been discussed in relation to head injuries in Chapter 5, but some particular features in child abuse must be mentioned, as it is a controversial subject, especially when such cases come to trial.

The most common fracture lies in the occipitoparietal area, but the differentiation from accidental falls is impossible on anatomical or radiological grounds alone, in spite of the dogmatic claims of some radiologists. An infant's skull is more flexible than that of an adult and may absorb some impacts without fracturing. Occasionally, a parietal bone may 'dimple' inwards without cracking, much as a table-tennis ball may be dented with a thumb. The skull of a child is much thinner than that of an adult, even though the brain size and weight is greater relative to the postcranial mass. This means that there are two opposing factors operating:

- Because of the thin skull, less force is required for fracturing.
- Because of the elasticity or 'springiness' of the skull, recovery from distortion caused by impact is greater, so



FIGURE 22.6 *Fractured skull of an infant after repeated blows against the floor by mentally ill mother (see also Figures 22.2 and 22.3).*

more force is needed to fracture the pliable bone, relative to its thickness.

Notwithstanding the flexibility, however, it remains a fact that an infant skull will fracture with the application of much less mechanical force than would be needed to fracture a mature skull. In addition, because the cranium is more easily deformed, a momentary depression of the skull can impinge upon the underlying brain (including membranes), damage it and return to its original shape so that, even in the absence of a fracture, brain damage is more likely to occur.

There is now a large literature on infant fractures (especially of the skull) in relation to child abuse, some of it contradictory.

One aspect that arouses much controversy is the height of a passive fall which can (a) fracture a child's skull and (b) cause brain damage. The two injuries are certainly not synonymous, as it is clear that most fractures, both in infants and adults, are not accompanied by any brain damage or neurological effects. However, forces that can cause a skull fracture certainly **can** – though not **must** – cause brain or meningeal lesions, and it is impossible to forecast what will happen following a fall of even minor magnitude.

Though many paediatricians will deny that a passive fall from adult waist level – or even higher – can cause either skull fracture or intracranial damage, there is experimental proof and witnessed cases on record where this has occurred.

In respect of skull fractures, Weber (1984) experimentally dropped dead infants from a horizontal position at only 'table height' (82 cm, 34 inches) onto a variety of surfaces and found that fractures were common. Fifteen infants less than 8 months old were dropped passively from a horizontal position onto concrete, carpet and linoleum; all developed cranial vault fractures in various positions. Though most fractures were in the parietal bones, some extended into the occipital bone. In 1985, Weber again dropped dead infants from 82 cm (34 inches) onto soft cushioning, such as 10 cm (4 inches) thick foam mat and 8 cm (3.2 inches) thick double blanket. Fractures were much less frequent, as was to be expected, but still one occurred on the thick foam and four out of 25 drops onto the folded blanket, all from only 82 cm (34 inches).

Reichelderfer *et al.* (1979) indicated that serious head injuries in playgrounds can occur when the impact force exceeds 50 G; a fall of only 7.5 cm (3 inches) onto concrete can generate 100–200 G and one of 0.3 m (a foot) no less than 475–500 G.

In 246 falls of infants under 5 years from bed or low structures less than 90 cm (36 inches) high, Helfer *et al.* (1977) found no serious injuries or deaths. Of these, 161 occurred at home and 175 had some injury, including two skull fractures. In 85 hospital falls, there were 28 injuries, with one skull fracture. Nimityongskul and Anderson (1987) investigated 76 childhood falls in hospital, 75 of which were younger than 5 years. The height of fall was between 30 and 91 cm (1 and 3 feet), and only one doubtful skull fracture occurred.

Of 398 falls studied by Williams (1991), 106 were observed by independent witnesses. There were 14 severe injuries in falls between 4.5 and 12.20 m (15 and 40 feet), but below 3 m (10 feet), there were no life-threatening injuries, though three skull fractures were detected. Similarly, Reiber (1993) found three skull fractures in infants who had died after witnessed short falls of less than 1 m (3 feet). This was from a series of coroners' cases where all had intracranial bleeding. One 21-month infant fell 1.5–1.8 m (5–6 feet) and had a subdural haemorrhage, but no skull fracture. Another 17-month child fell only 0.6–0.9 m (2–3 feet), but suffered a sub-dural and cerebral contusion. Reiber gives a good short survey of the competing literature, indicating that opinions fall into two groups – the 'major injury–major fall' set and the 'major injury–minor fall' camp.

Hall *et al.*'s (1989) series confirms that severe or fatal damage can occasionally arise from low falls. In a 4-year study, there were 18 deaths following falls from less than 0.9 m (3 feet). Two of these were witnessed by medical care persons, excluding abuse as a covert reason. Sixteen other similar deaths were not so witnessed, but abuse was not corroborated as a cause.

Chadwick *et al.* (1991), analysing 317 childhood falls, saw seven deaths in 100 falls from less than 1.20 m (4 feet), but doubted the veracity of the histories, as there was only one death in those who fell between 3 and 13.7 m (10 and 45 feet). Hobbs (1984) studied 89 children with skull fractures, 29 thought to have been abused. Of 20 deaths, 19 were abused. The characteristics of the battered infant fractures were multiplicity or complex configuration; depressed, wide and 'growing' fractures, the latter meaning widening of the fracture line after infliction; accidental fractures were felt to be narrow, linear and single, usually in the parietal area.

Leventhal *et al.* (1993) investigated 104 infant skull fractures and concluded that abuse was the cause in 34 per cent, accident in 62 per cent, the rest being doubtful. Billmire and Myers (1985) claimed that 64 per cent of all infant head injuries, excluding simple fractures, were caused by abuse and that of serious intracranial damage, 95 per cent were from abuse. These varying figures emphasize the lack of consensus in the literature.

Though the immature skull has more flexibility, once its elastic limit is exceeded during deformation, it will fracture. The pattern of fracturing is similar to that in the adult, but there are some variations because of the presence of open sutures and fontanelles. Fracture lines tend to end at sutures, but if they cross them there is frequently a lateral displacement so that the two limbs of the fracture are not in line. Most instances where what appears to be a fracture line crossing a suture with a 'side-step' are really two independent fractures either approaching or receding from each other, the origins or terminations being slightly offset. The most common example is seen in a child who has been dropped on the vertex of the head. Both parietal bones may then deform and crack transversely from the vertex anterior to the point of impact, the bilateral fracture lines running downwards towards the parietal bosses. The upper ends of both fractures terminate in the sagittal suture, but may be 'staggered' by a centimetre or so.

Another common fracture is a horizontal crack running backwards from the frontoparietal suture, which courses across the parietal bone, often turning down towards the base of the skull. This can be caused by a blow or fall on the side or top of the head. Such fractures can occur bilaterally, which is then an indication of an impact on the vertex of the skull, which causes marked depression of the top of the skull with crack fractures along the lines of maximum stress. These are then more marked on the outer aspect than the inner table – though the diploë of infants' skulls are absent or only partially formed, according to the age. Of course, such bilateral fractures can also be caused by two separate impacts on each side of the head; here multiple bruises on or under the scalp may assist in interpretation.

The frontal bone is less often involved than the parietotemporal area, the frontal suture that is still present in young infants giving more flexibility than in the fused older bone. Occipital fractures may occur from falls onto the back of the head, but again these are much less common than cracks at the vertex or sides of the cranium, though, as the experiments of Weber showed, occipital bone cracks can occur from simple low-level falls in small infants. Wherever the vault fractures, if it is severe enough, extension lines may run down into the base of the skull, but this is not a frequent finding in child abuse injuries.

Sutural 'diastasis' (separation) may occur with or without fractures, the loosely knit skull plates being easily parted by distortion of the calvarium when struck. As mentioned above, some fractures widen after infliction (sometimes due to rising intracranial pressure). These so-called 'growing fractures' are thought by some writers to be more likely to be associated with abuse, though logic would relate it more to severity of impact rather than to motivation.

Limb fractures

These provide some of the most characteristic signs of child abuse, as injuries are common around the metaphyses and epiphyses of growing bones, as well as being the cause of periosteal lesions. Most of the limb injuries are indirect, that is, the bone damage is caused by stresses from abnormal angulation, torsion or traction, rather than from a direct impact upon the bone. Swinging the child by the wrists or ankles, dragging it by an arm or shin and violent shaking using the limbs as 'handles', are the usual mechanisms.

Avulsion of the metaphysis or chipping of the edges of the metaphyses or epiphyses may occur, with small fragments seen isolated on radiographs. Swinging, wrenching or twisting actions can fragment the metaphysis. Small pieces of the adjacent cortex and parts of the provisional zone of calcification may be avulsed from the shaft. The epiphysis may even separate from the metaphysis. Cameron and Rae (1975) suggested that metaphyseal fragments are virtually pathognomonic of child abuse.

The periosteum in infants is only loosely attached to the bone and easily lifts where there is shearing or traction injury. Blood accumulates under the raised periosteum and this rapidly calcifies (usually within 7–14 days) to give a characteristic radiological picture of a bony shell extending along the shaft, often thicker at the extremity, having a lumpy, irregular profile (Evans and Knight 1981). In almost half the cases, this may be seen radiographically within one week (Cameron 1970). The calcified rim may extend around the end of the metaphysis and epiphysis, or between the two, giving a 'bucket-handle' loop effect around the end of the bone, especially the lower end of the femur.

In early infancy it must be appreciated that some breech deliveries have legs that radiologically show long, smooth periosteal thickening secondary to subperiosteal bleeding caused by handling during delivery. It is also accepted that mere growth can produce faint subperiosteal calcification, but this is symmetrical and limited to the central parts of the shaft, keeping clear of the metaphyses.

A spiral fracture of the diaphysis of a long bone must be considered a suspicious injury in infants, as such a lesion is likely to be the result of a twisting strain, unlikely to occur in accidental circumstances.

The lower end of the shaft of a long bone may be 'squared-off', as described by Caffey (1946), by metaphyseal fragments reuniting. Damage to the epiphyseal cartilage may cause permanent growth defects, sometimes with increased growth from hyperaemia following injury. The axis of growth may be deviated and cupping of the metaphysis may occur because of retarded longitudinal growth in the centre.

Although the metaphyseal and epiphyseal lesions described above are classically those seen in child abuse, transverse and spiral fractures of the diaphysis are also common. In a series of 100 cases reported by Kogutt *et al.* (1974), these fractures were more common than the injuries to ends of the bones.



FIGURE 22.7 *Chest radiograph of an infant showing multiple callus formation on the necks of the ribs, giving a 'string of beads' appearance down the paravertebral gutter. These indicate previous multiple fractures caused by lateral squeezing by adult hands.*

Damage to the chest cage

Apart from occasional perinatal fractures during delivery (Polson, Gee and Knight 1985), accidental fractures of ribs are very uncommon in infants, though the incidence is a matter of considerable controversy. Once again paediatricians, radiologists and pathologists may have differing views and experience.

In child abuse, ribs are commonly fractured, often several consecutive bones being affected on one or both sides. The damage may be fresh or old, giving different radiological appearances. The most characteristic picture of old fractures is of sequential callus formation seen in a vertical line down one or both paravertebral gutters. These form a 'string-of-beads' appearance on X-ray (Figure 22.7), where the ribs have been fractured near their angles, a sufficient time previously for new bone formation to occur – probably a minimum of 10 days, though dating is notoriously variable, and even the claims by experienced radiologists to date fractures have been confounded by a knowledge of the actual time of breakage.

These multiple posterior fractures are more common in small infants who have been picked up by adult hands under the armpits and squeezed from side to side. Whether or not such fractures can be caused by innocent handling, albeit rough or robust, as opposed to angry or impatient violence, is again a matter of dispute, beyond the competence of doctors to resolve – although this does not deter some from expressing strong opinions based on weak facts.

These fractures, a centimetre or so from the head of the ribs, are due to the rib being levered against the transverse process until breaking point is reached. They may be very difficult or impossible to see as fresh lesions on radiographs, if the fracture line is not exactly in line with the X-ray beam. This explains the occasional discrepancy between the radiologist's and the pathologist's report; the fractures are much more visible after a week or two, when callus is present.

If such injuries are recent (probably less than 10 days) no visible callus is formed, but the fractures may be seen on X-ray and confirmed at autopsy. However, as with fractures elsewhere – and perhaps more often in ribs than skull – the radiological and dissection diagnosis sometimes does not concur. Fractures seen at autopsy may not be visible radiologically – and conversely, alleged fractures seen on films may not be discoverable at autopsy, even after the most diligent dissection.

Rib fractures in the axillary line are likely to be the result of anteroposterior pressure, rather than side-to-side squeezing, but this mechanism is not exclusive. With fresh fractures found at autopsy, the possibility of chest compression



FIGURE 22.8 *Recent fractures of ribs of an abused infant. These breaks are near the necks of the ribs in the paravertebral gutter, caused by side-to-side squeezing of the chest.*

during cardiopulmonary resuscitation must always be considered, even though some paediatricians and radiologists will strenuously deny the possibility of this happening. The literature has different opinions on this matter, though it is admittedly very uncommon. As with other aspects of child abuse, the published material seems to flow more from those who lean towards abuse in the majority of injured children, rather from those who retain a more cautious approach and admit to the possibility of an innocent explanation.

It must be conceded that pliable infant ribs are unlikely to be broken by proper cardiac massage, which in infants should be performed with finger pressure; however, lay persons, especially in the panic of apparent collapse and death, may forcibly pump the small chest using techniques intended for adult resuscitation.

Fractures elsewhere are more likely to arise from direct impact such as a fist blow or kick. The clavicle is sometimes broken, usually from indirect stress from swinging by an arm. Fractures of the scapula or sternum are rare and arouse the probability of 'parental infliction' if some obvious trauma such as a traffic accident can be excluded.

Wherever the site of bony injury, the cardinal features that arouse suspicion are multiplicity and variation in fracture age. Though children often sustain accidental fractures, these are usually single lesions, unless some pathological bone disease is present. Similarly, the radiological demonstration of multiple fractures of varying ages must be accepted as evidence of abuse until proved otherwise.

Dating of fractures

As in the case of skin bruises, though the absolute dating of healing fractures by the state of callus formation is far from accurate (Evans and Knight 1981), marked differences in appearance on radiology usually indicate that the injuries were not sustained at the same time. As it can be shown, however, in control material, that the same person reveals callus of different extent and maturity in different but similar bones fractured contemporaneously, it becomes impossible to be dogmatic about radiological healing rates. Bone healing is rapid in healthy children and within months the abnormalities may have completely resolved, depending on the severity of the original damage.

Histological appearances are also very unreliable in placing an absolute date on fractures, in spite of assertions that this can be done with accuracy.

BONE DISEASES AND INFANT FRACTURES

Both in the differential diagnosis of childhood fractures and in the defence of allegations of child abuse, the several 'brittle bone diseases' that can cause abnormal skeletal fragility must be considered, on the grounds that lesser force, within normal parental handling or even spontaneous movements of the infant, could give rise to the observed fractures.

It has to be said at the outset that only a small minority of injured infants can be shown to have such abnormalities. When this possibility is being run as a defence in a criminal trial or child protection proceedings, it is essential to have an opinion from a radiologist or paediatrician with specialist knowledge of these conditions.

It is also important to have original radiographs, not copies, as the latter may not show marginal, indistinct abnormalities visible on the originals.

Osteogenesis imperfecta

This is a bone dysplasia with four types, numbered I, II, III and IV, of which there are several subgroups. The disease is an inherited disorder of connective tissue, with abnormal collagen, resulting in varying degrees of bone fragility, ligamentous laxity, skin fragility, sometimes blue sclera, hearing defects and dental abnormalities.

Types II and III have obvious bone disease and can hardly be confused with child abuse lesions.

Type I forms 70 per cent of cases and is the classical variety with a family history, blue sclera, Wormian bones and often dental changes, which again is hardly likely to be confused with abuse. It is type IV (only about 5 per cent of the overall disease incidence) that may cause difficulties in diagnosis, though it must be said that of all the medico-legal occasions in which this disease is postulated as a reason for brittle bones as a defence against allegations of abuse, the times upon which it can be proven are few indeed.

Type IVB, the larger subgroup, has dentinogenesis imperfecta. Type IVA has no family history of the disease, no osteoporosis, a high incidence of skull fractures and metaphyseal fractures and normal sclera. Subgroup IVA has Wormian bones, like IVB, but it has been postulated that some alleged cases of type IVA were really abuse.

It has been calculated that the incidence of type IV osteogenesis imperfecta in infants under one year, with fractures, no family history, no Wormian bones or dentinogenesis imperfecta is one in 1–3 million. A case would occur in a city of half a million population only once every 100–300 years.

Recent techniques of fibroblast culture and collagen analysis can provide evidence of defective connective tissue in the absence of overt clinical signs, but this is not necessarily synonymous with brittle bones. The case report by Ojima *et al.* (1994) gives a useful survey of the problem. Bone strength in otherwise normal SIDS infants has been measured by Morild *et al.* (1993) to obtain a baseline for comparison with alleged osteogenesis where this is raised as a defence against child abuse.

Infantile cortical hyperostosis (‘Caffey’s disease’)

Here there is extensive new periosteal bone laid down around the diaphyses, the bones most involved being the ribs, ulnae, clavicles and especially the mandible. The condition is rarely seen over the age of 3 years.

Congenital syphilis

This can mimic the changes seen in child abuse, though the condition is extremely rare in most Western communities. The periosteal thickening is similar to that of trauma, but tends to be symmetrical. The metaphysis may be fractured and even separated, the shaft adjacent to the metaphysis being porotic.

Copper deficiency

Again rare, this condition has radiological features in which periosteal thickening of the shafts of the long bones may be accompanied by symmetrical spurring of the metaphyses, osteoporosis, fractures and cupping of the metaphyses. Abnormalities of the hair may be present in this deficiency disease that is caused by lack of copper impairing the enzyme lysyl oxidase. The radiological appearances may cause confusion with child abuse. Other clinical features include psychomotor retardation, hypotonia, pallor, hypopigmentation of the skin and hair, prominent scalp veins, sideroblastic anaemia and neutropenia.

Menke’s syndrome (‘kinky hair’ syndrome)

This is another rare condition also associated with copper deficiency in which there are abnormal metaphyses. It affects males only, with abnormal hair, Wormian bones in the skull and mental retardation.

HEAD INJURY IN CHILD ABUSE

The most common cause of death in abused children is intracranial damage, with or without skull fracture. As well as being the most frequent fatal condition, brain trauma is responsible for the common tragedy of severe, and often permanent, neurological impairment.

The classic head injury associated with battered children is subdural haemorrhage, which formed part of ‘Caffey’s syndrome’ that he described five decades ago. It was also noted in Tardieu’s famous publication of 1860, when he described bleeding on the side of the cerebrum and other classical features (Knight 1986). Subdural haemorrhage is most common at the extremes of life, the topic being discussed fully in Chapter 5. In infants, it most often occurs from direct impact on the skull – as in a blow or fall. For some years, it has been held that vigorous shaking, without an impact, is also a common cause of subdural bleeding. This is a view strongly held by many paediatricians, who may prefer this mode as a first choice over a blow or fall, but recent research has thrown doubt on the common acceptance of this mechanism.

For example, the excellent textbook of DiMaio and DiMaio (1989) observes:

> Many forensic pathologists have doubted that the shaken baby syndrome exists [Norton 1983]. Most have felt that the injuries to the brain, including the retinal haemorrhages, are due to undetected direct impact

injuries. In all cases seen by the authors in which there has been retinal haemorrhage associated with subdural or subarachnoid bleeding, or some other brain trauma, direct impact injury to the head has been identified.

The forces generated in the cranial cavity by shaking have been shown to be of the order of 50 times less than in the deceleration stresses of an impact (Gennarelli and Thibault 1982; Duhaime *et al.* 1987). These authors investigated 13 fatalities alleged to have occurred from shaking, but though 7 showed no external head injury, all 13 revealed evidence of impact at autopsy. In infant models, they then compared impact with violent shaking; the mean tangential acceleration for 69 shaken babies was less than 10 G, whereas for 60 impacts, the mean was 428 G, some 50 times greater. The mean time for shakes was 106 milliseconds, but for impacts was only 20 milliseconds.

It is the rate of change and the duration of deceleration – the 'strain rate' – that is most damaging, rather than a steady deceleration. A head impacting on an immovable surface after a fall is an example of a high strain-rate injury, whereas low strain-rate injuries are those where the head decelerates over a longer period of time. Non-impact shaking of the head is a low strain-rate mechanical insult. Subdural bleeding from bridging veins is likely to occur from high strain-rate injury, even though this may be a low-energy injury, insufficient to cause cerebral tissue disruption. By contrast, low strain-rate injuries are more likely to cause cerebral contusion, with vascular damage only if concomitant high energy is generated (Howard *et al.* 1993).

Geddes and Whitwell (2004) have recently pointed out that there have been no formal systematic neuropathological studies of infant head injury and the evidence base for diffuse axonal injury (DAI) being a common finding in infant head injury is poor. In fact the idea of the presence of DAI in these cases was widely accepted before the advent of the modern diagnostic methods and before the diagnostic criteria for DAI had been established. Moreover, the findings of Shannon *et al.* (1998), the first formal study of microscopic damage in non-accidental injury (NAI), suggesting that axonal injury in such cases had been ischaemic or vascular in origin, had been largely ignored or misunderstood. In their recent series of 53 fatally injured infants (Geddes *et al.* 2001a, b), diffuse axonal injury was present in only two children, both of whom had multiple skull fractures and severe head injury, whereas the most frequent histological finding was global hypoxic damage in 84 per cent of the cases. In 11 of these cases (21 per cent), however, there was gross and microscopic evidence of injury to the craniocervical junction and concomitant axonal damage in the caudal brainstem long tracts in 8 subjects. This finding is in keeping with cervical hyperflexion/hyperextension injury pattern in adults and suggests as a possible mechanism of death: brainstem injury, apnoea and hypoxic brain swelling. In another systematic study of dural bleeding in 50 paediatric cases, including intrauterine deaths up to infants of 5 months of age, but without head injury, Geddes *et al.* (2003) found fresh haemorrhage into the layers of dura in a majority (36/50) of cases. The authors believe that this is a manifestation of severe hypoxia similar to the haemorrhages found in internal organs in birth asphyxia or prematurity, rather than being caused by trauma, and postulate that hypoxia is sufficient to cause extravasation of significant amounts of venous blood both in and under the dura.

Although shaking presumably may cause subdural haemorrhage (SDH), it is likely that it is a relatively uncommon cause, compared with impact. This situation may well have arisen because a blunt impact upon the head of infant, if spread over a wide area following contact with a flat surface, can leave no external scalp mark, no subscalp bleeding and no fracture of the skull – yet the transmitted forces can still be sufficient to cause high strain-shearing stresses within the cranium leading to subdural bleeding. In addition, as has been discussed elsewhere in this book, death is often not due to the irritative or space-occupying effects of the subdural, but is due to the intrinsic brain damage beneath, even if this is occult. Diffuse axonal injury, cerebral oedema and consequent circulatory disturbances are likely to be the fatal consequences, but detecting neuronal damage may be difficult or impossible histologically, due to the relatively rapid death of the child within 12–24 hours. Also, the microscopic features of diffuse axonal injury seem to be less common and less distinct in infants compared with adults, though the use of immunocytochemical methods, such as the demonstration of β-amyloid precursor protein (βAPP), described in Chapter 5, may provide a marker of use within the first few hours after injury. These factors combine to negate any proof of an impact injury and thus the shaking theory, which requires none of these criteria to be demonstrated, is an easier option.

Howard *et al.* (1993) looked at 28 instances of SDH in infants under 18 months of age. All had a history more consistent with an impact rather than shaking. Six Caucasian infants fell less than 0.9 m (3 feet), such as from a chair or standing adult. Eight non-Caucasians fell from a sitting or standing position or rolled off a bed onto a carpeted floor. There was a history of shaking in three, but these also had signs of impact, the shaking being resuscitation attempts after falling. Of these, 47 per cent of the Caucasians and 20 per cent of the non-Caucasians had a skull fracture. The authors state: 'Our findings do not support shaking as the only cause of SDH and also suggest that non-accidental injury is a less common cause of SDH than it is believed to be.'

There is a suggestion in several papers that Asian children are more susceptible to SDH from minor trauma;

Japanese infants have been reported with SDH after falling from only a sitting position (Aoki and Masuzawa 1984; Rekate 1985).

Most direct impacts in child abuse are caused by the moving head striking a fixed object, rather than the fixed head being struck. The latter certainly occurs, but is usually from an open-handed slap, albeit often of considerable force. It is unusual for the child's head to be struck with a weapon or for a direct punch to be given with the clenched fist. The moving head injury either arises from a fall in circumstances which are non-accidental, or by deliberate swinging or throwing of the child against a hard surface, often with added momentum being gained by holding the infant's ankles or wrist. For example, one such case seen by the author (BK) was a month-old baby whose father grasped it by the ankles to dash its head against stones at the edge of a canal, after which it was stripped so that its clothing could be sold in a street market, the body then being thrown into the canal.

Several other mechanisms of head injury have been described, including some seen by the author (BK) in which fathers were throwing their baby up in the air in a catching game called 'up-and-away', but for some reason missed the child on the downward return, allowing it to fall to the floor. When unwitnessed, this situation can give rise to accusations of deliberate malice, which are difficult to disprove.

Presumably, as vigorous shaking can sometimes rupture vessels in the subdural space, this must still be accepted as an alternative to impact in the causation of subdural haemorrhage. In an infant, the head is relatively large and heavy and the neck musculature undeveloped and often hypotonic. Thus repetitive shaking of the body – often attained by grasping under the armpits – can lead to unrestrained flexion and extension movements of the head with rotational movements of the heavy cerebral hemispheres relative to the skull.

Extradural haemorrhage is uncommon in child abuse, perhaps because the meningeal arteries do not run in deep grooves or even tunnels in the immature skull, as they do in the adult. Subarachnoid haemorrhage is, as always, an inevitable accompaniment of cerebral cortical contusion.

Brain damage may be of any type, as catalogued in Chapter 5, but as in any childhood head injury, cerebral oedema is more common than in the adult. Indeed, a significant proportion of deaths after a head injury in a child are caused by raised intracranial pressure without skull fracture, meningeal haemorrhage or visible brain injury. The typical autopsy indications may be found consisting of a heavy brain, flattened gyri, obliterated sulci and slit-like ventricles. The more florid signs seen in adults, such as herniation of the hippocampal gyrus through the tentorial gap, secondary brainstem haemorrhages and coning of the cerebellar tonsils are seen less frequently in children.

When there has been a severe head injury, with or without a fractured skull, cerebral contusion or laceration may occur. The position of this damage is usually related to the site of external impact. Although many episodes of child abuse involve dropping or throwing to the floor, classical contrecoup lesions are not as common as in similar adult injuries. They certainly do occur, but are often absent when the circumstances would indicate that contralateral contusion might be expected. The smoother internal profile of the infant skull may be a factor.

The distance of a fall sufficient to cause head injury has been mentioned earlier and is a matter of considerable controversy in the literature and amongst expert medical witnesses. There is no doubt, both from reliable anecdotal evidence and from experimental data, such as that by Weber, that skull fractures can occur in infant skulls from very low passive falls, including heights not exceeding chair or table level (Weber 1984: 82 cm; 34 inches). However, as catalogued above, skulls often fracture without any significant internal brain damage – although the reverse is also true. The evidence that low falls may cause brain or meningeal lesions is much less convincing than that proving skull fractures – but the possibility exists and cannot be dismissed by inflexible, dogmatic opinion. The problem with assessing the mechanical basis of head injury is that human experimentation is virtually impossible – Weber's work on dead infants probably could not be repeated in the present ethical climate – and obviously no data can be derived from the living. Animal models are useless, so the frequent difficulties for pathologist, lawyers and the courts have to rest on available statistical evidence – which can never give a definitive answer in any one case. If a phenomenon has definitely occurred once, then it can occur again, whatever the statistical weight is against its frequency, as a precedent has been established which cannot be gainsaid as a possibility.

One of the problems is the 'standard of proof', as in the criminal courts, it is 'beyond reasonable doubt', whereas in civil matters, it only has to pass the test of 'balance of probabilities', where statistical evidence is far more persuasive.

To rely on the 'experience' of medical witnesses is also fraught with difficulty, as their anecdotal memories of previous cases will provide unsatisfactory data in respect of the causation of the injury. Where adults are accused of malice or neglect, they are very likely to fabricate or distort the circumstances of the injury, and claim that the infant fell from the chair, the arms or the bed. Even in genuine accidents, feelings of guilt, clouded recollection from grief and panic, will often lead to an inaccurate account of the circumstances, so the doctor's past experience is often of lesser value than the accused adults, the lawyers and the court imagine, due to inadequate or false knowledge of the true circumstances of previous cases.

VISCERAL INJURY IN CHILD ABUSE

Damage to internal organs is almost always confined to the abdomen, as the heart and lungs are rarely injured. As stated earlier, rupture of an abdominal viscus is the second most common cause of death in child abuse after head injury. Forcible impacts on either the lower chest or the abdominal wall are responsible. Direct punching or heavy 'prodding' are the usual mechanisms rather than being dropped or thrown, which is a common cause of head injury. Often there will be an excuse that the child fell or tripped upon some protruding obstruction, such as a toy or piece of furniture; occasionally this may be true and it is a matter of fact and interpretation as to whether the circumstantial evidence is compatible with the medical findings. The liver is frequently injured, the most common lesion being a deep tear in either lobe, sometimes being a complete penetration or, more rarely, actual detachment of hepatic tissue. A haemoperitoneum results and in fatalities, may be the proximate cause of death. A heavy blow over the lower ribs or xiphisternal area is the most likely site of impact.

The small intestine is the other common target organ, the duodenum or jejunum being the most frequent site of damage. The second part of the duodenum is vulnerable to blows in the central abdomen, as beneath this area, the duodenum crosses the midline and is liable to be 'sandwiched' between the compressed anterior abdominal wall and the promontory of the lumbar spine. As the tissue thickness is small in a child, the gut can be virtually 'guillotined' at this point and may be completely transected, appearing almost as clean-cut as if it had been done with a surgical knife. Alternatively the gut wall may be damaged and, though it may not leak or rupture at the time of impact, ischaemic and necrotic changes over the next few hours or even days may lead to a delayed rupture, with the later onset of peritonitis.

The same lesions, though rarely as sharply cut, can occur in the jejunum, often accompanied by laceration of the mesentery and haemorrhage into the peritoneal cavity instead of – or in addition to – leakage of intestinal contents.

Rupture of the stomach can occur, but must be carefully differentiated from gastric rupture from non-traumatic causes and (these days) especially from external cardiac massage, which produces linear tears in the mucosa and even rupture of the complete wall.

DAMAGE TO EYES, EARS AND MOUTH

As part of general facial damage, black eyes, and scleral and conjunctival haemorrhages are often seen, but damage to the interior of the globe is much less apparent at autopsy. Some considerable time after the general recognition of the child abuse syndrome, it was discovered that a considerable proportion of victims, both live and dead, had significant internal damage to the eyes. Direct violence to the head and allegedly shaking, can cause bleeding into the vitreous humour, dislocation of the lens, retinal detachment and retinal haemorrhages (Gilliland *et al.* 1994).

The latter can also be caused by cardiopulmonary resuscitation, where vigorous compression of the chest has been applied; the literature on this topic is controversial, but numerous references confirm this mechanism, yet others,



FIGURE 22.9 *A ruptured duodenum in an abused child who suffered a blow in the central abdomen. This relatively common mode of death in fatal child abuse is caused by the duodenum being guillotined against the lumbar spine by an impact that indents the thin anterior abdominal wall. The gut may be severed immediately or may become infarcted because of damaged blood supply over the ensuing few days, then rupture into the peritoneal cavity.*

such as Gilliland and Luckenbach (1993), deny it. Once again, there are hotly contested viewpoints in the position taken by different doctors over the aetiology of various lesions in child abuse, both by clinicians and pathologists. They are also, of course, often secondary to raised intracranial pressure from head injuries, rather than due to primary direct violence. During life, these can be diagnosed by ophthalmoscopy, but at autopsy they must be sought by dissection. As disfigurement of the body of a child must be avoided wherever possible, examination for eye lesions may be achieved either by enucleation and replacement with glass prostheses – or by opening the orbits from the anterior cranial fossae and removing the posterior two-thirds of the globes.

Injury to the external ear is frequent, as abuse of a child is often directed at the obvious targets, such as face, head, arms, buttocks and ears. The pinnae may be bruised or even lacerated, usually by an open-handed slap. Damage to the internal ear from heavy impacts on the head may be diagnosed clinically, though often in retrospect from later deafness. At autopsy, damage to such minute structures is rarely visible, though sometimes haemorrhage into the petrous temporal bone may be found when routinely examining this area for middle-ear sepsis.

Injury to the lips and mouth is so common as to be one of the prime diagnostic signs of the battered child. Infants and older children are commonly slapped across the mouth, the swipe usually having a tangential component that moves the tissues laterally. This causes the most reliable indicator of child abuse, the torn frenulum (or 'frenum') beneath the upper lip. This small median band of mucosa that joins the upper gum to the upper lip is ripped as the lip is jerked sideways, and is virtually pathognomonic of battering. The other possible cause of a ruptured frenulum is the forcible entry of a feeding bottle teat into the mouth of a reluctant infant. Instead of entering between the gums, the teat is rammed up between the gum and lip, causing a tear. The lesion heals rapidly, as do all injuries in the mouth and, within a few days, nothing may be seen except perhaps a loose mucosal tag or an absent frenulum, or both.

Damage to the lips themselves is common, the type of injury varying somewhat according to whether or not the child is old enough to have teeth. In any event, bruising, swelling, abrasion and sometimes external laceration may be seen. The inner mucosal aspect of the lips may be bruised even if the child has no teeth and, if the blow is hard enough, laceration can occur. This is far more likely to happen if the lips are forced against the teeth, especially the cutting edge of the incisors.

The teeth themselves may be damaged, especially in older children. Total avulsion from the sockets, loosening and breakage may occur. In small infants, developing teeth may be forced back into the sockets, like pegs into holes. Expert dental advice should be sought wherever possible when injuries to teeth and jaws are found, both in live children and at autopsy.



FIGURE 22.10 *Bruising of the lips in child abuse caused by smacking in the mouth. When the child is old enough to have teeth, lacerations may occur inside the lips. The frenulum behind the midline of the upper lip (not shown) was ruptured in this child, a strong pointer to a blow across the upper lip.*



FIGURE 22.11 *Tearing of the frenulum of the upper lip of a child, a classical injury from a tangential slap across the mouth.*

BURNS IN CHILD ABUSE

Unfortunately, thermal injuries are by no means uncommon in abused infants. These may be moist scalds, dry burns or, exceptionally, electrical injuries.

Scalds result from dipping in hot fluid and often involve over-hot bath water. The line between accident and abuse may be blurred in some cases, but it can occur as a form of chastisement. In one case, a child was deliberately held in water at over 80°C as a punishment for persistently complaining about being cold. Other scalds may be from boiling water from a kettle or saucepan deliberately being poured over the child.

Dry burns can be inflicted in innumerable ways as a deliberate and sadistic act. Children have been forcibly sat on electric cooking rings and hotplates, branded with hot shovels and electric soldering-irons, or pressed against the bars of a fire. A particular type of burn seen relatively often in abused children is never the cause of death but may be found incidentally. This is the cigarette burn, seen most often on skin not normally covered by clothing, such as the hands, arms, neck and head. Such burns are usually circular, but not always; if the cigarette has been held obliquely against the skin, the mark may be triangular. The regular shape and size usually indicate the nature of the burn, though some skin diseases may simulate an old burn, such as a small patch of impetigo. Fresh cigarette burns are red, sometimes with a narrow rim of a deeper red. When healing, they become pink and later have a silvery sheen on the surface.

BITE MARKS IN CHILD ABUSE

Most bites on the skin surface are seen either in sexual offences or in child abuse. In the author's own experience, all bitten infants have had these inflicted by the mother, though published reports indicate that both male and female guardians can bite their infant charges. The topic is discussed in more detail in Chapter 26, but as they are relatively common in child abuse, a summary is repeated here.

Bites may be seen anywhere on the child's body. The arms, back of the hands, cheeks, shoulders, buttocks and abdomen are favoured sites. A bite mark usually consists of two opposing semicircles, which may be incomplete. Individual teeth marks may be visible or the dental arch may be represented by a continuous line. The mark is either an abrasion or a bruise, or a combination of both. There may be confluent petechiae in the centre caused by suction, but this is much more common in sexual assaults – the so-called 'love bite'. In child abuse, the centre is more often undamaged. The size of the dental arch should be carefully measured to determine whether it was formed by an adult, another child or even an animal, as is sometimes alleged in defence.



FIGURE 22.12 *Bite mark on baby's arm in a case of child abuse. The culprit was the mother. The teeth marks are deficient over one quadrant, the gap on the other side being smaller than usual.*

In older children, the possibility of self-biting must be borne in mind – the author has seen multiple self-bites all the way up one arm in a young person.

As with all dental matters, the advice of a dentist experienced in forensic problems is highly desirable. Not only can he confirm or exclude doubtful lesions, but he can identify individual teeth marks, make casts of any residual impression in the skin and take swabs for saliva identification. He can also examine any suspects to compare their dentition with the marks – a common excuse of the parents is that another child or even the family dog caused the bite. If no forensic odontologist is available, however, the pathologist must make the best examination possible and details are given in Chapter 26.

OTHER INJURIES IN CHILD ABUSE

A variety of injuries, some bizarre and sadistic, occur from time to time in battered children. The hair may be pulled out in clumps (epilation), leaving pseudoalopecia on the



FIGURE 22.13 *A child with numerous bruises on the body, totalling 80 on the face, neck, abdomen, back and legs. The male adult in the house claimed that she had 'slipped while being bathed'. At autopsy, there was a massive haemoperitoneum arising from multiple ruptures of the mesentery.*

scalp. Fingers may be broken by hyperextension and finger-tips crushed by blows or other means. Patterned marks from straps and ropes may be seen on the skin, usually on buttocks, thighs and abdomen. 'Pinch' or 'tweaking' marks are not uncommon, made by the skin being nipped between adult fingernails. These appear as two small opposing semi-circular or triangular bruises, often with a clear zone between them.

THE AUTOPSY IN CHILD ABUSE

This follows the usual routine for any forensic autopsy, but certain additional matters must be given close attention. Because of the emotive nature of child abuse, especially where a fatality is concerned, the pathologist must pay meticulous attention to all aspects of his examination and report. A full description of the autopsy in child abuse may be found in the chapter by Knight in *Paediatric Forensic Pathology* (Knight 1989). The following matters must be borne in mind:

- The scene should be visited wherever possible, though usually the child will already have been removed, usually to a hospital accident department. Even a retrospective visit can be helpful, however, to assess such matters as the nature of the floor and its coverings, where falls are alleged, the height of settees and chairs, and the general size and space between walls, doors and furniture, as claims of colliding with household structures are a constant line of defence – and may well be true in some instances.
- The child should be examined in its original clothing where possible.
- The appearances before washing and other cosmetic manoeuvres should be recorded; when children die in hospital accident departments, such compassionate acts may remove useful evidence, and the balance between

sympathy and justice can sometimes be hard to reconcile.

- Careful enquiries should be made about any resuscitatory attempts, as these can introduce a number of artefacts.
- Where any suspicion of abuse is present, a full radiological skeletal survey should be carried out before the autopsy is begun.
- Full physical measurements must be made including weight, crown–heel length, crown–rump length, foot length and head diameter.
- A meticulous external examination must be made, covering every square centimetre of the body, including all body orifices. The interior of the mouth and lips must be searched.
- A full photographic record must be made of any abnormality discovered. Where bruising is suspected, but not definitely apparent, the use of both infrared- and ultraviolet-sensitive film has been advocated, though experience is required in their interpretation, as artefacts are common.
- Extensive dissection of subcutaneous tissues is required wherever bruising is seen or suspected. Incisions must be made into doubtful areas or the skin flayed away to reach such areas, if disfigurement is to be avoided.
- Full sampling of blood, urine, stomach contents, liver, ocular fluid and cerebrospinal fluid must be taken, according to the circumstances. It is best to be liberal with the range of samples – it is easy to discard unwanted samples, but difficult or impossible to obtain them at a later date.
- Where appropriate, skin samples for fibroblast culture and swabs for microbiological culture are taken. Blood samples for grouping and other blood characteristics may be needed and a sufficient amount for DNA testing.
- Bite marks may need to be swabbed for saliva and casts made of tooth indentations. The cooperation of a forensic odontologist is then vital (see Chapter 26).
- A full internal dissection of all organs is required, with full sampling for histological purposes. Further radiographs may need to be taken on isolated bones or on the chest cage. The latter can be removed entirely by careful dissection if multiple rib fractures are present. X-rays can then be taken of the detached thoracic cage free of soft tissue and further histological blocks taken for decalcification in an attempt to date the lesions.
- If there is obvious or suspected brain damage, the brain should be removed carefully and suspended in formalin until firmly fixed. On no account should ‘wet cutting’ take place if intracranial damage or cerebral oedema is present.
- The globes of both eyes should be removed for histological examination: they can be taken entire and false eyes replaced for cosmetic purposes – or the posterior three-quarters of the globes can be removed via a superior approach through the base of the anterior fossa.

REFERENCES AND FURTHER READING

Ablin DS, Greenspan A, Reinhart M, *et al.* 1990. Differentiation of child abuse from osteogenesis imperfecta [see comments]. *AJR Am J Roentgenol* **154**:1035–46.

Adams PC, Strand RD, Bresnan MJ, *et al.* 1974. Kinky hair syndrome: serial study of radiological findings with emphasis on the similarity to the battered child syndrome. *Radiology* **112**:401–7.

Aoki N, Masuzawa H. 1984. Infantile acute subdural hematoma. Clinical analysis of 26 cases. *J Neurosurg* **61**:273–80.

Bacon CJ, Sayer GC, Howe JW. 1978. Extensive retinal haemorrhages in infancy – an innocent cause. *Br Med J* **1**:281.

Barlow B, Niemirska M, Gandhi RP, *et al.* 1983. Ten years of experience with falls from a height in children. *J Pediatr Surg* **18**:509–11.

Billmire ME, Myers PA. 1985. Serious head injury in infants: accident or abuse? *Pediatrics* **75**:340–2.

Brown RH. 1976. The battered child syndrome. *J Forensic Sci* **21**:65–70.

Bush CM, Jones JS, Cohle SD, *et al.* 1996. Pediatric injuries from cardiopulmonary resuscitation. *Ann Emerg Med* **28**:40–4.

Caffey J. 1946. Multiple fractures in the long bones of infants suffering from chronic subdural hematoma. *Am J Roentgenol* **56**:163–72.

Caffey J. 1972. On the theory and practice of shaking infants. Its potential residual effects of permanent brain damage and mental retardation. *Am J Dis Child* **124**:161–9.

Caffey J. 1974. The whiplash shaken infant syndrome: manual shaking by the extremities with whiplash-induced intracranial and intraocular bleedings, linked with residual permanent brain damage and mental retardation. *Pediatrics* **54**:396–403.

Cameron JM. 1970. The battered baby. *Br J Hosp Med* **4**:769–74.

Cameron JM, Rae LJ. 1975. *Atlas of the battered child syndrome.* Churchill Livingstone, Edinburgh.

Cameron JM, Johnson HR, Camps FE. 1966. The battered child syndrome. *Med Sci Law* **6**:2–21.

Carty H. 1988. Brittle or battered. *Arch Dis Child* **63**:350–2.

Case ME, Graham MA, Handy TC, *et al.* 2001. Position paper on fatal abusive head injuries in infants and young children. *Am J Forensic Med Pathol* **22**:112–22.

Chadwick DL, Chin S, Salerno C, *et al.* 1991. Deaths from falls in children: how far is fatal? *J Trauma* **31**:1353–5.

Chapman S. 1990. Radiological aspects of non-accidental injury. *J R Soc Med* **83**:67–71.

Cohle SD, Hawley DA, Berg KK, *et al.* 1995. Homicidal cardiac lacerations in children. *J Forensic Sci* **40**:212–18.

Cumming WA. 1979. Neonatal skeletal fractures. Birth trauma or child abuse? *J Can Assoc Radiol* **30**:30–3.

Department of Health and Social Security. 1988. *Diagnosis of child sexual abuse.* HMSO, London.

DiMaio D, DiMaio V. 1989. *Forensic pathology.* Elsevier, New York.

Duhaime AC, Gennarelli TA, Thibault LE, *et al.* 1987. The shaken baby syndrome. A clinical, pathological, and biomechanical study. *J Neurosurg* **66**:409–15.

Duhaime AC, Alario AJ, Lewander WJ, *et al.* 1992. Head injury in very young children: mechanisms, injury types, and ophthalmologic findings in 100 hospitalized patients younger than 2 years of age. *Pediatrics* **90**:179–85.

Eisenbrey AB. 1979. Retinal hemorrhage in the battered child. *Child's Brain* **5**:40–4.

Evans KT, Knight B. 1981. *Forensic radiology.* Blackwell Scientific Publications, Oxford.

Feldman KW, Brewer DK. 1984. Child abuse, cardiopulmonary resuscitation, and rib fractures. *Pediatrics* **73**:339–42.

Fontana VI. 1964. The neglect and abuse of children. *NY State J Med* **64**:215–20.

Friendly D. 1971. Ocular manifestations of physical child abuse. *Trans Am Acad Ophthalmol Otolaryntol* **75**:318–32.

Geddes JF. 1997. What's new in the diagnosis of head injury? *J Clin Pathol* **50**:271–4.

Geddes JF, Whitwell HL. 2001. Head injury in routine and forensic pathological practice. *Curr Top Pathol* **95**:101–24.

Geddes JF, Whitwell HL. 2004. New thoughts on inflicted head injury in infants. *Forensic Sci Int* accepted for publication.

Geddes JF, Whitwell HL, Graham DI. 2000a. Traumatic axonal injury: practical issues for diagnosis in medicolegal cases. *Neuropathol Appl Neurobiol* **26**:105–16.

Geddes JF, Whitwell HL, Graham DI. 2000b. Traumatic or diffuse axonal injury? Author's response. *Neuropathol Appl Neurobiol* **26**:491.

Geddes JF, Hackshaw AK, Vowles GH, *et al.* 2001a. Neuropathology of inflicted head injury in children. I. Patterns of brain damage. *Brain* **124**:1290–8.

Geddes JF, Vowles GH, Hackshaw AK, *et al.* 2001b. Neuropathology of inflicted head injury in children. II. Microscopic brain injury in infants. *Brain* **124**:1299–306.

Geddes JF, Tasker RC, Hackshaw AK, *et al.* 2003. Dural haemorrhage in non-traumatic infant deaths: does it explain the bleeding in 'shaken baby syndrome'? *Neuropathol Appl Neurobiol* **29**:14–22.

Gennarelli TA, Thibault LE. 1982. Biomechanics of acute subdural hematoma. *J Trauma* **22**:680–6.

Gilliland MG, Folberg R. 1992. Retinal hemorrhages: replicating the clinician's view of the eye. *Forensic Sci Int* **56**:77–80.

Gilliland MG, Luckenbach MW. 1993. Are retinal hemorrhages found after resuscitation attempts? A study of the eyes of 169 children. *Am J Forensic Med Pathol* **14**:187–92.

Gilliland MG, Luckenbach MW, Chenier TC. 1994. Systemic and ocular findings in 169 prospectively studied child deaths: retinal hemorrhages usually mean child abuse. *Forensic Sci Int* **68**:117–32.

Goetting MG, Sowa B. 1990. Retinal hemorrhage after cardiopulmonary resuscitation in children: an etiologic reevaluation [see comments]. *Pediatrics* **85**:585–8.

Goldstein B, Kelly MM, Bruton D, *et al.* 1993. Inflicted versus accidental head injury in critically injured children. *Crit Care Med* **21**:1328–32.

Gornall P, Ahmed S, Jolleys A, *et al.* 1972. Intra-abdominal injuries in the battered baby syndrome. *Arch Dis Child* **47**:211–4.

Grunebaum M, Horodniceanu C, Steinherz R. 1980. The radiographic manifestations of bone changes in copper deficiency. *Pediatr Radiol* **9**:101–4.

Hahn YS, Raimondi AJ, McLone DG, *et al.* 1983. Traumatic mechanisms of head injury in child abuse. *Child's Brain* **10**:229–41.

Hall C, Shaw D. 1991. Non-accidental injury. *Curr Imaging* **3**:88–93.

Hall JR, Reyes HM, Horvat M, *et al.* 1989. The mortality of childhood falls [see comments]. *J Trauma* **29**:1273–5.

Harcourt B, Hopkins D. 1971. Ophthalmic manifestations of the battered-baby syndrome. *Br Med J* **3**:398–401.

Harwood-Nash CE, Hendrick EB, Hudson AR. 1971. The significance of skull fractures in children. A study of 1,187 patients. *Radiology* **101**:151–6.

Helfer RE, Slovis TL, Black M. 1977. Injuries resulting when small children fall out of bed. *Pediatrics* **60**:533–5.

Hobbs CJ. 1984. Skull fracture and the diagnosis of abuse. *Arch Dis Child* **59**:246–52.

Hood I, Ryan D, Spitz WU. 1988. Resuscitation and petechiae. *Am J Forensic Med Pathol* **9**:35–7.

Howard MA, Bell BA, Uttley D. 1993. The pathophysiology of infant subdural haematomas. *Br J Neurosurg* 7:355–65.

Ingraham F, Heyl L. 1939. Subdural haematoma in infancy and childhood. *JAMA* **112**:198–204.

Ingram DM, Everett VD, Ingram DL. 2001. The relationship between the transverse hymenal orifice diameter by the separation technique and other possible markers of sexual abuse. *Child Abuse Negl* **25**:1109–20.

Kanter RK. 1986. Retinal hemorrhage after cardiopulmonary resuscitation or child abuse. *J Pediatr* **108**:430–2.

Kaur B, Taylor D. 1990. Retinal haemorrhages [see comments]. *Arch Dis Child* **65**:1369–72.

Kaur B, Taylor D. 1992. Fundus hemorrhages in infancy. *Surv Ophthalmol* **37**:1–17.

Kempe CH. 1971. Paediatric implications of the battered baby syndrome. *Arch Dis Child* **46**:28–37.

Kempe CH, Silverman FN, Steele BF, *et al.* 1963. Battered child syndrome. *JAMA* **181**:17–20.

Kiffney G. 1964. The eye of the battered child. *Arch Ophthalmol* **72**:231–3.

Kirschner RH, Stein RJ. 1985. The mistaken diagnosis of child abuse. A form of medical abuse? *Am J Dis Child* **139**:873–5.

Kleinman P. 1987. *Diagnostic imaging of child abuse.* Williams and Wilkins, Baltimore.

Kleinman PK, Marks SC, Blackbourne B. 1986. The metaphyseal lesion in abused infants: a radiologic-histopathologic study. *AJR Am J Roentgenol* **146**:895–905.

Kleinman PK, Marks SC, Adams VI, *et al.* 1988. Factors affecting visualization of posterior rib fractures in abused infants. *AJR Am J Roentgenol* **150**:635–8.

Knight B. 1986. The history of child abuse. *Forensic Sci Int* **30**:135–41.

Knight B. 1989. *The autopsy in child abuse.* In: Mason JK (ed.), *Paediatric forensic pathology*. Chapman and Hall, London.

Kobayashi M. 2001. Infant abuse in Osaka: health center activities from 1988 to 1999. *Pediatr Int* **43**:197–201.

Kogutt MS, Swischuk LE, Fagan CJ. 1974. Patterns of injury and significance of uncommon fractures in the battered child syndrome. *Am J Roentgenol Radium Ther Nucl Med* **121**:143–9.

Kravitz H, Driessen G, Gomberg R, *et al.* 1969. Accidental falls from elevated surfaces in infants from birth to one year of age. *Pediatrics* **44**(Suppl):869–76.

Lauer B, ten Broeck E, Grossman M. 1974. Battered child syndrome: review of 130 patients with controls. *Pediatrics* **54**:67–70.

Leventhal JM, Thomas SA, Rosenfield NS, *et al.* 1993. Fractures in young children. Distinguishing child abuse from unintentional injuries. *Am J Dis Child* **147**:87–92.

Mann K, Chan K, Yue C. 1986. Skull fractures in children: their assessment in relation to developmental skull changes and acute intracranial haematomas. *Child's Nerv Syst* **2**:258–61.

Mason JE. 1990. *Paediatric forensic medicine and pathology.* Chapman and Hall, London.

Maxeiner H. 2001. Demonstration and interpretation of bridging vein ruptures in cases of infantile subdural bleedings. *J Forensic Sci* **46**:85–93.

McClelland CQ, Rekate H, Kaufman B, *et al.* 1980. Cerebral injury in child abuse: a changing profile. *Child's Brain* **7**:225–35.

McCort J, Vaudagna J. 1964. Visceral injuries in battered children. *Radiology* **124**:681–4.

Milroy CM. 1999. Munchausen syndrome by proxy and intra-alveolar haemosiderin. *Int J Legal Med* **112**:309–12.

Morild I, Gjerdet NR, Giertsen JC. 1993. Bone strength in infants. *Forensic Sci Int* **60**:111–19.

Mushin AS. 1971. Ocular damage in the battered-baby syndrome. *Br Med J* **3**:402–4.

Nimityongskul P, Anderson LD. 1987. The likelihood of injuries when children fall out of bed. *J Pediatr Orthop* **7**:184–6.

Nokes L, Roberts A, Knight B. 1995. The use of the gadd severity index in forensic medicine: a case study. *Forensic Sci Int* **76**:85–90.

Norman MG, Smialek JE, Newman DE, *et al.* 1984. The postmortem examination on the abused child.

Pathological, radiographic, and legal aspects. *Perspect Pediatr Pathol* **8**:313–43.

Norton L. 1983. Child abuse. *Clin Lab Med* **3**:321–42.

O'Connor J, Cohen J. 1987. Dating of fractures. In: Kleinman P (ed.), *Diagnostic imaging of child abuse.* Williams and Wilkins, Baltimore.

Ogata M, Tsuganezawa O. 1995. An isolated perforation of the jejunum caused by child abuse. A case report. *Am J Forensic Med Pathol* **16**:17–20.

Ojima K, Matsumoto H, Hayase T, *et al.* 1994. An autopsy case of osteogenesis imperfecta initially suspected as child abuse. *Forensic Sci Int* **65**:97–104.

Parsons MA, Start RD. 2001. Acp best practice no. 164: necropsy techniques in ophthalmic pathology. *J Clin Pathol* **54**:417–27.

Pearn J. 1990. Physical abuse of children. In: Mason JK (ed.), *Paediatric forensic medicine and pathology.* Chapman and Hall, London, pp. 204–20.

Pena SD, Medovy H. 1973. Child abuse and traumatic pseudocyst of the pancreas. *J Pediatr* **83**:1026–8.

Pollanen MS, Smith CR, Chiasson DA, *et al.* 2002. Fatal child abuse – maltreatment syndrome. A retrospective study in Ontario, Canada, 1990–1995. *Forensic Sci Int* **126**:101–4.

Polson CJ, Gee D, Knight B. 1985. *Essentials of forensic medicine*, 4th edn. Pergamon Press, Oxford.

Rao N, Smith RE, Choi JH, *et al.* 1988. Autopsy findings in the eyes of fourteen fatally abused children. *Forensic Sci Int* **39**:293–9.

Reiber GD. 1993. Fatal falls in childhood. How far must children fall to sustain fatal head injury? Report of cases and review of the literature. *Am J Forensic Med Pathol* **14**:201–7.

Reichelderfer TE, Overbach A, Greensher J. 1979. Unsafe playgrounds. *Pediatrics* **64**:962–3.

Rekate HL. 1985. Subdural hematomas in infants [letter]. *J Neurosurg* **62**:316–17.

Rivara FP, Kamitsuka MD, Quan L. 1988. Injuries to children younger than 1 year of age. *Pediatrics* **81**:93–7.

Root I. 1992. Head injuries from short distance falls [see comments]. *Am J Forensic Med Pathol* **13**:85–7.

Sezen F. 1971. Retinal haemorrhages in newborn infants. *Br J Ophthalmol* **55**:248–53.

Shannon P, Smith CR, Deck J, *et al.* 1998. Axonal injury and the neuropathology of shaken baby syndrome. *Acta Neuropathol (Berl)* **95**:625–31.

Silverman FN. 1972. Unrecognized trauma in infants, the battered child syndrome, and the syndrome of Ambroise Tardieu. Rigler lecture. *Radiology* **104**:337–53.

Smith FW, Gilday DL, Ash JM, *et al.* 1980. Unsuspected costo-vertebral fractures demonstrated by bone scanning in the child abuse syndrome. *Pediatr Radiol* **10**:103–6.

Spevak MR, Kleinman PK, Belanger PL, *et al.* 1994. Cardiopulmonary resuscitation and rib fractures in infants. A postmortem radiologic-pathologic study. *JAMA* **272**:617–18.

Tardieu A. 1860. Etude medico-legale sur les services et mauvais traiments exerces sur les enfants. *Ann Hyg Pub Med Leg* **13**:361–98.

Thomas PS. 1977. Rib fractures in infancy. *Ann Radiol Paris* **20**:115–22.

Thomas SA, Rosenfield NS, Leventhal JM, *et al.* 1991. Long-bone fractures in young children: distinguishing accidental injuries from child abuse. *Pediatrics* **88**:471–6.

Tomasi LG, Rosman NP. 1975. Purtscher retinopathy in the battered child syndrome. *Am J Dis Child* **129**:1335–7.

Touloukian RJ. 1968. Abdominal visceral injuries in battered children. *Pediatrics* **42**:642–6.

Vowles GH, Scholtz CL, Cameron JM. 1987. Diffuse axonal injury in early infancy. *J Clin Pathol* **40**:185–9.

Wagner GN. 1986. Crime scene investigation in child-abuse cases. *Am J Forensic Med Pathol* **7**:94–9.

Weber W. 1984. [Experimental studies of skull fractures in infants.] *Z Rechtsmed* **92**:87–94.

Weber W. 1985. [Biomechanical fragility of the infant skull.] *Z Rechtsmed* **94**:93–101.

Weedn VW, Mansour AM, Nichols MM. 1990. Retinal hemorrhage in an infant after cardiopulmonary resuscitation. *Am J Forensic Med Pathol* **11**:79–82.

Williams RA. 1991. Injuries in infants and small children resulting from witnessed and corroborated free falls. *J Trauma* **31**:1350–2.

Wilson E. 1977. Estimation of the age of cutaneous contusions in child abuse. *Pediatrics* **60**:750–5.

Wooley PV, Evand WA. 1955. Significance of skeletal lesions in infants resembling those of traumatic origin. *JAMA* **158**:539–43.

Worlock P, Stower M, Barbor P. 1986. Patterns of fractures in accidental and non-accidental injury in children: a comparative study. *Br Med J Clin Res Ed* **293**:100–2.

Yukawa N, Carter N, Rutty G, *et al.* 1999. Intra-alveolar haemorrhage in sudden infant death syndrome: a cause for concern? *J Clin Pathol* **52**:581–7.

CHAPTER 23

Deaths associated with surgical procedures

- The autopsy on deaths associated with surgery and anaesthesia 480
- The mode and cause of death after surgery and anaesthesia 482
- Deaths associated with anaesthesia 484
- Malignant hyperthermia 485
- Autopsy procedure 486
- References and further reading 486

In most jurisdictions, deaths that occur during or within a short time after surgical operation, invasive diagnostic procedure or an anaesthetic, become the subject of a medicolegal investigation. Similarly, any death thought to be caused or contributed to, by any of these procedures – irrespective of the interval – may be enquired into if the medical attendants or the relatives consider that a causal relationship exists. To be effective such investigations must include an autopsy, and the pathologist involved in these has a difficult and often professionally sensitive task.

The pathologist should, wherever possible, be independent of the institution in which either the death occurred or which carried out the procedure. This is partly why the services of a forensic pathologist should be retained by the investigating authority, rather than a clinical or histopathologist belonging to the hospital, or associated institution. It is important that a separation should exist – and be seen to exist – between the loyalties of these two elements, not because there is any substantial likelihood of collusion, but because the public and private interest is best served by displaying the independence of the pathologist. In addition, there may be professional embarrassment when a close colleague of a surgeon or anaesthetist is placed in a potentially critical position within the same institution.

It is also sometimes useful to have the technical advice and expert opinion of an independent clinical consultant who is unconnected with the hospital, and who is not a colleague of the team involved in incident.

THE AUTOPSY ON DEATHS ASSOCIATED WITH SURGERY AND ANAESTHESIA

A number of difficulties exist, that are peculiar to this type of death. The following matters need particular attention:

- The morphological findings, especially in so-called 'anaesthetic deaths', may be minimal or even absent so, more than in any other type of case, expert advice and full clinical information are essential.
- Technically the autopsy on a post-operative death may be difficult as a result of the surgical intervention and its sequelae, especially in abdominal and thoracic procedures. Exudate, sepsis, adhesions, haemorrhage, oedema and distortion of the normal anatomy may make the dissection difficult, especially if the details of the surgical procedure are not fully known. Post-mortem changes can further complicate the appearances: for example, recent suture lines in the intestine or stomach may appear to be leaking, but this may be caused by autolysis, and even handling the tissues at autopsy may tear devitalized and autolytic structures even further.
- Numerous surgical and anaesthetic devices may have been introduced into the patient during the procedure, such as airways, endotracheal tubes, indwelling needles, intravascular cannulae, self-retaining catheters, wound

drains, chest tubes, monitoring electrodes, and metal or plastic prostheses. It is essential that none of these be removed before autopsy, as their proper placement and patency may need to be checked. Standing orders should be issued to hospitals within the jurisdiction of any coroner or medical examiner to the effect that no post-mortem interference with the body be made by members of the medical, nursing, technical or portering staff, as it has happened in the past that the single vital piece of evidence about some technical mishap has been discarded by some well-meaning person.

- Before any further disturbance of the body is made (for instance, by turning it over to look at the back) and certainly before a knife is picked up, the position of any endotracheal tube that may remain after anaesthesia must be checked. If the clinical information raises any doubt whatsoever about its malposition, then a pre-autopsy radiograph should be obtained, both anteroposterior and lateral.

  Oesophageal intubation is not all that uncommon in anaesthetic mishaps and should be investigated carefully. The tube may be palpable through the skin if properly in the trachea – if there is doubt, a small primary incision in the midline of the neck with a further careful cut into the trachea can resolve the matter. Sometimes the intubation has been into the oesophagus, then been rectified after the damage has been done. Here the pathologist may find a ring of oedematous oesophageal mucosa still present at a level equal to that of the tube in the trachea. When nitrous oxide or other anaesthetic gas has previously been passed down a tube in the oesophagus there may be distension of the stomach and intestines. A sample of the contained gas may reveal the agent on analysis.
- The hospital laboratory should be requested to retain any ante-mortem blood or body-fluid samples sent to them so that they remain available for analytical checks, such as blood grouping in transfusion mishaps, or creatine phosphokinase activity in malignant hyperthermia.
- Even more than usual, the fullest information is needed before beginning the autopsy. The patient's notes are essential, together with any other relevant information. Sometimes the nursing records may be more helpful



FIGURE 23.1 *Aorto-oesophageal fistula (arrow) due to ruptured anastomosis causing fatal haematemesis 18 days after replacement of the thoracic aorta with a prosthesis.*



FIGURE 23.2 *Gut strangulated through the handle of forceps left in the abdomen during surgery and detected during an unrelated autopsy six weeks later for pneumoconiosis assessment.*



FIGURE 23.3 *Bronchial obstruction by the cover of a ballpoint pen, used by a midwife to hold down the tongue of a pregnant woman, who died days after childbirth from pneumonia.*

than the medical notes, as they are frequently more detailed and recorded at shorter intervals.

Equally important is the attendance of clinicians at the autopsy. Indeed, in deaths associated with anaesthesia, this is usually more useful than the post-mortem dissection, which frequently reveals little or no morphological evidence. Sadly, attendance at autopsies has declined markedly in recent years, as have requests for clinical autopsies, but every effort should be made to secure the presence of someone who knows the circumstances of the case well and who can point out to the pathologist the procedures that were carried out. A discussion across the autopsy table is of paramount importance and it is of little use if a junior doctor is delegated to attend, especially if he confesses to knowing little or nothing about the patient.

Especially in anaesthetic-related deaths, this dialogue with a clinician – in this case, the anaesthetist – may provide virtually all the data upon which to base a cause of death. Discussion between pathologist, surgeon and anaesthetist may arrive at an amicable conclusion that will be the best consensus of opinion to offer the investigating authority in cases where a bare autopsy might reveal little or nothing upon which to base any interpretation of the fatal processes.

- During the autopsy, care must be taken to detect any surgical emphysema, pneumothorax or air embolism. When surgical operations have been conducted with the patient in the sitting position, as in posterior fossa neurosurgery or some thyroidectomies, the possibility of air aspiration into open veins or venous sinuses always exists.

  Where infusion or transfusion mishaps may be a possibility, especially where gas pressure has been used to hasten the infusion rate, the possibility of air embolism must always be borne in mind.

THE MODE AND CAUSE OF DEATH AFTER SURGERY AND ANAESTHESIA

The rather loose terms ‘operative deaths’ and ‘anaesthetic deaths’ are usually inaccurate descriptions. When used without due consideration, they may lead to medico-legal enquiries and even civil litigation, which is not justified by the actual circumstances.

Fatalities associated with surgical intervention or invasive diagnostic procedures can be separated into several categories:

- those directly caused by the disease or injury for which the operation or anaesthetic was being carried out
- those caused by a disease or abnormality other than that for which the procedure was being carried out
- those resulting from a mishap during, or a complication of, the surgical or diagnostic procedure
- those resulting from a mishap during, or a complication of, the anaesthetic being administered.

These groups must be considered in more detail.

Deaths directly caused by disease or injury for which surgery is performed

Many deaths during a surgical or diagnostic procedure or an anaesthetic are caused by the disease process or injury for which the procedure was being performed. The death may be virtually inevitable in some ‘heroic’ operations where urgent intervention is the only hope of saving life. Presumably there must have been some chance of success or even palliation, otherwise the intervention would not have been justified, but the decision not to operate may be difficult. When death occurs from the effects of such disease or injury, some medico-legal systems will certify the original condition as the cause of death and omit any reference to the intervention.

The American Society of Anesthesiologists have a classification system for deaths during surgical procedures, as follows:

- ASA 1: those with no serious disease
- ASA 2: those who may have a serious disease, but have no limitations on their activities
- ASA 3: those with serious disease and some limitation of their activities
- ASA 4: those with a serious disease that is a constant threat to their health and that limits their activities
- ASA 5: those with such serious disease that their death can be expected within 24 hours, with or without treatment.

The Society recommended that classes 1–3 require full investigation, as they were expected to survive; those in class 4 that were elective and not emergency procedures, with no expectation of death, are also included. The general principle is that unexpected deaths are investigated, though in the British coroner and Procurator Fiscal system there are no exceptions to such investigations, once reported by doctors to the appropriate legal authority.

Pathologists in some jurisdictions have problems in the nomenclature of certification following an autopsy. The strict test to be applied should be: ‘Would death have occurred when it did, if the operation had not taken place?’ Sometimes this is impossible to answer and the balance of probabilities may be evenly poised. If a patient has a leaking aortic aneurysm, which catastrophically ruptures whilst the surgeon is still making his skin incision, most would agree that the original disease process was the primary cause of death. Even here, however, it may be argued that the added disturbance of preparation and anaesthesia contributed something to a possible slight rise in blood pressure that further split the aneurysm wall.

Where a person dies of a pulmonary embolus 7 days after an elective gastrectomy for peptic ulcer, the connection between the operation and the death can hardly be denied, even though in up to a fifth of fatal pulmonary embolisms, depending on the study, no predisposing factors have been found (see Chapter 13).

When both trauma and surgical operation have taken place, then it can be impossible to separate the relative contributions of each to a death. A common example would be death a few days after the pinning of a fractured neck or femur in an old person. A fatal bronchopneumonia, pulmonary embolism or acute cardiac failure might all be caused either by the original trauma, by the stress of operation or by the subsequent immobilization in bed.

Death due to a disease or disability other than that for which surgery is performed

Where death is due to a disease or disability other than that for which the operation was performed, a distinction has to be drawn between those conditions that were known before the operation and those which were unsuspected.

When some disease is known beforehand, it must be evaluated in deciding whether or not the operative procedure is justified. For example, a patient with a non-obstructing hernia who has chronic obstructive airways disease might be thought to be too poor a risk for an elective, prophylactic operation. If that same patient's hernia becomes strangulated and he develops potentially fatal intestinal obstruction, however, the risk:benefit ratio dramatically changes and the danger of a perioperative death may have to be accepted. Naturally, operative and anaesthetic techniques may have to be modified to take account of the known adverse conditions.

It is different when an occult disease process is not suspected by the clinicians. It may be that they had no diagnostic means of appreciating the risk – such as an unsuspected phaeochromocytoma – but a medico-legal problem can arise if they took no reasonable precautions in detecting common risk factors, such as hypertension, lung disease or ischaemic heart disease, which in retrospect could have been diagnosed.

Death as a result of failure of surgical technique

Exceptionally, death is the result of a failure of surgical technique. This may be inadvertent, from a true 'accident', sometimes caused by unusually difficult operative circumstances, to anatomical abnormalities or even failure of equipment. When it is the result of error or incompetence, then a legal action for negligence may ensue and the pathologist must be even more meticulous than usual in producing a detailed, objective and impartial report. In all these cases, the presence of the surgeon is essential, so that agreement can be reached on what actually was found at autopsy.



FIGURE 23.4 *Calcification of myocardium and vascular endothelium (arrow) due to postoperative rhabdomyolytic myoglobinuria and acute renal failure after reconstructive hand surgery and the interruption of blood circulation to the corresponding arm for the time of a nerve reconstruction. (Von Kossa staining, original magnification ×100.)*



FIGURE 23.5 *Immunohistochemical demonstration of myoglobin in the renal tubuli with Anti-Human Myoglobin (Dakopatts a/s, Denmark).*

When a failure of equipment may be responsible, then expert examination and advice is essential. Anaesthetic machines, gas supply, compatibility of connections and all the sophisticated hardware of operating theatres must be subjected to the most rigorous inspection if a malfunction is suspected. This is no part of the pathologist's concern but, as he is responsible for the eventual decision about the cause of death, any conclusions about an equipment failure must be communicated to him.

Deaths due to anaesthetic administration

The foregoing categories account for most perioperative deaths and fatalities following surgery, even if delayed. True 'anaesthetic deaths' are comparatively rare, but have such potential medicolegal importance that they must be discussed in more detail.

DEATHS ASSOCIATED WITH ANAESTHESIA

Even more than is the case with surgeons, any autopsy on an anaesthetic-related death must be a cooperative process with the anaesthetist. Not only are the objective autopsy findings in true anaesthetic deaths meagre or absent, but the pathologist's training and experience of the complex techniques of modern anaesthesia is insufficient for him to appreciate, analyse and criticise constructively without the expert knowledge of the anaesthetist.

Most anaesthetic-related deaths are not caused by the anaesthetic agent itself, but due to other aspects of the procedure. Patients have anaesthetics because they have some significant – often very serious – disease or injury and, as has already been discussed, it is more likely that the fatality was the result of these or of some co-existent condition rather than the anaesthetic. There is a tendency on the part of relatives – and sometimes their lawyers – to assume that because someone died 'under' an anaesthetic, then this must be the major or even sole factor in the death because it was so closely related in time.

When factors other than anaesthesia can be excluded, certain features can be identified. A survey was conducted by Lunn and Mushin (1982) for the Association of Anaesthetists. This indicated that, although 1 in every 166 patients died within 6 days of a surgical operation, only 1 in 10 000 die solely as a consequence of the anaesthetic. Anaesthesia contributed to (but not totally caused) the death of 1 in every 1700 patients, many of these deaths being potentially avoidable.

The survey also showed that the causes have not changed significantly during the last 30 years, in spite of marked changes in anaesthetic technology and that anaesthesia may contribute to deaths that occur more than 24 hours after the administration. Many patients suffer from intercurrent disease unrelated to their surgical condition, but the implications for the anaesthetist are all too often ignored. The major causes of true anaesthetic fatalities include inexperienced and insufficiently supervised junior staff. Allowing periods of hypoxia to occur appears to be one of the common faults leading to a fatal outcome.

As far as the pathologist is concerned, the survey complained that the autopsy is of limited value in investigating the death. All too often irrelevant findings are offered, such as 'bronchitis'. Ischaemic heart disease was recorded in 39 per cent of the series. It was emphasized that the investigation of such deaths cannot be the sole province of the pathologist, but must rely heavily upon clinical data and cooperation with other doctors. Earlier investigations indicated that acute cardiovascular failure was the most common cause of unexpected death during anaesthesia. Lahey and Ruzicka in 1950 measured the risk of death during anaesthesia as about 1/1000, from all causes. Cardiac arrest was the most common single mode of death, being seen on average once or twice a year in most busy operating suites even under the most careful surgical and anaesthetic regimens. The autopsy is usually unhelpful in determining the cause, if coronary insufficiency can be excluded. Most cardiac arrest occurs under relative light anaesthesia and thus tends to occur at either the start or finish of the surgical procedure.

Reid and Brace (1940) showed that the arrest is mainly neurogenic and that any irritation of the respiratory tract, such as laryngoscopy or intubation, may cause a lightly anaesthetized patient to have a cardiac arrest. Inexperienced anaesthetists may not keep the patient at a level of unconsciousness appropriate to the manipulations of the surgeon, as it has been shown that such procedures can also precipitate arrest during light anaesthesia.

Hypoxia is also a potent precipitating factor in cardiac arrest. Deaths from respiratory failure also occur, and hypoxia is again a prime example – either from faults in the apparatus or more commonly to inexperience of the anaesthetist, especially in handling equipment with which he is not familiar. An overdose of the anaesthetic agent may depress the respiratory centres and begin a descending spiral of hypoxia. Excessive premedication and the use of muscle paralysing agents may also predispose towards respiratory failure unless appropriate measures are taken, such as assisted respiration.

Airway obstruction is another danger – from blood, teeth, dentures, faults in the connecting tubing, laryngeal spasm, swabs and an abnormal posture of the neck. Though regurgitation of gastric contents is a real danger, the use of



FIGURE 23.6 *Birefringent material in the alveoli due to contrast medium aspiration (barium sulphate).*

cuffed endotracheal tubes has greatly reduced the hazard. From the pathologist's point of view, the finding of gastric contents in the airways must be backed up by some clinical evidence of its ante-mortem origins, as a quarter of bodies have some gastric contents in some part of the air passages at autopsy, mostly as a result of agonal or even post-mortem transfer that is a consequence of the dying process, not a cause (Chapter 14).

Rarely, some physical fault in the anaesthetic equipment may cause death. Mention has been made of faults in the connecting tubing, which may be internal delamination, not visible from outside. Flow-meter errors occur, but a more common one is the confusion of bottled or piped gas supplies, and the inadvertent use of the wrong substance or the connection of an empty cylinder. Two such fatalities, where the wrong gas was introduced into the theatre piped supply, occurred in Hong Kong in recent years.

Fires are not uncommon, the most frequent danger being the ignition of spirit-based skin antiseptics ignited by cautery. Any electrical apparatus is potentially dangerous, and defective cauteries, defibrillators and diathermy equipment have all caused death.

Explosions from inflammable gases and vapours, such as cyclopropane and ether, have been catastrophic on occasions.

Hazards of local and epidural anaesthesia

Local anaesthetics rarely cause death, though the overall rate of complications is about 1/2000. Hypersensitivity and escape of contained adrenergic drugs form the major fatal hazards. It is said that most cases of 'hypersensitivity' are really overdosage, but there are undoubtedly some patients who have an abnormal sensitivity to the cocaine-like active constituents. Legal actions have been brought against doctors for failure to give a test skin dose before injecting the major quantity. Diffusion away from the operative site of adrenaline-like substances used to vasoconstrict the area and thus retain the anaesthetic effect may cause a sudden cardiac arrest.

Epidural and spinal anaesthesia has returned to favour, especially in obstetrics, after a period in which spinal injection of anaesthetic agents fell into disrepute because of a number of lawsuits brought because of spinal cord damage as a result of contaminants or excessive dosage.

The upwards diffusion of the active agents may cause paralysis, and the effect upon the vasomotor system may lead to a precipitous fall in blood pressure. Total spinal anaesthesia from upward diffusion blocks all sympathetic efferent impulses so, if the concentration of the anaesthetic agent in the upper thoracic and cervical spinal fluid level is high enough, efferent transmission to all motor fibres of the respiratory muscles will be blocked.

Epidural anaesthesia has now replaced intrathecal administration, but even this has occasional tragedies, and is said to have a 1/10 000 incidence of permanent nerve paralysis. This usually comes about either from an overdose or from puncture of the theca, instead of the anaesthetic solution remaining in the epidural space. In the rare autopsies on such deaths, a sample of cerebrospinal fluid should be taken for analysis to ascertain the concentration of anaesthetic substance. An attempt should be made to find the puncture in the dura, which is easier said than done. If an epidural catheter is still in place for continuous administration of the active agent, dye or Indian ink can be injected to see if it enters the subdural space.

MALIGNANT HYPERTHERMIA

This is a familial condition in which certain agents, including some anaesthetics and muscle relaxants, precipitate a metabolic change in skeletal muscle with the production of energy, and hence a rapid and sometimes fatal rise in temperature. The basic condition is an autosomal dominantly inherited trait associated with sudden uncoupling of oxidative phosphorylation, accompanied by massive energy production from the muscles with consequent overheating.

When malignant hyperthermia is diagnosed, the family members should be investigated, preferably by muscle biopsy, to assess the risk of their suffering a similar crisis if subjected to anaesthesia. In 70 per cent of carriers, the creatine phosphokinase and aldolase activities are elevated, though the basic abnormality appears to be a defect in calcium transfer and phosphorylation within the muscle fibres. This is one reason why hospital laboratories should be asked to retain any pre-mortem blood samples, as the creatine phosphokinase activity can be estimated retrospectively.

Suxamethonium and halogenated anaesthetic agents seem particularly prone to precipitate the condition. Halothane is one of the agents associated with malignant hyperthermia, either alone or in combination with suxamethonium. The condition occurs about once in every 10 000 anaesthetics, with various estimates ranging from 1/5000 to 1/70 000. There are virtually no autopsy features of any significance and the diagnosis is made on clinical grounds. The features of malignant hyperthermia include a sudden rise in temperature, sometimes reaching 43°C, with stiffening of the skeletal muscles, rapid heart rate and respiratory distress.

Halothane anaesthesia has acquired the reputation for causing liver injury known as halothane hepatitis and, rarely, a fulminant hepatic failure. Its incidence varies between 1/35 000 and 1/600 000 and if halothane anaesthesia is repeated within one month, 1/6000–1:22 000. It is a typical example of immune-mediated adverse drug reactions. Other drugs used in anaesthesia are occasionally responsible for death. Barbiturates used in induction, such as thiopentone, may give rise to cardiorespiratory failure, often because the quantity used has been excessive. Trichlorethylene and atropine have been involved in fatalities, the usual mode being sudden circulatory failure.

AUTOPSY PROCEDURE

In most autopsies on deaths during anaesthesia, toxicological investigations are generally unrewarding, except where overdose with specific drugs such as barbiturate or adrenaline is involved. It is usually impossible to make any quantitative assessment of the amount of volatile agents present, such as nitrous oxide, halothane or cyclopropane, even though some American writers advocate clamping a main bronchus and retaining a lung in a plastic – or preferably nylon – bag, so that head-space gas can be analysed. Neither is it practical to try to prove hypoxia by post-mortem measurement of blood gases. Usually the function of the autopsy is to discover or exclude natural disease, and mechanical blockages, as the pharmacological aspects are usually beyond investigation. Even when it seems obvious that a surgical error has taken place, one should be careful and not jump to conclusions nor let this distract from a thorough investigation. A full range of specimens for histological examination should be taken to exclude occult conditions such as a lymphoma or myocarditis, as well as to investigate the severity of the disease for which the surgical procedure was being performed. This includes also the investigation of any surgical specimens taken during the operation and sent to the histopathologist. Histological examination of the brain (fixed before cutting wherever possible) must be carried out. Though most mishaps will have occurred too quickly for much hope of any stigmata of cerebral hypoxia to be seen, changes can classically occur in Sommer's area of the hippocampal gyrus. Perhaps an even better marker is the distal parts of the cerebellar folia, where pallor and rapid loss of Purkinje cells can be seen within a few hours.

The work of Plum (Plum and Posner 1984) is relevant in this respect, as he found morphological changes in the brains of victims of only slight hypoxic periods who survived for long periods after an anaesthetic. At autopsy he recorded diffuse, severe leucoencephalopathy of the cerebral hemispheres, with sparing of the immediate subcortical connecting fibres and – usually – of the brainstem. Demyelination and obliteration of axons was observed and sometimes infarction of the basal ganglia. The cortical neurones were spared, however, and the damage appeared confined to the white matter. Plum attributed this damage to greater glycolysis in the white matter during hypoxia, compared with the grey.

Some new immunohistochemical techniques have been used in animal experiment to demonstrate structures of the cytoskeleton, e.g. in detecting ischaemic/hypoxic damage. Great caution must be exercised, however, when using these methods in autopsy material and it is therefore crucial to examine alterations occurring in the cytoskeleton as a result of post-mortem delay before conclusions can be drawn from the possible changes observed. Irving *et al.* (1997) investigated the post-mortem distribution of microtubule-associated proteins (MAP) in various regions of rat brain using immunohistochemistry. They showed that each MAP underwent unique changes that were dependent both on post-mortem interval and the brain region examined. Following long post-mortem delays, some of the changes in these proteins were similar to those seen in rodent models of cerebral ischaemia.

REFERENCES AND FURTHER READING

Adelstein A, Loy P. 1979. Fatal adverse effects of medicines and surgery. *Popul Trends* **17**:17–21.

Beecher HK, Todd DP. 1954. A study of deaths associated with anesthesia and surgery: based on a study of 599 548 anesthesias in ten institutions 1948–1952. *Ann Surg* **140**:2–12.

Briely JB. 1963. Cerebral injury following cardiac operations. *Thorax* **19**:291–6.

Britt BA, Locher WG, Kalow W. 1969. Hereditary aspects of malignant hyperthermia. *Can Anaesth Soc J* **16**:89–98.

Campling EA, Devlin HB, Lum JN. 1990. Gynaecology and the national confidential enquiry into perioperative deaths. *Br J Obstet Gynaecol* **97**:466–7.

Campling EA, Devlin HB, Lunn JN. 1989, 1990, 1992. *The report of the National Confidential Enquiry into*

Perioperative Deaths, *1989, 1990, 1992.* Royal College of Surgeons, London.

Campling EA, Devlin HB, Lunn JN. 1992. Reporting to NCEPOD. *Br Med J* **305**:252.

Caplan RA, Ward RJ, Posner K, *et al.* 1988. Unexpected cardiac arrest during spinal anesthesia: a closed claims analysis of predisposing factors [see comments]. *Anesthesiology* **68**:5–11.

Carr NJ, Burke MM, Corbishley CM, *et al.* 2002. The autopsy: lessons from the national confidential enquiry into perioperative deaths. *J R Soc Med* **95**:328–30.

Corby C, Camps FE. 1960. Therapeutic accidents during the administration of barium enemas. *J Forensic Med* **7**:206–20.

Denborough MA, Lovell RR. 1960. Anaesthetic deaths in a family. *Lancet* **2**:45–6.

Dinnick OP. 1964. Deaths associated with anaesthesia: a report on 600 cases. *Anaesthesia* **19**:536–44.

Edelstein JM. 1988. Sudden death following administration of radio contrast media. *J Forensic Sci* **33**:734–7.

Edwards G, Morton HJ, Pask EA, *et al.* 1957. Deaths associated with anaesthesia: a report on 1000 cases. *Anaesthesia* **11**:194–202.

Ermenc B. 2000. Comparison of the clinical and post mortem diagnoses of the causes of death. *Forensic Sci Int* **114**:117–19.

Falk E, Simonsen J. 1979. The histology of myocardium in malignant hyperthermia: a preliminary report of 11 cases. *Forensic Sci Int* **13**:211–20.

Hunt AC. 1958. Anaesthetic causes of death on the table. *J Forensic Med* **5**:141–5.

Irving EA, McCulloch J, Dewar D. 1997. The effect of postmortem delay on the distribution of microtubule-associated proteins tau, map2, and map5 in the rat. *Mol Chem Neuropathol* **30**:253–71.

Isaacs H, Barlow MB. 1970. The genetic background to malignant hyperpyrexia revealed by serum creatine phosphokinase estimations in asymptomatic relatives. *Br J Anaesth* **42**:1077–84.

Keats AS. 1988. Anesthesia mortality – a new mechanism [editorial]. *Anesthesiology* **68**:2–4.

Lau G. 1996. Perioperative deaths: a comparative study of coroner's autopsies between the periods of 1989–1991 and 1992–1994. *Ann Acad Med Singapore* **25**:509–15.

Lau G. 2000. Perioperative deaths: a further comparative review of coroner's autopsies with particular reference to the occurrence of fatal iatrogenic injury. *Ann Acad Med Singapore* **29**:486–97.

Leading article. 1964. Halothane re-examined. *Br Med J* **3**:325.

Loghmanee F, Tobak M. 1986. Fatal malignant hyperthermia associated with recreational cocaine and ethanol abuse. *Am J Forensic Med Pathol* **7**:246–8.

Lunn J, Mushin W. 1982. *Mortality associated with anaesthesia.* Nuffield Provincial Hospital Trust, London.

Lunn JN. 1994. The national confidential enquiry into perioperative deaths. *J Clin Monit* **10**:426–8.

Lunn JN, Devlin HB, Hoile RW, *et al.* 1993. Editorial. II – The National Confidential Enquiry into Perioperative Deaths. *Br J Anaesth* **70**:382.

Macrae WA, Miller KM, Watson AA. 1979. Malignant hyperpyrexia. *Med Sci Law* **19**:261–4.

Mazzia VD, Simon A. 1979. Another look at malignant hyperthermia. In: Wecht C (ed.), *Legal medicine annual 1978.* Appleton Century Crofts, New York.

National Confidential Enquiry into Early Post-operative Deaths (NCEEPOD): various reports 1989–95. Royal College of Surgeons, London.

Plum F, Posner JB. 1984. *Diagnosis of stupor and coma*, 3rd edn. F. Davis & Co., Philadelphia.

Ranklev E, Fletcher R, Krantz P. 1985. Malignant hyperpyrexia and sudden death. *Am J Forensic Med Pathol* **6**:149–50.

Reid L, Brace D. 1940. Irritation of the respiratory tract and its reflex effect upon the heart. *Surg Gynecol Obstet* **70**:157–62.

Relton JE, Britt BA, Steward DJ. 1973. Malignant hyperpyrexia. *Br J Anaesth* **45**:269–75.

Rognum TO, Vege A. 1997. [Forensic autopsy after possible medical malpractice. A 3-year material from the institute of forensic medicine in Oslo, 1993–95.] *Tidsskr Nor Laegeforen* **117**:2969–73.

Shanks JH, McCluggage G, Anderson NH, *et al.* 1990. Value of the necropsy in perioperative deaths. *J Clin Pathol* **43**:193–5.

Start RD, Cross SS. 1999. Acp. Best practice no. 155. Pathological investigation of deaths following surgery, anaesthesia, and medical procedures. *J Clin Pathol* **52**:640–52.

Truemner KM, White S, Vanlaudingham H. 1960. Fatal embolization of pulmonary capillaries. Report of a case associated with routine barium enema. *JAMA* **173**:1089–90.

Warden JC, Horan BF, Holland R. 1997. Morbidity and mortality associated with anaesthesia. *Acta Anaesthesiol Scand* **41**:949.

CHAPTER 24

Dysbarism and barotrauma

- Physical damage 488
- The autopsy in dysbarism and barotrauma deaths 489
- Further reading 490

Damage to the body from changes in external pressure usually lies in the province of specialized occupational or armed services medicine, rather than that of the forensic pathologist. The major exception is recreational and sporting diving, using SCUBA (self-contained underwater breathing apparatus) equipment. When death occurs in such circumstances, however, though criminality is rarely a factor, there is usually some form of official enquiry, be it quasi-judicial or an internal investigation. Civil suits for compensation may arise and in these circumstances a forensic pathologist may well become involved as the expert witness providing the autopsy evidence.

Injurious pressure effects are virtually always the result of a decrease in atmospheric pressure from a previous level. This can occur either from a decrease of high pressure to normal atmospheric pressure or a decrease from normal to a low pressure. An example of the first is the decompression of a diver ascending to the surface, while the second is seen in depressurization of an aircraft at high altitude. The first is by far the most common as a source of injury and death, mainly because of the great increase in recent years of diving activity associated with the offshore oil industry, which in Britain now forms the most dangerous type of commercial employment.

Dysbarism is a term that covers all adverse effects of pressure, while barotrauma describes the mechanical damage from gas released into the tissues.

In diving, each 10 m depth of water increases the pressure on the body by one atmosphere – 101 kiloPascals (kPa) – so that, in a non-rigid diving suit, the air supply has to be provided at the appropriate pressure relative to the working depth. This depth depends on the equipment used and is limited by legal constraints – for example, in Britain, dives of more than 50 m (164 ft) are not permitted using a nitrogen/oxygen mixture, a gas such as helium being mandatory. Similarly, surface decompression is only allowed at less than this depth of 50 m (164 ft).

When air is supplied at increased pressure, the contained nitrogen (and, to a much lesser extent, carbon dioxide) will progressively dissolve in the plasma and tissue fluids, the amount being governed by Henry's law (the solubility of a gas in a liquid is proportional to its partial pressure). This itself can produce nitrogen narcosis, a state resembling drunkenness in which orientation, judgement and rational behaviour may be diminished. This can occur at depths greater than 30 m. A more physical danger, however, is when a diver who has been at high pressure for long enough to have appreciable nitrogen dissolved in his tissues is returned too quickly to normal atmospheric pressure. The dissolved gas will then come out of solution, almost as champagne effervesces when the cork is released. Gas bubbles appear in the circulation, tissues and joint cavities, and can cause 'decompression sickness' with a wide range of clinical signs and symptoms.

Bubbles in the circulation can cause gas emboli that block small vessels and give rise to infarction, especially in the central nervous system, such as the spinal cord. In addition, such bubbles can interfere with the coagulation system, causing platelet aggregation and disseminated intravascular coagulation. Subcutaneous emphysema can appear as a result of gas under the skin.

PHYSICAL DAMAGE

When sudden, or too rapid, decompression occurs, there may also be physical damage from volume changes. The gas in body cavities expands markedly as the diver rises and, unless these can be progressively vented to the exterior, pressure effects from the contained gas will occur. Such effects may develop in the paranasal sinuses, if blocked, and even in the teeth, if small vacuoles of gas are trapped in the pulp cavities. The middle ear may also be involved and ruptures of the drum can occur. None of these lesions in themselves is likely to be fatal, however, unless the pain and disability interfere with performance – then drowning is the usual cause of death.

A more serious volume effect is in the thorax because, if the air in the lungs is not vented as the diver rises, the alveolar walls may be ruptured by the gas pressure. This leads to interstitial emphysema – air bursting through the respiratory membranes into the interalveolar, interlobular and interlobar septa. Bullae may appear on the pleural surface and, if these rupture, a pneumothorax is formed. Air may reach the mediastinum and track up the tissues to appear in the neck. Apart from a disabling pneumothorax, air can break into the lung capillaries and veins with the danger of air embolism to the left side of the heart, as it cannot move back down the pulmonary arteries. The filling of the left atrium and ventricle interrupts cardiac pump function and, if the volume is sufficient, can be fatal in itself.

Even though this does not occur in most cases of air entry, smaller volumes will be swept into the systemic arterial circulation and impact in the arterioles and capillaries of target organs, especially the myocardium, spinal cord and brain, causing microinfarcts, haemorrhagic necrosis and loss of function of vital tissues. This pulmonary barotrauma is not necessarily confined to deep diving, and may occur in only 2 or 3 m of water.

Many incidents occur to sporting divers, rather than to professionals, in relatively shallow water. The SCUBA diver is now a ubiquitous user of the seas, especially in the warmer, clearer waters of many parts of the world. It is estimated that there are about 80 000 recreational divers in the UK who complete more than two million dives each year. In 1987 there were 600 000 dives, which produced 162 incidents serious enough to be reported. Of these, 115 were of a 'medical' nature and included 8 deaths. There were 6 instances of air embolism, 69 of decompression sickness, 4 of hypothermia, 4 of nitrogen narcosis and 4 cases of ear damage. The incidence of medical incidents was 1/5000 dives, with 1 death in every 75 000 dives.

THE AUTOPSY IN DYSBARISM AND BAROTRAUMA DEATHS

Many of the vast quantity of reports on this subject deal with the clinical effects. Most deaths associated with diving are caused by drowning, though dysbaric disablement may have caused or contributed to the drowning. The autopsy must be directed to investigating the drowning aspect (Chapter 16), and to excluding or confirming any evidence of dysbarism or barotrauma.

The autopsy should not begin until some expert advisers are present, including someone with detailed knowledge of the equipment. If the victim has died in hospital or in a decompression chamber, then obviously much original information will be lost, as no *in situ* examination of the suit and breathing apparatus is possible. In any event, as few forensic pathologists are likely to be expert in this specialized field, every effort should be made to have the attendance of a naval or commercial person who is an authority on the equipment being used at the time of the death.

It has been recommended that the autopsy itself should be conducted in a decompression chamber in order to prevent the post-mortem dissipation of gas that must take place if the body is brought into atmospheric pressure. This is hardly likely to be a practical procedure except where the autopsy takes place under the aegis of armed-service or specialized commercial facilities, who have expert medical staff who are well versed in such procedures.

However, it must be recognized that the very act of decompression is likely to allow bubbles to form within the body, even if they were not there when death took place. This is an insurmountable difficulty for the pathologist unless, as just mentioned, the autopsy itself can be performed under pressure. Thus the finding of gas in the vessels and tissues has to be interpreted in the knowledge that they may be an artefact; part of the differentiation is quantitative, as a mass of froth distending the heart is unlikely to have accumulated post-mortem merely from the static fluid and tissues in the immediate vicinity, and is therefore more likely to have been brought there to form an 'airlock' by a vital circulation.

The autopsy should not begin – nor the body be undressed – until all necessary examination is made of the diving apparatus by an expert. Full photography at every stage, and radiology of the chest and major joints is essential before any dissection is attempted. It has been recommended that air samples should be taken by external lung puncture using a greased syringe so that chemical analysis can be performed to determine the oxygen:nitrogen ratio. This should only be performed under expert guidance. Externally, attention should be paid to the skin colour, as hypothermia is sometimes an associated hazard of diving. Unfortunately, many bodies recovered from water have a bright pink colour that may be post-mortem in origin, much as refrigerated bodies often have a pink hue. Red linear marks may be seen in those who have suffered 'squeezes' inside a neoprene drysuit when the external pressure has become excessive. Crepitance of the skin – usually of the head, neck and thorax – is an indication of barotrauma. The eardrums should be examined with an otoscope to detect any recent ruptures.

The brain should be removed before opening the body cavities, using a special technique to detect air in the cerebral arteries. Artery forceps should be placed on the middle cerebral, basilar and vertebral arteries before they are cut through; the brain should then be placed under water and the clamps removed to observe whether air bubbles escape from the cut ends of the vessels. The detection of air bubbles in the cerebral veins is of no significance, always being an artefact, as it is impossible to remove the calvarium without aspirating some air into the pial vessels. In any case, there is no way in which air in the arterial side of the cerebral circulation can penetrate the brain capillaries in sufficient volume to be visible in the cortical veins.

In the central nervous system, petechial haemorrhages may be seen in any part of the system, including the spinal cord. If the victim survives for a day or more, early infarcts may be seen. Histologically, ring-shaped haemorrhages around vessels may be seen in the white matter. In long-term survivors, living for some weeks, softening of the lateral and dorsal columns of the thoracic spinal cord may be seen if air emboli have impacted there.

Subcutaneous, mediastinal, retroperitoneal and subpleural emphysema must be sought. In the lungs, rupture of alveolar membranes allows air to track through the interstices from where it either enters the circulation or reaches the periphery of the lung to form subpleural bullae, or both. It can cross to the other lung via the hilum; in addition, local bronchial stenosis may trap air in a single lobe, causing a local distension.

The chest should be examined for pneumothorax, first by radiology and then by puncturing an intercostal space under a pool of water held in the lateral skin flap. Similarly, the heart should be examined radiologically for the presence of bubbles. If the air has emerged from the general tissue mass, it will have been conducted centrally by the venous drainage and so more air will be found in the right chambers than in the left side of the heart. If lung damage has occurred, then entry into the pulmonary venous system will bring it to the left side. It is hardly worth attempting to open the heart under a pericardium full of water, as froth in the chambers will be readily apparent if in sufficient volume to have caused death. Some authorities, however, advocate placing clamps on all the major thoracic vessels and the trachea before removing the thoracic pluck of organs. This is then placed under water and the clamps released to see if and from where air bubbles emerge.

Histologically, there are no particularly specific changes in spite of some claims. Lipoid-containing tissues, such as adipose tissue and adrenal cortex, may show microbubbles with a foamy appearance. There may be fatty change in the liver, possibly from air emboli. In lungs in which barotrauma has taken place, oedema, patchy haemorrhage, torn alveoli and focal emphysema confirm the macroscopic findings. The myocardium may show small foci of necrosis.

Fat embolism may occur, both in post-descent shock and in decompression in both water and high altitude. Not only fat, but cellular bone marrow may be found in target organs such as lung, myocardium, brain and kidney. There is controversy over the origin of fat emboli in decompression states, some claiming that it is caused by air-bubble disruption of fat depot tissues, while others favour a more complex genesis involving a redistribution of blood lipids, inter-relating with fibrin production and disseminated intravascular coagulation.

FURTHER READING

Brown CD, Kime W, Sherrer EL, Jr. 1978. Postmortem intravascular bubbling: a decompression artifact? *J Forensic Sci* **23**:511–18.

Busuttil A, Obafunwa J. 1995. A review of the forensic investigation of scuba diving deaths. *Sci Justice* **35**:87–95.

Calder IM. 1985. Autopsy and experimental observations on factors leading to barotrauma in man. *Undersea Biomed Res* **12**:165–82.

Calder IM. 1985. A method for investigating specialised accidents with special reference to diving. *Forensic Sci Int* **27**:119–27.

Calder IM. 1986. Dysbarism. A review. *Forensic Sci Int* **30**:237–66.

Calder IM. 1987. Use of postmortem radiographs for the investigation of underwater and hyperbaric deaths. *Undersea Biomed Res* **14**:113–32.

Davis OD. 1961. Physiological hazards of skin diving. *Med J Aust* **2**:1035–41.

Elliott D, Davis J. 1982. The causes of underwater accidents. In: Bennett PB, Elliott D (eds), *Physiology and medicine of diving*. Baillière Tindall, London.

Fryer DI. 1962. Pathological findings in fatal subatmospheric decompression sickness. *Med Sci Law* **2**:110–14.

Giertsen JC, Halvorsen JF. 1972. [Fatal scuba diving accidents. A discussion of 8 fatal cases.] *Tidsskr Nor Laegeforen* **12**:924–8.

Giertsen JC, Sandstad E, Morild I, *et al.* 1988. An explosive decompression accident. *Am J Forensic Med Pathol* **9**:94–101.

Goldhahn RT. 1976. Scuba diving deaths: a review and approach for pathologists. In: Wecht C (ed.), *Legal medicine annual 1976*. Appleton Century Crofts, New York.

Hart AJ, White SA, Conboy PJ, *et al.* 1999. Open water scuba diving accidents at Leicester: five years' experience. *J Accid Emerg Med* **16**:198–200.

Hayman J. 1985. Autopsy method for investigation of fatal diving accidents. *South Pacific Underwater Med Soc J* **15**:8–16.

Morild I, Mork SJ. 1994. A neuropathologic study of the ependymoventricular surface in diver brains. *Undersea Hyperb Med* **21**:43–51.

Obafunwa JO, Busuttil A, Purdue B. 1994. Deaths of amateur scuba divers. *Med Sci Law* **34**:123–9.

Smith N. 1995. Scuba diving: how high the risk? *J Insur Med* **27**:15–24.

Williamson JA, King GK, Callanan VI, *et al.* 1990. Fatal arterial gas embolism: detection by chest radiography and imaging before autopsy [see comments]. *Med J Aust* **153**:97–100.

CHAPTER 25

The pathology of sudden death

- Sudden or unexpected deaths 492
- Sudden death from cardiac disease 493
- Coronary atherosclerosis 493
- Sites of coronary stenosis and occlusion 495
- Myocardial infarction 495
- Complications of myocardial infarction 502
- Cause of death in coronary insufficiency 503
- Hypertensive heart disease 505
- Sudden death in aortic valve disease 506
- Sudden death from the cardiomyopathies 507
- Death in old age – the senile myocardium 509
- Sudden death from rupture of an aneurysm 509
- Pulmonary thromboembolism 513
- Sudden death in epilepsy 514
- Sudden death in bronchial asthma 515
- Respiratory obstruction 515
- Haemoptysis 516
- Gastrointestinal haemorrhage 516
- Fatal abdominal catastrophes 516
- Genitourinary system 517
- The relationship between trauma and disease 517
- References and further reading 520

Virtually all forensic pathologists deal not only with criminal, suspicious, accidental and suicidal deaths, but with a wide range of deaths from natural causes. Many of these are sudden, unexpected, clinically unexplained or otherwise obscure, even though there need be no unnatural element in their causation.

It is good that such a large substrate of natural deaths is available to most forensic pathologists: the situation where they deal exclusively with trauma and crime is professionally unhealthy, as they become progressively more out of touch with morbid anatomy, and lose daily contact with disease processes and uninjured tissues and organs. Involvement with natural death means frequent professional intercourse with clinicians and non-forensic pathologists, with all the consequent benefits of cross-fertilization of knowledge and ideas. To work in a totally forensic vacuum is to lose touch with pathological and clinical reality, which is essential for a medico-legal expert to retain a sense of proportion and an awareness of contemporary medical advances.

Another indispensable benefit of sustained experience in natural disease is the fact that some of the most difficult problems in criminal and litigious cases arise not out of gross, rapidly fatal, trauma, but in deaths where concurrent natural disease or complications after trauma lead to a fatal outcome. The assaulted victim that dies later from a stroke or the negligent minor accident that has a fatal pulmonary embolism – these can pose far greater difficulties over causation than a gunshot wound or a stabbing.

In this chapter no attempt is made to duplicate the detailed descriptions of disease processes provided in a score of illustrious textbooks of pathology, but a survey will be offered of the spectrum of causes of sudden or unexpected death as commonly encountered by forensic and 'coroner's' pathologists.

SUDDEN OR UNEXPECTED DEATHS

The definition of a sudden death varies according to authority and convention. The World Health Organization definition is of death within 24 hours from the onset of symptoms, but this is much too long for many clinicians and pathologists; some will only accept death within one hour from the onset of illness. We have to also bear in mind that a death may appear sudden and unexpected to an outsider but need not have been so from the point of the pathological disease process. The deceased may have been symptomless and utterly unaware of his chronic disease or he may have had symptoms but interpreted them as harmless. Also, fear, lack of human contact or his own disposition may have prevented him mentioning symptoms to anyone, including a doctor.

In many jurisdictions, deaths may only be certified by an attending physician if he has seen the patient recently and is satisfied that the death was caused by a potentially lethal disease from which he was aware the patient suffered. The fact that, without autopsy, this physician is wrong in his belief in between 25 and 50 per cent of cases cannot concern us at the moment, but the relevance is that, where a clinical doctor cannot so certify, the death is usually reported for medico-legal investigation. In many countries such notifications form by far the largest proportion of medico-legal autopsies, and in England and Wales they account for some 80 per cent of coroner's autopsies, the remainder being suicide, accident and homicide.

The description 'sudden' or 'unexpected' is not always accurate, as 'unexplained' is an equally common reason for medico-legal investigation. Here the clinician is unable to offer a cause for the death, though the patient was under medical care. Even after autopsy, the cause of death may still not be revealed and this problem of the obscure autopsy is discussed elsewhere.

In sudden death, the immediate cause is almost always to be found in the cardiovascular system, even though topographically the lesion is not in the heart or great vessels. Massive cerebral haemorrhage, subarachnoid bleeding, ruptured ectopic pregnancy, haemoptysis, haematemesis and pulmonary embolism, for example, join with heart disease and aortic aneurysms to contribute most of the vascular system reasons for sudden, unexpected death.

SUDDEN DEATH FROM CARDIAC DISEASE

Ischaemic heart disease is easily the most common cause of sudden death in Western nations. The term is employed rather loosely and inaccurately, often being used as if it was synonymous with 'coronary atherosclerosis'. Certainly the latter is the largest contributor to ischaemic heart disease, but not to the exclusion of other conditions.

As a further complication of nomenclature, 'coronary atherosclerosis' or 'coronary atheroma' is the proper title of the common degenerative disease that causes most deaths, but the term 'coronary artery disease' is so ingrained into popular usage that it is accepted as synonymous with coronary atherosclerosis, even though there are other coronary diseases.

Ischaemic heart disease comprises:

- coronary atherosclerosis
- hypertensive heart disease
- aortic valve disease
- anomalies of the coronary circulation
- other coronary artery diseases, such as polyarteritis
- cardiomyopathic enlargement
- some congenital heart disease.

CORONARY ATHEROSCLEROSIS

Sometimes called 'the Captain of the Men of Death', this is certainly the most frequent cause of sudden death in Western societies. The basic mechanism is stenosis or occlusion of one or more major branches of the coronary arteries by atheromatous lesions, or one of the complications of such a lesion. The severity of stenosis before death occurs is debatable: cardiac pathologists claim that at least 80 per cent of the normal lumen must be lost before myocardial necrosis occurs. Most forensic pathologists would admit to blaming coronary atheroma for death in autopsies where a significantly smaller percentage of the lumen was lost, when the symptomatology and circumstances were strongly suggestive. Areas of myocardial fibrosis and – rarely – even recent infarcts, may be seen in the presence of relatively small degrees of coronary atheroma. Part of the problem lies in quantifying the amount of stenosis at autopsy. Because of the empty vessels lacking the normal intraluminal blood pressure, the walls are lax, collapsed and unstretched. During life, the same lumen will be larger and only fixation at arterial pressure will retain a semblance of the original size. The pathologist sees all coronary arteries in the dead state, however, so the relative degree of stenosis is still a reliable observation, as both normal and diseased vessels can be compared, even if their absolute luminal size is incorrect.

Coronary atheroma may be focal, with irregular plaques that vary both in size and in stenosing effect from place to place. They may be few and localized, with a virtually normal lumen in the rest of the system. This means that every part of the major vessels must be examined at autopsy, with transverse cuts at no more than 3 mm intervals. It is unjustifiable to make a few cuts at wide intervals and claim that this provides a reliable estimate of the state of the coronary system. A coronary artery is like a chain – just as the latter is only as good as its weakest link, so a vessel is only as good as its narrowest point.

Two cuts, if even half a centimetre apart, may pass either side of a grossly stenosing plaque or a thrombus. Opening the vessels lengthwise obviates this danger, but this is outweighed by the disadvantage of not being able to measure accurately the degree of stenosis by making frequent cross-cuts. A compromise is the best answer to this dilemma, as described in Chapter 1.

Plaques are often eccentric, leaving a crescentic residual lumen, but another variety of coronary atheroma is a more diffuse lesion, where the vessel is concentrically narrowed by a more longitudinal degeneration, forming a tube-like segment with a narrow, sometimes 'pin-hole' central lumen. The author (BK) has the impression that this is more common in younger victims and that such lesions seem less likely to be ulcerated and calcified. Both types of lesion are often found in the same patient and there is presumably no fundamental difference in their pathogenesis.

Complications in coronary atheromatous lesions

ULCERATED PLAQUES

The simple endothelial thickening develops to involve the media and usually becomes infiltrated with lipids. Whilst the covering endothelium remains intact, the danger to life is confined to the luminal reduction from the bulge of the enlarging plaque. When the fibroendothelial cap begins to break down under the pressure and erosion of the central necrosing process, the plaque may rupture into the lumen. This has several consequences, which may precipitate acute symptoms or even death.

First, a large plaque may suddenly disgorge its pultaceous contents into the lumen. This can mechanically block the vessel or seriously stenose it. Thrombosis may be precipitated at that spot by the slowed blood flow plus thrombogenic tissue elements. The cap of the plaque may be projected across the lumen, forming a sudden and perhaps complete occlusion. This will be more dangerous if the open end of the ruptured plaque faces 'upstream' into the direction of the blood flow, so that the intimal cap is lifted up, causing a valve-like obstruction. When the blood flow sweeps across the cap in the opposite direction, the cap will not be displaced, though the soft, grumous contents of the plaque will be washed downstream. Sometimes the flap can be seen in histological sections, though it is difficult to know if this is a processing artefact. It is best demonstrated directly at autopsy, when two cuts are joined longitudinally and the intima examined with a lens or low-power microscope.

The contents of the plaque may be washed downstream by the blood flow, eventually impacting in small branches and occluding them. These can be seen histologically using lipid stains and the multiple small infarcts that often ensue can be seen either in classical histological sections or, more readily, by enzyme or fluorescent techniques. They are probably responsible for many of the small fibrotic areas commonly seen in the myocardia of sufferers from long-standing coronary disease.

HAEMORRHAGE

Haemorrhage often occurs within an atheromatous plaque, usually into the softened, necrotic centre. This 'subintimal haemorrhage' may give rise to a sudden reduction in the blood-carrying capacity of a coronary artery and cause sudden death. The source of the bleeding is somewhat controversial, but the best explanation is that it comes from rupture of small blood vessels in the periphery of a plaque. A normal coronary artery does not have a blood supply to the intima but, in the disorganization frequently associated with the distorted microanatomy of a diseased coronary artery, such vessels may lie within the intima and be eroded by extension of the degenerative process.

Haemorrhages, both fresh and old, can often be demonstrated in histological sections of atheromatous plaques. It is reasonable to presume that such a bleed may be precipitated by some sudden rise in blood pressure from exertion or emotion, though, if a vessel is sufficiently eroded by atheroma, such a precipitation is not strictly necessary for such an event to take place.

The sudden release of blood into an atheromatous lesion can rapidly enlarge it and may raise the cap of the plaque towards the other side of the already stenosed lumen. It may even rupture the plaque: some subintimal haemorrhages may track circumferentially, causing a 'minidissection'. Subintimal haemorrhage as a factor in acute coronary occlusion was investigated many years ago by Patterson (1938), who believed that they played a major part in coronary thrombosis. In the same year, Wartmann demonstrated occlusion by subintimal haemorrhage without rupture of the overlying intima. Though English and Williams (1943) doubted if haemorrhage could compress the lumen against arterial pressure, other authors, including Davies and Pomerance (1975) believe that the haemodynamics within the coronary vessels are such that the pressure varies markedly from place to place, and that there may even be a contributing factor to subintimal haemorrhage by a suction effect in certain conditions. Other authors, such as Drury (1954), consider that the blood within the plaque is not caused by haemorrhage from mural vessels, but from blood percolating from the lumen of the coronary artery at the time of rupture of a plaque. This seems a minority opinion, however, as many haemorrhages can be seen (some older ones containing haemosiderin) within plaques which have a perfectly intact overlying intima.

Whatever the precise origin of the blood, it is clear that subintimal haemorrhage is a potent factor in rapidly reducing the available lumen of a coronary artery – and sometimes precipitating thrombosis by further stretching and damaging the overlying intimal cap.

CORONARY THROMBOSIS

The atheromatous plaque may not undergo these more dramatic changes, but progressive internal necrosis may erode the luminal surface and expose the fibrofatty contents. This loss of normal covering endothelium then forms a nidus for thrombus formation, which may gradually accrete in layers so further reducing the lumen or even occluding it, especially if a combination of lesions causes the plaque to expand at the same time as roughening the surface. Thus mural thrombus may completely block or severely narrow the residual lumen, with all the consequences of reduced blood flow to the distal myocardium.

A narrow lumen is by no means essential to the formation of thrombosis, as it may occur in the abnormally wide, virtually aneurysmal, coronary arteries sometimes seen in aged people. The lumen may be up to a centimetre wide yet be firmly thrombosed, presumably solely because of damage to the intima. Thrombosis often occurs in recanalized vessels, secondary thrombosis taking place after organization and re-establishment of a lumen through the previous block. Multiple coronary thromboses are by no means unusual. Many are post-infarct, the original thrombus causing myocardial necrosis and the resulting stasis in circulation, together with the thrombogenic effect of tissue damage leading to sluggish flow of readily coagulable blood.

It has also been noted that coronary thrombosis may be accompanied by thrombotic lesions elsewhere in the body. For example, a coronary thrombosis may be followed by a pulmonary embolus from thrombosed leg vein – and the converse may also occur in non-fatal pulmonary embolism. The coagulability of the blood, together with circulatory stasis, aided by immobility in bed, are obvious factors.

SITES OF CORONARY STENOSIS AND OCCLUSION

The whole length of the coronary arterial system is not uniformly vulnerable to atheromatous lesions. First, the major trunks are most affected where they lie subepicardially, often in the fatty surface tissue. Once the arteries dip down into the myocardium, these more distal intramuscular branches become much less prone to significant atheroma, especially of the grumous, degenerative type, though intimal thickening may still be seen.

Second, there are sites of predilection in the three major arteries. The most common site of occlusion is in the first 2 cm of the anterior descending branch of the left coronary artery, which is more frequent than in the common trunk. The next most frequent site is in the right coronary artery, but here the thrombosis is more distal than in the left vessel, usually seen as the vessel courses around the right margin of the heart in the atrioventricular groove part-way between aorta and the beginning of the posterior descending branch.

The third most common place is the proximal part of the left circumflex artery, soon after the bifurcation from the common trunk. The latter is then the next most frequent site, in the short segment (sometimes absent) between the aorta and the birfucation into descending and circumflex branches. At autopsy, it is always necessary to transect the proximal part of both coronary arteries right up to the coronary ostia, as occlusion can sometimes be present in the first few millimetres.

MYOCARDIAL INFARCTION

There is a different emphasis laid upon myocardial infarction by the forensic pathologist and by the clinician. To the latter, the clinical signs of chest pain and shock mean an infarct and certainly, a much higher proportion of patients who reach hospital beds do have myocardial infarcts compared with those who are taken straight to the mortuary. Recently the Joint European Society of Cardiology/American College of Cardiology Committee for the Redefinition of Myocardial Infarction produced a consensus document examining the scientific and societal implications of a new definition for myocardial infarction from seven points of view: pathology, biochemistry, electrocardiography, imaging, clinical trials, epidemiology and public policy.

In the pathology of sudden death, overt infarcts are the exception, rather than the rule. The incidence in autopsy material from sudden deaths varies considerably, partly because of the different methods of demonstrating the muscle necrosis, but speaking of obvious naked-eye infarcts, the author (BK) would estimate that, in his material considerably less than a quarter of deaths attributable to coronary atherosclerotic disease have myocardial infarction. In Finnish autopsy material of the author (PS) the 5-year average (1987–1991) of infarcts among deaths due to coronary atherosclerotic disease was 13.5 per cent. The relevance of this observation in relation to the mechanism of sudden cardiac death is discussed later.

Almost all myocardial infarcts are caused by atheromatous lesions and their complications. A few are the result of other types of coronary obstruction, such as polyarteritis, other vasculitides, embolism of various types, ostial occlusion by syphilis, severe aortic stenosis, some congenital anomalies of the coronary arteries or great vessels, dissecting aneurysms at the aortic root, and tumour or sarcoidosis affecting the coronary vessels.

Most infarcts are caused by super-added coronary thrombosis, but even this statement needs further analysis. A proportion of infarcts have no demonstrable thrombus in the supplying vessel, but this proportion can be reduced by a more careful search. There is no doubt, however, that muscle necrosis can follow severe narrowing of the supplying vessel by subintimal haemorrhage, a ruptured plaque or simple severe stenosis from atheroma. In addition, grumous debris from a ruptured plaque can produce embolic occlusions with 'microinfarcts' in the distal myocardium. The fact that some thromboses are post-infarct has already been mentioned.

It is said that the original lumen must be reduced to 20 per cent or less before the ischaemia in the distribution zone is sufficient to cause myocardial necrosis. Most pathologists with considerable experience of sudden death autopsies will, however, have numerous experiences of undoubted infarction in the absence of an 80 per cent stenosis. The embarrassing situation occasionally occurs where an infarct exists with virtually normal coronary arteries.

The contrary is much more common: the finding of complete thrombosis of a major vessel with no sign of infarction. In this case, either an effective collateral circulation provided an alternative blood supply – or the victim died before signs of infarction had time to develop.

There are several types of myocardial infarct recognizable at autopsy:

- A laminar infarct in which the subendocardial region of much – or even all – of the left ventricle is involved, sometimes extending through half or more of the thickness of the wall. This is due to a reduction in perfusion pressure to the inner zones, as all the coronary supply comes from the epicardial surface. Laminar infarcts are the result of generalized stenosis in the major branches of the coronary vessels, but there is usually a second factor, in that a drop in blood pressure or the oxygenation of the blood compromises the already poor supply so that the outer zones of the ventricular wall consume the available oxygen and nutrients, leaving little for the inner zone. This is discussed further under hypertension and aortic stenosis.
- A regional or focal infarct is more common in pure coronary artery disease, and is caused by a localized occlusion or severe stenosis in a coronary artery. These are true myocardial infarcts, as the definition of an infarct requires occlusion of the vascular supply, which strictly excludes some laminar infarcts when perfusion pressure or relative insufficiency is caused by hypertension, or aortic valve disease. The regional infarct is a topographically demarcated zone of muscle necrosis, the size and position depending on the site of vascular occlusion, though any collateral supply may modify these. Almost all infarcts are in the left ventricle. Wartmann and Hellerstein (1948) found that between 6 and 9 per cent involved the right ventricle and that 7 per cent involved the atria, though Cushing's (1942) figure was 17 per cent for atria. Most of these infarcts, however, were overlapping from infarcts in the left ventricle.

The relative immunity of the right ventricle and atria is presumably because of the relatively thin walls, which do not require so much blood, do not have the perfusion gradient of the thick left ventricle and which can more easily obtain oxygen and other constituents from the blood in the lumen of the ventricle. The presence of a conus artery, small branches to foci, such as to the sinus node, and the presence of anastomotic channels between the left circumflex and right coronary arteries must all contribute to the better survival of these areas. The site of a left ventricular infarct does not always correspond strictly to the site of the coronary occlusion or thrombus because of the presence of a collateral circulation.

It was also shown by Wartmann and Souders (1950) that many infarcts involve only certain layers of muscle, which cannot be supplied by a particular vessel. There is obviously no simple explanation for the topography of a myocardial infarct – this is further confirmed by the patchy nature of myocardial damage on microscopic study, as the alternate necrosis and survival of adjacent fibres or even segments of the same fibre cannot be explained solely by coronary perfusion.

The autopsy diagnosis of early myocardial injury and infarction

The autopsy demonstration of an acute lesion in the heart, such as an early myocardial infarct, can have profound medico-legal implications. In a fatal traffic accident, or even rail or air crash, the proof of an acute disabling myocardial lesion in the driver may be vital in the investigation of the event and the apportionment of legal liability. In potentially criminal deaths, the presence of a recent infarct again may be relevant in causation or as a contribution to the death. It is thus important to make a full histological search for evidence of myocardial fibre damage, using all the methods available, including histochemical and fluorescent techniques.

The macroscopic appearances of myocardial infarction are described with a considerable lack of uniformity in most pathology texts, partly because of the varying ages of infarct that the authors depict. The age of an infarct is notoriously difficult to establish in the human, as the onset of clinical symptoms, however dramatically abrupt, are often much later than the onset of the pathological lesion precipitated by a coronary occlusion. In animal experiments, a coronary vessel can be ligated at zero time and serial sacrifices made at different intervals to gain an accurate estimate of the age of the infarct.

In the human, the time of chest pain and shock cannot be used in a similar fashion. When a victim of coronary disease dies say, 8 hours after the onset of acute symptoms, though one might expect an early infarct to be visible histologically or histochemically, not infrequently a demarcated yellow or tigroid area of necrosis is present, which must be several days old. The following appearances are typical of the stages of myocardial infarction, though marked divergences from this time scale are not uncommon:

- For the first 12–18 or even 24 hours, no definite naked-eye changes are visible. The first sign towards the end of this variable period is oedema of the affected area of muscles, which causes pallor as the swollen fibres squeeze the blood from the vessels that lie between them. The normal moist lustre of the cut surface becomes more granular and dull when cut by a sharp knife. Caution must be used with this feature, because if the scissors are used to cut even normal muscle, the crushed edges of the fibres will give a similar dry, matt appearance.
- From about the end of the first day progressively through the second and third, the area becomes better demarcated and turns yellow. With breakdown of the myocytes, streaks of red appear, being both dilated vascular channels and areas of interfibre haemorrhage. This gives a ‘tigroid’ appearance suggestive of tiger stripes across the area, though sometimes the yellow element is virtually uniform or the red streaks may fade after a few days.

  Demarcation becomes more sharply apparent and there may be a red zone in the less damaged muscle around the periphery. The size of the infarct depends on the means with which it is visualized; the naked-eye size is less than the area detectable by classical histology and this in turn is smaller than that demonstrable by enzyme studies, where the more peripheral fibres are sick but potentially recoverable.
- After a few days, progressing through weeks, the infarct becomes softer and more friable, justifying the old name ‘myomalacia cordis’. It is at this stage, from about the second or third day onwards, that ruptures occur into the pericardial sac. Some pathology textbooks are in error in stating that such cardiac rupture occurs in early infarcts.
- From the third week and later, the centre of the infarct becomes gelatinous, the colour fading to a translucent grey that often subsides below the level of the cut surface. This rather mucoid stage may still have old haemorrhage within it, but the stage of healing slowly develops and, during the next month or two, depending upon the size of the infarct, fibrosis replaces the dead muscle to form a scar. Even after this stage, there is often a narrow zone around the young fibrous tissue that shows muscle necrosis, though special staining or enzyme techniques may be needed to demonstrate this.

The laminar infarct goes through the same cycle of changes, but this is often less intense. Eventual fibrosis may be widespread but remains thin, often subendocardial, especially on the left ventricular aspect of the interventricular septum where a wide glistening sheet may obscure the underlying muscle. The apex also may show widespread fibrosis and all muscle may be replaced in this region, sometimes leading to a cardiac aneurysm on the free wall. Infarcts may be transmural, extending from epicardium to endocardium, or they may be confined to the inner zone. It is almost impossible to have an infarcted area confined to the outer subepicardial zone because of the topography of the coronary supply. The papillary muscles are usually involved, being particularly vulnerable to ischaemia as they are at the end of the line of coronary supply. The central part of the muscle may necrose and even rupture. Infarction usually spares the immediate subendocardial zone, the three or four most superficial layers of fibres surviving, even though they may show ischaemic damage. They presumably receive enough oxygen and nutrients from the ventricular blood to survive, though this does not seem to prevent deposition of mural thrombus over the infarcted area.

Microscopical appearances of myocardial injury and infarction

There are a vast number of publications on this subject dealing with morphological changes, classical histological methods, enzyme histochemistry, fluorescent studies, immunohistochemical methods and transmission and scanning electron microscopy. Only a brief summary can be offered here, though some of the methods of detecting very early infarction are detailed in Appendix 1.

MORPHOLOGICAL CHANGES

There is marked variation from case to case, just as in the gross appearances. The same difficulties exist about assessing the time of onset and hence the age of the infarct. This may sometimes have considerable medico-legal importance,



FIGURE 25.1 *Enzyme histochemistry of early myocardial damage. This photomicrograph shows strong succinate dehydrogenase reaction in the myofibres adjacent to the endocardium and moderate decrease of reaction elsewhere suggesting early injury. (Original magnification ×100.)*



FIGURE 25.2 *Fresh myocardial infarction with β-hydroxybutyrate dehydrogenase staining showing positive reaction in the myofibres adjacent to a larger vessel seen above as an empty space. The lower part of the picture shows infarcted myofibres with some lipofuscin but no enzyme reaction. (Original magnification ×160.)*



FIGURE 25.3 *Contraction bands in myocardium. (HE, original magnification ×500.)*

especially when cardiac disease may have caused a traffic or other transportation accident – and is sometimes relevant in criminal circumstances. In animal experiments, changes in myocardial fibres become apparent within 30 seconds of coronary ligation, the first change being a loss of glycogen as the cell shifts from aerobic to anaerobic respiration. This cannot be observed in human material, for obvious reasons. The first observable change is subjective and different pathologists given the same material will offer different opinions on whether or not ischaemic damage is visible. Some of the earliest changes are mimicked by autolysis, especially granularity of the cytoplasm. The infarcted area becomes swollen, so that the interfibre clefts become obliterated, and the overall appearance is pinker and more solid in routine sections. Care must be taken to assess sections of uniform thickness, as material from other laboratories may not conform to the observer's usual quality. Along with swelling, the cytoplasm becomes granular, the 'cloudy swelling' of the old texts.

Early morphological changes seen in light microscopy are unspecific: interstitial oedema, congestion and small haemorrhages. An overstretching of myofibres with a sarcomere length of about 2.51 μm is possible only when the fibre is injured. In experimental infarction in the rat and the dog sarcomere, overstretching has been observed 15 minutes after coronary ligation. Cellular infiltration is variable and neutrophil infiltration is seen in most infarcts during the first few days being replaced by a mononuclear response within a week or so.

Contraction bands, known also as myofibrillar degeneration, and coagulative myocytolysis, are commonly described in connection with different pathological conditions. The change signifies irreversible myocyte injury. Contraction bands are irregular, dense and in haematoxylin and eosin (HE) staining eosinophilic transverse bands alternate with lighter staining granular zones in the myocyte, possibly firstly described by Smith (1904) in the periphery of myocardial infarction. These lesions have been observed in various forms of experimental heart muscle injury and have been also seen, e.g. in association with potassium deficiency, magnesium deficiency, in cases of malignant hyperthermia, in the hearts of drug addicts and in cases of sudden cardiac death.

They may also be seen after blunt trauma to the chest or even cardiopulmonary resuscitation, both where mechanical massage has been applied and especially where cardiac stimulants like noradrenaline have been injected. In fact, catecholamines seem able to cause this fibre disruption, which may also appear during electrocution and other conditions



FIGURE 25.4 *Contraction bands in fresh myocardial infarction. (PTAH, original magnification ×250.)*



FIGURE 25.5 *Zonal lesions in haemorrhagic shock (HE).*

of cardiac stress. In sections stained with haematoxylin and eosin, pale areas in the fibre are common as a result of fibrocytolysis and the sarcolemma is often seen to be deficient at these sites. Although the change signifies fresh and irreversible myocyte injury and is more frequently observed in cardiac deaths, it is not specific to the cardiac death.

Contraction bands are best seen by phosphotungstic acid haematoxylin stain and all myocardial sections should be stained in this way as well as – or even in preference to – haematoxylin and eosin. Phosphotungstic acid haematoxylin stain does not reveal ischaemic damage at an earlier stage, but renders it far more obvious. Large areas can be scanned under low power of the microscope and the danger of missing abnormal areas is far less than with haematoxylin and eosin. The striations become distorted and break up, forming either a general 'sandy' appearance or the striking 'contraction bands' where fragmentation occurs in transverse lines across the fibre. The contractile material aggregates into thicker, darker masses, sometimes like 'Chinese writing', at first within an intact sarcolemma, but later the cell membrane ruptures and the basophilic contents scatter extracellularly.

Zonal lesions occur as a region of supercontraction of myocytes at the intercalated discs. These lesions have been observed both in the dog and in humans after haemorrhagic shock and the changes have been considered ubiquitous in and pathognomonic for hypovolaemic shock. These possibly reversible changes have been observed in experimentally induced shock in animals 15 minutes after the induction. The presence of catecholamines is also considered necessary.



FIGURE 25.6 *Fragmentation of myocardial fibres. (HE, original magnification ×250.)*

Fragmentation of myocardial fibres is, at least to some extent, practically always present in adult hearts and more frequently in the wall of the left ventricle. Although it has generally been associated with post-mortem changes, it has also been shown to be more frequently seen in myocardial samples from sudden cardiac death victims. Early injury possibly increases the brittleness of myocardium, resulting in increased fragmentation of myofibres after the fixation and cutting process. This phenomenon has, however, no value as a positive marker of myocardial injury.

Waviness of fibres was noted by Glogner (1903), who saw corkscrew-shaped myofibres in the heart and skeletal muscle in some cases of beri-beri. Similar patchy deformation of myofibres in a wavelike fashion was seen in association with fatty degeneration of the myocardium and in early and also more advanced human myocardial infarction. Both in cardiac deaths and non-cardiac deaths it can be observed more frequently in the wall of the right ventricle. It has no diagnostic significance as to the cause of death and it signifies only agonal injury.

LATER STAGES

The later stage of infarction follows the 18–24-hour period and, as by now macroscopic changes will be apparent, the histology is merely a confirmatory procedure. Even here, there is great variation in appearances, especially in cellular infiltration. There is a progressive degeneration of the fibres, best seen in longitudinal section. Eosinophila becomes stronger for a time until the internal architecture breaks down. The cellular oedema subsides and interfibre oedema takes over, separating the myofibres, a process that becomes more marked as the latter shrink and fragment.

Loss of nuclei is not an early phenomenon but, by the second to fourth days, the nuclei become hollow, shadowy and eventually ghost-like, though nuclear remnants can sometimes still be seen in completely necrotic infarcts. Cellular infiltration is variable and sometimes does not occur at all, again in contradiction to the established descriptions in most textbooks. In general, however, there is a neutrophil infiltration in most infarcts during the first few days, which subsides gradually and is replaced by a mononuclear response within a week or so. These are mainly macrophages clearing up the debris and fibroblasts coming in to lay down new collagen during repair.

By the end of the first week, disintegration of muscle fibres is well under way, and new capillaries and fibroblasts are appearing, though there are many exceptions to this timetable. In general, infarcts are older than most observers think, so that their age is usually underestimated. By the fourth week, depending upon the total size of the infarct – early fibrosis is evident but still with lacunae of necrotic, unrepaired muscle, which heals unevenly and slowly. From this point on there is a variable population of cells, leucocytes diminishing in favour of fibroblasts, macrophages and new vessels.

It is difficult, if not impossible, to date such an infarct even within weeks, and different parts of the same infarct may show quite different appearances. Only when sufficient time has elapsed for all the lesions to catch up with the end stages of firm fibrosis can one say that probably a minimum of about 3 months has elapsed – though again this is dependent on the size and other more imponderable factors, such as age and other concomitant disease.

HISTOCHEMICAL METHODS

In haematoxylin and eosin (HE) staining, increased cytoplasmic eosinophilia is an early form of cellular injury partially resulting from increased binding of eosin by cytoplasmic proteins. At the pH conventionally used in staining, eosin is negatively charged. The binding may increase because of greater exposure of positively charged reactive sites along polypeptide chains after their denaturation. The loss of cytoplasmic basophilia usually reflecting detachment and scattering of polysomes from rough-surfaced endoplasmic cisternae is considered as another cause for the increased eosinophilia.

The intensity of eosinophilia increases, sometimes uniformly, but often in patches with advancing injury. It is earlier and more distinctly seen in HE-stained cryosections and can be enhanced by placing a green filter in the light path of the microscope. Patchy hyperchromasia can be observed in all kinds of deaths and therefore it is of limited diagnostic value. Care must be taken to exclude the occasional thickened areas made by cutting artefacts, which look pinker because of a greater depth of cytoplasm. These early changes are not usually visible in the first 8–12 hours after the (presumed) onset of infarction.

Acid fuchsin (AF) was suggested to be useful for demonstration of early myocardial infarction in man or in animal experiments, but was found to be inconsistent and misleading.

Haematoxylin/basic fuchsin/picric acid stain (HBFP) was claimed to demonstrate early myocardial ischaemia and to be unaffected by post-mortem autolysis. In experiments with isolated cardiac myocytes in suspension made anoxic by complete oxygen deprivation, basic fuchsin was taken up by contracted or damaged myocytes, which, according to their morphology in suspension, revealed irregular contractions, but neither by undamaged nor necrotic myocytes. However, after the first promising reports, contradictory results started to accumulate and the method has been shown to produce inconsistent results and to be unreliable and non-specific and without value for diagnostic purposes.

FLUORESCENT METHODS

Fluorescent methods have been applied to demonstrate early myocardial infarctions and myocardial degeneration in animal experiments as well as in human heart either by using a fluorescent dye, e.g. acridin orange to stain unfixed cryostat sections or paraffin sections or utilizing the fluorescent properties of eosin in the HE-stained myocardium. Intravenously or intraperitoneally injected tetracycline has also been used in experimental infarction for demonstration of the perfused region in myocardium. Carle (1981) claimed that only hypereosinophilic cells autofluoresced, but Badir and Knight (1987) found that myocardium that had normal eosinophilic staining also fluoresced yellow in ultraviolet light; this has been confirmed by Saukko and Knight (1989).

Acridin orange stained cryosections of intact myocardium show golden brown fluorescence which turns into greenish fluorescence with increasing ischaemia time whereas eosin fluorescence of normal myocardium in paraffin-embedded samples show olive-green fluorescence which turns into yellow in injured tissue. Post-mortem autolysis does not seem to have any significant effect on the fluorescence but the high percentage of wrong positive samples indicates that at least eosin fluorescence is obviously too sensitive injury marker capable of demonstrating agonal ischaemic changes.

A major handicap common to all classical histochemical staining methods is that the basis of these colour reactions is poorly understood. Considering the possible legal implications, it is not reasonable to use such diagnostic methods for medico-legal purposes, when their diagnostic significance, to say the least, is questionable and one does not know for sure what the methods are actually measuring.

ENZYME HISTOCHEMISTRY

After Rutenburg *et al.* (1953) had found large amounts of succinate dehydrogenase in the myocardium of various species using blue tetrazolium as hydrogen acceptor, this method was also applied to autopsy material and the inactivation of histochemically demonstrable succinate dehydrogenase was observed in human myocardial infarction. The enzyme histochemical methods became soon widely applied in animal experiments and also to diagnose early human myocardial infarction in autopsy material. Various oxidative enzymes were demonstrated either by incubating thick myocardial slices in a medium containing a tetrazolium salt with or without exogenous substrate and coenzyme (macromethods) or to stain cryosections observed under the microscope (micromethods). It was assumed that enzyme histochemistry might be, at least, a 'semi-quantitative' indicator of the actual biochemical activity of a given enzyme and, therefore, a scientifically more solid biochemical indicator of myocardial metabolism and injury than the previously discussed traditional histochemical methods. In all, the results between individual authors and laboratories have been extremely variable, suggesting that the situation is not that simple. Hiltunen *et al.* (1985) assessed the enzyme histochemical methods, used by the author (PS) in autopsy material, comparing the enzyme histochemical reaction with the actual biochemical acitivity of the enzymes in a global ischaemia model in an animal experiment. The results pointed out that, although the enzyme histochemical methods have been named after the enzymes, the enzyme histochemical reactivity need not necessarily correlate with the actual biochemical activity of the enzyme at all, suggesting that other factors, such as the presence of auxiliary enzyme systems or other co-factors of the histochemical reaction, may be rate-limiting. This brings about the same dilemma as with the conventional histochemistry: unless the biochemical basis of any given enzyme



FIGURE 25.7 *Bright yellowish eosin fluorescence of damaged myofibres (a) corresponding exactly with eosinophilia as seen in the HE-stained cryosection (b) of a fresh myocardial infarction.*



FIGURE 25.8 *The size of a myocardial injury depends upon the method used to display it. These are four serial sections of a heart from autopsy, stained in different ways. Haematoxylin and eosin stained cryosection (a) does not reveal any damage; the adjacent section (b) is stained for malate dehydrogenase activity, and shows strong and uniform reaction. Section (c) is stained for succinic dehydrogenase and reveals a varying degree of enzyme loss in almost all the section, the section (d) on the right stained for β-hydroxybutyrate dehydrogenase activity reveals slightly larger area of damage. (Original magnification ×100.)*



FIGURE 25.9 *Patchy loss of malate dehydrogenase reaction simulating early injury. In fact, the injury was caused by artificially prolonged agonal period due to respiratory treatment and cardiac pacing. It was equally well visible in HE staining emphasizing the necessity of control staining with conventional methods always when more sensitive methods are used.*

histochemical method is thoroughly understood, it is precarious to use it for medico-legal purposes.

IMMUNOHISTOCHEMICAL METHODS

The advances in immunohistochemistry and good results in clinical pathology as well as the availability of a great number of new antibodies have resulted in numerous publications reporting on potential markers of early myocardial injury in both animal experiments and autopsy material. As it has been shown that ischaemia damages cell membrane, contractile proteins, cytoskeleton and subcellular organelles of the myocardium relatively quickly, the search for better diagnostic methods has been directed to various components of the myofibre, e.g. basement membrane (collagen IV, fibronectin, laminin), cytoskeletal proteins (actin, desmin, alpha- and beta-tubulin), cell-matrix focal adhesion molecules (vinculin, talin), membrane-associated proteins (dystrophin, spectrin), terminal complement complex (C5b-9) and fatty acid binding protein (FABP), among many others. In spite of the plethora of publications, the results have been rather contradictory and/or their practicability difficult to assess due to shortcomings in test material or design.

In spite of better insights into the pathophysiology of myocardial injury, the practical problem as to its diagnostic significance as a cause of death has not changed: whenever myocardial injury has been detected, either macroscopically or by using whatever conventional or more sophisticated methods, **it does not necessarily prove that the injury is the cause of death, unless other causes of death have been excluded**. The rule-of-thumb is that the more sensitive methods are used the greater the probability that agonal period and autolytic changes may be difficult to differentiate from intravital changes.

COMPLICATIONS OF MYOCARDIAL INFARCTION

Ruptured heart

Ruptured heart is the most common cause of a haemopericardium and cardiac tamponade, the rupture always occurring through an infarct. The softened, necrotic muscle gives way from the internal pressure of the ventricular blood during systole, there being no equalizing rise in external pressure. Hypertension will increase the risk, but a more potent factor is a senile, soft myocardium, so that the elderly woman is a common victim of a ruptured heart. This by no means excludes younger men if the infarct is extensive and transmural. The most common area for rupture is the more distal part of the free wall of the left ventricle. The septum occasionally ruptures and the consequent left–right shunt, whilst the patient survives, provides a classical diagnostic sign for the stethoscopes of clinicians.

The rupture does not take place in the early stages of a new infarct, but after a day or two when necrotic softening is well established. The blood usually tracks through tortuous channels between muscle bundles, rather than bursting a direct fistula from ventricle to pericardial sac. The infarcted area may not always be obvious, as the haemorrhagic patch may obscure it, but histologically the ragged tissues and the periphery may be seen to be necrosed.

Haemopericardium is the pathological condition found at autopsy and is not quite synonymous with ‘cardiac tamponade’, which is a clinical state caused by the progressive accumulation of blood within the closed pericardial sac. As the external pressure rises, the heart cannot fully expand in diastole to allow filling from the great veins. As input volume falls, so does stroke output. The venous drainage is dammed back so that congestion and cyanosis of the face and neck occur, until a fatal endpoint is reached.

Mural thrombosis

Mural thrombosis almost inevitably occurs when an infarct is based upon the endocardium of the left ventricle. Though there is usually a thin layer of viable (though sick) cells immediately beneath the endocardium, they do not seem to prevent deposition of platelets and fibrin.

The thrombus is often entwined between the muscular bands lining the distal ventricle, which aids its adherence. When extensive, the thrombus may fill the entire apical area of the ventricle. The layers nearest the endocardium are naturally the oldest, and visible strata (lines of Zahn) are often visible. The youngest layers on the surface are less organized and more friable, so fragments tend to break off and form emboli that enter the arterial circulation, and can cause infarcts in kidney, brain, spleen and even the myocardium itself.

Pericarditis

Pericarditis occurs with full-thickness (transmural) infarcts that form the most common cause of pericarditis in Western communities. The visceral pericardium becomes purple–red as a result of the infarct beneath, with a vascular blush on the surface. Granular fibrin deposit causes the surface to lose its glistening sheen, and strands of fibrin may link the visceral and parietal layers together. When healed, fibrous adhesions may form which can obliterate part or even all of the pericardial sac.

Myocardial fibrosis

Myocardial fibrosis has already been described, healed infarcts being replaced by dense collagen, as new muscle cannot be formed. Large plaques from healed infarcts can be anywhere in the left ventricle, depending on the vessel(s) that were occluded. The septum and the posterior wall are more common sites than the anterolateral wall, though the latter is by no means exempt. Often the fibrotic plaques are multiple or irregular, being scattered throughout the ventricular wall.

Diffuse fibrosis is common in elderly people, even when there is negligible coronary narrowing. This may be in part the result of ventricular hypertrophy in hypertension, which causes a relative ischaemia, but many old hearts with no enlargement (indeed, atrophy) reveal patchy fibrosis, either macroscopically or microscopically. In the latter case, the fibrosis is often perivascular in situation.

Cardiac aneurysms

Cardiac aneurysms occur where a large area of fibrosis replaces a previous transmural infarct, usually on the distal part of the free wall of the left ventricle. During systole, the cavity blood presses outwards onto the unsupported area and gradually herniates it into the pericardial sac. A saccular aneurysm develops and may undergo various changes, including calcification of the wall, adherence to the parietal pericardium, or filling with laminated thrombus. The aneurysm wall is tough and fibrous and, though lacking in elasticity, almost never ruptures – again contradicting some of the dicta of pathology textbooks.



FIGURE 25.10 *An infarct of the lateral wall of the left ventricle of between 5 and 10 hours' duration. It has been rendered visible by staining the heart slice with triphenyltetrazolium chloride, which colours the normal myocardium red by the activity of tissue dehydrogenases. The infarcted area remains unstained. The infarct is virtually transmural, though some subepicardial fibres survive; the papillary muscle is particularly vulnerable, being at the distal end of the coronary supply.*

CAUSE OF DEATH IN CORONARY INSUFFICIENCY

Most sudden deaths from coronary insufficiency do not have myocardial infarction, even when the most sophisticated techniques are employed for its detection. Neither do the majority have a coronary thrombosis, though severe coronary stenosis is by definition present.

The rare case of myocardial infarction with only moderate or even minimal coronary atheroma has to be relegated to the realms of mystery in the present state of knowledge, unless some embolic cause can be found. Some pathologists invoke 'spasm' of the coronary arteries when the vessels show minimal atheromatous stenosis, but this is a hazardous diagnosis for a pathologist to make. Though spasm is certainly seen by clinicians when performing cardiac catheterizations or cardiac operations, it can never be a morphological diagnosis at autopsy, for obvious reasons.

In most sudden 'coronary' deaths, the usual autopsy finding is of severe, long-standing stenosis sometimes with foci of complete occlusion from a ruptured plaque or a subintimal haemorrhage. There may often be partial thrombosis, in that a plaque or narrow segment may have mural thrombus that further narrows the lumen, though does not totally occlude it.

There is macroscopic and microscopic evidence of myocardial fibrosis in many of these cases. This may either be a large plaque of scar tissue at the site of a previous focal infarct or more diffuse fibrosis. There may be fibrosis subendocardially and in the papillary muscles. In many of these sudden deaths there is no naked-eye or even microscopic evidence of any new lesion in the coronary system or myocardium, so why do they die?

Death must be ascribed to a rhythmical defect, rather than loss of mechanical pumping power. Myocardium and especially the pacemaking and conducting system, is vulnerable to ischaemia and hypoxia. Disturbances of rhythm, from ectopic beats to atrial fibrillation through to ventricular fibrillation and cardiac arrest, may occur, as well as heart block and the many other clinical manifestations of ischaemic heart disease from whatever cause. In addition, many victims are hypertensive and left ventricular hypertrophy exacerbates their relative coronary insufficiency. Anyone with a heart weighing more than 450 g is a candidate for sudden death, with or without coronary artery stenosis. The mechanism of this sudden type of death, where there is no large infarct, seems to be a state of electrical instability from chronic hypoxia, so that sudden stresses (such as exercise or emotion) can suddenly cause the arrhythmias mentioned above, though it must be said that death can occur without any of these factors while the victim is asleep or at rest. It is known that the myocardium is sensitive to catecholamines, this being a physiological response to intrinsic adrenergic hormones. Excess catecholamines given parenterally can cause arrhythmias and even contraction-band damage to the myofibrils. Certain other drugs, such as organic solvents, can sensitize the myocardium to even physiological amounts of noradrenaline, leading to ventricular fibrillation and sudden death.

Those with fibrosis in the myocardium may have the additional risk of interruption of the conducting system, which may give some degree of heart block or defect in the spread of the contraction impulse, rendering them more prone to arrhythmias and arrest. This is especially so where a large fibrotic plaque occupies the interventricular septum, as here the left bundle branch penetrates to supply the apical region and may be strangled by dense fibrosis.

Where there is a recent coronary thrombosis, the absence of an infarct may mean that insufficient time has elapsed for it to become apparent, but of course the pumping efficiency will be compromised and the risks of electrical disturbance will already be operating, so that all the problems listed above exist. The other reason for lack of an infarct is an adequate collateral circulation but, even though necrosis is avoided, a new coronary occlusion can only further worsen the ischaemic and hypoxic state of the myocardium, with all the potential consequences of electrical instability.

If there is an infarct, then again all the above dangers exist, but there is the added liability of a loss of mechanical pumping function, which, with a large infarct, may be a substantial proportion of the whole cardiac output, leading to overt low-output failure during which sudden death can supervene at any time. In addition, the risks of sequelae of myocardial infarction, such as rupture and embolism, are ever present.



FIGURE 25.11 *Extensive myocardial fibrosis occupying the interventricular septum and apex of the heart with severe occlusive disease of the anterior descending branch of the left coronary artery. Near the apex all the muscle has been replaced by scar tissue. This type of lesion is particularly prone to cause sudden death, as well as clinically apparent dysrhythmias, as the septal fibrosis interrupts the left bundle branch of the cardiac conducting system.*

The role of the conducting system in sudden cardiac deaths is one which is attracting increasing interest, especially as new histological and immunohistochemical techniques are becoming available. A revised sampling technique, described by Song *et al.* (1997), uses longitudinal sectioning, reduces the workload and allows observation of continuity between different components of the cardiac conduction tissue. It demonstrates the sino-atrial (SA) node, the atrio-ventricular (AV) node and the distal part of the His bundle and the bundle branches of the cardiac conduction system in 4–5 blocks. However, although a significant number of abnormalities can be recognized, it is usually difficult or impossible to relate morphology to function. The fact that an AV or SA node, or the bundle of His or its branches shows fibrosis or some other lesion, does not necessarily mean that this played any part in the death. It has been shown that the conducting system is remodelled with advancing age – and many deaths from obvious extracardiac causes reveal lesions in the conducting system when studied at autopsy. Nevertheless, new knowledge now being accumulated about the conducting system may become useful in investigated sudden cardiac deaths, as it is obvious that a high proportion of these fatalities, which have no recent acute lesion demonstrable in the coronary arteries or myocardium, are due to arrhythmias and functional arrest, in which abnormalities of the propagation of the pacing impulse may be important. James (1996) has suggested that apoptosis, the programmed cell death, might be a logical explanation and responsible for histological abnormalities of the cardiac conduction system in sudden deaths due to progressive development of complete heart block and various arrhythmias.

HYPERTENSIVE HEART DISEASE

Hypertension may kill in a number of ways, such as by renal failure, ruptured aneurysm or cerebral haemorrhage, but here we are concerned with primary heart failure, a quite common cause of death. During life, the clinical syndrome of 'cardiac asthma' or 'paraoxysmal nocturnal dyspnoea' is caused by pulmonary oedema from hypertensive left ventricular failure. The same oedema is a marked feature of the autopsy on fatal hypertensive heart disease.

Because there is an aetiological connection between hypertension and coronary atheroma, the two conditions are often present together in a victim of sudden death, making it difficult to separate the myocardial consequences of each component. Sufficient 'pure' deaths from hypertensive heart disease are available where there is no concurrent coronary disease, however, to establish the effect of the former on the myocardium. When the left ventricle has to work against a higher pressure in the systemic arteries, the muscle fibres hypertrophy. They cannot increase in number, but they increase in length and thickness, with irregularity and enlargement of nuclei. This fibre enlargement leads to increase in the mass of the left ventricle, the well-known 'concentric hypertrophy' of hypertension.

If 360–380 g is taken as the upper limit of heart weight for an average size man, then hypertensive disease may produce hearts of 500–700 g. Hearts larger than this usually have some other cause, such as valvular disease or a cardiomyopathy. Though it is sometimes denied that hypertension can cause sudden death, most forensic pathologists would strongly disagree, all having performed numerous autopsies where no other reasonable explanation existed. The usual picture is of marked pulmonary oedema fluid running freely from the cut surfaces of the lungs because of a terminal failure of the left ventricle slightly prior to right ventricular arrest. This causes a rapid rise in pulmonary artery pressure and consequent transudation across the pulmonary alveolar membranes.

There may not always be evidence of hypertension in the often sparse history available at sudden death, but the presence of concentric hypertrophy in the absence of valve disease or a cardiomyopathy – together with characteristic changes in other vessels and organs, such as the kidney – is strong evidence of raised blood pressure. Sometimes the overall weight of the heart may be normal, yet there is relative left ventricular thickening; this again suggests hypertension. In the hearts of aged people, the usual atrophy – with tortuous surface vessels – may be concealed by a left ventricular hypertrophy, keeping the heart at normal weight.



FIGURE 25.12 *Concentric hypertrophy of the left ventricle in a person with cardiomegaly from hypertension. The slice has been stained with triphenyltetrazolium chloride to reveal dehydrogenase activity; some mottled areas, especially in the septum, show pallor from reduced enzyme activity as a result of relative ischaemia of the increased muscle mass.*

The existence of hypertensive heart disease as a specific entity was strengthened by some investigations published by the author (BK) in 1973, in which it was shown that gross enzyme deficiencies exist in the inner part of the wall of the hypertrophied left ventricle. This lesion is not specific to hypertension, but is seen whenever the left ventricle is enlarged, notably in aortic valve disease. In severe instances, the defect in dehydrogenase activity extends from endocardium almost to the epicardium, there being only a narrow zone of normal activity. In some ways this defect is similar to the 'laminar infarct' of coronary artery disease.

In pure hypertension and aortic valve disease, the cause is a relative ischaemia of the inner zone of the ventricular wall caused by insufficiency of coronary blood supply compared with the demands of the thickened ventricular mass. The reason for the laminar distribution is the anatomy of the coronary supply, graphically described by Farrer-Brown (1968, 1977). The various levels or strata of the ventricular wall have different arterial patterns. The subendocardial zone is supplied by arteries with many branching terminations that provide a profuse and concentrated blood supply. A second set of vessels passes straight through the ventricular wall without division – all the coronary supply coming, of course, from the epicardial surface. This set serves the papillary muscles and trabeculae carnae, while a third group tends to run circumferentially parallel and below the epicardium, giving branches both outwards and inwards.

Farrer-Brown found that the termination of these vessels were of two types, as they divided into arterioles and then capillaries. The direction of the tree-like branching in the subendocardial zone continued in the general line of the main artery. The area of myocardium supplied by these branches was small. This was in contrast to the pattern in the mid-zone of the wall, where the branches turned at an angle to the main artery and then divided to supply a much wider area of myocardium that was supplied by the terminal branch in the subendocardial zone. These anatomical differences suggest that the vessels in the mid-zone each have to supply a larger volume of muscle than in the other layers. This might well explain the greater vulnerability of this central zone to hypoxic changes, as indicated by reduced enzyme activity and the occurrence of laminar necrosis. In actual practice, the inner zone also suffers, apart from the immediate subendocardial layers, but the superficial subepicardial zone is almost always spared. The rationale of damage to the myocardium in hypertensive heart disease, as in aortic stenosis, would appear to be a relative coronary insufficiency. In pure coronary artery disease, part of a normal-sized myocardial mass is rendered ischaemic by localized reduction of blood flow by a coronary stenosis or occlusion, the resulting necrosis being distributed in a focal pattern according to the location of the block.

In hypertensive heart disease, normal coronary arteries attempt to supply a much larger muscle mass, so that there is the same imbalance between supply and demand. As there is no focal blockage, however, the resulting lesion is diffuse and the areas that suffer most are those in the mid- and inner zones, probably because of the microanatomy of the vessels described above. The same type of lesion may be seen in any severe sustained hypotensive episode of extracardiac cause, though the early onset of death in many of these will preclude the development of morphological evidence of laminar myocardial damage.

SUDDEN DEATH IN AORTIC VALVE DISEASE

A similar situation exists with aortic valve disease in which stenosis rather than incompetence can lead to sudden death. Most of the lesions are primarily degenerative, the commonest being 'idiopathic calcific aortic stenosis', most often seen in elderly men. Aortic stenosis of rheumatic origin always affects the mitral valve before the aortic, so a solitary aortic lesion cannot be ascribed to rheumatism and is therefore of the primary degenerative type. Rheumatic valve disease is becoming rare, both with the decline in rheumatic fever and the frequency with which valve lesions are treated surgically at an earlier stage, before marked ventricular hypertrophy and its myocardial lesions are evident.



FIGURE 25.13 *Calcific aortic stenosis, a common cause of sudden unexpected death especially in older men. Though the stenosed valves are often biscuspid, the stenosis often deforms normal valves, as in this illustration. Marked left ventricular hypertrophy usually ensues, the large muscle mass becoming ischaemic, especially in the inner layers.*

In the common calcific disease, the valve is thickened and rigid, with fusion of the commissures in most cases. There may be large, irregular excrescences on the cusps and in the sinuses behind. At a later stage, the whole valve may be an almost unrecognizable, chalky mass, with a lumen barely wide enough to admit a pencil. This type of valve may have been biscuspid from birth, a condition that undoubtedly encourages calcific degeneration. Many stenotic and apparently bicuspid valves are not truly bicuspid, however, but appear so because the degenerative process has destroyed or obliterated one of the commissures between the cusps. This may often be demonstrated by the fact that a trace of the commissure may still be seen, or by the fact that the two surviving cusps are not equal in size, the commissures being placed at 120° rather than 180°.

A tight aortic valve, from whatever cause, obstructs the outflow tract of the left ventricle and causes the muscle to hypertrophy in order to eject the same stroke volume through a narrower orifice. In addition, if there is associated regurgitation, further extra work has to be performed to attempt to throw out the refluxed blood.

The effect of a severe aortic stenosis in relation to sudden death is to enlarge the left ventricle to sizes even greater than those seen in hypertension. Some of the biggest hearts (excepting some cardiomyopathies) are seen in aortic valve disease, going up to 800 g or – exceptionally – 1000 g.

Another effect of a tight valve is to lower the perfusion pressure in the coronary arteries, which is made worse if there is also an element of regurgitation. It is the diastolic pressure in the proximal aorta that feeds the coronary supply, as during systole the contraction of the heart prevents flow in the intramural arteries. A less common effect may be the distortion of the coronary ostia by calcific masses in the sinuses of Valsalva and the wall of the root of the aorta, which can partly block the entry into the coronary vessels. The combination of a large myocardial mass and decreased coronary flow is often made worse by concomitant coronary atherosclerosis, so the propensity of victims of aortic valve disease to drop dead is considerable. Elderly men are the most frequent victims. Lesions of other heart valves seldom cause sudden death as an isolated cause, though the more chronic cardiac dysfunction – mainly congestive cardiac failure – caused by them may end life rather abruptly on occasions. Rheumatic mitral stenosis is one such lesion, but perhaps a more direct mitral cause of sudden death is the 'floppy' valve usually seen in old age.

SUDDEN DEATH FROM THE CARDIOMYOPATHIES

There is a heterogenous group of diseases of myocardium associated with cardiac dysfunction known as the 'cardiomyopathies', which, though of mixed and often uncertain aetiology, have sufficient in common pathologically to merit a special identity. As they account for the second largest number of sudden deaths after coronary artery disease, i.e. about 10–15 per cent of all sudden deaths of cardiac origin, they are briefly described here, though specialized texts and papers on cardiac pathology should be consulted for details. The outstanding feature is a large heart in the absence of hypertension or valve lesions. The victims are usually young adults, partly because in older groups in which there is atherosclerotic coronary disease and also hypertension, these overlay the cardiomyopathy and make the diagnosis difficult or impossible. The only exception is if there is definite histological evidence or if the heart weight is excessive (over 700 g) in the absence of a valve defect. Cardiomyopathies are the most common cause of heart failure and are an important cause of death in children and adults. According to the Report of the 1995 World Health Organization/International Society and Federation of Cardiology Task Force on the Definition and Classification of Cardiomyopathies, they are classified into the following main types: dilated, hypertrophic, restrictive and arrhythmogenic right ventricular cardiomyopathy.

Dilated cardiomyopathy (DCM) is the most common cause of congestive heart failure. The annual incidence varies, depending on the diagnostic criteria, from two to eight cases per 100 000. Around 30–40 per cent of them are familial (FDCM), but it may also be idiopathic, viral, immune or toxic, e.g. alcoholic. Idiopathic dilated cardiomyopathy (IDCM) is characterized by dilated ventricular chamber and reduced contractility without coronary, valvular or pericardial disease. Histology is non-specific; however, viral genome has been identified in 10–34 per cent of patients with dilated cardiomyopathy.



FIGURE 25.14 *Myofibre disarray in hypertrophic cardiomyopathy.*

Hypertrophic (obstructive) cardiomyopathy was first described in medicolegal autopsy material by a London forensic pathologist, Donald Teare, in 1958. Although he noted and described asymmetrical hypertrophy of the interventricular septum, so that a bulging pad of myocardium partly obstructed the left ventricular outflow tract, this cardiomyopathy is predominantly (75 per cent) a non-obstructive disease and, hence, hypertrophic cardiomyopathy (HCM) is now the preferred name. It is a primary sarcomere disorder characterized by left and/or right ventricular hypertrophy and, in most cases, inherited as a predominantly autosomal disease. It is caused by mutations of any of the genes encoding the proteins of the cardiac sarcomere.

Between 20 and 30 per cent are familial, and the condition may occur at any age from infancy to senility, though the majority of deaths occur in early middle age. The weight of the heart may range from a high normal at 400 g, to 800 g or even a kilogram. More striking than the total weight is the left ventricular preponderance, which is often maximum in the proximal septum, as described above.

Histologically the myocardium shows irregular-sized, large fibres with nuclear pleomorphism. Though once thought to be a rhabdomyoma or a hamartoma, or aberrant adrenergic tissue, the septal bulge usually shows a bizarre pattern of fibres, with loss of the orderly strata and replacement by a criss-crossing, confused architecture of muscle bundles. Interstitial fibrosis is common, and – though there may be an increase in interstitial cellularity – inflammatory infiltrate is not seen, as it would be in an active myocarditis.

Restrictive cardiomyopathy is, according to the WHO report, 'characterized by restrictive filling and reduced diastolic volume of either or both ventricles with normal or near-normal systolic function and wall thickness. Increased interstitial fibrosis may be present'. It may be idiopathic or associated with other diseases such as cardiac amyloidosis, cardiac haemochromatosis or endocardial fibroelastosis with or without hypereosinophilia.

Arrhythmogenic right ventricular cardiomyopathy (ARVC) is a primary myocardial disorder characterized by progressive fibrofatty degeneration of right ventricular myocardium, arrhythmias and risk of sudden death. In addition to familial autosomal-dominant disease with variable penetrance and polymorphic phenotype, two autosomal-recessive forms of ARVC are known.

The WHO classification includes further two groups of cardiomyopathies:

- specific cardiomyopathies that are associated with specific cardiac or systemic (ischaemic, valvular, hypertensive, inflammatory, metabolic, general systemic e.g. connective tissue or neuromuscular disorders) and
- unclassified cardiomyopathies, which do not fit readily in any group, e.g. fibroelastosis or isolated non-compaction of the ventricular myocardium (INVM), a rare disorder characterized by excessively prominent trabecular meshwork, ventricular arrhythmia and systemic embolism.

Myocarditis

Many infective diseases produce an acute myocarditis, which may be the immediate cause of death. A prime example is diphtheria, but this has virtually no forensic relevance. More important is 'isolated myocarditis', where the condition is primary and usually of unknown aetiology. It was formerly [and some recent results from an ongoing study by the author (PS) suggest, that it still is] a much-used and overused autopsy diagnosis, especially where no gross lesions could be found. Known by a variety of names, such as 'Fiedler's' or 'Saphir's' myocarditis, its incidence was said to be appreciable in victims of sudden death – and it was incriminated as the cause of accidents on the road and in the air that had been attributed to driver or pilot incapacity. In forensic pathology some 20–30 years ago, it became a 'fashionable' diagnosis on rather equivocal histological criteria. It was then found that many victims of trauma where death was rapid and where cardiac incapacity could not possibly be a causative factor in the accident, also had foci of mononuclear cells in the myocardium.



FIGURE 25.15 *Severe diffuse lymphocytic myocarditis with destruction of myocytes. (HE, original magnification ×10.)*

Stevens and Ground (1970), after finding six cases of myocarditis in 263 air pilots, when none of them could have been affected by a cardiac event, looked at a considerable number of other accident victims in circumstances in which disease was obviously unrelated to the trauma. They found about 5 per cent of young men had lesions otherwise histologically acceptable as 'myocarditis' and concluded that it was an unsafe diagnosis to use for the cause of death. Their histological minimum criteria for acceptance was one focus of 100 or more cells or many foci of half that size. Groups of lymphocytes, especially subepicardial of 40 or fewer cells, were disregarded.

In Australia, Tongue *et al.* (1972, 1977) did similar studies, but used whole transverse sections of ventricles at up to 18 levels in each heart. Their results showed that the more extensive the search, the greater the number of foci discovered in deaths that had no circumstantial relation to a sudden cardiac death. Using 18 full sections, they found that 90 per cent of the accident victims had 'myocarditis' lesions and suggested that, if the search was extensive enough, it could probably be brought up to 100 per cent.

The Dallas Classification System was proposed by eight cardiac pathologists in an attempt to provide the practicing pathologists with easily applicable and uniform criteria for the diagnosis of myocarditis in endomyocardial biopsies (Aretz *et al.* 1987). By this definition, the diagnosis of myocarditis can be made only if myocyte necrosis or degeneration or both are associated with an inflammatory infiltrate adjacent to the degenerating or necrotic myocytes. A semi-quantitation of the amount of inflammatory infiltrate was suggested as mild, moderate, or severe and its distribution characterized as focal, confluent, or diffuse. The composition of inflammatory infiltrate, i.e. the presence of lymphocytes, neutrophils, eosinophils or giant cells was suggested for differential diagnosis of the aetiology. According to Feldman and McNamara (2000) the Dallas criteria probably underestimate the true incidence of myocarditis.

Among the great variety of infectious agents, viruses have been considered as important cause of myocarditis. The molecular biological techniques such as polymerase chain reaction (PCR) and *in situ* hybridization have provided new diagnostic possibilities and viral genome has been detected both in myocardial biopsies as well as in autopsy material. However, the detection rate and the viruses identified have varied markedly according to the study. In addition, drugs may cause myocarditis, either through direct toxic or immune-mediated mechanism.

Probably, the position now to be accepted is that unless multiple, florid foci are found, with myofibril necrosis seen, using special stains if necessary, bland mononuclear foci that are purely interstitial and not involving muscle fibres must be disregarded. The presence of myofibre necrosis, however localized, would appear the most important confirmatory criterion. Where stenotic coronary artery disease exists, it can be difficult or impossible to differentiate the resulting cellularity, fibrosis and fibre necrosis from that of a myocarditis.

A disease process that may well have been underestimated in the pathology of sudden death is cardiac sarcoidosis. Unless routine histology is carried out on every sudden death, this diagnosis will be missed (Fleming 1988) as will a considerable number of myocardial amyloidoses, which need special stains.

DEATH IN OLD AGE – THE SENILE MYOCARDIUM

In many autopsies on old persons, no specific lesions can be discovered that provide a clear cause of death. In the increasingly aged population of the developed nations, this problem becomes a more frequent task for the pathologist. The history of the mode of death then becomes particularly important, as it may give some clue as to which area of the indeterminate lesions should be given priority in deciding on a cause of death. For instance, if there is moderate coronary artery disease, then if the person died with sudden breathlessness or chest pain, rather than slowly fading away, more credence would be given to the coronary lesions. Many old people have good, patent coronary arteries, however, even if the walls may be calcified – if they did not have such good vessels, they probably would not have lived to 88 or 95 years, anyway.

Where nothing other than general senile atrophy of most organs is found and the history is unhelpful as to a specific mode of death, as long as the pathologist can exclude any unnatural cause, then it is quite legitimate to ascribe the death to ‘myocardial degeneration due to senility’. The WHO’s ICD-10 (International Statistical Classification of Diseases and Related Health Problems, Tenth Revision, Geneva 1992) provides a code for such a disease even though many cardiac pathologists seem reluctant to agree to its existence, wishing always to find some more specific disease process. In the authors’ view, senile myocardial degeneration is quite acceptable, given exclusion of other causes. Senile hearts are usually small, but hypertension may have enlarged the ventricles long ago and the residual effect of this may be to sustain the heart at a normal weight. More important is the appearance of the heart, which is brown on the surface and in the muscle and is flabby and soft. The thumb can be pushed into such muscle at autopsy without difficulty. The weight may be down to 300 g or even 250 g, if no previous hypertrophy has existed. A good indication of cardiac atrophy is the presence of tortuous coronary vessels on the epicardial surface, especially the anterior descending branches. These may meander markedly, as the myocardium has shrunk, the apex has contracted nearer the base and so the vessels have to corrugate to fit into the diminished space.

Microscopically, the myocardial fibres are uneven in size, there may be a fine, diffuse fibrosis, which is not ischaemic in origin and the nuclei of the myocytes have prominent clumps of lipofuscin pigment at their poles. Unfortunately, none of these features is diagnostic of the cause of death, as other old persons dying of quite unrelated causes, such as trauma, might have equally poor heart muscle.

The justification for considering that senile myocardial degeneration is a valid cause of death comes from the species life span of different animals. Even without lethal specific disease, each species has a fairly uniform life span, the human being some 70–90 years. No one lives to 150 years, so there must be some limiting factor; as cardiac function is the most immediate arbiter of survival, it seems reasonable to indict heart contractibility as the primary factor. All tissues age, but senility of the spleen or thumbs does not have the immediacy for life support possessed by the myocardium.

SUDDEN DEATH FROM RUPTURE OF AN ANEURYSM

The most frequent extracardiac cause for sudden death arising in the cardiovascular system is a rupture of an aneurysm, almost always of the aorta or a cerebral vessel. Aortic aneurysms are of three types, all capable of catastrophic rupture.

The atheromatous aneurysm

The atheromatous aneurysm is the most common and is seen mainly in the abdominal segment of the aorta. Though atherosclerosis affects the whole length of the aorta, it is usually worse below the diaphragm, probably because of the haemodynamic effects of the larger branches that come off in this segment. Turbulence and 'Venturi' effects are known to localize the development of fatty streaks and atheromatous plaques, as they are seen first around the ostia of the intercostal vessels and become particularly severe at the major bifurcation into common iliac arteries. Though aneurysms can develop at any point in the aorta, most are below the diaphragm. Excepting dissecting aneurysms, however, any aneurysm in the thoracic segment is still more likely to be atheromatous than syphilitic, even though syphilis is virtually confined to the aortic arch. Most atheromatous aneurysms are fusiform or saccular, the bulge being either symmetrical about the axis of the vessel or more commonly bulging out more on one side than the other. Progressive destruction of the media by the fibrolipid degenerative processes of atherosclerosis leads to weakening of the aortic wall. Bulging caused by the continuous internal blood pressure begins, aided by the hypertensive tendencies of later life. The damage or complete destruction of the intima leads to platelet and fibrin deposition, so that mural thrombosis is laid down in the expanding aneurysm. This may partly or wholly fill the sac, being many centimetres thick in some instances, with well-marked stratification called the 'lines of Zahn'. The wall of the aneurysm may contain calcific fragments similar to the adjacent artery wall.

Most aneurysms remain intact throughout life and are found as incidental findings at autopsy. Naturally the incidence of ruptured aneurysms is greater in medico-legal autopsies by reason of the selective population of sudden deaths. When rupture occurs, the weakest point of the wall is penetrated by the contained blood and this usually leaks out into the retroperitoneal tissues, rather than free bleeding into the peritoneal cavity. The blood tracks behind the root of the mesentery and around the kidney. A large perirenal haematoma may form but, more often, the obvious site of bleeding is in the centre of the back of the abdomen. The diagnosis is usually quite obvious as soon as the autopsy begins for, as soon as the abdomen is opened and the intestine moved aside, a dark red mound may be seen projecting forwards over the lumbar spine, bulging at the root of the mesentery.

The development of a successful technique for the repair of many such arterial defects has reduced the death rate, though there is a substantial perioperative mortality, often because the patient is virtually moribund when the operation begins, or because gross calcification and degeneration of the remaining aortic wall makes it technically impracticable.

The dissecting aneurysm

Rupture of a dissecting aneurysm of the aorta is much less common than the atheromatous variety and seems to have decreased even more during the past decade. It is still by no means an uncommon cause of sudden death, however, and is the second most frequent cause of a haemopericardium and cardiac tamponade. Whereas atheromatous aneurysms are usually in the abdomen, the dissecting aneurysm can span the whole length of the vessel from iliac artery to aortic valve, though the main effects are usually manifest in the thoracic segment.

The basic lesion is a degeneration of the aortic media, the so-called 'medionecrosis'. The thick elastic media becomes degenerate and cystic in the central layers, producing a vessel wall like a sandwich with a soft cleavage plane in the middle. This defect is of unknown aetiology and affects both the elastic and muscular elements of the media. It is relatively common over the age of 50, especially in men. Many aortas seen at autopsy have this degeneration, but no aneurysms, as they never develop because the blood fails to enter the potential cleavage space from the lumen of the aorta.

In most cases where a dissecting aneurysm has caused death, the blood has broken through from the lumen through a tear in an atheromatous plaque, which is a quite separate disease process existing in parallel with the medionecrosis. When blood enters the medial cleft under high arterial pressure, the two layers of the media are split apart and the dissection may rapidly travel both upwards and downwards in the aortic wall. The upper component may split its way around the arch and beyond the attachment of the pericardium. Here, just above the aortic ring, the dissecting haemorrhage often bursts through the remaining outer media and adventitia into the pericardial sac. This causes a massive haemopericardium and the cardiac tamponade described earlier in relation to ruptured myocardial infarct. The distal extension may travel down to the iliac and even femoral arteries, sheathing them in blood. Rarely, in a patient who survives a dissection, the secondary lumen formed in the cleavage plane may rupture back into the main aortic lumen, thus forming a 'double-barrelled' aorta, a curiosity occasionally found at autopsy. Death usually occurs from cardiac tamponade, but some dissections do not burst into the pericardium. Here death is by a less obvious mechanism, which may be partly the sudden narrowing of the aortic lumen and pressure on the coronary ostia and roots of the coronary arteries. In persons under 50 years of age, there is a much less common alternative cause of medionecrosis, known as Erdheim's degeneration. This is sometimes called 'mucoid medial degeneration' and is associated with Marfan's syndrome, an inherited condition characterized by arachnodactyly and optic, aural and bony lesions.

The syphilitic aneurysm

Syphilitic aneurysms are now uncommon, because of the relative rarity of tertiary lesions as treatment is available for the



FIGURE 25.16 *Sudden unexpected death caused by a myxoma of the left atrium. The ball-shaped mucoid tumour impacted in the mitral valve during a postural change. No other cause of death was discernible.*

earlier stages of the disease. In some areas of the world, however, tertiary syphilis is not the rarity it has become in Europe and America.

The syphilitic aneurysm of the aorta is almost always in the thoracic segment and usually in the arch. Syphilitic aortitis, which precedes an aneurysm, may be recognized in the lining of the thoracic and abdominal aorta by its irregular corrugated pattern, though admixture with atheroma can obscure the classical appearances. There tend to be sinuous linear folds, like coarse wrinkles, which have been likened to the bark of an oak tree. If the aorta dissected free of adherent connective tissue is held up to a strong light, 'Gough's test' may be applied, in which translucent windows can be seen in the media. When confluent, these weak patches allow the internal blood pressure to blow out an aneurysm and the syphilitic bulge can be the largest of all, sometimes almost filling the upper part of the chest. The wall is thin and fragile, and there may be several separate bulges from overlapping aneurysms.

Pressure may erode bronchi, oesophagus, pulmonary vessels, lung and even the thoracic cage. The latter may allow the aneurysm to become subcutaneous and, in former years, the external bursting of a pulsating chest tumour must have been a dramatic event. The usual mode of rupture is into the pleural cavity or into the oesophagus or bronchus, giving rise to a sudden, massive haematemesis or haemoptysis. Histologically, it may be impossible to confirm syphilitic aortitis, as the reactive phase of the disease may have been long burnt out, but the gross pathological appearances are diagnostic in themselves.

Fatal aneurysms of other vessels

Fatal aneurysms of other vessels are rare, apart from the cerebral arteries. Atheromatous bulges can occur on the iliac and femoral vessels, and sometimes in the mesenteric arteries. Polyarteritis nodosa can produce mini-aneurysms from the inflammatory process eroding the wall, but death is not caused by the direct effects of rupture, but by vascular problems in the coronary, renal and other arteries. Infective mycotic aneurysms are rare in civilian practice, as are traumatic arteriovenous fistulae, but are not uncommon in war casualties.

Sudden death from ruptured cerebral aneurysm

The relationship of head and neck injury to subarachnoid haemorrhage is discussed in Chapter 5, but here we are concerned solely with spontaneous rupture of an aneurysm of the circle of Willis at the base of the brain. This is one of the most common causes of death in young to middle-aged adults, if coronary disease is excluded. In women, who are relatively immune from coronary occlusion up to the fifth decade of life, ruptured berry aneurysm is proportionately much more common than in men. It is a useful rule-of-thumb, when presented with the sudden death of a woman of child-bearing age, to consider a complication of pregnancy, self-poisoning, pulmonary embolism and subarachnoid haemorrhage as the first choices.

Subarachnoid bleeding can cause virtually instantaneous death, even though the mechanism is obscure. Numerous cases have been described where a previously fit person was seen to collapse and was apparently already dead when attended by onlookers. There must be an element of cardiac arrest in these examples, caused by the sudden bathing of the brainstem in blood from a jet of arterial blood impinging on the base of the brain. As with coronary disease, arterial spasm has been invoked as a cause of the sudden death in ruptured berry aneurysm, without any proof. Most cases of subarachnoid haemorrhage have a much longer course, with clinical symptoms and signs allowing either surgical intervention or, often, spontaneous resolution.

We are by definition here, however, concerned with sudden or rapid fatalities. In the usual coroner's case, the victim is either found dead with no available history, or has died rapidly and inexplicably, or has expired after suggestive symptoms like severe headache and rapid coma. Many die after physical or emotional exertion, especially sexual intercourse or strenuous sporting activity. Those that occur during or soon after some assault or altercation are dealt with in the chapter on head injuries (Chapter 5), and can pose a major forensic problem concerning causation.

At autopsy, the diagnosis of subarachnoid haemorrhage is self-evident. As the usual point of bleeding is in the circle of Willis, the most dense haemorrhage will be over the base of the brain, especially in the basal cisterns. The blood usually spreads laterally and may cover the whole surface of the cerebral hemispheres, the hindbrain and down into the spinal canal. This will be bright red in a fresh bleed; if survival lasts a week or so, a brownish tinge will appear as the haemoglobin undergoes changes. Haemosiderin can be detected by Perl's stain after about 3 days.



FIGURE 25.17 *A dense basal subarachnoid haemorrhage that caused rapid death. The blood clot filling the basal cisterns conceals a ruptured berry aneurysm of the circle of Willis; at autopsy, this must be removed under a stream of water, using careful blunt dissection to avoid further damage to the vessels.*

The detection of the source of the haemorrhage is sometimes difficult. An aneurysm is present in about 85 per cent of spontaneous subarachnoid haemorrhages, but the remainder reveal no aneurysm, even after an exhaustive search. This may be because of destruction of a small aneurysm at the time of rupture, but it is just as likely to be a leak from a vessel without an aneurysm, as a result of the existence of a point of weakness as described below.

A relatively rare cause of bleeding, especially in children, is the presence of a vascular malformation in the arterial system, such as an angioma, an arteriovenous anastomosis, or an aberrant vessel in the meninges. Post-mortem angiography may be of assistance in tracing intracranial bleeding from natural lesions, as in trauma. Karhunen *et al.* (1990) describe the techniques required.

Though berry aneurysms are often called 'congenital', they are not themselves present at birth, but a defect in the wall of a cerebral artery is probably present from late fetal life. The circle of Willis condenses out of an irregular embryonic meshwork of arteries over the base of the brain by unwanted vessels undergoing atrophy. Where these redundant vessels originally joined the surviving main arteries, a 'window' in the elastic and collagenous coat is left, usually at the junction of two vessels. This window is a weak point where rising blood pressure in adult life may begin to form a 'blow-out', a thin-walled aneurysm, which may be single or multiple. At a certain stage, any sudden extra rise in blood pressure or flow rate may rip the already tense sac, and cause extravasation of blood at full arterial pressure into the subarachnoid space. Where there is no aneurysm, it must be assumed that a weak point in a vessel wall has given way *ab initio*, without the prior formation of a sac.

The search for a small aneurysm at autopsy may be difficult because of the thick layer of blood clot that is trapped in the meninges and vessels. Blunt dissection should be used, employing the handle of a scalpel or the nose of a pair of forceps. The blood should be constantly washed away in a continuous stream of water. It is possible to inject water into one of the cut ends of a vertebral artery, having carefully tied or clamped the other vessel and the two cut terminations of the carotid arteries, to see where the water leaks from. The leaks are often multiple, however, from artefactual tearing of small vessels during autopsy removal of the brain. The search for an aneurysm is best carried out on the fresh unfixed brain, as formalin fixation hardens the blood clot so much that it cannot be removed without the danger of tearing the underlying vessel and any aneurysm. It is essential to carry out blunt dissection progressively in a continuous stream of water. Aneurysms are most often found at the bifurcation of the middle cerebral and posterior communicating arteries, at the bifurcation of the basilar arteries, on the middle cerebral in the Sylvian fissure, on the anterior communicating artery, or where the posterior communicating artery joins the posterior cerebral vessels. An aneurysm is sometimes on the cortical aspect of the artery and may be part-buried in the cerebral surface, making it hard to find. If the swelling (which may be completely collapsed at autopsy, especially when ruptured) is not seen on superficial examination of the circle of Willis, the vessels should be gently lifted away from the brain surface with a blunt elevator so that the underside can be inspected. Sometimes a buried aneurysm will rupture mainly into the cortex, causing a lesion that may be mistaken for an intracerebral haemorrhage. Berry aneurysms are frequently multiple and of varying size, from a few millimetres to several centimetres, though the usual diameter is of the order of 3–8 mm.



FIGURE 25.18 *Adrenal haemorrhage occurring several days after multiple injuries sustained in a traffic accident. There was no apparent abdominal injury. The haemorrhage is fresh and occupies the medulla, with the cortex stretched around the periphery.*

PULMONARY THROMBOEMBOLISM

This is discussed fully in Chapter 13, but here it is sufficient to emphasize that pulmonary embolism is the most underdiagnosed cause of death, according to Cameron and McGoogan (1981). Their figures show that less than half the deaths shown at autopsy to have been caused by a pulmonary embolism were so diagnosed by the attending clinician. Paradoxically, many other presumed deaths from this condition were found at autopsy not to have been embolic. Thus the overall statistics are not so much in error – but in relation to the wrong victims!

Pulmonary embolism is more common with advancing age, with obese subjects and in the majority of instances there is a predisposing factor such as trauma, surgical operation, confinement to bed or immobility from another cause. Even prolonged sitting can lead to deep vein thrombosis, as was seen in persons sleeping in deckchairs in air-raid shelters in the last war and, more recently, it has been described as a hazard of long air flights.

A significant proportion, however, estimated by the author (BK) at up to 20 per cent, occur unexpectedly in the absence of any of these usual factors, making the legal problem of causation difficult. This is especially so in criminal cases where a high standard of proof has to be



FIGURE 25.19 *A rare cause of pulmonary embolism. Metastasizing embryonal carcinoma + seminoma of the testis (a) and thrombosis attached to the wall of inferior vena cava due to metastases of the local lymph nodes (b) and (c) pulmonary metastasis (white arrow) and massive pulmonary embolism (white X).*



FIGURE 25.20 *A large recent intracerebral haemorrhage in a person with hypertension. The bleeding has originated in the region of the external capsule from a lenticulostriate branch of the middle cerebral artery then broken through into the posterior horn of the lateral ventricle.*

attained, rather than the balance of probabilities required for a civil action.

SUDDEN DEATH IN EPILEPSY

Every coroner's pathologist or the equivalent in other jurisdictions, has experience of sudden deaths in epileptics, when no morphological lesion can be found at autopsy. Epileptics can die unexpectedly without being in status epilepticus – or indeed, not even in a typical fit. It is true that many such deaths are not witnessed to prove that no such fit occurred, but sufficient evidence exists to indicate that a rapid sudden death can certainly occur.

There are, of course, many deaths in epileptics where the mode is apparent, such as asphyxia during a fit in bed when the face is pressed into the pillow, and saliva and mucus form an airtight seal against the fabric around the nose and mouth. Epileptics also drown in the bathtub and suffer other traumatic deaths because of fits occurring when they are in some vulnerable position.



FIGURE 25.21 *Two fibrinogen-positive Purkinje cells and three negative cells in a sudden unexpected death with a history of epilepsy. (Peroxidase-DAB immunostaining, original magnification ×20.)*

These causes apart, the victim of epilepsy seems to be able to die with no apparent immediate cause and the mechanism is obscure. It has been suggested that some massive cerebral electric discharge or neurone storm occurs, leading to cardiac arrest, but this is mere hypothesis. When all investigations have been completed (including toxicological screening for antiepileptic drug overdose), after an essentially negative autopsy, then the pathologist is justified in recording 'epilepsy' as an acceptable cause of death.

The autopsy should always include a search for bites on the tip and distal sides of the tongue, which suggest a fit. A careful examination of the brain is essential, to search for any cause of post-traumatic epilepsy. In some epileptics, without coronary stenosis, patchy myocardial fibrosis has been recorded (Falconer and Rajs 1976), said to be the result of episodic hypoxia from apnoea during fits. Based on the observation of Sokrab *et al.* (1988) that Purkinje cells become labelled by plasma proteins in experimental blood–brain-barrier (BBB) breakdown, Ikegaya *et al.* (2003) investigated immunohistochemically the presence of fibrinogen-positive Purkinje cells in 50 sudden unexpected deaths. There were 24 subjects with and 26 without known history of epilepsy. Regarding ⩾30 per cent of fibrinogen-positive Purkinje cells as diagnostic limit indicating recent major BBB breakdown, they found that 22 of the 24 cases with high percentage of fibrinogen-positive Purkinje cells had a history of epilepsy. One of the two remaining high-fibrinogen subjects had unknown leucoencephalopathy and the other had essential hypertension. Only two of the low-fibrinogen cases had a history of epilepsy. The immunopositivity of Purkinje cells is not specific for epilepsy but can occur in any conditions causing BBB breakdown, most likely due to uptake of fibrinogen



FIGURE 25.22 *Cross-section of a bronchus in sudden asthma death showing cell-laden mucus, folding of the soft tissues of the bronchial wall, thickening of the basement membrane and hypertrophy of the muscle. (HE, original magnification ×10.)*

from the cerebrospinal fluid irrigating the cerebellar surface. The time interval needed for the protein accumulation in man is not known. It is probable that, in addition to fibrinogen, other plasma proteins can also be used as a marker and an auxiliary method in assessing the probability of epileptic seizures contributing to the cause of death in sudden unexpected deaths.

SUDDEN DEATH IN BRONCHIAL ASTHMA

As in epilepsy, sufferers from bronchial asthma may die suddenly and unexpectedly, without necessarily being in status asthmaticus or even in an acute asthmatic attack. The mechanism is obscure, but experience proves that such fatalities are not uncommon. About 20 years ago, there was a marked increase in sudden deaths in asthmatics, but it was recognized that this was caused by the overuse of inhalers containing bronchodilators. These adrenergic drugs, used in excess, have a direct action upon the myocardium causing tachycardia, arrhythmias and ventricular fibrillation. Awareness among prescribing doctors rapidly reduced this danger but sudden deaths still occur, even when these substances are not used to excess.

The question of sudden death in asthma was discussed by Morild and Giertsen (1989). They considered that a number of factors contributed to death. Hypoxia and respiratory acidosis occur in asthma and increase myocardial irritability. Drugs such as theophylline and sympathomimetic agents can provide ventricular fibrillation. The β_2-antagonists so commonly used for the relief of bronchospasm are not so prone to cause cardiac arrhythmias, but they are by no means safe drugs in this respect. Of the 11 deaths in this Norwegian series, seven victims were found dead with a β_2-inhaler still clutched in their hands. Overdosage of the substance appears to be common. The use of theophylline derivatives combined with sympathomimetic agents tends to accentuate the cardiotoxicity of the bronchodilators.

Some of the deaths appeared to be in instances where the drug had been exhausted from the inhaler, but the propellant was still active. This may be another possible mechanism for some of these deaths, similar to the vagal inhibitory fatalities seen in butane misuse, where cold gas impinges on the pharynx.

At autopsy little or nothing is found, except confirmation of the chronic asthmatic state. On opening the chest cavity, the lungs are seen to fill the thorax, not collapsing as is usual and they have a pale spongy texture, forming stable pits when pressed with the fingers. The cut surface may reveal thick-walled prominent bronchi, often plugged with thick, clear mucus. This is not an explanation for the sudden collapse and death, however, and the mechanism remains obscure.

The topic of sudden death from asthma in childhood has been investigated by Champ and Byard (1994), who consider that it occurred only in children with significant chronic disease.

RESPIRATORY OBSTRUCTION

Mechanical obstruction by foreign bodies is dealt with in Chapter 14, but some rapid – if not actually sudden – deaths can be due to fulminating natural disease.

Rupture of a retropharyngeal abscess (‘quinsy’), when pus and necrotic material pour into the pharynx and larynx, is now a rare cause. Diphtheria is also virtually unknown in advanced countries so that the toxaemia, a fatal myocarditis and the possibility of laryngeal obstruction from a detached pharyngeal membrane are rarely considered by most doctors.

More common – and a cause of legal actions for negligence against doctors – is the fulminating epiglottitis caused by *Haemophilus influenzae* in children. This is a major paediatric emergency and any child with stridor of recent onset should be seen urgently by a paediatrician and anaesthetist. The gross infective oedema of the laryngeal entrance can lead to death within hours of onset of the illness, and may require rapid intubation or tracheostomy to save life.

HAEMOPTYSIS

Now that pulmonary tuberculosis is less common and treatable in advanced countries, deaths from haemoptysis are rare, as most massive respiratory haemorrhages were from this cause. However, warning signals are now evident about a revival of tuberculosis, even in 'advanced' countries. Part of the return of this scourge is due to opportunist infection in HIV-infected persons, but AIDS apart, phthisis seems to be on the march again, with worrying concerns about increasing resistance to the drugs, which revolutionized its treatment 30–40 years ago.

Bronchial tumours rarely cause fatal haemoptyses, unless a large vessel is eroded; syphilitic aortitis perforating the aorta or other large vessel is now almost a matter of history.

The bleeding rarely causes death from exsanguination except where the aorta is eroded, but smaller bleeds may fill the air passages, and cause an asphyxial-type death or a 'vagal inhibition'-type death from sudden flooding of the larynx.

GASTROINTESTINAL HAEMORRHAGE

Bleeding may take place at any point along the alimentary tract and though modern transfusion and resuscitatory methods make deaths unusual these days, some are seen in medico-legal practice when people living alone or otherwise remote from assistance, die without any medical intervention.

Bleeding from surgical operations in the mouth or pharynx, such as tooth extraction or tonsillectomy, rarely causes death, but can occasionally do so from blood and clot blocking the airways. In the oesophagus, a penetrating carcinoma may erode the aorta or other great vessel in the mediastinum, but the most frequent sources of bleeding are varices at the lower end, caused by the portal hypertension associated with hepatic fibrosis. It is often difficult to identify the varices at autopsy, as they have collapsed, but the absence of gastric or duodenal ulceration, and the congested, bluish vessels around the cardia often give away the lesion, especially in the presence of liver cirrhosis and splenomegaly.

Other causes of massive gastrointestinal bleeding are gastric and duodenal peptic ulcers, which can erode large vessels in their base. Acute erosions, though shallow, can produce considerable blood in the stomach and may require surgical resection. They are rarely the cause of lethal bleeding.

Carcinoma of the stomach can reach a large size and the crater variety may perforate a major vessel to produce severe haemorrhage. Bleeding from the small intestine is rare, except in certain haemorrhagic diatheses. More common is bleeding from colonic lesions, such as carcinomas and ulcerative colitis.



FIGURE 25.23 *Massive lethal bleeding from eroded vessels of a gastric ulcer.*

Polyps, sometimes malignant, may also give rise to melaena and even massive bleeding *per rectum*, though these are now rarely fatal unless medical intervention is delayed or absent.

FATAL ABDOMINAL CATASTROPHES

Though usually surgical emergencies, some abdominal conditions go untreated because the victim is either a solitary person living alone with no opportunity to call for help, or declines to seek medical assistance. They may well be found dead with no history to suggest a cause of death.

Mesenteric thrombosis and infarction is one such condition. The thrombosis may in fact be an embolus, rather than a thrombosis *in situ*, the most common cause of both being atherosclerosis of the aorta and its mesenteric branches. The length of small intestine supplied by the vessel becomes dark and necrotic, and may involve almost the whole length of the jejunum and ileum. Even if precipitated by an embolus, much of the rest of the arterial system may then thrombose and, on cutting into the mesentery at autopsy, the cut ends of arteries may show plugs of firm ante-mortem thrombus. The gut will be blue–red or even almost black, with loss of the serosal lustre and a friable necrotic wall.

Strangulated intestine is yet another condition that may present as sudden or rapid death, where medical attention is lacking, and even sometimes when it is negligently offered.

Hernias, both femoral and inguinal, and internal strangulation beneath fibrous bands in the peritoneal cavity, may all twist the intestine so that its blood supply is cut off, with subsequent necrosis. The gut above may develop ileus and become paralysed and dilated.



FIGURE 25.24 *Great distension of colon due to volvulus of sigmoid colon. Deceased found dead with history of abdominal pain.*



FIGURE 25.25 *A massive pontine haemorrhage in a person with hypertension. The circumstances and the irregular distribution of the bleeding within the brainstem distinguish this primary haemorrhage from the secondary lesions seen in raised intracranial pressure. Sometimes a natural intracranial haemorrhage may precipitate an accidental fall or traffic accident, however, and the resulting head injury may make it more difficult to identify the nature of the brain haemorrhage.*

Caution is needed at autopsy to differentiate the dark red colour of loops of intestine due to post-mortem hypostasis from true infarction. Hypostasis is seen to be interrupted when the gut is stretched out, due to alternate dependent loops, whereas real necrosis is usually continuous and the serosa is dull and friable.

Fulminating peritonitis may be seen in a variety of causes, again leading to death if undiagnosed or untreated. Death from acute appendicitis and appendix abscess is now uncommon, but perforation of the colon through a diverticulum, whether inflamed or merely distended and eroded by faecoliths, is common.

Tearing of the senile gut where it is adherent to other structures, such as uterus or tube, can also lead to peritonitis, and a carcinoma (often difficult to differentiate macroscopically from chronic diverticulitis) may also lead to perforation with loss of intestinal contents into the peritoneum.

A perforated peptic ulcer, usually duodenal, leads to a chemical peritonitis. The autopsy appearances are straightforward, turbid fluid being found in the peritoneal cavity, which may show early inflammatory changes, if the perforation occurred many hours previously. The perforation is most commonly found on the posterior surface of the duodenum.

GENITOURINARY SYSTEM

There is very little in the urinary system that can give rise to a sudden or rapid death, but the female genital organs certainly make up for this. Complications of pregnancy are discussed elsewhere (Chapter 19), but it should be repeated here that ectopic pregnancy, usually in the tubes, can rupture with massive intraperitoneal haemorrhage. Induced abortions, unless under reputable medical control, are another source of death from haemorrhage, air embolism, perforation of vagina or uterus, infection and the use of toxic substances.

THE RELATIONSHIP BETWEEN TRAUMA AND DISEASE

One of the most difficult problems in forensic medicine occurs when a death takes place in a person who has suffered trauma but who has either pre-existing natural disease or where some apparently natural disease has supervened after the trauma. The relative contributions of trauma and disease may then become an acute medico-legal problem.

For example, the author (BK) conducted an autopsy on an old man of 82 years, previously in excellent health, who had been tied up and slightly injured by robbers of a sub-post office. Within 2 hours of release from his bonds the old gentleman became ill and then hemiplegic, dying of a massive cerebral haemorrhage shortly afterwards. The attackers were charged with homicide, in addition to robbery, but that charge was rejected by magistrates on the grounds that a cerebral haemorrhage could be a natural disease, unrelated to the assault. The prosecution obtained a private Bill of Indictment to circumvent the magistrates, and at the Crown Court the accused were convicted of manslaughter on the grounds that the physical and emotional stress of being assaulted and tied up probably (beyond reasonable doubt) led to an elevation of blood pressure that precipitated a cerebral haemorrhage in a previously fit person, within such a short time span.

This marginal case illustrates the problems that can occur when trauma and natural disease coexist in the same person. A common dilemma exists in relation to subarachnoid haemorrhage from a ruptured berry aneurysm when there has been a head injury.

In autopsies when an injury has been sustained by a person with substantial natural disease, the following problems must be addressed:

- whether death was caused entirely by the disease and would have occurred irrespective of the injury
- whether death was caused entirely by the injury and would have occurred whether or not the disease was present
- whether the death was caused by a combination of these two processes.

In practical terms, the most common situations involve coronary artery disease, pulmonary embolism and subarachnoid haemorrhage.

Coronary atherosclerosis

The disease has invariably been present for months or probably years before the traumatic episode, and it is therefore indisputably obvious that the trauma can have no relationship to the genesis of the disease – though relatives and some lawyers are often hard to convince on this point. Furthermore, unless there was a direct blow onto the front of the thorax, which could physically have damaged the heart surface and caused a direct traumatic lesion of the coronary system (by dislodging an atheromatous plaque – but see end of this section – causing a subintimal haemorrhage or precipitating a coronary thrombosis, a rare event), there is no way in which the injury can be accused of worsening the state of the coronary arteries. If the state of the coronary system was already poor, thus it could justifiably be claimed by the defence that death could have occurred at any time. The standard of proof in criminal cases is high and must be proved 'beyond reasonable doubt', whereas in civil disputes, only 'the balance of probabilities' must be attained.

As opposed to showing that the trauma directly worsened the physical state of the coronary vessels, it is easier to claim that the physical and emotional stress associated with the traumatic event caused increased demands upon a weakened heart and caused it to fail. Recent investigations (see end of this section) have strongly confirmed the association between acute myocardial infarction, cardiac arrest and exertion.

The adrenal response of 'fight or flight' may be invoked, it being accepted that released endogenous catecholamines such as noradrenaline can send a chronically hypoxic heart into ventricular fibrillation and arrest. There may even be morphological evidence in some cases, by the finding of contraction bands in the cardiac myofibrils, especially in the superficial subepicardial layers.

It is often an assessment of the circumstances, in addition to the autopsy findings, that decides a court's attitude to the relationship of trauma to disease. Where a man who has had no previous cardiac symptoms drops dead immediately after some assault or strenuous activity, the court is more likely to assume an association than with some cardiac cripple, who has been hovering on the brink of heart dysfunction for a long time before the traumatic event.

The average jury is likely to decide that it would be too much of a coincidence for an assault to cause a man to drop dead on the spot, even if it was shown that his coronary artery stenosis had been there for several years. Much depends upon the individual circumstances, especially where there is only a short interval between the traumatic episode and death.

The strict test is: 'Would he have died when he did die if the assault had not taken place?' This is often unanswerable on medical grounds, but the court is entitled to take a commonsense view of coincidence in terms of immediacy in time and apply the 'beyond reasonable doubt' test to it.

The fact that a person is in a parlous state of health and might die from relatively minimal trauma is no defence in law, which states that 'an assailant must take his victims as he finds them'. In other words, it is immaterial whether the attacker knows that his victim is ill or not – if death results from an illegal act against him, the charge of homicide may stand. This dictum is not adhered to slavishly by public prosecutors, however, as it is a matter of practical politics whether a criminal prosecution can be maintained with any chance of success (using public funds), against an energetic defence that can show medically that the victim had such a degree of natural disease that he might have dropped dead spontaneously at any time. The prevalence of coronary disease is so widespread that a close association in time must be shown before any causal connection can be accepted. The actual death itself need not occur very soon after the assault, however, if it can be established that the latter could have precipitated an infarct in a myocardium already compromised by coronary stenosis. It is not only a blow or some physical trauma that may precipitate a myocardial infarct or arrhythmia; as stated above, even the emotional upset that accompanies injury, or even the threat or fear of an injury, can lead to death. The blow may never actually be struck or it may fail to land, yet the threatened person may suffer a transient hypertension or tachycardia that may precipitate a subintimal haemorrhage, arrhythmia, or cerebral or subarachnoid haemorrhage that leads to death. Such an event, however, with little or no morphological evidence to be presented as evidence, has a poor chance of acceptance in court unless the circumstances are clear-cut. These cases pose a problem for police and pathologist, in that it may be difficult to decide whether to arrest and charge the potential culprit with a criminal offence.

A typical case was once seen by the author (BK) in which an elderly man was involved in an altercation with another, concerning parking a car. There was a scuffle, in which only trivial blows were exchanged, but one participant immediately developed chest pain and breathlessness, and soon died. The other man was arrested, but as autopsy showed marked cardiac enlargement, extensive myocardial fibrosis and gross occlusive coronary atherosclerosis, the prosecution decided to offer no evidence and the charge was dropped, even though the answer to the 'acid test' of whether the victim would have been likely to die at that particular time had the altercation not taken place was probably in the negative.

In civil matters, considerable sums of money may hang upon such decisions by way of damages and insurance payments. Here the standard of proof is much lower, as the plaintiff only has to show that there was a 51 per cent or better chance of the association being present, rather than the much higher standard of criminal liability.

An actual example of the civil problems was a workman who was removing a truck wheel from his employer's vehicle with a wheelbrace. Under full pressure, the threaded stud in the hub suddenly snapped and the man was thrown to the ground under the force of his own muscular effort. He was shocked and soon developed chest pain and died the next day. Autopsy revealed no fresh infarct, but there was longstanding left ventricular hypertrophy, myocardial fibrosis and stenosing coronary atheroma. The employer's liability was disputed, but eventually a compromise settlement was reached.

Recent very careful and statistically meticulous research on large cohorts, both in the USA and Germany, have shown an indisputable relationship between exertion and sudden cardiac death. Mittleman *et al.* (1993) investigated 1228 patients with acute myocardial infarcts and showed that there was a sixfold increase in the incidence of infarction during or within one hour of heavy physical exertion, such as snow shovelling, jogging or sexual activity. In Germany, Willich *et al.* (1993) researched 1194 patients with the same condition and showed a twofold increase in risk. Both surveys showed that the risk was greater in those who were otherwise sedentary and that long-term moderate exercise was undoubtedly associated with a reduced risk of infarction (Curfman 1993). Several mechanisms were proposed for the increased risk during sudden severe exertion, including the splitting and dislodgement of an atheromatous plaque. It was also claimed that increased platelet activation occurred in sedentary people who suddenly exerted themselves. In an earlier publication, Siscovick *et al.* (1984) showed the same trend in primary cardiac arrest, exertion in otherwise sedentary persons increasing the risk, whilst habitual exercise protected.

Subarachnoid haemorrhage

Subarachnoid haemorrhage is another difficult area in which trauma and natural disease interact. When a berry aneurysm on the cerebral arteries ruptures, the allegation is often made that some traumatic occurrence precipitated that event. The matter is discussed in Chapter 5, but to recapitulate here, the problem is to decide whether the trauma itself was a mechanical factor in causing the arterial blister to burst.

A rupture is a relatively common event without external trauma, this cause of death being well-known in young to middle-aged persons who are not indulging in any strenuous activity whatsoever. It is known to occur, however, during innocent activities, such as jogging, intercourse and sporting exertion, probably because of a transient rise in blood pressure and pulse rate. Once again, a potent element may be in the adrenal response, catecholamines pushing up the blood pressure. Thus when a ruptured aneurysm occurs during or shortly after a fight or altercation, it is arguable whether a mechanical blow to the head or merely the emotional stress of a dispute is the most potent factor in causing rupture. There has been much medical argument about the role of trauma in causing the rupture, as many would maintain that the aneurysm is so deep-seated within the skull that internal pressure from hypertension is far more likely to be the reason.

Certainly, where a small aneurysm a few millimetres in size breaks, it is difficult to accept that a blow could have caused a tear, but in the more exceptional cases of a large tissue-thin globule, then it is easier to accept that intracranial stresses may have played a significant part. The role of alcoholic intoxication – another hotly disputed aspect – has been discussed in Chapter 5. The legal problem is similar in berry aneurysm deaths to that in coronary disease. The time interval is naturally important, though in most instances, bleeding occurs immediately or soon afterwards.

Autopsy is not all that helpful in assessing the relative contribution of assault versus pre-existing disease. Unless the aneurysm is found to be large and fragile, the morphological findings are mainly of use in confirming the diagnosis, evaluating any injuries and excluding any other contributory disease. It used to be the usual practice in England and Wales not to prosecute assailants when an aneurysm was demonstrated at autopsy, though in Scotland and on the continent of Europe no such reluctance was evident. Following a case in Gibraltar in 1978, however, in which a British sailor was convicted of homicide after kicking another in a drunken brawl, the latter eventually dying of subarachnoid haemorrhage from a ruptured aneurysm, such charges are now usually brought (Knight 1979).

Pulmonary embolism

The other major example of the interaction of trauma and natural disease is pulmonary embolism. This is discussed in Chapter 13, but is so important in medico-legal casework that the forensic aspects may be repeated here with advantage.

Deep vein thrombosis, almost always in the leg veins, is a common sequel to injury and consequent immobility. Virchow's triad of slowing of the circulation, local injury to vessel walls and increase in blood coagulability are the major factors, though deep vein thrombosis can occur in the absence of all three. When the leg is the site of the injury, it is more likely to occur in the ipsilateral limb, though it can occur contralaterally or bilaterally. The fact that a fatal embolus came from the contralateral limb when the other leg has been injured by no means rules out a causative element.

Pulmonary embolism typically occurs about 2 weeks after an injury or surgical operation, but the range of time during which a cause-and-effect mechanism operates can be anything from about 2 to 90 days. It becomes progressively more difficult to maintain a causative relationship, however, when the interval exceeds a few weeks.

Forensically, it is vital to show that the deep vein thrombosis post-dated the traumatic event, if an association is to be established. If a person suffers a fatal embolism a week after injury, yet histologically the deep vein thrombosis appears to be several weeks old, then obviously the injury could not have initiated the process. The embolus may, however, be much younger than the most distal part of the leg vein thrombosis (which may be as far down as the foot) as progressive proximal extension of a deep vein thrombosis undoubtedly occurs. It could still be argued, therefore, that although the original thrombosis antedated the injury, the latter encouraged extension and hence the eventual breaking off of an embolus. The case becomes weaker, however, than if the whole process was entirely subsequent to the traumatic event.

Histological dating of the embolus should always be undertaken, though it is less rewarding and more difficult than that of the leg vein thrombi, which must always be taken for microscopy with the vein wall intact. It is the thrombo-mural junction that gives the most information about the age of any thrombus. Thrombosis of the deep leg veins is far more common than pulmonary thromboembolism. In 100 consecutive coroner's autopsies, Knight and Zaini (1980) found 32 instances of deep vein thrombosis, but only 10 had pulmonary emboli, not all fatal.

The legal problem, outlined in Chapter 13, is that though trauma, surgery and immobility are potent factors in the development of deep vein thrombosis, the latter condition frequently occurs in the absence of all three. Thus it is difficult to maintain that any traumatic event was the cause of a subsequent fatal pulmonary embolism, as many fatal emboli occur in the absence of trauma. In a series of coroner's and hospital autopsies studied by Knight (1966), 25 per cent of fatal pulmonary emboli came 'out of the blue' in ambulant people who had no previous history of trauma or surgical operation. Later, Knight and Zaini studied 38 000 autopsy reports and found that 10 per cent of deaths due to pulmonary embolism had no history of any predisposing factors. The discrepancy in these proportions is caused by the variable standard of history reports and also by marked alterations in pathologist's reporting habits over the years – in fact, in the large series mentioned above, there was not a single fatal pulmonary embolism recorded in the 20 years from 1908 until 1928!

Even disregarding the dubious statistical value of such investigations, there can be no doubt that a significant proportion of fatal pulmonary emboli cannot be related to previous trauma. This provides a line of defence in those cases where the prosecution allege that a 'cause-and-effect' relationship exists between some criminal assault and death. It becomes a matter of law for the judge to decide whether he will let the issue go to the jury, and a matter of fact for the jury to decide whether this relationship can be 'beyond reasonable doubt' in circumstances where even conservatively, at least 10 per cent of pulmonary emboli are not related to trauma. Several court cases are within the author's (BK) experience in which quite different verdicts have been reached on essentially identical pathological evidence.

In civil cases, usually related to road traffic accidents or industrial personal injuries, the burden on the plaintiff is much lighter, as the 'balance of probabilities' test can be much more readily satisfied.

REFERENCES AND FURTHER READING

Al Rufaie HK, Florio RA, Olsen EG. 1983. Comparison of the haematoxylin basic fuchsin picric acid method and the fluorescence of haematoxylin and eosin stained sections for the identification of early myocardial infarction. *J Clin Pathol* **36**:646–9.

Anderson HN. 1964. An evaluation and comparison of macroscopic enzyme techniques for the autopsy demonstration of myocardial infarction. *J Pathol* **127**:93–8.

Ansari A, Maron BJ, Berntson DG. 2003. Drug-induced toxic myocarditis. *Tex Heart Inst J* **30**:76–9.

Aretz HT. 1987. Myocarditis: the Dallas criteria. *Hum Pathol* **18**:619–24.

Aretz HT, Billingham ME, Edwards WD, *et al.* 1987. Myocarditis. A histopathologic definition and classification. *Am J Cardiovasc Pathol* **1**:3–14.

Badir B, Knight B. 1987. Fluorescence microscopy in the detection of early myocardial infarction. *Forensic Sci Int* **34**:99–102.

Bajanowski T, Rossi L, Biondo B, *et al.* 2001. Prolonged QT interval and sudden infant death – report of two cases. *Forensic Sci Int* **115**:147–53.

Balachandra AT, O'Conner R, Bowden DH. 1987. Sudden unexpected death in asthmatics. *J Can Forensic Sci* **20**:227.

Baroldi G. 1975. Different types of myocardial necrosis in coronary heart disease: a pathophysiologic review of their functional significance. *Am Heart J* **89**:742–52.

Bateman JR, Clarke SW. 1979. Sudden death in asthma. *Thorax* **34**:40–4.

Bjork VD. 1964. *Cardiomyopathies.* Ciba Foundation Symposium. Churchill, London.

Bostrom H. 1966. Acute epiglottitis as a cause of sudden death. *Dtsch Z Gesamte Gerichtl Med* **61**:53–9.

Bouchardy B, Majno G. 1971. A new approach to the histologic diagnosis of early myocardial infarcts. *Cardiology* **56**:327–32.

Bouchardy B, Majno G. 1974. Histopathology of early myocardial infarcts. A new approach. *Am J Pathol* **74**:301–30.

Cameron HM, McGoogan E. 1981. A prospective study of 1152 hospital autopsies: I. Inaccuracies in death certification. *J Pathol* **133**:273–83.

Cardell BS, Pearson RS. 1959. Death in asthmatics. *Thorax* **14**:341–52.

Carle BN. 1981. Autofluorescence in the identification of myocardial infarcts. *Hum Pathol* **12**:643–6.

Champ CS, Byard RW. 1994. Sudden death in asthma in childhood. *Forensic Sci Int* **66**:117–27.

Chan AC, Dickens P. 1992. Tuberculous myocarditis presenting as sudden cardiac death. *Forensic Sci Int* **57**:45–50.

Clark JC. 1988. Sudden death in the chronic alcoholic. *Forensic Sci Int* **36**:105–11.

Clawson BJ. 1928. Myocarditis. *Am Heart J* **4**:1–7.

Cochrane GM, Clark JH. 1975. A survey of asthma mortality in patients between ages 35 and 64 in the greater London hospitals in 1971. *Thorax* **30**:300–5.

Copeland AR. 1986. Asthmatic deaths in the medical examiner's population. *Forensic Sci Int* **31**:7–12.

Corby C. 1960. Isolated myocarditis as a cause for sudden obscure death. *Med Sci Law* **1**:1–40.

Crawford T. 1977. *Pathology of ischaemic heart disease.* Butterworth, London.

Curfman GD. 1993. Is exercise beneficial – or hazardous – to your heart? [editorial; comment] [see comments]. *N Engl J Med* **329**:1730–1.

Cushing EH. 1942. Infarction of the cardiac auricles. *Br Heart J* **4**:17–26.

Davies M, Pomerance A. 1975. *Pathology of the heart.* Blackwell Scientific Publications, Oxford.

Davies MJ. 1981. Pathological view of sudden cardiac death. *Br Heart J* **45**:88–96.

Davies MJ, Popple A. 1979. Sudden unexpected cardiac death – a practical approach to the forensic problem. *Histopathology* **3**:255–77.

Decastello A, Remenar E, Toth J, *et al.* 1977. Post mortem detection of early myocardial infarction by determination of the tissue K^+/Na^+ ratio. *Acta Morphol Acad Sci Hung* **25**:289–96.

Derias NW, Adams CW. 1979. The non-specific nature of the myocardial wavy fibre. *Histopathology* **3**:241–5.

Derias NW, Adams CW. 1982. Macroscopic enzyme histochemistry in myocardial infarction: use of coenzyme, cyanide, and phenazine methosulphate. *J Clin Pathol* **35**:410–13.

deSa DJ. 1986. Isolated myocarditis as a cause of sudden death in the first year of life. *Forensic Sci Int* **30**:113–17.

Dettmeyer R, Schlamann M, Madea B. 1999. Immunohistochemical techniques improve the diagnosis of myocarditis in cases of suspected sudden infant death syndrome (SIDS). *Forensic Sci Int* **105**:83–94.

Dettmeyer R, Kandolf R, Schmidt P, *et al.* 2001. Lympho-monocytic enteroviral myocarditis: traditional, immunohistological and molecular pathological methods for diagnosis in a case of suspected sudden infant death syndrome (SIDS). *Forensic Sci Int* **119**:141–4.

Dettmeyer R, Reith K, Madea B. 2002. Alcoholic cardiomyopathy versus chronic myocarditis – immunohistological investigations with LCA, CD3, CD68 and tenascin. *Forensic Sci Int* **126**:57–62.

Drury RA. 1954. The role of intimal haemorrhage in coronary occlusion. *J Pathol Bacteriol* **67**:207–15.

Edston E. 1997. Evaluation of agonal artifacts in the myocardium using a combination of histological stains and immunohistochemistry. *Am J Forensic Med Pathol* **18**:163–7.

Edston E, Kawa K. 1995. Immunohistochemical detection of early myocardial infarction. An evaluation of antibodies against the terminal complement complex (C5b-9). *Int J Legal Med* **108**:27–30.

English JP, Williams FA. 1943. Haemorrhagic lesions of the coronary arteries. *Arch Intern Med* **71**:594–602.

Falconer B, Rajs J. 1976. Post-mortem findings of cardiac lesions in epileptics: a preliminary report. *Forensic Sci* **8**:63–71.

Farrer-Brown G. 1968. Normal and diseased vascular pattern of myocardium of human heart. I. Normal pattern in the left ventricular free wall. *Br Heart J* **30**:527–36.

Farrer-Brown G. 1977. *A colour atlas of cardiac pathology.* Wolfe Medical Publications, London.

Feibel JH, Campbell RG, Joynt RJ. 1976. Myocardial damage and cardiac arrhythmias in cerebral infarction and subarachnoid hemorrhage: correlation with increased systemic catecholamine output. *Trans Am Neurol Assoc* **101**:242–4.

Feldman AM, McNamara D. 2000. Myocarditis. *N Engl J Med* **343**:1388–98.

Feldman S, Glagov S, Wissler RW, *et al.* 1976. Postmortem delineation of infarcted myocardium. Coronary perfusion with nitro blue tetrazolium. *Arch Pathol Lab Med* **100**:55–8.

Ferris JA. 1974. Conducting tissue changes in sudden death. *Med Sci Law* **14**:36–9.

Ferris JA, Friesen JM. 1979. Definitions of ischaemia, infarction and necrosis. *Forensic Sci Int* **13**:253–9.

Ferris JA, MacLennan JR. 1973. A simplified method for examining the conducting tissues of the heart. *Med Sci Law* **13**:285–8.

Ferris JA, Rice J. 1979. Drug-induced myocarditis: a report of two cases. *Forensic Sci Int* **13**:261–5.

Fleming HA. 1988. Death from sarcoid heart disease: United Kingdom series 1971–1986, 300 cases with 138 deaths. In: Grassi C (ed.), *Sarcoidosis and other granulomatous disorders.* Excerpta Medica, Amsterdam, pp. 19–33.

Fleming HA, Bailey SM. 1981. Sarcoid heart disease. *J R Coll Physicians Lond* **15**:245–6, 249–53.

Fothergill DF, Bowen DA, Mason JK. 1979. Dissecting and atherosclerotic aneurysms: a survey of post-mortem examinations, 1968–77. *Med Sci Law* **19**:253–60.

Fraser PM, Speizer FE, Waters SD, *et al.* 1971. The circumstances preceding death from asthma in young people in 1968 to 1969. *Br J Dis Chest* **65**:71–84.

Fukumoto H, Naito Z, Asano G, *et al.* 1998. Immunohistochemical and morphometric evaluations of coronary atherosclerotic plaques associated with myocardial infarction and diabetes mellitus. *J Atheroscler Thromb* **5**:29–35.

Glogner. 1903. Cited by Stamer. 1907. *Virchows Arch Pathol Anat* 171.

Gore I, Saphir O. 1947. Myocarditis: a classification of 1042 cases. *Am Heart J* **34**:827–41.

Gormsen H. 1955. Sudden unexplained death due to myocarditis. *Acta Pathol Microbiol Scand* **105**(Suppl):303.

Gregersen M. 1979. Myocardial changes in sudden unexpected coronary deaths. *Forensic Sci Int* **13**:183–6.

Hansen SH, Rossen K. 1999. Evaluation of cardiac troponin I immunoreaction in autopsy hearts: a possible marker of early myocardial infarction. *Forensic Sci Int* **99**:189–96.

Hiltunen JK, Saukko P, Hirvonen J. 1985. Correlations between enzyme histochemical reactions and respective enzyme activities in global ischaemic rat hearts. *Br J Exp Pathol* **66**:743–52.

Hirvonen J, Hiltunen JK, Saukko P. 1987. Oxidative enzyme activities and respective histochemical reactions in ischemic rat myocardium. *Forensic Sci Int* **35**:231–6.

Holmbom B, Lindstrom M, Naslund U, *et al.* 1991. A method for enzyme- and immunohistochemical staining of large frozen specimens. *Histochemistry* **95**:441–7.

Hougen HP, Valenzuela A, Lachica E, *et al.* 1992. Sudden cardiac death: a comparative study of morphological, histochemical and biochemical methods. *Forensic Sci Int* **52**:161–9.

House RK. 1948. Diffuse interstitial myocarditis in children. *Am J Pathol* **24**:1235–48.

Hu BJ, Chen YC, Zhu JZ. 1996. Immunohistochemical study of fibronectin for postmortem diagnosis of early myocardial infraction. *Forensic Sci Int* **78**:209–17.

Hudson RE. 1963. The human conducting system and its examination. *J Clin Pathol* **16**:492–8.

Hudson RE. 1970. The cardiomyopathies: order from chaos. *Am J Cardiol* **25**:70–7.

Ikegaya H, Heino J, Laaksonen H, *et al.* 2003. Accumulation of fibrinogen in Purkinje cells in sudden death in epilepsy. *Forensic Sci Int* accepted for publication.

Inman WH, Adelstein AM. 1969. Rise and fall of asthma mortality in England and Wales in relation to use of pressurised aerosols. *Lancet* **2**:279–85.

Iwadate K, Tanno K, Doi M, *et al.* 2001. Two cases of right ventricular ischemic injury due to massive pulmonary embolism. *Forensic Sci Int* **116**:189–95.

Jaakkola K, Jalkanen S, Kaunismaki K, *et al.* 2000. Vascular adhesion protein-1, intercellular adhesion molecule-1 and P-selectin mediate leukocyte binding to ischemic heart in humans. *J Am Coll Cardiol* **36**:122–9.

Jääskeläinen AJ. 1968. Histochemical observations on phosphorylase, cytochrome oxidase and succinic dehydrogenase in experimental and human fresh myocardial infarcts. *Ann Univ Turku* **Series A II**(Suppl 39):1–64.

Jackson RT, Beaglehole R, Rea HH, *et al.* 1982. Mortality from asthma: a new epidemic in New Zealand. *Br Med J Clin Res Ed* **285**:771–4.

James TN. 1996. Long reflections on the QT interval: the sixth annual Gordon K. Moe lecture. *J Cardiovasc Electrophysiol* **7**:738–59.

Johnson AJ, Nunn AJ, Somner AR, *et al.* 1984. Circumstances of death from asthma. *Br Med J Clin Res Ed* **288**:1870–2.

Karhunen PJ, Penttilä A, Erkinjuntti T. 1990. Arteriovenous malformation of the brain: imaging by postmortem angiography. *Forensic Sci Int* **48**:9–19.

Kherdar A, Nevins MA. 1973. Right ventricular infarction. *Med Soc New Jersey* **70**:374–8.

Knight B. 1965. The postmortem detection of early myocardial infarction. *Med Sci Law* **5**:31–46.

Knight B. 1966. Fatal pulmonary embolism: factors of forensic interest in 400 cases. *Med Sci Law* **6**:150–4.

Knight B. 1967. Early myocardial infarction. Practical methods for its post-mortem demonstration. *J Forensic Med* **14**:101–7.

Knight B. 1971. The value of enzyme techniques in medicolegal pathology. In: Wecht C (ed.), *Legal medicine annual 1971*. Appleton Century Crofts, New York.

Knight B. 1973. The myocardium in sudden death from hypertensive heart disease or aortic stenosis. *Med Sci Law* **13**:280–4.

Knight B. 1976. Investigation of sudden deaths from myocardial ischaemia. *Forensic Sci* **8**:33–6.

Knight B. 1979. A further evaluation of the reliability of the HBFP stain in demonstrating myocardial damage. *Forensic Sci Int* **13**:179–81.

Knight B. 1979. Trauma and ruptured cerebral aneurysm. *Br Med J* **1**:1430–1.

Knight B, Zaini MR. 1980. Pulmonary embolism and venous thrombosis. A pattern of incidence and predisposing factors over 70 years. *Am J Forensic Med Pathol* **1**:227–32.

Knight BH. 1966. *The postmortem diagnosis of early myocardial infarction*. Cardiff University of Wales, Cardiff.

Lachica E, Villanueva E, Luna A. 1988. Comparison of different techniques for the postmortem diagnosis of myocardial infarction. *Forensic Sci Int* **38**:21–6.

Leadbeatter S, Stansbie D. 1984. Postmortem diagnosis of familial hypercholesterolaemia. *Br Med J Clin Res Ed* **289**:1656.

Leadbeatter S, Wawman H, Jasani B. 1989. Immunocytochemical diagnosis of early ischaemic/hypoxic damage in myocardium. *Acta Med Leg Soc (Liege)* **39**:187–8.

Leadbeatter S, Wawman HM, Jasani B. 1990. Further evaluation of immunocytochemical staining in the diagnosis of early myocardial ischaemic/hypoxic damage. *Forensic Sci Int* **45**:135–41.

Leestma JE, Kalelkar MB, Teas SS, *et al.* 1984. Sudden unexpected death associated with seizures: analysis of 66 cases. *Epilepsia* **25**:84–8.

Leestma JE, Hughes JR, Teas SS, *et al.* 1985. Sudden epilepsy deaths and the forensic pathologist. *Am J Forensic Med Pathol* **6**:215–18.

Lie JT, Holley KE, Kampa WR, *et al.* 1971. New histochemical method for morphologic diagnosis of early stages of myocardial ischemia. *Mayo Clin Proc* **46**:319–27.

Luke JL, Helpern M. 1968. Sudden unexpected death from natural causes in young adults. A review of 275 consecutive autopsied cases. *Arch Pathol* **85**:10–17.

Macdonald JB, Seaton A, Williams DA. 1976. Asthma deaths in Cardiff 1963–74: 90 deaths outside hospital. *Br Med J* **1**:1493–5.

Maisch B, Ristic AD, Portig I, *et al.* 2003. Human viral cardiomyopathy. *Front Biosci* **8**:S39–67.

Malik MA. 1973. Emotional stress as a precipitating factor in sudden deaths due to coronary insufficiency. *J Forensic Sci* **18**:47–52.

Malik MO. 1979. Sudden coronary deaths associated with sexual activity. *J Forensic Sci* **24**:216–20.

Mallory GK, White PD, Salcedo-Salgar J. 1939. The speed of healing of myocardial infarction. *Am Heart J* **18**:647–71.

Manion WC. 1966. Myocarditis: a review of the development of the concept. *Med Ann D C* **35**:405–13 passim.

Mann JI. 1984. Familial hypercholesterolaemia: renewed interest in an old problem [editorial]. *Br Med J Clin Res Ed* **289**:396.

Maron BJ. 1983. Myocardial disorganisation in hypertrophic cardiomyopathy. Another point of view. *Br Heart J* **50**:1–3.

Maron BJ. 2002. Hypertrophic cardiomyopathy: a systematic review. *JAMA* **287**:1308–20.

Marshall TK. 1970. Asymmetrical hypertrophy of the heart. *Med Sci Law* **10**:3–6.

Martin AB, Webber S, Fricker FJ, *et al.* 1994. Acute myocarditis. Rapid diagnosis by PCR in children. *Circulation* **90**:330–9.

Martin AM, Jr, Hackel DB. 1966. An electron microscopic study of the progression of myocardial lesions in the dog after hemorrhagic shock. *Lab Invest* **15**:243–60.

Martin AM, Jr, Hackel DB, Entman ML, *et al.* 1969. Mechanisms in the development of myocardial lesions in hemorrhagic shock. *Ann NY Acad Sci* **156**:79–90.

Mittleman MA, Maclure M, Tofler GH, *et al.* 1993. Triggering of acute myocardial infarction by heavy physical exertion. Protection against triggering by regular exertion. Determinants of myocardial infarction onset study investigators [see comments]. *N Engl J Med* **329**:1677–83.

Morild I, Giertsen JC. 1989. Sudden death from asthma. *Forensic Sci Int* **42**:145–50.

Möttönen M. 1970. Myocardial infarction and coronary atherosclerosis in forensic autopsy material. *Med Sci Law* **10**:115–19.

Nayar A, Olsen EG. 1974. The use of the basic fuchsin stain in the recognition of early myocardial ischaemia. *Cardiovasc Res* **8**:391–4.

Noren GR, Staley NA, Bandt CM, *et al.* 1977. Occurrence of myocarditis in sudden death in children. *J Forensic Sci* **22**:188–96.

Northcote RJ, Ballantyne D. 1983. Sudden cardiac death in sport. *Br Med J Clin Res Ed* **287**:1357–9.

Olsen EG. 1987. *Atlas of cardiovascular pathology.* MTP Press, Lancaster.

Osborn GR. 1963. *The incubation period of coronary thrombosis.* Butterworth, London.

Otsuka N, Hara T. 1965. Gross demonstration of the mammalian atrioventricular bundle by a periodic acid-Schiff procedure. *Stain Technol* **40**:305–8.

Park HY, Weinstein SR. 1990. Sudden unexpected nocturnal death syndrome in the Mariana islands [see comments]. *Am J Forensic Med Pathol* **11**:205–7.

Patterson JC. 1938. Capillary rupture with intimal haemorrhage as a causative factor in coronary thrombosis. *Arch Pathol* **25**:474–87.

Paul M, Schulze-Bahr E, Breithardt G, *et al.* 2003. Genetics of arrhythmogenic right ventricular cardiomyopathy – status quo and future perspectives. *Z Kardiol* **92**:128–36.

Paz Suarez-Mier M, Aguilera B. 1998. Histopathology of the conduction system in sudden infant death. *Forensic Sci Int* **93**:143–54.

Pedersen PK. 1980. Determination of potassium/sodium ratio in heart tissue. Evaluation of its use as an index of myocardial ischaemic damage. Comparison with the nitro-BT test. *Forensic Sci Int* **16**:271–80.

Penttilä A. 1980. Sudden and unexpected natural deaths of adult males. An analysis of 799 forensic autopsies in 1976. *Forensic Sci Int* **16**:249–59.

Phillips LH, Whisnant JP, Reagan TJ. 1977. Sudden death from stroke. *Stroke* **8**:392–5.

Piano MR. 2002. Alcoholic cardiomyopathy: incidence, clinical characteristics, and pathophysiology. *Chest* **121**:1638–50.

Piro FR, di Gioia CR, Gallo P, *et al.* 2000. Is apoptosis a diagnostic marker of acute myocardial infarction? *Arch Pathol Lab Med* **124**:827–31.

Plueckhahn VD, Cameron JM. 1968. Traumatic 'myocarditis' or 'myocarditis' in trauma. *Med Sci Law* **8**:177–80.

Preston HV, Bowen DA. 1987. Asthma deaths: a review. *Med Sci Law* **27**:89–94.

Priemer F, Keil W, Kandolf R. 1999. Hydrocution in a case of coxsackie virus infection. *Int J Legal Med* **112**:368–71.

Ramkissoon RA. 1966. Macroscopic identification of early myocardial infarction by dehydrogenase alterations. *J Clin Pathol* **19**:479–81.

Rammer L, Jansson O. 1976. Determination of electrolytes in the myocardium as a tool for the post-mortal diagnosis of recent infarction. *Forensic Sci* **8**:127–30.

Rampazzo A, Beffagna G, Nava A, *et al.* 2003. Arrhythmogenic right ventricular cardiomyopathy type 1 (ARVD1): confirmation of locus assignment and mutation screening of four candidate genes. *Eur J Hum Genet* **11**:69–76.

Randall B. 1980. Fatty liver and sudden death. A review. *Hum Pathol* **11**:147–53.

Reichenbach D, Benditt EP. 1970. Myofibrillar degeneration: a common form of cardiac muscle injury. *Ann NY Acad Sci* **156**:164–76.

Richardson HL, Graupner KI, Richardson ME. 1966. Intramyocardial lesions in patients dying suddenly and unexpectedly. *JAMA* **195**:254–60.

Richardson P, McKenna W, Bristow M, *et al.* 1996. Report of the 1995 World Health Organization/International Society and Federation of Cardiology Task Force on the Definition and Classification of Cardiomyopathies. *Circulation* **93**:841–2.

Rubin E. 1979. Alcoholic myopathy in heart and skeletal muscle. *N Engl J Med* **301**:28–33.

Rump AF, Theisohn M, Klaus W. 1995. The pathophysiology of cocaine cardiotoxicity. *Forensic Sci Int* **71**:103–15.

Rus HG, Niculescu F, Vlaicu R. 1987. Presence of C5b-9 complement complex and S-protein in human myocardial areas with necrosis and sclerosis. *Immunol Lett* **16**:15–20.

Rutenburg AM, Wolman M, Seligman AM. 1953. Comparative distribution of succinic dehydrogenase in six mammals and modification in the histochemical technic. *J Histochem Cytochem* **1**:66–81.

Sahai VB, Knight B. 1976. The post-mortem detection of early myocardial infarction by a simple fluorescent method. *Med Sci Law* **16**:17–20.

Sakurai S, Inoue A, Ohwa M, *et al.* 1995. [Immunohistochemical analysis of adhesion molecules in directional coronary atherectomy specimens.] *J Cardiol* **26**:139–47.

Sandritter M, Jedstadt R. 1958. Triphenyltetrazolium (TTC) als reduktionsindikator zur makroscopischen diagnose des frischen herzinfarktes. *Zent Allg Pathol* **97**:188–9.

Saphir O. 1942. Myocarditis: general review with analysis of 240 cases. *Arch Pathol* **33**:88–99.

Saphir O, Wile SA, Reingold IM. 1944. Myocarditis in children. *Am J Dis Child* **67**:294–312.

Saraste A, Pulkki K, Kallajoki M, *et al.* 1999. Cardiomyocyte apoptosis and progression of heart failure to transplantation. *Eur J Clin Invest* **29**:380–6.

Särkioja T, Hirvonen J. 1984. Causes of sudden unexpected deaths in young and middle-aged persons. *Forensic Sci Int* **24**:247–61.

Saukko P. 1983. Evaluation of diagnostic methods for early myocardial injury in sudden cardiac deaths. *Acta Univ Oul D 107, Anat Pathol Microbiol* **17**:53.

Saukko P, Knight B. 1989. Evaluation of eosin-fluorescence in the diagnosis of sudden cardiac death. *Forensic Sci Int* **40**:285–90.

Saukko P, Lignitz E. 1990. [Sudden death caused by malignant testicular tumors.] *Z Rechtsmed* **103**:529–36.

Schwender LA, Troncoso JC. 1986. Evaluation of sudden death in epilepsy. *Am J Forensic Med Pathol* **7**:283–7.

Seligman AM, Rutenburg AM. 1951. The histochemical demonstration of succinic dehydrogenase. *Science* **113**:317–20.

Sepulchre MA, Fechner G. 1992. [Detection of ischemic myocardial damage.] *Beitr Gerichtl Med* **50**:161–7.

Siboni A, Simonsen J. 1986. Sudden unexpected natural death in young persons. *Forensic Sci Int* **31**:159–66.

Simonsen J, Falk E. 1980. A case of sudden cardiac death in connection with *Salmonella typhimurium* infection. *Forensic Sci Int* **16**:283–7.

Simpson CK. 1947. Pathology of sudden death. *Lancet* **2**:745–7.

Siscovick DS, Weiss NS, Fletcher RH, *et al.* 1984. The incidence of primary cardiac arrest during vigorous exercise. *N Engl J Med* **311**:874–7.

Smith AJ. 1904–5. On the histological behaviour of the cardiac muscle in two examples of organization of myocardial infarct. *Univ Pennsylvania Med Bull* **17**:227–34.

Sokrab TE, Johansson BB, Kalimo H, *et al.* 1988. A transient hypertensive opening of the blood-brain barrier can lead to brain damage. Extravasation of serum proteins and cellular changes in rats subjected to aortic compression. *Acta Neuropathol (Berl)* **75**:557–65.

Song Y, Zhu J, Laaksonen H, *et al.* 1997. A modified method for examining the cardiac conduction system. *Forensic Sci Int* **86**:135–8.

Song Y, Laaksonen H, Saukko P, *et al.* 2001. Histopathological findings of cardiac conduction system of 150 finns. *Forensic Sci Int* **119**:310–17.

Sopher IM. 1974. Myocarditis and the aircraft accident. *Aerosp Med* **45**:963–7.

Speizer FE, Doll R, Heaf P, *et al.* 1968. Investigation into use of drugs preceding death from asthma. *Br Med J* **1**:339–43.

Speizer FE, Doll R, Heaf P. 1982. Observations on recent increase in mortality from asthma. *Br Med J* **285**:1251–5.

Stamer A. 1907. Untersuchungen über die Fragmentation und Segmentation des Herzmuskels. *Beitr Pathol* **42**:310–53.

Stevens PJ, Ground KE. 1970. Occurrence and significance of myocarditis in trauma. *Aerosp Med* **41**:776–80.

Stolley PD, Schinnar R. 1978. Association between asthma mortality and isoproterenol aerosols: a review. *Prev Med* **7**:519–38.

Tada T, Okada H, Okada N, *et al.* 1997. Membrane attack complex of complement and 20 kDa homologous restriction factor (CD59) in myocardial infarction. *Virchows Arch* **430**:327–32.

Teare D. 1958. Asymmetrical hypertrophy of the heart in young adults. *Br Heart J* **20**:1–8.

Thomas AC, Knapman PA, Krikler DM, *et al.* 1988. Community study of the causes of 'natural' sudden death. *Br Med J* **297**:1453–6.

Thomsen H, Held H. 1994. Susceptibility of C5b-9(m) to postmortem changes. *Int J Legal Med* **106**:291–3.

Thomsen H, Held H. 1995. Immunohistochemical detection of C5b-9(m) in myocardium: an aid in distinguishing infarction-induced ischemic heart muscle necrosis from other forms of lethal myocardial injury. *Forensic Sci Int* **71**:87–95.

Tonge JI, O'Reilly MJ, Davison A, *et al.* 1972. Traffic crash fatalities. Injury patterns and other factors. *Med J Aust* **2**:5–17.

Tonge JI, O'Reilly MJ, Davison A, *et al.* 1977. Traffic-crash fatalities (1968–73): injury patterns and other factors. *Med Sci Law* **17**:9–24.

Towbin JA, Bowles NE. 2002. The failing heart. *Nature* **415**:227–33.

Varga M, Zsonda L. 1988. A simple method for postmortem detection of acute myocardial infarction. *Forensic Sci Int* **37**:259–63.

Velisheva LS, Vikhert AM, Shvalev VN, *et al.* 1981. [Sudden cardiac death in alcoholic cardiomyopathy.] *Arkh Patol* **43**:32–7.

Wartmann WB. 1938. Occlusion of the coronary arteries by hemorrhage into their walls. *Am Heart J* **15**:459–66.

Wartmann WB, Hellerstein HK. 1948. The incidence of heart disease in 2000 consecutive autopsies. *Ann Intern Med* **28**:41–50.

Wartmann WB, Souders JC. 1950. Localization of myocardial infarction with respect to the muscle bundles of the heart. *Arch Pathol* **50**:329–38.

Whitehead R. 1965. Isolated myocarditis. *Br Heart J* **27**:220–4.

Willich SN, Lewis M, Lowel H, *et al.* 1993. Physical exertion as a trigger of acute myocardial infarction. Triggers and mechanisms of myocardial infarction study group [see comments]. *N Engl J Med* **329**:1684–90.

Wilson JD, Sutherland DC, Thomas AC. 1981. Has the change to beta-agonists combined with oral theophylline increased cases of fatal asthma? *Lancet* **1**:1235–7.

Wisten A, Forsberg H, Krantz P, *et al.* 2002. Sudden cardiac death in 15–35-year olds in Sweden during 1992–99. *J Intern Med* **252**:529–36.

World Health Organization. 1985. Sudden cardiac death. Report of a WHO Scientific Group. *WHO Tech Rep Ser* **726**:5–25.

Zhang JM, Riddick L. 1996. Cytoskeleton immunohistochemical study of early ischemic myocardium. *Forensic Sci Int* **80**:229–38.

Zugibe FT, Conley TL, Bell P, Jr, *et al.* 1972. Enzyme decay curves in normal and infarcted myocardium. *Arch Pathol* **93**:308–11.

CHAPTER 26

Forensic dentistry for the pathologist

- Bite marks 527
- Identification of the dead from the dentition 532
- Pink teeth 538
- References and further reading 538

Forensic odontology – the application of dentistry to forensic problems – is a discipline in itself and requires special dental expertise not possessed by pathologists qualified only in medicine. It is therefore imperative that, wherever possible, problems involving the teeth and jaws are referred to a dentist at an early stage, preferably at the time of the original autopsy or other examination of the subject.

A number of different circumstances need to be taken into account in this respect, however. First, it has to be accepted that by no means all dentists are either interested or competent in forensic problems. It is the same with pathologists, anatomists or any other specialists, in that the lack of enough motivation and experience can make their participation in legal matters of little value. A forensic odontologist naturally provides the best expertise, as he is professionally involved in the subject and will have training or experience, or both, of dento-legal problems, even though few forensic odontologists are occupied full time in this super-speciality, most being teachers or researchers in some other branch of dental science.

In many parts of the world, there are no forensic odontologists available. In developing countries there may be no forensic dentists at all – or the only expert is in the medical school of the capital city, inaccessible to distant areas. Even in more advanced states, problems of distance and travel may make it impracticable to call an odontologist to examine the body *in situ*. Dental expertise may be made available later, if material is retained for examination for transmission to the expert. In yet other circumstances, many problems of availability, cost and the lack of perceived importance of the case may make it impossible to involve an odontologist at an early stage – or even at all. In all these instances the pathologists or other medico-legal doctor may have no choice but to handle the dental aspects as best he can, either in the initial stages or even throughout the investigation.

This chapter is meant to be nothing more than a guide for the doctor placed in this position and is certainly not intended to encourage pathologists to attempt to replace or dispense with a good odontological opinion. It cannot be sufficiently emphasized that, where the issues are serious, every effort should be made to obtain expert forensic dental assistance. The remainder of this chapter must be looked on solely as a 'first-aid primer' for cases in which the ideal investigation cannot be attained for one reason or another. If no expert dental advice can be obtained at the outset, then the pathologist should do all he can to assemble and preserve both detailed records and physical specimens, which can be examined later by a forensic odontologist, if one can be found further along the investigative pathway.

The assistance that dentistry can render falls into two broad headings:

- the interpretation of bite marks
- personal identification, either individually or in the context of mass disasters.

BITE MARKS

One of the two major interests of forensic odontologists is one that has direct relevance to pathologists in that it concerns the interpretation of trauma to the body surface. For the sake of completeness, however, mention must first be made of bite marks on inanimate objects, usually foodstuffs.



FIGURE 26.1 *Bite mark on skin. The two opposing bruises from the upper and lower dental arches are separated as usual by a gap, as only the front pans of the two arches contribute to the injury.*

This is mainly within the province of forensic science in the sense of 'criminalistics', where dental evidence is used to identify the perpetrators of a crime who happen to have left their teeth marks in some substance left at the scene. This rarely concerns forensic pathologists, except in the rare instance of their being asked by the police to examine an object, such as an apple or piece of cheese, to see if some obvious dental abnormality of a suspect could have caused the unusual bite mark.

The doctor may also be asked how the bite mark may be best preserved until the object can be examined by a forensic odontologist at a later date. Where the substance is 'plastic', such as butter, cheese, lard, wax or chocolate, for instance, it should be stored in a refrigerator to prevent melting or gradual flowing. It should not be deep frozen, as this may cause brittleness and cracking. Forensic science advice should be taken if at all available. Fruit, especially apples, seems prone to be bitten at scenes of crime, and Marshall *et al.* (1974) recommend preservation in Campden solution, a metabisulphite fluid used for fruit bottling. Alternatively, 5 per cent acetic acid in 40 per cent aqueous formaldehyde solution can be used. Ordinary histological formalin is not satisfactory – nor is refrigeration, which allows the fruit to shrivel. Whatever preservation is recommended to the police, the object should be adequately photographed with the film plane at right angles to the bite and a scale placed in the focal plane. If appropriate, swabbing for saliva traces should be carried out (see below) and then the fruit preserved for future examination.

Returning to the human body, bites are relatively common, especially in cases of child abuse and in adult sexual assault. In the former, bites may be anywhere on the infant, favourite sites being the arms, hands, shoulders, cheeks, buttocks and trunk. In the author's (BK) experience almost all bites on small children have been inflicted by the mother, but this is by no means invariable in the generality of child abuse. A common excuse from the parents is that the infant was bitten by another sibling or by the family dog – and occasionally, this explanation may be true. Others may be self-inflicted. It is therefore vital that the bite mark be properly examined to determine whether it is of a size consistent with adult dentition, or whether it is small enough to have come from another child – or is of a different shape, indicative of an animal.

The other common circumstances in which human bite marks occur are rape or other sexual offences. Here the pathologist will need to examine bites as part of the autopsy in a sexual murder – or even sometimes in live victims of an assault, if it is part of his duties to deal with clinical examinations or where no 'police surgeon' or forensic physician is available.

In this type of crime, bites may be sexually orientated or be distributed on any part of the body. Common sites are the breasts and nipples, but the neck, shoulders, thighs, abdomen, pubis and even vulva may be attacked. As noted in the chapter on sexual homicide, care must be taken to recognize that some so-called 'love bites', especially with suction petechiae, may be part of acceptable (if over-enthusiastic) sexual intercourse, but where real damage occurs, especially to breasts and nipples, then a violent or sadistic element is likely.

Bites may also be inflicted on police officers when attempting to arrest resisting offenders. They are also suffered in sporting events, especially football and some forms of wrestling, and during assaults when the victim manages to bite the assailant. In these instances bites may be



FIGURE 26.2 *Bite mark on a nipple during sexual homicide. The injury is too small for any dental matching, but a saliva sample might provide the blood group of the assailant, if he is a secretor.*

inflicted anywhere, but the hands, fingers, nose, forearms, ears and even lips may be the targets.

Some bite marks are self-inflicted; falls onto the face or a fit may cause the tongue and lips to be badly bitten. Other persons deliberately bite themselves, sometimes to fabricate injuries for a variety of motives ranging from gain to psychiatric disorder. Multiple bite marks (especially of the suction type), which are seen on accessible areas of the shoulder and arms, raise the suspicion of self-infliction, especially in older children and teenage girls.

The nature of the bite mark

Though called a 'bite mark', some of the components of the application of the mouth to skin may not be from the actual teeth. The lips can transiently mark the skin if forcibly nipped, especially on children, though the marks are short-lived and rapidly fade in life, not persisting after death unless associated with petechiae. Suction can produce a crop of punctate haemorrhages, either small petechiae or larger ecchymoses merging into a confluent central bruise.



FIGURE 26.3 *Bite marks made during a sexual assault. The upper mark shows no specific features but its position is typical of a sexually orientated bite. The other shows central confluent petechiae and red bruising from suction and tongue pressure. There is a lower semi-circular pale zone corresponding with the lower lip, but the striking feature is the group of linear abrasions at the top of the mark made by the upper incisors dragging across the skin as the jaw is closed. Both bites are surrounded by zones of diffuse bruising.*

A human bite mark may present only a small part of the dental arcade, caused by the front teeth from canine to canine with an almost invariable gap at either side representing the separation of upper and lower jaw. A human bite is near circular or a shallow oval. A deep parabolic arch or a 'U-shape' can only be animal in origin. The teeth may cause clear, separate marks or they may run into each other to form a continuous or intermittently broken line. As time passes, originally clear tooth marks spread out and blur, progressively losing their definition – though abrasions on the skin surface retain their shape until scabbed healing is complete.

Teeth marks may be abrasions, bruises or laceration – or a combination of any two or three. The clarity of a bite mark depends on a number of factors. If the contour of the part bitten is irregular or markedly curved, then only part of the dental arch may contact the tissues. If the bite is forcible, then extensive subcutaneous bruising may spread laterally and blur the outline. If the bite was inflicted many days before, then healing of abrasions and lacerations, and absorption of bruising will leave progressively less detail. Where teeth have been forcibly applied, the typical appearance is of two 'bows' with their concavities facing each other and a gap at each end. Within this may sometimes be suction petechiae, which are often present without teeth marks, in the so-called 'love bite'. They are caused by the firm application of the lips, which form an airtight seal against the skin, then a sucking action reduces the air pressure over the centre. This causes a shower of petechial haemorrhages to appear from rupture of small venules in the superficial layers of the subcutaneous tissues. If forcible, the petechiae are confluent and a frank bruise, or even haematoma develops. Added to this is pressure from the tongue, pushing the tissues against the palate. This type of lesion is most often seen on the side of the neck and on the breasts of women, either in love play or after a sexual assault. They are by no means rare in child abuse, however, and are sometimes self-inflicted. Such a suction lesion must be human in origin and the claim that one is caused by a household pet can be immediately discounted.

Bites may be inflicted by the teeth closing down on a relatively flat skin surface, but there is usually an element of indrawing into the mouth, so that the teeth close down onto a parallel-sided or elliptical block of skin. In sexual bites, especially of the breast or nipple, the tissue may be actually sucked into the mouth before the jaws close upon it. This will naturally affect the shape of the resultant bite mark when the skin is released and flattens out once more.

Occasionally, the bite mark may not be two opposing arches, but more linear in pattern. This is seen especially where the upper incisors are scraped down the skin, leaving a series of parallel tracks, sometimes several centimetres long.

The lower incisors may leave either a curved line of static marks, or a straight or interrupted line below the upper incisor scrapes, as the lower teeth dig in and anchor the skin whilst the upper teeth gouge downwards towards them, during the act of closing the mouth.

The major problem with bite marks is the identification of the perpetrator and hence the problem cannot really be tackled without the expertise of a dentist fully experienced in this specialist task. Unless the dentition has some really characteristic features, especially in the incisors and canines, then a non-dentist is a poor witness if the matter comes to a legal dispute. Some odontologists would claim that a bite mark can only be identified in a negative sense – that is, suspects can be excluded if their dentition is obviously incapable of inflicting the bite mark under investigation, but that no positive match can be claimed. Though many forensic odontologists would dispute this conservative claim, it is probably the best attitude for a pathologist involved in such a problem, unless there is some really spectacular and unique feature in the front teeth of a suspect.

Missing teeth, grossly displaced teeth and substantially damaged teeth may suggest a match with a person – or the mark may be quite inconsistent, which is helpful to the investigators if they eliminate a person or persons, especially in the restricted range of a family in which a child has been abused.

It is probably best for a pathologist to realize his limitations in this field, however, and to confine himself to taking the best physical evidence for later study by a forensic odontologist, where this is at all possible.

The investigation of a bite mark

As stated, every effort should be made to obtain the best evidence for future specialist examination. First, the bite mark should be carefully and fully photographed. If police facilities are to be used, the pathologist – as in other aspects of forensic pathology – should direct them as to the important features required on film. Often such photographers, though otherwise expert in the technical aspects of their craft, do not appreciate the problems that inadequate or inappropriate views can cause – especially at a later date, when experts reviewing the case and lawyers presenting it in court have to rely on photographs without the benefit of having seen the original lesions.

The photographs should be taken from several different angles, but especially from a directly perpendicular viewpoint, with the plane of the film at right angles to that of the lesion. Some police photographers persist in taking tangential shots that foreshorten the true shape. An accurate scale should always be adjacent to the lesion, as close as possible, but not impinging upon it or obscuring any detail.

Bites are often on a curved surface, such as the face, breast or arm, and thus can never be reproduced exactly on a flat surface, as there is bound to be slight foreshortening at the ends, but several views at slightly different angles can overcome this problem. Small lens apertures and short focal lengths will obviate the blurring that results from the lesion curving out of the focal plane. Too short a focal length will itself produce image distortion.

The lighting is important, as perpendicular lighting may lead to a flat rendering with no capture of detail. Side



FIGURE 26.4 *A clear bite mark on the shoulder, a few days after infliction. This was from political abuse of human rights, there also being linear bruises on the shoulder and back from beating with a hose-pipe.*

lighting may throw small irregularities into relief, especially if there are tooth indentations in the skin. Both monochrome and colour photographs should be taken, with particular attention to sharp focus and correct exposure. The use of infrared-sensitive film has been recommended to reveal occult bruising, but it also appears to demonstrate artefacts. The lesion should almost fill the camera frame in some shots to capture as much detail as possible, either by short lesion-to-camera distance or the use of long-focus lenses. More general, wider shots should also be taken, however, to orientate the bite mark in relation to anatomical landmarks. During photography, care should be taken not to heat up the skin by the close proximity of high-power tungsten lamps. These should be placed at a distance or used only for short periods. Flash illumination will obviate this danger of heating the skin, which can distort the bite mark.

When photography is completed, swabs of the bite should be taken to try to recover saliva. Though not often successful, this technique can occasionally be vitally important in helping to identify or exclude the assailant, if he or she is one of the 80 per cent of people who are 'secretors', that is, who exude their blood-group substance in their saliva. Plain cotton-wool swabs are gently rubbed onto the bite – some experts recommend slightly moistening them first with water or saline. They should then be deep frozen unless sent straight to the serology laboratory.

Following photography and swabbing, there is usually little more that the pathologist can do in the absence of a dentist. If facilities are available and someone has the expertise, an impression of the bite can be made. This consists of laying a plastic substance over the bite mark, which then hardens, so as to produce a permanent negative cast of the lesion. It is usually made with a rubber- or silicone-based medium containing a catalytic hardener. Less satisfactory substances are water-based pastes, such as plaster of Paris, which are put on wet and allowed to dry before removal. These have the disadvantage of potential damage to the actual bite, if that is required for further evidential examination. Though it is unlikely that a pathologist will be able to carry out these procedures, it may be that a non-forensic dentist or a forensic scientist used to making casts of other evidence may be able to make satisfactory impressions that can then be preserved for later examination by an odontologist.

After autopsy, it is also possible for the whole area of skin carrying the bite to be removed and preserved in formalin for future examination. The shrinkage and distortion that are virtually inevitable, however, make these specimens of limited value for detailed tooth matching, though if good photographs with accurate scales are also available, they may be a useful addition to the dental evidence.

It is recommended that, as with all bruises and abrasions, the body be re-examined a few days after the first autopsy, as the appearances may be markedly enhanced. In a bite mark, faint or even absent original lesions may become more prominent, or even appear for the first time a day or two after death. The removal of skin carrying the lesion should be delayed if it is wished to see if this enhancement will occur, unless climatic conditions or lack of refrigeration would make this delay undesirable.

Matching the bite mark with the suspect's dentition

For a pathologist, this is such a specialist enterprise that it would rarely be attempted, unless there was no prospect whatsoever of a forensic dentist being available, even at a later date. As mentioned earlier, unless there is a striking dental feature in the bite mark or in the teeth of the suspect, the best that can be done is to try to exclude a limited number of potential assailants on the basis of lack of correspondence of their dentition with the bite mark. If neither mark nor teeth show any particular distinctive appearances, then even this should be avoided, without expert dental opinion. Where circumstances dictate that only the pathologist will ever be available to help the investigation, he should confine himself to the following routines:

- The teeth of those who are either suspected by the police or who had access to the victim should be examined. In most jurisdictions it is vital that fully informed consent should be obtained from the person beforehand. The doctor must explain what he intends doing and the reason for doing it. It must be made clear that this is to be done for the purposes of a legal investigation and that any information gained might be used as evidence – and that it is not related to diagnosis or treatment for the subject's own welfare.

- Any refusal must be a bar to any further action. Where children are concerned, usually in the setting of child abuse, the consent of the fully informed parents or guardian must be obtained. All such consent is preferably obtained in writing and many police forces have special forms for the purpose. If not written, then a dubious second best is getting oral consent; at least one witness to this must be obtained, if possible from independent persons other than relatives or police officers.
- With consent, the dentition is then examined and the following points determined and recorded by diagram and writing. Photographs should also be taken if there is an issue of possible correspondence between the teeth and the bite – or where exclusion is legally important.
  - The presence of full or partial denture – and, if so, were they worn at the time of the incident?
  - The number of teeth in upper and lower jaw.
  - A charting of any missing teeth, especially incisors and canines.
  - An estimate of the bite overhang, or whether there is edge-to-edge occlusion or an undershoot projection of the lower teeth.
  - Recording of any broken teeth or teeth with significant individual abnormalities; these must be charted and described.
  - A record of any irregularity or marked variation in the cutting edge profile of any front teeth.
  - An evaluation of the size and prominence of any teeth, especially in the canines and incisors and any developmental abnormalities, such as an extra interposed front tooth.
  - Recording of any abnormality in the orientation of any tooth or teeth, such as twisting (rotation) in the anteroposterior tilting or double row of teeth. Gaps and irregular spacing are vital factors.

Though it is unlikely that a pathologist will have either the expertise or materials to make an impression of the bite, this might be attempted if no dental assistance of any kind is available – though the aid of a local dental practitioner would be useful in obtaining a wax or other bite registration. If this is impossible, then a bite impression into any available plastic substance might be attempted. The use of such substances as modelling clay, Plasticine, or beeswax might be better than nothing if some unique feature required demonstration. Finally, whether it be from visual inspection of the teeth or from comparison with a cast, an attempt should be made to compare the characteristics of the bite mark with the dentition of the suspect or suspects. It is assumed that an animal bite will have already been excluded by this stage.

This comparison can be performed in various ways, different odontologists having their own techniques. Where marked abnormalities exist in the teeth, these may be present in the bite mark if the affected teeth happen to have registered in the lesion. Some forensic dentists prefer to match photographs of the mark with photographs or tracings of the teeth, the former being printed to a 1:1 magnification. Tracings can be made from positive casts of a bite impression, inking the cutting edges of the front teeth and transferring these to transparent sheets, which can then be laid over the photographs to determine correspondence. Others use a negative photograph of the teeth laid over a positive photograph of the bite, again ensuring exact correspondence of magnification.

In a bite mark it is said that a tooth impression is better evidence than an absent mark – in other words, the presence of a tooth mark means that the tooth was actually in the jaw, whereas a gap in the injury could either mean that the tooth was missing or merely that the occlusal edge had not marked the skin, perhaps because of slight shortening, unevenness or wear. In all matching procedures between a bite mark and the suspect teeth, allowance must be made for distortion of the skin surface during the biting process and the angle of attack of the teeth. Again it is emphasized that exclusion is probably a much safer exercise than an allegation of positive matching, unless there is some unique feature in the dentition. Unlike fingerprints, fewer points of definite correspondence are required to claim correspondence. This applies only in the hands of experts, where the number needed for a confident identification depends on the strength of the idiosyncratic features, but may be inferred from three or four identical points.

In practice, it is the six upper and six lower front teeth that give the most information. The canines may provide particular help when prominent and pointed. Premolars and molars are rarely useful, as might be expected from their lower profile and posterior position in the jaws.

IDENTIFICATION OF THE DEAD FROM THE DENTITION

The major contribution of forensic odontology is in the field of identification, especially in mass disasters, such as aviation and marine catastrophes. In air crashes, dental investigation is the most successful single procedure leading to identification of mutilated and burned bodies, as the passenger manifest lists provide a circumscribed population for whom dental records can be obtained in the majority of cases. In such disasters the involvement of dentists is imperative, but the size of the subject is far too large to be attempted in a book of this nature.

Apart from mass casualties, forensic odontology is frequently used in problems of individual identity that are the direct concern of the forensic pathologist, as accident, suicide and murder form the majority of such unidentified bodies.

As with skeletal remains (of which dental evidence is part), discussed in Chapter 3, there are two prime avenues of investigation:

- general or reconstructive identity, which attempts to classify the unknown person by age, sex and race
- comparative methods, which confirm or exclude the personal identity of the individual against ante-mortem dental records.

Once again, the pathologist can only act for the dentist in a 'second-best' way, when no forensic odontological expertise is available. Unlike bite marks, the material is likely to be much more permanent and, wherever possible, the pathologist should retain photographs, chartings and even the actual dentition against the time when expert dental opinion might become available. When time presses in a criminal inves-tigation, however, or where no dental help is ever likely to be forthcoming, then the pathologist has to do the best he can, though many special techniques such as radiology or tooth sections may be quite beyond his capabilities.

General or reconstructive identity

Unlike skeletal remains, the human origin of dental material is rarely in doubt. In badly decomposed or skeletalized bodies the jaws usually survive intact, though in dry skeletons, teeth may become loose and fall out, especially the single-rooted canines and incisors.

Even in fragmented bodies and skeletons, the jaw remnants and teeth are readily recognizable, even by lay persons. Where teeth have dropped out and been recovered independently of a body, they are still usually recognizable as human, as opposed to most domestic or farm animals. In countries where large primates exist, there may be some confusion, but this is a rare problem.

Having established the human origin, the next determination is sex and here teeth have a poor discriminating value, though the intact jaw is more helpful, as discussed in Chapter 3. Male teeth are usually larger, but this is generally unhelpful. The difference in size between the upper lateral and upper central incisors is often greater in women, the male incisors being more equal in size. The female canines are usually smaller and more pointed relative to the male, more especially in the mandible than the maxilla. Girl's teeth tend to calcify and erupt earlier than boys. If the skeletal age is known, then more advanced tooth eruption in young persons is an indication of being female, though in these circumstances there are usually far better indicators of sex available elsewhere in the skeleton. The mandibular first molar often lacks a fifth cusp in the female, which is almost always present in the male. Extraction of pulp tissue from a tooth, even up to many months after extraction or death, can provide material for fluorescent staining for the female intranuclear F-body, as described in Chapter 3, but this has now been superseded by sex determination via DNA, if recoverable from the pulp.



FIGURE 26.5 *Upper dental arch of a skeleton found buried on a small island in the Bristol Channel. The central incisors are 'shovel-shaped' and have a depressed groove on their posterior surface. This strongly suggests that the deceased was of mongoloid race.*

Race is also a difficult criterion to determine from teeth. The best-known feature is the 'shovel-shaped' upper central incisors of Mongoloid races, first described in Leipzig by Muhlreiter in 1870. The posterior surfaces of these teeth have a depression centrally, with two marginal bars, causing the back of the tooth to appear like a coal shovel with turned-up edges. The feature is found mainly amongst Chinese, Mongols, Eskimos and Japanese, but is also found amongst non-Mongoloid races in lesser numbers. Some 91 per cent of Chinese, Japanese and Tibetans have such teeth, 95 per cent of Native Americans, 84 per cent of Eskimos, 46 per cent of Palestinian Arabs – and 90 per cent of Finns. It is rare amongst Negroids and Australian Aboriginals. In Caucasian races, the lateral incisors in the upper jaw are usually smaller than the central, especially in women, a feature absent or less marked in Negroid or Mongoloid races. Caucasians also have long pointed canine roots, a feature not seen in Mongoloids. Enamel pearls, small nodules of enamel on the tooth surface, are much more frequent in Mongoloid teeth. Small nodules on the lingual surface of maxillary molars, called 'Carabelli's cusp', are most common in Caucasian races and rare in the other major racial groups. The condition of bull-tooth or 'taurodontism' is most common in Mongoloid peoples: here the pulp cavity of molars is wide and deep, and the roots are fused and bent. A congenital lack of the third upper molar is most common in Mongoloids, but can occur in any race. Negroid races tend to have large teeth and often have more cusps on their molars, even up to eight, with two lingual cusps on the mandibular first premolars as an additional common finding.

The age of the person is one of the most useful findings disclosed by the teeth, especially in the first two decades of life. The sequence of deciduous or 'milk' teeth is well known, overlapping the appearance of the permanent dentition, shown in Figure 26.6. This is only an average timetable, however, and is modified by several factors, such as sex, race and climate. Again, dental expertise is needed to refine the accuracy of such estimations. The determination of age from fetal teeth is also a matter for embryologists or dentists with specialized knowledge of this period. After the third molar has erupted in the third decade of life, then age determination becomes much more difficult. Much research has been expended in forensic odontology and the name of Gustafson (see references and further reading) is well known in this respect. His criteria for age in adult life comprised six factors:

- occlusal attrition of the tip of the tooth
- secondary dentine deposition in the apex of the pulp cavity
- apical migration of the attachment of the periodontal membrane
- increase in root transparency – the best single indicator
- root resorption
- accumulation of cementum around the root.

This method, as later modified by Johanson (1971), is said to give an age accuracy within 5 years either side of the true age.

It seems pointless to rehearse these methods in advice to pathologists, however, as specialized techniques, equipment and knowledge are needed for these procedures. The standard textbooks on forensic odontology and original papers should be consulted for the details. Returning to general features of age, obvious pointers are the state of the teeth in respect


(a)
Lower – 6–8 months
Upper – 9–12 months
Central incisor
Lateral incisor
Upper – 18–24 months
Canine
18–24 months
12–24 months
First molar
2–3 years
Second molar
(b)
Male
Female
6–7–8
6–7–8
7–8–9
C1
C1
7–8–9
L1
L1
10–11–13
10–11–12
C
C
9–10–12
8–10–11
1PM
1PM
10–11–13
2PM
2PM
9–11–12
5–6–7
1M
Upper
1M
5–6–7
11–13–14
2M
2M
11–12–14
17–21–25
3M
3M
17–21–25
Male
Female
6–6–7
5–6–7
7–8–8
C1
C1
6–7–8
L1
L1
10–11–12
C
C
9–10–11
9–11–12
9–10–12
1PM
1PM
10–11–13
2PM
2PM
9–11–12
5 – 6 – 7
1M
Lower
1M
5–6–7
11–12–13
2M
2M
10–12–13
17–21–25
3M
3M
17–21–25

FIGURE 26.6 *(a) Dates of eruption of deciduous teeth (average times). (b) Times of eruption of permanent teeth; three dates are shown (years) for early, average and late eruption, rounded to the nearest year.*



FIGURE 26.7 *Severe occlusal attrition in a jaw from the early nineteenth century. The crowns are worn down to expose the dentine by a rough diet that probably contained stone dust in the flour from contemporary milling methods.*

of wear, hygiene and colour, which may deteriorate with advancing age. Much depends upon the care with which they have been maintained, however, though marked occlusal attrition tends to go with increasing age, unless a rough diet has accelerated the wear. In Western Europe, gross occlusal attrition, sometimes down to gum level, is seen in old skeletal material. This usually indicates that the bones and teeth came from someone alive in the mid-nineteenth century or earlier, before modern milling methods removed abrasive stone dust from flour.

Edentulous jaws also suggest advancing age but, especially in former years before more conservative dentistry, even young adults often had total tooth clearances for caries. Once the teeth have gone, there is a general atrophy of the alveolar margins, but this is a poor criterion of age because of the great variability in the time when teeth are lost.

Newer techniques for age estimation include the variation with age of racemization of amino acids, especially aspartic acid, but this is a very specialized area.

Comparative identification from teeth

Establishing personal identity requires the matching of observed features with pre-existing dental records, the latter almost always obtained from previous diagnostic and therapeutic surveillance. For this method to be applied, there must be:

- Some collateral evidence to indicate either who the unknown body might be, so that records can be sought.
- Alternatively, a circumscribed population must be searched for records that may match the unknown. Such a population may be the known passengers on an aircraft or ship or a cohort of missing persons maintained on some register. It is manifestly impossible to search a large population, such as a whole country or even a city. Attempts were made in Britain to computerize dental records from the National Health Service so that a wide search could be made, but the completeness and quality of data was such that the scheme was found to be impracticable.
- The unknown person must have had dental attention in the past. The dentist or hospital must be known; the records must be traceable and, when found, must contain sufficient clinical information to provide adequate identifying features. The recovery of dental radiographs is a most useful adjunct. Unfortunately, these criteria are not always satisfied.

The dental records are needed to provide a description of the dentition and jaws at a date as late as possible before the finding of the body. Work may have been done on the deceased during life since the last record was made, if the person had been treated elsewhere and the information not recorded. Where a record does not conform to the dental state of a body who was expected to be a match, it is obvious that such discrepancies can be of two types:

1. If the record indicates some condition that is irreversible but which does not exist in the body, then that excludes matching. For example, if the record states that certain teeth have been extracted, yet they are still present in the jaws, then any hope of correspondence must be abandoned.
2. If fillings are present in the teeth, which are not shown in the records, then these may have been made later and not recorded. Of course, no discrepancies of point 1 must be present for those of point 2 to be acceptable.

Charting the teeth

In the absence of a forensic odontologist, the next best person to record the state of dentition of a dead body would naturally be a dental practitioner, to whom this task would be an everyday routine. The chart made by him could then be used for future reference in any identification procedure. This chapter is concerned with the imperfect yet sometimes inevitable circumstance where the pathologist is the only person available. Unfortunately, there are a host of different methods of charting the contents of the jaws, and, in spite of sustained efforts, no universal internationally accepted system has yet been adopted. For our purposes, any careful record of the number, position and state of the teeth made by a pathologist can be converted into whatever system of charting is required at a later stage.

Two main methods of recording data are in use: the first is a diagrammatic chart commonly used in large dental services such as the British National Health Service, seen in Figure 26.8. The other system uses a more pictorial representation of the teeth, so that all features can be recorded in a more exact topographical manner. Both systems, as well as many variants, have a notation which describes the position of the teeth, almost always in four quadrants, right upper, left upper, right lower and left lower. Unfortunately, there is considerable variation in the sequence of numeration, especially where the transition points from left to right, and from upper to lower are concerned, these being confusing and often not interchangeable. The pathologist need not concern himself too much with this problem, as his graphic representation can always be turned into whatever system of numeration is required at a later time. For example, if an unknown body has its teeth charted on one



FIGURE 26.8 *Two of the many types of chart used for recording dental characteristics. The upper is the 'Odontogram' designed for Interpol. The chart displays each surface of each tooth, including the deciduous teeth. The lower chart is that used in the British National Health Service, which is a simpler design. In both charts the buccal aspects are at the top and bottom and the lingual sides of the teeth face each other centrally.*

of the common diagrams and later the dental records of a potential 'identitee' become available, the chart can be transposed into the same system as the clinical records. The notation derived from this can then be transmitted by telephone, telex, fax or other form of communication, if the records are not available at the place where the body lies. This is particularly important in transportation fatalities such as air crashes, where the home base of the victims may be far removed from the scene of death.

On the diagrammatic or anatomical charts, each tooth is represented by a pictorial symbol that provides the same number of tooth surfaces as those on the same teeth in the mouth. The incisors and canines have four surfaces represented, while the premolars and molars have an additional facet, the occlusal surface. On these diagrams, the positions of fillings, crowns, caries and damage are marked, and, of course, missing teeth are deleted.

In charting the teeth, the pathologist needs good access to the mouth and this presents the first problem. Rigor mortis in a relatively fresh cadaver may make it impossible to open the mouth without great effort. Excessive force should not be used, especially leverage with a metal instrument, because of the danger of damaging the teeth. Where the rigor cannot be broken by sustained firm pressure on the chin – or where time prevents waiting for rigor to pass off – it may be necessary to extend the autopsy incision into a neck 'V' and dissect the skin off the lower part of the face, to gain access to the masseter and temporalis muscles, which can then be divided above their insertion into the mandible, to allow the jaw to become mobile. Care must be taken not to disfigure the face during this procedure.

When the body is decomposing, no rigor will be present. If badly rotted, then cosmetic considerations will not apply and more radical removal of the jaws may need to be performed. The same holds for badly burned bodies, where heat contraction of the facial muscles may make it impossible to open the jaws without dissecting away tissues. In both these instances, where identity is a prime consideration, both mandible and maxilla may need to be removed for retention and later examination. The mandible can be disarticulated at the temporomandibular joints and removed intact. The lower maxilla, comprising the tooth-bearing jaw, the palate and the inferior part of the facial skeleton, can be removed after the mandible has been taken. This is done by sawing horizontally across the maxilla at the level of the lower margin of the nasal aperture, taking care to saw above any tooth



FIGURE 26.9 *Use of dentures to identify a decomposed body from the sea. Some dental prostheses carry makers' or patients' record numbers embedded in the plate material. The loss of tissue around eyes and mouth was caused by marine predators. The cut throat was made by a nylon hawser that threw this ship's officer overboard.*

roots. After photography and charting, the jaws can be preserved in formalin or a freezer. With modern serological and DNA identification techniques, the need to keep some unfixed tissue for serology and other investigations should be borne in mind. Naturally, the presence of any full or partial dentures or any other type of dental prosthesis will have been recorded and the prosthesis carefully retained for examination. Even edentulous persons may show signs of having worn dentures by the presence of pressure marks on gums or palate. Wherever possible, radiographs should be taken of the head of an unidentified body (as discussed in Chapter 3) where non-dental considerations apply, such as craniometry or frontal sinus visualization. At the same time, the radiographs may show unexpected foreign bodies in the head and some of these may have unique dental importance, such as broken drill, broken roots or congenital abnormalities, which may be matchable with clinical films, or a note in the ante-mortem records. Radiography has a special place in forensic odontology, but specialist techniques and knowledge are likely to lie outside the abilities of a pathologist.

When, by whatever means necessary, the dental arches have been made available for examination, the following features are sought and recorded on the chart:

- Extractions – whether recent or old – should be noted from the condition of the socket.
- Fillings – their number, position and composition.
- Artificial teeth – gold, porcelain or stainless steel.
- Other prosthetic work in the mouth, such as bridgework or braces.
- Crowned teeth.
- Broken teeth.
- Pathological conditions in teeth, jaws or gums.
- Congenital defects such as enamel pearls, Carabelli's cusps or ectopic teeth.
- Malpositioned teeth – rotated or tilted for example.
- The general state of care and hygiene including caries, plaque, tobacco staining and gingivitis.
- Racial pointers, such as shovel-shaped upper central incisors or multi-cusped molars.

When all available information has been discovered and entered on the chart, the process of comparison with any ante-mortem records can be made. Much will depend on the quality and the date of these records, which are frequently less detailed and exact than the autopsy charting. Allowance must be made for the clinical records to be substantially out of date on occasions, as mentioned earlier. The process of matching is again really the work of an experienced dentist, but the major task of checking the above list against the previous records can be carried out adequately in respect of missing teeth, filling, prostheses and major trauma and other anomalies.

Anything on the clinical chart that is not represented in the actual jaws almost always excludes a matching – fillings cannot go away and extracted teeth cannot return, even though some remarkable feats of dental treatment now exist. The degree of correspondence that is acceptable for a positive match is a matter of common sense, and naturally other non-dental aspects must be taken into account – it is useless trying to claim a match on a woman's dental characteristics if other information clearly indicates that the missing person was a man. Finally, and at the risk of being over-repetitive, it must again be emphasized that, though the pathologist may be a collector of data and physical evidence, where the issues



FIGURE 26.10 *A short-cut in excluding homicide. A skeleton was found buried in a suburban garden. Initial suspicions were allayed when the ramus of the mandible was seen to carry a bronze wire for attaching a spring to suspend the jaw from the skull. Police enquiries confirmed that the house had previously belonged to a member of the medical school teaching staff.*



FIGURE 26.11 *A mandible from a skeletalized body found in suspicious circumstances. Identity was established solely from dental features, such as the gold bridge and acrylic tooth on the right side of the jaw and the numerous amalgam fillings. Comparison of dental radiographs obtained from a hospital confirmed the correspondence. The jaw, with the prominent square symphyseal region, is typically male.*

are vital (as in a homicide investigation), every effort must be made for the material to be evaluated by a forensic odontologist, even if the details have to be sent by air mail to another country.



FIGURE 26.12 *Pink teeth. The jaw came from a decomposed body dumped in the countryside after death from narcotic overdose. No carbon monoxide was present in the body, the pinkness being caused by haemoglobin products staining the dentine. (Reproduced by kind permission of Professor David Whittaker.)*

PINK TEETH

At autopsy on putrefied bodies, the teeth are sometimes seen to be a marked pink colour, especially near the gum line. Considerable research has been carried out into this interesting phenomenon and it is clear that the colour is the result of the dentine being stained by haemoglobin products. It was once thought that carbon monoxide played a part in the coloration, but this has been disproved. Claims that the phenomenon is a pointer to an asphyxial death can be discounted, though possibly a very 'congestive' mode of death – albeit a very non-specific condition – encourages pinkness because of retention of blood in the pulp.

REFERENCES AND FURTHER READING

Ajmal M, Mody B, Kumar G. 2001. Age estimation using three established methods. A study on Indian population. *Forensic Sci Int* **122**:150–4.

Bernitz H. 2001. Identification by means of denture marking. *SADJ* **56**:368–9.

Bernitz H, Kloppers BA. 2002. Comparison microscope identification of a cheese bitemark: a case report. *J Forensic Odontostomatol* **20**:13–16.

Borrman HI, DiZinno JA, Wasen J, *et al.* 1999. On denture marking. *J Forensic Odontostomatol* **17**:20–6.

Bowers CM, Johansen RJ. 2002. Photographic evidence protocol: the use of digital imaging methods to rectify angular distortion and create life size reproductions of bite mark evidence. *J Forensic Sci* **47**:178–85.

Bowers CM, Johansen RJ. 2002. Digital imaging methods as an aid in dental identification of human remains. *J Forensic Sci* **47**:354–9.

Brkic H, Strinovic D, Kubat M, *et al.* 2000. Odontological identification of human remains from mass graves in Croatia. *Int J Legal Med* **114**:19–22.

Brondum N, Simonsen J. 1987. Postmortem red coloration of teeth. A retrospective investigation of 26 cases. *Am J Forensic Med Pathol* **8**:127–30.

Cameron JM, Sims BG. 1973. *Forensic dentistry.* Churchill Livingstone, Edinburgh.

Commission on Armed Forces Dental Services. 1967. *Identification by dental means*, Vol. Redaction I–IV. Federation Dentaire International, Paris.

DeVore DT. 1977. Radiology and photography in forensic dentistry. *Dent Clin North Am* **21**:69–83.

Du Chesne A, Benthaus S, Brinkmann B. 1999. Manipulated radiographic material – capability and risk for the forensic consultant? *Int J Legal Med* **112**:329–32.

English WR, Robison SF, Summitt JB, *et al.* 1988. Individuality of human palatal rugae. *J Forensic Sci* **33**:718–26.

Fearnhead RW. 1961. Facilities for forensic odontology. *Med Sci Law* **1**:273–6.

Fielding CG. 2002. Nutrient canals of the alveolar process as an anatomic feature for dental identifications. *J Forensic Sci* **47**:381–3.

Forbes G, Watson AA. 1975. *Legal aspects of dental practice.* John Wright, Bristol.

Furness J. 1976. Positive dental identification. *Int J Forensic Dent* **3**:2–5.

Furness J. 1981. A general review of bite-mark evidence. *Am J Forensic Med Pathol* **2**:49–52.

Garn SM. 1958. The sex difference in tooth calcification. *J Dent Res* **37**:561–4.

Glass RT, Jordan FB, Andrews EE. 1975. Multiple animal bite wounds: a case report. *J Forensic Sci* **20**:305–14.

Gustafson G. 1950. Age determination on teeth. *J Am Dent Assoc* **41**:45–50.

Gustafson G. 1966. *Forensic odontology.* Staples Press, London.

Haines DH. 1972. Racial characteristics in forensic dentistry. *Med Sci Law* **12**:131–8.

Hanihara K. 1967. Racial characteristics in the dentition. *J Dent Res* **46**:923–6.

Harvey W. 1976. *Dental identification and forensic odontology.* Henry Kimpton, London.

Heliman H. 1929. Racial characteristic in the human dentition. *Am Phil Soc* **67**:157–74.

Hurme VO. 1948. Standards of variation in the eruption of the first six permanent teeth. *Child Dev* **19**:213–22.

Ito S. 1976. Age determination based on tooth crown. *Int J Forensic Dent* **3**:9–14.

Jakobsen JR, Keiser Nielsen S. 1981. Bite mark lesions in human skin. *Forensic Sci Int* **18**:41–55.

Johanson G. 1971. Age determination from human teeth. *Ondontol Rev* **22**(Suppl):22–8.

Kemkes-Grottenthaler A. 2001. The reliability of forensic osteology – a case in point. Case study. *Forensic Sci Int* **117**:65–72.

Kolltveit KM, Solheim T, Kvaal SI. 1998. Methods of measuring morphological parameters in dental radiographs. Comparison between image analysis and manual measurements. *Forensic Sci Int* **94**:87–95.

Koshy S, Tandon S. 1998. Dental age assessment: the applicability of Demirjian's method in South Indian children. *Forensic Sci Int* **94**:73–85.

Lund H, Mornstad H. 1999. Gender determination by odontometrics in a swedish population. *J Forensic Odontostomatol* **17**:30–4.

Luntz L, Luntz P. 1973. *Handbook for dental identification: techniques in forensic dentistry.* Lippincott, Philadelphia.

Maples WR. 1978. An improved technique using dental histology for estimation of adult age. *J Forensic Sci* **23**:764–70.

Marshall W, Potter J, Harvey W. 1974. Bite marks in apples – forensic aspects. *Criminol* **9**:21–6.

Masters PM. 1986. Age at death determinations for autopsied remains based on aspartic acid racemization in tooth dentin: importance of postmortem conditions. *Forensic Sci Int* **32**:179–84.

McKenna CJ, Haron MI, Taylor JA. 1999. Evaluation of a bitemark using clear acrylic replicas of the suspect's dentition – a case report. *J Forensic Odontostomatol* **17**:40–3.

Meredith HV. 1946. The order and age of eruption of the deciduous dentition. *J Dent Res* **25**:43–5.

Mertz CA. 1977. Dental identification. *Dent Clin North Am* **21**:47–67.

Metzger Z, Buchner A. 1980. The application of tetracyclines in forensic dentistry. *J Forensic Sci* **25**:612–18.

Miles AEW. 1963. Dentition in the estimation of age. *J Dent Res* **42**:253–5.

Muller M, Lupi-Pegurier L, Quatrehomme G, *et al.* 2001. Odontometrical method useful in determining gender and dental alignment. *Forensic Sci Int* **121**:194–7.

Myers JC, Okoye MI, Kiple D, *et al.* 1999. Three-dimensional (3-D) imaging in post-mortem examinations: elucidation and identification of cranial and facial fractures in victims of homicide utilizing 3-D computerized imaging reconstruction techniques. *Int J Legal Med* **113**:33–7.

Nambiar P, Carson G, Taylor JA, *et al.* 2001. Identification from a bitemark in a wad of chewing gum. *J Forensic Odontostomatol* **19**:5–8.

Ogino T, Ogino H, Nagy B. 1985. Application of aspartic acid racemization to forensic odontology: postmortem designation of age at death. *Forensic Sci Int* **29**:259–67.

Ohtani S. 1994. Age estimation by aspartic acid racemization in dentin of deciduous teeth. *Forensic Sci Int* **68**:77–82.

Ohtani S, Yamada Y, Yamamoto I. 1998. Improvement of age estimation using amino acid racemization in a case of pink teeth. *Am J Forensic Med Pathol* **19**:77–9.

Pretty IA, Smith PW, Edgar WM, *et al.* 2002. The use of quantitative light-induced fluorescence (QLF) to identify composite restorations in forensic examinations. *J Forensic Sci* **47**:831–6.

Ritz-Timme S, Cattaneo C, Collins MJ, *et al.* 2000. Age estimation: the state of the art in relation to the specific demands of forensic practice. *Int J Legal Med* **113**:129–36.

Rogers SL. 1988. *The testimony of teeth: forensic aspects of human dentition.* Thomas, Springfield.

Ruddick RF. 1974. A technique for recording bite marks for forensic studies. *Med Biol Illus* **24**:128–9.

Sheasby DR, MacDonald DG. 2001. A forensic classification of distortion in human bite marks. *Forensic Sci Int* **122**:75–8.

Sims BG, Grant JH, Cameron JM. 1973. Bite-marks in the 'battered baby syndrome'. *Med Sci Law* **13**:207–10.

Sognnaes RF. 1980. Hitler and Bormann identifications compared by postmortem craniofacial and dental characteristics. *Am J Forensic Med Pathol* **1**:105–15.

Solheim T. 1980. Unusual dental forensic cases in Norway. *Am J Forensic Med Pathol* **1**:197–203.

Solheim T. 1993. A new method for dental age estimation in adults. *Forensic Sci Int* **59**:137–47.

Stevens PJ, Tarlton SW. 1966. Medical investigation in fatal aircraft accidents. The role of dental evidence. *Br Dent J* **120**:263–70.

Sweet D, Shutler GG. 1999. Analysis of salivary DNA evidence from a bite mark on a body submerged in water. *J Forensic Sci* **44**:1069–72.

Tramini P, Bonnet B, Sabatier R, *et al.* 2001. A method of age estimation using raman microspectrometry imaging of the human dentin. *Forensic Sci Int* **118**:1–9.

Valenzuela A, Martin-de las Heras S, Marques T, *et al.* 2000. The application of dental methods of identification to human burn victims in a mass disaster. *Int J Legal Med* **113**:236–9.

Whittaker D, McRonald R. 1989. *Atlas of forensic dentistry.* Wolfe Medical Publications, London.

Whittaker DK, Brickley MR, Evans L. 1998. A comparison of the ability of experts and non-experts to differentiate between adult and child human bite marks using receiver operating characteristic (ROC) analysis. *Forensic Sci Int* **92**:11–20.

Whittaker DK, Richards BH, Jones ML. 1998. Orthodontic reconstruction in a victim of murder. *Br J Orthod* **25**:11–14.

Wright FD. 1998. Photography in bite mark and patterned injury documentation – part 2: a case study. *J Forensic Sci* **43**:881–7.

Xu XH, Philipsen HP, Jablonski NG, *et al.* 1991. Preliminary report on a new method of human age estimation from single adult teeth. *Forensic Sci Int* **51**:281–8.

Yaacob H, Nambiar P, Naidu MD. 1996. Racial characteristics of human teeth with special emphasis on the mongoloid dentition. *Malays J Pathol* **18**:1–7.

CHAPTER 27

Poisoning and the pathologist

- The concept of the fatal dose 541
- Variations in published fatal poison concentrations 542
- The autopsy in suspected poisoning 543
- Poisoning deaths in hospital 543
- The collection of autopsy samples for toxicological analysis 543
- Containers for toxicology samples 545
- Preservatives in samples 545
- The site of sampling for toxicological analysis 546
- The technique of obtaining autopsy samples 547
- References and further reading 550

Toxicology has a number of different aspects and, in such a huge subject, various specialists have different interests. The clinical toxicologist is most concerned with diagnosis and treatment of the living patient; the analytical toxicologist has the complex task of laboratory investigation; and the pathologist is concerned with evaluating poisons as a cause or a contribution to death. Though obviously linked, these various aspects are substantially different and few people can claim to be proficient in all three. As far as the pathologist is concerned, his main task is to exclude or confirm other non-toxic factors in the death. He has then to collect suitable samples for analysis and, when the laboratory results are available, to interpret them in the light of his knowledge of the history, clinical features and autopsy appearances.

The pathologist inevitably needs the expertise of the laboratory analyst and the latter's knowledge of the therapeutic, toxic and fatal levels of the substances under consideration. Such data must, however, be evaluated in the knowledge of other pathological and physiological conditions present, so that it is the pathologist, rather than the laboratory toxicologist, who should provide the final opinion upon the proximate cause of death. This does not always happen and some laboratory report forms may be seen that unequivocally – and unwisely – state that a particular drug **caused** the death.

Where, as so often happens, the toxic levels found at post-mortem are not in a potentially fatal or even toxic range, then the pathologist should seek the advice of a **clinical** toxicologist to determine whether any of the symptoms or signs during life may assist in deciding on the cause of death. As so often happens in forensic problems, the investigation of a fatal poisoning must be a cooperative effort, especially between pathologist and laboratory analyst. Even in apparently obvious cases, such as a blood saturation of 50 per cent carboxyhaemoglobin, it is not for the analyst to declare a definite cause of death, as the victim may also have had a fractured skull – but equally, the pathologist has an obligation to provide the laboratory with the best possible samples in the best possible condition, as well as good information about the circumstances of the case.

THE CONCEPT OF THE FATAL DOSE

Many persons, including some doctors, are under the firm misapprehension that, for most toxic substances, there are relatively constant quantities that will cause death. Not only the lay public, but lawyers, police, coroners and others assume that there is a more or less linear relationship between the amount of poison that enters the body, the resulting levels in blood and tissues and the degree of disability caused – the ultimate disability being death.

In addition, it is often thought that back-calculation from blood and tissue levels can arrive at a definite assessment of how much poison was originally administered. This aspect is of particular concern to coroners and similar officers, who have to decide on motive in potential suicides, where the magnitude of any overdose may assist in distinguishing between accident and self-administration.

The pathologist has his own difficulties in respect of 'the fatal dose', as quantitative results from the laboratory have to be matched against a knowledge of published blood and tissue levels for that substance in relation to its potential toxicity. Though numerous tables of toxic levels have been published, there is considerable variation between the levels recorded. Reasons for this are explored later. It is obvious that there is no 'fatal dose' in the sense of a single threshold concentration above which a person dies and below which he survives. Instead, there is a range of levels, the upper and lower margins of which vary from one authority to another, which encompasses most deaths – but even here there are many exceptions, instances being recorded where survival occurs well above the upper limit and death occurs below the lower margin. In such cases, the task of the pathologist – which cannot always be satisfactorily discharged – is to evaluate all other non-toxicological data to see if they can modify the circumstances sufficiently to allow an acceptable explanation for the death. It is sometimes difficult to explain these concepts of great biological variation to lawyers and police officers, who expect more definite decisions, and might even feel that the pathologist is being evasive or obstructive.

The concept of the 'LD_{50}' is sometimes raised by the more knowledgeable lawyer, but this does not assist materially in any individual case. The LD_{50} is a device used by pharmacologists and toxicologists in a statistical sense in animal experiments. Over a large number of tests, it provides a toxic level at which half the animals will be expected to die. Though the indicative value in a general sense in comparing the toxicity of one substance against another, there is no way of knowing whether the human victim of poisoning lies at the upper or lower end of the classical bell-shaped curve that characterizes most biological responses.

Far more useful is the cumulative record of actual laboratory results from toxicology centres that deal with human poisoning, which progressively build up a large database of blood and tissue levels, and correlate these with records of the clinical state, toxic effects and fatal outcome. Even here the variations are wide, as the many published tables testify, but at least general guidance can be obtained.

VARIATIONS IN PUBLISHED FATAL POISON CONCENTRATIONS

In the many publications that offer therapeutic, toxic and lethal ranges for a wide variety of poisonous substances, there is considerable variation in the quoted levels. These can be a source of confusion and sometimes dismay to the pathologist who, even with the advice of his local toxicologist, may find it difficult to decide whether a death can justifiably be attributed to a particular drug or other toxic substance. Even if he can so satisfy himself, he may be subjected to keen questioning, interrogation, doubt or criticism from colleagues, coroners, police, lawyers and others, who have access to different versions of toxic and fatal levels. The ultimate challenge may come in a criminal court, where opposing counsel may openly defy the pathologist's interpretations in cross-examination.

Dr A R W Forrest, Chemical Pathologist and Toxicologist at Sheffield's Royal Hallamshire Hospital (personal communication) points out some reasons for the variations found in such published data. He expresses the view that it is rather surprising that the order of disagreement is not greater, given the opportunities for disparity.

First, many of the published series are small, some being only individual case reports. Statistically, this is not a good foundation for establishing reference ranges, which are much better obtained from a database derived from the cumulative results of a large laboratory service, such as the British Home Office Forensic Science Service, which maintains a central computer store of all results from its laboratories.

Second, analytical techniques vary widely, both in method and accuracy. The specificity varies from laboratory to laboratory so that there may be a lack of uniformity about what is actually being measured. For example, paracetamol may be measured by a non-specific method that picks up its metabolites as well as the native drug, which will then offer a different blood level in a fatal case from that found by more specific methods. In other words, one is not comparing 'like with like'.

Third, as discussed elsewhere in this chapter, the site of sampling may introduce wide errors. With some substances, a several-fold variation in concentration may be found between femoral vein and cardiac cavity blood.

Last, errors occur because a 'fatal' level may be attributed to one substance without taking into account the level – or even the existence – of other toxic substances that the deceased may have taken, and of which the pathologist or analyst may not even have been aware. For example, the newer more potent benzodiazepines may be missed in a simple toxicological screen, but could well have contributed to the toxicological overload that caused the patient to die. In such a case, the level of the recognized drug would be blamed for the death, whereas in fact it may not have been a lethal dose in itself, though was recorded as such in any database or tables.

These facts highlight the dangers of limiting a request for analysis solely to the substance known or thought to have been taken. Often an efficient screen for other substances will reveal other unsuspected compounds, sometimes more toxic than the one originally suspected.

It has to be recognized, however, that, in many jurisdictions, the availability and expense of toxicological investigations may make it impossible to pursue a full analytical survey, especially if this is to be undertaken on a speculative basis rather than for quantification of a known or strongly suspected toxic agent. A full screen may only be practicable and justified in a suspected homicide, if laboratory facilities and fiscal support are severely restricted. In many countries homicide by poison is relatively rare and the funds to investigate accidental, suicidal and iatrogenic poisoning exhaustively may just not be available.

THE AUTOPSY IN SUSPECTED POISONING

The autopsy in these circumstances can be amongst the most difficult of problems faced by a forensic pathologist – not in the technical procedure of the examination, but in the final evaluation of all the available information.

The nature of the poisoning autopsy in Western countries has changed dramatically since the last century, when poisoning was a common method of homicide. There has been a marked change in the nature of poisons used in murder, suicide and accident. The corrosives, heavy metals and alkaloids commonly ingested in former years became relatively easy to detect, either by gross autopsy appearances or by straightforward analytical methods. Further refinements of toxicological techniques, instead of the old methods in which large samples had to be tested because of the insensitivity of laboratory tests, allow the detection of nanogram quantities.

Acids, alkalis, phenols, arsenic, antimony and strychnine, for example, became easy to detect, and in the Western world these gave way to compounds that leave little or no gross, or even histological changes in the body. Most are pharmaceutical or agrochemical substances, active in low dose compared to the old 'blockbuster' poisons. As for the majority of drugs used in legitimate medical therapy, an added problem arises when low post-mortem levels are found – is this merely a therapeutic dose or the tail-end of a declining lethal dose?

In some parts of the world, such as South-east Asia, Africa and the Indian subcontinent, poisoning remains common and more physically damaging substances continue to be seen that leave obvious autopsy lesions. Some of these are described under the appropriate headings in the succeeding chapters, but in most poisonings the major function of the autopsy is to evaluate any other conditions present, both from trauma and natural disease – but also to collect suitable material for laboratory analysis. The proper retention of optimal samples, their correct preservation and dispatch to the toxicologist are of such fundamental importance that they are discussed in detail.

POISONING DEATHS IN HOSPITAL

A considerable proportion of those who die from suspected poisoning will have died in hospital, and it is of prime importance that the medical records be obtained and studied before the autopsy begins. Even if poisoning was not confirmed or even suspected by the clinicians treating the patient, later information may have come to the pathologist to raise this possibility. Whether known or not, the results of ante-mortem investigations may be of considerable use to the pathologist. If poisoning was known or suspected before death, there may well have been toxicological analyses performed and the results of these may be of great value.

Whether poisoning was suspected or not, there may still be ante-mortem blood or urine samples (taken for biochemical or haematological tests) stored in the hospital laboratory, which may be rescued for retrospective analysis. Such ante-mortem samples are likely to be of greater use than fluids drawn off at autopsy, because of sampling defects, post-mortem changes and because toxic levels are likely to have been higher during life, representing more accurately the maximum toxic concentrations.

In addition, many patients dying in hospital from drug overdoses will have indwelling catheters in place. It is the common practice for the nursing staff to remove these at death and discard the urine. If it is possible to establish a practice in the wards where such terminal urine samples are saved, valuable material for analysis can be obtained.

THE COLLECTION OF AUTOPSY SAMPLES FOR TOXICOLOGICAL ANALYSIS

The investigation of a death from suspected poisoning may stand or fall upon the correctness or otherwise of the sampling of fluids and tissues from the body. Unsuitable samples, inadequate amounts, incorrect sampling sites, poor containers, inadequate preservation methods, and delayed or unsatisfactory storage and transport to the laboratory may frustrate or distort proper analysis. The final outcome may be wrong, either in failing to detect a poison actually present, in measuring only part of that originally present or – in some cases – even producing falsely high results that then lead to an incorrect cause of death. Not only must samples be in the optimal condition, but the accompanying information from the pathologist to the analyst needs to be as accurate and comprehensive as possible, so that the most appropriate techniques are used, and allowance made for any interfering substances that may be present.

In decomposed bodies infested with maggots, and in the absence of tissues or fluids normally taken for toxicology, Diptera and other arthropods can be used as alternative specimens for toxicological analyses. This relatively new field of forensic entomology is called entomotoxicology.

The time of sampling

It is obvious that the shorter the delay between death and the removal of samples, the better. Though some toxic substances, such as carbon monoxide, form stable compounds in the body, many others (especially volatile substances and some pharmaceutical products) will be broken down by post-mortem autolysis and decomposition. When an autopsy cannot be performed quickly after death, in terms of a few hours, then mortuary refrigeration is the first line of defence to slow up putrefactive and autolytic processes. If delay is foreseen, usually because of administrative problems in obtaining consent or authority for autopsy, it may be possible to obtain a sample of blood through the body surface, such as puncturing the femoral vein by needle and syringe. The blood can then be kept in optimal conditions, with preservative where needed, and perhaps with the serum or plasma separated from the cells to avoid haemolysis. Similarly, urine could be drawn off by catheter or even suprapubic puncture, unless strict regulations forbid this as anticipating autopsy permission.

In some jurisdictions, authority for autopsy may be particularly hard to obtain, from religious, financial or administrative reluctance. Where poisoning is suspected, permission may be granted only for external examination and sampling; here venous blood, urine and perhaps vitreous humour may have to suffice for all investigations.

Information supplied to the laboratory

When samples are submitted to the toxicologist, they should be accompanied by the best possible information relevant to the case. It is both counterproductive and an unprofessional discourtesy merely to record the personal details of the deceased and list the samples, with a terse demand such as 'Any poisons?' on the request form. Such a demand could legitimately be refused by the toxicologist, as it is quite inadequate information upon which he can be expected to function effectively and safely. The following information should be supplied and where necessary, supplemented by direct discussion either in person or by telephone:

- The personal details of the deceased, including age, sex and where thought relevant, the occupation (especially if in agriculture or industry).
- Brief details of symptoms, if any, and length of illness.
- The post-mortem interval before samples were obtained, and the actual date and time of sampling.
- The name, address and telephone number of the pathologist.
- A list of all samples provided, with an indication of the sampling site for each.
- The nature of any preservative in each of the samples.
- If there has been a delay in submitting or transporting the samples, a note of the condition under which they have been stored (for example, refrigeration or deep-freeze).
- Any special risk associated with the samples **must** be communicated to the laboratory. The most obvious are infective conditions, especially hepatitis B or C virus or HIV infection in the deceased, though other diseases such as tuberculosis, tetanus, anthrax, gas gangrene or any other bacterial or viral condition must also be specifically reported. In relation to hepatitis and HIV, even if these are not definitely confirmed, the toxicology laboratory must be told if the deceased was in a high-risk group, such as a drug addict or a homosexual. In many areas, including Britain, some toxicology laboratories will not accept samples from such high-risk groups until a blood sample has been screened for hepatitis B and HIV antibodies; if positive, they may decline to carry out the analysis or perform it only under strictly controlled conditions.

  Similar warnings must be given to the analyst if there is any possibility of certain harmful substances, such as radioactive isotopes or certain war gases, being present in the samples.
- When a death has criminal aspects, such as a murder or manslaughter, then the usual strict precautions must be taken for continuity of evidence. Each container must be carefully labelled and preferably countersigned by the pathologist. Some jurisdictions will require actual seals on the containers themselves or the package into which they are placed for transport, or both. Accompanying signed 'exhibit labels' with serial numbers corresponding exactly with numbers on the jars may be required. The containers must be given by the pathologist to a named person, usually the 'exhibits officer' of the police investigating team (or to forensic scientists if they attend the autopsy). The police officer must hand the samples personally to a member of the laboratory staff and a record of this chain of evidence must be kept, so that there can be no criticism levelled at anyone when the matter comes to court, raising doubts about the correct identity of the sample.

CONTAINERS FOR TOXICOLOGY SAMPLES

There will be considerable local variation in the type of containers used for the collection and transmission of samples to the laboratory. Some laboratories will issue their own kits, an example being those provided by the Home Office Forensic Science Service in England and Wales. These consist of a plastic bag containing a sheet of instructions about the most suitable samples, together with a large plastic pot with tightly self-sealing lid for liver, a smaller one for stomach contents, several plastic or glass 30 ml universal containers for blood and urine, a small vial containing fluoride for blood-alcohol estimation and a sterile syringe and several needles. Variations of such kits may be provided by different laboratories, but the general nature of the containers is the same. In other areas, the pathologist will provide the containers himself and they should conform to the following general specifications:

- They should either be new or, if previously used for other samples, have been rigorously cleaned and sterilized. Even when they are new, it is preferable for containers to be washed and sterilized before use unless the manufacturer's specifications clearly make this unnecessary. All containers must be chemically clean, not just apparently clean to the naked eye. This applies particularly to any rubber, plastic or other seal within the lid or cap, which may be a trap for any debris or even residue from a previous sample.
- Blood should be collected in screw-capped universal containers of about 30 ml or, where less will suffice, in plastic-capped tubes of about 5 ml. Urine is best held in 30 ml universal containers, as is bile. Stomach contents may be retained in glass or plastic jars with a volume of at least 250 ml, the lid being either a tight screw-thread with a cardboard or plastic liner, and a self-sealing plastic top. Some laboratories require the stomach wall as well as the contents, as toxic substances may be held in higher concentrations in the rugae and crypts of the mucosa, or even in the blood in the actual stomach wall. The size of the container may need to be larger if the organ itself is retained. Liver is usually required, preferably a piece weighing a few hundred grams, rather than the whole organ. The total weight of the liver should be communicated to the laboratory if only part is sent. It may be preserved in a larger glass or plastic container. When the laboratory wishes the whole organ, this container needs to be large enough to hold about 3 litres. If only small samples are needed, such as vitreous humour or cerebrospinal fluid, bijou bottles of 5 ml capacity or small tubes of similar size, are needed.

In Britain, the government forensic laboratories provide special bottles for blood-alcohol estimations, for use in both drink–driving offences in the living and for autopsy samples. These are short, wide bottles of about 10 ml capacity, with a fixed top consisting of a plastic diaphragm secured by a metal flange with a central aperture. They are filled by syringe, the needle being pierced through the diaphragm, but have the disadvantage of building up pressure when the blood is injected, so that, when the needle is removed, blood may spurt back and even contaminate the operator – the reverse of the intention of these vials to be safe. The danger can be avoided by either inserting a second needle through the diaphragm to equalize the pressure, or to suck out air from the bottle with the empty syringe and needle before taking the sample so that the introduced blood replaces the lost air. Intestinal contents, with or without the gut itself, can be placed in large jars or plastic pots, similar to those used for liver.

Plastic containers, especially polypropylene, are increasingly used and have the advantage of not smashing when dropped. Some analyses, however, may be affected by the plasticizer in either the container wall or the cap – cocaine is an example. The advice of the toxicologist with whom each pathologist normally collaborates should be sought in respect of his individual preferences for containers. Where lungs or other tissues are to be submitted for analysis for volatile substances, as in solvent abuse, ordinary polythene bags are not suitable containers. Nylon bags (such as those used by arson investigators) should be used, as they are not permeable to such substances.

PRESERVATIVES IN SAMPLES

Though many samples for analysis are best sent in their original state, others require additives to maintain them in optimum condition until they reach the laboratory. In addition to such preservatives, some require anticoagulants to keep the blood fluid. The prime example of sample preservations is that for blood alcohol, as improper care of samples may distort the original alcohol level in either an upward or downward direction. The usual preservative is sodium or potassium fluoride, which is essential if the sample is not to be analysed within a few hours of withdrawal from the body.

Errors caused by post-mortem changes before the sample is removed cannot be avoided. These are variable, depending partly on the conditions of the post-mortem environment and partly on the microbiological population of the corpse. In warm conditions, fermentation by yeasts and other alcohol-producing flora can produce appreciable quantities of alcohol: it has been reported that as much as 150 mg/100 ml have been generated within 24 hours after death.

Once the blood or urine has been withdrawn from the body, however, further changes can be arrested by preservatives. Much has been published on this subject and a variety of concentrations of fluoride have been recommended by different authors. Glendening and Waugh (1965) used 100 mg of sodium fluoride/10 ml blood and found no change in the alcohol content when samples were kept at room temperature for up to 3 months. Plueckhahn (1968) found that at least 5 mg/ml of sodium fluoride was required to inhibit alcohol dehydrogenase activity, which destroys alcohol. He found, however, that this concentration failed to inhibit alcohol-forming organisms completely, such as when yeasts were introduced into the samples. Together with Ballard, he investigated the use of mercuric chloride as a preservative (Plueckhahn and Ballard 1968). This substance was also used by Bradford (1966) who added 0.5 mg of sodium citrate and 0.1 mg of mercuric chloride/ml of blood to ensure that the samples remained liquid and sterile. When he replaced the mercury by fluoride, significant changes occurred, usually a loss of alcohol, though occasionally it increased.

In most cases the delay before analysis is relatively short, being measured in days – often with refrigerated storage – so the long-term experiments mentioned here do not apply. When the ambient temperature is high, much more caution needs to be used. It would seem that for general use, a concentration of 10 mg/ml of sodium or potassium fluoride is satisfactory. Fluoride should also be added to urine and vitreous humour if alcohol estimations are required. Cocaine and its metabolites are also labile *in vitro*, and fluoride should be added to samples submitted for analysis for this drug.

Cyanide may be formed in considerable quantities in plain blood samples, which are of little use for cyanide estimation. Fluoride should be added to such specimens, as well as for carbon monoxide (carboxyhaemoglobin) if the analysis is to be delayed. In all analyses for pharmaceutical drugs, two samples of blood should be submitted, one plain in large volume of at least 25 ml and another smaller sample in fluoride.

When insulin assay is required on a blood sample, special precautions should be taken. Haemolysis of the red cells releases enzymes which will reduce the S–S bonds in insulin and destroy its immunoreactivity, so the sample should be centrifuged as soon as it is obtained to separate the serum. A heparinized sample should also be taken for glycosylated haemoglobin estimation and fructosamine assay. Vitreous humour, blood and urine samples should be placed in fluoride and sent for glucose estimation, as well as tissue samples from around any putative injection site, together with a control tissue sample from a site elsewhere on the body where insulin is unlikely to have been recently injected.

THE SITE OF SAMPLING FOR TOXICOLOGICAL ANALYSIS

It is now obvious that, in the past, serious errors were made in toxicological analyses from lack of care or consideration concerning the source of body-fluid samples. Significant variation can be found in the concentration of many substances depending on the place from which sampling was carried out. In life there may be variations when arterial as opposed to venous blood is used, as tissues may take up the compound from the arterial supply, the concentration then being lower in the venous return. Similarly, portal blood may have a substantially higher concentration of a substance that is being absorbed from the intestine, before it is extracted by passage through the liver. After death, most variation is caused by uneven destruction by enzymatic and microbiological activity – and by diffusion from sites of higher concentration. The barriers formed by living cell membranes break down after death and small molecules in particular may move easily through the tissues into vascular channels.

Post-mortem levels of many substances are unreliable because of this diffusion effect, making the interpretation of physiological components, such as sodium, potassium, calcium, glucose, urea and many others extremely difficult, if not impossible. Applying these facts to toxic compounds, the concentrations may vary considerably according to the sampling site. As an illustration, the Moorgate Tube disaster in London showed that blood-alcohol levels may vary widely between different sampling points. The driver of an underground train was killed, along with a number of passengers, but his body could not be recovered from the warm environment for several days. As it was obviously vital to know if drink had contributed to the accident, four samples were taken from various sites in the body. On analysis, a fourfold variation from between 20 and 80 mg/100 ml was obtained, presumably because of variable rates of putrefactive alcohol production, as there was no evidence to show that the driver had imbibed alcohol before death.

Most research in respect of sampling variation has been directed at alcohol. One point of dispute, which is relevant even when post-mortem changes are minimal, is whether alcohol in the stomach can diffuse after death to neighbouring organs and produce a falsely elevated alcohol concentration in blood at those sites.

The relevance is clear, in that, if a person drinks alcohol immediately before death, there will be insufficient time for it to be absorbed. Thus ethanol remaining in the stomach after death cannot have contributed to his ante-mortem blood-alcohol level, and hence his cerebral function and consequent behaviour. If however, analysis of a sample of blood taken from the heart cavities is contaminated by post-mortem diffusion from the adjacent stomach, then a falsely high reading will be obtained, which may have serious legal implications, if the error is not appreciated.

Several workers have investigated this problem, with conflicting results. Gifford and Turkel (1956) introduced alcohol into the stomachs of cadavers and found that subsequent heart blood levels increased by 25 up to 106 mg/100 ml. They then compared femoral vein blood with heart blood voided into the pericardial sac in alcohol-positive autopsies and found that the concentration in the latter was higher. Plueckhahn and Ballard (1968), however, criticized this work on the grounds that pericardial fluid alcohol was usually about 20 mg/100 ml higher than that in the heart or peripheral vessels. Plueckhahn went on to instil alcohol into the stomach of cadavers, taking multiple site samples at times from 6 to 50 hours later. His results indicated that there was a significant diffusion of alcohol to the pericardial and pleural fluids, but that the increase was minimal in intraventricular heart blood.

Pounder and Yonemitsu (1991) carried out experiments with dead bodies in which they introduced a slurry containing alcohol, dextropropoxyphene and paracetamol into the trachea to simulate aspiration of stomach contents. After a delay of 48 hours, an autopsy was carried out and drug concentrations measured in samples taken from various sites. Whilst femoral vein blood remained clear of these substances, samples from vessels in the thorax showed up to 130 mg/100 ml of alcohol with a mean of 58 in a pulmonary vein – and up to 1934 mg/l of paracetamol (mean 969), both obviously spurious due to post-mortem diffusion. This situation could have occurred from agonal regurgitation of stomach contents with recently swallowed drugs back into the air passages and shows the dangers of inappropriate sampling sites, with the femoral the place of choice.

Winek *et al.* (1995) have shown that, in the sampling practice of transthoracic needling, especially in cases of trauma where the gastrointestinal tract has been damaged, false elevations of blood alcohol can occur. These workers used heart blood as their control, which itself seems suspect as a satisfactory autopsy sample.

For the reasons given above, **peripheral** vein blood should be used whenever possible, avoiding heart blood as a potential source of error for alcohol and presumably other easily diffusible substances.

THE TECHNIQUE OF OBTAINING AUTOPSY SAMPLES

Blood

There are several ways of obtaining blood samples at autopsy and perhaps the most useful advice is what **not** to take. Blood should never be obtained from body cavities after evisceration, as it is almost certain to be contaminated with other body substances. The practice of scooping 'blood' – or more accurately, bloody fluid – from the paravertebral gutters or the pelvis is always unacceptable, as urine, intestinal contents, gastric contents, lymph, pleural and ascitic fluid and general tissue ooze will always find their way into such a sample and negate the reliability of analysis.

When a large haemothorax or haemopericardium is present, it may be grudgingly acceptable to use such blood or clot, if a clean sample is taken immediately on opening the chest, before any dissection or disturbance of organs is made. This is only second best to obtaining intravascular blood – and, in the case of alcohol and other diffusible substances, the results cannot be relied upon, as the sample may be contaminated by post-mortem diffusion from the stomach, as discussed in the preceding section. Carbon monoxide estimations may also be made on clean cavity blood, if nothing else is available, as sometimes happens in a badly incinerated body. As it is absorbed through the lungs, it cannot diffuse from the gastrointestinal tract to give a false result. Even so, it is a rare autopsy that cannot provide a small sample of blood from some peripheral vein, if enough care and persistence is used.

To return to the general state of affairs, the most satisfactory way of obtaining a venous blood sample is venepuncture of the femoral vein by direct puncture in the groin before the autopsy begins. Practice is required as, unlike a living patient, the vein is not usually palpable. Once the lumen is entered, 25 ml can usually be drawn off without trouble, though a slow flow may be improved by massaging the leg to drive blood proximally or the leg may be raised, if rigor allows. Though less satisfactory than a leg vein, for reasons discussed earlier, a neck vein can also be punctured through the skin, and even after death the jugular may sometimes be both visible and palpable, especially in congestive deaths. The subclavian vein can also be tapped.

When collecting blood samples by percutaneous puncture, some pathologists prefer to use a needle designed for aspirating samples from rubber-capped vials, rather than a needle meant for clinical aspiration or injection. The same needles can be used for collecting vitreous humour. An example of this type of needle is the Becton Dickinson purple-hubbed 16 gauge one-inch or a similar American equivalent.

In some jurisdictions, especially in countries where the system allows only a low autopsy rate, transcutaneous sampling is virtually the only post-mortem investigation possible and the doctors in these areas become adept at cadaver venepuncture. Many pathologists, the authors included, have been brought up to obtain blood samples during the actual performance of autopsy and this can be as satisfactory as external venepuncture, as well as saving the expense of a new syringe and needle every time. A common procedure after evisceration is to hold a container (such as the 30 ml universal) under the severed end of the subclavian vein, within the upper part of the empty thorax. The arm is then elevated and massaged if necessary, to express blood into the container. Similarly, and perhaps preferably, the femoral or external iliac vein may be transected near the brim of the pelvis, and a container held under the cut while the leg is elevated, or massaged, or both. Either of these methods will provide ample, clean, peripheral venous blood, though care must be taken to avoid any contamination from the body cavities. This initial collection should be transferred into one or more new tubes, with preservative added if appropriate, as the first receptacle will be soiled externally during the collection process.

An alternative method of collecting a venous sample, which always gives a copious flow of blood, is to incise the internal jugular vein during the initial stages of the autopsy. As soon as the main autopsy incision is made, the flaps of the neck skin can be dissected aside and the jugular exposed, if necessary by dividing the sternocleidomastoid muscle. As in the previous technique, a bottle can be held against the vein as it is transected and the flow collected directly into it. The blood may overflow into the pouch formed laterally by the reflected skin, which forms a reservoir where a considerable volume may collect. If the flow is scanty, it can be improved by raising and lowering the head, which will cause blood to return from the upper venous drainage areas.

Even more can be expressed by pressing on the chest, but here there is the potential disadvantage of forcing up blood through the superior vena cava from the heart, which may distort the value of alcohol and other drugs that may have diffused port-mortem from the stomach. Blood should not be taken from the heart cavities, the inferior vena cava, or the portal or hepatic veins, as these may also give concentrations that are at variance with those in the peripheral vascular system. A full 30 ml of blood should be submitted to the laboratory wherever possible, together with a 5 or 10 ml fluorided sample.

Urine

Prior to, or in the absence of, an autopsy, urine can be obtained by catheter or suprapubic puncture with syringe and long needle. At autopsy it is usual to wait until evisceration has been carried out before dealing with the bladder. A sample can be obtained by puncturing the fundus with syringe and needle. Alternatively, the bladder can be stretched by pulling the fundus upwards with the fingers, then a sagittal incision made with a knife on the ventral surface, which must be free from blood soiling. The urine that wells out can be collected directly into a small container such as a 30 ml universal. If only a small amount is present, then the incision may have to be enlarged and the residual urine sucked out under direct vision, using a syringe without a needle.

Bile

This can be useful for some analyses, such as those for morphine and chlorpromazine, which are concentrated by the liver and excreted into the gallbladder. Direct collection into a bottle is advised, as bile is usually too viscous to be sucked through a needle.

Cerebrospinal fluid

This is not often required for toxicological analysis, though it may be needed for microbiological and virological studies. If needed, it should be collected by lumbar or cisternal puncture, as in the living patient. It can be difficult or impossible to obtain in this way because of the lack of any intrathecal pressure.

The body should be turned on to its side before the autopsy begins and flexed as much as possible by an assistant. If an infant, it should be sat up and again flexed forwards to curve the spine as much as possible. A needle on a syringe should then be passed between two lumbar or lower thoracic spines, and stopped as soon as any penetration of the theca is felt. Moderate suction should be maintained on the syringe piston to compensate for the lack of internal pressure. Alternatively, the needle should be passed into the midline just below the occiput and advanced upwards until the skull is contacted just posterior to the foramen magnum. The needle is slightly withdrawn and re-advanced until it slips through the posterior part of the atlanto-occipital membrane into the basal cistern when cerebrospinal fluid may be aspirated. It is of little use taking cerebrospinal fluid from the bowl of the posterior fossa after the brain has been removed as the concentration of many substances is different in blood compared with the fluid, so blood contamination distorts any results. Clear cerebrospinal fluid may, however, sometimes be obtained from the lateral ventricles, either by needle puncture or cutting down through the cortex.

Vitreous humour

This is sometimes useful, especially in bodies with appreciable post-mortem decomposition, as the fluid in the eye resists putrefaction longer than other body liquids. Vitreous fluid is also used for estimating the time since death (see Chapter 2).

A puncture should be made through the sclera at the outer canthus with a fine-gauge needle. This should be placed as far laterally as possible, pulling the lid out, so that when released it returns to cover up the puncture mark for cosmetic reasons. The fluid should be sucked out by syringe, but it will often come only slowly because of its viscosity. If the best restoration is needed, water should be reinjected through the same needle to reinflate the globe, which tends to collapse on suction.

Stomach contents

As stated earlier, these can be collected directly into wide-mouth glass or plastic pot of at least 250 ml volume. To collect them, the exterior of the stomach should be washed clean of blood and other contamination, and pulled with attached organs to the edge of the dissecting board or sink. The greater curvature should be opened cautiously with large scissors, and the jar held underneath so that the contents flow directly into it. When most have been expressed, the greater curvature can be opened up fully and the gastric lining examined. Any further contents are scraped out and any powder, capsule or tablets picked off, and either added to the main jar or placed in a separate small container. Such focal deposits form a more concentrated sample for the laboratory. Any undissolved tablets or capsules should be carefully preserved, as the laboratory or a pharmacist may be able to identify them by their appearance and colour. After the mucosa has been examined, including that of the duodenum, the stomach wall can be dissected off. Some laboratories require this for their analysis, either added to the jar of contents or sent separately. The wishes of each individual toxicologist should be discovered in advance.

Intestinal contents

These are not routinely required for analysis unless some particular gastrointestinal poison is suspected, such as one of the heavy metals. Again, the toxicologist should be consulted. If required, both ends of the small gut should be ligated by string sutures at duodenum and ileum. The intestine is cut through at these points and stripped out by cutting through the mesentery in the usual way. The intact gut can be sent to the laboratory in a large container (such as that used for liver) or – if the mucosa needs to be examined first – it should be opened in a large clean tray. One suture can be cut and the contents milked from one end to the other into a suitable jar, the gut then being opened and sent with the contents to the laboratory. The large intestine and contents are rarely required, as most toxicology laboratories are not keen on handling and storing large volumes of faeculent material. In heavy-metal poisoning, such as arsenic and antimony, however, some analysis may be required.

Vomit

This is rarely collected at autopsy, unless a large quantity has been found in the air passages. However, vomit is not infrequently collected by ambulance crews and police at the scene of the illness or agonal event, and brought with the deceased to hospital or the mortuary. If thought relevant in a case of suspected poisoning, it should be properly contained, labelled and forwarded with other samples for toxicological examination.

Other fluids

Other fluids are rarely collected, but on occasions may be useful, especially if clean blood cannot be obtained. Pericardial fluid, synovial fluid, pleural effusion and ascitic fluid can be used for qualitative analysis to identify a range of substances, though these levels can rarely be related to established ranges of blood concentrations. They may be collected and transported in the same type of container and with the same preservatives as vitreous humour.

Analysis for volatile substances

In solvent abuse and deaths from gaseous or volatile substances, the toxic material may be isolated from a whole lung. As soon as the thorax is opened at autopsy, a lung is mobilized and the main bronchus tied off tightly with a string ligature. The hilum is then divided and the lung placed immediately into a nylon bag, which is sealed and sent as soon as possible to the laboratory. Ordinary plastic (polythene) bags are not suitable for this task, as they are permeable to volatile substances. Nylon bags, as used by arson investigators to collect samples that may have volatile accelerants, do not suffer from this defect.

In collecting blood samples for volatile substances, plastic tubes or tube/syringe combinations of the 'monovette' type are unsuitable, as the concentration of such compounds as toluene or other solvents will decrease considerably over a few days in storage. Vials with a rubber septum as a seal are also unsuitable, as the volatile substance can escape through the rubber. Suitable tubes are made of glass with an aluminium foil-lined cap or a polytetrafluorethylene (Teflon) liner. This type of tube is often used in laboratories for scintillation counting and can be employed for the collection of solvent samples. Such tubes should be available in any busy autopsy room where solvent abuse deaths may be handled. The tubes should be filled to the top to avoid loss of volatile substances into the head space and should be stored at 4°C, rather than being frozen solid.

Body tissues

Body tissues may be needed for some toxicological analyses. Liver is the most usual, as it concentrates many substances and their metabolites, which may then be recoverable long after the blood and urine levels have declined. Either the whole organ is saved or an aliquot of 50–100 g, according to the wishes of the particular laboratory. If only a part is retained, it should be taken from the periphery, away from major vessels and bile ducts.

Brain and kidney may sometimes be required and again a 50–100 g aliquot is usually sufficient. As with liver, the total original weight of the organ should be recorded and notified to the toxicologist.

Where a toxic substance may have been injected into the subcutaneous tissue or muscle, these tissues should be excised and submitted to the laboratory. The usual method of identifying the site is from a needle puncture mark, and a zone of skin and tissue should be removed circumferentially around this or an ellipse cut away, so that the defect can be sewn up on the body. A few centimetres in diameter around the mark is usually sufficient. The depth of the sampling depends on how deeply the needle track extends and may need to go into the underlying muscle. Radiography may assist in rare cases, as in the George Markov murder in London, where a political assassination was carried out by the introduction of a tiny sphere, presumably injected from an air weapon concealed in an umbrella. The sphere, drilled out to carry a potent toxin, probably ricin, was located by X-ray at autopsy after a small skin puncture was found. Where an injection site is sampled, it is essential that a control area from a remote part of the body is also sent to the laboratory. It is usual to take this from a symmetrical zone on the contralateral side, but caution must be used, as in both drug dependence and insulin usage, alternate sides may be used at frequent intervals for injection, so another more remote site might be preferable.

The substances which may have been injected are numerous, but insulin, morphine, heroin, cocaine and other illicit drugs are most common. In the notorious Coppolino case in the USA, products of succinylcholine (suxamethonium) were identified from around a needle track in the buttock of an exhumed body of a woman, leading to the conviction of her anaesthetist husband for murder.

REFERENCES AND FURTHER READING

Baselt RC. 2000. *Disposition of toxic drugs and chemicals in man*, 5th edn. Chemical Toxicology Institute, Foster City, CA.

Bourel B, Fleurisse L, Hedouin V, *et al.* 2001. Immunohistochemical contribution to the study of morphine metabolism in Calliphoridae larvae and implications in forensic entomotoxicology. *J Forensic Sci* **46**:596–9.

Bradford LW. 1966. Changing attitudes in drinking driver enforcement as reflected by the actions of researchers, courts, prosecutors and society. *J Forensic Sci Soc* **6**:204–8.

Cordonnier J, Heyndricks A, Piette M. 1986. Drug levels in plasma, vitreous humor, bone marrow, liver and bile. *Police Surg* **30**:60–7.

Drummer OH, Gerostamoulos J. 2002. Postmortem drug analysis: analytical and toxicological aspects. *Ther Drug Monit* **24**:199–209.

Fermer RE. 1995. *Forensic pharmacology*. Oxford University Press, Oxford.

Gagliano-Candela R, Aventaggiato L. 2001. The detection of toxic substances in entomological specimens. *Int J Legal Med* **114**:197–203.

Gifford A, Turkel M. 1956. Diffusion of alcohol through stomach wall after death. *JAMA* **161**:866–8.

Glendening BL, Waugh TC. 1965. The stability of ordinary blood alcohol samples held at various periods of time under different conditions. *J Forensic Sci* **10**:192–200.

Goff ML, Lord WD. 1994. Entomotoxicology. A new area for forensic investigation. *Am J Forensic Med Pathol* **15**:51–7.

Grellner W, Glenewinkel F. 1997. Exhumations: synopsis of morphological and toxicological findings in relation to the postmortem interval. Survey on a 20-year period and review of the literature. *Forensic Sci Int* **90**:139–59.

Hilberg T, Rogde S, Morland J. 1999. Postmortem drug redistribution – human cases related to results in experimental animals. *J Forensic Sci* **44**:3–9.

Introna F, Campobasso CP, Goff ML. 2001. Entomotoxicology. *Forensic Sci Int* **120**:42–7.

Jenkins AJ, Levine BS, Smialek JE. 1995. Distribution of ethanol in postmortem liver. *J Forensic Sci* **40**:611–13.

Jones AW, Lofgren A, Eklund A, *et al.* 1992. Two fatalities from ingestion of acetonitrile: limited specificity of analysis by headspace gas chromatography. *J Anal Toxicol* **16**:104–6.

Klatt EC, Beatie C, Noguchi TT. 1988. Evaluation of death from hypoglycemia. *Am J Forensic Med Pathol* **9**:122–5.

Langford AM, Pounder DJ. 1997. Possible markers for postmortem drug redistribution. *J Forensic Sci* **42**:88–92.

Levine BS, Smith ML, Froede RC. 1990. Postmortem forensic toxicology. *Clin Lab Med* **10**:571–89.

McCurdy WC. 1987. Postmortem specimen collection. *Forensic Sci Int* **35**:61–5.

O'Neal CL, Poklis A. 1996. Postmortem production of ethanol and factors that influence interpretation: a critical review. *Am J Forensic Med Pathol* **17**:8–20.

Palmeri A, Pichini S, Pacifici R, *et al.* 2000. Drugs in nails: physiology, pharmacokinetics and forensic toxicology. *Clin Pharmacokinet* **38**:95–110.

Paterson SC. 1985. Drug levels found in cases of fatal self-poisoning. *Forensic Sci Int* **27**:129–33.

Plueckhahn VD. 1968. Alcohol levels in autopsy heart blood. *J Forensic Med* **15**:12–21.

Plueckhahn VD, Ballard B. 1968. Factors influencing the significance of alcohol concentrations in autopsy blood samples. *Med J Aust* **1**:939–43.

Polson CJ, Green MA, Lee MR. 1983. *Clinical toxicology*, 3rd edn. Pitman, London.

Pounder DJ, Jones GR. 1990. Post-mortem drug redistribution – a toxicological nightmare. *Forensic Sci Int* **45**:253–63.

Pounder DJ, Yonemitsu K. 1991. Postmortem absorption of drugs and ethanol from aspirated vomitus – an experimental model. *Forensic Sci Int* **51**:189–95.

Prouty RW, Anderson WH. 1990. The forensic science implications of site and temporal influences on postmortem blood-drug concentrations. *J Forensic Sci* **35**:243–70.

Shapiro HA. 1953. The concept of the fatal dose. *J Forensic Med* **1**:129–31.

Sperhake J, Tsokos M, Sperhake K. 1999. Perimortem fixation of the gastric and duodenal mucosa: a diagnostic indication for oral poisoning. *Int J Legal Med* **112**:317–20.

Stead AH, Moffat AC. 1983. A collection of therapeutic, toxic and fatal blood drug concentrations in man. *Hum Toxicol* **2**:437–64.

Wennig R. 2000. Threshold values in toxicology – useful or not? *Forensic Sci Int* **113**:323–30.

Winek CL, Jr, Winek CL, Wahba WW. 1995. The role of trauma in postmortem blood alcohol determination. *Forensic Sci Int* **71**:1–8.

CHAPTER 28

Forensic aspects of alcohol

- Mode of action of alcohol 552
- Absorption of alcohol 553
- Elimination of ethanol 554
- Alcohol concentrations: units and various drinks 555
- Physiological effects of alcohol 556
- Modes of death in acute alcoholism 557
- Chronic alcoholism 557
- References and further reading 558

Ethyl alcohol is the most commonly used drug in the world and has such numerous points of contact with medico-legal pathology that it has to be considered separately from all other substances. Its abuse is a prime factor in many accidents – transport, domestic and industrial – and the majority of homicides are catalysed by alcohol intake. It acts as an adjuvant to many other toxic substances, combining to cause a fatal outcome where often the other drug alone would not have caused death. The chronic abuse of alcohol leads not only to definite pathological changes in a number of target organs, but also contributes to deaths from neglect, hypothermia and burns.

This central role in forensic practice makes it imperative that a comprehensive knowledge of its metabolism and effects is held by every forensic pathologist, not only for an understanding of autopsy appearances, but to be able to assist investigative authorities to place the death into its alcoholic context.

MODE OF ACTION OF ALCOHOL

Ethanol is a small molecule that is easily miscible with water and therefore quickly diffuses through the whole of the aqueous compartment of the body.

There are slight variations in the intracellular concentration in different tissues – for instance, the red blood cells contain somewhat less alcohol than plasma, so that a whole-blood concentration is slightly less than that in separated plasma or serum. Most serous fluids are in equilibrium, however, though Plueckhahn (1968) claims that pleural and pericardial fluids have a higher concentration than that of plasma. The aqueous humour of the eye is in equilibrium with blood, as is cerebrospinal fluid, given sufficient time for equilibration.

It is said above that alcohol disperses rapidly through the aqueous compartment and this excludes the adipose tissues, as ethanol is almost insoluble in fat. This fact has important practical significance, as people with large fat stores will produce a higher blood-alcohol level for a given intake of alcohol than persons of the same weight who are lean, as the aqueous compartment is smaller. This is particularly relevant to women, who, by virtue of their **panniculus adiposus**, may develop blood-alcohol concentrations at least 25 per cent higher than men of the same body weight after similar drinks. This must be allowed for in all calculations that attempt to relate blood-alcohol levels to intake of drink.

The behavioural effect of alcohol is caused by its action on brain cells and is a function of the concentration in the blood, the alcohol readily passing the 'blood–brain barrier' to bathe neurones via the cerebral extracellular fluid. The action of alcohol is entirely depressant, a fact not always appreciated by those who observe the apparent excitant effect of drinking. Alcohol acts on neural cells in a way similar to hypoxia, reducing their activity. In lower concentrations, this action is confined to the more specialized and sensitive cells of the cerebral cortex, leaving lower brain functions relatively unaffected. The consequent depression of these higher areas releases their inhibitory tone and thus 'takes the brakes off' more primitive and unrestrained behaviour. This was aptly described by Thomas de Quincey (1785–1859) when he wrote that 'sobriety disguiseth man'!

With increasing concentrations of ethanol, progressively lower levels of brain function are depressed and, when the vital centres in the midbrain and medulla are affected, there is a danger of fatal cardiorespiratory failure. Alcohol also causes changes in the heat regulatory mechanism, both centrally and by a vasomotor effect. Generalized vasodilatation occurs, especially in the skin, which may lead to marked heat loss and dangerous hypothermia. There is an increase in heart rate with low concentrations but, when alcohol levels approach the dangerous ranges in excess of 300 mg/100 ml, bradycardia may develop. A slight and inconstant increase in blood pressure may occur, more often in the systolic level, which increases the pulse pressure between systolic and diastolic. There is no evidence to support the contention that alcohol dilates the coronary arteries and claims that it causes dilatation of cerebral arteries (and thus worsens intracranial haemorrhage) are also equivocal. Alcohol also has a diuretic effect and, when combined with large quantities of fluid, as in excessive beer drinking, may lead to electrolyte disturbances. In healthy test subjects short-term alcohol administration causes transitory hypoparathyroidism, accounting, at least in part, for the transient hypocalcaemia, hypercalciuria and hypermagnesiuria. In alcoholic patients especially hypomagnesaemia is common.

ABSORPTION OF ALCOHOL

For all practical purposes, it may be assumed that the only route of absorption of alcohol is by mouth as, although it can be inhaled, situations where this occurs must be rare indeed. One case is known to the author (PS), in which a man suffering from a tumour of the base of the tongue, probably causing difficulties in swallowing, had instilled fruit brandy rectally via a plastic tube using a pump, and dying as the result of acute alcohol poisoning.

Almost as soon as the alcohol is swallowed, it begins to be absorbed into the blood – and as soon as that blood reaches the liver, the alcohol begins to be eliminated. Therefore the blood level (and hence the brain concentration) is a dynamic balance between absorption and elimination, the peak determining the maximum behaviour effect. Such a balance is often represented graphically by the 'blood-alcohol curve' (BAC), which indicates the intensity and duration of physiological effects.

Ethanol is capable of being absorbed by any part of the gastrointestinal canal, but in practice this is confined to the stomach and upper small intestine, as only a little alcohol remains to pass through the wall of the ileum or colon. When alcohol is taken with food, however, there seems to be a deficit in the amount absorbed, as some never appears in the bloodstream. Some of this lost alcohol may be excreted in the faeces, but when absorption is slow, more may be destroyed by the liver directly from the portal blood, never surviving to enter the systemic circulation. Nickolls (1956) estimated this lost alcohol taken with food to be between 17 and 20 per cent and Alha (1951) gave the range as 10–20 per cent. Recent studies suggest that it is probably much less, around 5 per cent.

Owing to a thinner mucosa, a better blood supply and a larger surface area, the upper small intestine – the duodenum and jejunum – has the maximum capacity for absorption, compared with the gastric mucosa. This has practical implications, as drink taken by mouth will be absorbed more quickly when:

- a gastrectomy or gastroenterostomy has been carried out previously, as the drink will pass rapidly through to the upper small intestine
- the stomach is empty, as fluid will pass through the pylorus with almost no delay.

Conversely, when the stomach contains food, the drink will be held up until digestion has proceeded sufficiently for the contents to be released into the duodenum. A fatty meal will slow this process down even more and milk feed also has a marked delaying effect. Obviously some absorption will still occur in the interim via the gastric mucosa, but not at the same high rate as in the duodenum and jejunum. As well as delaying emptying, a full stomach will retard absorption by mixing with the alcohol and physically reducing its access to the gastric lining where transit into the blood takes place.

Another factor in the speed of absorption is the concentration of the alcohol. A strength of about 20 per cent is optimum for rapid absorption, which is met (in an empty stomach) by sherry or port wine, or spirits diluted with a 'mixer', such as gin and tonic or whisky and soda. It is also said that carbonated drinks (those containing dissolved carbon dioxide, such as champagne, tonic or soda water, or lemonade) hasten absorption, perhaps because the bubbles greatly increase the surface area carrying alcohol.

Dilute drinks, such as beer (with a concentration of about 4 per cent alcohol) will be absorbed much more slowly – probably because the large volume impedes access of the alcohol molecules to the stomach lining. Beer may take twice as long to absorb as stronger drinks, though part of the delay is caused by contained carbohydrates, which is another factor that slows absorption. For example, when whisky is diluted to the same strength as beer, absorption is more rapid and the peak is higher than drinking the same amount of alcohol in the form of beer.

Very strong drink slows the rate of transfer into the bloodstream. Neat spirits or liqueurs, which may be in excess of 40 per cent alcohol, cause:

- pyloric spasm and hence retarded emptying into the duodenum

- irritation of the gastric lining, forming a barrier of mucus, which slows absorption
- reduced gastric motility, which also retards emptying.

Given an empty stomach and an optimum concentration of alcohol, most of the drug will have entered the bloodstream between 30 and 90 minutes after drinking. According to research by Wilkinson *et al.* (1977), the average times to reach peak blood concentration were 22, 40, 55 and 60 minutes after drinking 11, 22, 36 and 45 g of alcohol in a bolus of similar volumes.

It has been calculated that 98 per cent of alcohol drunk would be absorbed within 10 minutes if it went straight into the small intestine – most of the delay is due to hold-up in the stomach. Rates vary greatly among different people and even in the same person at different times, irrespective of food being taken, but an acceptable mean time would be that 60 per cent of the imbibed alcohol would be absorbed within 60 minutes and 90 per cent within 90 minutes.

Food in the stomach can, however, at least double these times and a large fatty meal can delay total absorption for a number of hours. This has an important effect on the dynamic state between absorption and elimination, as the rate of the latter is relatively constant (see below) and can therefore deal with the slow delivery of alcohol from the portal blood so effectively that the peak of the blood-alcohol curve is low – indeed the curve becomes a long shallow curve instead of a sharp hillock. Where there is a legal threshold for blood alcohol in relation to driving, the taking of food can easily cause one person who has had a large meal to remain well under this limit, whereas another person who drank the same amount at the same time may rapidly exceed the threshold if he drank on an empty stomach. Incidentally, the same effect can occur, notwithstanding food, where a man and woman drink the same amount, as described earlier.

Some drugs will affect absorption rates, by modifying the speed of stomach emptying. Atropine, chlorpromazine, tricyclic antidepressants, procyclidine, amphetamines, morphine, antidiarrhoea compounds (e.g. Lomotil), codeine, methadone, heroin, pethidine, etc., will delay gastric transit, whilst the antiemetics cisapride and metoclopramide, as well as the antibiotic erythromycin, will hasten stomach emptying.

ELIMINATION OF ETHANOL

Almost all alcohol is detoxified by the liver, only 2–10 per cent being excreted unchanged. This means that a heavy drinking session places a great metabolic burden upon the liver and is the cause of hepatic damage after long-standing drinking. The elimination mechanism is an oxidation of alcohol by liver enzymes, through acetaldehyde to acetate. The first stage is performed by the enzyme alcohol dehydrogenase but, as the second stage is much more rapid, little acetaldehyde has time to accumulate. The acetic acid is rapidly oxidized further to carbon dioxide and water. Some may also be broken down by a microsomal oxidase system.

The rate of elimination is of crucial importance to the shape of the blood-alcohol curve, the height of its peak and to the duration of the alcoholaemia. It is also central to any attempts at retrospective calculations of blood, breath or urine levels, as discussed later. Whereas the rate of absorption is variable and is affected by a number of factors, the speed of detoxification in the liver is much more constant and relatively independent of external influences. This is not to say that it is fixed and immutable, even in the same person at different times, but it is capable of reasonable approximation. Much experiment and research has been devoted to this topic and the results, though variable, lie within a fairly narrow band.

Holford (1987) reviewed 11 different studies and found average rates varying between 12.6 and 26.8 mg/100 ml/hour. Neuteboom and Jones (1990) looked at levels in 1300 drivers stopped by the police, and calculated rates between 12 and 38 mg/100 ml/hour in 95 per cent of subjects. Several had rates over 48 mg/100 ml/hour. The elimination rate appeared to increase as the net blood concentration increased, for which several explanations are possible.

As a generalization, it has traditionally been assumed that blood alcohol declines, after the peak is reached, at a rate of around 15 mg/100 ml/hour, but more recent research, especially that of Holford, indicates that this should be raised to 18.7. This applies to healthy adults who are not habituated drinkers, and includes light to moderate drinkers and those 'binge drinkers' who may indulge heavily but intermittently. The enormous number of publications on alcohol must be consulted for details of the range of variation, but basically, elimination can vary from about 12 to 27 mg/100 ml/hour.

Taking the mean as around 18 mg, a man of average size can therefore destroy about 9 g alcohol/hour, with a range variation of between 7 and 16 g. This is about the same as the 'unit' of alcohol, a concept devised for convenience in estimating the daily or weekly intake of drinkers. A 'unit' is of 10 g and is contained (approximately) in half a pint of beer, one single measure of spirits, or a standard glass of table wine.

The habituated drinker, the 'chronic alcoholic', can eliminate far faster than the average person, at least until he suffers severe liver damage in the later stages of his addiction. Though there is some controversy about the experimental evidence, workers such as Bonnichsen (1966) have shown that the rate is greater in older people, at higher blood-alcohol levels, and in habituated drinkers. The rate in the latter may be in excess of 40 mg/100 ml/hour and work at

Lion Laboratories in Wales, who manufacture equipment for breath testing, have found rates over 50 mg/100 ml/hour in chronic alcoholics.

Between 90 and 98 per cent of ingested alcohol is removed from the blood by the liver, leaving a small residue to be excreted unchanged by the kidneys, lungs, sweat, salivary and mammary glands. The ethanol in glomerular filtrate is in equilibrium with plasma, but as water is absorbed in the renal tubules, the urine concentration is higher than the blood level at the time of filtration, the ratio being approximately 123:100. This means, for example, that the legal limit for driving in Britain of 80 mg/100 ml blood is taken to be 107 mg/100 ml in urine.

Unfortunately, it is obvious that, except in the highly unlikely circumstances of ureteric catheterization, the urine concentration can never accurately represent the blood concentration at any given time. The blood concentration is almost never static, but is either rising or falling, so the amount of alcohol in the glomerular filtrate is also constantly varying. It is being mixed in the bladder, however, with previously filtered urine and will also have that which is filtered later added to it, until the bladder is emptied – so it can only provide an average concentration for the time between two micturitions. An added error is that urine produced before drinking began (and which was therefore alcohol-free) may have already been in the bladder and will dilute the alcoholic urine. In many countries, where urine is used for drink–driving testing, the subject is instructed by the police to empty his or her bladder before collection is made over the subsequent hour, in order to avoid the dilution factor.

Breath is now used by many jurisdictions to measure alcohol intake, either as a screening test before blood is taken for analysis, or as an evidential method instead of blood or urine. There is still some controversy over the scientific accuracy of this method, but usually the results are so high that errors are immaterial – or in marginal results, more accurate blood testing is indicated.

Alveolar air at 37°C is in equilibrium with the pulmonary capillary plasma alcohol, the ratio being about 2300:1, volume to volume, for blood as against breath. There is some dispute as to the true ratio, which lies somewhere between 2100 and 2400. If sufficiently deep exhalation is made to drive out dead-space air, then the collected sample can be analysed to give a measure of the blood alcohol, though slight errors occur if there is incomplete elimination of dead-space air and a drop in temperature as the air travels through the dead space. In most countries using evidential breath testing, however, the offence is not in having a breath-alcohol level in excess of an equivalent blood level, but in having excess alcohol in the breath. This obviates defence ploys that would attempt to throw scientific doubt on the relationship between the two concentrations.

ALCOHOL CONCENTRATIONS: UNITS AND VARIOUS DRINKS

The concentration (often called the ‘level’) of alcohol in blood, urine and breath is expressed by a variety of metric units, which may lead to some confusion. The index most widely used for blood, urine and other body fluids is the weight of alcohol per volume of diluent – for example, milligrams per hundred millilitres (mg/100 ml). The expression ‘decilitre’ may be used instead of 100 ml (mg/dl). In some countries in continental Europe, alcohol concentration is expressed as ‘pro mille’, which is grams per litre (g/l), equivalent to milligrams per millilitre (mg/ml). Elsewhere, especially in the USA, a ‘percentage’ system is common, but can be ambiguous as it does not intrinsically state whether the percentage is volume/volume, volume/weight, weight/weight or weight/volume. Unless otherwise stated, it is assumed to be a weight/volume.

Breath is almost universally measured as micrograms per hundred millilitres (μg/100 ml). The matter of weight and volume is important in respect of alcohol concentrations. The specific gravity of alcohol is 0.79, the compound being appreciably lighter than water. In alcoholic drinks, the manufacturer’s description and labelling is almost always ‘volume/volume’ (v/v), but physiological calculations are made via the weight of alcohol in a given volume of body fluid (w/v). Therefore, especially for stronger alcoholic drinks, a conversion has to be made. For example, many spirits, such as whisky, may be labelled as 40 per cent v/v, but this would be only about 32 per cent weight/volume. For weak drinks, such as beer, it is hardly worth correcting the 4 per cent v/v, as calculations have a far greater intrinsic error from other factors.

Approximate strengths of common drinks are as follows (all v/v):

- beer, lager, stout: 3–5 per cent
- cider (variable): 5 per cent
- table wines (unfortified): 9–12 per cent
- fortified wines (sherry, port, vermouth): 18–20 per cent
- spirits (brandy, gin, whisky, rum, vodka): 37–42 per cent
- liqueurs (variable): 15–55 per cent.

The practice of using ‘units of alcohol’ has become popular in recent years, not so much for calculating concentrations, but for approximate estimates of intake, in relation to excessive drinking and the long-term medical consequences of alcohol consumption. A ‘unit’ is of the order of 10 per cent ethanol and very approximately delivered by ‘one drink’, where this is either a half pint of beer, one glass of table wine or one small measure of spirits. For example, it has been recommended that men should not exceed about 20 units per week and women 14, to avoid the risk of liver damage. It has recently been claimed that from statistical analysis of forensic autopsy material, the risk of coronary heart disease can be reduced by drinking 2 units a day (Thomsen 1995).

Calculation of blood levels from drink taken and the converse

The most important statement in this respect is to stress the utter unreliability and inaccuracy of attempting back-calculations in either direction. Only gross approximations can be achieved and no pretence at accuracy must be offered. In this book, we are not concerned with the controversial problems of trying to estimate blood or breath levels in living vehicle drivers at some time prior to an accident or other event, but with similar problems that can arise in fatal cases, especially in relation to drink and driving. In both criminal and civil disputes, evidence is often sought as to the alcoholic state of the deceased at some material time, based on calculations made from blood or urine alcohol analyses taken at autopsy. Less often, aviation, railway, diving and industrial fatalities may present the same potential problem. Criminal proceedings may arise because of alleged reckless driving on the part of another, when the drunken state of the deceased victim may offer some defence. In civil matters, often involving insurance companies, a significant blood-alcohol level may be used as contributory negligence.

Whatever the reason, the pathologist must offer interpretations of alcohol levels found at autopsy with caution, especially where retrospective calculations are requested. Less often, the pathologist may be asked what blood or urine levels might be expected at a certain time (for example, at the time of death) given a description and timetable of alcoholic drinks taken by the deceased. The same cautions against overprecise calculations must be offered here. In calculating approximate blood levels from a knowledge of the drink taken, there are several methods in use: either the well-known 'Widmark factor' or other calculations, which are really modifications or simplifications of the Widmark technique.

Widmark, in 1932, produced his well-known formula for calculating the total amount of alcohol in the body, from which knowing the body weight and assuming equilibration throughout the water compartment, the blood-alcohol level could be derived.

The Widmark equation is: $A = R \times P \times C$, where A is the total body alcohol, C the blood concentration, P the body weight in kilograms and R a factor, which is 0.68 in men and 0.55 in women. The sex difference is due to the different fat:water ratios, men having about 54 per cent and women 44 per cent water partition by weight.

Much research and modification of Widmark's factors has been carried out. Hume and Fitzgerald (1985) claimed that the use of body water distribution was too complex. Gullberg and Jones (1994) have published data on a re-evaluation of the Widmark equation, in which they claim to be able to estimate from a single blood-alcohol determination, the amount of alcohol consumed, within an error of ±20 per cent. Pounder and Kuroda (1994) claim that the use of vitreous fluid (which is sometimes used in decomposed or damaged bodies in place of blood) to predict the blood-alcohol concentration, is too variable to be of practical use.

A useful approximate calculation, derived from Widmark, is that an intake of 0.2 g of alcohol per kilogram body weight is likely to result in a blood-alcohol concentration in men of about 25 mg/100 ml.

The following facts are of use:

- The average rate of decline of blood alcohol after the peak of the curve is reached, may be taken as about 15 mg/100 ml/hour, though recent research suggests 18 as more accurate.
- The weight of alcohol imbibed may be calculated from knowledge of the v/v strength of the liquor and the amount taken. For example, if a 'double' British measure of 40 per cent v/v whisky is drunk, then 15 ml will contain $(40 \times 0.8) = 32$ per cent alcohol w/v in $15\ \text{ml} = 4.8\ \text{g}$.
- The weight of alcohol/kg body weight is calculated.
- A ratio of 0.2 g alcohol/kg body weight will produce a blood level of approximately 25 mg/100 ml in a man, assuming an empty stomach.
- In women, the level so produced may be 20–25 per cent higher.
- If only beer is drunk, the peak will be considerably less, sometimes only 50 per cent that produced from wine or spirits.
- Drinking during or after a meal markedly flattens the blood–alcohol curve.

PHYSIOLOGICAL EFFECTS OF ALCOHOL

The pathologist is frequently asked in either written opinions or in court testimony to give an estimate of the behavioural state of a victim at a certain level of blood alcohol or after having taken a specified amount of drink. Though he is usually not qualified as an expert on alcoholism in any

TABLE 28.1 *General spectrum of behaviour (mg/100 ml of alcohol in blood)*

Above 30	Impairment of complex skills such as driving
30–50	Definite deterioration in driving ability
50–100	Objective signs such as loquaciousness, progressive loss of inhibitions, laughter and some sensory disturbance
100–150	Slurred speech, unsteadiness, possible nausea
150–200	Obvious drunkenness, nausea, staggering gait
200–300	Stupor, vomiting, possibly coma
300–350	Stupor or coma, danger of aspirating vomit
Over 350	Progressive danger of death from respiratory centre paralysis

clinical sense, he will be a medical practitioner with general knowledge and some personal experience of alcoholic behaviour, from his pre-pathology years. He thus can give a general opinion to assist the court, but unless he has special experience of the matter, he should not extend himself into detailed clinical expositions, which are the province of the psychiatrist with an interest in alcoholism, a police surgeon or a casualty officer, all of whom deal frequently with drunken patients. A general level of knowledge can be offered to the lawyer, police or court, however, especially in respect of the usual level of capability and consciousness at different blood-alcohol levels (Table 28.1).

The list in Table 28.1 is probably ‘worst case’ in nature, as many people show less effects at given blood levels. Women are usually more affected at lower levels, though the ‘world record’ for survival may be a woman who survived a blood alcohol of 1510 mg/100 ml (Johnson *et al.* 1982). Many drivers stopped by the police at random road blocks in Australia had blood levels over 500 mg/100 ml.

MODES OF DEATH IN ACUTE ALCOHOLISM

Death from alcoholic poisoning is not uncommon and can occur at blood levels in excess of about 300 mg/100 ml. Johnson *et al.* (1982) claimed that some deaths could be attributed to alcohol at even lower concentrations. Death can be caused either by the direct depressive effects upon the brainstem, mediated via the respiratory centres – or through secondary events such as aspiration of vomit. As discussed in Chapter 14, the use of ‘aspiration of vomit’ as a cause of death must be used with great caution unless there is ante-mortem eyewitness evidence. The major exception to this proviso is in acute alcoholism, where if copious inhalation of stomach contents right down to the secondary bronchi is confirmed, then in the absence of significant natural disease, injury or other toxicity, a high blood-alcohol level may reasonably be incriminated as the probable cause. Many such fatalities occur during police custody, when considerable outcry, publicity and disciplinary investigations are the usual outcome.

Drunken persons are often involved in fatal trauma, which may be of many types. The majority of homicides are triggered by the aggressive behaviour engendered by alcohol. Road accidents, either caused by drunken drivers (often upon themselves) or by drunken pedestrians walking into traffic, are commonly related to alcoholic vulnerability. Falls are extremely frequent and often fatal. Drunken persons may fall down stairs or steps and suffer head injuries. Falls from high places are less common, but do occur from drunken carelessness or unsteady gait – exemplified by the notorious inquest on Helen Smith in Leeds in 1982.

Death from burns or carbon monoxide poisoning may occur in drunken persons who smoke when intoxicated. A common scenario is for a drunk to go to bed and fall asleep whilst smoking, the cigarette igniting the bedclothes. Sometimes, a gas, electric or kerosene heater may be knocked over during drunken staggering, which again starts a fatal fire.

Drowning is seen occasionally, especially in river or dockland areas. A typical happening is for a drunken sailor to return to his ship late at night, and fall from a bridge or gangway into the water. Death is sometimes not caused by drowning, but by sudden vagal cardiac arrest from the shock of hitting cold water or having cold water suddenly flood the pharynx and larynx. The drunken state seems to sensitize the victim to such vasovagal shock, perhaps because of the marked cutaneous vasodilatation encouraged by alcohol. The author (BK) has seen a number of such tragedies in Cardiff dockland, including a sailor and his woman companion, who both fell off the ship after carousing.

CHRONIC ALCOHOLISM

The pathological features of this condition are extensive and can only be surveyed briefly here. In this context, chronic alcoholism refers to the steady, regular abuse of drink, rather than intermittent ‘binge’ drinking, which gives the tissues time to recover between bouts of acute alcoholism.

At autopsy, there may be signs of general neglect and malnutrition, but many chronic alcoholics are obese or even oedematous, the latter because of chronic heart failure. The specific lesions are in the liver, heart and brain, though they may be difficult to identify as unequivocally caused by alcohol. The early stages of liver damage cause fatty change, usually with enlargement. The normal weight, according to the sex and build, is between 1300 and 1600 g, but a fatty liver may be well in excess of 2000 g.

The surface is pale and greasy, though this may not be a uniform change, especially in early or less severe cases. Patchy yellowish areas may be visible within normal hepatic parenchyma.

If the abuse continues, then the fatty change may eventually give way to fibrosis, the liver surface becoming rippled beneath its capsule. Such cirrhosis is fairly fine, with nodules of the order of 5–10 mm in diameter. In the later stages the liver becomes smaller and contracts to a hard, greyish-yellow block of only 800–1200 g.

Without a history of long-term alcohol abuse, it is difficult or impossible to be definite about the aetiology purely on autopsy appearances, though suspicion may be strong. A similar liver may develop as a sequel to hepatitis – and less often as an end result of certain dietary or metabolic defects. The spleen may be enlarged and firm, and portal varices may be present at the gastro-oesophageal junction, but these are both manifestations of portal hypertension and do not assist in determining the precise aetiology of the hepatic fibrosis. A useful index of liver damage and the progression or remission of alcoholic impairment is the level of the enzyme γ-glutamyl transpeptidase in the serum. Normal levels are less than 36 units, whereas liver damage can elevate this by a factor of many times. Alcoholic cardiomyopathy is certainly a real entity and can be diagnosed clinically. Whether it can be definitely identified on histological appearances alone is a matter of dispute. The heart is enlarged and shows patchy fibrosis with a variable mixed cellular infiltrate, hypertrophy of muscle fibres, patchy necrosis, hyalinization, oedema and vacuolization. Nuclear enlargement and polymorphism complete the range of changes, but none of these are specific, being found in hypertensive heart disease, coronary stenosis and other types of myocarditis. Combined with a definite history of chronic alcoholism, however, these relatively non-specific changes can be ascribed to alcohol if other causes can be excluded (see also Chapter 25). More specific myocardial damage has been caused by cobalt added to commercial beers and several outbreaks are on record. Systemic fat embolism has also been recorded in victims of alcoholic fatty liver. Microinfarcts in myocardium and brain are possible, though this aspect has so far been rather neglected in research. Fat stains are not usually employed in routine investigations and it is not known how the victims of a fatty liver compare with control subjects in respect of diffuse target organ embolism.

REFERENCES AND FURTHER READING

Al Lanqawi Y, Moreland TA, McEwen J, *et al.* 1992. Ethanol kinetics: extent of error in back extrapolation procedures [see comments]. *Br J Clin Pharmacol* **34**:316–21.

Alha A. 1951. Blood alcohol and inebriation in Finnish men. *Am Acad Sci (Fen Series A)* **V**:Medica.

Bonnichsen R. 1966. Oxidation of alcohol. *Q J Stud Alcohol* **27**:554–60.

Brownlie AR, Walls HJ. 1985. *Drink, drugs and driving*, 2nd edn. Sweet and Maxwell, London.

Buono MJ. 1999. Sweat ethanol concentrations are highly correlated with co-existing blood values in humans. *Exp Physiol* **84**:401–4.

Chikasue F, Yashiki M, Miyazaki T, *et al.* 1988. Abnormally high alcohol concentration in the heart blood. *Forensic Sci Int* **39**:189–95.

Dick GL, Stone HM. 1987. Alcohol loss arising from microbial contamination of drivers' blood specimens. *Forensic Sci Int* **34**:17–27.

Freireich AW, Bidanset JH, Lukash L. 1975. Alcohol levels in intracranial blood clots. *J Forensic Sci* **20**:83–5.

Gibson AG. 1975. Alcohol can be absorbed through the respiratory tract (a case report). *Med Sci Law* **15**:64.

Grant SA, Millar K, Kenny GN. 2000. Blood alcohol concentration and psychomotor effects. *Br J Anaesth* **85**:401–6.

Gullberg RG, Jones AW. 1994. Guidelines for estimating the amount of alcohol consumed from a single measurement of blood alcohol concentration: Re-evaluation of Widmark's equation. *Forensic Sci Int* **69**:119–30.

Helander A, Jones AW. 2002. [5-HTOL – a new biochemical alcohol marker with forensic applications.] *Lakartidningen* **99**:3950–4.

Holford NH. 1987. Clinical pharmacokinetics of ethanol. *Clin Pharmacokinet* **13**:273–92.

Hume DN, Fitzgerald EF. 1985. Chemical tests for intoxication: what do the numbers really mean? *Anal Chem* **57**:876A–878A, 882A, 884A passim.

Johnson RA, Noll EC, Rodney WM. 1982. Survival after a serum ethanol concentration of 1½% [letter]. *Lancet* **2**:1394.

Jones AW. 2000. Aspects of in-vivo pharmacokinetics of ethanol. *Alcohol Clin Exp Res* **24**:400–2.

Jones AW, Jonsson KA, Kechagias S. 1997. Effect of high-fat, high-protein, and high-carbohydrate meals on the pharmacokinetics of a small dose of ethanol. *Br J Clin Pharmacol* **44**:521–6.

Kalant H. 2000. Effects of food and body composition on blood alcohol curves. *Alcohol Clin Exp Res* **24**:413–14.

King LA. 1983. Nomograms for relating blood and urine alcohol concentrations with quantity of alcohol consumed. *J Forensic Sci Soc* **23**:213–17.

Kubo S, Dankwarth G, Püschel K. 1991. Blood alcohol concentrations of sudden unexpected deaths and non-natural deaths. *Forensic Sci Int* **52**:77–84.

Lahti RA, Vuori E. 2002. Fatal alcohol poisoning: medico-legal practices and mortality statistics. *Forensic Sci Int* **126**:203–9.

Lieber CS. 2000. Ethnic and gender differences in ethanol metabolism. *Alcohol Clin Exp Res* **24**:417–18.

Lieber CS, Davidson CS. 1962. Some metabolic effects of ethyl alcohol. *Am J Med* **33**:319–27.

Logan BK, Case GA, Distefano S. 1999. Alcohol content of beer and malt beverages: forensic consideration. *J Forensic Sci* **44**:1292–5.

Mason JK, Blackmore DJ. 1972. Experimental inhalation of ethanol vapour. *Med Sci Law* **12**:205–8.

Neuteboom W, Jones AW. 1990. Disappearance rate of alcohol from the blood of drunk drivers calculated from two consecutive samples; what do the results really mean? *Forensic Sci Int* **45**:107–15.

Nickolls LC. 1956. *The scientific investigation of crime.* Butterworths, London.

Paton A. 1988. *ABC of alcohol.* British Medical Journal publication, London.

Piette M, Timperman J, Vanheule A. 1986. Is zinc a reliable biochemical marker of chronic alcoholism in the overall context of a medico-legal autopsy? *Forensic Sci Int* **31**:213–23.

Plueckhahn VD. 1968. Alcohol levels in autopsy heart blood. *J Forensic Med* **15**:12–21.

Plueckhahn VD, Ballard B. 1968. Factors influencing the significance of alcohol concentrations in autopsy blood samples. *Med J Aust* **1**:939–43.

Pounder DJ, Kuroda N. 1994. Vitreous alcohol is of limited value in predicting blood alcohol [see comments]. *Forensic Sci Int* **65**:73–80.

Roine R. 2000. Interaction of prandial state and beverage concentration on alcohol absorption. *Alcohol Clin Exp Res* **24**:411–12.

Sunter JP, Heath AB, Ranasinghe H. 1978. Alcohol associated mortality in Newcastle upon Tyne. *Med Sci Law* **18**:84–9.

Thomsen JL. 1995. Atherosclerosis in alcoholics. *Forensic Sci Int* **75**:121–31.

Thomsen JL, Felby S, Theilade P, *et al.* 1995. Alcoholic ketoacidosis as a cause of death in forensic cases. *Forensic Sci Int* **75**:163–71.

Wilkinson PK, Sedman AJ, Sakmar E, *et al.* 1977. Pharmacokinetics of ethanol after oral administration in the fasting state. *J Pharmacokinet Biopharm* **5**:207–24.

Winek CL, Eastly P. 1976. Factors affecting contamination of blood samples for ethanol determination. In: Wecht C (ed.), *Legal medicine annual 1976.* Appleton Century Crofts, New York.

Winek CL, Esposito FM. 1985. Blood alcohol concentrations; factors affecting predictions. In: Wecht C (ed.), *Legal medicine annual 1985.* Praeger Scientific, New York.

Winek CL, Jr, Winek CL, Wahba WW. 1995. The role of trauma in postmortem blood alcohol determination [see comments]. *Forensic Sci Int* **71**:1–8.

CHAPTER 29

Carbon monoxide poisoning

■ Causes of carbon monoxide poisoning 560
■ The autopsy in carbon monoxide poisoning 562
■ Blood analysis 563
■ References and further reading 564

CAUSES OF CARBON MONOXIDE POISONING

After alcohol and some pharmaceutical drugs, carbon monoxide poisoning is probably the most common toxic condition to be met with in routine forensic pathology. The widespread introduction of natural gas (which contains no carbon monoxide) as a replacement for 'coal gas' as a heating fuel has removed a major source of the poison. Monoxide still provides lethal dangers in many other ways, however. It is produced whenever fossil fuels are incompletely oxidized to carbon dioxide and, because of its great affinity for haemoglobin, even low concentrations can be cumulative.

There are a vast number of publications on carbon monoxide toxicity, both in an environmental and industrial context. Once again, this discussion is confined to the pathologist's involvement in fatalities. A body coming to autopsy with suspected (or sometimes unsuspected) carbon monoxide poisoning, will have suffered that toxic condition by the following means.

Motor vehicle exhaust gases

Since the replacement of coal gas (containing up to 7 per cent monoxide) with natural gas, a major means of suicide has been removed. 'Putting the head in the gas oven' was the most common form of self-destruction in Britain and many other countries until this changeover. In 1961 in the UK, for example, there were 2711 suicides and 1014 accidental deaths from carbon monoxide. Since then, suicides have obtained carbon monoxide to kill themselves from the internal combustion engine. Petrol (gasoline) engines produce up to 5–7 per cent carbon monoxide in their exhaust fumes, and more if the engine is idling, defective or improperly tuned. Diesels produce far less monoxide than petrol engines. Normally, the exhaust pipe vents the gases into the atmosphere, where it may contribute to considerable low-level monoxide contamination in large cities, such that policemen on traffic duty may have up to 10 per cent saturation of their haemoglobin. When the exhaust fumes are confined to a small space, then a dangerous or lethal level can build up in a short space of time. It is calculated that a 1.5 litre petrol engine, idling in a closed single garage, can produce a lethal concentration in the atmosphere within 10 minutes.

Some suicides will merely sit in the garaged car with a window open and allow the gas to overtake them. More commonly, some device is fitted to pipe the gas into the interior of the car and this may be done outside a garage, often in a remote parking spot. The flexible tube from a vacuum cleaner seems a favourite means, though ordinary hose-pipe, pushed inside the tail-pipe and led in through a window, is a common alternative. Apart from suicide, accidental poisoning sometimes occurs in relation to internal combustion engines. A mechanic or car owner may work on a vehicle in a closed garage, especially in cold weather, and be overcome by monoxide before he is able to remove himself from the danger. The insidious nature of the toxic effects may make him unaware of the supervening stupor and coma.

Carbon monoxide can also affect drivers of a moving vehicle, usually because of a defective exhaust system, which allows gas to percolate through the floor or engine bulkhead into the interior. Rarely, a strong following wind blows the external exhaust gas into the open doors of a van or truck. Another motoring cause is a leak in the heat exchanger in those vehicles that use a direct air supply from around the exhaust manifold to provide passenger heating.

In aircraft – usually light planes with the engine immediately adjacent to the cockpit – a leakage of exhaust gas from the motor compartment can lead to disablement of the pilot and death from a crash rather than from fatal toxicity. The same applies to those road-vehicle drivers who are overcome by the gas to an extent that makes them incapable of driving safely. The differential diagnosis in survivors is between carbon monoxide and alcohol, as the clinical symptoms of both are quite similar at one stage of the toxic process.

Deaths have also been reported in 'scuba' divers, whose air cylinders have been contaminated with carbon monoxide during refilling from faulty petrol-driven compressors.

Domestic appliances

Domestic heating appliances can produce carbon monoxide in addition to the usual dioxide from a restriction of their air supply, so that incomplete combustion of the fuel takes place. The fuel can be natural gas, which, though itself free from monoxide, is only partially oxidized from some defect of design, maintenance, or patency of the exhaust flue. Solid-fuel boilers used for central heating may have some restriction of air entry or a partial blockage of the chimney system. Paraffin (kerosene) heaters may burn with inadequate oxygen ingress and any other form of hydrocarbon fuel appliance can malfunction so that part of the products of combustion are monoxide.

The author (BK) has dealt with several deaths that occurred because the faulty installation of natural-gas fires led to absent or inadequate ventilation, causing monoxide to back-diffuse into living rooms. Gas appliances, especially water heaters, are one reason why the bathroom is such a dangerous place. Apart from the extra hazards of electricity, a bath for drowning, wet surfaces for slipping, tablets in the cabinet and sharp instruments such as razor blades, the small-sized room and the frequent installation of a gas water heater or 'geyser' makes this room a frequent locus for unnatural death. Blockage of the exit or 'flue' pipe is a common fault, sometimes from bad installation or because it becomes blocked by soot or by birds' nests.

Structural fires

A common cause of monoxide deaths arises from structural fires in houses and other buildings. As described in Chapter 11, the majority of deaths in house conflagrations are caused not by burns, but by inhalation of smoke. These fatalities are largely caused by carbon monoxide poisoning, though other lethal gases such as cyanide, phosgene and acroleins are partly responsible. Many victims of house fires die remote from the flames, and may be overcome in different rooms or even on different floors, the monoxide percolating considerable distances and killing persons either asleep or trapped elsewhere in the building.



FIGURE 29.1 *Carbon monoxide poisoning in a chronic alcoholic. This is a relatively common event when a drunken person collapses with a lit cigarette across his bed (note the ashtray and cigarette packet). The burns are post-mortem, death being caused by a high level of carboxyhaemoglobin generated by the smouldering bed coverings.*

Industrial processes

Many industrial processes may lead to monoxide poisoning, especially in iron and steel works, where producer gas and water gas are deliberately formed and stored as part of the manufacturing process. Water gas can contain up to 40 per cent carbon monoxide and in former days was added to town gas for the domestic supply, which greatly enhanced the monoxide content of some 7 per cent from coal gas. Many other industrial processes, such as the Mond method of nickel production, use carbon monoxide, as well as the universal danger of any heating process producing the gas during combustion. In coal-mining, carbon monoxide is one of the gases that presents a constant threat; it escapes from the coal seams themselves but is also produced from the frequent small fires that smoulder in the recesses of the mines.

Incomplete combustion

Incomplete combustion of a gas flame from any gaseous fuel can produce carbon monoxide. Where such a flame impinges on a cold metal surface or where that surface is coated with soot, partial oxidation of the fuel supply leads to monoxide production. In appliances fuelled from the common butane or propane cylinder sources, as in caravans, campers and boats, maladjustment or restriction of ventilation can lead to slow but insidious production of monoxide. Deaths of whole families have occurred under such circumstances, as they are exposed overnight to slow accumulation of carbon monoxide from refrigerators and other appliances.

THE AUTOPSY IN CARBON MONOXIDE POISONING

As always, an adequate history may give the clue to the cause of death. Where the circumstances are obvious, such as a death in a car with a tube leading from the exhaust, the pathologist's attention will be directed towards carbon monoxide from the outset. There are many other circumstances, however, in which the history may be obscure, and only the vigilance of the pathologist and his staff will pick up the possibility of this type of toxicity. In fact, many a case has first been recognized by the mortuary technician who commented on the colour of the skin or tissues. A number of fatal monoxide poisonings have already been certified as 'natural causes' by uncritical clinicians (especially in general practice) when in fact carbon monoxide poisoning, either suicidal or accidental, was the true reason for the death. Failure to examine the body fully is the usual cause, as the pink coloration may only be noticeable in the areas of postural hypostasis not normally visible in a body in bed, though the sides and back of the neck are reasonably accessible even to cursory examination. The author (BK) recollects at least one suicide where the relatives placed the body back in bed and had it certified as 'coronary thrombosis' by an unsuspecting family doctor.

At autopsy the most striking appearance of the body is the colour of the skin, especially in areas of post-mortem hypostasis. The classical 'cherry-pink' colour of carboxyhaemoglobin is usually evident if the saturation of the blood exceeds about 30 per cent. Below this, familiarity and good lighting are needed and below 20 per cent, no coloration is visible. As these low concentrations are rarely fatal, however, little is lost. Sometimes, darker cyanosis tends to mask the skin colour, but the margins of the hypostasis and the internal tints are usually apparent.

When the victim is anaemic, the colour may be faint or even absent because insufficient haemoglobin is present to display the colour. In racially pigmented victims the colour may obviously be masked, though may still be seen on the inner aspect of the lips, the nail-beds, tongue, and palms and soles of the hands and feet. It is also seen inside the eyelids, but rarely in the sclera.

Rarely, there may be blistering of the skin of dependent areas, such as the calves and buttocks, and around wrists and knees, similar to the so-called 'barbiturate blisters'. These are not specific to carbon monoxide toxicity and are the result of cutaneous oedema in any profound coma where there is total immobility and lack of venous return from muscle movement. As most carbon monoxide deaths are relatively rapid, such blisters are rare. Internally the most noticeable feature is again the colour. Blood and muscle will be pink as a result of carboxyhaemoglobin and carboxymyoglobin. In relatively low concentrations, in poor light and in some artificial lighting in autopsy rooms, the cherry-pink colour may be difficult to see. It can be enhanced by diluting the blood with water against a white background, as in a porcelain sink or an enamel scale-pan, when the pinkness will be more evident. The pinkness of hypothermia or refrigeration is a different colour. Unfortunately, some pathologists have a red-colour visual impairment, which makes it difficult for them to differentiate between subtle changes in redness, so laboratory analysis is always required for objective confirmation and quantification of the monoxide concentration. Other suggestive indications of carbon monoxide are that, when tissues are placed in formol saline for preservation of histology, they do not decolourize as quickly as normal tissues and remain pink for a long period. If carbon monoxide poisoning is suspected at autopsy, a quick test is to add a few drops of blood to some 10 per cent sodium hydroxide solution on a white tile or in a tube against a white background. The normal blood will immediately become brownish-green but, if significant monoxide is present, the colour will remain pink, as no methaemoglobin is formed. One has to bear in mind though, that unlike adult blood, fetal blood up to the age of 6 months is more resistant to alkali and the colour change can take hours to develop. Another simple test, mentioned in 1857 by Hoppe, is to take 3 ml blood into a test tube and dilute it with 6 ml tap water and to heat it for a short while with care in a water bath. Carbon monoxide blood turns brick red whereas control blood becomes greyish-brown. However, these crude tests are not recommended as an alternative to proper analysis.

Other signs at autopsy are non-specific. Pulmonary oedema is usually present. The author (BK) has the impression that the white matter of the brain remains unusually firm and that the whole brain after removal from the skull keeps its shape better, being rather stiff and rigid. This may be caused either by oedema or by some minimal fixation change in the brain tissue.

None of these rather idiosyncratic tests can replace proper laboratory investigation, however. Blood should be taken for analysis in the usual way, preferably from a peripheral vein. In contrast to most toxicological investigations, even foul samples can still be useful for carboxyhaemoglobin estimations. Heart blood, blood from body cavities and even from bone marrow when the bones are split open, can still provide valid material for estimating the percentage of haemoglobin converted to carboxyhaemoglobin. It is the



FIGURE 29.2 *Basal ganglia degeneration after carbon monoxide poisoning. The patient survived for a number of weeks, but succumbed to bronchopneumonia. There are cystic lesions in the globus area of both cerebral hemispheres.*

ratio of haemoglobin to the carboxy-type that is required, rather than an absolute concentration in the blood, so virtually any blood-containing fluid will provide this answer. When a body has been badly damaged by fire, fluid blood may be hard to obtain, so that any sanguineous body fluid or bone marrow can provide material for analysis. If analysis is to be delayed more than a day, it is recommended that fluoride be added as a preservative.

There are no other autopsy features in acute deaths, which form the majority seen by forensic pathologists. Where survival occurs there are a number of neurological lesions that follow severe carbon monoxide exposure. Necrosis and cavitation of the basal ganglia in the brain, notably the putamen and globus pallidus, has been known for well over a century. Within about 5 days, histological changes occur here, with 'gitterzellen' scavenging cellular debris, the foam cells and microglia presenting an appearance characteristic of tissue breakdown in the central nervous system. There may also be damage in the substantia nigra of the brainstem. In delayed deaths, petechiae and ring-shaped haemorrhages may occur in the cerebral white matter. All these changes, together with the clinical symptomatology, are exhaustively described in neurological publications.

There are also tiny focal necroses in the myocardium in delayed deaths from this cause, and similar lesions were described by Korb and David (1962) even in acute deaths. Frank myocardial infarction has often been reported after severe monoxide exposure and relative hypoxia, usually in the presence of pre-existing coronary disease, is probably the reason.

BLOOD ANALYSIS

Carbon monoxide has an affinity for haemoglobin that is between 200 and 300 times greater than oxygen. Therefore even small concentrations of monoxide in the inspired air will progressively displace oxygen from the erythrocytes and this will lower the oxygen-carrying capacity of the blood. It was formerly thought that all the toxic properties of carbon monoxide lay in this hypoxic action, but more recently it has been shown to interfere with other ferroproteins such as myoglobin and various enzymes including members of the cytochrome family.

The major effect is undoubtedly the reduction in oxygen transport and, for this reason, it is the percentage saturation of the total available haemoglobin that is important rather than an absolute quantity of carboxyhaemoglobin in the blood. Anaemic persons will not show the external cherry-pink colour if insufficient haemoglobin is available for the monoxide component to become visible. It is the residual non-combined haemoglobin still available for oxygen transport that is important in maintaining life. For example, an anaemic person with only 8 g/100 ml of haemoglobin having four of those occupied with carbon monoxide (50 per cent saturation) is in much worse a state than a person with a total of 14 g of which four are monoxide-occupied. There are many tables available that relate saturation levels to the clinical symptoms. There is a wide margin of variation in these, as there is with lethal levels.

Broadly speaking, the saturation levels found in fatal cases reflect both the physical state of the victim and the rapidity with which the poisoning took place. Robust, healthy adults under 60 years of age rarely die at saturation level under 50–60 per cent unless the concentration of carbon monoxide in the inspired air was so great that death occurred before gas exchange in the lungs was able to progress sufficiently to enter all available monoxide into the red cells. Death may then supervene with post-mortem saturation levels of as low as 40 per cent. Where absorption is slow and life persists longer (for there seems to be a relationship between air concentration of monoxide and length of survival), autopsy samples may show 80 per cent saturation.

Old people may die at relatively low concentrations, such as 30 per cent and, in some cases, no other cause can be found when the carboxyhaemoglobin level is only 25 per cent. This may be the result of anaemia, so that there is less reserve for oxygen carrying when part of the haemoglobin is occupied by monoxide. In many cases, the senile myocardium is already in a fragile state and any extra hypoxia will cause it to fail. Infants also seem to die at relatively low levels, perhaps because their higher respiration rate allows a more rapid absorption. The variation in fatal concentrations is wide and quite irregular. This is best exemplified when two or more victims have died together in the same environment. The carboxyhaemoglobin concentrations of bodies lying alongside each other can sometimes be totally different, even in persons of the same age group and physical health. Any disease process can contribute to death at lower monoxide concentrations. Coronary artery disease, respiratory insufficiency and other debilitating conditions allow death to occur earlier, when the toxic level is still relatively low. Conditions that are worsened by hypoxia, such as myocardial insufficiency or obstructive airway disease, are particularly potent. In addition to disease, any separate toxic state is additive, such as hypnotic drugs or alcohol.

The method of analysis has traditionally been by reversion spectroscopy, but this is a crude technique in which accuracy cannot be attained to within 10 per cent of the true value. For most purposes related to fatalities, this is good enough, as more exact results do not add anything to the investigation. The only problem can be at the lower end of the scale, when it is difficult to be certain about positivity under about 15 per cent. Modern analytical methods include non-dispersive infrared spectrophotometry and gas chromatography. Carboxyhaemoglobin is stable and can be detected even in putrefied bodies a long time after death, as long as sophisticated laboratory techniques are used. Monoxide cannot enter a body post-mortem to any significant extent. Bodies burnt after death do not absorb any monoxide and thus a significant level (more than 10 per cent) in a body from a fire means that respiration must have been proceeding whilst the conflagration was in progress. As emphasized in Chapter 11, the converse is often not true, in that deaths from rapid fires, especially flash fires caused by petrol, for example, may have no carboxyhaemoglobin in the blood. The possibility of carboxhaemoglobin being formed in the blood post-mortem has been investigated as a possible source of error (Kojima *et al.* 1982) and fluorided samples are recommended.

A minor source of local carboxyhaemoglobin and myohaemoglobin is gunshot wounds, where the propellant gases (which are rich in the compound) are blown into the wound from contact or short-range discharges. The tissues absorb monoxide, especially around the entrance wound. It has been claimed that this is a way of differentiating the entrance from the exit wound, but in fact the whole track of the missile(s) may be sheathed in a zone of monoxide transfer into blood and muscle from a near-discharge, though theoretically there should be a gradient of concentration from one end of the track to the other (see Chapter 8).

Many other war, military and terrorist circumstances are associated with exposure to carbon monoxide. Large quantities are released from the firing of guns and, in enclosed spaces, can become a hazard. Detonation of explosives in places where there is little ventilation also allows monoxide to accumulate and it may persist long after the physical dangers of the explosion have passed.

REFERENCES AND FURTHER READING

Annotation. 1962. Carbon monoxide from paraffin stoves. *Br Med J* **1**:312.

Bohnert M, Weinmann W, Pollak S. 1999. Spectrophotometric evaluation of postmortem lividity. *Forensic Sci Int* **99**:149–58.

Bowen DAL. 1986. Acute renal failure in carbon monoxide poisoning. *J Forensic Med* **7**:78–82.

Chang MY, Lin JL. 2001. Central diabetes insipidus following carbon monoxide poisoning. *Am J Nephrol* **21**:145–9.

Chaturvedi AK, Smith DR, Canfield DV. 2001. Blood carbon monoxide and hydrogen cyanide concentrations in the fatalities of fire and non-fire associated civil aviation accidents, 1991–1998. *Forensic Sci Int* **121**:183–8.

Garland H, Pearce J. 1967. Neurological complications of carbon monoxide poisoning. *Q J Med* **36**:445–55.

Goldbaum LR. 1977. Is carboxyhaemoglobin concentration the indicator of carbon monoxide toxicity? In: Wecht C (ed.), *Legal medicine annual 1976*. Appleton Century Crofts, New York.

Goldsmith JR, Landaw SA. 1968. Carbon monoxide and human health. *Science* **162**:1352–9.

Gottfried JA, Chatterjee A. 2001. Carbon monoxide-mediated hippocampal injury. *Neurology* **57**:17.

Helpern M, Strassman G. 1943. Differentiation of fetal and adult human hemoglobin. *Arch Pathol* **35**:776.

Hoppe F. 1857. Über die Einwirkung des Kohlenoxydgases auf das Hämatoglobin. *Virchows Arch* **11**:228.

King LA. 1983. Effect of ethanol in fatal carbon monoxide poisonings. *Hum Toxicol* **2**:155–7.

Kojima T, Nishiyama Y, Yashiki M, *et al.* 1982. Postmortem formation of carbon monoxide. *Forensic Sci Int* **19**:243–8.

Kojima T, Okamoto I, Yashiki M, *et al.* 1986. Production of carbon monoxide in cadavers. *Forensic Sci Int* **32**:67–77.

Korb A, David K. 1962. Fluorescenzmikroskopische und elektronmikroskopische Untersuchungen am

Herzmuskel der Ratte nach Leuchtgasvergiftungen. *Deutsch Z Gesamt Gericht Med* **52**:549–55.

Kunsman GW, Presses CL, Rodriguez P. 2000. Carbon monoxide stability in stored postmortem blood samples. *J Anal Toxicol* **24**:572–8.

Lee CW, Yim LK, Chan DT, *et al.* 2002. Sample pre-treatment for co-oximetric determination of carboxyhaemoglobin in putrefied blood and cavity fluid. *Forensic Sci Int* **126**:162–6.

Levine B, Moore KA, Fowler D. 2001. Interaction between carbon monoxide and ethanol in fire fatalities. *Forensic Sci Int* **124**:115–16.

Lo Menzo G. 1966. Il comportomento dell'attivita citrocromossidasica a succinodeidrogenase di taluni organi nell'avvelenamento acute da co. *Folia Med* **8**:607–12.

Mant AK. 1960. Accidental carbon monoxide poisoning: A review of 100 consecutive cases. *Med Leg J* **28**:30–6.

Miro O, Casademont J, Barrientos A, *et al.* 1998. Mitochondrial cytochrome *c* oxidase inhibition during acute carbon monoxide poisoning. *Pharmacol Toxicol* **82**:199–202.

O'Donnell P, Buxton PJ, Pitkin A, *et al.* 2000. The magnetic resonance imaging appearances of the brain in acute carbon monoxide poisoning. *Clin Radiol* **55**:273–80.

Pearce J. 1968. Coal gas and the brain [leading article]. *Br Med J* **1**:767.

Petelenz T. 1972. Badania doswiadczaine dzilania. *Arch Med Sadowej Kryminol* **12**:219–25.

Seto Y, Kataoka M, Tsuge K. 2001. Stability of blood carbon monoxide and hemoglobins during heating. *Forensic Sci Int* **121**:144–50.

Simpson K. 1955. Carbon monoxide poisoning. *J Forensic Med* **2**:5–13.

Somogyi E, Balogh I, Rubanyi G, *et al.* 1981. New findings concerning the pathogenesis of acute carbon monoxide (CO) poisoning. *Am J Forensic Med Pathol* **2**:31–9.

Thom SR. 1993. Leukocytes in carbon monoxide-mediated brain oxidative injury. *Toxicol Appl Pharmacol* **123**:234–47.

Thomsen JL, Kardel T. 1988. Intoxication at home due to carbon monoxide production from gas water heaters. *Forensic Sci Int* **36**:69–72.

Uemura K, Harada K, Sadamitsu D, *et al.* 2001. Apoptotic and necrotic brain lesions in a fatal case of carbon monoxide poisoning. *Forensic Sci Int* **116**:213–19.

Walker E, Hay A. 1999. Carbon monoxide poisoning. *Br Med J* **319**:1082–3.

CHAPTER 30

Agrochemical poisoning

- Paraquat poisoning 566
- Organophosphorus pesticides 567
- References and further reading 568

In the last half century there has been a technological revolution in farming methods, which has spread to almost all parts of the world. The developing nations (who in terms of area of land usage and proportion of the population who work on that land, are numerically greatest at risk) suffer most and this is sometimes exacerbated by the less stringent controls and less safe working methods that exist in those countries.

The potent chemicals used in agriculture may harm persons by accidental exposure, either during their application to crops, or due to incorrect or careless storage. Another major source of human poisoning is through self-administration, when the easily available substances are used for suicide. For example, in Sri Lanka many thousands of hospital admissions each year are for agrochemical poisoning (16 649 in 1983) with over a thousand deaths annually (1521 in 1983). Of these, about three-quarters were self-administered, the remainder being accidental and occupational.

The main dangers from agricultural chemicals lie in the pesticides, especially organophosphorus compounds, such as parathion and herbicides, such as paraquat.

PARAQUAT POISONING

Paraquat is a herbicide that is sprayed on unwanted weeds and other vegetation before planting crops. It is absorbed by the foliage and rapidly kills the plant, but is inactivated when in contact with the soil, so cannot harm the seeds or young plants that are placed in the same ground a short time later. Paraquat (and the less popular diquat) are dipyridyl compounds, paraquat chemically being 1,1′-dimethyl-4,4′-bipyridyldiylium. It is produced commercially as a brownish concentrated liquid of the dichloride salt at 10–30 per cent strength, under the trade name Gramoxone and, for horticultural use, as brown granules called Weedol at about 5 per cent concentration.

Toxicity occurs almost exclusively through ingestion, though some cases are reported where inhalation through spraying has led to a fatal outcome. A suicide from intravenous injection of paraquat has been reported by Fernandez *et al.* (1991).

Only about 5 per cent of the substance is absorbed orally. Poisoning usually occurs either by deliberate self-ingestion of the liquid concentrate, or by accidental drinking from unmarked or incorrectly marked bottles. It is said that one swallowed mouthful of Gramoxone will almost always be fatal and certainly 5 ml has caused death. The decanting of the concentrate from the original manufacturer's containers leads to many accidental deaths. Because of the relatively high cost, paraquat is often taken from the large containers and kept in lemonade or other soft drink bottles. Such decanting is illegal in some countries such as the Republic of Ireland, because of the dangers of unlabelled bottles. Unsuspecting people, especially children, then take a drink from such bottles and immediately suffer the effects of the potent toxin.

Paraquat in concentrated form, is irritant to all epithelial tissues. The lips, mouth, pharynx and oesophagus are superficially eroded, though there is nothing like the dangerous structural damage of strong acids or alkalis. The major danger of paraquat is to the lungs and liver. The lungs are affected mainly by direct aspiration, either as the irritative substance is swallowed or by regurgitation from the stomach during vomiting.

Of that absorbed through the gastrointestinal tract, the major danger is to the liver, where paraquat causes a centrilobular necrosis, with giant mitochondria and crystalline inclusion bodies seen on electron microscopy. In the kidney, renal failure may develop within 2 or 3 days from diffuse tubular damage.

The striking lesion, almost characteristic of paraquat, is in the proliferative damage to the lungs. If rapid death from acute hepatorenal failure does not occur, either because of low dosage or energetic clearance of the residual poison, then progressive lung damage may still lead to death within the next 2 weeks. When paraquat reaches the distal air spaces, diffuse pulmonary oedema and haemorrhages occur, followed by stimulation of the alveolar lining cells. Prior to this, in the first day or two, there is damage to the pneumocytes with vacuolation, desquamation and necrosis. A hyaline membrane is often visible. The mechanism appears to be that paraquat reacts with tissue elements to produce peroxides, including hydrogen peroxide, which is responsible for the damage, which can be worsened by oxygen therapy.

Within a few days repair begins, the mesenchymal interstitial cells and the alveolar lining cells dividing rapidly and filling the alveoli. Both granular and membranous pneumocytes (types I and II) are involved. Within the first week, gas exchange begins to suffer as the air spaces become occluded by mononuclear cells forming rounded-up 'fibroblasts'. If survival continues, the alveoli begin to fibrose, with reticulin and collagen being laid down to form a rigid, stiff lung.

The autopsy in paraquat poisoning

There may be ulceration around the lips and mouth from escape of paraquat concentrate. The mucosa of the mouth may be reddened or desquamated, and the oesophagus may show worse changes, including casts of shed epithelium. None of these changes is by any means inevitable, however, and the upper gastrointestinal tract may be normal.

Similarly, the stomach may show erosion and patchy haemorrhages, or may be unremarkable. The liver may show pallor or mottled fatty change to the naked eye. It is unusual for any gross charges to be visible. Other organs show no specific changes, apart from the lungs; the kidneys may reveal cortical pallor if there is renal failure.

If the victim has lived a week or more, then the lungs may reveal typical changes in that they are large and stiff, keeping their shape when removed from the chest. There may be a fibrinous pleurisy and sometimes slight bloody pleural effusions. The cut surface reveals oedema and patchy haemorrhage, though this may have subsided in cases that survive for some time. The main appearances are microscopic and, unless the history is known, the lung may be mistaken for a diffuse pneumonia. The author (BK) saw a homicide by paraquat, in which the victim was in hospital for 2 weeks with a presumptive diagnosis of 'virus pneumonia', until a confession revealed the true cause of the lung changes. Samples required at autopsy, apart from full histology, include the usual blood samples, urine, stomach contents, lung and liver.

In most instances, the relative slowness of the death allows the diagnosis to be made on history and clinical grounds, so that ante-mortem toxicology is usually well documented.

Toxicology interpretation

Blood levels of paraquat of 0.2 mg/l are sufficient to cause lung damage. Survival has been recorded, however, with plasma levels of up to 1.6 mg/l. Paraquat is excreted over a long period and can be detected in urine at autopsy many days after ingestion. Concentrations in excess of 0.07 mg/l have been found 26 days later.

The concentrations found on analysis after autopsy naturally depend upon the dose taken and the time that has elapsed since ingestion. On the first day, ranges from 0 to 63 mg/l (average 15) have been found in the blood, with urine levels of 20–1210 mg/l (average 462). Seven days later, the blood level comes down to an average of 0.8 mg/l with 4.5 in the urine. Two to three weeks after ingestion, the blood concentration averages 0.5 and the urine level 0.6 mg/l.

ORGANOPHOSPHORUS PESTICIDES

Used in huge quantities throughout the world, these substances cause thousands of deaths in southern Asia, Africa and elsewhere. The major example is parathion, with malathion and dichlorvos used far less extensively. These chemicals act on insects and other arthropods by inhibiting cholinesterase and their toxic effects on man are caused by the same mechanism.

Parathion (nitrostigmine) is extremely toxic and can be absorbed through the skin, conjunctivae, lungs and gut. Because of the inhibitory effect on plasma and erythrocyte cholinesterases, acetylcholine builds up at neuromuscular junctions and other neurotransmitter sites, resulting in hyperexcitability of both voluntary and involuntary muscle.

Other organophosphorus compounds include malathion, which is much less toxic than parathion and is used more in horticulture: dithion, diazinon, hexaethyltetraphosphate (HETP), tetraethylpyrophosphate (TEPP), octamethylpyrophosphamide (OMPA) and demeton are other pesticides of this group.

Toxic signs and symptoms appear when the cholinesterase level drops to 30 per cent of its normal activity. Fatalities begin to occur after the ingestion of 125–175 mg, though ingestion of much larger amounts can be survived. Death can occur in less than an hour after ingestion, though usually several hours elapse in those who are not going to survive.

Autopsy appearances are more helpful than with many other compounds, in that parathion is dissolved in a kerosene base, which can often be detected by its smell. A greenish colouring agent is often added to the commercial products. The stomach therefore may be seen to contain an oily, greenish scum. The gastric mucosa may be haemorrhagic, though this is too non-specific to be of much use, as is the common finding of haemorrhagic pulmonary oedema.

The author (BK), when practising pathology in Southeast Asia, noted a useful diagnostic sign in some less modern mortuaries that were infested with flies and bluebottles. When these insects alighted on an opened cadaver at autopsy, many fell dead or dying onto the autopsy table when the case in progress was a parathion poisoning.

Toxicology interpretation

Post-mortem toxicology is usually conclusive in acute poisoning. The substance resists post-mortem autolysis well and can be recovered from putrefied bodies. The range of blood parathion concentrations in fatal cases may be from 0.5 to 34 mg/l with an average of 9.0. Urinary excretion ranges from 0.4 to 78 mg/l with an average of 10 mg/l. The liver may contain from 0.1 to 120 mg/kg, averaging 11.

Malathion is much less toxic but deaths certainly occur given a greater dose. Blood levels in fatalities ingesting from 25 to 70 g malathion ranged from 100 to 1880 mg/l with a mean of 815. The liver contained from 200 to 1700 mg/kg, with an average of 1300.

Other pesticides and insecticides include chlorinated compounds such as aldrin, DDI (dicophane), lindane (Gammaxane) and dieldrin. Other types include the carbamates (opxymyl, landrin and aldicarb), dinitrophenols, pyrethrum and derris. The phenolic pesticides include DNOC (dinitro-orthocresylphosphate) and dinitrobutylphenol. None of these has any specific autopsy features and the diagnosis rests upon the history, circumstances, and post-mortem analysis of blood, urine and liver.

REFERENCES AND FURTHER READING

Baselt RC. 2002. *Disposition of toxic drugs and chemicals in man*, 6th edn. Biomedical Publications, Foster City, CA.

Beebeejaun AR, Beevers G, Rogers WN. 1971. Paraquat poisoning-prolonged excretion. *Clin Toxicol* **4**:397–407.

Carson DJ, Carson ED. 1976. The increasing use of paraquat as a suicidal agent. *Forensic Sci* **7**:151–60.

Copeland AR. 1988. Organophosphate related fatalities – a violitional biohazard? *Forensic Sci Int* **39**:155–62.

Cravey RH. 1979. Poisoning by paraquat. *Clin Toxicol* **14**:195–8.

Crowley WJ, Jr, Johns TR. 1966. Accidental malathion poisoning. *Arch Neurol* **14**:611–16.

Davies DS. 1987. Paraquat poisoning: The rationale for current treatment regimes. *Hum Toxicol* **6**:37–40.

Davies DS, Hawksworth GM, Bennett PN. 1977. Paraquat poisoning. *Proc Eur Soc Tox* **18**:21–6.

De Alwis LB, Salgado MS. 1988. Agrochemical poisoning in Sri Lanka. *Forensic Sci Int* **36**:81–9.

Dearden LC, Fairshter RD, McRae DM, *et al.* 1978. Pulmonary ultrastructure of the late aspects of human paraquat poisoning. *Am J Pathol* **93**:667–80.

Fernandez P, Bermejo AM, Lopez Rivadulla M, *et al.* 1991. A fatal case of parenteral paraquat poisoning. *Forensic Sci Int* **49**:215–24.

Fernando R. 1989. *Pesticides in Sri Lanka.* Friedrich-Ebert Stifting, Colombo.

Gage JC. 1960. The detection of organic phosphorus compounds. *Med Sci Law* **1**:137–44.

Grant H, Lantos PL, Parkinson C. 1980. Cerebral damage in paraquat poisoning. *Histopathology* **4**:185–95.

Harsanyi L, Nemeth A, Lang A. 1987. Paraquat (gramoxone) poisoning in south-west Hungary, 1977–1984. Toxicological and histopathological aspects of group intoxication cases. *Am J Forensic Med Pathol* **8**:131–4.

Karalliedde L, Senanayake N. 1988. Acute organophosphorus insecticide poisoning in Sri Lanka. *Forensic Sci Int* **36**:97–100.

Klein-Schwartz W, Smith GS. 1997. Agricultural and horticultural chemical poisonings: mortality and morbidity in the United States. *Ann Emerg Med* **29**:232–8.

Kuo TL, Kuo CY. 1988. Determination of paraquat from formalin-fixed tissue. *Forensic Sci Int* **38**:243–9.

Neoral L, Dusek J, Smysl B. 1977. [A contribution to the pathogenesis of lethal paraquat poisoning (author's transl)]. *Z Rechtsmed* **80**:1–7.

Parkinson C. 1980. The changing pattern of paraquat poisoning in man. *Histopathology* **4**:171–83.

Peiris JB, Fernando R, De Abrew K. 1988. Respiratory failure from severe organophosphate toxicity due to absorption through the skin. *Forensic Sci Int* **36**:251–3.

Petty CS. 1958. Organic phosphate insecticide poisoning. *Am J Med* **23**:467–70.

Przybylska A. 1999. [Intoxications caused by plant protection chemicals in 1997.] *Przegl Epidemiol* **53**:121–8.

Rebello G, Mason JK. 1978. Pulmonary histological appearances in fatal paraquat poisoning. *Histopathology* **2**:53–66.

Reif RM, Lewinsohn G. 1983. Paraquat myocarditis and adrenal cortical necrosis. *J Forensic Sci* **28**:505–9.

Russell LA, Stone BE, Rooney PA. 1981. Paraquat poisoning: toxicologic and pathologic findings in three fatal cases. *Clin Toxicol* **18**:915–28.

Stewart MJ, Moar JJ, Mwesigwa J, *et al.* 2000. Forensic toxicology in urban South Africa. *J Toxicol Clin Toxicol* **38**:415–19.

Teare RD. 1976. Poisoning by paraquat. *Med Sci Law* **16**:9–12.

Tompsett SL. 1970. Paraquat poisoning. *Acta Pharmacol Toxicol (Copenh)* **28**:346–58.

Vercruysse A. 1964. Acute parathion poisoning; forensic problems. *J Forensic Med* **11**:107–19.

Wesseling C, van Wendel de Joode B, Monge P. 2001. Pesticide-related illness and injuries among banana workers in Costa Rica: a comparison between 1993 and 1996. *Int J Occup Environ Health* **7**:90–7.

Zivot U, Castorena JL, Garriott JC. 1993. A case of fatal ingestion of malathion. *Am J Forensic Med Pathol* **14**:51–3.

CHAPTER 31

Poisoning by medicines

- General considerations 570
- Autopsy appearances 570
- Results of laboratory tests 571
- Analgesics 571
- Paracetamol 572
- Antidepressant drugs 573
- The benzodiazepines 573
- The phenothiazines 573
- The barbiturates 573
- Insulin poisoning 574
- References and further reading 575

GENERAL CONSIDERATIONS

In most countries, especially those with advanced economies and relatively sophisticated medical services, poisoning with medicinal compounds is common. In many such countries, poisoning with therapeutic substances exceeds deaths from other types of toxic agents, especially in suicidal and accidental poisoning.

This is explained by the ease of access of such substances, whether they are obtainable from a doctor on prescription or on demand across the counter of a pharmacy. Where state-sponsored health services exist, the cost to the recipient may be minimal or absent and this ease of access contributes to opportunities for self-poisoning, whether it be deliberate self-destruction, suicidal gestures or accidental ingestion – the latter especially in children. Unfortunately, overprescribing or the supply of too great a quantity of drugs at one time allows excessive stocks of drugs to be easily available to the public.

Though only a minority of victims of medicinal poisoning fail to recover, there are still an appreciable number of deaths. These come to the attention of the investigative authorities and hence to pathologists. The autopsy investigation of a fatality from a therapeutic substance can be difficult, for a number of reasons:

- The nature of the substance may be uncertain or unknown.
- There may be more than one such substance involved.
- There may be a delay between ingestion and death sufficient to allow blood, urine and tissue concentrations to decline below fatal, toxic or even therapeutic levels.
- Analysis may be difficult to arrange because of lack of facilities.
- Information about fatal levels may be unobtainable.
- Most medicinal poisons leave virtually no characteristic features at autopsy, so diagnosis depends upon laboratory findings.
- Post-mortem changes may make analysis difficult, inaccurate or impossible.
- Where death is delayed after taking the substance, none may be recoverable from the stomach (which has emptied) or even from the intestine.
- The original substance may be rapidly metabolized into one or more breakdown products, adding to difficulties in identification and interpretation.

AUTOPSY APPEARANCES

The lack of characteristic autopsy appearances is often very frustrating for the pathologist. Unless there is an indicative or suggestive history as to which drug was taken – a matter for the investigators in respect of circumstances and recovery of containers – then an autopsy may have to be performed ‘blind’. Where no significant morphological lesions can be discovered, then a full toxicology screen must be considered, which in some jurisdictions may be difficult or impossible to obtain, or be extremely expensive.

The majority of modern medicinal substances are, by design, bland and non-irritant to the tissues and gastrointestinal tract. Most of those met with in forensic practice are taken orally and, though the active constituents may be potent in their pharmacological effect on target organs and tissues, the medicine will cause no erosion or damage to the alimentary tract. Thus little or no physical evidence can be obtained from a gross or even microscopic examination of the gastrointestinal tract or other organs. Much of the physical bulk of modern tablets or capsules is merely the vehicle for introducing the active component into the body and is thus unlikely to have any adverse effect.

When a medicinal compound causes death, the mode of death is most often some form of cardiorespiratory failure, often secondary to depressive effects on the central nervous system. This mode of death causes only non-specific changes discernible at autopsy, which are usually of no use in indicating the basic reason for the death. Acute congestive cardiac failure, pulmonary oedema, sometimes cerebral oedema, generalized organ congestion, scattered petechiae on serous membranes – none of these is of any real use to the pathologist, who has to rely on the results of toxicological analysis for a definitive answer.

There are some therapeutic substances, which, though not the cause of specific lesions, may suggest themselves from their autopsy appearances. An example is the widespread membrane ecchymoses sometimes seen in aspirin poisoning. This could not in any way be sufficient to provide a legally acceptable cause of death, however, unless absolutely reliable circumstantial evidence existed, together with the finding of a large bolus of undissolved tablet remnants in the stomach. Even then it might be contested that the substance was not aspirin – or not aspirin alone – unless analytical confirmation was obtained.

RESULTS OF LABORATORY TESTS

As discussed in Chapter 27, the investigation of fatal poisoning is a collaborative investigation between pathologist and toxicologist. The autopsy excludes, confirms or evaluates any trauma or natural disease, and provides suitable material for analysis. The toxicology laboratory conducts the technical assays, and produces qualitative and quantitative results. The toxicologist/analyst interprets those results to the pathologist, by providing an indication of the therapeutic, toxic and fatal ranges of concentrations in various body fluids and tissues, and by pointing out problems such as decline from post-ingestion survival, conversion to metabolites and many others. The pathologist then collates this information with his own knowledge of the history and autopsy findings to offer the best interpretation of the investigation for judicial authorities. Most problems arise either because the information about the medicine (especially if it is newly developed or where its toxicity is low) is incomplete in terms of toxic blood and tissue levels – because post-ingestion survival has allowed the originally lethal levels to have subsided to therapeutic or even lower limits. What is offered in the remainder of this chapter is a digest of information about such potentially lethal levels, culled from a variety of sources. The ranges are often wide as most of the data are of necessity derived anecdotally, and the problems of uncertainty of dosage, variation in post-ingestion survivals and wide individual biological variation make it impossible to lay down strict thresholds between therapeutic, toxic and fatal concentrations.

Wherever possible, the advice of the analytical toxicologist should be taken about each case – but where this is impracticable, then the following data and similar material, which is constantly being updated in forensic and toxicological publications, may be of assistance. The choice of substances is arbitrary, but represents the most common medicines seen in suicidal and accidental poisoning.

ANALGESICS

Aspirin (acetylsalicylic acid) and salicylates

Aspirin is the most widely used therapeutic drug, being analgesic, antipyretic and anti-inflammatory. It was formerly very common as an agent of self-poisoning, both accidental in children and suicidal in adults. In Britain in the last two decades, its use as a self-poisoning agent has declined remarkably, so that fatalities are now rarely seen.

The therapeutic dose is usually 325–975 mg, that is, 1–3 tablets. Rarely, persons with an aspirin hypersensitivity may become ill or even die after therapeutic doses, suffering urticaria, angioneurotic oedema, hypotension, vasomotor disturbances and laryngeal and glottal oedema.

Patients on long-term salicylate therapy for arthritic or rheumatic diseases may take 3–5 g/day and slowly reach blood concentrations which would be in the lethal range if caused by acute overdoses. Those on 3 g/day have blood levels varying between 44 and 330 mg/l.

Apart from deaths caused by hypersensitivity, death in an adult is unlikely with the ingestion of fewer than about 50 tablets, that is, about 16 g. The blood concentration (measured as total salicylate), from a medicinal dose of 975 mg, ranges from about 30 to 100 mg/l (with a mean of 77) 2 hours after ingestion. There is a rapid fall to around 25 mg/l some 8 hours later.

At autopsy, aspirin is one of the few medicines that may cause some gross abnormalities, though they are not particularly specific. Externally there is nothing to see, unless vomiting has taken place, when dark or even red, bloody gastric contents may be expelled. Rarely, there may be some haemorrhagic manifestations in the form of skin petechiae.

Internally, the stomach may still contain a mass of fused, unabsorbed tablets. These tend to start dissolving and then aggregate into a grey or dirty-white mass if a large number (several hundred) have been swallowed. The gastric mucosa may be eroded by the irritative, acidic substance. This may be localized in the stomach or spread widely across the fundus and cardia. The lining may be dotted with acute erosions, sometimes causing bleeding that may amount to a frank haematemesis. Black altered blood may lie in the stomach and pass into the intestine to form a melaena if survival is long enough. Mucosal petechiae and ecchymoses in the stomach, without actual erosive destruction, may be seen as part of a haemorrhagic result of the anticoagulant action of aspirin. Similar petechiae may be spread through other organs and especially serous membranes, particularly on the parietal pleura and epicardium. Even single tablets may cause a small ulcer if they stick to the stomach lining – this is sometimes seen incidentally at autopsy in non-poisoning cases, where a tablet has been swallowed shortly before death.

Post-mortem toxicology requires the usual samples of blood, urine, stomach contents and liver. The mass of aspirin in the stomach may remain for several days in life, forming a partly insoluble concretion that may retard the absorption of the drug. This is why it is always worth washing out the stomach of a live victim, as a large proportion of the aspirin may be removed before it can cause systemic effects. With the advent of soluble aspirin or effervescent preparations, this aspect is lost as no such insoluble bolus forms. At autopsy, part of such a mass can be sent for analysis, whilst quick ‘spot’ tests can be carried out on another part. Such quick chemical confirmation may be performed in the autopsy room itself, by using a 10 per cent solution of ferric chloride. If a small quantity is added to a urine sample or to the surface of the tablet mass, an immediate purple–blue colour suggests aspirin. This is by no means specific, but is merely suggestive. If negative, however, then aspirin can be virtually discounted. These are only rapid screening methods and by no means replace proper laboratory analysis.

Toxic blood levels (measured as total salicylate) begin at about 300–500 mg/l, though both death and survival are consistent with far higher or lower levels. Blood concentrations in fatal cases may range from about 60 to 7300 mg/l, some authorities suggesting that 500 mg/l is an average minimum level. The liver concentration in fatalities varies from 2.5 to 1000 mg/kg and urine salicylate from 20 to 1350 mg/l, emphasizing the wide levels that are compatible with life. Salicylate has a rather slow clearance rate from the blood, the half-life being up to a day in some massive overdoses.

Aspirin poisoning is dangerous in that sudden cardiac arrest can occur in the absence of any toxic symptoms. This accounts for the deaths that take place after patients have been discharged fit from the emergency departments of hospitals. They may have seemed quite well and symptom free, but suffer a fatal collapse up to a day or so later. Fatal cardiac arrhythmias can supervene without warning and make it advisable, where possible, to admit patients with aspirin overdoses for observation for a day or so.

PARACETAMOL

Paracetamol is also known as acetominophen, *N*-acetyl-*p*-aminophenol or 4′-hydroxyacetanilide. It is an analgesic and antipyretic, without the anti-inflammatory properties of aspirin, for which it is often used as an alternative because of the lack of gastric irritation.

In wide use, especially in combination with other drugs such as codeine and dextropropoxyphene, paracetamol is one of the most common agents in self-induced poisoning by medicinal products. It is used alone in therapeutic doses of up to 500 mg. Overdoses of 20 g or more are potentially lethal, but much less is needed in combination with other drugs, such as propoxyphene. Paracetamol is a potent liver poison, as a small proportion is converted by the liver enzyme ‘P450’ (microsomal mixed function oxidase) into a toxic compound, probably *N*-acetyl-*p*-benzoquinone. Normally, glutathione and other sulphydryl compounds detoxify this substance, but in overdose, these are exhausted and the toxic agent causes a profound centrilobular hepatic necrosis. The concurrent administration of other drugs, such as phenobarbitone or phenytoin in epileptics or chronic alcoholism, activate the P450 enzyme and worsen the toxicity through this mechanism.

At autopsy there is nothing specific to observe in the gastrointestinal tract. In massive overdosage, there can rarely be rapid death from a direct depressive action on the central nervous system, but most deaths are delayed 2–4 days whilst liver failure develops. At autopsy, the liver may be enlarged, but is often under the normal weight of 1500 g. It may be pale yellow or tan, or the damage may be only visible histologically, when a centrilobular necrosis is seen. Renal changes in the form of tubular necrosis may also be present and occasionally myocardial fibre damage may be visible histologically.

Analytically, the therapeutic range of plasma concentrations 6 hours after a 324 mg dose is 2–6 mg/l, though some

TABLE 31.1 *Fatal concentrations of some antidepressants (mg/l or mg/kg)*

	Blood (average)	Urine (average)	Liver (average)
Amitriptyline	2.7–4.7 (3.7)	0.4–7.9 (3.4)	13–317 (130)
Dothiepin	0.3–2.5 (1.5)	0.4–5.1 (3.2)	2.0–14 (8)
Imipramine	6–8.5 (7.3)	0.6–54 (20)	33–381 (166)
Tranylcypromine	3.7	25.0	7.3

records claim peak levels of up to 25 mg/l. The plasma half-life is a guide to hepatotoxicity, it being dangerous to have a half-life of more than 2 hours at a level of 300 mg/l at 4 hours after ingestion. Typical blood levels in overdoses when at least 10–15 g have been taken are 100–400 mg/l, with an average around 250. The urine may contain 150–800 mg/l, but all levels depend on dose and survival time. Paracetamol may exhibit post-mortem redistribution.

The inclusion of other drugs, especially dextro-propoxyphene (and, of course, alcohol), may markedly reduce the level needed for a fatal outcome. Paracetamol was the most frequently detected substance in a compilation of post-mortem femoral blood concentrations of drugs (Druid and Holmgren 1997) based on a selection of 15 800 samples sent to the Department of Forensic Chemistry in Linköping, Sweden, during 1992–95. In their series of 139 fatal intoxications with paracetamol in combination with other drugs and/or alcohol, the median concentration of paracetamol was 170 mg/l (range 90–320).

ANTIDEPRESSANT DRUGS

The tricyclic antidepressants are frequently involved in self-poisoning, partly associated with the type of patient for whom they are prescribed.

Amitriptyline, dothiepin, doxepin and trimipramine have additional sedative properties. Those with little or no sedating action include protriptyline, nortriptyline, imipramine, clomipramine, iprindole, lofepramine, desipramine and butriptyline.

Tetracyclic antidepressants include maprotiline and mianserin. Other types include the monoamine oxidase inhibitors, which are well known to have dangers related to the concurrent ingestion of other drugs and foods, especially those with sympathomimetic action and tyramine content, such as rich cheese, yeast extracts, red wine and beans. Dangerous hypertension may ensue with the risk of cerebrovascular haemorrhage. Drugs of this class include phenoxypropazine, tranylcypromine, isocarboxazid and phenelzine.

TABLE 31.2 *Fatal concentrations of three benzodiazepines (mg/l or mg/kg)*

	Blood	Urine	Liver
Chlordiazepoxide	20	8	10
Diazepam	5–19	3	16
Nitrazepam	1.2–9.0	1–10	0.7–4.0

TABLE 31.3 *Fatal concentrations of two phenothiazines (mg/l or mg/kg)*

	Blood (average)	Urine (average)	Liver (average)
Chlormethiazole	10–214 (55)	5–114 (43)	42–190 (94)
Chlorpromazine	6.6	1.2	84

THE BENZODIAZEPINES

These widely used drugs are employed for their sedative and tranquillizing effects. A large number of both 1,4- and 1,5-benzodiazepines are available, divided into short-acting, intermediate-acting and long-acting compounds.

Long-acting benzodiazepines include: flurazepam, nitrazepam, diazepam, ketazalam, chlordiazepoxide, clobazam, chlorazepate, medazepam and alprazolam. Intermediate-acting benzodiazapines include: loprazolam, lormetazepam, temazepam, flunitrazepam, lorazepam, bromazepam and oxazepam. A short-acting benzodiazepine is triazolam.

THE PHENOTHIAZINES

This group of tranquillizer drugs includes: haloperidol (butyrophenone), chlormethiazole, chlorpromazine, fluphenazine, diphenylbutylpiperidine, promazine, trifluoperazine and prochlorperazine.

The autopsy appearances are non-specific and toxicology may resolve any diagnostic problems if the death has occurred fairly soon after ingestion – which may often not be the case, when history and ante-mortem investigations can provide the only answer.

THE BARBITURATES

The massive problem posed by therapeutic administration of barbiturates until about 20 years ago has largely abated in countries with a responsible medical profession, which voluntarily refrained from the prescription of these drugs except where specifically indicated. Their use as sleeping tablets and general soporific sedative agents led to widespread abuse, so that at one time they were easily the most common agent of drug addiction. The development of non-barbiturate hypnotics, such as the benzodiazepines, helped to remove the need for the older and more lethal compounds. Unfortunately, barbiturates are still widely available on the illicit market, either alone or in combination with other substances such as amphetamines.

Barbiturates exist in many forms, the best classification (which relates to their degree of toxicity) being their speed of action:

- Long-acting barbiturates: barbitone, phenobarbitone and phenytoin, which is still prescribed for epilepsy.
- Intermediate-acting barbiturates: amylobarbitone, sodium amytal, pentobarbitone, allobarbitone, butobarbitone and pentobarbitone.
- Short-acting barbiturates: hexobarbitone, cyclobarbitone, secobarbital and thiopentone.

Much lower blood levels will be found in fatal poisonings in the short-acting group as death may occur more quickly from the usual mode of action, a central depression of the respiratory centres. The author (BK) has knowledge of a death within 20 minutes of taking a massive overdose of 'Seconal'.

At autopsy, the signs are of general cardiorespiratory failure, with often a cyanotic, congestive appearance. Though non-specific, probably the congested lungs in acute barbiturate poisoning are more intense than in any other condition. These organs may be almost black and the whole venous system is engorged with dark, deoxygenated blood. There may be 'barbiturate blisters' on dependent parts of the skin surface, especially buttocks, backs of thighs, calves and forearms, though as discussed in the chapter on carbon monoxide poisoning, these blisters are common to all states of deep coma.

Internally there may be local signs of erosion from the drug itself. The gastric mucosa may be badly damaged from the alkaline attack of drugs such as sodium amytal which, being the sodium salt of a weak organic acid, hydrolyses in the stomach. The fundus may be thickened, granular and haemorrhagic. The cardia and lower oesophagus may be eroded from reflux and, if the victim regurgitates, then black, altered blood may appear at the nose and mouth.

The capsules of certain barbiturates also leave characteristic traces in the mouth, oesophagus and stomach. The colour varies with the manufacturer, but the turquoise–blue of sodium amytal capsules may stain the stomach contents and even be visible through the wall of the intestine when the abdomen is opened. Other pigmented gelatine capsules can be red, yellow or blue. As with so many other drugs, combination with alcohol greatly increases the dangers of a fatality.

TABLE 31.4 *Fatal concentrations of barbiturates (mg/l or mg/kg)*

	Blood	Urine	Liver
Phenobarbitone	55–144	–	–
Amylobarbitone	29–68	210	106–580
Secobarbitone (or quinal barbitone)	5–52	–	15–330

INSULIN POISONING

Formerly a rarity, death from parenteral administration of insulin is now not uncommon. The Beverley Allitt case in Britain in recent years showed that multiple deaths can occur, especially where medical or nursing staff are concerned, as well as those in proximity to diabetics, as both groups may have access to insulin.

Another change is the relative ease with which analysis of body fluids and tissue can be carried out now, compared with the great technical difficulties of only a few years ago, so that fewer such deaths may be missed from lack of reliable insulin assays.

Fatal insulin toxicity may be accidental, suicidal or homicidal. The accidental fatalities are usually examples of medical error, mostly from misreading the label on the box or ampoule. A former student of the author (BK), on the fourth day of her first intern post, gave ten times the dose of insulin to a patient during a pituitary function test, by wrongly assuming that the stated number of units written on the box were the total ampoule contents, instead of being the strength per millilitre.

Suicide by insulin is not uncommon; the author (BK) has seen it given into a saline drip by a doctor and also injected into the abdominal wall by a non-diabetic who stole it from her diabetic neighbour's refrigerator.

As stated, homicide and attempted homicide have given rise to some notorious cases, both in UK and the USA. In one case known to the author (PS), a previously healthy 48-year-old man was delivered unconscious to the emergency unit because of a suspicion of decompression sickness. The treatment was aborted as the patient was found to be hypoglycaemic (nadir serum glucose 0.3 mmol/l) and treatment and diagnostics of hypoglycaemia commenced. Serum samples drawn at admittance were stored frozen, whereby it was possible to show retrospectively that, while the concentration of insulin in serum was high (75 mU/l, increasing further to over 240 mU/l in the next few hours), concentration of C-peptide was low (below detection limit of 0.1 nmol/l) at the hypoglycaemic stage, suggesting that the patient had received exogenous insulin somehow, and the police were informed. Due to severe hypoglycaemic brain damage, the patient remained in a vegetative state for 2 months before dying of multiorgan failure. Circumstantial evidence obtained during the ensuing criminal investigation was considered by the court to prove the patient's wife (a nurse) guilty of murder (Koskinen *et al.* 1999).

Insulin is, of course, inactive orally and has to be given by injection to perform its hypoglycaemic effect. At autopsy, where either from the circumstances or the finding of needle marks, insulin is a possibility, peripheral blood samples and skin and underlying tissue from the injection site should be carefully preserved, together with control skin from another site.

The fine needles usually used by diabetics may leave virtually no mark on the skin. The author (BK) has tested some such needles on cadaver skin and found that, often, the mark cannot be seen immediately after withdrawal, unless a small vessel has been damaged.

Although insulin has been recovered many days, even weeks, after death, the sooner the better as far as collecting samples is concerned. Serum should be separated from red cells and the former frozen until sent to the analysts, unless whole blood can be sent straight away. Skin and tissue samples should either be frozen or kept in the refrigerator – not fixed. Porcine or bovine insulin can be detected as such but, if therapeutic insulin is of human origin, then it cannot be distinguished on analysis from the patient's own insulin. As well as immunoassay of the insulin itself, the measurement of C-peptide, produced on a one-to-one basis by the pancreas, assists in distinguishing endogenous from exogenous insulin. All such interpretations are a matter for specialists in this field, upon whose advice the pathologist must rely.

Attempting to prove insulin-induced hypoglycaemia by measuring glucose levels in human post-mortem fluids is impracticable, due to the unreliability of such estimations after death.

Very low vitreous humour glucose levels may strongly suggest hypoglycaemia, but are not absolutely acceptable.

REFERENCES AND FURTHER READING

Baselt RC. 2002. *Disposition of toxic drugs and chemicals in man*, 6th edn. Biomedical Publications, Foster City, CA.

Bauman WA, Yalow RS. 1981. Insulin as a lethal weapon. *J Forensic Sci* **26**:594–8.

Beastall GH, Gibson IH, Martin J. 1995. Successful suicide by insulin injection in a non-diabetic. *Med Sci Law* **35**:79–85.

Brodsgaard I, Hansen AC, Vesterby A. 1995. Two cases of lethal nitrazepam poisoning. *Am J Forensic Med Pathol* **16**:151–3.

Cardauns H, Iffland R. 1973. [Fatal intoxication of a young drug addict with diazepam (author's transl).] *Arch Toxikol* **31**:147–51.

Chaturvedi AK, Hidding JT, Rao NG, *et al.* 1987. Two tricyclic antidepressant poisonings: levels of amitriptyline, nortriptyline and desipramine in post-mortem biological samples. *Forensic Sci Int* **33**:93–101.

Crifasi J, Long C. 1997. The GCMS analysis of tranylcypromine (parnate) in a suspected overdose. *Forensic Sci Int* **86**:103–8.

Druid H, Holmgren P. 1997. A compilation of fatal and control concentrations of drugs in postmortem femoral blood. *J Forensic Sci* **42**:79–87.

Engelmann L, Kohler H. 1971. [Clinical aspects of chlordiazepoxide poisoning.] *Dtsch Gesundheitsw* **26**:435–9.

Fatteh A, Blanke R, Mann GT. 1968. Death from imipramine poisoning. *J Forensic Sci* **13**:124–8.

Fermer R. 1995. *Forensic pharmacology*. Oxford University Press, Oxford.

Finkle BS, McCloskey KL, Goodman LS. 1979. Diazepam and drug-associated deaths. A survey in the United States and Canada. *JAMA* **242**:429–34.

Fletcher SM. 1983. Insulin. A forensic primer. *J Forensic Sci Soc* **23**:5–17.

Forbes G, Pollock Weir W, Smith H, *et al.* 1965. Amitriptyline poisoning. *J Forensic Sci Soc* 5:183–7.

Giusti GV, Chiarotti M. 1979. Lethal nitrazepam intoxications, report of two cases. *Z Rechtsmed* **84**:75–8.

Griffiths GJ. 1973. Overdose of parstelin (tranylcypromine). *Med Sci Law* **13**:93–4.

Haibach H, Dix JD, Shah JH. 1987. Homicide by insulin administration. *J Forensic Sci* **32**:208–16.

Iwase H, Kobayashi M, Nakajima M, *et al.* 2001. The ratio of insulin to C-peptide can be used to make a forensic diagnosis of exogenous insulin overdosage. *Forensic Sci Int* **115**:123–7.

Junge M, Tsokos M, Puschel K. 2000. Suicide by insulin injection in combination with beta-blocker application. *Forensic Sci Int* **113**:457–60.

Kanto J, Sellman R, Haataja M, *et al.* 1978. Plasma and urine concentrations of diazepam and its metabolites in children, adults and in diazepam-intoxicated patients. *Int J Clin Pharmacol Biopharm* **16**:258–64.

Kernbach-Wighton G, Puschel K. 1998. On the phenomenology of lethal applications of insulin. *Forensic Sci Int* **93**:61–73.

Koskinen PJ, Nuutinen HM, Laaksonen H, *et al.* 1999. Importance of storing emergency serum samples for uncovering murder with insulin. *Forensic Sci Int* **105**:61–6.

Langford AM, Taylor KK, Pounder DJ. 1998. Drug concentration in selected skeletal muscles. *J Forensic Sci* **43**:22–7.

Ledda F. 1968. [Acute chlordiazepoxide poisoning in a drug addict, followed by withdrawal syndrome.] *Clin Ter* **44**:167–71.

Levy WJ, Gardner D, Moseley J, *et al.* 1985. Unusual problems for the physician in managing a hospital patient who received a malicious insulin overdose. *Neurosurgery* **17**:992–6.

Lutz R, Pedal I, Wetzel C, *et al.* 1997. Insulin injection sites: morphology and immunohistochemistry. *Forensic Sci Int* **90**:93–101.

Mackell MA, Case ME, Poklis A. 1979. Fatal intoxication due to tranylcypromine. *Med Sci Law* **19**:66–8.

Marks V. 1995. Hypoglycaemia – real and unreal, lawful and unlawful: the 1994 Banting lecture. *Diabet Med* **12**:850–64.

Marks V, Teale JD. 1999. Hypoglycemia: factitious and felonious. *Endocrinol Metab Clin North Am* **28**:579–601.

Mirchandani H, Reich LE. 1985. Fatal malignant hyperthermia as a result of ingestion of tranylcypromine (parnate) combined with white wine and cheese. *J Forensic Sci* **30**:217–20.

Noirfalise A, Dodinval P, Quiriny J, *et al.* 1987. Death through injection of barbiturates. *Forensic Sci Int* **35**:141–4.

Patel F. 1992. Fatal self-induced hyperinsulinaemia: a delayed post-mortem analytical detection. *Med Sci Law* **32**:151–9.

Patel F. 1995. Successful suicide by insulin injection in a non-diabetic. *Med Sci Law* **35**:181–2.

Phillips AP, Webb B, Curry AS. 1972. The detection of insulin in postmortem tissues. *J Forensic Sci* **17**:460–3.

Polson C, Green M, Lee M. 1983. *Clinical toxicology*, 3rd edn. Pitman, London.

Pounder DJ, Owen V, Quigley C. 1994. Postmortem changes in blood amitriptyline concentration. *Am J Forensic Med Pathol* **15**:224–30.

Price LM, Poklis A, Johnson DE. 1991. Fatal acetaminophen poisoning with evidence of subendocardial necrosis of the heart. *J Forensic Sci* **36**:930–5.

Schneider V, Dulce HJ. 1979. [Suicidal poisonings with insulin and their demonstration on the corpse (radioimmunoassay).] *Arch Kriminol* **164**:142–52.

Sticht G, Kaferstein H. 1980. [Results of toxicological investigations on vesparax-poisonings (author's transl).] *Z Rechtsmed* **85**:169–75.

Sturner WQ, Putnam RS. 1972. Suicidal insulin poisoning with nine day survival: recovery in bile at autopsy by radioimmunoassay. *J Forensic Sci* **17**:514–21.

Williams KR, Pounder DJ. 1997. Site-to-site variability of drug concentrations in skeletal muscle. *Am J Forensic Med Pathol* **18**:246–50.

Wilson Z, Hubbard S, Pounder DJ. 1993. Drug analysis in fly larvae. *Am J Forensic Med Pathol* **14**:118–20.

Winston DC. 2000. Suicide via insulin overdose in nondiabetics: the New Mexico experience. *Am J Forensic Med Pathol* **21**:237–40.

Yacoub M, Cau G, Faure J, *et al.* 1968. [Medico-legal diagnosis of fatal imipramine poisoning.] *Med Leg Dommage Corp* **1**:211–13.

Yonemitsu K, Pounder DJ. 1993. Postmortem changes in blood tranylcypromine concentration: Competing redistribution and degradation effects. *Forensic Sci Int* **59**:177–84.

CHAPTER 32

Death from narcotic and hallucinogenic drugs

- Morphine and other opioid drugs 578
- Toxicological results 579
- Methadone 580
- Hallucinogens 580
- Cannabis 581
- The amphetamines 581
- Cocaine 581
- References and further reading 582

These substances are discussed solely from the point of view of the pathologist dealing with fatal cases.

Drugs of dependence may be absorbed orally, by intravenous, subcutaneous or – rarely – intramuscular injection, by smoking, or by nasal sniffing. The routine at autopsy, in respect of obtaining samples for toxicological analysis, is altered according to the route of administration. As mixing of drugs and addition of non-narcotic drugs is common, it is the usual practice to take a wide range of samples even if the primary route is known with some degree of certainty. For example, an addict dying ‘on the needle’ where intravenous injection is obvious, will still have stomach contents taken for investigation. The standard samples should be taken, as described in a previous chapter, comprising several samples of venous blood (one with fluoride), stomach and contents, liver and urine. In some circumstances, additional samples such as bile, cerebrospinal fluid and vitreous humour may be taken, as well as brain or kidney. The great advances in the analytical techniques allow the analysis of drugs also in other biological samples, such as saliva, sweat and hair. Hair analysis can also provide evidence of long-term exposure to drugs (weeks, months or years), because most drugs, if not all, incorporate in hair and are relatively stable. At least 50 mg of hair should be collected, cutting about a pencil thickness of strands of hair as close to the skin as possible from the back of the head, dried and stored in a sealed plastic bag or tube at room temperature.

When the drug has been injected, then an ellipse of skin around the injection mark, extending down through the subcutaneous tissue to the muscle, should be excised, along with a control area of skin from another non-injected site. These should be refrigerated, not fixed in formalin, until delivery to the laboratory can be arranged. Full histology should always be taken, especially if drugs have been injected, as foreign substances may be discovered as embolic particles, especially in the lungs. Pulmonary granulomata are well-known histological features of ‘mainlining’ addicts taking impure drugs intravenously, as the lung capillaries filter out coarse particulate matter used to dilute the active narcotic. Talc is particularly prone to form granulomata, sometimes with foreign body giant cells. Under polarized light, doubly refractile particles may be seen in the centre of the reactive nodules. Sometimes, strands of cotton may form foreign bodies, derived from the cloth strainer used to filter particles crudely from the drug solution before injection.

Siderophages were also claimed to be increased in these lungs, compared with healthy young adult controls. However, Lockemann and Püschel (1993), studying lungs stained for iron with Perl’s reaction, found conflicting results in two large series and conclude that the pathognomonic value of these cells in drug takers is uncertain.

If drugs may have been taken by the nasal route, such as cocaine and heroin, then dry swabs from each nostril should be taken.

MORPHINE AND OTHER OPIOID DRUGS

Morphine is the major representative of the general group of opioids, which comprise natural opium and a whole series of chemically related derivatives. They may be taken orally or injected and several, such as crude opium and heroin – may be absorbed by inhaling smoke. Morphine itself is poorly absorbed from the gastrointestinal tract; heroin can be taken via the nasal mucosa.

The group consists of opium, morphine, heroin (diacetyl morphine), codeine (dimethyl morphine), dihydrocodeine (DF 118), etorphine (Immobilon), methadone, papaverine, pethidine, dipipanone, dextromoramide, dextropropoxyphene, pentazocine, cyclazocine, diphenoxylate, buprenorphine, tramadol, fentanyl and many more.

Autopsy appearances

The autopsy findings in deaths from all these drugs are relatively non-specific. Toxicological analysis and expert interpretation of the results are necessary for the proper elucidation of the deaths, but certain features can be useful pointers. The first is the presence of injection marks. When fresh, they look just like any other needle mark commonly seen from therapeutic or diagnostic procedures. They are commonly on the arms, either in the classical position in the antecubital fossa on the front of the elbow, or into one of the prominent veins of the forearms or dorsum of the hand. The left side is favourite as most people are right-handed, but in habitual users, sclerosis of the veins may lead to the arms being used randomly. The veins of the dorsum of the foot may be used when the hands and arms have become unusable because of thrombosis and scarring. Less common sites are in the thighs but here, as with the abdominal wall, the injections may be subcutaneous, rather than intravenous. This mode of injection is known as 'skin-popping' and can lead to areas of subcutaneous sclerosis, fat necrosis, abscesses and, if the injections are deeper into the muscle, to chronic myositis.

Other external signs may be tattoos, often bizarre and connected with the drug subculture. One specific type is tattooing, often of numerals, such as '13', on the buccal (inner) surface of the lower lip. Where chronic addiction has taken its toll, the body may be emaciated, dirty and show signs of infection, especially in the form of skin ulceration. Rarely, there may be necrosis or even loss of phalanges from thrombotic or septic emboli. Old injection marks, sometimes with associated bruising, may be found, the bruising undergoing the usual spectrum of colour changes if not recent. The veins may show overlying fibrosis where phlebitis has occurred, or old venous thrombosis with firm cord-like vessels under the skin.



FIGURE 32.1 *Fresh injections marks on the arm of a drug addict.*



FIGURE 32.2 *Tattoo inside the lower lip of a narcotic drug dealer.*

Where sudden death has occurred in habituated addicts, there may be gross pulmonary oedema, with a plume of froth exuding from the mouth or nostrils, suggestive of drowning. As Polson *et al.* (1983) point out, this may cause some confusion when the victim is found dead in a bathroom, a common venue (along with toilets) for drug administration. This pulmonary oedema is sometimes a striking feature of rapid death in those who are habituated to opioid drugs, especially heroin. It does not seem to occur in novices to the habit, who tend to die in a different way, from a sudden primary cardiac arrest. The oedema may be blood-tinged, again causing confusion with drowning. The cause is not known, but is often attributed to some 'allergic' phenomenon, a rather unsatisfactory explanation. It has been claimed that it sometimes may be caused by adulterants in the drugs, such as quinine, but this is doubtful.

The death may be so rapid that the needle may still be found in the vein when the body is discovered, often in a public lavatory or sometimes in the presence of other addicts, who may then be charged with criminal offences in relation to the death as well as with possessing and using illicit drugs.

There are no other more specific autopsy appearances. Though clinically, a constricted pupil is a prominent sign of morphine administration, after death, any kind of pupil alteration may occur. They may remain small, dilate, or become quite unequal – this applies to any form of death, so no specificity exists for opioid poisoning.

Among new recruits to drug dependence, some die at the first injection of a parenteral dose of heroin or morphine. The mode of death appears to be a cardiac arrest following an arrhythmia and ventricular fibrillation, but no morphological signs can be found. It may be related to sensitization of the myocardium to catecholamines by the drug, the excitement and apprehension being similar to the triggers that seem to cause sudden death from falling into cold water or having a criminal abortion.

The other aspect of autopsies on drug-dependent victims is the risk of infection to pathologist and mortuary staff. Addicts form a high-risk group for both hepatitis B and C, HIV and AIDS. The way in which such autopsies are dealt with in different jurisdictions must vary widely, but it is common practice for HIV and hepatitis testing to be carried out prior to autopsy, unless the policy of the particular autopsy service is to accept all cases with appropriate safety techniques. The analytical laboratory must be informed of any high-risk samples being sent to them, and some will be reluctant to handle blood or tissue samples with positive serology. The pathologist may well refuse to carry out an autopsy on a suspect body until a negative result has been returned on a sample of blood taken (with adequate precautions) from the femoral vein. If positive for hepatitis B or C virus, and especially if the victim shows any signs of hepatic involvement such as jaundice, then many pathologists would decline to carry out a full autopsy unless there are pressing reasons. In that case, scrupulous safety precautions must be taken (see Chapter 1).

In relation to AIDS and HIV positivity, opinions and practices vary widely in the present state of knowledge. It seems obvious that the HIV virus is not in the same category of infectivity as hepatitis. Though autopsies on patients dying of clinical AIDS are routinely performed, there is a difference in the potential risk of a literally 'cold' autopsy being performed on a hospital death after a day or two in the mortuary refrigerator, compared with the urgent activities of a forensic pathologist who may be called upon to conduct an autopsy on a still-warm corpse within a few hours of a suspicious death. However, as mentioned in Chapter 1, HIV may remain viable for many days after death.

TOXICOLOGICAL RESULTS

As with all deaths from toxic substances, the interpretation of laboratory analytical results may present considerable difficulties. There may be a long delay between the administration of the drug and death, during which time the blood, urine and even tissue levels may decline, or even disappear. Many drugs break down rapidly in the body and their metabolites may be the only recognizable products of their administration. In some cases, data on lethal blood levels may be imperfectly known and great variations in personal susceptibility may make the range of concentrations found in a series of deaths so wide as to be rather unhelpful.

As mentioned above, some persons die rapidly after the first episode of taking a 'normal' dose of a drug because of some ill-understood personal idiosyncrasy and here quantitative analysis may not assist.

Where habituation and tolerance has developed, drug users may have concentrations in their body fluids and tissues far higher than lethal levels published for non-habitués. In general, the great usefulness of toxicological analysis is both qualitative and quantitative. The former will show what drugs have been taken in the recent past; the length of time that drugs or their metabolites – persist in different fluids and tissues varies widely.

The quantitative analysis can be useful, especially when the results reveal high levels – into the toxic or lethal ranges. These ranges are usually obtained anecdotally from surveys of large numbers of deaths but, as stated, can differ in terms of minimum and maximum values from different laboratories. The problems of idiosyncratic sensitivity and tolerance cause such published ranges to act only as a general yardstick and deaths that occur outside the ranges (usually off the lower end) cannot be excluded from having been caused by the drug in question if other factors may have been involved. Such factors include the presence of other drugs or alcohol, or both, delayed death and abnormal sensitivity.

Thus the analysis is not the final arbiter of the cause of death, although it is a highly important component of the whole range of investigation. The pathologist has the duty to correlate and interpret all known facts. He must fit the circumstances, the presence of natural disease, trauma and other toxic substances with the laboratory findings, to arrive at the most reasonable cause of death.

The advice of the toxicology laboratory is vital in this process, especially in relation to known lethal ranges and the significance of metabolites, but the analysts should not become the sole arbiter of the cause of death.

METHADONE

Methadone has come to be used primarily as a treatment for established heroin dependency, but unfortunately appears to substitute one form of addiction for another, albeit somewhat less lethal, though recent experience in Scotland (1995) has shown that deaths from methadone may exceed those from heroin, whose use it was intended to supplant. Its clinical uses are as an analgesic more powerful than morphine, with the advantage that it is almost as potent by oral administration as by injection. It has strong and often undesirable sedative properties, however, and is virtually as addictive as the other opioids.

Many deaths occur from its misuse, when obtained either legitimately for the replacement of heroin dependency or on the large illegal market. Most deaths follow oral administration and appear to be due to lack of tolerance, in the absence of which even 50 mg may be lethal, though some recipients appear to die at the outset of the replacement treatment (Drummer *et al.* 1992).

In post-mortem samples, the liver has the highest concentration. The fatal levels found on analysis overlap those found in persons on maintenance doses for heroin replacement, making interpretation difficult. The blood levels published by Manning in 10 fatal cases showed: blood – mean 1.0 mg/l (range 0.1–1.8); liver – mean 3.8 mg/l (range 1.8–7.5); bile – mean 7.5 mg/l (range 2.9–18.0); and brain – mean 1.0 mg/l (range 0.5–1.4).

TABLE 32.1 *Blood and tissue concentrations (mg/l or kg) of narcotic drugs from various series of fatalities (Baselt* et al. *1975; Stead and Moffat 1983)*

	Baselt *et al.*		
	Range	**Mean**	**Stead and Moffat**
Heroin			
Blood	0.05–3.0	0.3–0.4	>0.1 (mean 0.43)
Urine	0.7–86	5–18	
Bile	3.2–119	32	
Morphine			
Blood	0.2–2.3	0.7	>0.2 (mean 0.7)
Urine	14–18	3.0	
Liver	0.4–18	52	
Cocaine			
Blood	0.9–21	5.2	3.1 (one case)
Urine	1.4–215	47	
Liver	0.1–20	4.3	
Amphetamine			
Blood	0.5–41	8.6	>0.5
Urine	25–700	237	
Liver	4.3–74	30	
Phencyclidine			
Blood	0.3–25	4.8	>0.3 (mean 2.9)
Urine	0.4–120	35	
Liver	0.9–170	23	
Pethidine (meperidine), orally			
Blood	8–20	12	>2 (mean 14)
Urine	150	150	
Liver	5–10	7	

HALLUCINOGENS

Few of the hallucinogenic drugs are primary causes of death, but some may lead to traumatic deaths because of the abnormal behaviour of the person who is under their influence. For example, the victim of a lysergic acid diethylamide (LSD) 'trip' may be under the impression that he can fly and thus project himself from a high window. Some drugs, however, may have direct toxic effects, though, as with so many drugs of dependence, the autopsy findings are negative or totally non-specific.

Phencyclidine

Chemically this is 1-(1-phenylcyclohexyl) piperidine hydrochloride, known as PCP or 'angel dust' among many other nicknames. It is often used in combination with other drugs of addiction. A number of deaths have been reported from its use, a variety of modes including hyperthermia, intracranial haemorrhage and high output cardiac failure.

Phencyclidine is excreted in the urine for a long time after ingestion and autopsy samples may be positive for up to a week.

Lysergic acid diethylamide (LSD)

The well-known LSD, which takes its acronym from the German 'Lysergsäurediäthylamid', is a powerful hallucinogenic which is not fatal in itself, as mentioned above. It is an indole alkaloid derivative, of which other members are psilocybin and psieocin, contained in the Mexican mushroom (*Psilocybe mexicana*).

Mescaline, obtained from the cactus *Lophophora williamsii* of central America, is chemically trimethoxyphenethylamine, again not in itself a lethal substance.

CANNABIS

Cannabis, with all its various names in different parts of the world, has at least six active chemical constitutents, the most important of which is one of the tetrahydrocannabinols. Though its effects are a matter of controversy, there seems to be general agreement that used alone, it cannot be blamed for a single death. Proof of the intake of cannabis can be obtained from analysis of urine, blood, and swabs from lips and fingers.

THE AMPHETAMINES

Now rarely used in reputable medical practice because of the undesirable side effects, the amphetamine group of drugs was formerly employed for the abolition of fatigue and for the suppression of appetite. Methylamphetamine sulphate and dexamphetamine were the commonest analogues of amphetamine itself and are still widely available on the illicit market. Death is uncommon from overuse of the amphetamines alone. At autopsy there are no specific findings, apart from the rare possibility of a cerebral or subarachnoid haemorrhage from the induced hypertension.

Toxicology data suggests that after a therapeutic dose of 10 mg, the blood concentration at 2 hours is about 0.035 mg/l. After 30 mg, a peak plasma level of about 0.11 mg/l was observed at 2–5 hours, declining to 0.084 mg/l at 4.5 hours. Chronic abusers consuming large amounts may have blood levels of up to 2–3 mg/l. In the rare fatalities, there is a wider range of blood levels at autopsy, from 0.5 to 41 mg/l (average 8.6), depending on the size of the overdose and the time until death. Liver levels of 474 mg/kg (average 30) and high urine excretion, ranging from 25 to 700 mg/l, with an average of 237 mg/l, are common.

Methylenedioxymethamphetamine (MDMA) or ‘ecstasy’

In recent years, new derivatives of amphetamine have appeared in the drug abuser’s pharmacopoeia, though the substances have been available for medical use for many years. The most commonly encountered is MDMA (3,4-methylenedioxymethamphetamine), known as ‘ecstasy’, ‘XTC’ or ‘ADAM’. Others of the groups are MDA (methyl 3,4-methylenedioxyamphetamine) and MDM (*n*-methyl-MDA). MDMA or ‘ecstasy’ was developed as long ago as 1914 and for some time had a role in psychotherapy as a consciousness-altering agent. It is now widely used as an illegal hallucinogenic drug, and though deaths have been few, they are now being reported from both the USA and Britain. The author (BK) conducted an autopsy on the first fatality in the British Isles, in a man who swallowed a considerable supply on being challenged by the police. There were no autopsy signs apart from a marked generalized cyanotic congestive state and the diagnosis was made purely on toxicological evidence.

Since the first edition of this book, MDMA deaths have increased markedly due to its ubiquitous availability to young people, especially at ‘rave’ parties: hyperthermia, dehydration and myocytolysis are some of the potentially fatal consequences.

COCAINE

Along with heroin, cocaine and its associated drugs like ‘crack’ form the core of the hard-drug problem, from which fatalities are likely to arise. As cocaine is rapidly destroyed when given orally, it is usually taken by injection or sniffed. Recently, a fatality has been reported from absorption from administration via the rectum. This is in addition to some deaths in which cocaine smugglers have died after packets of the drug hidden in their alimentary tract have broken, causing a massive overdose. In India, cocaine has been used by means of urethral instillation and may also be used in the vagina by prostitutes.

In areas where cocaine usage is common, a significant proportion of fetal deaths are associated with the narcotic. In a series reported in New York by Morild and Stajic in 1990, of 103 fetal deaths, toxicology revealed cocaine in 64. The study suggested that fetal death, *abruptio placentae* and abortion were caused by maternal use of the drug.

Death has been recorded by as little as 20–30 mg being applied to the nasal mucosa, but a gram taken by mouth may not be lethal. As with other narcotics, marked habituation and tolerance occurs in chronic users, making estimates of dangerous dose levels difficult to forecast. Intravenous doses are of the order of 100 mg, a common lethal dose being 10 times greater, though far larger amounts can be tolerated by habitual users. Absorption via the nasal mucosa is less effective and larger doses are needed for the same effect than when used parenterally. Though ulceration and even perforation, of the nasal septum in chronic users is mentioned in most standard texts, they are extremely rare lesions.

Death may occur with considerable rapidity in cocaine overdose or hypersensitivity. It may be quite sudden, from cardiac arrest, in first-time users.

At autopsy, there are no specific features. The pulmonary oedema often seen in heroin deaths is not present with cocaine, though the mode of death is also a dysrhythmia.

The diluent used in 'cutting' the drug for street sale may be found in the injection sites, the regional lymph nodes, in the lungs and in other organs. Adulterants may be similar to those used with heroin and include talc, starch, quinine, lactose and dextrose. Particles of cocaine itself may also be found as microemboli. Strychnine has been used because of its bitter taste, like quinine. Deliberate poisoning by a supplier has been known by either increasing the strychnine content or by supplying pure cocaine or heroin, leading to a massive overdose.

Cocaine is an excitant and stimulator of the autonomic nervous system. Sudden dramatic rises in blood pressure can occur, sometimes to over 300 mmHg and cerebral haemorrhage is a possible complication of this acute hypertension.

As with the opioids, autopsy may reveal complications of the septic methods used for injection, apart from the already stated risks of virus infection, such as hepatitis and HIV. In former years, in New York and California, transmission of malaria was a well-known problem amongst those who shared syringes and needles – indeed, one suggestion for the use of quinine as a diluent, was as a treatment for the *Plasmodium*.

Pyogenic infections are most common, with phlebitis and distant embolic abscesses occurring. The injection sites may ulcerate, there can be regional lymphadenitis, but more serious sequelae that may be fatal include endocarditis. This can affect any heart valve, including those on the right side, which are not usually affected in post-rheumatic endocarditis. Many organisms are involved, mainly haemolytic and non-haemolytic streptococci, *Streptococcus faecalis*, *Staphylococcus aureus* and *Pseudomonas aeruginosa* and some fungi. Post-mortem blood cultures frequently show such a mixed flora from contamination that isolation of the true causative organism may be difficult, but a heavy predominant growth may be significant. The advice of a microbiologist should be enlisted in assessing the relevance of a positive blood culture.

Any drug used intravenously, if it has particulate matter admixed, such as starch or talc, may cause foreign-body granulomata in the lungs, when the undissolved components are filtered out in the pulmonary capillary bed. Such granulomata are characteristic of intravenous drug abusers – when viewed under a polarizing microscope, refractile elements may be easily visualized.

As cocaine is so commonly used by sniffing, swabs should always be taken from each nostril using a plain cotton-wool swab. An unused swab should be sent to the laboratory as a control. The full range of blood, urine, stomach contents, liver and vitreous samples should routinely be taken at autopsy. Blood levels in fatal cases vary widely, but typical ranges extend from 1 to 21 mg/l, with a mean of 5.2 mg/l according to Baselt *et al.* (1975).

REFERENCES AND FURTHER READING

Baden MM. 1972. Narcotic abuse: a medical examiner's view. *N Y State J Med* **72**:834–40.

Baden MM. 1972. Homicide, suicide, and accidental death among narcotic addicts. *Hum Pathol* **3**:91–5.

Baselt RC, Allison DJ, Wright JA, *et al.* 1975. Acute heroin fatalities in San Francisco. Demographic and toxicologic characteristics. *West J Med* **122**:455–8.

Billman GE. 1995. Cocaine: a review of its toxic actions on cardiac function. *Crit Rev Toxicol* **25**:113–32.

Burgess C, O'Donohoe A, Gill M. 2000. Agony and ecstasy: a review of MDMA effects and toxicity. *Eur Psychiatry* **15**:287–94.

Carter N, Rutty GN, Milroy CM, *et al.* 2000. Deaths associated with MBDB misuse. *Int J Legal Med* **113**:168–70.

Chakko S, Myerburg RJ. 1995. Cardiac complications of cocaine abuse. *Clin Cardiol* **18**:67–72.

Davis WM, Hatoum HT, Waters IW. 1987. Toxicity of MDA (3,4-methylenedioxyamphetamine) considered for relevance to hazards of MDMA (ecstasy) abuse. *Alcohol Drug Res* **7**:123–34.

Doss PL, Gowitt GT. 1988. Investigation of a death caused by rectal insertion of cocaine. *Am J Forensic Med Pathol* **9**:336–8.

Dowling GP, McDonough ET, Bost RO. 1987. 'Eve' and 'ecstasy'. A report of five deaths associated with the use of MDEA and MDMA. *JAMA* **257**:1615–17.

Drummer OH, Opeskin K, Syrjänen M, *et al.* 1992. Methadone toxicity causing death in ten subjects starting on a methadone maintenance program. *Am J Forensic Med Pathol* **13**:346–50.

Edland JF. 1972. Liver disease in heroin addicts. *Hum Pathol* **3**:75–84.

Finkle BS, McCloskey KL. 1978. The forensic toxicology of cocaine (1971–1976). *J Forensic Sci* **23**:173–89.

Garriot JC, Sturner WQ. 1973. Morphine concentrations and survival periods in acute heroin fatalities. *N Engl J Med* **289**:127–8.

Gill JR, Hayes JA, deSouza IS, *et al.* 2002. Ecstasy (MDMA) deaths in New York city: a case series and review of the literature. *J Forensic Sci* **47**:121–6.

Giroud C, Menetrey A, Augsburger M, *et al.* 2001. Delta(9)-THC, 11-OH-delta(9)-THC and delta(9)-THCCOOH plasma or serum to whole blood concentrations distribution ratios in blood samples taken from living and dead people. *Forensic Sci Int* **123**:159–64.

Gowing LR, Henry-Edwards SM, Irvine RJ, *et al.* 2002. The health effects of ecstasy: a literature review. *Drug Alcohol Rev* **21**:53–63.

Greene MH, Luke JL, Dupont RL. 1974. Opiate 'overdose' deaths in the District of Columbia. I. Heroin-related fatalities. *Med Ann D C* **43**:175–81.

Hayner GN, McKinney H. 1986. MDMA. The dark side of ecstasy. *J Psychoactive Drugs* **18**:341–7.

Helpern M, Rho YM. 1966. Deaths from narcotism in New York city. Incidence, circumstances, and post-mortem findings. *N Y State J Med* **66**:2391–408.

Henry JA. 2000. Metabolic consequences of drug misuse. *Br J Anaesth* **85**:136–42.

Huestis MA, Henningfield JE, Cone EJ. 1992. Blood cannabinoids. II. Models for the prediction of time of marijuana exposure from plasma concentrations of Δ^9-tetrahydrocannabinol (THC) and 11-nor-9-carboxy-Δ^9-tetrahydrocannabinol (THCCOOH). *J Anal Toxicol* **16**:283–90.

Isner JM, Estes NA, Thompson PD, *et al.* 1986. Acute cardiac events temporally related to cocaine abuse. *N Engl J Med* **315**:1438–43.

Karch SB, Billingham ME. 1988. The pathology and etiology of cocaine-induced heart disease. *Arch Pathol Lab Med* **112**:225–30.

Karch SB, Stephens B, Ho CH. 1998. Relating cocaine blood concentrations to toxicity – an autopsy study of 99 cases. *J Forensic Sci* **43**:41–5.

Katsumata S, Sato K, Kashiwade H, *et al.* 1993. Sudden death due presumably to internal use of methamphetamine. *Forensic Sci Int* **62**:209–15.

Kringsholm B. 1988. Deaths among drug addicts in Denmark in 1968–1986. *Forensic Sci Int* **38**:139–49.

Kringsholm B, Christoffersen P. 1987. Lung and heart pathology in fatal drug addiction. A consecutive autopsy study. *Forensic Sci Int* **34**:39–51.

Kringsholm B, Christoffersen P. 1987. Lymph-node and thymus pathology in fatal drug addiction. *Forensic Sci Int* **34**:245–54.

Kringsholm B, Voigt J, Dalgaard JB, *et al.* 1981. Deaths among narcotic addicts in Denmark in 1978 and 1979. *Forensic Sci Int* **18**:19–30.

Laposata EA, Mayo GL. 1993. A review of pulmonary pathology and mechanisms associated with inhalation of freebase cocaine ('crack'). *Am J Forensic Med Pathol* **14**:1–9.

Ling LH, Marchant C, Buckley NA, *et al.* 2001. Poisoning with the recreational drug paramethoxyamphetamine ('death'). *Med J Aust* **174**:453–5.

Lockemann U, Püschel K. 1993. Siderophages in the lung of drug addicts. *Forensic Sci Int* **59**:169–75.

Manno JE, Manno BR, Kemp PM, *et al.* 2001. Temporal indication of marijuana use can be estimated from plasma and urine concentrations of Δ^9-tetra-hydrocannabinol, 11-hydroxy-Δ^9-tetra-hydrocannabinol, and 11-nor- Δ^9-tetra-hydrocannabinol-9-carboxylic acid. *J Anal Toxicol* **25**:538–49.

Martin TL. 2001. Three cases of fatal paramethoxy-amphetamine overdose. *J Anal Toxicol* **25**:649–51.

Mirchandani HG, Rorke LB, Sekula Perlman A, *et al.* 1994. Cocaine-induced agitated delirium, forceful struggle, and minor head injury. A further definition of sudden death during restraint. *Am J Forensic Med Pathol* **15**:95–9.

Moore C, Negrusz A, Lewis D. 1998. Determination of drugs of abuse in meconium. *J Chromatogr B Biomed Sci Appl* **713**:137–46.

Morild I, Stajic M. 1990. Cocaine and fetal death. *Forensic Sci Int* **47**:181–9.

O'Connor A, Cluroe A, Couch R, *et al.* 1999. Death from hyponatraemia-induced cerebral oedema associated with MDMA ('ecstasy') use. *N Z Med J* **112**:255–6.

Parr MJ, Low HM, Botterill P. 1997. Hyponatraemia and death after 'ecstasy' ingestion. *Med J Aust* **166**:136–7.

Paties C, Peveri V, Falzi G. 1987. Liver histopathology in autopsied drug-addicts. *Forensic Sci Int* **35**:11–26.

Polson CJ, Green MA, Lee M. 1983. *Clinical toxicology*, 3rd edn. Pitman, London.

Price KR. 1974. Fatal cocaine poisoning. *J Forensic Sci Soc* **14**:329–33.

Ramcharan S, Meenhorst PL, Otten JM, *et al.* 1998. Survival after massive ecstasy overdose. *J Toxicol Clin Toxicol* **36**:727–31.

Rammer L, Holmgren P, Sandler H. 1988. Fatal intoxication by dextromethorphan: a report on two cases. *Forensic Sci Int* **37**:233–6.

Richards RG, Reed D, Cravey RH. 1976. Death from intravenously administered narcotics: a study of 114 cases. *J Forensic Sci* **21**:467–82.

Siegel H, Helpern M, Ehrenreich T. 1966. The diagnosis of death from intravenous narcotism. With emphasis on the pathologic aspects. *J Forensic Sci* **11**:1–16.

Stead AH, Moffat AC. 1983. A collection of therapeutic, toxic and fatal blood drug concentrations in man. *Hum Toxicol* **2**:437–64.

Steentoft A, Worm K, Christensen H. 1988. Morphine concentrations in autopsy material from fatal cases after intake of morphine and/or heroin. *J Forensic Sci Soc* **28**:87–94.

Stevens BC. 1978. Deaths of drug addicts in London during 1970–4: toxicological, legal and demographic findings. *Med Sci Law* **18**:128–37.

Suarez RV, Riemersma R. 1988. 'Ecstasy' and sudden cardiac death. *Am J Forensic Med Pathol* **9**:339–41.

Watling R. 1983. Hallucinogenic mushrooms. *J Forensic Sci Soc* **23**:53–66.

Weinmann W, Bohnert M. 1998. Lethal monointoxication by overdosage of MDEA. *Forensic Sci Int* **91**:91–101.

Wetli CV. 1987. Fatal cocaine intoxication. A review. *Am J Forensic Med Pathol* **8**:1–2.

CHAPTER 33

Corrosive and metallic poisoning

- Cyanide 585
- Corrosive acids, alkalis and phenols 587
- Oxalic acid and oxalate salts 588
- Ethylene glycol poisoning 589
- Metallic poisons 589
- References and further reading 592

Toxicology is a vast subject, most of it concerned with the nature, occurrence, symptomatology, biochemistry, mode of action and treatment of a wide range of poisonous substances. Many forensic medicine textbooks, especially those from Asia, devote a major part of their text to all these aspects of hundreds of toxic substances, many of which are seldom – if ever – encountered by a pathologist in most parts of the world. As the autopsy appearances of most poisons are non-specific, it seems fruitless to offer a repetitive catalogue, and therefore the descriptions selected here refer to some of those that either have specific features or are encountered more often. This chapter describes the autopsy appearances in a range of poisons that can broadly be classed as 'corrosive', even if this is not necessarily their main lethal mode of action. In addition, several toxic heavy metals will be discussed, again from the point of view of autopsy findings and relevant toxicological laboratory findings.

CYANIDE

Cyanide is a relatively common poison, both in suicide, accident and, occasionally, homicide. It forms part of lethal toxicity of many fires in buildings, where smoke inhalation kills the majority of victims, rather than burns (Chapter 11). Although the autopsy diagnosis of acute cyanide poisoning is rarely in doubt, toxicological analysis may be difficult to interpret because of both the destruction and production of cyanide in the dead body and even in stored blood samples awaiting analysis. Acute cyanide poisoning is most often self-administered (70 per cent in one series), in which case usually the sodium or potassium salt is swallowed. It may be accidental or industrial, in which case either salts may be involved, or it may be the free gas liberated from some commercial process.

Homicidal poisoning is rare, except for the mass homicides which still occur, such as the Jonesville tragedy in Guyana, or the use of cyanide as a weapon of war against civilians in the Middle East. It has also been used for judicial execution in parts of the USA, a practice which seems to be reviving in recent years.

Cyanide acts only as free hydrogen cyanide and therefore swallowed salts need to meet either water or gastric acid before liberating hydrocyanic acid, a process that takes only a few seconds. The fatal dose of cyanide is small, of the order of 150–300 mg, which allowed it to be used as hidden suicide pills by prominent Nazis at the end of the last war. Recovery has been recorded from far greater doses, however, such as 2–4 g of potassium cyanide. Much depends on the purity of cyanides, as they tend to decompose in storage and old samples may contain only half the weight as active cyanide.

Autopsy findings in cyanide poisoning

Cyanide acts by linking with the ferric iron atom of cytochrome oxidase, preventing the uptake of oxygen for cellular respiration. Cyanide cannot combine directly with haemoglobin, but can do so through the intermediary



FIGURE 33.1 *Haemorrhagic gastric mucosa in cyanide poisoning.*

compound methaemoglobin. Cyanides are moderately corrosive through their alkaline nature, causing local tissue damage that is unrelated to their more general toxicity via enzyme inhibition.

Externally there can be wide variations in the appearance. Traditionally, the hypostasis is said to be brick-red, due to excess oxyhaemoglobin (because the tissues are prevented from using oxygen) and to the presence of cyanmethaemoglobin. Many descriptions refer to a dark pink or even bright red skin, especially in the dependent areas, which can be confused with carboxyhaemoglobin. The few cases seen by the authors have shown a marked dark cyanotic hypostasis, perhaps caused by lack of oxygenation of the red cells by paralysis of the respiratory muscles. There may be no other external signs apart from the colour of the skin and possibly black vomit around the lips.

There may be a smell of cyanide about the body, though it is well known that many persons cannot detect this, the ability being a sex-linked genetic trait. This may be of importance to pathologists and mortuary staff, as corpses dead of cyanide poisoning can present a health hazard. A former colleague of the author (BK) became ill and was temporarily disabled shortly after conducting an autopsy on a suicide who had swallowed a massive amount of potassium cyanide. Presumably he had inhaled hydrogen cyanide from the stomach contents when examining the viscera.

Internally the tissues may also be bright pink caused by the oxyhaemoglobin that cannot be utilized by the tissues – which is probably more common than the presence of cyanmethaemoglobin. The stomach lining may be badly damaged and can present a blackened, eroded surface, by altered blood staining the stripped mucosa. This is mainly because of the strongly alkaline nature of the hydrolysed sodium or potassium salts of cyanide; hydrogen cyanide itself causes no such damage. In less severe cases, the stomach lining will be streaked with dark red striae, where the rugae have been eroded while leaving the intervening folds relatively unharmed. The stomach may contain frank or altered blood from the erosions and haemorrhages in the walls. If the cyanide was in dilute solution, there may be little damage to the stomach, apart from pinkness of the mucosa and perhaps some petechial haemorrhages. There may also be undissolved white crystals or powder, with the almond-like smell of cyanide mentioned above.

As death is usually rapid, little of the contents will have passed into the intestine. The oesophagus may be damaged, especially the mucosa of the lower third, though some of this may be a post-mortem change from regurgitation of the stomach contents through the relaxed cardiac sphincter after death. The other organs show no specific changes and the diagnosis is made by history, smell and the reddish colour of the internal tissues, and often skin.

Toxicological analysis

The usual blood, stomach contents, urine and any vomit should be submitted to the laboratory, taking particular care that the samples present no hazard to those packing, transporting or unpacking them. The laboratory should be warned in advance that a possible cyanide case is coming their way.

If death was possibly caused by the inhalation of hydrogen cyanide fumes, a lung should be sent intact, sealed in a nylon (not polyvinylchloride) bag.



FIGURE 33.2 *Skin burns on a victim of lysol suicide. The trickle pattern makes it obvious that the man was either standing or sitting erect when he drank the fluid. Lysol burns are usually leathery and brownish-purple.*

It is important to get the samples to the laboratory as soon as possible (in terms of days) to avoid the spurious formation of cyanide in stored blood samples. This usually occurs at room temperature so, if there is to be a delay, refrigeration is essential. By contrast, some positive samples may actually decrease on storage, as described by Curry (1969). Up to 70 per cent of the cyanide content may be lost after some weeks, from reaction with tissue components and conversion to thiocyanate.

The amount found on analysis naturally depends on the amount taken and the time between administration and death. Though the latter is usually measured in minutes, low dosage – or treatment – may allow survival for hours or even days.

Assuming that no spurious cyanide is formed, any significant amount found is evidence of cyanide ingestion, which in itself is abnormal and presumably confirmatory evidence of poisoning. However, Karhunen *et al.* (1991) have reported a case in which post-mortem burning of a homicide victim led to a blood cyanide level of 10 mg/l, presumably due to passive diffusion of cyanide through body cavities opened by the fire.

Typical blood levels in one series of fatal cases following ingestion of the poison range from 1 to 53 mg/l, with an average of 12 mg/l. The spleen always has the highest tissue concentration, presumably because it contains so many red cells; in the same series, the spleen level was between 0.5 and 398 mg/l, with a mean of 44 mg/l. In another series, mean blood levels were 37 mg/l.

CORROSIVE ACIDS, ALKALIS AND PHENOLS

Corrosive poisons were formerly common suicidal agents, though they are now relatively rare in Western countries, probably because of the ease of obtaining less painful substances. In some parts of the world, mineral acids are still often used for homicide, assault ('vitriol-throwing') and suicide. In Malaya, reagents used in rubber production, such as formic and acetic acids, were often taken as a means of self-destruction by young women, especially Tamil rubber workers.

In Britain, acids and alkalis are now almost unknown as agents of death. Even the occasional use of sulphuric 'battery acid' as a weapon of assault rarely causes death. The phenolic corrosives, however, such as carbolic acid and lysol, are occasionally encountered as suicidal agents. Toxicologically, none of these presents much problem, as the damage is often structural rather than poisonous, unless the victim survives long enough to have complications such as renal failure or chest infections. All the corrosive substances have the following features in common:

- There may be spillage of the fluid on the exterior of the body, corroding the skin in a pattern which may be helpful in reconstructing the posture of the victim at the time of drinking the substance. The lips may be burnt, and trickle and splash marks may run from the mouth down the chin, neck and chest. The pattern of burns at the mouth may sometimes indicate the shape of the container from which the poison was drunk, as the wide brim of a cup may mark the cheeks, while a bottleneck may sit more cleanly in the mouth. If the person was standing or sitting, then these runnels of fluid may pass down the chin onto chest and abdomen. If lying, then they may run across the face and cheeks and pass to the back of the neck. Further spillage may come from the nostrils due to spluttering and gagging. The hands may also be affected if the hands are instinctively brought up to the face.
- The interior of the mouth may be eroded, and the tongue swollen or shrivelled, according to the nature of the corrosive agent. The pharynx, larynx and oesophagus are all eroded, and if survival lasts more than a few minutes the glottis area may become oedematous. Spillage into the larynx and air passages may allow the respiratory mucosa to be damaged, and aspiration of liquid or vapour into the lungs can cause rapid pulmonary oedema and haemorrhages.



FIGURE 33.3 *Corrosion of larynx, oesophagus (a) and stomach (b) in suicidal ingestion of concentrated hydrochloride acid with alcohol.*

- The lower oesophagus and stomach rapidly become damaged, with discoloration, desquamation and sometimes perforation. Attempts at passing a stomach tube may themselves penetrate the softened wall of the oesophagus or stomach. If survival lasts long enough, some corrosive may pass through to damage the small intestine, but this is rare because of the time factor and spasm of the pylorus.
- All may cause death by pulmonary oedema from spillage into the lungs: if survival lasts a day or more, then a fulminating bronchopneumonia may be the terminal event.

The different corrosive agents have different actions on soft tissues, which can sometimes be differentiated by appearance and smell, though the mineral acids are not all that different. The phenolic compounds can usually be detected by smell alone. Strong acids act by dehydrating the tissues, coagulating the proteins and converting haemoglobin to haematin.

Sulphuric acid, in concentrated form, is extremely corrosive and produces great heat in contact with water or tissues. The tissues are grey to black, rather dry and dehydrated. They may actually be charred into a blackened crust by the generated heat. The gastric lining may be grey, dark brown or black, or mixtures of all colours, depending upon the amount of altered blood in each part. Perforation may occur.

The oesophagus and stomach may be grey and swollen, depending on the amount of acid and the amount of food already in the stomach. The tongue may be grey or black and distorted.

Nitric acid is similar, but has a brownish-yellow cast to its mucosal damage. There may be yellow or brown sharp-edged patterns on the skin burns of the face, with the usual trickle marks coming down from the corners of the mouth. Yellow fumes may arise from the stomach contents if a considerable quantity is present. The internal appearances are of yellowish-brown sloughing, though perforation seems less common than with sulphuric acid.

Hydrochloric acid has similar effects, especially on mucous membranes, but is not so injurious to intact skin as sulphuric and nitric acids. The stomach may be converted into a slimy, softened mass and can perforate. The colour is greyish to black, depending on the amount of altered blood.

Sodium hydroxide in concentrated form is also a corrosive, but soft, slippery slime is the characteristic appearance and feel to tissues damaged by caustic soda. The colour is dirty white to grey.

Phenol and lysol are also damaging and affect the tissues in much the same way as acids and alkalis. Carbolic acid (pure phenol) tends to stiffen the tissues and bleach them so that hard, cracked, whitish surfaces are seen on the face and skin. Internally, the same stiffness is noted in the oesophagus and stomach. Lysol is a soapy solution of phenol and cresols. It discolours the tissues a brownish purple, but is otherwise similar to phenol in its action.

OXALIC ACID AND OXALATE SALTS

These are not so corrosive as the mineral acids, but are poisonous and often act quickly, death occurring within minutes or the hour, from shock or hypocalcaemia. The acid is locally corrosive, but also has a systemic effect that may well be fatal even if the local damage is non-lethal.

At autopsy, if an appreciable amount of either the white crystals or a strong solution has been swallowed, the local effect is a bleaching, the mucosa of mouth, pharynx and oesophagus being white, though local haemorrhage can streak this with red. The stomach contains altered blood from the damaged mucosa and is dark brown or black from acid haematin, the wall studded with acute erosions. Calcium oxalate crystals may be seen in the stomach contents or in scrapings from the mucosa.

In those who have survived the acute phase, death may be caused by abnormalities of the muscle function (including the myocardium) from the hypocalcaemia, caused by the precipitation of body calcium as insoluble calcium oxalate. More common is renal failure, death occurring 2–10 days later. The renal tubules suffer necrosis, primarily in the proximal convoluted tubules. This is not caused by the presence of calcium oxalate crystals, though these can be demonstrated histologically in the kidney.

ETHYLENE GLYCOL POISONING

Though in no sense a corrosive poison, ethylene glycol has certain features in common with oxalate poisoning and is so common relative to death from mineral acids that it cannot be omitted. The glycols are used widely as antifreeze agents in motor engines and as solvents in industry, so they are easily available. Because of their chemical inclusion in the alcohol group, they are abused as a source of intoxication, as well as being accidental and suicidal agents. At least 40–60 deaths a year are reported and this is probably an underestimate. The compounds involved are ethylene, diethylene, propylene and hexylene glycols. These do not have the same toxic effects (in fact, propylene glycol is virtually non-toxic), but ethylene glycol is the most commonly encountered. When drunk in excess of 100–200 ml, it is almost certain to be fatal unless specific treatment is given, such as dialysis and competition with alcohol.

The first effects resemble drunkenness, but this passes into coma and death often within the first day. The glycol is metabolized in the body, a small but significant amount (about 1 per cent) being converted to oxalic acid, via the process glycol–glyoxal–glycolic acid–formic acid–glyoxylic acid–oxalic acid. It is not clear which of these compounds causes the most damage to the tissues.

At autopsy there is no local damage, but widespread precipitation of the sheaf-like doubly refractile crystals of calcium oxalate into the tissues can be rendered visible microscopically by the use of polarized light. It is a matter of controversy whether this crystal deposition is the cause or merely a side effect of the lethal action of glycols. There may be cerebral oedema and a chemical meningoencephalitis. In the kidney there is a tubular necrosis similar to that in oxalate poisoning, and the crystals can be seen in the interstitial tissues and the tubules. Diffuse liver damage can also occur.



FIGURE 33.4 *Birefringent calcium oxalate crystals in kidney in ethylene glycol poisoning as seen in polarized light under a microscope.*

Laboratory analysis in ethylene glycol poisoning

The blood levels naturally depend on the time that has elapsed since ingestion. It is usually greater than 300 mg/l and the mean is as high as 2400 mg/l in samples taken before the second day. The brain may contain from 300 to 4000 mg/kg and the urine from 600 to 10 000 mg/l, with a mean of 5700 mg/l.

METALLIC POISONS

There is a whole range of metallic poisons, most of them from the upper reaches of the Periodic Table, accounting for their usual description as ‘heavy metals’. The vast majority of toxic effects come from environmental and occupational poisoning, both chronic and acute. Acute poisoning by suicide, accident and homicide is becoming much less common, both because of the availability of other toxic agents, and because of greater awareness and controls on the environmental and industrial hazards of heavy metals. In former years, especially the nineteenth century, heavy-metal poisoning was common in homicide, but is now rarely seen in Western countries, mainly because they are now known to be easily detectable.

As the subject is dealt with in great detail by so many textbooks and monographs, only one such poison – arsenic – will be discussed, together with a mention of any significant differences with other metals.

Arsenic

A constituent of all animal tissue, arsenic is the twelfth most abundant element on earth. This emphasizes the need for strict controls when making analysis for arsenic in human fluids or tissues, as the excretion of a healthy person on a diet rich in fish (especially shellfish) can exceed that seen in chronic arsenical poisoning. Similarly, where an exhumation is performed after allegations of poisoning, full control samples of soil and grave water must be taken to ensure that arsenic found in the body could not have arisen from local contamination (Chapter 1).

Arsenic metal is not poisonous, only its compounds. These interfere with cellular respiration by combining with the sulphydryl groups of mitochondrial enzymes, especially pyruvate oxidase and certain phosphatases. Arsenic has a particular target in vascular endothelium, accounting for the many lesions caused by increased permeability, tissue oedema and haemorrhage, especially in the alimentary canal.

Arsenical poisoning may arise from the ingestion of arsenious oxide, a tasteless white powder – from copper, sodium and potassium arsenites, arsenates of lead and calcium, arsenic sulphides and gaseous arsine (confined to industry). In forensic practice, the rare cases of arsenic poisoning are now usually from arsenious oxide or one of the arsenites.

Arsenical poisoning may be acute or chronic, the latter being the presentation of most environmental and occupational toxicity. Suicides are obviously invariably acute, whereas the uncommon homicidal cases may be either acute or chronic.

FATAL DOSAGES IN ARSENICAL POISONING

If taken on an empty stomach, especially in solution, only about 150 mg may be fatal, but usually some 250–300 mg are needed as a minimum lethal dose. Much larger quantities have been survived and there is some evidence that tolerance to arsenic can be attained. With large doses, much may be vomited. Death can be rapid – within hours from ‘shock’ and cardiorespiratory failure – or may be delayed for many days, when hepatorenal failure is the mode of death. In chronic poisoning, no lethal dosage can be indicated, as if the ingestion exceeds the small normal excretion rate, then a cumulative build-up of arsenic will occur.

Autopsy findings

In acute poisoning the findings may be minimal, if death occurs within hours. There may be some mild irritation of the upper gastrointestinal tract, such as reddening of the gastric mucosa, especially along the top edges of the rugae. The description of ‘red velvet’ has been applied to some stomach linings in acute arsenic poisoning. There may be mucus coating and granules of the poisonous agent may be trapped on the lining – a reason for sending both contents and stomach wall for analysis, as in most suspected poisonings of any type. The intestines are usually normal in acute poisoning.

The only other lesion commonly seen is subendocardial haemorrhage on the left ventricular wall. This, of course, is a common finding in any severe shock condition when sudden hypotension occurs. It is seen in any gross injury, with loss of blood volume, blood pressure and neurogenic shock. Head injuries and raised intracranial pressure are other conditions in which these lesions are prominent (Chapter 13). The phenomenon can be rapid, the author (BK) having seen them in the victims of military air crashes where the heart was avulsed from its base at the moment of impact. One of the best descriptions of subendocardial haemorrhages was given by Sheehan in 1940 in obstetrical catastrophes. The haemorrhages are situated on the upper part of the interventricular septum and on the opposing papillary muscles. The most severe the author (BK) has ever seen was in a massive suicidal overdose of arsenious oxide, where the haemorrhages were actually raised blood-filled blisters under the endocardium. These suggested the true diagnosis before analysis was carried out, albeit with an element of speculative good luck.

In chronic arsenical poisoning, the picture is quite different, though unless some suggestive history or circumstantial evidence is available, the diagnosis may be extremely difficult. As many a clinician has discovered to his chagrin in the past years, many a chronic arsenical poisoning has been misdiagnosed as a gastroenteritis.

Part of forensic mythology surrounds the alleged preservation of corpses dying from arsenic poisoning. This has been endlessly discussed, but there is no real evidence that it is true. A more likely explanation is that the dehydration from diarrhoea in chronic poisoning retards the usual moist putrefaction.

Externally there may be a diffuse abnormality of the skin, with a dry, scaly, hyperkeratotic surface. Clinically, there is a ‘rain-drop’ punctate pigmentation, but this may not be apparent after death unless really marked. It is more common in skin flexures and over the forehead and neck. There may be some hair loss. Puffy thickening and oedema of the face has been described, suggestive of myxoedema.

Internally the stomach may be normal or may show a chronic gastritis with thickening of the mucosa and subserous coats. Mucus formation may be noticeable and there may be a patchy inflammatory redness of some of the rugae. Sometimes there is a haemorrhagic gastritis with acute and chronic erosions. The small intestine is dilated and generally reddened, with thickened mucosa, the whole picture being of a non-specific congestion oedema so commonly seen in any enteritis.

There is rarely any mucosal ulceration. The contents may be copious and fluid, the usual description of 'rice-water' being applied. The large intestine may show minimal changes or be normal: the contents may be fluid and similar to the small bowel. The liver may reveal fatty change or more severe necrosis, sometimes at the periphery of the lobule. Severe liver damage may be associated with externally apparent jaundice. The kidney is damaged in chronic toxicity, there being non-specific tubular necrosis. The myocardium may also show myofibril damage, interstitial collection of cells and sometimes fatty degeneration.

TOXICOLOGY SAMPLING AND ANALYTICAL RESULTS

In acute poisoning, the major requirement is the stomach and contents, and preferably the small intestine, tied off at each end. Blood, urine and liver should also be taken.

In chronic poisoning, especially if the diagnosis is not firmly established from circumstantial and gross autopsy findings, a much wider range of samples is needed:

- blood from peripheral veins
- stomach and contents
- small intestine and contents
- sample of large bowel contents
- urine
- bile
- whole liver
- one kidney
- nail clippings or whole nails
- hair samples – whole length of at least 20 hairs, including roots.

Arsenic levels in blood are elevated only for a short time following absorption, unless exposure is continuous. The highest concentrations of arsenic are found tissues rich in sulphydryl (SH-) groups, such as skin, hair and nails. Typical levels of arsenic found in healthy persons unexposed to extra amounts over and above that normally (but variably) present in their environment are as follows: urine, <2–20 μg/l; blood, <0.5–4 μg/l; liver, <60 μg/kg (dry weight); nails, $<10^3$ μg/kg (dry weight).

It was formerly thought that it took a week or two for ingested arsenic to find its way into the keratinized tissues such as hair and nails. More sensitive analytical techniques have, however, shown that it can appear there within hours of ingestion by mouth. The explanation was originally offered that arsenic was rapidly secreted into sweat, and spread to the hair and nails by surface diffusion. This has recently been disproved by neutron activation analysis and the mechanism remains obscure. The test for estimating the timing and duration of arsenic administration by analysing different lengths of the hair shaft has thus been vindicated. Arsenic can remain stored in keratin for several years after administration ceases.

TABLE 33.1 *Levels in acute arsenious oxide poisoning from 49 fatalities (Rehling 1967)*

	Range	Average
Blood (mg/l)	0.6–9.3	3.3
Liver (mg/kg)	2.0–120	29.0
Kidney (mg/kg)	0.2–70	15.0
Spleen (mg/kg)	0.5–62	8.8
Brain (mg/kg)	0.2–4.0	1.7

Antimony

Antimony is similar to arsenic in many respects. Apart from industrial exposure, the usual vehicle of poisoning is 'tartar emetic', antimony potassium tartrate. This has been used suicidally and homicidally, as well as in some accidental deaths. The pathology and toxicology are similar to that of arsenic, the minimum fatal dose of the tartrate being about 150 mg, though this was formerly the normal intravenous dose in the treatment of bilharzia. Vastly greater amounts of tartar emetic have been survived, so the minimal lethal dose is not a particularly useful concept, as with many other poisons.

Occupationally unexposed people have either zero or not more than 0.01 mg/l of antimony in their blood and a tenth of this concentration in their urine.

Baselt (2002) quotes a case of acute poisoning from antimony trichloride where the following concentrations (in mg/l or mg/kg) were found on analysis: blood, 4–6; liver, 45; kidney, 32; bile, 404.

Thallium

Though other heavy metals have declined in forensic importance over the past century, thallium has several times been used homicidally in recent years, sometimes for multiple poisonings. Thallium is used as a rat killer and widely employed in industry, especially in glass manufacture. It has curious aspects in relation to forensic pathology, in that it can be seen radiologically in the intestine and deposited in the liver, so in the rare event of a pathologist suspecting thallium poisoning,

TABLE 33.2 *Fatal thallium concentrations (mg/l or mg/kg) collected by Baselt (2002)*

	Range	Average
Blood	0.5–11	4.0
Urine	1.7–11	5.2
Kidney	6–20	11.0
Liver	5–29	15.0

X-rays of the body should be taken before autopsy. The other unique aspect is that it is probably the only homicidal agent to be confirmed after cremation. In the Young case in Britain in 1971, where two people died and several others were non-fatally poisoned by Young, thallium was detected retrospectively in the ashes of one of his victims.

The fatal dose is somewhere about 1 g, depending upon the type of thallium compound employed, as there are several different salts available, such as the acetate, sulphate or nitrate. The estimates vary from 6 to 40 mg/kg body weight, with an average of about 12 mg/kg.

Autopsy appearances are variable and non-specific, but pallor and streaking of a pale, degenerate myocardium have been recorded. Hair loss is one of the clinical signs that arouses suspicion of thallium poisoning, as it was formerly used as a depilatory. This effect begins about a week after administration, but may not be noticeable for twice that time. Large tufts tend to come away, rather than a general thinning. Loss of the outer third of the eyebrows is said to be a significant sign, though these are also the areas that are lost in hypothyroidism.

Examination of the roots of surviving hairs may show a black coating, caused not by the thallium itself, but by an excess of melanin. Liver necrosis and renal tubular necrosis are non-specific findings in those who survive for some time.

REFERENCES AND FURTHER READING

Ballantyne B. 1976. Changes in blood cyanide as a function of storage time and temperature. *J Forensic Sci Soc* **16**:305–10.

Barillo DJ, Goode R, Esch V. 1994. Cyanide poisoning in victims of fire: analysis of 364 cases and review of the literature. *J Burn Care Rehabil* **15**:46–57.

Baselt RC. 2002. *Disposition of toxic drugs and chemicals in man*, 6th edn. Biomedical Publications, Foster City, CA.

Baud FJ, Barriot P, Toffis V, *et al.* 1991. Elevated blood cyanide concentrations in victims of smoke inhalation. *N Engl J Med* **325**:1761–6.

Blackwell M, Robbins A. 1979. Arsine (arsenic hydride) poisoning in the workplace. *Am Ind Hyg Assoc J* **40**:A56–61.

Bogusz M. 1980. Vitreous humour as reliable material for ethylene glycol determination. *Forensic Sci Int* **16**:75–6.

Bowen DA, Minty PS, Sengupta A. 1978. Two fatal cases of ethylene glycol poisoning. *Med Sci Law* **18**:101–7.

Broor SL, Kumar A, Chari ST, *et al.* 1989. Corrosive oesophageal strictures following acid ingestion: clinical profile and results of endoscopic dilatation. *J Gastroenterol Hepatol* **4**:55–61.

Chaturvedi AK, Smith DR, Canfield DV. 2001. A fatality caused by accidental production of hydrogen sulfide. *Forensic Sci Int* **123**:211–14.

Cheng JT, Beysolow TD, Kaul B, *et al.* 1987. Clearance of ethylene glycol by kidneys and hemodialysis. *J Toxicol Clin Toxicol* **25**:95–108.

Chikasue F, Yashiki M, Kojima T, *et al.* 1988. Cyanide distribution in five fatal cyanide poisonings and the effect of storage conditions on cyanide concentration in tissue. *Forensic Sci Int* **38**:173–83.

Christesen HB. 1995. Prediction of complications following caustic ingestion in adults. *Clin Otolaryngol* **20**:272–8.

Curry A. 1969. *Poison detection in human organs.* Thomas, Springfield, IL.

Curry AS. 1963. Cyanide poisoning. *Acta Pharmacol Toxicol* **20**:291–4.

Curry AS, Price DE, Rutter ER. 1967. The production of cyanide in post mortem material. *Acta Pharmacol Toxicol (Copenh)* **25**:339–44.

Davis LE, Standefer JC, Kornfeld M, *et al.* 1981. Acute thallium poisoning: toxicological and morphological studies of the nervous system. *Ann Neurol* **10**:38–44.

Dilawari JB, Singh S, Rao PN, *et al.* 1984. Corrosive acid ingestion in man – a clinical and endoscopic study. *Gut* **25**:183–7.

Erkens M, Kellner H. 1981. [Toxicologic course studies in thallium poisoning.] *Beitr Gerichtl Med* **39**:157–61.

Fernando GC, Busuttil A. 1991. Cyanide ingestion. Case studies of four suicides [published erratum appears in *Am J Forensic Med Pathol* 1993 Dec;**14**(4):353]. *Am J Forensic Med Pathol* **12**:241–6.

Ferrari LA, Arado MG, Giannuzzi L, *et al.* 2001. Hydrogen cyanide and carbon monoxide in blood of convicted dead in a polyurethane combustion: a proposition for the data analysis. *Forensic Sci Int* **121**:140–3.

Galvan-Arzate S, Santamaria A. 1998. Thallium toxicity. *Toxicol Lett* **99**:1–13.

Gebel T. 2000. Confounding variables in the environmental toxicology of arsenic. *Toxicology* **144**:155–62.

Hawley CK, Harsch HH. 1999. Gastric outlet obstruction as a late complication of formaldehyde ingestion: a case report. *Am J Gastroenterol* **94**:2289–91.

Herrero F, Fernandez E, Gomez J, *et al.* 1995. Thallium poisoning presenting with abdominal colic, paresthesia, and irritability. *J Toxicol Clin Toxicol* **33**:261–4.

Hoffman RS. 2000. Thallium poisoning during pregnancy: a case report and comprehensive literature review. *J Toxicol Clin Toxicol* **38**:767–75.

Howell JM. 1986. Alkaline ingestions. *Ann Emerg Med* **15**:820–5.

Ikegaya H, Iwase H, Hatanaka K, *et al.* 2000. Postmortem changes in cytochrome *c* oxidase activity in various organs of the rat and in human heart. *Forensic Sci Int* **108**:181–6.

Ikegaya H, Iwase H, Hatanaka K, *et al.* 2001. Diagnosis of cyanide intoxication by measurement of cytochrome *c* oxidase activity. *Toxicol Lett* **119**:117–23.

Jacobsen D, Akesson I, Shefter E. 1982. Urinary calcium oxalate monohydrate crystals in ethylene glycol poisoning. *Scand J Clin Lab Invest* **42**:231–4.

Jacobsen D, Ostby N, Bredesen JE. 1982. Studies on ethylene glycol poisoning. *Acta Med Scand* **212**:11–15.

Kamijo Y, Soma K, Asari Y, *et al.* 1998. Survival after massive arsenic poisoning self-treated by high fluid intake. *J Toxicol Clin Toxicol* **36**:27–9.

Karhunen PJ, Lukkari I, Vuori E. 1991. High cyanide level in a homicide victim burned after death: evidence of post-mortem diffusion. *Forensic Sci Int* **49**:179–83.

Kazsuba A, Vitez A, Gall J, *et al.* 2000. Gastric hyalinization as a possible consequence of corrosive injury. *Endoscopy* **32**:356–8.

Lander H, Hodge PR, Crisp CS. 1965. Arsenic in hair and nails: its significance in acute arsenical poisoning. *J Forensic Med* **12**:52–67.

Lokan RJ, James RA, Dymock RB. 1987. Apparent post-mortem production of high levels of cyanide in blood. *J Forensic Sci Soc* **27**:253–9.

Makela JT, Laitinen S. 1997. Corrosive oesophageal injury. A study of four cases. *Ann Chir Gynaecol* **86**:360–3.

Marquet P, Clement S, Lotfi H, *et al.* 1996. Analytical findings in a suicide involving sodium azide. *J Anal Toxicol* **20**:134–8.

McCallum R. 1989. The industrial toxicology of antimony. The Ernestine Henry lecture 1987. *J R Coll Physicians Lond* **23**:28–32.

Meggs WJ, Hoffman RS, Shih RD, *et al.* 1994. Thallium poisoning from maliciously contaminated food. *J Toxicol Clin Toxicol* **32**:723–30.

Metter D, Vock R. 1984. [Structure of the hair in thallium poisoning.] *Z Rechtsmed* **91**:201–14.

Mollhoff G, Schmidt G, Bosche J. 1979. ['Thallium poisoning' – neurologic and forensic aspects.] *Arch Kriminol* **163**:1–13.

Moore D, House I, Dixon A. 1993. Thallium poisoning. Diagnosis may be elusive but alopecia is the clue. *Br Med J* **306**:1527–9.

Naon H, Shaul D, Mahnovski V, *et al.* 1996. Fibroproliferative disorder of the antrum after an alkali ingestion. *Am J Gastroenterol* **91**:383–4.

Neil MW. 1957. Immune to cyanide? *J Forensic Med* **4**:17–19.

Nolte KB, Dasgupta A. 1996. Prevention of occupational cyanide exposure in autopsy prosectors. *J Forensic Sci* **41**:146–7.

Pense SC, Wood WJ, Stempel TK, *et al.* 1988. Tracheoesophageal fistula secondary to muriatic acid ingestion. *Burns Incl Therm Inj* **14**:35–8.

Peterson CD, Collins AJ, Himes JM, *et al.* 1981. Ethylene glycol poisoning: pharmacokinetics during therapy with ethanol and hemodialysis. *N Engl J Med* **304**:21–3.

Poklis A, Saady JJ. 1990. Arsenic poisoning: acute or chronic? Suicide or murder? *Am J Forensic Med Pathol* **11**:226–32.

Questel F, Dugarin J, Dally S. 1996. Thallium-contaminated heroin. *Ann Intern Med* **124**:616.

Raekallio J, Jääskeläinen AJ, Mäkinen PL. 1967. The simple demonstration of calcium oxalate crystals in kidneys of victims of ethylene glycol poisoning. *J Forensic Sci* **12**:238–40.

Rehling CJ. 1967. Poison residues in human tissues. *Prog Chem Toxicol* **3**:363–86.

Saha JC, Dikshit AK, Bandyopadhyay MK, *et al.* 1999. A review of arsenic poisoning and its effects on human health. *Crit Rev Environ Sci Technol* **29**:281–313.

Shabalina LP, Spiridonova VS. 1979. Thallium as an industrial poison (review of literature). *J Hyg Epidemiol Microbiol Immunol* **23**:247–55.

Sheehan HL. 1940. Subendocardial haemorrhages in shock. *Lancet* **1**:831–2.

Stajduhar-Caric Z. 1968. Acute phenol poisoning. Singular findings in a lethal case. *J Forensic Med* **15**:41–2.

Stoeppler M, Vahter M. 1994. Arsenic. In: Herber RFM, Stoeppler M (eds), *Techniques and instrumentation in analytical chemistry*, vol. 15, *Trace element analysis in biological specimens*. Elsevier, Amsterdam, London, New York, Tokyo, pp. 291–320.

Tromme I, Van Neste D, Dobbelaere F, *et al.* 1998. Skin signs in the diagnosis of thallium poisoning. *Br J Dermatol* **138**:321–5.

Villanueva E, Hernandez-Cueto C, Lachica E, *et al.* 1990. Poisoning by thallium. A study of five cases. *Drug Saf* **5**:384–9.

Walton EW. 1978. An epidemic of antifreeze poisoning. *Med Sci Law* **18**:231–7.

Weinig E, Schmidt G. 1966. [On the distribution of thallium in the organism in fatal thallium poisoning.] *Arch Toxikol* **21**:199–215.

Westveer AE, Trestrail JH, Pinizzotto AJ. 1996. Homicidal poisoning in the United States: an analysis of the uniform crime reports from 1980 through 1989. *Am J Forensic Med Pathol* **17**:282–8.

Winek CL, Fusia E, Collom WD, *et al.* 1978. Cyanide poisoning as a mode of suicide. *Forensic Sci* **11**:51–5.

Winek CL, Bricker JD, Fochtman FW. 1980. Lithium intoxication. A case study. *Forensic Sci Int* **15**:227–31.

Winek CL, Esposito FM, Cinicola DP. 1990. The stability of several compounds in formalin fixed tissues and formalin-blood solutions. *Forensic Sci Int* **44**:159–68.

Winek CL, Rozin L, Wahba WW, *et al.* 1995. Ingestion of lye. *Forensic Sci Int* **73**:143–7.

Wormald PJ, Wilson DA. 1993. Battery acid burns of the upper gastro-intestinal tract. *Clin Otolaryngol* **18**:112–14.

Wu ML, Tsai WJ, Yang CC, *et al.* 1998. Concentrated cresol intoxication. *Vet Hum Toxicol* **40**:341–3.

Zamir O, Hod G, Lernau OZ, *et al.* 1985. Corrosive injury to the stomach due to acid ingestion. *Am Surg* **51**:170–2.

CHAPTER 34

Deaths from organic solvents

- Solvent abuse 595
- Substances used in abuse 596
- The autopsy on fatal solvent-abuse victims 597
- References and further reading 598

A wide range of organic compounds used in industry and in the home as solvents may cause injury or death, especially when used carelessly or for improper purposes. Other organic substances, often gaseous, can also be fatal when used or abused in the same circumstances.

SOLVENT ABUSE

This phenomenon arose, spontaneously and independently, in several parts of the world in the 1960s. It consists of deliberately inhaling a variety of substances, especially organic solvents, in order to achieve a distortion of consciousness. The effects vary from a state resembling alcoholic intoxication through euphoria (sometimes of an erotic nature) and distortion of perception, to actual hallucinations. The practitioners of this activity are predominantly, though by no means exclusively, male and most are between the ages of about 14 and 22 years, though again there are a few beyond either end of this age range. The majority of deaths occur in solitary users, some 70 per cent being reported by Anderson *et al.* (1985) as having happened when the young person was alone. Sniffing can certainly be a group activity, however, as is seen in schools and even the streets of some cities.

At first, the most common substance inhaled was a toluene-based adhesive and therefore the name ‘glue-sniffing’ soon became attached to the habit, though in fact many substances now used are not adhesives. The more accurate title of ‘solvent abuse’ has now been applied to this widespread and dangerous habit. Although (like the sexual asphyxias, with which there is some cross-relationship) the ratio of deaths to non-fatal escapades is relatively small, the large number of children and young people who indulge in the habit means that a considerable death toll occurs annually.

The usual method of abuse is for a quantity of the solvent or other chemical to be placed in a plastic bag – which may be any kind from a large black polythene garbage sack to a used potato-crisp packet. The open end is then placed against the nose and mouth, and the air inside re-breathed. The warmth of the hand holding the bag, as well as the warm breath, encourages vaporization of the solvent, which enters the tidal air stream and is absorbed through the pulmonary membranes into the blood. When the substance is not a viscous glue, it may be placed on a handkerchief or rag, and inhaled direct as a pad over the nose and mouth.

When gaseous substances are abused, they may be introduced directly into the mouth or nose. A common variety is butane or propane, taken from either a large cylinder used for camping, heating and cooking, or from the small ampoule cylinders sold for refilling gas cigarette lighters. Others are used directly from pressurized aerosol cans, including pain-relieving sprays used for the relief of muscular conditions. Yet again, sniffing may be attained by merely inhaling directly from the neck of a container. Tins, jerry-cans and the petrol-fillers of motor vehicles may be used in this way. Some fire extinguishers contain an organic bromine derivative which is also abused for inhalation. This has a particular propensity for sensitizing the myocardium to catecholamines.

Dangers of solvent abuse

SUDDEN DEATH

The major cause of death appears to be sudden cardiac arrest, following an arrhythmia. Any of the solvents appears to have the ability to sensitize the myocardium to the action of catecholamines, such as noradrenaline. Any sudden ‘flight-or-fight’ stimulus, even some considerable time after sniffing solvents, has the ability to precipitate ventricular fibrillation and hence sudden death. A recent instance seen by the author (BK) involved a youth whose habit was to steal fire extinguishers from trains parked in sidings and inhale the bromine-based contents. Having been in trouble with the police before, he took fright on seeing a constable approaching, though in fact the officer was merely walking his dog. The boy ran from his group of friends and did not reappear, being found dead in some bushes some time later, though he had not ‘sniffed’ that day. The autopsy and toxicology were negative, apart from residual traces of organic substance in his blood.

In addition to this physiological mechanism, actual myocarditis can occasionally occur, as in a 15-year-old girl who dropped dead whilst inhaling from the petrol tanks of vehicles. At autopsy all that the author (BK) could find was a florid, diffuse interstitial myocarditis with minimal myofibril necrosis.

CHEMICAL EFFECTS

The mechanical means of obtaining concentrated solvent vapour is in itself dangerous. Persistent rebreathing can produce hypoxia and hypercapnia, which is additive to the toxic effects of the solvent itself. When large plastic bags are used, the abuser sometimes places his head within the bag and this risks the dangers of rapid death from plastic bag asphyxia (Chapter 14). It is difficult to know if some of these cases are at least partially instances of erotic hypoxia, the effects of both oxygen lack and the hallucinogenic effect of the solvent combining to give both sexual pleasure and a heightened risk of death.

Another potent risk is vomiting while the effects of the solvent incapacitate the victim sufficiently to prevent his reflexes from protecting or clearing his glottis or air passages. The usual warning must be given, however, about uncritically accepting the finding of gastric contents in the air passages at autopsy. This may well have been an agonal regurgitation in a victim who was dying of the common cardiac (ventricular fibrillation) effect of solvents on the myocardium. This has medico-legal relevance in that a fellow abuser or even some other bystander may be accused of failing to render assistance in clearing the air passages, when in fact this was the effect, rather than the cause of death. This is not to say that aspiration of vomit cannot be the cause of death, as in alcoholic intoxication, but the autopsy finding should be backed up with some circumstantial evidence that it occurred before the agonal period.

PHYSICAL DANGER

When gaseous substances are used, such as butane or propane from cylinders, or propellants from aerosol cans, a physical danger is added to the chemical effects. The gases are commonly directed or sprayed into the open mouth while inhalation is performed. The release of high-pressure gas causes rapid cooling by the ‘refrigerator effect’ and the impact of this on the palate, pharynx and larynx may cause a reflex cardiac arrest. The author (BK) has dealt with two such cases, one in a school yard, where the users of small propane refuellers virtually dropped dead in the presence of other youths. The mechanism of this phenomenon is disputed, but freezing of the sensitive pharyngolaryngeal area is surely a parallel to the sudden deaths seen when cold water enters the nasopharynx in sudden immersion deaths.

DANGER TO LONG-TERM USERS

Long-term users can suffer liver damage, typical of halogenated hydrocarbon exposure, with fatty change in the liver and sometimes associated renal damage.

SUBSTANCES USED IN ABUSE

Toluene

Toluene was one of the first substances recognized as giving rise to ‘glue-sniffing’, as it is the solvent for many adhesives, such as the proprietary glue ‘Evostick’. It is an aromatic petrol hydrocarbon used widely in industry as a solvent and thinner for adhesives and paints. It resembles benzene in many of its properties, another substance that can be used in solvent inhalation. Toluene can cause acute and chronic intoxication in industrial situations. Exposure to relatively high concentrations in the air, between 10 000 and 30 000 p.p.m. can cause drunkenness, mental confusion and coma within a few minutes.

In non-fatal toluene abuse, blood levels of 0.3–7.0 mg/l were measured by Bonnichsen *et al.* (1966), with urine excretion of up to 5 mg/l. Those with blood concentrations of 1.0–2.5 mg/l showed some sign of intoxication, while half of those between 2.5 and 10 mg/l were admitted to hospital with marked symptoms. Those who were unconscious or dead had blood levels in excess of 19 mg/l. Nomiyama and Nomiyama (1979) found blood levels of between 50 and 80 mg/l in three fatalities. Baselt (2002) quotes a fatal range of between 10 and 48 mg/l with an average of 22 mg/ml for fatalities, the average in the lung being 12 mg/l and in the brain 47 mg/l. Brain damage has been reported in long-term abusers, with electroencephalographic changes, encephalopathy and occasional cerebral atrophy.

Petrol (gasoline), xylene and benzene

These closely resemble toluene in behaviour, though benzene is said to be more potent in causing intoxication. As with toluene and most other solvents, they can burn the skin if left in contact with it for some time. The odour threshold for benzene has been reported as 1–5 p.p.m. in air. In chronic exposure, benzene can cause bone-marrow depression and fatal aplastic anaemia, but this is not a feature of the shorter exposures in solvent abuse.

Methylene chloride and ethylene dizchloride

These are found in paint strippers and, as these solvents, in many other products. One used for abuse is the solvent for typewriter correction fluids, such as Tippex.

Butane and propane

These have been mentioned earlier, being used direct from pressurized containers. They are light hydrocarbons, being the upper fractions of oil distillation.

Fluorocarbons

These are the substances now blamed for having the worst effect on the ozone layers of the upper atmosphere. They are widely used as refrigerants and propellants in aerosol containers. It is in this latter role that they are widely abused for euphoric and hallucinatory effects. The various compounds are numbered, rather than named, two fluorine atoms being incorporated into molecules that otherwise resemble carbon tetrachloride. Those used for propellants are FC-11 and FC-12.

A similar compound incorporating bromine instead of fluorine is used as a fire extinguisher, as is carbon tetrachloride itself. As long ago as 1970, Bass published a series of 110 sudden deaths, including many from fluorocarbons. As mentioned earlier, these substances sensitize the myocardium to circulating catecholamines. The range of blood concentrations in fatal cases in respect of FC-12 is 0.6–12 mg/l, with a mean of 3.0 mg/l and for FC-11, 1.2–32 mg/l, with a mean of 12 mg/l. In the lung, FC-12 may be present at levels of 0.9–134 mg/kg, with a mean of 33 mg/kg; for FC-11 the corresponding figures are 5.8–94 mg/kg, with a mean of 43 mg/kg.

Carbon tetrachloride

Used as a degreaser, dry-cleaner and fire extinguisher, carbon tetrachloride is easily available from retail outlets as a spot remover. It is quite toxic, though it (unwisely) used to be used in human pharmacy to treat intestinal worms. As little as 3–5 ml can be fatal. Much of its toxicity is industrial, but it has also been used in suicide and solvent abuse. Chronic exposure can cause liver and renal damage, worsened by the simultaneous use of alcohol. Addiction can occur, even from initial exposure during industrial use.

As with most halogenated hydrocarbons, the liver suffers from exposure to tetrachloride. There is a centrilobular necrosis, usually preceded by fatty change if the poisoning is low level and lasting. In fatal cases there may well be virtually total acute yellow atrophy. The liver damage is markedly worsened by a high alcohol intake. Renal changes consist of a tubular necrosis and diffuse fatty degeneration in the cortex.

Post-mortem blood levels vary greatly, but a fatal case has been recorded with a concentration of 260 mg/l. Korenke and Pribilla (1969) found tissue levels at autopsy a week after inhalation as being 142 mg/kg in the liver and 39 mg/kg in the lung.

Other halogenated hydrocarbons

Other halogenated hydrocarbons have similar effects to carbon tetrachloride, but the level of toxicity varies with the number of chlorine atoms in the molecule. The ascending order of danger is methyl chloride, trichlormethane, chloroform and carbon tetrachloride. Others include trichlorethylene, used widely in both anaesthesia (Trilene) and in dry-cleaning. Several other similar compounds have been the cause of fatalities in industry as well as in solvent abuse. The pathological features are similar in most of them, the effects being on the central nervous system in acute massive overdose, whether by ingestion or inhalation, and upon the liver and kidneys in more chronic intoxications.

THE AUTOPSY ON FATAL SOLVENT-ABUSE VICTIMS

The scene should be visited if possible, though it is rare to find the body there, as strenuous resuscitation and removal by ambulance is always a prime consideration in children and young persons found apparently dead. The paraphernalia of sniffing may be seen in its original state.

At autopsy, the clothing should be examined, even though it has almost always been removed for resuscitation attempts. Any soiling with adhesive or solvent stains should be detected and, though volatile, should be kept for forensic science investigation. The best means is to pack them as soon as possible in a nylon bag to retain any vapour; these solvents will penetrate a polyvinylchloride bag and be lost.

Externally, the face should be inspected for any signs of chronic or recent solvent abuse. The act of holding a bag against the lower face, often contaminating it with glue or solvent, may leave skin lesions. These can be red erythematous pimples or actual excoriations from the irritant action of the solvent. The lesions may become infected or scratched, becoming crusted. The rest of the autopsy may be unrewarding from the point of view of gross pathology. Rarely, there may be a fatty liver from long-standing damage from the solvent, especially the halogenated hydrocarbons. Full samples for histological examination should be taken to determine the state of the myocardium, liver and brain. More immediate is the need to obtain samples for analysis.

Vigorous resuscitation, including mouth-to-mouth and chest compression, together with mechanical ventilation and oxygen administration, will obviously blow off much of the solvent in the lungs. If it has already been absorbed, however, some will come back into alveolar air from the lung tissue and the sensitivity of the head-space gas chromatography used for its detection is often sufficient to identify the substance, which can also be detected in blood and tissues.

Blood samples should be taken in the usual manner, including a tube with fluoride for alcohol, which is sometimes also present. A lung should be taken intact for the laboratory. It was formerly the practice to aspirate air from the trachea before removal of viscera, using a 50 ml syringe, which was then sealed and sent to the laboratory. This is impracticable, and the best method is to open the pleural cavity and pass a string ligature round the hilum of a lung, pulling it tight to occlude the main bronchus. This is then drawn tight and the hilum transected. In actual fact, little is lost if the lung is cut off without this procedure, as long as it is put straight into a nylon bag without delay and without squeezing out the contained air. The nylon bags are those that arson investigators use to save material for fire-accelerant examination, as they are impervious to organic solvents.

A urine sample, and unfixed tissue from liver and brain should also be supplied to the toxicology laboratory, though local discussion should be made to determine the requirements of each laboratory.

REFERENCES AND FURTHER READING

al-Alousi LM. 1989. Pathology of volatile substance abuse: a case report and a literature review. *Med Sci Law* **29**:189–208.

Anderson HR, Macnair RS, Ramsey JD. 1985. Deaths from abuse of volatile substances: a national epidemiological study. *Br Med J Clin Res Ed* **290**:304–7.

Backer RC, Pisano RV. 1978. Gas chromatography-mass spectrometry of fluorocarbons 11 and 12 in biologic specimens. *Clin Toxicol* **12**:69–75.

Barrowcliff DF. 1978. Chronic carbon monoxide poisoning caused by methylene chloride paintstripper. *Med Sci Law* **18**:238.

Baselt RC. 2002. *Disposition of toxic drugs and chemicals in man*, 6th edn. Biomedical Publications, Foster City, CA.

Bass M. 1970. Sudden sniffing death. *JAMA* **212**:2075–9.

Bonnichsen R, Maehly AC, Moeller M. 1966. Poisoning by volatile compounds. I. Aromatic hydrocarbons. *J Forensic Sci* **11**:186–204.

Chao TC, Lo DS, Koh J, *et al.* 1993. Glue sniffing deaths in Singapore – volatile aromatic hydrocarbons in post-mortem blood by headspace gas chromatography. *Med Sci Law* **33**:253–60.

Clark MA, Jones JW, Robinson JJ, *et al.* 1985. Multiple deaths resulting from shipboard exposure to trichlorotrifluoroethane. *J Forensic Sci* **30**:1256–9.

Claydon SM. 1988. Myocardial degeneration in chronic solvent abuse. *Med Sci Law* **28**:217–18.

Editorial. 1982. Solvent abuse. *Lancet* **2**:1139–40.

Escobar A, Aruffo C. 1980. Chronic thinner intoxication: clinico-pathologic report of a human case. *J Neurol Neurosurg Psychiatry* **43**:986–94.

Fuke C, Berry CL, Pounder DJ. 1996. Postmortem diffusion of ingested and aspirated paint thinner. *Forensic Sci Int* **78**:199–207.

Garriott J, Petty CS. 1980. Death from inhalant abuse: Toxicological and pathological evaluation of 34 cases. *Clin Toxicol* **16**:305–15.

George B. 1960. Kerosene poisoning. *Med Sci Law* **1**:14–52.

Harada K, Ichiyama T, Ikeda H, *et al.* 1999. A fatal case of oral ingestion of benzine. *Am J Forensic Med Pathol* **20**:84–9.

Harrer G, Kisser W, Pilz P, *et al.* 1973. [Three cases of trichloroethylene resp. Carbon tetrachloride 'sniffing' with fatal outcome.] *Nervenarzt* **44**:645–7.

Heath MJ. 1986. Solvent abuse using bromochlorodifluoromethane from a fire extinguisher. *Med Sci Law* **26**:33–4.

Inoue H, Iwasa M, Maeno Y, *et al.* 1996. Detection of toluene in an adipoceratous body. *Forensic Sci Int* **78**:119–24.

Isenschmid DS, Cassin BJ, Hepler BR, *et al.* 1998. Tetrachloroethylene intoxication in an autoerotic fatality. *J Forensic Sci* **43**:231–4.

Kamijo Y, Soma K, Hasegawa I, *et al.* 1998. Fatal bilateral adrenal hemorrhage following acute toluene poisoning: a case report. *J Toxicol Clin Toxicol* **36**:365–8.

Kim NY, Park SW. 2000. The comparison of toluene determination between headspace-solid phase microextraction and headspace methods in glue-sniffer's blood and urine samples. *J Forensic Sci* **45**:702–7.

Kimura K, Nagata T, Hara K, *et al.* 1988. Gasoline and kerosene components in blood – a forensic analysis. *Hum Toxicol* **7**:299–305.

King MD, Day RE, Oliver JS, *et al.* 1981. Solvent encephalopathy. *Br Med J Clin Res Ed* **283**:663–5.

Korenke HD, Pribilla O. 1969. [Suicide by single inhalation of carbon tetrachloride (CCl_4), with resulting leukoencephalopathy.] *Arch Toxikol* **25**:109–26.

Kringsholm B. 1980. Sniffing-associated deaths in Denmark. *Forensic Sci Int* **15**:215–25.

Levine B, Fierro MF, Goza SW, *et al.* 1981. A tetrachloroethylene fatality. *J Forensic Sci* **26**:206–9.

Morinaga M, Kashimura S, Hara K, *et al.* 1996. The utility of volatile hydrocarbon analysis in cases of carbon monoxide poisoning. *Int J Legal Med* **109**:75–9.

Nomiyama K, Nomiyama H. 1979. [Health effects of trichloroethylene in human subjects (author's transl).] *Sangyo Igaku* **21**:311–34.

Park SW, Kim N, Yang Y, *et al.* 1998. Toluene distribution of glue sniffers' biological fluid samples in Korea. *J Forensic Sci* **43**:888–90.

Poklis A. 1975. Determination of fluorocarbon 11 and fluorocarbon 12 in post-mortem tissues: a case report. *Forensic Sci* **5**:53–9.

Ramsey JD, Flanagan RJ. 1982. The role of the laboratory in the investigation of solvent abuse. *Hum Toxicol* **1**:299–311.

Reed BJ, May PA. 1984. Inhalant abuse and juvenile delinquency: a control study in Albuquerque, New Mexico. *Int J Addict* **19**:789–803.

Ridgway P, Nixon TE, Leach JP. 2003. Occupational exposure to organic solvents and long-term nervous system damage detectable by brain imaging, neurophysiology or histopathology. *Food Chem Toxicol* **41**:153–87.

Sourindrhin I. 1985. Solvent misuse [editorial]. *Br Med J Clin Res Ed* **290**:94–5.

Standefer JC. 1975. Death associated with fluorocarbon inhalation: report of a case. *J Forensic Sci* **20**:548–51.

Suwaki H. 1983. A follow-up study of adolescent glue-sniffers in Japan. *Br J Addict* **78**:409–13.

Tranthim-Fryer DJ, Hansson RC, Norman KW. 2001. Headspace/solid-phase microextraction/gas chromatography-mass spectrometry: a screening technique for the recovery and identification of volatile organic compounds (VOC's) in postmortem blood and viscera samples. *J Forensic Sci* **46**:934–46.

Trochimowicz HJ, Azar A, Terrill JB, *et al.* 1974. Blood levels of fluorocarbon related to cardiac sensitization: II. *Am Ind Hyg Assoc J* **35**:632–9.

Wang CC, Irons SV. 1961. Acute gasoline intoxication. *Arch Environ Health* **2**:715–20.

Watson JM. 1977. 'Glue-sniffing' in profile. *Practitioner* **218**:255–9.

Watson JM. 1979. Morbidity and mortality statistics on solvent abuse. *Med Sci Law* **19**:246–52.

Winek CL, Collom WD. 1971. Benzene and toluene fatalities. *J Occup Med* **13**:259–61.

Winek CL, Wahba WW, Huston R, *et al.* 1997. Fatal inhalation of 1,1,1-trichloroethane. *Forensic Sci Int* **87**:161–5.

APPENDIX 1

Technical methods

- Staining techniques 600
- Diatom technique in suspected drowning 602
- Useful conversion tables 603
- Samples and controls needed for DNA profiling 608

STAINING TECHNIQUES

Periodic acid–Schiff (PAS) for myocardium

In established early infarcts of probably at least 28–24 hours' duration, damaged myofibres stain a pale purple-blue with PAS, compared with the pinker colour of healthy fibres. This stainable material is diastase resistant and is probably a mucoprotein.

(a) Bring sections to water.
(b) Immerse in 1 per cent periodic acid for 5 minutes.
(c) Wash in water for 5 minutes.
(d) Rinse in distilled water.
(e) Immerse in Schiff's reagent for 10 minutes.
(f) Wash in water for 10 minutes.
(g) Stain in haematoxylin for 30 seconds.
(h) Blue in tap water and mount in usual way.

Malic acid dehydrogenase (MDH)

Enzyme histochemistry is the most reliable method of detecting early myocardial infarction. Succinic, lactic, malic, β-hydroxybutyric dehydrogenases and cytochrome oxidase are among those used by many workers and each has its advocates. The author (BK) prefers malate dehydrogenase, though β-hydroxybutyrate is also recommended. Fixed tissue cannot be used, as frozen cryostat sections are required. The method for malate dehydrogenase is given, though the technique for other enzymes is similar, using different substrates; details are found in standard histochemistry texts.

MALATE DEHYDROGENASE METHOD FOR MYOCARDIUM

Normal myocardium stains dark blue–black, mostly concentrated on intracellular mitochondria, with some staining of the cytoplasm. Fibres damaged by anoxia or ischaemia progressively lose their staining properties and may be completely devoid of colour when totally infarcted. There is almost always perivascular survival of a few layers of cells and the subendocardial and subepicardial layers usually also survive: this acts as a built-in control for the staining reaction.

Stock solutions

Buffer

0.2 M for pH 7.0 (store at 0–4°C).

Solution A: 2.4 g trometamol (TRIS) in 100 ml distilled water	25 ml
Solution B: 0.1 M hydrochloric acid	45 ml
(Use ANALAR concentrated HC1 diluted 1/12 for molar, then dilute further 10 times for 0.1 M)	
Distilled water	30 ml

Malic acid substrate

L-Malic acid 6.7 g in 50 ml distilled water.
Add 12 g TRIS to buffer to pH 7.0.
Store frozen.

Sodium cyanide

0.1 M solution: weigh out 0.25 g sodium cyanide in 100 ml distilled water.
Add 8–8.5 ml M hydrochloric acid to buffer at pH 7.2.
Store at 0–4°C.

Tetrazolium salt

Make up nitroblue tetrazolium at 1 mg/ml strength in distilled water. Keep frozen.

Nicotinamide adenine dinucleotide (NAD) – keep solid desiccated in freezer.

Method

Cut cryostat sections from myocardium frozen either in liquid nitrogen or in isopentane/solid carbon dioxide slush.

(a) Place slides carrying sections in 37°C incubator.

(b) Make up incubating medium as follows:

Sodium cyanide solution (0.1 M at pH 7.2)	0.1 ml
NAD coenzyme	6 mg
Nitroblue tetrazolium solution	0.25 ml
TRIS buffer pH 7.0	0.55 ml
Malic acid substrate (1 M at pH 7.0)	0.1 ml

(Check pH and adjust with a small amount of TRIS)

(c) Warm the incubating medium to 37°C and place sufficient on each section with a pipette, covering the section completely. Leave for 30 minutes, mount in glycerine jelly or an aqueous mountant. A negative control can be set up as required by omitting the malate substrate from the incubating medium.

Haematoxylin–eosin (H and E) autofluorescence

Routine formalin-fixed H and E sections can be examined under ultraviolet light for autofluorescence of those fibres that have anoxic or ischaemic damage. Fibres with early infarction show a shift of their secondary emission towards the yellow, away from the usual olive-green of healthy fibres. It has been said that only fibres that reveal increased eosinophilia in ordinary tungsten light will fluoresce in this way, but the authors and co-workers have noted yellow shift in fibres that cannot be detected in tungsten light as being eosinophilic.

Acridine-orange fluorescent stain for myocardium

Either formalin-fixed paraffin sections or unfixed frozen sections can be stained by this technique. The former must be brought to water first. After staining and mounting in water (no other mountant can be used, not even Fluormount), the sections are examined immediately under ultraviolet light. They can be photographed if required. If the cover-slip is removed and the sections allowed to dry, however, they can be retained indefinitely. To review, they need only be wetted and a cover-slip replaced. Normal myocardium is a golden brown or sometimes yellowish brown depending on the optical system used. Damaged fibres show a colour shift to green when viewed under ultraviolet light.

Method

A stock solution of 1 per cent acridine-orange in water is kept refrigerated. This lasts for several months. For use, it is diluted 1/10 with distilled water.

(a) Bring sections to water.

(b) Agitate in the 0.1 per cent stain for approximately 5 seconds, though the time is not critical.

(c) Briefly wash, wipe off the excess water from around the section.

(d) Apply a cover-slip.

They are then ready for immediate examination. The pH of the washing water is not critical and tap water can be used if the pH range is between 6.0 and 7.0.

Martius scarlet blue (MSB) stain for fibrin

This trichrome stain is useful for examining thrombi and emboli and for seeking fibrin in disseminated intravascular coagulation.

(a) Bring sections to water.

(b) Stain with celestine blue for 3 minutes and Mayer's haematoxylin for 1 minute.

(c) Blue in water.

(d) Rinse in 95 per cent ethanol and then stain for 2 minutes with 0.5 per cent Martius yellow in 95 per cent ethanol containing 2 per cent phosphotungstic acid.

(e) Rinse in water and stain with 1 per cent brilliant crystal scarlet in 2.5 per cent glacial acetic acid for 10 minutes.

(f) Rinse in water and treat with 1 per cent aqueous phosphotungstic acid for 5 minutes.

(g) Rinse in water and stain with 0.5 per cent soluble blue (Acid Blue 93) in 10 per cent aqueous acetic acid for 10 minutes.

(h) Rinse and mount.

This method stains fibrin red, erythrocytes yellow and collagen blue.

Lendrum's stain (phloxine-tartrazine)

Though this stain has a number of applications, such as the demonstration of viral inclusion bodies, its major forensic use is in the detection of amniotic fluid embolism deaths associated with pregnancy. The fetal squames are rendered visible much more readily than in haematoxylin–eosin stain.

(a) Stain with Mayer's haematoxylin for 6 minutes and rinse in running water for 5 minutes.
(b) Stain with 0.5 per cent phloxine in 0.5 per cent calcium chloride solution for 20 minutes in a Coplin jar.
(c) Rinse in water and drain almost dry.
(d) Flood with a saturated solution of tartrazine in cellusolve ($C_4H_{10}O_2$; ethylene glycol monomethyl ether), which differentiates counterstain. This takes about 7 minutes and should be monitored microscopically so that red cells appear red–brown.
(e) Rinse by two changes in 95 per cent ethanol and two changes in absolute ethanol.
(f) Transfer straight to xylol and mount.

The keratin of amniotic squames is stained red; nuclei blue and cytoplasm yellow.

The 'WHO' method

The 'WHO' method is similar for demonstrating keratin and mucin-like substances in amniotic fluid embolism.

(a) Bring sections to water.
(b) Stain with celestine blue/Mayer's sequence, rinse.
(c) Differentiate quickly in 0.5 per cent acid–alcohol, then blue.
(d) Stain with erythrosin (1 per cent) for 5 minutes and rinse.
(e) Differentiate quickly in 95 per cent alcohol, rinse.
(f) Stain, with alcian green solution for 5 minutes.
(g) Rinse – the section should now be slightly pink.
(h) Rinse and treat with 95 per cent alcohol.
(i) Stain with ethanolic saffron for 5 minutes.
(j) Mount without going through water.

The alcian green is made by mixing 50 ml of 1 per cent aqueous solution of alcian green with 50 ml of 1 per cent acetic acid then adding 20 mg of thymol and filtering. Ethanolic saffron is made by cutting up strands of saffron and warming in 95 per cent alcohol until no more will elute. This should be a deep yellow solution.

DIATOM TECHNIQUE IN SUSPECTED DROWNING

There are several versions of this method, each with its own advocates. More recent methods have used suction of the filtrate through a millipore membrane to trap the diatoms, but the author (BK) has encountered early clogging of the membrane by debris and prefers the older centrifugation. References to the published methods will be found in Chapter 16.

Take a sample of water from the site where the body was recovered or where the immersion was first thought to have occurred. Several litres should be collected in a clean container and allowed to settle overnight. The top 90 per cent volume is then carefully decanted and the remainder centrifuged. The deposit should be examined under phase-contrast or dark-ground microscopy to see if any diatoms are present. If not, it is pointless to examine the autopsy tissues. If present, they should be retained for species comparison.

If the water contains diatoms, then the material retained at autopsy can be processed. The following procedure should have been followed:

(a) The sternum or a long bone such as the femur, or both, should be removed from the body in the usual way. It should be taken to a part of the mortuary or a side room distant from the cadaver and well-washed externally in a clean bowl or sink. Tap water can be used, if it is checked at intervals to ensure that it is diatom-free. Some water supplies at irregular times contain a few diatoms, though these are rarely numerous enough to cause problems in interpretation.

When the exterior of the bone has been well washed to remove any contamination from the exterior of the body, a clean saw (not used in that autopsy) is employed to open the marrow cavity of femur or sternum. With a clean scalpel or gouge, several grams of marrow are removed into a glass universal (30 ml) container. Obtain red marrow if possible, as fatty yellow marrow causes problems during digestion.
(b) Whole kidney, lung, liver or brain is also washed in this way and 1 × 1 cm cubes (several from each organ) cut with a clean scalpel from the deeper tissue. The organs can then be returned to the autopsy area for the usual gross examination.
(c) Each container, holding its separate tissue, is placed in a fume cupboard and covered with five times the volume of concentrated nitric acid. If metal caps are used on the containers, they may need to be

shielded by polythene sheet to prevent dissolution. Digestion is allowed to proceed at room temperature for 1–2 days or, if the matter is urgent, they can be heated in a water-bath for a number of hours or overnight. When the solid cubes have dissolved into a slurry the containers are gently centrifuged, the supernatant acid poured off and replaced with distilled water. This process is repeated twice more to dilute the acid, knocking up the deposit, and recentrifuging, the final spin being as hard as possible to produce a small button of deposit. This may require transferring to a smaller conical centrifuge tube.

(d) A portion of this is transferred by pipette or loop to a slide and covered with a cover-slip to examination under phase-contrast or dark-ground illumination.

A prolonged search under medium power of the microscope is required before the sample is declared negative. The lung sample should be examined first, as if it is negative it is unlikely that other organs can be truly positive, for diatom-containing water can percolate passively down the air-passages even after death.

Opinion is divided about how many diatoms can be accepted as presumptive evidence of drowning when found in distant organs like brain, bone marrow and kidney. One solitary organism is certainly insufficient and the author (BK) requires five as a minimum under one coverslip before acceptance. The tissue examined may make a difference to the yield. Peabody strongly recommends brain as the choice and condemns femoral marrow, but bone marrow was the tissue used by the pioneers of the technique and seems to the authors to be satisfactory. The type of diatom found in the tissues should correspond to those found in the water sample, though it must be admitted that most diatoms seem to the non-botanical eye to be ovoid or boat-shaped. Expert advice from a suitable biologist should be sought if the issue is important.

USEFUL CONVERSION TABLES

TABLE A1.0 *Conversion factors*

To convert from	To	Multiply by
Centimetres	Inches	0.394
Inches	Centimetres	2.540
Grams	Pounds	0.002
Pounds	Grams	453.592

To convert Centigrade to Fahrenheit, multiply by 1.8 and add 32.
To convert Fahrenheit to Centigrade, subtract 32 and divide by 1.8.

TABLE A1.1 *Approximate weight of bodies*

Stones	Pounds	Kilograms
1	14	6.3
2	28	12.7
3	42	19.0
4	56	25.4
5	70	31.7
6	84	38.1
7	98	44.4
8	112	51.0
9	126	57.0
10	140	63.0
11	154	70.0
12	168	76.0
13	182	82.0
14	196	89.0
15	203	92.0
18	252	114.0

TABLE A1.2 *Height of bodies*

Feet and inches	Inches	Centimetres
4′10″	58″	145.0
4′11″	59″	147.5
5′	60″	150.0
5′1″	61″	152.5
5′2″	62″	155.0
5′3″	63″	157.5
5′4″	64″	160.0
5′5″	65″	162.5
5′6″	66″	165.0
5′7″	67″	167.5
5′8″	68″	170.0
5′9″	69″	172.5
5′10″	70″	175.0
5′11″	71″	177.5
6′	72″	180.0
6′1″	73″	182.5
6′2″	74″	185.0

TABLE A1.3 *Approximate breath–blood-alcohol equivalents*

µg/100 ml breath	mg/100 ml blood
10	23
20	45
30	68
40	91
50	114
60	137
70	160
80	182
90	205
100	228

1 µg/100 ml in breath = 2.28 mg/100 ml in blood.
1 mg/100 ml in blood = 0.43 µg/100 ml in breath.

TABLE A1.4 *Length conversion of wounds, etc.*

Inches	Centimetres
0.25	0.63
0.5	1.27
1.0	2.54
1.5	3.81
2.0	5.08
2.5	6.35
3.0	7.62
4.0	10.16
5.0	12.70

TABLE A1.5 *Normal ranges of biochemical blood analyses*

Sodium	133–147 mmol/l
Potassium	3.4–5.0 mmol/l
Urea	2.5–7.5 mmol/l
Calcium	2.2–2.6 mmol/l
Chloride	95–106 mmol/l
Bicarbonate	22–28 mmol/l
Glucose (fasting)	3.6–5.6 mmol/l
Lactate	0.8–2.0 mmol/l
Phosphate (inorganic)	0.8–1.4 mmol/l
Magnesium	0.6–1.0 mmol/l
Serum protein (total)	60–80 g/l
Albumin	35–48 g/l
Bilirubin	up to 17 μmol/l
Alkaline phosphatase	30–90 IU/l
Amylase	70–300 IU/l
Creatinine	50–100 μmol/l
Creatine kinase (CPK)	Up to 240 IU/l

TABLE A1.6 *Body weight and length 15–30 years.* In this table, three weights (without clothing) are given for each body length: (1) weight for persons of average build = middle entry; (2) weight for lightly built persons = top entry; (3) weight for heavily built persons = bottom entry*

Women					Men				
	Weight (kg)					Weight (kg)			
Body length (cm)	15 yrs	20 yrs	25 yrs	30 yrs	Body length (cm)	15 yrs	20 yrs	25 yrs	30 yrs
142.5	40.8	43.0	44.0	45.3	150	41.7	45.8	47.6	49.4
	45.3	47.6	49.0	50.3		46.2	50.7	53.0	54.8
	51.2	53.0	55.3	56.6		51.6	57.1	59.3	61.6
145	41.2	43.5	44.8	46.2	152.5	42.6	46.7	48.5	50.3
	45.8	48.5	49.8	51.2		47.1	51.6	53.9	55.7
	51.6	53.9	56.2	57.5		53.0	58.0	60.7	62.5
147.5	41.7	44.4	45.8	47.1	155	43.5	47.6	49.4	51.2
	46.2	49.4	50.7	52.1		48.5	53.0	54.8	56.6
	52.1	55.7	57.1	58.4		54.4	59.3	61.6	63.4
150	42.6	45.3	46.7	47.6	157.5	44.9	48.9	50.7	52.1
	47.1	50.3	51.6	53.0		49.8	54.4	56.2	58.0
	53.0	56.6	58.0	59.8		56.2	61.2	63.0	65.2
152.5	43.5	46.7	47.1	48.5	160	46.2	50.3	52.1	53.5
	48.5	51.6	52.6	53.9		51.2	55.7	58.0	59.3
	54.4	58.0	59.3	60.7		57.5	62.5	65.2	66.6
155	44.8	47.6	48.5	49.8	162.5	47.6	51.6	53.9	55.3
	49.8	53.0	53.9	55.3		53.0	57.5	59.8	61.2
	55.3	59.8	60.7	62.1		59.3	64.8	67.0	68.9
157.5	46.2	48.9	50.3	51.2	165	49.4	53.5	55.7	56.6
	51.2	54.4	55.7	56.6		54.8	59.3	61.6	63.0
	57.5	61.2	62.5	63.9		61.6	66.6	69.3	70.7

(*continued*)

TABLE A1.6 *Body weight and length 15–30 years.* (continued)*

Women					**Men**				
	Weight (kg)					**Weight (kg)**			
Body length (cm)	**15 yrs**	**20 yrs**	**25 yrs**	**30 yrs**†	**Body length (cm)**	**15 yrs**	**20 yrs**	**25 yrs**	**30 yrs**†
160	47.1	50.3	51.2	52.5	167.5	51.2	55.3	57.1	58.4
	52.5	55.9	57.1	58.4		56.6	61.2	63.4	64.8
	59.3	62.5	6.43	65.7		63.4	68.9	71.1	72.9
162.5	48.9	51.2	52.5	53.9	170	52.5	56.6	58.9	59.8
	54.4	57.1	58.4	59.8		58.4	63.0	56.2	66.6
	61.2	64.3	65.7	67.5		65.7	70.7	73.4	74.7
165	50.7	53.0	54.4	55.7	172.5	54.4	58.4	60.2	61.6
	56.2	58.9	60.2	61.6		60.2	64.8	67.0	68.4
	63.4	66.1	67.5	69.3		67.5	73.0	75.2	77.0
167.5	52.1	54.9	55.7	57.1	175	55.7	59.8	62.1	63.9
	58.0	60.7	62.1	63.4		62.1	66.6	68.9	70.7
	65.2	68.4	69.8	71.6		69.8	74.7	77.5	79.3
170	53.9	56.2	57.5	58.9	177.5	58.0	61.6	63.9	65.7
	59.8	62.5	63.9	65.2		64.3	68.4	71.1	72.9
	67.5	70.2	71.6	73.4		72.0	77.0	79.7	82.0
172.5	55.3	57.5	59.3	60.2	180	59.8	63.9	66.1	68.0
	61.6	63.9	65.7	67.0		66.6	70.7	73.4	75.7
	69.3	72.0	73.8	75.7		74.7	79.3	82.4	85.2
175	57.1	59.3	60.7	61.6	183	62.1	65.7	68.4	70.7
	63.4	65.7	67.5	68.4		68.9	72.9	76.1	78.4
	71.6	73.8	75.7	77.0		77.5	82.0	85.6	87.9
178	59.3	60.7	62.1	63.4	185.5	63.9	68.0	71.1	72.9
	65.7	67.5	68.9	70.2		71.1	75.2	78.8	81.1
	73.9	76.1	77.5	78.9		79.7	84.3	88.3	91.1
180	61.2	63.0	63.4	64.8	188	66.1	69.8	73.0	75.7
	68.0	69.8	70.7	72.0		73.4	77.5	81.1	83.8
	76.1	78.4	79.7	81.1		82.4	87.0	91.1	94.2

* From Basel JR, Geigy AG. 1953. *Wissenschaftliche Tabellen*, p. 199. By permission.
† Fourth decade weight should be maintained throughout life.

TABLE A1.7 *Weight of fetus (g) in relation to age (month)**

Lunar month	**Streeter**	**Scammon and Calkins**
Second	1.1	3.5
Third	14.2	14.3
Fourth	108.0	86.8
Fifth	316.0	260.9
Sixth	630.0	551.6
Seventh	1045.0	971.4
Eighth	1680.0	1519.0
Ninth	2378.0	2196.1
Tenth	3405.0	2998.8

* From Potter EL. 1961. *Pathology of the fetus and infant*, 2nd edn. Chicago, Year Book Medical Publishers. By permission.

TABLE A1.8 *Length (cm) of fetus in relation to age (month)**

	Crown–rump length		**Crown–heel length**	
Lunar month	**Streeter**	**Scammon and Calkins**	**Dietrich**	**Scammon and Calkins**
Second	2.3	–	3.0	–
Third	7.4	5.1	9.8	7.0
Fourth	11.6	10.7	18.0	15.5
Fifth	26.4	15.5	25.0	22.7
Sixth	20.8	19.7	31.5	29.2
Seventh	24.7	23.6	37.1	35.0
Eighth	28.3	27.1	42.5	40.4
Ninth	32.1	30.5	47.0	45.4
Tenth	36.2	33.6	50.0	50.2

* From Potter EL. 1961. *Pathology of the fetus and infant*, 2nd edn. Chicago, Year Book Medical Publishers. By permission.

TABLE A1.9 *Weights of the organs at various ages (in grams)**

	Lungs		Brain		Heart		Kidneys		Liver		Spleen	
	Men	**Women**	**Men**	**Women**	**Men**	**Women**	**Men**	**Women**	**Men**	**Women**	**Men**	**Women**
New born	51.7	50.9	353	347	19	20	24	24	124	125	8	6
0–3 mth	68.8	63.6	435	411	–	–	–	–	–	–	–	–
3–6 mth	94.1	93.3	600	534	–	–	–	–	–	–	–	–
6–9 mth	128.5	114.7	877	726	41	36	60	52	300	240	26	25
9–12 mth	142.4	142.1										
1–2 yr	170.3	175.3	971	894	54	48	72	65	400	390	35	34
2–3 yr	245.9	244.3	1076	1012	63	62	85	75	460	450	42	41
3–4 yr	304.7	265.5	1179	1076	73	71	93	84	510	500	48	47
4–5 yr	314.2	311.7	1290	1156	83	80	100	93	555	550	53	52
5–6 yr	360.6	319.9	1275	1206	95	90	106	102	595	595	58	57
6–7 yr	399.5	357.5	1313	1225	103	100	112	112	630	635	62	62
7–8 yr	365.4	404.4	1338	1265	110	113	120	123	665	685	64	67
8–9 yr	405.0	382.1	1294	1208	122	126	128	135	715	745	68	71
9–10 yr	376.4	358.4	1360	1226	132	140	138	148	770	810	73	77
10–11 yr	474.5	571.2	1378	1247	144	154	150	163	850	880	82	85
11–12 yr	465.6	535.0	1348	1259	157	168	164	180	950	950	91	93
12–13 yr	458.8	681.7	1383	1256	180	188	178	195	1050	1080	101	103
13–14 yr	504.5	602.3	1382	1243	202	207	196	210	1150	1180	111	112
14–15 yr	692.8	517.0	1356	1318	238	226	212	222	1240	1270	121	120
15–16 yr	691.7	708.8	1407	1271	258	238	229	230	1315	1330	135	127
16–17 yr	747.3	626.5	1419	1300	282	243	244	236	1380	1360	145	134
17–18 yr	776.9	649.5	1409	1254	300	247	260	240	1450	1380	152	140
18–19 yr	874.7	654.9	1426	1312	310	250	270	244	1510	1395	157	146
19–20 yr	1035.6	785.2	1430	1294	318	251	282	247	1580	1405	160	151
20–21 yr	953.0	792.8	–	–	322	252	290	248	1630	1415	162	155

* Boyd E. 1962. In: Altman and Dittmer (eds), *Growth, including reproduction and morphological development*. Biological Handbooks, Federation of American Societies for Experimental Biology, Washington, pp. 346–8.

TABLE A1.10 *Heart: men and women, weight in relation to body weight by sex**

Men				Women			
Body weight		**Heart weight (g)**		**Body weight**		**Heart weight (g)**	
Pounds	**Kilograms**	**Mean**	**Range**	**Pounds**	**Kilograms**	**Mean**	**Range**
				90	40	162	135–193
				95	43	171	143–204
				100	45	180	150–215
105	47	205	165–241	105	47	189	158–226
110	50	215	173–253	110	50	198	165–237
115	52	225	181–264	115	52	207	172–248
120	54	235	190–276	120	54	215	180–259
125	56	245	198–287	125	56	225	188–268
130	58	255	206–299	130	58	234	195–277
135	60	265	213–310	135	60	244	203–286
140	63	274	221–322	140	63	253	211–295
145	65	284	229–333	145	65	262	219–304
150	68	294	237–345	150	68	272	225–313

(continued)

Table A1.10 *Heart: men and women, weight in relation to body weight by sex* (continued)*

Men				**Women**			
Body weight		**Heart weight (g)**		**Body weight**		**Heart weight (g)**	
Pounds	**Kilograms**	**Mean**	**Range**	**Pounds**	**Kilograms**	**Mean**	**Range**
155	70	304	245–356	155	70	282	233–322
160	72	313	253–368	160	72	288	240–330
165	74	323	261–370	165	74	297	247–337
170	77	333	268–371	170	77	306	255–343
175	79	343	280–372	175	79	315	283–350
180	81	353	288–373	180	81	324	301–356
185	83	363	296–382	185	83	333	309–361
190	86	373	304–392	190	86	342	317–366
195	88	382	312–402	195	88	351	325–371
200	90	392	320–412				
Average weight of adult male heart: 294 g				Average weight of adult female heart: 250 g			

* Data from Smith HL. 1928. The relation of the weight of the heart to the weight of the body and of the weight of the heart to age. *Am Heart J* **4**:79–93.
NB There is considerable variation in published tables of heart weights: probably hypertensive hearts account for some of the upper ranges of 'normal'. However, the authoritative publication of Hangartner *et al.* gives considerably higher normal maximum weights. (Hangartner J, Marley N, Whitehead A, Thomas A, Davies M. 1985. The assessment of cardiac hypertrophy at autopsy. *Histopathology* **9**:1295–306.)

Table A1.11 *Heart: normal weight in relation to body length*

	Heart weight (g)			**Heart weight (g)**			**Heart weight (g)**	
	Males	**Females**		**Males**	**Females**		**Males**	**Females**
Body length (cm)	**$\sigma = \pm 40$**	**$\sigma = \pm 30$**	**Body length (cm)**	**$\sigma = \pm 40$**	**$\sigma = \pm 30$**	**Body length (cm)**	**$\sigma = \pm 40$**	**$\sigma = \pm 30$**
135	254	219	157	296	258	179	338	297
136	256	220	158	298	259	180	340	299
137	258	222	159	300	261	181	342	300
138	260	224	160	302	263	182	344	302
139	262	226	161	304	265	183	346	304
140	264	227	162	306	267	184	348	306
141	266	229	163	308	268	185	349	307
142	268	231	164	310	270	186	351	309
143	270	233	165	311	272	187	353	311
144	272	235	166	313	274	188	355	313
145	273	236	167	315	275	189	357	315
146	275	238	168	317	277	190	359	316
147	277	240	169	319	279	191	361	318
148	279	242	170	321	281	192	363	320
149	281	243	171	323	283	193	365	322
150	283	245	172	325	284	194	367	323
151	285	247	173	327	286	195	368	325
152	287	249	174	329	288	196	370	327
153	289	251	175	330	290	197	372	329
154	291	252	176	332	291	198	374	331
155	292	254	177	334	293	199	376	332
156	294	256	178	336	295	200	378	334

σ = standard deviation.
From Zeek PM. 1942. Heart weight. I. The weight of the normal heart. *Arch Pathol* **34**:820–32.
Copyright 1942, American Medical Association.
NB But see also Hangartner *et al.* 1985 (details above).

Table A1.12 *Brain: adults**

Age (years)	Brain weight (g)			
	Men		Women	
	Mean	Range	Mean	Range
17–19	1340	1170–1527	1242	1120–1420
20–29	1396	1158–1620	1234	1057–1565
30–39	1365	1075–1685	1233	1038–1440
40–49	1366	1069–1605	1240	995–1543
50–69	1375	1113–1665	1200	820–1477
60–69	1323	1018–1610	1178	920–1372
70–85	1279	1039–1485	1121	832–1370

* Data from Sunderman FW, Boerner F. 1949. *Normal values in clinical medicine.* W. B. Saunders Company, Philadelphia.

Table A1.13 *Brain: children**

Age	Body length (cm)	Brain weight (g)
Birth–3 days	49	335
3–7 days	49	358
1–3 wks	52	382
3–5 wks	52	413
5–7 wks	53	422
7–9 wks	55	489
3 mths	56	516
4 mths	59	540
5 mths	61	644
6 mths	62	660
7 mths	65	691
8 mths	65	714
9 mths	67	750
10 mths	69	809
11 mths	70	852
12 mths	73	925
14 mths	74	944
16 mths	77	1010
18 mths	78	1042
20 mths	79	1050
22 mths	82	1059
24 mths	84	1064
3 yrs	88	1141
4 yrs	99	1191
5 yrs	106	1237
6 yrs	109	1243
7 yrs	113	1263
8 yrs	119	1273
9 yrs	125	1275
10 yrs	130	1290
11 yrs	135	1320
12 yrs	139	1351

* Data from Sunderman FW, Boerner F. 1949. *Normal values in clinical medicine.* W. B. Saunders Company, Philadelphia.

SAMPLES AND CONTROLS NEEDED FOR DNA PROFILING

The essence of DNA profiling in forensic work is comparison between two samples. One is the 'test' sample from the living or dead subject (or objects with which he or she has been in contact, such as clothing) and the other the 'control', a somewhat inaccurate term for the samples obtained from a suspect, a group of suspects or a screening programme which may have hundreds or even thousands of items.

Since the beginning of the DNA analysis, significant advances have been made in methodology allowing forensic identification of individuals from minute amounts of DNA. Microgram amounts of relatively undegraded DNA is required for multi-locus typing of the restriction fragment length polymorphism (RFLP) analysis and hundreds of nanograms for single-locus typing. Polymorphic DNA sequences can be detected from the root of shed or freshly plucked single human hairs using the polymerase chain reaction (PCR). Mitochondrial DNA (mtDNA) has been detected even in a sample from a single hair shaft.

Blood

As red cells have no nuclear DNA, sufficient blood must be obtained to extract DNA from the much sparser leucocytes. At least 1 ml and preferably 5 ml are taken into an EDTA tube, which extracts metallic ions and not only prevents clotting, but inhibits enzymes in blood or micro-organisms, which may break down DNA during storage.

The blood sample, in a plastic (not glass) tube, should be frozen solid in a deep-freeze or the ice-making compartment of an ordinary refrigerator. As frozen blood is useless for some other forensic investigations, the DNA sample should be clearly marked as such. Other samples, for grouping and many other serological and toxicological tests, must be taken and stored at only 4°C.

If a blood sample is to be taken directly to the laboratory for DNA profiling, then freezing is not necessary, but wherever there is delay, either freezing or, at second best, effective cooling should be carried out.

Most of the laboratories are using nowadays FTA paper for the collection of blood samples. FTA paper is an absorbent cellulose-based paper that contains chemical substances to protect DNA molecules from nuclease degradation and preserve the paper from bacterial growth (Seah and Burgoyne 2000). As a result, DNA on FTA paper is stable at room temperature over a period of several years. The use of FTA paper simply involves adding a spot of blood to the paper and allowing the stain to dry.

Blood stains, as opposed to liquid blood, should either be sent intact on surfaces, kept as cool as possible before and during transit to the laboratory – or rubbed with a cotton-wool swab moistened with water. This swab is then air-dried without heat and frozen. Although not required for DNA testing, always provide the laboratory with control swabs for conventional blood grouping, including swabs rubbed on an area of the fabric away from obvious stains, as well as an unused swab.

Dried blood stains on hard surfaces can be scraped off with a scalpel into a small plastic container and sent as they are, kept as cool as possible.

Buccal cells

A disposable toothbrush may also be used for collecting buccal cells in a non-threatening manner. This method can be very helpful when samples need to be collected from children and this is the method actually used for most of paternity testing labs. After the buccal cells have been collected by gently rubbing a wet toothbrush across the buccal surface, the brush can be tapped onto the surface of FTA paper for sample storage and preservation.

Seminal and vaginal fluids

Swabs from vagina, rectum, mouth, etc., should be air-dried as quickly as possible, but not heated. They should then be stored in deep-freeze, unless sent straight to the forensic science laboratory. Liquid semen found in the vagina or elsewhere should be recovered with a fine pipette, placed in a small plain tube and frozen solid.

Seminal stains on small items of fabric or any other small objects may be frozen or kept as cool as possible during transit. Bulk clothing cannot be frozen and should merely be kept cool, transit to the laboratory being made as soon as possible, using strong sterilized paper bags, not impervious polythene, which encourages mould formation. Alternatively, damp swabs may be taken of suspect stains, which are then dried and frozen. As with blood, suspect dried seminal stains on hard surfaces may be scraped off and transmitted dry to the laboratory.

Mouth swabs may be taken either to seek semen in suspected oral intercourse (though positive recoveries are very rare) or to obtain buccal mucosa for DNA identification. In the latter case, the yield is small, so at least three to four swabs must be rubbed hard against the inside of the cheek – or the mouth lining scraped with an instrument and then smeared onto a swab. All such swabs should be frozen in the usual manner.

Hairs – head, pubic, etc.

Collection of hairs – head, pubic, eyebrow, axillary – from the victim or at the scene of crime is extremely important as a 2 cm piece of single hair is actually sufficient for mtDNA analysis. It is of paramount importance to avoid cross-contamination and to submit the hairs in sterilized paper bags, well identified.

Autopsy tissue samples

At least 0.5 g of tissue should be cut from the parenchyma of an organ and placed in a small plastic tube with no fixative or preservative. This should be frozen solid. Spleen is said to be one of the best organs for DNA recovery, though liver, muscle, kidney and brain may also be used. The fresher the tissue the better, and totally putrefied material was formerly of little use, as the nuclear chromatin was degraded. However, rapidly developing new techniques are allowing the recovery of recognizable DNA from old material.

For identification of skeletal remains using DNA technology, a well-preserved tooth is the tissue of election. In addition, long bones (femur) or ribs can also be used.

Other general remarks

The sensitivity of DNA technology is changing the strategy of sample collection. Very sensitive low-copy-number DNA methods are being developed allowing the detection of subnanogram amounts of DNA. For this reason, it is extremely important to avoid cross-contamination from the personnel collecting the samples.

DNA can even be obtained from personal objects, fingerprints, sweat and of course from saliva recovered from bite marks.

Finally, as for other type of forensic evidence, the chain of custody must be extremely well-preserved.

FURTHER READING

Badir B, Knight B. 1987. Fluorescence microscopy in the detection of early myocardial infarction. *Forensic Sci Int* **34**:99–102.

APPENDIX 2

Council of Europe Committee of Ministers Recommendation No. R (99) 3

- Recommendation No. R (99) 3 of the Committee of Ministers to Member States on the harmonisation of medico-legal autopsy rules 610
- Appendix to Recommendation No. R (99) 3 616

RECOMMENDATION NO. R (99) 3 OF THE COMMITTEE OF MINISTERS TO MEMBER STATES ON THE HARMONISATION OF MEDICO-LEGAL AUTOPSY RULES[1]

(*Adopted by the Committee of Ministers on 2 February 1999 at the 658th meeting of the Ministers' Deputies*)

The Committee of Ministers, under the terms of Article 15.*b* of the Statute of the Council of Europe,

Considering that the aim of the Council of Europe is to achieve a greater unity between its members;

Having regard to the principles laid down in the Convention for the Protection of Human Rights and Fundamental Freedoms and, in particular, the prohibition of torture or inhuman or degrading treatment or punishment, and the right to life;

Conscious that it is normal practice for autopsies to be carried out in all Council of Europe member States to establish the cause and manner of death for medico-legal or other reasons or to establish the identity of the deceased;

Considering the importance of compensation for victims and families in criminal and civil proceedings;

Underlining the need for investigation, description, photographic documentation and sampling during medico-legal autopsy to follow primarily medical and scientific principles and simultaneously consider legal requirements and procedures;

Conscious that the increasing mobility of the population throughout Europe and the world, as well as the increasing internationalisation of judicial proceedings, require the adoption of uniform guidelines on the way autopsies are to be carried out and on the way autopsy reports are to be established;

Considering the Council of Europe Agreement on the Transfer of Corpses (European Treaty Series No. 80) and having regard to the difficulties often experienced by the receiving country when a dead body is repatriated from one member state to another;

Aware of the importance of proper autopsy procedures, in particular with a view to bringing to light illegal executions, and murders perpetrated by authoritarian regimes;

---

[1] When this recommendation was adopted, the Representatives of Denmark and the Netherlands, in application of Article 10.2*c* of the Rules of Procedure for the meeting of the Ministers' Deputies, reserved the right of their Governments to comply or not with paragraph 2 (scope of the recommendation) of the present recommendation.

When this recommendation was adopted, the Representative of Germany, in application of Article 10.2*c* of the Rules of Procedure for the meeting of the Ministers' Deputies, reserved the right of his Government to comply or not with paragraph 2 *f* and *h* of the present recommendation.

Underlining the need to protect the independence and impartiality of medico-legal experts, as well as to make available the necessary legal and technical facilities for them to carry out their duties in an appropriate way and to promote their training;

Considering the importance of national quality control systems to ensure the proper performance of medico-legal autopsies;

Underlining the need to strengthen international co-operation with a view to the progressive harmonisation of medico-legal autopsy procedures at a European level;

Having regard to Recommendation 1159 (1991) on the harmonisation of autopsy rules adopted, at its 43rd Ordinary Session, by the Parliamentary Assembly of the Council of Europe;

Having regard to the Model Autopsy Protocol of the United Nations, endorsed by the General Assembly of the United Nations in 1991;

Taking into account the 'guide on disaster victim identification' adopted by the International Criminal Police Organisation (Interpol) General Assembly in 1997,

1 Recommends the governments of member states:
  (i) to adopt as their internal standards the principles and rules contained in this recommendation;
  (ii) to take or reinforce, as the case may be, all appropriate measures with a view to the progressive implementation of the principles and rules contained in this recommendation;
  (iii) to set up a quality assurance programme to ensure the proper implementation of the principles and rules contained in this recommendation.

2 Invites the governments of member states to inform the Secretary General of the Council of Europe upon his or her request of the measures taken to follow up the principles and rules contained in this recommendation.

PRINCIPLES AND RULES RELATING TO MEDICO-LEGAL AUTOPSY PROCEDURES

Scope of the recommendation

1 In cases where death may be due to unnatural causes, the competent authority, accompanied by one or more medico-legal experts, should where appropriate investigate the scene, examine the body and decide whether an autopsy should be carried out.

2 Autopsies should be carried out in all obvious or suspected unnatural death, even where there is a delay between causative events and death, in particular:
  a homicide or suspected homicide;
  b sudden, unexpected death, including sudden infant death;
  c violation of human rights such as suspicion of torture or any other form of ill treatment;
  d suicide or suspected suicide;
  e suspected medical malpractice;
  f accidents, whether transportational, occupational or domestic;
  g occupational disease and hazards;
  h technological or environmental disasters;
  i death in custody or death associated with police or military activities;
  j unidentified or skeletalised bodies.

3 Medico-legal experts must exercise their functions with total independence and impartiality. They should not be subject to any form of pressure and they should be objective in the exercise of their functions, in particular in the presentation of their results and conclusions.

Principle I – Scene investigation

A *General principles*
  1 In case of obvious or suspected unnatural death, the physician who first attended the dead body should report to the competent authorities, the latter deciding whether an examination should be carried out by a qualified medico-legal expert or by a physician familiar with medico-legal examination.
  2 Particularly in cases of homicide or suspicious death, medico-legal experts should be informed without delay and, where appropriate, go immediately to the place where the body is found and have immediate access there. In this respect, there should be an adequate structure of co-ordination among all persons involved and, in particular, among judicial bodies, medico-legal experts and police.

B *Examination of the body*
  1 Role of the police
  The following tasks, among others, should be carried out by police officers:
    a record the identities of all persons at the scene;
    b photograph the body as it is found;
    c make sure that all relevant artifacts are noted, and that all exhibits, such as weapons and projectiles, are seized for further examination;
    d in agreement with the medico-legal expert, obtain identification of the body and other pertinent information from scene witnesses, including those who last saw the decedent alive, where available;

- **e** protect the deceased's hands and head with paper bags, under the control of the medico-legal expert;
- **f** preserve the integrity of the scene and surroundings;

2 Role of the medico-legal expert
The medico-legal expert should without delay:

- **a** be informed of all relevant circumstances relating to the death;
- **b** ensure that photographs of the body are properly taken;
- **c** record the body position and its relation to the state of the clothing and to the distribution pattern of rigor mortis and hypostasis, as well as the state of *post-mortem* decomposition;
- **d** examine and record the distribution and pattern of any blood stains on the body and at the scene, as well as other biological evidence;
- **e** proceed to a preliminary examination of the body;
- **f** except where the body is decomposed or skeletal, note the ambient temperature and deep-rectal temperature of the body, and estimate the time of death by recording the degree, location and fixation of rigor mortis and hypostasis, as well as other findings;
- **g** make sure that the body is transported and stored in a secure and refrigerated location in an undisturbed state.

Principle II – Autopsy physicians

Medico-legal autopsies should be performed, whenever possible, by two physicians, of whom at least one should be qualified in forensic pathology.

Principle III – Identification

In order to ensure that proper identification of the body is carried out in accordance with the disaster victim identification guide adopted by the General Assembly of Interpol in 1997, the following criteria should be considered: visual recognition, personal effects, physical characteristics, dental examination, anthropological identification, fingerprints and genetic identification.

1. Visual identification
   Visual identification of a body should be carried out by relatives or persons who knew and have recently seen the decedent.
2. Personal effects
   A description of clothing, jewellery and pocket contents should be recorded. These may assist correct identification.
3. Physical characteristics
   Physical characteristic should be recorded through an external and an internal examination.
4. Dental examination
   Where appropriate, the examination of teeth and jaws should be carried out by a dentist with medico-legal experience.
5. Anthropological identification
   Whenever human material is skeletised or in an advanced stage of decomposition, an anthropological identification should be carried out, if necessary.
6. Fingerprints
   Where appropriate, fingerprints should be taken by police officers. A close collaboration should exist between all experts involved.
7. Genetic identification
   Where appropriate, genetic identification should be carried out by an expert in forensic genetics.

It is appropriate to take biological samples from the deceased in order to assist genetic identification. Measures should be taken in order to avoid contamination and guarantee appropriate storage of biological samples.

Principle IV – General considerations

1. Medico-legal autopsies and all related measures must be carried out in a manner consistent with medical ethics and respecting the dignity of the deceased.
2. Where appropriate, the closest relatives should be given an opportunity to see the corpse.
3. Before beginning the autopsy, the following minimum rules should be applied:
   - **a** record the date, time and place of autopsy;
   - **b** record the name(s) of the medico-legal expert(s), assistant(s) and all other persons present at the autopsy with indication as to the position and role of each one in the autopsy;
   - **c** take colour photographs or video, where appropriate, of all relevant findings and of the dressed and undressed body;
   - **d** undress the body, examine and record clothing and jewellery, verify the correspondence between injuries on the body and clothing;
   - **e** where appropriate, take X-rays, particularly in cases of suspected child abuse, and for identification and location of foreign objects.
4. Where appropriate, before beginning the autopsy, body orifices should be appropriately swabbed for the recovery and identification of biological trace evidence.

5 If the decedent was hospitalised prior to death, admission blood specimens and any X-rays should be obtained as well as hospital records.

Principle V – Autopsy procedures

I EXTERNAL EXAMINATION

1 The examination of the clothing is an essential part of the external examination and all findings therein are to be clearly described. This is especially important in those cases where the clothing has been damaged or soiled: each area of recent damage must be described fully and relevant findings are to be related to the site of injuries on the corpse. Discrepancies in such findings are also to be described.

2 The description of the body following an external examination must include:

- **a** age, sex, build, height, ethnic group and weight, nutritional state, skin colour and special characteristics (such as scars, tattoos or amputations);
- **b** post-mortem changes, including details relating to rigor and post-mortem hypostasis – distribution, intensity, colour and reversibility – and putrefaction and environmentally induced changes;
- **c** findings on a primary external inspection and description which, if required, include sampling of stains and other trace evidence on the body surface and a reinspection after removal and cleaning of the body;
- **d** inspection of the skin of the posterior surfaces of the corpse;
- **e** description and careful investigation of the head and the facial orifices includes: colour, length, density and distribution of hair (and beard); nasal skeleton; oral mucosa, dentition and tongue; ears, retro-auricular areas and external meati; eyes: colour of irises and sclerae, regularity and appearance of pupils, sclerae, conjunctivae; skin (presence and absence of petechiae to be described); if fluids have been evacuated from facial orifices, their colour and odour;
- **f** neck: checking for excessive mobility, presence and absence of abrasions, other marks and bruising (including petechiae) over the entire circumference of the neck;
- **g** thorax: shape and stability; breasts; aspect, nipples and pigmentation;
- **h** abdomen: external bulging, pigmentation, scars, abnormalities and bruising;
- **i** anus and genitals;
- **j** extremities: shape and abnormal mobility, abnormalities; injection marks and scars; palmar surfaces, finger and toe nails;
- **k** material findings under fingernails.

3 All injuries, including abrasions, bruises, lacerations and other marks have to be described by shape, exact measurement, direction, edges, angles and location relative to anatomical landmarks. Photographs should be taken. Bite marks shall be swabbed, and casts made where necessary.

4 Signs of vital reaction around wounds, foreign particles inside wounds and in their surroundings and secondary reactions, such as discolouration, healing and infections must also be described.

5 The investigation of cutaneous and sub-cutaneous bruising may require local skin incision.

6 Where appropriate, specimens from wounds must be removed for further investigations, such as histology and histochemistry.

7 All signs of recent or old medical and surgical intervention and resuscitation must be described. Medical devices must not be removed from the body before the intervention of the medico-legal expert.

8 A decision has to be taken at this stage as to the strategies of investigation and the necessity of documentation by X-rays and other imaging procedures.

II INTERNAL EXAMINATION

A General

1 All relevant artifacts produced by the dissection and from sampling procedures, must be documented.

2 All three body cavities – head, thorax and abdomen – must be opened layer by layer. Where appropriate, the vertebral canal and joint cavities should be examined.

3 Examination and description of body cavities include: an examination for the presence of gas (pneumothorax), measurement of volume of fluids and blood, appearance of internal surfaces, intactness of anatomical boundaries, external appearance of organs and their location; adhesion and cavity obliterations, injuries and haemorrhage.

4 The demonstration and dissection of the soft tissues and musculature of the neck have to be components of all medico-legal autopsies (see the paragraph concerning special procedures).

5 All organs must be examined and sliced following established guidelines of pathological anatomy. This includes opening of all relevant vessels, for example, intracranial arteries, sinuses, carotid arteries, coronary arteries, pulmonary arteries and veins, aorta and vessels of the abdominal organs, femoral arteries and lower limb veins. Relevant ducts have to be dissected, for example, central and peripheral airways, biliary ducts and ureters. All hollow organs have to be opened and their content described by colour, viscosity, volume (samples should be retained, where appropriate). All organs have to be sliced and the appearance of the cut surface described. If injuries are present, the dissection procedure may have to vary from the normal one: this should be appropriately described and documented.

6 All internal lesions and injuries must be precisely described by size and location. Injury tracks must be described in order to include their direction as regards the organ anatomy.

7 The weight of all major organs must be recorded.

B Detailed

1 *Head*

- **a** Before opening the skull, the periosteum must be scraped off in order to display or exclude any fractures.
- **b** The head examination procedure must allow the inspection and description of the scalp, external and internal surfaces of the skull and of the temporal muscles.
- **c** The thickness and appearances of the skull and sutures, the appearances of the meninges, the cerebrospinal fluid (CSF), the wall structure and contents of cerebral arteries and sinuses must be described. The description of the bones must also include an examination of their intactness, including the connection between the skull and the first two vertebrae.
- **d** In obvious or suspected head injury (for example, if a detailed examination is required or if autolysis or putrefaction is present) fixation of the whole brain is recommended before its dissection.
- **e** Middle ears must be always opened and nasal sinuses where indicated.
- **f** The soft tissue and skeleton of the face is dissected only in relevant cases, using a cosmetically acceptable technique.

2 *Thorax and neck*

The opening of the thorax must be performed using a technique which allows the demonstration of the presence of pneumothorax and the inspection of the thorax walls, including the postero-lateral regions. *In situ* dissection of the neck must display the details of its anatomy.

3 *Abdomen*

The opening procedure of the abdomen must allow an accurate examination of all layers of the walls, including the postero-lateral regions. *In situ* dissection is necessary in certain cases, particularly for the demonstration of injury tracks and evacuation of fluids. Dissection of organs should observe anatomical continuity of systems, where possible. The whole intestine must be dissected and its contents described.

4 *Skeleton*

- **a** The examination of the thoracic cage, the spine and the pelvis must be part of the autopsy procedure.
- **b** Where appropriate traumatic deaths need a precise dissection of the extremities, possibly complemented by X-ray examination.

5 *Special procedures*

- **a** If there is any suspicion of neck trauma, the brain and thoracic organs are to be removed prior to the dissection of the neck, to enable detailed dissection to take place in a bloodless field.
- **b** If there is a suspicion of air embolism, pre-autopsy radiology of the thorax must be performed. The first stage of the autopsy in such a case must be a careful partial opening of the thorax and dislocation of the lower three-quarters of the sternum with the subsequent opening of the heart under water, allowing the measurement and sampling of escaping air or gas.
- **c** For the demonstration of particular injury patterns, deviation from the normal procedure of dissection has to be accepted, provided that such procedures are specifically described in the autopsy report.
- **d** The dissection in traumatic deaths must include a full exposure of the soft tissues and musculature on the back of the body. The same procedure must be applied to the extremities (so called ‘peel-off’ procedure).
- **e** In suspected or overt sexual assaults, the sexual organs are to be removed *en bloc* together with the external genitalia, rectum and anus, before they are dissected. Relevant swabs of orifices and cavities must be taken prior to this procedure.

6 *Sampling*

The scope of the sampling procedure is to be case-dependent. However, the following minimum rules should be applied:

- **a** in all autopsies, the basic sampling scheme includes specimens from the main organs for histology and peripheral blood sampling (such as for alcohol and drug analyses and genetic identification), urine and gastric contents. All blood samples must be peripheral blood and not heart or thoracic;
- **b** if the cause of death cannot be established with the necessary degree of certainty, sampling includes

additional specimens and fluids for metabolic studies and thorough toxicology. This includes blood, vitreous humour, CSF, bile, hair samples and further relevant tissues;

c if death is related to physical violence, sampling includes the injuries, for example to determine wound age and any foreign materials in the wounds;

d if reconstructions are desirable, the removal of bones and osseous compartments may become necessary;

e if identification is the predominant aim, the removal of jaws and other bones may be necessary;

f if strangulation or the application of physical force to the neck is suspected or diagnosed, the entire neck structures, musculature and neurovascular bundles must be preserved for histology. The hyoid bone and the laryngeal cartilages must be dissected very carefully;

g biological samples must be collected in tightly closed jars, properly preserved and placed under seal and transported to the laboratory in perfect safety;

h certain specimens and fluids need to be sampled in a special way and analysed without delay.

7 *Release of the body*

After a medico-legal autopsy has been carried out, medico-legal experts should ensure that the body is returned in a dignified condition.

Principle VI – Autopsy report

1 The autopsy report is as important as the autopsy itself, as the latter is of little value if the findings and opinions of the medico-legal expert are not communicated in a clear, accurate and permanent document. The autopsy report should be an integral part of the autopsy procedure and be drafted carefully.

2 The report should therefore be:

a full, detailed, comprehensive and objective;

b clear and comprehensible not only to other doctors, but also to non-medical readers;

c written in a logical sequence, well-structured and easy to refer to in various sections of the report;

d be in a legible and permanent form, with hard paper copy even if it is retained in electronic storage;

e be written in a discursive ‘essay’ style;

3 When drafting an autopsy report, the following minimum content should be included:

a legal preface to fulfil statutory requirements, if needed;

b serial number, computer retrieval coding and International Classification of Disease Code (ICD) code;

c full personal details of deceased (including name, age, sex, address and occupation) unless unidentified;

d date, place and time of death, where known;

e date, place and time of autopsy;

f name, qualifications and status of medico-legal expert(s);

g persons present at the autopsy and their function;

h name of the authority commissioning the autopsy;

i person(s) identifying the body to the medico-legal expert;

j name and address of the medical attendant of the deceased;

k a synopsis of the history and circumstances of the death, as given to the medico-legal expert by the police, judges, relatives or other persons, as well as information contained in the file, where available;

l description of the scene of death, if attended by the medico-legal expert; reference should be made to the provisions contained in Principle I above;

m external examination; reference should be made to the provisions of Principle V above;

n internal examination by anatomic systems, together with a comment on every organ. Reference should be made to the provisions of Principle V above;

o a list of all samples retained for toxicology, genetic identification, histology, microbiology and other investigations should be included; all such specimens should be identified and attested by the medico-legal expert according to the legal system of the state concerned, for continuity of evidence;

p results of ancillary investigations, such as radiology, odontology, entomology and anthropology should be included, when such results are available;

q one of the most important parts of the autopsy report is the evaluation of the significance of the accumulated results by the medico-legal expert. After termination of the autopsy, evaluation is usually provisional because later findings and later knowledge of other circumstantial facts can necessitate alteration and modification. Medico-legal experts must interpret the overall findings so that the maximum information and opinion can be offered. Also questions that have not been raised by the competent authority must be addressed if they could be of significance;

r based on the final interpretation, the cause of death (in the International Classification of Disease should be given. Where several alternatives for the cause of death exist and the facts do not allow a differentiation between them, the medico-legal expert should describe the alternatives and, if possible, rank them in order of probability. If this is not possible, then the cause of death should be certified as 'Unascertained';

s the report should be finally checked, dated and signed by the medico-legal expert(s).

4 The date of the autopsy and the date of the provisional report should never be more than a day or two apart. The date of the autopsy and the date of the final report should be as close together as possible.

APPENDIX TO RECOMMENDATION NO. R (99) 3

SPECIFIC PROCEDURES (SELECTED EXAMPLES)

1 *Constriction of neck (hanging, manual and ligature strangulation)*

The examination of the scene where the body was found is extremely important: for example the presence of a chair or similar platform; fastening of the strangulation device; technique of tying of the knot; adhesive taping of hands and objects for trace evidence:

- Strangulation marks: depth, width, intermediate rings, direction, suspension point, raised ridges of skin, zones of hyperaemia, presence of duplicate strangulation marks; further specific neck injuries: dried excoriations due to slippage of the implement, marks due to textile weave pattern and structure, distribution of petechiae in the skin, bruising, scratch marks, blisters in the strangulation mark.
- Bleeding from facial orifices. Differences in widths of the pupils, localization of hypostasis, presence and distribution of congestion.
- Injuries due to convulsions, defensive injuries, injuries due to being held forcibly.

Dissection of the soft tissues, of the musculature and of the organs of the neck in a bloodless field is essential.

2 *Drowning/Immersion*

Note carefully the following findings: foam at the mouth, cutis anserina, maceration, mud and algae, lesions due to water animals, injuries due to surroundings (for example rocks and ships), loss of nails, skin, localization of livor mortis.

Technique: sampling of gastric contents, precise description of the lungs (weight, measurement, extent of emphysema), sampling, lung fluid, liver and other tissues, for the possible demonstration of diatoms and other contaminants.

If required, sampling of drowning medium (for example river, bath water) should be carried out.

3 *Sexually motivated murder*

The inspection and documentation of the scene of crime, e.g. relative to the injury pattern, is especially important. All injuries must be photographed together with a scale. If required, the body surfaces must be investigated under UV light and taped. Search for and sampling of foreign biological material must include pubic hairs and secretions on the body surface as for instance originating from bites. Such material must be preserved carefully for DNA investigation and protected against contamination. 'En bloc' dissection of the genital organs is strongly recommended. It is also necessary to proceed to the careful removal and sampling of material under the fingernails and control hairs.

4 *Death from child abuse and neglect*

State of nutrition and general care, thorough description and documentation of external injuries and scars, thorough examination for bone fractures (X-ray), must be evaluated.

Consider the removal of a variety of tissues: for example all injuries, regional lymph nodes in malnutrition, endocrine organs, immuno-competent tissues, specimens from different parts of the intestine.

5 *Infanticide/still-birth*

Special techniques of dissection are necessary to expose the falx cerebri and the tentorium cerebelli; describe the site of caput succedaneum; remove all fractures 'en bloc'; investigate all bone centres of ossification (size and presence). Special care is to be applied to the thoracic organs: degree of inflation of the lungs, flotation test 'en bloc' and 'en detail'. However, the limitations of the flotation test must be appreciated. All malformations must be described. As regards abdominal organs, gas content of the intestine must be investigated. The umbilical cord and the placenta must be subject to morphological and histological examination.

6 *Sudden death*

A subdivision into three main categories relative to the further strategy after gross examination is useful:

a findings that obviously explain the sudden occurrence of death (for example haemopericardium, aortic rupture). Cases belonging to this category can usually be regarded as sufficiently solved;

b findings that could explain the death but allow other explanations. Cases belonging to this category necessitate the exclusion of , for example,. poisoning and possibly histological proof of recent or chronic alterations relative to the cause of death;

c findings are either nil/minimal or do not explain the occurrence of death. Cases belonging to this category will usually require extensive further investigations.

This is especially so with sudden infant death cases. In such cases a more comprehensive investigative scheme is essential.

7 *Shooting fatalities*

The following should be carried out:

- extensive account on the scene of the incident, of weapons involved, of types of bullets, of sites of 'environmental' damage, of cartridge cases and of relative positions of persons involved;
- thorough examination of the clothing and description of relevant damage and careful sampling;
- thorough investigation and documentation of any blood (splashes) on the body surfaces (including clothing and hands);
- precise description of bullet entry and exit wounds relative to anatomical landmarks and distances from the soles of the feet and bullet tracks within the body;
- description of any impression marks of the muzzle;
- excision of uncleaned skin specimens surrounding entry and exit wounds;
- X-ray before and/or during autopsy (where necessary);
- determination of bullet tracks and their direction(s);
- final determination of direction(s) of fire, of the succession of shots, of intra-vital occurrence, of the victim's position (s).

8 *Death caused by explosive devices*

a As well as evaluating the cause of death, autopsy is essential to assist in reconstructing the nature of the explosion and identifying the type and maker of the explosive device, especially in aircraft sabotage or other terrorist actions.

b Full X-ray of the body must be made to detect and localise any metallic objects, such as detonator components, which may lead to the identification of the explosive device.

c The pattern of injury may indicate that the dead person was a perpetrator of the explosion, for example maximum injury in the lower abdominal region suggests that he or she carried the device on his or her lap during a premature explosion.

d At autopsy, all foreign objects in the tissues, identified on X-rays, must be carefully preserved for forensic examination.

e Samples of tissues, clothing, etc., must be retained for chemical analysis to identify the type of explosive.

9 *Blunt and/or sharp force injuries*

The following should be carried out:

- examination of the weapons or objects that are possibly involved (especially their dimensions);
- extensive examination and inspection of clothing (including damage, stains);
- careful dissection and description of all tracks (layer by layer) including their dimensions and weapon-related traces, signs of vitality.

10 *Fire Deaths*

The following should be carried out:

- examination of remains of clothing, - specific types and shapes of skin combustions;
- search for heat-related alterations and peculiarities;
- demonstration/exclusion of fire accelerants.;
- search for signs of vitality: carbon monoxide, HCN, soot inhalation, skin lesions.

11 *Suspicion of intoxication (General Outlines)*

11.1 Where anatomical findings do not reveal a cause of death and/or there is vague suspicion of poisoning, basic sampling should include peripheral blood, urine, stomach contents, bile, liver and kidney.

11.2 If specific suspicion arises, sampling should be group-related as follows:

- hypnotics, sedatives, psycho-active drugs, cardiac drugs and analgesics, pesticides: as aforementioned under (11.1);
- drugs of abuse: as aforementioned under (11.1) and additionally cerebrospinal fluid, brain tissue, injection marks, hairs;
- volatile fat-soluble substances such as fire accelerant and solvents: as aforementioned under (11.1) and in addition: blood from left ventricle, brain tissue, subcutaneous fat tissue, lung tissue, clothing;
- nutritional intoxication: as aforementioned under (11.1) and in addition: intestinal contents, if possible taken from 3 different sites;
- suspicion of chronic intoxication (heavy metals, drugs, pesticides etc.) as aforementioned under (11.1) and in addition: hairs (tufts), bones, fat tissue, intestinal contents.

12 *Decomposed bodies*

The presence of decomposition does not remove the need for a full autopsy.

Radiological examination will exclude bony injury, the presence of foreign bodies, for example bullets.

Toxicological studies (particularly estimation of alcohol concentrations) should be carried out but interpreted with great caution.

Index

References to autopsy, death and homicide are limited in the index, as these are major subject of the book. Readers are advised to seek more specific references. *vs* denotes differentiation or comparison.

- abdomen
  - anatomy, forensic 229
  - bruising, in child abuse 463
  - compression, traumatic 'asphyxia' in 363
  - examination in air embolism 347, 435–6
  - exposure/incisions at autopsy 17
  - internal examination at autopsy 18
  - kicking injuries 230
  - in neglect/starvation 413, 414
  - surface relations of organs 229
- abdominal injuries 229–33
  - child abuse 230, 463, 472
  - closed/blunt 229
  - complications 233
  - foreign bodies 232–3
  - haemorrhage 230, 232, 233
  - illegal abortion 433
  - open/penetrating 229
  - suicidal knife wounds 238
  - in vehicular accidents 286
    - drivers 283–4
    - pedestrians 294
- abdominal organs 229
  - examination at autopsy 18
  - removal at autopsy 21–2
- abdominal wall, bruising 229–30
- abortion
  - autopsy 435–6
    - external examination 435
    - internal findings 435–6
  - criminal/illegal 431, 432
    - air embolism 346, 432–3, 434, 435
    - causes of death 432–5
    - cervix dilatation 432, 433
    - dangers 435
    - drugs/chemicals 434–5
    - infections 433–4
    - infections/bleeding 432
    - instrumental interference 432
    - intrauterine infection 433–4
    - physical violence 433
    - syringe aspiration 433
  - deaths associated 431–5
  - septic 57, 432
  - skin colour 346
  - sudden death due to 517
  - therapeutic 346, 431
- abrasion collar 263–4, 268–9
- abrasions 137, 138–43
  - in bruising *vs* hypostasis 59
  - brush (tangential) 139, 140
    - face 178
    - motorcyclists 290
    - scalp 175
  - crushing 139–40
  - defence wounds 165–6
  - definitions and lay terms 137, 138
  - fingernail *see* fingernail, abrasions
  - footmarks 144, 150
  - impact, of scalp 175
  - intradermal bruising with 140, 141, 142, 146
  - linear (grazes) 138, 139
  - neck
    - infanticide 441, 443
    - strangulation 140, 372
  - patterned 141–3, 144
    - child abuse 475
    - facial 178
    - firearms muzzle 143
    - pedestrians 294, 295
    - tyres, vehicular injuries 142, 143, 294, 296
  - post-mortem 139, 143, 149–50
  - putrefied corpse 39
  - scalp 175
  - sexual offences 422
  - strangulation marks 141, 148, 372–3
- acceleration injuries 205, 281, 291
- accidents *see* trauma; vehicular accidents
- acetabulum, sex differentiation 111
- acetaminophen (paracetamol) poisoning 572–3
- acetylsalicylic acid *see* aspirin poisoning
- acid fuchsin (AF) staining 500
- acid phosphatase 428
- acquired immunodeficiency syndrome (AIDS) 579
- acridine-orange fluorescent stain 601
- actin 62

Index

actomyosin 62
acute tubular necrosis 345
ADAM (Ecstasy) 581
adenosine diphosphate (ADP) 62
adenosine triphosphate (ATP) 61, 62
adipocere
  chemistry/characteristics 70
  decomposition forms mixed with 72
  definition 64, 70
  formation 68, 70–2
    bacteria 71
    in drowning 406
    importance 71–2
    timing 71
adipose tissue
  decomposition *see* adipocere
  loss, in neglect/starvation 414
‘adrenal apoplexy’ 349
adrenal glands, autopsy 27, 349
adrenal haemorrhage 349, 513
adrenaline:noradrenaline ratio 419
β_2-adrenergic antagonists 515
adult respiratory distress syndrome 345
African features 122, 123
age
  hypothermia relationship 415
  infant, sudden infant death syndrome and 452
age estimation
  by dentition 534–5
  external examination at autopsy 11
  eyes 104
  infants 440, 443, 448–9
  non-skeletalized bodies 104–5
  skeletal remains 116–22
    adult 118
    child/young adult 118
    factors affecting 118
    fetus/young infant 117–18, 449
    later years 118
    pubic symphysis 118–20
    radiography/radiology 117, 121
    skull sutures 120–2
    sternal rib methods 120
  teeth 104–5, 534–5
agrochemical poisoning 566–9
  organophosphorus pesticides 567–8
  paraquat 345, 566–7
AIDS 579
  see also HIV infection
air
  in diving 488
  insufflation in illegal abortion 432–3, 435
  movement, effect on cooling curve 81
airbags 289
aircraft
  carbon monoxide poisoning 560–1
  crashes
    identification of dead from dentition 532–3
    necessities in planning 42–3
  pilots 296, 508
air embolism 346–8
  air volume for 346–7
  arterial 346
  aspirometer 347, 348
  autopsy in 347–8, 435–6
  barotrauma 346, 488, 489
  in cerebral veins, myth 347, 435–6, 490
  in cut throats 237, 346
  divers 488
  gas chromatography 347, 348
  homicide 346
  illegal abortion 346, 432–3, 434
    autopsy findings 435
  legal termination of pregnancy 432
  mechanism of death 346, 347
  medico-legal aspects 346
  radiograph 347
  transfusion/infusion/surgical accidents 346
air guns 271
  injuries 271–2
air-rifles, injuries 271–2
airways
  damage, resuscitation artefacts 41
  froth in, in drowning 402–3
  gastric contents in 362–3
  obstruction
    anaesthetic-related deaths 484–5
    choking 361–3
    gagging 360–1
    infections 361
    pressure on neck causing 368
  occlusion, fatal pressure on neck 368, 369
  thermal damage 319–20
Al-Alousi’s ‘temperature ratio’ method 83, 87
alcohol 552–9
  absorption 552, 553–4
    drugs affecting 554
    food effect 553, 554
  behavioural effect 552, 556–7
  binge drinkers 554
  blood-alcohol curve (BAC) 554
  blood levels 19–20, 553
    ante-mortem *vs* post-mortem 546–7
    calculation from drinks 556
    deaths in custody 307
    peripheral vein blood 547
    road traffic deaths 296, 557
    sample collection/containers 20, 545
    sample preservation 545, 546
    women 552
  breath 555
  carbon monoxide poisoning and 557, 560, 561
  cardiomyopathy associated 558
  choking association 363

alcohol (*contd.*)
  chronic abuse 552, 557–8
  concentrations of drinks 553–4, 555–6
  deaths from exposure 419
  deaths in custody 307
  as depressant 552–3
  diffusion (post-mortem) and sampling concerns 546–7
  driving and 554
    legal limit in UK 555
    urine levels 555
  elimination/excretion 554–5
  heat regulation changes 553
  hypothermia and 553
  hypoxia 552
  metabolism 554
  mode of action 552–3
  modes of death 557–8
    acute alcoholism 307, 557
    chronic alcoholism 557–8
  physiological effects 552–3, 556–7
  putrefactive production 545–6
  spontaneous combustion association 323
  subarachnoid haemorrhage and 199, 519
  sudden death from berry aneurysm and 199, 519
  sudden immersion in cold water 400, 557
  units 554, 555–6
    specific drinks 555–6
  volume/volume 555–6
alcoholism 554–5
  acute 307, 557
  chronic 552, 557–8
  falls 557
alkali, deaths from 587–8
alkaline phosphatase 169
alveoli
  alcohol levels in air 555
  in newborn lung 447–8
  in paraquat poisoning 567
Alzheimer's-like condition, in boxers 204
ambient temperature *see* temperature, ambient
American Society of Anesthesiologists 482
amino acids
  dating of bones 122, 127
  in teeth 105, 535
amitriptyline 573
ammunition 247
  rifled weapons 248
  shotgun 246, 247–8
  see also bullets
amnesia, retrograde 209–10
Amnesty International 301
amniotic fluid embolism 436–7
amphetamine abuse 580, 581
β-amyloid precursor protein 470
anaemia, carbon monoxide poisoning in 562, 563
anaerobes, adipocere formation 71
anaesthesia-related deaths, medico-legal aspects 482, 483
anaesthetic-related deaths 480–5
  airway obstruction 484–5
  autopsy procedure 480–2
  cardiac arrest 484
  causes 482–4
  equipment failure 485
  histology 483, 485, 486
  hypoxia in, brain changes after 484, 486
  incidence/risk 484
  local/epidural anaesthesia 485
  mode/causes of death 482–4
anaesthetist 482, 484
analgesics, poisoning 571–2
anal intercourse 427, 428–9
anatomy, forensic
  abdomen 229
  chest 222–3, 223
  circle of Willis 512, 513
  cranium 181
  heart 223
  larynx 376, 377
  scalp 174–5
  skin 137–8, 174
  skull and meninges 108, 181–2, 182, 189
  vertebral arteries 201
aneurysms
  aortic 509–10
    atheromatous 509–10
    diagnosis 510
    dissecting 510
    fusiform/saccular 510
  berry *see* berry aneurysm
  cardiac 503
  cerebral arteries 196, 512–13
    rupture 511–13
  circle of Willis 197, 198, 511
  mycotic 511
  rupture, sudden death 509–13, 519–20
  syphilitic 510–11
angel dust (phencyclidine) 580
angiography, post-mortem 26, 200–1, 203, 512
animal bones 107, 108
animal predation
  buried body decomposition 69
  dating of bones and 126
  immersion deaths 396, 397, 398
  maggot infestation 65, 66, 74–5, 77
  marine predation 68, 75–6, 396, 398, 399
  mummified corpse 73
  post-mortem damage 73–6, 74, 75–6, 126
  putrefied corpse 67
  types/types of damage 74
  see also insects
anoxia 52, 53
  stagnant 352
ante-mortem *vs* post-mortem injury
  burns 317–19, 320

- in fire 7
- fractures 182, 344
- joint splits 7
- laryngeal fractures 378
- skull fractures 182
- ‘undertaker’s fracture’ 21
- wounds 167–9, 170–1

anthropometric dimensions 123
anticoagulants 545
antidepressants, poisoning 573
antifreeze agents 589
antimony poisoning 591
ants, post-mortem damage 75
anus
- bruising
  - homosexual offences 429
  - sexual offences 422, 427
- dilatation
  - homosexuals 427
  - interpretation 423–4, 428
  - sexual offences 427, 428
- examination at autopsy 16
- funnel-shaped 16, 429
- in homosexuals 427, 429
- injuries, in sexual offences 423
- patulous 427, 429

aorta
- anatomy 223
- aneurysms *see* aneurysms, aortic
- atherosclerosis 509–10
- deceleration injuries 228, 229
- double-barrelled 510
- examination at autopsy 25
- impact injury 228, 229
- injuries 228
  - vehicular accidents 285, 289
- ‘ladder tears’ 21, 228, 285
- medionecrosis 510
- ruptured 228, 340
  - vehicular accidents 285
- transection 228

aortic valve disease 506–7
- sudden death 506–7

aortic valve stenosis 506–7
aortitis, syphilitic 511
aorto-oesophageal fistula, surgical procedures, deaths associated 481
apex, myocardial infarction 497
apnoea, in sudden infant death syndrome 455–6
apnoea alarms 456
aponeurosis 174–5
apoptosis, conducting system, sudden death due to 505
appendicitis, acute 517
appendix abscess 517
arachnoid 189
arachnoid granulations 189
arcus senilis 104
arm, injuries in vehicular accidents 284, 286
arm-locks 353, 383
- deaths in custody 306
- fractured laryngeal horns 378

arrest, deaths after/during 305–7, 353
- *see also* custody, deaths in

arrhythmias *see* cardiac arrhythmias
arsenical poisoning 590–1
- acute/chronic 590
- autopsy findings 590–1
- blood/tissue levels 591
- corpse preservation 590
- fatal dosages 590
- sources 590
- toxicology sampling/results 591

arsenious oxide poisoning 590, 591
artefacts *see* post-mortem artefacts; resuscitation artefacts
arterial spasm 503
arteriovenous anastomosis 512
arthritis 104
asbestos/asbestosis 24–5, 103
‘asphyxia’ 352–67, 368, 369
- autopsy diagnosis 356–7
- cautions on diagnosis 357, 358, 368
- classic signs 353–7
  - absent in suffocation 358
  - cautions on use 353, 357, 368
  - congestion and oedema 356
  - cyanosis 356
  - engorgement of right heart 356
  - fluidity of blood 356
  - petechial haemorrhage 353–6, 364
- conditions/examples 352
- definitions/terminology 352, 353
- histological/biomechanical diagnosis 357
- hypostasis colour confusion 57, 58, 356
- ligature strangulation 382
- masochistic 235, 240
- mechanical 353, 369
  - *see also* choking; smothering; strangulation; suffocation
- nature of 352
- ‘obsolete diagnostic quintet’ 353, 357
- plastic bag 390, 391, 596
- postural (positional) 355, 365
  - deaths in custody 306
- sexual *see* sexual asphyxia
- in solvent abuse 596
- sudden death in epileptics 514
- suicide by 240
- traumatic 352, 363–4
  - cyanosis 364
  - deaths in custody 306

aspiration, gastric contents *see* gastric contents
aspirin poisoning 571–2
- hypersensitivity 571
- spot tests 572

aspirometer, autopsy in air embolism 347, 348
assaults, berry aneurysm rupture and 198, 519–20

asthma, sudden death 515
astrocytes, in cerebral hypoxia 213
atherosclerosis 104
  aortic 509–10
  coronary *see* coronary atherosclerosis
atlanto-occipital dislocation, in vehicular accidents 284
atria, examination at autopsy 25
auditory meatus temperature 7
Austrian decree 1
autoerotic procedures 389–92
  see also sexual asphyxia
autolysis 36, 59–60, 89
  early myocardial infarction *vs* 498
  post-mortem 345, 500–1
automatic pistols 247, 248, 273
automatic weapons 248
autopsy
  clinical (academic) 2
  forensic *see* autopsy, medico-legal
  history 1
  legislation 2
  types 2
autopsy, medico-legal 2
  abortion 435–6
  abrasions caused by 143
  in air embolism 347–8, 435–6
  in 'asphyxia' 356–7
  attendance at 3–4
  authorisation/consent 3
  blind 10
  brain examination 28–9
  bruise development 145
  burns 315–16
  case history 9–10
  child abuse 475–6
  computed tomography (CT) 31
  consent documents 3
  consent issues 2
  in decompression chamber 489
  dentures examination 15
  DNA profiling sample 604
  drowning *see* drowning, autopsy signs
  epilepsy 514
  examination of organs *see individual organs*
  external examination *see* external examination at autopsy
  failure rates 45
  fatal abuse, evidence 301
  hazards for staff 10–11
    cyanide poisoning 586
    HIV/hepatitis infection 4, 10–11
  identification of body 8–9
  incisions 16–17, 17, 425
  infanticide 442–5
  internal examination *see* internal examination at autopsy
  legislation 2
  magnetic resonance imaging (MRI) 31
  mass disasters 44
  objectives 3
  obscure 44–7, 493
    mode of death 46–7
    samples 45–6
    syndrome 45
  photography *see* photography
  plastic bag suffocation 359–60
  post-mortem artefacts *see* post-mortem artefacts
  precautions 10–11
  procedures 2–4
  putrefied corpse 39–40
    see also putrefied corpse
  radiology *see* radiography/radiology
  reasons 493
  Recommendation No. R (99) 3 610
  report 33–5
    body sketches 35
    cause of death 10
    differential diagnosis 10
    discussions/conclusions 35
    external examination 34
    format/information 33–5
    information required 34
    internal examination 34–5
    'original,' legal requirements 35
    timescale 35
  resuscitation artefacts *see* resuscitation artefacts
  retention of tissues/organs 3
  samples/ancillary investigations 29–30
  standards 1–2
axonal injury, diffuse
  in child abuse 470
  concussion in 210

back injuries, in human rights abuse 303
'back spatter' 261
bacteria
  adipocere formation 71
  in putrefaction 64–5, 68
'barbiturate blisters' 562, 574
barbiturates 486, 573–4
  poisoning 573–4
barium, in tracheobronchial tree 363
baroreceptors 369
barotrauma 346, 488–91
  air embolism 346, 488, 489
  autopsy 30, 489–90
  definition 488
  physical damage 488–9
  pulmonary 489
Barr bodies 104
basal arteries 46, 347
'base wing index' 112
basilar artery 201, 203
  see also basilovertebral artery injury

basilovertebral artery injury 200–4
  autopsy appearances 201–2
  hypothesis and problems with 200
  see also vertebral artery
basisphenoid synchondrosis 121
bathroom, deaths in 400, 401, 405
  electrical fatalities 326, 333–4, 334–5, 400, 405
  homicide 400
baton rounds 274
battered baby *see* child abuse
battery acid 587
beard, growth after death 61
beatings, torture and human rights abuse 302–3
beetles 77–8
behaviour, alcohol effect 552, 556–7
'bends' 346
benzene abuse 597
benzidine 127
benzodiazepines, poisoning 542, 573
berry aneurysm 196
  autopsy 512
  'congenital' 512
  multiple/sizes 512
  ruptured 511
    alcohol and 199, 519
    trauma/disease interaction 198–9, 519, 520
  spontaneously leaking 199
  sudden death from, mechanism 198–9, 199, 511
'beyond reasonable doubt' test 341, 471, 518, 520
bile, sample collection 548
biochemistry
  post-mortem interval 89–90
  rigor mortis 61–2
  vitreous humour 88, 89–90, 575
birds, post-mortem damage 76
birth
  concealment 440, 441, 442
  live, definition/proving 440–1, 442, 443
  newborn, lungs 447–8
bites/bite marks 527–32
  autopsy/re-examination 528, 531
  bruises associated 146
  child abuse 474, 476, 528
  common sites 528
  ear 180
  in foodstuffs 527–8
  identification of suspect 530
  impression/casts of mark 531
  investigation 530–1
  love bites 146, 421, 474, 528, 530
  matching with suspect's dentition 532
  multiple 529
  nature of mark 529–30
  nipples 528, 529, 530
  photography 528, 530–1, 532
  preservation 528
  sample collection 528, 531
  self-inflicted 529
  in sexual offences 421–2, 528, 529, 530
black eye, causes 178, 179, 180
  direct violence 149, 179
  fractures of anterior fossae of skull 179, 180
  gravitational seepage 179
  movement of bruises 146, 148, 175–6, 179
bladder
  injuries 233, 289
  urine collection at autopsy 548
blast injury 226, 274–5
bleeding
  absence in crush injuries 339
  deaths in custody 307
  in illegal abortion 432
  post-mortem 225, 233, 340
  scalp injuries 175, 176
  spurious, behind larynx 58, 150, 375
  see also haemorrhage
blisters
  barbiturate 562, 574
  in burns 315
    first degree 312–13
    post-mortem/'peri-mortal' 315, 317
  in carbon monoxide poisoning 562
  in electrical fatalities 330, 331
  post-mortem artefacts 36
  in putrefaction 64, 65
blood
  alcohol levels *see under* alcohol
  in carbon monoxide poisoning 562, 563–4
    see also carbon monoxide
  carboxyhaemoglobin *see* carboxyhaemoglobin
  changes in drowning 404–5
  clotting 58, 341–2, 356
  culture, samples 29
  DNA profiling 106, 604
  flow, retinal, sign of death 54
  fluidity in asphyxia 356
  groups 428, 440
  from mouth/nostrils, post-mortem artefacts 12, 15, 36
  pooling, in hypothermia 417
  pressure, alcohol effect 553
  purging in putrefaction 36, 39, 65
  sample collection *see* sample collection, blood
  sample preservation 546
  sludging, in hypothermia 418
  splashes 5–6
    exclamation mark 6
  spurious formation of cyanide 587
  volume in cardiac tamponade 228
blood-alcohol curve (BAC) 553, 554
blood–brain barrier 212

blood vessels
  calcification 26
    see also calcification
  examination at autopsy 25–7
blowfly 76
bluebottles 76–7
'blue scar' of coal-miners 103
blunt injuries
  abdomen 229
  deaths in custody 306–7
  human rights abuse 304
  penetrating 153
  scalp 177
  skull fractures 177, 183
  see also abrasions; bruises/bruising
body
  buried *see* buried bodies
  clothed, examination at autopsy 8, 296
  dimensions
    effect on cooling curve 80
    male/females (tables) 108
    race determination 123
  fate after death 53
  fluids, sample collection 19–21, 549
  fragments, in explosion deaths 275–6
  identification *see* identification
  internal examination at autopsy 16–23
  labels/tags 9
  length/height *see* height; length
  posture, hypostasis pattern 56
  retrieval at mass disasters 43–4
  scene of death *see* scene of death
  size, racial/ethnic characteristics 105
  sketches, autopsy report 35
  transection 154
  weight *see* weight
body bag 7
body secretions
  clothing 8
  purging, in putrefaction 36, 39, 65
  release, external examination of body 12
  sample collection *see* sample collection
  in sudden infant death syndrome 453
  see also frothy fluid; specific secretions
bombs, injuries from 274–5
bondage, autoerotic procedures and 391
bone(s)
  animal origin 107, 108
  bullet wounds 266–7, 270
  decay, factors affecting 126–7
  density, dating of bones 126
  disease, infant fractures due to 468–9
  dried, stature determination 114, 117
  fragments, identification 107–8
  haversian architecture 108
  human origin, determination 107–8
  injuries, bone marrow embolism 344
  long
    lengths in women/men (table) 113
    race determination 122–3
    sexing 112–13
    stature determination 114
  recent *vs* old, differentiation 126
  recognition and confirmation 106–8
  sex determination from 108–14
  shotgun contact wounds over 250–1
  stature determination from 114–16
  wormian 469
  wounds from rifled weapons 266, 267, 270
  see also fractures; skeletal remains; *specific bones*
bone dysplasias 468–9
bone marrow embolism 344
boxers, head injuries 204
'boxer's attitude' 316
boxing, kinetic energy transfer 137
bradycardia 369
brain
  air gun pellets 272
  autopsy
    examination 28–9, 46
    fixation 28, 29, 512
    meningeal bleeding 28
    removal 22–3, 150
    serial sections preparation 28–9
    weight 28
    wetcutting 28
  in barotrauma/dysbarism 489–90
  in carbon monoxide poisoning 562, 563
  cerebral aneurysms 512–13
  damage 204
    carotid artery occlusion 369
    child abuse 192, 205, 465, 471, 476
    impact, theories 205
    mechanism 205–6
    motorcyclists 290
    pressure on neck causing 370
    see also cerebral injuries
  deformation
    closed head injuries 205, 206
    laminar 206
    transient 206
  in electrical fatalities 333
  petechiae 354
  putrefied corpse 40
  sample collection 550
  swelling *see* cerebral oedema
  see also entries beginning cerebral
brain death 52–3, 212
  medico-legal aspects 53
brain membranes
  forensic anatomy 181, 189
  haemorrhage 28, 188, 190–2, 211

    forensic implications 198
    see also extradural (epidural) haemorrhage; subarachnoid haemorrhage; subdural haemorrhage
  infections 189
brainstem
  damage 53
  death 53
  in electrical fatalities 327, 329
  haemorrhage 207, 214, 339
  lesions, secondary 213–14
breasts
  bites 528, 529, 530
  bruising, in sexual offences 422
breath, alcohol levels 555, 603
breathing, evidence in newborn 445–8
brittle bone diseases 468–9
bromine, abuse 597
bronchial asthma, sudden death 515
bronchial obstruction, surgical procedures, deaths associated 481
bronchial tumours 516
bronchodilators, 515
bronchopleural fistula 223, 225
bronchus, thermal damage in fires 320
bruises/bruising 143–50
  abdominal 229–30
  abrasions with 140, 141, 142, 146
  alteration with time 145, 146–8
  bite marks 148, 530
  cerebral 206
  chest/heart/face, resuscitation artefacts 40
  in child abuse 148, 462–3, 475
    age of bruises 148, 463
    fingertip 145, 148, 462, 463
  colour changes 147
  'coming out' 145
  dating, variables affecting 147
  defence wounds 165, 166
  definition 143–4
  depth/size and severity 145
  development 145
  factors affecting prominence/size 144–5
  fingertip 145, 148, 462, 463
  haemosiderin reaction 167
  hilt of knife causing 158
  hypostasis differences 59–60
    post-mortem *vs* 59–60
  in immersion deaths 398
  intradermal 140, 141, 142, 144, 146
    human rights abuse 302–3
  kicking causing 147, 149
  lacerations with 150–1, 151
  lips 150
    in sexual offences 421
  lungs 226
  movement 146, 175–6
    see also black eye
  muzzle imprint in shotgun wounds 250
  neck
    ligature strangulation 382
    manual strangulation 371–2, 374
  post-mortem artefacts 13, 36, 149–50
  prominence after death/autopsy 145, 176
  putrefied corpse 40
  scalp 175–6, 463
  seatbelts causing 289
  in sexual offences 421, 422, 427
  sixpenny 148, 463
  of special significance 148–9
  subcutaneous tissue 144–5
  'tramline' ('railway line') 148, 149, 302–3
  vessel fragility affecting 145
  vessels involved 144
brush abrasions *see* abrasions, brush
buccal cells, DNA profiling sample 604
'bucket-handle' effect, femur 466
buggery 427
bullets
  dumdum 137, 245
  explosive-tipped 137, 245
  modifications for kinetic energy transfer 137, 245
  'precessing' 265
  rifled weapons 248
  rubber and plastic 274
  soft-headed 245
  wounds *see* gunshot wounds; rifled weapons, wounds
'bumper' fractures 293
burial, traumatic 'asphyxia' in 363
buried bodies
  decomposition 68–9, 126
  deep burial 69
burning
  atypical localized (spontaneous combustion) 323–4
  suicide by 239–40
burns 312–25
  in acute alcoholism 557
  ante-mortem 315
    post-mortem burns *vs* 317–19, 320
  autopsy appearances 315–16
  child abuse 474
  classification of severity 312–13
  corrosive acids/alkalis 587
  deaths from lightning 336
  dry heat 314–15
    severity 315
  electrical 329–32
  fires 316, 318
  first degree 312–13
  flash 275
  friction *see* abrasions, brush
  hot water bottle 314, 320, 433, 435
  human rights abuse 303
  identification of body 99

burns (*contd.*)
  infections 314
  missile injuries from explosions 275
  moist heat (scalds) 313–14
  molten rubber 303
  muscle stiffening of body 63
  post-mortem 331–2
  renal failure after 345
  in rifled weapon wounds 259, 262
  'Rule of Nines' 13, 313
  scars, in identification 102
  second degree 313
  shotgun wounds 250, 251, 252
  spurious 'wounds' 316–17
  temperature/time relationship 312
  third degree 313
burnt bone fragments, identification 107–8
'burst atlas' injury 214
'burst head' 255, 267
'burst lobe' 207
butane 561, 595, 597
butcher's cleaver, wounds 165
buttocks, bruising, in child abuse 462, 463

cachexia 413
cadaveric spasm 61, 62–3
'cafe coronary' syndrome 362
Caffey's syndrome 469
calcification
  aortic valve 506, 507
  coronary arteries 26
  cricoid cartilage 376
  under periosteum 466
calcium oxalate 589
Calliphora 77
callus, in identification of remains 124, 125
callus formation 224, 467, 468
calvarium, removal 22, 347
cameras 32–3
  see also photography
Campbell de Morgan spots 11, 104
cannabis 581
capillaries
  bleeding (invisible to eye) 144
  dating emboli/thrombi 342
  permeability 212
capsaicin, injury 306
'captive-bolt' weapons 272–4
Carabelli's cusp 534
carbolic acid 587, 588
carbon dioxide, suffocation associated 357–8
carbon monoxide
  blood analysis 563–4
    sample collection 547
    sample preservation 546, 563
  blood levels
    anaemia 562, 563
    burns/fires 317, 322, 562
    road traffic deaths 296
    see also carboxyhaemoglobin
  in flash fires 320, 322, 564
  haemoglobin saturation 322, 563–4
  inhalation in fires 320–2, 561
    alive when fire started 564
    death due to 320–2
  poisoning 320, 560–5
    in aircraft 560–1
    alcoholics/alcoholism 557, 560, 561
    autopsy 562–3
    in bathroom 400
    blisters 562
    causes 560–2
    cherry-pink hypostasis 57, 321, 562
    children 322
    coal-mining 561
    divers 561
    elderly and infants 563
    neurological lesions after 563
    signs 321
    sodium hydroxide test 562
    suffocation in 357–8
    suicide 560
    vehicle drivers 560–1
  post-mortem formation 564
  in shotgun wounds 250, 252, 267
  sources 560–2
    fires 561
    heating appliances 560, 561
    incomplete combustion 561–2
    industrial processes 561
    motor vehicles 560
carbon tetrachloride 597
carboxyhaemoglobin 563–4
  analytical methods 564
  carbon monoxide poisoning 322, 562–3
  levels
    deaths in fires 562
    heat haematoma/peripheral blood 192, 317, 318, 319
  samples 20
  in shotgun wounds 250, 564
cardiac aneurysm 503
cardiac arrest 53, 55
  anaesthesia association 484
  asphyxia in 353
  aspirin poisoning 572
  choking due to food 362
  in electrical fatalities 328, 329
  manual strangulation *vs* 374, 378–9
  reflex 358, 362, 369–70, 370–1
    carotid artery damage 378–9
    causes 371
    criminal abortion 432
    deaths in custody 306
    frequency 370

    hanging and/*vs* 384, 388
    immersion deaths 400, 403
    solvent abuse 595–6
cardiac arrhythmias
  aspirin poisoning 572
  catecholamines 504, 579, 596
  electrical fatalities 327, 328, 329, 333
  sudden death due to 503
cardiac asthma 505
cardiac massage, external 231–2
cardiac sarcoidosis 509
cardiac tamponade 228
  aortic aneurysm rupture 510
  chest and heart injuries 227, 228
  myocardial infarction complication 502
cardiomegaly 505
cardiomyopathies
  alcoholic 558
  arrhythmogenic right ventricle 508
  definition 507
  dilated 507
    familial 507
    idiopathic 507
  heart weight 507
  hypertrophic obstructive 507
  sudden death 507–9
  World Health Organization classification 508
cardiopulmonary resuscitation (CPR)
  child abuse *vs* 467–8, 472–3
  myocardial contraction bands after 498–9
  see also resuscitation artefacts
cardiorespiratory failure 52, 53
  sign of death 53, 55
cardiovascular disease, death whilst immersed in water 397–8
carotid arteries
  compression 369
  damage
    in hanging 388
    in manual strangulation 378–9
    reflex cardiac arrest 378–9
  examination/dissection 24, 379
carotid sinus reflex 369
'carotid sleeper' 306
cartilage
  dating of bones 126
  stab wounds 163
case history, in autopsy 9–10, 453
catecholamines 41, 361, 419
  arrhythmias caused by 504, 579, 596
  resuscitation artefacts 41, 353
  sudden death from subarachnoid haemorrhage 519
cathepsins, in wounds 169
'cat-o'nine-tails' 303
Caucasian features 122, 123, 534
cause of death *see* death, cause
cavitation, high-velocity missiles/projectiles 246, 270
cellular death 52, 63–4
central nervous system, in barotrauma/dysbarism 490
cerebellar tonsils, herniation/coning 211
cerebral aneurysm, rupture 511–13
  see also berry aneurysm
cerebral arteries 197
cerebral arterioles, sensitivity 199
cerebral contusion 206
cerebral dysfunction, hypothermia with/and 415
cerebral fat embolism 343
cerebral haemorrhage *see* intracerebral haemorrhage
cerebral hypoxia 212–13
  histology 212–13
  in sexual asphyxia 389
  stages and changes 213
cerebral infarction 214
cerebral injuries 204–12
  in child abuse 192, 205, 465, 471, 476
  concussion after 209–10
  coup/contrecoup damage 207–9
  deceleration 205, 206
  intracerebral haemorrhage 207
  mechanism 193, 206
  rotatory movements of head and 209
  see also brain, damage
cerebral lacerations 206–7
cerebral oedema 211–12
  autopsy features 211
  cause 211
  child abuse 470, 471
  hypoxia in 212
cerebral veins, air embolism myth 347, 435–6, 490
cerebrospinal fluid
  anaesthetic-related deaths 485
  leakage 189
  sample collection method 21, 548
  in subarachnoid haemorrhage 197, 199
cervical shock, in illegal abortion 432
cervical spine
  autopsy 21, 203
  damage/dislocation in hanging 215, 384, 385
  hyperflexion/hyperextension injuries 214–15, 215, 284
  seatbelt damage 284
  vertebral artery trauma 203
cervical vertebrae
  dislocation 215, 384, 386
  injuries 214–15, 215
cervix
  dilatation, in illegal abortion 432, 433
  perforation 433
chemicals, illegal abortions 434–5
chemical tests, dating of bones 127–8
chest
  bruising, in child abuse 463
  compression, traumatic 'asphyxia' in 363
  crushing 363–4
  flail 223, 224, 294
  forensic anatomy 222–3

chest (*contd.*)
  haemorrhage 224–5
    external bleeding absent 225
  infection 224–5
  injuries 222–9
    cardiac tamponade 227, 228
    self-inflicted 243
    vehicular accidents 283–4, 285
  radiograph, in air embolism 347
  stab/sucking wounds 225
    see also stab wounds
  suicidal knife wounds 238
  see also thorax
chest wall
  damage, in child abuse 467–8
  injuries 223–4
  rib fractures *see* rib fractures
'chicken-fat' plasma clot 341
child abuse 11, 414, 461–79
  abdominal injuries 230, 463, 472
  abrasions, patterned 475
  autopsy 475–6
    radiology 32, 476
  axonal injury, diffuse 470
  bites/bite marks 474, 476, 528
  bone diseases *vs* fractures due to 468–9
  bruising *see under* bruises/bruising
  burns 474
  cardiopulmonary resuscitation *vs* 467–8, 472–3
  chest wall damage 467–8
  cigarette burns 474
  definitions 461
  duodenum rupture 472
  eye/ear/mouth injuries 472–3, 476
  facial injuries 178, 463, 472–3
  falls *vs* 465
  fractures 224
    dating in 468
    spiral 467
  general aspects 461–2
  haemoperitoneum 463, 475
  hair pulled, in 474–5
  head injuries 193, 469–71
    brain damage 192, 205, 465, 471, 476
    extradural haemorrhage 471
    mechanisms 469–70, 471
    moving 471
    subarachnoid haemorrhage 197, 470–1
    subdural haemorrhage 192, 193, 469, 470, 471
  injuries 462–3
    miscellaneous 475–6
  liver damage 232, 472
  medico-legal aspects 471
  modes of death 462
  non-fatal 462
  periosteum shearing 466
  psychological 461
  radiography/radiology 32, 476
  rib fractures 224, 467–8
  sample collection 476
  scalds 474
  scalp 463
  scene of death visit 475
  sexual 461
    anal dilatation 423–4, 428
    anal rapes 427, 429
    internal examination 425
    rape 425–6, 427, 429
  shaking and subdural haemorrhage 192, 193, 469, 470, 471
  skeletal damage 464–8
    chest cage 224, 467–8
    dating of fractures 468
    limb fractures 466–7
    rib fractures 224, 467–8
    skull fractures 185, 464–6
    see also skull fractures
  subdural haemorrhage 192, 193, 469, 470, 471
  teeth, avulsion/breakage 473
  visceral injury 472
children
  accidental hanging 389
  accidental injury, child abuse concerns 462
  adult-induced injury *see* child abuse
  age estimation from skeletal remains 118
  air gun injuries 271
  carbon monoxide poisoning in fires 322
  cerebral oedema 212
  hanging in 385
  head injury from falls 180
  neglect 412, 417
  pedestrians, injuries 292–3
  scalds 314, 474
  seatbelts 289
  skull fractures 180, 185, 466
  suffocation 358
  vulnerability in vehicular accidents 289–90
  see also infant
china, stab/slash wounds from 156, 164
chisel wounds 153
chlordiazepoxide 573
chloride 89, 317, 404
chloroform 597
chlorophyll 408
chlorpromazine 548
choke-holds *see* arm-locks
choking 361–3
  causes 361–3
  deaths in custody 307
  definition 353
  haemorrhage 361
  infanticide 443–4
  suicide 361
cholinesterase, inhibition 567
cigarette burns, child abuse 474

circle of Willis 197, 198, 512, 513
  see also berry aneurysm
circumcision 104, 105
cirrhosis of liver 558
cisternal puncture 548
civil cases, disease and trauma 519, 520
clavicle
  fractures, in child abuse 468
  medial end, epiphyseal fusion 118
clay, modelling 128
clinical toxicologist 541
Clostridium perfringens 57, 434
  adipocere formation 71
clothing
  body secretions on 8
  body temperature measurement and 82
  effect on cooling curve 81
  examination
    sexual offences 422, 423
    solvent abuse 597–8
  inadequate, hypothermia and 416
  pathologists' 4
  position in suicidal knife wounds 8, 239
  race/ethnic characteristics, in identification 104
  removal methods 8
  ripped, in deaths from lightning 336
  road traffic accidents 8, 296
  scene of death 8
  soiling/burning in shotgun wounds 8, 250, 251
  spontaneous combustion 323
  vehicular accidents 296
clotting, blood 58, 341–2, 356
clubbing injuries, in human rights abuse 304
coagulative myocytolysis 498
coal-mining, carbon monoxide poisoning 561
cocaine
  blood/tissue levels 580
  deaths associated 581–2
  toxicological sample preservation 546
coffin
  decomposition of bodies 69, 72
  exhumation 37, 38
  measurement 103
'cogitation' *see* hypostasis, post-mortem
cold
  injury caused by 414–18
    see also hypothermia
  local injuries 416, 419
  muscle stiffening 63
collagen 168, 342
collateral circulation 496
collodiaphyseal angle 113
colon
  perforation 517
  removal at autopsy 21
colour of skin *see* hypostasis; skin, colour
coma, epidural haemorrhage 190, 191
combustion, spontaneous 323–4
'commando punch' 371
comparisons, technique of 106
complications of injuries 339–51
  adult respiratory distress syndrome 345
  air embolism 346–8
  disseminated intravascular coagulation 345–6
  fat and bone marrow embolism 343–5
  haemorrhage 339–40
  infections 340
  pulmonary embolism 340–3
  renal failure 345
  subendocardial haemorrhage 348–9
  suprarenal haemorrhage 349
  see also under individual complications
compression wave, explosions 274
computed tomography (CT) 31
  gunshot wound 261
computer graphic techniques, facial appearance reconstruction 128–9
concealment
  birth 440, 441, 442
  mummification in 72
conception, products of 434, 436, 442
concussion 209–10
  diffuse neuronal/axonal injury 210
  extradural haemorrhage and 190, 191
conductors, electrical 326
congenital deformities 12
congenital heart disease 455
congestion, in 'asphyxia' 356
  traumatic 363
conjunctival haemorrhage 472
containers, sample collection 30, 545
continuity of evidence 8, 544
contrecoup lesions 179, 189, 207–9
  black eyes and 179
  contusion 207, 209
  subdural haemorrhage 193
  vacuum effect 205, 207
contusions 59, 137, 143–50
  cerebral 206
  contrecoup 207, 209
  definition 143–9
  firearm wounds 270
  see also bruises/bruising
conus artery 496
conversion tables 603–4
cooling, post-mortem 79–80
  'core' temperature 79
  curves 79
    factors affecting 79, 80–1
    nomogram method 83
    plateau 79–80, 82–3
  historical aspects 78–9
  measurement methods 81–2
  multiple-site serial measurements 83

cooling, post-mortem (*contd.*)
  rectal temperature 79–80
  ‘temperature ratio’ concept 83, 87
  see also post-mortem interval; temperature, body
copper deficiency 469
Coppolino case 550
corium (dermis) 138
cornea, signs of death 54
corneal reflex 54
cornuae *see under* larynx
coronary artery
  examination at autopsy 26, 46
  in hypertensive heart disease 506
  luminal size estimation 493
  occlusion 494, 495
  spasm 503
  stenosis 493, 503
  thrombosis 285, 495, 496, 503
    without infarction 504
  vessel types 505–6
  wounds, survival period after 170
coronary artery disease 493
coronary atherosclerosis 493–5
  atheromatous plaques 493–4, 495
    detection 493–4
  complications 494–5
    haemorrhage 494–5
    thrombosis 285, 495, 496, 503
    ulcerated plaques 494
  diffuse disease 494
  in elderly 509
  haemorrhage 494–5
  hypertension and 505
  mechanism/pathology 493–4
  sites 495
  trauma relationship 518–19
    ‘beyond reasonable doubt’ test 518
    time association 518
    violence/threats precipitating 518–19
  see also myocardial infarction
coronary insufficiency 505
  cause of death 503–5
coroner 3
corpus callosum, torn 206–7
corrosive acids, deaths from 587–8
costochondral junction, in age estimation 120
cot deaths *see* sudden infant death syndrome (SIDS)
coulombs 328
counselling, in sudden infant death syndrome 456, 457
‘country guns’ 248
coup lesions 207–9
coverings, body, effect on cooling curve 81
crack cocaine 581
cranial suture closure 120–1
craniometry 110–11, 124–5
cranium, anatomy 181
cratering, bullet wounds 266
creatinine 89
crenation
  edges of bites 75, 76
  shotgun wound edges 251, 253
crib deaths *see* sudden infant death syndrome (SIDS)
cribiform plate, ruptured/fractured 189
cricoid cartilage 376
  displacement 378
  in strangulation 376, 378, 382
crocodile-skin 331, 332
crown–heel length 448, 449
crown–rump length 118
crucifixion 365
crushing, crowds, traumatic ‘asphyxia’ in 363
crushing abrasions 139–41
crush injuries
  abdominal 229
  bleeding absent 339
crustaceans 76, 78
custody, deaths in 305–8, 353, 384, 386
  alcohol intoxication 307
  blunt injuries 306–7
  drugs 581
  hanging 308, 384, 386
  natural causes 308
  suicide 308
  see also torture
cutis anserina 395
cuts 154–5, 444
  human rights abuse 303–4
cut throats 236–7, 238
  homicidal 236, 237
CV-One syndrome 200
cyanide
  in fumes from fires 322
  inhalation 586
  poisoning 585–7
    autopsy findings 57, 585–6
    homicide 585
    sample collection 586–7
    suicide 585
    toxicology 586–7
  sample preservation 546
  smell 586
  spurious formation in blood 587
cyanmethaemoglobin 586
cyanosis 356
  carbon monoxide poisoning 562
  electric fatalities 333
  fatal pressure on neck 368
  hypothermia 417
  immersion deaths 400
  traumatic ‘asphyxia’ 364
cytochrome P450 572
cytological examination, sex determination 104

dagger, 'stiletto' 231
damp conditions, hypothermia in 415
dartos muscle 61
dating
  bruises, variables affecting 147
  emboli/thrombi 342–3, 520
  fractures 468
  myocardial infarction 496–7
  pulmonary embolism 342–3, 520
  skeletal remains 126–8
    environment effect 126
    physical appearance 126–7
    physical tests 127
    serological/chemical tests 127–8
  subdural haemorrhage 195–6, 197
  wounds 166–9, 170, 171
death
  brain *see* brain death
  cause 9–10
    mode *vs* 55
    obscure autopsy 45–7
  cellular 52, 63–4
  in custody *see* custody, deaths in
  fate of body after 53
  gunshot/explosive, radiology 31
  indications 53–5
  interval between injuries and 169–71
  manner 55
  mode 46–7, 55
  pathophysiology 52–97
  scene of *see* scene of death
  signs 53–5
  somatic 52, 53
  sudden *see* sudden death
  time of/since *see* post-mortem interval
  traumatic 8
  types 52–3
death certificates 10, 55, 341
death certification, by physicians 493
decalcification 203
decapitation
  hanging 384
  railway suicides 297
  sexual offences 423
  'tail-gating ' motorcycle accident 290
deceleration 281
  G forces 281
  seatbelts effect 288
deceleration injuries 214, 215, 281, 287
  aorta 228, 229
  cerebral 205, 206
  liver 232
  lungs 226
  spinal 214, 215
  subdural haemorrhage 193, 470
  tissue damage 281
  see also vehicular injuries
decomposition 63–78
  adipocere formation *see* adipocere
  buried bodies 68–9, 126
  changes in 64
  charting teeth and 536–7
  coffin 69, 72
  damage by predators 67, 69, 73–6
  dry (mummification) *see* mummification
  identification of corpse 99
  immersed bodies 67–8, 396–7, 398–9
  infant 441, 442–3, 446
  maggot infestation 65, 66, 69
  mixed forms in body 72
  putrefaction *see* putrefaction
  tattoos in identity establishment 100–1
  time scale 64
decompression
  aircraft 357
  divers 488, 489
  physical damage 488–9
decompression chamber, autopsy in 489
decompression sickness 488
deep vein thrombosis 341, 513
  dating 342–3, 520
  in hypothermia 418
  medico-legal aspects 341–2, 520
  sudden death from pulmonary embolism 513, 520
defence wounds 165–6, 167, 168
defibrillator, post-mortem artefacts 12, 36, 41
degenerative disease, age estimation 122
dehydration, in neglect/starvation 414
delayed deaths 339, 563
  see also complications of injuries
dental records 535
  diagrammatic/anatomical charts 535–6
  features to record 537
  odontogram 536
dentine, staining 538
dentistry, forensic 527–40
  bite marks 474, 527–32
    see also bites/bite marks
  identification of dead 532–8
    age determination 122, 534–5
    charting teeth 535–8
    general/reconstructive identity 533–5
    human origin 533
    mass disasters 44
    personal identity/comparative 535
    positive match 537
    race determination 533–4
    sex determination 533
  need for expert odontologists 527
  photography role 537
  pink teeth 538
  radiography role 537
  see also teeth

dentures
  choking due to 361
  examination at autopsy 15
  identification by 537
dermis 138
diabetes mellitus, post-mortem interval estimation 90
'Diachylon' 434
diastasis of suture lines 185, 187, 188
diatoms, types/species 407–8
diatom techniques *see under* drowning
diazepam 573
DIC (disseminated intravascular coagulation) 345–6, 432, 436, 437
diethylene 589
digestion 85, 86–8
diphtheria 361, 508, 515
diploe 181
Diptera 76
diquat poisoning 566
disasters *see* mass disasters
discoloration *see* skin, colour
discriminant function analysis 110
disease, natural
  deaths before immersion 397–8
  deaths in custody and 308
  deaths whilst in water 397–8
  trauma relationship 198–9, 517–20
  vehicular injuries and 295–6
  see also individual diseases
dismembered corpses, identification 99
dissection techniques 16–23
  see also autopsy, medico-legal
disseminated intravascular coagulation (DIC) 345–6, 432, 436, 437
divers/diving 488
  'bends' 346
  carbon monoxide poisoning 561
  pressure changes/effects 488, 489
DNA 105
  hair root cells 99
  hypervariable regions 106
  probes 106
  redundant segments 106
DNA fingerprinting/profiling 105–6
  dating of bones 127
  'hit-and-run' accidents 296
  identity establishment 105–6
  infanticide 440
  method 106
  samples/controls 106, 604
  seminal/vaginal fluids 106, 424, 428
  sex determination 104, 533
doctors, fingerprints 101
dogs, post-mortem damage 74
dothiepin 573
Down's syndrome 455
drag marks 140
drivers, medical checks 296
drowning 10, 401–2
  in acute alcoholism 557
  adipocere formation 406
  autopsy signs 402–4
    froth in air passages 402–3, 404
    other organs 404
    overinflation of lung 403, 404
  barotrauma and 489
  cadaveric spasm and 63
  chemical changes in blood 404–5
  decomposition of bodies 67–8
  diagnosis and diatom test 406–8, 602–3
    problems/criticisms 408
    techniques 406–7, 408
  'dry-lung' 400, 403
  electrolytes changes in 401, 404–5
  in epilepsy 514
  freshwater 401
  haemodilution 401, 404
  haemorrhage 404
  histological changes 405–6
  human rights abuse 304
  infanticide 445
  lungs 402–3, 404, 405
  mechanism of death 401–2
  petechial haemorrhage 403
  pulmonary haemorrhage 403
  seawater 401–2
  sodium, release in 401
  see also immersion deaths
drug(s)
  alcohol absorption and 554
  deaths in custody and 307, 581
  illegal abortions 434–5
  overdoses, in hospital 543
  poisoning/overdose *see under* poisoning
drug addicts/abuse 577–84
  autopsy appearances 578–9
  autopsy risks for pathologist 579
  intravenous 577, 582
  'mainlining' 577, 582
  see also specific drugs
drugs of dependence 577
'dum-dum' bullet 137, 245
duodenal ulcer, perforated 517
duodenum
  rupture, in child abuse 472
  transection 230
Dupertuis and Hadden's table, stature estimation 116
dura mater 189
dust blasting 275
Dwight's table, sex determination 112
dysbarism 488–91
  autopsy 489–90

- definition 488
- physical damage 488–9

ear
- barotrauma 488, 489
- bites 180
- blast injuries 275
- bruise below 148
- haemorrhage, in drowning 404
- injuries 179–80
  - child abuse 473
  - human rights abuse 304

ear crepitance test 447
'ecbolics' 434
ecchymoses 144, 353
- *see also* bruises/bruising; petechial haemorrhage

'ecstasy' 581
ectopic pregnancy 436
elderly
- carbon monoxide levels in blood 563
- chronic subdural haematoma 194, 195
- falls 180
- hypothermia 415, 416–17
- neglect 412
- subdural haemorrhage 192–3
- sudden death (senile myocardium) 509
- tearing of gastrointestinal tract 517

electrical conduit pipe weapon 248
electrical fatalities 326–38
- in bathroom 326, 333–4, 334–5, 400, 405
- cardiac arrhythmias 327, 328, 329, 333
- cutaneous burns/marks 329–32
  - areola of blanched skin 331
  - charring 331
  - earthing/'grounding' lesions 331
  - firm contact (blisters) 329, 330, 331
  - high-voltage 331
  - histology 333
  - spark burn 329, 330, 331
  - temperature and heat generation 329–30
- cyanosis 333
- effects on muscle 328–9
- electrical considerations 327–8
- histological appearances 333
- homicide 334–6
- hypostasis, post-mortem 56, 333
- internal appearances 333
- metallic traces in marks 332–3, 335
- mode of death 329
- non-electrical trauma in 329
- pathway for current 326, 327
- patterned electric marks 332, 336
- petechial haemorrhage 333
- physical factors 327
- post-mortem hypostasis 56, 333
- requirements for/events in 327, 328, 329
- resistance of skin 328
- rigor mortis timing 61
- suicides 239, 326, 334
- time, importance 327, 328, 331

electrical torture, in human rights abuse 304
electric current 327–8, 328
- alternating (AC)/direct (DC) 327–8
- application to genitals 391
- frequency 327
- mA leading to death 328

electric shock 326, 327
- tolerance to 327

electrocution 326
- *see also* electrical fatalities

electrolytes, changes in drowning 401, 404–5
electronic cameras, use at autopsy 32–3
electrons 326, 327
emaciation 412, 413
emboli, sources 343
embolism 341
- air *see* air embolism
- amniotic fluid 436–7
- bone marrow 344
- fat *see* fat embolism
- foreign body 344–5
- pulmonary *see* pulmonary embolism

'emmenagogues' 434
emphysema
- in barotrauma/dysbarism 490
- interstitial 489

emphysema aquosum 403, 405
enamel pearls, on teeth 534
endocarditis, post-rheumatic 582
endothelial proliferation 342
endotracheal tube, position 481
energy transfer, kinetic 137, 245, 246
English Infanticide Act (1938) 439
entomology 76–8
- collection of material 78
- insect succession 76
- insect types 76
- rationale 76
- *see also* insects

enzyme histochemistry 498–9, 500, 501–2
enzymes
- dating of wounds 169
- in myocardial infarction 498

eosinophilia, myocardial infarction 498, 500
epicardial petechiae 333
epicranial aponeurosis 174–5
epidermis 138
- tags 139

epidural anaesthesia, deaths related 485
epidural haemorrhage *see* extradural (epidural) haemorrhage
epiglottis, haemorrhages 378
epiglottitis 361, 515

epilation 474–5
epilepsy
  autopsy 514
  sudden death 514–15
    Purkinje cells in 514–15
  traumatic/post-traumatic 188–9, 514
epiphyseal fusion, age estimation 118
epiphyseal injuries/lesions, in child abuse 466, 467
equipment
  failure, surgical/anaesthetic deaths 484, 485
  internal examination 18
  scene of death 4–5
Erdheim's degeneration 510
ergometrine, illegal abortions 434
erythema, in burns 315
erythema ab igne 312
ethnic characteristics
  hair structure 99, 105
  identity establishment 105
  scars 102
  skin colour 99
  stature estimation from skeletal remains 114
  tattoos 100, 105
  see also race
ethyl alcohol *see* alcohol
ethylene 589
ethylene chloride 597
ethylene glycol poisoning 589
Europe, sudden infant death syndrome in 452
execution, extrajudicial 305
exertion, sudden death and 519
exhumation 36–9, 68
  arsenical poisoning 590
  coffin identification 37, 38
  legal procedures 37
  photography 37
  poisoning 38–9
  reasons for 37
  transportation 38
exit wounds *see* rifled weapons, wounds; shotgun wounds
explosions
  anaesthetic-related deaths 485
  deaths from 274–7
    autopsy in 276–7
    body fragments 275–6
    identification 276–7
    missile injuries 275–6
    nature of trauma 274–5
    radiography/radiology 31, 276
explosives, detonation, carbon monoxide poisoning 563
exposure, deaths from 419
external examination at autopsy 11–16
  age/race/sex 11
  anatomical diagrams 14
  external marks 12
  procedures/routine 11–16
  report 34
  vomit/secretions 12–13
  weight/length 11–12
external jugular occlusion 368
extradural (epidural) haemorrhage 190–2
  blood volume 190
  in child abuse 471
  clinical signs and latent interval 190–1, 198
  formation and sites 190
  heat haematoma *vs* 192, 317
  incidence/mortality rate 190
  'lucid' (latent) period 190, 191
  medico-legal aspects 191–2, 198
  in posterior fossa 191–2
  post-mortem artefacts resembling 192
extradural space, heat haematoma 317
eye(s)
  in age determination 104
  black *see* black eye
  colour, identity establishment 99
  examination 14–15
  globe tension decrease at death 54
  injury, in child abuse 472–3, 476
  laceration of eyebrow 151
  petechial haemorrhages 354, 371
  signs of death 54–5
  in traumatic 'asphyxia' 364
eyebrow, injuries 151, 178
eyelids, sign of death 54

face/facial appearance
  abrasions 178
  bloating in putrefaction 65
  bruising, in child abuse 463
  congestion 370
  examination, in solvent abuse 598
  external examination 13
  features in adipocere formation 71, 72
  in hanging 384
  hypothermia 416, 417
  identity establishment 99
  in ligature strangulation 380
  petechial haemorrhages 354, 355, 356
  pressure marks 358, 360
  in putrefaction 65
  racial/ethnic characteristics 105
  recognition in mummification 72
  reconstruction from skull 128–9
facial injuries 178–80
  brain removal at autopsy 22
  in child abuse 178, 463, 472–3
  from kicking 149, 178–9
  self-inflicted 242, 243
  in vehicular accidents 282, 284
faeces, purging, in putrefaction 65
faecoliths 414
'Falanga' 303
falls 180–1

- acute alcoholism and 557
- contrecoup lesions 208
- deaths in custody 307
- elderly 180
- head injuries 181, 471
- head injury in children 180, 187, 465
- from height
  - brain damage in children 465
  - cadaveric spasm and 63
  - injuries 181, 240
  - injury to aorta 228
  - onto feet 181, 214, 240
  - onto head 181, 471
  - pelvic injuries 233
  - skull fractures 184, 187
  - suicidal 240
- hip, dislocation in 233
- occipital, skull fractures 184
- scalp injuries 177–8
- spinal injuries 181, 214
- from standing position, injuries 180
- trajectory 181

falx, mechanism of brain damage 207

fat
- alcohol insolubility 552
- effect on cooling curve 80
- putrefaction 67

fat embolism 343–5
- autopsy findings 344
- in barotrauma/dysbarism 490
- cerebral 343
- in chronic alcoholism 558
- conditions associated 343
- marrow source 344
- petechial haemorrhage 344
- pulmonary 343
- systemic 343–4

feet, beating of soles 303

femoral heads, sexing from 112

femoral vein, blood samples 19–20, 547

femur
- fractures, in pedestrians 293
- sexing from 112–13
  - ‘mathematical sexing’ 112
  - shaft and angle 112–13
- stature estimation 114, 115, 117

fetishism 391

fetus
- age estimation from skeletal remains 117–18, 449
- deaths, cocaine use 581
- decomposition 64
- delivery after death 65
- maturity estimation, ossification centres 444, 445
- measurements 448, 449
- mummified 72–3
- skeletal age 449
- *see also* infanticide; stillbirth

fibrin
- amniotic fluid embolism 437
- dating of emboli/thrombi 342
- staining 342, 601

fibrinogen 346

fibrinolysis 346

fibroblasts 168, 195

fibula, fractures 293

Fiedler’s myocarditis 508

‘fight or flight’ response 170

fights, dynamic nature 154

finger, desquamated casts 102

fingernail
- abrasions 141
  - concavity of mark 141, 373
  - curvature/orientation 141
  - ligature strangulation 382
  - manual strangulation 141, 372–3, 373
- examination, in sexual offences 423
- putrefaction 65
- scraping/clippings 373, 423

finger pads, scarring 102

fingerprints
- desquamated casts 102
- identity establishment 101–2
  - putrefying corpse 39, 102
- immersion deaths 395, 396

fingertips, bruising by 148
- in child abuse 144, 462, 463

fire
- anaesthetic-related deaths 485
- ante-mortem *vs* post-mortem injury 7
- autopsy appearance after 315–16
- carbon monoxide poisoning 320–2, 561, 564
- cause of death 319–20, 322
- deaths, carboxyhaemoglobin levels 562
- evidence of being alive at 322, 564
- flash 320, 322, 564
- heat haematoma 191, 192, 317
- injuries to body 7
- suffocation in 357
- vehicular accidents 288, 297
- *see also* burns; smoke

firearms 246–8
- air guns 271
- calibre 247
- country guns 248
- muzzle, impression/patterned abrasion 143, 250
- range of discharge estimation 270–1
- rifled weapons 248
- shotguns (smooth-bore) 246–8
- veterinary pistols and ‘stud-guns’ 272–4
- wounds *see* gunshot wounds
- *see also* bullets; rifled weapons; shotguns

fire extinguishers 595

flail chest 223, 224, 294

'flaying' injury 152, 176
  scalp 176
  vehicular accidents 294
flotation test 445–6, 447
fluid, body *see* body secretions
fluorescence 127
  myocardial infarction 500–1
  sex determination 104
fluorocarbons, abuse 597
fontanelles, anterior/posterior 181
food
  alcohol absorption and 553, 554
  bite marks 527–8
  choking due to 361–3, 362
  diatoms in 408
  lack, hypothermia and 416
  total deprivation 412
foot, beating of sole 303
footprints
  abrasions/bruises 144, 150
  identity establishment 101–2
foramen magnum, ring fracture around 181, 185, 214, 283, 290
force
  assessment, stab wounds 161–3
  intensity, in wounding 136
  in skull fractures 186–7
forehead, sex determination from skull 109
forehead injury, movement of bruises 146
foreign bodies
  abdominal injuries 232–3
  choking due to 361
  embolism 344–5
  in gut 232
  respiratory obstruction 515
  sand/mud in immersion deaths 396, 404
  in vagina/rectum 426
forensic autopsy *see* autopsy, medico-legal
formalin fixation 28, 29, 30
formalin inflation, lungs 24–5
fractures
  ante-mortem *vs* post-mortem 182, 344
  'bumper' 293
  child abuse 224
  dating 468
    in child abuse 468
  heat, post-mortem artefacts 36
  infant, bone diseases causing 468–9
  'motor cyclist's' 185, 188, 290
  spiral, in child abuse 467
  undertaker's 21
  in vehicular accidents 283, 284, 293
  see also other specific fractures; rib fractures; skull fractures
frenulum of lip, rupture/tearing 178, 473
friction burns *see* abrasions, brush
frontal lobe
  'burst lobe' 207
  contrecoup lesions 208, 209
frontal sinus identification 124–5
frostbite 416, 419
frothy fluid, from mouth/nostrils
  burns 316
  drowning 402–3, 404
  morphine addicts 578
  sudden infant death syndrome 454
fruit, bite mark preservation 528
fume inhalation 319–22
  causes of death 319–20, 322
  toxic substances 322
  see also smoke

gagging 352, 353, 360–1
gags, in sexual asphyxia 391
galea aponeurotica 174–5
gall bladder
  examination at autopsy 27
  in starvation 414
garrotting 353, 379
  see also strangulation, ligature
gas appliances, carbon monoxide poisoning 561–2
gas chromatography 598
  autopsy in air embolism 347, 348
gas formation 66
  decomposition of immersed bodies 68
  putrefaction 64, 65, 435
gasoline 560, 597
gastrectomy 553
gastric contents
  agonal regurgitation 547
  aspiration 362–3, 557
    in anaesthesia 484–5
    medico-legal aspects 596
    sudden infant death syndrome 453, 454
  examination at autopsy 24
  mouth examination 15
  resuscitation artefacts 41
  sample collection 27, 545, 549
    containers 545
gastric emptying
  alcohol absorption and 553, 554
  factors effecting 87–8
  investigation methods 87
  post-mortem interval estimation 83, 85, 87–8
gastric erosions, acute, in hypothermia 418
gastric lining, alcohol irritation 553
gastric transit time 88
gastroenterostomy 553
gastrointestinal haemorrhage, sudden death 516
gastrointestinal tract
  barbiturate poisoning 574
  blast injuries 275
  foreign bodies 232
  paraquat poisoning 566
  perforation 233, 517

  tearing in elderly persons 517
  see also intestine; stomach
gastromalacia 36
genitals
  examination at autopsy 16
  injuries 233
    sexual offences 423–4
  sample collection, in sexual offences 423, 424
  self-mutilation 240, 241
genitourinary system, sudden death 517
G forces 281–2, 288
glass, wounds from 155, 156, 163–4
'glassing' 155
glottis, examination at autopsy 24
glucose 89–90, 575
'glue-sniffing' 595, 596
γ-glutamyl transpeptidase 558
glycine 127
glycogen 61, 62
  depletion 63
glycol poisoning 589
glycophorin A 40
'goose-flesh' appearance 61, 395
Gough's test 511
grade crossings, injuries at 297
grain silo, suffocation in 357–8
gramoxone 566
granulation tissue 168
gravel rash 138
gravity 281
grazes 137, 138, 139, 142
  see also abrasions
grease ring 264–5
great vessels, injuries 228–9
gunpowder 248
gunshot residues, clothing 8
gunshot wounds 249–77
  air guns 271–2
  ammunition *see* ammunition; bullets
  carbon monoxide levels 250, 252, 267
  computed tomography (CT) 261
  contusions 270
  defence wounds 166
  exit 267–70
  external bleeding absent 225
  internal organs 270
  mechanics 245–6, 268
  radiology 31, 276
  range of discharge estimation 270–1
  scars 102
  shock wave from missile 246
  suicidal 239, 252, 253, 254, 255
  velocity of missile 246, 258, 268
  weapons 246–8
  see also missile injuries; rifled weapons, wounds; shotgun wounds
Gustafson technique 105
Haase's rule 448
haematoidin 147
haematoma 146
  heat 191, 192, 317, 318, 319
  peri-orbital *see* black eye
  perirenal 510
  subcapsular liver 286, 340
haematoxylin basic fuchsin-picric acid (HBFP) stain 500
haematoxylin–eosin (H and E) autofluorescence 601
haematoxylin-eosin (HE) staining 500
haemodilution, in drowning 401, 404
haemoglobin 57
  carbon monoxide saturation 563–4
  dating of bones 127
  degradation in bruises 145, 146
  glycosylated 546
haemolysis, in subarachnoid haemorrhage 197
haemopericardium 228, 229, 502
  blood sample collection 547
  dissecting aortic aneurysm 510
haemoperitoneum, child abuse 463, 475
Haemophilus influenzae 361, 515
haemoptysis, sudden death from 516
haemorrhage 339–40
  abdominal 230, 232, 233
  adrenal 349, 513
  autopsy in strangulation case 373
  behind oesophagus, hypostasis artefact 59, 150, 375
  brainstem 207, 214, 339
  chest 224–5
  choking due to 361
  in coronary atherosclerosis 494–5
  delayed deaths due to 339–40
  drowning 404
  epidural *see* extradural (epidural) haemorrhage
  epiglottis 378
  infections, due to 340
  intracerebral *see* intracerebral haemorrhage
  intracranial *see* intracranial haemorrhage
  laryngeal, in manual strangulation 377, 378
  laryngeal fractures 378, 380
  mesenteric 230–1, 233
  perirenal 232, 510
  perivascular 418
  petechial *see* petechial haemorrhage
  post-mortem 225, 233, 340
  post-mortem artefacts 57, 59, 150, 375
  pulmonary 275, 286, 403
  Sheehan's 348
  spinal cord 216
  subarachnoid *see* subarachnoid haemorrhage
  subdural *see* subdural haemorrhage
  subendocardial 285, 348–9, 590
  subintimal 494
  suprarenal 232, 295, 349
  see also bleeding
haemorrhagic diatheses 145, 354, 516

haemorrhagic shock, zonal lesions 499
haemosiderin 147, 167, 168
  dating emboli/thrombi 342
  subarachnoid haemorrhage 197, 512
haemostasis, failure 339–40
haemothorax 224, 225, 258, 340
  blood sample collection 547
  source 224
hair
  arsenical poisoning 591
  clubbed 251, 262, 315
  colour
    age determination 104
    identity establishment 99
  in copper deficiency 469
  DNA profile 99
    sample 604
  drugs of dependence 577
  effect on skull fractures 184
  loss, in thallium poisoning 592
  microscopic examination 99–100
  pubic *see* pubic hair
  pulled, in child abuse 474–5
  racial/ethnic characteristics 99, 105
  scalp injuries and 174, 175, 176
  shaving 14
  singeing 315
    deaths from lightning 337
    shotgun wounds 251, 253
    wounds from rifled weapons 262
  structure, identity establishment 99–100
  texture, in identification 105
  wetting 17
hair follicles, rigor mortis 61
hallucinogens, deaths from 580
halogenated hydrocarbons 597
halothane 486
handedness, determination 372
handguns 248
hands
  examination 12, 16
    sexual offences 423
  self-inflicted injuries 242
  sudden infant death syndrome 453
hanging 383–9
  accidental 384, 389
  autoerotic procedures and 390, 392
  autopsy appearances 387–8
  carotid arteries damage 388
  cervical spine damage 215, 384, 385
  in children 385
  in custody 308, 384, 386
  decapitation 384
  homicide 389
  hypostasis, post-mortem 56, 387–8
  judicial 383–4
  knots 384, 385, 386
  laryngeal fracture 388
  marks 308, 381–2, 386–7
    position 387
  mechanism of death 388
  methods 384–6
  petechial haemorrhage 388
  serotonin from ligature mark 169
  signs 371
  suicidal 240, 384, 388
head
  in air embolism 347, 435–6
  rotational trauma 200–4
  weight 187
head injuries 174–221
  air-gun 271, 272
  in boxers 204
  cerebral oedema *see* cerebral oedema
  child abuse *see* child abuse
  closed 206
  deaths in custody 306–7
  examination at autopsy 14
  falls 181, 471
  infanticide 444–5
  intracranial *see* intracranial injuries
  nature of impact, and haemorrhages 198
  petechial haemorrhages 14
  post-mortem 176
  post-mortem heat injuries *vs* 317, 318
  sexual offences 423
  shotgun wounds 258
  subarachnoid haemorrhage and 196–8
  survival period after 170
  vehicular accidents 283
    drivers 284
    motor cyclists 188
    pedestrians 294
head-moulding, in childbirth 197
heart
  air embolism 346, 347
  anatomy 223
  avulsion 228, 285
  in barotrauma/dysbarism 490
  bruising, in vehicular accidents 285
  conducting system, sudden death due to 504–5
  in drowning 404
  in electrocution 327
  examination at autopsy 25–7
  incisions at autopsy 25
  injuries 226–8
    blunt 227
    cardiac tamponade 227, 228
    stab wounds 223, 226–7, 229, 238
    valves 229
  orientation 223
  ‘pendulum’ effect 285
  petechiae 354
  putrefaction 66–7

  rhythm disturbances *see* cardiac arrhythmias
  right, engorgement 356
  rigor mortis 61
  rupture 502
  sudden infant death syndrome 454
  suicidal stab wounds 238
  weight 26, 505, 507, 509
    cardiomyopathies 507
  wounds, survival period after 170
  see also entries beginning cardiac; left ventricle; right ventricle
heat
  convection/radiation 314–15
  flexures 317
  generation, cutaneous electric marks 329–30
  injuries 312
    see also burns; fire; scalds
  loss by body 79, 80–1, 81
    see also cooling, post-mortem
  muscle stiffening 63
  radiant, injuries 312
  regulation, alcohol effect 553
heat fractures, post-mortem artefacts 36
heat haematoma 191, 192, 317, 318, 319
heating, inadequate, hypothermia and 416
heating appliances, carbon monoxide poisoning 560, 561
heavy metal poisoning 549, 585, 589–92
height
  body 603
  estimation from skeletal remains 114–16
  identity establishment 103–4
  see also length
Heimlich manoeuvre, resuscitation artefacts 41
helmets, cyclists/motorcyclists 290, 291
Henry's law 488
Henssge's nomogram 83, 84–5, 86
hepatitis B, risk 4, 10–11, 544, 579
herbicides, poisoning 566–7
hermaphroditism 104
hernia 516
heroin 580
hexylene glycol 589
'hide-and-die' syndrome 418–19
Higginson syringe 432, 433
high-velocity projectiles/missiles 246, 270
high-voltage electrical burns 331
hip, dislocation in falls 233
Hippocratic facies 413–14
histamine, in dating wounds 169
histochemistry 498, 499, 500
  enzyme 498, 501–2
  myocardial infarction 498–9, 500
  wounds 168–9
histology
  asphyxia diagnosis 357
  cerebral hypoxia 212–13
  changes after wound infliction 167–8
  sample collection 30
  sudden infant death syndrome 455, 456
  surgical/anaesthetic-related deaths 483, 485, 486
history of case, in autopsy 9–10, 453
'hit-and-run' accidents 8, 294, 296
HIV, infectivity 11, 579
HIV infection
  pre-autopsy test 10
  risk at autopsy 4, 10–11, 579
  risk in toxicology samples 544
  tuberculosis and sudden death in 516
Home Office Pathologists 4
homicide
  acute alcoholism 557
  air embolism in 346
  in bathrooms 400
  cyanide poisoning 585
  electrocution 334–6
  'faking' of vehicular accidents 297
  hanging 389
  injuries before immersion in water 398
  insulin poisoning 574–5
  ligature strangulation 379
  scalp lacerations 152
  second autopsy 3–4
  sexual offences 421, 423, 424
  shotgun wounds 250, 252
  slash wounds 155
  smothering 358
  stab wounds 155, 160, 161, 163
  suicide *vs* 235, 236, 238, 239
  vehicular 297
  see also strangulation
homosexual, anus in 427, 429
homosexual offences 428–9
hospital, poisoning deaths 543
housefly 77
humane killers, weapons 272–4
human immunodeficiency virus *see* HIV infection
human rights abuse 301–11
  evidence of fatal abuse 301–5
  extrajudicial execution 305
  organizations 301, 302
  see also custody, deaths in
Human Tissue Act 1961 3
humeral head, sexing from 112
humerus
  sexing from 113
  stature estimation 117
humidity, effect on cooling curve 81
hunting accident, twelve-bore shotguns 259
hyaline membrane 196
hydrocarbons, halogenated 597
hydrochloric acid 588
hydrogen cyanide 586
hydrogen peroxide 567
hydrolysis, fat 70, 71
hydrostatic test 445–6, 447

hydroxyproline 127
hygiene, examination at autopsy 12
hymen 424, 425
hyoid bone 376–7, 377
  fracture *see* larynx, fractures
  in manual strangulation 377
hyperaemia, in rifled weapon wounds 260, 262
hypercapnia, in solvent abuse 596
hyperchromasia 500
hyperextension injuries 214–15
hyperflexion injuries 214–15, 284
hyperkeratosis 414
hyperpigmentation, human rights abuse 303
hypersensitivity
  anaesthetics 485
  aspirin 571
hypertension
  evidence 505–6
  intracerebral haemorrhage 207
hypertensive heart disease 505–6
hyperthermia
  effect on cooling curve 80
  malignant 485–6
hypertrophic obstructive cardiomyopathy 506
hypocalcaemia 588, 589
hypoproteinaemia 414
hypostasis, post-mortem 55–60, 333
  abdominal catastrophes *vs* 517
  artefact, haemorrhage behind oesophagus 59, 150, 375
  'asphyxia' confusion 57, 58, 356
  blotchy patches 55
  bruising *vs* 59–60
  cherry-pink, carbon monoxide poisoning 57, 321, 562
  clotting of blood 58
  colour 57, 99, 562
  cyanide poisoning 57, 586
  distribution 56, 57
  electrocution 56, 333
  in hanging 56, 387–8
  immersion deaths 396
  organs 18, 59
  petechial haemorrhage 355
  skin colour 99
  skin haemorrhages in 57
  sudden infant death syndrome 454
  testing 59–60
  timing/permanence 57–8, 58
hypotension, in subendocardial haemorrhage 348
hypothermia 10, 414–18
  alcohol consumption and 553
  autopsy findings 416–18
    skin colour 416, 417
  biochemical markers 419
  blood pooling 417
  case history 10
  cyanosis 417
  death in hospital after 416
  effect on cooling curve 80, 81
  elderly 415, 416–17
  face/facial appearance 416
  factors involved 415–16
  in 'hide-and-die' syndrome 418–19
  infants 415
  manifestations 416
  thrombosis 418
  vitreous glucose 90
hypothyroidism, hypothermia in 415–16, 417
hypovolaemic shock 499
hypoxaemia, in drowning 402
hypoxanthine 89
hypoxia 352, 353
  acute-on-chronic 455
  alcohol effect 552
  anaesthetic-related deaths 484, 486
  cerebral *see* cerebral hypoxia
  cerebral oedema and 212
  in coronary insufficiency 504
  episodic, myocardial fibrosis in epileptics 514
  oedema in asphyxia 356
  post-mortem diagnosis difficulty 357
  solvent abuse 596
  suffocation in airtight spaces 358
  total 53
  see also 'asphyxia'

identification 8–9, 98–135
  callus 124, 125
  characteristics used in 99–106
  coffin, exhumation 37, 38
  corpses/material requiring 98–9
  dentition used in *see under* dentistry, forensic
  DNA characteristics 105–6
  explosion deaths 276–7
  facial, after reconstruction from skull 128–9
  fatal abuse 302
  fingerprints *see* fingerprints, identity establishment
  general groupings and personal identity 98–9
  mass disasters, serial/pathology numbers 43
  of mother 440
  need for, reasons 98
  non-skeletalized bodies
    age determination 104–5
    racial/ethnic characteristics 105
    sex determination 104
    stature 103–4
  photosuperimposition techniques 128
  putrefied corpse 101, 102
  skeletal remains *see* skeletal remains
  tattoos 100–1
  see also age estimation; sex determination; stature
iliac veins, blood samples 20
imipramine 573

immersion deaths 395–411
  in bath 400, 401
  cooling curve 81
  cyanosis 400
  death from natural causes before 397
  deaths from immersion 399–400
  decomposition of bodies 67–8, 396–7, 398–9
  estimation of duration 396–7
  fingerprints 395, 396
  hypostasis, post-mortem 396
  injuries before entering water 398
  injuries sustained in water 398–9
  low temperature 369, 397, 400
  maceration 395, 397, 406
  mode of death 400
  natural death whilst in water 397–8
  position of body 399
  predator damage 396, 397, 398
  reflex cardiac arrest 400, 403
  sand/mud in 396, 404
  signs 395–6
  sudden immersion in cold water 400
  suicidal 239
  see also drowning
immobility, venous thrombosis in 341, 520
immunocytochemistry, axonal injury 210
immunohistochemistry, myocardial infarction 502
immunological methods, semen testing 428
impedance 328
incised wounds 137, 153–66
  cuts/slashes 154–5
  lacerations *vs* 150, 151, 177
  stabs/penetrating 155–66
    see also stab wounds
industrial processes, carbon monoxide poisoning 561
infant
  accidental hanging 389
  age/maturity estimation 440, 443, 448–9
    from skeletal remains 117–18
  carbon monoxide poisoning 563
  decomposition 441, 442–3, 446
  hypothermia 415
  live birth determination 440–1, 443
  measurements 448–9
  neglect 412, 413, 414, 417
  plastic bag suffocation 359
  sample collection 21
  separate existence 445–8
  skull flexibility 183
  smothering ('overlaying') *see* smothering
  sudden death *see* sudden infant death syndrome (SIDS)
  viability 440, 442
  vitreous humour chemistry 88
  see also children
infanticide 439–50
  autopsy 442–5
  choking 443–4
  concealment of birth 440, 441, 442
  death by act of omission/commission 441–2, 443, 445
  decomposition of infant 441, 442–3, 446
  DNA fingerprinting/profiling 440
  drowning 445
  evidence of breathing 445–7
  functions of pathologist 440–2
  head injuries 444–5
  identification of mother 440
  infant maturity estimation 440, 443, 448–9
  injuries 443
  investigations, pathologists role 440–2
  lavatory pan and 444–5
  'live birth' 440–1, 442, 443
  methods 443–5
  by omission to offer care 441–2, 445
  respiration determination 445–8
  'separate existence' 440–1, 442, 443
    proof 445–8
  stillbirth determination 440–1
  strangulation 443–4
infantile cortical hyperostosis 469
infections
  after skull fractures 189
  airway obstruction 361
  burns 314
  chest 224–5
  delayed deaths due to 340
  haemorrhage due to 340
  in illegal abortion 432, 433–4
  medico-legal aspects 340
  post-traumatic 340
  risk at autopsy 4, 10–11, 579
  skin, in neglect/starvation 414
  see also HIV infection
infinite cylinder model 79, 83
inflammatory response after injuries 170
infrared monitoring, temperature 82
infusion accidents 482
inhumation 36–7
insecticides, poisoning 567–8
insects
  infestation of putrefied corpse 39
  larval length 77
  life histories 76, 77
  post-mortem damage 74–5, 75, 76
  sample collection 78
  types and succession 76
  see also entomology
insufflation of air, abortion 432–3, 435
insulin 546, 574–5
insurance, trauma/disease relationship 519
intercostal muscles 224–5
internal examination at autopsy
  abdominal organ removal 21–2
  body cavity exposure 17

internal examination at autopsy (*contd.*)
  body fluids *see* body secretions; sample collection
  dissection techniques 16–23
  equipment 18
  incisions 16–17
  neck structures removal 21
  pelvic organs removal 22
  report 34–5
  thorax 17–18, 21
  see also specific anatomical regions/organs
International Death Certificate 10
interpol document, mass disasters 44
'Interruptin' 434
intersex 104
interstitial fibrosis 507–8
interventricular septum, rupture 227, 228
intestine
  child abuse injuries 472
  contents, sample collection 549
  examination at autopsy 28
  injuries 230–1, 231, 233
  obstruction, narcotics causing 233
  removal at autopsy 21
  rupture 233
  strangulated 516
  see also colon; gastrointestinal tract
intracerebral haemorrhage 207, 513, 514
  cocaine addicts 582
  traumatic 207
intracranial haemorrhage 517
  in child abuse 192, 193, 464, 469–70
intracranial injuries 189–215
  child abuse 193, 466, 469–71, 476
  subendocardial haemorrhage in 348
  see also individual injuries
intracranial pressure, raised 211, 212, 213–14, 473
intrapulmonary haemorrhage 403
intrauterine infection 433–4
intubation 481
iris, changes after death 61, 99
iron works, carbon monoxide poisoning 561
ischaemia 52, 496, 506
ischaemic heart disease 493, 505–6
  see also aortic valve disease; coronary atherosclerosis
ischio-pubic index 111

jaw
  edentulous 535
  fractures 178
  see also mandible; maxilla
jejunum, injuries, in child abuse 472
joint splits, ante-mortem injuries 7
joule burn 329
judicial hanging 383–4
jugular veins
  blood samples 20, 548
  cut 236–7
jugular venous compression 368, 369
jumping from heights, suicide 154, 240

Kastel–Meyer test 127
keloid formation 304, 315
Kernohan's notch 214
kerosene heaters 561
kicking injuries 149
  abdominal 230
  bruises/abrasions 149
  facial 178–9
  kidneys 232
  lacerations 153
kidney
  in ethylene glycol poisoning 589
  examination at autopsy 27–8
  failure, after trauma 345
  injuries 232
  paraquat poisoning 566
  sample collection 550
kinetic energy transfer 137, 245, 246
kinky hair syndrome 469
'knee-capping' 305
knife
  blade type 157–8
  dimensions from stab wound 157
  examination and measurements 155–6
  movement within wounds ('rocking') 156, 158–9, 161
  penetration of skin 162–3
  serrated edge 158
  stab wounds by 156
    see also stab wounds
  taper of blade 158
knife wounds 155, 156
  defence 165–6, 167
  'dentele' toothed incision 236
  scars from 102
  slashed 154–5, 155
  suicidal 236–9
  'tentative incisions' 236, 237, 238
  see also stab wounds
kwashiorkor 414

labels/tags, body identification 8
laboratory, toxicology *see* toxicology
lacerations 137, 150–3
  cerebral 206–7
  firearm wounds 270
  incised wounds *vs* 150, 151, 177
  lung 226
  patterned 152–3, 176–7, 294, 295
  'sandwich effect' 151
  scalp 151, 152, 175, 176–7
  stellate 176
  types of impact causing 151–2
  vehicular accidents 284
lactic acid 62

'ladder tears,' aorta 21, 228, 285
Laminaria digitale 433
lanugo 448
larder beetles 78
laryngeal spasm 400, 403
larynx
  blockage 362
  bruising around, in manual strangulation 372
  compression 368
  cornuae (horns) 376–7, 377
  forensic anatomy 376, 377
  fractures of horns
    ante-mortem, proof 378
    autopsy damage causing 377
    bleeding 378, 380
    causes 378
    in hanging 388
    ligature strangulation 378, 382
    manual strangulation 377
    post-mortem 377
    significance 377
  haemorrhages 378
    manual strangulation 377, 378
    mucosal 375
  injuries
    ligature strangulation 382
    manual strangulation 376–7
  spurious bleeding behind 59, 150, 375
  thermal damage in fires 320
lavatory, infanticide 444–5
laxatives, illegal abortions 433
LD50 542
lead poisoning 434
lead shot (pellets) 246, 255, 256, 258, 259
left circumflex artery 495
left coronary artery 495
left ventricle
  aortic stenosis 506–7
  in arsenical poisoning 590
  hypertrophy 61, 504, 505
  stab wounds 227
  wounds 170
leg
  injuries in pedal cycle accidents 291
  injuries in vehicular accidents
    drivers 283, 284
    motorcyclists 290
    pedestrians 293–4, 295
  see also limbs
Lendrum's stain 602
length
  assessment 11–12, 103–4
  see also height
Letulle's method, examination of viscera at autopsy 21
leucocytes
  air embolism 348
  dating emboli/thrombi 342
  dating of wounds 167–8, 170, 171
  sex differences 104
level crossings, injuries 297
life-support machines 53
ligamentum arteriosum 228
ligature strangulation *see* strangulation, ligature
lightning, deaths from 336–7
limbs
  bruising, in child abuse 462
  diameter, in neglect/starvation 413
  fractures *see* fractures
  length after death 239
  see also leg
lips
  autopsy findings in sexual offences 421
  bruises/bruising 150
  in child abuse 178, 473
  frenulum of, rupture/tearing 178, 473
  injuries 178
  pressure marks 360
  prints 101–2
liver
  alcohol detoxification 554
  central/parallel tears 286, 287
  in chronic alcoholism 557–8
  cirrhosis 558
  fatty changes 557–8
  injuries in child abuse 232, 472
  necrosis, halothane association 486
  paracetamol poisoning 572–3
  paraquat poisoning 566
  rupture 231–2, 232, 286
  sample collection 545, 550
  in solvent abuse 596
  subcapsular haematoma 286, 340
  temperature 82
  vehicular injuries 231, 232, 286, 287
lividity *see* hypostasis, post-mortem
'love-bites' 146, 421–2, 474, 528, 530
'lucid interval' 343
lumbar puncture 548
lung(s)
  autopsy, examination 24
  in barotrauma/dysbarism 489, 490
  diatoms in 406
  in drowning 402–3, 404, 405
  'dry-oedema,' in adult respiratory distress syndrome 345
  fat in 343–4
  fetal, maturation 447–8
  formalin inflation 24–5
  granuloma, in cocaine addicts 582
  haemorrhage *see* pulmonary haemorrhage
  hypostasis 59
  injuries 226
    bruising 226
    deceleration 226
    penetrating 226

lung(s) (*contd.*)
  injuries (*contd.*)
    'pincer contusions'/lacerations 226
    vehicular accidents 285–6
  newborn 447–8
  overinflation 403, 404
  paraquat poisoning 566–7
  post-mortem aeration in newborn 447
  sample collection, for volatile substances 549, 598
  stillbirth 446–7
  sudden death in asthma 515
  surgical/anaesthetic-related deaths 486
  thermal damage 320
  weight 403
  see also entries beginning pulmonary, respiratory
Luxol Fast Blue stain 213
lynching 384
lysergic acid diethylamide (LSD) 580
lysol 587, 588

maceration 64, 442–3
  immersion deaths 395, 397, 406
macrophage 168, 405–6
maggot infestation 65, 66, 74–5, 77
  see also animal predation
magnesium 404–5
magnetic resonance imaging (MRI) 31, 161
malar flush 416, 417
malate dehydrogenase 502
malathion 567, 568
malic acid dehydrogenase (MDH) 600
mandible
  fractures 178
  race determination from skeletal remains 122
  removal/examination 536
  sex determination 108, 109–10
marasmus 413
marbling 65
Marfan's syndrome 510
marine predation 68, 75–6, 396, 398, 399
  see also animal predation
Martius scarlet blue (MSB) stain 601
masks, in sexual asphyxia 391
masochistic practices 389–92
  see also sexual asphyxia
Mass Casualty Plan 42
mass disasters
  autopsy 44
  forward planning 41–2
  identity establishment
    from dentition 532–3
    frontal sinus comparison 124–5
  interpol document 44
  mortuary, facilities 42, 43
  necessities in planning 42–3
  pathologist's role 41–4
  pathology investigations 42–3
  retrieval of bodies 43–4
  Royal College of Pathologists guidelines 44
  temporary mortuaries 43
  toxicology samples 44
mastoid process, sex determination 109
masturbation 391
maternal deaths *see* abortion; pregnancy
maxilla
  fractures 178
  kicking injuries 149
  removal/examination 536–7
MDMA (methylenedioxymethamphetamine) 581
meals, post-mortem interval estimation and 85, 87–8
mechanical forces, wounding 136–7
medical records, poisoning deaths 543
medico-legal aspects
  air embolism 346
  aspiration of gastric contents 596
  brain death 53
  child abuse 471
  extradural (epidural) haemorrhage 191–2, 198
  infections 340
  myocardial infarction 496, 518–19
  neglect/starvation 414
  pressure on neck 370
  pulmonary embolism 340, 341–2, 520
  sexual asphyxia 391–2
  solvent abuse 596
  subarachnoid haemorrhage and berry aneurysm 198–9, 519–20
  sudden infant death syndrome (SIDS) 456–7
  surgery/anaesthesia-related deaths 482, 483
  trauma and disease relationship 517–18
medico-legal autopsy *see* autopsy, medico-legal
medionecrosis 510
meningeal haemorrhage 188, 190–2, 197
meninges *see* brain membranes
meningococcal septicaemia 349
Menke's syndrome 469
mentally disordered persons, self-inflicted injuries 240
mercuric chloride 546
mercy killings 346, 359
mescaline 580
mesentery
  haemorrhage 230–1, 233
  infarction 516
  injuries in vehicular accidents 286, 289
  lacerations/injuries 230–1, 231
  rupture 289
  thrombosis 516
metallic ions, in electrical marks 332–3, 335
metallic poisons 589–94
  see also arsenical poisoning
metaphysis, avulsion/lesions 466, 467
methadone, misuse 580
methaemoglobinaemia 57

methylamphetamine sulphate 581
methyl chloride 597
methylene chloride 597
methylenedioxymethamphetamine (MDMA) 581
metopic suture 121
microbiological culture, autopsy samples 20
microbiology samples 20, 45–6
  collection at autopsy 29
  contamination at autopsy 29
  see also sample collection
microvacuolation 213
microwave thermography 82, 83
middle meningeal artery, in haemorrhages 190, 192
miliary plaques 67
military weapons 248
minerals, diatomaceous materials in 408
miners, identity establishment 103
minisatellite DNA regions 106
missile injuries
  in explosions 275–6
  mechanics 245–6, 268
  trajectory of missile 245–6
  velocity of missile 246, 258, 268
  see also firearms; gunshot wounds
mitral stenosis 507
molluscs 396
Mond method 561
Mongoloid races 122, 123, 533, 534
morphine 548, 578–80
  autopsy appearances of addicts 578–9
  blood/tissue levels 580
  sudden death 578
mortuary, mass disasters
  facilities 42, 43
  temporary 43
motorcycles, modern safety features 290
motorcyclists, injuries 290–1
'motor cyclist's fracture' 185, 188, 290
motor vehicle accidents *see* vehicular injuries
motor vehicles
  carbon monoxide sources 560
  see also vehicles
mottling, in hypostasis 59
mould formation, mummified corpse 72, 73
mouth
  autopsy findings in sexual offences 421
  blood from, post-mortem artefacts 12, 15, 36
  child abuse 473
  examination at autopsy 13, 15
  injuries 178, 473
  paraquat poisoning 566, 567
  shotgun wounds 267
mucoid medial degeneration 510
mucosal ecchymoses, in aspirin poisoning 571, 572
mucus formation, in arsenical poisoning 591
mud, on body, in immersion deaths 396
'mugging' 353, 383
mummification 64, 72–3
  adipocere with 72
  artificial 72
  factors affecting 72
  injury preservation 73
  timing 73
Munchausen syndrome 241, 243
Munchausen syndrome by proxy 243
muscle
  cadaveric spasm 62–3
  contractures, burns 316
  damage, renal failure after 345
  electricity effects on 328–9
  flaccidity as sign of death 53, 60
  heat/cold stiffening 63
  rigor mortis 60, 61
  sample collection 550
  shortening, rigor mortis 62, 103–4
  spasm, electric current effect 328–9
mutilated corpses 31, 99
mutilation, in sexual offences 423
mycotic aneurysms 511
myelomalacia 216
myocardial failure, in drowning 401
myocardial fibres, in electrical fatalities 333
myocardial fibrosis 497, 503, 504, 509
  cause of death 503–4
  diffuse 503
  in epilepsy 514
myocardial infarction 493, 495–502
  age/dating 496–7
  atheroma/thrombosis causing 495–6
  autopsy diagnosis 496–7
  cause of death 503–4
  complications 502–3
    aneurysms 503
    mural thrombosis 502–3
    myocardial fibrosis 503
    pericarditis 503
    ruptured heart/tamponade 502
  enzyme histochemistry 498, 501–2
  fluorescent methods 500–1
  histochemical methods 498–9, 500
  immunohistochemical methods 502
  incidence 495
  laminar 496, 497
  macroscopic appearances/stages 496–7
  medico-legal aspects 496, 518–19
  microscopic appearances 497–502
    morphological changes 497–9
  nuclei loss 500
  regional/focal 496
  stages 497
  topography 496
  transmural 497
  transportation injuries 496, 498
  trauma/exertion relationship 518–19

myocardial infarction (*contd.*)
  types 496
  see also coronary atherosclerosis
myocardial ischaemia 496, 506
myocardial necrosis 496, 563
myocarditis 508–9
  chronic alcoholism 558
  solvent abuse 596
myocardium
  blood supply 505–6
  contraction bands 498–9
  discoloration, post-mortem artefacts 36
  examination at autopsy 27
  fat embolism 344
  fatty degeneration 499
  fragmentation of fibres 499
  hypertrophic obstructive cardiomyopathy 507
  hypostasis 59
  senile 509
  staining 498, 499, 500, 600–1
  waviness of fibres 499
myocytes 499
  nuclei 509
myofibrillar degeneration 498
myosin 62
myxoedema 415–16, 417
myxoma 511

nails *see* fingernail
narcotic drugs, deaths from 577–84
  autopsy appearances 578–9
  idiosyncratic sensitivity/tolerance 579
  mode of death 579
  toxicology 579–80
narcotics, body-packing 233
nasal aperture/bones, in sex determination 109
nazi concentration camps 413
neck
  abrasions, manual strangulation 372–3
  bruising
    child abuse 463
    ligature strangulation 382
    manual strangulation 371–2, 373, 374
  constriction, cyanosis 356
  dissection, manual strangulation 375, 377
  examination at autopsy 21, 24
  fatal pressure on 368–94
    cyanosis 368
    duration effect 370–1
    medico-legal aspects 370
    petechial haemorrhage 371
    see also hanging; strangulation
  fatal pressure on, mechanism of death 368–71
    airway occlusion 368, 369
    carotid artery compression 369
    combined/duration 370–1
    nerve effects 369–70
    reflex cardiac arrest 369–70, 370–1
  haemorrhage, manual strangulation 378
  injury to side of, vertebral artery trauma 201, 202
  post-mortem artefacts 59, 150, 375, 377
  putrefaction 65
  rotational trauma 200–4
  self-inflicted injury 242
  suicidal stab wounds 238
neck-holds, deaths in custody 306
necropsy *see* autopsy
negative autopsy *see* autopsy, medico-legal, obscure
neglect 412–14
  children 412, 417
  elderly 412
  general features 412–14
  infants 412, 413, 414, 417
  medico-legal problems 414
negligence, medical 483
  surgical procedures, deaths associated 481
Negroid features 534
nerves, pressure on neck and 369–70
Netherlands, sudden infant death syndrome prevention 452
neurological lesions, carbon monoxide, poisoning 563
neuronal injury, diffuse 209–10, 470
neurones, in cerebral hypoxia 213
Newton's Law of Cooling 79
nickel production, carbon monoxide poisoning 561
nipples, bite marks 528, 529, 530
Nissl granules 213
nitrazepam 573
nitric acid 322, 588
nitrocellulose 248
nitrogen, dating of bones 127
nitrogen narcosis 488
nitrostigmine (parathion) 567, 568
non-accidental injury in childhood *see* child abuse
nortriptyline 573
nose
  bleeding 178
  blood from, post-mortem artefacts 12, 15, 36
  fracture of bridge 178
nuclear chromatin, in sex determination 104
nylon bags, for samples 545, 549, 586, 598

obscure autopsy *see under* autopsy, medico-legal
obscure syndrome 45
obstetric catastrophes, subendocardial haemorrhage 348
obturator foramen 111
occipital bone, 'ring fracture' 181, 185, 214, 283, 290
occupational stigmata, identity establishment 103
odontogram 536
odontologists, forensic 527
odontology, forensic *see* dentistry, forensic
oedema
  in 'asphyxia' 356
  in hypothermia 417
  myocardial 500

  post-mortem dependent 56
  see also cerebral oedema; pulmonary oedema
oesophagus
  artefactual haemorrhage behind 59, 150, 375
  'banding' 375
  carcinoma 516
  corrosive acids/alkalis effect 587, 588
  cyanide poisoning 586
  intubation 481
  soot inhalation 323
  varices 516
Ohm's law 327, 328
Oil Red-O 343, 344
oleoresin capsicum (OC) 306
omentum, injuries 286
opioids 578–80
organic solvents *see* solvent abuse
organophosphorus pesticides, poisoning 567–8
organs
  atrophy, in neglect/starvation 414
  examination at autopsy 23–8
  firearm damage 270
  hypostasis 59
  position in stab wounds 159
  putrefaction 66–7
ossification centres 117, 118, 119, 121
  fetal maturity estimation 444, 445
  time of appearance (table) 119
osteogenesis imperfecta 468–9
osteometric board 117
osteoporosis 180
oxalate salts, deaths from 588–9
oxalic acid, deaths from 588–9
oxygen
  blood content 353
  deprivation 352, 357–8
oxygen:nitrogen ratio 489
oxyhaemoglobin 356, 396, 586

pachymeninges 189
pancreas, post-mortem artefacts 36
pancreatitis, acute, in hypothermia 418
papillary muscles, myocardial infarction 497
paracetamol poisoning 572–3
paradoxical respiration 223
paraffin heaters 561
paraquat poisoning 345, 566–7
parathion 567, 568
paroxysmal nocturnal dyspnoea 505
paternity testing 106
pathologists 2
  fingerprints 101
  infanticide investigations 440–2
  sudden death examination 492
  surgical procedure-related deaths 480
patient's notes 481–2
patterned abrasions *see* abrasions, patterned
patterned electric marks 332, 336
patterned lacerations 152–3, 176–7, 294, 295
PCP (phencyclidine) 580
Pearson and Bell's table, 'mathematical sexing of femur' 112
Pearson's table, stature calculation 116
pedal cyclists, injuries 291
pedestrians
  drug/alcohol intoxication 296
  injuries 291–5
    children 292–3
    primary/secondary/tertiary 291
    scooping-up 291, 292
    sequence of events 291–2, 292
    speed of impact 293
    types 293–4
pelvic 'indices' 111
pelvic organs, removal at autopsy 22, 436
pelvis
  fractures 233
  injuries 233, 294
  race determination from skeletal remains 122
  sex differentiation 111–12
penetrating injuries 155–66
penis, in putrefaction 65
penknife, wounds 226, 229
peppering, in explosions 275
pepper spray, injury 306
peptic ulcer, perforated 517
peribronchiolar cell infiltration 455
pericardial sac, bleeding into 228
pericarditis 503
pericardium, examination in air embolism 347
pericranium 175
periodic acid–Schiff (PAS) stain 600
periosteum
  blood and calcification under 466
  dating of bones 126
  shearing, in child abuse 466
perirenal haemorrhage/haematoma 232, 510
peritoneal cavity, bleeding into 230
peritonitis 233, 517
  chemical 433
perivascular haemorrhage, in hypothermia 418
Perl's reaction 167, 197
persistent vegetative state 53
personal defence spray, injury 305–6
personal identity, from skeletal remains 123–5
pesticides, organophosphorus 567–8
petechial haemorrhage 144
  'asphyxia' 354–6, 364
    as unreliable indicator 355
  barotrauma/dysbarism 490
  causes 354
  distribution 354
  drowning 403
  electric fatalities 333
  facial appearance 354, 355, 356

petechial haemorrhage (*contd.*)
  fatal pressure on neck 371
  fat embolism 344
  in hanging 388
  head injuries 14
  love bites 528, 530
  lungs, examination 24
  post-mortem artefacts 36
  posture affecting 355
  scleral/eye 354
  significance 355–6
  strangulation 354, 382–3
  subpleural 355, 403
  sudden infant death syndrome 454, 456–7
  traumatic 'asphyxia' 364
pethidine, blood/tissue levels 580
petrol 560
pets, post-mortem damage 76
Pfitner's table, bodily dimensions 108
pharynx, thermal damage 320
phencyclidine 580
phenols 588
  deaths from 587–8
phenothiazines, poisoning 573
phloxine–tartrazine stain 602
phosgene, in fumes from fires 322
phosphotungstic acid-haematoxylin stain (PTAH) 342, 499
photography
  at autopsy 13, 15, 32–3
  bite marks 528, 530–1, 532
  cameras 32–3
  child abuse 476
  exhumation 37
  film type 32
  identification by dentition 537
  illumination 32, 530–1
  scene of death 6
    composition 33
photosuperimposition techniques 128
physical abuse
  in custody *see* custody, deaths in
  fatal, evidence 301–5
  see also child abuse
physical activity
  cadaveric spasm and 63
  sudden death and 519
  timing of rigor mortis 60–1
physique, hypothermia relationship 415
pial veins 347
pia mater 189
piercing, infanticide 444
pigmentation, mottled, in heat injury 303, 304
pistols, injuries 271–2
placenta, examination in infanticide 443
plastic bag
  sexual asphyxia 390, 391, 596
  suffocation 359–60, 596
plastic bullets 274
plastic containers, for samples 545
plastic polymers, fumes from fires 322
platelets 342, 346
platysma muscle, bruising 373
pleural adhesions 21, 225, 226
pneumoconiosis, formalin inflation of lungs 24–5
pneumonia, paraquat poisoning *vs* 567
pneumothorax 223, 225–6
  autopsy 18, 31
  barotrauma/dysbarism 489, 490
  causes 225
  natural/unexpected deaths 226
  resuscitation artefacts 41
  'sucking wound' 225
  tension 225
  types 225
poisoning 541–51
  agrochemicals 566–9
  antimony 591
  arsenic *see* arsenical poisoning
  autopsy 543
  corrosive acids/alkalis and phenols 587–8
  cyanide 585–7
  detection of poison/chemical 543
  drugs of dependence 577
  ethylene glycol 589
  exhumation 38–9
  fatal concentrations, variations 542–3
  fatal dose concept 541–2
  hallucinogenic drugs 577–84
  hospital deaths 543
  medicines 8, 543, 570–6
    autopsy appearances 570–1
    autopsy difficulties 570–1
    laboratory test results 571
    mode of death 571
    see also specific drugs/medicines
  metals 589–92
  narcotic drugs 577–84
  organophosphorus pesticides 567–8
  oxalic acid and oxalate salts 588–9
  paraquat 566–7
  ricin injection 550
  sample collection *see* sample collection
  samples, 'exhibit labels'/'exhibits officer' 544
  subendocardial haemorrhage in 348
  thallium 591–2
polaroid cameras, use at autopsy 32
police
  autopsy request 3
  bite marks on 528
police cells, suicide in 308
police surgeons 421
politics, human rights abuse and 301
polyarteritis nodosa 511
polymerase chain reaction (PCR) 428

polymorphonuclear leucocytes, infiltration 168, 170
polyps, sudden death from 516
pontine haemorrhage 517
post-concussion state 209
post-mortem artefacts 36
  abrasions 139, 143, 149–50
  aortic tears 285
  bleeding behind larynx 59, 150, 375
  blisters/bloating/discoloration 36
  blood from mouth/nostrils 12, 15, 36
  bruises/bruising 13, 36, 149–50
  burns 331–2
  defibrillators 12, 36, 41
  epidural haemorrhage *vs* 192
  gastromalacia 36
  haemorrhage 57, 59, 150, 375
  haemorrhage patches 36
  myocardium discoloration 36
  neck, haemorrhage 59, 150, 375, 377
  pancreas 36
  petechiae 36
  petechial haemorrhage 36
  putrefied corpse 36, 65
  resuscitation *see* resuscitation artefacts
post-mortem bleeding 225, 233, 340
post-mortem blood clots 341
post-mortem changes 56–63
  burns 317
  hypostasis 56–60
  immersion deaths 67–8, 396–7, 398–9
  surgery/anaesthesia-related deaths 480
  toxicological 545–6, 547
  see also decomposition; hypostasis, post-mortem; rigor mortis
post-mortem cooling *see* cooling, post-mortem
post-mortem dependent oedema 56
post-mortem examination *see* autopsy
post-mortem hypostasis *see* hypostasis, post-mortem
post-mortem interval
  cerebral hypoxia diagnosis 213
  entomology and 76
    see also entomology
  estimation 78–90
    body cooling/temperature 7, 79–83
    gastric emptying 83, 85, 87–8
    multiple site temperatures 83
    post-mortem chemistry 89–90
    rectal temperature 81–2
    retinal changes 54
    at scene of death 6–7
    ‘temperature ratio’ concept 83
    thermometry 82–4, 83
    vitreous humour chemistry 88–9, 89–90
    see also cooling, post-mortem; rectal temperature
  hypostasis relationship 57
  rigor mortis and 60, 61
  ‘spot-check’ for 61
post-mortem overspill 363
postural asphyxia 355, 365
posture
  drunken prisoners 307
  effect on cooling curve 80–1
  petechial haemorrhages and 355
  sudden infant death syndrome 453
potassium 88, 89
  release in drowning 401
potassium cyanide 585, 586
potassium fluoride 545, 546
potassium permanganate 434
pre-auricular sulcus 111
precipitation (jumping from height) 240
predators, post-mortem damage *see* animal predation; insects
pregnancy 65
  deaths associated 431–8, 517
    see also abortion
  ectopic 436
  evidence from skeleton 114
  legal termination 431, 432
  seatbelt problems 289
premedication, excessive 484
pressure, adverse effects 488–91
pressure marks 359, 360
pressure sores 414
Prinsloo and Gordon artefact 59, 150, 375
procurator fiscal 3
propane 561, 595
propeller-induced injuries 399
property, personal 8
  mass disasters 43–4
  see also clothing
propylene 589
prostaglandins, illegal abortions 434
protein
  ante-mortem *vs* post-mortem burns 317
  dating of bones 127
  identification of bone fragments 108
pubic bone, sex differentiation 111
pubic hair 104
  examination in sexual offences 423
‘pubic scars’ 114
pubic symphysis, age estimation 118–20
‘Pugilistic’ attitude 63, 316, 321
pulmonary artery, injuries 228–9
pulmonary barotrauma 489
pulmonary damage, explosions 275
pulmonary embolism 24, 340–3, 513, 520
  after legal termination of pregnancy 432
  after surgery 483, 520
  appearances 341–2
  dating 342–3, 520
  medico-legal aspects 340, 341–2, 520
  post-mortem blood clot *vs* 341
  predisposing factors 341, 520

pulmonary embolism (*contd.*)
  rare causes 513
  sources of embolus 341, 520
  sudden death, deep vein thrombosis 513–14, 520
  trauma/disease interaction 340–1, 341, 520
pulmonary fat embolism 343
pulmonary granuloma 577
pulmonary haemorrhage 275, 286
  drowning 403
  vehicular accidents 286
pulmonary inflammation 455
pulmonary ligament 226
pulmonary oedema 343, 356, 455
  carbon monoxide poisoning 562
  deaths from corrosives 587
  drowning 402–3
  hypertensive heart disease 505
  hypothermia 418
  morphine addicts 578–9
pulmonary thromboembolism 513–14, 520
pulmonary tuberculosis, sudden death 516
pulsation, absence 352
‘punch-drunk’ syndrome 204
punching, in child abuse 472
puncture marks, autopsy resuscitation artefacts 40–1
puncture wounds 153
pupils
  ‘cadaveric position’ 54
  morphine administration effect 579
  sign of death 54
Puppe’s rule 266
purging of body fluids 36, 65
Purkinje cells, sudden death in epilepsy 514–15
putrefaction 64–9
  bacteria 64–5, 68
  blisters 64, 65
  definition 64
  facial bloating 65
  fingernail 65
  gas formation 64, 65, 435
  inhibition by adipocere formation 71
  internal organs 66–7
  purging due to 36, 65
  sequence of changes 64–7
  timing 64, 67, 69
    temperature effect 64, 67, 68
  see also decomposition
putrefied corpse
  bruising, glycophorin A detection 40
  external/internal examination 39–40
  fingerprints 39, 102
  identification 39, 101, 102
  insect infestation 39
  post-mortem artefacts 36, 65
  sex determination 104
pyloric spasm 553
pyogenic infections, in cocaine addicts 582

quinine, illegal abortions 434
quinsy 515

race 11
  determination
    dentistry, forensic 105, 533–4
    from skeletal remains 122–3
  identity establishment 105
  sex determination 108, 110
  skull features 110, 122, 123
  subdural haemorrhage in child abuse 470–1
  see also ethnic characteristics
radiation, burns 314–15
radiocarbon test 127–8
radiography/radiology
  age estimation in skeletal remains 117, 121
  air gun injuries 272
  ante-mortem, identity establishment 125
  in barotrauma 31
  bullet wounds 266
  child abuse 32, 476
  gunshot/explosion deaths 31, 276
  identification by dentition 537
  identification in explosion deaths 276–7
  mass disasters 44
  medico-legal autopsy 32
  mutilated remains 31
  neck, in manual strangulation 373–4
  pneumothorax 31
  vertebral artery trauma 203
radiostrontium 128
radius, in stature estimation 117
railway injuries 297–8
Rambo knife 143, 155
rape
  anal 427, 428, 429
  children 425–6, 427, 429
  crime scene 5
  deaths associated 421
  evidence 425–6
  genital injuries 424
  see also sexual offences, deaths associated
rats, post-mortem damage 75
razors, stab/incised wounds 163
rectal temperature
  cooling curve 79–80
  in hypothermia 416
  measurement methods and controversy on 81–2
  post-mortem interval estimation 81–2
    Henssge’s nomogram 83, 84–5, 86
  at scene of death 7, 81–2
  ‘temperature ratio’ concept 83, 87
rectum
  foreign bodies 426
  rupture 231
‘red flare’ 317

reflex cardiac arrest *see* cardiac arrest, reflex
refrigeration, infectivity effect 11
'refrigerator effect' 596
relatives
  attendance at autopsy 3
  information on autopsy 3
renal failure, after trauma 345
report, autopsy *see* autopsy, medico-legal, report
respiration
  cessation as sign of death 55
  changes in lung in infants 446–7
  chest wall injuries and 223
  evidence in newborn 445–8
  obstruction, foreign bodies 515
'respirator lung' 345
respiratory arrest, in electrical fatalities 328
respiratory infections 454, 456
respiratory insufficiency, in fat embolism 343
respiratory paralysis, in electrocution 327
resuscitation artefacts 36, 40–1, 224, 353
  β-adrenergic catecholamines 41, 353
  airway damage 41
  bruising chest/heart/face 40
  categories of damage 40–1
  defibrillators 12, 36, 41
  gastric contents 41
  haemorrhages 40, 41
  Heimlich manoeuvre 41
  pneumothorax 41
  puncture marks 40–1
  see also cardiopulmonary resuscitation (CPR)
rete pegs 168
retina
  child abuse 472–3
  sign of death 54
retinal haemorrhages 41, 472–3
retinal vessels, 'trucking' 54–5
retraction balls/globes 210
retrograde amnesia 209–10
retropharyngeal abscess, rupture 515
revolvers 247, 248
  see also rifled weapons, wounds
rheumatic valve disease 506, 507
'Rhyl mummy' 72
rib fractures 223–4
  callus formation 467, 468
  child abuse 224, 467–8
  pneumothorax 223
  respiration affected 223
  'string of beads' 467
  vehicular accidents 285, 290
ricin 550
rifled weapons 248
  ammunition 248
  barrel length 263
  muzzle velocity 268
  test firing 263, 270
rifled weapons, wounds 258–67
  abrasion collar 263–4, 268–9
  blowback into barrel ('back spatter') 261
  in bone 266, 267, 270
  burning/blackening 259, 262
  close-range 261–2
  contact 258–60
  direction of discharge 265–6, 268
  entrance wounds 262, 264, 265, 266, 267
  exit wounds 260, 262, 263, 268–9
  extreme trajectory 265
  fouling 263
  gas rebound 263
  grease ring ('ring of dirt') 264–5
  hyperaemia around 260, 262
  mechanics 245–6
  medium-distance 263
  muzzle gases 259
  muzzle imprint 260
  posture affecting 266
  powder tattooing 262–3
  range of discharge estimation 263, 270–1
  rust stains 260, 261
  shelving/undercutting 265
  soot/smoke soiling 262–3
  stellate 268
  suicidal 259, 261
  tangential/glancing 269
  'through-and-through' 268
  unburnt explosive/filler on skin 263
rifles 247, 248
right coronary artery 495
right ventricle
  hypertrophy 25
  stab wounds 226
rigidity, cadaveric *see* rigor mortis
rigor mortis 60–3
  biochemistry 61–2
  'breaking' 62
  charting teeth and 536
  duration 60
  electrical fatalities 61
  external examination 13
  false, heat and cold stiffening 63
  fingerprint taking 101
  goose-flesh in 61, 395
  gross effects 62
  height of body 103–4
  instant/cadaveric spasm 63
  movement of body after 62
  non-skeletal muscle/tissues 60, 61
  removal of clothes 8
  testing 60, 61
  timing/sequence 60, 61
    factors affecting 60–1
'ring fracture' 181, 185, 214, 283, 290
road traffic accidents *see* vehicular accidents; vehicular injuries

Royal College of Pathologists 30, 44
rubber bullets 274
'Rule of Nines' 13, 313

sacrum, sex characteristics 112
salicylate poisoning 571–2
saliva, samples 422, 528
sample collection
  in abortion deaths 436
  at autopsy 19–21, 547–50
  bile 548
  bites/bite marks 528, 531
  blood 19–20, 547–8
    containers 545
    for cultures 29
    for DNA testing 106, 604
    road traffic deaths 296
    sites not suitable 19–20, 547
    sites/procedures 19–20
  body fluids 19–21, 549
  cerebrospinal fluid 21, 548
  in child abuse 476
  containers for 30, 545
  in cyanide poisoning 586–7
  in drug overdoses 543–4
  entomological 78
  exhumation 37
  intestinal contents 549
  microbiological 20, 29, 45–6
  microbiological contamination 29
  obscure autopsy 45–6
  in poisoning deaths 38–9, 543–4
  retention, legal issues 3
  saliva 422, 528
  scene of death 6
  semen 106, 423, 424
  in sexual offences 106, 423, 424
  in solvent/volatile substance abuse 549–50, 597–8
  stomach contents 27, 545, 549
  in sudden infant death syndrome 456
  in surgical/anaesthetic-related deaths 486
  tissues 550
  toxicological 29–30, 46, 486, 543–4
    avoiding operator contamination 545
    containers 30, 545
    information for laboratory 544
    mass disasters 44
    post-mortem changes 545–6, 547
    preservation 544, 545–6
    request form 30
    sampling site 546–7
    timing 544
  toxicology kit 20
  urine 20, 548
  vitreous humour 20–1, 88, 548–9
  vomit 549
samples
  ancillary investigations 29
  DNA profiling 106
  histology 30, 46, 486
  labelling and continuity of evidence 544
  microbiological culture 20
  post-mortem changes 545–6, 547
  tape 6
sand, in body, in immersion deaths 396, 404
Saphir's myocarditis 508
sarcoidosis, cardiac 509
saw, internal examination of thorax 18
scalds 312–14
  child abuse 474
scalp
  bleeding 176
    after death 176
  bleeding below 175
  in child abuse 463
  forensic anatomy 174–5
  injuries 174–8
    abrasions 175
    bruising 175–6, 463
    from falls 177–8
    'flaying' 176
    lacerations 151, 152, 175, 176–7
  petechiae 354
scalping injuries 152, 176
scanning electron microscopy 332–3
scapula
  fractures 468
  sexing from 113
scars
  age of 102–3
  appearance/coloration 102, 103
  ethnic differences 102
  histology 103
  human rights abuse 102, 303, 304
  identity establishment 102–3
  knife and bullet wounds 102
  surgical 102
  traumatic 102
scene of death 4–7
  attendance by pathologist 4
  body
    blood splashes 5–6
    clothing/property 8
    position 5
    removal 7
  equipment/thermometers 4–5
  examination 4–7
  personnel at 5
  photographs 6, 33
  protection 6
  samples 6
  solvent abuse 597

  sudden infant death syndrome 453
  time since death estimation 6–7
    see also post-mortem interval, estimation
sciatic notch, greater 111
scissors, injuries from 164–5, 166
scleral haemorrhage, in child abuse 472
scratches 137, 141
  see also abrasions; fingernail, abrasions
screwdriver wounds 153
scrotum
  injuries 233
  putrefaction 64, 65
  rigor mortis 61
SCUBA diving 488, 489, 561
season, putrefaction timing 64, 67
seasonal incidence, sudden infant death syndrome 453
seatbelts 287–9
  cervical spine damage despite 284
  children/small persons 289
  criticisms 288
  injuries due to 288–9
  injury reduction 287–8, 288
  kinetic energy transfer reduced 137
  lap-strap type 287, 288
  legislation 287
  mechanism of action 287
  pregnancy 289
  types 287, 288
self-biting, in children 474
self-inflicted injuries 235–44
  non-suicidal 235, 240–3
    characteristics 242
    features assisting recognition 241
    for gain 241
  wound position and clothing 8
self-martyrdom 240
semen
  collection/sampling 106, 423, 424
  post-mortem ejaculation 12–13, 61, 391
  testing 106, 424, 426–8
    'spot' test 428
seminal fluid, DNA profiling sample 604
seminal stains 427–8
senile myocardium 509
septicaemia, in illegal abortion 433–4
septum, ruptured 502
serological tests, bones/bone fragments 108, 127–8
serotonin, in dating wounds 169
sex determination 11
  bodily dimensions 108
  cytological examination 104
  dentistry, forensic 533
  DNA analysis 104, 533
  fluorescence 104
  identification from teeth 533
  non-skeletalized bodies 104
  skeletal remains 108–14
    accuracy 108
    bone length 112, 113
    long bones 112–13
    other bones 113–14
    pelvis characteristics 111–12
    pregnancy evidence 114
    sacrum characteristics 112
    skull 108–11
  teeth 109
sex differences
  infant, sudden infant death syndrome and 452
  stature estimation 114
sexual asphyxia 389–92, 596
  features 389–91
  mechanism 389
  medico-legal aspects 391–2
  plastic bag 390, 391, 596
  suicide *vs* 390
sexual intercourse, evidence 425–6
sexual offences, deaths associated 421–30
  bites/bite marks 421–2, 528, 529, 530
  bruising 421, 422, 427
  children 106
    see also child abuse, sexual
  decapitation 423
  DNA profiling 106, 424, 428
  external examination/findings 421–4
  fingernail examination 423
  homicide 421, 423, 424
  homosexual 427, 428–9
  human rights abuse 305
  internal examination 424–5
  interpretation of minimal findings 425–6
  rectal temperature cautions 82
  sample collection 106, 423, 424
  semen testing 106, 424, 426–8
shaken-baby syndrome 193, 469–70, 471
shaking, subdural haemorrhage after 193, 469–70, 471
shark attacks 76
shaving, head 14
shear stress 193, 206, 209
Sheehan's haemorrhage 348
ships, suffocation in tanks 358
shock 170
shock waves, explosions/missiles 246, 275
shooting, human rights abuse 305
shotguns 246–8
  ammunition 246, 247–8
  cylinder and choke barrels 246
  test firing 253
  twelve-bore 247
shotgun wounds 249–58
  appearance 249, 251–3, 255–8
  burns 250, 251, 252
  carbon monoxide levels 250, 252, 267

shotgun wounds (*contd.*)
  cartridge constituents contributing 249
  close discharge 251–3
  contact wounds 249–51
    entrance *vs* exit wound 267
    muzzle impression 250, 251
    over bone 250–1
  direction of discharge/injury 254–5
  exit wounds 255, 259, 267
  features 251–3, 255–8
  foreign body embolism 345
  hair singeing 251, 253
  internal tract 255–6
  mid-to-distant range 253–4
  radiography 257, 258
  range of discharge estimation 249, 271
  'rat-hole' appearance 249, 253
  secondary damage 256
  shape 249–50, 254
  shelving/undercutting 254–5, 256
  short-to-mid-range discharge 253
  skull 266, 267
  soiling/burning 249–50, 251, 252
  suicidal 253, 254, 255
  tangential 256, 257–8
  tattooing in 252
  'through-and-through' 267
  track 255
  twelve-bore shotguns 251, 252, 253, 254, 255, 256, 258
    hunting accident 259
  wad wounds 254, 256–7
siderophage 577
SIDS *see* sudden infant death syndrome (SIDS)
sixpenny bruises 148, 463
skeletalization 67
skeletal remains 106–8
  age determination from *see* age estimation
  are the remains bones? 107
  dating *see under* dating
  evidence of pregnancy from 114
  extrajudicial execution 305
  facial appearance reconstruction 128–9
  fatal abuse 302
  general categorization 107
  human origin, determination 107–8
  identification 99, 106–8, 537
    personal identity 123–5
    see also under dentistry, forensic
  photosuperimposition techniques 128
  race determination 122–3
  sex determination *see* sex determination
  stature estimation *see under* stature
skeleton, reassembly and layout 108
skin
  in age determination 11, 104
  blisters *see* blisters
  burning *see* burns
  colour 12
    abortion deaths 346
    barotrauma 489
    burnt bodies 99
    carbon monoxide poisoning 57, 562
    cyanide poisoning 586
    ethnic characteristics 99
    hypostasis effect 99
    hypothermia 416, 417
    putrefaction 64, 65
  crepitance 489
  destruction, second degree burns 313
  forensic anatomy 137–8, 174
  haemorrhages, in hypostasis 57, 58
  heated, splits in 316, 318
  infections, in neglect/starvation 414
  maceration *see* maceration
  in mummification 72
  in neglect/starvation 413–14
  pigmentation, in identity establishment 99, 105
  'rain-drop' punctate pigmentation 590
  resistance to electrical current 328
  stab wounds 162–3
  structure 138
  temperature 79, 82
  thickness, stab wounds 162
'skin popping' 578
skin-slippage 64, 65, 99
skull
  bullet/shotgun wounds 266, 267
  children 464–5, 466
  examination at autopsy 22
  facial appearance reconstruction 128–9
  flexibility, in infants 183
  forensic anatomy 108, 181–2
  identification from
    age estimation 120–2
    personal identity 124–5
    race determination 110, 122, 123
    sex determination 108–11
  muscle ridges 109
  removal at autopsy 19
  stress lines 183
  suture lines 120–2, 181
    diastasis (springing) 185, 187, 188
  tensile strength 186–7
  thickness 181–2
skull fractures 181–9
  ante-mortem *vs* post-mortem 182
  anterior fossae, black eyes 179, 180
  axes/cutting weapons 186
  basal linear 184–5
  base of skull 185
  blood below pericranium 175
  blunt injuries 177, 183
  child abuse 185, 464–6
  children 180, 185, 466

  comminuted, bullet wounds 266, 267
  comminuted depressed 183, 186
  dangers 188–9
  depressed 177, 184, 186, 187, 188
    traumatic epilepsy after 188–9
  extradural haemorrhage associated 190–2
  falls 184, 187
  force required for 186–7
  frontal bone 466
  'growing' 466
  'hinge' 183–4, 188, 290
  horizontal cracks 466
  infections 189
  linear 183, 184–5
  mechanics 182–4
    'struck hoop' analogy 182, 183, 206
  meningeal haemorrhage after 188
  motorcyclists 185, 188, 290–1
  occipital 184, 466
  occipitoparietal 464
  pond fracture 185–6, 186
  Puppe's Rule 184
  'ring fracture' 181, 185, 214, 283, 290
  shotgun wounds 258
  significance 182, 204
  sites 183–4
  'spider's web' (mosaic) 184, 186
  'staggered' 466
  stepped 185
  types 184–6
  vehicular accidents 188–9, 284, 287
slashes 154–5, 155
slippery elm 433
smoke
  autopsy appearance of burns 315–16
  inhalation 317, 322
  soiling 252
  see also fume inhalation
smothering 358–61
  accidental 360
  definition 353
  infants 358, 359, 444, 456–7
    cot deaths *vs* 456–7
sodium 89
  release in drowning 401
sodium fluoride 545, 546
sodium hydroxide, burns 588
sodium hydroxide test, carbon monoxide poisoning 562
soft tissue injuries, pedestrians 294
soil, decomposition of buried bodies 69
solvent abuse 595–9
  asphyxia 596
  autopsy 597–8
  chemical effects 596
  dangers 595–6
  effects 595
  facial examination 598
  medico-legal aspects 596
  methods of abuse 595
  physical danger 596
  reflex cardiac arrest 595–6
  substances used 589, 596–7
  sudden death 595–6
somatic death 52, 53
Sommer's movements 62
soot
  inhalation 322–3
  staining, of skin 252, 262–3
space-occupying lesions, intracranial 193
'Spanish windlass' 240, 379, 380, 381
spark burns/lesions 329, 330, 331
spasm, cadaveric 61, 62–3
Spaulding's sign 443
specimen collection *see* sample collection
spermatozoa, retrieval 428
spiked instruments, stab wounds 156
spinal anaesthesia, deaths related 485
spinal column, stature estimation 116
spinal cord
  haemorrhage 216
  hyperflexion/hyperextension injuries 216
  infarction 216
  injuries 216
  removal/examination at autopsy 23, 24
spinal injuries 214–16
  compression damage 181, 214
  deceleration 214, 215
  examination at autopsy 23
  fractures in falls 181, 214
  hyperflexion/hyperextension 214–15
splanchnic shunt 397
spleen
  cyanide poisoning 587
  damage, in chronic alcoholism 558
  examination at autopsy 27
  haemorrhage 231, 233
  injuries 231, 286
  rupture 231
  vehicular accidents and 286
  weight, in drowning 406
spontaneous combustion 323–4
stab wounds 153, 155–66
  amount of force used 161–3
  characteristics 156–64
  chest 160, 162, 222–3, 225, 226–7, 229
    haemothorax and 224–5, 225
    heart 223, 226–7, 229, 238
    lung injuries 226
    suicidal 238
  depth 159
  direction 158–9, 159–61
  homicide 155, 160, 161, 163
  human rights abuse 303–4
  infanticide 444

stab wounds (*contd.*)
  kinetic energy transfer 136
  kitchen utensils 164
  knife dimensions and blade type 156, 157–8
  length 157
  movement of knife within ('rocking') 156, 158–9, 161
  multiple 157, 158, 160
  nature of weapons 155–6
  non-suicidal self-inflicted 241
  pneumothorax 225
  razors/glass 163–4
  sexual offences 423
  'shelving' (undercut) 159, 160
  skin 162–3
  skin thickness 162
  suicidal 238
    see also suicidal injuries, knife wounds
  survival period after 170
  'through-and-through' 226, 227
  track 160
  unilateral 'fish-tail' split 158
  'V-shaped' 160
'stagnant anoxia' 352
'staining' *see* hypostasis, post-mortem
staining techniques 600–2
stamping injuries 147, 149, 153
  flail chest 224
  great vessels 228–9
  head 179
  heart 227
starvation 412
  'dry'/'wet' types 413
  general features 412–14
  infanticide 445
  medico-legal problems 414
stature
  estimation from skeletal remains 114–16
    calculation systems 115–16, 117
    dried bones 114
    fragmentary bones 116
    length of long bones 114, 115, 116
    spinal column 116
  intact body, identity establishment 103–4
  tables, female/male 115, 116
'Stavanger definition,' sudden infant death syndrome (SIDS) 451
steel workers, identity establishment 103
steel works, carbon monoxide poisoning 561
steering wheel injuries 223, 229, 283, 287
  abdominal 229
sternal rib methods, age estimation 120
sternum
  autopsy in air embolism 347
  fractures 224, 468
  sexing from 113
stillbirth 439–40
  decomposition of fetus 64
  definition 439
  determination 440–1
  legal criteria 440–1
  proof of separate existence and 445, 446
stomach
  in aspirin poisoning 572
  in barbiturate poisoning 574
  carcinoma 516
  contents *see* gastric contents
  in cyanide poisoning 586
  deaths from corrosives 588
  in drowning 404
  emptying *see* gastric emptying
  examination at autopsy 27
  injuries 229–30
  in paraquat poisoning 566, 567
  'red velvet' in arsenical poisoning 590
  rupture 230, 231, 472
strangulation 369
  abrasion marks 141, 148, 372–3
  cricoid cartilage 376, 378, 382
  deaths in custody 308
  definition 353
  features 370
  hypostatic artefacts of oesophagus *vs* 59, 373
  infanticide 443–4
  ligature 353, 379–83
    accidental 383
    asphyxia 382
    embedded 380–1
    facial appearance 380
    hanging mark *vs* 381–2, 386
    homicide 379
    infanticide 443–4
    knots 382
    laryngeal horn fracture 378, 782
    ligature mark 141, 308, 379, 380–2
    mode of death 381, 382–3
    nature of ligature 379–80, 381
    position of mark 381–2
    signs of local injury 382
    suicidal 240, 380
  manual 371–9
    autopsy appearances 371–3
    bruising on neck 371–2, 373, 374
    cardiac arrest 374, 378–9
    carotid artery damage 378–9
    fingernail abrasions/marks 141, 372–3, 373
    internal appearance 373–4
    laryngeal fractures 377
    laryngeal fracture significance 377
    laryngeal injuries 376–7, 378
    spurious bleeding behind larynx 375
    vagal inhibition 371, 378

- petechial haemorrhage 354, 382–3
- scleral haemorrhage in 354

stress
- coronary atherosclerosis and trauma 518
- effect on digestion 88
- ruptured berry aneurysm and 199, 512

stroke, cerebral haemorrhage and 207
strontium 405
struck-hoop' action 206
'stud-guns' 273–4
subarachnoid haemorrhage 196–8
- alcohol and 199
- appearances/mechanism 196–8
- bleeding sources 197, 512
- blood volume 199
- bruise below ear 148
- in child abuse 470–1
- haemolysis 197
- investigation methods 203
- mechanism and relevance 198
- medico-legal implications 198–9, 519–20
- rapidity of death 198, 199, 511
- resuscitation artefacts 41
- rotational trauma to head/neck 200, 202
- ruptured berry aneurysm 198–9, 511, 519–20
- sudden death due to 196, 198, 511–12, 519–20
- trauma and 196–7, 198, 519
- trauma/disease interaction 519–20
- vertebral artery injury 200, 202, 203

subarachnoid space 189
subclavian veins, blood samples 20, 548
subcutaneous fat, in burns 315
subcutaneous tissue
- bruising 144–5
- sample collection 550

subdural haemorrhage 192–6
- acute 193–4
- blood volume 193
- in boxers 204
- child abuse 192, 193, 469, 470, 471
- chronic 194–5
  - enlargement mechanism 195
- closed head injuries 193
- colour changes 194, 196
- dating 195–6, 197
- elderly 192–3
- forensic implications 195, 198
- formation 193, 195
- latent interval and coma 194, 197–8
- 'neomembrane' formation 195
- racial aspects 470–1
- shaking causing 193, 469–70, 471
- 'spontaneous' 192

subdural space 189
subendocardial haemorrhage 286, 348–9, 590
'submarining' 289, 304
subpleural petechial haemorrhage 355
succinate dehydrogenase 498, 501
succinylcholine 550
sucking wounds, chest 225
suction lesions, bites in sexual offences 421–2
suction petechiae 530
- love bites 148, 421–2, 474, 528, 530

sudden death 492–526
- abdominal catastrophes 516–17
- abortion 517
- aneurysm rupture 509–13, 519–20
- aspirin poisoning 571, 572
- bronchial asthma 515
- cardiac disease 493–511
  - aortic valve disease 506–7
  - cardiomyopathies 507–9
  - coronary insufficiency 503–5
  - exertion relationship 519
  - hypertensive 505–6
  - myocarditis 508–9
  - senile myocardium 509
  - trauma relationship 518–19
  - *see also* coronary atherosclerosis; myocardial infarction
- definition 492–3
- electrical fatalities 329
- in epilepsy 514–15
- gastrointestinal haemorrhage 516
- genitourinary system 517
- haemoptysis 516
- in morphine addicts 578
- in old age (senile myocardium) 509
- pathologists 492
- pneumothorax causing 226
- pulmonary thromboembolism 513–14, 520
- respiratory obstruction 515
- solvent abuse 595–6
- subarachnoid haemorrhage 196, 198, 511–12, 519–20
- suprarenal haemorrhage 349, 510
- trauma/disease relationship 517–20
- tuberculosis 516
- vagal cardiac arrest 370
- women of child-bearing age 511

sudden infant death syndrome (SIDS) 451–60
- autopsy
  - failure 45, 456–7
  - procedure 456
- autopsy findings 359, 360, 454–5
  - external 453
  - histological 455, 456
- body secretions 453
- case history 10, 453
- causation theories 455–6
- congenital disorders and 455
- counselling 456, 457
  - organizations 457
- definition 451

sudden infant death syndrome (SIDS) (*contd.*)
  factors influencing risk 452–3
  gastric contents in air passages 363
  histology 455, 456
  incidence 451–2
  medico-legal problems 456–7
  multiple 457
  negative autopsy 45, 456
  petechiae 354
  petechial haemorrhage 454, 456–7
  posture at death 453
  publicity campaigns and 452, 455
  scene of death 453
  seasonal variation 453
  smothering of infants and 359
  'Stavanger definition' 451
  suffocation *vs* 456–7
  symptoms 453
sudden unexpected death (SUD) *see* sudden infant death syndrome (SIDS)
suffocation 352–67
  autopsy signs 360
  carbon monoxide, poisoning 357–8
  children 358
  cot deaths *vs* 456–7
  definition 353, 357
  human rights abuse 304
  plastic bag 359–60, 596
suicidal gestures 235
suicidal injuries 235–40
  fire-arm wounds 239
    automatic pistol 273
    rifled weapons 259, 261
    shotguns 239, 252, 253, 254, 255
  humane veterinary killer 273
  jumping from heights 240
  knife wounds 236–9
    abdominal 238
    chest 238
    clothing 8, 239
    cut throats 236–7, 237
    neck 238
    wrist 237–8
  multiple methods 237, 239
  sites 236
  stab wounds 238
  'tentative incisions' 236, 238
suicide
  agrochemical poisoning 566
  'asphyxia' 240
  in bathroom 400, 401, 405
  burning 239–40
  carbon monoxide poisoning 560
  choking due to foreign bodies 361
  corrosive poisons 587, 588
  in custody 308
  cyanide poisoning 585
  electrical fatalities 239, 326, 334
  falls from height 240
  hanging 240, 385, 388
  homicide *vs* 235, 236, 238, 239
  injuries before immersion in water 398
  by insulin 575
  ligature strangulation 240, 380
  medicine overdose 8
  methods 235
  by motor vehicle 297
  multiple methods 297
  notes 239, 391
  plastic bag suffocation 359, 360
  railway 297–8
  sexual asphyxia *vs* 390, 392
  submersion 239
sulphuric acid 588
supraorbital ridges, in sex determination 109
suprapubic angle 111
suprarenal artery, damage 232
suprarenal haemorrhage 232, 295, 349, 510
suprarenal vessels, damage 232
surgical procedures, deaths associated 480–7
  autopsy 480–2, 486
  bronchial obstruction 481
  classification system 482
  disease process causing 482–3
  histology 483, 485, 486
  medico-legal aspects 482, 483
  mode/causes of death 482–4
  pulmonary embolism 483, 520
  sudden death in gastrointestinal haemorrhage 516
  technique/equipment failure 483–4
  see also anaesthetic-related deaths
suspension, in torture 305
sutural diastasis 466
suxamethonium 486
syphilis 469, 511

'tache noire' 54
talc, granuloma 577
tape, samples 6
Tardieu's spots 354, 355, 364, 454
tartar emetic 591
tattooing, in gunshot wounds 252, 262–3
tattoos
  decomposition 101
  ethnic characteristics 100, 105
  identity establishment 100–1
  initials 100
  morphine addiction 579
  pigments 100, 101
  removal 101
  significance 100
taurodontism 534

teeth
  absence 535
  age determination 104–5, 534–5
  avulsion/breakage, in child abuse 473
  bite marks 530, 531–2
  bull-tooth (taurodontism) 534
  Carabelli's cusp 534
  choking due to 361
  eruption times 533, 534
  fillings 535, 537, 538
  impressions 531, 532
  loosened/broken 178
  milk 534
  occlusal attrition 534, 535
  pink 530, 538
  racemization of amino acids 105, 535
  racial differences 105, 533–4
  sex determination 109
  see also dentistry, forensic
'telefono' 304
Telkkä's table, stature calculation 116
temperature
  heat injury 312
  putrefaction 64, 67, 68
  scalds severity 314
  skin 79, 82
  tissue, electrical fatalities 330
  water, immersion deaths 369, 396, 400
temperature, ambient
  decomposition of buried bodies 68
  decomposition of immersed bodies 67
  effect on cooling curve 81
  low
    cerebral function recovery after immersion 369
    deaths from exposure 419
    hypothermia 415
    immersion deaths 396, 697, 698
  post-mortem interval estimation 7
  putrefaction 68
  rigor mortis timing 60
  succession of insects on corpses 76
temperature, body
  adipocere formation 70
  auditory meatus 7
  'core' 79, 416
  defects 312
  diurnal variations 80
  gradient for cooling 79
  initial, effect on cooling curve 80
  malignant hyperthermia 485
  measurement methods 81–2
  post-mortem interval estimation 7, 79–83
    see also cooling, post-mortem
  raised, sudden infant death syndrome 453
  rectal *see* rectal temperature
  skin 79, 82
  taking at scene of death 7
  'temperature ratio' concept 83, 87
  vitreous humour chemistry 88
temporal bone, petrous, haemorrhage 405
temporal bruise 176
tendon tags 126
tension pneumothorax 225
terrorist explosions 274–5, 277
terrorist weapons 248
testes
  fetal maturity estimation 448
  stimulation and sudden cardiac death 370
thallium poisoning 591–2
theophylline 515
thermal burns *see* burns
thermocouples 81, 82
thermometers 4, 81, 82
thermometry, post-mortem interval 82–4, 83
thighs, bruising, in sexual offences 422
thorax
  autopsy in air embolism 347, 436
  barotrauma 489
  contents, removal at autopsy 21
  internal examination at autopsy 18
  see also chest
throat
  blows to 371
  cut 236–7, 238
    air embolism in 346
thromboembolism, pulmonary 513–14
thrombosis
  coronary artery *see* coronary artery
  mesenteric 516
  mural 495, 502–3
  see also deep vein thrombosis; venous thrombosis
throttling, definition 353
'through-and-through' wounds 226, 227, 267, 268
thymic haemorrhage 454
thymus, petechial haemorrhages in 354
thyroid cartilage 376
  injuries, in manual strangulation 378
thyroid horn
  fractures 382, 388
    see also larynx, fractures
  injuries, in manual strangulation 377
tibia
  fractures 293
  stature estimation 117
tissue, sample collection 550
toluene abuse 596–7
tongue
  examination 23
  haemorrhages 378
tonsillar herniation 212
torture 301
  beatings 302–3

torture (*contd.*)
  electrical 304
  inversion in and postural asphyxia 365
  patterned electric marks 332
  scars 102, 303
  see also custody, deaths in
toxicology 541
  analyses 542–3
  laboratory, information for 544
  laboratory records 542
  mass disasters 44
  poisoning/drug abuse
    amphetamine 581
    antidepressants 573
    arsenic 590–1
    barbiturates 573–4
    cyanide 586–7
    ethylene glycol 589
    medicines 571, 572
    methadone 580
    narcotics 579–80
    organophosphorus pesticides 568
    paracetamol 572–3
    paraquat 567
  sample collection *see* sample collection
  solvent abuse 596–7
  surgical/anaesthetic-related deaths 481, 486
  toluene abuse 596
  see also poisoning
trachea
  compression 368
  soot inhalation 322–3
tracheobronchial tree, barium in 363
traffic accidents *see* transportation injuries; vehicular injuries
tranquilizer drugs, poisoning 573
transfusion accidents 482
transplant surgery 53
transport, body 7, 38
transportation injuries 281–300
  cause of death 295–7
  motorcyclists 290–1
  myocardial infarction in 496, 498
  pedal cyclists 291
  pedestrians *see* pedestrians
  railway 297–8
  suicide/homicide by 297
  vehicular *see* vehicular injuries
transsexualism 104
transvestism 391
tranylcypromine 573
trauma
  in acute alcoholism 557
  berry aneurysm rupture, and 198–9
  complications after *see* complications of injuries
  disease relationship 198–9, 517–20
    see also coronary atherosclerosis
  pulmonary embolism after 341, 520
  pulmonary fat embolism after 343
  subarachnoid haemorrhage and 196–7, 198, 519–20
  suprarenal haemorrhage after 349
traumatic asphyxia *see under* 'asphyxia'
trichloroethylene 486, 597
trichloromethane 597
tricyclic antidepressants, poisoning 573
Trotter and Gleser system 115
tuberculosis, sudden death 516
twinning, sudden infant death syndrome and 452–3
tyres, bruises/abrasions from 142, 143, 144

UK, sudden infant death syndrome in 452
ultraviolet light
  dating bones 127
  myocardial infarction 500
  semen testing 427–8
umbilical cord
  examination in infanticide 443
  post-partum changes 443, 445
unconsciousness 53
'undertaker's height' 11, 21, 103
unexpected death *see* sudden death
United States, sudden infant death syndrome in 452
urea 89
urethra, injuries 233
urine
  alcohol levels 555
  purging, in putrefaction 65
  sample collection methods 20, 548
  sample preservation 546
  toxicological analysis 543, 544
'Utus paste' 434

vagal inhibition 363, 370–1, 378, 399–400
  see also cardiac arrest, reflex
vagal reflex *see* cardiac arrest, reflex
vagina
  in abortion deaths 346, 432
  examination at autopsy 16
  in fatal sexual offences 426, 427
  foreign bodies 426
  perforation, in illegal abortion 432
  tearing/injuries 426, 427
vaginal discharge 12
vaginal fluid, DNA profiling sample 604
Valsalva experiments 371
vasectomy 428
vasovagal cardiac arrest *see* cardiac arrest, reflex
vasovagal reflex/shock *see* cardiac arrest, reflex
vegetative state 52–3
vehicles
  airbags 289
  exhaust fumes 560–1
  fragments, hit-and-run accidents 294, 296

  modern design/safety features 283, 286, 287–8, 289
    reversing warnings 293
    see also seatbelts
  rear-seat restraints 287
  seatbelts *see* seatbelts
  windscreen glass 282, 284
vehicular accidents
  in acute alcoholism 557
  concertinaing 281
  deceleration and G forces in 281
  delayed bleeding 340
  drivers 283–4
  'faking' 297
  fires in 288, 297
  a frame 283
  frontal 281, 283
  'hit-and-run' 294, 296
  intrusion of structures 283
  pedestrians in *see* pedestrians
  rear impact 281, 283, 284
  roll-overs 281, 283, 286, 287
  side-impacts 283
  suicide 297
  'tail-gating' 290–1
  types 281
  unrestrained 282
vehicular injuries 281–91
  aorta ruptured 285
  autopsy 296–7
  brush abrasions 139, 290, 294
  cervical spine hyperflexion 215, 284
  clothing examination in 8, 296
  delayed death 295
  disease, natural 295–6
  dynamics 281–2
    see also deceleration injuries
  ejection 286, 287
    seatbelt effect 287
  facial 282, 284
  flail chest 223, 294
  'flaying' 294
  head *see under* head injuries
  hyperflexion/hyperextension injuries 214, 215
  liver injuries 231, 232, 286, 287
  lung 285–6
  multiple 295
  natural deaths and 295–6, 296
  pattern abrasions from tyres 142, 143, 294, 296
  pattern of injuries 282–7
    driver 282–6
    front-seat passenger 287
    rear-seat occupants 287
  to pedestrians *see* pedestrians
  pulmonary haemorrhage 286
  radiator injuries 143
  ruptured aorta 228, 229, 285
  seatbelt effects *see* seatbelts
  steering wheel *see* steering wheel injuries
  suicidal and homicidal 297
  vulnerability of children 289–90
  see also deceleration injuries; *other specific injuries*
venereal disease 424, 426
venous congestion, in traumatic 'asphyxia' 364
venous obstruction, congestion in asphyxia 356
venous thrombosis 340–1, 341–2
  dating 342–3
  see also deep vein thrombosis
ventilation
  inadequate, carbon monoxide poisoning 561
  mechanical, adult respiratory distress syndrome 345
ventricular fibrillation
  drowning 401
  electrical fatalities 328, 329, 333
vernix caseosa 443
vertebral artery
  forensic anatomy 201
  occlusion 369
  trauma 200–4
    autopsy appearances 201–2
    autopsy demonstration 202–4
    investigations 203
    mechanism 202
    spinal blocks 203
    vulnerable points 202
vertebral bodies, compression fractures 214, 215
vertebro-occipital block 203
vessel fragility, bruising and 145
veterinary pistols 273
vials, sample collection 549
video cameras 128
Virchow's triad 348–9, 520
virus infections, myocarditis 509
virus infections, in sudden infant death syndrome 456
viscera, examination at autopsy 21, 23
'vital reaction' 169, 171, 317, 332, 363
vitreous humour
  chemistry, post-mortem interval estimation 89–90
  glucose levels 90, 575
  post-mortem interval estimation 88–9
  potassium levels 88, 89
  sample collection 20–1, 88, 548–9
  sample preservation 546
volatile substances
  sample collection 549–50, 597–8
  see also solvent abuse
voltage 328
voluntary organizations 412, 457
vomit
  aspiration 361–2, 557
  external examination at autopsy 12
  sample collection method 549
vomiting, in solvent abuse 596

vulva
  examination at autopsy 16
  injuries 233
    in sexual offences 423, 424

Wales, dating skeletal remains in 126
walkers, deaths from exposure and 419
'washer-woman's skin' 395, 396
wasting conditions 414
water
  adipocere formation 70
  carbon monoxide poisoning 561
  deprivation 412
  explosions in 275
  immersion deaths and *see* immersion deaths
  in plastic bags 360
Waterhouse–Friederichsen syndrome 349
Webley veterinary pistol 273
Weedol 566
weight
  body 603
    external examination 12
  brain, at autopsy 29
  heart *see* heart, weight
wetcutting, brain, at autopsy 27
whip, multi-thonged 303
whiplash injury 215, 283, 284
whipping, torture and human rights abuse 303
WHO method, staining 602
Widmark equation/factor 556
Wilson's classification of burns 312–13, 313
World Health Organization (WHO)
  cardiomyopathies classification 508
  cardiomyopathies definition 507
  death certificates 55
  staining method 602
  sudden death definition 492–3
  'undetermined death' 10
  wound classification 137
wounding, survival period after 169–71
wounds
  'ante-mortem' *vs* 'post-mortem' 167–9, 170–1
  chronological histological changes 167–8
  classification and types 137
  dating 166–9, 170, 171
  defence 165–6, 167, 168
  definition 136
  gunshot/firearm *see* rifled weapons, wounds; shotgun wounds
  healing 103, 167–8
  histochemical changes 168–9
  mechanism 136–7
  negative/positive vital reactions 169
  pathology 136–73
  razors/glass and china 163–4
  scissor 164–5, 166
wrists
  slashing, scars in identification 102
  suicidal cutting 237–8

XTC (Ecstasy) 581
xylene abuse 597

Zahn, lines of 503, 510
zonal lesions 499
zygomatic process, sex determination 109



RICHARD LI

FORENSIC BIOLOGY

SECOND EDITION

CRC Press
Taylor & Francis Group

FORENSIC BIOLOGY

SECOND EDITION

RICHARD LI

John Jay College of Criminal Justice
New York, New York, USA

CRC Press
Taylor & Francis Group
Boca Raton London New York

CRC Press is an imprint of the
Taylor & Francis Group, an **informa** business

CRC Press
Taylor & Francis Group
6000 Broken Sound Parkway NW, Suite 300
Boca Raton, FL 33487-2742

© 2015 by Taylor & Francis Group, LLC
CRC Press is an imprint of Taylor & Francis Group, an Informa business

No claim to original U.S. Government works
Version Date: 20140818

International Standard Book Number-13: 978-1-4398-8972-5 (eBook - PDF)

This book contains information obtained from authentic and highly regarded sources. Reasonable efforts have been made to publish reliable data and information, but the author and publisher cannot assume responsibility for the validity of all materials or the consequences of their use. The authors and publishers have attempted to trace the copyright holders of all material reproduced in this publication and apologize to copyright holders if permission to publish in this form has not been obtained. If any copyright material has not been acknowledged please write and let us know so we may rectify in any future reprint.

Except as permitted under U.S. Copyright Law, no part of this book may be reprinted, reproduced, transmitted, or utilized in any form by any electronic, mechanical, or other means, now known or hereafter invented, including photocopying, microfilming, and recording, or in any information storage or retrieval system, without written permission from the publishers.

For permission to photocopy or use material electronically from this work, please access www.copyright.com (http://www.copyright.com/) or contact the Copyright Clearance Center, Inc. (CCC), 222 Rosewood Drive, Danvers, MA 01923, 978-750-8400. CCC is a not-for-profit organization that provides licenses and registration for a variety of users. For organizations that have been granted a photocopy license by the CCC, a separate system of payment has been arranged.

Trademark Notice: Product or corporate names may be trademarks or registered trademarks, and are used only for identification and explanation without intent to infringe.

Visit the Taylor & Francis Web site at
http://www.taylorandfrancis.com

and the CRC Press Web site at
http://www.crcpress.com

Contents

Preface.......... xv
Acknowledgments.......... xvii
Author.......... xix
Introduction.......... xxi

SECTION I Biological Evidence

Chapter 1 Crime Scene Investigation of Biological Evidence.......... 3
- 1.1 Protection of Crime Scene.......... 3
- 1.2 Recognition of Biological Evidence.......... 3
- 1.3 Searches.......... 7
- 1.4 Documentation.......... 16
- 1.5 Chain of Custody.......... 17
- 1.6 Collection of Biological Evidence.......... 18
- 1.7 Marking Evidence.......... 20
- 1.8 Packaging and Transportation.......... 20
- 1.9 Final Survey and the Release of the Crime Scene.......... 25
- 1.10 Crime Scene Reconstruction.......... 29
- Bibliography.......... 30

Chapter 2 Crime Scene Bloodstain Pattern Analysis.......... 35
- 2.1 Basic Biological Properties of Human Blood.......... 35
- 2.2 Formation of Bloodstains.......... 35
- 2.3 Chemical Enhancement and Documentation of Bloodstain Evidence.......... 37
- 2.4 Analyzing Spatter Stains.......... 39
  - 2.4.1 Velocity of Blood Droplets.......... 39
  - 2.4.2 Determining the Directionality of the Stains.......... 39
  - 2.4.3 Determining Angles of Impact.......... 40
  - 2.4.4 Determining Area of Origin.......... 41
- 2.5 Types of Bloodstain Patterns.......... 44
  - 2.5.1 Passive Bloodstains.......... 44
  - 2.5.2 Transfer Bloodstains.......... 46
  - 2.5.3 Projected Bloodstains.......... 46
- Bibliography.......... 51

Chapter 3 Forensic Biology: A Subdiscipline of Forensic Science 53

- 3.1 Common Disciplines of Forensic Laboratory Services 53
- 3.2 Laboratory Analysis of Biological Evidence 53
  - 3.2.1 Identification of Biological Evidence 53
  - 3.2.2 Comparison of Individual Characteristics of Biological Evidence 54
  - 3.2.3 Reporting Results and Expert Testimony 54
- 3.3 Forensic Science Services Related to Forensic Biology 57
  - 3.3.1 Forensic Pathology 58
  - 3.3.2 Forensic Anthropology 58
  - 3.3.3 Forensic Entomology 60
  - 3.3.4 Forensic Odontology 64
- 3.4 Brief History of the Development of Forensic Biology 65
  - 3.4.1 Antigen Polymorphism 65
  - 3.4.2 Protein Polymorphism 66
  - 3.4.3 DNA Polymorphism 66
    - 3.4.3.1 Genes and Related Sequences 66
    - 3.4.3.2 Intergenic Noncoding Sequences 66
    - 3.4.3.3 Human DNA Polymorphic Markers 68
    - 3.4.3.4 Forensic DNA Polymorphism Profiling 69
- Bibliography 70

Chapter 4 Sources of Biological Evidence 77

- 4.1 Bodily Fluids 77
  - 4.1.1 Extracellular Nucleic Acids 77
- 4.2 Cells 81
  - 4.2.1 Cell Surface Markers 81
  - 4.2.2 Nucleated Cells 81
  - 4.2.3 Mitochondria and Other Organelles 83
  - 4.2.4 Cytosol 84
    - 4.2.4.1 Messenger RNAs 84
    - 4.2.4.2 MicroRNAs 85
- 4.3 Tissues 87
  - 4.3.1 Skin 87
    - 4.3.1.1 Biology of Skin 87
    - 4.3.1.2 Skin as Source of DNA Evidence 87
  - 4.3.2 Hair 88
    - 4.3.2.1 Biology of Hair 89
    - 4.3.2.2 Hair as Source of DNA Evidence 91
  - 4.3.3 Bone 92
    - 4.3.3.1 Biology of Bone 92
    - 4.3.3.2 Bone as Source of DNA Evidence 94
  - 4.3.4 Teeth 98
    - 4.3.4.1 Biology of Teeth 98
    - 4.3.4.2 Teeth as Source of DNA Evidence 100
- Bibliography 102

SECTION II Basic Techniques in Forensic Biology

Chapter 5 Nucleic Acid Extraction 111

- 5.1 Basic Principles of DNA Extraction 111
  - 5.1.1 Cell and Tissue Disruption 111
  - 5.1.2 Lysis of Cellular and Organelle Membranes 114
  - 5.1.3 Removal of Proteins and Cytoplasmic Constituents 114
  - 5.1.4 Storage of DNA Solutions 115
  - 5.1.5 Contamination 115
- 5.2 Methods of DNA Extraction 115
  - 5.2.1 Extraction with Phenol–Chloroform 115
    - 5.2.1.1 Cell Lysis and Protein Digestion 115
    - 5.2.1.2 Extraction with Organic Solvents 115
    - 5.2.1.3 Concentrating DNA 115
  - 5.2.2 Extraction by Boiling Lysis and Chelation 117
    - 5.2.2.1 Washing 117
    - 5.2.2.2 Boiling 117
    - 5.2.2.3 Centrifugation 117
  - 5.2.3 Silica-Based Extraction 118
    - 5.2.3.1 Cell Lysis and Protein Digestion 118
    - 5.2.3.2 DNA Adsorption onto Silica 118
    - 5.2.3.3 Washing 119
    - 5.2.3.4 Elution of DNA 119
  - 5.2.4 Differential Extraction 121
- 5.3 Essential Features of RNA 122
- 5.4 Methods of RNA Extraction 124
  - 5.4.1 RNA–DNA Coextraction 124
  - 5.4.2 miRNA Extraction 124
- Bibliography 127

Chapter 6 DNA Quantitation 133

- 6.1 Slot Blot Assay 133
- 6.2 Fluorescent Intercalating Dye Assay 134
- 6.3 Quantitative PCR Assay 137
  - 6.3.1 Real-Time Quantitative PCR 137
    - 6.3.1.1 TaqMan Method 138
- Bibliography 140

Chapter 7 Amplification by Polymerase Chain Reaction 143

- 7.1 Denaturation and Renaturation of DNA 143
- 7.2 Basic Principles of Polymerase Chain Reaction 143
- 7.3 Essential PCR Components 145
  - 7.3.1 Thermostable DNA Polymerases 145
  - 7.3.2 PCR Primers 146
  - 7.3.3 Other Components 147

7.4 Cycle Parameters 147
7.5 Factors Affecting PCR 149
  7.5.1 Template Quality 149
  7.5.2 Inhibitors 149
  7.5.3 Contamination 149
7.6 Reverse Transcriptase PCR for RNA-Based Assays 150
  7.6.1 Reverse Transcription 150
  7.6.2 Oligodeoxynucleotide Priming 151
  7.6.3 Reverse Transcriptase PCR 151
Bibliography 153

Chapter 8 DNA Electrophoresis 159

8.1 Basic Principles 159
8.2 Supporting Matrices 159
  8.2.1 Agarose 160
  8.2.2 Polyacrylamide 161
    8.2.2.1 Polymerization Reaction 161
    8.2.2.2 Cross-Linking Reaction 161
    8.2.2.3 Denaturing Polyacrylamide Electrophoresis 163
8.3 Apparatus and Forensic Applications 163
  8.3.1 Slab Gel Electrophoresis 163
    8.3.1.1 Agarose Gel Electrophoresis 163
    8.3.1.2 Polyacrylamide Gel Electrophoresis 164
  8.3.2 Capillary Electrophoresis 164
  8.3.3 Microfluidic Devices 165
    8.3.3.1 Modular Microfluidic Devices 167
    8.3.3.2 Integrated Microfluidic Devices 168
8.4 Estimation of DNA Size 168
  8.4.1 Relative Mobility 168
  8.4.2 Local Southern Method 170
Bibliography 171

Chapter 9 Detection Methods 175

9.1 Direct Detection of DNA in Gels 175
  9.1.1 Fluorescent Intercalating Dye Staining 175
  9.1.2 Silver Staining 175
9.2 Detection of DNA Probes in Hybridization-Based Assays 177
  9.2.1 Radioisotope Labeled Probes 177
  9.2.2 Enzyme-Conjugated Probe with Chemiluminescence Reporting System 180
  9.2.3 Biotinylation of DNA with Colorimetric Reporting Systems 180
    9.2.3.1 Biotin 180
    9.2.3.2 Enzyme-Conjugated Avidin 180
    9.2.3.3 Reporter Enzyme Assay 181
9.3 Detection Methods for PCR-Based Assays 182
  9.3.1 Fluorescence Labeling 182

9.3.1.1 Fluorescent Dyes 182
9.3.1.2 Labeling Methods....182
9.3.1.3 Fluorophore Detection 185
Bibliography 186

Chapter 10 Serology Concepts 189

10.1 Serological Reagents 189
10.1.1 Immunogens and Antigens....189
10.1.2 Antibodies....189
10.1.2.1 Polyclonal Antibodies....191
10.1.2.2 Monoclonal Antibodies....191
10.1.2.3 Antiglobulins 192
10.2 Strength of Antigen–Antibody Binding 193
10.3 Antigen–Antibody Binding Reactions....193
10.3.1 Primary Reactions 194
10.3.2 Secondary Reactions 194
10.3.2.1 Precipitation....195
10.3.2.2 Agglutination....197
Bibliography 198

Chapter 11 Serology Techniques: Past, Current, and Future.... 199

11.1 Introduction to Forensic Serology.... 199
11.1.1 The Scope of Forensic Serology.... 199
11.1.2 Class Characteristics and Individual Characteristics of Biological Evidence 199
11.1.3 Presumptive and Confirmatory Assays....200
11.1.4 Primary and Secondary Binding Assays....200
11.2 Primary Binding Assays 201
11.2.1 Enzyme-Linked Immunosorbent Assay (ELISA) 201
11.2.2 Immunochromatographic Assays 202
11.3 Secondary Binding Assays....204
11.3.1 Precipitation-Based Assays....204
11.3.1.1 Immunodiffusion....204
11.3.1.2 Immunoelectrophoretic Methods....206
11.3.2 Agglutination-Based Assays....208
11.4 DNA Methylation Assays for Bodily Fluid Identification....210
11.5 Forensic Applications of RNA-Based Assays and RNA Profiling..... 212
11.5.1 Messenger RNA-Based Assays....212
11.5.2 MicroRNA-Based Assays....214
11.6 Proteomic Approaches Using Mass Spectrometry for Bodily Fluid Identification 215
11.6.1 Mass Spectrometric Instrumentation for Protein Analysis 215
11.6.2 Analysis Strategies for Protein Identification....216
11.7 Microbial DNA Analysis for Bodily Fluid Identification....217
11.8 Nondestructive Assays for the Identification of Bodily Fluids....... 220
Bibliography 221

SECTION III Identification of Biological Evidence

Chapter 12 Identification of Blood 231

12.1 Biological Properties 231
  12.1.1 Red Blood Cells 231
  12.1.2 White Blood Cells 231
  12.1.3 Platelets 231
12.2 Presumptive Assays for Identification 232
  12.2.1 Mechanisms of Presumptive Assays 232
    12.2.1.1 Oxidation–Reduction Reactions 234
  12.2.2 Colorimetric Assays 234
    12.2.2.1 Phenolphthalin Assay 234
    12.2.2.2 Leucomalachite Green (LMG) Assay 234
    12.2.2.3 Benzidine and Derivatives 234
  12.2.3 Chemiluminescence and Fluorescence Assays 236
    12.2.3.1 Luminol (3-Aminophthalhydrazide) 237
    12.2.3.2 Fluorescin 238
  12.2.4 Factors Affecting Presumptive Assay Results 238
    12.2.4.1 Oxidants 238
    12.2.4.2 Plant Peroxidases 239
    12.2.4.3 Reductants 239
12.3 Confirmatory Assays for Identification 239
  12.3.1 Microcrystal Assays 239
    12.3.1.1 Hemochromagen Crystal Assay 239
    12.3.1.2 Hematin Crystal Assay 240
  12.3.2 Other Assays 240
Bibliography 241

Chapter 13 Species Identification 245

13.1 General Considerations 245
  13.1.1 Types of Antibodies 245
  13.1.2 Titration of Antibodies 246
  13.1.3 Antibody Specificity 246
  13.1.4 Optimal Conditions for Antigen–Antibody Binding 247
13.2 Assays 247
  13.2.1 Immunochromatographic Assays 247
    13.2.1.1 Identification of Human Hemoglobin Protein 247
    13.2.1.2 Identification of Human Glycophorin A Protein 248
  13.2.2 Double Immunodiffusion Assays 251
    13.2.2.1 Ring Assay 251
    13.2.2.2 Ouchterlony Assay 251
  13.2.3 Crossed-Over Electrophoresis 251
Bibliography 255

Chapter 14 Identification of Semen 257

14.1 Biological Characteristics 257
  14.1.1 Spermatozoa 257
  14.1.2 Acid Phosphatase 259
  14.1.3 Prostate-Specific Antigen 259
  14.1.4 Seminal Vesicle–Specific Antigen 259
14.2 Analytical Techniques for Identifying Semen 260
  14.2.1 Presumptive Assays 260
    14.2.1.1 Lighting Techniques for Visual Examination of Semen Stains 260
    14.2.1.2 Acid Phosphatase Techniques 261
  14.2.2 Confirmatory Assays 264
    14.2.2.1 Microscopic Examination of Spermatozoa 264
    14.2.2.2 Identification of Prostate-Specific Antigen 265
    14.2.2.3 Identification of Seminal Vesicle–Specific Antigen 269
    14.2.2.4 RNA-Based Assays 270
Bibliography 271

Chapter 15 Identification of Saliva 277

15.1 Biological Characteristics of Saliva 277
  15.1.1 Amylases 277
15.2 Analytical Techniques for Identification of Saliva 279
  15.2.1 Presumptive Assays 279
    15.2.1.1 Visual Examination 279
    15.2.1.2 Determination of Amylase Activity 279
  15.2.2 Confirmatory Assays 281
    15.2.2.1 Identification of Human Salivary α-Amylase 281
    15.2.2.2 RNA-Based Assays 285
Bibliography 286

Chapter 16 Identification of Vaginal Secretions and Menstrual Blood 289

16.1 Identification of Vaginal Stratified Squamous Epithelial Cells 289
  16.1.1 Lugol's Iodine Staining and Periodic Acid–Schiff Method 290
  16.1.2 Dane's Staining Method 293
16.2 Identification of Vaginal Acid Phosphatase 293
16.3 Identification of Vaginal Bacteria 294
16.4 Outlook for Confirmatory Assays of Vaginal Secretions 295
16.5 Menstruation 295
  16.5.1 Uterine Cycle 296
  16.5.2 Uterine Endometrial Hemostasis 298
16.6 D-dimer Assay 299
16.7 Lactate Dehydrogenase Assay 301
16.8 RNA-Based Assays 302
Bibliography 303

Chapter 17 Identification of Urine, Sweat, Fecal Matter, and Vomitus........................ 307
17.1 Identification of Urine... 307
17.1.1 Urine Formation.. 307
17.1.2 Presumptive Assays... 308
17.1.2.1 The Identification of Urea.................................... 308
17.1.2.2 Identification of Creatinine.................................. 314
17.1.3 Confirmative Assays.. 315
17.1.3.1 Identification of Tamm–Horsfall Protein............. 315
17.1.3.2 Identification of 17-Ketosteroids........................ 315
17.2 Identification of Sweat... 316
17.2.1 Biology of Perspiration... 316
17.2.2 Sweat Identification Assays.................................. 317
17.3 Identification of Fecal Matter.. 318
17.3.1 Fecal Formation.. 319
17.3.2 Fecal Matter Identification Assays......................... 319
17.3.2.1 Macroscopic and Microscopic Examination........ 320
17.3.2.2 Urobilinoids Tests.. 322
17.3.2.3 Fecal Bacterial Identification.............................. 324
17.4 Identification of Vomitus... 324
17.4.1 Biology of Gastric Fluid.. 324
17.4.2 Vomitus Identification Assays............................... 325
Bibliography.. 326

SECTION IV Individualization of Biological Evidence

Chapter 18 Blood Group Typing and Protein Profiling...331
18.1 Blood Group Typing... 331
18.1.1 Blood Groups.. 331
18.1.2 ABO Blood Group System.................................... 331
18.1.2.1 Biosynthesis of Antigens..................................... 333
18.1.2.2 Molecular Basis of the ABO System................... 333
18.1.2.3 Secretors... 335
18.1.2.4 Inheritance of A and B Antigens......................... 336
18.1.3 Forensic Applications of Blood Group Typing..................... 336
18.1.4 Blood Group Typing Techniques.......................... 336
18.1.4.1 Lattes Crust Assay.. 336
18.1.4.2 Absorption–Elution Assay................................... 338
18.2 Forensic Protein Profiling.. 338
18.2.1 Methods.. 339
18.2.1.1 Matrices Supporting Protein Electrophoresis...... 340
18.2.1.2 Separation by Molecular Weight......................... 340
18.2.1.3 Separation by Isoelectric Point............................ 341
18.2.2 Erythrocyte Protein Polymorphisms..................... 342
18.2.2.1 Erythrocyte Isoenzymes..................................... 342
18.2.2.2 Hemoglobin.. 342

18.2.3 Serum Protein Polymorphisms 344
Bibliography 345

Chapter 19 Variable Number Tandem Repeat Profiling 353

19.1 Restriction Fragment Length Polymorphism 353
19.1.1 Restriction Endonuclease Digestion 354
19.1.2 Southern Transfer 356
19.1.3 Hybridization with Probes 357
19.1.3.1 Multilocus Probe Technique 357
19.1.3.2 Single-Locus Probe Technique 358
19.1.4 Detection 359
19.1.5 Factors Affecting RFLP Results 360
19.1.5.1 DNA Degradation 360
19.1.5.2 Restriction Digestion–Related Artifacts 361
19.1.5.3 Electrophoresis and Blotting Artifacts 362
19.2 Amplified Fragment Length Polymorphism 363
Bibliography 364

Chapter 20 Autosomal Short Tandem Repeat Profiling 369

20.1 Characteristics of STR Loci 369
20.1.1 Core Repeat and Flanking Regions 369
20.1.2 Repeat Unit Length 370
20.1.3 Repeat Unit Sequences 370
20.2 STR Loci Commonly Used for Forensic DNA Profiling 371
20.3 Forensic STR Analysis 375
20.3.1 Determining the Genotypes of STR Fragments 376
20.3.2 Interpretation of STR Profiling Results 376
20.3.2.1 Inclusion (Match) 376
20.3.2.2 Exclusion 376
20.3.2.3 Inconclusive Result 376
20.4 Factors Affecting Genotyping Results 376
20.4.1 Mutations 377
20.4.1.1 Mutations at STR Core Repeat Regions 377
20.4.1.2 Chromosomal and Gene Duplications 380
20.4.1.3 Point Mutations 381
20.4.2 Amplification Artifacts 382
20.4.2.1 Stuttering 382
20.4.2.2 Nontemplate Adenylation 383
20.4.2.3 Heterozygote Imbalance 383
20.4.2.4 Allelic Dropout 383
20.4.3 Electrophoretic Artifacts 384
20.4.3.1 Pull-Up Peaks 384
20.4.3.2 Spikes 384
20.5 Genotyping of Challenging Forensic Samples 384
20.5.1 Degraded DNA 384

20.5.2 Low Copy Number DNA Testing 386
20.5.3 Mixtures 386
Bibliography 389

Chapter 21 Sex Chromosome Haplotyping and Gender Identification 407

21.1 Y Chromosome Haplotyping 407
21.1.1 Human Y Chromosome Genome 407
21.1.1.1 Pseudoautosomal Region 407
21.1.1.2 Male-Specific Y Region 407
21.1.1.3 Polymorphic Sequences 408
21.1.2 Y-STR 409
21.1.2.1 Core Y-STR Loci 410
21.1.2.2 Multilocal Y-STR Loci 411
21.1.2.3 Rapidly Mutating Y-STR 411
21.2 X Chromosome Haplotyping 412
21.3 Sex Typing for Gender Identification 416
21.3.1 Amelogenin Locus 416
21.3.2 Other Loci 418
Bibliography 419

Chapter 22 Single Nucleotide Polymorphism Profiling 437

22.1 Basic Characteristics of SNPs 437
22.2 Forensic Applications of SNP Profiling 438
22.2.1 *HLA-DQA1* Locus 438
22.2.1.1 DQα AmpliType and Polymarker Assays 438
22.2.1.2 Allele-Specific Oligonucleotide Hybridization 440
22.2.2 Current and Potential Applications of SNP Analysis 443
22.2.2.1 Application of SNP Analysis for Forensic Identification 443
22.2.2.2 Potential Applications of SNPs for Phenotyping 444
22.3 SNP Techniques 444
22.3.1 Next-Generation Sequencing Technologies 444
22.3.2 DNA Samples, Sequencing Library, and Template Preparation 446
22.3.3 NGS Chemistry 447
22.3.4 NGS Coverage 447
Bibliography 451

Chapter 23 Mitochondrial DNA Profiling 461

23.1 Human Mitochondrial Genome 461
23.1.1 Genetic Contents of Mitochondrial Organelle Genomes 461
23.1.2 Maternal Inheritance of mtDNA 463
23.2 mtDNA Polymorphic Regions 463
23.2.1 Hypervariable Regions 463
23.2.2 Heteroplasmy 463

23.3 Forensic mtDNA Testing 465
  23.3.1 General Considerations 465
  23.3.2 mtDNA Screen Assay 466
  23.3.3 mtDNA Sequencing 467
    23.3.3.1 PCR Amplification 467
    23.3.3.2 DNA Sequencing Reactions 468
    23.3.3.3 Electrophoresis, Sequence Analysis, and Mitotype Designations 471
  23.3.4 Interpretation of mtDNA Profiling Results 472
    23.3.4.1 Exclusion 474
    23.3.4.2 Cannot Exclude 474
    23.3.4.3 Inconclusive Result 474
Bibliography 474

SECTION V Forensic Issues

Chapter 24 Forensic DNA Databases: Tools for Crime Investigations 485
24.1 Brief History of Forensic DNA Databases 485
24.2 Infrastructure of CODIS 485
24.3 Indexes of CODIS 487
24.4 Database Entries 489
24.5 Database Expansion 490
24.6 DNA Profiles 491
24.7 Routine Database Searches for Forensic Investigations 492
  24.7.1 Case-to-Offender Searches 492
  24.7.2 Case-to-Case Searches 493
  24.7.3 Search Stringency and Partial Matches 493
24.8 Familial Searches 495
  24.8.1 Legal and Ethical Issues of Familial Search 495
  24.8.2 Familial Search Strategies 496
    24.8.2.1 Identity-by-State and Kinship Index Method 496
    24.8.2.2 Focusing on Rare Alleles 496
    24.8.2.3 Excluding Candidates through Y-STR Screening 498
Bibliography 498

Chapter 25 Evaluation of the Strength of Forensic DNA Profiling Results 503
25.1 A Review of Basic Principles of Genetics 503
  25.1.1 Mendelian Genetics 503
  25.1.2 Population Genetics 504
    25.1.2.1 Allele Frequency 504
    25.1.2.2 Genotype Frequency 504
    25.1.2.3 Heterozygosity 504
    25.1.2.4 Hardy–Weinberg Principle 505
    25.1.2.5 Testing for HW Proportions of Population Databases 505
    25.1.2.6 Probability of Match 511

25.2 Statistical Analysis of DNA Profiling Results....512
  25.2.1 Genotypes....513
    25.2.1.1 Profile Probability....513
    25.2.1.2 Likelihood Ratio....516
  25.2.2 Haplotypes....516
    25.2.2.1 Mitotypes Observed in Database....518
    25.2.2.2 Mitotype Not Observed in Database....518
Bibliography....518

Chapter 26 Quality Assurance and Quality Control....523

26.1 US Quality Standards....523
26.2 International Quality Standards....524
26.3 Laboratory Accreditation....525
26.4 Laboratory Validation....525
26.5 Proficiency Testing....526
26.6 Certification....526
26.7 Forensic DNA Analyst Qualifications....527
26.8 Code of Ethics of Forensic Scientists....528
Bibliography....529

Index....533

Preface

Since the first edition of this book, new developments in forensic biology have led to a rapid expansion of the knowledge of the field. Therefore, it is necessary to create a new edition. This edition provides updates in most chapters of the original edition. Additionally, three new chapters (Chapters 2, 16, and 17) have been added and approximately 200 new figures have been created for this edition. Just like the first edition of this book, the new edition aims to inspire an undergraduate audience to tackle new challenges in the forensic biology field. It is written specifically to provide a general understanding of forensic biology and assist students in becoming more knowledgeable about the field of forensic biology and the wealth of available information. My readers should find that this edition of the book contains useful information, presented in a way that is more easily understood. Hopefully, it will be utilized by students, particularly those interested in forensic biology, to further enhance their education and training. I will continue to be open to suggestions in the future.

Richard C. Li
John Jay College of Criminal Justice
City University of New York
New York, NY

Acknowledgments

Many people contributed to this book. I would like to thank my family members for their support during the many hours I spent sitting in front of my computer. I would like to thank Jan Li for spending numerous hours assisting with the completion of this book by handling tasks such as image preparation and text editing. I would also like to thank Zully Santiago and Robert Greco for their proofreading of the manuscript. Additionally, I must acknowledge that my students at John Jay College of Criminal Justice provided excellent comments, suggestions, and even a few criticisms. The editorial and production staff at Taylor & Francis Group should also be acknowledged for their contributions. I would like to thank Mark Listewnik and Becky Masterman, senior acquisitions editors, for excellent suggestions and support, as well as project editor Richard Tressider for helping to keep the project on track. I would also like to thank Michelle van Kampen, project manager at Deanta Global Publishing Services, for overseeing the production of the book.

Author

Richard Li earned his MS in forensic science from the University of New Haven and his PhD in molecular biology from the University of Wisconsin–Madison. After completing his PhD, Dr. Li was awarded a postdoctoral fellowship at Weill Medical College of Cornell University and subsequently worked as a research faculty member at the School of Medicine of Yale University. Dr. Li has served as a criminalist at the Department of Forensic Biology, the Office of Chief Medical Examiner of New York City. For the past decade, he has held faculty positions in forensic science programs in the United States. Currently, Dr. Li is an associate professor of forensic biology at John Jay College of Criminal Justice. Additionally, he serves as a faculty member for the PhD program in forensic science for the college. Dr. Li's current research interests include the identification and analysis of biological specimens that are potentially useful for forensic investigations.

Introduction

This text defines forensic biology as analyses performed in the forensic biology sections of forensic laboratories and thus focuses on forensic serology and forensic DNA analysis. The aim of this book is to emphasize the basic science and its application to forensic science in an effort to make the principles more understandable. In addition, it introduces the language of forensic biology, thus enabling students to become comfortable with its use, and it provides clear explanations of the principles of forensic analysis.

To convey a general understanding of the concepts of forensic biology, it is necessary to include explanations of various techniques that are utilized in the field. The intent is to provide students with a scientific grounding in the area of forensic biology by offering an introduction to methods and techniques utilized by forensic biology laboratories. The techniques introduced in this text are accompanied by brief background descriptions and discussions of basic principles and techniques. Schematic illustrations are included where necessary. The text also acknowledges the benefits and limitations that apply to forensic biology techniques. Forensic techniques that were used in the past are also described. Learning past examples of forensic tests can help students to review historical forensic cases.

This text contains five modules, organized by section: Section I, Biological Evidence (Chapters 1–4); Section II, Basic Techniques in Forensic Biology (Chapters 5–11); Section III, Identification of Biological Evidence (Chapters 12–17); Section IV, Individualization of Biological Evidence (Chapters 18–23); and Section V, Forensic Issues (Chapters 24–26). The 26 chapters are designed to be covered in a single-semester course.

SECTION I

Biological Evidence

1

Crime Scene Investigation of Biological Evidence

A forensic investigation involving biological evidence usually begins at the crime scene. The crime scene investigation process includes maintaining scene security, preparing documentation, and collecting and preserving physical evidence. A crime scene investigation requires teamwork and effort. Each team member should be assigned specific tasks (Figure 1.1).

1.1 Protection of Crime Scene

A crime scene investigation begins with the initial response to a scene (Figure 1.2). Securing and protecting the scene are important steps in a crime scene investigation (Figures 1.3 through 1.6), and this task is usually carried out by the first responding officer arriving on the scene. The entry of authorized personnel admitted to the scene should be documented using a log sheet (Figure 1.7). Suspects, witnesses, and living victims should be evacuated from the scene. If a victim is wounded, medical attention should be sought.

Appropriate supplies and devices should be used to prevent the contamination of evidence by investigators. Protective wear and devices including a face mask or shield, safety eyeglasses, a disposable coverall bodysuit, gloves, shoe covers, and a hairnet should be used (Figures 1.8 and 1.9). Exposure to bodily fluids may occur during a crime scene investigation. An investigator can be exposed to bodily fluids through the mucous membranes, skin exposure, and needlestick injuries (especially when investigating a clandestine drug laboratory scene). Therefore, biosafety procedures must be followed for the protection of personnel from infectious blood-borne pathogens such as the human immunodeficiency virus (HIV), hepatitis B virus (HBV), and hepatitis C virus (HCV); infectious aerosol tuberculosis pathogens; and other biohazardous materials.

1.2 Recognition of Biological Evidence

A preliminary survey should be carried out to evaluate potential evidence. In particular, the recognition of evidence plays a critical role in solving or prosecuting crimes. The priority of the potential evidence at crime scenes should be assessed based on each item's relevance to the solution of the case. Higher priority should be assigned to evidence with probative value to the case. For example, the evidence related to a *corpus delicti* is considered to be of the highest priority. *Corpus delicti* is a Latin term meaning "body of crime." In Western law, it primarily refers to the principle that in order for an individual to be convicted, it is necessary to prove the occurrence

N.Y.P.D.
POLICE
CRIME SCENE
UNIT
N.Y.P.D.
POLICE
CRIME SCENE
UNIT

Figure 1.1 A crime scene investigation team. (© Richard C. Li.)


POLICE
CRIME SCENE UNIT
NYPD

Figure 1.2 A crime scene unit vehicle that is used to respond to crime scenes. This type of vehicle is usually outfitted with devices and supplies that investigators need when processing a crime scene, as well as evidence packaging materials, fingerprint collection kits, and DNA collection kits. Additionally, it can be equipped with a workstation for computer access, a refrigerator for storing chemicals, and a compact fuming hood for processing latent fingerprints, as well as equipment cabinets and drawers. (© Richard C. Li.)


CRIME SCENE DO NOT CROSS
CRIME SCENE DO NOT CROSS

Figure 1.3 Crime scene barrier tape is used to ensure that only investigators are admitted to the scene. (Courtesy of H. Brewster.)


FBI
POLICE
POLICE DEPARTMENT
NY

Figure 1.4 A police officer guards the crime scene. (© Richard C. Li.)



Figure 1.5 Crime scene privacy screen and tent. The screen (top) and the tent (bottom) are useful devices for shielding the evidence or body from viewing by unauthorized personnel. (© Richard C. Li.)



Figure 1.6 Barricades are set up to keep crowds at a distance from the scene. (© Richard C. Li.)

of the crime. In a forensic investigation, it also refers to the physical evidence proving that a crime was committed. For example, when an individual is missing, a missing persons investigation is usually initiated. If *corpus delicti*, such as a dead body or a victim's blood at a crime scene (Figure 1.10), is discovered during the investigation, a homicide case can be established and a suspect can be charged with homicide. Higher priority should also be attached to evidence that can establish connections such as *victim-to-perpetrator linkage*. For example, items found in a perpetrator's possession may be linked to a victim. This also applies to transfer evidence based on the principles of transfer theory, also known as the *Locard exchange principle*, which theorizes that the cross-transfer of evidence occurs when a perpetrator has any physical contact with an object or another person (Figures 1.11 through 1.14). Thus, trace evidence, such as hairs and fibers, may be transferred from a perpetrator to a victim or vice versa. This explains why it is important to ensure that perpetrators and their belongings are thoroughly searched for trace evidence. Likewise, victims and their belongings should be examined for the same reason.

Victim-to-scene and perpetrator-to-scene linkages can also be established. Blood belonging to a perpetrator or a victim found at a crime scene can establish such a linkage (Figure 1.15). Additionally, reciprocal transfers of trace evidence from crime scenes can be used to link a suspect or a victim to a crime scene. A perpetrator may present a unique *modus operandi* (MO). *Modus operandi*, a Latin term commonly used in criminal investigations, refers to a particular pattern of characteristics and the manner in which a crime is committed. For example, Richard Cottingham, a serial killer known as "the torso killer," dismembered his victims and took their limbs and heads with him but left their torsos at the scene. He then set the rooms on fire before



Crime Scene Processing

1: Date ______/______/______ 2: Arrival Time: ____________ HRS

3: Assigned Criminalist ______________ 4: Assisting Criminalist(s) ________________

5: Supervisor ________________________________ Present ___Yes ___No

6: [redacted] Case Number [redacted] ___-_____________

7: Individual/Agency Requesting Investigation ______________________________

8: Location Address ____

a. Type of Scene ___Indoor ___Outdoor
b. Scene Secured ___Yes ___No
c. Weather Conditions ____
____

9: Other Personnel	Shield #	Agency	Arrival	Departure
			HRS	HRS
			HRS	HRS
			HRS	HRS
			HRS	HRS
			HRS	HRS
			HRS	HRS
			HRS	HRS
			HRS	HRS
			HRS	HRS
			HRS	HRS
			HRS	HRS
			HRS	HRS
			HRS	HRS
			HRS	HRS
			HRS	HRS
			HRS	HRS
			HRS	HRS
			HRS	HRS
			HRS	HRS
			HRS	HRS

10: Departure Time __________ HRS

Figure 1.7 An example of a log sheet for documenting authorized personnel at a crime scene. (© Richard C. Li.)

fleeing the scenes. Evidence that provides information on the MO is also vital to an investigation. A distinct MO can establish a *case-to-case linkage* for serial offender cases.

1.3 Searches

Some investigations require a search for specific items of evidence such as biological stains, human remains, and all relevant evidence. A search usually has a specific purpose. Thus, the use of search patterns can be helpful, especially in cases involving large outdoor crime scenes.



Figure 1.8 Personal protection wear and devices that are used at crime scenes. (© Richard C. Li.)



Figure 1.9 Disposable glove (left) and glove with extended cuff (right). (© Richard C. Li.)

Search patterns may include a grid, line, or zone (Figures 1.16 and 1.17). The method that is ultimately used depends on the type and size of the scene (Figures 1.18 through 1.20). Additionally, the points of entry and exit and the paths followed by a perpetrator should also be searched.

Searching for biological stains usually utilizes devices such as an alternate light source (ALS); see Figures 1.21 and 1.22. An ALS either produces a single specific wavelength of light or a desired wavelength by using specific filters. Biological materials such as blood, semen, and saliva emit fluorescent light under an ALS, which can facilitate the locating of biological materials. Additionally,



Figure 1.10 Photographic documentation of bloodstains on clothing. (© Richard C. Li.)



Figure 1.11 An electrostatic dust print lifting device can be utilized for processing impression evidence such as footprints and tire tracks. (© Richard C. Li.)


Voltage supply
Metallic side of lifting film
Plastic side of lifting film
Item in question
Ground plate

Figure 1.12 Basic components of an electrostatic dust print lifting device. The lifting film is placed on top of the item in question with the plastic side against the surface and the metallic side facing up. A ground plate is placed directly on the ground. The lifting film and ground plate are connected to the voltage supply apparatus. Once the charging voltage is turned on, the static charge transfers the dust particles from the surface to the plastic side of the lifting film. (© Richard C. Li.)



Figure 1.13 A high-intensity light-emitting diode (LED) device for locating evidence at a crime scene is particularly effective in highlighting trace evidence such as hairs, fibers, and shoe prints. (© Richard C. Li.)



Figure 1.14 A hair found on a victim's clothing can be transferred evidence from a suspect. (© Richard C. Li.)



Figure 1.15 Finding a victim's blood on a suspect's clothing can establish a link between them. (© Richard C. Li.)



Figure 1.16 Grid search pattern for an outdoor scene. The investigators and anthropologists present are searching for human bone evidence within the grid. (Courtesy of H. Brewster.)



Figure 1.17 Line search pattern for an outdoor scene. (Courtesy of H. Brewster.)



Figure 1.18 Using ground-penetrating radar (GPR) to locate clandestine graves of homicide victims. GPR uses electromagnetic waves emitted from a transmitter, which are detected by a receiver to locate clandestine burials and buried objects such as weapons embedded in soils. Images of the potential evidence are typically obtained by moving the antenna of the GPR device over the surface of the ground. (© Richard C. Li.)



Figure 1.19 Using cadaver-sniffing dogs to alert investigators to the presence of buried bodies. The odor produced by the decomposition of the human body may be sensed by cadaver-sniffing dogs. Odor-absorbing pads absorb and retain the scent of decomposed remains and can be placed at the scene for several days. Upon sniffing the pads, a cadaver dog may indicate the presence of buried human remains or may indicate that human remains were once buried in that location. However, it is not clear that this technique is reliable. (© Richard C. Li.)

MADISON
CONSTABLE SAR K9

Figure 1.20 Tracking dog for searching suspects. In a situation of processing a recent crime scene when the suspect may be in close vicinity to the scene, a tracking dog can be used. A tracking dog, such as a bloodhound, can potentially follow the scent from items left at the scene to locate a suspect nearby. (© Richard C. Li.)



Figure 1.21 Compact alternate light source devices, which are intended specifically for use at crime scenes, reduce search time and improve the recovery of evidence such as biological evidence and chemically enhanced latent fingerprints. (© Richard C. Li.)



Figure 1.22 LED light sources provide illumination for locating evidence such as bodily fluid stains, hair, or fibers. (© Richard C. Li.)



Figure 1.23 An example of a compact Rapid DNA device for processing DNA evidence in the field. (© Richard C. Li.)



Automobile Backing Card

Case # ________
Address of Incident: ________
Prints lifted by: ________
Badge # ________
Type of crime: ________
Victim name: ________
Suspect name: ________
Location of prints lifted: ________
Lift # ________

Year/Make: ________
Model: ________
Color: ________
Tag state # ________
VIN # ________

Circle Number Where Prints Found

FRONT
3
4
5
6
7
8
2
17
18
19
9
1
10
16
15
14
13
12
11

☐ Front Windshield ☐ Rear Window ☐ Windows

Date ______ Case No. ______
Offense ________
Victim ________
Address of Incident ________
Location of Prints Lifted ________
Prints Lifted By ________
Badge No. ________
Lift No. ________

SPEX FORENSICS • 800-657-SPEX

SKETCH AND/OR REMARKS

Place Print on Reverse Side

Figure 1.24 An example of sketch documentation. (© Richard C. Li.)

field tests and enhancement reagents can be used to facilitate crime scene searching (Chapter 12). These reagents can detect and identify biological evidence. The tests are very simple, rapid, and sensitive, and thus can be used at crime scenes. For example, phenolphthalin and leucomalachite green tests can be used for detecting blood evidence. Sometimes, minute amounts of blood may be



Figure 1.25 Sketches for documenting the sites of fingerprints. (© Richard C. Li.)

present at the scene as a result of attempts to clean up blood prior to the investigation. These stains may not be visible with the naked eye. Enhancement reagents such as luminol and fluorescein, which emit chemiluminant and fluorescent light upon reacting with certain biological materials, respectively, can be used. Additionally, the enhancement reagents can detect faint blood-containing pattern evidence such as faint bloody fingerprints, footprints, and other pattern evidence of physical contact such as drag marks in blood. However, precaution should be taken since these reagents are not usually very specific to blood. Certain substances such as bleach, various metals, and plants may also lead to chemical reactions with the field tests and the enhancement reagents. In these cases, the evidence collected is further tested with laboratory examination and analysis.

Recently, portable and field-deployable instruments have been developed that are capable of processing buccal swabs and potentially other evidence to produce a DNA profile on-site (Figure 1.23). It is a fully automated process, using the Rapid DNA technology (Chapter 8), that



Figure 1.26 A reflected ultraviolet imaging system (RUVIS) imager for documenting close-up views of evidence such as latent fingerprints. (© Richard C. Li.)



Figure 1.27 Scales for photographic documentation. Regular scales (top) can be used with visible light sources. Fluorescence scales (bottom) can be used for the documentation of fluorescing evidence after certain treatment, such as chemical enhancement, using alternate light sources. (© Richard C. Li.)

can be completed within 2 h by a trained crime scene investigator or police officer. These instruments may provide a new tool for expediting the identification of suspects and developing investigative leads at the scene. Additionally, this technology can enable law enforcement agents to rapidly determine whether the crimes were isolated incidents or part of serial crimes committed by the same offender, such as in serial burglary and arson cases. It can also be used in the identification of human remains in mass disasters.

1.4 Documentation

The conditions at a crime scene, including both the individual items of evidence and the overall scene, must be documented to provide vital information for investigators and for the courts. The most common documentation methods are drawing sketches and taking photographs and videographs. The sketch is to reflect the positions and the spatial relationships of items and persons with measurements using a scale. An investigator usually prepares a rough sketch first and later converts the rough sketch into a finished sketch (Figures 1.24 and 1.25). If bloodstains are present at the scene, the location of bloodstain patterns should be emphasized. Prior to handling and moving evidence, photographs should be taken with different views: an overall view of the entire scene, a medium-range view showing the positions and the relationships of items, and a close-up



Figure 1.28 Photographic documentation of bloodstain patterns. (© Richard C. Li.)

view showing details of the evidence (Figure 1.26). Photographs should also include a measuring device such as a scale (Figure 1.27) to accurately depict the sizes of items such as bloodstains or bite marks. This can be achieved simply by placing a ruler adjacent to the evidence when it is photographed (see Figure 1.28). A photograph log sheet can be used to record the chronological order of crime scene photographs and to note filming conditions and any additional relevant information (Figure 1.29). Similar documentation should be prepared for videographs when appropriate. Additionally, written or audio-recorded notes can be used. Notes should include complete and accurate information of a crime scene investigation, such as the case identifier number, the identities of the investigators, and a description of the scene or items (e.g., location, size, and shape). Additionally, any disturbance of evidence occurring during crime scene processing should be noted.

1.5 Chain of Custody

Custody information should be recorded at each event when evidence is handled or transferred by authorized personnel. Usually, a custody form listing a specific evidence item is used to document the chain (Figure 1.30). Each individual who acquires custody of the evidence must sign a chain of custody document. An incomplete chain of custody may lead to an inference of possible tampering or contamination of evidence. As a result, the evidence may not be admissible in court.



Photography Log

Date: _____/_____/_____ Case Number: _____-_______ Criminalist ________________

Roll # _______________ Film Type & ASA: ______________________________

EXP	Lens	*f*-stop	Category	Description
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				
31				
32				
33				
34				
35				
36				
37				

Figure 1.29 Crime scene photography log. (© Richard C. Li.)

1.6 Collection of Biological Evidence

After the crime scene documentation is completed, the collection of evidence can be initiated. Small or portable items, such as bloodstained knives, can be collected and submitted to a crime laboratory (Figure 1.31). Large or unmovable items of evidence (Figure 1.32) can be collected and submitted in sections, such as a section of wall where bloodstains are located. Table 1.1 and Figures 1.33 through 1.38 summarize and illustrate representative collection techniques. Specific care is required for the collection of biological evidence in the following situations:

- *Bloodstain pattern evidence*: It is especially important to thoroughly document the bloodstain pattern evidence at a crime scene prior to collection. Bloodstain patterns can be especially useful in crime scene reconstruction.


EVIDENCE
CHAIN OF CUSTODY
EVIDENCE
EVIDENCE
CHAIN OF CUSTODY
EVIDENCE

Figure 1.30 Labels with the chain of custody that are used for marking the evidence contained in the packaging. (© Richard C. Li.)


EVIDENCE/PROPERTY
Agency
Case No.
Item No.
Offense
Suspect
Victim
Date and Time of Recovery
Recovered By
Description and/or Location
Sealed By
Date
CHAIN OF CUSTODY
FROM
TO
DATE
SIRCHIE

Figure 1.31 Handling sharp objects. Bloodstained knives collected and submitted to laboratories (top) and a box for packing sharp objects (bottom). (© Richard C. Li.)



Figure 1.32 A section of bloodstained carpet is collected. (© Richard C. Li.)

- *Multiple analysis of evidence*: If multiple analyses are needed for a single item of evidence, nondestructive analyses should be carried out first. For example, a bloody fingerprint should be collected for ridge detail analysis prior to collecting blood for DNA analysis.
- *Trace evidence*: Trace evidence such as hairs and fibers can be present in bloodstained evidence and should be identified and properly collected.
- *Control samples*: Control (known or blank) samples should be collected from a control area (e.g., unstained area near a collected stain).
- *Size of stain*: Polymerase chain reaction (PCR)-based forensic DNA techniques are highly sensitive and allow for the successful analysis of very small bloodstains. All bloodstains, even if they are barely visible, should be collected at a crime scene.
- *Wet evidence*: Wet evidence should be air-dried (without heat) prior to packaging to prevent the degradation of proteins and nucleic acids, which are used for forensic serological and DNA analysis.

1.7 Marking Evidence

The marking of evidence is necessary for identification purposes so that it can be quickly recognized even years later (Figure 1.39). An investigator’s initials, the item number, and the case number are usually included in marking. Information can be marked on a tag, a label attached to the item, or directly on garment evidence. The marking of evidence should not be proximal to bullet holes or biological stains to prevent the mark from interfering with analyses.

1.8 Packaging and Transportation

Packaging is intended to protect and preserve evidence. All evidence should be secured and protected from possible contamination. Fragile items should be protected to prevent any damage during transportation. Exposure to heat and humidity should be avoided to protect biological evidence from degradation during transport. Various packaging methods are available

Table 1.1 Methods for Collecting Biological Evidence

Type of Evidence	Condition	Method of Collection	Procedure
Blood	Dry	Swab	Best on nonabsorbent surfaces; lightly moisten sterile swab with distilled or sterile water, rub over stain while rotating; allow to air-dry; a combination of first a moistened swabbing followed by second a dry swabbing (both swabs submitted) is recommended
		Cutting	Cut stain from item
		Scraping	Scrape bloodstain into a clean piece of paper using a clean blade; wrap sample using druggist's fold
		Lifting	Works for nonabsorbent surfaces; use fingerprint lifting tape that does not interfere with DNA testing to lift stain; lifted stain should be covered with a piece of lifter's cover
		Collect entire item	Collect if item contains bloodstain pattern; difficult to swab; requires multiple exams
	Wet	Swab	Absorb blood sample onto sterile cotton swabs; stain should be concentrated on tip and allowed to air-dry
		FTA paper	Use a sterile disposable pipet to collect liquid blood; spot on FTA paper; allow to air-dry
	Reference liquid blood sample	Venous blood collection	Collect blood in a purple-topped vacutainer tube containing ethylenediaminetetraacetic acid (EDTA) anticoagulant; refrigerate but never freeze
Semen	Dry or wet	See "Blood" above	See "Blood" above
	Condom	Collect entire item	Secure condom with a tie and place in a container in a refrigerator; submit to laboratory as soon as possible
	Various conditions	Victim sexual assault kit	Standardized kit to collect biological evidence from the body of a victim includes swabs, microscope slides, and envelopes
	Various conditions	Suspect standard kit	Standardized kit to collect biological evidence from the body of a suspect includes swabs, microscope slides, and envelopes

(continued)

Table 1.1 (Continued) Methods for Collecting Biological Evidence

Type of Evidence	Condition	Method of Collection	Procedure
Victim vaginal fluid	Dry or wet	See “Blood” above	Often collected from a suspect’s pubic area or fingers
Saliva	Dry or wet	See “Blood” above	Often collected from a bite mark or a victim’s pubic area
	Reference saliva (buccal) samples	Swab	Swab the inside of the cheek using two swabs, rotating them during collection; allow swabs to air-dry
		Filter paper	Place donor saliva sample on marked area of filter paper; allow to air-dry
Hairs	Head and pubic hairs	Lifting	Refer to dry bloodstain lifting method
		Transfer	Use forceps to transfer hair onto a piece of paper that can be folded
		Vacuum	Vacuum can be used if necessary; generally not recommended
Fingernails and scrapings	Various conditions	Clipping	Use a clean clipper to clip nails onto clean paper; wrap samples using druggist’s fold
		Scraping	Scrape undersides of nails onto clean paper; wrap samples using druggist’s fold
Bones	Various conditions	Freeze in container	Collect if blood is not available; collect bone with marrow if available; rib bone and vertebrae are preferred; place specimen in a container and freeze if wet
Teeth	Various conditions	Container	Collect teeth with dental pulp if possible into a container
Tissues and organs	Wet	Freeze in a container	Collect if blood is not available; place specimen in a container and freeze
DNA database samples	Various conditions	Various	Follow jurisdiction protocol for collecting samples from arrested individuals or convicted offenders or both

Source: Fisher, B., *Techniques of Crime Scene Investigation*, 7th edn., 2004, CRC Press, Boca Raton; Lee, H.C. et al., *Henry Lee’s Crime Scene Handbook*, 2001, Academic Press, San Diego; National Institute of Justice. Using DNA to solve cold cases, Special Report, 2002, US Department of Justice, Office of Justice Programs, Washington, DC.

Note: Samples requiring refrigeration or freezing are noted; other samples may be stored at room temperature. Dry evidence should be packed in a porous material such as paper (envelope, bag, box) as described in the text.


TX100
SEXUAL ASSAULT EVIDENCE COLLECTION KIT

Figure 1.33 Evidence collection kits. Sexual assault evidence collection kit (top). Paternity evidence collection kit (bottom). (© Richard C. Li.)



Figure 1.34 Various types of swabs that are used for collecting biological evidence. (© Richard C. Li.)



Figure 1.35 Fingernail swabbing for recovering evidence. Fingernail swabs are often collected from individuals who are involved in a struggle in violent crimes and in digital penetration in sexual assault cases. Fingernail swabs are sampled separately from both hands. (© Richard C. Li.)

depending on the type of evidence handled (Figures 1.40 through 1.42). The following are general considerations related to the packaging of evidence:

- *Evidence from different sources*: To prevent the transfer of evidence from different sources, items of evidence should not be grouped in a single package. However, evidence may be packed in a single container if the items were found together.
- *Folding of evidence*: Folding of clothing, especially items with wet bloodstains, can transfer evidence from one part of a garment to another. If a large, dry garment must be folded, a piece of clean paper should be placed between different parts of the garment to avoid direct contact between the different parts of the garment, thereby preventing the transfer of evidence.
- *Packing materials*: Envelopes, bags, and boxes that are made of porous materials such as paper are appropriate for packaging dry biological evidence. Dry, bloodstained evidence should not be sealed in plastic bags or containers that trap moisture.
- *Liquid evidence*: Tubes containing liquid such as blood should not be frozen because the volume of a liquid expands in freezing temperatures and this expansion may lead to cracking. Tubes should be placed in plastic bags to prevent leaks in case of



Figure 1.36 Hand bags for protecting the hands of a decedent in an alleged suicide. Gunshot residue can be found on hands after firing a weapon (top). The bagging of the hands, using paper bags and wide rubber bands, prevents the loss of gunshot residue during the transportation of the body (bottom). (© Richard C. Li.)

accidental breakage. Liquid evidence should be transported and submitted to a laboratory as soon as possible after the collection of evidence.

- *Trace evidence*: All such evidence should be wrapped in paper with a druggist's fold (Figure 1.43). The wrapped trace evidence can be packed in an envelope.

Packaged evidence should be properly labeled with a description of the evidence and sealed with evidence tape. It is important for the person packaging the evidence to initial and date across the seal to show authenticity (Figure 1.44). A seal should not be cut when a sealed evidence bag is opened. Instead, an opening can be created by cutting at an area distal from the existing seal. After analysis is complete, the evidence packaging should be resealed. Table 1.1 summarizes additional steps for packaging evidence.

1.9 Final Survey and the Release of the Crime Scene

During a final survey, a discussion with all personnel in the crime scene investigation team should be carried out to thoroughly review all aspects of the search. It is important to ensure



Figure 1.37 Blood cards are typically used for collecting blood evidence from a known source such as a suspect or a victim (top). A manual hole punch can be used to create a blood card punch for DNA extraction. Blood samples are air-dried on blood cards for storage (bottom). (© Richard C. Li.)



Figure 1.38 Application of Flinders Technology Associates (FTA) filter paper for the collection of biological evidence. (a) Biological fluid with cells is applied to FTA paper. (b) Cells are lysed and DNA is immobilized on FTA paper. (c) Cellular materials are washed away and DNA remaining on the FTA paper can be used for forensic testing. (© Richard C. Li.)



Figure 1.39 Photographic documentation of a knife. Note the evidence tag. (© Richard C. Li.)



EVIDENCE
CRIME SCENE UNIT

CRIME: Homicide		DATE 12/8/99
LOCATION: 446 Rogers Ave		
EVIDENCE(Type): 2 Blood Samples + 2 Control Samples		DS # 1 + DS-1A DS-2 + DS-2A
LOCATION RECOVERED: IN Store		VOUCHER # K112668
C.S.U. RUN # 99/2518	61 # 13179	PCT. # 77

C.S.U. INVEST. [redacted] 5603
ASSIGN [redacted] 46

Figure 1.40 Evidence containing dried bodily fluid stains is packed in a paper bag. (© Richard C. Li.)



Figure 1.41 Alleged diluted blood collected from a pipe (left) and placed in plastic containers (right). (© Richard C. Li.)



Figure 1.42 Evidence pouch. The front of the pouch is transparent for viewing the content. The back of the pouch is made of breathable materials allowing wet evidence, such as swabs, to dry inside the pouch. (© Richard C. Li.)



Figure 1.43 An example of a druggist's fold. Trace evidence should be deposited in the center (colored area) of the paper. (© Richard C. Li.)



Figure 1.44 Proper marking of sealed evidence. Note that the evidence packaging was cut a second time and resealed at a different location than that of the preexisting seal. (© Richard C. Li.)

that the scene has been searched correctly and completely, and that no area has been missed or overlooked. All documentation including the chain of custody document must be complete and all evidence should be collected, packed, documented, and marked. Photographs of the final condition of the scene should be taken. Once the final survey is completed, the crime scene can be released. Reentry into the crime scene may require a search warrant after the scene is released. Crime scene release documentation usually includes the time and date of release, to whom it is released, and by whom it is released.

1.10 Crime Scene Reconstruction

Crime scene reconstruction is the scientific process of determining the sequence of events and actions that occurred prior to, during, and after a crime. Reconstruction is carried out based on the information from the crime scene observations and the laboratory examination of physical evidence. The overall scientific process in reconstruction usually involves several steps. The process usually begins with the formulation of questions related to the problems that need to be solved. The questions can refer to the explanation of the specifics of the crime, for instance, “Where was the shooter’s position when the shooting occurred?,” “Where was the victim’s position when shot?,” and “What is the muzzle-to-target distance during the shooting?” In order to conduct a thorough crime scene reconstruction, all useful information is collected for review, such as photographs, videotapes, notes, sketches, autopsy reports, and analysis reports of the physical evidence. A hypothesis is then constructed based on the information obtained, which may explain the events and actions involved in a crime. The next step is making predictions that determine the logical consequences of the hypothesis. One or more predictions are selected for testing. The hypothesis is tested by conducting reconstruction experiments. One example of a reconstruction test is bloodstain pattern reconstruction in violent crimes (Chapter 2). Other examples of reconstruction may include trajectory and shooting, glass fracture, and accident reconstruction. The final step is to analyze experimental data and draw a conclusion. The experimental data are analyzed to see if the hypothesis is true or false. Additionally, the interpretation of physical evidence analysis, witness and confession statements, and investigative information should also be considered.


Crime scene information
Question formulation
Information collection
Hypothesis construction
Prediction making
Reconstruction testing
Data analysis and drawing conclusions
Theory developing and case solving

Figure 1.45 The scientific process of crime scene reconstruction. (© Richard C. Li.)

If the results of the experiment are consistent with the hypothesis, a theory can be developed that is intended to provide valuable information to the investigation and future prosecution of a case. Sometimes, forensic scientists may find that the hypothesis is inconsistent with the test results. In that case, an alternative hypothesis needs to be constructed to initiate another reconstruction process. Figure 1.45 illustrates the scientific process of crime scene reconstruction.

Bibliography

Ackermann, K., K.N. Ballantyne, and M. Kayser, Estimating trace deposition time with circadian biomarkers: A prospective and versatile tool for crime scene reconstruction. *Int J Legal Med*, 2010, **124**(5): 387–395.

Adderley, R. and J.W. Bond, The effects of deprivation on the time spent examining crime scenes and the recovery of DNA and fingerprints. *J Forensic Sci*, 2008, **53**(1): 178–182.

Barash, M., A. Reshef, and P. Brauner, The use of adhesive tape for recovery of DNA from crime scene items. *J Forensic Sci*, 2010, **55**(4): 1058–1064.

Benschop, C.C., et al., Post-coital vaginal sampling with nylon flocked swabs improves DNA typing. *Forensic Sci Int Genet*, 2010, **4**(2): 115–121.

Bond, J.W. and C. Hammond, The value of DNA material recovered from crime scenes. *J Forensic Sci*, 2008, **53**(4): 797–801.

Brownlow, R.J., K.E. Dagnall, and C.E. Ames, A comparison of DNA collection and retrieval from two swab types (cotton and nylon flocked swab) when processed using three QIAGEN extraction methods. *J Forensic Sci*, 2012, **57**(3): 713–717.

Buck, U., et al., Accident or homicide—Virtual crime scene reconstruction using 3D methods. *Forensic Sci Int*, 2013, **225**(1–3): 75–84.

Byard, R.W., et al., "Murder-suicide" or "murder-accident"? Difficulties with the analysis of cases. *J Forensic Sci*, 2010, **55**(5): 1375–1377.

Castello, A., F. Frances, and F. Verdu, Solving underwater crimes: Development of latent prints made on submerged objects. *Sci Justice*, 2013, **53**(3): 328–331.

Chen, T., et al., A rapid wire-based sampling method for DNA profiling. *J Forensic Sci*, 2012, **57**(2): 472–477.

Clarke, M., Alleged rape: An appeal case. *J Forensic Leg Med*, 2008, **15**(1): 32–36.

Courts, C., B. Madea, and C. Schyma, Persistence of biological traces in gun barrels—An approach to an experimental model. *Int J Legal Med*, 2011, **126**(3): 391–397.

Crispino, F., Nature and place of crime scene management within forensic sciences. *Sci Justice*, 2008, **48**(1): 24–28.

Durnal, E.W., Crime scene investigation (as seen on TV). *Forensic Sci Int*, 2010, **199**(1–3): 1–5.

Edelman, G., I. Alberink, and B. Hoogeboom, Comparison of the performance of two methods for height estimation. *J Forensic Sci*, 2010, **55**(2): 358–365.

Eldredge, K., E. Huggins, and L.C. Pugh, Alternate light sources in sexual assault examinations: An evidence-based practice project. *J Forensic Nurs*, 2012, **8**(1): 39–44.

Fisher, B., *Techniques of Crime Scene Investigation*, 7th edn., 2004. Boca Raton, FL: CRC Press.

Gokdogan, M.R. and J. Bafra, Development of a sexual assault evidence collection kit—The need for standardization in Turkey. *Nurse Educ Today*, 2010, **30**(4): 285–290.

Gosnell, J., Case three: Collection of evidence in a murder investigation. *Clin Lab Sci*, 2008, **21**(2): 124–125.

Gunasekera, R.S., A.B. Brown, and E.H. Costas, Tales from the grave: Opposing autopsy reports from a body exhumed. *J Forensic Leg Med*, 2012, **19**(5): 297–301.

Hammer, U. and A. Buttner, Distinction between forensic evidence and post-mortem changes of the skin. *Forensic Sci Med Pathol*, 2012, **8**(3): 330–333.

Hollmann, T., R.W. Byard, and M. Tsokos, The processing of skeletonized human remains found in Berlin, Germany. *J Forensic Leg Med*, 2008, **15**(7): 420–425.

Hornor, G., et al., Pediatric sexual assault nurse examiner care: Trace forensic evidence, ano-genital injury, and judicial outcomes. *J Forensic Nurs*, 2012, **8**(3): 105–111.

Hulse-Smith, L. and M. Illes, A blind trial evaluation of a crime scene methodology for deducing impact velocity and droplet size from circular bloodstains. *J Forensic Sci*, 2007, **52**(1): 65–69.

Ingemann-Hansen, O. and A.V. Charles, Forensic medical examination of adolescent and adult victims of sexual violence. *Best Pract Res Clin Obstet Gynaecol*, 2013, **27**(1): 91–102.

Ingemann-Hansen, O., et al., Legal aspects of sexual violence—Does forensic evidence make a difference? *Forensic Sci Int*, 2008, **180**(2–3): 98–104.

Jina, R., et al., Recovering of DNA evidence after rape. *S Afr Med J*, 2011, **101**(10): 758–759.

Kaliszan, M., et al., Striated abrasions from a knife with non-serrated blade—Identification of the instrument of crime on the basis of an experiment with material evidence. *Int J Legal Med*, 2011, **125**(5): 745–748.

Komar, D.A., S. Lathrop, and S. American, The use of material culture to establish the ethnic identity of victims in genocide investigations: A validation study from the American Southwest. *J Forensic Sci*, 2008, **53**(5): 1035–1039.

Larkin, B.A.J., et al., Crime scene investigation III: Exploring the effects of drugs of abuse and neurotransmitters on bloodstain pattern analysis. *Anal Methods*, 2012, **4**(3): 721–729.

Lee, H.C. and C. Ladd, Preservation and collection of biological evidence. *Croat Med J*, 2001, **42**(3): 225–228.

Lee, H.C. and E.M. Pagliaro, Forensic evidence and crime scene investigation. *J Forensic Invest*, 2013, **1**(1): 1–5.

Lee, H.C., T. Palmbach, and M.T. Miller, *Henry Lee's Crime Scene Handbook*, 2001. San Diego: Academic Press.

Lee, H.C., et al., Guidelines for the collection and preservation of DNA evidence. *J Forensic Ident*, 1991, **41**(5): 13.

Ma, M., H. Zheng, and H. Lallie, Virtual reality and 3D animation in forensic visualization. *J Forensic Sci*, 2010, **55**(5): 1227–1231.

Marchant, B. and C. Tague, Developing fingerprints in blood: A comparison of several chemical techniques. *J Forensic Ident*, 2007, **57**(1): 76–93.

Matte, M., et al., Prevalence and persistence of foreign DNA beneath fingernails. *Forensic Sci Int Genet*, 2012, **6**(2): 236–243.

Mennell, J., The future of forensic and crime scene science. Part II. A UK perspective on forensic science education. *Forensic Sci Int*, 2006, **157**(Suppl 1): S13–S20.

Morgan, J.A., Comparison of cervical os versus vaginal evidentiary findings during sexual assault exam. *J Emerg Nurs*, 2008, **34**(2): 102–105.

Mulligan, C.M., S.R. Kaufman, and L. Quarino, The utility of polyester and cotton as swabbing substrates for the removal of cellular material from surfaces. *J Forensic Sci*, 2011, **56**(2): 485–490.

National Institute of Justice. Using DNA to solve cold cases, Special Report, 2002. Washington, DC: US Department of Justice, Office of Justice Programs, Washington, DC, 2002.

Newton, M., The forensic aspects of sexual violence. *Best Pract Res Clin Obstet Gynaecol*, 2013, **27**(1): 77–90.

Nikolic, S. and V. Zivkovic, A healed bony puzzle: An old gunshot wound to the head. *Forensic Sci Med Pathol*, 2013, **9**(1): 112–116.

Nunn, S., Touch DNA collection versus firearm fingerprinting: Comparing evidence production and identification outcomes. *J Forensic Sci*, 2013, **58**(3): 601–608.

Oliva, A., et al., State of the art in forensic investigation of sudden cardiac death. *Am J Forensic Med Pathol*, 2011, **32**(1): 1–16.

Oliver, W.R. and L. Leone, Digital UV/IR photography for tattoo evaluation in mummified remains. *J Forensic Sci*, 2012, **57**(4): 1134–1136.

Osterkamp, T., K9 water searches: Scent and scent transport considerations. *J Forensic Sci*, 2011, **56**(4): 907–912.

Porta, D., et al., The importance of an anthropological scene of crime investigation in the case of burnt remains in vehicles: 3 case studies. *Am J Forensic Med Pathol*, 2013, **34**(3): 195–200.

Pringle, J.K., J.P. Cassella, and J.R. Jervis, Preliminary soilwater conductivity analysis to date clandestine burials of homicide victims. *Forensic Sci Int*, 2010, **198**(1–3): 126–133.

Ribaux, O., et al., Intelligence-led crime scene processing. Part I: Forensic intelligence. *Forensic Sci Int*, 2010, **195**(1–3): 10–16.

Ribaux, O., et al., Intelligence-led crime scene processing. Part II: Intelligence and crime scene examination. *Forensic Sci Int*, 2010, **199**(1–3): 63–71.

Rios, L., J.I. Ovejero, and J.P. Prieto, Identification process in mass graves from the Spanish Civil War I. *Forensic Sci Int*, 2010, **199**(1–3): e27–e36.

Rutty, G.N., A. Hopwood, and V. Tucker, The effectiveness of protective clothing in the reduction of potential DNA contamination of the scene of crime. *Int J Legal Med*, 2003, **117**(3): 170–174.

Sakelliadis, E.I., C.A. Spiliopoulou, and S.A. Papadodima, Forensic investigation of child victim with sexual abuse. *Indian Pediatr*, 2009, **46**(2): 144–151.

Sansoni, G., et al., Scene-of-crime analysis by a 3-dimensional optical digitizer: A useful perspective for forensic science. *Am J Forensic Med Pathol*, 2011, **32**(3): 280–286.

Schmidt, A., Crime scene investigation approach to sudden cardiac death. *J Am Coll Cardiol*, 2013, **62**(7): 630–631.

Schyma, C., B. Madea, and C. Courts, Persistence of biological traces in gun barrels after fatal contact shots. *Forensic Sci Int Genet*, 2013, **7**(1): 22–27.

Sharma, L., V.P. Khanagwal, and P.K. Paliwal, Homicidal hanging. *Legal Med*, 2011, **13**(5): 259–261.

Shaw, J. and R. Campbell, Predicting sexual assault kit submission among adolescent rape cases treated in forensic nurse examiner programs. *J Interpers Violence*, 2013, **28**(18): 3400–3417.

Shuttlewood, A.C., J.W. Bond, and L.L. Smith, The relationship between deprivation and forensic material recovered from stolen vehicles: Is it affected by vehicle condition and tidiness? *J Forensic Sci*, 2011, **56**(2): 510–513.

Smith, P.A., et al., Measuring team skills in crime scene investigation: Exploring ad hoc teams. *Ergonomics*, 2008, **51**(10): 1463–1488.

Solla, M., et al., Experimental forensic scenes for the characterization of ground-penetrating radar wave response. *Forensic Sci Int*, 2012, **220**(1–3): 50–58.

Taroni, F., et al., Whose DNA is this? How relevant a question? (a note for forensic scientists). *Forensic Sci Int Genet*, 2013, **7**(4): 467–470.

Thackeray, J.D., et al., Forensic evidence collection and DNA identification in acute child sexual assault. *Pediatrics*, 2011, **128**(2): 227–232.

Trombka, J.I., et al., Crime scene investigations using portable, non-destructive space exploration technology. *Forensic Sci Int*, 2002, **129**(1): 1–9.

Uzun, I., et al., Identification procedures as a part of death investigation in Turkey. *Am J Forensic Med Pathol*, 2012, **33**(1): 1–3.

Verdon, T.J., R.J. Mitchell, and R.A. van Oorschot, Swabs as DNA collection devices for sampling different biological materials from different substrates. *J Forensic Sci*, 2014, **59**(4): 1080–1089.

Wahlsten, P., V. Koiranen, and P. Saukko, Survey of medico-legal investigation of homicides in the city of Turku, Finland. *J Forensic Leg Med*, 2007, **14**(5): 243–252.

Walter, B.S. and J.J. Schultz, Mapping simulated scenes with skeletal remains using differential GPS in open environments: An assessment of accuracy and practicality. *Forensic Sci Int*, 2013, **228**(1–3): e33–e46.

Westen, A.A., R.R. Gerretsen, and G.J. Maat, Femur, rib, and tooth sample collection for DNA analysis in disaster victim identification (DVI): A method to minimize contamination risk. *Forensic Sci Med Pathol*, 2008, **4**(1): 15–21.

Wiegand, P., et al., Transfer of biological stains from different surfaces. *Int J Legal Med*, 2011, **125**(5): 727–731.

Winskog, C., Underwater disaster victim identification: The process and the problems. *Forensic Sci Med Pathol*, 2012, **8**(2): 174–178.
Yoon, D.Y., Newsmaker interview: Yoon Duk Yong. Crime scene investigation: The sinking of the Cheonan. Interview by Dennis Normile. *Science*, 2010, **328**(5984): 1336–1337.
Zeren, C., et al., A case of a serial sexual offender: The first ever report from Turkey. *J Forensic Leg Med*, 2012, **19**(7): 428–430.

2

Crime Scene Bloodstain Pattern Analysis

Bloodstain pattern analysis is the application of scientific knowledge to the examination and the interpretation of the morphology, the sequence, and the distribution of bloodstains associated with a crime. These analyses may determine the sequence of events; the approximate blood source locations; the positioning of the victim; and the position, the intensity, and the number of impacts applied to the blood source. They also can assist in the determination of the manner of death and can distinguish between accidents, homicides, and suicides. Bloodstain pattern analysis provides critical information for crime scene reconstructions in violent crime investigations (Chapter 1).

2.1 Basic Biological Properties of Human Blood

Blood is a bodily fluid circulating within the body. An average adult has a blood volume of approximately 8% of his or her body weight. Blood consists of a cellular portion as well as a liquid portion known as plasma (Chapter 12). The cellular portion consists of blood cells and platelets. The plasma is mostly composed of water and other substances such as proteins, inorganic salts, and other organic substances. The mass density of blood is only slightly greater than that of water. Blood can form clots (or *thrombi*) that are the result of blood coagulation (Chapter 16). Coagulation begins after an injury occurs, stopping blood loss from a damaged vessel. The normal coagulation time for 1 mL of venous blood in a glass tube is 5–15 min. The coagulation time can be affected by many factors such as blood volume and mechanical disturbance.

2.2 Formation of Bloodstains

The formation of a blood droplet is a complex event that is influenced by viscosity, surface tension, cohesion force, and gravity. Blood is viscous, and blood viscosity is a measure of the blood's resistance to flow. The viscosity of blood is approximately five times greater than that of water. During the formation of a drop of blood, blood leaks out from a blood source. The surface tension of the blood causes it to hang from the opening of a blood source and to form a pendant drop of blood (Figure 2.1). The molecules of a blood drop are held together by the cohesion force to maintain the shape of a blood drop (Figure 2.2). Surface tension causes liquids to minimize their surface. As a result, the formed blood drop is spherical. As the volume of the drop gradually increases and exceeds a certain size, it detaches itself and falls. The falling drop is also held



Figure 2.1 Forming a blood drop from a blood source. The blood that leaks out of the blood source forms a pendant drop of blood. As the volume of the pendant drop increases, the drop stretches in a downward direction. Eventually, the drop detaches and falls. The falling drop is largely influenced by the force of gravity and air resistance. (© Richard C. Li.)

together by surface tension. A falling blood drop is influenced by the downward force of gravity acting on the drop and the air resistance that acts in the opposite direction as the drop is in motion (Figure 2.1).

When a bloodstain lands on a surface, the shape and the size of the bloodstain is affected by the texture of the target surface. Bloodstains that land on porous or rough surfaces usually



Figure 2.2 The particles of blood are attracted to each other by cohesive forces that are responsible for surface tension. As a result, a formed blood drop is spherical in order to minimize its surface area. Black arrow, cohesive force; white arrow, surface tension. (© Richard C. Li.)



Figure 2.3 The respective morphologies of falling blood drops that land on surfaces with different textures at a 30° angle. (a) Tile, (b) cardboard, and (c) paper towel. (© Richard C. Li.)

have more distortion around the edges of the stains than those that land on smooth surfaces. A comparison of blood dropped onto different textures of target surfaces is shown in Figure 2.3.

2.3 Chemical Enhancement and Documentation of Bloodstain Evidence

Many chemical reagents react with blood to exhibit a color, a chemiluminescent light, or a fluorescent light (Chapter 12). These tests are extremely sensitive and thus are used as chemical enhancement reagents for detecting bloodstains. For bloodstain pattern analysis, the enhancement reagent is primarily used for detecting latent bloodstains such as diluted bloodstains that are visible on enhancement. A commonly used chemical reagent is luminol, which can be used for locating bloodstains at the scene. Other reagents such as phenolphthalein, leucomalachite green, and tetramethylbenzidine are not often used as enhancement reagents but rather as presumptive tests for blood. The positive reactions of all these reagents indicate the presence of blood.

Documenting bloodstain patterns at the scene is a major task of the investigation. Documenting bloodstain evidence can be done using a combination of photography, note-taking, and sketching. The general principle of crime scene documentation is described in Chapter 1. In bloodstain pattern analysis, special attention must obviously be given to bloodstains. The photographic documentation of bloodstains may be performed by multiple means, including film and digital photography, as well as videotaping. Photographs should be taken with an overall view followed by a medium-range and a close-up view of the bloodstain patterns. A scale of measurement must be included in the photograph, which is critical for bloodstain analysis. To avoid any distortion, the photographs should be taken with the camera lens parallel to the target surface where the bloodstains are located. An overall photograph provides an overall view of the scene including the bloodstain evidence (Figure 2.4a). A midrange photograph provides more details of the bloodstain pattern compared with that of the overall photograph (Figure 2.4b). Single bloodstains should be visible in midrange images. A close-up photograph, usually taken with a macro lens, provides a detailed image of single bloodstains, which is useful for spatter pattern analysis (Figure 2.4c).



Figure 2.4 Crime scene photographic documentation. (a) Overall, (b) midrange, and (c) close-up photographs. (© Richard C. Li.)

2.4 Analyzing Spatter Stains

A *spatter stain*, based on the recommended terminology of the Scientific Working Group on Bloodstain Pattern Analysis (SWGSTAIN), is "a bloodstain resulting from a blood drop dispersed through the air due to an external force applied to a source of liquid blood." The patterns of spatter stains, including the shape and the size of the stains, are affected by the direction and the angle of impact (discussed in detail in Section 2.5.3) of the spatter stains that are projected. This information can be obtained from an analysis of the patterns of the spatter stains. Thus, it is possible to determine the area of origin (discussed in detail in Section 2.4.4) where an external force was directly applied to the blood source.

2.4.1 Velocity of Blood Droplets

The sizes of bloodstains are affected by the external force that is directly applied on a blood source. Increasing the energy of the external force will reduce the surface tension, thus decreasing the size of the droplets. Since these travelling blood droplets are driven by the energy derived from the external force, the higher the energy, the higher the velocities of the droplets. Bloodstains can be divided into three categories based on different travelling speeds. Low-velocity impact spatter is formed when a blood droplet is travelling at <1.5 m/s. The resulting stains are usually >4 mm in diameter (Figure 2.5a). As the travelling speed of blood droplets increases, the size of the spatter stain decreases. Medium-velocity impact spatter is formed when a blood source is subjected to a force associated with beatings or stabbings. The resulting stains range from 1 to 4 mm in diameter (Figure 2.5b). High-velocity impact spatter is formed when a blood source is subjected to a force associated with shooting using firearms. The resulting stains are usually <1 mm in diameter.

2.4.2 Determining the Directionality of the Stains

In this analysis, the effects of the directionality of the spatter stains projected are examined. SWGSTAIN defines the directionality to be "the characteristic of a bloodstain that indicates the direction blood was moving at the time of deposition." This analysis is applicable when the blood source is projected onto a surface at an angle of between 0° and 90°. Under this condition, the resulting spatter stain is an elongated ellipse (Figure 2.6), which is known as the *parent stain*. Additionally, *satellite stains* in the vicinity of the parent stain can be observed. As defined by SWGSTAIN, a satellite stain is "a smaller bloodstain that originated during the formation of the parent stain as a result of blood impacting a surface." More importantly, a spine is observed, which is the pointed edge away from the parent stain. When such a pattern is observed, the pointed end of the spine always points toward the direction of travel of the bloodstains.



Figure 2.5 Bloodstains can be categorized based on their travelling velocities. (a) An example of a low-velocity impact spatter stain and (b) an example of a medium-velocity impact spatter stain. (© Richard C. Li.)



Figure 2.6 The morphology and directionality of a blood spatter stain. The arrow indicates the direction of travel. (© Richard C. Li.)

2.4.3 Determining Angles of Impact

SWGSTAIN defines the *angles of impact* to be "the acute angle (alpha), relative to the plane of a target at which a blood drop strikes the target." The shapes of the spatter stains are affected by the angle of impact. When a blood drop lands on a surface at a perpendicular angle (90°), a circular parent stain is formed (Figure 2.7), where the length and the width of the stain are equal. When a blood drop is projected onto a surface at an angle of between 0° and 90°, the stain is elongated. As the impact angle decreases, the shape of the spatter stain is more elongated (Figure 2.7), in which the length of the stain is greater than the width. It is observed that the ratio of the width and the length of the parent stain is proportional to the sine of the impact angle, which is summarized in the following trigonometric equation:

$$\sin \alpha = \frac{w}{l}$$



Figure 2.7 The effects of the impact angle on the shapes of blood spatter stains. Spatter stains are projected onto the surface of a ceramic tile at: (a) 90°, (b) 50°, (c) 20°, and (d) 10°. (© Richard C. Li.)

In this equation, α is the angle of impact, *l* is the length of the parent stain (major axis), and *w* is the width of the parent stain (minor axis). Thus, the angle of impact can be determined based on the relationship between the length and the width of the stain (Figure 2.8). Obviously, the measurement of the stain's axes is critical to the accuracy of the calculation of the angle of impact. To produce accurate and reproducible measurements, bloodstain pattern analysis software can be used, which superimposes a scaled close-up image of an individual bloodstain and calculates the angle of impact.

2.4.4 Determining Area of Origin

SWGSTAIN defines the *area of origin* to be "the three-dimensional location from which spatter originated." Using simple trigonometry, the area of origin can be determined based on the measurements from multiple elongated spatter stains (Figure 2.9). This can be accomplished by using the string method or the tangent method.



Figure 2.8 Impact angle. The angle between the path of a projectile and the plane of the target surface is shown. α, the impact angle; *l*, the length of the parent stain; and *w*, the width of the parent stain. (© Richard C. Li.)



Figure 2.9 Area of origin. The area of origin is determined using the string method. Only three representative bloodstains are shown. α, impact angle. (© Richard C. Li.)



Figure 2.10 Determining the area of origin using the string method. (a) Selecting elongated spatter stains, (b) connecting strings, and (c) setting the path of the strings. (© Richard C. Li.)

In the string method, multiple (approximately two dozen) well-formed, elongated spatter stains are selected for analysis (Figure 2.10a). For each stain, the angle of impact is calculated. A piece of string is then connected between the stain and a surface with one end of the string precisely attached to the spatter stain (Figure 2.10b). The path of the string, indicating the trajectory of the stain, is set using a protractor based on the calculated angle of impact (Figures 2.10c and 2.11). This process is repeated until all the stains that have been selected are processed. For



Figure 2.11 Tools for finding the area of origin. (a) Laser trajectory pointer and (b) string and scales. (© Richard C. Li.)



Figure 2.12 Determining the area of origin using the tangent method. Only three representative bloodstains are shown. α, the angle of impact; *H*, the height of the area of origin; and *D*, the distance from the spatter stain to the area of convergence. (© Richard C. Li.)

a spatter pattern generated from a single impact event, the strings converge. The area where the strings meet is the area of origin.

In the tangent method, the directionality of a single stain is determined first. A line is then back projected through the major axis of the bloodstain. For a single impact event, approximately two dozen stains are processed to determine the *area of convergence*. Based on SWGSTAIN's definition, the area of convergence is "the area containing the intersections generated by lines drawn through the long axes of individual stains that indicates in two dimensions the location of the blood source." Next, the angle of impact of each stain is calculated. The distance from the bloodstain to the area of convergence is measured (Figure 2.12). The height of the area of origin is calculated using the tangent function as shown:

$$H = D \cdot \tan \alpha$$

In the equation, α is the angle of impact, H is the height of the area of origin, and D is the distance from the spatter stain to the area of convergence.

2.5 Types of Bloodstain Patterns

Bloodstain patterns can be classified into three basic categories: passive, transfer, and projected bloodstains.

2.5.1 Passive Bloodstains

A *passive bloodstain* is formed due to bleeding from wounds, and the blood is deposited on a surface by the influence of the force of gravity alone. For example, a *drip stain* is formed when a falling drop of blood from an exposed wound or a blood-bearing object lands on a surface. If a blood source is moving, a *drip trail* is formed. A *drip pattern*, which is distinct from a drip stain, is formed when a liquid drips into another liquid, where one or both of the liquids are blood (Figure 2.13). As a result, secondary spatter stains are generated. As the dropping distance of the blood increases, the number of secondary spatter stains usually increases, and the size of these stains decreases. An approximate estimation of the dropping distance is possible. A *splash pattern* is formed when a volume of blood spills onto a surface (Figure 2.14). Splash patterns usually



Figure 2.13 A drip pattern. The secondary spatter stains are shown. (© Richard C. Li.)



Figure 2.14 A splash pattern. Peripheral, elongated bloodstains are shown. (© Richard C. Li.)

have large stains surrounded by numerous, peripheral, elongated bloodstains. A *flow pattern* is caused by the movement of a large volume of blood on a surface either due to gravity or to the movement of the target such as a victim or postmortem disturbance. A *pool* is a bloodstain resulting from the accumulation of liquid blood on a surface (Figure 2.15). Sometimes, air bubbles in the blood may cause a *bubble ring* pattern (Figure 2.15). If blood is coagulated, gelatinous *blood clots* can be observed. Additionally, a *serum stain*, which consists of the liquid portion of the blood after a clot is formed, may also be present.



Figure 2.15 Pool and bubble ring patterns. (a) A pool pattern, (b) a disturbed pool pattern, and (c) a splash pattern with a bubble ring. Bubble rings are also present in (a) and (b). (© Richard C. Li.)

2.5.2 Transfer Bloodstains

A *transfer bloodstain*, based on SWGSTAIN, is “a bloodstain resulting from contact between a blood-bearing surface and another surface.” For example, a *swipe pattern* is “a bloodstain pattern resulting from the transfer of blood from a blood-bearing surface onto another surface, with characteristics that indicate relative motion between the two surfaces.” For example, bloody impressions can provide information about the shape, the size, and the pattern of the objects such as finger ridges, hands, and shoe soles. Examples of hand and shoe swipe patterns are shown in Figures 2.16 and 2.17. A *wipe pattern* is “an altered bloodstain pattern resulting from an object moving through a preexisting wet bloodstain.” Examples of wipe patterns are shown in Figures 2.18 and 2.19. A *perimeter* stain, a type of wipe pattern, is a bloodstain that is disturbed before it is dried but it maintains the peripheral characteristics of the original stain (Figure 2.20). Perimeter stain patterns can be useful for the estimation of sequential events of acts. The pattern can also be used to estimate a time frame between the time of bleeding and the subsequent act. However, the drying time of a blood drop varies based on the surrounding conditions. Therefore, it is necessary to carry out a crime scene reconstruction under similar conditions to those of the scene to make such estimations.

2.5.3 Projected Bloodstains

A *projected bloodstain* is formed when a volume of blood is deposited on a surface under a pressure or a force that is greater than the force of gravity. For example, an *impact pattern* is



Figure 2.16 Bloody impressions. Bloody handprints are present on (a) a wall and (b) fabric. (© Richard C. Li.)



Figure 2.17 Bloody impressions. Bloody shoe prints on (a) paper and (b) fabric; and (c) bloody footprints on tile. (© Richard C. Li.)

formed when an object strikes liquid blood (Figure 2.21). A *cast-off pattern* is formed when blood drops are released from a moving blood-bearing object (Figure 2.22). Some spatter patterns are often associated with a wound penetrated by a projectile (Figure 2.23). A *forward spatter* is formed when blood drops travel from an exit wound in the same direction as a projectile, while a *back spatter* is formed when blood drops travel from an entry wound in the opposite direction of a projectile. Sometimes, internal bleeding caused by an injury may block the airway. An *expiration pattern* is formed when blood is forced by airflow through the



Figure 2.18 Wipe patterns. (© Richard C. Li.)



Figure 2.19 A wipe pattern caused by dragging a body through a pool of blood. (a) A pool of blood. Sections of the wipe pattern caused by dragging are shown in (b), (c), and (d). (© Richard C. Li.)



Figure 2.20 Perimeter stains. (a) Peripheral characteristics of the original stains are shown. Perimeter stains were created at different periods of time after the original stain was formed: (b) midrange view and (c) close-up view. (© Richard C. Li.)

trachea and out of the nose or mouth (Figure 2.24). An *arterial spurt pattern* is associated with wounds damaging arterial blood vessels where bloodstains are driven by arterial pressure. Although the shape of arterial patterns varies, these patterns usually have a series of large spurts with fluctuations corresponding to the systolic and the diastolic blood pressures. At a crime scene, if the projectile of bloodstains is blocked by an object, a *void pattern* is formed, which exhibits an area where there is an absence of blood surrounded by continuously distributed bloodstains.



Figure 2.21 An impact bloodstain pattern as a result of using blunt force. (© Richard C. Li.)



Figure 2.22 Cast-off patterns. Spatter stains are projected onto (a) a covered wall and (b) a lab coat. (© Richard C. Li.)


Entry wound
Exit wound
Back spatter
Forward spatter

Figure 2.23 Forward and back spatter patterns. Arrow, the direction of a projectile. (© Richard C. Li.)



Figure 2.24 An expiration pattern. (© Richard C. Li.)

Bibliography

Adam, C.D., Fundamental studies of bloodstain formation and characteristics. *Forensic Sci Int*, 2012, **219**(1–3): 76–87.

Adelson, L., The coroner of Elsinore. *New Engl J Med*, 1960, **262**(5): 229–234.

Attinger, D., et al., Fluid dynamics topics in bloodstain pattern analysis: Comparative review and research opportunities. *Forensic Sci Int*, 2013, **231**(1–3): 375–396.

Behrooz, N., L. Hulse-Smith, and S. Chandra, An evaluation of the underlying mechanisms of bloodstain pattern analysis error. *J Forensic Sci*, 2011, **56**(5): 1136–1142.

Benecke, M. and L. Barksdale, Distinction of bloodstain patterns from fly artifacts. *Forensic Sci Int*, 2003, **137**(2–3): 152–159.

Buck, U., et al., 3D bloodstain pattern analysis: Ballistic reconstruction of the trajectories of blood drops and determination of the centres of origin of the bloodstains. *Forensic Sci Int*, 2011, **206**(1–3): 22–28.

Byard, R.W., et al., Blood stain pattern interpretation in cases of fatal haemorrhage from ruptured varicose veins. *J Forensic Leg Med*, 2007, **14**(3): 155–158.

Camana, F., Determining the area of convergence in bloodstain pattern analysis: A probabilistic approach. *Forensic Sci Int*, 2013, **231**(1–3): 131–136.

Connolly, C., M. Illes, and J. Fraser, Affect of impact angle variations on area of origin determination in bloodstain pattern analysis. *Forensic Sci Int*, 2012, **223**(1–3): 233–240.

Davidson, P.L., et al., Physical components of soft-tissue ballistic wounding and their involvement in the generation of blood backspatter. *J Forensic Sci*, 2012, **57**(5): 1339–1342.

de Bruin, K.G., R.D. Stoel, and J.C. Limborgh, Improving the point of origin determination in bloodstain pattern analysis. *J Forensic Sci*, 2011, **56**(6): 1476–1482.

de Castro, T., et al., Interpreting the formation of bloodstains on selected apparel fabrics. *Int J Legal Med*, 2013, **127**(1): 251–258.

Denison, D., et al., Forensic implications of respiratory derived blood spatter distributions. *Forensic Sci Int*, 2011, **204**(1–3): 144–155.

Donaldson, A.E., et al., Using oral microbial DNA analysis to identify expirated bloodspatter. *Int J Legal Med*, 2010, **124**(6): 569–576.

Donaldson, A.E., et al., Characterising the dynamics of expirated bloodstain pattern formation using high-speed digital video imaging. *Int J Legal Med*, 2011, **125**(6): 757–762.

Emes, A., Expirated blood—A review. *J Can Soc Forensic Sci*, 2001, **34**(4): 197–203.

Finnis, J., J. Lewis, and A. Davidson, Comparison of methods for visualizing blood on dark surfaces. *Sci Justice*, 2013, **53**(2): 178–186.

Fujikawa, A., et al., Changes in the morphology and presumptive chemistry of impact and pooled bloodstain patterns by *Lucilia sericata* (Meigen) (Diptera: Calliphoridae). *J Forensic Sci*, 2011, **56**(5): 1315–1318.

Illes, M. and M. Boue, Robust estimation for area of origin in bloodstain pattern analysis via directional analysis. *Forensic Sci Int*, 2013, **226**(1–3): 223–229.

Karger, B., et al., Bloodstain pattern analysis—Casework experience. *Forensic Sci Int*, 2008, **181**(1–3): 15–20.

Kettner, M., F. Ramsthaler, and A. Schnabel, "Bubbles"—A spot diagnosis. *J Forensic Sci*, 2010, **55**(3): 842–844.

Kunz, S.N., H. Brandtner, and H. Meyer, Unusual blood spatter patterns on the firearm and hand: A backspatter analysis to reconstruct the position and orientation of a firearm. *Forensic Sci Int*, 2013, **228**(1–3): e54–e57.

Larkin, B.A. and C.E. Banks, Preliminary study on the effect of heated surfaces upon bloodstain pattern analysis. *J Forensic Sci*, 2013, **58**(5): 1289–1296.

Larkin, B.A.J., et al., Crime scene investigation III: Exploring the effects of drugs of abuse and neurotransmitters on bloodstain pattern analysis. *Anal Methods*, 2012, **4**(3): 721–729.

Lee, W.C., et al., Statistical evaluation of alternative light sources for bloodstain photography. *J Forensic Sci*, 2013, **58**(3): 658–663.

Liesegang, J., Bloodstain pattern analysis—Blood source location. *J Can Soc Forensic Sci*, 2004, **37**(4): 215–222.

Maclean, B., K. Powley, and D. Dahlstrom, A case study illustrating another logical explanation for high velocity impact spatter. *J Can Soc Forensic Sci*, 2001, **34**(4): 191–195.

Makovicky, P., et al., The use of trigonometry in bloodstain analysis. *Soud Lek*, 2013, **58**(2): 20–25.

Maloney, A., et al., One-sided impact spatter and area-of-origin calculations. *J Forensic Ident*, 2011, **61**(2): 123–135.

Nikolic, S. and V. Zivkovic, Bloodstain pattern in the form of gushing in a case of fatal exsanguination due to ruptured varicose vein. *Med Sci Law*, 2011, **51**(1): 61–62.

Peschel, O., et al., Blood stain pattern analysis. *Forensic Sci Med Pathol*, 2011, **7**(3): 257–270.

Pizzola, P.A., et al., Commentary on "3D bloodstain pattern analysis: Ballistic reconstruction of the trajectories of blood drops and determination of the centres of origin of the bloodstains" by Buck et al. [Forensic Sci. Int. 206 (2011) 22–28]. *Forensic Sci Int*, 2012, **220**(1–3): e39–e40; author reply e41.

Power, D.A., et al., PCR-based detection of salivary bacteria as a marker of expirated blood. *Sci Justice*, 2010, **50**(2): 59–63.

Ramsthaler, F., et al., Drying properties of bloodstains on common indoor surfaces. *Int J Legal Med*, 2012, **126**(5): 739–746.

Randall, B., Blood and tissue spatter associated with chainsaw dismemberment. *J Forensic Sci*, 2009, **54**(6): 1310–1314.

Raymond, M.A., E.R. Smith, and J. Liesegang, Oscillating blood droplets—Implications for crime scene reconstruction. *Sci Justice*, 1996, **36**(3): 161–171.

Raymond, M.A., E.R. Smith, and J. Liesegang, The physical properties of blood—Forensic considerations. *Sci Justice*, 1996, **36**(3): 153–160.

Sauvageau, A., et al., Bloodstain pattern analysis in a case of fatal varicose vein rupture. *Am J Forensic Med Pathol*, 2007, **28**(1): 35–37.

Stephens, B.G. and T.B. Allen, Back spatter of blood from gunshot wounds. Observations and experimental simulation. *J Forensic Sci*, 1983, **28**(2): 437–439.

Striman, B., et al., Alteration of expirated bloodstain patterns by *Calliphora vicina* and *Lucilia sericata* (Diptera: Calliphoridae) through ingestion and deposition of artifacts. *J Forensic Sci*, 2011, **56**(Suppl 1): S123–S127.

Taylor, M.C., et al., The effect of firearm muzzle gases on the backspatter of blood. *Int J Legal Med*, 2011, **125**(5): 617–628.

Thanakiatkrai, P., A. Yaodam, and T. Kitpipit, Age estimation of bloodstains using smartphones and digital image analysis. *Forensic Sci Int*, 2013, **233**(1–3): 288–297.

Trombka, J.I., et al., Crime scene investigations using portable, non-destructive space exploration technology. *Forensic Sci Int*, 2002, **129**(1): 1–9.

White, B., Bloodstain patterns on fabrics: The effect of drop volume, dropping height and impact angle. *J Can Soc Forensic Sci*, 1986, **19**(1): 3–36.

Yen, K., et al., Blood-spatter patterns: Hands hold clues for the forensic reconstruction of the sequence of events. *Am J Forensic Med Pathol*, 2003, **24**(2): 132–140.

Yi, R. and Y. Wang, The experimental observation of secondary spatter bloodstain in morphology. *Chin J Forensic Med*, 2011, **26**(1): 26–29.

3

Forensic Biology

A Subdiscipline of Forensic Science

Forensic laboratories provide scientific analysis, evidence evaluation, and consultations to various criminal justice agencies for the investigation of criminal cases. Additionally, forensic laboratories provide expert testimony related to the resolution of criminal cases to the courts.

3.1 Common Disciplines of Forensic Laboratory Services

Many of the disciplines of the forensic laboratory services are commonly practiced in various municipal, county, state, and federal forensic laboratories in the United States. Forensic biology is a subdiscipline of forensic science. A full range of forensic laboratory services, known as "full service," usually includes: crime scene investigation (Figure 3.1); latent print examination (Figure 3.2); forensic biology (Figure 3.3); controlled substance analysis (Figure 3.4); postmortem toxicology (Figure 3.5); questioned document examination (Figure 3.6); firearm, toolmark, and other impression evidence examination (Figures 3.7 through 3.10); explosive and fire debris examination (Figure 3.11); and transfer (trace) evidence examination (Figures 3.12 and 3.13). Table 3.1 describes the services that are normally provided by a forensic laboratory with their respective analyses.

3.2 Laboratory Analysis of Biological Evidence

Forensic biology uses scientifically accepted protocols to analyze biological evidence. Laboratory analysis (Figures 3.14 and 3.15) utilizes scientific techniques for the examination of evidence, the reconstruction of a crime scene, the identification of biological fluids, and the comparison of individual characteristics of biological evidence.

3.2.1 Identification of Biological Evidence

The identification of biological evidence is the first step that is performed before further analyses are carried out. This includes the identification of biological fluids such as blood, saliva, and semen; this process is discussed in more detail in subsequent chapters (Chapters 12 through 14). The *identification* is based on a comparison of *class characteristics*—a set of characteristics that allows a sample to be placed in a category with similar materials. By comparing the



Figure 3.1 Crime scene investigation. Recovery of fired casings at the scene can aid in determining the position of the shooter. (© Richard C. Li.)

class characteristics of a sample with known standards of its class, biological samples can be identified.

3.2.2 Comparison of Individual Characteristics of Biological Evidence

Individual characteristics refer to the unique characteristics of both the evidence and a reference sample such as fingerprints, which share a common origin to a high degree of certainty. An example of biological evidence possessing individual characteristics is DNA polymorphisms. In the case of biological evidence, current forensic DNA profiling can compare individual characteristics of DNA evidence with a known reference sample. It is possible to determine that a biological stain originated from a particular individual, which is useful for human identification. The examination of individual characteristics of evidence can also exclude the possibility of a common origin. The specific methods utilized for the individualization of evidence are also discussed in subsequent chapters (Chapters 19 through 23).

3.2.3 Reporting Results and Expert Testimony

After the analysis of evidence is completed, a report is prepared based on the results of the analysis, which may include sections discussing the specific evidence analyzed, the method of analysis used, the results obtained, and the conclusions drawn. In the case of DNA evidence, the strength of the conclusion is usually evaluated via statistical computations (Chapter 25). A forensic scientist often serves as an expert witness whose testimony


Magnetic Fingerprint Powder
Black
Silver
White
Bichromatic
Blitz-Red
Blitz-Green
Sketch and/or Remarks

Date | Crime | Case No.
Victim
Address of Incident
Location of Latent Prints Lifted
Prints Lifted by: | ID No.
Lightning Powder Company 1-800-852-0300

Figure 3.2 Developing latent fingerprints by dusting methods. Using magnetic fingerprint powder (top) that is held by a magnetic applicator (middle). Fingerprints (bottom) dusted by magnetic fingerprint powder, tape lifted and preserved on a fingerprint card. (© Richard C. Li.)

provides professional opinions about the evidence analyzed. Based on the federal rules of evidence, an expert witness is qualified based on his or her knowledge, skill, experience, training, or education, and may give an opinion to the court that is relevant to the analyses conducted. However, forensic scientists must also communicate their findings to attorneys, judges, and members of a jury. This requires the translation of technical information into layman's terms.



Figure 3.3 A section of a forensic biology laboratory showing an automated electrophoresis instrument used for forensic DNA profiling (left). Processing biological evidence in a biosafety cabinet (right). (© Richard C. Li.)



Figure 3.4 Gas chromatograph (top) and gas chromatograph-mass spectrometer (bottom) used for controlled substance analysis. (© Richard C. Li.)



Figure 3.5 Tissue samples (left) and gas chromatograph-mass spectrometer (right) for forensic postmortem toxicological analysis. (© Richard C. Li.)



Figure 3.6 A digital imaging system, using multiple illumination sources ranging from ultraviolet to infrared wavelengths, for examining altered and counterfeit documents (left). An electrostatic imaging system for detecting indented writing on questioned documents (right). This device generates an electrostatic image of indented writing, which is then visualized using charge-sensitive toners. (© Richard C. Li.)



Figure 3.7 Striation marks on fired bullets can be analyzed to match a bullet to a gun. (Courtesy of P. Diaczuk.)

3.3 Forensic Science Services Related to Forensic Biology

A number of specialized forensic science services beyond those provided by forensic laboratories are routinely available to law enforcement agencies. For example, forensic services related to biological evidence and those involving more specialized analysis are available. These services are important aids to a criminal investigation and require the expertise of individuals who have highly specialized skills.



Figure 3.8 Fired hollowpoint bullets (.45 caliber ACP Winchester). Striation marks are visible on the side view of a bullet (right). (© Richard C. Li.)



Figure 3.9 A comparison microscope is used for the simultaneous comparison of two items of firearm evidence side by side. (© Richard C. Li.)

3.3.1 Forensic Pathology

When a death is deemed suspicious or unexplained, medical examiners frequently perform autopsies to determine the exact cause (Figures 3.16 and 3.17). The manner of death is classified into one of five categories based on the circumstances: natural, homicide, suicide, accident, or undetermined. Additionally, a medical examiner participating in a criminal investigation is often responsible for estimating the time of death.

3.3.2 Forensic Anthropology

Forensic anthropology is the identification and the examination of human skeletal remains (Figures 3.18 and 3.19). Skeletal remains can reveal a number of individual characteristics that can be useful in attempting to identify an individual. An examination of bones may reveal an individual's origin, sex, approximate age, race, and the presence of a skeletal injury. A forensic anthropologist may also assist in creating facial reconstructions to aid in the identification of skeletal remains or may be called on to help collect and organize bone fragments in the course of identifying victims of mass disasters such as plane crashes as well as victims in mass graves discovered after wars or genocides.



Figure 3.10 Comparing the striations between evidence and reference samples using a comparison microscope: casings (top) and bullets (bottom). (Courtesy of P. Diaczuk.)



Figure 3.11 Scanning electron microscope used in the analysis of gunshot residue and explosives. (© Richard C. Li.)



Figure 3.12 Trace evidence such as hairs can be transferred during the acts of a violent crime. The analysis and comparisons of these types of trace evidence can potentially establish a link between a suspect or a victim and a crime scene. Hairs from human (top), horse (middle left), deer (middle right), dog (bottom left), and cat (bottom right). (© Richard C. Li.)



Figure 3.13 Trace evidence: fibers. Cotton (left), nylon (middle), and polyester (right). (© Richard C. Li.)

3.3.3 Forensic Entomology

The study of insects in relation to a criminal investigation is known as forensic entomology. This forensic discipline is valuable for estimating the time of death when the circumstances surrounding the crime are otherwise unknown. The stages of development of certain insect species present in or on a body can be identified and allow a forensic entomologist to approximate how long the body was left exposed (Figure 3.20).

Table 3.1 Common Services Provided by US Forensic Laboratories

Service	Function	Method
Crime scene investigation	Evidence recognition, documentation, collection, and preservation	Crime scene responses and related endeavors are diverse and vary with case and type of evidence
Latent print examination	Analysis of friction ridge detail in fingerprints Activities include visualization, recording, comparison, storage, and recovery of latent prints	Alternate light sources, physical (powder) and chemical enhancements Direct lifts, photography, and digital imaging Use of an Automated Fingerprint Identification System (AFIS) database
Forensic biology	Identification of biological fluids (blood, semen, and saliva) DNA profiling for individualization	Serological and biochemical methods Polymerase chain reaction (PCR)-based methods Automated electrophoresis platforms Use of Combined DNA Index System (CODIS)
Controlled substance analysis	Identification and quantification of drugs present in submitted evidence	Microscopic, chemical, chromatographic, and spectroscopic methodologies Gas chromatography–mass spectrometry or infrared spectrophotometry
Postmortem toxicology	Determination of concentrations of substances and their metabolites in biological fluids or tissues	Immunoassays and chemical methods Confirmatory techniques such as gas and liquid chromatography–mass spectrometry
Questioned document examination	Investigation of forgeries, tracings, disguised handwritings, computer manipulation of images, and recovery of altered documents Analysis of papers, inks, toners, word processors, typewriters, copiers, and printers	Macroscopic and microscopic comparisons Chromatographic and spectroscopic methods
Firearm and toolmark examination	Identification of firearms, tools, and other implements (expertise achieved predominantly through experience)	Microscopic comparisons of questioned and authenticated impressions Comparison of striae on recovered bullets Use of National Integrated Ballistics Information Network (NIBIN)
Explosive and fire debris examination	Identification, recovery, and detection of bulk explosives, residues, debris, and accelerants	Microscopic, spectroscopic, and chromatographic methods Gas chromatography–mass spectrometry may be needed to adequately characterize sample
Trace evidence examination	Analysis of transferred evidence such as hairs, fibers, soil, paints, and glass	Microscopic analysis of evidence with gas chromatograph-mass spectrometers, FTIR microscopes, scanning electron microscopes, basic and advanced microscopy, and capillary electrophoresis

Source: Adapted from US Department of Justice, Office of Justice Programs, National Institute of Justice (NIOJ), *Forensic Science: Review of Status and Needs*, 1999, US Department of Justice, Washington, DC.



Figure 3.14 Photographic documentation of a bloodstained shirt after visual examination. (© Richard C. Li.)



Figure 3.15 A multiwavelength viewing and imaging device used for the examination of various types of evidence, including bodily fluid stains. (© Richard C. Li.)



Figure 3.16 View of a forensic pathology facility. (Courtesy of G. Ledwell.)



Figure 3.17 Photographic documentation prior to autopsy (left). Preparing specimens for histological sections for forensic pathological examination (right). (Courtesy of G. Ledwell.)



Figure 3.18 Buried human skeletons recovered by forensic anthropologists. (Courtesy of H. Brewster.)



Figure 3.19 Human skull recovered at the scene. (Courtesy of H. Brewster.)



Figure 3.20 Insects found on a dead animal (left). Blow fly specimen. This insect is commonly encountered at crime scenes (right). (Courtesy of K. Wendler.)

3.3.4 Forensic Odontology

Practitioners of forensic odontology participate in the identification of victims whose bodies are left in an unrecognizable state. The characteristics of teeth, their alignment, and the overall structure of the mouth provide evidence that can identify a specific person. Dental records such as x-rays and dental casts allow a forensic odontologist to compare a set of dental remains with an alleged victim. Another application of forensic odontology in a criminal investigation is bite mark analysis (Figure 3.21). A forensic odontologist can analyze the marks left on a victim and compare them with the tooth structures of a suspect to make a comparison.


80
85
90
95
100
105
110
115
120
125
130
135

Figure 3.21 A dental cast can be utilized for identifying bite marks. (© Richard C. Li.)

3.4 Brief History of the Development of Forensic Biology

The developmental history of modern forensic biology spans three stages: (1) antigen polymorphism, (2) protein polymorphism, and (3) DNA polymorphism. Figure 3.22 illustrates this history.

3.4.1 Antigen Polymorphism

The human ABO blood groups were discovered in 1900 by Karl Landsteiner in a study of the causes of blood transfusion reactions. Landsteiner's discovery made blood transfusions feasible, and he received the Nobel Prize in 1930 when he revealed the four groups of human blood cells designated A, B, AB, and O. By the 1960s, a dozen more blood group systems had been characterized, and at least 29 systems are currently known (Chapter 18).


First genetic polymorphism, human ABO blood groups, discovered by Landsteiner
Locard lays down principle that "every contact leaves a trace"
(1960s–1980s) Multilocus DNA fingerprinting developed by Jeffreys, followed by single-locus profiling (SLP)
First use of DNA in a criminal case (identification of double murderer Colin Pitchfork, in leicestershire, UK)
First commercial forensic PCR kit detecting SNPs at the polymorphic *HLA-DQA1* locus by dot blot and oligonucleotide hybridization
First Y-STR described, and used in acquittal of rape (Germany)
First commercial forensic STR profiling kits developed
First mass disaster case (Waco, Texas)
Publication of National Research Council report *The Evaluation of Forensic DNA Evidence*
1900
1915
1920
1960
1984
1986
1987
1988
1991
1992
1993
1995
1996
1997
First antibody test for blood group (ABO) introduced and used by Lattes
(1920s–1950s) discovery and use of other blood groups and serum proteins (e.g., MNSs system, Rhesus, Lewis, Kell, haptoglobin)
Discovery and use of electrophoretic variants of red blood cell enzymes (e.g., phosphoglucomutase, glyoxylase)
New York v. Castro judgment on admissibility of DNA evidence led to strict quality control
First useful polymorphic human STRs characterized
First use of mtDNA in casework (UK)
Publication of National Research Council report *DNA Technology in Forensic Science*
UK national DNA database established (STR profiles)
DNA profiling from touched objects and single cells demonstrated

Figure 3.22 A brief history of the development of forensic biology. (From Jobling, M.A. and Gill, P., *Nat Rev Genet*, 5, 739–751, 2004. With permission.)

Subsequent studies found that the blood types in the ABO system were inherited, and the frequencies with which the four types appeared in specific human populations were found to differ. This led to the discovery of the first antigen polymorphic marker for use in human identification in forensic cases. In the past, forensic laboratories utilized blood group systems in a discipline known as forensic serology. While it is possible to exclude a suspect through the use of blood group typing, the evidence for the inclusion of a suspect is weak due to the high probability of a coincidental match between two unrelated persons.

3.4.2 Protein Polymorphism

Because of the limitations of antigen polymorphism, protein polymorphism was introduced for forensic identification (Chapter 18). Initially, a few polymorphisms in serum proteins and erythrocyte enzymes were reported. By the 1980s, however, approximately a hundred protein polymorphisms had been discovered. A few systems were commonly used in forensic laboratories, including the polymorphisms of erythrocyte enzymes, serum proteins, and hemoglobin. Blood groups and protein polymorphism analysis were combined in forensic investigations to lower the probability of a match between two unrelated individuals. However, more powerful methods were still sought.

3.4.3 DNA Polymorphism

The human genome contains all the necessary biological information for cellular and organ structure and function. It consists of the *nuclear genome* and the *mitochondrial genome* (Chapter 23 discusses the mitochondrial genome). The human nuclear genome, a set of 23 chromosomes, contains approximately 3 billion base pairs (bp). The Human Genome Project was initiated in 1990 to sequence the entire human nuclear genome. In 2003, 99% of the human genome, including the most important parts of the genome, was sequenced. Further analyses on the human genome sequences continue. The genome contains genes and intergenic noncoding sequences.

3.4.3.1 Genes and Related Sequences

Approximately 20,000–25,000 genes have been identified in the human genome, which encode the information for the synthesis of proteins. The functions of nearly half of these genes have been identified. Most encode the proteins that are responsible for the maintenance of the genome, the functioning of the cells, the immune response, and the structural proteins of cells.

Most human genes are discontinuous. The coding regions of genes are called *exons* and are separated by *introns*. During gene expression, the precursor messenger RNA transcript (pre-mRNA), consisting of both the exons and introns, is produced. The mRNA is a template for protein synthesis in which the sequence is based on a complementary strand of DNA. Through the process of splicing, the introns are removed and the exons are joined, producing the spliced mRNA form, which can be used for protein synthesis via the translation process. Other gene-related sequences include those responsible for gene transcription such as *promoter sequences*; those responsible for gene regulation such as *cis-regulatory sequences* (or enhancers); and *untranslated sequences*, which are transcribed but do not encode proteins. Figure 3.23 depicts the features of a representative human gene.

3.4.3.2 Intergenic Noncoding Sequences

More than 90% of the human genome sequence consists of intergenic noncoding sequences located between genes. The functions of these sequences are yet to be discovered. The intergenic noncoding sequences contain large quantities of various types of *repetitive DNA*, which falls into two categories: tandem repeats and genome-wide or interspersed repeats.

Tandem repeats are repeat units placed next to each other in an array. One type is called *satellite DNA* because of the observation of satellite bands containing DNA with tandem repeats


5′
3′
cis-Regulatory sequence
Promoter sequence
5′ Untranslated sequence
Exon 1
Intron 1
Exon 2
3′ Untranslated sequence
Poly (A) signal
Termination

Figure 3.23 Gene structure. Transcription, which can be regulated by the cis-regulatory sequence, is initiated at the transcription start site (arrow) near the promoter. The exons, noncoding introns, and the untranslated sequences are also shown. (© Richard C. Li.)

during density gradient centrifugation. Satellite DNA can be found at centromeres and telomeres consisting of regions composed of long stretches of tandem repeats. Minisatellites and microsatellites are two other types of shorter tandem repeats. *Minisatellites*, also known as *variable number tandem repeats* (VNTRs), form arrays of tandem repeats with a *repeat unit length* from several to hundreds of base pairs. In a *microsatellite*, also known as a *short tandem repeat* (STR) or a *simple sequence repeat* (SSR), the repeat unit length can be 2–6 bp long.

Mobile elements (*interspersed repeats*) are randomly located throughout the human genome (Figure 3.24). Two human types have been characterized: *DNA transposons* and *retrotransposons*. The mobile elements change their locations, a process called *transposition*, by which these sequences are inserted into a new site in the genome. The transposition of DNA transposons is through a "cut-and-paste" mechanism. During transposition, DNA transposons are excised from one site and inserted at a new site in the genome. In contrast, retrotransposons duplicate themselves during transposition and propagate throughout the genome, which is a copy-and-paste mechanism: a copy of the original retrotransposons is generated at the new site and the original copy is retained. Additionally, the transposition of retrotransposons requires an RNA intermediate, a process called *retrotransposition*. Retrotransposons have two subtypes: *long terminal repeat* (LTR) and *non-LTR retroposons*. The non-LTR retroposons can be further divided into two subtypes: *long interspersed elements* (LINEs) and *short interspersed elements* (SINEs). Alu elements are the most abundant type of human SINE. There are more than one million copies of Alu elements in the human genome (Figure 3.25). Some members of the Alu elements are


Mobile elements
DNA transposons
Retro-transposons
LTR retro-transposons
Non-LTR retro-transposons
LINEs
SINEs
tRNA derived
5S rRNA derived
Alu (7SL RNA derived)
Alu J
Alu S
Alu Y
Alu Ya
Alu Yb
Alu Yc

Figure 3.24 Mobile elements classification. (© Richard C. Li.)



Figure 3.25 Structure of Alu elements. The name, Alu elements, was given since these elements usually contain DNA sequences cleaved by the restriction enzyme *Alu*I. The Alu element is a dimeric structure including two regions separated by an A-rich sequence. The 5′ region has boxes A and B containing RNA polymerase III promoter sequences. The 3′ region contains a 31-nucleotide insertion. There is a short polyadenylation tail located at the 3′ end of the Alu element (terminal A-stretch). Full-length Alu elements are approximately 300 bp long. (© Richard C. Li.)



Figure 3.26 Detecting Alu element insertion polymorphism for human identification. The Alu element insertion site is amplified using the polymerase chain reaction assay. The presence and absence of the Alu element at the site can be detected based on the length of the DNA fragment analyzed. F, forward primer; R, reverse primer. (© Richard C. Li.)

polymorphic for the presence or absence of insertion that can potentially be used for forensic human identification (Figure 3.26).

3.4.3.3 Human DNA Polymorphic Markers

Most individual human genome sequences are very similar. However, variations in sequences do occur. The differences between individual genomes that occur at the DNA level are called *DNA polymorphisms*. In particular, a DNA polymorphism with alternative forms of a chromosomal locus that differ in nucleotide sequence is known as a *sequence polymorphism*. A DNA polymorphism that differs in the numbers of tandem repeat units is known as a *length polymorphism*. A DNA polymorphism can occur anywhere in a genome including genes and other chromosomal locations. Many DNA polymorphisms are useful for genetic mapping studies and hence are called *DNA markers*. DNA polymorphisms form the basis of forensic DNA profiling. The focus of this text is on the human genome, but polymorphisms also occur in the genomes of other organisms.

Most DNA polymorphisms are single nucleotide polymorphisms (SNPs) involving a single-base-pair change or a point mutation. Over one million SNPs have been identified. SNPs arise by spontaneous mutation. Most SNPs occur in noncoding regions of the genome, although some appear in coding regions as well. Other forms of DNA polymorphisms are tandem repeats such as STRs and VNTRs. Although their biological functions are unknown, STRs and VNTRs are very useful for forensic DNA analysis. Many are highly polymorphic, and the number of repeat units varies greatly among different individuals of a population. It is unlikely that two unrelated individuals will have exactly the same combination of STR or VNTR polymorphisms if sufficient markers are examined. Thus, a resulting genetic profile can be used for human identification.

Alternative forms of DNA polymorphisms are called *alleles*. The same allele present in both homologous chromosomes is referred to as *homozygous*. Two different alleles present in homologous chromosomes are referred to as *heterozygous*. A combination of alleles at a given locus is a *genotype*. In forensic analysis, the genotype for a panel of analyzed loci is called the *DNA profile*.

3.4.3.4 Forensic DNA Polymorphism Profiling

In 1984, Sir Alec Jeffreys (Figure 3.27) developed a DNA profiling technique using a VNTR technique involving multilocus profiling and later followed by single-locus profiling (Chapter 19). This technique led to the solving of a double murder that had been committed in Leicestershire (United Kingdom) in the 1980s. The case was the first to apply DNA evidence to a criminal investigation. During the investigation, DNA profiling not only identified the true perpetrator but it also excluded an innocent suspect. This case demonstrated DNA profiling's great potential in forensic investigations.

DNA profiling offered a number of advantages compared with earlier systems. The most important is the ability of the technique to reveal far greater individual variability in DNA than can be revealed by antigen and protein polymorphic markers. The probability of two unrelated individuals having the same DNA profile is very low. The great variability of DNA polymorphisms has made it possible to offer strong support for concluding that DNA from a suspect and from a crime scene originated from the same source. This technique was subsequently implemented in forensic laboratories worldwide.

In the mid-1980s, Kary Mullis and his coworkers developed the polymerase chain reaction (PCR) technique, which amplifies a small quantity of DNA. Mullis's invention had a powerful impact on molecular biology and earned him a Nobel Prize in 1993. Since the introduction of PCR, new techniques have been developed for forensic DNA testing purposes.

Figure 3.27 Sir Alec Jeffreys. (© Richard C. Li.)

The application of PCR-based assays makes forensic DNA analysis possible when only minute quantities of DNA can be recovered from a crime scene, for example, from hairs and cigarette butts. These assays have greatly increased the sensitivity of forensic DNA testing. The first forensic application of a PCR-based assay utilizing SNPs at the *HLA-DQA1* locus (formerly called DQα) was developed in 1986 (Chapter 22). One major disadvantage of the assay was the high probability (approximately 1 in 4000) of a match between two unrelated persons. Amplified fragment length polymorphism (AFLP) at the D1S80 locus has also been implemented in forensic laboratories. The D1S80 locus is a small-size VNTR marker that can be amplified by PCR. The *HLA-DQA1* and AFLP assays were used for some years until the introduction of STR assays.

In the late 1990s, forensic laboratories started utilizing STR loci. STRs have a number of advantages compared with VNTRs. For example, STRs can be amplified by PCR because of their smaller size, which greatly increases the sensitivity of the assay. Furthermore, STR markers are as highly variable as VNTRs. With the application of multiple STR loci, the probability of a match between two unrelated persons becomes extremely low. As a result of DNA testing, perpetrators have been identified and wrongly convicted innocent people have been exonerated (Chapter 20).

In 1995, the United Kingdom established the first national DNA database for criminal investigations. By the end of 1998, several other countries, including the United States, had created their own national DNA databases. The United States has selected 13 STR loci for the Combined DNA Index System (CODIS). These national DNA databases play important roles in solving criminal cases.

Another technique known as mitochondrial DNA (mtDNA) profiling has also been used for forensic testing. mtDNA is maternally inherited genetic material and is therefore particularly useful for human identification. Each cell contains multiple copies of mtDNA. Thus, mtDNA typing can be useful for analysis when nuclear DNA is severely degraded or present in very limited amounts, such as in cases involving decomposed human remains. Alternatively, polymorphic markers at the Y chromosome have also been utilized for forensic DNA testing. Y chromosomal markers are paternally inherited so they can be used for paternity testing. These markers are also very useful in analyzing DNA from multiple contributors in sexual assault cases.

Bibliography

Aleksander, A., Forensic expertise and judicial practice: Evidence or proof? *J Eval Clin Pract*, 2012, **18**(6): 1147–1150.

Alvarez-Cubero, M.J., et al., Genetic identification of missing persons: DNA analysis of human remains and compromised samples. *Pathobiology*, 2012, **79**(5): 228–238.

Andelinovic, S., et al., Twelve-year experience in identification of skeletal remains from mass graves. *Croat Med J*, 2005, **46**(4): 530–539.

Apostolov, A., S. Hristov, and E. Angelova, DNA identification of biological traces and interpretation in a sexual assault case. *Am J Forensic Med Pathol*, 2009, **30**(1): 57–60.

Aquila, I., et al., The role of forensic botany in crime scene investigation: Case report and review of literature. *J Forensic Sci*, 2014, **59**(3): 820–824.

Asari, M., et al., Multiplex PCR-based Alu insertion polymorphisms genotyping for identifying individuals of Japanese ethnicity. *Genomics*, 2012, **99**(4): 227–232.

Auvdel, M.J., Comparison of laser and ultraviolet techniques used in the detection of body secretions. *J Forensic Sci*, 1987, **32**(2): 326–345.

Baraybar, J.P., When DNA is not available, can we still identify people? Recommendations for best practice. *J Forensic Sci*, 2008, **53**(3): 533–540.

Bauer, C.M., et al., Molecular genetic investigations on Austria's patron saint Leopold III. *Forensic Sci Int Genet*, 2013, **7**(2): 313–315.

Bogdanowicz, W., et al., Genetic identification of putative remains of the famous astronomer Nicolaus Copernicus. *Proc Natl Acad Sci U S A*, 2009, **106**(30): 12279–12282.

Boljuncic, J., DNA analysis of early mediaeval individuals from the Zvonimirovo burial site in Northern Croatia: Investigation of kinship relationships by using multiplex system amplification for short tandem repeat loci. *Croat Med J*, 2007, **48**(4): 536–546.

Bond, J.W., Value of DNA evidence in detecting crime. *J Forensic Sci*, 2007, **52**(1): 128–136.

Boric, I., J. Ljubkovic, and D. Sutlovic, Discovering the 60 years old secret: Identification of the World War II mass grave victims from the island of Daksa near Dubrovnik, Croatia. *Croat Med J*, 2011, **52**(3): 327–335.

Brettell, T.A., et al., Forensic science. *Anal Chem*, 1999, **71**(12): 235R–255R.

Bruce-Chwatt, R.M., A brief history of forensic odontology since 1775. *J Forensic Leg Med*, 2010, **17**(3): 127–130.

Budowle, B. and A. van Daal, Extracting evidence from forensic DNA analyses: Future molecular biology directions. *Biotechniques*, 2009, **46**(5): 339–340, 342–350.

Budowle, B., et al., Role of law enforcement response and microbial forensics in investigation of bioterrorism. *Croat Med J*, 2007, **48**(4): 437–449.

Burg, A., R. Kahn, and K. Welch, DNA testing of sexual assault evidence: The laboratory perspective. *J Forensic Nurs*, 2011, **7**(3): 145–152.

Byard, R.W., K. Both, and E. Simpson, The identification of submerged skeletonized remains. *Am J Forensic Med Pathol*, 2008, **29**(1): 69–71.

Caenazzo, L., P. Tozzo, and D. Rodriguez, Ethical issues in DNA identification of human biological material from mass disasters. *Prehosp Disaster Med*, 2013, **28**(4): 393–396.

Caramelli, D., et al., Genetic analysis of the skeletal remains attributed to Francesco Petrarca. *Forensic Sci Int*, 2007, **173**(1): 36–40.

Carey, L. and L. Mitnik, Trends in DNA forensic analysis. *Electrophoresis*, 2002, **23**(10): 1386–1397.

Cattaneo, C., et al., Unidentified bodies and human remains: An Italian glimpse through a European problem. *Forensic Sci Int*, 2010, **195**(1–3): 167, e1–e6.

Cavard, S., et al., Forensic and police identification of “X” bodies. A 6-years French experience. *Forensic Sci Int*, 2011, **204**(1–3): 139–143.

Charlier, P., et al., Genetic comparison of the head of Henri IV and the presumptive blood from Louis XVI (both Kings of France). *Forensic Sci Int*, 2013, **226**(1–3): 38–40.

Claes, P., et al., Computerized craniofacial reconstruction: Conceptual framework and review. *Forensic Sci Int*, 2010, **201**(1–3): 138–145.

Coble, M.D., et al., Mystery solved: The identification of the two missing Romanov children using DNA analysis. *PLoS One*, 2009, **4**(3): e4838.

Connery, S.A., Three decade old cold case murder solved with evidence from a sexual assault kit. *J Forensic Leg Med*, 2013, **20**(4): 355–356.

Cordner, S.M., N. Woodford, and R. Bassed, Forensic aspects of the 2009 Victorian Bushfires Disaster. *Forensic Sci Int*, 2011, **205**(1–3): 2–7.

Courts, C. and B. Madea, Genetics of the sudden infant death syndrome. *Forensic Sci Int*, 2010, **203**(1–3): 25–33.

Courts, C. and B. Madea, Full STR profile of a 67-year-old bone found in a fresh water lake. *J Forensic Sci*, 2011, **56**(Suppl 1): S172–S175.

Craft, K.J., J.D. Owens, and M.V. Ashley, Application of plant DNA markers in forensic botany: Genetic comparison of *Quercus* evidence leaves to crime scene trees using microsatellites. *Forensic Sci Int*, 2007, **165**(1): 64–70.

Davis, G.G., Forensic toxicology. *Clin Lab Sci*, 2012, **25**(2): 120–124.

Davoren, J., et al., Highly effective DNA extraction method for nuclear short tandem repeat testing of skeletal remains from mass graves. *Croat Med J*, 2007, **48**(4): 478–485.

De Ungria, M.C., et al., Forensic DNA evidence and the death penalty in the Philippines. *Forensic Sci Int Genet*, 2008, **2**(4): 329–332.

Definis Gojanovic, M. and D. Sutlovic, Skeletal remains from World War II mass grave: From discovery to identification. *Croat Med J*, 2007, **48**(4): 520–527.

Dekeirsschieter, J., et al., Forensic entomology investigations from Doctor Marcel Leclercq (1924–2008): A review of cases from 1969 to 2005. *J Med Entomol*, 2013, **50**(5): 935–954.

Deng, Y.J., et al., Preliminary DNA identification for the tsunami victims in Thailand. *Genomics Proteom Bioinform*, 2005, **3**(3): 143–157.

Dirkmaat, D.C., et al., New perspectives in forensic anthropology. *Am J Phys Anthropol*, 2008, **137**(Suppl 47): 33–52.

Dissing, J., et al., The last Viking king: A royal maternity case solved by ancient DNA analysis. *Forensic Sci Int*, 2007, **166**(1): 21–27.

Djuric, M., et al., Identification of victims from two mass-graves in Serbia: A critical evaluation of classical markers of identity. *Forensic Sci Int*, 2007, **172**(2–3): 125–129.

Dobberstein, R.C., et al., Degradation of biomolecules in artificially and naturally aged teeth: Implications for age estimation based on aspartic acid racemization and DNA analysis. *Forensic Sci Int*, 2008, **179**(2–3): 181–191.

Dolan, S.M., et al., The emerging role of genetics professionals in forensic kinship DNA identification after a mass fatality: Lessons learned from Hurricane Katrina volunteers. *Genet Med*, 2009, **11**(6): 414–417.

Dzijan, S., et al., Evaluation of the reliability of DNA typing in the process of identification of war victims in Croatia. *J Forensic Sci*, 2009, **54**(3): 608–609.

Enserink, M., Can this DNA sleuth help catch criminals? *Science*, 2011, **331**(6019): 838–840.

Ferri, G., et al., Forensic botany: Species identification of botanical trace evidence using a multigene barcoding approach. *Int J Legal Med*, 2009, **123**(5): 395–401.

Fondevila, M., et al., Case report: Identification of skeletal remains using short-amplicon marker analysis of severely degraded DNA extracted from a decomposed and charred femur. *Forensic Sci Int Genet*, 2008, **2**(3): 212–218.

Foran, D.R., et al., The conviction of Dr. Crippen: New forensic findings in a century-old murder. *J Forensic Sci*, 2011, **56**(1): 233–240.

Foster, E.A., et al., Jefferson fathered slave's last child. *Nature*, 1998, **396**(6706): 27–28.

Ge, J., B. Budowle, and R. Chakraborty, Choosing relatives for DNA identification of missing persons. *J Forensic Sci*, 2011, **56**(Suppl 1): S23–S28.

Geserick, G. and I. Wirth, Genetic kinship investigation from blood groups to DNA markers. *Transfus Med Hemother*, 2012, **39**(3): 163–175.

Gewin, V., Forensics: The call of the crime lab. *Nature*, 2011, **473**(7347): 409–411.

Gill, P., Role of short tandem repeat DNA in forensic casework in the UK—Past, present, and future perspectives. *Biotechniques*, 2002, **32**(2): 366–368, 370, 372, passim.

Gill, P., A.J. Jeffreys, and D.J. Werrett, Forensic application of DNA "fingerprints". *Nature*, 1985, **318**(6046): 577–579.

Gill, P., et al., Identification of the remains of the Romanov family by DNA analysis. *Nat Genet*, 1994, **6**(2): 130–135.

Gingerich, O., The Copernicus grave mystery. *Proc Natl Acad Sci U S A*, 2009, **106**(30): 12215–12216.

Gonzalez-Andrade, F., et al., Two fathers for the same child: A deficient paternity case of false inclusion with autosomic STRs. *Forensic Sci Int Genet*, 2009, **3**(2): 138–140.

Graham, E.A., DNA reviews: Low level DNA profiling. *Forensic Sci Med Pathol*, 2008, **4**(2): 129–131.

Grellner, W. and B. Madea, Demands on scientific studies: Vitality of wounds and wound age estimation. *Forensic Sci Int*, 2007, **165**(2–3): 150–154.

Hampikian, G., E. West, and O. Akselrod, The genetics of innocence: Analysis of 194 U.S. DNA exonerations. *Annu Rev Genomics Hum Genet*, 2011, **12**: 97–120.

Hartman, D., et al., The contribution of DNA to the disaster victim identification (DVI) effort. *Forensic Sci Int*, 2011, **205**(1–3): 52–58.

Hartman, D., et al., The importance of Guthrie cards and other medical samples for the direct matching of disaster victims using DNA profiling. *Forensic Sci Int*, 2011, **205**(1–3): 59–63.

Hatsch, D., et al., A rape case solved by mitochondrial DNA mixture analysis. *J Forensic Sci*, 2007, **52**(4): 891–894.

Hinchliffe, J., Forensic odontology, part 4. Human bite marks. *Br Dent J*, 2011, **210**(8): 363–368.

Holland, M.M., et al., Mitochondrial DNA sequence analysis of human skeletal remains: Identification of remains from the Vietnam War. *J Forensic Sci*, 1993, **38**(3): 542–553.

Holland, M.M., et al., Development of a quality, high throughput DNA analysis procedure for skeletal samples to assist with the identification of victims from the World Trade Center attacks. *Croat Med J*, 2003, **44**(3): 264–272.

Holobinko, A., Forensic human identification in the United States and Canada: A review of the law, admissible techniques, and the legal implications of their application in forensic cases. *Forensic Sci Int*, 2012, **222**(1–3): 394, e1–e13.

Honda, K., The Ashikaga case of Japan—Y-STR testing used as the exculpatory evidence to free a convicted felon after 17.5 years in prison. *Forensic Sci Int Genet*, 2013, **7**(1): e1–e2.

Horsman-Hall, K.M., et al., Development of STR profiles from firearms and fired cartridge cases. *Forensic Sci Int Genet*, 2009, **3**(4): 242–250.

Howard, C., et al., A *Cannabis sativa* STR genotype database for Australian seizures: Forensic applications and limitations. *J Forensic Sci*, 2009, **54**(3): 556–563.

Howlett, R., DNA forensics and the FBI. *Nature*, 1989, **341**(6239): 182–183.

Hughes, V.K. and N.E. Langlois, Use of reflectance spectrophotometry and colorimetry in a general linear model for the determination of the age of bruises. *Forensic Sci Med Pathol*, 2010, **6**(4): 275–281.

Irwin, J.A., et al., DNA identification of "Earthquake McGoon" 50 years postmortem. *J Forensic Sci*, 2007, **52**(5): 1115–1118.

Ishiko, A., et al., Experimental studies on identification of the driver based on STR analysis. *Leg Med (Tokyo)*, 2008, **10**(3): 115–118.

Janisch, S., et al., Analysis of clinical forensic examination reports on sexual assault. *Int J Legal Med*, 2010, **124**(3): 227–235.

Jeffreys, A.J., Genetic fingerprinting. *Nat Med*, 2005, **11**(10): 1035–1039.

Jewkes, R., et al., Medico-legal findings, legal case progression, and outcomes in South African rape cases: Retrospective review. *PLoS Med*, 2009, **6**(10): e1000164.

Jobling, M.A. and P. Gill, Encoded evidence: DNA in forensic analysis. *Nat Rev Genet*, 2004, **5**(10): 739–751.

Just, R.S., et al., Titanic's unknown child: The critical role of the mitochondrial DNA coding region in a re-identification effort. *Forensic Sci Int Genet*, 2011, **5**(3): 231–235.

Karlsson, A.O., et al., DNA-testing for immigration cases: The risk of erroneous conclusions. *Forensic Sci Int*, 2007, **172**(2–3): 144–149.

Kayser, M. and P.M. Schneider, DNA-based prediction of human externally visible characteristics in forensics: Motivations, scientific challenges, and ethical considerations. *Forensic Sci Int Genet*, 2009, **3**(3): 154–161.

Kim, N.Y., et al., A genetic investigation of Korean mummies from the Joseon Dynasty. *Mol Biol Rep*, 2011, **38**(1): 115–121.

Kjellstrom, A., et al., An analysis of the alleged skeletal remains of Carin Goring. *PLoS One*, 2012, **7**(12): e44366.

Krishan, K., Individualizing characteristics of footprints in Gujjars of North India—Forensic aspects. *Forensic Sci Int*, 2007, **169**(2–3): 137–144.

Kupiec, T. and W. Branicki, Genetic examination of the putative skull of Jan Kochanowski reveals its female sex. *Croat Med J*, 2011, **52**(3): 403–409.

Lalueza-Fox, C., et al., Genetic analysis of the presumptive blood from Louis XVI, King of France. *Forensic Sci Int Genet*, 2011, **5**(5): 459–463.

Leclair, B., et al., Bioinformatics and human identification in mass fatality incidents: The World Trade Center disaster. *J Forensic Sci*, 2007, **52**(4): 806–819.

Lee, H.C., et al., DNA typing in forensic science. I. Theory and background. *Am J Forensic Med Pathol*, 1994, **15**(4): 269–282.

Lee, H.Y., et al., Genetic characterization and assessment of authenticity of ancient Korean skeletal remains. *Hum Biol*, 2008, **80**(3): 239–250.

Lee, H.Y., et al., DNA typing for the identification of old skeletal remains from Korean War victims. *J Forensic Sci*, 2010, **55**(6): 1422–1429.

Lehman, D.C., Introduction to forensic science. *Clin Lab Sci*, 2012, **25**(2): 107–108.

Li, X., et al., Mitochondrial DNA and STR analyses for human DNA from maggots crop contents: A forensic entomology case from central-southern China. *Trop Biomed*, 2011, **28**(2): 333–338.

Loreille, O.M., et al., Integrated DNA and fingerprint analyses in the identification of 60-year-old mummified human remains discovered in an Alaskan glacier. *J Forensic Sci*, 2010, **55**(3): 813–818.

Luna, A., Is postmortem biochemistry really useful? Why is it not widely used in forensic pathology? *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S27–S30.

Madea, B., et al., Molecular pathology in forensic medicine—Introduction. *Forensic Sci Int*, 2010, **203**(1–3): 3–14.

Maiquilla, S.M., et al., Y-STR DNA analysis of 154 female child sexual assault cases in the Philippines. *Int J Legal Med*, 2011, **125**(6): 817–824.

Manasatienkij, C. and C. Ra-ngabpai, Clinical application of forensic DNA analysis: A literature review. *J Med Assoc Thai*, 2012, **95**(10): 1357–1363.

Manhart, J., A. Bittorf, and A. Buttner, Disaster victim identification-experiences of the "Autobahn A19" disaster. *Forensic Sci Med Pathol*, 2012, **8**(2): 118–124.

Manjunath, B.C., et al., DNA profiling and forensic dentistry—A review of the recent concepts and trends. *J Forensic Leg Med*, 2011, **18**(5): 191–197.

Marjanovic, D., et al., DNA identification of skeletal remains from the World War II mass graves uncovered in Slovenia. *Croat Med J*, 2007, **48**(4): 513–519.

Marjanovic, D., et al., Identification of skeletal remains of Communist Armed Forces victims during and after World War II: Combined Y-chromosome (STR) and MiniSTR approach. *Croat Med J*, 2009, **50**(3): 296–304.

Matheson, C.D., et al., Molecular exploration of the first-century Tomb of the Shroud in Akeldama, Jerusalem. *PLoS One*, 2009, **4**(12): e8319.

McDonald, J. and D.C. Lehman, Forensic DNA analysis. *Clin Lab Sci*, 2012, **25**(2): 109–113.

Meissner, C. and S. Ritz-Timme, Molecular pathology and age estimation. *Forensic Sci Int*, 2010, **203**(1–3): 34–43.

Melchior, L., et al., Evidence of authentic DNA from Danish Viking Age skeletons untouched by humans for 1000 years. *PLoS One*, 2008, **3**(5): e2214.

Milde-Kellers, A., et al., An illicit love affair during the Third Reich: Who is my grandfather? *J Forensic Sci*, 2008, **53**(2): 377–379.

Monckton, D.G. and A.J. Jeffreys, DNA profiling. *Curr Opin Biotechnol*, 1993, **4**(6): 660–664.

Montelius, K. and B. Lindblom, DNA analysis in disaster victim identification. *Forensic Sci Med Pathol*, 2012, **8**(2): 140–147.

Mundorff, A.Z., E.J. Bartelink, and E. Mar-Cash, DNA preservation in skeletal elements from the World Trade Center disaster: Recommendations for mass fatality management. *J Forensic Sci*, 2009, **54**(4): 739–745.

Nakamura, Y., DNA variations in human and medical genetics: 25 years of my experience. *J Hum Genet*, 2009, **54**(1): 1–8.

National Institute of Justice. Using DNA to solve cold cases, Special Report, 2002. Washington, DC: US Department of Justice, Office of Justice Programs.

Neuhuber, F., et al., An unusual case of identification by DNA analysis of siblings. *Forensic Sci Int Genet*, 2012, **6**(1): 121–123.

Njoroge, S.K., et al., Microchip electrophoresis of Alu elements for gender determination and inference of human ethnic origin. *Electrophoresis*, 2010, **31**(6): 981–990.

Nunez, C., et al., Genetic analysis of 7 medieval skeletons from the Aragonese Pyrenees. *Croat Med J*, 2011, **52**(3): 336–343.

Nuzzolese, E. and G. Di Vella, Future project concerning mass disaster management: A forensic odontology prospectus. *Int Dent J*, 2007, **57**(4): 261–266.

Onoja, A.M., Paternity testing. *Niger J Med*, 2011, **20**(4): 406–408.

Opdal, S.H., et al., Mitochondrial tRNA genes and flanking regions in sudden infant death syndrome. *Acta Paediatr*, 2007, **96**(2): 211–214.

Page, M., J. Taylor, and M. Blenkin, Expert interpretation of bitemark injuries—A contemporary qualitative study. *J Forensic Sci*, 2013, **58**(3): 664–672.

Palo, J.U., et al., Repatriation and identification of the Finnish World War II soldiers. *Croat Med J*, 2007, **48**(4): 528–535.

Park, D.K., et al., The role of forensic anthropology in the examination of the Daegu subway disaster (2003, Korea). *J Forensic Sci*, 2009, **54**(3): 513–518.

Parson, W., et al., Unravelling the mystery of Nanga Parbat. *Int J Legal Med*, 2007, **121**(4): 309–310.

Piccinini, A., et al., World War One Italian and Austrian soldier identification project: DNA results of the first case. *Forensic Sci Int Genet*, 2010, **4**(5): 329–333.

Pietrangeli, I., et al., Forensic DNA challenges: Replacing numbers with names of Fosse Ardeatine's victims. *J Forensic Sci*, 2009, **54**(4): 905–908.

Pinckard, J.K., Memorial Eckert paper for 2007 forensic DNA analysis for the medical examiner. *Am J Forensic Med Pathol*, 2008, **29**(4): 375–381.

Pollak, S., Medical criminalistics. *Forensic Sci Int*, 2007, **165**(2–3): 144–149.

Pomara, C., et al., A medieval murder. *Am J Forensic Med Pathol*, 2008, **29**(1): 72–74.

Prainsack, B. and M. Kitzberger, DNA behind bars: Other ways of knowing forensic DNA technologies. *Soc Stud Sci*, 2009, **39**(1): 51–79.

Pretty, I.A., Forensic dentistry: 1. Identification of human remains. *Dent Update*, 2007, **34**(10): 621–622, 624–626, 629–630, passim.

Pretty, I.A., Forensic dentistry: 2. Bitemarks and bite injuries. *Dent Update*, 2008, **35**(1): 48–50, 53–54, 57–58 passim.

Primorac, D. and M.S. Schanfield, Application of forensic DNA testing in the legal system. *Croat Med J*, 2000, **41**(1): 32–46.

Prottas, J.M. and A.A. Noble, Use of forensic DNA evidence in prosecutors' offices. *J Law Med Ethics*, 2007, **35**(2): 310–315.

Puentes, K., et al., Three-dimensional reconstitution of bullet trajectory in gunshot wounds: A case report. *J Forensic Leg Med*, 2009, **16**(7): 407–410.

Raymond, J.J., et al., Trace DNA analysis: Do you know what your neighbour is doing? A multi-jurisdictional survey. *Forensic Sci Int Genet*, 2008, **2**(1): 19–28.

Rios, L., et al., Identification process in mass graves from the Spanish Civil War II. *Forensic Sci Int*, 2012, **219**(1–3): e4–e9.

Roewer, L., Y chromosome STR typing in crime casework. *Forensic Sci Med Pathol*, 2009, **5**(2): 77–84.

Rogaev, E.I., et al., Genomic identification in the historical case of the Nicholas II royal family. *Proc Natl Acad Sci U S A*, 2009, **106**(13): 5258–5263.

Roper, S.M. and O.L. Tatum, Forensic aspects of DNA-based human identity testing. *J Forensic Nurs*, 2008, **4**(4): 150–156.

Ruffell, A. and A. Sandiford, Maximising trace soil evidence: An improved recovery method developed during investigation of a $26 million bank robbery. *Forensic Sci Int*, 2011, **209**(1–3): e1–e7.

Rutkowska, J., et al., Donor DNA is detected in recipient blood for years after kidney transplantation using sensitive forensic medicine methods. *Ann Transplant*, 2007, **12**(3): 12–14.

Saigusa, K., et al., Practical applications of molecular biological species identification of forensically important flies. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S344–S347.

Sato, Y., et al., Multiplex STR typing of aortic tissues from unidentified cadavers. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S455–S457.

Schou, M.P. and P.J. Knudsen, The Danish disaster victim identification effort in the Thai tsunami: Organisation and results. *Forensic Sci Med Pathol*, 2012, **8**(2): 125–130.

Schwark, T., A. Heinrich, and N. von Wurmb-Schwark, Genetic identification of highly putrefied bodies using DNA from soft tissues. *Int J Legal Med*, 2011, **125**(6): 891–894.

Schwark, T., et al., Reliable genetic identification of burnt human remains. *Forensic Sci Int Genet*, 2011, **5**(5): 393–399.

Scott, R. and C. Skellern, DNA evidence in jury trials: The "CSI effect". *J Law Med*, 2010, **18**(2): 239–262.

Seo, Y., et al., STR and mitochondrial DNA SNP typing of a bone marrow transplant recipient after death in a fire. *Leg Med (Tokyo)*, 2012, **14**(6): 331–335.

Skinner, M., D. Alempijevic, and A. Stanojevic, In the absence of dental records, do we need forensic odontologists at mass grave sites? *Forensic Sci Int*, 2010, **201**(1–3): 22–26.

Skopp, G., Postmortem toxicology. *Forensic Sci Med Pathol*, 2010, **6**(4): 314–325.

Speller, C.F., et al., Personal identification of cold case remains through combined contribution from anthropological, mtDNA, and bomb-pulse dating analyses. *J Forensic Sci*, 2012, **57**(5): 1354–1360.

Stadlbauer, C., et al., History of individuals of the 18th/19th centuries stored in bones, teeth, and hair analyzed by LA-ICP-MS—A step in attempts to confirm the authenticity of Mozart's skull. *Anal Bioanal Chem*, 2007, **388**(3): 593–602.

Stene, L.E., K. Ormstad, and B. Schei, Implementation of medical examination and forensic analyses in the investigation of sexual assaults against adult women: A retrospective study of police files and medical journals. *Forensic Sci Int*, 2010, **199**(1–3): 79–84.

Sudoyo, H., et al., DNA analysis in perpetrator identification of terrorism-related disaster: Suicide bombing of the Australian Embassy in Jakarta 2004. *Forensic Sci Int Genet*, 2008, **2**(3): 231–237.

Suzuki, S., et al., Guilty by his fibers: Suspect confession versus textile fibers reconstructed simulation. *Forensic Sci Int*, 2009, **189**(1–3): e27–e32.

Swift, A.M., Case three: Ethics of coercion. *Clin Lab Sci*, 2008, **21**(2): 122–123.

Thompson, R., S. Zoppis, and B. McCord, An overview of DNA typing methods for human identification: Past, present, and future. *Methods Mol Biol*, 2012, **830**: 3–16.

Tokdemir, M., et al., Forensic value of gunpowder tattooing in identification of multiple entrance wounds from one bullet. *Leg Med (Tokyo)*, 2007, **9**(3): 147–150.

Tokutomi, T., et al., Identification using DNA from skin contact: Case reports. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S576–S577.

Tracey, M., Short tandem repeat-based identification of individuals and parents. *Croat Med J*, 2001, **42**(3): 6.

Travis, J., Forensic science. Scientists decry isotope, DNA testing of "nationality". *Science*, 2009, **326**(5949): 30–31.

Ubelaker, D.H., The forensic evaluation of burned skeletal remains: A synthesis. *Forensic Sci Int*, 2009, **183**(1–3): 1–5.

US Department of Justice, Office of Justice Programs, National Institute of Justice (NIOJ), *Forensic Science: Review of Status and Needs*, 1999. Washington, DC: US Department of Justice.

US Department of Justice, Office of Justice Programs, National Institute of Justice (NIOJ), *The Future of Forensic DNA Testing: Predictions of the Research and Development Working Group*, 2000. Washington, DC: US Department of Justice.

Vanek, D., L. Saskova, and H. Koch, Kinship and Y-chromosome analysis of 7th century human remains: Novel DNA extraction and typing procedure for ancient material. *Croat Med J*, 2009, **50**(3): 286–295.

Varsha, DNA fingerprinting in the criminal justice system: An overview. *DNA Cell Biol*, 2006, **25**(3): 181–188.

Vaz, M. and F.S. Benfica, The experience of the forensic anthropology service of the medical examiner's office in Porto Alegre, Brazil. *Forensic Sci Int*, 2008, **179**(2–3): e45–e49.

Verdiani, S., et al., An unusual observation of tetragametic chimerism: Forensic aspects. *Int J Legal Med*, 2009, **123**(5): 431–435.

von Wurmb-Schwark, N. and T. Schwark, Genetic determination of sibship and twin zygosity in a case of an alleged double infant homicide. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S510–S511.

von Wurmb-Schwark, N., et al., A new multiplex-PCR comprising autosomal and y-specific STRs and mitochondrial DNA to analyze highly degraded material. *Forensic Sci Int Genet*, 2009, **3**(2): 96–103.

Walsh, S.J., Recent advances in forensic genetics. *Expert Rev Mol Diagn*, 2004, **4**(1): 31–40.

Weedn, V.W. and H.J. Baum, DNA identification in mass fatality incidents. *Am J Forensic Med Pathol*, 2011, **32**(4): 393–397.

Wenk, R.E., Testing for parentage and kinship. *Curr Opin Hematol*, 2004, **11**(5): 357–361.

Williamson, R. and R. Duncan, DNA testing for all. *Nature*, 2002, **418**(6898): 585–586.

Willott, G.M., The role of the forensic biologist in cases of sexual assault. *J Forensic Sci Soc*, 1975, **15**(4): 269–276.

Wilms, H.R., et al., Evaluation of autopsy and police reports in the investigation of sudden unexplained death in the young. *Forensic Sci Med Pathol*, 2012, **8**(4): 380–389.

Wyman, J.F., Principles and procedures in forensic toxicology. *Clin Lab Med*, 2012, **32**(3): 493–507.

Zaya, D.N. and M.V. Ashley, Plant genetics for forensic applications. *Methods Mol Biol*, 2012, **862**: 35–52.

Zietkiewicz, E., et al., Current genetic methodologies in the identification of disaster victims and in forensic analysis. *J Appl Genet*, 2012, **53**(1): 41–60.

Zupanic Pajnic, I., B. Gornjak Pogorelc, and J. Balazic, Molecular genetic identification of skeletal remains from the Second World War Konfin I mass grave in Slovenia. *Int J Legal Med*, 2010, **124**(4): 307–317.

4

Sources of Biological Evidence

Biological evidence analysis is one of the standard forensic examinations in the investigation of a wide variety of crimes. In particular, DNA evidence facilitates investigators' efforts to link offenders to crime scenes by matching DNA profiles. DNA evidence can also be used to eliminate suspects. The DNA evidence that is routinely encountered at crime scenes can often be categorized into several groups or types. Table 4.1 lists sources of DNA that are frequently found on personal items. Figures 4.1 and 4.2 illustrate representative types of evidence that are processed and their success rates.

4.1 Bodily Fluids

Bodily fluids and their stains are useful biological evidence for forensic, serological, and DNA analysis and may be useful in solving crimes. The most common bodily fluids in forensic analysis are blood, seminal fluid, and saliva. Blood evidence, such as peripheral blood that circulates through the heart, arteries, veins, and capillaries, is one of the most common types of biological evidence that is found at crime scenes (Chapter 12). The fluid portion of blood is called *plasma*, a subcompartment of extracellular fluid, which is the bodily fluid outside cells. Blood contains various suspended blood cells. The cellular portion of the blood consists of *erythrocytes* (also known as red blood cells), *leucocytes* (also known as white blood cells), and *platelets*. Because mature human erythrocytes and platelets do not have nuclei, they are not useful sources of nuclear DNA. For forensic DNA profiling, the nuclear DNA in blood samples (Figure 4.3) is primarily isolated from leucocytes, which are nucleated. Besides peripheral blood, menstrual blood can be analyzed to investigate the possibility of the occurrence of a sexual assault crime (Chapter 16).

Other bodily fluids are *transcellular fluids*. These fluids are considered to be a subcompartment of the extracellular fluid that is contained within epithelial-lined extracellular spaces. For example, seminal fluid (Chapter 14) and saliva (Chapter 15) stains as well as vaginal secretions are analyzed for the investigation of sexual assault crimes. Sometimes, urine stains and fecal materials (Chapter 16) are related to assault crimes as well. Sweat, which is secreted from the eccrine and apocrine sweat glands in the skin (Chapter 17), and cerumen, also known as earwax (a waxy substance secreted in the ear canal), can be potentially used for human identification. Fluids present in vomitus (Chapter 17) can be potentially important for forensic investigations of violent crimes.

4.1.1 Extracellular Nucleic Acids

Blood plasma and other various bodily fluids usually contain small amounts of nucleic acids (DNA or RNA) known as extracellular nucleic acids. The nucleic acids circulating in plasma

Table 4.1 Common Items of Evidence

Evidence	Possible DNA Location	Source of DNA
Baseball bat	Handle	Skin cells, sweat, blood, tissue
Hat, bandana, mask	Inside surfaces	Sweat, hair, skin cells, dandruff, saliva
Eyeglasses	Nose, ear piece, lens	Sweat, skin cells
Facial tissue, cotton swab	Surface	Mucus, blood, sweat, semen, earwax
Dirty laundry	Surface	Blood, sweat, semen, saliva
Toothpick	Surface	Saliva
Used cigarette	Butt (filter area)	Saliva
Used stamp, envelope seal	Moistened area	Saliva
Tape or ligature	Inside or outside surface	Skin cells, sweat, saliva
Bottle, can, glass	Mouthpiece, rim, outer surface	Saliva, sweat, skin cells
Used condom	Inside surface, outside surface	Semen, vaginal cells, rectal cells
Bed linen	Surface	Sweat, hair, semen, saliva, blood
Through-and-through bullet	Outside surface	Blood, tissue
Bite mark	Skin surface	Saliva
Fingernail, partial fingernail	Scrapings	Blood, sweat, tissue, skin cells

Source: National Institute of Justice. Using DNA to solve cold cases, Special Report, 2002, US Department of Justice, Office of Justice Programs, Washington, DC.



Figure 4.1 Representative types of evidence samples. Data compiled from the third quarter 2005 (July–September) results for all police forces in England and Wales. (Adapted from Bond, J.W., *J Forensic Sci*, 52, 128–136, 2007.)



Figure 4.2 Success rate of obtaining suitable profiles from processed samples for submitting to DNA databases. Data are from the third-quarter 2005 (July–September) results for all police forces in England and Wales. (Adapted from Bond, J.W., *J Forensic Sci*, 52, 128–136, 2007.)



Figure 4.3 Biosafety cabinet for the extraction of DNA from biological evidence (left). Blood samples to be processed in a biosafety cabinet for DNA isolation (right). (© Richard C. Li.)

are referred to as *circulating* nucleic acids; the nucleic acids that are found in other body fluids, such as saliva and urine, are referred to as *cell-free* nucleic acids. Extracellular nucleic acids can remain soluble or form complexes with proteins and lipids.

The potential sources of extracellular nucleic acids are *extracellular vesicles* (EVs). EVs are endogenous vesicular structures, containing proteins and nucleic acids that are secreted by most eukaryotic cells (Figure 4.4). There are many types of EVs, including exosomes and microvesicles, which can be detected in bodily fluids. *Exosomes* are one potential source of extracellular nucleic acids. Exosomes are derived from multivesicular bodies (MVBs), which are intracellular organelles of the endocytic pathway (Figure 4.4a). MVBs fuse with the plasma membrane. As a result, the vesicles are released into the extracellular compartment as exosomes. *Microvesicles*, also called shed vesicles or ectosomes, are another possibility. Microvesicles shed from the plasma membrane and thus carry along membrane and cytosolic materials including nucleic acids (Figure 4.4b). *Apoptotic bodies* are a special type of microvesicle that is formed in apoptotic cells. During apoptosis, a process of programmed cell death, cells shrink and eventually form apoptotic bodies (Figure 4.5). Apoptotic bodies contain fragmented DNA by nucleolytic degradation that resembles similar characteristics to those observed in extracellular nucleic acids. However, messenger RNA (mRNA) within apoptotic bodies is protected from RNase degradation. These



Figure 4.4 Exosomes and microvesicles released from healthy cells. (a) Exosomes are derived from the endocytic pathway. In the endocytic pathway, clathrin-coated vesicles (CCV) are formed at the plasma membrane. The endocytic vesicles are then formed through endocytosis and are transported to early endosomes. Multivesicular bodies (MVBs) containing intraluminal vesicles (ILVs) are then developed from early endosomes. Through the exocytic fusion of the MVB membrane with the plasma membrane of the cell, exosomes, containing cellular components including nucleic acids, are released to the extracellular space. (b) Microvesicles are derived from the budding of vesicles from the plasma membrane. Microvesicles are then shed from the plasma membrane carrying along cellular components including nucleic acids that are present in the cytoplasm. (© Richard C. Li.)



Figure 4.5 Apoptotic bodies released during apoptosis. During apoptosis, the preapoptotic cell (left) undergoes morphological changes. The early apoptotic cell (middle) shows deformation: the cell shrinks, the membrane blebs, and chromatin condense. The late apoptotic cells (right) are fragmented, releasing apoptotic bodies, which contain cytosol and organelles, and nuclear fragments. In addition, proteolytic enzymes are activated that cleave the genomic DNA into fragments. (© Richard C. Li.)

extracellular nucleic acids are potentially useful sources for the forensic identification of bodily fluids and for forensic DNA profiling.

4.2 Cells

4.2.1 Cell Surface Markers

Many of the forensic markers that are analyzed in forensic laboratories are from cells, the building blocks of the human body. All cells have membranes, also known as plasma membranes, which constitute their outer boundaries (Figure 4.6). The functions of cell membranes include exchanges with the environment, signal transduction, and structural support. The cell membrane is a phospholipid bilayer containing lipids, proteins, and carbohydrates. Membrane proteins can act as enzymes, receptors, or ion channels. Many cells also have carbohydrate-rich molecules, including proteoglycans, glycoproteins, and glycolipids, on their membrane surfaces (Figure 4.6). Many of these molecules act as cell surface antigens (Chapter 18).

4.2.2 Nucleated Cells

Probative biological evidence usually contains nucleated cells. The *nucleus* (Figure 4.7) is surrounded by a nuclear envelope and contains chromosomes and a nucleolus. A nucleolus is a dense, non-membrane-bound structure due to its high RNA content. The function of a nucleolus is to transcribe ribosomal RNA and to form ribosomes.

There are two types of cells in the body: sex cells (sperm and oocytes) and somatic cells (all other types). Spermatozoa and ova, which are formed by germ cells, are called *gametes*. In humans, each gamete is haploid, containing 22 *autosomes* (chromosomes other than sex chromosomes) plus one *sex chromosome*. In ova, the sex chromosome is always an X, while in spermatozoa it may be an X or a Y. After fertilization, the zygote, which is the fertilized egg cell formed when two gamete cells are joined, becomes diploid as a result of the fusion of the haploid spermatozoon and ovum. Most of the other cells of the body, known as *somatic cells*, are diploid. This means that they have two copies of each autosome plus two sex chromosomes, XX for females or XY for males. This results in a total of 46 chromosomes per diploid cell. The two chromosomes of a pair in a diploid cell are *homologous chromosomes*. One of the homologous chromosomes is inherited from the spermatozoon and the other from the ovum.



Figure 4.6 Cell membrane and carbohydrate-containing glycoproteins and glycolipids. (© Richard C. Li.)



Figure 4.7 A cross-sectional view of a cell. 1, Microvilli; 2, cilia; 3, cytoskeleton; 4, centrioles; 5, mitochondrium; 6, smooth endoplasmic reticulum; 7, rough endoplasmic reticulum; 8, nucleolus; 9, peroxisome; 10, vesicle; 11, Golgi apparatus; and 12, lysosome. (© Richard C. Li.)

Although most somatic cells are diploid, exceptions exist. Some differentiated cells such as red blood cells and platelets have no nuclei and are designated *nulliploid*. A few other cells have more than two sets of chromosomes as a result of DNA replication without cell division and are referred to as *polyploid*. For example, the regenerating cells of the liver and other tissues are naturally tetraploid, while the giant megakaryocytes of the bone marrow may contain 8, 16, or even 32 copies of chromosomes.

The nuclear *chromosomes* of humans consist of complexes of DNA, histone proteins, and nonhistone chromosomal proteins. Each chromosome consists of one linear, double-stranded DNA molecule. The large amounts of DNA present in the human chromosome are compacted by their association with histones into nucleosomes and even further compacted by higher levels of folding of the nucleosomes into *chromatin* fibers. Each chromosome contains a large number of looped domains of chromatin fibers attached to a protein scaffold.

The degree of DNA packing varies throughout the cell cycle. During the metaphase of mitosis and meiosis of the cell cycle, chromatin is the most condensed. Two forms of chromatin have been defined on the basis of their chromosome-staining properties. *Euchromatin* regions are areas of chromosomes that undergo normal chromosome condensation and decondensation during the cell cycle. The intensity of staining of euchromatin is darkest in the metaphase and lightest in the synthesis (S) phase. Euchromatic regions account for most of the genome and lack repetitive DNA. Usually, the genes within the euchromatin can be expressed. *Heterochromatin* comprises the chromosomal regions that usually remain condensed throughout the cell cycle. It contains repetitive DNA and can be found at centromeres, much of the Y chromosome long arm, and the short arms of the acrocentric chromosomes (chromosomes with centromeres near one end). Genes within heterochromatic DNA are usually inactive.



Figure 4.8 The ideogram of a human chromosome and cytogenetic banding nomenclature. The cytogenetic banding pattern is shown after chemical staining such as G-banding, which treats chromosomes with Giemsa dye. The short arm is designated p; the long arm is q. The centromere, p telomere (p-tel), and q telomere (q-tel) are also shown. G-bands at increasing resolution (from left to right) are shown. (© Richard C. Li.)

Each human chromosome has a short arm, designated p (for petit), and a long arm, designated q (for queue), separated by a centromere (Figure 4.8). *Centromeres* are the DNA sequences that are found near the points of attachment of mitotic or meiotic spindle fibers. The centromere region of each chromosome is responsible for accurately segregating the replicated chromosomes to daughter cells during cell divisions. The ends of the chromosome are called *telomeres* and they help stabilize the chromosome and play a role in the replication of DNA in the chromosome.

Chemical staining of metaphase chromosomes results in an alternating dark and light banding pattern (cytogenetic banding) that can be seen under a microscope. Each chromosome arm is divided into regions based on the cytogenic bands. This process is known as *cytogenetic mapping*. The cytogenetic bands are labeled p1, p2, p3, q1, q2, q3, and so on, counting from the centromere out toward the telomeres. At higher resolutions, subbands can be observed. For example, the cytogenetic map location of a gene termed *AMELY* (amelogenin, Y-linked; Chapter 21) is Yp11.2, which indicates its location on chromosome Y, p arm, band 11, subband 2. The visually distinct banding pattern gives each chromosome a unique appearance. Recently, the cytogenic map has been integrated with the human genome sequence to allow the determination of the positions of cytogenetic bands within the DNA sequence.

Chromosomes can be identified on the basis of the size and the positions of the centromeres and cytogenetic banding patterns. The chromosome constitution is described as a *karyotype* and can be displayed as a *karyogram*, which includes the total number of chromosomes and the sex chromosome composition (Figure 4.9). Chromosomes are numbered in order of their size, with chromosome 1 as the largest (except chromosome 21 is smaller than 22). In the cases of chromosomal abnormality, the karyotype can also reflect the type of abnormality and allow visualization of the affected chromosome bands.

4.2.3 Mitochondria and Other Organelles

The cytoplasm contains the cytosol fluid in which organelles are suspended (Figure 4.7). Multiple copies of *mitochondria* are located within the cytoplasm. Mitochondria are surrounded by phospholipid membranes that separate them from the cytosol. The mitochondria are responsible for energy production through aerobic metabolism by producing molecules containing high-energy bonds, such as adenosine triphosphate (ATP). Mitochondria have their own genome, which can be analyzed for human identification (Chapter 23).



Figure 4.9 Human karyogram. The chromosomes are numbered. Cytogenic patterns show alternating dark and light bands (From www.genome.gov). Centromeres (in red) are shown.

Two types of *endoplasmic reticulum* (ER) can exist within the cytoplasm: the smooth ER (SER) is involved in lipid synthesis; the rough ER (RER) contains ribosomes on its outer surface and forms transport vesicles. The *Golgi apparatus* is responsible for the production of secretory vesicles and new membrane components, and also for the packaging of *lysosomes* (vesicles containing digestive enzymes for the degradation of injured cells). *Peroxisomes* carry enzymes that neutralize potentially harmful free radicals. Other organelles found within the cytoplasm of eukaryotic cells include the cytoskeleton, microvilli, centrioles, and cilia.

4.2.4 Cytosol

4.2.4.1 Messenger RNAs

The chromosomal DNA contains genes that encode for specific proteins. The genetic code is read as an array of triplet codes, a sequence of three bases that specifies the identity of a single amino acid. As gene expression is activated, transcription occurs in which precursor mRNA (pre-mRNA) is produced from a DNA template. After transcription, the pre-mRNA is capped, polyadenylated, and spliced to form matured mRNA. Only the matured mRNA is transported from the nucleus to the cytoplasm. Tissue-specific mRNA can be potentially used for the identification of biological evidence (Chapter 11). The proteins are synthesized in a process known as translation, in which amino acids are assembled based on the codons derived from the triplet code of the DNA contained in the sequence of the mRNA strand. Various components including the ribosomal complex are involved in translation. The cytosol also contains many proteins that can be used for the identification of bodily fluids (Chapters 11 and 12).

4.2.4.2 MicroRNAs

MicroRNAs (miRNAs) are short RNA molecules that are 21–23 nucleotides in length. In eukaryotic organisms, miRNAs function as negative regulators of gene expression. They play roles in development and cell differentiation. Additionally, the altered expression of miRNAs can be detected in many human diseases. The biological function and the potential application of miRNAs in forensic biology are discussed in Chapter 11.

It is estimated that the human genome may encode approximately 1000 miRNAs. Based on their genomic location and structure, miRNAs can be characterized into three types: intergenic, intronic, and exonic (Figure 4.10). *Intergenic* miRNA genes are distinct transcriptional units that are found in genomic regions. In humans, most of the intergenic miRNA genes have a transcription start site and a polyadenylation site. *Intronic* miRNAs reside within the introns of protein-coding and noncoding genes. The orientation of the intronic miRNAs can be the same as that of the sense (coding) strand of a host gene or that of the antisense strand (complementary to the sense strand) of a host gene. Sense intronic miRNAs are transcribed from the same promoter as their host genes. The antisense intronic miRNAs are transcribed from their own promoters. *Exonic* miRNAs are rare in eukaryotic genomes and reside in genomic regions that overlap with an exon and an intron of a pseudogene, which is a noncoding gene or is no longer transcribed. These miRNAs are also transcribed from their host gene promoter. miRNAs can also be monocistronic or polycistronic. A *monocistronic* miRNA has a single transcriptional unit with its own promoter. In *polycistronic* miRNAs, several miRNAs reside as a cluster of transcriptional units with a shared promoter.

The biogenesis of miRNAs begins in the nucleus. miRNAs are transcribed by RNA polymerase II. Nascent transcripts, referred to as primary transcripts (pri-miRNAs), can be several hundreds to thousands of nucleotides in length. The pri-miRNAs have a hairpin secondary



Figure 4.10 The genomic location and the structure of miRNAs. (a) An intergenic miRNA gene, (b) a sense intronic miRNA gene, (c) an antisense intronic miRNA gene, (d) an exonic miRNA gene, (e) a monocistronic miRNA gene, and (f) polycistronic miRNA genes. Exons (gray), introns (white), and miRNA genes (red) are shown. (© Richard C. Li.)

structure that is approximately 70 nucleotides long with imperfect base pairing in the stem. miRNA processing is initiated in the nucleus (Figure 4.11). The hairpin region of a pri-miRNA is then cleaved from the pri-miRNA by the nuclear RNase III endonuclease, Drosha. As a result, a pre-miRNA is formed. The pre-miRNA is transported from the nucleus to the cytoplasm by a nuclear transporter, Exportin 5. In the cytoplasm, a cytoplasmic RNAse III–like endonuclease, Dicer, cleaves the pre-miRNA to generate a double-stranded miRNA that is approximately 21–23 nucleotides in length. The mature miRNA strand is bound to the Argonaut protein to assemble the RNA-induced silencing complex (RISC). The complementary RNA strand is degraded.

A specific miRNA is designated with a prefix. The prefix for a mature miRNA is a capitalized “miR,” while the prefix for a pre-miRNA is an uncapitalized “mir.” The prefix “miR” is followed by a dash and a number (e.g., miR-135). Experimentally confirmed miRNAs are sequentially numbered and are deposited in the miRBase, which is a database that archives miRNA sequences and annotations.



Figure 4.11 The biogenesis of miRNAs. In the nucleus, the pri-miRNA (primary transcript) is processed by Drosha (nuclear RNase for double-stranded RNA) and DGCR (nuclear double-stranded RNA-binding protein), forming the pre-miRNA. The pre-miRNA is transported from the nucleus to the cytoplasm by the exportin. In the cytoplasm, the pre-miRNA is further processed by Dicer (cytoplasmic RNase for double-stranded RNA) and TRBP (cytoplasmic double-stranded RNA-binding protein). The mature miRNA strand is bound to the Argonaut protein to assemble the RISC (RNA-induced silencing complex). (© Richard C. Li.)

4.3 Tissues

4.3.1 Skin

4.3.1.1 Biology of Skin

The biological evidence related to skin is important in forensic investigations. For example, fingerprints are ridge skin impressions that are usually collected at crime scenes, and shed skin tissue is a source of DNA for human identification. The skin covers the entire body surface. Additionally, the skin contains specialized structures that include sebaceous and sweat glands, hair follicles, and nails. The thickness of skin varies throughout the body. The skin of the dorsal area of the body is usually thicker than that of the ventral area of the body. The skin consists of different layers (Figure 4.12). The *epidermis* is the outer layer of the skin. The epidermis also contains melanocytes that produce the skin pigment melanin. The *dermis* is the middle layer of the skin. It is filled with fibrous collagen proteins secreted by fibroblasts and contains hair follicles and sweat glands. Additionally, it contains blood, lymph vessels, and nerves. The *subcutaneous layer* is the deepest layer of the skin. The subcutaneous layer consists of collagen networks and adipose tissue to prevent loss of heat.

The epidermis is a multilayered tissue that includes a number of morphologically distinct zones: the basal, the spinous, the granular, and the cornified layers (Figure 4.12). The epidermis renews continually through the proliferation and differentiation of keratinocytes. The *basal layer* contains newly formed keratinocytes that are proliferative. Epidermal differentiation begins with the migration of the keratinocytes from the basal layer toward the outer layer of skin. Once the migrating keratinocytes reach the *spinous* and *granular* layers, the keratinocytes become nonproliferating and partially differentiated. As the cells reach the *cornified* layer, these cells are filled with keratin filaments and are differentiated into corneocytes, which are dead, and terminally differentiated keratinocytes. In the course of differentiation, the cells are flattened, and all organelles including the nucleus are lost. The corneocytes are then shed from the skin surface.

4.3.1.2 Skin as Source of DNA Evidence

Evidence from skin contact, also referred to as *touched evidence*, can be collected and used for forensic DNA analysis. One example of this evidence is shed skin cells that are found on worn clothing, which is frequently encountered in crime scene investigations. For instance, a perpetrator's shed skin cells that are deposited on worn clothing are potential evidence to be collected. After collection, a DNA profile can be obtained from shed skin cells, providing the forensic evidence or "lead" that is required for the criminal investigation. Touched evidence becomes more



Figure 4.12 A sectional view of the skin. Multilayered epidermis tissues are shown. (© Richard C. Li.)

useful and important when no other type of evidence (e.g., a fingerprint, bloodstain, or seminal stain) can be collected at the crime scene, especially for the investigation of certain criminal cases such as cold cases and property crimes such as theft and burglary (Figures 4.13 through 4.15). Touched evidence usually contains minute quantities of nuclear DNA. DNA recovered from touched evidence is referred to as *transfer DNA*. However, the source of DNA transferred through physical contact is not well understood. Although the shed skin cells from touched evidence lack nuclei, these cells may contain DNA remnants from partial degradation during the differentiation process. These can be a possible DNA source. Additionally, the sweat glands in the skin produce sweat. When the skin makes contact with an item, a residue of sweat is left on the surface of the item. It is known that sweat contains cell-free DNA. Thus, cell-free DNA from sweat is another possible source of DNA. Furthermore, a small number of nucleated cells can be observed in touched evidence. These cells possibly originated from sweat glands and ducts.

4.3.2 Hair

Hairs, including scalp and pubic hairs, frequently constitute biological evidence that is found at crime scenes, and their identification can be of great forensic importance. Formerly, the



Figure 4.13 Evidence collection using swabbing. The evidence from skin contact for forensic DNA analysis is usually collected by swabbing. More DNA can be recovered when evidence is collected with a double swab method than with a single swab. The double swab method involves applying a moistened cotton swab followed by a second dry cotton swab onto the same target surface of evidence. The target surface is swabbed using a moistened swab first. The moisture left by the first swab is absorbed by the second dry swab. Both swabs can be pooled for DNA extraction. (© Richard C. Li.)



Figure 4.14 A worn glove as a source of DNA evidence. Shed skin cells on a worn glove can potentially generate DNA profiles. (© Richard C. Li.)



Figure 4.15 A cigarette butt as a source of DNA evidence. Shed cells left behind on a cigarette butt can be a source of DNA. A portion (~1 cm^2) of the filter paper of a smoked cigarette butt can be cut for isolating DNA. (© Richard C. Li.)

principal methods that were utilized in forensic hair analysis were limited to morphological analysis and comparisons. Since then, protein polymorphisms provide some potential for identifying individuals from single hairs. However, human hairs contain DNA and as a DNA source they may be used for forensic analysis. The development of the polymerase chain reaction (PCR) amplification technique made it possible to analyze very small quantities of DNA in hair, and the use of hair as evidence of identification has become more significant.

4.3.2.1 Biology of Hair

The human hair shaft is a keratinized cylindrical structure (Figure 4.16). The center or core of the hair is called the *medulla*, which is present in the majority of hairs. The medulla is surrounded by a *cortex*, which is the outer layer of the hair shaft. The *cuticle* consists of overlapping layers of flattened keratinized cells that protect the hair. Hairs are produced in *hair follicles* (Figures 4.17 and 4.18). Each hair follicle is located deep in the dermis (a skin layer beneath the epidermis) and opens onto the surface of the epidermis (the outer layer of the skin). The hair follicle is composed



Figure 4.16 A sectional view of a hair shaft. (© Richard C. Li.)



Figure 4.17 Longitudinal section view of a scalp hair follicle with accessory structures. (© Richard C. Li.)

of the *bulge* and the *bulb* regions. The bulge exports the stem cells that migrate down and give rise to bulb cells. The bulge also produces the stem cells that migrate up to form skin cells. The matrix cells, which generate the hair shaft cells, are located at the lower portion of the bulb. The *dermal papilla* is situated at the base of the bulb and contains cells that regulate hair growth, which are nourished by blood vessels and nerves. The growing hair shaft is surrounded by two concentric layers of cells, which are referred to as the inner root sheath and the outer root sheath, respectively. The entire hair follicle is surrounded by a connective tissue sheath.

Human scalp hairs grow for a few years and shed according to the hair follicle cycle (Figures 4.19 through 4.21). A human scalp hair can grow at its highest rate of approximately 1 mm per day. The growing phase of hair is called the *anagen* phase. The matrix cells undergo rapid proliferation and eventually become differentiated cells such as hair shaft cells. As a hair grows, it is pushed toward the surface of the skin and becomes longer. During the migration upward, keratinization occurs as cells are filled with fibril keratin proteins. In these keratinizing cells, nuclei are absent. However, mitochondrial remnants can be observed. By the time a hair approaches the skin surface, cell death occurs at the medulla, cortex, and cuticle. At the end of the anagen phase, the matrix cells enter the *catagen* phase and undergo cell death, thus leading to the regression of the bulb. Hair follicles then enter the *telogen* phase: the stage of rest. When another cycle begins, the follicle produces a new bulb and the telogenic hair, also known as the club hair, is pushed to the surface and shed. On average, an adult loses approximately dozens of hairs daily.



Figure 4.18 Structure of an anagen-phase hair follicle. The diagram shows the hair follicle structure including the dermal papilla, sebaceous gland, bulge, bulb, and hair shaft. Concentric layers of the outer root sheath (ORS), the inner root sheath (IRS), and the hair shaft are also shown. (© Richard C. Li)

4.3.2.2 Hair as Source of DNA Evidence

The isolation of DNA from intact hair roots is routinely used in nuclear DNA analysis. In comparison, the quantities of DNA in telogen hair roots are considerably less than the DNA that is found in the roots of anagen hairs. Nuclear DNA analysis is usually accomplished by using freshly plucked hair roots (Figures 4.22 and 4.23) because cells at the root region may contain nuclear DNA. Unfortunately, most human hairs recovered from crime scenes are shed naturally (in the telogen phase) and contain little nuclear DNA (Figure 4.24). Thus, multiple telogen hairs with roots are necessary to isolate enough nuclear DNA. However, shed hairs that are found at crime scenes may be derived from different individuals. Therefore, the ability to perform a forensic DNA analysis of a single shed hair would be highly desirable. Nuclear DNA isolation from hair shafts is still far less reliable because hair shafts contain very low amounts of nuclear DNA. In addition, variations in the amounts of DNA isolated from hair shafts are observed in a comparison between different hairs from the same head and hairs from different individuals.

A hair follicle cell contains multiple copies of mitochondria. As a result, mitochondrial DNA (mtDNA) can be successfully isolated from hair roots. Additionally, mtDNA is embedded in the keratin matrix of hair shaft cells, which protects the mtDNA molecules from degradation. Thus, mtDNA can also be isolated from hair shafts. A sequence polymorphism analysis of mtDNA from hair can be carried out. mtDNA is maternally inherited, which is useful to identify maternal relatives but cannot be used to perform paternity testing. Additionally, the mtDNA profiling results are not as discriminating as nuclear DNA profiling. Furthermore, mtDNA analysis is time-consuming. Therefore, the typing of nuclear DNA from hair would be preferable for forensic DNA analysis.

Sometimes, a mixture of more than one mtDNA sequence in the same individual is observed. This heterogeneous pool of mtDNA molecules is referred to as *heteroplasmy*. In hair, it is



Figure 4.19 Diagrammatic representation of the scalp hair cycle. The morphological characteristics of a hair follicle are shown in three distinct phases encompassing the entire hair cycle: anagen (including early and full anagen), catagen, and telogen. DP, dermal papilla; M, matrix; ORS, outer root sheath; SG, sebaceous gland. (© Richard C. Li.)

believed that it is due to a mixture of mtDNA molecules from keratinocyte and melanocyte-derived mitochondria (Figure 4.25). Hair follicle melanocytes are formed at the beginning of each hair cycle and die at the end of the cycle. Melanocytes are located in the bulb hair follicle. Hair melanocytes play roles in hair pigmentation, which determine hair color. Melanin, which is produced by the melanocytes, is contained in an organelle called the *melanosome*. The melanosomes are transferred to neighboring keratinocytes though *dendritic processes*. In addition to melanosomes, the melanocyte mitochondria can also be transferred to keratinocytes. Thus, the keratinized cells in the hair shaft may carry more than one type of mitochondria, one from the keratinocytes and the other from the melanocytes. As a result, heteroplasmy of a mixture of different mtDNA molecules, with different DNA sequences, can occur in hairs.

4.3.3 Bone

4.3.3.1 Biology of Bone

The bodies of human remains begin to decompose shortly after death. The rate of decomposition of human remains varies greatly with environmental conditions such as climate, bacterial growth, and the presence of insects and other animal scavengers. However, soft tissues may be lost first while more stable bone tissues may remain. Identifying human skeletal remains can be applied in a variety of cases including mass fatality incidents, missing persons, fires, explosions, and violent crime cases involving skeletal remains.

An adult human skeleton consists of 206 bones (Figures 4.26 and 4.27). The shaft of a long bone, such as an arm or a leg bone, consists largely of an outer layer of *cortical* (or compact) bone, which is solid and strong. The shaft of a long bone forms a *marrow cavity*, which is filled with a specialized type of connective tissue called bone marrow. The portion at each end of a



Figure 4.20 Longitudinal section view of a scalp hair follicle during the hair cycle. (a) Early anagen, (b) full anagen, (c) catagen, and (d) telogen. (© Richard C. Li.)



Figure 4.21 Cross-sectional view of hair follicles. (a) Early anagen and (b) full anagen. Note that the new hair (arrow) and the club hair are shown. (© Richard C. Li.)

long bone is called the *epiphysis*, which is composed largely of *cancellous* (or spongy) bone, and can bear the force of compression. A flat bone can have primarily either cortical or cancellous bone. For instance, a rib consists of primarily cancellous bone surrounded by a thin layer of cortical bone. A skull bone usually consists of largely cortical bone.

Bone, which is a connective tissue, contains a matrix and cells. The bone matrix consists of an inorganic and an organic matrix. Calcium and phosphorus are the major components of the inorganic matrix, which consists mainly of hydroxyapatite crystals, $Ca_{10}(PO_4)_6(OH)_2$. The organic matrix consists of collagens, primarily type I collagen, which are insoluble fibrous proteins. With the deposition of calcium hydroxyapatite crystals around the collagen fibrils, bone becomes a weight-bearing hard tissue.



Figure 4.22 Hair root of a pulled hair with visible soft tissue attached. (© Richard C. Li.)



Figure 4.23 Pulled dreadlocks recovered from a crime scene. (© Richard C. Li.)

Developing bones contain small numbers of *osteoprogenitor* cells. These cells can divide to produce cells that differentiate into *osteoblasts*. Osteoblast cells regulate the calcification of the bone matrix. Osteoblasts that are embedded in the bone matrix are termed *osteocytes* and are the most abundant cells in bone. Osteocytes play a role in maintaining the surrounding matrix and repairing damaged bone. Another type of cell that can be found in bone tissues is *osteoclasts*. These cells are giant cells containing 50 or more nuclei and are responsible for dissolving and recycling the bone matrix.

4.3.3.2 Bone as Source of DNA Evidence

A number of methods are used to identify human remains, for example: the identification of facial characteristics; the recognition of individualizing scars, marks, and other special body



Figure 4.24 Telogen hair roots. From left to right: telogen club root with no visible soft tissue; telogen hair root with some visible soft tissue; telogen hair root with visible soft tissue. (From Bourguignon, L. et al., *Forensic Sci Int Genet*, 3, 27–31, 2008. With permission.)



Figure 4.25 Scheme diagram of the melanosome transportation. Melanosomes are released into the extracellular space from the melanocyte dendrites through exocytosis and subsequent endocytosis by keratinocytes. During the process, mitochondria originating from the melanocytes can be potentially transported to the keratinocytes. (© Richard C. Li.)

features; the matching of dentition with premortem dental x-rays; and the comparison of fingerprints. In some situations, these methods cannot be used because of the extensive decomposition of the remains. The mass fatality terrorist attack on the World Trade Center in 2001 (Figure 4.28) serves as an example of a situation where common identification techniques may not be useful. Large quantities of compromised human skeletal fragments were recovered at the fatality site. In these cases, DNA typing is a powerful tool for identifying human remains.

Most DNA in cortical bone is located in the osteocytes. It has been estimated that there are approximately 20,000 osteocytes per cubic millimeter of calcified bone matrix. As a result, microgram quantities of DNA can potentially be obtained from a gram of bone. Thus, compact bone tissue should contain sufficient amounts of nuclear DNA for analysis. However, the skeletal fragments recovered from burial sites are often subjected to decomposition (Figures 4.29 and 4.30). During the decomposition process, both nuclear and mtDNA can be degraded.



Figure 4.26 Bone structure. An adult human consists of 206 bones. A long bone, such as an arm or a leg bone, consists of an outer cylinder of cortical bone surrounding a marrow cavity. Each end of a long bone is called the epiphysis, which is composed largely of cancellous bone. Flat bones have variable structures; for example, the skull consists mainly of cortical bone whereas the spine consists mainly of cancellous bone. (a) Diagram of a long bone. (b) A bone fragment. Cortical and cancellous bones are shown. Blood vessels can be found in the Volkmann and Haversian canals. (© Richard C. Li.)

Additionally, burial conditions with high humidity and temperature promote the degradation of DNA. Thus, the identification of partial DNA profiles or the complete failure to obtain DNA profiles can occur after samples from decomposed remains are analyzed.

Processing bone samples for DNA extraction is a time-consuming task (Figure 4.31). Due to the potential for commingled remains and contaminants that interfere with forensic analysis, a bone sample initially must be cleaned prior to isolating DNA. The outer surfaces of bone fragments are usually removed by using a mechanical method such as sanding. However, to avoid cross-contamination of samples, the bone dust that is generated by sanding must be removed. Additionally, special protective equipment and safety procedures are necessary to protect analysts from exposure to blood-borne pathogens.

To obtain adequate quality and quantity of DNA from a bone sample, a high-yield DNA extraction method should be selected. The bone samples can be ground to powder to aid in DNA extraction (Chapter 5). The osteocytes containing DNA are embedded in a calcified bone matrix, which is a barrier for extracting DNA from the osteocytes. The bone matrix must be



Figure 4.27 Cross-sectional view of cortical bone. (a) The functional unit of cortical bones is a cylindrical structure known as osteon. Haversian canals are shown in the center of the osteon. (b) Detailed view of an osteon. Osteocytes (arrows) are shown within osteons. (© Richard C. Li.)

Figure 4.28 Sections of the Fire Department of New York City (FDNY) Memorial Wall. Memorial to the Fallen Firefighters of 9/11, at FDNY Engine Co. 10 on Liberty Street, New York, by Rambusch Studios. (© Richard C. Li.)



Figure 4.29 Human rib bone fragments recovered from burial site. (© Richard C. Li.)



Figure 4.30 Skeletal remains, exhumed from Frombork Cathedral in Poland, are thought to be those of astronomer Nicolaus Copernicus (1473–1543). (From Bogdanowicz, W., et al., *Proc Natl Acad Sci U S A*, 106, 12279–12282, 2009. With permission.)

removed to improve the yield of DNA. A decalcification method can be utilized to dissolve calcium ions to soften the bone tissue. Additionally, the application of proteinase can be used to digest the matrix proteins, thus increasing the yield of DNA that is harvested from osteocytes.

4.3.4 Teeth

4.3.4.1 Biology of Teeth

During embryonic development, two sets of teeth begin to form. The first to appear are the *deciduous teeth* or *primary teeth*. Most children have 20 deciduous teeth, which are later replaced by 32 teeth known as the *secondary dentition* or *permanent dentition* (Figure 4.32).



Figure 4.31 Tools for cutting bone samples. Osteotomes and a mallet (top), and a rotary device (bottom). (© Richard C. Li.)

The bulk of each tooth consists of a calcified connective tissue called *dentin* (Figure 4.33). The dentin of the crown is covered by a layer of *enamel*. The rest of the dentin is referred to as radicular dentin and is covered by a layer of *cementum*, which separates the tooth from the surrounding jawbone.

Similar to bone, tooth tissue contains a matrix. The inorganic matrix of tooth contains hydroxyapatite, a calcium phosphate in a crystalline form. The organic matrices of dentin and cementum are primarily collagens. In enamel, amelogenin is the major protein of the organic matrix. Other proteins include ameloblastin and enamelin, which are also the components of the enamel organic matrix.

The interior chamber within the tooth surrounded by dentin is known as the pulp cavity. The *dental pulp*, found within the pulp cavity, is the connective tissue made up of nerve fibers, blood vessels, and various cells. The blood vessels and nerves in the pulp cavity are innervated through the root canal, a narrow tunnel located at the root of the tooth. Incisor and cuspid teeth have single roots. Bicuspids have one or two roots. Molars typically have three or more roots.

The columnar cell bodies of *odontoblasts* are located along the peripheral dental pulp. A single *odontoblast process*, arising from each cell body of the odontoblasts, projects into the dentinal tubule (Figure 4.34). Odontoblasts play important roles in the formation of dentin. Odontoblasts secrete collagens and ground substances that are the components of the


Crown
Root
Enamel
Dentin
Gum
Pulp cavity
Blood vessels and nerves
Cementum
Root canal
Connective tissue
Bone

Figure 4.32 A sectional view of an adult tooth. (© Richard C. Li.)


Dentin
Odontoblasts
Pulp cavity

Figure 4.33 Cross-sectional view of a tooth. (© Richard C. Li.)

dentinal matrix. Additionally, odontoblasts regulate the calcification of the matrix of dentin. *Cementoblasts* are cells that play roles in forming the cementum. Cementoblasts secrete collagens and ground substances to form the extracellular matrix of the cementum. Through the process of forming cementum, cementoblasts become trapped in the extracellular matrix. The cementoblasts embedded in the cementum are referred to as *cementocytes*. *Ameloblasts* are cells that play a role in producing enamel and are subsequently lost during tooth eruption.

4.3.4.2 Teeth as Source of DNA Evidence

The characteristics of teeth, their alignment, and the overall structure of the mouth provide information for identifying a person. The use of dental records such as x-rays and dental casts can allow dental remains to be connected to a victim. Particularly in circumstances such as



Figure 4.34 Odontoblast processes. See Section 4.3.4.1. (© Richard C. Li.)



Figure 4.35 Tools for dissecting teeth. (© Richard C. Li.) (a) A dental chisel and a mallet. (© Richard C. Li.) (b) An amalgam well. (Courtesy of Dr. Ken Hermsen.)

decomposition, an odontological comparison is possible since the dental evidence often remains intact. When no antemortem dental record is available for comparison, forensic DNA testing can be carried out for postmortem human identification. The mineralized dental structure protects DNA from degradation in cases where it may be degraded in other tissues of the body. Thus, teeth are an excellent source of DNA for forensic DNA analysis under such conditions.

Dental pulp tissue contains various cells and is a suitable source of DNA. However, when tooth evidence has been exposed to high temperature and humid environments, decomposition of the pulp tissue can occur. Thus, cementoblasts within the cementum, containing both nuclei and mitochondria, can then be utilized as a source of DNA. Additionally, odontoblast processes within dentin, containing mitochondria, can also be used. Several different methods are used to obtain dental tissues for DNA isolation (Figure 4.35). A vertical section is cut along the longitudinal axis of the tooth, which allows the dissection of the pulp, dentin, and cementum tissues



Figure 4.36 Dissecting teeth for DNA isolation. Vertical cutting and dissecting of the pulp, dentin, and cementum tissues (left) and horizontal cutting and dissecting of the root portion (right). (Courtesy of Dr. Ken Hermsen.)



Figure 4.37 Extraction of pulp tissue using endodontic access procedures: trepanning the occlusal surface of a tooth using a dental bur mounted on a turbine (a), creating a cavity for endodontic access (b), and extracting pulp tissue using a nerve broach (a). (© Richard C. Li.)

(Figure 4.36). A horizontal section is cut through the cementum–enamel junction of the tooth (Figure 4.36). The root portion can be pulverized to a fine powder for DNA isolation. The crown can be preserved for forensic odontological comparisons if needed. Additionally, the extraction of pulp tissue can be carried out by standard endodontic access (Figure 4.37). For calcified tissues such as dentin and cementum, a decalcification step is needed to soften the dental matrix, which facilitates DNA isolation.

Bibliography

Abaz, J., et al., Comparison of the variables affecting the recovery of DNA from common drinking containers. *Forensic Sci Int*, 2002, **126**(3): 233–240.

Aditya, S., C.N. Bhattacharyya, and K. Chaudhuri, Generating STR profile from "Touch DNA". *J Forensic Leg Med*, 2011, **18**(7): 295–298.

Alakoc, Y.D. and P.S. Aka, "Orthograde entrance technique" to recover DNA from ancient teeth preserving the physical structure. *Forensic Sci Int*, 2009, **188**(1–3): 96–98.

Allouche, M., et al., Genetic identification of decomposed cadavers using nails as DNA source. *Forensic Sci Int Genet*, 2008, **3**(1): 46–49.

Alvarez Garcia, A., et al., Effect of environmental factors on PCR-DNA analysis from dental pulp. *Int J Legal Med*, 1996, **109**(3): 125–129.

Amory, S., et al., STR typing of ancient DNA extracted from hair shafts of Siberian mummies. *Forensic Sci Int*, 2007, **166**(2–3): 218–229.

Anderson, T.D., et al., A validation study for the extraction and analysis of DNA from human nail material and its application to forensic casework. *J Forensic Sci*, 1999, **44**(5): 1053–1056.

Anzai-Kanto, E., et al., DNA extraction from human saliva deposited on skin and its use in forensic identification procedures. *Pesqui Odontol Bras*, 2005, **19**(3): 216–222.

Barbaro, A., P. Cormaci, and A. Barbaro, Detection of STRs from body fluid collected on IsoCode paper-based devices. *Forensic Sci Int*, 2004, **146**(Suppl): S127–S128.

Barbaro, A., P. Cormaci, and A. Barbaro, DNA analysis from mixed biological materials. *Forensic Sci Int*, 2004, **146**(Suppl): S123–S125.

Barbaro, A., et al., Anonymous letters? DNA and fingerprints technologies combined to solve a case. *Forensic Sci Int*, 2004, **146**(Suppl): S133–S134.

Berger, B., et al., Chimerism in DNA of buccal swabs from recipients after allogeneic hematopoietic stem cell transplantations: Implications for forensic DNA testing. *Int J Legal Med*, 2013, **127**(1): 49–54.

Bogdanowicz, W., et al., Genetic identification of putative remains of the famous astronomer Nicolaus Copernicus. *Proc Natl Acad Sci U S A*, 2009, **106**(30), 12279–12282.

Bond, J.W., Value of DNA evidence in detecting crime. *J Forensic Sci*, 2007, **52**(1): 128–136.

Bourguignon, L., et al., A fluorescent microscopy-screening test for efficient STR-typing of telogen hair roots. *Forensic Sci Int Genet*, 2008, **3**(1): 27–31.

Bright, J.A., et al., The effect of cleaning agents on the ability to obtain DNA profiles using the Identifiler™ and PowerPlex® Y Multiplex Kits. *J Forensic Sci*, 2011, **56**(1): 181–185.

Bruck, S., et al., Single cells for forensic DNA analysis—From evidence material to test tube. *J Forensic Sci*, 2011, **56**(1): 176–180.

Burger, M.F., E.Y. Song, and J.W. Schumm, Buccal DNA samples for DNA typing: New collection and processing methods. *Biotechniques*, 2005, **39**(2): 257–261.

Castella, V., M. Lesta Mdel, and P. Mangin, One person with two DNA profiles: A(nother) case of mosaicism or chimerism. *Int J Legal Med*, 2009, **123**(5): 427–430.

Castella, V., et al., Successful DNA typing of ultrafiltered urines used to detect EPO doping. *Forensic Sci Int Genet*, 2007, **1**(3–4): 281–282.

Chiou, F.S., et al., Extraction of human DNA for PCR from chewed residues of betel quid using a novel "PVP/CTAB" method. *J Forensic Sci*, 2001, **46**(5): 1174–1179.

Cina, M.S., et al., Isolation and identification of male and female DNA on a postcoital condom. *Arch Pathol Lab Med*, 2000, **124**(7): 1083–1086.

Cook, O. and L. Dixon, The prevalence of mixed DNA profiles in fingernail samples taken from individuals in the general population. *Forensic Sci Int Genet*, 2007, **1**(1): 62–68.

Corte-Real, A., et al., The tooth for molecular analysis and identification: A forensic approach. *J Forensic Odontostomatol*, 2012, **30**(1): 22–28.

Courts, C. and B. Madea, Micro-RNA—A potential for forensic science? *Forensic Sci Int*, 2010, **203**(1–3): 106–111.

Courts, C., B. Madea, and C. Schyma, Persistence of biological traces in gun barrels—An approach to an experimental model. *Int J Legal Med*, 2012, **126**(3): 391–397.

Daly, D.J., C. Murphy, and S.D. McDermott, The transfer of touch DNA from hands to glass, fabric and wood. *Forensic Sci Int Genet*, 2012, **6**(1): 41–46.

de Lourdes Chavez-Briones, M., et al., Identification of human remains by DNA analysis of the gastrointestinal contents of fly larvae. *J Forensic Sci*, 2013, **58**(1): 248–250.

Delabarde, T., et al., The potential of forensic analysis on human bones found in riverine environment. *Forensic Sci Int*, 2013, **228**(1–3): e1–e5.

Dimo-Simonin, N., F. Grange, and C. Brandt-Casadevall, PCR-based forensic testing of DNA from stained cytological smears. *J Forensic Sci*, 1997, **42**(3): 506–509.

Dissing, J., A. Sondervang, and S. Lund, Exploring the limits for the survival of DNA in blood stains. *J Forensic Leg Med*, 2010, **17**(7): 392–396.

Dowlman, E.A., et al., The prevalence of mixed DNA profiles on fingernail swabs. *Sci Justice*, 2010, **50**(2): 64–71.

Durdle, A., R.J. Mitchell, and R.A. van Oorschot, The human DNA content in artifacts deposited by the blowfly *Lucilia cuprina* fed human blood, semen and saliva. *Forensic Sci Int*, 2013, **233**(1–3): 212–219.

Edson, S.M. and A.F. Christensen, Field contamination of skeletonized human remains with exogenous DNA. *J Forensic Sci*, 2013, **58**(1): 206–209.

Edson, J., et al., A quantitative assessment of a reliable screening technique for the STR analysis of telogen hair roots. *Forensic Sci Int Genet*, 2013, **7**(1): 180–188.

Ellis, M.A., et al., An evaluation of DNA yield, DNA quality and bite registration from a dental impression wafer. *J Am Dent Assoc*, 2007, **138**(9): 1234–1240; quiz 1267.

Farmen, R.K., et al., Assessing the presence of female DNA on post-coital penile swabs: Relevance to the investigation of sexual assault. *J Forensic Leg Med*, 2012, **19**(7): 386–389.

Flanagan, N. and C. McAlister, The transfer and persistence of DNA under the fingernails following digital penetration of the vagina. *Forensic Sci Int Genet*, 2011, **5**(5): 479–483.

Foran, D.R., M.E. Gehring, and S.E. Stallworth, The recovery and analysis of mitochondrial DNA from exploded pipe bombs. *J Forensic Sci*, 2009, **54**(1): 90–94.

Fridez, F. and R. Coquoz, PCR DNA typing of stamps: Evaluation of the DNA extraction. *Forensic Sci Int*, 1996, **78**(2): 103–110.

Goray, M., R.J. Mitchell, and R.A. van Oorschot, Investigation of secondary DNA transfer of skin cells under controlled test conditions. *Leg Med (Tokyo)*, 2010, **12**(3): 117–120.

Goray, M., J.R. Mitchell, and R.A. van Oorschot, Evaluation of multiple transfer of DNA using mock case scenarios. *Leg Med (Tokyo)*, 2012, **14**(1): 40–46.

Goray, M., R.A. van Oorschot, and J.R. Mitchell, DNA transfer within forensic exhibit packaging: Potential for DNA loss and relocation. *Forensic Sci Int Genet*, 2012, **6**(2): 158–166.

Goray, M., et al., Secondary DNA transfer of biological substances under varying test conditions. *Forensic Sci Int Genet*, 2010, **4**(2): 62–67.

Graham, E.A. and G.N. Rutty, Investigation into “normal” background DNA on adult necks: Implications for DNA profiling of manual strangulation victims. *J Forensic Sci*, 2008, **53**(5): 1074–1082.

Graham, E.A., E.E. Turk, and G.N. Rutty, Room temperature DNA preservation of soft tissue for rapid DNA extraction: An addition to the disaster victim identification investigators toolkit? *Forensic Sci Int Genet*, 2008, **2**(1): 29–34.

Grskovic, B., et al., Effect of ultraviolet C radiation on biological samples. *Croat Med J*, 2013, **54**(3): 263–271.

Grubwieser, P., et al., Systematic study on STR profiling on blood and saliva traces after visualization of fingerprint marks. *J Forensic Sci*, 2003, **48**(4): 733–741.

Gurvitz, A., L.Y. Lai, and B.A. Neilan, Exploiting biological materials in forensic science. *Australas Biotechnol*, 1994, **4**(2): 88–91.

Hellmann, A., et al., STR typing of human telogen hairs—A new approach. *Int J Legal Med*, 2001, **114**(4–5): 269–273.

Herber, B. and K. Herold, DNA typing of human dandruff. *J Forensic Sci*, 1998, **43**(3): 648–656.

Higgins, D. and J.J. Austin, Teeth as a source of DNA for forensic identification of human remains: A review. *Sci Justice*, 2013, **53**(4): 433–441.

Higuchi, R., et al., DNA typing from single hairs. *Nature*, 1988, **332**(6164): 543–546.

Hochmeister, M.N., PCR analysis of DNA from fresh and decomposed bodies and skeletal remains in medicolegal death investigations. *Methods Mol Biol*, 1998, **98**: 19–26.

Hochmeister, M.N., O. Rudin, and E. Ambach, PCR analysis from cigarette butts, postage stamps, envelope sealing flaps, and other saliva-stained material. *Methods Mol Biol*, 1998, **98**: 27–32.

Hochmeister, M.N., et al., PCR-based typing of DNA extracted from cigarette butts. *Int J Legal Med*, 1991, **104**(4): 229–233.

Hoile, R., et al., Gamma irradiation as a biological decontaminant and its effect on common fingermark detection techniques and DNA profiling. *J Forensic Sci*, 2010, **55**(1): 171–177.

Hopkins, B., et al., The use of minisatellite variant repeat-polymerase chain reaction (MVR-PCR) to determine the source of saliva on a used postage stamp. *J Forensic Sci*, 1994, **39**(2): 526–531.

Hopwood, A.J., A. Mannucci, and K.M. Sullivan, DNA typing from human faeces. *Int J Legal Med*, 1996, **108**(5): 237–243.

Hopwood, A., et al., Rapid quantification of DNA samples extracted from buccal scrapes prior to DNA profiling. *Biotechniques*, 1997, **23**(1): 18–20.

Johnson, D.J., A.C. Calderaro, and K.A. Roberts, Variation in nuclear DNA concentrations during urination. *J Forensic Sci*, 2007, **52**(1): 110–113.

Kaarstad, K., et al., The detection of female DNA from the penis in sexual assault cases. *J Forensic Leg Med*, 2007, **14**(3): 159–160.

Kaiser, C., et al., Molecular study of time dependent changes in DNA stability in soil buried skeletal residues. *Forensic Sci Int*, 2008, **177**(1): 32–36.

Kamodyova, N., et al., Prevalence and persistence of male DNA identified in mixed saliva samples after intense kissing. *Forensic Sci Int Genet*, 2013, **7**(1): 124–128.

Kamphausen, T., et al., Good shedder or bad shedder—The influence of skin diseases on forensic DNA analysis from epithelial abrasions. *Int J Legal Med*, 2012, **126**(1): 179–183.

Kenna, J., et al., The recovery and persistence of salivary DNA on human skin. *J Forensic Sci*, 2011, **56**(1): 170–175.

Kester, K.M., et al., Recovery of environmental human DNA by insects. *J Forensic Sci*, 2010, **55**(6): 1543–1551.

Kim, M., et al., Identification and long term stability of DNA captured on a dental impression wafer. *Pediatr Dent*, 2012, **34**(5): 373–377.

Kita, T., et al., Morphological study of fragmented DNA on touched objects. *Forensic Sci Int Genet*, 2008, **3**(1): 32–36.

Kitayama, T., et al., Evaluation of a new experimental kit for the extraction of DNA from bones and teeth using a non-powder method. *Leg Med (Tokyo)*, 2010, **12**(2): 84–89.

Kline, M.C., et al., Polymerase chain reaction amplification of DNA from aged blood stains: Quantitative evaluation of the "suitability for purpose" of four filter papers as archival media. *Anal Chem*, 2002, **74**(8): 1863–1869.

Kohnemann, S., et al., qPCR and mtDNA SNP analysis of experimentally degraded hair samples and its application in forensic casework. *Int J Legal Med*, 2010, **124**(4): 337–342.

Lee, E.J., et al., The effects of different maceration techniques on nuclear DNA amplification using human bone. *J Forensic Sci*, 2010, **55**(4): 1032–1038.

Li, R.C. and H.A. Harris, Using hydrophilic adhesive tape for collection of evidence for forensic DNA analysis. *J Forensic Sci*, 2003, **48**(6): 1318–1321.

Lijnen, I. and G. Willems, DNA research in forensic dentistry. *Methods Find Exp Clin Pharmacol*, 2001, **23**(9): 511–517.

Linacre, A., et al., Generation of DNA profiles from fabrics without DNA extraction. *Forensic Sci Int Genet*, 2010, **4**(2): 137–141.

Linch, C.A., The ultrastructure of tissue attached to telogen hair roots. *J Forensic Sci*, 2008, **53**(6): 1363–1366.

Linch, C.A., Degeneration of nuclei and mitochondria in human hairs. *J Forensic Sci*, 2009, **54**(2): 346–349.

Linch, C.A., et al., Specific melanin content in human hairs and mitochondrial DNA typing success. *Am J Forensic Med Pathol*, 2009, **30**(2): 162–166.

Lindahl, T., Instability and decay of the primary structure of DNA. *Nature*, 1993, **362**(6422): 709–715.

Lorente, M., et al., Dandruff as a potential source of DNA in forensic casework. *J Forensic Sci*, 1998, **43**(4): 901–902.

Maguire, S., et al., Retrieval of DNA from the faces of children aged 0–5 years: A technical note. *J Forensic Nurs*, 2008, **4**(1): 40–44.

Malsom, S., et al., The prevalence of mixed DNA profiles in fingernail samples taken from couples who cohabit using autosomal and Y-STRs. *Forensic Sci Int Genet*, 2009, **3**(2): 57–62.

Marrone, A. and J. Ballantyne, Changes in dry state hemoglobin over time do not increase the potential for oxidative DNA damage in dried blood. *PLoS One*, 2009, **4**(4): e5110.

Mayntz-Press, K.A., et al., Y-STR profiling in extended interval (> or = 3 days) postcoital cervicovaginal samples. *J Forensic Sci*, 2008, **53**(2): 342–348.

McCartney, C., LCN DNA: Proof beyond reasonable doubt? *Nat Rev Genet*, 2008, **9**(5): 325.

Medintz, I., et al., Restriction fragment length polymorphism and polymerase chain reaction-HLA DQ alpha analysis of casework urine specimens. *J Forensic Sci*, 1994, **39**(6): 1372–1380.

Misner, L.M., et al., The correlation between skeletal weathering and DNA quality and quantity. *J Forensic Sci*, 2009, **54**(4): 822–828.

National Institute of Justice. Using DNA to solve cold cases, Special Report, 2002, US Department of Justice, Office of Justice Programs, Washington, DC.

Ng, L.K., et al., Optimization of recovery of human DNA from envelope flaps using DNA IQ System for STR genotyping. *Forensic Sci Int Genet*, 2007, **1**(3–4): 283–286.

Niemcunowicz-Janica, A., et al., Typeability of PowerPlex Y (Promega) profiles in selected tissue samples incubated in various environments. *Arch Med Sadowej Kryminol*, 2007, **57**(4): 385–388.

Niemcunowicz-Janica, A., et al., Detectability of SGM Plus profiles in heart and lungs tissue samples incubated in different environments. *Leg Med (Tokyo)*, 2008, **10**(1): 35–38.

Nurit, B., et al., Evaluating the prevalence of DNA mixtures found in fingernail samples from victims and suspects in homicide cases. *Forensic Sci Int Genet*, 2011, **5**(5): 532–537.

O'Driscoll, L., Extracellular nucleic acids and their potential as diagnostic, prognostic and predictive biomarkers. *Anticancer Res*, 2007, **27**(3A): 1257–1265.

Offele, D., et al., Soft tissue removal by maceration and feeding of *Dermestes* sp.: Impact on morphological and biomolecular analyses of dental tissues in forensic medicine. *Int J Legal Med*, 2007, **121**(5): 341–348.

Ohira, H., et al., Effective appropriate use of dental remains and forensic DNA testing for personal identity confirmation. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S560–S562.

Opel, K.L., et al., Evaluation and quantification of nuclear DNA from human telogen hairs. *J Forensic Sci*, 2008, **53**(4): 853–857.

Paneto, G.G., et al., Heteroplasmy in hair: Differences among hair and blood from the same individuals are still a matter of debate. *Forensic Sci Int*, 2007, **173**(2–3): 117–121.

Pelotti, S., et al., Cancerous tissues in forensic genetic analysis. *Genet Test*, 2007, **11**(4): 397–400.

Pfeiffer, H., et al., Influence of soil storage and exposure period on DNA recovery from teeth. *Int J Legal Med*, 1999, **112**(2): 142–144.

Phipps, M. and S. Petricevic, The tendency of individuals to transfer DNA to handled items. *Forensic Sci Int*, 2007, **168**(2–3): 162–168.

Pinchi, V., et al., Techniques of dental DNA extraction: Some operative experiences. *Forensic Sci Int*, 2011, **204**(1–3): 111–114.

Prado, V.F., et al., Extraction of DNA from human skeletal remains: Practical applications in forensic sciences. *Genet Anal*, 1997, **14**(2): 41–44.

Quinones, I. and B. Daniel, Cell free DNA as a component of forensic evidence recovered from touched surfaces. *Forensic Sci Int Genet*, 2012, **6**(1): 26–30.

Raimann, P.E., et al., Procedures to recover DNA from pre-molar and molar teeth of decomposed cadavers with different post-mortem intervals. *Arch Oral Biol*, 2012, **57**(11): 1459–1466.

Ramasamy, S., A. Houspian, and F. Knott, Recovery of DNA and fingermarks following deployment of render-safe tools for vehicle-borne improvised explosive devices (VBIED). *Forensic Sci Int*, 2011, **210**(1–3): 182–187.

Remualdo, V.R. and R.N. Oliveira, Analysis of mitochondrial DNA from the teeth of a cadaver maintained in formaldehyde. *Am J Forensic Med Pathol*, 2007, **28**(2): 145–146.

Riemer, L.B., D. Fairley, and D. Sweet, DNA collection from used toothbrushes as a means to decedent identification. *Am J Forensic Med Pathol*, 2012, **33**(4): 354–356.

Roberts, K.A. and C. Calloway, Mitochondrial DNA amplification success rate as a function of hair morphology. *J Forensic Sci*, 2007, **52**(1): 40–47.

Roeper, A., W. Reichert, and R. Mattern, The Achilles tendon as a DNA source for STR typing of highly decayed corpses. *Forensic Sci Int*, 2007, **173**(2–3): 103–106.

Rubio, L., et al., Study of short- and long-term storage of teeth and its influence on DNA. *J Forensic Sci*, 2009, **54**(6): 1411–1413.

Rubio, L., et al., Time-dependent changes in DNA stability in decomposing teeth over 18 months. *Acta Odontol Scand*, 2013, **71**(3–4): 638–643.

Salvador, J.M. and M.C. De Ungria, Isolation of DNA from saliva of betel quid chewers using treated cards. *J Forensic Sci*, 2003, **48**(4): 794–797.

Schneider, H., et al., Hot flakes in cold cases. *Int J Legal Med*, 2011, **125**(4): 543–548.

Schwark, T., et al., Phantoms in the mortuary—DNA transfer during autopsies. *Forensic Sci Int*, 2012, **216**(1–3): 121–126.

Sewell, J., et al., Recovery of DNA and fingerprints from touched documents. *Forensic Sci Int Genet*, 2008, **2**(4): 281–285.

Shaw, K., et al., Comparison of the effects of sterilisation techniques on subsequent DNA profiling. *Int J Legal Med*, 2007, **122**(1): 29–33.

Shintani-Ishida, K., et al., Usefulness of blood vessels as a DNA source for PCR-based genotyping based on two cases of corpse dismemberment. *Leg Med (Tokyo)*, 2010, **12**(1): 8–12.

Simons, J.L. and S.K. Vintiner, Effects of histological staining on the analysis of human DNA from archived slides. *J Forensic Sci*, 2011, **56**(Suppl 1): S223–S228.

Soares-Vieira, J.A., et al., Y-STRs in forensic medicine: DNA analysis in semen samples of azoospermic individuals. *J Forensic Sci*, 2007, **52**(3): 664–670.

Sosa, C., et al., Nuclear DNA typing from ancient teeth. *Am J Forensic Med Pathol*, 2012, **33**(3): 211–214.

Sosa, C., et al., Association between ancient bone preservation and DNA yield: A multidisciplinary approach. *Am J Phys Anthropol*, 2013, **151**(1): 102–109.

Springer, E.E., T.L. Laber, and B.B. Randall, The examination of vaginally inserted plastic tampon applicators for genetic markers and evidence of prior sexual intercourse. *J Forensic Sci*, 1988, **33**(5): 1139–1145.

Steadman, D.W., et al., The effects of chemical and heat maceration techniques on the recovery of nuclear and mitochondrial DNA from bone. *J Forensic Sci*, 2006, **51**(1): 11–17.

Szabo, S., et al., *In situ* labeling of DNA reveals interindividual variation in nuclear DNA breakdown in hair and may be useful to predict success of forensic genotyping of hair. *Int J Legal Med*, 2012, **126**(1): 63–70.

Taguchi, M., et al., DNA identification of formalin-fixed organs is affected by fixation time and type of fixatives: Using the AmpF l STR(R) Identifiler(R) PCR Amplification Kit. *Med Sci Law*, 2012, **52**(1): 12–16.

Tanaka, M., et al., Usefulness of a toothbrush as a source of evidential DNA for typing. *J Forensic Sci*, 2000, **45**(3): 674–676.

Tang, D.L., et al., Multiplex fluorescent PCR for noninvasive prenatal detection of fetal-derived paternally inherited diseases using circulatory fetal DNA in maternal plasma. *Eur J Obstet Gynecol Reprod Biol*, 2009, **144**(1): 35–39.

Tate, C.M., et al., Evaluation of circular DNA substrates for whole genome amplification prior to forensic analysis. *Forensic Sci Int Genet*, 2012, **6**(2): 185–190.

Theodore Harcke, H., et al., Forensic imaging-guided recovery of nuclear DNA from the spinal cord. *J Forensic Sci*, 2009, **54**(5): 1123–1126.

Tilotta, F., et al., A comparative study of two methods of dental pulp extraction for genetic fingerprinting. *Forensic Sci Int*, 2010, **202**(1–3): e39–e43.

Toothman, M.H., et al., Characterization of human DNA in environmental samples. *Forensic Sci Int*, 2008, **178**(1): 7–15.

Tsuchimochi, T., et al., Chelating resin-based extraction of DNA from dental pulp and sex determination from incinerated teeth with Y-chromosomal alphoid repeat and short tandem repeats. *Am J Forensic Med Pathol*, 2002, **23**(3): 268–271.

van Oorschot, R.A., et al., Beware of the possibility of fingerprinting techniques transferring DNA. *J Forensic Sci*, 2005, **50**(6): 1417–1422.

Vandewoestyne, M., et al., Presence and potential of cell free DNA in different types of forensic samples. *Forensic Sci Int Genet*, 2013, **7**(2): 316–320.

von Wurmb-Schwark, N., et al., Fast and simple DNA extraction from saliva and sperm cells obtained from the skin or isolated from swabs. *Leg Med (Tokyo)*, 2006, **8**(3): 177–181.

Warshauer, D.H., et al., An evaluation of the transfer of saliva-derived DNA. *Int J Legal Med*, 2012, **126**(6): 851–861.

Webb, L.G., S.E. Egan, and G.R. Turbett, Recovery of DNA for forensic analysis from lip cosmetics. *J Forensic Sci*, 2001, **46**(6): 1474–1479.

Wiegand, P., T. Bajanowski, and B. Brinkmann, DNA typing of debris from fingernails. *Int J Legal Med*, 1993, **106**(2): 81–83.

Yasuda, T., et al., A simple method of DNA extraction and STR typing from urine samples using a commercially available DNA/RNA extraction kit. *J Forensic Sci*, 2003, **48**(1): 108–110.

SECTION II

Basic Techniques in Forensic Biology

5

Nucleic Acid Extraction

5.1 Basic Principles of DNA Extraction

Deoxyribonucleic acid (DNA) is a linear polynucleotide consisting of four types of monomeric nucleotides. Each nucleotide contains three components: a deoxyribose, a nitrogenous base, and a phosphate group (Figure 5.1). The four bases for DNA are adenine (A), cytosine (C), guanine (G), and thymine (T) (Figure 5.2). The deoxyribose is attached to the nitrogen of a base. The phosphate group is attached to the deoxyribose. In a *polynucleotide*, individual nucleotides are linked by phosphodiester bonds (Figure 5.3).

Interestingly, the first attempt to isolate DNA from humans, which involved the use of human leucocytes, was accomplished by the Swiss physician Friedrich Miescher in 1869. This study led to the discovery of the DNA molecule, which he referred to as "nuclein." Over the years, various methods for isolating DNA from blood samples were developed. However, many protocols still use the basic principles Miescher developed more than 100 years ago.

This chapter introduces basic techniques for DNA extraction used in forensic laboratories (Table 5.1). The commonly used methods isolate total cellular DNA, which is suitable for most forensic DNA analyses. However, DNA extraction procedures may vary according to the type of biological evidence, which can include cell types, substrates, the quantity of biological evidence collected, and the type of test that is being performed. Specific DNA extraction procedures for a sample of interest can be found in the literature. The extraction method of choice yields an optimal quantity, quality, and purity of DNA to satisfy forensic DNA testing needs. A sufficient quantity of DNA ensures the generation of a complete DNA profile. Poor quality of DNA, such as fragmentation due to DNA degradation, may result in a partial DNA profile or a failure to obtain a profile. Poor purity of DNA may cause interference during subsequent DNA testing. For example, DNA polymerase inhibitors interfere with DNA amplification (Chapter 7). Additional criteria for selecting proper DNA extraction methods include adaptability to automation, throughput potential, simplicity, the reduction of contamination risks, and cost-effectiveness. The most common DNA extraction protocols include basic components discussed below.

5.1.1 Cell and Tissue Disruption

In most DNA extraction protocols, enzymatic digestions, such as those with proteinase K, are used for cell and tissue disruption. The disruption process can also be carried out by boiling and by using alkali treatment and mechanical methods (Figures 5.4 and 5.5). Materials such as bone and teeth can be frozen in liquid nitrogen and then ground to a fine powder with a mortar or cryogenic grinder such as the SPEX CertiPrep® freezer mill (Figure 5.6). In such specimens, cells containing DNA



Figure 5.1 Structure of a nucleotide. Each nucleotide in a DNA polymer is made up of three components: a deoxyribose, a nitrogenous base (adenine is shown as an example), and a phosphate group. The 1′ carbon of the deoxyribose is attached to the nitrogen of a nitrogenous base. A phosphate group is attached to the 5′ carbon of the deoxyribose.



Figure 5.2 Chemical structures of nitrogenous bases: (a) adenine, (b) guanine, (c) cytosine, and (d) thymine.



Figure 5.3 DNA polynucleotide chain. Individual nucleotides are linked by phosphodiester bonds between their 5′ and 3′ carbons.

Table 5.1 Three Basic DNA Extraction Methods

Method	Forensic Application	Purity	DNA Strand	DNA Size	Throughput	Note
Solvent-based	RFLP- and PCR-based assay	High	Double stranded	Large	Time-consuming; difficult to adapt for automation	Uses toxic solvent; multiple transfer steps between tubes
Boiling	PCR-based assay	Low	Single stranded	Small	~30 min per sample	No transfer required
Silica-based	RFLP- and PCR-based assay	High	Double stranded	Large	~1 h per sample; amenable to automation	Minimum transfer required



Figure 5.4 An automated mechanical disruption device for efficient disruption of tissues. It can be used for high-throughput applications involving sample preparation for the isolation of nucleic acids. (© Richard C. Li.)



Figure 5.5 Tissue disruption using a pressure-generating instrument also known as a barocycler. During the process, a barocycler is utilized to apply alternating cycles of high and low pressures onto specimens placed in single-use processing containers. The technique is known as pressure-cycling technology (PCT). (© Richard C. Li.)



Figure 5.6 Tissue disruption using cryogenic grinding. A cryogenic mill (left), also known as freezer mill, can be used for the pulverization of hard tissue such as bone samples into fine powder prior to DNA extraction. During a grinding cycle, an impactor (right) moves back and forth, under a magnetic field, inside a grinding vial, grinding the sample to a fine powder. The grinding process is carried out at low temperatures (approximately −196°C), using liquid nitrogen to protect temperature-sensitive analytes such as DNA. (© Richard C. Li.)

are embedded in a calcified matrix that is responsible for the rigid structure of bone and teeth. In order to achieve a high yield of DNA extraction, it is necessary to remove the calcified matrix. A decalcification process removes calcium ions from the matrix, thus making the specimen suitable for DNA extraction. The most commonly used decalcifying agents for DNA extraction purposes are chelating agents such as ethylenediaminetetraacetic acid (EDTA), which sequesters the calcium ions. Decalcification is a lengthy procedure. Bone or teeth powder is usually treated with the decalcifying agent overnight or for a longer period of time, depending on the size and source of the sample.

5.1.2 Lysis of Cellular and Organelle Membranes

During or after tissue disruption, membranes—including those of cells, nuclei, and mitochondria—are lysed in order to release DNAs, including nuclear and mitochondrial DNA. The lysis can be carried out using salts and chaotropic agents (Section 5.2.3) such as guanidinium salts and detergents such as sarkosyl and sodium dodecyl sulfate (SDS). These substances can destroy membranes, denature proteins, and dissociate proteins such as histones from DNA. The lysis procedure is usually carried out in a buffer, such as Tris, in order to maintain a pH where endogenous *deoxyribonucleases* (DNases) remain inactive. DNases are a type of nuclease that catalyzes the cleavage of phosphodiester bonds of DNA. Endogenous DNases are located in cytoplasmic lysosomes and play a role in degrading the DNA of invading viruses. When cells are lysed, the DNases that are also released can degrade the extracted DNA. Chelating agents such as EDTA or Chelex® (Section 5.2.2) can therefore be used to chelate the divalent cations that are the cofactors of DNases, in order to inhibit DNase activities. Furthermore, reducing agents such as mercaptoethanol or dithiothreitol (DTT) can be used to inhibit the oxidization processes that can damage DNA.

5.1.3 Removal of Proteins and Cytoplasmic Constituents

After lysis, cytoplasmic constituents, such as proteins and liquids that interfere with DNA extraction, are removed. Proteins and lipids are usually removed by one or more rounds of extraction with organic solvents such as phenol–chloroform mixtures (Section 5.2.1). Another strategy to remove cytoplasmic constituents is to utilize the reversible binding of DNA to a solid material such as silica, which selectively binds DNA in chaotropic salt solutions. The proteins and cytoplasmic constituents can then be removed through washing steps.

5.1.4 Storage of DNA Solutions

Purified high-molecular-weight DNA is usually stored in TE buffer (10 mM Tris-HCl, 1 mM EDTA, pH 8.0). EDTA is usually included in storage solutions to chelate divalent cations and thereby inhibit DNases. Such a DNA solution may be stored at 4°C or −20°C. For long-term storage, −80°C is recommended. Frequent freezing or thawing cycles should be avoided because temperature fluctuations may cause breaks of single- and double-stranded DNA. Additionally, DNA containing impurities such as extracts generated via the Chelex method are much less stable. The presence of heavy metals, such as cadmium and cobalt, can cause breakage of phosphodiester bonds in the molecules. Additionally, unsuccessful removal of exogenous or intracellular free radicals, such as a hydroxyl radical (HO·), which have unpaired valence electrons, can cause DNA damage such as strand breaks. Furthermore, contamination by DNases may lead to subsequent degradation of DNA.

5.1.5 Contamination

Contamination is usually caused by the introduction of exogenous DNA to an evidence sample. It can occur between samples, between an individual and a sample, between other organisms and a sample, or between amplified DNA and a sample. Certain procedures can be utilized to prevent the occurrence of contamination. For example, evidence and reference samples should be processed separately in different rooms to avoid sample-to-sample contamination. In situations where space is limited, the evidence sample should be processed before the reference sample. Additionally, evidence samples should be processed and extracted for isolating DNA in separate areas (or at different times) from DNA amplification areas.

Solutions and test tubes used for extraction should be DNA-free, and aerosol-resistant pipet tips should be used during the extraction process. Additionally, the levels of contamination should be monitored by using *extraction reagent blanks* (having reagents but no samples), which monitor contamination from the extraction.

5.2 Methods of DNA Extraction

5.2.1 Extraction with Phenol–Chloroform

This method is also called organic extraction. Major steps include the following:

5.2.1.1 Cell Lysis and Protein Digestion

These steps can be achieved by digestion with proteolytic enzymes such as proteinase K before extraction with organic solvents.

5.2.1.2 Extraction with Organic Solvents

The removal of proteins is carried out by extracting aqueous solutions containing DNA with a mixture of phenol:chloroform:isoamyl alcohol (25:24:1). Phenol is used to extract the proteins from the aqueous solution. Although phenol has a slightly higher density than water, it is sometimes difficult to separate it from the aqueous phase. Therefore, chloroform is utilized as it has a higher density than phenol. As a result, the phenol–chloroform mixture forms the organic phase at the bottom of the tube and is easily separated from the aqueous phase. Isoamyl alcohol is often added to the phenol–chloroform mixture to reduce foaming. During partition, DNA is solubilized in the aqueous phase, while lipids are solubilized in the organic phase. Proteins are located at the interface between the two phases (Figure 5.7).

5.2.1.3 Concentrating DNA

Two common methods for concentrating DNA are ethanol precipitation and ultrafiltration. In the first method, the DNA is precipitated from the aqueous solution with ethanol and salts. Ethanol depletes the hydration shell of DNA, thus exposing its negatively charged phosphate groups. The


DNA
Protein
Aqueous phase
Organic solvent phase
Lipid

Figure 5.7 DNA extraction using organic solvent. The DNA is contained in the aqueous phase, while cellular materials such as lipids are contained in the organic-solvent phase. Proteins remain in the barrier between the two phases. (© Richard C. Li.)


Sample reservoir
DNA sample
DNA trapped by filter
Inverted cartridge
Filter
Filtrate
Concentrated DNA

Figure 5.8 Concentrating DNA solutions using filtration devices. DNA samples are loaded into the reservoir. The liquid is filtered by centrifugation and the DNA becomes trapped in the membrane. The cartridge is then inverted to recover the trapped DNA by centrifugation. (© Richard C. Li.)

precipitation can only occur if sufficient quantities of cations are present in the solution. The most commonly used cations, such as ammonium, lithium, and sodium, neutralize the charges on the phosphate residues of DNA, forming a precipitate. Ultrafiltration is an alternative to ethanol precipitation for concentrating DNA solutions. The Microcon® and Amicon® are centrifugal ultrafiltration devices that can concentrate DNA samples (Figure 5.8). A proper Microcon® unit can be selected with a nucleotide cutoff equal to or smaller than the molecular weight of the DNA fragment of interest. Usually, the cutoff size is 100 kDa for forensic DNA samples.

Phenol–chloroform extraction yields large, double-stranded DNA and can be used for either restriction fragment length polymorphism (RFLP)-based or polymerase chain reaction

(PCR)-based analysis. However, the organic extraction method is time-consuming, involves the use of hazardous reagents, and requires the transfer of samples among tubes.

5.2.2 Extraction by Boiling Lysis and Chelation

This technique, also called the Chelex® extraction method, was introduced in the early 1990s to forensic DNA laboratories. It usually includes the following steps:

5.2.2.1 Washing

This step removes contaminants and inhibitors that may interfere with DNA amplification. For example, heme compounds found in blood samples should be removed from blood samples because it inhibits DNA amplification.

5.2.2.2 Boiling

Cells are suspended in a solution and incubated at 56°C, where DNases are not active, for 20 min. This preboiling step softens cell membranes and separates clumps of cells from each other. The cells are then lysed by heating to boiling temperature in order to break open the membranes and to release the DNA. Additionally, the lysis of cells releases all of their cellular constituents, including DNases. The DNase degradation of the extracted DNA can be blocked by applying a chelating resin (Chelex® 100) during the extraction process. Chelex® 100 is an ion-exchange resin composed of styrene divinylbenzene copolymers. The paired iminodiacetate ion groups in Chelex® 100 act as chelators by binding to divalent metal ions such as magnesium. Magnesium is a cofactor of endogenous DNases. Thus, sequestering magnesium in the solution using Chelex® 100 protects DNA from degradation by DNases (Figure 5.9).

5.2.2.3 Centrifugation

Brief centrifugation is performed to pull the Chelex® 100 resin and cellular debris to the bottom of the tube. The supernatant is used for DNA analysis. Carrying the Chelex® 100 resin over into the DNA amplification solutions should be avoided because the resin chelates magnesium, which is a necessary cofactor for DNA polymerases used for amplification.



Figure 5.9 Utilizing Chelex® for preparing DNA samples. (a) Cations such as Mg^{2+} are required for the activity of endogenous DNase, which degrades DNA. (b) Chelex® prevents DNA degradation from endogenous DNase by sequestering the Mg^{2+}. (© Richard C. Li.)

This method is simple and rapid and uses only a single tube for extraction, thus reducing the risks of contamination and sample mix-ups. However, the heating step of this method disrupts and denatures proteins and also affects the chromosomal DNA. The resulting DNA extracted from the solution is fragmented single-stranded DNA. Thus, the DNA extracted is not suitable for RFLP analysis because RFLP requires double-stranded DNA samples. The DNA obtained by lysis and chelation can only be used for PCR-based DNA analysis.

5.2.3 Silica-Based Extraction

The method of adsorbing DNA molecules to solid silica surfaces is used for extraction (Figures 5.10 and 5.11). The method is based on the phenomenon that DNA is reversibly adsorbed to silica—silicon dioxide (SiO_2)—in the presence of high concentrations of chaotropic salts. Chaotropic salts can disrupt hydrogen bonding, affecting the three-dimensional structures of macromolecules. These salts are used to denature proteins. Additionally, chaotropic salts can facilitate the adsorption of DNA to silica.

In aqueous solutions, the hydration shells of nucleic acids shield the negative charges of phosphates at the phosphodiester backbone of nucleic acids. As a result, nucleic acids are usually hydrophilic in aqueous solutions. In the presence of chaotropic salts, nucleic acids become hydrophobic. The dehydrating effect caused by chaotropic salts allows the phosphate residues to become available for adsorption to the silica surface. Common chaotropic salts utilized for DNA extraction include guanidinium salts such as guanidinium thiocyanate (GuSCN) and guanidinium hydrochloride (GuHCl). GuSCN is a more potent chaotropic salt and also facilitates cell lysis and DNA adsorption. This technique usually includes the following steps:

5.2.3.1 Cell Lysis and Protein Digestion

This is carried out by proteinase K digestion. The cell membranes are broken open, and DNA is released.

5.2.3.2 DNA Adsorption onto Silica

This step utilizes silica as the stationary phase in a membrane configuration to which the DNA in the cell lysate binds. Adsorption of the DNA to the silica occurs in the presence of high concentrations of chaotropic agents (some protocols adjust pH conditions to enhance adsorption). Under these conditions, cellular materials and other contaminants that can inhibit DNA amplification reactions are not retained on the silica membrane. The adsorbed DNA is largely double stranded.



Figure 5.10 A silica-membrane spin column. (© Richard C. Li.)



Figure 5.11 Silica-based DNA extractions. (a) Cells are lysed in the presence of proteinase. The DNA then binds to the silica matrix. A washing step removes unbound cellular materials and salts from the matrix. The purified DNA is then eluted for use in downstream applications. (b) Using silica-coated paramagnetic particles for DNA extraction. The particle is added into a lysate, and then DNA binds to the silica surface of the particle. The particle is then captured by a magnetic field. Afterwards, the supernatant is removed, and cellular materials are washed away. DNA elution follows. See Section 5.2.3. (© Richard C. Li.)

5.2.3.3 Washing

This step removes chaotropic agents and other contaminants. An ethanol-based wash solution is used. This wash solution does not remove DNA from the silica. The chaotropic agents and contaminants that are present in the solution can be removed using the ethanol-based wash solution.

5.2.3.4 Elution of DNA

The adsorbed DNA can be eluted by rehydration with aqueous low-salt solutions. The eluted DNA is double stranded and can be used for a wide variety of applications.

Silica-based extraction methods yield high-quality DNA. Silica membrane devices can also be adapted for automation; for example, this can be done by using 96-well silica membrane plates and a variety of robotic platforms. Another type of device utilizes silica-coated paramagnetic particles that adsorb DNA in the solution (Figure 5.11b). A magnet is used for particle capture instead of centrifugation or vacuum filtration. The magnetic particles can be resuspended during the wash steps, and the solution containing contaminants and cellular materials is then discarded. DNA is eluted after washing. This device can also be adapted to automated, high-throughput methods.

Over the years, high-throughput silica-based procedures have been developed to process large numbers of samples in parallel. Some of these methods are adapted for automated DNA extraction platforms (Figures 5.12 and 5.13).



Figure 5.12 Automated bench-top DNA purification systems that enable the isolation of genomic DNA from a wide variety of forensic samples. A low-throughput sample-preparation system that can process up to 12 samples (left) and a low-to-medium throughput sample-preparation system (right). (© Richard C. Li.)



Figure 5.13 Integrated platforms enabling automated DNA sample preparation and liquid handling for subsequent assay setup. These systems utilize silica-coated bead chemistries and can achieve moderate to high throughput of processing (1–96 samples) with bar coding for sample tracking. A Hamilton (top) and a Qiagen system (bottom). (© Richard C. Li.)

5.2.4 Differential Extraction

This method is very useful for the extraction of DNA from biological evidence derived from sexual assault cases, such as vaginal swabs and bodily fluid stains. These types of evidence often contain mixtures of spermatozoa from a male contributor and nonsperm cells such as epithelial cells from a female victim. Mixtures of individual DNA profiles can complicate data interpretation.

This method selectively lyses the nonsperm and spermatozoa in separate steps based on the differences in cell-membrane properties of spermatozoa and other types of cells. Thus, the DNA from spermatozoa and nonsperm cell fractions can be sequentially isolated.

First, the differential extraction procedure involves preferentially lysing the nonsperm cells with proteolytic degradation using proteinase. Sperm plasma membrane contains proteins cross-linked by disulfide bonds. The membrane exhibits a much higher mechanical stability than nonsperm cells and is thus resistant to proteolytic degradation. The nonsperm DNA is released into the supernatant and the liquid containing it (the nonsperm fraction) is extracted, yielding a fraction that predominantly contains DNA from nonsperm cells.

To lyse the sperm cells, it is necessary to cleave the disulfide bonds in addition to proteolytic digestion. The application of DTT, a reducing agent, is an approach that can be used for cleavage. In the presence of DTT and proteinase K, the sperm plasma membrane is then lysed (Figure 5.14). Subsequently, DNA from the sperm cells can be extracted (Figure 5.15).



Figure 5.14 DTT reaction. The breaking of disulfide bonds in cystine residues is carried out by adding a reducing agent such as DTT.



Figure 5.15 Differential extraction process used to separate sperm cells from nonsperm cells. Nonsperm cells are lysed in the presence of SDS and proteinase K (PK); sperm cells are resistant to such conditions. The nonsperm cell DNA is extracted. The sperm cells are then lysed separately in the presence of SDS and proteinase K plus DTT to extract the sperm DNA. (© Richard C. Li.)

This process isolates sperm and nonsperm cell DNA separately for obtaining DNA profiles from male and female contributors, respectively. However, the non-sperm-cell DNA and sperm-cell DNA may not be completely separated from one another; this can happen, for example, if the sperm cells have already lysed due to poor sample conditions. Some sperm DNA may be present in the non-sperm-cell fraction. Additionally, if a mixture has an abundance of nonsperm cells and fewer sperm cells, non-sperm-cell DNA may be detected in the sperm fraction. Thus, new methods that can overcome these problems are highly desired.

5.3 Essential Features of RNA

Like DNA, *ribonucleic acid* (RNA) is a linear molecule containing four types of nucleotides linked by phosphodiester bonds (Figures 5.16 and 5.17). However, certain properties of RNA differ from those of DNA. Unlike DNA containing deoxyribose (see Figure 5.18), the sugar residue



Figure 5.16 The structure of ribonucleotide. Each ribonucleotide in a RNA polymer consists of three components: a ribose, a nitrogenous base (uracil is shown as an example), and a phosphate group. The 1′ carbon of the ribose is attached to the nitrogen of the nitrogenous base. A phosphate group is attached to the 5′ carbon of the ribose.



Figure 5.17 Chemical structure of RNA (polyribonucleotide) chain.



Figure 5.18 Comparison of (a) ribose and (b) deoxyribose. The hydroxyl group attached to the 2′ carbon of ribose is replaced by a hydrogen group in deoxyribose.

of RNA is a ribose, which has a hydroxyl (OH) group at the 2′ carbon position. Therefore, RNA has a lower pKa, which means that it is more acidic than DNA. RNA contains uracil (U) in the place of thymine in DNA (Figure 5.19). RNA is typically found in cells as a single-stranded molecule, while DNA is double stranded. Polyribonucleotides can form complementary helices with DNA strands by base pairing (with the exception of uracil pairs with adenine) (see Figure 5.20).

Total RNA contains all the RNA of the cells, including RNAs involved in protein synthesis and posttranscriptional modification, as well as regulatory RNAs. The RNA that carries codes from a DNA template is called messenger RNA (mRNA) and usually contains a cap and polyadenine tail at the 5′ and 3′ ends of the molecule, respectively (Figure 5.21).

The stability of RNA is an issue for mRNA-based forensic analysis. Single-stranded RNA is chemically less stable than DNA. The 2′ OH group of RNA can react with its phosphodiester backbone, potentially causing the nonenzymatic hydrolysis of an RNA molecule. Several factors, such as moisture, UV light, high temperature, and extreme pH, can facilitate the nonenzymatic



Figure 5.19 Comparison of (a) uracil and (b) thymine. Thymine has a methyl group attached at the 5-carbon position.



Figure 5.20 Base pairing of uracil (left) and adenine (right).



Figure 5.21 Structure of mRNA. Eukaryotic mRNA is modified at the 5′ end (cap) and 3′ end (polyadenine tail) needed for protein synthesis. Start and stop codons are required for the initiation and termination of protein synthesis. (© Richard C. Li.)

hydrolysis of RNA phosphodiesters, which leads to the degradation of RNA. Moreover, endogenous *ribonucleases* (RNases), present within cells, represent the major factor causing RNA degradation. Environmental microorganisms are also a common source of RNase contamination. RNases are very stable and usually do not require cofactors to carry out enzymatic reactions. Small amounts of RNases are sufficient to degrade RNA. RNA can be protected by adding RNase inhibitors such as diethylpyrocarbonate. Additionally, using RNase-free laboratory supplies and reagents and wearing disposable gloves while handling samples and reagents can reduce the risks of RNase contamination.

5.4 Methods of RNA Extraction

5.4.1 RNA–DNA Coextraction

For most forensic applications, total RNA is usually isolated. The procedure for isolating total RNA is simpler than that for mRNA. The total RNA isolated usually contains a sufficient amount of mRNA for subsequent reverse transcriptase PCR (RT-PCR; see Chapter 7). However, if the quantity of a target mRNA is very low, the procedures specifically for isolating mRNA should be used. There are a variety of protocols for isolating total RNA. However, RNA–DNA coextraction methods allow for the simultaneous extraction of high-quality DNA and RNA for forensic DNA analysis and bodily-fluid identification (Chapter 11), respectively, without the consumption of additional samples when extracted separately.

Biological samples are first lysed in lysis buffer. The lysis buffer usually contains chaotropic salts that can facilitate the lysis of cells and denature proteins, thus inactivating endogenous RNases to protect RNA. The lysate is then passed through a silica membrane column. A high-salt environment in the lysate allows selective binding of silica to genomic DNA over RNA. The column is washed, and purified DNA is then eluted.

The extraction of RNA is achieved by utilizing a high concentration of chaotropic salts that are already present in the lysate, along with ethanol, in order to decrease the hydrophilic property of RNA and increase its affinity for silica. After ethanol is added to the flow-through that passed the first column, the sample is then applied to a second silica column, where total RNA molecules, longer than 200 nucleotides, bind to the silica membrane. RNA including mRNA is then eluted (Figure 5.22). This method does not isolate small RNAs such as miRNA, rRNA, and tRNA, which comprise 15%–20% of total RNA.

5.4.2 miRNA Extraction

miRNAs (Chapter 4) are low-molecular-weight RNAs ranging between 15 and 30 nucleotides in length. Conventional methods routinely used for extracting total RNA do not effectively recover small RNAs; thus, they are not suitable for isolating miRNA. One approach to extracting small RNA molecules including miRNA involves two steps: organic-solvent extraction to isolate total RNA and solid-phase extraction to enrich small RNA.

To begin the process, tissues are disrupted and cells are lysed. The lysis reagents also inactivate RNases to protect RNA. The lysate is then extracted with an organic solvent, such as phenol and chloroform, with a high concentration of chaotropic salts such as GuSCN. The partitioning of DNA and RNA between the organic phase and the aqueous phase is determined by the pH during the organic extraction. At an acidic pH, DNA partitions to the organic phase. The pKa of RNA is usually lower than DNA; thus, RNA remains hydrophilic and is retained in the aqueous phase under this condition. This step removes most of the DNA, proteins, and other cellular components from the lysate into the organic phase.

The second step, silica-based extraction, further purifies and enriches small RNAs. It is achieved by utilizing the high concentration of chaotropic salt that is already present in the lysate, along with ethanol. The size-fractioning of RNAs is achieved using different ethanol


Lysate
Silica
DNA binding
EtOH
Elution buffer
Eluting
Transfer
DNA
RNA binding
Eluting
RNA

Figure 5.22 RNA and DNA coextraction using a silica-based method. See Section 5.4.1. (© Richard C. Li.)

concentrations. At a low ethanol concentration, the solvent-extracted lysate is passed through a silica membrane filter. Large RNAs are retained on the silica membrane, while small RNAs are not and are collected in the filtrate. The filtrate is passed through a second silica membrane filter. At a high ethanol concentration, the small RNAs are retained on the silica membrane. The small RNAs are then eluted in a low ionic strength solution (Figure 5.23). RNA less than 200 nucleotides, including miRNA, can be obtained.

After RNA is extracted, the small amounts of RNA can be quantified using a quantitative RT-PCR (Chapter 7) or fluorescent intercalating dye assay (Chapter 6). Purified RNA can be


Lysate
Solvent, patitioning
RNA
DNA
Transfer, low EtOH
Silica
RNA binding (> 200 nt)
Transfer, high EtOH
RNA binding (< 200 nt)
Eluting
Elution buffer
RNA (< 200 nt)

Figure 5.23 Schematic illustration of an miRNA extraction method. See Section 5.4.2. (© Richard C. Li.)

stored at −80°C in RNase-free water or Tris-EDTA buffer (pH 7). Single-use aliquots are preferred when possible to avoid multiple freeze–thaw cycles.

The integrity of extracted RNA is a great concern for RNA-based forensic analysis. RNA quality is traditionally assessed using the 28S:18S rRNA ratio. There are some conditions where this method has been shown to be inconsistent; that is, in which the 28S:18S rRNA ratio does not reflect the true level of RNA degradation. Recently, the *RNA integrity number* (RIN) has provided an effective method for determining RNA quality. RIN is a software algorithm that takes the electrophoretic RNA measurements into account in order to assign integrity values to RNA samples. RIN ranges from 1 to 10, with 10 being the most intact. Thus, the RIN method facilitates the assessment of the integrity of RNA samples. As reflected by RIN, RNA degradation has a negative influence on the reproducibility of the results of RNA-based forensic analysis.

Bibliography

Alvarez, M., J. Juusola, and J. Ballantyne, An mRNA and DNA co-isolation method for forensic casework samples. *Anal Biochem*, 2004, **335**(2): 289–298.

Amory, S., et al., Automatable full demineralization DNA extraction procedure from degraded skeletal remains. *Forensic Sci Int Genet*, 2012, **6**(3): 398–406.

Ananian, V., et al., Tumoural specimens for forensic purposes: Comparison of genetic alterations in frozen and formalin-fixed paraffin-embedded tissues. *Int J Legal Med*, 2011, **125**(3): 327–332.

Anzai-Kanto, E., et al., DNA extraction from human saliva deposited on skin and its use in forensic identification procedures. *Pesqui Odontol Bras*, 2005, **19**(3): 216–222.

Archer, E., et al., Validation of a dual cycle ethylene oxide treatment technique to remove DNA from consumables used in forensic laboratories. *Forensic Sci Int Genet*, 2010, **4**(4): 239–243.

Baker, L.E., W.F. McCormick, and K.J. Matteson, A silica-based mitochondrial DNA extraction method applied to forensic hair shafts and teeth. *J Forensic Sci*, 2001, **46**(1): 126–130.

Benoit, J.N., et al., An alternative procedure for extraction of DNA from ancient and weathered bone fragments. *Med Sci Law*, 2013, **53**(2): 100–106.

Bowden, A., R. Fleming, and S. Harbison, A method for DNA and RNA co-extraction for use on forensic samples using the Promega DNA IQ system. *Forensic Sci Int Genet*, 2011, **5**(1): 64–68.

Brevnov, M.G., et al., Developmental validation of the PrepFiler Forensic DNA Extraction Kit for extraction of genomic DNA from biological samples. *J Forensic Sci*, 2009, **54**(3): 599–607.

Castella, V., et al., Forensic evaluation of the QIAshredder/QIAamp DNA extraction procedure. *Forensic Sci Int*, 2006, **156**(1): 70–73.

Cattaneo, C., et al., A simple method for extracting DNA from old skeletal material. *Forensic Sci Int*, 1995, **74**(3): 167–174.

Crouse, C.A., J.D. Ban, and J.K. D'Alessio, Extraction of DNA from forensic-type sexual assault specimens using simple, rapid sonication procedures. *Biotechniques*, 1993, **15**(4): 641–644, 646, 648.

Davis, C.P., et al., Extraction platform evaluations: A comparison of AutoMate Express, EZ1(R) Advanced XL, and Maxwell(R) 16 Bench-top DNA extraction systems. *Leg Med (Tokyo)*, 2012, **14**(1): 36–39.

Di Nunno, N., et al., DNA extraction: An anthropologic aspect of bone remains from sixth- to seventh-century ad bone remains. *Am J Forensic Med Pathol*, 2007, **28**(4): 333–341.

Diegoli, T.M., et al., An optimized protocol for forensic application of the PreCR Repair Mix to multiplex STR amplification of UV-damaged DNA. *Forensic Sci Int Genet*, 2012, **6**(4): 498–503.

Dieltjes, P., et al., A sensitive method to extract DNA from biological traces present on ammunition for the purpose of genetic profiling. *Int J Legal Med*, 2011, **125**(4): 597–602.

Duarte, G.R., et al., Characterization of dynamic solid phase DNA extraction from blood with magnetically controlled silica beads. *Analyst*, 2010, **135**(3): 531–537.

Duval, K., et al., Optimized manual and automated recovery of amplifiable DNA from tissues preserved in buffered formalin and alcohol-based fixative. *Forensic Sci Int Genet*, 2010, **4**(2): 80–88.

Edson, S.M. and A.F. Christensen, Field contamination of skeletonized human remains with exogenous DNA. *J Forensic Sci*, 2013, **58**(1): 206–209.

Elliott, K., et al., Use of laser microdissection greatly improves the recovery of DNA from sperm on microscope slides. *Forensic Sci Int*, 2003, **137**(1): 28–36.

Eminovic, I., et al., A simple method of DNA extraction in solving difficult criminal cases. *Med Arh*, 2005, **59**(1): 57–58.

Farrugia, A., C. Keyser, and B. Ludes, Efficiency evaluation of a DNA extraction and purification protocol on archival formalin-fixed and paraffin-embedded tissue. *Forensic Sci Int*, 2010, **194**(1–3): e25–e28.

Fattorini, P., et al., CE analysis and molecular characterisation of depurinated DNA samples. *Electrophoresis*, 2011, **32**(21): 3042–3052.

Fattorini, P., et al., Assessment of DNA damage by micellar electrokinetic chromatography. *Methods Mol Biol*, 2013, **984**: 341–351.

Fracasso, T., et al., Ultrasound-accelerated formalin fixation improves the preservation of nucleic acids extraction in histological sections. *Int J Legal Med*, 2009, **123**(6): 521–525.

Fregeau, C.J. and A. De Moors, Competition for DNA binding sites using Promega DNA IQ paramagnetic beads. *Forensic Sci Int Genet*, 2012, **6**(5): 511–522.

Fregeau, C.J., C.M. Lett, and R.M. Fourney, Validation of a DNA IQ-based extraction method for TECAN robotic liquid handling workstations for processing casework. *Forensic Sci Int Genet*, 2010, **4**(5): 292–304.

Fregeau, C.J., et al., Automated processing of forensic casework samples using robotic workstations equipped with nondisposable tips: Contamination prevention. *J Forensic Sci*, 2008, **53**(3): 632–651.

Fridez, F. and R. Coquoz, PCR DNA typing of stamps: Evaluation of the DNA extraction. *Forensic Sci Int*, 1996, **78**(2): 103–110.

Frippiat, C., et al., Evaluation of novel forensic DNA storage methodologies. *Forensic Sci Int Genet*, 2011, **5**(5): 386–392.

Fujita, Y. and S. Kubo, Application of FTA technology to extraction of sperm DNA from mixed body fluids containing semen. *Leg Med (Tokyo)*, 2006, **8**(1): 43–47.

Garvin, A.M. and A. Fritsch, Purifying and concentrating genomic DNA from mock forensic samples using Millipore Amicon filters. *J Forensic Sci*, 2013, **58**(Suppl 1): S173–S175.

Garvin, A.M., et al., DNA preparation from sexual assault cases by selective degradation of contaminating DNA from the victim. *J Forensic Sci*, 2009, **54**(6): 1297–1303.

Ginestra, E., et al., DNA extraction from blood determination membrane card test. *Forensic Sci Int*, 2004, **146**(Suppl): S145–S146.

Greenspoon, S.A., et al., QIAamp spin columns as a method of DNA isolation for forensic casework. *J Forensic Sci*, 1998, **43**(5): 1024–1030.

Greenspoon, S.A., et al., Application of the BioMek 2000 Laboratory Automation Workstation and the DNA IQ System to the extraction of forensic casework samples. *J Forensic Sci*, 2004, **49**(1): 29–39.

Grubb, J.C., et al., Implementation and validation of the Teleshake unit for DNA IQ robotic extraction and development of a large volume DNA IQ method. *J Forensic Sci*, 2010, **55**(3): 706–714.

Hagan, K.A., et al., Chitosan-coated silica as a solid phase for RNA purification in a microfluidic device. *Anal Chem*, 2009, **81**(13): 5249–5256.

Hanselle, T., et al., Isolation of genomic DNA from buccal swabs for forensic analysis, using fully automated silica-membrane purification technology. *Leg Med (Tokyo)*, 2003, **5**(Suppl 1): S145–S149.

Hedman, J., et al., A fast analysis system for forensic DNA reference samples. *Forensic Sci Int Genet*, 2008, **2**(3): 184–189.

Heinrich, M., et al., Successful RNA extraction from various human postmortem tissues. *Int J Legal Med*, 2007, **121**(2): 136–142.

Hennekens, C.M., et al., The effects of differential extraction conditions on the premature lysis of spermatozoa. *J Forensic Sci*, 2013, **58**(3): 744–752.

Ho, T.T. and R. Roy, Generating DNA profiles from immunochromatographic cards using LCN methodology. *Forensic Sci Int Genet*, 2011, **5**(3): 210–215.

Hochmeister, M.N., et al., PCR-based typing of DNA extracted from cigarette butts. *Int J Legal Med*, 1991, **104**(4): 229–233.

Hoff-Olsen, P., et al., Extraction of DNA from decomposed human tissue. An evaluation of five extraction methods for short tandem repeat typing. *Forensic Sci Int*, 1999, **105**(3): 171–183.

Howlett, S.E., et al., Evaluation of DNAstable for DNA storage at ambient temperature. *Forensic Sci Int Genet*, 2014, **8**(1): 170–178.

Hudlow, W.R. and M.R. Buoncristiani, Development of a rapid, 96-well alkaline based differential DNA extraction method for sexual assault evidence. *Forensic Sci Int Genet*, 2012, **6**(1): 1–16.

Hudlow, W.R., et al., The NucleoSpin(R) DNA Clean-up XS kit for the concentration and purification of genomic DNA extracts: An alternative to microdialysis filtration. *Forensic Sci Int Genet*, 2011, **5**(3): 226–230.

Hulme, P., J. Lewis, and G. Davidson, Sperm elution: An improved two phase recovery method for sexual assault samples. *Sci Justice*, 2013, **53**(1): 28–33.

Iwasa, M., et al., Y-chromosomal short tandem repeats haplotyping from vaginal swabs using a chelating resin-based DNA extraction method and a dual-round polymerase chain reaction. *Am J Forensic Med Pathol*, 2003, **24**(3): 303–305.

Jakubowska, J., A. Maciejewska, and R. Pawlowski, Comparison of three methods of DNA extraction from human bones with different degrees of degradation. *Int J Legal Med*, 2012, **126**(1): 173–178.

Karija Vlahovic, M. and M. Kubat, DNA extraction method from bones using Maxwell(R) 16. *Leg Med (Tokyo)*, 2012, **14**(5): 272–275.

Kim, K., et al., Technical note: Improved ancient DNA purification for PCR using ion-exchange columns. *Am J Phys Anthropol*, 2008, **136**(1): 114–121.

Kochl, S., H. Niederstatter, and W. Parson, DNA extraction and quantitation of forensic samples using the phenol–chloroform method and real-time PCR. *Methods Mol Biol*, 2005, **297**: 13–30.

Kopka, J., et al., New optimized DNA extraction protocol for fingerprints deposited on a special self-adhesive security seal and other latent samples used for human identification. *J Forensic Sci*, 2011, **56**(5): 1235–1240.

Lee, E.J., et al., The effects of different maceration techniques on nuclear DNA amplification using human bone. *J Forensic Sci*, 2010, **55**(4): 1032–1038.

Lee, H.Y., et al., Simple and highly effective DNA extraction methods from old skeletal remains using silica columns. *Forensic Sci Int Genet*, 2010, **4**(5): 275–280.

Lee, S.B., et al., Assessing a novel room temperature DNA storage medium for forensic biological samples. *Forensic Sci Int Genet*, 2012, **6**(1): 31–40.

Li, R. and L. Liriano, A bone sample cleaning method using trypsin for the isolation of DNA. *Leg Med (Tokyo)*, 2011, **13**(6): 304–308.

Li, R. and S. Klempner, The effect of an enzymatic bone processing method on short tandem repeat profiling of challenged bone specimens. *Leg Med (Tokyo)*, 2013, **15**(4): 171–176.

Li, R., et al., Developing a simple method to process bone samples prior to DNA isolation. *Leg Med (Tokyo)*, 2009, **11**(2): 76–79.

Li, C.X., et al., New cell separation technique for the isolation and analysis of cells from biological mixtures in forensic caseworks. *Croat Med J*, 2011, **52**(3): 293–298.

Liu, J.Y., et al., AutoMate Express forensic DNA extraction system for the extraction of genomic DNA from biological samples. *J Forensic Sci*, 2012, **57**(4): 1022–1030.

Loreille, O.M., et al., High efficiency DNA extraction from bone by total demineralization. *Forensic Sci Int Genet*, 2007, **1**(2): 191–195.

Lounsbury, J.A., et al., An enzyme-based DNA preparation method for application to forensic biological samples and degraded stains. *Forensic Sci Int Genet*, 2012, **6**(5): 607–615.

Ma, H.W., J. Cheng, and B. Caddy, Extraction of high quality genomic DNA from microsamples of human blood. *J Forensic Sci Soc*, 1994, **34**(4): 231–235.

McMichael, G.L., et al., Comparison of DNA extraction methods from small samples of newborn screening cards suitable for retrospective perinatal viral research. *J Biomol Tech*, 2011, **22**(1): 5–9.

Meredith, M., et al., Development of a one-tube extraction and amplification method for DNA analysis of sperm and epithelial cells recovered from forensic samples by laser microdissection. *Forensic Sci Int Genet*, 2012, **6**(1): 91–96.

Montpetit, S.A., I.T. Fitch, and P.T. O'Donnell, A simple automated instrument for DNA extraction in forensic casework. *J Forensic Sci*, 2005, **50**(3): 555–563.

Nagy, M., et al., Optimization and validation of a fully automated silica-coated magnetic beads purification technology in forensics. *Forensic Sci Int*, 2005, **152**(1): 13–22.

Norris, J.V., et al., Acoustic differential extraction for forensic analysis of sexual assault evidence. *Anal Chem*, 2009, **81**(15): 6089–6095.

Parker, C., E. Hanson, and J. Ballantyne, Optimization of dried stain co-extraction methods for efficient recovery of high quality DNA and RNA for forensic analysis. *Forensic Sci Int: Genet Suppl Series*, 2011, **3**(1): e309–e310.

Phillips, K., N. McCallum, and L. Welch, A comparison of methods for forensic DNA extraction: Chelex-100(R) and the QIAGEN DNA Investigator Kit (manual and automated). *Forensic Sci Int Genet*, 2012, **6**(2): 282–285.

Piglionica, M., et al., Extraction of DNA from bones in cases where expectations for success are low. *Am J Forensic Med Pathol*, 2012, **33**(4): 322–327.

Raimann, P.E., et al., Procedures to recover DNA from pre-molar and molar teeth of decomposed cadavers with different post-mortem intervals. *Arch Oral Biol*, 2012, **57**(11): 1459–1466.

Reedy, C.R., et al., Volume reduction solid phase extraction of DNA from dilute, large-volume biological samples. *Forensic Sci Int Genet*, 2010, **4**(3): 206–212.

Rerkamnuaychoke, B., et al., Comparison of DNA extraction from blood stain and decomposed muscle in STR polymorphism analysis. *J Med Assoc Thai*, 2000, **83**(Suppl 1): S82–S88.

Reshef, A., et al., STR typing of formalin-fixed paraffin embedded (FFPE) aborted foetal tissue in criminal paternity cases. *Sci Justice*, 2011, **51**(1): 19–23.

Rothe, J., L. Roewer, and M. Nagy, Individual specific extraction of DNA from male mixtures—First evaluation studies. *Forensic Sci Int Genet*, 2011, **5**(2): 117–121.

Rucinski, C., et al., Comparison of two methods for isolating DNA from human skeletal remains for STR analysis. *J Forensic Sci*, 2012, **57**(3): 706–712.

Scherczinger, C.A., et al., DNA extraction from liquid blood using QIAamp. *J Forensic Sci*, 1997, **42**(5): 893–896.

Seo, S.B., et al., Technical note: Efficiency of total demineralization and ion-exchange column for DNA extraction from bone. *Am J Phys Anthropol*, 2010, **141**(1): 158–162.

Shalhoub, R., et al., The recovery of latent fingermarks and DNA using a silicone-based casting material. *Forensic Sci Int*, 2008, **178**(2–3): 199–203.

Shan, Z., et al., PCR-ready human DNA extraction from urine samples using magnetic nanoparticles. *J Chromatogr B Analyt Technol Biomed Life Sci*, 2012, **881–882**: 63–68.

Shaw, K., et al., Comparison of the effects of sterilisation techniques on subsequent DNA profiling. *Int J Legal Med*, 2008, **122**(1): 29–33.

Sinclair, K. and V.M. McKechnie, DNA extraction from stamps and envelope flaps using QIAamp and QIAshredder. *J Forensic Sci*, 2000, **45**(1): 229–230.

Stangegaard, M., et al., Automated extraction of DNA from blood and PCR setup using a Tecan Freedom EVO liquid handler for forensic genetic STR typing of reference samples. *J Lab Autom*, 2011, **16**(2): 134–140.

Stangegaard, M., et al., Biomek 3000: The workhorse in an automated accredited forensic genetic laboratory. *J Lab Autom*, 2012, **17**(5): 378–386.

Stangegaard, M., et al., Automated extraction of DNA from biological stains on fabric from crime cases. A comparison of a manual and three automated methods. *Forensic Sci Int Genet*, 2013, **7**(3): 384–388.

Stangegaard, M., et al., Evaluation of four automated protocols for extraction of DNA from FTA cards. *J Lab Autom*, 2013, **18**(5): 404–410.

Startari, L., et al., Comparison of extractable DNA from bone following six-month exposure to outdoor conditions, garden loam, mold contamination or room storage. *Med Sci Law*, 2013, **53**(1): 29–32.

Sweet, D., et al., Increasing DNA extraction yield from saliva stains with a modified Chelex method. *Forensic Sci Int*, 1996, **83**(3): 167–177.

Tack, L.C., M. Thomas, and K. Reich, Automated forensic DNA purification optimized for FTA card punches and identifiler STR-based PCR analysis. *Clin Lab Med*, 2007, **27**(1): 183–191.

Tsuchimochi, T., et al., Chelating resin-based extraction of DNA from dental pulp and sex determination from incinerated teeth with Y-chromosomal alphoid repeat and short tandem repeats. *Am J Forensic Med Pathol*, 2002, **23**(3): 268–271.

Vandenberg, N., R.A. van Oorschot, and R.J. Mitchell, An evaluation of selected DNA extraction strategies for short tandem repeat typing. *Electrophoresis*, 1997, **18**(9): 1624–1626.

Vandewoestyne, M., et al., Evaluation of three DNA extraction protocols for forensic STR typing after laser capture microdissection. *Forensic Sci Int Genet*, 2012, **6**(2): 258–262.

von Wurmb-Schwark, N., et al., The impact of DNA contamination of bone samples in forensic case analysis and anthropological research. *Leg Med (Tokyo)*, 2008, **10**(3): 125–130.

Walsh, P.S., D.A. Metzger, and R. Higuchi, Chelex 100 as a medium for simple extraction of DNA for PCR-based typing from forensic material. *Biotechniques*, 1991, **10**(4): 506–513.

Wilkinson, D.A., et al., The fate of the chemical warfare agent during DNA extraction. *J Forensic Sci*, 2007, **52**(6): 1272–1283.

Winskog, C., et al., The use of commercial alcohol products to sterilize bones prior to DNA sampling. *Forensic Sci Med Pathol*, 2010, **6**(2): 127–129.

Witt, S., et al., Establishing a novel automated magnetic bead-based method for the extraction of DNA from a variety of forensic samples. *Forensic Sci Int Genet*, 2012, **6**(5): 539–547.

Wolfe, K.A., et al., Toward a microchip-based solid-phase extraction method for isolation of nucleic acids. *Electrophoresis*, 2002, **23**(5): 727–733.

Wolfgramm Ede, V., et al., Simplified buccal DNA extraction with FTA Elute Cards. *Forensic Sci Int Genet*, 2009, **3**(2): 125–127.

Ye, J., et al., A simple and efficient method for extracting DNA from old and burned bone. *J Forensic Sci*, 2004, **49**(4): 754–759.

Yoshida-Yamamoto, S., et al., Efficient DNA extraction from nail clippings using the protease solution from Cucumis melo. *Mol Biotechnol*, 2010, **46**(1): 41–48.

Zamir, A., Y. Cohen, and M. Azoury, DNA profiling from heroin street dose packages. *J Forensic Sci*, 2007, **52**(2): 389–392.

Zehner, R., “Foreign” DNA in tissue adherent to compact bone from tsunami victims. *Forensic Sci Int Genet*, 2007, **1**(2): 218–222.

Zhang, H., et al., Solid-phase based on-chip DNA purification through a valve-free stepwise injection of multiple reagents employing centrifugal force combined with a hydrophobic capillary barrier pressure. *Analyst*, 2013, **138**(6): 1750–1757.

Zhang, S.H., et al., Genotyping of urinary samples stored with EDTA for forensic applications. *Genet Mol Res*, 2012, **11**(3): 3007–3012.

6

DNA Quantitation

Determining the amount of DNA in a sample is essential for polymerase chain reaction (PCR)-based DNA testing (Chapter 7). Because PCR-based DNA testing is very sensitive, a narrow concentration range is required for amplification to be successful. If too much DNA template is used in PCR, the resulting artifacts may interfere with data analysis and interpretation. On the other hand, very low amounts of DNA template may result in a partial DNA profile or failure to attain a profile. Samples with poor purity may contain PCR inhibitors that lead to a failure of DNA amplification. Thus, a test that can measure the quality and quantity of the DNA template of a sample is desirable.

Additionally, forensic samples containing DNA are often mixtures that may include nonhuman DNA. For instance, microbial DNA may be present. Thus, it is necessary to use human-specific DNA quantitation methods to selectively determine the amount of human DNA present. In the United States, quality-assurance guidelines require the use of a quantitation method that estimates the amount of human nuclear DNA in crime-scene evidence samples.

In this chapter, the slot blot, intercalating dye, and quantitative PCR methods are introduced. The quantitative PCR method is the most sensitive of the three methods. It is the only method that can detect PCR inhibitors. Both the slot blot and the quantitative PCR methods can detect human and nonhuman primate DNA. Current technology cannot distinguish between human and nonhuman primate DNA.

6.1 Slot Blot Assay

Historically, the slot blot assay was used to detect human genomic DNA in a sample. Methodically, the slot blot assay works based on the following principles. Prior to the quantitation, an alkaline solution is added to the genomic DNA sample, which denatures DNA. Generating single-stranded DNA is necessary for DNA to be cross-linked onto a nitrocellulose membrane. The DNA sample is then spotted, using a slot blot device, onto a nitrocellulose membrane (Figure 6.1). The single-stranded DNA is then immobilized onto a nylon membrane. The targeted sequence is revealed by hybridization with a labeled 40-nucleotide probe complementary to a primate-specific α-satellite DNA sequence at the D17Z1 locus (Figure 6.2). In humans, the α-satellite DNA sequences are highly repetitive sequences located near the centromeres of chromosomes. These sequences are usually distinct for each chromosome.

Three detecting schemes of the slot blot assay have been developed. Initially, the D17Z1 probe was labeled with radioisotopes that could be visualized by exposing the slot blot membrane to x-ray film. The hazardous radioisotope detection method was then replaced by alkaline phosphatase-labeled and biotinylated probes. The alkaline phosphatase-labeled probe can be coupled with chemiluminescent detection (Lumi-Phos Plus kit, Lumigen, Inc.). The biotinylated probe



Figure 6.1 A slot blot device. (© Richard C. Li.)

(QuantiBlot Human DNA Quantitation Kit, Applied Biosystems) can be coupled with either colorimetric or chemiluminescent detection.

In colorimetric detection, the biotin moiety of the probe is bound to streptavidin. The streptavidin is conjugated with horseradish peroxidase, which catalyzes the oxidation reaction of tetramethylbenzidine (TMB), a substrate, forming a blue precipitate. With the chemiluminescent detection method, the horseradish peroxidase catalyzes the oxidation reaction of a substrate such as luminol, emitting photons that can be detected by exposure to x-ray film. The sensitivity of chemiluminescent detection is slightly higher than that of the colorimetric detection. The detection mechanisms will be discussed in Chapter 9.

The detected signal intensity is proportional to the concentration of the DNA sample in question. Quantitative measurements can be made by comparing an unknown sample to a set of standards with known DNA concentrations (Figure 6.3).

The assay typically quantifies DNA over the range of 150 pg–10 ng. However, the quantitation results are manually read, and conclusions are based on subjective judgments. Additionally, the D17Z1 sequences of humans and other primates share homology. The probe cannot distinguish between human and other primate genomic DNA. This is not a great concern because cases involving nonhuman primates are rare. Nevertheless, the probe does not cross-react with all other species. This assay has been replaced by recently developed quantitative PCR assays (see Section 6.3).

6.2 Fluorescent Intercalating Dye Assay

Small quantities of DNA can also be quantified by using a fluorescent intercalating dye method. Intercalating dyes, usually planar molecules, can slide themselves in between base pairs of DNA without breaking the DNA double helix. The Quant-iT™ PicoGreen® dsDNA reagent (Invitrogen) is a fluorescent intercalating dye that stains double-stranded DNA (dsDNA) for quantitation in a sample (Figure 6.4a). The detection limit of this method is approximately 250 pg. Intercalating dyes, not specific to human DNA, bind to all DNA molecules. Therefore, fluorescent intercalating dye assay can be utilized for the quantitation of known reference samples. For instance, DNA database samples from known sources can be quantified using this method. The assay has also been adapted for automation and is, thus, a high-throughput method.

DNA samples are simply added to a solution containing the fluorescent intercalating dye. The fluorescence, proportional to the quantities of DNA (Figure 6.4b), is measured using a standard spectrofluorometer with excitation and emission wavelengths of the light source. A standard


TMB
(colorless)
Blue
precipitate
HRP
SA
Biotinylated D17Z1 probe
Immobilized question DNA
(a) Membrane
Luminol
hv
HRP
SA
Biotinylated D17Z1 probe
Immobilized question DNA
(b) Membrane
Lumigen® PPD
hv
AP
AP conjugated D17Z1 probe
Immobilized question DNA
(c) Membrane

Figure 6.2 Slot blot assay. Questioned DNA is immobilized onto a solid-phase membrane then hybridized with a biotinylated D17Z1 probe. The detection of the hybridization is carried out by (a) streptavidin (SA) and horseradish peroxidase (HRP) conjugate, and a colorimetric reaction is catalyzed by HRP using tetramethylbenzidine (TMB) as a substrate; (b) SA and HRP conjugate, and a chemiluminescent reaction is catalyzed by HRP using Luminol as a substrate; (c) immobilized DNA is hybridized with an alkaline phosphatase (AP)-labeled D17Z1 probe. The detection of the hybridization is carried out by a chemiluminescent reaction catalyzed by AP using Lumigen® PPD as a substrate. (© Richard C. Li.)


DNA standards
Question samples
DNA standards
10 ng
5 ng
2.5 ng
1.25 ng
0.625 ng
0.3125 ng
0.15625 ng
Blank
Blank
0.15625 ng
0.3125 ng
0.625 ng
1.25 ng
2.5 ng
5 ng
10 ng

Figure 6.3 Human DNA quantitation using the slot blot assay. Standards with known amounts of human DNA are applied, and unknown samples and a set of standards are compared. The quantities in the unknown samples are estimated by visual comparison to the standards. (© Richard C. Li.)


Intercalating dye
Excitation
hv
(a)
Question DNA sample
Fluorescence
0
Concentration of DNA
(b)

Figure 6.4 DNA quantitation using intercalating dye. (a) Fluorescent dye intercalates into DNA. The fluorescence can be measured upon applying an excitation light source. (b) A standard curve can be constructed using known amounts of DNA standards. The amount of questioned DNA can be determined by comparing the standard curve. (© Richard C. Li.)

curve is first created using samples containing known amounts of DNA. The assay is then performed for the unknown samples and the quantities of DNA in the samples are determined by comparing the results to the standard curve.

6.3 Quantitative PCR Assay

Based on the principle of PCR amplification (Chapter 7), the amount of PCR product amplified correlates with the initial concentration of DNA templates. Thus, the DNA concentration of a sample can be determined. There are two types of quantitative PCR methods. *End-point PCR* methods measure the quantity of amplified product at the end of PCR. Usually, the fluorescence is emitted by the dyes that intercalate into the double-stranded DNA. The quantity of amplified DNA is measured from the amount of fluorescence emitted from dyes such as SYBR (Figures 6.5 and 9.1b).

Real-time PCR methods can quantify the amplified DNA during the exponential phase of PCR (Chapter 7). The quantitation result is not affected to a significant extent by slight variations in PCR conditions. Thus, the precision of the quantitation of target sequences is improved with this method.

6.3.1 Real-Time Quantitative PCR

Real-time quantitative PCR (qPCR) was developed in the early 1990s, and it analyzes the amplification of a target sequence at each cycle of PCR. A fluorescent reporter is used to monitor the accumulation of amplified products during PCR. The fluorescence signals of the reporter molecule increase as amplified products accumulate with each cycle of PCR. qPCR is commonly used because of the following advantages:

- Better objectivity than the QuantiBlot method
- Increased sensitivity with a large dynamic range (30 pg–100 ng)
- More accurate measurements of small quantities of DNA in samples
- Fewer laboratory manipulations; amenable to automation
- Ability to detect PCR inhibitors (Section 6.3.1.1)



Figure 6.5 End-point PCR using SYBR Green detection. During the extension phase of PCR, in which DNA synthesis occurs, the dye binds to the double-stranded amplicons. Upon excitation, the emission intensity of the dye can be measured. Pol represents Taq polymerase. (© Richard C. Li.)

]

The technique is amenable to multiplexing to detect more than one type of DNA target sequence in a single reaction. Commercial qPCR kits for human DNA and Y-chromosome DNA quantitation are available. Additionally, the qPCR method for mtDNA quantitation is possible. qPCR uses commercially available fluorescence-detecting thermocyclers to amplify specific DNA sequences and measure their concentrations simultaneously. The fluorescent reporter can be a nonspecific intercalating double-stranded DNA-binding dye or a sequence-specific fluorescently labeled oligonucleotide probe (Chapter 9). The target sequences are amplified and detected by the same instrument, and the reporter fluorescence is monitored externally. Thus the reaction tubes do not need to be opened. This minimizes aerosol contamination and reduces the risk of false-positive results. A widely used qPCR probe technique is the TaqMan method (Applied Biosystems).

6.3.1.1 TaqMan Method

This method utilizes the 5′ exonuclease activity of *Taq* polymerase to cleave the probe during PCR (also known as the 5′ exonuclease assay). The probe is designed to anneal to the target sequence between the upstream and downstream primers and is added to the PCR mixture together with primers (Figure 6.6). The probe T_m (melting temperature; see Chapter 7) should be higher than the amplification primer T_m. A minor groove binder (MGB), such as dihydrocyclopyrroloindole tripeptide, is often linked at the 3′ end of the probe (Figure 6.6). A conjugated MGB binds to the minor groove of a B-form DNA helix (Figure 6.7), which is stabilized by van



Figure 6.6 TaqMan probe. Each probe is labeled with a reporter dye (R) on the 5′ end and a fluorescence quencher (Q) on the 3′ end. MGB represents a minor groove binder. (© Richard C. Li.)



Figure 6.7 DNA double helix. The double-helical structure of B-DNA, the most common form of DNA, is shown. With a helical diameter of 2 nm, each turn of the helix takes 3.4 nm, which corresponds to 10 base pairs per turn. The major and minor grooves are shown. (© Richard C. Li.)

der Waals forces. As a result, conjugating an MGB into a probe increases the T_m values, allowing for the use of shorter probes. As a result, having the probe T_m higher than that of the primers ensures that the probe is fully hybridized during primer extension. The oligonucleotide probe is labeled with both a *reporter* fluorescent dye, usually 6-carboxyfluorescein (6-FAM) or tetrachlorofluorescein (TET) at the 5′ end; and a nonfluorescent *quencher* moiety, such as tetramethylrhodamine (TAMRA), usually at the 3′ end or any thymine position. While the probe is intact, the quencher greatly reduces the fluorescence emitted by the reporter via fluorescent resonance energy transfers (FRET). FRET is a distance-dependent interaction between two molecules in which the excitation energy is transferred from a photon donor molecule (reporter) to an acceptor molecule (quencher) without emission of a photon. During the extension phase of the PCR cycle, the 5′ exonuclease activity of Taq polymerase cleaves the reporter dye from the probe. Because the reporter dye is no longer in close proximity to the quencher, the FRET is disrupted and the probe begins to fluoresce (Figure 6.8). The intensity of fluorescence can be measured (Chapter 9) and is proportional to the amount of target DNA synthesized during the PCR.

In this assay, the rate of accumulation of amplified DNA over the entire course of a PCR is generated. The greater the initial concentration of target templates in a sample, the fewer cycles required to reach a particular quantity of amplified product. The initial concentration of target templates can be expressed using the *cycle threshold* (C_T). C_T is defined as the number of PCR cycles required for the fluorescent signal to cross a threshold of amplification where the signal exceeds background level or baseline noise. A plot of C_T against the $\log_{10}$ of the initial concentration of a set of DNA standards yields a straight line as a standard curve (Figure 6.9). The target sequences in an unknown sample can be quantified by comparing to the standard curve. Additionally, qPCR has the ability to detect PCR inhibitors (Chapter 7) that interact with DNA or with DNA polymerases. The presence of PCR inhibitors in the DNA extracts can be measured by monitoring the amplification of the internal positive control (IPC). Most human DNA quantitation kits contain a known amount of exogenous DNA as IPC that can be fortified to the sample and amplified. Monitoring the amplification of IPC enables the detection of PCR failure due to inhibition when the IPC's C_T value is higher than that of an uninhibited PCR reaction.



Figure 6.8 Real-time PCR with TaqMan detection. The TaqMan probe is shown. During extension, the 5′ nuclease activity of Taq polymerase (Pol) cleaves the probe. Reporter dye is released during each cycle of PCR. (© Richard C. Li.)



Figure 6.9 Real-time quantitative PCR. (a) Amplification curves for a dilution series of standards with known quantities of DNA. C_T is the cycle threshold at which the amplification curve crosses the threshold, as indicated by the red line. (b) A standard curve based on data obtained from the amplification curves. The quantity of DNA in a questioned sample can be determined from the standard curve. (© Richard C. Li.)

Bibliography

Ahn, S.J., J. Costa, and J.R. Emanuel, PicoGreen quantitation of DNA: Effective evaluation of samples pre- or post-PCR. *Nucleic Acids Res*, 1996, **24**(13): 2623–2625.

Alonso, A. and P. Martin, A real-time PCR protocol to determine the number of amelogenin (X-Y) gene copies from forensic DNA samples. *Methods Mol Biol*, 2005, **297**: 31–44.

Alonso, A., et al., Specific quantification of human genomes from low copy number DNA samples in forensic and ancient DNA studies. *Croat Med J*, 2003, **44**(3): 273–280.

Alonso, A., et al., Real-time PCR designs to estimate nuclear and mitochondrial DNA copy number in forensic and ancient DNA studies. *Forensic Sci Int*, 2004, **139**(2–3): 141–149.

Andreasson, H. and M. Allen, Rapid quantification and sex determination of forensic evidence materials. *J Forensic Sci*, 2003, **48**(6): 1280–1287.

Andreasson, H., U. Gyllensten, and M. Allen, Real-time DNA quantification of nuclear and mitochondrial DNA in forensic analysis. *Biotechniques*, 2002, **33**(2): 402–404, 407–411.

Andreasson, H., et al., Nuclear and mitochondrial DNA quantification of various forensic materials. *Forensic Sci Int*, 2006, **164**(1): 56–64.

Budowle, B., et al., Simple protocols for typing forensic biological evidence: Chemiluminescent detection for human DNA quantitation and restriction fragment length polymorphism (RFLP) analyses and manual typing of polymerase chain reaction (PCR) amplified polymorphisms. *Electrophoresis*, 1995, **16**(9): 1559–1567.

Budowle, B., et al., The presumptive reagent fluorescein for detection of dilute bloodstains and subsequent STR typing of recovered DNA. *J Forensic Sci*, 2000, **45**(5): 1090–1092.

Budowle, B., et al., Using a CCD camera imaging system as a recording device to quantify human DNA by slot blot hybridization. *Biotechniques*, 2001, **30**(3): 680–685.

Del Rio, S.A., M.A. Marino, and P. Belgrader, Reusing the same blood-stained punch for sequential DNA amplifications and typing. *Biotechniques*, 1996, **20**(6): 970–972, 974.

Duewer, D.L., et al., NIST mixed stain studies #1 and #2: Interlaboratory comparison of DNA quantification practice and short tandem repeat multiplex performance with multiple-source samples. *J Forensic Sci*, 2001, **46**(5): 1199–1210.

Fox, J.C., C.A. Cave, and J.W. Schumm, Development, characterization, and validation of a sensitive primate-specific quantification assay for forensic analysis. *Biotechniques*, 2003, **34**(2): 314–318, 320, 322.

Green, R.L., et al., Developmental validation of the quantifiler real-time PCR kits for the quantification of human nuclear DNA samples. *J Forensic Sci*, 2005, **50**(4): 809–825.

Hayn, S., et al., Evaluation of an automated liquid hybridization method for DNA quantitation. *J Forensic Sci*, 2004, **49**(1): 87–91.

Hewakapuge, S., et al., Investigation of telomere lengths measurement by quantitative real-time PCR to predict age. *Leg Med* (Tokyo), 2008, **10**(5): 236–242.

Hudlow, W.R., et al., A quadruplex real-time qPCR assay for the simultaneous assessment of total human DNA, human male DNA, DNA degradation and the presence of PCR inhibitors in forensic samples: A diagnostic tool for STR typing. *Forensic Sci Int Genet*, 2008, **2**(2): 108–125.

Kihlgren, A., A. Beckman, and S. Holgersson, Using D3S1358 for quantification of DNA amenable to PCR and for genotype screening. *Prog Forensic Genet*, 1998, **7**: 3.

Kline, M.C., et al., NIST Mixed Stain Study 3: DNA quantitation accuracy and its influence on short tandem repeat multiplex signal intensity. *Anal Chem*, 2003, **75**(10): 2463–2469.

Koukoulas, I., et al., Quantifiler observations of relevance to forensic casework. *J Forensic Sci*, 2008, **53**(1): 135–141.

Krenke, B.E., et al., Developmental validation of a real-time PCR assay for the simultaneous quantification of total human and male DNA. *Forensic Sci Int Genet*, 2008, **3**(1): 14–21.

LaSalle, H.E., G. Duncan, and B. McCord, An analysis of single and multi-copy methods for DNA quantitation by real-time polymerase chain reaction. *Forensic Sci Int Genet*, 2011, **5**(3): 185–193.

Mandrekar, M.N., et al., Development of a human DNA quantitation system. *Croat Med J*, 2001, **42**(3): 336–339.

Morrison, T.B., J.J. Weis, and C.T. Wittwer, Quantification of low-copy transcripts by continuous SYBR Green I monitoring during amplification. *Biotechniques*, 1998, **24**(6): 954–958, 960, 962.

Myers, J.R., Validation of a DNA quantitation method on the Biomek® 3000. *J Forensic Sci*, 2010, **55**(6): 1570–1575.

Nicklas, J.A. and E. Buel, Development of an Alu-based, real-time PCR method for quantitation of human DNA in forensic samples. *J Forensic Sci*, 2003, **48**(5): 936–944.

Nicklas, J.A. and E. Buel, Quantification of DNA in forensic samples. *Anal Bioanal Chem*, 2003, **376**(8): 1160–1167.

Nicklas, J.A., T. Noreault-Conti, and E. Buel, Development of a real-time method to detect DNA degradation in forensic samples. *J Forensic Sci*, 2012, **57**(2): 466–471.

Niederstatter, H., et al., Characterization of mtDNA SNP typing and mixture ratio assessment with simultaneous real-time PCR quantification of both allelic states. *Int J Legal Med*, 2006, **120**(1): 18–23.

Niederstatter, H., et al., A modular real-time PCR concept for determining the quantity and quality of human nuclear and mitochondrial DNA. *Forensic Sci Int Genet*, 2007, **1**(1): 29–34.

Nielsen, K., et al., Comparison of five DNA quantification methods. *Forensic Sci Int Genet*, 2008, **2**(3): 226–230.

Omelia, E.J., M.L. Uchimoto, and G. Williams, Quantitative PCR analysis of blood- and saliva-specific microRNA markers following solid-phase DNA extraction. *Anal Biochem*, 2013, **435**(2): 120–122.

Ong, Y.L. and A. Irvine, Quantitative real-time PCR: A critique of method and practical considerations. *Hematology*, 2002, **7**(1): 59–67.

Puch-Solis, R., et al., Practical determination of the low template DNA threshold. *Forensic Sci Int Genet*, 2011, **5**(5): 422–427.

Richard, M.L., R.H. Frappier, and J.C. Newman, Developmental validation of a real-time quantitative PCR assay for automated quantification of human DNA. *J Forensic Sci*, 2003, **48**(5): 1041–1046.

Shewale, J.G., et al., Human genomic DNA quantitation system, H-Quant: Development and validation for use in forensic casework. *J Forensic Sci*, 2007, **52**(2): 364–370.

Sifis, M.E., K. Both, and L.A. Burgoyne, A more sensitive method for the quantitation of genomic DNA by Alu amplification. *J Forensic Sci*, 2002, **47**(3): 589–592.

Swango, K.L., et al., A quantitative PCR assay for the assessment of DNA degradation in forensic samples. *Forensic Sci Int*, 2006, **158**(1): 14–26.

Swango, K.L., et al., Developmental validation of a multiplex qPCR assay for assessing the quantity and quality of nuclear DNA in forensic samples. *Forensic Sci Int*, 2007, **170**(1): 35–45.

Tak, Y.K., et al., Highly sensitive polymerase chain reaction-free quantum dot-based quantification of forensic genomic DNA. *Anal Chim Acta*, 2012, **721**: 85–91.

Thomas, J.T., et al., Qiagen's Investigator Quantiplex Kit as a predictor of STR amplification success from low-yield DNA samples. *J Forensic Sci*, 2013, **58**(5): 1306–1309.

Timken, M.D., et al., A duplex real-time qPCR assay for the quantification of human nuclear and mitochondrial DNA in forensic samples: Implications for quantifying DNA in degraded samples. *J Forensic Sci*, 2005, **50**(5): 1044–1060.

Tozzo, P., et al., Discrimination between human and animal DNA: Application of a duplex polymerase chain reaction to forensic identification. *Am J Forensic Med Pathol*, 2011, **32**(2): 180–182.

Walker, J.A., et al., Multiplex polymerase chain reaction for simultaneous quantitation of human nuclear, mitochondrial, and male Y-chromosome DNA: Application in human identification. *Anal Biochem*, 2005, **337**(1): 89–97.

Walsh, P.S., J. Varlaro, and R. Reynolds, A rapid chemiluminescent method for quantitation of human DNA. *Nucleic Acids Res*, 1992, **20**(19): 5061–5065.

Waye, J.S., et al., A simple and sensitive method for quantifying human genomic DNA in forensic specimen extracts. *Biotechniques*, 1989, **7**(8): 852–855.

Westring, C.G., et al., Validation of reduced-scale reactions for the Quantifiler Human DNA kit. *J Forensic Sci*, 2007, **52**(5): 1035–1043.

Wilson, J., et al., Molecular assay for screening and quantifying DNA in biological evidence: The modified Q-TAT assay. *J Forensic Sci*, 2010, **55**(4): 1050–1057.

7

Amplification by Polymerase Chain Reaction

7.1 Denaturation and Renaturation of DNA

The DNA double helix is stabilized by chemical interactions. Base pairing of the two strands involves the formation of hydrogen bonds that provide weak electrostatic attractions between electronegative atoms. An adenine always pairs with a thymine (two hydrogen bonds), and a cytosine pairs with a guanine (three hydrogen bonds) (see Figure 7.1). Base stacking involves hydrophobic interactions between adjacent base pairs and provides stability to the double helix.

Double-stranded DNA is maintained by hydrogen bonding between the bases of complementary pairs. *Denaturation* occurs when the hydrogen bonds of DNA are disrupted, and the strands are separated. A *melting curve* can be obtained from measuring DNA denaturation by slowly heating a solution of DNA. As shown in Figure 7.2, an increasing temperature increases the percentage of the DNA that is denatured. The temperature at which 50% of DNA strands are denatured is defined as the *melting temperature* (T_m). The value of T_m is affected by the salt concentration of the solution, but can also be affected by nucleotide content, high pH, and length of the molecule.

Nucleotide content affects the value of T_m because GC pairs are joined by three hydrogen bonds while the AT pairs are joined by only two. Increasing the GC content of a DNA molecule increases the T_m. Excessively high pH causes the hydrogen bonds to break and the paired strands to separate. Finally, the length of the molecule also affects the T_m simply because a longer molecule of DNA requires more energy to break more bonds than a shorter molecule.

The single strands in a solution of denatured DNA can, under certain conditions, reanneal into double-stranded DNA. The process is called *renaturation* and two requirements must be met for it to occur. First, sufficient amounts of charged molecules, such as salts, must be present in the solution to neutralize the negative charges of the phosphate groups in DNA. This prevents the complementary strands from repelling each other. Additionally, the temperature must be high enough to disrupt hydrogen bonds that formed randomly between the bases of DNA strands. However, excessively elevated temperatures can disrupt the base pairs between the complementary DNA strands.

7.2 Basic Principles of Polymerase Chain Reaction

The *polymerase chain reaction* (*PCR*) allows the exponential amplification of specific sequences of DNA to yield sufficient amplified products, also known as *amplicons*, for various downstream



Figure 7.1 Base pairing between two DNA strands. (a) An adenine (right) pairs with a thymine (left). (b) A cytosine (left) pairs with a guanine (right).



Figure 7.2 Melting curve of DNA. The degree of DNA denaturation is increased by increasing the temperature. T_m and possible shapes of a DNA molecule are shown. (© Richard C. Li.)

applications. The technique is highly sensitive and can amplify very small quantities of DNA. Therefore, it can be utilized for the analysis of samples of limited quantity. PCR-based assays are rapid and robust. Thus, PCR forms the basis of many forensic DNA assays such as DNA quantitation (Chapter 6), short tandem repeat (STR) profiling (Chapter 20), and mitochondrial DNA (mtDNA) sequencing (Chapter 23).

The concept of synthesizing DNA by a cycling process was first proposed in the early 1970s. In the mid-1980s, PCR technology was finally developed by Kary Mullis and his coworkers (Cetus Corporation) to amplify the β-globin gene for the diagnosis of sickle-cell anemia. In the late 1980s, a



Figure 7.3 PCR amplification curve. A fluorescence signal results from the accumulation of amplicon. The location of the signal threshold is indicated as a dashed line. The C_T value for the curve is the cycle at which the amplification curve crosses the threshold. (© Richard C. Li.)

thermostable polymerase from *Thermus aquaticus* was utilized for PCR. This step greatly increased efficiency and allowed the process to be automated. The result was a powerful impact on molecular biology. In 1993, Mullis was awarded the Nobel Prize for the invention of PCR technology.

In the early 1990s, the technique for the simultaneous amplification and detection of the accumulation of amplicons at each PCR cycle was developed, and the concept of *real-time PCR* was born. This process allows the monitoring of amplicon production at each cycle of the PCR process. The fundamental processes were studied by characterizing the amplification kinetics of PCR using a graph that plotted the amount of amplicon yield at each cycle versus the cycle number (Figure 7.3).

An S-shaped amplification curve is obtained and divided into an exponential phase, a linear phase, and a plateau. During the exponential phase, the amplicon accumulates exponentially. It was revealed that the amplicon accumulation during PCR was correlated to the starting copy number of DNA template. Thus, the amount of amplicon produced during the exponential amplification phase can be used to determine the amount of starting material. This relationship can be further examined using a plot of cycle numbers versus a log scale of the serial dilution of the starting concentration of DNA template, which results in a linear relationship (see Chapter 6). It demonstrates that fewer cycles are needed if larger quantities of starting DNA template are present. The slope of this linear curve (Figure 6.9b) is known as the *amplification efficiency*. The exponential phase continues until one or more of the components (Section 7.3) in the reaction become limited. At this point, the amplification efficiency decreases, the amplicon no longer accumulates exponentially, and PCR enters the linear phase of the curve. At the plateau phase, no more amplicon is accumulated due to the exhaustion of reagents and polymerase.

7.3 Essential PCR Components

A PCR reaction requires thermostable DNA polymerases, primers, and other components, as described below (Figure 7.4).

7.3.1 Thermostable DNA Polymerases

A wide variety of DNA polymerases are available. They vary in fidelity, efficiency, and ability to synthesize longer DNA fragments. Nonetheless, *Taq* polymerase is the most commonly used

HAMILTON
microLAB
NIMBUS
NIMBUS PCR
Automated Assay Setup

Figure 7.4 A liquid handling workstation for automated PCR assay setup. (© Richard C. Li.)

enzyme for routine PCR applications (0.5–5 units per reaction). Currently, AmpliTaq Gold™ DNA polymerase (Applied Biosystems) is the most common DNA polymerase for forensic applications.

PCR reactions are usually set up at room temperature. Nonspecific annealing between primers and template DNA can occur, resulting in the formation of nonspecific amplicons. Additionally, annealing between the primers can occur to form primer dimers. Nonspecific annealing interferes with PCR amplification by reducing the amplification efficiency of the specific sequences of interest.

Such interference can be minimized by a *hot-start PCR* approach. The AmpliTaq Gold™ DNA polymerase, a modified enzyme, remains in an inactive form until activated with a pH below 7 prior to the PCR cycling in which the inhibitory motif is inactivated. The pH of the buffer system used in the PCR reaction is temperature sensitive; increasing the temperature decreases the pH of the solution. Thus, the activation of the enzyme can actually be carried out by a heating step at 95°C prior to the start of the cycling. During the heating process, the DNA strands also denature, which can prevent the formation of nonspecific PCR products.

7.3.2 PCR Primers

PCR primers are the oligonucleotides that are complementary to the sequences that flank the target region of the template. A pair (forward and reverse) of primers (typically 0.1–1 µM) is required. Properly designed primers are critical to the success of a PCR reaction. Computer software such as Primer3 is available to assist and optimize the designing of primers.

A primer must be specific to the target sequence; otherwise, nonspecific products that might interfere with the proper interpretation of a DNA profile might be produced. The primers within a pair should have similar T_m values. The estimated T_m values of a primer pair should not differ by more than 5°C. The T_m of an oligonucleotide primer can be predicted and calculated using the following equation:

$$T_m = 81.5°C + 16.6\left(\log_{10}[K^+]\right) + 0.41\left(\%\ [G+C]\right) - \left(\frac{675}{n}\right)$$

where:

$[K^+]$ = concentration of the potassium ion
$[G+C]$ = GC content (%) of the oligonucleotide
n = number of bases in the oligonucleotide

This equation shows that the T_m can be affected by primer base composition (GC content) and primer length. The GC content of an oligonucleotide primer should be 40%–60%, and the length of an oligonucleotide primer should be 15–25 base pairs, although longer primers can be used.

A primer should not contain self-complementary sequences that may form hairpin structures interfering with the annealing of primers and the template. Additionally, the primers in a pair should not share similar sequences, to avoid the primers from annealing to each other. These annealed primers may then be amplified during PCR, creating products known as *primer dimers*, which compete with the target DNA template for PCR components.

Multiplex PCR is the simultaneous amplification of more than one region of a DNA template in a single reaction to achieve high-throughput analysis. Multiplex PCR consists of multiple primer sets in a single reaction to produce amplicons of multiple target DNA regions. The primers should be designed to yield proper sizes of amplicons to be resolvable in downstream separation and detection procedures such as electrophoresis. To prevent preferential amplification of one target sequence over another, the annealing temperatures should be similar among multiplex PCR primer pairs. Additionally, the primers should lead to similar amplification efficiencies among the loci to be tested. Forensic applications of multiplex PCR, such as autosomal and Y-chromosomal short tandem repeat analysis, are discussed in Chapters 20 and 21.

7.3.3 Other Components

Essential components include template DNA with target sequences in either linear form (nuclear genomic DNA) or circular form (mitochondrial DNA). Both single- and double-stranded DNA can be used as a template for PCR. Typically, 1–2.5 ng of template DNA is utilized for forensic applications using PCR.

Deoxynucleoside triphosphates (dNTPs) are the substrates for DNA synthesis. A PCR assay usually contains equal molar amounts (typically, 200 μM) of dATP, dCTP, dGTP, and dTTP.

Divalent cations, such as Mg^{2+}, are required for the enzymatic activity of DNA polymerases. A PCR assay usually contains 1.5–2.5 mM Mg^{2+}. Monovalent cations, such as K^+ (50 mM), are usually recommended, and a buffer is often utilized to maintain pH between 8.3 and 8.8 at room temperature.

Controls should be used to monitor the effectiveness of PCR amplification. A *positive control* shows that PCR components such as reagents and PCR cycle parameters are working properly during a PCR. A standard DNA template should be used as a positive control and amplified with the same PCR components used on the rest of the samples. The amplification negative control and extraction reagent blank are discussed in Section 7.5.4.

7.4 Cycle Parameters

PCR cycling protocols may vary according to the type of analysis. Figure 7.5 shows representative PCR cycling conditions commonly used by forensic DNA laboratories. PCR utilizes a number of cycles for the replication of a specific region of a DNA template. During each cycle, a copy of the target DNA sequence is synthesized. A PCR cycle consists of three elements: denaturation, annealing, and extension. Precise and accurate temperatures at denaturation, annealing, and extension are critical to achieve a successful amplification. At the beginning of each cycle, the two complementary DNA template strands are separated at high temperatures (94°C–95°C) in a process called *denaturation*. The temperature is then decreased to allow *annealing* between the oligonucleotide primers and the template. The temperature for annealing is usually 3°C–5°C lower than the T_m of the oligonucleotide primer.

The annealing temperature is critical. If it is too high, a very low quantity of amplicon is yielded because of the failure of annealing between the primer and the template. If the annealing temperature is too low, nonspecific amplification can occur. Next, optimal temperature for DNA polymerase is reached, thus allowing for DNA replication (*extension*). By the end of each cycle, the copy number of the amplicon is nearly doubled (Figure 7.6).



Figure 7.5 Temperature parameters during thermal cycling of the PCR process. The first three cycles are shown. (© Richard C. Li.)



Figure 7.6 First cycle of PCR. The amplified region is determined by the positions of the primers. The direction (5′ to 3′) of DNA synthesis is indicated by arrows. Pol represents *Taq* polymerase. (© Richard C. Li.)

The number of cycles needed for PCR depends primarily on the number of copies of starting DNA template. The relationship can be expressed as the following equation:

$$N_x = N_0\left(1+E\right)^x$$

where:

X = number of PCR cycles
N_x = copy number of the amplicon after x cycles of PCR
N_0 = initial copy number of the template
E = amplification efficiency of the *Taq* polymerase

For example, in a 28-cycle PCR amplification, the DNA template can theoretically be amplified by a factor of approximately 10^8. If the cycle number is increased to 34, a factor of 10^{10} can theoretically be reached.

PCR amplification can be carried out using an instrument known as a *thermal cycler* (Figure 7.7). Various types of thermal cyclers differ in the number of samples they can process, the sizes of the sample tubes, and temperature control features.

Figure 7.7 Thermal cyclers. A thermal cycler can provide rapid temperature changes as desired to carry out PCR. A PCR thermal cycler (left) and a real-time PCR instrument (right). (© Richard C. Li.)

7.5 Factors Affecting PCR

7.5.1 Template Quality

It is important to prevent degradation of the DNA during the collection and processing of evidence. Degradation causes DNA to break into smaller fragments. If the damage occurs at a region to be amplified, the result can be failure in PCR amplification. In a degraded sample, the longer the amplicon length, the higher the risk of failure in PCR. Low copy number (LCN) of DNA template is often encountered in forensic samples. When amplifying very low levels (approximately 100 pg of DNA) of a template, the following phenomenon is often observed: one of the two alleles fails to be detected from a heterozygote and can falsely be identified as a homozygote. This phenomenon is also known as the *stochastic effect* in which the two alleles in a heterozygous individual are unequally detected at a low level of starting DNA template. Approaches such as increasing the cycle number, from 28 to 34 (Section 7.4), have been introduced to address the LCN problem.

7.5.2 Inhibitors

Inhibitors, if present, can interact with the DNA template or polymerase, causing PCR amplification failure. The presence of PCR inhibitors can be detected using an internal positive control (Section 6.3.1.1). A number of PCR inhibitors commonly encountered in evidence samples include heme molecules from blood, indigo dyes from fabrics, and melanin from hair samples. Thus, it is important to remove PCR inhibitors during DNA extraction. If PCR inhibitors are not eliminated during the extraction process, additional procedures such as the use of centrifugal filtration devices can be used. Centrifugal filtration devices can separate molecules by size. After the centrifugation step, small molecular weight inhibitors are filtered by passing through the membrane and are discarded. Alternatively, increasing the amount of DNA polymerase or adding bovine serum albumin (BSA) in the reaction can overcome the inhibition effects.

7.5.3 Contamination

PCR is a highly sensitive method; therefore, procedures that minimize the risk of contamination are necessary. To prevent contamination, pre- and post-PCR samples should be processed in separate areas or at different times. Additionally, reagents, supplies, and equipment used for pre- and post-PCR steps should be separated as well. Protective gear should include laboratory coats and disposable gloves. Facial masks and hair caps may be used if necessary. Aerosol-resistant pipet tips and DNA-free solutions and test tubes should also be used.

The levels of contamination must be monitored using controls. Extraction *reagent blanks*, which contain all extraction reagents but no sample, monitor contamination from extraction to PCR. Contamination detected in an extraction reagent blank but not in an amplification-negative control indicates that the reagents used for extraction are contaminated. Amplification-*negative* *controls*, which contain all PCR reagents and no DNA template, monitor contamination of the amplification. Contamination observed in an amplification-negative control but not in an extraction reagent blank indicates that the contamination occurred during the amplification step. Contamination observed in both an amplification reagent blank and an extraction-negative control indicates that amplification reagents are contaminated. A collection of DNA profiles of each member of a laboratory should be readily available for comparisons. Sources of laboratory contamination can be identified by comparing results with an analyst's DNA profile.

7.6 Reverse Transcriptase PCR for RNA-Based Assays

The pathway for the flow of genetic information is called the *central dogma*—a term coined by Francis Crick in 1956. According to the central dogma, parental DNA serves as the template for *DNA replication*. With RNA synthesis or *transcription*, the process is carried out using the DNA as a template. Conversely, RNA chains can be used as templates for the synthesis of a DNA strand of complementary sequence, in which the end product is referred to as *complementary DNA (cDNA)*. Protein synthesis, also known as *translation*, is directed by an RNA template (Figure 7.8).

The flow of genetic information from RNA to DNA is referred to as *reverse transcription*. It was discovered independently by David Baltimore and Howard Temin in 1970, and they shared the Nobel Prize for their work. Reverse transcription is carried out by a *reverse transcriptase* that forms the basis of reverse transcriptase PCR as described below.

Reverse transcriptase PCR (RT-PCR) is highly sensitive and can be used to detect very small quantities of mRNA. It can be utilized to measure levels of gene expression even when the RNA of interest is expressed at very low levels. Detecting mRNAs of tissue-specific genes can be utilized for bodily fluid identification in forensic investigations (Chapter 11). During an RT-PCR process, a single-stranded cDNA is synthesized from a template mRNA using reverse transcription. The cDNA is then amplified by PCR for detection and analysis.

7.6.1 Reverse Transcription

The synthesis of single-stranded cDNA from an mRNA template is catalyzed by reverse transcriptase. Reverse transcriptases share many features in structure and function with DNA polymerases. The catalytic function of cDNA synthesis requires a primer that anneals to a complementary mRNA template. The primer can be either RNA or DNA; however, DNA primers are more efficient than RNA primers. During the elongation of the primer, reverse transcriptase incorporates the corresponding deoxyribonucleotide triphosphate according to the rules of base pairing with the RNA template. The RNA template is then degraded by an intrinsic RNase H activity of reverse transcriptase during the reverse transcription reaction. The retroviral RNase H is a domain of the viral reverse transcriptase enzyme. It is a nonspecific endonuclease that cleaves RNA.

Several reverse transcriptases derived from retroviruses can be used to generate cDNA from an RNA template. The most common reverse transcriptases used for cDNA synthesis are



Figure 7.8 Pathway for the flow of genetic information. (© Richard C. Li.)

encoded by the *pol* gene from the avian myeloblastosis virus (AMV) and the Moloney strain of the murine leukemia virus (MMLV). These enzymes are genetically engineered reverse transcriptases but lack RNase H activity. Genetically engineered reverse transcriptases that are stable at higher temperatures (up to 60°C) are also produced. Increased thermal stability of reverse transcriptase allows the reverse transcription to be carried out at a higher than ambient temperature, which eliminates RNA secondary structures and improves the specificity of the reaction and the yields of the synthesis of full-length cDNA.

7.6.2 Oligodeoxynucleotide Priming

Oligodeoxynucleotide primers are an essential component for a reverse transcriptase reaction. Different priming strategies can be utilized to synthesize cDNA from a particular target mRNA or from all mRNA in a sample. *Gene-specific primers* are designed to hybridize to a particular mRNA sequence for the conversion of a specific gene sequence into cDNA. *Universal primers* can hybridize to any mRNA sequence in a sample to convert all mRNAs to cDNA. Two types of universal primers can be used: oligo (dT) and random hexamer primers. An *oligo (dT) primer* can hybridize to the 3′ termini poly (A) tails of eukaryotic mRNAs. Reverse transcriptases with oligo (dT) only synthesize cDNA from transcribed genes. *Random hexamer primers* are another type of universal primer. Random hexamers are nonspecific primers that can hybridize, at multiple sites, to any RNA sequence including non-mRNA templates such as ribosomal RNA.

7.6.3 Reverse Transcriptase PCR

During an RT-PCR process, a single-stranded cDNA is synthesized from a template mRNA using reverse transcription. The cDNA is then amplified by PCR with a pair of oligonucleotide primers corresponding to a specific sequence in the cDNA (Figure 7.9).

Two strategies of RT-PCR exist: a one-step and a two-step RT-PCR (Figure 7.10). One-step RT-PCR combines the reverse transcription reaction and PCR in a single tube. Only gene-specific



Figure 7.9 cDNA synthesis. The synthesis of a DNA strand transcribed from mRNA can be carried out using a primer and reverse transcriptase. A gene-specific primer that amplifies a specific target sequence is shown. (© Richard C. Li.)


Gene A
Gene-specific primers
RT-PCR
Gene B
RNA
Gene C
(a)
PCR amplicon
Gene A
Universal primers
RT
Gene-specific primers
PCR
Gene B
RNA
cDNA
Gene C
(b)
PCR amplicon

Figure 7.10 RT-PCR strategies. (a) One-step RT-PCR and (b) two-step RT-PCR. (© Richard C. Li.)

primers can be used for the reverse transcription reaction and PCR. RNAs from either total RNA or mRNA can be used. This approach simplifies the reaction setup as it is useful for processing large numbers of samples. The tubes are not opened between reverse transcription and PCR, thus minimizing the risk of pipetting errors and carryover contamination.

During a two-step PCR, the reverse transcription reaction and PCR are carried out in separate tubes. Following the reverse transcription reaction, the cDNA is transferred to a separate tube for the PCR amplification. Either oligo (dT) or random hexamer primers can be used for the reverse transcription reaction. Total RNA or polyadenylated RNA can be used for the reverse transcriptase reaction. This allows for the ability to convert all the messages in an RNA sample into cDNA. The two-step RT-PCR is useful for analyzing multiple mRNAs from a single sample.

Two types of PCR methods can be utilized for analyzing amplified products. The end-point PCR method measures the amount of amplified product synthesized during PCR at the end of the PCR amplification. The detection of the amplified product indicates the presence of the mRNA of interest. With the real-time PCR method, the amplified product is quantified during the exponential phase of PCR. The hot-start PCR strategy is typically used to increase sensitivity, specificity, and yield. Usually, the hot-start strategy is carried out at a high temperature, for example 94°C, prior to PCR cycling. Under this condition, *Taq* DNA polymerase is activated. Additionally, the RNA-cDNA hybrid is denatured, and reverse transcriptase is inactivated at 94°C. Multiplex RT-PCR assays have been developed that can detect multiple bodily fluid mRNAs from single or mixed stains (Chapter 11). The commonly used RT-PCR for forensic identification of bodily fluids is the two-step RT-PCR. The end-point PCR is usually utilized with the forward primers labeled with florescent dyes at the 5′ end. The amplified products are separated and detected in a standard capillary electrophoresis instrument.

Bibliography

Aboud, M., H.H. Oh, and B. McCord, Rapid direct PCR for forensic genotyping in under 25 min. *Electrophoresis*, 2013, **34**(11): 1539–1547.

Afonina, I.A., et al., Minor groove binder-conjugated DNA probes for quantitative DNA detection by hybridization-triggered fluorescence. *Biotechniques*, 2002, **32**(4): 940–944, 946–949.

Alaeddini, R., Forensic implications of PCR inhibition—A review. *Forensic Sci Int Genet*, 2012, **6**(3): 297–305.

Ballantyne, K.N., R.A. van Oorschot, and R.J. Mitchell, Comparison of two whole genome amplification methods for STR genotyping of LCN and degraded DNA samples. *Forensic Sci Int*, 2007, **166**(1): 35–41.

Ballantyne, K.N., R.A. van Oorschot, and R.J. Mitchell, Increased amplification success from forensic samples with locked nucleic acids. *Forensic Sci Int Genet*, 2011, **5**(4): 276–280.

Ballantyne, K.N., R.A. van Oorschot, and R.J. Mitchell, Locked nucleic acids in PCR primers increase sensitivity and performance. *Genomics*, 2008, **91**(3): 301–305.

Ballantyne, K.N., et al., Decreasing amplification bias associated with multiple displacement amplification and short tandem repeat genotyping. *Anal Biochem*, 2007, **368**(2): 222–229.

Bassam, B.J., et al., Nucleic acid sequence detection systems: Revolutionary automation for monitoring and reporting PCR products. *Aust Biotechnol*, 1996, **6**: 285–294.

Bekaert, B., et al., Automating a combined composite-consensus method to generate DNA profiles from low and high template mixture samples. *Forensic Sci Int Genet*, 2012, **6**(5): 588–593.

Birch, D.E., et al., Simplified hot start PCR. *Nature*, 1996, **318**: 2.

Bloch, W., A biochemical perspective of the polymerase chain reaction. *Biochemistry*, 1991, **30**(11): 2735–2747.

Bright, J.A., et al., The effect of cleaning agents on the ability to obtain DNA profiles using the Identifiler and PowerPlex® Y multiplex kits. *J Forensic Sci*, 2011, **56**(1): 181–185.

Brotherton, P., et al., Preferential access to genetic information from endogenous hominin ancient DNA and accurate quantitative SNP-typing via SPEX. *Nucleic Acids Res*, 2010, **38**(2): e7.

Budowle, B., A.J. Eisenberg, and A. van Daal, Validity of low copy number typing and applications to forensic science. *Croat Med J*, 2009, **50**(3): 207–217.

Chung, D.T., et al., A study on the effects of degradation and template concentration on the amplification efficiency of the STR Miniplex primer sets. *J Forensic Sci*, 2004, **49**(4): 733–740.

Date-Chong, M., et al., An examination of the utility of a nuclear DNA/mitochondrial DNA duplex qPCR assay to assess surface decontamination of hair. *Forensic Sci Int Genet*, 2013, **7**(3): 392–396.

Davis, C.P., et al., Multiplex short tandem repeat amplification of low template DNA samples with the addition of proofreading enzymes. *J Forensic Sci*, 2011, **56**(3): 726–732.

Deguilloux, M.F., et al., Analysis of ancient human DNA and primer contamination: One step backward one step forward. *Forensic Sci Int*, 2011, **210**(1–3): 102–109.

Dieffenbach, C.W., T.M. Lowe, and G.S. Dveksler, General concepts for PCR primer design. *PCR Methods Appl*, 1993, **3**(3): S30–S37.

Eckert, K.A. and T.A. Kunkel, DNA polymerase fidelity and the polymerase chain reaction. *PCR Methods Appl*, 1991, **1**(1): 17–24.

Eckert, K.A. and T.A. Kunkel, High fidelity DNA synthesis by the *Thermus aquaticus* DNA polymerase. *Nucleic Acids Res*, 1990, **18**(13): 3739–3744.

Edwards, M.C. and R.A. Gibbs, Multiplex PCR: Advantages, development, and applications. *PCR Methods Appl*, 1994, **3**(4): S65–S75.

Eilert, K.D. and D.R. Foran, Polymerase resistance to polymerase chain reaction inhibitors in bone*. *J Forensic Sci*, 2009, **54**(5): 1001–1007.

Endicott, P., et al., Genotyping human ancient mtDNA control and coding region polymorphisms with a multiplexed Single-Base-Extension assay: The singular maternal history of the Tyrolean Iceman. *BMC Genet*, 2009, **10**: 29.

Erlich, H.A., D. Gelfand, and J.J. Sninsky, Recent advances in the polymerase chain reaction. *Science*, 1991, **252**(5013): 1643–1651.

Estes, M.D., et al., Optimization of multiplexed PCR on an integrated microfluidic forensic platform for rapid DNA analysis. *Analyst*, 2012, **137**(23): 5510–5519.

Forster, L., J. Thomson, and S. Kutranov, Direct comparison of post-28-cycle PCR purification and modified capillary electrophoresis methods with the 34-cycle "low copy number" (LCN) method for analysis of trace forensic DNA samples. *Forensic Sci Int Genet*, 2008, **2**(4): 318–328.

Funes-Huacca, M.E., et al., A comparison of the effects of PCR inhibition in quantitative PCR and forensic STR analysis. *Electrophoresis*, 2011, **32**(9): 1084–1089.

Gasparini, P., et al., Amplification of DNA from epithelial cells in urine. *N Engl J Med*, 1989, **320**(12): 809.

Gavazaj, F.Q., et al., Optimization of DNA concentration to amplify short tandem repeats of human genomic DNA. *Bosn J Basic Med Sci*, 2012, **12**(4): 236–239.

Gefrides, L.A., et al., UV irradiation and autoclave treatment for elimination of contaminating DNA from laboratory consumables. *Forensic Sci Int Genet*, 2010, **4**(2): 89–94.

Ghasemi, A., et al., Design of a biological method for rapid detection of presence of PCR inhibitors in aged bone DNA. *Clin Lab*, 2012, **58**(7–8): 681–686.

Giardina, E., et al., Whole genome amplification and real-time PCR in forensic casework. *BMC Genom*, 2009, **10**: 159.

Giese, H., et al., Fast multiplexed polymerase chain reaction for conventional and microfluidic short tandem repeat analysis. *J Forensic Sci*, 2009, **54**(6): 1287–1296.

Gill, P., et al., An investigation of the rigor of interpretation rules for STRs derived from less than 100 pg of DNA. *Forensic Sci Int*, 2000, **112**(1): 17–40.

Grgicak, C.M., Z.M. Urban, and R.W. Cotton, Investigation of reproducibility and error associated with qPCR methods using Quantifiler® Duo DNA quantification kit. *J Forensic Sci*, 2010, **55**(5): 1331–1339.

Gyllensten, U.B. and H.A. Erlich, Generation of single-stranded DNA by the polymerase chain reaction and its application to direct sequencing of the HLA-DQA locus. *Proc Natl Acad Sci U S A*, 1988, **85**(20): 7652–7656.

Haas, C., E. Hanson, and J. Ballantyne, Capillary electrophoresis of a multiplex reverse transcription-polymerase chain reaction to target messenger RNA markers for body fluid identification. *Methods Mol Biol*, 2012, **830**: 169–183.

Haff, L., et al., A high-performance system for automation of the polymerase chain reaction. *Biotechniques*, 1991, **10**(1): 102–103, 106–112.

Hedman, J., et al., Improved forensic DNA analysis through the use of alternative DNA polymerases and statistical modeling of DNA profiles. *Biotechniques*, 2009, **47**(5): 951–958.

Henegariu, O., et al., Multiplex PCR: Critical parameters and step-by-step protocol. *Biotechniques*, 1997, **23**(3): 504–511.

Herrmann, D., et al., Microarray-based STR genotyping using RecA-mediated ligation. *Nucleic Acids Res*, 2010, **38**(17): e172.

Higuchi, R., et al., Kinetic PCR analysis: Real-time monitoring of DNA amplification reactions. *Biotechnology* (N Y), 1993, **11**(9): 1026–1030.

Higuchi, R., et al., Simultaneous amplification and detection of specific DNA sequences. *Biotechnology* (N Y), 1992, **10**(4): 413–417.

Hochmeister, M.N., et al., Confirmation of the identity of human skeletal remains using multiplex PCR amplification and typing kits. *J Forensic Sci*, 1995, **40**(4): 701–705.

Holland, P.M., et al., Detection of specific polymerase chain reaction product by utilizing the 5′–3′ exonuclease activity of *Thermus aquaticus* DNA polymerase. *Proc Natl Acad Sci U S A*, 1991, **88**(16): 7276–7280.

Hughes-Stamm, S.R., K.J. Ashton, and A. van Daal, Assessment of DNA degradation and the genotyping success of highly degraded samples. *Int J Legal Med*, 2011, **125**(3): 341–348.

Irwin, J.A., et al., Characterization of a modified amplification approach for improved STR recovery from severely degraded skeletal elements. *Forensic Sci Int Genet*, 2012, **6**(5): 578–587.

Isacsson, J., et al., Rapid and specific detection of PCR products using light-up probes. *Mol Cell Probes*, 2000, **14**(5): 321–328.

Ju, J., et al., Fluorescence energy transfer dye-labeled primers for DNA sequencing and analysis. *Proc Natl Acad Sci U S A*, 1995, **92**(10): 4347–4351.

Kaminiwa, J., et al., Vanadium accelerates polymerase chain reaction and expands the applicability of forensic DNA testing. *J Forensic Leg Med*, 2013, **20**(4): 326–333.

Kavlick, M.F., et al., Quantification of human mitochondrial DNA using synthesized DNA standards. *J Forensic Sci*, 2011, **56**(6): 1457–1463.

Kermekchiev, M.B., et al., Mutants of *Taq* DNA polymerase resistant to PCR inhibitors allow DNA amplification from whole blood and crude soil samples. *Nucleic Acids Res*, 2009, **37**(5): e40.

Kimpton, C., et al., Evaluation of an automated DNA profiling system employing multiplex amplification of four tetrameric STR loci. *Int J Legal Med*, 1994, **106**(6): 302–311.

Kitayama, T., et al., Estimation of the detection rate in STR analysis by determining the DNA degradation ratio using quantitative PCR. *Leg Med (Tokyo)*, 2013, **15**(1): 1–6.

Koon, H.E., et al., Diagnosing post-mortem treatments which inhibit DNA amplification from US MIAs buried at the Punchbowl. *Forensic Sci Int*, 2008, **178**(2–3): 171–177.

Koppelkamm, A., et al., Validation of adequate endogenous reference genes for the normalization of qPCR gene expression data in human post mortem tissue. *Int J Legal Med*, 2010, **124**(5): 371–380.

Krawczak, M., et al., Polymerase chain reaction: Replication errors and reliability of gene diagnosis. *Nucleic Acids Res*, 1989, **17**(6): 2197–2201.

Kunkel, T.A., DNA replication fidelity. *J Biol Chem*, 1992, **267**(26): 18251–18254.

Kutyavin, I.V., et al., 3′-minor groove binder-DNA probes increase sequence specificity at PCR extension temperatures. *Nucleic Acids Res*, 2000, **28**(2): 655–661.

Kwok, S. and R. Higuchi, Avoiding false positives with PCR. *Nature*, 1989, **339**(6221): 237–238.

Laurin, N. and C. Fregeau, Optimization and validation of a fast amplification protocol for AmpFlSTR® Profiler Plus® for rapid forensic human identification. *Forensic Sci Int Genet*, 2012, **6**(1): 47–57.

Lee, J.C., et al., Evaluating the performance of whole genome amplification for use in low template DNA typing. *Med Sci Law*, 2012, **52**(4): 223–228.

Maciejewska, A., J. Jakubowska, and R. Pawlowski, Whole genome amplification of degraded and nondegraded DNA for forensic purposes. *Int J Legal Med*, 2013, **127**(2): 309–319.

Markoulatos, P., N. Siafakas, and M. Moncany, Multiplex polymerase chain reaction: A practical approach. *J Clin Lab Anal*, 2002, **16**(1): 47–51.

Marshall, P.L., et al., Pressure cycling technology (PCT) reduces effects of inhibitors of the PCR. *Int J Legal Med*, 2013, **127**(2): 321–333.

McCloskey, M.L., et al., Encoding PCR products with batch-stamps and barcodes. *Biochem Genet*, 2007, **45**(11–12): 761–767.

Mitsuhashi, M., Technical report: Part 2. Basic requirements for designing optimal PCR primers. *J Clin Lab Anal*, 1996, **10**(5): 285–293.

Moretti, T., B. Koons, and B. Budowle, Enhancement of PCR amplification yield and specificity using AmpliTaq Gold DNA polymerase. *Biotechniques*, 1998, **25**(4): 716–722.

Morling, N., PCR in forensic genetics. *Biochem Soc Trans*, 2009, **37**(Pt 2): 438–440.

Myers, B.A., J.L. King, and B. Budowle, Evaluation and comparative analysis of direct amplification of STRs using PowerPlex® 18D and Identifiler® Direct systems. *Forensic Sci Int Genet*, 2012, **6**(5): 640–645.

Nazarenko, I.A., S.K. Bhatnagar, and R.J. Hohman, A closed tube format for amplification and detection of DNA based on energy transfer. *Nucleic Acids Res*, 1997, **25**(12): 2516–2521.

Nguyen, Q., et al., STR melting curve analysis as a genetic screening tool for crime scene samples. *J Forensic Sci*, 2012, **57**(4): 887–899.

Nicklas, J.A., T. Noreault-Conti, and E. Buel, Development of a fast, simple profiling method for sample screening using high resolution melting (HRM) of STRs. *J Forensic Sci*, 2012, **57**(2): 478–488.

Nogami, H., et al., Rapid and simple sex determination method from dental pulp by loop-mediated isothermal amplification. *Forensic Sci Int Genet*, 2008, **2**(4): 349–353.

Opel, K.L., D. Chung, and B.R. McCord, A study of PCR inhibition mechanisms using real time PCR. *J Forensic Sci*, 2010, **55**(1): 25–33.

Park, S.J., et al., Direct STR amplification from whole blood and blood- or saliva-spotted FTA without DNA purification. *J Forensic Sci*, 2008, **53**(2): 335–341.

Reynolds, R., G. Sensabaugh, and E. Blake, Analysis of genetic markers in forensic DNA samples using the polymerase chain reaction. *Anal Chem*, 1991, **63**(1): 2–15.

Roeder, A.D., et al., Maximizing DNA profiling success from sub-optimal quantities of DNA: A staged approach. *Forensic Sci Int Genet*, 2009, **3**(2): 128–137.

Rothe, J., N.E. Watkins Jr., and M. Nagy, New prediction model for probe specificity in an allele-specific extension reaction for haplotype-specific extraction (HSE) of Y chromosome mixtures. *PLoS One*, 2012, **7**(9): e45955.

Saiki, R.K., et al., Enzymatic amplification of beta-globin genomic sequences and restriction site analysis for diagnosis of sickle cell anemia. *Science*, 1985, **230**(4732): 1350–1354.

Saiki, R.K., et al., Primer-directed enzymatic amplification of DNA with a thermostable DNA polymerase. *Science*, 1988, **239**(4839): 487–491.

Sanchez, J.J., et al., Multiplex PCR and minisequencing of SNPs—A model with 35 Y chromosome SNPs. *Forensic Sci Int*, 2003, **137**(1): 74–84.

Schoske, R., et al., Multiplex PCR design strategy used for the simultaneous amplification of 10 Y chromosome short tandem repeat (STR) loci. *Anal Bioanal Chem*, 2003, **375**(3): 333–343.

Seo, S.B., et al., Effects of humic acid on DNA quantification with Quantifiler® Human DNA Quantification kit and short tandem repeat amplification efficiency. *Int J Legal Med*, 2012, **126**(6): 961–968.

Shuber, A.P., V.J. Grondin, and K.W. Klinger, A simplified procedure for developing multiplex PCRs. *Genome Res*, 1995, **5**(5): 488–493.

Smith, P.J. and J. Ballantyne, Simplified low-copy-number DNA analysis by post-PCR purification. *J Forensic Sci*, 2007, **52**(4): 820–829.

Solinas, A., N. Thelwell, and T. Brown, Intramolecular TaqMan probes for genetic analysis. *Chem Commun (Camb)*, 2002, (19): 2272–2273.

Steadman, S.A., et al., Recovery and STR amplification of DNA from RFLP membranes. *J Forensic Sci*, 2008, **53**(2): 349–358.

Sutlovic, D., et al., Interaction of humic acids with human DNA: Proposed mechanisms and kinetics. *Electrophoresis*, 2008, **29**(7): 1467–1472.

Swaran, Y.C. and L. Welch, A comparison between direct PCR and extraction to generate DNA profiles from samples retrieved from various substrates. *Forensic Sci Int Genet*, 2012, **6**(3): 407–412.

Tindall, K.R. and T.A. Kunkel, Fidelity of DNA synthesis by the *Thermus aquaticus* DNA polymerase. *Biochemistry*, 1988, **27**(16): 6008–6013.

Tokutomi, T., et al., Real-time PCR method for identification of Asian populations in forensic casework. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S106–S108.

Turrina, S., et al., STR typing of archival Bouin's fluid-fixed paraffin-embedded tissue using new sensitive redesigned primers for three STR loci (CSF1P0, D8S1179 and D13S317). *J Forensic Leg Med*, 2008, **15**(1): 27–31.

Verheij, S., J. Harteveld, and T. Sijen, A protocol for direct and rapid multiplex PCR amplification on forensically relevant samples. *Forensic Sci Int Genet*, 2012, **6**(2): 167–175.

Wallin, J.M., et al., Constructing universal multiplex PCR systems for comparative genotyping. *J Forensic Sci*, 2002, **47**(1): 52–65.

Walsh, P.S., H.A. Erlich, and R. Higuchi, Preferential PCR amplification of alleles: Mechanisms and solutions. *PCR Methods Appl*, 1992, **1**(4): 241–250.

Wang, J. and B. McCord, The application of magnetic bead hybridization for the recovery and STR amplification of degraded and inhibited forensic DNA. *Electrophoresis*, 2011, **32**(13): 1631–1638.

Weiler, N.E., A.S. Matai, and T. Sijen, Extended PCR conditions to reduce drop-out frequencies in low template STR typing including unequal mixtures. *Forensic Sci Int Genet*, 2012, **6**(1): 102–107.

Westwood, S.A. and D.J. Werrett, An evaluation of the polymerase chain reaction method for forensic applications. *Forensic Sci Int*, 1990, **45**(3): 201–215.

Weusten, J. and J. Herbergs, A stochastic model of the processes in PCR based amplification of STR DNA in forensic applications. *Forensic Sci Int Genet*, 2012, **6**(1): 17–25.

Whitcombe, D., et al., A homogeneous fluorescence assay for PCR amplicons: Its application to real-time, single-tube genotyping. *Clin Chem*, 1998, **44**(5): 918–923.

Wong, H.Y., E.S. Lim, and W.F. Tan-Siew, Amplification volume reduction on DNA database samples using FTA Classic Cards. *Forensic Sci Int Genet*, 2012, **6**(2): 176–179.

Yu, P.H. and M.M. Wallace, Effect of 1,2-indanedione on PCR-STR typing of fingerprints deposited on thermal and carbonless paper. *Forensic Sci Int*, 2007, **168**(2–3): 112–118.

8

DNA Electrophoresis

It is necessary to separate various sizes of DNA fragments so that the DNA fragment in question can be identified and analyzed. This can be achieved by electrophoresis, a process in which fragments are separated based on the migration of charged macromolecules in an electric field.

8.1 Basic Principles

DNA is a negatively charged molecule in an aqueous environment, with the phosphate groups of DNA nucleotides carrying negative charges. DNA molecules migrate from the negative electrode (cathode) toward the positive electrode (anode) in an electric field during electrophoresis. The *electrical potential*, a measure of the work required to move a charged molecule in an electric field, is the force responsible for moving the charged macromolecules during electrophoresis.

The *electrophoretic mobility* of macromolecules is primarily determined by their *charge-to-mass ratios* and their shapes. However, because the phosphate group of every DNA nucleotide carries a negative charge, the charge-to-mass ratio of DNA molecules is almost the same even if the length of the DNA fragment varies. Additionally, forensic DNA testing usually analyzes linear DNA molecules such as double-stranded linear DNA for variable number tandem repeat (VNTR) analysis (Chapter 19) and single-stranded DNA for short tandem repeat (STR) analysis (Chapter 20). The shapes of linear DNA molecules are similar. Therefore, the electrophoretic separation of different-sized DNA fragments, through a series of pores of the supporting matrix in which the fragments travel, is based more on their sizes than their shapes.

It is obviously easier for smaller molecules to migrate through the pores of a supporting matrix than larger molecules; this is why smaller molecules migrate faster through the matrix. Hence, the electrophoretic mobility increases as the size of the DNA molecule decreases. Conversely, larger DNA molecules migrate much more slowly because they experience more friction and collisions as they travel through the net of pores in a matrix. Therefore, the separation of DNA molecules with different sizes can be accomplished. Figure 8.1 depicts the models for DNA electrophoresis.

8.2 Supporting Matrices

Although the actual separation occurs in an aqueous phase, most variants of electrophoresis use a physical support material also called a *matrix*. As discussed in Section 8.1, the matrix can be used as a molecular sieve for the separation of DNA molecules, and it also reduces diffusion and convection during electrophoresis. Agarose and polyacrylamide are commonly used electrophoresis matrices because of their good reproducibility, reliability, and versatility.



Figure 8.1 Schematic illustrations showing some of the nucleic acid separation mechanisms. (a) Ogston sieving model for the separation of DNA fragments through electrophoresis. Based on this model, the matrix used for gel electrophoresis consists of randomly distributed pores. DNA molecules are considered to behave as globular objects. During the migration, smaller DNA molecules migrate faster than their larger counterparts through the matrix. However, this model does not apply to DNA molecules with a radius much larger than the pore size of the matrix. (b) A reptation model presents an alternative mechanism of gel electrophoretic separation of DNA molecules. Based on this model, DNA molecules are flexible and can migrate through the pores of the gel matrix through a reptation process that is driven by an applied electric field. This model can also apply to capillary electrophoresis separation of DNA molecules in entangled polymer solutions. +, anode; −, cathode; arrow, direction of migration. (© Richard C. Li.)

8.2.1 Agarose

Agarose is a linear polymer composed of alternating residues of D- and L-galactose (Figure 8.2). A gelatinized agarose forms a three-dimensional sieve with pores from 50 to 200 nm in diameter (Figure 8.3). DNA fragments ranging from 50 to 20,000 base pairs in size are best resolved in agarose gels.



Figure 8.2 Chemical components of agarose, a linear polysaccharide composed of alternating units of D- and L-galactose. Often, the L-galactose residue has an anhydro bridge between the 3 and 6 positions and is called 3,6-anhydro-L-galactose.



Figure 8.3 Agarose chains. Gelatinized agarose consists of a three-dimensional network in which chains of agarose form helical fibers that aggregate into supercoiled structures. (© Richard C. Li.)

The electrophoretic mobility of double-stranded DNA through agarose gel matrices is inversely proportional to the $\log_{10}$ of the size of DNA fragments ranging from 50 to 20,000 base pairs. The electrophoretic mobility of a linear DNA fragment is also inversely proportional to the concentration of agarose in the gel. A low concentration of agarose in a gel forms larger pores, allowing the separation of larger DNA fragments.

8.2.2 Polyacrylamide

A polyacrylamide gel matrix is very effective for the separation of smaller fragments of DNA (5–500 base pairs). Additionally, a single nucleotide difference in the length of a DNA fragment can be resolved with this type of gel. Polyacrylamide produces much smaller pore sizes than agarose gels and thus has a much higher resolving power than agarose gels for low-molecular-weight DNA molecules. A polyacrylamide gel matrix is formed by polymerization and cross-linking reactions.

8.2.2.1 Polymerization Reaction

Long linear chains of polyacrylamide are polymerized from acrylamide monomers (Figure 8.4). This polymerization reaction is initiated in the presence of free radicals that are generated from the reduction of ammonium persulfate (APS) by *N*,*N*,*N*′,*N*′-tetramethylethylene diamine (TEMED). See Figure 8.5.

8.2.2.2 Cross-Linking Reaction

As shown in Figure 8.5, three-dimensionally cross-linked polyacrylamide chains can be formed with the use of cross-linking agents, such as *N*,*N*′-methylenebisacrylamide (BIS; Figure 8.4).



Figure 8.4 Chemical structures of (a) acrylamide, (b) *N*,*N*′-methylenebisacrylamide (BIS), and (c) polydimethylacrylamide (a linear polymer for capillary electrophoresis).



Figure 8.5 Formation of polyacrylamide gel. Polymerization is followed by cross-linking in which the pore size of the gel is determined by its degree of polymerization and cross-linking. (© Richard C. Li.)

The porosity of the resulting gel is determined by the lengths of these chains and the degree of cross-linking between them. Therefore, the sizes of the pores that are formed can be adjusted by altering the concentrations of the acrylamide monomer and the cross-linking reagent.

Polyacrylamide can also be used in a capillary electrophoresis matrix. It is very difficult to insert a cross-linked polyacrylamide matrix into a capillary. Therefore, a solution of a linear polymer (non-cross-linked) of polydimethylacrylamide (Figure 8.4) is used as a matrix for capillary electrophoresis. For instance, POP-4 (4% un-cross-linked polydimethylacrylamide polymer) is used for fragment analysis, such as forensic STR analysis (Chapter 18), in which fluorescently labeled DNA amplicons are separated using electrophoresis and are identified based on their sizes by comparing them with a size standard. POP-6 (6% un-cross-linked polydimethylacrylamide polymer) is used for sequencing, such as mitochondrial DNA (mtDNA) sequencing (Chapter 21). These un-cross-linked polymers are commercially available (Applied Biosystems).

8.2.2.3 Denaturing Polyacrylamide Electrophoresis

Polyacrylamide-based electrophoresis can be carried out with both double- and single-stranded DNA. Electrophoresis that is performed under the conditions of single-stranded DNA is called *denaturing electrophoresis*. Denatured DNA migrates through the gel as linear molecules at a rate independent of the base composition and sequence. With short single-stranded fragments, molecules differing in size by a single nucleotide can be separated. This extraordinary sensitivity to size is extremely useful for the separation of small DNA fragments that are used for DNA sequencing and STR analysis in forensic applications. The denaturing condition can be best achieved by adding chemicals such as urea or formamide to the matrix or by increasing the temperature or pH during electrophoresis.

8.3 Apparatus and Forensic Applications

Agarose electrophoresis is carried out in a slab gel. Agarose gel can be prepared in a variety of shapes and sizes and can be run in different configurations. The most common gel for forensic use is the horizontal slab. Polyacrylamide can be used either in a slab gel or in a capillary electrophoretic apparatus.

8.3.1 Slab Gel Electrophoresis

8.3.1.1 Agarose Gel Electrophoresis

One forensic application of agarose gel electrophoresis is restriction fragment length polymorphism (RFLP) analysis of VNTR loci (see Chapter 19). An agarose gel is used to separate the DNA fragments by size ranging from 500 to 20,000 base pairs of commonly used VNTR loci for forensic testing. This type of electrophoresis is done under nondenatured conditions (double-stranded DNA).

Figure 8.6 shows an example of the apparatus used for gel electrophoresis of DNA. A slab (3–4 mm) of agarose gel is prepared by allowing liquid agarose to gelatinize in a cast. The gel is submerged in a buffer tank filled with an electrophoretic buffer with proper ionic strength, which is necessary to achieve efficient electrical conductance. The gel contains small wells for loading samples. The DNA samples are mixed with a gel loading buffer prior to loading them into the gel. The gel loading buffer contains dyes that add color to the sample to facilitate the process of loading. Dyes such as bromophenol blue and xylene cyanol FF migrate toward the anode during electrophoresis. In most forensic applications, these dyes migrate faster than DNA fragments. The dyes are visible and can thus be used to track the progression of electrophoresis. The electrophoresis can be stopped as the dye front reaches the bottom of the gel (anode side).



Figure 8.6 Horizontal agarose slab gel apparatus. The gel can be prepared by heating an agarose suspension to dissolve it. The agarose solution can then be poured into a gel cast and allowed to cool until gelatinized. An electrophoresis buffer is poured over the gel to submerge it. The samples, usually mixed with loading buffer containing dye to allow visualization, are loaded into the wells of the submerged gel using a pipet. The electrodes are indicated. (© Richard C. Li.)

The samples are loaded into the sample wells situated proximal to the cathode. An electric field is applied and the negatively charged DNA molecules migrate through the agarose toward the anode. Slab gel electrophoresis is capable of running multiple samples simultaneously. The sample is made visible by using a fluorescent intercalating reagent that can make DNA fluoresce under ultraviolet (UV) light (Chapter 9), either using the fluorescent intercalating reagent incorporated into the gel or staining the gel after electrophoresis. The separated DNA samples appear as bands and the sizes of the DNA fragments can be estimated by comparing them with the sizes of standards run concurrently.

8.3.1.2 Polyacrylamide Gel Electrophoresis

The forensic application of this apparatus is the separation of STR fragments and DNA sequencing reaction products of mtDNA. The sizes of DNA fragments that can be separated range from 100 to 500 base pairs—much smaller than what can be separated efficiently with agarose gels. Single-nucleotide resolution to distinguish similarly sized fragments can be achieved with this technique under denatured conditions with only single-stranded DNA. Polyacrylamide thin slab gels (0.75–1.5 mm) are usually used. Samples are loaded into wells flanked by two pieces of glass. Therefore, polyacrylamide gels are usually run in a vertical configuration (Figure 8.7). The detection of DNA bands in polyacrylamide gels will be described in Chapter 9. The sizes of DNA fragments can be calculated by including an internal size standard. As with agarose gel, polyacrylamide gel electrophoresis is capable of running multiple samples simultaneously and high throughput (a measurement of the rate that a sample is processed by a given analysis) can be achieved. However, caution should be taken to ensure that cross-contamination does not occur from the spilling of samples from adjacent wells. Additionally, polyacrylamide gels are more difficult to prepare than agarose gels.

8.3.2 Capillary Electrophoresis

Capillary electrophoresis (Figures 8.8 through 8.11) is a newer method than the slab gel method, and can be utilized to separate charged macromolecules, such as DNA, RNA, polysaccharides, and proteins.

One essential component of the capillary electrophoresis instrument is the capillary, a thin hollow tube made of fused silica (which typically has a diameter between 50 and 100 μm and a length between 10 and 50 cm). The capillary contains a translucent detection window for the instrument to detect signals from the labeled DNA fragments during electrophoresis.

Linear polydimethylacrylamide is used as the matrix. Capillary electrophoresis is conducted under denatured conditions for forensic applications such as STR analysis and mtDNA sequencing analysis. The denatured condition is achieved by including urea in the electrophoresis matrix and formamide during sample preparation. The injection of samples into the capillary is performed by an autosampler using an *electrokinetic* mechanism (an injection based on the charge of molecules). Only small quantities of sample are required for each injection, and any remaining sample can be saved in case an analysis needs to be repeated.

During electrophoresis, the capillary is connected to buffer reservoirs that are connected to electrodes. The efficient heat dissipation property of thin capillaries allows the separation to be performed at higher voltages, as the electric field (typically 200–300 V/cm) is much higher than that of a slab gel platform. Thus, the separation in capillary electrophoresis is rapid. During electrophoresis, DNA fragments migrate through the capillaries toward the anode. Similar to gel electrophoresis, DNA fragments are separated according to their sizes, with the shorter fragments moving faster than the longer fragments. During capillary electrophoresis, linear polymers in the solution can act as obstacles to the migrating DNA fragments. Thus, electrophoretic separation models (Figure 8.1) developed for gels are applicable for capillary electrophoresis. Currently, capillary electrophoresis can separate DNA fragments of up to 1000 nucleotides with single-nucleotide resolution.



Figure 8.7 Vertical slab polyacrylamide gel. (a) Front and side view of vertical slab polyacrylamide gel apparatus. (b) Automated gel electrophoresis instrument, ABI PRISM 377® Genetic Analyzer, which was used in forensic laboratories but is now discontinued. (© Richard C. Li.)

Capillary electrophoresis instruments are equipped with detection systems utilizing laser excitation sources that excite the fluorescently labeled DNA fragments. They also include fluorescence detectors that record the signals emitted from the labeled DNA fragments (Chapter 9). In capillary electrophoresis, samples can only be analyzed sequentially so the throughput is much more limited than with slab gels. This disadvantage can be overcome by utilizing capillary array systems that can run up to 16 capillaries at one time (Figure 8.10).

8.3.3 Microfluidic Devices

Forensic DNA analysis includes the extraction of DNA from a sample, DNA quantification, polymerase chain reaction (PCR) amplification, capillary electrophoresis, data collection, and genotyping. Various microfluidic devices have been developed for forensic DNA analysis. Microfluidic devices control the movement of samples and reagents in a small, geometrically constrained environment and carry out biochemical reactions and analysis. These devices are made using microfabrication technology. This technology fabricates miniature structures historically used for integrated circuit fabrication in semiconductor manufacturing. The microfluidic



Figure 8.8 Essential components of a capillary electrophoresis system. The system includes a capillary, buffer reservoirs, two electrodes, a laser excitation source, a fluorescence detector, and an autosampler that holds the sample. Sample injection, electrophoresis, and data collection are automated and controlled by a computer. (© Richard C. Li.)



Figure 8.9 A single-capillary electrophoresis instrument, ABI PRISM 310® Genetic Analyzer. This was used in forensic laboratories but is now discontinued. (© Richard C. Li.)

devices can be classified as modular and integrated devices. Overall, the microfluidic device has many advantages compared with conventional techniques. The reaction volume required in microfluidic devices is usually in the nanoliter range, which decreases reagent and sample consumption. Additionally, due to the high surface area-to-volume ratio of the system, the efficiency of the system is greatly improved. Lastly, it can be automated, which makes the device a potential new platform for forensic DNA analysis.



Figure 8.10 Photo of a multicapillary electrophoresis instrument. ABI PRISM 3500® Genetic Analyzer. (© Richard C. Li.)



Figure 8.11 Components of the ABI PRISM 3500® Genetic Analyzer. A capillary array (left), electrophoretic buffer chambers (middle), and an autosampler (right). (© Richard C. Li.)

8.3.3.1 Modular Microfluidic Devices

The modular devices are separate devices for DNA extraction, quantitation, amplification, electrophoresis, and so on. Each processing step is carried out on different devices. The modular design is flexible, allowing laboratories to choose the best device suited to the procedure for each step. For example, an electrophoresis microfluidic device has been developed (Figure 8.12). The electrophoretic assay is carried out on a modular microfluidic chip format using the same basic principle of capillary electrophoresis. The single-use chip contains wells for samples, a sieving polymer matrix for electrophoresis, and size standards. The wells are connected through microchannels. When the interconnected wells and channels are filled, the chip becomes an integrated electrical circuit. Each well is then connected to an electrode with an independent power supply. DNA molecules, carrying negative charges, are



Figure 8.12 A modular instrument for gel electrophoresis. Left: Agilent 2100 Bioanalyzers contain 16-pin electrodes that fit into the wells of a chip. Right: The chip can accommodate sample wells, gel wells, and a well for a size standard. (© Richard C. Li.)



Figure 8.13 Integrated instruments for rapid DNA analysis. Cartridges developed by IntegeneX (left) and Zygem (right). (© Richard C. Li.)

electrophoretically separated based on their size. Smaller molecular weight fragments migrate faster than larger fragments. The polymer matrix contains fluorescent dye molecules that intercalate with DNA in a sample, which can be detected by laser-induced fluorescence. The duration of electrophoresis is approximately 30 min. The sensitivity is approximately 0.1 ng/μL; thus, sample consumption is small. The device provides the sizing and quantitation information of the nucleic acid fragment. In addition to DNA, the device can also be used for the analysis of RNA and protein. In the forensic laboratory, it has been used for the quantitation of amplified mtDNA product to monitor successful amplification and to normalize the quantities of DNA template for cycle sequencing.

8.3.3.2 Integrated Microfluidic Devices

It is possible to integrate several different modular devices into a single device (Figure 8.13). These devices are also known as “micro-total analysis” systems. An integrated system is a fully automated process. It also reduces the risk of contamination from laboratory sources. Full integration of all the constituent steps required for forensic STR DNA analysis has been achieved by a *rapid DNA* instrument. This instrument integrates various microfluidic devices including DNA extraction, PCR amplification, electrophoresis, detection, and genotyping steps into a single process on a cartridge. The cartridge, made from a variety of materials such as polycarbonate, incorporates pumps and valves controlling fluidic movement for the delivery of samples and prefilled reagents to the chambers for processing. DNA extraction usually utilizes silica-coated magnetic particles that can be collected by a magnet for DNA extraction. Microquantitative PCR utilizes the Taqman real-time quantitative PCR technique. During amplification, multiplex PCR is accomplished using commercial STR kits. Additionally, the cartridge also integrates a microcapillary electrophoresis chip for the separation of amplified products. The fluorescently labeled DNA fragments are detected based on laser-induced fluorescence. Data analysis and genotyping are then carried out to produce a DNA profile, which is compatible with the CODIS DNA database (Chapter 24). Rapid DNA instruments are fully automated platforms that are designed to process a single-source sample such as a buccal swab to generate a DNA profile and database search in less than 2 h. The goal is for these instruments to be deployed in field tests at the scene or at the booking stations operated by trained law enforcement agents.

8.4 Estimation of DNA Size

8.4.1 Relative Mobility

The *relative mobility* (R_f) of a DNA molecule during electrophoresis can be calculated as the distance of band migration divided by the distance of tracking dye migration. The DNA



Figure 8.14 Measurement of the electromobility of DNA. Questioned DNA samples are analyzed concurrently with a set of standard DNA fragments of known size. The distances of DNA migration can thus be measured. The samples are usually mixed with a gel loading buffer prior to loading samples to the gel. The buffer contains dyes that add color to the sample to facilitate the process of loading. Dyes such as bromophenol blue and xylene cyanol FF migrate toward the positive electrode during electrophoresis. They can be used for tracking purposes as well. (© Richard C. Li.)

band migration is the distance from the sample origin to the center of the band. The tracking dye migration distance extends from the sample origin to the center of the dye band (Figure 8.14). To estimate the size of the DNA, standards containing DNA of known size and questioned samples are run on the same gel at the same time. The standards can be used to estimate the size of an unknown DNA molecule. A plot of $\log_{10}$ base pair of the standards versus R_f for a given gel can be constructed. A linear relationship, over a size range, between $\log_{10}$ base pair of the DNA molecule and the R_f can be observed. The R_f of the test sample is interpolated on the plot from which the size of an unknown DNA molecule can be determined (Figure 8.15).



Figure 8.15 Estimation of the size of a DNA fragment. A plot of size standards versus relative migration during electrophoresis is shown. The size of the questioned DNA fragment can be estimated using this plot. (© Richard C. Li.)

8.4.2 Local Southern Method

The size of a DNA fragment is determined by an internal size standard that is a set of synthetic fragments with known molecular weight. The standard is labeled with a different colored dye so that it can be spectrally distinguished from DNA fragments of an unknown size (Figure 8.16). The sample including the internal size standard is then mixed in with DNA samples and is analyzed by electrophoresis. To determine the sizes of DNA fragments, a standard curve using the internal size standards must be established based on the reciprocal relationship between the electrophoretic mobility and the sizes of DNA fragments. However, this relationship is not exactly linear; instead, it appears to be sigmoidal (Figure 8.17). Therefore, the *Local Southern method*, described by Sir Edwin Southern, is used to generate standard curves for determining the sizes of DNA fragments. The equation is as follows:

$$L = \left[\frac{C}{M - M_0}\right] + L_0$$



Figure 8.16 Electropherogram of a synthetic molecular weight size standard, GeneScan™ 500 size standard (Applied Biosystems). RFU, relative fluorescence units. (© Richard C. Li.)



Figure 8.17 Estimation of unknown DNA fragment sizes using the Local Southern method. The migration of ssDNA fragments (20–1200 base pairs) is not linear over the entire fragment size range and is somewhat sigmoidal. To determine the size of a DNA fragment in question, two curves are generated. The first curve is generated using three standard points: two points (a and b) that are smaller and one point (c) that is larger than the questioned fragment. As a result, a fragment size (L_1) is determined. The second curve is then generated using an additional three standard points: one point (b) that is smaller and two points (c and d) that are larger than the questioned fragment. Thus, a fragment size, L_2, is determined. The two values (L_1 and L_2) are averaged to determine the size (L) of the questioned fragment. (Adapted from Southern, E.M.,*Anal Biochem*, 100, 319–323, 1979.)

In the equation, L is the size of the unknown fragment; M is the mobility of the fragment; and C, M_0, and L_0 are constants that are obtained from the fragments of known size. To determine the size of an unknown fragment, two curves are generated based on the equation. Each curve utilizes three data points. The first curve utilizes two size standards that are smaller and one size standard that is greater than that of the unknown fragment. As a result, size L_1 is obtained. The second curve utilizes a size standard that is smaller and two size standards that are greater than that of the unknown fragment. Thus, size L_2 is obtained. Finally, the average of L_1 and L_2 is defined as the size of the unknown fragment. In this method, only the size standards that are in the proximity of the unknown fragment are analyzed. However, the accuracy of the standard curve relies on the proper separation of the standards during electrophoresis.

Bibliography

Aboud, M.J., M. Gassmann, and B.R. McCord, The development of mini pentameric STR loci for rapid analysis of forensic DNA samples on a microfluidic system. *Electrophoresis*, 2010, **31**(15): 2672–2679.

Biega, L.A. and B.W. Duceman, Substitution of H_2O for formamide in the sample preparation protocol for STR analysis using the capillary electrophoresis system: The effects on precision, resolution, and capillary life. *J Forensic Sci*, 1999, **44**: 3.

Bienvenue, J.M., et al., An integrated microfluidic device for DNA purification and PCR amplification of STR fragments. *Forensic Sci Int Genet*, 2010, **4**(3): 178–186.

Buel, E., M.B. Schwartz, and M.J. LaFountain, Capillary electrophoresis STR analysis: Comparison to gel-based systems. *J Forensic Sci*, 1998, **43**(1): 164–170.

Butler, J.M., C.M. Ruitberg, and P.M. Vallone, Capillary electrophoresis as a tool for optimization of multiplex PCR reactions. *Fresenius J Anal Chem*, 2001, **369**(3–4): 200–205.

Butler, J.M., et al., Rapid analysis of the short tandem repeat HUMTH01 by capillary electrophoresis. *Biotechniques*, 1994, **17**(6): 1062–1064, 1066, 1068, passim.

Butler, J.M., et al., Forensic DNA typing by capillary electrophoresis using the ABI Prism 310 and 3100 genetic analyzers for STR analysis. *Electrophoresis*, 2004, **25**(10–11): 1397–1412.

Chen, Y., et al., Sample stacking capillary electrophoretic microdevice for highly sensitive mini Y short tandem repeat genotyping. *Electrophoresis*, 2010, **31**(17): 2974–2980.

Choi, J.Y. and T.S. Seo, An integrated microdevice for high-performance short tandem repeat genotyping. *Biotechnol J*, 2009, **4**(11): 1530–1541.

Fernandez, C. and A. Alonso, Microchip capillary electrophoresis protocol to evaluate quality and quantity of mtDNA amplified fragments for DNA sequencing in forensic genetics. *Methods Mol Biol*, 2012, **830**: 367–379.

Frazier, R.R., et al., Validation of the applied biosystems Prism 377 automated sequencer for the forensic short tandem repeat analysis. *Electrophoresis*, 1996, **17**(10): 1550–1552.

French, D.J., et al., Interrogation of short tandem repeats using fluorescent probes and melting curve analysis: A step towards rapid DNA identity screening. *Forensic Sci Int Genet*, 2008, **2**(4): 333–339.

Gale, N., et al., Rapid typing of STRs in the human genome by HyBeacon melting. *Org Biomol Chem*, 2008, **6**(24): 4553–4559.

Gill, P., P. Koumi, and H. Allen, Sizing short tandem repeat alleles in capillary array gel electrophoresis instruments. *Electrophoresis*, 2001, **22**(13): 2670–2678.

Greenspoon, S.A., et al., A forensic laboratory tests the Berkeley microfabricated capillary array electrophoresis device. *J Forensic Sci*, 2008, **53**(4): 828–837.

Hagan, K.A., et al., A valveless microfluidic device for integrated solid phase extraction and polymerase chain reaction for short tandem repeat (STR) analysis. *Analyst*, 2011, **136**(9): 1928–1937.

Horsman, K.M., et al., Forensic DNA analysis on microfluidic devices: A review. *J Forensic Sci*, 2007, **52**(4): 784–799.

Hurth, C., et al., An automated instrument for human STR identification: Design, characterization, and experimental validation. *Electrophoresis*, 2010, **31**(21): 3510–3517.

Isenberg, A.R., et al., Analysis of two multiplexed short tandem repeat systems using capillary electrophoresis with multiwavelength fluorescence detection. *Electrophoresis*, 1998, **19**(1): 94–100.

Issaq, H.J., K.C. Chan, and G.M. Muschik, The effect of column length, applied voltage, gel type, and concentration on the capillary electrophoresis separation of DNA fragments and polymerase chain reaction products. *Electrophoresis*, 1997, **18**(7): 1153–1158.

Koumi, P., et al., Evaluation and validation of the ABI 3700, ABI 3100, and the MegaBACE 1000 capillary array electrophoresis instruments for use with short tandem repeat microsatellite typing in a forensic environment. *Electrophoresis*, 2004, **25**(14): 2227–2241.

Lazaruk, K., et al., Genotyping of forensic short tandem repeat (STR) systems based on sizing precision in a capillary electrophoresis instrument. *Electrophoresis*, 1998, **19**(1): 86–93.

Liu, P., et al., Integrated portable polymerase chain reaction-capillary electrophoresis microsystem for rapid forensic short tandem repeat typing. *Anal Chem*, 2007, **79**(5): 1881–1889.

Liu, P., et al., Real-time forensic DNA analysis at a crime scene using a portable microchip analyzer. *Forensic Sci Int Genet*, 2008, **2**(4): 301–309.

Liu, P. and R.A. Mathies, Integrated microfluidic systems for high-performance genetic analysis. *Trends Biotechnol*, 2009, **27**(10): 572–581.

Liu, P., et al., Integrated DNA purification, PCR, sample cleanup, and capillary electrophoresis microchip for forensic human identification. *Lab Chip*, 2011, **11**(6): 1041–1048.

Liu, P., et al., Integrated sample cleanup and capillary array electrophoresis microchip for forensic short tandem repeat analysis. *Forensic Sci Int Genet*, 2011, **5**(5): 484–492.

Liu, P., et al., Integrated sample cleanup and microchip capillary array electrophoresis for high-performance forensic STR profiling. *Methods Mol Biol*, 2012, **830**: 351–365.

Lounsbury, J.A., et al., From sample to PCR product in under 45 minutes: A polymeric integrated microdevice for clinical and forensic DNA analysis. *Lab Chip*, 2013, **13**(7): 1384–1393.

Madabhushi, R.S., Separation of 4-color DNA sequencing extension products in noncovalently coated capillaries using low viscosity polymer solutions. *Electrophoresis*, 1998, **19**(2): 224–230.

Mansfield, E.S., et al., Sensitivity, reproducibility, and accuracy in short tandem repeat genotyping using capillary array electrophoresis. *Genome Res*, 1996, **6**(9): 893–903.

Mansfield, E.S., et al., Analysis of multiplexed short tandem repeat (STR) systems using capillary array electrophoresis. *Electrophoresis*, 1998, **19**(1): 101–107.

McLaren, R.S., et al., Post-injection hybridization of complementary DNA strands on capillary electrophoresis platforms: A novel solution for dsDNA artifacts. *Forensic Sci Int Genet*, 2008, **2**(4): 257–273.

Montesino, M. and L. Prieto, Capillary electrophoresis of big-dye terminator sequencing reactions for human mtDNA control region haplotyping in the identification of human remains. *Methods Mol Biol*, 2012, **830**: 267–281.

Moretti, T.R., et al., Validation of STR typing by capillary electrophoresis. *J Forensic Sci*, 2001, **46**(3): 661–676.

Nai, Y.H., S.M. Powell, and M.C. Breadmore, Capillary electrophoretic system of ribonucleic acid molecules. *J Chromatogr A*, 2012, **1267**: 2–9.

Njoroge, S.K., et al., Integrated microfluidic systems for DNA analysis. *Top Curr Chem*, 2011, **304**: 203–260.

Pascali, J.P., F. Bortolotti, and F. Tagliaro, Recent advances in the application of CE to forensic sciences, an update over years 2009–2011. *Electrophoresis*, 2012, **33**(1): 117–126.

Pereira, J., et al., MtDNA typing of single-sperm cells isolated by micromanipulation. *Forensic Sci Int Genet*, 2012, **6**(2): 228–235.

Rosenblum, B.B., et al., Improved single-strand DNA sizing accuracy in capillary electrophoresis. *Nucleic Acids Res*, 1997, **25**(19): 3925–3929.

Roy, R., et al., Producing STR locus patterns from bloodstains and other forensic samples using an infrared fluorescent automated DNA sequencer. *J Forensic Sci*, 1996, **41**(3): 418–424.

Schneider, C., et al., Low copy number DNA profiling from isolated sperm using the aureka® micromanipulation system. *Forensic Sci Int Genet*, 2012, **6**(4): 461–465.

Sgueglia, J.B., S. Geiger, and J. Davis, Precision studies using the ABI prism 3100 genetic analyzer for forensic DNA analysis. *Anal Bioanal Chem*, 2003, **376**(8): 1247–1254.

Siles, B.A., et al., The use of a new gel matrix for the separation of DNA fragments: A comparison study between slab gel electrophoresis and capillary electrophoresis. *Appl Theor Electrophor*, 1996, **6**(1): 15–22.

Sinville, R. and S.A. Soper, High resolution DNA separations using microchip electrophoresis. *J Sep Sci*, 2007, **30**(11): 1714–1728.

Southern, E.M., Measurement of DNA length by gel electrophoresis. *Anal Biochem*, 1979, **100**, 319–323.

Tagliaro, F. and F. Bortolotti, Recent advances in the applications of CE to forensic sciences (2005–2007). *Electrophoresis*, 2008, **29**(1): 260–268.

Tereba, A., K.A. Micka, and J.W. Schumm, Reuse of denaturing polyacrylamide gels for short tandem repeat analysis. *Biotechniques*, 1998, **25**(5): 892–897.

Villablanca, A., et al., Suspension bead array branch migration displacement assay for rapid STR analysis. *Electrophoresis*, 2008, **29**(19): 4109–4114.

Wang, D.Y., et al., Identification and secondary structure analysis of a region affecting electrophoretic mobility of the STR locus SE33. *Forensic Sci Int Genet*, 2012, **6**(3): 310–316.

Wang, Y., et al., Rapid sizing of short tandem repeat alleles using capillary array electrophoresis and energy-transfer fluorescent primers. *Anal Chem*, 1995, **67**(7): 1197–1203.

Wenz, H., et al., High-precision genotyping by denaturing capillary electrophoresis. *Genome Res*, 1998, **8**(1): 69–80.

Westen, A.A., et al., Higher capillary electrophoresis injection settings as an efficient approach to increase the sensitivity of STR typing. *J Forensic Sci*, 2009, **54**(3): 591–598.

Yang, J., et al., An integratable microfluidic cartridge for forensic swab samples lysis. *Forensic Sci Int Genet*, 2014, **8**(1): 147–158.

9

Detection Methods

A variety of techniques are available for the detection of DNA fragments in forensic DNA analysis. For example, the direct detection of DNA fragments in a gel can be achieved via staining. The detection of DNA probes in a hybridization-based assay can be performed with radioisotopes, colorimetric assays, and chemiluminescence labeling. For polymerase chain reaction (PCR)-based assays, DNA primers can be labeled directly with fluorescent dyes.

9.1 Direct Detection of DNA in Gels

This section describes two simple and rapid detection methods used for detecting DNA: staining agarose gels with fluorescent intercalating dyes and staining denatured polyacrylamide gels with silver.

9.1.1 Fluorescent Intercalating Dye Staining

The location of DNA in an agarose gel can be determined directly by staining with low concentrations of fluorescent intercalating dyes (Chapter 6) such as ethidium bromide (Figures 9.1 through 9.3). These techniques allow the detection of DNA bands as small as 10 ng in agarose gels. Staining of DNA in agarose gels can be achieved by including an intercalating dye in the gel or staining the gel after electrophoresis in a dye-containing solution, followed by a washing step known as de-staining to reduce nonspecific staining. Historically, ethidium bromide-stained gels were photographed with a standard ultraviolet transilluminator at approximately 300 nm using a camera with an orange filter, whereas gels can currently be documented using digital techniques. When examining a DNA-containing gel under a UV lamp, the eyes and the skin should be protected from UV exposure. Ethidium bromide is a mutagen and a potential carcinogen. Ethidium bromide should be handled according to the Material Safety Data Sheet and safety protection wear should be used while handling the chemical. Ethidium bromide waste is usually disposed of as hazardous waste and is handled in accordance with laboratory guidelines. Alternatives to ethidium bromide are available, for example, fluorescent dyes such as SYBR® stains (Molecular Probes; Figures 9.2 and 9.3). Some of these alternatives are less mutagenic and have better performance than ethidium bromide.

9.1.2 Silver Staining

Electrophoretically separated DNA fragments can also be detected with silver nitrate staining. Silver staining of polyacrylamide gels has been used for the amplified fragment length polymorphism (AFLP; see Chapter 19) method of variable number tandem repeat (VNTR; see



Figure 9.1 Schematic illustration showing binding of an intercalating agent, ethidium bromide (EtBr) to DNA. It intercalates into the minor groove of DNA. (© Richard C. Li.)



Figure 9.2 Intercalating agents used as nucleic acid stains. (a) Chemical structure of ethidium bromide. Ethidium bromide has UV absorbance. The emission maximum of the DNA–dye complex in aqueous solution is approximately 590 nm. (b) Chemical structure of SYBR Green 1. The stain is a cyanine dye that binds to DNA and is used as a nucleic acid stain. The excitation and emission maxima of the DNA–dye complex are 494 and 521 nm, respectively. The stain preferentially binds to double-stranded DNA rather than single-stranded DNA and RNA.

Chapter 19) profiling. The sensitivity of silver staining is approximately 100 times higher than that obtained with ethidium bromide, and silver staining is less hazardous than ethidium bromide detection. Also, the developing chemicals are readily available at low cost.

Silver staining involves processing a gel followed by exposure to a series of chemicals. First, the gel is submerged in a silver nitrate solution. Silver ions are positively charged, and DNA is negatively charged. Therefore, silver ions bind to the DNA and are subsequently reduced using formaldehyde to form a deposit of metallic silver on the DNA in the gel (Figure 9.4). A photograph of the gel with images of the silver-stained DNA strands is kept as a permanent record. Alternatively, the gels may be sealed and preserved for record purposes. One disadvantage of this method is that silver stains RNA and proteins along with DNA. The presence of restriction enzymes and polymerase should therefore be minimized. Additionally, bands from both complementary DNA strands may be detected in a denatured polyacrylamide gel, which leads to a two-band pattern.



Figure 9.3 A DNA–dye complex emitting fluorescence on UV-light exposure. Ethidium bromide–containing agarose gel (left). SYBR Green 1–containing agarose gel (right). (© Richard C. Li.)



Figure 9.4 Silver staining of DNA. Silver (Ag^+) ions bind to DNA and are reduced to metallic silver (Ag) to form dark particles. (© Richard C. Li.)

9.2 Detection of DNA Probes in Hybridization-Based Assays

9.2.1 Radioisotope Labeled Probes

Radioisotope probe labeling was used for early versions of VNTR testing and DNA quantitation. Labeling can be accomplished in several ways (Figure 9.5). For example, nick translation incorporates labeled deoxyribonucleotides (dNTPs) into double-stranded DNA. DNase I is used to introduce single-strand nicks within the DNA fragment to be labeled. Next, DNA Polymerase I recognizes the nicks and replaces the preexisting nucleotides with new strands containing labeled dNTPs, resulting in the generation of ^{32}P-labeled double-stranded DNA molecules. ^{32}P, with a half-life of approximately 14 days, is the most common radioisotope used in this technique. Nick translation can utilize any dNTP labeled with ^{32}P.

Prior to hybridization, the probe is denatured into single-stranded fragments by boiling for a few minutes followed by rapid cooling on ice. After the hybridization process, these probes can be visualized by exposing the DNA-containing membrane to an x-ray film. The radioactive object is commonly placed in an x-ray cassette. The energy released from the decay of the radioisotopes is absorbed by the silver halide grains in the film emulsion and forms a latent image. A chemical development process amplifies the latent image and renders it visible on film (Figure 9.6). Because most ^{32}P emissions pass through the thin film emulsion without


5′
3′
3′
5′
DNase I
Nick
OH P
Tagged dNTPs
DNA polymerase
OH P
(a)
Denature anneal
3′
5′
Tagged dNTPs
DNA polymerase
(b)

Figure 9.5 DNA probe labeling using dNTPs. (a) Nick translation method. A DNase is utilized to create nicks along a DNA strand. Tagged nucleotides (one or more than one of the dNTPs) are then incorporated into the DNA strand using a DNA polymerase. DNA synthesis extends from the 5′ to 3′ end and the original strand is degraded. (b) Random primer labeling method. A template DNA is denatured and separated into single strands. A random mixture of hexameric deoxynucleotide fragments, as primers, is then annealed to the template strand. The tagged nucleotides are then incorporated by the Klenow fragment of the DNA polymerase. (© Richard C. Li.)



Figure 9.5 (Continued) (c) PCR method. DNA templates are denatured and then annealed to primers flanking the region of interest. During the DNA synthesis phase of a PCR cycle (see Chapter 7), tagged nucleotides are incorporated into the DNA strand using a Taq DNA polymerase, producing new double-stranded DNA. The process is repeated for many cycles. Only the first cycle is shown. (© Richard C. Li.)



Figure 9.6 Autoradiography. Exposure to radiation causes halide crystals to release electrons, thus reducing silver (Ag^+) ions to metallic silver (Ag). (© Richard C. Li.)

contributing to the final image, the detection process may require long exposure times. Signal intensity can be enhanced, however, by using intensifying screens at low temperatures. The screens emit photons upon receiving radioactive β-particles, thus further enhancing signals. Additionally, highly sensitive x-ray film can be used. One disadvantage of using ^{32}P is that it is a safety hazard. Additionally, autoradiography is a lengthy process. Therefore, nonradioisotopic detection methods have become popular alternatives.

9.2.2 Enzyme-Conjugated Probe with Chemiluminescence Reporting System

The use of alkaline phosphatase (AP)-conjugated probes with chemiluminescent substrates comprises a highly sensitive nonradioisotopic detection system.

Alkaline phosphatase can cleave the phosphate groups from a variety of substrate molecules. Its enzymatic activity can be measured using dioxetane-based chemiluminescent substrates such as Lumigen® PPD (Figure 9.7). The Lumi-Phos Plus kit of Lumigen Inc. contains this substrate and can serve as a detection system for slot blot assays for DNA quantitation (Chapter 6) and RFLP assays for VNTR profiling (Chapter 19). AP catalyzes the cleavage of the phosphate ester of Lumigen® PPD, resulting in the release of a photon (Figure 9.8). The Lumigen® PPD substrate yields a long-lasting light emission that can be detected by exposure to x-ray film. This system provides a highly sensitive chemiluminescent detection method for AP-conjugated DNA probes in solution or on a solid matrix such as a membrane (Table 9.1).

9.2.3 Biotinylation of DNA with Colorimetric Reporting Systems

9.2.3.1 Biotin

Biotin, also known as vitamin H, is a water-soluble molecule found in egg yolk (Figure 9.9). It can be incorporated onto oligonucleotide probes without interfering with the ability of probes to hybridize because of its small size (molecular weight: 244.31 u). Signals from a biotinylated probe can be detected with an enzyme-conjugated avidin system. Two steps are required to detect biotin-labeled probes. First, an avidin conjugate consisting of a reporter enzyme is added. Then, the reporter enzyme is assayed with substrates.

9.2.3.2 Enzyme-Conjugated Avidin

Avidin is a glycoprotein found in egg white; it binds to biotin with extremely high affinity. Thus, a biotin–avidin complex is very stable. However, avidin detection has a high background due to nonspecific binding. The nonspecific binding can be reduced by replacing avidin with its



Figure 9.7 Detection system using AP-conjugated probe. Chemiluminescence is generated by using the Lumigen® PPD as an AP substrate. (© Richard C. Li.)



Figure 9.8 Lumi-Phos Plus contains Lumigen® PPD (4-methoxy-4-[3-phosphatephenyl]spiro[1,2-dioxetane-3,2′-adamantane], disodium salt). AP catalyzes the removal of the phosphate group of Lumigen® PPD and generates a chemiluminescent intermediate that is subsequently broken down to the excited state of methyl-*m*-oxybenzoate. The decay of the excited state end-product releases a photon.

Table 9.1 Forensic Applications of Enzyme Reporting Systems for Detecting DNA

Reporter Enzyme	Labeling	Detection Mechanism	Substrate	Forensic Application
AP	AP-conjugated probe	Chemiluminescent	Lumigen®PPD	RFLP; blot assay for DNA quantitation
Horseradish peroxidase (HRP)	Biotinylated probe, recognized by streptavidin conjugated with HRP	Colorimetric/ chemiluminescent	TMB/luminol	Blot assay for DNA quantitation
	Biotinylated primer, recognized by streptavidin conjugated with HRP	Colorimetric	TMB	Reverse blot assay for DQA1 typing and for mtDNA typing



Figure 9.9 Nonradioactive tags for labeling and detecting nucleic acids. (a) Chemical structure of biotin, also known as vitamin H. Molecular formula: $C_{10}H_{16}N_2O_3S$. Molecular weight: 244.31. (b) Chemical structure of digoxigenin. Molecular formula: $C_{23}H_{34}O_5$. Molecular weight: 390.51.

streptavidin counterpart from *Streptomyces avidinii*. To detect binding, an enzyme-conjugated streptavidin such as horseradish peroxidase (HRP)-conjugated streptavidin can be used. HRP isolated from horseradish roots contains heme residues that catalyze the oxidation reactions of substrates (Chapter 12).

9.2.3.3 Reporter Enzyme Assay

HRP can be assayed with colorimetric, chemiluminescent, or fluorogenic substrates. One common colorimetric substrate for forensic DNA testing is 3,3′,5,5′-tetramethylbenzidine (TMB), which is oxidized by the peroxidase to form an insoluble precipitate of intense blue at an acidic pH (Figure 9.10). Because the colored precipitate is difficult to remove from membranes, TMB is not suitable if reprobing for RFLP analysis is required. This technique has been used for forensic DNA testing such as slot blot assays for DNA quantitation (Table 9.1). A chemiluminescent substrate such as a luminol-based reagent can also be utilized with


(a)
HRP
SA
Biotinylated probe or amplicon
(b)
HRP
SA
Biotinylated probe or amplicon
(c)
TMB (colorless)
Blue precipitate
HRP
SA
Biotinylated probe or amplicon
(d)
Luminol
hv
HRP
SA
Biotinylated probe or amplicon

Figure 9.10 Detection system using biotinylated DNA probes with colorimetric and chemiluminescent reactions. (a) Biotinylated probe is incubated with a streptavidin (SA) and horseradish peroxidase (HRP) conjugate complex. (b) Biotin is recognized by the complex. Reporter enzyme assays can be carried out using either a colorimetric reaction with a TMB substrate (c) or a chemiluminescent reaction using luminol analogs (d). (© Richard C. Li.)

HRP. The peroxidase catalyzes the oxidation of luminol to form a chemiluminescent product (Figure 9.10).

9.3 Detection Methods for PCR-Based Assays

9.3.1 Fluorescence Labeling

9.3.1.1 Fluorescent Dyes

The advantages of fluorescence detection methods include a higher sensitivity and broader dynamic range than comparable colorimetric detection methods. Furthermore, they have the capacity for simultaneous analysis of complex samples such as multiplex PCR products with different fluorescent labels (Figure 9.11), allowing the distinction of various amplicons. Commonly used fluorescent dyes in DNA labeling emit fluorescence in the range of 400–600 nm (Figures 9.12 and 9.13).

9.3.1.2 Labeling Methods

Fluorescent dye labeling can be incorporated into a DNA fragment using a 5′-end fluorescently labeled oligonucleotide primer (Figures 9.14 and 9.15). The dye-labeled primer method is usually used for STR profiling (see Chapter 20) in which only one primer from each primer pair is labeled; therefore, only one strand can be detected. The two-band pattern observed with silver staining does not appear with this method. Additionally, dye-labeled primers allow multiplex PCR amplifications in the same tube.



Figure 9.11 Emission spectra of common fluorescent dyes used for forensic DNA analysis. (© Richard C. Li.)

Color	Fluorescent dye	Globalfiler	AmpFlSTR Yfiler	PowerPlex fusion system	PowerPlex Y23 system
Purple dye	SID	☑			
Blue dyes	FAM	☑	☑		
	Fluorescein			☑	☑
Green dyes	JOE			☑	☑
	VIC	☑	☑		
Yellow dyes	NED	☑	☑		
	TMR (TAMRA)			☑	☑
Orange dyes	CC5			☑	☑
	LIZ	☑	☑		
Red dyes	PET		☑		
	ROX (CXR)			☑	☑
	TAZ	☑			

Figure 9.12 Examples of fluorescent dyes and their applications in STR kits. *Note*: Globalfiler and AmpFlSTR Yfiler are manufactured by Applied Biosystems. PowerPlex Fusion system and PowerPlex® Y23 System are manufactured by Promega.



Fluorescein
$\lambda_{ex} = 495; \lambda_{em} = 520$



FAM
$\lambda_{ex} = 494; \lambda_{em} = 518$


Cl
Cl
HO
O
O
H_3CO
OCH_3
COOH

JOE
$\lambda_{ex} = 522; \lambda_{em} = 550$



TMR
$\lambda_{ex} = 543; \lambda_{em} = 570$



ROX
$\lambda_{ex} = 570; \lambda_{em} = 595$

Figure 9.13 Chemical structures of representative fluorescent dyes. Fluorescein, 3′,6′-dihydroxyspiro[2-benzofuran-3,9′-xanthene]-1-one; FAM, 5(6)-carboxyfluorescein; JOE, 6-carboxy-4′,5′-dichloro-2′,7′-dimethoxy-fluorescein; TMR, 5-carboxytetramethylrhodamine; ROX, 5(6)-carboxy-X-rhodamine; λ_{ex}, peak excitation wavelength (nm); λ_{em}, peak emission wavelength (nm).


Fluorescent dye
Primer
DNA polymerase
Fluorescent labeled amplicon

Figure 9.14 A fluorescent dye–labeled primer can be used for the amplification of DNA. The dye is conjugated at the 5′ end of the primer. The amplified product is fluorescently labeled. (© Richard C. Li.)



Figure 9.15 Direct labeling of nucleic acids with fluorescent dye. Labeled cytosine is shown as an example. R, fluorescent dye.

Alternatively, fluorescent dye labeling of DNA fragments can be carried out by incorporating fluorescently labeled dideoxynucleotides (ddNTPs) in the PCR product. This labeling method is usually used in DNA sequencing such as mtDNA sequence profiling (Chapter 23).

9.3.1.3 Fluorophore Detection

The *fluorophore* is a component of a florescent dye molecule that causes the molecule to be fluorescent. First, a laser strikes a fluorophore covalently linked to the end of a DNA fragment. An electron of the fluorophore is then excited, rising to an excited state from a ground state. The excited electron then descends to the ground state and releases a photon (Figure 9.16). The emitted photon has a longer wavelength (emission spectrum) than that of the excitation photon (excitation spectrum). The wavelengths of excitation and emission spectra (Figure 9.17) are largely dependent on the chemical structure of the fluorophore.

Lasers are commonly used as *excitation sources* because laser light emissions have high intensity and are monochromatic (single wavelength). The argon ion gas laser is frequently used in applications such as fluorescence-labeled STR and mtDNA sequence analysis because the excitation wavelength of commonly used fluorescent dyes matches the wavelength of the argon laser.

Optical filters are used to filter out undesired light and to allow only one particular wavelength to pass through. An essential optical filter consists of three components: an excitation filter, a dichroic beam splitter, and an emission filter. The excitation filter selectively transmits light from an excitation source. The light is then directed by the dichroic beam splitter to DNA molecules labeled with fluorescent dyes. The light emitted from a fluorophore is also transmitted by the dichroic beam splitter toward the detector. The emission filter selectively blocks undesired light, thus transmitting a specific wavelength of the emitted fluorescence. The light intensity emitted from a fluorophore is detected using a photosensitive device such as a charge-coupled device (CCD). The signal from the fluorophore is collected and converted to an electronic signal expressed in an arbitrary unit such as a *relative fluorescence unit* (RFU). Signals from multiple fluorophores in the same sample can be recorded separately using optical filters and a mathematical *matrix* (fluorophore separation algorithm). The function of a matrix is to subtract the



Figure 9.16 A Jablonski diagram illustrating the absorption of a single photon and subsequent emission of fluorescence. During an excitation stage, a single photon with the appropriate energy excites a molecule to the first excited energy level (S_2). In fluorescence reactions, the energy is supplied by an external light source such as a laser, while in chemiluminescence reactions, the energy is derived from a chemical reaction. The excited molecule is not stable and relaxes to its lowest vibrational level in the excited state (S_1). The molecule then returns to the ground state (S_0), emitting a photon. (© Richard C. Li.)



Figure 9.17 A fluorescence excitation spectrum. In fluorescence reactions, the energy of the photon emitted is lower than that of the excitation photon. As a result, the wavelength of an emission photon is longer than that of an excitation photon. The difference in wavelength is known as the Stokes shift. (© Richard C. Li.)

color overlaps of the various fluorescent dyes. The matrix can be established by the calibration of fluorescently labeled standards.

Bibliography

Bassam, B.J., G. Caetano-Anolles, and P.M. Gresshoff, Fast and sensitive silver staining of DNA in polyacrylamide gels. *Anal Biochem*, 1991, **196**(1): 80–83.

Bregu, J., et al., Analytical thresholds and sensitivity: Establishing RFU thresholds for forensic DNA analysis. *J Forensic Sci*, 2013, **58**(1): 120–129.

Bronstein, I. and P. McGrath, Chemiluminescence lights up. *Nature*, 1989, **338**(6216): 599–600.

Bronstein, I., et al., Rapid and sensitive detection of DNA in Southern blots with chemiluminescence. *Biotechniques*, 1990, **8**(3): 310–314.

Brunk, C.F. and L. Simpson, Comparison of various ultraviolet sources for fluorescent detection of ethidium bromide-DNA complexes in polyacrylamide gels. *Anal Biochem*, 1977, **82**(2): 455–462.

Budowle, B., et al., Simple protocols for typing forensic biological evidence: Chemiluminescent detection for human DNA quantitation and restriction fragment length polymorphism (RFLP) analyses and manual typing of polymerase chain reaction (PCR) amplified polymorphisms. *Electrophoresis*, 1995, **16**(9): 1559–1567.

Buel, E. and M. Schwartz, The use of DAPI as a replacement for ethidium bromide in forensic DNA analysis. *J Forensic Sci*, 1995, **40**(2): 275–278.

Cardullo, R.A., et al., Detection of nucleic acid hybridization by nonradiative fluorescence resonance energy transfer. *Proc Natl Acad Sci U S A*, 1988, **85**(23): 8790–8794.

Decorte, R. and J.J. Cassiman, Evaluation of the ALF DNA sequencer for high-speed sizing of short tandem repeat alleles. *Electrophoresis*, 1996, **17**(10): 1542–1549.

Feinberg, A.P. and B. Vogelstein, A technique for radiolabeling DNA restriction endonuclease fragments to high specific activity. *Anal Biochem*, 1983, **132**(1): 6–13.

French, B.T., H.M. Maul, and G.G. Maul, Screening cDNA expression libraries with monoclonal and polyclonal antibodies using an amplified biotin-avidin-peroxidase technique. *Anal Biochem*, 1986, **156**(2): 417–423.

Gillespie, P.G. and A.J. Hudspeth, Chemiluminescence detection of proteins from single cells. *Proc Natl Acad Sci U S A*, 1991, **88**(6): 2563–2567.

Giusti, A.M. and B. Budowle, A chemiluminescence-based detection system for human DNA quantitation and restriction fragment length polymorphism (RFLP) analysis. *Appl Theor Electrophor*, 1995, **5**(2): 89–98.

Green, N.M., Avidin. *Adv Protein Chem*, 1975, **29**: 85–133.

Green, N.M. and E.J. Toms, The properties of subunits of avidin coupled to sepharose. *Biochem J*, 1973, **133**(4): 687–700.

Halpern, M.D. and J. Ballantyne, An STR melt curve genotyping assay for forensic analysis employing an intercalating dye probe FRET. *J Forensic Sci*, 2011, **56**(1): 36–45.

Johnson, E.D. and T.M. Kotowski, Chemiluminescent detection of RFLP patterns in forensic DNA analysis. *J Forensic Sci*, 1996, **41**(4): 569–578.

Laskey, R.A. and A.D. Mills, Enhanced autoradiographic detection of 32P and 125I using intensifying screens and hypersensitized film. *FEBS Lett*, 1977, **82**(2): 314–316.

Lee, L.G., et al., Seven-color, homogeneous detection of six PCR products. *Biotechniques*, 1999, **27**(2): 342–349.

LePecq, J.B. and C. Paoletti, A fluorescent complex between ethidium bromide and nucleic acids. Physical-chemical characterization. *J Mol Biol*, 1967, **27**(1): 87–106.

Mansfield, E.S. and M.N. Kronick, Alternative labeling techniques for automated fluorescence based analysis of PCR products. *Biotechniques*, 1993, **15**(2): 274–279.

Mayrand, P.E., et al., The use of fluorescence detection and internal lane standards to size PCR products automatically. *Appl Theor Electrophor*, 1992, **3**(1): 1–11.

McKimm-Breschkin, J.L., The use of tetramethylbenzidine for solid phase immunoassays. *J Immunol Methods*, 1990, **135**(1–2): 277–280.

Merril, C.R., Silver staining of proteins and DNA. *Nature*, 1990, **343**(6260): 779–780.

Mitchell, L.G., A. Bodenteich, and C.R. Merril, Use of silver staining to detect nucleic acids. *Methods Mol Biol*, 1994, **31**: 197–203.

Morin, P.A. and D.G. Smith, Nonradioactive detection of hypervariable simple sequence repeats in short polyacrylamide gels. *Biotechniques*, 1995, **19**(2): 223–228.

Renz, M. and C. Kurz, A colorimetric method for DNA hybridization. *Nucleic Acids Res*, 1984, **12**(8): 3435–3444.

Roberts, I.M., et al., A comparison of the sensitivity and specificity of enzyme immunoassays and time-resolved fluoroimmunoassay. *J Immunol Methods*, 1991, **143**(1): 49–56.

Selvin, P.R., Fluorescence resonance energy transfer. *Methods Enzymol*, 1995, **246**: 300–334.

Southern, E.M., Detection of specific sequences among DNA fragments separated by gel electrophoresis. *J Mol Biol*, 1975, **98**(3): 503–517.

Stone, T. and I. Durrant, Enhanced chemiluminescence for the detection of membrane-bound nucleic acid sequences: Advantages of the Amersham system. *Genet Anal Tech Appl*, 1991, **8**(8): 230–237.

Tizard, R., et al., Imaging of DNA sequences with chemiluminescence. *Proc Natl Acad Sci U S A*, 1990, **87**(12): 4514–4518.

Tuma, R.S., et al., Characterization of SYBR Gold nucleic acid gel stain: A dye optimized for use with 300-nm ultraviolet transilluminators. *Anal Biochem*, 1999, **268**(2): 278–288.

Waring, M.J., Complex formation between ethidium bromide and nucleic acids. *J Mol Biol*, 1965, **13**(1): 269–282.

Watkins, T.I. and G. Woolfe, Effect of changing the quaternizing group on the trypanocidal activity of dimidium bromide. *Nature*, 1952, **169**(4299): 506–507.

Yeung, S.H., et al., Fluorescence energy transfer-labeled primers for high-performance forensic DNA profiling. *Electrophoresis*, 2008, **29**(11): 2251–2259.

10

Serology Concepts

10.1 Serological Reagents

10.1.1 Immunogens and Antigens

A foreign substance that is capable of eliciting antibody formation when introduced into a host is called an *immunogen*. Natural immunogens are usually macromolecules such as proteins and polysaccharides. Other molecular structures can also act as immunogens, for example, glycolipids (such as A, B, and O blood group antigens) and glycoproteins (such as Rh and Lewis antigens). However, they must be foreign to their hosts. The molecular structure of an immunogen, usually a small portion recognized by an antibody, is called an *epitope* or determinant site. An immunogen usually consists of multiple epitopes and is thus considered *multivalent* (Figure 10.1). Each epitope can elicit the production of its own corresponding antibody.

An *antigen* is a foreign substance that is capable of reacting with an antibody. All immunogens can be considered antigens, but not all antigens can elicit antibody formation. *Hapten* is one example of a substance that is antigenic but not immunogenic. Haptens are chemical compounds that are too small to elicit antibody production when they are introduced to a host animal. However, a hapten can be coupled to a *carrier*, usually a macromolecule, to produce antibodies. A hapten-conjugated carrier can become immunogenic to elicit the formation of an antibody specific to the hapten. The resulting antibody can bind to free haptens. Certain controlled substances such as cocaine and amphetamines are haptens and can be detected through corresponding antibodies for forensic toxicological analysis.

10.1.2 Antibodies

Antibodies, also known as *immunoglobulins*, are capable of binding specifically to antigens and are designated with an Ig prefix. The five major classes of immunoglobulins are designated IgG, IgA, IgM, IgD, and IgE. Additionally, IgG immunoglobulins can be further divided into four subclasses (IgG1–IgG4) and IgA immunoglobulins can be further divided into two subclasses (IgA1 and IgA2). Thus, there are a total of nine immunoglobulin isotypes in humans. *Isotypes* are the immunoglobulins that differ based on the molecular variations in the constant domains of the heavy and light chains (Figure 10.2). IgD, IgE, and IgG are usually monomers. IgM can be a membrane-bound monomer or a cross-linked pentamer (secreted form). IgA can be a monomer, dimer, or trimer. In an immune response, an initial exposure to an immunogen elicits a primary response, producing IgM immunoglobulins. Further exposure to the immunogen can elicit a secondary response, producing IgG, IgA, IgE, and IgD immunoglobulins. IgG is the most abundant immunoglobulin in serum. A majority of serology tests are based on the IgG immunoglobulins.



Figure 10.1 Multivalent immunogen. A protein with two different epitopes is shown. (© Richard C. Li)

Immunoglobulins have many similarities in their molecular structures. Figure 10.2 illustrates a diagram of the IgG molecule. The structures of immunoglobulins were first revealed by Gerald Edelman and Rodney Porter who shared a Nobel Prize in 1972. Immunoglobulins are composed of four polypeptide chains: two heavy (H) chains and two light (L) chains. The polypeptide chains are linked by disulfide bonds into a Y-shaped complex. The H chain can be divided into fragment antigen-binding (*Fab*) and fragment crystallizable (*Fc*) fragments. The L chain consists of a Fab fragment only. A typical antibody has two identical antigen-binding sites and is thus considered *bivalent*. The antigen-binding activity is located within the Fab fragments. In particular, the N-terminal ends of the L and H chains together form antigen-binding sites. At the amino acid sequence level, both H and L chains have *variable and constant domains* (Figure 10.2). The variable domains are located at the N-terminal ends of the immunoglobulins. Additionally, three small *hypervariable regions* are located within the variable domain of each chain.



Figure 10.2 Immunoglobulin IgG structure. Immunoglobulin IgG is composed of light and heavy chains that contain variable domains. The remaining portions of chains form the constant domains. The variable domains of both light and heavy chains contain three hypervariable regions that form the antigen-binding site of the immunoglobulin. (© Richard C. Li.)

The diversity in the amino acid sequences of these hypervariable regions determines the specificity of the antigen-binding sites. The hinge regions provide flexibility to the antibody molecule and are important for the efficiency of the binding and cross-linking reactions. The basal portion of the H chain consists of *Fc* fragment.

The binding affinity and specificity of antibodies make them useful reagents for serological testing. Two types of antibodies are commonly used: polyclonal and monoclonal antibodies.

10.1.2.1 Polyclonal Antibodies

To produce an antibody, an immunogen is usually introduced into a host animal. A multivalent immunogen is capable of eliciting a mixture of antibodies with diverse specificities for the immunogen. As a result, a polyclonal antibody is produced by different B lymphocyte clones in response to the different epitopes of the immunogen. Antibodies can be circulating (in blood or other bodily fluids) or tissue bound (in cell surface antibodies). Circulating immunoglobulins are referred to as humoral antibodies.

The blood from an immune host is drawn and allowed to clot, resulting in the formation of a solid consisting largely of blood cells and a liquid portion known as *serum* containing antibodies (Figure 10.3). Such a preparation of humoral antibodies is also called a *polyclonal antiserum.* Depending on the type of animal used, the antibodies produced are classified as avian (B), rabbit (R), or horse (H) type. The characteristics of polyclonal antibodies may vary if they are produced from different individual host animals of the same species. Variations in reactions among different sources of antibodies should be monitored by quality-control procedures.

10.1.2.2 Monoclonal Antibodies

To produce a monoclonal antibody, spleen cells are harvested from a host animal, such as a mouse, inoculated with an immunogen (Figure 10.4). Next, the plasma cells of the spleen, which produce antibodies, are fused with myeloma cells. Since only a small population of cells fuse, a selection step is needed to allow only fused cells to grow (Figure 10.4). The fused cells, called *hybridoma* cells, are immortal (proliferate indefinitely) in cell cultures. Pools of hybridoma cells are diluted into single clones and are allowed to proliferate. The clones are then screened for the specific antibody of interest.



Figure 10.3 Serum component of blood. The blood of an immunized animal is collected in the absence of an anticoagulant and is allowed to clot. The resulting liquid portion of the blood is serum. (© Richard C. Li.)



Figure 10.4 Preparation of a monoclonal antibody. A mouse is immunized with an immunogen, and its spleen cells are fused with myeloma cells to generate hybridoma cells. The clone that synthesizes and secretes the monoclonal antibody of interest can then be identified. (© Richard C. Li.)

The desired hybridoma clone can be maintained indefinitely, and it produces a monoclonal antibody that reacts with a single epitope. The hybridoma-derived monoclonal antibodies are specific and homogenous, and can be obtained in unlimited quantities. Monoclonal antibodies have been utilized in many serological assays, as discussed in Chapter 11. However, they have certain limitations in serology assays. For instance, monoclonal antibodies react with only a single epitope of a multivalent antigen and, therefore, cannot form cross-linked networks in precipitation assays (see Section 10.3.2.1).

10.1.2.3 Antiglobulins

Immunoglobulins are proteins that can also function as immunogens. If a purified foreign immunoglobulin or a fragment of a foreign immunoglobulin is introduced into a host, the antibodies produced are known as *antiglobulins*. Antiglobulins that are specific to a particular isotype can be produced in laboratories. In addition to specific antiglobulins, it is possible to produce nonspecific antiglobulins, which recognize an epitope that is common to all isotypes of an immunoglobulin class, such as the Fc portion of the heavy chain of all subclasses of human IgG. Antiglobulins are important reagents in many serological tests.



Figure 10.5 Affinity is a measure of the interaction between a single epitope on an antigen and a single binding site on an antibody. (© Richard C. Li.)

10.2 Strength of Antigen–Antibody Binding

The binding of an antigen to its specific antibody is mediated by the interaction between the epitope of an antigen and the binding site of its antibody. Noncovalent bonds can be formed during antigen–antibody binding. Various forces act cooperatively during antigen–antibody binding. These include hydrogen bonding, hydrophobic interactions that exclude water molecules from the area of contact, and van der Waals forces arising from the asymmetric distribution of the charges of electrons. The binding process occurs rapidly and the formation of the antigen–antibody complex is reversible. Such binding occurs at short distances when the antigen and antibody are in close proximity. Additionally, the strongest binding occurs only if the shape of the epitope fits the binding site of the antibody. The strength of the interaction between the antigen and the antibody depends on two characteristics, designated affinity and avidity.

Affinity is the energy of the interaction of a single epitope on an antigen and a single binding site on a corresponding antibody (Figure 10.5). The strength of the interaction depends on the specificity of the antibody for the antigen. Nevertheless, antibodies can bind with lower strength to antigens that are structurally similar to the immunogen. Such binding is known as *cross-reaction*.

Avidity is the overall strength of the binding of an antibody and an antigen (Figure 10.6). Since an antigen is usually considered multivalent and an antibody is bivalent, the avidity reflects the combined synergistic strength of the binding of all the binding sites of antigens and antibodies rather than the sum of individual affinities. It also reflects the overall stability of an antigen–antibody complex that is essential for many serological assays.

10.3 Antigen–Antibody Binding Reactions

The binding of an antigen to an antibody is an equilibrium reaction consisting of three types of reactions. The primary and secondary reactions form the basis for many forensic serological assays and will be discussed in the following subsections. The third type is called the tertiary reaction. It is used to measure *in vivo* immune responses such as inflammation and phagocytosis. Because most forensic serology tests are *in vitro* assays, the tertiary reaction is not commonly utilized in forensic serology testing and will not be discussed here.



Figure 10.6 Avidity is a measure of the overall strength of the binding between antigens and antibodies. (© Richard C. Li.)

10.3.1 Primary Reactions

A primary reaction is the initial binding of a single epitope of an antigen (Ag) and a single binding site of an antibody (Ab) to form an antigen–antibody complex (Figure 10.7). This rapid and reversible binding reaction can be expressed as

$$\text{Ag} + \text{Ab} \rightleftarrows \text{AgAb}$$

At equilibrium, the strength of the interaction can be expressed as the affinity constant (K_a) that reflects the affinity of binding, where:

$$K_a = \frac{[\text{AgAb}]}{[\text{Ag}][\text{Ab}]}$$

The square brackets indicate the concentration of each component at equilibrium. K_a is the reciprocal of the concentration of free epitopes when half the antibody-binding sites are occupied. Thus, a higher K_a corresponds to a stronger binding interaction.

Techniques such as enzyme immunoassays, immunofluorescence assays, radioimmunoassays, and dye-labeled immunochromatography can measure the concentrations of antigen–antibody complexes formed by primary reactions (Chapter 11). These techniques are the most sensitive for detecting the presence of an antigen and an antibody in a sample. Additionally, many forensic serology assays are based on the detection of primary reactions and will be discussed in Chapters 12 through 17.

10.3.2 Secondary Reactions

The primary reaction between an antigen and an antibody is often followed by a secondary reaction. The three types of secondary reactions are precipitation, agglutination, and complement fixation. The techniques that detect secondary reactions are usually less sensitive but easier to perform than primary reaction assays. The precipitation and agglutination reactions form the basis for many serologic assays performed in forensic laboratories. These reactions will be discussed in the following subsections in detail. The third type of reaction is called *complement fixation*. If an antigen is located on a cell surface, the binding of the antigen and the antibody



Figure 10.7 Primary reaction. Initial binding forms an antigen–antibody complex. (© Richard C. Li.)

may activate the classical complement pathway and lead to cell lysis, also known as a complement fixation reaction. The detection of this type of reaction is not commonly used in forensic serology.

10.3.2.1 Precipitation

If a soluble antigen is mixed and incubated with its antibody, the antigen–antibody complexes can form cross-linked complexes at the optimal ratio of antigen-to-antibody concentration. The cross-linked complex is insoluble and eventually forms a precipitate that settles to the bottom of a test tube. Antibodies that produce such precipitation are also called *precipitins*.

This precipitation reaction can be characterized by examining the effect of varying the relative ratio of antigen and antibody. If an increasing amount of soluble antigen is mixed with a constant amount of antibody, the amount of precipitate formed can be plotted. A precipitin curve (Figure 10.8)



Figure 10.8 Precipitin curve. (© Richard C. Li.)

illustrates the results observed when antigens and antibodies are mixed in various concentration ratios. The curve can be divided into three zones known as the prozone, the zone of equivalence, and the postzone.

10.3.2.1.1 Prozone

At this zone, the ratio of antigen–antibody concentration is low. In other words, the antibody is in excess. Each antigen molecule is rapidly saturated with antibody, thus preventing cross-linking (Figure 10.9a). No precipitate is formed at the prozone stage.

10.3.2.1.2 Zone of Equivalence

As the concentrations of antigen increase, the amount of precipitate increases until it reaches a maximum. The amount of precipitation depends on the relative proportions of antigens and antibodies present. The maximum precipitation occurs in what is called the zone of equivalence. In the zone of equivalence, the ratio of antibody to antigen concentration is optimal and



Figure 10.9 Antigen–antibody binding in (a) prozone, (b) zone of equivalence, and (c) postzone. (© Richard C. Li.)

precipitation occurs as a result of forming cross-linked networks (Figure 10.9b). Precipitation assays are usually carried out under the condition of the zone of equivalence, forming a sufficient quantity of precipitation to be detected.

10.3.2.1.3 Postzone

With the addition of more antigens, the ratio of antigen–antibody concentrations is high. In other words, the antigen is in excess. The amount of precipitate decreases and eventually diminishes. Each antibody molecule is saturated with antigen molecules (Figure 10.9c). Cross-linkage cannot form, and precipitation does not occur.

10.3.2.2 Agglutination

As discussed in the previous subsection, precipitation reactions involve soluble antigens. If the antigens are located on the surfaces of cells or carriers (carrier cells such as sheep erythrocytes,



Figure 10.10 Agglutination reaction: (a) antigens are mixed with antibodies, (b) an antigen–antibody complex is formed during initial binding, and (c) the lattice is formed. (© Richard C. Li.)

bacteria, or latex particles), antibodies can bind to the surface antigens and can form cross-links among cells or carriers, causing them to aggregate. This aggregation is referred to as *agglutination*. In agglutination, a visible clumping can be observed as an indicator of the reaction of the antigen and the antibody. If the antigen is located on an erythrocyte, the agglutination reaction is designated *hemagglutination*. Agglutination is a two-step process that includes initial binding and lattice formation (Figure 10.10a).

10.3.2.2.1 Initial Binding

The first step of the reaction involves antigen–antibody binding at a single epitope on the cell surface (Figure 10.10b). This initial binding is rapid and reversible.

10.3.2.2.2 Lattice Formation

The second step involves the formation of a cross-linked network resulting in visible aggregates that constitute a lattice (Figure 10.10c). This involves an antibody binding to multiple epitopes because each antibody has two binding sites and antigens are multivalent. Lattice formation is a much slower process than the initial binding step. The cross-linking of cells requires physical contact. Additionally, an antibody must bind to epitopes on two different cells. The ability to cross-link cells depends on the nature of the antibody. Antibodies that produce such reactions are often called *agglutinins*.

Additionally, a *complete antibody* is capable of carrying out both primary and secondary interactions that result in agglutination. An antibody that can carry out initial binding but fails to form agglutination is called an *incomplete antibody*. This type of antibody is believed to have only one active antigen-binding site and is thus not capable of agglutination. It is potentially caused by the presence of steric obstruction due to the conformation of the incomplete antibody molecule, preventing the binding of antigens at the second binding site. However, other incomplete antibodies have two active sites but cannot bridge the distance between cells, thus failing to form lattices. Certain antibodies such as IgG are small and lack flexibility at the hinge region, and this may prevent agglutination. In contrast, the large IgM antibodies produce agglutination much more easily than IgG. Agglutination reactions have a wide variety of applications in the detection of antigens and antibodies. Such assays have high degrees of sensitivity and have been used for many years in forensic serology.

Bibliography

Baxter, S.J. and B. Rees, The use of anti-human haemoglobin in forensic serology. *Med Sci Law*, 1974, **14**(3): 159–162.

Dodd, B.E., Some recent advances in forensic serology. *Med Sci Law*, 1972, **12**(3): 195–199.

Fletcher, S. and M.J. Davie, Monoclonal antibody: A major new development in immunology. *J Forensic Sci Soc*, 1980, **20**(3): 163–167.

Giusti, G.V., Leone Lattes: Italy's pioneer in forensic serology. *Am J Forensic Med Pathol*, 1982, **3**(1): 79–81.

Goldsby, R., Kindt, T, and Osborne, B., *Immunology*, 6th edn. 2007, New York: W.H. Freeman and Company.

Lee, H.C., et al., Bits and pieces: Serology, criminalistics, anthropology and odontology. *J Forensic Sci Soc*, 1991, **31**(2): 293–296.

Patzelt, D., History of forensic serology and molecular genetics in the sphere of activity of the German Society for Forensic Medicine. *Forensic Sci Int*, 2004, **144**(2–3): 185–191.

Tietz, N. (ed.), *Fundamentals of Clinical Chemistry*, 1987. Philadelphia, PA: W.B. Saunders Company.

11

Serology Techniques

Past, Current, and Future

11.1 Introduction to Forensic Serology

11.1.1 The Scope of Forensic Serology

Forensic serology is the component of forensic biology that deals with the examination and identification of biological evidence. In particular, it focuses on determining the presence and identification of various bodily fluids such as blood, semen, and saliva in a questioned sample.

Bodily fluid stains are commonly associated with violent criminal cases. For instance, the identification of blood evidence (Chapter 12) is often necessary for investigating cases involving homicide, aggravated assault, sexual assault, and burglary. Proving the presence of blood has probative value or may corroborate allegations of violent acts. This evidence can also be used for investigative purposes. For example, the forensic DNA analysis of evidence such as a victim's blood on a suspect's weapon can establish a link between a victim and a suspect. The identification of semen (Chapter 14) and saliva (Chapter 15) is important for the investigation of a sexual assault case. For instance, a stain from a victim's clothing would be processed with forensic DNA analysis in a sexual assault case so that the DNA profile of the stain could be compared with that of an alleged suspect. Matching DNA profiles prove that the suspect's DNA was found on the victim's clothing, establishing a link between the suspect and the victim. Additionally, the identification of a biological stain as a semen stain through forensic serology testing proves that semen was found on the clothing taken from the victim and that the suspect is the source of the DNA from the semen stain. This evidence can then be used in court to support allegations that a sexual act occurred. Likewise, the presence of a suspect's saliva stains on a victim's genital area may corroborate an alleged oral copulation. The identification of bodily fluids other than blood, semen, and saliva will be discussed in Chapters 16 and 17.

11.1.2 Class Characteristics and Individual Characteristics of Biological Evidence

The identification of an unknown fluid sample is based on a comparison of the class characteristics (Section 3.2.1) of a sample with known standards of its class. Forensic identification typically involves bodily fluids, such as blood, semen, and saliva. If the presence of the bodily fluid is confirmed, the individual characteristics (Section 3.2.2) of the biological evidence are then determined to find out whether or not a bodily fluid sample has come from a particular individual. Today, this analysis can be achieved through forensic DNA analysis. The most commonly utilized forensic DNA analysis is the short tandem repeat (STR) analysis used for human identification. Additionally, Y-chromosomal STR analysis is often utilized for the investigation of sexual assault crimes. Furthermore, mitochondrial DNA analysis is used for the identification of human remains. Therefore, establishing the probative value of a sample requires both the identification of its class characteristics and the individualization of its contributor. Therefore, the identification of bodily fluids cannot be replaced by forensic DNA analysis.

11.1.3 Presumptive and Confirmatory Assays

The identification of bodily fluids can be carried out using presumptive and confirmatory assays to identify the type of bodily fluid in question. The advantages of *presumptive assays* are that these assays are sensitive, rapid, and simple. A positive reaction of a presumptive assay indicates the possibility of the presence of the bodily fluid in question. However, presumptive assays are not very specific. Therefore, they should not be considered conclusive for the presence of a type of bodily fluid. In contrast, a negative assay indicates that the questioned bodily fluid is absent. Thus, presumptive assays can be used as a screening method and for narrowing down bodily fluid stains prior to other types of analyses, such as forensic DNA testing. Moreover, these assays can be used as a search method to locate bodily fluid stains at the crime scene. Additional assays, such as confirmatory assays, should be conducted afterward if necessary.

Confirmatory assays are more specific for the bodily fluid in question. These assays are utilized to identify bodily fluids with higher certainty than presumptive assays. For example, bloodstains are commonly associated with criminal investigations. A reddish-brown stain that has been identified through visual examination is usually tested by using presumptive assays. If the result of the presumptive assay on the alleged bloodstain is positive, the stain is then further analyzed by forensic DNA analysis. This approach *indicates* the presence of blood. Confirmatory assays are performed when a sample has to be *identified* as blood (Figure 11.1). Additionally, the human or animal origin of blood evidence can be determined if necessary and the techniques to do so will be discussed in Chapter 13.

11.1.4 Primary and Secondary Binding Assays

Traditionally, the detection and measurement of the antigen–antibody binding reactions serve as the bases of forensic serology. These assays fall into two categories: primary and secondary binding assays. Recall that the primary binding assays involve the initial binding between a single epitope of an antigen and a single binding site of an antibody (see Section 10.3.1). Therefore, they are very sensitive. Although the secondary binding assays are less sensitive than the primary binding assays, they are easier to perform than primary assays. The secondary assays consist of precipitation-based and agglutination-based assays. Precipitation-based assays have been used for species identification. Agglutination-based assays are more sensitive



Figure 11.1 An example of work flow for processing blood samples. (© Richard C. Li.)

than precipitation-based assays. Agglutination-based assays, which detect antigens located on the surface of cells or carriers, are normally applied to blood group typing. Recently, emerging techniques such as RNA, proteomic, and DNA methylation assays, and fluorescence as well as Raman spectroscopy can potentially be used for the identification of bodily fluids.

11.2 Primary Binding Assays

11.2.1 Enzyme-Linked Immunosorbent Assay (ELISA)

An enzyme-linked immunosorbent assay (ELISA) is an immunoenzyme assay that can be used to detect and measure the antibody or antigen in question. The most common ELISA that is used in forensic serology is the antibody-sandwich ELISA (Figure 11.2). It is utilized to detect the prostate-specific antigen (PSA) to identify seminal stains and amylase for the identification of saliva (Chapters 13 and 14).

An antibody (usually monoclonal) coating is formed by nonspecific adsorption onto a solid phase such as the wells of a polystyrene plate. A sample containing the antigen to be tested is then added and binds to the solid-phase antibody. Subsequently, a second antibody is added to form an antibody–antigen–antibody sandwich complex. The second antibody binds to different epitopes of the antigen. Next, an enzyme-labeled antiglobulin (Chapter 10) is added to bind the sandwich. Subsequently, the excess enzyme-labeled antiglobulin is removed by washing and the bound antiglobulin can be detected.

A number of enzymes such as alkaline phosphatase and horseradish peroxidase have been used as reporting enzymes (Chapter 9) to label the antiglobulin for ELISA. The enzyme catalyzes the substrate and produces colorimetric or fluorometric signals. The intensity of the signals can



Figure 11.2 ELISA assay. (a) Sample containing Ag (antigen) is applied to a sample well where Ab (antibody) is immobilized. (b) Ag binds to an immobilized Ab to form an Ag–Ab complex. (c) A second Ab to a different epitope is added to form an Ab–Ag–Ab sandwich. (d) Labeled antiglobulin binds to the sandwich. The bound antiglobulin can be detected by various reporting schemes. (© Richard C. Li.)

be detected spectrophotometrically and is proportional to the amount of bound antigen. The amount of antigen can be quantified by comparing the standard with known concentrations. Recall that antiglobulin can recognize an epitope that is common to all isotypes within an antibody class (Section 10.1.2.3); the enzyme-labeled antiglobulin is a universal reagent regardless of the antibody used, as long as they are of the same class.

Alternatively, antibodies in a sample can also be detected and may be quantified by an ELISA system in which the antigen is bound to a solid phase instead of the antibody. After an antibody in a sample binds to the solid-phase antigen, an enzyme-labeled antiglobulin is added to bind to the bound antibody. The bound antiglobulin can be detected and measured by the addition of an enzyme substrate. The enzymatic catalytic reaction is similar to the antibody sandwich ELISA procedure previously described.

11.2.2 Immunochromatographic Assays

Figure 11.3 depicts a test using an immunochromatographic membrane device. A dye-labeled monoclonal antibody is contained in a sample well and a polyclonal antibody for the antigen (or a second monoclonal antibody to a different epitope of the antigen) is immobilized onto a test zone of a nitrocellulose membrane. An antiglobulin that recognizes the antibody is immobilized onto a control zone.

The assay is carried out by loading a sample into the sample well. The antigen in the sample binds to the dye-labeled antibody already in the sample well to form an antigen–antibody complex. The complex then diffuses across the nitrocellulose membrane until it reaches the test zone. The antibody immobilized at the test zone traps the antigen–antibody complex to form an antibody–antigen–antibody sandwich. The presence of the antigen in the sample results in a colored vertical line at the test zone. (Figure 11.4)

The immunochromatographic device also utilizes a control zone to ensure that the device works properly and that the sample has diffused completely along the test strip. Unbound



Figure 11.3 Immunochromatographic assay. (a) Sample containing Ag (antigen) is loaded in a sample well. (b) Ag binds to a labeled Ab (antibody) to form a labeled Ab–Ag complex. (c) At the test zone, the labeled Ab–Ag complex binds to an immobilized Ab to form a labeled Ab–Ag–Ab sandwich. (d) At the control zone, a labeled Ab binds to an immobilized antiglobulin and is captured at the control zone. (© Richard C. Li.)

monoclonal antibodies diffuse across the membrane until they reach the control zone where they are trapped by the immobilized antiglobulin. This antibody–antiglobulin complex at the control zone also results in a colored vertical line (Figure 11.4). The test is considered valid only if the line in the control zone is observed. The presence of an antigen results in a line at both the test zone and the control zone, while the absence of an antigen results in a line in the control zone only (Figure 11.4). This method is rapid and simple and thus can be used as a screening test in laboratories and as a field test at crime scenes to identify semen, saliva, and species (Table 11.1).

However, a false-negative result may be obtained if a sample contains a very high concentration of an antigen (Figure 11.5). Under this condition, the dye-labeled antibody will become saturated with the antigen to form antigen–antibody complexes. The unbound antigen will diffuse along with the



Figure 11.4 Immunochromatographic device. Positive and negative results are shown. (© Richard C. Li.)

Table 11.1 Common Immunochromatographic Assays for Forensic Applications

Assay	Antigen	Labeled Antibody	Immobilized Antibody	Forensic Application
ABAcard® HemaTrace® (Abacus Diagnostics)	Hemoglobin (Hb)	Monoclonal antihuman Hb antibody	Polyclonal antihuman Hb antibody	Blood and species identification
RSID™-Blood (Independent Forensics)	Glycophorin A (GPA)	Monoclonal antihuman GPA antibody	Monoclonal antihuman GPA antibody	Blood and species identification
RSID™-Saliva (Independent Forensics)	Human salivary α-amylase (HAS)	Monoclonal antihuman HAS antibody	Monoclonal antihuman HAS antibody[a]	Saliva identification
One-Step ABAcard PSA® (Abacus Diagnostics)	Prostate-specific antigen (PSA)	Monoclonal antihuman PSA antibody	Polyclonal antihuman PSA antibody	Semen identification
RSID™-Semen (Independent Forensics)	Semenogelin (Sg)	Monoclonal antihuman Sg antibody	Monoclonal antihuman Sg antibody[a]	Semen identification

[a] The epitope recognized by the immobilized antibody is different from that of the labeled antibody.



Figure 11.5 High-dose hook effect of immunochromatographic assay. (a) Ag (antigen) in sample is loaded in the sample well. (b) Ag binds to a labeled Ab (antibody) to form a labeled Ag–Ab complex. (c) At the test zone, free Ag binds to an immobilized Ab to form an unlabeled Ab–Ag complex and prevents the formation of a labeled Ab–Ag–Ab sandwich. (d) At the control zone, a labeled Ab binds to immobilized antiglobulin and is captured at the control zone. (© Richard C. Li.)

antigen–antibody complex toward the test zone. At the test zone, the unbound antigen will compete with the antigen–antibody complexes for the antibody immobilized at the test zone. Since the antigen is in excess, the unbound antigen binds to the immobilized antibody, preventing the formation of the antibody–antigen–antibody sandwich. The resulting reading appears as a negative result. This artifact is known as the *high-dose hook* effect. To prevent the high-dose hook effect, a smaller volume of sample can be applied, or the sample can be diluted to reduce the amount of antigen applied.

11.3 Secondary Binding Assays

11.3.1 Precipitation-Based Assays

These techniques are based on the precipitation reaction and are used primarily for species identification in forensic laboratories.

11.3.1.1 Immunodiffusion

Immunodiffusion is a passive method in which an antigen or an antibody or both are allowed to diffuse and therefore a gradient, from low to high concentration, is established for an antigen or an antibody or both. As a result, precipitation occurs due to the interaction between an antigen and an antibody. The assay can be carried out in a liquid or a semisolid medium such as agarose gel. The semisolid medium can stabilize the diffusion process and reduce interference such as convection, which is the movement of molecules within liquids. The two types are single immunodiffusion and double immunodiffusion.

11.3.1.1.1 Single Immunodiffusion

A concentration gradient is established for either an antigen or an antibody. One serology technique based on this principle is radial immunodiffusion—a single diffusion method in which a concentration gradient is established for an antigen. The antibody is uniformly distributed in the gel matrix (Figure 11.6). The antigen is loaded into a sample well and allowed to diffuse from the well into the gel until a precipitation reaction occurs. The precipitate ring around the well is observed; the area within the ring of precipitate is proportional to the amount of antigen loaded in the well. Standards using known concentrations of antigen can be included in the same assay along with the samples, and a standard curve can be plotted. The amounts of antigen in samples can then be quantified by comparing the results with the standard curve.

11.3.1.1.2 Double Immunodiffusion

The second type of assay is double diffusion in which a concentration gradient is established for both an antigen and an antibody. The most common examples are the ring assay and the Ouchterlony assay. The *ring assay* can be performed in a test tube or capillary tube (Figure 11.7). An antiserum, a denser phase, is placed in a small tube. An antigen solution is carefully layered on top of an antibody solution without mixing. Both the antigen and the antibody will diffuse toward each other. In a positive reaction, a ring of precipitate can be observed at the interface of the two solutions. A negative reaction is indicated by a lack of precipitation. The assay requires positive and negative controls along with questioned samples.



Figure 11.6 Radial immunodiffusion assay. (a) Immunodiffusion of antigens from a well into an antibody-containing gel. (b) Standard curve based on results of standards with known amounts of antigens. (© Richard C. Li.)



Figure 11.7 Ring assay. (© Richard C. Li.)

The *Ouchterlony assay* is named after the Swedish immunologist, Örjan Ouchterlony, who developed it. The assay can be performed in an agarose gel supported by a glass slide or polyester film (Figure 11.8). Wells are created by punching holes in the gel layer at desired locations. Often, a pattern with six wells surrounding a center well is used. The antibody is loaded in the central well while the questioned samples and the controls are loaded in the surrounding wells. The double diffusion of the antigen and the antibody from the wells is allowed to occur during incubation. If the reaction is positive, a precipitate line between wells can be observed at the end of incubation. The precipitate can be stained, enhancing visibility to aid observation. A single assay can compare more than one antigen to determine whether the antigens in question react the same way or differently with the antibody (see Chapter 7). This method is sometimes used to determine whether samples have come from the same or different origins.

11.3.1.2 Immunoelectrophoretic Methods

Diffusion techniques can be combined with electrophoresis to enhance test results. Electrophoresis separates molecules according to the differences in their electrophoretic mobility.

11.3.1.2.1 Immunoelectrophoresis

Immunoelectrophoresis (IEP) is a two-step procedure that can analyze a wide range of antigens. This technique uses electrophoresis to separate the antigen mixture prior to immunodiffusion (Figure 11.9). In the first step, the antigens in a sample are separated using agarose gel electrophoresis.



Figure 11.8 Ouchterlony assay. (© Richard C. Li.)



Figure 11.9 IEP assay. (a) Electrophoresis of antigens is carried out. (b) Various antigens are separated after electrophoresis. (c) Trough is cut. (d) Antibody is applied to the trough allowing diffusion to occur and forming precipitate lines. +, anode; −, cathode. (© Richard C. Li.)

Then, a trough is cut in the gel parallel to the array of antigens separated by electrophoresis. In the second step, an antibody is loaded in the trough and the gel is incubated for double diffusion. An arc-shaped precipitate line can be observed for a positive reaction. Multiple precipitate lines can occur if more than one antigen reacts with the antibody. The shapes, intensities, and locations of the precipitate lines of a known control and a questioned sample can be compared.

11.3.1.2.2 Crossed Immunoelectrophoresis

Crossed immunoelectrophoresis (CRIE), also known as two-dimensional IEP, is a modification of IEP. The first step utilizes electrophoresis to separate antigens contained in a sample (Figure 11.10). A strip of gel containing separated antigens is cut for the second round of electrophoresis. The gel including the gel strip is turned at a 90° angle and is further separated by a second-dimension electrophoresis. This drives the antigens from the gel strip into an agarose gel that contains uniformly distributed antibodies. Following the second-dimension electrophoresis, an arc-shaped precipitate line is formed. The area of the arc can be measured, and a sample can be identified by comparison with a known standard. This technique is more sensitive than IEP.

11.3.1.2.3 Rocket Immunoelectrophoresis

An antibody-containing agarose gel is used. The antigen is loaded into the well (Figure 11.11). Electrophoresis then drives the antigen from the well into the agarose gel. In a positive reaction,



Figure 11.10 CRIE assay. (a) Electrophoresis of antigens is carried out. (b) Various antigens are separated after electrophoresis. A strip of gel containing separated antigens is excised and then used for second-dimension electrophoresis. (c) As shown, second-dimension electrophoresis is carried out to drive the antigens into an antibody-containing gel; (d) arc-shaped precipitate lines are formed as a result. (© Richard C. Li.)



Figure 11.11 Rocket immunoelectrophoresis assay. Antigens are driven from the wells into an antibody-containing gel forming precipitate lines. (© Richard C. Li.)

a rocket-shaped precipitate line can be observed. The height of the rocket is in proportion to the amount of antigen in the sample. Quantitation can be achieved by comparing standards and the sample in the same gel.

11.3.1.2.4 Crossed-Over Immunoelectrophoresis

This technique is also known as counterimmunoelectrophoresis (CIE). Two arrays of opposing wells are created by punching holes in the agarose gel (Figure 11.12). The antibody and samples are loaded in opposing wells arranged by pairs. Electrophoresis is used to drive the antigen and the antibody toward each other. The wells containing the antibody should be proximal to the anode and the wells containing the samples should be proximal to the cathode. During gel electrophoresis, the antigen, which is usually negatively charged, migrates toward the anode. The antibody migrates in the opposite direction as a result of electroendosmosis—a phenomenon in which the movement of molecules is caused by fluid flow. A precipitate line is formed between the opposing wells if the antigen reacts with its specific antibody.

11.3.2 Agglutination-Based Assays

Agglutination reactions can be used as forensic serological assays such as for blood group typing (Chapter 18) and menstrual blood identification (Chapter 16). Agglutination assays are qualitative, indicating the absence or presence of antigens or antibodies. Semiquantitative results can be obtained by titration (diluting the antigen or antibody). Many types of agglutination reactions are available; only those used in forensic serology are discussed next.

Direct agglutination assays involve reactions in which an antibody interacts with antigens originally located on cell surfaces. In a *hemagglutination* reaction (Figure 11.13a), an antibody binds to the antigens located on erythrocytes. This method is used for the identification of blood types, for example, the testing of erythrocytes for ABO blood group typing. The assay can be carried out on a glass slide and the agglutination, as indicated by forming cell clumps, can be observed under a microscope (Chapter 18). The assay can also be carried out in a test tube. In a positive reaction, agglutinated cells are formed on the bottom of the test tube. Test tubes can also be centrifuged and then swirled to determine whether the cell clumps can be resuspended. Agglutinated cells cannot be resuspended. In a negative reaction, unagglutinated cells can be resuspended.

In *agglutination inhibition assays*, the presence of an antigen in question is indirectly detected (Figure 11.13b). If a known antigen is added to a mixture consisting of antigen-containing cells and antibodies, the added antigen will compete with the antigen located on the cell surfaces for antibody binding and inhibit the agglutination reaction. Another indirect agglutination assay is the absorption–elution assay (Chapter 18), which can be used for ABO blood group typing.

Passive agglutination assays are different from direct agglutination assays, in which the antigen is coated on the surface of carrier cells such as tannic acid–treated sheep erythrocytes. Tannic acid is considered to be a fixative. Treating with tannic acid can stabilize the carrier cells



Figure 11.12 Crossed-over immunoelectrophoresis assay. (© Richard C. Li.)


Ab
Agglutination
(a)
Ag
Inhibition
(b)
Ag
Ab
Agglutination
(c)

Figure 11.13 Agglutination-based assays. (a) Direct agglutination assay and (b) agglutination inhibition assay. Hemagglutination reactions are shown; antigens are located on erythrocytes. (c) Passive agglutination assay. (© Richard C. Li.)

for a subsequent coating of antigens. The carrier cells are then incubated with samples containing antigens. A coating of antigens can be formed on the surfaces of carriers. Such antigen-coated carrier cells can then be agglutinated using an antibody that is specific to the absorbed antigens (Figure 11.13c).

11.4 DNA Methylation Assays for Bodily Fluid Identification

In the eukaryotic genome, methylation occurs at the cytosine residues commonly in the CpG dinucleotide sequences of both DNA strands. The "p" in CpG refers to the phosphodiester bond between cytosine and guanine. Cytosine methylation is carried out *in vivo* by methyltransferase (DNMT). DNMT catalyzes the transfer of a methyl group (CH_3) from S-adenosylmethionine (SAM) to the C^5 position of cytosine (Figure 11.14). As a result, cytosine is converted to 5-methylcytosine. Cytosine methylation is observed throughout the eukaryotic genomes in both the coding and intergenic regions located between genes. However, cytosine methylation is rare at CpG islands, which are stretches of DNA containing a high frequency of CpG dinucleotides in the regulatory regions of genes (Figure 11.15). It is implicated that cytosine methylation alters the chromatin structure and causes chromatin condensation. As a result, gene expression is usually inhibited by cytosine methylation.

Genomic loci, known as *tissue-specific differentially methylated regions* (TDMRs), have been identified. TDMRs show differential DNA methylation patterns between different tissues. For example, semen-specific TDMRs are consistently hypomethylated in spermatozoa, which can be used to identify semen samples. Other TDMRs display varying degrees of methylation in different types of bodily fluids. This suggests that differential DNA methylation assays may be potentially useful for bodily fluid identification.

The detection of DNA methylation can be carried out by a number of methods. *Methylation-sensitive restriction enzyme digestion polymerase chain reaction* (MSRE-PCR) can be used for the



Figure 11.14 Eukaryotic cytosine methylation catalyzed by methyltransferase.



Figure 11.15 Methylation at the cytosine residues in CpG dinucleotide sequences. Note that the CpG dinucleotide sequences are usually unmethylated in the promoter regions. Black circle: methylated. Clear circle: unmethylated. Gray circle: partial methylated. (© Richard C. Li.)

rapid detection of DNA methylation. This method utilizes the *methylation-sensitive restriction enzyme* (MSRE). MSREs cleave DNA at unmethylated restriction sites, but they are not able to cleave once a cytosine residue is methylated. Thus, the methylated DNA remains intact. After PCR amplification, the methylated DNA is amplified and the amplicon is detected. In contrast, the unmethylated DNA is cleaved by the MSRE and cannot be amplified (Figure 11.16). *Bisulfite sequencing* is another widely used method. The genomic DNA is treated with sodium bisulfite, which catalyzes the hydrolytic deamination of unmethylated cytosines (Figure 11.17). As a result, unmethylated cytosines are converted to uracils, while methylated cytosines are resistant to conversion and remain unchanged. Next, uracils are replaced by thymines during PCR. After sequencing, the methylation sites can be deduced at a single-nucleotide resolution by comparing them with the reference sequence (Figure 11.18). *Methyl-DNA immunoprecipitation* (MeDIP) is a useful method for isolating methylated DNA. In this method, DNA is first sheared into fragments. The fragmented DNA is then treated with an antimethylcytosine antibody that binds to methylated cytosines. Methylated DNA fragments can then be isolated by immunoprecipitation for further analysis (Figure 11.19).



Figure 11.16 Methylation-sensitive restriction enzyme digestion PCR (MSRE-PCR) for the detection of DNA methylation. This method utilizes the methylation-sensitive restriction enzyme (MSRE) such as *Hha*I. *Hha*I cleaves DNA at the unmethylated sequence GCGC but is not able to cleave once a cytosine residue is methylated (GCmGC). The *Hha*I-treated DNA is then PCR amplified. The *Hha*I uncleaved DNA results in an amplicon, indicating the presence of a methylated cytosine in the sequence. The *Hha*I cleaved DNA cannot be amplified, indicating the absence of methylated cytosine in the sequence. Me, 5-methylcytosine site; red arrow, PCR primers. (Adapted from Frumkin, D. et al., *Forensic Sci Int Genet*, 5, 517–524, 2011.)



Figure 11.17 Bisulfite conversion of 5-methylcytosine.



Figure 11.18 Schematic illustration of bisulfite sequencing of cytosine methylation. In a deamination reaction, unmethylated cytosines are converted to uracil. PCR and DNA sequencing are then carried out. The retention of C indicates that the site was methylated; the conversion of C to T indicates that the site was unmethylated in the DNA sample. Me, 5-methylcytosines site. (© Richard C. Li)



Figure 11.19 Methylated DNA immunoprecipitation (MeDIP) for the detection of methylated DNA. Genomic DNA is randomly and mechanically sheared into fragments. Fragments are then denatured to single-stranded DNA. The fragments containing the methylated region can be immunoprecipitated using an antibody that specifically recognizes 5-methylcytosine. The methylated DNA sequence in the immunoprecipitated fragments can then be determined by DNA sequencing and methylation analysis. Me, 5-methylcytosine site; 5mC Ab, 5-methylcytosine antibody. (© Richard C. Li.)

11.5 Forensic Applications of RNA-Based Assays and RNA Profiling

11.5.1 Messenger RNA-Based Assays

mRNA-based assays have been developed to identify bodily fluids for forensic investigation. In forensic pathological investigation, they can potentially be used for wound age estimation and the age of biological stains. The assays are based on the expression of certain genes in certain cell or tissue types. Candidate tissue-specific genes that may be useful for the identification of bodily fluids have been identified. Thus, the techniques that are used in the identification of bodily fluids are based on the detection of specific types of mRNA that are expressed exclusively in certain cells. The *tissue-specific genes* that are utilized for bodily fluid identification are summarized in Table 11.2. Additionally, *reference genes* that are constitutively expressed housekeeping genes are utilized as internal controls. The amount of mRNA can be assessed by normalizing the target gene to the expression level of the reference genes. Compared with conventional assays that are used for bodily fluid identification, the mRNA-based assay has higher specificity and is amenable to automation. However, one limitation is that the mRNA is unstable due to degradation by

Table 11.2 Representative Markers of mRNA-Based Assays for Bodily Fluid Identification

Bodily Fluid	Gene Symbol	Description
Blood	*ALAS2*	Aminolevulinatesynthase 2
	AMICA1	Adhesion molecule, interacts with CXADR antigen 1
	ANK1	Ankyrin1
	CD3G	CD3 gammamolecule
	CD93	CD93 molecule
	HBA1	Alpha 1 hemoglobin
	HBB	Beta hemoglobin
	PBGD	Porphobilinogen deaminase
	SPTB	Beta spectrin
Saliva	*HTN3*	Histatin 3
	MUC7	Mucin 7
	STATH	Statherin
Semen	*KLK3*	Kallikrein 3 (prostate-specific antigen)
	PRM1	Protamine 1
	PRM2	Protamine 2
	SEMG1	Semenogelin 1
	TGM4	Transglutaminase 4
Vaginal secretions	*CYP2B7P1*	Cytochrome P450, family 2, subfamily B, polypeptide 7 pseudogene 1
	DKK4	Dickkopf homolog 4
	FUT6	Fucosyltransferase 6
	HBD1	Beta defensin 1
	IL19	Interleukin 19
	MUC4	Mucin 4
	MYOZ1	Myozenin 1
	SFTA2	Surfactant associated 2
Menstrual blood	*MMP7*	Matrix metalloproteinase 7
	MMP11	Matrix metalloproteinase 11
Skin	*CDSN*	Corneodesmosin
	LOR	Loricrin

(*continued*)

Table 11.2 (Continued) Representative Markers of mRNA-Based Assays for Bodily Fluid Identification

Bodily Fluid	Gene Symbol	Description
Reference gene	*18S rRNA*	18S ribosomal RNA
	ACTB	Beta actin
	G6PDH	Hexose-6-phosphate dehydrogenase
	RPS15	Ribosomal protein S15

Sources: Adapted from Bauer, M. and Patzelt, D., *J Forensic Sci*, 47, 1278–1282, 2002; Hanson, E.K. and Ballantyne, J., *Sci Justice*, 53, 14–22, 2013; Lindenbergh, A., Maaskant, P., and Sijen, T., *Forensic Sci Int Genet*, 7, 159–166, 2013; Nussbaumer, C., Gharehbaghi-Schnell, E., and Korschineck, I., *Forensic Sci Int*, 157, 181–186, 2006.

endogenous ribonucleases. Additionally, bodily fluid stains collected from crime scenes are often exposed to ultraviolet (UV) light, moisture, and high temperature, which can promote mRNA degradation. Nevertheless, the successful detection of mRNA from aged samples is possible.

11.5.2 MicroRNA-Based Assays

The biological function of microRNAs (miRNAs) is to regulate gene expression. The mature miRNA strand associated with the RNA-induced silencing complex (RISC) binds to its target mRNA. In animal cells, the mature miRNA forms a base pairing with its complementary sequence of the *miRNA responsive element* (MRE) within the 3′ untranslated regions (3′UTRs) of the target mRNA (Figure 11.20). A single miRNA can bind different mRNA transcripts encoded by multiple genes. Animal miRNAs usually form a base pairing with their target mRNAs through partial complementary sequences, which lead to translation repression to inhibit protein synthesis. If the base pairing is exactly complementary to its target mRNA sequence, then the cleavage and the degradation of the target mRNA occurs. As a result, the synthesis of the protein encoded by the mRNA is reduced. Thus, miRNAs play important roles in cellular function.

miRNAs have potential applications in forensic identification. Recent studies have revealed that miRNAs can be detected from various bodily fluids such as blood, saliva, semen, vaginal secretions, and menstrual blood. The type of miRNA expressed is not exclusively tissue- or cell-type specific. However, the expression patterns of specific miRNAs are unique for various bodily fluids. Thus, a bodily fluid in question can potentially be identified using multiple differentially expressed miRNAs as markers (Table 11.3). miRNA markers for bodily fluid identification have their advantages compared with those of mRNA. Mature miRNAs are much



Figure 11.20 Schematic illustration of the roles of miRNA in translational inhibition. In animal cells, miRNAs bind to 3′UTR of their target mRNA with partially complementary Watson–Crick base pairing. As a result, the binding of miRNA to the target mRNA inhibits translation of the target mRNA. Eukaryotic 40S and 60S ribosomal subunits are shown. (© Richard C. Li.)

Table 11.3 Differentially Expressed miRNA Markers for Bodily Fluid Identification

Biological Fluid	miRNA Set
Blood	miR16; miR451
	miR16; miR486
	miR20a; miR106a; miR144; miR185
	miR126; miR150; miR451
Semen	miR10b; miR135b
	miR10a; miR135a; miR943; miR507; miR891a
Saliva	miR205; miR658
	miR200c; miR203; miR205
Vaginal secretions	miR124a; miR372
Menstrual blood	miR214
	miR412; miR451
Reference gene	*RNU6-2* (U6 small nuclear 2 RNA)

Sources: Adapted from Courts, C. and Madea, B., *J Forensic Sci*, 56, 1464–1470, 2011; Hanson, E.K., Lubenow, H., and Ballantyne, J., *Anal Biochem*, 387, 303–314, 2009; Wang, Z. et al., *Forensic Sci Int Genet*, 7, 116–123, 2013; Zubakov, D. et al., *Int J Legal Med*, 124, 217–226, 2010.

smaller, approximately 21–23 nucleotides in length, than mRNA. As a result, miRNAs are less susceptible to degradation and more stable than mRNAs. Additionally, the sensitivity of the miRNA-based method is much higher than that of the mRNA-based methods.

11.6 Proteomic Approaches Using Mass Spectrometry for Bodily Fluid Identification

The forensic application of proteomic approaches is to identify biomarker proteins derived from bodily fluids to determine the type of bodily fluid in question for forensic investigations. Mass spectrometry (MS) is a highly sensitive and rapid technique for protein identification from complex biological samples.

11.6.1 Mass Spectrometric Instrumentation for Protein Analysis

A mass spectrometer is an analytical technique to identify a molecule by measuring the ratio of the mass (m) to the charge (z) of a charged molecule (Figure 11.21). A typical mass spectrometer instrument analyzes ionized molecules while in its gas phase. A mass spectrometer consists of an *ion source* that converts analytes into gaseous phase ions, through a process known as *ionization*, by gaining a positive or a negative charge from a neutral species. The ions are then introduced into the *mass analyzer* of a mass spectrometer, where ions are accelerated under electric fields and separated based on their m/z ratio. The separated ions are detected by an *ion detector* that records the number of ions at each m/z value. The result of molecular ionization,



Figure 11.21 Diagram of tandem mass spectrometry. For the initial mass analysis of thermolabile analytes including peptides and proteins, soft ionization techniques such as matrix-assisted laser desorption ionization (MALDI) and electrospray ionization (ESI) can be used to produce original ions. MALDI utilizes a laser beam to trigger ionization and facilitate the vaporization of the analyte. In the ESI method, a fine mist of droplets is formed in the presence of a high electric field, producing charged ions. In the first round of mass analysis, ions are separated based on their *m/z* ratio. A particular ion, called a precursor ion, is then selected for fragmentation, generating product ions. The fragmentation can be carried out using collision techniques such as collision-induced dissociation (CID) by multiple collisions with rare gas atoms. Additionally, a new fragmentation technique, electron-capture dissociation (ECD), can be used in which the fragmentation is induced through the capture of a thermal electron by a protonated peptide cation. The product ions are analyzed by the second round of mass analysis and detected by an ion detector. MS, mass analyzer. (© Richard C. Li.)

ion separation, and ion detection is a spectrum that can be used to determine the mass (or molecular weight) and potentially the structure of the molecule.

Furthermore, biomarker proteins can be identified by *peptide sequencing* using the tandem mass spectrometry (MS/MS) mode of operation in which a mass spectrometer uses two or more mass analyzers. After an initial mass analysis, individual peptide ions in the mass spectrum can be selected. The selected ions are known as *precursor ions*. A precursor ion is then subjected to a second round of fragmentation through collision and is broken into smaller ions known as *product ions*. The resulting product ions are further analyzed by MS. Thus, the corresponding protein can be identified through searching a protein database, based on the mass of a specific peptide obtained.

11.6.2 Analysis Strategies for Protein Identification

To date, various MS-based protein identification strategies have been developed, which can be divided into two categories: “top-down” and “bottom-up” strategies (Figure 11.22). In the *top-down* strategy, intact proteins in a complex mixture are fractionated and separated into less complex protein mixtures or single proteins. Intact proteins are then analyzed using MS. A liquid chromatography–mass spectrometry (LC–MS) system can be used for such an application. The advantage of this approach is that an entire protein is analyzed for identification purposes. However, the throughput and efficiency of this approach is still a major challenge for large-scale sample analysis in forensic applications.

The *bottom-up* strategy is commonly used for high-throughput analysis of small peptides derived from highly complex samples. Current MS usually cannot resolve the mass measurement of large proteins; rather, MS is ideal for the analysis of small peptides. One approach is the *sort-then-break* approach in which proteins in a complex mixture are first isolated and then enzymatically cleaved. The target proteins are isolated from their complex biological source using 1-D or 2-D gel electrophoresis (Chapter 18). The isolated proteins are then enzymatically


Complex protein sample
Top-down
Bottom-up
Sort-then-break
Break-then-sort (shotgun)
Fractionation separation (e.g., LC)
Fractionation separation (e.g., 2-D gel)
Enzymatic cleavage
Single proteins
Less complex mixture
Single proteins
Small peptide mixture
Enzymatic cleavage
Fractionation separation (e.g., LC)
Small peptides (~15 amino acids)
Small peptides (~15 amino acids)
MS/MS analysis
Identifying target protein

Figure 11.22 Top-down and bottom-up strategies for MS-based protein identification. LC, liquid chromatography; MS/MS, tandem mass spectrometry. (© Richard C. Li.)

cleaved into small peptides, approximately 15 amino acids in length, using proteases such as trypsin. These peptides are then analyzed by peptide sequencing using tandem MS to identify the target protein.

Break-then-sort, also known as the *shotgun* approach, is another approach of the bottom-up strategy. In this approach, proteins are cleaved first and the resulting peptide mixture is then separated by LC and analyzed by tandem MS (usually coupled to the LC). In a complex mixture, a peptide mass measurement alone is not sufficient for the identification of a target protein. Database searches are carried out utilizing software that compares the observed MS peptide spectra against all candidate spectra of the proteins that are present in a protein sequence (or translated from genomic DNA sequences) database for possible matches. Thus, a biomarker protein can be identified.

11.7 Microbial DNA Analysis for Bodily Fluid Identification

Human bodies harbor a large number of microbes. It is estimated that there are over 10 times more microbial cells than human cells in and on the human body, in the nose, mouth, throat, intestine, vagina, and skin. This microbial community is referred to as the human *microbiota*.

It is known that the microbiota has an important influence on human health. A decade ago, the concept of the *microbiome* was proposed by Nobel laureate Joshua Lederberg to identify and characterize the microbiota, their genomes, and their environmental interactions in a defined community. Traditionally, the studies of microbial genomes rely on cultivated individual species. The disadvantage of cultivation-based methods, however, is that large numbers of microbial species cannot be successfully isolated because many microbial species require specific growth conditions. Based on the advances in DNA sequencing technologies, a new approach, known as *metagenomics*, has been developed. Instead of studying the genome of an individual cultivated microbial species, metagenomics allows the study of the microbial genome of complete microbial communities harvested directly from natural environments. Metagenomics has been a powerful tool to analyze the human microbiome. Recently, human microbiota have been surveyed, revealing that microbial diversity is greatest in the teeth and the intestines, intermediate on the skin and the inside surface of the cheek, and lowest in the vagina (Table 11.4). More interestingly, each habitat is characterized by a small number of highly predominant bacterial taxa. The predominant taxa of each habitat can potentially be utilized for the forensic analysis of biological evidence. Bodily fluids identification is an important task in the forensic analysis of biological evidence. The detection of predominant taxa of bacteria can aid in the forensic identification of a particular type of bodily fluid (Table 11.4).

Table 11.4 Representative Microbiota that are Potentially Can Be Used for Forensic Identification

Body Habitats	Estimated Number of Microbial Species	Predominent Taxa	Potential Forensic Applications	DNA Marker	Further Reading
Cheek	800	*Streptococcus* spp.	Saliva identification	*gtf*	Nakanishi et al. (2011)
			Expirated blood	*gtf*	Donaldson et al. (2010)
				16S rRNA	Power et al. (2010)
Vagina	300	*Lactobacillus* spp.	Vaginal secretion identification	16S rRNA	Akutsu et al. (2012)
				16S–23S ISR	Fleming and Harbison (2010)
					Giampaoli et al. (2012)
Gastrointestinal tract	4000	*Bacteroides* spp.	Fecal matter identification	*rpoB*	Nakanishi et al. (2013)
Skin	1000	*Staphylococcus* spp.	Touched evidence identification	16S rRNA	Fierer et al. (2010)



Figure 11.23 Schematic diagram of an *Escherichia coli* rRNA operon. *E. coli* has seven rRNA operons. A typical rRNA operon is shown. The rRNA operon encodes for three ribosomal RNA (rRNA) genes: the 5S and 23S genes code for the large ribosomal subunit, while the 16S gene encodes for the small ribosomal subunit. *E. coli* encodes one tRNA gene in the rRNA operon. The intergenic spacer regions (ISRs) and the promoter and terminator sequences are also shown. The rRNA operon is transcribed into a single precursor RNA transcript that is cleaved into separate rRNA and tRNA transcripts. The diagram is not to scale to the physical map of rRNA operons. (© Richard C. Li.)

The detection of bacteria can be achieved by utilizing DNA markers. The most commonly used DNA markers are the essential genes present in all bacterial species. These markers have highly variable regions that can be used to distinguish various bacterial species. The DNA sequences within these variable regions can also suggest taxonomic relationships between different taxa. Additionally, DNA markers contain conserved regions that are necessary for use as primer-binding sites for PCR-based detection.

For example, the rRNA genes (Figure 11.23), encoding for the ribosomal RNA, are conserved in all living organisms including bacteria. The bacterial rRNA operon contains three rRNA genes: the 5S and 23S rRNA genes encode the RNA components of the large subunit of the ribosome, while the 16S rRNA gene encodes the RNA component of the small subunit of the ribosome. The 16S rRNA gene is the most commonly used marker for the taxonomic identification of bacteria. The bacterial 16S rRNA genes are similar in length, approximately 1.5 kb. They contain highly conserved regions that can be used as primer-binding sites for the amplification of the adjacent DNA regions. Additionally, they contain variable regions that allow for taxonomic identification. In forensic applications, they are used as a marker for the identification of vaginal bacteria as an indicator of vaginal secretions (Chapter 16). However, the number of variable regions in the 16S rRNA genes of some bacteria species is limited. Furthermore, closely related species have high levels of sequence similarity to the 16S rRNA genes. Thus, the 16S rRNA gene marker is not adequate for distinguishing closely related species.

DNA markers of bacteria identification can also be located in noncoding regions of DNA. The *intergenic spacer region* (ISR) between the 16S rRNA and 23S rRNA genes in the rRNA operon is another commonly used marker. The 16S–23S rRNA ISR contains both length and sequence variations between species. These variations are partially caused by the number and type of tRNA genes that this region of operon contains. For example, most gram-negative bacteria contain both a copy of the tRNA^{ala} and the tRNA^{ile} genes, while some contain only a copy of the tRNA^{glu} gene. In contrast, most gram-positive bacteria have no tRNA gene; some contain either a copy of the tRNA^{ala} gene or the tRNA^{ile} gene or both. Thus, heterogeneity in the length and in the sequence of the 16S–23S rRNA ISR allows bacteria to be identified at the species level.

In addition to rRNA genes, many other genes are utilized as DNA markers for bacterial species identification. For example, the *rpoB* gene encodes the β subunit of bacterial RNA polymerase and is used as a marker for the forensic identification of fecal matter (Chapter 17). The sequence variation of the *rpoB* gene allows the distinguishing of species when they are not distinguishable, using 16S rRNA gene sequences. Several oral streptococcal species that produce extracellular polysaccharides contain the *gtf* gene, which encodes glucosyltransferase. Thus, the *gtf* gene is a useful marker for oral streptococcal species identification as a potential indicator of saliva in forensic investigations. However, this marker cannot be used to identify bacteria other than *streptococcus*. Nevertheless, combining several DNA markers can be used for the identification of bacteria species.

11.8 Nondestructive Assays for the Identification of Bodily Fluids

Most of the bodily fluid identification techniques mentioned previously consume a portion of the evidence. When the amount of sample evidence is very limited, such destructive assays may consume the evidence that is also needed for subsequent forensic DNA analysis. Moreover, most of these tests are used for a single type of bodily fluid. Tests for multiple bodily fluids in question will consume additional amounts of the evidence. Therefore, nondestructive identification techniques are highly desired. Additionally, it is important to develop an assay that can be utilized to test multiple types of bodily fluids. Furthermore, a portable device that can identify bodily fluids at a crime scene is very useful. It provides investigators with test results immediately to aid the crime scene investigations. Two techniques have been developed that can potentially be used for nondestructive bodily fluid identification: fluorescence spectroscopy and Raman spectroscopy.

Fluorescence spectroscopy is one example of a nondestructive technique. Fluorescence is the emission of light by a fluorophore. A fluorophore is a moiety in a molecule that fluoresces on absorbing the energy from an excitation light source or radiation. The emitted light usually has a longer wavelength and lower energy than the absorbed radiation. Constituents present in bodily fluids, such as nucleic acids, proteins, lipids, and metabolites, can exhibit fluorescence. The unique composition of a bodily fluid emits characteristic emission spectra, thus making it identifiable. Using multiple wavelengths of an excitation light source, fluorescent emissions at a wide range of wavelengths can be detected, which allows for the identification of various bodily fluids. This technique is sensitive and rapid. It does not utilize chemical reagents and the detection does not require physical contact with a sample. After identification, the same biological sample can be used for forensic DNA analysis. Additionally, portable fluorescence instruments can potentially be used at a crime scene for bodily fluid identification. However, it is not clear if exposure to an excitation light source can damage DNA evidence.

Raman spectroscopy is another example of a nondestructive technique. Raman spectroscopy utilizes a near-infrared excitation light source and measures the scattering of laser light caused by the vibrating molecules of a sample. A typical Raman spectrum provides information about the molecular structure and the "signature" based on the properties of the constituents of a sample. Thus, it is possible to obtain unique Raman spectra for a particular type of bodily fluid. Raman spectroscopy is highly sensitive. The measurements can be carried out on very small amounts of sample, ranging from a few picoliters to femtoliters. This technique does not require any chemical reagent. Additionally, it does not consume the sample, which can be used for subsequent DNA analysis. Raman spectroscopy has been utilized for various forensic purposes including the identification of drugs, trace evidence such as fibers, and questioned document evidence such as inks and paints. It can potentially be used for the nondestructive identification of various bodily fluids. A portable Raman spectrometer will allow bodily fluids to be identified at crime scenes.

Bibliography

Aaspõllu, A., et al., Can microbes on skin help linking persons and crimes? *Forensic Sci Int Genet Suppl Series*, 2011, **3**(1): e269–e270.

Akutsu, T., et al., Detection of bacterial 16S ribosomal RNA genes for forensic identification of vaginal fluid. *Leg Med*, 2012, **14**(3): 160–162.

Allen, S.M., An enzyme linked immunosorbent assay (ELISA) for detection of seminal fluid using a monoclonal antibody to prostatic acid phosphatase. *J Immunoassay*, 1995, **16**(3): 297–308.

Alvarez, M., J. Juusola, and J. Ballantyne, An mRNA and DNA co-isolation method for forensic casework samples. *Anal Biochem*, 2004, **335**(2): 289–298.

Amin, K.M., et al., The exon-intron organization of the human erythroid beta-spectrin gene. *Genomics*, 1993, **18**(1): 118–125.

An, J.H., et al., Body fluid identification in forensics. *BMB Rep*, 2012, **45**(10): 545–553.

An, J.H., et al., DNA methylation-specific multiplex assays for body fluid identification. *Int J Legal Med*, 2013, **127**(1): 35–43.

Anderson, J.R., The agglutination of sensitised red cells by antibody to serum, with special reference to non-specific reactions. *Br J Exp Pathol*, 1952, **33**(5): 468–483.

Bauer, M., RNA in forensic science. *Forensic Sci Int Genet*, 2007, **1**(1): 69–74.

Bauer, M. and D. Patzelt, Evaluation of mRNA markers for the identification of menstrual blood. *J Forensic Sci*, 2002, **47**(6): 1278–1282.

Bauer, M. and D. Patzelt, Protamine mRNA as molecular marker for spermatozoa in semen stains. *Int J Legal Med*, 2003, **117**(3): 175–179.

Bauer, M., A. Kraus, and D. Patzelt, Detection of epithelial cells in dried blood stains by reverse transcriptase-polymerase chain reaction. *J Forensic Sci*, 1999, **44**(6): 1232–1236.

Benschop, C.C.G., et al., Vaginal microbial flora analysis by next generation sequencing and microarrays; can microbes indicate vaginal origin in a forensic context? *Int J Legal Med*, 2012, **126**(2): 303–310.

Berti, A., et al., Expression of seminal vesicle-specific antigen in serum of lung tumor patients. *J Forensic Sci*, 2005, **50**(5): 1114–1115.

Black, C.M., et al., Multicenter study of nucleic acid amplification tests for detection of *Chlamydia trachomatis* and *Neisseria gonorrhoeae* in children being evaluated for sexual abuse. *Pediatr Infect Dis J*, 2009, **28**(7): 608–613.

Bocklandt, S., et al., Epigenetic predictor of age. *PLoS One*, 2011, **6**(6): e14821.

Bowden, A., R. Fleming, and S. Harbison, A method for DNA and RNA co-extraction for use on forensic samples using the Promega DNA IQ™ system. *Forensic Sci Int Genet*, 2011, **5**(1): 64–68.

Brenig, B., J. Beck, and E. Schutz, Shotgun metagenomics of biological stains using ultra-deep DNA sequencing. *Forensic Sci Int Genet*, 2010, **4**(4): 228–231.

Brzezinski, J.L. and D.L. Craft, Characterization of microorganisms isolated from counterfeit toothpaste. *J Forensic Sci*, 2012, **57**(5): 1365–1367.

Chu, Z.L., et al., Erythroid-specific processing of human beta spectrin I pre-mRNA. *Blood*, 1994, **84**(6): 1992–1999.

Counsil, T.I. and J.L. McKillip, Forensic blood evidence analysis using RNA targets and novel molecular tools. *Biologia*, 2010, **65**(2): 175–182.

Courts, C. and B. Madea, Micro-RNA—A potential for forensic science? *Forensic Sci Int*, 2010, **203**(1–3): 106–111.

Courts, C. and B. Madea, Specific micro-RNA signatures for the detection of saliva and blood in forensic body-fluid identification. *J Forensic Sci*, 2011, **56**(6): 1464–1470.

Courts, C. and B. Madea, [Ribonucleic acid—Importance in forensic molecular biology]. *Rechtsmedizin*, 2012, **22**(2): 135–144.

Courts, C., M. Grabmuller, and B. Madea, Dysregulation of heart and brain specific micro-RNA in sudden infant death syndrome. *Forensic Sci Int*, 2013, **228**(1–3): 70–74.

Culliford, B.J., Precipitin reactions in forensic problems. A new method for precipitin reactions on forensic blood, semen and saliva stains. *Nature*, 1964, **201**: 1092–1093.

Cummings, C.A. and D.A. Relman, Genomics and microbiology. Microbial forensics— "cross-examining pathogens". *Science*, 2002, **296**(5575): 1976–1979.

Donaldson, A.E., et al., Using oral microbial DNA analysis to identify expirated bloodspatter. *Int J Legal Med*, 2010, **124**(6): 569–576.

Elkins, K.M., Rapid presumptive “fingerprinting” of body fluids and materials by ATR FT-IR spectroscopy. *J Forensic Sci*, 2011, **56**(6): 1580–1587.

Ferguson, L.S., et al., Direct detection of peptides and small proteins in fingermarks and determination of sex by MALDI mass spectrometry profiling. *Analyst*, 2012, **137**(20): 4686–4692.

Fierer, N., et al., Forensic identification using skin bacterial communities. *Proc Natl Acad Sci U S A*, 2010, **107**(14): 6477–6481.

Fleming, R.I. and S. Harbison, The development of a mRNA multiplex RT-PCR assay for the definitive identification of body fluids. *Forensic Sci Int Genet*, 2010, **4**(4): 244–256.

Fleming, R.I. and S. Harbison, The use of bacteria for the identification of vaginal secretions. *Forensic Sci Int Genet*, 2010, **4**(5): 311–315.

Fordyce, S.L., et al., Long-term RNA persistence in postmortem contexts. *Investig Genet*, 2013, **4**(1): 7.

Frascione, N., et al., Detection and identification of body fluid stains using antibody-nanoparticle conjugates. *Analyst*, 2012, **137**(2): 508–512.

Frumkin, D., et al., Authentication of forensic DNA samples. *Forensic Sci Int Genet*, 2010, **4**(2): 95–103.

Frumkin, D., et al., DNA methylation-based forensic tissue identification. *Forensic Sci Int Genet*, 2011, **5**(5): 517–524.

Gao, L.L., et al., Application and progress of RNA in forensic science. *J Forensic Med*, 2011, **27**(6): 455–459.

Gauvin, J., et al., Forensic pregnancy diagnostics with placental mRNA markers. *Int J Legal Med*, 2010, **124**(1): 13–17.

Gelmini, S., et al., Real-time quantitative reverse transcriptase-polymerase chain reaction (RT-PCR) for the measurement of prostate-specific antigen mRNA in the peripheral blood of patients with prostate carcinoma using the taqman detection system. *Clin Chem Lab Med*, 2001, **39**(5): 385–391.

Giampaoli, S., et al., Molecular identification of vaginal fluid by microbial signature. *Forensic Sci Int Genet*, 2012, **6**(5): 559–564.

Gipson, I.K., et al., Mucin genes expressed by human female reproductive tract epithelia. *Biol Reprod*, 1997, **56**(4): 999–1011.

Gipson, I.K., et al., MUC4 and MUC5B transcripts are the prevalent mucin messenger ribonucleic acids of the human endocervix. *Biol Reprod*, 1999, **60**(1): 58–64.

Goga, H., Comparison of bacterial DNA profiles of footwear insoles and soles of feet for the forensic discrimination of footwear owners. *Int J Legal Med*, 2012, **126**(5): 815–823.

Grskovic, B., et al., DNA methylation: The future of crime scene investigation? *Mol Biol Rep*, 2013, **40**(7): 4349–4360.

Gubin, A.N. and J.L. Miller, Human erythroid porphobilinogen deaminase exists in 2 splice variants. *Blood*, 2001, **97**(3): 815–817.

Gunn, A. and S.J. Pitt, Microbes as forensic indicators. *Trop Biomed*, 2012, **29**(3): 311–330.

Haas, C., E. Hanson, and J. Ballantyne, Capillary electrophoresis of a multiplex reverse transcription-polymerase chain reaction to target messenger RNA markers for body fluid identification. *Methods Mol Biol*, 2012, **830**: 169–183.

Haas, C., et al., mRNA profiling for body fluid identification by reverse transcription endpoint PCR and realtime PCR. *Forensic Sci Int Genet*, 2009, **3**(2): 80–88.

Haas, C., et al., mRNA profiling for the identification of sperm and seminal plasma. *Forensic Sci Int Genet Suppl Series*, 2009, **2**(1): 534–535.

Haas, C., et al., Collaborative EDNAP exercises on messenger RNA/DNA co-analysis for body fluid identification (blood, saliva, semen) and STR profiling. *Forensic Sci Int Genet Suppl Series*, 2011, **3**(1): e5–e6.

Haas, C., et al., MRNA profiling for the identification of blood—Results of a collaborative EDNAP exercise. *Forensic Sci Int Genet*, 2011, **5**(1): 21–26.

Haas, C., et al., Selection of highly specific and sensitive mRNA biomarkers for the identification of blood. *Forensic Sci Int Genet*, 2011, **5**(5): 449–458.

Haas, C., et al., RNA/DNA co-analysis from blood stains—Results of a second collaborative EDNAP exercise. *Forensic Sci Int Genet*, 2012, **6**(1): 70–80.

Haas, C., et al., RNA/DNA co-analysis from human menstrual blood and vaginal secretion stains: Results of a fourth and fifth collaborative EDNAP exercise. *Forensic Sci Int Genet*, 2014, **8**(1): 203–212.

Haas, C., et al., RNA/DNA co-analysis from human saliva and semen stains—Results of a third collaborative EDNAP exercise. *Forensic Sci Int Genet*, 2013, **7**(2): 230–239.

Hampson, C., J. Louhelainen, and S. McColl, An RNA expression method for aging forensic hair samples. *J Forensic Sci*, 2011, **56**(2): 359–365.

Hanson, E.K. and J. Ballantyne, Circulating microRNA for the identification of forensically relevant body fluids. *Methods Mol Biol*, 2013, **1024**: 221–234.

Hanson, E.K. and J. Ballantyne, Highly specific mRNA biomarkers for the identification of vaginal secretions in sexual assault investigations. *Sci Justice*, 2013, **53**(1): 14–22.

Hanson, E.K., H. Lubenow, and J. Ballantyne, Identification of forensically relevant body fluids using a panel of differentially expressed microRNAs. *Anal Biochem*, 2009, **387**(2): 303–314.

Hanson, E., et al., Identification of skin in touch/contact forensic samples by messenger RNA profiling. *Forensic Sci Int Genet Suppl Series*, 2011, **3**(1): e305–e306.

Hanson, E., et al., Specific and sensitive mRNA biomarkers for the identification of skin in 'touch DNA' evidence. *Forensic Sci Int Genet*, 2012, **6**(5): 548–558.

Harteveld, J., A. Lindenbergh, and T. Sijen, RNA cell typing and DNA profiling of mixed samples: Can cell types and donors be associated? *Sci Justice*, 2013, **53**(3): 261–269.

Heinrich, M., et al., Real-time PCR detection of five different "endogenous control gene" transcripts in forensic autopsy material. *Forensic Sci Int Genet*, 2007, **1**(2): 163–169.

Hochmeister, M.N., et al., Evaluation of prostate-specific antigen (PSA) membrane test assays for the forensic identification of seminal fluid. *J Forensic Sci*, 1999, **44**(5): 1057–1060.

Hochmeister, M.N., et al., Validation studies of an immunochromatographic 1-step test for the forensic identification of human blood. *J Forensic Sci*, 1999, **44**(3): 597–602.

Hsu, L., et al., Amplification of oral streptococcal DNA from human incisors and bite marks. *Curr Microbiol*, 2012, **65**(2): 207–211.

Iida, R., T. Yasuda, and K. Kishi, Identification of novel fibronectin fragments detected specifically in juvenile urine. *FEBS J*, 2007, **274**(15): 3939–3947.

Jakubowska, J., A. Maciejewska, and R. Pawłowski, mRNA profiling in identification of biological fluids in forensic genetics. *Z Zagadnien Nauk Sadowych*, 2011, **87**: 204–215.

Jakubowska, J., et al., mRNA profiling for vaginal fluid and menstrual blood identification. *Forensic Sci Int Genet*, 2013, **7**(2): 272–278.

Johnston, S., J. Newman, and R. Frappier, Validation study of the abacus diagnostics ABAcard HemaTrace Membrane Test for the forensic identification of human blood. *Can Soc Forensic Sci J*, 2003, **36**(3): 173–183.

Juusola, J. and J. Ballantyne, Messenger RNA profiling: A prototype method to supplant conventional methods for body fluid identification. *Forensic Sci Int*, 2003, **135**(2): 85–96.

Juusola, J. and J. Ballantyne, Multiplex mRNA profiling for the identification of body fluids. *Forensic Sci Int*, 2005, **152**(1): 1–12.

Juusola, J. and J. Ballantyne, mRNA profiling for body fluid identification by multiplex quantitative RT-PCR. *J Forensic Sci*, 2007, **52**(6): 1252–1262.

Kakizaki, E., et al., Bioluminescent bacteria have potential as a marker of drowning in seawater: Two immersed cadavers retrieved near estuaries. *Leg Med*, 2009, **11**(2): 91–96.

Kakizaki, E., et al., Detection of marine and freshwater bacterioplankton in immersed victims: Post-mortem bacterial invasion does not readily occur. *Forensic Sci Int*, 2011, **211**(1–3): 9–18.

Kakizaki, E., et al., *In vitro* study of possible microbial indicators for drowning: Salinity and types of bacterioplankton proliferating in blood. *Forensic Sci Int*, 2011, **204**(1–3): 80–87.

Kakizaki, E., et al., Detection of diverse aquatic microbes in blood and organs of drowning victims: First metagenomic approach using high-throughput 454-pyrosequencing. *Forensic Sci Int*, 2012, **220**(1–3): 135–146.

Kohlmeier, F. and P.M. Schneider, Successful mRNA profiling of 23 years old blood stains. *Forensic Sci Int Genet*, 2012, **6**(2): 274–276.

Koppelkamm, A., et al., Validation of adequate endogenous reference genes for the normalisation of qPCR gene expression data in human post mortem tissue. *Int J Legal Med*, 2010, **124**(5): 371–380.

Koppelkamm, A., et al., RNA integrity in post-mortem samples: Influencing parameters and implications on RT-qPCR assays. *Int J Legal Med*, 2011, **125**(4): 573–580.

Kumagai, A., N. Nakayashiki, and Y. Aoki, Analysis of age-related carbonylation of human vitreous humor proteins as a tool for forensic diagnosis. *Leg Med (Tokyo)*, 2007, **9**(4): 175–180.

Lee, H.Y., et al., Potential forensic application of DNA methylation profiling to body fluid identification. *Int J Legal Med*, 2012, **126**(1): 55–62.

Lee, H.Y., et al., Potential forensic application of DNA methylation profiling to body fluid identification. *Int J Legal Med*, 2012, **126**(1): 55–62.

Lehman, D.C., Forensic microbiology. *Clin Lab Sci*, 2012, **25**(2): 114–119.

Li, W.C., et al., Estimation of postmortem interval using microRNA and 18S rRNA degradation in rat cardiac muscle. *J Forensic Med*, 2010, **26**(6): 413–417.

Li, C., et al., Differences of DNA methylation profiles between monozygotic twins' blood samples. *Mol Biol Rep*, 2013, **40**(9): 5275–5280.

Lincoln, P.J. and B.E. Dodd, The use of low ionic strength solution (LISS) in elution experiments and in combination with papain-treated cells for the titration of various antibodies, including eluted antibody. *Vox Sang*, 1978, **34**(4): 221–226.

Lindenbergh, A., et al., A multiplex (m)RNA-profiling system for the forensic identification of body fluids and contact traces. *Forensic Sci Int Genet*, 2012, **6**(5): 565–577.

Lindenbergh, A., P. Maaskant, and T. Sijen, Implementation of RNA profiling in forensic casework. *Forensic Sci Int Genet*, 2013, **7**(1): 159–166.

Lucci, A., et al., A promising microbiological test for the diagnosis of drowning. *Forensic Sci Int*, 2008, **182**(1–3): 20–26.

Madi, T., et al., The determination of tissue-specific DNA methylation patterns in forensic biofluids using bisulfite modification and pyrosequencing. *Electrophoresis*, 2012, **33**(12): 1736–1745.

Moreno, L.I., et al., Determination of an effective housekeeping gene for the quantification of mRNA for forensic applications. *J Forensic Sci*, 2012, **57**(4): 1051–1058.

Nagasawa, S., et al., Detection of *Helicobacter pylori* (*H. pylori*) DNA in digestive systems from cadavers by real-time PCR. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S458–S459.

Nakanishi, H., et al., A novel method for the identification of saliva by detecting oral streptococci using PCR. *Forensic Sci Int*, 2009, **183**(1–3): 20–23.

Nakanishi, H., et al., A simple identification method of saliva by detecting *Streptococcus salivarius* using loop-mediated isothermal amplification. *J Forensic Sci*, 2011, **56**(Suppl. 1): S158–S167.

Nakanishi, H., et al., Identification of feces by detection of *Bacteroides* genes. *Forensic Sci Int Genet*, 2013, **7**(1): 176–179.

Nakatome, M., et al., Methylation analysis of circadian clock gene promoters in forensic autopsy specimens. *Leg Med (Tokyo)*, 2011, **13**(4): 205–209.

Nakayashiki, N., et al., Analysis of the methylation profiles in imprinted genes applicable to parental allele discrimination. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S471–S472.

Nakayashiki, N., et al., Investigation of the methylation status around parent-of-origin detectable SNPs in imprinted genes. *Forensic Sci Int Genet*, 2009, **3**(4): 227–232.

Nussbaumer, C., E. Gharehbaghi-Schnell, and I. Korschineck, Messenger RNA profiling: A novel method for body fluid identification by real-time PCR. *Forensic Sci Int*, 2006, **157**(2–3): 181–186.

Oakley, C.L. and A.J. Fulthorpe, Antigenic analysis by diffusion. *J Pathol Bacteriol*, 1953, **65**(1): 49–60.

Odriozola, A., et al., miRNA analysis in vitreous humor to determine the time of death: A proof-of-concept pilot study. *Int J Legal Med*, 2013, **127**(3): 573–578.

Omelia, E.J., M.L. Uchimoto, and G. Williams, Quantitative PCR analysis of blood- and saliva-specific microRNA markers following solid-phase DNA extraction. *Anal Biochem*, 2013, **435**(2): 120–122.

Ota, M., et al., Restriction enzyme analysis of PCR products. *Methods Mol Biol*, 2009, **578**: 405–414.

Ouchterlony, O., Antigen-antibody reactions in gels. *Acta Pathol Microbiol Scand*, 1949, **26**: 507.

Pang, B.C. and B.K. Cheung, Identification of human semenogelin in membrane strip test as an alternative method for the detection of semen. *Forensic Sci Int*, 2007, **169**(1): 27–31.

Park, J.L., et al., Forensic body fluid identification by analysis of multiple RNA markers using nanoString technology. *Genomics Inform*, 2013, **11**(4): 277–281.

Park, S.M., et al., Genome-wide mRNA profiling and multiplex quantitative RT-PCR for forensic body fluid identification. *Forensic Sci Int Genet*, 2013, **7**(1): 143–150.

Parker, C., E. Hanson, and J. Ballantyne, Optimization of dried stain co-extraction methods for efficient recovery of high quality DNA and RNA for forensic analysis. *Forensic Sci Int Genet Suppl Series*, 2011, **3**(1): e309–e310.

Partemi, S., et al., Analysis of mRNA from human heart tissue and putative applications in forensic molecular pathology. *Forensic Sci Int*, 2010, **203**(1–3): 99–105.

Petrie, G.F., A specific precipitin reaction associated with with growth on agar plates on *meningococcus*, *pneumococcus*, and *B. dysenteriae* (shiga). *Br J Exp Pathol*, 1932, **13**: 380.

Phang, T.W., et al., Amplification of cDNA via RT-PCR using RNA extracted from postmortem tissues. *J Forensic Sci*, 1994, **39**(5): 1275–1279.

Power, D.A., et al., PCR-based detection of salivary bacteria as a marker of expirated blood. *Sci Justice*, 2010, **50**(2): 59–63.

Qi, B., L. Kong, and Y. Lu, Gender-related difference in bloodstain RNA ratio stored under uncontrolled room conditions for 28 days. *J Forensic Legal Med*, 2013, **20**(4): 321–325.

Qin, J., et al., Application situation and prospect of mRNA in forensic medicine. *Chin J Forensic Med*, 2013, **28**(1): 30–33.

Quarino, L., et al., An ELISA method for the identification of salivary amylase. *J Forensic Sci*, 2005, **50**(4): 873–876.

Richard, M.L., et al., Evaluation of mRNA marker specificity for the identification of five human body fluids by capillary electrophoresis. *Forensic Sci Int Genet*, 2012, **6**(4): 452–460.

Roeder, A.D. and C. Haas, mRNA profiling using a minimum of five mRNA markers per body fluid and a novel scoring method for body fluid identification. *Int J Legal Med*, 2013, **127**(4): 707–721.

Sabatini, L.M., Y.Z. He, and E.A. Azen, Structure and sequence determination of the gene encoding human salivary statherin. *Gene*, 1990, **89**(2): 245–251.

Saeed, M., R.M. Berlin, and T.D. Cruz, Exploring the utility of genetic markers for predicting biological age. *Leg Med (Tokyo)*, 2012, **14**(6): 279–285.

Sakurada, K., et al., Evaluation of mRNA-based approach for identification of saliva and semen. *Leg Med*, 2009, **11**(3): 125–128.

Sakurada, K., et al., Identification of nasal blood by real-time RT-PCR. *Leg Med (Tokyo)*, 2012, **14**(4): 201–204.

Salamonsen, L.A. and D.E. Woolley, Matrix metalloproteinases in normal menstruation. *Hum Reprod*, 1996, **11**(Suppl 2): 124–133.

Salamonsen, L.A. and D.E. Woolley, Menstruation: Induction by matrix metalloproteinases and inflammatory cells. *J Reprod Immunol*, 1999, **44**(1–2): 1–27.

Sampaio-Silva, F., et al., Profiling of RNA degradation for estimation of post mortem interval. *PLoS One*, 2013, **8**(2): e56507.

Sato, I., et al., Rapid detection of semenogelin by one-step immunochromatographic assay for semen identification. *J Immunol Methods*, 2004, **287**(1–2): 137–145.

Schulz, M.M., et al., A new approach to the investigation of sexual offenses—Cytoskeleton analysis reveals the origin of cells found on forensic swabs. *J Forensic Sci*, 2010, **55**(2): 492–498.

Seidl, S., R. Hausmann, and P. Betz, Comparison of laser and mercury-arc lamp for the detection of body fluids on different substrates. *Int J Legal Med*, 2008, **122**(3): 241–244.

Setzer, M., J. Juusola, and J. Ballantyne, Recovery and stability of RNA in vaginal swabs and blood, semen, and saliva stains. *J Forensic Sci*, 2008, **53**(2): 296–305.

Sikirzhytski, V., A. Sikirzhytskaya, and I.K. Lednev, Multidimensional Raman spectroscopic signatures as a tool for forensic identification of body fluid traces: A review. *Appl Spectrosc*, 2011, **65**(11): 1223–1232.

Sikirzhytski, V., K. Virkler, and I.K. Lednev, Discriminant analysis of Raman spectra for body fluid identification for forensic purposes. *Sensors (Basel)*, 2010, **10**(4): 2869–2884.

Sikirzhytskaya, A., V. Sikirzhytski, and I.K. Lednev, Raman spectroscopic signature of vaginal fluid and its potential application in forensic body fluid identification. *Forensic Sci Int*, 2012, **216**(1–3): 44–48.

Sikirzhytski, V., A. Sikirzhytskaya, and I.K. Lednev, Advanced statistical analysis of Raman spectroscopic data for the identification of body fluid traces: Semen and blood mixtures. *Forensic Sci Int*, 2012, **222**(1–3): 259–265.

Sikirzhytski, V., A. Sikirzhytskaya, and I.K. Lednev, Multidimensional Raman spectroscopic signature of sweat and its potential application to forensic body fluid identification. *Anal Chim Acta*, 2012, **718**: 78–83.

Spencer, S.E., et al., Matrix-assisted laser desorption/ionization-time of flight-mass spectrometry profiling of trace constituents of condom lubricants in the presence of biological fluids. *Forensic Sci Int*, 2011, **207**(1–3): 19–26.

Steger, K., et al., Expression of protamine-1 and -2 mRNA during human spermiogenesis. *Mol Hum Reprod*, 2000, **6**(3): 219–225.

Suto, M., et al., PCR detection of bacterial genes provides evidence of death by drowning. *Leg Med*, 2009, **11**(Suppl. 1): S354–S356.

Sweet, G.H. and J.W. Elvins, Studies by crossed electroimmunodiffusion on the individuality and sexual origin of bloodstains. *J Forensic Sci*, 1976, **21**(3): 498–509.

Tims, S., et al., Microbial DNA fingerprinting of human fingerprints: Dynamic colonization of fingertip microflora challenges human host inferences for forensic purposes. *Int J Legal Med*, 2010, **124**(5): 477–481.

Tims, S., et al., Microbial DNA fingerprinting of human fingerprints: Dynamic colonization of fingertip microflora challenges human host inferences for forensic purposes. *Int J Legal Med*, 2010, **124**(5): 477–481.

Tran, T.N., et al., Classification of ancient mammal individuals using dental pulp MALDI-TOF MS peptide profiling. *PLoS One*, 2011, **6**(2): e17319.

Tran-Hung, L., et al., A new method to extract dental pulp DNA: Application to universal detection of bacteria. *PLoS One*, 2007, **2**(10): e1062.

Uchimoto, M.L., et al., Considering the effect of stem-loop reverse transcription and real-time PCR analysis of blood and saliva specific microRNA markers upon mixed body fluid stains. *Forensic Sci Int Genet*, 2013, **7**(4): 418–421.

Uchiyama, T., et al., A new molecular approach to help conclude drowning as a cause of death: Simultaneous detection of eight bacterioplankton species using real-time PCR assays with TaqMan probes. *Forensic Sci Int*, 2012, **222**(1–3): 11–26.

Valore, E.V., et al., Human beta-defensin-1: An antimicrobial peptide of urogenital tissues. *J Clin Invest*, 1998, **101**(8): 1633–1642.

van der Meer, D., M.L. Uchimoto, and G. Williams, Simultaneous analysis of micro-RNA and DNA for determining the body fluid origin of DNA profiles. *J Forensic Sci*, 2013, **58**(4): 967–971.

Van Steendam, K., et al., Mass spectrometry-based proteomics as a tool to identify biological matrices in forensic science. *Int J Legal Med*, 2013, **127**(2): 287–298.

Vennemann, M. and A. Koppelkamm, mRNA profiling in forensic genetics I: Possibilities and limitations. *Forensic Sci Int*, 2010, **203**(1–3): 71–75.

Vennemann, M. and A. Koppelkamm, Postmortem mRNA profiling II: Practical considerations. *Forensic Sci Int*, 2010, **203**(1–3): 76–82.

Virkler, K. and I.K. Lednev, Analysis of body fluids for forensic purposes: From laboratory testing to non-destructive rapid confirmatory identification at a crime scene. *Forensic Sci Int*, 2009, **188**(1–3): 1–17.

Virkler, K. and I.K. Lednev, Blood species identification for forensic purposes using Raman spectroscopy combined with advanced statistical analysis. *Anal Chem*, 2009, **81**(18): 7773–7777.

Virkler, K. and I.K. Lednev, Raman spectroscopic signature of semen and its potential application to forensic body fluid identification. *Forensic Sci Int*, 2009, **193**(1–3): 56–62.

Virkler, K. and I.K. Lednev, Raman spectroscopy offers great potential for the nondestructive confirmatory identification of body fluids. *Forensic Sci Int*, 2008, **181**(1–3): e1–e5.

Virkler, K. and I.K. Lednev, Forensic body fluid identification: The Raman spectroscopic signature of saliva. *Analyst*, 2010, **135**(3): 512–517.

Virkler, K. and I.K. Lednev, Raman spectroscopic signature of blood and its potential application to forensic body fluid identification. *Anal Bioanal Chem*, 2010, **396**(1): 525–534.

Visser, M., et al., mRNA-based skin identification for forensic applications. *Int J Legal Med*, 2011, **125**(2): 253–263.

Wang, Z., et al., A model for data analysis of microRNA expression in forensic body fluid identification. *Forensic Sci Int Genet*, 2012, **6**(3): 419–423.

Wang, Z., et al., Screening and confirmation of microRNA markers for forensic body fluid identification. *Forensic Sci Int Genet*, 2013, **7**(1): 116–123.

Wasserstrom, A., et al., Demonstration of DSI-semen—A novel DNA methylation-based forensic semen identification assay. *Forensic Sci Int Genet*, 2013, **7**(1): 136–142.

Wiener, A.S., M.A. Hyman, and L. Handman, A new serological test (inhibition test) for human serum globulin. *Proc Soc Exp Biol Med*, 1949, **71**: 96.

Wilkinson, D.A., et al., The effects of aerosolized bacteria on fingerprint impression evidence. *J Forensic Identif*, 2009, **59**(1): 65–79.

Xu, H., et al., Bisulfite genomic sequencing of DNA from dried blood spot microvolume samples. *Forensic Sci Int Genet*, 2012, **6**(3): 306–309.

Yoshida, K., et al., Quantification of seminal plasma motility inhibitor/semenogelin in human seminal plasma. *J Androl*, 2003, **24**(6): 878–884.

Young, S.T., et al., Estimating postmortem interval using RNA degradation and morphological changes in tooth pulp. *Forensic Sci Int*, 2013, **229**(1–3): 163.e1–e6.

Zhao, D., et al., Postmortem mRNA quantification for investigation of infantile death: A comparison with adult cases. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S286–S289.

Zhao, D., et al., Postmortem quantitative mRNA analyses of death investigation in forensic pathology: An overview and prospects. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S43–S45.

Zhao, G., et al., Study on the application of parent-of-origin specific DNA methylation markers to forensic genetics. *Forensic Sci Int*, 2005, **154**(2–3): 122–127.

Zhao, G.S. and Q.E. Yang, Applications of DNA methylation markers in forensic medicine. *Fa Yi Xue Za Zhi*, 2005, **21**(1): 61–64.

Zhao, S.M. and C.T. Li, Perspective of DNA methylation in forensic genetics and new progress of its detection methods. *J Forensic Med*, 2009, **25**(4): 290–295.

Zhao, S.M., et al., Differences of DNA methylation profiles in monozygotic twins' blood samples. *J Forensic Med*, 2011, **27**(4): 260–264.

Zubakov, D., et al., MicroRNA markers for forensic body fluid identification obtained from microarray screening and quantitative RT-PCR confirmation. *Int J Legal Med*, 2010, **124**(3): 217–226.

Zubakov, D., et al., New markers for old stains: Stable mRNA markers for blood and saliva identification from up to 16-year-old stains. *Int J Legal Med*, 2009, **123**(1): 71–74.

Zubakov, D., et al., Stable RNA markers for identification of blood and saliva stains revealed from whole genome expression analysis of time-wise degraded samples. *Int J Legal Med*, 2008, **122**(2): 135–142.

SECTION III

Identification of Biological Evidence

12

Identification of Blood

12.1 Biological Properties

Blood constitutes about 8% of the human body weight of a healthy individual. *Plasma* is the fluid portion of the blood. The cellular portion of the blood consists of *red blood cells*, *white blood cells*, and *platelets*, all of which are suspended in the plasma (Figures 12.1 and 12.2).

12.1.1 Red Blood Cells

These cells are also called *erythrocytes*. Their life span in humans is approximately 3–4 months. Additionally, mature human erythrocytes do not have nuclei, and therefore lack nuclear DNA. Erythrocytes consist of hemoglobin—proteins that are responsible for the transportation of oxygen. Most adult human hemoglobin consists of four polypeptide chains, two α chains and two β chains. Thus, adult hemoglobin is designated as $\alpha_2\beta_2$. Other forms of hemoglobin will be discussed in Chapter 18. Under normal physiological conditions, each hemoglobin subunit contains a heme moiety that binds to oxygen (Figure 12.3). A heme molecule consists of an organic component known as protoporphyrin IX and a *ferrous* (Fe^{2+}) iron ion (Figure 12.4). A heme molecule is also known as *ferroprotoporphyrin*. The ferrous ion of heme forms four bonds with the nitrogens of protoporphyrin IX, along with a fifth bond with a hemoglobin chain and a sixth bond with a molecule of O_2. Other chemicals such as carbon monoxide and cyanide also bind to the ferrous iron of the heme molecule and can cause chemical asphyxia. Heme groups are also present in the blood of various animals and in other proteins such as myoglobin in muscles and neuroglobin in the brain.

12.1.2 White Blood Cells

Also called leucocytes, white blood cells are subdivided into three types: granulocytes, lymphocytes, and monocytes. White blood cells are involved in defending the body against infection. They have nuclei and thus represent the main sources of nuclear DNA from the blood.

12.1.3 Platelets

These cells are also known as thrombocytes, and they play a role in blood clotting (Chapter 16). Platelets aggregate at sites of vascular and blood vessel injury. Like erythrocytes, they lack nuclei.



Figure 12.1 Basic composition of blood. Blood can be separated into two phases in the presence of an anticoagulant. The liquid portion called plasma accounts for approximately 55% of blood volume. The cellular elements include erythrocytes, leucocytes, and platelets. (© Richard C. Li.)



Figure 12.2 Blood cells. (© Richard C. Li.)

12.2 Presumptive Assays for Identification

12.2.1 Mechanisms of Presumptive Assays

Presumptive blood assays are designed to detect traces of blood. These assays are based on the basic principle of the oxidation–reduction reaction catalyzed by the heme moiety of the hemoglobin. As a result, colorless substrates catalyzed by heme undergo an oxidation reaction, causing either chemiluminescence, fluorescence, or a change of color. These assays are very sensitive and can detect blood in samples with 10^{-5}–10^{-6}-fold dilutions. A positive reaction indicates the possible presence of blood. Additionally, most of these assays do not interfere with forensic DNA analysis.


Heme moiety
α Chain
β Chain
β Chain
α Chain
Heme moiety

Figure 12.3 Human adult hemoglobin. Four subunits, two α and two β chains, of human adult hemoglobin are shown. Each hemoglobin subunit contains a heme moiety. (© Richard C. Li.)



Figure 12.4 Chemical structures of heme and its precursor and derivatives. (a) Protoporphyrin IX. (b) Heme (ferroprotoporphyrin). (c) Hemochromagen, R = pyridine (pyridineferroprotoporphyrin). (d) Hematin hydroxide, R = OH (ferriprotoporphyrin hydroxide); hematin chloride, R = Cl (ferriprotoporphyrin chloride).

12.2.1.1 Oxidation–Reduction Reactions

An oxidation–reduction reaction involves a change in the oxidation state of a molecule. Specifically, the *oxidation* of a molecule means that the molecule has lost electrons, and the *reduction* of a molecule means that the molecule has gained electrons. Chemicals that can be reduced and therefore gain electrons from other molecules are called *oxidants*. In contrast, *reductants* are chemicals that can be oxidized and therefore lose electrons to other molecules. In biochemical reactions, oxidation often coincides with a loss of hydrogen. Figure 12.5 depicts an example of an oxidation–reduction reaction for blood identification. In presumptive assays, heme is utilized as the catalyst, and hydrogen peroxide is utilized as the oxidant for the reaction. In the presence of heme, a colorless substrate is oxidized, yielding a product with color, chemiluminescence, or fluorescence.

12.2.2 Colorimetric Assays

Many procedures are available for detecting heme in blood through color reactions. The most common agents are phenolphthalin, leucomalachite green, and benzidine derivatives. The color reactions produced by these assays can be observed immediately with the naked eye.

12.2.2.1 Phenolphthalin Assay

Phenolphthalein, a member of a class of indicators and dyes, is used in titrations of mineral and organic acids as well as most alkalis. The phenolphthalin assay for blood identification is also known as the Kastle–Meyer test. Kastle published a study in 1901, presenting the results of a reaction in which phenolphthalin, a colorless compound, is catalyzed by heme with hydrogen peroxide as the oxidant (Figures 12.6 and 12.7). The oxidized derivative is phenolphthalein, which appears pink under alkaline conditions.

12.2.2.2 Leucomalachite Green (LMG) Assay

Malachite green is a triphenylmethane dye. The leuco base form of malachite green is colorless and can be oxidized by the catalysis of heme to produce a green color. The reaction is carried out under acid conditions with hydrogen peroxide as the oxidant (Figures 12.8 and 12.9).

12.2.2.3 Benzidine and Derivatives

Historically, *benzidine* was used as an intermediate in dye manufacturing (Figure 12.10). Subsequently, it was used as a presumptive assay for the presence of blood after the discovery that the oxidation of benzidine can be catalyzed by heme to produce a blue to dark blue color (carried out in an acid solution). Since the blue color may eventually turn brown, the reaction must be read



$$\underset{\text{(Colorless)}}{AH_2} + H_2O_2 \xrightarrow{\text{Heme}} \underset{\text{(Color)}}{A} + 2H_2O$$

Figure 12.5 Oxidation–reduction reaction as the basis for presumptive assays for blood identification. AH_2, substrate; A, oxidized substrate.



Figure 12.6 Chemical reaction of phenolphthalin assay.



Figure 12.7 Photograph of phenolphthalin assay results. Negative (left) and positive (right) reaction. (© Richard C. Li.)


N(CH3)2
H2O2
Heme
N(CH3)2
N(CH3)2
NCH3
Leucomalachite green
reduced (colorless)
Malachite green
oxidized (blue-green)

Figure 12.8 Chemical reaction of leucomalachite green assay.



Figure 12.9 Photograph of leucomalachite green assay results. Negative (left) and positive (right) reaction. (© Richard C. Li.)



Figure 12.10 Chemical structures of benzidine and derivatives: (a) benzidine; (b) orthotolidine; (c) tetramethylbenzidine.

immediately. Benzidine was found to be a carcinogen and is therefore no longer used for forensic testing. *Orthotolidine* is a dimethyl derivative of benzidine. Its oxidation reaction can be catalyzed by heme to produce a blue color reaction under acidic conditions (Figure 12.11). Orthotolidine is also considered a potential carcinogen based on animal studies, and for this reason it has been replaced by tetramethylbenzidine. *Tetramethylbenzidine* (TMB) is a tetramethyl derivative of benzidine. The oxidation of TMB can be catalyzed by heme to produce a green to blue-green color under acidic conditions. TMB continues to be used. The Hemastix® assay kit (Miles Laboratories) is a TMB-based assay that utilizes a TMB-containing strip device. A test is carried out by applying a moistened sample to a Hemastix® strip. The appearance of a green or a blue-green color indicates the presence of blood.

12.2.3 Chemiluminescence and Fluorescence Assays

Other organic compounds whose oxidation products have chemiluminescent or fluorescent properties are utilized for testing. In the *chemiluminescence assay*, light is emitted as a product of a chemical reaction. In this category, luminol produces chemiluminescence when blood is present. In contrast, a *fluorescence assay* requires the exposure of an oxidized product, such as fluorescin, to a particular wavelength of an excitation light source. The fluorescence is then emitted at longer wavelengths than that of the excitation light source.

One advantage of chemiluminescent and fluorescent reagents is that they can be sprayed over large areas where latent bloodstains are potentially located. A positive reaction identifies blood and also reveals the patterns of bloody impressions such as footprints and fingerprints. These methods are very sensitive and can pinpoint the locations of even small traces of blood. Additionally, they are useful for detecting blood at crime scenes that have been cleaned and show no visible staining. One disadvantage of chemiluminescent and fluorescent reagents is that precautions must be taken if stains are very small or have been washed. The spraying of



Figure 12.11 Chemical reaction of orthotolidine assay.

presumptive assay reagents may further dilute a sample and thus lead to difficulty in isolating sufficient amounts of DNA for forensic DNA analysis.

12.2.3.1 Luminol (3-Aminophthalhydrazide)

Luminol is usually utilized as a chemiluminescent reagent. The oxidation reaction of luminol catalyzed by heme produces light in the presence of an oxidant (Figures 12.12 through 12.14). The light emitted from a positive reaction can only be observed in the dark, which limits the



Figure 12.12 Chemical reaction of luminol assay.



Figure 12.13 Results obtained from testing a drop of blood on a glass plate with luminol. From left to right: drop of blood; drop of blood after spraying with luminol; drop of blood after spraying with luminol and viewing in the dark. A blue chemiluminescence indicates the presence of blood. (From Bergervoet, P.W., et al., *J Hosp Infect*, 68, 329–333, 2008. With permission.)



Figure 12.14 Detecting latent bloodstains on a floor with luminol. Left: with the light on; right: immediately after the light is switched off. A blue chemiluminescence indicates the presence of blood traces. (From Bergervoet, P.W., et al., *J Hosp Infect*, 68, 329–333, 2008. With permission.)

applications of luminol. The photodocumentation of a luminol-enhanced pattern should be done immediately before it fades away.

12.2.3.2 Fluorescin

Fluorescin is another reagent that is used to test for the presence of bloodstains at a crime scene (Figures 12.15 and 12.16). When oxidized and catalyzed by heme, fluorescin demonstrates fluorescent properties. Usually, fluorescin-sprayed stains are exposed to light in the range of 425–485 nm using an alternate light source device. In a positive reaction, the oxidized fluorescin emits an intense yellowish-green fluorescent light, which indicates the presence of a bloodstain. The light emitted from fluorescin-sprayed stains lasts longer than that of luminol.

12.2.4 Factors Affecting Presumptive Assay Results

The catalytic assays discussed in the previous sections are not specific to blood only, which can possibly lead to the observation of false-positive or false-negative results (Figure 12.17).

12.2.4.1 Oxidants

Chemicals that are strong oxidants may cause a false-positive reaction. Such chemicals can catalyze the oxidation reaction even in the absence of heme and result in a false-positive reaction. Certain metal salts, such as copper and nickel salts, household bleaches and cleaners that contain hypochlorite ions, and hair-coloring products that contain hydrogen peroxide, work as oxidants. To address this problem, a two-step catalytic assay should be performed. The substrate



Figure 12.15 Chemical structure of fluorescein.



Figure 12.16 Detecting diluted bloodstains on black cotton fabric with fluorescin (left) and Bluestar (right). (From Finnis, J., Lewis, J., and Davidson, A., *Sci Justice*, 53, 178–186, 2013. With permission.)



$$\underset{\text{(colorless)}}{AH_2} + H_2O_2 \xrightleftharpoons[\text{(3) Reductant}]{\substack{\text{(1) Oxidant}\\ \text{(2) Peroxidase}}} \underset{\text{(color)}}{A} + 2H_2O$$

Figure 12.17 Factors affecting presumptive assay results. Strong oxidant and peroxidase may cause false-positive results; reductant may cause false-negative results.

is applied first to the sample in question. A color change occurring before the addition of hydrogen peroxide indicates a false-positive result due to a possible oxidant in the sample. If a color change is observed after the addition of hydrogen peroxide, the result is a true positive.

12.2.4.2 Plant Peroxidases

Many types of plants such as horseradish contain peroxidases. Plant peroxidases may also catalyze oxidation reactions and lead to false-positive results. However, plant peroxidases are usually heat sensitive and may be inactivated by high temperatures. Because the heme molecule is relatively stable at high temperatures, samples can be retested after heating. This will inactivate any plant peroxidases in a sample.

12.2.4.3 Reductants

Although not common, a false-negative result can occur when a strong reductant is present in a sample. Strong reductants such as certain metal ions including lithium and zinc may inhibit the oxidation reaction.

12.3 Confirmatory Assays for Identification

12.3.1 Microcrystal Assays

Microcrystal assays apply chemicals to treat bloodstains, forming crystals of heme molecules. The morphologies of the resulting crystals are distinctive for heme and can be compared with a known standard using a microscope. A positive microcrystal assay strongly indicates the presence of blood. However, confirmatory assays are usually not as sensitive as presumptive assays. Additionally, these assays cannot distinguish between human and animal blood.

12.3.1.1 Hemochromagen Crystal Assay

Hemochromagens are heme derivatives in which the ferrous iron of the heme forms two bonds with nitrogenous bases (Figure 12.4). The method for forming hemochromagen crystals was documented in 1864. Since then, various modifications have been reported. The *Takayama crystal assay*, published in 1912, has been the method preferred by many forensic laboratories. A bloodstain is treated with pyridine and glucose (a reducing sugar that is capable of reducing ferric ion) under alkaline conditions to form crystals of pyridine ferroprotoporphyrin (Figure 12.18).



Figure 12.18 Microcrystal assays using the Takayama method. (© Richard C. Li.)



Figure 12.19 Microcrystal assays using the Teichmann method. (From James, S.H., Nordby, J.J., and Bell, S., *Forensic Science: An Introduction to Scientific and Investigative Techniques*, 4th edn., CRC Press, Boca Raton, 2014. With permission.)

12.3.1.2 Hematin Crystal Assay

This assay is also known as the *Teichmann crystal assay*. In 1853, Teichmann documented a method of forming crystals of blood specimens. When blood specimens are treated with glacial acetic acid and salts, and subsequently heated, hematin chloride (ferriprotoporphyrin chloride), a prismatic brown-colored crystal, is formed (Figure 12.19). Hematin (Figure 12.4) is a heme derivative; its iron is in the *ferric* (Fe^{+3}) state. This hematin assay has a similar sensitivity and specificity as hemochromagen assays. The hematin assay has the advantage of being more reliable than hemochromagen assays for aged blood samples.

12.3.2 Other Assays

Additional techniques may be used to confirm the presence of hemoglobin. For example, *chromatographic* and *electrophoretic methods* can identify hemoglobin by its mobility characteristics. *Spectrophotometric methods* for identifying hemoglobin are based on measurements of the

Table 12.1 Application of RT-PCR Assay for Blood Identification

Gene Symbol	Gene Product	Description	Further Reading
HBA1	Hemoglobin α1	Hemoglobin α1 chain (abundant in erythrocytes)	Waye and Chui (2001)
PBGD[a]	Porphobilinogen deaminase	Erythrocyte-specific isoenzyme of heme biosynthesis pathway	Gubin and Miller (2001)
SPTB	β-Spectrin	Subunit of major protein of erythrocyte membrane skeleton	Amin et al. (1993)

Source: Adapted from Juusola, J. and Ballantyne, J., *Forensic Sci Int*, 152, 1–12, 2005; Nussbaumer, C., Gharehbaghi-Schnell, E., and Korschineck, I., *Forensic Sci Int*, 157, 181–186, 2006.

[a] Also known as hydroxymethylbilane synthase (HMBS).

characteristic light spectra, with peak absorbance at 400–425 nm, absorbed by hemoglobin and its derivatives. Finally, *immunological methods* utilize antihuman hemoglobin antibodies. This antibody can be used to detect human hemoglobin and thus indicate the presence of human blood (see Chapter 13).

Recently, *RNA-based assays* have been developed to identify blood. These assays are based on the fact that certain genes are specifically expressed in certain cell types (Chapter 11). Thus, the techniques used in the identification of blood are based on the detection of specific types of messenger RNA (mRNA) that are expressed exclusively in erythrocytes. These assays utilize reverse transcriptase polymerase chain reaction (RT-PCR; see Chapter 7) methods to detect the gene expression levels of mRNAs for blood identification. Table 12.1 summarizes the tissue-specific genes utilized for blood identification. Compared with conventional assays that are used for blood identification, the RNA-based assays have higher specificity and are amenable to automation. However, one limitation is that RNA is unstable due to degradation by endogenous and environmentally born ribonucleases.

Bibliography

Amin, K.M., et al., The exon-intron organization of the human erythroid beta-spectrin gene. *Genomics*, 1993, **18**(1): 118–125.

Andersen, J. and S. Bramble, The effects of fingermark enhancement light sources on subsequent PCR-STR DNA analysis of fresh bloodstains. *J Forensic Sci*, 1997, **42**(2): 303–306.

Anderson, S.E., G.R. Hobbs, and C.P. Bishop, Multivariate analysis for estimating the age of a bloodstain. *J Forensic Sci*, 2011, **56**(1): 186–193.

Anderson, S., et al., A method for determining the age of a bloodstain. *Forensic Sci Int*, 2005, **148**(1): 37–45.

Andrasko, J., The estimation of age of bloodstains by HPLC analysis. *J Forensic Sci*, 1997, **42**(4): 601–607.

Anslinger, K., et al., Ninhydrin treatment as a screening method for the suitability of swabs taken from contact stains for DNA analysis. *Int J Legal Med*, 2004, **118**(2): 122–124.

Arany, S. and S. Ohtani, Age estimation of bloodstains: A preliminary report based on aspartic acid racemization rate. *Forensic Sci Int*, 2011, **212**(1–3): e36–e39.

Barnett, P.D., et al., Discussion of "Effects of presumptive test reagents on the ability to obtain restriction fragment length polymorphism (RFLP) patterns from human blood and semen stains". *J Forensic Sci*, 1992, **37**(2): 369–370.

Bauer, M., S. Polzin, and D. Patzelt, Quantification of RNA degradation by semi-quantitative duplex and competitive RT-PCR: A possible indicator of the age of bloodstains? *Forensic Sci Int*, 2003, **138**(1–3): 94–103.

Bergervoet, P.W., et al., Application of the forensic Luminol for blood in infection control. *J Hosp Infect*, 2008, **68**: 329–333.

Botoniic-Sehic, E., et al., Forensic application of near-infrared spectroscopy: Aging of bloodstains. *Spectroscopy* (Santa Monica), 2009, **24**(2): 42–48.

Boyd, S., et al., Highly sensitive detection of blood by surface enhanced Raman scattering. *J Forensic Sci*, 2013, **58**(3): 753–756.

Bremmer, R.H., et al., Remote spectroscopic identification of bloodstains. *J Forensic Sci*, 2011, **56**(6): 1471–1475.

Bremmer, R.H., et al., Forensic quest for age determination of bloodstains. *Forensic Sci Int*, 2012, **216**(1–3): 1–11.

Budowle, B., et al., The presumptive reagent fluorescein for detection of dilute bloodstains and subsequent STR typing of recovered DNA. *J Forensic Sci*, 2000, **45**(5): 1090–1092.

Caldwell, J.P., W. Henderson, and N.D. Kim, ABTS: A safe alternative to DAB for the enhancement of blood fingerprints. *J Forensic Sci*, 2000, **45**(4): 785–794.

Cheeseman, R., Direct sensitivity comparison to the fluorescein and luminol bloodstain enhancement techniques. *J Forensic Ident*, 1999, **49**(3): 8.

Cheeseman, R. and L.A. DiMeo, Fluorescein as a field-worthy latent bloodstain detection system. *J Forensic Ident*, 1995, **45**(6): 1.

Cheeseman, R. and R. Tomboc, Fluorescein technique performance study on bloody foot trails. *J Forensic Ident*, 2001, **51**(1): 12.

Courts, C. and B. Madea, Specific micro-RNA signatures for the detection of saliva and blood in forensic body-fluid identification. *J Forensic Sci*, 2011, **56**(6): 1464–1470.

Cox, M., Effect of fabric washing on the presumptive identification of bloodstains. *J Forensic Sci*, 1990, **35**(6): 1335–1341.

Cox, M., A study of the sensitivity and specificity of four presumptive tests for blood. *J Forensic Sci*, 1991, **36**(5): 1503–1511.

Creamer, J.I., et al., A comprehensive experimental study of industrial, domestic and environmental interferences with the forensic luminol test for blood. *Luminescence*, 2003, **18**(4): 193–198.

Creamer, J.I., et al., Attempted cleaning of bloodstains and its effect on the forensic luminol test. *Luminescence*, 2005, **20**(6): 411–413.

DeForest, P., R. Gaensslen, and H.C. Lee, *Forensic Science: An Introduction to Criminalistics*, 1983. New York: McGraw-Hill Book Company.

Della Manna, A. and S. Montpetit, A novel approach to obtaining reliable PCR results from luminol treated bloodstains. *J Forensic Sci*, 2000, **45**(4): 886–890.

Dixon, T.R., et al., A scanning electron microscope study of dried blood. *J Forensic Sci*, 1976, **21**(4): 797–803.

Dorward, D.W., Detection and quantitation of heme-containing proteins by chemiluminescence. *Anal Biochem*, 1993, **209**(2): 219–223.

Edelman, G., et al., Identification and age estimation of blood stains on colored backgrounds by near infrared spectroscopy. *Forensic Sci Int*, 2012, **220**(1–3): 239–244.

Farrugia, K.J., et al., Chemical enhancement of footwear impressions in blood on fabric—Part 3: Amino acid staining. *Sci Justice*, 2013, **53**(1): 8–13.

Finnis, J., J. Lewis, and A. Davidson, Comparison of methods for visualizing blood on dark surfaces. *Sci Justice*, 2013, **53**(2): 178–186.

Frascione, N., V. Pinto, and B. Daniel, Development of a biosensor for human blood: New routes to body fluid identification. *Anal Bioanal Chem*, 2012, **404**(1): 23–28.

Fregeau, C.J., O. Germain, and R.M. Fourney, Fingerprint enhancement revisited and the effects of blood enhancement chemicals on subsequent profiler plus fluorescent short tandem repeat DNA analysis of fresh and aged bloody fingerprints. *J Forensic Sci*, 2000, **45**(2): 354–380.

Fujita, Y., et al., Estimation of the age of human bloodstains by electron paramagnetic resonance spectroscopy: Long-term controlled experiment on the effects of environmental factors. *Forensic Sci Int*, 2005, **152**(1): 39–43.

Gaensslen, R.E., *Sourcebook in Forensic Serology, Immunology, and Biochemistry*, 1983. Washington, DC: US Government Printing Office.

Garner, D.D., et al., An evaluation of tetramethylbenzidine as a presumptive test for blood. *J Forensic Sci*, 1976, **21**(4): 816–821.

Gimeno, F.E., Fill flash color photography to photograph luminol blood stain patterns. *J Forensic Ident*, 1989, **39**(5): 305–306.

Gimeno, F.E. and G.E. Rini, Fill flash luminescence to photograph luminol blood stain patterns. *J Forensic Ident*, 1989, **39**(3): 1.

Grafit, A., A. Cohen, and Y. Cohen, Estimation of original volume of dry bloodstains using spectrophotometric method. *J Forensic Ident*, 2012, **62**(4): 305–314.

Greenfield, A., M. Sloan, and R. Spaulding, Identification of blood and body fluids, in S. James, J. Nordby and S. Bell (eds), *Forensic Science: An Introduction to Scientific and Investigative Techniques*, pp. 205–228, 2014. Boca Raton, FL: CRC Press.

Grispino, R.R.J., The effect of luminol on the serological analysis of dried human bloodstains. *Crime Lab Digest*, 1990, **17**(1): 13–23.

Gross, A.M., K.A. Harris, and G.L. Kaldun, The effect of luminol on presumptive tests and DNA analysis using the polymerase chain reaction. *J Forensic Sci*, 1999, **44**(4): 837–840.

Gubin, A.N. and J.L. Miller, Human erythroid porphobilinogen deaminase exists in 2 splice variants. *Blood*, 2001, **97**(3): 815–817.

Guo, K., S. Achilefu, and M.Y. Berezin, Dating bloodstains with fluorescence lifetime measurements. *Chemistry*, 2012, **18**(5): 1303–1305.

Haas, C., et al., MRNA profiling for the identification of blood—Results of a collaborative EDNAP exercise. *Forensic Sci Int Genet*, 2011, **5**(1): 21–26.

Haas, C., et al., Selection of highly specific and sensitive mRNA biomarkers for the identification of blood. *Forensic Sci Int Genet*, 2011, **5**(5): 449–458.

Haas, C., et al., RNA/DNA co-analysis from blood stains—Results of a second collaborative EDNAP exercise. *Forensic Sci Int Genet*, 2012, **6**(1): 70–80.

Hanson, E., A. Albornoz, and J. Ballantyne, Validation of the hemoglobin (Hb) hypsochromic shift assay for determination of the time since deposition (TSD) of dried bloodstains. *Forensic Sci Int Genet Suppl Series*, 2011, **3**(1): e307–e308.

Hanson, E.K. and J. Ballantyne, A blue spectral shift of the hemoglobin soret band correlates with the age (time since deposition) of dried bloodstains. *PloS ONE*, 2010, **5**(9): e12830.

Hatch, A.L., A modified reagent for the confirmation of blood. *J Forensic Sci*, 1993, **38**(6): 1502–1506.

Higaki, R.S. and W.M.S. Philp, A study for the sensitivity, stability, and specificity of phenolphthalein as an indicator test for blood. *Can Soc Forensic Sci*, 1976, **9**(3): 97–102.

Hochmeister, M.N., B. Budowle, and F.S. Baechtel, Effects of presumptive test reagents on the ability to obtain restriction fragment length polymorphism (RFLP) patterns from human blood and semen stains. *J Forensic Sci*, 1991, **36**(3): 656–661.

Inoue, H., et al., Identification of fetal hemoglobin and simultaneous estimation of bloodstain age by high-performance liquid chromatography. *Int J Legal Med*, 1991, **104**(3): 127–131.

Inoue, H., et al., A new marker for estimation of bloodstain age by high performance liquid chromatography. *Forensic Sci Int*, 1992, **57**(1): 17–27.

Introna, F. Jr., G. Di Vella, and C.P. Campobasso, Determination of postmortem interval from old skeletal remains by image analysis of luminol test results. *J Forensic Sci*, 1999, **44**(3): 535–538.

James, S.H. and Nordby, J.J., *Forensic Science: An Introduction to Scientific and Investigative Techniques*, 2nd edn., 2005. Boca Raton, FL: CRC Press.

Juusola, J. and Ballantyne, J., Multiplex mRNA profiling for the identification of body fluids. *Forensic Sci Int*, 2005, **152**: 1–12.

Kashyap, V.K., A simple immunosorbent assay for detection of human blood. *J Immunoassay*, 1989, **10**(4): 315–324.

Kent, E.J., D.A. Elliot, and G.M. Miskelly, Inhibition of bleach-induced luminol chemiluminescence. *J Forensic Sci*, 2003, **48**(1): 64–67.

Kohlmeier, F. and P.M. Schneider, Successful mRNA profiling of 23 years old blood stains. *Forensic Sci Int Genet*, 2012, **6**(2): 274–276.

Laux, D.L., Effects of luminol on the subsequent analysis of bloodstains. *J Forensic Sci*, 1991, **36**(5): 1512–1520.

Laux, D.L., The detection of blood using luminol, in S.H. James, P.E. Kish, and T.P. Sutton (eds), *Principles of Bloodstain Pattern Analysis: Theory and Practice*, pp. 369–390, 2005. Boca Raton, FL: CRC Press.

Lee, H.C., Identification and grouping of bloodstains, in R. Saferstein (ed.), *Forensic Science Handbook*, pp. 267–337, 1982. Englewood Cliffs, NJ: Prentice Hall.

Lee, H.C., T. Palmbach, and M.T. Miller, *Henry Lee's Crime Scene Handbook*, 2001. San Diego: Academic Press.

Lytle, L.T. and D.G. Hedgecock, Chemiluminescence in the visualization of forensic bloodstains. *J Forensic Sci*, 1978, **23**(3): 550–562.

Matsuoka, T., T. Taguchi, and J. Okuda, Estimation of bloodstain age by rapid determinations of oxyhemoglobin by use of oxygen electrode and total hemoglobin. *Biol Pharm Bull*, 1995, **18**(8): 1031–1035.

Miyaishi, S., et al., Discrimination between postmortem and antemortem blood by a dot-ELISA for human myoglobin. *Nihon Hoigaku Zasshi*, 1994, **48**(6): 433–438.

Nussbaumer, C., Gharehbaghi-Schnell, E., and Korschineck, I., Messenger RNA profiling: a novel method for body fluid identification by real-time PCR. *Forensic Sci Int*, 2006, **157**: 181–186.

Omelia, E.J., M.L. Uchimoto, and G. Williams, Quantitative PCR analysis of blood- and saliva-specific microRNA markers following solid-phase DNA extraction. *Anal Biochem*, 2013, **435**(2): 120–122.

Ponce, A.C. and F.A. Verdu Pascual, Critical revision of presumptive tests for bloodstains. *Forensic Sci Commun*, 1999, **1**(2): 1–15.

Quickenden, T.I. and J.I. Creamer, A study of common interferences with the forensic luminol test for blood. *Luminescence*, 2001, **16**(4): 295–298.

Quickenden, T.I. and P.D. Cooper, Increasing the specificity of the forensic luminol test for blood. *Luminescence*, 2001, **16**(3): 251–253.

Quickenden, T.I., C.P. Ennis, and J.I. Creamer, The forensic use of luminol chemiluminescence to detect traces of blood inside motor vehicles. *Luminescence*, 2004, **19**(5): 271–277.

Richards, A. and R. Leintz, Forensic reflected ultraviolet imaging. *J Forensic Ident*, 2013, **63**(1): 46–69.

Santos, V.R.D., W.X. Paula, and E. Kalapothakis, Influence of the luminol chemiluminescence reaction on the confirmatory tests for the detection and characterization of bloodstains in forensic analysis. *Forensic Sci Int Genet Suppl Series*, 2009, **2**(1): 196–197.

Shaler, R.C., Modern forensic biology, in R. Saferstein (ed.), *Forensic Science Handbook*, pp. 525–614, 2002. Upper Saddle River, NJ: Pearson Education.

Shipp, E., et al., Effects of argon laser light, alternate source light, and cyanoacrylate fuming on DNA typing of human bloodstains. *J Forensic Sci*, 1993, **38**(1): 184–191.

Spalding, R., The identification and characterization of blood and bloodstains, in S. James and J. Nordby (eds), *Forensic Science: An Introduction to Scientific and Investigative Techniques*, pp. 237–260, 2005. Boca Raton, FL: CRC Press.

Stoilovic, M., Detection of semen and blood stains using polilight as a light source. *Forensic Sci Int*, 1991, **51**(2): 289–296.

Strasser, S., et al., Age determination of blood spots in forensic medicine by force spectroscopy. *Forensic Sci Int*, 2007, **170**(1): 8–14.

Sutton, T.P., Presumptive blood testing, in S.H. James (ed.), *Scientific and Legal Applications of Bloodstain Pattern Interpretation*, pp. 48–70, 1999. Boca Raton, FL: CRC Press.

Suwa, N., et al., Human blood identification using the genome profiling method. *Leg Med*, 2012, **14**(3): 121–125.

Thomas, P. and K. Farrugia, An investigation into the enhancement of fingermarks in blood on paper with genipin and lawsone. *Sci Justice*, 2013, **53**(3): 315–320.

Tobe, S.S., N. Watson, and N.N. Daeid, Evaluation of six presumptive tests for blood, their specificity, sensitivity, and effect on high molecular-weight DNA. *J Forensic Sci*, 2007, **52**(1): 102–109.

Tsutsumi, H. and Y. Katsumata, Forensic study on stains of blood and saliva in a chimpanzee bite case. *Forensic Sci Int*, 1993, **61**(2–3): 101–110.

Tsutsumi, A., Y. Yamamoto, and H. Ishizu, Determination of the age of bloodstains by enzyme activities in blood cells. *Nihon Hoigaku Zasshi*, 1983, **37**(6): 770–776.

Vandenberg, N. and R.A. van Oorschot, The use of Polilight in the detection of seminal fluid, saliva, and bloodstains and comparison with conventional chemical-based screening tests. *J Forensic Sci*, 2006, **51**(2): 361–370.

Virkler, K. and I.K. Lednev, Raman spectroscopic signature of blood and its potential application to forensic body fluid identification. *Anal Bioanal Chem*, 2010, **396**(1): 525–534.

Waye, J.S. and D.H. Chui, The alpha-globin gene cluster: Genetics and disorders. *Clin Invest Med*, 2001, **24**(2): 103–109.

Webb, J.L., J.I. Creamer, and T.I. Quickenden, A comparison of the presumptive luminol test for blood with four non-chemiluminescent forensic techniques. *Luminescence*, 2006, **21**(4): 214–220.

Yanagida, J., M. Hara, and H. Nakamura, Estimation of age of dried bloodstains by a surface absorption spectrophotometric method. *J Saitama Med School*, 1978, **5**(3): 221–225.

Yanagida, J., et al., Colorimetric study on the color changes of ageing bloodstains. *J Saitama Med School*, 1981, **8**(1–2): 15–20.

Zubakov, D., et al., Stable RNA markers for identification of blood and saliva stains revealed from whole genome expression analysis of time-wise degraded samples. *Int J Legal Med*, 2008, **122**(2): 135–142.

Zubakov, D., et al., New markers for old stains: Stable mRNA markers for blood and saliva identification from up to 16-year-old stains. *Int J Legal Med*, 2009, **123**(1): 71–74.

Zweidinger, R.A., L.T. Lytle, and C.G. Pitt, Photography of bloodstains visualized by luminol. *J Forensic Sci*, 1973, **18**(4): 296–302.

13

Species Identification

Chapter 12 discussed the principles of the identification of blood. If a stain is identified as blood, the evidence can be tested to determine whether the blood is of human origin. If the bloodstain is nonhuman, further analysis is usually not necessary.

Before forensic DNA techniques were implemented, species identification was largely determined by serological methods. Currently, most forensic laboratories perform DNA quantitation prior to DNA profile analysis. The quantitation method specifically detects higher-primate DNA. The presence of DNA measured by the quantitation assays concurrently identifies a sample as being of human origin (since crimes involving primate blood are extremely rare). Thus, species identification is usually not performed in forensic laboratories.

Nevertheless, species identification assays can be useful for screening to exclude or eliminate nonhuman samples unrelated to an investigation. Thus, it is practical for small laboratories to eliminate unnecessary analyses due to time and budget constraints. Additionally, species identification kits such as immunochromatographic devices allow field testing by crime scene investigators.

In cases involving the killing, trading, and possession of products derived from species that are protected from illegal hunting, it may be necessary to identify the animal species prior to further analysis. Species identification using DNA analysis can be performed using commonly used loci at the mitochondrial cytochrome b gene (*Cytb*), the cytochrome c oxidase I gene (*COI*), and the D-loop region. This type of identification is usually within the scope of wildlife forensic science and is thus not discussed here.

13.1 General Considerations

Most assays for species identification are based on serological techniques, including primary and secondary binding assays. The most common primary binding assays are immunochromatographic assays. The most commonly used secondary binding assays are precipitation-based assays that rely on the binding of an antigen to an antibody, causing the formation of visible precipitation. These precipitation-based assays include ring assays, Ouchterlony assays, and crossed-over immunoelectrophoresis. These assays utilize antihuman and antianimal antibodies to identify human and animal species, respectively.

13.1.1 Types of Antibodies

An antihuman antibody that is used in the identification of human samples can be made by introducing human serum into a host animal, which then produces specific antibodies against the human serum proteins. Antibodies produced from different species of host animals may produce variations in the characteristics of reactions. Since albumin is the most abundant protein in human serum, the antihuman antibody that is produced reacts strongly with human albumin. Albumin is a protein that plays important roles in the maintenance of the vascular circulating fluid and the transportation of various substances such as nutrients, hormones, and metabolic products. Blood is drawn from the host animal and the serum portion is collected. The collected serum is a polyclonal antihuman antiserum containing a mixture of antibodies against various human serum proteins. Likewise, an antibody against animal serum proteins can also be made to identify animal species of interest.

Other antibodies such as antihuman hemoglobin (Hb) antibodies can also be used to identify the human origin of a sample. Hb is an oxygen-transport protein that is found in erythrocytes (Chapter 12). Purified Hb can be used to generate monoclonal and polyclonal antihuman Hb antibodies. Likewise, antibodies recognizing glycophorin A (GPA), a human erythrocyte membrane antigen (see Section 13.2.1.2), can also be produced in a similar manner.

13.1.2 Titration of Antibodies

Recall that the ratio of antigen to antibody is critical for the success of a secondary reaction (Chapter 10). An extreme excess of antigen or antibody concentrations can inhibit secondary reactions. The prozone and postzone phenomena must be considered, and the concentrations of antigen and antibody must be carefully determined for forensic serology assays. For instance, in the prozone situation, a false-negative reaction may occur due to the presence of a high concentration of antibody.

Quality-control procedures can be used to estimate the amount of a specific antibody that is present, often via titration (Figure 13.1). To titrate an antiserum, a series of dilutions are made and each dilution is then tested for activity using precipitation or agglutination methods. The reciprocal of the highest dilution giving a positive reaction is known as the *titer*. This reflects the amount of antibody in the antiserum. Additionally, the polyclonal antiserum is a mixture of antibodies; thus, the reaction of the antiserum may vary from animal to animal (of the same species). Each lot or batch of antiserum must be validated by titration.

13.1.3 Antibody Specificity

In addition to the titer, the specificity of the antihuman antibody must be tested. Most antihuman antibodies usually have cross-reactivity with higher primates. This is not a great



Figure 13.1 Titration of antibodies. Serum is serially diluted and a constant amount of antigen is applied to each tube. The mixture is incubated, allowing agglutination to occur. The reciprocal of the highest dilution giving a positive agglutination reaction is 64 (the titer). (© Richard C. Li.)

concern because crimes involving nonhuman primates are very rare. Nevertheless, the antihuman antibody must not cross-react with other commonly encountered animals. Antisera and positive control samples must be validated for cross-reactivity. Tissue specificity must also be validated. The antiserum against human serum is usually reactive with other human biological fluids such as semen and saliva.

13.1.4 Optimal Conditions for Antigen–Antibody Binding

A number of factors can affect antigen–antibody binding. For example, increasing ionic strength can inhibit the binding of an antigen and an antibody. Stronger inhibition is usually observed for ions with large ionic radii and small radii of hydration. It is believed that the lower degree of hydration permits interactions of ions and the antibody-binding site, leading to inhibition. A proper buffer system must be selected in serological assays to ensure reliable results. The introduction of polymers can facilitate precipitation in secondary binding reactions because the presence of a polymer in a solution decreases the solubility of proteins. Linear hydrophilic polymers with high molecular weights (e.g., polyethylene glycol) are preferred. Additional factors such as temperature and pH can also affect antigen–antibody binding.

13.2 Assays

Samples can be prepared by cutting out a portion of a stain or scraping stains from a surface. A sample is usually extracted with a small volume of saline or buffer. The extracted sample can be tested using the assays described in the following subsections. Controls should be included, for example, by using a known human serum as a positive control and an extraction blank as a negative control.

13.2.1 Immunochromatographic Assays

Immunochromatographic assays are rapid, specific, and sensitive and can be used in both laboratory and field tests for species identification. Two types of assays are discussed, including those based on the detection of human erythrocyte proteins. Chapter 11 discusses the principle of immunochromatographic assays in more detail.

13.2.1.1 Identification of Human Hemoglobin Protein

Commercially produced immunochromatographic kits such as the Hexagon OBTI (Human Gesellschaft für Biochemica und Diagnostica mbH, Wiesbaden) and the ABAcard HemaTrace® (Abacus Diagnostics, California) are available. They utilize the antibody–antigen–antibody sandwich method by using antibodies that recognize human Hb. The ABAcard HemaTrace assay utilizes a labeled monoclonal antihuman Hb antibody contained in a sample well, and a polyclonal antihuman Hb antibody immobilized at a test zone of a nitrocellulose membrane. Additionally, an antiglobulin that recognizes the antibody is immobilized onto a control zone (Figure 13.2).

A sample can be prepared by cutting a small portion (2 mm diameter) of a stain or a swab. Each sample is extracted for 5 min in 2 mL of extraction buffer. A longer extraction time may be used for older stains. The samples are loaded into the sample well, and the antigen in the sample binds to the labeled antibody in the well to form an antigen–antibody complex, which then diffuses across the nitrocellulose membrane. At the test zone, the solid-phase antihuman Hb antibody binds to the antigen–antibody complex to form a labeled antibody–antigen–antibody sandwich.

The ABAcard HemaTrace® uses a pink dye that is visualized in a positive result as a pink horizontal line at the test zone (Figure 13.3). In the control zone, unbound labeled antihuman



Figure 13.2 Immunochromatographic assays for the identification of Hb in human blood. (a) In a sample well, Hb in a blood sample is mixed with a labeled anti-Hb Ab. (b) The Hb binds to the labeled anti-Hb Ab to form a labeled Ab–Hb complex. The complex diffuses toward the test zone. (c) At the test zone, the labeled Ab–Hb complex binds to an immobilized anti-Hb Ab to form a labeled Ab–Hb–Ab sandwich. (d) At the control zone, the labeled anti-Hb Ab binds to an immobilized antiglobulin and is captured. Ab and Hb represent the antibody and hemoglobin, respectively. (© Richard C. Li.)

Hb antibody binds to the solid-phase antiglobulin. This antibody–antiglobulin complex at the control zone also produces a pink horizontal line. The test is considered valid only if the line in the control zone is observed. The presence of human Hb results in a pink line at both the test and control zones. The absence of human Hb results in a pink line in the control zone only. A positive result can appear in less than a minute.

Validation studies have revealed that the sensitivity of the ABAcard HemaTrace® can be as low as 0.07 μg/mL of Hb. The normal blood Hb concentration is 14–18 and 12–16 g/dL among males and females, respectively. This assay is more sensitive than the Kastle–Meyer assay (Chapter 12). Additionally, the assay is responsive to aged stains and degraded materials. Specificity studies have shown that it is specific for blood of higher primates, including humans. However, it is also responsive to seminal stains, and oral, vaginal, anal, and rectal swabs. It is believed that these biological fluids contain very low amounts of Hb, which can still be detected by highly sensitive assays. However, if the concentration of blood is too high, a false negative can result due to the high-dose hook effect described in Chapter 11.

13.2.1.2 Identification of Human Glycophorin A Protein

Commercially produced immunochromatographic kits such as RSID™-Blood (Independent Forensics, Hillside, IL) use antibodies that recognize human GPA (Figure 13.4). A labeled monoclonal antihuman GPA antibody is contained in a sample well, and a second monoclonal antihuman GPA antibody, to a different epitope of GPA, is immobilized onto a test zone of the membrane. An antiglobulin that recognizes the antibody is immobilized onto a control zone (Figure 13.5).



Figure 13.3 Human blood identification using immunochromatic devices. Top: In an assay using an ABAcard HemaTrace device, the negative (left) and positive (right) results are shown. The "C" band indicates that the test is valid. The "T" band indicates the presence of human blood. The sample well is labeled "S." (© Richard C. Li.) Bottom: The positive (left) and negative (right) results are shown using a Hexagon-OBTI device. The "C" band indicates that the test is valid. The "T" band indicates the presence of human blood. (From Ramsthaler, F., et al., Postmortem interval of skeletal remains through the detection of intraosseal hemin traces. A comparison of UV-fluorescence, luminol, Hexagon-OBTI(R), and Combur(R) tests. *Forensic Sci Int*, 209, 59–63, 2011. With permission.)

The sample can be collected by cutting out a small portion of a stain or a swab. The sample is then extracted overnight in an extraction buffer. The extract is removed and mixed with a running buffer. The assay is carried out by loading the extracted sample into the sample well. Again, the presence of GPA results in a pink line at both the test zone and the control zone, while the absence of GPA results in a pink line in the control zone only. The test is considered valid only if the line in the control zone is observed. A result can be read after 10 min.

Validation studies revealed that the sensitivity of the RSID kit can be as low as 100 nL of human blood. Species specificity studies showed no cross-reactivity with various animal species, including nonhuman primates. Biological fluid specificity studies revealed that the kit is not responsive to other human biological fluids such as semen, saliva, urine, milk, and amniotic and vaginal fluid. No high-dose hook effects were observed in samples containing up to 5 μL of blood.


Extracellular domain
Cytosolic domain

Figure 13.4 Diagram of the structure of glycophorin (GPA) protein. GPA is a transmembrane protein on the human erythrocyte membrane. A GPA dimer is shown. The extracellular domain of the GPA is glycosylated with carbohydrate side chains (red). Various GPA epitopes are antigenic determinants of several blood group systems. (© Richard C. Li.)


Anti-GPA Ab
GPA
Bond anti-GPA Ab
Unbond anti-GPA Ab
-S-S-
Test zone
Control zone
(a)
(b)
(c)
(d)

Figure 13.5 Immunochromatographic assays for the identification of GPA in human blood. (a) In a sample well, GPA in a blood sample is mixed with a labeled anti-GPA Ab. (b) The GPA binds to the labeled anti-GPA Ab to form a labeled Ab–GPA complex. (c) At the test zone, the labeled Ab–GPA complex binds to an immobilized anti-GPA Ab to form a labeled Ab–GPA–Ab sandwich. (d) At the control zone, the labeled anti-GPA Ab binds to an immobilized antiglobulin and is captured. Ab and GPA represent the antibody and GPA protein, respectively. (© Richard C. Li.)

13.2.2 Double Immunodiffusion Assays

13.2.2.1 Ring Assay

Chapter 11 discussed the basic principle of ring assay in detail. In this double immunodiffusion assay, an antihuman antibody reagent is placed at the bottom of a test tube and a bloodstain extract is placed on top of the bottom layer, as illustrated in Figure 13.6. The procedure is described in Box 13.1. In a positive reaction, a white precipitate between the two layers observed after several minutes indicates that a sample is of human origin. If the bloodstain extract is not human, no precipitation should appear.

13.2.2.2 Ouchterlony Assay

The basic principle of this double immunodiffusion assay has also been discussed in Chapter 11. The procedure of the Ouchterlony assay is described in Box 13.2. In a positive reaction, a line of precipitate will form between each antigen well and antibody well. This assay can also determine the similarity of the antigens (Figure 13.7). During the diffusion process, different antigen–antibody complexes migrate at different rates. Consequently, a separate line of precipitate will appear in the gel for each antigen–antibody complex. In an assay in which two antigens are loaded in adjacent wells and an antibody in the third well, the following results can be observed:

- If the two antigens are identical, the two lines will become fused. This phenomenon is referred to as *identity*.
- If the two antigens are totally unrelated, the lines will cross each other but not fuse; this is known as *nonidentity*.
- If the two antigens are related (share a common epitope) but are not identical, the lines will merge with spur formation. The spurs are continuations of the line formed by the antigen due to its unique epitope. This phenomenon is known as *partial identity*.

Thus, in a species test, a positive result is noted when the precipitate lines for the positive controls and the samples fuse. No spur formation should be observed.

13.2.3 Crossed-Over Electrophoresis

This method is a combination of immunodiffusion and electrophoresis (also see Chapter 11). The procedure for the assay is described in Box 13.3. With this technique, a sharp precipitate band is visualized in a positive reaction (Figure 13.8). However, false-negative results can occur due to the postzone phenomenon, in which excess antigen may inhibit precipitation. In this



Figure 13.6 Ring assay. The antigen solution is carefully applied over the antiserum solution. Incubation may be necessary in order to form a ring of precipitate. (© Richard C. Li.)

BOX 13.1 RING ASSAY PROCEDURE

Sample preparation and extraction

- Extract a portion of a stain with saline at 4°C overnight.

Controls

- Include a positive control (known human serum sample) and a negative control (extraction blank).

Loading of antibody and samples

- Spin the antihuman antibody in a microfuge and transfer the supernatant into test tubes or capillary tubes (depending on the volume of the stain and the antiserum extracted).
- Place the sample carefully over the top of the antiserum solution, which is usually denser than the sample.

Immunodiffusion reaction

- Carry out the reaction at room temperature.
- In a positive reaction, white precipitate between the two layers can be observed after several minutes. This indicates that the sample is of human origin. No precipitate is formed if a bloodstain extract is from a nonhuman origin.

BOX 13.2 OUCHTERLONY ASSAY PROCEDURE

Sample preparation and extraction

- Cut out a small portion (approximately 5×5 mm) of a stain or a portion of a swab.
- Extract at room temperature in 100 μL of water for 30 min. The extract can be diluted if necessary. Alternatively, a very small piece of the stain or swab can be inserted directly into the well.

Controls

- Positive (known serum)
- Negative (extraction blank)
- Substrate controls (extraction of substrate from unstained area) if applicable

Agarose gel preparation

Heat a suspension of agarose (4%) until liquefied. Cool the solution in a water bath at 55°C. Pour the agarose onto a piece of glass slide and let the gel solidify to a thickness of about 2–3 mm. Alternatively, a polyester support film such as GelBond (Cambrex, New Zealand) can be used as a gel support. The agarose should be poured onto the hydrophilic side of a piece of GelBond film (6×9 cm). Punch wells consisting of a central well surrounded by four wells using a template.

Loading antibodies and samples

- Apply antihuman antibody to the central well. Apply the positive control to one of the surrounding wells.
- Apply the sample(s) in question next to a positive control.
- Apply negative and substrate controls to the remaining wells; only one negative control is needed per gel.

Immunodiffusion reaction

Incubate the plate overnight in a moisture chamber at 37°C.

Staining

Soak the gel overnight in saline solution and then soak it in deionized water for 10 min. Repeat once. Dry the gel between paper towels with a weight on top for 30 min. Dry in an oven for 30 min. Stain the gel with Coomassie blue. Stained precipitate bands appear blue.



Figure 13.7 Results of Ouchterlony assay. Ab indicates an antibody. Ag1 and Ag2 are the antigen samples in question. (a) Identity. The two antigens are identical (fused line). (b) Nonidentity. The two antigens are unrelated (spur). (c) Partial identity. The two antigens are related but not identical (fused line with spur). (© Richard C. Li.)

situation, the sample can be diluted and the assay can be repeated. False-negative results can also occur due to simple mistakes made during electrophoresis:

- Electrophoresis is carried out in the opposite direction, which results in samples running off the gel.
- Electrophoresis is carried out using an incorrect buffer system, affecting antigen–antibody binding. The amount of current applied during the electrophoresis is too strong and generates heat and denatures proteins.

BOX 13.3 CROSSED-OVER ELECTROPHORESIS PROCEDURE

Sample preparation and extraction

- Cut out a small portion (~5×5 mm) of a stain or a portion of a swab.
- Extract at room temperature in 100 μL of water for 30 min. The extract can be diluted if necessary. Alternatively, a very small piece of the stain or swab can be inserted directly into the well.

Controls

- Positive (known serum)
- Negative (extraction blank)
- Substrate (extraction of substrate from unstained area) if applicable

Agarose gel preparation

Heat a suspension of agarose (4%) until liquefied. Cool the solution in a water bath at 55°C. Pour the agarose onto a piece of glass slide and let it solidify. Alternatively, a polyester support film such as GelBond can be used as a gel support. The agarose should be poured onto the hydrophilic side of a piece of GelBond (6×9 cm). Punch small wells (about 1–2 mm) in rows using a template.

Loading antibodies and samples

- Apply antihuman antibody in one row of wells.
- Apply samples in the other row of wells. Apply the positive, negative, and substrate controls.

Electrophoresis

Submerge the agarose gel in an electrophoresis tank in proper orientation. The wells containing antihuman antibody should be closest to the anode (positive electrode) and the wells containing samples should be closest to the cathode (negative electrode). During electrophoresis, the antibody in the antiserum should migrate toward the cathode while the antigen migrates toward the anode. Electrophoresis is carried out at 10 V/cm for 20 min.

Staining

Soak the gel overnight in a saline solution and then soak it in deionized water for 10 min. Repeat once. Dry the gel between paper towels with a weight on top for 30 min. Dry in an oven for 30 min. Stain the gel with Coomassie blue. Stained precipitate bands appear blue.



Figure 13.8 Results of crossed-over electrophoresis. A precipitate line is formed between a human blood sample and an antihuman antibody. No precipitate line is formed when the antihuman antibody is tested for an animal blood sample. A precipitate line is formed between the animal blood sample and the antianimal antibody. (© Richard C. Li.)

Bibliography

Allison, A.C. and J.A. Morton, Species specificity in the inhibition of antiglobulin sera: A technique for the identification of human and animal bloods. *J Clin Pathol*, 1953, **6**(4): 314–319.

Berger, B., et al., Validation of two canine STR multiplex-assays following the ISFG recommendations for non-human DNA analysis. *Forensic Sci Int Genet*, 2014, **8**(1): 90–100.

Bhatia, R.Y., Specificity of some plant lectins in the differentiation of animal blood. *Forensic Sci*, 1974, **4**(1): 47–52.

Coomber, N., et al., Validation of a short tandem repeat multiplex typing system for genetic individualization of domestic cat samples. *Croat Med J*, 2007, **48**(4): 547–555.

Dawnay, N., et al., Validation of the barcoding gene *COI* for use in forensic genetic species identification. *Forensic Sci Int*, 2007, **173**(1): 1–6.

DeForest, P., R. Gaensslen, and H.C. Lee, *Forensic Science: An Introduction to Criminalistics*, 1983. New York: McGraw-Hill.

Dorrill, M. and P.H. Whitehead, The species identification of very old human blood-stains. *Forensic Sci Int*, 1979, **13**(2): 111–116.

El-Sayed, Y.S., et al., Using species-specific repeat and PCR-RFLP in typing of DNA derived from blood of human and animal species. *Forensic Sci Med Pathol*, 2010, **6**(3): 158–164.

Grobbelaar, B.G., D. Skinner, and H.N. van de Gertenbach, The anti-human globulin inhibition test. In the identification of human blood stains. *J Forensic Med*, 1970, **17**(3): 103–111.

Hochmeister, M.N., et al., Validation studies of an immunochromatographic 1-step test for the forensic identification of human blood. *J Forensic Sci*, 1999, **44**(3): 597–602.

Imaizumi, K., et al., Development of species identification tests targeting the 16S ribosomal RNA coding region in mitochondrial DNA. *Int J Legal Med*, 2007, **121**(3): 184–191.

Johnston, S., J. Newman, and R. Frappier, Validation study of the Abacus Diagnostics ABAcard® HemaTrace® membrane test for the forensic identification of human blood. *Can Soc Forensic Sci*, 2003, **36**(3): 173–183.

Juusola, J. and J. Ballantyne, Messenger RNA profiling: A prototype method to supplant conventional methods for body fluid identification. *Forensic Sci Int*, 2003, **135**(2): 85–96.

Kanthaswamy, S., et al., Quantitative real-time PCR (qPCR) assay for human-dog-cat species identification and nuclear DNA quantification. *Forensic Sci Int Genet*, 2012, **6**(2): 290–295.

Karlsson, A.O. and G. Holmlund, Identification of mammal species using species-specific DNA pyrosequencing. *Forensic Sci Int*, 2007, **173**(1): 16–20.

Kun, T., et al., Developmental validation of Mini-DogFiler for degraded canine DNA. *Forensic Sci Int Genet*, 2013, **7**(1): 151–158.

Lawton, M.E. and J.G. Sutton, Species identification of deer blood by isoelectric focusing. *J Forensic Sci Soc*, 1982, **22**(4): 361–366.

Lee, H.C., Identification and grouping of bloodstains, in R. Saferstein (ed.), *Forensic Science Handbook*, pp. 267–337, 1982. Englewood Cliffs, NJ: Prentice Hall.

Lee, H.C. and P.R. De Forest, A precipitin-inhibition test on denatured bloodstains for the determination of human origin. *J Forensic Sci*, 1976, **21**(4): 804–810.

Lowenstein, J.M., et al., Identification of animal species by protein radioimmunoassay of bone fragments and bloodstained stone tools. *Forensic Sci Int*, 2006, **159**(2–3): 182–188.

Nakaki, S., et al., Study of animal species (human, dog and cat) identification using a multiplex single-base primer extension reaction in the cytochrome b gene. *Forensic Sci Int*, 2007, **173**(2–3): 97–102.

Ogden, R., Forensic science, genetics and wildlife biology: Getting the right mix for a wildlife DNA forensics lab. *Forensic Sci Med Pathol*, 2010, **6**(3): 172–179.

Parson, W., et al., Species identification by means of the cytochrome b gene. *Int J Legal Med*, 2000, **114**(1–2): 23–28.

Ramsthaler, F., et al., Postmortem interval of skeletal remains through the detection of intraosseal hemin traces. A comparison of UV-fluorescence, luminol, Hexagon-OBTI(R), and Combur(R) tests. *Forensic Sci Int*, 2011, **209**: 59–63.

Sato, I., et al., Forensic hair analysis to identify animal species on a case of pet animal abuse. *Int J Legal Med*, 2010, **124**(3): 249–256.

Shaler, R.C., Modern forensic biology, in R. Saferstein (ed.), *Forensic Science Handbook*, pp. 525–614, 2002. Upper Saddle River, NJ: Pearson Education.

Sivaram, S., et al., Differentiation between stains of human blood and blood of monkey. *Forensic Sci*, 1975, **6**(3): 145–152.

Spear, T.F. and S.A. Binkley, The HemeSelect test: A simple and sensitive forensic species test. *J Forensic Sci Soc*, 1994, **34**(1): 41–46.

Tabata, N. and M. Morita, Immunohistochemical demonstration of bleeding in decomposed bodies by using anti-glycophorin A monoclonal antibody. *Forensic Sci Int*, 1997, **87**(1): 1–8.

Tanaka, Y., et al., Enzyme-linked immunospot assay for detecting cells secreting antibodies against human blood group A epitopes. *Transplant Proc*, 2003, **35**(1): 555–556.

Tobe, S. and A. Linacre, Species identification of human and deer from mixed biological material. *Forensic Sci Int*, 2007, **169**(2–3): 278–279.

Tobe, S.S., et al., Recovery of human DNA profiles from poached deer remains part 2: Improved recovery protocol without the need for LCN analysis. *Sci Justice*, 2013, **53**(1): 23–27.

Tsutsumi, H. and Y. Katsumata, Forensic study on stains of blood and saliva in a chimpanzee bite case. *Forensic Sci Int*, 1993, **61**(2–3): 101–110.

van Asch, B. and A. Amorim, Capillary electrophoresis analysis of a 9-plex STR assay for canine genotyping. *Methods Mol Biol*, 2012, **830**: 231–240.

van Asch, B., et al., A new autosomal STR nineplex for canine identification and parentage testing. *Electrophoresis*, 2009, **30**(2): 417–423.

van Asch, B., et al., Forensic analysis of dog (*Canis lupus familiaris*) mitochondrial DNA sequences: An inter-laboratory study of the GEP-ISFG working group. *Forensic Sci Int Genet*, 2009, **4**(1): 49–54.

Virkler, K. and I.K. Lednev, Blood species identification for forensic purposes using Raman spectroscopy combined with advanced statistical analysis. *Anal Chem*, 2009, **81**(18): 7773–7777.

Whitehead, P.H. and A. Brech, A micro-technique involving species identification and ABO grouping on the same fragment of blood. *J Forensic Sci Soc*, 1974, **14**(2): 109–110.

Wictum, E., et al., Developmental validation of DogFiler, a novel multiplex for canine DNA profiling in forensic casework. *Forensic Sci Int Genet*, 2013, **7**(1): 82–91.

Wilson-Wilde, L., et al., Current issues in species identification for forensic science and the validity of using the cytochrome oxidase I (COI) gene. *Forensic Sci Med Pathol*, 2010, **6**(3): 233–241.

14

Identification of Semen

14.1 Biological Characteristics

A typical ejaculation releases 2–5 mL of semen, which contains seminal fluid and sperm cells (*spermatozoa*)**.** A normal sperm count ranges from 10^7 to 10^8 spermatozoa per milliliter of semen. The spermatozoa are formed from spermatogonia in the seminiferous tubules of the testes. This process of generating spermatozoa is referred to as spermatogenesis (Figure 14.1). The spermatozoa are then transported and stored in the tubular network of the epididymis where they undergo functional maturation (spermatogenesis and maturation take approximately 3 months). The epididymis joins the ductus deferens, which transports matured sperm from the epididymis to the ejaculatory duct. From there, spermatozoa follow the ejaculatory ducts into the prostatic urethra where they are joined with secretions from the prostate. Figure 14.2 illustrates the anatomy of the male reproductive system.

Seminal fluid is a complex mixture of glandular secretions. A typical sample of seminal fluid contains the combined secretions of several accessory glands. Seminal vesicle fluid accounts for approximately 60% of the ejaculate. Various proteins secreted by the seminal vesicles play a role in the coagulation of the ejaculate. Additionally, seminal vesicle fluid contains flavin, which causes semen to fluoresce under ultraviolet light, often utilized when searching for semen-stain evidence.

Prostatic fluid secretions account for approximately 30% of the ejaculate. The components of this fluid are complex as well. This portion of semen contains high concentrations of *acid phosphatase* (AP) and *prostate-specific antigen* (PSA). Both are useful markers for the identification of semen in forensic laboratories. The epididymis and the bulbourethral secretions each account for approximately 5% of the ejaculate.

A *vasectomy* is the surgical removal of a bilateral segment of the ductus deferens. The surgery prevents spermatozoa from reaching the distal portions of the male reproductive tract. However, a vasectomized male can still produce ejaculate that contains only seminal vesicle fluid, prostatic fluid, and bulbourethral fluid. The condition by which males have abnormally low sperm counts is known as *oligospermia***.** *Azoospermia* is a condition that causes males to produce no spermatozoa. However, the secretion of seminal fluid is not affected in males who have these conditions. DNA derived from epithelial cells can be isolated from the seminal fluids of these individuals.

14.1.1 Spermatozoa

A human spermatozoon has three morphologically distinct structures: the head, the middle piece, and the tail (Figure 14.3). The head contains a nucleus with densely packed chromosomes. At the tip of the head is the *acrosomal cap*, which is a membranous compartment



Figure 14.1 Spermatogenesis. In the seminiferous tubules (left) of the testes, spermatogonia (located at peripheral area of the seminiferous tubules) are differentiated to spermatids (located at the center of the seminiferous tubules). The spermatids are eventually differentiated to matured spermatozoa (right). (© Richard C. Li.)


Bladder
Ejaculatory duct
Prostatic gland
Seminal vesicle
Prostatic urethra
Ductus deferens
Bulbourethral gland
Vasectomy
Epididymis
Seminiferous tubule
Testis
External urethral orifice

Figure 14.2 Male reproductive system and accessory glands (unilateral view). (© Richard C. Li.)

containing enzymes essential for fertilization. The head is attached to the middle piece through a short neck where the mitochondria that provide the energy for moving the tail are located. The tail or flagellum is responsible for spermatozoon motility. In contrast to other cell types, a mature spermatozoon lacks various intracellular organelles such as an endoplasmic reticulum, Golgi apparatus, lysosomes, and peroxisomes. In a normal male, at least 60% of spermatozoa have normal morphology, so morphological abnormalities can often be observed.



Figure 14.3 Structure of spermatozoon. (© Richard C. Li.)

14.1.2 Acid Phosphatase

Acid phosphatase (AP) consists of a group of phosphatases with optimal activity in an acidic pH environment. The greatest forensic importance of AP is that the prostate-derived AP contributes most of the AP activity present in semen. AP levels in semen are not affected by vasectomies. AP isoenzymes are also found in other tissues (Section 16.2).

The half-life of AP activity at 37°C is 6 months. However, the half-life is decreased if a sample is stored in a wet environment. AP activity can be detected from dry seminal stains stored at –20°C up to 1 year. Low levels of prostatic AP are present in the sera of healthy males. Elevated levels of prostatic AP found in serum are useful in diagnosing and monitoring prostate carcinoma. Many AP tests utilized in clinical testing may be used to identify semen for forensic applications.

14.1.3 Prostate-Specific Antigen

Prostate-specific antigen (PSA) is a major protein present in seminal fluid at concentrations of 0.5–2.0 mg/mL. PSA is produced in the prostate epithelium and secreted into the semen. PSA can also be found in the paraurethral glands, perianal glands, apocrine sweat glands, and mammary glands. Thus small quantities can be detected in urine, fecal material, sweat, and milk. PSA can also be found at much lower levels in the bloodstream. An elevated plasma PSA is present in prostate cancer patients, and it is widely used as a screening test for this disease. PSA is also elevated in cases of benign prostatic hyperplasia and prostatitis. The synthesis of PSA is stimulated by androgen, a steroid hormone.

PSA is a protein that has a molecular weight of 30 kDa and is thus also known as *P30*. It is responsible for hydrolyzing *semenogelin* (Sg), which mediates gel formation in semen (Section 14.1.4). PSA is a member of the tissue *kallikrein* (serine protease) family and is encoded by the *KLK3* locus located on chromosome 19. In addition to PSA, other tissue kallikreins encoded by *KLK2* and *KLK4* loci are expressed in the prostate. The half-life for PSA in a dried semen stain is about 3 years at room temperature. The half-life is greatly reduced when a sample is stored in wet conditions.

14.1.4 Seminal Vesicle–Specific Antigen

Human *seminal vesicle–specific antigen* (SVSA) includes two major types, semenogelin I (SgI) and semenogelin II (SgII), and constitutes the major seminal vesicle–secreted protein in semen. On ejaculation, SVSA forms a coagulum that is liquefied after a few minutes due to the degradation of SVSA by PSA. In humans, both SgI and SgII are present in a number of tissues of the male reproductive system, including the seminal vesicles, ductus deferens, prostate, and epididymis. They are also present in several other tissues such as skeletal muscle, kidney, colon, and trachea. They have also been found in the sera of lung cancer patients.

The use of Sg as a marker for semen identification instead of PSA presents certain advantages. The concentration of Sg in seminal fluid is much higher than that of PSA, and this is beneficial for the sensitivity of detection. Sg is present in seminal fluid and absent in urine, milk, and sweat, where PSA can be found. Although Sg compounds are present in skeletal muscle, kidney, and colon, this is not a great concern because these tissue samples are not routinely collected for semen detection in sexual assault cases.

14.2 Analytical Techniques for Identifying Semen

The location of semen stains is usually carried out through visual examination. Particularly, the application of alternate light sources (ALSs) can facilitate searches for semen stains. The presumptive identification of semen is largely based on the detection of the presence of prostatic AP activity in a sample. However, most presumptive assays cannot completely distinguish prostatic AP from nonprostatic AP. Confirmatory assays for the identification of semen are available, including the microscopic examination of spermatozoa, the identification of PSA and SVSA, and the RNA-based assay.

14.2.1 Presumptive Assays

14.2.1.1 Lighting Techniques for Visual Examination of Semen Stains

Lighting techniques can be used to aid in searching for semen stains. A dried semen stain fluoresces under certain light sources such as ALSs or argon lasers. ALSs are most commonly utilized for the visual examination of semen stains (Chapter 1; Figures 14.4 and 14.5). Excitation wavelengths between 450 and 495 nm can be used, allowing for the visualization of fluorescence with orange goggles. However, this approach is not specific for semen. Other bodily fluid stains, such as saliva and urine stains, can also fluoresce with less intensity. Additionally, the intensity of the fluorescence can be affected by different colors of substrates, and the material, such as clothing, where semen stains have been deposited.



Figure 14.4 A tabletop ALS device (left) for the detection of semen stains (right). (© Richard C. Li.)



Figure 14.5 Examining a garment for semen stains. (a) A potential semen stain (labeled) is found on a garment, and (b) the stain fluoresces when irradiated with an ALS device. (© Richard C. Li.)

14.2.1.2 Acid Phosphatase Techniques

14.2.1.2.1 Colorimetric Assays

Colorimetric assays can be used for the presumptive identification of semen. The AP contained in semen can hydrolyze a variety of phosphate esters. It catalyzes the removal of the phosphate group from a substrate (Figure 14.6). Subsequently, an insoluble colored precipitate at sites of acid phosphatase activity is formed with a stabilized diazonium salt (usually in the form of zinc double salts).



Figure 14.6 Reaction catalyzed by acid phosphatases (EC 3.1.3.2). The optimal pH of the reaction is usually under pH 7.

However, interference during a test by nonprostatic AP isoenzymes (multiple forms of AP), such as contamination by AP commonly present in vaginal secretions (Chapter 16), can create problems in specimens collected from victims. Thus, it is desirable to be able to increase the specificity of the assay for prostatic AP. One solution is the application of substrates that are hydrolyzed rapidly by the prostatic enzyme and at a slower rate by the other forms of AP isoenzymes. For example, α-naphthylphosphate and thymolphthalein monophosphate are more specific to prostatic AP than phenyl phosphate and 4-nitrophenyl phosphate (Figure 14.7). The most common method for forensic applications is the use of α-naphthyl phosphate as a substrate. In the presence of AP, α-naphthylphosphate is hydrolyzed to phosphate and α-naphthol. Subsequently, the Fast Blue B, a stabilized diazonium salt, is added to carry out an azo coupling reaction, producing a purple azo dye (Figures 14.8 through 14.10).

Prostatic AP is water soluble. Thus, a moistened cotton swab or piece of filter paper can be used to transfer a small amount of sample from a stain by briefly pressing onto the questioned stain area. The α-naphthylphosphate reagent is added to the swab or filter paper followed by the addition of Fast Blue B reagent. If a purple coloration develops within 1 min, the test is considered a positive indication for semen. Color that develops after more than 1 min may arise from the activity of nonprostatic AP.

Additionally, the prostatic enzyme is strongly inhibited by dextrorotatory tartrate ions. Thus, these inhibitors, particularly tartrate, allow a distinction to be made between prostatic AP and other AP isoenzymes. Prostate and vaginal acid phosphatase can also be distinguished by using gel electrophoresis (Chapter 16).



Figure 14.7 Chemical structures of acid phosphatase substrates. (a) α-Naphthyl phosphate, (b) thymolphthalein monophosphate, (c) phenyl phosphate, (d) 4-nitrophenyl phosphate, and (e) MUP.


HO
P
OH
O
O
α-Naphthyl phosphate
AP
OH
α-Naphthol
H3CO
N≡N
2Cl
OCH3
Fast Blue B salt
OH
H3CO
N=N
N=N
OH
OCH3
Azo dye

Figure 14.8 A colorimetric acid-phosphatase assay. In this assay, α-naphthylphosphate is hydrolyzed by acid phosphatase to phosphate and α-naphthol. The α-naphthol is subsequently converted into a purple azo dye with a diazonium salt such as Fast Blue B salt. AP, acid phosphatase.



Figure 14.9 AP colorimetric assay. (a) A small amount of sample from the stain is transferred using a moistened cotton swab. (b) The substrate reagent is applied, followed by adding Fast Blue B reagent. (c) Purple coloration indicates a positive reaction. (© Richard C. Li.)



Figure 14.10 Photo of a colorimetric acid-phosphatase assay using α-naphthylphosphate as a substrate. (© Richard C. Li.)



Figure 14.11 The principle of MUP assay for detecting acid phosphatase activity. In the presence of acid phosphatase, 4-methylumbelliferone phosphate (MUP) is hydrolyzed, forming phosphate and 4-methylumbelliferone (MU), which fluoresces. AP, acid phosphatase.

14.2.1.2.2 Fluorometric Assays

Fluorometric methods are more sensitive than the colorimetric detection of AP and are used for semen stain mapping. AP catalyzes the removal of the phosphate residue on a 4-methylumbelliferone phosphate (MUP) substrate (Figure 14.11), a reaction that generates fluorescence under ultraviolet light. A piece of moistened filter paper, marked for proper orientation and identification, is used for transferring the prostatic AP. The evidence to be tested, a garment for example, is covered by the filter paper. Gloved hands are used to press the filter paper onto the stained area, ensuring that the evidence is in close contact with the paper. The filter paper is lifted from the evidence and examined in a dark room using long-wave ultraviolet light to detect any background fluorescence, which is then marked on the paper. The paper can then be sprayed with MUP reagent in a fume hood. The AP reaction on the paper can be visualized immediately. Areas where semen is present can be visualized as fluorescent areas on the filter paper (Figure 14.12).

14.2.2 Confirmatory Assays

14.2.2.1 Microscopic Examination of Spermatozoa

The cells from a questioned stain on an absorbent material can be transferred to a microscope slide by extracting a small portion of a stain with water, followed by gentle vortexing. The suspension is then transferred to a slide and evaporated at room temperature or fixed with low heat. Alternatively, it can be transferred by dampening the stain with water and rubbing or rolling it onto a microscope slide.



Figure 14.12 Fluorometric assay of acid phosphatase for locating semen stains. Evidence item (a) is closely covered by a piece of moistened filter paper (b) to allow transfer of a small amount of stain. The orientation of the paper is marked (c). The paper is lifted. The background fluorescence is marked under UV light (d). The filter paper is treated with MUP (e). The presence of fluorescence under ultraviolet light indicates semen stains (f). (© Richard C. Li.)

Microscopic identification of spermatozoa provides the proof of a seminal stain. Histological staining can facilitate microscopic examination. The most common staining technique is the *Christmas tree stain* (Figure 14.13). The red component known as Nuclear Fast Red (NFR) is a dye used for staining the nuclei of spermatozoa in the presence of aluminum ions. The green component, picroindigocarmine (PIC), stains the neck and tail portions of the sperm. The acrosomal cap and the nucleus stain pink-red, and the sperm tails and the midpiece stain blue-green. Epithelial cells, if present in the sample, appear blue-green and have red nuclei. Additionally, fluorescent detection utilizing SPERM HY-LITER Fluorescent Staining Kit can facilitate the identification of spermatozoa.

Laser capture microdissection (LCM) has been shown to be an effective technique for separating spermatozoa from nonsperm cells (i.e., epithelial cells from the victim) on a glass slide (Figure 14.14). This technique involves using a thin layer of a thermosensitive polymer that is placed on the surface of an LCM cap. Once spermatozoa are identified on the slide under a microscope, a polymer-containing LCM cap is placed over the spermatozoa on the slide. An infrared laser melts the polymer and causes it to adhere only to the targeted spermatozoa. The spermatozoa are then lifted off the slide. This allows spermatozoa to be separated and placed into snap-cap tubes for forensic DNA analysis.

14.2.2.2 Identification of Prostate-Specific Antigen

Over the years, a number of methods have been utilized to detect PSA: immunodiffusion, immunoelectrophoresis, enzyme-linked immunosorbent assay (ELISA), and immunochromatographic assays. ELISA and immunochromatographic assays have been found to be the most sensitive methods (Chapter 11).

14.2.2.2.1 Immunochromatographic Assays

Commercially produced immunochromatographic kits such as the PSA-check-1 (VED-LAB, Alencon), Seratec® PSA Semiquant (Seratec Diagnostica, Göttingen), and One Step ABAcard



Figure 14.13 Human spermatozoa stained with Christmas tree stain. (a) Staining spermatozoa on a microscope slide and (b) stained spermatozoa. (© Richard C. Li.)

Figure 14.14 A microscopic device for fluorescent detection utilizing SPERM HY-LITER Fluorescent Staining Kit (left) and a laser-capture microdissection device for separating sperm cells from other types of cells (right). (© Richard C. Li.)

PSA® (Abacus Diagnostics, California) are available. These devices utilize antihuman PSA antibodies. In the ABAcard PSA® assay, a labeled monoclonal antihuman PSA antibody is contained in a sample well, a polyclonal antihuman PSA antibody is immobilized on a test zone of a nitrocellulose membrane, and an antiglobulin that recognizes the antibody is immobilized on a control zone (Figures 14.15 and 14.16).



Figure 14.15 Immunochromatographic assays for identification of PSA in semen. (a) In a sample well, PSA in a semen sample is mixed with labeled anti-PSA Ab. (b) The PSA binds to the labeled anti-PSA Ab to form a labeled Ab–PSA complex. (c) At the test zone, the labeled complex binds to an immobilized anti-PSA Ab to form a labeled Ab–PSA–Ab sandwich. (d) At the control zone, the labeled anti-PSA Ab binds to an immobilized antiglobulin and is captured at the control zone. Ab and PSA represent antibody and prostate-specific antigen, respectively. (© Richard C. Li.)



Figure 14.16 Semen identification using an immunochromatic device (ABAcard PSA). The negative (left) and positive (right) results are shown. The “C” band indicates that the test is valid. The “T” band indicates the presence of human blood. The sample well is labeled as “S”. (© Richard C. Li.)

The assay is carried out by loading an extracted sample into the sample well. The antigen in the sample binds to the labeled antibody in the sample well to form an antigen–antibody complex. The complex then diffuses across the nitrocellulose membrane. At the test zone, the immobilized antihuman PSA antibody binds with the antigen–antibody complex to form an antibody–antigen–antibody sandwich. The ABAcard PSA® uses a pink dye that allows for the visualization of a positive test with a pink line at the test zone. In the control zone, unbound labeled antihuman PSA antibody binds to the immobilized antiglobulin. This antibody–antiglobulin complex at the control zone also results in a pink line. The test is considered valid only if the line in the control zone is observed.

The presence of human PSA results in a pink line at both the test and control zones. The absence of human PSA produces a pink line in the control zone only. A positive result can appear within 1 min; a negative result is read after 10 min. However, the high-dose hook effect, an artifact that may cause false-negative results (Chapter 10), occurs when high quantities of seminal fluid are tested.

14.2.2.2.2 ELISA

The ELISA method can be used to detect PSA with anti-PSA antibodies. The most common method used in forensic serology is antibody sandwich ELISA, in which an antibody–antigen–antibody sandwich complex is formed (Figure 14.17). The intensity of the signal can be detected and is proportional to the amount of bound antigen. The amount of PSA can also be quantified by comparing a standard with known concentrations. Although this method is specific and highly sensitive, it is time-consuming. Chapter 11 discusses the principle of ELISA in further detail.



Figure 14.17 Use of ELISA for identification of PSA in semen. (a) Sample containing PSA is applied to polystyrene tubes in which anti-PSA Ab is immobilized. (b) The PSA binds to immobilized Ab to form a PSA–Ab complex. (c) A second anti-PSA Ab, specific for a different epitope of PSA, is added to form an Ab–PSA–Ab sandwich. (d) A labeled antiglobulin then binds to the Ab–PSA–Ab sandwich. The bound antiglobulin can be detected by various reporting schemes. Ab and PSA represent antibody- and prostate-specific antigen, respectively. (© Richard C. Li.)

14.2.2.3 Identification of Seminal Vesicle–Specific Antigen

14.2.2.3.1 Immunochromatographic Assays

Commercially produced immunochromatographic kits include the RSID®-Semen test (Independent Forensics, Hillside, IL) and the Nanotrap Sg. In the RSID®-Semen assay, a labeled monoclonal anti-Sg antibody is contained in a sample well, and a second monoclonal anti-Sg antibody, to a different epitope of Sg, is immobilized on the test zone of the membrane. An antiglobulin that recognizes the antibody is immobilized on a control zone (Figure 14.18).

The sample can be prepared by cutting a small portion of a stain or a swab and is extracted for 1–2 h in an extraction buffer (200–300 μL). Approximately 10% of the extract is removed and mixed with the running buffer. The assay is carried out by loading an extracted sample into the sample well. The antigen in the sample binds to the labeled anti-Sg antibody in the sample well to form a labeled antibody–antigen complex that then diffuses across the membrane. At the test zone, the solid-phase anti-Sg antibody binds with the labeled complex to form a labeled antibody–antigen–antibody sandwich. The antigen in the sample produces a pink line at the test zone. In the control zone, unbound labeled anti-Sg antibody binds to the solid-phase antiglobulin. This labeled antibody–antiglobulin complex at the control zone also results in a pink line. The presence of Sg generates a pink line at both the test and control zones. The absence of Sg results in a pink line in the control zone only. Results may be read after 10 min.

Validation studies have revealed that the sensitivity of the RSID-Semen kit for detecting seminal fluid can be as low as a 5×10^4-fold dilution. Species specificity studies have shown no cross-reactivity with various animal species including ruminants and small mammals. Bodily fluid specificity studies have also shown that the assay is not responsive to human blood, saliva,



Figure 14.18 Immunochromatographic assays for identification of semenogelin (Sg) in semen. (a) In a sample well, Sg in a semen sample is mixed with labeled anti-Sg Ab. (b) Sg binds to the labeled anti-Sg Ab to form a labeled Ab–Sg complex. (c) At the test zone, the labeled complex binds to an immobilized anti-Sg Ab to form a labeled Ab–Sg–Ab sandwich. (d) At the control zone, the labeled anti-Sg Ab binds to an immobilized antiglobulin and is captured at the control zone. Ab represents antibody. (© Richard C. Li.)

urine, sweat, fecal matter, milk, or vaginal secretions. The assay results are not affected by condom lubricants or spermicides such as nonoxynol-9 and menfegol. However, the high-dose hook effect occurs when more than 3 μL of seminal fluid is tested.

14.2.2.3.2 ELISA

Identification of Sg for semen detection has also been carried out with ELISA. Anti-Sg antibodies are utilized. An antibody–antigen–antibody sandwich complex is formed (Figure 14.19). The intensity of the colorimetric or fluorometric signals can be detected spectrophotometrically and is proportional to the amount of bound antigen. The amount of Sg can be quantified by comparing a standard with known concentrations.

14.2.2.4 RNA-Based Assays

RNA-based assays (Chapter 11) have been developed to identify semen. The assays are based on the expression of certain genes in certain cell or tissue types. Thus, the techniques used in the identification of semen are based on the detection of specific types of mRNA expressed exclusively in spermatozoa and in certain cells of male accessory glands. These assays utilize reverse transcriptase polymerase chain reaction (RT-PCR; see Chapter 7) methods to detect gene expression levels of mRNAs for semen identification. Table 14.1 lists the tissue-specific genes utilized for semen identification. Compared to conventional assays used for semen identification, the RNA-based assay has higher specificity and is amenable to automation. However, one limitation is that the RNA is unstable due to degradation by endogenous ribonucleases.



Figure 14.19 Use of ELISA for identification of semenogelin (Sg) in semen. (a) Sample containing Sg is applied to polystyrene tubes in which anti-Sg Ab is immobilized. (b) Sg binds to immobilized Ab to form a Sg–Ab complex. (c) A second anti-Sg Ab, specific for a different epitope of Sg, is added to form an Ab–Sg–Ab sandwich. (d) A labeled antiglobulin then binds to the Ab–Sg–Ab sandwich. The bound antiglobulin can be detected by various reporting schemes. Ab represents antibody. (© Richard C. Li.)

Table 14.1 Application of RT-PCR for Semen Identification

Gene Symbol	Gene Product	Description	Further Reading
KLK3	Kallikrein 3	Also called prostate-specific antigen (PSA)	Gelmini et al. (2001)
PRM1	Protamine 1	DNA-binding proteins involved in condensation of sperm chromatin	Steger et al. (2000)
PRM2	Protamine 2	DNA-binding proteins involved in condensation of sperm chromatin	Steger et al. (2000)

Source: Adapted from Juusola, J. and Ballantyne, J., *Forensic Sci Int*, 152, 1–12, 2005; Nussbaumer, C., Gharehbaghi-Schnell, E., and Korschineck, I., *Forensic Sci Int*, 157, 181–186, 2006.

Bibliography

Ablett, P.J., The identification of the precise conditions for seminal acid phosphatase (SAP) and vaginal acid phosphatase (VAP) separation by isoelectric focusing patterns. *J Forensic Sci Soc*, 1983, **23**(3): 255–256.

Allard, J.E., The collection of data from findings in cases of sexual assault and the significance of spermatozoa on vaginal, anal and oral swabs. *Sci Justice*, 1997, **37**(2): 99–108.

Allard, J.E., et al., A comparison of methods used in the UK and Ireland for the extraction and detection of semen on swabs and cloth samples. *Sci Justice*, 2007, **47**(4): 160–167.

Allen, S.M., An enzyme linked immunosorbent assay (ELISA) for detection of seminal fluid using a monoclonal antibody to prostatic acid phosphatase. *J Immunoassay*, 1995, **16**(3): 297–308.

Allery, J.P., et al., Cytological detection of spermatozoa: Comparison of three staining methods. *J Forensic Sci*, 2001, **46**(2): 349–351.

Anoruo, B., et al., Isolating cells from non-sperm cellular mixtures using the PALM microlaser micro dissection system. *Forensic Sci Int*, 2007, **173**(2–3): 93–96.

Anslinger, K., et al., Sex-specific fluorescent labelling of cells for laser microdissection and DNA profiling. *Int J Legal Med*, 2007, **121**(1): 54–56.

Astrup, B.S., et al., Detection of spermatozoa following consensual sexual intercourse. *Forensic Sci Int*, 2012, **221**(1–3): 137–141.

Auvdel, M.J., Comparison of laser and high-intensity quartz arc tubes in the detection of body secretions. *J Forensic Sci*, 1988, **33**(4): 929–945.

Baechtel, S., The identification and individualization of semen stains, in R. Saferstein (ed.), *Forensic Science Handbook*, pp. 369–374, 1988. Englewood Cliffs, NJ: Prentice Hall.

Bauer, M. and D. Patzelt, Protamine mRNA as molecular marker for spermatozoa in semen stains. *Int J Legal Med*, 2003, **117**(3): 175–179.

Baxter, S.J., Immunological identification of human semen. *Med Sci Law*, 1973, **13**(3): 155–165.

Berti, A., et al., Expression of seminal vesicle–specific antigen in serum of lung tumor patients. *J Forensic Sci*, 2005, **50**(5): 1114–1145.

Bitner, S.E., False positives observed on the Seratec(R) PSA SemiQuant cassette test with condom lubricants. *J Forensic Sci*, 2012, **57**(6): 1545–1548.

Blake, E.T. and G.F. Sensabaugh, Genetic markers in human semen: A review. *J Forensic Sci*, 1976, **21**(4): 785–796.

Chapman, R.L., N.M. Brown, and S.M. Keating, The isolation of spermatozoa from sexual assault swabs using proteinase K. *J Forensic Sci Soc*, 1989, **29**(3): 207–212.

Chen, J.T. and G.L. Hortin, Interferences with semen detection by an immunoassay for a seminal vesicle-specific antigen. *J Forensic Sci*, 2000, **45**(1): 234–235.

Christoffersen, S., Immunohistochemical staining of human sperm cells in smears from sexual assault cases. *Int J Legal Med*, 2011, **125**(6): 887–890.

Clery, J.M., Stability of prostate specific antigen (PSA), and subsequent Y-STR typing, of *Lucilia* (*Phaenicia*) *sericata* (Meigen) (Diptera: Calliphoridae) maggots reared from a simulated postmortem sexual assault. *Forensic Sci Int*, 2001, **120**(1–2): 72–76.

Collins, K.A., et al., Identification of sperm and non-sperm male cells in cervicovaginal smears using fluorescence *in situ* hybridization: Applications in alleged sexual assault cases. *J Forensic Sci*, 1994, **39**(6): 1347–1355.

Cortner, G.V. and A.J. Boudreau, Phase contrast microscopy versus differential interference contrast microscopy as applicable to the observation of spermatozoa. *J Forensic Sci*, 1978, **23**(4): 830–832.

Dahlke, M.B., et al., Identification of semen in 500 patients seen because of rape. *Am J Clin Pathol*, 1977, **68**(6): 740–746.

Davidson, G. and T.B. Jalowiecki, Acid phosphatase screening—Wetting test paper or wetting fabric and test paper? *Sci Justice*, 2012, **52**(2): 106–111.

Davies, A., Evaluation of results from tests performed on vaginal, anal and oral swabs received in casework. *J Forensic Sci Soc*, 1978, **17**(2–3): 127–133.

Davies, A. and E. Wilson, The persistence of seminal constituents in the human vagina. *Forensic Sci*, 1974, **3**(1): 45–55.

De Moors, A., et al., Sperm Hy-Liter: An effective tool for the detection of spermatozoa in sexual assault exhibits. *Forensic Sci Int Genet*, 2013, **7**(3): 367–379.

Duenhoelter, J.H., et al., Detection of seminal fluid constituents after alleged sexual assault. *J Forensic Sci*, 1978, **23**(4): 824–829.

Elliott, K., et al., Use of laser microdissection greatly improves the recovery of DNA from sperm on microscope slides. *Forensic Sci Int*, 2003, **137**(1): 28–36.

Engelbertz, F., et al., Longevity of spermatozoa in the post-ejaculatory urine of fertile men. *Forensic Sci Int*, 2010, **194**(1–3): 15–19.

Enos, W.F. and J.C. Beyer, Prostatic acid phosphatase, aspermia, and alcoholism in rape cases. *J Forensic Sci*, 1980, **25**(2): 353–356.

Enos, W.F. and J.C. Beyer, Spermatozoa in the anal canal and rectum and in the oral cavity of female rape victims. *J Forensic Sci*, 1978, **23**(1): 231–233.

Eungprabhanth, V., Finding of the spermatozoa in the vagina related to elapsed time of coitus. *Z Rechtsmed*, 1974, **74**(4): 301–304.

Evers, H., et al., Investigative strategy for the forensic detection of sperm traces. *Forensic Sci Med Pathol*, 2009, **5**(3): 182–188.

Fraysier, H.D., A rapid screening technique for the detection of spermatozoa. *J Forensic Sci*, 1987, **32**(2): 527–530.

Gaensslen, R.E., *Sourcebook in Forensic Serology, Immunology, and Biochemistry*, 1983. Washington, DC: US Government Printing Office.

Gelmini, S., et al., Real-Time quantitative reverse transcriptase-polymerase chain reaction (RT-PCR) for the measurement of prostate-specific antigen mRNA in the peripheral blood of patients with prostate carcinoma using the taqman detection system. *Clin Chem Lab Med*, 2001, **39**(5): 385–391.

Greenfield, A. and Sloan, M., Identification of biological fluids and stains, in James, S.H., Nordby, J.J., and Bell, S. (eds), *Forensic Science: An Introduction to Scientific and Investigative Techniques*, 2009. Boca Raton, FL: Taylor & Francis.

Haas, C., et al., mRNA profiling for the identification of sperm and seminal plasma. *Forensic Sci Int Genet Suppl*, 2009, **2**(1): 534–535.

Haas, C., et al., RNA/DNA co-analysis from human saliva and semen stains—Results of a third collaborative EDNAP exercise. *Forensic Sci Int Genet*, 2013, **7**(2): 230–239.

Hardinge, P., et al., Optimisation of choline testing using Florence Iodine reagent, including comparative sensitivity and specificity with PSA and AP tests. *Sci Justice*, 2013, **53**(1): 34–40.

Healy, D.A., et al., Biosensor developments: Application to prostate-specific antigen detection. *Trends Biotechnol*, 2007, **25**(3): 125–131.

Herr, J.C. and M.P. Woodward, An enzyme-linked immunosorbent assay (ELISA) for human semen identification based on a biotinylated monoclonal antibody to a seminal vesicle–specific antigen. *J Forensic Sci*, 1987, **32**(2): 346–356.

Herr, J.C., et al., Characterization of a monoclonal antibody to a conserved epitope on human seminal vesicle–specific peptides: A novel probe/marker system for semen identification. *Biol Reprod*, 1986, **35**(3): 773–784.

Hochmeister, M.N., et al., High levels of alpha-amylase in seminal fluid may represent a simple artifact in the collection process. *J Forensic Sci*, 1997, **42**(3): 535–536.

Hochmeister, M.N., et al., Evaluation of prostate-specific antigen (PSA) membrane test assays for the forensic identification of seminal fluid. *J Forensic Sci*, 1999, **44**(5): 1057–1060.

Hueske, E.E., Techniques for extraction of spermatozoa from stained clothing: A critical review. *J Forensic Sci*, 1977, **22**(3): 596–598.

Ishiyama, I., Rapid histological examination of trace evidence by means of cellophane tape. *J Forensic Sci*, 1981, **26**(3): 570–575.

Iwasaki, M., et al., A demonstration of spermatozoa on vaginal swabs after complete destruction of the vaginal cell deposits. *J Forensic Sci*, 1989, **34**(3): 659–664.

Jones, E., The identification of semen and other body fluids, in R. Saferstein (ed.), *Forensic Science Handbook*, 2005. New Jersey: Pearson Prentice Hall.

Juusola, J. and J. Ballantyne, Messenger RNA profiling: A prototype method to supplant conventional methods for body fluid identification. *Forensic Sci Int*, 2003, **135**(2): 85–96.

Juusola, J. and J. Ballantyne, Multiplex mRNA profiling for the identification of body fluids. *Forensic Sci Int*, 2005, **152**(1): 1–12.

Keil, W., J. Bachus, and H.D. Troger, Evaluation of MHS-5 in detecting seminal fluid in vaginal swabs. *Int J Legal Med*, 1996, **108**(4): 186–190.

Khaldi, N., et al., Evaluation of three rapid detection methods for the forensic identification of seminal fluid in rape cases. *J Forensic Sci*, 2004, **49**(4): 749–753.

Laffan, A., et al., Evaluation of semen presumptive tests for use at crime scenes. *Med Sci Law*, 2011, **51**(1): 11–17.

LaRue, B.L., J.L. King, and B. Budowle, A validation study of the Nucleix DSI-Semen kit—A methylation-based assay for semen identification. *Int J Legal Med*, 2013, **127**(2): 299–308.

Laux, D.L. and J.P. Barnhart, Validation of the Seratec(R) SeraQuant for the quantitation of prostate-specific antigen levels on immunochromatographic membranes. *J Forensic Sci*, 2011, **56**(6): 1574–1579.

Levine, B., et al., Use of prostate specific antigen in the identification of semen in postmortem cases. *Am J Forensic Med Pathol*, 2004, **25**(4): 288–290.

Lewis, J., et al., The fallacy of the two-minute acid phosphatase cut off. *Sci Justice*, 2012, **52**(2): 76–80.

Liedtke, R.J. and J.D. Batjer, Measurement of prostate-specific antigen by radioimmunoassay. *Clin Chem*, 1984, **30**(5): 649–652.

Lilja, H., A kallikrein-like serine protease in prostatic fluid cleaves the predominant seminal vesicle protein. *J Clin Invest*, 1985, **76**(5): 1899–1903.

Lin, M.F., et al., Fundamental biochemical and immunological aspects of prostatic acid phosphatase. *Prostate*, 1980, **1**(4): 415–425.

Linde, H.G. and K.E. Molnar, The simultaneous identification of seminal acid phosphatase and phosphoglucomutase by starch gel electrophoresis. *J Forensic Sci*, 1980, **25**(1): 113–117.

Lunetta, P. and H. Sippel, Positive prostate-specific antigen (PSA) reaction in post-mortem rectal swabs: A cautionary note. *J Forensic Leg Med*, 2009, **16**(7): 397–399.

Maher, J., et al., Evaluation of the BioSign PSA membrane test for the identification of semen stains in forensic casework. *N Z Med J*, 2002, **115**(1147): 48–49.

Masibay, A.S. and N.T. Lappas, The detection of protein p30 in seminal stains by means of thin-layer immunoassay. *J Forensic Sci*, 1984, **29**(4): 1173–1177.

Mauck, C.K., G.F. Doncel, and G. Biomarkers of semen exposure clinical working, biomarkers of semen in the vagina: Applications in clinical trials of contraception and prevention of sexually transmitted pathogens including HIV. *Contraception*, 2007, **75**(6): 407–419.

McAlister, C., The use of fluorescence *in situ* hybridisation and laser microdissection to identify and isolate male cells in an azoospermic sexual assault case. *Forensic Sci Int Genet*, 2011, **5**(1): 69–73.

McGee, R.S. and J.C. Herr, Human seminal vesicle–specific antigen is a substrate for prostate-specific antigen (or P-30). *Biol Reprod*, 1988, **39**(2): 499–510.

McWilliams, S. and B. Gartside, Identification of prostate-specific antigen and spermatozoa from a mixture of semen and simulated gastric juice. *J Forensic Sci*, 2009, **54**(3): 610–611.

Miller, K.W., et al., Developmental validation of the SPERM HY-LITER kit for the identification of human spermatozoa in forensic samples. *J Forensic Sci*, 2011, **56**(4): 853–865.

Mitchell, A., Validation study of KPICS SpermFinder™ by NicheVision Forensics, LLC for the identification of human spermatozoa. *J Forensic Sci*, 2012, **57**(4): 1042–1050.

Montagna, C.P., The recovery of seminal components and DNA from the vagina of a homicide victim 34 days postmortem. *J Forensic Sci*, 1996, **41**(4): 700–702.

Murray, C., C. McAlister, and K. Elliott, Identification and isolation of male cells using fluorescence *in situ* hybridisation and laser microdissection, for use in the investigation of sexual assault. *Forensic Sci Int Genet*, 2007, **1**(3–4): 247–252.

Nettikadan, S., et al., Detection and quantification of protein biomarkers from fewer than 10 cells. *Mol Cell Proteomics*, 2006, **5**(5): 895–901.

Nishi, K., et al., Utilization of lectin-histochemistry in forensic neuropathology: Lectin staining provides useful information for postmortem diagnosis in forensic neuropathology. *Leg Med* (Tokyo), 2003, **5**(3): 117–131.

Norris, J.V., et al., Expedited, chemically enhanced sperm cell recovery from cotton swabs for rape kit analysis. *J Forensic Sci*, 2007, **52**(4): 800–805.

Nussbaumer, C., E. Gharehbaghi-Schnell, and I. Korschineck, Messenger RNA profiling: A novel method for body fluid identification by real-time PCR. *Forensic Sci Int*, 2006, **157**(2–3): 181–186.

Old, J., et al., Developmental validation of RSID-Semen: A lateral flow immunochromatographic strip test for the forensic detection of human semen. *J Forensic Sci*, 2012, **57**(2): 489–499.

Pang, B.C. and B.K. Cheung, Identification of human semenogelin in membrane strip test as an alternative method for the detection of semen. *Forensic Sci Int*, 2007, **169**(1): 27–31.

Peonim, V., et al., Comparable between rapid one step immunochromatographic assay and ELISA in the detection of prostate specific antigen in vaginal specimens of raped women. *J Med Assoc Thai*, 2007, **90**(12): 2624–2629.

Poyntz, F.M. and P.D. Martin, Comparison of p30 and acid phosphatase levels in post-coital vaginal swabs from donor and casework studies. *Forensic Sci Int*, 1984, **24**(1): 17–25.

Randall, B., Glycogenated squamous epithelial cells as a marker of foreign body penetration in sexual assault. *J Forensic Sci*, 1988, **33**(2): 511–514.

Rao, A.R., H.G. Motiwala, and O.M. Karim, The discovery of prostate-specific antigen. *BJU Int*, 2008, **101**(1): 5–10.

Redhead, P. and M.K. Brown, The acid phosphatase test two minute cut-off: An insufficient time to detect some semen stains. *Sci Justice*, 2013, **53**(2): 187–191.

Rodrigues, R.G., et al., Semenogelins are ectopically expressed in small cell lung carcinoma. *Clin Cancer Res*, 2001, **7**(4): 854–860.

Romero-Montoya, L., et al., Relationship of spermatoscopy, prostatic acid phosphatase activity and prostate-specific antigen (p30) assays with further DNA typing in forensic samples from rape cases. *Forensic Sci Int*, 2011, **206**(1–3): 111–118.

Roy, A.V., M.E. Brower, and J.E. Hayden, Sodium thymolphthalein monophosphate: A new acid phosphatase substrate with greater specificity for the prostatic enzyme in serum. *Clin Chem*, 1971, **17**(11): 1093–1102.

Sakurada, K., et al., Evaluation of mRNA-based approach for identification of saliva and semen. *Leg Med* (Tokyo), 2009, **11**(3): 125–128.

Sato, I., et al., A dot-blot-immunoassay for semen identification using a polyclonal antibody against semenogelin, a powerful seminal marker. *Forensic Sci Int*, 2001, **122**(1): 27–34.

Sato, I., et al., Use of the "SMITEST" PSA card to identify the presence of prostate-specific antigen in semen and male urine. *Forensic Sci Int*, 2002, **127**(1–2): 71–74.

Sato, I., et al., Rapid detection of semenogelin by one-step immunochromatographic assay for semen identification. *J Immunol Methods*, 2004, **287**(1–2): 137–145.

Sato, I., et al., Applicability of Nanotrap Sg as a semen detection kit before male-specific DNA profiling in sexual assaults. *Int J Legal Med*, 2007, **121**(4): 315–319.

Sato, I., et al., Urinary prostate-specific antigen is a noninvasive indicator of sexual development in male children. *J Androl*, 2007, **28**(1): 150–154; discussion 155–157.

Schiff, A.F., Reliability of the acid phosphatase test for the identification of seminal fluid. *J Forensic Sci*, 1978, **23**(4): 833–844.

Sensabaugh, G.F., Isolation and characterization of a semen-specific protein from human seminal plasma: A potential new marker for semen identification. *J Forensic Sci*, 1978, **23**(1): 106–115.

Sensabaugh, G.F., The quantitative acid phosphatase test. A statistical analysis of endogenous and postcoital acid phosphatase levels in the vagina. *J Forensic Sci*, 1979, **24**(2): 19.

Shaler, R.C. and P. Ryan, High acid phosphatase levels as a possible false indicator of the presence of seminal fluid. *Am J Forensic Med Pathol*, 1982, **3**(2): 161–163.

Simich, J.P., et al., Validation of the use of a commercially available kit for the identification of prostate specific antigen (PSA) in semen stains. *J Forensic Sci*, 1999, **44**(6): 1229–1231.

Sokoll, L.J. and D.W. Chan, Prostate-specific antigen. Its discovery and biochemical characteristics. *Urol Clin North Am*, 1997, **24**(2): 253–259.

Standefer, J.C. and E.W. Street, Postmortem stability of prostatic acid phosphatase. *J Forensic Sci*, 1977, **22**(1): 165–172.

Stefanidou, M., G. Alevisopoulos, and C. Spiliopoulou, Fundamental issues in forensic semen detection. *West Indian Med J*, 2010, **59**(3): 280–283.

Steger, K., et al., Expression of protamine-1 and -2 mRNA during human spermiogenesis. *Mol Hum Reprod*, 2000, **6**(3): 219–225.

Stoilovic, M., Detection of semen and blood stains using polilight as a light source. *Forensic Sci Int*, 1991, **51**(2): 289–296.

Stowell, L.I., L.E. Sharman, and K. Hamel, An enzyme-linked immunosorbent assay (ELISA) for prostate-specific antigen. *Forensic Sci Int*, 1991, **50**(1): 125–138.

Stubbings, N.A. and P.J. Newall, An evaluation of gamma-glutamyl transpeptidase (GGT) and p30 determinations for the identification of semen on postcoital vaginal swabs. *J Forensic Sci*, 1985, **30**(3): 604–614.

Talthip, J., et al., An autopsy report case of rape victim by the application of PSA test kit as a new innovation for sexual assault investigation in Thailand. *J Med Assoc Thai*, 2007, **90**(2): 348–351.

Vandewoestyne, M. and D. Deforce, Laser capture microdissection in forensic research: A review. *Int J Legal Med*, 2010, **124**(6): 513–521.

Vandewoestyne, M., et al., Automatic detection of spermatozoa for laser capture microdissection. *Int J Legal Med*, 2009, **123**(2): 169–175.

Vandewoestyne, M., et al., Suspension fluorescence *in situ* hybridization (S-FISH) combined with automatic detection and laser microdissection for STR profiling of male cells in male/female mixtures. *Int J Legal Med*, 2009, **123**(5): 441–447.

Vennemann, M., et al., Sensitivity and specificity of presumptive tests for blood, saliva and semen. *Forensic Sci Med Pathol*, 2014, **10**(1): 69–75.

Virkler, K. and I.K. Lednev, Raman spectroscopic signature of semen and its potential application to forensic body fluid identification. *Forensic Sci Int*, 2009, **193**(1–3): 56–62.

Ward, A.M., J.W. Catto, and F.C. Hamdy, Prostate specific antigen: Biology, biochemistry and available commercial assays. *Ann Clin Biochem*, 2001, **38**(Pt 6): 633–651.

Wasserstrom, A., et al., Demonstration of DSI-semen—A novel DNA methylation-based forensic semen identification assay. *Forensic Sci Int Genet*, 2013, **7**(1): 136–142.

Willott, G.M. and J.E. Allard, Spermatozoa—Their persistence after sexual intercourse. *Forensic Sci Int*, 1982, **19**(2): 135–154.

Willott, G.M. and M.A. Crosse, The detection of spermatozoa in the mouth. *J Forensic Sci Soc*, 1986, **26**(2): 125–128.

Yokota, M., et al., Evaluation of prostate-specific antigen (PSA) membrane test for forensic examination of semen. *Leg Med* (Tokyo), 2001, **3**(3): 171–176.

Yoshida, K., et al., Quantification of seminal plasma motility inhibitor/semenogelin in human seminal plasma. *J Androl*, 2003, **24**(6): 878–884.

Yoshida, M., et al., Examination of seminal stain by HPLC assay of phenolphthalein. *Leg Med* (Tokyo), 2009, **11**(Suppl 1): S357–S359.

Yu, H. and E.P. Diamandis, Prostate-specific antigen in milk of lactating women. *Clin Chem*, 1995, **41**(1): 54–58.

Zarghami, N., et al., Prostate-specific antigen in serum during the menstrual cycle. *Clin Chem*, 1997, **43**(10): 1862–1867.

15

Identification of Saliva

15.1 Biological Characteristics of Saliva

The human salivary glands produce 1.0–1.5 L of saliva daily. About 70% of saliva is produced from the submandibular salivary glands, 25% from the parotids, and 5% from the sublingual salivary glands (Figure 15.1). Although a continuous basal level of saliva secretion is maintained, a large amount of saliva is produced during eating. Saliva is largely water containing small quantities of electrolytes, proteins, antibodies, and enzymes. The digestion of carbohydrates in the diet begins in the oral cavity, where amylase in the saliva breaks down carbohydrates such as starch. Thus, detecting amylase indicates the presence of saliva.

15.1.1 Amylases

Amylases are enzymes that cleave polysaccharides such as starches, which are composed of D-glucose units connected by α1→4 linkages. Starches contain two types of glucose polymers: *amylose* and *amylopectin* (Figure 15.2). Amylose consists of long, linear chains of glucose residues connected by α1→4 linkages. Amylopectin is highly branched and consists of linear chains of glucose residues connected by α1→4 linkages with the branch points connected by α1→6 linkages. Both linear amylose and amylopectin can be hydrolyzed by amylase by cleaving the chains at alternate α1→4 linkages. Amylase cleaves off one maltose (two glucose units) at a time. However, the α1→6 linkages at the branch points are not cleaved by the amylase.

Two types of amylases are characterized. β-*Amylases* found in plant and bacterial sources cleave only at the terminal reducing end of a polysaccharide chain. The end of a chain with a free anomeric carbon (not involved in a glycosidic bond) is called the reducing end. Human α-*amylases* cleave at α1→4 linkages randomly along the polysaccharide chain.

Human α-amylases have two major isoenzymes (multiple forms that differ in their amino acid sequences). Human *salivary* α-*amylase* (HSA) is encoded by the *Amy1* locus, synthesized at the salivary glands and secreted into the oral cavity. Human *pancreatic* α-amylase (HPA), encoded by the *Amy2* locus, is synthesized by the pancreas and secreted into the duodenum through the pancreatic duct. The amino acid sequences of the HSA and HPA are highly homologous. Therefore, monoclonal antibodies against HSA also cross-react with HPA. However, HSA is inactivated by acids in the stomach, while most HPA is inactivated in the lower portions of the intestine, and some amylase activity remains in the feces.

Amylase activity is found in various bodily fluids including semen, tears, milk, perspiration, and vaginal secretions. Most amylase present in normal serum consists of HPA and HSA. The amylases are small molecules and can pass through the glomeruli of the kidney (Chapter 17).


Parotid salivary gland
Parotid duct
Submandibular duct
Submandibular salivary gland
Sublingual ducts
Sublingual salivary gland

Figure 15.1 Human salivary glands. (© Richard C. Li.)


1,4-Glycosidic bond
CH$_2$OH
O
OH
Nonreducing end
Reducing end
(a)
1,6-Glycosidic bond
1,4-Glycosidic bond
CH$_2$
(b)

Figure 15.2 Chemical structures of polysaccharides found in starch: (a) amylose and (b) amylopectin.

Thus, the amylase present in urine is derived from plasma. Amylase can be inactivated under boiling temperatures and strong acidic and alkaline conditions. Based on various studies, its stability varies from a few weeks to several months.

15.2 Analytical Techniques for Identification of Saliva

The use of alternate light sources facilitates the search for and the visual examination of saliva stains. The identification of saliva is largely based on detecting the presence of amylase in a sample. Two types of amylase assays can be utilized. The first type measures the enzymatic activity of total amylase. This type of assay cannot distinguish HSA from other amylases including HPA and nonhuman amylases, such as those from plants, animals, and microorganisms. The second type of assay, which includes direct detection of HSA proteins and RNA-based assays, is more confirmatory than enzymatic assays.

15.2.1 Presumptive Assays

15.2.1.1 Visual Examination

The lighting techniques used to search for semen stains can be utilized in searching for saliva stains. For example, a 470 nm excitation wavelength can be used with orange goggles to allow visualization of fluorescence. However, the fluorescence of a saliva stain is usually less intense than that of a seminal stain (Figure 15.3). Microscopic examination with proper histological staining can also be performed to identify the buccal epithelial cells, indicating the presence of a saliva stain (Figure 15.4).

15.2.1.2 Determination of Amylase Activity

15.2.1.2.1 Starch–Iodine Assay

Iodine (I_2) is used to test for the presence of starch. The amylose in starch reacts strongly with iodine to form a dark blue complex, while amylopectin develops a reddish-purple color. In the presence of amylases, starch is broken down to mono- or disaccharides. Consequently, such colors do not develop when iodine is added.



Figure 15.3 Examining saliva stains using an ALS technique. (© Richard C. Li.)



Figure 15.4 Buccal epithelial cells. (© Richard C. Li.)

A common configuration of the method is the radial diffusion assay (Figure 15.5). An agar gel containing starch is prepared. A sample well is created by punching a hole in the gel and an extract of the questioned sample is placed into the well. If amylase is present in the sample, it diffuses from the sample well and hydrolyzes the starch in the gel. The gel is then stained using an iodine solution. A clear area in the gel indicates amylase activity, and the size of the clear area is proportional to the amount of amylase in the sample. A linear standard curve



Figure 15.5 Radial diffusion assay for the identification of amylase. (a) Known amounts of amylase standards are applied to the well and allowed to diffuse. (b) The size of the clear area arising from amylase activity is plotted. The standard curve can be used to determine the amount of amylase in a questioned sample. (© Richard C. Li.)

(in log scale) can be prepared using a series of standard amylases with known concentrations. The amount of amylase can be quantified by comparing the results with the standard curve. However, this assay is not specific to HSA and can produce false-positive results. Moreover, the quantities of amylase can be used for determining the amount of sample needed for Y-STR analysis (Chapter 19), which now can be determined by using Y-chromosome-specific quantitative PCR assays (Chapter 6).

15.2.1.2.2 Colorimetric Assays

Dye-labeled amylase substrates such as dye-conjugated amylose or amylopectin are utilized. These substrates are not soluble in water. In the presence of amylase, the dye-containing moieties are cleaved and are soluble in water to produce a color. The degree of coloration, which can be measured colorimetrically by spectrophotometric methods, is proportional to the amount of amylase in the sample. Most of these assays are not HSA specific, although their specificity can be tested by using inhibitors that preferentially inhibit HSA, such as α-amylase inhibitors derived from the seeds of the wheat plant, *Triticum aestivum*. These amylase activity assays are considered presumptive, which means they are not conclusive for the presence of saliva in a sample.

While many substrates are available, Phadebas reagent (Pharmacia) is usually used in forensic laboratories. Produced in a tablet form, it is used to detect α-amylase in specimens for clinical diagnostic purposes. A small portion (approximately 3 mm^2) of a sample is cut and placed in a tube and incubated for 5 min at 37°C. One Phadebas tablet is added to each tube and mixed. Samples are then incubated for 15 min at 37°C, and the reaction is stopped at an alkaline pH by the addition of sodium hydroxide. The amylase substrate is an insoluble blue dye conjugated to starch. Amylase hydrolyzes the substrate to generate a blue color that can be measured at 620 nm using a spectrophotometer. The optical density of the supernatant is read and can be converted to amylase units by comparing to a standard curve.

The amylase assay can also be used for amylase mapping as a method of searching for possible saliva stains (Figures 15.6 and 15.7). These assays are based on the principle that amylase is water soluble and can be transferred from evidence to filter paper and then analyzed via colorimetric assay. This procedure is also referred to as a *press test*. The sensitivity of the method is similar to that of the test tube method.

The substrate can be prepared by evenly spraying the Phadebas reagent on a sheet of filter paper and allowing it to air-dry. The dried substrate-containing paper can be used immediately or stored until needed. To perform amylase mapping, a piece of paper is placed over the entire area to be tested (the item to be tested must be fairly flat to ensure good contact with the paper). The paper is dampened slightly by spraying with distilled water. An outline may be drawn on the paper to aid in locating stains. A piece of plastic wrap is placed on top to prevent the paper from drying during the assay, and a weight is applied to ensure close contact of substrate and evidence. The test is observed every minute for the first 10 min, and every 5 min thereafter up to 40 min, when a positive reaction should appear as a light blue area.

The SALIgAE® kit (Abacus Diagnostics), another commercially available colorimetric assay, has been validated for saliva identification (Figure 15.8). Its manufacturer also produces the SALIgAE spray kit, which can be used for amylase mapping.

15.2.2 Confirmatory Assays

15.2.2.1 Identification of Human Salivary α-Amylase

15.2.2.1.1 Immunochromatographic Assays

Commercially produced immunochromatographic kits include the RSID®-Saliva kit (Independent Forensics). A labeled monoclonal anti-HSA antibody is contained in a sample well. A second monoclonal anti-HSA antibody is immobilized onto a test zone of a membrane, and an antiglobulin that recognizes the antibody is immobilized onto a control zone (Figures 15.9 and 15.10).



Figure 15.6 Amylase colorimetric assay using Phadebas reagent. (a) A spot test for saliva and (b) amylase mapping result showing a saliva-stained area. N, a negative result; P, a positive result. (© Richard C. Li.)



Figure 15.7 Amylase mapping for saliva stains. (a) Amylase substrate is sprayed on a sheet of filter paper. (b) Substrate-containing paper is placed over the area to be tested. The orientation of the filter paper is marked to aid in locating the stain. (c) The filter paper is dampened by spraying it with water, and plastic wrap is placed on top to prevent the paper from drying. Blue color indicates a positive reaction. (© Richard C. Li.)



Figure 15.8 Saliva identification using SALIgAE reagent. P, a positive result; N, a negative result; S, a positive control. (© Richard C. Li.)



Figure 15.9 Identification of saliva using immunochromatographic assays. P, a positive result; N, a negative result. (© Richard C. Li.)

A sample can be prepared by cutting out a small portion of a stain or a swab. Each sample is extracted for 1–2 h in 200–300 μL of an extraction buffer. Approximately 10% of the extract is removed and mixed with a running buffer. The assay is carried out by loading an extracted sample into the sample well where the antigen in the sample binds to the labeled anti-HSA antibody in the well to form a labeled antibody–antigen complex. The complex then diffuses across the membrane to the test zone, where the solid-phase anti-HSA antibody binds with the labeled complex to form a labeled antibody–antigen–antibody sandwich.

The presence of antigen in the sample results in a pink line at the test zone. In the control zone, unbound labeled anti-HSA antibody binds to the solid-phase antiglobulin. The labeled antibody–antiglobulin complex at the control zone also results in a pink line. The test is



Figure 15.10 Immunochromatographic assay for the identification of HSA in saliva. (a) Sample containing amylases is loaded in a sample well. (b) Antigen binds to a labeled anti-HSA Ab to form a labeled Ab–HSA complex. (c) At the test zone, the labeled complex binds to an immobilized antihuman HSA Ab to form a labeled Ab–HSA–Ab sandwich. (d) At the control zone, the labeled anti-HSA Ab binds to an immobilized antiglobulin and is captured at the control zone. Ab, an antibody; HSA, human salivary α-amylase. (© Richard C. Li.)

considered valid only if the line in the control zone is observed. The presence of HSA results in a pink line at both the test zone and the control zone, while the absence of HSA results in a pink line in the control zone only. A result can be read after 10 min.

The sensitivity of the RSID®-Saliva kit can be as low as 1 μL of saliva. Additionally, the assay is responsive to samples extracted from saliva stains on both smooth and porous surfaces. In terms of species specificity, the kit has no cross-reactivity with various animal species, including monkeys (tamarin and callimico). As for bodily fluid specificity, it has also been shown that it is not responsive to human blood, semen, or urine. The high-dose hook effect, which creates an artifact that may cause false-negative results as described previously (Chapter 11), is not observed when up to 50 μL of saliva is tested. This method is rapid, specific, and sensitive and can be used in both laboratory and field analysis.

15.2.2.1.2 Enzyme-Linked Immunosorbent Assay (ELISA)

This method can be used to detect and to quantify a sample with the use of an anti-HSA antibody. The most common configuration in forensic serology is the antibody–antigen–antibody sandwich (Figure 15.11). ELISA utilizes reporting enzymes to produce colorimetric or fluorometric signals. The intensity of the signal can be detected spectrophotometrically and is proportional to the amount of bound antigen. The amount of HSA can be quantified by comparison with a standard of known concentration. This method is specific and highly sensitive in detecting HSA, but it is time-consuming. Chapter 11 discusses the ELISA principle in further detail.



Figure 15.11 ELISA for identification of HSA in saliva. (a) Sample containing antigen is applied to polystyrene tubes where anti-HSA Ab is immobilized. (b) Antigen binds to immobilized Ab to form HSA–Ab complex. (c) Second anti-HSA Ab, specific for a different epitope of HSA, is added to form Ab–HSA–Ab sandwich. (d) Labeled antiglobulin then binds to the sandwich. The bound antiglobulin can be detected by various reporting schemes. Ab, an antibody; HSA, human salivary α-amylase. (© Richard C. Li.)

15.2.2.2 RNA-Based Assays

RNA-based assays (Chapter 11) have been developed recently for the identification of saliva. They are based on the expression of certain genes in certain cell or tissue types. Thus, the techniques used in the identification of saliva are based on the detection of specific types of mRNA expressed exclusively in certain cells in the oral cavity. These assays utilize reverse transcriptase polymerase chain reaction (RT-PCR; see Chapter 7) methods to detect gene expression levels of mRNAs for saliva identification. Table 15.1 summarizes the tissue-specific genes utilized for saliva identification. Compared to conventional assays used for saliva identification, RNA-based assays present higher specificity and are amenable to automation. However, one limitation is that the RNA is unstable because of degradation by endogenous ribonucleases.

Table 15.1 Application of RT-PCR Assay for Saliva Identification

Gene Symbol	Gene Product	Description	Further Reading
HTN3	Histatin 3	Histidine-rich protein involved in nonimmune host defense in oral cavity	Sabatini et al. (1993)
STATH	Statherin	Inhibitor of precipitation of calcium phosphate salts in oral cavity	Sabatini et al. (1990)

Source: Adapted from Juusola, J. and Ballantyne, J., *Forensic Sci Int*, 152, 1–12, 2005.

Bibliography

Akutsu, T., et al., Applicability of ELISA detection of statherin for forensic identification of saliva. *Int J Legal Med*, 2010, **124**(5): 493–498.

Ali, M.M., et al., PCR applications in identification of saliva samples exposed to different conditions (streptococci detection based). *Pak J Biol Sci*, 2013, **16**(12): 575–579.

Aps, J.K. and L.C. Martens, Review: The physiology of saliva and transfer of drugs into saliva. *Forensic Sci Int*, 2005, **150**(2–3): 119–131.

Auvdel, M.J., Amylase levels in semen and saliva stains. *J Forensic Sci*, 1986, **31**(2): 426–431.

Auvdel, M.J., Comparison of laser and high-intensity quartz arc tubes in the detection of body secretions. *J Forensic Sci*, 1988, **33**(4): 929–945.

Barni, F., et al., Alpha-amylase kinetic test in bodily single and mixed stains. *J Forensic Sci*, 2006, **51**(6): 1389–1396.

Casey, D.G. and J. Price, The sensitivity and specificity of the RSID-saliva kit for the detection of human salivary amylase in the Forensic Science Laboratory, Dublin, Ireland. *Forensic Sci Int*, 2010, **194**(1–3): 67–71.

Courts, C. and B. Madea, Specific micro-RNA signatures for the detection of saliva and blood in forensic body-fluid identification. *J Forensic Sci*, 2011, **56**(6): 1464–1470.

Culliford, B.J., Precipitin reactions in forensic problems. A new method for precipitin reactions on forensic blood, semen and saliva stains. *Nature*, 1964, **201**: 1092–1093.

DeForest, P., R. Gaensslen, and H.C. Lee, *Forensic Science: An Introduction to Criminalistics*, 1983. New York: McGraw-Hill Book Company.

De Leo, D., et al., A sensitive and simple assay of saliva on stamps. *Z Rechtsmed*, 1985, **95**(1): 27–33.

Eckersall, P.D., et al., The production and evaluation of an antiserum for the detection of human saliva. *J Forensic Sci Soc*, 1981, **21**(4): 293–300.

Gaensslen, R.E., *Sourcebook in Forensic Serology, Immunology, and Biochemistry*, 1983. Washington, DC: US Government Printing Office.

Greenfield, A. and M. Sloan, Identification of biological fluids and stains, in S. James and J. Nordby (eds), *Forensic Science: An Introduction to Scientific and Investigative Techniques*, 2nd edn., 2005. CRC Press.

Haas, C., et al., RNA/DNA co-analysis from human saliva and semen stains—Results of a third collaborative EDNAP exercise. *Forensic Sci Int Genet*, 2013, **7**(2): 230–239.

Hedman, J., et al., Evaluation of amylase testing as a tool for saliva screening of crime scene trace swabs. *Forensic Sci Int Genet*, 2011, **5**(3): 194–198.

Hochmeister, M.N., et al., High levels of alpha-amylase in seminal fluid may represent a simple artifact in the collection process. *J Forensic Sci*, 1997, **42**(3): 535–536.

Hsu, L., et al., Amplification of oral streptococcal DNA from human incisors and bite marks. *Curr Microbiol*, 2012, **65**(2): 207–211.

Jones, E., The identification of semen and other body fluids, in R. Saferstein (ed.), *Forensic Science Handbook*, 2005. New Jersey: Pearson Prentice Hall.

Jones, E.L. Jr. and J.A. Leon, Lugol's test reexamined again: Buccal cells. *J Forensic Sci*, 2004, **49**(1): 64–67.

Juusola, J. and J. Ballantyne, Messenger RNA profiling: A prototype method to supplant conventional methods for body fluid identification. *Forensic Sci Int*, 2003, **135**(2): 85–96.

Juusola, J. and J. Ballantyne, Multiplex mRNA profiling for the identification of body fluids. *Forensic Sci Int*, 2005, **152**(1): 1–12.

Keating, S.M. and D.F. Higgs, The detection of amylase on swabs from sexual assault cases. *J Forensic Sci Soc*, 1994, **34**(2): 89–93.

Kennedy, D.M., et al., Microbial analysis of bite marks by sequence comparison of streptococcal DNA. *PLoS One*, 2012, **7**(12): e51757.

Lee, H.C., Identification and grouping of bloodstains, in R. Saferstein (ed.), *Forensic Science Handbook*, 1982. Englewood Cliffs, NJ: Prentice Hall.

Martin, N.C., N.J. Clayson, and D.G. Scrimger, The sensitivity and specificity of red-starch paper for the detection of saliva. *Sci Justice*, 2006, **46**(2): 97–105.

Miller, D.W. and J.C. Hodges, Validation of Abacus SALIgAE® test for the forensic identification of saliva, 2005. Available from: http://www.dnalabsinternational.com/SalivaValidation.pdf. Retrieved April 21, 2007.

Myers, J.R. and W.K. Adkins, Comparison of modern techniques for saliva screening. *J Forensic Sci*, 2008, **53**(4): 862–867.

Nakanishi, H., et al., A novel method for the identification of saliva by detecting oral streptococci using PCR. *Forensic Sci Int*, 2009, **183**(1–3): 20–23.

Nakanishi, H., et al., A simple identification method of saliva by detecting Streptococcus salivarius using loop-mediated isothermal amplification. *J Forensic Sci*, 2011, **56**(Suppl 1): S158–S161.

Nussbaumer, C., E. Gharehbaghi-Schnell, and I. Korschineck, Messenger RNA profiling: A novel method for body fluid identification by real-time PCR. *Forensic Sci Int*, 2006, **157**(2–3): 181–186.

Old, J.B., et al., Developmental validation of RSID-saliva: A lateral flow immunochromatographic strip test for the forensic detection of saliva. *J Forensic Sci*, 2009, **54**(4): 866–873.

Omelia, E.J., M.L. Uchimoto, and G. Williams, Quantitative PCR analysis of blood- and saliva-specific microRNA markers following solid-phase DNA extraction. *Anal Biochem*, 2013, **435**(2): 120–122.

Pandeshwar, P. and R. Das, Role of oral fluids in DNA investigations. *J Forensic Leg Med*, 2014, **22C**: 45–50.

Pang, B.C. and B.K. Cheung, Applicability of two commercially available kits for forensic identification of saliva stains. *J Forensic Sci*, 2008, **53**(5): 1117–1122.

Power, D.A., et al., PCR-based detection of salivary bacteria as a marker of expirated blood. *Sci Justice*, 2010, **50**(2): 59–63.

Pretty, I.A., The barriers to achieving an evidence base for bitemark analysis. *Forensic Sci Int*, 2006, **159**(Suppl 1): S110–S120.

Quarino, L., et al., Differentiation of α-amylase from various sources: An approach using selective inhibitors. *J Forensic Sci Soc*, 1993, **33**(2): 87–94.

Quarino, L., et al., An ELISA method for the identification of salivary amylase. *J Forensic Sci*, 2005, **50**(4): 873–876.

Ricci, U., I. Carboni, and F. Torricelli, False-positive results with amylase testing of citrus fruits. *J Forensic Sci*, 2014, **59**(5):1410–1412.

Rushton, C., et al., The distribution and significance of amylase-containing stains on clothing. *J Forensic Sci Soc*, 1979, **19**(1): 53–58.

Sabatini, L.M., Y.Z. He, and E.A. Azen, Structure and sequence determination of the gene encoding human salivary statherin. *Gene*, 1990, **89**(2): 245–251.

Sabatini, L.M., T. Ota, and E.A. Azen, Nucleotide sequence analysis of the human salivary protein genes HIS1 and HIS2, and evolution of the STATH/HIS gene family. *Mol Biol Evol*, 1993, **10**(3): 497–511.

Sakurada, K., et al., Evaluation of mRNA-based approach for identification of saliva and semen. *Leg Med* (*Tokyo*), 2009, **11**(3): 125–128.

Searcy, R.L., et al., The interaction of human serum protein fractions with the starch–iodine complex. *Clin Chim Acta*, 1965, **12**(6): 631–638.

Shaler, R.C., Modern forensic biology, in R. Saferstein (ed.), *Forensic Science Handbook*, 2nd edn., 2002. Upper Saddle River, NJ: Pearson Education.

Soukos, N.S., et al., A rapid method to detect dried saliva stains swabbed from human skin using fluorescence spectroscopy. *Forensic Sci Int*, 2000, **114**(3): 133–138.

Sweet, D., et al., An improved method to recover saliva from human skin: The double swab technique. *J Forensic Sci*, 1997, **42**(2): 320–322.

Uchimoto, M.L., et al., Considering the effect of stem-loop reverse transcription and real-time PCR analysis of blood and saliva specific microRNA markers upon mixed body fluid stains. *Forensic Sci Int Genet*, 2013, **7**(4): 418–421.

Vandenberg, N. and R.A. van Oorschot, The use of Polilight in the detection of seminal fluid, saliva, and bloodstains and comparison with conventional chemical-based screening tests. *J Forensic Sci*, 2006, **51**(2): 361–370.

Vennemann, M., et al., Sensitivity and specificity of presumptive tests for blood, saliva and semen. *Forensic Sci Med Pathol*, 2014, **10**(1): 69–75.

Wawryk, J. and M. Odell, Fluorescent identification of biological and other stains on skin by the use of alternative light sources. *J Clin Forensic Med*, 2005, **12**(6): 296–301.

Whitehead, P.H. and A.E. Kipps, A test paper for detecting saliva stains. *J Forensic Sci Soc*, 1975, **15**(1): 39–42.

Whitehead, P.H. and A.E. Kipps, The significance of amylase in forensic investigations of body fluids. *Forensic Sci*, 1975, **6**(3): 137–144.

Willott, G.M., An improved test for the detection of salivary amylase in stains. *J Forensic Sci Soc*, 1974, **14**(4): 341–344.

Willott, G.M. and M. Griffiths, A new method for locating saliva stains: Spotty paper for spotting spit. *Forensic Sci Int*, 1980, **15**(1): 79–83.

Zimmermann, B.G., N.J. Park, and D.T. Wong, Genomic targets in saliva. *Ann N Y Acad Sci*, 2007, **1098**: 184–191.

Zubakov, D., et al., Stable RNA markers for identification of blood and saliva stains revealed from whole genome expression analysis of time-wise degraded samples. *Int J Legal Med*, 2008, **122**(2): 135–142.

Zubakov, D., et al., New markers for old stains: Stable mRNA markers for blood and saliva identification from up to 16-year-old stains. *Int J Legal Med*, 2009, **123**(1): 71–74.

16

Identification of Vaginal Secretions and Menstrual Blood

The identification of vaginal secretions and menstrual blood is important for the investigation of sexual assault cases. Such identification can help to corroborate allegations of sexual assault. For example, in a sexual assault investigation, a stain was observed after examining the suspect's clothing. Subsequently, forensic DNA analysis revealed that the DNA of the stain originated from the victim, establishing a link between the victim and the suspect. However, the defendant may assert that the victim's DNA originated from a sweat stain as a result of casual contact and deny any criminal act. If vaginal secretions were found in the stain, the evidence has probative value to corroborate an allegation of a sexual act. Additionally, postcoital drainage stains on clothing or bedding are often recovered at crime scenes. These stains usually consist of a mixture of semen and vaginal secretions. In such cases, the presence of vaginal secretions in these stains indicates the occurrence of sexual intercourse. Sometimes, vaginal secretions can be transferred onto a perpetrator during a sexual assault. For example, the presence of vaginal secretions on a suspect's genital area can indicate the occurrence of sexual intercourse. Furthermore, the presence of vaginal secretions on an object can corroborate an allegation of vaginal rape with a foreign object.

If a sexual assault victim is in menses when an assault occurred, blood evidence, such as the victim's bloodstains located on the suspect's clothing, may be recovered at the scene. The defense may argue that the bloodstains resulted from an injury and deny that any sexual act occurred. In this case, the identification of menstrual blood would corroborate an alleged rape. Therefore, it is necessary to distinguish between peripheral and menstrual blood in investigations of sexual assault where blood evidence is found at the scene.

16.1 Identification of Vaginal Stratified Squamous Epithelial Cells

A normal human vagina is covered by the *squamous mucosa*, which is composed of stratified squamous epithelial tissue (Figure 16.1a). Lying under the squamous mucosa is the *submucosa*, which contains an abundance of connective tissue and capillaries. Below the submucosa is the *muscularis*, which is made up of smooth muscle.

The squamous mucosa consists of multiple layers of cells (Figure 16.1b). At the *basal layer* of the squamous mucosa, basal cells are anchored to the basement membrane that separates the squamous mucosa from the submucosa. The basal cells are small in size with relatively large nuclei and are highly proliferative. As the cells migrate up from the basal layer to the *parabasal layer*, the cells undergo differentiation. At the *intermediate layer*, the cells are flattened and their nuclei are compressed. As the epithelial cells reach the apical layer, the *superficial layer*, the cells are fully differentiated with small and dense nuclei.



Figure 16.1 Histological structure of human vaginal tissues. (a) The squamous mucosa and the submucosa. (b) Multiple layers of cells in the squamous mucosa. (© Richard C. Li.)

Vaginal epithelial cells do not accumulate keratin, which is different from skin cells (Chapter 4). The intermediate and superficial layer cells contain abundant glycogen in their cytoplasm. The presence of glycogen in these cells is an indication of normal development and the differentiation of the vaginal epithelial cells. The apical surface of the vaginal squamous mucosa is usually covered by mucus that is secreted from glands that are located deep in the epithelium. The cells of the apical layers are eventually sloughed and are continuously replaced by the cells of deeper layers. When the lining of the vagina is swabbed during the collection of evidence, glycogenated cells with small numbers of parabasal cells are usually recovered (Figure 16.2). In addition to the vagina, glycogenated squamous epithelial cells are found in the linings of the oral cavity, pharynx, esophagus, anus, and the apex of the urethra. The differentiation of the vaginal epithelial cells requires estrogen. However, in premenarche and postmenopausal women, estrogen levels are very low; thus, the vaginal epithelial cells only differentiate to the parabasal cells. Primarily, parabasal cells are found in specimens from these individuals.

16.1.1 Lugol's Iodine Staining and Periodic Acid–Schiff Method

Lugol's iodine solution, named after the French physician Jean Lugol, is originally used as an antiseptic that is applied to skin or tissue to prevent infection. In forensic applications, it is utilized for the identification of glycogenated vaginal epithelial cells. The technique is based on the



Figure 16.2 Vaginal stratified squamous epithelial cells. (© Richard C. Li.)

principle that iodine reacts with intracellular glycogen to exhibit a color. Glycogen is the principal storage form of glucose in animal and human cells and is found in the granules in the cytoplasm of the cells of many tissues. In addition to squamous epithelial cells, glycogen is also found in hepatocytes, which have the highest glycogen content, as well as muscle cells. Glycogen is a polysaccharide composed of D-glucose units. Similar to the amylopectin in plant cells (Chapter 15), glycogen is a branched polysaccharide consisting of linear and branched chains (Figure 16.3). The D-glucose residues of the linear chain are connected by α1→4 glycosidic bonds, while the branching points are connected by α1→6 glycosidic bonds. However, glycogen is more branched than



Figure 16.3 Structure of glycogen. Glycogen is a highly branched polysaccharide composed of glucose. Glycogen has a similar structure to amylopectin in starch (see Chapter 15). However, glycogen is more branched than starch. Additionally, glycogen contains a protein known as glycogenin at the center of its structure. (© Richard C. Li.)

amylopectin. Branch points occur approximately every 10 glucose residues in glycogen while they occur every 25 glucose residues in amylopectin. Lugol's stock solution is an aqueous solution of 5% iodine (I_2) and 10% potassium iodide (KI). Potassium iodide allows the iodine to be soluble in water through the formation of the triiodide ion. For staining the vaginal epithelial cells, 5% of the stock solution is usually used as the working solution. Iodine atoms fit into the helices of glycogen to form a dark brown glycogen–iodine complex (Figures 16.4 and 16.5). Vaginal epithelial cells can also be stained using the periodic acid–Schiff method. The cytoplasm of the vaginal epithelial cells is stained magenta, and the nucleus is stained purple.



Figure 16.4 Diagram of a glycogen–iodine complex. In the complex, the glycogen chain forms a helix structure with six monosaccharide residues (red) per turn. Iodine molecules (gray) fit in the helix to form the glycogen–iodine complex, exhibiting a color. (© Richard C. Li.)



(a) (b)

Figure 16.5 Epithelial cells stained with Lugol's iodine solution. (a) Vaginal and (b) buccal epithelial cells. (© Richard C. Li.)



Figure 16.6 Staining of epithelial cells with Dane's method. The results obtained using methanol fixation followed by Dane's staining on skin (a), buccal (b), and vaginal epithelial (c) cells are shown. The arrows indicate red nuclei in buccal and orange nuclei in vaginal cells. (From French, C.E., et al., *Forensic Sci Int*, 178, 1–6, 2008. With permission.)

16.1.2 Dane's Staining Method

Evidence containing skin, buccal, and vaginal epithelial cells is often recovered in forensic investigations, particularly in sexual assault cases. Thus, it is necessary to distinguish between these cells. Skin, buccal, and vaginal epithelial cells belong to stratified squamous epithelium. Differentiated skin epithelial cells are keratinized and are classified as keratinizing squamous epithelial cells, while buccal and vaginal epithelial cells are nonkeratinizing squamous epithelial cells. Additionally, the skin epithelial cells lose nuclei and other cellular organelles during differentiation. In contrast, buccal and vaginal cells contain nuclei. Based on their morphology, it is possible to distinguish skin epithelial cells from buccal and vaginal epithelial cells. However, buccal and vaginal cells are morphologically indistinguishable from each other. Although Lugol's iodine solution and periodic acid–Schiff can stain vaginal epithelial cells, these stains cannot distinguish vaginal from other glycogenated epithelial cells in the oral mucosa and the urinary tract. Recently, Dane's staining method has been developed to distinguish all three types of cells. Skin cells are stained red and orange; buccal cells are stained predominantly orange-pink with red nuclei; and vaginal cells are stained bright orange with orange nuclei (Figure 16.6).

16.2 Identification of Vaginal Acid Phosphatase

Acid phosphatases are a group of enzymes that are capable of hydrolyzing a variety of small organic phosphomonoesters under acidic conditions. To date, at least five different acid phosphatase isoenzymes have been identified in human tissues: erythroid acid phosphatase (encoded by the *ACP1* gene), lysosomal acid phosphatase (encoded by the *ACP2* gene), prostate acid phosphatase (encoded by the *ACPP* gene, also known as *ACP3*), macrophage acid phosphatase (encoded by the *ACP5* gene), and testicular acid phosphatase (encoded by the *ACPT* gene). Human prostatic acid phosphatase is found in large quantities in seminal fluid and is used as a biomarker for semen identification (Chapter 14). The prostatic acid phosphatase is a homodimer containing two identical subunits with a molecular weight of 50 kDa. Small amounts of acid phosphatase can be detected in vaginal fluid, which is produced in normal cervical epithelial cells. However, the molecular characteristics of vaginal acid phosphatase are still not known. Historically, vaginal acid phosphatase has been used as a biomarker for the identification of vaginal secretions using acid phosphatase catalytic assays (Chapter 14). In sexual assault investigations, it is important to distinguish vaginal acid phosphatase from prostate acid phosphatase originating from semen exposure. These two enzymes have identical molecular weights, enzymatic specificities, and responses to the same inhibitors. Nevertheless, vaginal and prostate acid phosphatases can be distinguished using agarose electrophoresis. Based on their electrophoretic mobility, bands of vaginal and prostate acid phosphatases can be separated. The prostate acid phosphatase



Figure 16.7 Distinguishing prostate and vaginal acid phosphatases using polyacrylamide gel electrophoresis. Bands of acid phosphatases are detected using 4-methylumbelliferyl phosphate (MUP). MUP is a substrate of acid phosphatases, resulting in a product that fluoresces in UV illumination (see Chapter 14). The prostate acid phosphatase has higher electrophoretic mobility toward an anode (a positively charged electrode) than vaginal acid phosphatase. S, semen; V, vaginal secretions; SV, mixture of semen and vaginal secretions; PAP, prostate acid phosphatase; VAP, vaginal acid phosphatase; MUP, 4-methylumbelliferyl phosphate; UV, ultraviolet illumination. (© Richard C. Li.)

has higher electrophoretic mobility toward an anode (a positively charged electrode) than the vaginal acid phosphatase (Figure 16.7). Thus, the presence of vaginal acid phosphatase can be determined.

16.3 Identification of Vaginal Bacteria

Lactobacillus can be found in the respiratory, the gastrointestinal, and the urogenital tract of healthy humans and animals. *Lactobacillus* taxa are the predominant bacteria in the vagina of women of reproductive age, and they play an important role in protecting the host against invasive pathogenic organisms. *Lactobacillus* consists of rod-shaped, nonmotile, and non-spore-forming gram-positive bacteria (Figure 16.8). Since these bacteria survive on carbohydrates, *Lactobacillus* bacteria produce lactic acid. As a result, a low pH environment is established in



Figure 16.8 Vaginal *Lactobacillus* bacteria (circled). (© Richard C. Li.)

the lumen of the vagina, which restricts the growth of pathogenic organisms. Such vaginal lactic acid–producing bacteria were thought to be *Lactobacillus acidophilus*. In the 1980s, it was determined that *L. acidophilus* was not a single species, but actually a group of related species known as the *L. acidophilus* complex. The species of the complex can now be distinguished based on their DNA sequences. The most frequently occurring *Lactobacillus* species found in the vagina are *L. iners*, *L. crispatus*, *L. gasseri*, and *L. jensenii*. Among them, *L. iners* is the most common species of *Lactobacillus* in women. *Lactobacillus* can be identified based on the sequences of DNA markers such as the 16S rRNA gene and the intergenic spacer region between the 16S rRNA and 23S rRNA genes (Chapter 11). In forensic applications, *L. iners*, *L. crispatus*, *L. gasseri*, and *L. jensenii* can be detected in vaginal secretions. Thus, the identification of *Lactobacillus* taxa can potentially be utilized for the forensic identification of vaginal fluid. However, the presence of *Lactobacillus* taxa is not specific enough to vaginal fluid. Some studies show that *Lactobacillus* taxa are present in semen while others show that *Lactobacillus* can be found in female urine. The openings of the female urogenital system are in close proximity; thus, it is possible to have partially overlapping microbiota between the urine and vaginal secretions. Thus, the identification of multiple bacterial species, at least the four *Lactobacillus* species previously mentioned, should be carried out to distinguish these samples.

16.4 Outlook for Confirmatory Assays of Vaginal Secretions

The identification of the vaginal stratified squamous epithelial cells provides important probative evidence in forensic investigations. However, the existing methods described earlier can sometimes give false-negative or false-positive results. In some situations, these assays also cross-react with other types of bodily fluids. Thus, none of these assays is confirmatory. A useful identification method for vaginal secretions should be able to distinguish vaginal secretions from other bodily fluids and should be easy to perform. For example, nondestructive confirmatory identification methods such as fluorescence spectroscopy and Raman spectroscopy (Chapter 11) can potentially be useful for the identification of vaginal secretions. Recently, the analysis of tissue-specific gene expression has been utilized for the identification of vaginal secretions. Using the reverse transcription polymerase chain reaction (RT-PCR) technique (Chapter 7), the mRNAs of the tissue-specific genes of vaginal epithelial cells can be detected. For example, two commonly used markers for vaginal secretion identification are *MUC4* and *HBD1*. *MUC4* encodes a mucin protein that is a major component of vaginal mucus, and *HBD1*, the human β defensin 1, encodes a vaginal antimicrobial peptide. Both *MUC4* and *HBD1* are expressed in vaginal epithelial cells and are considered reliable markers of vaginal fluid. Additional mRNA and miRNA markers are described in Tables 16.1 and 16.2.

16.5 Menstruation

Menstruation is the periodic discharge of blood and the elimination of the degenerated lining of the endometrium from the uterus of nonpregnant women. From menarche to menopause, women may menstruate up to 400 times during their reproductive age. The uterus plays an important role in preparing the uterine endometrium for the possible implantation of a developing embryo. The linings of the uterus are composed of the myometrium and the endometrium. The *myometrium* consists of the muscle fibers of the uterus. The *endometrium* consists of the simple columnar epithelium and the stroma (Figure 16.9). The simple columnar epithelium is formed by single-layered elongated cells located at the apical surface of the endometrium. The stroma consists of connective tissues as well as spiral arteries. Spiral arteries are small arteries that ascend through the endometrium and form a coil-like structure, which supplies blood to the endometrium.

Table 16.1 Representative Markers of mRNA-Based Assays for Vaginal Secretions and Menstrual Blood Identification

Biological Fluid	Gene Symbol	Description
Vaginal secretions	*CYP2B7P1*	Cytochrome P450, family 2, subfamily B, polypeptide 7, pseudogene 1
	DKK4	Dickkopf homolog 4
	FUT6	Fucosyltransferase 6
	HBD1	β Defensin 1
	IL19	Interleukin 19
	MUC4	Mucin 4
	MYOZ1	Myozenin 1
	SFTA2	Surfactant associated 2
Menstrual blood	*MMP7*	Matrix metalloproteinase 7
	MMP11	Matrix metalloproteinase 11

Source: Adapted from Bauer, M. and Patzelt, D., *J Forensic Sci*, 47, 1278–1282, 2002; Hanson, E.K. and Ballantyne, J., *Sci Justice*, 53, 14–22, 2013; Juusola, J. and Ballantyne, J., *Forensic Sci Int*, 152, 1–12, 2005; Nussbaumer, C., Gharehbaghi-Schnell, E., and Korschineck, I., *Forensic Sci Int*, 157, 181–186, 2006.

Table 16.2 miRNA Markers for Vaginal Secretions and Menstrual Blood Identification

Bodily Fluid	miRNA Marker	Sequence
Vaginal secretions	miR124*a*	UAAGGCACGCGGUGAAUGCC
	miR372	AAAGUGCUGCGACAUUUGAGCGU
	miR617	AGACUUCCCAUUUGAAGGUGGC
	miR891a	UGCAACGAACCUGAGCCACUGA
Menstrual blood	miR214	UGCCUGUCUACACUUGCUGUGC
	miR412	ACUUCACCUGGUCCACUAGCCGU
	miR451	AAACCGUUACCAUUACUGAGUU

Source: Adapted from Hanson, E.K., Lubenow, H., and Ballantyne, J., *Anal Biochem*, 387, 303–314, 2009; Wang, Z., et al., *Forensic Sci Int Genet*, 7, 116–123, 2013.

16.5.1 Uterine Cycle

The endometrium can be divided into two zones: the functionalis and the basalis (Figure 16.10). The *functionalis* is the luminal part of the endometrium. It is the zone of cyclic changes in the endometrium and is shed during menstruation. The *basalis* is the basal part of the endometrium and is not shed during menstruation. This zone produces cells to regenerate the functionalis during the next cycle.


Epithelium
Stroma
(a)
(b)

Figure 16.9 Uterus endometrium. (a) The proliferative phase and (b) the menstrual phase. (© Richard C. Li.)

During the uterine cycle, repetitive physiological changes occur in the functionalis (Figure 16.10). The cycle is divided into three phases: the menstrual, proliferative, and secretory phases. The first day of menstrual bleeding is considered the onset of the menstrual phase. During the menstrual phase, the functionalis degenerates and is sloughed off from the uterine wall and bleeding occurs, known as menses. During the proliferative phase, the functionalis begins regeneration in which the spiral arteries are proliferated. During the secretory phase, the spiral arteries are further developed and coiled. In the absence of pregnancy, a decrease in the progesterone level leads to the constriction of the spiral arteries. As a result, the functionalis becomes ischemic (insufficient blood flow), leading to hypoxia (low levels of oxygen in tissue). In addition, the activation of an enzymatic degradation process causes the destruction and


Stroma
Epithelium
Capillary
Uterine gland
Spiral artery
Functionalis
Basalis
D1
D5
D10
D15
D20
D25
Menstrual phase
Proliferative phase
Secretory phase

Figure 16.10 Changes in the functionalis of the uterine mucosa during a uterine cycle. D, day. (© Richard C. Li.)

shedding of the functionalis during menses. Menstrual fluid contains blood, the functionalis layer tissue, and mucus.

16.5.2 Uterine Endometrial Hemostasis

The cessation of menstrual bleeding is achieved by endometrial *hemostasis* that is initiated when injury occurs due to the shedding of the endometrium (Figure 16.11). Hemostasis begins with platelet activation and aggregation to form platelet plugs at the site of injury. Additionally, the blood coagulation cascade is activated to produce *thrombin*. Thrombin, a serine protease, converts soluble fibrinogen into fibrin. Fibrin, a protein involved in blood clotting, aggregates with the platelet plugs and leads to the cessation of bleeding by forming blood clots, known as *thrombi*. Under normal physiological conditions, uterine endometrial hemostasis is a balanced process between blood coagulation and clot dissolution to control blood loss and to prevent clot accumulation within the uterus. As a result, the balance of these two processes allows the removal of tissue fragments from the uterus cavity in order to reduce the risks of infection. Blood clots are prevented from accumulating during menstruation by forming low amounts of platelet plugs and synthesizing coagulation factor inhibitors that inhibit blood coagulation. Additionally, *fibrinolysis* is activated, during which thrombus is broken down by a protease known as *plasmin*. Plasmin cleaves fibrin, generating soluble degradation products. As a result, fibrinolysis can inhibit blood clot formation.



Figure 16.11 Diagram of hemostasis. Hemostasis occurs at the site of injury of a blood vessel. A platelet plug is formed as a result of the aggregation of platelets. The plug is further stabilized by the formation of a fibrin clot over the platelet plug. (© Richard C. Li.)

16.6 D-dimer Assay

During fibrinolysis, cross-linked fibrin is cleaved by plasmin, producing a degradation product known as *D-dimer* (Figure 16.12). Assays for D-dimer fragments have been utilized in the forensic identification of menstrual blood. A number of different formats of D-dimer assays can be used. In an enzyme-linked immunosorbent assay (ELISA; Chapter 11), antibodies bind to the D-dimer antigens on the solid phase. The D-dimer–antibody complex is subsequently analyzed using an antibody-based detection system. This method is highly sensitive, but is time-consuming. Latex agglutination assays are based on the interaction of antibodies and D-dimers that are located on carriers to form aggregates during the agglutination process (Chapter 11). However, the magnitude of the agglutination response is manually read and conclusions are based on subjective judgments. Immunochromatographic assays (Chapter 11) utilize monoclonal antibodies specific to D-dimers, which have been developed recently (Figures 16.13 and 16.14). This immunochromatographic assay is very specific, sensitive, and rapid, and can be completed within minutes. The immunochromatographic devices are portable, and thus can potentially be used at crime scenes. The D-dimer assays can positively identify menstrual blood samples. Although peripheral blood contains low levels of D-dimer, these assays do not show positive reactions with peripheral blood. Thus, menstrual blood can be distinguished from peripheral blood using D-dimer assays. However, postmortem blood also contains these D-dimers, which are detected by these assays. Although the detection of postmortem blood would complicate the interpretation of results, postmortem blood is not often encountered in sexual assault cases.



Figure 16.12 The formation and the degradation of a fibrin polymer. The activation of coagulation ultimately generates thrombin, which catalyzes the conversion of fibrinogen to fibrin by cleaving the fibrinopeptides (gray). A fibrin monomer contains an E domain and two D domains. The fibrin monomers are held together by noncovalent bonds (dotted red) between the D domains and E domain to form a fibrin polymer. Fibrin polymers are then covalently linked (solid red) to form a cross-linked fibrin polymer, which plays a role in forming clots. During fibrinolysis, plasmin cleaves the cross-linked fibrin at multiple sites giving rise to fibrin degradation products including D-dimer. (© Richard C. Li.)


Anti-D-dimer Ab
D-dimer
Bond anti-D-dimer Ab
Unbond anti-D-dimer Ab
Test zone
Control zone
D
E
D
S-S
(a)
(b)
(c)
(d)

Figure 16.13 Immunochromatographic assays for the identification of D-dimer in menstrual blood. (a) In a sample well, D-dimer antigen in a menstrual blood sample is mixed with labeled anti-D-dimer Ab. (b) The D-dimer binds to the labeled anti-D-dimer Ab to form a labeled Ab–antigen complex. (c) At the test zone, the labeled complex binds to an immobilized anti-D-dimer Ab to form a labeled Ab–antigen–Ab sandwich. (d) At the control zone, the labeled anti-D-dimer Ab binds to an immobilized antiglobulin and is captured at the control zone. Ab, antibody. (© Richard C. Li.)


10:55
DI-I
11:01
DI-PB

Figure 16.14 Detecting D-dimer using immunochromatographic assays. The results obtained using the Clearview Simplify D-dimer devices (Alere, Cheshire, UK) on menstrual (top) and peripheral blood (bottom) are shown. A positive result (arrow) indicates the presence of D-dimer. (From Baker, D.J., Grimes, E.A., and Hopwood, A.J., *Forensic Sci Int*, 212, 210–214, 2011. With permission.)

16.7 Lactate Dehydrogenase Assay

Lactate dehydrogenase (LDH) is an enzyme that plays an important role in glycolysis. In humans, LDH catalyzes the reversible reduction of pyruvate into lactate when the amount of oxygen is limited. LDH is a tetrameric enzyme consisting of three different types of subunits. The A subunit, also known as the M subunit, is encoded by the *LDHA* gene and is primarily expressed in skeletal muscle. The B subunit, also known as the H subunit, is encoded by the *LDHB* gene and is primarily expressed in cardiac muscle. The C subunit, encoded by the *LDHC* gene, is expressed restrictively in the testes. LDHs are found in various human tissues. Five isoenzymes can be found in blood (Figure 16.15). LDH1 consists of four identical B subunits; LDH2 consists of one A and three B subunits; LDH3 consists of two A and two B subunits; LDH4 consists of three A and one B subunits; and LDH5 consists of four identical A subunits. The five isoenzymes can be separated using electrophoresis (Figure 16.16) and detected using a colorimetric assay (Figures 16.17 and 16.18). According to their electrophoretic mobility, five bands can be identified. LDH1 has the highest electrophoretic mobility (toward an anode that is a positively charged electrode) and LDH5 has the lowest electrophoretic mobility. In peripheral blood, LDH1, 2, and 3 are the predominant forms of the isoenzymes and LDH4 and 5 are the minor forms of the isoenzymes. In contrast, LDH4 and 5 are consistently the predominant isoenzymes in menstrual blood, while the amounts of LDH1, LDH2, and LDH3 vary. Thus, menstrual blood can be distinguished from peripheral blood. LDH was historically used as a marker for the forensic identification of menstrual blood.



Figure 16.15 Isozymes of lactate dehydrogenase. Human lactate dehydrogenases are composed of four subunits. Five types of isozymes with their subunits are shown. A, LDH A subunit; B, LDH B subunit.



Figure 16.16 Electrophoretic separation of lactate dehydrogenase (LDH) isozymes. Extracted blood samples are loaded onto a cellulose acetate membrane. Electrophoresis is then carried out. Separated bands of LDH isozymes are detected using a colorimetric assay (see Figure 16.15). M, menstrual blood; P, peripheral blood. (© Richard C. Li.)



Figure 16.17 Detecting LDH activity using a colorimetric assay forming a colored dye. At the start of a cascade reaction, the LDH catalyzes the conversion of lactic acid to pyruvic acid. Nicotinamide adenine dinucleotide (NAD^+) is then reduced to $NADH/H^+$. Subsequently, Meldola's Blue (MB; 8-dimethylamino-2-benzophenoxazine), an electron carrier, transfers H/H^+ from $NADH/H^+$ to a tetrazolium salt. The pale yellow tetrazolium salt, nitroblue tetrazolium (NBT), is reduced to form a purple formazan dye.



Figure 16.18 The reduction and oxidation of Meldola's Blue. Meldola's Blue is an electron carrier, which transfers hydrogen atoms (coupled to electron transfer).

16.8 RNA-Based Assays

Matrix metalloproteinase (MMP) genes are considered tissue-specific markers for human endometrium tissues. MMPs are zinc-dependent endopeptidases that degrade extracellular matrix components. Additionally, they cleave other proteins such as cytokines, chemokines, and growth factors. The *extracellular matrix* (ECM) is the extracellular space of tissue that is filled by macromolecules such as collagens, laminins, fibronectins, and proteoglycans. The ECM can be divided into two categories: the interstitial matrix and the basement membrane. The interstitial matrices are located in the intercellular spaces. The basement membranes are thin layers of macromolecule fibers that usually lie under the epithelium and the endothelium. Both the interstitial matrices and the basement membranes provide structural support to the cells. It is proposed that MMPs play an important role in the degradation of ECM, leading to the destruction of endometrium tissues during the uterine cycle. To date, a total of 23 MMPs, divided into five subgroups, have been found in humans. The most commonly used markers for the forensic identification of menstrual blood are *MMP7* and *MMP11* (Table 16.1).

Many MMPs are expressed in human endometrium throughout the uterine cycle. The patterns of the MMP gene expressions are correlated with their functions in endometrium tissue breakdown during menstruation. *MMP7* is predominantly expressed in epithelial cells, while *MMP11* is expressed in the stromal cells of the endometrium. Both *MMP7* and *MMP11* mRNA expressions are elevated at the menstrual phase and remain at high levels during the proliferative phase. It is also known that MMPs' mRNA may be elevated in postpartum, wound healing, and metastatic cancer conditions, which may potentially lead to a false-positive identification of menstrual blood.

In menstrual blood samples, among all of the MMP genes tested, *MMP11* is the most sensitive and specific marker for distinguishing menstrual blood from peripheral blood. Using the RT-PCR technique (Chapter 7), *MMP11* mRNA can be detected in menstrual blood from the first to the eighth day of menstruation but it is absent in peripheral blood and vaginal secretions. Therefore, *MMP11* can be used as a marker for the identification of menstrual blood. Likewise, *MMP7* is also a useful marker for menstrual blood identification. However, the *MMP7* mRNA level in menstrual blood is less than that of *MMP11*. Additional markers such as miRNA markers for menstrual blood identification are included in Table 16.2.

Bibliography

Ablett, P.J., The identification of the precise conditions for seminal acid phosphatase (SAP) and vaginal acid phosphatase (VAP) separation by isoelectric focusing patterns. *J Forensic Sci Soc*, 1983, **23**(3): 255–256.

Adams, E.G. and Wraxall, B.G., Phosphatases in body fluids: The differentiation of semen and vaginal secretion. *Forensic Sci*, 1974, **3**: 57–62.

Akutsu, T., et al., Evaluation of latex agglutination tests for fibrin-fibrinogen degradation products in the forensic identification of menstrual blood. *Leg Med (Tokyo)*, 2012, **14**(1): 51–54.

Akutsu, T., et al., Detection of bacterial 16S ribosomal RNA genes for forensic identification of vaginal fluid. *Leg Med (Tokyo)*, 2012, **14**(3): 160–162.

Albrecht, K., et al., Immunohistochemical distribution of cyclic nucleotide phosphodiesterase (PDE) isoenzymes in the human vagina: A potential forensic value? *J Forensic Leg Med*, 2007, **14**(5): 270–274.

Alsawaf, K. and A.T. Tu, Isotachophoretic analysis of bloodstains: Differentiation of human, menstrual, bovine, and ovine bloods. *J Forensic Sci*, 1985, **30**(3): 922–930.

Baker, D.J., E.A. Grimes, and A.J. Hopwood, D-dimer assays for the identification of menstrual blood. *Forensic Sci Int*, 2011, **212**(1–3): 210–214.

Bauer, M. and D. Patzelt, Evaluation of mRNA markers for the identification of menstrual blood. *J Forensic Sci*, 2002, **47**(6): 1278–1282.

Bauer, M. and D. Patzelt, Identification of menstrual blood by real time RT-PCR: Technical improvements and the practical value of negative test results. *Forensic Sci Int*, 2008, **174**(1): 55–59.

Benschop, C.C., et al., Vaginal microbial flora analysis by next generation sequencing and microarrays; can microbes indicate vaginal origin in a forensic context? *Int J Legal Med*, 2012, **126**(2): 303–310.

Divall, G.B. and M. Ismail, Lactate dehydrogenase isozymes in vaginal swab extracts: A problem for the identification of menstrual blood. *Forensic Sci Int*, 1983, **21**(2): 139–147.

Ferri, G., et al., Successful identification of two years old menstrual bloodstain by using MMP-11 shorter amplicons. *J Forensic Sci*, 2004, **49**(6): 1387.

Fleming, R.I. and S. Harbison, The use of bacteria for the identification of vaginal secretions. *Forensic Sci Int Genet*, 2010, **4**(5): 311–315.

French, C.E., et al., A novel histological technique for distinguishing between epithelial cells in forensic casework. *Forensic Sci Int*, 2008, **178**(1): 1–6.

Fujita, Y., I. Tokunaga, and S.I. Kubo, Forensic identification of a vaginal fluid and saliva mixture through DNA analysis. *Acta Criminologiae et Medicinae Legalis Japonica*, 2003, **69**(2): 48–52.

Giampaoli, S., et al., Molecular identification of vaginal fluid by microbial signature. *Forensic Sci Int Genet*, 2012, **6**(5): 559–564.

Gray, D., N. Frascione, and B. Daniel, Development of an immunoassay for the differentiation of menstrual blood from peripheral blood. *Forensic Sci Int*, 2012, **220**(1–3): 12–18.

Hanson, E.K. and J. Ballantyne, Highly specific mRNA biomarkers for the identification of vaginal secretions in sexual assault investigations. *Sci Justice*, 2013, **53**(1): 14–22.

Hanson, E.K., Lubenow, H., and Ballantyne, J., Identification of forensically relevant body fluids using a panel of differentially expressed microRNAs. *Anal Biochem*, 2009, **387**: 303–314.

Hausmann, R. and B. Schellmann, Forensic value of the Lugol's staining method: Further studies on glycogenated epithelium in the male urinary tract. *Int J Legal Med*, 1994, **107**(3): 147–151.

Jakubowska, J., et al., mRNA profiling for vaginal fluid and menstrual blood identification. *Forensic Sci Int Genet*, 2013, **7**(2): 272–278.

Jones, E., The identification of semen and other body fluids, in R. Saferstein (ed.), *Forensic Science Handbook*, pp. 329–399, 2005. Upper Saddle River, NJ: Pearson Prentice Hall.

Juusola, J. and J. Ballantyne, Multiplex mRNA profiling for the identification of body fluids. *Forensic Sci Int*, 2005, **152**(1): 1–12.

Kaur, G. and V.K. Sharma, The determination of esterase D in menstrual blood stains. *Adli Tip Dergisi*, 1988, **4**(1–2): 3–9.

Metropolitan Police Forensic Science Laboratory, *Biology Methods Manual*, p. 5, 1978. London: Metropolitan Police Forensic Science Laboratory.

Miyaishi, S., et al., Identification of menstrual blood by the simultaneous determination of FDP-D-dimer and myoglobin contents. *Nihon Hoigaku Zasshi*, 1996, **50**(6): 400–403.

Nussbaumer, C., E. Gharehbaghi-Schnell, and I. Korschineck, Messenger RNA profiling: A novel method for body fluid identification by real-time PCR. *Forensic Sci Int*, 2006, **157**(2–3): 181–186.

Omelia, E.J., M.L. Uchimoto, and G. Williams, Quantitative PCR analysis of blood- and saliva-specific microRNA markers following solid-phase DNA extraction. *Anal Biochem*, 2013, **435**(2): 120–122.

Peabody, A.J., R.M. Burgess, and R.E. Stockdale, Re-examination of the Lugol's iodine test, pp. 1–18, 1981. Aldermaston: Home Office Central Research Establishment.

Peri, S. and P.K. Chattopadhyay, Differentiation of menstrual blood from other blood stains. *J Forensic Med Toxicol*, 2000, **17**(1): 6–11.

Peri, S. and P.K. Chattopadhyay, Studies on menstrual bloodstains: For species origin and blood groups. *Int J Med Toxicol Leg Med*, 2000, **2**(2): 1–8.

Plac-Bobula, E. and B. Turowska, Identification of menstrual bloodstains by determination of lactate dehydrogenase isoenzymes. *Arch Med Sadowej Kryminol*, 1979, **29**(4): 263–267.

Randall, B., Glycogenated squamous epithelial cells as a marker of foreign body penetration in sexual assault. *J Forensic Sci*, 1988, **33**(2): 511–514.

Sakurada, K., et al., Expression of statherin mRNA and protein in nasal and vaginal secretions. *Leg Med (Tokyo)*, 2011, **13**(6): 309–313.

Sikirzhytskaya, A., V. Sikirzhytski, and I.K. Lednev, Raman spectroscopic signature of vaginal fluid and its potential application in forensic body fluid identification. *Forensic Sci Int*, 2012, **216**(1–3): 44–48.

Simons, J.L. and S.K. Vintiner, Efficacy of several candidate protein biomarkers in the differentiation of vaginal from buccal epithelial cells. *J Forensic Sci*, 2012, **57**(6): 1585–1590.

Stombaugh Jr, P.M. and J.J. Kearney, Factors affecting the use of lactate dehydrogenase as a means of bloodstain differentiation. *J Forensic Sci*, 1978, **23**(1): 94–105.

Takasaka, T., et al., Trials of the detection of semen and vaginal fluid RNA using the genome profiling method. *Leg Med (Tokyo)*, 2011, **13**(5): 265–267.

Thompson, J. and K. Belschner, Differentiation of various menstrual bloodstains using LDH. *Calif Depart Justice Tie-Line*, 1997, **21**: 34–39.

Wang, Y.X., et al., A new method of identifying the peripheral blood and the menstrual blood. *Fa Yi Xue Za Zhi*, 2012, **28**(5): 359–361.

Wang, Z., et al., Screening and confirmation of microRNA markers for forensic body fluid identification. *Forensic Sci Int Genet*, 2013, **7**: 116–123.

Whitehead, P.H. and G.B. Divall, Assay of "soluble fibrinogen" in bloodstain extracts as an aid to identification of menstrual blood in forensic science. Preliminary findings. *Clin Chem*, 1973, **19**(7): 762–765.

Yang, H., et al., Proteomic analysis of menstrual blood. *Mol Cell Proteomics*, 2012, **11**(10): 1024–1035.

Yao, Y.N., H.L. Lu, and S. Chen, Preparation of anti-human MMP-11 polyclonal antibody for forensic application. *Chin J Forensic Med*, 2007, **22**(5): 305–307, 310.

Yao, Y.N., et al., Detection of MMP-11 from menstrual blood using immunohistochemistry. *Fa Yi Xue Za Zhi*, 2008, **24**(1): 32–33.

Zhang, Y.Q., H.L. Lu, and Y.N. Yao, Detection of matrix metalloproteinase-11 in menstrual blood by enhanced chemiluminescence method. *Fa Yi Xue Za Zhi*, 2012, **28**(2): 109–111.

Zheng, J., H.L. Lu, and S. Chen, Menstrual blood identification and matrix metalloproteinase-11. *Fa Yi Xue Za Zhi*, 2006, **22**(1): S1–S3.

17

Identification of Urine, Sweat, Fecal Matter, and Vomitus

17.1 Identification of Urine

The identification of the presence of urine is useful for the forensic investigation of an alleged sexual assault and harassment involving urination. More importantly, the identification of urine stains can aid in the investigation of homicides involving either ligature or manual strangulation. In these incidents, strangulation victims often involuntarily excrete urine prior to death. The locations of urine stains at the crime scene provide useful information to determine the site where the violence has occurred.

17.1.1 Urine Formation

In humans, the urinary excretory system eliminates soluble toxic wastes that are cellular metabolic by-products. The urinary system consists of the kidney, the ureter, the urinary bladder, and the urethra (Figure 17.1). The formation of urine takes place in the kidneys and, in particular, in the nephrons. The *nephron* is the basic structural and functional unit of the kidney (Figures 17.2 and 17.3). Each nephron is composed of a glomerulus, a Bowman's capsule, and a renal tubule. The glomerulus is formed by a network of capillaries and is surrounded by a Bowman's capsule. *Filtration* is the first step in urine formation. As blood flows through the glomeruli, much of its fluid, except cells and large molecules, is filtered through the capillaries into the Bowman's capsule. The glomerular filtrate, the preliminary form of urine, consists of water, salts (largely sodium and potassium ions), glucose, and waste products such as urea. The filtrate is then passed through the renal tubule where *reabsorption* occurs. During the reabsorption process, water, glucose, nutrients, and ions such as sodium are reabsorbed back into the blood. The last process of urine formation is *secretion*. Secretion occurs at the distal and the collecting tubules of the nephron where ions (such as hydrogen and potassium ions), ammonia, and certain metabolites are secreted from the blood into the lumen of the renal tubule to be eliminated in the urine. The urine is drained from the kidneys through the ureters and is stored in the bladder before it is finally excreted through the urethra.

Urine is an aqueous solution consisting largely of water. Urea is the most abundant waste product in urine, resulting from the elimination of ammonia that is produced from the metabolic process of amino acids. The average urea concentration in human urine is approximately 9 g/L. Other major components are creatinine, uric acid, and ions such as phosphate, sulfate,



Figure 17.1 Human urinary system. A longitudinal view of the right kidney is shown. (© Richard C. Li.)

chloride, sodium, and potassium. Healthy individuals also excrete a small amount of protein. Urine has a characteristic yellow color. Subsequent to excretion from the body, urine acquires an odor that results from the ammonia that is released from the breakdown of urea by bacteria.

17.1.2 Presumptive Assays

In forensic identification, urine stains can be located by visual examination based on the characteristic yellow color of urine and the detection of the distinctive odor of urine stains. Under alternative light sources, urine stains emit a fluorescent light that facilitates the locating of urine stains in clothing and bedding. Chemical analysis can be carried out to detect the major inorganic anions in urine such as phosphate and sulfate as well as the major organic compounds in urine such as urea, creatinine, and uric acid. These assays are summarized in Table 17.1. However, these assays are not specific to urine. Other bodily fluids, such as sweat, also contain these chemical components.

17.1.2.1 The Identification of Urea

The *para-dimethylaminocinnamaldehyde* (DMAC) assay is simple and rapid and is the most commonly used presumptive assay for the forensic identification of urine stains (Figure 17.4). The DMAC assay can be performed using two different methods: the colorimetric and the fluorometric methods (Figure 17.5).

In the colorimetric method, a portion of a stain (~1 cm^2) is cut and is extracted with 1 mL of distilled water. The extraction is transferred onto a piece of filter paper and is allowed to dry. One drop of 0.1% DMAC solution is then added to the filter paper. DMAC reacts specifically with urea, if present, producing a pink-colored (or magenta-colored) product. DMAC does not react with creatinine, ammonia, or uric acid. The appearance of a pink color within 30 min after applying the DMAC reagent is considered a positive reaction. No color change within 30 min is


Efferent arteriole
Afferent arteriole
Glomerulus
Bowman's capsule
Collecting duct
Distal tubule
Proximal tubule
Cortex
Ascending limb
Descending limb
Loop of Henle
Medulla
Vasa recta

Figure 17.2 Diagram of the human nephron. (© Richard C. Li.)


Glumerulus
Bowman's capsule
Renal tubule

Figure 17.3 Section view of the human nephron. (© Richard C. Li.)

Table 17.1 Assays for Identification of Urine and Sweat

Biological Fluid	Assays	Identification	Assay	Method	Further Reading
Urine	Presumptive assays	Locating stains	Visual examination	Alternate light source	Wawryk and Odell (2005)
		Urea	DMAC assay	Colorimetric method	Ong et al. (2012)
				Fluorometric method	Farrugia et al. (2012)
			Microscopic crystal assay	Microscopic examination of urea crystals and urea nitrate crystals converted from urea	Nickolls (1956)
				Microscopic examination of crystals using xanthydrol	Biles and Ziobro (1998)
			Urease assay	The enzyme catalyzes the breakdown of urea and releases ammonia and carbon dioxide. The ammonia is detected using an acid-base indicator, bromthymol blue, which exhibits a blue color	Bedrosian et al. (1984)
				The ammonia is detected using Mn and Ag nitrates, which exhibit a black color	Gaensslen (1983)
			Chromatography	Gas chromatograph–mass spectrometer, thin-layer chromatography	Lum (1991)
		Creatinine	Colorimetric assay	Jaffe's test, using picric acid to convert creatinine to a red creatinine picrate compound	Greenwald (1930)
				Using potassium ferricyanide to produce a blue nitroprusside compound	O'Leary et al. (1992)
			Chromatography	Gas chromatograph–mass spectrometer	Lum (1991)

		Uric acid	Uricase assay	Measuring the disappearance of the absorption of uric acid at 293 nm after treatment with uricase that catalyzes the oxidation of uric acid to 5-hydroxyisourate	Kageyama (1971)
	Confirmatory assays	Tamm–Horsfall glycoprotein	Immunological assays	RIA, crossover electrophoresis, Ouchterlony, ELISA, and immunochromatographic methods	Tsutsumi et al. (1988)
		17-ketosteroids	Mass spectrometer	Liquid chromatograph–mass spectrometer	Nakazono et al. (2002)
Sweat	Presumptive assays	Lactate, lactic acid, urea, and single amino acids	Various	SEM coupled with EDX and Raman microspectroscopy	Sikirzhytski et al. (2011)
	Confirmatory assays	Dermcidin	Immunological assay	ELISA	Sagawa et al. (2003)
			RNA-based assay	RT-PCR	Sakurada et al. (2010)



Figure 17.4 Chemical reaction of DMAC assay.


(a) (b)

Figure 17.5 Positive reaction of DMAC assay of a urine stain. (a) Colorimetric and (b) fluorometric method. (© Richard C. Li.)

considered a negative reaction. However, this method is not specific to urine, as other bodily fluids such as saliva, semen, sweat, and vaginal secretions can also give positive reactions. A diluted DMAC solution, from 0.1% to 0.05%, can maintain appropriate sensitivity to urine stains and minimize false-positive reactions caused by the detection of low levels of urea that are present in other bodily fluids.

The fluorometric method is useful for locating urine stains on large pieces of evidence such as clothing and bedding (Figure 17.6). Additionally, this method can detect patterns of urine stains (Figure 17.7), which can be useful in crime scene reconstructions. In the fluorometric method, the evidence to be examined, such as a garment, is covered by a sheet of filter paper that has been preabsorbed with the DMAC solution. The evidence and the filter are then wrapped together in a sheet of aluminum foil and are left overnight in a press, ensuring that the evidence is in close contact with the filter paper. Alternatively, the layers can be heated for 30 s using an iron. Using a light source at 473–548 nm, the DMAC-treated urine stain fluoresces. The fluoresced stain is best observed with a 549 nm filter. However, colored fabrics interfere with the assay since dyes and pigments can inhibit the fluorescence.

In addition to the DMAC test, the identification of urea that is present in urine stains can be carried out by urease assays. Ureases catalyze the breakdown of urea, thus releasing ammonia and carbon dioxide (Figure 17.8). The ammonia is detected using an acid-base indicator, bromthymol blue, which exhibits a blue color. Alternatively, the ammonia can be detected by manganese and silver nitrates, which exhibit a black color. Additional assays such as microscopic crystal and chromatographic assays are summarized in Table 17.1.



Figure 17.6 Fluorometric DMAC assay of urine stains. Evidence item (a) is closely covered by a piece of moistened filter paper containing DMAC. The orientation of the paper is marked (b). The layers are pressed to allow the transfer of a small amount of the stain onto the paper and are heated using an iron (c). The paper is then lifted. The DMAC-treated urine stain fluoresces under a light source at 473–548 nm (d). (© Richard C. Li.)



Figure 17.7 Fluorometric DMAC enhancement of a footwear impression in urine on white cotton fabric. From left to right: urine impression, DMAC-treated urine stains under white light, and DMAC-treated urine stains using an excitation light source. (From Farrugia, K.J., et al., *Forensic Sci Int*, 214, 67–81, 2012. With permission.)



Figure 17.8 Biochemical reaction of urease.

17.1.2.2 Identification of Creatinine

Creatinine is produced during normal muscle cell metabolism (Figure 17.9). During this metabolism, phosphocreatine, an energy-storing molecule in muscle cells, breaks down to form creatine. Creatine is then metabolized to creatinine, which is released from the muscle cells into the blood. Serum creatinine is largely filtrated by the renal glomeruli. A small amount of creatinine is secreted by the renal distal tubules. The amount of creatinine excreted in urine is proportional to the muscle mass of an individual. However, creatinine is not only present in urine. It is also present in other bodily fluids such as blood and semen.

The creatinine present in urine can be detected using the Jaffe color test (Figure 17.10). In this test, picric acid is used to convert creatinine, under alkaline conditions, to form creatinine picrate, which is a bright red product. Additional tests for urine creatinine are summarized in Table 17.1. Recently, a Uritrace device (Abacus Diagnostics) has been made commercially available for the detection of creatinine.



Figure 17.9 Schematic view of the formation of creatinine.



Figure 17.10 Chemical reaction of Jaffe's assay.

17.1.3 Confirmative Assays

17.1.3.1 Identification of Tamm–Horsfall Protein

Tamm–Horsfall protein (THP), also known as *uromodulin*, is the most abundant protein in urine, and accounts for 40% of the urine proteins. THP is exclusively synthesized in the epithelial cells of Henle's loop. THP is secreted from the apical plasma membrane of the epithelial cells into the lumen. Under physiological conditions, an adult excretes 20–100 mg of THP into urine daily. The biological function of THP is not fully understood. It is speculated that it prevents the body from contracting urinary tract infections and from forming renal stones.

THP is a urine-specific biomarker for forensic urine identification. It can be detected using an enzyme-linked immunosorbent assay (ELISA). More recently, it can be detected using an immunochromatographic assay, RSID-Urine, which utilizes a polyclonal rabbit antibody that is specific to THP (Figures 17.11 and 17.12). This test is rapid and simple and thus can be used as a screening test in laboratories and as a field test at crime scenes to identify urine. The detection limit of RSID-Urine for THP is 0.5 μL of urine. Although the sensitivity of RSID-Urine is lower than that of ELISA detection of THP, it is sufficient for forensic applications. These methods are specific to THP that is present only in urine while no detection is found in other bodily fluids such as plasma, saliva, semen, vaginal fluid, or sweat.

17.1.3.2 Identification of 17-Ketosteroids

In humans, urine contains derivatives of 17-ketosteroids such as androsterone, dehydroepiandrosterone (DHEA), and etiocholanolone. *Androsterone* is a steroid hormone with a weak potency of testosterone. *DHEA* is a metabolic intermediate in the biosynthesis of the gonadal steroids. DHEA also has a potential function as a steroid hormone. *Etiocholanolone* is a metabolite of testosterone. These compounds are present in urine as conjugates, in which 17-ketosteroids



Figure 17.11 Immunochromatographic assays for the identification of THP in urine. (a) In a sample well, THP in a urine sample is mixed with labeled anti-THP Ab. (b) The THP binds to the labeled anti-THP Ab to form a labeled Ab–THP complex. (c) At the test zone, the labeled complex binds to an immobilized anti-THP Ab to form a labeled Ab–THP–Ab sandwich. (d) At the control zone, the labeled anti-THP Ab binds to an immobilized antiglobulin and is captured at the control zone. Ab, antibody; THP, Tamm–Horsfall protein antigen. (© Richard C. Li.)



Figure 17.12 Results obtained using immunochromatographic assays (RSID™-Urine; Independent Forensics, Lombard, IL) for the identification of THP in urine. From left to right: negative control, undiluted, 1:10 diluted, and 1:100 diluted urine samples. A visible blue line at the test (T) zone and control (C) zone indicates a positive result. The blue line at the control zone only indicates a negative result. (From Akutsu, T., Watanabe, K., and Sakurada, K., *J Forensic Sci*, 57, 1570–1573, 2012. With permission.)

are modified in the liver through glucuronidation and sulfation. In glucuronidation, glucuronic acids are added to 17-ketosteroids while in sulfation, sulfates are transferred to 17-ketosteroids. As a result, these conjugates, containing charged moieties, are more water soluble than the nonconjugated 17-ketosteroids. Thus, they are excreted into urine to be eliminated from the body. The five major components of the 17-ketosteroid conjugates present in human urine are androsterone glucuronide, androsterone sulfate, DHEA sulfate, etiocholanolone glucuronide, and etiocholanolone sulfate (Figure 17.13). Thus, the analysis of 17-ketosteroid conjugates in urine stains is useful for the identification of human urine stains. These five 17-ketosteroid conjugates can be identified using liquid chromatography–mass spectrometry (LC-MS). However, some of these 17-ketosteroid conjugates are also detected in serum. Therefore, the presence of all five conjugated 17-ketosteroids in a sample is required to identify a urine stain. Additionally, the profiles of the 17-ketosteroid conjugates are human specific and are distinguishable between humans and animals.

17.2 Identification of Sweat

Sweat is the least common bodily fluid analyzed in forensic laboratories compared with others that have been mentioned in previous chapters. However, sweat identification is still useful for forensic investigations. For example, forensic DNA analysis allows the generation of DNA profiles from trace biological evidence such as fingerprints. Identifying sweat can be important for the analysis of these types of evidence.

17.2.1 Biology of Perspiration

Humans have two types of secretory sweat glands: the eccrine and the apocrine sweat glands (Figure 17.14). *Eccrine* sweat glands are distributed almost all over the body and are controlled by the sympathetic nervous system. Eccrine sweat glands play a role in regulating body temperature. When the body temperature rises, eccrine sweat glands secrete a watery sweat to the skin's surface where heat is carried away through the evaporation of the sweat to maintain normal body temperature. In humans, *apocrine* sweat glands, which are associated with hair follicles, are usually restricted to the underarm and genital areas and are controlled by emotional stress. Apocrine sweat glands are inactive until puberty. This type of sweat gland secretes an oily sweat that is odorous after being processed by skin bacteria. The majority of sweat evidence that is analyzed in forensic laboratories is sweat stains secreted from eccrine glands. Sweat contains water, minerals, lactate, and urea. Its biochemical composition varies


Androsterone
UGT
Sulfotransferase
Androsterone glucuronide
Androsterone sulfate
Dehydroepiandrosterone
Sulfotransferase
Dehydroepiandrosterone sulfate
Etiocholanolone
UGT
Sulfotransferase
Etiocholanolone glucuronide
Etiocholanolone sulfate

Figure 17.13 Structural formula of 17-ketosteroids and 17-ketosteroid conjugates present in human urine. UGT, UDP glucuronosyltransferase. (© Richard C. Li.)

among individuals and their physical activities. Sweat contains low levels of constituents that are also present in other bodily fluids such as urine. Thus, it has been considered a difficult bodily fluid to identify.

17.2.2 Sweat Identification Assays

Sweat evidence has been analyzed using presumptive assays (Table 17.1) such as elemental analysis using scanning electron microscopes coupled with energy dispersive x-ray spectroscopy in the detection of lactic acid. Since sweat contains many inorganic and organic compounds that are also present in other bodily fluids, these assays are not specific to sweat. Raman



Figure 17.14 Diagram of the human eccrine and apocrine sweat glands. (© Richard C. Li.)

microspectroscopy is potentially useful for the identification of sweat for forensic purposes, which is based largely on the profiles of lactate, lactic acid, urea, and single amino acids in urine.

Recently, *dermcidin* has been identified as a potential biomarker of human sweat. Dermcidin belongs to a class of human antimicrobial peptides of the innate immune defense system and plays an important role in protecting epithelial barriers from infections. Dermcidin, specifically expressed in eccrine sweat glands (Figure 17.15), is secreted into the sweat and is transferred to the epidermal surface. In forensic applications, dermcidin can potentially be utilized as a biomarker for the confirmatory assay of sweat identification. The detection of dermcidin in sweat stains can be performed using ELISA assays utilizing antibodies specific to human dermcidin. This method is highly sensitive and is able to detect dermcidin in sweat samples that are diluted 10,000-fold. Dermcidin is encoded by the *DCD* gene. Its mRNA can be detected using reverse transcription polymerase chain reaction (RT-PCR) assays (Chapter 7) that can detect *DCD* mRNA in 10 μL of sweat sample. Dermcidin assays are also specific to sweat as dermcidin is not detected in other bodily fluids such as semen, saliva, and urine.

17.3 Identification of Fecal Matter

The examination of feces has been used in criminal investigations for over a century. Specifically in 1948, a burglary case was reported using fecal analysis to link the shoes of a suspect to a crime scene. One of the aspects of fecal analysis is to determine a common origin of the reference sample and the fecal evidence, thus potentially linking a suspect to a crime scene. Today, the individual characteristics of a fecal sample can be effectively determined using forensic DNA analysis of sloughed intestinal epithelial cells that are present in fecal matter. The identification of fecal matter is valuable in providing important information for a criminal investigation. For example, the presence of fecal matter may corroborate a sexual



Figure 17.15 Localization of the dermcidin peptide in the sweat glands. Skin tissue sections are treated with a dermcidin antibody and stained. (a) Both the eccrine and apocrine sweat glands are shown. Only cells of the eccrine gland in the skin express dermcidin (brown stained). Arrows: eccrine sweat glands. Arrowheads: apocrine sweat glands. Scale bar: 100 μm. (b) Close-up view of the eccrine gland. The presence of the dermcidin peptide is observed (brown). Scale bar: 10 μm. (From Sagawa, K., et al., *Int J Legal Med*, 117, 90–95, 2003. With permission.)

assault involving sodomy, assault with fecal matter, vandalism, and burglary during which the perpetrator defecated at the scene.

17.3.1 Fecal Formation

Feces are a type of waste matter that is the direct result of food that has been processed by the digestive system (Figure 17.16). Human feces contain undigested foodstuffs, sloughed intestinal epithelial cells, intestinal bacteria, bile pigments, electrolytes, and water. Feces are formed in the intestines during the last phase of digestion. Feces first enter the colon in liquid form. Most of the nutrients are absorbed on the surface area of the small intestine. In the large intestine, water, sodium, and chloride are absorbed on the surface of the lumen. The remaining luminal contents are converted into feces. Food stays for approximately 2–6 h in the stomach. It takes an additional 3–5 h to travel through the small intestine and 12–24 h to travel through the large intestine.

17.3.2 Fecal Matter Identification Assays

A fecal analysis includes macroscopic and microscopic examination, chemical tests, and fecal bacterial identification.



Figure 17.16 Diagram of the human digestive system. The esophagus, stomach, liver, gallbladder, pancreas, small intestine (duodenum, jejunum, and ileum), and large intestine (cecum, colon, appendix, and rectum) are shown. (© Richard C. Li.)

17.3.2.1 Macroscopic and Microscopic Examination

The color and odor of human feces are useful characteristics for fecal identification. The normal brown color of feces primarily results from the presence of urobilinoids, which are heme catabolic by-products. The characteristic odor of feces is caused by the metabolic by-products of the intestinal bacterial flora. Indole, skatole, and hydrogen sulfide are the compounds that are responsible for the odor of feces.

When fecal stains are analyzed, the microscopic examination of the feces can be performed on an aliquot of fecal suspension. The presence of characteristic undigested foodstuffs can indicate human feces. Fecal matter can be transferred from samples of clothing by scraping with a sterile stainless steel spatula. The fecal matter is then hydrated in 6% formalin solution for 24–48 h prior to microscopic examination. Undigested foodstuffs such as vegetable fragments and meat fibers are often present in human feces. Vegetable fragments (Figure 17.17) are often undigested vegetable dermal tissues that cover and protect the plant and fragments of vascular tissues that play roles in transporting water and nutrients throughout the plant. The types of vegetables can be identified by comparing the observed fragments with known plants. Meat fibers (Figure 17.18) are undigested animal skeletal muscle fibers. These fibers have characteristic striations, usually rectangular in shape, that are used for comparison with known animal tissues.



Figure 17.17 Scallion vascular tissue (top) and dermal tissue (bottom). (© Richard C. Li.)



Figure 17.18 Cattle meat fibers. (© Richard C. Li.)

17.3.2.2 Urobilinoids Tests

The forensic analysis of fecal matter often involves the identification of fecal stains on swabs and clothing from which small amounts of sample may be available. Chemical tests can be useful for the analysis of fecal stains. By far the most common chemical test performed on feces is the detection of urobilinoids. *Urobilinoids*, including urobilin and stercobilin, are generated from the degradation of heme and are excreted into feces.

The average lifetime of erythrocytes is approximately 3–4 months. Erythrocytes are continuously undergoing hemolysis in which erythrocytes are naturally broken down and are usually processed in the reticuloendothelial system of the spleen. Hemoglobin is released daily during the hemolysis process and is degraded into heme, globin, and iron. Other sources of heme are derived from the degradation of erythrocyte precursors in bone marrow and other heme-containing proteins such as myoglobin and cytochromes. In the peripheral tissues, heme undergoes catabolism to form *bilirubin* (Figures 17.19 and 17.20). Bilirubin is further converted to *urobilinogen* in the intestine. A portion of urobilinogen is reduced to *stercobilinogen*. In the large intestine, the spontaneous oxidation of urobilinogen and stercobilinogen results in the formation of



Figure 17.19 The formation of urobilinoids. Aged erythrocytes are disposed in the spleen, releasing hemoglobin that is broken down to heme. The heme is converted to biliverdin and is subsequently reduced to bilirubin. The bilirubin is then released into the bloodstream where it is bound to albumin, which cannot be filtrated at the glomeruli. The bilirubin is transported through the bloodstream to the liver where it is conjugated with glucuronic acid, forming water-soluble bilirubin monoglucuronide and diglucuronide. The bilirubin glucuronides are excreted into the bile and are subsequently excreted into the small intestine. In the intestines, the glucuronic acid of the conjugated bilirubin is removed. The unconjugated bilirubin is metabolized by intestinal bacteria, forming urobilinogen. A portion of the urobilinogen is further metabolized to stercobilinogen. The urobilinogen and the stercobilinogen are oxidized by intestinal bacteria, forming urobilin and stercobilin, respectively, which are excreted into the feces. (© Richard C. Li.)


H₂C
OH HO
CH₃
H₃C
N
N
CH₂
N
HN
H₃C
CH₃
HOOC
COOH
UGT
Glucuronic acid
O
HO
HO
HO
O
O
H
C
OH
CH₃
OH HO
H₃C
N
N
CH
O
O
O
OH
OH
OH
HO
N
HN
H₃C
CH₃
HOOC
COOH
Bilirubin
Bilirubin diglucuronide

Figure 17.20 The formation of bilirubin glucuronides in the liver. UGT, UDP glucuronosyltransferases.

urobilin and stercobilin (Figure 17.21), respectively. These compounds are brown colored and are responsible for the characteristic color of feces.

The urobilinoids can be detected using the Schlesinger and Edelman tests. In the *Schlesinger* test, a sample is mixed with saturated zinc acetate in ethanol solution to form aurobilinoid–zinc chelation complex that emits a characteristic green fluorescence under ultraviolet light. The *Edelman* test is a variation of the Schlesinger test. A sample is treated with a mercuric salt solution to yield a pink-colored compound. Further treatment with a zinc salt produces fluorescence. However, less fluorescence is observed in the Edelman test than in the Schlesinger test. Inconclusive and inconsistent results are often obtained using these tests where fecal material sometimes gives no visible fluorescence. Additionally, the intensity of the fluorescence observed varies between samples. The reliability and selectivity of the tests can be increased using a spectrometric measurement of the fluorescence detection of fecal urobilinoids based on the principle of the Schlesinger test. A dry sample is treated with 1 mL of zinc acetate solution (1% zinc acetate methoxyethanol solution and 0.2% Tris). The suspension is then sonicated for 5 min, heated at 100°C for 10 min, cooled, and centrifuged. The presence of urobilinoids can be detected using excitation and emission maxima at 507 and 514 nm, respectively.

The disadvantages of the Schlesinger and the Edelman tests are their low species specificity as both tests cannot distinguish between human and other mammalian fecal materials. Moreover, under normal circumstances, up to 5% of urobilinogen is transported to the kidney and oxidized to urobilin in urine. Under some pathological conditions such as hepatic function disorders, the level of urobilin in the urine can be very high. Both the Schlesinger and Edelman tests respond to the urobilin of urine stains as well.


H₃C
O O
CH₃
CH₃
H₃C
NH
HN
H
H
N
HN
H₃C
CH₃
HOOC
COOH
Urobilin
H₃C
O O
CH₃
CH₃
H₃C
NH
HN
H
H
N
HN
H₃C
CH₃
HOOC
COOH
Stercobilin

Figure 17.21 Urobilinoids: urobilin and stercobilin. Arrow, site of reduction.



Figure 17.22 Intestinal bacteria. (© Richard C. Li.)

17.3.2.3 Fecal Bacterial Identification

The human intestinal microbiota contains more than 4000 bacterial species (Figure 17.22). Traditional methods for detecting fecal materials utilize the cultivation of fecal indicator bacteria such as *Escherichia coli* or *Enterococci* spp. However, these fecal indicator bacteria constitute only a small portion of the fecal microbiota, and thus may not be adequate for forensic identification purposes. *Bacteroides*, however, accounts for approximately 30% of fecal microbiota that are the predominant bacteria in human feces. *Bacteroides* can potentially be used for the forensic identification of feces. *Bacteroides* is a genus of rod-shaped, anaerobic gram-negative bacteria. These bacteria play a role in digesting complex carbohydrates and other substances that cannot be digested by human enzymes. The identification of *bacteroides* can be carried out by detecting specific DNA sequences of the *rpoB* gene, which encodes the β subunit of bacterial RNA polymerase (Chapter 11). The presence of the species-specific DNA sequence can be detected by RT-PCR utilizing primers that are specific to the target species but not to other species. Thus, only a targeted species can be amplified if it is present. Two fecal predominant bacteroides species, *B. uniformis* and *B. vulgatus*, can be detected in feces. *B. uniformis* is not detectable in blood, saliva, semen, urine, vaginal fluids, or on skin surfaces. Therefore, *B. uniformis* is considered as a specific indicator bacterium for forensic fecal identification. Sometimes, *B. vulgatus* can also be detected in vaginal fluid samples. Therefore, precaution should be taken in interpreting the results obtained using a *B. vulgatus* assay. Additionally, this method alone cannot discriminate between human and animal feces. Furthermore, fecal microbial populations can be affected by the host's diet. Individuals who consume saturated fats and proteins, which are abundant in Western diets, have predominantly *Bacteroides* species in their feces. However, individuals who consume a low-fat and carbohydrate-rich diet have predominantly *Prevotella* species, also a genus of gram-negative bacteria, in their feces.

17.4 Identification of Vomitus

17.4.1 Biology of Gastric Fluid

Gastric fluid can be found in stains derived from stomach wounds. Most often, gastric fluid is from vomitus found at a crime scene or as dried stains on clothing. Vomiting is the forceful expulsion of the contents of the stomach through the mouth (Figure 17.23). It is usually preceded by salivation, sweating, and the sensation of nausea. Vomiting usually begins with a deep



Figure 17.23 Act of vomiting. The contraction of the diaphragm and the stomach during the phase of vomiting is shown (in red). Additionally, the positions of the epiglottis and the uvula during vomiting are shown (in red). As a result, the stomach contents are expelled through the mouth. (© Richard C. Li.)

inhalation and the closure of the glottis. Subsequent contractions of the diaphragm and the abdominal muscles compress the stomach. The gastric contents are then forced upward through the relaxed sphincters and the esophagus, and are expelled through the mouth. Since the glottis is closed, vomitus usually does not enter the respiratory tract. Although the uvula is usually raised to close the nasal cavity, vomitus sometimes enters the nose. Vomiting can be caused by a wide variety of pathological conditions. Vomiting may be a specific response to acute intoxication in homicidal poisoning cases or it may be caused by trauma in a violent assault. Thus, the forensic identification of the gastric fluid can corroborate a criminal act.

The stomach stores ingested food until it can be emptied into the small intestines. When food enters the stomach, hydrochloric acid is secreted in large quantities, which facilitates the initial degradation of proteins. The stomach also secretes mucus that lubricates the gastric surface to protect the epithelium from acidic environments. Hormones such as gastrin, which are found in the gastric fluid, regulate acid secretion and gastric movement. A number of enzymes are secreted into the gastric fluid, including lipase, which plays a role in lipid hydrolysis, and gelatinase, which can hydrolyze gelatin. The stomach also secretes pepsinogens, which are enzyme precursors, into the gastric fluid. In the stomach, pepsinogens are activated by hydrochloric acid into pepsin, which is largely responsible for the digestion of proteins.

17.4.2 Vomitus Identification Assays

Vomitus is highly acidic and tends to be malodorous. The color of vomitus may be of forensic interest. Fresh blood in the vomit is usually bright red and suggests bleeding due to injuries, while dark red blood clots suggest bleeding in the stomach due to pathological conditions such as an ulcer. A microscopic examination (Section 17.3.2.1) can be performed to identify recently ingested food particles that are present in a sample. The presence of gastric fluid in vomitus can also be identified by the detection of pepsins secreted from the stomach. This identification test



Figure 17.24 The cleavage of polypeptide by pepsin. Pepsin cleaves polypeptide at sites of aromatic amino acids. R and R′: tryptophan, phenylalanine, or tyrosine.

is based on the proteolytic activity of pepsins. Pepsins are endopeptidases that cleave primarily on peptide bonds in the middle of the protein. Aromatic amino acids such as tryptophan, phenylalanine, and tyrosine are the preferred targeted amino acids for the cleavage reaction by pepsins (Figure 17.24). In the pepsin-proteolytic assay, fibrin blue is used as a substrate for pepsin. Fibrin blue is an insoluble protein–dye complex that is colorless. In the presence of vomitus, pepsin cleaves fibrin blue and releases a chromophore that is soluble in water and exhibits a blue color. In the assay, a fibrin blue–containing agarose gel is utilized. The sample from vomitus is loaded onto the gel plate. After incubation, a blue ring around the sample can be observed as a result of the enzymatic reactivity of pepsin. The amounts of pepsin in a sample can be quantified. The results on the gel plate can be photographed and the dried gel plate can also be preserved as evidence. This method can determine the pepsin content of fresh and aged forensic samples. Bodily fluids other than vomitus do not show positive reactions with the use of this method. However, this method cannot distinguish the vomitus of humans from that of other vertebrates.

Bibliography

Akutsu, T., K. Watanabe, and K. Sakurada, Specificity, sensitivity, and operability of RSID-urine for forensic identification of urine: Comparison with ELISA for Tamm–Horsfall protein. *J Forensic Sci*, 2012, **57**(6): 1570–1573.

Akutsu, T., et al., Evaluation of Tamm–Horsfall protein and uroplakin III for forensic identification of urine. *J Forensic Sci*, 2010, **55**(3): 742–746.

Bedrosian, J.L., M.D. Stolorow, and M.A. Tahir, Development of a radial gel diffusion technique for the identification of urea in urine stains. *J Forensic Sci*, 1984, **29**(2): 601–606.

Biles, P.V. and G.C. Ziobro, Identification of the source of reagent variability in the xanthydrol/urea method. *J Assoc Official Anal Chem Int*, 1998, **81**(6): 1155–1161.

Bock, J.H., M.A. Lane, and D.O. Norris, *Identifying Plant Food Cells in Gastric Contents for Use in Forensic Investigations: A Laboratory Manual*, 1988. Washington, DC: US Department of Justice, National Institute of Justice.

Brunzel, N.A., *Fundamentals of Urine and Body Fluid Analysis*, 2nd edn., 2004. Philadelphia, PA: W.B. Saunder.

De Araújo, W.R., M.O. Salles, and T.R.L.C. Paixão, Development of an enzymeless electroanalytical method for the indirect detection of creatinine in urine samples. *Sensor Actuat B-Chem*, 2012, **173**: 847–851.

Farrugia, K.J., et al., Chemical enhancement of footwear impressions in urine on fabric. *Forensic Sci Int*, 2012, **214**(1–3): 67–81.

Farrugia, K.J., et al., A comparison of enhancement techniques for footwear impressions on dark and patterned fabrics. *J Forensic Sci*, 2013, **58**(6): 1472–1485.

Fujishiro, M., et al., Identification of human urinary stains by the uric acid/creatinine quotient and HPLC chromatogram. *J Showa Med Assoc*, 2008, **68**(3): 175–181.

Gaensslen, R.E., Identification of urine, in *Sourcebook in Forensic Serology, Immunology, and Biochemistry*, pp. 191–195, 1983. Washington, DC: US Government Printing Office.

Greenwald, I., The chemistry of Jaffe's reaction for creatinine: VI. A compound of picric acid with two molecules of creatinine. Its combinations with acid and alkali. *J Biol Chem*, 1930, **86**: 333–343.

Iida, R., T. Yasuda, and K. Kishi, Identification of novel fibronectin fragments detected specifically in juvenile urine. *Fed Eur Biochem Soc J*, 2007, **274**(15): 3939–3947.

Johnson, D.J., L.R. Martin, and K.A. Roberts, STR-typing of human DNA from human fecal matter using the QIAGEN QIAamp® stool mini kit. *J Forensic Sci*, 2005, **50**(4): 802–808.

Jones, E., The identification of semen and other body fluids, in R. Saferstein (ed.), *Forensic Science Handbook*, pp. 329–399, 2005. Upper Saddle River, NJ: Prentice Hall.

Juusola, J. and J. Ballantyne, Multiplex mRNA profiling for the identification of body fluids. *Forensic Sci Int*, 2005, **152**(1): 1–12.

Kageyama, N., A direct colorimetric determination of uric acid in serum and urine with uricase-catalase system. *Clin Chim Acta*, 1971, **31**(2): 421–426.

Knight, B.H., The significance of the postmortem discovery of gastric contents in the air passages. *Forensic Sci*, 1975, **6**(3): 229–234.

Lai, Y., C.H. Wang, and J. Qin, A study on STR typing of human sweat latent fingerprints developed by various methods. *Chin J Forensic Med*, 2007, **22**(6): 366–368.

Lee, H.C., et al., Enzyme assays for the identification of gastric fluid. *J Forensic Sci*, 1985, **30**(1): 97–102.

Lloyd, J.B. and N.T. Weston, A spectrometric study of the fluorescence detection of fecal urobilinoids. *J Forensic Sci*, 1982, **27**(2): 352–365.

Lum, P., Seven month old substituted urine sample. *Calif Depart Justice Tie-Line*, 1991, **16**: 79–82.

Metropolitan Police Forensic Science Laboratory, *Biology Methods and Manual*, p. 5, 1978. London: Metropolitan Police Forensic Science Laboratory.

Nakanishi, H., et al., Identification of feces by detection of bacteroides genes. *Forensic Sci Int Genet*, 2013, **7**(1): 176–179.

Nakazono, T., et al., Identification of human urine stains by HPLC analysis of 17-ketosteroid conjugates. *J Forensic Sci*, 2002, **47**(3): 568–572.

Nakazono, T., et al., Dual examinations for identification of urine as being of human origin and for DNA-typing from small stains of human urine. *J Forensic Sci*, 2008, **53**(2): 359–363.

Nickolls, L.C., Urine, in *The Scientific Investigation of Crime*, pp. 209–210, 1956. London: Butterworth.

Norris, D.O. and J.H. Bock, Use of fecal material to associate a suspect with a crime scene: Report of two cases. *J Forensic Sci*, 2000, **45**(1): 184–187.

Nussbaumer, C., E. Gharehbaghi-Schnell, and I. Korschineck, Messenger RNA profiling: A novel method for body fluid identification by real-time PCR. *Forensic Sci Int*, 2006, **157**(2–3): 181–186.

O'Leary, N., A. Pembroke, and P.F. Duggan, A simplified procedure for eliminating the negative interference of bilirubin in the Jaffe reaction for creatinine. *Clin Chem*, 1992, **38**(9): 1749–1751.

Ong, S.Y., et al., Forensic identification of urine using the DMAC test: A method validation study. *Sci Justice*, 2012, **52**(2): 90–95.

Poon, H.H.L., Identification of human urine by immunological techniques. *Can Soc Forensic Sci J*, 1984, **17**: 81–89.

Reddy, K. and E.J. Lowenstein, Forensics in dermatology: Part I. *J Am Acad Dermatol*, 2011, **64**(5): 801–808.

Rhodes, E.F. and J.I. Thornton, DNAC test for urine stains. *J Police Sci Admin*, 1976, **4**: 88–89.

Roy, R., Analysis of human fecal material for autosomal and Y chromosome STRs. *J Forensic Sci*, 2003, **48**(5): 1035–1040.

Sagawa, K., et al., Production and characterization of a monoclonal antibody for sweat-specific protein and its application for sweat identification. *Int J Legal Med*, 2003, **117**(2): 90–95.

Sakurada, K., et al., Detection of dermcidin for sweat identification by real-time RT-PCR and ELISA. *Forensic Sci Int*, 2010, **194**(1–3): 80–84.

Sato, I., Detection of α S1-casein in vomit from bottle-fed babies by enzyme-linked immunosorbent assay. *Int J Legal Med*, 1992, **105**(3): 127–131.

Sato, K., et al., Identification of human urinary stains by the quotient uric acid/urea nitrogen. *Forensic Sci Int*, 1990, **45**(1–2): 27–38.

Sikirzhytski, V., A. Sikirzhytskaya, and I.K. Lednev, Multidimensional Raman spectroscopic signatures as a tool for forensic identification of body fluid traces: A review. *Appl Spectrosc*, 2011, **65**(11): 1223–1232.

Sikirzhytski, V., A. Sikirzhytskaya, and I.K. Lednev, Multidimensional Raman spectroscopic signature of sweat and its potential application to forensic body fluid identification. *Anal Chim Acta*, 2012, **718**: 78–83.

Srch, M., Examination of vomit [in Czech]. *Ceskoslovenska Patologie*, 1975, **11**(3): 46–47.

Srch, M., Examination of vomits. *Vysetrovánizvratků*, 1975, **20**(3): 46–48.

Taylor, M.C. and J.S. Hunt, Forensic identification of human urine by radioimmunoassay for Tamm–Horsfall urinary glycoprotein. *J Forensic Sci Soc*, 1983, **23**(1): 67–72.

Tsutsumi, H., et al., Identification of human urinary stains by enzyme-linked immunosorbent assay for human uromucoid. *J Forensic Sci*, 1988, **33**(1): 237–243.

Virkler, K. and I.K. Lednev, Analysis of body fluids for forensic purposes: From laboratory testing to non-destructive rapid confirmatory identification at a crime scene. *Forensic Sci Int*, 2009, **188**(1–3): 1–17.

Wawryk, J. and M. Odell, Fluorescent identification of biological and other stains on skin by the use of alternative light sources. *J Clin Forensic Med*, 2005, **12**(6): 296–301.

Yamada, S., et al., Vomit identification by a pepsin assay using a fibrin blue-agarose gel plate. *Forensic Sci Int*, 1992, **52**(2): 215–221.

Yan, P., et al., DNA-based species identification for faecal samples: An application on the mammalian survey in Mountain Huangshan scenic spot. *Afr J Biotechnol*, 2011, **10**(57): 12134–12141.

Zhang, S.H., et al., Genotyping of urinary samples stored with EDTA for forensic applications. *Genet Mol Res*, 2012, **11**(3): 3007–3012.

SECTION IV

Individualization of Biological Evidence

18

Blood Group Typing and Protein Profiling

18.1 Blood Group Typing

18.1.1 Blood Groups

For the purposes of this text, blood groups are defined as antigen polymorphisms present on erythrocyte surfaces. Human erythrocyte surface membranes contain a variety of blood group antigens. Transfusion reactions occur when an incompatible type of blood is transfused into an individual, which can lead to severe symptoms or even death. Karl Landsteiner discovered the first blood group, known as the ABO system, in the early 1900s, while studying transfusion and transplantation. The discovery made blood transfusions feasible, and Landsteiner was awarded the Nobel Prize in 1930.

The International Society of Blood Transfusion currently recognizes 29 blood group systems, which include hundreds of antigen polymorphisms (Table 18.1). From the 1950s to the 1970s, the structures and biosynthesis pathways of many blood group antigens were determined. The genes for most of these blood group systems have been identified as well. The isolation of blood group genes has made it possible to understand the molecular mechanisms of the antigenic characteristics of the blood group systems.

The ABO system of antigens in human erythrocytes is the most commonly used blood group system for forensic applications. Forensic laboratories also use others, including the Rh, MNS, Kell, Duffy, and Kidd systems.

18.1.2 ABO Blood Group System

In the ABO blood group system, two types of antigens, designated A and B, give rise to four blood types:

- Type A individuals have the A antigen.
- Type B individuals have the B antigen.
- Type AB individuals have both A and B antigens.
- Type O individuals have neither A nor B antigens.

The antigens may be found in other bodily fluids as well as blood, such as amniotic fluid, saliva, and semen as well as many organs including the kidney, pancreas, liver, and lungs.

Table 18.1 Blood Group Systems

Number	Name	Symbol	Number of Antigens	Gene Names	Chromosomal Location
001	ABO	ABO	4	*ABO*	9q34.2
002	MNS	MNS	43	*GYPA, GYPB, GYPE*	4q31.21
003	P	P1	1		22q11.2-qter
004	Rh	RH	49	*RHD, RHCE*	1p36.11
005	Lutheran	LU	20	*LU*	19q13.32
006	Kell	KEL	25	*KEL*	7q34
007	Lewis	LE	6	*FUT3*	19p13.3
008	Duffy	FY	6	*FY*	1q23.2
009	Kidd	JK	3	*SLC41A1*	18q12.3
010	Diego	DI	21	*SLC4A1*	17q21.31
011	Yt	YT	2	*ACHE*	7q22.1
012	Xg	XG	2	*XG, MIC2*	Xp22.33, Yp11.3
013	Scianna	SC	5	*ERMAP*	1p34.2
014	Dombrock	DO	5	*DO*	12p12.3
015	Colton	CO	3	*AQP1*	7p14.3
016	Landsteiner-Wiener	LW	3	*ICAM4*	19p13.2
017	Chido/Rodgers	CH/RG	9	*C4A, C4B*	6p21.3
018	H	H	1	*FUT1*	19q13.33
019	Kx	XK	1	*XK*	Xp21.1
020	Gerbich	GE	8	*GYPC*	2q14.3
021	Cromer	CROM	12	*DAF*	1q32.2
022	Knops	KN	8	*CR1*	1q32.2
023	Indian	IN	2	*CD44*	11p13
024	Ok	OK	1	*BSG*	19p13.3
025	Raph	RAPH	1	*CD151*	11p15.5
026	John Milton Hagen	JMH	1	*SEMA7A*	15q24.1
027	I	I	1	*GCNT2*	6p24.2
028	Globoside	GLOB	1	*B3GALT3*	3q26.1
029	Gill	GIL	1	*AQP3*	9p13.3

Source: Adapted from Daniels, G.L., et al., *Vox Sang*, 87, 304–316, 2004.

18.1.2.1 Biosynthesis of Antigens

All individuals generate the *O antigen*, also known as the *H antigen*. The O antigen is synthesized by *fucosyltransferase*, a fucose transferase encoded by the *FUT* genes, which adds a fucose on the end of a glycolipid (in erythrocytes) or glycoprotein (in tissues). An additional monosaccharide (Figure 18.1) is then transferred to the O antigen by a transferase encoded by the *ABO* locus. The specificity of this enzyme determines the ABO blood type (Figure 18.2):

- The *A* allele produces the A-transferase, which transfers N-acetylgalactosamine to the O antigen and thus synthesizes the A antigen.
- The *B* allele produces the B-transferase, which transfers galactose to the O antigen and thus synthesizes the B antigen.
- The *O* allele has a mutation (small deletion), which eliminates transferase activity, and no modification of the O antigen occurs.

As a result, the A and B antigens differ in their terminal sugar molecules. Subgroups of blood types A and B have been described. The most important are the A_1 and A_2 antigens. Both A_1 and A_2 (and A_1B and A_2B) cells react with anti-A antibodies. However, A_1 cells react more strongly than A_2 cells. The apparent difference between A_1 and A_2 is that each A_1 cell contains more copies of the A antigen than A_2 cells.

18.1.2.2 Molecular Basis of the ABO System

A- and B-transferases are encoded by a single gene, *ABO*, on chromosome 9. The *ABO* gene (approximately 20 kb) is organized into seven exons. Most of its coding regions are located in exons 6 and 7 of the *ABO* locus, including the domain responsible for catalytic activity (Figure 18.3). The gene products of the *A* and *B* alleles differ by four amino acid substitutions (Table 18.2). In particular, amino acid residues at positions 266 and 268 are more important in determining the enzymatic property of a transferase.

The A^1 allele and A^2 allele differ in a single nucleotide deletion upstream from the translation stop codon. The resulting reading-frame shift in the A^2 allele abolishes the stop codon, yielding a product with an extra 21–amino acid residue at the C-terminus.

Subgroups of blood types O have also been reported. The sequence of the O^1 allele has a deletion of a single nucleotide at exon 6. This nucleotide deletion leads to a reading-frame shift generating a truncated protein, which lacks the catalytic domain. While the O^{1y} allele also has a single nucleotide deletion, it differs from O^1 by nine nucleotides within the coding sequence. O^1 and O^{1y} have identical phenotypes. There is also an O^2 allele, which is inactivated by a substitution



Figure 18.1 Chemical structures of (a) *N*-acetylglucosamine, (b) galactose, (c) fucose, and (d) *N*-acetylgalactosamine.



UDP
N-AcGal
A-transferase
Fuc
N-AcGlu
Gal
N-AcGal
A antigen
Fucosyltransferase
N-AcGlu
Gal
N-AcGlu
Gal
Fuc
O antigen
B-transferase
UDP
Gal
Fuc
N-AcGlu
Gal
Gal
B antigen

Figure 18.2 Biosynthesis of ABO antigens. O-antigen biosynthesis is catalyzed by fucosyltransferase. A-antigen biosynthesis is catalyzed by the A-transferase that transfers the N-acetylgalactosamine from the donor and uridine diphosphate (UDP)-*N*-acetylgalactosamine to the O antigen. B-antigen biosynthesis is catalyzed by the B-transferase that transfers the galactose from UDP-galactose to the O antigen. N-AcGlu, *N*-acetytglucosamine; Gal, galactose; Fuc, fucose; N-AcGal, *N*-acetylgalactosamine. (© Richard C. Li.)



Exon 6
Exon 7
DNA
A^1
A^2
O^1
Protein

Figure 18.3 Structure of ABO gene and variants. Exons 6 and 7 are shown. The deletion mutation in A^2 and O^1 variants is indicated by an inverted triangle and leads to their A_2 and O phenotypes, respectively. (© Richard C. Li.)

Table 18.2 Amino Acid Substitutions at Four Positions in Human ABO Variants A^1, B, and O^2

ABO Variant	Amino Acid Position			
	176	235	266	268
A^1	Arginine	Glycine	Leucine	Glycine
B	Glycine	Serine	Methionine	Alanine
O^2	Glycine	Glycine	Leucine	Arginine

mutation at glycine (position 268) by arginine. Additionally, a few dozen other rare *O* alleles, which yield inactive proteins, have also been documented.

18.1.2.3 Secretors

In addition to erythrocytes, individuals whose A, B, and O antigens can be found in other types of bodily fluids are referred to as *secretors*. Eighty percent of Caucasians are secretors. As described earlier, the O antigen is the substrate for the A- and B-transferase because the A- and B-transferase can only utilize a fucosylated substrate. The O antigen is synthesized by fucosylation of the terminal galactosyl residue catalyzed by the fucosyltransferase, which is encoded by *FUT* genes.

Chromosome 19 contains two homologous genes: *FUT1* and *FUT2*. *FUT1* is expressed in tissues of mesodermal origin (embryonic tissues that serve as precursors of hemopoietic tissues, muscle, the skeleton, and internal organs) and is responsible for the synthesis of the O antigen in erythrocytes. *FUT2* is expressed in tissues of endodermal origin (embryonic tissues that are precursors of the gut and other internal organs); it is responsible for the synthesis of the O antigen in secretions.

About 20% of Caucasian individuals (called *nonsecretors*) are homozygous for a nonsense mutation in *FUT2* at amino acid position 143, resulting in a truncated protein. Bodily fluids such as the semen of type A or B nonsecretors (who carry homozygous *FUT2* mutations) contain no A or B antigens despite containing active A- or B-transferases (Figure 18.4). This can be a problem in investigating sexual assault cases when the blood type of the seminal evidence needs to be determined. However, nonsecretors have O antigens on erythrocytes synthesized by *FUT1* and thus have A or B antigens in blood. Individuals carrying very rare homozygous *FUT1* mutations produce erythrocyte O-deficient phenotypes in which the erythrocytes express no O antigens and thus express neither A nor B antigens, regardless of *ABO* genotype. Individuals



Figure 18.4 Tissue-specific O-antigen biosynthesis by *FUT1* and *FUT2* gene products. Tissue-specific O-antigen biosynthesis in erythrocytes is catalyzed by the *FUT1* gene product; in secretions, it is catalyzed by the *FUT2* gene product. The mutations abolishing the biosynthesis of O antigens are indicated. The *FUT2* mutation produces a nonsecretor phenotype. (© Richard C. Li.)

who carry both *FUT1* and *FUT2* mutations have no O antigens (nor A nor B antigens) in their erythrocytes and other bodily fluids and are known as Bombay (O_h) phenotypes.

18.1.2.4 Inheritance of A and B Antigens

A and *B* alleles are dominant. For *AO* and *BO* heterozygotes, the corresponding transferase synthesizes the A or B antigen. *A* and *B* alleles are codominant in *AB* heterozygotes because both transferase activities are expressed. The *OO* homozygote produces neither transferase activity and therefore lacks both antigens. The inheritance of *A* and *B* alleles obeys Mendelian principles (Chapter 25). For example, an individual with type B blood may have inherited a *B* allele from each parent or a *B* allele from one parent and an *O* allele from the other; thus, an individual whose phenotype is B may have the *BB* (homozygous) or *BO* (heterozygous) genotype. Conversely, if the blood types of the parents are known, the possible genotypes of their children can be determined. When both parents are type B (heterozygous), they may produce children with the genotype *BB* (B antigens from both parents), *BO* (B antigen from one parent, O from the other heterozygous parent), or *OO* (O antigens from parents who are both heterozygous). Thus, blood group typing can be used for paternity testing.

18.1.3 Forensic Applications of Blood Group Typing

The application and usefulness of blood typing in forensic identification are based on the ability to group individuals into four different types using the ABO blood system, allowing individuals to be identified. For example, if one crime scene blood sample is type B and a suspect has type A, the crime scene sample must have a different origin. However, if both the sample and the suspect are type A, the sample may have come from the same origin or from a different origin that happened to be type A.

Unfortunately, the probability that any two randomly chosen individuals have an identical blood type is very high. Approximately 42% of Caucasians have type A blood. The frequency of other blood types within the ABO system is shown in Figure 18.5. Multiple blood group systems were utilized to decrease the probability of a coincident match.

The A and B antigens are very stable and can be identified in dried blood even after many years. They can also be found in semen and other bodily fluids of secretors. Thus, in sexual assault cases, for example, the ABO type of a semen sample can be examined to identify a perpetrator.

18.1.4 Blood Group Typing Techniques

The most common assays used in forensic serology involve agglutination and include the Lattes crust and absorption–elution assays.

18.1.4.1 Lattes Crust Assay

In the early 1900s, Karl Landsteiner used his blood and blood obtained from his laboratory coworkers to test the effects of serum on erythrocytes. He discovered that naturally occurring



Figure 18.5 Frequency distributions of ABO types observed in American Caucasians. Different human populations may exhibit different frequencies of the four blood types. (© Richard C. Li.)

antibodies in serum caused agglutination of certain erythrocytes, and the agglutination patterns observed were designated A, B, and O. Each pattern indicated the presence or absence of a particular antigen on erythrocytes.

Shortly after birth, newborn infants develop antibodies against antigens that are not present in their own bodies. For example, type A individuals develop anti-B antibodies, type B individuals develop anti-A antibodies, type O individuals develop both types of antibodies, and type AB individuals do not develop anti-A or anti-B antibodies. When the plasma of a type A individual is mixed with type B cells, the anti-B antibodies from the type A individual cause the type B cells to agglutinate. This result forms the basis for blood group typing.

The Lattes crust assay relies on the principles of Landsteiner's experiments. It is an agglutination-based assay that utilizes the A, B, and O indicator cells to test the agglutination reaction with its corresponding naturally occurring serum antibodies in a questioned sample. The procedure for the Lattes crust assay is described in Box 18.1 and illustrated in Figure 18.6. Typical results are summarized in Table 18.3 and illustrated in Figure 18.7. Type A blood contains naturally occurring anti-B antibodies that agglutinate only with B cells. Likewise, type B blood agglutinates only with A cells, type O blood agglutinates with both A and B cells, and type AB blood does not agglutinate with any cells.

The Lattes crust assay is simple and rapid. However, one limitation is that the assay is not very sensitive and requires a large quantity of blood. Recall that successful agglutination reactions usually require intact cells. The agglutination assay of forensic samples is, therefore, difficult to carry out because blood cells lyse when they are dry. Therefore, this method is not reliable for testing old stains.

BOX 18.1 LATTES CRUST ASSAY PROCEDURE

1. Place small quantities of blood crust from a specimen on a microscopic slide and place a cover slide over the crusts. Prepare slides for A, B, and O cells separately.
2. Prepare cell suspensions with saline (0.85% NaCl in phosphate buffer, pH 7.4) for the A, B, and O cells separately.
3. Apply a few drops of the A-cell suspension and allow the cells to diffuse under the cover slip. Repeat this step for B cells and O cells.
4. Incubate the slides in a moisture chamber at room temperature for 2 h.
5. Examine results under a microscope.



Figure 18.6 Lattes crust assay. (© Richard C. Li.)

Table 18.3 Representative Results of Lattes Crust Assay

Blood Type	Serum Antibody	Agglutination Reaction Observed
A	Anti-B	B cells
B	Anti-A	A cells
O	Anti-A, anti-B	A cells, B cells
AB	None	None



Figure 18.7 Diagram of Lattes crust assay results. (a) Indicator cells added before incubation. (b) Strong agglutination: large clumps are observed after incubation. (c) Negative agglutination: a cloudy background may be observed after incubation.

18.1.4.2 Absorption–Elution Assay

The absorption–elution assay is highly sensitive and can be used for testing dried bloodstains. This method indirectly detects the presence of antigens. The antigens are immobilized in a solid phase (Figure 18.8). At low temperatures, the antigens bind to their corresponding antibodies: anti-A antibodies, anti-B antibodies, or anti-O lectins. (The anti-O lectin is isolated from plants and reacts strongly with the O antigen present in type O blood, but has some cross-reaction with the A antigen). The excess unbound antibodies are removed by washing, and the bound antibodies are then eluted at higher temperatures (recall that antigen–antibody binding can be affected by temperature; Chapter 13). The eluted antibodies can then be identified by an agglutination assay using A, B, and O indicator cells.

Typical results of an absorption–elution assay are summarized in Table 18.4. The bloodstains containing the A antigen can bind to anti-A antibodies. The eluted anti-A antibody can form agglutination with A cells. Likewise, for type B blood, the eluted anti-B antibody can form agglutination with B cells; for type AB blood, the eluted antibodies can form agglutination with both A and B cells; and with type O blood, the eluted anti-O lectins can form agglutination with O cells.

18.2 Forensic Protein Profiling

Because of the limitations of blood group systems, inherited protein polymorphic markers have been utilized to decrease the chances of matches between two unrelated individuals. The amino acid sequences of many proteins vary in the human population. An estimated 20%–30% of the proteins in humans are polymorphic. Some of the variations in amino acid sequences affect the function of proteins, but many of them exert little or no effect on protein function. Thus, individuals can be divided into groups based on the types of protein polymorphisms. A combination of the blood group systems and protein polymorphic markers can be used for



Figure 18.8 Absorption–elution assay. An antigen sample is immobilized on a solid-phase matrix. Antibodies (two different types are shown) are added. The antibody that is specific to the antigen binds. Unbound antibody is washed away. The bound antibody is then eluted. The eluted antibody is tested with indicator cells (two different types are shown). The indicator cell that is specific to the antibody eluted shows a positive agglutination reaction. (© Richard C. Li.)

Table 18.4 Representative Results of Absorption–Elution Assay

Blood Type (Stain)	Antibody Bound and Eluted	Agglutination Reaction Observed
A	Anti-A	A cells
B	Anti-B	B cells
O	Anti-O	O cells
AB	Anti-A, anti-B	A cells, B cells

criminal investigations and paternity testing. The probability that results for two unrelated persons would match is decreased to one in several hundred through use of the blood-typing and protein-profiling techniques.

18.2.1 Methods

Identification of protein polymorphisms is performed through electrophoretic separation based on the molecular weights (*Mr*) and charges of the protein variants.

18.2.1.1 Matrices Supporting Protein Electrophoresis

Electrophoresis of proteins is generally carried out in a support material, also called the matrix, to separate various macromolecules. The matrix also reduces the effects of diffusion and convection on the macromolecules. Historically, protein profiling for forensic application utilizes two types of matrices: papers such as cellulose acetate; and gels composed of starch, agar, agarose, or polyacrylamide. The first polymorphic protein marker, phosphoglucomutase, was characterized by starch-gel electrophoresis. However, agarose and polyacrylamide became more commonly used in electrophoresis due to good reproducibility and reliability (Table 18.5).

18.2.1.2 Separation by Molecular Weight

An electrophoretic method is frequently utilized to resolve various proteins based on their molecular weights. Native electrophoresis, also known as nondenaturing electrophoresis, can be used to isolate proteins for studying the functions of proteins. Biological activity of the protein can be retained for further analysis. However, some proteins are not well separated in electrophoresis in their native form. Thus, it may be necessary to denature the proteins in order for them to be resolved better during separation. This process is called *denaturing protein electrophoresis*. The following additives can be used:

18.2.1.2.1 Reducing Agents

It is common to include reducing agents such as mercaptoethanol (ME), dithiothreitol (DTT), or sodium mercaptoethane sulfonate (MESNA) to denature proteins. Reducing agents cleave the disulfide bonds of proteins. As a result, protein shape becomes unfolded and linear. These agents can be used during sample preparation and can also be added to the electrophoresis buffer.

18.2.1.2.2 Detergents

Detergents disrupt noncovalent interactions within the structures of native proteins. The procedure is generally performed with sodium dodecylsulfate (SDS), a strong anion detergent that binds to most proteins in amounts proportional to the molecular weight of the protein (approximately one molecule of SDS for two amino acids). The bound SDS contributes a large net negative charge on the protein, which masks any surface charges of the native protein. As a result, the charge-to-mass ratio of the protein becomes a constant. As with reducing agents, the various native conformations of proteins change to a more uniformly linear shape when SDS is bound.

Table 18.5 Properties of Matrices Supporting Protein Electrophoresis

Supporting Matrix	Pore Size	EEO	Reproducibility	Strength	Preparation	Toxicity
Cellulose acetate	Large	High	Poor	Good	Simple	Nontoxic
Starch	Large	High	Poor	Fragile	Simple	Nontoxic
Agar	Large	High	Poor	Fragile	Simple	Nontoxic
Agarose	Large	Low	Good	Fragile	Simple	Nontoxic
Polyacrylamide	Small	Very Low	Good	High; tolerates high electronic field	Complex	Toxic

Note: Electroendosmosis (EEO) occurs when fixed charges of the supporting matrix cause liquid flow toward the electrodes. A matrix with high EEO may affect the mobilities and separation performances of proteins during electrophoresis.

Electrophoretic mobility in the presence of SDS, therefore, becomes based on *M*r rather than both *M*r and the charge. Smaller proteins move through the pores of the gel matrix more rapidly than larger proteins. As a result, the larger the size of the protein, the smaller its electrophoretic mobility.

SDS gel electrophoresis can also be used to determine the *M*r of an unidentified protein based on its electrophoretic mobility on the gel. Standard marker proteins of known molecular weight are run on the same gel and allow the estimation of the *M*r of an unknown protein. A linear plot of log *M*r values of marker proteins versus relative migration during electrophoresis allows the molecular weight of the unknown protein to be determined from the graph.

18.2.1.3 Separation by Isoelectric Point

The *isoelectric focusing (IEF)* technique can be used to separate proteins according to their *isoelectric points (pI)*. The pI is the pH value at which the net electric charge of an amino acid is zero. All proteins are composed of amino acids, and each has its own characteristic pI at which its net electric charge is zero and does not migrate in an electric field.

In IEF electrophoresis, a pH gradient is created in a gel between the electrodes, and a protein sample is placed in a well on the gel. With an applied electric field, proteins enter the gel and migrate until they reach a pH equivalent to their pI values, at which they lose mobility (Figure 18.9). IEF, based on molecular charge, is capable of producing sharper bands than denaturing protein electrophoresis and thus has a higher resolving power. The technique can detect very low quantities of proteins in samples. A pH gradient in the gel is established by utilizing materials such as carrier ampholytes or immobilines that are dispersed in the gel. Carrier ampholytes are synthetic amphoteric compounds that contain multiple weak ionizable moieties acting as either acids or bases. To establish a pH gradient, a mixture of ampholytes with slightly different pIs is directly added to an IEF gel. The pH gradient is generated by applying an electric field on the ampholyte-containing gel. Under the electric field, the negatively charged ampholytes migrate toward the anode, and the positively charged ampholytes migrate to the cathode. As a result, a gradual pH gradient is created between the anodal end of the gel (acidic) and the cathodal side of the gel (basic). Immobilines are a series of modified acrylamide monomers that can be acidic or basic. The pH gradient of an IEF gel can also be established using a gradient-forming device that changes the proportion of the immobilines added to the gel matrix mixture as it is loaded into the gel-casting apparatus.



Figure 18.9 Isoelectric focusing. (a) A pH gradient is established by allowing low-molecular-weight organic acids and bases to distribute themselves in an electric field across a gel. A sample containing a protein mixture is loaded into a sample well. (b) During the electrophoresis, each protein migrates until it matches its pI. Proteins with different pIs are separated. (© Richard C. Li.)

18.2.2 Erythrocyte Protein Polymorphisms

18.2.2.1 Erythrocyte Isoenzymes

The human erythrocyte contains a number of *isoenzymes*, which are multiple forms of an enzyme that catalyze the same reaction but differ in their amino acid sequences. Individuals can be divided into groups on the basis of the different isoenzymes present in their erythrocytes. The isoenzyme type is also inherited according to Mendelian principles.

The polymorphism of erythrocyte phosphoglucomutase (PGM) was first described in the 1960s and was later successfully applied to the testing of bloodstains. PGM, an important metabolic enzyme, catalyzes the reversible conversion of glucose-1-phosphate and glucose-6-phosphate. The PGM found in erythrocytes is encoded at the *PGM1* locus at chromosome 1. The PGM encoded by *PGM1* can also be found in semen and thus can be utilized for the testing of semen samples in sexual assault cases. The protein polymorphisms of the PGM have two alleles, which result in three different phenotypes, depending on the combination of the two alleles. The success in the forensic application of PGM led to the similar use of many other erythrocyte isoenzyme polymorphisms. The most commonly used erythrocyte isoenzyme systems are listed in Table 18.6.

18.2.2.2 Hemoglobin

Recall that the use of hemoglobin (Hb) in screening and confirmatory blood tests was discussed in Chapter 12. Adult human Hb consists of two α chains and two β chains. Each polypeptide chain contains a heme group involved in oxygen binding. A very small portion of blood possesses a form of the human adult Hb consisting of two α chains and two δ chains.

More than 200 Hb variants have been identified and can be useful as markers for forensic applications. In particular, two types of human Hb variants are important in forensic testing: fetal Hb and sickle-cell Hb (Hb S). Hb S is the factor responsible for sickle-cell disease (Figure 18.10). Hb variants can be resolved using electrophoresis (Figure 18.11).

18.2.2.2.1 Fetal Hemoglobin

Humans have three forms of Hb during their development: embryonic, fetal, and adult Hb. In adults, the Hb tetramer consists of two identical α and two identical β chains. Embryonic erythrocytes contain Hb tetramers that are different from the adult form. Each embryonic Hb consists of two identical α-like chains and two identical β-like chains. The embryonic Hb is gradually replaced during pregnancy (approximately 3 months after conception) by fetal Hb, which comprises approximately 70% of the Hb in fetal blood. The fetal Hb has two identical α chains and two identical γ chains.

TABLE 18.6 Common Isoenzymes Used for Forensic Protein Profiling

Erythrocyte Isoenzyme	Protein Symbol	Number of Alleles
Phosphoglucomutase	PGM	2[a]
Erythrocyte acid phosphatase	ACP/EAP	3
Esterase D	ESD	2
Adenylate kinase	AK	2
Glyoxalase I	GLO	2
Adenosine deaminase	ADA	2

[a] Ten alleles can be observed using IEF electrophoresis.



Figure 18.10 Normal and sickle-cell hemoglobin β chains. (a) Normal hemoglobin β chain contains a glutamic acid residue (Glu) at position 6 of the N-terminal of the protein. (b) At position 6 of the sickle-cell hemoglobin β chain, the glutamic acid residue is replaced by a valine (Val). (© Richard C. Li.)



Figure 18.11 Hemoglobins resolved by isoelectric focusing electrophoresis. (© Richard C. Li.)

The embryonic and fetal Hbs have higher affinities to oxygen, required to provide the embryo and fetus with sufficient amounts of oxygen taken from maternal blood. Fetal Hb is replaced by adult Hb approximately 6 months after birth. These Hbs are encoded by their corresponding genes located at the globin gene clusters. The detection of fetal Hb in a bloodstain via electrophoresis can provide important evidence in cases of infanticide and concealed birth.

18.2.2.2.2 Hemoglobin S

Hb S polymorphism has forensic importance in identifying individuals. The Hb S polymorphism is observed in high frequencies among those of African heritage and some Hispanic populations. Such a protein polymorphic marker can provide investigational leads for the indication of the ethnic origin of a perpetrator. Hb S transports oxygen much less efficiently than normal Hb. Individuals who are homozygous for Hb S usually die early after suffering from sickle-cell anemia and related complications. However, a heterozygous individual (an individual with a copy of the wild-type Hb allele from one parent and a copy of the Hb S allele from the other) can survive. This condition is known as the sickle-cell trait.

In the 1950s, Vernon Ingram of Cambridge University discovered the molecular mechanism of the Hb S defect. His work revealed that the Hb S bears a mutation, which changes the glutamic acid in wild type to a valine at the sixth amino acid from the N-terminal end of the β chain. This substitution of amino acids causes a major change in the structure of the β chain, which in turn results in sickle-cell anemia.

18.2.3 Serum Protein Polymorphisms

The serum portion of blood consists of a large number of proteins. The work on serum proteins for forensic purposes started in the 1950s, when variations in serum proteins were found useful for distinguishing individuals. Over the years, a number of serum proteins were characterized and applied for forensic testing. Haptoglobin (Hp) was the most widely used of the polymorphic serum proteins in forensic biology (Figure 18.12). Haptoglobin is a protein that binds and transports Hb from the bloodstream to the liver for the recycling of the iron contained in the Hb.

Immunoglobulin (Chapter 10) accounts for approximately 15% of serum protein and has been found to be highly variable. Two immunoglobulin proteins are utilized for forensic application. The γ chain protein (G_m) is the heavy chain of immunoglobulin G and the κ chain protein (K_m) is one of two types of the light chain of all immunoglobulins. Table 18.7 lists common serum group systems. All exhibit genetic variations and can be detected in bloodstains. The variants of these proteins can be determined by electrophoresis or serological methods.



Figure 18.12 Polyacrylamide gel electrophoresis of haptoglobin proteins. From left to right: Hp2, Hp2-1, Hp2, Hp1, Hp2, Hp2-1, Hp1, Hp2, Hp2-1. An anode is at the bottom. (From James, S. and Nordby, J.J., *Forensic Science: An Introduction to Scientific and Investigative Techniques*, CRC Press, Boca Raton, FL, 2005. With permission.)

TABLE 18.7 Serum Proteins Used for Forensic Protein Profiling

Serum Protein	Protein Symbol	Gene Symbol	Chromosomal Location	Number of Amino Acids	Number of Alleles
Haptoglobin	Hp	*HP*	16q22.1	328/387	2
Group-specific component	Gc	*GC*	4q12–13	458	2
Transferrin	Tf	*TF*	3q22.1	679	3
Protease inhibitor (α1-antitrypsin)	Pi	*PI*	14q32.1	394	Many

Source: Adapted from Yuasa, I. and Umetsu, K., *Leg Med*, 7, 251–254, 2005.

Bibliography

Blood Groups

Achermann, F.J., et al., Soluble type A substance in fresh-frozen plasma as a function of ABO and secretor genotypes and Lewis phenotype. *Transfus Apher Sci*, 2005, **32**(3): 255–262.

Aki, K., A. Izumi, and E. Hosoi, The evaluation of histo-blood group ABO typing by flow cytometric and PCR-amplification of specific alleles analyses and their application in clinical laboratories. *J Med Invest*, 2012, **59**(1–2): 143–151.

Allen, F.H. Jr. and R.E. Rosenfield, Review of Rh serology. Eight new antigens in nine years. *Haematologia* (Budap), 1972, **6**(1): 113–120.

Anstee, D.J. and M.J. Tanner, Separation of ABH, I, Ss antigenic activity from the MN-active sialoglycoprotein of the human erythrocyte membrane. *Vox Sang*, 1975, **29**(5): 378–389.

Asari, M., et al., A new method for human ABO genotyping using a universal reporter primer system. *J Forensic Sci*, 2010, **55**(6): 1576–1581.

Bargagna, M. and M. Pereira, A study of absorption–elution as a method of identification of Rhesus antigens in dried bloodstains. *J Forensic Sci Soc*, 1967, **7**(3): 123–130.

Bargagna, M., M. Sabelli, and C. Giacomelli, The detection of Rh antigens (D,C,c,E,e) on bloodstains by a micro-elution technique using low ionic strength solution (LISS) and papain-treated red cells. *Forensic Sci Int*, 1982, **19**(2): 197–203.

Bassler, G., Determination of the Lewis blood group substances in stains of forensically relevant body fluids. *Forensic Sci Int*, 1986, **30**(1): 29–35.

Boorman, K.E., B.E. Dodd, and P.J. Lincoln, *Blood Group Serology*, 5th edn., vol. 4, p. 495, 1977. London: Churchill Livingstone.

Brauner, P., DNA typing and blood transfusion. *J Forensic Sci*, 1996, **41**(5): 895–897.

Brewer, C.A., P.L. Cropp, and L.E. Sharman, A low ionic strength, hemagglutinating, autoanalyzer for rhesus typing of dried bloodstains. *J Forensic Sci*, 1976, **21**(4): 811–815.

Busuttil, A., et al., Assessment of Lewis blood group antigens and secretor status in autopsy specimens. *Forensic Sci Int*, 1993, **61**(2–3): 133–140.

Camp, F.R. Jr., Forensic serology in the United States. I. Blood grouping and blood transfusion—Historical aspects. *Am J Forensic Med Pathol*, 1980, **1**(1): 47–55.

Cartron, J.P., et al., "Weak A" phenotypes. Relationship between red cell agglutinability and antigen site density. *Immunology*, 1974, **27**(4): 723–727.

Cayzer, I. and P.H. Whitehead, The use of sensitized latex in the identification of human bloodstains. *J Forensic Sci Soc*, 1973, **13**(3): 179–181.

Chatterji, P.K., A simplified mixed agglutination technique for ABO grouping of dried bloodstains using cellulose acetate sheets. *J Forensic Sci Soc*, 1978, **17**(2–3): 143–144.

Chester, M.A. and M.L. Olsson, The ABO blood group gene: A locus of considerable genetic diversity. *Transfus Med Rev*, 2001, **15**(3): 177–200.

Daniels, G., *Human Blood Groups*, 2nd edn., p. 576, 2002. Oxford: Blackwell Science.

Daniels, G.L., et al., Blood group terminology 2004: From the International Society of Blood Transfusion committee on terminology for red cell surface antigens. *Vox Sang*, 2004, **87**(4): 304–316.

DeForest, P., R. Gaensslen, and H.C. Lee, Blood, in *Forensic Science*: *An Introduction to Criminalistics*, pp. 230–263, 1983. New York: McGraw-Hill.

De Soyza, K. and D.G. Garland, Studies and observations on Lewis grouping of body fluids and stains. *Forensic Sci Int*, 1988, **38**(1–2): 129–137.

Denomme, G.A., The structure and function of the molecules that carry human red blood cell and platelet antigens. *Transfus Med Rev*, 2004, **18**(3): 203–231.

Erskine, A.G., *The Principles and Practices of Blood Grouping*, 1973. St. Louis, MO: Mosby.

Fayrouz, I.N., N. Farida, and A.H. Irshad, Relation between fingerprints and different blood groups. *J Forensic Leg Med*, 2012, **19**(1): 18–21.

Ferri, G. and S. Pelotti, Multiplex ABO genotyping by minisequencing. *Methods Mol Biol*, 2009, **496**: 51–58.

Fiori, A. and P. Benciolini, The ABO grouping of stains from body fluids. *Z Rechtsmed*, 1972, **70**(4): 214–222.

Fiori, A., M. Marigo, and P. Benciolini, Modified absorption–elution method Siracusa for ABO and MN grouping of blood-stains. *J Forensic Sci*, 1963, **8**(3): 419–445 contd.

Gaensslen, R.E., et al., Evaluation of antisera for bloodstain grouping. II. Ss, Kell, Duffy, Kidd, and G_m/K_m. *J Forensic Sci*, 1985, **30**(3): 655–676.

Gardas, A. and J. Koscielak, Megaloglycolipids—Unusually complex glycosphingolipids of human erythrocyte membrane with A, B, H and I blood group specificity. *Fed Eur Biochem Soc Lett*, 1974, **42**(1): 101–104.

Grunbaum, B.W., Some new approaches to the individualization of fresh and dried bloodstains. *J Forensic Sci*, 1976, **21**(3): 488–509.

Haak, W., J. Burger, and K.W. Alt, ABO genotyping by PCR-RFLP and cloning and sequencing. *Anthropol Anz*, 2004, **62**(4): 397–410.

Hakomori, S. and A. Kabata, Blood group antigens, in *The Antigens*, 1974. New York: Academic Press.

Hamaguchi, H. and H. Cleve, Solubilization of human erythrocyte membrane glycoproteins and separation of the MN glycoprotein from a glycoprotein with I, S, and A activity. *Biochim Biophys Acta*, 1972, **278**(2): 271–280.

Harrington, J.J., R. Martin, and L. Kobilinsky, Detection of hemagglutinins in dried saliva stains and their potential use in blood typing. *J Forensic Sci*, 1988, **33**(3): 628–637.

Harrington, J.J., et al., Chemically sensitized erythrocytes for hemagglutination reactions. *J Forensic Sci*, 1990, **35**(5): 1115–1124.

Henry, S., et al., Molecular basis for erythrocyte Le(a+ b+) and salivary ABH partial-secretor phenotypes: Expression of a *FUT2* secretor allele with an A→T mutation at nucleotide 385 correlates with reduced alpha (1,2) fucosyltransferase activity. *Glycoconj J*, 1996, **13**(6): 985–993.

Hughes-Jones, N.C. and B. Gardner, The Kell system studied with radioactively-labelled anti-K. *Vox Sang*, 1971, **21**(2): 154–158.

Hughes-Jones, N.C., B. Gardner, and P.J. Lincoln, Observations of the number of available c,D, and E antigen sites on red cells. *Vox Sang*, 1971, **21**(3): 210–216.

Huh, J.Y., et al., A rapid long PCR-direct sequencing analysis for ABO genotyping. *Ann Clin Lab Sci*, 2011, **41**(4): 340–345.

Jaff, M.S., Higher frequency of secretor phenotype in O blood group—Its benefits in prevention and/or treatment of some diseases. *Int J Nanomed*, 2010, **5**: 901–905.

Jiang, X., et al., An integrated system of ABO typing and multiplex STR testing for forensic DNA analysis. *Forensic Sci Int Genet*, 2012, **6**(6): 785–797.

Kabat, E.A., *The Blood Group Substances*, p. 330, 1956. New York: Academic Press.

Kaneko, M., et al., Molecular characterization of a human monoclonal antibody to B antigen in ABO blood type. *Immunol Lett*, 2003, **86**(1): 45–51.

Karpoor, C., et al., Study of secretors and non-secretors in normal healthy population—Its forensic implication in human identification. *Indian J Forensic Med Tox*, 2010, **4**(1): 11–13.

Kelly, R.J., et al., Molecular basis for H blood group deficiency in Bombay (Oh) and para-Bombay individuals. *Proc Natl Acad Sci U S A*, 1994, **91**(13): 5843–5847.

Kelly, R.J., et al., Sequence and expression of a candidate for the human secretor blood group alpha (1,2) fucosyltransferase gene (*FUT2*). Homozygosity for an enzyme-inactivating nonsense mutation commonly correlates with the non-secretor phenotype. *J Biol Chem*, 1995, **270**(9): 4640–4649.

Kimura, H. and S. Matsuzawa, Lewis blood group determination in bloodstains by planimetric measurement of eluted monoclonal antibodies. *J Forensic Sci*, 1991, **36**(4): 999–1009.

Kimura, A., et al., ABO blood grouping of semen from mixed body fluids with monoclonal antibody to tissue-specific epitopes on seminal ABO blood group substance. *Int J Legal Med*, 1991, **104**(5): 255–258.

Kimura, A., et al., Blood group A glycosphingolipid accumulation in the hair of patients with alpha-*N*-acetylgalactosaminidase deficiency. *Life Sci*, 2005, **76**(16): 1817–1824.

Kind, S.S., Absorption–elution grouping of dried blood smears. *Nature*, 1960, **185**: 397–398.

Kind, S.S., Absorption–elution grouping of dried blood-stains on fabrics. *Nature*, 1960, **187**: 789–790.

Kind, S.S. and R.M. Cleevely, The fluorescent antibody technique. Its application to the detection of blood group antigens in stains. *J Forensic Med*, 1970, **17**(3): 121–129.

Kobilinsky, L. and J.J. Harrington, Detection and use of salivary hemagglutinins for forensic blood grouping. *J Forensic Sci*, 1988, **33**(2): 396–403.

Koda, Y., M. Soejima, and H. Kimura, The polymorphisms of fucosyltransferases. *Leg Med (Tokyo)*, 2001, **3**(1): 2–14.

Koda, Y., et al., Missense mutation of *FUT1* and deletion of *FUT2* are responsible for Indian Bombay phenotype of ABO blood group system. *Biochem Biophys Res Commun*, 1997, **238**(1): 21–25.

Korchagina, E.Y., et al., Design of the blood group AB glycotope. *Glycoconj J*, 2005, **22**(3): 127–133.

Ladd, C., et al., A PCR-based strategy for ABO genotype determination. *J Forensic Sci*, 1996, **41**(1): 134–137.

Lappas, N.T. and M.E. Fredenburg, The identification of human bloodstains by means of a micro-thin-layer immunoassay procedure. *J Forensic Sci*, 1981, **26**(3): 564–569.

Lattes, L., *The Individuality of Blood*, p. 413, 1932. London: Oxford University Press.

Lee, H.C., Identification and grouping of bloodstains, in R. Saferstein (ed.), *Forensic Science Handbook*, 1982. Englewood Cliffs, NJ: Prentice Hall.

Lee, H.C., et al., Genetic markers in human bone: II. Studies on ABO (and IGH) grouping. *J Forensic Sci*, 1991, **36**(3): 639–655.

Lee, H.Y., et al., Rapid direct PCR for ABO blood typing. *J Forensic Sci*, 2011, **56**(Suppl 1): S179–S182.

Lee, J.C., et al., ABO genotyping by mutagenically separated polymerase chain reaction. *Forensic Sci Int*, 1996, **82**(3): 227–232.

Lee, J.C., et al., ABO genotyping by single strand conformation polymorphism—Using CE. *Electrophoresis*, 2009, **30**(14): 2544–2548.

Lee, J.C., et al., ABO genotyping by capillary electrophoresis. *Methods Mol Biol*, 2013, **919**: 113–120.

Lee, S.H., et al., Rapid ABO genotyping using whole blood without DNA purification. *Korean J Lab Med*, 2009, **29**(3): 231–237.

Lincoln, P.J. and B.E. Dodd, The application of a micro-elution technique using anti-human globulin for the detection of the S, s, K, Fya, Fyb and Jka antigens in stains. *Med Sci Law*, 1975, **15**(2): 94–101.

Liu, Y.H., et al., Distribution of H type 1 and of H type 2 antigens of ABO blood group in different cells of human submandibular gland. *J Histochem Cytochem*, 1998, **46**(1): 69–76.

Maeda, K., et al., ABO genotyping by TaqMan assay and allele frequencies in a Japanese population. *Leg Med (Tokyo)*, 2013, **15**(2): 57–60.

Martin, P.D., A manual method for the detection of Rh antigens in dried bloodstains. *J Forensic Sci Soc*, 1978, **17**(2–3): 139–142.

McDowall, M.J., P.J. Lincoln, and B.E. Dodd, Increased sensitivity of tests for the detection of blood group antigens in stains using a low ionic strength medium. *Med Sci Law*, 1978, **18**(1): 16–23.

McDowall, M.J., P.J. Lincoln, and B.E. Dodd, Observations on the use of an autoanalyser and a manual technique for the detection of the red cell antigens C, D, E, c, K and S in bloodstains. *Forensic Sci*, 1978, **11**(2): 155–164.

Miller, C.H., et al., Measurement of von Willebrand factor activity: Relative effects of ABO blood type and race. *J Thromb Haemost*, 2003, **1**(10): 2191–2197.

Mollicone, R., A. Cailleau, and R. Oriol, Molecular genetics of H, Se, Lewis and other fucosyltransferase genes. *Transfus Clin Biol*, 1995, **2**(4): 235–242.

Moureau, P., Determination of blood groups in bloodstains, in F. Lundquist (ed.), *Methods of Forensic Science*, p. 137, 1963. New York: Interscience.

Muro, T., et al., Determination of ABO genotypes by real-time PCR using allele-specific primers. *Leg Med (Tokyo)*, 2012, **14**(1): 47–50.

Nakanishi, H., et al., Preparation of latex reagents combined with IgM and its F(ab′)2 fragment from commercial ABO blood grouping reagent. *Colloid Surf B Biointerf*, 2007, **54**(1): 114–117.

Nickolls, L.C. and M. Pereira, A study of modern method of grouping dried bloodstains. *Med Sci Law*, 1962, **2**: 172.

Ohmori, T., et al., Monoclonal antibodies against blood group A secretors and nonsecretors saliva. *Hybrid Hybridomics*, 2003, **22**(3): 183–186.

Okiura, T., et al., A-elute alleles of the ABO blood group system in Japanese. *Leg Med (Tokyo)*, 2003, **5**(Suppl 1): S207–S209.

Oriol, R., ABO, Hh, Lewis, and secretion: Serology, genetics, and tissue distribution, in J.-P. Cartron and P. Rouger (eds), *Blood Cell Chemistry*, pp. 36–73, 1995. New York: Plenum Press.

Oriol, R., J.J. Candelier, and R. Mollicone, Molecular genetics of H. *Vox Sang*, 2000, **78**(Suppl 2): 105–108.

Outteridge, R.A., Absorption–elution grouping of bloodstains: Modification and development. *Nature*, 1962, **194**: 385.

Outteridge, R.A., Absorption–elution method of grouping blood-stains. *Nature*, 1962, **195**: 818–819.

Outteridge, R.A., Recent advances in the grouping of dried blood and secretion stains. A.S. Curry (ed.), *Methods of Forensic Science*,, 1965. New York: Interscience.

Painter, T.J., W.M. Watkins, and W.T. Morgan, Serologically active fucose-containing oligosaccharides isolated from human blood-group A and B substances. *Nature*, 1965, **206**(984): 594–597.

Prokop, O. and G. Uhlenbruck, *Human Blood and Serum Groups*, 2nd edn., p. 891, 1969. New York: Wiley Interscience.

Reid, M.E. and C. Lomas-Francis, *The Blood Group Antigen Facts Book*, 2nd edn., 2004. London: Academic Press.

Reid, M.E. and N. Mohandas, Red blood cell blood group antigens: Structure and function. *Semin Hematol*, 2004, **41**(2): 93–117.

Rosenfield, R.E., F.H. Allen Jr., and P. Rubinstein, Genetic model for the Rh blood-group system. *Proc Natl Acad Sci U S A*, 1973, **70**(5): 1303–1307.

Ruan, L., H. Zhao, and Q. Li, Multicolor real-time PCR genotyping of ABO system using displacing probes. *J Forensic Sci*, 2010, **55**(1): 19–24.

Sasaki, M. and H. Shiono, ABO genotyping of suspects from sperm DNA isolated from postcoital samples in sex crimes. *J Forensic Sci*, 1996, **41**(2): 275–278.

Schleyer, F., Investigation of biological stains with regard to species origin, in F. Lundquist (ed.), *Methods of Forensic Science*, p. 291, 1962. New York: Interscience.

Shaler, R.C., A.M. Hagins, and C.E. Mortimer, MN determination in bloodstains–selective destruction of cross-reacting activity. *J Forensic Sci*, 1978, **23**(3): 570–576.

Shintani-Ishida, K., et al., A new method for ABO genotyping to avoid discrepancy between genetic and serological determinations. *Int J Legal Med*, 2008, **122**(1): 7–9.

Smeets, B., H. van de Voorde, and P. Hooft, ABO bloodgrouping on tooth material. *Forensic Sci Int*, 1991, **50**(2): 277–284.

Snyder, L.H., *Blood Groups*, p. 35, 1973. Minneapolis: Burgess.

Springer, G.F. and P.R. Desai, Human blood-group MN and precursor specificities: Structural and biological aspects. *Carbohydr Res*, 1975, **40**(1): 183–192.

Storry, J.R. and M.L. Olsson, Genetic basis of blood group diversity. *Br J Haematol*, 2004, **126**(6): 759–771.

Styles, W.M., B.E. Dodd, and R.R. Coombs, Identification of human bloodstains by means of the mixed antiglobulin reaction on separate cloth fibrils. *Med Sci Law*, 1963, **20**: 257–267.

Tsuji, A., et al., A familial case of ABO phenotype-genotype discrepancy. *Fukuoka Igaku Zasshi*, 2013, **104**(2): 40–45.

Watanabe, K., et al., A novel method for ABO genotyping using a DNA chip. *J Forensic Sci*, 2011, **56**(Suppl 1): S183–S187.

Watkins, W.M., Blood-group substances. *Science*, 1966, **152**(3719): 172–181.

Watkins, W.M., Commemoration of the centenary of the discovery of the ABO blood group system. *Transfu Med*, 2001, **11**: 239–351.

Wynbrandt, F. and W.J. Chisum, Determination of the ABO blood group in hair. *J Forensic Sci Soc*, 1971, **11**(3): 201–204.

Xingzhi, X., et al., ABO blood grouping on dental tissue. *J Forensic Sci*, 1993, **38**(4): 956–960.

Yamada, M., et al., Determination of ABO genotypes with DNA extracted from formalin-fixed, paraffin-embedded tissues. *Int J Legal Med*, 1994, **106**(6): 285–287.

Yamamoto, F., et al., Molecular genetic basis of the histo-blood group ABO system. *Nature*, 1990, **345**(6272): 229–233.

Yu, Q., et al., Congenital tetragametic blood chimerism explains a case of questionable paternity. *J Forensic Sci*, 2011, **56**(5): 1346–1348.

Protein Profiling

Allen, R.C., R.A. Harley, and R.C. Talamo, A new method for determination of alpha-1-antitrypsin phenotypes using isoelectric focusing on polyacrylamide gel slabs. *Am J Clin Pathol*, 1974, **62**(6): 732–739.

Bark, J.E., M.J. Harris, and M. Firth, Typing of the common phosphoglucomutase variants using isoelectric focusing—A new interpretation of the phosphoglucomutase system. *J Forensic Sci Soc*, 1976, **16**(2): 115–120.

Blake, N.M. and K. Omoto, Phosphoglucomutase types in the Asian-Pacific area: A critical review including new phenotypes. *Ann Hum Genet*, 1975, **38**(3): 251–273.

Budowle, B., A method for subtyping group-specific component in bloodstains. *Forensic Sci Int*, 1987, **33**(3): 187–196.

Budowle, B., A method to increase the volume of sample applied to isoelectric focusing gels. *Forensic Sci Int*, 1984, **24**(4): 273–277.

Budowle, B. and E. Scott, Transferrin subtyping of human bloodstains. *Forensic Sci Int*, 1985, **28**(3–4): 269–275.

Budowle, B. and P. Eberhardt, Ultrathin-layer polyacrylamide gel isoelectric focusing for the identification of hemoglobin variants. *Hemoglobin*, 1986, **10**(2): 161–172.

Budowle, B., S. Sundaram, and R.E. Wenk, Population data on the forensic genetic markers: Phosphoglucomutase-1, esterase D, erythrocyte acid phosphatase and glyoxylase I. *Forensic Sci Int*, 1985, **28**(2): 77–81.

Burdett, P.E. and P.H. Whitehead, The separation of the phenotypes of phosphoglucomutase, erythrocyte acid phosphatase, and some haemoglobin variants by isoelectric focusing. *Anal Biochem*, 1977, **77**(2): 419–428.

Burdett, P.E., Isoelectric focusing in agarose: Phosphoglucomutase (*PGM* locus 1) typing. *J Forensic Sci*, 1981, **26**(2): 405–409.

Carracedo, A. and L. Concheiro, The typing of alpha-1-antitrypsin in human bloodstains by isoelectric focusing. *Forensic Sci Int*, 1982, **19**(2): 181–184.

Carracedo, A., et al., A silver staining method for the detection of polymorphic proteins in minute bloodstains after isoelectric focusing. *Forensic Sci Int*, 1983, **23**(2–3): 241–248.

Constans, J. and M. Viau, Group-specific component: Evidence for two subtypes of the Gc1 gene. *Science*, 1977, **198**(4321): 1070–1071.

Constans, J., et al., Analysis of the Gc polymorphism in human populations by isoelectrofocusing on polyacrylamide gels. Demonstration of subtypes of the Gc allele and of additional Gc variants. *Hum Genet*, 1978, **41**(1): 53–60.

Cox, D.W., S. Smyth, and G. Billingsley, Three new rare variants of alpha-1-antitrypsin. *Hum Genet*, 1982, **61**(2): 123–126.

Divall, G.B., Studies on the use of isoelectric focusing as a method of phenotyping erythrocyte acid phosphatase. *Forensic Sci Int*, 1981, **18**(1): 67–78.

Divall, G.B., The esterase D polymorphism as revealed by isoelectric focusing in ultra-thin polyacrylamide gels. *Forensic Sci Int*, 1984, **26**(4): 255–267.

Divall, G.B. and M. Ismail, Studies and observations on the use of isoelectric focusing in ultra-thin polyacrylamide gels as a method of typing human red cell phosphoglucomutase. *Forensic Sci Int*, 1983, **22**(2–3): 253–263.

Dorrill, M. and P.H. Whitehead, The species identification of very old human blood-stains. *Forensic Sci Int*, 1979, **13**(2): 111–116.

Dykes, D.D. and H.F. Polesky, Review of isoelectric focusing for Gc, PGM1, Tf, and Pi subtypes: Population distributions. *Crit Rev Clin Lab Sci*, 1984, **20**(2): 115–151.

Frants, R.R. and A.W. Eriksson, Alpha-1-antitrypsin: Common subtypes of Pi M. *Hum Hered*, 1976, **26**(6): 435–440.

Gorg, A., W. Postel, and R. Westermeier, Ultrathin-layer isoelectric focusing in polyacrylamide gels on cellophane. *Anal Biochem*, 1978, **89**(1): 60–70.

Grunbaum, B.W. and P.L. Zajac, Rapid phenotyping of the group specific component by immunofixation on cellulose acetate. *J Forensic Sci*, 1977, **22**(3): 586–589.

Grunbaum, B.W. and P.L. Zajac, Phenotyping of erythrocyte acid phosphatase in fresh blood and in bloodstains on cellulose acetate. *J Forensic Sci*, 1978, **23**(1): 84–88.

Hoste, B., Group-specific component (Gc) and transferrin (Tf) subtypes ascertained by isoelectric focusing. A simple nonimmunological staining procedure for Gc. *Hum Genet*, 1979, **50**(1): 75–79.

Itoh, Y. and S. Matsuzawa, Detection of human hemoglobin A (HbA) and human hemoglobin F (HbF) in biological stains by microtiter latex agglutination-inhibition test. *Forensic Sci Int*, 1990, **47**(1): 79–89.

James, S. and Nordby, J.J., *Forensic Science: An Introduction to Scientific and Investigative Techniques*, 2005. Boca Raton, FL: CRC Press.

Jones, D.A., Blood samples: Probability of discrimination. *J Forensic Sci Soc*, 1972, **12**(2): 355–359.

Khalap, S. and G.B. Divall, Gm(5) grouping of dried bloodstains. *Med Sci Law*, 1979, **19**(2): 86–88.

Kido, A., et al., A stability study on Gc subtyping in bloodstains: Comparison by two different techniques. *Forensic Sci Int*, 1984, **26**(1): 39–43.

Kimura, H., et al., The typing of group-specific component (Gc protein) in human blood stains. *Forensic Sci Int*, 1983, **22**(1): 49–55.

Kipps, A.E., G_m and K_m typing in forensic science—A methods monograph. *J Forensic Sci Soc*, 1979, **19**(1): 27–47.

Kipps, A.E., V.E. Quarmby, and P.H. Whitehead, The detection of mixtures of blood and other body secretions in stains. *J Forensic Sci Soc*, 1978, **18**(3–4): 189–191.

Kueppers, F. and B. Harpel, Group-specific component (Gc) "subtypes" of Gc1 by isoelectric focusing in US blacks and whites. *Hum Hered*, 1979, **29**(4): 242–249.

Kuhnl, P. and W. Spielmann, A third common allele in the transferrin system, TfC3, detected by isoelectric focusing. *Hum Genet*, 1979, **50**(2): 193–198.

Kuhnl, P. and W. Spielmann, Transferrin: Evidence for two common subtypes of the TfC allele. *Hum Genet*, 1978, **43**(1): 91–95.

Kuhnl, P., U. Schmidtmann, and W. Spielmann, Evidence for two additional common alleles at the *PGM1* locus (phosphoglucomutase—E.C.: 2.7.5.1). A comparison by three different techniques. *Hum Genet*, 1977, **35**(2): 219–223.

Lamm, L.U., Family studies of red cell acid phosphatase types. Report of a family with the D variant. *Hum Hered*, 1970, **20**(3): 329–335.

Lincoln, P.J. and B.E. Dodd, An evaluation of factors affecting the elution of antibodies from bloodstains. *J Forensic Sci Soc*, 1973, **13**(1): 37–45.

Markert, C.L., The molecular basis for isozymes. *Ann N Y Acad Sci*, 1968, **151**(1): 14–40.

Miscicka, D., T. Dobosz, and S. Raszeja, Determination of phenotypes of phosphoglucomutase (PGM1) in bloodstains by cellulose acetate electrophoresis. *Z Rechtsmed*, 1977, **79**(4): 297–300.

Murch, R.S. and B. Budowle, Applications of isoelectric focusing in forensic serology. *J Forensic Sci*, 1986, **31**(3): 869–880.

Neilson, D.M., et al., Simultaneous electrophoresis of peptidase A, phosphoglucomutase, and adenylate kinase. *J Forensic Sci*, 1976, **21**(3): 510–513.

Olaisen, B., et al., The ESD polymorphism: Further studies of the *ESD2* and *ESD5* allele products. *Hum Genet*, 1981, **57**(4): 351–353.

Randall, T., W.A. Harland, and J.W. Thorpe, A method of phenotyping erythrocyte acid phosphatase by isoelectric focusing. *Med Sci Law*, 1980, **20**(1): 43–47.

Rees, B., T.J. Rothwell, and J. Bonnar, Correlation of phosphoglucomutase isoenzymes in blood and semen. *Lancet*, 1974, **1**(7861): 783.

Sensabaugh, G.F., Biochemical markers for individuality, in R. Saferstein (ed.), *Forensic Science Handbook*, 1982. Englewood Cliffs, NJ: Prentice Hall.

Shaler, R.C., Interpretation of Gm testing results: Two case histories. *J Forensic Sci*, 1982, **27**(1): 231–235.

Sonneborn, H.H., Comments on the determination of isoenzyme polymorphism (ADA, AK, 6-PGD, PGM) by cellulose acetate electrophoresis. *Humangenetik*, 1972, **17**(1): 49–55.

Sorensen, S.A., Agarose gel electrophoresis of the human red cell acid phosphatase. *Vox Sang*, 1974, **27**(6): 556–563.

Sorensen, S.A., Report and characterization of a new variant, EB, of human red cell acid phosphatase. *Am J Hum Genet*, 1975, **27**(1): 100–109.

Stedman, R., Human population frequencies in twelve blood grouping systems. *J Forensic Sci Soc*, 1972, **12**(2): 379–413.

Stolorow, M.D. and B.G. Wraxall, An efficient method to eliminate streaking in the electrophoretic analysis of haptoglobin in bloodstains. *J Forensic Sci*, 1979, **24**(4): 856–863.

Sutton, J.G. and R. Burgess, Genetic evidence for four common alleles at the phosphoglucomutase-1 locus (*PGM1*) detectable by isoelectric focusing. *Vox Sang*, 1978, **34**(2): 97–103.

Teige, B., et al., Forensic aspects of haptoglobin: Electrophoretic patterns of haptoglobin allotype products and an evaluation of typing procedure. *Electrophoresis*, 1988, **9**(8): 384–392.

Thogmartin, J.R., et al., Sickle cell trait-associated deaths: A case series with a review of the literature. *J Forensic Sci*, 2011, **56**(5): 1352–1360.

Turowska, B. and M. Bogusz, The rare silent gene Po of human red cell acid phosphatase in a second family in Poland. *Forensic Sci*, 1978, **11**(3): 175–176.

Twibell, J. and P.H. Whitehead, Enzyme typing of human hair roots. *J Forensic Sci*, 1978, **23**(2): 356–360.

Whitehead, P.H., L.A. King, and D.J. Werrett, New information from bloodstains. *Naturwissenschaften*, 1979, **66**(9): 446–451.

Whitehead, P.H., et al., The examination of bloodstains by Laurell electrophoresis (antigen-antibody crossed electrophoresis). *J Forensic Sci Soc*, 1970, **10**(2): 83–90.

Wraxall, B.G. and E.G. Emes, Erythrocyte acid phosphatase in bloodstains. *J Forensic Sci Soc*, 1976, **16**(2): 127–132.

Wrede, B., E. Koops, and B. Brinkmann, Determination of three enzyme polymorphisms in one electrophoretic step on horizontal polyacrylamide gels. *Humangenetik*, 1971, **13**(3): 250–252.

Yuasa, I. and K. Umetsu, Molecular aspects of biochemical markers. *Leg Med*, 2005, **7**: 251–254.

19

Variable Number Tandem Repeat Profiling

Tandem repeats are abundant in the human genome. *Minisatellites* were first defined as a class of tandem repeats in the 1980s. Some of these repeats share a GC-rich core sequence. Subsequently, tandem repeats with higher AT contents of core sequence have also been characterized. The minisatellites are also called *variable number tandem repeats* (*VNTRs*), as shown in Figure 19.1. The repeat unit length of a VNTR can range from several to hundreds of base pairs (bp). The tandem repeat arrays can be kilobases (kb, corresponding to 10^3 bp) long, and the numbers of tandem repeat units in some VNTR loci are highly variable, leading to variable lengths of DNA fragments. A genotype is defined by a particular number of tandem repeat units at a given locus.

Table 19.1 lists the common VNTR loci used for forensic testing. To achieve high discriminating power, the VNTR loci should not be linked, which means that they should be inherited independently of each other. For example, loci located on different chromosomes or far apart on the same chromosome can be used (Section 21.2). Many VNTR loci used for forensic applications are highly polymorphic, and as many as hundreds of different genotypes per locus can be observed among the population. The discriminating power of VNTR loci used for forensic testing can be measured by *population match probability* (P_m; Chapter 25). The lower the P_m, the less likely a match will occur between two randomly chosen individuals. A P_m of up to 10^{-12} can be achieved by testing several VNTR loci.

19.1 Restriction Fragment Length Polymorphism

VNTR profiling utilizes RFLP—the first historical method used in forensic DNA testing (Figure 19.2). It utilizes *restriction endonucleases* that recognize and cleave specific sites along the DNA sequence. Cleavage of a DNA sample with a particular restriction endonuclease results in a reproducible set of restriction fragments of various lengths. Appropriate restriction endonucleases should be selected so that the genomic DNA is cleaved at sites that flank the VNTR core repeat region. The resulting fragments are then separated according to their sizes by gel electrophoresis through a standard agarose gel (Chapter 9).

The DNA is then processed using the *Southern transfer and hybridization* technique. The DNA is denatured and transferred from the gel to a supporting matrix such as a nylon or nitrocellulose membrane. The DNA immobilized on the membrane is then hybridized with a labeled *probe*. Only bands of DNA that have complementary sequences to the probe are recognized by detection systems such as autoradiography (Section 19.1.4). Using the RFLP technique, the



Figure 19.1 VNTR locus D2S44 (2q21.3–2q22). Each repeat unit consists of 31 bp. *Hae*III represents the *Hae*III restriction site.

Table 19.1 Common VNTR Loci

Locus	Chromosome Location	Repeat Unit Length (bp)	*Hae*III Fragment Size (kb)	Probe
D1S7	1	9	0.5–12	MS1
D2S44	2	31	0.7–8.5	yNH24
D4S139	4	31	2–12	pH30
D10S28	10	33	0.4–10	pTBQ7
D14S13	14	15	0.7–12	pCMM101
D16S85	16	17	0.2–5	3′HVR
D17S26	17	18	0.7–11	pEFD52
D17S79	17	38	0.5–3	V1

Source: Adapted from Budowle, B., et al., *DNA Typing Protocols: Molecular Biology and Forensic Analysis*, Eaton Publishing, Natick, MA, 2000; Office of Justice Programs, Future of forensic DNA testing: Predictions of the Research and Development Working Group. National Institute of Justice, US Department of Justice, 2000.

length variations among restriction sites can be detected. Most forensic applications focus on the length variations of VNTR regions located between two restriction sites.

In summary, the RFLP method includes several steps: (1) genomic DNA preparation, (2) restriction endonuclease digestion of the genomic DNA into fragments, (3) agarose gel electrophoretic separation of the DNA fragments according to size, (4) transfer of DNA fragments using Southern transfer, (5) hybridization with locus-specific probes, and (6) detection of locus-specific bands by autoradiography or chemiluminescence.

19.1.1 Restriction Endonuclease Digestion

Restriction endonucleases are enzymes that cleave the phosphodiester bond of DNA at or near specific recognition nucleotide sequences known as restriction sites. A restriction site usually is a short motif that is 4–8 bp in length. It often has a specific palindromic recognition sequence, that is, a segment of double-stranded DNA in which the nucleotide's sequence is identical with an inverted sequence in the complementary strand. Thus, double-stranded DNA is required to be cleaved by most restriction endonucleases. As a result, both sticky ends and blunt ends of restriction fragments can be generated after the cleavage (Figure 19.3).

To date, hundreds of restriction endonucleases have been described. They are traditionally classified into three types on the basis of subunit composition and enzymatic properties. Type II restriction endonucleases are most commonly used in molecular biology applications. Type II restriction endonucleases, requiring magnesium as a cofactor, usually cleave DNA at defined positions within their recognition sequences. The Enzyme Commission (EC) number of type II


Restriction
digestion
(a)
Size standards
Crime scene sample
Suspect 1
Suspect 2
Size standards
Southern transfer
Probing and detection
Agarose gel
Nylon membrane
Nylon membrane
(b)

Figure 19.2 RFLP. (a) Restriction digestion generates restriction fragments with various lengths of genomic DNA. (b) Restriction fragments are separated by gel electrophoresis. DNA is transferred to a solid phase and probed. The signal is detected and the DNA fragment of interest can be observed. Band patterns of heterozygous loci of individuals are shown. (© Richard C. Li.)

restriction endonucleases is EC 3.1.21.4. The EC number is a numerical classification system of nomenclature based on the chemical reaction that is catalyzed by the enzyme. In contrast, type I (EC 3.1.21.3) and type III (EC 3.1.21.5) restriction endonucleases cleave at sites remote from their recognition site, which are not utilized for RFLP applications.

Restriction endonucleases are isolated from various bacteria. Each enzyme is named using a nomenclature system after the bacterium from which it was isolated. For example, in the restriction enzyme *Hae*III, H is from the genus name *Haemophilus*, ae is from the species name *aegypticus*, and III stands for the third endonuclease isolated from the *Haemophilus aegyptius* bacteria.

The restriction endonucleases play a role in protecting the bacteria from phage (bacterial virus) infections by using their endonucleases to destroy foreign DNA molecules. Bacterial DNA is usually methylated. In prokaryotes, the *Dam* methylase transfers a methyl group to the N6 position of the adenine in the sequence GmATC and the *Dcm* methylase transfers a methyl



Figure 19.3 Restriction sites for *Hae*III, *Hinf*I, and *Pst*I. *Hae*III digestion produces a blunt end DNA fragment. *Hinf*I and *Pst*I digestions produce sticky ends. *N* represents any nucleotide. (© Richard C. Li.)

group to the C5 position of cytosine in the sequences CmCAGG and CmCTGG. The activities of restriction endonucleases can be influenced by DNA methylation. Many restriction endonucleases cannot cleave methylated DNA. Therefore, bacterial DNA is distinguishable from foreign DNA by the bacteria's restriction endonucleases. This phenomenon protects bacterial DNA from digestion by their own endonucleases. Note that because DNA methylation also occurs in the human genome (Chapter 11), it is important to choose the restriction endonucleases that are not affected by the methylation of human genomic DNA for RFLP analysis.

The type II restriction endonucleases were used in RFLP analysis for forensic DNA testing (Figure 19.3). In order to perform this analysis, the preferred restriction endonucleases for RFLP were those that cleave at the flanking regions of VNTR repeat units but not within the core repeat sequences of the VNTR. Most forensic laboratories used a single restriction endonuclease for a panel of VNTR loci because the DNA in evidence samples was often insufficient for performing multiple tests with different restriction endonucleases. For instance, *Hinf*I-based RFLP was commonly used in European forensic laboratories, and *Hae*III-based RFLP was used in North American and some European forensic laboratories. Other restriction endonuclease-based RFLPs such as *Pst*I were also used.

The use of these common restriction endonucleases allows the comparison of data of various laboratories. Several VNTR loci are suitable for RFLP analysis with these restriction endonucleases. For example, *Hae*III presents several advantages for forensic RFLP analysis. It recognizes a four-base sequence, 5′-GGCC-3′, and cleaves the DNA between the internal G and C residues of the recognition site (GG/CC). *Hinf*I recognizes a five-base restriction site, and *Pst*I recognizes a six-base restriction site. Hypothetically, four-base restriction sites are likely to occur more often than five- and six-base restriction sites in the human genome. Thus, *Hae*III restriction sites occur more frequently than *Hinf*I and *Pst*I sites. As a result, *Hae*III-cleaved DNA fragments are smaller than those of *Hinf*I and *Pst*I. The *Hae*III-generated VNTR allele sizes are easier to separate using conventional agarose gels, also called analytic gel electrophoresis. After electrophoresis, a smear of various sizes of DNA fragments can be observed. The analytic gel is then processed for Southern transfer. Moreover, the enzymatic activity of *Hae*III is not affected by the methylation of human genomic DNA. Its enzymatic activities also appear unaffected when a reaction proceeds under nonoptimal conditions. Additionally, low star activity is observed (Section 19.1.5.2.2).

19.1.2 Southern Transfer

Also known as *Southern blotting*, this technique was named after Sir Edwin Southern, who developed it in the United Kingdom in the mid-1970s. The method can be used to transfer

DNA from an agarose gel to a solid matrix so that it can be detected with a hybridization probe (Section 19.1.3). This method is still used today in many research laboratories. Prior to the transfer of DNA, the DNA in the gel must be denatured, under alkaline conditions such as treatment with sodium hydroxide, into single-stranded DNA. The single-stranded DNA in the gel is then transferred by capillary action to a solid matrix such as a piece of nylon membrane. The single-stranded DNA fragments transferred can be immobilized on a nylon membrane by an ultraviolet cross-linking process (Figure 19.4).

19.1.3 Hybridization with Probes

A hybridization probe of RFLP is a small segment of labeled DNA that is usually several hundred to a thousand bases in length containing the VNTR sequence. It is utilized to detect the presence of much longer target DNA sequences, in this case the VNTR sequences that are complementary to the nucleotide sequences of the probe. The probe is first denatured by heating or by exposure to alkaline conditions into single-stranded DNA. The hybridization process allows complementary pairing between the probe and the target sequence. Two types of probe techniques were developed for VNTR analysis: the multilocus probe and single-locus probe techniques.

19.1.3.1 Multilocus Probe Technique

The *multilocus probe* (*MLP*) technique can detect multiple VNTR loci simultaneously (Figure 19.5). Some VNTRs in the human genome share a short GC-rich core sequence of 10–15 bp. The MLP consists of this core sequence and hybridizes to multiple VNTRs that share these core sequences. As a result, the utilization of MLP produces a complex bar-code-like band pattern from alleles of multiple VNTR loci (Figure 19.6).

The MLP technique was pioneered by Sir Alec Jeffreys in 1984 at the University of Leicester in the United Kingdom and was called *DNA fingerprinting*. Because of its excellent discriminating power, the method was used for parentage testing in immigration disputes with great success.



Figure 19.4 Southern blotting. DNA in agarose gel is denatured into single-stranded DNA and transferred to a solid-phase membrane where the single-stranded DNA is immobilized by ultraviolet cross-linking. (© Richard C. Li.)



Figure 19.5 VNTR analysis using the MLP method. The technique can detect multiple VNTR loci simultaneously. Restriction sites are indicated by arrows. (© Richard C. Li.)



Figure 19.6 First application of DNA fingerprinting. The MLP method was used to analyze samples for an immigration case. M, mother; U, three undisputed children; B, male child in dispute; X, an unrelated individual. All bands in B can be traced back to M or U. (From Jeffreys, A.J., *Nat Med*, 11, 1035, 2005. With permission.)

However, one of the disadvantages of the MLP approach is that the interpretation of a mixed DNA sample from more than one individual is nearly impossible due to its complex DNA fingerprinting patterns. Therefore, MLP analysis was not widely utilized in forensic DNA laboratories.

19.1.3.2 Single-Locus Probe Technique

To resolve the disadvantages encountered in the MLP technique, probes that recognize the genomic DNA at the flanking regions of specific VNTR loci can be used. The probe only hybridizes to a single VNTR locus and the technique is called the *single-locus probe* (*SLP*), as depicted in Figure 19.7. SLP generates a simple pattern called a *DNA profile*, consisting of one band for a homozygote and two bands for a heterozygote per locus. In order to improve the discriminating power of the test, SLP analyses of different VNTR loci can be performed by using different probes sequentially with a single locus at one time. SLP can analyze mixed DNA samples from two or more contributors. The sizes of fragments can be estimated and converted into a numerical form suitable for databasing. Therefore, DNA profiles can be compared among different laboratories.



Figure 19.7 VNTR analysis using the SLP method. The technique can detect a single VNTR locus. Restriction sites are indicated by arrows. (© Richard C. Li.)

This technique led to the solving of a double murder case in Leicestershire in the 1980s. The case was the first to apply DNA evidence to a criminal investigation. DNA profiling identified the true perpetrator and also excluded an innocent suspect (Figure 19.8). In 1983 and 1986, two girls were raped and murdered. Crime scene evidence suggested that the two cases were committed by the same perpetrator. A young local man, Richard Buckland, was the suspect. However, the DNA evidence revealed that the semen samples from both crimes did not originate from Buckland. To solve the crimes, an investigation was carried out in which 5000 local men were asked to volunteer DNA samples for testing. Several months after the investigation, a witness tipped off police that a man named Pitchfork had paid someone for giving a blood sample as Pitchfork's. In 1987, Pitchfork was arrested. It was discovered that Pitchfork's DNA profile matched that of the crime scene evidence. He was sentenced to life imprisonment. This case demonstrated the great potential of DNA profiling in forensic investigations. Consequently, SLP became a common method in most forensic laboratories in the late 1980s–1990s.

19.1.4 Detection

To detect VNTR loci, a labeled SLP probe is hybridized to the target sequence of DNA, which has been immobilized on a solid matrix such as a piece of nylon membrane (see Southern



Figure 19.8 First application of DNA profiling in a criminal investigation using the SLP method. A, hair roots from the first victim; B, a mixture of semen and vaginal fluid from the first victim; C, blood from second victim; D, a vaginal swab from the second victim; E, a semen stain on clothing from the second victim; S, blood from the suspect. Alleles (arrows) are matched with the profiles of the two cases but not with the suspect profile. (From Jeffreys, A.J., *Nat Med*, 11, 1035, 2005. With permission.)

transfer, Section 19.1.2). Any unbound probes are washed away so that they do not interfere with the signal. Two types of detection systems are used for VNTR analysis. Radioisotope labeling, such as with a ^{32}P-labeled probe, can be used. The hybridized probe can be detected by exposing the membrane to a sheet of x-ray film to generate an autoradiograph. Alternatively, an enzyme-conjugated probe can also be used. Alkaline phosphatase (Section 9.2.2) is an example of an enzyme used in this type of probe. Its enzymatic activity can be detected with chemiluminescent substrates. A chemiluminescent signal can be detected by exposure to x-ray film as well.

In RFLP analysis, several loci are commonly analyzed sequentially using the same membrane. This approach has the advantage of not consuming additional DNA samples, which are often limited in forensic cases. When probing for multiple loci, multiple probes for each locus are sequentially hybridized and removed one at a time. Once the analysis of the first probe is completed, the probe is removed by a procedure called probe stripping, which is carried out under conditions such as high-temperature washing to denature the DNA strands (Chapter 17). The probe for the next locus to be analyzed is then hybridized to the same membrane, and the process is repeated for each probe to be tested.

Typically, a size standard is utilized on each gel. Band sizes can thus be estimated by comparison to these standards. However, the VNTR alleles that differ by only one or two repeat units are usually not distinguishable. For this reason, genotypes can be determined by bins but not discrete alleles. A *bin* is a range of DNA fragments that differ by only a few repeat units. A sample with a known VNTR genotype is also utilized on each gel as a positive control where historically a genomic DNA sample from cell line K562 (a human erythroleukemic cell line) was used for the positive control. DNA samples to be compared can be loaded side by side on the same gel. As a result, the patterns of VNTR fragments can be compared from sample to sample. The following possible conclusions can be made. If the VNTR fragments are at corresponding positions (profiles match), they are considered to be a match (inclusion). Chapter 25 evaluates and discusses the strengths of the results. If the profiles are different, the two DNA samples are considered to have come from different origins (exclusion).

19.1.5 Factors Affecting RFLP Results

The accuracy of VNTR profiling results can be affected by certain factors such as sample conditions, genetic mutations, and experimental artifacts appearing during the procedure. Consequently, these factors can impact data interpretation and are explained in the following sections.

19.1.5.1 DNA Degradation

RFLP analysis requires the genomic DNA to be intact. DNA degradation results in damage such as creating nicks and breaks in the strand. The more severe the degradation, the smaller the average size of the DNA fragments. When the average size of DNA fragments becomes too small, the allele may not be detected. Many VNTR tandem arrays can span several kilobases in length. In theory, large alleles are more likely to be affected by degradation than smaller alleles at a different locus.

A two-banded heterozygous profile can be observed as a one-banded homozygous profile if the larger band is not detected due to degradation. This artifact could lead to a false determination of exclusion. However, DNA degradation can be detected prior to conducting RFLP by the use of agarose gel electrophoresis, also known as a *yield gel*, used for evaluating the yield and integrity of the isolated genomic DNA. High-molecular-weight genomic DNA bands are usually observed for a typical genomic DNA sample. In contrast, a smear of low-molecular-weight DNA bands can be observed if DNA is degraded. The sizes of the DNA can be estimated by comparison to a size standard run on the same gel. Additionally, the yield of DNA can be estimated by comparing the intensity of the size standards with a known quantity of DNA.

19.1.5.2 Restriction Digestion–Related Artifacts

19.1.5.2.1 Partial Restriction Digestion

Complete restriction digestion should be achieved for RFLP analysis. If partial digestion occurs, the partially cleaved DNA strands are longer than the cleaved fragments (Figure 19.9). Thus, partial digestion results in a mixture of fragments with correct sizes and slightly larger fragments. Under these conditions, a larger uncleaved band, usually lower in intensity than the true bands, can be observed. The multibanded pattern due to the partial digestion can be observed at multiple loci analyzed in the same nylon membrane.

Detection of more than two bands in an RFLP profile may lead to a false interpretation and be incorrectly concluded to be a mixture. However, partial digestion can be detected after restriction digestion. DNA cleavage by restriction endonuclease digestion can be examined using agarose gel electrophoresis. A small portion of a sample can be analyzed. After separation using electrophoresis, a smear of various sizes of cleaved DNA fragments can usually be observed if restriction digestion is completed. Conversely, high-molecular-weight genomic DNA can still be observed from partially digested DNA samples. Additionally, comparisons can be made between the sample and uncleaved and completely cleaved standard samples of DNA. This quick assay is also called a *test gel*, used to determine if the DNA was cleaved to completion.

If partial digestion occurs, procedures such as additional purification of the DNA sample can be carried out. Additionally, optimal amounts of DNA, restriction enzymes, buffer, and proper incubation conditions should be used in achieving complete digestion.

19.1.5.2.2 Star Activity

Star activity refers to a deviation of the specificity of a cleavage site of a restriction endonuclease under certain conditions, such as a high concentration ratio of enzyme to DNA, the use of non-optimal buffers for restriction digestion, prolonged digestion time, the substitution of Mg^{2+} with other divalent cations, and the presence of organic solvents such as ethanol and concentrated glycerol. For instance, *Hae*III cleaves at the GGCC DNA sequence. When star activity occurs, the enzymatic specificity is reduced and cleaves at a sequence slightly different from GGCC. If the start site is presented at an internal location of a VNTR locus, the enzyme would cleave the GGCC sequences and additionally cleave at the internal star site (Figure 19.10). This would result in an additional band smaller than the true alleles, although the intensity of this band is usually not the same as other bands. Thus, a multiband pattern is observed. However, the star


*Hae*III
SLP
*Hae*III
*Hae*III
Correct size (complete digestion)
Incorrect size (partial digestion)

Figure 19.9 Effects of partial restriction digestion on the RFLP profile. Only the restriction fragments detectable by the probe are shown. *Hae*III restriction sites are indicated by arrows. (© Richard C. Li.)



Figure 19.10 Star effects on RFLP profiles. Only the restriction fragments detectable by the probe are shown. *Hae*III restriction sites and star sites are indicated by arrows. (© Richard C. Li.)

site presented externally to a VNTR locus cannot be detected by the probe and does not affect the profiling results. Star activity can usually be avoided by carrying out restriction digestion reactions under conditions recommended by their manufacturers.

19.1.5.2.3 Point Mutations

A *point mutation* is caused by the substitution, deletion, or insertion of a single nucleotide. Point mutations at a restriction site within flanking regions may abolish the site, and the result is a band slightly larger than the true allele (Figure 19.11). The point mutation may also be present internally in a VNTR sequence. If such a point mutation creates a restriction enzyme site, the enzyme will cleave at the regular site and at the mutation site and yield two smaller bands. If the created restriction site is located internal to the probe binding region, both bands will be detected for that allele. These rare mutations obey Mendelian inheritance.

19.1.5.3 Electrophoresis and Blotting Artifacts

19.1.5.3.1 Partial Stripping

If more than one VNTR locus is analyzed sequentially using the same membrane, a probe must be removed by the stripping process before the application of the next probe. Any probe remaining on the membrane due to partial stripping may generate additional bands when the next probe is analyzed. However, bands due to partial stripping are usually faint and have the same electrophoretic mobility as the previous autoradiograph.

19.1.5.3.2 Separation Resolution Limits and Band Shifting

Agarose gel electrophoresis cannot resolve restriction fragments that differ by one or a few repeat units, especially for high-molecular-weight fragments. These bands may not be



Figure 19.11 Effects of point mutations on the RFLP profile. Only the restriction fragments detectable by the probe are shown. *Hae*III restriction sites are indicated by arrows. (a) Point mutation (in red) abolishes the *Hae*III restriction site. (b) A point mutation (in red) creates an internal *Hae*III restriction site residing within the probe-binding region. (c) A point mutation (in red) creates an internal *Hae*III restriction site residing outside the probe-binding region. (© Richard C. Li.)

separated and will appear as a single band. This may lead to a false interpretation as a homozygous profile. Additionally, minor variations in the electrophoretic mobility of DNA fragments, known as band shifting, can cause two samples from the same individual to appear different.

19.1.5.3.3 Bands Running off Gel

The commonly used VNTR loci generate bands from hundreds of base pairs to 20 kb in length. The small bands have higher electrophoretic mobility and may run off the front edge of a gel during electrophoresis and fail to be detected. This phenomenon may also lead to a false interpretation as a homozygous profile. To prevent these DNA fragments from running off the gel into the buffer tank, a longer gel can be used. Alternatively, the electrophoresis can be stopped before the dye front, the furthest extent that dyes migrate, reaches the front edge of the gel.

19.2 Amplified Fragment Length Polymorphism

The RFLP analysis of VNTR profiling does not perform well for degraded or limited quantities of DNA from crime scene samples. For these reasons, an improved VNTR method was developed. Some VNTR loci have relatively short alleles (<1 kb). These loci are suitable for PCR amplification. This technique is called *amplified fragment length polymorphism* (*AFLP*). One locus, D1S80, was used by forensic DNA laboratories for AFLP analysis. Fragments in the range of 14–42 repeat units (16 bp per repeat) were amplified using the AFLP method (Figure 19.12). The amplified DNA fragments were commonly separated according to size using polyacrylamide gel electrophoresis and detected using a silver stain (Figure 19.13).

D1S80 loci are detected as discrete alleles and thus can be compared directly to an allelic ladder (a collection of common alleles used as a standard) on the same gel. This technique represented an improvement over the RFLP system. RFLP allele sizing cannot be performed with precision and the resolution limits of agarose gel electrophoresis are much lower than those of the polyacrylamide gels.

The AFLP technique requires less DNA than the RFLP method and performs better for degraded samples. The AFLP method at the D1S80 locus can be analyzed in a multiplex fashion with an amelogenin locus (Chapter 21). The amelogenin gene is used for forensic sex-typing applications. Typing the amelogenin gene enables the determination of the sex of the contributor of a biological sample.

Due to the wide variation in allele sizes at the D1S80 locus, preferential amplification may be observed. Under certain conditions, the larger alleles may not be as consistently amplified as the small alleles, which may cause lower signal intensity of the larger allele. Additionally, only one locus is analyzed in this system. Furthermore, the D1S80 locus contains two alleles that are very common in some populations. Thus, the discriminating power is reduced compared to RFLP. D1S80 was gradually replaced by multiplex STR systems in the late 1990s.



Figure 19.12 VNTR locus D1S80 (chromosome 1p). Each repeat unit is 16 bp long. PCR primers are indicated to amplify the core repeat region.


Amplicon
Amplicon
(a)
Allelic ladder
Crime scene evidence
Suspect 1
Suspect 2
Allelic ladder
(b)

Figure 19.13 AFLP analysis. (a) Heterozygous D1S80 loci amplified by PCR. PCR primers are indicated as *arrows*. (b) Silver-stained polyacrylamide gel showing D1S80 amplicons along with allelic ladders. (© Richard C. Li.)

Bibliography

RFLP

Balazs, I., et al., Human population genetic studies of five hypervariable DNA loci. *Am J Hum Genet*, 1989, **44**(2): 182–190.

Benzinger, E.A., et al., Time course and inhibitors of *Hae*III digestion in the forensic laboratory. *Appl Theor Electrophor*, 1995, **4**(4): 179–188.

Benzinger, E.A., et al., Products of partial digestion with *Hae*III. Part 1. Characterization, casework experience and confirmation of the theory of three-, four- and five-banded RFLP pattern origins using partial digestion. *J Forensic Sci*, 1997, **42**(5): 850–863.

Benzinger, E.A., et al., An illustrated guide to RFLP troubleshooting. *J Forensic Sci*, 1998, **43**(3): 665–679.

Bragg, T., et al., Isolation and mapping of a polymorphic DNA sequence (cTBQ7) on chromosome 10 [D10S28]. *Nucleic Acids Res*, 1988, **16**(23): 11395.

Budowle, B., et al., *Hae*III—A suitable restriction endonuclease for restriction fragment length polymorphism analysis of biological evidence samples. *J Forensic Sci*, 1990, **35**(3): 530–536.

Budowle, B., et al., Fixed-bin analysis for statistical evaluation of continuous distributions of allelic data from VNTR loci, for use in forensic comparisons. *Am J Hum Genet*, 1991, **48**(5): 841–855.

Budowle, B., et al., Simple protocols for typing forensic biological evidence: Chemiluminescent detection for human DNA quantitation and restriction fragment length polymorphism (RFLP) analyses and manual typing of polymerase chain reaction (PCR) amplified polymorphisms. *Electrophoresis*, 1995, **16**(9): 1559–1567.

Budowle, B., et al., The assessment of frequency estimates of *Hae*III-generated VNTR profiles in various reference databases. *J Forensic Sci*, 1994, **39**(2): 319–352.

Budowle, B., et al., *DNA Typing Protocols: Molecular Biology and Forensic Analysis*, 2000. Natick, MA: Eaton Publishing.

Duewer, D.L., K.L. Richie, and D.J. Reeder, RFLP band size standards: NIST standard reference material 2390. *J Forensic Sci*, 2000, **45**(5): 1093–1105.

Duewer, D.L., et al., Interlaboratory comparison of autoradiographic DNA profiling measurements. 4. Protocol effects. *Anal Chem*, 1997, **69**(10): 1882–1892.

Elder, J.K. and E.M. Southern, Measurement of DNA length by gel electrophoresis II: Comparison of methods for relating mobility to fragment length. *Anal Biochem*, 1983, **128**(1): 227–231.

Eriksen, B. and O. Svensmark, Comparison of two molecular weight markers used in DNA-profiling. *Int J Legal Med*, 1992, **105**(3): 145–148.

Gary, K.T., D.L. Duewer, and D.J. Reeder, Graphical tools for RFLP measurement quality assurance: Laboratory performance charts. *J Forensic Sci*, 1999, **44**(5): 978–982.

Gill, P. and D.J. Werrett, Exclusion of a man charged with murder by DNA fingerprinting. *Forensic Sci Int*, 1987, **35**(2–3): 145–148.

Giusti, A.M. and B. Budowle, Effect of storage conditions on restriction fragment length polymorphism (RFLP) analysis of deoxyribonucleic acid (DNA) bound to positively charged nylon membranes. *J Forensic Sci*, 1992, **37**(2): 597–603.

Hartmann, J.M., et al., The effect of sampling error and measurement error and its correlation on the estimation of multi-locus fixed-bin VNTR RFLP genotype probabilities. *J Forensic Sci*, 1997, **42**(2): 241–245.

Hau, P. and N. Watson, Sequencing and four-state minisatellite variant repeat mapping of the D1S7 locus (MS1) by fluorescence detection. *Electrophoresis*, 2000, **21**(8): 1478–1483.

Jeffreys, A.J., Genetic fingerprinting. *Nat Med*, 2005, **11**: 1035.

Jeffreys, A.J., V. Wilson, and S.L. Thein, Hypervariable "minisatellite" regions in human DNA. *Biotechnology*, 1985, **24**: 467–472.

Jeffreys, A.J., V. Wilson, and S.L. Thein, Individual-specific "fingerprints" of human DNA. *Nature*, 1985, **316**(6023): 76–79.

Jeffreys, A.J., M. Turner, and P. Debenham, The efficiency of multilocus DNA fingerprint probes for individualization and establishment of family relationships, determined from extensive casework. *Am J Hum Genet*, 1991, **48**(5): 824–840.

Kanter, E., et al., Analysis of restriction fragment length polymorphisms in deoxyribonucleic acid (DNA) recovered from dried bloodstains. *J Forensic Sci*, 1986, **31**(2): 403–408.

Kasai, K., Y. Nakamura, and R. White, Amplification of a variable number of tandem repeats (VNTR) locus (pMCT118) by the polymerase chain reaction (PCR) and its application to forensic science. *J Forensic Sci*, 1990, **35**(5): 1196–1200.

Laber, T.L., et al., Evaluation of four deoxyribonucleic acid (DNA) extraction protocols for DNA yield and variation in restriction fragment length polymorphism (RFLP) sizes under varying gel conditions. *J Forensic Sci*, 1992, **37**(2): 404–424.

Laber, T.L., et al., Validation studies on the forensic analysis of restriction fragment length polymorphism (RFLP) on LE agarose gels without ethidium bromide: Effects of contaminants, sunlight, and the electrophoresis of varying quantities of deoxyribonucleic acid (DNA). *J Forensic Sci*, 1994, **39**(3): 707–730.

Laber, T.L., et al., The evaluation and implementation of match criteria for forensic analysis of DNA. *J Forensic Sci*, 1995, **40**(6): 1058–1064.

Lander, E.S., DNA fingerprinting on trial. *Nature*, 1989, **339**(6225): 501–505.

Lewis, M.E., et al., Restriction fragment length polymorphism DNA analysis by the FBI laboratory protocol using a simple, convenient hardware system. *J Forensic Sci*, 1990, **35**(5): 1186–1190.

McNally, L., et al., The effects of environment and substrata on deoxyribonucleic acid (DNA): The use of casework samples from New York City. *J Forensic Sci*, 1989, **34**(5): 1070–1077.

Milner, E.C., et al., Isolation and mapping of a polymorphic DNA sequence pH30 on chromosome 4 [HGM provisional no. D4S139]. *Nucleic Acids Res*, 1989, **17**(10): 4002.

Nakamura, Y., et al., Isolation and mapping of a polymorphic DNA sequence pYNH24 on chromosome 2 (D2S44). *Nucleic Acids Res*, 1987, **15**(23): 10073.

Office of Justice Programs, Future of forensic DNA testing: Predictions of the Research and Development Working Group, 2000. National Institute of Justice, US Department of Justice.

Rankin, D.R., et al., Restriction fragment length polymorphism (RFLP) analysis on DNA from human compact bone. *J Forensic Sci*, 1996, **41**(1): 40–46.

Reed, K.C. and D.A. Mann, Rapid transfer of DNA from agarose gels to nylon membranes. *Nucleic Acids Res*, 1985, **13**(20): 7207–7221.

Richie, K.L., et al., Long PCR for VNTR analysis. *J Forensic Sci*, 1999, **44**(6): 1176–1185.

Rossi, U., International recommendations (as of March, 1988) on the application of methods involving DNA-polymorphisms in forensic haematology. *Haematologica*, 1989, **74**(2): 219–221.

Sharma, B.R., et al., A comparative study of genetic variation at five VNTR loci in three ethnic groups of Houston, Texas. *J Forensic Sci*, 1995, **40**(6): 933–942.

Stolorow, A.M., et al., Interlaboratory comparison of autoradiographic DNA profiling measurements. 3. Repeatability and reproducibility of restriction fragment length polymorphism band sizing, particularly bands of molecular size >10K base pairs. *Anal Chem*, 1996, **68**(11): 1941–1947.

Tahir, M.A., et al., Restriction fragment length polymorphism (RFLP) typing of DNA extracted from nasal secretions. *J Forensic Sci*, 1995, **40**(3): 459–463.

Tahir, M.A., et al., Deoxyribonucleic acid profiling by restriction fragment length polymorphism analysis—A compilation of validation studies. *Sci Justice*, 1996, **36**(3): 173–182.

Tully, G., K.M. Sullivan, and P. Gill, Analysis of 6 VNTR loci by “multiplex” PCR and automated fluorescent detection. *Hum Genet*, 1993, **92**(6): 554–562.

Wyman, A.R. and R. White, A highly polymorphic locus in human DNA. *Proc Natl Acad Sci U S A*, 1980, **77**(11): 6754–6758.

AFLP

Baechtel, F.S., K.W. Presley, and J.B. Smerick, D1S80 typing of DNA from simulated forensic specimens. *J Forensic Sci*, 1995, **40**(4): 536–545.

Baechtel, F.S., et al., Multigenerational amplification of a reference ladder for alleles at locus D1S80. *J Forensic Sci*, 1993, **38**(5): 1176–1182.

Budowle, B., et al., Analysis of the VNTR locus D1S80 by the PCR followed by high-resolution PAGE. *Am J Hum Genet*, 1991, **48**(1): 137–144.

Cosso, S. and R. Reynolds, Validation of the AmpliFLP D1S80 PCR amplification kit for forensic casework analysis according to TWGDAM guidelines. *J Forensic Sci*, 1995, **40**(3): 424–434.

Gross, A.M., G. Carmody, and R.A. Guerrieri, Validation studies for the genetic typing of the D1S80 locus for implementation into forensic casework. *J Forensic Sci*, 1997, **42**(6): 1140–1146.

Kasai, K., Y. Nakamura, and R. White, Amplification of a variable number of tandem repeats (VNTR) locus (pMCT118) by the polymerase chain reaction (PCR) and its application to forensic science. *J Forensic Sci*, 1990, **35**(5): 1196–1200.

Kloosterman, A.D., B. Budowle, and P. Daselaar, PCR-amplification and detection of the human D1S80 VNTR locus. Amplification conditions, population genetics and application in forensic analysis. *Int J Legal Med*, 1993, **105**(5): 257–264.

Koseler, A., A. Atalay, and E.O. Atalay, Allele frequency of VNTR locus D1S80 observed in Denizli Province of Turkey. *Biochem Genet*, 2009, **47**(7–8): 540–546.

Latorra, D. and M.S. Schanfield, Analysis of human specificity in AFLP systems APOB, PAH, and D1S80. *Forensic Sci Int*, 1996, **83**(1): 15–25.

Nakamura, Y., et al., Isolation and mapping of a polymorphic DNA sequence (pMCT118) on chromosome 1p [D1S80]. *Nucleic Acids Res*, 1988, **16**(19): 9364.

Sajantila, A., et al., Amplification of reproducible allele markers for amplified fragment length polymorphism analysis. *Biotechniques*, 1992, **12**(1): 16, 18, 20–22.

Skinker, D.M., et al., DNA typing of azoospermic semen at the D1S80 locus. *J Forensic Sci*, 1997, **42**(4): 718–720.

Skowasch, K., P. Wiegand, and B. Brinkmann, pMCT 118 (D1S80): A new allelic ladder and an improved electrophoretic separation lead to the demonstration of 28 alleles. *Int J Legal Med*, 1992, **105**(3): 165–168.

Walsh, S.J. and C. Eckhoff, Australian Aboriginal population genetics at the D1S80 VNTR locus. *Ann Hum Biol*, 2007, **34**(5): 557–565.

Watanabe, G., et al., Nucleotide substitution in the 5′ flanking region of D1S80 locus. *Forensic Sci Int*, 1997, **89**(1–2): 75–80.

20

Autosomal Short Tandem Repeat Profiling

A *short tandem repeat* (STR) is a region of genomic DNA containing an array of short repeating sequences. STRs are also called *microsatellites* or *simple sequence repeats*. A STR repeat unit can be several base pairs (bp) in length. Arrays range from several to approximately a hundred *repeat units*, which are the component of repetition. The number of STR repeat units varies among individuals. The most commonly used STR loci are 100–500 bp in length, which are shorter than the smallest variable number tandem repeats (VNTRs) (approximately 1000 bp). Thus, STR loci have many advantages compared to VNTR loci:

- STR loci can be amplified by PCR.
- STR profiling can be carried out for degraded DNA samples.
- Preferential amplification is reduced at STR loci.
- The resolution of electrophoretic separation of STR fragments is superior.
- STR loci are suitable for multiplex amplification.

Additionally, STR profiling, as with VNTR profiling, is suitable for the interpretation of mixed DNA profiles from multiple individuals. Thus, STR loci are better candidates for forensic DNA testing than VNTR loci. This chapter will discuss autosomal STR profiling. Male-specific Y chromosomal STR will be discussed in Chapter 21.

20.1 Characteristics of STR Loci

More than 10^5 STRs exist in the human genome. Many STRs have been characterized and used in various types of studies such as genetic mapping and linkage analysis. Some STRs have been characterized specifically for forensic DNA profiling.

20.1.1 Core Repeat and Flanking Regions

The *core repeat region* of each STR locus contains tandemly repeated sequences. The designation of genotypes for human identification is based on the number of tandem repeat units at a STR locus, which varies among human individuals (Figure 20.1). The *flanking regions* surrounding the core repeat region are also needed for STR analysis. PCR primers complementary to these flanking regions are used, allowing the core repeat regions to be amplified.



Figure 20.1 Core repeat and flanking regions of CSF1PO STR locus. It consists of eight repeating units of tetrameric nucleotides (TAGA); thus, it is designated as allele 8. (© Richard C. Li.)

20.1.2 Repeat Unit Length

Repeat unit length is the number of nucleotides in a single repeat unit. Dimeric, trimeric, tetrameric, pentameric, and hexameric repeat units appear in the human genome. For example, dimeric and trimeric repeats are very abundant, but they are not usually used for forensic applications. High frequencies of stutter peaks (Section 20.4.2.1) that interfere with genotype interpretation are observed when dimeric and trimeric repeats are amplified. On the contrary, only a few thousand pentameric repeats and a few hundred hexameric repeats exist in the human genome. The pentameric and hexameric repeats are very polymorphic. Only a few pentameric and hexameric repeats are used for forensic applications because they are less abundant in the human genome. The human genome has at least 10^4 tetrameric repeats representing approximately 9% of the total STRs. The STRs with tetrameric repeats are very polymorphic. When they are amplified by PCR, this category of STRs exhibits fewer frequencies of stutter peaks than STRs with dimeric and trimeric repeats. Therefore, the most commonly used STR loci for forensic DNA profiling are the STRs with tetrameric repeats.

20.1.3 Repeat Unit Sequences

STR loci compatible for forensic use can be divided into several classes based on their repeat unit sequences. Figure 20.2 shows representative examples of core repeat sequences. *Simple repeats* consist of tandem repeats with identical repeat unit sequences (Figure 20.2a). Allele designation is based on the number of repeat units in the core repeat region. For example, a D5S818 allele consisting of ten repeating units of the tetrameric nucleotide sequence AGAT is designated as allele 10. *Compound repeats* consist of more than one type of simple repeat (Figure 20.2b). *Complex repeats* contain several clusters of different tandem repeats with intervening sequences (Figure 20.2c).



Figure 20.2 Examples of core repeat sequences. (a) A simple repeat in which D5S818 $[AGAT]_{10}$ is designated as allele 10, consisting of 10 repeating units of the tetrameric nucleotides, AGAT. (b) Compound repeats. Allele 14 of D8S1179 consists of two types of repeating units: $[TCTA]_2$, $[TCTG]_1$, and $[TCTA]_{11}$. (c) Complex repeats. Allele 24 of D21S11 contains several clusters of different tandem repeats, $[TCTA]_4$, $[TCTG]_6$, and $[TCTA]_6$, with a 43 bp intervening sequence: $[TCTA]_3$ TA $[TCTA]_3$ TCA $[TCTA]_2$ TCCATA. (© Richard C. Li.)

Nonconsensus alleles with partial repeat units also appear in the population. These nonconsensus alleles, also known as *microvariants*, differ from common alleles by one or more nucleotides. They are designated by the number of consensus repeats, followed by a decimal point and the number of nucleotides of the partial repeat, for example, the TH01 allele 9.3 is 1 nucleotide shorter than allele 10.

Another type of nonconsensus allele can result from a limitation of STR analysis. These alleles have the same number of tandem repeats as common alleles but contain different sequences. These microvariants cannot be distinguished by STR profiling because their length is identical to the lengths of common alleles.

20.2 STR Loci Commonly Used for Forensic DNA Profiling

In the early 1990s, STR loci were initially utilized for genetic studies and were later applied to forensic DNA profiling. The first STR multiplex system, known as the quadruplex, was developed by Forensic Science Services in the United Kingdom. It consisted of four STR loci (F13A1, FES, TH01, and VWA) with a *population match probability* (P_m) of 10^{-4} (Figure 20.3). P_m measures the discriminating power of an STR locus used for forensic DNA analysis. The lower the P_m (i.e., the higher the discriminating power), the less likely a match will occur between two randomly chosen profiles from different individuals (Chapter 25). In 1995, the first national DNA database was established in the United Kingdom. It contained six STR loci, also known as the *second-generation multiplex* (SGM), consisting of D8S1179, D18S51, D21S11, FGA, TH01, and VWA, with a P_m value of 10^{-7}. The SGM system also included the amelogenin locus (Section 21.3.1) for determining the sexes of DNA contributors. Subsequently, four additional loci were added to SGM with a P_m as low as 10^{-13} (SGM Plus).

To allow for international data exchange, the European DNA Profiling Group (EDNAP) recommended the use of TH01 and VWA loci for all participating European laboratories in 1996. In 1998, the *European Standard Set* (ESS) of loci was established and included TH01, VWA, FGA, and D21S11 for forensic use in Europe. Thereafter, D3S1358, D8S1179, and D18S51 loci were added to the ESS. Other loci are used as well, such as SE33, which is used in Germany's database. In 1998, the US Federal Bureau of Investigation established the *Combined DNA Index System* (CODIS). It contains 13 core STR loci plus the amelogenin sex-typing locus with a P_m



Figure 20.3 DNA profile obtained using the first STR multiplex system: the quadruplex. F13A1, FES, TH01, and VWA loci are shown. (© Richard C. Li.)

Table 20.1 Common STR Loci

Locus Symbol	Repeat Motif	Repeat Category	Cytogenetic Map Location on Chromosome	Distance from pter (Mb)	Structural Gene
CSFIPO	TAGA	Simple	5q33.1	149.4	Intron 6 of c-fms protooncogene
FGA	[CTTT] [CCTT]	Compound	4q31.3	155.5	Intron 3 of fibrinogen α chain gene
TH01	AATG	Simple	11p15.5	2.2	Intron 1 of tyrosine hydroxylase gene
TPOX	TGAA	Simple	2p25.3	1.5	Intron 10 of thyroid peroxidase gene
SE33/ ACTBP2	AAAG	Complex	6q14	89	5′ Flanking sequence of β-actin-related pseudogene 2 gene
VWA	[TCTG] [TCTA]	Compound	12p13.31	6.1	Intron 40 of von Willebrand factor gene
D1S1656	[TAGA] [TAGC]	Compound	1q42.2	230.9	Anonymous
D2S441	[TCTA] [TCAA]	Compound	2p14	68.2	Anonymous
D2S1338	[TGCC] [TTCC]	Compound	2q35	218.9	Anonymous
D3S1358	[TCTG] [TCTA]	Compound	3p21.31	45.6	Anonymous
D5S818	AGAT	Simple	5q23.2	123.1	Anonymous
D7S820	GATA	Simple	7q21.11	83.8	Anonymous
D8S1179	[TCTA] [TCTG]	Compound	8q24.13	125.9	Anonymous
D10S1248	GGAA	Simple	10q26	–[a]	Anonymous
D12S391	[AGAT] [AGAC]	Compound	12p13.2	12.5	Anonymous
D13S317	TATC	Simple	13q31.1	82.7	Anonymous
D16S539	GATA	Simple	16q24.1	86.4	Anonymous
D18S51	AGAA	Simple	18q21.33	60.9	Anonymous
D19S433	[AAGG] [TAGG]	Compound	19q12	30.4	Anonymous
D21S11	[TCTA] [TCTG]	Complex	21q21.1	20.6	Anonymous
D22S1045	ATT	Simple	22q12.3	37.5	Anonymous

Source: Ensembl Homo sapiens version 75.37 (GRCh37). Mb, megabase.

[a] Locus is not mapped to the assembly in the current Ensembl database.

of 10^{-15}. As the database grows rapidly, the chances of finding incidental matches among DNA profiles are increasing. Recently, additional loci have been added to CODIS and ESS core loci to reduce the likelihood of adventitious matches, as well as to facilitate international data sharing among law enforcement agencies and to improve the discrimination power of forensic STR analysis.

Commonly used STR loci characterized for forensic DNA profiling are summarized in Tables 20.1 and 20.2. To achieve low P_m in forensic STR profiling, desired STR loci should possess certain characteristics as described below. First, the alleles of STR loci selected should be highly variable among individuals. Second, if more than one locus is selected, the loci should not be linked to each other or inherited together (Section 21.2). The STR loci utilized are usually located at different chromosomes to ensure that they are not linked. However, loci that are far

TABLE 20.2 Core STR Loci

Locus	SGM	SGM Plus	ESS	ESS-Extended	CODIS	CODIS-Extended
Amel	☑	☑	☑	☑	☑	☑
CSFIPO					☑	☑
D1S1656				☑		☑
D2S441				☑		☑
D2S1338		☑				☑
D3S1358		☑	☑	☑	☑	☑
D5S818					☑	☑
D7S820					☑	☑
D8S1179	☑	☑	☑	☑	☑	☑
D10S1248				☑		☑
D12S391				☑		☑
D13S317					☑	☑
D16S539		☑			☑	☑
D18S51	☑	☑	☑	☑	☑	☑
D19S433		☑				☑
D21S11	☑	☑	☑	☑	☑	☑
D22S1045				☑		2
DYS391						☑
FGA	☑	☑	☑	☑	☑	☑
THO1	☑	☑	☑	☑	☑	☑
TPOX					☑	1
VWA	☑	☑	☑	☑	☑	☑
SE33						3

Source: Hares, D.R., *Forensic Sci Int Genet*, 6, e135, 2012; Gill, P., et al., *Forensic Sci Int*, 156, 242–244, 2006.

☑, minimum required loci; 1–3, recommended loci in ranked order of preference.

enough apart on the same chromosome can still be used (Figures 20.4 and 20.5), since they are not linked. Additionally, STR loci with fewer amplification artifacts such as stutter products are desired. Stutters can complicate the interpretation of profiles derived from a mixed DNA sample from more than one contributor. Moreover, STR loci with short amplicon (amplified product) lengths are preferred for multiplex STR analysis and the testing of degraded DNA samples.


p15.3
p15.2
p15.1
p14
p13.3
p13.2
p13.1
p12
q11
q11.1
q11.2
q12
q13.1
q13.2
q13.3
q14
q15
q21
q22
q23.1
q23.2
q23.3
q31.1
q31.2
q31.3
q32
q33.1
q33.2
q33.3
q34
q35.1
q35.2
q35.3
D5S818
CSF1PO
(123.139 Mb) (149.436 Mb)

Figure 20.4 Cytogenetic map showing the locations of STR markers on chromosome 5. CSF1PO and D5S818 are separated by 26 Mb (megabases). (© Richard C. Li.)


p13
p12
p11.2
p11.1
q11.1
q11.2
q21
q22.1
q22.2
q22.3
D21S11
PentaD
(19.476 Mb)
(43.88 Mb)

Figure 20.5 Cytogenetic map showing the locations of STR markers on chromosome 21. D21S11 and PentaD are separated by 24 Mb (megabases). (© Richard C. Li.)

20.3 Forensic STR Analysis

STR loci are amplified using fluorescent dye-labeled primers. A multiplex STR system utilizes multiple fluorescent dyes to label each amplicon. The amplicons are separated via electrophoresis. The different fluorescent dye colors are resolved by the detector, and the signals corresponding to each DNA fragment are identified using specialized computer software. The data collection process generates an *electropherogram* that shows a profile of peaks corresponding to each DNA fragment. The positions of these peaks represent the electrophoretic mobility of the DNA fragments. A small fragment, migrating faster than a large one, peaks earlier in the electropherogram than a longer fragment. The DNA fragments are sized by comparison to an internal size standard (Figure 20.6; Chapter 8). Figure 20.7 summarizes the work flow of a forensic STR analysis.



Figure 20.6 Electropherogram of GeneScan™ 500 size standard (Applied Biosystems). RFU represents relative fluorescence unit. (© Richard C. Li.)


DNA extraction
DNA quantitation
PCR amplification (multiplex)
Electrophoresis
Detection of PCR products
Determine the size of STR fragment
Determine the genotype of STR loci
Electropherogram
Interpretation of STR profile

Figure 20.7 Capillary electrophoresis separation of amplified STR products. Fluorescent dye-labeled amplification products are separated and subsequently detected. Various fluorescent dye colors are resolved by the detector. The peaks corresponding to each DNA fragment are identified. (© Richard C. Li.)

The area or amplitude of the peak, expressed as relative fluorescence units (RFU) (Section 9.3.1.3), reflects the fluorescent signal intensity. The RFU value of peak height is proportional to the amount of DNA amplicons being analyzed. When the RFU value is very low, it is difficult to distinguish a signal from background noise. The manufacturer of commonly used instruments for forensic DNA analysis recommends 150 RFU as the threshold of detection. Peaks below 150 RFU should be interpreted with caution. Some forensic laboratories use lower thresholds, as low as 50 RFU, based on their own validation studies. In contrast, when the RFU value is too high, it saturates the sensitivity of an instrument as well as causing artifacts such as pull-up signals (Section 20.4.3.1). The maximum RFU allowed is usually 6000 RFU.

20.3.1 Determining the Genotypes of STR Fragments

As noted earlier, electropherograms are usually plotted as fluorescent signal intensity (in RFU) versus the sizes of the DNA fragments. The data in an electropherogram can then be converted into a genotype. The genotype for a specific STR locus is defined as the number of repeat units of the allele. STR genotype data generated from different laboratories can be compared easily and are suitable for databasing.

The genotype is determined by using an allelic ladder, which is important to achieve accurate genotype profiling. An allelic ladder is a collection of synthetic fragments corresponding to common alleles observed in the human population for a given set of STR loci (Figures 20.8 and 20.9). The ladders are compared to data obtained from an electropherogram of a questioned sample to determine the genotype. Thus, each allele in a ladder must be resolved properly in order to determine correct STR alleles for a sample. The sizes of DNA fragments of a sample are correlated to sizes of fragments for each allele in an allelic ladder in order to determine the allele designation (genotype) of a questioned sample (Figures 20.10 and 20.11). If a rare allele fails to match alleles within an allelic ladder, it is considered an *off-ladder allele*. If an off-ladder allele is present, the sample should be reanalyzed. The presence of a rare allele can be confirmed by repeating the electrophoresis process based on the characteristic electrophoretic mobility of the rare allele.

20.3.2 Interpretation of STR Profiling Results

General guidelines for the interpretation and the reporting of STR profile results were set by the Scientific Working Group on DNA Analysis Methods (SWGDAM) and the DNA Commission of the International Society of Forensic Genetics (ISFG). Typically, conclusions are categorized as inclusion, exclusion, or inconclusive result.

20.3.2.1 Inclusion (Match)

Peaks of compared STR loci, such as those between the profiles of suspect and crime scene evidence or victim and crime scene evidence, show identical genotypes. The strength of this conclusion can be evaluated via statistical analysis and is usually cited in the case report (Chapter 25).

20.3.2.2 Exclusion

The genotypes of two or more samples differ, and the profile of the sample is determined to be an exclusion, meaning that the profiles originated from different sources.

20.3.2.3 Inconclusive Result

The data do not support a conclusion of inclusion or exclusion. In other words, insufficient information is available to reach a conclusion.

20.4 Factors Affecting Genotyping Results

A number of genetics-, amplification-, and electrophoresis-related factors may affect the accuracy of genotypic profiles.



Figure 20.8 Electropherogram of the allelic ladder of the AmpFlSTR® COfiler® PCR Amplification Kit (Applied Biosystems). AMEL, CSF1PO, D3S1358, D7S820, D16S539, TH01, and TPOX loci are shown. (© Richard C. Li.)

20.4.1 Mutations

STR loci with low mutation frequencies are desired, in particular, for human identification in mass disasters and for missing person and paternity cases. However, STR mutations do occur, which can affect the profiling results.

20.4.1.1 Mutations at STR Core Repeat Regions

Mutations, usually resulting in a gain or a loss of a single repeat unit, are observed at STR loci. If a mutation occurs in the germ cells (cells that form gametes), the mutant allele will be transmitted to and be present in all cell types of the progeny. This type of inheritable mutation in germ cell lineage is called a *germ-line mutation*. The frequency of germ-line mutation can be measured by the *mutation rate*, expressed as the number of mutations per generation (germ-line transmission). The average mutation rate of commonly used STR loci is about 10^{-4} mutations per germ-line transmission. However, the mutation rate may vary among different STR loci.



Figure 20.9 Electropherogram of the allelic ladder of the AmpFlSTR® Identifiler® Plus Kit (Applied Biosystems). AMEL, CSF1PO, D2S1338, D3S1358, D5S818, D7S820, D8S1179, D13S317, D16S539, D18S51, D19S433, D21S11, FGA, TH01, TPOX, and VWA loci are shown. (© Richard C. Li.)



Figure 20.10 Individual DNA profile (Cofiler). The genotype of the DNA profile is shown. AMEL: X, X. CSF1PO: 10, 12. D3S1358: 14, 15. D16S539: 11, 12. D7S820:10, 11. TH01:8, 9.3. TPOX: 8, 8. (© Richard C. Li.)

In contrast, *somatic mutations* involve the mutation of only somatic cells. The germ cells are not affected, and thus a mutant allele is not transmitted to the progeny. A somatic mutation occurring at the core repeat region of an STR locus can be detected and compared to the wild-type allele. The ratio of the signal intensities of the wild-type and mutant alleles varies, depending on the number



Figure 20.11 Individual DNA profile (Identifiler). The genotype of the DNA profile is shown. AMEL: X, X. CSF1PO: 10, 10. D2S1338: 22, 23. D3S1358: 15, 15. D5S818: 12, 13. D7S820: 9, 10. D8S1179: 13, 15. D13S317: 12, 12. D16S539: 10, 11. D18S51: 16, 17. D19S433: 12, 12. D21S11: 28, 29. FGA: 9, 22. TH01: 7, 7. TPOX: 8, 9. VWA: 17, 17. (© Richard C. Li.)

of mutation-carrying cells in the tissue. Somatic mutations are usually tissue specific. STR profiles from different tissues of the same individual can be compared if a somatic mutation is suspected.

20.4.1.2 Chromosomal and Gene Duplications

Duplicating one of the homologous chromosomes results in a total of three copies of a particular chromosome. This condition, called *trisomy*, is rare and often associated with genetic diseases such as Down's syndrome (chromosome 21 duplication). Duplications have also been observed in chromosomes 13, 18, and X. Other anomalies include duplication of a portion of a chromosome and a single or group of genes instead of an entire chromosome.

A duplication bearing a mutation within the STR core repeat region can affect the number of tandem repeat units. If the duplicated locus is mutated, a *triallelic* or three-peaks pattern can be detected at a single locus, but not at loci located at other chromosomes in a multiplex STR profile (Figure 20.12). The three alleles usually have equal signal intensity (peak amplitude or peak area). Triallelic patterns at STR loci commonly used for forensic DNA analysis have been documented. Many occur at the TPOX, FGA, and CSF1PO loci. If the duplicate locus is not mutated, only two alleles will be observed in a heterozygote. However, the ratio of the peak amplitude of the alleles will be 1:2 (one copy vs. two copies including the duplicate) at that particular locus. However, STR profiles at the loci located at other chromosomes are not affected.

20.4.1.3 Point Mutations

Point mutations involve the changing of a nucleotide sequence through nucleotide substitution, insertion, or deletion. Insertion or deletion mutations affect the lengths of the core repeat regions and the amplified flanking regions of STR loci and thus affect STR profiles. Nucleotide substitution mutations (except those residing within the primer-binding regions) do not affect the length of DNA and thus do not affect STR profiles.

However, mutations occurring at the primer-binding sequences of the flanking regions of STR loci may affect genotype results. If a mutation at a primer-binding sequence prevents the primer from annealing to the template, this leads to a complete failure of the amplification of the allele. This phenomenon is known as a *null allele* or silent allele (Figure 20.13). To overcome the consequences of a null allele, an alternative primer annealing to a flanking region away from the mutated sequence can be used. Additionally, a primer with the sequence that is complementary to the known mutation can also be used. If the mutation does not completely prevent the primer from annealing but reduces the efficiency of the amplification, the resulting signal intensity of the allele is usually decreased. This problem may be solved by modifying the condition of amplification for the mutant allele.



Figure 20.12 Triallele. In this example, the triallele is observed only at D21S11 and not at other STR loci. (© Richard C. Li.)



Figure 20.13 Null allele. An allele present in the sample failed to be amplified by one of the primer sets as a result of a rare mutation at the primer-binding sequence of the flanking region: (a) wild type and (b) mutation. (© Richard C. Li.)

20.4.2 Amplification Artifacts

20.4.2.1 Stuttering

A stutter is a minor allele peak, also known as a stutter peak, whose repeat units are shorter or longer than the parental allele peak (Figure 20.14). Less stuttering is observed with pentameric and hexameric repeat unit loci compared to shorter repeat unit loci. The loci that contain complex repeat sequences usually exhibit reduced stuttering. At a given STR locus, large alleles appear to yield more stutter than smaller alleles.

Commonly observed stutters are one repeat unit shorter than the parental allele. It is believed that stuttering is due to the slippage of polymerase, which may have occurred during amplification reactions (Figure 20.15). Stutters with repeat units longer than the parental allele peak can also be observed, but are very rare. The *stutter ratio* is defined as the area of the stutter peak divided by the area of the parental peak. The stutter ratio is usually less than 0.15. A ratio of greater than 0.15 should be interpreted with caution due to the potential presence of DNA from more than one contributor.



Figure 20.14 Stutter products. (© Richard C. Li.)



Figure 20.15 Proposed mechanism for stutter products. During the DNA synthesis step of PCR amplification, a DNA polymerase slips, and a region of the primer–template complex becomes unpaired, causing the template strand to form a loop. The consequence of this one-repeat loop is a shortened PCR product smaller than the template by a single repeat unit. (© Richard C. Li.)

20.4.2.2 Nontemplate Adenylation

During PCR amplification, DNA polymerase often adds an extra nucleotide, usually an adenosine, to the 3′-end of an amplicon. Such a phenomenon is referred to as a *nontemplate addition* resulting in an amplicon that is one base pair longer than the parental allele (designated the +A peak), as shown in Figure 20.16. As a result, an amplicon has both the –A amplicon, which corresponds to the size of the parental allele, and the +A amplicon, which represents the amplicon with the nontemplate addition. To simplify the analysis, the most commonly used multiplex STR kits utilize amplification conditions that favor the adenylation of amplicons. Thus, most amplicons in a sample contain an additional adenosine at the 3′ end (+A peak). However, partial nontemplate addition can occur when too much DNA template is utilized in PCR amplification. As a result, a mixture of –A and +A peaks is usually observed.

20.4.2.3 Heterozygote Imbalance

Heterozygote imbalance occurs when one of the alleles has greater peak area or amplitude than the other allele within the same locus in which the two alleles of a heterozygote are compared (Figure 20.17). It is believed that heterozygote imbalance may arise if the DNA sample contains unequal copies of DNA template of the two alleles for the heterozygote, or the two alleles of a heterozygote are unequally amplified, a condition known as *preferential amplification*. Preferential amplification usually refers to an event where a smaller allele is amplified more efficiently than larger ones. As a result, the presence of heterozygote imbalance interferes with the interpretation of samples with a DNA mixture derived from more than one contributor.

20.4.2.4 Allelic Dropout

Allelic dropout occurs when an allele, usually one of the heterozygote alleles, fails to be detected. To date, our understanding of what causes the dropout is very limited. The occurrence of allelic dropout can be the result of an extreme situation of preferential amplification or heterozygote imbalance. Additionally, certain mutations leading to amplification failure (Section 20.4.1.3) can cause allelic dropout.



Figure 20.16 Nontemplate adenylation. OL represents the off-ladder allele. (© Richard C. Li.)



Figure 20.17 Heterozygote imbalance. The signal intensity of one allele is greater than that of the other allele within the same locus. (© Richard C. Li.)

20.4.3 Electrophoretic Artifacts

20.4.3.1 Pull-Up Peaks

A *pull-up peak* occurs when a minor peak of one color on an electropherogram is pulled up from a major allelic peak in another color (Figure 20.18) when the colors have overlapping spectra. For example, a green peak may pull up a yellow peak, or a blue peak may pull up a green peak. A pull-up peak may contribute to the inaccuracy of a profile if the position of a pull-up peak corresponds to the position of an allele. A pull-up peak often occurs when a sample is overloaded or a matrix file (a spectral calibration) is not updated. Thus, loading a proper amount of sample or installing an appropriate matrix file can prevent the occurrence of pull-up peaks.

20.4.3.2 Spikes

Spikes are sharp peaks, with similar signal intensities, that are present in all color panels of an electropherogram (Figure 20.19). Spikes are caused by air bubbles and urea crystals in the capillary of an electrophoretic platform. Voltage spikes can also contribute to spike peaks. The spikes are electrophoretic artifacts and are not reproducible. Thus, electrophoresis can be repeated to verify that the spikes occurred in a previous electrophoresis result.

20.5 Genotyping of Challenging Forensic Samples

20.5.1 Degraded DNA

Environmental exposure, such as high humidity and temperature, of biological evidence can lead to DNA degradation such as the breaking of DNA molecules into small fragments. The more severe the degradation, the more intensive the fragmentation. In forensic DNA analysis, the size range of STR amplicons is usually 100–500 bp in length. When a sample experiences some degradation, large alleles are less likely to be amplified than small alleles (Figures 20.20 and 20.21). As a result, the dropout of large alleles often occurs, leading to a partial DNA profile or even a failure in obtaining a DNA profile. To address this issue, the PCR primers can be



Figure 20.18 Pull-up peaks. The peaks with overlapping spectra observed in the top and middle panels are not observed in the bottom panel. (© Richard C. Li.)



Figure 20.19 Spike peaks can be observed in various intensities. (© Richard C. Li.)



Figure 20.20 Diagram of STR profiles of samples: without DNA degradation (top) and with degradation (bottom). Arrow: allelic dropout. (© Richard C. Li.)

redesigned to anneal more proximally to the STR core repeat region than standard STR primers, yielding small amplicons also known as miniSTRs. Using the miniSTR strategy, more alleles can be detected in degraded DNA samples than using the standard STR primers.

20.5.2 Low Copy Number DNA Testing

Low copy number (LCN) DNA analysis involves the testing of very small amounts of DNA (<100 pg) in a sample. LCN DNA analysis is often needed for samples derived from evidence such as fingerprints and tools and weapons handled by perpetrators. STR analysis of extremely low levels of human DNA can be achieved by increasing the number of PCR cycles (e.g., increasing from 28 to 34 cycles) to improve the yield of amplicons, thus improving the sensitivity of the analysis.

However, this approach also increases the appearance of artifacts that can make interpretation difficult. For instance, the occurrence of allele dropout, heterozygote imbalance, and stuttering is frequently observed in LCN DNA analysis. Additionally, allele drop-in can arise from contamination. The phenomenon of allele drop-in is usually not reproducible. In an LCN DNA analysis, genotypes can be determined if identical alleles can be detected from two independent amplification reactions.

20.5.3 Mixtures

Samples of DNA from two or more contributors are commonly encountered in forensic cases such as sexual assaults in which the evidence recovered from a victim is mixed with a suspect's bodily fluids (Figure 20.22). The interpretation of DNA profiles of mixed stains is known as *mixture interpretation*, which is described below:

1. *To determine the presence of a mixture*: First, determine whether the source of the DNA in the sample came from one or more individuals by examining the number of alleles at multiple loci. The characteristics listed below usually indicate a mixture:
    a. Severe heterozygote imbalance.
    b. Stutter ratio above 0.15.
    c. Presence of three or more alleles per locus at multiple loci.



Figure 20.21 DNA profile (AmpFlSTR® Profiler Plus® PCR Amplification Kit; Applied Biosystems) of the degraded sample. (© Richard C. Li.)

Additionally, caution should be taken to distinguish the presence of a mixture and various artifacts such as stutters and nontemplate adenylation.

2. *To determine the genotypes of all alleles and to identify the number of contributors*: Note that the maximum number of alleles at any given locus is two per individual. In the case of homozygous or allele overlap, the number of alleles observed can be less than two per individual.
3. *To estimate the ratios of the contributions*: Determine the relative ratios of the contributions to the mixture made by each individual by comparing the peak areas or



Figure 20.22 DNA profiles of mixed bodily fluids. (a) DNA profile of mixed stains from evidence, (b) DNA profile of the victim. (© Richard C. Li.)



Figure 20.22 (Continued) (c) DNA profile of the suspect.

amplitudes. Amelogenin, a sex-typing marker, is useful in determining the genders of DNA contributors.

4. *To consider all possible genotype combinations*: This may be done by pair-wise comparisons to determine the allele combinations that belong to the minor contributor and those that belong to the major contributor.
5. *To compare reference samples*: The final step is to compare the genotype profiles with the genotypes of reference samples from a suspect and victim. If the DNA profile of the suspect's reference sample matches a major or minor component of the mixture, the suspect cannot be excluded as a contributor.

Detailed guidance for basic steps in mixture interpretation is provided in a number of published guidelines. For example, the Interpretation Guidelines for Autosomal STR Typing by Forensic DNA Testing Laboratories was recently established by the Scientific Working Group on DNA Analysis Methods (SWGDAM), which provides direction on DNA profiling and mixture interpretation. Additionally, guidance for the statistical evaluations of the mixture analysis results is also provided.

Bibliography

STR Profiling

Andersen, J., et al., Report on the third EDNAP collaborative STR exercise. *Forensic Sci Int*, 1996, **78**(2): 83–93.

Anker, R., T. Steinbrueck, and H. Donis-Keller, Tetranucleotide repeat polymorphism at the human thyroid peroxidase (hTPO) locus. *Hum Mol Genet*, 1992, **1**(2): 137.

Asamura, H., et al., MiniSTR multiplex systems based on non-CODIS loci for analysis of degraded DNA samples. *Forensic Sci Int*, 2007, **173**(1): 7–15.

Asamura, H., et al., MiniY-STR quadruplex systems with short amplicon lengths for analysis of degraded DNA samples. *Forensic Sci Int Genet*, 2007, **1**(1): 56–61.

Aznar, J.M., et al., I-DNASE21 system: Development and SWGDAM validation of a new STR 21-plex reaction. *Forensic Sci Int Genet*, 2014, **8**(1): 10–19.

Balding, D.J., Evaluation of mixed-source, low-template DNA profiles in forensic science. *Proc Natl Acad Sci U S A*, 2013, **110**(30): 12241–12246.

Ballantyne, J., E.K. Hanson, and M.W. Perlin, DNA mixture genotyping by probabilistic computer interpretation of binomially-sampled laser captured cell populations: Combining quantitative data for greater identification information. *Sci Justice*, 2013, **53**(2): 103–114.

Bar, W., et al., DNA recommendations. Further report of the DNA commission of the ISFH regarding the use of short tandem repeat systems. International Society for Forensic Haemogenetics. *Int J Legal Med*, 1997, **110**(4): 175–176.

Barbaro, A., et al., Casework application of a stand-alone pentaplex assay of extended-ESS STRs. *Leg Med (Tokyo)*, 2013, **15**(4): 217–221.

Barber, M.D. and B.H. Parkin, Sequence analysis and allelic designation of the two short tandem repeat loci D18S51 and D8S1179. *Int J Legal Med*, 1996, **109**(2): 62–65.

Barber, M.D., B.J. McKeown, and B.H. Parkin, Structural variation in the alleles of a short tandem repeat system at the human alpha fibrinogen locus. *Int J Legal Med*, 1996, **108**(4): 180–185.

Becker, D., et al., New alleles and mutational events at 14 STR loci from different German populations. *Forensic Sci Int Genet*, 2007, **1**(3–4): 232–237.

Benschop, C., H. Haned, and T. Sijen, Consensus and pool profiles to assist in the analysis and interpretation of complex low template DNA mixtures. *Int J Legal Med*, 2013, **127**(1): 11–23.

Benschop, C.C., et al., Assessment of mock cases involving complex low template DNA mixtures: A descriptive study. *Forensic Sci Int Genet*, 2012, **6**(6): 697–707.

Betz, T., et al., "Paterniplex", a highly discriminative decaplex STR multiplex tailored for investigating special problems in paternity testing. *Electrophoresis*, 2007, **28**(21): 3868–3874.

Bill, M., et al., PENDULUM—A guideline-based approach to the interpretation of STR mixtures. *Forensic Sci Int*, 2005, **148**(2–3): 181–189.

Bornman, D.M., et al., Short-read, high-throughput sequencing technology for STR genotyping. *Biotechniques*, 2012, 10.2144/000113857: 1–6.

Brinkmann, B., E. Meyer, and A. Junge, Complex mutational events at the HumD21S11 locus. *Hum Genet*, 1996, **98**(1): 60–64.

Brookes, C., et al., Characterising stutter in forensic STR multiplexes. *Forensic Sci Int Genet*, 2012, **6**(1): 58–63.

Budimlija, Z.M. and T.A. Caragine, Interpretation guidelines for multilocus STR forensic profiles from low template DNA samples. *Methods Mol Biol*, 2012, **830**: 199–211.

Budowle, B., et al., Validation studies of the CTT STR multiplex system. *J Forensic Sci*, 1997, **42**(4): 701–707.

Budowle, B., et al., *DNA Typing Protocols: Molecular Biology and Forensic Analysis*, 2000. Natick, MA: Eaton Publishing.

Budowle, B., et al., STR primer concordance study. *Forensic Sci Int*, 2001, **124**(1): 47–54.

Buse, E.L., et al., Performance evaluation of two multiplexes used in fluorescent short tandem repeat DNA analysis. *J Forensic Sci*, 2003, **48**(2): 348–357.

Butler, J.M., Constructing STR multiplex assays. *Methods Mol Biol*, 2005, **297**: 53–66.

Butler, J.M., Genetics and genomics of core short tandem repeat loci used in human identity testing. *J Forensic Sci*, 2006, **51**(2): 253–265.

Butler, J.M., Y. Shen, and B.R. McCord, The development of reduced size STR amplicons as tools for analysis of degraded DNA. *J Forensic Sci*, 2003, **48**(5): 1054–1064.

Caragine, T., et al., Validation of testing and interpretation protocols for low template DNA samples using AmpFlSTR Identifiler. *Croat Med J*, 2009, **50**(3): 250–267.

Castella, V., J. Gervaix, and D. Hall, DIP-STR: Highly sensitive markers for the analysis of unbalanced genomic mixtures. *Hum Mutat*, 2013, **34**(4): 644–654.

Chakraborty, R., et al., The utility of short tandem repeat loci beyond human identification: Implications for development of new DNA typing systems. *Electrophoresis*, 1999, **20**(8): 1682–1696.

Chen, P.Y., et al., Substitution mutation induced migration anomaly of a D10S2325 allele on capillary electrophoresis. *Int J Legal Med*, 2013, **127**(2): 363–368.

Clayton, T.M., et al., A genetic basis for anomalous band patterns encountered during DNA STR profiling. *J Forensic Sci*, 2004, **49**(6): 1207–1214.

Coble, M.D. and J.M. Butler, Characterization of new miniSTR loci to aid analysis of degraded DNA. *J Forensic Sci*, 2005, **50**(1): 43–53.

Coble, M.D., Capillary electrophoresis of miniSTR markers to genotype highly degraded DNA samples. *Methods Mol Biol*, 2012, **830**: 31–42.

Collins, J.R., et al., An exhaustive DNA micro-satellite map of the human genome using high performance computing. *Genomics*, 2003, **82**(1): 10–19.

Collins, P.J., et al., Developmental validation of a single-tube amplification of the 13 CODIS STR loci, D2S1338, D19S433, and amelogenin: The AmpFlSTR Identifiler PCR amplification kit. *J Forensic Sci*, 2004, **49**(6): 1265–1277.

Cotton, E.A., et al., Validation of the AMPFlSTR SGM plus system for use in forensic casework. *Forensic Sci Int*, 2000, **112**(2–3): 151–161.

Cowell, R.G., Validation of an STR peak area model. *Forensic Sci Int Genet*, 2009, **3**(3): 193–199.

Cowell, R.G., S.L. Lauritzen, and J. Mortera, Identification and separation of DNA mixtures using peak area information. *Forensic Sci Int*, 2007, **166**(1): 28–34.

Cowen, S., et al., An investigation of the robustness of the consensus method of interpreting low-template DNA profiles. *Forensic Sci Int Genet*, 2011, **5**(5): 400–406.

Crouse, C.A. and J. Schumm, Investigation of species specificity using nine PCR-based human STR systems. *J Forensic Sci*, 1995, **40**(6): 952–956.

Cupples, C.M., et al., STR profiles from DNA samples with "undetected" or low quantifiler results. *J Forensic Sci*, 2009, **54**(1): 103–107.

Dauber, E.M., et al., Germline mutations of STR-alleles include multi-step mutations as defined by sequencing of repeat and flanking regions. *Forensic Sci Int Genet*, 2012, **6**(3): 381–386.

Davis, C., et al., Variants observed for STR locus SE33: A concordance study. *Forensic Sci Int Genet*, 2012, **6**(4): 494–497.

Debernardi, A., et al., One year variability of peak heights, heterozygous balance and inter-locus balance for the DNA positive control of AmpFlSTR© Identifiler© STR kit. *Forensic Sci Int Genet*, 2011, **5**(1): 43–49.

Dib, C., et al., A comprehensive genetic map of the human genome based on 5,264 microsatellites. *Nature*, 1996, **380**(6570): 152–154.

Divne, A.M., H. Edlund, and M. Allen, Forensic analysis of autosomal STR markers using pyrosequencing. *Forensic Sci Int Genet*, 2010, **4**(2): 122–129.

Drabek, J., et al., Concordance study between Miniplex assays and a commercial STR typing kit. *J Forensic Sci*, 2004, **49**(4): 859–860.

Duewer, D.L., et al., NIST mixed stain study 3: Signal intensity balance in commercial short tandem repeat multiplexes. *Anal Chem*, 2004, **76**(23): 6928–6934.

Edwards, A., et al., DNA typing and genetic mapping with trimeric and tetrameric tandem repeats. *Am J Hum Genet*, 1991, **49**(4): 746–756.

Edwards, A., et al., Genetic variation at five trimeric and tetrameric tandem repeat loci in four human population groups. *Genomics*, 1992, **12**(2): 241–253.

Ellegren, H., Microsatellites: Simple sequences with complex evolution. *Nat Rev Genet*, 2004, **5**(6): 435–445.

Ensenberger, M.G., et al., Developmental validation of the PowerPlex 16 HS system: An improved 16-locus fluorescent STR multiplex. *Forensic Sci Int Genet*, 2010, **4**(4): 257–264.

Ensenberger, M.G., et al., Developmental validation of the PowerPlex$^{(®)}$ 21 system. *Forensic Sci Int Genet*, 2014, **9**: 169–178.

Flores, S., et al., Internal validation of the GlobalFiler express PCR amplification kit for the direct amplification of reference DNA samples on a high-throughput automated workflow. *Forensic Sci Int Genet*, 2014, **10C**: 33–39.

Fordyce, S.L., et al., High-throughput sequencing of core STR loci for forensic genetic investigations using the Roche Genome Sequencer FLX platform. *Biotechniques*, 2011, **51**(2): 127–133.

Fregeau, C.J. and R.M. Fourney, DNA typing with fluorescently tagged short tandem repeats: A sensitive and accurate approach to human identification. *Biotechniques*, 1993, **15**(1): 100–119.

Fregeau, C.J., K.L. Bowen, and R.M. Fourney, Validation of highly polymorphic fluorescent multiplex short tandem repeat systems using two generations of DNA sequencers. *J Forensic Sci*, 1999, **44**(1): 133–166.

Fregeau, C.J., et al., AmpFlSTR Profiler Plus short tandem repeat DNA analysis of casework samples, mixture samples, and nonhuman DNA samples amplified under reduced PCR volume conditions (25 microL). *J Forensic Sci*, 2003, **48**(5): 1014–1034.

Ge, J., A. Eisenberg, and B. Budowle, Developing criteria and data to determine best options for expanding the core CODIS loci. *Investig Genet*, 2012, **3**: 1.

Gibb, A.J., et al., Characterisation of forward stutter in the AmpFlSTR SGM Plus PCR. *Sci Justice*, 2009, **49**(1): 24–31.

Gil, A., et al., Linkage between HPRTB STR alleles and Lesch-Nyhan syndrome inside a family: Implications in forensic casework. *Forensic Sci Int Genet*, 2013, **7**(1): e5–e6.

Gilder, J.R., et al., Run-specific limits of detection and quantitation for STR-based DNA testing. *J Forensic Sci*, 2007, **52**(1): 97–101.

Gilder, J.R., et al., Magnitude-dependent variation in peak height balance at heterozygous STR loci. *Int J Legal Med*, 2011, **125**(1): 87–94.

Gill, P. and J. Buckleton, Commentary on: Budowle B, Onorato AJ, Callaghan TF, Della Manna A, Gross AM, Guerrieri RA, Luttman JC, McClure DL. Mixture interpretation: Defining the relevant features for guidelines for the assessment of mixed DNA profiles in forensic casework. J Forensic Sci 2009;54(4):810–821. *J Forensic Sci*, 2010, **55**(1): 265–268; author reply 269–272.

Gill, P., A. Kirkham, and J. Curran, LoComatioN: A software tool for the analysis of low copy number DNA profiles. *Forensic Sci Int*, 2007, **166**(2–3): 128–138.

Gill, P., et al., The evolution of DNA databases—Recommendations for new European STR loci. *Forensic Sci Int*, 2006, **156**(2–3): 242–244.

Gill, P., et al., Interpretation of complex DNA profiles using empirical models and a method to measure their robustness. *Forensic Sci Int Genet*, 2008, **2**(2): 91–103.

Gill, P., et al., DNA commission of the International Society of Forensic Genetics: Recommendations on the evaluation of STR typing results that may include drop-out and/or drop-in using probabilistic methods. *Forensic Sci Int Genet*, 2012, **6**(6): 679–688.

Gill, P., Role of short tandem repeat DNA in forensic casework in the UK—Past, present, and future perspectives. *Biotechniques*, 2002, **32**(2): 366–368, 370, 372, passim.

Goodwin, W. and C. Peel, Theoretical value of the recommended expanded European standard set of STR loci for the identification of human remains. *Med Sci Law*, 2012, **52**(3): 162–168.

Graydon, M., F. Cholette, and L.K. Ng, Inferring ethnicity using 15 autosomal STR loci—Comparisons among populations of similar and distinctly different physical traits. *Forensic Sci Int Genet*, 2009, **3**(4): 251–254.

Green, R.L., et al., Developmental validation of the AmpFlSTR® NGM SElect PCR amplification kit: A next-generation STR multiplex with the SE33 locus. *Forensic Sci Int Genet*, 2013, **7**(1): 41–51.

Greenspoon, S.A., et al., Validation of the PowerPlex 1.1 loci for use in human identification. *J Forensic Sci*, 2000, **45**(3): 677–683.

Greenspoon, S.A., et al., Validation and implementation of the PowerPlex 16 BIO System STR multiplex for forensic casework. *J Forensic Sci*, 2004, **49**(1): 71–80.

Griffiths, R.A., et al., New reference allelic ladders to improve allelic designation in a multiplex STR system. *Int J Legal Med*, 1998, **111**(5): 267–272.

Guo, F., et al., Development of a 24-locus multiplex system to incorporate the core loci in the combined DNA index system (CODIS) and the European standard set (ESS). *Forensic Sci Int Genet*, 2014, **8**(1): 44–54.

Hammond, H.A., et al., Evaluation of 13 short tandem repeat loci for use in personal identification applications. *Am J Hum Genet*, 1994, **55**(1): 175–189.

Haned, H., et al., Estimating drop-out probabilities in forensic DNA samples: A simulation approach to evaluate different models. *Forensic Sci Int Genet*, 2011, **5**(5): 525–531.

Harder, M., et al., STR-typing of ancient skeletal remains: Which multiplex-PCR kit is the best? *Croat Med J*, 2012, **53**(5): 416–422.

Hares, D.R., Addendum to expanding the CODIS core loci in the United States. *Forensic Sci Int Genet*, 2012, **6**(5): e135.

Hares, D.R., Expanding the CODIS core loci in the United States. *Forensic Sci Int Genet*, 2012, **6**(1): e52–e54.

Heinrich, M., et al., Allelic drop-out in the STR system ACTBP2 (SE33) as a result of mutations in the primer binding region. *Int J Legal Med*, 2004, **118**(6): 361–363.

Hering, S., J. Edelmann, and J. Dressler, Sequence variations in the primer binding regions of the highly polymorphic STR system SE33. *Int J Legal Med*, 2002, **116**(6): 365–367.

Hering, S., et al., Complex variability of intron 40 of the von Willebrand factor (vWF) gene. *Int J Legal Med*, 2008, **122**(1): 67–71.

Hill, C.R., Capillary electrophoresis and 5-channel LIF detection of a 26plex autosomal STR assay for human identification. *Methods Mol Biol*, 2012, **830**: 17–29.

Hill, C.R., et al., Concordance study between the AmpFlSTR MiniFiler PCR amplification kit and conventional STR typing kits. *J Forensic Sci*, 2007, **52**(4): 870–873.

Hill, C.R., et al., Characterization of 26 miniSTR loci for improved analysis of degraded DNA samples. *J Forensic Sci*, 2008, **53**(1): 73–80.

Holland, M.M. and W. Parson, GeneMarker® HID: A reliable software tool for the analysis of forensic STR data. *J Forensic Sci*, 2011, **56**(1): 29–35.

Holt, C.L., et al., TWGDAM validation of AmpFlSTR PCR amplification kits for forensic DNA casework. *J Forensic Sci*, 2002, **47**(1): 66–96.

Huang, Y.M., et al., Assessment of application value of 19 autosomal short tandem repeat loci of GoldenEye 20A kit in forensic paternity testing. *Int J Legal Med*, 2013, **127**(3): 587–590.

Irwin, J.A., et al., Application of low copy number STR typing to the identification of aged, degraded skeletal remains. *J Forensic Sci*, 2007, **52**(6): 1322–1327.

Jamieson, A., et al., Two-, three-, and four-person mixtures in forensic casework: Difficulties and questions. *Croat Med J*, 2011, **52**(5): 653–654; author reply 654–656.

Jiang, X., et al., Development of a 20-locus fluorescent multiplex system as a valuable tool for national DNA database. *Forensic Sci Int Genet*, 2013, **7**(2): 279–289.

Jobling, M.A., In the name of the father: Surnames and genetics. *Trends Genet*, 2001, **17**(6): 353–357.

Junge, A., et al., Validation of the multiplex kit genRESMPX-2 for forensic casework analysis. *Int J Legal Med*, 2003, **117**(6): 317–325.

Kadash, K., et al., Validation study of the TrueAllele automated data review system. *J Forensic Sci*, 2004, **49**(4): 660–667.

Katsanis, S.H. and J.K. Wagner, Characterization of the standard and recommended CODIS markers. *J Forensic Sci*, 2013, **58**(Suppl 1): S169–S172.

Kimpton, C., A. Walton, and P. Gill, A further tetranucleotide repeat polymorphism in the vWF gene. *Hum Mol Genet*, 1992, **1**(4): 287.

Kimpton, C.P., et al., Automated DNA profiling employing multiplex amplification of short tandem repeat loci. *PCR Methods Appl*, 1993, **3**(1): 13–22.

Kimpton, C., et al., Evaluation of an automated DNA profiling system employing multiplex amplification of four tetrameric STR loci. *Int J Legal Med*, 1994, **106**(6): 302–311.

Kline, M.C., et al., STR sequence analysis for characterizing normal, variant, and null alleles. *Forensic Sci Int Genet*, 2011, **5**(4): 329–332.

Konarzewska, M., et al., Population data and sequence analysis of a "new" microsatellite locus HumHUU (D16S3433). *Forensic Sci Int Genet*, 2010, **4**(5): e143–e144.

Krenke, B.E., et al., Validation of a 16-locus fluorescent multiplex system. *J Forensic Sci*, 2002, **47**(4): 773–785.

Laberke, P.J., et al., Method to predict the chance of developing a male profile out of mixtures of male and female DNA. *Int J Legal Med*, 2012, **126**(1): 157–160.

Laird, R., P.M. Schneider, and S. Gaudieri, Forensic STRs as potential disease markers: A study of VWA and von Willebrand's disease. *Forensic Sci Int Genet*, 2007, **1**(3–4): 253–261.

Lareu, M.V., et al., A highly variable STR at the D12S391 locus. *Int J Legal Med*, 1996, **109**(3): 134–138.

Laurin, N., A. DeMoors, and C. Fregeau, Performance of Identifiler Direct and PowerPlex 16 HS on the applied biosystems 3730 DNA analyzer for processing biological samples archived on FTA cards. *Forensic Sci Int Genet*, 2012, **6**(5): 621–629.

Leclair, B., et al., Systematic analysis of stutter percentages and allele peak height and peak area ratios at heterozygous STR loci for forensic casework and database samples. *J Forensic Sci*, 2004, **49**(5): 968–980.

Lederer, T., et al., Characterization of two unusual allele variants at the STR locus ACTBP2 (SE33). *Forensic Sci Med Pathol*, 2008, **4**(3): 164–166.

Leibelt, C., et al., Identification of a D8S1179 primer binding site mutation and the validation of a primer designed to recover null alleles. *Forensic Sci Int*, 2003, **133**(3): 220–227.

Levedakou, E.N., et al., Characterization and validation studies of powerPlex 2.1, a nine-locus short tandem repeat (STR) multiplex system and penta D monoplex. *J Forensic Sci*, 2002, **47**(4): 757–772.

Li, H., et al., Three tetranucleotide polymorphisms for loci: D3S1352; D3S1358; D3S1359. *Hum Mol Genet*, 1993, **2**(8): 1327.

Lohmueller, K.E., Graydon et al. provide no new evidence that forensic STR loci are functional. *Forensic Sci Int Genet*, 2010, **4**(4): 273–274.

Luce, C., et al., Validation of the AmpFlSTR MiniFiler PCR amplification kit for use in forensic casework. *J Forensic Sci*, 2009, **54**(5): 1046–1054.

Lucy, D., et al., The probability of achieving full allelic representation for LCN-STR profiling of haploid cells. *Sci Justice*, 2007, **47**(4): 168–171.

Lygo, J.E., et al., The validation of short tandem repeat (STR) loci for use in forensic casework. *Int J Legal Med*, 1994, **107**(2): 77–89.

Manabe, S., et al., Mixture interpretation: Experimental and simulated reevaluation of qualitative analysis. *Leg Med (Tokyo)*, 2013, **15**(2): 66–71.

Mardini, A.C., et al., Mutation rate estimates for 13 STR loci in a large population from Rio Grande do Sul, Southern Brazil. *Int J Legal Med*, 2013, **127**(1): 45–47.

Margolis-Nunno, H., et al., A new allele of the short tandem repeat (STR) locus, CSF1PO. *J Forensic Sci*, 2001, **46**(6): 1480–1483.

Martinez-Gonzalez, L.J., et al., Intentional mixed buccal cell reference sample in a paternity case. *J Forensic Sci*, 2007, **52**(2): 397–399.

Masibay, A., T.J. Mozer, and C. Sprecher, Promega corporation reveals primer sequences in its testing kits. *J Forensic Sci*, 2000, **45**(6): 1360–1362.

Mills, K.A., D. Even, and J.C. Murray, Tetranucleotide repeat polymorphism at the human alpha fibrinogen locus (FGA). *Hum Mol Genet*, 1992, **1**(9): 779.

Miozzo, M.C., et al., Characterization of the variant allele 9.2 of Penta D locus. *J Forensic Sci*, 2007, **52**(5): 1073–1076.

Mitchell, A.A., et al., Validation of a DNA mixture statistics tool incorporating allelic drop-out and drop-in. *Forensic Sci Int Genet*, 2012, **6**(6): 749–761.

Moller, A., E. Meyer, and B. Brinkmann, Different types of structural variation in STRs: HumFES/FPS, HumVWA and HumD21S11. *Int J Legal Med*, 1994, **106**(6): 319–323.

Moretti, T.R., et al., Validation of short tandem repeats (STRs) for forensic usage: Performance testing of fluorescent multiplex STR systems and analysis of authentic and simulated forensic samples. *J Forensic Sci*, 2001, **46**(3): 647–660.

Mulero, J.J., et al., Development and validation of the AmpFlSTR MiniFiler PCR amplification kit: A MiniSTR multiplex for the analysis of degraded and/or PCR inhibited DNA. *J Forensic Sci*, 2008, **53**(4): 838–852.

Muller, K., et al., Q8—A short amplicon multiplex including the German DNA database systems. *Forensic Sci Int Genet*, 2007, **1**(2): 205–207.

Muller, K., et al., Validation of the short amplicon multiplex q8 including the German DNA database systems. *J Forensic Sci*, 2009, **54**(4): 862–865.

Muller, K., et al., Casework testing of the multiplex kits AmpFlSTR SEfiler Plus PCR amplification kit (AB), PowerPlex S5 system (Promega) and AmpFlSTR MiniFiler PCR amplification kit (AB). *Forensic Sci Int Genet*, 2010, **4**(3): 200–205.

Narkuti, V., et al., Microsatellite mutation in the maternally/paternally transmitted D18S51 locus: Two cases of allele mismatch in the child. *Clin Chim Acta*, 2007, **381**(2): 171–175.

Narkuti, V., et al., Mother-child double incompatibility at vWA and D5S818 loci in paternity testing. *Clin Chem Lab Med*, 2007, **45**(10): 1288–1291.

Narkuti, V., et al., Single and double incompatibility at vWA and D8S1179/D21S11 loci between mother and child: Implications in kinship analysis. *Clin Chim Acta*, 2008, **395**(1–2): 162–165.

Nelson, M.S., et al., Detection of a primer-binding site polymorphism for the STR locus D16S539 using the Powerplex 1.1 system and validation of a degenerate primer to correct for the polymorphism. *J Forensic Sci*, 2002, **47**(2): 345–349.

Odriozola, A., et al., Development and validation of I-DNA1: A 15-Loci multiplex system for identity testing. *Int J Legal Med*, 2011, **125**(5): 685–694.

Odriozola, A., et al., Development and validation for identity testing of I-DNADuo, a combination of I-DNA1 and a new multiplex system, I-DNA2. *Int J Legal Med*, 2012, **126**(1): 167–172.

Odriozola, A., et al., Recent advances and considerations for the future in forensic analysis of degraded DNA by autosomic miniSTR multiplex genotyping. *Recent Pat DNA Gene Seq*, 2011, **5**(2): 110–116.

Oh, C.S., et al., Autosomal short tandem repeat analysis of ancient DNA by coupled use of mini- and conventional STR kits. *J Forensic Sci*, 2012, **57**(3): 820–825.

Oostdik, K., et al., Developmental validation of the PowerPlex® 18D system, a rapid STR multiplex for analysis of reference samples. *Forensic Sci Int Genet*, 2013, **7**(1): 129–135.

Opel, K.L., et al., The application of miniplex primer sets in the analysis of degraded DNA from human skeletal remains. *J Forensic Sci*, 2006, **51**(2): 351–356.

Opel, K.L., et al., Developmental validation of reduced-size STR miniplex primer sets. *J Forensic Sci*, 2007, **52**(6): 1263–1271.

Park, H., et al., Detection of very large off-ladder alleles at the PentaE locus in a 15 locus autosomal STR database of 199 Korean individuals. *Forensic Sci Int Genet*, 2012, **6**(6): e189–e191.

Parsons, T.J., et al., Application of novel "mini-amplicon" STR multiplexes to high volume casework on degraded skeletal remains. *Forensic Sci Int Genet*, 2007, **1**(2): 175–179.

Pascali, V.L. and S. Merigioli, Joint Bayesian analysis of forensic mixtures. *Forensic Sci Int Genet*, 2012, **6**(6): 735–748.

Perez, J., et al., Estimating the number of contributors to two-, three-, and four-person mixtures containing DNA in high template and low template amounts. *Croat Med J*, 2011, **52**(3): 314–326.

Perlin, M.W., et al., Validating TrueAllele® DNA mixture interpretation. *J Forensic Sci*, 2011, **56**(6): 1430–1447.

Perlin, M.W., J.L. Belrose, and B.W. Duceman, New York State TrueAllele® casework validation study. *J Forensic Sci*, 2013, **58**(6): 1458–1466.

Perlin, M.W., et al., TrueAllele casework on Virginia DNA mixture evidence: Computer and manual interpretation in 72 reported criminal cases. *PLoS One*, 2014, **9**(3): e92837.

Petricevic, S., et al., Validation and development of interpretation guidelines for low copy number (LCN) DNA profiling in New Zealand using the AmpFlSTR SGM Plus multiplex. *Forensic Sci Int Genet*, 2010, **4**(5): 305–310.

Pfeifer, C.M., et al., Comparison of different interpretation strategies for low template DNA mixtures. *Forensic Sci Int Genet*, 2012, **6**(6): 716–722.

Phillips, C., et al., Development of a novel forensic STR multiplex for ancestry analysis and extended identity testing. *Electrophoresis*, 2013, **34**(8): 1151–1162.

Picanco, J.B., et al., Tri-allelic pattern at the TPOX locus: A familial study. *Gene*, 2014, **535**(2): 353–358.

Pitterl, F., et al., Increasing the discrimination power of forensic STR testing by employing high-performance mass spectrometry, as illustrated in indigenous South African and Central Asian populations. *Int J Legal Med*, 2010, **124**(6): 551–558.

Pitterl, F., et al., The next generation of DNA profiling—STR typing by multiplexed PCR—Ion-pair RP LC-ESI time-of-flight MS. *Electrophoresis*, 2008, **29**(23): 4739–4750.

Planz, J.V., et al., Automated analysis of sequence polymorphism in STR alleles by PCR and direct electrospray ionization mass spectrometry. *Forensic Sci Int Genet*, 2012, **6**(5): 594–606.

Poetsch, M., et al., Powerplex® ES versus Powerplex® S5—Casework testing of the new screening kit. *Forensic Sci Int Genet*, 2011, **5**(1): 57–63.

Poltl, R., C. Luckenbach, and H. Ritter, The short tandem repeat locus D3S1359. *Forensic Sci Int*, 1998, **95**(2): 163–168.

Poltl, R., et al., Typing of the short tandem repeat D8S347 locus with different fluorescence markers. *Electrophoresis*, 1997, **18**(15): 2871–2873.

Polymeropoulos, M.H., et al., Tetranucleotide repeat polymorphism at the human tyrosine hydroxylase gene (TH). *Nucleic Acids Res*, 1991, **19**(13): 3753.

Puch-Solis, R., et al., Evaluating forensic DNA profiles using peak heights, allowing for multiple donors, allelic dropout and stutters. *Forensic Sci Int Genet*, 2013, **7**(5): 555–563.

Puers, C., et al., Identification of repeat sequence heterogeneity at the polymorphic short tandem repeat locus HUMTH01[AATG]n and reassignment of alleles in population analysis by using a locus-specific allelic ladder. *Am J Hum Genet*, 1993, **53**(4): 953–958.

Reichenpfader, B., R. Zehner, and M. Klintschar, Characterization of a highly variable short tandem repeat polymorphism at the D2S1242 locus. *Electrophoresis*, 1999, **20**(3): 514–517.

Repnikova, E.A., et al., Characterization of copy number variation in genomic regions containing STR loci using array comparative genomic hybridization. *Forensic Sci Int Genet*, 2013, **7**(5): 475–481.

Ricci, U., et al., A single mutation in the FGA locus responsible for false homozygosities and discrepancies between commercial kits in an unusual paternity test case. *J Forensic Sci*, 2007, **52**(2): 393–396.

Rockenbauer, E., et al., Characterization of mutations and sequence variants in the D21S11 locus by next generation sequencing. *Forensic Sci Int Genet*, 2014, **8**(1): 68–72.

Ruitberg, C.M., D.J. Reeder, and J.M. Butler, STRBase: A short tandem repeat DNA database for the human identity testing community. *Nucleic Acids Res*, 2001, **29**(1): 320–322.

Schilz, F., S. Hummel, and B. Herrmann, Design of a multiplex PCR for genotyping 16 short tandem repeats in degraded DNA samples. *Anthropol Anz*, 2004, **62**(4): 369–378.

Schneider, H.R., et al., ACTBP2-nomenclature recommendations of GEDNAP. *Int J Legal Med*, 1998, **111**(2): 97–100.

Schumm, J.W., et al., A 27-locus STR assay to meet all United States and European law enforcement agency standards. *J Forensic Sci*, 2013, **58**(6): 1584–1592.

Seidl, C., et al., Sequence analysis and population data of short tandem repeat polymorphisms at loci D8S639 and D11S488. *Int J Legal Med*, 1999, **112**(6): 355–359.

Sharma, V. and M. Litt, Tetranucleotide repeat polymorphism at the D21S11 locus. *Hum Mol Genet*, 1992, **1**(1): 67.

Slooten, K. and F. Ricciardi, Estimation of mutation probabilities for autosomal STR markers. *Forensic Sci Int Genet*, 2013, **7**(3): 337–344.

Smith, R.N., Accurate size comparison of short tandem repeat alleles amplified by PCR. *Biotechniques*, 1995, **18**(1): 122–128.

Sparkes, R., et al., The validation of a 7-locus multiplex STR test for use in forensic casework. (I). Mixtures, ageing, degradation and species studies. *Int J Legal Med*, 1996, **109**(4): 186–194.

Spathis, R. and J.K. Lum, An updated validation of Promega's PowerPlex 16 system: High throughput databasing under reduced PCR volume conditions on applied biosystem's 96 capillary 3730xl DNA analyzer. *J Forensic Sci*, 2008, **53**(6): 1353–1357.

Sun, H.Y., et al., A paternity case with mutations at three CODIS core STR loci. *Forensic Sci Int Genet*, 2012, **6**(1): e61–e62.

Takayama, T., et al., Identification of a rare mutation in a TH01 primer binding site. *Leg Med (Tokyo)*, 2007, **9**(6): 289–292.

Tomsey, C.S., et al., Comparison of PowerPlex 16, PowerPlex 1.1/2.1, and ABI AmpFiSTR Profiler Plus/COfiler for forensic use. *Croat Med J*, 2001, **42**(3): 239–243.

Tucker, V.C., A.J. Kirkham, and A.J. Hopwood, Forensic validation of the PowerPlex® ESI 16 STR multiplex and comparison of performance with AmpFlSTR® SGM Plus®. *Int J Legal Med*, 2012, **126**(3): 345–356.

Tucker, V.C., et al., Developmental validation of the PowerPlex® ESI 16 and PowerPlex® ESI 17 systems: STR multiplexes for the new European standard. *Forensic Sci Int Genet*, 2011, **5**(5): 436–448.

Tucker, V.C., et al., Developmental validation of the PowerPlex® ESX 16 and PowerPlex® ESX 17 systems. *Forensic Sci Int Genet*, 2012, **6**(1): 124–131.

Tvedebrink, T., et al., Identifying contributors of DNA mixtures by means of quantitative information of STR typing. *J Comput Biol*, 2012, **19**(7): 887–902.

Tvedebrink, T., et al., Performance of two 17 locus forensic identification STR kits-applied biosystems's AmpFlSTR® NGMSElect™ and Promega's PowerPlex® ESI17 kits. *Forensic Sci Int Genet*, 2012, **6**(5): 523–531.

Tvedebrink, T., et al., Statistical model for degraded DNA samples and adjusted probabilities for allelic dropout. *Forensic Sci Int Genet*, 2012, **6**(1): 97–101.

Urquhart, A., C.P. Kimpton, and P. Gill, Sequence variability of the tetranucleotide repeat of the human beta-actin related pseudogene H-beta-Ac-psi-2 (ACTBP2) locus. *Hum Genet*, 1993, **92**(6): 637–638.

Urquhart, A., et al., Variation in short tandem repeat sequences—A survey of twelve microsatellite loci for use as forensic identification markers. *Int J Legal Med*, 1994, **107**(1): 13–20.

Vallone, P.M., C.R. Hill, and J.M. Butler, Demonstration of rapid multiplex PCR amplification involving 16 genetic loci. *Forensic Sci Int Genet*, 2008, **3**(1): 42–45.

Van Neste, C., et al., Forensic STR analysis using massive parallel sequencing. *Forensic Sci Int Genet*, 2012, **6**(6): 810–818.

Vanderheyden, N., et al., Identification and sequence analysis of discordant phenotypes between AmpFlSTR SGM Plus™ and PowerPlex® 16. *Int J Legal Med*, 2007, **121**(4): 297–301.

Voskoboinik, L. and A. Darvasi, Forensic identification of an individual in complex DNA mixtures. *Forensic Sci Int Genet*, 2011, **5**(5): 428–435.

Walsh, P.S., H.A. Erlich, and R. Higuchi, Preferential PCR amplification of alleles: Mechanisms and solutions. *PCR Methods Appl*, 1992, **1**(4): 241–250.

Walsh, P.S., N.J. Fildes, and R. Reynolds, Sequence analysis and characterization of stutter products at the tetranucleotide repeat locus vWA. *Nucleic Acids Res*, 1996, **24**(14): 2807–2812.

Wang, D.Y., et al., Development and validation of the AmpFlSTR® Identifiler® direct PCR amplification kit: A multiplex assay for the direct amplification of single-source samples. *J Forensic Sci*, 2011, **56**(4): 835–845.
Wang, D.Y., et al., Developmental validation of the AmpFlSTR® Identifiler® Plus PCR amplification kit: An established multiplex assay with improved performance. *J Forensic Sci*, 2012, **57**(2): 453–465.
Warshauer, D.H., et al., STRait Razor: A length-based forensic STR allele-calling tool for use with second generation sequencing data. *Forensic Sci Int Genet*, 2013, **7**(4): 409–417.
Weber, J.L. and P.E. May, Abundant class of human DNA polymorphisms which can be typed using the polymerase chain reaction. *Am J Hum Genet*, 1989, **44**(3): 388–396.
Welch, L.A., et al., European Network of Forensic Science Institutes (ENFSI): Evaluation of new commercial STR multiplexes that include the European standard set (ESS) of markers. *Forensic Sci Int Genet*, 2012, **6**(6): 819–826.
Westen, A.A., et al., Assessment of the stochastic threshold, back- and forward stutter filters and low template techniques for NGM. *Forensic Sci Int Genet*, 2012, **6**(6): 708–715.
Westen, A.A., et al., Combining results of forensic STR kits: HDplex validation including allelic association and linkage testing with NGM and Identifiler loci. *Int J Legal Med*, 2012, **126**(5): 781–789.
Wetton, J.H., et al., Analysis and interpretation of mixed profiles generated by 34 cycle SGM Plus(®) amplification. *Forensic Sci Int Genet*, 2011, **5**(5): 376–380.
Wiegand, P., et al., D18S535, D1S1656 and D10S2325: Three efficient short tandem repeats for forensic genetics. *Int J Legal Med*, 1999, **112**(6): 360–363.
Wiegand, P., et al., Forensic validation of the STR systems SE 33 and TC 11. *Int J Legal Med*, 1993, **105**(6): 315–320.
Yeung, S.H., et al., Rapid and high-throughput forensic short tandem repeat typing using a 96-lane microfabricated capillary array electrophoresis microdevice. *J Forensic Sci*, 2006, **51**(4): 740–747.
Yoshida, K., et al., Efficacy of extended kinship analyses utilizing commercial STR kit in establishing personal identification. *Leg Med (Tokyo)*, 2011, **13**(1): 12–15.
Yuasa, I., et al., A hypervariable STR polymorphism in the CFI gene: Mutation rate and no linkage disequilibrium with FGA. *Leg Med (Tokyo)*, 2013, **15**(3): 161–163.
Zhang, S., et al., A new multiplex assay of 17 autosomal STRs and amelogenin for forensic application. *PLoS One*, 2013, **8**(2): e57471.
Zhou, Y., et al., DNA profiling in blood, buccal swabs and hair follicles of patients after allogeneic peripheral blood stem cells transplantation. *Leg Med (Tokyo)*, 2011, **13**(1): 47–51.
Zupanic Pajnic, I., et al., Highly efficient nuclear DNA typing of the World War II skeletal remains using three new autosomal short tandem repeat amplification kits with the extended European standard set of loci. *Croat Med J*, 2012, **53**(1): 17–23.

Genetic Population Data

Abrahams, Z., et al., Allele frequencies of six non-CODIS miniSTR loci (D1S1627, D3S4529, D5S2500, D6S1017, D8S1115 and D9S2157) in three South African populations. *Forensic Sci Int Genet*, 2011, **5**(4): 354–355.
Abu Halima, M.S., L.P. Bernal, and F.A. Sharif, Genetic variation of 15 autosomal short tandem repeat (STR) loci in the Palestinian population of Gaza Strip. *Leg Med (Tokyo)*, 2009, **11**(4): 203–204.
Aguiar, V.R., et al., Updated Brazilian STR allele frequency data using over 100,000 individuals: An analysis of CSF1PO, D3S1358, D5S818, D7S820, D8S1179, D13S317, D16S539, D18S51, D21S11, FGA, Penta D, Penta E, TH01, TPOX and vWA loci. *Forensic Sci Int Genet*, 2012, **6**(4): 504–509.
Akhteruzzaman, S., et al., Forensic evaluation of 11 non-standard STR loci in Bangladeshi population. *Leg Med (Tokyo)*, 2013, **15**(2): 106–108.
Al-Enizi, M., et al., Population genetic analyses of 15 STR loci from seven forensically-relevant populations residing in the state of Kuwait. *Forensic Sci Int Genet*, 2013, **7**(4): e106–e107.
Alenizi, M., et al., STR data for the AmpFlSTR Identifiler loci in Kuwaiti population. *Leg Med (Tokyo)*, 2008, **10**(6): 321–325.
Alenizi, M.A., et al., Concordance between the AmpFlSTR MiniFiler and AmpFlSTR Identifiler PCR amplification kits in the Kuwaiti population. *J Forensic Sci*, 2009, **54**(2): 350–352.
Ali, I., et al., Allele frequencies of 15 STR loci using AmpF/STR Identifiler kit in the Maldivian population. *Forensic Sci Int Genet*, 2012, **6**(5): e136.

Andreassen, R., S. Jakobsen, and B. Mevaag, Norwegian population data for the 10 autosomal STR loci in the AmpFlSTR® SGM Plus™ system. *Forensic Sci Int*, 2007, **170**(1): 59–61.

Andreassen, R., et al., Icelandic population data for the STR loci in the AmpFlSTR SGM Plus system and the PowerPlex Y-system. *Forensic Sci Int Genet*, 2010, **4**(4): e101–e103.

Andreini, E., et al., Allele frequencies for nine STR loci (D3S1358, vWA, FGA, D8S1179, D21S11, D18S51, D5S818, D13S317, D7S820) in the Italian population. *Forensic Sci Int*, 2007, **168**(1): e13–e16.

Aranda, X.G., et al., Genetic composition of six miniSTR in a Brazilian Mulatto sample population. *J Forensic Leg Med*, 2011, **18**(4): 184–186.

Asamura, H., M. Ota, and H. Fukushima, Population data on 10 non-CODIS STR loci in Japanese population using a newly developed multiplex PCR system. *J Forensic Leg Med*, 2008, **15**(8): 519–523.

Bagdonavicius, A., et al., Western Australian sub-population data for the thirteen AmpFiSTR Profiler Plus and COfiler STR loci. *J Forensic Sci*, 2002, **47**(5): 1149–1153.

Barni, F., et al., Allele frequencies of 15 autosomal STR loci in the Iraq population with comparisons to other populations from the middle-eastern region. *Forensic Sci Int*, 2007, **167**(1): 87–92.

Bindu, G.H., R. Trivedi, and V.K. Kashyap, Allele frequency distribution based on 17 STR markers in three major Dravidian linguistic populations of Andhra Pradesh, India. *Forensic Sci Int*, 2007, **170**(1): 76–85.

Borosky, A., L. Catelli, and C. Vullo, Analysis of 17 STR loci in different provinces of Argentina. *Forensic Sci Int Genet*, 2009, **3**(3): e93–e95.

Branham, A., R. Wenk, and F. Chiafari, Allele frequencies of fifteen STR loci in U.S. immigrants from Haiti compared with African Americans and Afro-Caribbeans. *Forensic Sci Int Genet*, 2012, **6**(1): e3–e4.

Bright, J.A., J.S. Buckleton, and C.E. McGovern, Allele frequencies for the four major sub-populations of New Zealand for the 15 Identifiler loci. *Forensic Sci Int Genet*, 2010, **4**(2): e65–e66.

Brisighelli, F., et al., Allele frequencies of fifteen STRs in a representative sample of the Italian population. *Forensic Sci Int Genet*, 2009, **3**(2): e29–e30.

Budowle, B., D.A. Defenbaugh, and K.M. Keys, Genetic variation at nine short tandem repeat loci in Chamorros and Filipinos from Guam. *Leg Med (Tokyo)*, 2000, **2**(1): 26–30.

Budowle, B., et al., Population genetic analyses of the NGM STR loci. *Int J Legal Med*, 2011, **125**(1): 101–109.

Cai, J.F., et al., Population genetics of two STR loci D2S1322 and D2S1356 in a Chinese Han population in Hohhot. *J Forensic Sci*, 2007, **52**(4): 1001.

Camacho, M.V., C. Benito, and A.M. Figueiras, Allelic frequencies of the 15 STR loci included in the AmpFlSTR Identifiler PCR amplification kit in an autochthonous sample from Spain. *Forensic Sci Int*, 2007, **173**(2–3): 241–245.

Cassar, M., C. Farrugia, and C. Vidal, Allele frequencies of 14 STR loci in the population of Malta. *Leg Med (Tokyo)*, 2008, **10**(3): 153–156.

Castro, E.A., et al., Genetic polymorphism and forensic parameters of nine short tandem repeat loci in Ngobe and Embera Amerindians of Panama. *Hum Biol*, 2007, **79**(5): 563–577.

Chang, Y.F., et al., Genetic polymorphism of 17 STR loci in Chinese population from Hunan province in Central South China. *Forensic Sci Int Genet*, 2012, **6**(5): e151–e153.

Chen, J.G., et al., Population genetic data of 15 autosomal STR loci in Uygur ethnic group of China. *Forensic Sci Int Genet*, 2012, **6**(6): e178–e179.

Chouery, E., et al., Population genetic data for 17 STR markers from Lebanon. *Leg Med (Tokyo)*, 2010, **12**(6): 324–326.

Chula, F.G., et al., 15 STR loci frequencies with mutation rates in the population from Rio Grande do Sul, Southern Brazil. *Forensic Sci Int Genet*, 2009, **3**(2): e35–e38.

Chung, U., et al., Population data of nine miniSTR loci in Koreans. *Forensic Sci Int*, 2007, **168**(2–3): e51–e53.

Clark, D., et al., STR data for the AmpFlSTR SGM Plus loci from two South Asian populations. *Leg Med (Tokyo)*, 2009, **11**(2): 97–100.

Cortellini, V., N. Cerri, and A. Verzeletti, Genetic variation at 5 new autosomal short tandem repeat markers (D10S1248, D22S1045, D2S441, D1S1656, D12S391) in a population-based sample from Maghreb region. *Croat Med J*, 2011, **52**(3): 368–371.

Cortellini, V., N. Cerri, and A. Verzeletti, Population data on 5 non-CODIS STR loci (D10S1248, D22S1045, D2S441, D1S1656, D12S391) in a population sample from Brescia county (Northern Italy). *Forensic Sci Int Genet*, 2011, **5**(3): e97–e98.

Coudray, C., et al., Allele frequencies of 15 short tandem repeats (STRs) in three Egyptian populations of different ethnic groups. *Forensic Sci Int*, 2007, **169**(2–3): 260–265.

Coudray, C., et al., Allele frequencies of 15 tetrameric short tandem repeats (STRs) in Andalusians from Huelva (Spain). *Forensic Sci Int*, 2007, **168**(2–3): e21–e24.

Coudray, C., et al., Population genetic data of 15 tetrameric short tandem repeats (STRs) in Berbers from Morocco. *Forensic Sci Int*, 2007, **167**(1): 81–86.

Curic, G., et al., Genetic parameters of five new European standard set STR loci (D10S1248, D22S1045, D2S441, D1S1656, D12S391) in the population of Eastern Croatia. *Croat Med J*, 2012, **53**(5): 409–415.

da Costa Francez, P.A., et al., Allelic frequencies and statistical data obtained from 12 codis STR loci in an admixed population of the Brazilian Amazon. *Genet Mol Biol*, 2011, **34**(1): 35–39.

de Assis Poiares, L., et al., Allele frequencies of 15 STRs in a representative sample of the Brazilian population. *Forensic Sci Int Genet*, 2010, **4**(2): e61–e63.

Demeter, S.J., et al., Genetic variation at 15 polymorphic, autosomal, short tandem repeat loci of two Hungarian populations in Transylvania, Romania. *Croat Med J*, 2010, **51**(6): 515–523.

Deng, Q., et al., Genetic relationships among four minorities in Guangxi revealed by analysis of 15 STRs. *J Genet Genomics*, 2007, **34**(12): 1072–1079.

Deng, Y., et al., Genetic polymorphisms of 15 STR loci of Chinese Dongxiang and Salar ethnic minority living in Qinghai Province of China. *Leg Med (Tokyo)*, 2007, **9**(1): 38–42.

Deng, Y.J., et al., Genetic polymorphism analysis of 15 STR loci in Chinese Hui ethnic group residing in Qinghai province of China. *Mol Biol Rep*, 2011, **38**(4): 2315–2322.

Deng, Y.J., et al., Polymorphic analysis of 21 new STR loci in Chinese Uigur group. *Forensic Sci Int Genet*, 2013, **7**(3): e97–e98.

Di Cristofaro, J., et al., Genetic data of 15 STR loci in five populations from Afghanistan. *Forensic Sci Int Genet*, 2012, **6**(1): e44–e45.

Dognaux, S., et al., Allele frequencies for the new European standard set (ESS) loci and D1S1677 in the Belgian population. *Forensic Sci Int Genet*, 2012, **6**(2): e75–e77.

dos Santos, L.L., et al., Allele distribution of six STR/miniSTR loci (CD4, FABP2, D12S391, D14S1434, D22S1045 and D10S1248) for forensic purposes in Southeastern Brazil. *Ann Hum Biol*, 2011, **38**(1): 110–113.

Du, B., et al., Allele frequencies for two STR loci D6S1274 and D17S1299 in Chinese and Thai populations. *J Forensic Sci*, 2007, **52**(1): 225.

Dubey, B., et al., Forensic STR profile of two endogamous populations of Madhya Pradesh, India. *Leg Med (Tokyo)*, 2009, **11**(1): 41–44.

Eaaswarkhanth, M., S. Roy, and I. Haque, Allele frequency distribution for 15 autosomal STR loci in two Muslim populations of Tamilnadu, India. *Leg Med (Tokyo)*, 2007, **9**(6): 332–335.

Eaaswarkhanth, M., T.S. Vasulu, and I. Haque, Genetic affinity between diverse ethnoreligious communities of Tamil Nadu, India: A microsatellite study. *Hum Biol*, 2008, **80**(6): 601–609.

Eaaswarkhanth, M., et al., Diverse genetic origin of Indian Muslims: Evidence from autosomal STR loci. *J Hum Genet*, 2009, **54**(6): 340–348.

Eaaswarkhanth, M., et al., Microsatellite diversity delineates genetic relationships of Shia and Sunni Muslim populations of Uttar Pradesh, India. *Hum Biol*, 2009, **81**(4): 427–445.

Eckhoff, C., S.J. Walsh, and J.S. Buckleton, Population data from sub-populations of the Northern Territory of Australia for 15 autosomal short tandem repeat (STR) loci. *Forensic Sci Int*, 2007, **171**(2–3): 237–249.

El Andari, A., et al., Population genetic data for 23 STR markers from Lebanon. *Forensic Sci Int Genet*, 2013, **7**(4): e108–e113.

El Ossmani, H., et al., Assessment of phylogenetic structure of Berber-speaking population of Azrou using 15 STRs of Identifiler kit. *Leg Med (Tokyo)*, 2010, **12**(1): 52–56.

Elmrghni, S., et al., Genetic data provided by 15 autosomal STR loci in the Libyan population living in Benghazi. *Forensic Sci Int Genet*, 2012, **6**(3): e93–e94.

Erkol, Z., et al., STR data for the AmpFlSTR identifier loci from an old settlement in Northwestern Turkey. *Forensic Sci Int*, 2007, **173**(2–3): 238–240.

Ferdous, A., et al., Forensic evaluation of STR data for the PowerPlex 16 system loci in a Bangladeshi population. *Leg Med (Tokyo)*, 2009, **11**(4): 198–199.

Forward, B.W., et al., AmpPFlSTR Identifiler STR allele frequencies in Tanzania, Africa. *J Forensic Sci*, 2008, **53**(1): 245.

Fridman, C., et al., Brazilian population profile of 15 STR markers. *Forensic Sci Int Genet*, 2008, **2**(2): e1–e4.

Fujihara, J., et al., Allele frequencies for nine STR loci in Ovambo population using AmpFlSTR Profiler Kit. *Forensic Sci Int*, 2007, **169**(1): e7–e9.

Gazi, N.N., et al., Genetic polymorphisms of 15 autosomal STR loci in three isolated tribal populations of Bangladesh. *Forensic Sci Int Genet*, 2010, **4**(4): 265–266.

Goetz, R., et al., Population data from the New South Wales Aboriginal Australian sub-population for the Profiler Plus autosomal short tandem repeat (STR) loci. *Forensic Sci Int*, 2008, **175**(2–3): 235–237.

Gomes, A.V., et al., 13 STR loci frequencies in the population from Paraiba, Northeast Brazil. *Forensic Sci Int*, 2007, **173**(2–3): 231–234.

Gomes, V., et al., Population data defined by 15 autosomal STR loci in Karamoja population (Uganda) using AmpFlSTR Identifiler kit. *Forensic Sci Int Genet*, 2009, **3**(2): e55–e58.

Gomez, M.A., et al., Allele frequencies of 15 STR loci in the population of the city of Quito, Ecuador. *J Forensic Sci*, 2008, **53**(2): 510–511.

Gorostiza, A., et al., Allele frequencies of the 15 AmpFlSTR Identifiler loci in the population of Metztitlan (Estado de Hidalgo), Mexico. *Forensic Sci Int*, 2007, **166**(2–3): 230–232.

Grubwieser, P., et al., Evaluation of an extended set of 15 candidate STR loci for paternity and kinship analysis in an Austrian population sample. *Int J Legal Med*, 2007, **121**(2): 85–89.

Gutierrez, C.C., et al., Population genetic data for 15 STR loci (PowerPlex 16 kit) in Nicaragua. *Forensic Sci Int Genet*, 2011, **5**(5): 563–564.

Hatzer-Grubwieser, P., et al., Allele frequencies and concordance study of 16 STR loci—Including the new European standard set (ESS) loci—In an Austrian population sample. *Forensic Sci Int Genet*, 2012, **6**(1): e50–e51.

Havas, D., et al., Population genetics of 15 AmpFlSTR Identifiler loci in Macedonians and Macedonian Romani (Gypsy). *Forensic Sci Int*, 2007, **173**(2–3): 220–224.

He, J. and F. Guo, Allele frequencies for fifteen autosomal STR loci in a Xibe population from Liaoning Province, Northeast China. *Forensic Sci Int Genet*, 2013, **7**(3): e80–e81.

He, J. and F. Guo, Genetic variation of fifteen autosomal STR loci in a Manchu population from Jilin Province, Northeast China. *Forensic Sci Int Genet*, 2013, **7**(2): e45–e46.

Herrera-Paz, E.F., et al., Allele frequencies distributions for 13 autosomal STR loci in 3 Black Carib (Garifuna) populations of the Honduran Caribbean coasts. *Forensic Sci Int Genet*, 2008, **3**(1): e5–e10.

Hill, C.R., et al., U.S. population data for 29 autosomal STR loci. *Forensic Sci Int Genet*, 2013, **7**(3): e82–e83.

Hong, S.B., et al., Korean population genetic data and concordance for the PowerPlex® ESX 17, AmpFlSTR Identifiler®, and PowerPlex® 16 systems. *Forensic Sci Int Genet*, 2013, **7**(3): e47–e51.

Hou, G., et al., Genetic distribution on 15 STR loci from a Han population of Shenyang region in northeast China. *Forensic Sci Int Genet*, 2013, **7**(3): e86–e87.

Hou, Y.P., et al., D20S161 data for three ethnic populations and forensic validation. *Int J Legal Med*, 1999, **112**(6): 400–402.

Huang, Q., et al., Genetic polymorphism of 15 STR loci in Chinese Han population from Shanghai municipality in East China. *Forensic Sci Int Genet*, 2013, **7**(2): e31–e34.

Huang, S., et al., Genetic variation analysis of 15 autosomal STR loci of AmpFlSTR Sinofiler PCR amplification kit in Henan (central China) Han population. *Leg Med (Tokyo)*, 2010, **12**(3): 160–161.

Hwa, H.L., et al., Fifteen non-CODIS autosomal short tandem repeat loci multiplex data from nine population groups living in Taiwan. *Int J Legal Med*, 2012, **126**(4): 671–675.

Hwa, H.L., et al., Fourteen non-CODIS autosomal short tandem repeat loci multiplex data from Taiwanese. *Int J Legal Med*, 2011, **125**(2): 219–226.

Illeperuma, R.J., et al., Genetic profile of 11 autosomal STR loci among the four major ethnic groups in Sri Lanka. *Forensic Sci Int Genet*, 2009, **3**(3): e105–e106.

Illeperuma, R.J., et al., Genetic variation at 11 autosomal STR loci in the aboriginal people, the Veddahs of Sri Lanka. *Forensic Sci Int Genet*, 2010, **4**(2): 142.

Jacewicz, R., et al., Population database on 15 autosomal STR loci in 1000 unrelated individuals from the Lodz region of Poland. *Forensic Sci Int Genet*, 2008, **2**(1): e1–e3.

Jedrzejczyk, M., et al., Genetic population studies on 15 NGM STR loci in central Poland population. *Forensic Sci Int Genet*, 2012, **6**(4): e119–e120.

Jeran, N., et al., Genetic diversity of 15 STR loci in a population of Montenegro. *Coll Antropol*, 2007, **31**(3): 847–852.

Jin, H.J., et al., Forensic and population genetic analyses of eighteen non-CODIS miniSTR loci in the Korean population. *J Forensic Leg Med*, 2013, **20**(8): 1093–1097.

Juarez-Cedillo, T., et al., Genetic admixture and diversity estimations in the Mexican Mestizo population from Mexico City using 15 STR polymorphic markers. *Forensic Sci Int Genet*, 2008, **2**(3): e37–e39.

Kalpana, D., et al., Pentaplex typing of new European standard set (ESS) STR loci in Indian population. *Forensic Sci Int Genet*, 2012, **6**(3): e86–e89.

Kang, L., et al., Genetic polymorphisms of 15 STR loci in two Tibetan populations from Tibet Changdu and Naqu, China. *Forensic Sci Int*, 2007, **169**(2–3): 239–243.

Kang, L.L., et al., Allele frequencies of 15 STR loci of Tibetan lived in Tibet Lassa. *Forensic Sci Int*, 2007, **168**(2–3): 236–240.

Kee, B.P., et al., Genetic data for 15 STR loci in a Kadazan-Dusun population from East Malaysia. *Genet Mol Res*, 2011, **10**(2): 739–743.

Khodjet-el-Khil, H., et al., Allele frequencies for 15 autosomal STR markers in the Libyan population. *Ann Hum Biol*, 2012, **39**(1): 80–83.

Kido, A., et al., Population data on the AmpFlSTR Identifiler loci in Africans and Europeans from South Africa. *Forensic Sci Int*, 2007, **168**(2–3): 232–235.

Korzebor, A., et al., Statistical analysis of six STR loci located in MHC region in Iranian population for pre-implantation genetic diagnosis. *Int J Immunogenet*, 2007, **34**(6): 441–443.

Kraaijenbrink, T., et al., Allele frequency distribution for 21 autosomal STR loci in Bhutan. *Forensic Sci Int*, 2007, **170**(1): 68–72.

Kraaijenbrink, T., et al., Allele frequency distribution for 21 autosomal STR loci in Nepal. *Forensic Sci Int*, 2007, **168**(2–3): 227–231.

Krithika, S., et al., Allele frequency distribution at 15 autosomal STR loci in Panggi, Komkar and Padam sub tribes of Adi, a Tibeto-Burman speaking population of Arunachal Pradesh, India. *Leg Med (Tokyo)*, 2007, **9**(4): 210–217.

Lee, M.H., et al., Genetic variation of three autosomal STR loci D21S1435, D21S1411, and D21S1412 in Korean population. *Mol Biol Rep*, 2010, **37**(1): 99–104.

Li, B., et al., Population genetic analyses of the STR loci of the AmpFlSTR NGM SElect kit for Han population in Fujian Province, China. *Int J Legal Med*, 2013, **127**(2): 345–346.

Li, C., et al., Genetic polymorphism of 17 STR loci for forensic use in Chinese population from Shanghai in East China. *Forensic Sci Int Genet*, 2009, **3**(4): e117–e118.

Li, S., et al., Allele frequencies of nine non-CODIS STR loci in Chinese Uyghur ethnic minority group. *Forensic Sci Int Genet*, 2012, **6**(1): e11–e12.

Liao, G., et al., Population genetic study of 15 STR loci in a Chinese population. *J Forensic Sci*, 2008, **53**(1): 252–253.

Liu, C., et al., Genetic polymorphisms of 9 non-CODIS short tandem repeat loci in two ethnic minority populations in Southern China. *Forensic Sci Int Genet*, 2013, **7**(4): e114–e115.

Liu, J., et al., Allele frequencies of 19 autosomal STR loci in Manchu population of China with phylogenetic structure among worldwide populations. *Gene*, 2013, **529**(2): 282–287.

Lu, D.J., Q.L. Liu, and H. Zhao, Genetic data of nine non-CODIS STRs in Chinese Han population from Guangdong Province, Southern China. *Int J Legal Med*, 2011, **125**(1): 133–137.

Manamperi, A., et al., STR polymorphisms in Sri Lanka: Evaluation of forensic utility in identification of individuals and parentage testing. *Ceylon Med J*, 2009, **54**(3): 85–89.

Manta, F.S., et al., Terena Amerindian group autosomal STR data: Comparison studies with other Brazilian populations. *Mol Biol Rep*, 2012, **39**(4): 4455–4459.

Marian, C., et al., STR data for the 15 AmpFlSTR identifiler loci in the Western Romanian population. *Forensic Sci Int*, 2007, **170**(1): 73–75.

Martin, P., et al., Allele frequencies of six miniSTR loci (D10S1248, D14S1434, D22S1045, D4S2364, D2S441 and D1S1677) in a Spanish population. *Forensic Sci Int*, 2007, **169**(2–3): 252–254.

Martinez, B., J.J. Builes, and L. Caraballo, Genetic data analysis of nine STRs in two Caribbean Colombian populations: Cesar and Guajira. *J Forensic Sci*, 2008, **53**(1): 254–255.

Martinez-Cortes, G., et al., Origin and genetic differentiation of three native Mexican groups (Purepechas, Triquis and Mayas): Contribution of CODIS-STRs to the history of human populations of Mesoamerica. *Ann Hum Biol*, 2010, **37**(6): 801–819.

Martins, J.A., et al., Genetic data of 15 autosomal STR loci: An analysis of the Araraquara population colonization (Sao Paulo, Brazil). *Mol Biol Rep*, 2011, **38**(8): 5397–5403.

Maruyama, S., et al., Population data on 15 STR loci using AmpFlSTR Identifiler kit in a Malay population living in and around Kuala Lumpur, Malaysia. *Leg Med (Tokyo)*, 2008, **10**(3): 160–162.

Mastana, S.S., et al., Genetic variation of 13 STR loci in the four endogamous tribal populations of Eastern India. *Forensic Sci Int*, 2007, **169**(2–3): 266–273.

Melo, M.M., et al., Genetic study of 15 STRs loci of Identifiler system in Angola population. *Forensic Sci Int Genet*, 2010, **4**(5): e153–e157.

Montelius, K., A.O. Karlsson, and G. Holmlund, STR data for the AmpFlSTR Identifiler loci from Swedish population in comparison to European, as well as with non-European population. *Forensic Sci Int Genet*, 2008, **2**(3): e49–e52.

Monterrosa, J.C., et al., Population genetic data for 16 STR loci (PowerPlex ESX-17 kit) in El Salvador. *Forensic Sci Int Genet*, 2012, **6**(5): e134.

Mornhinweg, E., et al., D3S1358: Sequence analysis and gene frequency in a German population. *Forensic Sci Int*, 1998, **95**(2): 173–178.

Munoz, A., et al., Allele frequencies of 15 STRs in the Calchaqui Valleys population (North-Western Argentina). *Forensic Sci Int Genet*, 2012, **6**(1): e58–e60.

Nascimento, E., E. Cerqueira, and L. Gusmao, Population database defined by 13 autosomal STR loci in a representative sample from Bahia, Northeast Brazil. *Forensic Sci Int Genet*, 2011, **5**(1): e38–e40.

Nasibov, E., et al., Allele frequencies of 15 STR loci in Azerbaijan population. *Forensic Sci Int Genet*, 2013, **7**(3): e99–e100.

Nie, S., et al., Genetic data of 15 STR loci in Chinese Yunnan Han population. *Forensic Sci Int Genet*, 2008, **3**(1): e1–e3.

Noor, S., S. Roy, and I. Haque, An autosomal STR database of Muslims: The largest minority community, Uttar Pradesh, India. *Forensic Sci Int Genet*, 2011, **5**(4): e117–e118.

Noor, S., et al., Allele frequency distribution for 15 autosomal STR loci in Afridi Pathan population of Uttar Pradesh, India. *Leg Med (Tokyo)*, 2009, **11**(6): 308–311.

Novokmet, N., et al., Forensic efficiency parameters for the 15 STR loci in the population of the island of Cres (Croatia). *Coll Antropol*, 2009, **33**(4): 1319–1322.

Ocampos, M., et al., 15 STR loci frequencies in the population from Santa Catarina, Southern Brazil. *Forensic Sci Int Genet*, 2009, **3**(4): e129–e131.

Omran, G.A., G.N. Rutty, and M.A. Jobling, Genetic variation of 15 autosomal STR loci in Upper (Southern) Egyptians. *Forensic Sci Int Genet*, 2009, **3**(2): e39–e44.

Ossmani, H.E., et al., Allele frequencies of 15 autosomal STR loci in the Southern Morocco population with phylogenetic structure among worldwide populations. *Leg Med (Tokyo)*, 2009, **11**(3): 155–158.

Ota, M., et al., Allele frequencies for 15 STR loci in Tibetan populations from Nepal. *Forensic Sci Int*, 2007, **169**(2–3): 234–238.

Park, J.H., et al., Genetic variation of 23 autosomal STR loci in Korean population. *Forensic Sci Int Genet*, 2013, **7**(3): e76–e77.

Parys-Proszek, A., et al., Genetic variation of 15 autosomal STR loci in a population sample from Poland. *Leg Med (Tokyo)*, 2010, **12**(5): 246–248.

Pepinski, W., et al., Polymorphism of 11 non-CODIS STRs in a population sample of Lithuanian minority residing in northeastern Poland. *Forensic Sci Int Genet*, 2011, **5**(1): e37.

Pepinski, W., et al., Polymorphism of 11 non-CODIS STRs in a population sample of religious minority of Old Believers residing in Northeastern Poland. *Adv Med Sci*, 2010, **55**(2): 328–332.

Petric, G., et al., Genetic variation at 15 autosomal STR loci in the Hungarian population of Vojvodina Province, Republic of Serbia. *Forensic Sci Int Genet*, 2012, **6**(6): e163–e165.

Phillips, C., et al., Analysis of global variability in 15 established and 5 new European standard set (ESS) STRs using the CEPH human genome diversity panel. *Forensic Sci Int Genet*, 2011, **5**(3): 155–169.

Piatek, J., et al., Population genetics of 15 autosomal STR loci in the population of Pomorze Zachodnie (NW Poland). *Forensic Sci Int Genet*, 2008, **2**(3): e41–e43.

Pinto, L.M., et al., Molecular characterization and population genetics of non-CODIS microsatellites used for forensic applications in Brazilian populations. *Forensic Sci Int Genet*, 2014, **9**: e16–e17.

Poetsch, M. and N. von Wurmb-Schwark, Allele frequencies for the 16 short tandem repeats of the Powerplex ESX17 kit in a population from Turkey. *Int J Legal Med*, 2013, **127**(3): 591–592.

Poetsch, M., et al., First experiences using the new Powerplex® ESX17 and ESI17 kits in casework analysis and allele frequencies for two different regions in Germany. *Int J Legal Med*, 2011, **125**(5): 733–739.

Poiares Lde, A., et al., 15 STR loci frequencies in the population from Parana, Southern Brazil. *Forensic Sci Int Genet*, 2009, **4**(1): e23–e24.

Pontes, M.L. and M.F. Pinheiro, Population data of the AmpFISTR® NGM STR loci in a North of Portugal sample. *Forensic Sci Int Genet*, 2012, **6**(5): e127–e128.

Porras, L., et al., Genetic polymorphism of 15 STR loci in central Western Colombia. *Forensic Sci Int Genet*, 2008, **2**(1): e7–e8.

Projic, P., et al., Allele frequencies for 15 short tandem repeat loci in representative sample of Croatian population. *Croat Med J*, 2007, **48**(4): 473–477.

Raczek, E., Population data on the 11 STR loci in the Upper Silesia (Poland). *Forensic Sci Int*, 2007, **168**(1): 68–72.

Rak, S.A., et al., Population genetic data on 15 STR loci in the Hungarian population. *Forensic Sci Int Genet*, 2011, **5**(5): 543–544.

Rakha, A., et al., Genetic analysis of Kashmiri Muslim population living in Pakistan. *Leg Med (Tokyo)*, 2008, **10**(4): 216–219.

Rakha, A., et al., Population genetic data on 15 autosomal STRs in a Pakistani population sample. *Leg Med (Tokyo)*, 2009, **11**(6): 305–307.

Rangel-Villalobos, H., et al., Evaluation of forensic and anthropological potential of D9S1120 in Mestizos and Amerindian populations from Mexico. *Croat Med J*, 2012, **53**(5): 423–431.

Rangel-Villalobos, H., et al., Forensic parameters for 15 STRs in eight Amerindian populations from the north and west of Mexico. *Forensic Sci Int Genet*, 2013, **7**(3): e62–e65.

Rebala, K., et al., Belarusian population genetic database for 15 autosomal STR loci. *Forensic Sci Int*, 2007, **173**(2–3): 235–237.

Riccardi, L.N., et al., Genetic profiling of Bolivian population using 15 STR markers of forensic importance. *Leg Med (Tokyo)*, 2009, **11**(3): 149–151.

Rocchi, A., et al., Italian data of 23 STR loci amplified in a single multiplex reaction. *Forensic Sci Int Genet*, 2012, **6**(6): e157–e158.

Rodenbusch, R., et al., Allele frequencies of the five new generation forensic STR (D1S1656, D2S441, D10S1248, D12S391 and D22S1045) in the population from Rio Grande do Sul, Southern Brazil. *Forensic Sci Int Genet*, 2012, **6**(1): e55–e57.

Rodrigues, E.L., et al., Genetic data on 15 STR autosomal loci for a sample population of the Northern Region of the State of Rio de Janeiro, Brazil. *Forensic Sci Int Genet*, 2009, **4**(1): e25–e26.

Rodrigues, E.M., J. Palha Tde, and S.E. dos Santos, Allele frequencies data and statistic parameters for 13 STR loci in a population of the Brazilian Amazon Region. *Forensic Sci Int*, 2007, **168**(2–3): 244–247.

Rodriguez, A., et al., Population genetic data for 18 STR loci in Costa Rica. *Forensic Sci Int*, 2007, **168**(1): 85–88.

Roy, S., et al., Autosomal STR variations in three endogamous populations of West Bengal, India. *Leg Med (Tokyo)*, 2008, **10**(6): 326–332.

Rubi-Castellanos, R., et al., Genetic data of 15 autosomal STRs (Identifiler kit) of three Mexican Mestizo population samples from the States of Jalisco (West), Puebla (Center), and Yucatan (Southeast). *Forensic Sci Int Genet*, 2009, **3**(3): e71–e76.

Sanchez-Diz, P., et al., 16 STR data of a Greek population. *Forensic Sci Int Genet*, 2008, **2**(4): e71–e72.

Sanchez-Diz, P., et al., Population data on 15 autosomal STRs in a sample from Colombia. *Forensic Sci Int Genet*, 2009, **3**(3): e81–e82.

Santos, C., et al., Genetic structure of the Azores Islands: A study using 15 autosomal short tandem repeat loci. *Coll Antropol*, 2009, **33**(4): 991–999.

Schlebusch, C.M., H. Soodyall, and M. Jakobsson, Genetic variation of 15 autosomal STR loci in various populations from southern Africa. *Forensic Sci Int Genet*, 2012, **6**(1): e20–e21.

Shi, M., et al., Genetic polymorphism of 14 non-CODIS STR loci for forensic use in Southeast China population. *Forensic Sci Int*, 2008, **174**(1): 77–80.

Shotivaranon, J., et al., DNA database of populations from different parts in the Kingdom of Thailand. *Forensic Sci Int Genet*, 2009, **4**(1): e37–e38.

Silva, B.C., et al., Genetic diversity and statistical parameters of 15 autosomal STR loci in the Pomeranian subpopulation of Espirito Santo State, Brazil. *Mol Biol Rep*, 2011, **38**(5): 3013–3016.

Silva, M.B., et al., Allele frequencies of fifteen STR loci in a population from Central Brazil. *Forensic Sci Int Genet*, 2010, **4**(5): e151–e152.

Simkova, H., et al., Allele frequency data for 17 short tandem repeats in a Czech population sample. *Forensic Sci Int Genet*, 2009, **4**(1): e15–e17.

Smith, B.G., et al., Population data for 15 STR loci (Identifiler kit) in a Filipino population. *Leg Med (Tokyo)*, 2009, **11**(3): 159–161.

Soltyszewski, I., et al., Analysis of forensically used autosomal short tandem repeat markers in Polish and neighboring populations. *Forensic Sci Int Genet*, 2008, **2**(3): 205–211.

Sotak, M., et al., Genetic variation analysis of 15 autosomal STR loci in Eastern Slovak Caucasian and Romany (Gypsy) population. *Forensic Sci Int Genet*, 2008, **3**(1): e21–e25.

Sotak, M., et al., Population database of 17 autosomal STR loci from the four predominant Eastern Slovakia regions. *Forensic Sci Int Genet*, 2011, **5**(3): 262–263.

Stanciu, F., O.R. Popescu, and I.M. Stoian, Allele frequencies of 15 STR loci in Moldavia region (NE Romania). *Forensic Sci Int Genet*, 2009, **4**(1): e39–e40.

Stanciu, F., O.R. Popescu, and I.M. Stoian, STR data for the AmpFlSTR Identifiler from Dobruja region (SE Romania). *Forensic Sci Int Genet*, 2009, **3**(2): 146–147.

Stanciu, F., I.M. Stoian, and O.R. Popescu, Comprehensive STR data for the AmpFlSTR Identifiler from Transylvania (NW Romania). *Leg Med (Tokyo)*, 2009, **11**(1): 48–50.

Stanciu, F., I.M. Stoian, and O.R. Popescu, Population data for 15 short tandem repeat loci from Wallachia Region, South Romania. *Croat Med J*, 2009, **50**(3): 321–325.

Stanciu, F., et al., Genetic parameters and allele frequencies of five new European standard set STR loci (D10S1248, D22S1045, D2S441, D1S1656, D12S391) in the population of Romania. *Croat Med J*, 2013, **54**(3): 232–237.

Steinlechner, M., et al., Population genetics of ten STR loci (AmpFlSTR SGM plus) in Austria. *Int J Legal Med*, 2001, **114**(4–5): 288–290.

Stepanov, V.A., et al., Genetic variability of 15 autosomal STR loci in Russian populations. *Leg Med (Tokyo)*, 2010, **12**(5): 256–258.

Suadi, Z., et al., STR data for the AmpFlSTR Identifiler loci from the three main ethnic indigenous population groups (Iban, Bidayuh, and Melanau) in Sarawak, Malaysia. *J Forensic Sci*, 2007, **52**(1): 231–234.

Talledo, M., et al., Comparative allele distribution at 16 STR loci between the Andean and coastal population from Peru. *Forensic Sci Int Genet*, 2010, **4**(4): e109–e117.

Tamaki, K., et al., Evaluation of tetranucleotide repeat locus D7S809 (wg1g9) in the Japanese population. *Forensic Sci Int*, 1996, **81**(2–3): 133–140.

Tang, J., et al., Genetic analyzing of 15 STR loci in a Han population of Jinan (Northern China). *Leg Med (Tokyo)*, 2009, **11**(3): 144–146.

Taylor, D.A., J.M. Henry, and S.J. Walsh, South Australian Aboriginal sub-population data for the nine AmpFlSTR Profiler Plus short tandem repeat (STR) loci. *Forensic Sci Int Genet*, 2008, **2**(2): e27–e30.

Teng, Y., et al., Genetic variation of new 21 autosomal short tandem repeat loci in a Chinese Salar ethnic group. *Mol Biol Rep*, 2012, **39**(2): 1465–1470.

Thangaraj, K., et al., Autosomal STR data on the enigmatic Andaman Islanders. *Forensic Sci Int*, 2007, **169**(2–3): 247–251.

Tillmar, A.O., G. Backstrom, and K. Montelius, Genetic variation of 15 autosomal STR loci in a Somali population. *Forensic Sci Int Genet*, 2009, **4**(1): e19–e20.

Tong da, Y., et al., Polymorphism analysis and evaluation of nine non-CODIS STR loci in the Han population of Southern China. *Ann Hum Biol*, 2010, **37**(6): 820–826.

Tong, D., et al., Polymorphism analysis of 15 STR loci in a large sample of the Han population in Southern China. *Forensic Sci Int Genet*, 2009, **4**(1): e27–e29.

Tong, D., et al., Polymorphism analysis and evaluation of 19 STR loci in the Han population of Southern China. *Ann Hum Biol*, 2013, **40**(2): 191–196.

Toscanini, U., et al., Testing for genetic structure in different urban Argentinian populations. *Forensic Sci Int*, 2007, **165**(1): 35–40.

Turrina, S., et al., Evaluation of genetic parameters of 22 autosomal STR loci (PowerPlex® Fusion System) in a population sample from Northern Italy. *Int J Legal Med*, 2014, **128**(2): 281–283.

Uchihi, R., et al., Population data of six STR loci using hexaplex PCR amplification and typing system, "Midi-6" in four regional populations in Japan. *Forensic Sci Int*, 2007, **169**(2–3): 255–259.

Untoro, E., et al., Allele frequency of CODIS 13 in Indonesian population. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S203–S205.

Vargas-Diaz, R., et al., A genetic study of the Identifiler(™)System 15 STR loci in the general population of Nicaragua, Central America. *Leg Med (Tokyo)*, 2011, **13**(4): 213–214.

Vergara, I.A., et al., Autosomal STR allele frequencies for the CODIS system from a large random population sample in Chile. *Forensic Sci Int Genet*, 2012, **6**(3): e83–e85.

Veselinovic, I.S., et al., Serbian population data at the CODIS core STR loci. *J Forensic Sci*, 2007, **52**(6): 1426–1427.

Vieira, T.C., et al., Allelic frequencies and statistical data obtained from 15 STR loci in a population of the Goias State. *Genet Mol Res*, 2013, **12**(1): 23–27.

Vullo, C., et al., Frequency data for 12 mini STR loci in Argentina. *Forensic Sci Int Genet*, 2010, **4**(3): e79–e81.

Walsh, S.J. and J.S. Buckleton, Autosomal microsatellite allele frequencies for 15 regionally defined Aboriginal Australian population datasets. *Forensic Sci Int*, 2007, **168**(2–3): e29–e42.

Walsh, S.J. and J.S. Buckleton, Autosomal microsatellite allele frequencies for a nationwide dataset from the Australian Caucasian sub-population. *Forensic Sci Int*, 2007, **168**(2–3): e47–e50.

Wang, H.D., et al., Allelic frequency distributions of 21 non-combined DNA index system STR loci in a Russian ethnic minority group from Inner Mongolia, China. *J Zhejiang Univ Sci B*, 2013, **14**(6): 533–540.

Wang, J., et al., Allele frequencies of nine non-CODIS STR loci in Western Chinese Han population. *Forensic Sci Int Genet*, 2013, **7**(3): e88–e89.

Wang, R., et al., Genetic distribution on 15 STR loci from a population of Southern Liaoning in Northeast of China. *Forensic Sci Int Genet*, 2008, **2**(2): e25–e26.

Wei, Y., et al., Genetic diversity of five STR loci in Southeastern China. *J Forensic Sci*, 2007, **52**(4): 999–1000.

Wu, Y.M., et al., Genetic polymorphisms of 15 STR loci in Chinese Han population living in Xi'an city of Shaanxi Province. *Forensic Sci Int Genet*, 2008, **2**(2): e15–e18.

Xing, J., et al., Genetic polymorphism of 15 STR loci in a Manchu population in Northeast China. *Forensic Sci Int Genet*, 2011, **5**(3): e93–e95.

Xu, L.N., S.P. Hu, and G.Y. Feng, STR polymorphisms of the Henan population and investigation of the Central Plains Han origin of Chaoshanese. *Biochem Genet*, 2009, **47**(7–8): 569–581.

Yan, J., et al., Genetic analysis of 15 STR loci on Chinese Tibetan in Qinghai Province. *Forensic Sci Int*, 2007, **169**(1): e3–e6.

Yan, J., et al., Genetic polymorphism of two novel STR loci AY639920 and AY639923 in a Chinese population. *J Forensic Sci*, 2007, **52**(3): 754.

Yong, R.Y., et al., Allele frequencies of six miniSTR loci of three ethnic populations in Singapore. *Forensic Sci Int*, 2007, **166**(2–3): 240–243.

Yoo, S.Y., et al., A large population genetic study of 15 autosomal short tandem repeat loci for establishment of Korean DNA profile database. *Mol Cells*, 2011, **32**(1): 15–19.

Yuan, L., et al., Population data of 21 non-CODIS STR loci in Han population of Northern China. *Int J Legal Med*, 2012, **126**(4): 659–664.

Zeng, Z., et al., Genetic data of six STR loci of Han population in Henan Province (Central China). *J Forensic Sci*, 2008, **53**(2): 515–516.

Zeng, Z.S., et al., Population genetic data of 15 STR loci in Han population of Henan province (central China). *Leg Med (Tokyo)*, 2007, **9**(1): 30–32.

Zha, L., et al., Genetic polymorphism of 21 non-CODIS STR loci in the Chinese Mongolian ethnic minority. *Forensic Sci Int Genet*, 2014, **9**: e32–e33.

Zhang, H., et al., Analysis of 15 STR loci in Chinese population from Sichuan in West China. *Forensic Sci Int*, 2007, **171**(2–3): 222–225.

Zhang, H.B., et al., Nine polymorphic STR loci in the HLA region in the Shaanxi Han population of China. *Genet Mol Res*, 2012, **11**(3): 2534–2538.

Zhang, S., et al., Genetic polymorphisms in 12 autosomal STRs in a Shanghai Han population from China. *Electrophoresis*, 2013, **34**(4): 613–617.

Zheng, X., et al., Genetic data of 9 STR loci from Henan Province (central China). *Forensic Sci Int*, 2007, **169**(2–3): 244–246.

Zhivotovsky, L.A., et al., A comprehensive population survey on the distribution of STR frequencies in Belarus. *Forensic Sci Int*, 2007, **172**(2–3): 156–160.

Zhivotovsky, L.A., et al., A reference database on STR allele frequencies in the Belarus population developed from paternity cases. *Forensic Sci Int Genet*, 2009, **3**(3): e107–e109.

Zhivotovsky, L.A., et al., An STR database on the Volga-Ural population. *Forensic Sci Int Genet*, 2009, **3**(4): e133–e136.

Zhivotovsky, L.A., et al., Developing STR databases on structured populations: The native South Siberian population versus the Russian population. *Forensic Sci Int Genet*, 2009, **3**(4): e111–e116.

Zhou, A., et al., Population genetic data of the NGM SElect STR loci in Chinese Han population from Zhejiang region, China. *Int J Legal Med*, 2013, **127**(2): 377–378.

Zhu, B., et al., Population genetic analysis of 15 STR loci of Chinese Tu ethnic minority group. *Forensic Sci Int*, 2008, **174**(2–3): 255–258.

Zhu, B.F., et al., Genetic diversities of 21 non-CODIS autosomal STRs of a Chinese Tibetan ethnic minority group in Lhasa. *Int J Legal Med*, 2011, **125**(4): 581–585.

Zhu, B.F., et al., Population data of 15 STR loci of Chinese Yi ethnic minority group. *Leg Med (Tokyo)*, 2008, **10**(4): 220–224.

Zhu, B.F., et al., Population genetic analysis of 15 autosomal STR loci in the Russian population of Northeastern Inner-Mongolia, China. *Mol Biol Rep*, 2010, **37**(8): 3889–3895.

Zhu, J., et al., Genetic polymorphisms of 15 STR in Chinese Salar ethnic minority group. *Forensic Sci Int*, 2007, **173**(2–3): 210–213.

Zhu, Y., et al., Genetic analysis of 15 STR loci in the population of Zhejiang Province (Southeast China). *Forensic Sci Int Genet*, 2009, **3**(4): e139–e140.

21

Sex Chromosome Haplotyping and Gender Identification

21.1 Y Chromosome Haplotyping

21.1.1 Human Y Chromosome Genome

The Y chromosome is inherited from the father and is passed on to all male offspring; this is known as *patrilineage* (Figure 21.1). Thus, the Y chromosome is unique to males. The chromosome encodes dozens of genes required for male-specific functions, including sex determination and spermatogenesis. The human Y chromosome genome contains approximately 59 million base pairs (bp) and likely contains 50–60 genes. The Y chromosome can be divided into two regions: the pseudoautosomal region and the male-specific Y region (Figure 21.2).

21.1.1.1 Pseudoautosomal Region

The *pseudoautosomal regions (PARs)* are homologous nucleotide sequences that are present on the X and Y chromosomes. There are two PARs on each X and Y chromosome: PAR1 and PAR2. In the Y chromosome, PAR1 is located on the terminal region of the short arm. The PAR1 comprises 2.6 Mb. Twenty-four genes have been identified within the PAR1. The PAR2 of the Y chromosome is located at the tip of the long arm. The PAR2 comprises 320 kb, with only four genes identified so far.

The PARs play an important role in proper segregation of the X and Y chromosomes during meiosis. During meiosis in males, the PARs allow the Y chromosome to pair with the X chromosome. Crossing over and recombination (Chapter 25) within the PARs of the X and Y chromosomes can occur. As a result, males can inherit an allele originally present on the PARs of the X chromosome, and females can inherit an allele originally present on the PARs of the Y chromosome. In particular, PAR1 plays a major role in X–Y chromosome pairing. The deletion of PAR1 results in failure of pairing and leads to male infertility. PAR2 is much shorter than PAR1, and thus shows a lower frequency of pairing than PAR1. The deletion of PAR2 exhibits less severe phenotypes than that of PAR1.

21.1.1.2 Male-Specific Y Region

The remainder of the Y chromosome is known as the *male-specific Y (MSY)* region. It was previously called the *nonrecombining Y (NRY)* region. The bulk of this region does not participate in homologous recombination. However, certain sections involve intrachromosomal gene conversion, which is the nonreciprocal transfer of genomic DNA between a pair of repeated genes on a single chromosome; in this case, the Y chromosome. About 40 megabases (Mb) within the



Figure 21.1 Human family pedigree showing inheritance of the Y chromosome. Females and males are denoted by circles and squares, respectively. Red symbols indicate individuals who inherited the same Y chromosome.



Figure 21.2 Human Y chromosome structure. PAR, the pseudoautosomal region; MSY, male-specific Y region; Y_p, the short arm of the Y chromosome; Y_q, the long arm of the Y chromosome. (© Richard C. Li.)

MSY region are heterochromatic (highly repetitive sequences) including the centromeric region and the bulk of the distal long arm. The euchromatic region, which comprises transcriptional active genes, is approximately 23 Mb. Certain sections of the euchromatic region share some homology with the X chromosome. For instance, X-transposed sequences of the Y chromosome are 99% identical to sequences within Xq21 (a band in the long arm of the X chromosome). The X-transposed sequences are the sequences, a total of approximately 3.4 Mb in length, that were transposed from the X chromosome to the Y chromosome several million years ago. Additionally, dozens of genes located in the euchromatic region share 60%–96% homology with their X chromosome counterparts. The regions sharing homology with the X chromosome should be avoided when selecting Y chromosome–specific markers for forensic DNA profiling.

21.1.1.3 Polymorphic Sequences

The Y chromosome contains an abundance of polymorphic markers. DYF155S1, also known as MSY1, is the first characterized variable number of tandem repeats (VNTR) or minisatellite at the human Y chromosome. It consists of an array of AT-rich repeats at 25 bp per unit repeat. The DYF155S1 locus is highly polymorphic. The unit repeat sequence varies through base substitution. At least five different variant types of unit repeat sequences exist. Additionally, the numbers of these units also vary, ranging from 50 to 115 repeats. Thus, the length of alleles range from approximately 1200 to 2800 bp. DYF155S1 is of considerable interest as a potential marker in forensic testing. However, the analysis method is labor intensive, making it difficult to implement in forensic casework, such as the investigation of sex crimes. Moreover, many single nucleotide polymorphisms (SNPs) and mobile elements exist at the Y chromosome. However, the discrimination power of SNPs and mobile elements is considerably less than that of Y chromosome short tandem repeats (Y-STRs). To date, Y-STRs are usually used for Y chromosome DNA testing due to the high-throughput analysis and good discrimination power (Section 21.1.2).

21.1.2 Y-STR

Y chromosome loci are very important for forensic DNA profiling, and this chapter will discuss such applications. For instance, the Y-STRs used in forensic DNA testing are male specific (for humans and certain higher primates) and are thus useful in the investigation of sexual assault cases involving male suspects. The evidence gathered in such cases usually consists of a mixture of high levels of female DNA and low levels of male DNA. The Y chromosome–specific loci can be examined without interference from large amounts of female DNA; differential extraction of sperm and nonsperm cells may not be needed. Furthermore, the Y-STR system is useful for determining the numbers of unrelated male perpetrators in sexual assault cases. The Y-STR loci used for forensic applications are located in the nonrecombining section of the Y chromosome so that patrilineage can be established. The technique can be used for paternity testing and the identification of missing persons. Finally, data interpretation can be simplified by the use of a single allele per Y-STR locus profile at most loci. Reference databases are available for estimating Y-STR haplotype frequencies among various human populations for statistical analysis of profiling results.

The major disadvantage of Y-STR loci is that their discriminating power is lowerthan that of autosomal loci. Because Y chromosome loci are linked, the product rule for statistical calculations for profile probability does not apply. Chapter 25 discusses the statistical evaluation of the strength of the matches. Also, the current Y-STR profiling cannot distinguish individuals with the same patrilineage.

More than 400 STR loci have been identified in the Y chromosome genome. The precise locations of these loci have been sequentially mapped using human genome sequencing data. Most Y-STR loci, approximately 60% of the 400 identified, are located on the long arm of the chromosome; about 22% are located on the short arm and a few are found in the centromeric region (Figure 21.3). Y-STRs in the telomeric region have yet to be identified. Only about 5% of Y-STRs are located within 5′ untranslated or intron regions of protein-coding genes. The



Figure 21.3 Human cytogenetic map of the Y chromosome. The Y-STRs and positions are shown (Mb = megabase). Cytogenetic patterns with alternating dark and light bands are shown. (© Richard C. Li.)



Figure 21.4 Human Y-STRs with different repeat unit length. About 400 Y-STRs have been identified and categorized according to repeat unit length. (Adapted from Hanson, E.K. and Ballantyne, J., *Leg Med (Tokyo)*, 8, 110, 2006.)

repeat unit lengths of identified Y-STRs have been analyzed. Among the 400 Y-STRs, 6% are dimeric repeats, 39% are trimeric, 45% are tetrameric, 9% are pentameric, and 1% are hexameric (Figure 21.4).

Fewer than half of the Y-STRs have been characterized. Some loci are polymorphic and are useful for forensic applications and developing new Y-STR multiplex systems. Since homologous recombination does not occur on the majority of the Y chromosome, alleles of Y-STR loci are linked (inherited together); they are referred to as *haplotypes*. As a result, the discrimination power of Y-STRs is much lower than that of autosomal STRs. The most commonly used Y-STR loci for forensic testing are described below.

21.1.2.1 Core Y-STR Loci

In 1997, the *European minimal haplotype* locus set, also known as the minimal haplotype loci, was recommended by the International Y-STR User Group for forensic applications (Table 21.1; Figure 21.5). This haplotype set includes a core set of nine Y-STR loci: DYS19, DYS385a and b, DYS389I, DYS389II, DYS390, DYS391, DYS392, and DYS393. In 2003, two additional loci were recommended by the Scientific Working Group for DNA Analysis Methods (SWGDAM) for forensic DNA analysis. The SWGDAM loci include the European minimal haplotype loci plus two additional loci: DYS438 and DYS439 (Table 21.1).

The application Y-STR for forensic casework has been expanded with additional Y-STR markers. The use of Y-STR loci has been facilitated by commercially available PCR amplification

Table 21.1 Common Y-STR Core Loci

Locus	EMH	US Haplotype Loci	Repeat Motif
DYS19	☑	☑	TAGA
DYS385a/b	☑	☑	GAAA
DYS389 I	☑	☑	TCTA
DYS389 II	☑	☑	[TCTG] [TCTA]
DYS390	☑	☑	[TCTG] [TCTA]
DYS391	☑	☑	TCTA
DYS392	☑	☑	TAT
DYS393	☑	☑	AGAT
DYS438		☑	TTTTC
DYS439		☑	GATA



Figure 21.5 Electropherogram of Y-STR profile using an early generation of multiplex of four loci. The genotype of the DNA profile is shown (DYS19: 14. DYS389I: 10. DYS389II: 26. DYS390: 24). (© Richard C. Li.)

kits in multiplex Y-STR systems. To improve discriminating power, multiplex systems including new Y-STR loci are desired. Many new Y-STR loci are being characterized for developing new multiplex systems. Commercially available kits with more Y-STR loci are now available and have been validated for forensic use (Table 21.2; Figures 21.6 and 21.7). Some of the additional Y-STR loci are highly discriminating, allowing for further distinction between unrelated male individuals. Additionally, Y-STR loci, such as DYS570 and DYS576, with high mutation rates (see rapidly mutating Y-STR loci; Section 21.1.2.3) are included, which are useful for the discrimination of related individuals.

21.1.2.2 Multilocal Y-STR Loci

DYS385 and DYS389 are *multilocal Y-STR loci* (*MLL*). The MLL designation refers to the presence of a particular STR at more than one site on the Y chromosome due to duplication. To date, about 50 such MLL Y-STRs have been identified. Further MLL subdivisions are designated bilocal, trilocal, and so on. DYS385 and DYS389 are bilocal.

The DYS385 locus has two inverted duplicated clusters and is separated by a 4×10^4 bp interstitial region (Figure 21.8). It can be amplified by a single set of primers. One allele is observed if the duplicates are the same length. If the duplicated clusters have different lengths, they can generate two different alleles when amplified. The smaller allele is designated "a" and the larger allele is designated "b." Moreover, the DYS389 locus has two duplicated clusters with the same orientation (Figure 21.9). In a single set of PCR primers, there are two binding sites for the same forward primer at each 5′ flanking sequence of the core repeat region of DYS389. These binding sites between DYS389I and DYS389II are about 120 bp apart. Therefore, two amplicons are produced. DYS389I is designated for the smaller allele, and DYS389II is designated for the larger allele.

21.1.2.3 Rapidly Mutating Y-STR

Current Y-STR loci implemented in forensic casework have adequate resolution of males from different patrilineages. However, most Y-STR sets have limited abilities to differentiate related males who belong to the same patrilineage. Thus, current forensic Y-STR profiling is not able to exclude patrilineal relatives of the suspect. Recently, rapidly mutating Y-STR (RM Y-STR) loci have been identified and characterized. The mutation rates of RM Y-STR are above 10^{-2}, which is considerably higher than the average mutation rates of Y-STRs. The average mutation rate for the majority of the Y-STRs characterized, including the core Y-STR loci currently used in forensic casework, is approximately 10^{-4}–10^{-3} per generation. Due to the high mutation rates, RM Y-STRs can improve patrilineage resolution. For use in forensic casework, the RM Y-STR loci have potential abilities to differentiate both paternally related and unrelated males.

Table 21.2 Y-STR Loci Covered by Representative Commercial Kits

	Loci	Yfiler[a]	PowerPlexY23[b]
Core loci	DYS19	☑	☑
	DYS385a/b	☑	☑
	DYS389 I	☑	☑
	DYS389 II	☑	☑
	DYS390	☑	☑
	DYS391	☑	☑
	DYS392	☑	☑
	DYS393	☑	☑
	DYS438	☑	☑
	DYS439	☑	☑
Additional loci	DYS437	☑	☑
	DYS448	☑	☑
	DYS456	☑	☑
	DYS458	☑	☑
	DYS481		☑
	DYS533		☑
	DYS549		☑
	DYS570		☑
	DYS576		☑
	DYS635	☑	☑
	DYS643		☑
	Y-GATA-H4	☑	☑

[a] AmpFlSTR® Yfiler® PCR Amplification Kit (Applied Biosystems).

[b] PowerPlex® Y23 System (Promega).

21.2 X Chromosome Haplotyping

X-chromosomal STR (X-STR) profiling is a useful tool in kinship testing in forensic investigations. For example, males under usual circumstances have only one X chromosome; thus males are hemizygous for the X-STR loci on the X chromosome. Homologous recombination between the X and Y chromosomes is restricted to the homologous PARs (Figure 21.2). The paternal X chromosome is inherited by daughters as haplotypes. Thus, father–daughter kinship is easier to determine using X-STRs than autosomal STRs. In females, there are two copies of the X chromosomes. Homologous recombination can occur between two X chromosomes in the mother–child transmission. Although it is possible to determine mother–child kinship using X-STR analysis, the level of certainty is less than that of father–daughter kinship analysis. Nevertheless, sharing of rare X-STR haplotypes can strengthen an indication of kinship. The most useful



Figure 21.6 Electropherogram of the allelic ladder of AmpFISTR® Yfiler® PCR Amplification Kit (Applied Biosystems). DYS19, DYS385 a/b, DYS389 I, DYS389 II, DYS390, DYS391, DYS392, DYS393, DYS437, DYS438, DYS439, DYS448, DYS456, DYS458, DYS635, and Y-GATA-H4 loci are shown. (© Richard C. Li.)



Figure 21.7 Individual Y-STR profile (AmpFlSTR® Yfiler® PCR Amplification Kit). The genotype of the DNA profile is shown. DYS19: 15. DYS385 a/b: 11, 14. DYS389 I: 13. DYS389 II: 29. DYS390: 24. DYS391: 11. DYS392: 13. DYS393: 13. DYS437: 15. DYS438: 12. DYS439: 12. DYS448: 19. DYS456: 15. DYS458: 17. DYS635: 24.Y-GATA-H4: 13. (© Richard C. Li.)



Figure 21.8 MLL Y-STR locus DYS385. At the DYS385 locus, note the two inverted duplicated regions of the Y chromosome with an interstitial region of 40 kilobases (kb). These inverted regions can be amplified with a single pair of primers (indicated by arrows) in one PCR reaction. The allele designations are described in the text. (© Richard C. Li.)



Figure 21.9 MLL Y-STR locus DYS389. At the DYS389 locus, note the two duplicated regions of the Y chromosome with the same orientation. These duplicated regions can be amplified with a single pair of primers (indicated by arrows) in one PCR reaction. The allele designations are described in the text. (© Richard C. Li.)

application of X-STR profiling, however, is in situations where autosomal STR profiling fails to determine kinship with high levels of certainty, and where Y-chromosomal or mitochondrial DNA profiling results are inconclusive.

Many X-STR loci have been identified spanning the entire human X chromosome. Increasing the number of X-STR loci to be analyzed in the inherited region would increase the degree of certainty in determining kinship. However, it is necessary to take into consideration the linkage between X-STR loci on the X chromosome. Based on Gregor Mendel's first law, the different alleles of two loci segregate independently. This is definitely true for loci localized on different chromosomes. The segregation can also be observed for loci located on the same chromosome, including the X chromosome, due to homologous recombination and meiotic crossing-over. Generally speaking, the farther apart the two loci are on the chromosome in physical distance, the more likely those loci are to segregate independently. When two loci are very close to each other, the alleles of the two loci are inherited together as a haplotype. Therefore, including additional closely linked STR loci does not necessarily improve the discrimination power in kinship analysis.

Homologous recombination events at different regions of the genome may occur with different probabilities. Thus, the tightness of linkage between two X-STR loci cannot be accurately measured based on the physical distance. In order to determine how closely two different loci are linked, the *recombination fraction* (or recombination frequency) can be used, which is the percentage of recombinants resulting from chromosomal crossover between two loci during meiosis among all the offspring. The recombination fraction reflects how often the loci are inherited together or how often they are separated. The recombination fraction ranges from 0% to 50%. The minimum recombination fraction is 0, indicating perfect linkage (no recombinants). The maximum is 50%, meaning complete independence of the two loci (they are actually located on different chromosomes or on the same chromosome with great distance between them).

Multiplex X-STR assays have also been developed. Commonly used X-STR loci can be grouped into linkage groups. Each linkage group is presumably transmitted independently from one another. These loosely linked loci can be treated as if they were located on different chromosomes. The distribution of alleles at these X-STR loci should be in accordance with the Hardy–Weinberg principle (Chapter 25). Within each linkage group, the occurrence of recombination is negligible. Thus, loci within groups are generally considered as closely linked and are thus treated as a haplotype.

21.3 Sex Typing for Gender Identification

Sex typing of a biological sample is useful in forensic investigation. For example, the application of sex typing facilitates the identification of the victim and the offender's DNA evidence in sexual assault cases and the remains of victims in mass disasters or missing persons investigations. One commonly used sex-typing marker is the amelogenin (*AMEL*) locus. The use of multiplex PCR systems with an additional amelogenin marker, a non-STR marker, leads to potential gender determination.

21.3.1 Amelogenin Locus

This region encodes extracellular matrix proteins involved in tooth enamel formation (Table 21.3). Mutations in the *AMEL* gene can lead to an enamel defect known as amelogenesis imperfecta. Amelogenesis imperfecta is a disorder that causes abnormal formation of tooth enamel in both primary and permanent teeth. The formed tooth enamel is soft and thin; therefore it is easily damaged. The *AMEL* locus has two homologous genes: *AMELX* (Xp22.2) is located on the human X chromosome (Figure 21.10) and *AMELY* (Yp11.2) is located on the human Y chromosome (Figure 21.11). Although the genes constitute a homologous pair, they differ in size and sequence. The coding sequence of the *AMELX* gene has a size of 2872 bp and the *AMELY* gene has a size of 3272 bp in length.

The most commonly used sex-typing method at the *AMEL* locus is the detection of a 6 bp deletion at intron 3 of *AMELX* (Figures 21.12 and 21.13). This deletion is not present in *AMELY*. Sex typing can be performed using primers specifically amplifying the region of the *AMEL* locus. Primer sets were developed to amplify both alleles in a single PCR. The two most commonly

Table 21.3 Sex-Typing Makers and Homologous Genes on the Human X and Y Chromosomes

Sex-Typing Markers					
X Chromosome			Y Chromosome		
Gene Symbol	Chromosomal Location	Distance from Xpter (Mb)	Gene Symbol	Chromosomal Location	Distance from Ypter (Mb)
AMELX	Xp22.2	11.3	*AMELY*	Yp11.2	6.7
DXYS156	Xq21.31	88.9	DXYS156	Yp11.2	3.2
SOX3	Xq27.1	139.6	*SRY*	Yp11.31	2.7
STS	Xp22.31	7.1–7.3	*STSP1*	Yq11.221	17.7
TSPYL2	Xp11.2	53.1	*TSPY1*	Yp11.2	9.2–9.3

Source: Ensembl Homo sapiens version 75.37 (GRCh37). Mb, megabase.


p22.3
p22.2
p22.1
p21.3
p21.2
p21.1
p11.4
p11.3
p11.23
p11.22
p11.21
p11.1
q11.1
q11.1
q12
q13
q21.1
q21.2
q21.3
q22.1
q22.2
q22.3
q23
q24
q25
q26
q27
q28
STS
AMELX
TSPYL2
DXYS156
SOX3

Figure 21.10 Cytogenetic map of the human X chromosome and sex-typing loci shown with physical positions (Mb = megabases). Cytogenetic patterns with alternating dark and light bands are shown. (© Richard C. Li.)


p11.32
p11.31
p11.2
p11.1
q11.1
q11.21
q11.221
q11.222
q11.223
q11.23
q12
SRY
DXYS156
AMELY
TSPYL1
STSP1

Figure 21.11 Cytogenetic map of the human Y chromosome and sex-typing loci shown with physical positions (Mb = megabases). Cytogenetic patterns with alternating dark and light bands are shown. (© Richard C. Li.)


Exon
Intron
1
2
3
4
5
6
7
1
2
3
4
5
6

Figure 21.12 Structure of human *AMELY* gene. Exons 1 through 7 and introns 1 through 6 are numbered. (© Richard C. Li.)



Figure 21.13 Sex typing using *AMEL* markers. A 6-bp deletion in intron 3 is present in *AMELX* but not in *AMELY* and can be resolved using electrophoresis as described in the text. (© Richard C. Li.)

used amelogenin primer sets generate amplicons of 106 and 112 bp or 212 and 218 bp for *AMELX* and *AMELY* loci, respectively. The amplicons generated from *AMELX* and *AMELY* are separated by electrophoresis. The observation of the *AMELX* fragment alone indicates a female, whereas the observation of both *AMELX* and *AMELY* fragments indicates a male (Figure 20.8). Nevertheless, DNA from primates and some rudiments can be amplified as well, but the amplicon sizes vary. The *AMEL* locus has been coamplified with other markers to provide a combined sex and identity test. Such combined tests have been used in historical D1S80 AFLP profiling (Chapter 19) and various current STR multiplex analyses.

Cases of *AMELY* null mutations have been reported where only the *AMELX* fragment is detected in *AMELY* null males. Many of them are phenotypically normal but present the *AMELX* sex types of females. Various interstitial deletions at the Y chromosome short arm and point mutations within the primer-binding sites have been identified as the possible cause of some *AMELY* null sex typing. The frequency of *AMELY* null males is rare, but is higher in Sri Lanka and India. However, the mutations may lead to incorrect identification of sex if the mutations occurred in the DNA evidence of criminal investigations such as sexual assaults or in the identification of human remains in mass disasters. In the case of a female individual, an *AMELX* mutation, which is rare, usually affects one copy of *AMELX*; however, the wild-type copy of the *AMELX* is detected. Thus, the *AMELX* mutation is less problematic in females than the *AMELY* mutation in sex typing in males.

21.3.2 Other Loci

To solve the incorrect identification problem with null *AMEL* mutations, additional candidate genetic markers are used in combination with *AMEL* analysis (Table 21.3). One useful marker is the sex-determining region Y (*SRY*) gene located on the Yp11.31 of the Y chromosome. *SRY* encodes a transcription factor that plays a role in the regulation of sex determination toward male development. The *SRY* protein contains a DNA-binding domain known as the HMG box. *SOX3*, an *SRY*-related HMG box-containing gene, has been identified at Xq27.1 of the X chromosome, which shares sequence homology with *SRY*. *SRY*-specific amplification is achieved using *SRY*-specific primers.

Another marker is the *TSPY* locus located on Yp11.2 of the Y chromosome. The *TSPY* locus encodes the testis-specific protein Y-encoded gene that is only expressed in the testis and may play a role in spermatogenesis. The *TSPY* structural gene is approximately 20 kb in length, consisting of 6 exons and 5 introns. The *TSPY* gene has multiple copies. A single Y chromosome contains several dozen copies of *TSPY* genes that are organized as a tandem array. The *TSPY* gene cluster shows copy number variation (CNV) between individuals in a population ranging from 23 to 64 copies. *DYS14* is a marker utilized for the characterization of the *TSPY* locus. The

DYS14 locus includes the partial sequence of the first exon and intron of the *TSPY* gene and shares approximately 98% sequence homology with other members of the *TSPY* gene cluster.

A *TSPY*-like (*TSPYL*) gene has been identified on the short arm of the X chromosome and is designated as *TSPYL2*. *TSPYL2* is a single-copy gene per X chromosome and is 6.3 kb in length, consisting of 7 exons and 6 introns. *TSPYL2* shares homology with *TSPY*. Additionally, several *TSPYL* genes have been identified on the autosomes. Primers are designed to amplify *TSPY* only and not amplify *TSPYL2* and other *TSPYL* gene sequences. The sensitivity of detecting *TSPY*, due to multiple copies, can be considerably higher than any single copy genetic maker such as *SRY*.

Furthermore, the DXYS156 locus, located at the pseudoautosomal region of both X and Y chromosomes, is another candidate marker used for sex typing. DXYS156 is a polymorphic pentanucleotide STR. The DXYS156 Y alleles have an additional adenine insertion in the repeat units of STR. Thus, the DXYS156 Y alleles can be distinguished from the DXYS156 X alleles because of the insertion. Additionally, the DXYS156 alleles are ethnically distributed. The DXYS156 profiling may potentially indicate the ethnic origin of an individual as an investigative lead.

Moreover, the steroid sulfatase (*STS*) gene encodes an enzyme that catalyzes the conversion of sulfated steroid precursors to biologically active steroids such as estrogens and androgens. The *STS* gene is located on the distal part of the short arm of the X chromosome within Xp22.31. The *STS* gene is 146 kb in length, consisting of 10 exons and 9 introns. The size of exons is between 120 and 160 bp long. However, the sizes of introns vary greatly, ranging from 102 bp to 35 kb. The entire coding sequence of the *STS* gene is 1542 bp in length. Deletions and point mutations of the *STS* gene have been associated with X-linked ichthyosis, a skin disease that affects males. There is an *STS* pseudogene, 100 kb in length, on the long arm of the Y chromosome known as *STSP1*. Although *STSP1* shares some sequence homologies with the *STS* gene, the pseudogene does not encode a functional gene. Primer sets are designed to amplify the target sequences within the first intron (35 kb in length) of the *STS* gene and its homologous *STSP1* pseudogene sequence. Although the homology of these target sequences of the *STS* gene and *STSP1* pseudogene is approximately 80%, amplicons with two different sizes are produced to identify *STS* and *STSP1* alleles for sex typing.

Bibliography

Y Chromosome Haplotyping

Alves, C., et al., Evaluating the informative power of Y-STRs: A comparative study using European and new African haplotype data. *Forensic Sci Int*, 2003, **134**(2–3): 126–133.

Ambers, A., et al., Autosomal and Y-STR analysis of degraded DNA from the 120-year-old skeletal remains of Ezekiel Harper. *Forensic Sci Int Genet*, 2014, **9**: 33–41.

Andersen, M.M., et al., Estimating stutter rates for Y-STR alleles. *Forensic Sci Int Genet Suppl*, 2011, **3**(1): e192–e193.

Andersen, M.M., et al., Estimating Y-STR allelic drop-out rates and adjusting for interlocus balances. *Forensic Sci Int Genet*, 2013, **7**(3): 327–336.

Asamura, H., et al., Evaluation of miniY-STR multiplex PCR systems for extended 16 Y-STR loci. *Int J Legal Med*, 2008, **122**(1): 43–49.

Ayadi, I., et al., Combining autosomal and Y-chromosomal short tandem repeat data in paternity testing with male child: Methods and application. *J Forensic Sci*, 2007, **52**(5): 1068–1072.

Ayub, Q., et al., Identification and characterisation of novel human Y-chromosomal microsatellites from sequence database information. *Nucleic Acids Res*, 2000, **28**(2): e8.

Balaresque, P., et al., Genomic complexity of the Y-STR DYS19: Inversions, deletions and founder lineages carrying duplications. *Int J Legal Med*, 2009, **123**(1): 15–23.

Ballantyne, K.N., et al., A new future of forensic Y-chromosome analysis: Rapidly mutating Y-STRs for differentiating male relatives and paternal lineages. *Forensic Sci Int Genet*, 2012, **6**(2): 208–218.

Ballantyne, K.N., et al., Mutability of Y-chromosomal microsatellites: Rates, characteristics, molecular bases, and forensic implications. *Am J Hum Genet*, 2010, **87**(3): 341–353.

Ballard, D.J., et al., A study of mutation rates and the characterisation of intermediate, null and duplicated alleles for 13 Y chromosome STRs. *Forensic Sci Int*, 2005, **155**(1): 65–70.

Beleza, S., et al., Extending STR markers in Y chromosome haplotypes. *Int J Legal Med*, 2003, **117**(1): 27–33.

Bosch, E., et al., High resolution Y chromosome typing: 19 STRs amplified in three multiplex reactions. *Forensic Sci Int*, 2002, **125**(1): 42–51.

Bouakaze, C., et al., First successful assay of Y-SNP typing by SNaPshot minisequencing on ancient DNA. *Int J Legal Med*, 2007, **121**(6): 493–499.

Brion, M., et al., Hierarchical analysis of 30 Y-chromosome SNPs in European populations. *Int J Legal Med*, 2005, **119**(1): 10–15.

Burgarella, C. and M. Navascues, Mutation rate estimates for 110 Y-chromosome STRs combining population and father-son pair data. *Eur J Hum Genet*, 2011, **19**(1): 70–75.

Butler, J.M., et al., A novel multiplex for simultaneous amplification of 20 Y chromosome STR markers. *Forensic Sci Int*, 2002, **129**(1): 10–24.

Caglia, A., et al., Increased forensic efficiency of a STR-based Y-specific haplotype by addition of the highly polymorphic DYS385 locus. *Int J Legal Med*, 1998, **111**(3): 142–146.

Capelli, C., et al., Phylogenetic evidence for multiple independent duplication events at the DYS19 locus. *Forensic Sci Int Genet*, 2007, **1**(3–4): 287–290.

Carboni, I. and U. Ricci, Unexpected patterns in Y-STR analyses and implications for profile identification. *Forensic Sci Int Genet Suppl*, 2009, **2**(1): 55–56.

Carracedo, A., et al., Results of a collaborative study of the EDNAP group regarding the reproducibility and robustness of the Y-chromosome STRs DYS19, DYS389 I and II, DYS390 and DYS393 in a PCR pentaplex format. *Forensic Sci Int*, 2001, **119**(1): 28–41.

Cerri, N., et al., Mixed stains from sexual assault cases: Autosomal or Y-chromosome short tandem repeats? *Croat Med J*, 2003, **44**(3): 289–292.

Corach, D., et al., Routine Y-STR typing in forensic casework. *Forensic Sci Int*, 2001, **118**(2–3): 131–135.

D'Amato, M.E., V.B. Bajic, and S. Davison, Design and validation of a highly discriminatory 10-locus Y-chromosome STR multiplex system. *Forensic Sci Int Genet*, 2011, **5**(2): 122–125.

Davis, C., et al., Prototype PowerPlex® Y23 system: A concordance study. *Forensic Sci Int Genet*, 2013, **7**(1): 204–208.

de Knijff, P., et al., Chromosome Y microsatellites: Population genetic and evolutionary aspects. *Int J Legal Med*, 1997, **110**(3): 134–149.

Decker, A.E., et al., The impact of additional Y-STR loci on resolving common haplotypes and closely related individuals. *Forensic Sci Int Genet*, 2007, **1**(2): 215–217.

Decker, A.E., et al., Analysis of mutations in father-son pairs with 17 Y-STR loci. *Forensic Sci Int Genet*, 2008, **2**(3): e31–e35.

Dekairelle, A.F. and B. Hoste, Application of a Y-STR-pentaplex PCR (DYS19, DYS389I and II, DYS390 and DYS393) to sexual assault cases. *Forensic Sci Int*, 2001, **118**(2–3): 122–125.

Delfin, F.C., et al., Y-STR analysis for detection and objective confirmation of child sexual abuse. *Int J Legal Med*, 2005, **119**(3): 158–163.

Deng, Z.H., et al., Application of 17 Y-chromosome specific STR loci in paternity testing. *Zhongguo Shi Yan Xue Ye Xue Za Zhi*, 2008, **16**(3): 699–703.

Djelloul, S. and V. Sarafian, Validation of a 17-locus Y-STR multiplex system. *Forensic Sci Int Genet Suppl*, 2008, **1**(1): 198–199.

Dupuy, B.M., et al., Y-chromosomal microsatellite mutation rates: Differences in mutation rate between and within loci. *Hum Mutat*, 2004, **23**(2): 117–124.

Edlund, H. and M. Allen, Y chromosomal STR analysis using pyrosequencing technology. *Forensic Sci Int Genet*, 2009, **3**(2): 119–124.

Ge, J., B. Budowle, and R. Chakraborty, Interpreting Y chromosome STR haplotype mixture. *Leg Med*, 2010, **12**(3): 137–143.

Ge, J., et al., Mutation rates at Y chromosome short tandem repeats in Texas populations. *Forensic Sci Int Genet*, 2009, **3**(3): 179–184.

Ge, J., et al., US forensic Y-chromosome short tandem repeats database. *Leg Med (Tokyo)*, 2010, **12**(6): 289–295.

Geppert, M., J. Edelmann, and R. Lessig, The Y-chromosomal STRs DYS481, DYS570, DYS576 and DYS643. *Leg Med*, 2009, **11**(Suppl 1): S109–S110.

Geppert, M., et al., Hierarchical Y-SNP assay to study the hidden diversity and phylogenetic relationship of native populations in South America. *Forensic Sci Int Genet*, 2011, **5**(2): 100–104.

Gill, P., et al., DNA commission of the International Society of Forensic Genetics: Recommendations on forensic analysis using Y-chromosome STRs. *Int J Legal Med*, 2001, **114**(6): 305–309.

Goedbloed, M., et al., Comprehensive mutation analysis of 17 Y-chromosomal short tandem repeat polymorphisms included in the AmpFSTR® Yfiler® PCR amplification kit. *Int J Legal Med*, 2009, **123**(6): 471–482.

Gonzalez-Neira, A., et al., Sequence structure of 12 novel Y chromosome microsatellites and PCR amplification strategies. *Forensic Sci Int*, 2001, **122**(1): 19–26.

Gross, A.M., et al., Internal validation of the AmpFlSTR Yfiler amplification kit for use in forensic casework. *J Forensic Sci*, 2008, **53**(1): 125–134.

Gusmao, L., C. Alves, and A. Amorim, Molecular characteristics of four human Y-specific microsatellites (DYS434, DYD437, DYS438, DYS439) for population and forensic studies. *Ann Hum Genet*, 2001, **65**(Pt 3): 285–291.

Gusmao, L., et al., Robustness of the Y STRs DYS19, DYS389 I and II, DYS390 and DYS393: Optimization of a PCR pentaplex. *Forensic Sci Int*, 1999, **106**(3): 163–172.

Gusmao, L., et al., Alternative primers for DYS391 typing: Advantages of their application to forensic genetics. *Forensic Sci Int*, 2000, **112**(1): 49–57.

Hall, A. and J. Ballantyne, Novel Y-STR typing strategies reveal the genetic profile of the semen donor in extended interval post-coital cervicovaginal samples. *Forensic Sci Int*, 2003, **136**(1–3): 58–72.

Hall, T.A., et al., Human Y-STR profiling using fully automated electrospray ionization time of flight mass spectrometry. *Forensic Sci Int Genet Suppl*, 2011, **3**(1): e451–e452.

Hammer, M.F., et al., Hierarchical patterns of global human Y-chromosome diversity. *Mol Biol Evol*, 2001, **18**(7): 1189–1203.

Hammer, M.F., et al., Population structure of Y chromosome SNP haplogroups in the United States and forensic implications for constructing Y chromosome STR databases. *Forensic Sci Int*, 2006, **164**(1): 45–55.

Hanson, E., et al., Performance evaluation and optimization of multiplex PCRs for the highly discriminating OSU 10-locus set Y-STRs. *J Forensic Sci*, 2012, **57**(1): 52–59.

Hanson, E.K. and J. Ballantyne, Comprehensive annotated STR physical map of the human Y chromosome: Forensic implications. *Leg Med (Tokyo)*, 2006, **8**(2): 110–120.

Hanson, E.K. and J. Ballantyne, An ultra-high discrimination Y chromosome short tandem repeat multiplex DNA typing system. *PLoS One*, 2007, **2**(8): e688.

Hartzell, B., K. Graham, and B. McCord, Response of short tandem repeat systems to temperature and sizing methods. *Forensic Sci Int*, 2003, **133**(3): 228–234.

He, M., et al., Geographical affinities of the HapMap samples. *PLoS One*, 2009, **4**(3): e4684.

Hedman, M., et al., Dissecting the Finnish male uniformity: The value of additional Y-STR loci. *Forensic Sci Int Genet*, 2011, **5**(3): 199–201.

Henke, J., et al., Application of Y-chromosomal STR haplotypes to forensic genetics. *Croat Med J*, 2001, **42**(3): 292–297.

Heyer, E., et al., Estimating Y chromosome specific microsatellite mutation frequencies using deep rooting pedigrees. *Hum Mol Genet*, 1997, **6**(5): 799–803.

Holtkemper, U., et al., Mutation rates at two human Y-chromosomal microsatellite loci using small pool PCR techniques. *Hum Mol Genet*, 2001, **10**(6): 629–633.

Honda, K., The Ashikaga case of Japan—Y-STR testing used as the exculpatory evidence to free a convicted felon after 17.5 years in prison. *Forensic Sci Int Genet*, 2013, **7**(1): e1–e2.

Huang, D., et al., Y-haplotype screening of local patrilineages followed by autosomal STR typing can detect likely perpetrators in some populations. *J Forensic Sci*, 2011, **56**(5): 1340–1342.

Huang, Y.M., et al., Assessment of application value of 19 autosomal short tandem repeat loci of GoldenEye™ 20A kit in forensic paternity testing. *Int J Legal Med*, 2013, **127**(3): 587–590.

Hurles, M.E. and M.A. Jobling, A singular chromosome. *Nat Genet*, 2003, **34**(3): 246–247.

Jobling, M.A., Y-chromosomal SNP haplotype diversity in forensic analysis. *Forensic Sci Int*, 2001, **118**(2–3): 158–162.

Jobling, M.A., A. Pandya, and C. Tyler-Smith, The Y chromosome in forensic analysis and paternity testing. *Int J Legal Med*, 1997, **110**(3): 118–124.

Jobling, M.A. and C. Tyler-Smith, Fathers and sons: The Y chromosome and human evolution. *Trends Genet*, 1995, **11**(11): 449–456.

Jobling, M.A. and C. Tyler-Smith, New uses for new haplotypes the human Y chromosome, disease and selection. *Trends Genet*, 2000, **16**(8): 356–362.

Jobling, M.A. and C. Tyler-Smith, The human Y chromosome: An evolutionary marker comes of age. *Nat Rev Genet*, 2003, **4**(8): 598–612.

Jobling, M.A., et al., Y-chromosome-specific microsatellite mutation rates re-examined using a minisatellite, MSY1. *Hum Mol Genet*, 1999, **8**(11): 2117–2120.

Kayser, M. and A. Sajantila, Mutations at Y-STR loci: Implications for paternity testing and forensic analysis. *Forensic Sci Int*, 2001, **118**(2–3): 116–121.

Kayser, M., et al., Evaluation of Y-chromosomal STRs: A multicenter study. *Int J Legal Med*, 1997, **110**(3): 125–133, 141–149.

Kayser, M., et al., A comprehensive survey of human Y-chromosomal microsatellites. *Am J Hum Genet*, 2004, **74**(6): 1183–1197.

Kayser, M., et al., Characteristics and frequency of germ-line mutations at microsatellite loci from the human Y chromosome, as revealed by direct observation in father/son pairs. *Am J Hum Genet*, 2000, **66**(5): 1580–1588.

Krawczak, M., Forensic evaluation of Y-STR haplotype matches: A comment. *Forensic Sci Int*, 2001, **118**(2–3): 114–115.

Krenke, B.E., et al., Validation of a male-specific, 12-locus fluorescent short tandem repeat (STR) multiplex. *Forensic Sci Int*, 2005, **148**(1): 1–14.

Lagoa, A.M., T. Magalhães, and M.F. Pinheiro, Autosomic STR, Y-STR and miniSTR markers evaluation for genetic analysis of fingerprints. *Forensic Sci Int Genet Suppl*, 2008, **1**(1): 435–436.

Lahn, B.T., N.M. Pearson, and K. Jegalian, The human Y chromosome, in the light of evolution. *Nat Rev Genet*, 2001, **2**(3): 207–216.

Laouina, A., et al., Mutation rate at 17 Y-STR loci in “father/son” pairs from Moroccan population. *Leg Med (Tokyo)*, 2013, **15**(5): 269–271.

Lareu, M., et al., The use of the LightCycler for the detection of Y chromosome SNPs. *Forensic Sci Int*, 2001, **118**(2–3): 163–168.

Lim, S.K., et al., Variation of 52 new Y-STR loci in the Y chromosome consortium worldwide panel of 76 diverse individuals. *Int J Legal Med*, 2007, **121**(2): 124–127.

Ma, Y., et al., A Y-chromosomal haplotype with two short tandem repeat mutations. *J Forensic Sci*, 2012, **57**(6): 1630–1633.

Malsom, S., et al., The prevalence of mixed DNA profiles in fingernail samples taken from couples who co-habit using autosomal and Y-STRs. *Forensic Sci Int Genet*, 2009, **3**(2): 57–62.

Marjanović, D., et al., Identification of skeletal remains of communist armed forces victims during and after World War II: Combined Y-chromosome short tandem repeat (STR) and miniSTR approach. *Croat Med J*, 2009, **50**(3): 296–304.

Maybruck, J.L., et al., A comparative analysis of two different sets of Y-chromosome short tandem repeats (Y-STRs) on a common population panel. *Forensic Sci Int Genet*, 2009, **4**(1): 11–20.

Mayntz-Press, K.A. and J. Ballantyne, Performance characteristics of commercial Y-STR multiplex systems. *J Forensic Sci*, 2007, **52**(5): 1025–1034.

Mayntz-Press, K.A., et al., Y-STR profiling in extended interval (≥3 days) postcoital cervicovaginal samples. *J Forensic Sci*, 2008, **53**(2): 342–348.

Mulero, J.J., C.W. Chang, and L.K. Hennessy, Characterization of the N + 3 stutter product in the trinucleotide repeat locus DYS392. *J Forensic Sci*, 2006, **51**(5): 1069–1073.

Naitoh, S., et al., Assignment of Y-chromosomal SNPs found in Japanese population to Y-chromosomal haplogroup tree. *J Hum Genet*, 2013, **58**(4): 195–201.

Nebel, A., et al., Haplogroup-specific deviation from the stepwise mutation model at the microsatellite loci DYS388 and DYS392. *Eur J Hum Genet*, 2001, **9**(1): 22–26.

Niederstatter, H., et al., Separate analysis of DYS385a and b versus conventional DYS385 typing: Is there forensic relevance? *Int J Legal Med*, 2005, **119**(1): 1–9.

Olofsson, J., et al., Evaluation of Y-STR analyses of sperm cell negative vaginal samples. *Forensic Sci Int Genet Suppl*, 2011, **3**(1): e141–e142.

Onofri, V., L. Buscemi, and A. Tagliabracci, Evaluating Y-chromosome STRs mutation rates: A collaborative study of the Ge.F.I.-ISFG Italian group. *Forensic Sci Int Genet Suppl*, 2009, **2**(1): 419–420.

Oz, C., et al., A Y-chromosome STR marker should be added to commercial multiplex STR kits. *J Forensic Sci*, 2008, **53**(4): 858–861.

Paracchini, S., et al., Hierarchical high-throughput SNP genotyping of the human Y chromosome using MALDI-TOF mass spectrometry. *Nucleic Acids Res*, 2002, **30**(6): e27.

Park, M.J., et al., Characterization of deletions in the DYS385 flanking region and null alleles associated with AZFc microdeletions in Koreans. *J Forensic Sci*, 2008, **53**(2): 331–334.

Park, M.J., et al., Y-SNP miniplexes for East Asian Y-chromosomal haplogroup determination in degraded DNA. *Forensic Sci Int Genet*, 2013, **7**(1): 75–81.

Park, M.J., et al., Y-STR analysis of degraded DNA using reduced-size amplicons. *Int J Legal Med*, 2007, **121**(2): 152–157.

Parson, W., et al., When autosomal short tandem repeats fail: Optimized primer and reaction design for Y-chromosome short tandem repeat analysis in forensic casework. *Croat Med J*, 2001, **42**(3): 285–287.

Parson, W., et al., Improved specificity of Y-STR typing in DNA mixture samples. *Int J Legal Med*, 2003, **117**(2): 109–114.

Parson, W., et al., Y-STR analysis on DNA mixture samples—Results of a collaborative project of the ENFSI DNA working group. *Forensic Sci Int Genet*, 2008, **2**(3): 238–242.

Pascali, V.L., M. Dobosz, and B. Brinkmann, Coordinating Y-chromosomal STR research for the courts. *Int J Legal Med*, 1999, **112**(1): 1.

Prinz, M. and M. Sansone, Y chromosome-specific short tandem repeats in forensic casework. *Croat Med J*, 2001, **42**(3): 288–291.

Prinz, M., et al., Multiplexing of Y chromosome specific STRs and performance for mixed samples. *Forensic Sci Int*, 1997, **85**(3): 209–218.

Prinz, M., et al., Validation and casework application of a Y chromosome specific STR multiplex. *Forensic Sci Int*, 2001, **120**(3): 177–188.

Raina, A., et al., Misinterpretation of results in medico-legal cases due to microdeletion in the Y-chromosome. *Mol Cell Probes*, 2010, **24**(6): 418–420.

Ravid-Amir, O. and S. Rosset, Maximum likelihood estimation of locus-specific mutation rates in Y-chromosome short tandem repeats. *Bioinformatics*, 2010, **26**(18): i440–i445.

Redd, A.J., S.L. Clifford, and M. Stoneking, Multiplex DNA typing of short-tandem-repeat loci on the Y chromosome. *Biol Chem*, 1997, **378**(8): 923–927.

Redd, A.J., et al., Forensic value of 14 novel STRs on the human Y chromosome. *Forensic Sci Int*, 2002, **130**(2–3): 97–111.

Rodig, H., et al., Evaluation of haplotype discrimination capacity of 35 Y-chromosomal short tandem repeat loci. *Forensic Sci Int*, 2008, **174**(2–3): 182–188.

Roewer, L., Y chromosome STR typing in crime casework. *Forensic Sci Med Pathol*, 2009, **5**(2): 77–84.

Roewer, L. and M. Geppert, Interpretation guidelines of a standard Y-chromosome STR 17-plex PCR-CE assay for crime casework. *Methods Mol Biol*, 2012, **830**: 43–56.

Roewer, L., et al., A new method for the evaluation of matches in non-recombining genomes: Application to Y-chromosomal short tandem repeat (STR) haplotypes in European males. *Forensic Sci Int*, 2000, **114**(1): 31–43.

Roewer, L., et al., Online reference database of European Y-chromosomal short tandem repeat (STR) haplotypes. *Forensic Sci Int*, 2001, **118**(2–3): 106–113.

Rolf, B., et al., Paternity testing using Y-STR haplotypes: Assigning a probability for paternity in cases of mutations. *Int J Legal Med*, 2001, **115**(1): 12–15.

Rozen, S., et al., Abundant gene conversion between arms of palindromes in human and ape Y chromosomes. *Nature*, 2003, **423**(6942): 873–876.

Sanchez, J.J., et al., Multiplex PCR and minisequencing of SNPs—A model with 35 Y chromosome SNPs. *Forensic Sci Int*, 2003, **137**(1): 74–84.

Sanchez-Diz, P., et al., Results of the GEP-ISFG collaborative study on two Y-STRs tetraplexes: GEPY I (DYS461, GATA C4, DYS437 and DYS438) and GEPY II (DYS460, GATA A10, GATA H4 and DYS439). *Forensic Sci Int*, 2003, **135**(2): 158–162.

Santos, F.R., N.O. Bianchi, and S.D. Pena, Worldwide distribution of human Y-chromosome haplotypes. *Genome Res*, 1996, **6**(7): 601–611.

Santos, F.R., S.D. Pena, and J.T. Epplen, Genetic and population study of a Y-linked tetranucleotide repeat DNA polymorphism with a simple non-isotopic technique. *Hum Genet*, 1993, **90**(6): 655–656.

Schneider, P.M., et al., Results of collaborative study regarding the standardization of the Y-linked STR system DYS385 by the European DNA Profiling (EDNAP) group. *Forensic Sci Int*, 1999, **102**(2–3): 159–165.

Schoske, R., et al., High-throughput Y-STR typing of U.S. populations with 27 regions of the Y chromosome using two multiplex PCR assays. *Forensic Sci Int*, 2004, **139**(2–3): 107–121.

Schoske, R., et al., Multiplex PCR design strategy used for the simultaneous amplification of 10 Y chromosome short tandem repeat (STR) loci. *Anal Bioanal Chem*, 2003, **375**(3): 333–343.

Seo, Y., et al., A method for genotyping Y chromosome-linked DYS385a and DYS385b loci. *Leg Med (Tokyo)*, 2003, **5**(4): 228–232.

Sibille, I., et al., Y-STR DNA amplification as biological evidence in sexually assaulted female victims with no cytological detection of spermatozoa. *Forensic Sci Int*, 2002, **125**(2–3): 212–216.

Sinha, S.K., et al., Development and validation of a multiplexed Y-chromosome STR genotyping system, Y-PLEX 6, for forensic casework. *J Forensic Sci*, 2003, **48**(1): 93–103.

Sinha, S.K., et al., Development and validation of the Y-PLEX 5, a Y-chromosome STR genotyping system, for forensic casework. *J Forensic Sci*, 2003, **48**(5): 985–1000.

Skaletsky, H., et al., The male-specific region of the human Y chromosome is a mosaic of discrete sequence classes. *Nature*, 2003, **423**(6942): 825–837.

Sturk, K.A., et al., Evaluation of modified Yfiler™ amplification strategy for compromised samples. *Croat Med J*, 2009, **50**(3): 228–238.

Szibor, R., M. Kayser, and L. Roewer, Identification of the human Y-chromosomal microsatellite locus DYS19 from degraded DNA. *Am J Forensic Med Pathol*, 2000, **21**(3): 252–254.

Thompson, J.M., et al., Developmental validation of the PowerPlex® Y23 System: A single multiplex Y-STR analysis system for casework and database samples. *Forensic Sci Int Genet*, 2013, **7**(2): 240–250.

Tilford, C.A., et al., A physical map of the human Y chromosome. *Nature*, 2001, **409**(6822): 943–945.

Tsuji, A., et al., Personal identification using Y-chromosomal short tandem repeats from bodily fluids mixed with semen. *Am J Forensic Med Pathol*, 2001, **22**(3): 288–291.

Tsukada, K., et al., DNA typing using AmpFlSTR Y-filer for very long-term stored specimens. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S466–S467.

Tsutsumi, H., et al., A case of personal identification due to detection of rare DNA types from seminal stain. *J Oral Sci*, 2009, **51**(4): 645–650.

Underhill, P.A., et al., Y chromosome sequence variation and the history of human populations. *Nat Genet*, 2000, **26**(3): 358–361.

Underhill, P.A., et al., The phylogeography of Y chromosome binary haplotypes and the origins of modern human populations. *Ann Hum Genet*, 2001, **65**(Pt 1): 43–62.

Vallone, P.M. and J.M. Butler, Y-SNP typing of U.S. African American and Caucasian samples using allele-specific hybridization and primer extension. *J Forensic Sci*, 2004, **49**(4): 723–732.

Valverde, L., et al., Improving the analysis of Y-SNP haplogroups by a single highly informative 16 SNP multiplex PCR-minisequencing assay. *Electrophoresis*, 2013, **34**(4): 605–612.

van Oven, M., A. Ralf, and M. Kayser, An efficient multiplex genotyping approach for detecting the major worldwide human Y-chromosome haplogroups. *Int J Legal Med*, 2011, **125**(6): 879–885.

Vermeulen, M., et al., Improving global and regional resolution of male lineage differentiation by simple single-copy Y-chromosomal short tandem repeat polymorphisms. *Forensic Sci Int Genet*, 2009, **3**(4): 205–213.

Wei, W., et al., Exploring of new Y-chromosome SNP loci using Pyrosequencing and the SNaPshot methods. *Int J Legal Med*, 2012, **126**(6): 825–833.

White, P.S., et al., New, male-specific microsatellite markers from the human Y chromosome. *Genomics*, 1999, **57**(3): 433–437.

Willuweit, S., L. Roewer, and International Forensic Y Chromosome User Group, Y chromosome haplotype reference database (YHRD): Update. *Forensic Sci Int Genet*, 2007, **1**(2): 83–87.

Zhivotovsky, L.A., et al., The effective mutation rate at Y chromosome short tandem repeats, with application to human population-divergence time. *Am J Hum Genet*, 2004, **74**(1): 50–61.

Zuccarelli, G., et al., Rapid screening for Native American mitochondrial and Y-chromosome haplogroups detection in routine DNA analysis. *Forensic Sci Int Genet*, 2011, **5**(2): 105–108.

Genetic Population Data of Y Chromosome Haplotyping

Aboukhalid, R., et al., Haplotype frequencies for 17 Y-STR loci (AmpFlSTRY-filer) in a Moroccan population sample. *Forensic Sci Int Genet*, 2010, **4**(3): e73–e74.

Achakzai, N.M., et al., Y-chromosomal STR analysis in the Pashtun population of Southern Afghanistan. *Forensic Sci Int Genet*, 2012, **6**(4): e103–e105.

Alakoc, Y.D., et al., Y-chromosome and autosomal STR diversity in four proximate settlements in Central Anatolia. *Forensic Sci Int Genet*, 2010, **4**(5): e135–e137.

Alam, S., et al., Haplotype diversity of 17 Y-chromosomal STR loci in the Bangladeshi population. *Forensic Sci Int Genet*, 2010, **4**(2): e59–e60.

Ali, N., et al., Announcement of population data: Genetic data for 17 Y-STR AmpFlSTR® Yfiler™ markers from an immigrant Pakistani population in the UK (British Pakistanis). *Forensic Sci Int Genet*, 2013, **7**(2): e40–e42.

Alshamali, F., et al., Local population structure in Arabian Peninsula revealed by Y-STR diversity. *Hum Hered*, 2009, **68**(1): 45–54.

Ambrosio, B., et al., Y-STR genetic diversity in autochthonous Andalusians from Huelva and Granada provinces (Spain). *Forensic Sci Int Genet*, 2012, **6**(2): e66–e71.

Andersen, M.M., P.S. Eriksen, and N. Morling, The discrete Laplace exponential family and estimation of Y-STR haplotype frequencies. *J Theor Biol*, 2013, **329**: 39–51.

Andersen, M.M., et al., Estimating trace-suspect match probabilities for singleton Y-STR haplotypes using coalescent theory. *Forensic Sci Int Genet*, 2013, **7**(2): 264–271.

Baeza, C., et al., Population data for 15 Y-chromosome STRs in a population sample from Quito (Ecuador). *Forensic Sci Int*, 2007, **173**(2–3): 214–219.

Bai, R., et al., Haplotype diversity of 17 Y-STR loci in a Chinese Han population sample from Shanxi Province, Northern China. *Forensic Sci Int Genet*, 2013, **7**(1): 214–216.

Balamurugan, K., et al., Y chromosome STR allelic and haplotype diversity in five ethnic Tamil populations from Tamil Nadu, India. *Leg Med (Tokyo)*, 2010, **12**(5): 265–269.

Bembea, M., et al., Y-chromosome STR haplotype diversity in three ethnically isolated population from North-Western Romania. *Forensic Sci Int Genet*, 2011, **5**(3): e99–e100.

Bento, A.M., et al., Distribution of Y-chromosomal haplotypes in the Central Portuguese population using 17-STRs. *Forensic Sci Int Genet*, 2009, **4**(1): e35–e36.

Bing, L., et al., Population genetics for 17 Y-STR loci(AmpFISTR® Y-filer™) in Luzhou Han ethnic group. *Forensic Sci Int Genet*, 2013, **7**(2): e23–e26.

Borjas, L., et al., Usefulness of 12 Y-STRs for forensic genetics evaluation in two populations from Venezuela. *Leg Med (Tokyo)*, 2008, **10**(2): 107–112.

Brisighelli, F., et al., Patterns of Y-STR variation in Italy. *Forensic Sci Int Genet*, 2012, **6**(6): 834–839.

Budowle, B., et al., Texas population substructure and its impact on estimating the rarity of Y STR haplotypes from DNA evidence. *J Forensic Sci*, 2009, **54**(5): 1016–1021.

Budowle, B., et al., The effects of Asian population substructure on Y STR forensic analyses. *Leg Med (Tokyo)*, 2009, **11**(2): 64–69.

Builes, J.J., et al., Y chromosome STR haplotypes in the Caribbean city of Cartagena (Colombia). *Forensic Sci Int*, 2007, **167**(1): 62–69.

Caine, L.M., M.M. de Pancorbo, and F. Pinheiro, Y-chromosomal STR haplotype diversity in males from Santa Catarina, Brazil. *J Forensic Leg Med*, 2010, **17**(2): 92–95.

Carvalho, M., et al., Paternal and maternal lineages in Guinea-Bissau population. *Forensic Sci Int Genet*, 2011, **5**(2): 114–116.

Chang, Y.M., et al., Haplotype diversity of 16 Y-chromosomal STRs in three main ethnic populations (Malays, Chinese and Indians) in Malaysia. *Forensic Sci Int*, 2007, **167**(1): 70–76.

Cloete, K., et al., Analysis of seventeen Y-chromosome STR loci in the Cape Muslim population of South Africa. *Leg Med (Tokyo)*, 2010, **12**(1): 42–45.

Coble, M.D., C.R. Hill, and J.M. Butler, Haplotype data for 23 Y-chromosome markers in four U.S. population groups. *Forensic Sci Int Genet*, 2013, **7**(3): e66–e68.

Cortellini, V., et al., Y-chromosome polymorphisms and ethnic group—A combined STR and SNP approach in a population sample from northern Italy. *Croat Med J*, 2013, **54**(3): 279–285.

D'Amato, M.E., M. Benjeddou, and S. Davison, Evaluation of 21 Y-STRs for population and forensic studies. *Forensic Sci Int Genet Suppl*, 2009, **2**(1): 446–447.

Davis, C., et al., Y-STR loci diversity in native Alaskan populations. *Int J Legal Med*, 2011, **125**(4): 559–563.

Diaz-Lacava, A., et al., Geostatistical inference of main Y-STR-haplotype groups in Europe. *Forensic Sci Int Genet*, 2011, **5**(2): 91–94.

Diaz-Lacava, A., et al., Spatial assessment of Argentinean genetic admixture with geographical information systems. *Forensic Sci Int Genet*, 2011, **5**(4): 297–302.

Ehler, E., R. Marvan, and D. Vanek, Evaluation of 14 Y-chromosomal short tandem repeat haplotype with focus on DYS449, DYS456, and DYS458: Czech population sample. *Croat Med J*, 2010, **51**(1): 54–60.

Elmrghni, S., et al., Population genetic data for 17 Y STR markers from Benghazi (East Libya). *Forensic Sci Int Genet*, 2012, **6**(2): 224–227.

Ferri, G., et al., Y-STR variation in Albanian populations: Implications on the match probabilities and the genetic legacy of the minority claiming an Egyptian descent. *Int J Legal Med*, 2010, **124**(5): 363–370.

Frank, W.E., H.C. Ralph, and M.A. Tahir, Y chromosome STR haplotypes and allele frequencies in a southern Indian male population. *J Forensic Sci*, 2008, **53**(1): 248–251.

Gayden, T., et al., Y-chromosomal microsatellite diversity in three culturally defined regions of historical Tibet. *Forensic Sci Int Genet*, 2012, **6**(4): 437–446.

Gois, C.C., et al., Genetic population data of 12 STR loci of the PowerPlex Y system in the state of Sao Paulo population (Southeast of Brazil). *Forensic Sci Int*, 2008, **174**(1): 81–86.

Gonzalez-Andrade, F., et al., Y-chromosome STR haplotypes in three different population groups from Ecuador (South America). *J Forensic Sci*, 2008, **53**(2): 512–514.

Gonzalez-Andrade, F., et al., Y-STR variation among ethnic groups from Ecuador: Mestizos, Kichwas, Afro-Ecuadorians and Waoranis. *Forensic Sci Int Genet*, 2009, **3**(3): e83–e91.

Grskovic, B., et al., Population genetic analysis of haplotypes based on 17 short tandem repeat loci on Y chromosome in population sample from eastern Croatia. *Croat Med J*, 2010, **51**(3): 202–208.

Grskovic, B., et al., Genetic polymorphisms of 17 short tandem repeat loci on Y chromosome in central Croatian population. *Forensic Sci Med Pathol*, 2011, **7**(2): 155–161.

Grskovic, B., et al., Population data for 17 short tandem repeat loci on Y chromosome in northern Croatia. *Mol Biol Rep*, 2011, **38**(3): 2203–2209.

Guo, H., et al., Genetic polymorphisms for 17 Y-chromosomal STRs haplotypes in Chinese Hui population. *Leg Med (Tokyo)*, 2008, **10**(3): 163–169.

Haliti, N., et al., Evaluation of population variation at 17 autosomal STR and 16 Y-STR haplotype loci in Croatians. *Forensic Sci Int Genet*, 2009, **3**(4): e137–e138.

Hallenberg, C., et al., Y-chromosome STR haplotypes in males from Greenland. *Forensic Sci Int Genet*, 2009, **3**(4): e145–e146.

Hara, M., et al., Genetic data for 16 Y-chromosomal STR loci in Japanese. *Leg Med (Tokyo)*, 2007, **9**(3): 161–170.

Hashiyada, M., et al., Population genetics of 17 Y-chromosomal STR loci in Japanese. *Forensic Sci Int Genet*, 2008, **2**(4): e69–e70.

He, J. and F. Guo, Population genetics of 17 Y-STR loci in Chinese Manchu population from Liaoning Province, northeast China. *Forensic Sci Int Genet*, 2013, **7**(3): e84–e85.

Hedman, M., et al., Dissecting the Finnish male uniformity: The value of additional Y-STR loci. *Forensic Sci Int Genet*, 2011, **5**(3): 199–201.

Huang, T.Y., et al., Polymorphism of 17 Y-STR loci in Taiwan population. *Forensic Sci Int*, 2008, **174**(2–3): 249–254.

Hwa, H.L., et al., Seventeen Y-chromosomal short tandem repeat haplotypes in seven groups of population living in Taiwan. *Int J Legal Med*, 2010, **124**(4): 295–300.

Hwang, J.H., et al., Haplotypes for 12 Y-chromosomal STR loci in a Korean population (the central region). *Forensic Sci Int*, 2007, **168**(1): 73–84.

Illeperuma, R.J., et al., Haplotype data for 12 Y-chromosome STR loci of Sri Lankans. *Forensic Sci Int Genet*, 2010, **4**(4): e119–e120.

Jakovski, Z., et al., Genetic data for 17 Y-chromosomal STR loci in Macedonians in the Republic of Macedonia. *Forensic Sci Int Genet*, 2011, **5**(4): e108–e111.

Julieta Avila, S., I. Briceno, and A. Gomez, Genetic population analysis of 17 Y-chromosomal STRs in three states (Valle del Cauca, Cauca and Narino) from Southwestern Colombia. *J Forensic Leg Med*, 2009, **16**(4): 204–211.

Kang, L.L., K. Liu, and Y. Ma, Y chromosome STR haplotypes of Tibetan Living Tibet Lassa. *Forensic Sci Int*, 2007, **172**(1): 79–83.

Katsaloulis, P., et al., Genetic population study of 11 Y chromosome STR loci in Greece. *Forensic Sci Int Genet*, 2013, **7**(3): e56–e58.

Kayser, M., et al., Relating two deep-rooted pedigrees from central Germany by high-resolution Y-STR haplotyping. *Forensic Sci Int Genet*, 2007, **1**(2): 125–128.

Kim, S.H., et al., Genetic polymorphisms of 16 Y chromosomal STR loci in Korean population. *Forensic Sci Int Genet*, 2008, **2**(2): e9–e10.

Kim, S.H., et al., Population genetics and mutational events at 6 Y-STRs in Korean population. *Forensic Sci Int Genet*, 2009, **3**(2): e53–e54.

Kim, S.H., et al., Y chromosome homogeneity in the Korean population. *Int J Legal Med*, 2010, **124**(6): 653–657.

Kim, S.H., et al., Forensic genetic data of 6 Y-STR loci: An expanded Korean population database. *Forensic Sci Int Genet*, 2012, **6**(1): e35–e36.

Kovacevic, L., et al., Haplotype data for 23 Y-chromosome markers in a reference sample from Bosnia and Herzegovina. *Croat Med J*, 2013, **54**(3): 286–290.

Kovatsi, L., J.L. Saunier, and J.A. Irwin, Population genetics of Y-chromosome STRs in a population of Northern Greeks. *Forensic Sci Int Genet*, 2009, **4**(1): e21–e22.

Kumagai, R., et al., Haplotype analysis of 17 Y-STR loci in a Japanese population. *Forensic Sci Int*, 2007, **172**(1): 72–78.

Lacau, H., et al., Y-STR profiling in two Afghanistan populations. *Leg Med (Tokyo)*, 2011, **13**(2): 103–108.

Laouina, A., et al., Allele frequencies and population data for 17 Y-STR loci (The AmpFlSTR® Y-filer™) in Casablanca resident population. *Forensic Sci Int Genet*, 2011, **5**(1): e1–e3.

Larmuseau, M.H., et al., Micro-geographic distribution of Y-chromosomal variation in the central-western European region Brabant. *Forensic Sci Int Genet*, 2011, **5**(2): 95–99.

Leat, N., et al., Properties of novel and widely studied Y-STR loci in three South African populations. *Forensic Sci Int*, 2007, **168**(2–3): 154–161.

Lecerf, M., et al., Allele frequencies and haplotypes of eight Y-short tandem repeats in Bantu population living in Central Africa. *Forensic Sci Int*, 2007, **171**(2–3): 212–215.

Lee, H.Y., et al., Haplotypes and mutation analysis of 22 Y-chromosomal STRs in Korean father-son pairs. *Int J Legal Med*, 2007, **121**(2): 128–135.

Lee, J., et al., Y chromosomal STRs haplotypes in two populations from Bolivia. *Leg Med (Tokyo)*, 2007, **9**(1): 43–47.

Lim, S.K., et al., Variation of 52 new Y-STR loci in the Y chromosome consortium worldwide panel of 76 diverse individuals. *Int J Legal Med*, 2007, **121**(2): 124–127.

Ljubkovic, J., et al., Y-chromosomal short tandem repeat haplotypes in southern Croatian male population defined by 17 loci. *Croat Med J*, 2008, **49**(2): 201–206.

Lowery, R.K., et al., Sub-population structure evident in forensic Y-STR profiles from Armenian geographical groups. *Leg Med (Tokyo)*, 2013, **15**(2): 85–90.

Maybruck, J.L., et al., A comparative analysis of two different sets of Y-chromosome short tandem repeats (Y-STRs) on a common population panel. *Forensic Sci Int Genet*, 2009, **4**(1): 11–20.

Melo, M.M., et al., Y-STR haplotypes in three ethnic linguistic groups of Angola population. *Forensic Sci Int Genet*, 2011, **5**(3): e83–e88.

Mendes-Junior, C.T., et al., Y-chromosome STR haplotypes in a sample from Sao Paulo State, southeastern Brazil. *J Forensic Sci*, 2007, **52**(2): 495–497.

Mertens, G., et al., Twelve-locus Y-STR haplotypes in the Flemish population. *J Forensic Sci*, 2007, **52**(3): 755–757.

Mielnik-Sikorska, M., et al., Genetic data from Y chromosome STR and SNP loci in Ukrainian population. *Forensic Sci Int Genet*, 2013, **7**(1): 200–203.

Mizuno, N., et al., 16 Y chromosomal STR haplotypes in Japanese. *Forensic Sci Int*, 2008, **174**(1): 71–76.

Mizuno, N., et al., A forensic method for the simultaneous analysis of biallelic markers identifying Y chromosome haplogroups inferred as having originated in Asia and the Japanese archipelago. *Forensic Sci Int Genet*, 2010, **4**(2): 73–79.

Mršić, G., et al., Croatian national reference Y-STR haplotype database. *Mol Biol Rep*, 2012, **39**(7): 7727–7741.

Muro, T., et al., Simultaneous determination of seven informative Y chromosome SNPs to differentiate East Asian, European, and African populations. *Leg Med (Tokyo)*, 2011, **13**(3): 134–141.

Nagy, M., et al., Searching for the origin of Romanies: Slovakian Romani, Jats of Haryana and Jat Sikhs Y-STR data in comparison with different Romani populations. *Forensic Sci Int*, 2007, **169**(1): 19–26.

Nonaka, I., K. Minaguchi, and N. Takezaki, Y-chromosomal binary haplogroups in the Japanese population and their relationship to 16 Y-STR polymorphisms. *Ann Hum Genet*, 2007, **71**(Pt 4): 480–495.

Nunez, C., et al., Y chromosome haplogroup diversity in a Mestizo population of Nicaragua. *Forensic Sci Int Genet*, 2012, **6**(6): e192–e195.

Onofri, V., et al., Y-chromosome genetic structure in sub-Apennine populations of Central Italy by SNP and STR analysis. *Int J Legal Med*, 2007, **121**(3): 234–237.

Padilla-Gutierrez, J.R., et al., Population data and mutation rate of nine Y-STRs in a mestizo Mexican population from Guadalajara, Jalisco, Mexico. *Leg Med (Tokyo)*, 2008, **10**(6): 319–320.

Palet, L., et al., Y-STR genetic diversity in Moroccans from the Figuig oasis. *Forensic Sci Int Genet*, 2010, **4**(5): e139–e141.

Palha Tde, J., E.M. Rodrigues, and S.E. Dos Santos, Y-chromosomal STR haplotypes in a population from the Amazon region, Brazil. *Forensic Sci Int*, 2007, **166**(2–3): 233–239.

Palha, T., et al., Fourteen short tandem repeat loci Y chromosome haplotypes: Genetic analysis in populations from northern Brazil. *Forensic Sci Int Genet*, 2012, **6**(3): 413–418.

Palha, T.J., E.M. Rodrigues, and S.E. dos Santos, Y-STR haplotypes of Native American populations from the Brazilian Amazon region. *Forensic Sci Int Genet*, 2010, **4**(5): e121–e123.

Palo, J.U., et al., High degree of Y-chromosomal divergence within Finland—Forensic aspects. *Forensic Sci Int Genet*, 2007, **1**(2): 120–124.

Palo, J.U., et al., The effect of number of loci on geographical structuring and forensic applicability of Y-STR data in Finland. *Int J Legal Med*, 2008, **122**(6): 449–456.

Park, S.W., et al., Development of a Y-STR 12-plex PCR system and haplotype analysis in a Korean population. *J Genet*, 2009, **88**(3): 353–358.

Parkin, E.J., et al., Diversity of 26-locus Y-STR haplotypes in a Nepalese population sample: Isolation and drift in the Himalayas. *Forensic Sci Int*, 2007, **166**(2–3): 176–181.

Parvathy, S.N., A. Geetha, and C. Jagannath, Haplotype analysis of the polymorphic 17 YSTR markers in Kerala nontribal populations. *Mol Biol Rep*, 2012, **39**(6): 7049–7059.

Petrejcikova, E., et al., Allele frequencies and population data for 11 Y-chromosome STRs in samples from Eastern Slovakia. *Forensic Sci Int Genet*, 2011, **5**(3): e53–e62.

Piglionica, M., et al., Population data for 17 Y-chromosome STRs in a sample from Apulia (Southern Italy). *Forensic Sci Int Genet*, 2013, **7**(1): e3–e4.

Ploski, R., et al., Homogeneity and distinctiveness of Polish paternal lineages revealed by Y chromosome microsatellite haplotype analysis. *Hum Genet*, 2002, **110**(6): 592–600.

Pokupcic, K., et al., Y-STR genetic diversity of Croatian (Bayash) Roma. *Forensic Sci Int Genet*, 2008, **2**(2): e11–e13.

Pontes, M.L., et al., Allele frequencies and population data for 17 Y-STR loci (AmpFlSTR® Y-filer™) in a Northern Portuguese population sample. *Forensic Sci Int*, 2007, **170**(1): 62–67.

Rafiee, M.R., et al., Analysis of Y-chromosomal short tandem repeat (STR) polymorphism in an Iranian Sadat population. *Genetika*, 2009, **45**(8): 1105–1109.

Rapone, C., et al., Y chromosome haplotypes in central-south Italy: Implication for reference database. *Forensic Sci Int*, 2007, **172**(1): 67–71.

Rebala, K., et al., Forensic analysis of polymorphism and regional stratification of Y-chromosomal microsatellites in Belarus. *Forensic Sci Int Genet*, 2011, **5**(1): e17–e20.

Rebala, K., et al., Y-STR variation among Slavs: Evidence for the Slavic homeland in the middle Dnieper basin. *J Hum Genet*, 2007, **52**(5): 406–414.

Roewer, L., et al., Y-chromosomal STR haplotypes in Kalmyk population samples. *Forensic Sci Int*, 2007, **173**(2–3): 204–209.

Roewer, L., et al., Analysis of Y chromosome STR haplotypes in the European part of Russia reveals high diversities but non-significant genetic distances between populations. *Int J Legal Med*, 2008, **122**(3): 219–223.

Roewer, L., et al., A Y-STR database of Iranian and Azerbaijanian minority populations. *Forensic Sci Int Genet*, 2009, **4**(1): e53–e55.

Romero, R.E., et al., A Colombian Caribbean population study of 16 Y-chromosome STR loci. *Forensic Sci Int Genet*, 2008, **2**(2): e5–e8.

Salvador, J.M., K.A. Tabbada, and M.C. De Ungria, Population data of 10 Y-chromosomal STR loci in Cebu province, Central Visayas (Philippines). *J Forensic Sci*, 2008, **53**(1): 256–258.

Sanchez, C., et al., Haplotype frequencies of 16 Y-chromosome STR loci in the Barcelona metropolitan area population using Y-Filer kit. *Forensic Sci Int*, 2007, **172**(2–3): 211–217.

Schwengber, S.P., et al., Population data of 17 Y-STR loci from Rio Grande do Sul state (South Brazil). *Forensic Sci Int Genet*, 2009, **4**(1): e31–e33.

Seong, K.M., et al., Population genetic polymorphisms of 17 Y-chromosomal STR loci in South Koreans. *Forensic Sci Int Genet*, 2011, **5**(5): e122–e123.

Serin, A., et al., Haplotype frequencies of 17 Y-chromosomal short tandem repeat loci from the Cukurova region of Turkey. *Croat Med J*, 2011, **52**(6): 703–708.

Shi, M., et al., Southwest China Han population data for nine Y-STR loci by multiplex polymerase chain reaction. *J Forensic Sci*, 2007, **52**(1): 228–230.

Shi, M.S., et al., Haplotypes of 20 Y-chromosomal STRs in a population sample from southeast China (Chaoshan area). *Int J Legal Med*, 2007, **121**(6): 455–462.

Shi, M., et al., Population genetics for Y-chromosomal STRs haplotypes of Chinese Tujia ethnic group. *Forensic Sci Int Genet*, 2008, **2**(4): e65–e68.

Shi, M., et al., Haplotype diversity of 22 Y-chromosomal STRs in a southeast China population sample (Chaoshan area). *Forensic Sci Int Genet*, 2009, **3**(2): e45–e47.

Shi, M., et al., Population genetics for Y-chromosomal STRs haplotypes of Chinese Xibe ethnic group. *Forensic Sci Int Genet*, 2011, **5**(5): e119–e121.

Sims, L.M., D. Garvey, and J. Ballantyne, Sub-populations within the major European and African derived haplogroups R1b3 and E3a are differentiated by previously phylogenetically undefined Y-SNPs. *Hum Mutat*, 2007, **28**(1): 97.

Siriboonpiputtana, T., et al., Y-chromosomal STR haplotypes in central Thai population. *Forensic Sci Int Genet*, 2010, **4**(3): e71–e72.

Soltyszewski, I., et al., Y-chromosomal haplotypes for the AmpFlSTR Yfiler PCR amplification kit in a population sample from Central Poland. *Forensic Sci Int*, 2007, **168**(1): 61–67.

Stanciu, F., et al., Population data for Y-chromosome haplotypes defined by 17 STRs in South-East Romania. *Leg Med (Tokyo)*, 2010, **12**(5): 259–264.

Stevanovic, M., et al., Human Y-specific STR haplotypes in population of Serbia and Montenegro. *Forensic Sci Int*, 2007, **171**(2–3): 216–221.

Taylor, D., et al., An investigation of admixture in an Australian Aboriginal Y-chromosome STR database. *Forensic Sci Int Genet*, 2012, **6**(5): 532–538.

Taylor, D.A. and J.M. Henry, Haplotype data for 16 Y-chromosome STR loci in Aboriginal and Caucasian populations in South Australia. *Forensic Sci Int Genet*, 2012, **6**(6): e187–e188.

Thangaraj, K., et al., Y-chromosomal STR haplotypes in two endogamous tribal populations of Karnataka, India. *J Forensic Sci*, 2007, **52**(3): 751–753.

Theves, C., et al., Population genetics of 17 Y-chromosomal STR loci in Yakutia. *Forensic Sci Int Genet*, 2010, **4**(5): e129–e130.

Tian-Xiao, Z., Y. Li, and L. Sheng-Bin, Y-STR haplotypes and the genetic structure from eight Chinese ethnic populations. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S198–S200.

Triki-Fendri, S., et al., Population genetics of 17 Y-STR markers in West Libya (Tripoli region). *Forensic Sci Int Genet*, 2013, **7**(3): e59–e61.

Trynova, E.G., et al., Presentation of 17 Y-chromosomal STRs in the population of the Sverdlovsk region. *Forensic Sci Int Genet*, 2011, **5**(3): e101–e104.

Valverde, L., et al., 17 Y-STR haplotype data for a population sample of residents in the Basque Country. *Forensic Sci Int Genet*, 2012, **6**(4): e109–e111.

Valverde, L., et al., Y-STR variation in the Basque diaspora in the Western USA: Evolutionary and forensic perspectives. *Int J Legal Med*, 2012, **126**(2): 293–298.

Veselinovic, I.S., et al., Allele frequencies and population data for 17 Y-chromosome STR loci in a Serbian population sample from Vojvodina province. *Forensic Sci Int*, 2008, **176**(2–3): e23–e28.

Volgyi, A., et al., Hungarian population data for 11 Y-STR and 49 Y-SNP markers. *Forensic Sci Int Genet*, 2009, **3**(2): e27–e28.

Weng, W., et al., Mutation rates at 16 Y-chromosome STRs in the South China Han population. *Int J Legal Med*, 2013, **127**(2): 369–372.

Willuweit, S., et al., Y-STR frequency surveying method: A critical reappraisal. *Forensic Sci Int Genet*, 2011, **5**(2): 84–90.

Wolanska-Nowak, P., et al., A population data for 17 Y-chromosome STR loci in South Poland population sample—Some DYS458.2 variants uncovered and sequenced. *Forensic Sci Int Genet*, 2009, **4**(1): e43–e44.

Wolfgramm Ede, V., et al., Genetic analysis of 15 autosomal and 12 Y-STR loci in the Espirito Santo State population, Brazil. *Forensic Sci Int Genet*, 2011, **5**(3): e41–e43.

Wozniak, M., et al., Continuity of Y chromosome haplotypes in the population of Southern Poland before and after the Second World War. *Forensic Sci Int Genet*, 2007, **1**(2): 134–140.

Wu, F.C., et al., Y-chromosomal STRs haplotypes in the Taiwanese Paiwan population. *Int J Legal Med*, 2011, **125**(1): 39–43.

Wu, W., et al., Population genetics of 17 Y-STR loci in a large Chinese Han population from Zhejiang Province, Eastern China. *Forensic Sci Int Genet*, 2011, **5**(1): e11–e13.

Yadav, B., A. Raina, and T.D. Dogra, Genetic polymorphisms for 17 Y-chromosomal STR haplotypes in Jammu and Kashmir Saraswat Brahmin population. *Leg Med (Tokyo)*, 2010, **12**(5): 249–255.

Yadav, B., A. Raina, and T.D. Dogra, Haplotype diversity of 17 Y-chromosomal STRs in Saraswat Brahmin community of North India. *Forensic Sci Int Genet*, 2011, **5**(3): e63–e70.

Yanmei, Y., et al., Genetic polymorphism of 11 Y-chromosomal STR loci in Yunnan Han Chinese. *Forensic Sci Int Genet*, 2010, **4**(2): e67–e69.

Yoshida, Y. and S. Kubo, Y-SNP and Y-STR analysis in a Japanese population. *Leg Med (Tokyo)*, 2008, **10**(5): 243–252.

Zahra, N., et al., The analysis of UAE populations using AmpFlSTR® Y Filer™: Identification of novel and null alleles. *Forensic Sci Int Genet Suppl*, 2008, **1**(1): 255–256.

Zastera, J., et al., Assembly of a large Y-STR haplotype database for the Czech population and investigation of its substructure. *Forensic Sci Int Genet*, 2010, **4**(3): e75–e78.

Zhang, D., et al., Haplotypes of six miniY-STR loci in the Han population from Sichuan province and the Zhuang population in Guangxi Zhuang autonomous region. *Forensic Sci Int Genet*, 2009, **3**(2): e49–e51.

Zhang, G.Q., et al., Structure and polymorphism of 16 novel Y-STRs in Chinese Han population. *Genet Mol Res*, 2012, **11**(4): 4487–4500.

Zhang, H., et al., Haplotype of 12 Y-STR loci of the PowerPlex Y-system in Sichuan Han ethnic group in west China. *Forensic Sci Int*, 2008, **175**(2–3): 244–249.

Zhang, Y. and J. Lee, Genetic polymorphism of Y-chromosomal STR loci in South Korean population. *Forensic Sci Int*, 2007, **173**(2–3): 225–230.

Zhang, Y., et al., Population genetics for Y-chromosomal STRs haplotypes of Chinese Korean ethnic group in northeastern China. *Forensic Sci Int*, 2007, **173**(2–3): 197–203.

Zhang, Y., et al., Allele frequencies of 12 Y-chromosomal STRs in Chinese Tuvans in the Altay region. *Forensic Sci Int Genet*, 2013, **7**(1): e7–e8.

Zhang, Y.J., et al., Allele frequencies of DYS19, DYS385, DYS388, DYS389 (I and II), DYS390, DYS391, DYS392, and DYS393 STR loci in a Korean population. *J Forensic Sci*, 2007, **52**(6): 1424–1425.

Zhang, Y.L., et al., Genetic diversity of Y-chromosome microsatellites in the Fujian Han and the Sichuan Han populations of China. *Anthropol Anz*, 2007, **65**(1): 1–14.

Zhu, B., et al., Genetic analysis of 17 Y-chromosomal STRs haplotypes of Chinese Tibetan ethnic group residing in Qinghai province of China. *Forensic Sci Int*, 2008, **175**(2–3): 238–243.

Zhu, B., et al., Population genetic polymorphisms for 17 Y-chromosomal STRs haplotypes of Chinese Salar ethnic minority group. *Leg Med (Tokyo)*, 2007, **9**(4): 203–209.

X Chromosome Haplotyping

Castaneda, M., et al., Haplotypic blocks of X-linked STRs for forensic cases: Study of recombination and mutation rates. *J Forensic Sci*, 2012, **57**(1): 192–195.

Chen, D.P., et al., Use of X-linked short tandem repeats loci to confirm mutations in parentage caseworks. *Clin Chim Acta*, 2009, **408**(1–2): 29–33.

Diegoli, T.M. and M.D. Coble, Development and characterization of two mini-X chromosomal short tandem repeat multiplexes. *Forensic Sci Int Genet*, 2011, **5**(5): 415–421.

Edelmann, J., et al., Characterisation of the STR markers DXS10146, DXS10134 and DXS10147 located within a 79.1 kb region at Xq28. *Forensic Sci Int Genet*, 2008, **2**(1): 41–46.

Edelmann, J., et al., Validation of six closely linked STRs located in the chromosome X centromere region. *Int J Legal Med*, 2010, **124**(1): 83–87.

Freitas, N.S., et al., X-linked insertion/deletion polymorphisms: Forensic applications of a 33-markers panel. *Int J Legal Med*, 2010, **124**(6): 589–593.

Gusmao, L., et al., Capillary electrophoresis of an X-chromosome STR decaplex for kinship deficiency cases. *Methods Mol Biol*, 2012, **830**: 57–71.

Hering, S., et al., X chromosomal recombination—A family study analysing 39 STR markers in German three-generation pedigrees. *Int J Legal Med*, 2010, **124**(5): 483–491.

Li, C., et al., Development of 11 X-STR loci typing system and genetic analysis in Tibetan and Northern Han populations from China. *Int J Legal Med*, 2011, **125**(5): 753–756.

Li, L., et al., Analysis of 14 highly informative SNP markers on X chromosome by TaqMan SNP genotyping assay. *Forensic Sci Int Genet*, 2010, **4**(5): e145–e148.

Liu, Q.L., D.J. Lu, and H. Zhao, The establishment of a nine X-chromosome short tandem repeat loci multiplex PCR and detection of the polymorphism of these loci. *Chin J Med Genet*, 2009, **26**(6): 664–669.

Liu, Q.L., et al., Development and population study of the 12 X-STR loci multiplexes PCR systems. *Int J Legal Med*, 2012, **126**(4): 665–670.

Liu, Q.L., et al., Development of multiplex PCR system with 15 X-STR loci and genetic analysis in three nationality populations from China. *Electrophoresis*, 2012, **33**(8): 1299–1305.

Nothnagel, M., et al., Collaborative genetic mapping of 12 forensic short tandem repeat (STR) loci on the human X chromosome. *Forensic Sci Int Genet*, 2012, **6**(6): 778–784.

Penna, L.S., et al., Development of two multiplex PCR systems for the analysis of 14 X-chromosomal STR loci in a southern Brazilian population sample. *Int J Legal Med*, 2012, **126**(2): 327–330.

Pepinski, W., et al., X-chromosomal polymorphism data for the ethnic minority of Polish Tatars and the religious minority of Old Believers residing in northeastern Poland. *Forensic Sci Int Genet*, 2007, **1**(2): 212–214.

Pereira, R., et al., A method for the analysis of 32 X chromosome insertion deletion polymorphisms in a single PCR. *Int J Legal Med*, 2012, **126**(1): 97–105.

Turrina, S., et al., Development and forensic validation of a new multiplex PCR assay with 12 X-chromosomal short tandem repeats. *Forensic Sci Int Genet*, 2007, **1**(2): 201–204.

Zarrabeitia, M.T., et al., Analysis of 10 X-linked tetranucleotide markers in mixed and isolated populations. *Forensic Sci Int Genet*, 2009, **3**(2): 63–66.

Genetic Population Data of X Chromosome Haplotyping

Aler, M., et al., Genetic data of 10 X-STRs in a Spanish population sample. *Forensic Sci Int*, 2007, **173**(2–3): 193–196.

Barbaro, A., et al., Distribution of 8 X-chromosomal STR loci in an Italian population sample (Calabria). *Forensic Sci Int Genet*, 2012, **6**(6): e174–e175.

Becker, D., et al., Population genetic evaluation of eight X-chromosomal short tandem repeat loci using Mentype Argus X-8 PCR amplification kit. *Forensic Sci Int Genet*, 2008, **2**(1): 69–74.

Caine, L.M., et al., Genetic data of a Brazilian population sample (Santa Catarina) using an X-STR decaplex. *J Forensic Leg Med*, 2010, **17**(5): 272–274.

Fracasso, T., et al., An X-STR meiosis study in Kurds and Germans: Allele frequencies and mutation rates. *Int J Legal Med*, 2008, **122**(4): 353–356.

Gao, S., et al., Allele frequencies for 10 X-STR loci in Nu population of Yunnan, China. *Leg Med (Tokyo)*, 2007, **9**(5): 284–286.

Gomes, I., et al., Analysis of 10 X-STRs in three African populations. *Forensic Sci Int Genet*, 2007, **1**(2): 208–211.

Gomes, I., et al., The Karimojong from Uganda: Genetic characterization using an X-STR decaplex system. *Forensic Sci Int Genet*, 2009, **3**(4): e127–e128.

Grskovic, B., et al., Analysis of 8 X-chromosomal markers in the population of central Croatia. *Croat Med J*, 2013, **54**(3): 238–247.

Hedman, M., J.U. Palo, and A. Sajantila, X-STR diversity patterns in the Finnish and the Somali population. *Forensic Sci Int Genet*, 2009, **3**(3): 173–178.

Horvath, G., et al., A genetic study of 12 X-STR loci in the Hungarian population. *Forensic Sci Int Genet*, 2012, **6**(1): e46–e47.

Hou, Q.F., B. Yu, and S.B. Li, Genetic polymorphisms of nine X-STR loci in four population groups from Inner Mongolia, China. *Genom Proteom Bioinformat*, 2007, **5**(1): 59–65.

Hwa, H.L., et al., Genetic analysis of eight population groups living in Taiwan using a 13 X-chromosomal STR loci multiplex system. *Int J Legal Med*, 2011, **125**(1): 33–37.

Hwa, H.L., et al., Thirteen X-chromosomal short tandem repeat loci multiplex data from Taiwanese. *Int J Legal Med*, 2009, **123**(3): 263–269.

Illescas, M.J., et al., Population genetic data for 10 X-STR loci in autochthonous Basques from Navarre (Spain). *Forensic Sci Int Genet*, 2012, **6**(5): e146–e148.

Inturri, S., et al., Linkage and linkage disequilibrium analysis of X-STRs in Italian families. *Forensic Sci Int Genet*, 2011, **5**(2): 152–154.

Laouina, A., et al., Genetic data of X-chromosomal STRs in a Moroccan population sample (Casablanca) using an X-STR decaplex. *Forensic Sci Int Genet*, 2013, **7**(3): e90–e92.

Li, C., et al., Genetic analysis of the 11 X-STR loci in Uigur population from China. *Forensic Sci Int Genet*, 2012, **6**(5): e139–e140.

Li, H., et al., A multiplex PCR for 4 X chromosome STR markers and population data from Beijing Han ethnic group. *Leg Med (Tokyo)*, 2009, **11**(5): 248–250.

Lim, E.J., et al., Genetic polymorphism and haplotype analysis of 4 tightly linked X-STR duos in Koreans. *Croat Med J*, 2009, **50**(3): 305–312.

Liu, Q.L., et al., Development of the nine X-STR loci typing system and genetic analysis in three nationality populations from China. *Int J Legal Med*, 2011, **125**(1): 51–58.

Luczak, S., et al., Diversity of 15 human X chromosome microsatellite loci in Polish population. *Forensic Sci Int Genet*, 2011, **5**(3): e71–e77.

Luo, H.B., et al., Characteristics of eight X-STR loci for forensic purposes in the Chinese population. *Int J Legal Med*, 2011, **125**(1): 127–131.

Martins, J.A., et al., X-chromosome genetic variation in Sao Paulo State (Brazil) population. *Ann Hum Biol*, 2010, **37**(4): 598–603.

Mukerjee, S., et al., Genetic variation of 10 X chromosomal STR loci in Indian population. *Int J Legal Med*, 2010, **124**(4): 327–330.

Mukerjee, S., et al., Population genetic data for 11 X-STR loci in eleven populations of India. *Leg Med (Tokyo)*, 2012, **14**(3): 163–165.

Nadeem, A., et al., Development of pentaplex PCR and genetic analysis of X chromosomal STRs in Punjabi population of Pakistan. *Mol Biol Rep*, 2009, **36**(7): 1671–1675.

Nakamura, Y. and K. Minaguchi, Sixteen X-chromosomal STRs in two octaplex PCRs in Japanese population and development of 15-locus multiplex PCR system. *Int J Legal Med*, 2010, **124**(5): 405–414.

Nakamura, Y., et al., Multiplex PCR for 18 X-chromosomal STRs in Japanese population. *Leg Med (Tokyo)*, 2013, **15**(3): 164–170.

Nishi, T., et al., Application of a novel multiplex polymerase chain reaction system for 12 X-chromosomal short tandem repeats to a Japanese population study. *Leg Med (Tokyo)*, 2013, **15**(1): 43–46.

Pereira, V., et al., Study of 25 X-chromosome SNPs in the Portuguese. *Forensic Sci Int Genet*, 2011, **5**(4): 336–338.

Poetsch, M., et al., Allele frequencies of 11 X-chromosomal loci in a population sample from Ghana. *Int J Legal Med*, 2009, **123**(1): 81–83.

Poetsch, M., et al., Allele frequencies of 11 X-chromosomal loci of two population samples from Africa. *Int J Legal Med*, 2011, **125**(2): 307–314.

Ribeiro Rodrigues, E.M., et al., A multiplex PCR for 11 X chromosome STR markers and population data from a Brazilian Amazon region. *Forensic Sci Int Genet*, 2008, **2**(2): 154–158.

Ribeiro-Rodrigues, E.M., et al., Extensive survey of 12 X-STRs reveals genetic heterogeneity among Brazilian populations. *Int J Legal Med*, 2011, **125**(3): 445–452.

Samejima, M., Y. Nakamura, and K. Minaguchi, Population genetic study of six closely linked groups of X-STRs in a Japanese population. *Int J Legal Med*, 2011, **125**(6): 895–900.

Samejima, M., et al., Genetic study of 12 X-STRs in Malay population living in and around Kuala Lumpur using Investigator Argus X-12 kit. *Int J Legal Med*, 2012, **126**(4): 677–683.

Sim, J.E., et al., Population genetic study of four closely-linked X-STR trios in Koreans. *Mol Biol Rep*, 2010, **37**(1): 333–337.

Sun, R., et al., Genetic polymorphisms of 10 X-STR among four ethnic populations in northwest of China. *Mol Biol Rep*, 2012, **39**(4): 4077–4081.

Tariq, M.A., et al., Allele frequency distribution of 13 X-chromosomal STR loci in Pakistani population. *Int J Legal Med*, 2008, **122**(6): 525–528.

Tie, J., S. Uchigasaki, and S. Oshida, Genetic polymorphisms of eight X-chromosomal STR loci in the population of Japanese. *Forensic Sci Int Genet*, 2010, **4**(4): e105–e108.

Tillmar, A.O., et al., Analysis of linkage and linkage disequilibrium for eight X-STR markers. *Forensic Sci Int Genet*, 2008, **3**(1): 37–41.

Tomas, C., et al., X-chromosome SNP analyses in 11 human Mediterranean populations show a high overall genetic homogeneity except in north-west Africans (Moroccans). *BMC Evol Biol*, 2008, **8**: 75.

Uchigasaki, S., J. Tie, and D. Takahashi, Genetic analysis of twelve X-chromosomal STRs in Japanese and Chinese populations. *Mol Biol Rep*, 2013, **40**(4): 3193–3196.

Wu, W., et al., Allele frequencies of seven X-linked STR loci in Chinese Han population from Zhejiang Province. *Forensic Sci Int Genet*, 2009, **4**(1): e41–e42.

Xu, J., et al., Population data of 12 X-chromosomal STR loci in Chinese Han samples from Hebei Province. *Forensic Sci Int Genet*, 2013, **7**(2): e43–e44.

Zalan, A., et al., Hungarian population data of eight X-linked markers in four linkage groups. *Forensic Sci Int*, 2008, **175**(1): 73–78.

Zeng, X., A. Rakha, and S. Li, Genetic polymorphisms of 10 X-chromosome STR loci in Chinese Daur ethnic minority group. *Leg Med (Tokyo)*, 2009, **11**(3): 152–154.

Zeng, X.P., et al., Genetic polymorphisms of twelve X-chromosomal STR loci in Chinese Han population from Guangdong Province. *Forensic Sci Int Genet*, 2011, **5**(4): e114–e116.

Zhang, S., et al., Genetic polymorphisms of 12 X-STR for forensic purposes in Shanghai Han population from China. *Mol Biol Rep*, 2012, **39**(5): 5705–5707.

Zhang, S.H., et al., Genetic polymorphism of eight X-linked STRs of Mentype® Argus X-8 kit in Chinese population from Shanghai. *Forensic Sci Int Genet*, 2011, **5**(1): e21–e24.

Sex Typing for Gender Identification

Blagodatskikh, E.G., et al., Sex determination in biological specimens using the DYS14 marker. *Mol Biol*, 2010, **44**(4): 568–570.

Buel, E., G. Wang, and M. Schwartz, PCR amplification of animal DNA with human X-Y amelogenin primers used in gender determination. *J Forensic Sci*, 1995, **40**(4): 641–644.

Cadenas, A.M., et al., Male amelogenin dropouts: Phylogenetic context, origins and implications. *Forensic Sci Int*, 2007, **166**(2–3): 155–163.

Chang, Y.M., L.A. Burgoyne, and K. Both, Higher failures of amelogenin sex test in an Indian population group. *J Forensic Sci*, 2003, **48**(6): 1309–1313.

Chang, Y.M., et al., A distinct Y-STR haplotype for amelogenin negative males characterized by a large Y(p)11.2 (DYS458-MSY1-AMEL-Y) deletion. *Forensic Sci Int*, 2007, **166**(2–3): 115–120.

Davis, C., et al., A case of amelogenin Y-null: A simple primer binding site mutation or unusual genetic anomaly? *Leg Med (Tokyo)*, 2012, **14**(6): 320–323.

Esteve Codina, A., H. Niederstatter, and W. Parson, "GenderPlex" a PCR multiplex for reliable gender determination of degraded human DNA samples and complex gender constellations. *Int J Legal Med*, 2009, **123**(6): 459–464.

Fincham, A.G., et al., Human developing enamel proteins exhibit a sex-linked dimorphism. *Calcif Tissue Int*, 1991, **48**(4): 288–290.

Frances, F., et al., Amelogenin test: From forensics to quality control in clinical and biochemical genomics. *Clin Chim Acta*, 2007, **386**(1–2): 53–56.

Gibbon, V., et al., Novel methods of molecular sex identification from skeletal tissue using the amelogenin gene. *Forensic Sci Int Genet*, 2009, **3**(2): 74–79.

Graham, E.A.M., Sex determination. *Forensic Sci Med Pathol*, 2006, **2**(4): 283–286.

Haas-Rochholz, H. and G. Weiler, Additional primer sets for an amelogenin gene PCR-based DNA-sex test. *Int J Legal Med*, 1997, **110**(6): 312–315.

Jacot, T.A., et al., TSPY4 is a novel sperm-specific biomarker of semen exposure in human cervicovaginal fluids; potential use in HIV prevention and contraception studies. *Contraception*, 2013, **88**(3): 387–395.

Kashyap, V.K., et al., Deletions in the Y-derived amelogenin gene fragment in the Indian population. *BMC Med Genet*, 2006, **7**: 37.

Kastelic, V., B. Budowle, and K. Drobnic, Validation of SRY marker for forensic casework analysis. *J Forensic Sci*, 2009, **54**(3): 551–555.

Kim, K.Y., et al., A real-time PCR-based amelogenin Y allele dropout assessment model in gender typing of degraded DNA samples. *Int J Legal Med*, 2013, **127**(1): 55–61.

Kumagai, R., et al., DNA analysis of family members with deletion in Yp11.2 region containing amelogenin locus. *Leg Med (Tokyo)*, 2008, **10**(1): 39–42.

Lattanzi, W., et al., A large interstitial deletion encompassing the amelogenin gene on the short arm of the Y chromosome. *Hum Genet*, 2005, **116**(5): 395–401.

Lau, E.C., H.C. Slavkin, and M.L. Snead, Analysis of human enamel genes: Insights into genetic disorders of enamel. *Cleft Palate J*, 1990, **27**(2): 121–130.

Lau, E.C., et al., Human and mouse amelogenin gene loci are on the sex chromosomes. *Genomics*, 1989, **4**(2): 162–168.

Luptáková, L., et al., Sex determination of early medieval individuals through nested PCR using a new primer set in the SRY gene. *Forensic Sci Int*, 2011, **207**(1–3): 1–5.

Ma, Y., et al., Y chromosome interstitial deletion induced Y-STR allele dropout in AMELY-negative individuals. *Int J Legal Med*, 2012, **126**(5): 713–724.

Maciejewska, A. and R. Pawlowski, A rare mutation in the primer binding region of the amelogenin X homologue gene. *Forensic Sci Int Genet*, 2009, **3**(4): 265–267.

Mannucci, A., et al., Forensic application of a rapid and quantitative DNA sex test by amplification of the X-Y homologous gene amelogenin. *Int J Legal Med*, 1994, **106**(4): 190–193.

Mitchell, R.J., et al., An investigation of sequence deletions of amelogenin (AMELY), a Y-chromosome locus commonly used for gender determination. *Ann Hum Biol*, 2006, **33**(2): 227–240.

Morikawaa, T., Y. Yamamoto, and S. Miyaish, A new method for sex determination based on detection of SRY, STS and amelogenin gene regions with simultaneous amplification of their homologous sequences by a multiplex PCR. *Acta Medica Okayama*, 2011, **65**(2): 113–122.

Mukerjee, S., et al., Differential pattern of genetic variability at the DXYS156 locus on homologous regions of X and Y chromosomes in Indian population and its forensic implications. *Int J Legal Med*, 2013, **127**(1): 1–6.

Nakahori, Y., O. Takenaka, and Y. Nakagome, A human X-Y homologous region encodes "amelogenin". *Genomics*, 1991, **9**(2): 264–269.

Ou, X., et al., Null alleles of the X and Y chromosomal amelogenin gene in a Chinese population. *Int J Legal Med*, 2012, **126**(4): 513–518.

Oz, C., et al., A Y-chromosome STR marker should be added to commercial multiplex STR kits. *J Forensic Sci*, 2008, **53**(4): 858–861.

Parton, J., et al., Sex identification of ancient DNA samples using a microfluidic device. *J Archaeol Sci*, 2013, **40**(1): 705–711.

Quincey, D., et al., Difficulties of sex determination from forensic bone degraded DNA: A comparison of three methods. *Sci Justice*, 2013, **53**(3): 253–260.

Roffey, P.E., C.I. Eckhoff, and J.L. Kuhl, A rare mutation in the amelogenin gene and its potential investigative ramifications. *J Forensic Sci*, 2000, **45**(5): 1016–1019.

Sire, J.Y., S. Delgado, and M. Girondot, The amelogenin story: Origin and evolution. *Eur J Oral Sci*, 2006, **114**(Suppl 1): 64–77; discussion 93–95, 379–380.

Snead, M.L., et al., Of mice and men: Anatomy of the amelogenin gene. *Connect Tissue Res*, 1989, **22**(1–4): 101–109.

Steinlechner, M., et al., Rare failures in the amelogenin sex test. *Int J Legal Med*, 2002, **116**(2): 117–120.

Takayama, T., et al., Determination of deleted regions from Yp11.2 of an amelogenin negative male. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S578–S580.

Thangaraj, K., A.G. Reddy, and L. Singh, Is the amelogenin gene reliable for gender identification in forensic casework and prenatal diagnosis? *Int J Legal Med*, 2002, **116**(2): 121–123.

Tomas, C., et al., Typing of 48 autosomal SNPs and amelogenin with GenPlex SNP genotyping system in forensic genetics. *Forensic Sci Int Genet*, 2008, **3**(1): 1–6.

Tozzo, P., et al., Deletion of amelogenin Y-locus in forensics: Literature revision and description of a novel method for sex confirmation. *J Forensic Leg Med*, 2013, **20**(5): 387–391.

Turrina, S., G. Filippini, and D. De Leo, Evaluation of deleted region from Yp11.2 of two amelogenin negative related males. *Forensic Sci Int Genet Suppl*, 2009, **2**(1): 240–241.

Umeno, M., et al., A rapid and simple system of detecting deletions on the Y chromosome related with male infertility using multiplex PCR. *J Med Invest*, 2006, **53**(1–2): 147–152.

von Wurmb-Schwark, N., H. Bosinski, and S. Ritz-Timme, What do the X and Y chromosomes tell us about sex and gender in forensic case analysis? *J Forensic Leg Med*, 2007, **14**(1): 27–30.

22

Single Nucleotide Polymorphism Profiling

22.1 Basic Characteristics of SNPs

Human genomes contain sequence polymorphisms, which are the variations in nucleotide sequences among individuals. One type of sequence polymorphism is called *single-nucleotide polymorphism* (*SNP*). An SNP constitutes a single-base-pair change originating from a spontaneous mutation that can be a base substitution, insertion, or deletion at a single site. An estimated 10 million SNPs may exist in the human genome, and among them, over a million SNPs have been identified. Thus, SNPs are the most frequent form of DNA polymorphism observed in humans. Most SNPs appear in noncoding regions and some SNPs are found in coding regions of genes (Figure 22.1).

The vast majority of SNPs are biallelic, although very rare triallelic and tetraallelic SNPs also exist. If an SNP originating from a spontaneous mutation occurs in the germ line, it can be inherited by offspring and can spread in the human population. As a result, both the wild type (the typical form of an allele occurring in nature) and a mutant allele are produced. This type of SNP is referred to as a biallelic SNP. Subsequently, a third mutation, a very rare event, may occur at the same nucleotide site. This SNP has a wild type and two different mutant alleles, which results in a triallelic SNP. It is also possible that a triallelic SNP is created by introducing two of the mutations simultaneously at a single site, which is also a very rare event.

Generally speaking, there are a number of advantages to utilizing SNP loci as markers for forensic applications. First, SNPs are abundant within the human genome; therefore, a sufficient number of SNP loci that are suitable for human identification can be selected. Second, in SNP analysis, amplified fragments (amplicons) are usually 50–100 base pairs in length and are smaller than that in short tandem repeat (STR) analysis (Chapter 20). Therefore, SNP profiling can be more useful than STR for analyzing degraded DNA samples in which genomic DNA is fragmented (Section 20.5.1). Third, SNP loci have lower mutation rates than STRs and are, therefore, useful for specialized human identification such as paternity testing. Lastly, it is possible to achieve high-throughput SNP analysis by utilizing multiplex SNP assays, which are amendable for automation.

The application of SNPs for forensic DNA analysis also has some disadvantages, in that SNP loci are not as polymorphic as STR loci. It is estimated that the analysis of 50–60 SNP loci is needed to achieve a similar level of population match probability (P_m—the lower the P_m, the less likely a match occurs between two randomly chosen individuals; see Chapter 25) using 13



Figure 22.1 SNPs fall into several classes. Most reside in the noncoding regions of DNA and are designated as noncoding SNPs (ncSNPs). A subset of ncSNPs can also be found in introns. SNPs residing in exons are further divided into two types: The synonymous type (synSNP) is an exonic SNP that does not change the amino acid composition of the encoded polypeptide. Conversely, a nonsynonymous type (nsSNP) changes the encoded amino acid. SNPs in the promoter regions of the genome are known as promoter SNPs (pSNPs). Arrow: transcription start site. (© Richard C. Li.)

STR loci in CODIS. Moreover, most SNPs are biallelic; therefore, it is difficult to resolve mixed DNA profiles when a shared common allele exists in a mixture of more than one individual. Furthermore, most DNA databases contain STR profiles instead of SNP profiles, which means that it is not possible to carry out a database search for a matching SNP profile in cases where no suspect has yet been identified.

22.2 Forensic Applications of SNP Profiling

22.2.1 *HLA-DQA1* Locus

The first use of SNP-based profiling for forensic application involved sequence polymorphisms at the *HLA-DQA1* locus (formerly called the DQα locus). The *HLA-DQA1* gene is a member of the human leukocyte antigen (HLA) family, which contains a large number of genes involved in the immune response in humans. The *HLA-DQA1* locus is located within human HLA gene clusters on chromosome 6. The region tested for forensic use is highly polymorphic and is located at the second exon of the gene (Table 22.1).

22.2.1.1 DQα AmpliType and Polymarker Assays

The SNP profiling of the *HLA-DQA1* locus was carried out using the DQα AmpliType® kit. It was the first commercial kit, developed in the late 1980s by Cetus Corporation in Emeryville, CA. The *HLA-DQA1* panel can distinguish the following: alleles 1 (subtyped as 1.1, 1.2, or 1.3), 2, 3, and 4 (subtyped as 4.1 and 4.2/4.3, in which the 4.2 and 4.3 alleles are combined and cannot be distinguished). Therefore, a total of 28 possible genotypes from combinations of these alleles can be distinguished. Although the P_m of this SNP profiling is high (approximately 5×10^{-2}), it is useful as a preliminary test to quickly exclude suspects.

In addition to the *HLA-DQA1* locus, five additional loci—*LDLR, GYPA, HBGG,* D7S8, and *GC*—were utilized for forensic application in 1993 (Table 22.1). These loci were included in the second generation of the kit known as the AmpliType® PM PCR amplification and typing kit (also known as Polymarker), manufactured by Perkin-Elmer (Norwalk, CT). It consisted of one panel for the testing of *HLA-DQAl* and another panel for an additional five loci (Figure 22.2). Among these five additional loci, *LDLR, GYPA*, and D7S8 each have two alleles (designated

Table 22.1 Chromosomal Locations of SNP Loci Used in AmpliType® PM PCR Amplification and Typing Kit

Locus	Gene Product	Chromosome Location	Number of Alleles	Further Reading
HLA-DQA1	HLA-DQA1	6p21.3	7	Gyllensten and Erlich (1988)
LDLR	Low-density lipoprotein receptor	19p 13.1-13.3	2	Yamamoto et al. (1984)
GYPA	Glycophorin A	4q28-31	2	Siebert and Fukuda (1987)
HBGG	Hemoglobin G gammaglobin	11 p 15.5	3	Slightom et al. (1980)
D7S8	Anonymous	7q22-31.1	2	Horn et al. (1990)
GC	Group-specific component	4q11-13	3	Yang et al. (1985)



Figure 22.2 Panels of immobilized probes in the Polymarker kit. Top: *HLA-DQA1*. Bottom: additional five loci (*LDLR, GYPA, HBGG*, D7S8, and *GC*). C and S represent threshold control dots. (© Richard C. Li.)

A and B), while *HBGG* and *GC* each have three alleles (A, B, and C). As a result, the P_m of the Polymarker panels decreased to 10^{-4}.

The DNA profiles of the Polymarker system have been accepted in US courts. The Polymarker system has a number of advantages, particularly compared to variable number tandem repeat analysis (VNTR; see Chapter 19). First, the Polymarker system is a PCR-based method and is capable of analyzing a small amount of DNA sample (approximately 2 ng per analysis). Therefore, it is more sensitive than the method used in VNTR analysis. Second, the Polymarker system is an SNP assay with short amplicon sizes and, therefore, can analyze degraded DNA samples, which is not possible in VNTR analysis. Third, the Polymarker system is more rapid and less laborious than VNTR analysis. Lastly, the amplicon sizes of alleles at a given locus have identical lengths and, therefore, this assay does not exhibit preferential amplification as in amplified fragment length polymorphism (Chapter 19). However, the Polymarker system has its limitations compared to VNTR analysis. For example, compared to the VNTR analysis, the P_m of the Polymarker system is high, resulting in poor discrimination power in the comparison of two DNA profiles. Therefore, the Polymarker system is merely useful for excluding a suspect. Moreover, the SNP loci utilized in the Polymarker system are less polymorphic than VNTR loci. The limited number of alleles per SNP locus makes identifying the components of mixtures more difficult than with VNTR analysis in situations when contributors of a mixture sample share common alleles. For these reasons, the Polymarker system was replaced by STR profiling in the late 1990s.

22.2.1.2 Allele-Specific Oligonucleotide Hybridization

Both DQα AmpliType® and Polymarker kits utilize the *allele-specific oligonucleotide (ASO) hybridization* technique. This technique analyzes single-nucleotide variations, such as SNPs, at a given locus. It is based on the principle that ASO probes, usually 14–17 bases in length, hybridize to their complementary DNA sequences to distinguish known polymorphic alleles. ASO probes for multiple alleles at several loci can be arranged on the same panel to establish the presence or absence of specific alleles in PCR-amplified fragments of a DNA sample (Figure 22.3). Thus, the genotypes can be determined.

In the DQα AmpliType® and Polymarker kits, the oligonucleotides representing different alleles are immobilized to a solid matrix consisting of nylon membrane strips. Each immobilized probe at a particular site on the membrane is utilized to detect corresponding SNPs. Since the probe rather than the target DNA (as with regular blot format; see Chapter 9) is immobilized to the solid phase, the configuration used here is known as a *reverse blot* format.

The regions of the DNA in question are amplified by PCR. One of each pair of the primers is conjugated with biotin at the 5′ end (Figure 22.4). Thus, the amplicons are biotinylated for purposes of detection. This kit established multiplexing of a six-locus system, allowing simultaneous amplification of the *HLA-DQA1* locus along with *LDLR, GYPA, HBGG*, D7S8, and *GC* in



Figure 22.3 Hybridization with ASO. Two probes are incubated with the target DNA containing the SNP. Only the perfectly matched probe–target DNA can hybridize under optimal conditions.



Figure 22.4 Amplification of DNA using biotinylated primers. The biotin is conjugated at the 5′ end of the primer. The amplified products are biotinylated. (© Richard C. Li.)

a single reaction for each sample. Following the denaturation of the PCR product to separate the two complementary DNA strands of the amplicons, the biotinylated strands are hybridized to the immobilized probes. Hybridization and washing conditions are established to ensure proper hybridization of the ASO probe and its target sequence. Unbound amplicons are washed away.

The presence of a PCR product bound to a specific probe can be detected by a colorimetric detection system (Figure 22.5). Since the amplicons are biotinylated, a horseradish peroxidase–conjugated streptavidin complex is utilized to bind to the biotinylated amplicons. The horseradish peroxidase then catalyzes the oxidation reaction of the colorless substrate, tetramethyl benzidine (TMB), into a blue precipitate at a designated location on the membrane strip, allowing the genotype of the sample to be determined (Figures 22.6 and 22.7).

The kit uses a threshold control (C dot in the *HLA-DQA1* panel and S dot in the panel of the other five loci) to distinguish between signal and background noise and to determine whether a


Biotinylated amplicon
Immobilized probe
Membrane
(a)
HRP
SA
Biotinylated amplicon
Immobilized probe
Membrane
(b)
TMB
(colorless)
Blue
precipitate
HRP
SA
Biotinylated amplicon
Immobilized probe
Membrane
(c)

Figure 22.5 Reverse blot assay. (a) The probe is immobilized onto a solid-phase membrane and hybridized with a biotinylated PCR product having the target sequence. (b) The detection of hybridization is carried out by streptavidin (SA) and horseradish peroxidase (HRP) conjugate. (c) Colorimetric reaction is catalyzed by HRP using TMB as a substrate. (© Richard C. Li.)


1
2
3
4
C
1.1
1.2 1.3 4
1.3
All but 1.3
4.1
4.2 4.3
DQA1
1.1/1.1
1.2/1.2
1.3/1.3
2/2
3/3
4.1/4.1
(4.2/4.3)/(4.2/4.3)

Figure 22.6 DNA typing of homozygous alleles at the *HLA-DQA1* locus using the reverse blot assay (Polymarker kit). The genotype of each sample is noted on the right. (© Richard C. Li.)


1
2
3
4
C
1.1
1.2 1.3 4
1.3
All but 1.3
4.1
4.2 4.3
DQA1
1.2/3
1.1/2
1.3/3
1.2/4.1
3/4.1
3/(4.2/4/3)

Figure 22.7 DNA typing of heterozygous alleles at the *HLA-DQA1* locus using the reverse blot assay (Polymarker kit). The representative genotypes of the samples are noted on the right. (© Richard C. Li.)

sufficient amount of DNA has been amplified to detect all the alleles present in a sample. If the signal intensities of allele dots are greater than or equal to the threshold control, the alleles are considered true. If the allele dots are less intense than the threshold control, they are considered inconclusive for the determination of full genotypes because an allele may not have been detected due to a low level of DNA template.

22.2.2 Current and Potential Applications of SNP Analysis

22.2.2.1 Application of SNP Analysis for Forensic Identification

The applications of SNP analysis for forensic human identification are summarized in Table 22.2. Autosomal SNP panels can be used for the most common types of forensic testing, including analysis of degraded DNA samples. The SNP panels for mitochondrial DNA (mtDNA) profiling are useful for identifying human remains by comparing the DNA profiles in question to those of potential relatives. This approach may serve as an alternative method to the DNA sequencing method of mtDNA analysis, which is time-consuming and laborious. SNP loci on the Y chromosome are also potentially useful markers for paternity testing because of low mutation rates. SNP loci such as ancestry informative markers (AIM) can be used to determine the ethnic origins of questioned samples to generate leads for investigations.

Table 22.2 Examples of Forensic Applications of SNP Profiling

Testing	Candidate SNP Loci	Application	Further Reading
Identity	Autosomal SNPs	Human identification	Kidd et al. (2006); Sanchez et al. (2006)
		Human identification via degraded DNA	Budowle (2004)
	mtDNA SNPs	Human identification	Grignani et al. (2006)
	Y chromosome SNPs	Paternity testing	Hammer et al. (2006)
Biogeographical origin	Ancestry informative markers (AIMs)	Ethnic group identification	Frudakis et al. (2003); Shriver and Kittles (2004)
Physical characteristics	*MC1R* (melanocortin 1 receptor gene)	Hair color identification (investigative lead)	Grimes et al. (2001)
	P (gene has role in pigmentation)	Eye color identification (investigative lead)	Rebbeck et al. (2002)
Pathology	*KCNH2* (cardiac potassium channel gene)	Determining cause of sudden death from cardiac arrhythmia long QT syndrome	Lunetta et al. (2002)
	SCN5A (encodes cardiac sodium channel gene)	Determining cause of sudden death from cardiac arrhythmia long QT syndrome	Burke et al. (2005)
Toxicology	*CYP2C19*, *CYP2D6*, *CYP3A4*, *CYP2E1* (drug metabolizing enzyme genes)	Investigation of drug overdose (including death)	Kupiec et al. (2006)

22.2.2.2 Potential Applications of SNPs for Phenotyping

One potential application of SNP analysis is in determining phenotypic information, also known as *phenotyping* (Table 22.2). The relevant SNP loci are usually *nonsynonymous SNPs* (*nsSNPs*); they reside in the exon and change the encoded amino acid, which leads to an altered phenotype. Phenotyping of a questioned sample can reveal physical characteristics of an individual, such as hair and eye color, to provide leads for investigations. A number of SNPs residing within the melanocortin 1 receptor gene (*MC1R*) are associated with red hair, fair skin, and freckles, while SNPs residing within the *P* gene, which play a role in pigmentation, are associated with eye color variations.

Phenotyping can also be employed in the area of forensic pathology. Cardiac arrhythmia long QT syndrome (LQTS) can cause sudden death. A number of LQTS-associated SNPs—for example, SNPs in *KCNH2* and *SCN5A* genes—have been shown to correlate to such deaths. Thus, these SNPs are potentially useful for investigating the causes of death. Finally, phenotyping also has applications in forensic toxicology. A number of SNPs in genes, such as *CYP2D6*, that are responsible for metabolizing drugs can serve as potential markers for postmortem investigations of drug-overdose cases.

22.3 SNP Techniques

Over the years, various techniques of SNP analysis have been developed and can be divided into several groups based on the mechanisms used: allele-specific hybridization, primer extension, oligonucleotide ligation, and invasive cleavage. In *allele-specific hybridization*, allele discrimination is based on an optimal condition allowing only the perfectly matched probe–target hybridization to form. *Primer extension* methods are based on the ability of DNA polymerase to incorporate specific deoxynucleotides (dNTPs) complementary to the sequence of the template DNA. *Allele-specific oligonucleotide ligation* is based on the condition that only the allelic probe perfectly matched to the target is ligated. In the *invasive cleavage* method, allelic discrimination is based on DNA sequence-specific cleavage by endonucleases. A number of detection methods can be utilized in SNP analysis, such as the measurements of fluorescence, luminescence, and molecular mass. Most assays are carried out in solutions or on solid matrices such as glass slides, chips, or beads. Table 22.3 summarizes the representative assays for SNP typing.

For decades, Sanger sequencing, using chain-termination chemistry, has been the standard method for DNA sequencing (Chapter 23). In recent years, *next-generation sequencing* (NGS), a rapidly developing technology, has had a profound impact on biology. Compared to Sanger sequencing, NGS is advantageous in that it can achieve substantially higher throughput, and at lower cost, than the Sanger method. For example, a human genome can now be sequenced in several days using NGS technologies. Although NGS is not yet widely utilized for forensic applications, it has great potential for forensic DNA analysis, particularly in SNP analysis.

22.3.1 Next-Generation Sequencing Technologies

NGS technologies have two categories of application: *de novo* sequencing and resequencing. In *de novo* genome sequencing, uncharacterized genomes or characterized genomes with substantial structural variations are sequenced. Sequence reads are assembled without any reference sequence. In *resequencing* applications, characterized genomes are sequenced. Sequence reads are assembled against an existing reference sequence to identify sequence polymorphisms. Thus, resequencing can potentially be used for forensic applications to detect polymorphisms associated with human identification. *Target resequencing* is a useful method of resequencing that can be utilized for forensic applications. Prior to sequencing, the genomic regions of interest from a DNA sample are selectively isolated through a method known as *enrichment*. Several target-enrichment strategies have been developed. PCR is the most widely used enrichment method.

Table 22.3 Techniques for SNP Assay

Basis of Technique	Representative Assay	Detection	Format	Notes	Further Reading
Allele-specific hybridization	Reverse Blot	Colorimetry	Membrane based	Useful for screen assay	Saiki et al. (1989)
	LightCycler® (Roche)	Fluorescence	Solution based	Applicable for automation; limited multiplexing capability	Lareu et al. (2001)
	TaqMan® (Applied Biosystems)	Fluorescence	Solution based	Applicable for automation; limited multiplexing capability	De la Vega et al. (2005)
	Molecular beacons	Fluorescence	Solution based	Applicable for automation; limited multiplexing capability	Tyagi et al. (1998)
	GeneChip® (Affymetrix)	Fluorescence	Chip based	Designed for genotyping large number of SNPs; exceeds forensic needs	Mei et al. (2000)
Primer extension	SNaPshot™ (Applied Biosystems)	Fluorescence	Solution based	Applicable for capillary electrophoresis and multiplexing	Sanchez et al. (2006)
	PinPoint (Applied Biosystems)	Mass spectrometry	Solution based	Multiplex capability lower than SNaPshot™	Haff and Smirnov (1997)
	Arrayed primer extension (APEX)	Fluorescence	Chip based	Low reproducibility	Pastinen et al. (1997)
	Pyrosequencing	Fluorescence	Solution based	May be applicable for analysis of mixed profiles; not applicable for automation; limited multiplexing capability	Ronaghi et al. (1998)
Allele-specific oligonucleotide ligation	SNPstream® UHT (Orchid-Gene Screen)	Fluorescence	Chip based	Developed for mass disaster cases	Bell et al. (2002)
	SNPlex™ (Applied Biosystems)	Fluorescence	Solution based	Applicable for multiplexing; requires higher amount of target DNA template than other PCR-based methods	De la Vega et al. (2005)
Invasive cleavage	Invader® (Third Wave Technology)	Fluorescence	Solution based	PCR not required; large amount of target DNA required	Lyamichev et al. (1999)

Source: Adapted from Sobrino, B., M. Brion, and A. Carracedo, SNPs in forensic genetics: a review on SNP typing methodologies. Forensic Sci Int, 2005. 154(2-3): p. 181–94.; Budowle, B., SNP typing strategies. Forensic Sci Int, 2004. 146 Suppl: p. S139–42.

The PCR-based approach is highly effective in targeting genomic regions that are small in size. Nevertheless, a typical NGS involves several major steps, including sample, library, and template DNA preparation; template amplification; sequencing and detection; and base calling; as well as data analysis (Figure 22.8).

22.3.2 DNA Samples, Sequencing Library, and Template Preparation

For most sequencing applications, micrograms of purified DNA are needed. This requirement is still a challenge for forensic casework applications where nanograms of DNA are often obtained. Human autosomal genome sequencing usually requires converting a DNA sample into a sequencing library. Two types of sequencing libraries are usually used: mate-pair libraries and fragment libraries. A mate-pair library is often used in *de novo* sequencing applications, while the fragment libraries can be used for resequencing and forensic applications. To construct a fragment library, a DNA sample is fragmented using mechanical methods such as sonication, nebulization, or shearing; endonuclease digestion; or a transposon-based method. Subsequently, sequencing adapters containing primer-binding sites for universal PCR primers are ligated to both ends of the DNA fragments. In resequencing applications, multiplex sequencing of pooled samples is often carried out, which can improve the efficiency and reduce the costs of sequencing. For multiplex sequencing, an index tag containing a bar code can be ligated to each DNA fragment to allow it to be identified after sequencing. Indexing can minimize the risk of sample mix-ups and contaminations during the sample preparation.


Genomic DNA
Fragmentation and library preparation
Enrichment for target resequencing
Distribution on solid support
Flow cells
Beads
Solid-phase PCR
Emulsion PCR
Sequencing
Imaging and base calling
Sequence analysis

Figure 22.8 NGS work flow for potential forensic applications. (© Richard C. Li.)

Most imaging systems of sequencing platforms are not equipped to detect single-molecule fluorescence. Thus, DNA templates are amplified using either emulsion or solid-phase PCR. In the *emulsion PCR*, single-stranded DNA templates are bound to beads. DNA-bound beads are suspended in a water-in-oil emulsion, where each bead is placed in a single aqueous droplet. DNA fragments are amplified using PCR. As a result, each bead is coated with thousands of copies of the same template sequence. Subsequently, beads carrying amplified DNA are deposited on a glass slide or into individual fiber-optic wells for sequencing. In *solid-phase PCR*, both forward and reverse primers are attached to a slide (Figure 22.9). DNA templates are hybridized to immobilized PCR primers. The extended primer bends and hybridizes to a second immobilized primer, forming a bridge. During the "bridge amplification," the single-stranded template is amplified to form clusters. Solid-phase amplification can produce millions of spatially separated template clusters with free ends, allowing universal sequencing primers to hybridize for sequencing.

22.3.3 NGS Chemistry

The amplified template fragments are then sequenced. At present, there are two major categories of NGS chemistry that are routinely used: *sequencing by synthesis* and *sequencing by ligation*. The *pyrosequencing* technology is one example of NGS using the sequencing-by-synthesis chemistry. During the pyrosequencing, each nucleotide substrate is introduced one at a time. Only the correct nucleotide corresponding to the template is incorporated, and a pyrophosphate is released (Figure 22.10a). Pyrophosphate is then converted to ATP, catalyzed by sulfurylase (Figure 22.10b). ATP is then utilized by luciferase to convert luciferin to oxyluciferin, and the reaction emits light that is detected by a charge-coupled device camera (Figure 22.10c). This technology allows the generation of sequences with long read lengths. *Cyclic reversible termination* is another example of NGS using sequencing-by-synthesis chemistry. In this method, chain terminators (fluorescent-labeled dideoxynucleotides) are used to extend a primer sequence complementary to the template DNA. Each of four nucleotides is labeled with a different fluorophore. After incorporation and fluorescence detection, the terminating and fluorescent moieties are cleaved and removed (Figure 22.11). As a result, the next sequencing cycle is carried out. This process is repeated until the sequence is completed. This is the most commonly used method throughout the field of NGS.

In the sequencing-by-ligation chemistry, probes (eight nucleotides in length) are utilized for ligation reactions. Each probe contains five specific nucleotides that are complementary to the template and three nucleotides that are universal. Probes containing all possible combinations of the first five nucleotides are utilized. Each probe is fluorescently labeled according to the first two bases of the probe so that it can be identified. During the first round of sequencing reaction, only the probe that is complementary to the template sequence can hybridize. The probe is then ligated to the 3′ end of the primer. After detection, three universal nucleotides, including fluorophore, are cleaved. The ligation process is repeated several times using a new set of probes each time. The newly made complementary DNA strand is then stripped off. In the next round of sequencing, new primers that are one nucleotide shorter than the previous primer are utilized, and the ligation reaction is repeated. In this round of sequencing, different nucleotide positions are read. This process is repeated for several rounds with different primers, until all nucleotides in the template have been sequenced twice. As a result, this sequencing method has a low error rate.

22.3.4 NGS Coverage

In NGS, sequencing reads are usually not distributed evenly over the genomic regions of interest. As a result, some nucleotides will be covered by fewer or more reads than the average. Therefore, multiple reads for each nucleotide are necessary to obtain a reliable sequence. The average number of times that each nucleotide in the genomic regions of interest is sequenced is known as the


MiSeq
illumina
illumina
Insert Tray
Load Sample
Incorporation Buffer
illumina

Figure 22.9 A photo of an NGS platform. A MiSeq (Illumna) desktop sequencer (top), a flow-cell device (middle) where DNA templates are distributed for PCR, and a reagent cartridge (bottom) are shown. (© Richard C. Li.)


DNA polymerase
Base
5′
3′
OH
(a)
dNTP
Pyrophosphate
Sulfurylase
Adenylylsulfate
ATP
(b)
Pyrophosphate
Luciferase
Luciferin
Oxyluciferin
+
hν
(c)
ATP

Figure 22.10 Pyrosequencing chemistry. (a) During the pyrosequencing, a nucleotide substrate is incorporated, releasing a pyrophosphate. (b) Pyrophosphate is then converted to ATP. (c) ATP is utilized by luciferase, converting luciferin to oxyluciferin, which emits light.



Primer
Fluorescent 3′-O-allyl-dCTP
Extension
Deallylation
Base
5′
3′
F

Figure 22.11 Cyclic reversible termination. A single sequencing cycle is shown. The incorporation of a C is illustrated as an example.

coverage or the *sequencing depth*. The level of coverage depends on the types of applications. For example, for human genome SNP analysis, the level of coverage is from 10 to 30. The coverage can be calculated using the following equation:

$$C = \frac{LN}{G}$$

where:

C = coverage
G = haploid genome length
L = read length
N = number of reads

Currently, NGS has not been widely used in forensic applications. One disadvantage of NGS is that the error rate of NGS is higher than that of Sanger sequencing. Although the error rate of NGS is not yet acceptable for forensic casework analysis, it can potentially be overcome by increasing the sequencing coverage.

Bibliography

Ackerman, M.J., D.J. Tester, and D.J. Driscoll, Molecular autopsy of sudden unexplained death in the young. *Am J Forensic Med Pathol*, 2001, **22**(2): 105–111.

Ali, M.E., et al., HLA-A, -B and -DRB1 allele frequencies in the Bangladeshi population. *Tissue Antigens*, 2008, **72**(2): 115–119.

Alkhayat, A., F. Alshamali, and B. Budowle, Population data on the PCR-based loci LDLR GYPA, HBGG, D7S8, Gc, HLA-DQA1, and D1S80 from Arabs from Dubai. *Forensic Sci Int*, 1996, **81**(1): 29–34.

Allah, R., L. Yang, and S.B. Li, SNPs and forensic DNA typing. *Fa Yi Xue Za Zhi*, 2007, **23**(5): 373–379.

Allwood, J.S. and S. Harbison, SNP model development for the prediction of eye colour in New Zealand. *Forensic Sci Int Genet*, 2013, **7**(4): 444–452.

Altshuler, D., et al., An SNP map of the human genome generated by reduced representation shotgun sequencing. *Nature*, 2000, **407**(6803): 513–516.

Amigo, J., et al., The SNPforID browser: An online tool for query and display of frequency data from the SNPforID project. *Int J Legal Med*, 2008, **122**(5): 435–440.

Arnestad, M., et al., Prevalence of long-QT syndrome gene variants in sudden infant death syndrome. *Circulation*, 2007, **115**(3): 361–367.

Babol-Pokora, K. and J. Berent, SNP-minisequencing as an excellent tool for analysing degraded DNA recovered from archival tissues. *Acta Biochim Pol*, 2008, **55**(4): 815–819.

Bandelt, H.J. and A. Salas, Current next generation sequencing technology may not meet forensic standards. *Forensic Sci Int Genet*, 2012, **6**(1): 143–145.

Barbaro, A., et al., Genetic variability of the SNPforID 52-plex identification SNP panel in Italian population samples. *Forensic Sci Int Genet*, 2012, **6**(6): e185–e186.

Bell, B., et al., Distribution of types for six PCR-based loci; LDLR, GYPA, HBGG, D7S8, GC and HLA-DQA1 in central Pyrenees and Teruel (Spain). *J Forensic Sci*, 1997, **42**(3): 510–513.

Bell, P.A., et al., SNP stream UHT: Ultra-high throughput SNP genotyping for pharmacogenomics and drug discovery. *Bio Techniques*, 2002, **74**(Suppl 70-2): 76–77.

Birngruber, C., F. Ramsthaler, and M.A. Verhoff, The color(s) of human hair—Forensic hair analysis with SpectraCube. *Forensic Sci Int*, 2009, **185**(1–3): e19–e23.

Blake, E., et al., Polymerase chain reaction (PCR) amplification and human leukocyte antigen (HLA)-DQ alpha oligonucleotide typing on biological evidence samples: Casework experience. *J Forensic Sci*, 1992, **37**(3): 700–726.

Blanco-Verea, A., et al., Forensic validation and implementation of Y-chromosome SNP multiplexes. *Forensic Sci Int Genet Suppl*, 2008, **1**(1): 181–183.

Borsting, C. and N. Morling, Mutations and/or close relatives? Six case work examples where 49 autosomal SNPs were used as supplementary markers. *Forensic Sci Int Genet*, 2011, **5**(3): 236–241.

Borsting, C. and N. Morling, Reinvestigations of six unusual paternity cases by typing of autosomal single-nucleotide polymorphisms. *Transfusion*, 2012, **52**(2): 425–430.

Borsting, C., C. Tomas, and N. Morling, SNP typing of the reference materials SRM 2391b 1-10, K562, XY1, XX74, and 007 with the SNPforID multiplex. *Forensic Sci Int Genet*, 2011, **5**(3): e81–e82.

Borsting, C., C. Tomas, and N. Morling, Typing of 49 autosomal SNPs by single base extension and capillary electrophoresis for forensic genetic testing. *Methods Mol Biol*, 2012, **830**: 87–107.

Borsting, C., E. Rockenbauer, and N. Morling, Validation of a single nucleotide polymorphism (SNP) typing assay with 49 SNPs for forensic genetic testing in a laboratory accredited according to the ISO 17025 standard. *Forensic Sci Int Genet*, 2009, **4**(1): 34–42.

Borsting, C., H.S. Mogensen, and N. Morling, Forensic genetic SNP typing of low-template DNA and highly degraded DNA from crime case samples. *Forensic Sci Int Genet*, 2013, **7**(3): 345–352.

Borsting, C., et al., Performance of the SNPforID 52 SNP-plex assay in paternity testing. *Forensic Sci Int Genet*, 2008, **2**(4): 292–300.

Bouakaze, C., et al., Pigment phenotype and biogeographical ancestry from ancient skeletal remains: Inferences from multiplexed autosomal SNP analysis. *Int J Legal Med*, 2009, **123**(4): 315–325.

Branicki, W., U. Brudnik, and A. Wojas-Pelc, Interactions between HERC2, OCA2 and MC1R may influence human pigmentation phenotype. *Ann Hum Genet*, 2009, **73**(2): 160–170.

Branicki, W., et al., Determination of phenotype associated SNPs in the MC1R gene. *J Forensic Sci*, 2007, **52**(2): 349–354.

Branicki, W., et al., Model-based prediction of human hair color using DNA variants. *Hum Genet*, 2011, **129**(4): 443–454.

Brenner, C.H. and B.S. Weir, Issues and strategies in the DNA identification of World Trade Center victims. *Theor Popul Biol*, 2003, **63**(3): 173–178.

Brito, R.M., et al., South Portuguese population data on the loci HLA-DQA1, LDLR, GYPA, HBGG, D7S8 and Gc. *J Forensic Sci*, 1998, **43**(5): 1031–1036.

Brown, R.J., et al., Distribution of the HLA-DQA1 and polymarker alleles in the Basque population of Spain. *Forensic Sci Int*, 2000, **108**(2): 145–151.

Budowle, B. and A. van Daal, Forensically relevant SNP classes. *Biotechniques*, 2008, **44**(5): 603–608, 610.

Budowle, B., F.S. Baechtel, and R. Fejeran, Polymarker, HLA-DQA1, and D1S80 allele frequency data in Chamorro and Filipino populations from Guam. *J Forensic Sci*, 1998, **43**(6): 1195–1198.

Budowle, B., SNP typing strategies. *Forensic Sci Int*, 2004, **146**(Suppl): S139–S142.

Budowle, B., et al., PCR-based analysis: Allele-specific oligonucleotide assays, in *DNA Typing Protocols: Molecular Biology and Forensic Analysis*, pp. 95–118, 2000. Eaton: Natick, MA.

Budowle, B., et al., Validation and population studies of the loci LDLR, GYPA, HBGG, D7S8, and Gc (PM loci), and HLA-DQ alpha using a multiplex amplification and typing procedure. *J Forensic Sci*, 1995, **40**(1): 45–54.

Bunten, H., et al., OPRM1 and CYP2B6 gene variants as risk factors in methadone-related deaths. *Clin Pharmacol Ther*, 2010, **88**(3): 383–389.

Burke, A., et al., Role of SCN5A Y1102 polymorphism in sudden cardiac death in blacks. *Circulation*, 2005, **112**(6): 798–802.

Caratti, S., et al., Subtyping of Y-chromosomal haplogroup E-M78 (E1b1b1a) by SNP assay and its forensic application. *Int J Legal Med*, 2009, **123**(4): 357–360.

Chen, X., K.J. Livak, and P.Y. Kwok, A homogeneous, ligase-mediated DNA diagnostic test. *Genome Res*, 1998, **8**(5): 549–556.

Comey, C.T. and B. Budowle, Validation studies on the analysis of the HLA DQ alpha locus using the polymerase chain reaction. *J Forensic Sci*, 1991, **36**(6): 1633–1648.

Comey, C.T., et al., PCR amplification and typing of the HLA DQ alpha gene in forensic samples. *J Forensic Sci*, 1993, **38**(2): 239–249.

Consortium, I.H., A haplotype map of the human genome. *Nature*, 2005, **437**(7063): 1299–1320.

Cowland, J.B., H.O. Madsen, and N. Morling, HLA-DQA1 typing in Danes by two polymerase chain reaction (PCR) based methods. *Forensic Sci Int*, 1995, **73**(1): 1–13.

De la Vega, F.M., et al., Assessment of two flexible and compatible SNP genotyping platforms: TaqMan SNP genotyping assays and the SNPlex senotyping system. *Mutat Res*, 2005, **573**(1–2): 111–135.

de Paula Careta, F. and G.G. Paneto, Recent patents on high-throughput single nucleotide polymorphism (SNP) genotyping methods. *Recent Pat DNA Gene Seq*, 2012, **6**(2): 122–126.

Dimo-Simonin, N. and C. Brandt-Casadevall, Evaluation and usefulness of reverse dot blot DNA-PolyMarker typing in forensic case work. *Forensic Sci Int*, 1996, **81**(1): 61–72.

Dixon, L.A., et al., Validation of a 21-locus autosomal SNP multiplex for forensic identification purposes. *Forensic Sci Int*, 2005, **154**(1): 62–77.

Doktycz, M.J., et al., Analysis of polymerase chain reaction-amplified DNA products by mass spectrometry using matrix-assisted laser desorption and electrospray: Current status. *Anal Biochem*, 1995, **230**(2): 205–214.

Drobnic, K., et al., Typing of 49 autosomal SNPs by SNaPshot in the Slovenian population. *Forensic Sci Int Genet*, 2010, **4**(5): e125–e127.

Duffy, D.L., et al., Interactive effects of MC1R and OCA2 on melanoma risk phenotypes. *Hum Mol Genet*, 2004, **13**(4): 447–461.

Edelmann, J., et al., Long QT syndrome mutation detection by SNaPshot technique. *Int J Legal Med*, 2012, **126**(6): 969–973.

Eiberg, H. and J. Mohr, Assignment of genes coding for brown eye colour (BEY2) and brown hair colour (HCL3) on chromosome 15q. *Eur J Hum Genet*, 1996, **4**(4): 237–241.

Erlich, H.A., E.L. Sheldon, and G. Horn, HLA typing using DNA probes. *Biotechnology*, 1986, **4**: 7.

Erlich, H.A., HlA-DQ alpha typing of forensic specimens. *Forensic Sci Int*, 1992, **53**(2): 227–228.

Erlich, H.A., et al., Reliability of the HLA-DQ alpha PCR-based oligonucleotide typing system. *J Forensic Sci*, 1990, **35**(5): 1017–1019.

Fan, J.B., et al., Parallel genotyping of human SNPs using generic high-density oligonucleotide tag arrays. *Genome Res*, 2000, **10**(6): 853–860.

Fei, Z., T. Ono, and L.M. Smith, MALDI-TOF mass spectrometric typing of single nucleotide polymorphisms with mass-tagged ddNTPs. *Nucleic Acids Res*, 1998, **26**(11): 2827–2828.

Fildes, N. and R. Reynolds, Consistency and reproducibility of AmpliType PM results between seven laboratories: Field trial results. *J Forensic Sci*, 1995, **40**(2): 279–286.

Flanagan, N., et al., Pleiotropic effects of the melanocortin 1 receptor (MC1R) gene on human pigmentation. *Hum Mol Genet*, 2000, **9**(17): 2531–2537.

Fondevila, M., et al., Forensic performance of two insertion-deletion marker assays. *Int J Legal Med*, 2012, **126**(5): 725–737.

Fondevila, M., et al., Revision of the SNPforID 34-plex forensic ancestry test: Assay enhancements, standard reference sample genotypes and extended population studies. *Forensic Sci Int Genet*, 2013, **7**(1): 63–74.

Freire-Aradas, A., et al., A new SNP assay for identification of highly degraded human DNA. *Forensic Sci Int Genet*, 2012, **6**(3): 341–349.

Friis, S.L., et al., Typing of 30 insertion/deletions in Danes using the first commercial indel kit—Mentype® DIPplex. *Forensic Sci Int Genet*, 2012, **6**(2): e72–e74.

Frudakis, T., et al., Sequences associated with human iris pigmentation. *Genetics*, 2003, **165**(4): 2071–2083.

Gene, M., et al., Population study of Aymara Amerindians for the PCR-DNA polymorphisms HUMTH01, HUMVWA31A, D3S1358, D8S1179, D18S51, D19S253, YNZ22 and HLA-DQ alpha. *Int J Legal Med*, 2000, **113**(2): 126–128.

Geppert, M. and L. Roewer, SNaPshot® minisequencing analysis of multiple ancestry-informative Y-SNPs using capillary electrophoresis. *Methods Mol Biol*, 2012, **830**: 127–140.

Giardina, E., et al., Frequency assessment of SNPs for forensic identification in different populations. *Forensic Sci Int Genet*, 2007, **1**(3–4): e1–e3.

Gill, P., et al., An assessment of whether SNPs will replace STRs in national DNA databases—Joint considerations of the DNA working group of the European Network of Forensic Science Institutes (ENFSI) and the Scientific Working Group on DNA Analysis Methods (SWGDAM). *Sci Justice*, 2004, **44**(1): 51–53.

Gino, S., et al., LDLR, GYPA, HBGG, D7S8 and GC allele and genotype frequencies in the northwest Italian population. *J Forensic Sci*, 1999, **44**(1): 171–174.

Giroti, R. and V.K. Kashyap, Detection of the source of mislabeled biopsy tissue paraffin block and histopathological section on glass slide. *Diagn Mol Pathol*, 1998, **7**(6): 331–334.

Giroti, R.I., R. Biswas, and K. Mukherjee, Restriction fragment length polymorphism and polymerase chain reaction: HLA-DQA1 and polymarker analysis of blood samples from transfusion recipients. *Am J Clin Pathol*, 2002, **118**(3): 382–387.

Gra, O., et al., Microarray-based detection of CYP1A1, CYP2C9, CYP2C19, CYP2D6, GSTT1, GSTM1, MTHFR, MTRR, NQO1, NAT2, HLA-DQA1, and AB0 allele frequencies in native Russians. *Genet Test Mol Biomarkers*, 2010, **14**(3): 329–342.

Graf, J., R. Hodgson, and A. van Daal, Single nucleotide polymorphisms in the MATP gene are associated with normal human pigmentation variation. *Hum Mutat*, 2005, **25**(3): 278–284.

Graham, E.A., DNA reviews: Predicting phenotype. *Forensic Sci Med Pathol*, 2008, **4**(3): 196–199.

Grignani, P., et al., Subtyping mtDNA haplogroup H by SNaPshot minisequencing and its application in forensic individual identification. *Int J Legal Med*, 2006, **120**(3): 151–156.

Grimes, E.A., et al., Sequence polymorphism in the human melanocortin 1 receptor gene as an indicator of the red hair phenotype. *Forensic Sci Int*, 2001, **122**(2–3): 124–129.

Gross, A.M. and R.A. Guerrieri, HLA DQA1 and Polymarker validations for forensic casework: Standard specimens, reproducibility, and mixed specimens. *J Forensic Sci*, 1996, **41**(6): 1022–1026.

Grossman, P.D., et al., High-density multiplex detection of nucleic acid sequences: Oligonucleotide ligation assay and sequence-coded separation. *Nucleic Acids Res*, 1994, **22**(21): 4527–4534.

Gyllensten, U.B. and H.A. Erlich, Generation of single-stranded DNA by the polymerase chain reaction and its application to direct sequencing of the HLA-DQA locus. *Proc Natl Acad Sci U S A*, 1988, **85**(20): 7652–7656.

Haff, L.A. and I.P. Smirnov, Multiplex genotyping of PCR products with MassTag-labeled primers. *Nucleic Acids Res*, 1997, **25**(18): 3749–3750.

Hall, J.G., et al., Sensitive detection of DNA polymorphisms by the serial invasive signal amplification reaction. *Proc Natl Acad Sci U S A*, 2000, **97**(15): 8272–8277.

Hallenberg, C. and N. Morling, A report of the 1997, 1998 and 1999 Paternity Testing Workshops of the English Speaking Working Group of the International Society for Forensic Genetics. *Forensic Sci Int*, 2001, **116**(1): 23–33.

Hammer, M.F., et al., Population structure of Y chromosome SNP haplogroups in the United States and forensic implications for constructing Y chromosome STR databases. *Forensic Sci Int*, 2006, **164**(1): 45–55.

Hardenbol, P., et al., Multiplexed genotyping with sequence-tagged molecular inversion probes. *Nat Biotechnol*, 2003, **21**(6): 673–678.

Hart, K.L., et al., Improved eye- and skin-color prediction based on 8 SNPs. *Croat Med J*, 2013, **54**(3): 248–256.

Hashiyada, M., et al., Development of a spreadsheet for SNPs typing using Microsoft EXCEL. *Leg Med*, 2009, **11**(Suppl 1): S453–S454.

Heinrich, M., et al., Reduced-volume and low-volume typing of Y-chromosomal SNPs to obtain Finnish Y-chromosomal compound haplotypes. *Int J Legal Med*, 2009, **123**(5): 413–418.

Helmuth, R., et al., HLA-DQ alpha allele and genotype frequencies in various human populations, determined by using enzymatic amplification and oligonucleotide probes. *Am J Hum Genet*, 1990, **47**(3): 515–523.

Herrin, G., N. Fildes, and R. Reynolds, Evaluation of the AmpliType PM DNA test system on forensic case samples. *J Forensic Sci*, 1994, **39**: 9.

Hill, C.R., J.M. Butler, and P.M. Vallone, A 26plex autosomal STR assay to aid human identity testing*. *J Forensic Sci*, 2009, **54**(5): 1008–1015.

Hirschhorn, J.N., et al., SBE-TAGS: An array-based method for efficient single-nucleotide polymorphism genotyping. *Proc Natl Acad Sci U S A*, 2000, **97**(22): 12164–12169.

Hochmeister, M.N., et al., A method for the purification and recovery of genomic DNA from an HLA DQA1 amplification product and its subsequent amplification and typing with the AmpliType PM PCR amplification and typing kit. *J Forensic Sci*, 1995, **40**(4): 649–733.

Hochmeister, M.N., et al., Swiss population data on the loci HLA-DQ alpha, LDLR, GYPA, HBGG, D7S8, Gc and D1S80. *Forensic Sci Int*, 1994, **67**(3): 175–184.

Horn, G.T., et al., Characterization and rapid diagnostic analysis of DNA polymorphisms closely linked to the cystic fibrosis locus. *Clin Chem*, 1990, **36**(9): 1614–1619.

Hromadnikova, I., et al., Analysis of paternal alleles in nucleated red blood cells enriched from maternal blood. *Folia Biol*, 2001, **47**(1): 36–39.

Hsu, T.M., et al., Genotyping single-nucleotide polymorphisms by the invader assay with dual-color fluorescence polarization detection. *Clin Chem*, 2001, **47**(8): 1373–1377.

Huang, N.E. and B. Budowle, Chinese population data on the PCR-based loci HLA-DQ alpha, low-density-lipoprotein receptor, glycophorin A, hemoglobin gamma G, D7S8, and group-specific component. *Hum Hered*, 1995, **45**(1): 34–40.

Huckenbeck, W., et al., German population data on the loci low-density-lipoprotein receptor, glycophorin A, hemoglobin gamma G, D7S8 and group-specific component. *Anthropol Anz*, 1995, **53**(3): 193–198.

Inagaki, S., et al., A new 39-plex analysis method for SNPs including 15 blood group loci. *Forensic Sci Int*, 2004, **144**(1): 45–57.

Jankowski, L.B., et al., New Jersey Caucasian, African American, and Hispanic population data on the PCR-based loci HLA-DQA1, LDLR, GYPA, HBGG, D7S8, and Gc. *J Forensic Sci*, 1998, **43**(5): 1037–1040.

Johansen, P., et al., Evaluation of the iPLEX® sample ID Plus Panel designed for the Sequenom MassARRAY® system. A SNP typing assay developed for human identification and sample tracking based on the SNPforID panel. *Forensic Sci Int Genet*, 2013, **7**(5): 482–487.

Jung, J.M., et al., Extraction strategy for obtaining DNA from bloodstains for PCR amplification and typing of the HLA-DQ alpha gene. *Int J Legal Med*, 1991, **104**(3): 145–148.

Kastelic, V. and K. Drobnic, A single-nucleotide polymorphism (SNP) multiplex system: The association of five SNPs with human eye and hair color in the Slovenian population and comparison using a Bayesian network and logistic regression model. *Croat Med J*, 2012, **53**(5): 401–408.

Kastelic, V., et al., Prediction of eye color in the Slovenian population using the IrisPlex SNPs. *Croat Med J*, 2013, **54**(4): 381–386.

Keating, B., et al., First all-in-one diagnostic tool for DNA intelligence: Genome-wide inference of biogeographic ancestry, appearance, relatedness, and sex with the Identitas v1 Forensic Chip. *Int J Legal Med*, 2013, **127**(3): 559–572.

Kersbergen, P., et al., Developing a set of ancestry-sensitive DNA markers reflecting continental origins of humans. *BMC Genet*, 2009, **10**: 69.

Khodjet-el-Khil, H., et al., Genetic analysis of the SNPforID 34-plex ancestry informative SNP panel in Tunisian and Libyan populations. *Forensic Sci Int Genet*, 2011, **5**(3): e45–e47.

Kidd, K.K., et al., Developing a SNP panel for forensic identification of individuals. *Forensic Sci Int*, 2006, **164**(1): 20–32.

Kiesler, K.M. and P.M. Vallone, Allele frequencies for 40 autosomal SNP loci typed for US population samples using electrospray ionization mass spectrometry. *Croat Med J*, 2013, **54**(3): 225–231.

Kim, J.J., et al., Development of SNP-based human identification system. *Int J Legal Med*, 2010, **124**(2): 125–131.

Kimura, R., et al., Gene flow and natural selection in oceanic human populations inferred from genome-wide SNP typing. *Mol Biol Evol*, 2008, **25**(8): 1750–1761.

Kingback, M., et al., Influence of CYP2D6 genotype on the disposition of the enantiomers of venlafaxine and its major metabolites in postmortem femoral blood. *Forensic Sci Int*, 2012, **214**(1–3): 124–134.

Kitano, T., et al., Allele frequencies of a SNP and a 27-bp deletion that are the determinant of earwax type in the ABCC11 gene. *Leg Med*, 2008, **10**(2): 113–114.

Kling, D., et al., DNA microarray as a tool in establishing genetic relatedness—Current status and future prospects. *Forensic Sci Int Genet*, 2012, **6**(3): 322–329.

Kostrikis, L.G., et al., Spectral genotyping of human alleles. *Science*, 1998, **279**(5354): 1228–1229.

Krawczak, M., Informativity assessment for biallelic single nucleotide polymorphisms. *Electrophoresis*, 1999, **20**(8): 1676–1681.

Krjutskov, K., et al., Development of a single tube 640-plex genotyping method for detection of nucleic acid variations on microarrays. *Nucleic Acids Res*, 2008, **36**(12): e75.

Krjutskov, K., et al., Evaluation of the 124-plex SNP typing microarray for forensic testing. *Forensic Sci Int Genet*, 2009, **4**(1): 43–48.

Kubo, S., et al., Personal identification from skeletal remain by D1S80, HLA DQA1, TH01 and polymarker analysis. *J Med Invest*, 2002, **49**(1–2): 83–86.

Kupiec, T.C., V. Raj, and N. Vu, Pharmacogenomics for the forensic toxicologist. *J Anal Toxicol*, 2006, **30**(2): 65–72.

Kuppuswamy, M.N., et al., Single nucleotide primer extension to detect genetic diseases: Experimental application to hemophilia B (factor IX) and cystic fibrosis genes. *Proc Natl Acad Sci U S A*, 1991, **88**(4): 1143–1147.

Lai, E., Application of SNP technologies in medicine: Lessons learned and future challenges. *Genome Res*, 2001, **11**(6): 927–929.

Lamason, R.L., et al., SLC24A5, a putative cation exchanger, affects pigmentation in zebrafish and humans. *Science*, 2005, **310**(5755): 1782–1786.

Landegren, U., et al., A ligase-mediated gene detection technique. *Science*, 1988, **241**(4869): 1077–1080.

Lareu, M., et al., The use of the LightCycler for the detection of Y chromosome SNPs. *Forensic Sci Int*, 2001, **118**(2–3): 163–168.

Larsen, M.K., et al., Molecular autopsy in young sudden cardiac death victims with suspected cardiomyopathy. *Forensic Sci Int*, 2012, **219**(1–3): 33–38.

Larsen, M.K., et al., Postmortem genetic testing of the ryanodine receptor 2 (RYR2) gene in a cohort of sudden unexplained death cases. *Int J Legal Med*, 2013, **127**(1): 139–144.

LaRue, B.L., et al., A validation study of the Qiagen investigator DIPplex® kit; an INDEL-based assay for human identification. *Int J Legal Med*, 2012, **126**(4): 533–540.

Levo, A., et al., Post-mortem SNP analysis of CYP2D6 gene reveals correlation between genotype and opioid drug (tramadol) metabolite ratios in blood. *Forensic Sci Int*, 2003, **135**(1): 9–15.

Li, C., et al., Genetic polymorphism of 29 highly informative InDel markers for forensic use in the Chinese Han population. *Forensic Sci Int Genet*, 2011, **5**(1): e27–e30.

Li, C., et al., Selection of 29 highly informative InDel markers for human identification and paternity analysis in Chinese Han population by the SNPlex genotyping system. *Mol Biol Rep*, 2012, **39**(3): 3143–3152.

Lou, C., et al., A SNaPshot assay for genotyping 44 individual identification single nucleotide polymorphisms. *Electrophoresis*, 2011, **32**(3–4): 368–378.

Lunetta, P., et al., Death in bathtub revisited with molecular genetics: A victim with suicidal traits and a LQTS gene mutation. *Forensic Sci Int*, 2002, **130**(2–3): 122–124.

Lyamichev, V., et al., Polymorphism identification and quantitative detection of genomic DNA by invasive cleavage of oligonucleotide probes. *Nat Biotechnol*, 1999, **17**(3): 292–296.

Manta, F., et al., Indel markers: Genetic diversity of 38 polymorphisms in Brazilian populations and application in a paternity investigation with post mortem material. *Forensic Sci Int Genet*, 2012, **6**(5): 658–661.

Martin, P., et al., Population genetic data of 30 autosomal indels in central Spain and the Basque Country populations. *Forensic Sci Int Genet*, 2013, **7**(2): e27–e30.

Martinez-Cadenas, C., et al., Gender is a major factor explaining discrepancies in eye colour prediction based on HERC2/OCA2 genotype and the IrisPlex model. *Forensic Sci Int Genet*, 2013, **7**(4): 453–460.

Medintz, I., et al., HLA-DQA1 and polymarker allele frequencies in two New York City Jewish populations. *J Forensic Sci*, 1997, **42**(5): 919–922.

Mei, R., et al., Genome-wide detection of allelic imbalance using human SNPs and high-density DNA arrays. *Genome Res*, 2000, **10**(8): 1126–1137.

Mein, C.A., et al., Evaluation of single nucleotide polymorphism typing with invader on PCR amplicons and its automation. *Genome Res*, 2000, **10**(3): 330–343.

Mengel-From, J., et al., Human eye colour and HERC2, OCA2 and MATP. *Forensic Sci Int Genet*, 2010, **4**(5): 323–328.

Mikkelsen, M., et al., Frequencies of 33 coding region mitochondrial SNPs in a Danish and a Turkish population. *Forensic Sci Int Genet*, 2011, **5**(5): 559–560.

Muddiman, D.C., et al., Length and base composition of PCR-amplified nucleic acids using mass measurements from electrospray ionization mass spectrometry. *Anal Chem*, 1997, **69**(8): 1543–1549.

Musgrave-Brown, E., et al., Forensic validation of the SNPforID 52-plex assay. *Forensic Sci Int Genet*, 2007, **1**(2): 186–190.

Myakishev, M.V., et al., High-throughput SNP genotyping by allele-specific PCR with universal energy-transfer-labeled primers. *Genome Res*, 2001, **11**(1): 163–169.

Nakahara, H., et al., Automated SNPs typing system based on the Invader assay. *Leg Med*, 2009, **11**(Suppl 1): S111–S114.

Nakajima, T., et al., Evaluation of 7 DNA markers (D1S80, HLA-DQ alpha, LDLR, GYPA, HBGG, D7S8 and GC) in a Japanese population. *Int J Legal Med*, 1996, **109**(1): 47–48.

Neitzke-Montinelli, V., et al., Polymorphisms upstream of the melanocortin-1 receptor coding region are associated with human pigmentation variation in a Brazilian population. *Am J Hum Biol*, 2012, **24**(6): 853–855.

Neuvonen, A.M., et al., Discrimination power of investigator DIPplex loci in Finnish and Somali populations. *Forensic Sci Int Genet*, 2012, **6**(4): e99–e102.

Nicklas, J.A. and E. Buel, A real-time multiplex SNP melting assay to discriminate individuals. *J Forensic Sci*, 2008, **53**(6): 1316–1324.

Odriozola, A., et al., SNPSTR rs59186128_D7S820 polymorphism distribution in European Caucasoid, Hispanic, and Afro-American populations. *Int J Legal Med*, 2009, **123**(6): 527–533.

Osawa, M., et al., SNP association and sequence analysis of the NOS1AP gene in SIDS. *Leg Med*, 2009, **11**(Suppl 1): S307–S308.

Pai, C.Y., et al., Flow chart HLA-DQA1 genotyping and its application to a forensic case. *J Forensic Sci*, 1995, **40**(2): 228–235.

Pakstis, A.J., et al., Candidate SNPs for a universal individual identification panel. *Hum Genet*, 2007, **121**(3–4): 305–317.

Parson, W., et al., Evaluation of next generation mtGenome sequencing using the Ion Torrent Personal Genome Machine (PGM). *Forensic Sci Int Genet*, 2013, **7**(5): 543–549.

Pastinen, T., et al., Minisequencing: A specific tool for DNA analysis and diagnostics on oligonucleotide arrays. *Genome Res*, 1997, **7**(6): 606–614.

Pastinen, T., et al., A system for specific, high-throughput genotyping by allele-specific primer extension on microarrays. *Genome Res*, 2000, **10**(7): 1031–1042.

Pereira, R. and L. Gusmao, Capillary electrophoresis of 38 noncoding biallelic mini-Indels for degraded samples and as complementary tool in paternity testing. *Methods Mol Biol*, 2012, **830**: 141–157.

Pereira, R., et al., A new multiplex for human identification using insertion/deletion polymorphisms. *Electrophoresis*, 2009, **30**(21): 3682–3690.

Phillips, C., SNP databases. *Methods Mol Biol*, 2009, **578**: 43–71.

Phillips, C., M. Fondevila, and M.V. Lareau, A 34-plex autosomal SNP single base extension assay for ancestry investigations. *Methods Mol Biol*, 2012, **830**: 109–126.

Phillips, C., et al., Evaluation of the Genplex SNP typing system and a 49plex forensic marker panel. *Forensic Sci Int Genet*, 2007, **1**(2): 180–185.

Phillips, C., et al., Inferring ancestral origin using a single multiplex assay of ancestry-informative marker SNPs. *Forensic Sci Int Genet*, 2007, **1**(3–4): 273–280.

Phillips, C., et al., Resolving relationship tests that show ambiguous STR results using autosomal SNPs as supplementary markers. *Forensic Sci Int Genet*, 2008, **2**(3): 198–204.

Phillips, C., et al., Eurasiaplex: A forensic SNP assay for differentiating European and South Asian ancestries. *Forensic Sci Int Genet*, 2013, **7**(3): 359–366.

Pilgrim, J.L., et al., Characterization of single nucleotide polymorphisms of cytochrome p450 in an Australian deceased sample. *Curr Drug Metab*, 2012, **13**(5): 679–692.

Pimenta, J.R. and S.D. Pena, Efficient human paternity testing with a panel of 40 short insertion-deletion polymorphisms. *Genet Mol Res*, 2010, **9**(1): 601–607.

Pinto, N., et al., Assessing paternities with inconclusive STR results: The suitability of bi-allelic markers. *Forensic Sci Int Genet*, 2013, **7**(1): 16–21.

Podini, D. and P.M. Vallone, SNP genotyping using multiplex single base primer extension assays. *Methods Mol Biol*, 2009, **578**: 379–391.

Poetsch, M., et al., Prediction of people's origin from degraded DNA—Presentation of SNP assays and calculation of probability. *Int J Legal Med*, 2013, **127**(2): 347–357.

Pomeroy, R., et al., A low-cost, high-throughput, automated single nucleotide polymorphism assay for forensic human DNA applications. *Anal Biochem*, 2009, **395**(1): 61–67.

Porras, L., et al., Genetic variability of the SNPforID 52-plex identification-SNP panel in Central West Colombia. *Forensic Sci Int Genet*, 2009, **4**(1): e9–e10.

Pulker, H., et al., Finding genes that underlie physical traits of forensic interest using genetic tools. *Forensic Sci Int Genet*, 2007, **1**(2): 100–104.

Rebbeck, T.R., et al., P gene as an inherited biomarker of human eye color. *Cancer Epidemiol Biomarkers Prev*, 2002, **11**(8): 782–784.

Rees, J.L., Genetics of hair and skin color. *Annu Rev Genet*, 2003, **37**: 67–90.

Reich, D.E., et al., Human genome sequence variation and the influence of gene history, mutation and recombination. *Nat Genet*, 2002, **32**(1): 135–142.

Riccardi, L.N., et al., Development of a tetraplex PCR assay for CYP2D6 genotyping in degraded DNA samples. *J Forensic Sci*, 2013, **59**(3): 690–695.

Rockenbauer, E., et al., Characterization of mutations and sequence variants in the D21S11 locus by next generation sequencing. *Forensic Sci Int Genet*, 2014, **8**(1): 68–72.

Rodriguez-Calvo, M.S., et al., Population data on the loci LDLR, GYPA, HBGG, D7S8, and GC in three southwest European populations. *J Forensic Sci*, 1996, **41**(2): 291–296.

Rolf, B., N. Bulander, and P. Wiegand, Insertion-/deletion polymorphisms close to the repeat region of STR loci can cause discordant genotypes with different STR kits. *Forensic Sci Int Genet*, 2011, **5**(4): 339–341.

Romanini, C., et al., Typing short amplicon binary polymorphisms: Supplementary SNP and Indel genetic information in the analysis of highly degraded skeletal remains. *Forensic Sci Int Genet*, 2012, **6**(4): 469–476.

Romero, R.L., et al., The applicability of formalin-fixed and formalin fixed paraffin embedded tissues in forensic DNA analysis. *J Forensic Sci*, 1997, **42**(4): 708–714.

Ronaghi, M., M. Uhlen, and P. Nyren, A sequencing method based on real-time pyrophosphate. *Science*, 1998, **281**(5375): 363, 365.

Ronaghi, M., et al., Real-time DNA sequencing using detection of pyrophosphate release. *Anal Biochem*, 1996, **242**(1): 84–89.

Ross, P., et al., High level multiplex genotyping by MALDI-TOF mass spectrometry. *Nat Biotechnol*, 1998, **16**(13): 1347–1351.

Ruiz, Y., et al., Analysis of the SNPforID 52-plex markers in four Native American populations from Venezuela. *Forensic Sci Int Genet*, 2012, **6**(5): e142–e145.

Ruiz, Y., et al., Further development of forensic eye color predictive tests. *Forensic Sci Int Genet*, 2013, **7**(1): 28–40.

Sachidanandam, R., et al., A map of human genome sequence variation containing 1.42 million single nucleotide polymorphisms. *Nature*, 2001, **409**(6822): 928–933.

Saiki, R.K., et al., Analysis of enzymatically amplified beta-globin and HLA-DQ alpha DNA with allele-specific oligonucleotide probes. *Nature*, 1986, **324**(6093): 163–166.

Saiki, R.K., et al., Genetic analysis of amplified DNA with immobilized sequence-specific oligonucleotide probes. *Proc Natl Acad Sci U S A*, 1989, **86**(16): 6230–6234.

Sanchez, J.J., et al., A multiplex assay with 52 single nucleotide polymorphisms for human identification. *Electrophoresis*, 2006, **27**(9): 1713–1724.

Santos, C., et al., A study of East Timor variability using the SNPforID 52-plex SNP panel. *Forensic Sci Int Genet*, 2011, **5**(1): e25–e26.

Sato, Y., et al., HLA typing of aortic tissues from unidentified bodies using hot start polymerase chain reaction-sequence specific primers. *Leg Med (Tokyo)*, 2003, **5**(Suppl 1): S191–S193.

Sauer, S., et al., A novel procedure for efficient genotyping of single nucleotide polymorphisms. *Nucleic Acids Res*, 2000, **28**(5): E13.

Schmid, D., B. Bayer, and K. Anslinger, Comparison of telogen hair analyses: GenRES MPX-2SP kit versus genRES MPX-SP1 and genRES MPX-SP2 kits. *Forensic Sci Int Genet*, 2008, **3**(1): 22–26.

Schneider, P.M. and C. Rittner, Experience with the PCR-based HLA-DQ alpha DNA typing system in routine forensic casework. *Int J Legal Med*, 1993, **105**(5): 295–299.

Scholl, S., et al., Navajo, Pueblo, and Sioux population data on the loci HLA-DQA1, LDLR, GYPA, HBGG, D7S8, Gc, and D1S80. *J Forensic Sci*, 1996, **41**(1): 47–51.

Senge, T., et al., STRs, mini STRs and SNPs—A comparative study for typing degraded DNA. *Leg Med*, 2011, **13**(2): 68–74.

Sharafi Farzad, M., et al., Analysis of 49 autosomal SNPs in three ethnic groups from Iran: Persians, Lurs and Kurds. *Forensic Sci Int Genet*, 2013, **7**(4): 471–473.

Shen, M., Y. Shi, and P. Xiang, CYP3A4 and CYP2C19 genetic polymorphisms and zolpidem metabolism in the Chinese Han population: A pilot study. *Forensic Sci Int*, 2013, **227**(1–3): 77–81.

Shi, M., et al., 6 Y-SNP typing of China and Korean samples using primer extension and DHPLC. *J Forensic Sci*, 2007, **52**(1): 235–236.

Shi, Y., et al., Analysis of 50 SNPs in CYP2D6, CYP2C19, CYP2C9, CYP3A4 and CYP1A2 by MALDI-TOF mass spectrometry in Chinese Han population. *Forensic Sci Int*, 2011, **207**(1–3): 183–187.

Shriver, M.D. and R.A. Kittles, Genetic ancestry and the search for personalized genetic histories. *Nat Rev Genet*, 2004, **5**(8): 611–618.

Siebert, P.D. and M. Fukuda, Molecular cloning of a human glycophorin B cDNA: Nucleotide sequence and genomic relationship to glycophorin A. *Proc Natl Acad Sci U S A*, 1987, **84**(19): 6735–6739.

Slightom, J.L., A.E. Blechl, and O. Smithies, Human fetal G gamma- and A gamma-globin genes: Complete nucleotide sequences suggest that DNA can be exchanged between these duplicated genes. *Cell*, 1980, **21**(3): 627–638.

Soares-Vieira, J.A., et al., Brazilian population data on the polymerase chain reaction-based loci LDLR, GYPA, HBGG, D7S8, and Gc. *Am J Forensic Med Pathol*, 2003, **24**(3): 283–287.

Sobrino, B., M. Brion, and A. Carracedo, SNPs in forensic genetics: A review on SNP typing methodologies. *Forensic Sci Int*, 2005, **154**(2–3): 181–194.

Sokolov, B.P., Primer extension technique for the detection of single nucleotide in genomic DNA. *Nucleic Acids Res*, 1990, **18**(12): 3671.

Spichenok, O., et al., Prediction of eye and skin color in diverse populations using seven SNPs. *Forensic Sci Int Genet*, 2011, **5**(5): 472–478.

Spinella, A., et al., Italian population allele and genotype frequencies for the AmpliType PM and the HLA-DQ-alpha loci. *J Forensic Sci*, 1997, **42**(3): 514–518.

Syvanen, A.C., et al., A primer-guided nucleotide incorporation assay in the genotyping of apolipoprotein E. *Genomics*, 1990, **8**(4): 684–692.

Tahir, M.A., et al., DNA typing of samples for polymarker, DQA1, and nine STR loci from a human body exhumed after 27 years. *J Forensic Sci*, 2000, **45**(4): 902–907.

Takada, Y., et al., Application of SNPs in forensic casework: Identification of pathological and autoptical specimens due to sample mix-up. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S196–S197.

Taylor, M.S., A. Challed-Spong, and E.A. Johnson, Co-amplification of the amelogenin and HLA DQ alpha genes: Optimization and validation. *J Forensic Sci*, 1997, **42**(1): 130–136.

Templeton, J.E., et al., DNA capture and next-generation sequencing can recover whole mitochondrial genomes from highly degraded samples for human identification. *Investig Genet*, 2013, **4**(1): 26.

Tomas, C., C. Borsting, and N. Morling, A 48-plex autosomal SNP GenPlex assay for human individualization and relationship testing. *Methods Mol Biol*, 2012, **830**: 73–85.

Tomas, C., et al., Typing of 48 autosomal SNPs and amelogenin with GenPlex SNP genotyping system in forensic genetics. *Forensic Sci Int Genet*, 2008, **3**(1): 1–6.

Tomas, C., et al., Autosomal SNP typing of forensic samples with the GenPlex HID system: Results of a collaborative study. *Forensic Sci Int Genet*, 2011, **5**(5): 369–375.

Tomas, C., et al., Analysis of 49 autosomal SNPs in an Iraqi population. *Forensic Sci Int Genet*, 2013, **7**(1): 198–199.

Tsongalis, G.J. and M.M. Berman, Application of forensic identity testing in a clinical setting. Specimen identification. *Diagn Mol Pathol*, 1997, **6**(2): 111–114.

Tyagi, S. and F.R. Kramer, Molecular beacons: Probes that fluoresce upon hybridization. *Nat Biotechnol*, 1996, **14**(3): 303–308.

Tyagi, S., D.P. Bratu, and F.R. Kramer, Multicolor molecular beacons for allele discrimination. *Nat Biotechnol*, 1998, **16**(1): 49–53.

Valenzuela, R.K., et al., Predicting phenotype from genotype: Normal pigmentation. *J Forensic Sci*, 2010, **55**(2): 315–322.

Van Geystelen, A., et al., *In silico* detection of phylogenetic informative Y-chromosomal single nucleotide polymorphisms from whole genome sequencing data. *Electrophoresis*, 2014 (in press) 10.1002/elps.201300459.

Van Neste, C., et al., Forensic STR analysis using massive parallel sequencing. *Forensic Sci Int Genet*, 2012, **6**(6): 810–818.

Van Neste, C., et al., My-Forensic-Loci-queries (MyFLq) framework for analysis of forensic STR data generated by massive parallel sequencing. *Forensic Sci Int Genet*, 2014, **9**: 1–8.

Vu, N.T., A.K. Chaturvedi, and D.V. Canfield, Genotyping for DQA1 and PM loci in urine using PCR-based amplification: Effects of sample volume, storage temperature, preservatives, and aging on DNA extraction and typing. *Forensic Sci Int*, 1999, **102**(1): 23–34.

Vural, B., et al., Turkish population data on the HLA-DO alpha, LDLR, GYPA, HBGG, D7s8, and GC loci. *Int J Legal Med*, 1998, **111**(1): 43–45.

Walsh, S., et al., Developmental validation of the IrisPlex system: Determination of blue and brown iris colour for forensic intelligence. *Forensic Sci Int Genet*, 2011, **5**(5): 464–471.

Walsh, S., et al., IrisPlex: A sensitive DNA tool for accurate prediction of blue and brown eye colour in the absence of ancestry information. *Forensic Sci Int Genet*, 2011, **5**(3): 170–180.

Walsh, S., et al., DNA-based eye colour prediction across Europe with the IrisPlex system. *Forensic Sci Int Genet*, 2012, **6**(3): 330–340.

Walsh, S., et al., The HIrisPlex system for simultaneous prediction of hair and eye colour from DNA. *Forensic Sci Int Genet*, 2013, **7**(1): 98–115.

Watanabe, Y., et al., Japanese population DNA typing data for the loci LDLR, GYPA, HBGG, D7S8, and GC. *J Forensic Sci*, 1997, **42**(5): 911–913.

Weber-Lehmann, J., et al., Finding the needle in the haystack: Differentiating "identical" twins in paternity testing and forensics by ultra-deep next generation sequencing. *Forensic Sci Int Genet*, 2014, **9**: 42–46.

Wei, Y.L., et al., Forensic identification using a multiplex assay of 47 SNPs. *J Forensic Sci*, 2012, **57**(6): 1448–1456.

Westen, A.A., et al., Tri-allelic SNP markers enable analysis of mixed and degraded DNA samples. *Forensic Sci Int Genet*, 2009, **3**(4): 233–241.

Wilson, R.B., et al., Guidelines for internal validation of the HLA-DQ alpha DNA typing system. *Forensic Sci Int*, 1994, **66**(1): 9–22.

Woo, K.M. and B. Budowle, Korean population data on the PCR-based loci LDLR, GYPA, HBGG, D7S8, Gc, HLA-DQA1, and D1S80. *J Forensic Sci*, 1995, **40**(4): 645–648.

Yamamoto, T., et al., The human LDL receptor: A cysteine-rich protein with multiple Alu sequences in its mRNA. *Cell*, 1984, **39**(1): 27–38.

Yang, F., et al., Human group-specific component (Gc) is a member of the albumin family. *Proc Natl Acad Sci U S A*, 1985, **82**(23): 7994–7998.

Yang, H.C., et al., Integrative analysis of single nucleotide polymorphisms and gene expression efficiently distinguishes samples from closely related ethnic populations. *BMC Genomics*, 2012, **13**: 346.

Zaumsegel, D., M.A. Rothschild, and P.M. Schneider, A 21 marker insertion deletion polymorphism panel to study biogeographic ancestry. *Forensic Sci Int Genet*, 2013, **7**(2): 305–312.

Zeng, Z., et al., Genome-wide screen for individual identification SNPs (IISNPs) and the confirmation of six of them in Han Chinese with pyrosequencing technology. *J Forensic Sci*, 2010, **55**(4): 901–907.

Zeng, Z., et al., Evaluation of 96 SNPs in 14 populations for worldwide individual identification. *J Forensic Sci*, 2012, **57**(4): 1031–1035.

Zha, L., et al., Exploring of tri-allelic SNPs using pyrosequencing and the SNaPshot methods for forensic application. *Electrophoresis*, 2012, **33**(5): 841–848.

Zhao, S.M., S.H. Zhang, and C.T. Li, InDel-typer30: A multiplex PCR system for DNA identification among five Chinese populations. *Fa Yi Xue Za Zhi*, 2010, **26**(5): 343–348+356.

Zidkova, A., et al., Application of the new insertion-deletion polymorphism kit for forensic identification and parentage testing on the Czech population. *Int J Legal Med*, 2013, **127**(1): 7–10.

23

Mitochondrial DNA Profiling

Forensic mitochondrial DNA (mtDNA) analysis is an important tool for human identification and is especially useful for identifying victims such as missing persons and individuals in mass fatality cases. Because mtDNA is maternally inherited, the mtDNA profiles of these individuals can be compared to those of their maternal relatives, and thus these individuals can be identified. Additionally, cells contain a much higher copy number of the mtDNA genome than that of the nuclear genome. Therefore, mtDNA testing is frequently used to analyze evidence samples, such as hair shafts, that contain low amounts of nuclear DNA. Furthermore, buried bones and decomposed tissues, in which nuclear DNA may be degraded, can be tested with mtDNA analysis.

23.1 Human Mitochondrial Genome

Mitochondria are cellular organelles that serve as the energy-generating components of cells (Figure 23.1). Each cell contains hundreds of mitochondria, which have their own extrachromosomal genomes separated from the nuclear genomes. Although each human mitochondrion contains multiple copies of the mtDNA genome, the exact copy number varies for each cell. However, it is estimated that hundreds of copies of the mtDNA genome exist in most cells.

23.1.1 Genetic Contents of Mitochondrial Organelle Genomes

The human mitochondrial genome was first sequenced by Fred Sanger's laboratory at Cambridge University and was published in 1981; it is known as the *Cambridge reference sequence* (CRS). The sequence was largely derived from a placental sample from an individual of European descent and also partially from HeLa cells (a cell line derived from cervical cancer cells), as well as from bovine cells. It was later discovered, by resequencing the original mtDNA sample, that the CRS contains substitution errors at 10 nucleotide positions. The *revised Cambridge reference sequence* (rCRS) was published in 1999 and presented corrections to these substitution errors. Additionally, CRS contains a cytosine dimer at nucleotide positions 3106 and 3107, which is in fact a single cytosine nucleotide. This error is not corrected in the rCRS in order to retain the original nucleotide numbering system of CRS and thus to avoid inconsistency with the previous literature. The human mitochondrial DNA genome is circular with no beginning and end, which can make sequence comparison a potential problem. Therefore, the rCRS, with its nucleotide numbering system, is used as a reference when aligning with other mitochondrial sequences for comparison purposes.

Organelle genomes are usually much smaller than their nuclear counterparts. The human mtDNA genome consists of 16,569 base pairs (bp) containing 37 genes (Figure 23.2). Thirteen of


Outer membrane
mtDNA
Inner membrane

Figure 23.1 Mitochondrion. mtDNA, mitochondrial DNA. (© Richard C. Li.)


O_H
P_H
D Loop
16,569/0 P_L
CYTB
RNR1 (12S rRNA)
ND6
RNR2 (16S rRNA)
ND5
ND1
16,569 bp
ND2
ND4
O_L
ND4L
COI
ND3
COIII
ATP6
COII
ATP8
Transfer RNA gene

Figure 23.2 Human circular mitochondrial genome. The transcription direction for the H (heavy) and L (light) strands are indicated by arrows (P_H, P_L, respectively). The origins of replication are labeled O_H for the heavy strand and O_L for the light strand. The mitochondrial DNA genome encodes genes. ND, NADH coenzyme Q oxidoreductase complex; CO, cytochrome c oxidase complex; CYTB, cytochrome b; ATP, ATP synthase; rRNA, ribosomal RNA. Transfer RNA genes are shown as indicated. (© Richard C. Li.)

these genes code for proteins involved in the respiratory complex, a main energy-generating component in mitochondria. The other 24 specify noncoding RNA molecules required for the expression of the mitochondrial genome. The genes in the human mitochondrial genome are much more closely packed than in the nuclear genome and contain no introns. A *control region*, also known as a *displacement loop* (*D loop*), contains the origin of replication for one of the mtDNA strands but does not code for any gene products (Figure 23.2). An asymmetric distribution of



Figure 23.3 Pedigree of a human family showing inheritance of mtDNA. Females and males are denoted by circles and squares, respectively. Red symbols indicate individuals who inherited the same mtDNA.

nucleotides gives rise to light (L) and heavy (H) strands. The H strand contains a greater number of guanine nucleotides and a higher molecular weight in comparison to the L strand**.**

23.1.2 Maternal Inheritance of mtDNA

Maternal inheritance is typically observed for the mtDNA genome (Figure 23.3), which is inherited differently from nuclear genes. The inheritance of the mtDNA genome does not obey the rules of Mendelian inheritance and is thus called non-Mendelian inheritance.

The mitochondria of a spermatozoon are located in the midpiece (Chapter 14). At conception, only the head portion of a spermatozoon (containing a nucleus but no mitochondria) enters the egg. The fertilized egg contains the maternal mitochondria, which are transmitted to the progeny. Occasionally, the paternal mitochondria can enter the cell. However, paternal mitochondria in the spermatozoon that enter the egg are usually destroyed by the egg cell after fertilization (Figure 23.4). Therefore, the coinheritance of maternal and paternal mtDNA in a single individual is extremely rare in humans. The mtDNA sequence is identical for relatives within the same maternal lineage, a property that is useful when identifying individuals by comparing their mtDNA with that of maternal relatives.

Homologous DNA recombination (Chapter 25) has not been observed in the mtDNA genome. Thus, an mtDNA profile, also referred to as the *mitotype*, is considered a haplotype treated as a single locus. The mitochondrial genome has a higher mutation rate (up to 10 times higher) than its nuclear counterpart. The presence of mutations can be problematic in victim identification when comparing the mtDNA profiles of a victim with the relatives of the victim.

23.2 mtDNA Polymorphic Regions

23.2.1 Hypervariable Regions

The most polymorphic region of mtDNA is located within the D-loop (Figure 23.5). The three *hypervariable regions* in the D-loop are designated hypervariable region I (HV1: 16,024–16,365; 342 bp), hypervariable region II (HV2: 73–340; 268 bp), and hypervariable region III (HV3: 438–574; 137 bp). The most common polymorphic regions of the human mtDNA genome analyzed for forensic purposes are HV1 and HV2.

23.2.2 Heteroplasmy

Heteroplasmy occurs when an individual carries more than one mtDNA haplotype. Heteroplasmy may be observed with one kind of tissue and may be absent in other kinds of tissues; for example,



Figure 23.4 A model of uniparental mtDNA inheritance in humans. Paternal mitochondria occasionally enter the egg cell. Paternal mitochondria inside fertilized eggs are tagged by ubiquitin protein (Ub). It is proposed that the ubiquitination of sperm mitochondria leads to the degradation of paternal mitochondria in fertilized eggs. Tagged Ub can be recognized by proteasomes and lysosomes, which are cellular degradation machineries. A polyubiquitin chain with at least four ubiquitin units is needed to be recognized by the proteasomes. Ubiquitin with less than four ubiquitin units can be processed by the lysosomes. (© Richard C. Li.)



Figure 23.5 Hypervariable regions of the D-loop in mtDNA (with nucleotide positions). (© Richard C. Li.)

mtDNA heteroplasmy is commonly observed in hair samples (Chapter 4). Additionally, an individual may exhibit one mitotype in one tissue and a different mitotype in another. Thus, it is necessary to obtain and process additional samples to confirm the heteroplasmy when it is observed in a questioned sample but not in a known sample or vice versa. The two types of heteroplasmies are sequence and length heteroplasmy.

Sequence heteroplasmy is defined as the presence of two different nucleotides at a single position shown as overlapping peaks in a sequence electropherogram (Figure 23.6). Heteroplasmy usually occurs at one position, but on rare occasions it can be observed at more than one position. Hot spots for heteroplasmy have been documented at both HV1 and HV2 regions. Heteroplasmy may complicate the interpretation of mtDNA results, but its presence can also



Figure 23.6 Electropherogram showing mtDNA sequence heteroplasmy at position 234R (A/G) as indicated by an arrow. N, unresolved sequence. (© Richard C. Li.)



Figure 23.7 Length heteroplasmy. Electropherogram showing mtDNA length heteroplasmy at the C stretch of the HV1 region where position 16,189 is a T (top) and a C (bottom) as indicated by an arrow. N, unresolved sequence. (© Richard C. Li.)

improve the strength of a match. Both HV1 and HV2 of the human mtDNA D-loop region contain homopolymeric cytosine sequences known as *C stretches*. The HVI region contains a C stretch between nucleotide positions 16,184 and 16,193, interrupted by a thymine at position 16,189. If a base transition from T to C occurs at position 16,189 (a variant present in approximately 20% of the population), it results in an uninterrupted C stretch. A similar C stretch resides between positions 303 and 315 of the HV2 region.

Length heteroplasmies are often observed at the uninterrupted C stretches in sequencing, in which sequencing products with various lengths of polymeric cytosine residues are present. As a result, sequences downstream from the C stretch cannot be resolved (Figure 23.7). It is not clear whether the length heteroplasmy is due to replication slippage at the C stretches or results from the presence of a mixture of length variants in the cells. If length heteroplasmy occurs, alternative sequencing primers that anneal at the downstream of C stretches can be used to obtain the downstream sequences of the C stretches.

23.3 Forensic mtDNA Testing

23.3.1 General Considerations

mtDNA analysis is often used on samples derived from skeletal or decomposed remains. The surface of the sample should be cleaned to remove any adhering debris or contaminants. Bones and teeth are pulverized to facilitate extraction of the mtDNA (Chapter 5). Duplicate extractions (e.g., two sections of a single hair) are recommended if sufficient sample material is available.

mtDNA is extracted using a similar method to nuclear DNA (nuclear DNA is coextracted with mtDNA). The amount of mtDNA can therefore be estimated from the quantity of nuclear DNA obtained. Alternatively, mtDNA-specific quantization methods using real-time PCR (Chapter 6) can also be used to directly obtain measurements of mtDNA extracted.

For mtDNA sequencing, the analysis of both strands of the mtDNA in a given region must be performed to ensure accuracy. Due to the high sensitivity of mtDNA analysis, it is essential to minimize risks of contamination during the procedure. Contamination must be strictly monitored using proper controls such as extraction reagent blanks (Section 7.5.3) and amplification negative controls (samples containing all reagents except DNA template).

Finally, a positive control must also be used to monitor the success of the analysis. It should be introduced at the amplification step and remain through the sequencing process. A positive control consists of a DNA template of known sequence, such as DNA purified from the HL60 cell line.

23.3.2 mtDNA Screen Assay

One example of the assay for screening mtDNA variations is the allele-specific oligonucleotide (ASO) assay. It allows initial screening of mtDNA sequence polymorphisms and has the potential to reduce the number of samples required for mtDNA sequencing. This method is also useful for excluding or eliminating suspects from a case. However, HV1 and HV2 sequencing should be performed to obtain complete sequence information for the targeted HV regions to confirm a match.

The commercial Linear Array™ mtDNA HV1/HV2 region sequence typing kit (Roche Applied Sciences, Indianapolis) utilizes reverse ASO configuration with a panel of immobilized ASO probes that detect common polymorphic sites (Figures 23.8 and 23.9). The mtDNA is amplified at both HV1 (444 bp amplicon) and HV2 (415 bp amplicon) regions and the forward primers are biotin labeled at the 5′ ends of the oligonucleotides. Thus, the amplified PCR product (amplicon) is biotinylated. A horseradish peroxidase–conjugated streptavidin complex then binds to the biotinylated amplicon (see Chapter 9). Finally, colorimetric detection is carried out with tetramethylbenzidine (TMB) as the substrate to produce a colored precipitate at the designated location. The typing kit detects sequence variations in 19 positions within the HV1 and HV2 regions.



Figure 23.8 Reverse blot assay employed in mtDNA screen. A probe is immobilized onto a solid-phase membrane, and then hybridized with a biotinylated amplicon of the mtDNA HV sequences. Hybridization is detected by a streptavidin (SA) and horseradish peroxidase (HRP) conjugate. A colorimetric reaction is catalyzed by HRP using tetramethylbenzidine (TMB) as a substrate. (© Richard C. Li.)



Figure 23.9 Linear array mtDNA assay results (top) and negative control (bottom). (© Richard C. Li.)

23.3.3 mtDNA Sequencing

To sequence a specific region of mtDNA, a combination of PCR amplification and DNA sequencing techniques is utilized to reduce the time and labor needed to obtain DNA sequences from genomic DNA templates. mtDNA sequencing usually consists of (1) PCR amplification, (2) DNA sequencing reactions, (3) separation using electrophoresis, and (4) data collection and sequence analysis (Figure 23.10). Chapter 25 describes the evaluation of the strength of the results via statistical analysis.

23.3.3.1 PCR Amplification

The extracted DNA samples must be amplified to yield sufficient quantities of template for sequencing reactions. PCR amplification of all or a part of the D-loop region can be carried out with various primer sets. If a sample contains intact mtDNA, the HV1 and HV2 regions can be amplified as two amplicons, each of about 350–400 bp in length. If an mtDNA sample is fragmented due to degradation, the hypervariable regions can be amplified as smaller amplicons. PCR amplification of mtDNA is usually done in 34–38 cycles. Protocols for highly degraded DNA specimens sometimes require 42 cycles. The use of higher PCR cycle numbers can improve the yield of the amplicons.

Following mtDNA amplification, a purification step is necessary to remove excess primers and deoxynucleotide triphosphates (dNTPs). This step can be performed using filtration devices such as a Microcon® to remove small molecules from the sample or using nuclease digestion with shrimp alkaline phosphatase or exonuclease I to degrade remaining primers and dNTPs. The concentration of the amplicons is important for an optimal sequencing reaction in the next phase of mtDNA sequencing. The quality and quantity of the mtDNA amplicon must be evaluated to confirm the presence or absence of amplicons and their concentrations. This can be done


DNA extraction
DNA quantitation
PCR co-amplification of HV1 and HV2
Detection of PCR products
Cycle sequencing (HV1 forward primer)
Cycle sequencing (HV1 reverse primer)
Cycle sequencing (HV2 forward primer)
Cycle sequencing (HV2 reverse primer)
Electrophoresis
Electrophoresis
Electrophoresis
Electrophoresis
Sequence analysis and comparison

Figure 23.10 Sanger sequencing work flow for the mtDNA HV regions. (© Richard C. Li.)

using an agarose yield gel to visualize the amplicons of the sample or via capillary electrophoresis using a modular microfluidic chip device (Figure 8.12), a more informative method, for quantifying amplicons.

23.3.3.2 DNA Sequencing Reactions

The best-known DNA sequencing techniques are the *chain-termination* method and the *chemical degradation* method developed by Sanger and Gilbert (who shared the Nobel Prize for their work), respectively, in 1977. Over the years, the chain-termination method has become more common because it is suitable for automation and does not require the toxic chemicals necessary for the chemical degradation method.

23.3.3.2.1 Chain-Termination or Sanger Method

Using the chain-termination method, an oligonucleotide primer that can anneal to a single-stranded DNA template is utilized. A sequencing reaction contains DNA polymerase and the four dNTPs in order to carry out extension. The reaction also contains small quantities of dideoxynucleotide triphosphates (ddNTPs, Figure 23.11). Thus, a sequencing reaction involves a combination of extension and termination of the chain (Figure 23.12). If a ddNTP molecule is incorporated into a growing DNA chain, the absence of a 3′ OH group in the ddNTP molecule prevents the formation of a phosphodiester bond and thus disrupts the extension of the oligonucleotide chain.

The ratio of ddNTPs to dNTPs has been optimized to result in a collection of DNA fragments varying in length by one nucleotide from the primer length to the full length of the sequencing reaction product. As a result, the products of the sequencing reaction consist of a pool of various lengths of oligonucleotide chains terminated by ddNTPs. By using the four different ddNTPs, populations of DNA fragments are generated that terminate at positions occupied by every A, C, G, or T in the template strand.

The sequencing product of chain termination can be labeled with the *dye-terminator* system, in which the terminator is labeled, or with the *dye-primer* system, in which the primer is labeled.


HO
HO
P
O
O
HO
P
O
O
HO
P
O
O
O
base
3′
2′
(a)
HO
HO
HO
P
O
O
HO
P
O
O
HO
P
O
O
O
base
3′
2′
(b)

Figure 23.11 Chemical structures of dNTP and ddNTP: (a) dNTP; (b) ddNTP. Both hydroxyl groups attached to the 2′ and 3′ carbons of ribose are replaced by hydrogens.


HO
P
O
O
O
5′
CH_2
O
base
3′
HO
P
O
O
O
5′
CH_2
O
base
3′
OH
HO
HO
P
O
O
HO
P
O
O
HO
P
O
O
O
base
dNTP
HO
HO
P
O
O
O
5′
CH_2
O
base
3′
HO
P
O
O
O
5′
CH_2
O
base
3′
HO
P
O
O
O
5′
CH_2
O
base
3′
OH
(a)

Figure 23.12 Competition between extension and termination. (a) Growing chain in extension.



Figure 23.12 (Continued) (b) DNA strand with labeled ddNTP incorporated into a growing DNA chain that interrupts the incorporation of new nucleotides. The ddNTP usually is labeled with a fluorescent dye used for detection.

The dye-terminator system is commonly used for mtDNA sequencing in forensic laboratories. With the dye-terminator system, the ddNTPs are labeled with four different fluorescent dyes, each with a distinct spectrum. Thus, the sequencing with all four ddNTPs can be carried out in a single reaction. The labeled products of sequencing reactions are then resolved during electrophoresis and the sequencing data can be collected (Section 23.3.3.).

23.3.3.2.2 Cycle Sequencing

The chain-termination reaction is carried out using a *cycle sequencing* technique commonly used in forensic laboratories for mtDNA sequencing. Cycle sequencing, developed in the late 1980s, utilizes thermal cycling to generate a single-stranded template for chain-termination sequencing reactions. The application of thermal cycling in a sequencing reaction greatly increases the signal intensity and thus the sensitivity of the sequencing.

The sequencing reactions are carried out with multiple rounds of thermal cycling. Each cycle consists of three steps: denaturation of the double-stranded DNA template, annealing of a sequencing primer to its target sequence, and the extension of the annealed primer by DNA polymerase. Cycle sequencing utilizes only a single primer per reaction. During the extension of cycle sequencing, the extension of the strand is terminated with the incorporation of a ddNTP (Figure 23.13). The resulting partially double-stranded hybrid, consisting of the full-length template strand and its complementary chain-terminated product, is denatured during the first step of the next cycle, thereby liberating the template strand for another round of annealing, extension, and termination.

23.3.3.3 Electrophoresis, Sequence Analysis, and Mitotype Designations

The cycle sequencing products can be separated using electrophoresis in a 4% polyacrylamide denatured gel or a POP-6 polymer (Applied Biosystems) as the matrix for capillary electrophoresis (Figure 23.14). Following data collection, sequence data analysis can be performed with the Sequencher™ software (Gene Codes Corporation, Ann Arbor). Figure 23.15 shows sequence data.

Sequencing of a region of the mtDNA genome should be performed twice. Additionally, both strands of a region of the mtDNA genome should be sequenced to reduce ambiguities in sequence determination. The sequences of evidence samples and reference samples such as that of the victim or suspect can be compared. The nomenclature used in reporting should be compatible with International Union of Pure and Applied Chemistry (IUPAC) codes.

23.3.3.3.1 Reporting Format

The rCRS is used as a reference standard to facilitate the designation of mitotypes. For reporting purposes, sequence differences relative to the rCRS are listed in data format. When a difference between an individual's sequence and that of the rCRS sequence is observed, only the position (designated by a number) and the nucleotide differing from the reference standard are recorded. In this format, nucleotides identical to the rCRS are not listed. For example, at position 228 (HV2), the rCRS has a G. If a mitotype carries an A at position 228, the individual's mtDNA sequence is described as 228A. If an unresolved sequence ambiguity is observed at a position,



Figure 23.13 Cycle sequencing reaction. The reaction requires DNA polymerase, a template, and a primer. During DNA synthesis, the dNTP is incorporated by a new phosphodiester bond with the primer. The incorporation of ddNTP blocks further DNA synthesis of the growing chain. (© Richard C. Li.)


Template 3′ C C G A T T T C G G A A C C A C C A T C T A T A C G G A C 5′
Chain termination products
G G C T A A A G C C T T G G
G G C T A A A G C C T T G G T
G G C T A A A G C C T T G G T G
G G C T A A A G C C T T G G T G G
G G C T A A A G C C T T G G T G G T
G G C T A A A G C C T T G G T G G T A
G G C T A A A G C C T T G G T G G T A G
G G C T A A A G C C T T G G T G G T A G A
G G C T A A A G C C T T G G T G G T A G A T
G G C T A A A G C C T T G G T G G T A G A T A
G G C T A A A G C C T T G G T G G T A G A T A G
G G C T A A A G C C T T G G T G G T A G A T A G T
G G C T A A A G C C T T G G T G G T A G A T A G T C
G G C T A A A G C C T T G G T G G T A G A T A G T C C
G G C T A A A G C C T T G G T G G T A G A T A G T C C C
G G C T A A A G C C T T G G T G G T A G A T A G T C C C T
5′ G G C T A A A G C C T T G G T G G T A G A T A G T C C C T G 3′
Primer
DNA sequence

Figure 23.14 Diagram of the Sanger sequencing products. The DNA chain lengths are determined by the addition of ddNTP at different positions. The fluorescent dye-labeled cycle-sequencing products are separated using capillary electrophoresis. The fluorescent dyes are resolved by a detector, and the peaks corresponding to each DNA fragment are identified. (© Richard C. Li.)

the base number for the position is listed followed by an N. For example, 228N means an unresolved sequence ambiguity was observed at position 228.

23.3.3.3.2 Insertions

The insertion site is described by noting the position (at 5′ to the insertion) followed by a decimal point and a number. The number indicates the order of the insertions (e.g., 1 indicates the first insertion, 2 indicates the second, etc.). The base calling following the number indicates the inserted nucleotide (e.g., 524.1A, 524.2C).

23.3.3.3.3 Deletions

The deletion site designation is followed by the letter *d*. For example, a deletion at position 16,296 is recorded as 16,296d.

23.3.3.3.4 Heteroplasmic Sites

The IUPAC codes for base calling can be applied to heteroplasmic sites. For example, an A/G heteroplasmy can be designated as R, and a C/T heteroplasmy can be designated as Y.

23.3.4 Interpretation of mtDNA Profiling Results

Interpretation guidelines are used when comparing sequencing results between evidence and reference samples. General guidelines were set forth by the Scientific Working Group on DNA



Figure 23.15 Electropherogram representing a DNA sequence presented as peaks with corresponding colors for each of the four bases. The bases associated with each peak are noted. The sequence is read from left to right (5′ to 3′). (© Richard C. Li.)

Analysis Methods (SWGDAM) and the DNA Commission of the International Society of Forensic Genetics (ISFG). In reporting mtDNA profiling results, the most common categories of conclusions are the following: cannot exclude, exclusion, and inconclusive result.

23.3.4.1 Exclusion

If the sequences of questioned and known samples are different, then the samples can be excluded as originating from the same source. It should be taken into account that higher mutation rates are found with the mtDNA genome than are found with the nuclear genome. The SWGDAM's guidelines define that the conclusion of exclusion can be made if there are two or more nucleotide differences between the questioned and known samples. Additionally, mutations seem to be more common in certain tissues. For this reason, the sources of the tissues analyzed should be taken into consideration.

23.3.4.2 Cannot Exclude

If the sequences are the same, the reference sample and evidence cannot be excluded as arising from the same source. When an mtDNA profile cannot be excluded, it is desirable to evaluate the weight of the evidence. In cases where the same heteroplasmy is observed in both questioned and known samples, its presence increases the strength of the evidence. However, if heteroplasmy is observed in a questioned sample but not in a known sample or vice versa, a maternal lineage still cannot be excluded.

23.3.4.3 Inconclusive Result

If the questioned and known samples differ by a single nucleotide, and no heteroplasmy is present, the results are considered to be inconclusive.

Bibliography

Mitochondrial DNA Profiling

Adachi, N., K. Umetsu, and H. Shojo, Forensic strategy to ensure the quality of sequencing data of mitochondrial DNA in highly degraded samples. *Leg Med (Tokyo)*, 2014, **16**(1): 52–55.

Anderson, S., et al., Sequence and organization of the human mitochondrial genome. *Nature*, 1981, **290**(5806): 457–465.

Andreasson, H., et al., Forensic mitochondrial coding region analysis for increased discrimination using pyrosequencing technology. *Forensic Sci Int Genet*, 2007, **1**(1): 35–43.

Andrews, R.M., et al., Reanalysis and revision of the Cambridge reference sequence for human mitochondrial DNA. *Nat Genet*, 1999, **23**(2): 147.

Anjum, G.M., et al., Pyrosequencing-based strategy for a successful SNP detection in two hypervariable regions: HV-I/HV-II of the human mitochondrial displacement loop. *Electrophoresis*, 2010, **31**(2): 309–314.

Arnestad, M., et al., A mitochondrial DNA polymorphism associated with cardiac arrhythmia investigated in sudden infant death syndrome. *Acta Paediatr*, 2007, **96**(2): 206–210.

Asari, M., et al., Differences in tissue distribution of HV2 length heteroplasmy in mitochondrial DNA between mothers and children. *Forensic Sci Int*, 2008, **175**(2–3): 155–159.

Bandelt, H.J. and W. Parson, Consistent treatment of length variants in the human mtDNA control region: A reappraisal. *Int J Legal Med*, 2008, **122**(1): 11–21.

Bandelt, H.J., M. van Oven, and A. Salas, Haplogrouping mitochondrial DNA sequences in legal medicine/forensic genetics. *Int J Legal Med*, 2012, **126**(6): 901–916.

Bendall, K.E. and B.C. Sykes, Length heteroplasmy in the first hypervariable segment of the human mtDNA control region. *Am J Hum Genet*, 1995, **57**(2): 248–256.

Bendall, K.E., V.A. Macaulay, and B.C. Sykes, Variable levels of a heteroplasmic point mutation in individual hair roots. *Am J Hum Genet*, 1997, **61**(6): 1303–1308.

Bendall, K.E., et al., Heteroplasmic point mutations in the human mtDNA control region. *Am J Hum Genet*, 1996, **59**(6): 1276–1287.

Berger, C. and W. Parson, Mini-midi-mito: Adapting the amplification and sequencing strategy of mtDNA to the degradation state of crime scene samples. *Forensic Sci Int Genet*, 2009, **3**(3): 149–153.

Berger, C., et al., Evaluating sequence-derived mtDNA length heteroplasmy by amplicon size analysis. *Forensic Sci Int Genet*, 2011, **5**(2): 142–145.

Bintz, B.J., G.B. Dixon, and M.R. Wilson, Simultaneous detection of human mitochondrial DNA and nuclear-inserted mitochondrial-origin sequences (NumtS) using forensic mtDNA amplification strategies and pyrosequencing technology. *J Forensic Sci*, 2014, **59**(4): 1064–1073.

Brandon, M.C., et al., MITOMASTER: A bioinformatics tool for the analysis of mitochondrial DNA sequences. *Hum Mutat*, 2009, **30**(1): 1–6.

Brandstatter, A., et al., Dissection of mitochondrial superhaplogroup H using coding region SNPs. *Electrophoresis*, 2006, **27**(13): 2541–2550.

Buckleton, J.S., J.M. Curran, and P. Gill, Towards understanding the effect of uncertainty in the number of contributors to DNA stains. *Forensic Sci Int Genet*, 2007, **1**(1): 20–28.

Budowle, B., et al., Mitochondrial DNA regions HVI and HVII population data. *Forensic Sci Int*, 1999, **103**(1): 23–35.

Budowle, B., et al., Forensics and mitochondrial DNA: Applications, debates, and foundations. *Annu Rev Genom Hum Genet*, 2003, **4**: 119–141.

Budowle, B., et al., Addressing the use of phylogenetics for identification of sequences in error in the SWGDAM mitochondrial DNA database. *J Forensic Sci*, 2004, **49**(6): 1256–1261.

Budowle, B., et al., Mixture interpretation: Defining the relevant features for guidelines for the assessment of mixed DNA profiles in forensic casework. *J Forensic Sci*, 2009, **54**(4): 810–821.

Budowle, B., et al., Automated alignment and nomenclature for consistent treatment of polymorphisms in the human mitochondrial DNA control region. *J Forensic Sci*, 2010, **55**(5): 1190–1195.

Butler, J.M. and B.C. Levin, Forensic applications of mitochondrial DNA. *Trends Biotechnol*, 1998, **16**(4): 158–162.

Calloway, C.D., et al., The frequency of heteroplasmy in the HVII region of mtDNA differs across tissue types and increases with age. *Am J Hum Genet*, 2000, **66**(4): 1384–1397.

Carracedo, A., et al., DNA commission of the international society for forensic genetics: Guidelines for mitochondrial DNA typing. *Forensic Sci Int*, 2000, **110**(2): 79–85.

Cassandrini, D., et al., A new method for analysis of mitochondrial DNA point mutations and assess levels of heteroplasmy. *Biochem Biophys Res Commun*, 2006, **342**(2): 387–393.

Cerezo, M., et al., Applications of MALDI-TOF MS to large-scale human mtDNA population-based studies. *Electrophoresis*, 2009, **30**(21): 3665–3673.

Chemale, G., et al., Development and validation of a D-loop mtDNA SNP assay for the screening of specimens in forensic casework. *Forensic Sci Int Genet*, 2013, **7**(3): 353–358.

Clayton, D.A., Structure and function of the mitochondrial genome. *J Inherit Metab Dis*, 1992, **15**(4): 439–447.

Comas, D., S. Paabo, and J. Bertranpetit, Heteroplasmy in the control region of human mitochondrial DNA. *Genome Res*, 1995, **5**(1): 89–90.

Crespillo, M., et al., Results of the 2003–2004 GEP-ISFG collaborative study on mitochondrial DNA: Focus on the mtDNA profile of a mixed semen-saliva stain. *Forensic Sci Int*, 2006, **160**(2–3): 157–167.

Curran, J.M., A MCMC method for resolving two person mixtures. *Sci Justice*, 2008, **48**(4): 168–177.

Curtis, P.C., et al., Optimization of primer-specific filter metrics for the assessment of mitochondrial DNA sequence data. *Mitochondrial DNA*, 2010, **21**(6): 191–197.

D'Eustachio, P., High levels of mitochondrial DNA heteroplasmy in human hairs by Budowle et al. *Forensic Sci Int*, 2002, **130**(1): 63–67; author reply 68–70.

Danielson, P.B., et al., Resolving mtDNA mixtures by denaturing high-performance liquid chromatography and linkage phase determination. *Forensic Sci Int Genet*, 2007, **1**(2): 148–153.

Danielson, P.B., et al., Separating human DNA mixtures using denaturing high-performance liquid chromatography. *Expert Rev Mol Diagn*, 2005, **5**(1): 53–63.

Desmyter, S. and B. Hoste, Influence of the electrophoresis-resequencing method on the forensic mtDNA profiling quality. *Forensic Sci Int Genet*, 2007, **1**(2): 199–200.

Eduardoff, M., et al., Mass spectrometric base composition profiling: Implications for forensic mtDNA databasing. *Forensic Sci Int Genet*, 2013, **7**(6): 587–592.

Eichmann, C. and W. Parson, "Mitominis": Multiplex PCR analysis of reduced size amplicons for compound sequence analysis of the entire mtDNA control region in highly degraded samples. *Int J Legal Med*, 2008, **122**(5): 385–388.

Fan, L. and Y.G. Yao, An update to MitoTool: Using a new scoring system for faster mtDNA haplogroup determination. *Mitochondrion*, 2013, **13**(4): 360–363.

Fattorini, P., et al., Estimating the integrity of aged DNA samples by CE. *Electrophoresis*, 2009, **30**(22): 3986–3995.

Fendt, L., et al., Sequencing strategy for the whole mitochondrial genome resulting in high quality sequences. *BMC Genom*, 2009, **10**: 139.

Fernández, C. and A. Alonso, Microchip capillary electrophoresis protocol to evaluate quality and quantity of mtDNA amplified fragments for DNA sequencing in forensic genetics. *Methods Mol Biol*, 2012, **830**: 367–379.

Forster, L., et al., Evaluating length heteroplasmy in the human mitochondrial DNA control region. *Int J Legal Med*, 2010, **124**(2): 133–142.

Gabriel, M.N., et al., Improved mtDNA sequence analysis of forensic remains using a "mini-primer set" amplification strategy. *J Forensic Sci*, 2001, **46**(2): 247–253.

Gidlof, O., et al., Complete discrimination of six individuals based on high-resolution melting of hypervariable regions I and II of the mitochondrial genome. *Biotechniques*, 2009, **47**(2): 671–672, 674, 676, passim.

Gill, P., et al., National recommendations of the technical UK DNA working group on mixture interpretation for the NDNAD and for court going purposes. *Forensic Sci Int Genet*, 2008, **2**(1): 76–82.

Grignani, P., et al., Subtyping mtDNA haplogroup H by SNaPshot minisequencing and its application in forensic individual identification. *Int J Legal Med*, 2006, **120**(3): 151–156.

Grignani, P., et al., A mini-primer set covering the mtDNA hypervariable regions for the genetic typing of old skeletal remains. *Forensic Sci Int Genet Suppl*, 2009, **2**(1): 265–266.

Grignani, P., et al., Multiplex mtDNA coding region SNP assays for molecular dissection of haplogroups U/K and J/T. *Forensic Sci Int Genet*, 2009, **4**(1): 21–25.

Grzybowski, T. and U. Rogalla, Mitochondria in anthropology and forensic medicine. *Adv Exp Med Biol*, 2012, **942**: 441–453.

Hall, T.A., et al., Base composition profiling of human mitochondrial DNA using polymerase chain reaction and direct automated electrospray ionization mass spectrometry. *Anal Chem*, 2009, **81**(18): 7515–7526.

Hartmann, A., et al., Validation of microarray-based resequencing of 93 worldwide mitochondrial genomes. *Hum Mutat*, 2009, **30**(1): 115–122.

Hauswirth, W.W. and D.A. Clayton, Length heterogeneity of a conserved displacement-loop sequence in human mitochondrial DNA. *Nucleic Acids Res*, 1985, **13**(22): 8093–8104.

He, Y., et al., Heteroplasmic mitochondrial DNA mutations in normal and tumour cells. *Nature*, 2010, **464**(7288): 610–614.

Holland, M.M., M.R. McQuillan, and K.A. O'Hanlon, Second generation sequencing allows for mtDNA mixture deconvolution and high resolution detection of heteroplasmy. *Croat Med J*, 2011, **52**(3): 299–313.

Holland, M.M., Molecular analysis of the human mitochondrial DNA control region for forensic identity testing. *Curr Protoc Hum Genet*, 2012, (Suppl 74) 10.1002/0471142905.hg1407s74.

Howard, R., et al., Comparative analysis of human mitochondrial DNA from World War I bone samples by DNA sequencing and ESI-TOF mass spectrometry. *Forensic Sci Int Genet*, 2013, **7**(1): 1–9.

Hwan, Y.L., et al., A modified mini-primer set for analyzing mitochondrial DNA control region sequences from highly degraded forensic samples. *BioTechniques*, 2008, **44**(4): 555–558.

Irwin, J.A., et al., mtGenome reference population databases and the future of forensic mtDNA analysis. *Forensic Sci Int Genet*, 2011, **5**(3): 222–225.

Jarman, P.G., S.L. Fentress, and D.E. Katz, Mitochondrial DNA validation in a state laboratory. *J Forensic Sci*, 2009, **54**(1): 95–102.

Just, R.S., et al., Complete mitochondrial genome sequences for 265 African American and U.S. "Hispanic" individuals. *Forensic Sci Int Genet*, 2008, **2**(3): e45–e48.

Just, R.S., et al., The use of mitochondrial DNA single nucleotide polymorphisms to assist in the resolution of three challenging forensic cases. *J Forensic Sci*, 2009, **54**(4): 887–891.

Just, R.S., et al., Development of forensic-quality full mtGenome haplotypes: Success rates with low template specimens. *Forensic Sci Int Genet*, 2014, **10**: 73–79.

Kim, N.Y., et al., Modified midi- and mini-multiplex PCR systems for mitochondrial DNA control region sequence analysis in degraded samples. *J Forensic Sci*, 2013, **58**(3): 738–743.

Kohnemann, S. and H. Pfeiffer, Application of mtDNA SNP analysis in forensic casework. *Forensic Sci Int Genet*, 2011, **5**(3): 216–221.

Kohnemann, S., C. Hohoff, and H. Pfeiffer, An economical mtDNA SNP assay detecting different mitochondrial haplogroups in identical HVR 1 samples of Caucasian ancestry. *Mitochondrion*, 2009, **9**(5): 370–375.

Kohnemann, S., et al., A rapid mtDNA assay of 22 SNPs in one multiplex reaction increases the power of forensic testing in European Caucasians. *Int J Legal Med*, 2008, **122**(6): 517–523.

Kristinsson, R., S.E. Lewis, and P.B. Danielson, Comparative analysis of the HV1 and HV2 regions of human mitochondrial DNA by denaturing high-performance liquid chromatography. *J Forensic Sci*, 2009, **54**(1): 28–36.

Kurelac, I., et al., Searching for a needle in the haystack: Comparing six methods to evaluate heteroplasmy in difficult sequence context. *Biotechnol Adv*, 2012, **30**(1): 363–371.

Lacan, M., et al., Detection of the A189G mtDNA heteroplasmic mutation in relation to age in modern and ancient bones. *Int J Legal Med*, 2009, **123**(2): 161–167.

Lacan, M., et al., Detection of age-related duplications in mtDNA from human muscles and bones. *Int J Legal Med*, 2011, **125**(2): 293–300.

Lee, H.Y., et al., A modified mini-primer set for analyzing mitochondrial DNA control region sequences from highly degraded forensic samples. *Biotechniques*, 2008, **44**(4): 555–556, 558.

Lee, H.Y., et al., DNA typing for the identification of old skeletal remains from Korean War victims. *J Forensic Sci*, 2010, **55**(6): 1422–1429.

Lee, H.Y., et al., A one step multiplex PCR assay for rapid screening of East Asian mtDNA haplogroups on forensic samples. *Leg Med (Tokyo)*, 2013, **15**(1): 50–54.

Linch, C.A., D.A. Whiting, and M.M. Holland, Human hair histogenesis for the mitochondrial DNA forensic scientist. *J Forensic Sci*, 2001, **46**(4): 844–853.

Loreille, O.M. and J.A. Irwin, Capillary electrophoresis of human mtDNA control region sequences from highly degraded samples using short mtDNA amplicons. *Methods Mol Biol*, 2012, **830**: 283–299.

Mabuchi, T., et al., Typing the 1.1 kb control region of human mitochondrial DNA in Japanese individuals. *J Forensic Sci*, 2007, **52**(2): 355–363.

Malyarchuk, B.A., Improving the reconstructed sapiens reference sequence of mitochondrial DNA. *Forensic Sci Int Genet*, 2013, **7**(3): e74–e75.

Maricic, T., M. Whitten, and S. Paabo, Multiplexed DNA sequence capture of mitochondrial genomes using PCR products. *PLoS One*, 2010, **5**(11): e14004.

Marquez, M.C., Interpretation guidelines of mtDNA control region sequence electropherograms in forensic genetics. *Methods Mol Biol*, 2012, **830**: 301–319.

Melton, T., et al., Forensic mitochondrial DNA analysis of 691 casework hairs. *J Forensic Sci*, 2005, **50**(1): 73–80.

Miller, K.W. and B. Budowle, A compendium of human mitochondrial DNA control region: Development of an international standard forensic database. *Croat Med J*, 2001, **42**(3): 315–327.

Montesino, M. and L. Prieto, Capillary electrophoresis of big-dye terminator sequencing reactions for human mtDNA control region haplotyping in the identification of human remains. *Methods Mol Biol*, 2012, **830**: 267–281.

Montesino, M., et al., Analysis of body fluid mixtures by mtDNA sequencing: An inter-laboratory study of the GEP-ISFG working group. *Forensic Sci Int*, 2007, **168**(1): 42–56.

Moore, C.A., J. Gudikote, and G.C. Van Tuyle, Mitochondrial DNA rearrangements, including partial duplications, occur in young and old rat tissues. *Mutat Res*, 1998, **421**(2): 205–217.

Morling, N., et al., Interpretation of DNA mixtures—European consensus on principles. *Forensic Sci Int Genet*, 2007, **1**(3–4): 291–292.

Mosquera-Miguel, A., et al., Testing the performance of mtSNP minisequencing in forensic samples. *Forensic Sci Int Genet*, 2009, **3**(4): 261–264.

Nakahara, H., et al., Heteroplasmies detected in an amplified mitochondrial DNA control region from a small amount of template. *J Forensic Sci*, 2008, **53**(2): 306–311.

Nara, A., et al., Sequence analysis for HV I region of mitochondrial DNA using WGA (whole genome amplification) method. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S115–S118.

Naue, J., et al., Factors affecting the detection and quantification of mitochondrial point heteroplasmy using Sanger sequencing and SNaPshot minisequencing. *Int J Legal Med*, 2011, **125**(3): 427–436.

Nelson, K. and T. Melton, Forensic mitochondrial DNA analysis of 116 casework skeletal samples. *J Forensic Sci*, 2007, **52**(3): 557–561.

Nelson, T.M., et al., Development of a multiplex single base extension assay for mitochondrial DNA haplogroup typing. *Croat Med J*, 2007, **48**(4): 460–472.

Nicklas, J.A., T. Noreault-Conti, and E. Buel, Development of a real-time method to detect DNA degradation in forensic samples. *J Forensic Sci*, 2012, **57**(2): 466–471.

Nilsson, M., et al., Evaluation of mitochondrial DNA coding region assays for increased discrimination in forensic analysis. *Forensic Sci Int Genet*, 2008, **2**(1): 1–8.

Oberacher, H., H. Niederstatter, and W. Parson, Liquid chromatography-electrospray ionization mass spectrometry for simultaneous detection of mtDNA length and nucleotide polymorphisms. *Int J Legal Med*, 2007, **121**(1): 57–67.

Oberacher, H., et al., Increased forensic efficiency of DNA fingerprints through simultaneous resolution of length and nucleotide variability by high-performance mass spectrometry. *Hum Mutat*, 2008, **29**(3): 427–432.

Pakendorf, B. and M. Stoneking, Mitochondrial DNA and human evolution. *Annu Rev Genom Hum Genet*, 2005, **6**: 165–183.

Paneto, G.G., et al., Heteroplasmy in hair: Study of mitochondrial DNA third hypervariable region in hair and blood samples. *J Forensic Sci*, 2010, **55**(3): 715–718.

Parson, W. and A. Dur, EMPOP—A forensic mtDNA database. *Forensic Sci Int Genet*, 2007, **1**(2): 88–92.

Parsons, T.J. and M.D. Coble, Increasing the forensic discrimination of mitochondrial DNA testing through analysis of the entire mitochondrial DNA genome. *Croat Med J*, 2001, **42**(3): 304–309.

Polanskey, D., et al., Comparison of mitotyper rules and phylogenetic-based mtDNA nomenclature systems. *J Forensic Sci*, 2010, **55**(5): 1184–1189.

Prieto, L., et al., 2006 GEP-ISFG collaborative exercise on mtDNA: Reflections about interpretation, artefacts, and DNA mixtures. *Forensic Sci Int Genet*, 2008, **2**(2): 126–133.

Prieto, L., et al., GHEP-ISFG proficiency test 2011: Paper challenge on evaluation of mitochondrial DNA results. *Forensic Sci Int Genet*, 2013, **7**(1): 10–15.

Quintans, B., et al., Typing of mitochondrial DNA coding region SNPs of forensic and anthropological interest using SNaPshot minisequencing. *Forensic Sci Int*, 2004, **140**(2–3): 251–257.

Roberts, K.A. and C. Calloway, Characterization of mitochondrial DNA sequence heteroplasmy in blood tissue and hair as a function of hair morphology. *J Forensic Sci*, 2011, **56**(1): 46–60.

Rock, A., et al., SAM: String-based sequence search algorithm for mitochondrial DNA database queries. *Forensic Sci Int Genet*, 2011, **5**(2): 126–132.

Salas, A., et al., Phylogeographic investigations: The role of trees in forensic genetics. *Forensic Sci Int*, 2007, **168**(1): 1–13.

Salas, A., et al., A cautionary note on switching mitochondrial DNA reference sequences in forensic genetics. *Forensic Sci Int Genet*, 2012, **6**(6): e182–e184.

Schneider, P.M., et al., The German stain commission: Recommendations for the interpretation of mixed stains. *Int J Legal Med*, 2009, **123**(1): 1–5.

Seo, S.B., et al., Alterations of length heteroplasmy in mitochondrial DNA under various amplification conditions. *J Forensic Sci*, 2010, **55**(3): 719–722.

Serizawa, Y., et al., Detection of mitochondrial DNA polymorphisms from human hair shafts and formalin fixed tissue using whole genome amplification. *Int Med J*, 2008, **15**(3): 163–167.

Sosa, C., et al., A preliminary study on the incidence of heteroplasmy in mitochondrial DNA from vitreous humour. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S460–S462.

Stringer, P., et al., Interpretation of DNA mixtures—Australian and New Zealand consensus on principles. *Forensic Sci Int Genet*, 2009, **3**(2): 144–145.

Sutovsky, P., et al., Ubiquitin tag for sperm mitochondria. *Nature*, 1999, **402**: 371–372.

Tobe, S.S. and A.M. Linacre, A technique for the quantification of human and non-human mammalian mitochondrial DNA copy number in forensic and other mixtures. *Forensic Sci Int Genet*, 2008, **2**(4): 249–256.

Tully, G., et al., Considerations by the European DNA profiling (EDNAP) group on the working practices, nomenclature and interpretation of mitochondrial DNA profiles. *Forensic Sci Int*, 2001, **124**(1): 83–91.

Tully, G., et al., Results of a collaborative study of the EDNAP group regarding mitochondrial DNA heteroplasmy and segregation in hair shafts. *Forensic Sci Int*, 2004, **140**(1): 1–11.

Tully, L.A. and B.C. Levin, Human mitochondrial genetics. *Biotechnol Genet Eng Rev*, 2000, **17**: 147–177.

Turchi, C., et al., Italian mitochondrial DNA database: Results of a collaborative exercise and proficiency testing. *Int J Legal Med*, 2008, **122**(3): 199–204.

Umetsu, K. and I. Yuasa, Recent progress in mitochondrial DNA analysis. *Leg Med (Tokyo)*, 2005, **7**(4): 259–262.

Vallone, P.M., Capillary electrophoresis of an 11-plex mtDNA coding region SNP single base extension assay for discrimination of the most common Caucasian HV1/HV2 mitotype. *Methods Mol Biol*, 2012, **830**: 159–167.

Vallone, P.M., J.P. Jakupciak, and M.D. Coble, Forensic application of the Affymetrix human mitochondrial resequencing array. *Forensic Sci Int Genet*, 2007, **1**(2): 196–198.

van Oven, M. and M. Kayser, Updated comprehensive phylogenetic tree of global human mitochondrial DNA variation. *Hum Mutat*, 2009, **30**(2): E386–E394.

Warshauer, D.H., et al., Validation of the PLEX-ID™ mass spectrometry mitochondrial DNA assay. *Int J Legal Med*, 2013, **127**(2): 277–286.

Wilson, M.R., et al., Extraction, PCR amplification and sequencing of mitochondrial DNA from human hair shafts. *Biotechniques*, 1995, **18**(4): 662–669.

Wilson, M.R., et al., Recommendations for consistent treatment of length variants in the human mitochondrial DNA control region. *Forensic Sci Int*, 2002, **129**(1): 35–42.

Wilson, M.R., et al., Validation of mitochondrial DNA sequencing for forensic casework analysis. *Int J Legal Med*, 1995, **108**(2): 68–74.

Wu, J., et al., Multiplex mutagenically separated polymerase chain reaction assay for rapid detection of human mitochondrial DNA variations in coding area. *Croat Med J*, 2008, **49**(1): 32–38.

Xiu-Cheng Fan, A., et al., A rapid and accurate approach to identify single nucleotide polymorphisms of mitochondrial DNA using MALDI-TOF mass spectrometry. *Clin Chem Lab Med*, 2008, **46**(3): 299–305.

Genetic Population Data

Afonso Costa, H., et al., Mitochondrial DNA sequence analysis of a native Bolivian population. *J Forensic Leg Med*, 2010, **17**(5): 247–253.

Alshamali, F., et al., Mitochondrial DNA control region variation in Dubai, United Arab Emirates. *Forensic Sci Int Genet*, 2008, **2**(1): e9–e10.

Alvarez, J.C., et al., Characterization of human control region sequences for Spanish individuals in a forensic mtDNA data set. *Leg Med (Tokyo)*, 2007, **9**(6): 293–304.

Alvarez-Iglesias, V., et al., Coding region mitochondrial DNA SNPs: Targeting East Asian and native American haplogroups. *Forensic Sci Int Genet*, 2007, **1**(1): 44–55.

Al-Zahery, N., et al., Characterization of mitochondrial DNA control region lineages in Iraq. *Int J Legal Med*, 2013, **127**(2): 373–375.

Asari, M., et al., Utility of haplogroup determination for forensic mtDNA analysis in the Japanese population. *Leg Med (Tokyo)*, 2007, **9**(5): 237–240.

Ballantyne, K.N., et al., MtDNA SNP multiplexes for efficient inference of matrilineal genetic ancestry within Oceania. *Forensic Sci Int Genet*, 2012, **6**(4): 425–436.

Barbosa, A.B., et al., Mitochondrial DNA control region polymorphism in the population of Alagoas state, north-eastern Brazil. *J Forensic Sci*, 2008, **53**(1): 142–146.

Bobillo, M.C., et al., Amerindian mitochondrial DNA haplogroups predominate in the population of Argentina: Towards a first nationwide forensic mitochondrial DNA sequence database. *Int J Legal Med*, 2010, **124**(4): 263–268.

Bodner, M., et al., Southeast Asian diversity: First insights into the complex mtDNA structure of Laos. *BMC Evol Biol*, 2011, **11**: 49.

Brandstatter, A., et al., Generating population data for the EMPOP database—An overview of the mtDNA sequencing and data evaluation processes considering 273 Austrian control region sequences as example. *Forensic Sci Int*, 2007, **166**(2–3): 164–175.

Brandstatter, A., et al., Mitochondrial DNA control region variation in Ashkenazi Jews from Hungary. *Forensic Sci Int Genet*, 2008, **2**(1): e4–e6.

Cardoso, S., et al., Mitochondrial DNA control region variation in an autochthonous Basque population sample from the Basque Country. *Forensic Sci Int Genet*, 2012, **6**(4): e106–e108.

Cardoso, S., et al., Mitochondrial DNA control region data reveal high prevalence of nNative American lineages in Jujuy province, NW Argentina. *Forensic Sci Int Genet*, 2013, **7**(3): e52–e55.

Cardoso, S., et al., Variability of the entire mitochondrial DNA control region in a human isolate from the Pas Valley (northern Spain). *J Forensic Sci*, 2010, **55**(5): 1196–1201.

Castro de Guerra, D., et al., Sequence variation of mitochondrial DNA control region in North Central Venezuela. *Forensic Sci Int Genet*, 2012, **6**(5): e131–e133.

Chen, F., et al., Analysis of mitochondrial DNA polymorphisms in Guangdong Han Chinese. *Forensic Sci Int Genet*, 2008, **2**(2): 150–153.

Chen, F., et al., Genetic polymorphism of mitochondrial DNA HVS-I and HVS-II of Chinese Tu ethnic minority group. *J Genet Genom*, 2008, **35**(4): 225–232.

Chen, F., et al., Sequence-length variation of mtDNA HVS-I C-stretch in Chinese ethnic groups. *J Zhejiang Univ Sci B*, 2009, **10**(10): 711–720.

Diegoli, T.M., et al., Mitochondrial control region sequences from an African American population sample. *Forensic Sci Int Genet*, 2009, **4**(1): e45–e52.

Egyed, B., et al., Mitochondrial control region sequence variations in the Hungarian population: Analysis of population samples from Hungary and from Transylvania (Romania). *Forensic Sci Int Genet*, 2007, **1**(2): 158–162.

Fendt, L., et al., Mitochondrial DNA control region data from indigenous Angolan Khoe-San lineages. *Forensic Sci Int Genet*, 2012, **6**(5): 662–663.

Fendt, L., et al., MtDNA diversity of Ghana: A forensic and phylogeographic view. *Forensic Sci Int Genet*, 2012, **6**(2): 244–249.

Grzybowski, T., et al., Complex interactions of the eastern and western Slavic populations with other European groups as revealed by mitochondrial DNA analysis. *Forensic Sci Int Genet*, 2007, **1**(2): 141–147.

Hedman, M., et al., Finnish mitochondrial DNA HVS-I and HVS-II population data. *Forensic Sci Int*, 2007, **172**(2–3): 171–178.

Huang, D., et al., Typing of 24 mtDNA SNPs in a Chinese population using SNaPshot minisequencing. *J Huazhong Univ Sci Technol Med Sci*, 2010, **30**(3): 291–298.

Irwin, J., et al., Hungarian mtDNA population databases from Budapest and the Baranya county Roma. *Int J Legal Med*, 2007, **121**(5): 377–383.

Irwin, J., et al., Mitochondrial control region sequences from northern Greece and Greek Cypriots. *Int J Legal Med*, 2008, **122**(1): 87–89.

Irwin, J.A., et al., Development and expansion of high-quality control region databases to improve forensic mtDNA evidence interpretation. *Forensic Sci Int Genet*, 2007, **1**(2): 154–157.

Irwin, J.A., et al., Mitochondrial DNA control region variation in a population sample from Hong Kong, China. *Forensic Sci Int Genet*, 2009, **3**(4): e119–e125.

Irwin, J.A., et al., The mtDNA composition of Uzbekistan: A microcosm of Central Asian patterns. *Int J Legal Med*, 2010, **124**(3): 195–204.

Kato, H., et al., Molecular analysis of mitochondrial hypervariable region 1 in 394 Japanese individuals. *Leg Med (Tokyo)*, 2009, **11**(Suppl 1): S443–S445.

Lander, N., et al., Haplotype diversity in human mitochondrial DNA hypervariable regions I-III in the city of Caracas (Venezuela). *Forensic Sci Int Genet*, 2008, **2**(4): e61–e64.

Lehocky, I., et al., A database of mitochondrial DNA hypervariable regions I and II sequences of individuals from Slovakia. *Forensic Sci Int Genet*, 2008, **2**(4): e53–e59.

Liu, C., et al., Mitochondrial DNA polymorphisms in Gelao ethnic group residing in Southwest China. *Forensic Sci Int Genet*, 2011, **5**(1): e4–e10.

Maruyama, S., et al., MtDNA control region sequence polymorphisms and phylogenetic analysis of Malay population living in or around Kuala Lumpur in Malaysia. *Int J Legal Med*, 2010, **124**(2): 165–170.

Maruyama, S., et al., Analysis of human mitochondrial DNA polymorphisms in the Japanese population. *Biochem Genet*, 2013, **51**(1–2): 33–70.

Mikkelsen, M., et al., Mitochondrial DNA HV1 and HV2 variation in Danes. *Forensic Sci Int Genet*, 2010, **4**(4): e87–e88.

Mikkelsen, M., et al., Forensic and phylogeographic characterisation of mtDNA lineages from Somalia. *Int J Legal Med*, 2012, **126**(4): 573–579.

Nohira, C., S. Maruyama, and K. Minaguchi, Phylogenetic classification of Japanese mtDNA assisted by complete mitochondrial DNA sequences. *Int J Legal Med*, 2010, **124**(1): 7–12.

Nur Haslindawaty, A.R., et al., Sequence polymorphisms of mtDNA HV1, HV2, and HV3 regions in the Malay population of Peninsular Malaysia. *Int J Legal Med*, 2010, **124**(5): 415–426.

Palencia, L., et al., Mitochondrial DNA diversity in a population from Santa Catarina (Brazil): Predominance of the European input. *Int J Legal Med*, 2010, **124**(4): 331–336.

Parson, W., et al., Identification of West Eurasian mitochondrial haplogroups by mtDNA SNP screening: Results of the 2006–2007 EDNAP collaborative exercise. *Forensic Sci Int Genet*, 2008, **2**(1): 61–68.

Powell, G.T., et al., The population history of the Xibe in northern China: A comparison of autosomal, mtDNA and Y-chromosomal analyses of migration and gene flow. *Forensic Sci Int Genet*, 2007, **1**(2): 115–119.

Rakha, A., et al., Forensic and genetic characterization of mtDNA from Pathans of Pakistan. *Int J Legal Med*, 2011, **125**(6): 841–848.

Ribeiro-dos-Santos, A.K., et al., Nucleotide variability of HV-I in Afro-descendents populations of the Brazilian Amazon region. *Forensic Sci Int*, 2007, **167**(1): 77–80.

Saunier, J.L., et al., Mitochondrial control region sequences from a U.S. “Hispanic” population sample. *Forensic Sci Int Genet*, 2008, **2**(2): e19–e23.

Saunier, J.L., et al., Mitochondrial control region sequences from an Egyptian population sample. *Forensic Sci Int Genet*, 2009, **3**(3): e97–e103.

Scheible, M., et al., Mitochondrial DNA control region variation in a Kuwaiti population sample. *Forensic Sci Int Genet*, 2011, **5**(4): e112–e113.

Szibor, R., et al., Mitochondrial D-loop $(CA)_n$ repeat length heteroplasmy: Frequency in a German population sample and inheritance studies in two pedigrees. *Int J Legal Med*, 2007, **121**(3): 207–213.

Tetzlaff, S., et al., Mitochondrial DNA population data of HVS-I and HVS-II sequences from a northeast German sample. *Forensic Sci Int*, 2007, **172**(2–3): 218–224.

Tillmar, A.O., et al., Homogeneity in mitochondrial DNA control region sequences in Swedish subpopulations. *Int J Legal Med*, 2010, **124**(2): 91–98.

Turchi, C., et al., Polymorphisms of mtDNA control region in Tunisian and Moroccan populations: An enrichment of forensic mtDNA databases with Northern Africa data. *Forensic Sci Int Genet*, 2009, **3**(3): 166–172.

Wilson, J.L., et al., Forensic analysis of mtDNA haplotypes from two rural communities in Haiti reflects their population history. *J Forensic Sci*, 2012, **57**(6): 1457–1466.

Wong, H.Y., et al., Sequence polymorphism of the mitochondrial DNA hypervariable regions I and II in 205 Singapore Malays. *Leg Med (Tokyo)*, 2007, **9**(1): 33–37.

Yan, J., et al., Allele frequencies of mitochondrial D-loop $(CA)_n$ repeat polymorphism in six Chinese ethnic groups. *Leg Med (Tokyo)*, 2007, **9**(6): 330–331.

Yang, Y., et al., A new strategy for the discrimination of mitochondrial DNA haplogroups in Han population. *J Forensic Sci*, 2011, **56**(3): 586–590.

Zgonjanin, D., et al., Sequence polymorphism of the mitochondrial DNA control region in the population of Vojvodina Province, Serbia. *Leg Med (Tokyo)*, 2010, **12**(2): 104–107.

Zimmermann, B., et al., Mitochondrial DNA control region population data from Macedonia. *Forensic Sci Int Genet*, 2007, **1**(3–4): e4–e9.

Zimmermann, B., et al., Forensic and phylogeographic characterization of mtDNA lineages from northern Thailand (Chiang Mai). *Int J Legal Med*, 2009, **123**(6): 495–501.

SECTION V

Forensic Issues

24

Forensic DNA Databases

Tools for Crime Investigations

24.1 Brief History of Forensic DNA Databases

Forensic DNA databases are networks for exchanging information among law enforcement agencies to assist in solving crimes. For example, forensic DNA databases allow forensic laboratories to search DNA profiles against the databases to identify criminals. In 1995, the United Kingdom established the world's first national DNA database, NDNAD, in England and Wales. Scotland and Northern Ireland have their own databases but also submit their profiles to NDNAD. NDNAD demonstrated initial success in solving crimes. Three years later, the United States introduced its national *Combined DNA Index System* or CODIS. By the end of 1998, other countries (such as Austria, Germany, the Netherlands, New Zealand, and Slovenia) had also introduced national DNA databases. Table 24.1 describes some of these national DNA databases. This chapter will focus on CODIS.

24.2 Infrastructure of CODIS

In the United States, a pilot project of DNA databasing was initiated by the Federal Bureau of Investigation (FBI) and 14 participating state and local laboratories. Subsequently in 1994, the Congressional DNA Identification Act authorized the FBI to establish a national DNA database including "DNA identification profiles of persons convicted of crimes, and analyses of DNA samples recovered from crime scenes and from unidentified human remains." By 1997, 13 STR loci were selected and in 1998 were implemented as the core loci for the national database, known today as CODIS. All 50 states, the District of Columbia, the federal laboratories, the US Army Criminal Investigation Laboratory, and Puerto Rico contribute to CODIS.

CODIS has three hierarchical levels: the Local DNA Index System (LDIS), the State DNA Index System (SDIS), and the National DNA Index System (NDIS) (Figure 24.1). The LDIS is maintained at crime laboratories operated by police departments, sheriff's offices, and local agencies. All forensic DNA profiles originating at the local level are stored in the LDIS and are transmitted to the SDIS and NDIS. Each state maintains a SDIS, which is typically operated by a designated state laboratory. An SDIS also stores the DNA profiles generated from state laboratories. The quality assurance standards for a qualified laboratory were set up by the DNA Advisory Board in 1998. The periodic revision of the standards is now carried out by the

Table 24.1 Characteristics of National DNA Databases

Country	Year Established	Suspect Entry Criteria	Convicted Offender Entry Criteria	Removal Criteria
United Kingdom	1995	Any recordable offense that leads to imprisonment	Entered as suspect	Never removed
New Zealand	1996	No suspects entered	Relevant offense (≥7 years in prison)	Never removed unless conviction quashed
Austria	1997	Any recordable offense that leads to imprisonment	Entered as suspect	Only after acquittal
The Netherlands	1997	No suspects entered except when suspect's DNA is tested for case	Offense leading to >4 years in prison	20–30 years after conviction
Germany	1998	Offense leading to >1 year in prison	After court decision	After acquittal or 5–10 years after conviction if prognosis good
Slovenia	1998	Any recordable offense that leads to imprisonment	Entered as suspect	Depends on severity of crime
United States	1998	No suspects entered; under revision	Depends on state law	Depends on state law
Finland	1999	Offense leading to >1 year in prison	Entered as suspect	Only after acquittal
Sweden	2000	No suspects entered	Offense leading to >2 years in prison	10 years after release from prison
Switzerland	2000	Any recordable offense that leads to imprisonment	Entered as suspect	After acquittal or 5–30 years after conviction
France	2001	No suspects entered	Sexual assaults and serious crimes	40 years after conviction

Source: Adapted from Jobling, M.A. and Gill, P., *Nat Rev Genet*, 5, 739–751, 2004.

Scientific Working Group of DNA Analysis and Methods (SWGDAM). The SDIS enables local laboratories within that state to compare DNA profiles. SDIS also serves as the communication path through which the LDIS and NDIS are able to exchange messages. Communication is mediated using a secured network with encryption. Only authorized personnel, approved by the FBI, have access to CODIS network terminals and servers. NDIS is the highest level of the CODIS infrastructure, which contains DNA profiles contributed by participating local and state



Figure 24.1 CODIS infrastructure. All DNA profiles originate at LDIS, and then enter SDIS and NDIS. SDIS allows laboratories within states to exchange DNA profiles. NDIS is the highest level of the infrastructure. It allows the participating laboratories to exchange DNA profiles on a national level.

laboratories. Additionally, NDIS stores DNA profiles generated by federal laboratories, such as those generated by the FBI and the US Army Criminal Investigation Laboratory. NDIS enables qualified state laboratories to compare DNA profiles. Searches of DNA profiles can be conducted at the national level. All DNA profiles submitted to NDIS are automatically searched weekly against the DNA profiles from other states. NDIS is administered by the FBI, which provides software, training, and support for all participating laboratories. Many law enforcement laboratories from other countries utilize the CODIS software for their own databases. However, laboratories in foreign countries do not have any access to the CODIS system. Nevertheless, a search through the CODIS database may be requested either from the FBI or International Criminal Police Organization (Interpol). Conversely, a search of an international DNA database can be arranged through Interpol.

24.3 Indexes of CODIS

The DNA profiles entered in CODIS are organized into categories known as indexes (Figure 24.2). The Convicted Offender Index contains DNA profiles of individuals convicted of crimes. The Arrestee Index contains DNA profiles of arrested individuals. It varies in SDIS databases based on each state's law permitting the collection of DNA samples from arrestees. The Forensic Index contains DNA profiles, also known as forensic profiles, derived from crime scene evidence, potentially originating from perpetrators but not including suspects.

Additionally, the FBI also established the National Missing Person DNA Database (NMPDD) Program for the identification of missing and unidentified persons at the national level. The DNA profiles entered into the NMPDD are categorized into three indexes that can be searched against each other. The Missing Person Index and the Unidentified Human Remains Index contain DNA profiles from missing persons and unidentified human remains, respectively. The Biological Relatives of the Missing Person Index contains DNA profiles voluntarily contributed from relatives. This index may also store patrilineal or matrilineal DNA profiles from the relative such as a biological father, mother, or child of the missing person to assist investigations. Additionally, a pedigree chart (a diagram showing the relationship between the missing person and relatives) can be created.



Figure 24.2 Example of an SDIS maintaining the Forensic Index (red) and Convicted Offender Index (blue). In this example, the New York State Police Forensic Investigation Center serves as the SDIS laboratory for New York State. LDIS sites: 1. Erie County Department of Central Police Services Forensic Laboratory, 2. Monroe County Public Safety Laboratory, 3. Nassau County Office of the Medical Examiner Division of Forensic Services, 4. New York City Office of the Chief Medical Examiner Department of Forensic Biology, 5. New York State Police Forensic Investigation Center, 6. Onondaga County Center for Forensic Sciences, 7. Suffolk County Crime Laboratory, and 8. Westchester County Department of Laboratories & Research Division of Forensic Sciences. (© Richard C. Li.)

In 2010, the FBI established a Rapid DNA Program Office for the purpose of developing rapid DNA technology. Rapid DNA technology is a fully automated process of performing STR analysis within 1–2 h to generate a CODIS core STR profile from a reference sample such as a buccal swab (Figure 24.3). The Rapid DNA Index System (RDIS) is the proposed index of NDIS. It shall be an integrated system capable of applying rapid DNA technology and carrying out database searches from police custody or booking units by trained police officers. The entire process, including obtaining any match from a database search, shall take less than 2 h.

The forensic DNA analysis of a reference sample, taken from an individual, takes 2–3 days if processed immediately in a forensic laboratory. The entire process includes the extraction of DNA from a sample, DNA quantification, PCR amplification, electrophoresis, and data collection and analysis. After being transported to a laboratory for processing, samples are usually stored and batched in laboratories prior to analysis. A typical turnaround time for analysis of such a sample is 1–3 months. While the sample is processed, the suspect is often released from custody. Perpetrators released on police bail may commit another crime. Thus, it is desirable to develop new technology that is capable of completing the forensic DNA analysis and database search while the suspect remains in custody. This technology would also facilitate rapid exclusion of a suspect, thus redirecting the investigation.

Rapid DNA instruments are portable, compact instruments designed to be deployed into field testing. These instruments are fully automated for processing reference samples in order to generate a DNA profile in less than 2 h. Several versions of the instruments have recently been developed by manufacturers and some of them are currently commercially available. In addition to rapid DNA instruments, rapid DNA profiling may be achieved through alternative processes. First, it can be achieved through rapid services that offer a quick turnaround time (<2 h). Second,



Figure 24.3 A rapid DNA instrument. A compact instrument that is designed to process swab samples and to produce DNA profiles within 2 h in the field. (© Richard C. Li.)

rapid DNA techniques can be applied using standard laboratory equipment but implementing specialized protocols to generate CODIS-compatible profiles in less than 2 h.

The primary goal of the rapid DNA initiative is to produce a CODIS-compatible DNA profile of a sample taken from an arrestee in police custody and to search DNA databases during the booking process in less than 2 h. This technology could be used, for example, to quickly identify other unsolved crimes or eliminate suspects, which can aid in investigative decision making. It can also potentially be useful for other investigations, such as identifying human remains in mass disasters; identifying detainees in counterterrorism applications; and, for immigration and border agents, confirming and verifying individual identifications or family relationships.

24.4 Database Entries

Currently, over 190 public law enforcement laboratories participate in CODIS across the United States. As of April 2013, CODIS contains the DNA profiles of more than 10 million convicted felons, over 1 million arrestees, and half a million crime scene samples. The proportion of the population represented in the database is approximately 3%. The NDIS is one of the largest DNA databases containing DNA profiles in terms of absolute numbers. Each CODIS entry consists of the DNA profile of the sample and the specimen identification number, as well as the information of the laboratory submitting the DNA profile and the laboratory analyst that performed the DNA analysis. The entry does not include case information or the personal information of the offenders or arrestees. Access to CODIS profiles is restricted to criminal justice agencies for law enforcement identification purposes.

The SDIS database retains samples collected from convicted offenders after DNA profiles are obtained. State policies vary in the retention of samples and DNA profiles in situations of dismissed charges, acquittal, or no charges for arrestees. Some states, such as Virginia, destroy the DNA sample and expunge the DNA profile from the database. Other states, such as California, require a petition to destroy the sample and expunge the DNA profile from the database. There are two major reasons for sample retention. First, the sample is needed for confirmatory processes for the purpose of quality assurance and control. In confirmatory processes, the DNA analysis of the original sample is repeated and compared against the prior analysis. Second, the retention of samples allows for possible retesting if new technology becomes available. It also allows retesting of a sample for purposes of updating with expanded loci. Considerable debate has surrounded the retention of samples. It can be argued from the opposite perspective that the database could reveal private genetic information that could then be misused. The objection is based on concern for the protection of privacy rights. If a sample were made available to an unauthorized person, confidential information could be disclosed.

24.5 Database Expansion

Currently, all 50 states have authorized the collection of samples from convicted felons for DNA databasing. Over the years, the demand for the utilization of databases has increased sharply (Figure 24.4). More jurisdictions are incorporating more felonies into the lists of crimes that require DNA profiles, and some jurisdictions plan to include all felonies in such databases. Additionally, the database system is projected to include the profiles of minor criminals, because statistics show that most offenders found guilty of serious crimes were previously convicted for minor crimes. Broadening the size of the database and including samples from more types of crimes could lead to the assumption that the number of crimes solved would also increase. Although state laws vary, each state has its own statute governing the entry criteria of the database samples. More and more states are authorizing the collection of additional types of DNA samples, including individuals convicted of misdemeanor crimes and adult felony arrestees who have not yet been convicted for the offense. It is known that offenders tend to commit multiple



Figure 24.4 Growth of the CODIS database. In 2000, 460,365 offender profiles and 22,484 forensic profiles were entered.

crimes. Thus, including DNA profiles of arrestees in the database is beneficial in catching serial offenders and potentially preventing future crimes. Virginia is the first state to collect DNA from violent-felony arrestees, among other crimes. Over the years, more than half of states in the United States have amended their law to include all felony arrestees or a subset of arrestees for felonies that involve violence or sexual assault.

In 2009, Alonzo King was arrested in Wicomico County, Maryland, on violent assault charges. Maryland's DNA Collection Act authorizes law enforcement agencies to collect DNA samples from an individual who is arrested for violent crimes. During the booking process, under state law, King's buccal swabs were collected for forensic DNA identification. When King's DNA profile was entered into Maryland's SDIS, it matched to a crime scene DNA profile from an unsolved rape case in 2003. Based on the DNA evidence, King was indicted for first-degree rape by a grand jury. The defendant filed a motion to suppress the DNA evidence. King argued that using his DNA to investigate his connection to the 2003 rape was an unreasonable search and seizure under the Fourth Amendment, since the police had no reason to suspect his involvement in the 2003 rape. During the trial at Wicomico County Circuit Court, King's motion was denied. He was convicted of rape and sentenced to life in prison. The Court of Appeals of Maryland, the state's highest court, upheld that the DNA Collection Act was constitutional. The police had probable cause to arrest King on the assault charge, and thus collecting King's DNA sample was a reasonable search. However, the court overturned the low court and reversed King's conviction. It stated that the DNA Collection Act was inappropriately applied to King in this case. Thus, investigating King without probable cause for the unrelated rape was unconstitutional. To determine whether the Fourth Amendment permits states to collect and analyze the DNA of arrestees, a divided Supreme Court ruled 5–4 and reversed the Court of Appeals. The Supreme Court's judgment ruled that Maryland has the right to collect DNA evidence from individuals arrested for serious crimes. The ruling reflects the Supreme Court's view on the balance between the interest of criminal justice systems in solving violent crimes and an individual's interest in the Fourth Amendment, which protects them from unreasonable searches.

Some jurisdictions, such as the United Kingdom, allow DNA samples to be taken from individuals suspected of committing recordable offenses that may lead to prison sentences. In contrast, DNA profiles from suspects are not eligible for entry into CODIS. In some jurisdictions, it has been suggested that databases include many more offenders and suspects, as well as the general public. One advantage of including an entire population in a database is the ability to identify missing, kidnapped, and abducted individuals in addition to victims of major accidents and mass fatalities. Nevertheless, debates concerning the need to balance the benefits and dangers of developing a broader database will inevitably continue.

24.6 DNA Profiles

Currently, the CODIS software supports the storage and search of DNA profiles of short tandem repeat (STR), Y chromosome STR (Y-STR), and mitochondrial DNA (mtDNA). Y-STR and mtDNA profiles may only be searched within NMPDD-related indexes. The CODIS software no longer supports searches of DNA profiles generated by restriction fragment length polymorphism (RFLP) analysis. The 13 core CODIS STR loci are CSF1PO, FGA, THO1, TPOX, VWA, D3S1358, D5S818, D7S820, D8S1179, D13S317, D16S539, D18S51, and D21S11. DNA profiles are entered into one of the indexes, such as convicted offender, arrestee, forensic, unidentified human remains, missing person, or a relative of a missing person. There is a minimum loci requirement for each DNA profile entering CODIS: 13 core CODIS loci are required for a DNA profile entering the Convicted Offender Index and the Arrestee Index; 13 core CODIS loci and amelogenin, a sex-typing marker, are required for a DNA profile entering the Relatives of Missing Person Index; at least 10 CODIS loci are required (all 13 core loci must be tested) for the Forensic Index; and at least 8 loci and amelogenin are required (all 13 core loci must be tested) for the Missing Person and Unidentified Human Remains Index. The DNA profiles must be generated by an accredited and audited laboratory in accordance with the FBI's Quality Assurance Standards using approved commercially available kits. As the database is growing rapidly, the chances of finding incidental matches among DNA profiles is increasing. To increase discrimination power, it has recently been proposed that CODIS core loci be expanded to include 20 or more markers (Chapter 20). Additionally, the expanded core loci share additional loci compatible with international standards for forensic DNA analysis, which facilitates the exchange of information with international law enforcement agencies.

24.7 Routine Database Searches for Forensic Investigations

The ultimate goal of the database utilization is to provide investigative leads for law enforcement in solving crimes, particularly in cases where no suspect has yet been identified. Currently, DNA profiles uploaded to NDIS are automatically searched once a week (Figure 24.5). A hit is a match made from the information provided by comparing a target DNA profile against the DNA profiles contained in the database. There are two types of CODIS hits: an *offender hit* provides the identity of a potential suspect of a crime, while a *forensic hit* reveals the linkage between two or more crime scenes. Once a hit is identified, the match is verified by the laboratories that originally processed the evidence. A verified CODIS hit can be utilized as probable cause to allow law enforcement to obtain a court order to collect a DNA sample from a suspect. Collecting DNA with a warrant ensures admissibility in court. *Investigation-aided* cases are those assisted by CODIS hits, including case-to-case matches as well as case-to-offender matches. The number of investigations aided is a useful measure of the successful application of the database (Figure 24.6). As of April 2013, over 207,800 hits had been made with CODIS assistance in more than 199,200 investigations.

24.7.1 Case-to-Offender Searches

Matches of profiles from the Forensic Index and the Offender Index reveal the identities of perpetrators of crimes. For example, in 1998, a Florida man, Leon Dundas, became a suspect in a rape case but refused to provide his DNA reference sample for testing. Dundas was killed a year later in an illegal drug deal. Thus, a postmortem sample of Dundas was obtained and his DNA profile was compared with the Forensic Index of CODIS. It was discovered that Dundas's profile



Figure 24.5 Example of a weekly routine CODIS search. (© Richard C. Li.)



Figure 24.6 Number of hits and investigations aided by the CODIS database.

matched the DNA sample found in the rape case. Additionally, his DNA profile was linked to several other unsolved rapes in Jacksonville and Washington, DC. Such cases can now be solved by utilizing DNA databases.

24.7.2 Case-to-Case Searches

A target DNA profile from a crime scene is also searched against the profiles stored in the Forensic Index of the database. Matches of profiles among the target profile and the profile in the Forensic Index can link separate crime scenes and aid in identifying serial offenders. This helps law enforcement agencies in multiple jurisdictions to coordinate their investigations and share leads. For example, in 1996, two young girls were abducted from bus stops in St. Louis. Both girls were raped and DNA samples were collected. Both DNA profiles pointed to the same perpetrator. In 1999, the St. Louis police decided to reanalyze the samples using new STR technology through the CODIS database. The database found a match to a different rape case, to which the perpetrator, Dominic Moore, had already confessed, thus identifying him as the perpetrator of the 1996 rapes.

24.7.3 Search Stringency and Partial Matches

Database searches are carried out using the CODIS software with three stringency levels, which allow the search of complex forensic profiles against offender profiles (Figure 24.7). A high-stringency match requires an exact match in which all alleles are matched at each locus between the target and candidate profiles. A moderate-stringency match, as defined by the FBI, is a candidate match "between two single source profiles having at each locus all of the alleles of one sample represented in the other sample." In a moderate-stringency match, allelic drop-outs in a target or candidate profile are allowed, possibly resulting in a partial match at some loci. As a result, high-stringency matches are automatically included in a moderate-stringency



Figure 24.7 Diagram of match stringencies. A heterozygote (allele 14 and 15) at locus D3S1358 is utilized as the genotype for the forensic unknown profile. (© Richard C. Li.)

search. In a low-stringency search, both mismatches and allelic dropouts are allowed. Presently, NDIS searches are only carried out at moderate stringency. During forensic DNA analysis, DNA degradation may prevent full DNA profiles from being processed, producing only partial profiles. Additionally, mixture profiles derived from forensic samples containing DNA contributed by more than one individual may be encountered. Furthermore, due to mutations, null alleles may occur in the profiles produced with some primer sets but not other primers. Therefore, searching at moderate stringency allows the detection of matches under the situations described above.

Such moderate-stringency searches between the Forensic Index and Offender Index may occasionally generate partial match profiles. Since a partial match is not an exact match of the two profiles, further investigation is needed. For instance, additional Y-STR and mtDNA analysis is needed to eliminate unrelated individuals.

24.8 Familial Searches

Familial search, initiated in the United Kingdom, is a new method of applying databases in criminal investigations. It is known that, in the United States, nearly half of prison inmates have close relatives who have also been incarcerated. Familial search is based on the assumption that close relatives share more alleles of DNA profiles than unrelated individuals. Thus, databases may be utilized to identify perpetrators by finding a close relative, if the close relative has been convicted of a crime and is listed in the database. Familial search is an intentional search of a target crime scene profile against an offender database to obtain a list of candidate profiles that are similar to the target profile. This list may include the profile of a close relative of the perpetrator, who is the source of crime scene evidence. These matches most frequently involve siblings, parents, or children. The investigative leads produced by familial searches allow law enforcement to conduct further investigations to identify the perpetrator.

The first familial search leading to a successful prosecution was conducted in Surrey, England. In 2003, a truck driver was killed after a brick was thrown through his windshield from a bridge. The perpetrator's DNA profile was obtained from the brick. A search of the UK's national DNA database revealed no match for the perpetrator. Next, a familial search of the database was conducted. The system identified a close relative that led police to identify the perpetrator, Craig Harman, who was then convicted of manslaughter.

24.8.1 Legal and Ethical Issues of Familial Search

The use of forensic databases involves a balance of individual civil rights and the interests of the criminal justice systems. Many concerns have been raised, including the potential for these searches to violate the privacy of unrelated people whose genetic profiles happen to resemble those of individuals included in the databases. In the United States, the Fourth Amendment protects against unreasonable searches and seizures. The permissibility of familial searching under the Fourth Amendment is yet to be addressed by courts. The collection of biological material for the initial creation of a profile for law enforcement purposes is subject to the Fourth Amendment implications. In terms of familial searches, some legal experts argue that the biological materials are not collected directly from the individuals for a familial search, and that these individuals may thus be protected under the Fourth Amendment. Others argue, however, that the Fourth Amendment protects the initial creation of the profile, including the sample collection, forensic DNA analysis, and the databasing. They argue that the Fourth Amendment may not protect subsequent investigations of DNA profiles during familial searches. In addition, the CODIS database consists of a high percentage of profiles from individuals of racial minority groups, including African Americans. Familial searches can disproportionately focus on a specific racial group.

Familial searches are rare in the United States. Two jurisdictions, Maryland and the District of Columbia, have laws prohibiting the use of familial searches. Familial searches are not conducted at the NDIS. While familial searches are now being performed in several jurisdictions in the United States, policies on familial searches vary among jurisdictions. The major issues relate to criteria for privacy, information release, search approval, and the types of crimes eligible for familial searches. Currently, California, Colorado, Texas, and Virginia have state legislation permitting familial searches. Familial searches are initiated when a specific suspect is not known, and the cause for the search needs to be justified. Familial searches are usually conducted for crimes that pose a substantial threat to public safety, typically those cases involving the most serious offenses. Additionally, familial searches are only conducted after a routine search of a DNA profile has yielded no match in the database.

In 2003, for example, a crime scene DNA sample of a closed rape and murder case, committed decades previously, was reanalyzed using forensic DNA techniques. The crime scene DNA profile was compared to the profile of a man, Darryl Hunt, who was then imprisoned for the crime. Surprisingly, the crime scene DNA profile did not match either that of Hunt or those of convicted felons in the database. However, the database search revealed a close relative of the true perpetrator and thus led law enforcement to identify Willard Brown as the perpetrator. Brown was sentenced to life imprisonment. Additionally, Hunt was exonerated after 18 years in prison.

24.8.2 Familial Search Strategies

The familial search is usually carried out using specially designed software. Although the CODIS software is not designed for familial search, it can be used for familial search through a low-stringency search, which may result in a list of candidate profiles including close relatives of individuals, such as parent–offspring or full-sibling relatives. In a large offender DNA database, similar DNA profiles from unrelated people are often observed due to shared alleles. Therefore, the candidate profile list may also include unrelated individuals whose DNA profiles are similar to the target profile. As a result, a familial search can provide a list of potential candidates consisting of hundreds of profiles, which would be too labor intensive to pursue through further investigations. Several methods can be used to determine a cutoff analytical threshold in order to limit a pool of candidate profiles and exclude unrelated individuals from familial searches (Figure 24.8).

24.8.2.1 Identity-by-State and Kinship Index Method

The *identity-by-state* (IBS) method compares the number of shared alleles and loci between a target forensic profile and the offender profiles in a database but does not take into account allele frequencies. The analytical threshold for a familial search is determined by a preset number of shared alleles or loci in order to prompt further investigation. For example, some states use 15 shared alleles as the analytical threshold to be considered as a candidate, while other states require at least one shared allele for each locus. Additionally, this method can prioritize a pool of candidates based on the highest to the lowest number of shared alleles for investigation.

The *Kinship Index* (KI) method is a likelihood ratio–based method that evaluates the familial match by comparing the probability that two DNA profiles are from related individuals to the probability that they are unrelated. The KI method analyzes the allele frequency data, including all CODIS core loci, to calculate the Combined Kinship Index. The KI may vary based on the allele frequency data across the population. Thus, the accuracy of the KI method relies on the relevance of the population data set analyzed. False inclusions or exclusions may occur if nonrelevant population data are utilized. The KI method also allows the generation of a ranked candidate list according to the probability that the individuals are related. Generally speaking, the accuracy of the KI method is higher than that of the IBS method. However, using both IBS and KI methods is better than using a single method alone for familial search.

24.8.2.2 Focusing on Rare Alleles

During a familial search, target DNA profiles may contain rare alleles with low allelic frequencies. The chance of sharing rare alleles for two close relatives is higher than for two unrelated individuals. If a target profile carries a rare allele, it can be used to narrow the pool of candidates.

For example, Jeffrey Gafoor, then 23, had been living in a suburban neighborhood in Cardiff, Wales. He had a reputation for being a loner. Besides working in his family-owned shop, he spent most of his time at home. On February 13, 1988, Gafoor entered 7 James Street in the Butetown area of Cardiff. The first-floor unit was temporarily occupied by Lynette White, a 20-year-old


Serial criminal case, investigative leads are exhausted
Familial search
Partial match approach
Targeted search approach
IBS method
KI method
Rare allele method
List of candidates
Excluding candidates: Y-STR screening
Utilizing public records: Identifying candidate's relative
Further investigation: Comparing DNA from the relative and the crime scene
Case solving

Figure 24.8 Example of a familial search workflow. (© Richard C. Li.)

woman who was working as a prostitute in the area. Gafoor went there for the purpose of receiving sexual services. He left the scene in the early hours of Valentine's Day. On Valentine's night, White's body was discovered. She suffered from more than 50 stab, cut, and slash wounds as well as defensive wounds on her hands. The body was dragged to the corner of the room adjacent to the bed, the only piece of furniture in the room.

Gafoor left blood and semen evidence at the scene. He bled during the murder and deposited bloodstains at the scene. Additionally, he left seminal stains at the scene; the semen had no measurable level of sperm and most likely came from an individual who had a medical condition known as azoospermia (Chapter 14). After the murder, Gafoor lived at the same place as he did beforehand and kept the same job for many years.

Two years later, three local men, known as the "Cardiff Three," were convicted of White's murder and sentenced to life in prison. In 1992, however, their convictions were reversed by the court of appeal. Subsequently, the crime scene evidence was tested using new techniques in forensic DNA analysis that were not available in 1988. A DNA profile was obtained from the crime scene. A familial search revealed a similar profile from a 14-year-old boy in the UK National DNA Database. In particular, there was a rare allele match between the crime scene and the candidate DNA profiles. This search led to the further investigation of Gafoor, who was the uncle of the boy. Gafoor was charged with murder.

24.8.2.3 Excluding Candidates through Y-STR Screening

The vast majority of DNA profiles in CODIS come from males. Patrilineal markers, such as Y-STR loci, are successfully utilized to screen the candidates to verify the relationship between two individuals. This analysis helps to identify first-order relatives as well as paternal half-siblings. STR loci beyond the CODIS core loci and maternal lineage makers, such as mitochondrial DNA typing systems, can be used to narrow the pool of candidates and eliminate coincidental partial matches. One or more of these methods can be incorporated to evaluate highly ranked candidates.

For example, Lonnie Franklin lived in a southern Los Angeles neighborhood. Throughout the 1980s, Franklin worked for the city as a maintenance worker and a sanitation truck operator. His neighbors recalled that he often brought prostitutes to a camper parked in the backyard of his house. He also took photos of nude women, which he kept in his garage. Nevertheless, to many of his neighbors, Franklin seemed to be a friendly person who often chatted with them.

Since 1985, the bodies of many women, most of which were prostitutes, had been dumped in an alley running along Western Avenue in a southern Los Angeles neighborhood. The victims had been shot and some had been strangled after sexual contact. DNA and ballistics analysis revealed that at least 10 of the murders had been committed by the same perpetrator. The perpetrator was known to the general public as the “Grim Sleeper” because he had taken a 14-year break during the period in which these 10 murders had taken place. The crime scene DNA profile did not match any profile in the database.

In 2008, the first familial search of the “Grim Sleeper” case was conducted by the California Department of Justice. California state law allows familial searches for high-profile cases if all other leads have been exhausted. However, all candidate DNA profiles were excluded through Y-STR screening. As a result, no candidate was identified as a possible relative of the “Grim Sleeper.” In 2010, a second search targeted partial matches that shared at least 15 alleles. It produced a list of 100 candidate profiles ranked by the likelihood that they were related. Y-STR was used as a screen tool to identify possible patrilineal relatives. This time, the search generated a match to a new DNA profile of a felon, which had recently been entered into California’s SDIS, in 2009. The search suggested that the candidate was a relative of the source of the DNA from the crime scenes. This search led to the identification of Franklin as a suspect in the “Grim Sleeper” murders. Police detectives conducted surveillance and collected a discarded slice of pizza and a cup used by Franklin at a local restaurant for DNA identification. The DNA profile was identical to the crime scene DNA profiles. Franklin was arrested and was charged with ten counts of murder and one of attempted murder.

Bibliography

Alonso, A., et al., Challenges of DNA profiling in mass disaster investigations. *Croat Med J*, 2005, **46**(4): 540–548.

Aoki, Y., et al., Comparison of the likelihood ratio and identity-by-state scoring methods for analyzing sib-pair test cases: A study using computer simulation. *Tohoku J Exp Med*, 2001, **194**(4): 241–250.

Asplen, C. and S.A. Lane, International perspectives on forensic DNA databases. *Forensic Sci Int*, 2004, **146**(Suppl): S119–S121.

Baker, L.E. and E.J. Baker, Reuniting families: An online database to aid in the identification of undocumented immigrant remains. *J Forensic Sci*, 2008, **53**(1): 50–53.

Balding, D.J., The DNA database search controversy. *Biometrics*, 2002, **58**(1): 241–244.

Balding, D.J., et al., Decision-making in familial database searching: KI alone or not alone? *Forensic Sci Int Genet*, 2013, **7**(1): 52–54.

Barash, M., et al., A search for obligatory paternal alleles in a DNA database to find an alleged rapist in a fatherless paternity case. *J Forensic Sci*, 2012, **57**(4): 1098–1101.

Barber, M.D. and B.H. Parkin, Sequence analysis and allelic designation of the two short tandem repeat loci D18S51 and D8S1179. *Int J Legal Med*, 1996, **109**(2): 62–65.

Benschop, C.C., et al., Low template STR typing: Effect of replicate number and consensus method on genotyping reliability and DNA database search results. *Forensic Sci Int Genet*, 2011, **5**(4): 316–328.

Bereano, P.L., DNA identification systems: Social policy and civil liberties concerns. *J Int Bioethique*, 1990, **1**(3): 146–155.

Bieber, F.R. and D. Lazer, Guilt by association: Should the law be able to use one person's DNA to carry out surveillance on their family? Not without a public debate. *New Sci*, 2004, **184**(2470): 20.

Bieber, F.R., Turning base hits into earned runs: Improving the effectiveness of forensic DNA data bank programs. *J Law Med Ethics*, 2006, **34**(2): 222–233.

Bingham, R., A database of the innocent? *Splice Life*, 2001, **7**(2–3): 8–9.

Birmingham, K., UK leads on science and technology bioethics. *Nat Med*, 1998, **4**(6): 651–652.

Bradford, L., et al., Disaster victim investigation recommendations from two simulated mass disaster scenarios utilized for user acceptance testing CODIS 6.0. *Forensic Sci Int Genet*, 2011, **5**(4): 291–296.

Buckleton, J., J.A. Bright, and S.J. Walsh, Database crime to crime match rate calculation. *Forensic Sci Int Genet*, 2009, **3**(3): 200–201.

Budowle, B., et al., CODIS and PCR-based short tandem repeat loci: Law enforcement tools, in *Second European Symposium on Human Identification*, 1998. Innsbruck, Austria: Promega Corporation.

Burk, D.L., DNA identification testing: Assessing the threat to privacy. *Univ Toledo Law Rev*, 1992, **24**(1): 87–102.

Burk, D.L. and J.A. Hess, Genetic privacy: Constitutional considerations in forensic DNA testing. *Geoge Mason Univ Civ Rights Law J*, 1994, **5**(1): 1–53.

Cash, H.D., J.W. Hoyle, and A.J. Sutton, Development under extreme conditions: Forensic bioinformatics in the wake of the World Trade Center disaster. *Pac Symp Biocomput*, 2003, **8**: 638–653.

Chow-White, P.A. and T. Duster, Do health and forensic DNA databases increase racial disparities? *PLoS Med*, 2011, **8**(10): e1001100.

Chung, Y.K. and W.K. Fung, Identifying contributors of two-person DNA mixtures by familial database search. *Int J Legal Med*, 2013, **127**(1): 25–33.

Chung, Y.K., Y.Q. Hu, and W.K. Fung, Evaluation of DNA mixtures from database search. *Biometrics*, 2010, **66**(1): 233–238.

Corte-Real, F., Forensic DNA databases. *Forensic Sci Int*, 2004, **146**(Suppl): S143–S144.

Curran, J.M. and J.S. Buckleton, Effectiveness of familial searches. *Sci Justice*, 2008, **48**(4): 164–167.

Dawid, A.P., Comment on Stockmarr's "Likelihood ratios for evaluating DNA evidence when the suspect is found through a database search". *Biometrics*, 2001, **57**(3): 976–980.

Duster, T., Explaining differential trust of DNA forensic technology: Grounded assessment or inexplicable paranoia? *J Law Med Ethics*, 2006, **34**(2): 293–300.

Evett, I.W., J. Scranage, and R. Pinchin, Efficient retrieval from DNA databases: Based on the second European DNA Profiling Group collaborative experiment. *Forensic Sci Int*, 1992, **53**(1): 45–50.

Evison, M., DNA database could end problem of identity fraud. *Nature*, 2002, **420**(6914): 359.

Gabriel, M., C. Boland, and C. Holt, Beyond the cold hit: Measuring the impact of the national DNA data bank on public safety at the city and county level. *J Law Med Ethics*, 2010, **38**(2): 396–411.

Gamero, J.J., et al., A study of Spanish attitudes regarding the custody and use of forensic DNA databases. *Forensic Sci Int Genet*, 2008, **2**(2): 138–149.

Ge, J., et al., Comparisons of familial DNA database searching strategies. *J Forensic Sci*, 2011, **56**(6): 1448–1456.

Gershaw, C.J., et al., Forensic utilization of familial searches in DNA databases. *Forensic Sci Int Genet*, 2011, **5**(1): 16–20.

Gill, P., et al., Databases, quality control and interpretation of DNA profiling in the hHome Office fForensic sScience sService. *Electrophoresis*, 1991, **12**(2–3): 204–209.

Gill, P., et al., A comparison of adjustment methods to test the robustness of an STR DNA database comprised of 24 European populations. *Forensic Sci Int*, 2003, **131**(2–3): 184–196.

Gill, P., et al., The evolution of DNA databases—Recommendations for new European STR loci. *Forensic Sci Int*, 2006, **156**(2–3): 242–244.

Gosline, A., Will DNA profiling fuel prejudice? *New Sci*, 2005, **186**(2494): 12–13.

Guillen Vazquez, M., C. Pestoni, and A. Carracedo, DNA databases for criminal investigation purposes: Technical aspects and ethical–legal problems. *Law Hum Genome Rev*, 1998, (8): 137–158.

Guillen, M., et al., Ethical-legal problems of DNA databases in criminal investigation. *J Med Ethics*, 2000, **26**(4): 266–271.

Haimes, E., Social and ethical issues in the use of familial searching in forensic investigations: Insights from family and kinship studies. *J Law Med Ethics*, 2006, **34**(2): 263–276.

Harbison, S.A., J.F. Hamilton, and S.J. Walsh, The New Zealand DNA databank: Its development and significance as a crime solving tool. *Sci Justice*, 2001, **41**(1): 33–37.

Harding, H.W. and R. Swanson, DNA database size. *J Forensic Sci*, 1998, **43**(1): 248–249.

Hedman, J., et al., A fast analysis system for forensic DNA reference samples. *Forensic Sci Int Genet*, 2008, **2**(3): 184–189.

Heninger, M. and R. Hanzlick, The Fulton County Medical Examiner's experience with the Federal Bureau of iInvestigation National Missing Person DNA Database Program, 2004–2007. *Am J Forensic Med Pathol*, 2011, **32**(1): 78–82.

Hepple, B., Forensic databases: Implications of the cases of S and Marper. *Med Sci Law*, 2009, **49**(2): 77–87.

Herkenham, M.D., Retention of offender DNA samples necessary to ensure and monitor quality of forensic DNA efforts: Appropriate safeguards exist to protect the DNA samples from misuse. *J Law Med Ethics*, 2006, **34**(2): 380–384.

Hibbert, M., DNA databanks: Law enforcement's greatest surveillance tool? *Wake Forest Law Rev*, 1999, **34**(3): 767–825.

Hicks, T., et al., Use of DNA profiles for investigation using a simulated national DNA database: Part I. Partial SGM Plus profiles. *Forensic Sci Int Genet*, 2010, **4**(4): 232–238.

Hicks, T., et al., Use of DNA profiles for investigation using a simulated national DNA database: Part II. Statistical and ethical considerations on familial searching. *Forensic Sci Int Genet*, 2010, **4**(5): 316–322.

Hoyle, R., Forensics. The FBI's national DNA database. *Nat Biotechnol*, 1998, **16**(11): 987.

Huang, D., et al., Y-haplotype screening of local patrilineages followed by autosomal STR typing can detect likely perpetrators in some populations. *J Forensic Sci*, 2011, **56**(5): 1340–1342.

Jobling, M.A. and Gill, P., Encoded evidence: DNA in forensic analysis. *Nat Rev Genet*, 2004, **5**: 739–751.

Karjala, D.S., A legal research agenda for the human genome initiative. *Jurimetrics*, 1992, **32**(2): 121–222.

Kim, J., et al., Policy implications for familial searching. *Investig Genet*, 2011, **2**: 22.

Kimel, C.W., DNA profiles, computer searches, and the Fourth Amendment. *Duke Law J*, 2013, **62**(4): 933–973.

Kirby, R., The many dangers of relying on a DNA database. *Nature*, 2002, **419**(6904): 247.

Lakra, R. and F. Dimitriadis, Forensic DNA data banks: Considerations for the health sector. *Health Law Can*, 2002, **22**(3): 57–70.

Lehrman, S., Prisoner's DNA database ruled unlawful. *Nature*, 1998, **394**(6696): 818.

Lehrman, S., Partial to crime: Families become suspects as rules on DNA matches relax. *Sci Am*, 2006, **295**(6): 28–29.

Levitt, M., Forensic databases: Benefits and ethical and social costs. *Br Med Bull*, 2007, **83**: 235–248.

Linacre, A., The UK National DNA Database. *Lancet*, 2003, **361**(9372): 1841–1842.

Love, S.H., Allowing new technology to erode constitutional protections: A Fourth Amendment challenge to non-consensual DNA testing of prisoners. *Villanova Law Rev*, 1993, **38**(5): 1617–1660.

Machado, H., F. Santos, and S. Silva, Prisoners' expectations of the national forensic DNA database: Surveillance and reconfiguration of individual rights. *Forensic Sci Int*, 2011, **210**(1–3): 139–143.

Maguire, C.N., et al., Familial searching: A specialist forensic DNA profiling service utilising the national DNA database to identify unknown offenders via their relatives—The UK experience. *Forensic Sci Int Genet*, 2014, **8**(1): 1–9.

Mansel, C. and S. Davies, Minors or suspects? A discussion of the legal and ethical issues surrounding the indefinite storage of DNA collected from children aged 10–18 years on the national DNA database in England and Wales. *Med Sci Law*, 2012, **52**(4): 187–192.

Marjanovic, D., et al., Forensic DNA databases in Western Balkan region: Retrospectives, perspectives, and initiatives. *Croat Med J*, 2011, **52**(3): 235–244.

Martin, P.D., H. Schmitter, and P.M. Schneider, A brief history of the formation of DNA databases in forensic science within Europe. *Forensic Sci Int*, 2001, **119**(2): 225–231.

McEwen, J.E. and P.R. Reilly, A review of state legislation on DNA forensic data banking. *Am J Hum Genet*, 1994, **54**(6): 941–958.

McEwen, J.E., Forensic DNA data banking by state crime laboratories. *Am J Hum Genet*, 1995, **56**(6): 1487–1492.

McNamara, J.J. and R.J. Morton, Frequency of serial sexual homicide victimization in Virginia for a 10-year period. *J Forensic Sci*, 2004, **49**(3): 529–533.

Meester, R. and M. Sjerps, The evidential value in the DNA database search controversy and the two-stain problem. *Biometrics*, 2003, **59**(3): 727–732.

Melson, K.E., President's editorial—The journey to justice. *J Forensic Sci*, 2003, **48**(4): 705–707.

Mohanty, N.K. and S. Haldar, DNA test—A forensic boon. *J Indian Med Assoc*, 2006, **104**(2): 90–92, 94.

Murphy, E., The government wants your DNA. *Sci Am*, 2013, **308**(3): 72–77.

Myers, S.P., et al., Searching for first-degree familial relationships in California's offender DNA database: Validation of a likelihood ratio-based approach. *Forensic Sci Int Genet*, 2011, **5**(5): 493–500.

Nerko, C.J., Assessing Fourth Amendment challenges to DNA extraction statutes after Samson v. California. *Fordham Law Rev*, 2008, **77**(2): 917–949.

Nishimi, R.Y., et al., Genetic witness: Forensic uses of DNA tests. *J Int Bioethique*, 1991, **2**(1): 29–32.

Oz, C., M. Amiel, and A. Zamir, The Israel police DNA database: Recognizing the capability of databases in providing investigative leads. *Forensic Sci Int Genet*, 2012, **6**(1): e8–e10.

Parson, W. and M. Steinlechner, Efficient DNA database laboratory strategy for high through-put STR typing of reference samples. *Forensic Sci Int*, 2001, **122**(1): 1–6.

Pascali, V.L., G. Lago, and M. Dobosz, The dark side of the UK National DNA Database. *Lancet*, 2003, **362**(9386): 834.

Patyn, A. and K. Dierickx, Forensic DNA databases: Genetic testing as a societal choice. *J Med Ethics*, 2010, **36**(5): 319–320.

Peerenboom, E., Central criminal DNA database created in Germany. *Nat Biotechnol*, 1998, **16**(6): 510–511.

Pham-Hoai, E., F. Crispino, and G. Hampikian, The first successful use of a low stringency familial match in a French criminal investigation. *J Forensic Sci*, 2014, **59**(3): 816–819.

Raab, S., Cuomo seeks genetic data of offenders. *N Y Times*, May 10, 1992.

Reid, T.M., et al., Use of sibling pairs to determine the familial searching efficiency of forensic databases. *Forensic Sci Int Genet*, 2008, **2**(4): 340–342.

Reilly, P., Rights, privacy, and genetic screening. *Yale J Biol Med*, 1991, **64**(1): 43–45.

Rohlfs, R.V., S.M. Fullerton, and B.S. Weir, Familial identification: Population structure and relationship distinguishability. *PLoS Genet*, 2012, **8**(2): e1002469.

Rohlfs, R.V., et al., The influence of relatives on the efficiency and error rate of familial searching. *PLoS One*, 2013, **8**(8): e70495.

Rossy, Q., et al., Integrating forensic information in a crime intelligence database. *Forensic Sci Int*, 2013, **230**(1–3): 137–146.

Sankar, P., The proliferation and risks of government DNA databases. *Am J Public Health*, 1997, **87**(3): 336–337.

Scheck, B., DNA data banking: A cautionary tale. *Am J Hum Genet*, 1994, **54**(6): 931–933.

Schneider, P.M. and P.D. Martin, Criminal DNA databases: The European situation. *Forensic Sci Int*, 2001, **119**(2): 232–238.

Scott, G., M.F. Marshall, and C. Tindall, Of doctors and detectives. *N Y Times Web*, November 20, 2001, F7.

Shapiro, E.D. and M.L. Weinberg, DNA data banking: The dangerous erosion of privacy. *Clevel State Law Rev*, 1990, **38**(3): 455–486.

Shriver, M., T. Frudakis, and B. Budowle, Getting the science and the ethics right in forensic genetics. *Nat Genet*, 2005, **37**(5): 449–450; author reply 450–451.

Simoncelli, T., Dangerous excursions: The case against expanding forensic DNA databases to innocent persons. *J Law Med Ethics*, 2006, **34**(2): 390–397.

Sjerps, M. and R. Meester, Selection effects and database screening in forensic science. *Forensic Sci Int*, 2009, **192**(1–3): 56–61.

Smith, J.C., The precarious implications of DNA profiling. *Univ Pittsbg Law Rev*, 1994, **55**(3): 865–888.

Song, Y.S., et al., Average probability that a "cold hit" in a DNA database search results in an erroneous attribution. *J Forensic Sci*, 2009, **54**(1): 22–27.

Struse, H.M. and I.D. Montoya, Health services implications of DNA testing. *Clin Lab Sci*, 2001, **14**(4): 247–251.

Sullivan, K., et al., New developments and challenges in the use of the UK DNA database: Addressing the issue of contaminated consumables. *Forensic Sci Int*, 2004, **146**(Suppl): S175–S176.

Swinbanks, D., UK plans library of DNA profiles. *Nature*, 1993, **365**(6447): 596.

Taborda, J.G. and J. Arboleda-Florez, Forensic medicine in the next century: Some ethical challenges. *Int J Offender Ther Comp Criminol*, 1999, **43**(2): 188–201.

Taylor, D., et al., An investigation of admixture in an Australian Aboriginal Y-chromosome STR database. *Forensic Sci Int Genet*, 2012, **6**(5): 532–538.

Terry, S.F. and P.F. Terry, A consumer perspective on forensic DNA banking. *J Law Med Ethics*, 2006, **34**(2): 408–414.

Tvedebrink, T., et al., Analysis of matches and partial-matches in a Danish STR data set. *Forensic Sci Int Genet*, 2012, **6**(3): 387–392.

Van Camp, N. and K. Dierickx, The retention of forensic DNA samples: A socio-ethical evaluation of current practices in the EU. *J Med Ethics*, 2008, **34**(8): 606–610.

Voultsos, P., et al., Launching the Greek forensic DNA database. The legal framework and arising ethical issues. *Forensic Sci Int Genet*, 2011, **5**(5): 407–410.

Walsh, S.J., J.M. Curran, and J.S. Buckleton, Modeling forensic DNA database performance. *J Forensic Sci*, 2010, **55**(5): 1174–1183.

Walsh, S.J., et al., The collation of forensic DNA case data into a multi-dimensional intelligence database. *Sci Justice*, 2002, **42**(4): 205–214.

Werrett, D.J., The national DNA database. *Forensic Sci Int*, 1997, **88**(1): 33–42.

Williams, R. and P. Johnson, "Wonderment and dread": Representations of DNA in ethical disputes about forensic DNA databases. *New Genet Soc*, 2004, **23**(2): 205–223.

Williams, R. and P. Johnson, Inclusiveness, effectiveness and intrusiveness: Issues in the developing uses of DNA profiling in support of criminal investigations. *J Law Med Ethics*, 2005, **33**(3): 545–558.

Zamir, A., et al., The Israel DNA database—The establishment of a rapid, semi-automated analysis system. *Forensic Sci Int Genet*, 2012, **6**(2): 286–289.

Zimmermann, B., et al., Application of a west Eurasian-specific filter for quasi-median network analysis: Sharpening the blade for mtDNA error detection. *Forensic Sci Int Genet*, 2011, **5**(2): 133–137.

25

Evaluation of the Strength of Forensic DNA Profiling Results

25.1 A Review of Basic Principles of Genetics

25.1.1 Mendelian Genetics

Mendel's first law is the principle of segregation of alleles. Each pair of alleles segregates from others in the formation of gametes (mature reproductive cells such as spermatozoa and oocytes). One-half of the gamete carries one allele, and the other half carries the other allele.

Mendel's second law is the principle of independent assortment of alleles. The segregation of each pair of alleles is independent of the segregation of other pairs during the formation of gametes.

Gametes are formed during a process known as *meiosis*, in which cells with haploid chromosome numbers (23 in humans) are produced by the division of cells with diploid chromosome numbers (46 in humans). A fertilized human egg thus contains a diploid number of chromosomes. A diploid is composed of 22 pairs of autosomes and 2 sex chromosomes (XX in females and XY in males).

Based on Mendelian principles, genes on different chromosomes assort independently of one another in gamete production. Genes residing very closely together on the same chromosome are usually inherited together. Thus, they do not assort independently and are called *linked genes*. Genes distant from each other on the same chromosome are usually inherited separately. This results from an exchange of segments between a pair of *homologous* chromosomes when the chromosomes are paired during the early phases of meiotic division. These types of gene-exchange events on homologous chromosomes are collectively called *crossing over*, which results in the *recombination* of genes in a pair of chromosomes (Figure 25.1).

The Mendelian inheritances of genes can often be measured using *probabilities*. A probability is the ratio of the number of actual occurrences of an event to the number of possible occurrences. Additionally, the probability of two independent events occurring simultaneously is the product of each of their individual probabilities; this is known as the *product rule of probability*.

Mendelian principles apply to the inheritance of loci of the autosomal nuclear DNA genome commonly used for forensic testing. The Y-chromosomal genome is inherited paternally, which does not obey the rules for Mendelian principles. Mitochondria contain their own mitochondrial genomes and are inherited maternally. This maternal inheritance



Figure 25.1 Crossing over hypothesis. Chromosomes are replicated prior to the first meiotic division. Each duplicate is called a chromatid, which forms into tetrads in the prophase. A crossover event occurs between the maternal and the paternal chromatids. Each chromatid breaks at the point of the cross and fuses with a portion of its counterpart. Chromosomes are associated with the microtubules during metaphase I and are pulled toward the spindle poles during anaphase I. The maternal and paternal homologs of one chromosome are shown. (© Richard C. Li.)

of mitochondrial genes also does not obey the rules for Mendelian principles. The inheritance of Y-chromosomal and mitochondrial genomes is referred to as non-Mendelian inheritance.

25.1.2 Population Genetics

Population genetics studies the causes of patterns of genetic variations within and among populations.

25.1.2.1 Allele Frequency

Allele frequency (p) can be calculated directly by counting the number of alleles of one type at a given locus and dividing it by the total number of alleles at that locus in a sampled population. This is called the *gene counting* method.

25.1.2.2 Genotype Frequency

Genotype frequency (P) observed at a given locus can be calculated by dividing the number of individuals with one genotype by the total number of individuals in a sampled population. Each genotype at the locus can be calculated separately. The summation of all genotype frequencies at that locus should equal 1.

25.1.2.3 Heterozygosity

Heterozygosity is the proportion of alleles, at a given locus, that are heterozygous and is calculated as

$$h = 1 - \sum_i p^2 \tag{25.1}$$

where:

h = heterozygosity
p = allelic frequency of the locus for homozygotes

The amount of heterozygosity at a locus in a sampled population is a measure of genetic variation. The higher the heterozygosity, the more variation there is at a given locus.

25.1.2.4 Hardy–Weinberg Principle

The Hardy–Weinberg (HW) principle, independently discovered by two scholars in the early 1900s, allows predictions of genotype frequencies to be made based on allelic frequencies. However, certain conditions must be met. The population must be large; mate randomly; and lack mutation, migration, and natural selection. If these conditions of the HW principle are met, the population will be in *equilibrium*, and the following results are expected:

1. The frequencies of the alleles will not change from one generation to the next.
2. Genotype frequencies can be predicted by the allelic frequencies (p^2 and q^2 for genotype frequencies of homozygotes and $2pq$ for genotype frequencies of heterozygotes). The sum of the genotype frequencies should equal 1.

$$p^2 + 2pq + q^2 = 1 \tag{25.2}$$

If the observed genotype proportions are different from those expected, one or more of the HW assumptions have been violated.

25.1.2.5 Testing for HW Proportions of Population Databases

To determine whether the genotypes of a population in question obey the HW principle, a population database can be constructed. Samples (usually 100–200 samples for STR loci) are collected and analyzed at the loci of interest. Allelic frequencies are obtained by using the gene counting method. Table 25.1 shows the allelic frequencies of CODIS loci from a population database. The *observed genotype frequencies* at a given locus, as described earlier in Section 25.1.2.2, are calculated by dividing the number of individuals with one genotype by the total number of individuals in the population sampled. The *expected genotype frequencies* are calculated using p^2, $2pq$, and q^2.

The observed and expected genotype frequencies are then compared using a chi-square test. The significance of the differences between observed and expected genotype frequencies can then be determined. The chi-square is calculated using the following formula:

$$\chi^2 = \sum_{i=1}^{n} \frac{\left(O_i - E_i\right)^2}{E_i} \tag{25.3}$$

where:

O_i = ith observed genotype frequency
E_i = ith expected genotype frequency
n = total number of genotypes

Chi-square (χ^2) is calculated as the sum of all genotypes of a given locus.

The chi-square value and the degrees of freedom (the number of genotypes minus the numbers of alleles) are then used to obtain a p value (not to be confused with the allelic frequency designated p) from a table of p values, and such tables can be found at the backs of most statistics textbooks. If the p value exceeds 0.05 (5% significance level), the deviation of the expected genotype frequencies from the observed genotype frequencies is not considered statistically significant. Thus, the null hypothesis that the observed genotype frequencies fit the expected genotype frequencies predicted by the HW principle is not rejected if the p value is greater than 0.05.

Table 25.1 Allelic Frequencies of 13 CODIS STR Loci

Allele	Allelic Frequency (%)		
	African American	Caucasian	Hispanic
D3S1358	(*N*=210)	(*N*=203)	(*N*=209)
<12	0.476	0.000	0.000
12	0.238	0.000	0.000
13	1.190	0.246	0.239
14	12.143	14.039	7.895
15	29.048	24.631	42.584
15.2	0.000	0.000	0.000
16	30.714	23.153	26.555
17	20.000	21.182	12.679
18	5.476	16.256	8.373
19	0.476	0.493	1.435
>19	0.238	0.000	0.239
VWA	(*N*=180)	(*N*=196)	(*N*=203)
11	0.278	0.000	0.246
13	0.556	0.510	0.000
14	6.667	10.204	6.158
15	23.611	11.224	7.635
16	26.944	20.153	35.961
17	18.333	26.276	22.167
18	13.611	22.194	19.458
19	7.222	8.418	7.143
20	2.778	1.020	1.232
21	0.000	0.000	0.000
FGA	(*N* = 180)	(*N* = 196)	(*N* = 203)
<18	0.278	0.000	0.000
18	0.833	3.061	0.246
18.2	0.833	0.000	0.000
19	5.278	5.612	7.882
19.2	0.278	0.000	0.000
20	7.222	14.541	7.143
20.2	0.000	0.255	0.246
21	12.500	17.347	13.054

Table 25.1 (Continued) Allelic Frequencies of 13 CODIS STR Loci

Allele	Allelic Frequency (%)		
	African American	Caucasian	Hispanic
21.2	0.000	0.000	0.246
22	22.500	18.878	17.734
22.2	0.556	1.020	0.493
22.3	0.000	0.000	0.000
23	12.500	15.816	14.039
23.2	0.000	0.000	0.739
24	18.611	13.776	12.562
24.2	0.000	0.000	0.000
24.3	0.000	0.000	0.000
25	10.000	6.888	13.793
26	3.611	1.786	8.374
27	2.222	1.020	3.202
28	1.667	0.000	0.246
29	0.556	0.000	0.000
30	0.278	0.000	0.000
>30	0.278	0.000	0.000
D8S1179	($N = 180$)	($N = 196$)	($N = 203$)
<9	0.278	1.786	0.246
9	0.556	1.020	0.246
10	2.500	10.204	9.360
11	3.611	5.867	6.158
12	10.833	14.541	12.069
13	22.222	33.929	32.512
14	33.333	20.153	24.631
15	21.389	10.969	11.576
16	4.444	1.276	2.463
17	0.833	0.255	0.739
18	0.000	0.000	0.000
D21S11	($N = 179$)	($N = 196$)	($N = 203$)
24.2	0.279	0.510	0.246
24.3	0.000	0.000	0.000

(*continued*)

Table 25.1 (Continued) Allelic Frequencies of 13 CODIS STR Loci

Allele	Allelic Frequency (%)		
	African American	Caucasian	Hispanic
26	0.279	0.000	0.000
27	6.145	4.592	0.985
28	21.508	16.582	6.897
29	18.994	18.112	20.443
29.2	0.279	0.000	0.246
30	17.877	23.214	33.005
30.2	0.838	3.827	3.202
30.3	0.000	0.000	0.000
31	9.218	7.143	6.897
31.2	7.542	9.949	8.621
32	0.838	1.531	1.232
32.1	0.000	0.000	0.000
32.2	6.983	11.224	13.547
33	0.838	0.000	0.000
33.2	3.352	3.061	4.187
34	0.838	0.000	0.000
34.2	0.279	0.000	0.493
35	2.793	0.000	0.000
35.2	0.000	0.255	0.000
36	0.559	0.000	0.000
>36	0.559	0.000	0.000
D18S51	($N = 180$)	($N = 196$)	($N = 203$)
<11	0.556	1.276	0.493
11	0.556	1.276	1.232
12	5.833	12.755	10.591
13	5.556	12.245	16.995
13.2	0.556	0.000	0.000
14	6.389	17.347	16.995
14.2	0.000	0.000	0.000
15	16.667	12.755	13.793
15.2	0.000	0.000	0.000
16	18.889	10.714	11.576

Table 25.1 (Continued) Allelic Frequencies of 13 CODIS STR Loci

Allele	Allelic Frequency (%)		
	African American	Caucasian	Hispanic
17	16.389	15.561	13.793
18	13.056	9.184	5.172
19	7.778	3.571	3.695
20	5.556	2.551	1.724
21	1.111	0.510	1.970
21.2	0.000	0.000	0.000
22	0.556	0.255	0.739
>22	0.556	0.000	1.232
D5S818	(*N* = 180)	(*N* = 195)	(*N* = 203)
7	0.278	0.000	6.158
8	5.000	0.000	0.246
9	1.389	3.077	5.419
10	6.389	4.872	6.650
11	26.111	41.026	42.118
12	35.556	35.385	29.064
13	24.444	14.615	9.606
14	0.556	0.769	0.493
15	0.000	0.256	0.246
>15	0.278	0.000	0.000
D13S317	(*N* = 179)	(*N* = 196)	(*N* = 203)
7	0.000	0.000	0.000
8	3.631	9.949	6.650
9	2.793	7.653	21.921
10	5.028	5.102	10.099
11	23.743	31.888	20.197
12	48.324	30.867	21.675
13	12.570	10.969	13.793
14	3.631	3.571	5.665
15	0.279	0.000	0.000
D7S820	(*N* = 210)	(*N* = 203)	(*N* = 209)
6	0.000	0.246	0.239

(*continued*)

Table 25.1 (Continued) Allelic Frequencies of 13 CODIS STR Loci

Allele	Allelic Frequency (%)		
	African American	Caucasian	Hispanic
7	0.714	1.724	2.153
8	17.381	16.256	9.809
9	15.714	14.778	4.785
10	32.381	29.064	30.622
10.1	0.000	0.000	0.000
11	22.381	20.197	28.947
11.3	0.000	0.000	0.000
12	9.048	14.039	19.139
13	1.905	2.956	3.828
14	0.476	0.739	0.478
CSF1PO	(*N* = 210)	(*N* = 203)	(*N* = 209)
6	0.000	0.000	0.000
7	4.286	0.246	0.239
8	8.571	0.493	0.000
9	3.333	1.970	0.718
10	27.143	25.369	25.359
10.3	0.000	0.246	0.000
11	20.476	30.049	26.555
12	30.000	32.512	39.234
13	5.476	7.143	6.459
14	0.714	1.478	0.957
15	0.000	0.493	0.478
TPOX	(*N* = 209)	(*N* = 203)	(*N* = 209)
6	8.612	0.000	0.478
7	2.153	0.246	0.478
8	36.842	54.433	55.502
9	18.182	12.315	3.349
10	9.330	3.695	3.349
11	22.488	25.369	27.273
12	2.392	3.941	9.330
13	0.000	0.000	0.239
TH01	(*N* = 210)	(*N* = 203)	(*N* = 209)

Table 25.1 (Continued) Allelic Frequencies of 13 CODIS STR Loci

Allele	Allelic Frequency (%)		
	African American	Caucasian	Hispanic
5	0.000	0.000	0.239
6	10.952	22.660	23.206
7	44.048	17.241	33.732
8	18.571	12.562	8.134
8.3	0.000	0.246	0.000
9	14.524	16.502	10.287
9.3	10.476	30.542	24.163
10	1.429	0.246	0.239
D16S539	($N = 209$)	($N = 202$)	($N = 208$)
8	3.589	1.980	1.683
9	19.856	10.396	7.933
10	11.005	6.683	17.308
11	29.426	27.228	31.490
12	18.660	33.911	28.606
13	16.507	16.337	10.337
14	0.957	3.218	2.404
15	0.000	0.248	0.240

Source: Budowle, B., et al., *J Forensic Sci*, 44, 1277–1286, 1999. With permission.

25.1.2.6 Probability of Match

The discriminating power of genetic loci used above can be measured by *population match probability* (P_m). P_m is defined as the probability of having a matching genotype between two randomly chosen individuals. The lower the P_m, the less likely a match between two randomly chosen individuals will occur. This is calculated as follows:

$$P_m = \sum_i \left(p^2\right)^2 + \sum_j \left(2pq\right)^2 \tag{25.4}$$

where:

p and q = the frequencies of two different alleles

P_m can also be used to compare the discriminating powers of different loci

Tables 25.2 through 25.4 show P_m values of loci commonly used for forensic applications, including SNP, VNTR, and STR.

Table 25.2 Heterozygosity and P_m Values of Six SNP Loci

Locus	Allele	Heterozygosity	P_m
DQA1	7	0.828	0.053
LDLR	2	0.493	0.379
GYPA	2	0.498	0.376
HBGG	3	0.508	0.360
D7S8	2	0.476	0.388
GC	3	0.592	0.235
Average		0.566	
Product			2.5×10^{-4} (1 in 4000)

Source: Office of Justice Programs, National Institute of Justice, US Department of Justice, *The Future of Forensic DNA Testing: Predictions of the Research and Development Working Group*, 2000.

Table 25.3 Heterozygosity and P_m Values of Six VNTR Loci

Locus	Bins	Heterozygosity	P_m
D1S7	28	0.945	0.0058
D2S44	26	0.926	0.0103
D4S139	19	0.899	0.0184
D10S28	24	0.943	0.0063
D14S13	30	0.899	0.0172
D17S79	19	0.799	0.0700
Average		0.902	
Product			8.26×10^{-12} (1 in 1.2×10^{11})

Source: Office of Justice Programs, National Institute of Justice, US Department of Justice, *The Future of Forensic DNA Testing: Predictions of the Research and Development Working Group,* 2000.

25.2 Statistical Analysis of DNA Profiling Results

It is desirable to evaluate the strength of DNA profiling results, particularly if two DNA profiles match. A DNA profile from crime scene evidence and a profile from a suspect may be the same for two reasons: (1) the crime scene sample may have come from the suspect or (2) the suspect happens to have the same profile as the individual who left the evidence found at the crime scene. The significance of a match between DNA profiles can be evaluated by using statistical calculations that determine the rarity of a specific DNA profile in a relevant population. The statistical evaluation of the significance can be included in a case report

Table 25.4 Heterozygosity and P_m Values for CODIS Loci

Locus	Allele	Caucasian American		African American	
		Heterozygosity	P_m	Heterozygosity	P_m
CSF1PO	11	0.734	0.112	0.781	0.081
TPOX	7	0.621	0.195	0.763	0.090
TH01	7	0.783	0.081	0.727	0.109
VWA	10	0.811	0.062	0.809	0.063
D16S539	8	0.767	0.089	0.798	0.070
D7S820	11	0.806	0.065	0.782	0.080
D13S317	8	0.771	0.085	0.688	0.136
D5S818	10	0.682	0.158	0.739	0.112
FGA	19	0.860	0.036	0.863	0.033
D3S1358	10	0.795	0.075	0.763	0.094
D8S1179	10	0.780	0.067	0.778	0.082
D18S51	15	0.876	0.028	0.873	0.029
D2S11	20	0.853	0.039	0.861	0.034
Average		0.7812		0.7866	
Product			1.738×10^{-15} (1 in 5.753×10^{14})		1.092×10^{-15} (1 in 9.161×10^{14})

Source: Office of Justice Programs, National Institute of Justice, US Department of Justice, *The Future of Forensic DNA Testing: Predictions of the Research and Development Working Group*, 2000.

(Figure 25.2). Guidelines for DNA profile interpretation such as those issued by the National Research Council, the DNA Advisory Board, and the European DNA Profiling Group can be consulted.

25.2.1 Genotypes

The approaches to performing statistical analysis are (1) calculation of profile probability and (2) use of the likelihood ratio method. Although profile probability is the most commonly used method because of its simplicity, both approaches lead to the same conclusion.

25.2.1.1 Profile Probability

Profile probability can be calculated based on the following steps:

1. The locus genotype frequency can be calculated as follows; p and q are the allelic frequencies observed in the database for a given allele:

   Locus genotype frequency for homozygotes:

$$P_i = p^2 \tag{25.5}$$

Locus genotype frequency for heterozygotes:

$$P_j = 2pq \tag{25.6}$$

2. Profile probability can then be calculated based on the product rule by multiplying all the locus genotype frequencies calculated as above.

The lower the profile probability is, the less likely that an individual chosen at random will have a coincident match with the DNA profile of the evidence sample. Table 25.5 shows calculations of profile probability from a DNA profile.

25.2.1.1.1 Structured Populations

The above calculation of profile probability is based on the assumption that a randomly selected individual is unrelated to a perpetrator. However, it is likely that the individual and the perpetrator are from the same subpopulation (groups within a population) and are thus not completely independent. Mating is more likely to occur within subpopulations than between subpopulations. As a result, the proportion of homozygotes increases and the proportion of heterozygotes decreases in a subpopulation because individuals in a subpopulation appear to be related.



DEPARTMENT OF FORENSIC BIOLOGY

LABORATORY REPORT

LAB NO: IQAS 2003, Lab # 259

SUSPECTS: Suspect 1, 2032
Suspect 2, 2033
Suspect 3, 2034

SUMMARY OF RESULTS:

Semen* was found on the crime scene sample 2031b, based on the presence of P30 antigen and sperm.

PCR DNA typing was done on crime scene sample 2031b. Results indicate the semen could have come from the suspect 1. This combination of DNA alleles would be expected to be found in approximately:

1 in greater than 1 trillion Blacks**
1 in greater than 1 trillion Caucasians
1 in greater than 1 trillion Hispanics
1 in greater than 1 trillion Asians

The DNA from crime scene sample 2031b could not have come from suspect 2 or suspect 3.

Amylase, a component of saliva, was not found on crime scene sample 2031b.

No semen was found on the control sample 2035.

Crime scene sample 2031a was not analyzed.

The DNA results in this case do not match any previous PCR (STR) DNA cases to date.

*Semen has two components: the seminal plasma (which contains the P30 antigen) and spermatozoa. Semen can be identified by detecting either P30 antigen and/or sperm.

** OCME STR database, National Research Council (1996) The Evaluation of Forensic DNA Evidence, Natl. Acad. Press, Washington DC.

Figure 25.2 An example of a laboratory report. (© Richard C. Li.)

Table 25.5 Calculation of Profile Probability of STR Profile with 13 CODIS Loci

Locus	Profile	Allelic Frequency[a]	Formula	Locus Genotype Frequency
CSF1PO	10	0.25369	$2pq$	0.165
	12	0.32512		
D3S1358	14	0.14039	$2pq$	0.0691
	15	0.24631		
D5S818	11	0.41026	p^2	0.168
	11	0.41026		
D7S820	10	0.29064	$2pq$	0.117
	11	0.20197		
D8S1179	13	0.33929	p^2	0.115
	13	0.33929		
D13S317	11	0.31888	p^2	0.102
	11	0.31888		
D16S539	11	0.27228	$2pq$	0.185
	12	0.33911		
D18S51	15	0.12755	$2pq$	0.00911
	19	0.035710		
D21S11	30	0.23214	p^2	0.0539
	30	0.23214		
FGA	23	0.15816	$2pq$	0.0436
	24	0.13776		
TH01	8	0.12562	$2pq$	0.0767
	9.3	0.30542		
TPOX	8	0.54433	p^2	0.296
	8	0.54433		
VWA	17	0.26276	$2pq$	0.117
	18	0.22194		
				Profile probability $= 2.76 \times 10^{-14}$

[a] See Table 25.1.

The effect of population structure should be considered and an appropriate correction should be made to estimate profile probabilities. The correction can be made by using the factor θ. Thus, the locus genotype frequency can be calculated as follows:

Locus genotype frequency for homozygotes:

$$P_i = \frac{\left[2\theta + (1-\theta)p\right]\left[3\theta + (1-\theta)p\right]}{(1+\theta)(1+2\theta)} \tag{25.7}$$

Locus genotype frequency for heterozygotes:

$$P_j = \frac{2\left[\theta + (1-\theta)p\right]\left[\theta + (1-\theta)q\right]}{(1+\theta)(1+2\theta)} \tag{25.8}$$

The θ value is 0.01 for the majority US population and 0.03 for the Native American population. Table 25.6 shows the calculation of profile probability with subpopulation correction using $\theta = 0.01$. The profile probability is approximately three times higher than the value without the correction (Table 25.5). Additional corrections can be calculated for relatives, mixed stains, or database searches using formulas provided by the National Research Council's guidelines.

25.2.1.2 Likelihood Ratio

The *likelihood ratio* (LR) method is an alternative for evaluating the strength of a match. The method allows the calculation of the probability of the DNA profile under two hypothesis:

Hypothesis 1 (H_1) —The evidence and suspect profiles originated from the same source.

Hypothesis 2 (H_2) —The evidence and suspect profiles did not originate from the same source (i.e., the suspect happens to have the same profile as that of the individual who left the evidence).

The LR is the probability of hypothesis H_1 divided by the probability of hypothesis H_2. Where Pr_1 is the probability under hypothesis H_1, and Pr_2 is the probability under hypothesis H_2, this can be expressed as:

$$\text{LR} = \frac{\text{Pr}_1}{\text{Pr}_2} \tag{25.9}$$

The greater the numerator (Pr_1), the greater the likelihood ratio becomes. The result favors hypothesis H_1 (the evidence and suspect profile originated from the same source). Pr_1 is equal to 1 (100%) when a match occurs, and Pr_2 is equal to the profile probability. A LR of 1000 indicates that the evidence is 1000 times as probable if the evidence and suspect profiles originated from the same source.

25.2.2 Haplotypes

The term *haplotype* was first used to describe very closely linked polymorphic loci. During meiosis, alleles at neighboring loci cosegregate (both alleles segregate as a single allele) because of the close linkage of loci. The term also applies to genetic regions within which recombination events are very rare, that is, within mitochondrial and Y-chromosomal DNA. The entire mitochondrial DNA (mtDNA) sequence can be considered to be a single locus or haplotype because of the absence of recombination. Likewise, Y chromosome loci can also be considered haplotypes.

Where recombination is very rare, certain allelic combinations occur in populations much more frequently than would be expected. This phenomenon is called *linkage disequilibrium*. As a result, the HW principle cannot be applied. The two methods for evaluating the strength of

Table 25.6 Calculation of Profile Probability of STR with 13 CODIS Loci and Correction Factor ($\theta = 0.01$)

Locus	Profile	Allelic Frequency[a]	Formula	Locus Genotype Frequency
CSF1PO	10	0.25369	$\frac{2[\theta+(1-\theta)p][\theta+(1-\theta)q]}{(1+\theta)(1+2\theta)}$	0.168
	12	0.32512		
D3S1358	14	0.14039	$\frac{2[\theta+(1-\theta)p][\theta+(1-\theta)q]}{(1+\theta)(1+2\theta)}$	0.0734
	15	0.24631		
D5S818	11	0.41026	$\frac{[2\theta+(1-\theta)p][3\theta+(1-\theta)p]}{(1+\theta)(1+2\theta)}$	0.180
	11	0.41026		
D7S820	10	0.29064	$\frac{2[\theta+(1-\theta)p][\theta+(1-\theta)q]}{(1+\theta)(1+2\theta)}$	0.121
	11	0.20197		
D8S1179	13	0.33929	$\frac{[2\theta+(1-\theta)p][3\theta+(1-\theta)p]}{(1+\theta)(1+2\theta)}$	0.126
	13	0.33929		
D13S317	11	0.31888	$\frac{[2\theta+(1-\theta)p][3\theta+(1-\theta)p]}{(1+\theta)(1+2\theta)}$	0.113
	11	0.31888		
D16S539	11	0.27228	$\frac{2[\theta+(1-\theta)p][\theta+(1-\theta)q]}{(1+\theta)(1+2\theta)}$	0.187
	12	0.33911		
D18S51	15	0.12755	$\frac{2[\theta+(1-\theta)p][\theta+(1-\theta)q]}{(1+\theta)(1+2\theta)}$	0.012
	19	0.03571		
D21S11	30	0.23214	$\frac{[2\theta+(1-\theta)p][3\theta+(1-\theta)p]}{(1+\theta)(1+2\theta)}$	0.0630
	30	0.23214		
FGA	23	0.15816	$\frac{2[\theta+(1-\theta)p][\theta+(1-\theta)q]}{(1+\theta)(1+2\theta)}$	0.0473
	24	0.13776		
THO1	8	0.12562	$\frac{2[\theta+(1-\theta)p][\theta+(1-\theta)q]}{(1+\theta)(1+2\theta)}$	0.0815
	9.3	0.30542		
TPOX	8	0.54433	$\frac{[2\theta+(1-\theta)p][3\theta+(1-\theta)p]}{(1+\theta)(1+2\theta)}$	0.309
	8	0.54433		
VWA	17	0.26276	$\frac{2[\theta+(1-\theta)p][\theta+(1-\theta)q]}{(1+\theta)(1+2\theta)}$	0.120
	18	0.22194		
				Profile probability $= 7.8 \times 10^{-14}$

[a] See Table 23.1.

a match between haplotypes are (1) mitotype frequency and (2) likelihood ratios. The current most common approach for interpreting mtDNA profiles is mitotype frequency carried out with the gene counting method, that is, the calculation of the number of occurrences of a particular sequence or haplotype. The interpretation of Y chromosome profiles is similar to the interpretation of mtDNA profiles. The estimation of the frequency of a mitotype can be calculated as shown below.

25.2.2.1 Mitotypes Observed in Database

If a mitotype is observed at least once in a database, Equation 25.10 can be used. P_{mt} is the mitotype frequency, x is the number of observations of the haplotype, and n is the size of the database (the number of mitotype entries):

$$P_{\text{mt}} = \frac{x+2}{n+2} \tag{25.10}$$

Any sampling error may be addressed by a confidence interval:

$$P_{\text{mt}} \pm 1.96\sqrt{\frac{P_{\text{mt}}\left(1-P_{\text{mt}}\right)}{n}} \tag{25.11}$$

In this case, P_{mt} is the mitotype frequency, and n is the size of the database. The conservative upper bound of the frequency is usually quoted.

25.2.2.2 Mitotype Not Observed in Database

If a mitotype has not been observed in a database, Equation 25.12 can be used to calculate the mitotype frequency; α is 0.05 for a 95% confidence interval and n is the size of the database.

$$P_{\text{mt}} = 1 - \alpha^{1/n} \tag{25.12}$$

Bibliography

Aitken, C.G.G., *Statistics and the Evaluation of Evidence for Forensic Scientists*, p. 260, 1995. New York: Wiley.

Aktulga, H.M., et al., Identifying statistical dependence in genomic sequences via mutual information estimates. *EURASIP J Bioinform Syst Biol*, 2007, **2007**(1): 14741.

Allen, R.W., et al., Considerations for the interpretation of STR results in cases of questioned half-sibship. *Transfusion*, 2007, **47**(3): 515–519.

Amorim, A., A cautionary note on the evaluation of genetic evidence from uniparentally transmitted markers. *Forensic Sci Int Genet*, 2008, **2**(4): 376–378.

Andersen, M.M., P.S. Eriksen, and N. Morling, The discrete Laplace exponential family and estimation of Y-STR haplotype frequencies. *J Theor Biol*, 2013, **329**: 39–51.

Andersen, M.M., et al., Estimating trace-suspect match probabilities for singleton Y-STR haplotypes using coalescent theory. *Forensic Sci Int Genet*, 2013, **7**(2): 264–271.

Balding, D.J., The prosecutor's fallacy and DNA evidence. *Crim Law Rev*, 1994, 711–721.

Balding, D.J., When can a DNA profile be regarded as unique? *Sci Justice*, 1999, **39**(4): 257–260.

Balding, D.J. and P. Donnelly, Inferring identify from DNA profile evidence. *Proc Natl Acad Sci U S A*, 1995, **92**(25): 11741–11745.

Balding, D.J. and P. Donnelly, Evaluating DNA profile evidence when the suspect is identified through a database search. *J Forensic Sci*, 1996, **41**(4): 603–607.

Balding, D.J. and R.A. Nichols, DNA profile match probability calculation: How to allow for population stratification, relatedness, database selection and single bands. *Forensic Sci Int*, 1994, **64**(2–3): 125–140.

Beecham, G.W. and B.S. Weir, Confidence interval of the likelihood ratio associated with mixed stain DNA evidence. *J Forensic Sci*, 2011, **56**(Suppl 1): S166–S171.

Behar, D.M., et al., A "Copernican" reassessment of the human mitochondrial DNA tree from its root. *Am J Hum Genet*, 2012, **90**(4): 675–684.

Bodner, M., et al., Inspecting close maternal relatedness: Towards better mtDNA population samples in forensic databases. *Forensic Sci Int Genet*, 2011, **5**(2): 138–141.

Botstein, D., et al., Construction of a genetic linkage map in man using restriction fragment length polymorphisms. *Am J Hum Genet*, 1980, **32**(3): 314–331.

Brenner, C.H., Difficulties in the estimation of ethnic affiliation. *Am J Hum Genet*, 1998, **62**(6): 1558–1560; author reply 1560–1561.

Brenner, C.H., Fundamental problem of forensic mathematics—The evidential value of a rare haplotype. *Forensic Sci Int Genet*, 2010, **4**(5): 281–291.

Bright, J.A., J.M. Curran, and J.S. Buckleton, Relatedness calculations for linked loci incorporating subpopulation effects. *Forensic Sci Int Genet*, 2013, **7**(3): 380–383.

Buckleton, J., C. Triggs, and S. Walsh, *Forensic DNA Evidence Interpretation*, p. 534, 2005. New York: CRC Press.

Buckleton, J.S., M. Krawczak, and B.S. Weir, The interpretation of lineage markers in forensic DNA testing. *Forensic Sci Int Genet*, 2011, **5**(2): 78–83.

Buckleton, J.S., S. Walsh, and S.A. Harbison, The fallacy of independence testing and the use of the product rule. *Sci Justice*, 2001, **41**(2): 81–84.

Budowle, B., The effects of inbreeding on DNA profile frequency estimates using PCR-based loci. *Genetica*, 1995, **96**(1–2): 21–25.

Budowle, B. and T.R. Moretti, Genotype profiles for six population groups at the 13 CODIS short tandem repeat core loci and other PCR based loci. *Forensic Sci Commun*, 1999, **1**(2). Retrieved from http://www.fbi.gov/about-us/lab/forensic-science-communications/fsc/july1999/index.htm/budowle.htm.

Budowle, B., F.S. Baechtel, and R. Chakraborty, Partial matches in heterogeneous offender databases do not call into question the validity of random match probability calculations. *Int J Legal Med*, 2009, **123**(1): 59–63.

Budowle, B., et al., Population data on the thirteen CODIS core short tandem repeat loci in African Americans, U.S. Caucasians, Hispanics, Bahamians, Jamaicans, and Trinidadians. *J Forensic Sci*, 1999, **44**(6): 1277–1286.

Budowle, B., et al., Validation and population studies of the loci LDLR, GYPA, HBGG, D7S8, and Gc (PM loci), and HLA-DQ alpha using a multiplex amplification and typing procedure. *J Forensic Sci*, 1995, **40**(1): 45–54.

Budowle, B., et al., Source attribution of a forensic DNA profile. *Forensic Sci Commun*, 2000, **2**(3). Retrieved from http://www.fbi.gov/about-us/lab/forensic-science-communications/fsc/july2000/index.htm/source.htm.

Budowle, B., et al., CODIS STR loci data from 41 sample populations. *J Forensic Sci*, 2001, **46**(3): 453–489.

Budowle, B., et al., Use of prior odds for missing persons identifications. *Investig Genet*, 2011, **2**(1): 15.

Butler, J.M., et al., Allele frequencies for 15 autosomal STR loci on U.S. Caucasian, African American, and Hispanic populations. *J Forensic Sci*, 2003, **48**(4): 908–911.

Carracedo, A., et al., New guidelines for the publication of genetic population data. *Forensic Sci Int Genet*, 2013, **7**(2): 217–220.

Chakraborty, R., Detection of nonrandom association of alleles from the distribution of the number of heterozygous loci in a sample. *Genetics*, 1984, **108**(3): 719–731.

Chakraborty, R., Sample size requirements for addressing the population genetic issues of forensic use of DNA typing. *Hum Biol*, 1992, **64**(2): 141–159.

Chakraborty, R. and D.N. Stivers, Paternity exclusion by DNA markers: Effects of paternal mutations. *J Forensic Sci*, 1996, **41**(4): 671–677.

Chakraborty, R., et al., The utility of short tandem repeat loci beyond human identification: Implications for development of new DNA typing systems. *Electrophoresis*, 1999, **20**(8): 1682–1696.

Clayton, D., On inferring presence of an individual in a mixture: A Bayesian approach. *Biostatistics*, 2010, **11**(4): 661–673.

Cockerton, S., K. McManus, and J. Buckleton, Interpreting lineage markers in view of subpopulation effects. *Forensic Sci Int Genet*, 2012, **6**(3): 393–397.

Collins, A. and N.E. Morton, Likelihood ratios for DNA identification. *Proc Natl Acad Sci U S A*, 1994, **91**(13): 5.

Condel, K. and M. Al Salih, A simple method for establishing concordance between short-tandem-repeat allele frequency databases. *Transfusion*, 2011, **51**(5): 986–992.

Crow, J.F., Hardy, Weinberg and language impediments. *Genetics*, 1999, **152**(3): 821–825.

Curran, J.M. and J. Buckleton, The appropriate use of subpopulation corrections for differences in endogamous communities. *Forensic Sci Int*, 2007, **168**(2–3): 106–111.

Curran, J.M. and J. Buckleton, Inclusion probabilities and dropout. *J Forensic Sci*, 2010, **55**(5): 1171–1173.

Curran, J.M. and J.S. Buckleton, An investigation into the performance of methods for adjusting for sampling uncertainty in DNA likelihood ratio calculations. *Forensic Sci Int Genet*, 2011, **5**(5): 512–516.

Curran, J.M., S.J. Walsh, and J. Buckleton, Empirical testing of estimated DNA frequencies. *Forensic Sci Int Genet*, 2007, **1**(3–4): 267–272.

Curran, J.M., et al., Interpreting DNA mixtures in structured populations. *J Forensic Sci*, 1999, **44**(5): 987–995.

Edwards, A., et al., Genetic variation at five trimeric and tetrameric tandem repeat loci in four human population groups. *Genomics*, 1992, **12**(2): 241–253.

Egeland, T. and A. Salas, Estimating haplotype frequency and coverage of databases. *PLoS One*, 2008, **3**(12): e3988.

Egeland, T. and A. Salas, A statistical framework for the interpretation of mtDNA mixtures: Forensic and medical applications. *PLoS One*, 2011, **6**(10): e26723.

Egeland, T. and N. Sheehan, On identification problems requiring linked autosomal markers. *Forensic Sci Int Genet*, 2008, **2**(3): 219–225.

Evett, I. and B. Weir, *Interpreting DNA Evidence: Statistical Genetics for Forensic Scientists*, p. 278, 1992. Sunderland, MA: Sinauer Associates.

Evett, I.W. and P. Gill, A discussion of the robustness of methods for assessing the evidential value of DNA single locus profiles in crime investigations. *Electrophoresis*, 1991, **12**(2–3): 226–230.

Evett, I.W., R. Pinchin, and C. Buffery, An investigation of the feasibility of inferring ethnic origin from DNA profiles. *J Forensic Sci Soc*, 1992, **32**(4): 301–306.

Fisher, R.A., Standard calculations for evaluating a blood-group system. *Heredity*, 1951, **5**(1): 95–102.

Foreman, L.A., A.F.M. Smith, and I. Evett, Bayesian validation of a quaduplex STR profiling system for identification purposes. *J Forensic Sci*, 1999, **44**: 378–486.

Foreman, L.A. and I.W. Evett, Statistical analyses to support forensic interpretation for a new ten-locus STR profiling system. *Int J Legal Med*, 2001, **114**(3): 147–155.

Foreman, L.A., et al., Interpreting DNA evidence: A review. *Int Stat Rev*, 2003, **71**(3): 13.

Gaensslen, R.E., Journal policy on the publication of DNA population genetic data. *J Forensic Sci*, 1999, **44**(4): 4.

Ge, J. and B. Budowle, Kinship index variations among populations and thresholds for familial searching. *PLoS One*, 2012, **7**(5): e37474.

Ge, J., B. Budowle, and R. Chakraborty, Interpreting Y chromosome STR haplotype mixture. *Leg Med*, 2010, **12**(3): 137–143.

Ge, J., et al., Haplotype block: A new type of forensic DNA markers. *Int J Legal Med*, 2010, **124**(5): 353–361.

Ge, J., et al., Pedigree likelihood ratio for lineage markers. *Int J Legal Med*, 2011, **125**(4): 519–525.

Gill, P. and H. Haned, A new methodological framework to interpret complex DNA profiles using likelihood ratios. *Forensic Sci Int Genet*, 2013, **7**(2): 251–263.

Gill, P., et al., A comparison of adjustment methods to test the robustness of an STR DNA database comprised of 24 European populations. *Forensic Sci Int*, 2003, **131**(2–3): 184–196.

Gjertson, D.W., et al., ISFG: Recommendations on biostatistics in paternity testing. *Forensic Sci Int Genet*, 2007, **1**(3–4): 223–231.

Guo, S.W. and E.A. Thompson, Performing the exact test of Hardy–Weinberg proportion for multiple alleles. *Biometrics*, 1992, **48**(2): 361–372.

Haned, H., Forensim: An open-source initiative for the evaluation of statistical methods in forensic genetics. *Forensic Sci Int Genet*, 2011, **5**(4): 265–268.

Hardy, G.H., Mendelian proportions in a mixed population. *Science*, 1908, **17**: 49–50.

Hartman, D., et al., Examples of kinship analysis where Profiler Plus was not discriminatory enough for the identification of victims using DNA identification. *Forensic Sci Int*, 2011, **205**(1–3): 64–68.

Henderson, J.P., The use of DNA statistics in criminal trials. *Forensic Sci Int*, 2002, **128**(3): 183–186.

Hill, C.R., et al., Concordance and population studies along with stutter and peak height ratio analysis for the PowerPlex ESX 17 and ESI 17 Systems. *Forensic Sci Int Genet*, 2011, **5**(4): 269–275.

Holt, C.L., et al., Practical applications of genotypic surveys for forensic STR testing. *Forensic Sci Int*, 2000, **112**(2–3): 91–109.

Hong-Sheng, G., et al., HGD-Chn: The database of genome diversity and variation for Chinese populations. *Leg Med*, 2009, **11**(Suppl 1): S201–S202.

Hopwood, A.J., et al., Consideration of the probative value of single donor 15-plex STR profiles in UK populations and its presentation in UK courts. *Sci Justice*, 2012, **52**(3): 185–190.

Hosking, L., et al., Detection of genotyping errors by Hardy–Weinberg equilibrium testing. *Eur J Hum Genet*, 2004, **12**(5): 395–399.

Janica, J., et al., Database of genetic profiles at the Department of Forensic Medicine, Medical University of Bialystok. *Adv Med Sci*, 2008, **53**(1): 64–68.

Kling, D., T. Egeland, and A.O. Tillmar, FamLink—A user friendly software for linkage calculations in family genetics. *Forensic Sci Int Genet*, 2012, **6**(5): 616–620.

Lareu, M.V., et al., Analysis of a claimed distant relationship in a deficient pedigree using high density SNP data. *Forensic Sci Int Genet*, 2012, **6**(3): 350–353.

Lauc, G., et al., Empirical support for the reliability of DNA interpretation in Croatia. *Forensic Sci Int Genet*, 2008, **3**(1): 50–53.

Lee, J.C., et al., A novel strategy for sibship determination in trio sibling model. *Croat Med J*, 2012, **53**(4): 336–342.

Li, L., et al., Maternity exclusion with a very high autosomal STRs kinship index. *Int J Legal Med*, 2012, **126**(4): 645–648.

Lincoln, P. and A. Carracedo, Publication of population data of human polymorphisms. *Forensic Sci Int*, 2000, **110**(1): 3–5.

Lins, A.M., et al., Development and population study of an eight-locus short tandem repeat (STR) multiplex system. *J Forensic Sci*, 1998, **43**(6): 1168–1180.

Matsumura, S., et al., Kinship analysis using DNA typing from five skeletal remains with an unusual post-mortem course. *Med Sci Law*, 2011, **51**(4): 240–243.

Montinaro, F., et al., Using forensic microsatellites to decipher the genetic structure of linguistic and geographic isolates: A survey in the eastern Italian Alps. *Forensic Sci Int Genet*, 2012, **6**(6): 827–833.

Morton, N.E., Genetic structure of forensic populations. *Proc Natl Acad Sci U S A*, 1992, **89**(7): 2556–2560.

Mueller, L.D., Can simple population genetic models reconcile partial match frequencies observed in large forensic databases? *J Genet*, 2008, **87**(2): 101–108.

Nei, M., Estimation of average heterozygosity and genetic distance from a small number of individuals. *Genetics*, 1978, **89**(3): 583–590.

Noris, G., et al., Mexican mestizo population sub-structure: Effects on genetic and forensic statistical parameters. *Mol Biol Rep*, 2012, **39**(12): 10139–10156.

Nothnagel, M., J. Schmidtke, and M. Krawczak, Potentials and limits of pairwise kinship analysis using autosomal short tandem repeat loci. *Int J Legal Med*, 2010, **124**(3): 205–215.

NRC (National Research Council), *The Evaluation of Forensic DNA Evidence*, 1996. Washington, DC: National Research Council Committee, National Academies Press.

Nunez, C., et al., Reconstructing the population history of Nicaragua by means of mtDNA, Y-chromosome STRs, and autosomal STR markers. *Am J Phys Anthropol*, 2010, **143**(4): 591–600.

O'Connor, K.L. and A.O. Tillmar, Effect of linkage between vWA and D12S391 in kinship analysis. *Forensic Sci Int Genet*, 2012, **6**(6): 840–844.

O'Connor, K.L., et al., Linkage disequilibrium analysis of D12S391 and vWA in U.S. population and paternity samples. *Forensic Sci Int Genet*, 2011, **5**(5): 538–540.

Office of Justice Programs, National Institute of Justice, US Department of Justice, *The Future of Forensic DNA Testing: Predictions of the Research and Development Working Group,* 2000.

Palo, J.U., et al., Genetic markers and population history: Finland revisited. *Eur J Hum Genet*, 2009, **17**(10): 1336–1346.

Parson, W. and H.J. Bandelt, Extended guidelines for mtDNA typing of population data in forensic science. *Forensic Sci Int Genet*, 2007, **1**(1): 13–19.

Parson, W. and L. Roewer, Publication of population data of linearly inherited DNA markers in the *International Journal of Legal Medicine*. *Int J Legal Med*, 2010, **124**(5): 505–509.

Pereira, L., et al., PopAffiliator: Online calculator for individual affiliation to a major population group based on 17 autosomal short tandem repeat genotype profile. *Int J Legal Med*, 2011, **125**(5): 629–636.

Pereira, R., et al., Straightforward inference of ancestry and admixture proportions through ancestry-informative insertion deletion multiplexing. *PLoS One*, 2012, **7**(1): e29684.

Phillips, C., et al., D9S1120, a simple STR with a common Native American-specific allele: Forensic optimization, locus characterization and allele frequency studies. *Forensic Sci Int Genet*, 2008, **3**(1): 7–13.

Phillips, C., et al., The recombination landscape around forensic STRs: Accurate measurement of genetic distances between syntenic STR pairs using HapMap high density SNP data. *Forensic Sci Int Genet*, 2012, **6**(3): 354–365.

Prieto, L., et al., The GHEP-EMPOP collaboration on mtDNA population data—A new resource for forensic casework. *Forensic Sci Int Genet*, 2011, **5**(2): 146–151.

Pu, C.E. and A. Linacre, Increasing the confidence in half-sibship determination based upon 15 STR loci. *J Forensic Leg Med*, 2008, **15**(6): 373–377.

Pu, C.E. and A. Linacre, Systematic evaluation of sensitivity and specificity of sibship determination by using 15 STR loci. *J Forensic Leg Med*, 2008, **15**(5): 329–334.

Puch-Solis, R., S. Pope, and I. Evett, Calculating likelihood ratios for a mixed DNA profile when a contribution from a genetic relative of a suspect is proposed. *Sci Justice*, 2010, **50**(4): 205–209.

Rajeevan, H., et al., Introducing the forensic research/reference on genetics knowledge base, FROG-kb. *Investig Genet*, 2012, **3**(1): 18.

Ravid-Amir, O. and S. Rosset, Maximum likelihood estimation of locus-specific mutation rates in Y-chromosome short tandem repeats. *Bioinformatics*, 2010, **26**(18): i440–i445.

Raymond, M. and F. Rousset, Population genetics software for exact tests and ecumenicism. *J Hered*, 1995, **86**: 12.

Robertson, B. and G.A. Vigneaux, Expert evidence: Law, practice, and probability. *Oxford J Legal Stud*, 1992, **12**(1): 392–403.

Rodig, H., et al., Evaluation of haplotype discrimination capacity of 35 Y-chromosomal short tandem repeat loci. *Forensic Sci Int*, 2008, **174**(2–3): 182–188.

Roeder, K., DNA fingerprinting: A review of the controversy. *Stat Sci*, 1994, **9**(2): 222–278.

Rowold, D.J. and R.J. Herrera, On human STR sub-population structure. *Forensic Sci Int*, 2005, **151**(1): 59–69.

Royall, R., *Statistical Evidence: A Likelihood Paradigm*, 1997. New York: Chapman & Hall.

Sanchez, J.J., et al., Forensic typing of autosomal SNPs with a 29 SNP-multiplex—Results of a collaborative EDNAP exercise. *Forensic Sci Int Genet*, 2008, **2**(3): 176–183.

Sanchez-Diz, P., et al., Population and segregation data on 17 Y-STRs: Results of a GEP-ISFG collaborative study. *Int J Legal Med*, 2008, **122**(6): 529–533.

Santos, C., et al., Frequency and pattern of heteroplasmy in the control region of human mitochondrial DNA. *J Mol Evol*, 2008, **67**(2): 191–200.

Silva, N.M., et al., Human neutral genetic variation and forensic STR data. *PLoS One*, 2012, **7**(11): e49666.

Stockmarr, A., Likelihood ratios for evaluating DNA evidence when the suspect is found through a database search. *Biometrics*, 1999, **55**(3): 671–677.

Taroni, F., et al., Evaluation and presentation of forensic DNA evidence in European laboratories. *Sci Justice*, 2002, **42**(1): 21–28.

Taylor, C. and P. Colman, Forensics: Experts disagree on statistics from DNA trawls. *Nature*, 2010, **464**(7293): 1266–1267.

Thompson, W.C. and E.L. Schumann, Interpretation of statistical evidence in criminal trials: The prosecutor's fallacy and the defense attorney's fallacy. *Law Hum Behav*, 1987, **11**(3): 11.

Toscanini, U., et al., Evaluating methods to correct for population stratification when estimating paternity indexes. *PLoS One*, 2012, **7**(11): e49832.

Tvedebrink, T., et al., Estimating the probability of allelic drop-out of STR alleles in forensic genetics. *Forensic Sci Int Genet*, 2009, **3**(4): 222–226.

van Oven, M., et al., Unexpected island effects at an extreme: Reduced Y chromosome and mitochondrial DNA diversity in Nias. *Mol Biol Evol*, 2011, **28**(4): 1349–1361.

Walsh, S.J., et al., Evidence in support of self-declaration as a sampling method for the formation of subpopulation DNA databases. *J Forensic Sci*, 2003, **48**(5): 1091–1093.

Walsh, S.J., et al., Use of subpopulation data in Australian forensic DNA casework. *Forensic Sci Int Genet*, 2007, **1**(3–4): 238–246.

Weir, B.S. and W.G. Hill, Estimating F-statistics. *Annu Rev Genet*, 2002, **36**: 721–750.

Wenk, R.E., Detection of genotype recycling fraud in U.S. immigrants. *J Forensic Sci*, 2011, **56**(Suppl 1): S243–S246.

Willuweit, S., et al., Y-STR frequency surveying method: A critical reappraisal. *Forensic Sci Int Genet*, 2011, **5**(2): 84–90.

26

Quality Assurance and Quality Control

Quality assurance (*QA*) for forensic services requires certain processes to ensure that a service will meet laboratory requirements for the integrity of testing. A QA program must include components that address:

- Continuing education, training, and certification of personnel
- Specification and calibration of equipment and reagents
- Documentation and validation of analytic methods
- Use of appropriate standards and controls
- Sample handling procedures
- Proficiency testing
- Data interpretation and reporting
- Audits (internal and external) and laboratory accreditation
- Corrective actions to address deficiencies and assessments for laboratory competence

Over the years, many guidelines for quality assurance in forensic DNA laboratories have been established. These guidelines will be introduced in this chapter.

Quality control (*QC*) for forensic services refers to the operational procedures necessary to meet quality requirements. QC procedures may include maintenance of calibration records for equipment and instruments as well as the testing of chemical reagents and supplies used in analysis to ensure reliable results.

26.1 US Quality Standards

DNA profiling methods were first used in criminal investigations in the 1980s. By the early 1990s, emerging forensic DNA techniques had undergone detailed reviews by the *National Research Council* (*NRC*) of the National Academy of Sciences. In 1992, the first published NRC report included recommendations in the areas of (1) technical considerations, (2) statistical interpretation, (3) laboratory standards, (4) data banks and privacy, (5) legal considerations, and (6) societal and ethical issues related to forensic DNA testing. The NRC report attempted to explain the basic scientific principles of forensic DNA technology and made suggestions for applications and improvements. However, the report received negative criticism from both the forensic and the legal communities.

In 1996, a second NRC committee was formed "to update and clarify discussion of the principles of population genetics and statistics as they apply to DNA evidence." Its report stated:

> The central question that the report addresses is this: What information can a forensic scientist, population geneticist, or statistician provide to assist a judge or jury in drawing inferences from the finding of a match? To answer this question, the committee reviewed the scientific literature and the legal cases and commentaries on DNA profiling, and it investigated the criticisms that have been voiced about population data, statistics, and laboratory error. Much has been learned since the last report. The technology for DNA profiling as well as the methods for estimating frequencies and related statistics have progressed to the point where the reliability and validity of properly collected and analyzed DNA data should not be in doubt. The new recommendations presented here should pave the way to more effective use of DNA evidence. (*The Evaluation of Forensic DNA Evidence* also known as the NRC II report)

The NRC II report consisted of (1) an introduction describing the 1992 report, changes made subsequent to that report, and the validity and application of DNA typing techniques; (2) assurance of high standards of laboratory performance; (3) population genetics issues; (4) statistical issues; and (5) DNA evidence in the legal system.

In 1995, The *DNA Advisory Board* (*DAB*) was formed as a result of the DNA Identification Act (1994) passed by Congress. The DAB served from 1995 to 2000 to develop guidelines for quality assurance in forensic laboratories. During that time, the DAB provided two sets of guidelines: Quality Assurance Standards for Forensic DNA Testing Laboratories (1998) and Quality Assurance Standards for Convicted Offender DNA Databasing Laboratories (1999). These standards describe the requirements to ensure quality and integrity of the data as well as competency of laboratories.

These standards were built on the previous standards set by the *Scientific Working Group on DNA Analysis Methods* (*SWGDAM*). After the DAB's assignment ended in 2000, the SWGDAM became responsible for providing guidelines to the US forensic community. The SWGDAM was established in 1988 by the FBI Laboratory. It was initially called the Technical Working Group on DNA Analysis Methods; the name changed in 1998. The SWGDAM comprises forensic scientists from DNA laboratories in the United States and Canada. Its purpose is to facilitate forensic DNA community discussions regarding necessary laboratory methods and to share protocols for forensic DNA testing. The FBI sponsors and hosts its meetings and plays an important role in its activities.

The SWGDAM established and revised several guidelines including the Guidelines for a Quality Assurance Program for DNA Analysis, published in 1989, 1991, and 1995 (the validation section was revised in 2003); Quality Assurance Standards for Forensic DNA Testing Laboratories (2011); Quality Assurance Standards for DNA Databasing Laboratories (2011); Validation Guidelines for DNA Analysis Methods (2012); and SWGDAM Training Guidelines, published in 2001 and revised in 2013.

The SWGDAM also formed subcommittees to provide guidelines in more specific areas of forensic DNA testing, for example, SWGDAM's Interpretation Guidelines for Autosomal STR Typing by Forensic DNA Testing Laboratories (2010), Y-chromosome Short Tandem Repeat (Y-STR) Interpretation Guidelines (2009), and Interpretation Guidelines for Mitochondrial DNA Analysis by Forensic DNA Testing Laboratories (2013). The SWGDAM also organized a number of interlaboratory and validation studies for new techniques.

26.2 International Quality Standards

In the early stages of forensic DNA testing, the *International Society for Forensic Genetics* (*ISFG*) recognized the potential of DNA testing for criminal investigations and made a number of recommendations related to the forensic application of DNA polymorphisms.

The ISFG provided various recommendations for forensic DNA testing of STR, mtDNA, and Y chromosome markers for the international community. It formed a working group called the *European DNA Profiling Group* (*EDNAP*) in 1991. The EDNAP has investigated systems for DNA profiling, has organized a number of collaborative exercises for the evaluation of new methods, and has published reports of its studies.

The *European Network of Forensic Science Institutes* (*ENFSI*) formed its DNA working group about a decade ago to address issues of quality and standards for forensic DNA testing. The *Interpol European Working Party on DNA Profiling* (*IEWPDP*) also makes recommendations for applying DNA evidence to criminal investigations in Europe. Based on the EDNAP exercises and recommendations by the ENFSI and IEWPDP, the *European Standard Set* (*ESS*) for autosomal STR core loci was established. The Standardization of DNA Profiling Techniques in the European Union (STADNAP) group has been working on the selection of forensic DNA profiling systems, methods for use among European countries, and the maintenance of European population databases.

26.3 Laboratory Accreditation

Accreditation is the process used to assess the qualification of a laboratory to meet established standards. During an accreditation process, the services and performance of a laboratory are evaluated, particularly in the areas of management, operations, personnel, procedures, equipment, physical plants, security, and personnel safety procedures. The accreditation process generally involves several components such as self-evaluation, the preparation of supporting documents, on-site inspection and reports, and accreditation review reports.

Accreditation in the United States is offered by the *Laboratory Accreditation Board* of the *American Society of Crime Laboratory Directors* (*ASCLD/LAB*) for forensic laboratories performing casework. The *American Association of Blood Banks* (*AABB*) provides accreditation for laboratories performing DNA parentage testing according to the AABB's standards.

The accreditation of a forensic laboratory is granted for 5 years. To remain in compliance, a laboratory must undergo audits to evaluate its operation according to established guidelines. The FBI has published the Quality Assurance Standards Audit for Forensic DNA Testing Laboratories (2011) and the Quality Assurance Standards Audit for DNA Databasing Laboratories (2011). The areas of operating protocols, instruments and equipment, and personnel training are evaluated based on guidelines. Problems identified during an audit must be documented and actions to resolve the problems must be addressed. Annual internal audits and external audits during alternate years are required under the guidelines.

26.4 Laboratory Validation

Validation is the process of confirming that a laboratory procedure is sufficiently robust, reliable, and reproducible. A robust method maintains successful performance and can cope with errors. A reliable method produces accurate results. A reproducible method achieves the same or very similar results each time a sample is tested.

Two types of laboratory validations, developmental and internal validations, are used for modifying methods for forensic DNA analysis. An *internal validation* is required when adopting a procedure for forensic applications. Based on the SWGDAM's Validation Guidelines for DNA Analysis Methods, the internal validation is "an accumulation of test data within the laboratory to demonstrate that established methods and procedures perform as expected in the laboratory." The *developmental validation* "is the acquisition of test data and determination of conditions and limitations of a new or novel DNA methodology for use on forensic, database, known or casework reference samples." For example, the characterization of a new genetic marker requires studies in the inheritance, the genomic location, the detection method, and the polymorphism of the genetic marker. However, developmental validation studies in the same subject but from fields other than forensic DNA analysis may be acceptable for forensic applications.

Additionally, the precision and the accuracy of the test are important criteria for developmental validation. Based on the SWGDAM, *precision* "characterizes the degree of mutual agreement among a series of individual measurements, values and/or results. Precision depends only on the distribution of random errors and does not relate to the true value or specified value." The measure of precision can be expressed as a standard deviation of test results. *Accuracy* is referred to as "the ability of a measuring instrument to give responses close to a true value," which can be assessed by a *performance check*, a quality assurance procedure monitoring the performance of instruments and equipment affecting the accuracy of forensic DNA testing.

26.5 Proficiency Testing

Proficiency testing is an important component of quality control and quality assurance. It evaluates a laboratory's performance of DNA analyses according to the laboratory's standard protocols. Proficiency testing also evaluates the quality of performance by individual analysts following laboratory protocols.

Proficiency tests of DNA analysts must be conducted every 6 months based on DNA Advisory Board Standards. The testing usually involves mock forensic case samples including questioned bodily fluid stains and reference samples. The test is assigned to an analyst for processing according to the laboratory procedures. A report must be prepared and is then reviewed. The proficiency test can be administered as either an open or a blind test. In the blind test, the analyst is not aware that he or she is being tested. Blind testing is considered a more effective means of evaluating performance.

The tests may be administered internally or by any of a number of external testing organizations. For example, Orchid Cellmark provides the *International Quality Assessment Scheme* (*IQAS*) DNA proficiency test, and the Collaborative Testing Services (CTS) Forensics Testing Program offers similar proficiency tests. These proficiency tests may include a selection of sample types (neat or mixture) for serological tests and/or DNA analysis (autosomal STR, Y-STR, and mitochondrial DNA). The College of American Pathologists (CAP) has a paternity testing proficiency program offering external proficiency tests. In Europe, the *German DNA Profiling Group* (*GEDNAP*) provides proficiency testing for participating European laboratories.

26.6 Certification

Certification is a voluntary process that recognizes the attainment of professional qualifications needed for practice in forensic services. Certification is not required, but is desired by some laboratories. In 2009, a report entitled Strengthening Forensic Science in the United States: A Path Forward was published by the Committee on Identifying the Needs of the Forensic Science Community at the National Academy of Sciences. The report recommends that certification should be mandatory for forensic science professionals, which includes written examinations, supervised practice, proficiency testing, and compliance to a code of ethics (Section 26.8). In the United States, the *American Board of Criminalistics* (*ABC*) offers three types of certification for forensic scientists. A diplomate must pass a general knowledge examination. ABC also requires a bachelor's degree in a natural science and 2 years of experience in a forensic laboratory. To obtain fellow status (higher than diplomate status), an applicant must have 2 years of experience in his or her specialty and must have met the diplomate requirements in addition to passing a written specialty examination and a proficiency test.

ABC has added a third certification that is completely separate from the other certification programs. The technical specialist certification for molecular biology was created to recognize the qualifications required for the analysis of biological materials through DNA profiling. An applicant must take a specialist examination containing questions from the general knowledge examination and a subset of questions from the forensic biology fellow examination. This certification also requires a bachelor's degree in a natural science and 2 years of experience along with successful completion of a proficiency examination within 12 months of taking the technical specialist certification examination.

26.7 Forensic DNA Analyst Qualifications

DAB's Quality Assurance Standards for Forensic DNA Testing Laboratories require that an examiner or analyst have "at a minimum a BA/BS degree or its equivalent degree in a biology, chemistry or forensic science-related area and must have successfully completed college course work (graduate or undergraduate level) covering the subject areas of biochemistry, genetics and molecular biology," as well as "course work and/or training in statistics and population genetics as it applies to forensic DNA analysis."

Additionally, SWGDAM Training Guidelines discuss the course work requirements in detail. At least nine cumulative semester hours are required for the course work covering the required subject areas. Particularly, the section in Fundamental Scientific Knowledge of the SWGDAM Training Guidelines defines required key elements to be covered in course work. The key elements also aid in evaluating the contents of the course work.

Biochemistry "refers to the nature of biologically important molecules in living systems, DNA replication and protein synthesis, and the quantitative and qualitative aspects of cellular metabolism," and may include but is not limited to:

- Structure and function of cellular components such as proteins, carbohydrates, lipids, nucleic acids, and other biomolecules
- Chemistry of enzyme-catalyzed reactions
- Metabolism
- DNA and RNA
- Protein synthesis
- Cell membrane transport
- Signal transduction

Genetics "refers to the study of inherited traits, genotype/phenotype relationships, and population/species differences in allele and genotype frequencies," and may include but is not limited to:

- Heredity
- Function of genes
- Gene expression
- Recombinant DNA
- Mitosis/meiosis

Molecular biology "covers theories, methods, and techniques used in the study and analysis of gene structure, organization, and function," and may include, but is not limited to:

- Interrelationship of DNA, RNA, and protein synthesis
- Central dogma

- Transcription, translation, replication
- Recombinant DNA techniques
- PCR
- Cloning

Course work that is similar in content and scope to those described above may be qualified as required course work. Compliance with the required course contents can be evaluated through transcripts, syllabi, and letters from the instructors.

DAB's Quality Assurance Standards for Forensic DNA Testing Laboratories also describes requirements for an analyst to meet prior to initiating independent casework analysis using DNA technology. First, an analyst must have at least 6 months of forensic DNA laboratory experience "including the successful analysis of a range of samples typically encountered in forensic casework." Second, an analyst must have "successfully completed a qualifying test before beginning independent casework responsibilities."

26.8 Code of Ethics of Forensic Scientists

Ethical codes for forensic scientists are used as guides for individuals making their decisions in distinguishing the difference between correctness and incorrectness. These codes are usually adopted by forensic organizations to regulate the profession. Failure to comply with a code of forensic practice can raise doubt in an individual's fitness for providing forensic services. Additionally, it may result in the expulsion of an individual from a forensic organization. A typical document of ethical codes for forensic scientists generally contains five sections: (1) ethics relating to the scientific method, (2) ethics relating to opinions and conclusions, (3) ethical aspects of court presentation, (4) ethics relating to the general practice of forensics, and (5) ethical responsibilities to the profession.

For the first section, the ethical application of scientific methods is discussed in detail. True scientific methods should be utilized to adequately analyse all the evidence. Such analyses should not be conducted by secret processes. Conclusions should be drawn from the analyses of evidence that appears representative, typical, or reliable.

Moreover, ethical standards relating to opinions and conclusions are very important to the forensic profession. Conclusions should always be drawn from the application of proven scientific methods. The purpose of experimental design and the interpretation of results is to reveal facts. During an analysis, experimental controls should always be utilized. If necessary, the results of analyses should be verified by repeating the analysis or using additional techniques. Explanations should be provided where inconclusive results are obtained. The opinion provided by a forensic scientist should be unbiased and should not be influenced by matters unrelated to the specific evidence in question. A forensic scientist should not choose the interpretation that is in favor of the side of his or her employer.

Pertaining to the courtroom, ethical standards relating to expert witness testimonies is a crucial component for a forensic scientist. An expert opinion is defined as a formal consideration of a subject within an individual's knowledge, skill, education, training, and experience. A forensic scientist should not extend an opinion beyond his or her competence. Appropriate terms should be used to represent the degrees of certainty of an expert opinion. A forensic scientist should not only present the evidence that supports the view of the side of his or her employer. When testifying as an expert witness, language that can be understood by lay jurors should be used to avoid misinterpretation.

Furthermore, in terms of the general practice of forensic science, a few things should be mentioned here. A forensic scientist in private practice should set a reasonable fee for the services provided, which should not be rendered on a contingency fee basis. When a different opinion is presented by another analyst in the reexamination of evidence, both analysts should resolve their contradiction before the trial. A forensic scientist may serve, in an advisory capacity, either the prosecutor or defense in the cross-examination of another expert.

Lastly, ethical responsibilities to the profession are an important component of ethical codes. Information regarding new developments or techniques of forensic analysis should be made available to other forensic scientists. Likewise, any information regarding methods in use that may appear unreliable should be brought to the attention of others. Individual forensic scientists should not seek publicity for the association of their name with specific cases, developments, publications, or organizations solely for the purpose of gaining personal prestige.

Bibliography

Andersen, J., et al., Report on the third EDNAP collaborative STR exercise. *Forensic Sci Int*, 1996, **78**(2): 83–93.

Balazic, J. and I. Zupanic, Quality control and quality assurance in DNA laboratories: Legal, civil and ethical aspects. *Forensic Sci Int*, 1999, **103**: S1–S5.

Bar, W., et al., DNA recommendations. Further report of the DNA commission of the ISFH regarding the use of short tandem repeat systems. International Society for Forensic Haemogenetics. *Int J Legal Med*, 1997, **110**(4): 175–176.

Buckleton, J., Validation issues around DNA typing of low level DNA. *Forensic Sci Int Genet*, 2009, **3**(4): 255–260.

Budowle, B., et al., A perspective on errors, bias, and interpretation in the forensic sciences and direction for continuing advancement. *J Forensic Sci*, 2009, **54**(4): 798–809.

Carracedo, A., et al., DNA commission of the International Society for Forensic Genetics: Guidelines for mitochondrial DNA typing. *Forensic Sci Int*, 2000, **110**(2): 79–85.

Carracedo, A., et al., Results of a collaborative study of the EDNAP group regarding the reproducibility and robustness of the Y-chromosome STRs DYS19, DYS389 I and II, DYS390 and DYS393 in a PCR pentaplex format. *Forensic Sci Int*, 2001, **119**(1): 28–41.

Cormier, K., L. Calandro, and D.J. Reeder, Evolution of the quality assurance documents for DNA laboratories. *Forensic Mag*, 2005, 2(1): 16–19.

Council, N.R., *NRC II: The Evaluation of Forensic DNA Evidence*, 1996. Washington, D.C.: National Academy Press.

Coyle, H.M., The importance of scientific evaluation of biological evidence—Data from eight years of case review. *Sci Justice*, 2012, **52**(4): 268–270.

DNA Advisory Board, Federal Bureau of Investigation, US Department of Justice, Quality assurance standards for forensic DNA testing laboratories. *Forensic Sci Commun*, 2000, **2**(3). Retrieved from http://www.fbi.gov/about-us/lab/forensic-science-communications/fsc/july2000/codis2a.htm.

Duewer, D.L., K.L. Richie, and D.J. Reeder, RFLP band size standards: NIST standard reference material 2390. *J Forensic Sci*, 2000, **45**(5): 1093–1105.

Duewer, D.L., et al., NIST mixed stain studies #1 and #2: Interlaboratory comparison of DNA quantification practice and short tandem repeat multiplex performance with multiple-source samples. *J Forensic Sci*, 2001, **46**(5): 1199–1210.

Frank, W.E., et al., Validation of the AmpFlSTR Profiler Plus PCR amplification kit for use in forensic casework. *J Forensic Sci*, 2001, **46**(3): 642–646.

Gill, P., et al., Report of the European DNA profiling group (EDNAP)—Towards standardisation of short tandem repeat (STR) loci. *Forensic Sci Int*, 1994, **65**(1): 51–59.

Gill, P., et al., Report of the European DNA profiling group (EDNAP): An investigation of the complex STR loci D21S11 and HUMFIBRA (FGA). *Forensic Sci Int*, 1997, **86**(1–2): 25–33.

Gill, P., et al., Report of the European DNA profiling group (EDNAP)—An investigation of the hypervariable STR loci ACTBP2, APOAI1 and D11S554 and the compound loci D12S391 and D1S1656. *Forensic Sci Int*, 1998, **98**(3): 193–200.

Gill, P., et al., DNA commission of the International Society of Forensic Genetics: Recommendations on forensic analysis using Y-chromosome STRs. *Int J Legal Med*, 2001, **114**(6): 305–309.

Gill, P., et al., DNA commission of the International Society of Forensic Genetics: Recommendations on the interpretation of mixtures. *Forensic Sci Int*, 2006, **160**(2–3): 90–101.

Gill, P., et al., DNA commission of the International Iociety of Forensic Genetics: Recommendations on the evaluation of STR typing results that may include drop-out and/or drop-in using probabilistic methods. *Forensic Sci Int Genet*, 2012, **6**(6): 679–688.

Gusmao, L., et al., DNA Commission of the International Society of Forensic Genetics (ISFG): An update of the recommendations on the use of Y-STRs in forensic analysis. *Forensic Sci Int*, 2006, **157**(2–3): 187–197.

Holt, C.L., et al., TWGDAM validation of AmpFlSTR PCR amplification kits for forensic DNA casework. *J Forensic Sci*, 2002, **47**(1): 66–96.

Houck, M., et al., The balanced scorecard: Sustainable performance assessment for forensic laboratories. *Sci Justice*, 2012, **52**(4): 209–216.

Jarman, P.G., S.L. Fentress, and D.E. Katz, Mitochondrial DNA validation in a state laboratory. *J Forensic Sci*, 2009, **54**(1): 95–102.

Kimpton, C., et al., Report on the second EDNAP collaborative STR exercise. European DNA profiling group. *Forensic Sci Int*, 1995, **71**(2): 137–152.

Kline, M.C., et al., Interlaboratory evaluation of short tandem repeat triplex CTT. *J Forensic Sci*, 1997, **42**(5): 897–906.

Kline, M.C., et al., NIST mixed stain study 3: DNA quantitation accuracy and its influence on short tandem repeat multiplex signal intensity. *Anal Chem*, 2003, **75**(10): 2463–2469.

Kline, M.C., et al., Production and certification of NIST standard reference material 2372 human DNA quantitation standard. *Anal Bioanal Chem*, 2009, **394**(4): 1183–1192.

LaFountain, M.J., et al., TWGDAM validation of the AmpFlSTR Profiler Plus and AmpFlSTR COfiler STR multiplex systems using capillary electrophoresis. *J Forensic Sci*, 2001, **46**(5): 1191–1198.

Lanning, K.A., et al., Scientific working group on materials analysis position on hair evidence. *J Forensic Sci*, 2009, **54**(5): 1198–1202.

Laux, D.L., Development of biological standards for the quality assurance of presumptive testing reagents. *Sci Justice*, 2011, **51**(3): 143–145.

Levin, B.C., et al., Comparison of the complete mtDNA genome sequences of human cell lines—HL-60 and GM10742A—From individuals with pro-myelocytic leukemia and leber hereditary optic neuropathy, respectively, and the inclusion of HL-60 in the NIST human mitochondrial DNA standard reference material—SRM 2392-I. *Mitochondrion*, 2003, **2**(6): 387–400.

Lincoln, P.J., DNA recommendations—Further report of the DNA commission of the ISFH regarding the use of short tandem repeat systems. *Forensic Sci Int*, 1997, **87**(3): 181–184.

Marquez, M.C., Interpretation guidelines of mtDNA control region sequence electropherograms in forensic genetics. *Methods Mol Biol*, 2012, **830**: 301–319.

Micka, K.A., et al., TWGDAM validation of a nine-locus and a four-locus fluorescent STR multiplex system. *J Forensic Sci*, 1999, **44**(6): 1243–1257.

Morling, N., et al., Paternity testing commission of the International Society of Forensic Genetics: Recommendations on genetic investigations in paternity cases. *Forensic Sci Int*, 2002, **129**(3): 148–157.

Ong, B.B. and N. Milne, Quality assurance in forensic pathology. *Malays J Pathol*, 2009, **31**(1): 17–22.

Patterson, D. and R. Campbell, The problem of untested sexual assault kits: Why are some kits never submitted to a crime laboratory? *J Interpers Violence*, 2012, **27**(11): 2259–2275.

Peterson, J.L., et al., The feasibility of external blind DNA proficiency testing. I. Background and findings. *J Forensic Sci*, 2003, **48**(1): 21–31.

Peterson, J.L., et al., The feasibility of external blind DNA proficiency testing. II. Experience with actual blind tests. *J Forensic Sci*, 2003, **48**(1): 32–40.

Presley, L.A., The evolution of quality standards for forensic DNA analyses in the United States. *Profiles DNA*, 1999, 3(2): 10–11.

Prieto, L., et al., 2006 GEP-ISFG collaborative exercise on mtDNA: Reflections about interpretation, artefacts, and DNA mixtures. *Forensic Sci Int Genet*, 2008, **2**(2): 126–133.

Prieto, L., et al., GHEP-ISFG proficiency test 2011: Paper challenge on evaluation of mitochondrial DNA results. *Forensic Sci Int Genet*, 2013, **7**(1): 10–15.

Prinz, M., et al., DNA commission of the International Society for Forensic Genetics (ISFG): Recommendations regarding the role of forensic genetics for disaster victim identification (DVI). *Forensic Sci Int Genet*, 2007, **1**(1): 3–12.

Rand, S., M. Schurenkamp, and B. Brinkmann, The GEDNAP (German DNA profiling group) blind trial concept. *Int J Legal Med*, 2002, **116**(4): 199–206.

Rand, S., et al., The GEDNAP blind trial concept part II. Trends and developments. *Int J Legal Med*, 2004, **118**(2): 83–89.

Reardon, S., Faulty forensic science under fire. *Nature*, 2014, **506**(7486): 13–14.

Reeder, D.J., Impact of DNA typing on standards and practice in the forensic community. *Arch Pathol Lab Med*, 1999, **123**(11): 1063–1065.

Roewer, L. and M. Geppert, Interpretation guidelines of a standard Y-chromosome STR 17-plex PCR-CE assay for crime casework. *Methods Mol Biol*, 2012, **830**: 43–56.

Schneider, P.M., Scientific standards for studies in forensic genetics. *Forensic Sci Int*, 2007, **165**(2–3): 238–243.

Schneider, P.M., et al., Results of collaborative study regarding the standardization of the Y-linked STR system DYS385 by the European DNA Profiling (EDNAP) group. *Forensic Sci Int*, 1999, **102**(2–3): 159–165.

Scott, C.L., Believing doesn't make it so: Forensic education and the search for truth. *J Am Acad Psychiatry Law*, 2013, **41**(1): 18–32.

SWGDAM (Scientific Working Group on DNA Analysis Methods), Revised validation guidelines. *Forensic Sci Commun*, 2004, **6**(3). Retrieved from http://www.fbi.gov/about-us/lab/forensic-science-communications/fsc/july2004/index.htm/standards/2004_03_standards02.htm.

Szibor, R., et al., Cell line DNA typing in forensic genetics—The necessity of reliable standards. *Forensic Sci Int*, 2003, **138**(1–3): 37–43.

Tully, G., et al., Considerations by the European DNA profiling (EDNAP) group on the working practices, nomenclature and interpretation of mitochondrial DNA profiles. *Forensic Sci Int*, 2001, **124**(1): 83–91.

Tully, G., et al., Results of a collaborative study of the EDNAP group regarding mitochondrial DNA heteroplasmy and segregation in hair shafts. *Forensic Sci Int*, 2004, **140**(1): 1–11.

Wallin, J.M., et al., TWGDAM validation of the AmpFISTR blue PCR amplification kit for forensic casework analysis. *J Forensic Sci*, 1998, **43**(4): 854–870.

Welch, L.A., et al., European Network of Forensic Science Institutes (ENFSI): Evaluation of new commercial STR multiplexes that include the European Standard Set (ESS) of markers. *Forensic Sci Int Genet*, 2012, **6**(6): 819–826.

FORENSIC SCIENCE

FORENSIC BIOLOGY

SECOND EDITION

Over the last several years, new research and developments in analysis methods and practice have led to rapid advancements in forensic biology. Identifying critical points of knowledge and new methodological approaches in the field, ***Forensic Biology, Second Edition*** focuses on forensic serology and forensic DNA analysis. It provides students and professionals with a scientific grounding in biological evidence—both the techniques utilized to identify it and the methodology to analyze it.

This second edition:

- Introduces the language of forensic biology, enabling students to become comfortable with usage and terminology
- Provides clear explanations of the principles of forensic identification and analysis of biological evidence
- Explains forensic serology and DNA techniques used in the field and the laboratory
- Discusses the benefits and limitations that apply to various forensic biology techniques
- Includes schematic illustrations to clarify concepts
- Presents three new chapters (Chapters 2, 16, and 17) created for this edition
- Adds more than two hundred new full-color figures

Covering the full scope of forensic biology, the book uses an accessible, straightforward style designed to enhance students' education and training so they are prepared, both in the laboratory and in the field.

K14098

ISBN: 978-1-4398-8970-1

90000

9 781439 889701

CRC Press
Taylor & Francis Group
an informa business
www.crcpress.com

6000 Broken Sound Parkway, NW
Suite 300, Boca Raton, FL 33487
711 Third Avenue
New York, NY 10017
2 Park Square, Milton Park
Abingdon, Oxon OX14 4RN, UK

www.crcpress.com

Healing
the symptoms known as
Autism

Second
Edition

PDF
E-Book

Kerri Rivera

with Kimberly McDaniel & Daniel Bender

Jim Humble • Dr. Andreas Kalcker
Dr. Marco Ruggiero • Robert L. Sands

Disclaimer

Healing the Symptoms Known as Autism is not intended as medical advice. This book is for informational and educational purposes only. Please consult a medical professional when the need for one is indicated. For obvious reasons neither the author, co-authors, contributing authors, the publisher, nor their associates can take medical or legal responsibility for having the contents herein considered as a prescription for everyone or anyone. You are ultimately responsible for the uses made of this book.

All content, including text, graphics, images, and information, contained in this book or our website, is for general information purposes only. We take no responsibility for the accuracy of information contained herein, and such information is subject to change without notice.

PDF
E-Book

Healing
the symptoms known as
Autism

Second Edition

by Kerri Rivera

with Kimberly McDaniel & Daniel Bender

Healing the Symptoms Known as Autism
Second Edition (PDF E-Book Version)

by Kerri Rivera
with Kimberly McDaniel & Daniel Bender

Copyright © 2014 by Kerri Rivera

All rights reserved. No part of this book may be reproduced or transmitted in any form or by any means, electronic or mechanical, including photocopying, recording, or by any information storage retrieval system without the written permission of the author. The only exception being by a reviewer who wishes to quote brief passages in connection with a review written for inclusion in a magazine, newspaper, blog, or broadcast.

ISBN: 978-0-9892890-2-3
Library of Congress Control Number: 2013945511 (LOC# of Print Edition)

1st Edition released May 2013
2nd Edition released January 2014
Printed in the United States of America

Mailing Address:
AutismO2
PO Box 10334
Chicago, IL 60611

Feedback Email: kim@cdautism.org

For further information:
www.cdautism.org
www.HealingTheSymptomsKnownAsAutism.com

The Kalcker Parasite Protocol as integrated into Chapter 8 has portions Copyright ©2013 by Dr. Andreas L. Kalcker & Miriam Carrasco Maceda.
Original English Translation by Mercy Acevedo
Edited & revised by Michael Harrah, Kimberly McDaniel & Daniel Bender

Original Cover Design: Eduardo A. Davad
http://edudes.weebly.com/

Back cover photo of Kerri Rivera by PaulVanVleckPhotography.com

I would like to dedicate this book to the families
of children on the spectrum the world over.

May all of our children
find the healing that they need.

~ Kerri

This book is dedicated to my Dominick.
I love you forever; thank you for being our angel.

~ Kim

Healing
the symptoms known as
Autism
Kerri Rivera
with Kimberly McDaniel

One of our fans currently working towards recovery thanks to the protocol.

Table of Contents

Foreword by Lorna B. Ortiz, PhD.
President of Curando el Autismo, CEA.......... vii

Preface by Kimberly McDaniel.......... ix

Terminology & Units of Measure.......... xiii

Acknowledgements xv

Introduction: Autism is Avoidable, Treatable and Curable.......... xxi

Chapter 1: Kerri's Story 1

Chapter 2: Yes We Can!!! (Testimonials).......... 19

Chapter 3: Step 1 – The Diet.......... 41

Chapter 4: An Introduction to Chlorine Dioxide.......... 77

Chapter 5: Step 2 – Chlorine Dioxide (CD) 81

Chapter 6: CDS – Another Way of Delivering Chlorine Dioxide 145

Chapter 7: CDH – The Research Continues 155

Chapter 8: Step 3 – The Kalcker Parasite Protocol 165

Chapter 9: Step 4 – Other Supplements.......... 243

Chapter 10: Step 5 – Chelation.......... 255

Chapter 11: Step 6 – Hyperbarics.......... 263

Chapter 12: Step 7 – GcMAF & Autism.......... 293

Chapter 13: Beyond Recovery: The Maintenance Plan 319

Chapter 14: Miscellaneous Information You Should Know.......... 323

Chapter 15: Final Thoughts.......... 347

Chapter 16: Healing Beyond Autism.......... 349

Appendix 1: More Miracles & Testimonials 357

Appendix 2: CD Autism Worldwide 441

Appendix 3: Accidental Cure by Optimists...443

Appendix 4: Autism Treatment Evaluation Checklist (ATEC) 447

Appendix 5: Molecular Mimicry...449

Appendix 6: Measuring the Strength of Your CD, CDS & CDH..................467

Appendix 7: Diluting HCl Concentration...471

Appendix 8: Other Uses of Chlorine Dioxide 473

Appendix 9: Blank Kalcker Parasite Protocol Chart.....................................475

Appendix 10: Lunar Phase Calendar for Kalcker Parasite Protocol...........477

Appendix 11: Health Benefits of Diatomaceous Earth.................................485

Appendix 12: Summary of Protocols...491

Appendix 13: Body Burden – The Pollution in Newborns 499

Appendix 14: Avoiding Autism...505

Appendix 15: Recipes - Cooking with Ana...513

Appendix 16: Websites We Like...517

Appendix 17: Direct Help from Kerri Rivera 521

References 523

Index 529

About the Author 563

Foreword

Autism, not the one described by Kanner in 1943, but the one that we see today diagnosed in 1 of 50 kids is a combination of immune disorders that need to be treated biomedically. There is a lot that we still need to understand about why and how these immune dysfunctions affect our kids' development, causing near complete impairment of their social interaction and communication.

There is a long, hard road ahead to fully comprehend the integrated system that comprises "autism," but our kids cannot wait. It takes more than just medical, professional, or even scientific interests working hard day and night to find a suitable and effective solution to help our kids. It takes drive, passion, and guts to do the right thing; to hear and read the overwhelming stories of parents from all over the world and not turn our backs, but help. It takes an eternal and extreme will to help, even when your own child is on the spectrum.

Kerri's protocols have been indispensible to the full recovery of many of the kids in our Curando el Autismo (CEA) Foundation. These protocols represent a readily available and effective solution to alleviate most of the pathogenic insults to the immune system. Years from now, when "autism" diagnoses do not exist, when we find ourselves fully knowledgeable about the now mysterious immune-brain-behavior connection, I will remember Kerri not only as a friend but as one of the first courageous leaders that dared to change the path for our ill kids. She goes against all odds, sharing knowledge, experience and simply making it happen.

~ Lorna B. Ortiz, PhD.
President of Curando el Autismo, CEA

“Based on parent reports, the prevalence of diagnosed ASD in 2011–2012 was estimated to be 2.00% for children aged 6–17. This prevalence estimate (1 in 50) is significantly higher than the estimate (1.16%, or 1 in 86) for children in that age group in 2007.”

US Department of Health & Human Services
National Health Statistics Reports
Number 65, Pg. 2 - March 20, 2013
www.cdc.gov/nchs/data/nhsr/nhsr065.pdf

Preface

by Kimberly McDaniel

Darkness cannot drive out darkness; only light can do that.
Hate cannot drive out hate; only love can do that.
~ Martin Luther King, Jr.

Welcome to the Second Edition of *Healing the Symptoms Known as Autism!* We are absolutely thrilled to share with you the latest protocol updates and everything else that has happened since May, 2013.

You may be thinking: Why a second edition so soon? Our first edition gave us the structure to explain the protocol, and a foundation to build on. This book has already helped many families around the world, and in fact some parents read it and recovered their children without even contacting us until afterwards! Keep in mind that when it was released in May, 2013 it was absolutely up to the minute, but as we mentioned, this protocol will continue to evolve until we have something that is consistently recovering people on the spectrum of all ages. As of January 2014, we again are sharing the latest updates, as well as a whole lot more information that we hope will be as interesting and beneficial to you as it was to us.

Here are some of the exciting new additions:

- Olive Kaiser of www.GlutenSyndrome.net has written a section on gluten and its role in molecular mimicry and autoimmunity. Since many of you are not new to the autism community, a gluten free diet for your children is nothing new. However, you may be interested to find out just how damaging gluten can be for folks who are off the spectrum as well.

- Scott McRae has contributed a chapter on CDH (Chlorine Dioxide Holding [Solution]). A new method of preparing chlorine dioxide that many families are now using with success. This gives us an even wider variety of preparations available to accommodate the needs of our families.

- The Kalcker Parasite Protocol chapter now has some beautiful charts that spell out the timing of all the components for the 18 days a month that a child will be on the parasite protocol. Thanks to Dan Bender, a lot of the confusion surrounding how to make it all fit will be cleared up. You will also find years of lunar calendars to make it easy to see when the protocol is active. You won't have to check Google again to see when the full or new moon is coming.

- The "Worm Whisperer" Robin Goffe shares with us part of her journey towards healing for her 19-year-old son. Her advice is for the Extreme Cases—Self Injurious behavior, aggression, violence, etc. If you are the parent of an older child on the spectrum, or a child who displays these behaviors, or you know someone who is living with a child like this, you owe it to yourself to read Robin's suggestions. They are full of hope and wisdom.

- The one and only Marco Ruggiero, lead researcher on GcMAF, (Gc Macrophage Activating Factor—an immune system supplement) has written an entire chapter on GcMAF and its applications for autism. A must read.

- Last but not least, a whole new crop of testimonials that will make you cry. If after reading this book you still have doubts about giving this protocol a chance, I highly recommend you revisit these testimonials. If I had to pick one part of the book that was absolute favorite, this would be it. It may be because I collect a lot of them, and usually have a little correspondence with the families to get their permission, and genuinely get to feel their excitement, their sense of accomplishment when they see their child start to heal, and not to mention their endless gratitude for being able heal their own children.

  I pray that all of these testimonials find their way to the people who need them and as a result children stop suffering because their parents see them reflected in those words and understand that if other children can heal, their children can as well.

  To me, there is nothing more real than hearing from someone that has walked a mile in your shoes. There is nothing more inspiring that to hear someone say, "I know it's possible, because I did it, I lived it, and I am here to tell you about it."

The families that courageously walked this path and then took the time to share their stories are pioneers and heroes to their own families and to our entire community and beyond. They are blazing a trail for others to follow and countless lives will benefit from their diligence, fortitude and dedication. The stories of healing come from all over the world... from children and adults of all ages. We hope that they move you as much as they moved us. We are eternally grateful for the service these families have provided to humanity and thankful that they were generous enough to take the time out of their lives to pay it forward and share.

- The book now as an extensive index making it much easier to use as a reference.

As of this printing, families are healing their children with autism using this protocol in over 58 countries! Our Facebook groups have over 3,500 members in many of these countries. CD officially knows no borders. It is absolutely thrilling to us that people are coming together with the common goal of healing their children themselves, and to help others do the same! It fills our hearts with joy to be a part of this and to be able to see and feel the love that is shared every single day.

The development of this protocol has been a growing grass roots effort, in sharp contrast to how modern medicine usually works. The reason for this is clear: Modern medicine has not really helped to heal autism and may very well be part of its cause. While we don't have any double blind studies to rest on, we do have a slew of anecdotal evidence, which may not mean much to those in the arena of modern medicine or modern science, that doesn't make it any less real. Time and time again, our *results*—children dropping ATEC points—are being duplicated by families all over the world. For a family who is using this protocol, there is absolutely nothing more real than watching their child come back to them. Ask any autism parent what they would rather have... a long-term double-blind study published in a peer reviewed journal... or a healthy child. My money's on the latter.

As exciting as it is to be a part of this, and as wonderful as it is to hear about gains and read uplifting testimonials, we know there are still families working to heal children that are very sick, and our groups share the highs as well as the lows. Kerri will tell you that some months are better than others and the gains ebb and flow. I urge you to read and reread the testimonials. These are real stories of real healing and if you haven't already I invite you to believe that your child can be one of the success stories in those testimonial pages.

All of our families are proving what many were told was impossible: Children with the symptoms known as autism can heal! This grass roots movement is creating a paradigm shift in the way the world views healing from autism. The second edition of this book will be translated into at least 13 languages including Spanish, Portuguese, French, Flemish, German, Czech, Norwegian, Arabic, Polish, Italian, Hungarian, Bulgarian and Serbian. This is exciting. This is real. And, this is a living protocol. Every family that uses it every single day is helping to shape the future and heal the children who are affected today, and quite possibly prevent children from becoming affected tomorrow. For this we are eternally grateful.

Here's to you and the continued healing of humanity,

Terminology & Units of Measure

Throughout this book we talk about "CD," which is an abbreviation for *chlorine dioxide*, a well-established oxidizer. Chlorine dioxide is also often referred to as MMS, which is the common name given to it by Jim Humble, the man who discovered various applications of chlorine dioxide. There are many books, videos, blogs and articles using the name, "MMS," which is surrounded by a fair amount of controversy. We choose to not get tangled into that debate since our focus is on helping our children recover from autism. For us, our only concern is that (1) it is safe for our children, and (2) that it works. Based on extensive use of CD on thousands of children with autism, we can confidently say that both those statements are true. If this were not so, this book would not exist.

Units of Measure

Throughout this book we talk about various measured treatment components and containers using fluid volumes and weights. Since this book primarily addresses a US audience, we sometimes talk about measures in the US system of pounds and fluid ounces; while also using the internationally recognized metric system, which is frankly... easier to use.

The common abbreviations of measure you will see throughout this book include:

l = liter (volume)
mg = milligram (weight)
ml = milliliter (volume)
lb = pound (weight)
lbs = pounds (weight)
ppm = parts per million (concentration)
fl. oz. = fluid ounce (volume)
net. wt. oz. = net weight ounce (weight)

For easily measuring small amounts, syringes (without needles) are a great tool. Don't bother going to a chain store pharmacy... they won't sell them to you without a prescription. Instead, check your local medical supply store, animal supply store, private pharmacy or protocolsupplies.com. Cost: Surprisingly dirt cheap. The complete set of five below cost about $1.00 in Mexico—less than most candy bars—and not much more in the US. Note: Some brands of syringes have printed on scales that easily rub off, especially if your hands are a little oily. To prevent from losing the markings, cover the scale with some clear tape or clear nail polish.

SensiMedical
SensiMedical
SensiMedical

When it comes to accurately measuring larger volumes, you can buy a set of 7 Polypropylene Graduated Cylinders. Of course this is not a requirement. You can use common kitchen measuring utensils, but these are more accurate and easier to read. If you decide to get them, avoid those with printed on lettering (it rubs off). Raised lettering is best, although sometimes a bit difficult to read. Typical cost on ebay™ or Amazon® for a set is around $25USD. The sizes range from 10ml to 1000ml. You can also buy individual cylinder sizes made of plastic or glass.

Acknowledgements

Gratitude makes sense of our past,
brings peace for today,
and creates a vision for tomorrow.
~ Melody Beattie

Thank you to my Mother who taught me by example the value of volunteerism and to help others who are less fortunate. Thank you for always telling me that I am the best and that I could do anything. I believed you :)

Thank you to my husband of nineteen years for supporting me on this journey. As challenging as it is, you have always stood by me. You are the love of my life, and father of the sweetest boys on the planet. Thank you for giving me the strength to be strong enough to do a mammoth job. It would not be possible without a pillar of your magnitude.

Thank you to Alex, the best big brother in the world who supports and enjoys what we do as a family and who sees the big picture. I couldn't be prouder than I am of you. I am so grateful you chose me as your Mom, and you chose to be on this journey with me, the road less traveled. I love you forever!

Thank you to Patrick for bringing to our family a higher good. You are an angel. You have brought light to all who meet and know you. Thank you for choosing me to be your mother. You and your brother have taught me more about myself and about life than I could have ever dreamed. I am grateful to you and I Love You more than words can say. Through me, you have given people their lives back. You have forever changed the face of autism.

Thank you to Linda for giving me my sister and one of my greatest friends.

Thank you Slimmie for your support, love and dedication, you are my BFF and we speak the same languages. Thank you for the support of my projects and always having me look prepared.

Lorna, thank you for supporting me, believing in me, trusting me, being faithful to your heart, and for being one of the most honest people I have ever known. You are my sister of the heart and I love you very much.

Susan Wiseman, thank you for offering your connection on that day when I most needed it. That one act of humility changed the future forever. I will never forget what you did for me.

Norrah Whitney, thank you for pointing me toward the direction of recovery, and explaining to me what I needed to do. You are without a doubt my first angel on this journey.

Ana Meckes, thank you for being another much needed angel and teaching me how to advocate for my son. I have not stopped ever since.

Anju, thank you for being my friend, for sharing with me, and for believing in me. You are a unique treasure.

Pina, thank you for helping and supporting me, we will be friends forever. I will always remember what you did for me, the clinic, and the kids.

Kenny, thank you for you excellent books full of sage advice and making biomed user friendly. Most of all, thank you for sharing fever therapy with us.

Carolina, Yamileth y El Jefe... gracias por apoyarme, defenderme y creer en mi. Son amigos en todo el sentido de la palabra. Estoy orgullosa de ustedes, moviendo montañas con el amor que solo una familia puede tener por un hijo….y ustedes lo han hecho por un pais. Les quiero mucho.

Bob Sands, thank you for seeing something special in me, thank you for taking me to meet Bernie and Mrs. Rimland. That day changed my life forever. Thank you for giving us the best hyperbaric chamber in the world. With that chamber we have seen so many miracles.

Jim, you have brought light to many and hope to all who have had the fortune to know the miracle that is CD (Chlorine Dioxide). I am grateful to you every day of my life. I have witnessed first-hand the miracle that is autism recovery. Thank you for staying the path that has never been easy. But it is as you say, "The right thing to do..." I love you.

Andreas, my dear friend, thank you for your dedication, your research and for your willingness to help. You are the science, the reason and the truth that is chlorine dioxide, the molecule that has the power to save humanity. Thank you to you and Miriam for your unfailing support over the years. Your contributions to the world of autism are changing the way the world views autism forever. And the lives of so many children are now recovered thanks to your contribution to The Protocol. Without you both, these recoveries would not have been so abundant.

Dan Bender, thank you for seeing the big picture and for giving so generously of yourself to help us help children with autism. Your selflessness has allowed this protocol to reach more families all over the world. Thank you for making the second edition of this book a reality, we never would have gotten it off the ground without you.

Thank you Michael Harrah for standing by me and working tirelessly to share the information that has had such a positive effect on so many families all over the world. Your wisdom and know-how have been invaluable to me in this book, our website and forums. You were a friend when I most needed one. I am grateful that you are in my life.

Dr. Bernard Rimland, even though you have left us all too soon, you moved mountains while you were here. Thank you for letting me train as a DAN! Clinician, and for allowing us to translate the protocol to Spanish. Thank you for giving us Infantile Autism in 1964, changing forever the thinking that autism was caused by the refrigerator mother. And setting into motion biomedical interventions for healing our children I wish we had more like you. I try to think "What would Bernie do?" and I usually get the answer. Always helping and always available. Humility. You set the standard for humanitarian.

Thank you to all the families on our forums for blazing a trail for others to follow and fighting for the health of your children every single day. You are an inspiration.

To all the Mods; Ginette, Caryn, Joy, Alison, Heidi, Michael, Pam, Katya, Carolina, Nilesh, Mirena, Robin, Debbie, Sue, Susan A., Brandi, Don, Clint, Maggie, Claire, Amber, Dawn, Naomi, Maryann, Susan R., Stacey, Jessi, Lina, Boris and Susanne, Olive, Dana, and Pat, for being the best mods in the world. Your help changes lives for the better each and every day. This is for you:

> *It's in our interest to take care of others. Self-centredness is opposed to basic human nature. In our own interest as human beings we need to pay attention to our inner values. Sometimes people think compassion is only of help to others, while we get no benefit. This is a mistake. When you concern yourself with others, you naturally develop a sense of self-confidence. To help others takes courage and inner strength.*
>
> ~ The Dalai Lama

Thank you Joy for sharing with Alison that you had heard about CD for autism through the seminar that Jim had in the Dominican Republic. That gesture opened the gates to the north and from there to everywhere. You are a special healer.

Teri and Ed Arranga, thank you for the platform and for helping so many families find what they need for their children, and never blinking, even when it gets really scary.

Thank you Doll, for a much-needed distraction from autism when I really need it most. BFFs are good at doing that.

Thank you to the Mansours, for believing in my projects and me. Your support made this book and our website possible.

Thank you to the various proof readers who helped with that fun process, including Michael Harrah, Pam Gotcher, Joy Whitcomb, Charlotte Lackney, Don Kalland, James Beyor, Cathy Fuss, Jeremy Horne, Ph.D., Luane Beck, Candace, Andreas Schreiber, Olive Kaiser, Susan, and Clint Melanchuk.

Thank you Mads, for your website magic and our beautiful logo.

Thank you Carolyn Unck for helping get this book into shape and all your support and advice.

Thank you Marco and Stefania for thinking out of the box and preserving the truth because it works.

Thank you so much Pam Gotcher for going above and beyond everyday to make sure our readers get their books!

Thank you Scott McRae, Brenda McRae, and Charlotte Lackney for contributing the CDH chapter. This new method of preparation has already been beneficial to many of our families, and is an exciting new addition to this book.

The purpose of life is to contribute
in some way to making things better.

~ Robert F. Kennedy



Alex Rivera, Kim McDaniel (Kerri's sister), & Patrick Rivera

Introduction

Autism is Avoidable, Treatable and Curable

Your body's ability to heal is greater
than anyone has permitted you to believe.
~ ***Anonymous***

Congratulations on finding this book, and welcome to the world of autism recovery. This book comes to life as more and more children with an autism diagnosis respond and recover in more than 58 countries around the globe. This book gives families a do-it-yourself guide to an *Autism Spectrum Disorder* (ASD) recovery program with answers all in one place.

I have, on my ASD recovery journey with my son Patrick, personally been frustrated with the lack of information and answers leading to lost time and money. For example, when I first knew that Patrick was no longer developing "normally" (in 2003), I was unable to get a diagnosis. Seven years, dozens of interventions and hundreds of thousands of dollars later I was still searching for pieces to Patrick's autism puzzle.

I learned over the years of many people recovering their children using various protocols and interventions, and I looked into all of them. Some gave us improvements but not recovery (most specifically for Patrick, diet). Some gave us nothing.

My goal with this book is to alleviate that frustration and loss of time and money for other parents.

I became interested in chlorine dioxide (CD) in 2010 but I was unable to find any information about using it with autism on the Internet. Since I knew that almost every child with autism suffers from similar pathogens (viruses, bacteria, candida, and parasites), heavy metal toxicity, inflammation and allergies I researched those conditions in combination with chlorine dioxide—removing "autism" from my vocabulary.

I realized with further research that CD would be excellent for curing the symptoms collectively known as autism. When Patrick was first diagnosed in 2004, his *Autism Treatment Evaluation Checklist* (ATEC) score was 147 and after six years of biomed he was at a 63. (The diets made the biggest difference in those initial dropped ATEC points). 2½ years of CD later he is at a 21. CD has made all the difference in his life, in my life, and in so many lives around the world.

I brought CD to my *Defeat Autism Now!* style Clinic in Puerto Vallarta in 2010. Today more than 115 children globally have lost their diagnosis of autism (meaning an ATEC score of under 10 points). Additionally, thousands of children around the globe have dropped points on their ATEC and are moving towards recovery. 27 children in less than 1 year in Venezuela alone lost their diagnosis of autism with a combination of diet, CD, and ocean water to the surprise of the doctors who diagnosed them in the first place. Many of those same doctors are now looking at CD for other patients.

It is my dream that every family of a child with autism be given this information so that they can decide for themselves whether they want to give it a try.

This book is a protocol for all of us. Some of you may be completely new to autism recovery; some of you may be a veteran like me and/or parents of older children and adults on the spectrum. This protocol works for even the classic "non-responders" and for those who are so close to recovery yet can't seem to get through the door. This book is for you. CD helps the body heal the symptoms we call "autism" across the board—it is an equal opportunity healer.

I know from experience that an autism diagnosis is devastating on many levels. The initial regression of a neurotypically developing baby takes away eye contact, speech, and the emotional connection between parent and child. Then, when strange new behaviors such as flapping, squealing, rocking, spinning or even self-injurious behaviors appear, you know in your deepest mommy (or daddy)-gut that your child was not born like this. It seems to take forever to get the truth about what happened to your happy, healthy baby. It takes even longer and is more confusing when you have to figure out how to heal that sick child. Far too many "health" providers in the autism field are focused on making money so we can't blindly trust anyone. We must do our own homework. The journey itself is a lot of trial and error coupled with misinformation.

Many supposed "autism experts" don't know much about recovery, or the effective order of treatments and end up costing our children time and the parents money. The less time a child spends chronically ill, the easier and faster it is to recover them. Not to mention the child spends less of their lifetime suffering the physical, emotional and mental effects of autism.

I feel that all parents who begin this protocol should expect a full recovery from autism because this protocol treats what causes this diagnosis. Our research indicates that every person with a diagnosis of regressive autism has virus, bacteria, candida, parasites, heavy metals (biofilm), inflammation and allergies. This protocol handles every one of these issues, and that's why it has been so successful. Some recover faster than others. But, every day we are one step closer to the end of autism.

How do you know if the protocol is working and how long does it take to see results?

The ***Autism Treatment Evaluation Checklist*** (ATEC) is our measure. The ATEC is an online survey that evaluates the severity of a child on the spectrum. For more information see Appendix 4, page 447. Many families notice changes from day one, while others take longer. You will get results when you correctly apply the interventions in this book in the proper order and without breaks.

What are the results you can expect from the protocols in this book?

I would love to say that everyone who follows the protocol will get their child down to an ATEC of 10 or less—what we call a recovery—and we have 115 of those already. The majority of those I'm in contact with report substantially significant improvements, even if they have not reached recovery. In the case of my son Patrick, he started at 147 in 2004 and has come down to 26. I'm optimistic as I continue to search for further answers, and will continue to share what I find.

If you are not getting results and have gone through this book including the Frequently Asked Questions (FAQs) and troubleshooting, please contact me through the forum at...

www.cdautism.org

...there are always tweaks we can make to keep moving towards recovery.

I recommend you read this book straight through in the order that it is written as that is the order in which it is to be applied. Jumping around the interventions can lose time for your child and waste money for you. Doing interventions in the correct order, when your child is ready for them, is the best to way to achieve recovery. Diligence and perseverance win the race every time.

My mission is to share with whoever is interested, the blessings that I have received. If the information presented here feels right and resonates with you, then please, give it a try. It might just be what your child needs.

This book in a nutshell:

If you want the best chance at recovery, here's the overview of how to do it:

1. The Diet: Eliminating gluten, dairy, soy, sugar, and toxins, to stop inflammation and reduce the overall toxic burden.
2. The CD Protocol to kill pathogens while using a multimineral like ocean water.
3. The Kalcker Parasite Protocol.
4. Explore and implement other potentially synergistic supplements to aid in speech facilitation, neurotypical behavior and/or seizure reduction.
5. Consider gentle chelators.
6. After 3 parasite protocols and consideration of all above steps, find a hyperbaric chamber (1.75ata).
7. Consider adding in GcMAF.

It is important to consider all of the pieces of information in Chapter 14, *Miscellaneous Information You Should Know* (page 323) and apply them from the beginning when they make sense for your child. You also may find the *Summary of Protocols* in Appendix 12 a good resource when you do not have time to reread a chapter to find something specific.

On the right is what we call the *Stairway to Recovery*. Joy Whitcomb, one of our amazing moms, came up with this so you can see just how each step rests on the previous steps, and without them you would not reach the top step… RECOVERY!

Author's Note: It is never my intention to "change someone's personality" or take away their character by healing autism. I see it quite the opposite. When children start to recover, their personality starts to shine through. The behaviors that we saw before (spinning, flapping, squealing, smearing feces, auto aggression, lining things up, tantrumming, etc.) are not personality traits but symptoms of a sick body. These symptoms start to disappear once the body begins to heal and our children can express who they really are through smiles, eye contact, words, gestures, etc. They can show us what they need and want and play an active role in their own lives. It is my dream that every child has the opportunity to mature and choose the life they want for themselves, and be responsible for making their own decisions. I truly believe this is possible for all of our children and adults on the spectrum, and I want families to have the opportunity to offer healing to their children.

Throughout this book we have used the pronoun "he" when referring in general to "a child on the spectrum." This is not to alienate families with girls or women on the spectrum. It is simply a question of fluidity. To use *he/she* or *his/hers* every time we chose to use a pronoun seemed cumbersome, so therefore we are using "he" or "his" throughout the book. We chose "he" rather than "she" because autism is five times more common among boys than among girls. As of March 2013 the CDC revealed the results of a new study conducted during 2011 and 2012 which surveyed 95,000 families and estimated the prevalence of autism at 1 in 50 children.

The acronym DAN! is no longer applicable to *Defeat Autism Now!*, as it belongs to *Divers Alert Network*. The acronym has been used in several places in this book as several of the personal anecdotes are from a time when its use was still appropriate. Today, a "DAN! Doctor" could be defined as a practitioner who received training through the network formerly known as *Defeat Autism Now!*.



Stairway to » Recovery

Step 7: GcMAF

Step 6: HBOT (1.75ATA)

Step 5: Gentle Chelators such as BioChelate and Bentonite clay.

Step 4: Add possible supplements for speech, seizures, etc.

Step 3: Kalcker Parasite Protocol (12-18 months)

Step 2: Chlorine Dioxide (CD) Protocol. Implemented gradually until full dose is reached. Administered orally, through enemas and baths.

Step 1: The Diet: GFCFSF+; Remove certain fruits; Evaluate & remove certain supplements, especially those that interfere with Chlorine Dioxide.

Concept by Joy Whitcomb.

Everything yields to diligence.

~ Antiphanes

IMPORTANT NOTICE

Please keep in mind that the protocols in this book are still evolving, and will continue to be improved as new discoveries are made. We will release new editions to incorporate those new discoveries. The topics of CDS & CDH are particularly new and rapidly evolving. This book is current as of January 2014. Please be sure to check this book's website for important corrections and updated information beyond this and subsequent editions:

HealingTheSymptomsKnownAsAutism.com

Chapter 1

Kerri's Story

"The impossible is now declared possible as soon as you agree to it. It's just a flip of the mind, letting go really, nothing more."

~ *Stuart Wilde*

"What happened, what did you do to Patrick?" That was the first thing my husband asked me when he first saw our son, after returning from a weeklong trip. This was just five days after our youngest son Patrick received his last vaccine—the DPT (diphtheria-pertussis-tetanus) + Hepatitis B + Influenza B (what is known in Mexico as the *Pentavalente*) on the 13th of August 2002 at two years and one day old.

That question was the first of many to propel us down our path paved with autism. I told Memo (my husband) that we shouldn't worry. The nurse mentioned that we could expect a fever, or he could be listless. These were completely normal reactions. Contrary to what she said, what we observed during those first days and weeks were loss of eye contact, flapping, toe walking, high-pitched marine noises along with excessive drooling—drooling that would soak the front of his clothing.

Patrick had also lost all of the speech he had acquired; Mama, Pa, *agua* (*water* in Spanish), letters of the alphabet, numbers... all of it. The only thing he wanted to do was watch videos while running back and forth in his bedroom squealing the "ambulance sound," flapping and banging his gut, and drooling through all his clothes.

Not being well versed at the time in these problematic symptoms, we chalked it up to a case of the terrible twos. But these particular terrible twos led to loss of sleep for Patrick as well as the rest of the family, antibiotic use for green nose and eye mucous, and raging diarrhea that was so acidic it would burn his skin upon contact. This would be the story for the rest of the third year of his life.

The first of many to associate Patrick's behavior with autism would be my great aunt. She mentioned to me that she believed Patrick had autism after observing him at a family get together in April of 2003 while we were visiting relatives in Chicago. It was the most ridiculous thing I had ever heard.

Nevertheless, I went home that evening and immediately Googled the symptoms of autism. Laid out on the website were symptoms like spinning objects, lining up objects, self-injurious behavior, lack of socialization, and several other factors that I felt in no way described my son. I dismissed the comment, and continued to watch my son display strange behaviors, without understanding why.

I was back in Chicago a few months later in July. While going out for a run, I saw a girlfriend of mine who has a child the same age as Patrick. We stopped to chat and she asked me how he was doing. I said, "fine." She asked me if he was talking yet. I told her he had developed language, but since March he had lost all the vocabulary that he had previously acquired. My girlfriend looked at me and said "Oh…" with a look of concern on her face. I asked her, "What's wrong? What does that mean?" Now I was extremely nervous. "Well," she said reluctantly, "loss of language is a red flag for autism." There was that word again. I told her that we had already gone through all that, because by then I had taken Patrick to a neuro-pediatrician in Guadalajara, a psychologist with a huge center in Guadalajara, and a local psychologist in Puerto Vallarta. All three of these experts had told me that he was fine; they didn't see any problems with his development.

I started on my jog, and about halfway through, it hit me that Patrick did have autism, so I sprinted home, sat down at the computer and went to the *Autism Society of America*'s website and found a checklist of 16 symptoms of autism. The directions said if your child had 12 or more than most likely he has autism, Patrick had exactly 12. Looking back, he most likely had 14 or more, but I wasn't ready to see those just yet.

That same day I called his pediatrician in Puerto Vallarta and I told her I thought my son had autism, and she told me, "No, I have never seen anything like that in your son, but bring him and I will take another look." When we went in she observed him. She said that he didn't line things up, he didn't hit his head, he would still come to me, he was 'playing' with some toys in the waiting room, so therefore my son didn't have autism.

The pediatrician told me to go home that day to wait for him to straighten out. All the experts told me he was the way he was because he was the baby of a bilingual family that—according to them—traditionally produces late talkers; his parents and brother were all late talkers. He was spoiled. He had a nanny. And, he's a boy—boys are late talkers, etc., etc. The pediatrician successfully talked me out of the diagnosis once again.

As nothing was wrong, that fall we put Patrick into a kindergarten. His teacher would tell me Patrick isn't doing this activity or that, and I replied that we had taken him to see all the specialists, and he was just a late talker. She was super sweet about it and every few months she would make a comment to me because she saw him drastically different from his classmates.

Then one day it happened, I got a call from the director of the school saying that her friend, a neuropsychologist was in town from the United States, and she would like her to see my kids. At 6pm on March 12, 2004 I had an appointment with this neuropsychologist. I had already figured that this woman wanted to see Alex, my older son because he hadn't been doing well at school. He hadn't been sleeping well since Patrick hadn't been sleeping, which led to some poor performance in school. I had already gotten the news that Patrick was fine, so when she started focusing on him and his behaviors I was slightly confused. We sat down in his classroom, and she started asking me if he always… runs in circles, flaps, drools excessively, squeals like a dolphin, etc., (we actually used to joke that his mother must have been a dolphin). After that, I told her how we had already gone to all of these specialists and they said he was fine.

I was tired of getting the run around, and then everybody asking me what was wrong with my kid when he was just taking some extra time getting going. That's when she said to me, "I can't believe they didn't tell you your son has autism."

These words changed my life forever. Of course I asked her if she could be wrong, and she said, sure there exists a possibility, but she had done her post grad in autism, had seen hundreds of cases and this diagnosis was her professional opinion. That opened the floodgates for a river of tears that didn't end for years to come.

Being a positive person, I asked her what I should do. She said, "I would like to introduce you to a group of psychologists that are in town." The next day I went with her to a hopeless place, with hopeless people and I asked her if this is something that we can cure, and she said, "No, you can do therapy with these psychologists, and that's it." Children are born with autism and they will die with it, was the basic sentiment. I knew for sure that my son was NOT born with autism. He was the smartest, bright-eyed baby ever, and we had the photos and the videos to prove it. He was not born the ghost of a child that we had now. I knew that I would keep searching until I found something else for Patrick. I became proactive and never returned to that place.

The very next day I saw another girlfriend and she mentioned that she had a book on ADD and autism, so I immediately picked up the book and it was all about diet. Gluten-free, casein-free to be specific, and I decided to start it right away. Truth be told, Patrick's diet was horrible, he had self-restricted to only dairy and wheat. Bread products and cheese were his staple foods, but the good news was he still ate potatoes. Even as an autism novice, I knew I couldn't take him to a fast food chain because those fries were coated in gluten. We started off with just homemade fries with sea salt, because that was the only thing left on his diet that he would eat. After three days of being on the diet he said three words, the first three words he had said in over a year. I knew we were onto something.

The next week I ran into a friend from tennis, I really didn't want to say hi, because I was really depressed, but I heard a voice saying to me "It's not about the road but about smelling the flowers along the way." So, I forced a smile on my face, and went to say hi to her in my great depression. Well, she started to complain about her week, so I listened patiently, and then I told her about my week; Thursday my identity was stolen on the Internet, Friday my son was diagnosed with autism, and Saturday my dog of 14 years had to be put to sleep.

When she heard all this she turned off her car and told me how sorry she was. She said that she would put me in touch with her friend that had opened the *Early Autism Center* in Toronto, Canada. When I woke up the very next morning, I had a long email from Norah Whitney waiting in my inbox. She would turn out to be the first of many autism angels in my life.

I received a lot of precious information from that email, but what was maybe the most important detail for me was that what had happened to my son was an effect of all the vaccines he had received, he wasn't born with autism, as I knew. I also hadn't caused this, and I needed to start letting go of some of my guilt. Norah also told me that we can treat autism and I needed to immediately contact a DAN! Doctor, and Dr. Bobby Newman, Board Certified Behavior Analyst and Licensed Psychologist. Norah said that they were the best, and that this group of DAN! Doctors were curing autism.

I got in touch with everybody and that same month we started our own *Applied Behavior Analysis* (ABA) program. I also took Patrick to the States to see his first DAN! Doctor. When I got back home from that trip I had bought nearly $5,000 (US) of supplements and injectables. That didn't mean I knew how to use them, and by no means was I watching my son improving before my eyes. This was June of 2004, and we went through the rest of that summer with some supplements, other biomedical interventions, and 40 hours a week of ABA therapy.

That fall, some friends mentioned to me that their father was receiving chelation in San Diego, and I had just heard someone else saying that chelation was working for kids with autism, due to their extreme metal toxicity. By the end of the evening I had the phone number for the clinic that was providing his chelation. When I called for information, they told me that they referred all of the children's chelations to Dr. Woeller in Temecula California, so I made Patrick an appointment. In March of 2005, I took the whole family to Temecula to see Dr. Woeller, because basically nothing was happening with the supplements I had been giving to Patrick. I knew I needed to keep exploring other avenues.

Several thousand miles and various tantrums later, we arrived at Dr. Woeller's office. I told the receptionist that we had come to see Dr. Woeller. To my chagrin she said, "No, you have an appointment with some other doctor, Dr. Woeller isn't even in town right now." My husband was sure I had messed up the appointment and was extremely upset with me. Meanwhile, Patrick was screaming, crying and taking his clothes off in the waiting room. They finally let us through to speak with the other doctor and after going through Patrick's autism we explained that we wanted to chelate. We had the understanding at that point that his autism was coming from the mercury in the vaccines. She told us point blank that we couldn't do everything at once, and before we could chelate we would have to clean up his gut. I flew home with my family totally deflated. We started on the impossible journey of cleaning the gut.

My first ever autism conference turned out to be *AutismOne* in late May of 2005. I met a lady who was a rescue angel for *Generation Rescue*, and I told her I wanted to chelate my son with those DMPS drops, which were fashionable at the time. She told me that when it came to my son's recovery I shouldn't take no for an answer. I had to advocate for my son, and not let myself get pushed around. With that wisdom, I called Dr. Woeller's office again and told them I wanted my appointment with Dr. Woeller himself, and I would not be given the run around. The manager listened to me and said that she would put me through to him. After a long c'onversation, Dr. Woeller agreed to take Patrick's case and that he would help me chelate my son. He agreed with me that it was silly to think that we could have the gut completely under control before beginning chelation. Eventually I got the DMPS drops for Patrick that I had so coveted, and I felt we were back on track. However, after about six months of using the drops we still saw no change.

Flashback to that same *AutismOne* conference, where I had attended a lecture about the *Specific Carbohydrate Diet* and the removal of all grains from the diet—a diet that helped Patrick inch forward minimal improvement by minimal improvement.

In November of 2005, I had a phone consult with Dr Woeller, and having been disappointed with the transdermal DMPS I decided to ask if there was anything new in the world of autism. The answer that would end up changing all of our lives was hyperbarics or HBOT (hyperbaric oxygen therapy).

I learned that there was a really nice man by the name of Bob Sands in San Diego who owned a corporation that manufactured hospital grade hyperbaric chambers. I phoned Bob's office because Patrick was going to need 40 sessions right away, and I wanted to check prices and see if there was a package discount for hyperbarics. The answer was yes, in fact there was a discount. I scheduled Patrick's HBOT, and took both of my kids to San Diego, where we stayed for 20 really long days to get Patrick his first 40 sessions of hyperbarics—two a day—everyday, morning and night.

During that time, my husband and mom would call and ask me if Patrick was better, but he was still naked in front of the TV, jumping up and down, flapping and squealing. It wasn't until we got back home that he began to pronounce the first syllables of all of the words for things he wanted, like "ap" for apple. We considered hyperbarics a great success, but like I said that wasn't until a couple of weeks after we finished the 40 sessions. That's when we really began to see the changes in Patrick. Bob always says that HBOT is the gift that keeps on giving; you can see benefits for up to two months after you finish your sessions.

Meanwhile, Bob and I hit it off right away. He had a real jovial and family-oriented atmosphere in the clinic. I told him my story and how I wanted to help people know that autism is avoidable, treatable and curable. I shared with him that there was no information, much less Biomed or autism recovery in Mexico (and most of Latin America). I wanted to help people and to share with people that there is a lot we can do to help our children heal.

The very next day he walked into the office and changed the course of my life forever. He told me that he was in fact friends with Dr. Bernard Rimland, "Bernie," the Grand Godfather of Biomedical treatment for autism, and the author of *Infantile Autism*, *Dislogic Syndrome*, and the founder of the *Autism Research Institute*. I told Bob that meeting Bernie today, would be akin to having met Mick Jagger when I was 15. He then announced that we would be having lunch with none other than Bernie himself and Mrs. Rimland. For the first time in my life, I admitted to Bob that I was so excited that I didn't know what to say. Bob told me that when it was my turn to say something that I should ask Bernie "What can I do for DAN!?"

In a tizzy I ran over to Marshall's, the discount retailer; bought a new suit, hose, and even a pair of high heels. The next afternoon, I put on my new ridiculous clothes, ditched my kids with my friend's maid, and hopped in Bob's Jag to meet Bernie and Gloria (Dr. and Mrs. Rimland)—an absolute dream come true. When we arrived at their favorite restaurant, I was completely overdressed. Gloria ordered a salad, and the guys had tilapia because Bernie didn't really like vegetables. The conversation ranged from Kinotakara patches, to the difference between soft-sided hyperbaric chambers and hard hyperbaric chambers.

I waited until there was a lull in the conversation and I went for it, I asked him what could I do for DAN!, and he said I should translate the DAN! Protocol and take it to all of Latin America. His words left me totally dumbfounded. Had I heard right? Latin America? I was thinking my town of Puerto Vallarta, or maybe Jalisco, (the state we lived in) and maybe in my wildest dreams all of Mexico, but this was much bigger than I had imagined. At this point, though there was no stopping the momentum that we had started. Within months we translated the Protocol to Spanish, and donated it to the Autism Research Institute, for dissemination throughout Latin America. Much later I would find out that one of my dear friends, Yeroline, would heal her son from autism using the translation of the DAN! Protocol, as well as others.

During that same trip my husband and I spoke to Bob about buying one of his chambers for the not-for-profit autism clinic we were planning on opening in Puerto Vallarta. The plan was to run the clinic on a non-profit basis, but anchor the clinic by charging the public for their sessions in the chamber, allowing all the profits to pay for children with autism to go for free in the chamber.

It was a green light all the way. We deposited the money for the chamber in March of 2006, and it arrived on October 31, 2006. AutismO2—Hyperbaric Clinic officially opened its doors on Dec 1, 2006. We threw a party for the inauguration, invited friends, family, Patrick's therapists, and our local priest came to Bless This House. We all wore white, and in honor of Patrick, who was our motivation for opening the clinic, we all had on nametags that said *Kerri—Patrick's Mom*, *Memo—Patrick's Dad*, etc. It was a special evening for all of us, but me especially, as it solidified what would be the path that I would still be walking as I write this book seven years later.

The clinic had a Sand's Hyperbaric Chamber, an allopathic physician with a specialty in Hyperbarics, 2 psychologists, 2 hyperbaric technicians, and me, to initially meet with the parents. As for the chamber, we always knew that it was going to help a lot of kids with autism, but it has helped a lot of others as well. The chamber was what gave language back to Patrick in 2006.

Later that same year we sent our allopathic doctor with our naturopathic hippie doctor to Ixtapa, Mexico for a hyperbaric conference, where they serendipitously met Dr. Giuseppina Feingold, (Dr. Jo) a DAN! doctor using hyperbarics for children with autism. As soon as our guys got back to Puerto Vallarta they started insisting that I had to contact her because she is curing kids with a protocol that included hyperbarics. Never one to waste time, I emailed her immediately, but at the time I didn't know she wasn't an email person and, because I am just not a phone person, we didn't connect.

Fast forward to January 2007, my husband, Memo, was buying a 1951 Desoto on eBay. We had to pay for the Desoto with a check, and therefore started to talk to Bryan, the seller of the car. During their conversation, Memo, my husband, said to Bryan "If you don't want to sell, because it's worth more than your selling price I will understand." Bryan had already decided to let it go, but at the same time he was interested in where the car was going, what Memo did for a living, etc. Memo told him about our life in Puerto Vallarta, and the classified ad magazine business that he owns. That's when Bryan stopped him and said, "I've heard of that magazine!"

It turned out that this Bryan was a nurse who works with a doctor who does hyperbarics and heals kids with autism. Well, that piqued Memo's interest, so he told Bryan about Patrick's autism and then Bryan says you must call Dr. Jo, yes, the very same Dr. Jo that our clinic doctor had met months earlier at the Hyperbaric Conference in Ixtapa. So, I called her immediately and when she answered I said who I was, and I told her Bryan told me I had to call her. I asked her if she believed in God and she said yes. I went on to tell her that in September she had met with my clinic's doctor and how I had emailed, but never heard back. At the time, Dr. Jo had been receiving so many emails that sometimes she couldn't get to all of them.

Finally we had connected, and we hit it off right away. I immediately told her all about the clinic and Patrick, hoping that she could come to Vallarta. She told me that I had to go see her in New York first, and we would get Patrick some treatment. So off we went to freezing cold New York in March of 2007.

We immediately started treating Patrick with IV chelation. The theory at the time was the main factor causing autism were heavy metals coming from vaccines that were damaging the methylation pathways. During my daily treks to Dr. Jo's office I finally met Bryan, the owner of the Desoto that my husband bought on eBay. We started talking about my clinic and what we could do collaboratively if Bryan were to move there. Bryan had already been in nursing for almost 30 years and was an expert in ozone and other alternative therapies. He told me he was ready for some changes, and we were very interested to have someone of Bryan's caliber and relaxed personality to join us at the clinic.

Within a week of my return to Puerto Vallarta Bryan came for his first visit, to see if he could call Vallarta home. Two months later he came back with all of his equipment to set up his office. We were a great fit, and Dr. Jo would fly down from time to time to help out with patients.

From 2007 to 2008 we were treating Patrick with IV chelation on top of his regular GF/CF/SF, diet, supplements, and hyperbarics. In May of 2008, I met a mom who had recovered her autism spectrum child with homeopathy. Almost immediately I started working with a world class homeopath from June 2008 to May 2009, but I didn't see anything to make me feel that the cure to autism was down that path. That same year I met a doctor doing the Yasko protocol, and she had some ideas, so we gave it a try from August 2009 until the end of May 2010. At that point, Patrick honestly looked worse than before we had started giving him 80 supplements a day.

By now I had become disenchanted with *Defeat Autism Now!* based megavitamin protocols. A precious few of the families that we helped recovered their children with diet, supplements, chelation and hyperbarics. However, the overwhelming majority still had an autism diagnosis after tons of work by their parents, and usually a lot of money spent on supplements and treatments. I started feeling like it was a fraud, telling people to follow this protocol, which I knew wasn't going to be enough to recover most of the kids. That's not to say that we weren't seeing vast improvements, but counting all of the children that we worked with, only two children recovered.

By July of 2010, I was totally disillusioned and befuddled and I didn't want to continue doing what I was doing the way I was doing it. So, I asked the Universe/God/Angels—whoever was listening, for help. If my mission truly was to help families recover their children from autism then I was going to need a tool to work with. One that was available on every continent and that was affordable to everyone, because what we had just wasn't doing the job.

No magic voice came, thank God! Because that would have really freaked me out. However, I started to remember these colorful little bottles of chlorine dioxide that I never used. I decided to research their use on Google. Disappointingly, there was absolutely nothing on the Internet about autism and Miracle Mineral Solution (MMS) aka chlorine dioxide (CD). So I started thinking about what autism is made up of. So, I Googled chlorine dioxide with virus, bacteria, candida, heavy metals, blood brain barrier, allergies, and inflammation. The evidence was overwhelmingly positive, which showed me that CD could treat all of the components that make up autism. I had hope once again.

I was especially interested because at the clinic, we specialize in oxidative therapies such as hyperbarics and ozone. As chlorine dioxide is more benign than what we were already using, I decided to investigate further.

No side effects except a possible Herxheimer reaction; which is not a side effect of chlorine dioxide itself, but can happen with any detoxification protocol. I decided to speak to my husband and son Alex, who were also excited. The next day at the clinic, my husband's best friend's cousin and his wife were getting out of the chamber. I said, "Hi!" and she immediately said to me, "I'm taking CD." She didn't say "Hi!" or "Kerri!" just, "I'm taking CD." That was the definitive moment for me—my Aha! moment. I told her I had been researching it for weeks, and I was extremely interested. She was having great results, so my husband said he would try it first. If after three days on the drops he was still alive then we would start Patrick on them.

I contacted Jim Humble, discoverer of CD. I was hoping he would help me to better understand how to dose CD for children with autism. I explained to him that there was nothing on the Internet for kids. He helped me do just that. He gave the following recommendations: 1 drop 8x a day for children under 25lbs, 2 drops 8x a day for children under 50lbs, and 3 drops 8x a day for children under 100 lbs. He told me that the more doses that we can get in one day the better, 8 doses are the minimum.

That first week Patrick vomited (classic Herxheimer reaction), because I went too fast with the dosing. On the Internet, the only protocols I found gave high doses a few times a day, and as I found that week low and slow doses all day was the way to go. However, despite the Herxheimer reaction I caused Patrick (through lack of a low and slow dosing protocol) he was still noticeably better. Seven days later my son had improved eye contact and was asking for things that he had never requested in his life. At 9pm he looked me straight in the eye and said, "I want bed." With my jaw hanging open in disbelief, I followed him upstairs to his room. When we got there he turned to me and looked me straight in the eye again and said, "I want take bath." I knew I was not dreaming, and I had really just heard that. After his bath he looked me straight in the eye and said "I want brush teeth" and the whole time we brushed his teeth he was giggling... so I asked him what he wanted and he said, "I want 'kanket'" so I said, "blanket" and he repeated, "blanket, yes" and ran to the bed, and jumped on it to enjoy the blanket. He had never jumped into the bed in his life before that. This was the first seven days on CD. I was blown away.

By September of 2010, every person that was previously only using herbs or medications to kill viruses, bacteria, candida and other pathogens was about to hear about CD. That's when things really started to happen.

Back in 2007, I learned how Dr. Anju Usman was having great success with her biofilm protocol. She concluded that virus, bacteria, candida, parasites, and heavy metals are all joined together in the biofilm (more on this in Chapter 5, starting on page 117). And when I saw that CD killed pathogens and neutralized heavy metals and so many other things that make up the core of autism, I knew we would kill a lot of birds with one stone. I was also hoping to sidestep a few pharmaceutical pieces of the biofilm protocol, i.e. antifungals, antibiotics, antivirals and be able to use something with no side effects (a Herxheimer reaction is different than a side effect).

I was in the process of discovering how we could use this extremely inexpensive oxidizer that is available all over the world to help the body heal from autism. The other important part of CD is that you don't need to take your child somewhere for treatment, as in the cases of hyperbarics, ozone or IV chelation... there is no doctor needed, or trips to visit doctors in other countries. It's as simple as taking a supplement and you modify your dose depending on what you feel and see. Basically, any family with access to the internet, diet, CD and a few choice supplements can heal their child with autism.

After having limited success with my son on different biomedical treatments, even with the best doctors in the world, it was time for a change. With CD we are attacking the biofilm all day as CD destroys the electron shells of the different molecules making up pathogens, therefore releasing toxins into the bloodstream. This release of toxins is the principal reason one must go slow and build up the dose, to avoid a Herxheimer reaction as so many of these children are very toxic. If we kill too many pathogens at once, too many toxins enter the bloodstream. The body will immediately look to eliminate them, most notably through diarrhea and vomiting. This is unpleasant and totally avoidable.

CD is so benign you can use it on your skin, hair, ears, eyes, orally, rectally, vaginally, inhaled, etc. At the doses we use CD in aqueous solutions; it is not detrimental to healthy cells. It specifically targets pathogens due to their negative charges. Once I understood the basics, and Patrick was still improving, I started to share with others to understand how to use CD. Very quickly we were having success that many other clinicians weren't having. Kids on the spectrum were improving, some started recovering, and we had to sit up and take notice. I was blown away again.

In November, a child recovered and then in December another child recovered. Their families took them to psychiatrists and their doctors to have their diagnosis removed. These were the very important first steps that convinced me that this is something that we must continue to do. We started to spread the word that this was an inexpensive treatment modality available in every continent of the world.

With my background in biomed I learned that you watch for reactions while you load the dose. *Low and slow* is the rule. We arrived at the one-drop at a time dose and as kids recovered, parents shared their stories with other parents and more and more people started using it. It was very grass roots.

This is when the explosion happened. I started to think that this might be the missing piece of the puzzle that we had been looking for. In all seriousness, there is no one cure for all kids with autism, which is why each child's protocol and path to recovery is different. While we have seen great success with CD today I keep working to discover new modalities that help these children heal as non-invasively as possible. Now that we had had success in the Spanish-speaking world, I needed to share these treatments with families of children with autism all over the world.

Around this time something very interesting started happening with the CD enemas... parasites; more specifically roundworms were coming out with the CD enemas of the parents and their children using the Protocol. Today I have hundreds of photos, which were sent to me from parents all over the world (first world and third world nations) who have seen worms passed in stools.

At the moment laboratory testing is woefully inadequate, but a keen veterinarian can easily check for the presence of parasites in a stool sample using a high-powered microscope. The children who have had stool samples reviewed by microscopy have come back positive. Pinworms, roundworms, tapeworms and hookworms are the most common findings. Stool analysis done by laboratories have consistently come back negative even when worms have clearly been seen and photographed and seen under the microscope. In fact, one mother I know sent in a live, moving worm that her child had passed. The result? Negative for parasites! At this point it is simply not enough to trust a coprological analysis when looking for parasites.

Dr. Andreas Kalcker and Miriam Carrasco have been instrumental in this piece of the puzzle and have designed an amazing parasite protocol that has already helped many children including Patrick. In October of 2011, Andreas gave me the first parasite protocol and families in Spain, Mexico, Venezuela and others throughout Latin America began to use it. We'll talk about it in depth in Chapter 8, page 165 and how it has affected my life as well as the lives of so many other families with children on the spectrum.

In January of 2012, I got in touch with Teri Arranga and I was invited to speak at *AutismOne* in May of 2012. This would be the first time I would present at *AutismOne* in English, and obviously the first ever presentation on CD. After eight years of biomed and six years of helping families in Latin America I would be flying above the radar, knowing full well there would be a tradeoff. While I would reach families all over the US, for the first time I would end up taking a lot of flak in the blogosphere. We survived!

When I first came across CD in 2010 and began to watch it work it's miracles with autism, I expected parents, doctors and professionals who dealt with autism to be excited. I assumed they would begin to do research as to how and why the chlorine dioxide molecule was healing/curing autism. Much to my chagrin, many people were disinterested. Some even went so far as to say that what I had seen was impossible or that CD was toxic. Well, to that I would say that healing/curing autism with a toxic substance is impossible. Since then a handful of some of the best doctors in the world have become interested (that number is growing) and quite a few parents are taking note. Hundreds in fact went to my presentation at *AutismOne*. Several told me in hindsight that they had thought about not attending because the title of the presentation sounded too good to be true... *40 Children Recovered in 21 Months*.

The people who did attend were pleased with the information and many began the Protocol. However, what was to happen the days and weeks after my presentation blew my mind and was absolutely beyond my wildest nightmares. Some parents attacked me in print and on the Internet. I received threatening and accusatory emails filled with hate speech and foul language.

In most cases these emails and blogs were from anti-biomed parents. Others in the biomed movement told me not to worry, that these people were notorious for doing this sort of thing to others. They jump on the newest and brightest intervention in order to get their time in the limelight. Stealing attention away from the treatment, altering the truth, and in some cases lying to people about what is happening just to get other parents up in arms. Never could I have imagined anything like what transpired. However, as time passed, so did the threats, negative blog posts, etc.

Update for 2014

One of my favorite quotes states:

> *"All truth passes through three stages. First, it is ridiculed. Second, it is violently opposed. Third, it is accepted as being self-evident."*

Fortunately, the 2013 *AutismOne* conference was a totally different experience—which may indicate we are slipping into that third stage. In May of 2013, we were at 93 recoveries, and during my presentation at *AutismOne,* some courageous parents took the stage with me to share their children's stories of healing and recovery. There were no attacks. As the first edition of this book launched at the conference, many of our wonderful moderators were on hand to answer questions, and assist parents who were interested in getting started. I had a book signing along with the pleasure of meeting many parents I had up until then only known through email or Facebook. By January 2014, the first edition had already sold thousands of copies. If you searched for "autism" in the category of "books" on Amazon, it was showing up in various positions of the first two pages of over 10,000+ results, with the majority being five-star reviews. If you changed the order to "Average Customer Review," it was in the top 10, sometimes in position #1.

This has always been a grassroots parent driven movement, and today help is available in 7 languages online to answer questions and offer support. As with anything, if you attract enough attention, you will also attract some "haters," however CD has already earned itself a place in the treatment modalities that are healing the symptoms known as autism.

CDS (chlorine dioxide solution) was introduced in the first edition, as we were still hoping that it was something better than it turned out to be. It was a better tasting and more tolerated form of CD, and still remains an excellent preparation choice for those who are extremely sensitive, and have trouble tolerating even one drop of classic CD. However, we found that over the long haul, only one child so far has recovered with strict CDS use—the other 114 were with classic CD.

In this edition we are introducing *Chlorine Dioxide Holding [Solution]* (CDH). When this preparation technique was introduced it was touted as something similar to CDS… having a better taste, is better tolerated, along with less Herxheimer reactions. However, there is one big difference; CDH still contains a small amount of the raw materials required for the preparation of CD (sodium chlorite and citric/hydrochloric acid). On the other hand, CDS was chlorine dioxide gas ONLY dissolved in water. That small amount of raw materials in the CDH preparation may be what makes the difference. After 90 days of CDH use with over 70 families, it has not failed. Gains have not plateaued, and parents seem to be having an easier time increasing their children's dose, without any Herxheimer reactions. Another amazing thing about CDH is that the natural sweetener *Stevia* can be added to improve the flavor, while the potency of the dose does not change. This can be a game changer for kids that have taste aversion to classic CD. It should be noted that not all brands of Stevia are created equal and there may be some that can't be used. We are still testing various brands.

CDS and CDH have both earned their place in methods of chlorine dioxide preparation, thus allowing more people to benefit from the healing properties of CD who might not have otherwise been able to tolerate it.

People are always interested to know how my son Patrick is doing, and I am happy to share a little bit about what has been going on in his life lately. This past August 2013, Patrick turned 13. I had expected him to be recovered by now; however, we are still working towards a full recovery. He is better every month and his current ATEC is somewhere between 22 and 24. Patrick is very social, he loves a party. This Halloween, my sister threw a party and it was 11:30pm before he was finally ready to go home. He also loves spending time with his family. Every night he tells me, "I love you Mommy, gimme kissy." That is not only his way of telling me he wants a kiss, but that he wants me to come spend time with him before we go to sleep.

He has been preparing his own food in the kitchen, and while he has always liked to help chop, his being able to place his selection in the toaster oven and heat it himself is new. We didn't show him how to do this. He decided on his own that he would heat and serve himself his dinner one day. Another major advancement is that he is now able to clean himself after toileting, which is something he always asked for help with before. He will even wear headphones when listening to YouTube videos or watching DVDs if someone has to make a phone call.

We don't have any conduct issues, and if no one told you I had a son with autism, and you saw us out, you would never know. Apraxia remains the biggest factor delaying Patrick's recovery. That said, Patrick does communicate more than ever, and attempts more language than ever before.

As far as where I see this movement heading in the future, I believe that if truth does pass through 3 stages then we have finally entered the third stage of "self-evidence." The CD Protocol has now recovered 115 children (as of

December 2013); is used in 58 countries; and has already helped over 5,000 people on the spectrum, with more and more being added every day. The power of social media allows for parents to share with other parents their successes with the protocol, thus forming a stronger bond. Parents in the autism community trust other parents above doctors, and rightfully so.

At this point we are breaking many stereotypes associated with healing autism. For example, we now know that after the age of 9, recovery is still very possible (a 31 year old man is nearing recovery as I write these words). You do not have to be rich to recover your child from autism. You do not have to speak English—there are Facebook groups in 7 languages and this book will be translated into at least 13 languages. We now know that autism is not a psychological disorder. It is biomedical... viruses, bacteria, candida, parasites, and heavy metals cause the behaviors that lead to an autism diagnosis. Once you remove what is causing the symptoms, you can remove the diagnosis.

I witness on a daily basis what was not supposed to be possible: the healing of autism.

The future is bright, and it is up to us to share it!

Best in health,

Alex, Kerri & Patrick Rivera

Jim, Andreas and myself in Venezuela where 2 of the most amazing women in the world have a foundation to help Venezuela heal from the autism epidemic. I am so grateful to Yamileth Paduani and Carolina Moreno for their foundation and hard work. 28 recovered children from their foundation with this protocol in their first year of service. Thank you ladies. I am so proud to be your sister of the heart.

Healing
the symptoms known as
Autism

Ty reading and healing

Chapter 2

Yes We Can!!!

Without faith, nothing is possible. With it, nothing is impossible.
~ ***Mary McLeod Bethune***

Before we embark on the path of healing autism, it may provide you some comfort and encouragement to hear from those who have gone before you.

Some of the parents of the children who lost their diagnosis through this Protocol were generous enough to share a photo of their children along with a "thank you note." You will see that a couple of the older children wanted to write their own notes and share their success with the world.

①

My son gets to
play little League!

Thanks to ATEC of 4,
autism IS treatable!

THANK YOU
KERRI!

②

OMG! I'm still rubbing my eyes. Nathan just played with cars appropriately! He pushed them along while saying, "vroom vroom!" Until now, he would simply mouth, spin or tap toys.

-Week 5 of MMS

③

Today in my son's school they had an "I Can Run" day for good health and to collect food for families in our community. Last year he couldn't make it 1 mile - they run / walk around a track. This year he ran 2 miles... Whhaattt? 7 months on mms and 6 months treating parasites.

④

I love you Miss Kerri,
Thank you for giving me CD.
Matthew

⑤

Wow! Here is something to be grateful for! It was time to do my son's one year ATEC doing MMS (7 months detoxing parasites) and his score was...drum roll please...15! You read it right, a 15! I am tearing up right now writing this. My son is 14 years, 4 months old. He was at a 27 when we started, then went up to a 34 when we started treating parasites (behaviors worsened), then down to 21 three months ago, and now a 15! Thank you so much Kerri! Without you, who knows where he'd be.

⑥

Before MMS we were able to get my sons atec score down to a 24. Although he mainly functioned as a "neurotypical" child, he still would have behavioral problems. He was easily agitated and would struggle with some anxiety and OCD. We were constantly battling yeast, constipation, metals and come to find out, parasites! We began MMS very slowly. We noticed his moods were improving. He was smiling more and over all just really pleasant to be around. We decided to retake his atec after only 1 month. It was a shocking 4!!! It dropped 20 points in 1 month!!! We have our boy back and will forever be grateful! We will be starting the parasite protocol this month and looking forward to an atec of 0!!!

⑦

I just wanted to share that today my daughter said a full sentence!

She normally only makes two word sentences and often stutters and stammers, with a lot of articulation problems.

My husband came home after a week away for work and she walked up to him as he sat at the computer and she said: "I want... to sit with daddy."

And in the bathtub (I'm doing the MMS steambath as both my kids are coughing right now), she turned to her brother and said "Look brother, cup." and she held the plastic cup in front of him. She has never been this coordinated and 'present', nor articulate. I am so grateful.

Even though we still have a long way to go, I feel like a huge weight has been lifted off my shoulders. Thank you for your hard work.

⑧

Thank you for helping me to rescue my son. God bless you Kerri Rivera!

⑨

My son is at a three-day camp with 100 NT 5th graders! We have provided all his food, and go up to give supplements twice a day... other than that, he is on his own sleeping with friends for the first time in his life! I have no words other than Praise The Lord for bringing me Kerri Rivera and also for giving me and my family the strength to never give up! Our little bird had taken flight... thanks be to God!

Thank you God for your fidelity, thank you my beautiful girl for giving me your gaze and your smile every day, thank you Kerri McDaniel de Rivera for walking with me.

⑪

Hello, I'm Silvia, Alejandro's mom, we live in Spain. I was giving MMS to my son for 10 months without seeing any changes. Kerri told me that I wasn't doing something right... and that was correct. Being the warrior she is, she made me tell her everything I was giving Alejandro and she got it, Alejandro drank pineapple juice all day long, he would take more than a liter a day and that made the MMS not work, I stopped giving him pineapple juice 2 months ago, and he is a new child... He pays attention, his comprehension is almost 100% I must say my baby did not speak, but with this he started saying: "Come on, mom!" "My mommy" All this because I started giving him the MMS as I should. I want to say NO juice near MMS because it anulls its effectiveness. I thank God for putting Kerri in my path. My son improves everyday, slowly but you can see that he is saying goodbye to his little world. Thank you Kerri for being in our lives and for making us see the light. Also thank you JIM HUMBLE for giving hope to our lives.

⑫

Thank God for putting Kerri Rivera in our path, and giving us our prince back, totally recovered.

⑬

My son turned 12 today - hooray!! This is truly the very first time since his 1st birthday that my heart didn't shatter into a million pieces because it's another year down the road, and still so far away from recovery!! He decided that he was staying at home today to play with his birthday toys, he told his teacher (several times over), and when she asked if she could take the day off too, he said "nooooo!!. When his grandpa called from Holland to sing Happy Birthday, he sat quietly listening with a smile on his face - the usual is "no singing!" Besides that - here's my brag for the day - his teacher told me that she had to move him and his best class buddy away from each other because they were copying each other's work!!! YAHOO - we were SO excited - yes I know, we're crazy, but hey - if it's typical, I don't care what it looks like, I WILL TAKE IT!!! If you think this is weird, you should've seen me when he bit a child when he was 3!! I want to encourage you all today, look for the small things, check in with the people who are in contact with your kids and keep a journal of the changes. You will be amazed at how much we miss, because we spend every waking moment watching over them! I feel SO blessed!!

14

Dear Kerri,

Thank you so much for bringing our son's smile to life. The happiness you see in these eyes comes from listening to you and your amazing protocol.

We were stunned when his ATEC dropped 18 points in 3 weeks, and has now reached a staggering 1 from the original 36 in less than one year.

I thank God every day for having me in that AutismOne lecture in 2012 where you opened my eyes to what else we could do to help him. I want every parent out there to know this is a real Protocol with real results.

Thank you again and God Bless everything you do for our Children.

You Rock! Love Maryann

15

Greetings from Monterrey.

Just to let you know, we went to visit you in Puerto Vallarta on June 21st, and my child started treatment in July with MMS. As of today my son eats almost all on his own, and wipes his mouth whenever he needs to. For about a month now he has been doing funny things; like covering up his cards when we play as if to hide them, if he sees me squatting on the floor he runs over and jumps on me. He shows expectation on his face when he knows that I am coming to tickle him. He hides behind a wall when we play hide-and-seek.

In both of the institutes where he goes they have told me he is able to pay attention for longer periods of time, his way of being has changed, and they have also said that his eye contact is much better. According to his therapist he is now a candidate for speech therapy because he is able to pay attention.

For us, Kerri, this is a miracle come true, to see our son waking up little by little and to see him eat all on his own. Thank you so much for sharing all of this with us.

⑯

Since starting MMS my daughter's play skills improved, she actually looks into my eyes and gives me eye contact which means a lot. She started answering questions, more engaging and now I started to feel as if the end of the tunnel is not too far. I am so grateful to Kerri for showing me a way to recover my child. GOD BLESS.


You are the angel that God sent us.
Autism is curable!
Thank you Godmother Kerri
⑰

18

Hi Kerri,

I cannot believe it has been 5 weeks since we spoke on the phone.

My son turned 22 yesterday. He actually opened each birthday card, and read the inside. We always knew he could read, but he Never showed an interest in opening cards or gifts. He had some interest in his gifts last night. He has been wearing only light grey shirts for 5 years. This week he wore a blue one and a charcoal grey shirt.

Looking straight at me, and asking for what he wants. No real bad effects yet. We are on 22 drops as of today. 2 enemas a day 300ml - 8 drops - ocean water in the morning.

I have attached 2 pictures from this week, I think these are worms.

Can I hope that he can get better?... After all the treatments we have been through?... well I am. I think, what will I do with my time when he is better (possibly recovered)?... I will yell from the roof tops and dedicate myself to helping other families. Is this what I was meant to do? My purpose? I would love it!

19

Thank you for this look.
I share this look with
you, the same look
that you have given
back to my Mom, this
photo would not be, if
it hadn't been for you.
I love you very much,
your Godson Gabriel

⑳



My family and I are very grateful to Kerri Rivera for making available the CD protocol to treat ASD which has recovered myself and made a huge difference to thousands of kids and families all over the world.

CD can recover even a teenager like me whom others had given up on. Of all the bio-medical interventions, CD cost the least and made the biggest difference.

Muchas Gracias por salvar mi vida Kerri.

㉑

This is Benjamin. 4 years 5 months old, current atec of 4 and dropping weekly :) Diagnosis atec at 3 years 2 months was 134. Atec when starting CD protocol was 18 and was stagnant after full on bio-med/ diet intervention. Dropped all supps except melatonin when starting protocol and obviously can't be happier with that decision. Thank you to Kerri Rivera of course for giving me a way to save my baby boy... We will continue with protocol until atec = 0 :)

㉒



To my God Mother Kerri,
Because of you, my eyes are
seeing life as it should be...
FULL OF HOPE!
Love, Gannon

㉓

My sons started using MMS exactly 2 and a half months ago and we saw improvements almost immediately, my twins attention got better just days after we started the treatment and at 10 days after starting my son Juan Pablo started calling me mom! He has never done that before. (Neither of my twins were verbal, meaning they were not able to speak a single word.) A few days later Jesus Alejandro said "Mom, water" while pointing to the fridge, it was shocking for me.

My two sons can now say 4 or 5 words and their communication skills have gotten a lot better, even if it's not verbal they are very good at expressing what they want. There is a lot of improvement in comprehension, following orders and accomplishing small tasks, they react when you say their names, they are controlling their bowel movements, and in general their whole quality of life has gotten so much better since they started with MMS.

I know we have a long road to go but we are on the right track and I trust that thanks to the science that discovered the great effects of this wonderful formula for our children with autism we will recover them, as it truly does detoxify!

Ing. Artebys Cedeño
Mother of Jesus Alejandro and Juan Pablo

OAHU
Surf Academy

24

Dear Godmother Kerri,

How can we ever thank you enough for crushing autism out of TJ's life? We now have a smart, happy, helathy boy that has great confidence in himself!

We are forever grateful to you!!!

25

We started using MMS a month ago. We are not even at the full dose yet but have been seeing some amazing gains.

I took my son to the mall about a week ago because it is one of his favorite things to do. When we got home he did something he has NEVER done before. He came up to me, hugged me and said "Thanks". Wow.

Two days ago my husband had to go to the local farm supply store because something broke in the barn. So we asked my son if he wanted to go and he literally jumped off the couch and excitedly came with us. While he was there he picked out a couple of books he was interested in and a couple of small vehicle toys. When we got home I was helping him with his coat and boots he said "you're great mom". Never have I ever had spontaneous comments like this and the only thing I can attribute it to is the MMS because we stopped everything else. This gives me inspiration to continue the protocol and I look forward to what the future holds for my son and our family.

Thank you Kerri!

26

If it were not for you Kerri, my mother would still be worried about my future.

You are my Guardian Angel!!!

Autism is curable!

Thank you Kerri
Gracias Kerri!

27 His speech therapist told me today that his sentences are so much better, more organized, also his ability to converse back and forth and also his concentration have improved!! Sooooooooo..... Yay!
Oh, before we went to see his speech therapist he said: Mummy, my speech is getting so much better!
Yup, he said that! He knows!

28

I can't believe it! I just did my daughter's ATEC and in one month it dropped from 72 to 48!!! I am so shocked! Is this a dream? We revised the scores over and over with my husband and accepting that some of our answers could be just very positive feelings, still the improvement is huge!! I am so thankful Kerri Rivera! I have no words!! I am praying this is not a dream!! THANK YOU SO MUCH!!!! I believe there is more to come but right now I am so much in shock!

㉙

I have to post our Sunday gain, my daughter is and always has been on sensory overload, those of you who deal with this know that teeth brushing, hair combing and showers can be torturous for child AND parent. I literally dread washing her hair. She screams so loud she could break the windows. She smacks her wet thighs so hard that they've been bruised for years. This morning she gets in the tub, sits down and sees me roll my sleeves up (which is usually the moment she loses her mind because she knows I'm about to grab the shower head), she stood up, looked me dead in the eye, smiled at me and said "R. shower". I began to wet her hair down, still convinced that the screaming was about to begin any minute. I started shampooing and she said "well done", I smiled and said "VERY we'll done baby". My husband peeked in to see why it was so quiet and she looked at him and said "Daddy shower", smiling from ear to ear as to say 'I'm taking a shower Daddy'..... what a great way to start our Sunday. HUGE, HUGE deal for her and for us. I feel like I finally exhaled today. MMS rocks and so do all of you!!! Happy Sunday ;-))))

㉚

Dear Kerri,

Thank you SO MUCH for helping us with our daughter's complicated health issues. The CD/PP protocol allowed my daughter to sleep through the night, for the FIRST time in 7 years! One month on the parasite meds, she began sleeping perfectly and has slept perfectly ever since!

We are FOREVER grateful! Also, the more her pathogen load decreased on the protocol, the more foods she would eat and LIKE!

My daughter eats SALAD now! AND will try any food I give her. I thank you from the bottom of my heart and will be forever grateful!

With love,

The WHOLE Clark Family!



㉛

I was cured,
Yes we can.

I love you
very much
Godmother
Kerri!

㉜

My son had a great week - yesterday we went bowling as a family. It's difficult with him to notice gains sometimes because he is really close - his ATEC was a 7 last time I did it and the changes in him may be subtle and harder to notice. While we were bowling he was calm (despite the loud music, lights and commotion) he sat in between his turn watching everyone, (and the music videos playing) knew when it was his turn and cheered for me (I was beating my husband at the time - lol). He carried his ball down the lane and swung it with one arm - omg!! It was the most NT I have seem him! He now is a brown belt in Tae Kwon Do and this was the first time he was able to swing the ball - I used to have to carry the ball to the ramp, help him lift it and count to 3 for him to push the ball. He was diagnosed hypotonic at 3.5 years, MMS and PP are what helped him get some strength, energy and endurance. I increased his MMS by a drop about 2 weeks ago and we are also ramping up on GcMaf.

Great FUA moment today. My son took his first ever lesson.... swim lessons. He did amazing!!! Followed all instructions, waited in line, smiled, talked, and let the instructors help him. Amazing.... I cried almost the entire time. At one point he smiled, waved, and said "hi mommy." ㉝

㉞

Thank you Kerri!
Because we followed the protocol with obviously great results.

㉟

My son has continued to improve on his handwriting and his anger has melted away. We had an IEP today and we lost 2.5 hours of services because he has done so well he does not need those services. They were surprised at how well he is doing. And he fed his little brother soup tonight to get him to eat his dinner.

Thank you Kerri for
helping us to recover our son!

㊱



37

*I'm Number 102!
Thank you for giving me a chance at a future
Kerri Rivera!*

On any given day, I probably rattle out the words I LOVE YOU, directed at my boys at least a dozen times. My NT boy almost always will reply back. My ASD boy usually says, YES YOU DO as his answer. And I have completely accepted that that is his way of receiving my I love yous.

On very rare occasion he will say I love you to me...

Well, by now you know where this is going.

This morning I was walking past him and he said to me.... I LOVE YOU!

I wasn't at first sure what he said as he didn't shout it, So I asked him, what was that?

He repeated, I love you.

I said thank you son, I love you too!!!

38

Wait for it...

Bammity bam bam BAM!!!

Celebrating every little big thing. Appreciating my 3 favorite words. Loving every minute of every day. Even loving those big red lips this morning knowing he is detoxing...



Our son was quickly slipping away from us. We were lost. This protocol gave us direction and ultimately brought our son back to us. He looks at us with smiling eyes and tells us he loves us. He has a full childhood now. Words could never convey the magnitude of our gratitude for Kerri and all who support her efforts to make a future for our kids. See Gunnar's full testimonial on page 378.

Gracias Madrina Kerri!! I now have an ATEC of 10!

41

We started the DAN protocol when our 10 year old daughter was 18 months old and remained on it for 9 years. Before starting CD, our daughter appeared neurotypical, but she was heavily dependent on supplements and her progress had stagnated for a few years. She had a distended belly, poor growth, severe constipation, anxiety, a touch of OCD, and focus/concentration/fogginess issues.

Her ATEC before starting CD was 24. Just 26 days later, her ATEC is 7. A 17 point drop in 26 days! We haven't even had time to do a parasite protocol or a 72/2 weekend yet! Her belly is much flatter and her anxiety, minor OCD, and focus issues are greatly improved! We're going to keep her on CD and I plan on starting the protocol myself this week. As a friend said, "DAN got her to third base and CD brought her home!"

42

My son just saw me reading this page, and asked what CD Autism was. I told him it was the medicine he's taking. He said, "I think my autism is gone. How do you know someone has it still?" Soon, baby, soon!

Spiro and Peter (9 year old twins)

After years of doing many interventions for our twin boys, and having moderate success at best, we learned about CD. It took about a year before we felt comfortable enough to try it. I can honestly say that, it is the BEST intervention that we've used. We started CDS in mid July 2013. In the 4 short months that we've been using CDS and now CD, we have had more gains in every area, than in the last 6 years of doing so many different treatments. What I love about this protocol, is the simplicity of it, less is more, and that was a huge change in thinking for me.

Just to give you an idea on how well our boys are doing, here are their ATEC scores so far:

Spiro: He was number 100 to recover on the "Healing Train" and the 1st child to recover using CDS.

ATEC prior to starting CDS - 22.

ATEC one month after starting CDS - 16.

ATEC two months after starting CDS - 9.

Peter: He was pre verbal prior to CDS and now uses single words and the odd 2 word combination to communicate. Well on his way to healing.

ATEC prior to starting CDS - 69.

ATEC one month after starting CDS - 55.

ATEC two months after starting CDS - 46.

We finally know, deep in our hearts, that our boys are well on their way towards "true healing". We don't have that stress and anxiety about what the future holds anymore. We finally feel like we can breathe easier, and that day by day, the gains keep coming consistently. The gains stay, and that feels better than anything.

Thank you, to my FB friends who introduced me to MMS and to Kerri Rivera who we have such admiration and respect for. I thank GOD everyday that we were fortunate enough to find out about this treatment. Our boys are coming back to us and their beautiful personalities are emerging. We now look to the future with such HOPE. Kerri, we will forever be grateful to you. xoxoxoxoxoxoxoxoxoxo

Tim Hortons
43

㊹

Whoa... My severe kid walked in the door and wrapped his arms around my neck and gave me a normal hug for the first time in his life (6.5 years). Umm... This is crazy. He wiped his butt for the first time EVER... no prompting, no asking! I wasn't even in the room with him! When I got excited and asked, "Did you wipe???" I swear to GOD... I heard "Yeah, Mom!" Kid's never said a word ever. Could be dreaming, but WOW!!! What a day!!!

Please share your experiences!

Testimonials are one of the best ways to share your experiences with this protocol. Perhaps you learned about it by reading or watching a video testimonial?

If you don't tell us your experiences, we can't share them or take action on issues that need improving or correcting...

Send your testimonials to:

testimonials@cdautism.org

Also, let us know if we are free to publish your testimonial, with or without your name.

More miracles & testimonials starting on page 358.

Chapter 3

Step 1 – The Diet

"Let food be thy medicine and medicine be thy food."
~ Hippocrates

If I could choose the one part of *The Protocol* that would be the single most important piece of the recovery puzzle it would be—*The Diet*. By *The Diet,* I mean the dietary plan that I recommend to all of the families that want to start *The Protocol*. It is a combination of the classic gluten-free, casein-free, and soy-free diet along with the elimination of sugar, corn syrup, coloring, preservatives, and other harmful foods. *The Diet* is the basis for the rest of The Protocol; similar to laying the foundation of a house that the rest of the structure will rest on. Adhering to *The Diet* is critical to the effectiveness of the rest of *The Protocol*.

When a family of a child with autism comes to see me, the first thing they want to know is:

What can I do to help my child?

I always, always start with *The Diet*. In fact, I send them away after that first meeting with hope that they will be able to recover their child, but only if they commit to *The Diet* 100%. I explain to the families that they must think about food the same way their great grandparents thought about food. In generations past, food came directly from the Earth, with little processing. Fruits, vegetables, nuts, and meats were dietary staples for our great grandparents and they should be for our children as well. We must think whole foods and not ~~processed foods~~. There is no point in going from regular junk food to gluten-free/casein-free junk food!

After my first meeting with a family, they leave with the list of permitted foods and I have them email me when they have a week straight with zero exceptions or "errors" in *The Diet*. That is where the parents who are truly hungry for recovery are separated from those who are interested in having someone else "fix" their child for them.

One of two things generally happens during that first week. In the first scenario, I get an email from an ecstatic mother or father saying, "I can barely believe it, Johnny slept through the night for the first time in years," or "Johnny had a normal bowel movement," or "Johnny said two new words yesterday!" That's what I hope for.

The second scenario is... I never hear from the family again. There may have been tantrums, or an adjustment period related to *The Diet* that proved too much for them, and they decided to pursue another avenue. That's not to say that everyone sees a miracle, or that there's no middle ground. Some of the results are less obvious, such as more eye contact or less redness in the face, but generally speaking, we see positive changes. Any change is a good sign. *The Diet* is only the first piece of the puzzle. We must continue from here, layering in interventions until we get the desired, end result.

> Kerri... Bless you! When my son was 3 years old he was prescribed Ritalin®, Risperdol® and Clonazepam... can you believe it? Obviously I never gave them to him, it hurt me to see my child "drugged." 2 days after starting the diet he slept through the night, the sparkle is back in his eyes... I can't wait to start with MMS, I am so happy!!!

Throughout this book "miracles," which are actual emails and forum posts from parents about their children's improvements, have been set in text boxes (like the one above) and placed in the chapters that they accent. Please note that as many of these miracles were collected some time ago the contributors have used the term MMS instead of CD. Due to time constraints it was impossible to request permission from these contributors to change the acronym of MMS to CD in their testimonials. MMS and CD are the same substance. Where the acronym MMS is used please know that chlorine dioxide is the substance being discussed and is responsible for the healing.

Author's note: I'm not against all prescription drugs, especially those necessary to bring about healing. However, I don't condone medicating a child with drugs, masking the symptoms known as autism. So, when I see an email like this, I know we've got a great chance to heal that child because we have a parent who has committed herself to healing her child, and who is excited to see what changes the next tool will bring.

Your child's doctor may not have heard of *The Diet* or may be misinformed of its benefits. The references section at the end of the book lists several studies and articles discussing dietary intervention for ASD's. You can use them as a jumping off point for your own study. If you are consulting with a doctor, it is important to choose someone who is familiar with autism and the recovery of autism.

Many doctors do not have time to study up on what's new in autism recovery and if they have zero recoveries then they are in dire need of overhauling their protocols. Another major problem in the mainstream medical community is gigantic egos. If what we are doing is not working to recover our children, then we need to look at what we are doing and why we are doing it. Let's check our egos, update our protocols, and look at what has worked for families who have recovered their children.

Researchers at the New Jersey Medical School's Autism Center found that "children with autism were more likely to have abnormal immune responses to milk, soy, and wheat than typically developing children," which is published in a chapter of Cutting-Edge Therapies for Autism 2011-2012, by Siri and Lyons.[1] In addition, interest is growing in the study of the link between autism and gastrointestinal (GI) ailments. Siri and Lyons also relate a study by the University of California, Davis Health System, where they found that children with autism born in the 1990s were more likely to have gastrointestinal problems, including constipation, diarrhea, and vomiting than children with autism who were born in the early 1980s.

If your doctor is uninformed, or tells you there is no evidence to prove that *The Diet* will help your child, do the research for yourself since only you are in charge of your child's diet. Heck, why not do *The Diet*? It doesn't cost you any money and it just might help your child heal. Whether he eats cheesy puffs or fruits and vegetables will ultimately come down to you. You are the one with the money in your pocket. The only way to know for sure if your child is going to be one of the individuals who recovers with *The Diet*, is to try. It can take gluten six months or more to be removed from the microvilli or "shag carpeting" of the small intestine. As I mentioned previously, some children have obvious changes in two to three days, but even if your child's evolution is taking a little longer than most, DO NOT GIVE UP! At the writing of this book, I have helped about 5,000 or more families of children with autism; all of the children who have lost their diagnosis, as well as those coming close to recovery, have used varied protocols depending on their symptoms. The one thing that they all—unequivocally—have in common is: ***The Diet*!**

In my opinion, it makes little difference what other interventions you apply to your child if you can't manage *The Diet* 24/7/365. Hyperbarics, chelation, ABA, etc., simply will not have the desired effects if you are still feeding "drugs" (aka garbage foods) to your child.

Why do I say drugs? Because that is what gluten and casein become in the bodies of our children on the spectrum; more specifically, gluteomorphin (also called gliadorphin) and casomorphin, which are similar to morphine. Gluteomorphin and casomorphin are produced in the gut due to improper digestion of peptides (as we will explain more in detail later). In a person with "leaky gut syndrome" (increased intestinal permeability), they are able to leave the intestine and cross the blood-brain barrier where they act exactly like morphine or heroin. Would you purposely give your child street drugs? NO!

Once we have this information and understand the severity of this issue, we have a responsibility to our children to do better. We must take away the foods that are keeping them ill. Invite your family and your child's school to help heal your child's ailing body. Explain that they can no longer give your child these items, and that if they do, it's like giving them a dose of morphine. If it sounds drastic... that's because it is!

Researchers have found an abnormal amount of these undigested peptides (gluteomorphin/casomorphin) in the urine of children with autism, proving their existence in the body. Among others, Dr. Knivsberg and colleagues in Norway have found that urine samples from people with autism, PDD, celiac disease, and schizophrenia contained high amounts of the casomorphin peptide.[2] Similarly, Gliadorphin (gluteomorphin) has been verified by mass spectrometry techniques to be present in unusual quantities in urine samples of children with autism.[3]

Do *The Diet*!

There are still plenty of food options that are permitted. I promise you—your child won't starve! We have included some recipes in Appendix 15 on page 513 to get you started. *The Diet* is absolutely the most important piece of the puzzle. If we can't remove what is directly linked to brain and gut inflammation, as well as immune-allergic reactions to offending foods, it is nearly impossible to heal a child on the spectrum. I have personally never seen a family recover a child without dietary intervention. That's not to say it hasn't happened, but I have never seen or heard of it.

Like I said before, when we started with my son Patrick, his only legal food was homemade French fries. So that's what he ate. Little by little he began to accept more foods. I assure you, the adjustment period will fade and they do eat. Stop the cycle of inflammation and addiction. Only then will your child begin to heal, and once your child starts to feel better he will accept more foods.

In the case of my own son, his acidic diarrhea and sleepless nights stopped the week we started *The Diet*. From that moment on I was hooked, not only on *The Diet*, but also on biomedical treatments for curing autism. I have never looked back. I strongly encourage you to experience *The Diet* for your child, or even as a family. It is an amazing thing.

> I thought the following might encourage some of you who have recently made big dietary changes for your kids and are struggling with all that involves. I put my son on a GF/CF/SF... well, basically, EVERYTHING-free diet when he was 11 months old, following a major vaccine-induced crash. My choice to put him on a diet was criticized by nearly everyone in my life, beginning with his pediatrician who told me I was "just imagining" that he'd regressed and that he "probably wasn't allergic" to what I had taken out; she called a week later with the test results and an apology, and a long list of other things he was allergic to! He's now just a little over seven and doing GREAT. I just delivered a GF/CF muffin to him, and he said, "You know what I love best about you, Mommy? I love that you are so nice to us, and that you always make sure we have food that doesn't make us sick." So, don't feel bad about not giving your kid that ice cream cone when Mr. Softee comes by or not loading their Easter basket up with food dye this weekend. It may take years, but they will see that you loved them enough to NOT give them these things.

Some other tips include the following:

Review Your Child's Supplement List

Vitamin A
Vitamin B
Folic acid
Vitamin C
Vitamin D
Vitamin E
Vitamin K
Minerals

Is your child taking 30+ supplements a day? We will talk more about this throughout the book, but this protocol is geared towards eliminating excesses and not about supplementing deficiencies. It's important to carefully review your child's supplements. In order to maximize the benefits from this protocol consider removing any antioxidants, (they kill CD—more on that in Chapter 5, page 88), calcium, magnesium (which feeds the biofilm), as well as iron and B_{12} (which are favorite foods of parasites). Supplements for increasing speech, reducing seizures, enzymes, and probiotics obviously have their place in individual protocols. B_{12}, while known to feed parasites, has also been known to greatly boost speech in some children. If your child saw benefits in speech from B_{12}, it may be worth keeping in. As always, these are decisions that each family has to make for their child on an individual basis.

If a certain supplement proved beneficial to your child, then don't remove it (the exception being antioxidants and the other aforementioned supplements). The goal of this step is to remove unnecessary supplements as they are most likely feeding parasites and creating "excess noise" in the body. Anything that is not serving a purpose needs to be eliminated.

Keep a Journal

Keep a record of the foods you have removed and those you have added in. Then, take note of the types of reactions you observe: rash, more or less hyper, more or less stimmy (self-stimulatory behavior), sleep patterns, frequency and consistency of bowel movements, tantrums, acceptance of new foods, eye contact, language, etc. Write everything down so that you can follow any relationships or patterns that will allow you to identify when something is working, or when it is not. Record these observations in a notebook because it helps guide us, especially those of us who are stressed, frazzled, and sleep deprived.

Don't Stress About Raw Foods or Perfectly Balanced Meals…Yet!

When you are first transitioning, feed your child whatever legal foods he/she will eat. We are taking baby steps. Once your child is on *The Diet* 100%, you can start adding in new foods, bite by bite, if necessary.

Do the ATEC

Keep track of your progress with the ATEC checklist (see page 447), which you can find at...

www.autism.com/index.php/ind_atec

This is an excellent way to see how you are doing. Every time that you begin a new intervention, it's a good idea to do the ATEC, and then repeat it every three months or so to see how your child is evolving. Sometimes our children are recovering right before our very eyes and we don't even know it. The ATEC can be used to measure the effects of all new interventions, not just *The Diet*.

Using the ATEC is a great way to measure improvement. Many of us are tired, burned out, or don't have the best memory. A formal questionnaire can help us to discern when an intervention is working or not, and it only takes about seven minutes to fill out. See Appendix 4, page 447 for a sample survey and more information about ATEC.

Always Read Labels

Read the label on the back of all packages—not just the one on the front that says "gluten-free." Many times they have sugar, yeast, carrageenan, or other items that are not allowed. We must know what we are putting into our children's bodies. If you can't pronounce it... you don't want to put it into your child. Be careful of hidden offenders like malt, natural flavors, artificial flavors, whey, and numbers (red 40, E-441), etc.

Have a Support System

It doesn't matter whether it is a friend, family member, rescue angel, or neighbor. Have a shoulder to lean on. Autism recovery is a marathon not a sprint, and no one should have to go it alone. There are so many amazing parents out there who have walked this path and are willing to help newbies! As of this writing we have several public forums open, including...

www.cdautism.org

and

www.facebook.com/groups/AutismCD

This is an excellent resource for finding the latest info, protocol changes, and share hope and/or frustration with parents all over the world who are walking the same path. Don't forget to sign up for our newsletter as well by visiting the home page at www.cdautism.org!

Take it One Day at a Time

One day
at a
time

Defeatist thinking will only harm your resolve to help your child "I can't do this for the rest of Johnny's life!" or "How will I get through this year?" are defeatist thoughts. Go hour-by-hour or minute-by-minute, and know there are victories every day in the world of autism. We must draw strength from those victories, even when they aren't our own. Both this book and my website have a section of miracles and testimonials (see Chapter 2, page 19 and Appendix 1, page 357), which are real correspondence I have received from parents describing the advances their children have made as a result of doing *The Protocol.* We receive these miracle emails and forum posts every day, but we had to pick and choose which ones to share in the book. You will also see them sprinkled throughout the chapters of this book. Take some time to read them, know that children are recovering every day, and believe your child can be next. If something doesn't go as planned, wake up the next day and know that, *THIS IS the first day of autism recovery.*

Why Does My Child on the Spectrum Need to Go on a Gluten-Free/Casein-Free/Soy-Free Diet?

As I said before I have never seen a child recover without *The Diet.* The following information comes from *www.gfcfdiet.com* and explains why *The Diet* is so important for people with autism.

Scientific studies have shown the presence of high levels of peptides derived from casein and gluten proteins.[4,5] The digestion process is considered "normal" in terms of protein digestion for most people, as they make smaller particles called peptides that are further broken down into amino acids. However, in people diagnosed with autism it is more difficult to properly digest some of these proteins, thus allowing them to enter the blood directly as peptides. This often happens due to a lack of enzymes that help with the optimal assimilation of food and can be a factor in causing exaggerated bowel permeability (aka, leaky gut syndrome). This results in poor digestion, which facilitates the entry of these harmful proteins directly into the bloodstream, where they can cross the blood-brain barrier.

Leaky gut syndrome has been attributed to many causes including viruses; Candida; gluten, which produces zonulin, a protein thought to cause leaky gut; amongst other things.[6]

Gluten-containing foods may destroy the digestive system if they are consumed excessively or are introduced too early into a child's diet. Wheat is hybridized through artificial processing, resulting in inadequately prepared grains. Casein-containing foods may also destroy the digestive system because they are pasteurized and/or homogenized. These processes may result in damage to the enzymes that break down gluten or casein, thus causing incomplete digestion of these proteins.

Recently, Dr. Andreas Kalcker introduced us to the theory that the inability to properly digest these proteins may stem directly from parasites in the intestinal tract. These parasites may contribute to a leaky gut and thereby play a role in the development of allergies towards gluten, casein, soy, etc.

Gluten is found primarily in wheat, rye, barley, oats, spelt, malt, most breads, cakes, muffins, cereals, flour tortillas, pizzas, pastries, and donuts, etc. Gluten is also found in food starches, semolina, couscous, malt, some vinegars, soy sauce, teriyaki sauce, flavorings, artificial colors, and hydrolyzed vegetable proteins. Casein is contained in milk from cows, sheep, goats and any or their derivatives such as yogurt, butter, ice cream, or cheese. No form of cow's milk may be consumed as it causes inflammation and mucous. Even if the product claims to be lactose free, cream free, or casein free—it is not allowed.

Improperly digested gluten and casein fragments can both enter the bloodstream and cross the blood-brain barrier. Because of their opioid properties, these peptides can react with opiate receptors in the brain to cause effects similar to those of an opiate drug such as heroin or morphine.[7] These opiates are called gluteomorphin (or gliadorphin) and casomorphin, and can react with some parts of the brain, for example, the temporal lobes, which are actively involved in the process of the integration of language and hearing. Interestingly, these are two of the areas most affected by autism.

Besides their effects on the brain, opioid-forbidden foods cause inflammation in the gut and brain. When a child has an allergy to a food—in this case gluten, casein, and/or soy, etc.—as it enters the body the immune system sees it as an invader and reacts by trying to protect the body from the substance.

The first time the body is exposed to a food allergen, the immune system makes antibody-specific immunoglobulin E (IgE) against the allergen. IgE antibodies circulate in the blood and adhere to types of immune cells called mast cells and basophils. Mast cells are found in all body tissues, especially in the nose, throat, lungs, skin, and gastrointestinal tract (GI). Basophils are found in the blood and in tissues that have been swollen due to an allergic reaction.

The next time the body is exposed to the same food allergens, the allergen binds to IgE antibodies that bind to mast cells and basophils. These connections between allergens and antibodies direct the cells to release large amounts of chemicals, one of which are histamines. After the liberation of a histamine by an activated mast cell, the permeability of the vessels near the site increases. Therefore, the blood fluids (including leukocytes, which are also involved in immune response) enter the area causing inflammation. Histamine release also causes the release of cytokines and inflammatory mediators by leukocytes. These chemicals, in turn increase the inflammatory response.

Welcome to The Diet!

Now that we've covered the science behind *The Diet*, it's time to get started. First, make sure you complete an ATEC and save the results so you have a baseline score. Next, prepare a shopping list based on the following allowed items.

Author's Note: Organic products are better but not required.

Permitted Foods List

Proteins:

- Beef
- Chicken
- Eggs
- Fish (small not large size)
- Pork
- Turkey
- No processed meats or cold cuts (hot dogs, bologna, etc.)
- No shellfish (preferably—full of toxins)

Fruits:

- Most fresh fruits are permitted (except citrus, mango, pineapple, kiwi and limit berries).
- Frozen fruit without added cream or sugar.
- NO canned fruit (nothing canned ever).
- Be careful of dried fruit as it may contain sugar.

Author's Notes:

Juice is not permitted on this protocol as it has proven time and time again to annul CD and cost families precious time and money. The amount of fruit necessary to make a glass of juice also causes it to be high in sugars, albeit natural, and they can still affect the immune system. Children on this protocol need to drink water and generally speaking most former juice drinkers transition from drinking flavored beverages to water without much issue. If your child must drink a flavored beverage it would be acceptable to blend and strain or juice one apple, for example, and add it to some water and if you choose you can sweeten it with stevia (SweetLeaf® or KAL® brands are ok).

Fruit should not be consumed after a meal as a dessert due to its rapid digestion. If it is eaten after other more slowly digested foods (i.e. meat, grains, etc.), it can ferment in the stomach, causing bloating, gas, or discomfort. Fruit is best eaten before a meal or separate from meals.

Vegetables:

- All vegetables!!!
- Including French fries, however, not frozen fries or fries from fast food chains; these are often coated in flour.

Author's Note: I don't condone the prolonged use of potatoes, as they convert to sugar in the body. However, it was the only "legal" food my son would eat when we began the GF/CF/SF diet.

Nuts:

- Almonds
- Cashews
- Coconut
- Hazelnuts
- Walnuts
- Plus, they all make great milks!

Grains:

- Amaranth
- Buckwheat
- Corn
- Millet
- Quinoa
- Rice
- Sorghum
- Tapioca
- Xanthan gum

Author's Note: I prefer a grain free diet for autism recovery, especially if your child suffers from "grain brain" (addiction to grains, undesireable behaviors and/or inability to concentrate after eating grains). If your child seems to be addicted to carbs, i.e. fruits and starches, you may want to consider the Ketogenic diet or the Rosedale diet.

Even though these grains are allowed, they can be difficult to break down, and can easily ferment in the intestinal tract due to excessive Candida overgrowth, bacteria, and parasites.

Beans:

- All beans—EXCEPT soy
- Garbanzo
- Lentils
- Navy
- Peanuts

Sweeteners:

- Stevia (This is the best of all the sweeteners, but make sure it does not contain erythritol—a sugar alcohol!)
- Agave syrup
- Honey
- Maple syrup (natural/real—not made from corn syrup)
- Xylitol
- NO piloncillo (unrefined sugar)
- NO sugar

Author's Note: Honey is allowed, however, it can create insulin spikes.

Prohibited Foods List

After working with thousands of families, and conducting independent research, it is my personal opinion that the products on the following list should be avoided if your intention is to heal autism:

- Acetic acid (E260)
- Artificial flavoring
- Artificial sweeteners
- Bouillon cubes
- Bread
- Cacao/Cocoa
- Candy
- Cane sugar
- Carrageenan
- Catsup
- Chocolate milk
- Coloring
- Corn flakes
- Corn syrup
- Cow's milk in any form (even lactose-free milk products)
- Flour tortillas
- Gelatin
- Malt
- Margarine

- Mayonnaise
- Microwave popcorn
- MSG (Monosodium Glutamate)
  (MSG goes by many names—too numerous to mention here. A detailed list is available at www.truthinlabeling.org/hiddensources.html)
- Natural flavoring
- Noodle soup
- Oatmeal (except for Bob's Red Mill GF oats)
- Pasta
- Children´s nutritional shakes
- Play-Doh™
  (Contains gluten—Gluten-Free Dough is available at www.discountschoolsupply.com)
- Preservatives
- Processed meats (hotdogs, ham, sausage, cold cuts)
- Sodas
- Soy/fruit beverages
- Soy milk
- Soy sauce
- Sports drinks
- Sugar
- Yeast

NO Cow's Milk:

- Not casein free
- Not lactose free
- Not organic
- Not raw
- Not evaporated
- No No No cow's milk!
- Sorry, no goat's milk either! It too has casein.
- All cow's milk, regardless of what is removed from it, causes mucous production in the body. This, in turn, provides an ideal environment for pathogens.

If you're thinking that once you go GF/CF/SF + that your child will starve, trust me they won't! The list of foods they eat may get shorter, but they will keep eating. As I mentioned earlier, my son Patrick ate homemade French fries for the first three weeks of *The Diet* until he began accepting different fruits, nuts, and chicken again, but we did it... we transitioned. What I have seen in my own son, and in other children, is that when they begin to get healthier in the weeks and months after starting *The Diet*, they become more open to accepting new "legal" foods.

Wow... quite amazing Kerri...

I have always believed that "you are what you eat" and have been very careful with what I give to my kids, so their diet has been quite healthy, except for the occasional ice cream, etc. My son even spits out candies when someone offers him one because he really doesn't like them. He is not into sweets at all, thank God.

But I must say this diet is just what he needed! Yay!

There are a few loopholes to the above list. If you make your own catsup, mayonnaise, etc. with items from the permitted foods list, then your child can obviously eat those foods. The list refers to those items that come from the grocery store that contain white sugar, preservatives, and other problematic ingredients.

There are many items on the forbidden foods list that don't contain gluten, casein, or soy. Here is the explanation behind a few of those items:

White refined sugar: Refined sugar has been found to reduce immune system function as well as contribute directly to obesity and Type II diabetes.

The following list is excerpted from *Suicide by Sugar.*[8]

- Sugar can suppress your immune system.
- Sugar upsets the mineral relationships in the body.
- Sugar can cause juvenile delinquency in children.
- Sugar eaten during pregnancy and lactation can influence muscle force production in offspring, which can affect an individual's ability to exercise.
- Sugar can cause hyperactivity, anxiety, inability to concentrate and crankiness in children.

MSG: An excitotoxin that can literally "excite neurons to death." We need all of our neurons!

Yeast: Feeds Candida and other fungi.

Carrageenan: Contributes to inflammation in the body and studies have linked it to colon cancer in rats.[9]

Artificial sweeteners containing sucralose: In making sucralose, the chlorine in the sweetener bonds to carbon, producing a chemical known as a chlorocarbon. "According to physician and biochemist, Dr. James Bowen, chlorocarbons are never nutritionally compatible with our metabolic processes and are wholly incompatible with normal human metabolic functioning."[10]

Processed Meats (hot dogs, ham, cold cuts, and sausages): The fats found in these meats may contain high amounts of toxins such as heavy metals, pesticides, and herbicides. In addition, processed meats contain sodium nitrite, which can harm the liver and pancreas. They may also contain corn syrup and flavoring.

Natural Flavoring: The exact definition of natural flavorings & flavors from Title 21, Section 101, part 22 of the Code of Federal Regulations is as follows:

> *The term natural flavor or natural flavoring means the essential oil, oleoresin, essence or extractive, protein hydrolysate, distillate, or any product of roasting, heating or enzymolysis, which contains the flavoring constituents derived from a spice, fruit or fruit juice, vegetable or vegetable juice, edible yeast, herb, bark, bud, root, leaf or similar plant material, meat, seafood, poultry, eggs, dairy products, or fermentation products thereof, whose significant function in food is flavoring rather than nutritional.*[11]

Basically if you start with a natural ingredient, you can process or manipulate it any way you choose. No matter how many chemicals or solvents are added it will be labeled as a "natural flavor."

Notice they can come from meat, seafood, dairy, and wheat, etc., can also contain MSG.

Coloring: Food dyes have been linked to allergic reactions, hyperactivity in children, and even cancer. Red No. 2, for example, was banned in 1976 after it was suspected to be carcinogenic. Red No. 40, in a number of tests, was shown to damage DNA in mice.

When we are dealing with children on the spectrum, their immune systems are already compromised, and their detox pathways can be blocked or impaired. The idea is to decrease their burden with life-giving, nutritious foods, rather than add more stress to a body that is already maxed out.

Corn Syrup/High Fructose Corn Syrup: Simply because corn is a permitted food does not mean corn syrup/HFCS are "legal." Both of these shut down the immune system, as refined sugar does. They are chemically similar in composition. There is much controversy surrounding the use of mercury in the refining process, and how much if any, is in the final product.[12]

> I wanted to update you on everything with my daughter.
>
> We had a mishap 2 days ago. A substitute teacher gave my daughter a regular granola bar and a flavored beverage containing sucralose. You know what Kerri, when she came home from school that day she was in her own world and was ignoring me. I knew right away she had something she shouldn't have had. I was angry and saddened by what I was witnessing. Is there anything we should do since she had those 2 items that she's not supposed to have. Or just continue to move forward??
>
> After a while on the diet it becomes obvious when an infraction happens, if you are present when it happens you can give an enzyme to help break down the food, if not, we move forward and learn how to prevent it from happening in the future.

Common Errors:

"It's no big deal if we break the diet every once in a while."

Not True! Every time you break the diet, further inflammation is caused in the brain and gut. When gluten and casein proteins are not properly broken down, the resulting peptides reach the brain as gluteomorphin and casomorphin. It takes three days for casein to be eliminated by the body, but months for gluten to be eliminated by the body.

"My child can drink milk as long as it doesn't have casein."

Not True! As long as the milk comes from a cow, your child cannot drink it. It doesn't matter how it's labeled. If it comes from a cow it's off limits. Cow's milk can provoke the body to produce mucous, thus providing an ideal environment for pathogens which can cause chronic inflammation.

"The allergy panel says my child isn't allergic to gluten or casein, therefore he can eat them."

Not True! If your child has autism, or is on the spectrum, he must avoid gluten, casein, and soy. You should also observe your child carefully after adding a new food, or a food he hasn't eaten in a while. In one particular case, even though the child didn't test positive for an orange allergy he continued to produce symptoms of an allergic reaction whenever he ate one. We must remember that the body is changing constantly and that any test is only good for a couple of months, if at all.

I have seen the same story repeated over and over again with mangoes, oranges, bananas, apples, and corn, etc. Observing the conduct of your child after consuming a food you suspect he may have an allergy/intolerance to is the best way to measure whether the food is acceptable or not. As our children move towards healing, foods that at one point produced allergy-type symptoms can be tolerated without an immune system response.

"My doctor says that autism has no cure, and that the diet doesn't work."

Not True! Run from any doctor who says he will take your money even though he feels that autism is incurable. The first question you need to ask a doctor is:

"How many children have your recovered from autism?"

If the answer is zero, keep looking!

The Diet is free—no one earns money if your child is on *The Diet*—so do it! You have nothing to lose, and everything to gain. However, if you choose not to do it, you may further lose the health or your child. Commit 100% to *The Protocol*, and your child may be one of the next recovery stories.

> My son had what can only be described as a miraculous reaction to the GF/CF/SF diet. Since starting 2 weeks ago, all the bumpy red areas on his face disappeared, tantrums went from about a 10 to a 2, and diarrhea is all but gone.

"We tried the diet, but Johnny didn't get any better."

***The Diet* is only one piece of the puzzle.** However, it is the foundation of everything we are going to do. Without maintaining *The Diet*, it is difficult to know which intervention is actually helping.

Candida will be dying and a reaction to *The Diet* may be a Herxheimer. We must go beyond the diet to heal autism, but diet is the first piece of the recovery process.

When I receive an email complaining that a child isn't getting better I ask for a detailed list of exactly what the child is eating. I always find errors in parents' application of the GF/CF/SF + diet. What I typically uncover is that *The Diet* did not fail but that the application was flawed.

"I should remove gluten and casein from my child's diet gradually."

Not True!!! Remove them from the diet immediately and watch your child improve before your very eyes. Foods that cause IgG or IgE allergic reactions cause many other problems in the body including inflammation and psychotic behaviors, in response to gluteomorphin and casomorphin. The sooner you can remove these foods the faster your child will recover.

> As soon as we started working on the diet, my son received a developmental evaluation, although he was 20 months old, the results were that of a child of 15 months. 4 months after implementing the diet, the changes have been dramatic. My boy smiles again, he speaks in his own way, he points, has eye contact, interacts with others, he is very close to being recovered, although he is still missing a little bit. He is occasionally nervous and sometimes distant, but the most important thing is that the therapist reapplied the developmental test and my son is now reacting like a child of 24 months (his current age), even in some areas surpassing it! And this is only with the diet because he hasn't taken any supplements, just a probiotic that was ineffective.

"A gluten-free/casein-free/soy-free diet is good enough."

It's Not! Like I said before, I always find errors when a parent goes step-by-step with me through their child's diet. The list on page 52 is a detailed list of what our children should not eat under any circumstances. Many of these foods contain neurotoxins/excitotoxins. These foods can negatively affect developing and mature nerve tissue. Keep them out of your child's diet.

Beyond GF/CF/SF +

Sometimes, *The Diet* as explained is not enough and we need to go beyond it. If your child suffers from constipation, diarrhea, or seizures it is recommended to do a period on the Specific Carbohydrate Diet™ (SCD™). The following text was sourced from the website...

www.breakingtheviciouscycle.info

...by Elaine Gottschall. A complete list of references is also available at that website.

The Specific Carbohydrate Diet™ has helped many thousands of people with various forms of bowel disease and other ailments vastly improve their quality of life. In many cases people consider themselves cured. It is a diet intended mainly for Crohn's disease, ulcerative colitis, celiac disease, diverticulitis, cystic fibrosis and chronic diarrhea. However it is a very healthy, balanced and safe diet that has health benefits for everyone. The foods that are allowed on the Specific Carbohydrate Diet™ are based on the chemical structure of these foods. Carbohydrates are classified by their molecular structure.

The allowed carbohydrates are monosaccharides and have a single molecule structure that allow them to be easily absorbed by the intestine wall. Complex carbohydrates which are disaccharides (double molecules) and polysaccharides (chain molecules) are not allowed. Complex carbohydrates that are not easily digested feed harmful bacteria in our intestines causing them to overgrow producing by products and inflaming the intestine wall. The diet works by starving out these bacteria and restoring the balance of bacteria in our gut.

Autism & GI Problems

Altered intestinal permeability was found in 43% of autistic patients, but not found in any of the controls (Harvard University). Intestinal permeability, commonly called "leaky gut", means that there are larger than normal spaces present between the cells of the gut wall. When these large spaces exist in the small intestine, it allows undigested food and other toxins to enter the blood stream. When incompletely broken down foods enter the body, the immune system mounts an attack against the "foreigner" resulting in food allergies and sensitivities. The release of antibodies triggers inflammatory reactions when the foods are eaten again. The chronic inflammation lowers IgA levels. Sufficient levels of IgA are needed to protect the intestinal tract from clostridia and yeast. The decreasing IgA levels allow for even further microbe proliferation in the intestinal tract. Vitamin and mineral deficiencies are also found due to the leaky gut problem.

In a healthy intestinal tract the small intestine and stomach are not inhabited by bacteria. When the flora balance in the colon is lost, the microbes can migrate into the small intestine and stomach, which hampers digestion. The microbes compete for nutrients and their waste products overrun the intestinal tract. One of the toxins produced by yeast is actually an enzyme that allows the yeast to bore into the intestinal wall. The yeast also produce other toxins such as organic acids, which can also damage the intestinal wall.

Bacterial growth in the small intestine destroys enzymes on the intestinal cell surface, which prevents carbohydrate digestion and absorption.

The last stage of carbohydrate digestion takes place at the minute projections called microvilli. Complex carbohydrates that have been broken down by the enzymes embedded in the microvilli can be absorbed properly and enter the blood stream. But when the microvilli are damaged, the last stage of digestion cannot take place. At this point only monosaccharides can be absorbed because of their single molecule structure.

In the small intestine, the body should absorb the nutrients needed from what is eaten. But in the case of malabsorption, the undigested carbohydrates left in the small intestine cause the body to draw water into the intestinal tract. This pushes the undigested carbohydrates into the colon where the microbes can feast on it. This allows for even more proliferation of the unwanted microbes and continued increase in malabsorption problems.

Low intestinal carbohydrate digestive enzyme activity was found in 43% of patients with autism. (Horvath) Recent studies point out that ongoing carbohydrate malabsorption keeps the digestive system constantly weakened, leading to systemic disorders. Suspected carbohydrate malabsorption should be treated to ward off further damage to the body's digestive system. (GSDL)

Most intestinal microbes require carbohydrates for energy. The Specific Carbohydrate Diet™ limits the availability of carbohydrates. By depriving these microbes of their food source, they gradually decrease in number. As the number of microbes decreases so do the toxic by-products they create.

The Specific Carbohydrate Diet™ (SCD™) is intended to stop the vicious cycle of malabsorption and microbe overgrowth by removing the source of energy from the microbes. The SCD™ allows simple monosaccharides that do not need to be broken down in order to be absorbed.

By following the SCD™, malabsorption is replaced with proper absorption. Inflammation is decreased and the immune system can return to normal. Once the immune system is returned to adequate levels, it can begin to keep in the intestines microbes in proper balance.

The SCD™ allows simple carbohydrates, but prohibits complex carbohydrates. The diet is started by following an introductory diet, which consists of a limited selection of foods. After the introductory diet, the next stage of the diet allows many more foods, but requires that all fruits and vegetables be peeled, seeded and cooked in order to make them more easily digested. Raw fruits, vegetables, nuts and seeds are added to the diet later. To properly follow this diet, it is imperative to read Breaking the

> *Vicious Cycle by Elaine Gottschall. The book details the progression of allowed foods as well as providing many delicious recipes.*[13, 14]

Salicylates/Phenols

Phenol is a naturally occurring chemical found in many of the foods we eat, such as fruits and vegetables, nuts, and in bioflavonoids and cartenoids (carotene, lutein, lycopene, xanthophylls, and zeaxanthin), etc. Phenols can be found in toothpaste, hair dye, and disinfectants, etc. Many foods have phenols, and they are impossible to avoid completely. Salicylates are a subgroup of phenols, related to aspirin. There are several kinds of salicylate, which plants make as a natural pesticide to protect themselves from insects, fungi, and harmful bacteria. Foods high in natural salicylates are tomatoes, apples, peanuts, oranges, cocoa (chocolate), red grapes, coffee, all berries, and peppers, to name a few.

You may also need to consider a low salicylate and/or phenol diet, as many children on the spectrum may have issues with these items. The following was sourced from *www.scdlifestyle.com*.

> *Dr. Feingold is probably the most widely known individual to study this chemical, as he developed what is now referred to as the Feingold Diet. He started out in the 1960s as a pediatrician and allergist studying children's negative reactions to aspirin. Through his work, he found that many other dietary chemicals were causing physical and even behavioral reactions in his patients. He developed the Feingold Diet to eliminate all food additives, colorings, and salicylates.*
>
> ### ***Why Do People React to Them?***
>
> *In a normal body that has the correct levels of sulphates and liver enzymes, phenols and salicylates are easily metabolized. The body utilizes what it needs from the chemicals and properly disposes of the rest through the bowels. In those whose levels are not normal or in the case of "leaky gut syndrome", intolerance to this chemical family can occur rather quickly.*
>
> *Many people with gut issues such as yeast/bacteria overgrowth or digestive diseases can develop salicylate intolerance as a result of "leaky gut" syndrome. Leaky gut is a result of various digestive problems and occurs when the small intestine becomes too damaged to properly filter the size and types of food particles or chemicals that enter the bloodstream. [For more on leaky gut syndrome see http://scdlifestyle.com/2010/03/the-scd-diet-and-leaky-gut-syndrome/] When these improper particles are allowed to repeatedly enter the bloodstream the*

body tries to get rid of them by triggering an immune system response. Because phenols/salicylates are so common in most foods, a person with a leaky gut will have much higher than normal levels of these chemicals in their blood and can very quickly develop intolerance´s to these specific particles.

Why Can Phenols Affect Children on the Autism Spectrum More Than Others?

Research by Dr. Rosemary Waring at the University of Birmingham found that children on the autism Spectrum have low levels of the enzyme phenol-sulfotransferase-P (the enzyme that breaks down the phenol and amine families, also known as PST) and the substrate it uses: sulfates. Sulfates are a key tool that the body uses in the process of detoxification and break down phenols such as salicylates. Without normal levels of sulfates in the body, the sulfotransferase enzyme cannot do the task it was created to do: metabolize salicylates. So there are two problems with PST deficiency: low sulfate levels and low enzyme levels. PST deficiency alone can cause problems in children (remember phenols are normal) but factor in any intestinal damage resulting in leaky gut along with it and your child's body can easily be overwhelmed. The end result is a salicylate intolerance and the subsequent physical and behavioral reactions that come with it.

Reactions Caused by Phenols

Salicylates stimulate the central nervous system in people that react to them. This can often bring with it an emotionally extreme high followed by a very low, low. Other reactions to the phenol family can occur anywhere from immediately after consumption up to 48 hours after the consumption of the chemical, depending on the immune response. Physical reactions can include: dark circles under the eyes, red face/ears, diarrhea, headache, difficulty falling asleep at night, night waking, and in some cases excessively tired and lethargic. Behavioral symptoms of a reaction can be: hyperactivity, aggression, head banging or other self-injury, and even inappropriate laughter. Hyperactivity is more common in children's reactions, while adults generally experience symptoms similar to chronic fatigue.[15]

For additional information on leaky gut syndrome you may wish to look at (search for) *Dr. Peter Osborne*:

www.glutenfreesociety.org

If your child suffers from self-injurious behaviors limit these foods that are moderate to high in phenols:

- Almonds
- Apples
- Avocados
- Bananas
- Cacao
- Cantaloupes
- Cherries
- Cider vinegar
- Coconut oil
- Colored fruits
- Dates
- Food coloring
- Honey
- Mangos
- Mint
- Oranges
- Oregano
- Peanuts
- Pineapples
- Powdered chili pepper
- Processed meats
- Raisins
- Strawberries
- Tangerines
- Tomatoes

For more information on this you can visit:

www.scdlifestyle.com

and

www.feingold.org

* * *

She's quite the book worm and has an impressive collection which includes classic favorites such as Brown Bear, Llama Llama Red Pajama, Barnyard Banter and Goodnight Moon... But lately, she has been drawn to her Mama's new favorite read... Perhaps she is hoping that someday her story of recovery will be told too...

Gluten Syndrome

For many parents of children on the spectrum, having their children on *The Diet* is something that is second nature to them. However, as more and more people are using the protocol in this book to heal their own health ailments we have decided to include the following section on how gluten can negatively affect many more than just the autism community. You will get a very interesting look into how the immune system works and why so many sufferers have misunderstood gluten syndrome. Thank you Olive for contributing to our understanding of the subject.

Molecular Mimicry

What It Is & How It Relates to the Gluten Syndrome

by Mrs. Olive Kaiser

Who am I?

I am a married stay at home mom, blessed with a wonderful husband and seven fantastic kids. In 2003, after decades of searching, we learned about gluten reactivity through our daughter's nursing school training and eventually confirmed that we are a gluten syndrome family. Our daughter and my husband had the most obvious symptoms, but we all had manifestations and antibodies. Additionally our oldest son reacted to his MMR vaccination and probably other shots, which added high functioning ASD/ADD to the mix, and he developed type 1 diabetes at age 19. Two other sons had various shades of ADD/ADHD. My own school age vaccinations in the 1950's may have led to repeated bouts of strep throat until I reacted to a strep antibiotic injection about age 10. I developed PANDAS from that reaction (Pediatric Autoimmune Neuropsychiatric Disorder Associated with Streptococcus). What a struggle! Decades later it has responded somewhat to diet changes and now the CD/parasite protocol. I give thanks to God for His guidance along the way.

How did I get into this community and this health project?

We tested for gluten syndrome (we called it celiac disease back then) using standard tests recommended by celiac experts and received confusing results. Then, our daughter had a troubling experience with a gluten challenge that did not match the celiac story we'd been taught. I delved into medical literature and networked extensively with the gluten syndrome community looking for help. In that desperate discovery and prayer process I found practitioners and researchers who stepped outside the "villi damaged celiac only" box. They were able to explain why we received, in the midst of obviously gluten-induced incidents, false negative results from our celiac blood tests and villi biopsy. Those tests significantly led us astray and eventually I put up a website...

www.TheGlutenSyndrome.net

...to warn others of discrepancies we stumbled upon in the diagnostic process.

What is Molecular Mimicry?

Molecular mimicry is a recognized medical theory which explains very nicely why gluten reactions may potentially inflame and damage so many different parts of the body, leading to very different symptoms in different people. It also clarifies why gluten antibodies may cross react with other foods and infections, and why it only takes a small exposure to trigger them.

When we understand molecular mimicry we are better equipped to deal with tempting social situations. Gluten syndrome has its own rules, which do NOT make sense unless this concept is understood.

The following is a brief introduction to Appendix 5, page 449, which goes into much more detail, along with references, about the following questions:

1. How does the gluten syndrome reaction actually damage our bodies?

> Molecular mimicry. The molecular structure of gluten resembles the molecular structure of many of our body tissues. When the immune system attacks gluten it may also attack body tissues that "look like" gluten. Even if you do not read the other detailed answers, learn the details for this question on page 450.

2. Does gluten always damage the villi of the small intestine as the celiac story teaches? Many other tissues such as thyroid, pancreas, liver, joint, brain, nerves, heart, bone, blood vessel walls, etc., are involved in this disorder. Does all that other damage only arise from poor nutrient absorption from injured gut villi?

> No, according to published research, many researchers and practitioners believe the villi are not always damaged in an autoimmune gluten reaction. Where there is no villi damage, injury to other organs CANNOT be due to nutrient deficiencies caused by villi damage. Molecular mimicry provides a mechanism for direct autoimmune gluten damage to many other tissues and organs when the villi are fine, OR other tissues/organs, *including villi*, may be directly damaged through molecular mimicry.

Dr. Vojdani's abstract in his editorial *The Immunology of Gluten Sensitivity Beyond the Intestinal Tract*, supports that the villi are not always injured. To quote his editorial abstract, "Evidence has been accumulated in literature demonstrating that gluten sensitivity or celiac disease can exist even in the absence of enteropathy [gut/villi damage], but affecting many organs."

3. I don't have damaged villi, and my tTG/gliadin tests were negative, but I feel so much better gluten-free. Why?

The tests were likely false negative. That is very common. As gluten digests, it breaks into more pieces than we have tests developed to check them, and the immune system makes a separate antibody for each piece. Standard tests only check 2-3 antibodies. You may have others (Cyrex Labs tests 28 antibodies). Your villi may be fine, but you may be injured somewhere else—for example: thyroid, nerves, heart, etc.

4. Why do many gluten syndrome patients not only react to wheat, barley, and rye but also at times to other foods, particularly oats, milk, corn, soy, egg, yeast, coffee, sesame, rice, chocolate and others?

These foods "look like" gluten closely enough in their structure that the immune system may mistake them for gluten. This situation may also cause your gluten antibodies to run high after you go gluten-free. The immune system may misrecognize other foods, such as yeast, corn or milk, and others for gluten because they resemble gluten molecularly.

5. The diet seems excessively strict? Why does it take so little gluten to start a reaction?

Our perspectives are skewed. We accept that miniscule amounts of venom injected by a bee sting, or a tiny exposure to peanuts in allergic individuals can set off immediate life threatening allergic reactions. Many medications are contained in very TINY pills, but they have powerful effects in our bodies. Immune gluten reactions are also that sensitive. "Crumbs matter."

6. Why do many people react to gluten, proven by antibody tests, but they have few or no warning symptoms for a long time and then they crash with something serious, usually autoimmune?

Gluten is famous for slowly injuring nerves by molecular mimicry, and in many cases, the nerves are silenced by that injury. The patient does not realize there is a problem until the tissue or organ that those nerves supply begins to fail.

7. Why do so many of us react to gluten today, when for centuries most people appeared to be fine with wheat, barley, rye and oats? After all, wheat and barley are mentioned positively in the Bible and other historical documents.

Today's gluten is altered, violently, by nuclear radiation and chemical mutation within the past 60 years*, plus our toxic and poorly nourished bodies do not have optimal digestive capabilities to break it down. Weak, toxic, leaky body barriers/membranes, particularly leaky gut, set the stage for gluten induced molecular mimicry.

*Nina Federoff, *Mendel in the Kitchen*

8. Why do specialists and researchers insist that the gluten-free diet must be life long? Can't we heal this problem and go back to our beloved wheat bagels, croissants, and brownies?

Our scientists still insist that gluten-free is a strict lifelong commitment. I agree. For me it is not worth playing with today's wheat. There is something strange and unpredictable about it. The memory B cells in the immune system never forget what the enemy "looks like", and fresh exposure retriggers antibodies.

9. Traditional peoples soaked and/or sprouted their wheat berries and then made sourdough bread with them. Does that process alter the gluten sufficiently for gluten syndrome patients to safely consume this bread, particularly spelt or einkorn?

No. These processes and ancient wheat grains do make the bread more digestible, but not gluten-free and still unsafe.

10. Should I substitute all the gluten foods I routinely eat with gluten-free substitutes?

No, not routinely. The gluten-free community finds that they are still mainly expensive high carb processed food (i.e., junk food).

11. What are gluten withdrawals?

Occasionally, gluten breaks into specific "pieces" in the gut that resemble opiate drugs. When a person goes gluten-free, they may experience temporary, but unpleasant, withdrawal symptoms for a few days as these pieces disappear from the blood stream.

12. What are the risks of formal gluten challenges?

Many patients avoid these challenges. Occasionally a patient tries the gluten-free diet for an extended period of time and then the patient or doctor decides to run tests to confirm gluten reactivity. The standard advice to restart the production of antibodies is to consume gluten products 4 x per day for 4-6 weeks, and then run the standard blood test, followed by a villi biopsy if the blood work is positive. This is called a gluten challenge and has created some very dramatically unhappy reactions, some of them neurological/psychological.

Please see Appendix 5 (page 449) and www.GlutenSyndrome.net for more info and references. When we understand molecular mimicry our understanding of the gluten syndrome comes into focus. It explains why gluten-free diets and beyond are important tools to reduce inflammation and promote healing. As time goes on, gluten-free diets are easier to manage in public, tests are better and social awareness has grown. The Just Eat Real Food movement and others play into healthy gluten-free dining with wonderful recipes that avoid processed foods and incorporate healthy fats and nutrient density. This is a happy, encouraging era as we watch our children heal and adults find better stability in the midst of a health crisis. Bon Appetit!!!

* * *

The Diet - FAQs

The following FAQ's were printed with permission from gfcfdiet.com:

Slight changes were made to match the formatting of this book; however, the content remains unaltered. Please visit gfcfdiet.com for complete list of the references contained within the following text.

1. My doctor has never heard of any of this and she is extremely skeptical. I'm embarrassed to tell her I'm considering this approach. What do you think?

Skepticism is a good thing in a medical doctor or scientist. However, since there is preliminary evidence to support this safe, non-invasive intervention, it is up to you to educate her, state your wishes, and ask for her support. For a doctor, it is better to wait until all of the data is published in peer-reviewed journals before advocating a treatment. However, for a parent, it is reasonable to want to help one's child without waiting for all of the results of the "double-blind placebo" studies. Because this approach does not include any unusual supplements, invasive drugs, or expensive treatments, your pediatrician should be supportive. Explain that you would like to try this for a few weeks, and agree that you will be objective about recording your child's progress while on the diet.

If you feel that you need to support your case legally with the scientific and medical documentation that is currently available, please see the medical links at www.gfcfdiet.com or at www.autismndi.com.

2. What is casomorphin?

Casomorphin (or caseomorphin) is a peptide derived from casein, a milk protein. Casein is one of the major proteins in the milk of all mammals including cows, goats, and humans. When casein is digested properly, it breaks down into large peptides like casomorphin, and should then be broken down further into smaller amino acids.

However, Dr. Reichelt in Norway, Dr. Cade at the University of Florida, and others found that urine samples from people with autism, PDD, celiac disease, and schizophrenia contained high amounts of the casomorphin peptide in the urine.[4] In its peptide form, casein has opiate properties similar to morphine, and may plug into the same opiate receptor sites in the brain. Researchers have found that these peptides may also be elevated in other disorders such as chronic fatigue, fibromyalgia, and depression based on anecdotal reports of symptom remission after exclusion of wheat and dairy.

3. What is gliadorphin?

Gliadorphin (also called alpha-gliadin or gluteomorphin) is a substance that resembles morphine. Ordinarily, this is a short-lived by-product from the digestion of gluten molecules (found in wheat, barley, rye, oats, and several other grains). Gliadorphin is very similar to casomorphin. Gliadorphin has been verified by mass spectrometry techniques to be present in unusual quantities in urine samples of children with autism, and are believed by many to be a central part of the system of causes and effects that cause autistic development.

The most probable reasons for the presence of these molecules are:

- One or more errors in the breakdown (digestion) process caused by enzyme deficiency and/or
- Abnormal permeability of the gut wall (that would allow these relatively large molecules to enter the bloodstream from the intestine in abnormal quantities).

4. I am confused about allergy vs. intolerance. I understand that our children may be sensitive to corn, soy, and other foods as well as gluten and casein. Does this mean that they will eventually start turning these foods into the morphine-like compounds too? If this were the case, would they show up as an allergy on a RAST test? Or were our children always allergic to these foods (a regular allergy

that may cause behavioral changes in our children), and we just didn't know because the gluten and casein were hiding the allergy?

To a traditional physician or allergist, "allergy" is used to describe a reaction of the IgE part of the immune system, resulting in hives, swelling, or breathing problems. However, the words "allergy" and "intolerance" are often used to describe any inappropriate reaction to foods or substances that should normally be harmless to the body.

There are at least three different ways that a child with autism may have a problem with foods that contain gluten or casein, and it's important to understand the distinction:

1. An IgE ALLERGY commonly results in skin problems, hives, swelling, and breathing problems, etc. This can be tested using a skin test or blood test.

2. An INTOLERANCE (usually mediated by the IgG or IgA part of the immune system, or by an enzyme insufficiency such as lactose intolerance) has more varied or vague symptoms like discomfort, stomach problems, sleep problems, joint pain, ear infections, or hyperactivity and behavior problems. Sensitivity to these substances can be tested with an ELISA blood test.

3. PEPTIDUREA (peptides in the urine) is caused by the inability of the body to properly break down certain proteins. It is hypothesized that certain peptides, notably from milk and wheat proteins, are plugging into the opiate receptor sites of the brain and disrupting brain and nervous system function. Urine testing for this is still experimental, and many parents believe that the best way to find out if this is what is causing a child's autism is a strict trial period on the GF/CF diet.

On the GF/CF diet, gluten and casein are avoided because they are strongly suspected of having a direct pharmacological effect. When these proteins are only partly broken down, some of the resulting fragments can be strikingly similar to morphine, and act in more or less the same manner. (This type of reaction can co-exist along with a classic type of allergy towards the same foods.)

Recent research indicates that protein from both corn and soy may also contain some molecular sequences that could, if the patient has an enzyme deficiency, be broken down into something closely resembling opioid peptides. Even spinach protein has been found to have some opioid activity.

Products made from soy or corn will also often contain metabolic end products made by microscopic organisms like bacteria, molds, or other fungi. Some of these are suspected of being harmful to a small number of people who are genetically predisposed to autism. The amount of danger will depend on individual conditions AND on the quality of the corn or soybeans used in the production process. Soy OIL (lecithin) may be worse than most other soy products since this product will look and taste okay, even when made from moldy raw material, and since it is commonly made from the "bottom grade" of the harvest.

Some people also think that one of the natural pigments in corn (lutein) may cause problems for reasons that are not properly understood (see: "Sara's Diet"). This must be regarded as highly speculative.

5. I don't think my child has allergies, or that allergies could cause autism. Why should I try removing foods from his diet?

Although parents have been reporting a connection between autism and diet for decades, there is now a growing body of research that shows that certain foods seem to be affecting the developing brains of some children and causing autistic behaviors. This is not because of allergies, but because many of these children are unable to properly break down certain proteins.

6. Milk and wheat are the only two foods my child will eat. His diet is completely comprised of milk, cheese, cereal, pasta, and bread. If I take these away, I'm afraid he'll starve.

There may be a good reason your child "self-limits" to these foods. Opiates, like opium, are highly addictive. If this "opiate excess" explanation applies to your child, then he is actually addicted to those foods that contain the offending proteins. Although it seems as if your child will starve, if you take those foods away, many parents report that after an initial "withdrawal" reaction, their children become much more willing to eat other foods. After a few weeks, most children surprise their parents by further broadening their diets.

7. Isn't milk necessary for children's health?

Americans have been raised to believe that this is true, largely due to the efforts of the American Dairy Association, and many parents seem to believe that it is their duty to feed their children as much milk as possible. However, lots of perfectly healthy children do very well without it. It is calcium children need, not milk. Cow's milk has been called "the world's most overrated nutrient" and "fit only for baby cows." There is even evidence that the cow hormone present in dairy actually blocks the absorption of calcium in humans.

Be careful. Removing dairy means all milk, butter, cheese, cream cheese, and sour cream, etc. It also includes product ingredients such as "casein" and "whey," or even words containing the word "casein." Read labels—items like bread and tuna fish often contain milk products. Even soy cheese usually contains caseinate.

For more information on dairy-free living, there's a very good book called *Raising Your Child Without Milk* by Jane Zukin. Another great book called *Don't Drink Your Milk* by Frank Oski (the late head of pediatrics at Johns Hopkins and author of *Essential Pediatrics*). This book cites the results of several research studies that conclude that milk is an inappropriate food for human children. It is available for $4.95 from Park City Press, PO Box 25, Glenwood Landing, NY 11547, ISBN #0671228048.

8. How do I know which foods he's allergic to?

Try an allergy elimination diet. For example, keep common allergens out of his diet for a few days and then re-introduce them, one-by-one. If you see symptoms, either physical or behavioral, try again in a few days. By being systematic you will be more certain of which foods are causing problems and correctly rule them out. Two excellent resources, probably available at your library, are Doris Rapp's book, *Is This Your Child*, and William Crook's, *Solving the Puzzle of Your Hard to Raise Child*.

9. Aren't eggs dairy?

Many years ago, most of us were taught that eggs and dairy were part of the same section of the food pyramid under "dairy." However, they are not. Eggs are free of any dairy. Dairy can be from cows, sheep, or goats. The eggs we eat are normally from chickens. Dairy and eggs happen to be side-by-side in the refrigerator section of the grocery store, which may add to the confusion.

10. What do I do when we go to a party or out to another person's house and are trying to maintain my child on a GF/CF diet? At times we find it impossible to catch him before he ingests something he shouldn't.

It is a good idea to bring some favorite GF/CF goodies with you. Keep them hidden until that moment of "competition." Show the surprise treat to your child before your child eats one of the gluten and/or casein laden foods. Bring more than one goodie to be on the safe side. Also, there are two small pamphlets that are great for handing out to friends and family members that give a simple explanation for your child's special dietary requirements. These are: "Alternative Treatments for Children Within the Autistic Spectrum: Effective, natural solutions for learning disorders, attention deficits, and autistic behaviors," by Deborah Golden Alecson, and "Leaky Gut Syndrome: What to do about a health threat that can cause arthritis, allergies, and a host of other illnesses," by Elizabeth Lipski, M.S., C.C.N. Both of these books cost $3.95 each and can be found at health food stores.

11. Do we need to worry about gluten-containing lotions, shampoos, and toothpaste being absorbed through the skin?

Nicotine patches, birth-control patches, and other transdermal applications of medications are proof that the skin does absorb many things (and pass them to the bloodstream). However, the molecules in gluten are too large to pass through the skin, according to John Zone, MD (a dermatologist quoted in the Spring 2003 issue of *Living Without* magazine).

Most often the problem occurs from hand to mouth (i.e. touching colored modeling dough and then touching one's face), which is a good reason to avoid giving our kids much access to anything that poses a threat. If your child's school has a sensory table, you can request that it be filled with rice or dried beans, instead of macaroni or gluten grains. Likewise, we suggest that you volunteer to be the "Play-Doh™ parent" and keep the classroom supplied with a safe version that you don't have to worry about.

We are not too concerned about shampoo, unless you have a child who is likely to try to drink the stuff. But toothpaste is an entirely different matter, since some of it is likely to be ingested, rather than spit out.

12. I'm already worried about my child's nutrition, and his "allergies" are causing me to further reduce his choices. If apple juice and bananas are the only fruits he will eat, and he's reacting to them, how is he supposed to get by?

Fruit contains water, sugar, fiber, and vitamins. If he will not eat other fruits then he needs to get these things from other sources.

13. I am wondering if anyone else is having problems with school and keeping them on the diet? I have sent a note saying: "Please don't give my son dairy, wheat, corn, or soy." Today I came in and they were giving him Popcorn!

My kid doesn't eat ANYTHING that isn't sent from home. He's almost ten now, and this policy has been good for him because succumbing to temptation outside of the house has simply never been an option. I don't think it would occur to him to take food from anybody without our permission.

We always made sure there are backup snacks and birthday party treats at school for emergencies. I think the school has always taken this seriously because they can see how seriously we take it.

We once got a note from a mom who said that her son had been strictly GF/CF for months without an improvement. I asked what he was eating, and she gave me a long list including expensive GF prepackaged products. Then she ended her letter by saying, "Of course, that's just what he gets at home. I have no idea what he gets in his school lunch, or what they're using for food reinforcers in his ABA program."

Definitely try this—you might see a real difference.

14. What percentage of children will respond to dietary intervention?

DAN! doctors used to try to be conservative about this, and say at least a third of children, and then, after seeing more patients, they said two thirds. Now that they have seen hundreds or thousands of patients, most tell us that they believe that almost every ASD child will benefit from this diet. Many will need further modifications (i.e. removing grains or sugar) before the full benefits are realized.

However, age plays a big part in how quickly results will be seen. We can probably say that the response will be dramatic in more than two thirds of the children under three, and perhaps more subtle, but still helpful, in at least two thirds of older children. We think those are pretty good odds.[3]

Some Additional FAQs...

Kerri, yesterday the therapist was playing with Play-Doh™ with my daughter. She could not resist eating it. We tried very hard to stop her with no luck. In the end we had to stop her from playing with it. People say this is due to a zinc deficiency. Do you know if this is correct? Will giving her Zinc stop her from wanting to eat Play-Doh™? If yes, how much should I give?

She is not eating Play-Doh™ because of a zinc deficiency. Play-Doh™ contains wheat. She is addicted to gluteomorphin, a by-product of her eating gluten, which is contained in Play-Doh™. So, she broke her diet. She cannot touch nor eat Play-Doh™.

What exactly is Candida?

Candida albicans is an opportunistic fungus (or form of yeast) that is the cause of many undesirable symptoms ranging from fatigue and weight gain, to joint pain and gas.

The Candida yeast is a part of the gut flora, a group of microorganisms that live in your mouth and intestine. When the Candida population starts getting out of control it weakens the intestinal wall, penetrating through into the bloodstream and releasing its toxic by-products throughout the body.

What Causes Candida Overgrowth?

Candida is an opportunistic pathogen that can rapidly take over when a person is under a course of antibiotics. Antibiotics destroy beneficial gut flora but have little effect on Candida, giving this normally harmless yeast the chance to take over dominance of the gut environment very quickly.

Babies born via C-section, or to mothers who were treated with IV antibiotics during labor are especially vulnerable to the ravages of Candida overgrowth. This is because they are not exposed to a healthy balance of gut flora on the way through the birth canal prior to the moment of birth.

…disaccharides, or double sugars, are present in many carbohydrates including ALL grains—not just gluten containing ones. An inflamed, imbalanced gut overridden with Candida is unable to digest double sugar molecules completely because the lack of beneficial gut flora has compromised the function of the enterocytes.

According to Dr. Natasha Campbell-McBride MD, author of *Gut and Psychology Syndrome*, and one of the key scientists at the forefront of gut restoration research today, enterocytes are the cells that reside on the villi of the gut wall and produce the enzyme, disaccharidase, which breaks down the disaccharide molecule into easily absorbed monosaccharide molecules. When the enterocytes are not nourished and strengthened properly by adequate beneficial flora, they become weak and diseased and may even turn cancerous. Unnourished, enterocytes cannot perform their duties of digesting and absorbing food properly.[16, 17]

The critical importance of the enterocytes to health cannot be overstated!

Weak and diseased enterocytes also have trouble digesting starch molecules, which are very large molecules that consist of hundreds of monosugars, connected in long branchlike strands. People with weak digestion due to Candida overgrowth and messed up enterocytes have a terrible time digesting these complex molecules leaving large amounts of it undigested—the perfect food for pathogenic yeasts, bacteria, and fungi like Candida to thrive upon. Even the starch that manages to get digested results in molecules of maltose, which is—you guessed it—a disaccharide! This maltose also goes undigested due to a lack of the enzyme disaccharidase and becomes additional food for Candida.

We are a few days into the diet. Can someone comment on what they send to daycare with their kids for snacks? Our daycare is nut free as well. We are ok for lunches but what should we take for snacks. The gluten-free pretzels, etc. we were taking he can't have now because of yeast and soy.

Here a few suggestions: Hard boiled eggs, cut up raw veggies and fruit, air popped popcorn, apples, bananas, dried fruits (with no sugar added). Also you can join "CD/CDS MOMS WHAT IS MY KID EATING TODAY" Facebook group. You can find more ideas there.

Chapter 4

An Introduction to Chlorine Dioxide

by Jim Humble

"Condemnation without investigation is the height of ignorance"

-Albert Einstein

Jim Humble, the man behind chlorine dioxide for healing, was kind enough to write the following introduction to our CD section...

I just can't tell you how pleased and proud I am that Kerri has developed protocols using chlorine dioxide as the main ingredient to bring health and normalcy to many children who had the symptoms called autism. Their resulting healing is one of the greatest stories of this and the last century. Kerri's ability to look at something new and to evaluate the value of the new item without being totally affected by the dictates of present established medical science is truly rare. Kerri decided to do something since modern medicine has yet to come up with a reasonable priced globally available solution to the problem of autism that yielded good results. Medical science says that autism is incurable, that millions of children have to be left to suffer and live without reaching their potential. At this writing 115 children have recovered, hundreds more are near recovery and thousands have had documented improvements as a result of being treated with Kerri's protocol.

Here are some basic points:

Chlorine dioxide (the molecule) was discovered in 1814, with many giving credit to Sir Humphrey Davy for its creation, and today several patents exist for healing various ills with it (see list on page 85).

MMS (Master Mineral Supplement) – I rediscovered chlorine dioxide in 1996 and since then more than 1,020 people have traveled from more than 95 countries to the Dominican Republic, Mexico, and other countries, to be trained in its use. By our estimation, more than 10 million people worldwide have used chlorine dioxide.

The highest cost of a set of bottles of sodium chlorite + activator is less than \$25 for 4 ounces of each. This means that almost any place in the world the average dose of chlorine dioxide is less than 4 cents, or less than \$.40 a day or \$25 for 2 months. In most places it is even less than that. So far there is no one in the world who can't afford it or who wouldn't be able to get it merely by asking if they can't afford it.

The chlorine dioxide molecule is the weakest of all oxidizers used in the human body and thus has very little effect on human cells. This molecule has the unique ability to recognize and oxidize (kill) harmful bacteria. Hans Christian Gram, a scientist of the 19th century, discovered that most harmful bacteria have a negative charge. He was able to dye positive and negative bacteria two different colors. His techniques are still used in laboratories and universities. All oxidizers, including chlorine dioxide, have a positive charge that will attract and kill negatively charged bacteria while repelling positively charged bacteria. Chlorine dioxide is thusly able to kill bad bacteria without destroying the good bacteria. This is simple high school science; like charges repel and unlike charges attract.[1]

Most chemicals and many foods in this society are tested to determine their poison index, which is designated by giving them a toxicity number known as LD_{50}. Sugar, table salt, butter, arsenic, cyanide, vinegar, wine, Clorox, window cleaner, and dozens of other household and industrial chemicals are rated as to their toxicity by force feeding 10 rats with the food or chemical in question until ½ of them die. The amount of chemical or food that it takes to kill 5 of the 10 rats determines the LD_{50} number. Every chemical has a toxic rating and is indicated as an LD_{50} number. All chemicals are toxic in large enough quantities and there are a lot of unlucky rats in our society.

There has never been a recorded death caused by ingestion of chlorine dioxide or sodium chlorite in humans. In the case of chlorine dioxide, it would take 1000 times more chlorine dioxide than is used in a daily treatment dose to reach a toxic dose for a human being. The following information is from the *Toxicological Profile for Chlorine Dioxide and Chlorite* (published by the U.S. Dept., of Health & Human Services) which contains LD_{50} toxic numbers for chlorine dioxide along with documentation that no deaths have been caused by chlorine dioxide (Emphasis in italics is the author's):

> *No information was located regarding death in humans following oral exposure to chlorine dioxide or chlorite. Shi and Xie (1999) indicated that an acute oral* LD_{50} *value (a dose expected to result in death of 50% of the dosed animals) for stable chlorine dioxide was > 10,000 mg/kg in mice.*[2]

I should say something about bleach as a number of critics insist that MMS (chlorine dioxide) is a bleach and thus is a poison. Chlorine dioxide, the chemical that is MMS, has never been used domestically as a bleach for cleaning toilets. It is an industrial bleach when used 4000 times more concentrated than MMS. It is never used for bleaching purposes in the homes of people of this world.

Legally, ethically, morally, and logically, if any item does not have the characteristics of a particular item, it cannot be said to be that kind of an item. This means that a chemical that does not have the characteristics of bleach cannot be called bleach. So a chlorine dioxide solution being 4000 times weaker than that of bleach cannot be called bleach. This is a fact accepted in courts of law of the world.

I sincerely hope you will take the time to understand the basics of chlorine dioxide as explained here. Any time one has helped someone overcome the symptoms of autism he has helped save a life, as those suffering from the symptoms of regressive autism are not living their full lives. The end result of learning this data is that the time may come when you will need chlorine dioxide to save your own life or that of a loved one.

Jim Humble

Archbishop Jim Humble

A message from Kerri to Jim Humble

"With all my love, respect and gratitude. You have swum against the current for so long, and I am so fortunate that you waited for me. I will continue to recover these generations of children that are the victims of a senseless epidemic. As you have done, I will do. We can't change the past, but the future is ours. You have brought light to where there once was none."

Chapter 5

Step 2 – Chlorine Dioxide (CD)

"All truth passes through three stages. First, it is ridiculed. Second, it is violently opposed. Third, it is accepted as being self-evident."
~ Arthur Schopenhauer

CD (chlorine dioxide) is the most amazing intervention that I have ever tried with my son. It by far packed the biggest punch in the shortest amount of time—we saw the positives in under a week with no side effects! (A Herxheimer reaction is not a side effect.) After seven days on CD, my son was looking at me in the eyes and requesting non-preferred activities using four word sentences. I have never, with any other intervention, seen a change in my son come about so quickly, especially since Patrick was your typical non-responder before CD.

The chlorine dioxide molecule (CD).

Why CD for Autism?

We know that the symptoms known as autism are caused by:

- Viruses
- Bacteria
- Candida (yeast)
- Parasites
- Heavy Metals
- Inflammation
- Food allergies

CD catapults children into recovery because it kills these exact things. As of this writing, over three years since we started using CD in our protocol to heal autism, 115 children have lost their diagnosis. Thousands of children around the world are healing, and that means their families are healing as well, and for this I am eternally grateful.

CD has confirmed my faith and has shown me time and time again that autism IS curable. My life has changed since the day my son was able to look me in the eyes, smile, and request things. I could not keep information of this magnitude a secret. I absolutely had to share it with anyone who would listen.

CD is very affordable as you can purchase a two to three month supply from multiple worldwide suppliers on the Internet for around $25USD. The cost difference between the CD Autism Protocol and a megavitamin/supplement based biomedical protocol for a family living without insurance (or in a third world nation) could be the difference between recovering their child and not recovering their child. The results are also vastly different.

You can think of CD as a shortcut to recovery because it kills all pathogens with one shot. Hypothetically, you could use antibiotics, antifungals, and antivirals to get the same results; however, you could also cause damage due to harmful side effects from these products (liver and kidney stress, etc.). Also, antibiotics, antifungals, and antivirals can only target certain bacteria, viruses, and fungi. CD targets all types of pathogens based on their electrical charge and pH. The particular strain is irrelevant.

CD causes no side effects, leaves no toxic residues, and causes no liver damage. It causes no new stress to already stressed bodies. Everything else we use to kill pathogens leaves something behind. For example, antibiotics also kill your beneficial bacteria, and antiviral use comes with contraindications and side effects. CD is gone from the body one hour after your last dose, leaving no trace behind. We dose hourly throughout the day because CD is only active in the body for up to one hour. We must continue to dose if we want to stop the proliferation of pathogens and eliminate them from the body.

A few children with autism in Venezuela recovered using only CD, The Diet, and a probiotic. That doesn't happen every time, but it can.

False Information and the Fear it Creates

The most common reason that families have told me they are afraid of trying CD is because of false propaganda. The FDA, anti-biomed parents, and others have claimed that MMS (Jim Humbles term for a weak concentration of chlorine dioxide in aqueous solution) is a "poison," comparing it to chlorine or chlorine bleach, which it is not.

If you are interested in a deep dive into the science behind chlorine dioxide therapy (also known as MMS), please spend some time on Dr. Andreas Kalcker's websites...

www.medicasalud.com

...mostly in Spanish, though it has a few pertinent documents in English, and...

www.andreaskalcker.com

Also check Jim Humble's website:

www.jimhumble.org

There, you can also find a forum (G2Cforum.org) of people discussing the use of CD (MMS) for the healing of a multitude of ailments.

In a nutshell, chlorine (Cl) and sodium hypochlorite (NaOCl, aka chlorine bleach) are as different from chlorine dioxide (ClO_2) as "required-for-life" oxygen (O_2) and "will-damage-the-lungs" ozone (O_3) are different from each other. Chlorine (Cl) and sodium hypochlorite (NaOCl) destroy pathogens through "chlorination," while chlorine dioxide (ClO_2) destroys pathogens by "oxidation." The by-products of chlorination can bond with other molecules and form potentially carcinogenic trihalomethanes. The only byproducts of oxidation by chlorine dioxide are two neutral oxygen atoms and a chlorite ion, which can bond with sodium in the body to form table salt (NaCl).

Chlorine Dioxide

IS NOT

CLOROX
SPLASH-LESS

Laundry Bleach
OR

Pool Chlorine

Your doctor is most likely not a chemist, and may or may not be fluent in the language of oxidizers. If you are working with a doctor, please take the science to them when you speak with them about adding CD to your child's protocol. The best thing we can do for our sick children is to make informed decisions. Understanding the difference between chlorine and chlorine dioxide, or chlorine bleach and chlorine dioxide may mean the difference between your child recovering or not.

I have shared this with thousands of families around the globe whose children have used chlorine dioxide in very dilute aqueous solutions, and NONE have had any injuries from CD. Sure, we have had discomfort in the form of a Herxheimer reaction. This is something we have learned to minimize, and can often be prevented by going low and slow. I have learned that what may appear negative at the outset, often turns out to be a healing crisis that leads to incredible gains in the long run.

Many of the first world children who have done the CD protocol have done it in parallel with other autism protocols. They have had regular blood, urine, and stool tests and generally test healthier while using CD than before they started. CD is fortifying immune systems, improving liver function, reducing bacterial and viral loads, *Candida* markers, and inflammation.

> Just did round of blood tests on my son,
> Liver Function Test best ever after 7 months of MMS.

Critics also frequently cite the fact that sodium chlorite and chlorine dioxide can be used for industrial bleaching processes, as a way to frighten parents out of using it. Just because a substance has the power to remove color, or bleach something, doesn't mean it's "bleach." Lemon, sunlight, hydrogen peroxide, and toothpaste all remove color from textiles. We would never call toothpaste bleach, even though it's capable of removing color, nor would we call sunlight bleach, even though that's what it can do to your clothes if you leave them outside long enough. From here we can draw a very similar analogy to using chlorine dioxide for health. The dilutions we are using for internal consumption in aqueous solution (water) are very weak. Day one starts with just one drop in eight fluid ounces of water.

The 1984 study, *Controlled Clinical Evaluations of Chlorine Dioxide, Chlorite and Chlorate in Man*, found no deleterious effects when taking a concentration of up to 50ppm over several hours a day for three weeks.[1] As Jim Humble mentioned (see page 79), the concentrations used for industrial purposes are are thousands of times more concentrated than what families have been using for their children on the spectrum.

Any substance can become toxic if taken in too high a concentration—even water.[2,3] Chlorine dioxide is no exception. We always increase CD dosages, *low and slow*, and have a respect for the power that chlorine dioxide can have over pathogens, always resisting the urge to ramp up our dosing too quickly.

> We started MMS 68 Days ago and my son's ATEC has dropped from 50-23... Now that's a MIRACLE!!! He is So much more "with us" and I'm seeing improvements daily. He is just so much more fun to be with now:) He did have a plateau, but is back on track. We have only done 4 enemas to date, but they made a big difference! Baths do as well:) I can't wait to see what he is like on his 4th birthday (still 39 days away).

Chlorine Dioxide was discovered in 1814 by Sir Humphrey Davy as an effective disinfectant. Since then, numerous companies have patented its use for countless applications, including food and health.

The following is an excerpt from Jim Humble's Nov 21, 2012 newsletter:

> Dr. Andreas Kalcker spoke of patents obtained by different multinational pharmaceutical companies, to cash in on this product or to prevent it from being marketed.
>
> Some of those patents include:
>
> - Nontoxic Antiseptic (Pat 4035483/1977)
> - For combatting human amoebas (Pat.4296102/1981)
> - Against dementia caused by AIDS (Pat.5877222/1999)
> - For curing all types of illness of the skin (Pat 4737307/1988)
> - For disinfecting live blood (Pat. 5019402/1991)
> - For curing injuries more rapidly (Pat. 5855922/1999)
> - For all types of oral care (Procter & Gamble) (Pat. 6251372B1/2001)
> - Against infections caused by bacteria (Pat. 5252343/1993)
> - For treatment of severe burns (Pat.4317814/1982)
> - For the regeneration of bone marrow (Pat. 4851222/1989)
> - Treatment of Alzheimers, dementia etc. (Pat. 8029826B2/2011)
> - To stimulate the immune system in animals (Pat. 6099855/2000)
> - To stimulate the immunological system (Bioxy. Inc.) (Pat. 5830511/1998)

> ...The danger that may occur is if one mistakenly used a highly concentrated form. Highly concentrated forms of virtually every substance can cause death. In his conference, Dr. Andreas Kalcker points out that 70g of even plain table salt can cause death.
>
> There have been thousands of reports worldwide of excessive doses of MMS being ingested, however, with the hundreds of millions of tons of this substance used each year worldwide for water purification, preservation of vegetables, sterilization of slaughtered meat, and hundreds of other uses, there has never been a report of a death caused by ingestion of chlorine dioxide.
>
> This proves chlorine dioxide to be one of the safest products known.

There are many products that contain chlorine dioxide (ClO_2) that are currently approved by the Food and Drug Administration (FDA) in US. They are manufactured by *Frontier Farmaceutical*, *Alcide*, *Bioxy*, and others for skin and oral care. A number of these product names are listed below:[4]

- DioxiRinse™ Mouthwash
- DioxiBrite™ Toothpaste
- DioxiWhite™ Pro Teeth Whitener
- WhiteLasting™ Maintenance Gel
- BioClenz™ Dental Unit Waterline Cleaner
- Penetrator™ Periodontal Gel
- Simply Clear™ Acne Treatment
- DioxiWhite™ Home Teeth Whitener
- Cankers Away™ Canker Sore Cure
- DX7™ Skin Protectant Gel
- Periodontitis Treatment
- DioxiSmooth™ Facial Exfoliant
- Gingivitis Treatment Surface Disinfection
- Fire Fighter™ Burn Pain Reliever
- DioxiGuard™ Spray Disinfectant
- Nail-It™ Nail Protector

Chlorine Dioxide is an Oxidant… But aren't Antioxidants Good for Us?

In 1954, Denham Harman published an article called the "Free Radical Theory of Aging,"[5] claiming antioxidants would slow the aging process. However, he later found that mitochondria determined life span, and that antioxidants do not enter the mitochondria, and subsequently published the

"Mitochondrial Theory of Aging,"[6] in 1972. The "Free Radical Theory of Aging" is still responsible for billions of dollars in antioxidant supplement sales a year. While writing this book, a fascinating article was published in the journal *Open Biology* by Dr. James Watson (of Watson and Crick) called "Oxidants, antioxidants and the current incurability of metastatic cancers."[7]

Watson sets forth a hypothesis that links the presence of antioxidants in the body with late-stage (metastatic) cancer. He points out that some successful cancer treatments use "free radical" molecules to treat cancer—the very same molecules that antioxidants attack and kill. Watson urges his readers of the new paper to consider the following: "Unless we can find ways of reducing antioxidant levels, late-stage cancer 10 years from now will be as incurable as it is today."[8]

The following was excerpted from the same article in *Open Biology*.[8] Please see the original document for references contained within the text.

> Free-radical-destroying antioxidative nutritional supplements may have caused more cancers than they have prevented.
>
> For as long as I have been focused on the understanding and curing of cancer (I taught a course on Cancer at Harvard in the autumn of 1959), well-intentioned individuals have been consuming antioxidative nutritional supplements as cancer preventatives if not actual therapies. The past, most prominent scientific proponent of their value was the great Caltech chemist, Linus Pauling, who near the end of his illustrious career wrote a book with Ewan Cameron in 1979, *Cancer and Vitamin C,* about vitamin C's great potential as an anti-cancer agent [52]. At the time of his death from prostate cancer in 1994, at the age of 93, Linus was taking 12 g of vitamin C every day. In light of the recent data strongly hinting that much of late-stage cancer's untreatability may arise from its possession of too many antioxidants, the time has come to seriously ask whether antioxidant use much more likely causes than prevents cancer.
>
> All in all, the by now vast number of nutritional intervention trials using the antioxidants β-carotene, vitamin A, vitamin C, vitamin E and selenium have shown no obvious effectiveness in preventing gastrointestinal cancer nor in lengthening mortality [53]. In fact, they seem to slightly shorten the lives of those who take them. Future data may, in fact, show that antioxidant use, particularly that of vitamin E, leads to a small number of cancers that would not have come into existence but for antioxidant supplementation. Blueberries best be eaten because they taste good, not because their consumption will lead to less cancer.

Don't Oxidants Cause Oxidative Stress?

Not necessarily. Dr. Andreas Kalcker presented us with another theory explaining why oxidative stress is caused by pathogens and parasites rather than oxidants. If you take an oxidant such as CD, it is likely to upset the parasites living in the intestinal tract, causing them to defecate. Waste from worms can contain many toxic substances including MDA (malondialdehyde), formaldehyde, and ammonia. These toxins are known to cause oxidative stress.[9,10,11,12] When parasites are present in the body they are releasing these toxins, even if we don't kill them. Parasitic presence in the body is responsible for many of the symptoms known as autism.

Oxidants themselves are not directly responsible for oxidative stress in the body. However, they can exacerbate oxidative stress, which can cause parasites in the body to release toxins. The solution is to get rid of the parasites. Please see Chapter 8 for an effective Parasite Protocol.

Chlorine Dioxide & Antioxidants

Although antioxidants have their place in personal health and are common in many foods and supplements, they cannot be taken at the same time with chlorine dioxide—they negate each other. This is why vitamin C, juices, and other antioxidant containing foods are prohibited in *The Diet*.

> Just a testimonial to MMS: For those of you new to the group and still unsure of the MMS protocol I wanted to tell you about us. I was afraid at first, but we decided to try MMS. Within 3 weeks my son went from an ATEC of 36 to 18! That was amazing. Then we were afraid of the enemas. We said no way, we would just do oral MMS. Of course, after seeing others progress here we decided to do them. He would calm down! Then for months we agonized over the PP. We were afraid of it. We were scared of the meds, everything. Finally we decided to try it too. We are in the middle of our first PP and our son, who used to hit, kick, bite and scream at me over the smallest things all the time, has now been a perfect joy. When he gets mad it is over quickly and does not escalate into world war 3. Also these bumps he had on his face have cleared up along with his attitude! So if you are unsure of MMS like I was, here is one more testimonial of just how good the protocol really is. Thanks Kerri, and all the other moms that came before me!

Herxheimer Reaction (Die-Off Reaction)

There are many stories on the Internet about the "side effects" of CD. The definition of a side effect is:

The unintended or secondary effects of a substance.

When people describe what they believe to be side effects of CD, they are actually talking about a Herxheimer reaction. Jim Humble's original chlorine dioxide (MMS) protocols called for higher doses per hour ramped up much faster than we titrate up for autism. In some cases that resulted in nausea, vomiting, and/or diarrhea. Critics of CD claim that a Herxheimer reaction, which is the result from ramping up too quickly, is the body's reaction to being 'poisoned' by chlorine dioxide.

This is absolutely not the case, as the aforementioned study by Judith R. Lubbers and colleagues found that when healthy individuals were given minimal doses of chlorine dioxide in increasingly higher concentrations, no deleterious effects were noted.[2]

A Herxheimer reaction indicates that the patient is suffering from an overload of pathogens/toxins. If the person taking CD has a fair amount of pathogens, the rapid killing of these invaders produces excess toxins in the bloodstream. It is these substances that the body wants to rid itself of in short order. People with autism often have impaired methylation cycles that reduce their ability to eliminate toxins, making it even more difficult to handle an influx of toxins. So LOW AND SLOW is the way to go.

Children with autism typically don't (or can't) tell you they have nausea. However, discomfort may be visible from seeing that they're eating less, their eating habits have changed, or they're more listless than usual. That's usually a sign of detox, and in which case, we won't give the child any more CD that day. Detox is great, it's what we want, but without stressing the body further. We need to stay just beneath a Herxheimer reaction.

A Herxheimer reaction can present itself in many forms including:

- Blisters
- Bloating
- Burping
- Chills
- Diarrhea
- Fatigue
- Flatulence
- Flushing
- Headache
- Heart Burn
- Hiccups
- Nausea
- Runny nose
- Sleep changes
- Vomiting

If any of these symptoms appear, suspend the remaining doses of CD for the rest of the day. The following day, return to the number of doses given when the child was stable, which is usually the dose that was given the day prior to the Herxheimer reaction.

To mitigate a Herxheimer reaction from chlorine dioxide, you can give vitamin C or orange juice, as either one of these will cut the effects of CD immediately. To help bind the excess toxins you may want to try activated charcoal, bentonite clay, (be aware that these both can cause constipation), or burbur (a liquid detox extract).

Using Chlorine Dioxide for Autism

As I developed this protocol, it became clear to me that we needed to focus on excesses causing the symptoms of autism, rather than deficiencies caused by them. In the autism biomed world, we are accustomed to supplementing deficiencies (low iron, low B_{12}, low calcium, etc.), without questioning why the deficiency exists in the first place (i.e., presence of pathogens/parasites).

As soon as a family completes one week on *The Diet*, we get right into CD. Everyone starts with the "baby bottle" method, one drop of CD in eight fluid ounces of water, which makes the first day's dose 1/8 of a drop at a time. We have greatly minimized Herxheimer reactions by using this method, but it remains very important to monitor your child while they are using chlorine dioxide. It's very important to go low and slow. Every drop we give is helping to heal our children.

What is Chlorine Dioxide (CD)?

Refer to the diagram on the right for a visual overview.

You can't actually buy CD. You have to make it. Fortunately, it's not a big deal. If you can make coffee... you can make CD, which stands for *chlorine dioxide*.

Chlorine dioxide (ClO_2), is a gas produced through a chemical reaction when two liquids, sodium chlorite ($NaClO_2$) and an acid (such as hydrochloric acid (HCl) or citric acid ($C_6H_8O_7$)), are mixed. The acid brings the combined pH level below five, causing the sodium chlorite to become unstable and release chlorine dioxide (ClO_2).

If any of this sounds complex, it isn't. Go through the following explanation and don't get bogged down by the chemical symbols.

Conceptual Overview of Chlorine Dioxide (CD)


Sodium Chlorite
(White Powder or Flakes)
Water
(Distilled)
Sodium Chlorite Solution (22.4%)
Clear Liquid
Hydrochloric Acid 4%
(Best Choice)
OR
Citric Acid 50%
Clear Liquid
Chemical Reaction
when mixed
Measured in drops or milliliters.
Yellow/Amber Colored Liquid
Chlorine Dioxide in solution
containing some amount of sodium chlorite, acid, water, etc.

Advanced users can buy raw materials and save $.

When first starting out, buy a kit to avoid mistakes.

Often referred to as the *Activator*.

CAUTION! Chlorine Dioxide gas easily escapes when these liquids are not in a sealed container. Avoid breathing excessive amounts of this gas.

Sodium Chlorite ($NaClO_2$)

This is the first chemical you must have to make CD.

You can get it in one of two forms:

- **Sodium chlorite liquid in water:**
    - If you are beginning, get a starter kit of this.
    - Expect to pay about $20-$30 for a 4 fl. oz. bottle set (usually includes acid activator).
    - 22.4% sodium chlorite solution (from 28% technical grade sodium chlorite salts).
    - Recommended: Buy quart or liter sized quantities of liquid once you understand the principles.
- **Sodium chlorite powder or flakes:**
    - FOR ADVANCED USERS ONLY!
    - Cheaper in the long run.
    - Recommend buying 5 lbs. of flakes/powder for a cost of about $100-$200.
    - Look online or check with your supplier for mixing instructions.
    - Avoid buying 90% sodium chlorite flakes. You want 80%. Most suppliers that sell liquid also sell flakes.
    - NEVER mix any acid directly with powder/flakes!

What's the 28%? 22.4%?

This is not a critical thing for you to worry about unless you are mixing your own. But here is the jist: sodium chlorite powder is not 100% sodium chlorite. It's usually 80% sodium chlorite and 20% salt and other inert ingredients. When diluted in water, you end up with 28% solution of powder, but only 22.4% is sodium chlorite. Labels usually show one or both of these numbers.

Sodium Chlorite Flakes vs. Powder

Sodium chlorite flakes and sodium chlorite powder are the same thing. The resulting physical consistency may vary by different manufacturers. We've even seen clumps of powder. It's still the same chemical. The important part is that it is technical grade, and 80% of the powder/flakes should be sodium chlorite ($NaClO_2$). Mixing info is at: *www.youtube.com/watch?v=t0C8XVm9QVE*.

Acid - The Activator

To produce CD, you must add the second chemical, which is a food acid, to the liquefied sodium chlorite (22.4% solution in water). Chlorine dioxide gas is produced when the pH of the sodium chlorite goes below five. We call the acid used to lower the pH of sodium chlorite an "activator" because it activates the sodium chlorite to produce the chlorine dioxide.

There are several activators to choose from. These are food acids in that they are commonly found in food preparations, or are actually food:

- **Hydrochloric Acid (HCl)**
    - The same acid found in your stomach, and therefore, the most biocompatible option.
    - Working concentration is between 4% and 10%.
    - Available on the market in liquid concentrations of 4%, 5%, 10%, 32%, 35%, and 37%.
    - Any concentration over 10% must be reduced to a working concentration of between 4% and 10%. See Appendix 7, page 471. (Note: We use 4% for CD and CDH; & 10% for CDS.)
    - Only available in liquid form.
- **Citric Acid**
    - Commonly available around the world.
    - Often found in soft drinks to give them a tangy flavor.
    - Some people have problems tolerating this acid.
    - Usually used in 50/50 concentration by weight mixed in water.
    - Available in liquid and powder form.
    - Inexpensive; can be purchased online.
- **Lemon or Lime Juice**
    - Consider this an emergency alternative to be used if the first two choices are not available.
    - Can be found in most stores carrying produce.
    - Should be from pure, organic and freshly squeezed lemons (or limes).
    - Relatively weak acidity requiring five drops of lemon juice to every one drop of sodium chlorite solution.
    - Substantially longer activation time.
    - Lower ClO_2 output.

The amount of acid used, and the length of time you wait to dilute the mixture, will depend on the acid activator and its strength. The following chart gives you an idea.

Activator	Strength	Ratio	Time
Hydrochloric Acid	10%	1:1	40 secs
Hydrochloric Acid	4%	1:1	60 secs
Citric Acid	50%	1:1	60 secs
Citric Acid	33% or 35%	1:1	60 secs
Lemon Juice	Pure	1:5	120+ secs

You are unlikely to be using lemon juice, but we've included it here for completeness.

Families should use whichever activator is available to them depending on where they live and what they have access to. All kids are different, so if yours doesn't respond well to 4% HCl, by all means, try citric acid, or vice versa.

If the HCl you purchased is anything other than 4% or 5%, then see Appendix 7 for instructions on reducing concentration.

If you are using one of the two most commonly available activators, then you are likely to be using a 1:1 mixing ratio (1 drop sodium chlorite + 1 drop activator).

In the case of 10% citric acid or pure lemon juice, you would be using five drops of activator to one drop of sodium chlorite, and waiting about three times as long as if you were using one of the newer, more concentrated activators.

Purchasing Product

When you first start out, you should buy a starter kit and get familiar with the chemistry. A starter kit usually comes in two bottles of four fluid ounces each.

1. Sodium chlorite, (4 fl. oz.)
2. Activator (hydrochloric acid or citric acid), (4 fl. oz.)

The bottles look something like those shown in the diagram on page 91. Getting the hydrochloric acid activator is slightly preferable.

You will also need an 8 fl. oz. baby bottle. This is a handy tool for storing a day's worth of CD doses with the added benefit of having marks that show how much it contains. Glass bottles are much better than any kind of plastic bottle. Lifefactory.com (shown on the right) produces a bottle we especially like. It is made of silicon-covered glass and has a reliable top. This particular bottle is marked as having a capacity of nine fl. oz., but we use it up to only eight fl. oz. Plastic should only be used for lids; avoid bottles with metal tops. Over time, CD will oxidize metals so they can't be used.

Another item that most people have at home is a shot glass or wine glass that tapers down in the middle like a "U" shape. This will be used to mix the chemicals and the tapered shape insures that even as few as two drops will find each other. You can also use a cup with a flat bottom, but must tilt it so both solutions pool together.

lifefactory

A standard shot glass with a "U" shaped bottom is the preferred mixing container for CD & activator. A glass baby bottle, such as the one made by Lifefactory®, is the ideal dosing bottle.

Terminology of Available Products

There can be a bit of confusion for some as to what to look for and buy. The following chart shows the actual chemical, and some of the common names found on the label. There may be other names we are not aware of. In most cases, the chemical and its strength are identified on the bottles.

Common Activators & Their Various Names on the Market	
Chemical	**Common Names**
Sodium Chlorite	Chlorine Dioxide – Part 1 (Purifier) Master Mineral Solution Miracle Mineral Solution Miracle Mineral Supplement MMS MMS Drops MMS Solution MMS Water Purification Drops MMS1 NaClO2 Natriumchlorit (German) Pathogen Biocide Sodium Chlorite 28% Water Purification Drops Water Purificator
Hydrochloric Acid	Activator Chlorine Dioxide – Part 2 (Activator) MMS Activator
Citric Acid	Activator Citric Acid – 20% Citric Acid – 50% MMS Activator

Checklist for Preparing a CD Dose

Assuming you have received the starter kit, it's time to make your first dose. Here's the check list of what you now should have on hand before you begin:

- ☐ Bottle of sodium chlorite solution (28% sodium chlorite salts / 22.4% sodium chlorite)
- ☐ Bottle of acidic activator (hydrochloric acid or citric acid)
- ☐ A clean and dry shot-glass with a "U" shaped bottom.
- ☐ 8 fl. oz. glass baby bottle.
- ☐ Distilled or reverse osmosis water (filtered water will do, but no alkaline water!).

A Few Points Worth Noting!

Looking at the short checklist above, it should be apparent that this is not going to be rocket science. Nevertheless, a few pointers are in order:

- In the past, people who used CD for various things would mix a fresh batch each time they took CD. This involved a lot of extra work that could be avoided by producing one batch big enough to last the entire day. For this exercise, we are assuming you are starting out and going to do things low and slow. We are going to produce 8 fl. oz. of water solution containing one drop of CD, with the intention of your child consuming one fl. oz., of water (containing 1/8 drop of CD) eight times throughout the day.

- When you mix sodium chlorite solution and the acidic activator, you are mixing equal drops of each substance (unless you are using one of the less concentrated activators mentioned earlier).
- CD doses are measured in drops of sodium chlorite. So one drop of sodium chlorite + one drop of activator = one drop of CD.
- On your first day, start with one drop of sodium chlorite and one drop of activator (in other words—ONE drop of CD).
- If you put in too many drops of one solution or the other, start over with a clean and dry shot glass.
- A batch of CD is good for 24 hours. However, you must keep the cap on tight!
- Keep the bottle with the daily CD batch out of direct sunlight. A brief exposure won't ruin it, but it will become weaker. Why? The chlorine dioxide gas will come out of the water and sometimes form a cloud in the air pocket of the bottle. No need to worry if you see the cloud—it's a common occurrence.



Vincent taking his hourly dose.

Preparing Your First One drop CD Batch for the Day

1.	Start by filling the baby bottle with 8 fl. oz. (237ml) of water (distilled or reverse osmosis). NO alkaline water!	
2.	Place 1 drop of sodium chlorite solution into the CLEAN and DRY shot glass.	
3.	Add 1 drop of acidic activator (hydrochloric acid or citric acid) to the shot glass containing the drop of sodium chlorite. The number of drops may be higher if you are using a weaker activator. See chart on page 94.	
4.	Now wait the appropriate time for the mixture to react (see chart on page 94). You should see the color change from clear to slightly yellow. If there were more drops in the shot glass, the color change is more noticeable. You are also likely to notice the chlorine-like smell coming from the shot glass. Remember, this is NOT chlorine, but rather chlorine dioxide.	
5.	After the activation time has passed, pour a little water from the baby bottle into the shot glass and let it mix. This mostly stops the chemical reaction and insures you get most of the mixture out in the next step.	
6.	Lastly, pour all of the watered down mixture in the shot glass back into the baby bottle, and seal it tightly with the cap—don't leave it sitting open for any length of time. Think partially used soda pop and how you would want to keep that closed.	

Voilà! You have just produced your first batch of CD!

This is now a ONE drop batch, that makes EIGHT hourly doses—each 1/8 of a drop in strength. If your batch is larger; your hourly dose is stronger:

- 2 drop batch = 8 hourly doses of 1/4 drop
- 4 drop batch = 8 hourly doses of 1/2 drop
- 8 drop batch = 8 hourly doses of 1 drop


This bottle has some extra room. Labeled having 9 fl oz capacity.
9 fl oz
8 fl oz
7 fl oz
6 fl oz
5 fl oz
4 fl oz
3 fl oz
2 fl oz
1 fl oz
0 fl oz
1/8 Drop of CD
1/8 Drop of CD
1/8 Drop of CD
1/8 Drop of CD
1/8 Drop of CD
1/8 Drop of CD
1/8 Drop of CD
1/8 Drop of CD
1 drop of CD in 8fl oz (237ml) of water

Oral Protocol for CD in Autism Spectrum Disorders (ASDs)

In the previous exercise, you learned how to prepare the dose for Day One. Children and adults all start by taking only one drop of CD divided into eight hourly doses. On Day Two, you make a batch of two drops sodium chlorite plus two drops activator and mix that into eight fluid ounces of water. Increase this dosage by one drop per day, unless you see a Herxheimer reaction (see page 89 for more information).

The chart on the right allows you to determine the estimated full oral CD dose based on the weight of the individual. This gives you an idea of the maximum goal number of drops per day for your child. Once the child has been at the full suggested dose for several months, we may need to increase again, by a few drops, to prevent a plateau.

Important Note: Some children can't go up by one drop each day and need to go slower. A child may have a relatively higher toxic load, or he may be extremely sensitive. Whatever the case, resist the urge to try to get to full oral dose as quickly as possible. This is not a race! Some children need to spend a few extra days at the same dose to avoid a Herxheimer reaction. Even if you must remain at one level for a few days or more does not mean you are making no progress. Whatever the level of dosage, you are detoxing the body.

When you get within two to three drops of your child's maximum dose by weight, go ahead and spend three days at each dose, while carefully observing your child, moving up only when your child is stable. For example, if the full dose is 16 drops in the 8 fl. oz. (237ml) baby bottle, stay at 14 drops for a few days to see how that dose level is tolerated, and then increase every third day till reaching the full dose. If the person is better at a drop or two below the calculated full dose, go back to that lower dose that they tolerated best.

> *Just had a fascinating appointment with my son's functional neurologist. My son had this third Qeeg today, which clearly showed that previously under-stimulated parts of his brain are 'waking up'. I told our doctor about CD very early on and he believes that it is THIS that is having such a huge impact on his brain. He got quite emotional and said 'every time you get a worm, you are saving your son. Keep doing what you're doing, cause he clearly isn't autistic. He's poisoned'. Goosebumps!!*

Estimated Full Oral CD Doses by Weight

Use these numbers as a guide only. You may need to go up by as much as 50% or more over the indicated drops. Read chart as: **POUNDS / KILOGRAMS → DROPS OF CD (per 8 fl. oz. water)**

25/11→8	62/28→17	99/45→24	136/62→29	173/78→33	210/95→37
26/12→8	63/29→17	100/45→24	137/62→29	174/79→33	211/96→37
27/12→9	64/29→17	101/46→24	138/63→29	175/79→34	212/96→37
28/13→9	65/29→18	102/46→24	139/63→30	176/80→34	213/97→37
29/13→9	66/30→18	103/47→24	140/64→30	177/80→34	214/97→37
30/14→9	67/30→18	104/47→25	141/64→30	178/81→34	215/98→37
31/14→10	68/31→18	105/48→25	142/64→30	179/81→34	216/98→37
32/15→10	69/31→18	106/48→25	143/65→30	180/82→34	217/98→37
33/15→10	70/32→19	107/49→25	144/65→30	181/82→34	218/99→38
34/15→10	71/32→19	108/49→25	145/66→30	182/83→34	219/99→38
35/16→11	72/33→19	109/49→25	146/66→30	183/83→34	220/100→38
36/16→11	73/33→19	110/50→26	147/67→31	184/83→35	221/100→38
37/17→11	74/34→19	111/50→26	148/67→31	185/84→35	222/101→38
38/17→11	75/34→20	112/51→26	149/68→31	186/84→35	223/101→38
39/18→12	76/34→20	113/51→26	150/68→31	187/85→35	224/102→38
40/18→12	77/35→20	114/52→26	151/68→31	188/85→35	225/102→38
41/19→12	78/35→20	115/52→26	152/69→31	189/86→35	226/103→38
42/19→12	79/36→20	116/53→26	153/69→31	190/86→35	227/103→38
43/20→13	80/36→21	117/53→27	154/70→31	191/87→35	228/103→38
44/20→13	81/37→21	118/54→27	155/70→31	192/87→35	229/104→38
45/20→13	82/37→21	119/54→27	156/71→32	193/88→35	230/104→39
46/21→13	83/38→21	120/54→27	157/71→32	194/88→35	231/105→39
47/21→14	84/38→21	121/55→27	158/72→32	195/88→36	232/105→39
48/22→14	85/39→21	122/55→27	159/72→32	196/89→36	233/106→39
49/22→14	86/39→22	123/56→27	160/73→32	197/89→36	234/106→39
50/23→14	87/39→22	124/56→28	161/73→32	198/90→36	235/107→39
51/23→15	88/40→22	125/57→28	162/73→32	199/90→36	236/107→39
52/24→15	89/40→22	126/57→28	163/74→32	200/91→36	237/108→39
53/24→15	90/41→22	127/58→28	164/74→32	201/91→36	238/108→39
54/24→15	91/41→23	128/58→28	165/75→33	202/92→36	239/108→39
55/25→16	92/42→23	129/59→28	166/75→33	203/92→36	240/109→39
56/25→16	93/42→23	130/59→28	167/76→33	204/93→36	241/109→39
57/26→16	94/43→23	131/59→28	168/76→33	205/93→36	242/110→39
58/26→16	95/43→23	132/60→29	169/77→33	206/93→37	243/110→39
59/27→16	96/44→23	133/60→29	170/77→33	207/94→37	244/111→40
60/27→17	97/44→24	134/61→29	171/78→33	208/94→37	245/111→40
61/28→17	98/44→24	135/61→29	172/78→33	209/95→37	246/112→40

Serving Cup Dilution

Don't have your child drink out of the baby bottle. Pour the hourly dose into a separate cup and add extra water if needed. Make sure to add water to each dose to ensure that there is a **minimum** of one fluid ounce of water per activated drop of CD. However, there is no maximum amount of water for dilution. To be absolutely clear about this, note the following chart which assumes eight fl. oz., daily batches containing eight hourly doses.

Drops of CD in Batch	Hourly Dose	Min. Water Dilution
1	1/8 drop	1 fluid ounce
2	2/8 drop	1 fluid ounce
3	3/8 drop	1 fluid ounce
4	4/8 drop	1 fluid ounce
5	5/8 drop	1 fluid ounce
6	6/8 drop	1 fluid ounce
7	7/8 drop	1 fluid ounce
8	1 drop	1 fluid ounce
9	1 1/8 drops	2 fluid ounces
10	1 2/8 drops	2 fluid ounces
11	1 3/8 drops	2 fluid ounces
12	1 4/8 drops	2 fluid ounces
13	1 5/8 drops	2 fluid ounces
14	1 6/8 drops	2 fluid ounces
15	1 7/8 drops	2 fluid ounces
16	2 drops	2 fluid ounces
17	2 1/8 drops	3 fluid ounces
18	2 2/8 drops	3 fluid ounces
19	2 3/8 drops	3 fluid ounces
20	2 4/8 drops	3 fluid ounces
21	2 5/8 drops	3 fluid ounces
22	2 6/8 drops	3 fluid ounces
23	2 7/8 drops	3 fluid ounces
24	3 drops	3 fluid ounces
25	3 1/8 drops	4 fluid ounces
26	3 2/8 drops	4 fluid ounces
27	3 3/8 drops	4 fluid ounces
28	3 4/8 drops	4 fluid ounces
29	3 5/8 drops	4 fluid ounces
30	3 6/8 drops	4 fluid ounces
31	3 7/8 drops	4 fluid ounces
32	4 drops	4 fluid ounces

CD is active in the body for about one hour and, as result, hourly doses give us the best progress. This is difficult on school days, but we recommend that you dose two to three times before school and the rest after to distribute the pathogen-fighting more evenly. Eight doses a day is the minimum requirement, but the more you can fit in the better. Try to dose every hour as much as possible.

Special Cases: "The Double Dose"

As a child goes through the detox process, they may exhibit conduct which can include hyperactivity, anxiety, OCD, aggressiveness, and night wakings. In these cases, a double dose is 2 fl. oz. (60ml) of the baby bottle given at once. For example, if your child receives one drop per fluid ounce of the baby bottle method, they will be receiving 2 drops. Let's say for example your child wakes up at 1am, give them a double dose. If your child is still awake at 2am, give another dose. The most common scenario is that after 1 or 2 double doses, the child will fall back asleep. This helps oxidize the toxins from the die-off. During the day if your child has a tantrum or other issues with conduct, we can double dose every hour as well.

CD has two functions with pathogens; one is that is oxidizes the pathogen itself, and the second is that it oxidizes the toxins released by the pathogens while they are living, dead, or dying.

Advanced Protocol – The Enema!

In early 2011, we added enemas to the protocol to kill the pathogens causing dysbiosis in the large intestine (we didn't know about parasites yet). We wanted to get the chlorine dioxide into the blood stream so it could kill the biofilm that exists in the blood. In this way, the blood can carry the CD past the blood-brain barrier to kill pathogens in the brain

When we are detoxing, it is absolutely critical to keep the colon moving and avoid the reabsorption of toxins through the intestinal walls. Enemas allow us to do just this. Some toxins can exit the intestine through the intestinal wall (more so if leaky-gut syndrome is present), and cross the blood-brain barrier, therefore affecting cognition and behavior. When we cleanse the colon, we get those out before they can cross into the brain, and we detoxify the lymphatic system, liver, and gallbladder.

The Enema Stigma

When I say the word enema to a family new to the protocol, I often hear things like "*I could never do that!*," or "*My son would never let me do an enema.*" I assure you it's not traumatic as it has been hyped up to be. Modern society has gotten away from it, but for millennia, cleansing the colon was considered part of daily hygiene. Enemas were mentioned in the Vedas, the Bible, and by the Mayans. The reason for doing CD enemas is NOT for relief of constipation. Of course, when constipation is present, CD enemas can relieve the cause of constipation.

> Great news! First enema today...
>
> My son was so happy that we did and the first thing he said while sitting on the toilet was: "Mommy! IT WORKED!!!" hahaha He is so used to sitting on the toilet and having such a hard time. Poor thing, he was so happy that IT WORKED!
>
> And he even said he wants to do it again tomorrow. He felt so much better and ate so much more for dinner with an empty stomach. I think he got rid of stuff that was there for ages! His tummy is now soft and not hard as usual. Quite amazing and it didn't bother him at all.
>
> Today his molar hasn't bothered him so a perfect day to start the enemas! His appetite has gone up quite a bit. He has seldom asked for food before and now he asks a few times a day for something to eat. The diet is going wonderfully and he is now used to the change of foods. He asks about cheese and milk but I try to talk about something else to distract him so he eventually stops asking. hahaha He hasn't gotten upset about food he wants (that he can't have) not even once. YAY!

I would like to clear up one thing here before we get in the mechanics of the enemas. More than one person has asked in the blogosphere, "*If Kerri Rivera loves enemas so much, why doesn't she do them on herself???*" As a matter of fact I do! I have done my own enemas for years, so has my husband, my sister, and plenty of the parents using this protocol for their children. We understand the benefits of a fit colon, and have no problem applying our own enemas or going for a colonic from time to time.

Actually, I would strongly advise you to practice on yourself. That way you know from first-hand experience that this is really no big deal. You will also discover how much better you feel after cleaning out your colon, and you will understand when your child feels better as well.

When to Start Giving Enemas

Enemas should be started when the child reaches full oral dose.

However, if your child suffers from constipation you can add enemas and baths on day one (see page 113), before you get to the full oral dose. However, alternate them on opposite days or opposite ends of the day.

Frequency of Enemas

I recommend enemas no less than once every other day. You may need to do them more often, particularly if you see parasites coming out. Doing as many as four in a day is not uncalled for if each one results in parasites being released. Some of the older children seem to pass a lot of parasites in one day, typically in or around a full or new moon.

Timing of Enemas

If your child is going to school, avoid giving an enema in the morning since they may need to visit the toilet a few times after. If the child is homeschooled or too young or sick to attend, the timing is up to you. Ideally, do the enema after the child has a bowel movement.

Enemas — What You Need

The first thing you are going to need is some kind of a large plastic, liquid measuring container. Glass is not recommended since it can get knocked over and break in the confines of a bathroom.

You will also need all the same things you used for making CD batches:

- Water. Use reverse osmosis, filtered, or distilled.
  DO NOT use tap water or alkaline water!
- Sodium chlorite solution
- Acidic activator
- Shot glass
- Natural lubricant (coconut oil or any other simple food oil). NO perfumed baby oil or chemical lotions such as Petroleum Jelly or K-Y® Jelly.
- Enema kit (see your options on the following page)

Enema Options (Most to Least Preferred)

Gravity Bag or Bucket with hose

PiC
indolor
IRRIGADOR
ENTEROCLISE
KLISTEERSPUIT
ΚΛΙΣΜΑ

Pros:
- Holds plenty of liquid
- Can be refilled without taking it down
- Flow is easy to control
- Can be hung on a door
- Can be used for both enema and douching
- PIC Indolor: Folds for easy travel
- PIC Indolor: Has valve
- PIC Indolor: Two sizes of cathetors

Cons:
- Bucket doesn't fold for easy travel

Enema / Douche Bag / Hot Water Bottle

Hot / Cold
Water Bottle System
Hot/Cold
Therapy Anytime...
Anywhere!
Safe
Durable
Hygienic

Pros:
- Holds plenty of liquid
- Flow is easy to control
- Can be hung on a door
- Can be used for both enema and douching
- Easy travel
- Has two sizes of cathetors

Cons:
- Can't be refilled without taking down
- Usually made of rubber, which tends to dry out quickly, especially from CD.

Syringe & Catheter

Pros:
- Flow is easy to control
- Can be used for both enema and douching
- Good for small children

Cons:
- Holds only 60ml-140ml
- Need more than one.
- Have to swap them out to go beyond the capacity of one syringe.
- The graduations rub off easily (suggest putting clear shipping tape over them to protect the markings if they are important to you).

Enema Bulb

Pros:
- Portable
- Can be used for both enema and douching
- Good for “implants” of mebendazole

Cons:
- Volume too small for an effective treatment.
- Hard to clean inside
- Can’t tell if dirt is on the inside.
- Holds only about 200ml.

Fleet Enema (Last Resort)

Fleet
Enema
saline
Twin Pack
LAXATIVE
ready-to-use
latex free
Soft, Flexible Comfortip
EASY SQUEEZE
2

Pros:
- Cheap
- Can find it in most pharmacies
- Portable
- Can be used for both Enema and Douching

Cons:
- Volume too small for an effective treatment.

Enema Kits

As shown in the previous two pages, here are your enema kit options listed from best to less than good. Prices are estimates in US Dollars and are likely to be higher outside the US:

★★★★★ PIC Indolor Gravity Bag (~$15-$30)
★★★★☆ Enema Bucket (~$5-$10)
★★★⯪☆ Multipurpose Enema/Douche Bag/Hot Water Bottle (~$15-$30)
★★★☆☆ 100ml+ Syringes plus Catheter (~$5-$10)
★★☆☆☆ Enema Bulb (~$5-$15)
★☆☆☆☆ Fleet Enema (emptied out) (~$5-$15)

You must have a separate enema kit for each person doing enemas. This insures that you are not cross-contaminating parasites.

In my own home we have recently started using the PIC Indolor enema/douche bag. This has made the process faster, and we can tolerate more water before feeling full and desiring to release the enema. This is probably the most practical kit, especially because of the built-in shut-off valve. The enema bucket is a close second, but the sliding clamp that comes with it doesn't last long and breaks easily. You can always just kink the hose and control the flow that way.

The multipurpose enema/douche/hot water bottle type is a good option, but it is usually made of rubber. This material often goes bad over time and CD just speeds up that process. Rinse it out several times before and after use to insure that no breakdown or CD residue is left. Don't use if you notice the rubber becoming brittle.

Even two-year-olds still use about 400 to 500ml in an enema. The intestine is long. Parents with small children sometimes like the 100ml syringe/catheter method. The enema bulb or fleet enema are not really practical for our purposes due to the small volumes they hold. However, if you want to get started right away, they are usually available in most major pharmacies.

You can find syringes, catheters, gravity bags, multipurpose enema/douche bags on various online sites, pharmacies and medical supply stores around the world.

Preparing and Administering the Enema

Make all your supplies easily accessible in your work area before bringing your child in the bathroom. If this is your first time and you are working out the process, you may wish to ask your spouse or someone else for assistance. It's a good idea to do a dress rehearsal without the child, to insure that it goes smoothly when the child is present. Once you and your child have the process down, it will be easy. Being prepared is the key to success.

Please note: The eight fluid ounce baby bottle is NOT involved in any way with enemas!

1. Ideally, time the enema just after a bowel movement.
2. Start by washing your hands to insure you are not introducing any new bacteria into the colon. Everything you are working with should be clean. Wearing gloves and a face/surgical mask is HIGHLY recommended.
3. Assuming you are using one of the suggested gravity bags, find a good and stable location to hang it up. The best location really depends on your particular bathroom's layout and where you are going to place the child during the procedure. I hang mine from a towel hook in the bathroom, or you can use the shower curtain rod. The idea is to have the bag/bucket about three feet (~one meter) over where the enema will be administered. Most parents put a towel on the floor of the bathroom and lay their child on the towel (smaller children can lay across your lap).
4. Refer to the chart below and measure out the appropriate amount of water for the individual receiving the enema. The ratio is two drops of CD per 100ml of filtered warm water.

Age/Size	Water Volume	Drops of CD
Child	1/2 Liter (500ml)	10
Adolescent	1 Liter (1000ml)	20
Teen/Adult	up to 2 Liters (2000ml)	40

5. Don't add any CD yet. The next step is to heat the water to body temperature (98°F / 37°C). The water should feel warm to the touch—NEVER hot! Similar to the temperature of milk in a baby bottle... test it on your wrist. If you are concerned about getting the temperature right use a quality thermometer. Be aware... many cheap thermometers are notoriously inaccurate!

6. After the heating step, pour the water back into the big measuring cup.
7. Referring again to the chart on the previous page, prepare a CD mixture in the clean dry shot glass that's appropriate for the volume of water needed. For example, if you have an adolescent and are preparing one liter, then you will need to mix 20 drops of sodium chlorite and 20 drops of acidic activator to end up with 20 drops of CD! Note: The most important part of the enema is the ***water***. Resist the urge to add more than two drops per 100ml of water.
8. After the appropriate activation time, pour the concentrated CD from your shot glass into the large measuring cup. You may want to rinse out the shot glass with some water from the large mixing cup so you get all the concentrated CD solution into the water.
9. The bag/bucket should now be in its working location with the hose firmly attached, Place the end of the hose so it is over the top of the bag/bucket. A clothes pin can come in handy to hold it up over the bag/bucket. Now, fill the bag/bucket about 3/4 full with the CD water mixture you just prepared.
10. Make sure the hose is filled with water. You may want to let a bit run out into the sink or some other container and then clamp it. The bucket type enema has a plastic clamp for this purpose. The bag type has a valve where the catheter attaches. What you don't want is for there to be a bunch of air in the hose that then is transferred into the colon.
11. If all of the above is ready, it is time to bring your child into the bathroom.
12. Explain what you are going to do. Some parents say that they are going to put the catheter in his bottom, and that it has "special water" in it to help him feel better. One little boy called it "butt medicine" while another called it "butt wash." We recommend you say that you are the only person who is allowed to give this to him. Just say whatever you need to say to explain what is happening.
13. If the child is on the floor (on a rug or towel), they should lie on their stomach. If the child is small then laying them on your lap is best. You can also have them in a doggy position on the floor.
14. Place one or two drops of coconut oil (or similar) on their anus so the area is well lubricated.

15. Now take the hose and gently insert the tip, (one to two inches is plenty—more is not necessary) as the sphincter muscle will hold the tip of the catheter in place. If you are having any problems getting the catheter in, then you may need to add a bit more oil and/or adjust the angle.

16. Release the clamp or open the valve to allow the liquid to flow. The goal is *fill & release*.—NOT *fill & hold*. We are imitating the colonic process that is made up of gallons of water, yet in the home environment.

17. Your child will most likely hold the contents on their own—they will squeeze hard so as not to "go." This kind of happens naturally.

We do a fill and release method. The first part of the enema is usually stool. After that, we usually see parasites and or biofilm.

It's a learning experience and as time goes on, you will get the hang of it.

> *Quote from a teenager using the Protocol: "I like the enemas. Before them I am mad. But then when I get one, I feel better. My mad leaves in my poop.*

Syringe/Catheter Method

Before I started to use the gravity bag, the syringe/catheter method was my favorite. We have a YouTube video on our channel that shows how to fill the syringes and switch them out while using the catheter. If you don't have access to that video here is an explanation on how to do it:

1. Fill a bowl with body temperature filtered water and fill your syringes. If your child uses 500ml for an enema, fill all five syringes and dump out whatever water is still left in the bowl.
2. Squirt all the water from the syringes back into the bowl. You now have exactly 500ml of purified water.
3. Activate your drops of CD in a clean dry shot glass. If you are using ten drops, activate them and then use the water from your bowl to stop the activation process.
4. Pour the contents of the shot glass back into the bowl.
5. Refill your syringes with the activated CD solution.
6. Lubricate the tip of your catheter with coconut oil, and attach the first syringe.

Note: If you wish to preserve the graduation marks on the syringes, cover them with some clear plastic shipping tape. The printed on marks are often easily rubbed off and the tape will prevent that.

Fleet Enema Method

The third option for enemas is to use a Fleet enema, which can be purchased at any drug store. This method is acceptable if you don't have access to the other items but want to start immediately, as, generally speaking they are easy to find. An enema bulb is a fancy fleet enema without being prefilled with saline solution. Skip step one if that's what you are using:

1. Dump out the contents of the enema (basically saline water). Since a Fleet enema only holds 137ml, two drops of CD are the maximum number you can add. To use more water, empty additional Fleet enemas.
2. Activate your two drops of CD and dilute them with filtered water (not tap water).
3. Funnel the activated CD solution back into the Fleet bottle. Insert the applicator and squeeze the bottle until all or most all of the contents are empty.

Comments & Suggestions from Parents

Most people are surprised at how well this goes. Some parents have asked if they can do the Protocol without the enemas, and I say yes, but why? The results are just that much better with them. Enemas have, in fact, been around for thousands of years, and colon hydrotherapy is becoming a growing trend in autism recovery.

> I was really intimidated at first by the enemas.
> The syringe/catheter system, however, is brilliant. I lube the tip up with coconut oil, attach a filled syringe, and ask my son to put it in. He's 7 and very low verbal. He started inserting the tip by himself maybe on our 3rd or 4th enema with this system and I would depress the syringe. A few months later of every other day(ish) enemas, and he's doing the syringe depressing part himself. All I do is fill and swap syringes out. We are now to 11 100ml syringes, with 3-5 releases per enema (4 months into enemas). He requests enemas frequently on days I don't plan to give him one by getting the box of supplies and handing it to me.

Here are one mom's enema guidelines:

> *Be low-key about it, your attitude sets the tone. Have all your enema gear ready to go and in the bathroom for when the moment strikes. Put a nice, fluffy, washable blanket on the floor; bring in iPad, iPhone, whatever occupies your child for a few minutes. I've been doing my son's enemas after an afternoon poop if I get one because I figure it is easier as he is already in the bathroom, the bowel should be emptier, leaving more room for CD. Also the one time I did an enema close to bedtime, I swear he was up for an extra hour, however, another child might have the opposite reaction. I kneel on the floor, lay a beach towel over my lap, lay my son across me so he's on the ipad, pull his knees up a bit and then in it goes. You can put coconut oil on the anus or on the tip of enema. I ask my son to count to try to hold it in. (On the 4th enema, we only got to 40 seconds.) Then plop them on the toilet, and there you go.*
>
> *If possible, start the enema while lying on the left side, then rolling to the right. In this way, more water is able to reach the colon. (However, this may not be possible for all children.)*

CD Baths

Taking a bath with CD is another good way of detoxing your child. The CD gets into the pores and helps with skin rashes common with autism detoxification. This additional process can be added when you start with the enemas after reaching full oral dose, but avoid giving the child a CD bath right after an enema.

CD baths are done on non-enema days, unless you are doing daily enemas, in which case they are done on opposite ends of the day.

Enemas Every Other Day						
Sun	**Mon**	**Tue**	**Wed**	**Thur**	**Fri**	**Sat**
Enema	Bath	Enema	Bath	Enema	Bath	Enema

Enemas Every Day **(Enemas can also be in the morning and baths at night.)**						
Sun	**Mon**	**Tue**	**Wed**	**Thur**	**Fri**	**Sat**
Morning Bath	**Morning** Bath	**Morning** Bath	**Morning** Bath	**Morning** Bath	**Morning** Bath	**Morning** Bath
Evening Enema	**Evening** Enema	**Evening** Enema	**Evening** Enema	**Evening** Enema	**Evening** Enema	**Evening** Enema

The CD baths can go from as low as 10 drops to as high as 80 to 100 drops; it just depends on the person, and the size of your tub. With younger/smaller children we start with ten drops. Since we're doing baths every other day, start with ten drops on Monday, 11 drops on Wednesday, and 12 drops on Friday. Just keep going up until you get to 20 drops. The bigger and older the person is, the more drops they can tolerate.

Fill the tub to a level that maximizes skin contact.

If they start getting nauseous/listless or have loose stool, you should back down and find out what their signature dose is on the baths. Some people who have suffered from chronic constipation have done CD baths with up to 100 drops and had a BM during the bath or immediately after, without the use of drugs, laxatives, or suppositories.

CD Steam Bath

Inhalation of CD for children is generally impossible, because you just can't tell a child, especially a child with autism, "just inhale a little bit." That's not going to work. So we do the following:

In a bathtub, with the bathroom door and windows closed, plug the drain, put 20 activated drops on the floor of the tub, and turn on a hot (to tolerance) shower water. The steam will bring the CD into the air, making a really nice steamy bathroom.

When the tub is full, turn it off and place the child to soak in the water for 20 minutes. This way, the child is absorbing it through their skin as well as inhaling it through the air. This technique creates a very dispersed, low concentration dosage. I've seen a lot of children that were going back and forth to the hospital, getting steroid injections and lots of antibiotics due to bronchitis, coughs, asthma, etc., and it was rounds and rounds. This is how this particular method of steam baths came to be a very gentle way of inhaling the CD. It works beautifully; particularly if the child has a really bad cold and is congested, do the oral, enemas, and steam baths. Steam baths are great for asthma, flu, first signs of a cold, runny nose, coughing, etc., putting an end to running to the hospital or pharmacy.

CD Foot Baths

Sometimes it is impossible to give a CD bath, and in some places not all homes have bathtubs. To remedy this you can use a CD foot bath. Fill a small plastic container with hot (to tolerance) water and add your activated drops of CD.

If you have a smaller child, start with ten activated drops, and work up from there. If you have a larger child or an adult, start with 20 drops and go up. Soak feet for 20 minutes every other day, alternating with enemas, or opposite ends of the day if using daily enemas.

72/2 Protocol (Weekend Protocol)

When we give a child eight oral doses of CD throughout the day we are killing more and more pathogens. But at night when we sleep, the pathogens don't. So in order to get ahead of them, we can dose throughout the night. Imagine the progress we can make if we don't give them the chance to gain strength overnight!

Hence, the 72/2 Protocol, which involves giving one dose of CD every two hours for 72 hours straight—including the middle of the night. Here are some additional thoughts and guidelines:

- Start protocol when you pick up your child from school on Friday.
- Give them the last 72/2 dose when you drop them off at school on Monday.
- Avoid giving CD enemas or CD baths during this protocol, UNLESS they are dumping parasites, in which case you might need to reduce the amount of CD on both the oral and enema dose to insure the child doesn't have a Herxheimer reaction.
- Why not give hourly doses during the day at the usual dose? It's simply too much if you are doing it all night as well.
- Watch for improvements on Tuesday or Wednesday each week.
- Ideally, get your spouse or significant other to help with every other nightly dose.

The key is to observe your child and their reactions to the various treatments while keeping the pressure on eliminating the pathogens. You can do this every weekend or not at all. Some families are so happy with the results that they dose throughout the night for months on end.

Ocean Water

This protocol concentrates on excesses and not deficiencies. While we are using CD to reduce pathogen populations and heavy metal toxicity in the body, we need to remineralize the body. Remineralization is extremely important as vital nutrients may be lost along with toxins while detoxing. Children with autism are often mineral deficient to begin with due to these same pathogens and parasites, as well as gut dysbiosis which can prevent adequate nutrient absorption. We need to fortify our cells and tissues so that they can overcome the deficiencies and eventually return to a state of vitality.

Ocean water has helped us achieve mineralization and has led to increased brain connectivity; not to mention the parasites hate it. The importance of ocean water to this protocol cannot be understated. On page 388 of the Testimonials appendix you will see before and after lab tests proving that this protocol, when used correctly, can correct imbalances. More than one family has reported healthy nails, hair and skin as well as appropriate growth and weight gain.

We've all been taught that drinking salt water from the ocean is dangerous. Let me make it clear: We are not advocating drinking glasses full of straight ocean water nor water mixed with table salt. That would most likely make anyone sick, since it would be too much salt for the body. Rather, we are talking about diluted ocean water. Also, there is no comparison between real ocean water and just taking plain salt and mixing it into a glass of water!

The ocean is a complete source of minerals that are bioavailable to the human body. I prefer ocean water to any synthetic minerals, since the body easily recognizes and assimilates it.

Ocean water contains trace amounts of over 74 bioavailable elements including:

- sodium
- iron
- selenium
- sulfur
- calcium
- molybdenum
- cobalt
- boron
- silver
- fluorine
- potassium
- chromium
- zinc
- silicon
- chlorine
- vanadium
- nickel
- lithium
- iodine
- magnesium
- manganese
- copper
- phosphorus
- bromine
- gold
- etc.

We can use water directly from the ocean (diluted to 25%) and drink this to remineralize ourselves. However, the water must be from clean locations where schools of small fish swim and/or near ocean vortices. These locations provide safe and clean ocean water from which we can harvest. Most of us do not have access to oceans. Fortunately, clean ocean water is available commercially from multiple vendors online.

For further information about how and why ocean water is specifically beneficial to all of us, please research Rene Quinton's work on how he healed the sick using ocean water.

Using Ocean Water with CD

You can add ocean water in before starting CD, or after reaching full CD dose. We use a one part ocean water plus three parts drinking water mixed together (1:3). If we take too much ocean water, we can get loose stool. Start low and slow, 5ml ocean water mixed with 15ml drinking water and go up to tolerance.

Use the following chart as a rough guide:

Ocean Water Dosing

Size	When	Pure Ocean Water	Purified Water	Total Volume
Child	Start at	5ml	15ml	20ml
	Go to	30ml	90ml	120ml
Adolescent	Start at	10ml	30ml	40ml
	Go to	50ml	200ml	250ml
Teen / Adult	Start at	15ml	45ml	60ml
	Go to	75ml	225ml	300ml

Ocean water should be given three times a day, with the first dose being given in the morning, after the first dose of CD. You want to separate the dose of ocean water from doses of CD by at least five minutes. Larger children can take anywhere from between 70 and 120ml, depending on the child. Some adults take up to a cup (plus dilution water) per day. It is important to watch for loose stool/diarrhea when you are increasing the dose of ocean water, as that will be an indicator that the person is at their upper limit. The ratio of ocean water to drinking water is 1:3 (one part ocean water to three parts drinking water). It is important to stay under diarrhea. So we need to add slowly, and to tolerance. If someone suffers constipation, with the right amount of ocean water that will quickly change. So low and slow as we increase the ocean water.

Some parents have reported that their children will not drink ocean water, even when diluted, due to its salty taste. You can try adding a little flavored SweetLeaf® Stevia, or if necessary adding it into a beverage or soup. As some ocean water purists say, heating it kills some qualities of the ocean water. Nevertheless, your child will still be receiving all of the minerals.

Biofilm

One of the pioneers in autism recovery, Dr. Anju Usman gave the autism community one of the critical pieces of the puzzle—biofilm. The following information is used with permission from her presentation, *Gut Biology and Treatment.*

What is Biofilm?

A biofilm is a collection of microbial communities enclosed by a matrix of extracellular polymeric substance (EPS) and separated by a network of open-water channels. Their architecture is an optimal environment for cell-cell interactions, including the intercellular exchange of genetic material, communication signals, and metabolites, which enables diffusion of necessary nutrients to the biofilm community.

The matrix is composed of a negatively charged polysaccharide substance, held together with positively charged metal ions (calcium, magnesium, and iron). The matrix, in which microbes in a biofilm are embedded, protects them from UV exposure, metal toxicity, acid exposure, dehydration, salinity, phagocytosis, antibiotics, antimicrobial agents, and the immune system.

Ok, so in layman's terms, these are microbial (bacteria, Candida, virus, etc.) communities that have a protective layer around them, which makes them 100 to 1000x harder to kill than if they did not live in these protected communities.[13]

Why are they so hard to get rid of?

- Microbes impart genetic material to one another to maintain resistance.
- Colonies communicate with one another through the use of quorum sensing molecules.
- Colonies fail to express OMP (outer membrane proteins).[14]

These colonies are fairly amazing in their development. They communicate with each other, share genetic material to prolong their own survival, and don't express outer membrane protections. This last statement is very important to understand. This is the main reason that the immune system doesn't attack these colonies, they don't express themselves as a threat, and therefore the immune system, which in many children with autism is already compromised, is not able to detect or eliminate them.

In addition to this we must be careful with what supplements we choose to give to our children. Some supplements and nutrients may inadvertently feed the biofilm. "When trying to kill bugs, if you take calcium, you may not be making headway," Usman said. "Calcium, iron, and magnesium block our efforts to dismantle the biofilm."

Why CD Works on Biofilm

The microorganism communities attach to surfaces (in many cases the gut), and are held together by polysaccharides (sugars/carbohydrates) and by iron, calcium, and magnesium. EDTA is a known chelator, and can therefore break the bonds (iron, calcium and magnesium) that hold the matrix together. Neither an antibiotic alone nor a chelator alone was effective against a staph (bacterial) biofilm. However, when combined, EDTA broke the bonds exposing the bacteria to the antibacterial agent, allowing the body to expel the biomass.

Chlorine dioxide oxidizes inorganic compounds by effectively removing their charges. Here is how it works: Fe_2+, Ca_2+, and Mg_2+ are positively charged ions that hold the negatively charged matrix together. When these substances are oxidized by CD, the bacteria are then exposed to the CD which can oxidize (kill) the bacteria, allowing the body to finally expel the biofilm mass.

Many parents using chlorine dioxide orally, and with enemas, have found biofilms in their children's stool. Biofilm can look thick, mucousy, cloudy, whitish, greyish, sometimes like pantyhose, etc.

There is some more interesting information available through the AutismPedia about Dr. Usman's work with biofilm.[14]

We had our appointment yesterday and to all our surprise when he tested her for Lyme it was negative. Just 3 months ago and before starting MMS she was testing very positive for it. He was pleased with the outcome. Thank you so much for your guidance and we owe this to the miracle of MMS and your dedication to helping me with my questions. I really, really appreciate your help in bringing us one step closer to the cure.

Also, this article "Lyme-Induced Autism Conference Focuses on Biofilm and Toxicity"[15] by Mary Budinger discusses the effects of pathogens present in the biofilm for Lyme disease and autism. The following is a notable quote from the aforementioned article by Dr. Stephen Fry of Fry Labs, which explores the possible pathogenic causes of chronic disease.

> *I could be barking up the wrong tree, but maybe not. Remember that we used to think stomach ulcers were caused by too much acid production. Then Barry Marshall and Dr. Robin Warren turned medical dogma on its head by proving that a bacterium was the cause. The pair identified*

> *the bacterium H. pylori and proved how it causes inflammation, then ulcers. Maybe in 10 years we will be smart enough to know that the 'auto' in 'autoimmune' actually means pathogen and the whole concept of autoimmunity will change. Chronic inflammation is chronic infection. In autoimmune disease, my model is that there is a chronic infection that cannot be eliminated, thus the immune system is always switched on. The self antibodies are due to apoptosis and death of host cells with host immune response.*

I couldn't agree more, and am so grateful that we have CD to combat pathogens, and restore the body to a state of health.

Mitochondrial Dysfunction

Children on the spectrum are also more likely to have mitochondrial dysfunction than neurotypical children of the same age group. The following is an excerpt from *Science Daily*.[16]

> Children with autism are far more likely to have deficits in their ability to produce cellular energy than are typically developing children, a new study by researchers at UC Davis has found. The study, published in the Journal of the American Medical Association (JAMA), found that cumulative damage and oxidative stress in mitochondria, the cell's energy producer, could influence both the onset and severity of autism, suggesting a strong link between autism and mitochondrial defects.
>
> "Children with mitochondrial diseases may present exercise intolerance, seizures and cognitive decline, among other conditions. Some will manifest disease symptoms and some will appear as sporadic cases," said Cecilia Giulivi, the study's lead author and professor in the Department of Molecular Biosciences in the School of Veterinary Medicine at UC Davis. "Many of these characteristics are shared by children with autism."
>
> Dysfunction in mitochondria already is associated with a number of other neurological conditions, including Parkinson's disease, Alzheimer's disease, schizophrenia and bipolar disorder.
>
> Mitochondria often respond to oxidative stress by making extra copies of their own DNA. The strategy helps ensure that some normal genes are present even if others have been damaged by oxidation. The researchers found higher mtDNA copy numbers in the lymphocytes of half of the children with autism. These children carried equally high numbers of mtDNA sets in their granulocytes, another type of immune

> cell, demonstrating that these effects were not limited to a specific cell type. Two of the five children also had deletions in their mtDNA genes, whereas none of the control children showed deletions.[10]

In our MMSAutism webinar, Dr. Andreas Kalcker mentions that CD changes the mitochondrial membrane electrical potential.[17] This leads to increased power in every cell in the body, including immune system cells. The mitochondria are the electric generator or "powerhouse" of each cell. When we turn off this electrical generator, cancer can develop. If the cell cannot produce electrical energy through oxidation it will use fermentation.

In practice, what I have seen is that children who suffered from lack of energy, listlessness, and other symptoms that can be related to mitochondrial dysfunction have perked up with the use of CD. They are able to do exercise again, walk without having to be carried, and can cognitively sustain activities without tiring. You will see a few testimonials mentioning "mito issues" at the end of the book. It is wonderful to think that this is another means by which CD can help people on the spectrum heal.

ATEC Statistics

Through some of our Facebook groups we have been collecting ATEC data for the past year. Just to give you an idea of what others are experiencing in terms of test results, here are some statistics:

- 246 parents have given us 2 ATEC scores. Of those, the average drop between ATEC1 and ATEC2 is 15 points. We take ATEC data quarterly, so in general that drop is in three months or less. The more impacted a child is the bigger their initial drop – kids starting with an ATEC over 100 averaged a 26 point drop between ATEC1 and ATEC2.
- Of those 246 ATEC reports, we had 32 children (13%) gain in points in the first quarter. The average gain among those 32 was 7 points. All 32 reported ATEC scores three months later, and 29 of them dropped points between their ATEC2 and ATEC3 scores. Further, 13 of those 29 dropped enough points to put them at or below their ATEC1 starting number. Which means at the 6 month mark, only 19 out of 246 (or 7%) had gained points. 93% of children who do this protocol have improved their ATEC score at the six month mark.
- We have now had 163 parents provide four consecutive ATEC scores (encompassing one year on the protocol). Of those 163, the average ATEC drop between ATEC1 and ATEC4 was 24 points.

- Of those 163, a total of 9 or 6% reported an increase in ATEC score between ATEC1 and ATEC4. The average increases was 6 points. 94% of children who do this protocol have improved their ATEC score at the one year mark.
- In a Facebook group collecting ATEC data, we have 25 recoveries as defined by the ATEC dropping to 10 or under in a year. So we have a rate of 15% recovery as defined as ATEC score under 10 in the parents who have taken this protocol through one year.

Thus showing that the longer they are on the protocol the more points they lose.

Although we all would like to see "high level" statistical research done, this is no doubt a major step in the right direction, and demonstrates that the protocol does work. But, research takes money.

DOs & DON'Ts of CD for Autism Recovery

DO review all current supplementation that your child is taking and remove all supplements which contain any antioxidants including vitamin C, vitamin E, vitamin A, vitamin K, ALA, Coenzyme Q_{10}, and colloidal silver as these will neutralize the CD, rendering it ineffective.

DO consider removing supplements that include iron and vitamin B_{12}. These are principal foods for the parasites, which explains why many children are low in them. If you are seeing a chronic iron or vitamin B_{12} deficiency, revisit the parasite chapter. These levels should normalize when parasites are no longer consuming nutrients.

DO use the Baby Bottle Method in an eight-ounce glass bottle with a completely sealing lid and start at one drop, regardless of weight. Increase by one drop/day, until you reach the optimal dosage.

DO dose frequently throughout the day. The less time we leave the pathogens to proliferate the better. Do a minimum of eight doses a day, but try to get in more doses if possible. Go for 16 in cases of PANS/PANDAS and acute situations like colds and flu.

DO activate CD for the proper amount of time for the acid you use. HCI and citric acid both activate sodium chlorite in 60 seconds.

DO supplement minerals using ocean water.

DO completely avoid the following: citrus fruits, corn syrup, fruit juices, green tea, pineapple, vitamins C, E, A, and K. Only give coconut milk and coconut water a minimum of one hour after the last CD dose at night so they will have no chance of affecting the CD. Coconut milk and coconut water are very alkaline.

DON'T give fruit juice of any form—not fresh, organic, homemade or store bought.

DON'T give highly antioxidant foods including chocolate (cacao/cocoa), coffee, green tea, kombucha, citrus fruits, pineapple, mango, or kiwi. Berries (if you have to give them at all) can only be given at night, one hour after the last CD dose.

DON'T mix anything but water with your CD drops.

DON'T give CD with food.

DON'T use a vitamin C shower water filter—yes, there is such a thing to neutralize chlorine in tap water. Unfortunately, it also neutralizes chlorine dioxide.

CD Troubleshooting Checklist

Before you decide that CD isn't working for your child please take a look at following list of common errors. If it looks like you are doing everything right, but you aren't seeing gains, please, before giving up, use one of the support options shown in Appendix 17, page 521. You are NOT alone! We have a network of parents who are ready and willing to help you.

☐ Are you preparing your CD in a clean, dry shot glass, or other type glass container that insures both chemicals are mixing?

☐ Is the CD mixture turning yellowish brown? There should be a chlorine-like smell. If there isn't, something is not right. Perhaps you have bad or incorrect chemistry? Maybe the supplier did something wrong in preparing the solutions.

☐ Are you using the correct ratio of sodium chlorite to acidic activator drops? See chart on page 94 for the correct mixture ratio depending on the type and concentration you are using.

☐ Are you allowing the correct activation time before dilution with water after mixing the sodium chlorite and acidic activator? See chart on page 94 for the minimum activation time you must wait for the chemical reaction to occur.

☐ If you question the potency of your CD, then you may wish to test its strength. See Appendix 6, page 467 for testing information.

☐ Is your CD or activator cloudy or not changing color after they are mixed? If so, there is something wrong with one or both chemicals. Check with your supplier.

☐ Did you leave your baby bottle solution in direct sunlight? A brief exposure to light is no big deal, but if you left it in a hot car for an hour, it may have lost potency.

☐ Are you keeping the same baby bottle solution for too many hours? It should be used on the day it was prepared.

☐ Are you giving antioxidant supplements or a multivitamin containing antioxidants? Vitamin C, vitamin E, etc., should not be given. Cod liver oil and fish oil supplements in general have lots of antioxidants to keep them from spoiling. Make sure those are out as well. Mixing any of these will cancel out the effect of the CD—and the vitamin. You CAN give them a few hours apart.

☐ Have you checked all your labels of supplements and foods to make sure they don't contain antioxidants?

☐ Have you removed all juices and all citrus fruits from the diet (including oranges, pineapple, mango, kiwi)? Berries (if you have to give them at all) can only be given at night, no less than one hour after the last CD dose.

☐ Are you dosing CD 30 minutes apart from food, as a minimum (one hour is optimal, but not always possible)? Grazers do 15 minutes and we dose CD 16 times a day.

☐ Are you mixing anything with your CD, such as baking soda, juice, etc.? The only thing you can add into your dose of CD is more water!

☐ Are you using alkaline water to prepare your CD? Alkaline water kills CD. Some expensive water filtration systems are designed to produce alkaline water, which we must totally avoid!

- ☐ Are you breaking The Diet? Could there be dietary infractions at school or with relatives while you're not there?

- ☐ Are you dosing so high that you are detoxing your child too fast and getting a Herxheimer reaction? Some people need to increase every three days—NOT every day.

- ☐ Are your doses too low to accomplish anything?

- ☐ Are you giving too few doses of CD? We need a minimum of eight doses per day or more.

- ☐ Have you started the Kalcker Parasite Protocol? If you have done three Parasite Protocols (PP) it is time to start looking into supplements, chelation, HBOT, GcMAF, etc.

Frequently Asked Questions (FAQs)

Can I use less than one ounce (30ml) of water to administer a dose of CD?

One ounce of water, or more, is best. You can always add more water, but at least an ounce is the minimum per drop.

We have been on the Protocol and are at five activated drops of CD in the baby bottle. My son's "usual" autistic symptoms got exacerbated to the maximum. He has horrible constipation, stimming, scripting, and he seems to be in a bad shape. Our target dose is 15 drops. What should I do?

The general protocol is to wait with CD enemas and CD baths until one is at their full target oral dose. His negative symptoms are probably from reabsorption of toxins from his unpassed stool. You need to resolve his constipation to stop this vicious cycle. You can administer CD enemas and CD baths on consecutive days. This should help the constipation, and flush the toxins out of his system. Then, once he is stable you can resume slowly titrating up to full dose.

What should I do if my child can handle "double doses" (two ounces of the baby bottle) all day with no herxing?

If your child is taking "double doses" all day, then it is NOT a double dose—it's his actual dose! Depending on his gains and what else you are folding into your protocol you can consider going up from there.

Is 72/2 only if you have done the parasite protocol? We are full oral dose but won't do PP until next full moon.

You can do 72/2 protocol before the Parasite Protocol, but you must have reached full dose of CD.

We are really struggling to get in enough doses of CD with school. We do well to get in 8; we really need more (way, way more). Night dosing is not an option (he won't go back to sleep; our mornings start early enough around here as it is), nor is coming to school during the day to dose him (we both work). Advice?

Some parents are dosing every 45 minutes to get in their doses when they are with their children. However, we need to be killing pathogens around the clock. It is not possible to be effective at killing pathogens when we are giving them 16 hours without a dose of CD. You need to get 1 to 2 doses in before school starts. Then get the other 6 (ideally more) in after school is over and in the evening.

My child hates the flavor of CD. Can I give Stevia with CD to improve the taste?

We recently discovered that some brands of Stevia are compatible with CD, CDS and CDH (i.e., SweetLeaf® & KAL® brand)—it doesn't reduce the potency. However, past tests were not so positive. Some added ingredients may be why this was so in our initial tests. Try to use only pure Stevia or check with the Facebook groups on what others are using successfully.

SweetLeaf
Sweet Drops Sweetener
STEVIACLEAR
KAL
PURE Stevia
ORGANIC extract

Preliminary tests show that some brands of Stevia can be used with CD to improve taste without losing potency. The two brands we have tested in-house are SweetLeaf® and KAL®. Some of our moms report having successfully used flavored versions of SweetLeaf®.

When you say do two back-to-back baby bottles of 11 drops... you mean do a total of 22 drops in 16 hours? Correct? I'm going slowly up on oral CD because of behaviors. If I go from 11 to 22 drops overnight, won't he have strong detox and behaviors?

This is spread out over 16 hours or more, such that every 60 minutes it is the same amount. It is different than putting 22 drops in 8 fl. oz. Behaviors associated with bacteria (PANDAS/PANS) are often reduced with the tolerated dose spread over longer periods of time. Remember that CD is only active in the body for about one hour.

My child seems very uncomfortable. What should I do?

If you see a detox like this, stop dosing for the day. The next day, return to the last dose when the child was stable. Pathogens are dying and toxins are being released into the bloodstream on their way out of the body. This causes discomfort in some people.

How do you know if I should go past full oral dose of CD?

A Herxheimer reaction will be your biggest indicator if you have gone too far. If you have reached full oral dose and it seems like your child has plateaued, please schedule a consult with Kerri to discuss your options. Note: The full oral dose chart (page 101) is only a general guide and not a one size fits all.

Is an hour enough time to separate CD neutralizers from the CD dose?

CD is only active in the body for about one hour, however, supplements like vitamins A, C, E, K and ALA, CoQ10, and GSH (glutathione) need to be avoided. Also, orange juice, pineapple juice, and other high antioxidant fruits are a problem even after one hour. So, the best thing to do is eliminate everything that kills the CD. If not, it is pretty much like not using CD. I have seen it too many times and it's not worth it. Antioxidants destroy CD. There is no period of time that is safe to use antioxidants with CD.

I know you have to start the parasite protocol on a certain day of the month, but how about the first dose of CD?

You can start giving CD any day of the month. That said, it might be easier to start on a weekend, or a day when you will be with your child all day to make sure to get in all of their doses, and keep an eye on them to make sure they tolerate it well, i.e. no Herxheimer reaction.

What is 72/2?

72/2 is when you give a dose every two hours around the clock for 72 hours. We use a baby bottle and a half to get through the night hours. This can be added in once you are comfortable at your full oral dose and have added in enemas and baths. See page 115 for more information.

Do you recommend 72/2 for everyone?

Once a child is at 100% of their target oral CD, enema, and baths then they can do a 72/2 weekend. They are exhausting for the parents, but some kids do wonderfully. A lot of families get a nice boost. But, if you do a couple of weekends and you don't see anything afterwards, then forget it. The benefits are usually seen two to three days after the 72/2 is over.

My son suffers from constipation. Can I start the enemas before I get to his full oral dose?

Anyone who suffers constipation needs enemas right away. These can be combined with oral doses. Still start low and slow, but it is important to get the bowels moving with any detox protocol. When constipation is present, we do not wait to start enemas.

What is the maximum amount of water to use with enemas? How many times do you hold and release?

First of all, we don't encourage holding. Rather we do a fill and release, which is kind of a home colonic. If your child can hold for a few seconds without fuss, then great. The number of cycles depends on the results of each. If all you are getting out is water, you may be finished, unless the person is seriously constipated. The amount of water really depends on the individual's size and the number of cycles administered. My basic philosophy is: *Any enema is a good enema.* So, even if not much comes out, you are still getting some water and CD in.

Is it possible that my son has been getting rid of mucous after his CD enemas? What is up with the mucous? Why is it there in the first place? And, is it a good or a bad thing that it is coming out?

Mucous is always a sign of inflammation and can contain pathogens and parasites. Mucous gives a home to pathogens. The inflammation and mucous can be caused from the allergies and pathogens. It is common to see mucous come out in the beginning of the enemas since our children have so much intestinal dysbiosis.

What is a good enema method for a 17 year old boy? I am having trouble understanding the enema part of the book. The video in the file really helps, but I am having a hard time imagining doing it on my son. How do other people with older children do it? Can it be self-administered eventually? Kerri mentioned a gravity bag, so you don't have to keep changing syringes. Has anyone tried that? Where do you get the bag?

Here is some advice one mom gave to another mom on one of our boards:

My son is 14 and tends toward constipation. I had done suppositories in the past to help him have a bowel movement. So, I told him that the enema was "fanny medicine" to help him have a BM and make him better. I started with just showing it to him after a BM after I wiped him. Then, I just put it next to his anus the next day. Then closer every day. He was still constipated so just inserting the tip would help him poop and then later I was able to push the liquid with him standing next to the sink and it would run all down his leg. After several weeks of this, it was a full moon and he could not poop at all and was lying on his bed in pain. I said let's try it here because it will really help you. I got out a hundred towels and did it right there and he pooped. It was a slow process over two months but now we do them AM and PM always right after the shower. I counted over 20 feet (of parasites) coming out this last PP. And that is just what I could see. I don't dig, just pull out obvious ones that are a foot long. Main advice is keep calm with soothing voice and have tons of patience and keep telling your son how much you appreciate his patience too. I also tell him this will get rid of his autism. He is non-verbal but said with RPM that he is mad he has autism. Also, the soft tip is key. I use syringes because they go fast.

My son is not having daily bowel movements. What should I do?

Do CD enemas every day until the stools normalize to daily. If you absolutely cannot do enemas, use CD baths in high doses (50+ drops depending on the size of the tub). Ocean water in high doses will move the bowels as well. Castor oil also helps.

I am scared of the CD enemas. Will CD harm the intestinal lining?

CD stays active only for about one hour and can gently, but effectively remove biofilm and kill pathogens in the intestine. Our society has shied away from this healing method in the last few decades. However, CD enemas have been proven to be positive turning points in the treatment, time and time again. Lots of kids will actually ask for enemas, as they provide them relief and comfort. If you are nervous, apply an enema to yourself first. You will see it is no big deal, and feel more at ease applying one to your child. Some parents have shown their higher functioning children how to apply their own enemas, so no one has to be there, and to make them feel more comfortable.

What is the difference between colonics and enemas?

Colonics cleanse the entire length of the colon while enemas cleanse the lower part of the colon. Colonics involves multiple infusions of water into the colon, while enemas involve a single infusion of water into the colon (which can be repeated). With colonics, fecal material leaves the body via a tube. Colonics normally involves going to an office and receiving assistance by a trained colonics hydrotherapist, while enemas are free and done in the privacy of your own home.

I have never done an enema before. How do you administer it?

There are several positions that work well, but there will be one that works best for the individual. The enema instructions are on page 109. Some examples would be on all fours or lying on your left side on a towel, or a small child could lay across your lap.

Enema clean up question: What are we boiling? What are we spraying with *Everclear*? What are we throwing away?

After you are finished looking for worms you can throw away any plastic plates/forks you may have used. Pour boiling water on your specimen collector, enema nozzle and catheter. Then spray with *Everclear* grain alcohol. If you are using syringes, you may pour boiling water over them as well.

How far do I need to insert the catheter for an enema?

Not very far at all; one to two inches is plenty. The anal sphincter is about one inch past the anus. As soon as the catheter passes this muscle, it will hold it in place and there is no need to go further.

What is intestinal biofilm supposed to look like?

Biofilm is fluffy, cloudy, and mucousy in appearance. There are no rules on the color. It can look like pantyhose. But, it is usually mucousy and a cloudy whitish/grey color.

How far away should we be doing enema from food? If we miss the morning enema, can I give it right after lunch?

They can go together; there is no need to separate enemas from food. Any enema is a good enema.

I'm having trouble with my syringes (for enemas). One plunges really smoothly, but the other two are almost impossible to move. Do I need to grease them up somehow before each use? How do you clean them?

I use *Everclear* grain alcohol to clean them, but note, it will dry out rubber parts. You can use coconut oil to lube the plunger gasket.

Is it normal to see black specks coming out after using enemas? We saw white specks for a couple of days too.

Black specks can be heavy metals. Oxalates are known to bond to metals and would come out with metals. White dots are generally parasite eggs.

Does ocean water need to be refrigerated after opening?

No it does not, it is fine at room temperature.

If I harvest my own ocean water do I have to sterilize it?

No. Sterilizing is not necessary or desirable in our experienc—we don't want to denature it. Pouring it through a coffee filter to remove any potential particulate matter is fine. Do NOT use charcoal filters (such as a Brita® water filter), because they will alter the characteristics of the natural ocean water. Just make sure to collect the water far from any harbours or large river outlets.

I bought pure sea water in Australia. It sounds like a great mineral drink. Would this be beneficial for killing parasites or just putting goodness back into the body?

Actually, it does both.

How do I avoid feeding the pathogens?

CD kills pathogens. I would use CD to rid the body of pathogens rather than try not to feed them.

Is it possible to use CD, CDS, or CDH during pregnancy? If it is ok, how much can be used?

CD/CDS/CDH are not advisable during pregnancy or nursing.

Can I add CD to breast milk to the bottle to help the baby detox?

CD must be given in water. Mixing breast milk and CD will reduce or potentially cancel out the potency of the CD.

How many drops go in a CD bath?

It depends on the weight of the child (20-100 drops). If he is a little guy I might start at 10 or 15 activated drops and work up over the course of the following couple of weeks. The size of your tub also plays a part. The bigger the tub, the more CD you are going to need. See page 113 for more information.

I've heard that some people mix CD directly in capsules and then swallow them. Can we use that on our children?

NO! Not a good idea! Since many children with autism can't speak, they won't be able to tell you when the capsule gets stuck. CD needs to be diluted in water before taking as instructed in this chapter.

Can I use warm water instead of cold water to store CD and how long will it remain potent mixed in the baby bottle?

CD is a gas dissolved in water and therefore has to be preserved in a sealed container. If not, it will lose its potency, similar to how soda goes flat if the cap to the bottle isn't screwed on tight. Colder is better because the CD will gas out quicker at higher temperatures. If you have doubts about CD potency, get the Lamotte ClO_2 test strips to be sure. See Appendix 6, page 467 for more information.

Are purified, distilled and filtered water all the same thing?

They are different. However, we can use purified, distilled or filtered water. But, alkaline water should never be used!

Must the activated CD water mix be stored in a glass bottle, or is a no-BPA plastic bottle with an airtight cap ok?

I prefer glass to any plastic. Over time, chlorine dioxide can degrade plastic, and that means you or your child will be consuming it. Yes, the bottle needs to remain sealed. Plastic is acceptable for lids only! Metal lids should never be used because they quickly rust, even if covered with a plastic coating.

Is it a problem to transfer one ounce of CD to a steel bottle briefly before drinking it?

That is fine for a transfer, but I wouldn´t store CD in a steel bottle.

Is the GF/CF/SF "clean" diet essential to the CD protocol? My son doesn't have bad reactions and I just do not see how we could implement it.

A healthy, clean diet is very important to the healing process. Unfortunately, our "standard diet" is filled with preservatives, colorings, and other potentially harmful chemicals. When the goal is to heal, the diet is necessary. Dairy especially can cause inflammation and mucous production. Mucous provides protection to parasites.

What is a good CD-friendly multivitamin?

All multivitamins have antioxidants. What we need to supplement during detoxification are the minerals. Ocean water has 90 bio-available minerals, and it is what I prefer for this protocol.

Are there other specific foods, veggies or fruits that need to be avoided in addition to juices?

When you are following the CD Protocol, all antioxidants need to be avoided. Chocolate is a strong antioxidant. As far as vitamins are concerned; A, E, K, and ALA are off limits. High antioxidant supplements such as curcumin have also been a problem for many people. In the case of vitamin D, it is not an antioxidant, but it has caused aggression in previously calm children. Therefore, as a supplement, it must be used with care, if at all.

Vegetables and legumes which are high in antioxidants have not shown to be very detrimental to the effects of CD. However, citrus fruits, pineapple, mangoes must be avoided. Berries are best given at night, one hour after the last dose of CD, if you must give berries. Juice, any sort of fruit juice, is completely prohibited. Not only can the antioxidants involved kill CD, but the high sugar content (albeit natural) shuts down the immune system, which is already impaired in children with autism.

Can our kids drink anything other than water for the duration of the CD protocol or just not drink juices down with the CD?

Some people are not used to drinking water and find it difficult. Some people drink nut milks or rice milk. On occasion, some folks put a piece of fruit in the blender with an apple and blend it, strain it, water it down and have that sometimes. Juicing is taking 5 apples to make a glass of juice and that is a lot of sugar (albeit natural) as well as a lot of antioxidants. Antioxidants kill CD and sugar slows the immune system. You want to totally avoid alkaline water.

Can I use rice milk to give the CD instead of water?

Water is what we need to use to give the CD. If you are giving CD mixed with another beverage you are reducing its potential. By combining CD with liquids other than water we will not get the desired results. Rice milk might be okay, but you would need to test how it affects the potency of the CD. You can get the *LaMotte High Range Chlorine Dioxide Test Strips* (#3002) at www.amazon.com. This way you can see for yourself how mixing CD with any beverage affects its potential. However, I do not recommend putting CD in anything but distilled/purified water.

Can I give my child fresh pressed green juices (celery, kale, cucumber, apple)?

Anything that is very nutritious to the human body is nutritious for the pathogens/parasites. So, a healthy green drink is very healthy for the pathogens. If you are giving "green" juices make sure they are not loaded with sugar from apples, carrots, etc. In my opinion, it is preferable to avoid these for the first few months of the Parasite Protocol (PP), at least.

Can I use coconut and almond milk with CD?

You can drink coconut and almond milk 60 minutes after your last dose of CD, but I would not combine anything other than purified water with the dose of CD.

Can my child drink coconut water if he is taking CD?

If you want to give your child coconut water, give it one hour after your child's last dose of CD, at night, before bed.

Does lemon interfere with CD, even after it is cooked?

Yes, in some cases. A family of a child who suffered from SIB noticed a direct correlation with lemon use in their meals with the return of his SIB. I would avoid it at all costs.

My son barely drinks anything, especially all at once. This is why we have been unsuccessful with detox programs. Is CD different?

You should make sure that your child is well hydrated, but for the CD alone one ounce (30ml) of water is sufficient. I find that it is easier to drink CD cold rather than at room temperature. Also, if the smell is a problem, put the dose in a plastic syringe and squirt it right into your child's mouth. This prevents them from having to smell it before they swallow it. Enemas are a great tool for hydration.

My child's appetite has changed since starting CD. Is this normal?

Yes. On average larger kids tend to slim down, while thinner kids tend to gain some weight.

Can I give green tea or kombucha while taking CD?

That is out of the question in my humble opinion. Green tea is high in antioxidants and caffeine. Kombucha is similar. I don`t know exactly how long the antioxidants in either one are active in the body, so with autism, if we are looking for healing, avoid them both.

Can I use original Nutriiveda™ with CD?

Nutriiveda™ is derived from whey, a dairy product. In humans, all dairy causes inflammation and mucous, which provides a protective refuge for pathogens. That makes this product contraindicated for this protocol, plus it contains antioxidants.

Can I use Chia seeds with CD?

Yes. But do not mix them directly into the CD.

How do I dose my child when he/she is at school from 8:30 am to 3 pm? I work full time so "dropping in to dose" is not an option.

Give a dose upon waking, one at the door of the school at 8:30 and the third dose of the day at 3pm at the door of the school. The last dose of the day is at bedtime, there should be at least four hours between school pickup and bedtime to get in the other four doses. Once you get the hang of it, it is not that hard, it just takes a little getting used to and some prior planning.

What should I do if my son goes away for 5 days with school? Do you think it is possible to prepare a bottle of CDS for 5 days and he takes only one portion each evening?

It's not ideal, but better than nothing.

My son is refusing the CD. What do I do?

Have you tried adding more water with the dose, using cold water, using a syringe or a straw? Here is some advice from a Mom whose daughter refused oral CD:

We just went through a REALLY rough patch with my daughter when she absolutely refused to take oral CD, and I know it gets super stressful for both you and your child if you try to force it… I had to respect her as clearly she was telling me in her own way, "Mom, this does not make me feel good!" for whatever reason and after maybe a week we were back on track. During that time I was able to give her a few doses (dropped from 14 drops of CD to 5) here and there, during really good moments. For example, in the bath or swing that she loves and I think that helped her associate CD with feeling better again. You WILL be back on track in no time!!!!! Good luck! Keep calm and dose on!

I am on 30 activated drops/day with my teenage boy. The taste is simply horrible. He refuses to drink his doses. What should I do?

You can dilute your baby bottle as far as a liter bottle if necessary; it will not impact its effectiveness. Obviously, one dose will be more like a half a cup or a full cup in this case. However, be mindful of your conversion rate so that you get your dosage right. Cold water helps with the taste. You can add approved Stevia brands to cover the taste of CD. See page 126.

If the country I live in doesn't have glass baby bottles, can I use a plastic bottle?

No, do not use plastic for storing CD. If the cap is plastic, we can live with that. In almost any country you can find a glass water bottle (with a plastic cap). You can use a shot glass to measure out eight ounces, and even mark them on the outside of the bottle with permanent marker. Many parents in Venezuela do this, as neither glass baby bottles nor LifeFactory® bottles are available in their country. NEVER use a Stainless steel (or other metal) bottle or container!

Do you think this Protocol could work for a child who already has a low ATEC score (18)?

Yes. I started with a 12-year-old, who last February 2012 had an ATEC of 18. He did not budge from there after years of biomedical interventions. He could not stop with fears, phobias, anxiety (all parasitic in nature) and we started him on CD in February 2012 and the Parasite Protocol in June 2012. His ATEC is now a one!

My son's ATEC is not going down as I had hoped it would by now. It has hovered around 65 the past few ATEC's. I think it is probably due to the fact that if I am not home my husband often forgets to give him his doses or his PP meds. Does anyone have any suggestions on how to stress the importance of this protocol to him?

The following responses are from moms on our public Facebook group:

You will never know what following the protocol will do for your son until you follow the protocol. When I first started the protocol a little over a year ago, I remember I had been using a special juice that so many people were raving about and I was paying $140 monthly for this miracle juice and I really wanted to keep in in my son's protocol. I asked my husband to give it to my son at 4 am when he got up, and that was 4 hours before he would get any CD doses... how could that effect our results? The juice was given 4 hours before starting CD for the day, we were following the protocol exactly otherwise, and even doing the enemas. Well, nothing happened, nothing, until about 3 weeks later when I said, well let's stop the juice and see... BAM! Immediately my son's ATEC results dropped and he blossomed. I mean not only did his constant pacing stop, but his eyes lit up, he not only started talking more, more, more but even his laugh changed to a typical sounding teenager's laugh. It was incredible. His ATEC dropped instantly and kept dropping, 68, 25, 13, 7, 5, 3. It's a 6 today but this a super bad new moon for him. You will never know until you follow the protocol.

We have also seen our son stop pacing, stop suffering minute to minute, in the beginning we made our mistakes, missed a dose, didn't get this or that done, we now stick to it, the cumulative effect of staying on protocol means the difference in drops in ATEC scores and staying the same or going up, it did for us anyway. I could feel the slipping, we are still working on getting this right, it is an evolving protocol that requires the entire family's buy in. I have kept my son home from school to make sure he is dosed properly but that's just us. In November he is supposed to begin going to school full days, if they do not dose him correctly, I will hire a homeschool teacher, that's how important this is. You will not get your child well, Kerri told us 16 doses a day, he got better, she told us to start *enema's early, that made a big difference, we started our first PP before he was at full dose, it's all made a huge difference, email her, keep watching your child to see what's working, this protocol works, it may take time, but what is the alternative????*

My husband is not good about giving meds either. When I'm gone my older girls give it. I text them reminders. Sometimes setting a timer can help. I also set all of the meds that go along in a morning and night dose daily case. Often when I organize it all for them it's much easier for the meds to be given properly and in time.

My child has horrible nasal congestion. Can CD help?

Yes, you can use CD and make nose, eye, and eardrops. Put one activated drop of CD into one ounce of water. Use one drop of the mixture in the nose (eyes or ears) every 15 minutes till symptoms disappear. NOTE: DO NOT USE PURE ACTIVATED CD WITHOUT DILUTING IT!

You can also do a steam bath, which is done by closing off the bathroom (windows and door shut), and putting 20 activated drops on the floor of the tub. Run hot shower water on top of the drops until the tub fills; the air will be full of CD smell. Now, turn off the shower, put the child in the water to soak for 20 minutes, where he will breathe the light CD air.

Is there a seasonal-allergy protocol for using CD? I suffer from extreme itching in my eyes, redness, puffiness, sneezing, sinus congestion etc. Will CD provide relief quickly or does it need to be used over a long period of time?

Being on full CD, ocean water and the parasite protocol the allergies should begin to fade away.

Can I try the CD ear protocol if my child has not started oral doses?

Yes!! Please start the eardrops, if there is an infection, every hour until the symptoms disappear. If you catch an infection at the onset of its symptoms, give one drop of the mix every 15 minutes. We have seen earaches clear up in a couple hours. In any case, work towards a full oral dose, at least one drop eight times a day to combat the infection on all fronts. The eye, ear, and nose protocols are all the same: one activated drop of CD in one ounce of water in a sealed dropper bottle. Apply one drop of this mix every hour until symptoms diminish.

Can CD help arthritis?

Absolutely! CD is amazing for arthritis. Include CD baths in your routine. Use CD in conjunction with DMSO.

Our son has a runny nose and sneezes a lot, but has no fever. He hasn't been sick in well over a year! I'm wondering if it is from doing CD.

This sounds like a very typical die-off reaction. Monitor his progress, make sure he is hydrated, and continue with the Protocol. If his reactions remain manageable, you don't need to back down or change much. This could also be parasites, depending on whether the symptoms are chronic, etc.

Has anyone seen kids who had never been sick start getting sick as they heal?

Yes, it means immune system is waking up and fighting back against the crud they've been carrying around for a long time. It's called a healing crisis and is not uncommon and is actually a good thing.

Does CD, CDS or CDH work on HIV? Also, are there any contraindications of CD and HIV drugs?

We do not focus on HIV or its treatment and therefore we cannot give you a definitive answer. Anecdotally, there are many testimonials that indicate CD having a positive impact on the disease. In addition, we have spoken to doctors in various parts of the world who use CD to treat their HIV/AIDS patients and have positive results from what we understand.

Can I use CD in a Netti pot when doing an ear, eye or nose wash?

No. Do not use a Netti pot with CD. Instead, use the steam bath method. See page 114 for more information.

I´m wondering if CD can be used in a nebulizer? With our daughter's chronic mycobacterium issues, we can never get rid of the cough. I thought maybe it would be helpful to get it into her lungs or is this not safe?

Try a steam bath. Inhaling CD directly has to be done very delicately. This is why the steam bath is recommended, as the particles have time to disperse into a very large area rather than being inhaled directly. Some people are using humidifiers with 35 drops of CD per gallon. See page 114 for more information.

What supplements do I need to avoid while using CD?

Antioxidants (vitamins C, E, A, K, ALA, and CoQ10) need to be avoided because they kill CD. We avoid iron and vitamin B12 because parasites feed on these. So if you do not have something in place to kill pathogens/ parasites, like CD, then the majority of your supplementation goes to strengthening the parasites instead of your child.

I really don't understand something basic... Vitamin C in food. I know not to give citrus or mangoes. Also, kiwis are rather high in vitamin C. If my child eats a kiwi or other high vitamin C containing food, how long does this impact CD? When will it wear off?

Kiwis and other fruits high in vitamin C are a tough call. We do our best to avoid the biggest offenders. Unfortunately, I have seen families lose months because they continued to give fruit juice or supplements high in antioxidants. As soon as these were pulled, their children began to improve. A few years ago, a popular omega high in antioxidants became popular for autism. Families that I was helping all over the world noted regression in their children. As soon as we figured out what the common thread was, and pulled that supplement, the improvements began again, but it was a nightmare. To answer the second part of your question, I don't know exactly how long vitamin C from a natural fruit source lasts in the body. A few different websites estimate up to 24 hours.

We have been using gluthatione every day and modified citrus pectin as a binder. Are those compatible with CD?

Gluthatione is a very powerful antioxidant and cannot be used as a supplement with CD. Modified citrus pectin is fine.

I have heard that CD helps with oxalate problems. Is that true?

Rompepiedras (RP) is very effective against oxalate-crystal formation. There are connections between parasites and oxalate problems, which this protocol seems to be helping. Ridding the body of parasites helps with high oxalates.

I know that CD neutralizes heavy metals. What does that actually mean? What is the difference between chelating and neutralizing?

The mechanism of how CD neutralizes and removes heavy metals such as mercury is not clearly known (or understood). However, a number of recovered children have had heavy metal burden tests performed before and after the use of CD, and their heavy metal burden dropped. We also know of an adult in our circles who was extremely toxic with mercury and was able to normalize his levels after all other medical interventions had failed him.

So is CD enough and we don't need to chelate?

For many it is not necessary to chelate while on CD. There are some children though who do IV chelation and CD at the same time. This method seems to have good results; there are big metal dumps, when administering chelation challenge testing. As time goes by, we add interventions until we reach recovery.

Are all chelators compatible with CD?

In many cases there is no need to do both. To answer your question, EDTA is fine as well as DMSA and DMPS with CD.

You may want to consider Bio-Chelat™, bentonite clay or zeolite clay. These are great light chelators.

We have tried every biomed option available, but nothing has helped. What makes CD different?

Biomedical treatments in general provide large amounts of antioxidants. CD is an oxidizer and kills all pathogens in the body. The premise is that once your body does not have to feed and house pathogens, it will work much better and will heal. This protocol focuses on excesses and not deficiencies, which in itself makes it different from many other biomedical interventions. With CD and the Parasite Protocol we are eliminating the pathogens and parasites that cause the symptoms known as autism.

Most biomedical interventions seem to be only applicable to small kids. Does CD work on "older" kids, teenagers or young adults?

Of course! Families with older teens and adults have had success. The body wants to heal at any age be it 7 or 70! This year, two 17-year-olds lost their diagnosis through the use of CD as part of their biomedical protocols. A 32-year-old male is doing excellent on the Protocol as well. Time will tell, and parent/caregiver dedication is the key to success.

How long should I do the protocol to see if it is working for us?

Within 30 days you will know. If you do the Protocol 100%, and in the order laid out here you should see improvements. Some see improvements with their first dose!

Has anyone had an increase in PANDAS/PANS stuff while on CD? Our ATEC didn't budge this time around and it is mainly due to the OCD and other PANDAS stuff that has increased. I get in 16 doses on weekends, but not on weekdays—maybe I get in 12 on a good day during the school week. Has anyone done anything to treat this PANDAS stuff?

Parasites typically coexist with bacteria, so it is very important to treat bacteria and parasites at the same time. It is extremely important to get in 16 doses a day, whether you get in doses earlier in the morning, or send doses to school. Also, many children with PANDAS/PANS need to be treated month long for parasites. If you are giving a probiotic, you can try doing a period without it and see if you child does not improve. We must keep in mind that if you are seeing parasites coming out with the enemas, we may not be seeing gains until we have eliminated a good number of the parasites living in the body. The toxins that they excrete—living and dead—can also cause some of the behaviors we relate with PANDAS/PANS.

Has anyone seen elevated liver enzymes while on CD?

Liver enzymes will not be high from CD. I have watched people do the liver enzyme tests for two years and the kids are in the normal range. However, when they are dumping worms or doing parasite meds is when we may see the enzyme levels go up. Within a couple of weeks they go back to normal, in the handful of times that I have seen them go up. Mebendazole and Combantrin® are non-systemic, and therefore are not absorbed; they basically travel through the intestinal system and are eliminated in the stool and urine.

My son still has a lot of mercury (DMSA provocation). Is it possible that the level can go down from using this protocol? How long should I wait before testing him again?

It is very common for the heavy metal load to go down. If you want to do labs, you can do them in three to four months.

How young is too young for CD?

There is no age that is too young. If a baby is showing signs of cold/flu, etc., you can start with the baby bottle method, one drop in 8 fl. oz. of water, so they are getting 1/8 of 1 drop per dose. The protocols are based on weight.

Ok we have had my son on this protocol for 11 months now. We started at an ATEC of 82 and had a dramatic decrease right away. Our second score was 26! Now we have had 3 consecutive ATECs of 33, most points being in the speech category. Where should I go from here? More diet changes and or supplements? We have been GFCFSF for years, considering going grain free next. We already use omegas and ocean water, and have done nine parasite protocols.

It may be time to look into hyperbarics or GcMAF, as you have *The Diet*, CD and parasite protocol firmly in place. If these 2 options are not financially possible, you need to look at the speech supplement list. Go in order, and see if your child doesn't see gains from some of those. You can also look at chelators. Also, please check that your omega does not have any antioxidants in it, as that will be killing your CD.

Is it normal to see diarrhea in the beginning of the CD protocol?

I consider there to be two types of diarrhea. One is the water faucet, which we want to avoid. If you see water faucet diarrhea, stop for the day, and give a lower dose of CD the next day, when you start up again. The other type of diarrhea is loose, unformed stool, which is normal during detox. As the body is attempting to eliminate the excess toxins quickly, the digestive process will speed up, and not all of the excess water will have a chance to be absorbed through the intestinal tract, causing loose stool.

How do you move CD through inspections at the airport?

Don’t carry concentrated sodium chlorite and activator bottles into the cabin. They must go into your checked luggage. Make sure each bottle is tightly sealed. Double bag each bottle SEPARATELY and place at opposite ends of your luggage but not right up against the sides. You may wish to stick each bottle into a pair of socks as extra protection. Surround each bottle with plenty of clothes to insure they will be protected if the bag is roughly handled. According to TSA regulations, you can bring aboard up to 3.4 fl. oz., (100ml) of a liquid in your carry-on luggage, which can hold 3 doses from your baby bottle batch.

Can I use CD as a toothpaste? Should I use regular toothpaste in addition?

I use CD spray (ten drops of activated CD per ounce) on the toothbrush first. Then, brush the teeth, and follow with fluoride-free toothpaste. CD is great for healthy teeth, tongue, and gums.

Is it okay to go swimming when on CD? I worry about the chlorine.

They do have a molecule in common; however one has nothing to do with the other. Some doctors don’t let ASD kids swim in chlorinated pools. But, as far as taking CD goes, the chlorine in the pool will not deactivate the CD in your body, nor react with it. A child on CD can swim in a chlorinated pool, just as a child not on CD can swim in a chlorinated pool.

Can I give colloidal silver with CD?

No. Colloidal silver is active for up to 24 hours in the body, and will lower the potency of CD. Therefore the two are not compatible.

Where is the autism clinic in Venezuela?

Puerto Ordaz, Fundacion Venciendo el Autismo. Carolina Moreno is the president and one of my best friends. Her email is venciendoelautismo@hotmail.com. We have over 36 recovered children there. It is wonderful.

My son has been sick and has really bad diarrhea. Can we skip the enemas for a few days or still do them?

We don’t use enemas just for constipation, but for overall colon irrigation and health. CD kills pathogens in the colon, and thereby helps heal autism. As the sickness causing the diarrhea is most likely pathogen induced, CD enemas will continue to kill these pathogens and help your son get over this acute situation faster.

My daughter just drank undiluted CDS. What do I do?

First, get her to drink plain water right away. Next, give orange juice or vitamin C to neutralize the CDS. Give burbur or activated charcoal to mop up the toxins that were released. Considering the strong taste, it is unlikely she would have consumed very much.

Can CD be harmful?

In the past 3 years that families have been using CD for autism, we have not seen any children or adults harmed by using this protocol correctly. Liver enzyme tests, nutritional tests, metal porphyrins tests, etc., have consistently shown improvement in the health of the children. Since Jim Humble started using chlorine dioxide for health, no one has died from ingesting CD (or MMS). The story that is often shared around the internet from Vanatu, concerning a woman who unfortunately passed away, was not attributed by the coroner to be the result of ingesting chlorine dioxide. There was another case of a 25-year-old male who attempted suicide with 10g (nearly the contents of a four ounce bottle of sodium chlorite at 22.4% solution) of sodium chlorite (inactivated CD). He developed methemoglobinemia, which he received treatment for, but survived his suicide attempt. That said, as we have mentioned before... anything used incorrectly or recklessly can harm you. Water, table salt, etc. The reason we outlined the protocol in such detail is to prevent mistakes and help families use it responsibly to recover their children with autism.

Does clay or bentonite clay interfere with CD? How far apart should it be taken from CD?

One hour apart from CD is fine. I use diatomaceous earth about ten minutes apart from a CD dose.

Is ibuprofen ok to take while doing CD protocol?

We have never seen a drug that was contraindicated with CD. Always consult your physician for prescription contraindications.

Is it ok to add Epsom salts to a CD bath?

We do not use epsom salts baths in this protocol. We use CD baths. See page 113.

Is it ok to take SAMe (S-adenosylmethionine) with CD? I took out all antioxidants, but not sure about SAMe.

No, it contains magnesium and vitamin C. For a mineral supplement, we take Ocean Water. Vitamin C kills the CD. Magnesium feeds biofilm, and therefore is counterproductive to our goals of healing.

Can I use DMSO in a CD enema to help drive the CD into the parasites?

Warning: Never use DMSO in an enema! Never introduce it into the body rectally. If it is applied rectally, it will carry toxic fecal matter into the bloodstream through the intestinal wall.

How do I use DMSO?

Every chance you can, apply DMSO to a clean body for 20 to 25 minutes and let it soak in. Apply it to affected parts first then remove rings/jewelry to cover all parts of the hands. Allow it to dry while applying to another body area (i.e. right arm, left arm, right leg, left leg). Apply to clean skin with clean hands. Use natural fiber clothing if it is going to come in contact with the DMSO, which can dissolve synthetics. Dr. Stanley Jacob has proven that DMSO brings about healing of rheumatoid arthritis, and it is great for migraine headaches, etc. You can research his work at...

www.dmso.org

...or find a DMSO retailer at...

www.protocolsuppliers.com

The 99% pure stuff is best, but never use that strength on the skin directly. It must be diluted to 70% or less for topical use.

Does DMSO neutralize CD?

No, it does not. However, DMSO has not proven itself to be a tool for autism recovery. In general, we use it for self-injurious behavior (SIB). The "S" in DMSO (dimethyl sulfoxide) is "sulf" as in sulfur. Many children with autism have a spirochete (amongst other pathogens), which feeds on sulfur. We saw many setbacks when adding DMSO. It is used on a case-by-case basis.

Chapter 6

CDS
Another Way of Delivering Chlorine Dioxide

There is more than one way to skin a cat.
~ *Seba Smith*

In October 2011, I received an email from Jim Humble. After a visit with Dr. Andreas Kalcker, he had some fantastic new information for healing autism. Jim wanted me to fly to the Dominican Republic to see him yet again that year so he could share this new information.

The big news surrounded the creation of *Chlorine Dioxide Solution* (CDS)—a new method of producing and using chlorine dioxide; substantially different from the CD mixing process we were using (described in Chapter 5). Jim was excited about all of the great things that Andreas was developing.

Andreas was contacted by a cattle farmer who was frustrated by the health problems of newborn calves he was receiving. These calves were suffering from infections, diarrhea, ear problems, cysts, coccidiosis, bovine respiratory syndrome, etc. His yearly veterinary drug bill was around €28,000, not including the cost of feed. The farmer had heard about the wonders of MMS in humans and wondered if it might help his animals as well.

Andreas thought, "Sure! Why not?" However, he quickly learned that cattle were very different from humans when it came to their digestive system. Cattle digest through fermentation, which CD disrupts, so he had to find a way to bypass their digestive system and go directly to their blood stream. But, that idea had another big problem. The pH of standard CD was too acidic and therefore not compatible with the calves' blood stream. Injecting even dilute CD caused great pain and could result in damage to the veins. There had to be another way!

After much thought and research, Andreas came up with a distillation process to extract the chlorine dioxide—the key ingredient—from the CD mixture so it would not contain any sodium chlorite or acidic activator. He named the resulting liquid *Chlorine Dioxide Solution* (usually abbreviated CDS). Note: CDS can still contain trace amounts of sodium chlorite and whatever acidic activator used to produce it, but usually not enough to be an issue.

This new CDS solution was injected into the 800 cattle with very positive results. The animals health improved and the vet bill dropped like a rock.

In one case, the farmer called Andreas about a particularly sick cow. He advised him on a dosage, but apparently the farmer misunderstood the instructions and gave the cow 10 times the recommended amount. The result? The cow was a bit "high" with ears and tail standing up, but subsequently became healthy with no ill effects from the accidental overdose.

On the human side, CDS also solves the problem some people have with sensitivity to citric acid as well as the taste of CD. Not having the original chemicals (sodium chlorite/citric or hydrochloric acid) in CDS makes a big difference for some. Another advantage of CDS was a drastic reduction in Herxheimer reactions.

After a long weekend in the Dominican Republic, we went home with new information to try out with Patrick.

I began by swapping out drops of CD for milliliters of CDS. Initially, I didn't notice improvements or regression, but I did notice that Patrick was waking earlier and having a less profound sleep. After about 30 days of trying the new miracle I began to think that, "If it ain't broke, don't fix it." So we went back to the original CD that had given us all of the recoveries and improvements. Patrick went back to sleeping very well and I never looked back. I was a confirmed CD user and CDS, for me, had no obvious advantages.

A little over a year later, Jim was at our home, and on December 26th, 2012, his new assistant showed up from the Middle East to help him. She could be called the "CDS poster child." We differed on this topic right away. But, she was very insistent. She asked me why I didn't like CDS and I told her. So, she told me that I had been using "unstabilized" CDS and now they "stabilize" the CDS.

When the CDS is "stabilized" (with some sodium chlorite added back into the CDS liquid), it gives an extra kick, such that when the chlorine dioxide molecule oxidizes a pathogen, there is sodium chlorite on hand to react with the acid that is created by the death of the pathogen. The result is more chlorine dioxide released on the spot.

I decided to try stabilized CDS with Patrick. We arrived at his full dose based on tolerance. His sleep has been perfect. He sleeps as any pre-teen should—like a rock. And, he has great energy all day long. I can say that there was no noticeable difference over the four months that he was taking CDS, from the days when he took CD. However, he is a little bit "lighter," as if he has no cares in the world. It seems as if something that might have made him uncomfortable no longer bothers him. Little by little, a few families switched to CDS to see if their children did better, worse, or as well as they did with CD.

After a couple of trial months with about 20 families, I think that it is safe to say that CDS has its place in the buffet of different methods of chlorine dioxide administration. We still have the original CD, made with citric acid or HCl. Now, we have CDS and CDH (Chapter 7). Today, we no longer use stabilized CDS, as I feel that CDS is only for hypersensitive individuals and to be used only until they can switch over to CD or CDH. Whatever formula we choose, it will help to heal the body of unwanted pathogens, and helps with parasites as well as heavy metals. Each person is different, and it is up to us as parents to observe and decide which method of chlorine dioxide administration is best.

You are in no way encouraged to switch to CDS if what you're doing with CD is working for you. For some people it may be better, but as of now, only one of our recoveries has come from CDS—all the rest are from CD. Some children may try CDS and come to realize that CD is still better for them.

When to Use CDS

CDS is used when someone just can't get past 1 drop divided in 8 fl. oz., over a day without experiencing a Herxheimer reaction. This allows us to get past the road block and still detoxify the body. Eventually, we want to go back to the standard CD Protocol which I believe to be more effective.

This is not a common situation, but it does occur.

Making vs. Buying CDS

Most people are a bit concerned about making CDS since it involves a distillation process where you produce chlorine dioxide gas and then cause it to go into water. When Andreas first came up with making CDS, it involved two containers, a hose, heat and lots of ventilation. There are still lots of videos on YouTube explaining that original process. However, there is now a much better, easier and safer way to produce CDS at home. So, if you see a CDS making video or read instructions that talk about using a hose—forget it! The new process is much easier and safer and doesn't involve any heat nor hoses.

There are some online sellers of CDS, but the cost of it is high and making your own is simple. It just takes a little effort in learning the process and having the right equipment. In addition, by making your own, you will have a better understanding of the behavior of chlorine dioxide.

Some Important CDS Points

When it comes to CDS, it is all in the concentration of chlorine dioxide in water; measured in *parts per million*—abbreviated **ppm**.

When buying or making your own, the goal is to end up with a bottle of CDS having a concentration strength of 3,000ppm. This bottle should ideally be made out of glass and kept in the refrigerator. You never use this concentrated solution directly. It must be diluted.

When we say, for example, use 10ml of CDS, we mean mix 10ml of 3,000ppm CDS with whatever indicated amount of water, and use that diluted mixture for the indicated purpose.

Make sure you read and understand Appendix 6, page 467 which explains more about concentration and measuring ppm.

There are several names attributed to this new, better and simpler method of making CDS, such as:

- The Shot Glass Method
- The Overnight Method
- The New Method

There are some demonstrations on YouTube showing this new method along with write-ups on various forums. These methods use a plethora of different containers having different shapes and sizes. The specific tools used to produce CDS can have a significant impact on the concentration.

It should also be noted that the concentration strength is reduced every time you open the CDS source bottle as chlorine dioxide gas escapes the liquid and evaporates into the air space above the liquid. When you open the source container, some of the chlorine dioxide gas escapes. So, the strength of a half full CDS bottle can be substantially less than what you started off with when the bottle was full. This is similar in concept to a pop bottle that loses its fizz if not used up quickly.

To substantially reduce the evaporation of the chlorine dioxide gas, the CDS source bottle should be stored in the refrigerator, which stabilizes and significantly reduces the amount of CD gas escaping the CDS solution. But, no matter what the temperature, some gas will always escape and reduce the concentration each time the bottle is opened. A narrow neck bottle helps maintain the integrity of the CDS for longer periods.

It is better to store the concentrated source CDS in smaller 300ml bottles than keep it in a larger one liter bottle. That way you use up what is in one bottle faster with less concentration loss. A good storage bottle is shown and described on page 160.

The New CDS Making Method — The Basic Concept

First, let's go over the basic principles of the CDS making process and then we will go into details.

We start with two containers (both ideally made of glass). One container is larger and has some kind of a lid that can be tightly closed. The other is a smaller container having NO lid. The relative size of each container is such that the smaller container fits comfortably inside the larger container while allowing the lid to properly close on the larger container when the smaller one is inside. See page 151 for an example of a well-made glass kit distributed by wps4sale.com.

The large container is then partially filled with filtered/distilled water. The level of water must be low enough so as to not overflow into the smaller container if it is placed into the partially filled larger container. The photos on page 151 show the concept of the two bottles visually.

Now that you have the basic idea, let's make some CDS...

Using the Overnight CDS Generating Kit

The following directions assume you have the glass *Overnight CDS Generating Kit (1000 ml)* from wps4sale.com (as shown on page 151). You are of course not required to use their kit. However, based on our own experience of looking high and low for a good one, theirs has the key features:

- Made of glass
- Smaller glass fits inside of larger container AND 1000ml of water inside the big container will not flood into the smaller container once placed inside.
- Lid fits tight and no gas escapes during the chemical reaction time.
- Lid is plastic—NEVER USE METAL LIDS!

Note: There are plastic CDS kits that work. You may be able to find a combination of containers made of plastic but not glass where you live. In fact, I made a YouTube video where I show how to make CDS using a plastic container. Just understand that chlorine dioxide will deteriorate plastic containers over time, so it should be avoided. Even if you have to use a plastic jar to make the CDS, store the final product in glass. The less time the CDS is in plastic, the better! As for lids, we have no choice. Only use plastic lids. Metal lids will oxidize VERY rapidly! Even metal lids with a plastic coating on the inside will deteriorate.

Steps to Making CDS:

1. Start by pouring one liter of distilled or reverse osmosis water into the large glass container. The water should be around room temperature.

2. Place the empty dessert cup inside the large container making sure no water spills into the cup.

3. Measure 75ml of sodium chlorite solution (22.4% $NaClO_2$ in water) and pour into the dessert cup, while being careful not to spill any sodium chlorite into the water surrounding the cup.

4. Measure 75ml of 10% HCl or 50% citric acid solution and pour into dessert cup.

5. IMMEDIATELY screw on the lid to the large container while being careful to not jiggle the container which could potentially cause the CD solution



wps4sale.com sells this Overnight CDS Generating Kit that produces 1 liter of CDS at 3,000ppm from 75ml of sodium chlorite plus 75ml of activator. The only part not made of glass is the plastic lid. The glass dessert cup is sized just right to fit inside the larger glass jar with enough room left over for 1 L of water that won't overflow into the dessert cup.

---

to mix with the surrounding water. Make sure the cover is tightly screwed down so as to not have any leaks. If you smell chlorine dioxide (beyond the little that escapes while you are putting on the lid) then something is wrong with the lid and/or container.

6. If you did everything correctly you should see the CD solution turn a dark amber/brown within about a minute (see below) and notice that the water starts to turn a light yellow several minutes later. It is also normal to see bubbles form in the dessert cup. It is normal for the pressure to change during the chemical reaction. We find that citric acid produces a vacuum and HCl can produce a pressure at first and then a vacuum.

7. Cover the kit with a towel to reduce its exposure to light. It doesn't have to be in a pitch black location, but it definitely should not be in direct sun light. Feel free to check it from time to time and see how the colors change. Of course keep this kit out of the reach of children or anything that could disturb it. I keep mine in the cabinet overnight with a towel on it.

8. When the color in the dessert glass matches that of the surrounding water, the chemical reaction is complete. There is no harm in waiting a bit longer—nothing more will happen. This usually takes from 12-24 hours depending on room temperature and the strength of the acid used.



After the sodium chlorite and activator mix, the color will quickly turn a dark amber, almost black color (left). After about 12 hours, the color of the solution in the dessert cup and that of the water surrounding it should be identical (right), which indicates the chemical reaction has completed and the CDS is ready to be poured into a storage container.

---

9. Have your glass storage bottle(s) clean and ready to receive the CDS solution.

10. Before opening the kit make sure your work area is well ventilated. Perform the steps that follow outside or have the door and/or window open nearby. Having a fan lightly blowing any gas that escapes away from you is a good idea.

11. Slowly open the container being careful to not jostle it which could cause the CD solution to mix with the freshly made CDS. If the chemicals mix, you will have to start over again, so be careful! You will most likely smell the chlorine dioxide gas that was sitting in the air space when you first open it. This is normal, hence the need for good ventilation.

12. Slowly remove the dessert cup while being careful to not spill its contents into the CDS. Immediately dispose of the contents in the toilet and rinse off the dessert cup.

13. Now pour the CDS into the storage bottles while being aware that some chlorine dioxide gas will come out of the water into your working area.

14. Tightly seal the storage bottle(s) and place in the refrigerator.

Note: 10% HCl is the recommended activator when making CDS. However, you can also use 4% of HCl, but the reaction time will be slowed down. It may take as much as a full day before the color of the CD solution and the water match.

Dosing CDS

As mentioned earlier, CDS is particularly well-suited for unusually sensitive individuals who cannot tolerate even low doses of CD.

Start with a baby bottle filled with 8 fl. oz., of water and add 1ml of CDS. This will provide eight doses of 1/8ml. If all is well on the first day, increase to 2ml on the second day. Each day you increase by one milliliter. Increase the amount based on tolerance. If the person is having a problem with a certain level of CDS, then go down to where they were fine and stay there a few days before increasing again.

Tolerance is the key here. Once you can no longer increase you have reached that person's full oral dose of CDS.

Slowly Switching Back to CD

Once you have found the full oral dose where they are stable and cannot go higher, it is time to fold CD back in.

The goal of using CDS is not to replace CD, but rather do some fundamental detoxing so you can bring CD back and reach full oral dose of CD.

This is accomplished by taking out one milliliter of CDS and replacing it with 1 drop of CD. For example, if the individual can tolerate 20 milliliters of CDS, then an ideal transition would be represented in the chart on page 154.

Of course this chart represents an unlikely scenario where everything goes exactly as desired. However, it does demonstrate what we are striving for—switching out CDS for CD and continuing to increase the dose of CD as described in Chapter 5 (page 81).

To accomplish this process effectively requires careful observation of your child and making decisions as to when you can go up; when to hold; and when to back down.

Hypothetical CDS to CD Transition

Transition Day	CDS in milliliters	CD in drops	Comments
1	20	0	Last CDS only day.
2	19	1	Transition starts
3	18	2	Transition continues
4	17	3	
5	16	4	
6	15	5	
7	14	6	
8	13	7	
9	12	8	
10	11	9	
11	10	10	
12	9	11	
13	8	12	
14	7	13	
15	6	14	
16	5	15	
17	4	16	
18	3	17	
19	2	18	
20	1	19	
21	0	20	Transition completes
22	0	21	CD increases each day
23	0	22	
24	0	23	
25	0	24	

CDS Enemas

CDS enemas can be useful for sensitive individuals when starting the protocol. Follow the same enema instructions in Chapter 5, page 103, keeping in mind that 1ml of CDS has a relative strength of approximately 60% of 1 drop of CD. With that in mind you can work up to 40ml of CDS per liter of enema water.

Chapter 7

CDH - Going Beyond CD & CDS

"The progressive development of man is vitally dependent on invention. It is the most important product of his creative brain."
~ Nikola Tesla

This protocol is constantly evolving, and until every person with autism recovers, we will continue to search for things to add or tweak to the protocol so we reach that goal. A few months before the release of this second edition, I was made aware of a new method of CD preparation, known as *Chlorine Dioxide Holding (solution)* or simply CDH.

CDH can almost be described as a hybrid between classic CD and CDS. Where CDS has no raw material left in the final product, but only chlorine dioxide gas dissolved in water, CDH contains some raw material (similar to classic CD) along with the chlorine dioxide in the final product. This new process allows the sodium chlorite to react with the acid for a significantly longer period of time, thereby reducing much of the remaining amount of unactivated sodium chlorite and activator. Some people cannot tolerate citric acid so CDH is usually made with 4% HCl. Initial reports indicate that CDH is better tolerated than CD.

Another interesting benefit of CDH is that it appears to mix well with the permitted natural sweetener stevia (SweetLeaf® brand) without reducing the potency of CDH. This can help children who have an aversion to the taste of CD. Many families have also reported that they were able to increase their child's dose without producing a Herxheimer reaction, in contrast to classic CD. Older children and severely affected children have benefitted as well from the CDH preparation; you can read more about that on page 221.

Currently, this new method is being used by a relatively small group of families (around 70 as of November, 2013). Many of them are reporting that CDH continues to produce results for their children on the spectrum, and they are seeing even better things than before.

As with all new things, it is important to test with a diverse group of families over a long enough time period to make sure that gains are sustained. So we ask that you please keep in mind that CDH is literally the bleeding edge of this protocol. While we are excited to share a new option with you, the decision to use CDH must not be taken lightly. If you are doing well with classic CD you may never need to use CDH. Consider the old saying, "If it ain't broke, don't fix it." Of the 115 children who have lost their autism diagnosis, 114 have done so with CD and 1 with CDS. So far, 0 with CDH (4 months in use for ASD). I expect this number to change soon as we are seeing good things from CDH. Time will tell. Stay tuned.

Scott McRae, his wife Brenda, and Charlotte Lackney have been pioneers in developing the CDH method. The following section is written by Scott where he discusses how CDH evolved along with detailed instructions on how to prepare and use it.

* * *

My wife, Brenda, and I first learned about CD early in 2009, through Bhante Vimalaramsi, an American born Buddhist monk. He's now a very close friend of ours, and even as I'm writing this, I'm at a meditation retreat which is based upon his understanding of the open-minded, experiential teaching of the Buddha.

After receiving our first set of CD bottles from an online seller, we started by trying to get to 15 drops of CD activated with lemon juice for 3 minutes, twice a day, which was the protocol at the time. Though we gave it a good effort, we couldn't get past 6 drops before vomiting and having diarrhea, and this caused us to initially stop taking CD. Then, after moving to Jakarta, Indonesia (Brenda's home town), I experienced almost monthly illnesses, which I believe was due to being in a new and tropical part of the world (I'm from San Diego, CA), riding in public transportation twice a day and teaching in a school of over 300 students. After a year and a half of constantly being sick, I remembered our bottles of CD which we had fortunately brought with us from the US, and I started on Protocol 1000. By that time, *Protocol 1000* had been developed to be what it is now—3 drops of CD (activated for 20 seconds with 50% citric acid) per hour, 8 times a day—and so I decided to do the 3 week cleanse. By doing the cleanse, I experienced a huge improvement in my health. Not only did I immediately stop getting sick, but I also felt that my energy level had increased by about 25%! Obviously, I was excited by these great results and so was my wife because she had started taking CD again as well. However,

Scott & Brenda McRae from Jakarta, Indonesia

even though our results were great and our experience was far better than before with the old, "try to get to 15 drops twice a day protocol," we still were having some nausea and bouts with diarrhea when we took CD. This was especially true at the times when we felt the symptoms of a cold or flu and tried to take more than the 3 drops doses in order to overcome it. Still the results we were getting with CD on Protocol 1000 outweighed the nausea and diarrhea that we experienced and so we continued using it, especially when we felt some sickness coming on.

After taking CD for about a year in this way, CDS hit the CD world. Being the experimental type, I decided to give it a try. After searching all over Jakarta for the plastic tubing for a couple of days and finally finding it, I made our first batch of CDS. We both tried CDS for about six months but found it to be less effective than CD, so we stopped with CDS and went back to CD and Protocol 1000.

Nevertheless, there were 2 things I really liked about CDS: (1) it NEVER caused us any nausea or diarrhea, and (2) it was so easy to use since it was pre-made (no mixing of chemicals before each use). The main thing for me was not having any more nausea because I really disliked feeling sick. So, I started thinking about CDS and my experience with making it and I came to the conclusion that possibly, the reason why CDS wasn't nauseating was because there wasn't any unactivated sodium chlorite in the solution—it was just chlorine dioxide dissolved in water. I remembered that when I made CDS myself, even after the activation process had gone on for an hour in a heated condition, if I stirred or swirled the activation chamber bottle, more ClO_2 would still come out of it. This got me to thinking... if the chemical reaction between the sodium chlorite and the 50% citric acid solution used to make the CDS was still able to produce more chlorine dioxide after an hour in a heated condition, then surely the 24 drops that I was using to make my daily CD dosing bottle weren't being fully activated after just 20 seconds.

Therefore, I decided to increase the activation time and tried it out on myself first and then my wife (aren't I considerate?). We both found there was no longer a nausea problem, even when taking more drops per hour than we had ever taken before.

Since I was in an experimental mode, I decided to see if I could make larger quantities of concentrated CD all at once to make it more convenient. I mixed equal amounts of sodium chlorite and 50% citric acid in a bottle, let it activate for about a minute, and then added a specific amount of hot water to further encourage the activation process. In the end, I had a total of 140 ml of this concentrated CD solution. Later, I found that hot water wasn't necessary and that room temperature water worked even better because there was less CLO_2 gas lost in the process.

The finished chemistry was indeed very strong and still didn't cause any nausea, so I was compelled to post my discovery on the Genesis II Forum. I named it *7 Day Fridge MMS (CD)* because it provided a 7 day supply of Protocol 1000. The ingredients added up to 140 ml, so each 20 ml was 1/7th of the total, or a one day supply of "pre-activated" CD similar to Protocol 1000. This made taking CD every day really easy. Just pour out 20ml of the new concentrated solution into a water dosing bottle, and then pour out 1/8th of the bottle every hour into some water in a glass, and drink it.

The *7 Day Fridge MMS (CD)* method worked great for my wife and me. Others on the Forum also tried it and liked it. In addition, I gave it to some people at the school where I work to overcome their colds (usually overnight) as well as other diseases within a short time.

About 18 months later, Charlotte, my Forum friend, began testing the *7 Day Fridge MMS (CD)* process to determine the actual ClO_2 content using her *Sensafe*^{TM} Chlorine Dioxide Photometer. Over several months, we worked together to further refine the 7 Day Fridge method. The result of all of our testing and refinements is this new and exciting CDH product.

The final formula to produce CDH using the 1 Bottle Method came out to be:

22 parts water	91.6%
1 part sodium chlorite	4.2%
1 part HCl (4%) or Citric Acid (35%)	4.2%
Total Solution	**100%**

I believe this new way of making CD will be of great benefit to humanity because it will allow people to gradually double or even triple the amount of CD they can take with little or no stomach upset. By increasing their doses to higher levels, people will be able to overcome CD treatable diseases more quickly than ever before.

As with any new technology, more changes and developments are likely. For example, we now know that CDH tastes much better if activated with hydrochloric acid instead of citric acid.

Producing CDH Using the One Bottle Method

Making CDH is really quite simple. You can use any size of bottle, and produce any quantity you wish, as long as you follow the basic instructions and keep the proportions the same. However, before diverting into different quantities, it is recommended you follow these directions exactly to insure you have the process down correctly.

Note the following volume equivalents:

Fluid Ounce (U.S.) Approximate Equivalents

30ml = 1 fl. oz. US (2 Tablespoons)

660ml = 22 fl. oz. US

720ml = 24 US fl. oz. US

750ml = 25 US fl. oz. US

Equipment Needed

- One 750ml (25 fl. oz. US) glass bottle with an airtight cap. DO NOT use a metal cap (even if it is lined with plastic). The best caps are plastic or even a synthetic cork in good condition. A common 750ml wine bottle is ideal for this as you can get them colored to reduce possible UV exposure (the darker the better). But, a colored bottle is not absolutely necessary and using a clear one will allow you to actually see the chemical reaction as it turns from clear to yellow.
- Three 240ml (8 fl. oz. US) bottles ideally made of colored glass to protect the CDH from UV light (the darker the better), but colored bottles are not absolutely necessary. You can also use smaller bottles if you like—these are just used to divide up the resulting 720ml of CDH into smaller bottles to help retain the ClO_2 concentration while opening and closing the bottles during dosing. *Schweppes*™ sells 6-packs of Ginger Ale, Club Soda and Tonic Water in 10 fl. oz. glass bottles with plastic lids that are great for this purpose, and hold 300ml easily. Only the Ginger Ale is in a colored bottle (green), the others are clear.

Schweppes
GINGER ALE

- One measuring cup or graduated cylinder to accurately measure liquid in either milliliters or fluid ounces.

Ingredients Needed

Ingredients should be at room temperature—not cold. If CD and/or activator are right out of the refrigerator make your water warmer to offset, or allow ingredients to warm up before using.

- 660ml of distilled or purified water at about 70° - 90°F (21° - 32°C).
- 30ml of sodium chlorite (22.4% solution) near room temperature or slightly above.
- 30ml of 4% Hydrochloric Acid (HCl) or 35% Citric Acid ($C_6H_8O_7$) near room temperature or slightly above.

Note: The amounts indicated above add up to 720ml, while the wine bottle easily has room for an additional 30ml and more. Refer to the chart on right if you wish to produce a different batch amount.

The CDH Formulation Table and Different Acid Concentrations

What if you have 10% Hydrochloric acid or 50% Citric Acid (very common)? Or, you wish to use a different size of bottle? Not a problem. These acids can still be used. However, the formula changes accordingly.

The table below is a great tool for determining the formula for a given bottle size. To use the table, start by circling the size of the bottle you wish to fill in the left most column. Next look at the acid you have and its labeled concentration. Match that with one of the 4 options across the top. Below the matching acid/concentration you will find the 3 formulation numbers for water, sodium chlorite (labeled "SC"), and whatever acid you are using. Just go down the appropriate 3 columns to where the bottle size line intersects and you will have the numbers you need. Substitute these numbers in the following preparation instructions if your situation calls for it.

CDH Formulation Table

(Applies to the One Bottle Method of making CDH ONLY!)

SC=Sodium Chlorite / HCl=Hydrochloric Acid / CA=Citric Acid

Water Bottle (ml)	Hydrochloric Acid 4%			Hydrochloric Acid 10%			Citric Acid 35%			Citric Acid 50%		
	Water (ml)	SC (ml)	HCl (ml)	Water (ml)	SC	HCl (ml)	Water (ml)	SC (ml)	CA (ml)	Water (ml)	SC (ml)	CA (ml)
10	9.2	0.4	0.4	9.4	0.4	0.2	9.2	0.4	0.4	9.3	0.4	0.3
20	18.3	0.8	0.8	18.8	0.8	0.3	18.3	0.8	0.8	18.6	0.8	0.6
30	27.5	1.3	1.3	28.3	1.3	0.5	27.5	1.3	1.3	27.9	1.3	0.9
40	36.7	1.7	1.7	37.7	1.7	0.7	36.7	1.7	1.7	37.2	1.7	1.2
50	45.8	2.1	2.1	47.1	2.1	0.8	45.8	2.1	2.1	46.5	2.1	1.5
60	55.0	2.5	2.5	56.5	2.5	1.0	55.0	2.5	2.5	55.8	2.5	1.7
70	64.2	2.9	2.9	65.9	2.9	1.2	64.2	2.9	2.9	65.0	2.9	2.0
80	73.3	3.3	3.3	75.3	3.3	1.3	73.3	3.3	3.3	74.3	3.3	2.3
90	82.5	3.8	3.8	84.8	3.8	1.5	82.5	3.8	3.8	83.6	3.8	2.6
100	91.7	4.2	4.2	94.2	4.2	1.7	91.7	4.2	4.2	92.9	4.2	2.9
150	137.5	6.3	6.3	141.3	6.3	2.5	137.5	6.3	6.3	139.4	6.3	4.4
200	183.3	8.3	8.3	188.3	8.3	3.3	183.3	8.3	8.3	185.8	8.3	5.8
250	229.2	10.4	10.4	235.4	10.4	4.2	229.2	10.4	10.4	232.3	10.4	7.3
300	275.0	12.5	12.5	282.5	12.5	5.0	275.0	12.5	12.5	278.8	12.5	8.7
350	320.8	14.6	14.6	329.6	14.6	5.8	320.8	14.6	14.6	325.2	14.6	10.2
400	366.7	16.7	16.7	376.7	16.7	6.7	366.7	16.7	16.7	371.7	16.7	11.7
450	412.5	18.8	18.8	423.8	18.8	7.5	412.5	18.8	18.8	418.1	18.8	13.1
500	458.3	20.8	20.8	470.8	20.8	8.3	458.3	20.8	20.8	464.6	20.8	14.6
550	504.2	22.9	22.9	517.9	22.9	9.2	504.2	22.9	22.9	511.0	22.9	16.0
600	550.0	25.0	25.0	565.0	25.0	10.0	550.0	25.0	25.0	557.5	25.0	17.5
650	595.8	27.1	27.1	612.1	27.1	10.8	595.8	27.1	27.1	604.0	27.1	19.0
700	641.7	29.2	29.2	659.2	29.2	11.7	641.7	29.2	29.2	650.4	29.2	20.4
720	660.0	30.0	30.0	678.0	30.0	12.0	660.0	30.0	30.0	669.0	30.0	21.0
750	687.5	31.3	31.3	706.3	31.3	12.5	687.5	31.3	31.3	696.9	31.3	21.9
800	733.3	33.3	33.3	753.3	33.3	13.3	733.3	33.3	33.3	743.3	33.3	23.3
850	779.2	35.4	35.4	800.4	35.4	14.2	779.2	35.4	35.4	789.8	35.4	24.8
900	825.0	37.5	37.5	847.5	37.5	15.0	825.0	37.5	37.5	836.3	37.5	26.2
950	870.8	39.6	39.6	894.6	39.6	15.8	870.8	39.6	39.6	882.7	39.6	27.7
1000	916.7	41.7	41.7	941.7	41.7	16.7	916.7	41.7	41.7	929.2	41.7	29.2

Preparation Instructions

Follow the steps of mixing ingredients in this order (assuming you are using the 750ml glass bottle):

1. Pour 660ml of purified water into the 750ml glass bottle.
2. Add 30ml of sodium chlorite to the 750ml glass bottle.
3. Add 30ml of 4% HCl or 30ml of 35% citric acid to the 750ml glass bottle.
4. Immediately cap/cork the bottle tightly so that no ClO_2 gas can escape and give it a good shake to thoroughly mix the ingredients (and a few more times later on if possible).
5. Store the bottle in a dark place with a temperature of 70°F to 90°F (21°C to 32°C) for 12 to 24 hours or more (24 hours or longer if you're in a cold environment—below 70°F (21°C)).
6. After the storage time has passed, place the bottle of CDH into the refrigerator (not the freezer) and allow it to cool down for 3+ hours before opening it for the first time. The temperature of the solution should be no more than 51°F (10.5° C). Note: If you are using a significantly smaller bottle, cool down time can be reduced because the smaller volume of solution will cool faster.
7. Finally, pour the CDH from the 750ml bottle into the smaller bottles, cap tightly and keep refrigerated until ready to use. The smaller bottle are easier to dose from and they also help reduce the number of times gas can escape and reduce the potency of the solution.

Using CDH

The CDH is now ready for use. Each milliliter of CDH solution contains 1 pre-activated drop of CD. It can be used for ANYTHING that CD is used for; viruses, bacteria, yeast, parasites, heavy metals, enemas, tub baths, gums & teeth, skin care, infections, etc.

When used orally, each 1ml of CDH should be added to at least 30ml of water. You can add even more water if you notice slight throat irritation with higher doses. If taste is an issue, a little bit of stevia may be added to each dose to improve taste by sweetening it. Some of the moms are adding SweetLeaf® Natural Stevia Sweetener to their daily bottle and report no negative impact on ppm level.

Although CDH is strong, it has shown to be gentler on folks who have issues with nausea when using traditional CD. You should be able to start at whatever drop dose you were on with CD and switch to an equivalent milliliter dose of CDH and gradually increase to tolerance. Typically, people are able to take 2 to 3 times as much of CDH as traditional CD, without experiencing nausea.

The CDH bottle should be kept refrigerated and only taken out to extract doses. Since 720ml is a fairly large quantity that may take many days to finish, it's a good idea to take the 720 ml and divide it up into 3 smaller 240ml bottles (720ml ÷ 3 = 240ml) so you won't lose much of the ClO_2 each time you open the bottle. By doing this, you will conserve as much of the ClO_2 as possible. It's also easier to extract doses from a smaller bottle using a syringe or pipette.

Also, keep the CDH bottle out of direct or indirect sunlight to prevent loss of ClO_2. If you make a dosing bottle for the day, it's best to keep it cold, but it is not absolutely necessary.

A little note about taste: Most people who complain about the bad taste of CD, CDS or CDH (which does not have any taste at low doses) are actually reacting to the smell of the ClO_2 which can lead to developing a long-term aversion to any of the treatment solutions. So, if you can minimize the gas floating around your nose, you will have an easier time with drinking the CD, CDS or CDH dose. To accomplish this, Charlotte suggested avoiding the use of a cup or wide mouth drinking bottle. Instead, use a bottle with a small opening such as a common water bottle (preferably made of glass). Of course, if the smell doesn't bother you, this is a moot point, but at least you have this little trick if it does.

Well, that's all you need to know to get started on this great new way to make and use CD. May this new CDH formulation bring you and your family much health and happiness.

Scott McRae
Jakarta, Indonesia
November, 2013

* * *

We appreciate Scott, Brenda and Charlotte's contribution to the variety of ways to produce and use chlorine dioxide. Be sure to check the Facebook groups and forums for the latest developments on CDH.

Some of you may feel overwhelmed by what you just read. So, let me give you my "Easy-Peasy" single paragraph method of making CDH: I take a 600ml Lifefactory™ bottle, put in 550ml of water; add 25ml of sodium chlorite; followed by 25ml of 4% HCl (or 50% citric acid). Leave it 12 hours in a cabinet, after which it goes in the fridge for 2 or more hours. Done! ☺

Healing
the symptoms known as
Autism
Kerri Rivera
with Kimberly McDaniel
Healing the Symptoms Known as Autism
Kerri Rivera
With over 120 testimonials from around the world!

Healing & beating autism.

Chapter 8

Step 3

The Kalcker Parasite Protocol

> *All of our fathers had a treatment for parasites as a part of their cultural practice. We have gotten away from this because of our reliance on modern practice. We would do quite well to relearn the ways of our ancestors in this area and keep ourselves in relatively good health always.*
>
> ~ ***Chief Two Trees***

The word "parasite" comes from the Greek word meaning, "one who eats off the table of another." Parasites, to Ancient Greeks, were those who sat at another's table, and paid for their meal with flattery.

As I mentioned earlier in the book, a very interesting thing started happening with the CD enemas. What we had previously believed to be mucous or biofilm coming out with the enemas, turned out in many cases to be worms (helminths) (aka parasites)—in rare cases they were still alive and wiggling in the toilet! We believed the most common were *Ascaris lumbricoides* (roundworm). However, what we are now seeing more and more appear to be rope parasites, a potential new species of helminth discovered by Dr. Gubarev, Dr. Alex Volinsky, and coworkers (submitted January 14, 2013). DNA testing is the only way to definitively say, but at $25,000 USD for each analysis, with a minimum of 100 test cases, it is rather cost prohibitive at the moment.[1]

In addition to Ascaris and rope parasites, parents have also seen hookworms, pinworms, tapeworms, and flukes, among others. This is an extremely important piece of the puzzle for so many of our children. We have been led to believe that in first world nations, parasites are not a problem. This is absolutely not the case.

A well washed parasite. You can almost feel the texture.

Andreas Kalcker,
co–author of the
Kalcker Parasite Protocol

Miriam Carrasco Maceda,
co–author of the
Kalcker Parasite Protocol

I was honored to have Dr. Andreas Kalcker and Miriam Carrasco Maceda share a chapter from their upcoming book, *Parasites: The Silent Enemy*. Andreas explains the importance of lifelong deworming, and shares with us a protocol that has helped many children and adults become healthier; and for some children on the spectrum was the last piece added that led them to recovery. The version included here has been tailored specifically for children and adults with ASDs. The original protocol can be found at:

www.andreaskalcker.com/
index.php/en/health/parasite

Very few details have been changed, but it is important to note that the Parasite Protocol here is what has been proven to help many of our children on the spectrum, including many of the recovered children.

Thank you Andreas and Miriam for your valuable contributions to this movement, selflessly sharing your findings, and for always taking the time to help.

HOW TO DETECT AND TREAT A PARASITIC INFECTION

Parasitic infections are more common than most people think, and may or may not result in serious health problems. We may be infected with multiple types of parasites, which vary in size and location, on or in the body.

Parasites can be classified as either microparasites, such as malaria that are only visible under the microscope, or large macroparasites such as round or flat intestinal worms (roundworms, tapeworms, etc.). These can be seen by the naked eye, and can reach great sizes. Internal parasites are found, not only in the intestines, as is generally thought, but anywhere in the body, including the lung, liver, muscle, stomach, gallbladder, brain, blood, skin, joints, and even in the eyes.

In recent history, the great migratory movements of the human population via rapid transportation and widespread trading have shortened the distances that previously had separated people and diseases. Formerly localized diseases have thus become universal ailments. Parasites previously confined to very specific geographical areas now appear in other locations, far away from their initial homelands. Unfortunately, conditions typical of the lower socioeconomic strata, (under which a large percentage of the global population lives) tend to favor the transmission of diseases and parasites.

A high percentage of the world population suffers from infections by parasites, which the WHO (World Health Organization) estimates are responsible for 15 million child deaths annually. In addition to the great cost represented by deaths, chronic and persistent infections have increased as parasites have developed multiple mechanisms of evasion and resistance to specific immunity. This allows them to circumvent and cancel the host immune response.

Persistent parasitic infection in human hosts leads to chronic immune reactions, which can result in tissue damage and altered immune regulation. Ninety percent of the world population is infected with one or more parasites, and up to five different types may coexist in the same host.

This situation becomes dangerous when the internal balance within the host is upset, the number of parasites skyrockets, and the host begins showing signs of serious illness that may even result in death. However, in some cases, parasitic worm infections do not result in disease, in fact, a number of carriers are found to be healthy.

A really good look into a parasite. You can see the actual intestines of the parasite. Also known as a helminth.

The same parasite (as above) from a different angle.

Considering that most people are not even aware of their infections, parasites have become silent killers, claiming the lives of many unsuspecting victims going about their lives oblivious to the danger. Some doctors in Western Europe and the U.S. seem unwilling to even contemplate that we may be infected.

Taking into account the recent increase in travel, immigration, and trade across continents, it is not hard to see how the problem has now become magnified to an alarming level. Parasites, especially the modern "toxified" versions, may well be causing many of the rare diseases now becoming more prevalent, as well as other recently identified or growing problems such as chronic fatigue, fibromyalgia, and arthritis.

The most common verminosis (infestation with or without obvious symptomatology of disease caused by parasitic worms) is intestinal. People who have them not only suffer from a large quantity of lost nutrients (absorbed by the parasites), but also from perforations made by worms in the digestive tract that can open the door to various infections and possible autoimmune deficiencies. Intestinal worm infections are very common and can affect everyone, not only people with poor hygiene habits. Helminths (worms) are transmitted by ingesting the eggs or larvae of parasites, which then hatch in the intestinal tract.

A parasitic infection or reinfection can be acquired through one or more of the following avenues:

- From more or less direct contact with an infected person (fecal or sexual).
- From self-infection, for example, through anal-hand-mouth contact. By scratching the anal area, eggs can become lodged under the fingernails.
- From congenital transmission (mother to fetus).
- From commonly contaminated objects.
- From soil contaminated by human or animal excrement.
- From eating contaminated raw or undercooked meat.
- From eating raw fish.

In some countries, raw fish is included in traditional foods. We can avoid the consumption of the larvae or worms by freezing the meat or fish for at least twelve hours, depending on temperature.

A great photo of a dead parasite, believed to be the Ascaris lumbricoides, or possibly a rope worm in the "seaweed" stage.

A very good look at how long some helminths are. The more worms the people pass, the healthier they get, and the improvements come faster and faster. This child passed a lot of parasites in the beginning. Then after a few months was no longer passing them and now has an ATEC score of 5. Meaning, he no longer has the diagnosis of autism.

This is the parasite that measured 32 inches.

Another long, well washed parasite for the collection. The road to recovery is paved with many dead parasites. Adios Autism…

This is a 32-inch parasite that a young boy passed. He went on to have a great day after getting this out.

These are rope parasites as confirmed by Dr. Alex Volinsky.

60cm long worm (Oct 1, 2013) from child; 6 months on CD; 2 drops every 1-2hr; no parasite protocol; 1tblsp DE; 2-3 vials of Quinton.

This 33 inch parasite (aka "Chester") was discovered by a woman using the protocol on herself.

The bubble visible in this photo leads us to believe this is a late stage rope worm.

After passing this parasite, the child went on to have a fabulous day at school. It is so great to feel good and healthy.

The FDA recommends freezing and storing [fish] at -4°F (-20°C) or below for seven days (total time), or freezing at -31°F (-35°C) or below until solid and storing at -31°F (-35°C) or below for 15 hours, or freezing at -31°F (-35°C) or below until solid and storing at -4°F (-20°C) or below for 24 hours is sufficient to kill parasites. FDA's Food Code recommends these freezing conditions to retailers who provide fish intended for raw consumption. Note: These conditions may not be suitable for freezing particularly large fish (e.g. thicker than six inches).[2]

▶ From drinking contaminated water.

▶ From consuming contaminated vegetables or fruits. Often we eat poorly washed (parasite infested) vegetables or fruits. There is a common misconception that vegetables from organic farming are free from any problems, pesticides, or chemicals. The danger is that the eggs or larvae of the worms reach the farm soil through animal waste, decomposed forms of natural compost, and manure (fertilizer) added to the field. There are eggs, such as Ascaris lumbricoides, which can survive in soil under extreme temperatures for five years. It is very important to perform a thorough cleaning of fruits and vegetables, and never eat anything raw and straight from the ground, however healthy it may seem.

▶ From parasite infested animals. Parasitic infections are very easy to spread by contact with pets. Veterinarians are quick to insist upon the quarterly deworming of our animals, but there are steps we must take on our own to avoid contamination.

Parasites come in all shapes and sizes. Of course, they can also come out in pieces.

Suggested: Deworm your pet at least every three months for life, as directed by your veterinarian. During the first month, it should be done every week. Prevent pets from eating raw viscera. If animals eat raw meat or raw bones the best option is to freeze the food in advance for at least 12 hours (See citation above). If the deworming treatment is working, the animal will expel the worms in the feces or vomit, which must then be burned or buried, during the eight-day treatment.

Avoid being licked in the mouth by animals as they are in direct contact with feces, soil, and their own anus. When petting an animal, wash your hands with soap and water before eating or handling food, as the eggs of the parasites remain in the animal's hair.

- Do not walk barefoot or with open toe shoes in soil or sand.
- Avoid Hippotherapy (horseback riding)

Symptoms of Parasitic Infections

The different types of worms and toxic waste produced by parasites in our body may cause the following common problems:

Parasites come in all sizes. Some are very long. These get washed with hot water for photos. This way we get the best look at them.

Blood Disorders & Blood Parasite Diseases

Parasites absorb essential nutrients from the body, such as iron, vitamin B_{12}, and sugars, which may result in certain blood disorders. In addition, some diseases are known to be caused by blood parasites:

Blood disorders:

- Anemia
- Dizziness
- Hypoglycemia
- Weakness

Blood parasite diseases:

- African Sleeping Sickness
- Babesiosis
- Chagas Disease
- Malaria

Fatigue:

The toxic waste produced by the parasites themselves (including ammonia and psychoactive substances), can stress the detox organs and cause disorders of the central nervous system such as:

- Chronic fatigue syndrome (CFS)
- Cold in the extremities
- Dizziness
- Extreme weakness
- Internal cold
- Lethargy
- Low energy
- Night waking
- Restless sleep

Gastrointestinal Symptoms

- Abdominal pain or tenderness
- Blood in stool
- Burning in the stomach
- Chronic constipation
- Chronic diarrhea or diarrhea caused by poor absorption of food
- Colitis
- Cramping
- Cravings for greasy foods and sugary foods, lots of carbs and bread, fruit, fruit juices, alcohol, or vinegar
- Digestive problems
- Distended belly
- Eating more than normal but still feeling hungry
- Excessive bowel movements
- Fever
- Frequent vomiting and nausea
- Gas and bloating (noted after eating)
- Hemorrhoids
- Irritable bowel syndrome (IBS)
- Intestinal irritation
- Intestinal obstruction
- Leaky gut
- Malabsorption syndrome
- Mucous in stool
- Pancreatitis
- Passing a worm in stool

Growth Problems, Weight, & Appetite

Parasites usually live without being detected by the host. They rob the body of many of the essential nutrients in the food consumed. Many overweight people, who are infected with parasites, go hungry for lack of essential nutrients, causing them to eat in excess due to their parasitic infection. Furthermore, depending on the type of infestation, many people are malnourished and cannot gain weight. The following is a list of some possible symptoms:

In children:

- Poor growth
- Poor physical and intellectual development consistent with their biological age

In children and adults:

- Chronic burping
- Craving white flour products; cookies, cakes, pastries, etc.
- Feeling hungry after a meal
- Inability to gain or lose weight
- Long-term obesity
- Loss of appetite
- Obsession and/or compulsion to eat sweets or very specific foods (wheat, sugar, dairy)
- Ravenous appetite
- Uncontrollable hunger to eat more than usual
- Weight gain (specifically around the time of the full moon)
- Weight loss

Mood Problems & Anxiety

Toxins that are released by parasites can irritate the central nervous system. Anxiety and nervousness are often caused by parasites that migrate throughout the body. Some of the problems caused are:

- Anger and irritability
- Anxiety
- Confused thinking (brain fog)
- Depression
- Disorientation
- Forgetfulness
- Lack of coordination
- Mood swings

- Nervousness
- Obsession
- Restlessness
- Slow reflexes

Muscle & Joint Pain

Parasites can travel almost anywhere in the body. When they migrate to the joints and the muscles they can cause cysts and inflammation. These can often be mistaken for arthritis and/or muscle pain.

Toxins from parasites can also accumulate in the joints and muscle tissue causing:

- Chest pains
- Fibromyalgia
- Joint pain
- Muscle cramps
- Muscle spasms
- Numbness of the hands or feet
- Pain in the back, thighs, or shoulders
- Pain in the navel
- Rapid heartbeat
- Restless leg syndrome
- Seizures

Parasites in Children (including children with ASDs)

Parasites can be found in the body in asymptomatic and symptomatic stages. The former are usually found in adults. Symptomatic stages occur mainly in children, in whom we can often observe the following:

- Anorexia
- Anxiety
- Bruxism (teeth grinding)
- Cramping
- Diarrhea that alternates with periods of constipation
- Excessive Flapping
- Growth retardation
- Headaches
- Inability to gain weight
- Itching/Burning/Picking of the anus
- Nasal itching and/or anal urticaria (hives/rash)
- Nervousness and irritability

- Nose Picking
- OCD (Obsessive Compulsive Disorder)
- Rage
- Smearing feces
- Unexplained laughter or weeping
- Verbal stims
- Weight loss

Tapeworms, and some other parasites, have an affinity for B_{12} and iron. Therefore, lab results that show deficiencies in B_{12} and/or iron can be indicators of parasitic infections.[3,4] Due to its size, the tapeworm consumes enormous amounts of food that it obtains by taking the child's food. This can affect the child's normal development.

Treatment is simple, but it requires that the head of the tapeworm be removed, otherwise it will continue to grow. Tapeworm treatment is separate from this protocol and usually requires niclosamide. However, the only way to be sure the head has been removed is to identify it in the stool.

Respiratory Disease

The passage of larvae through the respiratory system or larval invasion in the lungs may cause symptoms such as:

- Acute bronchitis
- Asthma
- Drowsiness
- Dyspnea (shortness of breath; air hunger)
- Chronic/irritative cough
- Pneumonia
- Shortness of breath or respiratory failure

Sexual & Reproductive Disorders

Immune dysfunction as a result of a parasitic infection can lead to:

- Candida - yeast infections
- Cysts and fibroids
- Erectile dysfunction
- Fluid retention
- Male impotence
- Menstrual problems
- Premenstrual syndrome
- Prostate problems
- Urinary Tract Infections

Skin Disorders & Allergies

External parasites (lice, bedbugs, scabies, etc.) that penetrate the skin can cause itching, redness, and/or rashes etc. However, internal parasites can be responsible for skin disorders as well. Parasites create toxic metabolic waste, and because the skin is the largest organ, the body tries to eliminate them through it, resulting in many skin problems.

Some symptoms may include:

- Allergies (to foods, dust, mold, etc.)
- Anal itching
- Brittle hair
- Crawling sensation under the skin
- Dermatitis
- Dry hair
- Dry skin
- Eczema
- Eruptions
- Hair loss
- Itchy nose
- Itchy skin
- Jaundice
- Psoriasis
- Skin ulcers
- Sores
- Swelling
- Urticaria (hives; skin rash)

Sleep Disorders

The body reacts to parasites during rest periods because at night is when parasites are most active. Nocturnal awakenings are common, especially between 2 and 3am, when the liver tries to rid the body of toxins produced by parasites. This in turn may produce:

- Insomnia
- Teeth grinding
- Bedwetting
- Drooling while sleeping
- Sleep disturbances - multiple awakenings during the night
- Restless sleep

Other Problems Associated with Parasites

- Bad breath
- Blurred vision
- Body odor
- Breathing problems
- Chronic infections: viral or bacterial
- Circulatory problems, numbness in the extremities, difficulty in moving
- Cough or coughing up blood
- Difficulty swallowing
- Excessive salivation
- Fever
- Fluid build-up or retention during the time of the full moon.
- Low immune response
- Peritonitis
- Sensation of a foreign body or discomfort in the throat
- Swollen eyes
- Weight gain during the full moon.

Blood Analysis

The following markers may be present when a person is suffering from a parasitic infection or the resulting allergies:

- Anemia/low iron
- Elevated immunoglobulin (IgE)
- Elevated eosinophils (The eosinophil is a specialized cell of the immune system, more specifically it is a proinflammatory white blood cell. According to the Registry for Eosinophilic Gastrointestinal Disorders (REGID), their known functions include movement to inflamed areas, trapping substances, killing cells, antiparasitic, and bactericidal activity, participating in allergic reactions, and modulating inflammatory responses.)
- High ammonia
- High oxalates
- Low vitamin B_{12}

Measures in the Home Environment to Prevent Reinfection

It is important to treat all people and pets that live in the same environment to prevent someone from infecting others. Reinfection occurs via underwear, bedding, towels and household items such as children's toys or animals that have been in contact with eggs. It is important to wash all clothing that has contact with intimate body areas at a temperature not below 60°C (140°F).

All bed linen and underwear must be washed daily (or to the extent possible) while performing anti-parasitic therapy. Affected individuals should not share their swimwear with other members of the family, and should use a separate cloth to wash his anal area. It is best to sleep wearing both underwear and pants to avoid involuntary scratching during the night. This will prevent infection through anal-hand-mouth contact because by scratching the anal area, eggs can become lodged under the fingernails. Keep pets away from the place of rest of their owners, such as beds, sofas, blankets, and cushions.

Thoroughly wash fruits and vegetables in water and soak them in CD or CDS solution for a few minutes. Clean the sink with alcohol, as the eggs of many parasites are immune to the pH of normal cleaning products such as soap or bleach. It is important to note that parasites do not leave any kind of immunity behind in the host, therefore, once cured, the person who has suffered can suffer from them again. The only surefire method of killing the eggs of *Ascaris lumbricoides* is in water above 60°C (140°F) or with 96% grain alcohol (Everclear).

Evolutionary Cycles of Intestinal Parasites

Although there are many more, here is a description of the three most common types of intestinal parasites that can be found in developed countries:

Ascaris Lumbricoides **(Roundworm)**

Ascaris reproduce quickly, as a single female can lay up to 200,000 eggs each day. This parasite is very common, especially in damp conditions, and when hygiene measures are inadequate. It can affect the entire population, but mostly affects children, seriously disrupting their development and growth. It's so infectious that the WHO estimates that there are about 700,000,000 people infected worldwide, of which around 60,000 cases end in death per year, mainly children.[5]


i = Infective Stage
d = Diagnostic Stage
4
7
i
1 d
♀
♂
3
6
5
Feces
2 Fertilized egg d
2 Unfertilized egg will not undergo biological development. d
CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx

Parasite eggs reach the duodenum through the mouth of the host. Gastric juices rid the eggs of their shells and release the larvae. These larvae, which are highly mobile, penetrate the duodenal mucosa and migrate to the liver. From there, they continue their migration to the heart, reaching the lungs through pulmonary circulation, and finally become trapped in the pulmonary capillaries. Here, the larvae break the thin walls of the capillaries and penetrate the alveoli, bronchioles, and bronchi at which point they are able to travel up through the pharynx. Once the eggs pass the epiglottis (see diagram above), the larvae are swallowed such that they return to the duodenum, where they complete their maturation process. This process takes approximately two to three months to complete; therefore we calculate that to find ourselves completely parasite free, the initial treatment should be done for at least 12-18 months, possibly longer. From there on out, you may only need to follow a routine deworming two to four times a year.

Keep in mind that eggs are expelled through the feces (human or animal) into the environment where they can survive even in harsh conditions, favoring the persistence of the parasite. They are resistant to low temperatures, desiccation, strong acids, soaps, chlorine, formaldehyde (pH between 2 and 11.5), and can live in planted soils for five or more years, creating a "parasite hotbed" that makes them almost indestructible. Once dry, they are transported through the air, fly in air currents like dust that can be inhaled and/or swallowed. We have recovered eggs from nasal mucus, paper currency, potting soil, dust, and in indoor airborne particles, etc.

Taenia Saginata **and** ***Taenia Solium*** **(Tapeworm)**

Taenias reach humans when humans eat their eggs, by the consumption of tissue from infected cattle or pigs. In infected animals, the larvae are encysted in the muscle tissue. If the infected animal is consumed, development may proceed in the human digestive system. Humans are hosts for *T. saginata* (beef tapeworm) and *T. solium* (pork tapeworm). The tapeworm is considered to be solitary, because usually no more than four species are found in any one individual host. The danger of this parasite is that the larvae can migrate to the brain, or other vital organs (cysticercosis). Tapeworms may be detected by identifying segments in the host's stool that the worms discard as they grow. However, tapeworms may go undetected for many years, living asymptomatically within their host.

According to classification, they can vary in size ranging from 2 to 12 meters in length. They consist of a head called the scolex, which attaches to the intestine by means of suction cups, and a body consisting of repeating units called proglottids. A single Taenia can grow from 1,000 to 2,000 proglottids, depending on the type. A tapeworm produces an average of 720,000 eggs per day.

Pinworms (*Enterobius Vermicularis*)

Humans are considered the only host of what are commonly called pinworms (*Enterobius vermicularis*). This type of worm is the most typical in the family because it propagates easily. It is common for children to become reinfected in schools, through contact with others, or through anal-hand-mouth contact. Pinworms have an elongated shape, are whitish in color, and are about 1cm long. They inhabit the large intestine of humans. Female pinworms leave eggs around the anus. Once deposited, the eggs are infectious for a period of up to 20 days. Once in the intestine, it takes between five and eight weeks to develop into adult worms. The most important symptom is intense itching that occurs in the anal area, especially at night. In women, inflammation of the vulvar area is very common.

A pinworm infection is, generally speaking, not very serious. Unlike other parasites, they infect only humans. Transmission from person-to-person happens by handling clothing, bed sheets, towels, and environmental surfaces (such as curtains, carpeting) contaminated with pinworm eggs, which are so light that they are able to become airborne. A small number of eggs can be integrated into air particles that when inhaled follow the same developmental process as ingested eggs. Enemas are extremely useful in removing this parasite from the large intestine.

Graham's method is a simple method of detection. Just after waking and before a bowel movement, press a piece of tape against the anal folds. The tape will catch the remains of eggs and/or parasites that are situated there. With the naked eye we can see small worms no more than an inch long, but with a microscope, many transparent eggs from females and even other species may be seen.

The Importance of Lifelong Deworming

Once we begin the process of deworming, we should recognize that we must maintain this habit of cleaning for the rest of our lives to enjoy good health. It is common among people who have pets, to follow the recommendations of their veterinarians, and deworm their pets every three months. It is interesting to ask why family physicians do not give the same advice to humans. Perhaps some physicians ignore this information, or simply do not consider it important to eliminate these pests, which are just as harmful to people as they are for animals.

It is true that many parasites are not endemic or common outside certain climates, but human migration and global marketing of food products have facilitated the spread of many parasitic pests silently. It is important that we understand the lifecycle of each parasite, from birth to death including reproductive and death stages. This information is crucial for the complete elimination of the parasite. For example, in the case of intestinal parasites treated here with this protocol, some can live in the host for up to ten years, as in the case of a single Taenia, while others may remain in the host for a lifetime, reproducing again and again, as in the case of the pinworms or the well-known Ascaris.

The Kalcker Parasite Protocol & Lunar Cycle Timing

In the modern civilization in which we live, we have lost touch with much of the ancient wisdom of the past. One of the things we have forgotten is how the natural cycle of the moon influences many of nature's routines. This is especially true for the behavior of parasites. They are known to sync their life-cycle with that of the lunar cycle. Your child may demonstrate extreme behaviors on certain lunar cycle days… especially on the full moon and sometimes even the new moon.

Therefore, to maximize effectiveness, this Parasite Protocol is specifically timed to the lunar cycle. Appendix 10, page 477 provides an easy reference for you to look up the days to perform the Parasite Protocol, which is administered over 19 days—numbered 0 to 18—each month; starting three days prior to the full moon and continue during the waning moon. This period of the moon's cycle is very effective for deworming because many nematodes (parasitic worms) travel back into the intestine to mate at this time.

Length of Treatment

This protocol is not a one-time treatment. You should plan for at least 12 to 18 months to insure you have purged multiple parasite life-cycles and continue beyond 12 months if your child is still expelling parasites.

Building on CD

This protocol builds on what you have already learned using CD. During treatment, it is absolutely necessary to continue CD dosing, CD baths and CD enemas.

Tape Worms

This protocol is specifically designed for the deworming of large intestinal parasites, especially round nematodes such as Ascaris. It is effective for most nematodes, but may not be effective against tapeworms. In the case of infestation by Taenias, the recommended treatment is Niclosamide, the preferred medication due to its low toxicity.

Components of the Kalcker Parasite Protocol

This protocol uses some of what you have already learned and should already be doing, along with a set of ingredients you will need to have on hand before you start (shown in bold below). Here is an overview list of the items you will need to have on hand, and the items are described in detail on the pages that follow:

- Meal time (1, 2, 3)
- CD / CDS (4-19)
- CD Baths (20)
- CD Enemas (21, 22)
- Ocean Water (23, 24, 25) (see page 115)
- **Diatomaceous Earth** (26, 27)
- **Lepidium Latifolium Extract (Rompepiedras)** or **Chanca Piedra (Stone Breaker)** (28, 29)
- **Pyrantel Pamoate (Combantrin®)** (30, 31)
- **Mebendazole** (32-36)
- **Castor Oil** (37)
- **Neem** (39, 40)
- **Probiotic (usually THERALAC®)** (41)

Check the following website for the latest information on where to find these products:

www.ProtocolSuppliers.com

You may have noticed one or more numbers in parenthesis following each of the previous items, such as "(40)" for the probiotic. The timing of what to give when, is covered in great detail in the daily charts starting on page 198. These numbers match those found on the daily sample charts to make it easier for you to connect the dots and also be able to identify related notes under each chart. They have nothing to do with the quantity/dosing of any substance. The use of these numbers allows us to comment on specific items and when and where they come into play as shown on the daily sample charts.

We now detail each one of the items on the list above and discuss what you need to know about them and how to acquire them (including their associated numbers on the charts).

Meals (1, 2, 3)

Obviously meals are part of everyone's day. The purpose in mentioning them here is that many of the following steps are related to meal timing. Some actions or ingredients are taken before breakfast, others during or after.

In our example charts, we make some assumptions which include:

- Breakfast (1) is at 7:30am
- Lunch (2) is at 12 noon
- Dinner (3) is at 5pm

CD, CDS or CDH (4-19)

As you learned in Chapter 5, you continue to dose CD (or CDS/CDH) as before during the Parasite Protocol. Nothing changes in that regard with the Parasite Protocol building on top of those steps already in place.

The sample charts assume your child is going to school, and so you may not be able to administer doses of CD during his school day (7-12) unless you are home-schooling, in which case you are encouraged to give hourly CD doses, even if the total exceeds 8 for the day.

CD Baths (Optional) (20)

Our sample charts assume you administer a CD bath just before bedtime. See pages 113 for more information about CD baths.

CD Enemas (21, 22)

Ideally, give your child a CD enema in the morning (21) and another one in the evening (22). However, if your child is going to school, a morning (21) enema may not be a good idea due to the possibility of an "accident." Therefore, consider the morning enema optional, but the night time enema a must do! See page 103 for more information.

Ocean Water (23, 24, 25)

Supplementing ocean water minerals is important to support the body through the detoxification process. See page 115 for more information on ocean water.

Dosing:

(23) A dose of ocean water should be administered upon waking, but five minutes apart from CD dosing.

(24) One dose of ocean water immediately after school (or at lunch time if at home).

(25) One dose of ocean water, 15 minutes before or after dinner.

Diatomaceous Earth (DE) - Food Grade (26, 27)

Diatoms are unicellular plants that existed by the trillions in our oceans over 300 million years ago. They are encased by a cell wall that is made of silica. When diatoms die, this microscopic coating deposits at the bottom of oceans. Over time, they pile up in banks forming deposits thousands of meters in size. With the receding of the oceans, these deposits have been uncovered. Through compression, and ultimately fossilization, these silica deposits have given rise to a chalk rock called diatomaceous earth.

DE is an inert, nontoxic compound, which contains a number of minerals such as manganese, magnesium, iron, titanium, calcium silicates, and others. Properly ground, the skeletons of microscopic diatoms become sharp silica needles, harmful to parasites, fungi, yeast, worms, and amoebas. However, these needles are harmless to humans and other warm-blooded animals. Although it is safe to consume diatomaceous earth continuously, the best method (as with everything else) is to allow for periods of rest. During the 18-day treatment, take two teaspoons (5ml) twice a day.

Dosing: ½ to 1 teaspoon twice a day for smaller kids, 1 teaspoon three times a day for adults and bigger kids. Mix with a little water and drink. Given on days 1 through 18. DE mixes well with water but never dissolves. Stir the DE/water slurry vigorously and drink immediately before the DE settles to the bottom. Some people take heaping tablespoons in water, but larger amounts are not necessary. DO NOT take dry!

Note: In rare cases, DE can cause constipation, which can usually be managed by reducing the dosages to 1/2, 1/4 or even 1/8th of a teaspoon. If that doesn't resolve the issue, remove DE from the protocol and continue with all other directions.

Source & Cost: Search online for "Food Grade Diatomaceous Earth." Buy at least 1 pound and expect to pay about $20 more or less. Better yet, buy a five pound bag, which will reduce your cost per pound. DE does not expire or degrade, but should be kept in a dry container. Note: Diatomaceous Earth is often used as non-toxic element in pool filtration systems. You DO NOT want to use this kind of DE since it has been processed. Only get "Food Grade" Diatomaceous Earth!

Lepidium Latifolium Extract (aka Rompepiedras or Pepperwort) or Chanca Piedra (aka Stone Breaker) (28, 29)

1.7 fl.oz.
PEPPERWORT
natural extract
Lepidium latifolium L.
SoriaNatural
ROMPEPIEDRAS
PEPPERWORT
50 ml e/1.7 fl.oz.

50ml e
ROMPEPIEDRAS
extracto natural
Lepidium latifolium L.
SoriaNatural
ROMPEPIEDRAS
PEPPERWORT
50 ml e/1.7 fl.oz.

PHARM HERB PHARM
LIQUID HERBAL EXTRACT
STONE BREAKER
(Chanca Piedra)
COMPOUND
HERB PHARM
HERBAL SUPPLEMENT

Lepidium Latifolium (Rompepiedras) and Chanca Piedra (Stone Breaker) both break up hard substances in the body. The reason we use it in this protocol is two-fold: It breaks up the protective outer coating of parasites, and annihilates oxalates, which many of our kids have an abundance of because oxalates are produced by parasites.

Note #1: It is often simply referred to as "RP" in our discussion forums.

Note #2: If you are having trouble finding this particular ingredient, don't let its absence stop you from starting the protocol with all other ingredients.

Dosing: 15 drops for a 100 pound child mixed in with the diatomaceous earth/water. Use seven drops for smaller children.

Source & Cost: You have a choice of two herb extracts; Lepidium Latifolium Extract (aka Rompepiedras or Pepperwort) and Chanca Piedra (aka Stone Breaker). One US source is www.mightyguts.com, which sells a 50ml dropper bottle of Pepperwort for about $30. A primary manufacturer in Europe is Soria Natural from Spain that labels their product Rompepiedras, while they also have an English labeled box that says Pepperwort. They both show Lepidium Latifolium on the box.

Pyrantel Pamoate (30, 31) (Trilombrin/Combantrin®)

Pyrantel pamoate is a broad spectrum anthelmintic, which works by causing a neuromuscular block that produces spastic paralysis of the parasite, and its subsequent expulsion by intestinal peristaltic action, without excitation of the parasites or encouragement of their migration. Pyrantel pamoate acts over a short duration, and tends to be completely eliminated from the body in the feces and urine within three to four days. Pyrantel pamoate is poorly absorbed from the gastrointestinal tract, and approximately 6 to 8% total is found in the urine, with the remainder in the feces. The recommended dose is one daily dose of 10 mg per kilo.

Pyrantel pamoate is incompatible with the use of piperazine, because the two substances neutralize each other. Thus Pyrantel pamoate should not be combined with pumpkin seeds, which contain piperazine, or with antiparasitic drugs that contain piperazine in their formulation.

Dosing: Pyrantel pamoate is given only twice during one cycle of the parasite protocol; once during breakfast on day one (30), and again during breakfast on day five (31). Dose is based on weight and calculated by multiplying your child's weight in kilograms times 10mg of pyrantel pamoate. To make it easy, refer to the following chart:

Pyrantel Pamoate (Trilobrin/Combantrin®) Dosing by Weight		
Pounds	**Kilograms**	**Dose in mg.**
20	9	91
40	18	181
60	27	272
80	36	363
100	45	454
120	54	544
140	64	635
160	73	726
180	82	816
200	91	907
220	100	998
240	109	1089

Pyrantel pamoate (often just referred to as Combantrin®) is available in three forms:

- **Liquid:** where each milliliter contains a certain number of milligrams. For example, one available formulation contains 144mg/ml. So a 100lb child would take 3ml.
- **Tablets:** where each usually contains 250mg.
- **Capsules:** where each usually contains 250mg.

You will have to read the label or the particular product you acquire and determine the milligrams to use.

Source: Combantrin® is available by prescription in the US. Most other countries have it available over the counter.

The preferred source of pyrantel pamoate is a compounding pharmacy, as to avoid coloring and flavoring. If you are unable to find it without coloring/ flavoring then I would personally use mebendazole for the entire 18 days rather than risk giving your child an ingredient which may cause regression.

Note #1: Some brands of Combantrin® include mebendazole. You want the stand-alone Combantrin®!

Note: #2 Pumpkin seeds should not be consumed with pyrantel pamoate because they neutralize its effects.

Mebendazole (Vermox®/Lomper®) (32-36)

Mebendazole is a drug used in treating diseases caused by helminths (parasites of the gastrointestinal tract). This drug prevents the parasite from using glucose, which results in a decrease in energy and therefore death of the parasite.

Mebendazole is a non-systemic drug which means it is only absorbed, to a limited extent, in the gastrointestinal tract (approximately 5 to 10%). However, if it is consumed with fatty foods then more absorption occurs.

Approximately 2% of the administered mebendazole is excreted in the urine, while the remainder is excreted in the feces. The appropriate dose of mebendazole may be different for each patient as it depends on the type of parasite causing the infection.[6] The most frequently recommended dose is 100mg for children, 200 mg for adults, two times a day for seven of the first nine days of the Protocol.

Adverse effects from mebendazole are generally rare due to its poor absorption. However, it may cause nausea, vomiting, abdominal pain, and diarrhea. Normally these effects are in fact a result of the release of toxins from the very death of the parasite itself. Anti-parasitic drugs can be administered very effectively by diluting them in water, putting the mixture in a small bulb enema, and inserting the anally. This is especially suitable in the case of oxyuriasis (pinworms). Read more about this "implant method" on page 220.

Dosing:

Note: Indicated weights should only be considered a rough guide.

Small Children (20-40lbs.): Days 2, 3, 4, 6, 7, 8 & 9 — Take as little as 25mg of mebendazole with breakfast and dinner, and do NOT do a blitz on Day 9.

Children (41-70lbs.): Days 2, 3, 4, 6, 7, & 8 — 50mg with breakfast and dinner. On Day 9 they can take 50mg, 50mg and 25mg.

Adolescents (71-100lbs.): Days 2, 3, 4, 6, 7, & 8 — 100mg during breakfast and 100mg during dinner. Day 9 is "Mebendazole Blitz Day" where you administer ONE 200mg dose during breakfast; ONE 200mg dose at lunch; and a final 100mg dose at dinner.

Teens & Adults (101 lbs. and up): Days 2, 3, 4, 6, 7, & 8 — 200mg during breakfast and 200mg during dinner. Day 9 is "Mebendazole Blitz Day" where you administer ONE 500mg dose during breakfast and no dose at lunch or dinner for the remainder of the current cycle.

Source: Mebendazole is available by prescription in the US and over the counter in other countries.

Note #1: Some brands combine mebendazole with Combantrin®. You want the stand-alone mebendazole!

Note #2: Mebendazole is mostly sold in tablet form, but it is also available in liquid. DO NOT buy the liquid form—stick with the tablets! I have seen horrible reactions from the "inert" vehicles used in the liquid products.

Castor Oil (37)

Apollo
CASTOR
OIL

Castor oil is extracted from the seed of a plant called Ricinus communis ("Higuera del diablo"). Its seeds contain between 50-80% oil, which has a high content of ricinoleic acid, which has excellent laxative and purgative properties. Once you begin anti-parasitic treatments, spastic paralysis may occur in some parasites and many together may form a "knot" of worms that can cause intestinal obstruction. It is important to help your body purge them by using castor oil. Castor oil should be taken in the morning, two hours after breakfast and other medications. If your child goes to school they take it as soon as they walk in the door from school. A typical dose for a child is 1/2 tsp to 1 tsp, or up to tolerance. The adult dosage is 15 to 30ml (two tablespoons), two hours after breakfast and other medications. If you experience any intestinal distress, mineral purgatives such as Epsom salts, or vegetable purgatives such as senna leaves, can be used.

Castor oil is also available in gelcaps for those who dislike the taste.

Dosing: The amount to administer varies and really depends on the individual's tolerance. A good starting point is ½ teaspoon for smaller children and up to two tablespoons for larger children and adults. Only experimentation will determine the right amount, if castor oil causes diarrhea.

Source & Cost: Readily available in liquid form at most pharmacies in the laxative section. Usually under $10 for 16oz. Also available online.

Neem (Azadirachta indica), Caps or Tea (38, 39)

PREMIUM
Nature's Way
HERBAL
Neem
Leaves
100 Capsules / Certified 475 mg
DIETARY SUPPLEMENT
Recommendation: Take 2 capsules three times daily, preferably with food.
Supplement Facts
Actual Capsule Size

The neem tree is a great natural inheritance of mankind. References in Sanskrit scriptures and ayurvic medicine practices indicate the use of neem since ancient times in Hindu medicine. Even today, Hindus living in rural areas call the neem tree the "village pharmacy" for its ability to alleviate many diseases and is currently endorsed by authorities in India for its use in medicinal preparations. Neem is one of the purifying and detoxifying plants with the greatest potential. Neem has been used to combat all forms of body parasites, external and internal parasites alike. To prepare neem, boil four leaves (normally the contents of an envelope) in one liter of water for five minutes. Drink the tea throughout the day over the course of each parasite protocol.

Dosing: Neem is given each parasite protocol from day 10 through Day 18.

You have a choice of caps or tea. I prefer caps over tea because the taste is strong and unpleasant, so some kids will buck drinking tea.

Caps (assuming 475mg each): An adult takes six in a day, three times two caps at meal times.

Follow the directions on the bottle. Give a full dose for teens and adults 100 lbs. and over. Small children receive ¼ to ½ dose.

If using caps, give one dose during breakfast and one dose at dinner.

Tea: Give four doses throughout the day. Prepare a tea from the leaves, one tea bag in one liter of water (add stevia if needed to cover some of the bitter taste). One tea bag usually contains approximately four leaves. If using loose leaves, then make one liter of tea with four neem leaves. If using crushed leaves, then use approximately one slightly heaping teaspoon.

Neem Tea Dosing

Weight of Person	Total Daily Amount (To be split into 4 doses)
20-34 lbs	100 ml
35-49 lbs	200 ml
50-64	300 ml
65-84	400 ml
85-109	500 ml
110 and over	600 ml

Source & Cost: Neem capsules cost about $8 for 100x 475mg caps. Look in your local health food store. One popular brand in the US is Nature's Way®. BioPure™ sells a product called *Neem Synergy* which contains a few additional herbs that do not affect the neem.

Neem tea can be purchased in bags or as dried leaves.

THERALAC® (Probiotic) (40)

THERALAC
PROBIOTIC MASTER SUPPLEMENT
5+2
BIOTHERAPY
30 CAPSULES

TruFlora
Probiotics + Enzymes
ACID-PROOF

THERALAC® is a probiotic that should be given during the parasite protocol to help reestablish good gut flora. Ideally, it is rotated every other month with THERALAC® TruFlora®.

The key reason for recommending THERALAC® over other probiotics is explained in this paragraph excerpted from their website:

> *THERALAC® probiotics survive transit through the harsh acidity of the stomach and arrive alive in the intestinal tract. THERALAC's ACID PROOF™ technology utilizes sodium alginate from seaweed in a unique formulation that assures survival at pH 1.6 for 90 minutes, the most severe stomach acid conditions normally experienced. Other probiotics that claim acid resistance are tested at pH 2.5 – 3.0, or >10 times less acidic than pH 1.6 – not a fair test. THERALAC's ACID PROOF® technology is protected by US Patents 7,122,370 and 7,229,818. This technology goes beyond resisting stomach acid and involves keeping the probiotic cells together in a viscous alginate-gel moving in group-force, not as separate individual cells like other probiotics, deep into the intestinal tract while retaining key formula ingredients, LactoStim® and Sodium Alginate in close proximity.*

Dosing: One capsule of THERALAC® is given each and every night at bedtime, irrelevent of age/weight. This probiotic is also to be given outside of the 19 Parasite Protocol days.

THERALAC® can be given at the same time as CD if your child swallows capsules. However, if you are using the THERALAC® powder form then give it at least five to ten minutes after the last CD dose of the night. See their website for more information about the powder form.

Special exception: Some people do not tolerate probiotics, in which case we have no choice but to leave them out. In some of these cases, sauerkraut and fermented veggies may help to cultivate beneficial bacteria.

Source & Cost: Amazon carries "THERALAC® 30 caps by Master Supplements Inc." for $37.

Sample Parasite Protocol Daily Calendar

To assist you in understanding the Parasite Protocol and how it changes from day to day, we have prepared the following visual set of daily charts showing how all the pieces fit together. To prepare this set of charts, we made up the following times for example purposes only:

- Your child's awake time is between 6am and 10pm.
- Breakfast is at 7:30am
- Your child goes to school, which starts at about 9am
- School is out at about 2:30pm
- Dinner is at 5pm

As stated earlier, each dose or activity is labeled with a unique number. Those numbers relate to notes below each chart AND they match longer descriptive notes in the previous pages.

You are encouraged to copy/enlarge the blank chart in Appendix 9 (page 475) and workout your real-life schedule based on these example charts.

Refer to the lunar calendar (Appendix 10, page 477) for the exact days the protocol should be followed, as well as to get an idea of behaviors related to parasites around the full and new moon.

> After four years of biomed and no major gains, we decided to try mms/cd protocol. We started in April and are currently on our second parasite protocol. Initially, we were really intimidated by the enema part but realized if we were apprehensive our 7 yr old daughter would pick up on that. We told her that what we were about to do would help her feel better we gave her the iPad right before the procedure and a new fav toy (beanie boos) and she was game. After it was over she said "no more booboo in my tummy". We all cried. To make a three-month adventure short and sweet, her team at school cannot figure out how her fragmented speech has gone from 2-3 word utterances to long, drawn out sentences. Her expressive language and receptive have increased. Her auditory processing speed has quadrupled. The most amazing part thus far has been the increase in social skills. Or just the fact that she is interested in engaging. Socially she was nonexistent and is now at a four year old level. We just spent a week with family and she was saying hi and engaging without being prompted!!! She now has a million questions, wants to know when and where we are going and the sequence in which events will take place. All this from a girl who never asked questions before mms! STOP thinking about trying! Just Do It!! For the first time in seven years, I can hear the bells of freedom ringing!!!! Thank you Kerri Rivera !!!!!

Day 0 (3 days before Full-Moon)

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1											
8:00 AM		6										
8:30 AM												
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24							
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3											
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 0 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
40	Probiotic at the end of the day

Day 1 (2 days before Full-Moon)

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28	30				
8:00 AM		6										
8:30 AM										*		
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24					37		
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29					
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 1 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolium with breakfast and dinner.
30	Dose of Combantrin with breakfast
*** 37**	Castor oil 1 hour after breakfast or immediately upon return from school.
40	Probiotic at the end of the day

Day 2 (1 day before Full-Moon)

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28		32			
8:00 AM		6										
8:30 AM												
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24							
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29		33			
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 2 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolium with breakfast and dinner.
32, 33	Small Child Dose: 100mg Mebendazole with breakfast and dinner. Teen/Adult Dose: 200mg Mebendazole with breakfast and dinner.
40	Probiotic at the end of the day

Day 3 (Full-Moon)

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28		32			
8:00 AM		6										
8:30 AM										*		
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24					37		
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29		33			
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 3 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolium with breakfast and dinner.
32, 33	Small Child Dose: 100mg Mebendazole with breakfast and dinner. Teen/Adult Dose: 200mg Mebendazole with breakfast and dinner.
*** 37**	Castor oil 1 hour after breakfast or immediately upon return from school.
40	Probiotic at the end of the day

Day 4

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28		32			
8:00 AM		6										
8:30 AM												
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24							
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29		33			
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 4 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolium with breakfast and dinner.
32, 33	Small Child Dose: 100mg Mebendazole with breakfast and dinner. Teen/Adult Dose: 200mg Mebendazole with breakfast and dinner.
40	Probiotic at the end of the day

Day 5

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28	31				
8:00 AM		6										
8:30 AM										*		
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24					37		
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29					
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 5 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolium with breakfast and dinner.
31	Dose of Combantrin with breakfast (NO Mebendazole today!)
*** 37**	Castor oil 1 hour after breakfast or immediately upon return from school.
40	Probiotic at the end of the day

Day 6

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28		32			
8:00 AM		6										
8:30 AM												
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24							
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29		33			
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 6 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolium with breakfast and dinner.
32, 33	Small Child Dose: 100mg Mebendazole with breakfast and dinner. Teen/Adult Dose: 200mg Mebendazole with breakfast and dinner.
40	Probiotic at the end of the day

Day 7

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28		32			
8:00 AM		6										
8:30 AM										*		
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24					37		
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29		33			
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 7 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolium with breakfast and dinner.
32, 33	Small Child Dose: 100mg Mebendazole with breakfast and dinner. Teen/Adult Dose: 200mg Mebendazole with breakfast and dinner.
*** 37**	Castor oil 1 hour after breakfast or immediately upon return from school.
40	Probiotic at the end of the day

Day 8

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28		32			
8:00 AM		6										
8:30 AM												
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24							
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29		33			
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 8 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolium with breakfast and dinner.
32, 33	Small Child Dose: 100mg Mebendazole with breakfast and dinner. Teen/Adult Dose: 200mg Mebendazole with breakfast and dinner.
40	Probiotic at the end of the day

Day 9 (Mebendazole Blitz Day)

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28		34			
8:00 AM		6										
8:30 AM										*		
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM									35			
3:00 PM		13			24					37		
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29		36			
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 9 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolium with breakfast and dinner.
34	Blitz Day - Small Child Dose 1: 200mg Mebendazole with breakfast. Teen/Adult Dose: 500mg Mebendazole with breakfast ONLY!
35	Blitz Day - Dose 2: 200mg Mebendazole with lunch (or right after school) Teen/Adult Dose: N/A
36	Blitz Day - Dose 3: 100mg Mebendazole with dinner. Teen/Adult Dose: N/A
*** 37**	Castor oil 1 hour after breakfast or immediately upon return from school.
40	Probiotic at the end of the day

Day 10

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28				38	
8:00 AM		6										
8:30 AM												
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24							
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29				39	
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 10 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolium with breakfast and dinner.
38, 39	Start dosing Neem Caps with breakfast and dinner. If using tea, 4 doses throughout the day.
40	Probiotic at the end of the day

Day 11

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28				38	
8:00 AM		6										
8:30 AM												
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24							
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29				39	
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 11 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolium with breakfast and dinner.
38, 39	Neem Caps with breakfast and dinner. If using tea, 4 doses throughout the day.
40	Probiotic at the end of the day

Day 12

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28				38	
8:00 AM		6										
8:30 AM										*		
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24					37		
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29				39	
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 12 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolum with breakfast and dinner.
*** 37**	Castor oil 1 hour after breakfast or immediately upon return from school.
38, 39	Neem Caps with breakfast and dinner. If using tea, 4 doses throughout the day.
40	Probiotic at the end of the day

Day 13

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28				38	
8:00 AM		6										
8:30 AM												
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24							
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29				39	
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 13 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolium with breakfast and dinner.
38, 39	Neem Caps with breakfast and dinner. If using tea, 4 doses throughout the day.
40	Probiotic at the end of the day

Day 14

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28				38	
8:00 AM		6										
8:30 AM												
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24							
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29				39	
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 14 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolium with breakfast and dinner.
38, 39	Neem Caps with breakfast and dinner. If using tea, 4 doses throughout the day.
40	Probiotic at the end of the day

Day 15

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28				38	
8:00 AM		6										
8:30 AM										*		
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24					37		
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29				39	
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 15 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolium with breakfast and dinner.
*** 37**	Castor oil 1 hour after breakfast or immediately upon return from school.
38, 39	Neem Caps with breakfast and dinner. If using tea, 4 doses throughout the day.
40	Probiotic at the end of the day

Day 16

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28				38	
8:00 AM		6										
8:30 AM												
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24							
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29				39	
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 16 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolium with breakfast and dinner.
38, 39	Neem Caps with breakfast and dinner. If using tea, 4 doses throughout the day.
40	Probiotic at the end of the day

Day 17

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28				38	
8:00 AM		6										
8:30 AM												
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24							
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29				39	
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 17 - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolium with breakfast and dinner.
38, 39	Neem Caps with breakfast and dinner. If using tea, 4 doses throughout the day.
40	Probiotic at the end of the day

Day 18

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM		4		21	23							
6:30 AM												
7:00 AM		5										
7:30 AM	1					26	28				38	
8:00 AM		6										
8:30 AM										*		
9:00 AM		7										
9:30 AM												
10:00 AM		8										
10:30 AM												
11:00 AM		9										
11:30 AM												
12:00 PM	2											
12:30 PM												
1:00 PM		11										
1:30 PM												
2:00 PM		12										
2:30 PM												
3:00 PM		13			24					37		
3:30 PM												
4:00 PM		14										
4:30 PM												
5:00 PM	3					27	29				39	
5:30 PM												
6:00 PM		16		22								
6:30 PM												
7:00 PM		17			25							
7:30 PM												
8:00 PM		18										
8:30 PM												
9:00 PM		19	20									
9:30 PM												40

Day 18 (Last Day!) - Notes:	
1, 2, 3	Breakfast, Lunch & Dinner
4 - 19	At least 8 CD doses throughout the day, preferably more, at least 30 to 60 minutes away from food.
20	CD Bath at the end of the day.
21, 22	Enema in the morning (optional) and in the evening (mandatory).
23 - 25	3 doses of ocean water at least 5 minutes away from CD.
26 - 29	Diatomaceous Earth and Lepidium Latifolium with breakfast and dinner.
*** 37**	Castor oil 1 hour after breakfast or immediately upon return from school.
38, 39	Neem Caps with breakfast and dinner. If using tea, 4 doses throughout the day.
40	Probiotic at the end of the day

Parasite Protocol *Off Days*

Days "19" through to the next "Day 0" are "Off Days" where you discontinue parasite meds and herbs. Here's a simple chart showing what to continue doing and what to stop during this *off* time:

Continue with these:
CD / CDS / CDH Dosing
CD / CDS / CDH Baths
CD / CDS / CDH Enemas
Ocean Water
Probiotic

Stop these:
Diatomaceous Earth
Lepidium Latifolium
Pyrantel Pamoate (Combantrin®)
Mebendazol
Neem
Castor Oil

Of course this represents a hypothetical case and your situation may call for taking other meds or supplements.

Detection of Parasites in Stool

It is necessary to detect the parasites by observing the stool carefully. For that we use a small plastic basin, and a plastic stick or fork for examination.

Author's Note: One of the moms who is a part of our forum came up with some guidelines for processing your child's stool for parasite identification. She calls it, "Everything You Wanted to Know About Sorting Through Poop." Here are her suggestions:

Supplies:

- rubber gloves
- paper plates
- plastic forks (plastic sticks, chop sticks, or plastic back scratcher)
- a pen
- a coin
- toilet hat

I like to use a plastic "toilet hat" also known as a specimen collector or a specimen collection unit, which goes under the toilet seat and collects the stool before it sinks into the bottom of the toilet (available on Amazon.com).



The Collection:

When your child poops, it is collected in the toilet hat (specimen collector). After I get my child cleaned up and taken care of, I remove the toilet hat from the toilet and put the specimen on a paper plate with my plastic fork. I have a look for anything interesting and then transfer that part to a clean plate using my trusty plastic fork. I discard the remainder of the specimen into the toilet, flush and put that dirty paper plate in the bathroom garbage. (We now line with kitchen garbage bags, and I change it after each of these poops.) On the clean plate with the suspected worm, I may add a bit of water and swish it around to get the worm cleaner. I then may transfer the worm to a third plastic plate to get a clear picture. On the clean plate with the washed worm, I write the date, and the initials of the person the worm came from. If you need help identifying the worm, place a penny next to the worm (for size context), snap a picture, and mail the image to kerri@cdautism.org, (Kerri collects the photos for documentation purposes, so send those worm pictures). Then flush the worm and put all paper plates, gloves, and fork in garbage and take it outside. Now, you can go find out what your child has gotten into while you were doing all this.

Clean Up:

Use HOT water (60°C/140°F), and sterilize with 96% (180 proof) grain alcohol (Everclear).

Microscope

It is very useful to have a microscope for diagnosis because it enables you to see both the small parasites that may appear in the blood, as well as eggs or larvae in the feces. This way we are more accurately able to determine if the number of parasites decreases. A simple microscope that costs about $100 is suitable for this kind of identification. The easiest method to determine what you see is to compare your sample to images you find on Google. This way you can enlarge the images, see various samples from different angles, and get a much wider variety of samples than if you were comparing a sample with many textbooks.

Bulb Enemas (aka "Implant")

To prevent anal itching from pinworms, night wakings, etc., you can use a bulb enema or small catheter/syringe with a dilution of 50mg of mebendazole in 10 to 15ml of water for small children, or 100mg of mebendazole in 15 to 20ml of water for larger children/teens/adults. The best way to do this is to introduce the medication together with the water in the rectum immediately before bedtime and hold overnight. If you are using the "implant," a morning enema is mandatory.

So we did the 100mg of Mebendazole with 20ml of water. He kept it in and we did it right before bed... Next day a ton of worms came out!!! Better yet he started singing songs with a tune - 3 different songs over the last 2 days and counting on his fingers very purposefully! His aide at school said he did amazing today - no behaviors, very focused, better articulation and better social interest.

The Worm Whisperer

The following words of wisdom are from a mom who has earned the nickname *The Worm Whisperer* (although her ability to destroy parasites may make the *Worm Ninja* more apropos). Her dedication and diligence have not only made the difference in the life of her son, but countless other children who are what she calls "extreme cases." The information presented here may be the difference between an older/aggressive child living with their family or going to a group home for the care that their family is no longer able to provide them. Thank you Robin, for being a pioneer and for never giving up. Thank you for having the guts, the know-how, and the generosity to share what you have learned with those who need it most.

Extreme Cases by Robin Goffe

This section is for older children who may be violent, self-injurious, destructive, physically aggressive, high risk and/or bedridden.

Some families have children who are older when they first start treatment. My son was 18 years old. We call ourselves the "last chance" group. We say this because our children have lived their whole lives infested, unbeknownst to us. Our children lived as happy, relatively easily manageable, learning-disabled children: perhaps slightly annoying with their routines of movie dialogue scripting or attachment to Disney movies, maps, or little known facts. They were mostly friendless but pretty easy to take care of. However, during the hormonal teen years, things took a grave turn. We may have chalked up their newfound solitude to just giving up socially for lack of friends. They did not fit in. We had no idea that something else was brewing. The hormones within them began to have a bitter war with the parasites living inside them, and a war would soon break out. Their mental state would diminish considerably. What we are faced with are grown, strong children who are mentally ill and violent, self-injurious, and destructive. Some have even become so ill that they had to stay in bed.

This "last chance" is an opportunity to try ONE MORE THING before putting them in a group home; to give them away—for their own safety and the safety of their families.

These things that I am going to share with you are unique to the standard treatment outlined in the book. It is a more aggressive treatment because it is needed. Our children are so highly infested that it is shocking to tell you what we have found. There is a lot to do, but there is a method. It is time

The Goffe family.

consuming and it is a lot of work. But here I will outline what we did to get our son from an aggressive, self-injurious, destructive young man to one who has regained patience, language, understanding, and reasoning; but best of all, the opportunity to remain in our home. With continued treatments, he has the hope for a future: a job perhaps, and maybe even a family of his own.

Beginning treatment for the older child and especially one who is aggressive, self-injurious, violent, and destructive is one done starting low and slow.

Day one = one drop.

I kept a very detailed journal, and I will simply tell you what we did. I will tell you what worked for us and what did not. I will also tell you what I shared with others that worked for them as well. I am not a physician. I am not a chemist. I am a mother in love with my son and his utmost comfort was my main concern. My only goal was to clear his parasites. I had no idea that the things I learned by digging through his stool for 9 months would eventually give me the nickname, "The Worm Whisperer." Although intestinal parasites have been around longer than man, and they are smart enough to live within a human being lifelong, they can go completely undetected. I was ready to plot out a war against them. By the beginning of our 9th month of treatment, I estimate that I had cleaned and examined 35 pounds (16 KG) of solid parasites. Hard to believe? I have 80% of them photographed. The last two months in jars total seven pounds and a running total of the combined length will be at over 200 feet (61 meters), at the publishing of this book. There is not a classroom in the world that can teach what I learned in my bathroom day after day in latex gloves and a hospital mask. There was a fan blowing on me to manage the stench and by the third week my gag reflex was under control.

I examined the parasites, the pieces, how did it die? What was my son feeling at the time? Was he violent? Sweating? Slapping his legs from the pain of the parasites moving around and torturing him from the inside? I needed to eliminate these worms without allowing them to cause my son pain as they were killed. I had no idea the monsters I was to face.

In March of 2013, we started our son on one drop of chlorine dioxide. One of the most feared things that the parents of adult sized children face is the dreaded enema. It is just not something that most of us grew up with as standard care. But even so, my husband and I knew it was something that made sense. There are toxins inside these kids. They must be flushed out. The bowel is the way out. So on the very first day and the very first drop, we also explained to our severely autistic child that we were going to help his belly feel better. Our son, by this time, was so severe in regression that I can only best explain him as non-human. He was no longer speaking, unable to react to us, had stopped answering to his name, and could no longer contain the saliva in his mouth. He walked with a 12-inch drool hanging from his mouth. He ate like an animal, glaring at us. He was frequently violent: jumping on cars and denting them in, kicking down fences and destroying property.

This was the child that we were going to start giving enemas to. If we could do it, anyone can.

Each day we went up a drop; two drops on day two, three drops on day three, and so on. He was edgy and tired. We went for walks, as per usual, to deal with his aggression, but by day seven he began to have a runny nose and had a great deal of fatigue. We were so happy since we knew this was a sign to look for; that the immune system was kicking in. He slept for about 15 hours as we woke him and dosed him every hour and by the next morning there were about 25 white, hairy, thin looking objects in his stool. We knew these were worms and that we had our answer. After three weeks we began to see 4-6 inch parasites in all shapes and sizes, yet the aggression continued. It was here that I learned that what we were experiencing was POWS (Pissed Off Worm Syndrome). By this point we were at 13 drops, and while we were killing the smaller parasites, we were only pissing off the larger ones. The parasites do not like their environment disturbed, and subsequently they cause distress to the host. Parasites excrete ammonia, (possibly, leading to hyperammonemia and possibly seizures), morphine, and a meth-like substance. As these toxins enter the body, they can also cause aggression and anger. We had many possessions broken during these tantrums. We stopped valuing material objects.

It was here that we were told about—double dosing. So even though our son was getting about the equivalent of two drops an hour, if we saw increased aggression, OCD or self-injurious behavior we would give him four (see page 103 for an explanation of double dosing). If he did not calm down, we gave him another four drop dose. This was the perfect return attack for the parasites. Within a few moments the aggression settled. His red face and wild eyes diminished, and we had made it past another hurdle.

We used the double dose method dozens and dozens of times over the following months, and this helped tremendously to curtail the aggression caused by the parasites.

By the third week of treatment, we were concerned about the time during the night that our son would not be getting doses. So for the next six months our family had a dosing schedule, dosing additionally at midnight, 2am, 4am and picking back up to hourly doses from 6am to 10pm. This schedule was shared by not only my husband and I, but also our son's siblings,who would also set their alarms and take their turns, while we all rotated lack of sleep.

By the second month we found that our son's behavior not only changed around the full moon but the new moon as well. The standard protocol uses mebendazole over the full moon. However, with the older, more aggressive children we have had success with including mebendazole over the new moon cycle as well. These mini mebendazole courses feature shorter bursts of 5-6 days each, over the new and full moons beginning four days before each. We also deemed it necessary to start earlier in the moon phase than with the younger kids, since the infestation was greater, and the parasite movement occurred earlier, causing behaviors sooner.

For the child that has aggression, every parent must remember that the behavior is parasite related. During treatment you will see a variety of behaviors stemming from the parasites attempting to control their environment aka—the host. We found that increasing the frequency of the dose dampened the violence and aggression. It can be difficult to trust your child who is lost in a rage. You feel deceived and hurt. Those were our frequent emotions as well. It does pass. It took about 4-5 months for the rages to stop. They happened everywhere and were happening even on the toilet while trying to expel the parasites. Have a plan. Music worked very well for us. So did reading books. Find something to distract, and always give soothing, comforting tones. We frequently told our son how much we loved him and we rubbed his head and back. These herxing behaviors may be avoided through the use of a new method of preparing CD called CDH (see Chapter 7, page 155 for more info on CDH).

CDH: This new preparation method has really been a huge asset for the older kids that need to go higher in drops. At around 20 drops, the volume of the regular CD became unpleasant, making some children nauseous. My son was one of them. With the CDH preparation, I firmly believe that the older, tough-nut children will have more success with getting to the appropriate levels needed to start expelling the larger parasites. It is my personal belief that the amount needed in many of the non-seizure older kids with aggression, violence, self-injury, and destruction to be between 75-100ml of CDH daily. This amount may have a connection to the voltage needed in order for the mitochondria in the white blood cells to be given the power to not only kill the parasites, but to also destroy the bacteria. The job is two-fold, and must be done quickly as once the parasite is dead, the bacteria want to devour them immediately. I say these things because I have seen the condition of the parasites every day. I found that if I can kill the parasite with the least amount of disturbance or preparedness by the parasite, then there is no time for them to fight back and cause herxing. The bacteria also come into play and must be dealt with. Higher amounts of CDH kill both, without so much as a frown or a concern on the face of my son.

Stevia: I found that by adding the sweetener stevia to the CDH, the process can be more pleasant and does not affect the properties or effectiveness of the dose. As proven by Lamotte ClO_2 test strips (see page 467 for information on using the test strips).

Humidifier: In the beginning months, the infestation level is so high that nightly doses may have to be sacrificed in order to start breaking down the will of the parasites. It is not about seeing them every day, but slowly and consistently breaking their will. The constant aggressive irritation of the CDH will kill parasites, stopping them from making gains. There is another layer of nighttime treatments, and that is the humidifier. We fill a cool air humidifier that holds one gallon of water, and put 35 drops of activated CD (NOT CDH) and let it run all night near our son's head. This too was a method we used for maximum parasite elimination.

Spices and Herbs: It is urgent that we work constantly with our older kids to rid the body of parasites and pathogens. We have found that for kids that can easily swallow pills, filling empty gel capsules with the recommended herbs and spices in this chapter under Other Medicinal Plants (page 231) helpful. We have found great results by filling the gelcaps with the variety mentioned there: black walnut, ginger, rue, wormwood, and yarrow and giving two to four different ones with each meal as a toxic feast to the parasites. Don't narrow your selection to those mentioned here—get them all. There is no plan or pattern. Use any combination.

Colonics: Professional colonics have been an important addition to healing and cleansing parasites in our older kids. We started these a few months after our son was accustomed to the routine enemas. This has been a wonderful addition, and we try to do at least one weekly. Some places will allow you to do inserts, and we have taken our CDH there working up to 50-100ml CDH with great success.

Limiting Undesirable Behaviors

Probiotics: If you are using probiotics and your child is aggressive or becomes aggressive after restarting the probiotics, consider removing them as a first step. There could be such a high infestation rate that the child's system does not distinguish between good bacteria and bad bacteria.

Enemas: CD enemas should start on day one of treatment for the aggressive/older child. Since they have such a high rate of infestation, it is necessary to clear the pathogens on a continuing cycle from the very beginning. Please follow instructions for enemas starting on page 103.

Diatomaceous Earth (DE): In some children, the DE may shred the larger parasites to death, causing them to spew additional toxins into the child's body, which results in herx symptoms. Discontinuing DE for a few months may help to ease the distress, and give a cleaner kill.

Salt Baths: There are times that the body is unable to pull out the toxins fast enough. Be careful about killing too fast (dosing without or not enough enemas). If you have done enemas, and there still seems to be distress, you can buy a 40-pound bag of plain pool salt, take 9 pounds of salt and put it into a hot bath. Allow the salt to dissolve and have the child soak for one hour. If the child sweats during the bath, this is a good sign, as it shows toxins are being pulled out. Do not use Epsom salts. They contain magnesium. Magnesium feeds parasites as well as biofilm. Plain pool salt is cheap, and helps to remove toxins.

Dandelion Tea: This is an incredible detoxing source as well. There have been times that our son was in and out of a salt bath all day drinking dandelion tea to get the built-up toxins out. This is a tea ready made by Traditional Medicinals® (traditionalmedicinals.com).

Tips on What to Expect During the Parasite Elimination

Intestinal parasites have been on Earth longer than humans. Their plan is to find a host, and to continue to create life. They have the home advantage by living inside of your child. There are many things that I have learned while at war with them. They have a plan and so should you.

Situations We Have Come Across

Peetox: As you kill the parasites, they are alerted that you have taken away their joyful life. As a result, they do things to the host to show their displeasure. One of the things the parasites do is to spew toxins, including a morphine-like substance that can cause your child to not feel that he needs to urinate or that he is urinating. Naturally, this can lead to accidents. This is not the child's fault, but only a part of the parasite elimination process. One of the most difficult things we did was to put our 18-year-old son in adult diapers. It was heart breaking because it felt that we were moving backwards instead for forwards. However, this was only temporary, and for his own dignity. Especially if they go to school; perhaps being in diapers for a while is the answer. Our son was in and out of them for about two months. This does end.

Sleepytox: As you are going higher in drops, the CD is assisting the immune system to get the parasites out. It will take a lot of energy to do this. Remember, your child is the host and there is a war going on! Sometimes, your child may be tired for days. Our son slept for nearly the entire summer at the beginning of his treatment. Allow the rest they seek. Now our son gets higher doses of CD on the weekends, and he is very tired and sleeps then, too. By Monday morning, we can usually get a big fat rope worm after our efforts. Sleepytox is great because you can get a lot done on your home "to do" list.

Behaviors/OCD/Tics: Some may become alarmed because their child starts having behaviors that they did not have before treatments, or they feel that the behaviors have gotten worse. Parasites have a plan. It is to stay alive and to procreate. They want their eggs to return back into a host to repeat the cycle. So, you may see behaviors of playing with feces, touching their anus to their mouth, trying to put their fingers into your mouth or another person. There are finger and nail chewing, and spitting. These are all parasite controlled behaviors. We have found that eliminating parasites helps to minimize this behavior and it will eventually subside. There may also be a mineral deficiency attached as well. We have found that giving PLENTY of ocean water can help to tame these behaviors. Our 19-year-old son gets over 200ml OW mixed with 400ml spring water per day.

POWS (Pissed-Off Worm Syndrome): POWS presents itself when you have been dosing, and your child seems weepy, is pacing, and/or unhappy. Sometimes it is really that you have pissed off the worms, but are not killing them. Always check with Kerri regarding your concerns. But many times the answer is to go up in drops not down. You need to kill them—not piss them off, or they will fight back.

Clear Zone: This time period can be about five to seven days before the full moon; once infestation is brought down after six months or more of treatment. You may be able to start seeing glimpses of your child being lucid. This is a good time for an ATEC test.

High Volume Eating: Often times, the kids reach a point where they realize that they have been starving. The parasites have been taking a bulk of their nutrients, causing their mental deficiencies. They may even be eating non-stop all day. It is tough to juggle the timing and effectiveness of the CD with the continued eating. Allowing the child to eat high volumes of food while dosing with CD will still kill the parasites, but the CD levels may not be high enough to avoid a herx. Though the parasites may be killed the CD level may not be high enough to also kill off the bacteria eating the dead parasite. One solution we found was to give our son homemade bone broth with ocean water many times a day. This will help to replace the lack of nutrients, meanwhile reducing the overeating enough to continue the CD without risking a herx reaction.

Weight Loss: Our son lost 50 pounds during the first seven months of treatment. He was very over weight at 5’9” and 200 pounds. The weight loss brought concern to people who had not seen him for long periods. During this time I estimate that 35 pounds was solid parasites. His stomach was very bloated, as was his face. Our children are full of parasites and pathogens (i.e., yeast, bacteria, etc.), and all of these things can make them gain weight or be bloated. Our son is now in the normal weight range for his height, and has a flat stomach.

Night Terrors: During the night you may see that your child has trouble settling down, or they may wake in the night screaming your name. They may even do night walking, possibly leaving out the front door in a sleepwalk state. We saw these behaviors years ago, as our son was heading into a higher infestation level. Now that we are on the healing end, many of the behaviors return as sort of a rewind. The behaviors that came into play going down the ladder are sometimes repeated heading back up the ladder to wellness. We feel that our son was experiencing separation anxiety, and the recognition that he had total control again. This new gained independence may be frightening. At a point, our son entered the peetox stage (see above). He had no feeling or sensation to urinate, so he was put into adult diapers. As our son's infestation rate decreased, the normal behaviors like waking in the night and feeling the urge to urinate returned. Then, as he would get up to go to the bathroom, he would suddenly stop, and feel perhaps lost and afraid to continue this task alone. He would scream out or wander around whimpering. Although night wakings were disturbing, we found them to be a necessary passage for bringing our son to reality. In order to give comfort, at night we continued the CD humidifier, as well as CD ear and nose drops. Many times a CD bath before bed was calming as well.

Emotional Blindness: Because the toxins that the parasites excrete are substances that have the effects of morphine, ammonia, and histamine, these toxins can cause emotional confusion in your child. They may be confused by your laughter, smiles, and affection. Your positive and loving encounter may be perceived as threatening or challenging. Your smile may bring a rage. Any spoken words by you no matter how soothing they may be, could be perceived as a confrontation. This is difficult on both parent and child, as the child may see you as a threat and perhaps even as mocking them; while you as the parent feel rejected in your affections. Many times the child's behaviors evolve into a stoned-out loss of reality and presence. These are all related to the toxic build up and defense of the parasites. Their motivation is to remain in the host; they show their displeasure to the discomforts we have given them in our elimination attempts. Many times during these episodes, we have found it best to avoid words or eye contact, but rather to offer double doses as outlined by Kerri, and keep a calm environment. We have found that these toxic levels can be lowered through salt baths and dandelion tea.

Despite the behaviors that may be brought on by a parasite protocol, the results are amazing. In our family we are finally getting our son back. I would recommend staying the course. As we know, these kinds of parasitic infestations in immune-comprised children will not go away on their own. Children do not "grow out of" worms. In fact, the worms will continue to grow inside of them. The following parasites were expelled by my older son, by making the aggressive modifications aimed at older children. By removing these parasites we are seeing the first stages of recovery. The jars on the following page represent seven pounds of worms in less than two months.

Yours in healing,
Robin

Jar #2 Sept 30th
Oct 13 Rope

7 lbs. of 35 lbs. (total) of the parasites extracted in 9 months (160 feet in total above).



39+ inch long worm.

Other Medicinal Plants

Author's Note: The following information is extremely powerful for our continued health and well-being. However, these plants and foods ALONE have NOT been proven to heal autism. Rather, follow the 18-day deworming protocol presented starting on page 187. When this is done for 12-18 months it has proven to be an important part of the protocols that have led to the recovery of many children. With that in mind, some parents of older children, and aggressive/self-injurious children have started to implement a few of the plants and foods listed below, in addition to the aforementioned 18-day protocol. In many cases, these additions have led their children to increased gains through increased parasite elimination.

A number of other plants are also effective for deworming. If, after three months of treatment, the problem persists we can change the type of plant, or repeat any plant that was effective in previous months. We can use them in combinations, mixing several plants at once, or take them individually. Plant formulations that should be considered are alcoholic extracts, in oil or by infusion, and include the following plants:

- Clove (*Syzygium aromaticum*)
- Common Rue (*Ruta graveolens*)
- Dandelion (*Taraxacum officinale*)
- Gentian Root (*Gentiana lutea*)
- Mint (*Mentha sativa*)
- Mugwart/Common Wormwood (*Artemisia vulgaris*)
- Pomegranate Root Bark (*Punica granatum L.*)
- Southernwood (*Artemisia abrotanum*)
- Sweet Wormwood (*Artemisia annua*)
- Sweetflag/Calamus Root (*Acorus calamus*)
- Tansy (*Tanacetum vulgare*)
- Walnut shell (*Juglans*)
- White Fraxinella (*Dictamnus albus*)
- Yarrow (*Achillea millefolium*)

Preventative Food & Diet

There are groups of foods that should be avoided if you have a parasitic infection. For example, dairy products in general, refined sugars (sucrose, fructose, corn syrup), flour (especially refined), and overly sweet foods in general. The list of foods and plants below promote good internal balance of the body, hence becoming our allies. With good production of stomach acid, a normal level of healthy bacteria, and proper bile production, it is impossible for parasites to survive for long. Worms need an acidic environment that comes from the breakdown of sugars and putrefaction from the ingestion of unhealthy or processed foods. It is very important to eat raw vegetables and fruit juices, which provide us with enzymes and other elements necessary to protect us.

Choucroute/sauerkraut (fermented cabbage in salt).

Many people have low levels of stomach acid, which is the cause of many intestinal problems, because the body is unable to defend itself against intruders. Sauerkraut juice or cabbage/sauerkraut is one of the most powerful stimulants for your body to produce stomach acid. The use of unpasteurized fermented foods (water kefir, soy sauce, miso, etc.) is highly recommended for its stimulation of the beneficial bacterial flora that is responsible for generating control over parasites. Take a few spoonfuls of cabbage juice before meals, or better yet sauerkraut juice, because it will do wonders to improve your digestion.

Author's note: I do not recommend soy, in any form, for anyone with an ASD.

Garlic

Garlic, eaten regularly, turns the stomach and intestine into a lethal environment for parasites, providing constant protection. Garlic is the quintessential home remedy to eliminate intestinal parasites naturally. It has been used by many different cultures such as Chinese, Greek, Roman, Indian, and Babylonian.

Garlic is still in use today by practitioners of modern medicine. It is used both fresh and as an oil. The simplest treatment is to eat three cloves of garlic every morning, or take a teaspoon of garlic oil. Alternatively, mix crushed garlic in a little cold water and drink the mixture immediately. Another recipe is to cut and crush four cloves of garlic, place them in milk, and allow the mixture to sit overnight. Take the liquid while fasting the next day.

Pumpkin Seed

Pumpkin seeds contain a substance called piperazine. It acts by paralyzing the parasites, which allows them to be removed easily.

We can find piperazine commercially in pharmacy drug formulations or naturally, as we said, in the seeds of the pumpkin. This traditional method of deworming has been used around the world since man can remember. There are several effective traditional formulas, below we describe one of them:

Use one cup of peeled and mashed pumpkin seeds (about 80 seeds). Mix them with coconut water and two tablespoons of honey. Take the mixture over three hours on an empty stomach. Do not eat during this three-hour period. At the end of the three hours, take castor oil in order to quickly eliminate the parasites.

Papaya and Papaya Seeds

Papain is a digestive enzyme contained in papaya that is capable of breaking down the outer layer of adult parasites. The milky juice of unripe papaya is a powerful agent for destroying roundworms. The adult dose is one tablespoon of fresh green papaya juice, an equal amount of honey, and three or four tablespoons of hot water. Two hours later, administer a dose of castor oil mixed with warm milk. This treatment should be repeated for two days if necessary. For children seven to ten years of age, half of this dose should be administered. For children under three years of age, one teaspoon (5ml) of the mixture is sufficient.

Papaya seeds are also useful for this purpose as they are rich in papain and caricin. For every tablespoon of crushed, fresh seeds, add an equal amount of honey. Take the dose of one teaspoon (5ml) daily in the morning or at night on an empty stomach for ten days, rest five days and repeat the cycle three times. We recommend the use of a purgative.

Ginger

Ginger not only helps to combat intestinal parasites but also reduces nausea and can help calm nerves. For hundreds of years, fresh ginger has proven to be highly successful in destroying intestinal worms. The most common way to consume ginger is raw or by infusion. Ginger extract may also be sprinkled on a variety of foods.

Propolis

Propolis is a resin like substance gathered by bees from the bark and leaf buds of trees, to help disinfect, build and maintain their hives. Propolis has been used for at least 3,000 years. Its use dates back to the Egyptians and the Romans, and remains in use today. To the Greeks we owe the name pro, meaning "before" and polis, meaning "city." This translates as "defenses before the city," or "defender of the city." Thanks to the antibiotic action of propolis, which protects against the activity of viruses and bacteria, the hive is one of the most sterile places known to nature.

Many scientific studies have proven the antiparasitic activity of propolis, therefore it is recommended for treatment of: *Giardia*, amoebas and roundworms, and also for intestinal infections caused by gram-positive bacteria.

Take propolis, diluted in water or fruit juice, for treatment of parasites, for seven days, on an empty stomach. Use Propolis standardized at 30% in either propolis tincture or capsules. Take three drops per kilo of weight, or three capsules one half-hour before each meal. A seven-day treatment cycle should include seven days on, followed by seven days off; repeat three to five times to ensure complete elimination of parasites or bacteria. Repetition of the treatment is essential to halt bacterial reproductive cycles. By repeating the treatment at least three times, the effective elimination of parasites is ensured. The benefits of propolis are that it has no side effects, is well tolerated, and is highly effective.

Pomegranate Bark

Pomegranate bark contains an alkaloid known as punicine, which is highly toxic to earthworms. It is used by decoction of the root bark, stem, or fruit. The root bark is preferable because it contains a greater quantity of the alkaloid than the bark of the trunk. This alkaloid is also highly toxic to tapeworms. A cold decoction of root bark, preferably fresh, should be given in quantities of 90ml to 180ml three times per day (for adults), with one-hour intervals between cups. A purgative should be taken after the last glass. For children, a dose of 20ml to 60ml is appropriate. A decoction is preferably used to eliminate solitaires (tapeworm, *Taenia Solium*).

Carrots

Carrots are another effective home remedy for eliminating intestinal parasites in children. The chemical constituents of carrots attack pests by preventing their development. It is one of the most effective natural treatments for children, when given a small cup of grated carrots each morning until the problem desists.

Condiments

Seasoning plants are also powerful weapons to keep in mind in our everyday cooking. Since time immemorial, mankind has used them to control parasitic diseases. The following are most interesting because of their effects:

- Cayenne
- Cinnamon
- Cloves
- Paprika
- Pepper
- Tarragon
- Thyme
- Turmeric

Thank you Andreas and Miriam for sharing what I know will be very enlightening, not only to the families of children with autism, but to people all over the world suffering from mysterious symptoms consistent with parasitic infections. I want to share one interesting tidbit about parasite infections before we get into the FAQs on parasites and the parasite protocol.

"We have a tremendous parasite problem right here in the U.S. It is just not being addressed."[5] - Dr. Peter Wina, Chief of Patho-Biology in the Walter Reed Army Institute of Research in 1991. (The problem existed in 1991, and with modern globalization parasites are more prevalent than ever, yet they still not being addressed.

Parasite Protocol FAQs

I showed my family practitioner pictures of the worms we have found. He thinks they are not a parasite, but just mucous. How can I be certain?

It can be difficult to identify parasites, and most general practitioners are not trained to do so. Some parents have success with a local vet, who analyzes samples in their office. As a crude test, you can pour boiling hot water onto your specimen. If it falls apart, it is probably biofilm or mucous. If it withstands the wash, it is probably a parasite. Unfortunately, most stool analyses are notorious for false negatives. If you put hot water on parasites, they do not dissolve. Mucous dissolves in any water—hot or cold.

Is it ok to do the Kalcker Parasite Protocol during pregnancy?

No. Don't do any kind of detox or parasite protocol while you are pregnant or nursing. Any detox will release toxins into the blood stream that could potentially negatively impact the developing fetus or nursing baby. If you are planning on getting pregnant, it would be advisable to do whatever detox or deworming procedure before pregnancy.

When is it appropriate to stop the parasite protocol? In other words, does every child on this protocol need both the CD and the other parts of the Parasite Protocol or are there some that only need CD? This is a critical question since these are two protocols joined together and not every child may need both. We have done the Parasite Protocol and have never passed parasites so I am uncertain about my child.

Usually the Parasite Protocol is repeated for 12-18 months, sometimes less. The most important thing is to make sure that there are no fertilized eggs left that could hatch at a later date. As it is very difficult to know if there are remaining eggs, it is important to complete the 12-18 month treatment. The Parasite Protocol is a complete protocol heavily researched to achieve the best results. The Parasite Protocol in conjunction with CD has been shown to be one of the most effective methods to heal regressive autism. Parasites are cyclical and need to be treated as such. You continue with the parasite protocol until no more parasites are seen—be that in behavior or actually in the stool.

What does the process of worms toxifying the brain look like?

Ascaris lumbricoides (roundworm), for example, produces at least five different toxins: Malondialdehyde, ammonia, histamine, formaldehyde, and morphine. Malondialdehyde is responsible for oxidative stress, and is mutagenic.[7] Ammonia, which can lead to hyperammonemia, can be responsible for seizures, tremors, flapping, poor coordination, growth retardation, combativeness, lethargy, and other symptoms. Comparing hyperammonemia with the symptoms known as regressive autism yields overwhelming similarities. Formaldehyde has been shown in some laboratory studies to affect the lymphatic and hematopoietic systems. Morphine inhibits nerve reactions and slows intestinal peristalsis. It also keeps the immune system from finding parasites, and from doing anything about them. This is a reason we often can't identify parasites. We only find parasites when the infection is acute, not chronic. This is because IgE or IgM reactions are altered by morphine. Histamine can lead to chronic inflammation in the body.

As a family, we expect to be doing the CD and parasite protocols for some time. How do we know when to stop? Should we wait until we have a few months of no symptoms?

We do it until full recovery is reached.

We have been doing full oral dose CD and the Parasite Protocol. We are seeing some amazing changes, but we don't see worms. Are we doing something wrong?

CD affects parasites of different sizes. You may be clearing parasites that would be undetectable to the naked eye, or nematodes that are very small and therefore hard to detect in the stool.

Why is my child so deficient in vitamins?

As a general rule, most children with autism are deficient in vitamins. In the first place many pathogens feed off of vitamins intended for the host, and helminthes especially love B12 and iron. Since many of us, especially those of us living in cold climates, do not receive enough sun, we are deficient in vitamin D. Calcium is used by the body as an antagonist for acid inflammation; all acidity in the body is compensated by calcium, and therefore it is usually low with the kids on the spectrum. As our children heal, these deficiencies fade and homeostasis returns.

I just gave mebendazole, Not pyrantel this AM. What should I do?

Don't stress. Tomorrow is a new day, and you can begin again. Give mebendazole tomorrow as that is tomorrow's scheduled dose.

Aren't there some parasites that are good for us and help our immunity and gut healing?

A parasite is defined as a living being that is dependent on a host for survival, to the detriment of that host.

For those of you that continue the parasite protocol thru the new moon, how many days do you stay on it? We are now 3 days past the new moon.

Some people treat month long. The Kalcker protocol itself is 18 days long. Each family has to find a protocol that suits them. Some folks use mebendazole 3 days before the new moon, the day of, and three days after. Other families use herbal remedies on the off days. If you consult with a healthcare provider, this would be a question to ask them. Each child is unique and has different needs when it comes to treating parasites.

Why are live worms not digested? Poisons?

Live helminths are protected by a glucosoid mucous with positively charged ions, making them resistant to stomach acid, or digestive fluids. When they die, the mucous separates from the helminth, leaving them open to digestive enzymes. We often see the mucous, as well as semi-digested helminths, in the stool of people using the protocol.

Does everyone in the family need to do the parasite protocol at the same time? With or without CD, enemas, diatomaceous earth, Rompepiedras/stone breakers, and castor oil? My (neurotypical) daughter will take the anti-parasitic drugs, mebendazole, and pyrantel pamoate, but not these other parasite protocol ingredients, which is why I ask.

Your entire family needs to do the protocol at the same time, or you risk reinfection. Neurotypical family members should do as much of the protocol as possible. If someone will only take the meds, so be it. However, I feel the more the better.

Do I need to separate the neem from CD?

Yes, I give neem with food, and would separate from CD by at least an hour.

If I don't see any worms, does that mean my child doesn't have parasites, or are we just missing the eggs?

Just because you don't see parasites doesn't necessarily mean you don't have any. For example, *Toxocara canis* or *Toxocara cati*, which are very common in our pets (and can infect humans as *Toxocariasis*), are not expelled in fecal matter. Some families on the protocol did not see actual worms until month seven.

To what extent do the rest of us need to do the CD protocol? Is it the same as our ASD children? And, is it necessary to do the whole nine yards with the full Parasite Protocol for the whole 12 months? Are there any shortcuts for healthier individuals?

All of the family members, including pets, need to be on anti-parasite treatment for a year and thereafter lifetime maintenance is best. As mentioned before, with neurotypical family members, you do as much as you can, but the anti-parasitic medications are crucial to preventing reinfection.

Is diatomaceous earth a binder and therefore must it be given apart from food, medication, and supplements?

No. It is not a binder. It is fine to give with or without food, and does not affect medication or supplements.

Do you have to do the Protocol forever if you are fully recovered or is there a maintenance plan?

When the child gets to where you want him, you can start to pull things. Then, we do maintenance dosing of CD; one dose on Monday and one on Thursday. We do the Parasite Protocol for a week every three months since we live in a world of parasites. It is good preventative medicine for all. Ocean water is also good for all of us. See Chapter 13 (page 319) for the complete maintenance plan.

Does CD kill parasites?

Yes. CD kills amoebas, *Giardia lamblia*, and other smaller parasites. CD does not kill the larger macroparasites due to their higher oxidative stress resistance.

When is it ok to start the parasite protocol prior to reaching full dose of CD?

Healing autism is a marathon not a sprint. The point is to heal with the least amount of aggravation. Therefore, you should be at a full dose of CD before starting, and have added in enemas and baths. If you are seeing Herxheimer reactions then don't start yet. Obviously, everyone must make his or her own decisions.

Where in the gut do helminths live? Do CD enemas (300 ml) reach them?

It depends on the type of helminth. There are more than 300 different helminths so they could be in many different places. However, most live in the small intestine. Some lay their eggs in the rectum. The size of the person will dictate how high an enema will reach.

Do you tell your kids that they have worms? Do you show them? Are they scared? My son is very interested about everything in the world and asks 4,000 questions a day. What do I tell him?

How to handle this situation is unique to each and every family. There is no right or wrong answer here. The following are some suggestions we have received from families on the protocol:

Nope. My husband was just telling me a story from when he was a kid about another kid who got teased all the time about having worms. He still remembers it. So, no I will not tell my kids.

My kids (ages 10 & 7) know about worms because we have talked about their Lyme disease and other symptoms for a long time. I think it helps them understand why they feel grumpy or sick and why the enemas help. But, I think every child is different. The risk is that they might tell their friends. I tell them that it is private information and that pretty much everyone has worms but some people have more and get sick from them. And, I told them that even most doctors don't know this but slowly people are learning and getting smarter about this and a good diet, etc... My boys like to see the big ones, and try for new records. They like to show their brother the records. I think that's a boy thing.

I have a 10 year-old, and I tell him that we have parasites. I have not showed him anything, I ask him to leave the room before I start to sort the poo. ;)

My son had another bowel movement FULL of worms, pinworms—and I mean hundreds. This is only our second day on CD (1/2 drop in 8 fl. oz.) so a bit thrown to the deep end. Has anyone else had a start like this? How did everything go from there on?

I have seen it a handful of times. I get VERY excited about this. Everyone has autism a bit differently. But, if we see worms early, in many cases the recovery begins early too. That may be the case for your child.

I understand that even organic produce needs to be washed properly. What is the best way to wash my fruits and vegetables?

The Ascaris eggs are resistant to UV, and can withstand a pH from 2 to 11.5. Eggs are killed by heating to approximately 60°C (140°F). Spray your fruits and veggies with CD spray. 10 drops per 1 fl. oz., of water, no need to rinse off.

Anyone notice a huge growth spurt after starting the parasite protocol?

Many parents have reported their children resumed growth as well as weight gain. No real surprise considering they are getting back what the parasites were taking from them.

Do we need to treat our pets if they are taking heartworm medication?

Yes, heartworm medication does not address intestinal parasites, which can infect us and our children. We need to deparasitize our pets, as well as ourselves.

We put "cascara sagrada" in place of castor oil because for my son and me, it is difficult to take the oil. Is it ok?

Cascara sagrada is not the same thing as castor oil and is not part of the protocol. An alternative solution to liquid castor oil is to buy castor oil in softgels. You will need many but it does solve the taste problem.

My son is very high in Trichinella spiralis, which is a roundworm from undercooked meat or pork. It's supposed to be rare in the US, so I'm wondering how my child would have picked this up. Any ideas? No undercooked meat here for the kids, and we don't eat pork.

At this moment we have not seen a relationship between *Trichinella spiralis* and autism. It may be a multi-parasitic infection, or a misdiagnosis. Apart from the standard protocol, your child might need something else. I would consult the practitioner for the appropriate dosage, and only if your child has a definite Trichinella spiralis diagnosis.

How do we know if there are parasites in the brain, and what can we do about it?

Parasites in the brain are very rare. (According to the CDC, *Cysticercosis* is a parasitic tissue infection caused by larval cysts of the pork *tapeworm.* These larval cysts infect brain, muscle, or other tissue, and are a major cause of adult onset seizures in most low-income countries. An individual acquires cysticercosis from ingesting eggs excreted by a person who has an intestinal tapeworm.)[6] Larvae can be seen on a scan. Many people assume that the problem causing behavioral issues, or mental issues, must be located in the brain. However, the problem likely exists elsewhere. If the blood contains toxins, this will affect the brain. For example, if you ingest too much alcohol, your brain, nervous system, etc. will be affected, but the problem is not in the brain itself. We can think the same way about parasites. The chemicals that they produce will have effects on the brain, however, rarely will the parasites be located there.

Do parasites cause autism? If so, why doesn't every child with parasites have autism?

Regressive autism has been called parasitological vaccinosis by Dr. Andreas Kalcker. This is a cross reaction between a child with parasites that receives certain vaccines. Further research is needed for a definitive answer.

Why don't normal lab tests find parasites?

Generally speaking, lab tests need to find living creatures or eggs. The eggs are only present certain days of the month, and even on those days they won't necessarily be present in a particular stool sample. Living worms are extremely rare in stool because they are generally passed only once they die. They are very good at avoiding being excreted in stool. Furthermore, if they die internally, they can be partially or fully digested within our bodies before being expelled.

Are some labs better than others? Is it worth taking a stool sample to a vet if they send it out, or only if they look under a microscope?

We haven't found a lab that consistently finds parasites. Metametrix™ has identified parasites, but in our experience and the experience of the families I have helped, we have not found a lab that is consistent. It is only worth sending a sample to a vet if they are identifying parasites with a microscope.

Combantrin® is available in tablet and liquid form. Which is better?

I hate the liquid and never use it. It may have added colors and flavors. If you absolutely can't find it without additives, I would use only mebendazole instead of using pyrantel with additives.

Why are there no systemic drugs in the protocol?

They are not needed with this Protocol. Treating parasites without systemic drugs is much safer and easier on the body. The suggested treatments using mebendazole and pyrantel pamoato are nearly unabsorbed by the body, meaning that we do not add more toxins to an already overloaded body.

When does a child need systemic drugs?

This is necessary only for certain parasites like cysticercosis, which is caused by tapeworms, hookworms, Trichinella spiralis (from pork), or other hard to kill helminths. These may be identified by a blood test. The practitioner may prescribe systemics depending on the situation.

Should I start on the new moon if my child's behavior declines then?

The full 18-day Kalcker Parasite Protocol always starts before the full moon. However, some parents have found that by treating parasites for 3 days over new moon that they are able to get through the new moon as well as the full moon with limited issues if any.

Is there a time in the moon calendar, where it is normal that there are no worms in the stool? (We don't have any at new moon.)

Further research is necessary to determine this definitively.


Healing
the symptoms known as
Autis
Kerri Rivera
with Kimberly McDaniel
With over 120 testimonials from around the world!

Hero Guy taking a peek at *The Protocol.*

Chapter 9

Step 4 - Other Supplements

"One of the first duties of the physician is to educate the masses not to take medicine."
~ *William Osler*

Most of the families that followed this Protocol, and recovered their children, used a combination of these additional supplements along with CD. Each supplement combination is completely unique, depending on the symptoms of the child, and how the child reacts to each intervention. If after *The Diet*, full *CD Protocol*, and three *Kalcker Parasite Protocols* we are still dealing with an autism diagnosis, then families start adding in supplements. This section is about "unfinished business." I like to do three Kalcker Parasite Protocols before adding back in supplements because parasites love supplements, especially vitamin B_{12} and iron.

I feel when we supplement deficiencies in children with underlying parasitic infections, it can result in resistant parasites. We aren't making the child healthier; we're making the parasites healthier and stronger. If significant supplementation does little or nothing to change lab values in subsequent blood, urine, and stool tests, then it's fair to say that we have a flaw in our approach. Pathogens and parasites can cause vitamin/mineral deficiencies. By killing them, instead of feeding them with additional supplementation, we are focusing on the root cause of the symptoms that we call autism.

When I came back from our first *Defeat Autism Now!* doctor visit, I had thousands of dollars in supplements that I did not know how to use. We kept going to different doctors hoping to find the one that had the answer. At one point, Patrick was on a protocol, given to me and supervised by a doctor, which called for 70+ different supplements a day. He looked worse during the entire nine-month period that we followed that protocol. In hindsight, all those years of supplementation made it harder to eliminate Patrick's pathogens.

That is why this protocol focuses on the excesses instead of the deficiencies for children with an autism diagnosis. If by eliminating the excesses of viruses, bacteria, candida, parasites and heavy metals, we can see a reduction in the symptoms known as autism, then eventually we can reach full healing.

Commonly, when a new family contacts me, they send me a list of all the supplements their child is taking. I frequently see lists of 30+ supplements that may be combined in ways that negate their effects. For example, probiotics are given in the morning with breakfast, or GABA with food. Both are incorrect, probiotics go alone at night right before bed, and GABA is always taken without food. If there is a legitimate reason for a certain supplement, then it absolutely must be given correctly or it's just excess noise in the body, and more stress on the detox organs.

The following list of supplements can be considered after *The Diet*, ocean water, CD, and three months of the *Kalcker Parasite Protocol* (except probiotics and enzymes which may start day one). This chapter is to be used as a starting point for your own research on these supplements. This list contains references and the websites used in this research with some of the more pertinent information about products.

Probiotics

The vast majority of the families who have recovered their children with this Protocol have used THERALAC® brand probiotic. It is a prebiotic plus probiotic in a capsule that can withstand stomach acid, which allows it to pass to the small intestine, where the beneficial bacteria are needed. THERALAC® contains three *lactobacillus* and two *bifidobacterium* strains.

The paragraph below was slightly modified from www.theralac.com where you can find more information. Please visit their site for details on references contained within the text.[1] The following two paragraphs were taken from different sources, and help explain benefits of THERALAC®, specifically for children on the spectrum.

> Probiotics are defined as: "Live microorganisms that when administered in adequate amounts confer a health benefit to the host" (World Health Organization 2001). According to the International Probiotics Association (IPA), the benefits of probiotics can include reduction in diarrhea caused by antibiotics and rotavirus, alleviation of symptoms of lactose intolerance, alleviation of symptoms of food and skin allergies in children, reduction of recurrent ear and bladder infections, and other positive indications.

How Does THERALAC® Benefit My Immune System?

> THERALAC®'s five probiotic strains work in unison to support the mucosal immune system on the intestinal surface; activation signals are then sent to the body's systemic immune system. This is a gentle and controlled process because THERALAC®'s strains are beneficial. Essentially, the immune system is put on alert so that it is ready to act quickly if there is an appearance of pathogenic microorganisms.[2]
>
> Many children with autism have chronic digestive problems. In fact, gastrointestinal symptoms in autistic children often first appear in conjunction with initial changes in emotion and behavior during the onset of autism, leading researchers to suspect a gut-brain connection.[3]

Normally, proteins are digested in stages by enzymes; first to peptides, and then to smaller amino acid components, which are absorbed into blood capillaries in the gut mucosa. The larger peptides are generally unable to cross this mucous membrane barrier, if they do, however, they can act as opioids affecting neurotransmitters in the brain causing abnormal behaviors and/or activity. These incompletely digested peptides—known as exorphins, casomorphins, and gluteomorphins usually come from milk proteins such as casein, or from wheat (gluten), and are structurally similar to morphine. The formation of excess peptides in the gut is possibly associated with sub-optimal enzyme activity, or an insufficient supply of enzymes required to breakdown these peptides. So if we repair the imbalance of beneficial bacterial organisms in the gut and the gut lining, while killing the pathogens causing the dysbiosis, we have the opportunity to heal children with autism. Probiotics can be used to improve the quality of the gut mucosa.[2]

In addition to aiding in the repair of the gut lining and improving digestion, there is also evidence that probiotics can help with detoxification of heavy metals such as toxic mercury.

The paragraph below was taken from the presentation "Gut biology and Treatment" by Dr. Anju Usman:

> Emerging literature is showing the beneficial effect of oral probiotics on mood and anxiety symptoms. In a double-blind, placebo controlled randomized parallel group study, daily use of probiotics reduced psychological distress.[5] A number of studies have shown the anti-anxiety effects of probiotic use in patients with medical conditions.[6]

> Dr. Vincent Young, University of Michigan (2009): "the gut ecosystem needs to be preserved and that changing the ecosystem through stresses such as antibiotics could irreversibly change the ecosystem, with deleterious effects." Dr. Young has studied the effects of antibiotics on the microbes in our gut. He found that mice when given particularly strong antibiotics completely wiped out all their normal gut microbes. Even more striking, clostridium species and fungal species are then able to overgrow without the bacteria there to fend them off.

There is no doubt in my mind that probiotics helped get my son's gut back in order, helped improve my own health, and that of thousands of families of children on the spectrum. Probiotics should be given without food, directly before bedtime. This way, they have the entire night to proliferate in the small intestine where they are needed.

Special note for those with PANDAS/PANS: We have received some reports where some PANDAS/PANS and/or older children were becoming violent and having more SIBs while on probiotics. Be observant and watch for behavior changes when adding probiotics. In addition, know that we may need to remove them for a period of time!

Omega-3 & Omega-6 Fatty Acids

Omega-3 and omega-6 fatty acids are polyunsaturated fatty acids and are considered essential fatty acids. Essential fatty acids must be consumed because your body cannot produce them. They are important for brain development, immune system and cardiovascular function, and normal metabolism. Omega-3 and omega-6 fatty acids are commonly found in marine and plant oils. While a healthy diet often provides adequate supplies of both, supplementation is sometimes necessary.

Omega-3 fatty acids also help to regulate energy levels, as well as normalizes blood sugar levels. They help improve concentration as well as mental vividness. Using omega-3 fatty acid supplements helps with anxiety, mood swings, and depression. They are especially significant in the treatment of autism. The entire body benefits from ingesting omega-3 fatty acids; from physical development, to relaxation from anxiety and jitteriness, to developing brain cells; all of these aspects can aide in the treatment of autism.[6]

Omega-6 fatty acids promote healthy brain function and assists with skin and hair growth, bone development, and metabolism. A healthy balance of omega-3 and omega-6 fatty acids promotes heart health and minimizes inflammation. Omega-6 may also be used to treat allergies, eczema, osteoporosis and premenstrual syndrome.[7]

Unlike omega-3 fatty acids, excessive consumption of omega-6 fatty acids can have negative effects. Therefore, their consumption must be monitored. Omega-6 fatty acids, in large quantities, can promote inflammation in the body that may lead to flare-ups of eczema, acne, and the aches and pains associated with arthritis. It is recommended that you maintain about a 4:1 ratio of omega-6 to omega-3 fatty acids.

Some research has been done that suggests improvements in overall health, cognition, sleep patterns, social interactions, and eye contact when children on the spectrum were given an EFA (Essential Fatty Acid) supplement.[8]

Furthermore, another study showed the positive effects of EFA's on dyspraxia (a motor disorder frequently associated with cognitive, behavioral, and social challenges). The participants showed improvements in reading, spelling and behavior during the treatment period.[9]

I have personally found that I really like omegas from YES™ Supplements. Dr. Brian Peskin has some very informative videos on YouTube discussing the merits of vegan versus animal based omega sources. I highly recommend you have a look for yourself. My own son, and many other children have built up to taking one tablespoon, two times a day.

L-carnitine

L-carnitine is a vital amino acid that promotes healthy neural levels of acetylcholine, an important neurotransmitter that aids memory and proper brain function. Research suggests that an L-carnitine deficiency may be implicated in a number of conditions, including ME/CFS (chronic fatigue syndrome), diabetes, Alzheimer's, dementia, and autism.

L-carnitine is composed of two essential amino acids, lysine and methionine. It is produced in the liver and kidneys and is contained in most cells of the body. It is required for the proper metabolism of fat and helps with mental concentration, and energy production. It transports long-chain fatty acids across the mitochondrial membrane so that they can be burned to produce energy.

A clinical trial studying the use of L-carnitine as a potential therapy for autism demonstrated the children taking L-carnitine showed improvements in their ability to relate to people, body use, adaptation to change, listening response, verbal communication, sociability, sensory/cognitive awareness, and health/physical behavior. There are a few articles that may be helpful for a better understanding of the importance of this amino acid. Check out an article by Henke Schultz, "L-carnitine helps kids with autism, study finds" and another by Emily Singer, "Defects in carnitine metabolism may underlie autism."

The average dose for L-carnitine is anywhere from 250-1000 mg per day with food, depending on weight and reactions.

GABA

GABA (gamma-aminobutyric acid) is an amino acid and a neurotransmitter (a type of chemical responsible for carrying information from one cell to another). It is produced naturally in the body, but is also widely available in supplement form. Manufacturers claim that GABA supplements can help boost the brain's GABA levels and, in turn, treat anxiety, stress, depression, and sleep problems.

The GABA system acts as something of an information filter to prevent the nerves from becoming over stimulated. It has long been suspected that this filtering process is compromised in many autistic children. Impairment of the GABA system could overwhelm the brain with sensory information, leading to many of the behavior traits associated with autism. GABA is also believed to play a key role in the early development of the brain.[10]

GABA is also involved with the production of endorphins in our brain, which make us feel positive and upbeat. GABA can reduce stress, relieve anxiety, and increase alertness. GABA can be helpful for behavior, language, and possibly even seizures.

GABA is used for control of seizure activity and works on the same receptors as the drug Keppra®. GABA is also useful for speech, helps facilitate language in nonverbal children, and improves language in children that are beginning to speak.

If you are going to give GABA to your child, the max is 5,000 mg per day, divided into two doses, one in morning and one at night, always on an empty stomach. In the evening, GABA can be given 15 minutes after your last dose of Chlorine Dioxide, with your probiotic. I start at 250 mg two times a day, one in the morning and one at night. I then titrate up the dose daily or every other day if everything looks good. If you observe sleepiness or irritability it is a good idea to back down.

5-HTP (5-Hydroxytryptophan)

5-HTP, also known as oxitriptan, is a naturally occurring amino acid. It is a chemical precursor to the neurotransmitters, serotonin and melatonin from tryptophan. 5-HTP works in the brain and central nervous system by increasing the production of the chemical serotonin. Serotonin can affect sleep, appetite, temperature, sexual behavior, and pain sensation.

From *Saving Eli: One Family's Struggle* - Vitamin Research Products website:

> While not clearly understood, researchers know that serotonin pathways are disturbed in autism, contributing to sleep disorders and mood. Tryptophan has been shown to help but has been banned by the FDA since 1989. We found that 5-HTP helped immensely, calming tantrums and increasing communication with our son.[11]

5-HTP is used between 50 mg and 200 mg, divided into two doses, morning and evening with food. I have seen it help children with autism for attention, focus, sleep, and cravings.

L-theanine

L-theanine or gamma-glutamylethylamide or 5-N-ethyl-glutamine, is an amino acid commonly found in tea. Theanine is able to cross the blood–brain barrier, and is reported to have positive effects on mood, stress, and cognition.

The following is excerpted from the L-Theanine website:[12]

> Many people experience stress on a daily basis and are looking for natural and safe ways to manage it. For thousands of years, it has been suggested that drinking green tea will make one relaxed. Recently this relaxation effect was found to be true and works because of an amino acid called L-Theanine which is found in the tea. Clinical research will show that ingesting up to 200mg of L-Theanine will promote the creation of the very important "anti-stress" neurotransmitter in the brain called GABA or gamma-aminobutyric acid. This results in a relaxed, clear and alert mental state.
>
> When used in the correct amounts in supplemental form, L-Theanine may:

- Reduce Stress
- Reduce Occasional, Simple Nervous Tension
- Promote Relaxation without Drowsiness
- Promote Mental Clarity and Focus
- Promote Positive Mood
- Promote Alertness
- Promote Learning and Memory
- Help Prevent Jitters Caused By Caffeine

I have found that when we can reduce these symptoms in individuals with ASDs we can get an increase in speech, learning, focus, concentration, and attention. L-Theanine is given with GABA upon waking, and can also be given at bedtime if needed, always without food. You can work up to 200 or 250mg/day.

Pycnogenol®

Pycnogenol® (pic-noj-en-all) French maritime pine bark extract acts as a potent blend of antioxidants, it is a natural anti-inflammatory, stimulates generation of collagen and hyaluronic acid and help with natural dilation of blood vessels by supporting production of nitric oxide.[13]

Pycnogenol® is not a supplement I tend to use very often, because it is an antioxidant, and therefore cannot be combined with chlorine dioxide. However, in some people it has proved necessary and helpful for speech and reduction of seizures. It should be given in the morning with food at a dose between 25 and 400 mg/day depending on need. Pycnogenol® may not be suitable for children who are sensitive to phenols.

L-Carnosine

L-Carnosine is a dipeptide of the amino acids beta-alanine and histidine. It is highly concentrated in muscle and brain tissues.

L-Carnosine is believed to stimulate the frontal areas of the brain, resulting in overall improved levels of functioning. More and more research shows that the frontal lobes and temporal lobes in the brain control emotion, epileptic activity, cognitive, expressive speech, and abstract thinking. Studies have shown Carnosine to improve language, socialization, and overall level of functioning in individuals within the autism spectrum. It has also been shown in studies to have anti-seizure properties without the side-effects of prescription anti-seizure medications.

Research indicates it prevents the formation of the beta amyloid plaque that is found not only in neurological conditions such as Alzheimer's, Parkinson's and autism, but also in the eyes in degenerative eye conditions and in the pancreas in diabetes. It is a neuroprotectant, with a study indicating it reduced severity of damage in stroke patients.[14]

Chez and coworkers found that after eight weeks on L-carnosine, children showed statistically significant improvements on the Gilliam Autism Rating Scale (GARS). They relate this to the likely ability of L-Carnosine to enhance neurological function, perhaps, in the enterorhinal or temporal cortex.[15] This enhancement in neurological function has led to speech in many of the families that I have worked with.

I have also seen L-Carnosine help reduce seizures in some children and increase language in others. It is given twice a day with breakfast and dinner at a dose of 200 to 400mg, 2 times a day. If you note hyperactivity, remove it.

Taurine

Taurine is an amino acid, a chemical that is a required building block of proteins. Taurine is found in large amounts in the brain, retina, heart, and in blood cells called platelets. It can be consumed through eating meat and fish.

Autism and Low Taurine

"Are You Dangerously Deficient in Taurine"[16] explores possible problems associated with a taurine deficiency. Among the problems noted in the article is autism and low taurine levels. In the article, Leonard Smith MD writes about the benefits of taurine, some of which can be of interest to people dealing with autism spectrum disorders:

- Brain and nervous system function
- Helps eliminate toxins
- Stabilizing the brain (can be effective in treating seizure disorders)

Taurine, like all amino acids, must be given without food. The maximum dose is between 500 and 1,500 mg.

DMG

DMG, or dimethylglycine, is an amino acid that can be found in many common food items like meats (especially liver), various grains, and beans. It has been classified as a type of amino acid that is closely linked to vitamin B.

There have also been interesting developments in the use of a DMG supplement for children with autism. Because many children who have autism are unable to tolerate eye contact, and some have problems forming complete sentences and thoughts studies investigated whether an increase in DMG consumption could help to alleviate many of these problems. In fact, the study found that when children with autism were given supplemental DMG they appeared less frustrated and showed a marked increase in their speaking and cognitive abilities.[17] At present, this research remains novel and therefore further investigation is necessary to determine what the long-term effects of DMG supplementation might have on children on the spectrum.

The following paragraphs were excerpted from *Defeat Autism Now!*[18]

> ### Dimethylglycine (DMG) for Autism
>
> For over 20 years ARI has been hearing from parents who have tried DMG on their autistic children. In many cases remarkably good results have been seen, especially in enhancing speech. In some cases, drug-resistant seizures have been stopped by DMG. (See New England Journal of Medicine, 10-21-82, pgs 1081-82).
>
> There is an extensive research literature on the safety and health benefits of DMG. Many studies have shown that DMG enhances the effectiveness of the immune system, improves the physical and athletic performance of humans and other animals (e.g. race horses) and has, all in all, a very wide range of beneficial effects. It is very safe. I have seen no evidence of any toxic or significant adverse effects.
>
> Many parents have reported that, within a few days of starting DMG, the child's behavior improved noticeably, better eye contact was seen, frustration tolerance increased, the child's speech improved, or more interest and ability in speaking was observed.

A full dose of DMG is 900 mg per day, taken without food upon waking. However, it is best to start at a lower dose and slowly work up to 900 mg over a week or so. If you see an increase of hyperactivity (which is rare), reduce the dose. If no improvement is seen within a month I would switch to TMG.

TMG - Trimethylglycine (Betaine Anhydrous)

TMG (Betaine anhydrous} is a chemical that occurs naturally in the body, and can also be found in foods such as beets, spinach, cereals, seafood, and wine.

How does it work?

A form of betaine called betaine anhydrous helps in the metabolism of homocysteine, a chemical involved in the normal function of many different parts of the body, including blood, bones, eyes, heart, nerves, and the brain. Betaine anhydrous prevents the buildup of homocysteine seen in people who have problems with its metabolism from birth.[19]

The following is excerpted from the *Autism Canada Foundation*.[20] Please visit their site...

www.autism.org

...for full references contained within the text.

The benefits of taking DMG or TMG range from behavioral changes, reduction of seizures, and decreased obsessive-compulsive behaviours to improved language. DMG and TMG have been reported from thousands of families to be quite beneficial to many individuals with autism.

Research on humans and laboratory animals has shown that DMG and TMG enhance the effectiveness of the immune system. Some children and adults with autism have seizures, and there are published reports of decreases in seizure activity as a result of DMG. A double-blind placebo-controlled study by Drs. Shin-siung Jung, Bernard Rimland, and Stephen M. Edelson involving 84 participants documented a significant decrease in behavioral problems.

It should be noted that some kids tolerate DMG but not TMG. TMG is given upon waking without food, in a dose of 500mg. If DMG didn't yield improvements in language, then we switch to TMG.

FAQ's

There are times when I do see undigested food in my son's stools. I am particularly concerned. He never complains of stomach pains. But I do see some at times, especially cashews. Should I bother with an enzyme? Or is it better without one. If so, which brand?

> I love enzymes. Kirkman has one with Isogest®, 851/180 is the number, and it's broad spectrum. Also, Biofilm Defense® is great for dissolving the biofilm. A number of the parents online have used Ness® enzymes Gastric comfort formula #601 very successfully.

How should I administer THERALAC®?

The best time to administer probiotics is at bedtime. Children's THERALAC® is a granular formula so you can sprinkle it on yogurt or mix it into a smoothie and still obtain the same benefits! So how do you take it? We recommend that you take a level 1/4 teaspoon and fold it into yogurt, applesauce, or food of a similar consistency and let it sit for a minute. This is to keep the granules as close together as possible, thus allowing our acid proof gel matrix to form around the product. Visit the THERALAC® website for more info:

www.theralac.com/childrens-theralac.aspx

Supplement Dosing Overview

Supplement	Dose	Time of Day	Empty Stomach (ES) or With Food (WF)
Probiotics	1 cap	Before Bed	ES
Omega-3/ Omega-6	1 Tbsp	With any meal 1-3x / day	WF
L-Carnitine	250-1000mg/day	With any meal 1-3x / day	WF
GABA	Up to 2,500mg 2x/day	Upon waking & at bedtime	ES
5-HTP	50-200mg	Morning & Evening	WF
L-Theanine	Work up to 200-250mg/day	Mornings or Mornings & Nights	ES
Pycnogenol	25-40mg a day/as needed	Morning	WF
L-Carnosine	200-400mg 2x / day	Morning & Evening	WF
Taurine	500-1500mg/day	Morning, Noon & Night	ES
DMG	900mg/day	Morning	ES
TMG	500mg/day	Morning	ES
Enzymes	1 cap w/meals	Morning, Noon & Night	WF

Chapter 10

Step 5 - Chelation

So, let's say we're clipping along; full Diet, CD, Kalcker Parasite Protocol, and we've added in whatever supplements the child specifically needs and the child still has autism. Recovery is still not a reality... yet! At this point, it's time to look at chelation.

Why use Chelation for Autism?

Chelation became very popular in the world of autism about a decade ago, when things were heating up around the Thimerosal/Autism connection. Today, many of our children are still metal toxic. Metal challenges (testing that shows metals in urine) from any of the thousands of children whose families I have helped show the same thing—extremely high levels of mercury, lead, aluminum, as well as sometimes tin, cadmium, and other metals.

These heavy metals can come from various sources such as:

- Coal burning power plants. According to the EPA, coal-fired power plants in the United States emit about 48 tons of mercury into the air every year, where more than half of this mercury falls within five miles of the plant itself. When it reaches the water, microorganisms consume it and convert it into a substance called methyl mercury.
- Drinking water
- Our food supply
- Cookware
- Deodorant
- Beauty products
- Dental amalgams
- Vaccines, etc.

Heavy metals are known to accumulate in different parts of the body including organs, bones, joints, and the brain, etc. Metal toxicity can provoke inflammation, kill neurons, cause behavioral changes, affect the thyroid and other master glands, lower T-cell counts, and cause a myriad of other symptoms. Furthermore, new research shows that fluoride in drinking water makes the aluminum that we ingest more bio-available. As was reported in the journal *Brain Research*, the combination of aluminum and fluoride causes the same pathological changes in brain tissue found in Alzheimer's patients.[1]

Many children with autism also have impaired methylation cycles. The result of this impairment is an inability of the body to rid itself of excess metals, thereby prolonging chronic illness.

What exactly is methylation?

Methylation reactions are those that involve the transfer of a methyl group from one compound to another. The methylation cycle is the name given to a biochemical pathway that contributes to a range of crucial bodily functions, including:

- Detoxification
- Immune function
- Maintaining DNA
- Energy production
- Mood balancing
- Controlling inflammation

Impairments or mutations on the methylation cycle can lead to problems with:

- ASD's
- Alzheimer's
- Diabetes
- Allergies and Asthma

An overload of toxins (including heavy metals), can contribute to the impairment of the methylation cycle, and if the methylation cycle is impaired the body is unable to detoxify as needed, therefore creating a vicious catch 22.

We need to help our children's bodies rid themselves of their excess metals as part of the healing process. Dr. Usman has shown us that heavy metals are present in the biofilm, and Dr. Klinghardt has shown that removing mercury can be directly related to a reduction in chronic infections.[2]

Let's get those metals out!

What exactly is Chelation?

Chelation is a process used to rid the body of heavy metals. It is described as a chemical process in which a substance (chelator) is used to bind molecules, such as metals or minerals, and hold them so that they can be removed from the body.

Some of the most common chelators used in the world of autism are:

EDTA

This is an amino acid that attracts lead, other heavy metals, and some minerals from the bloodstream and expels these toxic elements in the urine. EDTA works to remove excess lead from the body, but it is not specific to mercury or methyl mercury as are DMSA or DMPS. It can be taken orally, by rectal suppository, or IV.

DMSA

This is an FDA approved drug that can be used in children when lead toxicity is suspected, however it can also be effective at removing other heavy metals including mercury and arsenic. It can be taken orally, transdermally, or given as a suppository.

DMPS

DMPS is given to remove mercury from the body. It can be given IV, intramuscularly, subcutaneously, transdermally, or by suppository.

Patrick has been prescribed all of these at different points of his life, and I can't say that I saw miraculous results during the time that I used them. However, some families have seen results, and this is something you may want to discuss with your doctor. After years of using chelators, and seeing other families use chelators, I have opted for a gentle approach. I like to use two products: bentonite clay baths and Bio-Chelat™. These products are strong enough to help the body rid itself of heavy metals, but have not been shown to stress the liver or provoke undesirable detox symptoms.

Knowing now that metals are in the biofilm, I feel it is short sighted to focus solely on metals or heavy metals rather than all the pathogens in the biofilm.

Bentonite Clay Baths

Bentonite clay is sedimentary clay composed of weathered and aged volcanic ash. Bentonites are more widely known as healing clays used for detoxing, cleansing, and drawing out impurities. They are used in many everyday products such as toothpaste, antacids, and cosmetics.

Indigenous people have used bentonite clay for centuries; Dr. Weston A. Price in his book, "Nutrition and Physical Degeneration,"[3] stated that when studying the diets of native tribes he examined their knapsacks. Among the tribes examined in the High Andes, in Central Africa and the Aborigines of Australia, Dr. Price reported that some knapsacks contained balls of volcanic ash clay, a little of which was dissolved in water.

Bentonite is known as "swelling clay." When bentonite clay absorbs water and swells up, it is stretched like a sponge. Toxins are drawn into these spaces through electrical attraction and bound. In fact, according to the Canadian Journal of Microbiology, bentonite clay can reportedly absorb pathogenic viruses, as well as herbicides and pesticides.[5]

One of my personal favorites has been *Even Better Now*®'s product available at:

www.evenbetternow.com

> "EBN® Cleansing Clay is 100% pure sodium bentonite clay which has the highest cation exchange capacity (CEC of 98-107 meq/100g) of any bathing clay that we tested on the market. This clay is high purity air-classified sodium bentonite, selectively mined, consisting of micronized particles, which is a free-flowing powder. EBN® Cleansing Clay is 100% pure, hypoallergenic, and free of viruses, bacteria, yeast, and mold, as well as having a high cation exchange capacity."

There are other quality clays on the market, but EBN® tests every batch for heavy metals when it comes in. No, I do not receive financial gain from the company.

Bio-Chelat™

Another product I really like for gentle (low and slow) chelation is Bio-Chelat™. This is a German product containing a minimal amount of EDTA, which is FDA approved as a food substance. According to a clinical trial carried out in Germany:

> The therapeutic value of the Bio-Chelat™ in the context of other chelators that are currently on the market is seen as follows: Chelators work relatively fast, but they are also very strong with a relative high washout of important trace elements and a high degree of specific side effects. Bio-Chelat™ works much gentler than most common chelators.

> Although during the treatment a significant decrease of the body's heavy metal ion load was seen, this is accomplished without greatly disturbing the mineral and trace element relationships. The reduction of zinc should be looked at with caution and may easily be corrected throughout the treatment.[5]

I have seen very positive changes in many of the children who added in either bentonite clay baths, Bio-Chelate™, or both. As with any other intervention, add them separately while closely observing your child. Keep a log to record any changes, progress, or reactions you observe. Even if you don't see anything right away, I would keep using the products for a minimum of three months. Again, since they work LOW and SLOW changes may not be apparent at the outset, but that doesn't mean they are not helping to heal your child's body.

I use the CD baths every other day and then two times a week I do bentonite clay baths. I don't do the CD bath and the bentonite clay bath on the same day. I do them at opposite ends of the week.

Three days or so later, we'll add in the Bio-Chelat™. Again, follow the instructions on the package, and you can always start low and work your way up. Since Bio-Chelat™ doesn't alter the CD, the drops can be added to a single dose of CD. In addition, since the drops have no flavor, it is suitable to add them to water or any other drink your child might consume throughout the day.

Common Errors in Chelation:

Urine analysis without provocation:

Many families will do urine analysis to see if there are heavy metals present. If you have not done any chelation (oral or intravenous) you really don't get a good picture of what kinds of metals are actually in the body. Simply because the metals don't show up in urine, doesn't mean they are not present in the bones, the intestinal tract, the brain, and organs, etc. If we don't do any sort of provocation, we may end up with a false negative, leading a family to believe that their child is not metal toxic, when in fact they are. Bentonite clay baths and Bio-Chelat™ are gentle enough that they will not cause any harm to a child (metal toxic or no) but can greatly help reduce the heavy metal load, as well as other toxins in the body.

Healing the gut before starting chelation:

A doctor once told me that we had to heal the gut before we could start the chelation process. However, in the children that I have seen recover, probably up to the last month before they recover, their gut might still not yet be perfect. For example, one of the little girls that recovered continued to suffer from constipation at 30 days before she lost her autism diagnosis. However, at this stage something seemed to switch, she started having regular bowel movements and within 30 days she lost her diagnosis.

Basically we're healing the intestines as we're chelating, as we're healing everything else. They are all parts of the puzzle. I would never put chelation before the CD or parasite protocols. However, it's definitely something that's part of our road when, after these other approaches, children have not yet recovered. At some point after we have the CD, ocean water, parasite protocol and some supplements is when we can add in chelators. It's not like I'm saying, "Oh we'll talk about that in a couple of years." We want our children recovered in less time. It's like a marathon, we keep the pace, never lose our heads, or break into a sprint.

Do not chelate with constipation:

If the child suffers from constipation, it's really important that we start moving the intestines when we're using chelators. There are a few options open to us for moving the intestines. I have found that the most effective is through the use of CD enemas. If your child isn't having a daily bowel movement, I would do an enema once a day. If you absolutely can't do enemas, get that child in a CD bath. We're finding that 50 to 100 drops in a bathtub is allowing children who previously had constipation to have bowel movements.

There are a few children/adults on the protocol that will not do enemas, or the parent will not. Whatever their situation may be, we have to get the bowels moving again. In this case, we do 50 to 100 drops in their bath water along with their max oral dose every day. The result has been that they're having regular bowel movements. That's one way we can move it along and then you can keep chelating. It's really important to have a daily bowel movement with any kind of chelation because otherwise the toxins are simply reabsorbed through the intestinal wall, whether they're heavy metals or other pathogens.

IV chelation is not the only means by which to cure autism:

I think at one point between 2006-2008, we were all focused on the problem in the world of autism being the heavy metals, because there was mercury/Thimerosal in the vaccines. We had to get the mercury out of our children. Well, part of the problem is they're not detoxing. As mentioned before, methylation cycles are impaired in children on the spectrum. I met a young girl whose parents were both allopathic doctors and they really believed at that point, as most of us did, that heavy metals were the problem with autism. If we could get the heavy metals out then they would recover. The parents did 122 IV chelations and their child never improved. At this point I have lost touch with them, but these are things that we have to learn along the way. I know now that it is NOT just about chelation, and why metals are NOT the only important piece. All of the pieces play a role and likely interact to cause autism in our children. There is a symbiotic relationship between the viruses, bacteria, candida, and parasites that exist in the biofilm. Since CD can break down biofilm and kill the pathogens living in it, as well as neutralize heavy metals, it has been a very powerful tool for us.

Doing a blood test to look for heavy metals:

Generally speaking, within three days of heavy metals entering the bloodstream, the body will deposit the heavy metals into tissues, organs, and eventually bones. For this reason, a blood test is not the best place to look for heavy metals in children with autism. Unless the child has very recently been exposed to heavy metals, we are unlikely to see elevated levels of heavy metals through a blood analysis.

The articles at the end of this book (Appendices 13 & 14) will provide further insight as to why chelation can be so important for our children on the spectrum.

Healing
the symptoms known as
Autism
Kerri Rivera

Luca

Chapter 11

Step 6 - Hyperbarics

by Bob Sands (Introduction by Dr. Beatrice Golomb)

> *"What Oxygen is to the lungs, such is hope to the meaning of life."*
> ~ ***Emil Brunner***

We were fortunate enough to have the amazing Bob Sands write this chapter on hyperbarics explaining its importance in healing ASD's.

Note: Throughout this section of the book, the author, Robert Lyne-Sands uses the actual names of the people with whom he came in contact with. In some instances it is with their permission, in others it is not. The accuracy of quotations, opinions expressed within this chapter, and the names used are solely the responsibility of Robert Lyne-Sands. Great care has been taken to remain within the bounds of current journalistic integrity and practice.

Robert Lyne-Sands new book, *OXYGEN: The First Medicine, Volume 1 CANCER*, is expected to be released January 2014.

Robert Lyne-Sands author of the Hyperbaric section of the book, with one of his young patients, getting ready for a session.

Robert Sands is one of only about five licensed manufacturers of hyperbaric oxygen therapy (HBOT) machines in the US, with extensive experience in clinical hyperbaric treatment, whose expertise will be an exceptional asset to this project. He has designed and manufactured HBOT machines for the US, Australia, Britain, Thailand, and many other nations, for naval/military use, civilian diving use, and medical use. He has the theoretical understanding of HBOT therapy that derives from intimate involvement in the process of designing and manufacturing these machines. He has the practical experience that derives from running a set of HBOT centers, and personally overseeing greater than 20,000 hours of HBOT sessions over 35 years.

~ Dr. Beatrice Golomb, MD, PhD.
Professor of Medicine. UCSD 2011.

Beatrice Alexandra Golomb, MD, PhD (PI) is singularly qualified to lead this study. She has expertise in GWI including authorship of four RAND reports related to GWI29-31, and work in the scientific literature. She has been a member, since its inception, of the Department of Veterans Affairs Research Advisory Committee on Gulf War Veterans' Illnesses, and served as Scientific Director of this Committee. As a licensed internist, she is a primary care physician for a panel of ~280 veterans, including GWV, at the VA San Diego Healthcare Center.

Recently, I sought the answer to something that was puzzling me. My friend, Dr. Bernard Gunter, is a revered and renowned psychologist in his eighties and, if anyone would know the answer, Bernard would.

"Does God, Great Spirit in the Sky, The Universe or whatever unseen deity you worship give you freedom for personal choices or is everything predestined?"

Bernard's eyes twinkled. He was never in a hurry to answer a question. In my mind, Dr. Bernard Gunter is sort of the American version of the Dali Lama.

He thought for a moment, selecting his words carefully, and then replied, "Funny you should ask that—just the other day I was talking with Eckhart Tolle and asked him that very same question. Tolle replied, 'God allows you to think that you have free will and free choice—and you do, by and large. However the roadmap is laid out for you beforehand.'"

Just as I suspected.

Dr. Bernard Rimland, Kerri Rivera, and the Hand of God.

On January 20th, 2006, a tall, glamorous woman walked into my San Diego clinic; her name was Kerri Rivera. She had brought her small five-and-a-half-year-old son, Patrick all the way from Mexico for hyperbaric oxygen therapy. The little fellow was absolutely gorgeous, but had a vacant stare and made no eye contact with any adult, rarely even with his mother. Day after day Patrick spent time in the chamber.

Kerri explained to me that Patrick developed normally for almost the first two years of his life. Then, to comply with vaccine regulations, Patrick received the DPT, HepB, and Influenza B (Pentavalente) vaccines in one day. Patrick fell into a complete zombie-like state after the injections. By the time Kerri arrived in San Diego, she had already done her homework. She blamed the vaccinations and had already undertaken the task of healing her son.

After her own experience with autism, Kerri wanted to help people and she was already doing the DAN! Protocol, etc., as Dr. Rimland has done so much for the children and she had a lot of respect and admiration for him and his work.

One day, I walked into the clinic and told her, "We're having lunch with Bernie tomorrow. Get a babysitter." At that point, totally shocked, she said, "Oh my God, yes, but I don't have anything to wear!"

"Trust me, what you have on would be just fine." A flustered Kerri rushed off to purchase some dressy clothes—she was, after all, a woman originally from Chicago. The very next day, we were sitting with Bernie and his wife Gloria in a quaint little restaurant, *The Green Tomato*. If the reader wishes to see that day, just go to your computer and look up Bernie on Wikipedia and there you will see Kerri in her black business suit (http://en.wikipedia.org/wiki/Bernard_Rimland).

Over lunch, Bernie and Kerri bonded immediately. None of us at the table realized that Bernie was suffering from cancer and had less than a year to live. Driving the short distance back to my clinic I made the observation to Kerri that I suspected she was about to become a scientist, and no longer just a trophy wife. "Be careful," I warned her, "Bernie Rimland's mantle will be heavy on your shoulders."

Kerri turned her face toward me and said, "I will carry that mantle willingly and with honor."

After a few days, Bernie told me that he thought Kerri had what it takes to carry the torch and help families heal their children with autism. I saw a lot of Bernie in the next nine months. He would come down to the clinic for regular hyperbaric treatments because it eased the pain of his cancer. Just before his death, he told me, "I will not die before I have found the reason for and defeated autism." But die he did on November 21, 2006, at the age of 78.

As I drove to Bernie's grave, I anticipated many, many people lining the way with some hundreds even thousands thronging the memorial park, similar to Giuseppe Verdi's funeral, in 1901, where 200,000 people gathered. At his graveside, the thousands of mourners spontaneously burst into the "Slaves Chorus" from his Opera, Nabucco.

I was stunned upon arriving. Probably less than thirty or so weeping caregivers of children with autism were present at the burial, along with Gloria and Bernie's three children. WHERE WERE ALL THE PEOPLE, THE MOTHERS AND FATHERS, THE RESEARCHERS AND SCIENTISTS? I asked myself. It was my first Jewish funeral and I think that the booming sound of the shovel full of earth that I threw down onto his plain casket made me look heavenward and ask, "God, where are you now?"

I drove home, eyes unfocused with tears, and stone eggs of the birds of unhappiness in my heart, stopping only to purchase two fine bottles of wine to toast Bernie. I knew one would not be enough. Arriving at my house, I found the fine crystal goblet my Mom had left me, filled it, and played Neil Diamond's, Morningside over and over, with each playing, another glass, held high to Bernie...

Morningside
The old man died
And no one cried
They simply turned away

And when he died
He left a table made of nails and pride
And with his hands,
He carved these words inside
'For my children'

Morning light
Morning bright
I spent the night
With dreams that make you weep
Morning time
Wash away the sadness
From these eyes of mine
For I recall the words an old man signed
'For my children'

And the legs were shaped with his hands
And the top made of oaken wood
And the children
That sat around this great table
Touched it with their laughter
Ah, and that was good

Morningside
An old man died
And no one cried
He surely died alone
And truth is sad
For not a child would claim the gift he had
The words he carved became his epitaph
'For my children'

In fact, as I sit here writing this, I play Diamond's melody and listening to the words makes my heart swell and my eyes become damp.

The morning after Bernie's funeral, hung-over and miserable, I pondered: Did my beloved friend Bernie die feeling that he failed? I now doubt it for he had passed his mantle to carry on his search for the cure without fear, without the need for accolades and rewards and to do so with integrity. I did not know it, but before his passing, Bernie and Kerri had been in communication. Bernie had given her permission to translate his *Defeat Autism Now!* Protocol into Spanish, Kerri's other language, as well as other tasks.

In review, I now see God's Hand at work—and it started one afternoon at the Green Tomato. Thus, my question to my friend on free will versus predestination right at the start of my notes on this section.

Brain overload and frozen fingers.

At the time, when Kerri asked me to write this section of her book about hyperbaric oxygen therapy and the treatment of challenged children, my mind went into overload. Why? Kerri was (in my view and that of others) the most efficient and effective health scientist with a high normalization rate of challenged children (autism, etc.). With her own hospital-quality hyperbaric oxygen center, Kerri had first-hand knowledge that to normalize such an afflicted person required a lot more than some trips in a oxygen chamber or some Silver Bullet response from a pharmaceutical company.

My brain whistled like an express train rushing through a tunnel. I thought of the dozens of children that hyperbaric oxygen therapy has helped at my different centers. Some of the little guys were so badly damaged they would repeatedly punch at their own head, or chewed on their own wrists. I'm thinking of Marco as I write this. Ten years later, he still punches. A clearly defined casualty of a hotshot thimerosal vaccination, normal until three, his parents won a multimillion-dollar lawsuit against Big PHARMA. There has been some progress over the years; but it will be a matter of unrelenting attention to Marco.

I remember another little guy; a handsome, articulate smiling boy of about 12 years of age named Chase. Meeting him and his parents, you would never know he had autism or ADHD. Chase was a "runner." When his treatment in the chamber was over, he would promptly disappear out of the clinic doors. Eventually, Chase would be carted back down by one of the upstairs nurses. "Chase" by name and chased by nature.

After one such session in the chamber, he rocketed out and into the restroom of the clinic. I was sitting at the controls when he came back. Chase climbed up onto my knee and said, "I love you Bob," and he rubbed his hands across my face. From the terrible odor I knew in an instant what was all over my face and my lips. Chase had used his hands instead of toilet paper and bypassed the washbasin on the way out.

"Oh goodness," came from his horrified mother. "He got you. I am so sorry. It is one of his favorite jokes."

"Not to worry," I said, "I have eaten and tasted this in a variety of forms most my life." So, whenever I hear somebody say, "Sands is not a Doctor so he doesn't know s—t from Shinola," I think of Chase.

Normalizing kids is so rewarding, but you have to take a chance on s**t.

My fingers were not ready for the keyboard as I tried to wade through dozens of experiences with these children, my own personal experiences, and finally adding input from experts in the field of pediatric abnormalities. (Many of these experts became my close, personal friends as the years went by.)

For any parent or caregiver to delve into all of the opinions and conclusions of the so-called experts, it is a bewildering journey through a lot of contradictory and self-serving educated guesses and erroneous assumptions. To arrive at something that the reader will identify with, and believe in, I have to go way back. After 70 years on the face of this planet, I have reached certain conclusions about the treatment of children that enables me to write this section. Mind you, I'm not stuck in my ways and I am open to change my thoughts and conclusions as the science improves on treating children with autism.

Little Patrick Rivera, Little Bobby Sands Something in Common?

Here is something that I doubt my adult children even know about. In 1947, polio was raging throughout Australia. I was seven years of age and had developed a sore throat and fever. My father, a wealthy man, called the very best doctor to my bedside—yes physicians did make house calls in those days. I can even remember the doctor's name, Dr. Bradfield. His father had been the engineer that designed the Sydney Harbor Bridge. My dad, with all of his money drew a lot of water in those days and could get almost anything he wanted. Bradfield came in and examined me briefly; after all he had other house calls that night.

Bradfield told my Mom and Dad that he did not think I had polio, but perhaps diphtheria and that I should spend time in isolation in the infectious disease hospital overlooking Botany Bay, "just in case." The next morning an ambulance came and, in spite of my fear, pleading, misery, and tears they carted me away. The three-hour journey became a six-hour journey. The ambulance broke down outside the Sydney airport. I remember looking out of the rain spattered window and seeing the aircraft clearly visible over the fence. We sat on the side of the road for almost two hours before the replacement ambulance came to transport me, and my journey continued to a huge colonial building complex, built by convicts and perched on rolling, green lawns that looked down onto the Pacific. The complex was known as, The Coast Infectious Disease Hospital, which later became Prince Henry Hospital. I was terrified and clutched my teddy bear, *Threadbare*, under the blankets. Threadbare became my only friend for the next four months, and a glimpse of airplanes over the fence became an enduring memory of the trip.

My parents were already there and had obviously filled out all of paperwork. I never got to say goodbye to them since it was an infectious disease hospital. As they walked past a big hopper window, they paused momentarily and Mum waved through the window. I saw them maybe three times in the next four months when the nurses wheeled my bed up against the window that looked out into the hall. They would tap on the glass and smile at me but because my father was quickly bored, after about five minutes they would wave and be gone for another couple of weeks. It was a long way for them to travel.

The night of my arrival, a team of doctors and nurses arrived and they rolled me onto my side. Full syringes lay on a tray; in those days they were glass with little thumb and finger holes on each side and each needle was reused and supposedly resharpened before their next use. This meant that the needles were thick and long. One-by-one these needles were inserted into my upper thigh on the left-hand side. The pain was agonizing and I'm sure I screamed and screamed. I remember at least three nurses holding me down. At seven, I was just a little fellow. There had to be at least 20 of these very large syringes. Checking the history books, I believe that they were mostly penicillin and sulfa drugs. I might add, it was already known to Doctor Bradfield that I was highly allergic to sulfa and remained so for my entire life.

The next morning, when I awoke, I found that I was paralyzed from the feet up to just under my arms. Threadbare was my only friend for the next four months. The days all blurred together. One thing I do remember vividly is that I used to deliberately wet the bed. I did so only when a lovely red-haired nurse with a band of freckles across her nose was on duty. This nurse was kind and gentle, probably in her twenties. After she had changed the sheets, she would stroke my cheek and tell me that everything was going to be okay and not to worry about wetting the bed. The other older nurses scolded any of the other pediatric patients if they had an accident. At some point later, my gentle nurse told me that I really did not need to wet the bed to get her attention. I soon stopped and I still got a cuddle from her. Such a display of care and affection was unknown to me from my parents back at home.

After that stay in the hospital, I was never the same. I know that there was constant discussion amongst my family members that I should be placed in some sort of an institution because my behavior was "contrary and stubborn." I was either talking my head off, trying to make my family love me, or distant, and as such, I was said to be "uncooperative." Soon after, I was placed in a Hogwarts-style boarding school.

Could that childhood experience have made me what I am today, forever alone, but rarely lonely? As the years ticked by, to my surprise (and I think everybody else's), the school counselors found that I had a genius IQ. Amongst the 1,200 boys, I was second from the top.

After seventeen years of treating so-called challenged children, I have yet to find one that was not as smart as a whip in something.

I managed to burn every social bridge at the boarding school, thrown out of every special social club at Newington. On Saturday afternoon, after mandatory sports such as Cricket or Rugby, the other boarders would get to do things they wanted like billiards, photography, or gardening (these were clubs that you had to apply for and join). However, I had been expelled from each of them so I wandered alone each Saturday afternoon and finally picked the lock on a large room-sized cage full of Sulfur-Crested Cockatoos and other Australian parrots. I would sit alone with them and be jeered at by the boys in the garden club that were planting and weeding. Within weeks, these birds would happily climb all over me, enjoying my company. The birds loved me, but the boys and masters did not. To me, it was a two-way street. Animals made better friends than people. Eventually some of the other boys would come and beg to be allowed to accompany me into the cage so they too could have that same privilege.

Do not get the wrong impression of my beloved Newington College in Sydney Australia; even today I dream of the sanctuary of that place. It was better than what I had with my family back home.

The really curious thing is that my mind had blotted my hospital stay out, or had hidden it in some black cabinet in my brain where the really bad things are kept to allow me to get on with the reality of NOW. I remembered the illness and isolation only when Kerri asked me to write this. The details have returned with clarity: the old iron beds, the smiling face and freckles of my favorite nurse, being cold at night, the colors on the wall, the distant sight of the ocean through a window on the other side of the big ward, the frame of the window so far away that it looked like a painting hanging there. If I close my eyes as I write I can see it now.

I now ask myself, "Is this the way children with autism feel?"

I don't know. What I do know is that my old friend and confidant, teddy bear, is sitting on the desk as I write this. I reach out to rub Threadbare's head and a great calmness washes over me. The little fellow is 64-years-old now and there is a great competition amongst my adult children to see who gets him after I die.

Botched diagnosis
The incorrect pharmaceutical response.

With almost 40 years of working in medicine behind me, and now in my retirement, I do know that neither diphtheria nor polio were the problem. The suffocating "Bull Neck" or the "Strangling Angel of Children," diphtheria, had not happened to me, nor did the withered limbs of poliomyelitis set in after paralysis.

Simply put, Dr. Bradfield cocked it all up in a big way by guessing, not taking enough time and arriving at the wrong medical response on his visit. The relentless attack on me with sulfa drugs caused paralysis, which was probably what is commonly known today as Guillain–Barré Syndrome, a disorder affecting the peripheral nervous system. Ascending paralysis, weakness beginning in the feet and hands and migrating towards the trunk, is the most typical symptom; the disease is usually triggered by an infection.

It sure sounds similar to what happened to little Patrick, and probably to the reader's challenged child as well.

Migrating to America in 1990 with my tribe of offspring.

I arrived in the United States over twenty years ago. If the reader is interested enough, a quick look at a funny but classy "roast" presentation is on YouTube. You can find it by searching "Robert Lyne-Sands" on YouTube.

After completing the United States Navy transportable chamber development project, I arrived in swank, Pacific Palisades, on the outskirts of Los Angeles; living amongst all of the Hollywood greats. I was going nuts with boredom and became the "Bob Clampett" of the area; jogging down the leafy streets I always said Gudday to any celebrity. I rarely remembered their names but knew their faces. They never replied on the first go past, but then I would jog backwards, keeping pace with them (big stars like Madonna always ran with a group of minders) and I would yell out "I said Gudday. My goodness, your manners are appalling." I might add, it was not just me; they never ever nodded to each other when their paths crossed either.

Around this time, I opened the very first freestanding hyperbaric oxygen therapy center. It was more or less hidden away in Santa Monica on 6th Street. Tucked away in what used to be an old motel, you could almost refer to it as a "speakeasy" center, akin to something from the days of prohibition, where you had to knock on the door three times before being let in. I would only treat people who had been referred by another patient. Most of these people were from the entertainment industry in Hollywood, many with the HIV virus, and lots of folks with chronic fatigue syndrome.

The kiss of death in Hollywood is to be known to be ill. Hyperbaric oxygen therapy works so well that the word soon got around, and I was inundated with patients, some famous and well-known, and others just hardworking folk in the movie industry. Thus, I ended up being known for some years as "Mr. Oxygen," and because of the remarkable effects of HBOT, I befriended many of these celebrities, who subsequently invited me as their guest to many of the big Hollywood functions (the only one that I missed was the Academy Awards).

One of the first of these talented people that became my close friend was Harold Michelson. Harold was an award-winning art director working out of DreamWorks. He was suffering the aftermath of a mild stroke. His wife Lillian had told me that her Harold loved crossword puzzles, but since his stroke he would put the across answer in the down column. This caused him immense frustration since his answer was usually correct, just in the wrong place. Five treatments in the little chamber were all it took for Harold to get his verticals and horizontals in the right place. The big thing that he noticed was that his blood pressure stabilized, his lung problems normalized, and he needed less medication for his diabetes.

Harold still stood well over 6-feet–tall, though stooped with old age. We hit it off immediately because Harold had a quick wit and loved a good laugh. The stories and banter between us were constant. Harold was extremely talented yet self-effacing. He really was a hero in the truest sense of the word. As young man, he made over 40 flights across the English Channel to bomb Germany. As navigator, Harold sat in the nosecone of the B-17 and either froze with the cold on the trip or froze with fear when making the lower-level bombing run. "Bob, I was so frightened of the flak from the antiaircraft fire from the Germans on the ground. As the puffs of smoke would erupt around the front of the aircraft, shrapnel would pierce plexi-glass windows in front of me. I would hold the navigational map in front of me and try to believe that the thin paper would stop the lethal fragments."

The first challenged child to be treated in a hyperbaric chamber—Emily.

I need to jump forward in time for a moment before getting back to Harold Michelson and his wife, Lillian. I went back into production of hyperbaric chambers after I realized the great need for hospital-grade dispensing of oxygen to the public. There were no rules preventing me from doing this even though I'm not a physician. All my patients needed was a prescription from a registered physician; that was the easy part. My first center was in San Diego.

In the first few months of patient treatments we received a call from a father in Canada. His daughter, Emily, had cerebral palsy. The father had read that hyperbaric oxygen therapy would perhaps help his little girl normalize, and so when he asked me what I thought I gave him my usual answer, "I do not know, I am not a physician." And then I added, "I would hate for you to waste your money on a trip from Canada to San Diego if it doesn't work."

The father replied, "I have two choices. I can go to England where there is snow on the ground or I can come to San Diego. It is an easy choice to make."

So father and daughter duly arrived. Emily was the most delightful child. When she walked through the door she had a crash helmet on, knee guards, and wrist-guards to prevent serious injury when she would crash, face first, into the floor. We learned a lot in the first ten days of treating Emily. One of the first things was the fact that fathers can never properly do a good job on their daughter's hair. I felt for the father since Emily had lots and lots of hair and was never still for a moment (I have a few daughters myself). Emily would arrive looking like a rag doll; her little blonde head would have pins, bits of string and ribbon through it. So the very first task of our nurses would be to grab Emily (usually tearing around the clinic), and comb her hair out to make her more presentable.

Now, the really big thing that we noticed was that on day ten she arrived at the clinic without any of her body armor. Yes, she still "toe-walked" because her heels did not touch the floor. To compensate, she would park her little fists against her chest, push her elbows out to keep a center of gravity, and rush around the clinic. On day 11, father and daughter spent five hours at the San Diego Zoo without the usual body protection. Emily never lost balance or tumbled even once. Follow-up visits over the last 17 years find that Emily is living a normal life. Yes, she still has some walking problems, but never needed to undergo the mutilating surgery that was recommended to her by her Canadian doctors. During 20 days of hyperbaric oxygen treatments in San Diego, something had changed in Emily's brain.

Likely the most important introduction in my life... The Great-Spirit-in-the Sky's (God's) hand at work.

Listening to the improvements that little Emily had made, Harold Michelson was both enchanted and excited.

"Did you know that Lillian and I have an autistic son? We need to introduce you to a couple of people in San Diego. Dr. Eric Courchesne, who runs the autism research center for the University of San Diego, known as the Autism Center of Excellence or ACE."

Lillian chimed in and said, "I really must call them about you. Eric is a gem and his wife Rachel is also a research doctor. They work side-by-side and will be so helpful."

With Emily's positive results, and more children making gains at the center, I called the Courchesne couple at the ACE and offered to provide them with the use of a $150,000 hospital-grade hyperbaric chamber for one full year. There was no response to my offer.

While you may imagine that the UCSD-ACE Research Center is located in some lofty center of learning, it is in fact to be found in a delightful millionaire's village known as La Jolla in Southern California, a block or so from the Pacific Ocean. On the top floor of a three-story building, an elegant balcony ran across the front of the building, while red and white umbrellas and tables make it look more like a posh restaurant than a research center.

I waited about a month and called again and repeated my offer of a hyperbaric chamber, operated by trained technicians for a year, or whatever time it took to make a decision on efficacy, at zero cost to the ACE. About an hour after making the second call, my secretary told me that a Dr. Rachel Courchesne was on the line and needed to speak to me on an urgent matter. I picked up the telephone, anticipating a good conversation but this is the way that it went, all one-way at me. Dr. Rachel was in fine fury and, looking back, the only way I could have put a word into that conversation would have been to fold the word flat and slip it into the tirade, sideways. She told me that it was amateurs such as myself that muddied the scientific waters of autism research and that, essentially, I should crawl back into whatever hole I came out of.

She made it clear to me that the mission of the ACE was to perform research to find a cure with pharmaceuticals. In fact, the ACE receives funding from drug companies, and that I should not bother them again. I was taken aback, to say the least.

A decade later, Dr. Eric is apparently doing fine work. For example, in his recent research, quoted widely in the media, he has found that the frontal lobes of an autistic child's brain is abnormally large. This is an observation, perhaps useful in the future, but only time will tell. But does it matter to you the reader whether this is so? Maybe yes, maybe no, so let's hold off on that sort of thing until we get into the scientific part of the book.

Let's get back to Dr. Rachel's harangue of me. In my mind, there is no doubt about the fact that for her, at least, it was all about the money and the potential for a patented silver bullet for Big PHARMA. If successful, a drug company could charge you a huge amount of money to heal your child with autism. At worst, there would be the ability to raise more money for research despite scant evidence of clinical results on children.

An example of this ability to raise money on a potential medical marketplace is the fact that in the year 2012, the National Institute of Health (NIH) allocated $100 million over a five-year period to a bunch of ACE research across the United States. So much for Lillian's glowing endorsement of Dr. Rachel.

However, the Michelson's other introduction proved to be a link in the chain.

Autism research with integrity—Dr. Bernie Rimland.

"A dear friend of ours, Dr. Bernard Rimland, also has a research center in San Diego which he calls *Defeat Autism Now!*, or DAN! for short. Bernie's son, Marc, is a true autistic savant. The movie with Dustin Hoffman and Tom Cruise, Rain Man, was modeled around Bernie and Gloria's son. Bernie was the technical advisor for the film. You must meet Bernie."

Lillian was especially grateful and fond of Bernie and his wife, Gloria. Back in the early 1950s, autistic children were attributed to cold, hard, heartless mothers. Many psychologists and psychiatrists agreed with the "Emotional frigidity" hypothesis, which suggested that the mothers were the cause of what we now know as autism. A lot of children in the United States were taken by force from their parents, and placed in isolated institutions to "protect" them from their parents. Bernie Rimland alone stood against this hypothesis; after all Bernie did have degrees in psychology, including a PhD. In fact, it was Bernie that took away the shame, the blame, and the guilt of many loving parents who were bullied into believing labels put upon them by the so-called "learned."

Driving forces behind autism research centers.

Unlike the La Jolla location for the ACE, Bernie's Autism Research Institute (ARI) was about five minutes drive from my San Diego hyperbaric oxygen dispensary; two minutes of freeway, a quick turn into Adams Avenue, and I had arrived. Again with an erroneous assumption, I had thought that Bernie's ARI would be similar to the ACE La Jolla location. In fact, I drove past Bernie's place three times before I found it. An unassuming, clay-colored, converted storefront, with a little sign on the front door that said, "Autism Research Institute." I knocked on the door and walked in. Instantly, the smell of antiquity and old books overwhelmed me and beguiled me, like something out of a Harry Potter movie. Stacks of papers were high on the floor almost in a willy-nilly fashion. A gentleman dressed in a checkered shirt came towards me. "Bob Sands? The Michelson's said to expect you." He peered over his glasses and gray whiskers at me. In that one glance, we created a bond of friendship that lasted for more than a decade. At least once or twice a month we would lunch together along with his wife, Gloria; always two blocks from his Center, at the *Bleu Boheme*. Bernie and Gloria would carefully examine the menu and then they would both look out and recommend, "Let's all order the fried green tomatoes."

Bernie was interested in clinical results. He would turn over any stone that would perhaps unlock the mystery of autism. When I first met Bernie, 1 in 850 children born in the United States was afflicted with this mysterious and terrifying disorder. As I write, autism spectrum disorders have spiked to 1 child in every 88. So when the phone rang at the ARI, Bernie would often answer it and ask many questions, if the person believed that they had found a cure or a clue. He never discarded anything, in stark contrast to my encounter with Dr. Rachel at the ACE in La Jolla. I once listened in when he spoke with a lady who believed that you could cure autism by filling crystal glasses to different levels and rubbing your fingers around the edges to create pure tones.

Bernie put the telephone down and said to me, "It could be worth looking into. Music does create new neuronal wiring in small children, for example, or a mother singing to a child." I had already mentioned to him that when a child with autism was in the chamber, if you played unfamiliar sounds such as whale songs, or bagpipes, the unresponsive child would often brighten up and look around.

"Maybe new neuronal connections are being established," Bernie pondered as he rubbed his whiskers.

In those days, I worked on weekends. If I wanted to chat with Bernie, Sunday was the best day. No staff to answer the telephone, so he always did. I once asked him whether he took a day off and his response was succinct:

"When autism takes a day off so will I."

Bernie, a $2.6 million donation and his ARI.

Now, here is the most interesting of Bernie Rimland's driving forces—to me at least. It was not about dollars or ego, not in the slightest.

At that time, I was also friends with another Bernie, the renowned anthropologist, Dr. Bernard Aginsky. To avoid confusion between the two Bernie's I will refer to him as Dr. Aginsky. He was in his late 90s at the time, as rich as Croesus. For many years, he had leased the penthouse of the La Jolla Shores Hotel, right on the beach of one of the most desired parts of Southern California. Again, like most of my friends, Dr. Aginsky was a humble man and thought nothing of his wealth other than as a means of accomplishment. Out of the blue, one day in my office, Dr. Aginsky looked at me thoughtfully and then asked, "I have $2.6 million and I want to give it to somebody that would make a difference. Can I give it to you?"

I immediately thought of Bernie and the children with autism and the nonprofit status of the Autistic Research Institute. "Hold that thought Dr. Aginsky. I will give you an answer in a couple of days."

A couple of days later, Bernie and I were traveling to take part in a medical internal review board. I was wearing a shirt with French cuffs and a silk tie. Bernie had on his usual checkered shirt. He confided in me once that he had to make a choice between wearing a tie or trimming his Santa Claus-gray beard. The beard always won. Wondering about his shirts, I respectfully asked him whether he ever received a salary from his ARI.

"Good gracious. I could never pay myself a salary from ARI funds and donations. You must remember that I am on a full Navy pension so it would be wrong to double dip."

After the meeting, as we traveled back along the I-405 to San Diego, I broached the subject of Dr. Aginski's offer of a $2.6 million donation for the Autism Research Institute. Bernie looked out the window for a few moments and fiddled with his beard. I could see he was calculating in his head. He turned to me and said, "We have so much money in the ARI at this time, donations and such, that I think that amount of money could be used elsewhere. Find another recipient."

Dr. Bernard Aginsky, a widower, passed away in January 2000. I have no idea where his donation ended up. I do know whether Bernie Rimland ever had a second thought about not taking that money. He never mentioned our conversation again.

DAN! changing to parallel other autism research.

Research costs money. Bernie used his resources wisely and was not interested in empire-building. He just wanted to find the cause and the answers. Bernie cured kids.

On the anniversary of his death, I went to his Kensington ARI center. I had two bottles of good wine, a bunch of wine glasses, and a whole lot of chocolates. I walked in and was astonished. The whole tenor and tone of the place had changed. The clutter was gone. Bookshelves were neat and organized. The smell of scholarly interest in documents and old books had evaporated. It was as if the ghost of Dr. Bernard Rimland seemed to have moved to another place completely. The staff were delighted to see me, and happily munched on the yummy chocolates that I had brought for them. I commented on the neatness and the vast changes that I observed. One of the staff shrugged her shoulders, grimaced, and said,

“You have no idea just what changes have taken place, and what is about to happen.”

An example of the transformation in attitude is exemplified by an offer for inflatable, aka soft-sided, chambers for DAN! while Bernie was still alive. One day, he called me up and explained to me that a group was coming to do a presentation on these soft chambers, and suggested that I plant one of my staff at the ARI to listen to the blurb from the manufacturer, Oxyheal. My secretary, Crystal was waiting amongst Bernie’s staff to greet the technicians, doctors, and such that accompanied the owner of the company. They arrived at the ARI, set up the inflatable chamber, and gave their sales pitch, extolling the virtues of hyperbarics at low pressure and at a low cost.

Crystal reported back to me that Bernie looked dour during the presentation and asked, “What would happen to this with a razor blade?” Bernie and I discussed the concept of inflatable chambers the next time he was at my center, after he had finished his treatment in a chamber. He was not convinced about the soft-sided chambers.

“I worried that the scientific data that they quoted was all from hospital quality chambers. I think you are correct Bob, the physics do not hold up. I could not recommend this device to parents for their children.”

The “discovery” (observation) of God’s gunpowder + Bernie Rimland and Kerri Rivera.

Throughout history, air was taken for granted. You just breathed in and out and there it was; bugs and birds flew in it, mostly useful to keep your floors and ceilings apart. Even in this day and age, many folks think of it in the same way.

Let´s revisit what is now called the Age of Enlightenment, the 17th and 18th Centuries. About 1774, the kindly and soft spoken clergyman/scientist Joseph Priestly and his close friend Benjamin Franklin. They spent time drinking coffee together once a week in a London coffee house along with other scientists. Together they realized that air was actually a mixture of gases, but mostly nitrogen and oxygen. Priestly and Franklin could kill a mouse in a glass jar in less than five minutes by depriving it of one of those gasses. Put the poor little mouse in a glass jar with a lit candle (which consumed the oxygen) and the flame of life in the mouse departed by about the time the candle went out.

Using precise scales, Joseph Priestly and the French chemist Antoine Lavoisier, gave oxygen its name. It could be weighed on a scale just like you would weigh out a cup of rice. Each unseen gas has a weight. Baros is the Greek word for weight. Words that we are familiar with come from this: barometer, barometric pressure, and hyperbaric (as in hyperbaric oxygen therapy, hyper meaning more than and baric meaning weight of the gas).

Weigh oxygen?

The weight of air (mixed oxygen and nitrogen) is 14.7 pounds per square inch at sea level. Most folks like me would prefer to use the word pressure, however, the math is easier if we use the doctors measure (the same as that used in measuring blood pressure – millimeters of mercury or mmHg). An average blood pressure measure is typically 120/80 mmHg. Let's look at it this way; if air at sea level is 760 mmHg, then 20% of that air (oxygen) is 20% of that amount. So multiply 760 by 0.20 and you will realize that vital, life-giving oxygen going into your lungs is about 150 mmHg.

Oxygen - You cannot see it, or smell it but you have to "eat" a kilogram of it each day to stay alive.

Make no mistake. If you take a substance into your body, ALL of your 60 to 90 trillion cells will be affected. Snort it, chew it and swallow it, breathe it, or inject that substance and it will have a positive or negative effect on your whole body. Cells "consume" the substance. Another word for consume is "eat." We will discuss this process, known as oxidative metabolism shortly and, especially how to produce stem-progenitor cells.

Eat oxygen?

Oxygen is a cellular food. The adult human consumes approximately 0.6 kg of oxygen each day (about 1.2 pounds). We can live about three weeks without the food that we chew and swallow, survive three days without water, but we can only live approximately three minutes without oxygen. Body cells start to die—the brain is the most vulnerable. Even a minute or so without oxygen can cause permanent damage.

Don't worry about the earth running out of oxygen. Back in the 1700s Ben Franklin and Joe Priestly also discovered the fact that sunlight on green vegetation produces oxygen—a process called photosynthesis. They showed this with the mouse and candle in the glass jar. As the candle flame seemed to flicker, about to go out and the mouse lay, apparently dead, if there was a sprig of a green plant, both the candle and mouse came back to life. All of the oxygen that you are going to eat in the next 24-hours is replaced by just one square meter of grass producing oxygen through photosynthesis during that same length of time. In populated areas, where there is not much greenery, life-sustaining winds carry oxygen over the oceans and hills to all humans and animals.

Captain Cook, Joseph Priestly, Bernie Rimland, and Kerri Rivera—Explorers

Before we stop talking about Joseph Priestly, he made another observation about gas and this applies to our subject of autism, Bernie, and Kerri.

Living next door to a brewery, Priestly was intrigued about the gas given off by the fermentation of beer in the barrels. He put a dish of water under the vent-pipe coming out of the barrel. When he tasted the water it was full of refreshing bubbles we now call fizz. In 1767, Priestly discovered how to carbonate a liquid. He taught the Navigator, Captain Cook, how to carbonate water and, thinking that drinking that bubbly water would prevent scurvy, Cook set sail with it in 1772. It did not prevent scurvy, but, just like Bernie and Kerri, everything is worth investigating.

We now know that any gas becomes soluble if it is concentrated or made thick. In this instance, the gas was an extremely light gas known as carbon dioxide (yes, the stuff we breath out and, unlike the 21% oxygen, there is only about .033% of carbon dioxide in the air we breathe). However, if you concentrate it to 100% some of it melts into the water and becomes carbonic acid, as is the case with soft drinks. Pop the lid and the acid turns back into carbon dioxides gas, forming little bubbles in the liquid. Joseph Priestly should have patented his observation. Ten years or so later, Joseph Schweppes patented the process in Germany and most folks think of him, not Priestly, when they have a gin and tonic.

Thereby hangs another Newtonian rule about gas that cannot be changed. "Gas under pressure becomes soluble in a liquid according to its density (or thickness)." – Henry's Law.

And this is how oxygen works in a hyperbaric chamber – Newtonian Gas Laws

Stay with the soda can thought and the thicker gas melting into the sugary drink. When a human climbs into a hyperbaric oxygen chamber, we substitute oxygen for carbon dioxide. Believe it or not, you do not feel squashed by the pressure other than you have to "pop" or equalize your ears. Humans are mostly water and other fluids that cannot be compressed like a gas. What is happening in the chamber is that the oxygen (it should be 100% oxygen) is being made thicker or concentrated. And, just like the soda, Henry's Law kicks in. The oxygen melts and the body supersaturates with oxygen.

Another curious thing about a well-oxygenated body is that it becomes slightly alkaline. Your powers of hydrogen (pH) read about the same as seawater, which is alkaline because of the dissolved oxygen in it. Yes, even fish need their daily meal of oxygen!

The word "saturate" comes from the Latin word meaning "to completely fill." Since only our red blood cells (RBC) carry oxygen, they are almost always full of oxygen in a healthy human. The little pulse-ox device that clips on your finger when you are in hospital almost always reads 99% unless you are anemic.

It takes between one and three minutes for each RBC to leave your heart, make its complete circuit, and be back in your lungs for its next load of oxygen. Remember that Henry's Law also applies here, therefore, oxygen is a gas in your lungs but turns into molecular oxygen when it enters your body's fluids. This is so complex that there is no chemical symbol for it, but rest assured, your body's cells feed on it with a great appetite. (More on oxidative cellular metabolism shortly.)

Supersaturate?

When you fill a glass of water to the brim, it is full or saturated. Right? Yes. Holding it under the faucet and running more water into the glass will only mean that the water slops over the edges. The glass is still full. However, this is not the case with any gas, particularly oxygen breathed in by a human. Sure, just like a glass of water, oxygen can be measured by volume, but there is plenty of room to over-fill our bodies with oxygen—supersaturated.

To illustrate a complex process, let's paint a simple picture—An underground subway system.

Think of your lungs as a subway station. Passengers get off the carriages and others get on. In this instance, remember that air is made up of (for easy math calculations) 80% nitrogen and 20% oxygen. Visualize each gas molecule of either type as a gas-person. The body is already full of nitrogen at sea level and since it does nothing at all (it is inert), the nitrogen-people just come in and out your lungs. However the oxygen-people are dynamic and bustle to climb on board the little red-blood-cell carriage (which has a special oxygen-people magnet—an iron molecule), and away the red blood cell rushes with the oxygen-people ready to jump off to the hungriest of the body's cells.

Since Henry's Law allows a gas to melt into clear fluids (and our body has lots of clear fluids), there is a whole lot of room to add more oxygen-people. For example, if we barred entry to our lungs of the nitrogen-people (simple to do—just put on a mask and breath oxygen out of a 100% oxygen tank), then our lung-subway station would have five times more oxygen-people and that would mean that we increased the oxygen-people with each breath from 160 mmHg to 760 mmHg. Remember that they are dynamic, and that each red-blood-cell carriage has an oxygen magnet in it. The thick crowd oxygen-people all bustle to get onto that carriage, through the wet soapy surfactant in the wall of your lungs, even though it was already full.

Essentially, the oxygen-people fill the red-blood-cell carriage, and into the plasma where they are quickly swept along in that clear plasma fluid. Then, when even more oxygen-people continue to crowd on back at the subway station (i.e. the lungs), the plasma, which normally does not carry oxygen-people (molecular oxygen), then needs to put the overload of oxygen somewhere. From here the oxygen-people go out through the rail tunnels (i.e. the circulatory system) and into the clear fluid (i.e. interstitial fluid) that bathes our body cells. As this fluid fills with oxygen, it dumps it off into the body's largest water compartment—the body's cells (the intra-cellular compartment). These cells now have a veritable feast of oxygen available.

About 90 minutes after you start breathing 100% oxygen, you are supersaturated with five times the normal amount of molecular oxygen. No, you do not swell up since we are talking about molecules in existing body fluid, not added fluid. Curiously, if you put the little pulse-ox back on your finger, it would still only read 99% since it is just measuring the oxygen in your red blood cells. However, using high-tech oxygen measuring equipment (transcutaneous oxiometry), you can even measure molecular oxygen in your urine, saliva, and tears—something once thought impossible.

Now comes the hyperbaric chamber part. You climb in, the door is shut, and 100% oxygen floods in. The technician can look at the physician's prescription and increase the thickness of the gas in that chamber. Double the thickness (i.e. weight or pressure) to 1520 mmHg; ninety minutes later you will climb out of that chamber with ten times the number of oxygen-people (molecular oxygen) in your body. Or, put another way, since your body's cells are going to consume (eat) that additional oxygen, this is the only way you can increase the weight of oxygen-food available in a 24-hour period. One hundred percent pure oxygen at sea level and you will "eat" between just under half a kilogram to just over one kilogram of oxygen.

The deeper/thicker the oxygen is in the chamber the more you get. In fact, following Dalton's Universal Gas Laws, by doubling the pressure, you can actually get your daily oxygen meal at almost two kilograms.

Now the nifty thing about oxygen supersaturation.

Unlike many pharmaceuticals that are weight dependent, (too much of a certain drug will sicken or kill a smaller patient, not enough of the same drug and there will be no therapeutic benefit to the patient) with hyperbaric oxygen no individual can suffer from an "overdose" of oxygen, regardless of whether the patient is a mouse, rabbit, horse, or human. All climb out of the chamber, (depending on the pressure/thickness of oxygen they were treated at) with the same amount of molecular oxygen in their body. Not one person has suffered from an "overdose" of oxygen.

Our oxygen dispensary centers have treated, according to their physician's prescription, tiny babies, the elderly, and everyone in between; we have never seen a negative side effect. Instead, we have observed clinical positive effects for all.

What happens when we actually give people an extra "oxygen feast" by putting them in the chamber? Again, an extremely complicated process has to be simplified for understanding. However, before making things simpler we must first look at the science. Chatelier's principle predicts the effect of a change in conditions on a chemical equilibrium. The principle is named after Henry Louis Le Chatelier, who observed that if a chemical system at equilibrium has a change in concentration, temperature, volume, or partial pressure then the equilibrium shifts to counteract the imposed change and a new equilibrium is established. Any change in the status quo prompts an opposing reaction in the responding system.

Time to change just a couple of words for better understanding. Let us start with the word equilibrium and now call it "the way it was." We can also use that term for status quo and counteract can be changed to "pushing back." So what is really being said here is, if we change something in any chemical environment it will push back hard to be the way it was. Now it is time to make things even easier.

We are all chemical systems.

We have already mentioned cola in a can and advised against giving it to anybody, your child or yourself, because of the acidity of the liquid in the soda. But there is an even more compelling reason—the sugar. There are 39 grams of sugar, about ten teaspoons of sugar, in one can of soda. Would you feed your child that much dry sugar?

"Come on," you might think to yourself, "No way. It does not taste that sweet." It is true. The manufacturers of sodas use a lot of phosphoric acid to disguise the sickly sweetness of the drink. If you still doubt this, take an ordinary penny, or an egg and put it in a glass full of cola overnight. Within a few days, you will find all tarnish removed and instead a bright, shiny penny; the eggshell will be soft and pliable, all its protein dissolved.

Visualize what happens when you allow your small child a glass of cola (or any soda drink). Your little kid becomes supercharged, bouncing off the wall, and for some time you cannot get the child to sit still. In other words, your child has become hyperglycemic. Too much sugar, of any sort, whether it be corn fructose, beet or cane sugar, the results are the same according to Chatelier's principle. Remember, we are all chemical systems and by adding all of the sugar to a small child's body, all of the cells in that body will push back to return to the way they were before the additional sugar. The most efficient way to return to this state is to increase physical activity, causing cells to consume all of the additional added sugar.

Run, baby, run!

Another way, of course, is to rely on the body to use its own chemicals to burn off the sugar. This is predominantly the job of the hormone insulin. If an adult drinks a lot of soda each day (or even has one gin and tonic, which has about half as much sugar as a soda) and does not increase physical activity, diabetes eventually sets in as the body become insulin exhausted, unable to produce more. Then the risk of blindness in old age, amputations, and other terrible consequences may become a reality.

The process of cells using the nutrients we consume is called cellular metabolism. Overloading cells with nutrients that we do not need such as excessive raw sugars (or even food that is easily converted by the body into glucose) and fats, results in obesity; your brain will become sluggish. Now, add extra oxygen and your body will certainly consume it. This is called oxidative metabolism. The added oxygen will push all cells into overdrive; repair cells use the added oxygen to work harder in an effort to restore their state prior to entering the hyperbaric chamber. Repair cells help get rid of the toxins, acids and, excess/unneeded sugars.

After people have been in a hyperbaric chamber, healthy adults comment on the fact that their brain is working more efficiently. Memory becomes vivid and problems are easier to solve. This state is commonly known as the “cappuccino” effect or “brain brightening.”

As for small children with autism, almost all of them have a neuronal oxygen transport problem. So the additional feast of oxygen actually makes the good cells, the repair cells, work harder for just a little while after the treatment. This increase in oxidative metabolism dissipates after a couple of hours, but that little bit of improvement lasts: brain cells wire up into complex circuits, blood vessels within the brain become robust, and stem cells are produced. (More on that shortly.)

This is why all oxygen treatments need to take place over consecutive days. There is no point in attending one hyperbaric treatment and then not following it up for another week. Sort of like a seed sprouting from the earth. With each treatment, the positive changes begin to accumulate, and positive results are visible with the passing days.

Can oxygen therapy alone cure autism?

The short answer is no; it cannot. I make this statement based on the treatment of scores of challenged children that have come to my centers across America, and in other parts of the world. Something more is needed—an interdisciplinary approach.

How many treatments in the chamber does a challenged child need to be part of that recovery program?

As noted earlier, we treated our first challenged child, Emily, in one of my centers in the United States. Just one treatment per day at 2 ATA, the pediatrician's decision, made a vast difference to little Emily. Then along came a physician, Dr. Paul Harch, a very bright health scientist. He came to the conclusion 15 years ago that two 60-minute treatments each day at 1.75 ATA for 20 days could cure children with autism. He was so sure of himself that he even took out a patent on that protocol.

I was nonplussed and puzzled. I did not think that you could patent a natural phenomenon such as the effects of hyperbaric oxygen therapy or gravity. Of interest is the fact that the Supreme Court came to the same conclusion in 2012 with what is now known as the "Prometheus" ruling. In essence, the courts had taken all of the enforceable teeth out of Dr. Harch's protocol. This is not to say that there isn't some merit in the treatment pressure, nor is it to imply that Dr. Harch was ignorant of the science of hyperbaric rights in the therapy. So my centers took notice of the fact that he is a physician, and for a little while at least, we did use the Harch protocol on children.

While our little patients saw useful and positive results, there was never a normal recovery by any of the children in that 20-day double ride. This left a lot of the parents disappointed, some angry at what they felt were false claims about hyperbaric oxygen therapy, and rightfully so.

It is significant to note that Dr. Harch, and other clinicians, no longer use the two treatments a day protocol for challenged children, and he no longer claims that recovery is possible in just 20 days.

Now, onto our wonderful Jennifer; the ballet dancer and champion ice-skater. Her mom, Vickie, a bright spirit and highly intelligent woman (actually that describes the whole family), independently arrived at the conclusion that diet was a most important part of the normalization program. All together, over a 12-year period, Jennifer had 135 rides in the hyperbaric chamber. She ice skated at 2am (when the rink was clear), and focused on diet. In a nutshell, while the extra oxygen was feeding one side of cellular metabolism in spurts of 20 treatments at a time, Jennifer's cells were getting the correct diet of nutrients on the other. All of Jen's cells were giving off the right amount of heat and energy, particularly her repair cells.

Bernie and Kerri proved scientifically that the addition of proper nutrients, combined with the removal of deleterious/toxic foods is probably more important than hyperbaric oxygen therapy for children and young adults on the spectrum. Yes, the oxygen boost helps propel the patient to "normal," but the other nutritional changes are really the rocket fuel. It is a long journey, not all that expensive, and certainly worthwhile.

When a hyperbaric chamber is not a hyperbaric chamber.

One final comment about treating neuronal disorders at 1.75 ATA pressure is of utmost importance; this is that 100% oxygen is essential to the protocol. Since Dr. Harch arrived at this treatment depth, there have been thousands of inflatable chambers, so-called mild hyperbaric chambers, sold in the United States and around the world. These are not the same as hospital grade, hard-sided chambers. These bag-chambers do not deliver the needed 100% oxygen. In my opinion, at the very best, if you modify them (against FDA rules) you will only get 34% oxygen.

What have we learned thus far? Time for a review and then THE BIG SECRET REVEALED!

- Oxygen cannot be seen, but we can weigh it.
- Our bodies "eat" oxygen every day because it is a food for our cells.
- The only way we can get additional oxygen is in a hyperbaric chamber.
- This is because any gas becomes soluble and melts into a fluid (i.e. Henry's law); the same reason we can carbonate soda drinks.
- In a single treatment in a hyperbaric-oxygen-therapy chamber, we cannot overdose (and I have never witnessed any negative side effects).
- With the extra oxygen feeding the cells, our bodies get a boost of energy, particularly the repair cells.
- For oxygen in the chamber to be effective, it must be 100% oxygen. Inflatable chambers do not deliver 100% oxygen.
- Hyperbaric oxygen therapy alone will not cure autism, but it does make a big difference.
- There is no such thing as a "one-size fits all" treatment protocol in a hyperbaric chamber that works for all patients. For example, twice a day in the chamber for 20 days will make some difference but not necessarily "normalize" a challenged child.

Did you miss the big secret?

It was already mentioned about one page back—the discoveries of Bernie and Kerri. Let us repeat the secret for you and then push the edges of their really stunning discovery that is backed up by the latest science.

Bernie and Kerri proved scientifically that the addition of the proper nutrients, in the absence of offending foods, in addition to eliminating pathogens and parasites, are most likely more important than hyperbaric oxygen therapy for children and young adults. Yes, the oxygen boost helps propel the patient to "normal" but the other dietary interventions are really the rocket fuel. Not to mention freeing the body of offending pathogens/parasites which wreak havoc on the body. It is a long journey, not all that expensive and, certainly worthwhile.

Nutritional "padding." Hyperbaric oxygen therapy and the production of progenitor and stem cells.

When a baby is growing inside its mother, it has progenitor cells and stem cells. The function of these cells is considered to be, as yet, undecided. Although studies continue to elucidate exactly which mechanisms are involved in determining the fate of these cells, it is generally accepted that their surrounding cells will dictate their development. For example, the big arteries that crisscross the chest area make a decision sooner or later to turn into a heart with all of its compartments. Then, as development moves on different parts of the baby appear. These are called progenitor or stem cells.

There are various estimates on how many different types of cells the developed human has in total; however, it is predicted there are somewhere between 210 and 300. Mind you, when the baby takes its first breath of air, all but about four of these different cell groups stop reproducing. For example, the brain, with all of its neuronal pruning and circuitry needs about 20 year's worth of stimulation to properly wire all of the connections. Surprisingly, a lot of the neurons will be shed or "pruned" since they will not be put to use in the adult. However, neuroplasticity allows new skills to be added or repairs to be made to and by the brain in a lifetime.

However, medical scientists have now realized the great need for progenitor or stem cells (cells that can make decisions to replace worn or damaged cells within the body), and the search is on for these decision-making cells. Many scientists are looking for something they can patent and as a result are missing the point that it is already here. Or they are ignoring it, because but they cannot patent it.

It is called hyperbaric oxygen therapy.

> Penn Study Finds Hyperbaric Oxygen Treatments Mobilize Stem Cells
>
> **Science Daily** — According to a study to be published in the American Journal of Physiology-Heart and Circulation Physiology, a typical course of hyperbaric oxygen treatments increases by eight-fold the number of stem cells circulating in a patient's body. Stem cells, also called progenitor cells are crucial to injury repair. The study currently appears online and is scheduled for publication in the April 2006, edition of the American Journal.
>
> Stem cells exist in the bone marrow of human beings and animals and are capable of changing their nature to become part of many different organs and tissues. In response to injury, these cells move from the bone marrow to the injured sites, where they differentiate into cells that assist in the healing process. The movement, or mobilization, of stem cells can be triggered by a variety of stimuli including pharmaceutical agents and hyperbaric oxygen treatments. Where as drugs are associated with a host of side effects, hyperbaric oxygen treatments carry a significantly lower risk of such effects.
>
> "This is the safest way clinically to increase stem cell circulation, far safer than any of the pharmaceutical options," said Stephen Thom, MD, PhD, professor of emergency medicine at the University of Pennsylvania School of Medicine and lead author of the study." This study provides information on the fundamental mechanisms for hyperbaric oxygen and offers a new theoretical therapeutic option for mobilizing stem cells."
>
> "We reproduced the observations from humans in animals in order to identify the mechanism for the hyperbaric oxygen effect," added Thom. "We found that hyperbaric oxygen mobilizes stem/progenitor cells because it increases synthesis of a molecule called nitric oxide in the bone marrow. This synthesis is thought to trigger enzymes that mediate stem/progenitor cell release."[1]

Nutritional padding: It has long been known that when hyperbaric oxygen therapy is applied, existing cells, the good ones, the repair cells, turn the body into its own pharmaceutical company, providing the right sort of chemicals at the right time. Above all, there is a dramatic increase in the production of the molecule called nitric oxide from the bone marrow. Probably the best way of describing the addition of hyperbaric oxygen therapy, as an adjunct to the correct nutritionals, is simply by putting fuel onto an already existing smoldering fire. Out of the glow of embers and smoke you will see a vigorous combustion as your fireplace heats up and the flames appear.

Now imagine other ingredients that have yet to be discovered as beneficial. For example, stem cells that repair the damaged brain of a person with autism. It could be that adding external stem cells to the recipe of recovery and normalization, with simple nutritional low-cost padding, and putting the little patient in the chamber would be a faster way of achieving what all parents want for their children—to eventually become fully functional and independent adults.

All of this by just a little bit of nutritional padding and helping the body to rid itself of pathogens/parasites.

Now, it is time to turn back to Kerri so she can tell you what she has seen when hyperbaric oxygen therapy is added to the correct nutritional padding, along with chlorine dioxide to keep pathogens under control. That is the big secret to helping your child through the challenges that living in this century have visited upon you.

* * *

As Bob mentioned, I have seen miracles happen when hyperbaric oxygen therapy was applied to a child who is ready. Two girls, in particular, lost their diagnosis completely within weeks of completing treatment in the chamber. As I mentioned before, hyperbaric oxygen therapy gave my own son his speech back. Before his first 40 dives he had several single-syllable sounds, but after, he began stringing words together to request his favorite foods.

Today we are seeing that one dive a day at 1.75 ATA (atmospheres absolute) for 90 minutes at depth is better than two 60-minute sessions were first prescribed for Patrick seven years ago. Every three months after the first treatment of 20 sessions, apply ten sessions of 90 minutes, each at 1.75 ATA, until your child is recovered.

A lot of parents ask when is a good time to do hyperbarics. To this I reply that we must first have diet and chlorine dioxide totally under control, and be at least three months into the Parasite Protocol. At that point it's time to start looking for a chamber.

Make sure to do an ATEC before your child's hyperbaric oxygen therapy sessions, and repeat two months after the sessions are over; the results will be obvious.

Healing
the symptoms known as
Autism

This is my Asperger son Tobias, 10 years old, and me... when we received the book this summer.

Chapter 12

Step 7 - GcMAF & Autism:

State of the Art & Future Perspectives for a Natural Cure

by Marco Ruggiero, MD, PhD.
Specialist in Diagnostic Radiology
Full professor of Molecular Biology
Dept. of Experimental & Clinical Biomedical Sciences
University of Firenze, Italy

"The voyage of discovery is not in seeking
new landscapes but in having new eyes."
~ Marcel Proust

My family and I have been in biomed for so long, that there aren't too many interventions we haven't already tried. A few years back, Dr. Usman mentioned to me that GcMAF might be something good for Patrick. She explained that GcMAF is a human protein that occurs naturally in a healthy body. It is a special supplement that replaces the missing part of the immune system, and also acts as the body's own internal medicine.

IMMUNE GCMAF
NG/ML 2.2ML
STORE AT 4°C
TCH M1210-25
RETAINED VIAL

Based on her recommendation, we ordered a vial, and applied it for about two and a half months. I saw less obsessive compulsive eating, but when the vial ended and I hadn't seen amazing results, I wasn't extremely motivated to continue. Not only that, funds were scarce, so continuing really wasn't an option.

Two years went by and I spoke to Dr. Usman again. She said we really should give it four to five months before making a final decision. So, we scraped together the money for a second order. We started again in November of 2012, and reached full dose by December, 26th 2012. Seemingly, as time went on, Patrick started to do new things.

By springtime of 2013, Patrick's BFF's mom was saying how well he was doing, and reminded me that during the prior month Patrick had not been doing the things that he was now doing. As I write this in October of 2013, all of my money now goes to GcMAF. ☺

One of the things that I feel makes GcMAF so exciting is the fact that it helps regrow dendrites in a matter of hours after it is injected. The dendrites are the very things that got fried when mercury entered our children's bodies. With the help of GcMAF, we are now able to restore what was lost. Not to mention, GcMAF boosts the immune system, which we have come to find is often sorely lacking in people with ASD's.

Many people have asked me if GcMAF is now an official part of the protocol. When working towards recovery, I feel that we need to try everything at our disposal that has been proven to heal autism—in the correct order, or course. GcMAF fits that description. According to www.gcmaf.eu, "As of February 2013, on the American National Library of Medicine alone, 142 eminent scientists from 8 nations have published 59 major GcMAF research papers, which can be viewed on the US Government's Pubmed system." There is now enough research to prove that GcMAF has secured its place as a powerful biomedical intervention for healing autism. Therefore, after three months on the Kalcker Parasite Protocol, it is time to start thinking about adding in supplements, HBOT and GcMAF.

We are blessed to have the one and only Dr. Marco Ruggiero, the lead GcMAF researcher, write the remainder of this chapter about this substance, it's benefits and applications in autism and beyond.

The information he presents is extremely important because I feel that GcMAF is the future of medicine—today. What other intervention boasts a cancer recovery rate of 80%? None! Dr. Bradstreet is reporting 85% responders and 15% recovery rate from autism with GcMAF.[1]

Imagine adding GcMAF to the protocol already outlined in this book at the right moment (after working down some of the pathogen load), we should start seeing even higher rates of recovery than 15%. I look forward to seeing what transpires during the upcoming year as more families add GcMAF to their children's protocols. I am excited for more and more people to lose their autism diagnoses.

For the past 20 years, Dr. Marco Ruggiero has worked on the vitamin D axis, a metabolic pathway that includes the vitamin D binding protein-derived macrophage activating factor or GcMAF. In the past 3 years he has published studies on the immunotherapeutic effects of GcMAF in cancer, HIV/AIDS, chronic fatigue syndrome and neurological conditions.

Marco Ruggiero holds a PhD in Molecular Biology, is a certified Medical Doctor specializing in Clinical Radiology and is a professor of Molecular Biology at the Department of Experimental and Clinical Biomedical Sciences of the University of Firenze, Italy.

He served in the Army as Medical Lieutenant with specific training in chemical, biological and nuclear warfare. He worked at Burroughs Welcome Co. North Carolina, USA publishing a seminal paper with Nobel Laureate Sir John Vane and, subsequently, at the National Cancer Institute of the NIH in Bethesda, working with Dr. Stuart A. Aaronson and Dr. Peter Duesberg.

Since 1992, he holds the chair of Molecular Biology at the University of Firenze where he leads a research group of about 10 researchers. He has published more than 150 peer-reviewed scientific papers on signal transduction in a variety of experimental and spontaneous pathologic system related with cancer, chronic kidney disease, chronic fatigue syndrome and neurological conditions.

The role of nutrition in the treatment and eradication of the symptoms of autism is well established and other chapters of this book treat this topic in detail. What is far less known is the fact that certain natural components of the diet, certain nutrients, have profound effects on all the systems that are affected in autism and in particular on the brain and the immune system. Their effects are so dramatic that for about 20 years, these natural components have been labelled as "drugs" even though they are essential parts of our bodies, just like hormones or neurotransmitters. I am referring here to the family of molecules that is known as GcMAF, an acronym that stands for Gc-protein-derived Macrophage Activating Factor.

GcMAF has been the object of intense research in the past 20 years for its therapeutic role in cancer, autoimmune diseases, and HIV infection (for review, see: Anticancer Res. 2012 Jan;32(1):45-52). But, only one year ago, in 2012, its dramatic effects on the eradication of the symptoms of autism were published in a prestigious peer-reviewed scientific journal (Autism Insights 2012:4 31–38).

In this chapter I shall provide an overview on GcMAF with particular reference to its therapeutic role in autism and to the future perspectives deriving from the basic and applied research that is revolving around this fascinating molecule.

A Brief History of GcMAF

The first publication on GcMAF in a peer-reviewed journal indexed in the US National Library of Medicine is dated 1994 (J Immunol. 1994 May 15;152(10):5100-7). In this article, a group of researchers from the Department of Biochemistry at the Temple University School of Medicine in Philadelphia, USA, described the effects of a protein, defined as GcMAF, on rat macrophages. Macrophages are key elements of the immune response and the research group led by Dr. Nobuto Yamamoto, the first author of this paper, showed that GcMAF activated these cells. Given the central role of macrophages in the control of all immune responses, GcMAF was considered a powerful regulator of the immune system and the research on GcMAF initially was focused on its immune-stimulant properties. In fact, one year after the initial observation on rats, Dr. Yamamoto, who in the meantime had moved to the Laboratory of Cancer Immunology and Molecular Biology of the Albert Einstein Cancer Center in Philadelphia, authored a paper suggesting that a defect in endogenous GcMAF production contributed to immunodeficiency in AIDS patients (AIDS Res Hum Retroviruses. 1995 Nov;11(11):1373-8.). Consequently, he provided GcMAF to Medical Doctors treating HIV patients and, 14 years later, after 7 years of follow-up, he published a seminal paper describing eradication of HIV infection through GcMAF administration (J Med Virol. 2009 Jan;81(1):16-26).

Immunodeficiency, however, is not unique to HIV/AIDS and, back in 1996, Yamamoto and colleagues, hypothesized that deficient endogenous GcMAF production was responsible for the relative immunodeficiency that is typically observed in cancer patients (Cancer Res. 1996 Jun 15;56(12):2827-31). Quite logically, this observation of 18 years ago, led to the proposal of administering GcMAF to cancer patients with the goal of empowering the immune system that in turn would fight the cancer growth. This approach is known as "immunotherapy" and it is much older than GcMAF since, in modern times, it stems from the observation of Dr. William Coley in 1891. However, it could be argued that the idea of stimulating the immune system to fight diseases is even older since, as it is stated in this recent article, "…cancer regresses when associated with acute infections such as bacterial, viral, fungal, protozoal, etc. Acute infections are known to cure chronic diseases since the time of Hippocrates…" (Indian J Cancer. 2011 Apr-Jun;48(2):246-51).

Whatever the case, administration of GcMAF to patients with metastatic advanced cancer proved efficacious and there are now scores of papers published in the peer-reviewed literature describing the dramatic therapeutic effects of GcMAF in all types of experimental or spontaneous tumors.

Nowadays, the interest for GcMAF in the immunotherapy of cancer is so high that the prestigious scientific journal "OncoImmunology" dedicated the cover of its August 2013 issue to GcMAF. The molecular rendering of GcMAF is on the left of the cover with a caption linking it to an article by Thyer and colleagues published in the same issue and describing successful treatment of advanced cancer patients (Figure 1).



OncoImmunology

Volume 2 Issue 8
August 2013

Editors-in-Chief
Guido Kroemer
University of Paris Descartes

Laurence Zitvogel
INSERM, Institut Gustave Roussy

Lorenzo Galluzzi
University of Paris Descartes

EDITORIAL

New immunotherapeutic paradigms for castration-resistant prostate cancer
Lorenzo Galluzzi
eLocation ID: e26084

RESEARCH PAPERS

Immunological effects of the TGFβ-blocking antibody GC1008 in malignant pleural mesothelioma patients
James P Stevenson, Hedy L Kindler, Emmanouil Papasavvas, Jing Sun, Monica Jacobs-Small, Jennifer Hull, Daniel Schwed, Anjana Ranganathan, Khang Newick, Daniel F Heitjan, Corey J Langer, John M McPherson, Luis J Montaner and Steven M Albelda
eLocation ID: e26218

GC protein-derived macrophage-activating factor decreases α-N-acetylgalactosaminidase levels in advanced cancer patients
Lynda Thyer, Emma Ward, Rodney Smith, Jacopo JV Branca, Gabriele Morucci, Massimo Gulisano, David Noakes, Robert Eslinger and Stefania Pacini
eLocation ID: e25769

Interferon γ-induced intratumoral expression of CXCL9 alters the local distribution of T cells following immunotherapy with Listeria monocytogenes
Patrick Guirnalda, Laurence Wood, Radhika Goenka, Joel Crespo and Yvonne Paterson
eLocation ID: e25752

Oncolytic vesicular stomatitis virus quantitatively and qualitatively improves primary

About the cover. Rendering of molecular interaction between Gc-protein-derived Macrophage Activating Factor (GcMAF) and the vitamin D receptor (VDR). This figure illustrates a possible interaction between the N-acetylgalactosamine moiety of GcMAF at threonine 420 (Thr 420), and a string of acidic amino acids in the vitamin D receptor. The acidic amino acids are indicated in the box. Vitamin D bound to both molecules is represented in yellow. For additional information, see Thyer et al., e52769.

Figure 1

Source: https://www.landesbioscience.com/journals/oncoimmunology/oncoimmunology_2-8.pdf

Consecration of GcMAF in the Olympus of science, however, occurred a few days later, on September 14, 2013, when another article by Thyer and colleagues was published in "Nutrients", an international, peer-reviewed open access advanced forum for studies related to human nutrition (Nutrients. 2013 Jul 8;5(7):2577-89). In fact, this article describing the effects of GcMAF on human breast cancer cells, was ranked in the top 5% of all articles ever tracked by Altmetric. The Altmetric score is a general measure of the attention that an article, book or dataset has received online and reflects the quantity of attention received as well as the quality of that attention. By the time that the GcMAF was ranked in the top 5% of all scientific articles ever tracked, Altmetric had analyzed 1,510,524 articles across all scientific journals. Therefore, we may safely state that in this chapter we are describing one of the hottest topics in today's world science (Figure 2).



Score in context

Puts article in the top 5% of all articles ranked by attention

show more...

Mentioned by

- 16 tweeters
- 1 Facebook users

Readers on

- 0 Mendeley
- 0 CiteULike

Track this article

- Get email updates when this article is shared

The Altmetric score is one measure of the quality and quantity of online attention that this article has received. You can read about how Altmetric scores are calculated here.

This article scored **16.25**

The context below was calculated when this article was last mentioned on **14th September 2013**

Compared to all articles in Nutrients

So far Altmetric has tracked 288 articles from this journal. They typically receive a little more attention than average, with a mean score of 5.1 vs the global average of 4.0. This article **has done particularly well**, scoring higher than 94% of its peers.

In the 94%ile

Ranks 17th

All articles of a similar age

Older articles will score higher simply because they've had more time to accumulate mentions. To account for age we can compare this score to the 58,396 tracked articles that were published within six weeks on either side of this one in any journal. This article has done particularly well, scoring **higher than 92% of its contemporaries**.

In the 92%ile

Other articles of a similar age in Nutrients

We're also able to compare this article to 5 articles from the same journal and published within six weeks on either side of this one. This article **has scored higher than all of them**.

In the 99%ile

Ranks 1st

All articles

More generally, Altmetric has tracked 1,510,524 articles across all journals so far. Compared to these this article has done particularly well and is in the 95th percentile: it's **in the top 5% of all articles ever tracked** by Altmetric.

In the 95%ile

Figure 2

The interest for the therapeutic effects of GcMAF in a variety of conditions derives from the early observation by Yamamoto and colleagues in 1995, who showed elevated level of serum alpha-N-acetylgalactosaminidase (Nagalase) in the serum of AIDS patients. Nagalase is an enzyme that deglycosylates (degrades) the precursor of GcMAF that is the circulating Gc-protein, also known as vitamin D-binding protein (AIDS Res Hum Retroviruses. 1995 Nov;11(11):1373-8). This results in the loss of GcMAF precursor activity and consequent dysfunction of the immune system. Increased Nagalase activity, however, is not observed uniquely in AIDS patients. For example it was demonstrated that the increase of Nagalase activity in the serum of cancer patients is due to the fact that cancer cells release Nagalase and, therefore, Nagalase activity reflects tumor burden, aggressiveness and progression of the disease. Consequently, determination of Nagalase activity is currently proposed as a reliable way of evaluation of cancer severity (Cancer Lett. 2009 Oct 8;283(2):222-9).

In short, in cancer, HIV/AIDS, and in many other chronic conditions, elevated serum Nagalase, degrades Gc-protein that is the precursor of GcMAF. Therefore, GcMAF is not produced inside the body to a sufficient extent and this leads to immunodeficiency. Serum Nagalase, however, does not degrade GcMAF, and this justifies the administration of exogenous GcMAF in all those conditions where its endogenous production is insufficient due to elevated Nagalase activity.

Until 2002, it was thought that GcMAF exerted its effects only on macrophages and that its therapeutic efficacy was due to stimulation of macrophages that in turn would attack and destroy cancer cells as well as virus-infected cells. In 2002, however, a novel effect of GcMAF was described. Kanda and colleagues, working at the Department of Molecular Microbiology and Immunology, Division of Endothelial Cell Biology, Nagasaki University Graduate School of Medicine, Nagasaki, Japan, published a paper, co-authored by Yamamoto, describing the inhibitory effects of GcMAF on angiogenesis (J Natl Cancer Inst. 2002 Sep 4;94(17):1311-9.). Angiogenesis is the process of building new blood vessels that provide the tumor mass with the required supply of blood and nutrients that it needs to grow and metastatize. Therefore, since 1971 it was postulated that inhibition of angiogenesis could be a successful strategy to deprive the growing tumor mass of its supply of blood and nutrients (N Engl J Med. 1971 Nov 18;285(21):1182-6). While there are scores of inhibitors of angiogenesis, some of which in use in the therapy of cancer, GcMAF offers the advantage of performing more than one anticancer effects; in fact, not only it inhibits tumor-induced angiogenesis (Cancer Immunol Immunother. 2011 Apr;60(4):479-85), but it also stimulates macrophages that attack and destroy the cancer cells (Nutrients. 2013 Jul 8;5(7):2577-89).

If these combined anticancer effects were not enough, in 2010 Gregory and colleagues, working at the Department of Ophthalmology and Visual Sciences of University of Kentucky in Lexington, Kentucky, USA, demonstrated that GcMAF directly inhibited proliferation and metastatic potential of human prostate cancer cells (PLoS One. 2010 Oct 18;5(10):e13428). Slightly more than one year later, we were able to demonstrate that GcMAF not only inhibited proliferation and metastatic potential of human breast cancer cells, but it also reverted their neoplastic phenotype; in other words, cancer cells treated with GcMAF became normal (Anticancer Res. 2012 Jan;32(1):45-52).

On the basis of the peer-reviewed scientific literature quoted above, we can now state that GcMAF exerts multiple effects that are responsible for its efficacy in anticancer therapy:

1. It stimulates macrophages that attack and destroy cancer cells, as originally postulated by Yamamoto and colleagues.
2. It inhibits tumor-induced angiogenesis thus depriving the growing tumor mass of blood and nutrients.

3. It directly inhibits cancer cell proliferation and metastatic potential and it retro-transforms cancer cells into normal healthy cells.

Given this plethora of effects on cancer, it is no wonder that the majority of GcMAF research has been focused on its anticancer properties. There are, however, a few research articles suggesting that GcMAF might exert also other biological actions with therapeutic implications. In addition to the studies on HIV and AIDS quoted above, GcMAF has received attention for its potential role in the therapy of bone disorders (Blood. 1996 Oct 15;88(8):2898-905), and autoimmune diseases such as Lupus Erythematosus (Clin Immunol Immunopathol. 1997 Mar;82(3):290-8).

Despite these scanty evidences on the possible role of GcMAF in conditions other than cancer and AIDS, it was not until 2012, however, that GcMAF proved dramatically effective in the therapy of autism.

GcMAF & Autism

GcMAF, being derived from Gc-protein, also known as vitamin D binding protein, belongs to the so called "vitamin D axis", a nutritional metabolic pathway described in detail in a recent review (European Nephrology, 2011;5(1):15–9). My research group had been working on the vitamin D axis since 1996 (Epidemiol Prev. 1996 Apr-Sep;20(2-3):140-1), that is since the beginning of GcMAF research. Just like our colleagues in the USA and Japan, we were mainly interested in the role of the vitamin D axis in bone metabolism and cancer (Radiol Med. 1996 Nov;92(5):520-4. Oncol Res. 1998;10(1):43-6). Therefore, it came as a surprise when Dr. Nobuto Yamamoto first mentioned to me the effects of GcMAF on neurodegenerative diseases such as Parkinson's and Alzheimer's diseases.

In the hot summer of 2010 we visited Dr. Yamamoto in his hometown of Philadelphia, and we had the honor and the pleasure to spend two very intense days with this old-style exquisite gentleman. Dr. Yamamoto gave us a detailed history not only of his decade-long research activity, but also of the entire field of immunotherapy, starting with the pioneering work of Dr. William Coley at the end of the nineteen century. During these intense and fruitful talks, Dr. Yamamoto mentioned the dramatic effects that he had personally observed by administering GcMAF to a patient suffering from Parkinson's disease. According to Dr. Yamamoto, the effects had been almost immediate and dramatic up to the point that he himself was amazed. Regrettably, he had been unable to clinically document the case and, therefore, this remained an anecdote. From this anecdote, however, an entire new field of GcMAF research was about to rise; that is the study on the role and implications of GcMAF in treating neurologic and neurodegenerative disorders.

The first solid evidences for a role of GcMAF in treating a neurodegenerative disorder were simultaneously presented by Dr. Paul Cheney and Prof. Kenny de Meirleir at the meeting of the International Association for Chronic Fatigue Syndrome and Myalgic Encephalomyelitis (CFS/ME) held in Ottawa in September 2011. A few days later, in collaboration with Dr. Paul Cheney, we presented in Padova, Italy, a study demonstrating that food-based GcMAF dramatically improved the symptoms of CFS/ME, and this work was published in the official journal of the Italian Society of Anatomy and Histology, one of the oldest and most respected European scientific societies, founded at the beginning of the twentieth century (It. J. Anat. Embryol. Vol. 116, No 1, 2011).

CFS/ME is a complex disorder that shares many features of autism. In fact, it is characterized by immune system dysfunction, widespread inflammation, and multi-systemic neuropathology (J Intern Med. 2011 Oct;270(4):327-38. In Vivo. 2013 Mar-Apr;27(2):177-87). Dysfunction of the immune system involves abnormal functions and distributions of T lymphocytes, B lymphocytes, natural killer cells, and monocyte/macrophages (Nihon Rinsho. 1992 Nov;50(11):2625-9. Brain Behav Immun. 2012 Jan;26(1):24-31). The etiology of CFS/ME, just like the etiology of autism, is still unknown and multiple factors are thought to be responsible for its onset and progression, thus lending credit to the hypothesis that both etiology and pathogenesis are multifactorial (J Intern Med. 2011 Oct;270(4):327-38). Heavy metal exposure and viral infections are among the factors that contribute to CFS/ME etiology and pathogenesis, and a role for human endogenous retroviruses has been recently hypothesized (In Vivo. 2013 Mar-Apr;27(2):177-87). Both chronic heavy metal exposure and viral infections are considered responsible for the immune system dysfunction and neuropathology that are typical of CFS/ME (Med Hypotheses. 2012 Sep;79(3):403-7. In Vivo. 2013 Mar-Apr;27(2):177-87).

In addition to these areas of overlapping, it had been noticed by Doctors treating autism and/or CFS/ME, that in several families the two conditions are often associated with parents of autistic children suffering from CFS/ME. Interestingly, this happens also in families with adopted children with autism, thus lending credit to the hypothesis that environmental or infectious factors may contribute to both conditions.

Whatever the case, it had been observed that CFS/ME patients had elevated levels of serum Nagalase together with a number of immunological alterations, and it was hypothesized that they could benefit from GcMAF treatment. The results presented in Ottawa and in Padova confirmed this assumption and ever since immunotherapy with GcMAF is a stronghold of CFS/ME treatment.

At about the same time, Dr. Bradstreet, a leading authority in the field of autism, began to study the levels of Nagalase in autistic children and their responses to GcMAF treatment. The results obtained in a first cohort of 40 subjects were reported in a seminal paper published in 2012 (Autism Insights 2012:4 31–38). This paper represents a turning point in the understanding of autism pathogenesis and treatment.

The first significant finding is the observation that the average level of Nagalase in autistic subjects was more than two folds higher than the normal level, thus lending credit to the hypothesis that immunodeficiency or immune system dysfunction is a hallmark of autism. The second finding, probably the most important in recent years, is the observation that GcMAF treatment significantly improved the symptoms of autism and this improvement was associated with a decrease of Nagalase levels.

The therapeutic response to GcMAF was statistically significant and showed the typical bell-shaped curve that is expected when a biologically effective treatment is at work. About 15% of subject did not respond; this means that their symptoms were not ameliorated by GcMAF treatment. However, more than 15% of children responded so dramatically that all the symptoms of autism were eradicated in a matter of weeks up to the point that the children could no longer be defined as "autistic." According to the very word of the authors, in the children in this group, "This response was demonstrated at school, during therapies, home and outside the home as substantial improvement to the point that many or most of the criteria of autism were no longer present."

The remaining 70% of children were distributed according to the so-called Gaussian distribution in the groups showing "slight," "moderate," or "considerable" improvement.

This paper demonstrated for the first time that GcMAF treatment was able to eradicate the symptoms of autism in a matter of weeks, thus reinforcing the idea brought forward in many chapters of this book that autism is a curable condition indeed.

Quite obviously, the dramatic results obtained by Dr. Bradstreet did not go unnoticed and, in April 2013, he presented further results at the First GcMAF Immunology Conference held in Frankfurt, Germany. According to Dr. Bradstreet, as the time of follow-up and the number of subjects increased, a shift toward the right (that is the "best") part of the curve could be observed. This means that the percentage of those showing "considerable" to "very considerable" improvement increased.

From the point of view of the general practitioner, the issue could be considered closed: GcMAF cures a significant percentage of autistic children now and that figure is rising.

However, since I am a researcher in addition of being a Medical Doctor, the successes of Dr. Bradstreet in treating autism and the research papers published by Immuno Biotech laboratories are in the middle of an exciting series of observations that are leading to a completely new understanding of how GcMAF works and what autism truly is.

In fact, the undisputable efficacy of GcMAF in treating autism raises a number of questions on the mechanisms involved at the cellular and molecular levels. The most important questions are:

1. The efficacy of GcMAF in curing autism is due only to its immune-stimulating effect?
2. Or, is GcMAF acting directly also on neurons as it does on cancer cells?
3. Does GcMAF revert the neuro-anatomical alterations that are typical of the autistic brain?
4. Why a certain number of autistic subjects do not respond to GcMAF?
5. Can we devise strategies to have these non-responders respond?
6. Can we devise strategies to further improve this already dramatic therapeutic effect?

The Effects of GcMAF on Human Neurons

GcMAF is a protein and, as such, it was thought that it would stimulate cells from the outside. In other words, until 2013, it was conjectured that, on their external surface, cells had a receptor that bound GcMAF and conveyed the signal to the inside of the cell and, ultimately, to the nucleus and the DNA, thereby modifying the cell behavior. However, despite 20 years of research, such a receptor for GcMAF had not been identified. And this might appear truly odd considering that the entire human genome had been sequenced, that is studied in every single detail, more than 10 years ago.

In our first publication with Dr. Yamamoto, presented at the XVIII International AIDS Conference in Vienna in 2010, we had demonstrated that the response to GcMAF in human mononuclear cells (that is macrophages) was dependent on polymorphisms (that are the individual variations among humans) of the vitamin D receptor (VDR) gene. This observation was not surprising considering that vitamin D, its receptor, and GcMAF all belong to the vitamin D axis.

In order to further investigate this relationship between GcMAF and the VDR we began studying the molecular assembly of GcMAF that is the "shape" that the molecule assumes in its physiological conformation. Having done this, we looked for complementary areas in the GcMAF and VDR molecules and… voilà! The two molecules complemented each other as two elements of a puzzle.

We published this observation in the "Nutrients" paper that is now in the top 5% of all articles ever tracked, and the picture of the two molecules interacting with each other is in the front cover of the OncoImmunology August 2013 issue. The molecular mechanisms through which GcMAF and VDR interact and the consequent complex web of intracellular signaling are topics for specialists and rather difficult to divulge; the basic point, however, is that we had demonstrated how is it possible that GcMAF exerted so many different effects that can be exploited to treat a number of diseases so different from each other.

From this observation we deducted that all cells having the VDR would have responded to GcMAF and, given our interest for the effects of GcMAF in neurological conditions such as autism and CFS/ME, we began our study on human neurons. In fact, human neurons express (i.e. "have") the VDR and therefore, they are candidate to be stimulated by GcMAF.

We cultured human neurons in Petri dishes and we challenged them with ultra-pure GcMAF; in this type of experiments there were no other variables. That is, there were only neurons and GcMAF; the cells of the immune system or other molecules were not involved. By doing so, we would have been certain that whatever effect we observed, this was due uniquely to GcMAF.

As I have shown at the congress "Curando el Autismo" in San Juan de Puerto Rico in August 2013, GcMAF at extremely low concentration significantly increased neuronal cell viability and metabolic activity. These effects on cell viability were associated with dose-dependent intracellular cAMP production (cAMP is an intracellular second messenger). This means that GcMAF increased the production of energy inside human neurons and made them more active, more viable. Increased viability and metabolic activity following GcMAF stimulation as well as cAMP formation were accompanied by morphological changes, meaning that stimulated neurons changed their shape.

In the absence of GcMAF, human neuronal cells under the microscope appeared as small, relatively undifferentiated cells with large nuclei. After 24h stimulation with GcMAF, neurons showed a significant change in morphology that was consistent with the induction of neuronal differentiation and increased connectivity. The cytoplasm was enlarged and cytoplasmic elongations could be observed. After 72h incubation with GcMAF, these morphological changes were more evident and well differentiated cells could be observed.

After incubation with GcMAF, the cells appeared to establish contacts with each other. Taken together these results indicated that GcMAF increased neuronal cell viability, metabolic activity and differentiation, with the first effects being observed at 24h. It is worth noticing that the assay that we used to determine cell viability, measured mitochondrial activity, and mitochondrial dysfunction is known to be hallmark of ME/CFS (Int J Clin Exp Med. 2012;5(3):208-20), and possibly of autism as well. Therefore, the effects of GcMAF that we observed explain the reason why GcMAF is so effective in CFS/ME and autism; it counteracts the molecular alterations that are the pathogenetic basis of both conditions.

I wish to spend a few words here on the effects of GcMAF on neuronal connectivity. It is well assessed that this is one of the basic alterations in the brain of autistic subjects; neurons do not establish contacts with each other and therefore the neurological signal cannot be transmitted from one area of the brain to another thus causing a "disconnection" (Rev Neurol. 2012

Feb 29;54 Suppl 1:S31-9). GcMAF re-establishes neuronal connectivity by stimulating the formation of what are called "cytoplasmic elongations" that are like small "arms" that protrude from the neurons and establish contact with each other as if neurons were tending arms to "touch" each other and exchange information.

In Figure 3A, human un-stimulated human neurons in culture can be observed; they are small and roundish. After stimulation with GcMAF (Figure 3B), they are much larger because increased energy production leads to increased protein synthesis in their cytoplasm. But, perhaps more important, they have a highly irregular, elongated, triangular, shape with spikes that touch each other. The areas of contact between the two neurons can be clearly observed in the central part where they establish connecting bridges. Please notice that both pictures were taken with the same magnification.

Figure 3



These observations provide an answer to the first two questions raised by the article published by Dr. Bradstreet: the therapeutic effects of GcMAF in autism can be ascribed to at least two different actions of GcMAF. On one side, it rebalances the immune system that is typically dysfunctional in autistic subjects; on the other side, it directly stimulates human neurons increasing their metabolic activity and their connectivity. But, as it always happens in research, these "answers" led to other "questions": does GcMAF cross the blood brain barrier? That is, does it arrive to the neurons of the central nervous system? Before challenging this question further, however, let's proceed with order and let's try to provide an answer to the other questions that were raised by the Bradstreet's paper.

GcMAF and the Neuro-Anatomical Alterations of the Autistic Brain

If the etiology of autism is still undefined, the pathogenesis and the brain alterations associated with autism are better understood. Several studies using sophisticated imaging techniques demonstrated that there is atypical structural brain connectivity within cortical white and grey matter and it is postulated that such an alteration of brain connectivity may represent one of the principal neural substrates underlying autistic symptoms (PLoS One. 2013 Jun 18;8(6):e67329. Proc Natl Acad Sci U S A. 2013 Jul 22.).

The observed atypical brain connectivity is localized to particular areas of the brain and the alterations in the fronto-temporal regions are associated with the severity of social and repetitive symptoms of autism (Proc Natl Acad Sci U S A. 2013 Jul 22.). Atypical brain connectivity in autism is also associated with reduction of grey matter volume in different areas of the brain (Cerebellum. 2013 Apr 10.). In the bilateral superior temporal gyrus significantly decreased functional connectivity was accompanied by the strongest trend of grey matter volume decrease (PLoS One. 2013 Jun 18;8(6):e67329), thus reinforcing the hypothesis that study of grey matter volume may provide indication of functional connectivity.

However, the studies on brain connectivity and grey matter reduction quoted above were conducted with sophisticated Magnetic Resonance Imaging (MRI) equipments using complex softwares. Because of their cost and complexity, these techniques are not suitable for routine examination and this appears to be in contrast with the need to provide the general practitioners with the instruments to study autism. In fact, given the current epidemiological trend, it is highly probable that even primary care providers will see with increased frequency a patient with autism spectrum disorder in their clinic (Curr Probl Pediatr Adolesc Health Care. 2013 Jan;43(1):2-11). This consideration prompted us for the search of accessible methods to study brain alterations in autism and to study the response to different treatment including GcMAF.

To this end, we developed an easily accessible method to study the brain cortex using transcranial ultrasonography. This technique was first applied to the diagnosis and treatment CFS/ME a syndrome that, as we know, share neuropathological similarities with autism (Toxicology. 2008 May 2;247(1):61-72). In particular, we proposed to use ultrasounds to study the grey matter in the temporal lobe, and to evaluate signs of neuronal layer disorganization and brain inflammation (Med Hypotheses. 2012 Sep;79(3):403-7). It is worth noticing that these same neurological alterations, i.e. minicolumn structural changes and inflammation are frequently observed in autism (Front Immunol. 2013 Jun 10;4:140. doi: 10.3389/fimmu.2013.00140. Print 2013). Therefore, we hypothesize that ultrasounds could be used in autism in order to study the brain alterations that have been described using more sophisticated and less accessible techniques.

First of all, we assessed the safety of the technique; to this end we used sub-thermal ultrasounds. These are considered inherently safe and have been used for fetal imaging in utero, and virtually every part of the body, including brains of newborn babies through fontanelles. Their inherent safety and any lack of correlation with the onset of autism have been confirmed by meta-analysis of thousands of cases. A recent randomized controlled trial on over 1.400 cases demonstrated beyond any reasonable doubt that there is no link between the prenatal ultrasound scans and the autism phenotype (J Autism Dev Disord. 2012 Dec;42(12):2693-701).

Then, in a collaborative work with Dr. Bradstreet, we decided to focus our attention on the temporal cortex in order to compare our results with those already published by Hameroff and colleagues and by ourselves using this technique (Med Hypotheses. 2012 Sep;79(3):403-7. Brain Stimul. 2013 May;6(3):409-15). In addition, having to choose a particular area of the brain for this initial study, the temporal lobe was particularly interesting because of its accessibility to ultrasounds and its involvement in the pathogenesis of autism (PLoS One. 2013 Jun 18;8(6):e67329. Print 2013).

In the typical adults subject, meninges appeared as a well-organized array of layers of about 2.6 mm thickness. The meninges were separated from the cortex by a structure that shows echogenic and morphological feature consistent with the sub-arachnoid space. The cortex of the temporal lobe appeared as a well-organized array of alternate, hyper-echogenic/hypo-echogenic, layers. The thickness of the cortex was 5.0 mm. This value of thickness and the anatomical positioning of the probe led us to hypothesize that we were observing the temporal areas designated by von Economo as TG and TE, i.e. those areas involved in the control of eye movements and balance in standing position (area TE), social behavior, mood and decision making (area TG) (von Economo C. Temporal lobe. In: Triarhou LC, editor. Cellular structure of the human cerebral cortex. Basel; 2009. p. 114-132). It is worth noticing that the layers within the column-like structure of the healthy subject appeared well-organized and parallel to each other.

However, the images obtained in a representative autistic subject showed that the thickness of the cortex of the temporal lobe was significantly reduced, as it had been observed with MRI (PLoS One. 2013 Jun 18;8(6):e67329. Print 2013). Other images showed a concomitant increase in the spinal fluid in the sub-arachnoid space that was twice as much as in the healthy subject. These findings are consistent with the very recent observation that infants who developed autism spectrum disorder had significantly greater extra-axial fluid characterized by excessive cerebrospinal fluid in the sub-arachnoid space (Brain. 2013 Jul 9.).

Taken together, the results obtained in autistic subjects demonstrate that our technique was able to visualize the excess extra-axial fluid in a manner comparable to MRI; however, at variance with MRI, the observation with ultrasounds was immediate and intuitive and could be easily performed with no discomfort during a routine examination.

Another finding that we observed was a relative disorganization of the neuronal layer arrangement in the temporal cortex of autistic subjects. It was possible to observe that the neuronal layers had a different orientation and that there were black areas of about 0.4 mm that could represent areas of poor connectivity.

Since this technique has been applied only recently to the study of autism, there is no statistical analysis indicating whether GcMAF or any other effective treatment can reverse the anatomical alterations that we have observed in the brain of autistic subjects. Therefore, there is no sound scientific answer to this question; there are only some anecdotic evidences suggesting that this might indeed be the case. Autistic subjects treated with GcMAF and showing considerable clinical improvement showed a normal brain anatomy. Future observation will tell whether these anecdotic evidences have a statistical meaning.

Ultrasounds, however, in addition to their role in early diagnosis and follow-up, might also have a role in the therapy of autism and in particular in improving the response of those subjects who do not appear to benefit from GcMAF treatment.

GcMAF Non-Responders

As odd as it may appear to non-researchers, the presence of non-responders is often the best assurance that we are dealing with a real biological phenomenon and not with placebo effects or worse. In fact the bell-shaped curve presented in the article by Bradstreet and colleagues it typical of any effective treatment and it confirms the validity of the results. This having said, however, there is the need to provide an answer to those who do not respond. And, in the effort of providing an answer to non-responders, improvements in the overall efficacy of the treatment for everyone will eventually follow.

At the moment, there are two hypotheses that could help explaining why certain subjects do not respond to GcMAF in terms of improvement of symptoms of autism.

The first hypothesis is related with the VDR gene polymorphisms. As we proposed at the AIDS conference in Vienna in 2010, and later published in 2012 (J Nephrol. 2012 Jul-Aug;25(4):577-81), the individual responsiveness to GcMAF depends on the individual variations (polymorphisms) in the VDR gene. In other words, there are subjects harbouring variants that are associated with little or no response. However, this lack of response is relative and not absolute. In fact, it has been observed with vitamin D that these individuals respond to higher doses of the vitamin, thus indicating that the VDR is "less" responsive, but still functioning. This would mean that the so-called non-responders might need a higher dose or a longer time of GcMAF treatment to obtain the desired therapeutic effects. Prolonged observation of a higher number of cases will tell whether this hypothesis is correct.

The second hypothesis is closely associated with the first one as well as with the question briefly outlined in a preceding section: "does GcMAF cross the blood brain barrier?" In a recently submitted paper, we proposed that the interconnection between GcMAF and VDR signaling is responsible for the transport of GcMAF through the blood brain barrier. In fact, transport of macromolecules across the blood brain barrier requires both specific and nonspecific interactions between macromolecules and proteins/receptors expressed on the luminal and/or the abluminal surfaces of the brain capillary endothelial cells (Int J Cell Biol. 2013;2013:703545. doi: 10.1155/2013/703545). Since VDR signaling appears to enhance brain to blood transport at the blood brain barrier through both genomic and non-genomic actions, it can be hypothesized that the interaction between GcMAF and VDR (Nutrients. 2013 Jul 8;5(7):2577-89. doi: 10.3390/nu5072577) may favor GcMAF transport into the brain. This means that subjects with a less responsive VDR because of unfavorable genetic variants, would also have a less efficient transport of GcMAF to the brain.

This latter consideration, however, opens the way to a possible solution that might also help increasing the effectiveness of GcMAF in those who already respond to it.

In fact, now that we know the physiological molecular assembly of GcMAF, we can design specific GcMAF molecules that are more efficient in crossing the blood brain barrier and, therefore, are more effective in treating neurological conditions such as CFS/ME and autism. These molecules exploit the fatty acid binding site in the GcMAF molecule, and use one of the most beneficial fatty acids, oleic acid, the basic component of olive oil, to target brain cells.

Most interestingly, GcMAF/oleic acid molecules do not only stimulate human neurons with a much higher efficiency than GcMAF, but they also regulate glial cell metabolism. Glial cells are the connective tissue of the brain and glial cell dysfunction is involved in the pathogenesis of autism. In particular, glial cell dysfunction seems to be responsible for the neuronal underconnectivity typical of the autistic brain (Neuron Glia Biol. 2011 May;7(2-4):205-13). In short, we can postulate that the development of these novel GcMAF/oleic acid molecules will prove beneficial not only for the GcMAF non-responders, but also for improving the therapeutic efficacy of GcMAF in all neurological conditions where GcMAF treatment is indicated.

In addition to these novel, more physiological, brain-targeted, molecules, there are other strategies that can improve GcMAF transport into the brain with consequent increased therapeutic efficacy. Just a few days ago, in a journal dedicated to advanced radiological research, it was published a report demonstrating that ultrasounds, just like those described in the preceding section, transiently open the blood brain barrier. This phenomenon is exploited to favor transport of chemotherapeutic drugs into the brain of individual with brain tumors and it proved safe and efficacious after extensive testing.

On the basis of this observation, one could devise a simple treatment protocol using the same ultrasound system that is currently used for transcranial ultrasonography. In analogy with what is performed to deliver chemotherapeutic drugs to brain tumors, ultrasounds could be used to facilitate the transport of GcMAF through the blood brain barrier and to focus its delivery into those areas of the brain that are known to be altered in autism.

In this manner, during a regular examination, the health professional could exploit our technique to assess the neuro-anatomical alterations in the autistic brain and to deliver GcMAF to those areas. The use of more physiological, brain-targeted GcMAF molecules that can be administered sublingually, would greatly improve the efficacy of the treatment and it will most likely reduce the percentage of the so called non-responders to GcMAF.

As noted above, however, the use of ultrasounds to treat neurological conditions is not completely new. In fact, we and others have demonstrated that non-thermal ultrasounds have significant effects on mental states (Brain Stimul. 2013 May;6(3):409-15), modulate neurotransmission (Neuropsychobiology. 2012;65(3):153-60), cardiac frequency and blood pressure and improve skeletal muscle strength (The Journal of IiME, vol. 6 (1), p 23-28, 2012). These effects can be observed with ultrasounds alone, that is in the absence of other treatments.

In a protocol for the treatment of autism and CFS/ME, we propose to use our ultrasonographic technique together with timely administration of sublingual GcMAF/oleic acid molecules. In this manner, we are able to exploit the direct effects of ultrasounds on the neuronal microtubules (Brain Stimul. 2013 May;6(3):409-15), together with the ability of ultrasounds to favor the transport of GcMAF/oleic acid into the brain and, more precisely into those areas where the neuroanatomical alterations are observed.

What is GcMAF?
A drug, a hormone, a natural component, a nutrient?

How to define a molecule that is formed every time a wound is licked? This is the most evolutionary conserved protective behavior in animals, humans included. The enzymes in the saliva convert the Gc-protein in the blood that is on the wound into active GcMAF that prevents infection of the wound and promotes repair (PLoS One. 2013 Jul 18;8(7):e69059).

For many years researchers considered GcMAF only a key regulator of the immune system because of its activity on macrophages and its denomination reflects this early conjecture. However, as it often happens in science, the original denomination of a molecule proves incorrect with the passing of time and the accumulation of scientific evidences. Vitamin D is a notable example; it is not an vitamin and it does not contain any amine group (even though the suffix “vita” applies, in that it is indispensable for life). Now it is rightly considered a hormone produced by the body and, to be more precise, a secosteroid hormone that has a mechanism of action similar to that of classical steroidal hormones. GcMAF, being a part of the vitamin D axis might soon become another example of scientific mislabeling. In fact, we now know that it exerts its actions in many other cell types in addition to macrophages and that its role go well beyond activation of macrophages.

And even though there are no doubts that it is a powerful stimulant of the immune system, it would not be surprising to realize that this might not be its most relevant physiological role. In this respect, GcMAF shares the destiny of its precursor, the Gc-protein. Gc-protein is a serum alpha 2 glycoprotein composed of a single polypeptide chain, structurally related to serum albumin, that performs a variety of actions in several cell types. It is synthesized in the liver and has been detected on the surface of several cell types, yolk sac endodermal cells, and some T lymphocytes. In B cells, it participates in the linkage of surface immunoglobulins. In addition to vitamin D, it binds actin and acts as an actin scavenger. These characteristics are of paramount importance in human pathology since actin is the most abundant protein in eukaryotic cells and it is a major cellular protein released during cell necrosis that may cause fatal formation of actin-containing thrombi in the circulation if the actin scavenging capacity of Gc-protein is exceeded. Not surprisingly, therefore, several studies suggest an association between Gc-protein and resistance or susceptibility to chronic obstructive pulmonary disease, thyroid diseases, diabetes, multiple sclerosis, and sarcoidosis (for a review on Gc-protein and the vitamin D axis, see: European Nephrology, 2011;5(1):15–9).

From these considerations it derives that the potential indications for GcMAF treatment might be far too numerous than those currently envisaged. And also this parallels the fate of vitamin D, once thought only to prevent rickets and now involved in almost all aspects of human physiology and pathology up to the point that a (serious) scientific article on this subject was entitled: "Does vitamin D make the world go 'round'?" (Breastfeed Med 2008; 3: 2392–50.).

Apart from issues of biomedical terminology, it is now emerging the concept that GcMAF is an essential component of that nutritional pathway that is the vitamin D axis. It is not a case or a coincidence that the article on GcMAF that has received the greatest attention was published in a scientific journal named "Nutrients". With the proceeding of research it is becoming apparent that GcMAF participates in such a variety of physiological events that each proposed definition is limited.

But, if we accept the concept that GcMAF is a natural nutrient, indispensable for brain and immune system development and function (and possibly for many more essential physiological events), two questions spontaneously arise: “Where do I find it in nature?” and “How can I consume it?”

The second question already has an answer: now that the physiological molecular assembly of GcMAF is known, there are on the market several GcMAF products that can be used sublingually or simply eaten. Modern biotechnology has reproduced the physiological conformation of GcMAF so that it can be absorbed in a natural way without recurring to intravenous or intramuscular injections. GcMAF injections are reserved for those cases where a strong and rapid stimulation is required.

The other question is more intriguing and leads to the final section of this chapter.

My Own Personal Experience with GcMAF

As it happens in many people of my age exposed to the radiations from the Chernobyl incident, I have several thyroid nodules. Being a radiologist, it was easy for me to perform ultrasonography on my thyroid and what I saw on the screen was not nice. In addition to small lesions in my right lobe, in my left lobe I observed a massive mixed (solid and cystic) protruding nodule substituting for most of the lobe. The anterior-posterior diameter was about 3 cm, whereas the longitudinal diameter was greater than the length of the probe (4 cm). The structure was grossly inhomogeneous with cystic areas and hypo-reflecting areas alternated with iso- or hyper-reflecting areas. The margins bordering the residual normal thyroid tissue appeared well defined with an area of edema (inflammation) surrounding the nodule. The blood vessels were located around and inside the nodule and few or no blood vessels could be observed in the large hypo-reflecting areas suggesting the presence of metabolically inactive tumor tissue. Consistent with these findings, laboratory tests showed signs of immunodeficiency and anemia. And, it has been reported that anemia is among the predictive elements of malignancy in thyroid nodules (Tunis Med. 2002 Sep;80(9):536-41).

It was immediately clear to me that I needed a powerful stimulant of the immune system as wells as an anticancer agent, and GcMAF was my first thought. However, at that time, GcMAF was synthesized only in academic research laboratories and it was not available on the market as the pure, highly active, quality controlled product that we know today. Therefore, we decided to look for natural sources of GcMAF.

We already knew that GcMAF is naturally formed when a wound is licked because saliva contains the enzymes that convert blood Gc-protein into active GcMAF. Licking my thyroid, however, quite obviously, was not an option.

Because of these hindrances, we hypothesized that GcMAF could be obtained through a natural food fermentation process that exploits the characteristic of certain microbial strains to produce the enzymes that convert food Gc-protein into GcMAF (Hollis and Draper, 1979). According to our hypothesis, fermented food-derived GcMAF would activate the macrophages widely diffused in the walls of the entire gastrointestinal tract and, in particular, in the Waldeyer's-Pirogov tonsillar ring (or pharyngeal lymphoid ring). Our first goal was to assess the feasibility of obtaining natural GcMAF through home-made food processing procedures. To this end, we devised a strategy to prepare a fermented food product using those microbes, known to mankind for their healthy properties for millennia, that express the enzymes involved in GcMAF synthesis (Hollis and Draper, 1979).

After having prepared this fermented food at home, I began consuming it on a daily basis.

Since at that time we too considered GcMAF mainly for its immune-stimulating properties, the first objective was to assess the efficacy of this procedure on certain markers of immunodeficiency, the so called CD4 lymphocytes. The general public became familiar with CD4 lymphocytes because of their involvement in HIV infection and AIDS, and CD4 cell number is considered a reliable marker of immune system function. The role of CD4 cells in the immune system has been widely popularized up to the point that the webpage of the AIDS Authority of the Government of the United States of America states; "CD4 cells or T-cells are the "generals" of the human immune system. These are the cells that send signals to activate your body's immune response when they detect "intruders," like viruses or bacteria. Because of the important role these cells play in how your body fights off infections, it's important to keep their numbers up in the normal ranges..."

In our observation, the reference laboratory considered normal value for CD4 cell count 500 - 1500 cells/μL. Before consumption, my CD4 count was low, close to the threshold of AIDS definition (372 cells/μL). CD4 count rose from the abnormal value of 372 to the normal value of 609 cells/μL after three weeks of consumption of the fermented food that I had prepared. Such an increase continued up to eight weeks with CD4 cell count reaching 853 cells/μL. After many years, they are still in the normal range.

The trend toward normalization of blood parameters was observed also in other abnormal haematological values. My values (low or abnormal) changed as follows:

	Before Consumption	After 3 Weeks	Normal Values
Red Blood Cells			
(x106/uL)	4.55	4.85	4.6 - 6.2
Haematocrit, %	42.9	45.9	40 - 52
Haemoglobin, g/dL	14.8	15.6	13 - 18
Platelets/uL	165,000	206,000	140,000 - 440,000

The neutrophil cell count decreased from 77% to 55% in about 12 weeks, indicating a normalization of parameters suggestive of a pro-inflammatory state. Overall, the observed changes in haematological parameters were consistent with those positive modification of immune responses in humans that might represent the potential mechanism by which food fermented by probiotic bacteria confer health benefits.

Being a researcher, I am very well aware that this report is a mere anecdote that, in the era of evidence-based medicine, has low value or is not even considered to be medical evidence. However, a very recent study on the evaluation of clinical practice challenges the deprecation of stories like that reported above. Thus, it is well known that some studies present large and impressive statistics obtained from many observations while others report a small number of noteworthy events, as we did in this study. However, according to this authoritative epistemological approach, “all of these stories become evidence of what works in medicine” (J Eval Clin Pract. 2011 Oct;17(5):920-6).

Conclusions

In August 2013, a paper published in the very prestigious American Journal of Immunology reported a series of clinical cases successfully treated with GcMAF (Am. J. Immunol., 9: 78-84. 2013). Among these, there were pathologies already known to be responsive to GcMAF treatment, such as cancer, autism, and CFS/ME. Other neurodegenerative diseases such as multiple sclerosis and amyotrophic lateral sclerosis, however, had not been treated with GcMAF before, and this is the first report on such a successful treatment. This paper, together with all the other recognitions reported above, places GcMAF as one of the most effective tool to fight diseases that were considered incurable until very recently.

In other chapters of this book it is clearly stated that autism IS curable, and the successes of GcMAF in curing autism further strengthen this concept. What is emerging and what I hope to have been able to convey, is that GcMAF is not an exogenous drug that "fixes" some problem, but rather a very natural component of our body that is essential for, at least, brain and immune system development and function. In many conditions, including autism, GcMAF is not produced to a sufficient extent and therefore it has to be administered from the outside. With the advent of a courageous little biotech company that has perfected the synthesis of natural, fully physiological, GcMAF molecules that can be eaten, GcMAF treatment will become all the more and flexible to fit the individual needs. Eventually, GcMAF will become part of an integrated nutritional plan as it was intended by nature during evolution.

Consistent with this concept, I wish to conclude with an example from the realm of nature.

According to the Genetic Science Learning Center of the University of Utah, "Some mother rats spend a lot of time licking, grooming and nursing their pups. Others seem to ignore their pups. Highly nurtured rat pups tend to grow up to be calm adults, while rat pups who receive little nurturing tend to grow up to be anxious. It turns out that the difference between a calm and an anxious rat is not genetic—it's epigenetic. The nurturing behavior of a mother rat during the first week of life shapes her pups' epigenomes. And, the epigenetic pattern that mom establishes tends to stay put, even after the pups become adults."

It seems that licking their pups while breastfeeding in the first week of life is the decisive factor; in the saliva there are the enzymes that convert milk Gc-protein into GcMAF. What is more natural than this?

* * *

Subcutaneous GcMAF has been available through FIRSTiMMUNE for several years. Their website is:

www.gcmaf.eu

They now also produce a sublingual version of GcMAF called GOleic. They also have Bravo probiotics, and more. Please visit their website for more information.

"If you're not stubborn, you'll give up on experiments too soon. And if you're not flexible, you'll pound your head against the wall and you won't see a different solution to a problem you're trying to solve."

~ Jeff Bezos
Founder of Amazon

Chapter 13

Beyond Recovery: The Maintenance Plan

"Success is not final, failure is not fatal:
it is the courage to continue that counts."
~ Winston Churchill

We see these questions on our boards from time to time:

Will my son have to take CD for the rest of his life?

or

Will we be sorting through poop forever?

The answer is No!

Once your child has recovered, you can move to the maintenance phase. Since we live in a toxic world, it is important to continually detox the system, and keep the body free of parasites. While this can look different for every child and every family, the following are some general guidelines designed to keep our kids healthy once they are recovered.

Diet

While some families go back to giving their children foods that aren't permitted here, many do not. Wheat, dairy, and soy aren't "healthy" foods for any of us to be consuming. After reading Olive Kaiser's section on gluten, you may have a tough time giving your child any bread products ever again. That said, once the gut is healed, it should be able to tolerate many of these foods again, to the extent that a "healthy" person would.

CD

Even into the recovered stage of autism, many of the families keep using CD (oral, baths, enemas) to reach an ATEC of zero... or until there are no behaviors left from the autism. Once that is accomplished, then a maintenance plan of one oral dose on Monday and one oral dose on Thursday is enough. Typically, such a dose is 3 drops for children and 6 drops for adults—all in one dose on each of those 2 days. However, each family does this a little differently depending on weight and what the optimum dose was while on the full protocol.

The more I learn about how toxic our planet is (i.e. GMOs, toxins in the air, drinking water, parasites in the environment, etc.), the more I realize how critical it is to be on a at least a limited long-term detoxing program. This is especially true for someone who was, or may still be immunocompromised. I do believe that once a child recovers from autism, their immune system can do the job that it was designed to do. However, healing takes time, and every case is different. Some people ask me if recovered children still take CD once recovered—and to be honest—many do not.

Parasite Protocol

It is impossible to avoid parasites in our world. As Andreas and Miriam explained to us, their larvae are nearly indestructible in nature and can live for years. A strong immune system, as well as sufficient stomach acid, may prevent a parasitic infection from taking hold in the body. To make sure, it is best to do a "mini protocol" every 3 months. You can do the full 18 days every 3rd month or a 1-week mini version—whichever you prefer.

Other Supplements

While ocean water is necessary when detoxing with CD, it is extremely beneficial to all of us as our soils are almost completely devoid of nutrients and are contaminated with heavy metals and toxins. Also, it has been theorized that many GMO crops are lacking in nutrition as well. The 90 bioavailable nutrients in OW can certainly go a long way in keeping our bodies healthy. I especially love that it helps with conductivity in the brain. And, it is conducive to speech and cognitive function as well.

Depending on each individual's needs it may behoove a family to keep giving MCT oil or Vegan 3,6,9 omegas. Certain supplements may still be required if there is a history of seizures.

Chelation

Gentle chelators like Bio-Chelate™ can continue to be used into the recovery phase as heavy metals are present in our air and water.

Hyperbarics

Nothing brings down inflammation quite like a hard hyperbaric chamber. However, 10 to 20 sessions can be very cost prohibitive for some families, making it a very personal decision as to whether or not to continue with HBOT after recovery.

GcMAF

I never felt better than when I did a course of GcMAF injections on myself. Energy went up and so did my ability to concentrate. Again, GcMAF is a fairly expensive intervention and that will factor into each family's decision as to whether to keep using it. or not

In a nutshell, I would at least continue with CD two times a week, and a mini parasite protocol every 3 months, just as a preventative. Staying healthy is as important as getting healthy.

> Um, YEAH so just took an ATEC. We have officially been on the protocol for 12 months now and finishing up our 11th PP. ATEC of THREE!!!!!!!!!!!!!!! 57 to 3 in 12 months. Henry's speech is what is keeping us from 0. He has great conversation with people that are patient and don't interrupt him so we are so close to a BIG ZERO!!! 57 to 3 in 12 months!!!! Far cry from the severe autism diagnosis he got at 2.5 years old. Here is to the doctor that told me my son should be medicated, would never speak, and will probably need to be institutionalized. I hope YOU never say those things to another person!!!!! All you need is hope, determination, and LOVE.

Healin
the symptoms kno
Auti
l Rivera
mberly McD

Chapter 14

Miscellaneous Information You Should Know

"Always bear in mind that your own resolution to succeed
is more important than any one thing."
~ *Abraham Lincoln*

Seizures

An estimated 40% of children with autism suffer from some form of seizures. Seizures can be absolutely terrifying for both child and family and deleterious to the health of a child who is already suffering from various issues. I have talked to many different professionals about seizures and in turn have heard just as many different opinions on why this happens. Many doctors are unsure, while some simply don't express their opinions. Some say it is a virus in the brain or heavy metals, inflammation, or pathogens/parasites. In a presentation by Dr. Andreas Kalcker, he stated that high levels of ammonia in the body can cause seizures and the high levels of ammonia in the body come from parasites. Since we know that CD kills pathogens/parasites, neutralizes heavy metals, and helps to reduce inflammation, it is not surprising that we have noticed reduced, or even eliminated seizure activity in children with seizure disorders that use CD in combination with the Parasite Protocol.

MCT (medium chain triglyceride) oils, which come from the Ketogenic Diet out of UCLA, are also a very important piece to healing the body and eliminating seizure disorders. There is plenty of information on the Internet that discusses the results of people (on the spectrum and otherwise) using MCT oils for seizure disorders.

The following is a list of things that parents on The Protocol have used successfully to reduce/eliminate seizures in their children.

- CD
- Parasite Protocol
- MCT oil

- GABA
- Hyperbarics at 1.75 ATA
- Ketogenic diet
- SCD diet (grain free)
- L-Carnitine
- P5P with magnesium
- L-Carnosine
- Taurine
- DMG
- Pycnogenol®

The first four in this list have proven to be the most important and have shown consistent results. If you have a child suffering from seizures, you would be wise to review and consider these interventions immediately. The others have also proven very helpful and can be added in one-by-one, (always leaving three days between each new supplement) while you watch for a decrease in seizures.

When we introduce GABA, we increase the dose daily in search of the appropriate dose for the individual. While establishing the correct dose for one intervention it is not appropriate to add in other supplements. Watch out for sleepiness or undesired behavior with GABA. In these cases, I would personally discontinue its use, as with everything there is not one formula that is right for every child. Similarly, if you see hyperactivity or undesired behavior with DMG discontinue its use.

All of the above supplements/interventions have proven very important for eliminating seizures, in different combinations, for different families. Whether the seizures are grand mal (tonic clonic) or petit mal (absence), they start to fade away as a result of the Protocol.

Sometimes, when a family starts corresponding with me, their child may already be taking some of these supplements, and they continue to do that. They may have already taken some of these and seen no improvement. Some other families live in parts of the world where these supplements are unavailable, and in that case we focus on CD and killing parasites.

As I mentioned, a critical piece for some of the children with seizures has been the implementation of the Parasite Protocol. This has also led to a reduction or cessation of seizure activity in many children with seizures.

Interestingly, once some moms were made aware of the parasite/seizure connection it was easy to time seizure activity/anxiety/aggression to full and/or new moons. As Dr. Andreas Kalcker talked about in the parasite section, the full moon period is when parasites are mating, many in the gastrointestinal tract, and therefore "wormy behaviors" (anxiety, SIBs, depression, tantrums, aggression, and teeth grinding to name a few) will generally be higher around that period. New moons can also cause an increase in these behaviors.

Children who have a seizure disorder or are self-injurious need to avoid food coloring, eggs, tomatoes, pork, and chocolate. When adding in the supplements for the seizures that we listed above, follow the same rules as before, never adding more than one supplement every three days, and always carefully observing and keeping track of any and all changes in your notebook so we know what causes what.

After starting anti-parasitics with the help of her daughter's doctor, one veteran mom introduced the CD protocol; a combination that has been extremely beneficial for her daughter, who suffered from frequent grand mal (tonic clonic) seizures.

Her Advice:

Most of my understanding of how parasitic infections can lead to seizures involves my own tracking of seizure activity patterns in my daughter, which coincided with new moon and full moon periods. Then, since MOST doctors want references to what they feel are 'reliable sources,' I started by Googling "NIH parasites seizures," which brought me to:

ncbi.nlm.nih.gov/pubmed/18754958
Helminthic parasites and seizures. [Epilepsy. 2008][1] *- PubMed - NCBI*

I would strongly suggest that you document patterns of seizure activity against the Farmer's Almanac of Full Moons (you can even look up past Full Moons) and marry that information with info from sites like the one above. Also, I would highly recommend you hunt down a pediatric infectious disease specialist in your local area (start by researching pediatric staff at local hospitals) and bring with you all information/insight to your first appointment.

Her Testimonial:

From her very first drop of activated CD in early July 2012 (actually her very first one-eighth drop to be exact), I witnessed an improvement in my daughter. Within about two hours of drinking her first ounce of the activated CD water solution (one activated drop of CD mixed into eight ounces of water), I witnessed her sitting still in our kitchen and observing me in such a way unlike she had ever done before. She was calmly observing me instead of running around the kitchen. She was taking my actions in. She was studying me. Her eyes were focused on me, rather than constantly scanning everything else in the room. Both her facial expression and her body language were calmer than I had ever witnessed before. She was more focused, more centered. She appeared content.

This change that I witnessed in her was so noticeable and so sudden, that I couldn't help but think to myself, "So this must be why the first word in MMS is Miracle." It was that amazing of a change in those moments.

Shortly after those incredible moments, my daughter went on to eating contently and then jumping on the neighbor's netted trampoline. She has enjoyed the neighbor's trampoline for years; yet on that particular day, only a few hours after her first drink of a tiny amount of CD, I noticed something quite different in her behavior. As I observed her from the windows of our house, I could see that she was jumping less than usual and instead looking around a lot more. She was calmly looking around at the neighbors' houses, down at some birds in the grass, up at the trees, the clouds, etc. It was all as though she was perhaps truly noticing them for the first time. She had glanced at these things before that day, sure, but she never before appeared to be studying them in the manner she was in those moments on the trampoline that July afternoon. She did engage a bit in some of her tic-like spitting movements with her mouth while on the trampoline, but to nowhere near the intensity, nor duration that would more typically have consumed her prior to that day.

When she came back into the house after using the trampoline and observing her world, I asked her, "why were you spitting out there?" To my surprise, she then very calmly replied, "because it's sensory." Wow! She truly was more connected somehow to her world than ever before. Something good was happening to my girl—only hours after drinking one-eighth of a drop of activated CD with one ounce of water. From those moments on I felt encouraged in my heart and soul that CD could possibly be a very important catalyst toward improving my daughter's health and well-being.

With the help of a caring local doctor, we had already begun some trials of anti-parasitic medications on our daughter in early May 2012, prior to starting CD, in response to behavioral struggles that had been consistently intensifying around full moons every month. (Later, we noticed new moon behavioral intensities as well). We had seen some improvement with anti-parasitic medication, yet CD seemed to somehow boost our daughter toward further improvements that much quicker. In fact, our daughter's ATEC score before starting CD measured 79 on July 8th, 2012 (the day before starting CD), but as of September 30th had dropped down to 55 (only two and a half months later).

Now, in early December 2012, our daughter still appears to be on an overall upward trend of improving health and stability, attributable to the synergy of CD and anti-parasitic medications. Natalie's interpersonal skills have improved, her growth rate has improved, her focus has improved, and her frequency of seizures has lessened.

In fact, at this writing she is 53 days seizure free, which is quite an improvement considering before she was on a terrifying pace of grand mal (tonic clonic) seizures occurring every 2-3 weeks. These are very dangerous, life-threatening events. Her seizures were rapid onset, heading toward grand mal within seconds. They could happen anywhere, i.e. while in her car seat coming back home from a Dr.'s appointment, while driving away from Costco, while running in the backyard playing with the dog, or swinging high on the swing set in the backyard with a neighbor girl. Yet another occurred while wading in the lake (with life vest on), another hit while in our neighbor's four-foot swimming pool with me and her brother. She was right next to me, walking around and then suddenly, she was in the throes of a rapid-onset grand mal seizure that required me to lift her out of pool into her NT (neurotypical) brother's arms. May these be the last my daughter ever knows of seizures.

It is our hope that, in time, CD will be able to take on the lead role as the primary health-support for our daughter, if not, perhaps even someday the sole healthcare support to her. We're looking forward to the days when we may be able to remove or reduce many, or perhaps even almost all, of her current supportive medications (i.e. antibiotic, antiviral, anti-seizure, etc.). With the caring support of parents of The Thinking Moms' Revolution, as well as some excellent local doctors, we suspect that our daughter's life will continue to improve. In the almost 14 years of caring for our daughter in her various states of medical fragility, we have never ever had this much Hope. We feel fortunate to have been swept up into this Revolution and embraced warmly by so many Thinking Moms who are also in the process of working toward more healing for their children. Working to heal illness is so much nobler than working to mask illness, wouldn't you agree? God Bless Jim Humble, Andreas Kalcker, Kerri McDaniel de Rivera and all the TMR families!

UPDATE: January 30th, 2013

I too am so thankful for Kerri and her whole 'crew'. Thanks to Kerri for bringing CD to all of our kids on the spectrum worldwide. My Natalie is now OFF of her former roller-coaster ride of prescription anti-fungals, OFF of her former roller-coaster ride of prescription antibiotics, OFF of prescription antiviral, OFF of prescription low-dose naltrexone, etc. Her belly distention has disappeared, she's gained weight, she's gained height and she's now almost 103 days seizure free (as of 6:16pm tonight). She still has a ways to go toward more improvements, but she's happily climbing up from bottom of the trenches; she's climbing up from what seemed like the very bottom of the abyss that vaccine injury/injuries had placed her in. Thank you Kerri, Andreas Kalcker, Jim Humble and all of the moderators on the supportive websites!!!

UPDATE: February 1st, 2013

My Natalie's long run of 105 seizure-free days has ended. After being off of Albenza® less than 24 hours, BOOM! a grand mal (tonic clonic) seizure occurred yesterday evening. This same thing happened the last time we stopped Albenza®, sooooo we're not sure if it's withdrawal related or parasitic activity related. We're going to closely watch her behaviors this week for signs of parasitic burden. We put her on Alinia® now, just to give her some sort of parasitic coverage while we wait to likely restart Albenza®, soon. She did fine on Alinia® 200mg BID in the past. I'll keep you all posted, but for now we unfortunately need to restart the clock on my Natalie's 'seizure-free days' tracking. I'm bummed, but thought I should keep you in the loop on this; as I've been soooooo excited over the past three months about her freedom from seizures, which I believe was due to the synergy of CD and Albenza®. I'll touch back if/when we learn more.

UPDATE February 2nd, 2013

O.K. so, I just wanted to kind of round out this long thread a bit with my thoughts, for whatever they're worth: I really truly suspect that perhaps too sharp of a drop off (lack of weaning) from the systemic med, Albenza® lead to the seizure. Natalie is stable right now on a low-dose interim of Alinia® 200mg BID for now until all insurance approvals are in for the delivery of more Albenza®. This leads me to believe that the several courses of Albenza® over the past months likely HAS lowered her overall parasitic load/burden fairly well thus far (it's a pretty broad-spectrum anti-parasitic, from what I understand). However, I don't think for a *minute that Natalie's broad spectrum anti-parasitic medicine needs are finished. For this reason, we'll resume Albenza® as soon as we're able.*

Although further discussion/negotiation between myself and Natalie's pediatric infectious disease doctor is required, my thought is that she may need an entire year on Albenza. However, certainly in the future, whenever we stop Albenza®, I'm going to plan for a slow weaning off period so as not to disrupt Nat's delicate nervous system. Also, I'm kind of thinking that perhaps if our kids 'wig out' when CD is eventually dropped that maybe we've not lowered the overall parasitic burden enough, as yet to allow their immune system to 'kick in gear' and properly function??? I don't know, obviously, just theorizing with the brain matter God has given me.

SUMMARY & UPDATE FOR SECOND EDITION: December 1st, 2013

From birth to age 7 years, my daughter Natalie unfortunately had her share of health and developmental struggles. Her diagnoses began with 'Failure to Thrive' shortly after birth, followed thereafter by a Mitochondrial Encephalopathy Partial Complex III Deficiency diagnosis by age 7 months, then Hypothyroidism as well as global developmental and cognitive delays obvious from there. Despite significant medical and developmental challenges, Natalie entered a Kindergarten designed for the 'mild cognitively impaired' (formerly referred to as educatably mentally impaired 'EMI') with daily opportunities for mainstreaming with the typical Kindergarten classroom next door. After a fall 2005 Flu shot early in that same Kindergarten year, however, all bets were off. She regressed very rapidly in every way: medically, developmentally, and behaviorally. Within months of that shot, a laundry list of additional diagnoses began to form: Sensory Integration Disorder, Autism, Epilepsy, P.A.N.D.A.S., P.A.N.S., and Combined Immune Deficiency, to name a few. After much study by a large team of educational specialists, Natalie was reclassified by school professionals by the following April of 2006 to the 'SXI" category of disabilities (Severely Multiply Impaired), having deteriorated terribly from her former classifications of POHI (Physically or Otherwise Health Impaired) and 'CI' (Cognitively Impaired) within only months of that Flu shot. Her significant healthcare needs and behavioral challenges since have necessitated assignment of a one-on-one Para-educator to her case, even while she's been schooled within high adult-to-student ratio basic education special- needs classrooms over the past several years.

In 2011, between the ages of 12 and 13, I began to notice patterns of apparent P.A.N.S. flares in Natalie, which seemed to coincide with the New Moon and Full Moon weeks. When I began to study this phenomenon a bit more closely, I also recognized a pattern of seizure activity that tracked these timeframes as well. In reading about potential parasite activity that is thought to link to the New Moon and Full Moon timeframes, I requested anti-parasitic medications for Natalie. Thankfully, a local Pediatric Infectious Disease doctor kindly accommodated my request. Each time that the doctor prescribed various anti-parasitic medications for Natalie, she would improve. The improvements were noticeable both at school and at home. It was incredible to witness. However, each and every time that she was off of such medications, she would regress back to her former state of illness (displayed primarily by significant behavioral regressions). So, we found that we needed to try to keep her on various anti-parasitic medications more often than off of them, in order for her to enjoy overall improved health and neuropsychiatric stability. Even so, there was still some sort of physiological strain that she was very *definitely experiencing, but we were unable to decipher what it could be. This was frustrating, of course; to witness her continued rollercoaster of ups and downs in health and her various psychiatric disturbances each month.*

It wasn't until a friend suggested we get Natalie started on CD, that the health and behavioral 'rollercoaster ride' began to show signs of smoothing out. In July 2012, after her first drink of CD (only one-eighth of a drop), Natalie began to show initial signs of relief from whatever it was that was still ailing her. Her connectedness and overall psychological state of being changed within hours of that first one-eighth drop of CD. After that first day, we of course then continued with a very slow and conservative ramp-up of CD (orally, then baths, then enemas) alongside various anti-parasitic medications and all of the components of the Kalcker PP (with frequent swap out of Mebendazole with Albendazole, predominantly). With each passing month over the past sixteen months, we've been able to witness improvements in Natalie; perhaps a bit more slowly than some of the younger and/or potentially less health-compromised kids that Kerri's protocol has healed, but improvements nonetheless. Before CD, Natalie's ATEC score was a 79. As of this writing, her ATEC score is a 39. Even more astounding to us than that improved ATEC score have been the changes witnessed thus far in her overall health status and health regimen. Here is a list of some of the improvements that I can very easily recall as I write this (there are likely many more that I could comment upon, if I had more time):



Natalie in 2006 (left) and in 2013 (right)

1. *Daily prescription anti-fungal medications no longer needed.*
2. *Daily prescription antibiotic medications no longer needed.*
3. *Daily prescription antiviral medication no longer needed.*
4. *Daily prescription LDN (low dose naltrexone) immune modulator removed.*

5. *Daily prescription Leucovorin removed without ill effects noticed, as well as several other daily supplements that might have been ultimately not helpful.*
6. *Prescribed Immune Globulin (weekly subcutaneous, formerly monthly intravenous for years) removed.*
7. *Distended belly gone & improved posture (no longer hunched over).*
8. *Formerly very frequent tongue sores/lesions lessening more & more.*
9. *Seizures formerly as high as every 17-21 days in her worst times; now she's enjoyed seizure-free stretches as high as 105 days (3.5 months) followed shortly thereafter by a seizure-free stretch of 168 days (5.5 months). Prescription anti-seizure medication reductions have also been enjoyed as well as fewer headaches resultant of those reductions.*
10. *P.A.N.S. flares controlled with the combination of CD and anti-parasitic meds. Neuropsychiatric symptoms of flares very dramatically declined.*
11. *Overall appearance of improved health, improved language and interpersonal skills, improved attentiveness (per Neurology's opinion at recent appointment).*
12. *Improved stamina and strength (core, legs, etc.) noticed at Special Needs Performance Cheerleading practices, physical therapies, etc. Her ability to peddle adaptive bike has also improved.*
13. *No more nose bleeds, no more ear infections, no more apparent seasonal allergies, fewer headaches (as noted above).*
14. *Incredibly improved sleep and need for naps only once in a while now (as opposed to formerly daily).*
15. *Improved growth rate and normalized appetite.*
16. *Improved language (more descriptive words, more sentences).*
17. *Healthier-looking skin overall; softer, less dry, improved color & ability to tan.*
18. *Improving oral muscular abilities, able to swallow pills/capsules.*
19. *Capable of successful dentist appointments and now even Orthodontist appointments, with calm and ease.*
20. *Increased success rate during therapies (Speech Therapy, Occupational Therapy, Physical Therapy, etc.).*
21. *Less rigidity overall, fewer transition issues, cooperates more often than she ever used to.*

With all of the well-documented improvements noticed in Natalie at home, at school and in doctors' offices, I don't have the same level of fear as other parents might surrounding our open use of CD, as Natalie's doctors are all well informed and quite supportive. We've also formally notified her social worker (both verbally at a home meeting and in writing) of our use of Kerri's CD Protocol (including Kalcker's Parasite Protocol and of course a GFCFSF/low sugar diet) while under Natalie's local medical team's support and medical monitor. We're 'out of the closet', so to speak, when it comes to our use of CD for improving Natalie's health. It's been quite obvious to Natalie's doctors; actually, that Kerri's protocol has been extremely complementary to their medical efforts for improving Natalie's health and overall quality of life.

There's of course no way to predict with certainty how far my sweet Natalie will be able to ultimately improve via this protocol, but based upon what we've witnessed thus far, I do feel that her current best hope for continued improvement lies within the pages of this book; as these healing strategies of Kerri Rivera's have brought Natalie toward more health (physical, neuropsychiatric, emotional and even some initial cognitive improvements) than any other medical effort attempted since her 2005 Flu shot injury. All other medical efforts for Natalie over the years, I feel, perhaps only temporarily patched her severe illness. Kerri's methods actually work to attack disease, kill it and remove it. Yes, that's right. Eight years after Natalie's tragic rapid spiral downward, it's now finally a time of healing for Natalie. Thank you, Kerri Rivera, for all of your help given to our girl and to so many children around the world.

Self-Injurious Behaviors (SIBs)

Self-injurious behaviors (SIBs) can be absolutely devastating for families with children on the autism spectrum. Common self-injurious behavior includes: headbanging, hand biting, pinching, slapping head/ears, eye poking, hair pulling, scratching/rubbing, throwing one's body on the floor, etc. The horror of watching your own sick child further inflict pain onto himself, and the helplessness of not knowing what to do to help him is heartbreaking. I have met with families through the clinic who have had terrifying episodes of SIBs in front of me as well as at home, and many of these families as well as others are now using the Protocol to help their children with very good results.

There are many theories as to why some children have SIBs. The article "Self-Injurious Behavior" by Stephen Edelson on ARI's website discusses several different theories and supporting research.[2] The theory that most fits what I see on the ground is that of pain alleviation. Many of our kids are in chronic pain and cannot tell us. Sadly, we haven't always had answers to help them.

If we follow this thinking, and assume that many of these children suffer from severe gastrointestinal pain, or headaches (supported by head banging, gut clutching, etc.) we can hypothesize that much of this pain can come from pathogenic overload, parasites wreaking havoc on the body and the resulting inflammation.

Families applying CD in combination with the Kalcker Parasite Protocol are reporting a dramatic reduction in SIBs in their children. I believe there is an important connection to be made here, as we eliminate pathogens and parasites SIBs decreases. More research is needed, but for families facing the horrors of self-injurious behavior, this combination could be of great value. (More testimonies on decreased SIB's can be found in Chapter 2, and the Miracles and Testimonials section at the end of the book starting on page 357.)

Prior to starting CD, we had tried almost every autism biomedical protocol. We saw several DAN and GI specialists and numerous other practitioners. We spent tens of thousands of dollars on consults, supplements, diets, medicine and medical procedures not covered by insurance. My daughter either had no response or negative ones and she continued to get worse. She developed extreme self-injurious behaviors that progressed to the point of her needing to be restrained several times a day in an attempt to prevent her from pinching or biting herself until she drew blood. Her body was covered with bruises and cuts. She would also pull out big clumps of her hair. She would be up for hours screaming in the night with these behaviors. She was severely malnourished despite the fact that two registered dieticians had deemed her daily caloric intake adequate. She was 14 years old and weighed a little over 70 pounds. I honestly did not think that CD would be any different than anything else we had ever tried but figured things could not get much worse.

Since starting CD her self-injurious behaviors are almost entirely gone. She went from having to be restrained almost daily to once in the last 5 months. Her former multiple daily 45 minute self-injurious tantrums are now a few minutes of crying or protest and happen once a week if at all. We have noticed gains in language and cognition (20 point drop in her ATEC score). After years of fluctuating between loose stools and constipation, she is now regular and has gained almost 10 pounds. She sleeps through the night and we are able to take her places that we would have never dared to before. If my daughter can make gains this drastic in 5 months at age 14, I can't wait to see what the future holds.

Julie, Colorado, USA

PANS, PANDAS and PITAND

PANS stands for *Pediatric Acute-onset Neuropsychiatric Syndrome*. It encompasses PANDAS (Pediatric Autoimmune Neuropsychiatric Disorder Associated with Streptococcal Infections) and PITAND (Pediatric Infection Triggered Autoimmune Neuropsychiatric Disorders), where PANDAS is a subset of PITAND. Dr. Susan Swedo, Chief of Pediatrics & Developmental Neuroscience Branch at the National Institute of Mental Health (NIMH), and her research team identified a subtype of OCD in children during the 1990s that is triggered by infection. Streptococcal infection has been most studied; however, any infection can trigger this condition.[3]

I have run across these diagnoses a lot since I have started helping families in first world nations. There seems to be an overlap in some autism and PANS/PANDAS/PITAND cases. I have heard that around 25% of children with ASD's also suffer from PANS/PANDAS, and/or PITAND. Some practitioners would put that figure even higher. However, since further research is needed, and this field is still developing it is impossible to say for certain at the moment.

According to the International OCD (Obsessive Compulsive Disorder) Foundation some of the symptoms of PANDAS/PANS may include:

- Acute sudden onset of OCD.
- Challenges with eating, and at the extreme end, anorexia.
- Sensory issues such as sensitivity to clothes, sound, and light.
- Handwriting noticeably deteriorates.
- Urinary frequency or bedwetting.
- Small motor skills deteriorate - a craft project from yesterday is now impossible to complete.
- Tics
- Inattentive, distractible, unable to focus and has difficulties with memory.
- Overnight onset of anxiety or panic attacks over things that were no big deal a few days ago, such as thunderstorms or bugs.
- Suddenly unable to separate from their caregiver or to sleep alone.
- Screaming for hours on end.
- Fear of germs and other more traditional-looking OCD symptoms.

I know several moms who have been able to reduce/control/eliminate their children's symptoms with CD. In fact, families began to eliminate the antibiotics that they were using as they reached full dose of CD. I am by no means suggesting anyone reduce or remove a prescription medication without a doctor's supervision. I am simply reporting on what I have witnessed.

We know that CD kills bacteria, so we could hypothesize that CD could have a similar effect on the PANS/PANDAS/PITAND symptoms that an antibiotic would. What has worked in these cases is upping the number of doses of CD given a day so as to kill pathogens around the clock. For PANDAS/PANS/PITAND use two baby bottles a day. If your max dose is eight drops in an eight ounce bottle, and a PANDAS flare presents, prepare two baby bottles with eight drops in each and give one dose every hour over the course of 16 hours. Some families are doing 16 doses a day even if there is no flair and the child is doing excellent.

As noted previously, in the absence of research, we cannot recommend doing nothing for these children. Their suffering is intense and the risk of long-term damage cannot be ignored. We also do not know if some of these children remit spontaneously later in adolescence. We do not know if some of them grow into adults with the most treatment resistant OCD due to permanent basal ganglia damage. While we research those questions, offering treatment options at the local level, especially in the first few months after onset, could be critical to the long term success for these kids.[4]

We parents are pioneers in the research surrounding PANS/PANDAS/PITAND, so it is critically important that we document what we are doing with our children and what is working for them. In fact, A MOM was the first to discover the connection between strep and OCD/tics. Her child was the first documented PANDAS child. Dr. Susan Swedo reinforces that physicians should listen to what the mothers have to say![5] Speak up to your doctor, share your findings, join our forum to learn, and share what is working for you. Parents are driving the biomed movement (and always have) for ASDs as well as PANS/PANDAS/PITAND. In fact Dr. Bernard Rimland was a parent and the first to suggest biomedical interventions for people on the spectrum. We as parents can help countless other families by sharing our experiences.

You will find more info on PANS/PANDAS/PITAND at:

www.pandasnetwork.org

and

ocfoundation.org/PANDAS

Fever Therapy

Dr. Kenneth Bock and Nellie Sabin, in their groundbreaking book *The Road to Immunity: How to Survive and Thrive in a Toxic World*, explain how to use fever therapy and how it is an incredible tool for healing.[6] When a mom emails me to tell me her child has a fever, it tells me that the immune system is reacting to an invader, and we have an excellent opportunity to kill pathogens in the body. Having a fever is part of an effective immune response. This is also true in infants as well as small children. Using over-the-counter (OTC) fever reducers interferes with the body's own ability to fight infection.

This section was excerpted from the aforementioned book.

> Fever has long been recognized as an important tool in the process of healing. The process of heating the body is called "hyperthermia." Hyperthermia, or ordinary fever, can be very effective against cancer cells, various pathogens, or invading organisms that cannot "tolerate the heat." Hyperthermia may not kill all pathogens in the body, but may reduce the number of invaders in the body to a manageable level for the immune system. Hyperthermia may also be responsible for stimulating the immune system to produce cytokines i.e. antibody production, and release of toxins from fat cells.

What Temperature Constitutes a Fever?

According to Dr. Robert Sears, the following are normal temperatures in children over 3 months:[7]

Normal temperature: 97° to 99° F (36° to 37.2° C)
Low-grade fever: 99° to 100.9° F (37.3° to 38.3° C)
Common fever: 101° to 103.5° F (38.4° to 39.7° C)
High fever: 103.6° F (39.8° C)

Fever Therapy in Practice

If your child develops a fever, it is not a failure of the body that needs to be corrected, but a mechanism that brings the body closer to healing. Rather than administer an OTC remedy to reduce fever, apply a cool, damp washcloth to the forehead and neck, replace them as they warm, and let the body do its job. Some parents put damp socks on their child's feet.

During a fever you can dose orally, as well as do one CD bath and one CD enema in one day. Keep dosing CD every hour (16 to 24 doses a day), unless the person stops eating. Even if you must reduce the number of drops, even if you are only giving one drop, keep dosing every hour. CD baths, as well as baths in general, are also your friend if your child has a fever. Some parents have given several baths throughout the day while a fever is present with great results. Bath the child if the fever spikes. Always be vigilant that the temperature does not rise too high or too fast so as to cause febrile seizures, we have to use common sense and trust our instincts. Bath and keep a cool damp wash cloth going 24/7 until the fever pases.

According to the National Institute of Neurological Disorders and Stroke febrile seizures are convulsions brought on by a fever in infants and small children. The majority of children with febrile seizures have rectal temperatures greater than 102° F. Approximately 1 in 25 children (4%) will have one febrile seizure. Although febrile seizures can be frightening to parents, the vast majority of febrile seizures are fast and harmless. There is no evidence that short febrile seizures cause brain damage. Large studies have found that children with febrile seizures have normal school achievement and perform as well on intellectual tests as their siblings who don't have seizures.[8]

If your child has a febrile seizure, experts recommend that you try to stay calm, keep the environment around your child safe (place them on the floor if they are not, and clear objects out of the way), and allow the seizure to resolve spontaneously without restraint. Try to look at your watch so you will know how long the seizure lasted. Do not put anything in your child's mouth as it may break, obstructing their airway.

Skin Issues

I have been hearing about skin issues right and left: rashes, hives, redness, acne, eczema, psoriasis, pustules, etc. It is very easy to assume that since skin is on the outside of our bodies that these reactions are caused by exterior factors (i.e. irritation from a detergent, mold, etc.). However, the skin is our largest detox organ, and many pathogens seek exit through the skin causing many of the above conditions.

The scenario that I keep hearing is the following: We just started the Kalcker Parasite Protocol. Little Johnny has a rash with white heads on his legs. What do I do? When the families keep up with the parasite protocol, and continue dosing daily with CD these eruptions disappear, and this is generally accompanied by improvements in behavior, or hyperactivity/anxiety.

We need to think about skin issues as outward manifestations of inner toxicity, and use our protocols accordingly. Skin issues can be a good indicator that something is being flushed from the system, or something needs to be flushed from the system. The Kalcker Parasite Protocol combined with CD tends to eliminate skin issues at the root.

The following paragraphs were excerpted from leakygut.co.uk, written by Dr. Gloria Gilbere ND DA hom PhD[9]:

> Experts agree that most chronic skin disorders, specifically psoriasis, is the external manifestation of the body's attempt to eliminate internal toxins that have accumulated within the lymphatics and blood stream by "seeping" through intestinal walls in a condition known as leaky gut syndrome.
>
> In working with clients around the world, the protocols that have been most effective are those that include repairing the intestinal walls by first beginning a protocol to eliminate candida yeast and parasites.
>
> The most effective cleansing protocol is obtained by clearing out these "uninvited" health-depleting microorganisms in order to release the accumulated pressure on the liver and the intestines—allowing free passage and thus reduction of overall toxic load.

The following paragraphs, authored by Dr. Edward F. Group III, DC, ND, DACBN, DABFM, were excerpted from parasite-cleanse.com/intestinal-parasite-symptoms.html[10]:

> **Symptoms of Intestinal Parasites Related to Skin**
>
> The presence of intestinal parasites, at times, manifest as allergies, tumors, and various other skin conditions.
>
> Intestinal parasites cause the human body to release hormones and immune system defenders, which in turn irritate the skin and cause various skin conditions such as acne, hives, rashes, itching, weeping eczema, ulcers, swelling, sores, lesions, blisters on lips, and dermatitis. It also deprives the skin of its usual glow.
>
> Intestinal parasites cause irritation and inflammation in the stomach making it difficult to digest certain types of foods. The presence of undigested food particles in the stomach causes the body to produce increased levels of eosinophil, an immune system defender. These eosinophils inflame the body's tissue and cause skin rashes.
>
> Intestinal parasites trigger the body's immune system to develop a tumor-like mass known as granuloma to encase parasitic larvae or eggs. Granulomas usually develop in the colon, rectal wall, lungs, liver, peritoneum, and the uterus.

Btw, you were bang on re his allergies and PP (parasite protocol). He had this horrible red lip thing because of food allergies. He would make it worse by rubbing it. It would get really bad. After first PP (Parasite Protocol) - NO MORE RED LIP ISSUES!

Families often tend to panic when dealing with sudden "unexplained" skin issues. If you are seeing chronic or acute skin issues I think there is enough evidence to look towards parasites as the main or at least a contributing culprit. Therefore, if we work towards removing the parasites causing the symptoms, rather than treating the symptoms topically we can expect an alleviation of the symptoms.

If you are seeing acute or chronic skin issues and you have not started a Parasite Protocol, I would suggest you revisit the parasite chapter and go over the recommendations with your healthcare provider. Keep dosing CD, in some cases upping the dose has helped resolve the issue faster, and in the case of severe irritation using a CD spray topically can provide relief (10 activated drops per ounce of water in a spray bottle) and a CD bath can also help. I have seen most, if not all skin issues resolved with CD and/or the Kalcker Parasite Protocol.

Healing Adults with Autism

Common thinking in the biomed community and the autism community at large is that autism is only "curable" or "recoverable" up to a certain age. I have heard that two to nine years old is the "golden window" for autism, and that after nine years of age improvement would be possible, but not recovery. The neural pathways would be set, the damage done, and the child would retain the autism diagnosis for life.

Not anymore. This year a 15-year-old recovered from autism, as well as two 17-year-olds. In addition, I am helping an amazing mother of a 31-year-old with autism that began the Protocol and for the first time in 28 years was seeing real progress with her son. In fact that young man's ATEC score dropped from a 65 to somewhere in the 20s in his first three months on The Protocol. I want to prove that autism recovery is possible at any age. It may take longer, and the road may prove more challenging, but it's already happening. Families that have been using biomedical interventions for more than ten years are finding the Protocol and sharing their gains.

Older children and adults on the spectrum start the same way as the little kids—clean up the diet first, and then on Day one of CD, give one drop in eight ounces of water over eight doses throughout the day. It is so important to start low and slow even with adults because they have often been chronically ill much longer than young children and have deep rooted pathogenic and parasitic infections. This means that when we start giving CD they might experience a detox reaction considering the amount of pathogens that will be dying.

Working with Neurotypical Adults

Can CD benefit parents and other adults not on the spectrum? Absolutely. You can literally find thousands of testimonials on the Internet (Jim Humble's website, www.jimhumble.org or www.curezone.com, etc.) on people who successfully detoxed, or healed a myriad of illnesses using CD.

Many parents who have seen improvements in their children have decided to use CD, or the Kalcker Parasite Protocol for themselves. I have done CD oral, baths, and enemas on myself, especially when I feel "something coming on" and with great results.

It's important to keep in mind that just because we weigh more than our children doesn't necessarily mean we should jump in and go to full dose from one day to the next. The best way to start an adult who may have 40 or 50+ years of accumulated toxins/pathogens/parasites is low and slow. Use the baby bottle method and start day one with one drop spread out over eight doses and go up from there. Chart your progress, see how you feel, go low and slow. When we as adults use the protocol it can be great for us, but also a window into how our children are feeling.

I love to see a mom or dad begin CD with their child. Both begin at one drop on day one in eight ounces of water, 1/8 or a drop per dose, for eight doses throughout the day. Starting with our children gives us a much better understanding as to how our child is feeling, and when we up the dose how that feels as well. This includes enemas. Once parents see how good they can feel after an enema, it helps garner confidence, if we had doubts about using them for our children. Applying our own enemas can help to remind us just what a powerful tool they are for healing.

Many of the parents doing the protocol for themselves write me to tell me about their remission from fibromyalgia, chronic fatigue syndrome, Lyme disease, life-long constipation, etc.

We all do the parasite protocol in my house so as not to re-infect my son, as parasites can be highly contagious. Last year I did a round of parasite medications prescribed to me by a doctor. During the course of treatment I felt a tremendous amount of anxiety and some depression (feelings I had never felt before) right before I passed worms, I can assure you it felt awful. That experience motivated me to encourage parents to get these invaders out of their children's bodies.

As soon as I started passing worms and detoxing more with CD, I started to feel good again. The cough that I had had on-and-off for years miraculously disappeared. Seriously, go low and slow, a toxic body can only process so much at a time. Too much too fast can cause headaches and diarrhea. The way I see it, there is no need for that, listen to your body and go at whatever pace you need. Don't just "push through," low and slow wins the race. Always remember to drink water when doing any sort of detox!

Tax on a Marriage

During the first five years after an autism diagnosis married couples face an estimated 80% divorce rate, and a 90% chance of divorce beyond the tenth year of marriage. My family was almost a statistic. Even before we had a diagnosis, our family was suffering. Due to Patrick´s constant screaming and tantrums, he wasn't sleeping at night, and that meant that no one else was sleeping either. He had also stopped being the affectionate baby that he was for the first two years of his life, which was emotionally challenging for all of us. We were all over stressed and sleep deprived, not to mention having symptoms of post traumatic stress disorder (PTSD).

If I could give any advice to families dealing with a new diagnosis it would be to start The Protocol and CD immediately. The sooner the affected family member starts to heal, so will the rest of the family, similar to the sun coming out after a storm—this too shall pass.

Financial Stress

Not only is an autism diagnosis emotionally stressful on a marriage, but it can be extremely financially stressful as well. The Protocols outlined here can be extremely cost effective, even if including ocean water. Recently, one of the moms using The Protocol did some calculations comparing what she spent previously (see table on page 342) using another biomedical intervention with many supplements, etc., to what she spends now (see table below).

The Protocol - Estimated Cost

Product	Size	Price	Reorder Schedule	Current Cost per Month
CD	1 bottle	$22	1/mo	$22.00
Diatomaceous Earth	2.5 lb	$15	1/3mo	$5.00
Rompepiedras	50 ml	$24	1/2mo	$12.00
Vortex Ocean Water	1 L	$40	1/mo	$40.00
THERALAC®	30 caps	$36	1/mo	$36.00
Natures Way® Neem	100 caps	$4.09	1/5mo	$0.75
Pyrantal Pamoate (Combatrin®)	32 oz	$35	1/6mo	$5.00
NOW® Castor Oil	16 oz	$8.23	1/6mo	$1.38
Mebendazole	90 tabs	$28	1/5mo	$5.60
TOTAL				**$127.73**

Defeat Autism Now! based Protocol - Estimated Cost

Product	Size	Price	Reorder Schedule	Current Cost per Month
Actifolate	60	$15.00	1/2mo	$7.00
Calm PRT	120	$89.00	1/5weeks	$78.00
Caprilex™	90	$16.00	1/6weeks	$10.60
Cytoflora™	4 oz	$79.00	1/mo	$79.00
Designs for Health Lithium Synergy	120 caps	$22.00	1/mo	$6.00
DMG	90	$16.00	1/5mo	$10.60
Douglas B-Complex	60	$21.00	1/6mo	$21.00
Douglas CoQ10	60	$49.81	1/6mo	$12.50
Enhansa™	150 caps	$58.00	1 / 75 days	$29.00
Enzymedica Virastop™	120 caps	$32.11	1 / 4 months	$8.00
Garden of Life Probiotics	81g	$32.17	1/mon	$32.17
GI Revive	225g	$52.00	1/mon	$52.00
Homocycsteine Supreme	60 caps	$20.00	1/4months	$5.00
Kirkman Digestive Enzyme	200 caps	$60.00	1/3months	$20.00
Kirland Vit E	500	$13.65	1/16months	$0.84
Klaire Multivitamin	180	$28.00	1/3months	$9.00
Liver Life	4 oz	$50.00	1/2months	$25.00
Magnesium	240	$13.25	1/6months	$7.00
Metagenics Adreset®	60	$33.00	1/4months	$8.00
Milk Thistle	100	$25.00	1/3months	$8.00
NDF+	1 oz	$80.00	1/6months	$15.00
NeuroProtek®	4 bottles	$140.00	4/4months	$35.00
NeuroScience Avipaxin	60	$58.00	1/2months	$28.00
NeuroScience EndoTrax	1 bottle	$27.00	2/month	$54.00
NeuroScience Kavinace	120	$65.00	4/4months	$32.50
New Beginnings Copper	50 ml	$20.00	1/year	$1.75
NOW MCT	32 oz	$17.00	1/6months	$2.80
Nutribiotic GSE	4 oz	$16.99	1/6months	$3.00
OSR	30	$60.00	1/2months	$30.00
Oxycell Glutathione Cream	1 jar	$33.00	1/2months	$16.50
Pharmax Cod Liver Oil	8 oz	$13.33	1/mon	$13.33
Source Naturals B6 (p5p)	240	$15.00	1/6months	$2.60
Source Naturals Evening Primrose Oil	90	$7.45	1/6weeks	$4.97
Source Naturals Gaba	100g	$18.00	1/4months	$4.50
Source Naturals Lysine	200	$10.00	1/mon	$10.00
Source Naturals Quercitin	200	$25.80	1/3months	$8.25
Speak EFA	60	$42.00	1.5/month	$63.00
TheaNAQ	90	$54.00	1/month	$54.00
Therabiotic	120	$69.00	1/2months	$35.00
TravaCor Jr.	120 caps	$24.00	1/4months	$7.00
Vit B12 shots	1 refill	$45.00	1/3months	$15.00
Wobenzyime®	120	$60.00	1/2months	$30.00
TOTAL				**$894.91**

Tips for a Non-Toxic Home

Many of our children on the spectrum have chemical sensitivities, and even if they don't, it's wise to limit their exposure to toxins during the healing process as much as possible. Toxins are not good for anyone at any point in their life. The benchmark investigation "Bodyburden: The Pollution in Newborns" by the Environmental Working Group[11] (see Appendix 13, page 499) explains why this is so important for children with developing brains and immune systems. The following is a list of products to use instead of toxin filled, name brand cleaning products.

Floor cleaner: Add one cup of white vinegar and baking soda to a bucket of water (add a squirt of liquid soap if you like).

Air Freshener: To remove odors from carpets spread on baking soda and then vacuum the carpet. Simmer cloves and cinnamon as air freshener.

Removing Toilet odors: Borax

Trashcans: Spread baking soda in the bottom, then spray to disinfect with a solution of borax and water.

Dish soap: I use liquid dishwashing soap and white vinegar to cut grease. If you buy dish soap make sure it's biodegradable.

Disinfectants: Borax with water is an excellent disinfectant, or spray CD.

Laundry detergent: Soak the clothes for an hour in borax soap before putting into the washer.

Oven Cleaner: Dissolve two teaspoons of liquid soap (not detergent) and two teaspoons of borax with enough warm water to fill a spray bottle.

Windows and Mirrors: Club soda in a spray bottle

Toilets and Tubs: Baking soda with apple cider vinegar

96% Alcohol: Kills parasites on enema catheters, etc., and is great for cleaning bathrooms.

Videos

I have had many parents ask me if I think it is a good idea that their child watch "Genius Baby" or other videos that are supposed to help with their development. I do not believe these videos to be appropriate for a developing brain. Studies were done in Cuba that found that excessive TV watching before three years of age can cause the symptoms of autism. When the TV was removed from the children that presented symptoms of autism, the symptoms disappeared. They also reported that TV watching could cause neurological discharges in the brain.

I can also tell you that the only time my son stims or flaps is when he is allowed to watch TV. When he was younger, and deep in the throes of autism, the only thing he wanted to do was watch TV, while running back and forth and squealing. Any other activity was met with screaming and tantrums. He is much more interested in other activities now, and easily transitions from one to the next, including school. However, he still requests to watch YouTube in the evenings when all of his activities are complete, and that is truly the only time he flaps his hands anymore. To me it is very obvious that TV is a source of over stimulation for him. However, it is hard to deny him a truly preferred activity, especially when he enjoys videos on cooking and foreign language! The least amount of screen time (TV, computer, iPad, etc.) the better, however, we do what we can.

Therapy Options:

ABA is not the only therapy for children with autism.

Many parents worry because ABA/IBI is either not available, or not affordable to them. I firmly believe that something is better than nothing. At the same time, I have seen many children recover without any ABA or IBI. Here are some of the options that have worked for families in conjunction with the protocol:

- ABA - Applied Behavior Analysis
- Occupational Therapy
- DIR® Developmental - Individual Difference, Relationship-based Model
- Floortime Therapy
- TEACCH - Treatment and Education of Autistic and Related Communication Handicapped Children
- Son-Rise®
- PROMPT - Prompts for Restructuring Oral Muscular Phonetic Targets
- Sensory Integration Therapy
- RPM - Rapid Prompting Method
- Supportive Typing

There are many other options not mentioned here. Human interaction is key for our children on the spectrum to find joy with us in our world.

I have known many families to have varying degrees of success with all of the above therapies. Some are better for younger children and some for older children. Depending on the areas most lacking in your child's development, you can investigate any one of these types of therapies. Families in many countries where insurance doesn't cover any type of therapy have had to be trained themselves in how to apply therapy. Sometimes an aunt, sister, cousin, or neighbor steps up to help out. No ONE therapy has been fundamental to all of the recovered children and for that reason I say something is better than nothing when it comes to therapy.

Even household chores can be therapeutic and task oriented. Simply because a person has autism doesn't mean they can't have responsibilities and learn new skills while helping out in the home.

A word on laboratory testing

I can't stand to watch people waste money that they could be using for healing their children through various interventions on laboratory testing. If you have all the money in the world, and want to chart your child's progress through laboratory testing, so be it. However, the rest of us sometimes have to choose between expensive testing and treatment. So many families have come to me after spending thousands of dollars they didn't have on testing to tell me their child has viruses, bacteria, and candida. Am I surprised? Never. I have yet to see a child with regressive autism that does not have pathogens/parasites. No matter which pathogens are present, we use CD.

Testing for parasites is woefully lacking at this time, and in fact, the only practitioners who have consistently diagnosed parasites have been veterinarians and practitioners of alternative medicine (also Metametrix labs have identified parasites in some cases).

Generally speaking, if a child doesn't have viruses, bacteria, yeast, parasites, heavy metals and allergies they don't have autism.

Stay Up-To-Date

Subscribe to our Newsletter!

Just go to www.cdautism.org and enter your name and email address...


CD AUTISM dot org
Autism: Avoidable. Treatable. Curable.
SEARCH
MENU
Frontpage
Forum
MMS
Diet
Miracles
Miracle videos
Consult Kerri
Andreas Kalcker
Andreas Kalcker Español
Kerri at AutismOne 2012
MMS Autism Worldwide
MMS Fact sheet
CD vs. Chlorine
Donations
Contact
NEWSLETTER
Email*
Name
Subscribe
CONSULT KERRI
BUY BOOK
JOIN OUR FACEBOOK DISCUSSION GROUP!
Welcome Video for CD Autism / MMS Autism
0:00 / 1:17

Welcome to CD Autism! :-)

Created on Friday, 12 October 2012 06:19

A total of **100 children** have so far been **recovered** (ATEC score of 10 or below,) using the CD Autism protocol! CD stands for Chlorine Dioxide, the active ingredient of MMS1

For more miracles, please check our video testimonial section!

Thank you so much for visiting our site! We hope you will find the information that you need to help your child with an Autism Spectrum Disorder. If it's your first time here please watch the video below explaining how to begin The Protocol

Our latest free webinars on Ustream:
MMS Conference in Sofia, Bulgaria, with Kerri Rivera and Andreas Kalcker (02-02-2013)

Help Andreas Kalcker (11-23-2012)
Read more - Sign petition

Thank you for visiting!!

Chapter 15

Final Thoughts

If you knew how powerful your thoughts were
you would never think a negative thought again.
~ Peace Pilgrim

What would be your message to families of children with autism who have just read the book, but not started the protocol?

Do not wait! Get started now! Autism is Avoidable, Treatable and Curable! You don't have to spend fortunes on lab testing, imported foods nor supplements. Even if the medical community can't decide if your child has autism, PDD-NOS, ADHD, Asperger's, PANDAS, etc.... don't wait! Start the diet. Even if you cannot do more than that, it will help. Some children have lost their diagnosis with just diet. There are parents all over the world doing biomedical protocols for autism, get together with them, join the forum at...

www.cdautism.org

...or the CDAutism Facebook group. The Internet helps us all to be close and share information. Don't let anyone tell you the diet doesn't work, just keep going and don't stop. There is never an excuse to not do what is right for your child. "Their future depends on our courage."

The final chapter of this book is yet to be written. Until the day we have recovered every victim of regressive autism, there is no success. Just progress. Here I have expressed what I have seen and what the road of autism recovery has brought to me. I have learned a lot and continue to learn. Our children need us to keep learning and searching until we find what unlocks them from their autism. Not everything works for everyone. However, I have seen that this protocol works for most. Especially when it is done exactly as it should be. If you have found this book you have an advantage that I did not have with my son. When I first learned of Patrick's diagnosis I lost precious time and money that I didn't have to lose, trying interventions that didn't yield results. In the nine years that my son has been in recovery I have yet to come across another protocol that has helped as many children to recover from autism in such a short amount of time—less than three years, to be exact! As of the date of this writing in May of 2013, 93 children have lost the diagnosis of autism and every month more and more are recovering.

Please remember that if your journey is autism you will never walk alone. I am here too. Just one click away...

www.cdautism.org

I wish everyone who is ill to have the fastest recovery possible from whatever it is that ails them.

To be continued…

Dr. Andreas Kalcker, Kerri Rivera, Jim Humble, in Puerto Vallarta, Mexico 2012.

Chapter 16

Healing Beyond Autism...

When TRUTH is found, understood and accepted is when we realize it was not even close to what we thought it would be...
~ Miriam Delicado

As Jim Humble has been proving for many years, chlorine dioxide is a molecule capable of healing many common ailments. When combined with the other elements of this protocol, in the correct order, it has shown to be even more effective. We have decided to include this bonus chapter because it is time to start sharing this information with everyone, as pathogens and parasites are the root cause of many of the diseases that are causing suffering in our world today.

As parents saw improvements in their children's health from the protocol, some of them decided to use it on themselves as well. Similarly to when the flight attendant tells you to put on your own oxygen mask first before helping others, it is important to take care of yourself if you want to be able to help your children heal, grow, learn and mature.

Over time, parents who followed in their children's footsteps started to have some undeniable gains in their own health. This was an added bonus many didn't expect, and we couldn't resist sharing their stories with you.

After reading the parasite chapter, you may have been surprised to see how many common symptoms can be caused by parasitic infections. Imagine what would happen if we could get this information into the hands of people who have seen many doctors, used various drugs, and applied countless protocols for years while only masking the symptoms of the underlying cause. So, there should be no surprise if going after the real cause was life changing in real ways.

The following testimonials are a small sample of how some of these people's lives have been changed. Serious afflictions such as Lyme disease, fibromyalgia, chronic fatigue syndrome (CFS), depression, cancer, and chronic infections, are just some of the conditions that improved or completely cleared up. By cleaning up toxic pathogens and parasites, as well as removing foods that feed these invaders, it should be no surprise that disease triggering inflammation is reduced so true healing can take place.

I am so excited for you to read these, and I know that some of you will recognize yourselves here. Please know that healing is possible! We have a public Facebook group called *CD Health* where adults using the protocol for themselves can share questions, doubts and success stories. I highly recommend that you check it out if you are looking for support or some guidance getting started.

Testimonials Beyond Autism

After we saw our son recover from ASD using CD, I tried CD myself and it helped me recover from Lyme and its co-infections. Some of our extended family heard about our success and they have had very good results using CD for treating Hypertension, Diabetes and Liver problems. My younger NT son used to bang his head in sleep since he was born, CD has now resolved the problem. I think anyone who tries CD sincerely, can only benefit in treating so many hard problems. One very beneficial side effect I have seen with CD is the resolution to seasonal allergies and improvement in the immune system to the point where kids do not fall sick or catch colds. In this regard CD is much better than yearly flu shots which have so many toxic elements in them and still do not protect adequately.

—Nilesh

To say I was anxious about the impending birth of Baby #2 is an understatement. I felt like I had failed our first born on so many levels and was a mess believing that I'd do the same for our new daughter.

But alas, she was born a perfect and healthy baby girl. So was Callum, our son, but unlike Lila who had zero interventions, Callum had antibiotics from my labor, the Vitamin K shot, HiB, and DTaP. And it was the DTaP vaccine at 15 months that took the shine from our sweet boy's eyes.

We discovered Kerri's protocol when Lila was 3 months old and more worries cropped up about how to best protect her from the die off that was going on in our house.

At 5-months, she developed an eczema patch underneath her chin, became chronically constipated, and her normally cheerful disposition became irritable.

As soon as she hit the 20-lb mark, I started giving her 20 drop CD baths, low dose oral CD, and 3 drop CD/150 mL water enemas. To my horror and surprise, Lila started passing 1" baby roundworms almost daily.

In a family with both NT and ASD children, the NT child always has some type of quirky behavior. Now we know why! Parasites do not only affect the ASD *population, they affect everyone. Having CD in my tool chest gives me the power to prevent so many things that may have been in my daughter's future.*

Don't be afraid to treat your babies! Her eczema is gone and she's pooping regularly once more.

I write and share my story in that it might help or save someone else's life. That it may just be the key to help someone see what may be what is happening for them as it was and is happening to me. If it helps just one person onto their path to recovery and health then it will have been worth sitting down at this computer and sharing it.

For the past 10 years or so my world has been collapsing in on me, and getting smaller and smaller, and accelerating the past 5 years. I have felt as if I were under a thick coffee mug on the edge of a table about to fall off. On a scale of 0 to 20 with 0 being death and 20 being fully alive and cognizant, I felt as thought I was at 3 staring at 0. For the past 5 years at least I have done so much research, listened to so many radio interviews, done so many different modalities, bought so many products, paid a lot of money to different therapists, ate weeds, made my own concoctions, etc. My mother would always say to me wow you should be so healthy to which I would reply no mum, actually I am not. I began feeling like a phony. I ate real good took all the right stuff, got plenty of rest foraged for my own food and spring water, got exercise, walked barefoot, etc, but always felt exhausted and looked worse and worse. I was fighting with everyone it seemed and chasing people away including family.

Four months ago my wife decided we should go away on a weekend getaway and relax. We fought the whole drive up there and when we got there she threw me my room key and said you're on your own. I spent the whole weekend in bed and on the trip home we both decided to end our 20 year relationship and marriage. I was good with that and looking forward to being on my own. I was finally chasing the last person who mattered to me away.

A week later an angel came into my life. I have been listening to oneradionetwork.com for the last 5 years and on this day Patrick Timpone had a lady by the name of Kerri Rivera on and she spoke about how she was curing kids with autism and that the kids had parasites. I looked up the symptoms of autism and realized I had quite a few of them. I immediately began the mms enema protocol which she recommends. I could not believe what then came out of me. I kept this up for a week and still there was no let up with the amount of parasites, biofilm, and who knows what coming out of me. After a week of this and seeing no let up on what was coming out of me, and having just done an mms enema I laid on my bedroom floor and the grief just poured out of me. My wife came in and lay down next to me and just held me. I knew then that something had changed, that my life and my marriage were now on a healing path. That the pain, the toxins and parasites were now leaving my body.

It has now been just over 3 months and there has been no let up on what has been coming out of me. If I were to have scooped it all up and put it in a jar I am sure it would fill a one gallon jar with hardly any water in it. I now feel I am at about a 9 with 20 in my sights. I thank God that this info came into my life and I took action on it. It has saved my life and my marriage. I love my wife, and cannot imagine not having her with me. And I love my life and am looking forward to not only getting *to the 20 mark but what is beyond the 20. What is possible when one's brain is at full capacity and not being inaundadated with toxins? Much love and appreciation goes out to Patrick Timpone at oneradionetwork.com, Kerri Rivera and her work with autistic kids (adults too Kerri), and to Andreas Kalcker. Thank you all for showing me and pointing to the keys I needed to free myself from what has been a nightmare.*

A big part of my healing has been reviewing my life and realizing that this has been going on for most of it and answers so many questions I have had. As a child growing up I had pain in my stomach and what the doctors eventually did was take out my appendix, which most of us know now is needed to keep the healthy flora in our intestines. And they told my parents that it was all in my head. So whenever I complained about stomach aches and pains was told that it was all in my head. School was a nightmare for me, as socially I felt I didn't fit in or belong, and a lot of easy concepts that most others got, I just couldn't get. I always had the feeling like I was missing something. I felt as though I was stupid or something just wasn't right with me. I now know there are many just like me. The words Autism, add, adhd, ocd, etc were not a reality back then. And I know those are just words or diagnosis of toxins and parasites. Get rid of the toxins and parasites and the diagnosis goes away. Easy peasy. Thank you all for listening to this chapter of my story. I look forward to many more chapters in my life story. Please feel free to pass this along to anyone who it may help. Much love.

—Bruce

When starting the protocol for my son's Autism, I decided to do it along with him.
I was suffering from Hypothyroidism, Adrenal Fatigue, a Hormonal Imbalance, and Severe Anemia. My cortisol was at a 3. One week into the protocol, my cortisol was at a 14, and my iron levels were normal without supplements. My thyroid medication dosage was decreased twice. My vitamin levels were all normal. My uterine fibroid cysts were completely gone after a few months on the protocol. I continue to see improvement in my health. This protocol has been a Godsend for my family.

—Maggie Kaye

CD has been life changing for my 18 year old son who has autism and Lyme, although his ATEC today is only a 3, down from a 68 at the start of cd, but I never thought it would be so instrumental in my dad's life also.

My dad, William, has a malignant melanoma in his eye and has received radiation for treatment for the last few years. I talk about cd all the time but they never took this treatment seriously, at least for anything besides autism until now. My dad gets terrible ear infections that he sometimes has to go to the hospital for. They tell him each time that he has "swimmers ear" and they give him abx, sometimes it seems to work, sometimes not, and he goes back to the drs or hospital for more abx....over and over. Recently he was leaving here for his 7-hour trip home, and he was very worried that he would not make it home with the painful infection that had begun, *and he would have to stop on the way and visit a strange hospital. So I mixed up some cd, and told him to drop a few drops of the cd mixture in his ear periodically on his way home. To his surprise, the infection cleared up by the time he got home and there was no need to even call a doctor.*

Of course, my secret plan is to get him on the cd protocol to finally deal with the tumor in his eye and that's the plan we have started. Whether he uses it and shrinks the tumor and saves his life with cd or not, he's a true believer now that cd cures infection.

I have been taking CD and the parasite protocol for 5 mo., and here are my observations. I have had long-term chronic sinus issues which has caused sever sleep problems. Also, a few months ago, I had a severe toothache in the upper left area. The dentist examined and found no fault with the tooth, even though there was severe swelling in the area. The infection originated from my sinus, and by taking my CD regularly hourly, was quickly solved. (My hourly CD doses were compromised by travel) I have also noticed improvement in my sinus condition, resulting in better sleep, although I have not fully recovered yet. Right now my sleep is somewhat interrupted by peetox. I will continue CD and PP for the 18 mo. Previously; I had used several naturopaths, with either negative results or limited results that disappeared when the medications were discontinued. So far I am happy with CD and would recommend it to people to try.

—Ed Canada.

A friend started eardrops with her 13-year-old pug 3 weeks ago. The pug Lucy was almost deaf from ear infection after ear infection, on constant drops, had seizures. After 3 weeks on CD eardrops, went to the vet, no ear infection, hearing is improving!! Winning!!



Since I was a child, I had been anemic and reading the book "Healing the symptoms known as autism" on the Parasite chapter, I saw that anemia is a sign of parasite infection. Since my son is taking CD I also took CD to know how my son feels and maybe cure my anemia. I had no problem going up to 24 drops in less than 2 weeks. I stopped taking my iron pill after 1 month of taking CD. I also did parasite protocol as I do not want to reinfection my son. Since, I stopped taking my iron pill I never had any dizzy spells and I feel great.

I used to wake up at night too to use the bathroom, now with CD no more night waking. In 2009, I was informed by my Doctor that I need to go and see a specialist as there was some suspicious stuff in my Pap Test and if not removed it *can lead to cervical cancer. I was booked in the hospital for the procedure. After taking CD reaching full dose, I had been discharging this horrible smell, like rotten egg, whenever I urinate. It took about a month before it stopped. Whatever that was, CD cleansed me and I think that discharge is related to my diagnosis on the pap test result. I am very grateful for CD for giving me my health back. I am still continuing taking CD as I want to be healthy and I will also try to complete the Parasite protocol for 12 months, I just finished my 5th PP and have been seeing lots of parasites mainly pinworm and ascaris. Now, I know the root cause of my anemia especially. I would encourage people to try the Protocol and see where the healing leads you. Thanks to Kerri Rivera, Jim Humble, Andreas Kalcker and people who used the CD before me as you gave me courage to use the CD.*

—G.M, Canada.

Two days before our first set of cd bottles arrived (we bought it to start Kerri's protocol with our autistic daughter), our son (6) got sick with scarlet fever. We didn´t give him antibiotics because we just finished our research on cd and were excited to use it instead. My sons face was swollen and red, he had a moderate fever and rash all over his body. After the first dose of 1 activated drop of cd within one hour his swollen red face subsided completely and in the evening the fever was gone. His rash got dry and after 3-4 days it was not visible anymore. Our physician told us that scarlet fever without antibiotics lasts up to three weeks. We were done within 4 days, without damaging his gut flora, as it would have using antibiotics. CD has taken care of many infections in our family since then and most important - brought our daughters ATEC down from 100 to 46 in nine months. I´m beyond grateful for its discovery.

For the past six years, my life has been plagued with anxiety/fear, depression, pressure in my chest, making it difficult to lay flat and sleep, bloating which caused me to look 7 months pregnant and which made my abdomen very tight and uncomfortable. Headaches, weight gain, sore joints, no energy, fibromyalgia pain, and dizziness causing me to feel drugged and off balance.

The anxiety and fear were debilitating literally making it impossible for me to sleep. I would go night after night not sleeping, just dead on my feet suffering with so much anxiety and very frightened wondering what in the world was wrong with me.

When Kerri's book, Healing The Symptoms Known As Autism came into our lives, I read it wanting to help or autistic son. I soon realized I had so many of the symptoms that I needed to do the protocol.

I started on the cd taking a very small amount, 2 drops every hour, about 12 doses per day, and worked up to between 60 and 90 drops a day, I also took cd baths and did enemas. I increased the cd every day by just a drop or two. Very soon I started to calm down significantly. I started sleeping! I started losing weight! For about 5 weeks I thought I had died and gone to heaven. In two months I lost 20 lbs.

But when my anxiety started coming back I set up a consultation with Kerri. I learned I needed to begin the parasite protocol to kill the parasites. The cd just killed the little ones.

With Kerri's help in several consultations I was able to tweak the protocol in her book and apply it to me for my personal needs. I started on low doses and increased it for what I needed to sleep.

As of today I have only been taking Mebendazole, the medication that kills parasites, for 3 and a half weeks. I sleep at night. Some nights are a little choppy but I get 4-5 hours of sleep. I am not depressed. My emotions are not all over the place. I am coping. I'm functioning without sever headaches, only mild ones. I still have bloating but not as severe. I feel like I will live and that I am not dying anymore. I hardly ever feel depressed.

To date I take 200mg Mebendazole at breakfast, lunch, dinner and bedtime, plus a 200mg implant right before I get into bed. The implant has been the turning point in my healing. (Consult with Kerri for directions regarding the implant.) I also take 2 neem tea capsules with each meal. Also, one dose of Combantrin everyday at lunch. I take castor oil as needed each day 1-2 Tablespoons to keep things moving, plus a cd bath at bedtime, 150 drops soaking for 20 minutes.

Trying to differentiate what is die-off and what are actual symptoms from the parasites is challenging. Pay close attention to how you feel after you do or take something. After an hour note how you feel. Worse, better? You have to listen to your body. Consult with Kerri often and keep her informed by email. You may have to tweak the protocol every few days so write everything down, day, time, how much, how you feel etc.

All of my symptoms are not gone 100% but they have greatly improved. The anxiety, which was the worst and most debilitating symptom, is the greatest improvement I have had. I know I will be able to heal completely and get my life back. I have just begun!! I have had so much progress in just a few short weeks that I still cannot believe it!! And...I have lost 2 more pounds!!

Thank you Kerri for all of your love, support and guidance!! I could not have attempted this without your knowledge and help!! You are an angel!!!! I AM HEALING!!!!!!

Your devoted friend, Marcie

My mother 84 yrs of age- who has dementia was very, very serious last week. Her lungs were filled with mucous and she could not spit it out. We thought this was the end and my sister invited the priest to bless her. The doctors suggested that I place her in a hospice, but I refused! They also offered antibiotics, but I bought some CDS and gave it to her every hour. I placed a humidifier with 40 drops of activated CD by her bedside day and night. And massaged different parts of her body with CD and DMSO. soaked her feet just once in CD as it is difficult. She cant sit straight. To everyone's surprise she made it through. Just a little bit more to clear up! Thank you everyone for sharing wonderful tips on loving and caring for our loved ones! This is a wonderful extended family! love the CD!!!!!!!!!!

* * *

I want to thank all of those who were kind enough to share their personal stories with us. There are many more, but you get the idea. I am so excited for you to read them, and I know that some of you will recognize yourselves here. It just goes to show that healing challenging illnesses is possible. We have a public Facebook group called *CD Health* where adults using the protocol for themselves can share questions, doubts and success stories. I highly recommend that you check it out if you are looking for support or some guidance getting started.

Appendix 1

More Miracles & Testimonials...

The only limits you have are the limits you believe.
~ Wayne Dyer

To date, 115 children have lost their diagnosis of autism by using CD and some or all of this Protocol. Autism IS curable!

This section is comprised of testimonials, miracles, and short blurbs on gains made by children using The Protocol. In many cases, these are candid emails from parents to Kerri sharing their joy at their child healing. These were gathered over the past 3 years, and have come from families all over the world. Some were translated by the parents of the child to English, and some were translated by my sister or I. We have done our best to honor these exactly how they came to us, unless a correction was needed for clarification, these were not edited. Many are anonymous for the protection of the families and their children. Names were used when permission was given. These families were generous enough to share their experiences with all of us to spread hope and joy, as well as to prove that children all over the world of all ages are healing from the symptoms know as autism. Please enjoy and share.

Please note that many of these testimonials were collected some time ago and therefore some contributors use the term MMS instead of CD. Due to time constraints it was impossible to request permission to change the acronym of MMS to CD in their testimonials. As we mentioned previously, MMS and CD are the same substance. Where the acronym MMS is used in the following testimonials please know that chlorine dioxide is the substance responsible for the healing.

We have added many new testimonials since the first edition came out. Those new testimonials are located at the end of chapter 2 and continue on the next page, followed by those appearing in the first edition.

(continued from Chapter 2, page 40)

45. *Things I wish I'd known before starting this protocol:*
    - * *My son would drop juice and pick up a water regimen immediately.*
    - * *My son would sleep through the night every night.*
    - * *My son would not be constipated again.*
    - * *My sons ATEC score would be halved in 7 weeks.*
    - * *My son's speech would be at age level.*
    - * *My son wouldn't need his daily rx med again.*
    - * *My son would be excited about and participate in his birthday celebration.*
    - * *My son would come into the bathroom and say, "I'm ready to wash my butt" unprompted.*
    - * *My son would drink ocean water.*
    - * *My son would get acclimated to school and would initiate conversation with his peers.*
    - * *My son's dark circles under his eyes would disappear. He would start to look and act like a healthy boy, and others would take notice.*
    - * *My son would be affectionate, tell me he loves me, crack jokes, and be connected to me like never before.*
    - * *The people who opposed our diet and protocol choices would be unable to deny that this works and we're on the right track.*
    - * *My marriage would be saved by rolling our sleeves up and tackling this together.*
    - * *I would find a way to heal my own ailments.*

    The future is bright

---

46. *My son with autism is 31 years old. Although he is fully verbal, he had a lot of issues: SIB, Aggression, he was not able to sleep. We have been trying different kinds of protocols since he was 3 years old. Unsuccessfully. I heard about Kerri Rivera and the CD Protocol last September. We started right away. We were continuously in touch with Kerri who kept giving us the faith, that even at that old age it is possible to heal and even recover. In September, when we stared CD he had an ATEC of 87, 4 months later we measured 63, and now, after 8 mounts, he has an ATEC of 28. There are some SIB's and aggression left, but it happens only rarely. If we could get rid of it, my son would be recovered. He became an interested young man, his memory improved. He keeps giving proper answers to my questions, something he never did before. I can see his real personality now: he became a nice, lovable, open-minded young man from a very sick raging, roaring, screaming, suffering boy. There are no words to say thank you to Kerri to show us the end of the tunnel. I think I'm on the best way to recover my 31-year-old son!*

    Mark, 31, Hungary

---

47. *Dear Kerri, I am very grateful to you for your benevolent service of helping to recover kids with Autism like myself. You have really improved the quality of lives of many hopeless kids. I really feel the difference now that my ATEC score is a*

1 and I am still making inroads in executive functioning and social skills. Without someone like you, we would have not known about CD and it would have taken several years to cure me solely with chelation. By that time, I would have been out of high school and probably in a community college taking rudimentary general education courses and would have had a bleak future ahead of me. But now, I am doing well in school and am taking college level courses. And I am not the only one in my family that has had benefitted from using CD. My brother used to have mild seizures in the form of head banging and most of that has now stopped. My father has used it because he contracted Lyme's disease twice. And my grandparents have used it to treat Alzheimer's, Diabetes, Blood pressure and Hepatitis C. So again, I cannot thank you enough for everything you have done that has not only changed my life forever but has made a profound difference in the lives of others afflicted with Autism.

---

48. My seventeen-year-old son was a healthy happy baby until he received vaccinations at age three. The day after the vaccinations he began having horrible anxiety problems. Day by day he lost skills and regressed. He developed problems with fine and gross motor skills, and social skills, memory and sensory integration. He also had multiple learning disorders and struggled in school. He spent all of his time in his room by himself and he did not make eye contact.

We tried many interventions to try and help him. Biomedical interventions, antibiotics, therapies homeopathy and Biofeedback all had limited benefits for my son. The only thing that helped him some was a gluten free, casein free, sugar free diet. While reading Healing the Symptoms Known as Autism we learned that most of the interventions we tried did not work because we were feeding the parasites that were causing my son's autism with vitamins and supplements.

While I was watching videos about Chlorine Dioxide I came across a video of Kerri Rivera talking about the protocol she uses with autistic children. As I watched the video everything began to make sense and I knew the protocol would help my son.

We bought Kerri's book Healing the Symptoms Known as Autism, gathered the supplies and my whole family started the protocol. To our amazement we saw improvements in my son overnight. We had taken the ATEC test for my son right before we started the protocol and it was a 43. In just one month of Kerri's protocol my son's ATEC dropped to a 5! We will continue with the protocol for the recommended time and we expect to see my son's ATEC drop to zero before we finish.

His social skills, motor skills, thinking, behavior, attention span and stimming have all improved immensely. His sleep patterns, digestion, physical appearance and weight have also improved tremendously.

Kerri Rivera's book gave us the tools we needed to reach in and pull my son away from the grip that autism had on him. We will forever be grateful to Kerri. She devotes her life to helping children with autism and always has an open line of communication for anyone who needs help. She is the voice for so many children that don't have a voice. Thank you from the bottom of my heart!

---

49. FUA!!!! BIG moment... crazy morning, ughhh we miss the Bus I was so mad because my other daughter had preschool at 9:30 so my morning was a mess, I had to leave in Pj's and make them eat breakfast in the car....but then in our way to school my son saw a School Bus passing by our side and said "school Bus is gone, L is sad" OMG OMG OMG......did he just said this 30 words sentence?????

(actually 7 words but seems like 30 to me!!!) Ok...WAIT then I get to school not mad anymore, I walked with him still in shock, I couldn't believe what I just heard....and when he saw the line of kids by the wall he point at them and said "my friends" OMG OMG OMG....ok WAIT....then we get there and he takes the teacher hands, gives me a kiss and said "bye mommy" OMG OMG OMG .... WAIT then the teacher ask him L, remember back pack by the wall, so he goes to the wall with his back pack in his back and does exactly what he was ask to do!!!! O M G

FUA...THAT'S RIGHT.... 223 days in this Protocol, searching poop, dosing, enemas, writing in his food diary every little thing he eats, therapies ABA, speech, occupational, hours hours of work, hard work...all just to witness this miracle of healing...to see him think, react, analyze a situation, be happy, spontaneous and smart by himself (no prompt or reinforcer necessary)....THANK YOU Kerri Rivera since the first day I found you in YouTube I have never stopped believing....I LOVE YOU WITH ALL MY HEART!!!! YES COMADREEEEE!!!!! I can feel it...we are close...it's happening.... so happy I missed the Bus this morning... this is the best day in my son's way to recovery so far!!!!!

HOPE FOR ALL!!!!

---

50. My son is 23 and we have tried many, many approaches to heal him over the years. Typically we would see some initial progress, but then the rate would slow down and he would plateau again, slipping further and further behind. Lyme disease and co-infections, as well as various viral, fungal and metabolic issues complicated everything. We had to resort to psych meds, even, for his depression, anxiety and mood disregulation.

We started Kerri's protocol in the summer of 2012, and had to cut the number of drops again and again to something he could tolerate, since he has MTHFR genetic issues with detoxing, until he was at 1/64th of a drop per dose. By October 2012, he was at full dose and after two weeks, began to talk about learning to drive, to offer to do a chore at home, to draw again. So it has been about a year for us, and the improvements are continuing, his ATEC score went from 77 pre-meds to 11 now, and our lives are all much better thanks to this book and Kerri's dedication to the cause of healing the children. Please, if you are reading this, don't be afraid to try one more thing!

---

*51. My son started Kerri's protocol 10 months ago. At the time we started the protocol he was doing a home based therapy program for 60 hours a week. We did not send him to school because he was not able to handle all of the outside stimulus, unable to follow directions, and unable to communicate effectively. He stimmed most of his day and only spoke in 2-3 word sentences to get needs met only. When he started the protocol his ATEC was 57. It quickly dropped and the improvements were mind blowing. In 5 months time his ATEC was a 9. Today at 10 months after starting the protocol his ATEC is a FIVE!!!! He now attends school with out any kind of extra support and exceptions made for him. He is truly just one of the other children. I have been volunteering in his school and I have had 5 different office people tell me that he stops and greets them on his way to different specials (p.e, library, art, gardening). They told me he initiates the greetings and says: hello, good morning, buenas noches, and all with a big smile on his face. I have even been told by 2 of them that he greets them by name. Did I mention that he leaves the classroom on his own to go to specials??? Yep, my one time *severely autistic* child finds his name and places it in that specials category* *basket, leaves the classroom and goes to specials on his own???? When he is done with specials he goes back to his classroom and does his work. Holy CRaP!!!! A dream come true.*

Thank You Kerri!!

---

52. *My 6 year old son's ATEC went from 45 to 22!!! Wow I knew he was doing better but more then half!!*

    Thanks Kerri Rivera!!

---

53. *I don't know what to chalk it up to--we just finished our 3rd PP and did our 2nd shot of GcMAF on Saturday--but my 9 y/o son has started taking pictures with my iPhone. They are not just random shots; he is finding objects or angles and taking pictures. They are FASCINATING! He has also figured out how to use the reverse feature, and has taken a series of self-portraits, which he flips through and says to himself "Who's that?"*

---

54. *My 16-year-old son is doing great on your CD protocol. ATEC down from 89 to 37. Best thing that ever happened after doing 8 years biomed with him.*

---

55. *We started CD with my precious 5 year old 'O-ster' in June 2013. Some of the completely new developments we have seen since we started....... He is aware of how to burp and toot, and thinks it is funny. He is apologizing for things he does wrong. Even a day later, he will remember and apologize. He goes to the bathroom on his own. He is completely pottytrained, even at night. He does household chores happily. He sent people on my contact list emails that said 'I love my mommy.' He has better problem-solving, more motivation to draw pictures. If he gets messy, he just goes to the bathroom and washes his hands and wipes off his shirt by himself without saying anything. He dresses himself. He does somersaults (just a few months ago, it was impossible for him to even get in somersault position), can open baby gates, can get in crab walk position, can jump off of furniture with both feet. He greets us when we come home and is excited to see us. He MISSES us when we are gone and talks about it during the day. He's making up 4 line rhymes. He cares what he wears and picks out his clothes! He is not running back and forth as much. We have normal trips to restaurants. I can leave our front door open now, and not worry that he will run away. He tries to help put our dog in his crate and fetches with him. He wants to come with me if I leave the house to go somewhere. He will now eat almost anything I put on his plate. He used to vomit at the mere thought of things like GF pasta or rice, and he wouldn't allow any food on his plate to touch another type of food on his plate. He will now eat bowls full of tomato sauce, onions, burger, rice, garlic and peppers all mixed together. Our family can eat dinner together now. I no longer have to make separate meals. He even eats raw peppers! He yells 'watch me!' and does things like diving onto the bed or jumping off of something. He looks at cloud formations to see what pictures he sees in them. Last week he heard a toddler crying in Target. He wondered why the child was crying and wanted to go find her. He misses his little sister when she is not at home. He wants her to play with us when we are playing. He is completely aware of what is going on now. He is much more aware of danger. He notices the weather. There is a sense of calmness about him that he did not have before. His tantrums are much less severe and much less frequent. I was supposed to be his aide this year in preschool, but I have been able to just drop him off at school. There are many more new things that he is saying and thinking and doing.*

Our quick biomed history- He regressed after vaccines at 12 months. Starting at 18 months of age, he was gfcfsf for 1 year, then scd for almost 3 years. It feels like we have tried everything with supplements over the last 4 years. Some things helped a little, but nothing really tackled his pathogen load, even though he was on an awesome diet. His ATEC was 66 in Dec 2010. Low dose chelation brought it down to 33 in 3 months. The ATEC stayed at 33 for 2.5 years. We did 112 rounds/weekends of low dose chelation during that time. ATEC June 2013 was 34 (before starting CD), July 2013 was 30, October 2013 was 20! We are on our way down. This is the first time that I have physical proof that we are getting rid of the pathogens that have controlled and poisoned his body and brain for most of his life. It feels so good to finally help him. I am hoping to write our complete recovery story in Kerri's next book. I thank God that we saw Kerri at AutismOne.

56. *Nick texted me yesterday for the first time, on his own. "Hi from Nick" - that's a 2013 FUA fo sho. – Alison*

    (this text was accompanied by an ATEC drop from 69 at 6 years old to 14 at 8.5 years)

57. *Yesterday my son told me I worried too much, I said you worry too much Too Noah! He responded, my hair is red, yours is gray, so who is the worrier, hahaaa! The windshield wipers keep wiping away the autism, what's staying around it seems, is completely lucid speech and unbelievable comebacks! He never could say things like that before, not at all, he really was in there somewhere.*

58. *Something really beautiful is going on in our household right now...Caleb is totally blossoming socially on every level. There is a calmness in his body. He is alert, responding to his name, sharing his toys with other kids, wanting to give affection without prompting, soothing Lilia when she is crying rather than batting at her. We even have gotten a few spontaneous silly phrases!!!! Oh baby, oh baby, oh baby!!! We are on our way!!!!!*

59. *We started the diet on the 1th of March, CD on the following week. Adam started to ask questions in April. Since then he keeps asking continuously…His ATEC dropped down from 49 to 38.*

    Tunde, Hungary

60. *OMG OMG OMG!!!!! My son is singing!!! He was ZERO verbal... I mean ZERO!! His shadow teacher told me a week ago that he started to mimic, I said to myself "yeah he was babbling and she thought he is mimicking!..." Yesterday she told me he started to sing and I said to myself, "Yeah right, she is absolutely illusionist or exaggerating!!!" She knew I will not believe her because he is just humming at home! So she sent me a video which was a shock for us. He is singing the song "A is for apple, a a apple... B is for ball, b b ball... C is for cat, c c cat... D is for dog, d d dog..." I don't have enough words to thank you and thank Kerri Rivera and this incredible protocol!!! Thank you for saving my child. xoxo*

61. *...My son is doing his first CD PP. We picked him up from preschool he was extremely happy. Hugs & kisses. Then...runs up to a classmate and touches his shoulder and says, "bye Johnny", runs to another classmate and says, "bye Kevin." Then he skips to the car. These improvements in his socialization is new. We are so pleased and I wanted to pass along these social gains with you all. His atec at start is 58.*

62. *My little sweetpea is almost 4...and completely NON VERBAL...upon picking her up from therapy today, her teacher said she was having a great last few days... and both therapists said her eye-contact has been different...like in a really good way!!! I've also noticed her looking at me...straight into my eyes for what seems like forever...almost as if she has never seen me before?! They also said that she has been looking at them and has been opening her mouth trying to make sounds...as if she wants to say something very badly...but can't...but with a lot of prompting...she did say "Hi!"...all I know is that somewhere in there is this amazing person waiting to be let out! I often worry if we are ever gonna make it...finances and healing your family can be very overwhelming...especially on one income. But for the love of my daughter we just cannot give up...feeling very hopeful and blessed today...and very grateful that something is finally working.*

---

63. *Hi Kerri,*

I wanted to write and thank you for discovering and sharing your protocol. This protocol has saved my almost 5-year-old son.

My son suddenly started having absence seizures that would freeze his breath. From the day he had his first noticeable seizure, he was hospitalized every seven weeks for uncontrollable status epilepticas, a life threatening condition. They would pump him with seizure meds, Ativan, and Valium for hours before the seizures would finally stop.

Since starting CD five months ago my son has not been hospitalized once. He went ten weeks seizure free. He had a few mild seizures that he brought himself out of without any extra medications. He currently broke this record and has made it another thirteen and a half weeks seizure free. I true miracle.

Everything we searched for to treat his Lyme disease in the past would either cause seizures or not help to prevent them and I now know why. As you predicted after starting your protocols we discovered that he not only has Lyme, he is also incredibly loaded with parasites. So much so, that it scares me to think of what may have happened to him if we didn't find you.

I'm so amazed to watch him subtly emerge. Since we started, he went from saying about 20 words to saying 69 words, along with two and three word combinations, and over the past month he has begun to answer simple questions. His vestibular system has gotten much better; he'll actually swing. He just started jumping off curbs. His eye contact is perfect. He's gained two pounds in the past three months, something he hasn't' done since being diagnosed with failure to thrive at a year old. He is playing with his three year old sister; it's so adorable to watch them chase each other around the house, hug, chase each other, hug, get in the dog crate together, hug, take turns pushing each other in their wagon, and kick the ball back and forth. Last night the three of us played catch together for over 10 minutes. I'm so happy for her to have her brother to play with.

This protocol changed his life, my life, and our family's life.

There are no words to thank you enough for all your help along the way – he's on his way…

Love, Love, Love

Update: as of December 3rd, 2013 this little guy is 18 weeks seizure free!

64. *My name is Dawn. Below is a shortened version of what we've been through prior to and since Kerri Rivera coming into our lives and changing our family forever.*

I am Noah and Eli's mom, caregiver, advocate etc., that's been my job for 17 years. Prior to having children with special needs I had a career that I loved and my plan was to continue my career, how deluded I was, my life has been forever changed by my children and their symptoms as my entire existence over these years has been to save my son.

My son Noah born August 19, 1996 has struggled and suffered with what is now known as the symptoms of autism. His symptoms began at 8 months of age with a rare blood disorder known as neutropenia, he had a low white blood count. As he continues to improve, I too, along with our entire family seem to be healing as we bore witness to his daily struggles of self injurious behaviors, aggressions and rages, learning disabilities, speech and auditory delays, 2 steps forward and 4 steps back.

Healing the symptoms know as autism with the Chlorine Dioxide and Kalcker Protocol have been a cathartic exercise for me as well, no amount of therapy would have soothed my soul like witnessing my son's return from the daily brink of death.

My hopes and dreams for my son dashed with vaccines before he was old enough to speak. I'm 50 this year, however I'm older then those years, and my views and outlook on life have changed forever. Imagine fighting for my son's life against those trusted factions of our society supposedly put in place to protect us, i.e., government agencies, churches, schools, teachers, principles, school boards, doctors, hospitals. I'm changed forever by the daily battles, but somehow they are small now in comparison to the beast of the symptoms that ravaged my boy with red hair, often referred to by me as my favorite Martian. As he continues on his healing path, so do those of us who have loved him so dearly, despite his outwardly awkwardness, he is the innocent victim left to suffer for what is often referred to as the "greater good", he's responsible for so much more in my life then just the symptoms known as autism.

It was a Saturday morning in May of 2003. Noah, at the time 6 yrs. old, had slept with us because of seizures on and off through the night. Like so many times before, I was very concerned he would go 'status epileptus', a state of continuous seizures. He ate cantaloupe for breakfast that day. I remember it vividly even 11 years later. His seizures would come about every 20-25 days. First he would complain of a stomach ache, and I could hear the gurgle of his stomach. They usually lasted a few minutes and then went away. This day, the Saturday before Mother's Day, he didn't come out of the seizure. We administered his anti-seizure medication but it didn't work. We called 911, the fourth such call in Noah's brief life. When EMS arrived, Eli, then 3 years old, ran to his bedroom upstairs. I remember the technicians working on stabilizing Noah. They ripped the shirt from his body as they worked on him and carried him out to the ambulance. As I followed them to the ambulance I happened to look back to see Eli watching from his upstairs window as they placed his brother in the ambulance. He stood motionless. Darryn scooped him up and followed us as we drove swiftly through traffic to Texas Children's emergency room, about 25 miles away. I remembered thinking, why don't people heed the right of way? I looked back as they worked on Noah. His seizures continued until we arrived at the hospital. Once we arrived he was taken straight to the ER, ICU room, where *four doctors began to work on him. Darryn and Eli arrived as I stood next to the bed while the doctors worked to save his life. I took Eli out of the room and we sat in a chair looking in at what was happening. His eyes were as big as I have ever seen them and he sat perfectly silent in my lap, we colored. I overheard the doctors explain to my husband that they were having problems stopping the seizure. They wanted permission to use a drug that could stop his heart. Darryn asked if there were any other options. The doctor shook his head. He asked what they would do if the heart stopped. The paddles. So he was given the drug. No heart stoppage. His breathing became shallow and the seizures finally stopped after 6-7 straight hours. A couple of hours later Noah woke up in his hospital bed, connected to monitors and the like, in a drugged stupor. By this time my parents had arrived (like so many times before) and had taken Eli home. Darryn stood next to Noah's bed rubbing his chin nervously. Noah asked if he could use the restroom. Darryn said yes, and in the next second Noah leapt from the bed, almost a perfect swan dive, toward the floor. Luckily, Darryn was there to catch him. Noah's life was saved twice in the same day. After the drugs wore off, he was released from the hospital. Noah missed a week of school while he learned to walk again.*

I never knew the impact this had on Eli until Father's Day that same year. About a month after the seizure we planned to attend with some friends one of those workshops at Home Depot where the kids make a gift for Dad. He was excited to do the workshop. As we approached the store we noticed the local fire station had an area of the parking lot roped off for tours of ambulances and fire trucks. Eli became frightened and started crying, and began backing up, finally screaming and contorting. This from a child that hadn't given us a peep of trouble before. I had to leave our friends standing in the parking lot as my second son became inconsolable. At the time it hadn't occurred to me that he remembered the incident with his brother just a month prior. He too suffered, and sadly he was 3 years old at the time, unbeknownst to me, Eli has probably remembered more then I realize even today.

Noah had his first seizure in March 1998 at 18 months of age, shortly after a round of vaccines. (His doctors continually assured us that vaccines had nothing to do with Noah's problems, but I know otherwise.) Seizures were not Noah's only problem, however. He was diagnosed with neutropenia (the lack of neutrophils or a type of white blood cells) in 1997. He has suffered from acid reflux for as long as we can remember. He was hospitalized for 4 days at 4 years old for a roto-virus infection, something most children get through at home in a couple days. He had a cyst removed from his thyroid. His tonsils were removed due to frequent infections. In 2005, he was diagnosed with Lyme disease. In 2008 his pediatrician discovered his blood was missing carnitine, a key component for the body's metabolism. We took him to a specialist who diagnosed him with mitochondrial disease. His seizures stopped after we started giving him medication for the carnitine deficiency. But his behavioral symptoms continued and even worsened which always indicated a deeper underlying illness plaguing Noah. But what?

Early in 2013 Noah began to show some psychiatric symptoms that frightened us to the point we had to consider putting him in a home. He had frequent panic attacks (all day, minute to minute), tics, and sudden bursts of outrage over insignificant things. He often didn't make sense while speaking, and secluded himself in his bedroom. He fantasized uncontrollably about his videos, and spoke over and over about what we were going to do about the characters (not what *we would do if we were in the stories). He had repeated events of unrealistic fears. We took him to see an energy medicine specialist. The energy medicine protocol involved various supplements and dietary changes, as well as electrical pulses to adjust his body voltage (an approach similar to acupuncture). During one of our visits we learned of MMS, which this doctor indicated could be used in small doses to treat colds. Symptoms improved, but very little. But then they worsened again dramatically. We took him to his pediatrician who diagnosed PANDAS, and prescribed antibiotics. This helped but only temporarily. His psychiatrist prescribed anti-anxiety medications, with only marginal results. He was unable to attend school through all of this, and needed someone by his side constantly. His pediatrician prescribed Albenza thinking parasites may be involved (despite a negative stool test). This improved his behaviors some but only marginally. There was also the side effect of hair loss. Noah became completely bald, like a cancer patient.*

To see your son regress into psychotic behavior is something no human can ever imagine. Facing people everyday as they watched Noah regress and comment, it was a slow slip and then suddenly he was in a dive toward insanity. I felt he was slipping away. I scoured the Internet for answers. I had heard of Kerri Rivera but thought antibiotics were the only treatment for my son, like the vaccines, I had been told by doctors that the only treatment for Lyme was antibiotics. I emailed her and she answered immediately to "start the protocol." We began the CD protocol in June 2013. The protocol takes complete dedication, it requires steadfast commitment, and it's the best gift I have ever given Noah. I have learned so much about illness and it's roots through treating my son with the protocol.

Noah's behavioral symptoms started to improve immediately. He had fewer and fewer tics and outbursts. He was noticeably calmer. He now answers the phone, takes messages, and helps me scan food items at the grocery store. He even got behind the wheel of our car for a practice drive in the school parking lot. He asks a lot of questions. So much has improved in such a brief time. Prior to the CD protocol I scored Noah as a 38 on the ATEC test. Since then, he has improved to an 8. Darryn (Noah's Dad) scored Noah a 55 before we started, and two months after beginning it was a 22. It's amazing that a few brief months ago we were considering having him put him into an institution. Although we try not to think too far in advance, now we can hope our son can someday lead the normal life he was meant to.

I can't help one final story about Noah. Yesterday he asked me what autism was. We've never explained to him that he has it, because he would not have been able to understand it even if we tried. While I searched for an answer, he said "you know, Mom, Sponge Bob couldn't get his boating license because of his autism." I belted out a loud laugh and said "Ok. Noah, you know you have a little bit of autism too." And he said "Yes Mom, I know that," and smiled.

While he still has much to make up, years of life to regain, experiences to live, we're so pleased and grateful to Kerri and the others responsible for these protocols for these improvements, his life is being restored. I would encourage anyone to follow the protocols as closely as possible and do not delay. It is so fitting that the only opportunity I've ever been given to tell a little of what my family has been through would be afforded to me by the very person that actually saved my son…she gains nothing from what she has done for us, except the knowledge that she saved a boy's life that she has yet to meet, by saving my son, she has saved my family.

65. *Shay is doing so well it's surreal. In the past week the balance has shifted so that he is now recovered more of the time than not. He is having a 2-4 hour block every day or two where he is back in his old state (weeping, raging, zero-to-flipout, shrieking, obstinate, defiant, OCD, mean, potty-mouthed, etc.). The rest of the time he is lucid, has perfect mental clarity, is as funny as can be, does his math quickly, has perfect handwriting, gets along with his sister, is generous, expresses himself clearly, plays well, understands how others feel, etc. It is a mind blower Kerri.*

Although Shay doesn't have the awareness to know when he is in the autistic state, he is now clearly aware when he is in the recovered state. He comes up to me and says quietly, "Mom, it's gone again. Do you think it will come back?" I tell him yes, that it will be like this for a while, coming and going, until one day it will be gone and it won't come back. Shay and I have been discussing which "number" he is going to be in the line of children that recover. :) He is also planning a big "Goodbye Autism" party for himself.

Bella is getting over her meltdowns much more quickly. Sometimes I say "no" to something and then flinch, waiting for the screaming, but it's small, or sometimes she cries and gets over it within minutes. This is a big improvement for her. In her own words, she has noticed that she feels less anxious.

---

66. *We started the protocol 9 months ago. My son had 2, 3 horrible days every month. He wouldn't stop crying all day long, and he could not get any sleep at night. After talking to Kerri, we realized that these terrible days were always the days of the full moon. We saw improvement straight after the first PP. After 6 months, all of the bad behaviors were gone. I realized that the PP helped my child to improve month by month.*

And to prove that it is not only me who can see the changes, my son's therapist from school told me the other day: "Well, when is full moon again? So that you would start the Mebendazol? I love when he gets it, he is doing so well with it".

Staring atec in February was 50, now his atec is 34. Thank you so much, Kerri!

Betti, Hungary

---

67. *We are celebrating 3 months on CD and 2 PP's done! Our little angel has (or I should say had) extreme ADHD...we are not seeing much of that anymore. Our life altering issue is her lungs. This child has undergone over 35 surgeries in 8 years. 17 of those to surgically remove mucous from her lungs. She is hospitalized every 6 weeks with pneumonia. We have O2 in our home. She even had a port placed for IV meds at home. Our life has revolved around illness. In 8 years the docs have done every test in the book to figure out the cause. We've turned up nothing. In July, we flew to NYC to see a medical mystery doctor. He told us it's all nutritional and had us do some parasite testing. The testing turned up zilch, but thanks to Jean Marie, we ended up here. Long story short, we are making huge strides. We are not there yet, but to give you an idea, normally her pneumonias take 4 months to clear, this time it was only one month! She's only needed one antibiotic in 3 months, normally it's 8 antibiotics in 3 months. She's doing better in school too, which is just a bonus. Today she came home and told me she was able to run in gym, something she hasn't done for years! Thank you Kerri Rivera and Jean Marie and all the mods for welcoming us to this group and for helping us to take back this child's life. Bless it! Bless all of you!*

68. *30 days of gratitude, Day 4...I am thankful for an evening alone with my son. It's rare that we have time together alone. He jumped on the bed and danced around while I packed for my trip in the morning, talking and singing the whole time. The dinner table was lonely by ourselves so we decided to eat in front of the fire. I said, "This is fun, isn't it?" and he said, "I love this and I love you, Mom" Moments like this were non-existent before our journey brought us to Kerri Rivera who is an angel on earth. She gave us the direction we needed to heal our son.*

---

69. *I observed my kiddos at school today. Get this........my once severely autistic 6 year old choose and received a Spanish lesson that lasted 27.5 minutes (I timed it). The whole lesson he was sitting on his bottom, following instructions, answer questions correctly (in Spanish), smiling, great eye contact, and really enjoying his time with the Spanish teacher. FUA to the max! This time last year Henry was speaking in 1-2 word sentences to get needs met. Now he is talking in complete sentences in English and Spanish!!!!!!!*

---

70. *In the past, if I gave Nate a hug and told him I loved him, he would sort of hug me back, awkwardly jutting his backside out (to reduce physical contact) and patting me on the back and saying, "I love you, too." He would then escape as soon as possible.*

    After a few days of being on 7 drops (last week) Nate approached me with full eye contact, threw his arms around me, gave me a prolonged bear hug and spontaneously said, "I love you, Mom". I hugged him back and we stood there, just enjoying the moment, while I quietly balled my eyes out.

    Thirteen years. I had waited 13 years for that moment.

    And now he has been doing it almost every day since that first hug.

    This alone is the world.

---

71. *There's a lot of people jumping on the "Thankfulness Train" this time of year. Here's my contribution. There's only one major thing I can think of this year that I am thankful for. Of course, there's so much to be thankful for, but one thing that really stands out. That would be this protocol. God led us to see Kerri Rivera at Autism One this year. I only went because it was basically the one thing I didn't know much about. The day before Kerri presented, I saw my friend Laura at Karaoke Night (so fun by the way!). She told me she was doing CD and I'm pretty sure I looked at her like she was crazy! Saw Kerri the next day and I was hooked. We started the protocol June 3rd. Laura got me in this group. Thank you Laura, for your patience with me and for letting me know about this group! Thank you, Debbie who has talked to me many times about the protocol, about my son's aggression, reassuring me that things will get better and they have! Much, much better. We still have further to go, but there is light at the end of the tunnel. My four kids and myself are doing the protocol. We all have Lyme. We are all feeling so much better. We are no longer spending thousands of dollars a month on empty treatments. We are getting our lives back; our finances under control, and my son with autism went from an ATEC of 47 to 20 in four months. Thank you and love you all. And to Kerri Rivera, there are no words. Thanks and love isn't enough. You can be assured of my prayers for you, Patrick and your family for life. That's the least I can do for all you have done for all of us.*

---

72. *Small progress this week! My son had his ABA therapy yesterday and at the end the therapist gives him a "high five" before he leaves. The therapist asked my 3-year-old normally non-verbal son for a "high five". My son looked at him, gave him a high five and said "HIGH FIVE!" plain as day. My husband almost fell over sideways in shock! He also put his toys away without being asked to, and that too is a big change. CD is the best!"*

---

73. *We have been on the protocol since Aug 30th of this year. We've done one PP. My DS is 8 with severe apraxia and autistic.*

    ATEC: 4/2013: 62 starting some biomed

    ATEC: 8/15/2013: 51 before CD

    ATEC: 10/6/13: 24

    Some WOW moments for us so far:

    - *Playing soccer with other kids at school three weeks after the start of the protocol. *Really "on" in conversations...adding information when we didn't think he was listening because he was playing on his iPad.*
    - *Talking about other things in his day besides Minecraft or Plants Vs Zombies.*
    - *Going from a battle with homework that would last over three hours to picking him up at daycare with his homework already finished. And correct. That he did on his own.*
    - *His ST saying he is able to follow three step directions better and was able to talk/ask Who and What questions for nearly the entire hour...I actually had to tell the ST what we are doing because it was obvious to her it was more than just diet.*

    He's just happier. We're all just happier.

---

74. *We came back from our Intensive in December of last year on a high. After a week with the Son-Rise® team, Jordan was saying 20 different words; he was more confident, and more mature. He had such an amazing time learning and growing. Every morning he would take his facilitator by the hand and walk him/her into the playroom. He really grew up that week. I loved watching him grow through love and laughter. What an amazing, wonderful thing to witness.*

    We, also, learned at our IAHP appointment that Jordan was reading at about a third grade level. What a trip! The evaluator held up a paragraph for Jordan to read. It was so fast I didn't even have time to read it. Then, she held up a question for him to read, then, a sheet with the answers. She, then, asked him to point to the answer and he did. He was three for three. My son taught himself to read. What?! We were, also, very surprised to find out that between running our Son-Rise® program and incorporating exercises from IAHP, Jordan improved 433% from September to December. WOW!

    Between the two experiences on the east coast, I felt like I didn't know my own son. I always believed he can accomplish anything and yet I had tremendously underestimated his ability. I was so excited to get home and start his program. I knew that if we focused and put everything into his therapy for two years, he would be ready to go to mainstream kindergarten.

    I was so excited; I was beyond hopeful; I believed he was on his road to healing.

    On Christmas Eve, Jordan was crouching down and just froze there. I called his *name, no response. I ran over to him and noticed his lips were turning blue. Immediately, I tipped him over, hit him on the back and did a swipe in his mouth to get out what he was choking on. There was nothing there, but he gasped for air and began breathing again. Did he just have a seizure?*

January 15 has become a day I will never forget. We woke up to Jordan throwing up and he didn't want to get out of bed. He just wanted to sleep; he must have caught the flu and needed to sleep it off? Finally, around 10am he got up and ran around the house like nothing was wrong so we began therapy. While I was in the playroom with him we were jumping on the trampoline and he suddenly stopped and looked at me with a panicked look on his face and reached out for me. Clearly, jumping was too active for his upset stomach so I brought him to the family room with Kaiyan and my helper.

Suddenly, he looked off and froze again. He then threw up again and passed out. Oh shit, he just had a seizure, and another one, and another one, and another one. All the while staying unconscious. I brought him to the ER where he slept and had another mild seizure. While he was passed out they gave him a CT head scan to make sure there wasn't a bleed or something in his brain. Everything was fine.

Shortly after, he woke up. He was playing, running around the ER as if nothing had happened. He went through what little water I had brought and was asking for food and water. A good sign, I thought. The ER wouldn't allow him to eat or drink anything "just in case". Anyone who knows anything about seizures knows that no food and drink could very well cause a seizure…and it did.

This time the ER Doctor went into full-blown panic mode, probably because she saw what happened. They began trying to get blood out of him. On a good day this is almost impossible. Now, they are trying on a kid that didn't have any fluids in his system to help expand the veins.

And so it went, needle poke, dig around in the arm searching for a vein, Jordan would hold his breath from the pain and have a seizure. Seizures are typically the brains way of trying to get oxygen; the pinpricking was inadvertently inducing seizures because of the breath holding. This went on for two hours: needle poke, dig, hold his breath, seizure. They poked him 27 times: in his neck, head, ankles, thigh, anywhere they could think of.

This of course wasn't enough. They insisted on doing a spinal tap to check for meningitis, which we had been declining all day. Now they are telling us that the way he had been seizing for the past two hours is classic for meningitis and not doing it could be fatal. They crunched him in the tightest ball they possibly could and held him so tight he couldn't move…or breath. After the fifth poke, I began to get faint and had to sit down. They didn't know what they were doing. When I sat down I could really see how they were holding him and asked if he was breathing. The nurse looked down and said, "he's blue, get the oxygen" and they put oxygen near his face.

I immediately thought, "they're killing him. They don't know what they're doing." That's when I reached out to every FB group I'm on and asked for prayers. That was the only thing that was going to save him.

When they, finally, let him go he had the worst seizure he's had to date. He was actually convulsing. As they went for blood the 28th time, I told the nurse that's enough. This has gone on far too long. She agreed, ran and got the Dr., they wheeled him into to the CPR room, and called for a crash cart. I think I said, "what the fuck?" She said it's "just in case".

They proceeded to get a drill and drill a hole through his shin and into his shinbone so they could put in an IO (IV into the bone). They pumped him full of all kinds of drugs and, at long last, drew blood.

He looked up at me with a longing in his eyes and reached out for me. I went over and put my hand on his chest and he passed out. He was transferred by ambulance to our local children's hospital; we were allowed to follow the ambulance, but couldn't ride with him. He remained unconscious until he arrived into his private room at the hospital.

The first thing he did when he woke up was reach out for my hand and give me a kiss. My little boy!

The blood they had finally taken revealed low electrolytes and bicarbonate at a life-threatening low level. Screaming and crying can drop bicarbonate, which he did for two hours in the ER; lack of food and drink can drop bicarbonate levels, which he wasn't allowed to have in the ER. Low bicarbonate levels can cause seizures. What a recipe for disaster!

The hospital ran every test they could think of and no reason was found for the low bicarbonate or the seizures. We came home after five days, followed by several follow up appointments over the next two weeks. Everything seemed to check out fine until I brought his labs to his DAN (Defeat Autism Now) Dr., she looked at the blood test, pointed to something and said, "Lyme, every time I see this in one of my kids, it's Lyme."

We had the (one of many) $800 test at the best lab in hopes we wouldn't get a false negative, which is very common with Lyme. Jordan came back positive! Now we had something to go on. I was excited to finally have an answer to what was going on with my little boy. Lyme is known for seizures and abnormal electrolyte levels.

We scheduled an appointment with a Lyme Literate Medical Doctor (LLMD) and were ready to start healing our guy. Two days before the appointment, we woke up to Jordan vomiting. He didn't want to get out of bed. He finally did and ran around like nothing was wrong and then he had another seizure. We were told to take him for blood tests immediately the next time he had a seizure. We took him to his DAN Dr. an hour away, but knew they would be able to get his blood without difficulty. We went to lunch, came home, he had a seizure, turned blue, threw up, passed out, had a seizure, turned blue, threw up, passed out, had a seizure, turned blue, threw up, passed out. His DAN Dr. just happened to call to check on him in the middle of this and told us to get him to the hospital before he had a heart attack. We went to the ER...

And so the story goes every seven weeks TO THE DAY, seizure, turn blue, vomit, pass out, seizure, turn blue, vomit, pass out, admitted to the hospital where he was pumped full of drugs for hours to try and stop the seizures, and they ran the same tests over and over again. The hospital didn't think he had Lyme even with a positive test and thought that seizures every seven weeks to the day was a coincidence, although, they could still not offer any explanation.

We tried treating him with ABX that the LLMD prescribed. One teaspoon and he had a seizure, turned blue, threw up, passed out, had a seizure, turned blue, threw up, and passed out. This time the Valium I administered did stop the seizure cycle, most likely because it was induced from the ABX and not part of his regular seven week seizure cycle. He had multiple mild seizures every day for two weeks from that one-teaspoon.

Clearly, ABX were not going to work. I emailed with a woman who coauthored the book, "The Lyme Autism Connection" and tried the homeopath that she used down in San Diego. This was definitely working with detoxing, but it wasn't helping with the seizures. He went from seven weeks to the day to three weeks to the day. This treatment was working on opening Jordan's detox pathways so his body could rid itself of the Lyme. I liked the idea of treating this way, but the process could take four years. I didn't want Jordan having what the neurologist told us were life-threatening seizures for four years. I was desperate to find something to help him.

We knew what was wrong, but needed something safe to treat him. Nothing was covered by insurance and we were running out of money. I had lost hope. Every treatment seemed to make him worse and I couldn't bear to see my boy suffer the way he had been for the past six months. I didn't know what to do.

I, literally, got on my knees and prayed for help every night. In the same week, a woman who attended the same Son-Rise® start-up emailed me about a newly discovered treatment she was doing. I had signed up for a Lyme conference that mentioned the same treatment, and I had signed up for an autism telesummit that unbeknownst to me had Kerri Rivera as one of the speakers. (Kerri is the woman who discovered this treatment for autistic kids.) I emailed back and forth with Kerri, I posted on the FB group, trying to get all my questions answered. I was terrified to treat Jordan with anything given his seizure history.

Then, he was hospitalized again for uncontrollable seizures and I realized I couldn't let fear get in the way of helping him. I started the day we were home from the hospital at a really low dose that Kerri recommended. She has held my hand through this process to help prevent him from having any seizures.

Since we started in May, he went 10 weeks seizure free and had several mild seizures that he brought himself out of without any extra medication and NO hospital. He is currently at a record-breaking 15 weeks seizure free.

Through this treatment we have learned that in addition to Lyme he has three different visible parasites. He is loaded—he passes more parasites than most of the teenagers in the FB group. It scares me to think what would have happened to him if we weren't led to this treatment. Thank God for Kerri Rivera sharing what she has learned and being so gracious and generous with her time.

I'm incredibly grateful we attended the Son-Rise® Intensive before all of this began. His team of facilitators created a base for him that continued to blossom even through this tumultuous year. Coupled with the parasite treatment, Jordan has gone from 20 to 90 words—he's picking up new words almost daily. His balance is amazing, his muscle tone is getting better, and he understands everything. Even more exciting, he's playing interactively with his sister. He is on the road to recovery.

We are finally able to start picking up the pieces of where we left off back in December. I felt stuck; I had PTSD; I needed help believing we can move past (what I had deemed) the horror of this year. The first thing I did was turn to Son-Rise®; I started having monthly dialogue sessions with Bears (Barry Neil Kaufman)—the co-founder of Son-Rise®, which has been incredible. This is one of those times that happen in life that can make you a better person or break you. Bears is guiding me to be better. I just arrived back from another Son-Rise® training where I realized that staying in fear and being nervous about getting excited or anxious about feeling hopeful again will prevent me from being the *bridge to healing that I want to be for Jordan. I felt a relaxation that I haven't felt all year. I've been wound real tight, waiting, being on the look out for that next seizure.*

This year has had a huge impact on Kaiyan as well. She'd see her brother sick and then her mommies would disappear. I'm noticing she's wound pretty tight as well. Her favorite moments are when the entire family is together. I'm hoping talking with her about what happened and spending more one on one time with her will help. She asks daily is Jordan throwing up, is he having a seizure? She doesn't really know what it all means, but is really aware it's not good. She, recently, said she wanted to have autism. After I explained to her that autism is why Jordan isn't talking or riding a bike, she decided she didn't want autism. She wants to be a boy and insists on wearing Jordan's clothes almost daily. I think it's her way of healing and feeling included in the process.

We've been doing Son-Rise® again and it feels great. I do feel like we have some time to make up for since this year has been spent dealing with health issues rather than cognitive issues so we are working up to having a full time program, having quarterly consultations, and doing another Intensive.

Son-Rise® and Kerri's protocol's are not only bringing our son back, they're bringing me back.

---

75. *Healing From Autism*

Hospital birth, bottle fed, fully vax until age 4. Digestive disorders beginning at age 1. Low tone, speech and language delay. Mild early education interventions. GF since age 2, GF, Soy free, sugar free since age 4. Majority of autism symptoms presented in 2013; in the fall of 2012, our son did not qualify as being in need of special education, and thus, could not attend school in our district at all.

Long winter days in a tiny home had me sending him out to play, in our tiny backyard, which had a patch of grass and a bush, under which small animals and birds lived. In his boredom, he sprinkled the dirt all over himself; his head, face, clothes, shoes, on several different days.

Later in the early spring, the symptoms of autism appeared more and more obvious: disobedience, disinterest in sitting for a story or coloring, lost interest in puzzles of more than 24 pcs, jumping on and off furniture for hours, despite scoldings and time-outs. Sudden relapse in bedwetting. Then by summer, the symptoms were very obvious: longer tantrums, rages, anger issues, hitting, fighting, a mean spirit; running out of the house without permission, with no respect for danger or regard for safety. Weepiness, hypersensitivity to touch, suddenly repeating the same phrase, over and over all day. Lost balance and coordination, bumping into walls and furniture, stubbing toes. Shoulder shrugging, all day, but not able to stop or say why he was doing it. Lost dexterity—could not put cards in a box. Lost organizational skills—could no longer put toys or clothes away. Extreme nighttime drooling and bedwetting. The need for sameness, and to have all food served cold. He frequently did not seem to be in his right mind.

In desperation, I asked a group of special needs moms for advice, and ordered a handful of books on Autism, including Healing the Symptoms of Autism by Kerri Rivera.

It was the best money I ever spent.

I read the book thoroughly, ordered the supplies and began the CD Protocol on July 8, 2013. Starting ATEC: 46. We ramped up slowly on drops, serving doses 8 times per day. My son has had two low dose/partial PP's, to minimize the emotional meltdowns, the gas and discomfort. I did not realize how very deficient in minerals he was, and did not give him enough ocean water. Now I order the big 10-liter jug of ocean water, so I am not tempted to be stingy. He needs more than 100 ml ocean water per day for his digestive system to handle the parasite dumping during the PP. His previous digestive trouble was unexplained chronic constipation, since age one, and that is really linked to his high need for the OW. Interestingly, his doctors had all said to keep giving Miralax, and that he might possibly need that laxative every day for the rest of his life. We stopped the laxative when we started the CD program, and began the enemas right away. When I sifted the stool and saw the number of parasites, I understood finally why he couldn't poop well on his own for the last 4 years, despite diet interventions. We are looking forward

to PP #3, in which I hope to ramp up to full dose on all components.

Poop sifting revealed what 6 pediatricians and 2 GI specialists could not tell us. Our son is infected with at least 6 different kinds of parasitic flukes and 3 kinds of parasitic worms. His stool has had a very large amount of sediment, with odd, tiny, but defined shapes. A search for "rodent and avian parasites" reveals photos of very tiny creatures.

I just completed his ATEC at Kerri's request: November 12, 2013: he now scores a 10, with a 1 in language, 2 in social, and 7 in health.

What does his recovery look like? We enrolled our son in a small private school this fall, with one teacher for 6 students, no aide. He now memorizes poems, Bible verses, and songs. He sings, knows his alphabet and all the sounds of the letters, and can count to 47 with precision. He shows kindness to others, is mindful of safety, and has glowing reports from his NT school. He sits with me for stories, and brings books to 'read' to his baby sister. He is not literate quite yet, but enjoys word search games, where he can complete levels and advance to more challenging puzzles. Twice now he has played the word search game on Leap Frog for 45 minutes. He has regained his balance and coordination. The rages, anger, and shoulder shrugging disappeared within the first 10 days on CD. He identifies printed numbers and letters, and does well in math, phonics, penmanship and reading class. He is learning to write numbers and letters in cursive, and follow directions on drawing worksheets. He operates the TV and DVR unaided, recording and watching programs he chooses.

He is happy; he has a patience and joyfulness about life that was previously lacking. He tells me jokes, and now has the coordination to operate a hand puppet while speaking for the puppet!! He is thoughtful and obedient. He has regained fine and gross motor skills, and motor planning skills.

There are still improvements we hope for: further speech, language, and vocabulary improvements. Social graces. More improved digestive health; I can see that he still has parasites in his stool. We will continue the CD Protocol, and we look forward to further healing. Thank you all for your support and encouragement.

The CD Autism Program has done more than cure our son of his brief affliction with Autism; it addresses the pervasive, underlying gut disorder and parasite issues that have plagued him all his life. Where complex testing in expensive medical centers has failed, a simple home health program succeeds. Thank you Kerri Rivera!!

76. *Well...we too did an ATEC! Our son was 11.5 when we started the CD Protocol July 2012 First fully loaded (All PP meds on board) was November 2012*

    VERY First ATEC: Jan. 2006= 124

    ATEC in July 2012: 64

    ATEC August 2012: 52

    ATEC Oct. 2012: 48

    ATEC Dec. 2012: 45

    ATEC May 2013: 40

    ATEC August 2013: 39

    ATEC NOV. 2013: 33

    I actually did one myself as I have done throughout all the previous, but I had hubby do one and combined and divided by the 2! Resulting in the 33! Oddly, it's the "SPEECH" that remains consistently around 14 & 15 throughout ALL of these! All the others continue to go down! We've had some ups and downs, but with continued evacuation of some MIGHTY big worms...we continue to see major gains!

    This is the ONLY Protocol that has EVER given us the progress we've seen in one year's time let alone in 6 months! Thank you Kerri Rivera and especially Patrick Rivera for being such pioneers in this journey to recovery! You are SOOO loved and appreciated beyond words! Thank you for never giving up! Thank you for giving so much, and bringing healing to our son! He's come a long way, but we have a ways to go! But with the progress he's making...I honestly feel it will seem like nothing from where we've come!

    Again THANK YOU! XOXOXO!

---

77. *We had a great day today. For the first time, he joined me in throwing something at a target (blocks at carpet circles). He laughed and smiled and pulled me to play with him better than he has in weeks. I heard a lot more sounds and approximations today. When I couldn't figure out what he was saying, he kept trying until I did.*

    My favorite part of the day, and I know this is odd, was when his head collided with my mouth. I exclaimed in pain and he was clearly worried/empathetic. He kept trying to get close to see my lip and giving me kisses. I've seen him concerned before but never that clearly empathetic.

---

78. *Just wanted to share that on 21/8/13 my sons ATEC was 46, just redid because we're at the start of our first pp & his score has come down to 31! The big improvement came after introducing CD enemas 3 weeks ago. Although he's been on oral CD for about 2 months, it was always the case that if I missed a dose within 1/2 hour he'd be sensory, inflexible, super-anxious, shouting, aggressive etc & I'd have to syringe it down him but within 10mins of dosing the lightswitch would flick on & he'd be in control & a calm, loving boy again. Since the 3 enemas I gave him 3 weeks ago (only 3 because then his brother had one, panicked, screamed & totally freaked out my 4yr old who up til then had said he liked them bc they made him feel good afterwards) his personality has been shining through again, there's less panick/anxiety, less sensory issues & there's no 'reaction' if I miss a dose or more of CD. I've seen more improvements this week, on Monday he decided to sit down & colour & proceeded to colour neatly,*

inside the lines - he was so pleased with himself! (He used to colour so neatly but about 6 months ago his colouring became scribbly & he frustrated that he couldn't do it neat anymore). Then tonight, when I asked him to hop out of the bath, HE DID! He stood up, stepped out & as I handed him a towel he took it & said 'thank you mummy' and wrapped himself in it & walked out - all completely relaxed - like it was usual!!! WWWOOAHAHH! Yes! He has never done this, it's always tantrums, always arguing, needs to bathe longer, has to be made to get out, refuses to step out, has to be lifted, needs me or hubby to wrap & dress him, & usually all while panicking, crying, demanding, arguing or screaming because it's cold, different, he doesn't want to, it's not right etc. I just can't believe what happened tonight! I'm still astounded. It's like the Finlay we 'know' isn't Finlay & now we're beginning to see who he really is!

So I'm REALLY excited about our 1st pp. We're already seeing full moon behaviours & although tough it's been great to see them because it's a reminder of what Finlay was like every day until 3 weeks ago!

He's already healing. It's soooo exciting! Thank you Kerri - may God bless you & all the children on this protocol. Healing, here we come!

---

79. *True Hope by Maggie Kaye*

Most people don't know that babies are born with about 100 million brain cells. That is more cells with more connections than there are stars in the galaxy! This is difficult to picture when you consider an infant's brain only weighs about 12 ounces at birth, about 25% of it's full size. But, there is a logical explanation for this: Brain cells; like the brain itself, have yet to grow. As neurons (brain cells) mature, they become larger, stronger, and form tentacle-like branches that form synapsis (connection and communication) with other brain cells. Brain growth is directed by neural activity. The neural activity of the cerebral cortex (the largest, most complex part of the brain) molds the way a child will think, behave, and acheive.

Conventional wisdom long held the belief that the human brain cannot change… that it is hard-wired at birth. Scientists today have proven that this is not the case. They have found that the brain is malleable. It has the ability to change shape, size, number of branches, number of connections, and even the strength of it's connections over time. The potential growth, or neuroplastisity (neuro means neurons or brain cells, plastic meaning changable) is far-reaching. At birth, the brain is simply a blueprint of what it will become. No one can predict the amount of growth that a brain has yet to acheive.

For the parents of a child with Autism, the diagnosis can be devastating. But, the biggest and most harmful blow can come from the prognosis: There is no cure. Kenn and I were given a diagnosis of an Autism Spectrum Disorder for our son, but we were not given this prognosis. In fact, the word "Autism" was avoided at our son's diagnostic evaluation until the therapists heard us say it first, and realized we were comfortable with the word. For many parents, a diagnosis is the end all, be all. For far too many parents, the words "No cure" are scary and harmful. We did not hear these words nor would we have accepted them as truth if we had. We do not want to change our son. We want him to be his best self. We are not looking for a cure. We are in search of treatment and *healing for his symptoms. We know and understand that a Therapist is not God. A Therapist cannot predict the future for our son. He or she can simply assess where Gunnar is developmentally and give us options for a treatment plan for a healthy, successful future. Our son's diagnosis was not an ending. It was simply the begininning of a journey through a world of strength, challenges, support, opposition, and the love of a parent that cannot ever be fully defined.*

Our son, Gunnar was born with an Autoimmune disorder, Hypothyroidism. He was tested at birth, was diagnosed, and has been treated by an Endocrinologist since he was three days old. We were not upset by the Hypo diagnosis, but rather ready for the course of action to regulate all of Gunnar's bodily systems. What did surprise us was the constant shrugging off of our concerns over our son's developmental delays and gastrointestinal symptoms over the last few years. We were continually disappointed by the compartmentalization of our son's physical and mental challenges by every Pediatrician and Specialist we saw. To us, Gunnar's symptoms all had to be as connected as are all of his body parts. But, we were treated as if our concerns were dumbfounded…as if digestive, behavioral, and physical challenges were not intertwined.

Let's be clear...The brain does not function in isolation. It is a team player. It needs vital nutrients and informational input to perform at optimum levels. To fill these needs, the brain relies heavily on complex interactions between the immune, endocrine, and gastrointestinal systems. Gunnar, like so many other children on the Autism spectrum, suffers from gastrointestinal issues uncluding chronic constipation, diarrhea, and abdominal discomfort. Scientific studies and countless parent reports are pointing to gut inflammation caused by casein, gluten, and soy in our foods. Gunnar has shown clear physical and behavioral reactions to these foods, and improvement in these areas with the removal of Gluten, casein, and soy from his diet. This is not an allergy from the perspective of a traditional allergist. This is what is called a T Cell Inflammatory response.

The use of a gluten, casein, and soy free diet as a means of treatment for Autism symptoms has gotten mixed responses. Many parents and doctors who deal with Autism, Immune, and Endocrine disorders rave about it's benefits, including me and my husband. Still, others call it "junk science". Clearly, if someone is looking purely at one body part at a time, they will not be open to the truth that the body and brain are codependent. I, personally, have been challenged by the choice to follow this diet for my own thyroid disease and for my son's Autism. I was even told on an online support forum that the GFCFSF diet is "fake science" and is causing "false hope" for parents of children on the Autism Spectrum.

False Hope?

This may be one of the biggest oxymorons I've ever heard. This ranks right up there with "God Hates". I cannot say what causes people to be so oppositional to our choice to follow this eating plan. Perhaps the resistance to this way of eating is due to a simple misunderstanding of the leaky gut syndrome that plagues so many children on the Autism Spectrum. This leaky gut syndrome does not cause food allergies. It causes food sensitivities.

In food allergies that many parents are famililar with, the symptoms arise immediately in the form of hives, watery eyes, sneezing, or difficulty breathing. They can even produce life-threatening anaphylactic shock. Only about 10% of *autistic kids have this type of allergy. Some 85% of children with Autism have food sensitivities. Rather than immediate physical symptoms, these sensitivities produce and inflammatory response that results in more subtle mental and behavioral symptoms that can take anywhere from 6-72 hours to appear. The brain's primary fuels are oxygen and glucose which are manufactured from nutrients in our food supply. It only makes sense that we get out of our brains what we put into our bodies.*

When it comes to the treatment of any neurological disorder, many parents and doctors focus solely on the obvious cognitive impairments and fail to realize that correcting their child or patient's underlying intestinal imbalances can; and often does, lead to significant overall improvement. Leaky gut syndrome which is so prevalant in children with Autism Spectrum Disorders causes a long list of vitamin and mineral deficiencies because the inflammation process damages the various carrier proteins normally present in healthy GI systems. Our plan is to treat our son from the inside out; Reduce the inflammation, test for vitamin and mineral deficiencies, provide necessary supplements, test for toxin poisoning and remove if necessary, provide therapy as needed, and set Gunnar up for the best possible outcome. When you feel better, you perform better. Who can argue with this rationale?

Many people have differing opinions on what does and doesn't work for families facing Autism. There is a saying in the Autism community, "If you have met one child with Autism, you have met one child with Autism" There is a broad spectrum with severe to mild physical and behavioral symptoms. One person's treatment protocol might not work for another person. I am not judging what others choose to do to treat their child, I am simply sharing what has worked for us thus far. I am not searching for or promising a cure, I am finding a treatment for and healing the symptoms that affect our son. Whether or not you agree with how my family and I choose to approach this journey does not change the outcome. If we have helped one person understand this complex neurological disorder, we have helped spread understanding, and that makes us happy. And, if you are a family facing Autism and don't know which avenue of treatment to pursue first, our advice is: Go with your gut.

---

80. Recovery #107

Having a sick child is a full time job. Even when they are well, your mind is filled with ways to keep them from getting sick again, ways to improve their current state, ways to help others who were where you were just a short time ago. It is my hope to do all three.

Autism entered my life a few years ago, but I didn't recognize it. My son, Gunnar was three when my husband and I realized he wasn't progressing as he should. He wasn't asking why, what, where, or when questions. He wasn't growing. He was lining up his trains and cars, screaming if we touched one of them. Gunnar was oppositional and refused to go into a crowded place. He didn't look anyone in the eye, and it seemed to make him uncomfortable to try. He had several sensory issues such as covering his ears when music played, even when the volume was low. He had an aversion to touch and would often yell, "ouch!" when someone touched his arm softly. He was constipated. He smeared his feces on the wall. He often woke in the middle of the night screaming. My husband or I *would find him in the fetal position and he couldn't or didn't respond when we asked what hurt. Gunnar went ballistic when we tried to wash or cut his hair or brush his teeth. He was indifferent to me leaving for work, and what was most painful for me, he ran and hid when I returned. He didn't much care for his own mom and that was heart breaking for me.*

We also noticed some regression. Gunnar stopped showing interest in potty training. He went from saying, "Gotta go pee pee!" to not even recognizing he'd soiled his pants. He started refusing foods he previously enjoyed. He went from using several words in succession to not speaking more than two words strung together. He started to be extremely picky when it came to the foods he would eat and spent most of his time at the dinner table staring out of the window. We were losing our son.

Our son was born with an autoimmune condition, Hypothyroidism. He started taking medication just three days after he was born. Initially my husband and I interpreted some of our son's Autism symptoms as side effects from his medication dosage fluctuations. After all, we voiced our concerns to his Pediatric Endocrinologist, and she assured us he was fine. She said the medication was likely making him lethargic. She said boys took longer to potty train. As time went on, Gunnar's symptoms multiplied and worsened, and other caregivers took notice and shared their concerns. At our son's next Endocrinologist appointment, I insisted on a referral for a developmental evaluation.

Our son was diagnosed with an Autism Spectrum Disorder in January of 2013. He was 4 years old. I immediately went into research mode reading everything I could get my hands on that was related to healing Autism. Two weeks after his diagnosis, we started a gluten, dairy, soy free diet and saw digestive issues disappearing. The night-waking was going away. He turned toward us when we called his name. He spoke in short sentences, requesting to watch a movie or eat a snack.

A month after Gunnar's diagnosis we had further testing done to see where he was on the spectrum. When we showed up for the appointment, the diagnostic team was impressed with our son's progress. He responded when they asked him to point to specific items, and he had no trouble matching items together. I remember thinking he was much smarter than I'd realized. Clearly the problem with our son was physical.

The test results showed Gunnar's speech and language to be at a 23 month old's level with his gross and fine motor skills not much further along. We were determined to heal our son and scheduled an appointment to have all kinds of testing done including food allergies, comprehensive stool analysis, and genetic mutation tests. These results showed that our son was sick with food allergies, leaky gut caused by an overgrowth of bacteria, and pathogens. We knew what we were up against. We were on the right track with diet, but had to find out how to get rid of the bacteria and pathogens. In my research, I stumbled upon the CD forum. It was the first treatment program that made complete sense to me.

We received the book in June. It was the first book our son ever showed interest in. He kept saying, "This is it!" and, "This book is the best!" He didn't want to put the book down. My husband and I looked at each other with tear-filled eyes. We knew Gunnar was right; this was it.

We started the CD Protocol immediately...just five months after our son's diagnosis. His starting ATEC was an 80. Immediately we saw regular bowel movements, diminished dark circles under his eyes, and healthy skin coloring. Gunnar began to sleep through the night. Four days into the protocol, our son started taking turns and sharing with other kids. That night, he danced at a graduation party. Every day, his vocabulary improved.

Four weeks into the protocol, our son no longer needed his thyroid medication he'd been on his entire life. He started using the bathroom unprompted. He dressed himself unprompted. He brushed his teeth on his own. Gunnar didn't mind getting his hair cut. He began to engage in reciprocal conversation.

Seven weeks into the protocol, we saw so many behavioral improvements; we decided to take the ATEC test again. Gunnar's score was a 40. It was cut in half in seven weeks!!! Eight weeks into the protocol our son celebrated his 5th birthday. It was the first time he showed anticipation for a party. He was excited to open his gifts and thanked everyone individually. Normally, Gunnar would run and play by himself when guests came over. He had always covered his ears and yelled, "Stop singing!" at previous parties. Gunnar was happy when everyone sang Happy Birthday to him. He was healthy and present. It was one of the happiest days of our lives.

Twelve weeks into the protocol, our son started mainstream preschool. All previous attempts to take him to school resulted in anxiety and complete meltdowns. He started speaking in complete sentences and his speech was relevant to the situation. He started showing interest in books. Fifteen weeks in, our son read his own bedtime story with no help. He picked out his own Halloween costume. He brought home his artwork and proudly showed it to us. His teachers continually voiced their pleasure at his progress. His speech therapist said he was at age level for speech and language. (that's 3 years worth of progress!)

Twenty-four weeks into the protocol, our son's ATEC score is a 10. He continues to go to mainstream preschool and is interested in learning. He is reading a variety of books. He is counting in English and Spanish. He knows his US geography, and does puzzles that are advanced for his age. He asks questions. His speech is appropriate and relevant with continued improvement in vocabulary and articulation. He loves to sing, dance, and paint. Our son is smart, funny, and very affectionate. He spontaneously hugs and kisses me and tells me he loves me. And the best part of all? When I come home from work, Gunnar yells, "Moooommmmyyyy!", runs up to me, jumps into my arms, and wraps his little arms around my neck. I have my son back.

I could never sufficiently thank Kerri Rivera for all of her selfless help. She and her team of parents give freely of their time and energy to bring kids and their families out of the depths of Autism. It is my hope to pay it forward. All children deserve a healthy childhood. If you are holding this book, you are likely in the position my family was in just 10 months ago. This is the way to turn your feelings of desperation into determination. This is the way to change the future for your family. This is the way out of Autism.

—Maggie Kaye

81. *Ok, my brother is 17 and started CD at the end of october. We are on 9 drops as of today. Non verbal. My mom called me crying and my brother said "I want snack please." My mom asked if he wanted something and he "no, no, no." He got his yogurt (df) out and said "thank you." This is just so amazing. Thank you God for putting us on this path and around so many amazing warrior parents to help us with our journey. Happy healing to all!!!*

---

82. *At the age of 3 our son was absent. He talked a lot... to himself. Scripting. It was almost impossible to get him to look into our eyes when we spoke to him. He almost never answered back, and when he did, it was scripting again (from a show on TV or a movie he was into.) He played by himself. He refused to potty train. He would wake up in the middle of the night crying and holding his stomach but was unable to tell us what was wrong. He stopped eating whatever we put in front of him and seemed to only want fruit snacks, American cheese, hot dogs, chicken nuggets and fries. And thats it. He didn't seem to be growing anymore, both physically and mentally. He seemed to be slipping away from us. You could see it in his eyes. Those eyes that were pointed off in a different direction. It was gradual...hard to notice right away. But definitely a change, and not one we were happy with.*

Up until this time he was progressing like any other child. He ate well. He slept well. He played well. Was even starting to potty train. A typical child. But not anymore. Then there was the diagnosis. Autism. No parent wants to hear that, but we knew. Every parent knows what I mean. You just know. And at this point we (as parents) have to make a choice.

We can choose to do nothing. Just live with it. We can listen to our doctor, or a specialist in the field. You know, someone who claims to know everything about you and your child in the 5 minutes they spend with you. Or you can talk to other parents. Parents that spend every moment with their children. Not just a few minutes every six months. You can network. You can research. Ask whats working for them, or more importantly what's not.

We chose the latter, and because of this our son is recovering. He looks into our eyes. He asks questions. He sleeps at night. He's potty trained. He sets the dinner table with his older sister and asks to be excused when he's done eating. He's in pre-school now and plays with all of the other kids. He calls them by name. He draws. He paints. He reads books. He does all of the things a typical five year old does.

Our son is recovering, and I need to give two heartfelt thanks for this. The first to my wife for the countless hours of reading and research she did immediately following our sons Autism diagnosis. She is an incredible woman who refuses to give up on anything. Ever. She refused to believe that we had to accept what was handed to us. She knew in her heart and mind that we could make a difference. We just had to do it. Because of this determination, she found Kerri Rivera, whom is the next person I want to thank. She is a true pioneer, someone who refused to keep thinking inside the box, someone who is helping families like ours all over the world.

" We have the world at our fingertips. Every book, every encyclopedia for us to read at our local library, in our own homes, and now on (most) of our cell

phones. It's a beautiful tool for us to use. Use it. Do your own research. Talk with parents. Find out what works and do it.

The only thing I really have to say about Kerri's book and the protocol it explains is that it works. We have our son back.

—Kenn Kaye, Father of Gunnar Kaye

---

83. *Last night, my 19 year old son came out into the kitchen, picked up a purple straw from the dish drainer, and pretended to play it like a clarinet with great enthusiasm. Pretend play. For the first time in 19 years.*

---

84. *We've been playing the "healing game" with my son for some time, (7 years 11 months old) but we've never really healed anything. To be honest we've never known what we were up against...until now. Like everyone here, my child is very sick. He doesn't grow, he has maldigestion and malabsorption issues and he's chronically constipated. His history of constipation is long and extensive. ANYTHING that disrupted his gut flora would result in this extreme constipation; whether it was a cold, a new food, treating the GI. To say he has leaky gut is a tremendous understatement. So, when we started Kerri's protocol 6/15 my biggest health markers for initial healing were growth and for him to poop daily on his own. With his history being what it is I wasn't surprised to see he was instantly constipated. How could he not be? We are killing pathogens and parasites like gang busters. We started enemas on day two and have done them daily. But, an amazing thing is happening! He is healing. He has grown two inches in these last three months and he starting to poop on his own. BTW, these aren't just lame little poops they are total TROPHY poops. They are soft, formed, have no undigested food and there is lots (I'd show you a picture but we barely know each other)*

Yep... It's taken 3.5 months to get here, but his little; fragile and damaged body is doing what it is supposed to do.

Trust the process... It's not easy; it's not always fast. There will be ups and downs. But, my gosh, watching the body heal is an extraordinary thing. It's nothing short of a miracle.

---

85. *Hi Kerri,*

I started my son on the CD last night. I'm taking it with him.

Well, I for one, feel fabulous. My lungs are clearing up, the low-level depression I felt is evaporating. Wow!!!

I've noticed some subtle changes in my son. He is more "with us" in the world and not looking out the window at cars quite as much. Also, a little less flapping his hands.

He and I have been doing a ketogenic version of the GAPS diet (no sweet vegetables, no dairy, no sweeteners) since January of 2013, and I think that's why we've been so successful with the CD! :)

I was thinking of upping it to two drops per 8 oz bottle--one for him, one 8 oz bottle for me.

I am hoping that Sulfur is Ok to still give him. We used to cut it with Kombucha, but that is now a no-no.

Thanks and Huzzah!

86. *Ryan is the first of our 3 children to recover. Ryan was not considered autistic by most standards but did score a 19 on the ATEC test prior to starting the CD protocol. He is 9 years old and has been in mainstream classes without an IEP. We did hold him and his twin brother back one year prior to starting kindergarten so they could have more time to heal from Lyme Disease which we had been treating since they were 4.*

Ryan was a healthy baby but I did notice after saying his first words at the appropriate age, he stopped talking a few months later. (I now know that is a symptom of autism!) And both he and his brother were very late with language despite knowing their alphabet at a very young age. Ryan did eventually talk but was often hyperactive and had a hard time sitting still in class or at the dinner table. It was often hard to get his attention and to get him to listen to requests. He was constipated since he was a baby and was a very picky eater. I dreaded mealtimes because it was so hard to get him to eat. We often had to spoon-feed food into his mouth even when he was 7 years old. Treatment for Lyme Disease helped many of his symptoms but he still had some remaining symptoms such as weakness, stomachaches, seeing orange and blue spots at night (more noticeable in the dark), nightmares, bedwetting, difficulty falling asleep and early awakening, and overly emotional and irrational behavior. These symptoms worsened dramatically when our house well water became contaminated with parasites and bacteria. It took us two years to figure out that the water was the cause of our deteriorating health. During this time, Ryan became unable to play sports or have play dates without melting into irrational tantrums when things didn't go his way. When playing mini golf, he refused to finish the round after getting a score of "10" on one hole and had a crying tantrum. In tennis class, he would sit down on the court and start crying if he didn't get to hit as many balls as the other children on the court with him. We didn't even attempt to put him in team sports for fear that he would melt down and storm off, refusing to play the rest of the game.

Then we discovered CD and Kerri's protocol, and his and our lives changed forever. Within three weeks of taking CD, Ryan's ATEC dropped to an 8. This improvement was the difference in Ryan being able to play sports. He was able to play on a baseball team and while he did get angry if he struck out or made an error, I was there with a dose of CD and that would keep him from a complete meltdown. As the season continued, Ryan's emotions became more and more stable and normal. His energy increased greatly and now after 6 months on the protocol, Ryan is playing three different sports, taking piano lessons and excelling in above grade level reading and math. His ATEC is a 3 but we will continue until it is 0. His first report card since starting the protocol was the best of his life. We were most excited to see that his scores for behavior and attention were above expectations. Last year, these same scores were all below expectations because Ryan was so hyperactive and unable to focus due to the parasites. Ryan still sees a few orange spots at night but they are diminishing and we know they will be gone so long as we stick with this protocol until he is completely healed. We are so grateful that Kerri blazed the way for us all by developing this protocol. I have been searching for the past 7 years for a way to fully heal my children and the CD was the last but most significant piece of the puzzle for us. We will be forever thankful to you Kerri!

87. *I first heard about CD, then called MMS, to treat autism in May 2012 and wanted to try it out with my then 10-year-old son. I bought supplies, and did the then-current protocol for a few months, but then school ended and summer vacations started and I put CD on the back burner or did it very sporadically. My son was verbal and high functioning, but still had lots of autistic behaviors. His ATEC score in 2012 was 27.*

I started reading about CD again in the summer of 2013. This time there was more information out there. Kerri had written her breakthrough book and lots of facebook friends in the autism community were mentioning it. I bought the book and dove in, first using my old supplies (CD with citric acid) then buying HCl and trying that. My son did very well with the new protocol, starting low and getting to full dose around the time of his 12th birthday at the end of August. I started seeing worms before we even started our first Parasite Protocol! When I started the Parasite Protocol and added in ocean water, things kept getting better! No set-backs or regressions. School was seemingly much easier for my son. He was in a mainstream class with resource room help for reading and writing for the second year, but this year, math homework was no longer taking several hours, but 20 minutes! His reading comprehension was improving as well, and more importantly, I didn't worry about hearing about behavioral issues anymore!

I wanted to complete three months of CD before I took another ATEC. When I filled in out in November, at the start of our third Parasite Protocol, I was shocked to see a score of 7! My son had dropped 20 points from his 2012 score! Seeing the single digit score was so amazing! My son had been diagnosed with autism at age 2 ½ and there were no options given to me at the time. An early IQ test given by a speech therapist had shown he was mentally retarded and that was that. However, I looked into everything I could, and was not going to give up on my son. So glad I didn't! Nine years of autism, but the beginning of his 12th year marks the end of it! I know his ATEC score will be 0 soon!

---

88. *"thank you for your help in recovering me"*

This is what my son just typed to me this morning on his iPad with the app we use for supportive typing!

Thank you Kerri & Patrick for all you have done and continue to do!

Without you BOTH, we would NEVER be in the place we are right now... HEALING & RECOVERY!

Just know you are LOVED!

—Melissa in Indiana

---

89. *Sophia was born on March 9, 2006. She was a typical happy baby who slept well and seldom got sick. She met all of her developmental milestones and laughed and made great eye contact. When she turned one just after her vaccines she became violently ill and vomited with fever for 2 days straight. After that she was never the same, her smile was rare and words were gone. When she was nineteen months after more shots, we took her to an ear doctor out of concern that she was not responding to her name or speaking clear words. Her hearing was tested and we were told she was fine and to give her time. After a few months of no change her pediatrician determined that she was developmentally-*

delayed and had all the symptoms of Autism. We were stunned and unprepared for this news. I went into warrior mode and ended up with a DAN dr, who started her on lots of supplements after initial lab results showed heavy metal toxicity and high amounts of intestinal yeast. We followed the program and advice of this doctor for the last 4 years with the only change being dietary fluctuations. Sophia did improve but hit a plateau where no new gains were made in the last year or so, so in May 2013 her DAN doctor suggested that we do another round of stool testing after a urine acid test showed bad bacteria overgrowth and terrible mito issues. Her comment to me was "this kid's DNA is so messed up, I haven't seen a test this bad since the 1990's." This was after thousands of dollars and too many supplements to count. I was done at that point. There were no answers there obviously. I came across this protocol on a Facebook page for autism parents and purchased Kerri's book in September 2013. I immediately knew that this was the answer for my daughter. I had a gut instinct that she would be healed . We started the diet immediately and CD just after. My daughter had been a juice addict before this and I was worried about her taking the CD and being able to drink the water. This was only an issue for a day or so. I have not missed a day of giving her 8 or more doses. We get up very early and dose her ocean water and 2 CD doses before school. On weekends we are doing 16 doses/day. In the second week we started seeing some herxheimer/die off, very sleepy followed by fevers. This is when the transformation started! I followed the fever protocol and did enemas and she got better. She also had an episode around week 7 of very red throat and fever which we double dosed for and resolved. We have seen a withdrawn, self -focused child with little interest in the world outside of herself disappear and turn into a child interested in friendship with peers, reading books and understanding the story (huge!), and having relevant conversation with great eye contact. She gets all A's at school and has made a complete turnaround with behavior. We have so much hope for her future and she is blossoming into a beautiful, happy girl!

---

90. *Here are a few of the emails I mentioned from my son's therapist in regard to what's happening at therapy! :)*

This is an email from the exact day I restarted the CD, which was August 21 of 2013.

We discovered a new game today. He was being a turkey and running up the hall to try to get around me to get places he wasn't supposed to go. I started singing (to the tune of rolling down the river) about whatever he was doing "walking, walking, walking down the hallway" "jumping, jumping jumping down the hallway" climbing, climbing, climbing up the ladder. He thought it was hilarious, especially when I'd change in the middle of a verse "running running, jumping down the hallway.

—Your son's therapist

Great day today! Vail seems to be understanding first, then sequencing and I think I finally have a bribe for him--he loves our fish.

Also, he made a friend today. One of our other pt's was playing in the gym and he was watching him, imitating him a little and said his name 2x!

—Your son's therapist

We tried to play the game and he wasn't interested. Instead we ended up *pushing the fisher price horse, sheep, goat, and cow off the treehouse. He would "randomly" produce sounds which we took for requests for the animal associated. Then we would give him the animal "requested." Reviewed his sound cards and he produced the /n/ and /h/. Coulda sworn he said go a couple of times, and mom said she heard a whispered "home." Listen and be watchful for whispers! Oftentimes children with apraxia can get one system working but not the other, ie. articulate with no sound, or vocalize with intonation and no articulation, like when he says "ah uh oo" for "I love you." Yep, he does that!*

Cheers!

---

91. *Hi had to share this moment today, just wish daddy wouldn't have missed it!*

Well, we were seeing daddy off for work this evening, when Vail decided that he wanted to go run around in the grass. I told him we needed to put on socks and shoes and then we could play outside. He walked straight to the door, we walked in, I pointed at his socks and shoes, and FOR THE FIRST TIME EVER (always knew he could, just to stubborn to do it unless he really wants too!) he promptly walked over, picked up his socks and shoes and turned and handed them to me!!! (all the while doing it with an attitude!!!"lol)

This is Just from MOM to therapists. :)

CD and Kerri have been life changing for our entire family. We now can give Vail choices, usually of two items. For example I showed him two pairs of pants and asked which he wanted to wear, and he grabbed one pair and started to put them on even though he was still in his pj's. I showed him two shirts, and he picked a shirt. Same thing with his shoes and socks, he is able to choose now on his own. I look forward everyday to him doing something differently or completely new, and he almost always does now!!! This was not possible for CD!!! THANK YOU KERRI !!! WE LOVE YOU FOR SHARING AND FIGHTING THE FIGHT!!!

LOVE,

—The parents of Vail

---

92. *Best day of the entire school year! My son initiated verbal interactions 5 times today and responded to his teacher in a group over 5 times, WITHOUT A SINGLE PROMPT! Most days his TA is poking him to pay attention and ask other kids for directions, rather than an adult, all day long! She is tracking these interactions as they are his IEP goals.*

---

93. *Casey is a young man who is 17 years old today, and the estimated ATEC score from 2006 is from when he was 10 years old. Proving once again that recovery is possible at any age.*



Casey H. ATEC History	ATEC Estimated	Start CD	3 months	6 months
	10/12/2006	5/6/2013	8/6/2013	11/6/2013
I. Speech/Language/Communication	6	1	1	2
II. Sociability	14	11	3	0
III. Sensory/Cognitive/Awareness	25	13	6	5
IV. Health/Physical/Behavior	39	28	8	5
TOTAL ATEC SCORE:	84	53	18	12

94. Daniel - beginning ATEC June 2013 - 101. Today ATEC Nov 12, 2013 - 44! We are thru our 3rd PP and starting speech supplements. Speech, by far, has been the hardest thing. In all other areas he is under "10" on the ATEC! Kerri Rivera words are coming. This week alone he is saying "Hi" and "Bye" and trying to say others. I can't wait to hear "I love you Mom"! You are the Bomb Diggitty Kerri. We all love you!

UPDATE: December 3rd, 2013

I officially want to tell the world that my son, Daniel, who has autism is nonverbal no more! He is starting to talk. Praise God! This battle has been the struggle of my life, but i have learned to trust God, be patient, and enjoy the journey! Where some take a lot for granted regarding their children, I have been waiting almost 7 yrs to hear his beautiful voice! And thank God he has one! Autism is treatable and there is hope!

---

95. We had a super exciting trip, we went to a therapist on the 28th who teaches Rapid Prompting Method. We have tried since by daughter was diagnosed to get her to speak, but haven't had any luck yet, she is now 11. We thought we would give RPM a try to see if the therapist could get her to communicate.

We not only found out that she is able to make correct choices, but can actually SPELL! Her very first word that she spelled was CLOUD!

Later on in the session the therapist asked her what her favorite color was... she spelled out PINK!

I was sitting on the floor in awe... For the first time in 11 years, I finally know what my girl's favorite color is... it was surreal... it was amazing... she is so smart, but had no way of letting us know... I am soooooooo proud of her!

---

96. Diagnosed at 20 months old in August 2011

Started supplements under Dan in September 2011

Started CD / PP on July 1, 2013, after seeing rope in stool

Starting ATEC on July 1, 2013, was 46

Present ATEC 22

Gained 5 pounds from July 1st to present!

Too many improvements to list!!!!!

Also doing GcMAF which has also helped……but, I believe GcMAF may have helped more with the viral load. I suspect this because we actually started IV GcMAF in January 2013, before CD . Huge gains with GcMAF but after 35 shots, her gut was still a mess and GcMAF definitely didn't help with the gut. Found Kerri in July 2013, and began our healing journey.

The following lab results are proof of just how well the child described above is doing since starting the protocol. Here is what her mom had to say:

> *"The original test was taken last August of 2012, which showed a deficiency in almost everything despite the fact that my daughter had been on supplements for over a year at that point. The re-test was just taken October 2013, only 4 months after CD / PP and removal of ALL supplements. Wow!"*
>
> *You can see in the second test that her high viral titers were reduced as well.*



Patient Copy

Genova Diagnostics
Improving Healthcare for Chronic Disease

63 Zillicoa Street
Asheville, NC 28801
© Genova Diagnostics

ONE FMV
OPTIMAL NUTRITION EVALUATION

Patient: B
DOB: November 18, 2009
Sex: F

Completed: August 27, 2012
Received: August 21, 2012
Collected: August 13, 2012

ONE Results Overview

	Normal	Borderline	High Need	Supplementation for High Need
Antioxidants				
			Vitamin A / Carotenoids	Vitamin A / Carotenoids Dose = 3,000 IU
			Vitamin C	Vitamin C- Dose = 250 mg
			Vitamin E / Tocopherols	Vitamin E / Tocopherols Dose = 100 IU
	α-Lipoic Acid			
			CoQ10	CoQ10- Dose = 30 mg
B-Vitamins				
		Thiamin - B1		
			Riboflavin - B2	Riboflavin - B2 Dose = 5 mg
		Niacin - B3		
		Pyridoxine - B6		
		Biotin - B7		
		Folic Acid - B9		
			Cobalamin - B12	Cobalamin - B12 Dose = 50 mcg
Minerals				
			Magnesium	Magnesium Dose = 200 mg
	Manganese			
		Molybdenum		
		Zinc		

© Genova Diagnostics · A. L. Peace-Brewer, PhD, D(ABMLI), Lab Director · CLIA Lic #34D0655571 · Medicare Lic #34-8475

UONE RMS 3147 Rev 5



Patient Copy

GENOVA DIAGNOSTICS

63 Zillicoa Street
Asheville, NC 28801
© Genova Diagnostics

ONE FMV®
OPTIMAL NUTRITION EVALUATION

Patient: B
DOB: November 18, 2009
Sex: F

Completed: October 28, 2013
Received: October 18, 2013
Collected: October 17, 2013

ONE Results Overview

	Normal	Borderline	High Need	Supplementation for High Need
Antioxidants				
			Vitamin A / Carotenoids	Vitamin A / Carotenoids Dose = 3,000 IU
	Vitamin C			
			Vitamin E / Tocopherols	Vitamin E / Tocopherols Dose = 100 IU
		α-Lipoic Acid		
	CoQ10			
B-Vitamins				
		Thiamin - B1		
	Riboflavin - B2			
	Niacin - B3			
		Pyridoxine - B6		
	Biotin - B7			
	Folic Acid - B9			
	Cobalamin - B12			
Minerals				
			Magnesium	Magnesium Dose = 200 mg
	Manganese			
	Molybdenum			
	Zinc			

© Genova Diagnostics · A. L. Peace-Brewer, PhD, D(ABMLI), Lab Director · CLIA Lic. #34D0655571 · Medicare Lic. #34-8475

UONE RMS 3147 Rev 5



LabCorp

Patient Name							
B.C.							
	Patient ID	Control Number	Date and Time Collected	Date Reported	Sex	Age(Y/M/D)	Date of Birth
			08/21/12 11:21	08/25/12	F	2/09/03	11/18/09

```
              TESTS                  RESULT     FLAG       UNITS      REFERENCE INTERVAL   LAB
Zinc, Whole Blood                      478                 ug/dL        440 - 860          01

Anti-DNase B Strep Antibodies
                                       <71                 U/mL           0 - 77           01
      **Results verified by repeat testing**
      Limit of assay detection is <71

Rubeola Antibodies, IgG
 Rubeola Ab, IgG, EIA                 4.33     High        index      0.00 - 0.90          02
                                                             Negative        <0.91
                                                             Equivocal 0.91 - 1.09
                                                             Positive        >1.09

                    Presence of antibodies to Rubeola is presumptive evidence
                    of immunity except when active infection is suspected.

Human Herpes Virus Type 6 IgM
                                     <1:10                               Neg:<1:10         04
      Results for this test are for research purposes only by the assay's
      manufacturer.  The performance characteristics of this product have
      not been established.  Results should not be used as a diagnostic
      procedure without confirmation of the diagnosis by another medically
      established diagnostic product or procedure.

HHV 6 IgG Antibodies                  7.66     High        index                           01
                                                           Negative          <0.76
                                                           Equivocal  0.76 - 0.99
                                                           Positive          >0.99
                    Results for this test are for research purposes
                    only by the assay's manufacturer.  The performance
                    characteristics of this product have not been
                    established.  Results should not be used as a
                    diagnostic procedure without confirmation of the
                    diagnosis by another medically established diagnostic
                    product or procedure.

Antigliadin Abs, IgG
 Deamidated Gliadin Abs, IgG           15                  units          0 - 19           02
                                           Negative                       0 - 19
                                           Weak Positive                 20 - 30
                                           Moderate to Strong Positive    >30

HSV Type 2-Specific Ab, IgG
 HSV 2 IgG, Type Spec                <0.91                 index      0.00 - 0.90          02
                                                             Negative        <0.91
                                                             Equivocal 0.91 - 1.09
                                                             Positive        >1.09

Rubella Antibodies, IgG                58                  IU/mL                           01
                                                           Non-immune      <5
                                                           Equivocal    5 - 9
                                                           Immune          >9
```



Quest Diagnostics Page 2 of 4 10/17/2013 04:07:42 PM **Report Status: Final**

Patient Information	Specimen Information	Client Information
B.C. **DOB: 11/18/2009** **AGE: 3** Gender: F Fasting: U Patient ID: NG	Collected: 10/07/2013 Received: 10/07/2013 / 21:37 EDT Reported: 10/17/2013 / 14:42 EDT	

Test Name	In Range	Out Of Range	Reference Range	Lab

A positive result indicates that the patient has antibody to CMV. It does not differentiate between an active or past infection.

RUBELLA IMMUNE STATUS				QHO
RUBELLA ANTIBODY (IGG)	3.13			

Value	Interpretation
< or = 0.90	Negative
0.91-1.09	Equivocal
> or = 1.10	Positive

The presence of rubella IgG antibody suggests immunization or past or current infection with rubella virus.

EPSTEIN BARR VIRUS VCA AB (IGG)	< OR = 0.90		index	QHO

Index	Interpretation
< or = 0.90	Negative
0.91 - 1.09	Equivocal
> or = 1.10	Positive

DNASE B ANTIBODY	<95		< 251 U/mL	SLI
MEASLES ANTIBODY (IGG)	4.09		index	QHO

Index	Explanation of Test Results
< or = 0.90	Negative - No Rubeola (Measles) IgG Antibody detected
0.91 - 1.09	Equivocal
> or = 1.10	Positive - Rubeola (Measles) IgG Antibody detected

Positive results suggest recent or previous infection with Measles (Rubeola) virus and imply immunity. Patients exhibiting equivocal results should be retested in one month, if clinically indicated.

HERPESVIRUS 6 ANTIBODIES (IGG, IGM)				XE:
HERPESVIRUS 6 IGG		1:80 H		
HERPESVIRUS 6 IGM	<1:20			
INTERPRETATION	PAST INFECTION			

REFERENCE RANGE: IgG <1:10
IgM <1:20

Human Herpesvirus 6 (HHV-6) infects T-lymphocytes, and has been identified as an etiologic agent of exanthema subitum. Rises in antibody titers to HHV-6 have been detected during infection with other viruses. In seroepidemiology studies of the prevalence of exposure using serum screening dilutions of 1:10, the detection of IgG antibody in a mid-life population approaches 100%. Due to this high prevalence of HHV-6 antibody,

PAGE 2 OF 4

Quest, Quest Diagnostics, the associated logo and all associated Quest Diagnostics marks are the trademarks of Quest Diagnostics.

Testimonials from the First Edition Continue Here...

97. *Meeting a Rescue Angel*

The way OUT of AUTISM

My 5 year old little daughter, Anna's story has been long and paved with lots of suffering and doubt, compared to her age, but prayers have always helped us in our journey. We are aware that it may take years to get out of the dark depths of Autism but now we know we are going in the right direction. Finally! Thanks to Kerri Rivera, the Rescue Angel of so many suffering children. She showed us the way out!

We have wasted so much time by trying to face the fact, that unfortunately there is a problem with our perfectly healthy-born daughter. After the consultation with many doctors, they first suspected a hearing problem. As the result of this, she went under many surgeries and antibiotic-treatments, which made her state worse mentally and physically as well. The medical professionals could not find any evidence of physical abnormalities, so they choose the easy way out, the one word diagnosis of Autism! Dear Mom, please accept it, you cannot do anything about it. Try some developmental therapies, but do not put your hopes high!

It is very hard to accept the unexplainable. What does autism mean? If you google it, you will find the verdict immediately: "Autism is a lifelong developmental disability characterized by impaired social interaction and communication, and by restricted and repetitive behavior" How is it possible that a perfectly developing child changes overnight? She stops saying the words she said before; she stops paying attention when called by her name and simply forgets some of her skills she knew so well before. How can one accept that? For us, it was impossible. We took up the gauntlet!

We spent so many sleepless nights on the Internet searching for solutions, to be shortly shocked to learn that in the US, there is a totally different concept and approach to autism. A group of medical professionals and scientists are proving the crucial role of environment and vaccines in the rapid rise of autism, accepting genetics as not the single cause but a factor of susceptibility to the disease. More and more so called DAN (Defeat Autism Now) clinics and practitioners are treating children on the spectrum all over the world with different biomedical interventions with various success rates. Whichever method one chooses in their realm, the base line to all is a strict diet, especially free from gluten, casein and sugar. There is no way out without eliminating these from the diet of an autistic child.

We immediately changed her diet from a bread and butter with chocolate milk style to a much stricter one. The first items to remove were sugar, gluten and casein, but these were shortly followed by potato, rice, corn and all artificial additives. We slowly changed to SCD (Specific Carbohydrate Diet). A few days into the diet and Anna slept through the night, and what's more, the painful eczema spots that had been on her face since she was a baby have shortly disappeared. Parallel with the diet modifications we also started the DAN interventions. We spent a fortune on lab testing, supplements and to see a DAN practitioner in Germany. Unfortunately none of these brought us significant improvements.

But I knew and believed that there has to be a solution.

And yes! I cannot keep it to myself and I would like to spread the word happily, powerfully and self-confidently, that there is a solution! This year in August, I have found the presentation of Kerri Rivera on the internet. Autism is preventable, avoidable, treatable and curable."

At the beginning "Kerri Rivera rose against the wind rather than with it when, after a frustrating slew of hits and misses, her youngest son, Patrick, was diagnosed with autism nine years ago. He was two at the time. Surrounded by literally no local expertise or any type of peer support circle, she did what most mothers would do: She became informed and involved in the biomedical community. It was through the Autism Research Institute (www.autism.com), a non-profit organization dedicated to autism research, diagnosis and treatment for the past 40 years, that she learned about a specialized biomedical protocol involving a special diet and supplements, physical therapy, applied behavioral analysis, chelation and hyperbaric treatment. There was light for Patrick, Kerri's son at the end of the tunnel."

But Kerri did not stop here! As she told me, she felt that there was a missing piece to the autism puzzle. A huge piece! It shortly turned out to be the MMS piece. She developed MMS protocol which can be done at home. Following Kerri's protocol, 68 children lost their autism diagnosis in the past two years! This result is outstanding, considering the fact that this is said to be an incurable disease.

The day I saw her presentation I e-mailed her and I got an answer within a half an hour. Kerri Rivera's MMS protocol is the missing piece of the puzzle to cure autism, ADHD, asthma, allergies, seizure disorders. Even mothers of children with Down Syndrome have reported improvements with this protocol.

My whole family was in Mexico in August. We spent two months with the person, who is also a mother of a child with autism, who sacrificed part of her life to help others. For free, out of faith, humanity and love. Approximately 8-900 children are following Kerri's protocol currently all over the world. The protocol is available for everybody and can be done at home (www.mmsautism.com).

Anna is getting better every day. Although we have heard very promising sounds from her, speech is not developed yet. However she has improved a lot in the last 3 months in many other areas like mood, communication, learning ability, focus and attention span are all better and she started pointing. There were no signs of these at the beginning of the summer.

We are fully aware that there is still a long journey ahead of us, but now we know we are on the right track. Thanks to God and Kerri Rivera to guide us to recovery!

---

98. Hi Kerri,

PLEASE use our testimony. MMS kept my daughter's PANDAS under control after switching from Silver Hydrosol BUT the biggest is the PP's (parasite protocols) in combo with MMS. She began sleeping through the night, THEN, sleeping in her own room after sleeping in our room for 9 months. THEN she began putting herself to sleep for the first time in 7 years. We always laid with her--her WHOLE life--I KNEW it was NOT "behavorial", knew it was due to *something going on interally, AND NOW, we read, kiss, and WALK OUT of her room! It's SURREAL really. Seriously SURREAL!*

Also, she was a chronic chewer, nose picker. Almost GONE! Peaks at new and full moon, BUT goes away. She was chewing about 20 straws a day before PP! Mangling them! UNREAL! I have pics of the straws... cant even recognize them as a "straw" once she was done with them. CLEARLY parasites. CLEARLY on the right track. NO other interventions. Except for how the MMS PP protocol is outlined MINUS Rhompe etc.. and Neem. NO sleep intervention supps etc.. None.

---

99. *Favy is my God sent angel. He is 4 years old and since he was born he came to change lives, to make families stronger and to help others forgive. As many of your stories, everything was "perfect" (besides of milk intoleration, delay speech and sleeping problems) the rest was great, milestones on time.. Then gradually after 13to 18 month something was clearly wrong, we loose him and then the bomb!: diagnosed in Puerto Rico by a developmental pediatrician and a neurologist as PDD-NOS on December 6, 2010.*

We moved fast and start the diet GFCFSFYF no sugars.. Etc Thanks to CEA non- profit organization who help parents with kids with autism. Soon we saw positive changes, then probiotics and a natural anti fungal. Difficult days... But always seeing little good things. On march 2011 I met an angel: Kerri Rivera and we start MMS protocol!!! Then we start to see the light! We moved to FL and they diagnosed him (now I know he was having a die off when reevaluate) he was diagnosed as Autism. For me , not a big differences, still in the spectrum and he still sick!!! We need to cure him!!!

After MMS the big changes came ,and still coming!!

first from 2 to 4 hours straight per night to 6to 9 straight during night plus a nap during day!!!!! Eye contact was much better and he had less tantrums. He learned fast 3 signs to communicate. He was more happy. I didn't see more great results because I was using Mms incorrectly for almost a year (with juice, antioxidants and vit c) When a couple of months ago I started doing it right (just water and no vit c nor antioxidants etc) he started to improve again and better.. After a lot of efforts, dedication, patience and hours of hard work, with Kerri Rivera MMS protocol Favy to improved in many areas.

This is all he have improved:

Educational:

- *Respond to his name when called and say his name when ask.*
- *Recognize people: Mommy, Daddy, Sister, Teachers, Therapists, friends*
- *Name and identify some body parts: eyes, nose, mouth, ears, belly, feet*
- *Recognize some animals (Ipad application or tv) : cow, horse, duck, chicken, zebra turtle.*
- *Recognize some colors: blue, yellow, purple, red.*
- *Recognize and count 1-10 (can repeat 11, 13)*
- *Recognize and/ or use some common objects: plate, spoon, fork, bottle, chair, pants, shirt, shoes, backpack, lunch box, blanket, pillow, tv, books, some toys, ball, cars.*
- *Stack objects like blocks, books*

- * *Match pictures, objects or things.*
- * *Color independently but refuses, he can trace but hand over hand.*

Social / Emotional:

- * *He enjoyed for the first time his birthday Party, he was happy! He opened his presents and show emotions!!!*
- * *He is beginning to interact more with others.*
- * *He can follow direction of 1 step and some cases of 2. (clean up your plate to the sink and push your chair.)*
- * *He is affectionate : kisses, hugs, eye contact is better.*
- * *Wave and say bye.*
- * *Greet with a good morning or good night.*
- * *Play around and with others: chase, tickles, peek-a-boo,*
- * *Dancing and imitating some song rituals like: The wheels on the bus, If you are happy, head shoulders knees and toes, and some in Spanish too.*
- * *Throw, push, blow, pull, jump, run, walk, go up and down stairs, climb, open, close, zip, unzip,*
- * *He can watch an ABC DVD seated or lay down , dancing or repeating.*
- * *He can be seated for almost 5 to 8 minutes with his favorite books.*
- * *He enjoys to go to playgrounds, go up and down slide or swing.*
- * *He enjoyed the trick or treating this year, going house to house picking candy and wore all night his costume.*

Comunication:

- * *I think this is the area of more improvement. From 0 to almost 35 words and different ways to label, request, interact and communicate!*
- * *He can answer questions with yes or no (yeah- nah)*
- * *He signs (modified) more, all done, juice*
- * *He can use 3 words at a time (mommy water please, mommy come here, I love you, mommy ipad please, mommy hungry, eat)*
- * *Say independently—not all of the sound clear but very similar sounds.*
- * *Mommy*
- * *Dadda*
- * *On*
- * *Yes(yeah)*
- * *No (nah)*
- * *Please (peas)*
- * *All done (ah dah)*
- * *More (mor)*
- * *Water (at-ter)*
- * *go*
- * *Four*
- * *Three*
- * *Tickles*

- *Zebra (eebah)*
- *Turtle (totlo)*
- *Uh oh!*
- *Oh No!*
- *I Love You!*
- *Under*

When Prompting or Repeat:

- *Tv (tetete)*
- *Dvd (dededah)*
- *Off*
- *Come (she)*
- *Itch (each)*
- *Scratch (ach)*
- *Bubbles (babah)*
- *Bye (bah)*
- *Swing (win)*
- *Push (pah-sh)*
- *Five (hi)*
- *Nine (nun)*
- *Ten (ttn)*
- *Baby*
- *Ble (buh)*
- *Purple (por-po)*
- *Yellow (ye-yo)*
- *Chase (ch sound)*
- *Play (ay or pah)*
- *He can imitate some animal sounds like tiger, horse and wolf.*
- *He make choices between to objects . (playing, dressing, eating)*
- *Independent Functioning (he needs some prompting)*
- *He eats independently with spoon and clean up after finished.*
- *He can drink of a regular cup.*
- *With pictures or social stories he can transition to different activities.*
- *He is showing understanding of routines and rules. (dvd or toy stay home, 2 minutes and we are all-done)*
- *He can pull up and down his pants (multiple prompt)*
- *He can put his shirt on but need assistance to take it off.*
- *He can pick up and put on hamper his clothes.*
- *He can put his shoes (crocs) independently and cooperates with other type.*
- *He move furniture to reach what he wants.*

Health:

Favy still in the Gluten, Casein, Soy, Yeast, Antibiotics and Hormones free diet. He is trying new textures, flavors and consistency in a variety of food allowed.

He is drinking more water. MMS help us every time he have a cold, a mosquito bite aor nasal allergies. Is the best product we can ever find!

We are excited about all he learned, do and know during this last year because of the use of the protocol of MMS. We are proud of his efforts, but we still have areas to improve. We will continue with MMS, diet and wil start the parasite protocol with faith because MMS Rocks!!!!

We love you Godmother Kerri! God Bless you and your Family.

100. *Conversation at pick up:*

Aide: "What did you spike his breakfast with this morning? I've never seen him like this!"

*Me: *smile* "Oh glad he had a good day"...in my head...'three doses of MMS before drop off'...*

This child is going to figure out he has wings and start to SSSSOOOOAAAARRR!!!!

101. *I have a 4-year-old son on the autism spectrum and MMS has been the most effective treatment we have tried for him. He had bad eczema on his legs for over a year that I was never able to get rid of. We tried diet, medication, cream and nothing seemed to clear it up. Within 2 weeks of starting MMS it was completely gone and has not returned. My son has made great strides in the past 5 months of being on MMS and the parasite protocol. He is more interactive with all the members of the family, talking more, and becoming more successful with his OT goals.*

102. *Kerri; Thank you all for your great job. Because through the Webinar—Autism and MMS—the information has come to me and gave me the strength to start a treatment.*

103. *Hi Kerri,*

My wife and I did an ATEC on 8 year old son and it came in at 7. Wow.

We're learning so much from you about how this whole recovery thing works. The child's health takes three steps forward then two steps back then three steps forward then two steps back...but over time that one extra step forward seems to slowly add up. His pee is smelly again but, as you taught us, it's pee-tox and this is a good thing. His focus is still a bit of a challenge at school and he still won't shut up :-) but we are feeling that he truly is slowing getting better.

We've got a ways to go yet but we feel that we are truly moving forward. Thanks so much for all of the help you've given us and any help you might be able to give in the future.

104. *My son is 19 years old. We started MMS in July. For 2 months my son did not sleep. The end of August at full oral dose we started the baths. At night you could see he was uncomfortable. I don't know how we did it but we talked him into doing enemas. My husband does it. They induce him to have a bowel movement.*

Before enemas my son would have nights where you heard him walking back and forth from his bed to the toilet. In the morning I would say you had a bad night *last night, what was your problem? He would spell constipation. He doesn't seem to be doing this since the enemas.*

On Saturday 11-10 our son went to the first day of the season Special needs Ice Hockey. He is just learning. There were no problems with him about anything. In fact for the first time he put on his hockey gloves without objecting, which we have been trying to do the last 2 years. He followed directions from a volunteer on the ice, using his hockey stick to hit the puck back and forth to him and towards the goal. When hockey was over we went outside and hung out at the car and did nothing for about 20 minutes and had a dose of MMS. He did not care one bit. He entertained himself by watching the sea gulls. He was not impatient.

Next we walked over to the bowling alley, which is next door to the ice rink. He participated in special needs bowling. They have the bumpers up so the kids don't get gutter balls. My son actually threw some balls that didn't hit the bumpers. There were times in the past where every ball he threw hit the bumpers. Again there was not a single problem, incident, or signs of agitation from him while we were there. This is the first time in his life where we were able to go from one activity to another and not have an upset. He enjoyed himself.

What was really interesting was that he usually stims with a container of pumpkin seeds when he is in the car or at the bowling alley. This Saturday he left the container of seeds at home and not once did he even ask for them while we were out.

My son asks for a heating pad, which he has been doing for years. We wonder is it worms that have been causing all this pain for him? We would love to eliminate the pain, the repetitive behaviors, and the prompting through self-help and activities. He does lay around a lot. Everything he does is at a slow pace. He lacks stamina and speed for appropriate activities.

---

105. Hi Kerri, my daughter's first atec was 85. We just did it again and it is now 55! :) :) (approximately 2 months on MMS)

---

106. Hi Kerri,

I just wanted to let you know that we are up to 30 drops per 8 oz bottle and now I'm seeing some new things. He used future tense this morning (he sticks larry boys super suction ear to his window and waits for him to fall) This morning he said "Larry boy will fall." Usually when he falls he says in his high pitched voice "are you ok". Today when Larry Boy fell he said in a deep 11 year old voice "ouch". I just burst out laughing.

---

107. Dear Kerri,

In the spirit of giving thanks, I wanted to say how deeply grateful I am to you and your amazing work with mms and recovering children. I have never felt such hope for my son and such joy sifting through poop!!!

What a truly tremendous gift you have given us all...

Sending love and Thanks

---

108. My son is getting tiny bit more normal every day!!! I could kiss you!!!!!

---

109. *There was once a day not too long ago when all my son would do is scream and cry. No words at all. No communication. Today he asked me "mommy who holds up the clouds so they don't fall?" :) xoxo love that question! It means so much!! Autism is big. But God is bigger!! Don't give up ladies!! God led us to mms & to Kerri for a reason!!*

---

110. *Kerri is fabulous. She is very loving and supportive and will do anything to help our daughter recover. Using her MMS and parasite protocols have resulted in our eleven year old girl's ATEC scores dropping by half in less than sixth months. She is fully connected and much more responsive and affectionate. She herself is now motivated to succeed! We look forward to full recovery through Kerri's guidance.*

---

111. *I think we are over the initial die off hump!!! We are getting good reports from school about better focus and independence. Also, my son shampooed and combed his hair independently this morning. He even used a Q tip in his ears! I only asked him to try and shampoo by himself. He rewarded me with the combing and Q tip! Awesome mms!*

Thank you again!

---

112. *I am so grateful to have found you!! MMS here in our house is a MUST and my boy gets better by the day because of it.*

---

113. *6 months ago, my son was on antibiotics for PANDAS, he was suffering with OCD and anxiety, as well as completely distracted - like a zombie.....his teachers came out one day with tears in their eyes because my son said he feels like monsters are inside his head and they are scaring him! They were so worried about him, as we all were!*

We started MMS in April. My son got up to full dose relatively quickly and we added in MMS baths and MMS enemas and then I pulled the antibiotics—cold turkey! I was emailing Kerri at the time and was afraid to stop the antibiotics. She guided me and gave me the confidence that was needed! As suggested by Kerri, we also did night dosing of MMS. This really helped my son. Keeping a constant flow of MMS was the key.

My son is flourishing!! He is HAPPY and confident. His focus has increased greatly! Since the start of the new year, he has had great day reports everyday in school! SO many gains in all areas! His coordination and strength have improved - he can do 11 sit ups (In June he couldn't do 1) He was chosen as Student of the Month in his Tae Kwon Do school (he is now a purple belt). The best news to report is his ATEC is now a 10!!!!

Our family is so grateful to Kerri!!! This protocol has made the BIGGEST impact on my son's recovery!

Thank you so much Kerri - My son's Fairy Godmother!!!

Xoxoxo

---

114. *I was praying for a new direction to go in to heal my boy. I literally woke up the next morning with a link to Kerri's presentation in my inbox from a friend whose daughter is making beautiful gains with mms. We are on day 3 here and things are going great, I am so excited! Thank you!!*

---

115. *Yes, my son is making real progress - slow and steady but real progress. The MMS & Parasite Protocol has been very beneficial for him...that's why I am trying to stick to it very closely. Also, I have wanted to tell you that one of the best things that we have ever done for my son is the enemas!!! He is a gut kid with chronic constipation and your enema program has really improved his daily life.*

    Thanks again for all of your help and guidance—always truly appreciated!

---

116. *Hi, I'm the mother of Lizbeth Hernandez Saray Miramontes and I want to share my testimony in case it is useful to you.*

    My 13-year-old daughter started The Diet in January 2012, in June the full moon protocol to deparasite and withinin two months, she expelled a worm. This helped her regain 8 kilos of weight. (She was 10 kilos underweight when beginning the protocol) Her attitude has changed completely, from being very passive and low energy, she began to smile and be more active.

    Thank you and God bless!

---

117. *From the ATEC at www.autism.com*

    Total Score: 5

    I. Speech/Language/Communication: 1

    II. Sociability: 1

    III. Sensory/Cognitive Awareness: 2

    IV. Health/Physical/Behavior: 1

    Started at 56 score in March.

    I´m still having problems in environmental awareness, because in his mind sometimes he is Super-Hero (he wants to help to all the people in disasters, his own words). Sometimes he is eating portions like me, not such big portions but he is burning calories in the swimming classes. His meals are so healthy.

    So, my homeopathic doctor told me (and recommends me) to wait until January next year to start the PP. He wants to see the effects of MMS, Probiotics and some homeopathy that he will provide at the end of this month.

    We continue using as I said MMS, Theralac, GFCFSF diet, NAET and A.B.A therapy. I am so happy to share it with you.

    Hugs my dear God Mother

---

118. *My daughter is doing well on the MMS. Her ATEC went from 53 to 26*

    in three months. The special education teacher at her school was very impressed with how well she is doing. She told me to keep doing whatever it was that I was doing, because it is working!

    Thank you for your help.

---

119. *Kerri, good day*

    I want to tell you about the progress of my child, the treatment began in July and the progress that we have seen is:

    -He has gone from not wanting to eat ANYTHING, TO EATING BY HIMSELF, SITTING DOWN he grabs his spoon and he cleans his mouth every time he gets dirty

    * *He has stopped wearing a diaper, and goes to the bathroom by himself, almost like any other typical child.*

- *He lets people other than my wife and I hug him.*
- *He now gives hugs and has started imitating a few other things.*
- *He can now obey simple instructions that he couldn't before.....no, pick it up, get down, get up, give me your hand, etc.*
- *At the institute where he receives therapy they have told us that they are seeing great improvement in his eye contact, as he now focuses his vision more clearly on an object.*
- *He still will not play with other children, but at least he is where they are.*

Thank you for everything and we are together in this fight day after day, winning small battles everyday to win the war.

God bless

---

120. *My son was a non responder. We worked with a DAN! Dr. for 14 years. We did the DAN! protocol tirelessly with very, very little gains. Did 3 years of ABA and 2 of SonRise. Did the diet. Still do the diet. We started the MMS protocol in April of this year. My son has had more gains since April of this year than with 14 years of DAN protocol combined. My local children's hospital specialist told me to put my son in a home and forget I ever had him. What a jerk. We pressed on and I could write a book about the gains since April. My son's Dr said he had two near impossible "tough nut kiddos to crack open...one being my son." Well, MMS works. If my son can improve I know yours can too. Whatever you have to do to do enemas, and get him to drink it...do it. My son is drinking 35 drops a day. Trust me, it is yuck. But he understands that if he drinks it, it makes the autism go away and he slams it down and says, "yuck." He totally knows I am helping him and cooperates. Be encouraged.*

---

121. *Hi Kerri,*

We're now at 1/4th of a drop per oz and today my daughter for the first time EVER answered a 'Where is...' question. I was putting out the garbage and when I came back in I remembered I had forgotten to put away a black marker

and when I found it was missing, I could only hope the property damage would not be too bad this time. I checked the living room and the kitchen but could not find any traces and meanwhile my daughter had taken the photo camera

and was taking pictures of herself in the mirror. Amazingly she seemed to have a way better understanding of the thing. I asked her twice where the black marker was, and after the second time she pointed towards the kitchen and said "There."

SHE HAS NEVER DONE THIS BEFORE! I checked the kitchen and found the black market next to the fruit. The pears, melon and mango all had black circles and stripes. I was a bit overwhelmed I should say.

Thank you, thank you, thank you for never having given up your search!

---

122. *My son Fernando Latin is 8 years old and was diagnosed at age 3 and half. When I started this struggle with autism all the relevant studies were performed. We visited a neurologist, psychologist and a gastroenterologist, he began taking the supplements according to DAN! protocol, but the list of pills he was taking was increasing and my boy was restless. Then I went to a homeopath,*

the treatment worked a little but it was so expensive I couldn't continue, it is needless to say how much money and time I spent on appointments and tests, plus the hyperactivity problem was growing each day. Until God put in my path an extraordinary friend MARIA CAMPERO and she talked to me about a foundation in Port Ordaz "VENCIENDO EL AUTISMO" FOUNDATION (Carolina, Yamileth and all that beautiful team) they brought Kerri Rivera to lecture here in Venezuela, on 04/02/2011. I will never forget these words AUTISM IS PREVENTABLE, TREATABLE, AND CURABLE. A new hope that a mother's heart never looses… In that conference she also talked about MMS and its benefits I was lucky Kerri evaluated my child, I started giving him MMS plus some supplements and have won this since:

- *Better pronunciation, for example he used to say Dowg and now he says Dog.*
- *He obeys orders.*
- *Spends more time sitting.*
- *Evacuates normally with no bad smell.*
- *He stopped biting his clothes.*
- *He stopped making noises like: wiiiii yiiiii.*
- *He stopped playing with his hands.*
- *We go somewhere and he is relaxed.*
- *If we take a picture, he looks at the camera.*
- *He is more aware of his environment.*
- *He is improving a lot and really fast with his ABA therapy*

These are all the benefits I've seen with my son after starting with the MMS, I know there is a lot to do but know a have real hope. Some advice for parents that are starting this road: please accept what is happening, inform yourselves. I always think that to get your children through this you need the four-legged table:

- *Diet*
- *MMS, Supplement treatment*
- *Therapy*
- *Help at home*

I've always asked God to give me enough wisdom to help my child and to put me in a direction were I could find people that can help me, and believe me he has listened: Venciendo al Autismo Foundation, Kerri Rivera, my sons therapist Milagros Alcanta, Danny her teacher-shadow, Maria Campo, a woman not only committed to her son but to all of those who she can help and guide me, including Marilyn Aparcedo and her team. All of them are my bases to keep going and as Kerri and Carolina say: This is an endurance test and there is no giving up!

I have nothing but thanks these wonderful and professional people, Thank you!

Norkis Pinto, El Tigre—Venezuela.

---

123. Alexander was a normal baby until he was 6 months old, after that he suffered a change that, when we got home from work it was like no one came in, he was very uneasy, we talked to him but he didn't seem to care, first we thought that he didn't listen, the pediatrician and neurologist recommended hearing tests, *we did them and his results were normal. The pediatrician also recommended a psychiatrist but I thought it was very early for that so I took him to a psychologist, but he didn't diagnosed him, instead he referred me to a psychiatrist specialized in autism, and with a simple test he confirmed the suspicions: your child has autism and this has no cure, take him to special classes and therapy. I quickly signed him to a special camp and school, but they they just took my money and my sacrifice to travel 60 kilometers daily, they didn't do what they promised, they charged me triple just to give me a diagnosis and I believe he didn't even receive therapy. In my despair I went to the internet, I made an email account, a facebook page and started to look for parents that were going through the same things I was, then I contacted a Dominican mom living in Puerto Rico and she told me about Kerri Rivera and the diet. She told me that Kerri was the person to go to about this and Kerri answered immediately and asked me if my boy was on the diet and I said he was only 50% and she told me that if I wanted my boy to get better I had to do 100% so I wrote her back when I was doing the diet entirely. She gave me the first three supplements MMS1, THERALAC AND QUINTON WATER. Everything has been so difficult to get but if you persevere you get want you're looking for. I got the MMS1 but I was scared because of the strong smell of chlorine but I gave it to him with faith, I took it and my youngest baby girl started taking it. She had had a cold for about a month and it disappeared, Alex started to get better in every aspect but the biggest changes began 15 days ago, since I give him his MMS1 treatment. I start at 3 o'clock and finish at 12 at night. On weekends I start at 1 and I complete 12 doses of one drop mixed with citric acid and give him that daily. My 3 year and 4 month old baby boy is saying his first words. He is more connected, pays attention, he is aware of what happens to him and he is more loving than ever. I am so happy; I thank God, Kerri Rivera, Zeneida, Cynthia. But I mainly thank MMS1, because with a supplement so cheap, I'm getting my son back, the one that Autism wanted to steal from me.*

---

124. Juan Eduardo is 9 years old and he was diagnosed with Autism at age 2. It has been a long road in which we have tried everything. 7 years after trying and failing, in April of this wonderful 2011 we started in the right way. MMS came to our lives. Juan Eduardo was a self-centered boy and with a lot of fixations to objects. His improvement in school has been slow, but in 5 months he has improved what he improved in 5 years. MMS in our lives has been wonderful, despite the hyperactivity and lack of sleep at the beginning of the protocol, the life of Juan Eduardo and our lives have changed drastically in a very positive way. He will start regular school at the beginning of next year. He is a happy boy, he sleeps all night, he talks a lot more even if there is a long way to go, his quality of life is so much better. He shares with whoever is around him, a lot of times he surprises us with his qualities. He has adapted to the MMS in a great way. We took the panel viral test and the results were amazing, there was no virus. When I saw the great positive effects the MMS has made, I started to do protocol 1000 for maintenance with 100% success. Last year I suffered from several episodes of flu in which I had to take antibiotics, but this year I feel excellent, Thank God and Kerri and MMS I haven't been ill. I thank God, Kerri for putting you in our lives; I'm sure he has given back everything you selflessly have done for everybody. The smiles and looks in our children's eyes are priceless. Thank you Kerri and Jim Humble. A big hug.

---

125 Yes, I have increased the drops. Honestly, since we last spoke, he has had some of his best days...super happy. He actually read a book on his own on the way to school this morning. Seems very calm. Thank you.

126. *Hello Kerri! I have not written you in some time. I must tell you I have already been using MMS for two months. We have seen a lot of improvement. He suddenly speaks, says single words. If I sing a song or the vowels, he tries to imitate me, although it is still not very clear. But he tries to imitate. He smiled back at me when I smiled at him. And so those are several things. Tantrums are also less.*

---

127. *She is doing excellent! Every day we see small but important progress. I am not sure if she has noticed the changes in herself, the best will be when she starts school and classmates and teachers can give me their opinions. Family members have also commented on the changes we have seen in her.*

She is also answering questions about what she wants... With yeah, nah or the sign for all done with and then says dddon!

Now she wanted to see Mickey and told me ttttttiii and I showed her the movies and she said "ickey!" ;) We are communicating!!

---

128. *We are a family that lives in a country where living is not easy at all. The maternal death rates and child deaths are very high, and there is hardly any chance of getting access to special medical treatments and therapies. Our son started to show signs of autism since he was 2 years 8 months old. He had begun speaking but at that moment he stopped talking, he started to show no expression with his eyes, to roll around trees, to scream and to tantrum, and to not allow contact with anyone. Little by little he started to be very hyperactive and to have serious sleeping problems (he didn't want to wake up and he could not go to sleep at night).*

The start of my son's autism went along with colds, severe coughing and infectious diarrhea. Our son's teacher had always had excellent reports about our son's behavior, but since this severe cold with synovitis in his hip, the transformation begun. Since then, the awful diagnosis and the absence of guidance led us to an abyss. Our son presented total absence of self, almost no language, hyperactivity and many sicknesses. 6 months went by in which he met with a real parade of doctors and therapists that gave us bad treatments, bad diagnoses and almost no information, our life became a living hell. We went into a state of denial in which we didn't want to see anything on the Internet regarding Autism. In that time our son had been diagnosed with severe sinusitis, complications with his adenoids, and limitations that he developed because of his hearing capacity.

By the end of the year 2007, I alone broke the pact I had made with my husband, and started to search the Internet and found Yeroline Ruiz's page where she commented about the biomedical protocol through which she had gained her son back in months. Little by little I tried to convince my husband, who at the beginning was completely reluctant to the possibility, but by December 2007 we made our first order of supplements and quelators (magnetic clay from the United States). The supplements took forever to get to us and when they arrived we gave them to our son without any clue or guidance and hardly any diet. The results were horrible, he got worse and worse, and this lasted about 8 months. During this time the therapists gave us a terrible prediction about our son's future. Our family problems were also getting worse and the only guide we had was Yeroline and the Curando el Autismo foundation. Thank God we didn't give up and we passed the hard times.

We eliminated some of the food that is forbidden in the protocol and we started to use Enzymes. Our son started to improve, his health got a lot better and we stopped visiting traditional doctors and I decided to take care of his treatment, the process was not easy because there aren't even the basics for the protocol in my country, from the flour to the milk, everything is really hard to get. Obviously a DAN! doctor or supplements are unthinkable. However even if his health had improved, the Autism symptoms were still present, the speech therapy did not help and sometimes even made it worse. With a lot of effort we brought Rosa Dominguez (Tomatis Therapist) and we begun applying this technique to our son. The economic effort was very big but the results were worth it, he was more in control of his body, the clearest sign of this was the control of his sphincter that happened almost magically. His language also improved even if he still didn't use it socially, but little by little we verified that our son had no sign of retardation compared to other kids his age. Even with the improvement, the tantrums, frustration and limitations of his language remained, we decided then to make a new effort and traveled to Panama to the Stem Cells Institute to make a stem cell transplant.

Our debt was huge, and despite the effort our baby showed two contrary signs: a positive one that was that our boy was completely connected to his environment (he is never outside of the world anymore) and a negative one: he became aggressive. He had never shown aggression, auto-aggression or violent behavior, but from the moment the anesthesia was applied these began.

Our child started hitting himself when things didn't go his way and he bit other people out of frustration. We remained on our path with despair because we could not see the light. We tried hyperbarics for 70 days in a row, eqinotherapy, and others. In 2011 we came across Puerto Rico's CEA conference and we found Kerri's topic and the SCIA topics very interesting. We decided to do the SCIA tests and we confirmed that our boy also had virus and an inflammation even though his immune system didn't seem very affected. Because of our country's limitations we couldn't complete the SCIA tests but then we had a lead on how to start a new journey. All we needed was a doctor that could apply the SCIA protocol.

But then there was a miraculous day in which we saw Kerri's talk and hope grew inside us, we contacted her immediately and she answered immediately too, with good will and all the indications as to how give him MMS and how to apply the protocol. After two weeks we started seeing a change in our son. Eye contact was way better; he speaks fluid sentences and gives structure to his words.

We are now three weeks into the protocol, we can see almost no aggressions and tantrums, we teach him letters and he recognizes them, reads and writes his name (he does it with some difficulty) his receptive language is %100 active, he is very loving, specially with me. (His mom), he hugs me and kisses me and tells me he loves me. We know we still have a lot to go but I'm certain that we will make it. My son has now Borderline Autism; his connection with the world is total. We are still thinking about doing all the SCIA tests but just to find out our child is cured. The light and hope that Kerri and the MMS have given us does not compare to anything. Thank God! Kerri is a blessing in our lives!

129. *This email was after an ATEC drop of 64 to 44:*

This is truly AWESOME!!! He lacks in the "Speech/Language/Communication" area the most!!

I honestly thought when I was filling this ATEC out that he would have regressed because I just thought he might have...it seems everything else we have EVER done it is always too good to be true! It actually is not this time!! Praise the Lord Jesus Christ! \o/ I even had my oldest daughter give her thoughts on the questions too so that I doubled checked myself regarding his behavior etc...you know to make sure I was not out of touch! :)

We definitely have a ways to go, but I have never had my son at this level of 'awareness' before! We are doing RDI (Relationship Development Intervention) and have been since Feb. 2011...he's made great gains with it, but he is FLYING now only because of the MMS!!

~Melissa, IN, USA

---

130. *Hello, my name is Silvia and I have a 5-year-old son named Ricardo who was diagnosed with Autism 2 ½ years ago. From that moment he has been on a gluten and casein free diet and a therapy routine that help him day by day. Three months ago I met Kerri Rivera and the Venciendo el Autismo Foundation, and started giving Ricardo MMS. From that moment on he has improved significantly, his language is better and his behavior is a lot more controlled, plus with the biomedical treatment he goes to the bathroom regularly, this makes me very happy because he was always constipated.*

Silvia Morales — Caracas.

---

131. *Since I was a baby I was a very sick child ... I remember I had many gastrointestinal problems, I made my mom's life miserable with all the diarrhea and vomiting ... I couldn't gain weight and I had no appetite. All this accompanied me for many years; the diarrhea became chronic constipation, fluid retention and dry skin.*

All of this without knowing I had a serious problem, until I gave birth to my first child. The constipation was a nightmare, my baby got ill, when I fed him breast milk he would get a rash, and then he had convulsions for about 20 seconds, when I fed him again the same would happen but now the convulsions lasted for nearly a day. The doctors didn't know what was going on either. In one of my researches I ran into a page that talked about Autism and Candida being one of the main causes, this is when I find out that my son had chronic candidiasis and that he got it from me when I breast fed him. I tested my child and myself and we both had Candida, and I have had it since I was a baby.

One day I heard about the existence of a woman named Kerri Rivera who is devoted to helping children with Autism and I contacted her and she gave me all the help to treat my child. I will be forever grateful. She talked to me about the MMS and how to give it to my son. I also started taking it and in a matter of days I had a white layer in my tongue, it was the Candida getting out. I have gained my energy back, the headache I had in the mornings is gone, I feel vivid and almost all the Candida is gone. I've been with MMS for a month and I've never felt so satisfied with a treatment. This simple and yet powerful remedy has given my health and family back and with this I can assure, by my own experience that MMS works.

132. *Hi Kerri, I want to tell you that Erik has started with the speech therapist, and psychologist, when she finished the session with Erik, I asked if she thought that Erik could still be diagnosed with autism. She looked me in the eye and said, autism? Are you sure that he was correctly diagnosed? I found her the forms and she told me today Erik has eye contact, he socializes, and is cooperative. She said he does seem small for his age, and that we were going to have to work on strengthening the muscles of his mouth and the tongue as well because they are very week. She said that not chewing would affct the development of one's language, and Erik has only been chewing for 8 months, which started after we did the chamber with you in Mexico. That was the answer she gave me, and that's something, the fact that she told me that this is not autism is really something, even though she doesn't want to contradict the diagnosis they gave two years ago. The truth is, I am so glad he has come to improve, and that is since you KERRI have started to help my child. It's been a year since we started with the MMS protocol and the improvements have been incredible, he still lacks language as he mispronounces many words, but the worst is over. You can publish this if you want, thank you very much for all your help.*

Kisses

---

133. *We had first formed stool at 4 drops. It was so inspiring. Since then somedays we have formed stool, some days we have loose stool but I relate this to detox - I can clearly see his gut healing. His expressive speech hasn't changed yet but he obviously understands much, much better and is able to follow complex comands like "come and give me one teaspoon from the drawer" or "go and put this in the dishwasher" or "wait for daddy to get out the baby from the car and then you can lock the door and put on the alarm". Things like that, that were unthinkable before. I hope he will go beyond his few words soon and will begin to talk.*

Although speech is the thing that interests me most of all, perhaps the most impressive thing that MMS brought to us all of a sudden is the sense of smell - our boy never seemed to feel any smell, good or bad, in his entire life. He got this sense a week ago. We are thrilled - something is waking up in his brain, perhaps some pathogens in some part of his brain or in his nose or whatever died and now he is able to sense a smell. Things are getting moved.

Thank you Kerri.

---

134. *My son is 8 1/2 years old. I have spent six years and well into six figures to help my son. While I would see gains, nothing was really moving him forward. Three months with MMS, DE and ocean water; the junk that is coming out of him is both horrifying and thrilling. I think he is finally starting to feel better, and because he feels better he is more with us. He is trying so hard to speak and everyday he is saying at least four new words. He also watched a movie and laughed at a funny part!*

---

135. *We started MMS 68 Days ago and my son's ATEC has dropped from 50-23... Now that's a MIRACLE!!! He is So much more "with us" and I'm seeing improvements daily. He is just so much more fun to be with now:) He did have a plateau, but is back on track. We have only done 4 enemas to date, but they made a big difference! Baths do as well:) I can't wait to see what he is like on his 4th birthday (still 39 days away).*

Kelly, CA, USA

136. *Is it just an amazing day or is the MMS already working? Its just day 1! I know people say that once your child starts talking, they never stop, but holy cow... Today in the grocery store, it took me 3x's longer to shop because he was talking about everything he saw around him and needed a response on all of it from me! So unlike anything we have ever experienced with him before. Could it really be the MMS already? Also, potty training has been going well (slow & and steady), but today, he didn't need much prompting! Many times, he just stopped what he was doing and ran to the bathroom to go all by himself! This is amazing, because he never stops a preferred activity to go potty! When i thought it had been too long since he went last and said "its time to go potty." he just ran in there and peed, washed hands etc. No tantrums or weight dropping, he just ran in and went! God is answering my prayers! :) I'll keep you posted on what happens tomorrow!*

---

137. *You know Kerri, I had to email you directly I waited until today to retake my son's atec...just did his first Parasite Protocol and did the 72/2 hr this weekend, so waited a few days to pass by before we did...so this atec was based SOLELY on this past monday, tuesday & today. I got an 11, hubby got a 13. so average: 12. (he was 32 before MMS, then 27 after 3 weeks of MMS...now 12) I had to email you to thank you b/c well...because. What is there really to say :) cant think of the right words really :) thank you?? not really enough if u know what i mean :) ...But to think i was going to skip your presentation at A1 b/c I thought it's too good to be true. But you caught my attention when you started tearing up as you got up on stage :) you were the only person/speaker to show emotion like that. AND have NOTHING TO SELL ON YOUR TABLE :) You were there only for our children...getting nothing back in return! :) I know I've been emotional, but I'm prego and my sons getting better so cut me some slack :)*

I'm SO grateful for all you do Kerri. If there is something I can do in return, Please let me know. I know you have a lot on your plate. You have a heart of gold; such a giving, compassionate person. a "rare-ity" (this word is in my dictionary!!) You & Patrick are always in our prayers. I seriously want to go visit you in Mexico w/my family so my son can meet you when he's recovered. I told my hubby & he's up for it hehe :)

Anyways, long email but really just wanted to let you know how well he's doing and to 'thank you'. It blew my mind after I got the results. He still has issues in socialization and getting his vocab/speech up to his 4 year old level. I think much of that will change as he learns English better: he'll interact better with his peers.

Thank you Kerri from the bottom of me & husbands heart :) You are loved & covered in prayer. :)

---

138. *We started to see a setback in January with our 1 year 8 month old girl. Until this date she had had a normal development, like her sisters (she is our third child) but then, she stopped talking, she just screamed and twirled. She would twirl like 20 times a day for no reason until she got dizzy and she fell to the ground. She didn't look at anybody in the eyes and could be behind a curtain hours comparing her toothbrushes; she wasn't hungry nor asked for her milk, we had to push the food into her mouth so she would eat it. I was desperate so I went in to a forum and a friend from Venezuela told me to look for Kerri Rivera in my country so I did. She immediately answered and gave me hope, since the*

three doctors I had seen before told me that Autism had no cure, that all we could do is to teach her how to survive and be a little bit more independent.

I found my hope in Kerri, I read the testimonies on her page and sent her a message that she answered right away. She told me to do the diet, remove milk and everything else, I went to her clinic and within a week of the diet Abby could look at me and smile (she had stopped doing that long ago) When I went to her clinic Autismo2 in Puerto Vallarta she looked at Abby with all the patience in the world, she gave me MMS, the supplements and all the hope in the world. Everything was new to me but I had faith that I was in the right place and from that moment on, while always counting on Kerri's advice, my baby girl started to get much better. Her first ATEC was 95 and a year and a half after it's a 15. My girl now smiles, talks, dances, she obeys and stopped screaming, her only tantrums are of a normal girl her age. I did hyperbarics and am still doing MMS, supplements and deworming her. She is now diagnosed with Pervasive Developmental because the Autism symptoms are gone. She doesn't run from one place to another, she plays, looks for other kids to play with and has friends. The only thing left is for her to establish a conversation, and to put together the words to make sentences, but I know she is going to make it.

Once she sat down on ant hill and a bunch of ants bit her, we had to go to the hospital and the doctors gave her cortisone and she was seriously ill, now when a bug stings or a mosquito bites she tells me where it bit her, and she asks me to apply a calendula ointment that I use for the mosquito bites. She sets the table and can eat by herself, she doesn't use a diaper anymore, we can go shopping or to parties and she is well behaved, there is no more tantrums or fixations, this is wonderful! I know there is a long way to go, I've been in this fight for a year and a half, but with KERRI RIVERA'S HELP I will rescue my baby from autism, even though some say that Autism has no cure I know it does. Kerri has been a blessing for our lives and I thank God for putting her in my path.

Thank you Kerri, I have no way to repay what you have done for Abby.

---

139. Our 10 year old son, Ben, showed symptoms of autism since he was an infant. Until he was 6, he never connected normally with family or peers. As his mother, I ached for a hug, to be called "Mommy," or for a lingering look of love. I never got them.

Until he was diagnosed with autism at age five, I was utterly befuddled. What had I done? What was wrong with Ben? Why didn't he want to play with other children? Why did he drool endlessly, laugh constantly for no reason, and bolt from play dates and parties with no warning? Why was he constantly lethargic, to the point where we called him "the playdough boy?"

Ben was always happy, dwelling far from us, in his own perfect little heaven. My husband and I were depressed, even despondent, despite attempts at gluten-free, casein-free diets, ABA therapy, and many supplements, because we saw no substantive and lasting changes in our child.

Finally we found the Son-Rise Program®, which brought Ben back to us. After three-plus years of a mostly full-time Son-Rise Program®, Ben became highly interactive, engaged, and interested in his peers. That alone was a palpable miracle. As we say in Hebrew, Dayeinu! That would have been sufficient. But we constantly experienced regressions back into autistic symptoms. For no apparent reason, and despite endless biomedical interventions, including the DAN!

protocol—to the tune, I might add, of tens of thousands of dollars, multiplied over four to five years—Ben would suddenly revert to autistic behaviors, and we would lose contact. He became once again non-responsive, uninterested in family or peers, and seemingly unable to connect. Only the day before, he had been totally connected.

After being on the SCD and GAPS diets, and finding even them ineffective to alleviate these regular and devastating returns to autism, we were advised by Dr. Campbell-McBride that it sounded to her as if Ben had parasites. A friend of mine who was also a Son-Rise mom had mentioned to me that she and another Son-Rise mom friend of ours were trying something called "MMS." When I heard the words for which the acronym stood, I gave an internal scoff. "Master Mineral Solution? Is this a joke?"

I can tell you, in all seriousness, that now, five and a half months into our MMS autism protocol, MMS is definitely no joke. Since starting MMS, we have seen nothing but progress in Ben. We are still doing GAPS, but avoiding foods we know Ben cannot yet digest. Ben's ATEC score has dropped from 43 when we started MMS to a startling 20. We are seeing sustained, natural, unsolicited and consistent eye contact, like never before. Ben is consistently responsive, certainly on par with most 10 year old boys. He is playing hockey in our driveway with friends. He is solicitous of others, and compassionate when others are hurt in any way. He is funny, expressively loving, and eager to please and be loved. It makes me cry to write this. I wanted this so badly, and now, with MMS leading the other interventions, I have what I prayed for.

We are not perfect on the MMS. Ben is in his first year of school post-Son-Rise, and dosing during the school day is not easy. But we are tremendously hopeful and excited.

I truly believe, as Kerri Rivera has often said, that parasites are the missing piece of the autism puzzle. Like so many other warrior parents, we have done everything. But everything minus one was not enough for Ben. Now, I think we truly have the tools, and it is only a matter of time, faith, and love, to fully and permanently recover our beloved Ben.

---

140. Caitlin has been on the MMS protocol for 3 months now. Caitlin is now off her 100 plus supplements a day that were the glue holding her together so to speak, with no regression. She is happier, more affectionate and focused. She no longer has a distended belly. She used to have terrible smelling gas on a daily basis and very foul smelling bowel movements. This is gone! She has increased muscle tone (has a diagnosis of low muscle tone and bilateral hip anteversion). She has been seizure free as well! She continues to make slow but steady gains in her reading and math skills at school. She isn't conversational in her speech yet but can comment on things and express her wants in longer and more elaborate sentences. She is falling asleep faster and sleeping longer.

---

141. Eczema!!

At last my son (4 yrs) is living now without eczema, he was born with severe eczema all over his body, we used every allergic cream and med and even the magical Dead Sea Clay but it didn't work, but now after using mms and pp (parasite protocol) for 2 months... ITS GONE!! Thank you MMS!!"

Thank you!

---

142. *This is the story of our son who is 4 years and 9 months old today. Our story is a desperate struggle to defeat Autism, the same struggle that a lot of families are going through to free their sons and daughters. Guillem started to have ear inflammation and laryngitis when he was a few months old and we medicated him with antibiotics, he had his vaccines according the vaccine calendar, and by the time he was 9 months old he was showing signs of Autism. He would put his fingers in his throat until he choked, he would hit his head on the wall and he was always mad, his tantrums were frequent, longer and more intense, he started to look at the lights and to twirl with no sense, he showed less interest in people day by day and he would get really mad if someone said anything to him. He was hyperactive, couldn't stop running and going up and down the stairs. The nights were terrible too, he didn't sleep well and woke up screaming as loud as he could plus he could not say a word.*

My father and my brothers blamed me for this; they said that my boy wanted to dominate me and to get my attention. I had a hard time recognizing that it wasn't this, that my boy had something else. Once I accepted it I spent hours and hours reading on the Internet, and I read about the gluten-free diet and that was our first step. When Guillem was 2 and half years old we changed the diet and it worked. Guillem started to respond to orders, there was less screaming and his first words appeared. Three months into the diet we contacted Kerri, this has been a key moment in our history, because she has been our guide to get our son out of this long tunnel. The first thing she did was to check what our son was eating, I thought that I was doing a perfect diet but I wasn't, there were some foods with sugar, soy and additives, the next thing we did was to talk about the supplements and MMS, but I was very scared to use it and it wasn't until three months later, the day Guillem turned 3 that I started giving it to him. Now we have been using MMS for a year and 9 months. We give him MMS daily and every weekend we can but minimum one weekend a month we do the 72/2. His improvement was amazing, his language got better, his dressing skills, he learned how to use the bathroom, his sleep was normal, and the screaming was almost gone. The next step was to start with the MMS enemas, every enema made Guillem more alert, more present, we started with the enemas 4 months after starting with the MMS. We saw that the enemas expelled a great amount of biofilm and the more he expelled it, the more abilities Guillem gained back, I saw the importance of healing the intestine and that has been my obsession since.

The next important step was the sessions in the hyperbaric chamber, his first sessions were at age 3 and 9 months, and the changes we saw were mainly in the obsessions he had, he paid much more attention to everything, his social skills were very affected but after this he made his first friend. Now we do hyperbarics with seawater every three months. Another piece in the puzzle were the parasites but with Kerri's help we've been on the protocol against parasites for 7 months and every deworming cycle our son improves. I know that we have to keep fighting but I also know that we are closer to the exit. Now Guillem sings, he plays with his brothers, we go to the movies, we do puzzles, we paint, and he is very happy, he has learned to spell his name and he walks joyfully down the street telling you about his day. He goes to school, plays football and more importantly, we are a family again.

For all of this we are deeply thankful to Kerri, because she has always been there for us, without Kerri and MMS our story would be completely different, so we owe them EVERYTHING. I know that we will someday say Guillem is cured, and all the other children with Autism can say that too.

UPDATE: As of December, 2012 Guillem no longer has a diagnosis of autism, here is an email his Mother sent to Kerri when she knew he had recovered:

> *KERRI!!!*
>
> *My son has an ATEC of 10!!!!*
>
> *I have it repeated several times because I did not believe it...*
>
> *I have copied it below...I'm going to have it framed!*
>
> *The truth is that this Christmas we have enjoyed our whole family, we've been to the Zoo, to the fair, and during family meals he was very well behaved and enjoyed the Magi and the magic of Christmas. Christmas last year was totally different. For all this we give infinite thanks! There are not enough words to tell you how we feel! Without you our story would be different. We will continue working to get to zero!*
>
> *A big hug!*

---

143. I started with MMS on April 2012, I was afraid but had a lot of faith. I did the ATEC for my son and it was 92. He could not use the bathroom alone nor say a single word. The day I started I thought there was nothing different, but when we were at the beach on vacation I noticed that when I called his name he would turn, and come to where I was. All this with one drop! Before that day I always had to stand up and find him so he would pay attention to me. He wouldn't look at me but he would listen to instruction. Days went by and when we came back from the beach he went straight to the bathroom… I couldn't believe it; I sat down and asked my self WHAT IS THIS? What happened? And I silently thanked God and Kerri. This was decisive for me to continue. After this he improved day by day, after 5 weeks his ATEC had gone down to 76 points.

I made a few mistakes at the beginning because I didn't know the protocol very well, and wanted to rush things. Again, Kerri with her infinite patience and love for others led me to the right path, and I started to see more, way more.

My son started writing, he knows his letters, he reads some words (he has memorized them) he is great in the bathroom, he listens, his eye contact has improved significantly, his last ATEC was last month and it was 60 points. I know we have a long way to go, but I every month there is improvement and even though there are some bumps and setbacks the good things overcome the bad.

My son has also started saying words, names of movies, he can say over 100 words (names of movies or things he likes). Some will think it doesn't mean anything to know the name of a movie but for me, it is to know how my son's voice sounds and that, is priceless. Now my next goal is to hear him say "MOM"

~Myrna Sterling, Mother of Gianmarco, age 5.

Myrna is the president of the GM foundation for Autism

---

144. My wife and I have always been fond of traveling, getting to know different cultures and people, this is why we had our little one we decided t o keep traveling but to adapt to his rhythm.

When he was 9 months old he went on his first international journey. Everything was perfect, he was the happiest baby on the plane, he played with the people in the seats behind us, the stewardess wanted to stay with him to play, all the plane ride went along perfectly.

Something happened between his 15th and 18th month, his smile was gone, we no longer had happiness in our home, only nerves and less language. Maybe the excessive vaccines were destroying his immune system and leaving the door open for parasites to take hold.

When he was 18 months we went on a second trip and it was an absolute nightmare. He wouldn't stop crying and screaming on the plane, he didn't want to play with anybody. We spent a few days getting to know this new place while our baby fell further into this abyss in front of our astonished eyes.

Something was wrong, and after an episode of auto aggression we knew that this was not normal. After watching a couple of videos on the Internet we started to understand, and we went to a psychologist who didn't give us a diagnosis because our son was so young.

Later on we went to a neuro-pediatrician who also used the excuse of our son's young age to dismiss us, and finally a last doctor who didn't explain anything either.

Not even our family listened because they thought we were exaggerating. We were left alone and our biggest ally was and still is the Internet.

After the medical failure and their "anti-diagnosis" we took the best and most important decision of our lives, that was not to listen to any of the diagnoses, or to wait another 6 months to be called by the neuro-pediatrician again. We started down this road without an official diagnosis but with all the symptoms and behaviors that define autism.

We started with the casein, gluten and soy free diet with no experience on how to do it and our baby suffered awful withdrawal symptoms. We couldn't believe what we were seeing, his nervousness and aggression took us to our limits. After a few days on the diet his tantrums went down little by little until he was stable. But we needed something else because everything was out of control; this is when we went back to the Internet.

After three months of false doctors and pseudo medical experts we found Kerri Rivera.

She gave us hope, and filled us with confidence, but most importantly she was clear with us from the beginning. Everything she told us was logical and everything made sense as to why it was done so we trusted her without a moment's doubt.

He got better and better everyday. Kerri told us how to do the ATEC and what it meant. Our first result was 57 points when he was 2 years old, which was very high for us because of his young age. We have been doing everything Kerri suggests, improving the diet, and using everything she recommends, and the results have been spectacular, right now he is 2 years and 10 months old, his ATEC is 8 and he is doing great. Our goal is to have him at 0, and I'm certain that once we free his intestines of all the parasites, he will be a strong, healthy and happy boy.

He doesn't have any behaviors like the ones he had one year ago, now he smiles again, he talks and asks for things, he plays a lot and he is happy.

This was possible thanks to his Godmother Kerri.

Kerri, you have done and given us everything in exchange for nothing, and that is your defining quality as a human being and as a person.

Every day you give hope to all that YES WE CAN defeat Autism and now we have a lot of puzzle pieces to complete our puzzle. We may find a new one soon because there are a lot of people investigating and that makes us feel alive, to fight against the entire circus that has sprung up around this problem.

I would recommend that if anyone is not seeing progress in their children, to come to Kerri, and try everything she says word for word. She has done it all and has the best investigators and doctor on her side. The ones that aren't intimidated by the absurd laws of the upper echelon, those who only want our children to be sick all their lives so they can sell medicine to us.

We will keep up the fight.

145. *Hi Kerri, I just got the third MMS Autism newsletter, and I tell you it couldn't have arrived at a better moment. For the last few days my nephew has had a strange infection, he was hospitalized and the doctors couldn't figure how to fight it because it was resistant to many antibiotics. I told my brother-in-law about MMS and he started using it. After two days my nephew was healed, the doctor asked me for a little so he could examine it, and his answer was that the way MMS functions is amazing, he couldn't believe that such a simple and powerful product hasn't come out to the public eye.*

146. *My husband and I were on the couch having our morning coffee and my son came bolting out of the room and ran up to my husband's face and said..."Oh Hi Daddy, I'm back!" And then ran back to his room...this is our once in a while "word" little man. After 3 non-progressive PPs (parasite protocols) the 4th one was a charm. A nightmare, but quite an eliminator... Lots of Worms Gone! And he is slowly coming back...we are seeing it in fact he is even reassuring us that he "is back".*

~The previous email was accompanied by an ATEC drop from 95 to 35 in 6 months.

147. *Dear Kerri,*

It's a pity I don't speak English and that's why I can't write you on my own. Currently, a lot of good things are happening to my son (31 years old). I have followed all your advice and as a result he has completely calmed down. I have learned to prepare CDS at home with the help of Jim Humble's video. The CDS is a 600 ppm solution; my son drinks 30 ml per day with the feeding bottle method. I suppose this is the daily dose for a person of his weight. We are past the third PP and preparing for the fourth one.

Unfortunately I won't be able to attend the congress in Prague, since I can't find anyone to look after my son. If it were in the summer I would risk going by car and taking him with me.

I am very grateful for your attention to our life and progress and for your help in curing my son. God bless you for helping children with autism by sharing your knowledge and experience with the world. I will try to give a regular account on the progress of my son. I have no doubt he will be cured, too.

148. Three more tiny little gains on our step by step path to recovery....yesterday Nick got a haircut and did not cry at all AND was relaxed enough that it was the first time it wasn't like a sheep shearing, he actually got to get a little style (so cute!). Also, he was doing some pretty terrible screaming in the car in the parking lot at Whole Foods while I tried to find a parking space (I wanted to scream too) and I let him know he scared me. When we got into the store he spontaneously said "I'm sorry" -total first! Lastly, He has requested a hug from me three times recently - HUGE new thing and I love it. Thank you MMS and Kerri.

---

149. Thank you Kerri. For all of your help, answering my emails, and for all that you're doing to help all of us, help our kids!!! I was at a breaking point. Nothing was helping her anymore, her organs continuing to get worse, hadn't grown in 4 years, and had become Jeckyll/Hyde this past 4 years...A violent, raging Hyde being increasingly present more and more each year, each month. I knew something had a hold of her all these years. And it amazes me how 2 endocrinologists, 3 pediatric GI specialists, and many other doctors had no clue.

Thank you for ALL you are doing to get the truth out there. You are an angel!!!

Merry Christmas - xoxo

---

150. Puerto Ordaz, November 4th, 2011

My name is Carolina Moreno and my husband is Rafael Colmenares, we are the lucky parents of a little 6 year-old whose name is Ana Victoria, she came to this world to give us the world's greatest lesson, through her we have learned the real value of life, to be steadfast, and brave. We learned that it's our job to fight for our dreams if we want to accomplish them, and over all we've learned that God is who holds us up and gives us the strength and tools to move forward.

My journey with Autism began the 27th of march of 2007, my daughter Ana Victoria was 23 moths old, her initial development was normal, but little by little she stopped talking, she didn't understand anything, she didn't miss her parents, she didn't play with other children or even her toys, she didn't like to be kissed or hugged, she acted as she was deaf but we didn't know that all this were symptoms of autism. It wasn't until the day that we went to a neurologist in our area, that someone told us that this was Autism, an incurable condition, and that our daughter would have it all her life. It was a very hard moment for us; all of our plans to be a happy and healthy family went down in a matter of hours.

As parents we didn't want to give up, after recovering from the horrible news, we began looking for information on how to help Ana Victoria. In our country of Venezuela there were 4 specialists in Autism and they were all using the gluten and casein free diet, vitamin therapy, as well as expensive tests performed in the United States to check candida and bacteria. Thanks to them I learned how important the diet was to get Ana back from Autism, without it, recovery would be impossible.

We did some testing through Great Plains labs, and the results indicated candida, bacteria, inflammation and much more . We started with Ketazol and Flegyl. My daughter was taking up to 400 mg of Ketazol even though she was barely three years old. Now with everything I've learned I can not believe that a physician could prescribe such a high dose to a child who is only 3 years old and weighs only 16 kg. That alone should be punished and criticized

However, I felt that I wasn't doing the right thing, years passed, Ana Victoria was 5 and her comprehension and attention levels were very low, my husband always thought there had to be something else we could do!

One day my dear friend Carolina Garcia talked to me about Kerri Rivera's blog, she told me that it explained the reason for the supplements and the hours they had to be taken, for example that the antifungals had to be given away from food and the pro-biotics worked better if they are given at night. After I read her blog and visited her website in July 2010 I called the Clinic Autism02 and Kerri Rivera herself answered me. I explained my daughter's case, and she asked me to give her an opportunity to help, and if in 2 months we didn't see anything different with our daughter we could continue doing what we always did. I told my husband and we agreed to try. I felt a great sense of peace when when Kerri told me, "I'm here, and I promise I will walk with you until we recover your daughter"

In August Ana Victoria was on Kerri's full protocol and in November God gave me the opportunity to go to Puerto Vallarta, México. An entire month in this city were my daughter received the hyperbaric chamber treatments, we started with MMS, plus we got together with Kerri at her home every night with pen and paper, she explained to us step by step how we could heal our children. From that moment a beautiful friendship was born between Kerri and I.

This is when I understood that Autism is caused by a weakness of the immune system and this brings as consequences; viruses, bacteria, candida, intestinal and brain inflammation, food allergies and contamination with heavy metals, and that it is necessary to attack every aspect to be able to heal autism.

The 23rd of November Ana Victoria Started to take MMS and in 30 days of treatment we noticed the firsts changes. My daughter's stools were consistent; there were no food residues or foul smells. When I came back from Vallarta I was full of new knowledge and a lot of MMS bottles, Ana Victoria had already a very well defined protocol and the best thing was that it wasn't a long list of supplements, only 7, MMS and Theralac. Everyone in my family noticed a great change in our daughter, better eye contact, controlled hyperactivity, she started saying her first words with sense and purpose; I want park please, I want food please, I want to sleep. She was doing much better in therapy and at school. Anita had begun her way back to the world she left when she was 1 and half years old.

When I saw this improvement in my daughter I decided to share my experience with other members of my community and it was there with my dear friend Yamileth Paduani and her husband Alejandro Teran that Fundación Venciendo el Autismo was born. Mr. Alejandro asked if Kerri could come to Venezuela and talk to parents in a simple way so everyone could understand that Autism is curable. Kerri was delighted to accept the invitation and in only 7 moths of work we had 2 conferences and many evaluations and nowadays there are 700 kids on Kerri's protocol that is: casein, soy, gluten and sugar free diet, some supplements depending on every child, MMS and Theralac. The results are very positive and there hundreds of families that have started with their children's recovery.

Then came the great discovery of the parasite protocol, for me, it was the missing piece in my daughter's puzzle. The first few months of the PP were severe (fever, laughter, hyperactivity) and many worms in her stool. However, after all these worms came out out I saw how her mind cleared, and month by month we waited for the full moon to deworm ...

Ana Victoria is now improving very quickly, she is a girl that enjoys being with her family, the park, a day out, she goes to school and she says to me that at school she now does her work in silence without crying, when I arrive home she greets me with a smile, she runs to me and calls me Mom, she tells me what she wants and what she doesn't, she can use the computer like an expert, she takes her own shower and dresses herself, she even picks out her clothes, she knows when Christmas is coming and that there will be gifts. Her therapists and her shadow teacher are really happy to see how Anita is progressing day by day.

Yesterday we were all at the table eating lunch ... and she points with her finger …"Papa's food, Mama's food and Ana Kikota's (Victoria's) food…yummy… heeheehee. My husband and I were laughing with excitement and happiness. Some time ago we felt that speech would be nearly impossible for Ana Victoria.

My advice: do not be afraid of MMS ... be afraid of autism; that which is unforgiving and has the power to destroy lives and families if we don't attack it on time.

We are grateful to God because He has never abandoned us and has always given us the strength and tools to fight and to believe that it is possible to recover our children. We thank God for putting Kerri in our path and we ask God to bless her everyday for having such a big and noble heart, she who is always helping others in a selfless way. We also thank Jim Humble and Andres Kalcker for helping us find the missing piece in this great puzzle that is Autism. We can do it!!!

To all of you, many sincere thanks for helping the children in my country.

Blessings,

Carolina Moreno, President of Fundación Venciendo el Autismo. (The Defeat Autism Foundation)

Venezuela.

---

151. *Good Day, first of all I want to thank God for giving me all the necessary tools to be able to help my son, Jesus Soto who is 8 years old today. Jesus was born normally with no complications, loved by his parents and family, everything was going fine, but when he turned 18 months old he became ill; laryngitis, and fever, amongst other things.*

He was diagnosed with Autism at age 3. As a worried mother, I took him to the psychologist because I observed several behaviors that were not normal. After the terrible diagnosis we started to take him to a specialist after specialist, they were all very good doctors, his DAN! doctor in Venezuela, and my sons gastroenterologist were very helpful. I met a very special friend Mayerling Aparcedo who brought the ABA method to Venezuela. My son had many improvements but we still felt that we needed something else. I spent my time on the internet finding out as much as I could until I found Kerri Rivera that without even knowing me helped me via Internet, talked to me about MMS and about the supplements and how to take them. My friend Carolina Moreno had the joy to travel to Puerto Vallarta and wrote to me from there, telling me that MMS was helping a lot of children. The 14th of December I ordered my first MMS and the 27th of January it arrived to my country, from that date on my son is taking MMS.

The 2nd of April Kerri arrived to Venezuela and I went to see her, I took all the tests I had and she checked them, after only two months of taking MMS his viral *load went down to near normal levels, and his liver profile showed no problems. I made some adjustments that day and I continued with the treatment seeing a lot of improvement in his language, socialization, understanding of things, his hyperactivity has gone down and the laughter for no reason stopped. I'm very happy with the results and now all the family is taking MMS.*

I'm very grateful to God for putting my husband in my life, as he has been a very special part of this battle that we are winning, I also want to thank our family, Kerri, Carolina, Yamileth, Mr. Alejandro and everyone from the Fundación Venciendo al Autismo.

Yours truly,

Maria Campero

---

152. *My baby girl Yuliangel Nazareth Quijada Montero was diagnosed with autism when she was one and a-half years old. From that moment she was given a treatment to allow her to sleep and to control her tantrums: "Risperdal" which had absolutely no effect, I gave her up to three pills before bed and even them nothing happened, I was just damaging her brain. She didn't sleep night or day, I was worried because she screamed all the time and she hit herself.*

The 2nd of April 2011 I attended the conference of Fundación Venciendo el Autismo, where I heard for the first time that Autism had a cure. Kerri explained in a very simple way how I could cure my girl, even though I didn't have all the economic resources necessary for her treatment, the Foundation helped me with a part of the treatment, MMS and multivitamins. From there I started noticing changes, with a lot of sacrifice and effort my girl was on a strict casein, soy and gluten free diet. When I started giving her the MMS I would give her 72/2 on weekends and then I noticed that there was a lot of mucus in her stool, from there she started talking, she slept the entire night, and took naps in the afternoon, she pays attention, she knows how to count and all the colors with only three years of age. For me MMS is a miracle, since I started giving it to her she is a very healthy little girl, with no colds or any of the diseases she used to have, she is now considered to be very high functioning (14 pts. on the ATEC scale) with MMS, Vitamins, and the diet my child is getting out of the Autism spectrum. She does not go to therapy because of my finances but my sister Yenitze Montero interacts a lot with my girl, and her grandparents Raiza and Julian help me a lot with the diet, my nephews Jesus and Luis are also helping me with the home therapy and of course her dad and me fill her with love and care. My daughter is healthy, she has meaningful speech, she recognizes herself, she sleeps well with no pills and we are all very happy with the results. God Bless the entire team at Fundacion Venciendo el Autismo, especially Kerri Rivera for bringing MMS to my country, it is absolutely miraculous. Blessings.

Yurliana Montero and Jonatha Quijada

---

153. *Martin is 6 years old, weighs 19 kilograms and is diagnosed with severe non-verbal Autism. He was diagnosed when he was 2.*

He almost made no progress with therapy, when he turned 4 everything seemed to be lost, but when he was 5 we tried a new therapy and he started to say a few words. He also got very sick almost everyday, he coughed a lot, had an ear inflammation and fever, he couldn't go to school.

He started taking MMS the 29th of June 2011, when he was only taking two doses of one drop and two drops every third day has intestines were not moving and he had a psychotic attack (something that I've never seen before) and this lasted 2 hours.

Children with Autism are severely intoxicated so his reaction to the MMS was very clear. After 15 days of taking 8 takes of a drop a day Martin stopped coughing, he is more alert, connects all the time, his expression changes, he started to make friends, he starts to play with the computer, I hear from school that he'll be a preschooler because all the improvement he has had and that he didn't have all year. (I was almost going to get him out of school) he was attending school with a shadow teacher but had no apparent social communication or increase in cognitive capabilities.

This past October, in a meeting with his team of therapists, I asked them all what they thought about Martin's improvements and they were very happy, I asked 2 of his speech therapists who have worked with him for more than three years, "Did Martin have severe autism?" "Yes." They both responded. "And now?" I asked them. "Noooo" they both agreed. The rest of the team, who have only known Martin for a few months looked at each other, and said that they could not imagine Martin like that.

The path out of autism is scary, but MMS is giving us great joy and hope.

Martin has not been sick anymore, the last time he was sick, before MMS, we had to admit him to the hospital, his cough was so bad that he was vomiting non-stop.

First off we give thanks to God, we thank Jim, Andreas, my dear Kerri who guides me with all her love, and to every single mother that is in this struggle. I also thank Mr. Luis from Buenos Aires, Argentina who has made it easy for me to get MMS; he is a wonderful human being who helps those in need.

We are on the way to full recovery for Martin, I'm sure of that.

---

154. So I just redid my daughter's ATEC. She was a 71 a month and a half ago and is now a 60!!! I thought she was making nice improvements but it really set in when I saw her score. Some things that have changed for her are now she is pooping on the toilet every day and telling me. She used to just go every few nights in her diaper. There's no more diarrhea, she's not constipated, she's sleeping great. She is just starting to show signs of imaginative play and a big one for us is that she just learned to blow. She couldn't blow no matter what we did to try to teach her. Now she's got it. Hopefully more good things to come.

---

155. My now 8-year-old daughter was dx with autism at 18 months old. Started GF/CF diet and started with a DAN! She slowly made progress with speech, had a few words, a few 2 and 3 word sentences, and despite having autism, she was always a happy, calm, sweet little girl. Shortly after her 3rd birthday, she "changed.' She became more of a Jekyll / Hyde personality, and all progress in speech and improvements in eye contact and sociability started to fade. Seemed like everything we did was just like yo-yoing back and forth between improving, and then crashing yet once again.

Last year at this time, we had just left the doctor we had been taking her to. For years she was on antivirals, antifungals, antibiotics on and off, SSRI's, Tenex, and when her violent SIB had become so bad the second year into treatment with him, he put her on Abilify. SSRI's and the Abilify did nothing for her except make *her behave worse. Neither did any of the other things he had her on. The first year she was doing pretty good, but possibly because the antivirals were acting as an anti-inflammatory. She always had chronic constipation with loose stools/diarrhea. Nothing helped that either. We finally left that doctor who yelled at us in his office for 20 min straight, in front of my daughter, because he did not like that I had been challenging him on all of this for the past 6 months. I was no longer going to let him put the blame on us and everyone else... that her ABA and speech therapists didn't know what they were doing, and telling us she acted out this way because we didn't know how to give proper time outs or how to correctly give "pep talks" at bedtime. I was convinced that she had PANDAS/PANS and/or parasites that were causing her ever increasing SIB, loss of all progress she had made in speech over the past 4 years, and the fact that she had not grown in 4 years...did not gain 1 pound, feet did not grow at all, and she only grew 1/2 inch in height in that 4 year span. We had taken her to a very well respected endocrinologist the previous summer who ran all the tests. Could find nothing wrong as to why she wasn't growing. But he decided to put her on HGH anyway. Thankfully, we left and decided not to give her the HGH. We also took her to one of the best Ped Psychiatric doctors at UCLA who specialized in autism that summer. He observed her, her SIB happened right there in his office for him to see. He said her SIB is coming from pain, discomfort, something medical going on inside, most likely stemming from her gut. He suggested we get her scoped upper and lower. So we did. The only thing that came up was on the upper endoscopy, and that was that she had esophageal gastritis. So the GI dr gave her Nexium.*

All the parasite stool tests we had done over the years had always come back neg except for one at age 3 came back with Giardia. But that was it. So last January, when we had finally left that her doctor of 3 years, her liver AST and ALT were at 130 and 135, her Creatinine (kidneys) were severely elevated at a dangerous level, she now had hypothyroidism, and after testing her cortisol thru blood and saliva we discovered she was barely making any at all. She had dark circles under her eyes, grinding her teeth for 3 years now, and agitated beyond belief ALL the time. Mind you when we started with him 3 years prior, her thyroid, liver, and kidneys were all in normal range. She did have dark circles, many many food allergies, some SIB, but nothing compared what we were dealing with now, or what was to come.

So now, what to do. We took her to a very highly recommended Pediatric GI in Los Angeles who was very nice. Listened to what we had to say. Ran the most sensitive and comprehensive stool analysis. Came back with nothing at all. Then took her to the head of pediatric Infectious Disease at Cedars Sinai. She obviously had her mind made up before she even walked in the door. She saw the word AUTISM on my daughter's chart, and that was it. I showed her every blood and stool test, explained the not growing at all for 4 years despite all the endocrinology labs said everything related to growth was in normal range, her severe SIB. She said to us..."I know you want to help your child. You want to find something "medical" that has caused her autism so you can fix it. But the truth is, your daughter has autism. You need to accept that, and take her to a pediatric psych dr who can help her with these SIB's. There are lots of meds that can help her be calmer." Had she not listened to one damn word I told her!!! All the meds we had tried in the past did nothing, already took her to a psych dr who specialized in autism telling us something internal was wrong. She would not run any blood tests, or any other kind of Infec Disease tests. So with that, my *husband, my sister, and I completely dumbfounded started to walk out. The dr then had the nerve to say..."She hasn't been vaccinated since 18 months (she was 7 here) Let's get her caught up right now before you go. I can give her 6 vaccines today." I looked at her and said you have got to be crazy! I am not giving my very sick child vaccines full of the poisons that did this to her."*

So a month later we started with doctor who "gets it." Who listens, and treats parents with respect. Values their opinions. And the networking I had been doing for the past 6 months on a few different bio-med autism groups with other moms was paying off. The moms are the ones who KNOW!!! That's how I found my daughter's current doctor and how I found Dr Maile Pouls last June to help her with nutritional and metabolic healing. Dr Pouls ran a $100, 24 hour collection urine analysis, and we found out she had severe malabsorption, Ph was too Alkaline, she was catabolic, extremely electrolyte and mineral deficient, severely Vit C and D deficient, and had severe bowel toxicity. Working with Dr Pouls and her new doctor lead them to suspect parasites/worms. I was encouraged to look into mms, but of course I had heard nothing but bad things like it's bleach. I was very hesitant to try it, but I researched it, and sought out other moms on Facebook who were doing it. The toxins from the parasites had completely taken over her body and brain. She was SIB almost all day, every day by now. It was pure hell. We thought we were going to lose our minds it was so bad. We had stopped taking her anywhere but school and dr's appointments for the past 2 years because she would just suddenly out of nowhere, for no reason, violently freak out and there was no way to help her calm down. Her doctor said she's so toxic, and her body is so sick that she can't detox. That the mms will not only help kill, but will neutralize the toxins and help her calm down. So we started mms, and I could not believe how much calmer, happier, and more present she was in just a week. MMS is literally saving her life, and bringing her back to us. Before starting mms, we did just parasite meds like Alinia and Mebendazole. The parasite meds alone did not help her, even though she was dumping worms, but she was still completely psychotic, and getting more crazy and manic every day. Since starting mms she has dumped hundreds of worms, some 10-12" long, ascaris eggs, TONS and TONS of the shedded skins of the worms, tons of liver flukes, and hundreds of tapeworm segments. We had not done any PP yet. This had all been with MMS only! We actually started Albendazole for treating tapeworm about a month ago and saw immediate improvements with it. It really seems like this is her biggest beast right now to deal with.

These are her labs from before MMS, and after starting MMS:

2/7/2012 - one month after leaving scumbag dr of 3 years

AST = 79 ALT = 108 Creatinine = 1.24 EOS = 11.2 Sed Rate = 9

~ Started MMS 11/23/2012 ~

12/4/2012

AST = 73 ALT = 64 Creatinine = 1.32

1/15/2013

AST = 61 ALT = 60 Creatinine = 1.30

2/27/2012

AST = 51 ALT = 42 Creatinine = 0.92 EOS = 5.1 Sed rate = 12

Ref Range for AST is [15 - 46] ALT is [3 - 35]

Ref Range for Creatinine (kidney) is [0.60 - 1.20] Shows how well kidneys are working. Anything close to or over the 1.20 is considered to be of serious concern

*Ref Range for EOS (eosinophils) is [0.00 - 3.0] * High EOS are always seen with parasites*

Ref Range for Sed Rate (marker for inflammation) is [0 - 10]

Her doctor said her Sed Rate is likely high because when killing off pathogens and detoxing, inflammation will go up temporarily.

So I say never give up. Don't listen to doctors who don't listen to you. Kerri, thank God you saw those bottles of MMS at the clinic that day and asked what they were. And that you bought some out of curiosity and tried it. And that you selflessly have taken what you've learned and experienced, and shared it. Given so much of your time to help others, to help heal and recover their kids. You are truly an amazing person. We finally have the answers to our daughters autism after almost 7 years of numerous doctors and specialists, so many tests, so much money and valuable time wasted... and now we finally have real hope...real results. We know without a doubt she is going to get healthy, which will in turn give her the happy joyful life back that she once had before she got "autism." ~ xoxo

---

156. *Today was just wonderful! We have been on MMS since 12/11 and this is our second round of Ivermectin from our Dr, just started today. My son has been very rigid lately, but not today. For the first time in over 6 months we went to the park and had a great time (no stimming), then we were able to run an errand and pick up books from the library. (he usually gets upset unless we do one specific route in the car). Felt like a regular mom running kids to the park and one errand. So lovely!!!*

---

157. *Just a testimonial to MMS. For those of you new to the group and still unsure of MMS protocol I wanted to tell you about us. I was afraid at first, but we decided to try MMS. Within 3 weeks my son went from an ATEC of 36 to 18! That was amazing. Then we were afraid of the enemas. We said no way, we would just do oral MMS. of course after seeing others progress here we decided to do them. He would calm down! Then for months we agonized over the PP. We were afraid of it. We were scared of the meds, everything. Finally we decided to try it too. We are in the middle of our first PP and our son, who used to hit, kick, bite and scream at me over the smallest things all the time, has now been a perfect joy. When he gets mad it is over quickly and does not escalate into world war 3. Also these bumps he had on his face have cleared up along with his attitude! So if you are unsure of MMS like I was, here is one more testimonial of just how good the protocol really is.*

Thanks Kerri, all the other moms that came before me!

---

158. *Dear Kerri and the readers,*

I would like to say that we started giving MMS to my son Filip, autistic/PDD NOS, when he turned 5 years old, after having tried lots of things (diet, many different supplements, HBOT, some sort of behavioral therapy Teach and ABA), we have seen enormous changes already in the first month.

I had heard about MMS from a mom of an autistic child. I started reading about it, but was not impressed by the comments I read on the internet. I contacted *a few mums that I knew from the Son-Rise programme in the US and they have reassured me that it works miracles.*

I was however very sceptical of MMS, as I have read so many "negative" comments on the internet. This is why I decided to start it myself for a few months to see what would happen to me. Also, I had to figure out how I was gonna dose MMS 8 - times a day, when I am working 10 hours a day and Filip is going to the kindergarden.

In fact, I was just feeling great when I started using MMS.

I wanted to start with my son when on holiday, but my husband displaced MMS bottles by mistake. I was so mad. I have only found them the last day when we were returning home. I have immediately decided to give one drop to Filip before we started to drive. I need to underline that my husband was very sceptic. Filip would at that time speak, but it would mostly be scripting and rarely would he say things in context. Otherwise he also had other autism symptoms- tantrums, no friends, low muscular tone, no drawing, obsessive occupations (in Filip's case watching cartoons and reading books), no sense of danger, wandering out, nose picking, scratching but, toe walk etc. But suddenly Filip started commenting everything in the car, asking questions, observing the things he would see from the car etc. Me and my husband looked at each other and my husband commented " Maybe it is working after all".

Filip's ATEC was 48 at the time we started. At start, my mother-in-law helped out in dosing and we were able to dose 8 times a day. Filip's ATEC fell to 32 the first month. Unfortunately, my mother-in-law read some horrible stories on the internet and the FDA's advice was detrimental for her decision to stop dosing Filip, even though she was seeing wonderful results, she was scared and said that she is only believing the official medicine, admitting that the official medicine has nothing to offer our son.

I was very disappointed, but continued to dose as much as I could, however not reaching the recommended 8 times a day. I was therefore only able to dose 4-5 times a day. I started telework on Friday's in order to at least get 8-10 doses in on Fridays, Saturdays and Sundays and 4-5 doses the rest of the week. My son was great in November (the volunteers working on Son-Rise with Filip were commenting on unprecedented success), but his ATEC only fell to 28, I would say due to low dosing the progress was slower. Filip was having some hard times in January, when he was more hyperactive. At that time we have also introduced the GcMaf injections, which could have added to Filip's hyperactiveness.

But since two weeks now Filip is back to his shape. He is so communicative, uses unseen vocabulary, amazes us every day, he started drawing without being prompted, communicates with everyone, was invited to a birthday from a girl at the kindergarden, started to dress without prompting, started to tell me:" Common mummy, hurry up, let's go." or "Where are you mummy? What are you doing?" or when he occasionally wakes up during the night " Is it day already? or " I should not go on the street, because a car can hit me" or " Daddy, you are not sad, you look angry" or just yesterday when he draw a picture in the kindergarden he said to his teacher " I want to show it to my mum". The list goes on and on and every day I have to thank the all mighty for having led me to Kerri and to the MMS protocols. I know we are on the right path to recovery and I am not scared of the future any more. And, finally, i just did his ATEC to check out his ATEC- it is 16!!!!!! LOVE IT! LOVE IT!!!!!!

Kerri, thank you!!!!!!!!!

159. *My daughter has had really bad SIB for over 4 years. We've been in the ER for massive goose-egg bumps on head, and she always had severe bruising on her tailbone and spine from dropping herself down, butt first and legs in a "W" position, onto the floor, and then would fling and flail herself into walls, tables, furniture, bang her head on all of the above and the floor, a rage like she was the girl from the Exorcist. Nothing could stop it. It just had to run its course...like a tornado. Comes out of nowhere, and it will disappear when it's ready to. Nothing can stop it.*

But after starting MMS, it was 80% better right away. Then after 3 weeks it started coming back. For a month it was really bad again, and we could not move up past 2 drops without her going crazy. Then after you had us switch to the HCl, she was remarkably better in about 5-6 days. She has had a few "episodes" in the past 2 weeks, but now they can last 30 min max, where before mms they would last anywhere from 15 min - 2 hours literally non-stop. The year before starting mms, there were times I had to lay her on the bed or couch and just sit on top of her, like on her butt so she couldn't hurt herself. I would just lose strength after about 30-45 min of trying to hold her.

---

160. *Hey everyone! Just wanted to give a positive report about the HCl activator. My son is 12, non-verbal, very hyper and lots of food intolerances. I got mine in the mail today, gave a quick 3 drop dose to my son before he went out the door to school, noticed he was a bit more compliant and calm than usual after school. have given 2 more doses since coming home and he has been doing his usual, but he is much more calm today than he has been in months!!! I gave him a snack and he took it and started to eat and I told him: can you say thank you mom? and he actually responded with a sorta grumbled "graaaa mooooom" which was to me "thanks mom."*

---

161. *Thanking God for Kerri Rivera and happy here too. My 15 y/o is in the chorus of his HS play. He has to do 5 costume changes, his own hair and makeup and several song/dance numbers, which he did perfectly on opening night! He is not your typical MMS/autism kid. He was pretty much recovered, starting with biomed at age 2.5, until age 11 when he hit puberty and he started getting rigid and anxious. We had some supplements going and were starting to look at stem cells when we found Kerri. He is not on the strict MMS protocol but takes it when he can and does PP and enemas each month. He is so much better since starting this last August! So thankful for all the info and support from this group.*

---

162. *Hi Kerri,*

Last week I contacted you regarding our 8 year old son and his focus issues and the disappearing act his mathematical skills have taken, and we've done our best follow through on your advice to up the number of doses to 16 per day. I visited my son's Integrative Medicine doctor this morning, who has been his biomed doctor for the last 3 or so years to do a live cell microscopy, and to see if he had any ideas about the focus issues our son has been having. I told my son's doctor in detail what we've been up to over the last 10 months (MMS Protocol, Parasite Protocol) and he took it all in.

When he looked under the microscope he was shocked to see that our son's nasty dysbiosis issues were gone! He told me that he's had almost no luck completely getting rid of dysbiosis in a case like my son's. The yeast beast is gone! He still has evidence of leaky gut but the drainage looks great. He was so excited, our 20 minute scheduled visit turned into 40 minutes as he wanted *to know all about what we did so he can find a way to use it in his practice. He also remarked that you must be one bright lady to come up with the protocol, but we already knew that. :-) He had us fill out an ATEC when we first visited him back in 2010 and our son was at 55. He dropped into the 30's when we started him on Carnitine but the MMS protocol has brought him down to the 6. The doctor also noticed the distinct lack of autistic behaviours, so it's nice to get some outside feedback to help confirm what we are showing on the ATEC. I asked him directly if he thought we should change anything at this point and was direct...don't change anything keep going. And so we continue on our quest for the zero ATEC. :-) About two years ago we did a chelation challenge test (DDI) and found our son extremely high in lead and so we proceeded with IV chelation at that time. He ants us to do a chelation challenge test to check the metals status just to rule out lead and the possibility that metals might be still at the heart of our son's lack of focus and more ADHD like symptoms.*

He wants me to send him some information on your MMS protocol. He attempted to use chlorine dioxide about 10 years ago and found that he couldn't get the results that you are getting. I'll send him to MMS Autism website but can I include your contact info (email)?

Thank you for being so patient with us and everyone. As you know full well when it involves your own kid the emotions come out and it's hard to remain logical.

---

163. Drum roll....

I have been dying to share...

Been off MMS for a few weeks...AND HOLY SMOKES we are ALLLLL GOOD!!!!!!!!!!!!!!!!

Summary...

My daughter—PANDAS—MAJOR sleep issues—fluctuate between diarrhea and constipation

Me—Acne—horrible—and nail fungus

ALL GONE. ALL.

NOBODY could EVER, ever, ever tell me why I broke out so much esp. with our squeaky clean diet.

First PP, OMG it was REALLY bad—worst ever—and became cystic—painful—so for SURE worse before better in my case BUT believed in protocol and KEPT GOING.

By month 4, GONE and yet to return

Fungus—gone in month 1, never to return

My daughter:

Well, you know, AMAZING!!!!!

YOU, Kerri, YOU helped me figure out FINALLLLLY after a zillion docs, WHY MY KID could NOT SLEEP! EVER! 7 LONG years... long long—exhasuting years—and it was PARASITES NO DOUBT in my mind! Month 1 of PP, literally like a light switch, SLEEPING —falling asleep ON HER OWN—(not with a circus routine to "get her to sleep") AND staying asleep ALL NIGHT LONG! UNREAL! This is HUGE!

AND bye bye PANDAS (Siver/Aloe nipped it, MMS maintained her gains, *BEAUTIFULLY!) SO I do believe in our Silver Aloe protocol for PANDAS, 100% worked for us! AND MMS. Both.*

AND since OFF MMS, my daughter is 100% pooping NORMAL—OMG first time in her WHOLE LIFE!!!!!!!!!!!!!!!!!!!!!!!!!!!!!!! (on MMS it was still fluctuating...)

AND she is eating things she would have NEVER ever touched! EVER! Raw veggies, nuts, trying EVERYTHING I make... unreal... this is HUGE too... the "healthier" you get, your tastes DO change... and one becomes less "picky"

I have learned that SOME probiotics can literally throw a child into a PANDAS rage--and also brought back MY symptoms—literally within 12 hours of consuming. (Like "Regarding Caroline" posted) This clearly happened to us. Mental note: NOT all prob's are appropriate for everyone. We react to fermented food—so I am going to experiment with no prob's and with THeralac __ONLY THeralac BTW

Now,

We are back to silver/aloe, daily, as prevention

We will still take DE (prevention)

Vit D3

Trace Mineral Drops

Enemas as needed

AND I am going to go BACK to the herbs for 3 months around full moon "just in case"—

I CANNOT WAIT to meet you in person, THANK YOU, and share our story with EVERYONE that will "hear me".

Again, my daughter did not have 'autism' per se, but autoimmune issues, meaning that, perhaps, her treatment protocol is 'shorter' then someone who is "more sick' etc. if that makes sense.

We also did a boat load of work prior to this. Meaning diet in place, for instance, for 4 years already—so healing began. This was the final layer for us. The frosting on the cake!!!!!

I have 2 brand new bottles of MMS in my cabinet :) AND will ALWAYS have it on stock!

With MUCH LOVE and respect to you Kerri.

-Jeni, IL, USA

---

164. *My daughter was born Sept 9 2010 and she had pretty good health until she had 15 months, she was able to say five to ten words by then, she had all her vaccines on time as recommended by our pediatrician, and she was really lovely and happy but suddenly every start to change slowly, we noticed she start losing the words she had learned, she use to wave people saying hi, and suddenly she was not interested on waving anymore and she start to isolate herself little by little to the point she stop being a happy girl, she barely looked at us and we started to worry about it, anyway, I believe the first thought every parent may have think in this very same situation is that her personality is different than other kids and is something temporal.*

When she had 18 months we went to the regular doctor check and they asked us to get the opinion of a development pediatrician since her social and language skills were behind the expected, and this started the worst nightmare ever.

It seems like every single development pediatrician has a waiting list huge enough to have more than a couple months totally scheduled, we called on May and the first available appointment was 4 months later, we called like 4 or 5 of the recommended pediatricians and institutions but it was all the same thing, but we finally got a pediatrician, not form the recommended list, but he made room for us in a couple of weeks and we were able to see him in a couple of weeks.

The diagnostic was mild autism, the recommended treatment was ABA therapy and the follow up was going to be 1 year later since he did not have may expectations of positive changes in the next 6 months, we were devastated by this, my wife was in denial, and I started our journey to recovery the very same day, I started researching and suddenly I found tons of information about autism and people who claimed to have recovered their children from autism.

I sent emails everywhere and I never imagined I would have such a great response from every person I wrote extending me a helping hand on all my doubts with the most sincere and honest recommendations, 2 or 3 days later I found Autismo2.com website and I saw all the videos available.

I bought 3 or 4 books on amazon, I saw many hours of recordings and seminars in Spanish and English, and I was amazed about some kids losing their diagnostic, but also about how they were affected by heavy metals, bacteria, viruses and all sort of things.

At the beginning I thought my daughter could not be sick, she has never had a single cold, how come? but a home heavy metal screen test gave us the first clue, and some lab tests confirmed the very same problems all our kiddos share, mercury levels on the roof, candida, yeast, you name it.

I started the GFCFSF diet the first weekend after her confirmed diagnosis and just one week later we started noticing changes, then I started with baths with bentonite clay, and noticed more improvements, we also started ABA on July, and little by little our daughter started to improve, later on we introduced MMS baths, Quinton water, DE, probiotics, and she improved every day.

I honestly believe that the early diagnosis and prompt reaction from our side played a big role on her fast recovery, It happened that we never canceled the first appointment that was made with the most recommended development pediatrician, by then we were looking for a second opinion and a new evaluation due to her huge improvements, we never imagined this pediatrician will say what.

Although my history with this disease or condition has been very short nobody knows how much pain, stress and suffering had caused to our family, we now enjoy our daughter more than ever when we see her playing with her old sister and taking away every single concern we had, we continue keeping an eye on her development but she is doing really well, I wish nothing more than every single mother I have hear on the discussion groups I follow have the very same results we have had with all the guidance from such smart and courageous parents like Kerri Rivera and many others that shed us the light on our darkest night.

I am more than grateful with all of those parents, I would do anything on my reach to help them, we need to help every single kid and family that goes through this disease to recover our kids.

UPDATE:

I'm very happy to forward the last ATEC from my daughter, today we came from her 2 year check up with the new pediatrician and she found her pretty well, she just told us" It's pretty hard to believe she was diagnosed with mild autism keep *doing whatever you are doing, since I would say she is acting like a regular kid for her age."*

I would say that keeping in mind that most of her ATEC score is on the Language section, for a 2 year old and from what we came from she is on her way to full recovery (Previous ATEC was 55, at this writing was a 23)

---

165. *I found Jim on the Internet 2 years ago, and I immediately started Jim's protocol for MMS. Unfortunately we were so loaded with mercury, so when I reaches 8 drops of mms, and my son 2 drops (after more than 2 months on slow upgrading) we were really sick, again. All the heavy metals that where released with mms could not get out of us. That´s when I found zeolites, and that was our way back.*

Now, two years later, my arthritis is gone, and now I know it was mms that killed the clostridium bacteria that I had been carrying since I was 13 (I am 52 now). 6 months ago my son fell off his bike and got an open wound. It was infected and some hours later the blood was black in his hand. Now I had a choice, to go to the doctor and give him antibiotics, which I knew would kill the bacteria but make him worse, or do it my own way. I gave him 2 x 3 drops of mms, and the blood was ok in some hours, I thought. Some days later he started to wave his hand. I thought he had eaten something else that he could not digest, but it got worse. After 4 weeks he was not only waving/flapping both his hands, but also his head. Then I started get suspicious. I tested him for bacteria (I use a Rayonex PS 10 for testing, bioresonance) and I found Clostridium botulism.

Now I had a choice again. I had a fully booked week, but his father came and took him home to his island, where they could use MMS every day and be in a calm environment. He got 2 x 3 drops of mms, for 6 days. After 3 days his father called and said "Eva this is scary, the flapping is getting worse". And I smiled and calmed him down, the bacteria are dying and the toxins are being released, I said. The zeolites took care of the toxins, and after 4 week he was ok again.

My lesson in this was, apart from the clostridium toxins, that I also found an imbalance in my son on Condrogenesis with the Rayonex. When I was 13 I stepped on a rusty nail. The blood was poisoned in the foot, but I did not dare tell my parents. After 3 days the whole leg up to my knee was black. I got antibiotics, of course. At 18 I was diagnosed arthritis in my knee. I think I had small amounts of bacteria left, as my son had, and the toxins from clostridium bacteria degenerates the cartilage near the infection. After some years one develop arthritis. I did, but it's gone now!

Eva, Sweden

---

166. *Drum roll please.......my son is 17 years old. He's been on mms for 5 months now, I'm so excited I don't even know, could it be 6? I think we started late July. He started with a 63.......he is now a 7. He went from 63 to 25 in just a few weeks, then a 13 a couple months later, now a 7. I feel like I'm cheating every time. I go back and look, argue with myself, nitpick....but whether he's a 5, 7 or 9, it's nothing short of a miracle because just one year ago, he was WAY over 100.*

The ATEC is not perfect, not even close. There are things that the ATEC does not show. All that is true, but this is incredible improvement that no doctor I know would have ever been able to accomplish. Been there, did that, spent the 425K+.

And no, it's not just MMS, but that has been the main treatment and everything else we do supports MMS and general health because I believe that in the end, *it's a battle between your immune system...and all that's attacking it. We are winning and I sure do wish they would STOP CALLING IT AUTISM. That alone hurts so many.*

Here's a little background on my son: Matthew was very high functioning from age 6-12. That was after diet since 3, floortime play therapy, some aba, AIT, IVIG, chelation for a year, OIG, years of infusions of glutathione, vitamin C, B-com, etc...immune stuff. Then he did very well GFCF ages 6-12, ran track (very well), 2nd degree black belt, boxing lessons, etc....Then puberty hit, and what I did not know about, Lyme and co-infections RAGED, and for around 3 years, I lost him cognitively, worse, worse, worse. At 15, he was like an advanced Alzheimer's patient, ADVANCED, he had lost ALL short-term memory, it was horrible, he struggled to think and could not.

He became more and more violent; choking me, kicking me, did I say he was a blackbelt? Even though he lost everything cognitively, like the ability to answer a question, those karate skills popped back into his head and he nearly killed me.... really close a couple times.

That was a year ago when his ATEC was over 100. So, here's what worked: 1. Low amylose diet helped with the constant urinating. (he acted like a diabetic and had 14 of 16 PANDAS symptoms so auto-immune) 2. Biofeedback helped calm him some. 3. Cholestyramine helped him psychologically - I could see him clear up mentally in minutes. (chemical/mold/dust sensitivities big time) By this time, his doc had him on Ketamine for pain. 4. PEMF (pulsed electromagnetic field device) stopped the pain in 6 weeks, got him off of Vicodin, which was not working anyway at double doses, and all the Ketamine. I hated drugging him. Got him off the psych drugs over 6 months time. Then he got a lot better but communication did not really come around until 5. MMS. BAM. Big improvements in communication and PERSONALITY. With MMS, even his laugh changed to a typical sounding teenager's laugh, and for the first time in years, he can sit still and stop pacing, pacing pacing....the parasites were eating him alive....and now more recently, I know 6. Hydro-colonics is taking us to another level of clear communication. Now there's lots of spontaneous language.

I write things on Facebook so that I can remember and maybe write a book one day. I don't care how bad things get, believe me, your kids can get better and it's amazing, they really do store up all this info that you didn't think was there. It is there, and they will share it with you one day.

I hope one day Matthew can share his perspective with others. It's just that it has taken a very long time for us to help him understand that the things he did back then were not in his control so I'm careful not to talk about it. For months he would out of the blue apologize and feel terrible, over and over. Then there's memories of his dad losing it also....protecting me.

Thankfully, Matthew has blacked out or forgotten a lot of it. He did say he remembers being locked in his room. We had to turn the lock around and sometimes lock him in there. Bad memories. We were all traumatized. But not anymore. He is a different person today but he's always been the sweetest boy I know. I knew that, even back then. One day, he'll probably talk more about it.

---

167. Hi Kerri,

First of all a HUGE big thank you for what you are doing with our children! My daughter has been on MMS two weeks now and she is like a different child!!!!!!!! Every day she gets better...By leaps and bounds. She WILL be one of your recovered ones ;)

UPDATE:

My daughter has now been on MMS for three weeks. ATEC down from 78 to 44. This IS a miracle. We have been in absolute desperation for almost three years trying to figure out what in the world is going on with our child. After hundreds of thousands of dollars, experts all over the world, LA, New York, San Fransisco... and nothing would work. Minor improvements but nothing that I could say really worked. Everyone always agreed that she probably does not have "autism" but what is making her behave that way?!?!?! So a long story short... If I could I would wrap my arms around all of you helping my daughter and so many others through MMS until I was sure you truly understand what your dedication means and that you are saving lives...literally <3 This is by far the biggest thing that has ever happened to my family. We are forever thankful.

UPDATE #2

I sent you my daughter's ATEC a week ago but redid it today. We started MMS in December and I decided I will do the test every month. Here are the results, 4 more points gone!!!! In 1 month from 78 to 40... Almost half off!!!!!! Her team is blown away ;) all we need now is that language score to come down... Kerri my goal is to have her recovered by A1!!!

Update #3

We are seeing such amazing improvements every single day. I think the true testament is the daily feedback from people working with her who do not know we are doing MMS. Here is part of a note from her SLP " her communication on the whole is truly remarkable- words, iPad, eye contact...everything is improving!!!!!!! So exciting. Has anyone told you lately that your daughter is a superstar? You should be so proud. :)" And I am...

Our main challenge has always been anxiety and today we had a breakthrough on that front. Instead of clinging to me for her dear life when I separate from her at school she took her friends hand, waived AND said goodbye and walked away... Here is the best part, she then turned her head, waived and gave me the biggest smile . Her face at that moment is forever engraved to my heart.

Also for the first time EVER my son was able to have a friend come over from school in our car without her having a major meltdown. Instead she shared her iPad with the friend to show him her program and use it TOGETHER!

Honestly I think our major challenge at the moment is for the rest of the family to heal with her... We had lost all hope and settled for life with Autism. We can now look at the future very differently and actually look forward to it! Love our new life

UPDATE #4

I have never really posted gains but this is too huge not to share. We started MMS 3,5 months ago and at that point I could hardly take my daughter to the grocery store. And even if I did it was a guaranteed meltdown. Well we just got home from a two week long vacation that included travel by air, time difference, different language, going from hot weather to freezing temps and piles *of snow, totally different foods, nothing but strangers to her, visit after visit to new places...The list goes on and on.The BEST part - the vacation was full of excitement, fun, laughter and happiness every single day I have to pinch myself to believe this is my life after such a short time on MMS.Thank you all for your support and guidance I have my life back and can't wait for the future now! We still have a looooong way to go but we'll get there.*

Today is a wonderful day already

---

168. *MMS Works!*

It's my number one pathogen fighter. Our family continually suffers from Strep, my son specifically from Pandas. MMS remains and continues to keep our strep symptoms at bay. I have used everything for our bacterial flares (Abx, herbals, supplements even homeopathics) and nothing has worked so effectively like MMS does for us.

Recently I changed over to the HCL activator and within in a few days we heard my severely apraxic son's first WORD "Mama" Its been just over a month on the HCL activator and he is now stringing two words together!! MMS is a huge part of our recovery protocol. I feel relief beyond measure that I found a post on MMS and decided to try it, and mostly I'm immensely grateful to Kerri for putting the MMS protocol together and for her love for our kids.

---

169. *We just had a good meeting with all of Amor's teachers and therapists. In the last few months there has been big jumps in Amor's cognitive skills.*

I used to worry that Amor might have dyslexia. I never pushed her to read even if was behind her peers. I know frustration will only make things worse. Her 'x' and 'k', 'b' and 'd' were always mixed up. I have been observing this mix up for the past 2 years. Early this year, her speech therapist agreed that dyslexia might be an issue and we were ready to start studying dyslexia management.

However, Amor now shows interest in reading both phonics and sight words. She can answer letter names and sounds precisely.The same speech therapist now says that we shouldn't look at dyslexia anymore. It might have simply been a mix-up as part of early learning.Amor's dyslexia issues in 2 years all of a sudden went away in 2 months??

Amor is also doing well with number recognition and improving in one-to-one correspondence.This is something her former speech therapist (back in Japan) was working on for a year...with little progress.

All these seem so simple but these are great strides from someone who has vision issues.Amor also wears glasses.

If I were to plot Amor's improvements with time, the biggest jumped occurred in the past few months, which of course can easily be explained by MMS.

MMS clears the gut of bad bacteria, yeast and parasites.All these affect sensory processing thus inhibiting the child's ability to understand her environment and people around her. Clean the gut, remove autism...in Amor's case, remove GDD.

We are also running a son-rise lifestyle program. I.e. we don't put fixed hours into her program but use the son-rise attitude and son-rise her in the weekends.

170. *Luca came into our lives July 26, 2010, he was premature, but all my kids were born in week 35, so I was not surprised. He was perfect, I have thousands of videos of him looking into my eyes, smiling, playing with his sisters, following daddy to the door when he was ready to leave to work and saying bye bye. He walked at one, and was a perfect little baby. It is hard to know exactly when he changed but I can tell you when I started to get worried, and saw him behaving differently. I had a neighbor the same age as my son, and when they got together to play I was surprised at how my neighbors son followed simple directions and looked into my eyes every time I called his name. When I had play dates with my friends all the moms were so relaxed, and while they were talking and kids were playing with toys, I was always chasing Luca and trying to keep him in the same room because he was not interested in toys or playing with other kids.*

My first trip to the Zoo with my three kids was a disaster, Luca didn't want to move from the Monkey's area and had his first melt down, all over the floor screaming and crying. I remember seeing all the families with kids the same age as my son, and seeing how they understood, and paid attention to what their mothers or fathers were saying. For me that was enough to feel for the first time something was not right, and it was not that I was a bad mother, I knew deep in my heart it had nothing to do with discipline.

I enrolled him in a school thinking that would help. The first day when I picked him up the teacher said they needed to move him with the babies because he was not ready for the 2-year-old class. That day I came home just knowing - and despite all my family, friends, husband and Pediatrician thinking I was crazy, we got him evaluated and the rest is history. On November 15th, 2012 it was official and we got the papers. Classic Autism, by that time we had read so much, watched hundreds of videos and searched every day on the Internet for interventions, schools, therapy etc.

I remember I wanted to start ABA the same day that I got the diagnosis, but the waiting list was really long and we would have to wait. So we waited and started an early intervention program in the Kent District. Surprisingly, I think we took the diagnosis really well; we just wanted to help him as soon as possible.

After the first month I stopped asking for a miracle or cure. I even asked all family and friends to do the same. I needed to accept it!!! My miracle was already here. My husband wanted to do the Gluten free diet and I was not even 100% in agreement...why??? He is such a blessing; let our miracle eat whatever he wants!!! I agreed to do the diet anyway, but wasn't really interested. I just had the feeling my husband was not "getting IT" or accepting autism = our new precious miracle. Now I can recognize and see clearly I was in total denial too. I was so afraid to let anybody know, even myself, that I didn't want this for Luca. I tried and tried and tried, but a voice inside of me was not in peace. I spent a lot of time crying and looking for recovery videos on YouTube, imagining Luca being one of them, and was fascinated with those stories.

Then one day I found Kerri Rivera's conference in Bulgaria, it was a "Godcidence," (like my father always says) I wasn't looking for MMS, I didn't know anything about that. I remember I watched the conference 3 times, and I felt butterflies for the first time since I got the diagnosis. It was like that voice was finally quiet and listening to every single word! "I want this."

I did my homework and found a lot of negative information about MMS but I did not care…that voice was so strong that I knew, the same way I knew about

Luca being autistic, that this was something I needed to explore. I looked for her in FB and to my surprise she answered me in minutes, when I asked her about the testimonies she connected me with some moms with recovered kids, REAL moms that decided to believe too. After I saw pictures from before and after and reading about their journeys I felt Hope!!! I knew deep in my heart this was the way and the path we should take. So I got my case together and when I was ready I talked to my husband about it.

It was easier than I expected, we wanted so badly to recover our son!!! It was not an easy process but finally after almost 3 months I GOT IT…WE GOT IT...THERE IS NOTHING WRONG TO WANT THIS, that is ALL we want for Luca!!!! For the first time I recognized my kid's autism was not a blessing, he was sick; GI problems, extreme constipation, food issues, sensory problems... and that voice (God voice) sounds really clear and loud; I NEED TO HELP MY KID TO RECOVER!!!!!!

On February 18th we started a Dietary Intervention with all Kerri's recommendations, the one diet that we were doing was full of sugar and carbohydrates, so we started to be really serious about all the food choices. We kept a very detailed food diary and ordered the MMS. By March 12th when our bottles arrived at our doorstep we were ready to start Kerri Rivera's Baby Bottle Protocol. March 13th we did our first bottle and that same day I asked Luca to look for a ball in the other room, and give it to me, and he did.

It was like he was sleeping soundly, and then he woke up. He was extremely alert and he was looking in a different way. At first I thought I was crazy, but then my husband noticed it too and the changes keep coming. He improved dramatically in all his therapy sessions, his waiting time, sitting at the table, responding to commands, pointing, eye contact, everything improved!

Kerri recommended doing an ATEC when we started back on February 18th, so I did, his score was 64 points. By April 1st he dropped 20 points! He now follows simple directions, plays with his sisters, recognizes them by name, hugs me and says mommy and daddy, has close to 200 words, and every day is a surprise for us.

I'm proud to say my son is on his way to RECOVERY AND HE WILL RECOVER, HE WILL BE RECOVERED!!!!!!!! I'm loving Kerri Rivera's Protocol, I'm loving my kid dropPing 20 points in his ATEC in a month, I'm loving searching his diaper, and inspecting his poop finding parasites, I know it seems impossible but I truly get excited! (Probably some mothers would understand) I'm loving this side of the picture FULL of hope. HOPE. I don't think I can leave this road now, I don't think I want my son to live in his "perfect" world and not in mine... I'm a fighter and thanks to Kerri I'm a believer ...THAT... is the blessing right there HOPE AND FAITH IN GOD IS ALL I HAVE AT THE MOMENT… Luca is really special, but it's not the autism that makeS him special, autism sucks!!! Overcoming it and all the obstacles he encounters every day, and doing what he is doing now is what makes him THE MOST SPECIAL KID ON THE PLANET, HE ALWAYS WILL BE SPECIAL TO ME NO MATTER WHAT, AUTISM OR NOT….I see it in his eyes now, he is a fighter like me, he is telling me what to do, recovery is soooooo in the picture!!!!!! I can actually see it!!!! I'm a HAPPY Mom!!!!!!!!!!!!!!!!!!!!!!!!

-Alma

171. *Today is a wonderful day already. My daughter got up to her alarm, took a shower without help, got dressed, packed her lunch, woke up her sisters, and is now getting breakfast for everyone ready. It amazes me how independent she is becoming, and how much our life is changing because of her new independence.*

She is 10 and we started MMS in Sept. She had done 5 PP and following the PANDAS protocol the last week after emailing Kerri Rivera last weekend with concerns about eye fluttering. She is also on Fish oil, garlic, Magnesium, and GABA. Before she was very hyper, spacey, a lot of language, but not using it correctly. She was extremely impulsive, and would fixate on object to play with and ignore others. Now she does reciprocal play, she talks back and forth with her friends, she cracks jokes that are now actually funny. She is focused with her school work and not hyper - except in typical situations.

This week my husband forgot to pick her up to take her to therapy and she came to my classroom to tell me how irresponsible he was, and that she was disappointed in his inconsistent behaviors. I had to laugh, but at the same time I was so proud as I explained to her the whole situation because we where having a fabulous discussion about life. She is doing so well. Thank you to all of you who have restored some of my hope that there is a cure.

---

172. *We are now in our 7th month of using MMS (CD) and in our 4th year of treating B.D., our son, who was diagnosed Autism. Our first week of MMS (CD) brought on a skill that we had spent years trying to accomplish, over night potty training. Week 1 of MMS (CD) and B.D. was out of pull-ups and in underwear. We weren't even close to full dose and already seeing positives. We knew we were on to something big at this point. One month later, we all witnessed my son blow out his birthday candles and open birthday gifts. Probably the first time he knew this event was a birthday and it was meant for him. As a gift to him, we took a trip to Disneyland. Not only did B.D. walk the entire park at our side, but he never once cried, whined, or objected to anything on the trip. Prior to this, he had to be in a stroller or wagon at all times.*

B.D.'s skills continued to flourish over the next few months. We enrolled B.D. in swimming lessons hoping he would feel comfortable without a life jacket on and clinging to an adult. This hope turned into a major accomplishment. B.D. has passed all Beginner levels in swimming and is now on to Intermediate. He is now swimming unassisted in the deep end of the pool! I used to hold my breath during his sessions hoping he wouldn't do anything that would scare the other kids in the pool. I still hold my breath, but now I'm at the end of my seat recording him as he's giving every single bit of effort to learn from his instructor and pass another level!

Just the other day, we went to a birthday party that was held in a warehouse full of screaming kids, loud music, inflatable jumpy houses and slides. This place can over stimulate just about anyone! In the past, my son would vocally stim, cover his ears, run behind the jumpers where the generators are (trying to turn them off) and require me, or his Dad to keep him engaged with the rest of the kids. Well, not anymore! He blended right in with the rest of the kids! Not a single stim, didn't cover his ears, stood in lines, listened and followed the rules and instructions, stood in lines and PLAYED with the other kids. His Dad and I were able to hang out with all the other parents, watching him run and whiz by with all the other kids as if that is how it has always been. Only it hasn't. He has come so very far in the past 7 months. We have a 6 year old son who no longer has sound sensitivity, loves to eat whatever is placed in front of him, DRINKS *tons of WATER, has manners, shows empathy, is careful and aware of other kids (especially babies and toddlers), making progress academically, and so very affectionate. B.D. isn't recovered… YET, but we expect it to happen now more than ever. We have to put our shades on because the end of the tunnel just got closer and brighter!*

---

173. *My husband and I were told to come to the 2nd grade assembly this morning. They gave awards to 2 kids in each of the 4 second grade classes. One was for outstanding in academics, and the other was for most improved in Self Control, which is the "character trait of the month" for the whole school. Kayla was given the award for most improved in Self Control in her class! She walked up and got her award and stood up there with the other kids holding theirs. Up until a few months ago, she would have violent, self-injury tantrums at school every day... throughout the day, lasting anywhere from 10 - 90 min. She could never get through a class singing performance without losing it and tantruming, screaming through the whole thing. Her teacher came up to me on Wed. and said she just can't get over how happy my daughter is lately, and that all the teachers and staff in the school have really noticed too. FUA!!!! I'm so proud of my girl!*

---

174. *Our third child (K) was diagnosed with moderate autism at 21 months of age. K was very ill. He suffered from vomiting and diarrhea mixed with severe constipation for years. At first, we began every intervention we could afford. The first step was removing all gluten, caseine and soy. We saw a decrease in stimming behaviour and an increased ability to learn. We implemented many vitamins and B12 injections, cranio sacral therapy, anti-fungals, HBOT and an even stricter diet removing all artificial colours, flavours, preservatives and most sugar. Our son was making slow but steady gains. ABA therapy continued from when he was two until just this past March (4.5 years). K was seeming much better but despite these gains, was never close to "normal".*

In July of 2012 a friend suggested MMS. I did my research and so it began. In three days K started to sleep through the night. After less than one week at a very low dose, K stopped the constant verbal scripting and obsessive speech- his most evident sign of autism. In that same week he began dressing himself independently. In the coming months, K's ATEC began dropping steadily. He began to make jokes, initiate social interactions, show empathy, cope with noise and busy places and best of all- understood safety. The risk of him running away was a memory. We could go places and he would stay near us. Teachers and Educational assistants were raving about his progress, unaware of the protocol we had begun. His most significant changes happened after a three months of the Parasite Protocol, using mms, Vermox, rompepiedras, neem and diatomaceous earth. Through enemas, he expelled worms as long as 24 inches to my husband and family doctor's disbelief. What K expels in his stool now looks normal and ordinary.

His ATEC in July 2012 was 46. Ten months later he has a score of 6.

He is undecipherable within his classroom and amongst his peers. He laughs, plays and acts like any other child his age. His academics are at par with his peers.

Our son does not appear to have autism anymore and only a trained eye would suspect that he ever had it to begin with. We thank Kerri Rivera, her Facebook group for all their support and MMS for being the final, and most significant leg in our sons' journey to recovery.

Maria A., Ontario Canada

---

175. *My severe autistic boy has been now doing wonderful!!! This protocol has completely changed my life!! He's been dumping tons of parasites since we started MMS about three months ago we're now in the second pp...he's now much calmer more happier!! His ATEC dropped down from 80 to 48 in three months only...that was truly amazing he is now gaining weight, I feel like I'm getting my child back to normal again!! I wish I could tell the whole world how Kerri Rivera has changed thousands of people's lives!!! God bless u Kerri for all your hard work to help others!!!*

---

176. *My son Nick started MMS just after his 7th birthday. Within 6 months he had cut his ATEC score in half from 66 to 37. Nick showed speech gains from the very first drop of MMS after having made no changes in speech for two years. Really, Nick hadn't made any improvements at all for two years. He was in a total stall until we began MMS. We raised Nick's oral dose of MMS very slowly taking two months to get to his target dose and never experienced die off that was unreasonable. Three significant changes are obvious in Nick's health at this point; he has been off of his Mitochondrial cocktail (for several years he has had blood labs pointing towards Mito dysfunction) for over 8 months and we haven't seen any of the lethargy that used to concern us so much, he was able to wean off of his seizure medication for his absence seizures and we haven't seen any return of seizure activity, and his thyroid appears to be beginning to shift from his long standing diagnosis of hypothyroid. The nicest changes we see are in the vibrancy of his health and how happy he is! His eyes sparkle and he has lots of energy for the day. He is no longer sitting on the couch staring out the window waiting for someone to figure out how to help him feel better. Since beginning MMS, every day Nick shows us just a little bit more of the boy that he is underneath the veil of autism and sickness. He tells us what his favorite things are, what he wants to do, and his sense of humor is coming shining through. MMS has given me a ton of hope that we just might get our boy back!"*

---

177. *After 7 years of biomedical treatments, numerous therapies, and more doctors than I care to think about, our son, who was diagnosed with autism, could speak a full sentence, was potty trained, and could finally go to the mall and movie theater without screaming and putting his hands over his ears.*

Victory??...yes...however, we knew we had so much farther to go. You see, as your child gets older, you realize that he is missing the key things in life that are crucial for independence. Our son had become "stuck" if you will, he was not socially maturing, and still lacked empathy, mature connections with peers, and proper communication with teachers and the other adults in his life. He would still yell when he didn't win a game, and he did not always react in an age appropriate manner, if something did not go his way.

My research went on as always...searching, searching, searching...we were not getting anywhere with his current doctor, and I knew that we had to change our current plan for treatment.

A good friend of mine called me to tell me about a new product that some of our warrior mom friends were trying. The letters MMS were spoken to me for the first time in March of 2012. My son was 11 years old and I was desperate for help. The first thing I asked was, "How much does it cost?" $25.00...what?? It can't be! We have spent our life savings, and now I am looking at something that cost less than a night out for dinner?? I decided to check it out!

I emailed Kerri Rivera and told her that I wanted to start the MMS autism protocol, and I'll never forget her quick response..."YIPEE", she said, let me know if you have any questions, I am here for you.

I read, studied, and called my friend about twenty times over the next couple of days, and then we began the next chapter in our journey.

About three weeks into the protocol, our son seemed calmer, as well as aware of others on a more mature level...we were excited! Once he was at full dose, we began, baths and enemas, and he continued to improve. Our next move was to try the 72/2 protocol, which is giving MMS every two hours around the clock for 72 hours.

Well, it was as if someone had kicked our sons maturity clock into high gear. We saw HUGE gains!

"Hey mom, I like your dress...you look really nice today"....WHAT??

"I'll try that new kind of chicken for lunch"...WHAT??

"I feel like I'm beginning a new life"...WHAT??

"It's OK that I didn't win the race, I had fun"...WHAT??

I wanted to call the Good Morning America Show and say, LOOK AT WHAT MY SON IS DOING!

He also began to grow and put on weight for the first time in three years! He put on 10 pounds and 2 shoe sizes in about 2 months!

The gains continue to come, and our boy is coming alive...recovering...finally it's here! My eyes well up with tears as I write these words...the words I have dreamt about for eight long years.

He celebrated his 12th birthday on January 3rd, and has told us that 2013 is going to be the best year of his life...YES...it is!

He is our angel, our fighter, our miracle. Thanks be to God for MMS!

We are blessed and forever grateful~

---

178. Once upon a time there was a little boy who had a strange mind, he hooted and he danced and he did not learn like the other children around him. So, he was sent to a special school. For his whole educational life he was separated, because he could not express correctly the answers put before him.

As he grew older he seemed sad and very much in pain. He appeared to try to stop the pain by clawing at his face and arms. He also stopped talking. We, his mom and dad, were very sad.

Then an angel came into our lives and told us of a magic potion.

"But" said the angel. "You must give him the potion every hour of the day and night for him to be better."

So the little boys' mom and dad have been doing that now for 9 weeks and 4 days. Every hour.

Now in those hours the mom and dad still cry. Some, because the little boy has been hurting for so long, and..... now they know why. But they also cry because they see that their little boy is not hurting like before. They are happy for his healing, and that he does not claw at his body any more.

And they are also happy because their little boy is talking again. And he is laughing. And the things that he knows surprise them. We thought he was not learning…turns out he was.

179. *Feeling really good still about my Natalie's progress from the combination of anti-parasitic medication, the supportive components of the PP and CD (HCL version). Natalie is about 63-64 lbs and she takes 2 drops of CD an hour both at home and at school. We don't wake her for CD in the middle of the night; but if she wakes for the restroom or something, then we give her another 2 drops (we just keep it pre-mixed in the bathroom near her bedroom). CD has been the single most important catalyst to Natalie's improvements/healing over the past 10.5 months; utilizing all three modes of delivery (oral, baths and enemas). Kerri having escorted CD into the ASD community is like a Miracle, in my opinion. Sorry... I don't mean to be corny nor impose my Beliefs on anybody else; but I sometimes find it hard to contain my Joy now and I get chills just thinking about all of the children now feeling better and/or beginning to feel better and better with CD. Before CD, it was hard to feel Hope for my special little Natalie; who was formerly suffering very extreme PANS flares and re-flares monthly as well as rapid-onset grand mal (tonic clonic) seizures every 2.5-3 weeks on top of her ASD and global developmental disabilities. Now Natalie's PANS 'flares' if/when they occur are waaaayyy less intense and better-controlled/'snufffed out' with CD than the former roller-coaster of oral antibiotics that her Drs had tried for years, her seizure activity is decreasing significantly and we've even begun a slow reduction in her anti-seizure med Lamictal ODT. We're optimistic that Natalie will be able to remain stable on less and less of that med, as we feel it might be causing her some nasty side effects. Our Hope for her is that she might even be able to come fully off of Lamictal ODT, as we continue CD and PP for her. Time will tell. While she's still a 'work in progress' [Note: She's 14 years old and been ill since infancy and it's a bit harder to heal longterm infection(s) and/or infestation(s)], we do see lowering ATECS in Natalie's future and brighter and brighter days. Patience is a virtue. So Grateful. Thank you Kerri and all you supportive Moms & Dads. More and more healing to come to ALL of our children!*

---

180. *Hi Kerri,*

Thank you for helping my daughter, age 15, recover from Autism. Thank you for the MMS/CD program and the support to carry it out. Here is a summary of her recovery:

June 19, 2012 Atec=52

Started with MMS slowly, adding one drop a day

GF/CF/SF diet

It took her 1 1/2 months to get to full dose.

Noticed improvement in physical health & behavior

Began parasite program

Sept. 18, 2012 Atec=24

Continued with 6-8 doses/day & baths

More improvements

School discontinued IEP, because she was doing so well academically and socially

January 15, 2013 Atec=19

My daughter, who is not vaccinated, comes down with Chicken Pox

No one at school or in community had it before her. It appears to be an isolated case.

It may have been in her system and released as parasites died?

Fever of 102 degrees for two weeks was the lead up to the Chicken Pox. Seemed like her immune system woke up! After chicken pox, huge gains! That is when we noticed she was recovered!

April 25, 2013 Atec=6

Yeah!

* * *

Please share your experiences!

Testimonials are one of the best ways to share your experiences with this protocol. Perhaps you learned about it by reading or watching a video testimonial?

If you don't tell us your experiences, we can't share them or take action on issues that need improving or correcting...

Send your testimonials to:

testimonials@cdautism.org

Also, let us know if we are free to publish your testimonial, with or without your name.

It's in our interest to take care of others. Self-centredness is opposed to basic human nature. In our own interest as human beings we need to pay attention to our inner values. Sometimes people think compassion is only of help to others, while we get no benefit. This is a mistake. When you concern yourself with others, you naturally develop a sense of self-confidence. To help others takes courage and inner strength.

~ Dalai Lama

Appendix 2

CD Autism Worldwide

Since September of 2011 over 5,000 families in 58 countries have used CD to help with an autism spectrum disorder. Here is a list of all the countries who have at least one family using CD to help heal the symptoms known as autism. This list is constantly updated at www.CDAutism.org.

- Argentina
- Australia
- Austria
- Belgium
- Bolivia
- Brazil
- Bulgaria
- Canada
- Chile
- China
- Colombia
- Costa Rica
- Cuba
- Czech Republic
- Dominican Republic
- Ecuador
- Egypt
- England
- France
- Germany
- Ghana
- Greece
- Hungary
- India
- Iraq
- Ireland
- Italy
- Japan
- Jordan
- Kenya
- Kuwait
- Malaysia
- Mexico
- Montenegro
- Morocco
- New Zealand
- Norway
- Panama
- Peru
- Philippines
- Poland
- Portugal
- Puerto Rico
- Qatar
- Russia
- Scotland
- Singapore
- Slovakia
- Slovenia
- Somalia
- South Africa
- Spain
- Swaziland
- Sweden
- Tanzania
- Turkey
- United Arab Emirates
- United States
- Venezuela

If you are using CD for autism in a country not listed above please email us so we can add you to the list... kim@cdautism.org.

Conformity is the jailer of freedom and the enemy of growth.

~ Robert F. Kennedy

Appendix 3

AutismOne on Healing Autism: Accidental Cure by Optimists

by Simon Yu, MD

Accidents happen. We accept the reality of them as is and we usually move on. On the other hand, accidental discovery is another story. For some people, they ask questions like, “why me?” Or keep asking for a deeper meaning: Is this really an accident or a message to understand? An accident is a fertile ground to find out if you are a pessimist or optimist.

Tom Jacobs, story teller from Kansas City, recently told a story about a pessimist and optimist: Two sales men were assigned to Africa in the early years of the shoe industry to sell their shoes. One week later, one salesman telegrammed to his boss, “Business situation in Africa is hopeless. Nobody wears shoes”. On the other side of the continent, the other salesman excitedly telegrammed to his boss, “Unlimited potential in Africa. Nobody wears shoes!”

I don’t know about you but I would rather be an optimist. I always encourage my patients to look at the bright side and be cautiously optimistic no matter how grim their conditions might be. Hope is a powerful driving force to promote healing. Pessimists do not call themselves pessimists. Just realists.

Today, I saw a 77 year old patient with a history of chronic pulmonary fibrosis, bronchiectasis and rheumatoid arthritis with a recent diagnosis of stage one bladder cancer. She has been depressed and joined a cancer support group because of feeling a sense of hopelessness.

After a long discussion, I told her how lucky she is that her lung and rheumatoid conditions have been stable and she has only a relatively benign early stage of bladder cancer. I told her if you are going to have cancer, this is the kind of cancer to have and she should be thankful. All of a sudden, her doom and gloom mood was lifted with a broad smile. The rest of our session was uplifting.

The AutismOne 2013 conference was held in Chicago during Memorial Day weekend. I was invited to give a talk on parasites, allergies, and autism. Autism is not my field. I usually see adults as an Internist. However, beginning in 2012, I have been seeing autistic children with rather interesting responses. In May 2013, I wrote an article about a medical hypothesis of a relationship between parasite infection and autism in preparation for my lecture for the AutismOne conference.

I attended a full day of lectures and was awestruck by the thousands of autism parents from all over the country attending the lectures. Multiple lectures were conducted by many autism specialists at the same time covering a large variety of topics. This conference was driven by a grass roots movement of parents with a hope to help their children. Here is a short synopsis of the lectures.

Dr. Anju Usman, MD from the Chicago area covered gut-brain connection and biofilms by pathogens in the gut. Symptoms such as depression, anxiety, poor attention and focus, and obsessive compulsive behaviors may be related to the delicate balance of bugs which produce a mucous slime known as biofilm.

Andreas Ludwig Kalcker, Ph.D. Bio-Physicist from Spain, who studied under German bio-physicist Fritz Albert Popp, Ph.D., discussed parasites in depth. He demonstrated a successful treatment for more than 65 children around the world with his parasite protocol over a one year period.

Kerri Rivera, from Mexico, one of the main leaders of the group running the AutismOne conference, showed many cases of successfully treated autistic children including her child. She has been using chlorine dioxide in conjunction with diet, nutritional supplements, detox, and hyperbaric oxygen.

By the time I presented my medical hypothesis on parasite infection and autism, they had already had numerous discussions about parasites and had been saying all along how parasite infection might be one of the major underlying problems for autism that has been overlooked. I felt like I was repeating what had already been presented.

Dr. Andreas Kalcker and Kerri Rivera collaborated using chlorine dioxide for two years with prescribed parasite medications, albendazole and pyrantel pamoate, to turn around autistic children. Professionally, I have no experience using chlorine dioxide on my patients. The difference with my therapy was that I was using acupuncture meridian assessment as a guide to detect and treat parasites.

If what they are reporting is even partially true for these autistic children, it would be a major breakthrough in the autism community. Some of the audience was crying in excitement but some were skeptical and saying it sounded too good to be true. I could feel the excitement of the audience but also a sense of fear that Kerri Rivera and Andreas Ludwig Kalcker will be attacked by special interest groups. Chlorine dioxide is too inexpensive to a fault.

Is this an accidental finding leading into an accidental cure for autism? It is too early to tell but any chronic medical conditions like cancer, heart disease, diabetes, arthritis, Alzheimer’s dementia, or autism seems driven by epigenetic influences from environmental toxins, parasites, hidden dental problems, and faulty diet and nutrition.

I spent several hours with Andreas Kalcker after our lectures were over. We found a common ground for treating parasites: his experience as a bio-physicist and my experience as a military medical officer. Few people truly understand and are aware of the magnitude of parasite problems. This man was very passionate to rescue these children from the scourge of autism.

Kerri Rivera just published a book called [Healing the Symptoms Known as Autism]. I just finished the book. This book is for everyone but especially for both autism parents and all medical professionals involved in the care of autistic children. The book contains much important information that is not available in the main stream autism community.

Most pediatricians might be sympathetic but they are rather pessimistic regarding the care of autistic children. Andreas Kalcker and Kerri Rivera are true optimists in the midst of skeptics and pessimists. They see unlimited potential for the cure for autism based on diet, nutrition, and parasite eradications using chlorine dioxide and parasite medications. If you want to know more about autism and what is possible, I highly recommend reading [Healing the Symptoms Known as Autism] by Kerri Rivera. The book explains in detail the Kalcker parasite protocol.

Dr. Simon Yu, M.D. is a Board Certified Internist. He practices Internal Medicine with an emphasis on Alternative Medicine to use the best each has to offer. For more articles and information about alternative medicine as well as patient success stories, and Dr. Yu's revolutionary health book Accidental Cure: Extraordinary Medicine for Extraordinary Patients, visit his web site at...

www.PreventionAndHealing.com

...or call Prevention and Healing, Inc., 314-432-7802. You can also attend a free monthly presentation and discussion by Dr. Yu on Alternative Medicine at his office on the second Tuesday each month at 6:30 pm. Call to verify the date. Seating is limited, arrive early.

Appendix 4

Autism Evaluation Treatment Checklist (ATEC)

The next page contains a copy of the original *Autism Evaluation Treatment Checklist* (ATEC) developed by the late Dr. Bernard Rimland, the founder of the *Autism Research Institute*. We are not suggesting you use this particular copy. It is only included here for those not familiar with the evaluation so you have an idea what the ATEC involves since we mention it throughout this book.

The survey consists of a series of questions to be answered by a parent about what they are observing in their child's CURRENT behavior. It is not uncommon for both parents to take the survey separately and compare/average the scores.

The best way to take the survey is online at the *Autism Research Institute's* website. Here is the direct link to the current survey:

www.autism.com/index.php/ind_atec_survey

After completing the questions, a score is generated that can range from 0 to 180. 0 means no autism while 180 would mean that the answer to every question was in the most negative extreme.

We consider a child recovered from autism if their score is between 0 and 10.

You are encouraged to complete an ATEC before starting the Protocol, and every 3 months thereafter so you can clearly see the progress you are making.

Also, please share your results with us; we collect data on the children whose parents follow the Protocol as explained in this book. Send your name, date of the survey, general location (city, state, country) and score to:

atec@cdautism.org

If you have a history of ATEC results while on the protocol, please include them all.

NOTE: Do not send questions to this email address! You are unlikely to get any response from this address! It is just a collection point.



ARI/Form
ATEC-1/11-99

Autism Treatment Evaluation Checklist (ATEC)

Bernard Rimland, Ph.D. and Stephen M. Edelson, Ph.D.

Autism Research Institute

4182 Adams Avenue, San Diego, CA 92116
fax: (619) 563-6840; www.autism.com/ari

Project/Purpose				
Score: I	II	III	IV	Total

This form is intended to measure the effects of treatment. Free scoring of this form is available on the Internet at: www.autism.com/atec

Name of Child ____________ ____________ ☐ Male Age ________
Last First ☐ Female Date of Birth ________
Form completed by: ____________ Relationship: ____________ Today's Date ________

Please circle the letters to indicate how true each phrase is:

I. Speech/Language/Communication: ***[N] Not true [S] Somewhat true [V] Very true***

N S V 1. Knows own name
N S V 2. Responds to 'No' or 'Stop'
N S V 3. Can follow some commands
N S V 4. Can use one word at a time (No!, Eat, Water, etc.)
N S V 5. Can use 2 words at a time (Don't want, Go home)
N S V 6. Can use 3 words at a time (Want more milk)
N S V 7. Knows 10 or more words
N S V 8. Can use sentences with 4 or more words
N S V 9. Explains what he/she wants
N S V 10. Asks meaningful questions
N S V 11. Speech tends to be meaningful/ relevant
N S V 12. Often uses several successive sentences
N S V 13. Carries on fairly good conversation
N S V 14. Has normal ability to communicate for his/her age

II. Sociability: ***[N] Not descriptive [S] Somewhat descriptive [V] Very descriptive***

N S V 1. Seems to be in a shell – you cannot reach him/her
N S V 2. Ignores other people
N S V 3. Pays little or no attention when addressed
N S V 4. Uncooperative and resistant
N S V 5. No eye contact
N S V 6. Prefers to be left alone
N S V 7. Shows no affection
N S V 8. Fails to greet parents
N S V 9. Avoids contact with others
N S V 10. Does not imitate
N S V 11. Dislikes being held/cuddled
N S V 12. Does not share or show
N S V 13. Does not wave 'bye bye'
N S V 14. Disagreeable/not compliant
N S V 15. Temper tantrums
N S V 16. Lacks friends/companions
N S V 17. Rarely smiles
N S V 18. Insensitive to other's feelings
N S V 19. Indifferent to being liked
N S V 20. Indifferent if parent(s) leave

III. Sensory/Cognitive Awareness: ***[N] Not descriptive [S] Somewhat descriptive [V] Very descriptive***

N S V 1. Responds to own name
N S V 2. Responds to praise
N S V 3. Looks at people and animals
N S V 4. Looks at pictures (and T.V.)
N S V 5. Does drawing, coloring, art
N S V 6. Plays with toys appropriately
N S V 7. Appropriate facial expression
N S V 8. Understands stories on T.V.
N S V 9. Understands explanations
N S V 10. Aware of environment
N S V 11. Aware of danger
N S V 12. Shows imagination
N S V 13. Initiates activities
N S V 14. Dresses self
N S V 15. Curious, interested
N S V 16. Venturesome - explores
N S V 17. "Tuned in" — Not spacey
N S V 18. Looks where others are looking

IV. Health/Physical/Behavior: *Use this code: [N] Not a Problem [MI] Minor Problem [MO] Moderate Problem [S] Serious Problem*

N MI MO S 1. Bed-wetting
N MI MO S 2. Wets pants/diapers
N MI MO S 3. Soils pants/diapers
N MI MO S 4. Diarrhea
N MI MO S 5. Constipation
N MI MO S 6. Sleep problems
N MI MO S 7. Eats too much/too little
N MI MO S 8. Extremely limited diet
N MI MO S 9. Hyperactive
N MI MO S 10. Lethargic
N MI MO S 11. Hits or injures self
N MI MO S 12. Hits or injures others
N MI MO S 13. Destructive
N MI MO S 14. Sound-sensitive
N MI MO S 15. Anxious/fearful
N MI MO S 16. Unhappy/crying
N MI MO S 17. Seizures
N MI MO S 18. Obsessive speech
N MI MO S 19. Rigid routines
N MI MO S 20. Shouts or screams
N MI MO S 21. Demands sameness
N MI MO S 22. Often agitated
N MI MO S 23. Not sensitive to pain
N MI MO S 24. "Hooked" or fixated on certain objects/topics
N MI MO S 25. Repetitive movements (stimming, rocking, etc.)

Appendix 5

MOLECULAR MIMICRY
What It Is
&
How it Relates to
The Gluten Syndrome

by Mrs. Olive Kaiser

After reading the short answers in *The Diet* Chapter (page 64), we understand (simply) the basics of how some of these departments of the immune system function. It is easier to grasp how, through molecular mimicry, gluten can damage so many different tissues in different people, and sometimes cause other foods that *look like* gluten to also be reactive. Before we go any further, I would like to thank the following professionals for their contributions to our family's well-being and a wider understanding of the gluten syndrome and other related topics. If you would like to conduct further research into this topic, the body of work that the following professionals have contributed would be a great place to start. There is so much more to learn.

Dr. Alessio Fasano, MD, shook America awake on gluten awareness in the 1990's and in 2003 published a landmark paper[1] on one small subset of the gluten syndrome, villi damaged celiac disease. That study provided the impetus that brought gluten awareness to the table (or sadly, OFF many tables) across our nation.

Dr. Thomas O'Bryan, DC, Functional Medicine, and international gluten syndrome educator - www.thedr.com. Dr. O'Bryan is my functional medicine doctor. He taught me much of what I learned about gluten and other topics and led me to his mentor, Dr. Aristo Vojdani. Later Dr. O'Bryan's amazing research review seminars on gluten contributed hugely to my knowledge base and bolstered my confidence to manage our new lifestyle in a then difficult social era.

Dr. Aristo Vojdani, PhD., MsC, Immunologist, CEO owner of *Immunosciences Lab*, Los Angeles, CA. Dr. Vojdani is also chief scientific advisor of *Cyrex Laboratories*, Phoenix, AZ. Dr. Vojdani has published nearly 150 excellent research papers.[2,3,4] They fit the community like a glove.

Dr. Rodney Ford, MD, pediatric gastroenterologist, NZ, grasped the extent of neurological injury,[5] and "silenced nerves phenomenon."[6] This compellingly suggests why many of us do not recognize symptoms of gluten damage until we are in deep trouble. This builds on the previous work of Dr. Marios Hadjivassiliou, Professor of Neurology, Sheffield, UK.[7]

Dr. Kenneth Fine, MD, gastroenterologist, Dallas, Texas, owner of an investigative research lab, *Enterolab* (www.Enterolab.com). His lab ran the only accurate gluten antibody tests our family received back in 2004.

Without the courage of these astute researchers, we would still be wandering in the dark. Thank you all, and other individuals who thought outside the box. Kerri you are one of those thinkers. Thank you!

Lastly, special thanks to **LuEllen Giera**, my support group leader, for leading me to Dr. O'Bryan and Dr. Vojdani.

1. What is Molecular Mimicry? How does gluten damage us?

The structure of gluten resembles the structure of many of our body tissues. When the immune system attacks gluten or partly digested "pieces" of gluten it may also attack body tissues that "look like" those pieces of gluten. There may also be other processes that we do not yet understand.

What is gluten? - Gluten is a stretchy protein found in some bread grains. The problematic types are found in wheat, barley, and rye, and now early research suspects possibly rice, corn and oats (Dr. Peter Osborne, DC, CCN, www.glutenfreesociety.org).

What are proteins? - Proteins are a class of materials found in living tissues, such as hair, nerves, enzymes, etc. Molecularly, all proteins look like necklaces of beads strung into various color sequences. The different sequences make the proteins different, and the "colored beads" represent 22 separate amino acids. Our digestive system uses enzymes to cut up these necklaces into single beads so they are small enough to cross the gut wall properly and be restrung into new proteins. See image on page 452.

Unfortunately, many folks today are toxic and poorly nourished and do not have strong digestion, so the gluten "necklaces" may never completely break down. As weaker bonds between the beads break, "pieces", called "peptides," of gluten are formed. Gliadin is a well known gluten piece and there are many others.

Our immune system - has "departments" to protect us in various ways, including IgA, IgG, IgE, IgM, IgD and others. IgE can cause immediate allergic reactions to bee stings or peanuts, etc. IgA, IgG and IgM may react more slowly with less drama. They all manufacture "workers" or "soldiers", called antibodies, each custom designed to patrol our bodies, looking for the bead sequence of one particular enemy. When they find that bead sequence, they "tag or stick onto" it. Our killer white blood cells interpret the antibody tag as a condemned sign and know to surround and destroy that protein.

If an antibody test lists "Gliadin – IgA", "Gliadin – IgG", and"Gliadin – IgM" it means the test checked for gliadin antibodies in the IgA, IgG and IgM departments. If the antibodies are high it means the immune system is does not like gliadin and is working to destroy it.

Weak, leaky barriers - Our gut wall and other barrier membranes such as the skin, lung, placental, and blood brain barriers are held together with "tight junction proteins" that act like velcro. Inflammation, parasites, gluten, medications, infections, electrosmog, etc, may damage the "velcro" or open them up too much. Substances may slip through them into places they should not be and cause trouble.

Unfortunately if the gut wall does not hold together well, i.e., is "leaky", pieces of incompletely digested gluten strings (and others) may slip through and run into the immune system—our dutiful "guard dog" on the other side. Due to their too-large size "he" may raise the alarm. The invader strings are "frisked out" i.e., examined. If they are rejected, one or more of the immune departments make matching antibodies to "tag" them so the killer cells know to go after them.

It is at this point more problems may arise. A gluten antibody may "run by" a natural body tissue, for example a nerve in the heart. It may see in that innocent nerve tissue a sequence of "beads" that matches or partly matches the gluten sequence it was designed to "tag" and stick to that section of the nerve protein instead. This, unhappily, attracts killer cells to the misidentified nerve, resulting in autoimmune injury to the nerve. This is molecular mimicry.

Other foods and proteins beside gluten may also initiate molecular mimicry when they prematurely cross a leaky gut, and may prompt allergies (IgE) or intolerances (IgA, IgM, or IgG). However specialists agree that gluten's particular "bead" (amino acid) sequences are uniquely guilty in their ability to upset the immune system and instigate molecular mimicry between "their" antibodies and our tissues.

Molecular mimicry can take place between non-food proteins and body tissues also. Infectious microbe sequences such as strep, for example, are believed to partially match, (in the case of strep), heart and joint proteins and so injure the heart muscle or valves, and (rheumatic) joints. Ditto is suspected for root canal and cavitation infections that may circulate and injure specific tissues, including the heart. Flu microbe sequences can resemble gluten and may trigger or surface gluten syndrome. There are numerous other examples of mimicry between infections, foods and body tissues.

Consider the image below. An antibody may be made to seek the shorter "bead" sequence of a gluten piece that crossed the gut wall, but it might also recognize a similar sequence, a partial match, in the longer nerve protein sequence. The antibody "tags" or "sticks to", the part of the nerve tissue that matches the gluten piece that it seeks.

<table>
<tr><td colspan="16">Gluten Peptide (and antibody) Sequence
Note: the different colors represent different amino acids.</td></tr>
<tr><td></td><td></td><td></td><td></td><td></td><td>pink</td><td>blue</td><td>white</td><td>brown</td><td>brown</td><td>brown</td><td>red</td><td>red</td><td>green</td><td></td><td></td></tr>
<tr><td colspan="16">Nerve Sequence</td></tr>
<tr><td>orange</td><td>orange</td><td>yellow</td><td>green</td><td>red</td><td>red</td><td>blue</td><td>white</td><td>brown</td><td>brown</td><td>brown</td><td>red</td><td>orange</td><td>green</td><td>blue</td><td>yellow</td></tr>
</table>

It gets more complicated, but eventually the victim tissue is attacked by killer cells on an ongoing basis. This process may be slow but stealthy. In time, the nerve may malfunction and the organ it serves may also begin to fail; for example, heart failure. This is termed autoimmunity. The body attacks its own tissue.

Molecular mimicry can occur in hundreds of places in the body since gluten can break up into numerous pieces having amino acid sequences that partly match many of our natural tissues. This may explain why gluten syndrome presents so differently in different people.[2]

Once this process starts, like elephants who never forget, the memory B cells that manufacture the antibodies never forget the sequence of the "invader" gluten pieces. If gluten is removed, antibody manufacture eventually stops, but any time the immune system sees even a tiny amount of that protein sequence, antibody production is retriggered. This is why specialists insist the gluten-free diet is strict and lifelong.

Gluten removal stops production of the initial antibody, which decreases the inflammatory process significantly. Literature shows the gluten-free diet may reverse or improve many serious conditions, but it may not always arrest an advanced autoimmune disease. Prevention is key.

Example: Once a ball is pushed down a hill, further pushing will only send it downhill faster, but it will roll on its own. To correlate, molecular mimicry between the gluten antibody and victim tissue starts the ball rolling. Removal of gluten stops pushing the process, and the sooner the better. The longer the exposure[8], and to other factors as well in a triad of autoimmunity (a. environmental stress, toxins, infections, etc.; b. a faulty blood brain barrier; and c. susceptible genetics), the higher the chance of autoimmune disease.

Dr. Vojdani comments, "If it is detected early enough and steps are taken early enough the condition may be reversed. If any condition is advanced enough you can reach a point when simple removal may not be enough. Autistic children generally have autoimmune reactivity rather than full-blown autoimmune disease, which is why they show great improvement upon the removal of gluten."

2. Does gluten always damage the villi of the small intestine as the celiac story teaches? Many other tissues such as thyroid, pancreas, blood vessels, joints, brain, nerves, liver, bone, etc. may be involved in this disorder. Does all that other damage arise due to poor nutrient absorption from injured gut villi?

No, according to published research many researchers and practitioners now believe the villi are not always damaged in an autoimmune gluten reaction.[2] Where there is no villi damage, injury to other organs cannot be due to nutrient deficiencies caused by villi damage. Molecular mimicry provides a mechanism for direct autoimmune gluten injury to many other tissues and organs when the villi are fine. It is also possible that several tissues and organs, *including villi,* may be injured and then nutrient deficiencies from poor villi absorption may affect other areas.

Dr. Vojdani's abstract in his editorial, *The Immunology of Gluten Sensitivity Beyond the Intestinal Tract,*[2] supports that the villi are not always injured. To quote his editorial abstract, "Evidence has been accumulated in literature demonstrating that gluten sensitivity or celiac disease can exist even in the absence of enteropathy" [gut/villi damage], "but affecting many organs."

3. I do not have damaged villi, and my tTG/gliadin blood tests were negative, but I feel so much better gluten-free. Why?

The tests were likely false negative. That is very, very common. As gluten is processed in the digestive system, it can break into more pieces than we have tests developed to check them, and the immune system makes an antibody for each separate piece. The test probably missed your antibodies because they were different from the one or two the test checked. Many patients have proven this because they received negative results to the standard test, and then found a number of positive gluten related antibodies when they ran a more comprehensive panel. Cyrex Laboratories (www.cyrexlabs.com), runs 28 gluten related antibodies in 3 areas of the immune system.

Your properly performed* biopsy was probably negative because likely your gut villi are fine.** Your gluten injury may have targeted other organs or tissues, not the villi.*** For instance, if gluten has damaged the heart, snipping intestinal villi will not help find the heart injury. Damage in either place is not ok.

More detail on False Negative Tests

The blood and saliva tests - Standard celiac blood and saliva tests only check tissue transglutaminase IgA, (tTG – IgA) as an initial screener. Most doctors give up if that test is negative. However, the literature shows that standard tTG-IgA tests are only elevated when the villi are completely destroyed. Dr. Vojdani finds that form of tTG is often not found in other gluten injured tissues. Therefore the standard tTG-IgA test is a poor screener for most patients, and returns many false negatives. More forms of tTG have now been discovered.

Doctors might also order a standard test for deamidated gliadin IgA and possibly IgG. Unfortunately these tests also have a miserable failure rate for picking up gluten syndrome because many patients have other antibodies beside those two. The gluten "string" can break up into many other pieces, plus other "departments" of the immune system may react.

---

* If there IS villi damage it is possible for the biopsy to miss it if the damage is patchy or further down the duodenum than the villi samples are taken. Most good "gluten aware" gastroenterologists take a number of samples to try to avoid this possibility.

** It is possible that very early villi damage may slowly accumulate long before it shows up on a pathology report. An elevated IEL count, (intraepithelial lymphocyte, an early sign of inflammation) of the villi tissue indicates this process is underway. Ask the gastroenterologist to specify that the pathologist do an IEL count.

*** I am careful to specify the "villi of the gut". There may actually be gut damage, but not to the villi. There are many types of tissue in the gut, such as nerves, for instance. The villi may be fine, but it is still possible that some other gut tissue may be damaged by molecular mimicry or other processes we do not yet understand. For instance, if the nerves that control peristalsis (wave like gut motion) are injured, it could result in chronic constipation.

Villi biopsy vs. positive antibodies for diagnosis? - To add insult to injury, even if antibodies are discovered, many celiac, villi focused specialists may still insist that the villi biopsy is the final word for "celiac" diagnosis and they trust a negative villi biopsy over positive antibodies. Many folks have positive antibodies and suspicious symptoms, including improvement upon gluten removal, but no apparent villi damage. Their doctors assure them they can eat gluten! This is a serious mistake for many patients.

More on the villi biopsy – By now it is easy to understand why even properly performed* villi biopsies are only useful for the relatively small subset of patients in which the villi of the duodenum are injured. Most patients do not happen to have damaged villi. Their damage is somewhere else in their body, other organs, nerves, etc., or some enzyme or functional item has been damaged by gluten antibodies. Scientists such as Dr. Aristo Vojdani[2,3,4,] do NOT recommend villi biopsies for gluten syndrome diagnosis (there may be other reasons to scope the gut, such as tumors, etc). Dr. Vojdani explains that if there are elevated antibodies to gluten, the immune system is screaming "I do NOT want this substance! I am manufacturing antibodies to tag and destroy it." That is sufficient reason to remove gluten from the diet. It is less expensive to check an extensive array of gluten antibodies than undergo an endoscopy anyway, and is much less invasive.

4. Why do many gluten syndrome patients not only react to wheat, barley, and rye but also sometimes to other foods, particularly oats, milk, corn, soy, egg, coffee, sesame, yeast, chocolate and others.

These foods have similar amino acid sequences to gluten. Now that we grasp molecular mimicry, this is logical. The immune system may misrecognize them for gluten, causing cross reactions which may keep the gluten antibodies running high even on a gluten-free diet. Happily, this does not always occur. Cyrex labs, Array # 4, checks a list of cross reactive and gluten substitute foods, IgA and IgG.

5. The diet seems excessively strict? Why does it take so little gluten to start a reaction?

We understand that miniscule amounts of bee venom, or peanut, can trigger emergency allergic reactions, and very tiny medication pills can cause major effects on our bodies. This is also true of gluten reactions, both immediate allergic IgE, and delayed IgA, IgG, and IgM.[3] "Crumbs matter." The difference is that delayed reactions are not as obvious as the allergic reaction. They may go unnoticed for hours to decades, but may be a long, slow, serious process. Their lack of drama robs these reactions of the compliance respect they deserve.

6. The silent syndrome - Why do many people react to gluten, proven by antibody tests, but they have few or no warning signs, or seemingly unrelated symptoms they do not recognize or connect with their diet for a long time. Then they crash with something serious, often or usually autoimmune?

Gluten is famous for slowly injuring nerves[5] by molecular mimicry, and in many cases the nerves are silenced by that injury.[6] The patient does not realize there is a problem until the tissue or organ that those nerves supply begins to fail. Furthermore some areas of the body do not contain many pain nerves, so we may not feel the damage. Slow silent damage is understood in other diseases. Heart damage, cancer, and aortal aneurysms are examples of conditions that develop silently and then suddenly flare. Prevention is best.

For years, celiac literature recognized 2 neurological conditions, peripheral neuropathy and gluten ataxia. In the wider perspective of gluten syndrome, nerve damage may be one of the most important areas of injury.[5]

Dr. Rodney Ford, MD, suggests in his book, *The Gluten Syndrome: Is Wheat Causing You Harm*,[6] that this is primarily a neurological disease[5], injuring and in some cases silencing nerves, compromising the health and function of the tissues they serve. This idea was reinforced by an astute observation made by Dr. Ford of one of his patients, an elementary school child who had not achieved bowel control. After she went gluten-free, the problem resolved. Dr. Ford realized the child now recognized the signal to visit the toilet, and accidents were avoided. The nerves in the lower bowel apparently "woke up" once the antibodies that injured them disappeared. This is an interesting and logical theory to explain "silent gluten injury", and it fits the community. Here is an abstract of Dr. Ford's published paper which discusses a possible widespread neurological focus:[5]

The Gluten Syndrome: A Neurological Disease, by R.P. Ford

Hypothesis: gluten causes symptoms, in both celiac disease and non-celiac gluten-sensitivity, by its adverse actions on the nervous system. Many celiac patients experience neurological symptoms, frequently associated with malfunction of the autonomic nervous system. These neurological symptoms can present in celiac patients who are well nourished. The crucial point, however, is that gluten-sensitivity can also be associated with neurological symptoms in patients who do not have any mucosal gut damage (that is, without celiac disease). Gluten can cause neurological harm through a combination of cross reacting antibodies, immune complex disease and direct toxicity. These nervous system affects include: dysregulation of the autonomic nervous system, cerebella ataxia, hypotonia, developmental delay, learning disorders, depression, migraine, and headache. If gluten is the putative harmful agent, then there is no requirement *to invoke gut damage and nutritional deficiency to explain the myriad of the symptoms experienced by sufferers of celiac disease and gluten-sensitivity. This is called "The Gluten Syndrome."*[5]

7. Why do so many of us react now, when for centuries most people appeared to be fine with wheat? After all, wheat is spoken of positively in the Bible and many other historical documents.

There may or may not be a conclusive answer to this question, but a few factors may play a role.

a. Many folks have higher toxin levels now, their nutritional status is worse, and digestive strength is weaker.

b. Today's wheat is different. Gluten grains have been subjected to a lot of changes, some genetically violent, according to Nina Federoff, a pro GMO scientist. She asserts in her book, *Mendel in the Kitchen*, that gluten grains were altered with nuclear radiation and chemical mutation by the 1950's – 1960's.[9] Recently a stash of old blood samples from that era, stored in a freezer by the military, were checked with standard celiac antibody tests. The incidence of positive antibodies was much less in those samples than is typically found in the general public today.

c. Wheat seed is sometimes treated with mercury. Might this play into unintended results?

8. Why do specialists and researchers insist that the gluten-free diet must be life long? Can't we heal the gut and go back to our beloved wheat bagels, croissants, and brownies?

Our scientists insist that gluten-free is a strict lifelong commitment. The memory B cells in the immune system never forget what the enemy "looks like." Today's gluten is a violently altered substance according to the very scientists who defend genetic alterations.[9] It is not worth playing with today's wheat. There is something strange and unpredictable about it. Even if a leaky gut has healed, future circumstances, toxins and stress might injure it and retrigger the syndrome, perhaps silently. Researchers say gluten creates leaky gut for a few hours in everyone.

Particularly since gluten appears to be the "bad boy" that predisposes to other intolerances, I prefer to walk away for life and concentrate on other nutrient dense foods. However, it is wise to consume whole foods rich in B vitamins, (ex., liver or bee pollen), and silica (the herb horsetail, "equisetum hymale" species, is a source,) as gluten grains contain those nutrients.

9. Traditional peoples soaked and/or sprouted their wheat berries and then made sourdough bread with it. Does that process alter the gluten sufficiently for gluten syndrome patients to safely consume it today, particularly organic spelt and einkorn?

No. These methods make bread more digestible, but the fermented products and ancient gluten grains still contain gluten and can trigger reactions in research trials. Even if there are no visible reactions, silent injury cannot be ruled out without long term research. Additionally, the preparation process before fermentation is completed is definitely gluten based, so significant cross contamination issues come into play in the kitchen. Healing the gut is a challenge. Other areas crop up that need cleanup too, such as the parasite issues. Gluten specialists advise us to go gluten-free, stay that way, and move on.

10. What are gluten withdrawals?

Rarely, a few days to a few weeks after going gluten-free, or after being glutened, a patient may experience a few hours to a couple of weeks of a parade of varied and unusual symptoms including dizziness, black pit depression, crying, physical or emotional exhaustion, even as in difficulty getting up to use the rest room, and other odd symptoms. In severe cases they may experience an inability to socialize, make eye contact, make decisions or hold a normal conversation. Children or teens may act out in extreme ways during this situation. Often patients cannot bring themselves to discuss this experience afterward. However, a patient reluctantly described her experience 2 years later as "encountering an empty white board with nothing on it." The rest of life around her seemed to be "across the Grand Canyon." This appears to be a temporary crisis that resolves anywhere from a few hours to a couple of weeks or so according to folks who contact me about them. It is assumed that this phenomenon is due to particular pieces of gluten strings called gluteomorphins with amino acid sequences which resemble opiate drugs. When these gluten pieces disappear from the blood stream the patient may experience "withdrawal," very much like a drug withdrawal. Another theory for why this may happen involves changes in blood flow to the brain that may create a temporary neurological crisis. Autistic children may suffer these withdrawals and may take longer to stabilize, but they usually make nice gains after the crisis passes. Happily, once withdrawal is over the patients are usually much better, and they are VERY vigilant with their diet.

In the rare event that this type of reaction might occur, family and friends of the person do well to understand that the person may (or may not) be able to prepare their own food, for instance, but not be able to verbally communicate much, make eye contact, hold a conversation, answer questions, and may be uncharacteristically snappy particularly if others attempt to communicate with them. Family members may wish to be quietly and unobtrusively nearby until the person passes through this stage. If the patient has children to care for, help may be needed, and also solitude, rest, and simply prepared "real" nourishing food that is gluten-free and easy to digest such as bone broth. Probiotics or old fashioned fermented raw veggies or sauerkraut from the refrigerated section of the health food store may be helpful. Family and friends should not take the person's temporarily withdrawn personality personally.

For details on these unstudied rare reactions, or if you need support during a crisis, see...

www.theglutensyndrome.net
/Adverse_reactions.htm

...or contact me at *jka8168@sbcglobal.net*. I collect testimonials, so feel free to contribute if you have experienced this type of reaction. We hope these reactions will eventually be studied.

11. Should I replace all the gluten foods I routinely eat with gluten-free substitutes?

No, most gluten-free substitutes are still mainly expensive processed food (aka junk food). For the first few weeks it is normal for newbies to look for substitutes to replace their "old gluten friends" and it helps them make the very real emotional transition, but there are better, more nutrient dense food choices. The substitutes are still high carb, (potato, corn, tapioca, rice), and most contain sugar, processed gums, GMOs and ingredients that do not help us get well. We may actually eat more of them BECAUSE they are gluten-free. Additionally they are expensive and not always easy to prepare at home.

Many experienced gluten-free folks gradually wean themselves off a constant diet of the rather junky substitutes in favor of other real unprocessed foods, such as meat, eggs, veggies, fruits, nuts, fermented vegetables, bone broths, and so on according to their digestive abilities. The gluten-free substitutes become the occasional treat, such as pizza crust. Gluten free families are wise to find the healthiest GF versions of just the items they miss the most, and skip the rest. For example, at our house, I had served gluten spaghetti for years, but when I dropped that habit, no one noticed. However, my husband wanted his breakfast toast, so we found a gluten free brand he liked and continued that tradition. Each family works out these adjustments for themselves.

Lettuce wraps are crunchy and yummy instead of sandwiches. Hamburger patties without the bun but with onion for the onion lovers, are still tasty and they feel better afterward. In our family we now use watermelon or a watermelon basket for birthday "cake", complete with candles and a bow in the summer. Fruit pizza with a nut flour or nut/date crust, avocado chocolate or other dairy-free or fruit based pudding for the sauce, and an artistic fruit/coconut topping works for parties. There are lots of ways to celebrate happy healthy gluten-free, junk free birthdays.

12. Warning! Formal gluten challenges for testing purposes – risky!

A word of caution. Antibody tests must be performed while the patient is still consuming gluten or shortly after going gluten-free. Sometimes doctors advise patients who are already gluten-free to go back on gluten, 4 slices a day for 4-6 weeks to restart the antibodies for testing purposes. Patient experience has shown that once the system is fairly clean of gluten, going back to perform a formal gluten challenge for testing purposes may be risky. The secondary reactions for some individuals can be significant, particularly neurologically. Challenges have been known anecdotally to trigger psychological black pit crashes, fibromyalgia, and other organ injury. Autistic children may have a hard time when they just go gluten-free initially or consume gluten accidentally. A planned challenge for them may be very unwise.

13. Intermittent infractions (aka cheats) are seriously unwise and may increase injury.[10]

This is not a fad, or cheater's diet. The gluten-free diet is a medical diet to treat or control serious autoimmune, inflammatory, and often neurological diseases. There is no room for casual infractions. Research suggests that repeated, intermittent cheats, even every few weeks, over time may actually influence mortality rates.[10] This is not a reason to avoid the diet, but to take it seriously. Once the strictness of the diet is embraced the patient or family adjusts and discovers that it is doable. Gluten-free food bars, nuts, a packet of gluten-free soy sauce, and GlutenEase™ or other brands of DPP IV enzymes are good to keep in the glove compartment or backpack to handle emergencies. NOTE: DPP IV (pronounced DPP 4) digestive enzymes help break down gluten but they do not stop a reaction and are NOT a reason to cheat. However if there is a possibility of exposure it makes sense to take them for whatever help they might afford. In the case of a confirmed gluten exposure, take the enzymes, keep the bowels moving, stay calm and deal with it. Worry and drama makes everything worse.

14. Discrepancy – The celiac focus uses villi biopsy for diagnosis. The wider perspective relies on positive antibodies or improvement on the diet. Question? How did villi damage become the gold standard?

The first place the medical profession found conclusive damage by gluten in the 1950's – 60's was to the villi of the gut. After the endoscopy tool was developed, villi damage and subsequent healing upon gluten removal could be observed. They concluded that gluten damaged the villi. This was true. The particular subset of cases they scoped had villi damage, but their conclusion that the villi were the only target of damage for everyone with gluten syndrome was too narrow according to research today.[2] In most patients the target damage was NOT the villi, but the bones, joint lining, heart, thyroid, pancreas, liver, brain, almost any organ, blood vessel walls, nerves almost anywhere in the body, and so on. The patients might even have injury to multiple tissues, BUT NOT NECESSARILY ALWAYS TO THE VILLI. When the villi biopsy was declared the gold standard for gluten syndrome diagnosis, it cut out most of the patients who were reacting to gluten. Snipping villi does no good if the damage is in the thyroid or brain. For the next 60 years very few patients were prescribed a gluten-free diet because most of them did not have damaged villi, (or the doctor never thought to look at all). Their gluten-induced injury was somewhere else in their body, so they were never diagnosed.

15. Discrepancy - The villi damaged celiac disease story teaches that celiac disease is autoimmune and much worse than "non autoimmune" non-celiac gluten syndrome (NCGS). The wider gluten syndrome perspective teaches that both are autoimmune and serious.[2,3,4]

A significant disagreement exists over the autoimmunity of non-celiac gluten syndrome (NCGS). In the beginning, antibodies to gluten could not be found in NCGS patients, therefore it was assumed that NCGS was not autoimmune. However, Dr. Vojdani insists NCGS IS autoimmune. The NCGS patients have plenty of antibodies, just different ones than the standard tests check. His tests, which check and find more antibodies,**** the illnesses these patients develop, and recoveries or improvements on the diet all prove his point. He also asserts that NCGS can indicate a gut wall in worse shape than the celiac villi damaged subset.[2,3,4] The damage is simply somewhere else, not to the villi. See the link below for diagrams of these reactions, and compare the condition of the gut wall in the celiac diagram with the gut wall in the gluten intolerance diagram.

**www.TheGlutenSyndrome.net/
VojdaniDiagrams.htm**

**** Dr. Vojdani's research found several more forms of both tTG, and gliadin antibodies, (alpha, gamma, omega), gluteomorphins, glutinins, and others. His saliva and blood panels check 12 separate antibodies in 3 different immune departments and 2 mediums, totaling 28 gluten related antibodies. The two panels, run together, nearly always find antibodies if they are present in the patient, translating to far fewer false negatives.

> This disagreement fosters confusion among NCGS patients that villi damaged celiac disease is the "big bad boy" to avoid (true, it is bad), but that NCGS is less severe, not autoimmune. This translates in real life to gluten birthday cake for the Friday night party and then back on the gluten-free bandwagon Saturday morning, "so I won't eventually develop villi damaged celiac disease." Yes, that could happen also, particularly if the person seesaws on the diet, but the notion that NCGS is not as bad as villi damaged celiac disease is a misunderstanding according to Dr. Vojdani.[2,3,4] To repeatedly seesaw off and on gluten indiscriminately is unwise according to medical literature,[10] and community experience. Gluten exposure needs to be an accident, which happens occasionally even to the most vigilant. Casual cheats are a more risky mindset, usually meaning "more frequent."[10] Take it seriously, nerves, blood vessels, and organs are precious.

Gluten Tests with a Good Track Record

Some families cannot afford to test or good tests are not available. In the case of autism this protocol and most others require gluten-free and that is the end of the matter. Kerri takes this position partly due to cost and the miserable record of false negatives that standard tests return. The protocol does not work without the diet. Period.

Some adults are also willing to go gluten-free without a test. Their bodies tell them what they need, they listen, and are happy to find answers. Social pressure does not sway their decision or ability to comply.

In many other situations, a positive test is very meaningful. It gives patients confirmation that gluten-free is right for them, silences critics, and helps them comply with the diet. In the case of children it provides proof to the other parent, grandparents, therapists, doctor, etc. It may also come in handy if the child turns into an invincible teen who doubts he ever needed the diet in the face of pizza and beer, ditto for his future spouse and in-laws. The catch is that the test must be adequate. A false negative misvalidates the skeptics. These are decisions every individual or family must evaluate for themselves. Thankfully there are test panels with good track records now.

Absolutely, regardless of any test result, if the body is able to communicate a reaction to gluten or its removal, then that is the final answer. Be grateful and go gluten-free.

This testing section is for those who wish to test for their own confirmation or social support.

NOTE: If a patient has been ill for a very long time it is possible for the immune system to be so worn out that few antibodies are manufactured. Lower antibody counts might show a false negative but not prevent injury to innocent tissues. Also, due to the wide variety of antibodies a patient may happen to make, it is possible to run any antibody panel and miss those particular antibodies. The more antibodies that are checked the less likely this may occur, but should be considered in the event of a negative test that the patient or practitioner questions. In this case a gene test may be helpful.

Enterolab - Stool and 1 part gene tests

For 10 years Enterolab's mail in home collection research stool test stood in the gap for thousands of patients who received false negative standard tTG and gliadin blood tests. It has saved many lives, and gave our family the social confirmation we needed. This unpublished research test checks stool for tTG-IgA and gliadin-IgA only. The use of stool as the testing medium appears to pick up those antibodies most of the time, much much more often than standard tTG or gliadin IgA blood tests. However, since only two antibodies are checked, it may miss in some cases.

Dr. Fine's lab also offers a one part gene test which he believes is adequate for a reasonable price. Dr. Fine finds if a gene is present, nearly always so are the antibodies, and two genes are worse. Villi damaged celiac specialists recognize only HLA DQ 2 and 8 as gluten related, but Dr. Fine includes 1 and 3 and their subsets 5, 6, 7 and 9. In fact according to Enterolab, HLA DQ 4 is the only DQ gene that does NOT correlate with gluten syndrome. According to him, a patient needs 2 copies of the HLA DQ 4 gene to miss the predisposition. This translates to 81% of the Caucasian population with a predisposition to trigger gluten syndrome at some point in their lifetime, including before they are born.

Cyrex Labs - Better blood and saliva tests

Cyrex Labs (www.CyrexLabs.com) opened their doors in 2010 in Phoenix, Arizona. They run much more complete antibody panels designed by Dr. Aristo Vojdani, PhD., their scientific advisor, an immunologist, and researcher. Dr. Vojdani found a wider variety of gliadin antibodies, (alpha, gamma, omega) and variations of tTG in other tissues, plus gluteomorphins, and several others. He also checks an IgM antibody due to possible malfunctions in that system. Cyrex blood and saliva panels, Array #1 and #3, combined, test for 28 gluten related antibodies between 3 immune departments, 2 mediums, plus IgA insufficiency. They rarely miss a diagnosis because they look for so many antibodies. (Note: Vojdani believes stress, toxins and infections, i.e. environment, can trigger a gluten reaction without the genes.)

Gluten Free Society - Two Part Gene Test

A third approach espoused by Dr. Peter Osborne, *The Gluten Free Society*, Sugarland, Texas, (www.glutenfreesociety.org), is to run only the gene test, since any antibody panel may theoretically miss the particular ones the patient may have. He uses a 2 part test, the most complete method, and looks for both celiac and gluten sensitivity genes. A positive gene test does not prove a current immune response as do antibodies, but predisposition to it. Presence of 2 genes indicates a more severe case. Gene tests have an advantage in that they can be run anytime, gluten consumption is unnecessary, and depending on the results, useful information can be gleaned for immediate and extended family members.

Elimination Diet

The elimination diet is inexpensive. Often/usually it demonstrates improvement upon removal of gluten, or worsening upon reintroduction. Many "heads up" practitioners accept this as reason enough to go gluten-free.

There are occasional complications or interpretation issues for the elimination diet as follows:

a. Reintroduction of gluten (gluten challenge) can trigger stronger, sometimes risky reactions.[10] Stop a challenge upon negative symptoms, including depression and emotional instability, or best, don't challenge. An accidental infraction may come up that provides insight.

b. Occasionally it takes several months to see the difference, or a silent reaction may mask symptoms.[6]

c. If the patient later decides to test and is already "clean" on the gluten-free diet, blood tests will not work unless gluten is reintroduced for many weeks.[10] No! Stool/gene tests are safer.

d. There is no lab confirmation to silence naysayers.

Other Related Tests

Cyrex Labs Array # 2 - Intestinal Permeability Panel focuses on specific causes of leaky gut. This helps strategize treatment, and is an improvement over the old lactulose/mannitol test.

Cyrex Labs Cross Reactive Foods and Gluten Substitutes, Array # 4. - This specific list checks foods that commonly cross react with gluten and also foods commonly used to replace gluten. It helps customize an anti-inflammatory diet.

Cyrex Labs Predictive Antibody panels determine if or which tissues are currently under antibody attack. This predicts autoimmunity years ahead of time and gives the patient advance notice in order to address trouble spots.

Enterolab (www.Enterolab.com) offers several stool based food antibody panels and gut related stool tests.

What are the lab instructions?
Do I need to consume gluten for testing?

Antibody tests, (blood, saliva, stool), prove a reaction and require recent gluten consumption. Ideally, test first, then go gluten-free. If the patient is off gluten, call the lab for advice on the time window before the test will not work.

Cyrex Labs (www.CyrexLabs.com) tests require prescriptions and a saliva specimen and/or blood draw. If a doctor is needed to write the script, check www.thedr.com for a partial list of practitioners who are familiar with Cyrex Labs. Results are sent to the prescribing doctor.

Enterolab stool specimens are ordered online, kits are sent, home collected and mailed. No prescription is required. Results arrive on email. Enterolab's test works for several months after going gluten-free.

Gene tests do not require gluten consumption or a script and can be run at any time. Genes prove a predisposition to gluten reaction.

Enterolab's gene test is a relatively inexpensive "one part" test. It is a mail in cheek swab and reports the patient's actual genes.

Gluten Free Society (www.Glutenfreesociety.org) gene test is a "two part" (more complete) mail in cheek swab and reports yes or no for both celiac and gluten sensitivity genes.

For information on testing (I have no financial interests) see:

www.TheGlutenSyndrome.net

The latest version of this article and a complete list of references is available at:

www.TheGlutenSyndrome.net /Molecular_Mimicry.pdf

Author's note: While the information Olive has provided can be extremely helpful for adults or children who are not on the spectrum or who are suffering from other ailments, a gluten-free diet is non-negotiable for healing autism. We need to remove foods that cause inflammation and mucous, and which can produce gluteomorphin in the body. I have seen many families waste time and money doing testing only to get confused by false negatives—time and money they could have spent on recovering their child.

Online Gluten Summit – A Chance to Support CDAutism

Recently, in November 2013, Dr. Thomas O'Bryan, an internationally recognized gluten educator, put together an amazing online Gluten Summit. Twenty nine iconic experts on Celiac Disease and its wider perspective, Gluten Sensitivity, also called Gluten Syndrome, covered every possible aspect before 115,000 appreciative viewers. This set of interviews plus extra materials is available for purchase at only $3.30 per speaker and is a priceless addition to all our libraries. It also is a great gift and a good way to inform friends and family. Often our closest loved ones accept new information better from a respected professional rather than from us.

Arrangements are in place to contribute half of your purchase price of The Gluten Summit interviews to the CDAutism project. Go to the link below to order and also credit CDAutism with your contribution.

gg110.infusionsoft.com/go/tgso/Kerri

Appendix 6

Measuring the Strength of Your CD, CDS & CDH

by Charlotte Lackney

CD, CDS, and CDH work because all of them contain chlorine dioxide (ClO_2). ClO_2 is made when a 22.4% solution of sodium chlorite ($NaClO_2$) is activated with an acid, usually 4% hydrochloric acid (HCl) for CD and CDH; and 10% HCl for CDS.

Sometimes it might be useful to measure the amount of ClO_2 in those solutions, although that has not been done in the past when using CD. And, it may only be necessary to know the amount of chlorine dioxide if you are not getting the expected results. There could be a problem with the ingredients or process and knowing the amount of ClO_2 in the solution could be helpful in determining what might be wrong.

The amount of ClO_2 in a solution is measured in *parts per million* (ppm). It is always necessary to specify the volume of solution when talking about ClO_2 ppm because the ppm will vary depending on the dilution of the solution.

If using CDH or CDS with the protocol in this book, it is assumed that you are preparing them at 3000ppm. If using CDS, please keep in mind that the relative strength of one milliliter of CDS is approximately 60% of one drop of CD.

However, if the ingredients are of good quality and the CD or CDH protocol is closely followed, there is usually no need to know or measure the ClO_2 concentration.

Both CD and CDH may continue to activate inside the body from whatever sodium chlorite has not been activated outside the body. That is not the case with CDS, as it has no sodium chlorite to continue activating inside the body. Some believe that this is why many people can tolerate a higher dose of CDS than an equivalent dose of CD.

Measuring the concentration of ClO_2 can easily be done at home. You will need to purchase ClO2 test strips made by *LaMotte* or others. I have only used LaMotte Insta-Test® High-Range Test Strips, 0 to 500ppm (code #3002). The container's label has a chart showing seven colors on it wih each color indicating a ClO_2 concentration in ppm. Note: LaMotte recently changed the appearance of their labels, as shown on the right. Both are the same product. For more information, see their website:

www.lamotte.com/
en/water-wastewater/test-strips/3002.html

Directions for how to use the LaMotte test strips are printed on the side of the container and need to be followed in order to get an accurate ClO_2 concentration reading.

The numbers below each of the seven colors represent 0, 10, 25, 50, 100, 250 and 500ppm. Many people who use the test strips think the 50ppm color is the best one to use for color matching, because they can see the difference in color below and above that color more easily than the others.

If the ClO_2 solution you want to measure is suspected to be 3000ppm, how do you measure that if the test strips highest ClO_2 concentration color is 500ppm? Recall that I had said that it is always necessary to specify the volume of solution when talking about ClO_2 ppm, because the ppm will vary depending on the dilution of the solution.

So if we dilute the suspected 3000ppm ClO_2 stock solution with more water, the same amount of ClO_2 will now be evenly spread out in the larger amount of solution if stirred. There will be less ClO_2 in any one spot than before dilution, because the ClO_2 is now dispersed into a larger volume of water. Visualize what happens when a drop of red food coloring falls into a glass of water. It disperses throughout the water if stirred, and that dark red color is now much lighter because it is diluted in the water.

In order to read 3000ppm with a test strip, and have it match the 50ppm color on the container, we will need to dilute a small sample of the stock solution.

Stock solution (1ml)	÷	Desired dilution in ppm	=	Volume of water for dilution.
3000ppm		50ppm		60ml

Insta-TEST
50 Test Strips
High Range
Chlorine Dioxide
For testing sanitized water
Just dip & read!
LaMotte

InstaTest ANALYTIC
High Range
Chlorine Dioxide
50 Test Strips
Code 3002
LaMotte

The chlorine dioxide test strips (code #3002) made by LaMotte are available on the market with two different labels, although both are the same product. Both labels show the same measuring color chart on the outside of the container.


InstaTest ANALYTIC
High Range Chlorine Dioxide
0
10
25
50
100
250
500
Using a cup-size sample, immerse strip for 2 seconds.
Keep wet fingers out of the bottle

So, if we take a 1ml sample of the stock solution and add it to 60ml of water, then the stock solution is diluted 60 times its original volume. Technically, one should add the 1ml of stock solution to 59ml of water, for a total of 60ml, but using 60ml is easier to measure and you would not see the difference in ClO_2 readings if 59ml of water was used.

To measure, pour 60ml of distilled water into a small glass and then add 1ml of stock solution. Stir well to evenly distribute the ClO_2 sample in the water. Then take one of the test strips—taking care not to touch the pad of chemicals on the end of the strip—and dip it in the solution for two seconds. Keep the strip in one place in the solution and do not move it around during the two-second period.

Without flicking any of the solution off the strip, remove the strip from the test solution with the pad facing up and wait ten seconds. Now compare the color of the test strip pad to the color chart on the side of the test strips container (as shown above).

If the stock solution is 3000ppm, then the color on the test strip will match the 50ppm color on the container. Multiply 50 times 60 (the amount of dilution) and you get 3000ppm.

If the color on the test strip does not match the 50ppm color on the container, try to estimate the ppm number between container colors and multiply that number by 60 to get the ClO_2 concentration.

Tip: You can cut the strips lengthwise to get 100 strips instead of 50; just be sure not to touch the strip's pad with your fingers or your readings may not be accurate. Also it is important to keep the container tightly capped to keep moisture out which can affect the readings.

Healing
the symptoms known as
Kerri Rivera

Dana one year after
starting Kerri's protocol.

Appendix 7

Diluting HCl Concentration

The protocols in this book use two different concentrations of hydrochloric acid (HCl): 10% & 4%. Some suppliers sell both concentrations, while others only one. You may also find a source with a different concentration and wish to dilute it to 4 or 10%. The math to determine how much to dilute your stock solution is rather simple. You should have no problem if you know how to multiply, divide, add and subtract. Note: The same calculation works for citric acid if you have 50% and need to go down to 35%.

What you will need is:

- Bottle of concentrated HCl (10% or higher)
- Receiving bottle to store the resulting diluted HCl
- Graduated cylinder or other measuring cup

On the next page is a graphical representation of the dilution equation. It may look intimidating at first glance, but it is actually quite simple and is made up of three simple mini-calculations. Each box is labeled with a letter which refers to the graphic. Just fill in the numbers with a pencil and follow the directions.

We'll go over one example here: Let's say you have 10% HCl and want to make 1 liter of 4% HCl. Here's what you would have to calculate:

Desired Volume		Desired HCl %		Temporary Number
1000ml	×	4%	=	4000

Temporary Number		Stock HCl %		Amount of 10% HCl
4000	÷	10%	=	400ml

Desired Volume		Amount of 10% HCl		Amount of water
1000ml	–	400ml	=	600ml

So, in this example, you would need 400ml of 10% HCl and 600ml of water. to make 1 liter of 4% HCl. If you add them together, you should have 1000ml (1 liter).


1st Calculation
Desired Volume
Desired Concent. %
Temp. Value
Stock Concent. %
Stock Amount
×
=
÷
=
A
B
C
D
E
2nd Calculation
3rd Calculation
Desired Volume
Stock Amount
Water To Add
–
=
F
G
H
I

A	Determine the volume of the receiving bottle in milliliters. For example, if you have a 1 liter bottle, you would enter the number “1,000” for 1,000ml.
B	This is where you enter the % of the final solution. If you are making 4%, then enter “4” in this box.
C	Multiple **A** and **B** and enter the result into box **C**. This is a temporary value you will need for the next calculation.
D	This is where you enter the percentage of your concentrated stock solution–the HCl you want to dilute. If you have 10%, then enter a “10” in this box.
E	Now divide the temporary value in **C** by **D** and enter the result in **E**. This is the amount of concentrated stock HCl (in milliliters) you will need.
F	Copy what you entered in **A** to **F** for the next calculation.
G	Copy the result from **E** to **G**.
H	Do the subtraction of **F** – **G** and enter he value in **H**. This is the number of milliliters of distilled or filtered water you will need.
I	Measure the resulting volume of water calculated in **H** and pour it into the receiving bottle **I**. Finally, measure out the value in **G** and pour it into the receiving bottle **I**.

Appendix 8

Other Uses of Chlorine Dioxide

Bladder Infection Protocol (for Adults)

The protocol for bladder infection is three oral drops of CD eight times a day with a douche of 10 drops CD three times the first day, and then once every day thereafter, for 30 days (for females).

Ear, Eye, Nose Protocol

Make a mixture that contains one ounce of water for every one drop of CD. Use one drop of that mixture in the affected orifice every hour until symptoms disappear. If the issue is acute you can use one drop every 15 minutes. This method can be used in the ears for infections, in the nose for congestion/infection, and the eye for infection or conjunctivitis.

General Fever Protocol

If the person has a fever, or if you want clarification of any kind, email Kerri, but in the meantime, this will hopefully get you started:

1. Give baths interspersed with enemas, approximately eight hours apart (e.g. bath in the evening and enema in the morning or vice versa).
2. Give oral CD doses (using the person's usual number of drops) 12 to 16 times or more a day (essentially every hour); unless they stop eating, in which case, stop oral dosing. Enemas and baths can continue.
3. Have them drink lots of water.
4. Cool clothes on forehead and neck.

Please see Chapter 14, page 335 for more information on fever therapy.

Teeth

Ten activated drops of CD per one ounce of water. Put this in a spray bottle and spray on the toothbrush.

Throat Spray

Ten activated drops of CD (chlorine dioxide) in one ounce of water. Spray on throat once/hour. Recommended in the case of a sore throat.

Vaginal Douching for Yeast Infections:

Put six activated drops of CD in 60 ml of water. Hold this in for two minutes every day for a few weeks or between periods. Six drops MAX in the vagina.

CD Skin Spray

Use ten drops of activated CD per one ounce of water in a spray bottle.

CD spray is great for a variety of ailments.

- Skin
- Dandruff
- Scrapes
- Cuts
- Rashes
- Toe Fungus

Burns

Any burn should be sprayed with full strength sodium chlorite solution (no acid added) directly from a small spray bottle. Do not add citric acid or HCl at all! If you don't have a spray bottle available drip sodium chlorite solution directly onto the burn, making sure the area is soaked with it.

Wait up to five minutes, but no longer before rinsing off with room temperature water. If you fail to rinse off the sodium chlorite solution, the burn will continue to hurt and get worse.

This technique will cause the burn to heal in 1/4 the time normally required. The pain should stop almost immediately or reduce to almost zero within several minutes.

Sunburns should be treated the same way. Spray the red area, wait 1 to 5 minutes, and rinse off. If the area is still sore, in about an hour spray the area again and wait 5 minutes before rinsing off. Remember, DO NOT allow the sodium chlorite to remain in place. It must be rinsed off! The pain should be gone in a couple of minutes. Generally two doses will overcome most sunburns, but on rare occasions if the discomfort is not all gone you can use a third dose. Be sure to rinse it off.

Note that sodium chlorite is alkaline and burns are acidic. Therefore the sodium chlorite neutralizes the acidity that resides in the burned areas. This is part of the reason why burns heal rapidly after sodium chlorite applications.

Appendix 9

Blank Kalcker Parasite Protocol Chart

The next page contains a blank Kalcker Parasite Protocol Daily Chart identical to those found on pages 199 through 217. You are encouraged to copy this chart for use in your parasite protocol planning. Setting the copy machine to enlarge at 125% should fill a standard letter-sized page.

Time	Meal Time	CD / CDS / CDH	CD / CDS / CDH Bath	CD / CDS / CDH Enema	Ocean Water	Diatomaceous Earth	Lepidium Latifolium Extract (Rompepiedras / RP)	Pyrantel Pamoate (Combantrin®)	Mebendazole	Castor Oil	Neem	Probiotic
6:00 AM												
6:30 AM												
7:00 AM												
7:30 AM												
8:00 AM												
8:30 AM												
9:00 AM												
9:30 AM												
10:00 AM												
10:30 AM												
11:00 AM												
11:30 AM												
12:00 PM												
12:30 PM												
1:00 PM												
1:30 PM												
2:00 PM												
2:30 PM												
3:00 PM												
3:30 PM												
4:00 PM												
4:30 PM												
5:00 PM												
5:30 PM												
6:00 PM												
6:30 PM												
7:00 PM												
7:30 PM												
8:00 PM												
8:30 PM												
9:00 PM												
9:30 PM												

Appendix 10

Lunar Phase Calendar for Kalcker Parasite Protocol

As covered in Chapter 8, the Kalcker Parasite Protocol is administered over a period of 19 days and scheduled according to the lunar cycle. We have included an easy to follow calendar starting on the next page for the years 2014 through 2016.

Each chart page shows 6 months with each month broken up into 3 columns: Column 1 is the day of the month; column 2 indicates the lunar phase; and column 3 shows the corresponding Parasite Protocol day.

The full moon is identified with an “F” in the second column and the new moon is identified by an “N” in each month section, which usually occurs towards the end of each protocol cycle.

We have used New York as our center point since it is roughly the center of the majority of those using this book in the US and Europe. The moon phase may occur 1 day before or after the dates shown if you are in another part of the world, but the difference is not great, so feel free to use the dates shown. However, you are welcome to be precise for your particular location. The Farmer’s Almanac is a great source and provides an online calendar that can be adjusted to your location:

www.almanac.com/moon

You may also wish to install a moon phase app into your smart phone. Many free options exist.

2014 - Lunar Phases for New York, NY

Jan			Feb			Mar			Apr			May			Jun		
1	N	18	1			1	N	18	1			1	N		1		
2			2			2			2			2			2		
3			3			3			3			3			3		
4			4			4			4			4			4		
5			5			5			5			5			5		
6			6			6			6			6			6		
7			7			7			7			7			7		
8			8			8			8			8			8		
9			9			9			9			9			9		
10			10			10			10			10			10		0
11			11		0	11			11			11			11		1
12		0	12		1	12			12		0	12			12		2
13		1	13		2	13		0	13		1	13		0	13	F	3
14		2	14	F	3	14		1	14		2	14		1	14		4
15	F	3	15		4	15		2	15	F	3	15		2	15		5
16		4	16		5	16	F	3	16		4	16	F	3	16		6
17		5	17		6	17		4	17		5	17		4	17		7
18		6	18		7	18		5	18		6	18		5	18		8
19		7	19		8	19		6	19		7	19		6	19		9
20		8	20		9	20		7	20		8	20		7	20		10
21		9	21		10	21		8	21		9	21		8	21		11
22		10	22		11	22		9	22		10	22		9	22		12
23		11	23		12	23		10	23		11	23		10	23		13
24		12	24		13	24		11	24		12	24		11	24		14
25		13	25		14	25		12	25		13	25		12	25		15
26		14	26		15	26		13	26		14	26		13	26		16
27		15	27		16	27		14	27		15	27		14	27	N	17
28		16	28		17	28		15	28		16	28		15	28		18
29		17				29		16	29	N	17	29		16	29		
30	N	18				30	N	17	30		18	30	N	17	30		
31						31		18				31		18			

2014 - Lunar Phases for New York, NY

Jul			Aug			Sep			Oct			Nov			Dec		
1			1			1			1			1			1		
2			2			2			2			2			2		
3			3			3			3			3		0	3		0
4			4			4			4			4		1	4		1
5			5			5		0	5		0	5		2	5		2
6			6			6		1	6		1	6	F	3	6	F	3
7			7		0	7		2	7		2	7		4	7		4
8			8		1	8	F	3	8	F	3	8		5	8		5
9		0	9		2	9		4	9		4	9		6	9		6
10		1	10	F	3	10		5	10		5	10		7	10		7
11		2	11		4	11		6	11		6	11		8	11		8
12	F	3	12		5	12		7	12		7	12		9	12		9
13		4	13		6	13		8	13		8	13		10	13		10
14		5	14		7	14		9	14		9	14		11	14		11
15		6	15		8	15		10	15		10	15		12	15		12
16		7	16		9	16		11	16		11	16		13	16		13
17		8	17		10	17		12	17		12	17		14	17		14
18		9	18		11	18		13	18		13	18		15	18		15
19		10	19		12	19		14	19		14	19		16	19		16
20		11	20		13	20		15	20		15	20		17	20		17
21		12	21		14	21		16	21		16	21		18	21	N	18
22		13	22		15	22		17	22		17	22	N		22		
23		14	23		16	23		18	23	N	18	23			23		
24		15	24		17	24	N		24			24			24		
25		16	25	N	18	25			25			25			25		
26	N	17	26			26			26			26			26		
27		18	27			27			27			27			27		
28			28			28			28			28			28		
29			29			29			29			29			29		
30			30			30			30			30			30		
31			31						31						31		

2015 - Lunar Phases for New York, NY

Jan			Feb			Mar			Apr			May			Jun		
1		0	1		1	1			1		0	1		1	1		2
2		1	2		2	2		0	2		1	2		2	2	F	3
3		2	3	F	3	3		1	3		2	3	F	3	3		4
4	F	3	4		4	4		2	4	F	3	4		4	4		5
5		4	5		5	5	F	3	5		4	5		5	5		6
6		5	6		6	6		4	6		5	6		6	6		7
7		6	7		7	7		5	7		6	7		7	7		8
8		7	8		8	8		6	8		7	8		8	8		9
9		8	9		9	9		7	9		8	9		9	9		10
10		9	10		10	10		8	10		9	10		10	10		11
11		10	11		11	11		9	11		10	11		11	11		12
12		11	12		12	12		10	12		11	12		12	12		13
13		12	13		13	13		11	13		12	13		13	13		14
14		13	14		14	14		12	14		13	14		14	14		15
15		14	15		15	15		13	15		14	15		15	15		16
16		15	16		16	16		14	16		15	16		16	16	N	17
17		16	17		17	17		15	17		16	17		17	17		18
18		17	18	N	18	18		16	18	N	17	18	N	18	18		
19		18	19			19		17	19		18	19			19		
20	N		20			20	N	18	20			20			20		
21			21			21			21			21			21		
22			22			22			22			22			22		
23			23			23			23			23			23		
24			24			24			24			24			24		
25			25			25			25			25			25		
26			26			26			26			26			26		
27			27			27			27			27			27		
28			28			28			28			28			28		0
29						29			29			29			29		1
30						30			30		0	30		0	30		2
31		0				31						31		1			

2015 - Lunar Phases for New York, NY

Jul			Aug			Sep			Oct			Nov			Dec		
1	F	3	1		4	1		6	1		7	1		8	1		9
2		4	2		5	2		7	2		8	2		9	2		10
3		5	3		6	3		8	3		9	3		10	3		11
4		6	4		7	4		9	4		10	4		11	4		12
5		7	5		8	5		10	5		11	5		12	5		13
6		8	6		9	6		11	6		12	6		13	6		14
7		9	7		10	7		12	7		13	7		14	7		15
8		10	8		11	8		13	8		14	8		15	8		16
9		11	9		12	9		14	9		15	9		16	9		17
10		12	10		13	10		15	10		16	10		17	10		18
11		13	11		14	11		16	11		17	11	N	18	11	N	
12		14	12		15	12		17	12	N	18	12			12		
13		15	13		16	13	N	18	13			13			13		
14		16	14	N	17	14			14			14			14		
15	N	17	15		18	15			15			15			15		
16		18	16			16			16			16			16		
17			17			17			17			17			17		
18			18			18			18			18			18		
19			19			19			19			19			19		
20			20			20			20			20			20		
21			21			21			21			21			21		
22			22			22			22			22		0	22		0
23			23			23			23			23		1	23		1
24			24			24		0	24		0	24		2	24		2
25			25			25		1	25		1	25	F	3	25	F	3
26			26		0	26		2	26		2	26		4	26		4
27			27		1	27	F	3	27	F	3	27		5	27		5
28		0	28		2	28		4	28		4	28		6	28		6
29		1	29	F	3	29		5	29		5	29		7	29		7
30		2	30		4	30		6	30		6	30		8	30		8
31	F	3	31		5				31		7				31		9

2016 - Lunar Phases for New York, NY

Jan			Feb			Mar			Apr			May			Jun		
1		10	1		12	1		11	1		12	1		12	1		14
2		11	2		13	2		12	2		13	2		13	2		15
3		12	3		14	3		13	3		14	3		14	3		16
4		13	4		15	4		14	4		15	4		15	4	N	17
5		14	5		16	5		15	5		16	5		16	5		18
6		15	6		17	6		16	6		17	6	N	17	6		
7		16	7		18	7		17	7	N	18	7		18	7		
8		17	8	N		8	N	18	8			8			8		
9	N	18	9			9			9			9			9		
10			10			10			10			10			10		
11			11			11			11			11			11		
12			12			12			12			12			12		
13			13			13			13			13			13		
14			14			14			14			14			14		
15			15			15			15			15			15		
16			16			16			16			16			16		
17			17			17			17			17			17		0
18			18			18			18			18		0	18		1
19			19		0	19			19		0	19		1	19		2
20		0	20		1	20		0	20		1	20		2	20	F	3
21		1	21		2	21		1	21		2	21	F	3	21		4
22		2	22	F	3	22		2	22	F	3	22		4	22		5
23	F	3	23		4	23	F	3	23		4	23		5	23		6
24		4	24		5	24		4	24		5	24		6	24		7
25		5	25		6	25		5	25		6	25		7	25		8
26		6	26		7	26		6	26		7	26		8	26		9
27		7	27		8	27		7	27		8	27		9	27		10
28		8	28		9	28		8	28		9	28		10	28		11
29		9	29		10	29		9	29		10	29		11	29		12
30		10				30		10	30		11	30		12	30		13
31		11				31		11				31		13			

2016 - Lunar Phases for New York, NY

Jul			Aug			Sep			Oct			Nov			Dec		
1		14	1		16	1	N	17	1		18	1		18	1		
2		15	2	N	17	2		18	2			2			2		
3		16	3		18	3			3			3			3		
4	N	17	4			4			4			4			4		
5		18	5			5			5			5			5		
6			6			6			6			6			6		
7			7			7			7			7			7		
8			8			8			8			8			8		
9			9			9			9			9			9		
10			10			10			10			10			10		0
11			11			11			11			11		0	11		1
12			12			12			12			12		1	12		2
13			13			13		0	13		0	13		2	13	F	3
14			14			14		1	14		1	14	F	3	14		4
15			15		0	15		2	15		2	15		4	15		5
16		0	16		1	16	F	3	16	F	3	16		5	16		6
17		1	17		2	17		4	17		4	17		6	17		7
18		2	18	F	3	18		5	18		5	18		7	18		8
19	F	3	19		4	19		6	19		6	19		8	19		9
20		4	20		5	20		7	20		7	20		9	20		10
21		5	21		6	21		8	21		8	21		10	21		11
22		6	22		7	22		9	22		9	22		11	22		12
23		7	23		8	23		10	23		10	23		12	23		13
24		8	24		9	24		11	24		11	24		13	24		14
25		9	25		10	25		12	25		12	25		14	25		15
26		10	26		11	26		13	26		13	26		15	26		16
27		11	27		12	27		14	27		14	27		16	27		17
28		12	28		13	28		15	28		15	28		17	28		18
29		13	29		14	29		16	29		16	29	N	18	29	N	
30		14	30		15	30	N	17	30	N	17	30			30		
31		15	31		16				31						31		

Three things cannot be long hidden:
the sun, the moon, and the truth.

~ Buddha

Appendix 11

Health Benefits of Diatomaceous Earth

by Dee McCaffrey, CDC



You've probably never heard of one of the best and most economical supplements to improve your health and cleanse your body. In fact, this supplement is perhaps one of the best kept secrets ever. This relatively unknown "food" supplement is called Diatomaceous Earth, also known as DE. It is a completely natural substance that is rich in naturally occurring silica, a mineral whose list of documented health benefits continues to grow as more research is being conducted.

Some of the most recent studies show that it can strengthen bones and joints, prevent osteoporosis and restore bone health if you already have osteoporosis, boost the immune system, ward off Alzheimer's, prevent premature aging and wrinkling of the skin, and strengthens the arterial walls to maintain good heart health. Another of the benefits of silica is that it helps to destroy bad fats in the body. Used as a daily treatment, diatomaceous earth can alleviate the potentially deadly risks of high cholesterol, high blood pressure, and obesity.

Additionally, because of its physical structure, diatomaceous earth is a highly effective anti-inflammatory and internal cleansing agent for the body. It can remove intestinal bacteria, parasites, e-coli, viruses, pesticides, heavy metals, and other toxins. It has also been known to assist with vertigo, headaches, tinnitus, and insomnia.

Sound too good to be true? Read on to learn more about this overlooked multi-purpose supplement and how it can improve many aspects of your health at a fraction of the cost of other supplements.

What is Diatomaceous Earth?

Diatomaceous earth is the fossilized shells of microscopic water-dwelling organisms known as diatoms. Diatoms are one-celled plants (algae or phytoplankton) that are the primary food source for marine life. These plants have been part of the earth's ecology since prehistoric times, yet their species still exists today in both salty and fresh waters all over the world.

Diatoms use soluble silica (sand) from their environment to make their shells, or exoskeletons. As diatoms die, their shells fall to the bottom of the bodies of water in which they live. It is believed that 30 million years ago the diatoms piled up to form thick beds of chalky fossilized sediment. These beds, known as diatomite or diatomaceous earth, were discovered after the waters receded.

Today, hundreds of large deposits of diatomaceous earth occur all over the world. Some are still underwater and some are found in ancient dried lake bottoms. It has been estimated that one cubic inch of diatomaceous earth may contain as many as 400 million shells, that's how small diatoms are!

Diatomite is mined and ground into a powder that looks and feels like talcum powder. This all natural powder is called Diatomaceous Earth (DE) or fossil shell flour. It is made up of approximately 33% silicon, 19% calcium, 5% sodium, 3% magnesium 2% iron and many other trace minerals such as titanium, boron, manganese, copper and zirconium.

What Do Fossilized Shells Have to Do With Improving Your Health?

It's all about the silica.

As I mentioned earlier, the shells of diatoms are made up mostly of silica (known by chemists as silicon dioxide). Silica is one of the most abundant minerals on the planet, but most of it is in a form that is unabsorbable by humans, and there are limited numbers of foods that contain an adequate amount of the absorbable form to supply the quantity our body needs. Silica is the most important trace mineral for human health. It plays an important role in many body functions and has a direct relationship to mineral absorption. For optimal health, the average human body needs to hold approximately seven grams of silica, a quantity far exceeding the figures for other important minerals such as iron and calcium.

Silica can be found in such foods as alfalfa, beets, brown rice and oats. Bell peppers and leafy green vegetables also provide silica, while asparagus, Jerusalem artichokes, parsley, sunflower seeds and grain husks, such as barley, millet and wheat contain smaller amounts.

Years ago, the silica found in our foods was adequate, but with today's depleted soils, only about one-third of the silica needed by our body is supplied in our food.

In our youth, our tissues absorb and maintain high levels of silica— enabling our bodies to remain flexible, resilient, and energetic—but as we age, and as our dietary sources of silica are not meeting our needs, our silica levels steadily decline until they become almost non-existent. In fact, 80% of all of our body's silica is used up by the time we become adults.

Our bodies need silica regardless of our age and even when diet is not the primary factor in cases of deficiencies, we often become deficient in this essential trace element simply thorough the aging process. The effect of this steady decrease in silica levels is a progressive decline in health, increasing fatigue and acceleration of the aging process.

Diatomaceous earth, which is very high in the absorbable form of silica, can replenish silica levels in the body, which can vastly improve your health and reverse many chronic problems. Studies show that high levels of silica can:

Improve Bone Health and Stop Osteoporosis: Calcium and vitamin D alone are not sufficient for bone growth, density, strength, and flexibility. In fact, the body cannot absorb and use calcium without the presence of silica. Recent data suggests that instead of promoting healing, calcium supplements actually speed up the leeching away of bone calcium and accelerate the degenerative process of osteoporosis and similar diseases that affect the connective tissues in the human body!

To re-mineralize and repair damaged bones, it is now advised that a sufficient silica supplement be taken daily because bones are composed of mainly of the minerals phosphorus, magnesium and calcium; however, these minerals need the presence of silica to be deposited into the bones, especially calcium. Silica hastens the healing of fractures and also diminishes scarring at the location of a fracture. A great deal of research evidence indicates that silica has the ability to "morph" itself into calcium through a transmutation process. Yes, silica actually has the ability to be turned into calcium when there is a calcium deficiency and the body needs it!

That fact alone should be reason enough to supplement with DE!!

Ward Off Alzheimer's: Scientists and researchers have long hypothesized that Alzheimer's disease is linked to a build up of aluminum in the brain, and links between aluminum in drinking water supplies and Alzheimer's have now been ascertained. A factor that had been overlooked is that silica reduces the accumulation of aluminum. When researchers added silica to aluminum-laced water supplies, it inhibited the aluminum from being absorbed. It also caused a proliferation in the excretion of aluminum in urine and lowered aluminum concentrations in the brain, liver, bone, spleen and kidneys. Silica, therefore, may be important in supporting neurological health.

Improve Heart and Lung Health: Silica can hinder the effects of coronary disease by fortifying blood vessels. Studies confirm that with age, silica disappears from the aorta, the heart's key blood vessel—thus weakening its critical connective tissue, and resulting in a greater cardiac risk. Studies have shown diatomaceous earth to significantly lower cholesterol by removing plaque and keeping arteries and veins supple. It also helps to regulate blood pressure. Silica also aids in the repair and maintenance of vital lung tissues and defending them from pollution.

Stop Premature Wrinkling and Sagging Skin: Silica is excellent for supporting bones and connective tissue. Your body needs healthy connective tissue for internal organs and the largest organ which is your skin. And you probably know that degrading connective tissue, with age is why wrinkles appear and skin begins to sag. Perhaps it is not age, but rather not enough silica that makes this happen.

Collagen, which is mostly made up of silica, is the glue that holds us together. Collagen accounts for up to 75% of the weight of the dermis and is responsible for the resilience and elasticity of the skin. Our connective tissues consist of collagen, elastin, mucopolysaccharides and mucous carbohydrates which aid in moisture retention. Their capacity to hold on to moisture keeps the connective tissue resilient and has apparent importance in the prevention of premature aging. All these valuable molecules house large quantities of silica. Also, many people with advanced arthritis suffer from bone deformation when tendons and ligaments in the joints lose flexibility due to loss of collagen. Tendons and ligaments need silica for health and flexibility.

Boost the Immune System: Silica may play an important role in the immune system and its biological response to harmful stimuli. Silica is necessary for the body to produce antibodies that fight off viruses, bacteria, allergens and other invaders that the body views as foreign.

Other Ways Diatomaceous Earth Can Improve Your Health

One of the most sought after benefits of diatomaceous earth is to cleanse the digestive tract. Many people consume a variety of processed foods, which contain various harmful chemicals and toxins. Plus, as air quality has decreased, we are constantly putting more toxins in our body that need to be removed.

Diatomaceous earth can purge any parasite, virus, bacteria, or toxin that is clinging to our digestive tract. While diatomaceous earth feels like a soft powder, the truth is that diatomaceous earth is actually a small cylinder with extremely sharp edges. As we consume diatomaceous earth, these sharp edges scrape away parasites, toxins, and viruses clinging to the lining of our digestive tract. Plus, any toxins or bacteria floating in our digestive tract are absorbed and trapped by diatomaceous earth. It has also been shown to cling to bad fats in the body, effectively reducing bad cholesterol. Diatomaceous earth is then expelled through our bowel movements and these harmful materials are removed.

Our skin and organs are strong and thick enough not to be affected by these sharp edges, which is why we feel no pain taking diatomaceous earth. After a few days, the body's digestive system can be thoroughly cleansed and can operate much more efficiently.

Are All Forms of Diatomaceous Earth the Same?

No! There are two types of DE—Food Grade and Pool Grade.

Most deposits of diatomaceous earth are from salt water sources, while only a few are from fresh water sources. Of the hundreds of DE deposits that exist worldwide, only 4 of them can be called food grade. The DE sourced from fresh water beds are of extremely high purity—so pure that it is called Food Grade Diatomaceous Earth, or also known as fossil shell flour. Food grade diatomaceous earth, the only form safe for human consumption, is a white powder, while other forms of diatomaceous earth may have a brown/reddish tint.

Also, there are two types of naturally occurring silica—crystalline silica and non-crystalline (amorphous) silica. Crystalline silica can be very dangerous, especially to our lungs if inhaled, while non-crystalline silica is completely safe, even for human and animal consumption. The fresh water diatoms contain mainly non-crystalline silica, while salt water diatoms can contain both types, with higher amounts of the crystalline form.

PERMA-GUARD™ is the trade name known worldwide for using a grade and quality of Diatomaceous Earth (DE) that is extremely pure. Brands that use Perma-Guard™ food grade Diatomaceous Earth contains less than 0 .5% crystalline silica. It is important to have a consistent shape diatom and no unwanted sediment. The shape of the diatom must be tubular with holes on the walls. It must be from fresh water because the fresh water diatoms form a harder shell and are less fragile that those from salt water. Salt water deposits contain a mix of diatom species. These deposits shapes and sediments are inconsistent making them unusable for safe human consumption.

Other types of diatomaceous earth have other industrial uses. It is heated to a very high temperature (about 1000°C or 1800°F). This type of DE is called "calcined." It is used for pool filters and other types of filtering but it is also used as a filler and can end up in paints, cosmetics, drugs, chemical insecticides, and other things. Food grade DE is never heated.

Bottom Line: ONLY use Food Grade Diatomaceous Earth for health purposes!!! Food grade diatomaceous earth is the purest form of diatomaceous earth and can be consumed and used by humans. Food grade diatomaceous earth is heavily regulated and must contain less than a certain amount of specific minerals.

Pool grade DE is calcinated and is a stronger, more potent form of DE. It is not to be used by humans and pool grade DE must be handled with gloves and a mask to ensure no throat irritations occur.

All DE should have a label that tells you if it has been calcined and how much crystalline silica it contains.

How Much to Take—How Safe Is It?

Food grade diatomaceous earth is a very fine powder and is very light due to its high porosity. It mixes easily into liquids and foods. Most people take a teaspoon or a tablespoon two or three times a day (up to a total of one quarter cup per day) for best results. Mix it into water, juice, smoothies or other foods.

It sort of resembles putting a spoonful of baking soda in water and drinking it!

Silica is water soluble; hence, once you get it into your body it easily absorbed via the intestinal wall and is also rapidly excreted. It does not accumulate in the body, so consistent daily supplementation is important. Studies have not found any negative side effects from too much silica. Its safety and extensive range of uses makes silica one of the most important minerals used in complementary therapy and alternative medicine. Regular supplementation could make a significant difference in your health.

Being approved by the FDA, Diatomaceous Earth has absolutely no dangerous side effects. It can be used by anyone, as long as the person doesn't suffer from a serious illness. As with any other health supplement, talk to a doctor before using DE. You might have some intolerance to it, so it's advisable to not risk your health. Pregnant and breastfeeding mothers can use it as long as their doctor has agreed.

What Other Uses Does DE Have?

One of the most commonly known uses for diatomaceous earth is as a non-toxic bug killer. DE is almost pure silica (with some beneficial trace minerals); under a microscope, it looks like shards of glass (glass is made from silica). On any beetle-type insect that has a carapace, like ants, fleas and cockroaches, the DE works under the shell and punctures the body, which then dehydrates their innards and the insect dies. DE is totally nontoxic. There is no buildup of tolerance like there is to poisons because the method of killing is PHYSICAL, not chemical. But rest assured, food grade DE doesn't hurt people or animals. In fact, it makes a great flea killer for your pets, and can also be added to their food as de-wormer. Many farmers use it to keep farm animals healthy, both inside and out. Food grade DE is also added to grains in storage because it keeps bugs from eating the grain. So if you eat any grains, you're probably already eating a little bit of DE!

Where to Get It!

You can buy food grade diatomaceous earth online. Processed-Free America sells it through its online store.

Written by Dee McCaffrey, CDC, who lost 100 pounds and has kept it off for over 20 years. For more info, go to: www.processedfreeamerica.org

Appendix 12

Summary of Protocols

The purpose of this list is to have all the protocols in one place, so you don't have to be hunting and flipping pages to find something. This information is also available on our website www.cdautism.org if you would like to print anything full size.

Diet

Permitted Foods List:

Note: Organic products are better but not required.

Proteins

- ☐ Beef
- ☐ Chicken
- ☐ Eggs
- ☐ Fish (small not large size)
- ☐ Pork
- ☐ Turkey

Fruit

- ☐ Most fresh fruits are permitted (except citrus, mango, pineapple, kiwi, and limit berries).
- ☐ Frozen fruit without added cream or sugar.
- ! NO canned fruit (nothing canned ever).
- ! Be careful of dried fruit as it may contain sugar.

Vegetables

- ☐ All vegetables are fine!!!
- ☐ Including French fries, however, not frozen fries or fries from fast food chains; these are often coated in flour.

Nuts

- ☐ Almonds
- ☐ Cashews
- ☐ Coconut
- ☐ Hazelnuts
- ☐ Walnuts

Grains

☐ Amaranth
☐ Buckwheat
☐ Corn
☐ Millet
☐ Quinoa
☐ Rice
☐ Sorghum
☐ Tapioca
☐ Xanthan gum

Beans

☐ All beans—EXCEPT soy
☐ Split Pea
☐ Garbanzo
☐ Lentils
☐ Navy
☐ Peanuts

Sweeteners

☐ Stevia (Best choice of all sweeteners)
☐ Agave syrup
☐ Honey
☐ Maple syrup (without added sugar)
☐ Xylitol

Prohibited Foods List

- Acetic acid (E260)
- Artificial flavoring
- Artificial sweeteners
- Bouillon cubes
- Bread
- Candy
- Cane sugar
- Carrageenan
- Catsup
- Chocolate milk
- Coloring
- Corn flakes
- Corn syrup
- Cow's milk in any form (even lactose-free milk products)
- Flour tortillas
- Gelatin
- Malt
- Margarine
- Mayonnaise
- Microwave popcorn
- MSG
- Natural flavoring
- Noodle soup
- Oatmeal (except for Bob's Red Mill GF oats)
- Pasta
- Piloncillo (unrefined sugar)
- Children´s nutritional shakes
- Play-Doh™
- Preservatives
- Processed meats (hotdogs, ham, sausage, bologna, cold cuts)
- Shellfish (full of toxins)
- Sodas
- Soy/fruit beverages
- Soy milk
- Soy sauce
- Sports drinks
- Sugar
- Yeast

Preparing Your First One drop CD Batch for the Day

1.	Start by filling the baby bottle with 8 fl. oz. (237ml) of water (distilled or reverse osmosis). NO alkaline water!	
2.	Place 1 drop of sodium chlorite solution into the CLEAN and DRY shot glass.	
3.	Add 1 drop of acidic activator (hydrochloric acid or citric acid) to the shot glass containing the drop of sodium chlorite. The number of drops may be higher if you are using a weaker activator. See chart on page 94.	
4.	Now wait the appropriate time for the mixture to react (see chart on page 94). You should see the color change from clear to slightly yellow. If there were more drops in the shot glass, the color change is more noticeable. You are also likely to notice the chlorine-like smell coming from the shot glass. Remember, this is NOT chlorine, but rather chlorine dioxide.	
5.	After the activation time has passed, pour a little water from the baby bottle into the shot glass and let it mix. This mostly stops the chemical reaction and insures you get most of the mixture out in the next step.	
6.	Lastly, pour all of the watered down mixture in the shot glass back into the baby bottle, and seal it tightly with the cap—don't leave it sitting open for any length of time. Think partially used soda pop and how you would want to keep that closed.	

Estimated Full Oral CD Doses by Weight

Use these numbers as a guide only. You may need to go up by as much as 50% or more over the indicated drops. Read chart as: **POUNDS / KILOGRAMS → DROPS OF CD (per 8 fl. oz. water)**

25/11→8	62/28→17	99/45→24	136/62→29	173/78→33	210/95→37
26/12→8	63/29→17	100/45→24	137/62→29	174/79→33	211/96→37
27/12→9	64/29→17	101/46→24	138/63→29	175/79→34	212/96→37
28/13→9	65/29→18	102/46→24	139/63→30	176/80→34	213/97→37
29/13→9	66/30→18	103/47→24	140/64→30	177/80→34	214/97→37
30/14→9	67/30→18	104/47→25	141/64→30	178/81→34	215/98→37
31/14→10	68/31→18	105/48→25	142/64→30	179/81→34	216/98→37
32/15→10	69/31→18	106/48→25	143/65→30	180/82→34	217/98→37
33/15→10	70/32→19	107/49→25	144/65→30	181/82→34	218/99→38
34/15→10	71/32→19	108/49→25	145/66→30	182/83→34	219/99→38
35/16→11	72/33→19	109/49→25	146/66→30	183/83→34	220/100→38
36/16→11	73/33→19	110/50→26	147/67→31	184/83→35	221/100→38
37/17→11	74/34→19	111/50→26	148/67→31	185/84→35	222/101→38
38/17→11	75/34→20	112/51→26	149/68→31	186/84→35	223/101→38
39/18→12	76/34→20	113/51→26	150/68→31	187/85→35	224/102→38
40/18→12	77/35→20	114/52→26	151/68→31	188/85→35	225/102→38
41/19→12	78/35→20	115/52→26	152/69→31	189/86→35	226/103→38
42/19→12	79/36→20	116/53→26	153/69→31	190/86→35	227/103→38
43/20→13	80/36→21	117/53→27	154/70→31	191/87→35	228/103→38
44/20→13	81/37→21	118/54→27	155/70→31	192/87→35	229/104→38
45/20→13	82/37→21	119/54→27	156/71→32	193/88→35	230/104→39
46/21→13	83/38→21	120/54→27	157/71→32	194/88→35	231/105→39
47/21→14	84/38→21	121/55→27	158/72→32	195/88→36	232/105→39
48/22→14	85/39→21	122/55→27	159/72→32	196/89→36	233/106→39
49/22→14	86/39→22	123/56→27	160/73→32	197/89→36	234/106→39
50/23→14	87/39→22	124/56→28	161/73→32	198/90→36	235/107→39
51/23→15	88/40→22	125/57→28	162/73→32	199/90→36	236/107→39
52/24→15	89/40→22	126/57→28	163/74→32	200/91→36	237/108→39
53/24→15	90/41→22	127/58→28	164/74→32	201/91→36	238/108→39
54/24→15	91/41→23	128/58→28	165/75→33	202/92→36	239/108→39
55/25→16	92/42→23	129/59→28	166/75→33	203/92→36	240/109→39
56/25→16	93/42→23	130/59→28	167/76→33	204/93→36	241/109→39
57/26→16	94/43→23	131/59→28	168/76→33	205/93→36	242/110→39
58/26→16	95/43→23	132/60→29	169/77→33	206/93→37	243/110→39
59/27→16	96/44→23	133/60→29	170/77→33	207/94→37	244/111→40
60/27→17	97/44→24	134/61→29	171/78→33	208/94→37	245/111→40
61/28→17	98/44→24	135/61→29	172/78→33	209/95→37	246/112→40

Advanced Protocols (After Full Oral Dose is Reached)

CD Enemas:

I recommend enemas no less frequently than every other day. You can do them more often particularly if you see parasites coming out. The ratio is 1-2 drops chlorine dioxide per 100 ml of filtered warm water. Work your way up to 500 mL – 1.5 L of water per enema, depending on the size of your child. You have the following options for methods of administering the enemas: a catheter and syringes, a multipurpose enema/douche bag, empty out a fleet enema, or a gravity bag. (note, if your child suffers from constipation you can add enemas and baths in before you get to full dose, alternating them on opposite days or opposite ends of the day).

Enemas should be started when the child reaches full oral dose. However, if your child suffers from constipation you can add enemas and baths on day one (see page 113), before you get to the full oral dose. However, alternate them on opposite days or opposite ends of the day. The following chart is an approximate amount of water based on the size of the person, and calculated the maximum of 2 drops of CD per 100mL of water.

Age/Size	Water Volume	Drops of CD
Child	1/2 Liter (500ml)	10
Adolescent	1 Liter (1,000ml)	20
Teen/Adult	up to 2 Liters (2,000ml)	40

CD Baths:

10-100 Activated drops of CD in a hot (to tolerance) bath with enough water to cover the child's body. Soak for 20 minutes. Apply on alternate enema days, unless you are doing daily enemas, in which case apply on opposite ends of the day.

The CD baths can go from as low as 10 drops to as high as 80 to 100 drops; it just depends on the person, and the size of your tub. With younger/smaller children we start with ten drops. Since we're doing baths every other day, start with ten drops on Monday, 11 drops on Wednesday, and 12 drops on Friday. Just keep going up until you get to 20 drops. The bigger and older the person is, the more drops they can tolerate. Fill the tub to a level that maximizes skin contact.

72/2 Protocol

Give one dose of CD every 2 hours for 72 hours straight, including the middle of the night. Apply every possible weekend.

This involves giving one dose of CD every two hours for 72 hours straight—including the middle of the night. Here are some additional thoughts and guidelines:

- Start protocol when you pick up your child from school on Friday.
- Give them the last 72/2 dose when you drop them off at school on Monday.
- Avoid giving CD enemas or CD baths during this protocol, UNLESS they are dumping parasites, in which case you might need to reduce the amount of CD on both the oral and enema dose to insure the child doesn't have a Herxheimer reaction.
- Why not give hourly doses during the day at the usual dose? It's simply too much if you are doing it all night as well.
- Watch for improvements on Tuesday or Wednesday each week.
- Ideally, get your spouse or significant other to help with every other nightly dose.

Supplement Dosing Overview

Supplement	Dose	Time of Day	Empty Stomach (ES) or With Food (WF)
Probiotics	1 cap	Before Bed	ES
Omega-3/ Omega-6	1 Tbsp	With any meal 1-3x / day	WF
L-Carnitine	250-1000mg/day	With any meal 1-3x / day	WF
GABA	Up to 2,500mg 2x/day	Upon waking & at bedtime	ES
5-HTP	50-200mg	Morning & Evening	WF
L-Theanine	Work up to 200-250mg/day	Mornings or Mornings & Nights	ES
Pycnogenol	25-40mg a day/as needed	Morning	WF
L-Carnosine	200-400mg 2x / day	Morning & Evening	WF
Taurine	500-1500mg/day	Morning, Noon & Night	ES
DMG	900mg/day	Morning	ES
TMG	500mg/day	Morning	ES
Enzymes	1 cap w/meals	Morning, Noon & Night	WF

Parasite Protocol

Please see the complete explanation of the parasite protocol starting on page 187. Day-to-day protocol charts can be found on page 198.

Chelation:

I suggest that when you decide to add clay baths into your child's protocol that you do so on the off days of the CD baths.

Follow the instructions on the package, and follow septic tank precautions if you have one.

Three days or so later, you can add in the Bio-Chelat. Again, follow the instructions on the package, and you can always start slowly and work your way up. Since Bio-Chelat™ doesn't alter the CD, the drops can be added to a single dose of CD. In addition, since the drops have no flavor, it is suitable to add them to water or any other drink your child might consume throughout the day.

Hyperbarics:

Option #1:

Two sessions of 60 minutes each for 20 days for a total of 40 sessions at 1.75 ATA.

Option #2:

One 90-minute session a day for twenty days at 1.75 ATA.

Instead of thinking outside of the box, get rid of the box.

~ Deepak Chopra

Appendix 13

Body Burden
The Pollution in Newborns

When I came across the following investigation I knew it was the perfect precursor to the incredible "Avoiding Autism" by Dr. Anju Usman and Beth Hynes. Babies are exposed to toxins in the womb and this study by the Environmental Working Group demonstrates so perfectly why the advice in the "Avoiding Autism" article is so very crucial to health of our children and for our species as a whole.

Body Burden — The Pollution in Newborns

A benchmark investigation of industrial chemicals, pollutants and pesticides in umbilical cord blood.

Environmental Working Group, July 14, 2005

Summary. In the month leading up to a baby's birth, the umbilical cord pulses with the equivalent of at least 300 quarts of blood each day, pumped back and forth from the nutrient- and oxygen-rich placenta to the rapidly growing child cradled in a sac of amniotic fluid. This cord is a lifeline between mother and baby, bearing nutrients that sustain life and propel growth.

Not long ago scientists thought that the placenta shielded cord blood — and the developing baby — from most chemicals and pollutants in the environment. But now we know that at this critical time when organs, vessels, membranes and systems are knit together from single cells to finished form in a span of weeks, the umbilical cord carries not only the building blocks of life, but also a steady stream of industrial chemicals, pollutants and pesticides that cross the placenta as readily as residues from cigarettes and alcohol. This is the human "body burden" — the pollution in people that permeates everyone in the world, including babies in the womb.

In a study spearheaded by the Environmental Working Group (EWG) in collaboration with Commonweal, researchers at two major laboratories found an average of 200 industrial chemicals and pollutants in umbilical cord blood from 10 babies born in August and September of 2004 in U.S. hospitals. Tests revealed a total of 287 chemicals in the group. The umbilical cord blood of these 10 children, collected by Red Cross after the cord was cut, harbored pesticides, consumer product ingredients, and wastes from burning coal, gasoline, and garbage.

This study represents the first reported cord blood tests for 261 of the targeted chemicals and the first reported detections in cord blood for 209 compounds. Among them are eight perfluorochemicals used as stain and oil repellants in fast food packaging, clothes and textiles — including the Teflon chemical PFOA, recently characterized as a likely human carcinogen by the EPA's Science Advisory Board — dozens of



Chemicals and pollutants detected in human umbilical cord blood

Hg **Mercury (Hg) - tested for 1, found 1**
Pollutant from coal-fired power plants, mercury-containing products, and certain industrial processes. Accumulates in seafood. Harms brain development and function.

PAH **Polyaromatic hydrocarbons (PAHs) - tested for 18, found 9**
Pollutants from burning gasoline and garbage. Linked to cancer. Accumulates in food chain.

BD/F **Polybrominated dibenzodioxins and furans (PBDD/F) - tested for 12, found 7**
Contaminants in brominated flame retardants. Pollutants and byproducts from plastic production and incineration. Accumulate in food chain. Toxic to developing endocrine (hormone) system

PFC **Perfluorinated chemicals (PFCs) - tested for 12, found 9**
Active ingredients or breakdown products of Teflon, Scotchgard, fabric and carpet protectors, food wrap coatings. Global contaminants. Accumulate in the environment and the food chain. Linked to cancer, birth defects, and more.

D/F **Polychlorinated dibenzodioxins and furans (PCDD/F) - tested for 17, found 11**
Pollutants, by-products of PVC production, industrial bleaching, and incineration. Cause cancer in humans. Persist for decades in the environment. Very toxic to developing endocrine (hormone) system.

OC **Organochlorine pesticides (OCs) - tested for 28, found 21**
DDT, chlordane and other pesticides. Largely banned in the U.S. Persist for decades in the environment. Accumulate up the food chain, to man. Cause cancer and numerous reproductive effects.

PBDE **Polybrominated diphenyl ethers (PBDEs) - tested for 46, found 32**
Flame retardant in furniture foam, computers, and televisions. Accumulates in the food chain and human tissues. Adversely affects brain development and the thyroid.

CN **Polychlorinated Naphthalenes (PCNs) - tested for 70, found 50**
Wood preservatives, varnishes, machine lubricating oils, waste incineration. Common PCB contaminant. Contaminate the food chain. Cause liver and kidney damage.

PCB **Polychlorinated biphenyls (PCBs) - tested for 209, found 147**
Industrial insulators and lubricants. Banned in the U.S. in 1976. Persist for decades in the environment. Accumulate up the food chain, to man. Cause cancer and nervous system problems.

Source: Chemical analyses of 10 umbilical cord blood samples were conducted by AXYS Analytical Services (Sydney, BC) and Flett Research Ltd. (Winnipeg, MB).

widely used brominated flame retardants and their toxic by-products; and numerous pesticides.

Of the 287 chemicals we detected in umbilical cord blood, we know that 180 cause cancer in humans or animals, 217 are toxic to the brain and nervous system, and 208 cause birth defects or abnormal development in animal tests. The dangers of pre- or post-natal exposure to this complex mixture of carcinogens, developmental toxins and neurotoxins have never been studied.

Chemical exposures in the womb or during infancy can be dramatically more harmful than exposures later in life. Substantial scientific evidence demonstrates that children face amplified risks from their body burden of pollution; the findings are particularly strong for many of the chemicals found in this study, including mercury, PCBs and dioxins. Children's vulnerability derives from both rapid development and incomplete defense systems:

- A developing child's chemical exposures are greater pound-for-pound than those of adults.
- An immature, porous blood-brain barrier allows greater chemical exposures to the developing brain.
- Children have lower levels of some chemical-binding proteins, allowing more of a chemical to reach "target organs."
- A baby's organs and systems are rapidly developing, and thus are often more vulnerable to damage from chemical exposure.
- Systems that detoxify and excrete industrial chemicals are not fully developed.
- The longer future life span of a child compared to an adult allows more time for adverse effects to arise.

The 10 children in this study were chosen randomly, from among 2004's summer season of live births from mothers in Red Cross' volunteer, national cord blood collection program. They were not chosen because their parents work in the chemical industry or because they were known to bear problems from chemical exposures in the womb. Nevertheless, each baby was born polluted with a broad array of contaminants.

U.S. industries manufacture and import approximately 75,000 chemicals, 3,000 of them at over a million pounds per year. Health officials do not know how many of these chemicals pollute fetal blood and what the health consequences of in utero exposures may be.

Had we tested for a broader array of chemicals, we would almost certainly have detected far more than 287. But testing umbilical cord blood for industrial chemicals is technically challenging. Chemical manufacturers are not required to divulge to the public or government health officials methods to detect their chemicals in humans. Few labs are equipped with the machines and expertise to run the tests or the funding to develop the methods. Laboratories have yet to develop methods to test human tissues for the vast majority of chemicals on the market, and the few tests that labs are able to conduct are expensive. Laboratory costs for the cord blood analyses reported here were $10,000 per sample.

A developing baby depends on adults for protection, nutrition, and, ultimately, survival. As a society we have a responsibility to ensure that babies do not enter this world pre-polluted, with 200 industrial chemicals in their blood. Decades-old bans on a handful of chemicals like PCBs, lead gas additives, DDT and other pesticides have led to significant declines in people's blood levels of these pollutants. But good news like this is hard to find for other chemicals.

The Toxic Substances Control Act, the 1976 federal law meant to ensure the safety of commercial chemicals, essentially deemed 63,000 existing chemicals "safe as used" the day the law was passed, through mandated, en masse approval for use with no safety scrutiny. It forces the government to approve new chemicals within 90 days of a company's application at an average pace of seven per day. It has not been improved for nearly 30 years—longer than any other major environmental or public health statute—and does nothing to reduce or ensure the safety of exposure to pollution in the womb.

Because the Toxic Substances Control Act fails to mandate safety studies, the government has initiated a number of voluntary programs to gather more information about chemicals, most notably the high production volume (HPV) chemical screening program. But these efforts have been largely ineffective at reducing human exposures to chemicals. They are no substitute for a clear statutory requirement to protect children from the toxic effects of chemical exposure.

In light of the findings in this study and a substantial body of supporting science on the toxicity of early life exposures to industrial chemicals, we strongly urge that federal laws and policies be reformed to ensure that children are protected from chemicals, and that to the maximum extent possible, exposures to industrial chemicals before birth be eliminated. The sooner society takes action, the sooner we can reduce or end pollution in the womb.

Copyright © Environmental Working Group, www.ewg.org. Reprinted with permission.



Tests show 287 industrial chemicals in 10 newborn babies

Pollutants include consumer product ingredients, banned industrial chemicals and pesticides, and waste byproducts

Sources and uses of chemicals in newborn blood	Chemical family name	Total number of chemicals found in 10 newborns (range in individual babies)
Common consumer product chemicals (and their breakdown products)		**47 chemicals** **(23 - 38)**
Pesticides, actively used in U.S.	Organochlorine pesticides (OCs)	7 chemicals (2 - 6)
Stain and grease resistant coatings for food wrap, carpet, furniture (Teflon, Scotchgard, Stainmaster...)	Perfluorochemicals (PFCs)	8 chemicals (4 - 8)
Fire retardants in TVs, computers, furniture	Polybrominated diphenyl ethers (PBDEs)	32 chemicals (13 - 29)
Chemicals banned or severely restricted in the U.S. (and their breakdown products)		**212 chemicals** **(111 - 185)**
Pesticides, phased out of use in U.S.	Organochlorine pesticides (OCs)	14 chemicals (7 - 14)
Stain and grease resistant coatings for food wrap, carpet, furniture (pre-2000 Scotchgard)	Perfluorochemicals (PFCs)	1 chemicals (1 - 1)
Electrical insulators	Polychlorinated biphenyls (PCBs)	147 chemicals (65 - 134)
Broad use industrial chemicals - flame retardants, pesticides, electrical insultators	Polychlorinated naphthalenes (PCNs)	50 chemicals (22 - 40)
Waste byproducts		**28 chemicals** **(6 - 21)**
Garbage incineration and plastic production wastes	Polychlorinated and Polybrominated dibenzo dioxins and furans (PCDD/F and PBDD/F)	18 chemicals (5 - 13)
Car emissions and other fossil fuel combustion	Polynuclear aromatic hydrocarbons (PAHs)	10 chemicals (1 - 10)
Power plants (coal burning)	Methylmercury	1 chemicals (1 - 1)
All chemicals found		**287 chemicals** **(154 - 231)**

Source: Environmental Working Group analysis of tests of 10 umbilical cord blood samples conducted by AXYS Analytical Services (Sydney, BC) and Flett Research Ltd. (Winnipeg, MB).

The ultimate ignorance is the rejection of something you know nothing about and refuse to investigate.

~ Dr. Wayne Dyer

Appendix 14

Avoiding Autism

By Anju Usman, MD and Beth C. Hynes JD, MBA

Whether or not you are the parent of a special needs child, please pay special attention to this article, we do believe autism is totally preventable and that starts with pregnancy. Here's to your health!

Every parent's dream is to have a healthy baby. Over the past ten years of working with families devastated by the diagnosis of autism, we, along with our patients' parents, have realized one key fact: if we knew then what we know now, the diagnosis of the disease called autism could very well have been prevented. Considering that the cause(s) of the current epidemic of autism spectrum disorders (ASD) are unknown (and scant research dollars are being dedicated to finding the most likely culprits), there is no surefire method to avoid having your infant regress into this devastating state. That sad fact, however, does not mean that there are no proactive steps parents can take to try to mitigate the chances of this disease overtaking their baby and stealing their hopes and dreams for that child's life.

Having reviewed the medical and laboratory test results of thousands of children afflicted with ASD, clinicians using a biomedical approach to treating autism see repeating patterns in these children—impaired methylation and detoxification, mitochondrial dysfunction, gastrointestinal distress, and immune dysregulation compounded by chronic viral, fungal and bacterial infections and a burden of heavy metals and other toxins. From this perspective, we have come to view autism as a multifactorial medical disease that can be treated and overcome and, therefore, possibly avoided. Coming straight from the heart, this advice is for thinking, active parents and prospective parents who want to know what they can do to reduce the risk that their infant will regress into autism. In our practice, we have helped many parents go on to have healthy children even though they already have a child with autism. Considering that the information provided here is not harmful but, to the contrary, is helpful in promoting improved maternal and fetal health, there is little downside to pursuing these strategies while simultaneously minimizing the risk of having your child slip away into the autism epidemic. According to the latest statistics out of California, that epidemic continues to grow from the already shocking 1 out of 150 children. The aim here is to provide an analytical construct that will guide parents in making choices for both their own health and that of their baby before, during, and after pregnancy.

Think of the analogy of the straw that broke the camel's back. Human beings start life as infants with some "straws" in their saddle – these are predispositions to be harmed by certain chemicals, to be susceptible to certain diseases, or to have a less robust detoxification capacity. The goal of gestating and parenting an infant in today's toxic world is to not accumulate additional straws during your baby's gestation and infancy, thereby avoiding adding the straw that breaks the camel's back. Autism seems to occur when the infant's body is so overwhelmed by toxins, viruses and/or pathogenic elements that typical development is arrested and/or derailed.

Children diagnosed with autism have a variety of medical problems, the underpinnings of which can be ameliorated and/or healed. The symptoms associated with autism occur through malfunctioning of the infant immune, gastrointestinal, and central nervous systems ("Infant Body Systems") – all of which, when functioning properly, contribute to the healthy development of the brain. Viruses, heavy metals, toxins, fungi, and bacteria together form a weapon that disrupts the development of, and harms the functioning of, these critical Infant Body Systems. As researchers have recently found, "a single toxicant may promote different immune-associated diseases that are dependent upon the specific window of early life exposure, the gender of the exposed offspring, and the genetic background of the offspring." Our construct will consist of actions you can take to promote the healthy development of these Infant Body Systems as well as steps you can take to avoid upsetting the healthy development of those systems.

Due to the symbiotic relationship between a mother and her developing fetus, care must be taken by the mom before, during, and after pregnancy (if nursing) to both avoid exposure to harmful elements and to promote optimal maternal detoxification processes so that the host body remains as clean an environment as possible within which vigorous infant development can unfold.

Only recently have researchers begun closely linking environmental factors with developmental delays in our children. A host of studies show how environmental factors including diet, nutrition, air quality, clean water, heavy metals (e.g., mercury, lead, arsenic, and aluminum), xenobiotics (e.g., chemicals, pesticides, plasticizers, and perchlorates), pharmaceuticals, and vaccinations can change your child's inborn risk.

This area of study is called epigenetics – the molecular changes in our DNA caused by environmental factors. In 2003, researchers at Duke University found that rats carrying a gene for obesity, cancer, and diabetes, when fed a diet high in B-12, folic acid, choline, and methyl-rich foods, had babies that were born healthy and with a reduced risk of developing disease; this research revealed that these genetic changes persisted across four generations. Thus, when you eat a healthy diet, you are affecting not only the health of your own kids but also your grandchildren, great-grandchildren, and great-great-grandchildren. Researchers are finding hundreds of unwanted and potentially toxic chemicals in the placenta and cord blood of newborns as well as in mothers' breast milk. That means that today's children are born with a toxic burden their infant bodies must contend with from day one. Studies out of China, Texas, and San Francisco show that if pregnant mothers can decrease their exposure to pollutants during gestation, they can improve health outcomes for their children – especially brain development. Compounds such as mercury, cadmium, nickel, trichloroethylene, and vinyl chloride in the air around the birth residence caused a 50% increase in the risk of autism.

Numerous studies document the neurotoxic effects of heavy metals – especially dangerous to the developing brain is mercury. Yet, many of our children are actually injected with the mercury-containing preservative thimerosal in their infant vaccines. Although thimerosal has been removed from, or perhaps phased out of, many childhood vaccines, it still remains in the flu vaccine, which is recommended by health authorities to pregnant woman as well as to children under age 2. Mercury exposure is such a concern that pregnant women are advised by health authorities not to eat fish because of potential mercury contamination – yet injecting thimerosal is much more damaging than the exposure suffered through eating it in food such as fish. Vaccines also contain aluminum, formaldehyde, and other toxic elements as well as live viruses that, in a subset of infant bodies, can trigger harmful impacts. Heavy metals have also been identified as factors affecting human fertility. Diagnosing and reducing the heavy metal burden of women improved the spontaneous conception chances of infertile women. Women with many dental amalgams had a higher incidence of miscarriages and a higher excretion of mercury when given the chelating agent DMPS (2,3-Dimercapto-1-propanesulfonic acid). It has been found that DMPS was a useful and complementary method to increase fertility compared to hormone therapy in infertile women.

With all this evidence mounting against various environmental toxins affecting human development, an international assembly of scientists, doctors, toxicologists, and researchers sponsored by the

World Health Organization (WHO), the European Environmental Agency, the Centers for Disease Control (CDC), and the National Institutes of Health (NIH) gathered in the Faroe Islands in May 2006. Their consensus statement was clear: "it is time to take action, now." As expected, the declaration highlighted the results of hundreds of studies that showed early fetal exposures to toxic substances, even at low concentrations, can cause health problems later in life. There are a growing number of chemicals that affect the developing embryo, fetus, and infant, including the pesticides DDT, atrazine, methoxychlor, and vinclozolin. Also suspect are plastics and the epoxy resin bisphenol A, plasticizing agents called phthalates, mercury, lead, arsenic, organotoxins, polychlorinated biphenols (PCBs), carbon monoxide, smog, tobacco smoke, and alcohol. The health problems caused by exposure to these substances comprise a dizzying array of maladies including cancer, diabetes, obesity, asthma, and allergies as well as reproductive, cardiovascular, neurological, cognitive, endocrine, psychological, immune, and respiratory troubles.

Other troubling chemicals include parabens (found in various creams and lotions) and triclosan, an antibacterial agent (found in toothpaste, soaps, and cleaning products). Although parabens and triclosan are not ingested, absorbing chemicals through the skin can be far more dangerous than swallowing because transdermal applications are transported directly to the bloodstream. Most women absorb 51 pounds of chemicals every year from their cosmetics alone! Additional exposures emanate from daily lifestyle, profession, and locale. For those elements for which we have the flexibility to make choices, we must choose wisely. After all, it is not just our health that is being affected by our choices but the health of our children and progeny as well.

Basic principles to guide you in decision making surrounding pregnancy are as follows:

1. You are what you eat (and drink); therefore, make healthy choices in what you consume.
2. Skin is the largest organ in the body, so be very careful of what you rub into yours and your baby's.
3. Think beyond "green": What is "green" for the environment is not always what is healthiest for the body, but what is healthiest for the body is always "green."

Suggestions to promote these principles are below and are cumulative, so keep following each set of suggestions as this journey into and through parenthood progresses.

Pre-Pregnancy

While planning a pregnancy, we recommend that you clean up any toxicity in your body and begin to follow a more organic, healthy lifestyle. Remember, the less toxic you are, the better for you and your future baby. Undertake a sequential detoxification program that targets the liver and colon; this type of program can take six months or more and should not be done while pregnant. In a careful manner, with an experienced dentist, remove amalgams from your teeth, which also can take six months or more. Take the time now to find organic, nontoxic makeup, hair, and body products that you like and start integrating them into your daily life. Ask your doctor to run some tests to determine any additional specific supplementation you may need to optimize levels within your body; a good place to start is your copper-zinc ratio (1:1 is the ideal ratio), thyroid function (TSH, free t3, free t4), Vitamin D 25 OH, vitamin A levels, and total cholesterol (low cholesterol is associated with preterm births).

Next, clean up your living and working environment. Remove all harmful chemical cleaning agents from your cleaning routine at home and at the office, and instead use cleaning products labeled level 1 by the EPA. Do not forget to include products for dishwashing and clothing detergent in your cleanup, and avoid toxic dry cleaning as much as possible. Finally, improve your nutrition with a targeted vitamin supplementation program to include omega-3 essential fatty acids, sublingual methyl B-12, folinic acid, vitamin D3, zinc, and antioxidants.

DO	DON'T
• Eat organic, hormone-free food • Drink organic green tea, filtered water, and antioxidant rich organic juices • Use stevia, raw organic honey, and xylitol as sweeteners • Go for walks and get some sunshine daily • Use aluminum-free natural deodorant in them • Use natural hennas to color your hair • Use cast iron, glass, or stainless steel cookware • Use chemical-free cleaning products in your home	• Consume fish or foods w/MSG or food dyes • Drink soda, carbonated beverages, or alcohol • Consume artificial sweeteners • Be exposed to lawn chemicals or second-hand smoke • Use moisturizers or makeup with chemicals or parabens • Use chemical dyes, perms, or other such hair treatments • Cook with pans that are non-stick, Teflon coated, or made from aluminum

During Pregnancy

We would suggest that you find a holistic health practice to guide you during pregnancy and delivery as there are many decisions to make during this time. In general, we suggest avoiding medications to the extent possible as well as acetaminophen because it hinders normal detoxification. Add zinc, calcium, essential fatty acids, and prenatal vitamins to your daily supplement intake. Discontinue use of nail polish and any makeup (including lipstick) products that contain parabens and other toxins. Use fluoride-free toothpaste as fluoride interferes with iodine metabolism, which is an issue implicated in mental retardation worldwide.

DO	DON'T
• Yoga and engage in stress management techniques, such as massages and listening to soothing music • Eat fermented foods, cook with organic coconut oil, use organic raw apple cider as salad dressing, and consume healthy fats, and cold pressed oil • Use natural remedies for pain, like homeopathic arnica • Drink kombucha and take probiotics • Run an air filter in your bedroom while you sleep	• Start a rigorous exercise program, sit in a sauna, or get dental work (not even cleanings) • Wait until labor arrives to discuss NOT subjecting your baby to vaccines • Talk on a cell phone without a headset or work with a laptop computer on your lap • Undertake a major home renovation (concern is for lead and other toxins in the process)

Infancy

Healthy babies grow and develop perfectly when nature's biochemical processes are allowed to unfold uninterrupted. The sequence of events that leads an infant to begin to focus, develop gross and fine motor skills, begin to speak and to walk is based on a delicate but deliberate series of biochemical processes and chemical interactions. A primary goal of raising a healthy infant is to avoid disruption or interference with this sequence. Babies look fragile and, indeed, they are. An infant's immune system, which guards the rest of the body from harm, is immature and requires time and peace to mature maximally. Thus, help your infant progress uninterrupted by avoiding the introduction of toxins, viruses, allergens, and heavy metals into their bodies. In light of this, parents should consider an alternate, gradual vaccine schedule of carefully thought through vaccines for infants being raised in the domestic United States.

If you have amalgams and plan to nurse, you should send a sample of your breast milk to a specialty lab for heavy metal testing. If you plan to use formula, use those containing DHA (docosahexanenoic acid), an essential fatty acid critical to the healthy development of the central nervous system. In terms of food introduction, organic baby food is recommended. Start feeding with organic rice cereal. Avoid the introduction of soy, gluten, or dairy until after the baby turns two years of age. After one year, supplement your baby with a quarter teaspoon of mercury-free cod liver oil – again this is to increase the supply of omega-3 essential fatty acids.

In terms of coping with baby colds and other minor illnesses, unless symptoms are severe, less is more when it comes to treatment. For fevers over 101˚F, treat with a tepid bath or dye-free ibuprofen. Fevers, while nerve-wracking for new parents, are the response of a healthy immune system reacting to kill off an invading virus through heat. Antibiotics should be used sparingly and only for confirmed bacterial infections (they do not alleviate viral infections). Remember, antibiotic use disrupts the normal gut flora and promotes the overgrowth of yeast and resistant organisms that, in turn, harms the optimal functioning of the immune system. Bear in mind that most ear infections are viral and are thus not treatable with antibiotics. Use homeopathic ear drops to help ease the symptoms associated with ear infections and colds.

DO	DON'T
• Invest in an organic baby matress, bedding and pillows and hypo allergenic encasements • Bathe your baby daily in warm filtered water — enjoy the experience with your baby! • Feed with all organic and hormone-free products • Feed baby using glass bottles • Wearing a hat, walk outside with baby to get 10 to 15 minutes of sunshine daily • Run an air filter in baby's bedroom	• Clothe the baby in pajamas soaked in flame retardant chemicals • Use soaps, moisturizers, or other "baby products" on the skin as such items are unnecessary and contain harmful chemicals • Introduce dairy, gluten, or soy until after age two • Feed baby from plastic bottles or cups or microwave formula or breast milk • Take your infant into polluted and heavily populated locations

Source: http://www.autismfile.com/what-is-autism-facts/autism-symptoms/avoiding-autism

Reprinted with permission.

When a truth is not given complete freedom,
freedom is not complete.

~ Vaclav Havel

Appendix 15

RECIPES

Cooking with Ana

Since 2001 Ana Bobadilla has been a chef to Kerri Rivera and family, including her son Patrick, who has a diagnosis of regressive autism. Over the years she has mastered gluten-free/casein-free to vegan to Atkins and back again. Her dishes always impress and nourish guests and family members alike.

One of the most important pieces to the autism recovery puzzle is diet. As Kerri always says, if your goal is to heal autism, you must do *The Diet.* However, that is easier said than done for many families whose children have self-limited to grilled cheese sandwiches and pizza.

A book is in the works containing dozens of delicious recipes using natural ingredients that can be found in almost any country. Ana has found unique ways to make foods that children on the spectrum can enjoy, without breaking the bank. The ingredients that she uses can be found all over the world, not just the US. They are presented here in a very approachable way so even if you are not a whiz in the kitchen your child will be able to enjoy what you serve.

The following is a sneak peek from *Cooking with Ana*:

Almond Milk

Amount: 1 L of milk

- 1 cup of peeled almonds
- 1 L of filtered water
- Stevia and vanilla to taste

Preparation:

To a saucepot of boiling water, add the almonds. Remove immediately from the fire. Allow almonds to soak for 20 minutes, remove them from water, rinse, dry and blend in a liter of filtered water. Strain the liquid through a piece of cheesecloth until all the water is drained. Add agave syrup and vanilla to taste.

Vegetable Fries

3 Servings

Ingredients:

- 3 Carrots
- 1 cup oil
- Salt to taste

Preparation:

Peel the carrots and then form very thin slices using the same peeler. Pat dry with a piece of cloth to remove any excess water. Heat oil in a frying pan and fry carrots. When frying be very careful because they can quickly burn, be sure to have a slotted spoon ready to remove from the oil as soon as they are crisp. After frying carrots remove excess oil with a paper towel and sprinkle some salt on top of them.

You can also do this recipe with banana, potato, sweet potato or jackfruit. This is a great alternative to French fries or if you want to eat something crunchy.

Beef or Chicken Tostadas

4 Servings

Ingredients:

- 5 ground chicken breasts or beef filets
- 1 cup of rice or coconut flour
- 1 cup of oil
- Salt and pepper to taste

Preparation:

In a mixing bowl, combine the ground chicken, flour, salt, pepper and a ½ cup of oil. Mix thoroughly until a uniform dough results. Take approximately 2 tablespoons of the dough and form small tortillas/flat circles with it. They should be approximately ¼ inch think and 4 inches wide. Fry in a layer of oil until cooked through, and a thin outer crust forms, or bake in a 350 degree oven, after pouring a dollop of oil on top of each tostada.

Coconut Bars

15-18 bars

Ingredients:

- 3 cups of vegan butter (or coconut oil)
- 1 cup of honey
- 1 cup of raisins
- 1 cup of grated of coconut
- 1 cup of walnuts
- 1 tablespoon of salt

Preparation:

In a saucepan over medium heat combine honey and butter, stirring constantly for a few minutes until thoroughly combined. Remove from heat and mix with all other ingredients. Spread in a 9x13 casserole pan without oil, and bake in an 350°F (180°C) over for 25 minutes until it sets. Allow to cool, and cut into small rectangles.

Get people back into the kitchen
and combat the trend toward
processed food and fast food.

~ Andrew Weil

Appendix 16

Websites We Like

General:

- **Our website containing the latest information about our research, videos, forums, etc.**
  www.cdautism.org

- **The Spanish version of our website.**
  www.autismo2.com

- ***Curando el Autismo* is a Puerto Rican organization created by three mothers of children recovered from autism who have an interest in helping the community learn about their options.**
  www.curandoelautismo.com

- **Defeating Autism - Non-Profit Organization in Venezuela that utilizes Kerri's Protocols.**
  www.fundacionvenciendoelautismo.blogspot.mx

- **Autism Research Institute originally founded by Dr. Bernard Rimland. Home of the ATEC survey.**
  www.autism.com

- **Our public Facebook page.**
  www.facebook.com/groups/AutismCD

- ***CD Health*: Facebook group dedicated to using the protocol for non-autism related issues.**
  www.facebook.com/groups/mojoother

Diet:

- **Website forcused on the *Specific Carbohydrate Diet*™ (SCD) in English.**
  www.pecanbread.com

- **Top 10 FAQs about the *Specific Carbohydrate Diet* (SCD) in Spanish.**
  www.pecanbread.com/pandenuez/10preguntas.html

- **Autism Network for Dietary Intervention**
  www.autismndi.com

- **Gluten Free/Casein Free Diet Intervention website.**
  www.gfcfdiet.com

- **Intestinal health through diet with the Specific Carbohydrate Diet™**
  www.breakingtheviciouscycle.info

- **Resource for naturally healing digestive disease, reducing stress and living a long, healthy life.**
  www.scdlifestyle.com

- ***The Feingold® Association* is a non-profit organization helping provide dietary management and generate public awareness of the role food and synthetic additives play in behavior, learning and health problems.**
  www.feingold.org

Chlorine Dioxide (CD):

- **Jim Humble's MMS (CD) website.**
  www.jimhumble.org

- **Another popular site about MMS (CD).**
  www.mmswiki.org

- **Spanish site selling various books about MMS (CD)**
  www.voedia.com

- **Andreas Kalcker's website (in English)**
  www.andreaskalcker.com

- **CD research site by Andreas Kalcker (in Spanish)**
  www.medicasalud.com

- **A huge public health forum with thousands of discussions about every imaginable health topic. Also includes surveys about various topics.**
  www.curezone.com

- **Good sources of CD and other related supplies.**
  www.wps4sale.com
  www.mightyguts.com

- **The latest information on CDH.**
  http://www.mmsinfo.org/infosheets/infosheet_cdh.pdf

Hyperbarics:

- **Good source of information about Hyperbaric Oxygen Therapy.**
  www.hyperbaric-oxygen-info.com

Other Valuable Source of Information:

- **PubMed comprises of more than 23 million citations for biomedical literature from MEDLINE, life science journals, and online books.**
  www.ncbi.nlm.nih.gov/pubmed

- **Parents Helping Parents - P.A.N.D.A.S. Network: A Resource Library of Medical Studies and Case Histories**
  www.pandasnetwork.org

- **International OCD Foundation**
  www.ocfoundation.org/PANDAS/

Videos / Audio of Interest:

- **Video Testimonials. This link contains various health testimonials related to MMS, many are about autism.**
  www.youtube.com/mmstestimonials

- **AutismOne 2012: 38 Children Recovered in 20 months with MMS by Kerri Rivera**
  www.autismone.org/content/38-children-recovered-20-months-mms-0

- **Video about Kerri, produced by Daniel Bender in 2012.**
  www.youtube.com/watch?v=HnCiX5bII-Y

- **Kerri speaks in Bulgaria, 2013 (Voice in English, slides in Bulgarian)**
  www.youtube.com/watch?v=4OxNGIEWzds

- **Kerri on the Robert Scott Bell Show**
  http://www.youtube.com/watch?v=-1zJhr5VhxE

- **MMS Autism Webinars**
  http://www.ustream.tv/channel/mms-autism-webinar%20

- **Patrick Timpone interviews Kerri Rivera (8/15/2013)**
  http://oneradionetwork.com/health/kerri-rivera-healing-the-symptoms-known-as-autism-children-are-not-born-with-autism-so-they-should-not-die-with-it-august-15-2013/

- **Patrick Timpone interviews Kerri Rivera (11/18/2013)**
  http://oneradionetwork.com/health/kerri-rivera-encore-interview-healing-the-symptoms-known-as-autism-using-parasite-protocols-and-chlorine-dioxide-november-18-2013/

- **Bulletproof Executive Radio with Dave Asprey (11/27/2013)**
  http://www.youtube.com/watch?v=R7s7lYj2SCs

Appendix 17

Direct Help from Kerri Rivera

Consults

Since the release of the first edition of the book, we have found that when families decide to implement The Protocol some do not need further assistance beyond reading the information in this book, using our online support groups, YouTube videos, and attending conferences. However, there are some of us who need a more personalized approach and support to navigate the information, or would like ideas on dosing or timing.

For those of us who need or want that additional support, consults are perfect. We can work together to map out a plan for the parent/family and child, brainstorm through challenges, or just know that you will never walk alone. Whatever the case may be I am available if you need me. I am fluent in English and Spanish, and we can use a translator for other languages. We can speak over the phone or on Skype.

As time goes on, more and more practitioners will be able to support families while using this protocol. In the meantime, If you would like to set up a consult with me, please click on the "Consult Kerri" button on...

www.CDAutism.org

...and follow the instructions there.

> Kerri Rivera's undivided attention + discussing your child + $100 = priceless. Tonight, instead of living it up in Mexico, Kerri spent her Friday evening on the phone doing a consult with me. Not only was the consult informative but also highly enjoyable. Kerri's energy is contagious, her vision boundless and her sense of humor edgy (just the way I like it). Kerri thank you for rocking our world! You are an amazing lady and my family is eternally grateful for your love of our children. Peeps, if you are new, stuck, confused or you want a better understanding of the protocol PLEASE, PLEASE, PLEASE take advantage of this opportunity. I've done a million consults over the years but this was by far my favorite.

Note: A consult with Kerri does not constitute medical advice, nor is it a substitute for a consult with your doctor or healthcare provider. As always, you are responsible for your health, and for the health of your children.

might not be
tonight.
tomorrow or
the next day..
but everything's
gonna be ok
e.s

Healing
the symptoms known as
Autism
1st Edition

References

Chapter 3 - Diet

1. Siri, Ken, and Tony Lyons. Cutting-Edge Therapies for Autism 2011-2012. New York: Skyhorse, 2011. Print.
2. Knivsberg, A.M., K.L. Reichelt, T. Høien, and M. Nødland. "A randomized, controlled study of dietary intervention in autistic syndromes. Nutritional Neuroscience 5.4 (2002) : 251-261. Print.
3. "Frequently Asked Questions." The GFCF Diet Intervention – Autism Diet. TheGFCDiet.com, n.d. Web. 19 Mar. 2013.
4. Reichelt, Karl L., Dag Tveiten, Anne-Mari Mari Knivsberg, and Gunnar Brønstad. "Peptides´ role in autism with emphasis on exorphins." Microbial Ecology in Health & Disease 23 (2012). Web. 11 May 2013.
5. Shattock, Paul, and Paul Whiteley. "Biochemical aspects in autism spectrum disorders: updating the opioid-excess theory and presenting new opportunities for biomedical internvention. Expert Opinions on Therapeutic Targets 6 (2002) : 175–183. Print.
6. Fasano, A. "Dr. Fasano on Leaky Gut Syndrome and Gluten Sensitivity. " Gluten Free Society, n.d. Web. 11 May 2013.
7. "How does gluten and casein relate to the problem of autism?" University of Florida. Department of Pediatrics Division of Genetics and Metabolism, n.d. Web. 11 May 2013.
8. Appleton, Nancy, and G.N. Jacobs. Suicide by Sugar A Startling Look at Our #1 National Addiction, New York: Square One, 2009. Print.
9. Tobacman, J.K. "Review of harmful gastrointestinal effects of carrageenan in animal experiments." Environmental Health Perspectives 109.10 (2001) : 983-994. Print.
10. McMillan, Tricia. "Does Splenda sugar substitute have chlorine in it?" Livestrong.com, Demand Media. 11 June 2011. Web. 11 May 2013.
11. "Food and Drugs." 21 CFR 102.22. 2012. Web. 11 May 2013.
12. Wallinga, David, Janelle Sorensen, Pooja Mottl, and Brian Yablon. Institute for Agriculture and Trade Policy. "Not So Sweet: Missing Mercury and High Fructose Corn Syrup." 2009. Web. 11 May 2013.
13. Gottschall, Elaine. "About the Diet." Breaking the Vicious Cycle, n.d. Web. 11 May 2013.
14. Gottschall, Elaine. "Autism & GI Problems." Breaking the Vicious Cycle. n.d. Web. 11 May 2013.

15. Reasoner, Jordan. "Phenols and Salicylates: What They Are and Why it Matters." SFK. Web. 2010. 11 May 2013.

16. Campbell-McBride, Natasha. Gut and Psychology Syndrome: Natural Treatment for Autism, Dyspraxia, A.D.D., Dyslexia, A.D.H.D., Depression, Schizophrenia. 2nd ed. Cambridge UK: Medinform. 2010. Print.

17. Sarah. "Don't Waste Your Time: Why the Candida Diet Doesn´t Work." The Healthy Home Economist. Austus Foods. 15 Nov. 2012. Web. 11 May 2013.

Chapter 4 - An Introduction to Chlorine Dioxide

1. Port, Tami. "Gram Negative (Gram-) Bacteria." Suite101. 27 July 2007. Web. 11 May 2013.

2. Toxicological Profile for Chlorine Dioxide and Chlorite. U.S. Department of Health and Human Services. Public Health Service. Agency for Toxic Substances and Disease Registry. September 2004. Pg 25. 3.2.2 Oral Exposure. 3.2.2.1 Death. Web. 11 May 2013.

Chapter 5 - Chlorine Dioxide (CD)

1. Lubbers, Judith R., Sudha Chauan, and Joseph R. Bianchine. "Controlled Clinical Evaluation of Chlorine Dioxide, Chlorite and Chlorate in Man." Environmental Health Perspectives 46 (1982) : 57-62. Print.

2. Ballantyne, Coco. "Strange but True: Drinking Too Much Water Can Kill You." Scientific American. 21 June 2007. Web. 11 May 2013.

3. "Woman died from too much water´." BBC News. 12 Dec. 2008. Web. 11 May 2013.

4. Humble, Jim. The Master Mineral Solution of the Third Millennium. 5th ed. Jim V. Humble 2011. Print.

5. Harman, D. "Aging: a theory based on free radical and radiation chemistry." Journal of Gerontology 11.3 (1956) : 298-300. Print.

6. Harman, D. "The biologic clock: the mitochondria?" Journal of the American Geriatrics Society 20 (1973) : 145–147. Print.

7. Watson, J. "Oxidants, antioxidants and the current incurability of metastatic cancers." Open Biology. 12 April 2013. Web. 11 May 2013.

8. Tarr, Peter. "Nobel laureate James Watson publishes novel hypothesis on curing late-stage cancers." Cold Spring Harbor Laboratory. 7 January 2013. Web. 11 May 2013.

9. Kilic, Eser, Süleyman Yazar, Recep Saraymen, and Hatice Ozbilge. "Serum malondialdehyde level in patients infected with Ascaris lumbricoides." World Journal of Gastroenterology 9 (2003) : 2332-2334. Print.

10. Kosenko, Elena, Yuri Kaminski, Oksana Lopata, Nikolay Muravyov, and Vicente Felipo. "Blocking NMDA receptors prevents the oxidative stress induced by acute ammonia intoxication." Free Radical Biology & Medicine 26 (1999) : 1369-1374. Print.

11. Lee, J.K., E.H. Choi, K.G. Lee, and H.S. Chun. "Alleviation of aflatoxin B1-induced oxidative stress in HepG2 cells by volatile extract from Allii Fistulosi Bulbus." Life Science 77 (2005) : 2896-2910. Print.

12. Nielsen, F., B.B. Mikkelsen, J.B. Nielsen, H.R. Andersen, and P. Grandjean. "Plasma malondialdehyde as biomarker for oxidative stress: reference interval and effects of life-style factors." Clinical Chemistry 43 (1997) : 1209-1214. Print.

13. Anwar, H., M.K. Dasgupta, and J.W. Costerton. "Testing the susceptibility of bacteria in biofilms to antibacterial agents." Antimicrobial Agents and Chemotherapy 34.11. (1990) : 2043-2046. Print.

14. Usman, Anju. AutismPedia. 12 May 2010. Web. 11 May 2013.

15. Budinger, Mary. "Lyme-Induced Autism Conference Focuses on Biofilm and Toxicity." Public Health Alert. 4.8. Publichealthalert.org. Aug. 2009. Web. 11 May 2013.

16. "Children With Autism Have Mitochondrial Dysfunction, Study Finds." Science News. 30 November 2010. Web. 11 May 2013.

17. MMS Autism Webinar - May 10, 2012, Andreas Kalcker & Kerri Rivera.

Chapter 8 - The Kalcker Parasite Protocol

1. Volinsky, Alex, A., Nikolai V. Gubarev, Galina M. Orlovskaya, and Elena V. Marchenko. "Developmental stages of the rope´ human intestinal parasite" Submitted to arxiv.org 13 Jan. 2013. Web. 11 May 2013.

2. United States. Department of Health and Human Services, Food and Drug Administration, Centre for Food Safety and Applied Nutrition. Fish and Fishery Products Hazards and Controls Guidance 4th Edition. Florida: Government Printing Office, 2011. Web. 11 May 2013.

3. Zam, S.G., Martin, W.E., and Thomas Jr., L.J. "In Vitro uptake of Co^{60} –vitamin B_{12} by *Ascarias suum." The Journal of Parasitology 49* (1963): 190-196. Print.

4. Vasudevan D.M., Sreekumari, S., and Vaidyanathan, K. "Textbook of BIOCHEMISTRY for Medical Students. 6th ed." *Section D: Nutrition*. New Delhi, 2011. 404. Print.

5. "Water related diseases; Ascariasis." Water Sanitation Health. WHO. 2013. Web. 11 May 2013.

6. "Mebendazole Dosage." Drugs.com. n.d. Web. 11 May 2013.

7. Wina, Peter. "Clay Uses – Parasite Removal – Yes, You Do Have Worms!" aboutclay.com. n.d. Web. May 13 2013.

8. "Parasites – Cysticercosis." Centers for Disease Control and Prevention. n.d. Web. 11 May 2013.

9. Nielsen, Flemming, Mikkelsen, Bo Borg, Nielsen, Jesper Bo, Andersen, Helle Raun, and Grandjean, Philippe. "Plasma malondialdehyde as biomarker for oxidative stress: reference interval and effects of life-style factors." Clinical Chemistry 43 (1997) : 1209-1214. Print.

Chapter 9 - Other Supplements

1. "What are probiotics?" Theralac. Master Supplements. n.d. Web. 11 May 2013.
2. "Frequently Asked Questions About Theralac." Purest Colloids. 2013. Web. 11 May 2013.
3. "Autism." The Probiotic Revolution. Freedom. n.d. Web. 11 May 2013.
4. Messaoudi, Michaël, Robert Lalonde, Nicolas Violle, Hervé Javelot, Didier Desor, Amine Nejdi, Jean-François Bisson, Catherine Rougeot, Matthieu Pichelin, Murielle Cazaubiel, and Jean-Marc Cazaubiel. "Assessment of psychotropic-like properties of a probiotic formulation (Lactobacillus helveticus R0052 and Bifidobacterium longum R0175) in rats and human subjects." British Journal of Nutrition 105 (2011) : 755–764. Print.
5. Silk, D. B. A., A. Davis, J. Vulevic, G. Tzortzis, and G.R. Gibson. "Clinical trial: the effects of a trans-galactooligosaccharide prebiotic on faecal microbiota and symptoms in irritable bowel syndrome." Alimentary Pharmacology & Therapeutics 29 (2009) : 508–518. Print
6. "Omega-3 fatty acids." University of Maryland Medical Center. A.D.A.M. 2011. Web. 11 May 2013.
7. "Omega-6 fatty acids." University of Maryland Medical Center. A.D.A.M. 2011. Web. 11 May 2013.
8. Bell, J.G., E.E. MacKinlay, J.R. Dick, D.J. MacDonald, R.M. Boyle, and A.C.A. Glen. "Essential Fatty Acids and Phospholipase A2 in Autistic Spectrum Disorders." Prostaglandins Leukotrienes and Essential Fatty Acids 71.4 (2004) : 201-204. Print.
9. Richardson, A.J., and P. Montgomery. "The Oxford-Durham Study: A Randomized, Controlled Trial of Dietary Supplementation with Fatty Acids in Children with Developmental Coordination Disorder." Pediatrics 115.5 (2005) : 1360-1366. Print.
10. "GABA." Healing Autism & ADHD. n.p. n.d. Web. 11 May 2013.
11. English, Jim. "Saving Eli: One Family´s Struggle with Autism." Jim English. 2012. Web. 11 May 2013.
12. "L-Theanine Information." L-Theanine. n.d. Web. 11 May 2013.
13. "Pycnogenol." Horphag. n.d. Web. 11 May 2013.
14. "1 in 50 US. Kids Have Autism." Autism Coach. n.d. Web. 11 May 2013.
15. Chez, Michael G., Cathleen P Buchanan, Mary C. Aimonovitch, Marina Becker, Karla Schaefer, Carter Black, and Jamie Komen. "Double-Blind, Placebo-Controlled Study of L-Carnosine Supplementation in Children With Autistic Spectrum Disorders." Journal of Child Neurology 17 (2002) : 833-837. Print.
16. Smith, Leonard. "Are You Dangerously Deficient in Taurine?" drlwilson. n.d. Web. 11 May 2013.
17. "DMG supplement." Healthcare Information Directory. iHealth Directory. n.d. Web. 11 May 2013.
18. "Dimethylglycine (DMG) for Autism." Autism Research Institute. n.d. Web. 11 May 2013.

19. "Find a Vitamin or Supplement Betaine Anyhydrous." WebMD. Therapuetic Research Faculty. 2009. Web. 11 May 2013.
20. "Nutritional DMG/TMG Treatment Overview." Autism Canada Foundation. 2011. Web. 11 May 2013.

Chapter 10 - Chelation

1. "Why Cleanse Metals." Baseline of Health Foundation. n.d. Web. 11 May 2013.
2. Klinghardt, Dietrich. "D: Amalgam/mercury detox as a treatment for chronic viral, bacterial and fungal illnesses." Explore 8 (1997) : 13-16. Print.
3. Price, Weston A. Nutrition and Physical Degeneration. 8th ed. Lemon Grove, CA: Price Pottenger Nutrition, 2008. Print.
4. "Bentonite clay for internal healing." Healing Daily. 2005. Web. 11 May 2013.
5. Clinical Evaluation of Bio-Chelate™." Bio-Chelat™. 09 Dec. 1987. Web. May 11, 2013.

Chapter 11 - Hyperbarics

1. University of Pennsylvania School of Medicine. "Penn Study Finds Hyperbaric Oxygen Treatments Mobilize Stem Cells." ScienceDaily. 28 Dec. 2005. Web. 11 May 2013.

Chapter 12 - GcMAF & Autism

1. Bradstreet, James Jeffrey, Vogelaar Emar, and Thyer Lynda. "Initial Observations of Elevated Alpha-N-Acetylgalactosaminidase Activity Associated with Autism and Observed Reductions from GC Protein—Macrophage Activating Factor Injections." Original Research. "Autism Insights 4 (2012): 31-38. Print.

Chapter 14 - Miscellaneous Information You Should Know

1. Garcia, H.H, and M. Modi. Helminthic parasites and seizures. Epilepsia 49 Suppl 6. (2008) : 25-32. Print.
2. "Self-Injurious Behavior." Autism Research Institute. n.d. Web. 11 May 2013.
3. PANDAS-PITAND Awareness & Research Support. 2011. Web. May 11 2013.
4. Jenike, Michael, and Susan Dailey. International OCD Foundation. 2012. Web. May 11 2013.
5. Jenike, Michael, and Susan Dailey. "Sudden and Severe Onset OCD – Practical Advice for Practitioners and Parents." Beyond OCD. 2013. Web. 11 May 2013.
6. Bock, Kenneth and Nellie Sabin. The road to Immunity: How to Survive in a Toxic World. New York: Pocket Books, 1997. Print.
7. "Fever." AskDrSears. 2013. Web. 11 May 2013.
8. "NINDS Febrile Seizures Information Page." National Institute of Neurological Disorders and Stroke. 2013. Web. 11 May 2013.

9. Gilbère, Gloria. "Skin & Intestinal Disorders." Leaky Gut Syndrome. Dawn Mellowship. 2005. Web. 11 May 2013.

10. Edward, F. "14 Common Symptoms of Parasites." Parasite Cleanse Resource Center. 10 June 2009. Web. 11 May 2013.

11. "Body Burden: The Pollution in Newborns. A Benchmark Investigation of Industrial Chemicals, Pollutants and Pesticides in Umbilical Cord Blood." Environmental Working Group. 14 July 2005. Web. 11 May 2013.

Appendix 5 - Molecular Mimicry

1. Fasano A, Berti I, Gerarduzzi T, Not T, Colletti RB, Drago S, Elitzur Y, Green PH, Guandalini S, Hill ID, Pietzak M, Ventura A, Thorpe M, Kryszak D, Fornaroli F, Wasserman SS, Murray JA, Horvath K. "Prevalence of celiac disease in at-risk and not-at-risk groups in the United States: a large multicentre study." Arch Intern Med. 163.3 (2003): 286-292. Print.

2. Vojdani A, O'Bryan T, Kellermann GH. "The immunology of gluten sensitivity beyond the intestinal tract." European Journal of Inflammation." 6.2 (2008) : 0-0.

3. Vojdani A., O'Bryan T, Kellermann GH. "The Immunology of Immediate and Delayed Hypersensitivity Reaction to gluten." European Journal of Inflammation Vol 6.1, (2008) :1-10

4. Vojdani A, O'Bryan T, Green JA, McCandless J, Woeller KN, Vojdani E, Nourian AA, Cooper EL. "Immune Response to Dietary Proteins, Gliadin and Cerebellar Peptides in Children with Autism." Nutr Neurosci. 7.3 (2004) : 151-161. Print.

5. Ford RP. "The gluten syndrome: a neurological disease. Med Hypotheses." 73.3 (2009) : 438-440. Print.

6. Ford, RP. The Gluten Syndrome: Is Wheat Causing You Harm. Dr. Rodney Ford MD MBBS FRACP Smashwords 2011 ebook

7. Hadjivassiliou M, Sanders DS, Grunewald RA, Woodroofe N, Boscolo S, Aeschlimann D., "Gluten sensitivity: from gut to brain." Lancet Neurol. 9.3(2010):318-30.

8. Solaymani-Dodaran M, West J. Logan RF. Long-term mortality in people with celiac disease diagnosed in childhood compared with adulthood: a population-based cohort study. Am J Gastroenterol. 102.4 (2007): 864-870. Print.

9. Fedoroff, Nina V, and Nancy Marie Brown. Mendel in the Kitchen: A Scientist's View of Genetically Modified Food. Washington, DC: Joseph Henry Press, 2006. Print.

10. Corrao G, Corazza GR, Bagnardi V, Brusco G, Ciacci C, Cottone M, Guidetti CS, Usai P, Cesari P, Pelli MA, Loperfido S, Volta U, Calabró A, Certo M. "Mortality in patients with coeliac disease and their relatives: a cohort study." Lancet. 358.9279 (2001) : 356-361. Print

Index

5-Hydroxytryptophan 249
  dosing 249
5-N-ethyl-glutamine. *See* L-theanine
7 Day Fridge MMS 158
72/2 protocol 115, 126, 128

A

ABA. *See* Applied Behavior Analysis (ABA)
absorption
  proper 60
abstract thinking 250
Accidental Cure by Optimists (article) 443
ACE. *See* Autism Center of Excellence
acetic acid 52
acetylcholine 247
acid exposure 118
acidic activator 93, 96, 105, 110, 123, 146
  citric acid 90, 93, 94, 146, 147. *See also* citric acid
  hydrochloric acid 93
  lemon juice 93
  lime juice 93
acidity in the body 236
acne 86, 247, 337, 338
actifolate 342
activated charcoal 143
activator 78, 93. *See* acidic activator
  buying 94
acupuncture 445
ADD 64, 352
additives, food 61
ADHD 64, 268, 347, 352, 367, 393, 425
affection 229
African sleeping sickness 176
agave syrup 52
aggression 62, 103, 133, 325
aging
  premature 485
Aginsky, Dr. Bernard 277, 278
agitation 20
AIDS 85, 138, 296, 298, 300, 315
air freshener 343
air quality 506
ALA 122, 133, 138
albendazole 327, 328, 329
Albenza®. *See* albendazole
alcohol 240, 343, 508
Alecson, Deborah Golden 73
alertness 248, 250
alfalfa 486
algae 485
Alinia® 327
allergens 50, 488
allergic reactions 50, 55, 66, 451
  emergency 455
allergies xxi, xxiii, 10, 45, 49, 56, 57, 69, 70, 71, 73, 128, 137, 181, 247, 256, 338, 345, 444, 508
  food 338
allergy panel 56
allergy-type symptoms 57
almond milk 134
almonds 51, 63
alpha-gliadin. *See* gliadorphin
alpha-N-acetylgalactosaminidase (Nagalase). *See* Nagalase
aluminum 255, 256, 487, 506, 507
Alzheimer's Disease 85, 120, 247, 251, 256, 300, 445, 487
amalgams 509
amaranth 51
American Dairy Association 71

American Journal of Physiology 290
amino acids 48, 69, 245, 248, 249, 250, 251, 252, 450, 458
amino acid sequences 452, 455
ammonia 88, 176, 229, 236, 323
  high 182
amoebas 85, 190, 233, 238
amyotrophic lateral sclerosis 316
anal itching 179, 181, 220
anemia 176, 182, 314
anger 34, 178
angiogenesis 299
anorexia 179, 333
antacids 257
anthelmintic, broad spectrum 192
antibacterial agent 508
antibiotics 11, 75, 82, 118, 119, 244, 246, 327, 329, 333
  use 1
antibodies 50, 451, 452, 455, 457
  production of 335
  tests for 66
antibody panel 463
antibody-specific immunoglobulin E 49
anticancer agent 314
antifungals 11, 82, 327
anti-inflammatory 250, 485
    antimicrobial agents 118
antioxidant foods 123
antioxidants 45, 86, 87, 88, 124, 127, 132, 138, 139, 143, 250
anti-parasitic medications 326, 328
anti-seizure 327
  medications 251
antiseptic, nontoxic 85
antivirals 11, 82, 327, 329
anxiety 20, 54, 103, 136, 178, 179, 246, 248, 325, 333, 337, 340, 444
anxiety, separation 228
aortal aneurysms 456
appetite 249, 330
appetite, ravenous 178
apple juice 73
apples 51, 57, 61, 63, 76, 133
Applied Behavior Analysis (ABA) 4, 43, 74, 344
Apraxia 15
ARI. *See* Autism Research Institute
Arranga, Teri 13
arsenic 78, 257, 506, 508
arterial wall, strength of 485
arthritis 73, 137, 169, 179, 247, 445
  rheumatoid 144, 443
artichokes 486
artificial colors 49
artificial flavoring 47, 52
artificial sweeteners 52, 55
Ascaris lumbricoides (roundworm) 12, 165, 167, 174, 183, 187, 233, 236, 240
  longevity 174
ASD 64
asparagus 486
Asperger's 347
aspirin 61
asthma 114, 180, 256, 508
ATEC xxi, xxiii, 46, 47, 136, 140, 141, 319, 339
  not going down 136
  statistics 121
athletic performance 252
atrazine 508
autism 44
  adults with 339
  avoiding 505
  curing 303
  environmental factors 506
  epidemic 505
  regressive 236, 347
  statistics viii, xxv
Autism Canada Foundation 253
Autism Center of Excellence 274, 275, 276
AutismO2 Clinic 7
AutismOne (conference) 5, 13, 14, 24, 444
AutismPedia 119

Autism Research Institute 6, 7, 276, 278
Autism Society of America 2
Autism Treatment Evaluation Checklist. *See* ATEC
autoimmune 462
autoimmune deficiencies 169
autoimmune disease 295, 453, 460
autoimmune gluten reaction. 453
autoimmune reactivity 453
autoimmunity 452, 453
autonomic nervous system 456
avocados 63, 460
azadirachta indica. *See* neem

B

Babesiosis 176
baby 505, 509
baby bottle 98, 109, 493
  Lifefactory.com 95
  method 90
bacteria xxi, xxiii, 10, 11, 52, 59, 70, 76, 78, 81, 82, 85, 118, 140, 162, 225, 244, 258, 261, 334, 345, 488
  beneficial 82
    imbalance of 245
  growth 59
  harmful 61
  healthy 231
  intestinal 485
  load 84
  negatively charged 78
    CD kills 78
  overgrowth 61
  positively charged 78
bad breath 182
bagels 67, 457
baking soda 124, 343, 490
balance 274
bananas 57, 63, 73, 76
banging 1
bark 55
barley 49, 66, 69, 455, 486
barometer 280
barometric pressure 280
basal ganglia damage 334
basophils 50
bath 131. *See also* salt baths; *See also* CD baths
bathtub 114
B-Complex 342. *See also* vitamin B
beans 52, 252
  navy 52
beauty products 255
bedwetting 181, 333
beef 50
bee pollen 457
bee stings 66, 451. *See also* bee venom
beets 253, 486
bee venom 455
behavior 228, 247, 248, 324
  changes 253, 256
  problems 20, 70
  undesirable
    probiotics, remove 226
behavioral
  reactions 62
bell peppers 486
bentonite clay 140, 143, 257, 258
  baths 257, 259
    schedule 259
Bernie. *See* Rimland, Dr. Bernard
berries 61, 123, 133
beta-alanine 250
beta amyloid plaque 251
beta-carotene 87
betaine anhydrous. *See* trimethylglycine (TMG)
bifidobacterium 244
bile 231
Bio-Chelat™ 140, 257, 258, 259, 320
biofilm xxiii, 11, 45, 103, 111, 117, 118, 119, 129, 130, 143, 165, 226, 235, 257, 261, 444
  appearance 130
  protocol 11
  what is 118
  why CD works on 119
bioflavonoids 61
biomedical intervention 341

biomedical protocols 347
biomedical treatments 11, 140
biomed movement 334
biopsy 454, 455
bipolar disorder 120
birth-control patches 73
bisphenol A 508
biting 332
  hand 331
black pit depression 458
black walnut 226
bladder infections 244
blank chart 198
bleach 79, 84
blisters 89, 338
blitz day. *See* mebendazole
bloating 51, 89, 177
blood 50, 85, 253, 299, 310, 507
blood analysis 182
blood-brain barrier 10, 48, 49, 451, 453
blood cells 251
blood disorders 176
blood flow
  changes in 458
blood panels 461
blood parasites 176
blood pressure, high 485
blood stream 48, 60, 75, 103, 145, 337
blood tests 67, 70, 243, 261, 454
blood vessels 250, 453
blood vessel walls 461
blueberries 87
Bobadilla, Ana 513
Bock, Dr. Kenneth 335
body language 325
body odor 182
body products
  non-toxic 509
bologna 50
bone 65, 253, 255, 259, 261, 453, 461, 485
  disorders 300
  health 487
  marrow 85
  metabolism 300
bone broth 459
borax 343
boron 116, 486
bottle
  wine 162
bouillon cubes 52
bovine respiratory syndrome 145
bowel movements 28, 42, 46, 105, 260
  excessive 177
bowel permeability 48
Bowen, Dr. James 55
Bradfield, Dr. 269, 270, 272
Bradstreet, Dr. 302, 303, 306, 308, 310
brain 49, 65, 248, 249, 250, 251, 253, 255, 259, 295, 305, 307, 310, 320, 323, 344, 453, 461, 487, 507
  connectivity, increased 116
  development 246
  fog 178
  function 247
bread 4, 49, 52, 71
Breaking the Vicious Cycle (book) 60
break the diet 56
breastfeeding 317, 490
breast milk 507
breathing problems 70, 182
bromine 116
bronchiectasis 443
bronchitis 114, 180
brownies 67, 457
brown rice 486
Bruxism. *See* teeth grinding
buckwheat 51
bud 55
Budinger, Mary 119
burbur 143
burns 85, 474
burping 89, 178
butter 49, 72, 78

C

C6H8O7. *See* citric acid
cabbage juice 232
cacao 63, 123
Cade, Dr. 69
cadmium 255, 507
caffeine 134, 250
cake 49
calamus root 231
calcium 45, 90, 116, 118, 119, 236, 486, 487
calcium silicates 190
Calm PRT 342
calves 145
Campbell-McBride MD, Dr. Natasha 75
cancer 54, 55, 87, 121, 295, 296, 298, 299, 300, 316, 335, 444, 445, 456, 507, 508
  bladder 443
  breast 297
    inhibition of 299
  colon 54
  immunotherapy of 297
  metastatic 87
candida xxi, xxiii, 10, 11, 49, 52, 54, 57, 75, 81, 84, 118, 180, 244, 261, 337
  antibiotics 75
  c-section 75
  overgrowth 75, 76
candy 52, 54
canker sores 86
cantaloupes 63
CaprilexTM 342
carbohydrates 59, 60, 75, 119
  complex 59, 60
  digestion 59
  malabsorption 60
carbon 55
carbon dioxide 282
carbon monoxide 508
carcinogenic 55
cardiovascular 246
  problems 508
caricin 233
carnitine 248
carnosine 250
carotene 61
carotenoids 61
carrageenan 52, 54
Carrasco Maceda, Miriam 13, 166, 235
carrots 133, 234
cascara sagrada 240
casein 44, 48, 49, 53, 54, 56, 58, 69, 70, 72, 245
caseinate 72
casein-free 4, 41, 45, 48, 49, 57, 58, 70, 72, 74, 513
cashews 51
casomorphin 44, 49, 56, 58, 69, 245
  peptide 69
castor oil 129, 188, 194, 233, 237, 341
  source & cost 195
catsup 52, 54
cattle 145
cayenne 234
CD 9, 10, 11, 42, 77, 78, 81, 83, 84, 89, 90, 103, 111, 114, 115, 121, 145, 188, 244, 319, 336, 445, 446. *See also* sodium chlorite
  72/2 protocol 115, 126, 128
  activation time 110, 124
  activator 78
  antioxidants 124
  appetite 134
  aqueous solution 84
  ATEC 136
  babies 131
  back-to-back baby bottles 127
  baths 113, 114, 125, 131, 187, 189, 229, 260, 319, 336
  best bottles to store 132
  bottle caps 132
  bottles 135
  bottle, steel 132
  breast milk 131
  buying 82
  capsules 132
  chelator compatibility 140
  chia seeds 134
  child refusing dosing 135
  Controlled Clinical Evaluations of

- Chlorine Dioxide, Chlorite and Chlorate in Man 84
- controversy xiii
- critics 84
- Davy, Sir Hymphrey 77
- deaths 78
- diarrhea 89, 141
- die-off reaction 138
- diet requirements 132
- discomfort 127
- DOs & DON'Ts 122
- doses, missed 136
- dosing 102, 187
- dosing schedule 135
- dosing too low 125
- double doses 103, 125
- double dosing 103, 125
- drug interactions 143
- ears 11
- emergency 142
- enemas 12, 125, 187, 189, 226
- eyes 11
- false information/propaganda 82
- first dose 127
- flying 142
- food 124
- foods to avoid 133
- foot baths 114
- forum 83
- full oral dose 125, 126, 128
  - going past 127
- green tea 134
- hair 11
- harmful? 143
- health 84
- heavy metals 139
- humidifier 225
- industrial bleaching processes 84
- industrial purposes 85
- inhaled 11
- internal consumption 84
- intervention 81
- introduction to 77
- killing parasites 238
- kombucha 134
- life expectancy of 124
- maintenance dosing 238
- Master Mineral Supplement 77
- mercury 141
- molecule 77
- multivitamins 132
- nausea 89
- nebulizer 138
- neutralizers 127
- night dosing 115
- Nutriiveda 134
- oral protocol 11, 100
- overdose 142
- patents 77, 85
- pH 145
- poison index 78
- pregnancy 131
- prescription contraindications 143
- protocol xxiv
- rectal 11
- school 126, 135
- school field trip, dosing on 135
- serving cup dilution 102
- side effects 81, 89
- skin 11
- smell, chlorine like 98, 493
- sodium chlorite 78
- steam bath 114
- stevia 126
- strength 467
- sunlight 124
- supplements 138
- taste 135, 225
- testing 124
- test strips 133, 225
- toxicity 78
- toxic rating 78
- toxic residues, no 82
- troubleshooting checklist 123
- users of 78
- vaginal 11
- vomiting 89
- water 125, 132
- water temperature 132
- weight gain/loss 134
- yellow color 123

CD4 315

CDH 14, 155, 156, 158, 225, 226
- baths 162
- Easy-Peasy method of making 163
- Formulation Table 161
- making, detailed instructions 159
- strength 467
- taste 163
- testing 467
- using 162

CDS 14, 145, 146, 147, 157, 188
- buying 147
- CDS to CD transition table 154
- color of solution 151, 152
- concentration strength 148
- deteriorate plastic (avoiding) 150

- detoxing with 153
- distillation process 145, 147
- enemas 154
- hose, making with a 147, 148
- instructions on making 150
- making 147
  - New Method, with 148
  - Overnight Method, with 148
  - Shot Glass Method, with 148
- metal (avoid) 150
- overdose 146
- Overnight CDS Generating Kit 150, 151
- sleep 146
- sodium chlorite, added back in 146
- stabilized 146
- strength 467
- switching back to CD 153
- testing 467
- time it takes to make 151
- unstabilized 146
- waking time 146

CEA. *See* Curando el Autismo Foundation

celery 133

celiac disease 44, 59, 65, 69, 454, 456, 461
- celiac antibody tests 457
- villi damaged 449

cell-cell interactions 118

cellular metabolism 286

Centers for Disease Control (CDC) 508

central nervous system 62, 176

cereal 49, 71, 253

cerebella ataxia 456

cerebral cortex 309

cerebral palsy 273

cerebrospinal fluid 309

CFS/ME 305, 311, 316
- aetiology 301

chagas disease 176

chanca piedra 191
- dosing 191
- source & cost 191

chart
- Estimated Full Oral CD Doses by Weight 101, 494
- hourly dose / mimimum water dilution 102

Chatelier's Principle 284, 285

cheese 4, 49, 71, 72

cheese puffs 43

chelation 5, 43, 139, 141, 255, 257, 259, 260, 320
- IV 261
- what is 257

chelator xxiv, 119, 257, 258

chemical mutation 457

chemicals 50, 55, 174, 506
- absorption through skin 508

Cheney, Dr. Paul 301

cherries 63

chest pains 179

chia seeds 134

chicken 50, 53, 72

children
- growth spurt 239
- nutritional shakes for 53
- older 140, 155

chili pepper 63
- powdered 63

chills 89

chlorination 83

chlorine bleach 55, 83, 84, 116, 142

chlorine dioxide. *See also* CD
- antioxidants 88
- patents 85
- testing 467

chlorine dioxide gas 147, 149

Chlorine Dioxide Holding (Solution). *See* CDH

chlorine dioxide photometer 158

Chlorine Dioxide Solution (CDS). *See* CDS

chlorite molecule 83

chlorocarbon 55

chocolate 61, 66, 123, 133, 325, 455, 460
- milk 52

cholesterol 509
- high 485

choline 507

choucroute 232

chromium 116

chronic fatigue syndrome 62, 69, 169, 177, 247, 272, 340
chronic illness 256
chronic immune reactions 167
cider vinegar 63
cinnamon 234
citric acid 96, 98, 155, 493
citrus 123, 124, 133, 139
clay 257
cleaning products 508
  harmful 509
clear zone 228
ClO2. *See* CD
clonazepam 42
clorox 78
clostridia 59
clostridium 246
clothes
  sensitivity to 333
cloves 231, 234
coal power plants 255
cobalt 116
coccidiosis 145
cocoa 61, 123
coconut 51, 134, 460
coconut milk 123
coconut oil 63
coconut water 123, 134, 232
cod liver oil 124, 342
coffee 61, 66, 123, 455
cognition 247, 249
cognitive
  abilities 252
  decline 120
  impairment 328
  problems 508
cold 157
  internally 177
cold cuts 50, 53, 55
colds 114
Coley, Dr. William 296, 300
colitis 177
collagen 250, 488
colloidal silver 122, 142
colon 59, 60, 103, 104, 130, 338, 509
  cancer 54
  hydrotherapy 112
colonics 104, 111, 130, 226
  hydrotherapist 130
colored fruits 63
coloring 41
Combantrin®. *See* pyrantel pamoate
combativeness 236
Combined Immune Deficiency 328
comprehension 28
concentration 30, 247
condiments 234
confused thinking 178
congestion 114
  sinus 137
constipation 43, 58, 104, 125, 128, 129, 177, 179, 260, 340
consults with Kerri Rivera 521
cookware 255
coordination 21
  lack of 178
  poor 236
copper 116, 342, 486, 509
CoQ10 122, 127, 138, 342
cork 160, 162
corn 51, 57, 66, 69, 70, 74, 455, 459
corn flakes 52
corn syrup. *See* high fructose corn syrup (HFCS)
cosmetics 257, 489
  absorption of 508
cost of protocol (estimated) 341
cough 114, 180, 182, 340
Courchesne, Dr. Eric 274, 275. *See also* Autism Center of Excellence
Courchesne, Dr. Rachel 275, 277. *See also* Autism Center of Excellence
couscous 49
cow's milk. *See* milk, cow's
cramps 177, 179

crankiness 54
cravings 177, 178, 249
cream 49, 50
cream cheese 72
creams 508
crohn's disease 59
croissants 67, 457
Crook, William 72. *See* Solving the Puzzle of Your Hard to Raise Child (book)
Cruise, Tom (actor) 276
crust 460
crying 332, 458
crystalline silica 489
C-section 75
cucumber 133
Curando el Autismo Foundation vii, 305, 404, 517
curcumin 133
curezone.com 339
cyanide 78
Cyrex Laboratories 450, 454, 463, 464
Cysticercosis 240
cystic fibrosis 59
cysts 145, 179, 180, 240
CytofloraTM 342
cytokines 50, 335

D

dairy 4, 55, 69, 72, 74, 134, 231, 319. *See also* milk
dairy-free 460
Dalton's Universal Gas Laws 284
DAN!. *See* Defeat Autism Now! (DAN!)
dandelion 231
    tea 227, 229
dates 63
Davy, Sir Humphrey 77, 85
daycare 76
DDT 508
DE. *See* diatomaceous earth
Defeat Autism Now! (DAN!) xxii, xxv, 4, 6, 7, 8, 9, 74, 243, 252, 265, 267, 276, 278, 279, 332
    estimated costs 342
defeatist thoughts 48
deficiencies 116
    iron 180
    vitamin B12 180
deglycosylates 298
dehydration 118
dementia 85, 247, 445
dental amalgams 255. *See also* mercury
dental problems 445
deodorant 255
Department of Health & Human Services (DHHS) 78
depression 69, 178, 248, 325, 340, 443, 444, 456, 458, 464
dermatitis 181, 338
dessert 51
detergent 337
    clothing 509
    dishwashing 509
detox 89, 103, 127, 257, 340
detoxification 62, 256, 505
detoxification program 509
detoxing 115
detoxing program 320
detox organs 176
detox pathways 55
detox reaction 339
developing fetus 235
developmental delay 456
Developmental - Individual Difference, Relationship-based Model (DIR®) 344
deworming 166, 231
    importance of lifelong 186
diabetes 54, 247, 251, 256, 313, 445, 507, 508
    type 1 64
    Type II 54
diapers 227
diarrhea 11, 43, 57, 58, 59, 62, 89, 141, 142, 145, 157, 177, 179, 244, 340

diatomaceous earth 143, 188, 190, 226, 237, 238, 341, 485
  calcined 489
  deposits of 486
  dosing 190
  food grade 489
  medication, affect on 238
  source & cost 190
  sources 490
diatomite. *See* diatomaceous earth
diatoms 190, 485
die-off reaction 89
diet xxi, 4, 11, 56, 74, 506
  preventative 231
dietary intervention 42
Diet, The xxiv, 41, 42, 43, 44, 45, 46, 47, 50, 53, 57, 90, 244, 319, 462, 513
digestion 49, 51, 59, 69, 245
  diseases of 61
  enzymes 237
  poor 48
  problems, chronic 245
  system 49, 60
digestive system 454
dimethylglycine. *See* DMG
dimethyl sulfoxide 144
disaccharidase 75
disaccharides 59, 75, 76
discomfort 51, 70, 127
dishwashing detergent 509
dishwashing soap 343
disinfectants 61, 343
disorientation 178
distant 58
distended belly 177, 330
distillate 55
distractible 333
Divers Alert Network xxv
diverticulitis 59
divorce rate 341
dizziness 176, 177, 458
DMG 252, 253, 324, 342
  dosing 252
DMPS 6, 140, 257, 507
  drops 5
DMSA 140, 257
DMSO 137, 144
  application 144
DNA 120, 256, 304
DNA testing 165
Don't Drink Your Milk (book) 72
donuts 49
double-blind placebo xi, 68
double sugars 75
douche bag 108
dough 73
DPP IV enzymes 460
DPT (diphtheria-pertussis-tetanus) 1, 265
drinking water 255, 320
  fluoride 256
drooling 1
  while sleeping 181
drowsiness 180
drugs 295, 489
dry cleaning 509
duodenum 184
dysbiosis 103, 245
dyspnea 180
dyspraxia 247

E

ear
  infections 70, 244, 330
  problems 145
Early Autism Center (Toronto, Canada) 4
ears
  red 62
eating, high volume 228
EBN® Cleansing Clay 258
e-coli 485
ecosystem 246
eczema 181, 247, 337, 338
Edelson Dr. Stephen M. 253, 331
EDTA 119, 140, 257, 258
egg 455
eggs 50, 55, 66, 72, 325, 459
  hard boiled 76
elastin 488

electron shells 11
electrosmog 451
elimination diet 464
ELISA blood test 70
embryo
  chemicals that affect 508
emotion 245
  extreme high 62
  extreme low 62
emotional confusion 229
emotional frigidity hypothesis 276
emotional instability 464
endocrine problems 508
endorphins 248
enema 12, 26, 85, 88, 103, 104, 105, 108, 113, 115, 119, 128, 129, 130, 134, 162, 165, 220, 226, 237, 239, 260, 319, 340
  administering 109
  black specks 131
  bucket 106, 108
  bulb 107, 108, 112, 220
  catheter 108, 110, 111, 130
  CDS 154
  clean up 130
  colonic process, similar to 111
  comments & suggestions from parents 112
  constipation 129
  diarrhea 142
  distractions 113
  DMSO 144
  douche bag 106, 108
  enema bucket 108
  enema bulb 108, 112
  Everclear grain alcohol 130
  explaining to child 110
  fill & release 111
  fleet enema 107, 108
  fleet enema method 112
  frequency 105
  gravity bag 106, 108, 111, 129
  heating water 110
  history 104
  hose 110
  hot water bottle 106, 108
  how far to insert 130
  how to fill the syringes 111
  kids ask for 129
  kits 105, 108
  location 109
  lubricant 105, 110
  mucous 128
  oil 110, 111
  one mom's enema guidelines 113
  options 106
  position 110
  sphincter muscle 111
  stigma 104
  syringes 107, 108, 129, 130
  syringes & catheter 108
  teens & adults 129
  temperature 109
  timing 105, 109, 113, 130
  water 128
    amount of 109
    mixture 110
  when to start 128
energy 60, 147, 156, 247, 256
  lack of 121
  low 177
  production 247
EnhansaTM 342
enterobius vermicularis 185
enterocytes 75
Enterolab 450, 463, 465
enteropathy 454
environment
  beyond thinking green 508
  living 509
  working 509
environmental factors 507
environmental stress 453
environmental toxins 507
enzymes 45, 48, 49, 56, 59, 232, 244, 245, 342, 460
  deficiency 69
enzymolysis 55
eosinophil 338
EPA (Environmental Protection Agency) 255
epigenetics 507
epilepsy 328
epileptic activity 250
epoxy resin 508
Epsom salts 143, 226
equisetum hymale 457
erectile dysfunction 180

eruptions 181
essence or extractive 55
essential fatty acid 247
essential nutrients 178
essential oil 55
excitotoxins 58
exercise 54, 121
  intolerance 120
exhaustion 458
exorphins 245
extracellular polymeric substance 118
eye contact xxii, 42, 46, 58, 247, 252, 458
eyes 137, 253
  dark circles under 62
  degenerative conditions 251
  poking 331

F

face
  red 62
Facebook xi, 14, 16, 47, 76, 121, 122, 126, 136, 163, 347, 350, 356, 517
facial expression 325
failure to thrive 328
families
  advice to 341
farm animals 490
farmers 490
Farmer's Almanac 325, 477
Fasano, Dr. Alesio 62, 449
fat cells
  releasing toxins from 335
fatigue 75, 89, 176
fats 55
  bad
    destroying 485
fatty acids 246, 311
fatty acids, essential 509
FDA (Food and Drug Administration) 86, 249, 257, 490
  food code 174
fears 136
Federoff, Nina 67, 457
feet 115
Feingold Diet 61
Feingold, Dr. Ben 61
Feingold, Dr. Giuseppina 8
fermentation 55, 121, 458
  digestion 145
  food, of 51
fever 177, 182, 335, 336
  protocol 473
  reducers 335
  temperature 336
  therapy 335
fever therapy 336
fiber 74
fibroids 180
fibromyalgia 69, 169, 179, 340
financial matters 341
Fine, Dr. Kenneth 450, 463
fish 50, 251
fish oil supplements 124
flapping xxii, 1, 6, 179, 236
flatulence 89
flat worm 167
flavorings 49, 55
floor cleaner 343
Floortime Therapy 344
flora 76
flora balance 59
flour 49, 51, 52, 231
flu 114, 452
fluid retention 180, 182
flukes 165
fluoride 142, 256
fluorine 116
flushing 89
flu vaccine 507
  injury 331
focus 249, 250, 333, 444
folic acid 507
folinic acid 509
food
  acids 93
  addiction 71
  additives 61
  allergy 49, 50, 57, 70, 81, 244
  choices 508

  coloring 52, 55, 61, 63, 325
  fast 51
  intolerance 69
  mercury in 507
  nutrient dense 457
  preventative 231
  processed 41, 231
  pyramid 72
  raw 46
  reaction to 70
  supply 255
  to be avoided 133

food bars 460

foot baths. *See* CD, foot baths

Ford, Dr. Rodney 450, 456

foreword vii

forgetfulness 178

formaldehyde 88, 236, 507

fossilized shells 485

fossil shell flour 486, 489

fractures 487

Franklin, Benjamin 279, 280

Frank Oski. *See* Don't Drink Your Milk (book)

frazzled 46

free radical molecules 87

Free Radical Theory of Aging (article) 86, 87

french fries 44, 51

french maritime pine bark extract 250

fructose 231

fruit 41, 43, 50, 51, 53, 55, 60, 61, 73, 76, 127, 139, 459
  beverages 53
  canned 50
  dried 50, 76
  frozen 50
  juice 51, 55, 123, 124, 133, 139, 231, 490
  raw 60

frustration 252

Fry, Dr. Stephen 119

Fry Labs 119

full moon. *See* parasite protocol, full moon

fungus 54, 61, 71, 75, 76, 82, 190, 246

G

Gaba 342

gallbladder 103, 167

GAMA. *See* gamma-aminobutyric acid

gamma-aminobutyric acid 244, 248, 249, 324
  dose 248

gamma-glutamylethylamide. *See* L-theanine

Garbanzo 52

garlic 232

garlic oil 232

gas 51, 75

gastrointestinal distress 505

gastrointestinal (GI)
  ailments 43
  cancer 87
  pain 331
  problems 59
  symptoms 177
  tract 50, 325

GcMAF 32, 125, 141, 293, 295, 321
  AIDS Conference 304
  alpha-N-acetylgalactosaminidase (Nagalase) 298
  Altmetric score 297
  anticancer properties 300
  autism 295, 300, 301, 302, 305, 306, 307, 308, 311
  autism, curing 303
  autism improvement 302
  autism is a curable condition 303
  autism pathogenesis 302
  autism treatment 302
  bacterial 296
  biotech company 317
  blood brain barrier 306
  bone disorders 300
  brain 317
  brain inflammation 308
  breastfeeding 317
  cancer 296
  CFS/ME 305
  conclusions 316
  DNA 304
  energy, increase of 305
  eradication of HIV infection 296
  fermented food product 315

  - first publication on 296
  - food fermented by probiotic bacteria 316
  - fungal 296
  - Gc-protein 298, 300
  - grey matter 307
  - haematological parameters 316
  - history of 296
  - hottest topics in today's world science 297
  - human neurons 304
  - immune system 306
  - immune system development 317
  - immunotherapy 296
  - injections 314
  - licking 317
  - Lupus 300
  - metabolic activity, increase of 306
  - metastatic advanced cancer 296
  - most effective tool to fight diseases considered incurable 316
  - MRI studies 307
  - Nagalase 302
  - natural component of body 317
  - natural nutrient 313
  - neuronal connectivity 305
  - neurons 305
  - neutrophil cell count 316
  - non-responders 303, 310
  - normal brain anatomy after treatment 309
  - personal experience 314
  - protein, is a 304
  - protozoal 296
  - radiation exposure 314
  - saliva 312, 315, 317
  - sublingually taken 314
  - therapeutic effects of 298
  - transcranial ultrasonography 307
  - tumours 299
  - ultrasound 308, 311
  - viral 296
  - vitamin D 300
  - what is? 312
- Gc-protein 298, 313, 315
- Gc-protein-derived Macrophage Activating Factor. *See* GcMAF
- gelatin 52
- gelcaps 226
- Generation Rescue 5
- gene test 463, 464
- genetic material 118
- genetics 453
- Genova Diagnostics 388, 389
- gentian root 231
- germs
  - fear of 333
- gestation 507
- Giardia lamblia 233, 238
- Giera, LuEllen 450
- Gilbere, Dr. Gloria 337
- Gilliam Autism Rating Scale 251
- ginger 226, 233
- gingivitis 86
- Giulivi, Cecilia 120
- glands 256
- glass bottles 160
- gliadin 451, 454
- gliadin antibodies 461
- gliadin blood test 463
- gliadin-IgA 463
- gliadorphin 44, 49, 69
- glial cell dysfunction 311
- glutathione 127, 342
- gluten 4, 43, 44, 49, 53, 54, 56, 58, 64, 66, 67, 69, 70, 73, 75, 245, 449, 451, 454, 455, 464
  - accidental exposure 462
  - antibodies 65, 66
  - ataxia 456
  - challenge 64
  - challenge testing 67
    - risks of 460, 464
  - cheats 460, 462
  - cross reactive foods 465
  - diet 455
  - elimination diet 464
  - gluten-free 454, 456, 458, 459
  - gluten-free diet 4, 41, 45, 47, 48, 57, 58, 70, 74, 453, 457, 513
    - diet 67
    - lifelong commitment 67
    - pretzels 76
  - grains 73, 457
  - infractions (dietary) 460
  - junk food 459
  - molecules 69
  - mortality rates 460
  - peptide sequence 452
  - pieces 453, 458
  - proteins 48

  - reactions 455
  - related tests 464
  - sensitivity 456
  - silent gluten injury 456
  - silent syndrome 456
  - substitutes 465
  - syndrome 65, 66, 67, 449, 452, 454, 458
    - diagnosis 455, 461
    - reaction 65
  - testimonials 459
  - what is 450
  - withdrawals 67, 458

GlutenEase™ 460

gluten-free diet 464

Gluten Free Society 464

gluten reactivity 64

Gluten Syndrome: A Neurological Disease (paper) 456

Gluten Syndrome: Is Wheat Causing You Harm?, The (book) 456

gluteomorphins 44, 49, 56, 58, 69, 75, 245, 458, 461

gluthatione 139

glutinins 461

GMOs 320, 457, 459

gold 116

Golomb, Dr. Beatrice 263, 264

Gottschall, Elaine 58, 61

grain free diet 51

grains 51, 69, 75, 252, 324, 490
  - grain-free 141
  - grain husks 486

Gram, Hans Christian 78

granola bar 56

granulocytes 120

granuloma 338

grapes 61
  - red 61

grass roots movement 444

green juices 133

green tea 123, 134

Group III, Dr. Edward F. 338

growth rate 330

GSE 342

Guillain-Barré Syndrome 272

gums 162, 459

Gunter, Dr. Bernard 264

gut 49, 246, 319
  - clutching 331
  - dysbiosis 115
  - flora 75
  - Gut and Psychology Syndrome (book) 75
  - gut-brain connection 245
  - healing the 260
  - inflammation 44
  - microbes 246
  - mucosa 245
    - improve 245
  - villi 65

Gut Biology and Treatment (presentation) 117

gut villi 454

gut wall 451

H

Hadjivassiliou, Dr. Marios 450

haematological values 316

hair 116
  - brittle 181
  - dry 181
  - dye 61
  - loss 181
  - pulling 331, 332

hair products
  - non-toxic 509

ham 53, 55

hamburger patties 460

handwriting 34
  - poor 333

Harch, Dr. Paul 287

Harman, Denham 86

Hazelnuts 51, 52

HBOT 6, 125

HCl 90, 94, 96, 98, 155, 467, 493

headaches 62, 89, 179, 330, 331, 340, 456, 485
  - migraine 144

head banging 62, 331

healing crisis 84. *See also* Herxheimer reaction

hearing 49

heart 65, 251, 253, 451, 452, 454, 461, 485, 487
  damage 456
  disease 445
  failure 452
  muscle 452
Heart and Circulation Physiology 290
heart burn 89
heartworm medication 240
heavy metals xxiii, 10, 11, 55, 81, 139, 141, 147, 162, 244, 245, 255, 257, 259, 260, 261, 320, 323, 345, 485, 505, 506, 507. *See also* metals
  exposure 301
  load 259
  toxicity xxi, 115
helminths 165, 193. *See also* parasites
hemorrhoids 177
Henry's Law 281, 282, 283
Hepatitis B 1, 265
herbicides 55, 258
herbs 11, 55, 226
heroin 44, 49
Herxheimer reaction 10, 11, 14, 57, 81, 84, 89, 90, 100, 125, 127, 146, 147, 155, 225, 226, 228, 339
HFCS. *See* high fructose corn syrup (HFCS)
hiccups 89
high fructose corn syrup (HFCS) 41, 52, 55, 123, 231
high oxalates 182
hippotherapy 175
histamine 50, 229, 236
histidine 250
HIV 138, 272, 298, 300, 315
  infection 295
hives 70, 337, 338
Hoffman, Dustin (Actor) 276
homeopathy 9
homeostasis 236
homocycsteine 342
homocysteine 253
  metabolism of 253
homogenized 49
honey 52, 63, 232, 233
hookworms 12, 165
hopelessness 443
hormones 295, 312
horsetail 457
hot dogs 50, 53, 55
H. pylori 120
Humble, Jim xiii, 10, 22, 77, 84, 85, 89, 143, 145, 327, 339, 348
  message from Kerri 80
humidifier 225
humidity 225
hunger 177, 178
hyaluronic acid 250
hydrochloric acid. *See* HCl
hydrogen peroxide 84
hydrolyzed vegetable proteins 49
hydrotherapy. *See* colon hydrotherapy
Hynes JD, MBA, Beth C. 505
hyperactivity 46, 54, 55, 62, 70, 103, 251, 324, 337
hyperammonemia 236
hyperbaric chamber 267, 321
  inflatable chamber 279
hyperbaric (oxygen) chamber xxiv, 282, 284, 286, 287, 288
hyperbaric oxygen therapy 6, 280, 287, 290, 291
hyperbarics 6, 11, 43, 141, 263, 267, 321, 324
hyperglycemia 285
hypersensitive individuals 147
hyperthermia 335
hypoglycemia 176
hypothyroidism 328
hypotonia 456
hypotonic 32

I

IBS. *See* irritable bowel syndrome (IBS)
ibuprofen 143
ice cream 49, 54
IgA 59, 451, 454, 455

IgA blood tests 463
IgD 451
IgE 70, 236, 451, 455
  allergic reactions 58, 70
  antibodies 50
IgG 58, 451, 454, 455
IgM 451, 455, 463
IgM reaction 236
immune cells 50
immune complex disease 456
immune dysregulation 505
immune function 256
immune globulin 330
immune gluten reactions 66
immune response 50, 296
  effective 335
  low 182
immune-stimulant 296
immune system 49, 51, 54, 60, 64, 66, 67, 70, 84, 85, 118, 120, 133, 227, 245, 246, 252, 253, 295, 296, 313, 320, 335, 338, 451, 453, 454, 455, 457, 463, 488
  dysfunction 301, 302
  function 54
  problems 508
  response 57, 62
immunodeficiency 298, 314, 315
Immunology of Gluten Sensitivity Beyond the Intestinal Tract, The (editorial) 453
Immunosciences Lab 450
immunotherapy 296, 300
implant, the 220
impotence, male 180
inattentive 333
Infant Body Systems 506
infants 335
infections 85, 120, 145, 162, 169, 182, 335, 451, 452, 453
  bladder 244
  chronic 167, 256
inflammation xxi, xxiii, 10, 49, 50, 53, 54, 56, 58, 60, 81, 84, 120, 128, 132, 134, 179, 236, 247, 256, 314, 323, 331, 338, 451, 485
inflammatory
  disease 460
  mediators 50
  process 453
  response 50
Influenza B (Pentavalente) 1, 265
insecticides 489
insects 61
insomnia 485
insulin 52
  spikes 52
International Probiotics Association 244
interventions 324
intestinal
  damage 62
  dysbiosis 128
  obstruction 177
  peristalsis 236
  peristaltic action 192
  permeability 59
  tract 49, 52, 59, 60, 259
  wall 59
intestinal wall 103
iodine 116
iron 45, 90, 116, 118, 119, 122, 138, 176, 180, 190, 243, 486
irritability 178, 248
irritable bowel syndrome (IBS) 177
irritation 338, 339
Is This Your Child (book) 72
itching 338
  anal 179
  nasal 179, 181
IV chelation 8, 9, 11, 139, 261

J

Jacob, Dr. Stanley 144
Jacobs, Tom 443
jaundice 181
jitteriness 246
jitters 250
Jo, Dr.. *See* Feingold, Dr. Giuseppina
joint lining 461
joint proteins 452

joints 65, 167, 179, 255, 453, 485
  pain 70, 75
journal, keeping a 46
Journal of the American Medical Association 120
juice. *See* fruit juice
juicing 133
Jung, Dr. Shin-siung 253
junk food 41, 67, 459
Just Eat Real Food movement 68
juvenile delinquency 54

K

Kaiser, Olive 64, 319, 449
Kalcker, Dr. Andreas 13, 49, 83, 85, 86, 88, 121, 145, 166, 235, 240, 323, 324, 327, 348, 444, 445
Kalcker Parasite Protocol. *See* parasite protocol
kale 133
Kanner, Leo vii
kefir 232
Keppra (drug) 248
ketogenic diet 51, 323
kidney 82, 487
killer cells 452
kiwi 123, 124, 139
Klinghardt, Dr. Dietrich 256
Knivsberg, Dr. 44
kombucha 123, 134

L

LabCorp 390
labels
  LaMotte Chlorine Dioxide Test Strips 469
  reading 47, 72
  Rompepiedras 191
  sodium chlorite 92
  supplements 124
laboratory testing 12, 345. *See also* tests
Lackney, Charlotte 156, 158, 163
lactation 54
lactobacillus 244
lactose 53
  intolerance 70, 244
  lactose-free 49
  lactose-free milk products 52
LaMotte High Range Chlorine Dioxide Test Strips (#3002) 133, 468
language 46, 49, 248, 250, 253, 330, 332
laughter 229
  inappropriate 62
laundry bleach 83. *See also* chlorine bleach
laundry detergent 343
Lavoisier, Antoine 280
laxative 195
L-carnitine 247, 248, 324
  dose 248
L-carnosine 250, 324
LD50 number 78
lead 255, 257, 506, 508
leaky gut syndrome 44, 48, 49, 59, 61, 62, 67, 73, 177, 337, 451
learning 250
learning disorders 456
lecithin 71
legumes 133
lemon 84, 134
lemon juice (CD activator) 94, 156
lepidium latifolium extract 139, 188, 191, 237, 341
  dosing 191
  Source & Cost 191
lesions 338
lethargy 62, 177, 236
lettuce 460
Leucovorin 330
leukocytes 50
ligaments 488
light
  sensitivity to 333
lime juice 93
lips 338
Lipski, M.S., C.C.N., Elizabeth 73
listening 248

listlessness 89, 121
lithium 116, 342
liver 55, 65, 82, 103, 181, 252, 313, 338, 342, 453, 457, 461, 487, 509
    enzymes 61, 141
    enzyme tests 143
    flukes 165
    function 84
Living Without (magazine) 73
localized diseases 167
Lomper® 193. *See also* mebendazole
lotions 73, 508
low intestinal carbohydrate digestive enzyme activity 60
L-theanine 249
Lubbers, Judith R. 89
lunar cycle 187
lunar phase calendar 477
lungs 50, 138, 338, 451, 487
lupus 300
lutein 61, 71
lycopene 61
Lyme disease 119, 239, 340
lymphatic system 103
lymphocytes 120, 315
Lyne-Sands, Robert. *See* Sands, Bob
lysine 247, 342

M

macromolecules 310
macroparasites 238
macrophages 296, 299, 304, 312, 315
magnesium 45, 116, 118, 119, 143, 190, 226, 324, 342, 486, 487
maintenance plan 319
makeup
    nontoxic 509
malabsorption 60
    problems 60
    syndrome 177
malaria 167, 176
malnourishment 178, 332
malondialdehyde 88, 236
malt 47, 49, 52
maltose 76
manganese 116, 190, 486
mangoes 57, 63, 123, 124, 133, 139
maple syrup 52
margarine 52
marriage 341
Marshall, Barry 119
mast cells 50
maternal detoxification 506
mayonnaise 53, 54
McCaffrey, CDC, Dee 490
McRae, Scott & Brenda McRae 156, 157
MCT 323, 342
meals 188
measurements in
    fluid ounces xiii
    pounds xiii
meats 41, 50, 51, 53, 251, 252, 459
    processed 53, 55, 63
mebendazole 141, 188, 193, 220, 237, 329, 341
    blitz day 194, 208
    dosing 194
    source 194
medications 451
medicinal plants 226, 231
medium chain triglyceride. *See* MCT
megavitamin protocols 9
Meirleir, Prof. Kenny de 301
melatonin 27, 249
memory 247, 250, 333
memory B cells 67, 452, 457
Mendel in the Kitchen (book) 457
menstrual problems 180
mental clarity 250
mercury 55, 139, 141, 245, 255, 257, 261, 457, 506, 507, 508, 509
metabolic end products 70
metabolism 246, 248
    of proper fat 247

metabolites 118
Metagenics Adreset® 342
metals 255, 257. *See* heavy metals
  porphyrins tests 143
  toxicity 5, 118, 255
Metametrix™ Clinical Laboratory 345
methemoglobinemia 143
methionine 247
methoxychlor 508
methylation
  cycle 89, 256, 261
  impaired 505
methyl mercury 255, 257. *See also* mercury
metric system xiii
Michelson, Harold 273, 274
microbes 59, 60, 118, 246
  overgrowth 60
  proliferation 59
  proliferation of the unwanted 60
  proper balance 60
microorganisms 244, 245
microparasites 167
microscope 12, 167, 186, 220
microvilli 43, 60
migraine 456. *See also* headaches
milk 43, 49, 51, 52, 53, 56, 66, 70, 71, 455. *See also* dairy
  cow's 52, 53, 69, 71, 72
  evaporated 53
  goat 49, 53, 69, 72
  human 69
  nut 133
  protein 69, 245
  raw 53
  rice 133
  soy 53
milk thistle 342
millet 51, 486
minerals 116, 122, 132, 257
  absorption 486
  deficiencies 59, 115, 243
  supplementation 143
  synthetic 116
mint 63, 231
miracle 48
Miracle Mineral Solution (MMS) 9. *See also* CD
miscarriages 507
miso 232
mission, Kerri's xxiii
mitochondria 86, 120, 121, 225
  voltage 225
mitochondrial
  defects 120
  dysfunction 120, 121, 505
  membrane 247
    electrical potential 121
  Mitochondrial Encephalopathy Partial Complex III Deficiency 328
  Mitochondrial Theory of Aging (article) 87
MMS xiii, 42, 77, 86. *See also* CD
modified citrus pectin 139
mold 70, 258, 337
molecular mimicry 64, 65, 67, 449, 451, 452, 455
  what is 450
molybdenum 116
monosaccharide molecules 75
monosaccharides 59, 60
monosodium glutamate (MSG) 53, 54
monosugars 76
mood 20, 249, 250, 256
mood swings 178
moon 187
morphine 44, 49, 69, 70, 229, 236, 245
mouthwash 86
MRI 309
MS. *See* multiple sclerosis (MS)
MSG. *See* monosodium glutamate (MSG)
mucopolysaccharides 488
mucosal gut damage 456
mucosal immune system 245
mucous 49, 128, 132, 134, 165, 235, 444
  in stool 177
mucous membrane barrier 245
muffins 49
mugwart 231
multiple sclerosis (MS) 313, 316

multivitamins 132, 342

muscle 250
  cramps 179
  spasms 179

muscle & joint pain 179

muscular abilities 330

music 277

mycobacterium 138

N

NaClO2. *See* sodium chlorite

Nagalase 298, 302. *See also* alpha-N-acetylgalactosaminidase

nails 116
  chewing 227

naltrexone 327, 329

National Health Statistics Reports viii

National Institute of Mental Health (NIMH) 333

National Institute of Neurological Disorders and Stroke (NINDS) 336

National Institutes of Health (NIH) 276, 508

natural flavoring 47, 53, 55

natural pesticide 61

nausea 89, 157, 177

navel, pain in the 179

NCGS. *See* Non-Celiac Gluten Syndrome (NCGS)

NDF+ 342

nebulizer 138

needles 190

neem 188, 195, 237, 341
  dosing 196
  source & cost 197

nematodes 187

nerves 65, 66, 253, 451, 453
  protein sequence 452

nervousness 58, 179

nervous tension 250

netti pot 138

neurodegenerative disorders 301

neurological
  disease 456, 460
  function 251
  health 487
  problems 508

neuronal connections 277

neurons 256, 305, 306

neuropathology 301

neuroprotectant 251

NeuroProtek® 342

neuropsychiatric symptoms 330

NeuroScience
  Avipaxin 342
  EndoTrax 342
  Kavinace 342

neurotoxins 58

neurotransmitters 245, 247, 248, 249, 295

neutrophil cell count 316

newborns 507

New England Journal of Medicine (NEJM) 252

New Jersey Medical School (NJMS) 43

New Jersey Medical School's Autism Center 43

Newman, Dr. Bobby 4

new moon. *See* parasite protocol, new moon

newsletter 47

Newtonian Gas Laws 282

nickel 116, 507

niclosamide 180, 187

nicotine patch 73

nightmares 228

night terrors 228

night wakings 103, 220

nitric oxide 250

nitrogen 283

non-celiac gluten-sensitivity 456

Non-Celiac Gluten Syndrome (NCGS) 461

non-crystalline silica 489

non-responder xxii, 81, 310, 311

non-systemic drug 193

noodle soup 53

nose 50
  bleeds 330

nuclear radiation 67, 457

numbness 182

numbness of the hands or feet 179

nut flour 460

nutrients 59, 60, 295, 299
- absorption 115, 453
  - poor 65
- deficiencies 453
- lost 169

Nutrients (publication) 297, 304, 313

Nutriiveda™ 134

nutrition 295, 506
- deficiency 457
- poor 451
- shakes 53

nutritional tests 143, 388, 389, 390, 391

Nutrition and Physical Degeneration (book) 258

nuts 41, 51, 53, 60, 61, 459, 460

O

oatmeal 53

oats 49, 66, 69, 455, 486

obesity 54, 178, 286, 485, 507, 508

O'Bryan, Dr. Thomas 449

obsession 179

Obsessive Compulsive Disorder (OCD) 20, 103, 140, 180, 227, 333, 334, 352, 444
- decreased 253

occupational therapy 330, 344

OCD. *See* Obsessive Compulsive Disorder (OCD)

ocean 116

ocean water xxii, 26, 115, 116, 122, 129, 132, 141, 143, 188, 189, 238, 244, 260, 282, 320, 341
- care of/handling 131
- charcoal filters 131
- dilution 117
- dosing 117
- parasites 131
- Quinton, Rene 116
- timing of chlorine dioxide dosing 117

oils
- marine 246
- plant 246

oleic acid 311

oleoresin 55

olive oil 311

Omega-3 & Omega-6 Fatty Acids 246, 247
- excessive consumption 247

omegas 320

OMP. *See* outer membrane proteins

OncoImmunology (scientific journal) 297

onions 460

opiate receptor sites 69

opiates 71

opioids 245

opium 71

oral care 85

orange juice 127

oranges 56, 57, 61, 63, 124

oregano 63

organic 53, 123, 509

organic acids 59

organisms, invading 335

organotoxins 508

organs 259, 261

Ortiz, PhD., Lorna B. vii

Osborne, Dr. Peter 450, 464

OSR 342

osteoporosis 247, 485, 487

outer membrane proteins 118

oven cleaner 343

oxalates 131, 139

oxidants 86, 88

oxidants, antioxidants and the current incurability of metastatic cancers (article) 87

oxidation 83, 120, 121

oxidative
- metabolism 286
- stress 88, 120, 236

oxidizer xiii, 78, 84

oxitriptan (5-HTP) 249

oxygen 83, 272, 280, 281, 282, 283, 284, 286, 288

oxygen chamber. *See* hyperbaric chamber

Oxyheal 279

ozone 11, 83

P

P5P 324

pain 129, 249, 331
  back, thighs, or shoulder 179

pancreas 55, 65, 251, 453, 461

pancreatitis 177

PANDAS 64, 127, 140, 328, 333, 334, 347
  probiotics 246

panic attacks 333

PANS 127, 140, 328, 330, 333, 334
  probiotics 246

papain 233

papaya 233
  seeds 233

paprika 234

parabens 508

parasite protocol xxiv, 13, 88, 125, 126, 127, 133, 136, 140, 141, 165, 166, 187, 189, 244, 260, 291, 320, 323, 337, 338, 339, 340, 444, 477
  breakfast 189
  CD 189
  CDS 189
  chanca piedra 191
  chlorine dioxide 187
  components of 187
  daily calendar 198
  diatomaceous earth 190
  dinner 189
  family members 237
  family requirements 238
  full moon 126, 129, 178, 182, 187, 224, 228, 241, 325, 326, 477
  length of treatment 187, 235, 236
  lepidium latifolium extract 191
  lunch 189
  maintenance plan 238
  meals 188
  new moon 187, 237, 325, 326, 477
  not seeing worms 236
  off days 218
  pregnancy 235
  supplies 218
  toilet hat 218
  what to expect 227
  when to stop 235

parasites xxi, xxiii, 11, 12, 20, 46, 49, 52, 81, 88, 103, 105, 111, 115, 128, 129, 140, 147, 162, 165, 167, 169, 174, 181, 183, 190, 244, 261, 320, 323, 324, 331, 337, 345, 444, 445, 458, 485
  abdominal pain or tenderness 177
  african sleeping sickness 176
  allergies 181
  altered immune regulation 167
  ammonia 176
  anal itching 181
  anemia 176, 182
  anger & irritability 178
  animal excrement 169
  animal waste 174
  anorexia 179
  anus, itching, burning, picking 179
  anxiety 178
  appetite, loss of 178
  appetite, ravenous 178
  arthritis 169, 179
  ascaris lumbricoides 183
  asthma 180
  autism 240
  babesiosis 176
  bad breath 182
  bedwetting 181
  bleach 183
  bloating 177
  blood 167
  blood analysis 182
  blood disorders 176
  blood parasites 176
  body odor 182
  bowel movements, excessive 177
  brain 167, 236, 240
  brain fog 178
  breathing problems 182
  bronchitis 180
  burping 178
  CD 238
  chagas 176
  chest pains 179
  chlorine 185
  chronic fatigue 169
  chronic fatigue syndrome 177
  clothing 183

cold, internally 177
cold in the extremities 177
colitis 177
collection 219
confused thinking 178
congenital transmission 169
constipation 177, 179
contaminated raw or undercooked meat 169
contaminated vegetables or fruits 174
contaminated water 174
coordination, lack of 178
cough 180, 182
cramps 177, 179
cravings 177, 178
cysts 179, 180
definition of 237
depression 178
dermatitis 181
desiccation 185
detox organs 176
deworming of our animals 174
diarrhea 177, 179
disorientation 178
distended belly 177
dizziness 176, 177
doctors in Western Europe and the U.S. 169
drooling (while sleeping) 181
drowsiness 180
dyspnea 180
eczema 181
eggs 131, 169, 174, 183, 184, 185, 227, 338
elevated immunoglobulin (IgE) 182
energy, low 177
enterobius vermicularis 185
eosinofils, elevated 182
erectile dysfunction 180
eruptions 181
essential nutrients 176
everything you wanted to know about sorting through poop 218
evolutionary cycle 183
eyes 167
    swollen 182
farm soil 174
fatigue 176
fecal contact 169
fertilizer 174
fever 177, 182
fibroids 180
fibromyalgia 169, 179
fish, raw 169
fluid retention 180, 182
forgetfulness 178
formaldehyde 185
freezing 174
freezing meat or fish 169
fruits & vegetables 183
gastrointestinal symptoms 177
glucosoid mucous 237
good for us? 237
growth retardation 179
hair
    brittle 181
    dry 181
    loss 181
headaches 179
hemorrhoids 177
high ammonia 182
high oxalates 182
hippotherapy 175
host immune response 167
hunger 177, 178
hypoglycemia 176
immune response, low 182
impotence, male 180
infections 182
inflammation 179
insomnia 181
intestinal
    skin problems 338
intestinal irritation 177
intestinal obstruction 177
iron 176
irritability 179
irritable bowel syndrome (IBS) 177
itching, nasal 179, 181
jars of 230
jaundice 181
joints 179
lab tests 241
large numbers in BM 239
larvae 169, 174, 184
leaky gut 177
lethargy 177
liver 167
location of 238
lunar cycle timing 187
lung 167
magnitude of problem 445
malabsorption syndrome 177
malaria 176
manure 174
mating 325
menstrual problems 180

  mood swings 178
  muscle 167
  muscle cramps 179
  muscle & joint pain 179
  muscle spasms 179
  nausea 177
  navel, pain in the 179
  nervousness 179
  niclosamide 180
  not visible 237
  numbness 182
  numbness of the hands or feet 179
  obesity 178
  obsession 179
  organic farming 174
  outer coating 191
  pancreatitis 177
  perforations made by 169
  peritonitis 182
  pets 175, 183, 240
  photos 165, 168, 170, 171, 174, 175, 230
  pinworms 185
  pneumonia 180
  poor absorption of food 177
  poor growth 178
  poor hygiene habits 169
  poor physical and intellectual development 178
  premenstrual syndrome 180
  prostate problems 180
  psoriasis 181
  psychoactive substances 176
  rapid heartbeat 179
  reflexes, slow 179
  respiratory disease 180
  restless leg syndrome 179
  restlessness 179
  saliva, excess of 182
  seizures 179
  self-infection 169
  sexual contact 169
  sexual & reproductive disorders 180
  shortness of breath 180
  skin 167
    crawling sensation under 181
    dry 181
    itchy 181
    ulcers 181
  sleep
    disorders 181
    restless 177, 181
  smearing feces 180
  soaps 183, 185
  soil contamination 169
  sores 181
  stomach 167
    burning in 177
  stool
    blood in 177
    detection in 218
    mucus in 177
  sugar 176
  swallowing, difficulty 182
  sweets, cravings for 178
  swelling 181
  symptons 175
  taenia saginata 185
  taenia solium 185
  tapeworm 180, 185, 187
  teeth grinding 181
  telling children about 239
  temperatures 185
  test for 235
  toxic waste produced by 176
  toxins 179, 229
  unexplained laughter or weeping 180
  urinary tract infections 180
  urticaria 181
  veterinarian 241
  vision, blurred 182
  vitamin B12 176
  vitamin B12, low 182
  vomiting 177
  waking at night 177
  wash produce, best way to 239
  weakness 176
  weakness, extreme 177
  weight gain 178
  weight gain during full moon 182
  weight, inability to gain or lose 178, 179
  weight loss 178, 180
  yeast infection 180
parasitic infection 167
  supplementing deficiencies 243
parasitological vaccinosis 240
Parkinson's disease 120, 251, 300
parsley 486
parts per million 148, 467
pasta 53, 71
pasteurization 49, 232
pastries 49
Pathogen Biocide. *See* chlorine dioxide

pathogenesis 301
pathogenic overload 331
pathogens xxi, 11, 82, 85, 89, 103, 115, 120, 128, 147, 245, 257, 260, 261, 323, 334, 335, 337, 444
  dying 127
Patrick. *See* Rivera, Patrick
Pauling, Linus 87
PCBs 508
PDD. *See* Pervasive Developmental Disorder (PDD)
PDD-NOS 347
peanuts 52, 61, 63, 66, 451, 455
Pediatric Acute-onset Neuropsychiatric Syndrome. *See* PANS
Pediatric Autoimmune Neuropsychiatric Disorder Associated with Streptococcal Infections. *See* PANDAS
pediatricians 445
Pediatric Infection Triggered Autoimmune Neuropsychiatric Disorders. *See* PITAND
peer-reviewed journals 68
peetox 227
Pentavalente (Spanish). *See* DPT (diphtheria-pertussis-tetanus)
pepper 234
peppers 61
pepperwort. *See* lepidium latifolium extract
peptides 44, 48, 49, 56, 69, 245, 451
peptidurea 70
perchlorates 506
peripheral neuropathy 456
peritoneum 338
peritonitis 182
permitted foods list 50
Pervasive Developmental Disorder (PDD) 44, 69
Peskin, Dr. Brian 247
pessimists 443
pesticides 55, 174, 258, 485, 506, 508
pets 85, 183, 186, 353
pH 82, 282
phagocytosis 118
pharmaceuticals 506
phenols 61
phenol-sulfotransferase-P 62
phobias 136
phosphoric acid 285
phosphorus 116, 487
photosynthesis 281
phthalates 508
Physically or Otherwise Health Impaired (POHI) 328
physical therapy 330
phytoplankton 485
PIC Indolor Gravity Bag 108
piloncillo 52
pinching 331, 332
pineapple 123, 124, 133
  juice 22, 127
pinworms 12, 165, 185, 194, 220
  eggs 186
piperazine 192, 232
Pissed-Off Worm Syndrome (POWS) 228
PITAND 333, 334
pizza 49, 460
placental 451
plants, medicinal 226, 231
plasticizers 506
plasticizing agents 508
plastics 508
plateau 85
platelets 251
Play-Doh™ 53, 73, 75
PMS. *See* premensrual syndrome
pneumonia 180
pollutants 507
pollution 487
polychlorinated biphenols (PCBs) 508
polysaccharides 59, 118
polyunsaturated fatty acids 246
pomegranate bark 234

pomegranate root bark 231
pool 142
pool chlorine 83
popcorn 74
  air-popped 76
  microwave 53
Popp, Ph.D., Fritz Albert 444
pork 50, 325
post traumatic stress disorder 341
potassium 116
potatoes 4, 51, 459
poultry 55
powers of hydrogen. *See* pH
POWS. *See* Pissed-Off Worm Syndrome (POWS)
PP. *See* Kalcker Parasite Protocol
ppm 467
prebiotic 244
pregnancy 54, 235, 490, 508, 509
premenstrual syndrome 180, 247
prescription medication 42
  removing a 333
preservatives 41, 53, 54
preterm births 509
Price, Dr. Weston A. 258
Priestly, Joseph 279, 280, 281
primrose oil 342
probiotics 45, 58, 140, 188, 197, 226, 244, 245, 248, 342, 459
  PANDAS/PANS 246
  when to give 246
produce
  wash, best way to 239
Prompts for Restructuring Oral Muscular Phonetic Targets (PROMPT) 344
propolis 233, 234
prostate problems 180
protein 48, 49, 50, 70, 245, 251, 451
  digestion 48
  hydrolysate 55
proteins
  beads 450
  what are 450
Protocol 1000 157
psoriasis 181, 337
PST. *See* phenol-sulfotransferase-P
psychoactive substances 176
psychological distress 245
psychological problems 508
psychotic behaviors 58
pudding 460
pulmonary disease 313
pulmonary fibrosis 443
pumpkin seeds 192, 193, 232
punicine 234
purgative 233
pustules 337
Pycnogenol® 250, 324
  dose 250
pyrantel pamoate 141, 188, 192, 193, 237, 341, 445
  dosing 192
  source 193

Q

quercitin 342
Quest Diagnostics 391
quinoa 51
Quinton, Rene 116

R

radiation 67
rage 180
Rain Man (movie) 276
Raising Your Child Without Milk (book) 72
raisins 63
rapid heartbeat 179
Rapid Prompting Method (RPM) 344
Rapp, Dr. Doris 72
rash 46, 337, 338
RAST test 69
rats 78
reactions 46
reading 247
recipes 61

recovery xxii, 12
rectal suppository 257
rectal wall 338
redness 337
Red No. 2 55
Red No. 40 55
reflexes, slow 179
Reichelt, Dr. Kalle 69
relaxation 250
remineralization 115, 487
reproductive problems 508
respiratory disease 180
respiratory problems 508
restless leg syndrome (RLS) 179
restlessness 179
retardation
  growth 236
retina 251
retroviruses 301
rheumatoid arthritis 443
rice 51, 66, 459
Ricinus communis. *See* castor oil
ricinus oil. *See* castor oil
rickets, prevent 313
rigidity 330
Rimland, Dr. Bernard xvii, 6, 253, 264, 265, 266, 267, 276, 278, 279, 281, 289, 334
  funeral 265
  song in memory of 266
Risperdol® 42
Ritalin® 42
Rivera, Patrick xv, xx, xxi, xxiii, 1, 3, 4, 5, 6, 8, 10, 11, 13, 15, 17, 44, 81, 82, 146, 257, 264, 265, 269, 272, 341, 347
RLS. *See* restless leg syndrome (RLS)
Road to Immunity: How to Survive and Thrive in a Toxic World, The (book) 335
rocking xxii
Rompepiedras. *See* lepidium latifolium extract
root 55
root canal 452
rope parasites 165
rope worm 165, 170, 173. *See also* rope parasites
Rosedale diet 51
rotavirus 244
roundworm. *See* Ascaris lumbricoides (roundworm)
rubbing 331
rue 226, 231
Ruggiero, MD, PhD., Marco 293, 467
runny nose 89, 114, 138
rye 49, 66, 69, 455

S

Sabin, Nellie 335
S-adenosylmethionine 143
salicylate intolerance 61, 62
salicylates 61, 62
salinity 118
saliva 317, 461
saliva tests 454
salivation, excessive 182
salt 78, 83, 116
  table 86, 116
salt baths 226, 229
salt water 116
SAMe 143
sand 486
Sands, Bob xvi, 6, 263
  hospital 269
  polio 269
Sand's Hyperbaric Chamber 7
sandwiches 460
Sara's Diet 71
sarcoidosis 313
sauce 460
sauerkraut 197, 232, 459
sausages 53, 55
SCD. *See* Specific Carbohydrate Diet (SCD)
schizophrenia 44, 69, 120
school 74, 105, 126, 135, 302

Schultz, Henke 248

Schweppes, Joseph 281

Schweppes™ Bottles 160

scratching 331

screaming 332, 333, 341

scripting 125

seafood 55, 253

Sears, Dr. Robert 336

seasonal allergies 137, 330

sea water. *See* ocean water

seaweed 197

sedimentary clay 257

seeds 60

seizures 45, 58, 120, 179, 236, 240, 248, 251, 252, 253, 323, 324, 325, 326, 328, 330, 336
  febrile 336
  full moon 324
  grand mal 324, 325, 326
  new moon 324
  parasite protocol 324
  parasitic infections 325
  petit mal 324

selenium 87, 116

Self-Injurious Behavior (article) 331

self-injurious behavior (SIBs) xxii, 62, 144, 325, 331, 332
  probiotics 246

semolina 49

sensory/cognitive awareness 248

Sensory Integration Disorder 328

Sensory Integration Therapy 344

sensory overload 31

sensory table 73

separation anxiety 228

serotonin 249
  pathways 249

sesame 66, 455

Severely Multiply Impaired 328

sexual behavior 249

sexual & reproductive disorders 180

shakes 53

shampoo 73

sheep 49, 72

shellfish 50

Shi and Xie 79

shortness of breath 180

shot glass 96, 98, 105, 110, 493

shower 114

SIBs. *See* self-injurious behavior (SIBs)

side effects 11, 82

silenced nerves phenomenon 450

silent gluten injury 456

silica 457, 485, 486, 490

silicon 116, 486

silicon dioxide 486

silver 116

Singer, Emily 248

Siri and Lyons 43

skepticism 68

skin 50, 73, 85, 116, 330, 451, 488, 508
  allergies 244
  care 162
  crawling sensation under 181
  dry 181
  itchy 181
  problems 70
  test 70
  ulcers 181
  wrinkling of 485

skin issues 337
  chronic 338

slapping head/ears 331

sleep 31, 42, 62, 147, 247, 249, 330
  changes 89
  deprived 46
  patterns 46
  problems 70, 248
  restless 177

sleepiness 248, 324

sleepytox 227

small intestine 43, 59, 60, 61

smearing feces 180

smile 229

Smith, Dr. Leonard 251

smog 508

smoothies 490

sneezing 137
soaps 183, 508
sociability 248
social interactions 247
socialization 250
socializing
  problems with 458
soda 53, 285
sodium 83, 116, 486
sodium bentonite 258
sodium chlorite 78, 84, 90, 92, 105, 123, 146, 155, 157, 467
  buying 94
  powder or flakes 92
  solution 96
  technical grade (salts) 92
sodium hypochlorite 83
sodium nitrite 55
soft chambers 279
solvents 55
Solving the Puzzle of Your Hard to Raise Child (book) 72
Son-Rise® 344
sores 181, 338
sorghum 51
sound
  sensitivity to 333
sour cream 72
sourdough bread 67, 458
southernwood 231
soy 43, 49, 52, 53, 54, 56, 66, 69, 70, 74, 76, 319, 455
  cheese 72
  milk 53
  oil 71
  sauce 49, 53
  soybeans 71
  soy-free 41, 48, 57, 58
soy sauce 232, 460
spaghetti 459
Specific Carbohydrate Diet (SCD) 58, 59, 60, 324
speech xxii, 1, 45, 46, 141, 248, 250, 251, 252
  therapist 30
  therapy 24, 330
spelling 247
spelt 49
spices 55, 226
spinach 70, 253
spinal fluid 309
spinning xxii
spirochete 144
spitting 227, 326
spleen 487
sports drinks 53
squealing xxii, 1, 6
stairway to recovery xxiv
stamina 330
starch 49, 76
starch molecules 76
statistics, autism viii, xxv
steambath 21, 114, 138
steroid injections 114
stevia 51, 126, 155, 162, 225
  KAL® 51, 126
  SweetLeaf® 51, 117, 126
stimming 125
stimmy 46
stomach 51, 59, 338
  burning in 177
  problems 70
  ulcers 119
stone breaker. *See* parasite protocol, chanca piedra
stool
  analysis 12
  blood in 177
  loose 141, 332
  mucous in 177
  sample 12, 241
  tests 243, 463, 465
strawberries 63
strength 330
strep 334
strep throat 64
streptococcal infection 333
stress 248, 249
  reduce 250
stressed 46
stroke 251
sublingual methyl B-12 509
sucralose 55, 56

sucrose 231

sugar 41, 47, 50, 51, 52, 53, 54, 74, 78, 119, 133, 176, 231, 285, 459
  cane 52
  cravings for 178
  natural 51
  refined 55

Suicide by Sugar (book) 54

sulfotransferase enzyme 62

sulfur 116, 144

sulphates 61

sunflower seeds 486

sunlight 84

supersaturate 282

supplement list 45

supplements xxiv, 4, 11, 21, 45, 58, 87, 118, 138, 139, 243, 260, 320, 324, 341
  focus on excesses 90

support beyond this book 521

Supportive Typing 344

support system 47

suppositories 129

swallowing, difficulty 182

Swedo, Dr. Susan 333, 334

sweeteners 52, 55

sweetflag 231

SweetLeaf® stevia. *See* stevia

sweets 54
  cravings for 178

swelling 70, 181, 338

swelling clay. *See* bentonite clay

swimming 142

syringe/catheter method 111

systemic immune system 245

T

taenia saginata 185

taenia solium 185

tangerines 63

tansy 231

tantrums 42, 46, 57, 103, 249, 325, 332, 341

tapeworms 12, 165, 167, 180, 185, 234
  eggs 185

tapioca 51, 459

tarragon 234

taurine 251, 324

t-cells 256

tea 249. *See also* green tea

teenagers 140

teeth 86, 162, 473
  amalgams 509
  grinding 179, 181, 325
  mercury 509
  root canal 452

temperature 249

temperature, body
  common fever 336
  high fever 336
  low-grade fever 336
  normal temperature 336

temporal cortex 308

tendons 488

teriyaki sauce 49

testimonials 19, 42, 357
  curezone.com 339

tests
  antibody 456, 460
  blood 454, 464, 465
  celiac antibody 457
  false negative 65, 454, 462, 463
  gene 464, 465
  gluten
    good 462
  laboratory testing 345
  parasites 345
  saliva 454, 465
  stool 465

TheaNAQ 342

therabiotic 342

THERALAC® 188, 197, 244, 245, 341
  dosing 197
  dosing time 254
  source & cost 197

thermometer 109

thimerosal 255, 261, 507
  vaccination 267

Thinking Moms' Revolution, The 327

Thom, MD, PhD, Stephen 290

throat 50

thyme 234

thyroid 65, 256, 453, 461
  disease 313
  function 509
  nodules 314

tics 227, 333, 334

tin 255

tinnitus 485

tiredness 62. *See also* sleep

tissues 261

titanium 190, 486

TMG. *See* trimethylglycine (TMG)

toast 459

tobacco smoke 508

toe walking 274

toilet odors 343

tomatoes 61, 63, 325

tongue sores/lesions 330

toothbrush 142

toothpaste 61, 73, 84, 86, 142, 257, 508

tortillas
  flour 49, 52

toxic by-products 60

toxicity 451, 456

Toxicological Profile for Chlorine Dioxide and Chlorite (report) 78

toxic substances, exposures to 508

toxin levels 457

toxins 11, 50, 55, 59, 88, 89, 103, 115, 143, 259, 320, 337, 453, 485, 505
  environmental 445, 507
  oxidize 103

trace minerals 258, 486

transdermal applications of medications 73, 508

transglutaminase 454

TravaCor Jr. 342

Treatment and Education of Autistic and Related Communication Handicapped Children (TEACCH) 344

tremors 236

Trichinella spiralis 240

trichloroethylene 507

triclosan 508

trilombrin. *See* pyrantel pamoate

trimethylglycine (TMG) 253
  dosing 253

tryptophan 249

tTG 66, 454, 461, 463

tTG-IgA 454, 463

tumors 338

tuna fish 72

turkey 50

turmeric 234

TV watching 343, 344

U

UC Davis 120

UCLA 323

ulcerative colitis 59

ulcers 120, 338

ultrasound 308
  anatomical alterations, observed 309
  autism, treatment of 309
  autistic subject appearance 309
  drugs, transport of 311
  meninges 308
  mental states, effect on 312
  safety 308

undigested carbohydrates 60

units of measure xiii

University of California Davis Health System 43

University of Pennsylvania School of Medicine 290

updates and corrections to this book xxvii

urinary tract infections (UTI) 180
  treating 473

urination
  frequent or bedwetting 333

urine 257, 487
  analysis 243, 259
  sample 44, 69

urticaria 181

US Department of Health & Human Services viii, xxv, 78

US Food and Drug Administration 174

Usman, Dr. Anju 11, 117, 245, 256, 444, 505
uterus 338
UTI. *See* urinary tract infections (UTI)
UV exposure 118
UV light 160

V

vaccines 1, 4, 45, 255, 261, 265, 506, 507
    induced crash 45
    injury 327
    MMR 64
vaginal douche 474
vanadium 116
vegan 513
vegetables 41, 43, 51, 55, 60, 61, 133, 459
    fermented 197, 459
    juice 55
    leafy green 486
    raw 76
Venezuela Autism Clinic 142
venom 66
verbal
    communication 248
    stims 180
verminosis. *See* parasites
Vermox®. *See* mebendazole
vertigo 485
veterinarians 12, 174, 175, 186, 241
villi 65, 453
    biopsy 67, 455, 461
    damage 65, 460
Vimalaramsi, Bhante 156
vinclozolin 508
vinegar 49, 78, 343
vinyl chloride 507
viral load 84
viruses xxi, xxiii, 10, 11, 49, 81, 82, 118, 162, 244, 258, 261, 323, 345, 485, 488, 507
vision, blurred 182
vitality 116
vitamin A 87, 122, 123, 127, 133, 138, 509
vitamin B 252, 457
vitamin B6 342
vitamin B12 45, 46, 90, 122, 176, 180, 236, 243, 507
    low 182
vitamin B12 shots 342
vitamin C 87, 122, 123, 124, 127, 138, 139, 143
    water filter for shower 123
vitamin D 133, 236, 300, 304, 310, 312, 313, 487, 509
    aggression 133
vitamin deficiencies 59, 236, 243
vitamin E 87, 122, 123, 124, 127, 133, 138, 342
vitamin K 122, 123, 127, 133, 138
vitamins 74
Vojdani, Dr. Aristo 66, 449, 450, 453, 454, 455, 461, 463
volcanic ash 257
Volinsky, Dr. Alex 165, 172
vomiting 11, 43, 89, 177

W

waking at night 177
walnuts 51
walnut shell 231
Walter Reed Army Institute of Research 235
Waring, Dr. Rosemary 62
Warren, Dr. Robin 119
waste products 59
water 51, 105, 124, 133, 160, 340, 487, 506
    filter 123
        Brita® type 131
    purification 86
    reverse osmosis or distilled 96
watermelon 460
water purification drops. *See* CD
Watson, Dr. James 87
weakness 176
    extreme 177
weekend protocol. *See* 72/2 protocol

weight
  gain/lose 75, 116, 134
  inability to gain 179
  inability to gain or lose 178
  loss 228
wheat 4, 43, 49, 55, 66, 67, 69, 71, 74, 319, 455, 457, 486
  bagels 67, 457
  berries 67
  proteins 70
wheat berries 458
whey 47, 72, 134
whimpering 229
Whitcomb, Joy xxiv
white blood cells 225, 451
white fraxinella 231
white heads 337
Whitney, Norah 4
WHO. *See* World Health Organization (WHO)
whole foods 41
Wina, Dr. Peter 235
window cleaner 78
wine 78, 253
withdrawal reaction 71
Wobenzyime® 342
Woeller, Dr. Kurt 5, 6
World Health Organization (WHO) 167, 183, 244, 508
worms 26, 88, 165, 190. *See also* parasites
wormwood 226, 231

X

xanthan gum 51
xanthophylls 61
xenobiotics 506
xylitol 52

Y

Yamamoto, Dr. Nobuto 296, 298, 299, 300, 304
yarrow 226, 231
Yasko Protocol 9
yeast 20, 47, 53, 54, 55, 59, 61, 66, 75, 76, 81, 162, 190, 258, 337, 345, 455
  edible 55
  infection 180
yogurt 49
Young, Dr. Vincent 246
Yu, Dr. Simon 443

Z

zeaxanthin 61
zeolite clay 140
zinc 75, 116, 259, 509
zirconium 486
Zone, Dr. John 73
zonulin 49
Zukin, Jane. *See* Raising Your Child Without Milk (book)

About the Author

Kerri Rivera is a native of Chicago, but has lived the last 19 years of her life in Puerto Vallarta, Mexico with her husband. Both of her sons were born there, and 13-year-old Patrick is currently in autism recovery. Kerri is the founder of AutismO2, a non-profit autism clinic based on what is formerly known as the *Defeat Autism Now!* approach. Located in Puerto Vallarta, the clinic opened in 2006. Kerri is the clinic's biomedical consultant as well as a consultant for Curando El Autismo (Latin America), and Venciendo el Autismo (Venezuela).

At the request of Dr. Bernard Rimland, she was responsible for translating the *Defeat Autism Now!* protocol to Spanish and donating it to the Autism Research Institute, so it could be applied throughout Latin America. Since then she has helped over 3,500 families in over 58 countries to improve the lives of their children on the autism spectrum. She has become the foremost expert on the use of CD (chlorine dioxide) for spectrum disorders. Since the addition of CD to the biomedical protocol she has seen 115 children recover from autism in the past 2.5 years.

Since 2007 Kerri has lectured internationally on the Biomedical Protocol for autism and CD for autism. She has been featured on *One Radio Network* with Patrick Timpone, *The Bulletproof Executive* with Dave Asprey, *The Mother Cub Show*, *Thought for Food*, *Enlightened Health Radio* with Justin Elledge, *Voice America*, and *The Robert Scott Bell Show.* She is the Mexican Liaison for AutismOne. Kerri graduated as a Certified Homeopath in June of 2013.

Our greatest weakness lies in giving up.

The most certain way to succeed is always to try just one more time.

~ *Thomas Edison*

The world of autism is rocking again. Kerri Rivera has done it. In this comprehensive book she has condensed and simplified the core elements of the biomedical approach, those that work 90% of the time on 90% of the children. Her focus on using a unified and affordable approach to reduce the body burden of chronic infections and infestations is addressing the very core issue of most autistic children and adults.
It has made her method the most powerful tool to this day to help many children recover safely, inexpensively and solidly. Her research is validated by the enormously positive response from parents from all over the world.

—Dietrich Klinghardt MD, Ph.D.

EXCITING UPDATES TO THIS EDITION INCLUDE:
A new method of CD preparation • New parasite protocol charts
Lunar calendar • Many new testimonials
A section on gluten's role in molecular mimicry and autoimmunity
Information on helping older or violent / aggressive children

In the seven months since the release of the first edition of *Healing the Symptoms Known as Autism*, 22 more children have lost their autism diagnosis and returned to a state of health, for a total of 115 recovered children and counting. Hundreds more have lost ATEC points, as well as shown many cognitive, behavioral, emotional and physical gains thanks to the protocol outlined in these pages. This edition includes all protocol updates and a whole lot more information that can benefit families of children and adults on the spectrum.

In 3 years, 115 children previously diagnosed with regressive autism were able to shed their diagnosis, their symptoms and return to an overall state of health and vitality. If you have any interest in finding out how they were able to heal you need to read this book. Kerri has a heart for children with autism, and she cares greatly about recommending safe, economical interventions that are helping to confront an epidemic.

—Teri Arranga
Executive Director of AutismOne (www.autismone.org)

With over 180 TESTIMONIALS from around the world!

ISBN 978-0-9892890-2-3
52499>
9 780989 289023

NEW RESEARCH FINDINGS show that all diseases have simple explanations and cures once their true cause is known. This book describes the causes of both common and extraordinary diseases and gives specific instructions for their cure.

The Cure for all Diseases

With Many Case Histories

of diabetes, high blood pressure, seizures, chronic fatigue syndrome, migraines, Alzheimer's, Parkinson's, multiple sclerosis, and others showing that all of these can be simply investigated and cured.

Hulda Regehr Clark, Ph.D.,N.D.

Electricity can now be used to kill bacteria, viruses and parasites in minutes, not days or weeks as antibiotics require.

If you have been suffering from a chronic infection or have cancer, or AIDS, learn to build the electronic device that will stop it immediately. It is safe and without side effects and does not interfere with any treatment you are now on.

The Cure For All Diseases

© Copyright 1995 by Hulda Regehr Clark, Ph.D., N.D.
All rights reserved.

Permission is hereby granted to make copies of any part of this document for non-commercial purposes provided this page with the original copyright notice is included.

Published in the United States by New Century Press
1055 Bay Blvd., Suite C, Chula Vista, CA 91911
(619) 476-7400, (800) 519-2465
www.newcenturypress.com
ISBN 1-890035-01-7

Other books by Dr. Clark available from New Century Press:
The Cure For All Cancers
Heilverfahren Aller Krebsarten (Cure For Cancers, German)
The Cure for All Cancers (Japanese Translation)
The Cure For All Cancers (Korean Translation)
Heilung ist möglich (Cure For All Diseases, German)
The Cure For HIV And AIDS
The Cure For All Advanced Cancers

30 29 28 27 26 25 24 23 22 21

Notice to the Reader:

The opinions and conclusions expressed in this book are mine, and unless expressed otherwise, mine alone. The opinions expressed herein are based on my scientific research and on specific case studies involving my patients. Be advised that every person is unique and may respond differently to the treatments described in this book. On occasion we have provided dosage recommendations where appropriate. Again, remember that we are all different and any new treatment should be applied in a cautious, common sense fashion.

The treatments outlined herein are not intended to be a replacement or substitute for other forms of conventional medical treatment. Please feel free to consult with your physician or other health care provider.

I have indicated throughout this book the existence of pollutants in food and other products. These pollutants were identified using a testing device of my invention known as the Syncrometer.™ Complete instructions for building and using this device are contained in this book. Therefore anyone can repeat the tests described and verify the data.

The Syncrometer is more accurate and versatile than the best existing testing methods. A method for determining the degree of precision is also presented. However at this point it only yields positive or negative results, it does not quantify. The chance of a false positive or a false negative is about 5%, which can be lessened by test repetition.

It is in the public interest to know when a single bottle of a single product tests positive to a serious pollutant. If one does, the safest course is to avoid all bottles of that product entirely, which is what I repeatedly advise. These recommendations should be interpreted as an intent to warn and protect the public, not to provide a statistically significant analysis. It is my fervent hope that manufacturers use the new electronic techniques in this book to make purer products than they ever have before.

Dedication

I would like to dedicate this book to all the persons who visited me professionally, from the very first person in 1963, **Mrs. R. Biehl**, to the present. I learned so much from each of you and I appreciate your confidence, your intelligence and your reluctance to be defeated.

Acknowledgments

I would like to express my gratitude to my son, **Geoffrey**, who always listened to my “crazy ideas” on Sundays, right at supper time. He was patient, kind, helpful and willing to share his expertise in electronics and computers. Without him, this book could not have been written.

A big thank you goes to **Frank Jerome, DDS**. Without the loan of his parasite slide collection many of my discoveries could not have been make, and without his development of metal-free dentistry, many of these patient histories could not have ended happily. Thank you to **Linda Jerome** for nurturing us both with personal interest and patience. And thank you to **Edna Bernstein** for her resourceful assistance.

Contents

FIGURES XIII

PREFACE XVII

THE PROMISE 1
Only Two Health Problems 2
Be A Health Detective 3

THE DISCOVERY 5
Everything Has A Unique Frequency 8
Selective Electrocution 9
Bioradiation 12
Zapping Bugs 13
The Bioradiation Spectrum 16

BUILDING A ZAPPER 19
Killing The Surviving Pathogens 20
Zapper Parts List 21
Assembling The Zapper 23
Using The Zapper 28
Simple Pulser 28
Using The Simple Pulser 30

PARASITES & POLLUTION 31
The Worst Parasite 33
Pollution 36
Solvent Pollution 36
Metal Pollution 37
Mycotoxins 38
Physical Toxins 38
Chemical Toxins 40

HOW WE REALLY GET SICK.. 43
Self Health 46
How To Heal 47
The Road To Wellness... 49

PAIN FROM TOE TO HEAD 51
Searching For Bacteria 53
What You Will Find.. 54
Toe Pain.. 55
Balance Your pH 57
Foot Pain... 59
Heel Pain 61
Leg Pain In Children 69
Leg Pain In Adults.. 70
Leg Pain Protocol 73
Fibromyositis and Fibromyalgia 75
Joint Pain or Arthritis.. 78
Osteo or Common Arthritis 79
Rheumatoid Arthritis 82
Allergic Arthritis... 84
Thigh Pain... 86
Hip Pain.. 87
Bone Strengthening... 87
Groin Pain... 89
Low Back Pain... 92
Lower Abdominal Pain... 97
Stomach Pain... 98
Appendicitis.. 100
Urinary Tract Pain.. 101
Irritable Bowel Syndrome(IBS), Colitis, and Spastic Colon 102
Crohn's Disease 103
Central Abdominal Pain.. 108
Interstitial Cystitis.. 108
Uterine Pain 109
Endometriosis 109

- Contraception 112
- The Silent Cervix 112
- Menopausal Symptoms, Hot Flushes, PMS 113

Infertility 117

- Nausea 121

Prostate Problems 124

Side Pain 128

Midabdomen Pain, Stomach Pain 131

Stomach Ulcer 132

Hiatal Hernia 133

Respiratory Illness 134

- Asthma 134
- Bronchitis, Croup, Chronic Cough 140

Breast Pain 142

Breast Sensitivity 143

- Breast Lumps 144

Heart Pain 146

- Slow Pulse/Syncope (Passing Out) 149

Chest Pain 149

Upper Back Pain 150

Shoulder Pain 151

Upper Arm Pain 153

Elbow Pain 154

Wrist Pain 154

Thumb Pain and Hand Pain 155

Finger Pain 155

Back Of Neck Pain 156

Front Neck Pain 156

Temporal Mandibular Joint (TMJ) Problems 157

Tooth Ache 158

Throat Pain 159

Eye Pain 160

- Macular Degeneration 162

Headache and Migraines 162

Earache 168

Ear Noises And Ringing 169

Scalp Pain 171

NON-PAINFUL DISEASES 173

Diabetes 173
  Prediabetic 178
  Diabetes Of Childhood 178
Herpes 179
Fatigue 182
Skin Problems 188
  Sebaceous Cysts 188
  Skin Rash 189
  Hives 191
  Acne 192
  Psoriasis, Eczema 192
Warts 195
Tapeworm Stages 197
The Flu 201
Fever 203
Multiple Sclerosis & Amyotropic Lateral Sclerosis 204
High Blood Pressure 210
Glaucoma 213
Tooth Decay 214
Muscle Diseases 218
  Muscular Dystrophy 219
  Myasthenia Gravis 221
Universal Allergies 222
  Environmental Illness 223
Alcoholism 227
Seizures 230
Weight Problems 237
Sleep Problems 241
  Sleep Apnea 241
  Insomnia 243
Yeast Infections 246
  Diaper Rash 246
  Treat Yeast or Fungus the Same 247
Fluke Disease 249

Flukes and Solvents 251
Flukes Not Alone 252
Burning And Numbness 253
Depression 256
Manic Depression 257
Schizophrenia 261
Autism 263
Digestion Problems 266
Alzheimer's 269
Dementias, Memory Loss 272

PUSHING BACK AGE 275
Diet 275
Increase Oxygen 278
Niacin 279
TIA’s, Strokes and Purpura 281
Blood Pressure 281
Air Pollution 282
Anemia 285
Acid Levels 287
Increase Minerals 287
Chelation 289
Pulse 289
Heart Health 290
Incontinence 293
Bad Digestion 295
Chewing 295
Stomach Acid 296
Salmonella and Shigella 297
Other Clues 299
Liver Bile 299
Constipation 301
Poop Your Troubles Away 301
Sugar Regulation 302
Elderly Person’s 7 Day Diabetic Diet 302
Breakfast 302
Lunch 303
Dinner 304

- Supper 307
- Diabetic Supplements 309
- Diabetic Eating Out 309
- Extra Diet Tips For The Elderly 309
- Salt 310

Tremor 312
- Tremor Remedies 313

Weakness 317
Heart Disease 318
- Heart/Kidney Relationship 320
- Diuretics 321

Feeling Comfortable 322
Hearing Loss 324
Insomnia 326
Healthful Habits 326
Not Old Yet 328
Super Longevity 329
Dying 330

CURING CANCER 331
Another Fluke Disease 331
Teamed With A Solvent 332
Propyl Alcohol Polluted Products 335
Getting Well After Cancer 336
Herbal Parasite Killing Program 338
- Parasite Program Handy Chart 341

Maintenance Parasite Program 341
Pet Parasite Program 343
Parasites Gone, Toxins Next 345
Watch For Bacteria 346
Help Your Family, Too 347
Aflatoxin 348

CURING HIV/AIDS 351
Method Of Treatment 353
Benzene Polluted Products 354

Plan For The Future 356

CURING THE COMMON COLD 357
Tapeworm Stage or Mites.. 357
Molds and Colds.. 360
The Cure 363
Mold Free Diet 365
Prevention... 368
Curing Symptoms 369
True Origins Of Viruses.. 370

BODY WISDOM AND WHY BAD FOOD TASTES GOOD373
Salt.. 373
Fats 374
Starch.. 374
Sugar... 375
Dislikes.. 375
Outwit The Cravings 377
Back To Normal... 379
Toxic Food... 379
Moldy Food 381
Aflatoxin...382
Eradicating Aflatoxin...383
Zearalenone 384
Sterigmatocystin...385
Ergot...385
Cytochalasin B 387
Kojic Acid..388
T-2 Toxin...388
Sorghum Molds..388
Patulin..388
Mold Avoidance...389
Getting Away From Grains..392
Pets Teach Health Lessons...................................... 394

EASY LIFESTYLE IMPROVEMENTS 397
Living Hand To Mouth.. 397

Better Laundry Habits 398
Better Kitchen Habits 399
Better Housekeeping 402
Windows Open Or Closed? 405
What Kind Of Heat 407
Getting Rid of Mites 407

FOUR CLEAN-UPS 409
Dental Clean-up 409
Guidelines For A Healthy Mouth 411
Horrors Of Metal Dentistry 416
Dental Rewards 419
Diet Clean-up 420
Breakfast 420
Lunch 422
Supper 423
Beverages 424
Horrors In Commercial Beverages 428
Food Preparation 430
Food Guidelines 431
Dining Out 433
Body Clean-up 435
Stop Using Supplements 439
Safe Supplements 441
Home Clean-up 444
Your Basement 444
Your Garage 445
Special Clean-up for Freon (CFCs) 446
Special Clean-up for Fiberglass 447
Special Clean-up for Asbestos 447
Your House 448
Unnatural Chemicals 451

BIOELECTRONICS 457
Making A Syncrometer 457
Making a Hobby Kit Syncrometer 458
Making Test Plates 460
Test Plates Parts List 460

Test Plates Assembly 461
Using The Syncrometer 462
Resonance 465
Lesson One 466
White Blood Cells 468
Making a White Blood Cell Specimen 469
Lesson Two 470
Lesson Three 470
Lesson Four 471
Preparing Test Substances 472
Impure Test Substances 472
Making Organ Specimens 477
Making a Complete Set of Tissue Samples 478
Purchasing a Complete Set of Tissue Samples 478
Body Fluid Specimens 479
Lesson Five 481
Lesson Six 482
Lesson Seven 484
Testing the Air 485
Testing Someone Else 486
Lesson Eight 486
Saliva Testing 487
Lesson Nine 487
Surrogate Testing 488
Lesson Ten 489
Lesson Eleven 491
Lesson Twelve 492
Lesson Thirteen 493
Lesson Fourteen 493
Lesson Fifteen 494
Lesson Sixteen 494
Lesson Seventeen 495
Sensitivity of Pollutant-In-Product Testing 497
Microscopy Lesson 498
Taking Pictures Of What You See 501
Using A Frequency Generator 502
The Theory 502
Lesson Eighteen 504
Lesson Nineteen 505
Lesson Twenty 506

Lesson Twenty One 507
Lesson Twenty Two 507
Lesson Twenty Three 508
Lesson Twenty Four 508
Lesson Twenty Five 509
Lesson Twenty Six 509
Lesson Twenty Seven 509
Lesson Twenty Eight 510
Lesson Twenty Nine 510

RECIPES 513
Beverage Recipes 513
Lemonade 513
Fresh Tomato Juice 513
Fresh Pineapple Juice 514
Maple Milk Shake 514
Yankee Drink 514
Hot Vanilla Milk 514
Red Milk 515
C-Milk 515
My Own Soda Pop 515
My Own Super C-Pop 516
Half And Half 516
Buttermilk-C 516
Food Recipes 516
Daily Foods 517
Two Granolas 518
Peanut Butter 519
Sweetening and Flavoring 519
Preserves 520
C Dressing 521
Cheese Sauce 521
Sour Cream-C 521
Yogurt 521
Soups 521
Fish and Seafood recipe 522
Baked Apples 522
5 Minute Ice Cream 522
Seven Day Sample Menu 523
Recipes for Natural Body Products 525

Borax Liquid Soap..526
For Laundry..526
For Dishes 527
In The Dishwasher..527
In The Sink...527
Shampoo 528
Hair Spray...529
Homemade Soap 529
Liquid Soap...530
Skin Sanitizer..530
Deodorant 531
Brushing Teeth 532
For Dentures...533
Mouthwash...533
Contact Lens Solution 533
Lip Soother...534
Foot Powder 534
Skin Healer Moisturizer Lotion 534
Other Skin Healers..535
Massage Oil..536
Sunscreen Lotion...536
Nose Salve 536
Quick Corn Starch Skin Softener 537
Cornstarch Skin Softener..537
After Shaves..537
Personal Lubricants 537
Baby Wipes...538
People Wipes 538
Recipes For Natural Cosmetics 539
Eye liner and Eyebrow Pencil.......................................539
Lipstick...539
Face Powder 540
Blush (face powder in a cake form) 540
Recipes For Household Products.............................. 540
Floor Cleaner 540
Furniture Duster and Window Cleaner.........................540
Furniture Polish 541
Insect Killer..541
Ant Repellent..541
Flower and Foliage Spray 542

Moth Balls 542
Carpet Cleaner 542
Health Improvement Recipes 543
Black Walnut Hull Tincture 543
Quassia recipe 546
Emmenagogue (Menstrual Period Inducer) 546
Bowel Program 546
Constipation Tea 548
Weight Reduction 548
Kidney Cleanse 549
Liver Herbs 552
Liver Cleanse 552
Lugol’s Iodine Solution 559
Vitamin D Drops 560

PATHOGEN FREQUENCIES 561
Bandwidth Of Organism Families 562
Mold, Mold Toxin Frequencies 562
Bacteria and Viruses 563
Roundworms, Flatworms, One-celled Animals 566
Wart Frequencies 569
Tapeworms 569
Mite Frequencies 570
Miscellaneous Frequencies 571
Toxic Elements 571
Solvents 574
Pathogen Frequency Chart 576

SOURCES 581

FINALE 589

INDEX 591

Figures

Fig. 1 Selected animal bandwidths. 17
Fig. 2 Selected pathogen bandwidths. 18
Fig. 3 Zapper schematic. 22
Fig. 4 Finished zapper, outside and inside. 27
Fig. 5 Simple pulser 29
Fig. 6 Ascaris. 32
Fig. 7 (L to R) Human intestinal fluke, pancreatic fluke, sheep liver fluke, and human liver fluke. 33
Fig. 8 Fasciolopsis' normal life cycle 35
Fig. 9 Feed animals out of your yard and away from where children play. Their wastes contain pathogens. 50
Fig. 10 Your kidneys with the adrenal glands sitting like hats on top. The ureters lead to the bladder 60
Fig. 11 All disposable diapers I tested had mercury and thallium! These toxins can be absorbed through babies’ skin. 69
Fig. 12 Do not use any commercial personal products, the risk of pollution is too great. 71
Fig. 13 Safe substitutes for personal products 72
Fig. 14 Tooth numbering system. 74
Fig. 15 Trichinella larvae settled in muscles 76
Fig. 16 Hookworms, strongyles, and whipworms 79
Fig. 17 Stone ground corn tortillas, high in calcium. 81
Fig. 18 Your lymph nodes are your best friends 90
Fig. 19 Colon. 97
Fig. 20 Keep personal water bottles sterile. 98
Fig. 21 Estrogen and progesterone levels (pg./ml) 114
Fig. 22 The liver has a large lobe on your right side with the gallbladder tucked inside. The left lobe is smaller. 128
Fig. 23 Gallstones 130
Fig. 24 Stomach, esophagus, diaphragm, gallbladder. 132
Fig. 25 Hiatal hernia. 133
Fig. 26 Lymph node neck glands 157
Fig. 27 Eye. 160
Fig. 28 Bottling equipment should be rinsed with ethyl (grain) alcohol, not propyl alcohol or wood alcohol. 183

Fig. 29 Tight diapers are a modern atrocity, forcing mercury and thallium into the baby’s sponge-like skin. 190
Fig. 30 Some cysticercus varieties (types) have multiple heads.......197
Fig. 31 Emerged cysticercus. 198
Fig. 32 Sheep liver flukes. Black threads in toilet are indicative of fluke remains..222
Fig. 33 I found all calorie boosters to be polluted with wood alcohol. Make your own. 240
Fig. 34 Alcoholic beverages contain ergot and aflatoxin. Add vitamin C (1/8 tsp.) upon opening and wait 10 minutes for it to act.....280
Fig. 35 Chlorinated water can cause mental problems......................283
Fig. 36 Red blood cells, top and side view. 285
Fig. 37 Water pitcher with filter. 288
Fig. 38 Sea salt flats are often roosting places for sea gulls. 311
Fig. 39 Too hot and too cold..323
Fig. 40 Products with propyl alcohol...334
Fig. 41 U.S. regulations on sterilizing solutions. 348
Fig. 42 Keep both salt and vitamin C powders in closable plastic shakers. 349
Fig. 43 Grilled food has benzopyrenes as do hot dogs and “smoke flavored” foods. 352
Fig. 44 Mexican made candy with no benzene. 354
Fig. 45 Pollutants are in unlikely places..355
Fig. 46 Every brand of popcorn and corn chips I tested had zearalenone contamination. 355
Fig. 47 This Mexican bread has no molds. It is made from white, unbleached flour and is not wrapped in plastic.....................362
Fig. 48 Goods baked in a panaderia (Mexican style bakery) never tested positive to molds. 367
Fig. 49 Starter set of homeopathic remedies......................................369
Fig. 50 All U.S. brands of pasta I tested had mold, including health food brands like the one shown here (left). No Mexican brands of pasta, like the one pictured (right), had any molds..........385
Fig. 51 All cold cereals I tested were full of mold toxins (besides solvents), health food varieties were worst. 387
Fig. 52 Packaged herb tea is moldy and polluted with solvents. Get yours in bulk from an herb company. 390
Fig. 53 Three safe flavorings. 391
Fig. 54 Don’t eat the green on the potato..392
Fig. 55 Potato harvest of the future. 393

Fig. 56 Smooth floors allow every bit of dust to be removed. 404
Fig. 57 Moving into the summer kitchen got you away from the accumulation of filth from winter! 406
Fig. 58 Mite 408
Fig. 59 Dental replacements 411
Fig. 60 Tops and bottoms of some metal crowns. 412
Fig. 61 Thallium excerpt. 418
Fig. 62 More dental metal 419
Fig. 63 Beautiful plastic mouth. 419
Fig. 64 Ugly metal in mouth. 420
Fig. 65 Unpolluted breakfast cereals. 421
Fig. 66 Lawful uses of solvents in food 428
Fig. 67 Some unsafe beverages. 430
Fig. 68 Some good foods 432
Fig. 69 All breads I tested had mold if they were in plastic 433
Fig. 70 Good restaurant foods 434
Fig. 71 Examples of commercial “food lube.” 437
Fig. 72 Detergents with PCBs. 438
Fig. 73 Safe soaps 438
Fig. 74 Some polluted supplements 439
Fig. 75 Pure salt 440
Fig. 76 Laboratory salt label 441
Fig. 77 Garage fumes. 445
Fig. 78 Our future, unless we act 456
Fig. 79 Syncrometer schematic 458
Fig. 80 Syncrometer parts list. 459
Fig. 81 Bottle with white blood cells taped on top. 470
Fig. 82 Some purchased parasite and tissue slides. 479
Fig. 83 Table of the future. 483
Fig. 84 Microscope, slides and coverslips 498
Fig. 85 Setup for finding resonant frequencies 503
Fig. 86 Function generators 512
Fig. 87 Light colored, roasted peanuts in the shell had no aflatoxin. 519
Fig. 88 Make a bottle of borax liquid to fill your soap dispensers and shampoo bottle. Use citric acid to rinse and condition. 528
Fig. 89 These are gallstones. 554
Fig. 90 Chart of bandwidths for organism families. 562

Preface

The sick have been held hostage for their money or intangible assets since time immemorial. Doctors, even primitive and natural healers, surround themselves with mystery as they use herbs or chemicals and incantations or “prognoses” to help the sick recover. Today, the medical industry (doctors and their suppliers and insurers) take a significant amount of the worker's earnings. Wouldn't it be nice if they could all go back to gardening or some other primitive and useful endeavor? Wouldn't it be wonderful if the sick could join them?

The most promising discovery in this book is the effectiveness of electricity to kill viruses, bacteria and parasites. Does this mean you can cancel your appointment with your clinical doctor? No it does not. Killing your invaders does not make you well instantly. But happily, at your next doctor visits she or he will be removing drugs, not adding them.

You might think that such an invention should be quickly patented. That was my universal advice. But I chose not to. It helps me, my children, and my grandchildren, if you are well. The whole world needs to come out of the dark ages of medicine and illness. And to learn the true causes of infection and disease. We must and can usher in the **new age of disease-free living.**

No diabetes, no high blood pressure, no cancer, no HIV/AIDS, no migraines, no lupus and so on!

Not a single disease is left unconquerable with this new understanding!

The Promise

Step into a new world.

A world without chronic diseases.

Step out of your old world.

It has kept you a prisoner.

Try something new.

The prison has no walls. It has only lines. Lines that mark the ground around you. Inside the lines are your old ideas. Outside are new ideas that invite you to step over and escape your prison. Dare to try these new ideas and your illness promises to recede. In a few weeks it can be gone.

If you are very ill or chronically ill you must have asked yourself many times: why have these problems chosen me? Will there never be a way to conquer them?

You may be quite familiar with your doctor's explanation of your illness or your child's illness. A *Coxsackie* virus has entered your child's brain causing inflammation (encephalitis) there. You pray that your child's immunity will overcome it. You may be familiar, but so very helpless against this microscopic invader.

If you had the proverbial 3 wishes they would be: 1) please spare my child's life; 2) please make it so my child doesn't have permanent damage; 3) please bless and guide the wonderful doctors and nurses who are keeping the oxygen tent going, and are watching my child's temperature and vital signs.

What if you could turn a dial and in 3 minutes kill every Coxsackie virus in your child's body?

What if this had no side effects?

What if the virus never came back?

In this book you will learn how to do that. You will also learn why your child got encephalitis or other disease and how to prevent it forever.

If this is too mind boggling, just take it a step at a time: First, learn about the radio-type broadcasting that all living animals do. Second, find the "station frequencies" that your particular invader(s) broadcast at. Third, learn how to "jam" their frequency until they **expire**: it takes only minutes!

Finally, learn how to make your own diagnostic and treatment devices. The instructions are simple enough for anyone. Only by putting this power in your hands will it be safe from government regulation, however well intended.

Only Two Health Problems

No matter how long and confusing is the list of symptoms a person has, from chronic fatigue to infertility to mental problems, I am sure to find only two things wrong: they have in them **pollutants** and/or **parasites**. I never find lack of exercise, vitamin deficiencies, hormone levels or anything else to be a primary causative factor. So the solution to good health is obvious:

Problem	**Simplest Cure**
Parasites	Electronic and herbal treatment
Pollution	Avoidance

It's a valiant quest: The quest for health. With optimism in one hand and determination in the other, you too can work the miracles for yourself that my clients accomplished in the case histories.

More good news is that it is not expensive. The cost will range from a few hundred dollars to only a few thousand in order to eliminate both problems and cure your chronic diseases.

Be A Health Detective

After curing your own diseases, teach your friends and family how it's done. Families are related and their problems are related. This should make the task easier. Keep a small notebook to become part of the treasured family legacy as much as photographs do. If your aunt, father and brother had diabetes as well as yourself and all were cured after introducing them to this concept and technology, isn't this worthy of notes in your family's history?

Notice what a strong line of inheritance there can be, **not due to sharing genes** but due to sharing a roof, a table, a supermarket, and a dentist!

Many problems can be disinherited. Cure yourself of retinitis pigmentosa, Muscular dystrophy (the “inherited” kind), and break down your family's faith in the gene-concept for these diseases. Bring hope to your family by proving diseases' true etiology. Bring respect back for your loyal genes that bring you hair color, and texture, not hair loss. That bring you eye color, not eye disease. Your genes brought you the good things about your ancestors, not the bad things. Parasites and pollution brought you the bad things.

Killing all your invaders is just the first step, though. It is indeed the life-saving step. But getting well is more than saving your life. Next comes the more tedious task of finding their sources. Where did they come from? Why did they invade you so massively. Why you?

The story of your personal pollution unfolds as in a book. Look closely and you see the whole panorama of your numerous tiny invaders being held at bay by your valiant immune system, your white blood cells. You can see what they are fighting besides the invaders. Your ill-chosen diet and lifestyle products!

Your heart may go out to those tiny white blood cells. Never again, you may say, will you give them arsenic and mercury and lead. Never again, cobalt and asbestos and freon.

That great body of wisdom, your body, the same as listened to your three wishes, will reward you over and over as you co-operate with it, until you have had not 3 but 30 wishes granted, each one seemingly as impossible as climbing Mt. Everest.

- Your chronic yeast infection can go away.
- Your hair can stop falling out–might even grow back.
- Your body can become pregnant–when you had already given up.
- Your fatigue can vanish.
- Your insomnia can be gone.
- Your warts can fall off.
- Your sight and hearing can sharpen.
- Your constant hunger can disappear.

Health isn't just being free of sickness. Health is feeling great, feeling like laughing at funny things. Health is feeling grateful to be alive. It is feeling happy to see the sky and to see growing things and to feel confident in human society's progress. Health is remembering the good parts of childhood and believing you still have a lot of them.

The Discovery

What makes me think I can find things in the human body that a blood test can not? What new technology makes this possible? Why is electronic testing superior in many ways to chemical methods? What are my claims of electrically killing parasites based on?

In 1988 I discovered a new way to scan a body organ. It was electronic. We already can “see” an organ with a sonogram, X-rays, computerized tomography (CAT) scan, or with magnetic resonance imagery (MRI). These techniques can identify abnormal shapes in an organ without having to explore or guess. But my new electronic technique can check for viruses, bacteria, fungi, parasites, solvents and toxins, and in addition is simple, cheap, fast and infallible. Electricity can do many magical things; now we can add detecting substances in our body to that list.

The method rests on radio electronic principles.

If you match, very precisely, the capacitance and inductance properties of an external circuit so that its resonant frequency is the same as the emitted frequency coming from somewhere else, the circuit will oscillate. This means there will be positive feedback in an amplifier circuit. You can hear it. Like when a public address system squeals.

The external circuit I use is called an *audio oscillator*, quite easy to build or buy. Your body provides the emitted frequencies. When you combine the audio oscillator circuit with your body, and you hear *resonance*, then you have detected a match! Something in your body matches something in the circuit on the test plate. By putting a laboratory sample of, say, a virus on the test plate, you can determine if your body has that virus by listening for resonance. Hearing resonance is easy if you're a radio technician or musician. Others must patiently practice. The details are given in the Bioelectronics chapter (page 457).

You do not have to be an expert in anything to learn the electronic detection method. But a keen sense of hearing helps.

In 1988 I learned a way to put anything on my skin, blindfolded, and identify it electronically in a few minutes. I could taste something without flavor and identify it electronically. The system worked fine for detecting things in the skin and tongue. Would it be reliable for internal organs, too?

A whole world of discovery lay ahead of me. I wanted to know what was in my inner ear causing tinnitus, in my eyes causing pain, in my stomach causing indigestion and a thousand other things.

But behind the daily excitement of new discoveries, a gnawing question lingered in my mind. How is this possible without some pretty high frequency energy source, radio frequency in fact, running through my circuit? My audio oscillator was only 1000 Hz (*hertz*, or cycles per second); radio frequency is hundreds of thousands of Hz. And the phenomenon could be produced with an old-fashioned *dermatron*[1], too, that only puts out DC (direct current)–no frequencies at all!

A high frequency energy had to be coming from somewhere. Was it me? *Ridiculous*!

But there was a way to test. If my own body was putting forth the high frequency energy, it could be bled off and diverted into the ground with a correct size capacitor. This should stop the feedback oscillations. This turned out to be true; it was stopped. But *ridiculous* kept ringing in my ears and I tried another test. If there was indeed radio frequency (RF) running through my circuit I should be able to block it with the right snap-on choke. It did block. I thought of a third test. If this was truly a resonance phenomenon I should be able to add a capacitance to this circuit and see the resonance destroyed. Then add an inductance and see the resonance return. It did just that. I made graphs of the relationship between capacitance and inductance. They were entirely reproducible.

---

[1] The dermatron was invented decades ago and made famous by Dr. Voll. Establishment science disdained it!

Then why couldn't I see the RF on my RF oscilloscope? Probably because it was high frequency energy, not high energy frequency, and I didn't know how to amplify it above the background noise level. It was nevertheless not convincing. Yet much too tantalizing to ignore.

I thought of yet a fourth test. If I was really producing RF radiation that could be channeled through a circuit, I should be able to interfere with it by adding another RF radiation from an outside source. I added a frequency from my frequency generator, first at 1,000 Hz. Now there was no resonance. It interfered. Did this mean that my body was not producing radiation at 1,000 Hz? Or was my 1,000 Hz radiation being matched and canceled? I raised the frequency gradually, from 1,000 to 10,000 to 100,000 to 1,000,000 Hz. There was no resonance anywhere, and I couldn't draw any conclusions. It was 5 o'clock on Sunday afternoon. Quitting time. But one last look at my generator reminded me that it could reach 2,000,000 Hz and I was just at 1,000,000. One more quick experiment wouldn't take much time. I cranked it to 1,800,000 Hz. And now a resonance screamed out! Was I “hearing things?” No more interference. I did it over and over. Why was it resonating now and not before? Had I arrived at my body's own *bandwidth* (transmission range), and this was the reason it no longer interfered?

I found the lowest frequency that resonated to be 1,562,000 Hz. All frequencies that I checked (about 2,000) from there up to 2,000,000 (my frequency generator would go no higher) also resonated.

A year later I purchased a better frequency generator to search for the upper end of my bandwidth. Any frequency between 1,562,000 and 9,457,000 Hz could be added to the circuit and produce resonance.

It seemed obvious, then, that the human body broadcasts electrically, just like a radio station, but over a wide band of frequencies and very low voltages, which is why it has not been detected and measured until now.

Everything Has A Unique Frequency

It was a busy year, now 1989. I was determined to find a bandwidth for other living things: I found them for flies, beetles, spiders, fleas, ants. They were between 1,000,000 Hz and 1,500,000 Hz; cockroaches were highest amongst insects I tested.

Then came a dismaying finding. A dead insect had a bandwidth too! Much narrower, and near the top end of the same range it had when living, but distinctly present. So it wasn't altogether a living phenomenon.

But if dead things had a resonant bandwidth, then maybe a prepared microscope slide of a dead creature could be used, and my trips to the garden and telephone calls to abattoirs (for meat parasites) could cease. That was a lucky thought. My first slide was of the *human intestinal fluke*, a huge parasite, scourge of humanity. I had just found it to be present in the liver (not intestine) of every cancer sufferer I saw. The (dead) adult parasite had a resonant frequency around 434,000 Hz. Slides of that parasite's redia resonated nearby (432,000 Hz), as did its other stages.

Dead things still resonated! The entire catalog of biological supply companies, hundreds of specimens of viruses, bacteria, parasites, molds, and even toxins, were now available to research with this new technique!

Suddenly an idea bolted out of the blue. If a person were to hold on to the frequency generator while it was generating 434,000 Hz, what would happen to the adult fluke, if you were infected with it?

I tested this plan that same week on myself, not with the fluke but with *Salmonella* bacteria and *Giardia* and *Herpes* that I carried chronically. After a 3 minute treatment, I retested myself. I could no longer find them in my organs! There were no emissions at their characteristic frequencies. I repeated and repeated. Were they really dead? Maybe they were just numbed or were suddenly hiding. But symptoms were gone quickly too. My *Herpes* lesion stopped tingling. It was all too simple and unbelievable.

But was it safe? Within three weeks I had reliable data regarding the necessary level of electrical treatment. It only took 5 volts for three minutes at the specific frequency. It is not as if you had to use house current which would kill you, along with the parasite.

Selective Electrocution

In twenty minutes (three minutes at six different frequencies) a whole family could get rid of this parasite. Cancer cases showed that in a few hours the universal cancer marker, *ortho-phospho-tyrosine* could be banished from their bodies by killing this same parasite.

"Incurable" HIV cases lost their virus in a few hours, too. Laboratory retesting for HIV came back negative! Most cases of pain got immediate relief if I could identify the correct "bug" and have its frequency found by the next office visit. This seemed to be absolute proof that living things had an essential high frequency output of some kind of energy.

What was actually happening to the bacteria or parasites? If I could kill something as large as an *Ascaris* worm or intestinal fluke, then perhaps I could kill something even larger, like an earthworm or flea, something I could see with my own eyes instead of having to imagine its demise inside my body.

Ten minutes at a frequency chosen near the top of their broadcast range seemed to anesthetize them. But they didn't die. Later I checked the body bandwidth (the range of frequencies they emit) of each. The earthworms had lost a lot of their bandwidth, both at the top and bottom. The fleas seemed hardier; they had only lost a little. However they did not recover, even weeks later, from this loss.

Could it harm humans to douse them with RF frequencies **in their own bandwidth?** Quite probably, if the voltage were high enough. There was no need to experiment, though, because the parasites we want to kill have characteristic frequencies that **do not overlap** the characteristic frequencies of a human. In fact, they are far away (see the chart on page 17).

So my electronic method attacking illness was born. Find the resonant frequency of a bacterium, virus or parasite using a slide or dead bit. Treat the living invaders inside the human body with this frequency and in a matter of minutes they are no longer transmitting their own bandwidths—they are dead or sick and will be removed by our white blood cells.

It was a worrisome truth. Perhaps the department of defense would use this knowledge and develop super high voltage devices to kill people ("enemies") somewhere in the world. But I couldn't let sick people suffer. Besides, it would probably require a voltage much like lightning to kill people from a distance. Possibly a way could be found to shield yourself from frequencies harmful to humans by wearing a choke (inductor) coil which suppresses these frequencies. Remember, there was no recovery, just a slow death for my experimental animals. It must not happen to humans!

Meanwhile, people must be alerted that they can safely kill their invaders and heal their chronic illnesses. Invaders that have been increasing exponentially due to lowered immunity in recent decades. Possibly this is true for all species on our planet. The pollution of the entire biosphere has been increasing and with it the prospect of acquired immune deficiency syndrome (AIDS) for all of us.

Remember, though, that the true challenge is not to kill our invaders but to regain our health and immunity.

More than just parasites are making us sick! Pollution is too. Selective electrocution rarely makes people completely well. Sick people always have an environmental factor that must be corrected also.

How do we do that? The ship of “progress”, of increasingly complex, processed foods and products, must be turned around and simplicity become our goal. Survival is in simplicity of food intake, simplicity of life habits. Did Ralph Waldo Emerson foresee this when he said “To be simple is to be great”? Or will daily parasite and pathogen electrocution become another crutch that makes us just enough better that we can continue a detrimental lifestyle? Yet another “Band-Aid” treatment for our poisoned planet?

Bioradiation

Strange as it appears, it now seems obvious that every living creature broadcasts its presence like a radio station, the sun, or the stars. I have named it *bioradiation*.

Perhaps it is the same energy as the Asian *chi*; perhaps it is merely related to it. Perhaps it is the energy that runs along the meridians discovered eons ago by Asian practitioners.

Perhaps it is the energy that faith healers and religious teachers know how to harness, perhaps not.

Perhaps it is the energy that psychics perceive and that drives occult phenomena, perhaps not.

What is truly amazing is that ordinary persons have discovered such energy well ahead of scientists. Persons using the “art” of kinesiology, pendulums, radionics, dousing rods and many other forms of “strange energy” have no doubt harnessed a part of this bioradiation. It is a tribute to the generally high intelligence of common people and to their open-mindedness that they discovered this energy, **in spite of** opposition from scientists of today.

Over a century ago the scientists of Europe proposed the existence of a “life force” called “élan vitale.” They were scorned out of existence (and out of jobs). Young scientists, (including myself) were systematically taught to scorn this idea. Of course we were also taught that a good scientist was unemotional, does not scorn ideas, has a completely open mind, and does not rule something out until it is disproved to their satisfaction. The youthfulness of college years is so susceptible to prejudices of all kinds, and the desire for acceptance is so great, that special effort needs to be made to teach neutrality. Or at least to distinguish between emotion and fact. Where have these basic pedagogic principles gone? I was indeed inspired with the phrase “search for truth” but then promptly led down the path of “search for acceptance.”

I do not know what bioradiation, this electrical broadcast from our cells, is made of. Only its frequency was noticed and caught (modulated) in such a way as to be measurable. And this frequency, 1,520,000 to 9,460,000 Hz (for a human infant) is in the radio frequency (RF) range[2].

Anyone who is experienced with RF knows its strange behavior. Not strange in the “unknown” sense but in the amazing sense. Circuits don't need to be complete or closed for it to travel. Bodies and objects can “pick it up” without being in the circuit. These amazing properties are due to the capacitive and inductive properties of objects all around us, including ourselves.

Zapping Bugs

By *zapping* I mean selectively electrocuting pathogens. For years I used a commercial frequency generator to “zap” one pathogen after another.

First I made a chart of the frequencies for most of the bacteria and viruses in my collection (over 80, see page 561). Then I would test the sick client for each one of these, and hope they did not have one for which I didn't have a sample. Even persons with a simple cold typically had a dozen they tested positive to (not just *Adenovirus*).

Next it was time to tune in the frequency generator to a dozen frequencies for three minutes each. The total process, testing and treatment, would take about two hours. They frequently got immediate relief. But often the relief would be temporary. What I didn't know at that time was that viruses could infect a larger parasite such as a roundworm. Until you killed your roundworm and your virus, you would keep getting the virus back promptly.

---

[2] AM radio broadcasts are from 540,000 Hz to 1,600,000 Hz (slight overlap with lower end of human band), FM is 88,000,000 to 108,000,000 Hz (out of the human range).

In 1993 my son, Geoffrey, joined me and we tried a new approach. He programmed a computer controlled frequency generator to automatically cover all the frequencies populated by all the parasites, viruses, and bacteria, from 290,000 Hz to 470,000 Hz. It spent about three minutes for every 1000 Hz it covered. This was more efficient, but it meant spending ten hours being zapped.

Again, the results were disappointing. Arthritis pain, eye pain, colds were improved, but not completely cured overnight. Months later I would find that organisms were transmitting as low as 170,000, and as high as 690,000 Hz. My specimen collection was obviously incomplete. To cover this larger range, spending three minutes for every 1000 Hz, would take 26 hours. Still worth doing if it would indeed help all our illnesses. But even this method of zapping was not 100% effective for reasons yet to become clear.

In 1994 my son built a hand held, battery operated, accurate frequency generator. The purpose was to enable everyone to kill the intestinal fluke at 434,000 Hz with a low cost device. Enough benefit would be derived from zapping at various frequencies that I thought everyone should know how to make one. When I tested it on one of my own bacteria, however, **three others at much different frequencies died also!** This had never happened before. When I tested it on others, even though they had dozens of pathogens, all were killed!

Subsequent testing showed it was not due to some unique design, or special wave form produced by the device. It was due to battery operation!

Any positively offset frequency kills all bacteria, viruses and parasites simultaneously

given sufficient voltage (5 to 10 volts), duration (seven minutes), and frequency (anything from 10 Hz to 500,000 Hz).

Before this I had always set my commercial frequency generator to alternate between positive and negative voltage. Now I tried setting it to alternate between positive and zero voltage (*positive offset*). It was just as effective as the battery operated frequency generator my son designed.

Generating positive offset frequencies is the best way to kill all pathogens quickly.

But it takes more than one treatment.

It takes three treatments to kill everything. Why? The first zapping kills viruses, bacteria and parasites. But a few minutes later, bacteria and viruses (different ones) often recur. I conclude they had been infecting the parasites, and killing the parasites released them. The second zapping kills the released viruses and bacteria, but soon a few viruses appear again. They must have been infecting some of the last bacteria. After a third zapping I never find any viruses, bacteria or parasites, even hours later.

Why didn't the virus inside the parasite die with the first zapping? It may be because electricity travels on the exterior of things. The body of the parasite shielded the interior. This is why my earlier, promising work spending hours on a frequency generator gave only partial or temporary improvement—it was only done once, not three times. And it explains why a single treatment with a frequency generator or zapper frequently gives you a cold!

Zapping does not kill shielded organisms

such as those that may be in the middle of your stomach or intestines. The electricity travels along the stomach or intestine wall, not through their contents.

So zapping is still not perfect, but can bring such manifest relief that everyone should buy or make one. Parts cost less than $25.00; the plans are in the next chapter.

The Bioradiation Spectrum

Everything emits a characteristic range of frequencies (bandwidth). In general, the more primitive the organism, the lower its bandwidth. Advanced animals have higher frequencies and the range is wider.

BANDWIDTH OF BIORADIATION OF ANIMALS



Fig. 1 Selected animal bandwidths.

The human range is from 1520 KHz to 9460 KHz. Pathogens (molds, viruses, bacteria, worms, mites) range from 77 KHz to 900 KHz. Fortunately for us we can work on zapping pathogens in the lower ranges without affecting humans in the upper range.

BIORADIATION OF TYPICAL PATHOGENS



Fig. 2 Selected pathogen bandwidths.

Applying an alternating electrical voltage within an organism's bandwidth injures it. Small organisms with narrow bandwidths are extinguished quite readily (three minutes at five volts).

Positively offset frequencies can kill the entire range of small organisms (viruses, bacteria, parasites) in just seven minutes.

Building A Zapper

Being able to kill your bacteria and other invaders with electricity becomes much more of a panacea when you can do it all in three 7 minute sessions. No need to single out specific frequencies or to sweep through a range of frequencies one KHz at a time. No matter what frequency it is set at (within reason), it kills large and small invaders: flukes, roundworms, mites, bacteria, viruses and fungi. It kills them all at once, in 7 minutes, even at 5 volts.

How does it work? I suppose that a positive voltage applied anywhere on the body attracts negatively charged things such as bacteria. Perhaps the battery voltage tugs at them, pulling them out of their locations in the cell doorways (called *conductance channels*). But doorways can be negatively charged too. Does the voltage tug at them so they disgorge any bacteria stuck in them? How would the positive voltage act to kill a large parasite like a fluke? None of these questions can be answered yet.

Other fascinating possibilities are that the intermittent positive voltage interferes with electron flow in some key metabolic route, or straightens out the ATP molecule disallowing its breakdown. Such biological questions could be answered by studying the effects of positive frequencies on bacteria in a lab.

The most important question, of course, is whether there is a harmful effect on you. I have seen no effects on blood pressure, mental alertness, or body temperatures. It has never produced pain, although it has often stopped pain instantly. This does not prove its safety. Even knowing that the voltage comes from a small 9 volt battery does not prove safety, although it is reassuring. The clotting of red blood cells, platelet aggregation and functions that depend on surface charges on cells need to be investigated. But not before you can use it. Your safety lies in the short period of exposure that is necessary. Viruses and bacteria disappear in 3 minutes; tapeworm stages, flukes, roundworms in 5; and mites in 7. One need not go beyond this time, although no bad effects have been seen at any length of treatment.

The first seven minute zapping is followed by an intermission, lasting 20 to 30 minutes. During this time, bacteria and viruses are released from the dying parasites and start to invade you instead.

The second seven minute session is intended to kill these newly released viruses and bacteria. If you omit it, you could catch a cold, sore throat or something else immediately. Again, viruses are released from the dying bacteria. The third session kills the last viruses released.

**Do Not Zap If You Are Pregnant
Or Wearing A Pacemaker.**

These situations have not been explored yet. Don't do these experiments yourself. Children as young as 8 months have been zapped with no noticeable ill effects. For them, you should weigh the possible benefits against the unknown risks.

That is all there is to it. Almost all. The zapping current does not reach deep into the eyeball or testicle or bowel contents. It does not reach into your gallstones, or into your living cells where *Herpes* virus lies latent or *Candida* fungus extends its fingers. But by zapping 3 times a day for a week or more you can deplete these populations, too, often to zero.

Killing The Surviving Pathogens

The interior of gallstones may house parasites inaccessible to the zapping. Eliminate this source of reinfection by flushing them out with liver cleanses (page 552).

Although the center of the bowel contents is often unaffected by electric current, which lets bowel bacteria like *Shigella, Escherichia coli (E. coli)* and parasite stages survive, sometimes it is nearly all sterilized by zapping. This results in considerable shrinkage of the bowel movement. Eliminate remaining parasites and bacteria with a single dose (2 tsp.) of Black Walnut Hull Tincture, Extra Strength (see page 543).

There is no way of distinguishing between "good" and "bad" bacteria with either of these methods. However even good bacteria are bad if they come through the intestinal wall, so zapping targets mostly "bad" bacteria. The good news is that perfect bowel habits often result in a few days. Evidently, the good bacteria are benefited by killing the invasive ones. Homemade yogurt and buttermilk (see *Recipes*) are especially good at recolonizing the bowel. But it does not seem wise to culture yourself with special commercial preparations and risk getting parasite stages again when you can become normal so soon anyway. If you do decide to take some *acidophilus* bacteria to replenish your intestinal flora make sure you test for parasites like *Eurytrema* first.

When a large number of parasites, bacteria and viruses are killed, it can leave you fatigued. Try to give yourself a low-stress day after your initial zapping. But there are no significant side effects. I believe this is due to the second and third zapping which mops up bacteria and viruses that would otherwise be able to go on a feeding frenzy with so much dead prey available.

To build your zapper you may take this list of components to any electronics store (Radio Shack part numbers are given for convenience).

Zapper Parts List

Item	**Radio Shack Catalog Number**
large shoe box	
9 volt battery	

9 volt battery clips	270-325 (set of 5, you need 1)
On-Off toggle switch	275-624A micro mini toggle switch
1 KΩ resistor	271-1321 (set of 5, you need 2)
3.9 KΩ resistor	271-1123 (set of 2, you need 2)
low-current red LED	276-044 or 276-041 or 276-045
.0047 uF capacitor	272-130 (set of 2, you need 1)
.01 uF capacitor	272-1065 (set of 2, you need 1)
555 CMOS timer chip	276-1723 (set of 2, you need 1)
8 pin wire-wrapping socket for the chip	276-1988 (set of 2, you need 1) Note: Radio Shack is discontinuing all wire wrap sockets. Find another parts store or use 276-1995 (but the legs are much shorter and harder to attach clips to).
short (12") alligator clip leads	any electronics shop, get 6
Microclip test jumpers	278-017 (you need 2 packages of 2)
2 bolts, about 1/8" diameter, 2" long, with 4 nuts and 4 washers	hardware store
2 copper pipes, ¾diameter, 4" long	hardware store
sharp knife, pin, long-nose pliers	

Hints for absolute novices: Don't let unusual vocabulary deter you. A "lead" is just a piece of wire used to make connections. When you remove a component from its package, label it with a piece of tape. A serrated kitchen knife works best as does a large safety pin. Practice using the microclips. If the metal ends are L-shaped bend them into a U with the long-nose pliers so they grab better. Chips and chip holders are very fragile. It is wise to purchase an extra of each in case you break the connections.

R1	1K
R2	3.9K
R3	1K
R4	3.9K
C1	.01ì f
C2	.0047ì f
U3	MC1455
LED1	2 ma LED Red
Pin 1	ground
pin 8	power



Give this to an electronics person or make it yourself in a shoebox by using the following instructions.

Fig. 3 Zapper schematic.

Assembling The Zapper

1. You will be using the lid of the shoe box to mount the components. Save the box to enclose the finished project.
2. Pierce two holes near the ends of the lid. Enlarge the holes with a pen or pencil until the bolts would fit through. Mount the bolts on the outside about half way through the holes so there is a washer and nut holding it in place on both sides. Tighten. Label one hole "grounding bolt" on the inside and outside.



3. Mount the 555 chip in the wire wrap socket. Find the "top end" of the chip by searching the outside surface carefully for a cookie-shaped bite or hole taken out of it. Align the chip with the socket and very gently squeeze the pins of the chip into the socket until they click in place.
4. Make 8 pinholes to fit the wire wrap socket. Enlarge them slightly with a sharp pencil. Mount it on the outside. Write in the numbers of the pins (connections) on both the outside and inside, starting with number one to the left of the "cookie bite" as seen from outside. After number 4, cross over to number 5 and continue. Number 8 will be across from number 1.



5. Pierce two holes ½ inch apart very near to pins 5, 6, 7, and 8. They should be less than 1/8 inch away. (Or, one end of each component can share a hole with the 555 chip.) Mount the .01 uF ca-



pacitor near pin 5 on the outside. On the inside connect pin 5 to one end of this capacitor by simply twisting them together. Loop the capacitor wire around the pin first; then twist with the long-nose pliers until you have made a tight connection. Bend the other wire from the capacitor flat against the inside of the shoe box lid. Label it .01 on the outside and inside. Mount the .0047 uF capacitor near pin 6. On the inside twist the capacitor wire around the pin. Flatten the wire from the other end and label it .0047. Mount the 3.9 KΩ resistor near pin 7, connecting it on the inside to the pin. Flatten the wire on the other end and label it 3.9. Mount the 1 KΩ resistor and connect it similarly to pin 8 and label it 1K.

6. Pierce two holes ½inch apart next to pin 3 (again, you can share the hole for pin 3 if you wish), in the direction of the bolt. Mount the other 1 KΩ resistor and label inside and outside. Twist the connections together and flatten the remaining wire. This resistor protects the circuit if you should accidentally short the terminals. Mount the 3.9KΩ resistor downward. One end can go in the same hole as the 1K resistor near pin 3. Twist that end around pin 3 which already has the 1K resistor attached to it. Flatten the far end. Label.



7. Next to the 3.9KΩ resistor pierce two holes ¼ inch apart for the LED. No-

tice that the LED has a positive and negative connection. The longer wire is the anode (positive). Mount the LED on the outside and bend back the wires, labeling them + and - on the inside.



8. Near the top pierce a hole for the toggle switch. Enlarge it until the shaft fits through from the inside. Remove nut and washer from switch before mounting. You may need to trim away some paper with a serrated knife before replacing washer and nut on the outside. Tighten.
9. Next to the switch pierce two holes for the wires from the battery holder and poke them through. Attach the battery and tape it to the outside.

NOW TO CONNECT EVERYTHING

First, make holes at the corners of the lid with a pencil. Slit each corner to the hole. They will accommodate extra loops of wire that you get from using the clip leads to make connections. After each connection gently tuck away the excess wire.

1. Twist the free ends of the two capacitors (.01 and .0047) together. Connect this to the grounding bolt using an alligator clip.
2. Bend the top ends of pin 2 and pin 6 (which already has a connection) inward towards each other in an L shape. Catch them both with an alligator clip and attach the other end of the alligator clip to the free end of the 3.9KΩ resistor by pin 7.

3. Using an alligator clip connect pin 7 to the free end of the 1KΩ resistor attached to pin 8.
4. Using two microclips connect pin 8 to one end of the switch, and pin 4 to the same end of the switch. (Put one hook inside the hole and the other hook around the whole connection. Check to make sure they are securely connected.)
5. Use an alligator clip to connect the free end of the other 1KΩ resistor (by pin 3) to the bolt.
6. Twist the free end of the 3.9KΩ resistor around the plus end of the LED. Connect the minus end of the LED to the grounding bolt using an alligator clip.
7. Connect pin number 1 on the chip to the grounding bolt with an alligator clip.



(As seen from the inside.)

8. Attach an alligator clip to the outside of one of the bolts. Attach the other end to a handhold (copper pipe). Do the same for the other bolt and handhold.
9. Connect the minus end of the battery (black wire) to the grounding bolt with an alligator clip.
10. Connect the plus end of the battery (red wire) to the free end of the switch using a microclip lead. If the LED lights up you know the switch is ON. If it does not, flip the switch and see if the LED lights. Label the switch clearly. If you cannot get the LED to light in either switch position, you must double-check all of your connections, and make sure you have a fresh battery.

11. Finally replace the lid on the box, loosely, and slip a couple of rubber bands around the box to keep it securely shut.



Fig. 4 Finished zapper, outside and inside.

- Optional: measure the frequency of your zapper by connecting an oscilloscope or frequency counter to the handholds. Any electronics shop can do this. It should read between 20 and 40 kHz.
- Optional: measure the voltage output by connecting it to an oscilloscope. It should be about 8 to 9 volts. **Note: a voltage meter will only read 4 to 5 volts.**
- Optional: measure the current that flows through you when you are getting zapped. You will need a 1 KΩ resistor and oscilloscope. Connect the grounding bolt on the zapper to one end of the resistor. Connect the other end of the resistor to a handhold. (Adding this resistor to the circuit decreases the current slightly, but not significantly.)

The other handhold is attached to the other bolt. Connect the scope ground wire to one end of the resistor. Connect the scope probe to the other end of the resistor. Turn the zapper ON and grasp the handholds. Read the voltage on the scope. It will read about 3.5 volts. Calculate current by dividing voltage by resistance. 3.5 volts divided by 1 KΩ is 3.5 ma (milliamperes).

Using The Zapper

1. Wrap handholds in one layer of wet paper towel before using. Grasp securely and turn the switch on to zap.
2. Zap for 7 minutes, let go of the handholds, turn off the zapper, and rest for 20 minutes. Then 7 minutes on, 20 minutes rest, and a final 7 minutes on.

Trying the zapper on an illness to see “if it works” is not useful. Your symptoms may be due to a non-parasite. Or you may reinfect within hours of zapping. The best way to test your device is to find a few invaders that you currently have (see Lesson Twelve, page 492, or Lesson Twenty Seven, page 509). This gives you a starting point. Then zap yourself. After the triple zapping, none of these invaders should be present.

Simple Pulser

If you are ill or want a reliable zapping, make the first model. However, there is another way to make a zapper if you can not afford to build the first model.

An ordinary battery is a source of positive voltage. It is the positive voltage that eliminates so many parasites at once, not a specific frequency. So although the zapper's frequency is about 30 kHz (thirty thousand “zaps” per second), even 5 Hz (five “zaps” per second), **about as fast as you can tap the battery with your hand, is moderately effective!**

You must be connected to both terminals. One will be marked + (positive) and the other – (negative). If you simply touch these terminals with your wet fingers, nothing much happens. That is because your resistance to the current starts going up right away, so less and less current passes through you.



Fig. 5 Simple pulser.

However if you tap the positive terminal with your wet hand, and tap it at a fairly high rate, your body's capacitors come into play. Capacitors only take part in the flow of electricity when they are charged and discharged. Tapping the terminal starts and stops the voltage so capacitors charge and discharge. This kind of resistance to current flow is much smaller.

The faster you tap, the greater the frequency of current pulses and the lower this kind of resistance becomes. Now you can have a considerable sustained current flow through your body.

If you can tap even twice per second (2 Hz) for ten minutes without interruption you can give yourself a zapping that is moderately effective. Remember to take an intermission of twenty minutes and then repeat to avoid catching new viruses. After a second twenty minute intermission repeat zapping a third time.

Using The Simple Pulser

9 volt battery
2 short (12") alligator clip leads (from any electronics shop)
2 copper pipes, ¾" diameter, 4" long (from a hardware store)

1. Wrap each handhold with one layer of wet paper towel. Place each on a non-conductive surface, like a plastic bag.
2. Connect the positive battery terminal to one handhold and the negative terminal to the other handhold using alligator clip leads.
3. Don't let the handholds touch.
4. Place a clock in front of you to time yourself.
5. Pick up the right handhold with your right hand.
6. Leave the left handhold on the table. Tap it with your left hand, preferably the fleshy part of the palm. You may brace yourself with your fingers on the plastic. Keep up a steady pace as fast as you are able.
7. When you get tired pick up the left handhold with your left hand and tap with your right hand. Keep changing off with the least interruption.
8. Repeat a second time 20 minutes later, and a third time 20 minutes after that.

A single 9 volt battery will wear out rather quickly used this way. Put two together, in parallel, for longer lasting power. This requires two more short alligator clips. Connect positive terminals of the batteries to each other, and the negatives also.

Parasites & Pollution

The word "parasites" is used in two senses. Everything living on you or in you, not just to perch, but to take its food from you is a *parasite*. No matter what its size, it can be called a parasite.

But in some way the big worms need to be distinguished from the medium-sized amoebae, the even smaller bacteria and the smallest of all—viruses. So often the term parasite is reserved for the bigger things, from amoebae on up. In this book, the word parasite will be used in both ways as usual. You can easily guess what is meant.

Parasitic worms are divided into *roundworms* and *flatworms*. Roundworms are round like earthworms even though they may be as thin as hairs (threadworms, *filaria*) or microscopically small (like *Trichinella*). Flatworms are more like leeches. They have a way to attach themselves sometimes with the head (*scolex*) like *tapeworms*, sometimes with a special sucker like *flukes*.



Worm parasites go through stages of development that can look very, very different from the adult.

Roundworms like *Ascaris* (common cat and dog roundworm), are simplest. The **eggs** are swallowed by licking or eating a bit of filth. They hatch into a tiny *larva*. The larva treks to the lungs. You cough it up and swallow it. Meanwhile it has molted a few times. It then crawls to the intestine where it becomes an adult, shedding eggs in your stool.



Fig. 6 Ascaris.

Worms usually have preferred locations. The favorite organ for *Dirofilaria* (dog heartworm) is the heart (even human heart). Sometimes the rules can be broken. My tests show *Dirofilaria* can live in other organs, too, if they are sufficiently polluted with solvents, metals and other toxins.

Flatworms like **tapeworms** are much more complicated in their life history. You could eat the eggs accidentally with dirt. After hatching, the tiny larva burrows into its favorite organ. Your body encases it with a cyst. The white blood cells have been taught never to attack your body...and the cyst case is your body! So the tapeworm stage has safe residence for some time. If you are a meat eater, you could eat such a cyst if it happens to be lodged in the meat you are eating! Your teeth break it apart as you crunch. The little larva is swallowed and tries to attach itself to your intestine with its head. Then it grows longer by making segment after segment. The segments with their eggs leave with the bowel contents. I often see dog tapeworm of the small variety in their human family.

Flatworms like **flukes** are also very complicated. The eggs, passed out with bowel contents were not meant to be eaten as such. They were meant to hatch in a pond where snails and minnows eat them. The larva grows up in these new "secondary" hosts. Later, the snail sheds them and they attach themselves to foliage near the pond. They over-winter in a tough *metacercarial* cyst. An unsuspecting browsing animal now eats them. They come out of their metacercarial cyst as a small adult and quickly attach themselves to the intestine with a sucker. They now have "safe haven" and can go about maturing and laying eggs.

Four common flukes are: **human intestinal fluke, human liver fluke, sheep liver fluke, pancreatic fluke of cattle.** Don't let the terms sheep and cattle mislead you. They are all found in humans.



Fig. 7 (L to R) Human intestinal fluke, pancreatic fluke, sheep liver fluke, and human liver fluke.

The Worst Parasite

Fasciolopsis buskii is the fluke (flatworm) that I find in every case of cancer, HIV infection, Alzheimer's, Crohn's disease, Kaposi's, endometriosis, and in many people without these diseases. Its life cycle involves six different stages:

Stage	**Normal Life Cycle**	
1 Egg	Expelled with bowel movement onto soil. Washed by rain into ponds.	
2 Miracidia	Hatches from egg in water. Has cilia, can swim vigorously and must find intermediate snail host in one to two hours or may be too exhausted to invade.	
3 Redia	Develop inside miracidia as little balls until expelled. Those are "mother" redia, and each one bears "daughter" redia for up to 8 months, all still inside the snail, and living on the fluids in the lymphatic spaces. Similarly, daughter redia are continually developing cercaria.	
4 Cercaria	Have a tail, use it to exit from snail and swim to a plant. If the snail is feeding on a plant, cercaria can latch onto plant with sucker mouth and start to encyst (form a "cocoon") within minutes. Tail breaks off and swims away to dissolve.	
5 Metacercaria	Two-walled cyst. The outer wall is very sticky. But as you eat the plant it is stuck to, the least pressure will break it, leaving the cyst in the mouth. The "almost unbreakable" inner cyst wall protects it from chewing, and the keratin-like coat prevents digestion by stomach juices. However when it reaches the duodenum, contact with intestinal juices dissolves away the cyst-wall and frees it. It then fastens itself to the intestinal lining and begins to develop into an adult.	

6 Adult	Lives in your intestine and can produce 1000 eggs per bowel movement and live many years.	

Fig. 8 Fasciolopsis' normal life cycle.

Note that the adult is the only stage that “normally” lives in the human (and then only in the intestine). *Fasciolopsis* depends on a snail, called a *secondary host*, for part of its life cycle. **But when your body has solvents in it, the other five stages can develop in you!**

If **propyl alcohol** is the solvent, the intestinal fluke is invited to use another organ as a secondary host—this organ will become cancerous. If **benzene** is the solvent, the intestinal fluke uses the thymus for its secondary host, setting the stage for AIDS. **Wood alcohol** invites pancreatic flukes to use the pancreas as a secondary host. This leads to pancreatic dysfunction which we call *diabetes*. If **xylene** (or **toluene**) are the solvents, I typically see any of four flukes using the brain as a secondary host. If **methyl ethyl ketone** (MEK) or **methyl butyl ketone** (MBK) are the solvents, the uterus becomes a secondary host and endometriosis a likely result.

This is a new kind of parasitism, based on pollution. I call the diseases caused by fluke stages in inappropriate locations **Fluke Disease**; it is discussed in more detail later (page 249).

Are tapeworms and roundworms affected by solvents this way, too? This is a fascinating and very important question. Search for the answer and help others search for the answer. I do not know yet.

Pollution

Pollutants are all the dead things around us that should not get into your body because they interfere with its work. As long as they don't penetrate your tissues, they won't interfere, like plastic eyeglasses and clothing. But if they are invasive, your body must fight to remove them.

Pollutants can invade your body via the air you breath, the foods and beverages you eat, and the products you put on your skin.

The biggest tragedy is not recognizing when a pollutant is harming you.

Two people can use the same face cream. One develops a rash, the other does not. The one who did not assumes the cream is not harmful to them…that they are like a bank vault, impregnable to that product. A better assumption is that the face cream is somewhat toxic, as evidenced by the rash that can develop, and they escaped the rash only because they had a stronger immune system. The immune system is like money, paid out of the bank vault, for every toxic invasion. When the money is gone, the bank (your health) fails.

Solvent Pollution

Solvents are compounds that dissolve things. Water is a useful, life giving solvent. Most other solvents dissolve fats and are life threatening, because fats form the membrane wall around each of our cells, especially our nerve cells.

The solvent that does the most harm is **benzene**. It goes to the thymus, ruins our immune system, and causes AIDS. The next worst solvent is **propyl alcohol**. It goes to the liver and causes cancer in some distant organ. Other major culprits of disease are **xylene**, **toluene**, **wood alcohol**, **methylene chloride**, and **trichloroethane** (TCE). I'll discuss each one later, with the ailment it's associated with.

Metal Pollution

Biochemists know that a mineral in raw element form always inhibits the enzyme using that mineral. Copper from the meat and vegetables you eat is essential. Inorganic copper, like you would get from a copper bottomed kettle or copper plumbing, is carcinogenic[3]. Unfortunately, the inorganic form of metals is what pervades our environment. We put metal jewelry on our skin, eat bread baked in metal pans, and drink water from metal plumbing.

Another obvious metallic threat is tooth fillings. **Mercury amalgam fillings**, despite the assurances of the American Dental Association, are not safe. And sometimes the mercury is polluted with **thallium**, even more toxic than mercury! **Gold** and **silver** seem to have fewer harmful effects, but no one should have any pure metal in or on their body.

Other prevalent toxic metals include **lead** and **cadmium** from soldered and galvanized plumbing, **nickel** and **chromium** from dentalware and cosmetics, and **aluminum** from food and drink cans, and cooking pots.

---

[3] Haleem J. Issaq, The Role of Metals in Tumor Development and inhibition. From *Carcinogenicity and Metal Ions*, volume 10, page 61, of a series called *Metal Ions in Biological Systems*, edited by Helmut Sigel, 1980.

Mycotoxins

Molds produce some of the most toxic substances known, called *mycotoxins*. One small moldy fruit or vegetable can pollute a huge batch of juice, jam or other product. Although molds are alive, and can be killed by zapping, mycotoxins are not, and must be detoxified by your liver.

But because mycotoxins are so extremely poisonous, a tiny amount can incapacitate a part of the liver for days!

Aflatoxin is the most common mycotoxin I detect. It is produced by molds that grow on quite a variety of plants. For that reason I am always cautioning people to eat only perfect citrus fruit, and never drink commercial fruit juice. Of the thousands of oranges that go into the batch of orange juice you drink, one is sure to be moldy, and that is all it takes to give your liver a setback.

A heavy dose of vitamin C helps the liver recover quickly. It also helps get rid of aflatoxin before it is consumed, right in the food container. So keep a plastic shaker of vitamin C powder handy and use it like salt on all your food.

There are thirteen other mycotoxins I have searched for in our foods. They are described in the section on moldy food (page 381).

Physical Toxins

Breathing in dust is quite bad for you so your body rejects it by sneezing, coughing, spitting up and out. Imagine breathing in broken glass particles. They cut into the lungs in a thousand places and couldn't be coughed up. They would travel. Imagine swallowing a needle or open pin. If the tip was blunt it could move through the intestine. But because it is sharp it gets caught in your tissue, then works its way deeper and deeper.

Would we ever knowingly breathe in broken glass? We are justifiably afraid of it in our food or under our bare feet. We are unaware that it fills our homes when **fiberglass** insulation is left imperfectly sealed off. Any hole made through the ceiling or wall, even if covered with cloth, lets swarms of broken glass bits into the house air. Air currents flow inward, into your living space. So all holes leading to the attic or insulated spaces must be sealed airtight. Of course, fiberglass should never be used in home construction, draperies, or around water heaters. The best advice is to have it all removed while you are away and then vacuum and dust.

Occasional exposures by house builders working outdoors does much less harm. Chronic exposure from a single small hole in the ceiling does a lot of harm, leading to cyst formation. And that cyst is a perfect place for parasites and bacteria to settle and multiply. When the intestinal fluke settles there it becomes malignant!

Cancer patients with *solid tumors* have either fiberglass or asbestos in them.

Asbestos is another tiny bit, sharp as glass, that moves through your body like a swordfish, impaling your cells until it, too, gets routed into a cyst.

We have been led to believe that we no longer have asbestos in our homes because we have outlawed the fireproofing materials it was used in. While that may be true, the source I find most often is all too prevalent: the clothes dryer belt. As it gets hot the belt releases a blast of asbestos particles that are forced through the seams of your dryer, and also openings in your exhaust hose, by the high pressure formed inside. It is now in your air.

Chemical Toxins

Chlorofluorocarbons (**CFCs**) or **freon** is the refrigerant in your air conditioner and refrigerator coils. CFCs are suspected of causing the ozone hole above the South Pole. All cancer sufferers test positive for CFCs in their cancerous organ! I have preliminary evidence that it is CFCs that attract other pollutants–fiberglass, metals, PCBs–to form a growing tumor instead of allowing their excretion. This would make it a "super carcinogen.". How could you detect CFCs leaking in your home? By the time your air conditioner or refrigerator needs recharging, you have been exposed for a long time. We desperately need an inexpensive, in-home test for this unsuspected killer.

Arsenic is used in pesticide. Why would we poison ourselves along with the cockroaches? Is it because we can't see it happening? Just as we couldn't see the fiberglass floating in the air? Our diligent scientists have studied the mechanism of arsenic poisoning in great detail. Then why are we allowed to put it on our lawns to be carried into our carpets via shoes?

Polychlorinated biphenyls (PCBs), oily compounds with wonderfully useful electrical properties, were originally used in transformers until their inability to break down into less toxic substances in our environment was spotlighted. Banned from use, I find them in most commercial soap and detergents! Is transformer oil being disposed of by selling it to soap makers?

Formaldehyde is used to cure foam. As a result, foam furniture, pillows and mattresses give off formaldehyde for about two years after manufacturing. If you sleep with your nose buried in a new foam pillow all night, you are risking major lung problems.

Every cleanser in your house probably has a toxic warning on its label. Every fluid your automobile uses is toxic. Every pesticide, herbicide and fertilizer you put on your lawn is probably toxic. Every paint, varnish, wax, lubricant, bleach and detergent will send you to the hospital if even a small amount is ingested. Why do we keep them around? See *Recipes* (page 513) for safe, old-fashioned, alternatives.

If you are ill even after zapping, it is toxins still at work. Getting rid of them is a major step toward being well.


I DON'T THINK WE SHOULD LET HUMANS INTO THE HOUSE. WE'LL GET ALL THEIR PARASITES.
YEAH, I JUST CAN'T GET RID OF THIS MANGE.

How We Really Get Sick

What if you invented a device that could search people for the presence of mycotoxins (extremely toxic substances made by food molds)? And what if you found that although many people had them, those who were sick with a cold always had at least one of them. Would you ask whether a sudden buildup of mycotoxins is what really lets colds develop? Why do some people in the same family get the cold while others do not?

- What if you found everyone with **cancer** had the human intestinal fluke in their liver, and no one else did?
- What if you found everyone with **diabetes** had the pancreatic fluke of cattle in their pancreas, and few others did?
- What if you found everyone with **environmental illness** tested positive for Fasciola (sheep liver fluke) in their liver?
- What if you found everyone with **asthma** tested positive for Ascaris in their lungs?

What if you always found every mysteriously ill person had some unsuspected parasite or pollutant?

The device is the Syncrometer^{TM}, and these "what ifs" are all true. They forced me to alter my entire outlook on what really causes some of our "incurable", mysterious diseases.

We used to believe that diabetes was caused by over consumption of sugars, a cold by a virus you caught from somebody, cancer from carcinogen exposure, depression from poor parenting. This multicausal concept is what made the study of medicine so difficult that only a few could undertake it. And every year new syndromes are added to the list of human illnesses.

But these diagnoses are based on a description of what is happening at a particular place in your body. This is like calling a mosquito bite behind the ears by one name and a mosquito bite behind the knee by another name. If you never see the true cause, a mosquito at work, this system could be excused as somewhat sensible.

And, until now, the profession of medicine has made some sense. The new truths, however, make the old descriptive system obsolete. You can now find the true causes of all your illnesses. And you can find them yourself by building the electronic diagnostic circuit (page 457)!

Once you have seen a mosquito at work on your body you no longer need to go to the doctor for a red, itchy bump. You don't need to search for the correct diagnosis and an appropriate drug. **You put up screen doors and windows!**

Once you have seen how common house dust is implicated in the common cold you get rid of the house dust. Once you have seen the mold in your food facilitate the cold virus you throw out that moldy food. But only seeing is believing. Nothing is left to faith. The electronic resonance method described in this book will let you see all these things for yourself.

You are not a hapless pawn attacked by bacteria and viruses that dart at you from nowhere to make you ill. You are not at the mercy of diseases all around you, hoping, by chance, to escape, like a soldier hoping to come home from the war. Nature and your body make good sense.

There is no disease that can outwit you if you know enough about it. Not even Lou Gehrig's disease! Nor asthma or diabetes. Read how the people in the case histories made themselves well. Read why some people failed. You have an advantage they did not have. Their instructions were hard to carry out because they had to have faith in them. You don't. You can replace faith with your own hard headed observations by building the diagnostic circuit (Syncrometer). The great convincer is seeing it yourself. When you personally find the mold in your peanut butter, or *Shigella* in your cheese, you have the knowledge, not faith, that convinces and guides you.

All illness comes from two causes, PARASITES and POLLUTANTS.

Only two causes! This is what simplifies the picture to make it possible for you to cure yourself.

We have been taught that illness is largely our own fault. That it is due to “catching something”, not eating what we should, like roughage or vitamins, or not doing what we should, like dressing properly, exercising or going to bed on time. Somehow, it's our own fault. Either by doing something we shouldn't or not doing something we should. When absolutely no fault can be found we are told it's in our genes! True inherited diseases are extremely rare. Our genes have evolved over millions of years to produce healthy humans. Nor are genes that mutate during your lifetime at fault. Pollutants, which are known to be mutagens, are the real culprits.

Neither the parasites nor the pollutants in you are “your fault”. Notice that other people all around us are doing the same things or not doing the same things, and even share our genes and don't have our illness. The current concepts on disease causation blaming our actions and our genes are simply not logical.

But until now they appeared logical. Suppose 1000 people were bitten by a mosquito or flea, it would always be in a different place, and if you were using the location and effect system to diagnose the problem you could have a thousand diagnoses listed for them, including a defective gene. Could you be persuaded to accept a gene replacement for your red itchy bumps? The new gene might be for antihistamine production so the welts don't become large, red and hot, or lead to impetigo. If you were the research doctor, you might be tempted to alleviate a thousand persons' distress with a new gene. Fortunately, you are not and only need to solve your own problems. You can be more logical.

After you have found the parasite interlopers hiding in your body you can kill them electronically. And after you have identified the pollutants stuck in your organs you can stop eating them, breathing them or putting them on yourself. In response, your body will begin to heal, just as surely as a mosquito bite heals.

Heal from multiple sclerosis, emphysema, myasthenia? Yes!! Some healing will be swift. Some healing will be slow. Healing is not understood. It is much faster in young persons. But fast or slow you know it has begun. It will be an exciting adventure to watch yourself lose your symptoms and get stronger.

Self Health

The entire purpose of this book is to enable you to diagnose and treat yourself for any disease. You have three new approaches that make this wish a reality: the understanding that only pollution and parasites make you sick, the quick and inexpensive diagnostic circuit that lets you find which pollutants and parasites they are, and the zapper or herbal recipe that kills the parasites.

Wouldn't it be nice not to have to go to the doctor for your aches and pains? And not to be dependent on the doctor to diagnose and treat you?

Self health means keeping yourself healthy. Doing it **yourself**.

Suppose your doctor has already diagnosed you as having "Atypical Lateral Sclerosis" or "Shoulder-Hip Girdle Metastable Aplasia." Could you re-diagnose this for yourself so as to treat and cure it? And be successful? Why not? You have already succeeded in many enterprises. You learned to talk, walk, read, get along with people. These skills took a few years to master. Learning to keep well is a new skill. It may take a few years too. After you have learned these skills you may pass them on to your children. And so a new gift is given to humanity, like the gift of music or the art of cooking.

How To Heal

Your body has been trying to rid itself of its parasites and pollutants all your life! It had its own ways. It made stones, it made mucus secretions, it made itself toxic dumpsites. These were good tactics but now of course, they are no longer necessary. Can you help your body get rid of these accumulations and sweep itself clean again?

Sweeping your liver clean is the most powerful way of helping your body to heal itself after the parasites are gone. There are thousands of bits of "trash" accumulated in the liver bile ducts. They will turn into stones (gallstones) if left in place.

The kidney, too, has made numerous small stones in its effort to keep your body clear of lead, cadmium, mercury and other impassable pollutants. You can assist the kidney to expel all these.

In days, not weeks or months, you can feel the healing effects of clearing gallstones and kidney stones from your body. But there are miles of bile ducts (50,000 ducts) in the liver; the herbal recipes that do this are used over and over, patiently, until all, the "trash" is removed. This can take several years.

So, although you can stop your disease very quickly from progressing, the healing process may not be complete for years.

Nevertheless, you are healthy again. This means your pains are either gone or greatly reduced. Your organs are functioning better. You have a new sense of well being. Your energy is up. Your desire to live and accomplish something is back.

Organs that have been damaged beyond the ability of our simple methods to reverse can be treated with the magic of modern surgery. Cataracts, bunions, old injuries are examples. Possibly, these too, are "stone" formations. But no recipe has been found to clear them up simply and in a useful time frame.

Killing parasites, removing pollutants and clearing gallstones and kidney stones from your body is a powerful combination of treatments. It is so powerful you can change yourself into a new person in half a year. And then go on improving for years more.

Should you stop taking your prescription medicine while you are treating yourself? NO. Wait until you have cured yourself of the condition that required the medicine. Reduce your medicine and eventually go off it. Will your doctor approve? Find one that will. Remember that the medicine is buying you the time to cure yourself, something to be grateful for.

The Road To Wellness

To review our new understanding of health vs. disease:

- We have only two problems: parasites and pollutants. Parasites are things that live on us, using up our food and giving us their wastes. Pollutants are toxic things in us making it difficult for our organs to do their work. These two things are responsible for all our other problems.
- Our bodies have been trying to rid us of these by making stones, making secretions, giving us swellings, inflammations and benign tumors. We develop deficiencies and disabilities.
- Finally, some permanent damage is done. Our hair turns gray, we develop cataracts, the spine bends, nerves and muscles die. We weaken.

Our strategy to undo all this will be a logical one.

First, we will kill all parasites, bacteria, viruses and fungi.

Second, we will remove the toxic molds, metals and chemicals in our foods and body products.

Third, we will clear away and wash away the stones, secretions and debris already formed, that hinder healing.

Fourth, we will use herbs and special food factors to hasten healing, being very careful to use pure products. (These act more quickly when given intravenously but the emphasis in this book will be on oral consumption.)

Finally, for repairs that are beyond our abilities, we will seek help from health and medical professionals.

What could be more exciting than finding the tremor is out of your arm or the pain is out of your shoulder? Won't it be admirable to correct your pulse and your high blood pressure, by yourself? What an adventure it could be to get rid of all your warts.

But getting rid of pain seems like a first priority to me, since pain often undermines our morale, our initiative to do things, even our interest in getting well!



Many of our illnesses are caused by unsuspected sources. I have found pigeon tapeworm in humans, for instance.

Fig. 9 Feed animals out of your yard and away from where children play. Their wastes contain pathogens.

Pain From Toe To Head

I would rather die than endure excruciating, unrelievable pain. That puts **pain** at the very top of my priority list.

Fortunately for us, pain killers are at hand to get us through it and buy us the time it takes to solve the real problem behind it.

The pain killing industry also brought us the addiction industry. As we turn to electrical pain killing the need for addicting drugs should decline. There are other very useful pain killers: acupuncture, massage, listening to music, feedback devices, contemplation, hypnotism, and prayer.

But we will focus on getting rid of the cause of pain and healing the organs that are in pain so none of these methods are needed.

I am not talking about the pain of a broken bone, twisted ankle, bee sting or sunburn. I am not talking about the pain of a misaligned vertebra or stretch trauma in your leg muscles or arm muscles. I am referring to pain that is in one of your organs and refuses to go away. For example, arthritis. Other pains are headache, foot pain, elbow pain, hip pain, chest pain. All of these may have special names like rheumatoid arthritis, cluster headache, fibromyalgia, bursitis, tennis elbow and so on, but they are all the same phenomenon.

Knowing that parasites and pollutants are the real culprits, let us get right down to the job of finding out which they are, where they come from, and how to get rid of them.

The parasites that cause pain are not the large ones, like worms or amoebas. Nor are they the very tiny viruses. They are *bacteria*. Bacteria are the right size to get into the doorways of our cells. Our cells try to keep their doorways tight-shut but, of course, they have to open to let food in, or hormones, or other life-signals. If bacteria are swarming around the outside of cells, some will manage to slip into a doorway while it is open. A battle begins. The cells refuse to let the bacteria in. The bacteria refuse to let go of the door latch. There is probably a specific electrical attraction between them and an exact physical fit. The body's extra forces, the immune system, are called in to help quell the invasion. The bacteria multiply as fast as they can. There is swelling. There is heat produced. There is pressure against other organs. All together it is called inflammation and infection.

The answer is not to deinflame with drugs (like the cortisone variety). The answer is not to reduce swelling or body temperature. **The answer is certainly not pain killer.** The answer is to kill the bacteria. (Even this is not the ultimate answer. We must stop the source of the bacteria and your body's invitation to be invaded. We will get to this later.)

So **Step One** is to search for the bacteria nibbling at our painful regions and identify them. This gives us the clue to finding their source. **Step Two** is to exterminate them electrically. Within minutes they fall out of the doorways to our cells. Your white blood cells are waiting for them, and will gobble them up in a grand feast.

But, remember, there is another cause of pain, pollutants. **Step Three** is to find the pollutants and identify them because this gives us a clue as to their source. **Step Four** is to eliminate our pollution sources. **And the job is done. Pain is gone.**

An intriguing question will pop into your head as you search your organs for parasites and pollutants. Which came first? Pollutants can jam their way into your cell's doorways too. Does this allow the bacteria to swim in? Or do the bacteria come first, jamming open the doorways so the pollutants can enter? Both seem possible. Maybe both events go on simultaneously. Perhaps that is why bacteria and pollutants are always seen together. Viruses can land on your cell's doorways, too, and cause viral diseases, but they are not as often pain producing.

You will also notice something, as you keep testing and watching over your health. **Your body is very good at killing bacteria and viruses**. Your body kills them faster than a wave of a magic wand! The only ones that get away are those that are stuck in doorways and ‘channels with pollutants in them! This seems like evidence that pollutants do the gate-opening. But it isn't proof and we must keep all possibilities in mind.

Fortunately we do not have to know exactly how parasites and pollution make us sick in order to get well.

Searching For Bacteria

In order to find which organs have the bacteria and which bacteria are present you will need to learn the new technology that makes all of this possible. This technology is a simple electronic circuit that is capable of trapping frequencies in such a way that you can hear them. Your body's frequencies, the frequencies of bacteria, viruses and parasites are all different and can be heard as distinctly as a **mooo**, **baah**, **tweet**, or **oink** coming from a farm yard.

But do you have to do all that?

No! You don't. You could simply electrocute all these tiny invaders. But how would you know what to avoid in the future? If your pain returned how would you know if it was the same old bacteria or a new one?

Learning to test takes the guesswork out of diagnosis.

My hope is that you will find it all so intriguing, so absolutely fascinating, that in spite of some chronic pain, you will feel compelled to make the searches yourself. Find someone willing to help. Trade your information. It is less difficult than learning to use a computer.

What You Will Find

First we will study and cure pains of all kinds, starting with the toes and working our way up the body. We don't need to be very specific about the location of the pain since bacteria and toxins flow over to nearby locations anyway.

For each kind of pain, we will look into the causes so you can eliminate them. Pain could come back in an hour if you didn't know the bacteria were coming from cheese and you had a cheese sandwich after *zapping* (killing parasites electrically). In fact, the pain may not have had time to go away before the next onslaught begins and you might conclude, wrongly, that this method doesn't work.

Parasites might also come back to your specially painful place from a few far away places that are hard to reach by your zapper's electrical current. The inside of your eyeball, the testicle, the interior of gallstones, the middle of a tooth abscess or the bowel contents are such places. Your zapper current, because it is high frequency, prefers to “go around” these items, rather than through them. But with repeated zapping, and herbal parasite treatment, you can decimate them, too, and stop reinfecting the rest of your body.

In fact, it is such knowledge about reinfection and sources of our pollutants that is the most important contribution of the case histories.

After dealing with pains we will turn our attention to the diseases that aren't pain producing, like diabetes, myasthenia gravis and so on.

Toe Pain

The ends of your feet get the poorest "service" from your blood supply. They are the furthest away. The blood here has the most accumulated acid and the least oxygen supply. The body produces quite a bit of *uric acid* and this should, of course, be excreted into the bladder by the kidneys. But if the kidneys are doing a poor job of this, levels in the body and blood stream rise. The blood can only hold so much. It holds even less in acid conditions such as the ends of your feet experience. Uric acid begins to settle out or precipitate at our feet.

Hippuric acid, too, is found where pain is found. Hippuric acid is made in large amounts (about 1 gram/day) by the liver because it is a detoxification product. It makes no sense to consume *benzoic acid*, the common preservative, since this is what the body detoxifies into hippuric acid. Read all labels on food you buy. Don't buy any beverages or baked goods preserved with benzoic acid. *Citric acid* is fine. The joints of the big toes are favorite places for pain to develop. This is made even worse when circulation is poor. Take a *cayenne* capsule with each meal to improve circulation. If you cannot find your pulse just below your inner ankle your circulation is poor.

The accumulation of uric and hippuric acid invites bacteria to feed on them. As bacteria multiply the tissue fights back with

inflammation. Now the stage has been set for **pain**. Some people do not have pain although these acids and other deposits are present making their joints knobby and unbending. Bacteria have not found them yet or haven't multiplied sufficiently in them to invade your tissues. Perhaps there are other reasons as well.

If you have **toe pain** your course of action is this:

1. Kill all bacteria possible with your zapper. Repeat daily until no further benefit is seen.
2. Dissolve the deposits away. An herbal recipe, quite elaborate, is capable of doing this. It is called the Kidney Cleanse (page 549). Toe deposits are made of the same crystals as kidney stones, which is why the Kidney Cleanse works for toe pain. But because these deposits are far away from the kidney, it takes longer than merely cleaning up kidneys. It may take six months to make a significant dent on these deposits. This will at the same time remove kidney crystals so that these are no longer a source of bacteria.
3. Get teeth cavitations cleaned (cavitations are bone infections in the jaw where a tooth was pulled; it never healed; see Dental Cleanup page 409). This can “magically” stop the toe pain the same day as they are cleaned. The effect lasts for days afterward showing it is not the dental anesthetic that is responsible. It also teaches you that the bacteria in the toes can come from the teeth. But pain may return as other bacteria find the deposits.
4. Clean the liver of stones using the Liver Cleanse (page 552). This, too, can give immediate pain relief in the toes showing you they are a source for bacteria. Liver cleaning may take you two years to complete! Meanwhile your toe pain is receding. And, of course, this pays extra dividends in health for your body.

5. Reduce the acidity in your toes. First, check your acidity with pH paper meant for testing urinary pH, called Nitrazine™ paper. Ordinary pH paper, as for fish tanks, is almost as accurate and will serve as well. Tear a ½inch piece and hold it in the urine stream. Early morning is the time your urine is most acid. If this reads below 5.5 your feet must have been even lower in the night (lower is more acid).

Once deposits start, it is hard to stop them. If they start forming at 2 a.m., they are likely to continue for several hours even if the pH goes back up to normal. Your tactic will be to go to bed with an alkalizing action. Taking a calcium and magnesium supplement at bedtime, drinking milk at bedtime, using baking soda at bedtime are all remedies to be tried. They should raise your urinary pH to 6 in the morning.

Balance Your pH

Most persons with painful deposits anywhere in their feet have a morning urine pH of 4.5! At 4.5 it is safe to guess that a lot has precipitated again in the night. During the day, your body's pH swings back and forth. The urine gets quite alkaline right after a meal; this is called the *alkaline tide*. Three meals a day would bring you three alkaline tides. During these periods, lasting about an hour, you have an opportunity to dissolve some of your foot deposits. But if you allow your pH to drop too low in the night you put the deposits back again. The net effect decides whether your deposits grow or shrink.

To alkalinize yourself at bedtime, choose one of these options:

1. Two oyster shell tablets, equaling 750 mg. of calcium plus a magnesium oxide tablet, 300 mg (see *Sources*). The magnesium helps the calcium dissolve and stay in solu-

tion. Taking more calcium at one time is not advised because it cannot be dissolved and absorbed anyway and might constipate you. For the elderly only one calcium tablet is advised. Take calcium tablets with vitamin C or lemon water to help dissolve (¼ tsp. vitamin C powder; adding honey is fine).

2. One cup of sterilized milk or buttermilk, drunk hot or cold, plus 1 magnesium oxide tablet, 300 mg. (adding cinnamon is fine).

   If these two remedies work for you, your morning urinary pH will come up to 6.0 but if for some reason they don't, you need to take more drastic measures. Take the supplements and milk earlier in the day and reserve bedtime for:

3. ½tsp. baking soda in water. This is *sodium bicarbonate*. But don't use baking soda from a store because most brands I have tested are polluted with benzene! (See *Sources* for safe baking soda.) Using a combination of sodium and potassium bicarbonate in a ratio of 2:1 is actually a much more healthful potion. You can make your own or ask a pharmacist to make it for you. Mix two parts baking soda and one part potassium bicarbonate (see *Sources*) in a jar. Keep tightly closed. Label it **sodium potassium bicarbonate alkalizer** (this potion is also very useful in allergic reactions of all kinds). Take 1 level tsp. in water at bedtime. If your pH reaches 6 in the morning continue each night at this dose. If it does not, take 1½tsp. Keep watching your pH, since it will gradually normalize and you will require less and less. If you are using plain baking soda, instead of the mixture, watch your pH each morning, also, so you can cut back when the pH goes higher than 6.

Persons with a limit on their daily sodium intake must carefully count the grams of baking soda consumed in this way.

Each tsp. weighs about 2 grams, of which half (1 gram or 1000 milligrams is sodium. The sodium/potassium mixture would only give you half as much sodium (½gram per tsp.). By comparison, the usual daily intake of sodium is about 5 gm., although salt eaters consume twice that amount.

You have done five things to pull the rug out from under the bacteria living in and around the deposits in your toes. Now when you kill bacteria with your zapper, you can expect the pain to go away and stay away.

Locations at the base of toes may be painful due to a *neuroma*. Deposits and bacteria here are even more painful because this is the location of nerve centers. If the build-up is large, you may prefer some surgical help or a cortisone shot rather than wait several years for solid relief.

Foot Pain

This kind of pain does not involve as much deposits as toe pain and is therefore easier to clear up. But trauma to the foot is more important. First, even though your shoes are comfortable, change them. Get wider shoes, longer shoes, lower heels. Alternate two pairs of shoes in a single day. In your home take shoes off.

Keep feet very warm. Wear natural fiber socks, not synthetics. If your circulation is poor, take a *cayenne* capsule with each meal. When circulation is moderately poor, your feet get cold easily. When circulation is very poor, the heart pulse cannot be felt in your feet (take your pulse just below your inner ankle). Again:

- Get teeth cavitations cleaned (Dental Cleanup, page 409).
- Do the herbal Kidney Cleanse (page 549).
- Kill parasites and bacteria with a zapper.

- Then clean the liver (page 552).
- Check body pH in the morning upon rising using Nitrazine™ or other pH paper. Correct it as discussed in Toe Pain. If the urinary pH is 7 or higher, it means you have a bladder infection. Treat it immediately (page 101).

If there is any swelling around the foot or ankle, you are "holding water." It may be called *edema*. This is due to poor adrenal and kidney function. The adrenals are located on top of the kidneys and together they regulate how much salt and water stays in your body. Because they are situated so close together, they share their parasites and pollution. When the kidneys form *kidney crystals* the flow through the kidney tubes is hindered, and less water and salt can leave the body. It stays in your tissues as edema.

The kidney herb recipe will dissolve the crystals. But you must remove toxins such as metal from tooth fillings and kill parasites. Continue doing the Kidney Cleanse after the original six weeks is up until all foot pain and edema are gone. Continue killing your tiny invaders with a zapper twice a week. You may need to cleanse the liver several times, too, before all the pain and edema are gone.



Fig. 10 Your kidneys with the adrenal glands sitting like hats on top. The ureters lead to the bladder.

The supplement, *pantothenic acid* (see *Sources*), is particularly good for feet. Take 500 mg three times a day for several weeks to see if it helps. Massage and reflexology are also good for them.

Heel Pain

Sometimes heel pain is due to heel spurs, sometimes it is not. Heel spurs are due to deposits. The usual heel deposits are *uric acid* and various *phosphates*. Uric acid deposits become a breeding ground for bacteria. The phosphates give the deposits a rigid structure that is hard to dissolve. You may have to choose a pain killer, get specially built "orthopedic" shoes, or stop your daily walks to get relief from the piercing pains. These will not cure the problem but may "buy you some time" while you make basic changes in your lifestyle.

Stop drinking tea and cocoa because they contain *oxalic acid*. Stop drinking coffee, decafs, fruit juice and soda pop because they are contaminated with solvents. All of these must be detoxified by your body and eliminated by your kidneys. We should spare the kidneys these extra tasks when we wish them to clean up heel spur deposits. You must first dissolve the deposits, then help the kidneys eliminate them.

To dissolve them, you alkalinize your body's pH, watching over it carefully with pH paper or Nitrazine paper. To help kidneys eliminate them, use the Kidney Cleanse and drink lots of water. Only water, not a beverage, helps the kidneys to eliminate.

Drink a pint of water upon rising in the morning, and a pint of water between meals.

Do not buy "special" water. Use your cold tap water only. If you don't like the taste of your own tap water, get it from somebody else's tap. Use only glass or reused polyethylene jugs. Polyethylene is opaque, not clear. It has already lost its plasticizer into the water that stood in it earlier. (Somebody drank it!) Purchased water has traces of solvents from machinery and sterilizing equipment used in its bottling. Your own tap water is not pure (indeed it may have 500 toxic elements), but it never contains solvents in amounts I can detect.

Traces of solvents are worse than traces of other toxins.

Water filters are not the solution. They trap the pollutants and then allow a tiny amount to enter the water on a daily basis. Chronic toxin consumption is much worse for your health than periodic surges of toxins. You can use a small filter, that gets changed every month without much risk. This would dechlorinate the water, at least, and improve the flavor. The pitcher variety (it should be made of hard, inflexible plastic) and the faucet variety are listed in *Sources*.

Bottled water is popular,

and tasty, and has appealing advertising, but it is just not safe.

Why is it easier for everyone to spend dollars per day, for the rest of their life, buying water instead of insisting that their water pipes are metal-free?

Another reason not to drink water from bottles, however convenient, is that it is stagnant and is soon contaminated with our own bacteria from contact with mouth or hands. *Staphylococcus (Staph)* and *E. coli* are commonly seen. The solution is not to add still more chemical disinfectants, the solution is to drink from a flowing source, such as our faucets. If you must carry water, use glass containers; plastic is porous and much more difficult to wash clean (sterilizing in a dishwasher is effective, though).

By drinking a total of four pints of water in a day, the kidneys will notice the assistance. (Any single herb tea without added salt or sweetener counts as water.) The urine will stop having any odor and will become very light colored. This is especially important while you are dissolving the heel deposits since your body is now carrying these in the circulation.

Killing bacteria with a zapper may give you instant pain relief and is, of course, beneficial to your body. But you can't expect the pain to stay away until the deposits are gone and the source of bacteria is also removed. Go after the usual sources: teeth and stones. Another source is dairy food contaminated with *Salmonella* and *Shigella* bacteria. Sterilize all of it by boiling. Even the amount put on cereal in the morning or used in scrambled eggs is enough to reinfect you! Butter and heavy whipping cream also need boiling. Stop eating yogurt and cheese which can't be boiled.

Phosphate deposits are a mixture of three phosphates: *monocalcium phosphate* ($CaH_2\ PO_4$), *dicalcium phosphate* ($Ca_2H\ PO_4$) and *tricalcium phosphate* ($Ca_3\ PO_4$). They are formed by eating too much (way too much) phosphate relative to calcium.

Our high phosphate foods are meats, carbonated beverages and grain products like rice, cereals, breads, pastas and nuts.

The body's normal elimination tactic for phosphate is to combine it with calcium and magnesium in order to neutralize it first. Unneutralized phosphate is very acidic and would burn the delicate kidneys. But where shall the calcium and magnesium be taken from? Magnesium is often in very short supply since it comes from green vegetables in the diet and is not stored up in any special organ. So it falls on calcium to be used for this purpose since it is stored up (in your bones and teeth).

The acid condition created by phosphates dissolves your bones and allows large amounts of bone structure to be washed out with the urine: this can be directly seen with an analysis of urine (you can ask your doctor to order this at a lab). If you catch all the urine in a 24 hour period you can measure all the calcium you have wasted. You should not lose more than 150 mg calcium in a day because this is all you can absorb in a day![4] If you do lose more than 150 mg in a day, you are dissolving your bones at a fast clip. This also means there is too much calcium in your blood and lymph, from dissolving so much bone so quickly.

Once you have dissolved your bones it is not so easy to put the calcium back into them. Your body will try to put it back as soon as possible—as soon as your acid condition is gone. But your bones can't do this without *vitamin D*. Vitamin D may "come from" sunshine and from vitamin D in milk but it isn't that simple. Vitamin D must be activated by your kidneys before it can go to work! Remember, though, it was the kidneys that had a problem in the first place, allowing deposits to form! With old kidneys, clogged with crystals, hampered by heavy metal and mold toxins, and beleaguered by bacteria and parasites, is it any wonder that sunshine and vitamin D fortified milk don't supply large amounts of activated vitamin D? It takes large amounts to put back into your bones the large amount of calcium that dissolved out during the acid state you put yourself in by over consuming phosphate food.

If you can't put the calcium back into your bones promptly where is it to go? It may attach itself to tissues that were never meant to be used this way. Your arteries fill with "scale," your kidneys form calcium phosphate crystals, heels form spurs, joints become knobby with deposits.

---

[4] You absorb 5 to 10% of what you eat. If you eat 1 gram (1000 mg) you absorb 50 to 100 mg. But you absorb 25-40% if it comes from milk!

Young persons and children, with healthy unclogged kidneys, make–that is, activate–ample vitamin D, so even if they consume too much phosphate and develop an acid condition that dissolves their teeth and bones, **they can put the dissolved calcium back in its proper place.** They don't develop hardened arteries, heel spurs, and knobby joints, at least not at first. Their bodies can take a considerable amount of abuse without showing it.

In general, people eat way too much phosphate. Meat eaters eat too much meat. Vegetarians eat too much grain. Most everyone drinks phosphated beverages. In this way we set the stage for hardened arteries, joint disease, calcified tissues that no longer have flexibility. We all get kidney crystals that become stones. This is *aging*. All these deposits invite bacteria to live in them and on them, creating pain.

Old age and pain go together as if they were true partners. Yet it is just the result of bad food choices.

Try to undo as much of this false aging as possible.

1. Reduce your meat consumption. Switch to fish which supplies calcium in the tiny bones. It is true, these bones are made of calcium phosphate and one might expect, logically, to be getting a less effective calcium source. Logic isn't necessarily biologically correct. The bones of fish work nicely as a calcium source and their phosphate content is not too great. Such a diet has worked for many primitive societies. Further, I have never seen a case of mercury toxicity from eating fish; amalgam tooth fillings are our truly significant source.

2. Reduce your grain consumption. Instead of cereal for breakfast, add fruit and reduce the cereal to half. Cut bread consumption in half. Cut pasta consumption in half. Cut rice and corn consumption in half. Eat more bananas and other fruits. Eat more vegetables; always choose potato (not potato chips) instead of rice or macaroni. Always choose a leafy salad instead of pasta salad. At any restaurant or salad bar ask yourself: is this wheat, rice or corn? If so, choose potatoes or other vegetables. Choose coleslaw. Choose mixed fruit. You don't need to go off the grains, only reduce them to improve your condition.
3. Take vitamin D as a supplement. Nothing less than 40,000 units has any real impact by the time there are problems. This strength is available by prescription only (usually 50,000 units, which is close enough). To avoid getting a polluted product, ask your pharmacist to follow the recipe on page 560. (In the past some cases of poisoning by overdosing resulted in this regulation. If you overdose you will get joint and muscle pain and nausea but it is reversible.) Take one a day (not more), for the first three weeks, then two a week forever after.
4. Finally, toss the carbonated beverages right out of your diet or make your own (see *Recipes*). It is not the carbonation that is harmful, it is the added phosphate. Drink water, herb teas, homemade fruit and vegetable juices, milk or buttermilk.

Milk, like fish, is full of calcium in the form of calcium phosphate. Again, logic might speak against the effectiveness of this form of calcium. Again, logic is wrong. Evidently, the calcium and phosphate story must be much more complex than I am depicting here.

Milk works best as a calcium source, in spite of its phosphate content. Possibly the *lactose* and other complexities of its composition contribute to this. My recommendation when deposits have formed anywhere in the body, such as heel, toe, arteries, joints, is to switch to milk as a beverage. Compare the calcium level of your urine before and after the switch (allowing several weeks first). Also compare calcium levels in your blood serum. It should move towards normal. This means **up** if it is too low (below 9.2). It means **down** if it is too high (10). If you are monitoring the effectiveness of the kidney herb recipe in dissolving away your phosphate crystals, notice that drinking milk keeps them from reforming. Taking calcium tablets does not! Taking nothing lets them reform the quickest.

The milk must be 2% or higher in butter fat to be effective.

With your body fluids at their proper acid level, with your kidneys able to flush out acids, with heavy metal toxins no longer settling in, with your bone-dissolving stopped, your heel deposits can shrink. Bacteria have no place to feed and breed. You can kill them several times more with your zapper to catch stragglers. And your heel pain becomes history. Be careful not to bruise the sensitive tissue with too much walking or running immediately after the pain is gone. Wear cushioning socks and well cushioned shoes.

Names in the case histories have been changed to ones of the same sex, picked at random from a telephone directory. Other facts may have been altered in non-essential ways.

Walter Jones, a man of 67, was diabetic for 14 years. His feet and upper legs hurt so much for the past 13 years he could barely shuffle along now. They were also cold and clammy. The herb, juniper berry was added to the Kidney Cleanse recipe to make it even more effective for him and he was advised to stop smoking, using alcohol, and caffeine. He also started the parasite killing program (at that time an herbal parasite program was being used instead of a zapper) and a liver cleanse that yielded several hundred small gallstones. Three months from his first visit his legs were better and feet OK, although he still had some trouble walking due to pain in upper thighs.

Dinah Sagun, a minister's wife, had a lot of walking and standing to do besides traveling a lot. She had knee surgery 15 years ago to remove deposits but now they were getting bad again. Also her heels were sore. My tests showed she had phosphate and oxalate deposits in her kidneys. She was started on the Kidney Cleanse followed by the parasite program. She stopped using benzene polluted items, especially her Chap Stick™. Her diet was changed to include milk and leave out store-bought beverages. In 4½ months her heel pain was gone along with the bad headaches we had not even started to work on.

Julie Fernandez came with a list of 10 serious problems including foot pain and ankle swelling. Her urinalysis showed crystals. My test showed they were uric acid crystals. Her parasites included *Trichinella*. There was a house cat. Her toxic metal test showed tellurium and platinum accumulation from metal dentalware and arsenic from pesticide. She was to start on a Kidney Cleanse and add the parasite program two weeks later. She was to remove all roach hives and other pest killers from her house and arrange for dental metal replacement. At her third visit, four weeks later, she could walk without pain although she still had *Trichinella* and arsenic problems. Two months later she was aching all over again and her kidneys hurt. She still had *Trichinella* and some dental work to do. She was to do a 5-day high dose parasite treatment and treat the cat also and repeat the kidney cleanse. This relieved her pain.

Dorothy Shelley had numerous pains including foot pain in the arch, lower back pain and cramps with her period. She had oxalate and uric acid crystals in the kidneys so was started on kidney herbs. Three weeks later her foot pain and low back pain were gone.

Paul Longtin had toe cramps, calf cramps, and heel pain. After cutting down on smoking, quitting caffeine and soda pop and taking niacin (250 mg time release; 1 capsule each meal and upon rising in morning) and doing a kidney cleanse, all in three weeks, he was much improved and didn't even need his arch supports.

Juan Onley, age 58, came for his gout in both feet and one hand. He could hardly walk, in spite of soft shoes and pain killer. It started 7 years ago. He also had prostate pain and couldn't sit comfortably. My tests showed his kidneys were full of uric acid, oxalate and cystine stones. His prostate was full of *Gardnerella* and *Campylobacter* bacteria. His wisdom teeth were harboring *plantar wart #4 virus* and *Coxsackie B4* virus. *Gardnerella* often comes with fluke parasites and indeed he had intestinal flukes in his kidney! He began with the kidney herb program, then the parasite killing program. It took five months to clear them all. Then he could walk and sit without pain.

Leg Pain In Children

It is commonly accepted as normal(!) in children to have pain in the shins or calves of the leg. They may even be called "growing pains." Children may cry with the pain and never tell anyone the reason for crying. It happens mostly after napping. This may be caused by cramping of the leg or spasms of the blood vessels. *Lead toxicity* is a common cause of both. Test for the presence of both **lead** and **cadmium** in the tap water. Only your own electronic tests are helpful. Water department tests are much too crude.

ULTRAS
ULTRA
Pampers
Pampers
Pampers
Pampers
Pampers
Huggies
Huggies

Fig. 11 All disposable diapers I tested had mercury and thallium! These toxins can be absorbed through babies' skin.

If either poison is

found, test the water supply from each faucet in the house, in the morning, before it has been run. Find the offending sources, change the water pipes to polyvinyl chloride (PVC).

Also search for thallium or mercury in the child's saliva. If it is there, remove all dental metal. Stop using all commercial disposable diapers, dental floss, cotton swabs and bandages; they are polluted with mercury and thallium probably from manufacturing them in foreign countries where it is legal to sterilize with mercuric chloride. Test again, several times, after plumbing or dental work has been completed. To relieve pain:

- immerse legs in warm water
- massage legs gently
- give 25-50 mg niacin, not time-release, to dilate blood vessels.

Leg Pain In Adults

Leg pain in adults is usually associated with *cadmium* or *thallium*. Cadmium is present in tap water that runs through corroded galvanized pipes. The cadmium is probably a contaminant of the zinc used for galvanizing. Test the water, electronically, for cadmium. If you have all copper pipes but there is cadmium in the water, there must be a short piece (a **Y** or a **T** joint) made of old galvanized pipe lurking somewhere. Track it down by testing water from all your faucets.

Cadmium causes the blood vessels to spasm and it is made worse by smoking, that's why the condition is sometimes called **Smoker's Leg**. But extremely painful legs are due to chronic thallium poisoning more than any other cause!

It is very important to know exactly how toxic thallium is. Read the clipping on page 417 right now!

Where would you ever get thallium? From your very own mouth! The mercury in fillings is often itself polluted with thallium! Replace your amalgam fillings with composite.

Bandages

Sanitary napkins and tampons

Cotton swabs

limpiecitos

Cotton balls

ACE
First Aid
First Aid
First Aid

Floss



Toothpicks (the one on the right is ten years old and had no mercury or thallium)

TOOTH PICKS
Diamond
TOOTHPICKS
Forster

Fig. 12 Do not use any commercial personal products, the risk of pollution is too great.

Thallium has another source: it is riding along as a pollutant in cotton swabs, cotton balls, commercial bandages, toothpicks, floss, gauze, sanitary napkins, tampons, disposable diapers, and paper towels. Evidently these are being sterilized with mercuric chloride which, in turn, has thallium pollution.

- Line **disposable diapers** with a tissue
- Line **sanitary napkins** and pads with a tissue
- Use the **polyester puff** in the top of vitamin bottles in place of cotton balls. Twirl some around a plastic stirrer for a swab.
- Use pieces of **tissue and masking tape** for bandages.

Cheese
Cloth

Use cheesecloth in place of gauze.



Use monofilament fish line (2 or 4 lb. test) for floss

Fig. 13 Safe substitutes for personal products.

If you do have thallium in your white blood cells and you haven't used toothpicks, etc. earlier in the day, then it is in your tooth fillings and **you have no higher priority than getting the**

amalgams out. Find a dentist immediately who will remove them, drilling deeply and widely not to miss a speck of it, thereby getting the thallium out, too. You cannot cure your leg pains without removing thallium.

Leg Pain Protocol

1. Stop smoking.
2. Repair plumbing.
3. Do dental cleanup and chelate out the mercury and thallium that has gotten into your tissues with EDTA (see *Sources*). You will need to find a chelating doctor; ask a friendly chiropractor to help you locate one. Or at least take thioctic acid 100 mg, (2 three times a day) and vitamin C (5 gm or one teaspoon) daily for a month.
4. Take magnesium oxide 300 mg (take 1 twice a day).
5. Take niacin, as much as you tolerate—time release varieties are less effective. Try 50 mg with each meal.
6. Change your diet to reduce phosphate and include milk (sterilized).
7. Do the herbal Kidney Cleanse (page 549) followed by a Liver Cleanse (page 552).
8. Zap yourself on alternate days at bedtime. If this zapping makes no difference whatever, your problem is purely spasms. But if you get relief, even if it's very short lived, you must have killed something. Bacteria must come from somewhere. Concentrate your efforts on dental health and better diet.

Jean Booth, age 30, had sore, tired legs and severe three-day headaches. She would get stabbing pains in back of her thighs. After we found thallium and mercury in her kidneys she did a Kidney Cleanse and got all her metal tooth fillings replaced. She then felt fine for one year. Suddenly she got fatigue and heavy legs again with stabbing pain at the outer thigh. She had seen a neurologist. Her chiropractor suggested it was leftover mercury so she came back to us. Indeed, she was toxic with lead, mercury, thallium, but her dentist could not find the leftover metal in her mouth. Three cavitations were cleaned; she was put on thioctic acid; eight varieties of bacteria and viruses were killed with a frequency generator and her legs became well again. Our test showed thallium at 4 teeth, but it was not a big enough deposit to show up on dental X-ray. She may eventually choose to have these redrilled.

Charlie Snelling was a picture of pain: pain in arms, elbows, shoulders, wrist, hands, chest, low back, legs, knees, and feet. He was started on kidney herbs and a few pains were reduced. He was toxic with cadmium so he changed his plumbing to plastic. However, he continued to be toxic with cadmium and thallium throwing suspicion on his numerous old tooth fillings. He got them all replaced and cavitations cleaned. He used our frequency generator to kill *beta Streptococcus*, *Pseudomonas*, *Troglodytella* and *Staphylococcus aureus* all of which were under one tooth (#15). A year later he still had bouts of leg pain. He still had numerous bacteria under his teeth because the jaw bone was not healing. He had not been taking vitamin D, nor magnesium nor drinking milk for the necessary calcium. But he had improved enough to go back to work full time.



Fig. 14 Tooth numbering system.

Victor Abhay, age 16, could no longer play in high school sports because of knee pain. It began “with a virus” and high temperature two years ago. His knee started to bother him after that. He had *cysteine* kidney crystals and four parasites: *Cryptocotyl*, human liver fluke, *Echinococcus granulosus* cyst and *Echinostomum revolutum* in his white blood cells. He was to start the kidney herb recipe and follow this with the parasite program. Five months later, when we next saw him, his knee was fine.

Kim Murphy, 45, had painful legs, feet and knees. They also were swollen and itched. She was parasitized by *Trichuris*, (dog whipworm). She also had tapeworm stages (*Taenia pisiformis*) and intestinal fluke in the intestine. She started on the kidney herbs, followed by the parasite program. She stopped using zirconium-containing products (deodorant) and barium (lipstick). She stayed out of bus exhaust. (She knew she was allergic to diesel exhaust.) In one month her leg pain and itching were gone; slight swelling remained.

Nancy Tong, 80's, had edematous legs. In fact she could get no stockings on. They appeared like pillars with no taper at all. She was on diuretic medicine from her doctor. It kept her blood pressure down but she was losing ground with water excretion. This raised her general toxicity (blood BUN[5]) which made her feel bad most of the time. Yet she drank enough water, curtailed her salt, used no caffeine and had no really bad habits. She had to wear several pads for incontinence. We found she was toxic with cadmium and lead, which were probably responsible for her huge accumulation of kidney stones. The metals were in her tap water and she was unable to resolve this problem since she lived in a senior citizen center. We advised her to move, or to have her tap water carried in, but she could do none of these. Although the situation was hopeless, she did the kidney cleanse, parasite killing program and changed her metal rimmed glasses and wrist watch to plastic. She gained enough ground from these improvements to be able to wear elastic hose and thereby give some physical assistance to her body. This encouraged her to do a liver cleanse. She had a headache with the cleanse but immediately afterwards she fit into a smaller size “Keds” (elasticized stockings). A half a year from the beginning, her legs had taper to them; she didn't even mind wearing a dress.

Fibromyositis and Fibromyalgia

When pain is widespread, not just in joints or legs but in many muscles and soft tissues of your body your doctor may call it *fibromyositis* or *fibromyalgia*.

---

[5] BUN stands for blood urea nitrogen. It is a body waste and is normally kept low by the kidneys.

For bacteria to get all over your body, they must be riding along with parasites that get all over your body. Microscopically tiny roundworms can do this.

Trichinella is the most common cause of these diseases, but sometimes *Ascaris* larvae or *hookworms* or *strongyle* larvae are the main culprits. These wormlets bring hosts of **bacteria** with them, mainly *"Streps"* (*Streptococcus* varieties) and *"Staphs"* (*Staphylococcus* varieties), but also *"Clostridiums"* (*Clostridium* varieties) and "Campyls" (*Campylobacter* varieties). The bacteria are probably the pain causers. By killing all bacteria—*Staphs*, *Streps*, *Clostridiums* and *Campyls*—using a zapper, you may get relief for one hour!



Fig. 15 Trichinella larvae settled in muscles.

By killing *Trichinella* and *Ancylostomas* (worms) first, followed by the bacteria, you may get relief for several hours. By killing the parasites and bacteria in every household member and the pets at the same time and by never putting your fingers to your mouth, you can expect permanent pain relief. It is interesting to speculate why the other family members, who are also infected with these tiny roundworms don't develop *fibromyalgia*. Perhaps the larvae stay in the intestine or go to the diaphragm (causing coughing) or the eyes (causing "lazy" eye muscles). Perhaps they merely cause **anemia**. *Trichinella*, hookworms and *strongyles* are extremely difficult to get rid of in a family.

These roundworm larvae undoubtedly cross the placenta into the unborn child during pregnancy, too. So they can be "inherited." Try to clear up the whole family before the next pregnancy.

Clearing up pets of these parasites is even harder. The best advice is to give your pets away. They will continue to harbor them even though they are on a pet parasite program. It is impossible to stay free of the parasites your pets have: they will move to your soft tissues immediately, giving you the bacteria and inflammation again.

The next most important advice is to keep fingers out of your mouth (read Hands, page 397). None of these parasites enter through your skin (this is in spite of teachings that hook-worms enter this way), you must put them into your mouth somehow! Consider your mouth off limits to anything but food and kissing.

Finally, if there is a baby in diapers in the family, be patient. When diapering days are over you will have less bowel contact, giving you an opportunity to finish your own treatment. Meanwhile, wash fingernails in Skin Sanitizer (see *Recipes*) after cleaning up children's bowel movements, diapers and yourself. Use borax liquid for soap to leave an antibacterial residue on the skin.

Try to identify your parasites before killing them so you can be on the lookout for them in the future. Get slides or dead cultures of various pathogens and search in your white blood cells. If you can't do this, at least save a saliva sample of your own; keep it frozen or preserved. Also make a saliva sample for your pet. This gives you specimens to test yourself for later. You won't know which parasite is in this saliva specimen, but if you ever test positive for it again you will know you got it back. Then zap yourself.

Brenda Byrd was diagnosed with myofibrositis two years earlier at the age of 36. Her blood test showed triglycerides slightly high (152 mg./DL), indicating the beginnings of urinary tract problems. Her urinalysis stated “hazy” (hazy with bacteria or crystals) instead of clear urine. It also listed white blood cells, red blood cells, and a few bacteria present in her urine. Our tests revealed mercury and numerous other heavy metals distributed in her thyroid, stomach, kidney, lungs, bones and bone marrow. She was also full of beryllium (usually from "coal oil") contained in the hurricane lamps she kept in every room. She had numerous parasites, including *Strongyloides* and hookworms spread through her body tissues. She was thrilled to learn how to get her health back and started with the dental problem.

Marcia Cochran, 36, had muscles twitching all over her body. It was diagnosed as fibromyalgia. Her joints were tender and her chest felt "tight." She had bronchitis twice a year. She was on Amytryptaline™ for muscle twitching and Bentyl™ to calm the intestine (spastic colon). She had depression with it and was on medicine for that. It all started with fever and chills that she thought was the flu but after they went away, she was left with a tremor. Sometimes she felt that little electric shocks were going through her. She had *Ascaris* and hookworm larvae widespread in her body. She had sheep liver flukes in her liver. She was started on the parasite program. She was also toxic with PVC and tellurium (dental metal). The PVC was traced to plastic storm windows applied to the inside of the window and to new shower curtains. Two months passed and she had not solved any of her problems. Then she did her first liver cleanse and got over 100 stones out. This instantly reduced her fibromyalgia to occasional attacks. She was so encouraged she decided to go ahead with dental cleanup.

Joint Pain or Arthritis

Two main kinds of arthritis are recognized clinically, *osteoarthritis* and *rheumatoid arthritis*. In osteoarthritis the joints have bacteria living on the deposits left there. In rheumatoid arthritis the bacteria come from larger parasites—wormlets actually living in these joints. The worms are the common little roundworms whose eggs hatch into microscopic wormlets that travel.



Fig. 16 Hookworms, strongyles, and whipworms.

We have four common roundworms: *Ascaris, hookworm, Strongyloides, Trichinella*. Their life cycle normally directs them to travel to the lungs but in some people they travel through the entire body, including brain, muscles and joints. More research is necessary to explain this. My suspicion is that there are toxins, like **mercury**, **thallium**, **cadmium**, **lead**, as well as **solvents**, distributed through the body, lowering immunity and allowing the tiny larvae to reside there. Once the pathway (routing) to these organs has been established, it continues to be used by other parasites as well. Soon a variety of parasites, their bacteria and viruses, and pollutants are all headed toward these organs.

Osteo or Common Arthritis

When joints are painful it is a simple matter to kill the bacteria with an electronic zapper. Treat yourself with a zapper daily until the pain is gone. Maybe it will stay away, but chances are the bacteria have a steady source.

The most common source for *Staphs* and *Streps* are small abscesses in the jaw bone, under and beside old extractions, root canals and mercury fillings. You may get immediate pain relief just from a dental cleanup, and again disappointment may follow. *Staphs* and *Streps* are such ubiquitous bacteria, they may come not only from jaw bone infections but from gallstones, kidney stones and other parasites. The correct treatment for arthritis is a complete overhaul of body health: a diet cleanup, a body cleanup, and environmental cleanup.

Start with the herbal parasite program and zapping. Follow this with a kidney cleanse, then liver cleanse. If any toxin is overlooked, especially asbestos and fiberglass, it is sure to find your joints and permit bacteria to return and cause pain. Make sure to correct your body acid levels after doing pH measurements of the urine (page 57).

Arthritic deposits contain a large amount of phosphates combined with calcium. This calcium came from some other bone, such as the base of your spine or the wrist. Here the bones are getting weaker due to this calcium loss. Calcium was taken out of your bones for the simple purpose of neutralizing the excess phosphate in your diet. Reduce phosphate consumption (meats, soda pop, grains) by half, eating fish, milk, vegetables and fruit instead. Drink three cups of milk a day. If you are allergic to milk, do several liver cleanses, switch brands of milk, use milk digestant, and use it in cooking and baking. Cheese and cottage cheese are not substitutes for milk (the calcium stayed in the whey). Dairy products must be boiled before consuming and should be no less than 2% butter fat. It takes bile to make calcium absorbable, yet milk with less than 2% butterfat does not trigger the gallbladder to empty it's bile at mealtime.

If you are not used to dairy products, start slowly and work up gradually to the 3 cups a day needed.

Carol Lachance was diagnosed with arthritis of her back and knees. (She had spurs in both places.) She was positive for *Trichinella*, *Ascaris* and *Dirofilaria* (she also had pain over the heart). They had an outdoor dog. Her blood test showed a high phosphate and alkaline phosphatase level showing she was dissolving her bones. After changing her diet to include milk, extra oyster shell calcium (one a day), magnesium oxide and vitamin B_6, and reducing her meat and grain consumption her phosphate level went down to normal (below 4). She did the kidney cleanse and liver cleanse as well as parasite program but still had pain. A toxic element test revealed lead in her bones. It was traced to a drugstore variety multivitamin tablet she had taken daily for years. When she stopped these and added prescription vitamin D (50,000 units) for three weeks to help her bones heal she got relief.

Gail Hildebrand, age 62, had painful arthritic hands and gum disease. She had 12 parasites free-loading on her and was toxic with asbestos. This was traced to her clothes dryer. Four months later, after killing parasites, her hand pain and gums were much better. She had the dryer vent taped up tighter and this got rid of her asbestos problem. She started on kidney herbs and in one month saw that her enlarged knuckles were beginning to go down.

Norma Littrell, age 53, came in for her severe arthritis of six years. Her knees, shoulders and hands were painful. I explained to her that painful shoulders did not belong to the arthritis picture but had a gallstone etiology which she could easily fix in a single night at a later time (liver cleanse). She also had mid-back, upper back and lower back pain; again the upper back pain belonged to the liver problem. She had tricalcium phosphate kidney crystals as well as uric acid crystals. She was told to go off coffee (no decaf either), decrease her meat and grain consumption (phosphate) and increase milk and use stone ground cornmeal products (genuine stone ground tortillas as well as pickled pigs' feet are high in utilizable calcium). She started on the kidney herbs. In 33 days her low back pain had improved a lot, she could wash her own hair again and she could sit down and get up from her living room floor without pain. She was elated but we recommended less stress than such exercises for her joints.

TORTILLAS
Santa Fe
Santa Fe

Fig. 17 Stone ground corn tortillas, high in calcium.

Patricia Robinson, age 76, had pain in her knees, feet, lower back, hands and wrists. Also in her shoulders and upper back which is not part of the arthritis picture. She had swollen puffy eyelids which is a telltale sign of Ascaris. She had heartburn, cold feet and insomnia as well as high blood pressure. She was on several medicines. We started her on the kidney recipe and ornithine (four to eight as needed at bedtime) for sleep. We hoped she could stop her Ativan™ drug soon. She was to go off coffee, tea and decafs. Her hands were knotted and misshapen at the joints, also tender. Two months later there was little change; her doctor had put her on Prozac™ and she hoped that would do a lot for her (so she stopped the kidney herbs) but it didn't. The parasite test still showed *Ascaris* and she was started on the parasite program. We also found fluoride (from toothpaste), iridium, samarium and palladium, all from her tooth implants. She was to remove as much metal as the dentist could replace, clean cavitations, and take thioctic acid, 2 a day, to help clear metal from her body. In four weeks the sharp pain in her back was gone and in three more weeks the pain in her hands was gone.

Lynne Snyder, 72, had pain in every joint and had to be on pain medicine to keep moving. Her potassium level was very low (3.6—an adrenal/kidney problem), and she was started on kidney herbs, carrot juice, vegetable juice and bananas. In ten days she could feel some new energy but her pains were terrible, especially her knees. She was taken off tomato juice, cranberry juice, citrus, pepper (she was using a lot), and given buttermilk as a beverage which she enjoyed. After three weeks of kidney herbs she was started on parasite killing herbs. In another month her arthritis was much better. She was not on any pain medicine and could get to sleep without it. She thought it was mostly going off pepper that helped.

Rheumatoid Arthritis

When inflammation and swelling affect your joints, besides pain, it is called *rheumatoid arthritis*. In addition, a blood test may reveal “rheumatoid factor” to be present. In this case, the common tiny round worms have invaded your joints. These are *Ascaris*, *Ancylostomas*, *Strongyloides*, and *Trichinella*. Their eggs are everywhere around us, in dust and dirt and the filth under fingernails and our own bowel movements.

Superior sanitation is your first defense. Rinse fingernails in alcohol after cleaning up bowel movements or changing diapers. Never, never, tolerate long fingernails in any family member. If this discipline can't be enforced, do not allow food preparation by “long nails” unless gloves are worn. He or she may not be getting ill (yet) from the family parasites, but you are. Of course, you can kill them with a zapper (internally, not the ones under the nails) but that is after you have been infected. They are easily picked up again. It would be wise to zap for roundworms every week, just in case.

Make sure your pet is treated with parasite herbs or by zapper as well. A pet that goes outdoors will quickly (the very next day) bring these roundworms into the house again. Give away your pets if possible.

Check for dental problems. Do the Dental Clean-Up (page 409). Then do a Kidney Cleanse and Liver Cleanse.

You may relieve your pain and begin to heal immediately after zapping but it is wise to do all the health programs, anyway. Change your diet. Reduce phosphate, start using sterilized milk for calcium. Switch to fish from meats. Drink much more water. Use only harmless beverages (see *Recipes*) and foods. Switch to toxin-free body products. Live in a non-toxic house. Stay on a maintenance parasite program of herbs, and zap regularly. Stay on the kidney cleanse for three to six weeks and repeat a one-week session every few months to keep removing deposits which may also choose these sick joints to settle in. Knees are a favorite location for rheumatoid arthritis. Knees are very dependent on kidneys.

To summarize, do everything as for osteoarthritis, emphasizing the roundworm parasites for elimination.

Allergic Arthritis

A prominent food toxin that is said to affect knees is *piperine*, found in the pepper family which includes black and white pepper (not cayenne). The *Solanaceae* family of plants (potatoes, tomatoes, eggplant, tobacco!) also has a common "allergen" that produces joint pain. Try going off these for two weeks to see if it helps. Two more chemicals that can trigger arthritis-like pain are *hippuric acid* and *phenylisothiocyanate* (PIT).

Your body makes large amounts of hippuric acid, up to a gram a day. It is the product of benzoic acid detoxification by the liver. Quite a few fruits contain natural benzoic acid. But we can easily triple and quadruple our benzoic acid intake by consuming commercial beverages and pastries where benzoic acid is used as a preservative. It is indeed a "natural" preservative. All of it must be detoxified, though, and this gives us way too much hippuric acid. The kidneys are unable to excrete such overloads of hippuric acid, so it distributes itself in our organs. I suspect a simple mechanism could explain its pain-triggering action: hippuric acid molecules could attach themselves to our cell's conductance channels keeping the gates jammed open. This might invite bacteria and viruses to enter there. But there are also hippuric acid-loving bacteria that feed on it. Perhaps hippuric acid can cause pain without the help of bacteria. This requires further study. It is only sensible for persons with chronic pain not to consume benzoic acid (or benzoate) preserved foods.

PIT is a food chemical found especially in chicken, eggs, the cabbage family, peas. PIT is also part of the body's own chemistry, taking place in the liver, and involving detoxification of *cyanide*-containing foods. Many vegetables, notably the cabbage family, contain such cyanides, giving them protection from insects, disease, and grazing animals. It can take the liver a week to detoxify a meal full of these cyanides: in the meantime, PIT levels are higher in the body. PIT is very reactive. In fact, it is the chemical used as a general reactant with amino acids in the well known **Edman degradation** reaction. But now, your body is the reaction flask, supplying the amino acids. Since all organs supply amino acids, it is no wonder they can all react to PIT, giving you multiple allergic reactions and pains.

If you have any kind of arthritis, stop eating the high-PIT foods and clean the liver until you are free of all allergies you are aware of. This suggests that the liver is capable, again, of detoxifying the cyanides for you in a reasonable time and you may eat them again. These foods do have many benefits, of course.

Joint pain, or arthritis, was known in antiquity long before dogs and cats were household pets and giving us their parasites. Pigs and horses harbor these roundworms too and may have been the source at that time.

Herbs and treatments that help arthritis are, therefore, plentiful. Maybe they act by killing roundworms, bacteria, and viruses, or help metabolize hippuric acid and PIT. Homeopathic treatments, as well as massage, heat and electronic devices also help. With this wide range of effective treatments dating to the distant past, why is none of them a permanent cure? The answer is simple. The common roundworms are everywhere about us, sanitation is poor, and our civilized lifestyle leads to deposit formation that invites bacteria. But knowing this, you can stop your pain and remove the causes to become one of the first humans to achieve a permanent cure.

Verna Plumb, age 46, was diagnosed with rheumatoid arthritis four years earlier. Since then she had been continuously on methotrexate™ and prednisone.™ This had caused her to gain a lot of weight from water retention. The drugs were no longer effective and she would need to do something else very soon. She had the typical causes: her body was toxic with mercury and nickel from tooth fillings. Her kidneys were full of five kinds of stones. She had numerous roundworm parasites including two kinds of *Ascaris*, two kinds of hookworm, *Strongyloides* and *Trichinella*. She would have to clean everything up to get relief. She started on the kidney herbs, killed parasites with a frequency generator and in two months noticed her swelling was receding.

Camille Franklin had hands that were swollen and hot and painful. She also had "arthritis" in shoulders and knees. We explained that shoulders were not part of the arthritis picture. She could deal with that in a single evening, soon. She also had bone spurs at sinuses which needed surgical removal. Her kidneys revealed tricalcium phosphate crystals. She was given a diet change; onto milk, fruits and vegetables, off other beverages, less meat and grains. She was started on kidney herbs. In five weeks all the swelling and redness and heat was out of her finger joints.

Thigh Pain

Inner thigh pain often stems from the *sciatic nerve* which is suffering pressure at the lower back. If this is so, chiropractic adjustments should help. The correct treatment, after killing bacteria electronically, is to clean up the entire kidney area using the kidney herb recipe.

If this is not the correct explanation, (and you're not getting pain relief) you may have a trauma—perhaps you overstretched your leg in some exercise. The minor trauma invited bacteria to settle there and give you pain.

If the pain recurs after clearing it several times, there must be a chronic source of bacteria. Since the kidneys are already cleaned, consider the teeth, as well as recurring parasites, and the liver. Clean the liver every two weeks until 2000 or more stones have appeared and no more appear. This could take 1-2 years. Be patient. Do a dental clean up. Keep killing the bacteria so they can't spread. And, of course, let the painful leg rest.

Hip Pain

Hip pain is always due to bacteria. In fact, these bacteria regularly come from two sources: the kidneys and the teeth. This simplifies the treatment since neither of these places takes a long time to clear.

Start yourself immediately on the kidney cleanse (page 549) to clean your kidneys. Continue on the recipe until the dental cleanup has been completed. Both must be clean together to stop exporting bacteria to the hip.

The dental cleanup could take several weeks if extensive work is required. During this time, kill all parasites electronically. Keep killing bacteria, especially *Staphs*, *Streps*, *Clostridia*, *Campyls*.

The dental problem is not always on the same side as the hip pain. The jaw may be very fragile and porous, full of invading bacteria. Cleaning these cavitations may give immediate pain relief in the hip (proving the bacterial source). But getting the jaw bone to heal by taking up calcium again is not guaranteed by the cleaning process.

Give your jaw bone every chance to heal:

- Start taking vitamin D (40,000 to 50,000 u.), every day for three weeks from the day of the dental work or before. After this, take it twice a week forever. **Do not take more.**
- Take vitamin C (1+ gm a day) and B_6 (250-500 mg a day) for healthy gums.
- Get one gram of usable calcium in your daily diet.

Bone Strengthening

Vegetable calcium can't be dissolved by our stomachs (*ruminants*, like cows, can dissolve it—they have an extra stomach loaded with special bacteria who do the actual retrieving of calcium). Tablet-form calcium can't be dissolved well either, especially as we age. We need predissolved calcium if a little is to go a long way.

Primitive people who lived on fish or stone-ground meal ate 4-6 grams of calcium a day.[6] Even if only 20% of this got dissolved, they would still have about 1 gram of utilizable calcium for themselves. Chances are good they dissolved even more, since they were young (life expectancy was less than 50 years). Their skull remains show beautiful, cavity-free teeth. They lived outdoors, mainly, so getting enough sunshine-derived vitamin D was not a problem. Their natural diet supplied enough vitamin B_2 to protect them from UV (ultraviolet) damage from sunshine exposure.

But these are civilized times. Our lives are stretched into old age, when our stomachs no longer produce enough acid to kill bacteria, nor to dissolve the minerals in our food. So they need to be dissolved for us. Milk is a beverage where the calcium has already been dissolved by the other ingredients. The lactic acid in milk formed during digestion gives the calcium the correct chelated structure for absorption by the intestine. Even the bile participates in calcium absorption. Milk also contains phosphate, but not too much to be useful. I recommend milk as a calcium-source to heal the jaw bone after and before dental work. You need 1+ grams a day. One quart of milk has 1 gm (1000 mg) of utilizable calcium. You absorb only 250-400 mg. The rest is excreted and eliminated. Only the absorbed calcium can heal your jaw bone. Use milk in cooking as well as a beverage. The calcium in it is indestructible.

Bones are not made of calcium alone. **Magnesium** is essential. Since magnesium is more soluble and easy to assimilate than calcium, the tablet form (magnesium oxide, 300 mg, see

---

[6] Read Nutrition and Physical Degeneration by Weston A. Price, DDS first published in 1939. At least, gaze at the pictures. Ask your library to buy a copy, available from Price-Pottenger Nutrition Foundation, (800) 366-3748.

Sources) will do. If you are not absorbing the magnesium it will stay in your intestine and act as a laxative. If this happens acidify your stomach during meals: always add fresh lemon, vinegar, or vitamin C to your food or drink to help digest milk and dissolve minerals for you. **Boron** (3 mg. once a day) and **manganese** (15 mg. once a day) are additional bone hardeners.

When your diet is improved, your dental problem is cleared, and your kidneys are clean, your hip pain will stay away and you can stop thinking about hip replacement surgery.

Mary Hammond, 48, had two painful hips. She was diabetic and drinking five cups of coffee a day. She had *Staphylococcus aureus* infections under three teeth that she no longer had. After going off caffeine (caffeine may spread bacteria by making tissues more permeable) and getting some dental work done, her right hip stopped hurting. When cavitations were cleaned, her left hip stopped hurting too, but after a week the pain returned. She still had parasites and their bacteria to kill. She had solvents to eliminate and a kidney cleanse to do but she was quite enthusiastic and enjoyed showing off how well she walked.

Groin Pain

Lymph nodes are situated here, as well as in armpits and around the neck. Lymph nodes are your best friends. They are hives of activity. Your white blood cells “nest” here. Lymph nodes sample your body fluids (lymph) at these locations, much like the water department and health department sample our milk and water, making sure they are pure and sterile. Of course, they never really are. But your white blood cells keep working at it. They are busy removing impurities like zirconium and titanium and pathogens like bacteria and viruses.



Fig. 18 Your lymph nodes are your best friends.

When an especially challenging dose of parasite or pollution arrives at the node, it enlarges, in order to handle the bigger sized task. This enlargement can be felt. It may press against other organs and you feel the pain of pressure in the groin. This should alert you, of course, to the danger. Kill the parasites and pathogens immediately with your zapper. Start the kidney cleanse. Stop using toxic products and eating toxic food. If you are being effective, the lymph nodes will begin to shrink in a few days, relieving the groin pain. If it does not come back, you probably eliminated the main cause. But if it recurs, try to diagnose it accurately. Test yourself for HIV and AIDS and then to pet saliva, dairy products and other disease specimens. Stop reinfecting from humans or pets or dairy food. Assist your body by cleaning up your dentalware, and environment. Check all supplements for toxins before using them on a daily basis. (If they show up in your white blood cells a few minutes after eating them, there is a toxin.) If your groin pain doesn't go away, you probably missed something!

There are other causes of groin pain, though, such as **hernia**. A physician will help you identify it. Have it surgically repaired. The Shouldice Hospital[7] has the best surgical record and will disclose their statistics! You won't even need full anesthesia there.

Pain from the **ovaries** is often felt near the groin. Sometimes a large cyst in the ovary puts pressure on the sensitive nearby organs. The formation of cysts, *cystic ovaries*, is a common condition of cats, too. Obviously, something is not right in the ovaries.

---

[7] Shouldice Hospital, 7750 Bayview Ave. Box 370, Thornhill, Ontario, Canada L3T-4A3, telephone (416) 889-1125.

Ovaries make hormones: **progesterone** and **estrogen**. If bacteria (like *Gardnerella, syphilis, gonorrhea*) are living there, the ovaries are handicapped and may under-produce or over-produce some hormone. The first treatment should be to kill parasites, especially the flukes. Then kill all other parasites and bacteria, especially *Gardnerella* and enteric bacteria which can migrate easily from intestine to ovary. In spite of all this, the cyst may not shrink. In order to shrink the cyst you must determine what is filling the cyst. Then stop filling it. The cyst will eliminate itself and shrink.

Many kinds of pollution can fill an ovarian cyst. Test for CFCs and PCBs. Gold is another favorite. Particulate pollutants like asbestos and fiberglass are often put into cysts by your body. Your body is wise. If these can't be eliminated through the kidneys or bile, it will at least keep them all together (in the form of a cyst) the same way a toxic dump spares the rest of the landscape. As long as you are adding to it, it cannot get smaller. Fortunately, your loyal white blood cells are trucking toxins away from your cysts every minute of every day and night. All you need to do is stop adding. Remove dental mental, clean up your body, diet, and environment.

You will notice shrinking of cysts in three weeks. What you actually notice is absence of pain, implying shrinkage. Meanwhile pain relief by killing bacteria, herbal ovarian assistance (try wild yam), chiropractic, pain killers are all useful. Decongest the area by means of a kidney cleanse. If your cyst does not shrink you have missed the pollutants. After it does shrink, stay on a regular program of parasite killing, herbal or electronic, and improved lifestyle.

Ovaries may be giving you pain even without a cyst present. By cleaning up parasites and pollutants you can eliminate it quickly; much more quickly than when a cyst has formed.

Synthetic hormones (Provera,™ Premarin,™ Ogen,™ etc.) are often used to clear up ovary problems of various kinds. Don't continue to use them when the need no longer exists. Although they have low toxicity, there are disadvantages such as the need for liver detoxification, and risk of heavy metal pollutants. Cancer acceleration has been seen when taking estrogens.

Low Back Pain

We have been told that lower back pain originates in an inherited weakness of the spine at its base because we humans walk upright instead of on four legs. And we have been told that the bony hooks that keep the spine aligned are flatter in some families, making it harder for them to hold the spine together. We are also told that "proper exercises" could have kept this part of our bodies strong so lower back pain could be avoided.

These theories become obsolete when, without surgery or exercise or change in posture, lower back pain can be made to disappear quickly and permanently.

Acupressure massage and chiropractic can bring "miraculous" relief. The most severely crippled lower back pain sufferer can shuffle lamely into a chiropractor's office and walk out normally, without pain or painkiller after treatments. So although there has been slippage of disc or spine, apparently it goes back into place rather easily.

If muscle relaxation is the clue, we must ask why these muscles spasm so easily. Any muscle spasms if you irritate or injure it suddenly. In fact, your whole body spasms and flinches if a sliver or bit of broken glass is in your shoe. If you remove these objects, the leg can walk normally.

Oxalic acid crystals are as sharp as broken glass. Use the kidney cleanse (page 549) to dissolve them and other stones. All lower back pain can be cured by removing the sharp crystals in the kidneys. It takes about three weeks to dissolve them. In some very severe cases, it may take six weeks.

Whether you have suffered a year or 20 years, the permanent cure is only weeks away.

Our bodies make eight or more different kinds of kidney "stones." The oxalic acid variety is associated with sharp stabbing pains. In its effort to eliminate this extremely vicious acid your body neutralizes it with calcium first to make calcium oxalate. Your kidneys can keep a bit of calcium oxalate in solution but not a lot. The excess hardens into crystals. A glass of regular or iced tea (not herb tea or green tea) has about 20 mg[8] of oxalic acid—way too much for kidneys to excrete. Tea is a toxic drink, not to be considered a beverage. Chocolate is very high in oxalate, too, and should not be used as a beverage (as cocoa).

Children should never drink tea or cocoa. Their delicate kidneys should not be faced with the daily burden of excreting large amounts of oxalic acid. And calcium used to neutralize oxalic acid is wasted. Calcium is a precious nutrient. It should be conserved for children's bone development.

---

[8] Taken from Food Values 14th ed. by Pennington and Church, 1985.

It isn't necessary to find which variety of kidney crystals are causing your muscle spasms. Different herbs dissolve different kinds. And by combining them into a grand herbal mixture you can be dissolving all varieties at the same time.

Wherever oxalate crystals have formed, a particular bacterium, *Proteus vulgaris*, can be found. Does that bacterium somehow thrive on oxalate crystals? Or even help them form? Does *Proteus* itself contribute to lower back pain? Is lower back pain in reality two pains in one—the sharp jabbing of glass-like particles plus the inflammatory effect of bacteria? Fortunately, you can kill *Proteus vulgaris* electronically.

By using your new diagnostic skills, you can test your kidneys for crystals. The kidney stone varieties I have tested for are: **calcium oxalate, uric acid, cysteine, cystine, monocalcium phosphate, dicalcium phosphate, tricalcium phosphate.** All these varieties can be dissolved by the herbal mixture. But all can be formed again in a week!

To prevent **oxalate** formation stop drinking oxalic acid (eating oxalate rich vegetables is not significant—spinach, chard, rhubarb and sorrel all have their place in the diet). Also take magnesium and B_6 supplements (as directed in the kidney cleanse).

To prevent **phosphate** crystals from forming, reduce phosphate consumption and drink milk as a calcium source. Keep your kidneys squeaky clean with herbs and copious water drinking. After drinking one quart of sterilized milk, two pints of water, one-half glass of homemade fruit juice and one-half glass of vegetable juice, there is little desire for additional beverages.

I have no understanding of what may cause **cysteine** or **cystine** stones (the genetic theory does not explain them either, considering that people without *cystinuria* make these stones).

Since they are sulfur-containing, and I have seen them appear after taking sulfa-drugs, it may be wise to avoid use of sulfa-drugs if you have a choice, or go on the kidney cleanse afterward.

If you have severe lower back pain you probably have several kinds of stones. Some persons have all seven kinds!

Rosie Zakar, age 30, came to see us because her mother was cured of lower back pain so severe she could do no housework for 30 years. Rosie had the usual crystals in her kidneys: oxalate, urate and phosphates. She was started on the kidney herb recipe. In three weeks she was so much better she would have missed her appointment if she had not wanted to cure her digestive problem and fatigue too.

Vera Vigneault, age 32, came mainly for help in getting pregnant but she already had lower back pain and mid-back pain. If she had gotten pregnant before clearing this up, she might have developed eclampsia and high blood pressure which are kidney-related disorders. She was started on kidney herbs for these. She chewed gum a lot and had bleeding gums. She stated her bad teeth were hereditary (meaning other family members had bad teeth also). For this she was instructed to stop chewing gum, start drinking three glasses of 2% milk a day and take a vitamin A&D perle. She was to floss her teeth once a day. (All floss varieties are polluted with mercury and thallium. Use monofilament fish line, 2 to 4 lb. weight.) Immediately after flossing she was to brush them with a new very soft toothbrush with five drops of 17½% food grade hydrogen peroxide. She was to avoid brushing teeth with metal fillings to reduce erosion. She was to brush them a second time without flossing first, this time with five drops of white iodine (potassium iodide) made up by the pharmacist, again avoiding the metal. She had only oxalate kidney stones and was to stop drinking regular tea, replacing it with single-herb teas. In five weeks her gums were better although she was still chewing a little gum and the "peroxy" had been too painful for her to use. Her low back and mid-back pains were gone too.

Gerhard Rogers, age 39, came for his lower back pain and leg cramps. He had mono, di and tricalcium phosphate crystals in his kidneys. His diet was changed to reduce phosphate (meat, cereal, breads, pasta, carbonated beverage) and increase calcium and minerals. He was to drink three glasses of 2% milk a day and to start the kidney herb recipe. In 25 days he had only minor improvement. He still had phosphate crystals. He was afraid to drink milk because he had heard so many bad things about it. He was told to boil it first to eliminate these “bad things”. A toxic element test showed a buildup of copper, arsenic, cobalt, cadmium, lead, thallium, vanadium and radon. This could easily explain his leg cramps, headaches and sleep problem, too. The arsenic came from pesticide, cobalt from detergent, thallium and copper from tooth fillings. The vanadium was fixed by having the gas pipes tightened, and radon could be reduced by improving ventilation under the house. He was thankful for the information and set about cleaning up his body and environment.

Alberta Mellos age 52, came in for lower back pain and upper back pain. It was explained to her that lower back pain was simply due to tiny stones cutting into her tissues but upper back pain was due to gallstones. She could clear her low back pain first. The kidney test showed she had oxalate and cysteine crystals. She was started on the kidney herb recipe. Nineteen days later she arrived with a cold but stated that her low back pain was gone.

Glenn Dirk, age 62, called on the telephone to say his urination had stopped, probably due to kidney stones. This had happened once before and now he was in a panic. He started our kidney herb recipe the same day and passed 117 stones the same night without bleeding or enough pain to need painkiller. After this, he could focus on his prostate enlargement and pain with sitting. He had intestinal flukes and other stages in his prostate gland as well as in his intestine. He also had *Clonorchis* (human liver flukes and their eggs) in his prostate. He had carbon tetrachloride methyl butyl ketone and TC Ethylene from food pollution accumulated there too. After stopping grocery store beverages and killing parasites with a frequency generator, he could urinate normally, freely and without pain.

Lower Abdominal Pain

The lower abdomen on the left side has the sigmoid colon as it comes down and bends. This is a favorite location for larger parasites to settle permanently. Flukes, roundworms, parasites of all kinds and their attendant bacteria and viruses can be felt if they produce gas and pain. Sometimes they live perfectly quietly, seemingly in harmony with us.

Moving the bowel more frequently expels them repeatedly and prevents their numbers from getting very high. Nature may help you with this by setting up diarrhea. Diarrhea is your clue that intestinal freeloaders are present.

The small intestine leads into the colon at your lower abdomen on the right side. At the junction is the ileocaecal valve that prevents backwash, and the appendix. The ascending colon goes up your right side then becomes the transverse colon that crosses your abdomen at the belly button level. The colon descends on your left side, leading into the sigmoid.



Fig. 19 Colon.

E. coli and *Salmonella* and *Shigella* are “enteric” (they live in your bowel) bacteria that can give you severe abdominal distress and pain. In fact, you can become a chronic sufferer. They can live on hands and under your fingernails, so reinfection from yourself is the most important source. Never, never touch your fingers to your lips. Most importantly, don't try to stop your frequent bowel movements. They will stop on a dime when your parasites and bacteria are dead and gone.

Other sources of *E. coli* are personal water bottles, other people's hands, hands that have changed baby diapers or cleaned bathrooms.

Hands do everything. To eliminate their threat of reinfection, cut out the section on hands (page 397) and paste it on your refrigerator.



Fig. 20 Keep personal water bottles sterile.

Stomach Pain

Our dairy foods are polluted with *Salmonella* and *Shigella* bacteria. It is impossible to operate a dairy without getting some cow manure into the milk. Although udder wash contains antiseptic it does not kill all manure bacteria. Later, when milk is pasteurized, many heat sensitive bacteria are killed like the “friendly” *streps* and *staphs*, but not all the harmful *Salmonellas* and *Shigellas*. Some survive to colonize the milk, then later infect the consumer. Only milk that is sterilized is safe. A commercial source of sterilized (safe) milk can sometimes be found on the shelf (unrefrigerated). If it had any bacteria, it would not survive shelf life for more than one day!

You may not notice any discomfort from drinking milk, buttermilk, or eating yogurt without sterilizing it. Your stomach acids may be strong enough to kill them, or your liver able to strain them out of your body fluids and dump them, dead, into your bile ducts. Or they may live quietly in some part of the bowel where you feel no effects. Sterilize all your dairy foods by heating at the boiling point for 10 seconds, even if you have no symptoms.

If you are intolerant of milk it doesn't mean that you are lactase deficient, but that you are unable to kill any *Salmonellas* and *Shigellas*. These, in turn, can make you lactase deficient via frequent diarrheas. You can correct this situation by not eating any more bacteria. Give your body clean food, as intended by nature. Don't eat any deli foods, don't eat salad bar food or restaurant food unless it has been baked or cooked. Never eat chicken or red meat at restaurants. They are not thoroughly cooked.

As soon as a new abdominal pain or discomfort, or a gassy condition appears, zap bacteria and try to eliminate your bowel contents. Use the herb, *Cascara sagrada* (follow directions on label) as a laxative, or Epsom salts if necessary. Also start the Bowel Program (page 546).

If you have chronic abdominal problems, make sure you eliminate the bowel contents two or three times a day. There are herbs that can kill enteric bacteria, known to our ancestors of various cultures. **Echinacea** was a treasured herb of American Indians. **Goldenseal** is another favorite. **Turmeric** can kill *E. coli* and some *Shigellas*. **Fennel** can also kill some. But a single dose of Black Walnut Tincture Extra Strength seems to do the most. Make it yourself if possible (see *Recipes*, page 543).

If your body has lost its ability to kill *Salmonellas* and *Shigellas*, all the antibiotics and herbs and good bowel habits cannot protect you from these ubiquitous bacteria. You could ask how you lost your natural protection from them. There is evidence that common **antibiotics** that kill *Streptococcus* and *Staphylococcus* varieties are responsible.

A fraction of your bowel bacteria should be the friendly *Strep. lactis* and *Staph. epidermidis*. After repeated doses of penicillin-like antibiotics (that you may be taking for your strep throat) they are eradicated along with the “bad” *Strep. pneumoniae* bug. No amount of acidophilus culture (which contains active *Lactobacillus*) can replace these *Streps* or *Staphs*.

In mice, it takes a million Salmonella bacteria to start an infection. After giving them streptomycin, it only took 10 bacteria to infect them![9] Your intestines are similarly handicapped after antibiotics, and allow even very small amounts of *Salmonella* and *Shigella* to escape and multiply!

Try to get some natural killing power back. This means improving the stomach's ability to produce acid and the liver's ability to make bile. In turn, this means getting the toxins out of the stomach and cleaning the liver. Certain toxins accumulate in the stomach when the liver and kidneys can't keep up with elimination. Arsenic is a prominent stomach toxin. Get all sources of arsenic removed. Freon is another stomach toxin. Switch to a non-Freon containing refrigerator.

The metals from dentalware: mercury, silver, copper, thallium, first are swallowed and then land in the stomach. Clean up your dentalware. Toxins you inhale such as asbestos, formaldehyde, fiberglass, also are coughed up and swallowed to accumulate in the stomach. Test for them and clean up your environment. Any stomach can recover a significant part of its function by cleaning it up. Even though you regain your tolerance toward minute bits of filth in dairy products, do not go back to unsterilized milk products.

Appendicitis

The lower abdomen on the right side has the valve that separates the small intestine (*ileum*) from the large intestine

---

[9] Sherwood L. Gorbach, M.D., Perturbation of Intestinal Microflora, Vet Human Toxicol 35 (Supplement 1) 1993.

(*caecum*) called the *ileocaecal* valve. It is a common trouble spot because large parasites can attach themselves behind it and keep themselves safe from elimination. (A parasite's biggest worry is your elimination.) It is a favorite location for pinworms in children. It is near this point where the appendix attaches and this, too, is a favorite location of pinworms. With an appendix full of pinworms and their bacteria, is it any wonder when it gets inflamed and causes pain?

Appendicitis refers to inflammation of the appendix. Often, the pain isn't felt over the appendix but over the navel (this is an example of pain being caused at one location but felt at another; it is called *referred pain*). If there are any suspicions of appendicitis, zap pinworms and all enteric parasites and bacteria immediately. Because the current does not penetrate the bowel contents very well, zap every day for two weeks and take 2 tsp. (½tsp. for children) Black Walnut Hull Tincture Extra Strength one time. Make sure bowel movements are regular after this (see the Bowel Program, page 546, for hints) and hands are washed after bathroom use and before eating. Keep fingernails short for the whole family.

If appendicitis does not clear up it can lead to a burst appendix, spewing the dreadful contents into the abdomen. Kill pinworms and roundworms and enteric parasites regularly (once a week) in children. Keep pets on a regular diet of parasite-killing herbs.

Urinary Tract Pain

Urinary tract infections, including bladder, kidney, and urethral infections, are easier to clear up than to test for. Start by drinking a half gallon of water a day. Put yourself on the kidney herb recipe (page 549). This will dissolve the tiny crystals where bacteria hide and multiply.

Common urinary tract pathogens are *Gardnerella*, *Proteus, Trichomonas, Campylobacters, E. coli*, and *Salmonellas*. Sex will give you an instant dose of your partner's urinary tract bacteria. Make sure both of you clean up the urinary tract by zapping and doing the Kidney Cleanse.

Irritable Bowel Syndrome(IBS), Colitis, and Spastic Colon

are all conditions that combine parasite and bacterial problems plus an allergic trigger. If dairy foods trigger yours, you can guess it is not allergic at all but simply *Salmonella* or *Shigella* infection. Boil all dairy foods, stop eating ice cream, cheese and yogurt which you cannot boil. If eating lettuce triggers your intestinal attack, but other roughage does not, it may be a true allergen and cleaning the liver will eventually cure it. Apples, cinnamon and other “allergic” foods can be salvaged the same way. Wheat “allergy” is due to the pancreas being full of pancreatic flukes, wood alcohol, Kojic acid (a mycotoxin), and gold.

All these bowel diseases are quite easily cured by killing all parasites, bacteria, and viruses. Since reinfection is such a big problem, give your pet away until you are completely cured. Have your pet on the herbal parasite program before bringing it back. Clean up your diet, dentalware and environment. Your abdomen will be happy once more and grateful to you for your kind attention. Remember that zapping does not penetrate into the bowel contents. It kills only the outside layer of pathogens. For this reason you should zap daily for several weeks. For this reason, too, I recommend the Bowel Program (page 546) and Black Walnut Hull Tincture Extra Strength even though you may have gotten immediate relief from zapping alone.

Crohn's Disease

is somewhat more serious because the sores are higher up in the digestive tract. This is because sheep liver fluke and pancreatic fluke are commonly the main parasites and these live in the pancreas and liver. They often spill over into the upper intestine. *Salmonella* and *Shigella* are always part of the picture, too, as are various amoebae and fungi. The treatment is the same, kill all parasites and remove all pollutants, especially wood alcohol in commercial beverages. Healing of the digestive tract is very quick, often in a week. Reinfection is very quick too, if the rule about cooking dairy foods is not observed. Keep up meticulous hand sanitation.

Michelle Whorton had stomach pain at the middle of her abdomen, not related to eating. She had occasional very bad diarrhea and also daily headaches. She was started on the kidney herbs for other reasons. Her diarrhea disappeared! We found she had *Ascaris* (probably in her stomach where they cause indigestion and inflammation). She zapped them with a frequency generator set to 408 KHz for three minutes at 10 volts. She was to be very careful with sanitation since they owned a number of farm dogs. Next seen after six weeks, she stated that all her previous problems were gone but she had a different pain in the mid-lower abdomen that got worse during her period and sent pain shooting down both legs.

This turned out to be uterine in origin, but not endometriosis. Her uterus was full of asbestos, arsenic, gold, silver, titanium, propyl alcohol, benzene, styrene, toluene and carbon tetrachloride. This would invite any bacteria toward it!

Mark Lippman, age 51, came in for his irritable bowel syndrome, hoping we would find *Giardia* and put an end to it quickly. Actually, he had intestinal flukes, beginning to invade the liver. He also had propyl alcohol built up in his body giving him a precancerous condition that needed immediate attention. The flukes were killed in twenty minutes, along with *Ascaris* (he had swollen eyelids). He was allergic to milk as could be expected with so much interference with digestion. He was immediately better and did not need to come back.

Billy Henry, a 9-year-old boy, had diarrhea daily and stomach aches. He also wet the bed. There was an indoor pet dog and a bird. Electronic testing showed he had two kinds of *Ascaris* and pinworms. His young body also had a buildup of benzene, moth balls and carbon tetrachloride that he was eating, drinking, and breathing. His bed wetting stopped after killing parasites with the herbal program. His other problems recurred until he was older and could stop licking his fingers when eating.

Tom Ochs, age 36, had chronic stomach problems, alternating constipation and diarrhea, was labeled "lactose intolerant" after an elaborate test, and finally had been diagnosed with irritable bowel syndrome. Actually, he had *Ascaris*, besides other smaller parasites. He was also toxic with cesium from drinking beverages out of clear plastic bottles. This frequently causes depression and he was happy to understand his mood changes. After changing to purer food and products and killing his parasites, he did not need to come back. Five months later he was able to drink all the milk he wanted, no longer had sinus problems and lost his IBS.

Rex Callahan, age 5, had dark circles under his eyes, numerous ear infections until tonsils were removed and tubes put in, and many strep throat infections. Clinically, he was found allergic to dust mites, pollens, and animal dander. His skin got "rashy" if he drank too much fruit juice. He had frequent diarrhea. We found he had *Ascaris* parasites. They were not difficult to clear and he was soon a new person.

David Falls, age 52, had stomach pain and numerous health problems stemming, no doubt, from his diagnosed Crohn's disease. He became allergic to the sulfa drugs commonly used in this disease. We found he had sheep liver flukes and all their developmental stages in his blood and intestine. He was put on the herbal parasite program which he found difficult to follow. Nevertheless, in three months his bowel was nearly normal and the pain in his intestine much less.

Edward Marsili age 7, had bouts of stomach pain. He had intestinal flukes and a build-up of benzene in his body. This would seriously lower his immunity and ability to fight off tiny parasites. He was using a product containing an herbal oil that was polluted with benzene. His parasites were quickly killed with a frequency generator and he was put on the herbal parasite program. One month later his stomach felt much better, but he still had an occasional stomach ache. Testing showed hookworm and rabbit fluke. His benzene was now gone so the tendency to “pick up everything” was gone too. Staying on a child's maintenance parasite program would protect him.

Kim Johnson, almost two years old, had lots of ear infections. It started at eight months so the mother took her off cow's milk and wheat. This stopped her ear infections until mid-winter. She had to be back on antibiotics and a few months ago the doctor began discussing tube implants with her since she was still on antibiotics (six months). Another ear, nose and throat doctor agreed with this opinion, but was willing to wait until Autumn. The baby had been passing a lot of undigested food and was unhappy. They were vegetarians. The baby nursed. Our test showed pancreatic fluke infestation; this would easily lead to bad digestion, especially of milk and gluten in wheat. Fortunately, she was nursed throughout, in spite of going to daycare. Simply killing the parasites (in both mother and baby) solved both problems and she did not need to come back. The ear infections were probably caused by bacteria and viruses brought in by the parasites.

Cynthia Prout, age 36, brought her three children because of their poor health. They all, including herself, had stomach problems, a lot of allergies, asthma, ear infections, and milk intolerance. One boy, age 8, was intolerant of both milk and wheat and hadn't had them for years. He was infested with two kinds of *Ascaris* and pancreatic flukes. His sister, Nola, had itching legs and headaches besides; she was toxic with bismuth and antimony (from shampoo fragrance and laundry fragrance). She also showed a build up of vanadium, implying a gas leak in the home. The youngest, age 5, had frequent stomach aches and vomiting. It was a simple matter to kill *Ascaris* electronically at 408 KHz and the pancreatic fluke with all its stages (421 through 434) after which the children did fine.

Sofia Sobel had extreme ulcerative colitis although she came for her headache. She had been on Prednisone for a month with no relief. We found she had the three large flukes plus *Chilomastix*, dog whip worm, and amoebas in her intestine (but not in body organs).

There were several house dogs. Her stomach and intestines were much too sensitive to accept parasite herbs, or in fact, anything—anything except slippery elm powder. This herb (1 tbs. made into a paste first with water and then drunk as a beverage three times a day) paved the way for acceptance of two oyster shell calcium, one magnesium and one zinc tablet. Her blood test showed high phosphate levels since she was dissolving her bones to get calcium. She added sodium alginate (¼ tsp. to a cup of vegetable broth soup) twice a day to help her tolerate the parasite killing herbs. Her children were given VMF (vermifuge or parasite killing) syrup. By the 12th day of the parasite program she no longer needed colitis medicine; her bowel movements were down to twice a day, soft and formed, but still with a little blood streaking. She loved the alginate mixed with slippery elm. She was able to eat fruits and vegetables but agreed to stay off wheat and corn until her liver was cleansed. In another week she was free from all abdominal complaints except a heaviness over the uterus, possibly due to two missed periods. The thought of pregnancy put her in a panic. She was instructed to induce her period (Emmenagogue, see *Recipes*). She was sure she wanted her period, not a pregnancy and this seemed to be her God-given right. Three weeks later she had a flare up of colitis due to *Salmonella* in food; it also gave her a urinary tract infection. This time she took Quassia herb to kill invaders in addition to the maintenance parasite program which she had begun to neglect. She had been very busy, had lots of energy and wasn't on medications. She treated her urinary tract infection with betaine-hydrochloride (to acidify the stomach), began using plastic utensils to reduce her nickel intake (see Prostate Pain, page 124)) and drank a lot of water. This experience taught her valuable lessons that she was eager to learn, benefiting her family and herself immensely.

Rebecca Goetz, age 53, had ulcerative colitis and her husband had Crohn's disease. She had been on Azulfidine™ and Flagyl™ frequently. Her parasites were only intestinal flukes and their stages, and *Endolimax*, an amoeba. It was a simple task for her to clear her problems by killing them and by sterilizing her dairy foods. Wes, her husband, had three surgeries to remove sections of bowel due to Crohn's disease. He now had a colostomy but was on Advil™ for pain in the rectal area. He could hardly sit. He had been tried on anti parasitic medicine (Cypril™ and Flagyl™) but they did no good. He had intestinal flukes and all their reproductive stages in his body, also pancreatic flukes, *Capillaria* roundworm, and *Diphyllobothrium erinacea* scolex. We interrupted his testing at that point. His kidneys were full of phosphate crystals— he ate no dairy products. He was started on half-doses of kidney herbs and only part of the parasite program in view of his colostomy and possible diarrhea. Two weeks later we continued testing, finding pinworms, *Haemonchus*, *Leishmania tropica*, *Paragonimus*, *Sarcocystis*, *Stephanuris* and *Trichuris* (whip worm.) Quassia was added and doses increased. His blood test showed a high thyroid hormone level (T4), contributory to over activity of his bowel He was started on goat milk, vitamin C (3 gm. daily) and B_{12} shots. He was given magnets to sit on for pain. He was toxic with cadmium, from his old tooth fillings. But in five weeks he could sit comfortably without pain pills. There was less blood in the stool. Dental work would bring him his next big improvement.

Benito Villamar, a middle age man, had severe side pain for several weeks. He was also gassy. He had sheep liver fluke and stages in his thymus and intestine. The thymus is under the top of the breastbone and is a very important organ of immune function. It is easily damaged by benzene. He did, indeed, have benzene accumulated there. He was given a list of benzene-polluted products to avoid and was started on the parasite killing herbs after killing the flukes instantly with the frequency generator. Two weeks later his side was very much better, his benzene was gone and he was eager to rid himself of lower back pain, which he also had.

Al Vickers, age 9, had stomach aches, headaches, a constantly runny nose and asthma. He was on Slo-Bid™ medicine and allergy treatment. He had a sleep problem. He also had two dogs, one rat and two hamsters. The dogs and he had high levels of *Ascaris*. He was zapped for *Ascaris* and the four common flukes (without testing). He was put on vermifuge syrup and Rascal capsules. This ended his problems and began a new chapter of better care for his health by his parents.

Tim Melton, age 16, had several colitis attacks yearly, requiring hospitalization, from third grade to the present. He also drooled constantly, needing to spit a lot. (This is due to mercury toxicity from amalgam fillings. It is better to spit out the mercury than to swallow it.) He had intestinal flukes at a high level for which he was started on the parasite program. One month later he was very much better. He had only one diarrhea session since the last visit. But he still had sharp pains under both buttocks (probably due to kidney stones). He had been an iced tea drinker and had numerous oxalate and cysteine crystals deposited. He was appalled that a common beverage could be so harmful.

Central Abdominal Pain

can be coming from the uterus, bladder, or bowel. It is difficult to tell which is the source. The first step is to simply kill enteric (bowel) free-loaders and get into good bowel habits. Gas and bloating should be gone. If this isn't the solution to the pain there may be special bladder parasites with their bacteria. *Schistosomes* prefer to invade the bladder wall. In fact, very many parasites temporarily invade the bladder because the body is trying to excrete many of them. The whole family should be cleared of these same parasites. Kill them by zapping. Pets should not be kept indoors since they have many of these parasites, too, and they are easily transmitted to us.

Interstitial Cystitis

is one of the most painful conditions described by clients. *Schistosomes* are the real perpetrators but after the bladder wall is weakened, other parasites and their bacteria and viruses accumulate here too. To regain your bladder's health all toxins must be cleared as well. Dental metal, environmental toxins, including radon, asbestos, formaldehyde, must be cleaned up. The diet, body products and home should be carefully searched for toxins. *Schistosomes* are easily zapped but easily picked up off toilet seats and doorknobs. Always wash hands after toileting: a single droplet reinfects you!

Uterine Pain

Endometriosis

Many a woman's dreams have been shattered by her inability to have a child. Endometriosis is often the cause. It starts with painful cramps at period times. They get worse and worse until pain killers are necessary just to get out of bed and move about the house. There are flukes in the uterus! Large intestinal flukes in a rather small organ! Did they migrate to the uterus from the intestine or did they develop there from eggs?

Sometimes sheep liver fluke is seen there. Once an avenue to the uterus is established, numerous other parasites move in the same direction: *Clonorchis*, the human liver fluke and even *Eurytrema*, the pancreatic fluke, can invade the uterus wall. Why have they taken up so abnormal a living place? Because the uterus has solvents in it! This is the green light for flukes. This disarms your organs so they are left helpless against fluke stages left there by the blood and lymph. Stop eating solvent-polluted foods. There are solvents in all cold cereals. Make cooked cereal. There are solvents in purchased drinking water. Drink from your cold kitchen faucet. There are solvents in grocery store bread, grocery baked goods and cholesterol-reduced foods. Eat none of these. Buy baked goods and bread at your local bakery. Stay away from "low cholesterol" foods. There are solvents in decaffeinated and other powdered mixes for beverages. Drink nothing except milk from the grocery store (sterilize it). Milk does not have solvent pollution. The hormones, antibiotics and udder wash can be tolerated—solvents cannot.

Beverages and powdered mixtures sold at health food stores are no exception. Use no powdered mixture intended for weight loss or weight gain, nor vitality supports, nor dietary supplements. They are all polluted. Some solvents (I often see methyl ethyl ketone and methyl butyl ketone) choose the uterus to accumulate in. This sets the stage for endometriosis and fertility problems. Where there are large parasites, smaller ones soon crowd in. All bring their own bacteria and viruses. *Gardnerella*, especially, is found in cases of endometriosis, ovarian cysts and menstrual problems. The flukes evidently travel from the uterus to other parts of your body cavity, distributing bits of the uterine lining as they go. Once this distribution has occurred, can the bleeding (regular menstrual bleeding) at these extra sites ever be stopped?

It stops immediately when the flukes are dead!

Your body knows how to clean up after dead flukes and does the job perfectly. You can be free of pain in time for your next period. Zap to kill the four common flukes, *Gardnerella*, all other common parasites, and urinary tract bacteria (common ones include *Proteus*, *Salmonella*, *Campylobacter*, *Chlamydia*, *Trichomonas*). Avoid reinfection by avoiding solvents! It is impossible not to pick up parasites. If your uterus has solvent in it, they will find their way to it in a day. Without solvent, they will not.

The solvents will leave by themselves. Help your body get rid of them with vitamin C and B_2 (3 grams and 300 mg. respectively, daily, see *Sources*).

To heal the uterus so it no longer attracts parasites, clear up its internal pollution besides solvents. This means mainly the dental metal that has piled up and environmental toxins such as asbestos, arsenic, fiberglass, and formaldehyde. Gold and silver are especially attracted to the uterus. Don't wear gold rings or any metal jewelry touching your skin anymore, and, of course, get all metal out of your teeth. Never try to get pregnant before you have cleared up endometriosis.

The advice given by obstetricians to get pregnant to solve your pain problem is most unwise. Indeed, pregnancy changes your body's metabolism and without periods you get pain relief. But it seems much too risky to grow a baby in an infested, polluted uterus. Fear of birth defects is an intelligent fear. Be careful not to get pregnant while you are killing parasites and getting mercury removed from your teeth.

Healing starts as soon as all the parasites and pollutants are gone.

Joanne Biro, age 22, had severe cramping pain with her periods, diagnosed as endometriosis. She had adult intestinal flukes and the *cercaria* stage in her uterus. She had a xylene (solvent) buildup in both her brain (cerebrum and cerebellum) and uterus. She was started on the herbal parasite program following the kidney cleanse. Her next period was pain free. A check up showed she was free of flukes but had thallium in her immune system. Dental cleanup was next on her agenda.

Denise Leyva, 22, was on birth control pills to control the growth of endometrial tissue. She had laser surgery previously. She had hexanedione and methyl butyl ketone buildup in her uterus supporting the intestinal fluke and its eggs in the uterus. There were also some sheep liver flukes and human liver fluke stages there! She was advised to stop eating cold cereals and commercial beverages and kill the parasites immediately. She had no recurrence.

Anita Pierce, age 32, had numerous surgeries for her endometriosis. She also had chronic fatigue syndrome, and several allergies. She had two beautiful poodles in her home. She could not part with them so she gave them the pet parasite herbs faithfully. She had intestinal flukes, tapeworm stages, *Ascaris* and various other flukes in the uterus. She had all her dental metal removed and home detoxified. Her body was teeming with *Nocardia* and Epstein Barre Virus (EBV). In spite of repeatedly killing the flukes and bacteria with a frequency generator and making herculean efforts she was no better off eight months later. She was unable to solve the problem of reinfection from her dogs.

Christine Solton, age 27, had extremely heavy and painful periods and didn't stop bleeding between periods. A large cyst had been seen by X-ray in the uterine wall. She also had constant bladder pain. Both problems kept her in the bathroom most of the time (90 visits/day). She had the intestinal fluke in her uterus (probable cause of cyst) and *Schistosoma haematobium* (bladder parasite) throughout her body. She was started on the parasite program and in one week her bladder pain was under control but bleeding (from the cyst in uterine wall) continued. *Schistosomes* are very contagious, probably even from toilet seats and the house dust of an infected person. She had them again three weeks later. This time she zapped them and got instant relief. Her bladder and uterus were both full of propyl alcohol, tooth metal, fluoride, cobalt, zirconium, aluminum, antimony, cadmium, and formaldehyde. She was delighted, though, to understand her problem and made the dental appointment.

Contraception

There is an excellent pamphlet available at health food stores, called Wild Yam for Birth Control Without Fear[10] that informs that 3 capsules taken two times a day provides reliable (perfect) contraception provided you give it a two month head start. Also, an emmenagogue recipe is on page 546.

The Silent Cervix

The cervix is a big "trouble spot" for women just as the prostate is for men. It seldom lets you know with pain, however, that bacteria or parasites or toxins are present. Sometimes a brief needle-like pain does alert you to something going on there, but it is easy to miss. The cervix is constantly secreting a little bit of mucous and this helps it stay clean but why give it mercury and copper and gold to secrete? Many a fertility problem has been solved by stopping the toxic pollution of uterus, ovaries, and cervix. Clean up your dentalware and clean up your diet and environment.

---

[10] Willa Shaffer, published by Woodland Health Books, PO Box 1422, Provo, Utah 84603.

Kill parasites and bacteria regularly, every week, with the herbal recipe or by zapping. You should have no pain with menstruation, no bloating, fatigue or headaches. A PAP smear test should always be “good”. If it isn't, hurry to the rescue of your cervix.

Menopausal Symptoms, Hot Flushes, PMS

Insomnia, irritability, PMS (pre-menstrual syndrome), depression, anxiety, nervousness, are all not to be expected at and after menopause. They may certainly be caused by hormone imbalances. It is these imbalances that are not normal.

NO menopausal symptoms are normal

After the ovaries are done with their cycles of estrogen and progesterone production, the **adrenal glands'** hormone production was meant to “kick in” and make up any deficit.

During your fertile years, you were meant to have a peak of 100 picograms/milliliter (pg./ml) of estrogen on day 9 and day 22 of your cycle. Progesterone, on the other hand, only peaks once, on day 22, and it should reach a level 20 to 100 times as high as estrogen! After this ends, your adrenals can still keep your hormone levels regulated. Typical values are 20 pg./ml estrogen and, again, 20 to 100 times as much progesterone. Keeping these two hormones in balance is just as important as the actual amounts. **20 pg./ml estrogen is enough to prevent menopausal symptoms** including hot flushes, and to give you heart protection and bone density protection. Taking synthetic hormones usually gives you exactly such levels. But if your own adrenal glands can supply them, surely it is a better approach. (A blood test can tell you your levels; do it on day 21, 22 or 23 before menopause, after menopause the day is not critical.)



daily estrogen levels

daily progesteron levels

Fig. 21 Estrogen and progesterone levels (pg./ml).

Why aren't your adrenals producing them? Because they are hampered by parasites and pollutants! Kill all the parasites, bacteria and viruses, especially *Gardnerella*, *Proteus*, *Chlamydia*, *Campylobacter*, *Neisseria*, *Treponema*, *Salmonella*. Use the zapper.

Notice that these are also the favorite urinary tract bacteria! This makes good sense, because the adrenal glands sit right on the kidneys and would be geographically close to the kidney bacteria. To avoid getting them back, do a kidney cleanse (page 549) to remove all crystals where they might hide.

After this, hot flushes can be suddenly gone. If not, continue the cleanse. Meanwhile, do some permanent lifestyle improvement. Start drinking two pints of water between meals plus water and milk (sterilized) at mealtime.

Don't drink cranberry juice with its copious *hippuric acid* and its solvent pollutants. You won't need such insufficient help after cleaning up your body, dentalware, and environment. Besides giving you a better hormone supply, your newly revitalized adrenals will get you through stress in better shape and keep your blood pressure normal.

If bacteria are not kept down they will begin to invade other organs. *Gardnerella* goes to ovaries to feast on the corpus luteum after ovulation. This keeps the corpus luteum from making enough progesterone and PMS results.

Menstrual problems and PMS, in general, although they may not be pain-causers, are a sign that all is not well with the uterus and ovaries. Go on a cleanup program. Kill your invaders with herbs or the zapper. Clear up your toxic accumulations from dental metal and environmental sources.

Don't be surprised by a pregnancy! This is not the time to get pregnant, though. If you wish to get pregnant, clean up your body first, being very careful to prevent pregnancy during this time. If this is not under your control do your dental work first. Since every cleanup job increases your fertility, it is best to get the mercury, thallium, copper and nickel out of your body before your risk of conception is raised further by making other improvements. Many an amalgam replacement job had to be halted in the middle due to pregnancy! Couples just couldn't believe they could have a child as a result of cleaning up their bodies so they were careless in spite of my warnings! **A dentist will not take out mercury during pregnancy.**

Nicole Truett, 40ish, had PMS before her periods. She was a returning student and couldn't afford to feel emotionally upset. She also had recurrent yeast infections, *Herpes* and panic attacks. She complained that her thinking was weird, although she was an excellent student (she got her birth date wrong on our office forms!) She had high levels of mercury and we suggested dental work immediately. Two months later she was feeling much better and had all metal removed but was experiencing a slight return of symptoms which panicked her. She still had *E. coli* and *Bacillus anthracus* at four tooth locations, giving her chronic sinus symptoms. She needed her cavitations cleaned. Four weeks later she described how she had gotten immediate emotional relief after two cavitations were done. Our solvent test showed methyl butyl ketone, benzene and carbon tetrachloride (which we found in her Mountain Valley Arkansas Spring Water). They were lowering her immunity giving recurrent Herpes and yeast problems. These disappeared in a week. She was so happy to find the cause of her problems and yet so angry at the nature of the cause that she planned to write to the water company. We need more such environmental activists.

Monica Koziol was on Ibuprofen^{TM} for menstrual cramps. She also got a severe sugar craving and minor depression and headache with her period. She was toxic with silver, copper, platinum, mercury and lead. She also had hookworms, pinworms, human liver fluke and cat liver flukes infesting her. A hormone test showed very low estrogen (57.6 pg/ml) probably due to all these interfering factors. She had all the metal from her fillings replaced and killed parasites with the herbal recipe. This gave her regular normal periods for several months. She decided to get pregnant but couldn't. A follow-up showed she was full of parasites again. She had stopped the maintenance parasite program. She resumed it and began kidney and liver cleanses to get longer lasting benefits.

Barbara Ashby, age 43, had suffered for 1½ years from menstrual pain. She had oxalate crystals in her kidneys and was started on the kidney cleanse. She followed this with the parasite program and dental metal replacement. Then she cleaned her liver and after three cleanses (she got over 1,000 stones the first time!) she said she felt great again.

Terri Entzminger, age 16, had a long list of health problems including painful ovaries and painful periods for which she was put on birth control pills by her doctor. She had several bacteria in her genital tract: *Neisseria gonorrhea*, *Plasmodium cyano*, *Staphylococcus* *aureus* (also at tooth #28 which had a plastic filling), *Streptococcus pyogenes* (also at tooth #28). A parasite test showed intestinal fluke adults in the uterus, not in the intestine or liver. There were also fluke *cercaria* here. She was started on the parasite herbs. Three weeks later there was no improvement. She had a rabbit, a dog and a hamster. She was to get them all onto the pet parasite program. Her diet was changed to exclude solvents. Six weeks later her periods were "great", she did not need the pill and she was keeping the whole household on a maintenance program killing parasites. Three weeks later she had cramps again. This time it was sheep liver fluke in the uterus. She probably got them from the snails in her fish tanks. She was off the maintenance program and drinking caffeine free cola again. This would fill her with solvents that make fluke disease possible. She killed them all with a frequency generator and decided to be more vigilant over parasites as long as she was such an ardent animal lover.

Azar Moya, 57, was on Premarin™ and Provera™ for hot flushes and emotional extremes, Synthroid™ for the thyroid, Xanax™ for nerves and sleep problems, something for diarrhea and something for depression. In five months she needed none of it. She had done a liver cleanse by then and got a commode-full of stones (about 1,000), she had changed her plumbing, got rid of the water softener, killed parasites and cleansed her kidneys. She still had sinus problems and some arthritis and was planning dental metal replacement and cavitation cleaning to clear them up too.

Infertility

An ominous sign in any species, infertility is not just another disease or "problem."

When birds' eggs don't hatch their species is doomed. So we learned from the DDT experiment humans did with birds in the 1960's. The DDT changed the thickness of their egg shells so they cracked when the mother bird sat on them. All changes are experiments whether intentional or unintentional. Nature by itself produces sweeping changes, too, such as droughts, wind storms, fires, ice ages, but usually living things had time or mobility to adapt to them. When there wasn't time, and they couldn't run away, the species went extinct.

Are we humans an exception to this rule of adapt or perish? Nobody feels more helpless and hopeless than the infertile couple. They can not run away, time is limited, and obviously adaptation is not occurring. More likely their lineage will perish. The couples' only wish is “Give us one child, now.” Surely, it is their birthright, as it is any living creatures', to reproduce.

Can we relax with the assurance that our intelligence, through the arm of science, will always rescue us? Are test tube fertilizations, fertility drugs, Cesarean sections, incubators for premature babies all triumphs for science? No, they are signs of reproductive failure for the human species.

When the concern is overpopulation of this planet, reproductive failure might seem less ominous. Maybe it's no worse than the natural way any species curbs its growth rate. Maybe only those who can survive parasitism, pollution and immune deficiency should survive in order to strengthen the species. But when reproductive intervention becomes a necessity, not an option, surely the danger signal is present as it was for the DDT'd birds who saw cracks develop in their eggs. The solution to our reproductive failure is not to find ever more artificial ways to conceive, to give birth, and to care for damaged babies. The solution is to fix the old fashioned way; to safeguard the natural way.

If you are unable to conceive or to provide viable sperms use an intelligent approach. Remove the obstacles. **The obstacles are parasites and pollutants, the same enemies of health we have seen before.**

Kill all large and small parasites with a zapper and the herbal parasite killing program. Don't try to keep a pet parasite free, give it away. Living close to another species is a luxury you can't afford at present. The pet can live with its parasites, you can't. Remember to kill bacteria and viruses too, especially *Gardnerella, Neisseria, Treponema,* the ancient enemies of human reproduction.

Is it safe to kill parasites if you might be pregnant?

The electronic way of killing parasites is safe if you use a frequency generator. The frequencies of parasites and bacteria are far away from human frequencies. The treatment with each frequency is short. There are no side effects.

The zapper has not been tested and should not be used during pregnancy.

The herbal way of killing parasites has been used by pregnant women without bad effects but this is not enough safeguard. I recommend waiting until the baby is born if at all possible. The treatment is long and intense. The growing baby is exposed continuously to herbs. Perhaps this is preferable to the toxins produced by parasites. You must use your own judgment. Obviously it is wiser to take a chance on herbs than to take a chance on inheriting AIDS or “genetic” diseases.

Part two of regaining your reproductive freedom to have a child is removing pollutants. Gold, silver, copper and mercury can accumulate in the reproductive organs, wrecking the delicate hormone balance between estrogen and progesterone, or wrecking the motility of sperm. Research has not been done to search for dental metal in the uterus, ovaries and testicle of infertile couples. You can do this research yourself. Slides of ovary tissue cost less than $10.00 as do other parts of the reproductive system. Search for dental metal yourself. Remove all dental metal from your mouth, and replace it with metal-free composite. Extract teeth with root canals.

A Word Of Warning!

Be extra careful with contraception during the dental cleanup. You could get pregnant the very next day! **This is no joke.** It is a serious hazard to conceive a child while mercury is loose and rampant in your body from the removal process. It may be a higher risk than leaving it untouched. If you are pregnant no dentist will want to finish the job of mercury removal! **Don't try to get pregnant yet.**

You may have tried fertility pills, in vitro fertilization, and other methods for getting pregnant over a ten year time period, all to no avail. Then you start cleaning up your body and taking your mercury out and suddenly you are pregnant before the job is complete! It may seem unreasonable and illogical to have to be careful after ten years of no worries, but play it safe.

If you fail to observe this warning and do get pregnant too soon, you may pray for miscarriage. Otherwise, take vitamin C and thioctic acid and hope for the best. Men should add daily zinc and arginine (60 mg. and 450 mg, respectively) to their diets. Both men and women should add vitamin E (200 mg.), a prenatal multivitamin and multimineral tablet, eat freshly grown vegetables for folic acid, and add vitamin C (at least a gram daily, see *Sources*). **No other supplements**! Supplements polluted with heavy metals or solvents do more harm than good. If you are not sure of their purity, test one by eating it and searching for it in your immune system five minutes later. If it is there, it is harmful; eat no more.

Nausea

of pregnancy is the scourge of expectant parents. After waiting hard and long for the desired pregnancy, the mother-to-be feels rotten, salivates and gags at the thought of food, and wants no more sex. Maybe sex is ill-advised during pregnancy, no matter how reassuring the male or male-oriented obstetrician is! Maybe salivation is actually mercury excretion being attempted by the body. Maybe nausea is all about keeping toxins out of the body and away from the developing child. These are intriguing possibilities, worthy of your research expertise.

A few decades ago the treatment for nausea was a weekly B_6 and B_{12} shot. Ask your obstetrician for this to see if it helps.

An older, herbal remedy was cinnamon tea: 2 tbs. cinnamon (bark or powder) in 2½cups boiling water, steeped for 10 minutes. Strain and add honey to taste. Dose: ¼ cup three times a day before meals.

Nausea invites starch eating—pasta, potatoes, rice and bread. Starches can absorb. Perhaps they absorb the noxious substances causing nausea. Make sure you add vitamin C to grains. In any case you must still eat additional nutritious food to grow your baby. In spite of craving a pickles/chocolate pudding/carbonated beverage lifestyle, you must eat mainly good food. Craving can take strange turns. Search for the taste you crave in good food and in long forgotten childhood foods.

These are all the fertility cases I saw in a year's time. None were left out in order to hide failure. Assess the success rate yourself:

Domilita Renshaw and her husband had been trying for six years to get pregnant. Both had been tested and treated in assorted ways. Domilita's period was irregular, a sure sign that all is not well in the area of reproduction. I gave them the usual warning about not risking pregnancy during their deparasitizing and depolluting procedures they both would be going through. Her hormone test showed slightly high (125 pg/ml) estrogen levels for day 22 (if it really was day 22!) and higher still if it was not yet day 22! Obviously, something was irritating the ovaries into overproduction of estrogen. She had oxalate and urate crystals and was put on the kidney herb recipe. She was switched to milk (3 glasses 2% a day) as her primary beverage besides water. She was toxic with nickel (dental metal) which would invite hordes of urinary tract bacteria, dangerously close to the ovaries. She made her dental appointment. She had sheep liver flukes and was started on the parasite program. She broke out in hives from a new hair spray polluted with praseodymium which got into her ovaries. She prepared to clean her liver for her frequent hives. Then she called to cancel her next appointment because she was pregnant (four months from first visit). Fortunately she had one visit with dentist completed. Nine months later she had a beautiful perfect baby.

Lindy Maloy and her husband had been trying for eight years to have their second child. They all had *Ascaris*, including, of course, their house dog. They wormed the dog monthly and did not want to part with it since they did not believe it mattered. They used the pet parasite program, but five months later she had higher *Ascaris* loads than ever. She also could not rid her uterus of intestinal fluke stages in spite of killing them with a frequency generator and using the parasite herbs. She remained full of solvents, bacteria and platinum from dentalware. Her endometriosis continued. They gave up.

Rosemary Peterson, age 33, had been trying to get pregnant for fourteen years. She had seven laparoscopies for endometriosis and very hard cramps with her period. She had intestinal flukes and sheep liver flukes in her uterus. There were sheep liver flukes and human liver flukes in her liver. There were intestinal fluke redia and cercaria in her saliva. The solvents in her uterus were methyl butyl ketone, acetone, carbon tetrachloride (from drinking store bought water), styrene (from drinking out of styrofoam cups), xylene (from carbonated beverages) and decane (from cholesterol-reduced foods). She also had a chronic yeast infection, treating it constantly with Nystatin™. She killed the flukes and yeast electronically before leaving the office and started herself on the parasite program and diet restriction. She got pregnant immediately, and did not return.

Elisabeth Tran, age 37, had tried to get pregnant for five years. She did get pregnant recently, on a special “gift” surgery program, but lost it. Her ovaries and uterus were toxic with mercury and thallium from polluted dental alloy. She also had barium and titanium in them, probably from lipstick. We did not see her again, we hope she solved these problems.

Christopher Gravely, a young man of 26 and Frederica, 22, promised faithfully not to get pregnant until their cleanup was complete. He was found by his doctor to have slow moving (low motility) sperm. He was robust and healthy looking but suffered a lot from low back pain—a clue to swarms of bacteria in the lower abdomen. An electronic search of his testicles and prostate (which had been infected once) revealed iridium, platinum and yttrium. This implicated tooth metal. He was also started on kidney herbs. Eight months later he had completed all his tasks, his low back and pain with urination had stopped, and this encouraged him to continue with his fertility program. We started him on thioctic acid two a day and zinc (60 mg.) two a day, switched him to an electric razor so he wouldn't have to use any chemicals on his face, and recommended that he ventilate his garage which was attached to the house, to reduce fumes in his home.

Meanwhile, Frederica, his wife, was also checked for toxic elements. She had antimony (from mascara) in her ovaries and breasts. She had sensitive painful breasts during her periods which were quite irregular. She also had indium and gallium, dental alloys in the ovaries and breasts. She, too, was started on the kidney herbs and instructed to get metal tooth fillings replaced. After two months they canceled their appointment. Frederica was pregnant! Not for long, though, and a wiser couple returned a few months later. Frederica finished her dental work. Both started the parasite program. Frederica's periods became regular. She was started on thioctic acid (one a day) plus zinc, (one a day), until her first missed period. Twelve months later they sent me their baby's picture: he was two months old.

Ginger Hart had been trying for three years to get pregnant. After an endometrial biopsy, a D&C,[11] and laparoscopy she was diagnosed with "inadequate corpus luteum." We found her ovaries toxic with nickel and europium from tooth fillings and strontium from toothpaste. She was delighted to understand her problem and set about correcting it.

Marjory Davis, age 28, had been on the "pill" (synthetic hormones) a long time but was off now and couldn't get pregnant. She actually got pregnant about one year ago but lost it at one month. A toxic element test showed her ovaries and uterus were full of beryllium (gasoline and coal oil), gadolinium and gallium. The metals are alloys of gold used in dentistry. She wore a lot of jewelry, just loved her chains, necklaces, rings, etc. But she agreed to go off all except two rings which did not have these alloys. To reduce fossil fuel fumes in the house she removed all gas cans and the lawn mower from the attached garage. They parked the cars outside. She was started on kidney herbs and promised to use contraception until she was done. She was to drink three glasses of 2% milk a day and take a magnesium tablet and stop drinking other beverages. Three weeks later her husband canceled her appointment because she was too embarrassed and delighted to call herself.

Prostate Problems

If urination is not complete, so you must soon go again, especially in the night, it is suggestive of pressure on the urethra from an enlarged prostate gland. Keeping a little urine from being voided is conducive to bladder and kidney infection, too, because bacteria soon find this "free food."

The prostate collects toxins as if it were a designated dump site, especially for nickel. Urinary tract bacteria quickly find "their" metal, nickel. Any supply of nickel will attract bacteria as quickly as crumbs and cheese attract mice. Urinary tract bacteria are making use of your urea as their food. To digest it, they first break the urea molecule apart into two ammonia molecules. It is the ammonia smell of the urine that gives away their presence. The urine should have no ammonia smell. Our bodies do not make ammonia. Only bacteria can do this! Their digestive enzyme is called *urease*. In order to do its job, this enzyme requires the element nickel.

---

[11] A surgical procedure, called *dilation and curettage*, meaning dilate the bladder with air and scrape away the inner lining.

Nickel is plentiful in the soil which is undoubtedly where these bacteria belong, breaking up and utilizing the urine and droppings left there by animals. They perform an essential task in our environment, destroying animal excrement and thereby cleaning-up the soil around us. What folly it is to load ourselves up with nickel so that in one short hop from the earth they are residing in us! Bacteria are all around us doing their valuable jobs. We cannot stop associating with bacteria. We were not meant to feed them, however. If we did not supply them with nickel, as if we were just another patch of earth, they could not gain a foothold in our urinary tract and then to the prostate.

How can we rid our bodies of nickel? This is the challenge. Are we eating dirt? A small amount of dirt can't be avoided on our food. But we can stop sucking on nickel as if it were a lollipop. Our spoons, forks and knives are made of nickel! Stainless steel is 8% nickel! Does it really come off as you eat? When you stick a knife into the mayonnaise jar, it is stained in a few minutes. Try it. The mayonnaise has reacted with the metal loosening the nickel. When you smear the knife over your bread, this film comes off and you eat it. If you were to put the knife in your mouth, now, you could taste the metal. You will later wash the knife but not before you have eaten enough nickel to supply all the bacteria in your body with the daily allowance of their essential element, nickel. Nickel is not our essential mineral. Even plants keep their nickel levels very low. But due to pollution of animal feed with it, even a hen's egg now has 3 mcg/100 gm of nickel in it.[12] To produce a nickel-polluted egg, the chicken must be polluted.

Especially infants and children should never be given metal cups or cutlery. They need all their immune power to combat the barrage of new bacteria and viruses that is emerging in this age of AIDS. Nickel is part of dirt and belongs there, not in our pots and cutlery.

Another large source of nickel is metal dentalware. It is used to harden gold! If you suffer from prostate problems, remove metal from your dentalware. Nickel is used to make bridges, gold crowns, retainers, amalgams. Exchange it all for plastic ware and composite buildups (see *Sources* for more dental information). Stop eating and cooking with metal utensils; use old fashioned wooden or sturdy plastic cutlery instead. Always use a plastic knife for butter or mayonnaise. Never buy foil-wrapped butter.

Nickel is fat soluble and is stored in your skin fat temporarily when a surge of it enters the body. Your skin oils may be loaded with nickel causing “allergies” in the skin. Male pattern baldness is such an allergy. The sweat tries to excrete it for you. Always wash off your scalp sweat to help with this excretion. The skin oils dissolve nickel from metal jewelry (sometimes leaving your skin with a greenish black color) and transport it into your body. Don't wear metal jewelry. Earring posts should be plastic. Metal watches and metal rimmed glasses should be replaced with all plastic types. Metal rings should be replaced. After lowering your total body nickel levels and your prostate disease is only a memory, you might notice scalp hair returning to sparse areas. Search around the edge of the hair line for the first returnees.

Bacteria cannot live in the prostate without nickel being present. You can cure your prostate problems with the simple tactic of stopping nickel pollution of your body. Notice that you get a fresh attack after accidentally using metal cutlery in a restaurant or eating mayonnaise-style salad with a metal spoon stuck in it. It might be wise to take a **histidine** capsule (about 500 mg., one a day for three weeks, see *Sources*) when this happens. Histidine is a nickel chelator. Taking **zinc** is helpful too (60 mg. two times a day for a month). Possibly, the nickel was poisoning zinc enzymes. Read about the benefits of **flaxseed**, too, but remember to test every product for pollutants before accepting it as a supplement.

---

[12] Food Values by Pennington and Church, 1985

Prostate problems of all kinds clear up when bacteria are zapped, the Kidney Cleanse is done, dental cleanup is done, and the Bowel Program is followed.

Richard Traylor, age 71, had suffered from prostate and urinary tract disease for three years. Scar tissue had to be removed occasionally from prior treatments of them. He was started on the kidney herbs and in two weeks (13 days) he had a considerable improvement in urine flow. At his follow-up visit we searched for toxins. He had radon, chromate, yttrium and strontium in his genital and urinary tract. He got rid of his water softener (such salts are polluted with chromate), toothpaste (strontium source) and opened the crawl space vents (source of radon). This cured these problems in less than two months. It also cured his stomach ulcers for which he had to take medicine. He was so pleased he decided to install a crawl space fan and pursue a parasite program and dental health just to see what extra health improvements he might get.

Omer Whitney, age 45, had always been a strong, healthy, hard worker. He could now barely walk, due to weakness and pains of several kinds; his prostate problems began several years ago. Our tests showed 4 kinds of kidney stones. He was started on only half a dose of the herbal recipe to give them a chance to dissolve more slowly. One month later he still had some stones although his leg cramps were already gone. At this time we found *Ascaris* (both kinds) which he killed with a frequency generator. We also found carbon tetrachloride and pentane (in decaf beverages) built up in him; also gasoline and TCE. He was considerably improved five weeks later and was quite eager to improve further. A toxic element test showed he was full of copper, antimony (from mineral ice massages), cobalt (aftershave), zirconium (deodorant), thulium (vitamin C fortified orange drink) and mercury (very high, from tooth fillings). He planned on cleaning all of it out of his body and regaining his lost strength.

Harvey Van Til, age 35, came in for his prostate and testicle swelling which began shortly after a vasectomy. He ached over the front right side of his abdomen. He was started on the kidney herbs and in four weeks he had eliminated his oxalate crystals and felt considerably better. We next found the adult intestinal flukes and human liver flukes in his prostate gland! After killing them immediately with a frequency generator and getting instant relief of pain, he got his own device and did not need to return.

Clayton Gamino, 26, had pain during urination which he interpreted as a left-over from a prostate infection he once had. He got all the metal out of his mouth, and did a kidney cleanse. A half year later he had no remaining pains and was able to father his first child.

Side Pain

Pain on the right side can come from problems at the ileocaecal valve or the appendix or the large intestine itself. It can also come from the liver which is higher up but is sending its pain message to your side. Pursue it as an intestinal problem first, killing parasites and bacteria and normalizing bowel movements with the Bowel Program. If the pain persists, especially if it reaches up the side to the



Fig. 22 The liver has a large lobe on your right side with the gallbladder tucked inside. The left lobe is smaller.

middle of the waist, it is probably due to the liver.

The liver is a large organ, mostly on the right side of the body, but with a smaller lobe on the left side. It is the chemical manufacturing plant for the body. It pulls in the food from the intestine (that you ate hours ago) and makes your body's chemicals from them. Toxic items are changed chemically into non-toxic items that the kidney is able to excrete into the bladder. Fatty things must be made water soluble for them to leave with the urine. The liver also makes bile and sends toxic items along with it to the intestine through the bile ducts. The bile enables calcium and fat to be absorbed. If the liver isn't getting much bile to the intestine, fat is left in the bowel contents and the feces will float in the toilet bowl. That is your clue to bile duct blockage.

Bile is bright green. Mixed with intestinal contents it turns the bowel movement dark brown. If the bile is not arriving in the intestine the bowel movement will stay light colored, even yellow or orange. This is another clue to bile duct blockage. Over a quart of bile should exit the body each day. Since bile is loaded with cholesterol this daily excretion of bile is a major method of keeping cholesterol levels low. If the bile ducts are choked with debris so only half as much (often only a cup instead of a quart!) bile is produced and excreted you can expect cholesterol levels to rise, and digestion to be bad. When food isn't promptly digested and absorbed the ever present, ever-ready bacteria will grab it for themselves.

> Taking cholesterol-lowering drugs should be reserved for cases where natural excretion cannot be regained.

E. coli and other intestinal bacteria, which do no harm in moderate numbers, can overgrow in a few hours to give you bloating, gas and pain. Your body produces no gas. Only bacteria can produce gas. If your side pain is accompanied by bloating and gas, you know you have a digestive problem. And that this digestive problem stems from a congested liver if the pain is directly under it or over it, or if the feces are light colored or your cholesterol levels are high. Not everybody has all the symptoms.

To clear the clogged passages of the bile ducts, you simply do the liver cleanse (page 552) over and over until the problem is gone. There is one catch. If there are living parasites in the bile ducts, they will not let the bile ducts clear themselves. They are stuck fast to your ducts as a tick can be to your skin. They must be killed before they will let go. Zap them all, or you may use the herbal parasite program, staying on a twice a week maintenance program. Only after parasites are dead (after day 20 if using the herbal program) will you get a lot of “green stuff” and be able to clear “stones” out of your bile ducts. Only one large duct at a time will clean itself. We have hundreds of larger ducts and thousands of tiny ducts feeding into the larger ones! Stay on a schedule of cleansing the liver every two weeks (unless you are ill) until your side pain is gone, your digestion is normal, and you are bouncing with energy. You may also lose some weight, but only if you are overweight.

Remember that a clogged liver does not necessarily give you pain by itself. It is more likely the bacteria in the gall bladder and bile ducts, causing inflammation there and in your intestine, that cause pain. Don't wait till pain occurs over the liver. Use whatever clues you can to diagnose your clogged condition. Or just assume it is clogged. Do the cleanse, and see if you get any stones out. It can never hurt and can help a lot.



Fig. 23 Gallstones.

Bruce Hearn, 40ish, had severe side pain for several weeks and was rather gassy. He had seen a clinical doctor who found him in good health. But we found sheep liver flukes in the intestine and in the thymus! The thymus is an immunity-giving gland, so anything in the thymus is a very serious matter. He also had benzene in his thymus (inviting AIDS). He quickly switched from drinking soda to drinking milk. He went off everything in the benzene list. He killed the flukes electronically and started on the parasite program. Three weeks later the benzene was gone, his side was very much better and he could begin a kidney cleanse for his low back pain. He hadn't cleansed his liver yet! His improvement was probably due to improving his immunity which then controlled the bacteria.

Midabdomen Pain, Stomach Pain

The colon crosses over from your right side to the left side at the midabdomen. This is also the location for the bile duct to join your small intestine. Most midabdomen pain comes from either the colon or the bile duct connections. Kill parasites and bacteria by zapping or with the herbal recipe. Improve your digestion with diet clean up (off moldy food, boil dairy products). Sometimes the midabdomen pain stems from the stomach itself. The valves at the top and bottom of the stomach are meant to keep the food in. The valve at the top where the stomach joins the esophagus is a favorite location for bacteria.

You seldom feel them here though. This is just under your breastbone. They do their work quietly. Eventually, the tissue there is so weakened, the valve can't shut tightly and food is allowed to go back up the esophagus. This is called *reflux* and you may be told to sleep with your head elevated and to eat small meals, especially at bedtime. You may be given Reglan,^{TM} a drug to help empty the stomach faster. Digestive enzymes will help empty the stomach, too, but may harbor molds. The real solution is to kill the bacteria in this area and keep them from reinvading it. Start by killing the *Salmonellas* and *Campylobacters* (zap them).



Fig. 24 Stomach, esophagus, diaphragm, gallbladder.

Within a day or so, however, the area can be re-invaded. Some bacteria are coming from your teeth! Some come from the liver! Often both sources are supplying bacteria to the stomach. The stomach allows a little bile to enter at the end of each meal, this is normal. But if the bile is full of live parasite stages and bacteria they may try to colonize the stomach, too. If there is insufficient stomach acid to kill them or if there is an accumulation of toxin in the stomach, they will get a foothold. Then they can burrow down deep to escape acid. Eventually, an ulcer can develop.

Stomach Ulcer

Often, such an ulcer is painless.

You are, therefore, not alerted to the parasites' presence until they have established themselves in good hiding places. Taking antacids, of course, works in their favor. The solution for both stomach pain and stomach ulcers is to kill parasites and bacteria, followed by dental and liver clean ups. One very common toxin that accumulates in the stomach is the pesticide **arsenic**. You inhale it right along with the flies and roaches you may be trying to kill with arsenic-laced pesticides.

Other inhaled toxins are fiberglass, asbestos, formaldehyde and freon. Your nose and mouth mucous traps a lot of these whereupon you swallow them and they glide into the stomach. Tooth bacteria and tooth metal get into the stomach the same way. You simply swallow them.

Clean up your air, don't use any pesticides (see other methods in *Recipes*). Your dentalware may be cleaned up in a few dental visits but the liver cleanses must go on for a year or two before it is reasonably clean. You may get pain relief in a few weeks but this should not derail your intention to revitalize yourself completely with a cleaned liver and stomach.

Hiatal Hernia

When bacteria have spread to the diaphragm and weakened it, along with the upper-stomach valve, food is allowed to get pushed up right through the diaphragm. Pressure in the abdomen from overeating or sitting in an easy chair pushes it up. Walk after eating. Empty the stomach before going to bed. Don't sit in recliners. Very many of us, about 25%, have a small hiatal hernia. It only hurts if it is inflamed. Work at clearing the inflammation first, to get pain relief. In time, the area will strengthen and the hernia itself may get smaller.



Fig. 25 Hiatal hernia.

Jeffy, 3½ months, had been screaming a lot ever since birth. He was very gassy. He could not be put down without starting to cry. He was congested and had colds. He was on mother's milk exclusively so his chronic *Salmonella* infection must have come from someone who was a carrier, possibly his mother, although she had no symptoms. The mother had platinum and tellurium in her milk (*Salmonella* can be transmitted in milk but this was not checked). The solution was to clean up the mother's milk by getting the dental metal out of her mouth, and washing hands before nursing. Jeffy's father had an *Ascaris* and intestinal fluke infestation. It is quite possible the baby had these also, giving him a nasty tummy ache in addition to the gas pains. The baby's older sister had screamed and cried the first nine months, too, so the parents were told it was a “familial thing.” She also had ear infections, colds and a flaky patch of skin occasionally. She, too, had *Ascaris*. They were very pleased to be able to clear up the whole family's problems by killing parasites and removing toxins.

Ruby Adair, age 14, filled a page with her symptoms. She was also chronically fatigued and had consumed enough antibiotic “to fill a room.” She had shooting pains from under her feet up her legs. A quick check revealed mercury and thallium in her immune system. Instead of being dismayed, this news filled her with hope for recovery. She arranged for dental metal replacement. Then she related her stomach “story”. While at a wedding, a year ago, she began vomiting with diarrhea. She thought it was the stomach “flu” but she didn't recover for six months and had to miss school. The psychologist thought it was emotional. She was still only attending school one hour a day. We found *Fasciolopsis*, the intestinal fluke, in her stomach wall as well as in her intestine. She started the parasite program and in three weeks her appetite was back, insomnia was gone, fatigue was better and a significant improvement was evident.

Respiratory Illness

Asthma

is a very old disease described in the ancient literature. The only progress we have made to date with this disease is to give drugs to soothe the symptoms.

Asthma is associated in **all** (100%) cases with tiny *Ascaris* larvae. As soon as eggs hatch (in the stomach, immediately after swallowing filth) the microscopic larvae travel to the lungs, not the intestines. Imagine the distress of lungs full of tiny worms! One tries to cough them up, of course, but in our misguided effort to be polite we teach children to swallow anything they cough up! Some swallowing is inevitable and the young worms are back in the stomach, this time to set up their housekeeping in the intestine. Some never leave the stomach, causing children stomach aches and, of course, a large entourage of bacteria which, in turn, have their viruses.

Most cases of *Ascaris* infestation also show *Bacteroides fragilis* bacteria which, in turn, carry the *Coxsackie* viruses (brain viruses). Whether or not these bacteria or viruses will thrive in you depends on whether you make a good home for them, namely have low immunity in some organ. The preferred organs for *Bacteroides* are liver and brain (brain tumors always show *Bacteroides*). The preferred organs for *Coxsackie* viruses appear to be tooth abscesses and brain.

Not everybody with *Ascaris* develops asthma, even though they always go through a lung stage. Does it depend on the age of the person when the infection develops? Or how many *Ascaris* are present? Or the time of year when lung infection is present?

That innocent cough of early childhood should not be neglected, as simply "croup." At the first sign of a cough, use a frequency generator set to 408 KHz, the frequency for *Ascaris*, or use a zapper. Pay extra attention to washing hands before meals. Pay extra attention to the animals nearby. Kill their *Ascaris* with a zapper and keep it up daily or put parasite killing herbs in their food.

Asthma sufferers become **allergic** to many air pollutants such as pollen, animal dander, smoke. The production of histamine in the lungs and the vast interconnectedness of histamine to allergies has been well studied scientifically. Although invasion by worms is known to result in both histamine production and high eosinophil counts (over 3), and **asthma clients typically have both**, they are not routinely checked for worms clinically! They are simply given drugs to enable better breathing. More and better (though toxic) drugs have been developed.

But you can put an end to your asthma by terminating your *Ascaris* infection. Then wash your hands and fingernails with grain alcohol, and let no more filth past your lips. Wear plastic gloves for a week to break a nail biting or finger sucking habit. For children wash hands before eating anything, even between meals; keep fingernails short.

Dogs, cats, pigs and horses all get *Ascaris*. Never, never let a child clean up any vomit or mess left by an animal. This could lead to massive infection, the kind that could result not only in asthma but **seizures**. Kill the worms in animal messes before you clean them up too. Never use your dustpan or broom. Use cardboard, newspaper or anything that you can afford to throw away with the mess. Squirt povidone iodine (available at drug stores) on the mess–even if it's outside–and cover with salt before cleaning up. Discard it in outside trash. Wash your hands with grain alcohol, paying special attention to fingernails. If you are a food preparer, you could infect the whole family if you don't wash carefully.

If there is an asthmatic in your family, the whole family should be treated for *Ascaris* with a zapper or with the herbal parasiticides. Even after everybody including the pets have been treated, pets should not be allowed in the bedroom of the asthmatic person. Asthma is more than parasitism. It is also an allergic reaction, to the pet and to other inhaled bits of matter.

Clean the air. Smoke of any kind, fragrance and chemicals of any kind, all household cleaners, polishes, and so forth should be removed. Store essentials in the garage, not the basement, since basement air rises. Clean up the whole house. Persons who must use hair spray or nail polish should do so outside in the summer and in their own rooms with the doors closed in winter. Use a chlorine filter for the water, especially at the shower. Install central air conditioning if possible, with maximum filtering (but never with chemicals added to the filter and never with a fiberglass filter) at the furnace. A room air filter (not fiberglass) is next best. Use it for an hour in the bedroom ahead of bedtime so the air currents can cease. Just moving dust around is worse than leaving it there. Never do dusting when an asthmatic is in the house. Lungs heal quickly when the air is clean and there is no reinfection. The best place to recover is outdoors away from trees and bushes or indoors with total pollution-free air conditioning (free of asbestos, formaldehyde, arsenic, fiberglass, pet dander).

As your asthma lessens, reduce your inhalers, but always keep them on hand. When you suddenly need them, try to identify your source of reinfection or allergens. Use this experience wisely. Try to understand the recurrence of your asthma. Keep notes. It may take half a year with a dozen recurrences to finally learn and conquer! It will feel great to breathe without spraying yourself and taking medicine. If it comes back a year later, figure out what is happening that's seasonal. A pine tree near the house, a flowering bush, the first mown grass? Stay away from these until you are completely healed.

There are traditional herbs for helping lungs. Grow your own **comfrey** and **garlic**. Make **mullein** tea from the dried herb (see *Sources*). Read herb books for more help. Dry some for winter use, being careful to do it right and not let it mold.

Suzanne Carlyle, 45, had asthma from infancy. She was currently on Albutesol™ spray and tablets daily. Now she was beginning to have arthritis too. She was given arginine to replace caffeine. She had two species of *Ascaris* and was allergic to cats and other animals. She was started on the herbal parasite program after killing *Ascaris*, *Bacteroides* and *Coxsackie* viruses with a frequency generator. Her lungs showed kerosene, carbon tetrachloride, mineral oil, benzalkonium (from udder wash, she was also milk sensitive), aluminum from her cookware, and aluminum silicate from her salt. She had two extra lung parasites: *Paragonimus*, a lung fluke, and *Pneumocystis*. She was immediately improved after cleaning up these sources and canceled her future appointment.

Cay Wenkert, 63, had asthma for many years for which she took Proventil™, but this gave her such bad side effects she had to stay home now and not venture out. Her lungs were full of benzalkonium (toothpaste), arsenic (ant poison under kitchen sink), zirconium (deodorant), and nickel from tooth metal. She had dog heartworm in her lungs(!), in addition to her heart where she sometimes felt pain. She had *Ascaris* and *Naegleria*, *mycoplasma*, *Endolimax* and the intestinal fluke in her lungs! She coughed up blood, after her doctor had diagnosed *bronchiestasis* recently, meaning her lungs were not capable of sweeping out the daily refuse we all breathe in. In spite of killing these and cleaning up her environment she got no improvement. She repeatedly got parasitized. She had four or five root canal teeth which she was unwilling to have pulled. Hopefully, the tradeoff between teeth and health will soon begin to look poor.

Amy Newberry, 41, had recently begun to have asthma attacks. She had been on cortisone but now was on inhalers through the day (two puffs Ventillin™ 3x/day, plus three puffs Intel™ 3x/day plus four puffs Asthmacort™ 3x/day). She was often hospitalized for attacks. She also had stomach trouble and sinus problems (had pneumonia recently). She had *Ascaris* larvae, *Endolimax*, *Naegleria* and *Acanthocephala* in her lungs! She also had arsenic and palladium (tooth metal). Going onto homeopathic medicine for stuffiness helped her avoid some hospital visits. It took several months (5 visits) to track her arsenic source to the bedroom carpets (stain resistance!). After steam cleaning it herself and doing a liver cleanse (after first killing parasites) she was amazed at her improvement. She had not been to the hospital in a month and was only using inhalers preventively. She planned to get dental work done. She got all her former health back.

Laura Brewster, 25, lived in a very old house. The slightest exertion would give her an asthma attack. She frequently got pneumonia, too. Her lungs had beryllium (coal oil) and asbestos, and two parasites, *Paragonimus* (lung fluke) and *Ascaris*. She got rid of all the old fashioned lamps and candles in the house, but could not find the source of asbestos. She got rid of the attacks but her cough and pneumonia bouts will continue until she moves from that house.

Brett Wilsey, 70, was congested most of the time, had chronic sinus problems, was getting allergy shots for dust and mold, and was on several inhalers for his asthma plus emphysema. He had asthma for eight years. He had oxalate, urate, and all three phosphate variety crystals in his kidneys. He was started on kidney herbs. His blood test showed high "total carbon dioxide" or "carbonate" showing that his air exchange was not good. His potassium was low, showing that his adrenals couldn't keep his electrolytes (sodium, potassium and chloride) regulated, in turn, giving him muscle weakness. His LDH was very high, showing that his heart muscle) was in distress, too. Fortunately, his RBC was slightly elevated, to help with oxygen delivery. (See Anemia page 285). His eosinophil count was high, as is the rule for asthmatics since they all have *Ascaris* worms. Besides *Ascaris* he had pancreatic and intestinal flukes in his lungs(!) plus *Heterakis* (a chicken roundworm), human hookworm, and *Prosthogonimus*, another fluke. He was started on the parasite herbs. Two weeks later he felt a lot better although he still had some *Ascaris*. He was toxic with barium and hafnium (which were traced to his dentures) nickel, tin, rhenium. He stopped using commercial "denture-soak." His wife stopped using hair spray and they started leaving the car out of the garage and walked around to the front door, instead of using the attached garage. He also started drinking homemade comfrey tea. This made him feel still better.

When he removed his watch he got rid of his nickel source. Nickel has an affinity for lungs (as well as prostate and skin). He was now down to one puff of inhaler instead of two, only four times a day instead of hourly. He could breathe deeper than before. Then the lead in his water was found and traced to a single "sweated" joint in the pipes. He was started on food grade hydrogen peroxide, working up a drop at a time; now his cough became "productive", he was coughing up a lot.

He got the plumbing fixed and did a liver cleanse after which his fatigue lifted. He couldn't stop laughing and joking about the "emphysema" he was so worried over earlier.

Bea Karnes, 49, had asthma from childhood when she also had eczema. She was presently on several medicines plus allergy shots and antibiotics for it. She was toxic with antimony although she used no eye makeup and europium, tantalum, and gadolinium from dental metal. She also had hand swelling in the morning and was started on kidney herbs. She killed her intestinal flukes (in the intestine) and *Ascaris* in her lungs and was not seen for half a year. When we eventually saw her, she said her asthma had been “wonderful.” She was faithfully controlling parasites with the maintenance program and occasionally drinking kidney herb tea.

Cynthia Prout's whole family (mentioned previously) had asthma. She was told it was inherited. The three young children and herself were on inhalers, nose sprays, cough syrups and antibiotics. Nola, age 10, also had ear infections and numerous allergies. Lewis, age 8, was a slight, nervous boy; he had been off wheat and milk for many years due to intolerance. Irwin, age 5, seldom went with the family due to his frequent stomach aches and the fact he could vomit without notice. The mother and two children who were with her (Irwin stayed home) had *Ascaris* infection and Lewis also had pancreatic flukes. Their home was toxic with vanadium, namely, a gas leak. The parasites were quickly killed and gas leak repaired. The whole family got well and canceled their next appointment. Some inherited disease!

Asthma is just one of our common respiratory problems. The causes are always a combination of *Ascaris* and other parasites with pollutants (allergies).

Bronchitis, Croup, Chronic Cough

- In **bronchitis** the bronchioles are the site of the problem.
- In **croup** it's further down.
- In cases of **chronic little hacky coughs** it may be heartworm!

Bud Portillo, 62, worked on earth moving machines. He frequently had a “bronchial virus” or “bronchial infection.” He was always coughing. He had *Ascaris* infestation and arsenic pollution in his home. He also had palladium toxicity from tooth fillings. As soon as they removed the mouse bait from their home, tore down the hallway wallpaper (arsenic source) and changed wells (the well water had arsenic in it from seepage!) and killed parasites, his cough was gone. He also finished his dental work. All this took six months.

Gene Mizell, age 4, was constantly clearing his throat. His parents wondered if it was a "nervous habit." He had two species of *Ascaris* living inside his small body. He was started on a small dose of parasite herbs immediately, stirred into a daily dose of VMF syrup (see *Sources*). He also had PCBs, aluminum silicate, lutetium from recent painting in the house and xylene and toluene solvents. He was switched off soda pop and onto milk. We saw him five weeks later. He had gone through three treatments with vermifuge syrup. His throat clearing was gone, as well as his hacky cough and the blue circles around his eyes. He still had PCBs, which they later cleared by switching off detergent.

Carmen Castro, 30ish, had a chronic cough without being ill. She also had some heart irregularity. She had *Dirofilaria* (dog heartworm) and *Loa loa*. There were no indoor pets. After killing the parasites with a frequency generator and starting on the parasite herbs she was still coughing a bit but her pulse was down to 80 (from 120). She still had toluene, TC Ethylene solvents and mercury, platinum and lead in her body. Then a gas leak developed in their home. She used moth balls and painted a room. After this she had to be on antibiotics for her extreme cough. This time she had *mycoplasma*, *Haemophilus* and *influenza*. She killed these electronically and her coughing stopped. Until she gets the dental work done she will continue to pick up new infections.

Hope Feldman, 57, had been coughing for half a year. She had seen many doctors including a reflexologist. She had *mycoplasma* and *alpha strep* at tooth #17 (lower left wisdom tooth). As soon as these were killed with a frequency generator her cough stopped. She was advised to wear turtleneck sweaters for extra warmth over her bronchii and get a cavitation cleaned at tooth #17.

Teresa White, 37, had bronchitis several times each winter and was put on antibiotic for the whole season to keep it from breaking out. Her lungs were loaded with tantalum from dental metal, cobalt from detergent and thulium from her vitamin C. She had taken herself off milk, thinking it might be a factor, and used an air cleaner but without results. As soon as she had the tooth metal replaced with plastic (in less than a month) she could go off antibiotics and also was rid of a chronic sinus condition, but still had a bronchitis bout. She had *Ascaris* larvae in her lungs and phosphate and oxalate crystals in her kidneys. Her diet was changed to include milk and fish, magnesium, lysine (500 mg one a day), vitamin B_6 and a vitamin A+D capsule. She started on the kidney cleansing herbs and then the parasite program. In another month the whole problem was gone. Wisely, she got ready to cleanse her liver.

Craig Stewart, 2, had a history of respiratory problems. He had been on Ceclor™ and Ventilin™ for a long time; he had pneumonia the previous year. He had whip worm (*Trichuris*) infesting his intestine which was promptly killed with parasite herbs (as much as his parents could get down him was effective). He was toxic with asbestos. When the clothes dryer belt was changed to a U.S. variety (imported belts contain asbestos which flies into the air when the dryer is used), Craig's health turned around.

Doris Gumb, 26, was on Isoniazid™, Tussionex™ and Rifodin™ for tuberculosis. It started with coughing. She was down to 98 lb. in weight. Her lungs were toxic with beryllium (coal oil fuel), mercury, uranium, and tellurium. She began by clearing all toxic items from her house and basement and then bringing an air sample for testing. She also had *Ascaris* larvae in her lungs and pancreatic fluke in her pancreas. In three weeks she was coughing less and producing less with each cough. The “clean” air sample still had uranium, tellurium, mercury and beryllium. She had no metal tooth fillings, though. In the next three weeks she found a hole in the floor to the crawl space. It was letting up uranium dust and radon. The mercury was traced to the carpet in a child's bedroom. After throwing it out, her sputum cleared up and she was on the way to recovery, although we never found the source of tellurium.

Breast Pain

Although lumps and cancer in the breast produce no pain, they sometimes do give you little warning twinges. These twinges cross into the breast from the armpit or from any direction. It is gone in a second, leading one to believe it couldn't be serious. If the breast has any unusual sensations, painful or not, investigate immediately.

Test yourself for cancer. (You may use a specimen of mother's milk as a cancer test since this has mitotic stimulants in it—see Curing Cancer page 331). If you have purchased a slide of breast tissue (mammary gland) you can search your breast for cancer. If not, but you find “mother's milk” in your white blood cells, assume it is cancer and clear it up immediately.

If you don't have cancer, search for the pollutants giving you these twinges of pain. Search for your deodorant, cosmetics, and soap in your white blood cells. Search for dental metal. The breasts are often full of nickel. Nickel is quite soluble in fat and the breast is mainly fat. Nickel is one of the top carcinogens listed by researchers. It could even explain the high incidence of breast cancer. But titanium and barium from cosmetics, as well as asbestos and fiberglass are also quickly accumulated in the breast. Clean up your dentalware and body products. Check for exposed fiberglass. Change your dryer belt. Buy a new non-CFC refrigerator. Never try to get rid of these pains with pain killers; let the pains show you whether the clean up has been complete.

Breast Sensitivity

Breast sensitivity can be quite uncomfortable to the point of not being able to wear a bra, especially near period time. It may be due to high estrogen levels; this is also conducive to breast lumps and breast cancer. Most of your estrogen is produced by the ovaries before menopause and later by the adrenal glands. Too high estrogen levels plague the modern woman. Certain food molds, particularly **zearalenone**, causes over-estrogenization. It affects men too. I have found it in popcorn and corn chips! And brown rice. Stop eating these. Eat white rice. If you make cooked cereals be sure to add vitamin C to them before cooking (1/8 tsp. per cup), to detoxify food molds. I do not know whether taking vitamin C with your popcorn would detoxify zearalenone. Don't risk it. The excess estrogen compounds must be detoxified by the liver. Yet, the liver may be incapable of this because you ate yet another food mold! See the section on moldy food (page 381).

Over-estrogenized women are over-emotional, seemingly on a roller coaster of enthusiasm and despondence. They can develop a high pitched voice, that almost sounds squeaky. High enough estrogen levels are important for fertility but too high levels can cause infertility. Your body is eager to set the level just right, if only you will clean up the ovaries of parasites and pollution. Don't stop your clean up until the breast feels normal again throughout your cycle and you don't feel over-emotional, even just before your period.

Breast Lumps

Breast lumps may or may not be painful. If you feel one, don't wait to be more certain, don't wait to analyze it with tests, don't wait for a doctor's diagnosis or a mammogram. Obtain a frequency generator or zapper and zap yourself immediately. Also do the herbal parasite program immediately (page 338).

Your body often turns the breast into a collecting station for toxic wastes that have been drawn downward from the top of your body. From your head where shampoo and hair spray and cosmetics leave their daily deposits, from your dentalware with its constant supply of heavy metals, from neck and armpits where cologne, deodorant and soap leave their toxic residues. The lymph nodes under the armpit and the region above the breast, collect it all and let it slip into the breast where it is bundled up in a cyst. Perhaps the kidneys are clogged so toxins are forced to go to a designated dump site instead of out through the bladder. Do a kidney cleanse. Don't rest until all your breast lumps are gone. They will begin to shrink in three weeks if you are removing the correct toxins. Even radon and asbestos go to the breast, so be meticulous with your cleanup.

When the platelet count (in a blood test) is very high (over 400) there is quite a tendency to form cysts or lumps since platelets make your blood clot. The platelet count goes up when parasites are present. Maybe your blood is attempting to clot them! These clots make “nests” for fluke stages which may be why breast lumps often become cancerous. If yours is over 300, (it should be 250,000/cu mm) start patrolling parasites regularly. Stopping the use of caffeine and taking vitamin E (400 u. a day) are helpful in recovery but don't rely on these minor measures. Breast lumps definitely invite breast cancer.

Leslie Yeager, age 37, had breast soreness and "fibrocystic lumps”. She had cerium and nickel accumulated in her breasts. They cleared up in weeks after her dental metal was gone (she simply took out her retainer). Later she replaced it with a partial made of plastic.

Kari Pfeifer, age 36, had numerous cysts in both breasts and uterus. Her estrogen level was too high (187 pg/ml on day 22 of her cycle; the day of testing is important since it varies through the cycle). Her breasts were full of beryllium (coal oil from hurricane lamps) and radon. After these toxins were removed, all her breast lumps got smaller. After she did the kidney and Liver Cleanse, the lumps got softer and breasts were no longer painful. She had several root canals which filled her breasts with numerous bacteria, mainly *Histoplasma cap* (root canals develop infection around themselves). After starting her dental cleanup and killing bacteria with a frequency generator, all her breast lumps disappeared.

Claudia Davis, age 41, had breast soreness ever since a mammogram two years earlier. She had numerous other pains and indigestion. She had intestinal flukes in her intestine and fluke eggs in her blood: a dangerous situation. They might land in the breasts and start developing there. This is how cancer begins. But she did not have cancer yet. She had a buildup of niobium from polluted pain killer drugs and thulium from her vitamin C. She had *Salmonella* and several other bacteria in her white blood cells, which accounted for digestive problems. In eight weeks she had cleaned kidneys, killed parasites and gotten rid of her heavy metals. Her breast pain was better and a lump on her eyelid had also disappeared.

Stephanie Nakamura, 68, had six surgeries to remove breast lumps, going back to youth. Her recent mammogram was O.K. Her breasts were toxic with cadmium, lead, gold, radon, uranium, gallium, silver. Our tests showed she had kidney crystals and she was started on the kidney cleanse. She was given vitamin E, (400 units daily), sodium selenite (150 mcg daily) and vitamin C (1 or more grams daily). Her triglycerides were also very high showing again that she had kidney problems. She was given magnesium (300 mg daily), vitamin B_6 (250 mg daily) and lysine (500 mg daily). She killed parasites and cleaned up everything except gallium, silver, mercury, gold, cadmium. These must have come from her gold crowns. Her dentist advised against removing these and proclaimed they had nothing to do with her developing glaucoma, arthritis and stomach ulcers. It was a tough decision for her and she made the wrong choice. Perhaps if she had been up for the next breast surgery she would have gotten those “gold” crowns replaced with composite too.

Heart Pain

Pain over the heart region is usually quite real, even though an EKG does not find any abnormality. The most common cause is *Dirofilaria*, heartworm of dogs. It often begins as a pain just above the heart but spreads itself over the whole heart region. Kill it with your zapper. Parasite herbs can also be effective. If you did kill them, the pain often intensifies for a day before it leaves. Then the pain should be completely gone.

Heartworm is very easy to pick up again. If you have had heartworm, you should no longer keep a dog for a pet. Give it away.

Another heart parasite, *Loa loa*, is also a filarial worm and may be the causative factor. Both *Dirofilaria* and *Loa loa* can be obtained as slide specimens to use for testing yourself. Heart muscle can also be obtained as a slide specimen, but a chicken heart from the grocery store or snippets of beef heart (make sure to sample all 4 chambers) will do.

Follow up on your heart, even when no pain remains. These tiny heart parasites have stages that you may not be able to purchase in slide form and therefore can't test for. These stages, if not killed, will become adults so a maintenance parasite killing program, herbal or electronic, is essential. Virtually all dogs have *Dirofilaria* in spite of monthly medicine to kill it. They pick it up immediately after their last treatment for it and can give it to you again. The only way to live safely with pets is to give them parasite killing herbs daily in the feed.

Other heart problems such as irregular beat and mitral valve prolapse can clear up along with the pain. Or they may be due to bacteria (see Heart Disease, page 318).

Meredith Zackman, age 53, came for her diagnosed cardiomyopathy (heart disease). She owned a beautiful, old, very big dog, and of course she would never part from him. We knew she would lose her battle against heart disease. She had both *Dirofilaria* and *Loa loa* which we killed instantly with a frequency generator. She was on Lanoxin™, Furosemide™, Captopril™ and Metoprolol.™ We found she also had *Cytomegalovirus*, *Staphylococcus aureus*, *Streptococcus pneumonia* in her heart. The *Staph* bugs were also in tooth #17. She had copper in her heart (from tooth fillings) and cobalt and PCB from her detergent. There was zirconium from her deodorant and fiberglass from somewhere. Her pulse was typically in the 90's. Eight days later, after her dental work to replace metal was done her pulse was normal (low 70's), both worms were gone and she felt much better. But she still carried four bacteria, five viruses and two tapeworm stages: *Taenia solium* scolex in the spleen (she had chronic pain there) and *Taenia pisiformis* in the liver. She was started on Rascal (an herbal combination) for these. Six days later she had all of her problems back including *Loa loa*. She repeated everything, then she had to go off her heart medications because they lowered her blood pressure and pulse too much. She started the dog on the parasite program but continued to be heavily laden with parasites and bacteria that always found their way to her heart. She purchased her own frequency generator and was quite faithful with dog treatments. She may outlive her dog and then regain her health, finally.

Bruce Walby, age 42, had chest pain for three years. We found he had *Dirofilaria* and *Loa loa* in all four chambers of his heart. When he zapped them, the pain left a day or so later.

D'Ann Fonties, age 22, had a lot of chest pain but was told by her doctor it was simply “gas bubbles”. She also had a serious digestion problem. She had *Dirofilaria*, high levels of styrene (from styrofoam drinking cups) and benzene. This information delighted her and she planned to change her habits.

Sheila Osborn, age 27, had chest pain when she lifted objects. Her pulse was slightly elevated (81) and slightly irregular. She had *Dirofilaria*. Five weeks after starting the parasite program she was feeling much better but still had the chest pain. This time she had *Loa loa* (but not *Dirofilaria*).

Wendy Lewellen, age 28, had a chronic cough and chest pain at midsternum (the sternum is the bone attached to the ribs and runs up the middle of the chest). She had *Dirofilaria* in one chamber of her heart (right auricle). She had xylene and toluene solvents which came from her daily beverage, Mountain Dew.™ She was also full of asbestos from her trips to do laundry nearby (this could not be proved, but when she switched laundromats, the asbestos went away). Two months later, after killing parasites, she was free of heartworm and her cough and chest pain were almost gone. She was probably healing very slowly due to the asbestos which was still present.

Lupita Cline, a young mother, had a chronic hacky cough and irregular heart beat. She had *Dirofilaria* in all chambers of her heart and *Loa loa* in her blood but not in her heart. She had carbon tetrachloride, propyl alcohol, hexanedione, toluene, and TC Ethylene buildup from drinking Pepsi™ and Mountain Dew.™ Her pulse was slightly elevated at 80. There were no pets in the house. She was started on the parasite program and two months later was rid of her heartworm but now had *Loa loa* in her heart and was still coughing a bit. She was full of platinum, mercury and palladium from tooth metal as well as vanadium from a gas leak in her home and paradichlorobenzene from using moth balls. She was on antibiotics for a "bronchial infection" and was happy to learn about a better solution.

Slow Pulse/Syncope (Passing Out)

Mason Heckler, 30s, was a mechanic by trade and could not afford to pass out on the job. Yet, it had been happening off and on for 10 years. He had acquired high blood pressure in his teens! This was soon followed by an extremely slow pulse (50 beats/mm). No medicine worked (he had been tried on many) so he was on none. Then he got high blood pressure, it was 160/80 currently. He also had constant chest pain around the left nipple. He had heartworm and was started on the herbal parasite program. He never had a dog. In five weeks his pulse was 72; the parasite was gone. I presume his syncopes were due to sudden blood pressure changes or missing a few heart beats in a row. He began the kidney cleanse next to lower his blood pressure.

Chest Pain

When there is a tightness or just a little pain at the middle of the chest, especially under the breastbone, you may be merely having an allergic reaction. You might be feeling little spasms coming from the esophagus, and reaching up toward the throat from gallstones. You might also have HIV/AIDS disease which has a similar symptom over the sternum. So it is very important to pay attention to even a minor symptom in the chest.

Ruling out HIV disease ranks first in importance. Search for its emission at 365 KHz, or purchase a microscope slide with the dead virus on it as a test specimen (see *Sources*). Or purchase a set of slides representing all the stages of *Fasciolopsis buskii*. Without this parasite you can't get the HIV virus. Purchase a slide of the thymus gland or make your own specimen of throat sweetbreads. Check yourself for benzene buildup in the thymus. (See Using The Syncrometer page 462.)

If you have neither the benzene nor the parasite stages, you have no risk. Your chest distress is due to something else. Improve your air quality so that your lungs are not in distress. This includes radon, chlorine (from the bleach bottle under the sink), colognes, room fresheners as well as the usual pollutants (asbestos, arsenic, formaldehyde, fiberglass, freon).

If you feel waves of pain reaching up to your throat, you probably have a gallstone stuck in a bile duct. Epsom salts can relax that bile duct in 20 minutes. Take a tablespoon in ¾ cup water but only on an empty stomach or you may feel quite ill. Taking a large dose of valerian herb (6 to 8 capsules) may also buy you a little time by relaxing the duct. If you do get relief, you can be sure it was a spasm of some kind. The magnesium in Epsom salts relaxes spasms. I would recommend cleaning the liver (page 552) a number of times to try to dislodge the sticking gallstone. The instructions for liver cleansing advise you to kill parasites and cleanse the kidneys first. But if your throat pain is severe enough, you might just zap and go ahead with it at once.

Upper Back Pain

The main pain may be a dull ache over a shoulder blade, or between the shoulder blades or running right through you from the front to the back of the chest. These are all gallstone pains coming from the liver! Get yourself ready to clean them out. Clean the kidneys first, kill all the parasites that might be residing in the bile ducts and blocking them (flukes, pinworms and roundworms) and get onto a maintenance parasite program. Then mark your calendar for your first liver cleanse. Even if your first cleanse gives you only a dozen bits of green "stuff" you have done well; you have accessed the bile ducts. The pains will probably be "magically" gone the next day, but they might start to return in two days. The bile ducts are having spasms again due to the remaining stones.

After you have cleaned out 1,000 or more, you will get permanent relief. Repeat every two weeks, unless ill, until the upper back pains are gone, permanently. If chest pain or upper back pain is severe, try going off your favorite high fat food (ice cream, butter, cheese). Also try taking 6 valerian capsules, 4 times a day including bedtime to relieve the spasms.

Shoulder Pain

Some shoulder pain is called *bursitis* and some is called *arthritis*. But it always derives from stuck gallstones in the bile ducts of the liver! You can prove this by taking a tablespoon of Epsom salts in ¾cup water at 6 p.m. instead of supper and on an empty stomach (or you may feel quite ill). If some of the pain subsides then you have evidence as to its true cause, because Epsom salts relax the bile duct valves.

Get started cleaning the liver (page 552). By the time you have chronic or acute shoulder pain you have about 3,000 Stones! Count them roughly, as they float in the toilet after the liver cleanse so you know how much progress you have made toward the final goal. Don't start cleaning the liver until you have killed parasites and spent three weeks cleaning the kidneys though. This improves elimination of liquid toxins so a liver cleanse is promptly cleaned up for you.

What emerges from the liver is the most contaminated mess imaginable, full of bacteria and viruses and parasite eggs and stages (all dead we hope) of every kind. It needs prompt clearing from your body. The diarrhea sees to the bowel elimination. But some toxins can only pass through the kidneys. Kidneys should be clean and capable of doing the job. Remember it is unwise to clean the liver before all parasites are dead, especially flukes, because they produce a substance that inhibits any action of the bile ducts!

You are only one day away from freedom of shoulder motion and sleeping on your side again. Permanent improvement, though, depends on progress with your total stone count. Your bursitis can return in a few days or a few weeks. Be patient. You may only cleanse once in two weeks, and not if you are ill. After six cleanses you can be quite sure of being relatively pain free.

Between cleanses use valerian capsules to stop the spasms. It takes 6 capsules 4 times a day to be effective.

Typically only some bile ducts are spasming, and typically those ducts have a single fatty food trigger. Stop eating the high fat food you consume the most (it's probably your favorite). If that hasn't helped in two days choose a different high fat food to omit. The most common culprits are ice cream, potato chips, salad dressings, cheese, butter, cream, and milk.

Perhaps the pain is actually caused by bacteria living in the blocked bile ducts and invading the shoulder. This point has not been clarified. Using your zapper or frequency generator does no good for this pain. Only liver cleaning brings your shoulders back to their youthful mobility.

Upper Arm Pain

Excruciating pain in the upper arm soft tissues can keep your arm hanging straight down for fear of worsening it with motion.

Magnets of high strength (2x5000 gauss) taped to your arm, under your sleeve, can get you through the day. Also try valerian capsules (6 capsules four times a day). Go off all fat in the diet to let the spasm subside. Then start your liver cleanse at 6 p.m. If you used pain killer drugs during the day, the cleanse may not yield anything but it's worth a try anyway. You might be lucky and pop out the chief culprit stone. If not, you should wait several days before trying again; this time avoid pain killers the day of the cleanse. Be sure to zap parasites the day before or earlier.

Peggy Patton, age 60, had shoulder pain and painful feet in addition to aching all over. The aching was due to *Trichinella* which both she and her husband had. It took six months on the parasite program before it stayed away. She had clay colored stools, evidence of bile duct blockage. Then two liver cleanses cured her shoulder pain, nausea and remaining pains. She started gardening again and immediately picked up hookworms and *Trichinella* again. But she learned to sanitize her hands with grain alcohol after washing away dirt and this kept her parasites in check.

Jessica Atkinson, a middle age school teacher, developed a pain in the right cheek quite suddenly. She also had pain over the right mid abdomen and right side at the waist but X-rays and scans showed nothing (she had been X-rayed three times). She struggled for seven years to stay employed. She was having severe pain attacks over the liver and described her stool as almost white after these attacks. She cleaned her liver at least 30 times before she related, one day, that her joy in living had returned. Her gallstones were exceptionally large (½ x ¾ inch). Eventually the abscesses in her upper teeth were found, clearing up her cheek pain and protecting the liver from recurrent infections from these bacteria. Only then did she get permanent and complete pain relief.

Lisa Mattie, 72, had her right arm hanging limply by her side. It was so painful she bent forward to let it hang straight down. But in seven months she had done 6 liver cleanses, getting over 3,000 stones out. All pain was gone although some numbness in that arm persisted. She could also stop using Tums^{TM}, stop coughing, and no longer was bothered by her hiatal hernia.

Elbow Pain

One variety of elbow pain is due to an inflamed tendon there; it is sometimes called "tennis elbow." It is not due to playing tennis or any other arm use. The inflammation is caused by a liver full of stones and parasites, especially flukes which manufacture a chemical that affects tendons. Kill all flukes and cleanse the liver for quick relief. Using your elbows while they are inflamed is traumatic to them, like working with a sore thumb. Don't play tennis or do other arm exercises until they are pain free.

Parasites consume large amounts of your vitamins and minerals. Give yourself vitamin A (25,000 u daily), zinc (60 mg. daily), and B_6 (250 mg twice a day) until the pain is gone.

Wrist Pain

Tendons passing through the wrist can become inflamed from the unnatural chemicals produced by fluke parasites in the liver. Using the wrists to work further traumatizes them (injures them) making it harder for them to heal. A small hole between the tendons lets the nerve and blood vessels through into the hand. Fluke parasites also make chemicals that thicken tendons. When tendons at the wrist thicken, they can squeeze down on the nerves and blood vessels until the hand or fingers feel numb. If you have pain at the wrist or numbness in your hands, killing parasites and cleaning the liver may give you the permanent cure. Wearing a wrist bandage or support can help reduce trauma damage to the wrist while it is healing.

Numbness of hands, without wrist pain, is more often due to a brain problem with parasites and pollutants. Lead, mercury, fluke parasites are the usual culprits.

Thumb Pain and Hand Pain

can be due to liver parasites. Get yourself ready for a liver cleanse. If the pain goes away beforehand, while you are on the kidney cleanse, it shows you had deposits in your joints. You were headed for arthritis in your hands. Read the information on arthritis (page 78) to protect yourself.

Finger Pain

This is pain in a joint, often accompanied by some enlargement or knobbyness of the joint. It is not hard to recognize these as deposits of the same kind as we saw in the toes. You can test yourself to identify the variety. **Uric acid** and **phosphates** are the commonest types. Read the section on toe pain (page 55) for detailed instructions. You can greatly reduce your finger joint deposits and the size of the knobs. In six weeks after starting the kidney cleanse and changing your diet, the knobs may already be shrinking. A large magnet (5000 gauss—used only as directed) may bring pain relief but only dental cleanup and environmental cleanup will give you lasting improvement.

Back Of Neck Pain

The back sides of the neck seem to be highways that run between the teeth and liver. Both contribute to pain at the back of the neck. Pulling an infected tooth or cleaning a cavitation can bring complete relief, only to return the next time a tooth is extracted. Extractions should be followed by cleaning out the cavity created so an infection can't start here. Cleaning the liver can also bring immediate relief, only to find pain and stiffness to return months later. You must cleanse many times for permanent relief.

An allergic reaction to potatoes and tomatoes can express itself in neck pain too. When the liver can no longer detoxify the chemicals (solanine, etc.) in this food family they are free to roam the body with the circulation. Perhaps they prefer to attach themselves at a particular neck site and cause inflammation here. Perhaps an injury was already there, beforehand. Whiplash is often blamed for back-neck pain and indeed chiropractic adjustments can bring total relief. Perhaps the trauma of whiplash first invited all of these contributors. Merely killing bacteria with a zapper is not long lasting. But dental cleanup plus liver cleansing is.

Front Neck Pain

Lymph nodes under the jaw strain your body fluids of the head, removing bacteria and toxins. They are sometimes called “neck glands.” If the stream of bacteria is endless such as when they are coming from a hidden tooth infection, the lymph nodes will enlarge to do a better job. They will also try to remove toxic metals, mouthwash, and toothpaste for you.



Fig. 26 Lymph node neck glands

To see what is affecting your lymph nodes, purchase a slide of lymph nodes. Since we have lymph nodes in many locations in the body, you can't single out the neck nodes for study. So you will get to see all the toxins affecting lymph nodes everywhere: PCBs in your underwear being removed by groin lymph nodes, lead in your intestinal lymph nodes from the water you are drinking, mercury in your neck lymph nodes from amalgam fillings. Eliminate all these. Don't rest as long as any of your glands are enlarged.

Roland Sanford, 23, had minor pain and a lot of stiffness along the sides of his neck. His arms had some numbness. He only had one metal tooth filling but his whole body was toxic with samarium, beryllium, indium, copper, cesium, and mercury. When it was replaced, his neck pain and numbness got better.

Audrey Doyle had severe neck pains she attributed to sitting all day and sleeping in her wheelchair. She had to take pain killers to get to sleep at night because they were so bad. She knew eating cream and butter made it worse but she had no will power, she said. After a liver cleanse, getting "thousands" of tiny stones, she was free of it.. for one day! But it was enough to convince her and she was determined to be off pain killers.

Temporal Mandibular Joint (TMJ) Problems

Pain at the angle of your jaw is not due to a poorly fitting joint. It fits perfectly but the muscles nearby are pulling it out of joint with their frequent spasms. There is always a hidden tooth infection present. Ask the dentist to search for hidden tooth infections and to clean your cavitations (you will need to find an alternative dentist, and read Dental Cleanup, page 409). Begin immediately to heal these bone lesions with vitamin D (40,000 to 50,000 units once a day for 3 weeks, followed by 2 such doses per week forever), milk-consumption for calcium, and a magnesium oxide tablet. (See bone healing, page 87).

Kill pinworms with a zapper or frequency generator in yourself and family members twice a week and keep everyone's fingernails short for extra hygiene in the family for a month to prevent reinfection. Pinworms can cause tooth grinding and contribute to TMJ dysfunction. For extra muscle relaxation, take two magnesium tablets at bedtime and valerian capsules.

Tooth Ache

Before the pain becomes acute and excruciating, kill bacteria of the mouth, including “tooth decay” and “tooth plaque” frequencies (see frequency list, page 561). Make your dental appointment immediately. If zapping bacteria several times in a few hours relieves pain enough to get you through the night or past the weekend, do not delay a single day. Zapping does not reach into the middle of an abscess—it circles around, so some bacteria are left to repopulate.

Try to understand the problem. If there are teeth with root canals near the location of pain, extract them. The toxic materials of the root canal jeopardize your total body health. Removing them always helps and may let the jaw heal normally where they were extracted. Since the pain is caused by a bulging infection pressing on a jaw nerve, and because each tooth has a related organ(s) it is especially important to clear up all infections to protect these organs.

These relationships are not understood yet. Finding that teeth have the same tissue frequency as some distant organ sheds a little light on the situation. Until the meaning and function of these frequencies is understood we can only guess that they interact somehow. Bacteria have taken advantage of this common resonance and have invaded both organs.

Heart infection by *Staphylococcus aureus* is an example. It is a common heart bacterium, causing much of our heart ailments, particularly mitral valve disease and irregularity problems. They always derive from teeth, whether present or missing! After wisdom teeth are extracted, the hole left in the jaw frequently does not heal, it picks up *Staphylococcus aureus* from the mouth and a chronic infection is started. For this reason it seems ill advised to pull wisdom teeth if it isn't necessary.

Another heart bacterium, *Nocardia*, can originate in the teeth. *Nocardia* can also invade the brain and nerves. Persons with Parkinson's disease always harbor quite a population of *Nocardia*. Zap all these bacteria before and after your dental visits. Remember that killing bacteria in itself is not a panacea. Pain and body damage will return unless you do the proper repair and cleanup work.

Throat Pain

Recurring sore throats are always improved by removing dental metal and root canals, and by cleaning up hidden tooth infections. This is essential for a permanent solution. Bacteria and viruses that cause sore throats are thriving in hiding places under and around dental metal. It is quite difficult to reach the center of such places (abscesses) with electric currents. Even if you could, you would reinfect the very next time you ate non-sterile food! Zapping is not a substitute for cleaning up your dentalware.

Keep your neck warmer than would be perfectly comfortable, gargle with hot water to bring in extra circulation. Use zinc tablets (60 mg. see *Sources*) twice a day; suck on them before swallowing. After cleaning up dentalware you may never have another sore throat!

Children with recurrent sore throats usually do not have a dental problem. They invariably have an air pollution problem. Asbestos, formaldehyde, fiberglass, Freon and arsenic are the chief culprits. Clean these out of the house. Eating moldy food is especially conducive to respiratory illness. The immunity drop can last for weeks! Go off the moldy suspects to raise your family's resistance.

Eye Pain

is caused by parasites.

The eye is a favorite location for many parasites, including *Giardia, amoebas, hookworm, schistosomes, Toxoplasma,* and innumerable others. The eye has two large bodies of watery fluid: the *aqueous humor* and *vitreous humor*, where no blood traverses to bring in extra white blood cells when the need arises. It has its own protective devices, like tears, but some parasites, like *Toxoplasma*, have overcome all the body's



Light travels through the cornea, through the aqueous liquid, the lens, and then the vast vitreous humor, finally striking the super sensitive spot on the retina, called the macula.

Fig. 27 Eye.

defenses and regularly invade the eye if they get into the body somewhere.

We get *Toxoplasma* from cats; the infectious stage is in cat feces.

Toxoplasma infection could be the beginning of a lifetime of eye disease due to weakening of the eyes at an early age. *Toxoplasma* also invades the brain, frequently causing a dull ache or pressure at the back of the head. *Trichinella* is another common eye parasite, invading the eye muscles, so that a muscle is weakened and doesn't allow perfect alignment of the two eyes. Dogs and cats are the source of these.

**There should never be a cat box in the house.
Never let a child near a cat box.**

By killing all the large parasites plus a few bacteria (*Staphylococci*, *Chlamydias*, *Neisserias*) the eye can become pain free in a few days. If pain returns, you missed something or reinfected yourself. Everyone in the family including pets needs to be treated for all the parasites. No indoor pets should be kept by a person of low immunity, since infecting yourself daily and then killing parasites daily is not a solution.

Herpes of the eye is not a single actor. The true host of this virus is a larger parasite, possibly a tapeworm stage. Tapeworm stages should be killed with an herbal preparation, Rascal, or with a zapper. (Not with a frequency generator. Only a zapper can kill all the segments and eggs at once, leaving nothing alive to wander about and find a new tissue to invade.)

Mary Rauch, age 60, filled a page with different pains and problems. Even her eyes had a dull ache around and behind them, sometimes reaching to the back of the head. Her teeth hurt when she ate and she had been getting B_{12} shots once a week for 36 years for pernicious anemia. She was full of *Ascaris*, amoebas and pinworms which kept her legs twitching and jerking in bed at night, even waking her up. She was so much better after the kidney cleanse and parasite program she was eager to cleanse her liver. Before two months had passed her eye pain was gone.

Jessie Healy, middle aged and in good health otherwise, had carried the anxiety of having inherited *retinitis pigmentosa* for forty years. Now her drivers' license was in jeopardy due to fast progression of her disease. Numerous heavy metals had accumulated in her retina, including cerium from dental floss, arsenic from pesticide, tin from health food brand deodorant, PCB from skin salve, cobalt from dish detergent and indium from tooth metal. She had eight parasites in the retina including *Toxoplasma* from association with cats years ago. Removal of dental metal alone arrested the disease process. Two years later she was slightly improved and still driving her car.

Macular Degeneration

Dolores Bollapragada, 50ish, had suffered from clinical ergot poisoning in the past which put her in a coma for several weeks. Ergot is a grain (especially rye) fungus, very toxic to the liver. Its byproducts are used in migraine medicine. She had overdosed, somehow. Perhaps her liver never recovered. It no longer detoxified solvents for her, allowing them to accumulate in her retina. There she had propyl alcohol, benzene, carbon tetrachloride acetone, butyl nitrite, styrene, gasoline, wood alcohol, paradichlorobenzene (moth balls), pentane, methylene chloride and decane. She stopped snacking on cold cereal through the day. She had many habits and products to change. But she was determined to salvage her sight. She did.

Headache and Migraines

Headaches can take the joy out of living. They can lower your motivation level so low that you don't even want to do anything about them! People with daily headache deserve our deepest sympathy since they must carry on with life's daily duties in spite of it. Often, no medicine helps. Although there are common headaches, sinus headaches, migraines, and others, the causes of all overlap a great deal.

Tooth infection, urinary tract infection, bowel problems, and a wormlet, *Strongyloides* are the common causes.

There are also allergic connections which include milk, eggs, citrus and salty foods. But the allergy-approach is difficult to put into practice. It is almost impossible to stay off these foods for long time periods. Eliminating bacteria and *Strongyloides* leads to a permanent solution.

Possibly the parasite wormlet comes first, since even young children can suffer with migraines. *Strongyloides* is a microscopically small threadworm that horses are plagued with, but humans and our pets pick it up easily. Every migraine sufferer (100%) has high levels of this tiny worm. Perhaps it is really the special bacteria it brings with it that cause the blood vessels to seep or to spasm in the brain, causing pain. Zap it immediately.

Bacteria hidden under a tooth filling or root canal or in a space where once a tooth was pulled can be the cause. *Staphylococcus aureus* is a favorite, but various *Clostridia*, *Streps* and others are often seen, too. You don't feel pain from this small abscess because the pressure isn't building up inside it. It has found a way into your body–namely, your brain!–so no pressure builds up to alert you. Find an alternative dentist with experience cleaning cavitations and finding small hidden abscesses. If you get immediate relief from dental work, only to lose ground again later, the abscess may have formed again (they are notorious for forming again). Go back to the dentist. Irrigate the dental wound site with white iodine (potassium iodide, 12 drops) or Lugol’s (6 drops) to ¼ cup water using a curved-tip syringe.

Do not use iodine if you know you are allergic to it.

The colon is always a thriving mass of bacteria. It should be emptied at least twice a day to keep their levels down. Use the simple herb, *Cascara sagrada*, senna tea, or magnesium oxide tablets (2 to 3 a day) to help you eliminate frequently if your own regularity is lacking.

Gallstones in the liver and a congested liver are sources of bacteria, too. Do several liver cleanses and note the effect.

Is it the toxins made by bacteria or the inflammation from the bacteria or wormlets themselves that produces the headache? Certainly, one can eat the toxins by themselves in foods like yogurt, cheese, wine, sour cream and develop "royal" headaches. Stay away from these **tyramine** containing foods. Boil all your dairy foods to prevent *Salmonellas* and *Shigellas* from swimming into your beleaguered brain. Don't eat dairy foods that can't be boiled for ten seconds.

Begin by killing all *Strongyloides* and other parasites, bacteria and viruses with a zapper. Hopefully, this will only leave a few stragglers behind in abscesses, gallstones and the colon contents. If the colon bacterium, *E. coli*, is your headache cause, start the Bowel Program. Search for the source of your *E. coli* in food or polluted water. Stop reusing water bottles. Most people get their *Strongyloides* back in a few days from pets, other family members, and themselves! Zap every day for three weeks. Try to "clean up" family members and pets. Never let a horse or pet salivate on you. Never put your fingers in your mouth. Always sanitize your hands with grain alcohol after using the bathroom.

To summarize the steps to cure migraine headaches:

1. Kill *Strongyloides* and bacteria by zapping.
2. Do the herbal kidney cleanse.
3. Clean up dentalware.
4. Do the Bowel Program.

5. Boil all dairy foods.
6. Do liver cleanses.

This has never failed to substantially reduce migraine intensity and frequency.

Headaches are also caused by toxins in your environment; especially things you breathe in. Household gas is the most common offender. You don't smell it after you get used to it! Gas pipes are notoriously leaky. Conducting gases through pipes with joints in them, where gases could escape, must be the most ludicrous of all modern “conveniences”. Would you try to conduct water through pipes with holes in them? You would soon see the water on your kitchen or bathroom floor. But gas doesn't land on the floor, it doesn't make a puddle, so you, the consumer, are left helplessly believing you don't have leaks. Every gas pipe that has a seam should have a clear plastic boot around it containing indicator compound to let it be known when gas is escaping. Other methods could be invented to make the gas utility safe. As you will see from the case histories, very many persons are living in a cloud of poisonous gas.

The telltale element is **vanadium**. When your vanadium test is positive, you have a gas leak that your body found, even though the gas company may not. Many gas companies use outmoded equipment to search for it. Four out of five gas companies miss the gas leak. Health Departments and building contractors use modern equipment that detects even the tiniest leak; call them.

If you are a headache sufferer, fixing the pipes is not good enough. Switch from fossil fuels to electric. There will be many dividends. (Remember not to use candles as part of your lifestyle, nor to be a smoker.) Your air needs to be clean: clean of perfumes and colognes, clean of potpourri and air fresheners, clean of air sprays, pesticides, formaldehyde, freon, carpet and car odor, fireplace lighter, and of wood smoke.

Janette Donovan, age 52, had migraines every day but could not tolerate any medication for it. She walked about "like a zombie" most of the time. She frequently had vomiting with them. She was gassy, had pain in her right groin for many years and chronic bladder leakage. Our kidney stone test showed urate crystals. Her urinalysis also showed urate crystals and a slight amount of blood, obviously chronic urinary tract infection. The parasite test showed *Strongyloides*, *Trichuris* and *Fasciolopsis buskii* in the intestines. Her heavy metal test showed beryllium. This was tracked down to hurricane lamps that once held coal-oil in them— it filled her house air unbeknownst to her. Thirty five days later she had done an herbal parasite killing program, done the kidney cleanse, cleared out the hurricane lamps and all fuel containers. Her headaches were "more like pressure" now than pain. She still had *Strongyloides*. Four months later she had some headaches still but not migraines. They were down to once a week. Three months after that she had done a liver cleanse and gotten abut 3,000 stones out! She was still getting some headaches. She tested positive to *Histoplasma* and *Coxsackie virus #4* (a common brain virus) probably stemming from dentalware. She had many root canals and couldn't decide what to do. Keep her teeth and risk return of migraines; or get partial dentures. After eight months of indecisiveness she was back up to ten headaches per month, although not migraines.

Patsy Olsen, age 30, had migraines daily, frequently with vomiting. She had *Strongyloides* as well as *Ascaris*, and other bowel parasites as did her husband and two children. She couldn't tolerate any medication and had to give herself an enema daily for constipation. The whole family was put on parasite killing herbs. A gas leak was found and fixed and the baby's diapers were changed to non fragrant. Ten months later, the whole family still had *Strongyloides*. By one year she was experiencing a couple of good days a month although she still had *Ascaris*, *Coxsackie* viruses, and various tooth-related bacteria. Her two and a half year old had swollen neck glands, was toxic with bismuth from disposable diapers but did not have *Strongyloides*. The eight year old was also toxic with the lotions and fragrance of baby-stuff in the home; she was constantly congested and coughing but became free of *Strongyloides* in six months. After another ten months (the baby had been potty-trained meanwhile) the mother began to have headache-free days.

Donald Schaible, age 14, had migraines, learning disabilities and severe acne. The parasite test showed *Strongyloides*, *hookworm* and *Ascaris*. In spite of being on the parasite program two weeks and zapping, he still had *Strongyloides*.

Kenneth Jones had migraines for thirty five years and had tried all the new medications. They worked for a while, then stopped helping, but he continued taking them anyway. He usually went to the emergency room for the really bad ones, once a week but lived with the constant daily variety. There were two house dogs. They and the whole family had *Strongyloides*. After cleaning up an asbestos problem, killing parasites for five months and clearing kidneys of urate stones, he was down to two to three mere headaches a week. Two months later, he was getting migraines again; they all had *Strongyloides* again. With renewed efforts, one month later his bad headaches were down to one a month, although his low level chronic headache persisted: they had the dogs on a strict schedule of parasite killing herbs as well as themselves. He had not been to the emergency room for a month.

Angelina Gander, age 46, had daily headaches, not migraines. She also had persistent urinary tract infection and sinus infection. She was put on the herbal parasite program and four weeks later was much better. She also lost her chest pain due to heartworm and regained her milk tolerance.

Gracie Arlington had a boy age 6 who wet the bed, a girl age 8 with a behavior problem at school. She was stressed by an unfaithful spouse and thought she should go back to school for a Nursing degree so she could support the family. But she was getting two or three migraines a week in addition to colitis attacks which she feared would make her unable to study. The two cats, a dog, the children and herself all had *Strongyloides*, *Ascaris*, and a variety of other intestinal parasites. The humans were promptly zapped for parasites and the boy was dry that night for the first time in his life. A few nights later he was wet again. This time the animals were zapped and put on the pet parasite program and the children's toileting was carefully supervised. When she dropped her extreme vigilance over all, they all relapsed. After a year of trying, they gave away their beloved dog, put the cat box in the porch

> and the mother did the cleaning herself but nothing prevented relapses. A half year later, her six year old son asked if he could launder his own sheets and blankets. This request broke her heart and she planned to give away one cat. Even with only one cat, the girl's behavior and grades fluctuated extremely, the mother had a migraine a week and the boy wet. During a vacation the mother loaned the last cat, (her cat) to which she was very endeared, to a friend, to see if it made a difference. The boy never wet again, the girl made straight A's, and the mother's headaches became sinus headaches. Some intensive dental work cleared these up. She brought her Nursing diploma to our office two years after beginning. She should have had another diploma for **Intelligent Parenting.**

Earache

Earache is particularly common in children. Bacteria, mainly *Streptococcus pneumoniae,* have built up to a high level. Zap them. They were probably introduced by some larger parasite. But why did they multiply and thrive in your child's ear? There must have been food for them and protection from the immune system. Probably the Eustachian tubes are full of mucous, providing habitat. The mucous is present because some air toxin is irritating the sensitive linings. Clean up the air: not just asbestos, fiberglass, formaldehyde, freon, and arsenic, but perfumes, fragrant school supplies, potpourri.

Being housebound, as in winter, makes the air-toxin problem worse. Use summer time to strengthen your child for the winter—spend summer outdoors. Always wash hands a lot. Stay away from moldy food. Give small doses of niacin (25 mg., niacin thins mucous so it can run away) along with vitamin C (250 mg.) at bedtime.

Putting in “tubes” is a short term solution that is better than perpetually staying on antibiotics, but neither should be necessary.

To hasten healing, as soon as earache is suspected put room temperature olive oil in both ears, tug the earlobe to let bubbles out, and stopper them with cotton wool salvaged from vitamin bottles (other types are polluted with mercury). Put on a light bat that covers the ears.

When adults get earache, the *Streps* are hiding under tooth fillings and in gallstones. Clean up these two sources and zap.

Drinking non sterile milk adds *Salmonellas* and *Shigellas* to the *Strep* ear infection! Small wonder milk is thought to make people mucousy. The ears must now battle them, too. Even a few bacteria consumed in milk can start a whole colony if bowel bacteria have been disturbed by antibiotics. If your child has become "allergic" to milk or gets mucousy, remove cheese and ice cream–not milk–from the diet. Even cheese can be eaten if baked as in pizza or casseroles. Milk must be boiled. Try to reduce the child's *Salmonella* sensitivity by avoiding unnecessary antibiotics. Keep immunity high by avoiding moldy food!

Ear Noises And Ringing

This is also called *tinnitus*. A hissing or buzzing sound is heard in one or both ears. It can be continuous or pulsing off and on. It can be as loud as roaring.

Tinnitus is caused by three things acting in partnership: toxic elements, an allergy to *salicylates* (the aspirin family) and a bacterium *Streptococcus pneumoniae* (the pneumonia bug). This "bug" can be carried in the chronic state after a bout of pneumonia or what seems to be a head-cold. It is always present in earache. It is easily activated by exposure to cold wind or drafts and certain toxic substances. For this reason I recommend keeping the ears warm in winter by keeping them covered or wearing a cotton plug or ear-muffs. The *Strep* bug can also cause *Meniere's syndrome*, congestion, loss of balance and chronic sinus problems. Often an antibiotic of the penicillin family helps immediately, then loses its effectiveness. This shows you that bacteria are involved but cannot be truly vanquished with antibiotics.

Streptococcus pneumoniae often hides in pockets under infected teeth and in holes left where teeth have been pulled—especially wisdom teeth. These can be found by alternative dentists who clean these cavitations. *Strep* also resides in the liver; clean them out with liver flushes.

Certain foods and many medicines, especially cough medicine and lozenges contain salicylate.

To cure the tinnitus we must stop using aspirin or any high level source of salicylates. We must also stop the exposure to certain toxic elements—lead, beryllium, zirconium, benzalkonium. They are present in the air at gas stations and in many of our body lotions, soaps and salves. Switch to safe varieties. Niacin tablets, such as 100 mg, taken three times daily is another treatment, intended to increase the blood supply to the inner ear. Taking a thyroid tablet, by prescription, often helps too.

These methods never fail to improve tinnitus but a complete cure is seldom possible.

William Thall, 47, had a headache daily and was on pain medicine for it daily. He had tinnitus, a loud humming noise in the right ear. He had *Shigella* (producing nerve toxins) and *Borellia* (Lyme disease virus). He had *Gaffkya*, a respiratory bacterium under two wisdom teeth (right side). He also had *Campylobacter* and *Anaplasma* growing on him somewhere. He had *Strongyloides* too. He was toxic with vanadium (gas leak) and asbestos. After ten weeks he had two cavitations on the right side of his jaw cleaned, he had been on the parasite program and his tinnitus was gone, (he still had occasional headaches indicating he still had some *Strongyloides*).

Billie Scott, 26, had a history of ear problems, and lots of headaches. She was started on the kidney cleanse. Then she added the parasite program including their two dogs. She had a cyst in her left buttock, due to PCBs traced to the well water. She stopped using this well and switched off detergents for laundry and dishes. She switched off soda pop, onto milk. In 3½ months her tinnitus was gone and the cyst was shrinking.

Larry Pelegrini, 59, had tinnitus in both ears but was otherwise a strong, tall, intelligent person, who cared for sick people, whether family or not. As soon as he saw how simple it was to kill invaders with a frequency generator, he bought one. Preventing their recurrence was his big challenge since he had neither the means nor insurance to do dental work. He was toxic with aluminum, copper and PCBs. After switching to borax for all washing purposes, he got rid of aluminum and could feel his memory improve. The kidney herbs cleared him of uric acid and oxalate and he felt more supple. He had to go off his favorite beverage to get rid of pentane and methyl ethyl ketone. Twice a week he killed two dozen parasites and bacteria, that just seemed to pop up from nowhere, in order to feel better and reduce his tinnitus. But he lived alone, had to cook, garden, take care of animals and his sick friends which gave him a lot of parasite exposure. Sometimes he would be toxic with arsenic (a new pesticide he tried out) or vanadium (gas leak) but mainly it was tooth filling metal. If only this wonderful man could afford his dental work: what a blessing to society he could be for a long time to come.

Scalp Pain

Infection anywhere in the head can cause sensitive scalp and scalp pain. Even a common cold can cause bouts of scalp pain. Clean up your dentalware and environment.

Lumps on the scalp are often called *sebaceous cysts*, actually this is where your body has sequestered PCBs (polychlorinated biphenyls, extremely hazardous, now banned in the U.S., but often a pollutant in detergents.) Get rid of them by switching off detergents for all purposes. See *Recipes* for dishwasher liquid, dishwasher detergent, and laundry detergent replacements.

Non-Painful Diseases

Explanations for many of these “mysterious” diseases become rather obvious when you see a **common parasite, or pollutant, or both** consistently show up in case after case.

Diabetes

All diabetics have a common fluke parasite, *Eurytrema pancreaticum*, the pancreatic fluke of cattle, in their own pancreas. It seems likely that we get it from cattle, repeatedly, by eating their meat or dairy products in a raw state. It is not hard to kill with a zapper but because of its infective stages in our food supply we can immediately be reinfected.

Eurytrema will not settle and multiply in our pancreas without the presence of **wood alcohol** (methanol). Methanol pollution pervades our food supply—it is found in processed food including bottled water, artificial sweetener, soda pop, baby formula and powdered drinks of all kinds including health food varieties. I presume wood alcohol is used to wash equipment used in manufacturing. If your child has diabetes, **use nothing out of a can, package or bottle** except regular milk, and no processed foods.

By killing this parasite and removing wood alcohol from the diet, the need for insulin can be cut in half in three weeks (or sooner!)

Be vigilant with your blood sugar checks. The pancreas with its tiny islets that produce insulin recovers very quickly. Even if 90% of them were destroyed, requiring daily insulin shots, half of them can recover or regenerate so insulin is no longer necessary. The insulin shot itself may be polluted with wood alcohol (this is an especially cruel irony—the treatment itself is worsening the condition). Test it yourself, using the wood alcohol in automotive fluids (windshield washer) or from a paint store, as a test substance. Try different brands of insulin until you find one that is free of methanol.

Artificial sweeteners are polluted with wood alcohol! Instead of helping you cope with diabetes, they are actually promoting it! Do not use them.

Drugs that stimulate your pancreas to make more insulin may also carry solvent pollution; test them for wood alcohol and switch brands and bottles until you find a pure one. You may not need them much longer, so the extra expense now may soon reward you.

Many persons can detoxify the amount of wood alcohol that pollutes our foods. They do not have a food mold, **Kojic acid**, built up in their bodies as diabetics do. I have found Kojic acid in coffee, and potatoes with gray areas inside. Do not eat discolored potatoes or peels, even if cooked or baked. Being able to detoxify a poisonous substance like wood alcohol should not give us the justification for consuming it. All poisons are bad for us. Do not consume them.

All diabetic persons also carry a virus, *HA virus* in the pancreas. This virus grows in the skin as a wart but is spread quite widely in the body such as in the spleen or liver besides pancreas. It is not necessary to kill this virus since it disappears when the pancreatic fluke is gone. The HA virus undoubtedly belongs to the pancreatic fluke. The question can be asked: Does the fluke or its virus cause diabetes? There might even be a bacterium, so far missed in our observations, that is the real perpetrator.

While recovering from diabetes, it is very important to check your blood sugar every day. Improvement is so rapid, you may suddenly be over-insulinized by your next shot. Cut down your dose to suit your actual need.

There are additional aspects to diabetes that have been studied by alternative physicians. For instance, allergy to wheat and other grains containing gluten is common. Perhaps the pancreas and its islets would heal much faster if grains were out of the diet for a while. Perhaps the 50% improvement that is consistently possible just by killing parasites and stopping wood alcohol consumption could be improved further by a month of grain-free diet. Eating **fenugreek seeds** has been reported to greatly benefit (actually cure) diabetes cases. Are they a specific fluke killer, virus killer, or neither? It seems like a good idea to add this to your diet if you are a diabetic. Wood alcohol also accumulates in the eyes, and there is a connection between diabetes and eye disease. **Bilberry leaves** are an herbal treatment for both diabetes and weak eyes. Do they help by counteracting wood alcohol or detoxifying Kojic acid? Make a tea for yourself, using ¼ cup leaves to three cups water. Drink ½ cup a day. Chromium is another must for diabetics (200 mcg three times a day). It helps insulin enter your cells.

Gold is attracted to the pancreas. Heavy metals should be removed from dentalware including all gold crowns and no metal should be worn next to the skin as jewelry, including all gold items.

Blythe Jenkins was on Micronase™ (5 mg) daily for her diabetes but she still had a morning blood sugar of 183. She had pancreatic flukes and sheep liver flukes in her pancreas, vanadium (a gas leak) in her home and cadmium in her water (old pipes). After killing parasites and cleaning kidneys her morning blood sugar was down to 148. She also got rid of her hot flushes, groin and leg pain. This encouraged her so much she did the rest of her body cleanup and could go off her medicine completely.

Robert Greene, age 65, had been on insulin five years already, getting two shots a day (25 u each), and even this was not controlling his blood sugar which was 288 in the morning. He was raised to 30 units without much improvement. His legs and feet were too painful to walk without a walker to lean on. He had *Loa loa* in his pancreas. (This is another example of a parasite going to the "wrong" location, this time the pancreas instead of the heart. I believe the solvent makes this possible.) Also *mumps virus*, *HA wart virus*, *mycoplasma*, *flu virus*, *chicken pox virus*, *Adenovirus* and *Shigella*, all making their home in his pancreas! This was possible because he had wood alcohol accumulated there, from drinking various beverages and using artificial sweetener. As soon as he stopped this practice and killed everything with a frequency generator his blood sugar fell below 100 in the morning and he had to reduce his insulin to 20 units. He was also on chromium 200 mcg (2 three times a day). Meanwhile, he cleared 2,000 stones out of his liver. He could now walk well again and decided to take a part time job. The whole process took one year.

Ralph Dixon, age 72, had been switched to 30 units of insulin, once a day, after six years on pills for his diabetes. He still had a fasting blood sugar of 242. He had the pancreatic fluke and a host of bacteria and viruses in his pancreas. He had a poodle. After killing the pathogens and cleaning his kidneys, his blood sugar dropped so he cut his insulin to 25 units (blood sugar was at 111) Soon he had to cut it to 20 units. He was also on chromium 200 mcg (2 three times a day), manganese 50 mg. (one a day), fenugreek capsules (2 a day), and bilberry leaves, each supplement by itself. He also lost his angina and fatigue with all this body-cleaning. But if he went off the maintenance parasite program he would promptly get a spike in his blood sugar, showing how easy it was for him to reinfect and how new parasites would immediately find his pancreas.

Melissa Bird, 54, had major illnesses including heart disease (2 angioplasties), numerous other surgeries and diabetes. She took 15-18 units of insulin once a day. Besides pancreatic flukes in her pancreas, she also had intestinal flukes there(!) plus widespread *Ascaris*. She also had warts and candidiasis. Fortunately there were no pets. Her parasites were instantly eliminated with a frequency generator and she was started on kidney herbs for her other problems. Seven weeks later she stated she had to cut down her insulin because her morning blood sugar had dropped to 90. Then she eliminated the decafs and artificial sweetener that were giving her wood alcohol, started the parasite herbs and did a liver cleanse. The day after the liver cleanse her blood sugar went up to 164 but was completely normal after that (under 100) and she did not dare take any more insulin or pills. We advised her to keep monitoring her blood sugar and be very, very vigilant and to please stop smoking.

John Angert, 65, was not on any medicine in spite of his diabetes. He was too embarrassed to tell us his blood sugar. He had a long list of other health problems, too. He was toxic with thulium (vitamin C) and palladium (from tooth fillings). He had a variety of parasites. After doing some dental work and parasite killing his fasting blood sugar dropped to a normal 98. But his leg cramps kept returning in spite of doing a kidney cleanse. Only after changing his diet to include milk did the phosphate crystals stay away and eliminate his cramps.

Cornelius Edens, age 33, came for his diabetes, although he also had fatigue, digestion problems, and headaches. He had numerous other minor symptoms like chest pain over the heart, soreness in testicles, etc. His diabetes was only diagnosed one year ago. he was on insulin (Humulin^{TM} 20 long acting plus 6 regular units) in the morning. He often omitted the evening dose which should be 14 long plus 6 regular. This brought his fasting blood sugar down to 166 in the morning.

He had pancreatic flukes in his testicles besides in his pancreas. His aflatoxin level was very high; he was told to stop eating grocery store bread, eat bakery bread only. He had silver, nickel and very high levels of gold–probably all three coming from his gold crowns–he was to have them all replaced with composite. He had fiberglass in his pancreas. Wood alcohol was present in large amounts in his pancreas as expected. He was to stop drinking all store bought beverages, whether frozen, powdered, or ready to drink. He did not test positive to benzene, propyl alcohol, *Salmonellas*, *Shigellas*, or *E. coli*. But he had *Staph aureus* growing at high levels in his pancreas. The usual source for this is in teeth, so he was told to ask his dentist to search for cavitations and clean up hidden tooth infections while replacing the gold crowns. He was to find the exposed fiberglass and seal it off. He was to zap parasites every other day for 1 month. His supplements were vitamin C (1 tsp. with each meal for constipation; then 1 tsp. daily), vitamin B-50 complex (2 per day), thioctic acid (2 per day). He was to start the Kidney Cleanse recipe for his testicle problem, and after 6 weeks do a Liver Cleanse. He was to follow up with us in 3 weeks, after dental work was completed. He never returned. Four months later we received a phone call he was too embarrassed to make himself. He needed no insulin and was doing fine. Another 3 months later he was still doing well, and off insulin.

Prediabetic

Alyce Dold, 64, came because she was worried about her blood sugar and chest pain. Indeed, a blood test showed her fasting blood sugar to be 136, just beginning to show insufficient insulin production by her pancreas. She had pancreatic flukes and wood alcohol there. Also *mumps virus* and *HA virus*. She had six more solvents accumulated due to eating raisin bran and other cold cereals each day. She was glad to be forced off this routine: she switched to 2 eggs every other day with biscuits or bread (not toast) and cooked cereal in between. Her chest pain was due to dog heartworm and *Staphylococcus aureus* bacteria that originated at teeth #16, 17, 1, 32. The worms and *Staph* were killed with a frequency generator. She was referred to a dentist for cavitations and started on kidney herbs. Two weeks later, there was still a little residual heart pain due to *Staph*; dental work was not yet done. She was given chromium (600 mcg per day) to help her insulin regulate sugar. Her LDH (See tests) was still high from the recent heart stress, no doubt. But she had accomplished a lot and planned to get it all done.

Diabetes Of Childhood

The problem is the same for diabetes of childhood as for diabetes of later onset, but much easier to clear up, provided the whole family cooperates.

Wesley Evanco, age 6, had his onset at age 11 months. Prior to that he had chicken pox and his baby shots. He had pancreatic flukes and their reproductive stages in his pancreas as well as wood alcohol. He had no other solvents accumulated. The problem was clearly due to these two enemies of his small body. Wesley's father did not have pancreatic flukes but his mother had very high levels, along with wood alcohol. She had to clear hers up before Wesley could recover. She chose not to. She couldn't believe the connection. Our most persuasive efforts were not successful. We hope Wesley can forgive us all in due time.

Herpes

The *Herpes* family of viruses includes *Herpes Simplex Virus* (HSV) 1 and 2, *Epstein Barre Virus* (EBV), *shingles or Chicken Pox* (*Varicella zoster*), *Cytomegalovirus* (CMV) and some newly discovered ones.

Herpes simplex virus 1 is the virus that breaks out around or inside the mouth. We call it a cold sore because it often follows a cold in childhood. As children, we may get HSV 1 once or twice each winter. When they come more often the child's immunity is low. Adults who get repeated attacks also have low immunity (this is obvious from a blood test where the white blood cell count is less than 5,000 per cu mm).

Herpes simplex virus 2 breaks out in the genital area. It is often blamed on promiscuous sex but I believe it has quite different origins.

I believe the virus is introduced to our bodies by another large parasite. Perhaps it is pinworms, or *Ascaris*. Perhaps it is a tapeworm stage, picked up from dust and dirt.

I have some evidence that it is released from dog tapeworm stages when these are being killed by your immune system. It is probably the same tapeworm stage as releases the *Adenovirus* (cold virus) which would explain why children frequently get "cold sores" during or after a cold. (See Curing The Common Cold, page 357.)

Nevertheless, you would not get sick from these viral releases unless your immunity was lowered.

Herpes lives in your nerve centers (*ganglia*) and it is from here that you can be attacked after the initial infection. Evidently your immune system can destroy them as quickly as they emerge. But a meal of **aflatoxin** or other **moldy food** suddenly "gags" your white blood cells and lets a viral attack happen.

The viruses can also be "triggered" which lets them out of hibernation (latency) to multiply and travel along the nerve fiber to the skin. Triggers are things that put these nerve centers to work: sudden cold and heat, trauma from chafing and friction. Never drink water with ice cubes in it. Never eat hot soup with a metal spoon. Don't tweeze hairs.

Begin your prevention program by raising the immunity of your skin; this means removing all toxins from the skin. Use only natural lotions, softeners, cleansers on your skin made from recipes in this book. Health food brands are not superior. This will get rid of nickel, chromate, titanium, zirconium, aluminum, and benzalkonium from your skin and probably your whole body! Do laundry with borax and washing soda, only, to eliminate commercial detergent as a source, too.

As soon as you feel that warning tingle or sensation of *Herpes*, zap or use a frequency generator at 293 and 345 KHz (HSV 1) or 360 and 355 KHz (for HSV 2). Immediately take a **cayenne** capsule and 8 **lysine** tablets (500 mg each). The cayenne slows down travel of the virus along the nerve.

Attacks probably occur when the triggers act at the same time as an immune drop occurs. Immune drops happen frequently due to eating moldy food. Of course, mercury in amalgam tooth fillings keeps immunity chronically lowered. Many persons report they stopped breaking out with *Herpes 1* after replacing their amalgams. Stopping wearing tight synthetic underpants helps reduce *Herpes 2* out breaks.

When you get an outbreak, mop up a droplet of the blister fluid and prepare it as a specimen for yourself. If you search for it in your white blood cells when your attack is over, it will not be found because it is in hiding inside your nerve cells. Zapping does not reach them inside your own cells. Nevertheless, you can totally eliminate them by repeated zapping provided you kill them at their earliest warning. Evidently, they haven't multiplied yet, so gradually their numbers go down.

Even after you have been *Herpes* free for a long time, stick to your preventive principles. Avoid the trigger foods, peanuts, and chocolate, or be ready to zap. Avoid cold wind or direct sunlight on your face. Don't eat abrasive or acid foods like popcorn, nuts, toast, crackers, candy, citrus. Although you may stop the virus in its tracks by zapping, healing the lesion takes time. Keep the skin softened with a cornstarch or sodium alginate recipe (see *Recipes*).

A lysine mush helps too: crush a lysine table with a large wooden spoon, add a pinch of vitamin C powder and a pinch of zinc oxide. Save part of this mixture for later use. Wet a small bit of it with a few drops of water to make a paste. Apply to lesions.

Bazezew Hailey, 38, started breaking out in the genital area after a period of antibiotic use. She was started on lysine (500 mg, 8 a day), cayenne caps (one with each meal). She was to fill her prescription for Zovirax™ from her doctor, though. By the time she had it filled, the next day, her lesion had stopped enlarging, and she could reduce her supplements. Her skin was full of mercury, lead, strontium, aluminum. Her white blood cell count was low, showing low immunity. Her ratio of segmental to lymphocyte white blood cells was low, evidence for a chronic viral condition. Her bone marrow contained lead and radon. She stopped using toothpaste (strontium), salt, deodorant, detergents (aluminum). She got the metal out of her mouth and eliminated her radon problem by opening crawl space vents. The lead source was never found, but after she moved to a new house it went away. *Herpes 2* stayed away. A year later she still hadn't opened the Zovirax™ bottle.

Fatigue

Fatigue, whether minor or extreme, is always associated with blood sugar disturbances. The more disturbance, the more fatigue. We have three organs that do most of the sugar regulating: our **adrenals**, the **liver**, and the **islets in the pancreas**. In severe fatigue, that keeps you partly bedridden, all three organs are heavily parasitized. *Epstein Barre Virus* (EBV) is running amok in your body, as a rule, even when clinical culture techniques cannot find it. With your frequency generator and Syncrometer you can find it emitting at 380 KHz. Killing the viruses is not as important as killing the larger parasites and getting your organs functioning for you again. The viruses will go away by themselves.

The liver's role in blood sugar regulation is to get it out of storage when needed. When sheep liver flukes have taken up residence they're spewing their chemicals as well as their own bacteria and viruses into your circulation; it is surprising that the liver has any sugar in reserve and can function at all. Sheep liver flukes are commonly seen in fatigue syndrome cases.

The adrenals (the outer layer called the cortex) help to regulate the blood sugar in a complex way. Some adrenal factors influence the thyroid which is another energy-related organ. Both adrenals and thyroid have toxic buildups in fatigue cases! Their work is hampered.

The heart of sugar regulation is in your pancreas in the tiny islands of cells that secrete insulin, called the *islets of Langerhans*. Here we always find the pancreatic fluke in residence. It actually breeds there when wood alcohol accumulates in it. Wood alcohol is a common pollutant of food, even in artificial sugar which is often recommended to replace real sugar and spare the pancreas. There is wood alcohol in store-bought drinking water, fruit juice, powders meant to be stirred into beverages, even if they are health food varieties. It's probably being used to clean tubes and hoses in the manufacturing plant. The only beverage you can safely buy (not safe unless you sterilize it, though) at a grocery store is milk. Make your own beverages using recipes in this book.



Fig. 28 Bottling equipment should be rinsed with ethyl (grain) alcohol, not propyl alcohol or wood alcohol.

Your first step toward curing your fatigue syndrome is to kill the pancreatic fluke and all other living invaders of the pancreas, liver, adrenals and thyroid. Use a zapper. Drink milk or buttermilk for several days afterward to provide lactic acid for the "good" bacteria to feed and recover on.

Your second step is removing metal from your mouth, particularly gold. Gold from teeth and jewelry readily goes to the pancreas! Do everything in the *Easy Lifestyle Improvements* chapter.

Your energy can bounce back in a few weeks by attending your liver, adrenals and pancreas. Help these organs heal and grow strong again. Avoid food molds (read Moldy Food, page 381). The most powerful assistance to the liver is a cleanse. This will eliminate liver viruses such as EBV and *Cytomegalovirus* (CMV). Be patient. Do it on a schedule until you have over 2,000 stones out. Take **vitamin C** at least 3 gm/day, to help both liver and adrenals. Take **B_2** and **B_6** to help adrenals and kidneys. Take glucose tolerance factor, **chromium** (two 200 mcg tablets 3x/day). See *Sources* for all of these. Take these supplements for three weeks, then cut the dose in half, and take on alternate days only, as a hedge against possible pollution in these.

Although your energy may be normal in three weeks, you are at higher risk for fatigue than the average person. Reinfection with anything will put the new parasites right back where the old ones were. Other bacteria, solvents and toxins will head for the pancreas, liver and adrenals again because these are weakened organs. It could take two years to build your health to its previous level, but is well worth it to have youth, initiative, and a beautiful appearance again. Going back to school is a good use of your time when your initiative has returned but your physical strength is still not up to housework or a job. When your energy comes back to you, it is tempting to overwork: to clean the whole house or to get into some gardening.

It is better to be moderate today than in bed tomorrow.

Anyone who has suffered from Chronic Fatigue Syndrome (CFS) or recurrent EBV has learned that lesson well.

June Timony, age 38, was diagnosed with Chronic Fatigue Syndrome), EBV and *Candida* around 1½ years ago by her family doctor. She also had a thyroid problem and a high estrogen level (165 pg/ml). She had severe depression at times. Our test showed her body was full of bismuth (fragrance) and silver (tooth fillings) especially in the ovaries. She cleansed her kidneys and killed parasites but could not make up her mind to do the expensive dental work.

Janice Brown, age 21, had EBV with chronic fatigue and depression along with a dozen more symptoms. Her skin, kidneys, breasts, brain, ovaries and pancreas were all loaded with mercury, platinum and other metals. She was full of radon and bus exhaust and the plumbing was shedding cadmium. Rather than do all this she and her husband decided to move. Before the moving date arrived she had cleansed kidneys, killed parasites and done dental work and was feeling noticeably better. Then they moved. She immediately was very fatigued again and worried that the move had been in vain. This time she had a liver full of Salmonella and a return of phosphate crystals in her kidneys. But it was easy to clear up and it was a very useful lesson to her to avoid unsterilized dairy products. She was much more careful after this.

Dee Safian, age 36, came especially for her low energy. She had EBV once. It left her extremely nervous. We advised going off caffeine but not substituting for it by drinking decafs. Her tissues were full of arsenic from pesticide; her urinalysis showed kidney crystals and her eosinophil count was high 5.5% (parasites). She had sheep liver flukes and stages in her pancreas due to a buildup of wood alcohol there. In four months after killing parasites and doing a kidney cleanse she was much improved.

Josefina Linzer, age 32, came for her fatigue and depression. Her tissues were full of arsenic, PCBs, chromate (eye makeup), mercury, yttrium, radon and terbium. She needed tooth metal replacement but could not schedule it immediately. She had *Ascaris* and pancreatic flukes in her pancreas and reacted to sugar in her diet quite strongly, so avoided it. She also had *Strongyloides* and *Trichinella*. She killed all these with a frequency generator and started on the kidney herbs. Her wood alcohol buildup was coming from carbonated beverages. She went off. In 6 weeks she had done everything except the mercury removal and was feeling much better.

Brigette Dawn, age 21, had Chronic Fatigue Syndrome with EBV, along with other problems. She cleaned her home and cleansed kidneys, killed parasites, and did two liver cleanses. Still the fatigue would return two days later. Meanwhile, though, her infertility problem got solved (she got pregnant) and this encouraged her to continue the battle against fatigue after the baby was born.

Hector Garcia, age 14, was getting gamma globulin injections every three weeks for his chronic fatigue syndrome. He had pancreatic flukes in his pancreas, sheep and human liver flukes in his liver and intestinal fluke in his intestine. He had a buildup of benzene, propanol, and carbon tetrachloride as well as aflatoxin from his granola breakfasts. He also had *Candida* and measles in his white blood cells. He killed parasites with a frequency generator and went off the solvent polluted items in the propyl alcohol and benzene lists. He immediately (in 20 days) felt much better.

Dana Levi, age 16, had chronic fatigue syndrome and dizziness; he was not in school. He had pancreatic fluke in his pancreas, sheep, human and intestinal flukes in his liver! Both benzene and propyl alcohol were present in his immune system. As soon as the parasites were killed (with a frequency generator) and he changed a lot of his products, he felt better but soon lost his improvement. At the next visit, our tests showed a buildup of vanadium (from burning candles in his bedroom). When he stopped this, he was better again for a while only to relapse again. His propyl alcohol level was up as was aflatoxin. But getting a taste of normal energy gave him the determination to get himself well! He embarked on a liver cleanse program and still more careful food selection.

Dennis Dillard, age 16, was beginning to do poorly at school due to fatigue. He had to stop athletics although his regular doctor pronounced him well. He was also getting chronic sinus infections. His lungs and trachea had accumulated seven heavy metals: vanadium, palladium, cerium, barium, tin, europium, beryllium. His fasting blood sugar was low (73 mg/DL) and LDH very low (90 u/L; it should have been 160). The body makes LDH in response to lactic acid levels. When the muscles aren't making much lactic acid from their normal metabolism, LDH levels will fall too. Was he developing a muscle disease? The gas leak was fixed (vanadium), the garage was sealed off from the house to eliminate barium and beryllium but the other toxic elements came from his dental retainer. As soon as his retainer came out, and they stopped using flea powder on their dog, his energy became normal and sinuses cleared up. A year later he still had not been ill.

Evelina Rojas, age 12, was having extreme fatigue with mood problems and sudden fevers. She killed *Ascaris* and sheep liver flukes with the parasite program but promptly got them back due to a benzene buildup I believe due to using products containing an herbal oil. Her high levels of *Streptococcus pneumoniae* (cause of fevers), *Staphylococcus aureus* and *Nocardia* could not be eliminated until her three baby teeth (with root canals) were pulled. After that, she was well.

Elaine Perkins, 48, came specifically for her low energy and nervousness. She was toxic with arsenic, a substance that replaces energy with nervous excitement and exhaustion. She also had a backlog of antimony (using baby oil), aluminum, rhenium (hair spray), benzalkonium (toothpaste) and radon. In four months, she had the arsenic and three other toxins eliminated and already had more energy.

Neil Youngblood, 53, was so fatigued, he had to brace himself even while sitting. A blood thyroxin level (T_4) of 1.0 instead of the normal 7.5 mcg/DL explained his fatigue. He had a mouthful of assorted dental metals which were accumulating in the thyroid, inviting viruses, particularly CMV, into it. He had to be on four grains of thyroid to feel near normal. After he had all his tooth metal removed, he only needed one grain to feel O.K. This encouraged him to clean up more of his body.

Scott Pennington, 50ish, was on thyroid medicine for his hyperthyroidism. He had been on iodine-radium earlier. He had the *miracidia* of the intestinal fluke, sheep liver fluke, and pancreatic fluke in his thyroid! Adult human liver flukes were also there! His thyroid was toxic with iridium, nickel, tellurium and mercury (metal tooth fillings) and decane, TC Ethylene and pentane solvents. He had been drinking a great deal of regular tea, which let oxalate crystals deposit in his kidney and slow down the excretion of toxins. The parasites were killed with a frequency generator, he changed his diet to get rid of solvents. In two weeks he was feeling better, had more energy and better sleep. This encouraged him to do the dental work.

Skin Problems

Sebaceous Cysts

Your body, in its wisdom, keeps toxins together and out of harm's way by making a cyst out of it. All the *sebaceous cysts* I have seen are filled with *polychlorinated biphenyls* (PCBs).

Get rid of PCB sources in order to clear PCBs from your body. This can take 6 to 12 months. Change all detergents (for dishes, laundry, and body use) to borax and/or washing soda.

Commercial detergents are wonderful cleaners...

but are unquestionably toxic. Whether you have cysts or not, it is always a good idea to use borax and washing soda instead.

If you have a particularly visible cyst, try to poultice it to the surface. Washing away some of it would be a great help to your body. Read herb books on poultices or just take whatever wild leaves you can gather; make a mush out of them with a blender, mix with honey or homemade skin softener to make it spread like peanut butter and cover the cyst with it night and day, covered with a piece of plastic. The wetness has drawing power. The plant juices have other benefits. If you can't poultice and must rely on kidney excretion, be sure to take kidney herbs at the same time.

Skin Rash

Rashes can be caused by many things. To find the cause, follow a logical pattern. It may be due to:

- HIV
- Yeast and Fungus
- Allergy
- Childhood Diseases (rubella, etc.)

HIV is the most alarming possibility. Eliminate it first by testing for it. It's often too early for a clinical test to be positive for HIV, so use the Syncrometer (page 457). I often see the rash disappear within days of eliminating the virus.

Probably the most common cause of rash is **yeast**. *Candida* has a resonant frequency of 384-388 KHz. If you test positive for it, stop all commercial soap and detergent for all possible uses. Zapping *Candida* may drive it away for a few days. The fungus is hosted by another parasite but finds your skin quite satisfactory for a home, at least while your skin immunity is low. It may be low from wearing metal jewelry, having metal tooth fillings, aluminum (from lotions and soaps), cobalt (from shaving supplies), and zirconium (from deodorant.). When all these are removed, the skin will dry up quickly in open air or under a heat lamp.

In babies' skin, immunity is low from diaper chemicals (mercury and thallium), wipes, and soap and detergent chemicals. Tight fitting, mercury treated diapers are a modern atrocity. Always line them with a tissue and keep them loose fitting.

The skin that has rash or fungus should be dried with paper towels, unfragranced and uncolored, in order not to contaminate the cloth towels, and thereby transport the tiny infectious spores to other skin locations. You may use skin healers.

Only the skin healers given in *Recipes* are safe to use. Keep them refrigerated when not in daily use. Commercial lotions, including health varieties, all contain toxic ingredients.

Many adult rashes are due to **allergies**. Allergy to nickel is common, the reaction is easiest to see under rings or watches. The metal is pulled into the body for elimination. Since nickel is used by so many bacteria, especially urinary tract bacteria, it doesn't get eliminated, it gets taken up by bacteria. It also piles up in kidneys, adrenals, bladder and prostate where bacteria thrive on it. Strangely, it also accumulates in the male scalp (and in women's scalps who have male pattern baldness).



Fig. 29 Tight diapers are a modern atrocity, forcing mercury and thallium into the baby's sponge-like skin.

Allergy to strawberries, perfume, deodorant or chlorinated water, however different they are, can all be expressed the same way, in a rash. The liver has refused (been unable) to detoxify the chemicals in these items and allows them to circulate in the body. Not for long, though, since great damage could be done to brain and other tissues. Mercifully, the skin grabs these chemicals into itself. Ultimately, it must still be removed. The allergic reaction and your immune system come to your skin's rescue, although bringing you discomfort.

Why didn't the liver detoxify the chemicals given to it? The answer is based on a simple experiment. Try cleaning your liver (page 552) several times or until 1,000 bits of refuse have been washed out of the bile ducts. This relieves the back pressure on that part of the liver, and allows it to do its work again. The physiological details are not understood. Fortunately, the results are instantaneous. The day before the liver cleanse you would never eat a strawberry or peanut for fear of a reaction. A few days after the cleanse, your body “knows” which food it might tolerate and as you try a bit, you notice no reaction, no rash This simple experiment suggests that the liver couldn't detoxify these foods because of the refuse in its ducts.

Each liver cleanse “cures” a different set of allergies suggesting that the liver is compartmentalized—different parts having different duties. It follows that by getting all the stones out all your allergies will disappear. Experience shows this to be true, although it can take two years to carry out such a program.

Meanwhile, avoiding the offensive food or product is very important. It is quite destructive to bathe the brain in strawberry chemicals or your toes in maple syrup chemicals. Stay off allergy-producing foods and products even if you can tolerate a little or can be “desensitized” to them with shots or homeopathic methods. Use these methods for relief, not license to continue using items that tax your body.

Certain **childhood diseases** produce a rash and this can be diagnosed by testing for the suspected disease with a slide or culture of it. Then use a zapper to kill both the bug and any larger parasites that may have brought it in.

Hives

Sometimes your body will break out in hives instead of a rash. Again, gallstones in the liver and gallbladder are responsible. Do the Liver Cleanse.

Acne

The more severe cases of acne cover parts of the body as well as face and can pit the face so badly there is hardly any clear skin left.

In ten days you can reverse this, so most of the skin is beautifully clear. There are bacteria involved and skin oils of youth feed these bacteria. Acne has been extensively studied by scientists. Perhaps the true culprit was too big to be seen with a microscope or too small (antigen) to be recognized or just too unimaginable. I inevitably find *Trichinella*, one of the four common roundworms that infect humans.

Test yourself to *Trichinella* with the slide called "larvae in tissue." Search for it in your skin. It is generally believed to reside in muscles, especially the diaphragm, but in acne cases it is in the skin.

If you only have a frequency generator, set it at 404.5 KHz and at neighboring numbers, extending 5 KHz on each side, to be sure to include all eggs and other molt stages. Or zap.

Psoriasis, Eczema

Psoriasis and eczema are both caused by *Ascaris*. Their molting chemicals are quite allergenic; perhaps it is these that are affecting the skin. Since pets pick these worms up daily, there is chronic reinfection in families with pets. Keep zapping.

Bernadette McNutt, 34, had acne on her back, chest and face. She had been treated since teen age with ultraviolet light, Retin A, and antibiotics. She already had a history of shingles and fungus, two more skin conditions. Her skin was toxic with strontium and her kidneys had cadmium, silver and beryllium deposits inhibiting excretion. She had only one parasite, extremely high levels of *Trichinella*. Her children were also infected as was the cat. In spite of using parasite herbs for months she got no improvement until the baby was out of diapers. Then she cleared up.

Royce Hamilton, 17, had acne so dense on his face there was no good spot the size of a dime anywhere. He had it about one year. His urinalysis showed "amorphous" crystals (stones of all kinds) and a trace of protein. He had *Trichinella* worms throughout his organs. He was very fatigued. He was started on kidney herbs so there would be good excretion after killing the *Trichinella*. His thyroid and kidneys were full of zirconium and titanium from all the lotions he used for his skin. He didn't need deodorant. Evidently even his armpit bacteria had been affected. It took four months to clear his *Trichinella* although there were no young children or pets in the house. His face was beginning to heal, but three months later he had a recurrence, although his parent was not a carrier. After this, he cleared it up again and his face looked as beautiful as a child's.

Evan Knight, 36, had psoriasis at elbows and knees from age 9 but now it was spreading to his fingers and scalp. He occasionally had bronchitis and puffy eyelids, indicative of *Ascaris* but at the time of his visit he had *Trichinella* fluke stages and *Echinostomum* in his skin. He was started on the parasite program and in three weeks it was clearing instead of advancing. He switched to milk for his beverage to raise his immunity and removed the arsenic, formaldehyde and thulium (from his vitamin C) by doing the necessary cleanups.

Gerry Chastain, 41, had a red nose, erupted along the sides. He had been on sulfa drugs and Emycin.™ He had *Leishmania tropica*. He killed it in the office with a frequency generator and got immediate improvement but four weeks later it was back. He had four solvents built up in his body: benzene, TCE, TC Ethylene and hexanedione. This situation would make recovery impossible since he was no doubt reinfecting himself. He also had titanium, platinum and silver accumulated in his tissues and needed to replace his dentalware before expecting a permanent cure.

Floyd Oldham, 50s, was getting pimples on his nose. His whole face was red and flushed looking. His bowels were loose and he had some urinary urgency. He harbored two kinds of *Leishmania* (*braziliensis* and *tropica*). He killed the *Leishmanias* with a frequency generator and started himself on the kidney herb program. Five weeks later the pimples were gone but general redness had reappeared. The *Leishmanias* were still gone but this time he was toxic with cobalt.

Cobalt is known to promote skin cancers and also heart disease. This was discovered decades ago when an outbreak of heart disease occurred in England. It was traced to a pub (where they all partook) where cobalt was added to the beer to make the foam rise higher! In fact, the foam will just stay in place like a hairdo, if you add cobalt. It was made an illegal additive. Gradually, it has crept back into consumer's products: first toilet cake (blue), then window washer (blue), then dishwasher detergent, and now even mouthwash. If you see a blue colored product, **stay away from it**. It accumulates in the heart and skin. People with skin cancers often have cobalt build up.

Floyd stopped using all these products and cleared up again.

Grethe Driscoll, middle aged, wore tons of make up, so skillfully applied that scars from a face lift could never be detected. When she had minor breakouts, which usually occurred while away on a trip, it seemed like a catastrophe. She tried everything available but could not get to her parasite herbs until she was back home several weeks later. After one week on them (5 day high dose plus maintenance) her complexion was perfect again.

Crofton Thornton, 15, had an embarrassing case of acne. He had *Ascaris*, hookworm and *Strongyloides* (he also had migraines) all reacting in the skin. He stopped drinking commercial beverages that gave him solvents. He killed parasites electronically and with herbs and got a considerable improvement. But he still had *Strongyloides* one month later. Nevertheless, he had seen the connection and he knew it was just a matter of persistence to a clear complexion. Note, he should have had *Trichinella*—did I miss testing for it?

Warts

Could we get warts from playing with toads in childhood? We don't play with toads anymore. Yet we get warts. We don't know how we get them. But after learning how to get rid of them, you will probably know how you got them. Not all warts are the same. In fact, they might all be different: each one is made up of 5 or 6 different viruses, not just one as we had believed.

Peel a tiny fragment off one of your warts. Prepare it for testing by placing it in a small bottle. Add a few tsp. filtered water and a ¼ tsp. grain alcohol, Label it with the location you got it from: like "left middle finger knuckle. "First, search your body for other locations of this wart (organs that test positive to your sample). You can easily find them in your skin, of course. But also search electronically in your liver, spleen, muscles, stomach, heart, pancreas. **Notice how often they are present in the pancreas**. The pancreas seems to be a wart-virus heaven. Are they in the islets or the rest of the pancreas?

Without a zapper, you will need to find the frequency of each virus to completely destroy it. Attach your frequency generator and search between 400 and 290 KHz. When you find its resonant frequency, kill it by treating yourself for three minutes at 10 volts from a frequency generator. Will your warts fall off?

In a few days one or two of your warts will begin to shred. After a week you may lose one or two completely, and find that several more have become smaller. The remainder are unchanged. Continue to identify and kill them. Notice that they are not necessarily gone from the pancreas or other organs at the same time as they are gone from the skin. Perhaps warts are not the benign entities we have believed them to be. They may, in fact, ride into the body on some common bacteria, like *Salmonella*, or common parasite like pinworms or tapeworm stages.

Zapping doesn't reach all the viruses in a wart either. It takes repeated zappings to start the shredding and gradual killing of warts.

Guy Laird, age 11, had warts on his lips besides fingers. His job was feeding the three outdoor dogs. He was full of *Ascaris*. He had *Taenia pisiformis* and *Taenia solium* bladder cysts in his liver. These were shedding viruses into Guy. He was started on Rascal for six weeks (this was before the zapper was invented). Maybe his benzene buildup was responsible for letting so many parasites (and their viruses) survive and multiply in his body. He stopped using toothpaste, killed *Ascaris* (408 KHz) and some flukes (434 to 421 KHz) and improved his diet. All except one wart came off (without bleeding). He was given different chores, too, to reduce his contact with animals and their parasites.

Georgianna Mills, a middle age music teacher, broke out with warts all over her hands, at least 30 in total. A few months later she was diagnosed with bone cancer; she always wondered if there was a connection. She cleared up her cancer and killed her viruses and bacteria with a frequency generator. Nearly all her warts disappeared. But her indoor pet brought new parasites daily, especially *Moniezia* tapeworm stages. With each *Moniezia* infection (about once a month) she got new warts. She was never able to clear them completely.

I concluded that each wart is actually composed of 3 to 6 viruses and these viruses are distributed throughout our bodies! How satisfying to be able to rid our bodies of them, once and for all even in internal organs. There is a catch. Small remnants of some warts do not disappear in spite of killing most of them. More accurately, they disappear and then reappear in our internal organs. Could this suggest to us their true origin? Could it be a tapeworm stage?

Tapeworm Stages

Our bodies harbor numerous stages of tapeworms. But not the tapeworm itself, which may belong to a dog, cow, or pigeon. Tapeworms lead complicated lives, much like insects with their caterpillars, larvae, larval molts, pupae and eventual adults. Tapeworms shed eggs with the bowel movement of the animal host. The eggs blow in the dust and reside in the earth. A vegetarian animal nibbling vegetation near this filth, or licking dirt and dust off its coat, swallows the eggs. Humans, too, eat plenty of filth by licking their fingers. As children we all eat dirt simply by eating with unwashed hands.

The Jewish society discovered the great importance of washing hands before eating, thousands of years ago. But many of us choose to ignore truths that seem old fashioned. In our own relatively short life times we cannot see the whole picture as well as the prophets and seers of ancient cultures could. We eat plenty of dirt and along with it, the eggs of tape-worms. Dog and cat tapeworms are most prevalent, but sheep, cow, pig, and seagull tapeworms are also common.



Fig. 30 Some cysticercus varieties (types) have multiple heads.

There is hardly a predator species in existence that doesn't have its own characteristic tapeworm. Whatever animal species you live near, or once lived near, you probably swallowed some of its filth and some tape eggs. The **eggs** hatch in your stomach and the tiny **larvae** burrow into a neighboring organ without any consideration that this is your stomach wall or spleen or muscle. The larva's plan is not to grow into a long worm—that can wait. The larva must simply survive until you can be conveniently eaten! A wolf or a tiger will surely come along! In bygone days it did.

The larva is about ¼ inch long, surrounded by a "sac of waters," like a tiny water balloon. Looking very closely at this sac, called a **cysticercus**, we see a head (scolex), complete with hooks and suckers, turned inside out, inside a bladder.

As the tiger's teeth bite down on the cysticercus, the pressure pops it out. The head is now right side out with hooks and suckers ready for action. Now it grows in the tiger!

It quickly hooks into a loop of intestinal wall so it can't be swept away and begins its growth into a regular long **adult** tapeworm. The tiger is the true or **primary host**. We were merely the secondary or **intermediate host**. Why does the adult tapeworm prefer the tiger instead of us? Only Mother Nature knows. But the best way to get to a carnivore is through its prey.



Fig. 31 Emerged cysticercus.

You can find these larval cysts in your organs using slides of the *cysticercus* stage of various common tapeworms. Search in your muscles, liver, stomach, pancreas, spleen, intestine and even brain. **You will not find even little bits of them in your white blood cells**. My explanation for this curious finding is that the tapeworm leaves no debris to be cleaned up by your white blood cells. Evidently your body builds a cyst wall around the larva to tightly encase it and prevent toxins and debris from entering your body. Thus your white blood cells are not alerted in any way. Of course, the larva is much too big to be devoured by tiny white blood cells anyway. Yet, it seems that if a pack of white blood cells had attacked the larva just as soon as it hatched from the egg they would have been able to devour it. Perhaps it enlarges too rapidly. Perhaps our white blood cells are preoccupied. In any case, we begin to load up on tapeworm stages from infancy and by the time we are middle aged we have dozens tucked away in our organs.

Some do die in the course of time. Perhaps their true secondary host is a rabbit or a mouse instead of a human. The short life span of these other hosts might mean that the life span of the *cysticercus* is also quite short, not 40 years! When they die, the white blood cells do clean them up and we can see them in our white blood cells at this time. It can take several weeks for the *cysticercus* to be completely gone by this natural method. During this time, we become ill! Numerous bacteria and viruses spring up, as if from nowhere, in our organs.

Don't be surprised if you are testing yourself during illness to find a tapeworm or two in your white blood cells! It is well worth searching for at such a time. Help your body dispatch the tapeworm stages all together with your zapper. A frequency generator is bound to miss some. Some cysticercus varieties consist of many heads, and each head has even more heads inside it! These might have different resonant frequencies. Only killing them together has the desired effect. Remember bacteria and viruses are released by killing tapeworms, so always follow with a second zapping in 20 minutes, and a third zapping 20 minutes after that. Only then can your tapeworm-related illness disappear.

If you do nothing, your body will be kept busy killing bacteria and viruses as the tape cysticercus wears down and eventually dies. You may not wish to identify all of them (but at least search for *Adenovirus*, the common cold) and just note where you are being attacked: your nose, throat, ears, lungs, bronchi. Internal organs are attacked too. It seldom takes more than three weeks, though, for your body to clean up a tape stage even without any help from a zapper. The attendant illness will be gone by then, too.

Watching these events in your body gives you insight into the very powerful forces at work, called immunity or body defense. The body "knows" a great deal more than we have surmised. There is yet so much to discover.

What initiated the death or dying process of the tapeworm stage in the first place? Has your body been trying all along and finally succeeded? Has the *cysticercus* reached the end of its life span naturally? Have its (the tapeworm's) own viruses and bacteria gotten the upper hand and killed it? Did it accidentally absorb something that killed it?

By taking a herbal combination, Rascal, you can soon find a tapeworm stage in your white blood cells where you could not find it earlier. It is now dead or dying. This proves the effectiveness of Rascal, even though it is slow.

Since we all eat dirt and inhale dust that is laden with dog feces or other animal excrement, we all harbor tapeworm stages, although none may be present in our white blood cells. **Are they harming us?** Perhaps they are living out their lives as quietly as they can in our organs, the way mice or ants try to live in our dwellings. Yet, when tapeworm stages are being killed, either spontaneously by your body or with a zapping device, we see an assortment of bacteria and viruses spread through the body, including the common cold.

Getting rid of the tapeworm stages in your organs seems a very worthwhile goal. Since each of us has been associated with dozens of animal species in our past, we probably have dozens of varieties of tapeworm stages in us. I cannot identify more than a handful due to lack of prepared slides. You can find them without identifying first, though, by listening to their emission frequencies. Their emissions are often extremely weak, possibly due to being encased in a cyst. Search between 510 KHz and 410 KHz. You may wish to "track" them for a while before killing them. You may wish to search for identical frequencies in your pet's saliva. Or you may wish to dispatch them as rapidly as possible. Use the zapper, not a frequency generator. Remember to "mop up" after your tapeworm killing by zapping again to kill bacteria and viruses that have been released from the tapeworm.

You may be disappointed not to feel any different after ridding yourself of numerous tapeworms and their pathogens. Evidently, the tapeworm stage itself doesn't make you sick; it is simply there like a wart is there, without making you sick. Its viruses can make you sick. Depending on which virus it is, it can make you very sick or not sick at all. Different viruses invade different organs. And some of these turn into warts!

The Flu

Influenza is a virus that can cause “the flu.” Does it belong to us as humans or to a larger parasite we are hosting? It is easily transmitted from person to person and in less than a year can spread across the planet. Some flu examples are Influenza A, B, C and Swine flu.

However, much that is called “flu” is actually caused by a bacterium, either *Salmonella* or *Shigella*. If someone in your family is “catching” a flu, test their saliva for the presence of dairy products, implicating the *Salmonellas* and *Shigellas*. Also test for influenza A, B, and C. Children's “flus”, especially when there is a fever, are usually due to *Salmonellas*. Even after zapping it can take an hour for the symptoms and fever to go away.

Go straight to the refrigerator and throw away all dairy products. Throw away all milk, cheesecakes, buttermilk, cream, butter, yogurt and cottage cheese, deli food and leftovers. You may wish to identify the food source of your family's bacteria first, and save the uncontaminated food. Use the sick person as a subject, searching for foods that appear in her white blood cells (or search their saliva sample for the food offender). If the flu is “going around” your neighborhood, you might wish to tell some of your neighbors which foods you found were contaminated. They may have purchased the same food! Obviously, when a contaminated shipment of dairy products arrives in your grocery stores, quite a few people will be consuming it, setting the stage for a “bad flu” that “goes around”.

Why can some people eat contaminated food without getting sick? Maybe their *Salmonellas* don't multiply rapidly. Maybe their stomach acid is strong enough to kill most of them. Maybe their bowel movements are frequent enough to expel them quickly. Maybe they haven't been on frequent treatments with anti-strep antibiotics. The answer is not known yet. After a serious bout with *Salmonellas* or *Shigellas* the body does not completely clear itself of them. They stay in hiding somewhere. When a new batch of bacteria arrives, even though very sparse, as in 1 tbs. of milk, the two subtypes can hybridize and produce a much more vigorous offspring. This is called *virulence*. You are made much sicker by more virulent subtypes of bacteria. You may have diarrhea, vomiting, illness. Especially if you believe you have “lactose intolerance,” pay attention to *Salmonella* and *Shigella*.

If your flu is due to an influenza virus, kill it with your zapper. Some family members may prefer to take a homeopathic flu “remedy” such as Oscillococcinum™ or Flusolution.™ Others may take herbs. These probably act by prying the viruses out of your cells' gateways and channels so the white blood cells can easily devour them.

But flu due to *Salmonella* is not easily zapped away. Remember, the zapper current does not penetrate the bowel contents, which is exactly where *Salmonella* lives! Besides zapping to clear them from your tissues, you must eliminate them from the bowel by using the Bowel Program (page 546).

Lugol’s iodine solution (see *Recipes*) can quite quickly get rid of Salmonella throughout the body. Use 6 drops (small drops from an eyedropper) in ½glass of water four times a day. If no more *Salmonella* is consumed, it will be vanquished in a day or two.

If your flu brings you a fever, use Lugol's.

Fever

Fevers are there to help your body fight the invaders...up to a point. Don't use a fever medication unless the body temperature goes over 102°F, and then only enough to bring the fever down a bit.

Most fevers, especially **"fevers of unknown origin"** are due to *Salmonellas* and *Shigellas*. Your body may be young and strong enough to kill them but not strong enough to kill an everlasting supply of them coming from dairy foods you eat on a daily basis. Stop eating salads at restaurants immediately. Stop eating food made by others' hands unless it is sterilized. Stop eating dairy foods until you have cooked them. Stop eating those that can't be cooked.

Sam Ellis, age 7, had two episodes of severe abdominal pain with fever lasting two weeks. He got hyperactive with milk products, had a frequent cough and stuffy nose. (Here the picture is quite clear. The milk products were bringing him *Salmonellas*, *Shigellas* and other bacteria which grew in his intestine to produce pain. But why only Sam and not his brothers?) Sam had a buildup of benzene from using bathroom soap containing a special herbal oil. Sam also had hookworms, intestinal fluke, and rabbit fluke, probably due to his lowered immunity from the benzene. Then his mother boiled Sam's milk, removed the polluted soap (she planned to use it herself!) and killed his parasites with the parasite herbs. His fever went away and stayed away. He said he enjoyed all this because now he "could play after school" without a stomach ache and he wasn't being sent to the nurse's office because of a fever. Notice the bacteria causing the temperature went away by themselves, probably due to the return of his normally strong immune system.

Jalene McCormick, 46, had been passing lots of kidney stones (hundreds) for years and had a temperature most of the time for which she was on antibiotics. It took her six months on our kidney herb recipe to dissolve and pass so many they no longer showed up on X-ray, and to stop making them. Then her fever left, not to return.

Kristen Jane Johnson, a young mother, had recurrent fevers and fatigue but, besides EBV, her doctors found no cause. We found HIV virus and a lot of bacteria and parasites. The fever-causing bacterium was *Salmonella*. To stop her *Salmonella* attacks she had to raise her immunity besides boiling all dairy products. Moldy foods (pasta) and lunch meats (benzopyrenes) were the source of liver toxicity. Each new *Salmonella* attack immediately invaded the liver so a vicious cycle was set up. When she stayed meticulously on the parasite program, meticulously off unsterilized dairy products, and meticulously off benzene-polluted items, she cured herself of fevers and night sweats and the HIV infection. Perhaps in two years the liver will have recovered enough to kill *Salmonella* that enter it, but she is not taking any chances till then.

Although Kristen was eating food polluted with both *Salmonellas* and *Shigellas* she only “picked up” *Salmonella*, never *Shigella*! Why is that? In contrast, people with multiple sclerosis “pick up” *Shigellas*, not *Salmonellas*.

Multiple Sclerosis & Amyotropic Lateral Sclerosis

Multiple sclerosis (MS) is a disease of the brain and spinal cord. It is called *lateral sclerosis* if the disease is mainly in the spinal cord.

It is caused by fluke parasites reaching the brain or spinal cord and attempting to multiply there. Any of the four common flukes may be responsible. Kill them immediately with your zapper or a frequency generator (434 KHz to 421 KHz). They cannot return unless you reinfect yourself. Stop eating meats, except fish and seafood. All meats are a source of fluke parasite stages unless canned or very well cooked. Pets and family members are undoubtedly carriers of the same flukes, although they do not show the same symptoms. Give away your house pets. Don't kiss your loved ones on the mouth. Make sure your sex partner has also been freed of fluke parasites.

The most important question you must be able to answer is why did these parasites enter your brain and spinal cord? When the brain contains solvents, it allows flukes to multiply there. The solvents, **xylene** and **toluene** are common brain solvents always seen in MS cases. Evidently these solvents accumulate first in the motor and sensory regions of the brain, inviting the parasites to these locations.

Xylene and toluene are industrial solvents used in paint and thinners. It is also a pollutant of certain carbonated beverages (I found it in 7-Up,™ ginger ale and others that I tested). Stop drinking them.

All MS cases I have seen also harbor *Shigella* bacteria in the brain and spinal cord. These come from dairy products. They are manure bacteria. Be absolutely meticulous about sterilizing dairy products. Even one tsp. unsterilized milk added to scrambled eggs could reinfect you. Not even heavy whipping cream or butter is safe without boiling. Kill bacteria every day with a zapper. *Shigellas* produce chemicals that are toxic to the brain and spinal cord. Eliminating *Shigellas* brings immediate improvement.

All large parasites like flukes have their own entourage of bacteria and viruses. Perhaps it is these that initiate the brain's reaction, which is inflammation and scar tissue formation in the outer covering of brain cells and nerve fibers. Perhaps it is the fluke stages themselves. Your brain is trying desperately to heal these lesions, only to be assailed by a fresh batch of solvent and *Shigellas* and another generation of parasites and pathogens.

The other pollutant associated with MS is **mercury** from dental metal. The mercury that is constantly released in the mouth does not all get excreted by the kidneys or eliminated by the bowels. Some of it travels up to the brain and gets into the spinal cord as well. You will be able to eliminate and excrete more mercury by doing a kidney and liver cleanse. The mercury may itself be polluted with **thallium** which is even more toxic. For this reason mercury removal should be done extra thoroughly to be sure no thallium has been left behind.

If you are concerned about MS-like symptoms, purchase slides of the brain regions, cerebrum, and cerebellum. Or purchase pork brains at the grocery store and snip out a portion of the sensory lobe and cerebellum. Prepare these as test substances (sterilize your hands afterward). Test your daily foods and body products for their presence in these brain areas. Also test for parasites, bacteria (especially *Nocardia* and *Shigella*) and other pollutants such as arsenic and pesticides. If the disease (tremor and lack of sensation) has not progressed too far, you can cure it. In all cases you can stop it from progressing further by cleaning up dentalware, the environment and diet.

Brandi Rainey, age 34, of Amish religious culture, was diagnosed with MS four months earlier after an MRI confirmed it although she had symptoms for many years. She was told she had inherited a gene for it and that Amish folk are particularly susceptible to MS for reasons of inbreeding. She had a constant pain running down the side of her neck, and headache. Her legs were getting too heavy to get up stairs. Our tests showed her brain was full of scandium (tooth metal alloy) and fluoride (toothpaste). Her vision was getting worse; her eyes were full of wood alcohol. She lost no time in getting dentures: there were no teeth that could be saved. She had several bacteria growing in her jaw bone: *Strep G* (sore throat bacteria), *Staphylococcus aureus* (this was raising her pulse to over 100), *Clostridium tetani* (causes great stiffness), and *Shigella* (produces nerve toxins). She killed these with a frequency generator. Five weeks later the pain and stiffness in her neck were gone, her pulse was down to 100, her periods were free of pain and her hands seemed to shake less. She was put on the parasite program plus thioctic acid (2 a day) and histidine (500 mg, one a day to keep nickel levels down)and advised to cook and eat with non metal. Four weeks later her pulse was down to 80, her legs were much better. She zapped four remaining bacteria. Two months later the numbness and tremor had left; her legs still felt tired and her hands sometimes shook but she was quite reassured that MS would not claim her life. Nor had a gene betrayed her. A half year later she was walking and working normally, doing liver cleanses and keeping up her vigilance against parasites and pollutants.

Kendra Welch, 56, was diagnosed with MS a year ago, by MRI. She went to a chelating doctor and this cleared up her temporary ischemic attacks (T.I.A's) which were occurring daily. But she had lost her balance, eyesight was getting worse, her feet and hands stung. Her sister also had MS but nobody else in the family did which baffled her doctor. Her brain tissue was full of barium, europium, gadolinium, and platinum. These are dental alloys, although barium could come from bus exhaust (she wore no lipstick). She was advised to have all metal removed from her mouth immediately. Two days afterward she came into the office without any neurological symptoms. She stated she was afraid to stop her new health program, though, and this was good policy.

Lynne Ceretto, age 15, was diagnosed with an “MS-like syndrome” by MRI. She had intestinal flukes and stages, human liver flukes and *Trichinella* in the brain. She had no tooth fillings. But there was benzene in her thymus keeping her immunity low. She also had propane and asbestos in her brain from leaky pipes and a worn washing machine belt. She, too, was told she had a “bad” gene. She was barely able to walk with help. It took several months to track down the source of benzene—the drinking water. Sometimes it was polluted; sometimes it was not! When the pump was oiled, some of it dripped onto the cement platform. Rain washed it to the center and down the pipe in the well. They eagerly removed the platform, found the oil on the water surface, cleaned everything up carefully, until no benzene could be found which put her on the road to recovery. A year later she had recovered further.

Norma Luellen, a young mother, had tingling, numbness and weakness on the entire left side of her body. She was in process of clinical tests for MS. Her body was full of pentane, possibly from her workplace since 12 other persons working there also had MS (such a situation should make our government eager to jump at investigations)! She had intestinal flukes and their stages, not in the intestine or liver or thymus, but in her brain! We found her home air toxic with bismuth too, probably from cosmetics. In spite of staying on the parasite program she got reinfected with sheep liver fluke, probably from eating hamburgers. She was not able to stop her carbonated beverage habit and frequently showed xylene, acetone, methylene chloride in addition to pentane in her white blood cells.

Shannon Synder, age 44, had been getting more numb over her whole body for several years and was presently considered by her doctor to have MS. Her muscles twitched all night, making sleep impossible, and her hands shook. She had intestinal flukes in the brain (cerebrum and cerebellum) but none in the intestine! The brain also had wood alcohol from drinking Diet Coke.™ She also had bismuth (cosmetics), palladium, copper, samarium, and tellurium (tooth alloys) in her brain. She began to improve enough to be off Prednisone by her 10th day of the parasite program.

Erica Blake, age 41, was diagnosed with MS two years earlier although her symptoms went back 13 years. She was on Prednisone™ but her balance was getting so bad she had to be in a wheelchair. Chelation treatments kept her from deteriorating further. Her brain was full of gasoline; she used to work at a gas station and now was getting it from the attached garage. Her hands and feet were completely numb. She had 5 root canals extracted and a few days later was able to stand. She could now walk with a cane. She had human liver flukes, sheep liver fluke and *Trichinellas* and dog tapeworm stages in her cerebellum (motor control center). After killing parasites and starting to take thioctic acid (4 a day) and cleaning up her environment she improved enough to drive a car again, walk without a cane in her home. She regained enough feeling in her hands and legs to do her housework, too.

Kurt Nielsen, age 43, was told he had peripheral neuropathy. His feet were so numb he had to look at the clutch to drive. Also both hands were numb. He was full of kerosene and benzene possibly from fuel oil that he pumped for a living. There were fluke stages in his brain and a dozen bacteria and viruses. He also had mercury and thallium in his immune system which came from tooth fillings. However, he had all his metal fillings replaced two years earlier! He thought there was no mercury left in his mouth! Actually, he had little bits (called tattoos) left somewhere. And they were giving him the classical symptoms: numbness of hands and feet and gradual destruction of his nervous system. His peripheral neuropathy was due to thallium poisoning. The dentist couldn't find tattoos, and he was left in his predicament. (This was before I found mercury and thallium sources in many personal products.)

Duncan Wood, a middle age father of 5 young children, could still slowly shuffle along when he arrived. He could not raise his arms to eat. He had uncontrolled inappropriate laughter every minute. He was diagnosed with MS two years earlier and told he had a "bad" gene. The fact that one child was beginning to show similar symptoms strengthened their belief in the gene theory. Ten days later his inappropriate laughter stopped; he could get his right hand to his face, he walked twice as fast and had very little tremor remaining. Strong chelating treatments obtained at a Mexican clinic had drawn much of the mercury and thallium out of his brain. He killed the flukes and *Shigella* bacteria electronically and stopped consuming unboiled milk. The brain solvents, xylene and toluene were removed quickly, too, as well as asbestos. His fast improvement showed them how important it was to remove the source of these pollutants in his home.

Two days later he regressed considerably which made him feel quite depressed, since his chelating treatments had not stopped. Was there still an unknown factor? It was a return of *Shigella* bacteria! He had inadvertently eaten a non-sterile dairy food: milk added to soup when it was already done cooking! This was a valuable lesson. Nothing else had returned. He was away from the asbestos and xylene from the workshop at home. He zapped the bacteria again and applied greater vigilance to eating only sterilized dairy foods. He recouped his losses in one day.

Then they scheduled their dental work, which had already been done once two years ago! He had leftover mercury and thallium. Now, selecting a dentist with experience in finding tattoos and cleaning cavitations made much more sense to him than it had before. He also planned to do a kidney and liver cleanse after returning home. And to stay out of the workshop until the asbestos-containing belt had been replaced and the furniture painting had been moved to a different building.

Shigella also causes irritability and depression, a frequent problem for MS cases.

High Blood Pressure

High blood pressure is one of the easiest problems to correct without resorting to drugs.

The most important change to make is to stop using caffeine as in coffee, tea, or carbonated beverages. Don't use decaffeinated coffee or tea either because of the solvent pollution in them. Switch to hot milk or hot water if a hot beverage is desired, or any of the beverages given in the recipe section. If being without caffeine leaves you fatigued, take an arginine tablet in the morning (500 mg).

Blood pressure is mainly controlled by the adrenal glands which sit like little caps on top of the kidneys. Whatever is affecting the kidneys is probably affecting the adrenals, too, since they're so close to each other. You must find out what it is.

You could do your search in the kidneys since kidney tissue is available in grocery stores. Adrenal tissue is available on microscope slides. What will you find? Probably **cadmium**.

Search for the cadmium source in your drinking water! Cadmium comes from the metal pipes. In fact, you could scrape a galvanized pipe to get a cadmium test substance. Conducting or storing drinking water in containers of metal is as foolish a practice as eating food off the floor. Water picks up everything it touches simply because it is wet! You may not see what it picked up any more than you can see if it has picked up sugar or salt. The cadmium and other metal is dissolved in the water. The older the pipes the softer, more corroded they are, and the more metal is picked up as the water rushes by. If you find cadmium in your hot or cold water, you will never be able to filter it out. Nor should you switch to bottled water. The amount of cadmium in your clothing from doing laundry with this water is already too much for your adrenals and kidneys.

Change your galvanized pipes to PVC plastic. If you believe you already have plastic pipes or all copper (which leads to leukemia, schizophrenia and fertility problems) you will need to search every inch of plumbing for a very short piece of galvanized pipe left in the system! A piece as short as a 2 inch T or Y can be causing all the trouble.

The toxicity of cadmium, in fact, the high blood pressure connection, has been known a long time. After finding the cadmium start on the kidney cleanse. You might miss the cadmium problem if you don't attend to it first. Also remove all metal from your mouth.

All (100%) cases of high blood pressure I have seen could be easily cured by eliminating cadmium and other pollutants, followed by cleansing the kidneys.

To test whether you still need your blood pressure medicine, wait until your pressure is down to 140/90 or better. Then cut the dose in half. Check it again next day. If it has climbed back up you are not ready; go back to ¾or a full dose of medicine. Try again a few days later. If your blood pressure stays down, cut your medicine in half again (you are now down to ¼ the regular dose) and see if your blood pressure stays improved.

When you are down to 130/80 go off completely. But stay on the kidney herb recipe. At 120/80 try yourself on a few shakes of sea salt. The amount of salt eaten, once the pressure is down, has little influence. In fact increasing salt intake improves energy without raising blood pressure. Take no more than one teaspoon a day (2,000 mg sodium), total, including cooking. Better yet, make a salt that is a mixture of sodium and potassium chlorides (see *Sources*). Mix it for yourself in a 1 to 1 ratio or whatever your taste can accept. The sodium portion could be sterilized sea salt (test and make sure it has no aluminum silicate in it first).

Mold toxins have specific kidney effects! Especially **T-2 toxin**, found mostly in dried peas, beans and lentils. Rinse these thoroughly first, throw away shriveled ones, and add vitamin C to the cooking water. All cases of serious kidney disease show a build up of T-2 toxin. Be extra careful to avoid moldy food (read Moldy Food, page 381).

Bala Cuzmin, age 72, had high blood pressure for ten years but the upper (systolic) pressure remained high in spite of various medicines that were tried. She had three kinds of kidney stones and only one functional kidney. She stopped using caffeine, switching to arginine tablets to get over the let-down. Her diet was changed to reduce phosphate and add calcium, and she took magnesium and Vitamin B_6 to assist the kidneys. She was very anemic and her mean cell volume (MCV) was high due to *Ascaris* infestation. She killed parasites, cleansed kidneys but saw no drop in blood pressure which stayed at 150 to 170 systolic. Her adrenal glands were choked with copper and platinum. She had all the metal in her mouth replaced and promptly saw a blood pressure drop to 145-1 50. Three months later it was at 128 to 133 on half her medicine. She had not been tested for T-2 toxin yet, nor changed her copper water pipes.

Sabrina Patton, 66, had a long list of health problems, including high blood pressure for six years. She was on Corgard™ and diazide drugs which kept it down to 140-160/74-80. She had phosphate crystals in her kidneys and was started on kidney herbs and a diet change to include milk and exclude soda pop. She had high levels of mercury and copper in her immune system. She was feeling so much better after the kidney cleanse that she decided to remove her last fillings and replace her bridge, too, since it was shedding ruthenium. On her way home from the dentist, her ears stopped ringing and soon her blood pressure was down to 126/68. She was still on half a dose of drugs because she was too afraid to go off entirely. But when her pressure stayed down she found the courage to go off completely. This gave her the energy she wanted to play basketball with the grandchildren again.

Rolf Ehrhart, 61, had 80% blockage of heart arteries and high blood pressure for which he was on a Hydropres™ patch, Tenormin™, and Logol™ (diuretic). He had phosphate and uric acid crystals in his kidneys. He was started on kidney herbs followed by the parasite herbs. His *Ascaris* and flukes were zapped. He stopped using store-bought beverages. Then he could cut back on his medicines, measuring his blood pressure daily to guide him. After seven weeks it was down to 140/85, so he decided to do without medicine, a bit early. He was also getting chelation therapy and was now able to walk 2-4 miles a day. His next chore, which he approached gladly, was removal of all metal from his mouth.

Len Gerald, 45, was on Vasotec™ for high blood pressure. He was constantly sleepy; his blood test showed a low thyroid level in spite of being on Euthyroid.™ He was started on kidney herbs followed by parasite herbs. In two weeks, barely into his program, his blood pressure dropped. He had to go off his blood pressure medicine. It stayed at 126/80. He still had some *Ascaris* and other health problems but was highly motivated to clean them up, too.

Glaucoma

In glaucoma the pressure in the eyeball gets too high, putting pressure on fragile retina cells that do your seeing. The first question to ask is: "Is my blood pressure too high?," because there is a link between high blood pressure and elevated eyeball pressure.

Your blood pressure should be 120/80. Your doctor may say 140/85 is "not high." He or she is kindly refraining from giving you drugs until this level of pressure is reached. It is your tip-off, though, that something is not right and you should correct it now, when it is easy, and before other damage is done. Read the section on high blood pressure (page 210) to learn how to reduce it by going off caffeine, checking for cadmium poisoning from your water pipes, and cleansing the kidneys (page 549). Even though your doctor has explained how the tiny tube draining your eyeball is too narrow, you should ask: was it not too narrow before high blood pressure struck? Simply getting your blood pressure to normal is sufficient help for beginning glaucoma.

Antonia Guerrero, age 51, had glaucoma for five years and was deteriorating rapidly. She cleansed her kidneys, killed parasites and changed her diet to the anti-arthritic one since she also suffered from arthritis in her hands for ten years with painful enlarged knuckles. She didn't get relief from taking aspirin. She got rid of her asbestos toxins by bringing her own hair blower with her to the hairdresser. After seven months she had pain relief for her arthritis (without aspirin) and her glaucoma was pronounced stable by her ophthalmologist.

Tooth Decay

The strongest part of our body structure is our bones. The strongest bones are our teeth. How can they decay? We must look at the **enamel**, **dentine** and **root** of the tooth as well as the bone they rest in for some answers.

Scientists have already searched very hard and long for answers. But their work is hampered by commercial interests that try to shape the results. Since commerce determines which research can be done (that is, paid for) sacred territory can be ignored. For example, the effects of sugar-eating, gum-chewing, tooth brushing, fluoridation, tooth filling materials and diet can be ignored if it interferes with product sales. Trivial studies such as comparing shapes of toothbrushes, studying the chemical composition of plaque, and studies of bacterial structure and genes are done instead. Studies “at the molecular level” do not threaten existing industries.

Important research has lapsed since the 40's and 50's. Perspective on tooth health was sound and clear in the mind of Dr. Weston Price in the 1930's. His scientific studies stand as a beacon even today because truths, once found, do not change. He traveled the world over in search of good teeth. Anywhere and anytime he found them, he described the people who had them. This is excellent science. It lets you draw the conclusions. He described what he saw in a book, titled Nutrition and Physical Degeneration.[13] They came to these conclusions from the following observable facts:

1. Skulls of primitive peoples who lived along coastlines, such as Peruvians, Scandinavians and various islanders, and whose staple foods included fish daily, showed perfect teeth; not a single cavity in a lifetime. They had strong bones that didn't break even once in a lifetime of 45 years. Skeletal structure was fully developed, meaning the jaw bone was not undershot or cheek bones squeezed together, forcing the teeth to grow into a smaller than ideal space. Consequently, there was room for the wisdom teeth, and no need to crowd the remainder. They saw no crooked teeth or unerupted wisdom teeth. The authors estimated a daily consumption of **4 to 5 grams of calcium** in their fish containing diet.

Our daily consumption of less than 1 gram calcium daily is small by comparison. Our wisdom teeth erupt poorly, our other teeth are often crooked. But today bad teeth go shamefully unheeded because we don't need to chew our food, we can lap it (ice cream) or suck it, or gum it (applesauce).

2. These primitive peoples got all the calcium, magnesium, phosphate, boron and other bone builders they needed simply from eating (fish) bones. Mexican peoples got 4 to 6 grams of calcium a day from **stone-grinding** of corn for their staple, tortillas, instead of from fish.

---

[13] It is still available from the Price-Pottenger Nutrition Foundation, a non-profit organization that seeks to keep his observations alive. Their address is PO Box 2614, La Mesa, California 91943, (800) 366-3748.

Where do we get our calcium? Milk is our only supply. One quart supplies one gram. There is little excuse for a carnivorous society like ours to regularly throw away the bones of its food animals in view of our dire shortage. It leaves us dependent on milk alone. Milk has so many disadvantages. It is impossible to milk a cow by machine and not get a few manure bacteria, *Salmonellas* and *Shigellas*, into the milk. These bacteria are not completely killed by pasteurization the way more susceptible bacteria are. It takes boiling temperature to kill all of them. Why isn't milk sterilized? Water was sterilized for human consumption in distant decades. Chlorination of water is not ideal but it did sterilize the water. Milk could be sterilized by boiling or flash-heating.

Milk has other disadvantages: dozens of antibiotics, both by feed and by shot, bovine growth hormone, chemicals added in milk processing, the bad effects of homogenization, and allergy to milk. Yet, in a choice between milk drinking and bone loss, one must choose the milk. This would not be necessary if bones were properly salvaged–ground to powder and added back to the meat where it belongs–to offset the acidifying effect of the phosphate in meat. One gram of calcium is not much bone (½tsp.) but it requires a whole quart of milk. Bone powder added back to ground meat, soups, stews could greatly improve our tooth decay problem, bone density problem, and skeletal growth problems.

Softened teeth set the stage for decay; bacteria do the dirty work.

Zapping bacteria does not kill them all. The zapper current does not reach into abscesses under metal filled teeth or around root canals. *Staphylococcus aureus*, which we are constantly stuffing in our mouths as we lick our fingers, finds an immediate hiding place in a crevice where it can't be zapped. Many other bacteria hide here, too: those that cause ear ache, sore throats, bronchitis, stiff knees, joint disease. You can try zapping all the *Clostridia*, *Streps* and tooth decay or plaque bacteria. But the only way to successfully eliminate them is to pry them out of hiding and wash them away. This is a job for the dentist (see Dental Cleanup page 409).

Strep. mutans is considered to be the bacterium that causes tooth cavities. I have found it in milk, evidently another pasteurization escapee. All the more reason to sterilize dairy products.

Frannie LaSalle, 52, was getting compression fractures in her spine, but the weak bone condition was evident in her mouth (many teeth were loose—they could be jiggled!). Her gums were red and inflamed. A low thyroid condition (she needed 2½ grains a day of thyroid—in one day the normal body goes through 5 grains of thyroid products) contributed to this. Her blood phosphate level was high (4.7 mg/DL—should be below 4.0) and her alkaline phosphatase was 205, also high, showing she was dissolving her bones (including tooth sockets) at a rapid pace. Her whole system was too acid, as could be seen in elevated CO_2 levels (28, when 23-30 is normal).

Only the major minerals, sodium, potassium, calcium and magnesium can have an impact on this major disturbance. The dentist said she had to have all her teeth pulled and replaced with dentures. Her kidneys showed all three types of calcium phosphate crystals. She drank no milk. She had only three weeks before her oral surgery appointment. She was started on ½ cup 2% milk, 6 times a day plus 50,000 units of vitamin D (a prescription dose) to make sure she absorbed all the calcium. She also took magnesium oxide (300 mg. once a day) and vitamin B_6 500 mg (one a day).

She was started on the kidney cleanse to help activate the vitamin D and to help the adrenal glands make *estrogen*. Her estrogen level (5.2 pg/ml) was too low to get the calcium deposited back into her bones. She was also given licorice herb for their estrogen-like action to help with this and vitamin C, 1 gram (1,000 mg) 2 to 3 a day.

Her mouth care was to be as follows: potassium iodide (white iodine, made up by dissolving 88 gm potassium iodide in one liter/quart water). Purchase a new very soft toothbrush. Use no toothpaste or store bought floss. Use 2 lb. or 4 lb. (the 4 lb. is coarser) fish line (rinse first). Brush twice a day; floss only once at bedtime before brushing. Use 6 drops of food grade hydrogen peroxide for daytime brushing. Use 6 drops of potassium iodide for nighttime brushing. Use no mouthwash, chewing gum, candy. In three weeks her teeth could not be jiggled. Her dentist was astonished (but was not interested in how she achieved this). In six weeks her mouth looked normal and she could chew some foods. Her vitamin D was tapered as follows: Take 6 a week for the first week (miss one day). Take 5 a week for the second week (miss two days). Take 4 a week for the third week. Then 2 a week indefinitely. She never lost a tooth.

Muscle Diseases

There are a variety of muscle wasting diseases, thought to be genetic in their cause. Yet, what could be more easily inherited than a parasite? Persons living together share food, living habits. refrigerators, and parasites. Their shared genes indeed give them similar susceptibilities but if we take muscle parasites away, muscle diseases “magically” disappear.

Of course, there is no magic involved. It is actually hard work. Hard work to rid the whole family of parasites that are shared and possibly were present even at birth. Parasites that normally don't go to the muscles. For example liver flukes and intestinal flukes. They belong in the liver and intestine! Yet, in muscle disease they show up and reproduce themselves in the muscles. The reason for this becomes clearer when you see that certain solvents have accumulated there. Heavy metals, bacteria, and viruses have accumulated there, too. The host's muscles, instead of kidney and bowel, have taken on the duties of toxic dumping grounds. Could it be that the regular routes of elimination were overwhelmed? Or did the muscles, traumatized by these unusual parasites, invite the toxins? A tantalizing question.

But in seven minutes you can methodically kill everything and anything that is alive in your muscles and shouldn't be there. Zap until you are free of all parasite invaders. Your muscles will feel lighter afterward.

Muscular Dystrophy

In muscular dystrophy the solvents, **xylene** and **toluene** are seen to accumulate in muscles. These also accumulate in brain and nervous tissue! (See Alzheimer's page 269 and multiple sclerosis, page 204). Could it be that these solvents are actually present in the nerves of the muscles?

Fortunately these solvents will leave your body, by themselves, in five days after you stop consuming them! Stop drinking all store bought beverages, including water and powders that you mix, and including health food varieties. Water claims and health food powder claims sound as convincing and strong as a twelve inch plank to walk on. But if the plank leads out over the side of a ship, would you walk it?

Throw all your possible sources of solvents out. Flavored foods are the chief offenders (cold cereals, sweets and candy too). But of course, you should check in your basement or attached garage for cleaning solvents. Places where painting is done or automobiles are worked on should be off limits to you.

If you've been wondering whether you have muscular dystrophy, which I consider to be a fluke disease, search your muscles electronically. Use prepared slides of flukes along with a sample of hamburger meat to represent your muscles. If flukes have already taken up residence in them, you should diagnose yourself as "Positive". If not, but other parasites and toxins are present, you have pre-muscular dystrophy.

Also, the likelihood of finding thallium is quite high, judging by the case histories.

Mel Rickling, age 18, had been seeing a specialist for bouts of muscular weakness for several years, but no diagnosis was given. His condition was not yet severe enough although it was difficult for him to raise an empty glass or get upstairs. It began at puberty, not too long after his first mercury tooth filling. He had asthma in childhood. The flukes attacking his muscles were liver fluke, intestinal fluke, and pancreatic fluke. Other parasites in his muscles were *Leishmanias*, several dog tapeworm cysts, and pinworm.

He also had assorted bacteria in his muscles. The solvents propyl alcohol, benzene, toluene, and xylene were accumulated there too. Ortho-phospho-tyrosine (cancer test) was already positive. His doctors had not searched for cancer in their biopsies. His drinking water contained lead and since he had lived in one house since birth he was probably drinking lead every day of his life. He also had high levels of mercury and some thallium accumulated in his muscles; these came from the tooth fillings in his mouth and could explain why his problems began after his first filling was put in.

His flukes and other large parasites were killed immediately with a frequency generator. He was started on the herbal parasite program to prevent reinfection. His diet and body products were changed to exclude solvent pollution. He could have no commercially prepared beverages except milk which needed to be boiled to kill bacteria. In twelve days his daily stomach pains were gone, so he was able to eat more and gain some much needed weight. The rash on his face was gone, the pain at his right side was gone, his muscle twitches were gone, his joints no longer ached and his mood was much better. The whole family was put on the parasite program and Mel was scheduled for dental cleanup. The plumbing repairs removed lead from the water and he was soon able to walk upstairs, in fact run upstairs.

A young man, seeing himself regain normalcy, wants nothing more than to lead a normal life" which includes reckless behavior. But after several warnings from his muscles he stuck to his restrictions and gained the weight he wanted in order to participate in athletics.

Myasthenia Gravis

is probably a fluke disease. Some chemical, possibly coming from the fluke, may affect the acetylcholine receptors, thereby causing an allergic reaction so they become inefficient. This is most noticeable in the eyelids. They droop from lack of strength to lift them.

The thymus is often involved, too. The thymus is extremely sensitive to benzene and with so much benzene pollution in our products and foods (pollution from gasoline is negligible by comparison), you will probably find benzene accumulated there. Search the thymus and the muscles for parasites, bacteria and tooth metal as well as toxins in the foods eaten daily. Kill invaders twice a week with a zapper or stay on an herbal parasite program until all danger of recurrence is past (one to two years).

Clean up dentalware, diet and environment. Keep no indoor pets since any new parasite, however tiny, will surely find the niche left behind by the flukes and give you a new myasthenia gravis-like disease. The whole family must be parasite-free to protect the member with myasthenia gravis. But it is a task easily accomplished and desirable in its own right, so discuss your plan immediately with family members. Don't delay. The flukes don't waste a single minute. They go right on feeding and breeding.

Carmen Opsal, age 37, was told by her specialist she had her myasthenia from birth since she didn't have the strength to nurse. She had pancreatic fluke stages throughout her body. Her plan was to start on the parasite killing program, clean her kidneys, remove toxic elements, kill bacteria and clean her liver. Long before she accomplished this, in one month, she was feeling better and had return of her strength on some days. She still had the solvent, methylene chloride, from drinking “pure” orange juice and praseodymium from eating foil-packaged foods, also thulium from her brand of vitamin C. She was full of auto exhaust and nickel from dental metal. There was hafnium from nail polish and hair spray and zirconium from deodorant. She planned to get rid of it all, and never need to return.

Universal Allergies

If minor allergies are due to a disabled liver, then extreme allergies must be due to an extremely disabled liver. This is the case for persons suffering from "universal" allergies, namely "everything", like the lacquer on floors, plastic chairs, the neighbor's flowers, and the grocery store.



Fig. 32 Sheep liver flukes. Black threads in toilet are indicative of fluke remains.

They have more than merely clogged bile ducts. They have the sheep liver fluke living in the bile ducts! A tip-off to this situation is allergy to wool and wool fat (lanolin). A few flukes might not be noticed but a liver full of flukes that spill over into the intestine can give the worst case of allergy imaginable.

Sometimes the body manages to kill them with its own resources (maybe you ate something even too toxic for them!) They come through the bowel in a torrent. In the water of the toilet bowel they explode, spewing their infectious eggs all over in little black threads. Because these look like hairs, you may believe you passed "things with black hairy legs." These are actually burst flukes with black strings of highly infectious eggs. Why some people are literally taken over by these flukes is unclear. Amongst sheep, only certain sheep will be severely affected, being called "liver-rot." The disease in animals has been extensively studied.

Kill flukes with a frequency generator (434-421 KHz) or zapper. Come to the aid of the liver by avoiding food molds, removing dental metals, stopping chronic *Salmonella* infection and finally cleaning the kidneys and liver.

Environmental Illness

is another name for "universal" allergies. When more than a few flukes are present in the liver, they keep the liver from doing its major job: detoxifying all the food and chemicals that are taken into your body.

Different parts of the liver have different detoxifying jobs. One part detoxifies plastics and solvents, another part detoxifies perfumes and another newsprint ink, and so on. Foods have natural chemicals that need detoxification. By changing our food constantly we avoid overburdening any one of our detoxifying mechanisms. This is probably the basis for wanting different food at each meal and different meals each day. We somehow "know" when we're ready for the same food again.

Less extreme forms of allergy can be due to other flukes in the liver, such as human liver fluke (*Clonorchis*), or just plain clogging with numerous cholesterol crystals.

Anything that is lodged in the bile ducts obstructs the flow of bile. This causes back pressure in that part of the liver so it produces less bile.

The bile duct system is a gigantic tree with lots of interconnecting branches. Remember how "stringy" liver can be when you buy it in the grocery store. These strings are bile ducts. When one is obstructed, others take over its job. But when a whole section of the liver gets obstructed and it can't detoxify a whole set of chemicals you dare not get those chemicals into you again.

What if you do? These chemicals go coursing all over your body! They are taken up by various organs. The brain has special protection, called the *blood brain barrier*. But this can get broken by parasites that burrow. Now chemicals can roam through the brain. Some attach themselves and cause an "allergic reaction". Beryllium, from "coal oil," kerosene and gasoline attaches itself to the brain easily. Then other things attach themselves to the beryllium!

The extreme form of allergies simply requires killing the sheep liver fluke and other flukes inhabiting the liver. They tend to overflow the liver and inhabit the intestine, too. In this case, you might actually see some in the bowel movement after killing them. They won't let go of you as long as they are alive.

They have two attachments to hold onto you, yet, they are not difficult to kill, even with herbs. Use the herbal parasite recipe (page 338), zapper, or a frequency generator.

Sheep liver flukes might actually be breeding, that is, multiplying in the liver of the hyperallergic person. This is not normal. Sheep liver flukes "should" only spend their adulthood in our bodies. When the baby stages are also found in our bodies, (instead of in minnows or snails) there is undoubtedly a specific solvent involved. Environmentally ill persons have quite a few solvents accumulated in their organ tissues. Which one enables the sheep liver fluke to go through all of its development in the human is not known yet.

Obviously, the extremely allergic person, should remove all solvents from their diet and environment. Begin with eliminating propyl alcohol and benzene. The same products have other solvents too. It is processing of foods that puts solvents into them. Go completely natural. Dairy products are free of solvents, except for some cheeses. Remember to boil them to get rid of bacteria. Salt, olive oil, butter, and honey are free of solvents. With electronic technology, you can find solvent free products. Otherwise, if it didn't grow or you didn't make it from scratch, you must assume it has solvents! Cook from scratch, make your own pasta, bread, fruit juices, beverages.

Often, but not always, persons with sheep liver fluke, have a specific allergy to lanolin, a sheep product. Since lanolin is widely used in other products, this becomes a very broad range allergy. Such persons “can get no fat” at mealtimes or wear no wool without a considerable reaction. The allergy to lanolin does not disappear the day the flukes are all dead. But cleaning the liver with several liver cleanses (page 552) after killing parasites will start the recovery process.

Which comes first, the flukes or the solvents? That can't be answered. But what happens next is easily seen. The more flukes, the less able the liver is to detoxify solvents. The more solvents the better able the fluke is to multiply. A vicious cycle is set up that accelerates the illness.

Perhaps neither of these came first. Perhaps something else poisoned the liver so both solvents and flukes are given a home in your liver! Such a powerful liver poison would be a food mold: *aflatoxin*, *cytochalasin B*, *sterigmatocystin*, *zearalenone*, *ochratoxin, sorghum mold, griseofulvin, citrinin, T-2 toxin, Kojic acid, ergot* and others. Avoid food molds—see Mold Free Diet, page 365. The diet must be quite limited at first, to allow the liver time to "regain" its detoxifying capability.

Of course, it is assumed that environmentally ill persons have had their dental metal replaced by metal free composite. This includes gold. Gold accumulates in the pancreas, another organ of digestion. This may mean choosing partial dentures. Read the section on healing the jaw and Bone Strengthening (page 87) to ensure this move brings you success.

The liver is a versatile organ. It can regenerate itself but it won't if food molds block regeneration. Given half a chance it will become like new. After killing parasites do the liver cleanse (page 552). If it has been a month or more since you killed parasites, then go on a high dose parasite herb treatment the week before, or zap. Don't use the herbs the day of the cleanse. With one major allergy gone after each cleanse and by timing liver cleanses two weeks apart, it takes only six months to have a reasonably normal life again. You can endure indoor air again, sit on plastic chairs, read newspapers, wear cotton clothing and leather shoes without reacting. You must still be patient and careful as you take back the world for you to live in.

Delores Flores, 53, was brought by her husband to the driveway in front of the office. There she put on her mask and advanced to the outdoor bench. She did not dare to come in. Without doing any testing her condition was obvious. She must start killing liver parasites. But it seemed too simple to be believable. And she knew she'd be allergic to the parasite killing herbs (this was before the zapper). She decided to do nothing.

Patricia Humphry arrived wearing an industrial painters' mask. It smelled rubbery. Her winter boots smelled moldy. And a faint scent of mothballs came from somewhere. Even her car had an engine problem, spewing exhaust fumes into the driveway. I suggested she begin with some basic reading material on allergies. She did not return either.

Arlene Kelly, 50ish, could eat no fat—not the tiniest snippet. But at Thanksgiving she allowed herself a little gravy. The consequences were swollen eyelids, swollen face, swollen throat: quite a dangerous situation. After killing *Ascaris* and the flukes, and cleansing the liver (all in time for Christmas) she dared a little pie—and got along quite well!

Alcoholism

When the portion of liver that detoxifies ethyl alcohol (the drinking kind) is hampered you are at risk for alcoholism. The other contributors to alcoholism are **beryllium** and **ergot**. Perhaps there are even more contributors.

Beryllium is plentiful in coal products such as “coal oil”, and in gasoline to which kerosene or coal oil has been added. Fuel for “hurricane lamps” is a common offender, filling the air with beryllium. Liver blockage can force beryllium to circulate through the body; if it happens to attach itself to the addiction center of the brain, you're in a heap of trouble. Beryllium is very reactive. Any other allergen coursing by can react with it. If this happens to be alcohol–the drinking kind–you will be alcoholic unbeknownst to you.

When the liver is quite disabled, there may still be alcohol coursing through your body the day after you drank even a little bit! It is bound to find the beryllium stuck to the addiction center. Together, they turn the brain into a uncontrolled machine. Neurotransmitters are released that shouldn't be; others not released that should be. Mood is affected in a typically “alcoholic” way. Depression may be lifted—or caused!

Alcoholic persons should remove all fossil fuels from their environment, and never choose a career that exposes them to paint, cleaners, or automotive products. They should do liver cleanses until 2,000 stones or more are out.

Of course, they should never touch a drop of alcohol: not even the Black Walnut Hull Tincture in the herbal parasite program. The aqueous recipe should be made for them. Since alcohol is produced anyway, in the body, the liver should never be poisoned by molds, especially ergot: the very mold that is so abundant in alcoholic beverages! Alcohol and ergot interact to make each more toxic.

To help the brain recover its neurotransmitter status, take glutamine (500 mg.), a B-50 complex, and niacinamide (500 mg—to help detoxify ergot), with each meal.

To prevent alcoholism, protect your liver from food molds, especially ergot. Add vitamin C to nuts, pasta cereals, grains and even alcoholic beverages! Avoid fossil fuel pollution of your home by switching to all electric utilities.

Alcohol Addiction

There are many definitions of addiction. My definition is based on the special brain toxins, *beryllium* and *ergot*.

The brain has a region called the addiction center. If this center is stimulated it produces pleasure-chemicals. It is carefully controlled so that not too much pleasure or happiness can be experienced.

When a toxic substance, beryllium, is inhaled it circulates with the blood to the brain and may land at the addiction center. The more beryllium is inhaled the bigger the chance that it will occupy the addiction center. The brain cells in the addiction center have receptor sites for *glutamate* (the same glutamic acid that comes from the protein in our food). Normally, glutamate activates the addiction center. But when beryllium has “stolen” these seats, the glutamate is powerless to activate the joy and happiness center. The result is a low level chronic depression. The more beryllium there is to clog the receptors the worse the depression. Giving glutamic acid does not help but giving **glu-**

tamine does! Addicted or depressed persons should take glutamine, no less than 3 grams (3000 mg) a day. It comes in 500 mg. tablets. It is completely harmless.

When we drink alcohol or put it on the skin (as in mouthwash, tinctures, medicine) or produce it by fermentation in the intestines (*Candida* produces alcohol) a substance, *salsol,* is formed. Salsol reacts with beryllium. If the beryllium is in the pleasure center it reacts with it there. This reaction has the effect of activating the cells! Now a large amount of pleasure-chemical can be released. The amount is larger than normal because so many clogged cells are activated together. This explains the alcohol "high". In all the alcohol-addicted persons I studied, salsol was present, along with beryllium, on the receptor sites normally activated by glutamate (or NMDA or kainate). As we removed the beryllium we saw that the salsol also disappeared.

The solution to alcoholism is to avoid ergot contaminated food and avoid beryllium inhalation. We also remove the brain beryllium using **thioctic acid**. Stopping the use of alcohol may save a life or career but does not correct the problem. Even after 30 years of abstinence, I still see the beryllium present in the addiction center and the salsol, derived no doubt from endogenous sources, still attached to the beryllium. This is why the addiction is never gone even after years of abstinence.

If any member of the family is, or was, addicted to alcohol the house should be searched for beryllium sources. Hurricane lamps or antique lamps are the most common sources. Remove them permanently. Washing does not clean them. Remove all solvents, cleaners, lighters. Switch to a butane lighter. The air should be tested for beryllium. The garage door to the house should be permanently closed, and the car and lawnmower kept out of it. Addicted persons should not be painters! Nor walk into a dry-cleaning business. Soon you will see a more cheerful disposition in the addicted person and this will be rewarding for the whole family.

Miguel Alcorn's wife cleaned up the environment for Miguel, whose alcoholism was 30 years long. Even lighter fluid was removed. The garage was sealed off from the house. She added vitamin C to his meals so he didn't have to "take anything". She was very careful about moldy grains. He lost his preoccupation with drinking after killing parasites. She believes he is not sneaking any. Our hats are off to her.

Seizures

are always caused by tiny *Ascaris* larvae in the brain.

I suppose they find their way to the seizure center by accident. It is not normal for them to be in the brain, they typically travel between the stomach and lungs. *Ascaris* eggs are present everywhere in animal filth. Dogs, cats, horses and pigs all get *Ascaris*. Their excrement dries and flies about in the dust, but mostly it resides in the soil. Children playing in the dirt cannot help but pick up *Ascaris* eggs. The eggs hatch in the stomach and the tiny larvae, microscopic in size, travel first to the lungs. Here they go through a *molt*. This causes some coughing.

Whenever a child coughs for part of the day do not assume it is harmless. Use a frequency generator set to 408 KHz, or use a zapper. Children should be treated for *Ascaris* anyway, whether coughing or not, once a week. The tiny larvae are in the cough up. Children should not be taught to politely swallow this. They could be swallowing their own future seizures, asthma, or eczema. Teach children to use tissues for all spit up. The lungs are doing what they can to rid the body of these invaders. Your intelligence must cooperate with your lungs.

Ascaris do not come sweet and clean in themselves. They bring their own bacteria and viruses. One of these bacteria is *Bacteroides fragilis*. *Bacteroides* needs a host like *Ascaris* so it can be oxygen-free. Such a requirement is termed *obligatory anaerobic* meaning "must have absence of air."

Being transported to the brain inside *Ascaris* larvae is probably the means by which *Bacteroides* gets into the brain. Brain abscesses and brain tumors usually have *Bacteroides fragilis* growing there. Brain tumors will not shrink unless all the parasites, bacteria and viruses are dead. *Bacteroides*, in turn, are big enough to house thousands of viruses. Two common viruses seen with *Ascaris* are *Coxsackie* B_1 and *Coxsackie* B_4. Perhaps it is the toxins of the *Ascaris* larvae or *Bacteroides* or *Coxsackies* that induces the seizures. Maybe it is something else about the infestation that induces them. But by killing *Ascaris, Bacteroides* and *Coxsackies* (zapper or frequency generator at 408, 325, 364, 362.5 KHz) you have eliminated the first essential link in the chain of developments that causes seizures.

The brain does not quietly tolerate these invaders. It fights back with its immune system. But the wormlets are already too big to be eaten by white blood cells. The brain fights back by producing **inflammation**.

Inflammations are intended to attract calcium so a wall can be built around the intruders. Inflammations are negatively charged regions so the positively charged calcium can find its way to the inflamed site. But lead and mercury are also positively charged! Perhaps this is how these **toxic metals** are attracted to the brain. All metals are positively charged. Perhaps this is their fateful poisonous attraction to living things. Perhaps they do not poison when no inflammations are present! In seizure cases we see many tooth metals in the brain. These must be removed so the inflamed site can heal.

Other toxic substances have also found their way to the inflammation at the seizure center: **vanadium** from leaking household gas; **PVC** from new carpets; **titanium** from face powder; **zirconium** from deodorant; **asbestos** from the clothes dryer belt or hair blower; **lead** from tainted drinking water. Do a good clean up of your environment.

Solvents accumulate here, too. Especially **toluene** and **xylene**. These are found in paint (persons with seizures should never be around fresh paint) but are also found in trace amounts in carbonated beverages. A person with seizures should drink no commercial beverages: see the Recipe section for homemade carbonated and other beverages. There are several other specific brain irritants that accumulate at the seizure center.

The food fungus, **ergot**, is always seen in seizure cases. Perhaps it can act alone to produce seizures. After all, seizures are an ancient malady, existing long before chemicals and solvents were manufactured.

MSG, which is *monosodium glutamate* should never be used in food. It was already banned in infant food in Europe a decade ago. Why are we still allowing it? Are our children not as precious? Healthy adults may tolerate it better than young children. But what about sick adults? Specifically, adults with a brain illness? Glutamic acid is a natural constituent of protein in our foods. And the sodium glutamate it must form in the body does no harm. But MSG is not biologically produced. It is lab-made. Lab-made amino acids are not the same as biologically made. Perhaps it is these “isomers”, perhaps it is the simple overdose of a natural thing that is brain-toxic. Whatever the mechanism, MSG should not be consumed by anyone, let alone a seizure sufferer. Fortunately, you can ask at restaurants, where (not whether) MSG is used so you can avoid these foods.

BHT and **BHA**, standing for *bishydroxytoluene* and *bishydroxyanisole* are food preservatives and also seizure triggers. They are often put on the boxes of cereals, rather than the cereals themselves, so the cereals can be pronounced preservative-free. Imagine how much the box must be drenched with to prevent oxygen leakage into the interior?

A more insidious seizure trigger is a perfectly natural substance, **malvin**. Malvin is the natural dye found in grapes, strawberries, plums and blueberries. Stop eating strawberry and grape jam or juice. Chickens and the eggs they lay, have lots of malvin too, stop eating chicken and eggs.

Here are foods relatively free of malvin: artichokes, asparagus, almonds, barley, beans of all kinds, green beans, broccoli, Brussels sprouts, cantaloupe, celery, nectarines, citrus, dates, mango, pears, kiwi, pineapple, Granny Smith apples.[14]

To Summarize

To stop your seizures on a dime, and not have another one:

1. Avoid malvin in food. Eat nothing colored red or blue, chicken, eggs, MSG, BHA & BHT. Boil all dairy products or don't eat them.
2. Avoid ergot in food. Eat no whole grain products; take niacinamide 500 mg three times a day to help the liver detoxify tiny bits in other foods.
3. Kill *Ascaris*, *Bacteroides* and *Coxsackie* virus and stay on a maintenance program of killing them. Avoid reinfection. It would be wise to have only outdoor pets.
4. Replace dental metal with metal-free plastic (See Dental Clean-up).
5. Clean up the home environment and body products of toxic substances.
6. Keep your fingers sanitary: spray them with 10% grain alcohol or vodka after bathroom use.

You can often tell by how you feel whether you are near to having a seizure. But some people get no warning. Don't take chances. Keep your drugs with you, even though you no longer need to take them. Drugs like Tegretol^{TM} and Phenobarbital^{TM} are not harmless. Once you can tell that you're better, try reducing your drug dosage slightly. See how you manage. If you have a breakthrough seizure you could fall and break a bone. Don't take chances. Even a year after your last seizure you should carry your medicine with you and have some in your house. This is because it is so easy to pick up *Ascaris* again. The highway to the brain–its seizure center–is still open. They will travel it again. It might only take two days from the time of accidental swallowing of animal filth, to having little larvae in the brain. Use a frequency generator every day at first, or zap daily to guard against this. Notice that killing parasites the first time may actually start a seizure coming. Simply stop zapping if you feel one coming. Do shortened zapping until you can tolerate a regular treatment. Have someone with you while zapping.

---

[14] Taken from *A Guide to the Identification and Treatment of Biocatalyst and Biochemical Intolerances*, 1988 by J. A. Krohn, Los Alamos Medical Center, 3917 West Road Suite 136, Los Alamos, NM 87544.

Say good-bye to seizures forever. But don't forget your susceptibility. I believe you should be extra careful for two years. If you have a recurrence, repeat the whole procedure. This time it should be curable in a single day.

Doug's mother was distraught when she brought him, age 8 months. Her doctor only seemed sympathetic with her purpose to keep the baby's temperature down the next time he catches a cold. But her doctor had referred her to the county social worker. She had been completely honest with her doctor, because she was that kind of trusting person. Since her baby had only experienced one seizure (which was during a fever), she didn't see why her beautiful first born child should be on medicine “the rest of his life”. She wanted her baby to be perfect. But the social worker had called her, talked about “the law” and being an unfit mother. She was all apart. The baby was supposed to be on Phenobarbital^{TM} twice a day. Our tests showed Doug had *Ascaris* plus lead toxicity. He was also getting home made strawberry and grape juice. She promised to put the three cats outdoors, keep the baby off the floor, keep Doug's fingernails short and always wash his hands before eating. The parasites were easily killed. The lead was sporadically present in the water. She planned to move, and until then would filter all the drinking water so her breast milk would be free of it too. His diet was changed to eliminate eggs, chicken and the red and blue fruits. We recommended leaving the state in order to be able to peacefully raise her child. We promised to treat her child free of charge if another seizure should occur. Two years passed and we heard she was doing fine with her child.

Clara Scruggs, 50ish was losing control over her seizures and had to be hospitalized while a new medicine was tried. It changed her personality (again!) which upset her husband, too. She was started on the herbal parasite program but could only increase by one drop of Black Walnut Hull Tincture a week, instead of daily, since each new increase would give her a seizure. In half a year she was fairly free of seizures in spite of being off drugs. After each seizure, a checkup showed she had picked up *Ascaris* again sometimes with additional parasites. She could not bear to put her cat outside; Boots had been a friend in need many times. When she finally got Boots onto a regular parasite program she improved enough to go to church and church events again. When Boots finally “wanted out” she didn't mind. She decided to do a liver cleanse—this, too, gave her two seizures the next day but paid big dividends in other ways. She eventually improved to an incidence of one small seizure (“spacey” time or incoherent speech) in two weeks.

Chun Yee, age 28, has been on Dilantin™ from age 15. Now he was up to five pills a day and it didn't control his seizures. Any activity would trigger it. He was put on a low malvin diet and started on the kidney cleanse. His blood test showed he was anemic with a high MCV (104 cu microns), suggesting the *Ascaris* worms were using up all his vitamin B_{12} too. In six weeks he was down to one or two seizures per week, although he had not yet started the parasite program. He had beryllium built up in him, probably from a kerosene heater. When the pets and family were all treated for parasites he had no more breakthrough seizures and could cut his medicine in half which gave him much more energy. He was no longer in danger of losing his job.

Shiresse Nobel, age 7, was having minimal seizures but the mother did not want to start her on medicine. Shiresse had high levels of mercury in her body, although she had no tooth fillings. The whole family cleared their Ascaris infestation and in three weeks the seizures were gone but aggressive behavior remained. There was mercury in the air of some rooms but it was not in the paint. The bathroom was the worst. When everything in the bathroom was removed, the air cleared and so did Shiresse's behavior problem.

Drew Seaton, age 8, had his first seizure lasting nearly a minute. The parents were very fastidious and extremely conscientious about diet and habits. They were distraught. They all had *Ascaris*. A baby was still being diapered. Drew had arsenic (pesticide under kitchen sink), formaldehyde (some remodeling) and PVC (a new carpet) accumulated in his body. The carpets had to be steam cleaned to get rid of the arsenic. He was started on parasite herbs at once, since he was on medication that would shield him from having another seizure while killing *Ascaris*. Two weeks later everybody, except the mother, was free of *Ascaris*. In another two weeks they were all free and had cleaned up house toxins. They dared to stop his medicine. This let Drew's former happy personality come back to everyone's delight. Two years later there was still no recurrence.

Cosmo Maser, 30ish, was in a hospital across the country. He was having continuous seizures, although he had been there a week. It seemed impossible to transport him but, against doctor's orders, they got him into a station wagon. He had nothing to eat or drink that had any malvin in it (he ate four very well done hamburgers, plain, with lettuce on his trip) and his seizures stopped immediately. They felt a bit sheepish upon arrival 20 hours later since he could sit up, could tell his own story and no longer looked ill. He was without medication, too. They had left in a hurry. They immediately removed all the metal from his mouth; this cleared his mercury problem. He was started on parasite medicine and weathered the small seizures each increase gave him. He could return home in five days with his new diet and thioctic acid daily as a supplement. He occasionally had a seizure (2 a month) until they moved away from the busy street below their apartment. About a year later he could hold a job and go off Social Security support.

Weight Problems

Overweight is not the same problem as *obesity*. In fact, I do not have the answer to either problem, only a part of the answer.

In **obese** women, the ovaries, pancreas and thyroid are all involved. Perhaps the adrenals, the brain satiety center, and the liver are also involved. Maybe it's as simple as gold accumulation in all these places. Perhaps it is bacteria in all these places. When you weigh close to 300 pounds obviously some organ isn't working right. Try several things, but not a starvation diet.

The cause is not eating too much. Try removing all gold: gold teeth, gold jewelry and gold rings. Replace them with non metal varieties. After removing the gold, pull the remaining gold out of your tissues with thioctic acid (2 or 3 a day for several months). Make sure kidneys are able to excrete the gold instead of making crystals by doing a kidney cleanse. Gold accumulates in the pancreas, the brain (possibly in a control center here) and the ovaries (causes some infertility here). Also try clearing the body of all bacteria and parasites by regularly using a zapper. Use the Bowel Program (page 546) to evict the last of the *Shigellas*. Be very careful to avoid nonsterile dairy products. Try cleansing your liver by doing liver cleanses. Get 3,000 stones out.

Make sure you are getting enough nutritious food; make carrot and vegetable juice; use no commercial beverages. Avoid moldy food—don't take risks. If all these measures bring your weight down to the level of mere overweight give yourself good grades.

Overweight is a low energy condition. Your food is being turned into fat instead of energy. The decision not to make energy is being made in the liver mainly, but perhaps other organs as well.

Try cleaning the liver (page 552) until no more stones come out: get at least 2,000 stones. Notice that as the liver gets cleaner you get more and more energy right after each cleanse. Some cleanses have a dramatic effect. Others do not. This suggests that a certain part of the liver is the responsible part. Soon after the cleanse–within a week–the same old lassitude sets in. But during these few days notice how your body feels. It feels light. Your abdomen feels tight, like it's a part of you again. You're mind isn't on food throughout the day. It's very easy to lose weight, in fact you may lose five pounds in these few days without dieting or exercising. Definitely, your long-lost weight regulation is back in force. But then it vanishes. Fortunately, a bit of the weight loss stays with you, and by repeating cleanses (only once in 2 weeks, though) you can shed the pounds you want and gain energy in a permanent way. It is probably the way nature intended.

Try increasing your bowel movements. Notice how cats and dogs seem to derive energy from emptying their bowels. A cat walks to its litter box; after emptying its bowels and carefully covering it up, it jumps from the box and runs away. It now has its playful mood. A body chemical, *acetylcholine*, plays a role in emptying the bowels. Acetylcholine is a necessary operator for many of our muscles. Is there a disturbance in our acetylcholine metabolism in overweight conditions?

Coax your body to release more acetylcholine, at least in the intestines, by using a herbal laxative like Cascara sagrada. Other varieties are useful, too, but don't use a drug laxative: it burdens the liver more. Try to have three bowel movements a day.

Shigella bacteria can cause dreadful constipation. Immediately, the body feels sluggish, abdomen feels disconnected or hanging out. A nameless hunger sets in. Keep a close watch on dairy foods to make sure they are sterile. Zap when in doubt and do the Bowel Program.

Exercise helps as long as you keep at it. Strict dieting works as long as you keep doing it. But there's the problem. When you stop, you lose ground. It doesn't solve the problem of an inefficient body metabolism.

Raising thyroid levels helps but this can be dangerous. Raising thyroid levels naturally, by removing toxins is a very effective method—provided it was low to begin with. Overweight people often have a low body temperature, showing that the thyroid is involved: it is under producing. **But giving the body extra thyroid doesn't solve the thyroid's problem. It only temporarily solves the rest of the body's problem.** The thyroid will have viruses and heavy metals in it. The metal in your mouth drains downward to the stomach passing very close to the thyroid. Perhaps its iodine uptake is inhibited. The chlorine in water and bromine in bread may inhibit iodine uptake by the thyroid, too. After all, they are all halogens. Stop eating bleached bread and filter out the chlorine in your water. If this raises your body temperature you could expect better weight control.

The traditional herb, *Fucus*, was used to treat thyroid problems (and overweight) in days when herbs ruled medicine. Herbalists made a point of discouraging use of plain iodine. Fucus, they said, was much more effective. See *Recipes*.

If all these measures don't work for you, at least you have improved your health trying.

There are some advantages of being overweight. Overweight people seem to weather illness better. They laugh more. But one look in the mirror or at the scales ruins it. Put away the long mirror and scales. Don't ruin your whole life over it. Make a reasonable effort and then let go. Enjoy your stay on this planet.

Underweight can be just as difficult as overweight to correct. Once the stomach has been trained to say “full” or “full enough,” even after a few mouthfuls, it is difficult to heal. *Salmonellas* in the stomach wall are often seen. *Giardia* and other common parasites, that don't belong in the stomach, are seen here in cases of underweight.

The stomach is invaded by bacteria and parasites when its immunity is low. The common culprit is tooth metal draining down continuously into the stomach. Remove every bit of mouth metal. Don't cook or eat with metal. Stimulate your appetite with B-vitamins. And, again, the liver plays a role. If it is toxic with mold, it may say "eat no more" and the body obeys.

A stage of cancer illness is weight loss. This is called *cachexia*. The victim believes he or she is eating enough. They may not even have a poor appetite. Yet weight drops steadily. This metabolic problem has been studied scientifically. A chemical, **hydrazine sulfate** (prescription only), can reverse it to some degree. Use 65 mg three times a day for 30 days. Perhaps a lesson taken from cachexia metabolism could be applied to obesity. For the cachexia sufferer, life would end sooner if high calorie supplements were not used. But don't use canned "calorie boosters". They are polluted—often with the very solvent that makes the condition worse. Instead, make an eggnog: ½cup boiled milk, ¼ cup boiled whipping cream, a raw egg (exterior carefully washed), 1 tsp. olive oil, a banana, honey, cinnamon, cloves, nutmeg to taste. Mix all in a blender. Drink 1 cup a day. Vary it daily to keep it interesting.



Fig. 33 I found all calorie boosters to be polluted with wood alcohol. Make your own.

If all this fails, give yourself credit for achieving health improvement and shift your focus to a different project. Underweight is not all bad either.

Sleep Problems

All big animals sleep, but some sleep by day instead of night. When humans do this, that is, work the night shift, they don't feel as well. Humans need about seven hours of sleep out of the twenty-four. Younger ones sleep more; newborns sleep much more. When we are deprived of sleep we are grouchy, think less clearly next day and have less energy. In spite of lots of research at "sleep labs" sleep problems are not understood, except for sleep *apnea*. Breathing should be even. When breaths are missed it is called apnea. It is especially disturbing when a baby shows apnea.

Sleep Apnea

Since breathing is regulated by acid levels in the blood and this is influenced by air quality, air toxins should be searched for first. **Cigarette smoke** is an air toxin. **Vanadium** from a gas leak is a very serious air toxin and can go unnoticed. Do your own checking since gas companies give wrong answers four out of five times. Ask a home construction company to check for gas leaks or the Health Department. **PVC** from new carpeting may be polluting the air. **Arsenic** from "treated" carpets and drapes and furniture also pollutes. **Asbestos** from clothes and hair dryers may be the toxin responsible. Perhaps even **fiberglass**, **formaldehyde**, or **freon**.

Adults with sleep apnea show swollen throat tissues: not necessarily pain. This makes the air passage smaller; long gasps of air are taken to try to make up for the missed oxygen and the carbon dioxide build up.

Swelling of the throat is a common allergic reaction. The possibility of allergy should get second consideration after air quality. Drug reactions, even in a nursing baby, where only the mother is using a medicine could be the problem. Allergy to food, chemicals has been suggested, as well as a simple lack of vitamin C (implicating mold and medicine which consume vitamin C in the detoxification process).

A third possibility is infection. Many bacteria and viruses can cause throat swelling. Redness of the throat is a telltale sign. It doesn't necessarily hurt. Kill all invaders with a zapper and try to understand the basis of low immunity in the throat.

Keeping metal in the mouth constantly, is a cause of low throat immunity since it must drain past the throat.

If you snore, you can deduce that your throat is swollen, even if you don't have sleep apnea. Pursue all three possible causes (air toxin, allergy, infection).

Overweight and obesity have been emphasized as causes. This may apply to some cases but certainly not to babies.

Whatever you do, don't do nothing. Keep removing bad things until you find the cause of irregular breathing.

Chester Fannon, 5Oish, was quite overweight and wore a mask at night with an air blower to assist his breathing. He had been referred to a sleep center for sleep apnea. He had extreme dryness of his throat at night and some hearing loss in one ear. He was toxic with arsenic (roach killer), bismuth (cologne), tin (toothpaste), and thallium (polluted dentalware). He was infested with both species of *Ascaris* and had a hacky cough. He had four solvents accumulated in his tissues. He was growing nine pathogens: *Mycoplasma*, *Haemophilus inf.*, *Streptococcus pneu*, *A-strep*, *Nocardia*, *Staphylococcus aureus*, *Bacillus cereus* and Flu virus, over half of them in his throat. These were killed with a frequency generator and a general cleanup was done. After two teeth were pulled he no longer needed his mask, he no longer had apnea.

Peter Day, middle age, was set for throat surgery in a few days. He had a couple of scary nights when he thought he was dying and couldn't risk many more nights with his obstructed airways. He was overweight. His throat was red and swollen, although he felt nothing. He never even had colds. His diet was completely changed, to things he rarely ate (bananas, milk, soup, oatmeal) and off things he ate daily (hamburgers, fries, tea, pancakes with genuine maple syrup). In two days, his throat was quite clear, the tissues having become unswollen. Maybe it was the molds in the maple syrup, maybe it was the oxalic acid in the tea, or something else he could not detoxify in these foods. He was certainly happy not to live the rest of his life with an artificial voice box.

Insomnia

Another sleep disturbance is waking in the night and not being able to go back to sleep for hours. Or not being able to get to sleep.

I believe these problems are caused by a high ammonia level in the brain. This belief is based on two observations. **Ornithine**, an ammonia reducer, induces a wonderful sleep in sleep-deprived persons. It is also observed that after killing parasites, which produce ammonia, sleep is much improved. Our metabolism does not produce ammonia. We produce urea which is excreted by the kidneys along with water and then called urine. When we are parasitized, our metabolism is burdened with ammonia, though, made by the parasites. We have to turn it into urea in the liver and kidneys so we can excrete for them. But this can't be done in the brain! The brain lacks an essential enzyme, *ornithine carbamyl-transferase*, for this bit of biochemistry. The brain was never meant to be parasitized or infected and has no defense. Most of our parasites come from animals we associate with. We weren't meant to live with horses, cows, sheep, pigs, monkeys, guinea pigs, cats, dogs and chickens nor to come in contact with dozens more at a zoo. We do so at our own peril.

It is known that ammonia is a strong brain irritant. In fact, a person can be awakened from a coma by being made to smell ammonia "smelling salts." Ornithine reacts with ammonia, mopping it up like a sponge. **Arginine**, another amino acid, also reacts with ammonia, but does not put you to sleep. So there is more to insomnia than mere inability to reduce ammonia levels. Arginine results in alertness and therefore should be used in the morning, when needed. Ornithine, given at bedtime, may take ½ hour to do its magic. Both are perfectly safe, since they are natural to your body, and a food constituent.

Start by taking two ornithine capsules (each 500 mg.) on the first night. Take four the next night. Take six the night after and choose the dose you like best. Sometimes it takes five days to "catch up" on everything that needs to be done for the brain and get you sleeping. Meanwhile, of course, you are planning to kill your parasites and be done with insomnia in the most effective way of all.

Another sleep aid is herbal. A couple of herbs, **valerian** and **skullcap**, are known for such action. The mechanisms are not understood and this makes for nonuniform action. Some persons sleep well with them, others do not. Simply try them to find out. We are all so different in our metabolism details, we respond differently to herbs. But it is a blessing that the mechanism is not understood. Herbs, a tradition that precedes civilization, need to be forever off limits for intervention by government agencies.

Tryptophane, another amino acid, is about twice as powerful as ornithine, but was taken off the market a few years ago. Some persons taking it daily were seen to become quite ill and some deaths ensued. Since tryptophane had been used in prior years without noticing toxicity, something unusual should have been suspected. My tests showed extreme pollution of tryptophane capsules. They contained PCBs, mercury, ruthenium, strontium, praseodymium, aluminum, and benzalkonium. I can only speculate that a mixing vat broke, dumping its precious load onto the floor—but it was salvaged. Or that the mixing vat wasn't cleaned thoroughly from it's last use.

Persons with illness due to taking tryptophane developed an extremely high eosinophil count in their blood test—an index of parasitism, too. Parasitism, that would have led to insomnia in the first place! Were these unfortunate victims seeing the cause or the result of their tryptophane use? This tragic event should have led to a discovery of the heavy pollution, a revelation of the industrial manufacturing process, and a safeguarding against any repetition. It has not been done (certainly not publicly).

Foreign countries' manufacturing processes do not come under U.S. scrutiny or jurisdiction, although some imported products must pass tests. There are no safeguards against repetition of the tryptophane experience. It behooves us to demand safe supplements and medicines. It is not the list of ingredients that informs. Lot analysis, after bottling, would give us the necessary safeguard. The presence of filth contamination and toxins cannot be completely avoided but the consumer can make informed choices if he or she knows it is there. Disclosure, of course, is the bane of the manufacturing business. Interest rate disclosure was the bane of the money lending business. Such important matters can't be left to “self-regulation” policies. The consumers must simply demand to know what they are consuming.

Ruby Adair, 14, ached all over, had ringing in her ears, sinus problems and chronic fatigue. She couldn't get to sleep, ever; and had been half a year out of school already. She had intestinal flukes in her stomach. In three weeks she had eliminated them with parasite herbs and she could go to sleep naturally.

Yeast Infections

The most common yeast in humans is *Candida albicans*. *Candida* has always been around. It flies in the air, searching for a place to land and reproduce. It can invade a variety of human tissues like the mouth (called thrush), skin (including some kinds of diaper rash), vagina, and the digestive tract. We all have some yeast in our digestive tract, but when it gets out of hand, it's called *candidiasis*.

Yeast is a **fungus**. It needs dampness to survive and sugar to grow.

Our immune system, white blood cells, are capable of eradicating yeast provided it isn't growing too fast. And provided the white blood cells aren't immobilized or preoccupied with something else.

Diaper Rash

A baby's rash is an example of the white blood cells being preoccupied. When chemicals are used in the diaper, the white blood cells go after the chemicals and let the yeast grow. Drying the baby's skin helps since the yeast must have dampness. This should be done with air, sunlight and a heat lamp, not with more chemicals! Certainly not with cortisone containing salves that further reduce the immune competence of white blood cells.

Use a heat lamp for five minutes at a time, several times a day. Switch to cloth diapers; do not bleach them with chlorine bleach, the residual chlorine trapped in the cloth is a chronic irritant, setting the stage for another rash and future chlorine-allergy. Cloth diapers should be sterilized, not bleached. Use the hottest water your laundry system is capable of producing. Add ½ cup borax for the washing process. If you have homemade Lugol’s iodine (made by your pharmacist or by yourself, see *Recipes*), add a tsp. to the wash or rinse. Vinegar is a yeast inhibitor, add it to the rinse. Dry diapers at the hottest setting. Dry to kill. Kill all the yeast spores in the diapers.

To strengthen the baby's skin against future infection, do not put chemicals on the skin. Do not use any soap, fragrance, bath oil, ointment or lotion. Do not use cotton balls or baby wipes. Do not give a daily bath. Wash bottoms gently, with borax followed by a vitamin C rinse. Vitamin C is acid and is our natural healing agent but it will sting on a broken skin surface. Use it as dilute as necessary to be tolerated. Zinc oxide is another natural healer because it competes away the iron that fungus and bacteria need for their reproduction. Never use commercially available zinc compounds though, simply purchase your own zinc oxide powder, mix it with cornstarch and keep in a large old salt shaker, dust it wherever there is moisture or fungus growth.

Treat Yeast or Fungus the Same

Other fungus growths, like *Tinea* (crotch itch), ringworm (not a worm at all), athlete's foot, along with *Candida*, can be similarly eradicated:

1. Deprive the fungus of moisture.
2. Deprive the invaders of iron.
3. Deprive the fungus of sugar.
4. Strengthen the skin's immune power.
5. Strengthen the skin's healing ability.

It may be impossible to deprive the fungus of moisture, for example if your feet sweat and you must wear socks. Take your socks off as soon as you are at home, treat your feet with a heat lamp. Use zinc oxide or cornstarch to powder and dry the skin. Boil your socks when laundering. Dry them to tinder-heat (too hot to touch). Launder with borax only (soaps and detergents contain aluminum which pollutes the skin). Rinse skin with vitamin C water. It takes all these measures used simultaneously to clear up athlete's foot fungus. And great persistence. They may have developed a foothold underneath the toe nail where a steady supply of moisture, iron and sugar is available to them. Nevertheless, your white blood cells will eventually gobble them up if you let them.

In thrush (yeast infection of the mouth) you must again outwit its growth by doing everything possible at one time. Eat no sugar, drink no fruit juice, stay off antibiotic. Avoid trauma like eating abrasive foods (crusts, popcorn, nuts, lozenges) or sucking on things. Floss teeth only once a day (using monofilament fish line), followed immediately by brushing with white iodine (or Lugol’s, but this may temporarily stain). Hydrogen peroxide is not strong enough. Remember to sterilize your toothbrush with grain alcohol or iodine. You may also rinse your mouth with Lugol’s (6 drops to ¼ cup of water). Or apply 6 drops directly to the tongue and rub it in lightly with your lips.

Do not use Lugol’s iodine if you have been told you are allergic to iodine.

Kill *Candida* daily with a frequency generator or zapper. Since reinfection is constant, you must continue to do all the treatments given to permanently cure yourself of fungus disease.

Since *Candida* grows right into your living cells (which you are not attacking!) you cannot kill it all at once. Only surface fungus can be accessed by either Lugol’s or electrical “zapping”. But as the top layer is killed, exposing the next layer, you will make progress. It will take a month of daily treatment to clear it.

Clearing up fungus at one location but not another will not bring you a permanent cure, either. Damp locations like under the breasts, under the belly fold, groin and crotch need to be kept dry with cornstarch daily. Keep it up long after it seems to be cured.

Fluke Disease

Flukes, or flatworms, have a complex life cycle with many stages. Although sheep, cattle, pigs and humans can be "natural" hosts to the **adult** stage, the other stages are meant to develop outdoors and in secondary hosts. When fluke stages other than the adult are able to develop in us, I call it *fluke disease*.

Or, when an adult that "normally belongs" to another species is able to develop in us, I also call that fluke disease. Or even with adult flukes in their "normal" host, when they move from the organ that they "normally" colonize to other organs in the body I call this fluke disease, too.

Four fluke varieties engaged in this extra territorial pursuit are the **intestinal fluke**, **sheep liver fluke**, **pancreatic fluke**, and **human liver fluke**.

As you can see from their names, scientists have studied them well, and know exactly which animals are the "normal" hosts, and which organ in that animal is the adult fluke's "normal" home. Fluke disease is when any of these is "wrong."

Flukes don't have eyes to see with or legs to walk with, so how can they find and travel to the organ they want in the middle of your body? Scientists do not know for sure. However it's concluded from many scientific studies that the liver fluke, *Fasciola*, for example, has no trouble seeking out and colonizing the liver.

Here are some examples of what can happen when flukes go "wrong:"

- Adult flukes (any of the four mentioned) in the uterine wall causes cramping and bleeding when it is not menstrual period time. If an adult crosses the wall to the inside and then manages to get out through the fallopian tubes to the abdominal cavity it takes some endometrium with it—causing **endometriosis**.

- If adults develop in the kidneys, it can cause **lupus** or **Hodgkin's disease**.
- If adults complete their cycle in the brain, **Alzheimer's** disease and **multiple sclerosis** result.
- If the intestinal fluke (*Fasciolopsis buskii*) becomes adult in the liver it causes **cancers** of many (hundreds) kinds.
- If the pancreatic fluke completes its cycle in the pancreas it leads to **diabetes**. This is not an example of flukes straying into the wrong organs, but of having its stages reproducing where they never could before.
- If flukes develop in the thymus, immunity is lowered. If it happens to be the intestinal fluke, **HIV** (Human Immunodeficiency Virus) is released there. In turn, HIV invades other tissues, like penis and vagina.
- These four flukes can also invade the muscles, causing **dystrophies**.

As dissimilar as we always thought these diseases to be, it's obvious to me that they are but one disease—fluke disease

Considering the size of these flukes (adults are easily visible), it is not surprising that they can quickly lay waste a human's organs. Yet a human is big and makes a valiant effort to kill the stages, block access to tissues and otherwise battle them.

But only the human's intelligence can be counted on to defeat them. The intelligent approach is to discover what enables these mighty monsters to do their reproducing in our bodies instead of the pond with its snail/minnow secondary hosts.

Flukes and Solvents

The explanation I have found for two of these flukes is the presence of solvents in our bodies. The presence of *isopropyl alcohol* is associated in 100% of cancer cases (over 500 cases) with reproduction of the intestinal fluke stages in a variety of organs causing cancers in these organs.

The presence of *benzene* is associated in 100% of HIV cases (over 100 cases) with reproduction of intestinal fluke stages in the thymus.

The presence of *wood alcohol* is associated in 100% of diabetes cases (over 50 cases) with reproduction of pancreatic fluke stages in the pancreas.

The presence of *xylene* and *toluene* is associated in 100% of Alzheimer cases (over 10 cases) with the reproduction of intestinal fluke stages in the brain.

Much more work needs to be done to examine the relationship between fluke reproduction, the solvent and the chosen organ. But it seems probable that the solvent allows it all to happen. And our intelligence, to save us, must find a solution.

Stopping use of these solvents seems to me to be the most urgent advice. Finding which foods and products are polluted with them is the first step. It is imperative that you test everything you use or eat for solvent pollution. The Syncrometer makes that an easy task. Ideally, we should all pool our results, adding to the body of knowledge I have begun.

In my observations, when the big sources of solvents are stopped, the body's levels go back to zero. In other words, the minute amounts that we inhale here and there do not accumulate to the point of serious damage. We have to eat, drink or absorb them on a daily basis to injure us! So where can they come from?

The sources of benzene and propyl alcohol that I found are given in special lists (page 354 and 335). The sources of wood alcohol are not as well known, but include commercial beverages, cold cereals, artificial sweetener, vitamins, and drugs. Other solvents are even less studied. But a pattern is emerging: foods and products that require sterilization of bottles and machinery to fill these bottles are polluted with propyl alcohol or wood alcohol. Foods and products containing flavorings or oils are polluted with benzene. Let the buyer (you) be wary! Test your own products if possible. If not, do not purchase them.

There are many other flukes and many other diseases. Are there other fluke/solvent/disease trios? Has fluke disease been going on for a long time or is it a recent phenomenon? Certainly cancer is 100 years old, so is the use of propyl alcohol. Diabetes is quite old as an illness, too, and so is its associated solvent, wood alcohol. But HIV, AIDS and Alzheimer's are recent diseases. Should we conclude that benzene, xylene and toluene were used much less in the past?

Fluke diseases could be eradicated with some simple actions: monitoring of solvents in foods, feeds and products. Hopefully, this will begin. It is in the interest of the consumer to have her or his own independent way of monitoring too. Chemical ways can be devised, besides the electronic way presented in this book. Imagine a small test strip like a flat toothpick which turns color when in contact with propyl alcohol. Keep a pack in your pocket and never be unknowingly dosed again...all in tomorrow's world.

Flukes Not Alone

There are other families of parasites. The roundworms and tapeworms are gaining ground too. Are they associated with solvents? Or with yet undiscovered factors? Are they changing their life cycles to take advantage of our lowered immunity? These are important questions. But you are armed with excellent technology. The answers will be found.

And along with answers there will surely develop a new industry. An industry that not only proclaims purity for its products but provides the proof to your satisfaction.

Burning And Numbness

Burning sensations in the skin let you know that nerves are involved. Mercury is the most common offender. Mercury may have started the trek of a host of other toxins as well into your nervous system: pesticide, automotive chemicals, household chemicals, fragrance and even food chemicals. Some people can get a burning sensation after a car trip, some when exposed to perfume, some when walking down the soap aisle in a grocery store. When the affected nerves don't go to skin but instead go to an organ like toes, you might feel a toe cramp or finger cramp instead. Remove your mercury sources.

Burning skin is an ancient malady—maybe even the basis of concepts like “hell.” St. Anthony's fire was caused by *ergot* (food fungus) ingestion. Molds don't necessarily come singly. Maybe other mold toxins can go to your nerves, too (see Moldy Food, page 381). Maybe the mold toxins interfere with **pantothenic acid** used by your body, because giving pantothenate (500 mg three times a day) can sometimes relieve the condition and, of course, this is good for your body.

Monosodium glutamate (MSG) can cause burning, especially of the face and lips. Sometimes swelling occurs too. MSG is used as a flavor enhancer. It was found decades ago to be a brain toxin and was taken out of baby food. But what about adults? Especially those who already have a brain problem. Throw it all out of your kitchen. Ask at restaurants which foods have it.

Numbness has a similar cause. Numbness of fingers or feet has become quite common since thallium and mercury toxicity has spread so widely.

If you have burning and numbness, can multiple sclerosis (MS) be far away? Remove all the metal in your dentalware immediately, replacing with composite (see Dental Cleanup, page 409). Hopefully, your immune system is still strong enough to clear the bacteria growing around the metal and in pockets in the jaw. Check and clean cavitations. Start your jaw healing with the milk, magnesium, vitamin D diet. Use thioctic acid to help clear your tissues of remaining metal (3 to 6 a day).

The most common nervous system bacterium is *Shigella*. Its beginning can already be seen in cases of burning and numbness. It is deeply entrenched in cases of MS. Three kinds of *Shigella* are readily obtainable on slides: *Shigella dysenteriae*, *Shigella flexneri, Shigella sonnei*. *Shigella flex* causes depression and irritability. All can cause gas and bloating. Zapping doesn't kill all of them because they inhabit the bowel. You must empty your bowels frequently, two or three times a day. And do the Bowel Program until all symptoms are gone. Be very careful not to put contaminated dairy food in your mouth again. Boil all milk products. They must be at boiling point for 10 seconds. This includes cheese, cottage cheese, buttermilk and regular milk. Eat only home made yogurt or home made buttermilk. Butter and whipping cream need this treatment, too. Never use raw dairy products.

Nana Hughes, 48, had numbness of the whole right arm, hand and right side of her head; it was particularly bad in the last four months. She was toxic with PCBs, titanium and dysprosium (paint). She was on thyroid, Xantac™ (for stomach) and chlorazipate medicines. We also found dog heartworm (she had chest pain over the heart). She started on the parasite program, stopped using nail polish, and stopped all detergents for dishes or laundry. In three weeks her numbness was greatly reduced. She still had titanium buildup from dental metal (a partial bridge). Seeing she was on the right track, she stopped use of MSG in her food, switched from concocted beverages to milk and cut down on her smoking. She brought her arm pretty near to normal.

Maria Santana, 45, had numbness in both arms; they would tingle and "go to sleep" a lot. It was spreading to one leg. Her muscles were toxic with thallium. It was in some very old pesticide, still effective and still in use in the house. It was also in the well water, probably, from pesticide seepage. She went off all commercial body products, did a kidney cleanse and killed parasites. She had difficulty getting rid of *Prosthogonimus* but in two months she had everything cleaned up. Her legs, arms, sleep problem, urinary tract problems were all gone and she could focus on her last problem, digestion.

Candy Donaldson, 44, had numbness from her shoulder to the wrist of one arm, it started a year ago. She was toxic with iridium, lithium and vanadium from a gas leak. She was advised to stop caffeine use and switch to milk (her calcium level was low: 9.0 mg/DL) and a magnesium tablet (300 mg daily). Her triglycerides were high, implying a kidney problem. She had urate and phosphate crystals in her kidney. She decreased the phosphate in her diet (meat, nuts, grains, soda pop) and started the kidney cleanse. When the gas leak was fixed, both her lithium and vanadium toxicity disappeared. In six weeks she had also killed parasites and her periods became regular for the first time. An ovarian cyst had disappeared, too, as checked by ultrasound. Soon her PMS was gone, including hot flushes. After four months she had done three liver cleanses and suddenly her numbness improved. After a few more there was no numbness at all.

If cleaning cavitations brings you immediate improvement you know that these bacteria were part of the problem. Have them checked again if problems return; dental bacteria are notorious for returning. If kidney cleansing makes it worse for a day and then better, you know kidney bacteria are partly responsible. If liver cleanses (page 552) make matters worse for a day and then better, you know bacteria are entrenched in the liver. Continue cleansing until none of these sources exist any longer. Kill all bacteria at least once a week electronically. Burning and numbness can be cured, not just arrested. In other words, your nerves can be cleaned up and healed.

Depression

All persons I have seen with clinical depression had small roundworms in the brain. Is it any wonder the brain can't make enough neurotransmitters or gets them out of balance? The usual worms are hookworms (*Ancylostoma*), *Ascaris* of cats and dogs, *Trichinellas* and *Strongyloides*.

Although it is commonly believed that hookworms penetrate the skin when walking barefoot on earth, this appears to be a negligible route. The important routes are eating animal filth and inhaling filthy dust. Our pets pick these worms up daily. We get them and give them in constant exchange with our pets and family members. Diapering babies is an especially hazardous, though necessary, business. Letting little children clean up after their own bowel movements is even more hazardous. Hands should be sanitized with grain alcohol after dealing with bowel contents, whether your own, your child's, or an animal's. If you clean up a messy diaper and then your hands well with soap, then go to make the chopped salad for dinner, you're sure to give each family member a dose of whatever the baby has. It was hiding under the fingernails. Animals clean up the easy way: they simply lick the youngster's bottom. But, we humans are not strong enough to take on a dose of bottom with each meal. **We must sanitize our hands**.

Cleaning bathrooms is also dangerous. Wear gloves. If nobody suffers from depression, you can use bleach (stored in the garage) to disinfect the stool, otherwise use alcohol (50% grain alcohol). Keep doorknobs and faucet handles wiped with alcohol, too.

If you suffer from depression use your zapper to immediately kill these four roundworm species: *Ancylostoma*, *Ascaris*, *Trichinella* and *Strongyloides*.

Other family members should be cleared of these four worms on the same day or as close to it as possible. Reinfection always occurs. In the depressed person, the microscopic parasites travel immediately to the brain. In others, they may simply reside in the intestine or lungs or liver, or other organs. Pathways (routes) to the brain have become established for the depressed person. These must heal before there is any tolerance to reinfection.

Solvents and other toxins, also in the brain, slow down or prevent healing. For this reason the depressed person should do the *Four Clean-ups*.

The bacteria of the *Shigella* family are always seen in depression cases. Kill all *Shigellas* and avoid reinfection by boiling dairy products and not eating those that can't be boiled. Go on the Bowel Program (page 546). Do not eat deli food or hand prepared salads at salad bars. Finally, do the Liver Cleanse, repeating every two weeks. Depression, even of long standing, can lift within days after the brain finally has its territory to itself. Look in the mirror and smile at yourself for your success in vanquishing your invaders. Never again, let these creepy crawlers into the happiness-center of your brain.

Manic Depression

This variety of depression is associated with *Strongyloides*, as the main parasite in the brain. Plus **chlorine** as an allergen! *Strongyloides* is the same worm that causes migraines and other severe types of recurrent headache. It probably depends on where these tiny worms have set up their “housekeeping” which symptoms you get: manic depression or migraines. Maybe chlorine is the deciding factor.

These tiny wormlets can pass the placenta into the unborn fetus. Is it any wonder that these brain disturbances seem to be inherited? Of course, there is ample opportunity to simply eat them off hands, other people's hands, and off floors during childhood. The amazing truth is that some family members do not get infected with it or at least do not get brain symptoms! It is very difficult to eradicate *Strongyloides* in a whole family and thereby let the depressed person get well. It is, in fact, impossible if there is a pet or other animal connection. Getting rid of the chlorine allergy is also very challenging. Step one is to zap all parasites.

I usually see an accumulation of **bromine** as well. Since bromine, fluorine and chlorine are all *halogens,* maybe getting too much of any one could saturate the liver's ability to detoxify chlorine. Stop eating brominated (bleached) bread. Stop taking drugs containing bromides. That is the easy part. You must also stop even washing your face in chlorinated water (use a pure carbon filter system). You inhale it as you wash. Never drink it or use it for any purpose. Of course, there should be no bleach container in the house, even when tightly closed; nor should bleached clothing be worn.

Do the *Four Clean-ups*. Sometimes the cloud lifts and the mind clears on the way home from the dentist. Recovery can be very rapid—less than a week. And recurrence just as rapid when a tiny bit of chlorine is inhaled or drunk. But your careful vigilance pays off. In half a year you can expect no recurrence.

Humans, it seems, must lick fingers with the same compulsion that cows lick their noses and cats lick their rears. The single, most significant advance in human hygiene would most assuredly be stopping the hand to mouth habit. We must always eat with utensils. And never leave a bathroom without washing. These are difficult changes but the new age of parasitism makes it necessary. Together with the new pollutants, solvents, and heavy metals, parasites will overtake us unless we change.

Don't go off lithium and other medicines until your doctor agrees you are ready, about a half year. After this, make sure you still keep it handy. Although you may be free of manic depression in a day, reinfecting yourself weeks later will attack your brain like a hurricane; it has not yet healed, the routes are open. Be patient; healing will happen as it did for these happy persons.

Lena Constantine, age 39, had a history of migraine, TMJ, heavy clotting with periods and numerous pains but it shouldn't have made her try suicide 1½ years ago. She was put on Prozac™ afterward. She was parasitized by intestinal flukes (in the intestine), dog whipworm, *Strongyloides* and human liver flukes. She was started on a parasite program and kidney cleanse. This made her feel so good she took herself off Prozac™ and landed in the hospital for reasons she couldn't remember. After 42 days spent there she got out, wiser than before. She set to work again, leaving no detail undone, because she could remember how good it felt to be free of depression (not drugged out of it). Three months later she still had *Strongyloides* (she had a cat) but she did her first liver cleanse anyway. She got over 500 stones out. Her depression was gone. She substituted 4 ornithine and 2 ginseng capsules daily (more if tension was not relieved) for Prozac and cured her problem.

Mona Zabala, 33, was extremely depressed over her job. She was full of mercury, arsenic, PCBs, chromate from eye liner, wood alcohol from drinking colas and she had *Ascaris*, pancreatic flukes, *Trichinellas* and *Strongyloides*. She thought she was a hopeless case. But in less than three months, when only half her clean-up chores were done, she was already saying positive things about her job.

Acey O'Hara, a young graduate student, was very careful to avoid junk food, caffeine, fragrance, and body products because he had learned the hard way that he didn't tolerate them. When “crying” depression hit him he was not only surprised but angry that his good health habits “hadn't paid off.” He was buying his drinking water; it came in clear plastic containers. He had cesium in his tissues and brain. When he switched back to plain tap water (filtered in small quantities) the depression lifted in a week and he was no longer crying over anything.

Leisa Underwood, 46, was clinically depressed and in therapy. She believed it was due to going through menopause. She had a heavy burden of *Strongyloides* but no other worms. Only one of her two dogs had *Strongyloides* (saliva test) and the cat was free of them also. She was full of cesium (from drinking refrigerator water) and vanadium (from a gas leak). In two months she had accomplished the impossible: all pets and herself were free of *Strongyloides*, they had repaired three gas leaks and her depression was just a memory.

Roland Greeley was diagnosed as manic depressive a few years ago and was put on Ativan™ and Prozac.™ This controlled him but did not relieve depression. He had a prominent tremor. He had *Ascaris* and sheep liver fluke stages in the brain. Also *Trichinella*, *Strongyloides* and human liver fluke stages. Styrene (from styrofoam cups), methyl ethyl ketone (beverage) and carbon tetrachloride were in his brain also, probably setting the stage for parasite reproduction. He had high levels of mercury and silver but highest of all–throughout his body–was chlorine (from bleach and tap water). In four weeks he had all the metal removed from his mouth. He stated that this "unchained" him. He could already tell on his way home from the dentist that something special had happened. His depression was simply gone "the way you lift a blanket off a bed". He resolved to clean up his whole body and recover from his illness using logical methods, like ours. Staying away from regular chlorinated water was a fine challenge to his resolve but with whole house filtering now available he may have done it.

Darren Knox, age 48, had been on Thorazine™ for 36 years but was recently changed to Desyral™ and Valium™ and lithium. He had *Ascaris* and hookworm and two dozen more assorted parasites including fluke stages. His brain was also hosting *Bacteroides* and *Nocardia*. All parasites were killed in half an hour by frequency generator at his first visit whereupon he immediately announced himself free of depression; better than the last eight years. He had many metals in his brain, also chlorine. In four weeks his tremor was way down, after dechlorinating his tap water. His depression never came back after dental work was done.

Schizophrenia

Much more mold toxin was seen in schizophrenic families than in other kinds of illness. They usually had four or more kinds of mold toxins at the same time, meaning that one toxin was not detoxified before the next was already eaten. It may reflect on the liver as much as the food selected. The initial injury, though, to the liver may have occurred in early childhood.

Schizophrenia does not require mercury or other dental metal pollution for its expression. This pattern is logical when it is seen that young children can have schizophrenia. Schizophrenia is an ancient illness, being described in some very old literature, before dentistry existed. But parasites existed. And moldy food existed. And copper existed!

Ergot is always seen in sick persons. Other mycotoxins are also present, including *sterigmatocystin*, *cytochalasin B*, and *aflatoxin*. As the mycotoxin panorama changes, brain symptoms can change from compulsive hand washing to paranoia or from hearing voices to meanness in disposition.

It is my belief that the current increase in violent crime in U.S. society can be attributed to the especially high levels of mold consumption in foods and beverages, with the resultant effect that behavior erupts into violence with almost no provocation, merely some frustration. It would not be difficult or expensive to experiment with a mold-free diet in our prisons.

A bacterium, *Mycobacterium phlei*, may also be a cause because I have seen a high correlation between it and schizophrenia cases. What its specific effects are, I don't yet know. This bacterium may be hiding under teeth. It is also seen in dogs.

Shigella bacteria from nonsterile dairy foods are part of the problem, too. They produce brain and nerve toxins resulting in irritability, depression, anger. In fact, anger can be so intense, it erupts in violence.

Lead and copper are commonly seen in schizophrenia sufferers. The usual source for these is the household water (household plumbing may have lead solder joints). Change plumbing to PVC, then take thioctic acid (100 mg, twice a day).

Parasites always found in schizophrenia are hookworms (4 *Ancylostoma* varieties) in the brain.

Instructions:

1. Stop eating all grain products, nut products and syrups immediately.
2. Sterilize all dairy products.
3. Search for lead and copper in the water.
4. Stop drinking commercial beverages, including bottled water.
5. Zap the parasites in the whole family for three days, followed by repetitions twice a week.
6. Eliminate *Shigellas* with the Bowel Program (page 546).
7. Give away pets. Schizophrenia is too serious to risk reinfection.
8. Do the dental cleanup (page 409).

The need to zap repeatedly arises from reinfection. Nothing needs to be killed twice. But reinfection from self, family members, pets and food happens every hour. One cannot rely on zapping to stay well. Do a thorough diagnostic search of all foods eaten at the last meal, the water drunk, the air breathed. Only when all these are clean, will the brain heal.

When can you eat grains again? When you are well. Find a cereal or pasta that has no mold. Test it for the mold frequencies (77, 88, 100, 126, 131, 177, 188, 232, 242, 277, 281, 288, 295

KHz). Search especially for ergot (295). Remember, ergot makes *lysergic acid diethylamide* (LSD), not a good thing for a schizophrenic brain. Honeys, too, have ergot. Ergot takes longer (up to 20 minutes) to detoxify with added vitamin C. (Read the section on Moldy Food, page 381). If you become ill again after starting grains, go off again. Take 500 mg. niacinamide 3 times a day to speed up ergot detoxification by the liver. Avoidance is much easier.

Healing of the brain is very rapid; in less than one week feelings and behavior are more normal. Perhaps there are herbs that hasten healing; considering how old the illness is, there must surely be several useful herbs. But considering that herbs, too, can be moldy, be very careful to search for molds electronically before using any herbs. Blue vervain, sage, and ginseng are herbs worth trying.

A question may have popped into your mind as well as mine. If the whole family is eating moldy food, why aren't they all schizophrenic? In fact, family members usually do suffer from some symptoms that are similar to the victim. But every person's collection of parasites and pollutants is unique. Certainly, the whole family should obey the moldy food rules, in order to function better.

Autism

Childhood brain disorders suggest an inherited genetic defect. Yet numerous parasites and pollutants are able to pass into the unborn child through the placenta. Even some bacteria and viruses can.

Lead accumulation is always seen in children with autism. Was it acquired before birth?

Mercury can be transmitted from mother to child, too. If mercury fillings were not removed before pregnancy, have them replaced as soon after delivery as possible (never during pregnancy since the removal itself causes a surge of heavy metal to enter the body).

The common tiny worms such as *Ascaris*, hookworm, *Strongyloides* and *Trichinellas* easily enter the brain. They are present in dirt. Dirt enters buildings via shoes. Shoes carry animal filth. Don't let children put their own shoes on until they have learned to avoid touching the soles. Don't let your child crawl on the floor of a public building, even though it looks glossy. Don't set shoes on furniture or table! A preferred habit is to leave shoes at the door.

Once wormlets have found a pathway to the child's brain it is difficult to reroute them. They must all be killed repeatedly since there is daily reinfection from putting hands in mouths. All family members should kill these parasites weekly to protect the child with autism. When lead and parasites are gone consistently for several weeks the pathway to the brain heals and reinfection no longer sends them to the brain and your child can resume a normal life.

I have not treated enough cases to point to a particular parasite or pollutant. For this reason you must do a total cleanup: body, environment, dental, diet (especially solvents and molds).

Leon Dickson, age 10, appeared normal at birth but he crawled and walked late. At age 3½ he began having seizures and was also diagnosed with autism. (Seizures are caused by *Ascaris* larvae, they probably began the routing to the brain). He was started on Phenobarbital™ by his clinical doctor; switched to Dilantin™ then two other drugs were tried. Now he was on Tegretol™ plus Depacote.™ The mother used no anti nausea medicine during pregnancy, no caffeine, no alcohol or nicotine, not even a single aspirin. In spite of his medicines he seemed to have headaches, continued to have seizures which disturbed his sleep and he wasn't trying to talk. He vomited a lot. He would take no pills or drops (no herbs even mixed with honey) and our frequency generator method was not discovered at that time. He couldn't kill his parasites and *Shigellas*. His brain was full of thallium (not mercury!)

> besides the roundworm larvae. He must have gotten this from Q-tips™ or cotton balls or some other mercury-sterilized product. Leon's favorite food was grilled chicken which he ate nearly every day, as well as two eggs a day.
>
> His diet was changed to exclude chicken, eggs, bacon, chips, preservatives and colors in foods, grape jelly and strawberry jam. One month later he had not improved, nor had they been able to kill his parasites with the herbal recipe. The diet change was extremely difficult; he was screaming for his favorite junk food and the whole family was upset over his restrictions. But we encouraged the mother to stick to her purpose, get a different baby-sitter who would obey her, and to try to get some parasite herbs and thioctic acid (100 mg. daily, stirred into honey, to take out lead) down him. The first week the new baby-sitter succeeded in getting him to take thioctic acid. He had only one seizure that week. This encouraged the mother to enforce the parasite program and the diet rules. He became attentive in one month and tried to voice sounds.

The problem with eggs is that they are contaminated with *Salmonellas*. I find, however that it is the outside of the eggshell and the carton that is contaminated. The safe way to handle eggs is to remove them and return the carton to the refrigerator, then wash the eggs and your hands before cracking them. Eggs also contain malvin, a known seizure trigger.

Kirk Peeples, age 5, did not have any words yet but he would point to something and voice M-M-M to mean he wanted it (usually food). He was in a special school and “doing well.” He had the brain toxin MSG, and antioxidants BHT and BHA accumulated in him. In other words, his liver was not able to detoxify these common food chemicals. At that time, I had not found the mold toxins yet; I would now surmise that they were responsible for the liver's disability. Besides going off these food additives he was “desensitized” to them with homeopathic drops by an alternative allergist. The result was immediate. In one week he tried several new sounds and managed his first word: “box.” After killing parasites with the herbal program over a four week time period he could speak 19 words. The parents were bewildered with joy. They cleaned the toxins out of their home so thoroughly, there was no place to sit and nothing familiar to eat. But their son could say things and the parents loved each new sound as if it came from a newborn baby. In two months he was saying two-syllable words and putting phrases together. He needed us no more (he was on homeopathic thyroid drops, too).

Geoff Berkely was diagnosed autistic. He went about his business of examining everything in the office without a word. He was infested with both species of *Ascaris* (there was a pet dog) and was started on the herbal parasite program: just a little less than the adult doses. (Children's' syrups are not as effective.) He was toxic with mercury, too. He had 2 or 3 “baby” root canals. These were to be pulled out. He was also taken off food color, MSG, chicken and eggs. The parents accomplished all this very quickly and called to say their child had become normal but they didn't want us to spread the good news to the “autism” club they attended for fear of criticism for doing unorthodox things. Only in the USA could such thinking occur!

Digestion Problems

Burping, bloating, and being gassy are signs that your digestion isn't perfect. What has gone wrong? Burps are gases escaping upward. Bloating is due to bubbles of gas causing pressure. Your body does not make gas! Gas can only be made by bacteria. The immediate conclusion is that bacteria are growing in your digestive tract (stomach and intestines) that should not be allowed to do so. They are likely to be the common enteric (digestive tract) bacteria: *Salmonellas*, *Shigellas*, *E. coli*, *Bacteroides fragilis*.

You may wish to identify them before killing them with the zapper. Or you can sweep through the whole bacterial and viral range killing all with a frequency generator. The good effects can be felt in an hour, although the last gases may take days to get rid of. *Salmonella* and *Bacteroides fragilis* are two bacteria that can eat bile, and can do without oxygen, so they are commonly seen in the liver. *Bacteroides* probably escaped from its roundworm host, *Ascaris*. *Salmonella* probably came with non-sterile dairy food.

If you have an intestinal problem involving digestion or pain, start immediately to boil all dairy foods. Stop eating those that can't be boiled: cheese sandwiches, yogurt, ice cream. It must be boiled for 10 seconds. The bacteria are in the liver because your liver attempted to strain them out of your blood and lymph in order to kill them with bile. Instead, they turned around and "ate" the bile, turning it brown as evidence. Now, every time the liver lets down bile into the intestine (and stomach), a population of these bacteria goes with it. The intestine becomes a seething mass of bacteria, bubbling away as they produce CO_2, SO_2, H_2S, CO (carbon dioxide, sulfur dioxide, hydrogen sulfide, carbon monoxide). Some of these gases are quite toxic.

Help your liver expel its bacterial overload with liver cleanses (page 552) until all the bile is a beautiful bright green. This is evident as dark brown bowel movements. Without the green color of bile added to your intestine, the bowel movement remains light colored, such as tan, yellow or orange! By stopping eating polluted food, killing bacteria and cleansing the liver, digestion becomes normal again.

Of course, there must be enough acid in the stomach and digestive enzymes produced to make good digestion possible. Otherwise, leftover food goes to feed the waiting bacteria.

Persons with a chronic digestion problem may also find they harbor lead, cadmium, or mercury in the intestine! This is very good in a sense. Your body has kept these toxins in the intestine, preventing it from getting into your vital organs. The bad news is that their presence in the intestine could start an intestinal disease. Toxins in the intestine would inhibit your immune system (here the white blood cells are in clumps called *Peyer's patches*), from gobbling up the "bad" enteric bacteria. Maybe the "good" bacteria found your intestine too toxic to live there. Clean up your dentalware. Search for lead and cadmium in your drinking water. After improving your lifestyle, continue to do liver cleanses. Keep your goals high: a flat tummy that feels energetic, no burps or gas.

Stomach ache (page 98) and **hiatal hernia** (page 133) are also digestive problems but are dealt with under pain. (See also lower abdominal pains, page 97, and appendicitis, page 100).

Alan Barth had his two young sons with him. One of them had a very sensitive stomach, a poor appetite, wanting nothing but sweets or chips to eat. The 16 year old had aches and pains that were keeping him out of sports. The father had a tonsil problem; they swelled if he drank milk. One problem was obvious. Their milk was tainted with *Salmonellas* and *Shigellas*, setting up throat problems for the father, stomach problems for one child and a pain syndrome for the other child. Boiling all their milk, not bringing raw chicken into the house (*Salmonella* Source) and stopping eating yogurt and cheese was the solution. There were traces of lead in their tap water and the house air had vanadium in it, announcing a gas leak. They were all heavily parasitized. When these problems were cleaned up, the whole family's health improved.

Kae Nakajima, middle age, had a history of ulcers and stomach problems. She took a lot of Zantac™ and Tagamet™ over the years. She was drinking coffee, tea and colas. She had *Ascaris* and cadmium in her stomach. Five months later she had cleaned up everything except dentalware and was feeling very good. She didn't need any medicines. She still had arthritis and sinus problems but felt so encouraged she had the dental work scheduled.

Sven Lippencott, age 4, had been tube fed for several years due to weak stomach action. He was quite underweight for his age. He had a population of intestinal fluke in his stomach along with arsenic (pesticide). The rest of the family also had intestinal flukes. After killing parasites and washing the upholstered furniture, Sven's appetite went up so he ate more by mouth and grew immediately. But he soon picked up *Ascaris* and cat liver fluke (there was an indoor cat). Then the whole family got intestinal flukes again. They all, including Sven, drank carbonated beverages *ad*

> *libitum* (whenever they wished). With both parents working it would not be possible to discipline the habit. Sven had wood alcohol, methyl butyl ketone, hexanedione, methylene chloride and toluene buildup making his recovery hopeless.

Alzheimer's

What was once a rare disease has become a household word because it now affects so many. Two new pollutants of the brain, inviting an old parasite to a location it would not normally be, is the explanation. The new pollutants are solvents that seek the brain.

Xylene and **toluene** are pollutants of popular beverages, decaffeinated powders and carbonated drinks. At first, the body can detoxify these but with a steady stream of solvent arriving, detoxification slows down and parasites begin to build up in the brain. Common fluke parasites which we eat in undercooked meat and perhaps get from our pets, can now reach the brain and multiply there.

Other toxins are also present, such as aluminum, mercury, freon, thallium, cadmium. Aluminum buildup is seen in all Alzheimer's sufferers (100%). This is undoubtedly part of the true cause. Did it come before or after the parasites?

Whatever the answer, your job is clear. Remove every bit of aluminum from the food and environment. Throw out the pots, the aluminum foil, the cookie sheets, the tea ball. Throw out the kitchen salt, the pickles, the baking powder. Buy things made with baking soda (not baking powder), use a plastic salt shaker, buy salt without added aluminum. Stop using commercial soaps and lotions. Make the soap recipes in this book. Finally, tape over all aluminum handles in the bathroom and elsewhere (e.g. the walker) with masking tape. Then find a chelating doctor to help remove aluminum from the brain. Also use thioctic acid (100 mg; take 2 three times a day).

Kill the four common flukes with the first frequency genrator or zapper you can get your hands on. Prevent reinfection from meats and pets. Stop all commercial beverages, including water. The processing has left xylene and toluene in them. They are not put in intentionally. For the same reason, health food beverages are similarly polluted. Only milk is safely bought from the store. You must still sterilize it, however. Make your own fruit juices. Select beverages from the list of recipes given. Drink water from your cold water tap, filtering it with a small pure carbon filter as in a filter pitcher (see *Sources*).

As much as xylene and toluene are brain-seeking solvents, *Shigella* is a brain-seeking bacterium. The symptoms it causes are not always the same since they depend on the location of infection. Sometimes they cause tremor, sometimes loss of balance, sometimes speech problems. But they are very serious problems. Kill *Shigellas* every day at bedtime with your zapper. Start the Bowel Program (page 546). When improvement is lasting you know you have stopped reinfecting from your own bowel or from polluted dairy products.

Remove dental metal and use thioctic acid as a help to clear tissues of metal. Use vitamin C (3 grams) and B_2 (300 mg) to assist the liver with detoxification. Use B complex (2 a day) to assist the liver generally. Avoid food molds; ergot especially has strong mental effects (see Moldy Food, page 381).

Start a kidney cleanse (page 549) as soon as you can. Follow this with a liver cleanse (page 552). Clean up environment and diet. Your beloved family member or friend with Alzheimer's can regain her or his mental function to a considerable degree. **Most important is stopping the mental deterioration** before it is not reversible.

Lisa Anne Reed, 60ish, was tentatively diagnosed with Alzheimer's 10 years ago. She needed complete care at present but was able to walk (could disappear quickly) and eat. She could occasionally say her name. Her brain had intestinal flukes and their eggs and was toxic with aluminum (cooking pots) and aluminum silicate (salt). One week later she still had the parasites because nobody could skillfully give her the parasite program. She was also toxic with benzene so reinfection was occurring. In addition she was toxic with bromine (from brominated bread?), chlorine (chlorinated water?) lithium, bismuth, vanadium, and tungsten, all known to have strong brain effects. She was also toxic with moth balls and iridium. She harbored *Naegleria*, another brain parasite. In another week there still were no changes due to inability to administer the treatment.

Isabelita Ufford, 77, was in a wheelchair, brought by her two daughters who took turns caring for her. She was on Clanopin™ medicine, did not try to speak and needed total care, including feeding. She had been ill about seven years. She had intestinal flukes and their stages in her brain (the cerebrum) as well as intestine. She also had isopropanol solvent, aluminum, chromate and high levels of arsenic in her body. She was given the parasite herbs plus instruction to get rid of solvents and metals but the plans could not be carried out. The parasites could not be killed without considerably more help than was available. She was a dear, sweet person. The daughters were highly motivated but were overwhelmed with the size of the task.

Beth Hamm, 60ish, arrived led by her ever-vigilant, ever-caring husband. She was started by medical doctors on EDTA chelation to remove aluminum from her brain. My tests showed aluminum, toluene, sheep liver flukes, asbestos and *Shigella* bacteria. The parasites and bacteria were zapped immediately and her husband began the difficult task of excluding non-sterile dairy products from the diet provided. In four days she was able to walk by herself, knowing where she was going. She could finish a short sentence and comply with directions to sit down and get up. Then she had a set back—she had acquired *Salmonellas* in the brain from a bit of dairy food that had slipped by his attention. She was given Lugol's and she improved further. In ten days she was a new person; an interview of twenty minutes length did not reveal Alzheimer symptoms. Will she be able to hold on to her gains? Only if the aluminum and asbestos are removed from her home environment, his vigilance with dairy food keeps up, and she stays on a maintenance parasite program. But her husband appeared intent on her recovery. She is a person again. And there seems to be a delightful companionship.

Ruben Camberos was brought by his wife and a friend for Alzheimer's. The first day he arrived, the intestinal flukes in his brain were found and killed. He was started on EDTA chelation. They were warned about non sterile dairy foods. His *Shigella* was zapped. Four days later he spoke his first meaningful sentence: it was three words long. He could pay attention to the appointment proceedings. Two days after that he was reading a newspaper. This was utterly shocking to his wife. In another three days, he could hold a conversation consisting of very short sentences. Larger ones became hopelessly garbled. He was started on ornithine (4) and valerian capsules (6) at bedtime: this produced a beautiful nights sleep (especially for his caretakers!) and his days were less agitated. There were still setbacks later but his wife was determined to get him well.

Dementias, Memory Loss

Memory loss is progressive with age but not due to aging. There are plenty of nonagenarians and centenarians with clear minds and good memories to prove that age is not the deciding factor in the dementias. Why do some people deteriorate much sooner? Could you prevent personal deterioration of mental abilities? You probably can. You will know it by noticing memory improvement. Telephone numbers that left you with no recall, unless you wrote them down, number by number, now form groups as you hear them, and you can jot them down the way you always did! This is a good sign of memory improvement. Your writing can improve. The jagged, crooked, misaligned words can be smoothly written again! You can remember things that happened earlier in the day and talk about it later, at mealtime. You can finish your thoughts in conversation.

Mental deterioration of the elderly is not as complicated as is generally believed. Although circulation and blood pressure play a role, **the effect of toxins is much greater**. The action of toxins is greater in age than in youth. The same polluted water and food causes disorientation in the elderly when it only gives a young person a stomach ache.

The liver's detoxification capability may be the real issue. Indeed, the liver may age, in accordance with the calendar date. Perhaps the liver is the only truly aging organ. It may even determine your life span. The answer, then, is to stop giving it toxic substances and shortening your life span.

As the liver is less able to detoxify them, common toxins are allowed to roam the body with the circulation, doing harm to all the organs. The brain feels disoriented or dizzy; there is memory loss. At first, the liver can “catch up” its work and finally clear the toxin for excretion. But, eventually, it can't catch up or keep up. The body, notably the brain, is bathed in toxic chemicals that interfere with its functioning. Now, the elderly person must use a cane for stability, must walk very carefully not to fall, must write everything down to remember it, calls people by their wrong names, can't “find” the right words to speak with, can't finish sentences, must write on a calendar to keep the days straight, starts talking to themselves to help think of things, develops tremors and unsteady gait, acquires a passive personality, loses weight, gets stooped, stops reading the newspaper.

All these signs of aging (dementias) can be reversed by simply removing the common toxins with which we are already familiar.

Of primary significance are food molds. These cause brain hemorrhages. Clean up diet, mouth, body, environment, very meticulously.

Of course, an elderly person cannot bring these changes to herself or himself. If you have a loved one with symptoms of aging, and this person is willing to cooperate with you, you can honestly promise them numerous improvements. Spend a good deal of your effort on persuasion since living longer or being healthier may not seem worth giving up a coffee and doughnut breakfast. On the other hand, they might respond to the goal of needing fewer pills, getting into their own apartment again or becoming freed from a walker.

Walter Heffern, 64, had been to various neurologists but could not find any help. He appeared to have the same kind of mental deterioration as his mother, but at a much earlier age. He couldn't understand an ordinary conversation; he constantly spoke about winning money, walked hesitantly and had to be left undisturbed to accomplish anything—even eating and dressing. He needed a lot of care. We found he had *Ascaris* larvae in the brain—in the cerebrum, where you think. He also had *Acanthocephala*, *Dipetalonema* (a chicken roundworm), amoeba (*Entamoeba histolytica*) and *Fischoedrius* in the thinking part of his brain. He had been in the poultry business all his life: his mother probably shared this exposure, as well as other lifestyle habits that gave them solvents and pollutants besides parasites. He had constant ringing in his ears, this could affect hearing an ordinary conversation. He had a water softener that would have supplied a daily dose of aluminum to the brain, too. There always were dogs in the house. Perhaps the marvel is that he was no worse off, a tribute to human strength in general.

Pushing Back Age

This chapter is a tribute to Jimmy, Nazy, Michele, Suzanne, Marlena and all the others who achieved excellence with daily care-taking of Mary Austin, deceased at 97.

It's true that we have to die sometime. But why die before our life span is up? If many people can live to 100 years, then surely this is the human life span, not three score and ten. Some scientists think the true human life span is closer to 140 years! And that we all lead shortened lives. The shortening is due to failure of some organ in us. Other organs are dependent on the failing organ and begin to fail also. When the brain fails, death occurs, sometimes in five minutes.

If we knew which organ is failing, we could come to its assistance and prevent the collapse of the whole body. Often it is easy to see which organ is failing. But whether this is the true beginning of the body's problems we cannot know. Before death there may have been appetite loss. Before the appetite loss there may have been a broken hip. Before the broken hip, dizziness. Before the dizziness a blood pressure or blood sugar problem. Before these, an episode of "flu" or a dental "repair." Sometimes we know what started it all. But often we don't. Just make a guess and begin somewhere.

Diet

If your aging friend or relative is in a home for the elderly, you may be able to persuade him or her to choose a diet that is wiser than the average diet people eat there. This can help a lot. Just stopping drinking the coffee, decaf, iced tea and carbonated beverages that are served, and switching to the recipes in this book could get them off some of their medicines.

The beverages to encourage are sterilized milk and hot water—delicious with whipping cream, honey and cinnamon. This gets them away from solvents, oxalic acid and caffeine.

Old age is not a time when you "no longer need milk." Calcium losses increase in old age. Milk has the organic form of calcium, chelated with lactic acid, and it has the cream to promote absorption. For this reason, milk should never be reduced in fat content (not less than 2%). The cream is necessary to improve calcium absorption.

In old age it is downright dangerous to be taking many calcium tablets. The stomach does not have the acid necessary to dissolve them. They pass into the intestine, disturbing its function and acid levels. With tablets, too, one must be careful with dosages, while food is self limiting. No elderly person would be able to drink more than one cup of milk at a time. This contains 250 mg. of calcium.

Milk, however, requires stomach acid to curdle it as the first step in digestion. If there is not sufficient acid, it will pass undigested into the intestine, causing new problems. We must listen to the elderly when they say milk gives them gas or other troubles.

Having the milk warm to hot helps in getting digestion started in the stomach. Milk served hot with cinnamon accomplishes two purposes: it will stimulate acid secretion and the cinnamon is an insulin aid. Milk served hot with honey adds the nutritive value of honey, displacing the need for other unnatural sweets. The meal should always include something sour to curdle the milk. It does not have to be added to the milk; it can simply be included with the meal somewhere.

Lemon juice or vinegar can be put in certain foods but the most reliable way to get it into the diet is to put 1 tablespoon into the water glass along with a teaspoon of honey. This gives the water a "sweet and sour" flavor, enough to make it interesting throughout the meal. The fresh lemon juice or white distilled vinegar and a honey dispenser that is easy to use should always be on the table. Bring these two items to your loved one at the "home" if it cannot be provided regularly and reliably. Pop in at mealtime to check up on it. Powdered vitamin C (¼ tsp.) is another useful acid if the first two are not effective enough.

The lemon and honey habit, alone, can add years (healthier years) to an elderly person. The extra acid taken with lunch and supper (the stomach has its own best supply of acid in the morning, for breakfast) improves overall digestion and helps dissolve the calcium, magnesium, iron, zinc, manganese, and other minerals in the food so they can be absorbed.

The habit of using vinegar and honey in water as a beverage was made famous by Dr. Jarvis in his book *Folk Medicine,* circa 1960. He recommended apple cider vinegar for its extra potassium. In those days, vinegar was made of good apples. Now, all the regular vinegars have mold in them. The toxin, *patulin,* in moldy apples has been carefully studied by scientists. It taints the vinegar as well as apple juice and concentrate made from them. I have not tested patulin to see if it can be detoxified by vitamin C. We must use only white distilled vinegar, even though it lacks potassium, aroma and popularity. Using a variety of honeys can make up for the need to vary the flavor. Get orange blossom, linden blossom, buckwheat, wildflower, and sage honey, besides clover blossom.

But honey is not perfect food. It usually has *ergot* mold, a very serious toxin. To detoxify the ergot, you simply add vitamin C to the honey as soon as it arrives from the supermarket. This gives it plenty of time to react with the ergot before you eat it. Bring your "fixed" honeys to the home.

If your elderly loved one has not tolerated milk in years, start with the vinegar and honey beverage, or lemon and honey, and be patient until that is accepted. Then add only ¼ cup milk to the day's diet, (in the morning, on homemade cereal). Go up very gradually and only when digestion allows it. Of course, the milk must be sterile.

If it is not sterile, the final warming will only increase the bacterial count. You must be sure of its sterility. Boil the milk yourself. Near-boiling is not hot enough. It must be heated until it bubbles up and almost goes over the container for ten seconds. Use a non-metal pot that holds one to two quarts. You may throw away the skin. Then cool and refrigerate. Supply it to the home, too.

Milk that is marketed in paper containers that need no refrigeration has been sterilized; it is safe.

Once the body, even an aged body, finds a nutritious food that does not cause troubles of its own, it asks for more. Your loved one will accept it and drink it without forceful coaxing, if there is no problem with it. As long as your loved one tries to avoid drinking it, your challenge is to find the problem and solve it. It is not a matter of taste or habit. It is a matter of digestibility and lack of toxicity. When your loved one is drinking three cups of milk (or buttermilk or whey) a day and three cups of water, there will be no room (nor request) for the usual coffee and tea and other bad beverages.

We all must die of something. But it needn't be a stroke, or heart failure, or cancer. Choose what seems to be the most pressing problem to work on. Common problems that plague the aged are brain problems, incontinence, bad digestion, diabetes, tremor, weakness, feeling cold, sensitivity to noise, losing the sense of taste and smell, hearing loss, insomnia, kidney and heart failure.

Increase Oxygen

Brain problems include memory loss, communication deficit, dementia (calling things by inappropriate names and saying inappropriate things). The brain is simply not getting enough oxygen and food to work right. It is like having a pocket calculator with rundown batteries: it will give you wrong answers (without telling you they are wrong). Not enough oxygen to the brain is the main cause of memory loss, inability to find the right words, getting words mixed up and not being able to speak in sentences. You can prove this by providing oxygen from a tank; modern equipment is very easy to use and inexpensive. If your loved one responds well to a few hours of oxygen, you have proof of the problem.

How can you increase oxygen in the brain?

1. Open the blood vessels wider.
2. Increase pressure of blood running through the blood vessels.
3. Raise the oxygen level in the air that is breathed. Less carbon dioxide, tobacco smoke and auto exhaust. All these, including a gas leak from the pipes in the house, compete with oxygen.
4. Increase the oxygen delivery system to the brain by raising hemoglobin levels. Cure anemia and low iron levels.
5. Raise oxygen saturation of blood by keeping body acidity down.
6. Correct a slow and irregular heart beat.

Niacin

Open blood vessels wider by giving **niacin**. Give it early in the morning, upon rising, as soon as the feet are set on the floor. Keep it at the bedside, use small capsules or tablets and combine this chore with water drinking. The water should not be cold and should have nothing added to make it a beverage. (Drinking water within minutes of sitting upright may also move the bowels soon.) A 250 mg. time-release niacin tablet (see *Sources*) is a good choice. The elderly have little side effects. Even the niacin-flush, which reddens the face and neck is welcomed since it gives a sensation of warmth.

The flush is intensified by giving hot liquids or acids (even vitamin C) to drink. The flush is reduced by giving cold liquids. The opening of blood vessels by niacin only lasts a few hours. If you see it has a good effect on your loved one, give several a day. Do not use a prescription variety, since they are polluted with heavy metals; use only the brand in *Sources*, or a brand that you have tested pure. You can freely experiment with niacin to find the best dosage and variety; it is not toxic in this amount; but the size of the tablet should not turn it into an unpleasant chore. Reduce it if it seems too large to swallow. Don't cut tablets in half, the rough edges can scratch the throat.

Hawthorn berry is an herb that opens blood vessels, particularly to the heart. Carefully watch the effect on blood pressure when using it.

Food mold, particularly ergot, has the opposite effect of niacin. Brain blood vessels are made narrower, cutting down the oxygen supply. Ergot is a common contaminant of grains: don't provide rye or pumpernickel breads or crackers. Don't provide wine or other alcoholic beverages; they are too contaminated with ergot and aflatoxin. Narrowing the blood vessels in the brain can lead to stroke. If you notice an attack of dementia coming, try a niacin tablet (100 mg, not timed release) immediately.

Fig. 34 Alcoholic beverages contain ergot and aflatoxin. Add vitamin C (1/8 tsp.) upon opening and wait 10 minutes for it to act.

TIA’s, Strokes and Purpura

Sometimes, the elderly person is aware of the onset of a brain attack; they may see stars or peculiar shapes or lose vision temporarily. These are called *temporary ischemic attacks* (TIA's). Immediately give a 100 mg tablet of niacin, 1 gram vitamin C, and a B-complex in this order of importance.

TIA’s are caused by spasming in the brain blood vessels. If this causes them to spring a tiny leak somewhere, a part of the brain will not get its usual oxygen and nourishment. A stroke results.

The spasming was probably caused by sorghum molds. Cooking during the manufacturing of sorghum syrup kills the mold but its toxic byproducts (mycotoxins) are still present. Other syrups may have sorghum added, polluting them. Brown sugar is also polluted with sorghum molds, but fortunately you can detoxify this mold with vitamin C as usual. Mix well ¼ tsp. powdered vitamin C with each new (1 lb.) box of brown sugar.

Purple patches, like bruises, on the hands or arms of an elderly person are called *purpura*, and is also caused by sorghum molds. It weakens blood vessels so they break easily.

When an elderly person has purpura or TIA’s and the mold source isn’t obvious, you must track it down. Test in a saliva sample for all the sweetenings used recently (at least an hour ago). At the very least, keep notes on all the sweeteners being used. Look for a common one at the next attack. Never let the trigger food be eaten again.

Blood Pressure

Increase blood pressure if it is habitually too low. Blood pressures below 110 may prevent strokes but ruin the quality of life. Low blood pressures are often due to toxins from foods. But severe salt deprivation in the diet can also cause this. If the adrenal glands are not conserving salt properly, too much sodium is allowed to leave the body with the urine, resulting in low sodium levels in the blood and a blood pressure drop. Adrenal performance is improved by taking the kidney herb recipe.

The kidney herbs (page 549), at half dose level (½cup a day instead of a whole cup) can be given daily for three weeks and then on alternate days indefinitely. Be very careful to keep the herbal tea sterile by reheating. Elderly people seem to sense the improvement given by kidney herbs. Try other kidney herbs from time to time: **shave grass, cedar berries, juniper berries, butcher's broom, cornsilk**. None interfere with drugs. Remember, they also have a diuretic effect. Be prepared to use extra paper padding in underwear to help catch the extra urine output. The first few nights may be disturbed by extra urination. Interpret this positively.

After the blood pressure comes up to 115 (systolic) mental performance will be greatly improved. Don't try to bring it up to 120 since this raises the stroke potential without giving you much improvement in performance. Use an electronic device to measure blood pressure, one with a finger cuff, not an arm cuff which can itself induce broken blood vessels. Purchase a device that needs no adjustments of any kind and has automatic cuff tension control (see mail order catalogs if your pharmacy does not have one).

Air Pollution

Improve the quality of the air by lowering the pollution level. Check into carbon dioxide, carbon monoxide, fumes from a gas stove pilot light, auto exhaust from an attached garage or nearby highway, arsenic from household pesticide, PVC from new plastic curtains or carpeting, formaldehyde from wearing new clothing before washing it, asbestos from hair dryers, freon from a refrigerator, fiberglass, and chlorine from running tap water. Some of these displace oxygen, some are simply toxic to the body and lungs. Clean up the air according to the general principles of environmental cleanup (see Four Clean-ups, page 409).

For the elderly pay special attention to **chlorine** in the air. Shower water puts a lot of chlorine into the bathroom air which then distributes itself through the rest of the house. Notice whether your elderly person goes into the bathroom in fair shape mentally but comes out confused, unreasonable. Not every day's chlorine exposure will have the same effect. Trust your judgment. Attach a carbon filter to the shower head (see *Sources*). Purchase a variety that has very simple-to-replace cartridges. Figure out how long it should last and write the date for replacement on the outside of it for your own convenience.



When into and out of the bathroom is a different performance suspect chlorine. Put a filter on your faucets.

Fig. 35 Chlorinated water can cause mental problems.

Washing hands and face in chlorinated water can give off enough chlorine to trigger a manic episode in a manic-depressive person. Certainly, it is enough to cause mental effects in an elderly person. Of course, the chlorine bleach bottle should not be kept under the sink. It should be kept in a closed plastic bag in the garage. It should not be used while the elderly person is in the house and never for his or her laundry. Use chlorine-free bleach.

Don't pollute the air with fresh flowers, potpourris, or room fresheners. These can induce a dizzy spell.

Room air conditioners may have a fiberglass filter! This fills the house with tiny particles of glass to be breathed by everybody. The body makes tumors out of them in order to stop them from cutting through your tissue. Replace the filter with a foam sheet. This sheet is 1/8 inch thick and washable. I have not found these types of foam filters to emit formaldehyde.

Room air filters are not the answer to polluted air. Removing the pollution source is. Air filters may remove some of the toxic elements but by blowing the air (and dust) around vigorously the remaining toxins are made much more vicious in their effect. The noise of a filter motor and fumes it may put out itself adds misery to the simple job of breathing. Using a non-fiberglass filter at the furnace is a better idea.

Make sure all fragrances are removed from the air, even though family members “like” them. They don't belong in air. The lungs treat them like toxins to be coughed up or removed by the kidneys and immune system. This includes colognes, scented tissues, soap and shampoo and shaving supplies. If you can walk into the bathroom blindfolded and know you're in the bathroom, it's not clean enough. Everything in the bathroom pollutes the air of the whole house. People who must use fragrance should apply it outdoors to keep the indoor air less polluted.

Anemia



Fig. 36 Red blood cells, top and side view.

Oxygen gets to the brain on a carrier system of tiny rafts called *red blood cells*. They were meant to be an exact shape and size to fit the most oxygen molecules onto them.

Each red blood cell is shaped like a doughnut without the hole. This fits a lot more oxygen, O_2, than round balls would. Yet, if there isn't enough vitamin B_{12}, the dimple isn't put into them to make them doughnut shaped. This reduces the body's oxygen supply and the disorder is called *"pernicious" anemia*. The changed shape of the red blood cells is reflected in a bigger volume called *mean cell volume* (MCV). The correct volume for red blood cells is about 90 cubic microns. Many elderly persons have a MCV over 100!

I have seen pernicious anemia to be associated with *Ascaris* infestation. Kill *Ascaris* on a frequency generator (408 KHz) or zap. The source of *Ascaris* is usually a pet, owned in the past. Once infected, the tiny worms do not leave your body on their own. The infestation may date back to childhood. What a relief for the bone marrow whose job it is to make red blood cells to have enough vitamin B_{12} again! What does *Ascaris* do with your B_{12}? B_{12} is a beautiful rose colored vitamin. Some worms are actually pink from absorbing your B_{12}! Giving B_{12} shots is the current clinical treatment for B_{12} deficiency. Killing *Ascaris* twice a week by zapping and taking B_{12} lozenges (see *Sources*) is a better solution. (If your loved one is getting shots, make sure that no isopropyl alcohol is used on the skin beforehand. Provide vodka yourself in a small pocket flask or 70% grain alcohol for this purpose. Unfortunately, the shot itself may contain traces of this harmful solvent—take a sample home for testing.)

Other kinds of "anemia" can deprive your elderly person of oxygen. A low red blood cell count (under 4.4 million/mm^3) is the "garden" variety. Sometimes iron levels are low and can explain the low red blood cell count. Sometimes they are not.

Most regular anemias, including low iron levels, are associated with hookworm infestations.

Kill all *Ancylostomas* along with *Ascaris* twice a week. It is not wise to take iron pills, even if they do raise hemoglobin levels, except in life-threatening situations. Remove the tiny creatures that cause microscopic bleeding instead. Iron in the form of pills is too easily snatched up by bacteria who also need it, making them more virulent to the body. Use grain alcohol rinse in the bathroom to kill *Ascaris* and hookworm eggs under fingernails. Don't have pets in the house or keep them on daily parasite killing herbs.

It takes nutritious food to build the blood back up to its normal hemoglobin level. Eggs and meats (all very well cooked) are the richest sources of iron and other minerals used in blood building. B_6 and other vitamins are also involved and can be given as a B-complex (see *Sources*). Do not use black strap molasses as an iron source, or any molasses, since it contains toxic molds. (The molds could be detoxified with vitamin C the same way as honey. However, I have not tested enough molasses for solvents and you cannot risk these.) In the past, when the nutrient properties of molasses were discovered, the molasses manufacturing was a small, carefully conducted business. Now it has molds which cause platelet destruction, (purpuric spots) internal bleeding, and immune failure.

Acid Levels

Oxygen must first jump onto its raft, the hemoglobin, in the lungs. Later, in the brain, oxygen must jump off again to enter the brain cells. A difference in acid levels makes this possible. Acid levels operate the latching system that decides whether oxygen will be attached to hemoglobin or let go! Acidity unlatches oxygen. There should be no acidity in the lungs so oxygen can attach here. Sometimes, the entire body is too acid! Diabetics, asthmatics, arthritics, especially, suffer from total body acidity.

Acid was meant to be removed from the blood and loaded into the stomach at mealtime for digestion. When this isn't happening, it was meant to be shipped out of the body with the urine. But the kidneys may be doing a poor job because they are clogged with tiny crystals and because not enough water is drunk, so the body's acid levels rise. You can test total body acidity by measuring the pH of the morning urine. It should not be under (more acid than) 5.5. If the body acid level is too high, help the kidneys excrete it by adding more water to the diet and more minerals to neutralize the acid. The main minerals for this purpose are calcium and magnesium.

Increase Minerals

Adding water to the diet could be the most difficult of tasks if your elderly loved one “doesn't like it.” Calcium should be in the form of milk, magnesium as a tablet. When tablets cannot be swallowed; use magnesium oxide powder (see *Sources*). Use 1/8 tsp. added to cooked cereal, soup, stew, pudding. Magnesium, being a mineral, does not get destroyed as vitamins may. You can add it anywhere in the diet where it won't be tasted. Notice how calming it is to have extra magnesium in this gradual way. And how much better the sleep is at night.

When water "doesn't taste good," there is probably a valid reason. The body may be trying to reject chlorine or other toxins in it. In this case, filter it with a small all-carbon unit that is changed right on schedule. A plastic pitcher (not clear plastic or flexible plastic) with a carbon pack fitted into the top is best. Sterilize it once a week by putting a cup of water and one tbs. of grain alcohol in it and turning it upside down so the filter can soak for 15 minutes. Flush out the alcohol with two pitchers of water. Make sure the temperature suits the person. Temperature can mean everything to the never-thirsty person. Don't allow ice cubes, however, nor beverage making, with the essential water. Adding lemon or vinegar (white distilled) and 1 tsp. honey is probably the best way to stimulate both thirst and appetite.



Fig. 37 Water pitcher with filter.

When blood is properly oxygenated it takes on a bright red color, unoxygenated blood is more purple. A chelation doctor can easily see the state of oxygenation.

Chelation

Chelation is a powerful way to quickly improve oxygenation of blood. The most important rule to observe, though, is to take the treatment slowly. Especially if *ethylene diamine tetra acetate* (EDTA) is being used to remove heavy metals, it is important to take the treatment over a two hour time period. Mini doses may be given in a shorter time. Generally, you are in charge of the flow rate. Discuss it with the nurse. Weekly chelations can correct many problems of the elderly that no other treatment could.

Because of hostility from insurance companies who do not wish to add another cost to their ledger and doctors indoctrinated with misinformation, bad publicity is given to this wonderful, life-prolonging mode of treatment. Clinical doctors who have no time to really investigate the statistics of chelation treatments and for whom this is purely competition may feel antagonistic to these treatments. Your loved one should not be the one who must suffer from medical politics. Go to see for yourself what chelation is all about. The receptionist should be glad to show you around. The secret is to talk to the patients themselves. They are usually sitting around a room, eating their lunch and reading as their IV's drip. The pulse, blood pressure and blood chemistry is also carefully monitored. Sit down with them to find out their stories. Get a realistic picture of benefits and costs.

Pulse

The pulse reflects the heartbeat. A **slow pulse** can give weird brain symptoms besides great fatigue. The cause is usually a drug that is being taken to correct a **fast pulse**! Check with the nurse. Read the insert included with packaging for all drugs used. The drugs responsible are usually “beta blockers”, used for the purpose of smoothing out the heart beat, that is, making it regular. Often the drug can be changed.

Less than 60 beats per minute will lead to trouble. For a young person it is a good sign to be as low as 60, provided no drug is involved. But for the elderly it does not reflect a strong athletic heart beat.

The heart is made of four separate “chambers” or compartments each pulsing in turn. They are like four horses pulling a wagon. Unless they pull evenly, the wagon feels jerky, and irregular. The wagon will wear out sooner with jerky pulling. To smooth them out you simply slow them down. Apparently they sense each other better and can pull evenly now.

A heart that is beating 100 times per minute, not unusual for a weak old heart, can be so irregular that it misses every fourth beat. That creates a terrible deficiency of oxygen. Imagine your four cylinder car or lawnmower missing one out of four engine strokes! Beta-blockers have some quite undesirable side effects but heart regularity has a higher priority. So drugs are the immediate choice. Later, when heart health is improved, the heart will beat regularly without drug use. In the meantime, watch over the pulse. When the pulse drops below 60 the new danger is slowness. Take the pulse daily when a new drug has been added, or when you are working on heart health, without getting your loved one anxious about it.

Heart Health

To improve heart health, the first steps of course would be to go off caffeine and to kill parasites and bacteria. This alone could drop the pulse from 120 to 80 in a few days. Obviously, the need for a drug is gone. Cut the drug dosage in half immediately. Don't wait for a doctor's appointment to O.K. it. If you waited another day the pulse could be below 60.

Many common bacteria, especially *Staphylococcus aureus*, choose the heart as their favorite location. Their nesting place, though, will be under a missing tooth in the jaw (cavitation). Heartworm and *Loa loa* are two very common heart parasites. You can have all these killed in a day, without side effects and your heart is once more free to beat regularly. Don't take a chance on over-medicating. As soon as the beat is regular and under 100 per minute, reduce your heart drugs. Stop them when you are regular and under 80. Fatigue will leave and the brain will work better.

Raising potassium levels slows the pulse. Try to do this with diet by eating more potassium rich food and by conserving on potassium losses. The adrenals are in control of losses. Give them a thorough cleaning. The adrenals are situated right on top of the kidneys where all toxic things are being excreted. Being this near to the urinary tract will result in shared toxins. Urinary tract bacteria, small kidney stones, moldy foods and metal from dentalware are the chief offenders. Switch to composite tooth fillings. Use non-metal jewelry. Cook and eat with non-metal ware. Don't handle metal unconsciously throughout the day. Aluminum objects that must be touched should be wrapped in masking tape: this includes walker, shower door, bathroom supports.

Door knobs, taped walker handles, and cane handles should be wiped daily with a grain alcohol solution.

Treat the adrenal glands to 5 supplements

1. **Vitamin C:** shake some into all foods that can absorb a bit of the sour taste, even cooked cereal and vinegar water.
2. **Pantothenic acid:** 500 mg., one daily.
3. **B_6:** 250-500 mg. daily.

4. **Folic acid:** 800 mcg. daily.
5. **B_2:** 150 mg. daily. These are minimum dosages.

If no capsules or tablets can be swallowed put a three day supply in a heavy plastic bag. Pound with a hammer; then roll finer with a big glass jar. Use about 1/3 of the mix each day. If you are trying to do all this in a nursing home, feed it to your loved one while visiting. Put the powder mix in a plastic (not styrofoam) cup, add honey and stir until you get a paste. Feed the paste directly by spoon. Often the elderly prefer it this way in order not to bother with pill taking at meal time. Remind them it will turn the urine yellow.

When the brain problems are corrected for an elderly person, be sure to relate the improvement to him or her. Improvements should not be dismissed lightly. Keep notes. This encourages the elderly, letting them know their existence and quality of life is important to you. Improvements are not merely steps to yet further improvements. Enjoy each bit of progress; it is often too subtle for your loved one to notice even when it is glaringly obvious to you. Before and after a chelation treatment can show a dramatic change in mood, energy, appetite and communication ability, yet get no comment from your loved one. Point it out explicitly so your loved one can look forward to it, too.

Aging is no fun. The elderly long for a brisk gait, laughter, and a picnic at a park again. They dwell on dying, though, because they know it isn't far away and wonder what to do about it. They dare not talk about it because it is too painful a subject for the loved ones. And the immediate problems are too pressing to allow much contemplation of future problems. Talk about aging in its positive aspects. Let your loved one express feelings about it.

Incontinence

plagues most elderly persons. It begins to plague women much earlier—after childbirth, for instance. Surgically shortening the bands that hold the bladder in position (called bladder "lifting") can give temporary relief, but the surgeon may be the first to tell you that it is a temporary fix. Still, it is so shocking not to be able to run a few steps or sneeze or cough without wetting the underwear, that anything seems better than doing nothing. Surgeons will tell you that the bands have been "overstretched."

The real reason why nothing, not even surgery, is permanent is that the support bands are weak. Bacterial invasion causes most of this weakness. Low potassium levels (due to excess potassium losses by the adrenals) causes more weakness. When you kill bacteria (and *Schistosomes* and *Ascaris* and other parasites that bring in bacteria) and blood potassium levels go up, the problem is solved. Overnight you may throw those pads away. Even though you needed three pads to be "safe" you will not need any. Whether you have killed bacteria permanently determines whether you have permanently cured the condition. Make sure all dairy foods are absolutely sterile. Ask that the milk be boiled for ten seconds and other foods that can't be sterilized are not on the menu, like sour cream. Sour cream has too much *tyramine* to be safe. Tyramine is a bacterial by product that is quite toxic; it is rather high in aged cheese, also. With the food bacteria, *Salmonellas* and *Shigella*, out of the way and parasites being killed regularly, you can focus attention on the adrenals which control potassium levels.

Be careful not to rave about the foods that your loved one cannot eat.

Eating more potassium in food is a good nutrition project. Bananas are the top choice. Fresh fruit salad and baked potatoes and soup also provides a lot. Mixing potassium salt with regular salt, half and half, for the shaker is another easy trick, even if you only use it in cooking where the taste cannot be detected. Potassium by prescription is often used by clinicians to conserve body potassium during diuretic use. This need not be stopped (if the pills are not polluted) although taking potassium pills is less useful than salting it in because the adrenals will let any big dose escape anyway. A sign of too much potassium is a slow pulse.

It may be necessary to wear some kind of incontinence underwear. Try to avoid them at night, though, so the skin can breathe freely. Bring a commode near the bed for the night, rather than diapering your loved one (but don't call them diapers; say “underwear”). Absorbent pants of all kinds are heavily chemicalized. This is absorbed by the skin and adds to the toxin level. Less will be absorbed if you powder the skin with cornstarch first. Use them minimally and line them with tissue or paper towel. Chair and bed pads, too, are chemicalized. Don't sit on them with bare skin. To facilitate getting to the commode quickly in the night, dress the elderly in a short night shirt, no pajamas or long gown. Bed socks on the feet help with warmth.

Wash the body parts daily, around the urinary and rectal outlet, using borax water. Follow with 5% grain alcohol. Put washcloth in laundry after a single use. Nothing, not even brain improvement, impresses and encourages an elderly person as much as seeing the incontinence lessen. This bit of progress will put him or her solidly on your side. When they believe in you, it makes your task more rewarding. Remember to enjoy and celebrate your achievements together; don't make a grim business out of it.

Bad Digestion

with its excessive gas and burping is another plague of the elderly. They would rather not go to church nor visit a friend than embarrass themselves in that way.

Chewing

It all begins with the stomach although chewing food well is essential for really good digestion. Dentures should fit perfectly so the mouth does not develop sores. Using denture cream is not a good substitute for correct fit and is toxic. Denture plastic is often toxic, even containing mercury in its composition! Toxins in plastic can seep! Such toxins lower the immunity of the mouth and throat and stomach since it all flows down into the stomach. Low immunity in the mouth permits throat infections to be chronic. If your elderly loved one has a red-looking mouth or throat, instead of pink, an infection is going on in spite of no coughs and no complaints.

It will do no good to keep zapping bacteria when reinfection is so easy. First kill the bacteria in the dentures by soaking in 70% grain alcohol. Then test the dentures for toxins. Soak the dentures in water for several hours. Rinse and soak again in fresh water. Repeat a third time to insure that any toxin found came from the dentures, not the saliva. Save this water for testing. Search for heavy metals in the denture water. If you find any, you know the dentures are toxic! Get new ones, made of uncolored methacrylate (see Dental Cleanup, page 409).

The denture-soak should kill bacteria each night. Plastic has tiny pores where bacteria can hide. Use 70% grain alcohol which you make yourself or plain vodka which is about 50% alcohol. Since alcohol evaporates and is expensive, use a wide mouth jar with close fitting non-metal lid for all this. Fish them out with your toothbrush so it gets sterilized too. It only takes minutes to kill everything. Commercial denture cleaners are much more toxic than grain alcohol; don't use them.

Use food grade hydrogen peroxide or salt water to brush teeth in your mouth, never **toothpaste**. Toothpaste has toxic metals (tin, fluoride, strontium) besides benzene pollution. See the section on brushing teeth (page 532) for details and sources. If you are responsible for this daily chore, use homemade floss (2 pound to 4 pound nylon fish line) first; then brush. If your loved one is seated they may be able to handle the brush by themselves, giving them pride in the achievement.

If an elderly person refuses or can't wear dentures, provide food that is soft and without chunks since this decides whether the stomach can digest it. The stomach is the weak point of the digestive process for the elderly because nearly all don't produce enough acid to get the job done.

Stomach Acid

The body produces hydrochloric acid (HCL) which gets pushed into the stomach from the blood! The enzyme, *carbonic anhydrase*, a zinc enzyme, is involved. Not many ways are known to stimulate this whole process. Drinking water before meals stimulates it in unknown ways but is hard to do for the elderly. Next best is to provide acid.

Because strong HCL would dissolve teeth it is not available as a solution to aid digestion. Ask a pharmacist to make a 1% HCL solution and use 10 drops of it in a beverage at mealtime once a day. HCL as a tablet (“Betaine HCL”) is available but doesn't have enough HCL in it.

Using a lemon or vinegar and honey beverage helps with digestion although this provides citric or acetic acid, not hydrochloric. These acids are completely metabolized so they don't add to the body acid level. But the fact that it is not hydrochloric means that it can't kill bacteria and parasites in the stomach like regular hydrochloric acid could. The stomach becomes a haven for *Salmonellas* and other bacteria and this is **the biggest digestive plague of the elderly**. *Salmonellas* dig deep into the stomach wall, safe from antibiotics and stomach acid and aren't washed away with the food. When they take over the region near the top of the stomach, it weakens the esophageal sphincter and food keeps coming back up a bit—a most uncomfortable development, especially after supper or when lying down.

When the Salmonellas spread out further to invade the diaphragm around the sphincter, the diaphragm weakens, and lets a bit of the stomach up through the hole.

This causes *hiatal hernia* distress. Don't settle your loved one in an easy chair after supper. This presses the stomach upward and the food up, too. Leave them sitting at the table a while, then walk a bit, to get the food down lower. The food will sink lower if some of it can leave the stomach at the lower pyloric end. But if *Salmonellas* are entrenched here, too, the lower end does not have enough action to push the food through the valve. Drugs like Reglan^{TM} are given to speed this up.

What helps most is getting digestion completed. This sets up the natural cues for emptying. Digestive enzyme tablets have been in popular use to help digestion. But they may not be safe since they have not been sterilized. Always try the vinegar and honey method first. Coughing during eating is a sign that the diaphragm is irritated (by a hiatal hernia). If drinking water starts the coughing, omit it at the beginning of meals. Work in sips during the meal.

Salmonella and Shigella

Some *Salmonella* infections can bring dizziness to your elderly person. Dizziness is another plague of the elderly, keeping them from going shopping, getting to church and even from getting around their own homes. Drugs such as Antivert^{TM} are given but only take the edge off the problem. Feeling dizzy can make your loved one home bound and stuck to a walker for every move.

Salmonellas, along with *Shigellas*, produce very toxic substances that cause dizziness. There are three common *Salmonella* varieties: *Salmonella enteriditis*, *Salmonella paratyphi*, and *Salmonella typhimurium* (386, 380, 354 KHz). Kill *Salmonellas* daily for a month by taking Lugol's iodine (6 drops in a half cup water, after meals and bedtime, see *Recipes*). Unfortunately, this will not kill *Shigellas*; follow the Bowel Program (page 546) to get them.

During this time set up a system of sterilizing all dairy products (see Milk, page 425) since this is the source of reinfection. Set up a system of rinsing fingers (and fingernails) in 10% grain alcohol in the bathroom. Deli food and restaurant salads carry *Salmonellas* and *Shigellas*, too. Kill them, routinely, after eating such food due to necessity. A warm stomach full of food at a neutral pH is just the right culture condition for these bacteria. It's like putting yeast into a bowl of warm water, flour and sugar. In half an hour it is overflowing with growth.

Once *Salmonella* is entrenched in an organ it is difficult to eliminate. Only an electric zapper can kill them all (in an organ, not the bowel). If your body has the right conditions (like a low acid stomach) to let them grow you dare not swallow another one! *Shigellas* arrive with dairy foods, too, but prefer the lower intestine as their headquarters. Indigestion that starts right after eating is probably due to *Salmonellas*. If your indigestion comes in the night, this suggests *Shigellas*, since they've had time to reach their favorite place further down.

Campylobacter and *E. coli*, other digestive bacteria, are sometimes the culprits. The Bowel Program is effective against these also. Besides getting digestive improvement you get mental improvement, less depression, less dizziness, less irritability after clearing these up. Remember that eating bacteria and killing them later will not solve the problem. Stopping eating them will.

Other Clues

Digestion problems that remain after eliminating bacteria can be diagnosed in a rational way. Ask these questions:

- Is the stool orangish-yellow, or very pale, instead of greenish brown? If so, bile isn't getting delivered to the small intestine from the liver.
- Is there abdominal pain? (More about this on page 97). It may be due to *Ascaris*, flukes, or other parasites.
- Is there constipation? This will let wastes accumulate, all the longer for bacteria to thrive on them.
- Is there bloating? This is due to gas made by bacteria.
- Does the stool float? If so, it must be lighter than water and contain fat or a great deal of undigested material.

Liver Bile

Bile is necessary for digestion. Absorption of fat and calcium depends on bile mixing with the food. When fat isn't absorbed, it stays in the intestine. Fat is lighter than water; it makes the stool float. Feces should not float. When the stool floats you can assume that calcium isn't being absorbed either, leaving the blood in a deficit which will be taken from the bones.

If the stool floats or is orangish in color prepare your elderly person for a liver cleanse (page 552) to clear a bile duct of obstruction. They get quite fond of these cleanses and will ask to have one. Liver cleanses are completely safe, even for persons in their 80's. One of the stones pictured on page 554 came from a woman age 97. The general rules apply to the extremely elderly: kill all parasites first by zapper if possible, otherwise by herbal parasite killing. Do a kidney cleanse (page 549) first, using half a dose instead of the regular dose, for three to six weeks. Attend your loved one in person for the liver cleanse, have a commode at bedside, protect bedding from accident: use paper underwear if necessary. Share the joy of getting gallstones out painlessly with your loved one; let them see and count them if they wish before you flush them (use a flashlight).

Be extra careful with the skin cleansing. Hot water soothes and heals. Use starch skin soother to dispense onto the wet paper towel, besides borax solution and alcohol. Don't use ordinary soap. The starch skin softener gives the smoothness of soap, and prevents the pain of friction. An elderly person may have no diarrhea at all with the Epsom salts! Evidently the body absorbs all the magnesium so eagerly, none is left in the intestine to absorb water and create diarrhea. It is especially important though to rehydrate your elderly person after a diarrhea. This time they do not balk at water consumption. The liver cleanse, it seems, gives them new thirst as well as new appetite. But it doesn't last long. As the stones from the far corners of the liver move forward, they compact into larger stones and plug the ducts again. Their previous symptoms return. Try to give a cleanse once a month until the dark color of the stool returns and it no longer floats.

The benefits of a liver cleanse will last longer if **valerian herb** is taken the day after the cleanse and from then forward. It may be preventing spasm of the bile ducts. Use 2 oz. of the herb (cut) in 3 cups water. Simmer for 5-10 minutes, let settle or strain. Add honey to sweeten. Give a few tbs. every 4 hours (or 6 capsules) for several days followed by a daily dose at bedtime.

Constipation

If constipation is a problem, use an herbal product rather than a drug until you have removed the cause. **Cascara sagrada** (half dosage) or **prunes** work for many people. Adding **roughage** to the diet is a good solution but often doesn't work. If you try bran, you should add vitamin C and boil it, first, because it is very moldy. But even eating tree branches for supper won't move a bowel that has the wrong bacteria in it.

Bacteria are part of the cause; and part of the result! Constipation increases the bacteria level which causes further constipation! You may solve the constipation problem immediately by zapping. Even though this kills some “good” with some “bad” bacteria, no harm is done. The stool is recolonized in one to two days.

Poop Your Troubles Away

Two bowel movements a day are the minimum necessary for good health. The first one should be in the morning. The morning cup of water, drunk at the bedside has the magical ability to move the bowels. Cold water may fail. But the water effect only works in the early morning. Waiting until after breakfast may not work. Notice the energy lift your loved one gets from this most primitive body cleanse. Take advantage of this to exercise them. Go immediately for the morning walk. This might be the only time of day they can enjoy their walk.

Walking and **liver cleansing** are the most health-promoting activities you can do for your loved one.

Make walking as essential as eating. Walking is not merely walking about the house or shopping. Walking should be done outdoors. Walking is a brisk exercise, done as speedily as possible and lasting at least ½hour. Only if the weather doesn't allow outdoor walking can an indoor walk be substituted. Don't let your elderly person choose whether they will walk that day. To overcome resistance, find a cheerful neighborhood person willing to do this task for pay. The need to respond to a new stranger energizes the elderly more than your persuasion can.

Sugar Regulation

Diabetes is a common development in the elderly. If your loved one is already on a pill for beginning diabetes, take this as your challenge never to let it get worse. It is not a chronic metabolic deterioration. It is a destruction of the pancreas (specifically the islets) by the pancreatic fluke which is attracted to the pancreas by wood alcohol. Zap flukes and eliminate wood alcohol as described in the section on diabetes (page 173).

Use no artificial sweetener and no beverages besides milk, water and the recipes given in this book. This is one regimen your loved one will not resent. They are well motivated to prevent the need for giving themselves daily shots of insulin. Use this motivation to acquire the taste for new foods and beverages.

Elderly Person’s 7 Day Diabetic Diet

Daily supplements: 4 chromium (200 mcg. each), 1 or 2 B-50 complex, vitamin C (1,000 mg. or ¼ tsp.). Take with food.

Breakfast

Choose any one; they need not be in order.

1. Two eggs, (replace carton and wash hands and eggs before cracking), wheat-free, corn-free bread, not toasted (special breads can be found in the freezer section of natural food

stores), with butter and 1 tbs. orange blossom honey. 1 peeled pear, raw, with whipping cream. One cup hot milk with cinnamon.

2. Old fashioned oats, with 1/4 tsp. cinnamon and 1/8 tsp. vitamin C, stirred in just before serving. Mix whipping cream with sterilized milk to make a “half n half” for the cereal. 1 tbs. honey. 1 banana. One half cup milk, one half glass water with honey and vinegar.
3. Fried potatoes with 2 eggs (use only butter, olive oil or lard), 1 cup hot or cold milk. A quartered orange (wash the orange before quartering).
4. Cream of rice, with homemade “half n half” or whipping cream, cinnamon and vitamin C stirred in. 1 cup milk, 1 banana.
5. Cottage cheese, cooked in covered skillet to sterilize. Add chives or peeled fruit (not canned). Wheat-free, corn-free bread, or rice bread with 1 tbs. honey. 1 nectarine or piece of melon. 1 cup hot milk. Water with vinegar and honey.
6. Pancakes or waffles with butter and eggs (no sweetening). Fruit (peeled), hot milk, water.
7. Fruit cup, large bowl of peeled, chopped mixed fruit with whipping cream and 1 tbs. honey and rice bread or other wheat-free, corn-free bread with unsalted butter. 1 cup hot milk with cinnamon.

Remember, all honey must be pretreated with vitamin C. All fruit is peeled and free of blemishes and soft spots. All milk, cream, butter must be sterilized for 10 seconds at full boiling point. Butter must not be “raw”. Get wheat-free, corn-free bread at a natural foods store.

Lunch

It is better to have most of the day's calories in the middle of the day than at the end. Arrange for dinner at noon if possible.

Dinner

Choose any one.

1. Green beans with potatoes, meat dish, cabbage apple salad, water with lemon juice and honey, 1 cup hot milk. Water.

   Fresh green beans, especially fava beans contain a substance that is described in old herbal literature to be especially beneficial to diabetics. Don't overcook them—it might harm this substance.

   For the same reason, don't use canned green beans. If “fresh” isn't possible, choose “frozen” but rinse the chemicals off before cooking. Potatoes (not overcooked), peeled to make sure there are no blemishes (contain mold and pesticide) can be cooked with the beans. Cook with onions and oregano for flavoring. Add fresh chopped parsley to the sauce or butter for both green beans and potatoes. Fresh parsley has special herbal goodness (high magnesium, high potassium, diuretic.)

   The meat dish should be overdone. “Fast food” is plopped from the freezer into the boiling grease which browns the outside nicely but can easily leave the inside undercooked. Meat must never be “rare.” There should be no redness near bones! Canned meat is safe from parasites but may have smoke flavoring added (contains benzopyrene) or nitrates. Avoid these chemicals. Avoid MSG too. Whenever a meat dish is not accepted, substitute sardines. Let them choose from a display of six kinds. Purchase the flip-top cans to avoid eating metal grindings from the can opening process.

   Cabbage for salad should be chopped fine enough to be digestible. Add finely chopped apples (peeled) and a few apple seeds and whipping cream for the dressing.

Sweet things are reserved for dessert. Since a diabetic's tissues are not absorbing sugar, they crave it more and more. As the diabetes improves they crave it less. For dessert, serve 1 tbs. of honey to satisfy this craving without endangering their blood sugar regulation. It can be used in the hot milk or in other ways. Undercooking the vegetables also helps slow down the sugar release. Never serve mashed potatoes for this reason.

The drinking water should always have a little vitamin C, lemon juice or vinegar added, and 1 tsp. honey if desired.

2. Asparagus, potato, raw salad, fowl dish, fruit, water with vinegar and honey, 1 cup hot milk.

   The asparagus can be fresh or canned. Bake the potato: not in aluminum foil, not baked until fluffy. Don't let the skin be eaten. Use genuine butter, only, or a homemade sour cream dressing (see *Recipes*). Fresh chopped chives may be added but no regular sour cream since this is very high in *tyramine*, a brain toxin.

   The raw salad should be chopped small enough to be edible by dentures. Use homemade salad dressing with a preference for oil and vinegar styles.

   The fowl dish should be very well done, never “fast food”.

   For dessert, fresh fruit chunks dipped in a homemade honey sauce (honey, water and cinnamon). Less sweets are consumed if you dip the fruit rather than pour the sauce over. Limit the total to 1 tbs. honey. Don't serve grapes or strawberries due to the intense mold problem.

3. Soup, sandwich, fruit, hot milk, water.

   Soup should be homemade from scratch. Add bones and 1 tbs. vinegar (white distilled) or a tomato to the kettle to ensure some calcium leaches out of the bones. A fish chowder serves this purpose very well, too.

The sandwich has lettuce, real butter, and whatever else tastes good (no cheese, bacon bits or condiments). The bread is wheat-free, corn-free, stored in freezer. Homemade salad dressing can be added.

The fruit may be chopped with whipping cream, cinnamon and honey sauce (not more than 1 tbs. honey).

The water may be plain if there was vinegar in the soup.

4. Fish, green beans, potatoes, other greens, fruit, hot milk, water.

   Fried or baked fish is served with lemon or lime. Green beans are served with a cheese sauce so a lot will be eaten. (Cheese sauce: add milk, olive oil to a block of cheese. Melt and cook at least 10 seconds.) Serve au gratin potatoes or scalloped potatoes or any kind of potatoes that will be enjoyed. The extra greens can be beet greens, collards, mustard greens or spinach served with a favorite dressing to make sure it's eaten. (No croutons or bacon bits, though.)

   Never serve dessert if the plate has not been cleared. Your loved one isn't hungry enough. If appetite is very poor, sweets will only worsen the problem. Try to change the menu to stimulate the appetite. Acid foods stimulate; spices and B-vitamins (especially B_1) stimulate; hot foods stimulate. Much appetite is controlled by the liver and brain. Toxins at either location (especially food-derived toxins) tell the body to stop eating. Suspect food molds first, bacteria and chemical additives next.

5. Asparagus, meat dish, white rice (brown rice contains mold), coleslaw, milk, water, ice cream.

   A hot meat dish (no pasta, no wheat flour, no regular gravy) can be fried, cooked or baked, but not grilled. Asparagus is fresh, frozen or canned. Rinse if frozen. Fix it differently than last time. Season rice with parsley and minimal salt and pure herbs like thyme; no MSG or mixed seasoning, make butter sauce. Dessert is homemade ice cream (see *Recipes*).

6. Fish or seafood hot dish. Green peas or peas and onions. Peeled sweet potato with butter (not canned). May switch sweet potato with rice on asparagus day. Sliced tomatoes or cucumber or other raw vegetables with or without dressing. Milk, 1 tbs. honey (can be used on sweet potato).
7. Chili or stew with unlimited rice-bread and butter. If chili produces gas, stay away from it. Serve no canned varieties. Grated carrot salad with stewed raisins added and heavy cream. Milk, water as usual. Blueberry pie, sweet potato pie, custard pie.

If more bread is requested, provide a wheat-free, corn-free variety; but limit bread eating to "after main dish" eating. If not enough milk is drunk: make custard pudding or rice pudding so the daily amount (3 cups) is consumed.

Supper

1. Tuna with salad dressing or tuna salad (no pasta). Non-wheat raisin bread (from natural foods store) and butter. Milk, water.
2. Custard, cooked greens, baked potato. Rice-bread and butter. Herb tea with milk added (single herb only, not mixed herbs).
3. Vegetable soup, homemade, from scratch. Leftover meat sandwich with rice-bread (no deli or cold cuts or luncheon meat). Milk, water.
4. Baked squash with butter, rice pudding with cinnamon, raisins, and honey. Canned salmon or sardines with wheat free, corn free bread. Milk, water.
5. Chili or stew leftovers with wheat free, corn free bread. Custard pudding sweetened with honey, and nutmeg/cinnamon mix. Milk, water.

6. Sardines and rice bread or other wheat free, corn free bread. Homemade tomato juice with celery, strained. Milk, plain water. Pie a la mode (homemade pumpkin or squash pie and homemade ice cream).
7. Potato salad. Leftover meat dish and beans, stewed tomatoes, squash. Baked apple with cinnamon, cream and honey. Milk, water.

Many diabetics lose 50 points (mg/DL) of blood sugar in a few days on this diet. This is why: there is less bread than a diabetic would prefer. There is very little cheese (it must always be boiled in a sauce to sterilize). There is no fruit or vegetable juice except homemade, and not much of that because it crowds out milk and water. If your elderly loved one can't eat all this, make sure there are no snacks consumed between meals that are forbidden.

There is no pasta anywhere. Pasta is mold-ridden. Even after cooking, it may be toxic. There is no wheat or corn bread. The menu is heavy on green beans and asparagus and cinnamon. If by chance, your elderly person hates these and starves themselves to get your sympathy, add a lot more potatoes and rice (never brown) to raise calories.

There is no sweetening other than honey (5 kinds). There are no syrups or sugars. Honey is self limiting—the taste for it is all gone after 1 tbs. Not so for other sugars. The heavy use of cream and butter is offset by no deep fat fried food and little cheese.

Keep in mind that this diet may reduce the need for insulin almost immediately. You may have to cut it in half! But how would you know this? The morning blood sugar test is essential to keep track of changing circumstances. Don't neglect it. Be careful not to use rubbing alcohol when making the finger stick (use vodka or grain alcohol). Your elderly person will feel it is all worthwhile (doing without coffee or pie) if one less insulin shot is needed or if they can go back on tablets instead of insulin. Or even just the knowledge they are staying well controlled and will never have to take insulin shots. Remember to give yourself the credit for a fine accomplishment when your loved one's diabetes improves.

Diabetic Supplements

Several supplements are especially good for diabetics:

- Fenugreek seeds, 3 capsules with each meal.
- Fresh vegetable juice made of raw green beans and carrots (½cup total).
- Bilberry leaves. Maybe they have something in them that helps detoxify wood alcohol, since bilberry leaves are good for eyes, too. Get in capsules or make a tea.

Diabetic Eating Out

Since the rules are always somewhat relaxed when “eating out” a diabetic loved one will badger you to go out with them. If rules are sure to be broken, calculate it into the rest of the day so you can compensate for it.

Extra Diet Tips For The Elderly

Food should taste good.

Eating is a fundamental pleasure of living. In old age there is no other pleasure that can equal enjoyment of food. It is a time when we long for the foods of our own childhood, too. Ethnic foods often had to be given up when children were raised (switched to hot dogs and pizza) but with this diversion gone, a return to family food would be most welcome and most healthful. Ethnic foods were made from scratch. And they certainly were made at home where cleanliness and “persnickitiness” are at their finest! A speck in the batter gets noticed. Not so in a commercial mixing vat. Pots and pans are sanitized with hot water, not chemicals.

Good advice is to return to old fashioned home cooking: with its flour and butter, lard and cream, homemade pasta, olive oil and soup, coarse cereal grains and plain fruit. Gone are the fruit juices, flour mixes, crackers and sweets that fill grocery shelves. What about convenience? Old fashioned cooking took most of the day. It does take 3 or 4 hours to make a soup from scratch. But you then get 3 days off! Each day you reboil it, it is sterile again. Or freeze half of it (take the potatoes out first). It does take a whole morning to make pasta or some ethnic dish. Freeze it in plastic sealed containers so the delicate flavor isn't spoiled. Baking homemade bread is automated now. Do at least this much to get away from the mold-ridden grocery store loaves. Make your own ice cream and nut butters. They last many days and free your schedule.

Time is the great inhibitor but if you have the means or the help, the best advice, nutritionally, is a return to old-fashioned cooking and recipes. Use your new insights to improve them where you can. Don't use your mother's aluminum ware; use her enamel ware or the new glass and ceramic ware. Don't use her copper-bottomed tea kettle or gold-rimmed cups or “silver”. Use her wooden spoons, glass glasses, and plain dishes, her wooden and straw bowls and enamel pots and pans.

Salt

Should you avoid salt? No. But a good salt rule is to either cook with it or have it on the table, but not both. Use aluminum-free sea salt, and make sure the salt is sterilized by heating five minutes at 400°F in a glass pie plate to kill mold. (Sea gulls fly over the salt flats where sea salt is gathered. Their droppings provide a medium for mold.)

Fig. 38 Sea salt flats are often roosting places for sea gulls.

The best salt is a mixture of 1 part of your aluminum-free, sterilized sea salt and 1 part potassium chloride (another kind of salt, see *Sources*). Potassium ousts sodium (salt) from your body, so you can use twice as much of this kind of salt! Also, the extra potassium helps lift fatigue and has other benefits.

Always use a non-metal salt shaker with a closable lid to keep out moisture. Don't put rice in your salt because it invites mold.

Since you, the cook, know where the salt is, (mostly in soups and stews), don't serve as much of these when there is heart and kidney illness or high blood pressure. Don't put salt in cereal, cooking vegetables, or other dishes. Just leave it out! Use herbs instead. **Tip:** encapsulated herbs stay fresher and are more potent. Fenugreek and thyme are the most beneficial of the common cooking herbs. Just open a capsule and season.

Tremor

Tremor is a symptom, not a natural part of aging. The nerves controlling the hands and arms are poisoned. The nerves originate in the brain where the poison has accumulated. What is the poison? Did it happen long ago? No! It could have happened as long as two weeks ago but not longer!

Tremor is the result of ongoing poisoning! It is important to find the poison as soon as you can since the rest of the body will soon be affected, too. Search your memory for the new things that happened in the last two weeks. It is a herculean task but only gets harder each day, so keep notes as you ask: Is there new carpeting? Is there a new furnace? Is there a different water supply? Is there a new hair dresser? Did somebody bring a vase of fresh flowers? Is there a new laundry person? Was the place sprayed for insects? Is there a new medicine (drug) or supplement? Was remodeling done? Is there a new food?

The list is endless and the situation looks hopeless because so many new things can happen in two weeks.

Rather than asking individual questions like these, let's ask only **five general questions** and have the assurance that one of them will catch the culprit.

1. Is it in the **air**? This will catch insecticide, flowers, carpets all together.
2. Is it in the **water**?
3. Is it in the **medicines** or **supplements**?
4. Is it in the **clothing**?
5. Is it in the **food** or on the dishes?

To answer each question, test the item using your Syncrometer searching technique. Make a test substance. Then search a saliva sample for it.

To test the air, take a dust sample off the kitchen counter or table (this gives you fresh dust). Pick up the dust with a few wipes by a small, two inch square of damp paper towel. Place in a resealable baggy.

To test the water, make samples by putting about a tsp. of hot, cold, or filtered water into a resealable baggy with a bit of paper towel in it. Try to get the first morning water before it has run.

To test the medicines and supplements put one of each in resealable baggies.

To test clothing (laundry) use a bit of it, (such as a sock) rolled up tightly.

Testing food is the biggest job. If there are leftovers in the refrigerator or freezer, this helps. You can combine all the leftovers in a single baggy. Frozen things don't need to be thawed for testing. Still, the chance of missing a food culprit is quite high. Be sure to test everything eaten in a two week time period: unusual things like popcorn, candy, crackers, cookies, health foods and special powders. A consolation is that you will find a number of bad foods that are not necessarily the tremor causes but which cause other health problems.

Tremor Remedies

1. Let us imagine that the air (dust) sample proves toxic (resonates with the saliva sample). What is it in the air that is toxic? These are the biggest suspects:

- CFCs (from leaking refrigerant, check refrigerator and air conditioner by removing them from the house and retesting the dust after three days, or simply buy a non-CFC variety)
- vanadium (from leaking house gas from a fuel line—repair)
- arsenic from pesticide (switch to boric acid)
- solvent from a lamp or can of lighter fuel (take them out of the house)

- chlorine from water (use carbon filters; remove bleach bottles)
- asbestos (clothes dryer belt)
- paint thinner, carpet cleaner (remove from house)
- fiberglass from bare insulation somewhere (fix holes in ceiling or wall)
- formaldehyde (new foam bedding, new fabric or clothing)

2. Suppose the water proves toxic (appears in your white blood cells); search for lead, copper, and cadmium. Although municipal water tests occasionally detect small amounts of propyl alcohol, benzene, or wood alcohol, I have never detected them—you need not search for them.

3. If the medicines are toxic just change brands. Your pharmacist can help you find a replacement brand. Find which ones are toxic and stop using them. (Don't use up any of the polluted pills or supplements.) They do more harm than good.

4. If the clothing or dishes are toxic (appear in the saliva), suspect

- cobalt
- PCB
- aluminum

Stop all detergent use. Use borax, or washing soda, or use paper plates and plastic cups (not styrofoam).

5. If the food is toxic, suspect

- food molds
- aluminum
- bacteria

Don't eat that food any more.

6. Any bacterium or toxin that invades certain brain centers can cause tremor. The most common culprits are *Shigella*, mercury, thallium and arsenic. Try to identify these for your sake as well as your loved one.

The *Salmonellas* and *Shigellas* will have come from some food. Be sure all dairy foods, including butter and whipping cream, are sterilized. Parasites come from meats. Be sure no undercooked or fast food meats are eaten. Kill all bacteria, viruses and parasites with a zapper. Sterilize fingernails with grain alcohol to prevent reinfection. Use Lugol's (see *Recipes*) and the Bowel Program (page 546) to clear them up.

Bacteria, coming from teeth and jaw (bone infections, called *cavitations*) may not seem as recent as two weeks. Indeed, they may have been there for ten years. But something recent may have aggravated them, so they now can enter more easily into the blood and brain. You may never find out what caused this. It is wisest to check this possibility with a dentist before doing weeks of other testing. See a dentist who can find and clean cavitations. Do dental repair according to the principles described in the dental section.

Going after a tremor problem in this logical way always finds the cause of tremor

whether its a simple short attack or a situation of long standing tremor with head shaking and drooling. If your situation is extra difficult, you will at least improve it and stop its progression. **This includes Parkinson's cases.**

In cases of Parkinson's disease I often find the bacterium *Clostridium tetani*, well known for causing stiffness. It hides under tooth fillings, too.

Remember, there is a consolation for doing all this work. When you find the culprit, you not only will be stopping the tremor, you will be improving a lot of other conditions along the way. Conditions like hesitant speech, shuffling walk, getting up stiffly and slowly from a chair. These are extra dividends for your loved one. And you have learned which things to avoid for yourself too.

One more thing, don't take no for an answer.

If the problem is a drug, don't accept "No, it can't be changed." Everything can be changed. Go to higher levels of authority. Doctors are very understanding and sympathetic with your intent. If the problem is leaking house gas, don't accept "We can't find a leak," implying there is none. Go to a building contractor or the Health Department. Their equipment is better. If you get nowhere, change to electric utilities. If the problem is auto exhaust, don't accept "But we have to use the kitchen door to the garage, because it's cold outside." Conveniences vs. tremor is no contest. Everyone benefits by excluding auto fumes from the house. Lock the door and cover it with plastic. By the time you have identified the culprits (probably 20 hours of work) surely you have won the right to make changes.

Often others are not impressed. Even when the tremor lessens and the elderly person plainly states they feel better, family members may disregard your recommendations. **Get tough!** It's your loved one. You have something at stake too. Be sympathetic with negative responses. But very firm. Make their choices clear:

- Either the inside door to the garage gets sealed off or the cars and lawn mower get parked outside and anything containing gasoline or solvents gets put in a detached shed.
- Either the girls use their hair dryers in their bedrooms with the door closed or you'll get them all new ones that don't contain asbestos.
- Either the clothes dryer gets a new belt or it is taped securely shut and the laundry is dried on the line or taken to a Laundromat.
- Either the plumbing gets changed (to plastic) or each faucet in the house gets a filter. (If your plumbing is corrod-

ing, not even filters are a good idea—you would have to change them every week!)

Weakness

should not be taken for granted in the elderly. Especially if they themselves complain about it. It isn't normal for them. Sometimes they will describe “spells” of weakness. This is an important clue. Check the pulse immediately. Count for 30 beats at least. Are there missing beats? There should not be! Missing two beats in a row certainly can produce a weak or “sinking” spell. The brain and body need every pulse of blood sent out right on time.

Check into caffeine use first. Take it all away. Caffeine speeds up the heart; then the overworked heart has to “take time out” for itself by missing a beat. Don't switch to decafs because this introduces solvents and new problems. If no other natural beverages appeal, serve hot water with cream and cinnamon. After stopping caffeine use ask: Is the pulse too slow or too fast? The pulse should be between 60 and 80 beats per minute.

If it is lower than 60, a medicine may be at fault. Ask the clinical doctor about it immediately. A slow pulse could certainly bring about weakness. A young athlete may have a slow pulse legitimately, due to having a very strong efficient heart, but your elderly person does not fit this category. The cause must be found.

If the pulse is quite high, over 100 perhaps, this will wear the heart out much sooner than necessary. Ask why it is beating so fast? A probable answer is that it is so weak that it has to beat faster to keep up with its job of circulating the blood. What is making the heart so weak?

Heart Disease

When the heart is enlarged, the valves don't quite close where they should, making the work harder for it and weakening it. It may be called "congestive heart failure." Why is it enlarged? Possibly because it is so weak! Yes, it becomes a vicious cycle, getting worse and worse. But you can break into this cycle and get it all reversed again. The real culprit is parasite invaders and toxic pollutants.

The most common parasite heart invaders are *Dirofilaria*, heartworm "of dogs" and *Loa loa*, another small filaria worm. At one stage these worms are so tiny that they can slide through the smallest blood vessels. They are very contagious. Even persons who don't live with a house dog can pick up heartworm. *Loa loa* is thought to be a tropical parasite but it is alive and thriving in the USA! The source of *Loa loa* seems to be tapeworm stages; this is not a certainty.

Both heartworm and *Loa loa* are very easy to kill with a zapper and both are very easy to pick up again. Treat your elderly person twice a week if there is any heart problem. It makes no difference that the house dog is getting monthly preventive treatments for heartworm. They pick it up daily and have thirty days to develop it and give it to others between treatments. Killing the dog's parasites twice a week with a zapper would be very helpful to you. These heart parasites may not cause any pains, yet disturb the rhythm or the pulse of the heart and cause it to enlarge.

Staphylococcus aureus is a bacterium hiding out in far away places like pockets left under teeth when they were extracted or along root canals. Make sure extractions heal and don't leave permanent cavitations where bacteria can live. Ask a dentist familiar with cavitations to do a mouth search. Once the mouth source is cleaned up, the bacteria do not come back to the heart (after one last zapping). If they do, go back to the dentist!

Killing these three invaders (heartworm, *Loa loa, Staphylococcus aureus*) should cure an irregular heart beat immediately (within a day).

If the elderly person is on a heart-slowing drug, check the pulse twice a day after zapping to make sure it doesn't drop too low. They may need to be off their heart medicine. Nobody will notice the relief of going off this medicine as much as you. The sunshine breaks out! Your loved one can smile again at little things! Even interest in sex returns so watch out! Life is normalized when drugs, especially beta blockers are gone. (Other heart medicines, such as Digitoxin,^{TM} don't have this depressive effect. They are used to make the heart beat stronger, not to affect the rate of beating.)

The pulse should be around 70 beats per minute and perfectly regular.

If it isn't, there is still something wrong. Get rid of toxic body products and house pollutants. Test your air for gas leaks frequently. Gas heat, gas stoves and gas water heaters are notoriously leaky. Weather changes, namely temperature changes make pipes expand or shrink—leaving cracks! The gas is toxic and a small amount can't be smelled. What a predicament! Delivering poisonous house gas to our homes in pipes that are not fail-safe is an archaic practice. Especially when the blood test shows a high “total CO_2" level, near the upper limit, search for an air pollutant like house gas or auto fumes. And read the sections in this book on pulse (page 289) and brain problems (page 278) very closely for more things to check.

With the heart regular again, it will be much stronger, too, since it doesn't have to work against itself. This strength is necessary to push the blood into the farthest “corners” of the body, especially the hands and feet, and warm them up! If your loved one constantly has cold hands or feet, try to improve circulation. Dissolve phosphate crystals with the kidney herb recipe. Give niacin (page 279). Give cayenne capsules (one with each meal). Blood thinning drugs to improve circulation are dangerous—use only if the doctor insists. Monitor blood clotting time if your loved one is on a thinner.

Heart/Kidney Relationship

A strong heart is necessary, too, to push the blood through the kidneys. Often a kidney problem is linked to the heart disorder. Kidneys are made of tubes that get finer and finer. It takes pressure, namely strength, to push the blood through them so wastes and extra water can be let down the kidney tube. Think of the kidneys as a colander full of tiny holes of various sizes that let certain things through them but not bigger things. These holes are constantly being adjusted by the adrenals which sit right on top of the kidneys and "supervise".

If the elderly person is not producing four cups of urine in a day (24 hours), it is not enough. The body cannot get enough cleansing action from less than four cups. More liquid must be consumed. If most of the urine is passed in the night this reflects on unhealthy kidneys. Use the kidney herb recipe—but only half a dose (so it will take six weeks instead of three to see good effects). As the tiny "colander" holes open up there is freer flow and many more trips to the bathroom result. The urine loses its awful odor (no ammonia, acetone and bacteria!) and gets a clear look that shows no sediment. Now that water and wastes (urea and uric acid and other acids) can leave the body quickly through more holes, it takes less pressure from the heart to get blood pushed through the kidneys. This brings relief to the heart because its work is easier. The heart and kidneys work together. Like horse and wagon the heart provides the power and the kidneys follow.

This is why heart medicine and diuretics are commonly given together. *Diuresis* (urine flow) helps the heart and a stronger heart helps the kidneys. Similarly, they fail together. In the old days this was called *dropsy*. Urine that should have left the body is backed up in the tissues. Sometimes it shows up in pockets that hang like giant oranges from the skin.

Even (especially) when the strongest diuretics (Maxzide™, Lasix™) fail to work, even when coupled with strong heart medicine (Digitoxin™), the kidney herb recipe can bail you out of the emergency.

The secret is in the varied actions of different herbs. This makes them work together. Be very careful to keep the herb tea sterile by reheating every fourth day. Freeze unused larger amounts. If too much is drunk at once, especially on the first day, a stomach ache can develop and a pressure felt in the bladder that is most uncomfortable. Go extra slow on the first few days, even though you find it quite tasty, so there is no discomfort (only lots of bathroom visits).

Diuretics

As soon as urine is flowing better, blood pressure may drop. Keep track of this twice a day with a modern electronic finger device (not an arm cuff that itself can break blood vessels). Cut down on drug diuretics gradually, using only ¾dose the first day, then ½dose, then ¼ dose. The amount of urine produced or the weight of the person can be used to assess how effective your method is. **Your goal is to not need any drug diuretics.** Again, mood will improve dramatically when diuretic drugs are removed for your loved one. The sense of humor comes back:

be prepared for some new jokes and new laughter. Give yourself good grades for this accomplishment.

Don't throw out the drug diuretics. After being off them for a while, they become more potent again. So if an emergency (sudden edema) should arise they could again be useful.

With a parasite and pollution-free heart and a low-resistance, freely flowing kidney, some reserve strength will soon be built up. Weak spells are gone and forgotten. Your loved one is walking better, needing less sleep, and a “golden age” finally arrives. It is free of pain, free of medicine, free of shots and doctor visits, free of dementia, free of the dreadful weakness that demands so much help. They are free to enjoy family and friends again. Seeing themselves gain strength and be able to do more for themselves gives the elderly a sense of pride.

Give them the credit for improving their health. When they balk at having to take herbs or vegetable juice, remind them of the days they were on a handful of pills and still had heart failure, pain and kidney disease.

Feeling Comfortable

If all this improvement doesn't warm up their feet or hands (feel them yourself) put extra socks on. Warming up their feet might have the effect of warming up hands, too. But if it doesn't, raise the room temperature.

Being forced to feel cold is an undeserved misery of the aged.

Others must accommodate to the elderly's need for body warmth. The thermometer does not tell all. Comfort is paramount for each of us. Younger persons can undress for comfort. The elderly can't make changes for themselves. Usually, by the time they are complaining of cold, they have suffered a long time, feeling too guilty to request a temperature hike. Ask your loved one. They will appreciate it. A shawl, a lap-blanket, woolen sweater, long underwear and fleecy thermal outerwear help a lot. But if your hand still senses cold feet, the thermostat must still go higher. Cold body temperature is an invitation for fungus and viruses to multiply. Viruses escape into the body daily. Don't give them the advantage.


Do you find it warm in here?
That's OK, Mom, I don't mind.

Fig. 39 Too hot and too cold.

But unless all these things are tried, don't raise the temperature. It is much healthier to be warmly dressed and breathe cool air than to be lightly dressed in an 80°F room. The heart, especially, benefits by the cooler air temperature.

For this reason, it is important to have air conditioning during the hot season. Keep your elderly person warmly dressed, away from air conditioner or fan drafts, but keep it cool. As cool as their body temperature and comfort will allow. Don't seat an elderly person under a fan in restaurants. The blowing air not only chills them, but brings filth in dust that blows in the air currents. Bacteria and viruses are soon to follow.

Being comfortable, knowing you are there to care for them, brings out the best in your elderly person. They might get well enough to long for a genuine relationship again. And put you to the test. The test of listening. This can be very rewarding if they are still able to communicate and distill their life experience into wisdom for you. If you can listen and be interested in their distillations or their ramblings their longing for relationship will be fulfilled. There's just one catch, if the new found interest in communication can't be expressed. If they haven't communicated much for a long time, it would be easy for you to miss a simple fact. They can't hear!

Hearing Loss

The hearing deficit in an elderly person is always much greater than they or you realize. Try to understand these communications:

What you (caregiver) say	What the elderly person hears	What they think	What they respond
“Look at the sunshine, isn't it a nice day?”	“Look at something, isn't it a nice bay?”	What a stupid sentence. But she wants an answer. So here goes,	“MmmHmmm” (Meaning, “yes.”)
“We'll have such a nice walk.”	“Have a…rock.”	Rock what? I'm not in a rocking char. I better not say anything.	
“What kind of soup should I make?”	“What kind of hoop should I make?”	I haven't used a hoop for embroidery for a long time. Why is she digging that up. I better say I don't know.	“I don't know.”

Don't let this ruin your relationship. It takes the fun out of their life as much as yours. **Get hearing aids**.

Don't ask your loved one if they need a hearing aid. The answer may be "I'm not deaf." You can go about it more persuasively. Every time you talk, come quite near to the person's ear and speak loudly. They can see that you must come near. If they are fighting against the whole business, they will say things like, "You don't have to shout. I can hear you." (It's what you're saying that's wrong!)

Arrange for a hearing test. It is free. That will appeal. The results of a hearing test, as it is told by a salesperson, is much more persuasive than you can be. Let the salesperson use his or her special talents to sell your loved one on hearing aids. But you make the choice on quality. Both you and your elderly person deserve the best tone quality that is made. Plus a regular cleaning service. Most companies do offer this but don't tell the customer because of the dreadful amount of time it would take if everybody took advantage of it. You take advantage of it. Clogged hearing aids are the most troublesome feature of any of them—and never mentioned! Make it a rule to buy your batteries at the same hearing aid office where they are cleaned free of charge. This repays them and serves the elderly best. Hearing loss is too subtle to leave to chance; have the hearing aids cleaned each time you buy fresh batteries (about three months). Take your loved one to a nurse for ear cleaning every six months after hearing aids are begun. Wax and debris accumulate behind the aid because the channel is stopped up.

With hearing aids that hear, and kidneys that flush and a heart that beats strongly, your elderly person may choose to attend concerts again, go to church or gatherings—and leave you out of the picture. Give yourself good grades for this achievement. Get them incontinence pants, get regular taxi service. **Do whatever it takes to get your loved one out into the world again!**

If the excitement of a night out keeps him or her from sleeping use **ornithine** and **valerian** capsules. They are good for the health anyway. Hot milk and a piece of cake (homemade, never chocolate) may do as much.

But if insomnia is the rule, not the exception, you need to go after it as a special problem.

Insomnia

is always associated with high levels of parasites and bacteria. This leads me to believe it is their waste products, namely ammonia, that really causes insomnia. Read the section on Insomnia under Sleep Problems for more on this (page 243).

A sound sleep refreshes as nothing else can. Your elderly person will have more energy throughout the day and a better mood if sleep was good.

Of course you must guard against daytime napping if nights are sleepless. Sleep at night is more important than sleep by day. They are not equal. Try to turn your loved one's cycle back to night-time sleeping if it has become turned around by bad kidney function (frequent urination at night) or too much daytime napping. Sleep can be disturbed by taking vitamins at bedtime too. Sleep is enhanced by taking magnesium. Limit bedtime supplements to magnesium, ornithine, valerian (6 capsules) taken with hot milk.

Healthful Habits

If your loved one had his or her way, they would drive the car forever, wear the same cosmetics forever, smoke or chew tobacco forever and eat their favorite dessert forever.

But if you are the caretaker, you know that some things must stop. You also know that gentle persuasion is useless; it merely erodes your relationship. Here are a few tips.

1. Ask your loved one to ask their doctor (clinical doctor or trusted medical advisor) the following question: “Would it be better for my lungs to stop smoking?” Be present so the question does not turn into “Will smoking a few cigarettes once in a while kill me?” Hearing it from the doctor is what's needed.
2. Don't ever purchase something you believe is detrimental to your elderly person. Whether it's coffee, cigarettes, beer or lipstick, say “That is something I can't buy for you; it's against my principles.” Don't be surprised if you cave in a few times to some super ruse they use on you. But the next time, have your answer ready.
3. Let your family and other caretakers know you are no longer supplying these items (the car keys, the wine bottle, the codeine-containing pain pills). Try to get cooperation. Discussing it with your loved one may do more harm than good. If they start the discussion, you end it. This is not a task for the timid! After it's done, you'll wonder what was so difficult.
4. Don't buy a wheelchair if your loved one can still walk with your help. Stay with a cane as long as possible. Then the walker. Stay with a walker as long as possible. Then your personal help. Once a wheelchair has been accepted, the last bit of exercise, walking, is lost. Fight against it. Hide it in a far away closet.

Aging is necessary but chronic illness and pain are not.

If you have managed to free your loved one from having to take pills or from certain disabilities that would soon require pills, you can give yourself great credit. Perhaps you, too, will find the needed natural help when you are aged and have lost your authority and your way mentally. Our lives are all foreshortened, much like the life of a domestic steer's. Does a captive animal learn from seeing its companion disappear? It does nothing to escape its fate. Should we accept our fate with the same docility? None of us can remember how things were in precivilized times. We are eager to believe the present is the best time that has ever been. The steer, too, has its feed provided, its water provided, its shelter for the night provided, seemingly the best time it ever had. Perhaps the price we pay for civilization, like the steer's price, is simply too high. There must be other ways. As a society, we should search for our lost longevity.

Not Old Yet

For persons merely over 40 and not ill a most important rule is: **don't overdo**.

It's easy to injure tendons and muscles by pulling or stretching them too far. Don't try, with almighty determination to open a jar. Leave it for stronger hands. Don't try to stretch a gigantic stretch to reach something on a high shelf. Wait for someone taller to come along and reach it down for you. Don't do exercises, that have left you with strains in the past. Do different exercises. Don't do new exercises, with a determined approach; start moderately; stay moderate. If you start a new job that uses a foot, leg, hand or wrist a lot, more than it was used before, even though it's in ordinary use, it can feel injured. These stresses and strains invite bacteria toward themselves. Bacteria from the liver or your own intestines find these strained tissues immediately and intensify the pain. Kill the bacteria with a zapper, cleanse the liver, and start the Bowel Program if this has already happened to you.

Don't kneel on the floor to do some cleaning job. Don't sit on the floor at a gathering. Don't let your grandchildren take “rides” on you. Don't bend over as far as you can to pick something up. Let your family know you are aiming to reach 100 years in healthy condition.

Super Longevity

We should be able to live to 140 years of age. Middle age might begin at 65, old age at 90. What is the clue to long life? Surely it is keeping all your cells healthy so they can coordinate the constant tasks of nourishing themselves, removing their wastes, plus whatever job that cell was meant to do.

Since your cells divide and therefore start again at age zero, even though you are 90, why do you age at all? Only the nervous system does not divide. Is it the nerve that ages then, and decides death for each of us?

It would never do to live forever. It would clutter the planet. Are evolutionary forces at work preventing this? But we have never cluttered the planet yet. So how could evolutionary forces have “learned” to establish death to prevent overpopulation? Living to age 140 is not living forever. Wisdom comes with age. Wisdom would serve our society well. Perhaps wisdom is needed more than ever for humans to survive. Part of the human tragedy is war. Wisdom gathered from a knowledge of history, might help end wars! But history can't be gathered and understood in less than 100 years. If centenarians can't think well or express themselves, their perspectives are lost. Longevity seems a very useful trait if only it were accompanied by health!

Dying

Although it can't be avoided it can be helped. Dying alone is the most barbaric of all society's practices.

It is still like death in the forest amongst chimpanzees. Unable to feed, to run, to call for help brings pain, fear, loneliness and finally, death. When your loved one is in the mood to talk about dying, listen. Especially if it is about their own imminent death. This doesn't obligate you to carry out any of their wishes. When death approaches the important thing is simply to be there. They may not have requested this, out of a sense of guilt or masochism, or plain dementia. But it is the most primitive of needs, the same as having a loved one nearby during childbirth. It is just a presence that counts. How can you be there if you have a job or are attending a family's needs? It is a time of great frustration for you. All your hard work and successes are culminating in one grand failure!

The good news is that it need not be you who attends your loved one every minute of the last week. Pay for someone to sit—someone who is recognized. But arrange for immediate privacy when you return. No matter how much your loved one admonishes you to go about your business, you will know when you share the final minute that your presence helped. The loneliness of the last coma, the last silence is unspeakable. Give yourself the reward of knowing you shared the pain, fear and silent cry for help.

Curing Cancer

Cancer is no longer the deadly disease it once was. In fact, you can clear it up in less time than it takes to get a doctor's appointment for a check up. If you notice a lump or think you might have cancer, don't rush to see a doctor first. Rush to clear it up, yourself, first. By the time your doctor's appointment arrives, you can be sure of a negative test.

Another Fluke Disease

Cancer is so easily cured because it is a parasite-caused disease. Kill the parasite and you have stopped the cancer. This does not mean you have also stopped being ill. If the cancer damaged your ovaries or prostate, you still must heal these organs. The Ca-125 or PSA test will not drop to normal unless you begin to heal them. These markers reflect the condition of the organ, not its malignant nature. Remember that killing a mosquito does not remove the lump it caused. That will take its course. It will heal beautifully if you let it. But if you scratch it mercilessly, it will take longer. Removing toxins from the affected organs lets them heal.

Fortunately for us, **cancer is not like a fire, unstoppable once it has started**. It takes only 7 minutes to zap all the parasite adults and their stages which cause your cells to multiply.

The responsible parasite is *Fasciolopsis buskii,* the **human intestinal fluke**, a flatworm. It is a human parasite although it can also parasitize other species. It normally lives quietly in the intestine. (The goal for all larger parasites is to live quietly. After all, your demise is their demise.) They were meant to pass their thousands of eggs with your bowel movement, outside, to some pond where snails live. But when the eggs hatch before they leave your body and are allowed to continue their development inside you, the setting is right for cancer to develop.

If the fluke eggs and other stages go through their development in your breast it can become breast cancer. If it is in the prostate it can become prostate cancer. And so on. Each different kind of cancer means the developmental stages of the intestinal fluke are present there. Only one more thing is needed to bring about an avalanche of reproduction, so that hundreds of little larvae turn into hundreds more in a short time: a growth factor. It makes them multiply and your cells are similarly affected. This growth factor, *ortho-phospho-tyrosine* (and possibly, also, *epidermal growth factor* and *insulin-dependent growth factor*) really begins your cancer.

Teamed With A Solvent

The good news is that this growth factor, which is essential for cancer to develop, cannot be made, without the presence of an abnormal solvent, **propyl alcohol** (or more exactly, isopropyl alcohol).

Without taking in propyl alcohol you could never get cancer. It takes two things, together, to give you cancer: propyl alcohol and the human intestinal fluke parasite.

Since it takes a frequency generator (3 minutes at each of 434, 432, 427, 425, 423, 421 KHz) or zapper mere minutes to kill the fluke and its stages you will be stopping the production of growth factors immediately.

Zap yourself every day for three seven minute periods, until after you are completely well.

After killing the flukes, those growth factors already formed will disappear in one hour. Your malignancy is stopped. It cannot return unless you infect yourself with the parasite again!

Getting rid of propyl alcohol is also a simple task. Once you have stopped using it, the last remnants leave your body within three days.

We must marvel at the body's wisdom and capabilities for restoring health. You are not permanently damaged by this large and hungry parasite. Given half a chance your body will throw the rascals out and restore order in your tissues.

Read the list of foods and products that are polluted with propyl alcohol. It is not, of course, usually on the label. If it is used as an ingredient, it is on the label, easy for you to avoid. It is the pollutants not appearing on the label that pose sinister hazards.

All the store bought shampoo I tested had propyl alcohol. Health brands were no exception

INFUSIUM23
INFUSIUM23

CRYSTAL GEYSER

All bottled water is polluted with antiseptics from the bottling procedure. This is a main source of propyl alcohol.

Cosmetics are laced with propyl alcohol. Use the recipes in this book to make your own.



Fig. 40 Products with propyl alcohol.

Propyl Alcohol Polluted Products

THROW THESE OUT

even if propyl alcohol is not listed on the label!

- **shampoo**, even health brands
- **hair spray** and **mousse**
- **cold cereals**, even "natural" granolas
- **cosmetics** (make your own)
- **mouthwash**
- **decaffeinated coffee**, Postum^{TM}, herb tea blends (single herb teas are OK)
- **vitamins, minerals and supplements** (unless you test them)
- **bottled water**, distilled water, or spring water
- **rubbing alcohol**
- **white sugar** (brown is OK if detoxified)
- all **shaving supplies** including aftershave
- **carbonated beverages**
- store-bought **fruit juice**, including health food brands

Tear out this page, put it on your refrigerator, and make a copy to stick on your medicine cabinet. Remember propyl alcohol is also called propanol, isopropanol, isopropyl alcohol and rubbing alcohol. You won't drop dead from getting propyl alcohol, but your cancer will flare up with each small addition.

Avoid the entire list, meticulously. Even using one of these, **like your favorite shampoo or bottled water**, will result in failure. Your body will continue to make *human chorionic gonadotropin* (hCG) and the pathology will remain "indeterminate"—not cancerous but not well, either. If you have learned the new bioelectronic technology described in this book, you can test all your foods and products for isopropyl alcohol.

When you find a beverage that is free of propyl alcohol, it may have other pollutants. Xylene and toluene invite parasites to the brain. Wood alcohol invites them to eyes and pancreas. The diseases caused by these are not as frightening, perhaps, as cancer, but entirely avoidable. For this reason, I suggest in this book that you go back (actually "forward") to self made products, unprocessed food and a limited number of tested supplements.

Getting Well After Cancer

The ravages of cancer must be healed once the malignancy has been stopped. This is where *carcinogens* play a role. The lung lesions will not heal unless cigarette smoking, freon, asbestos, and fiberglass exposure is stopped. Carcinogens were thought to be the cause of cancer. Actually, they drew the cancer to the organ. Nickel draws cancer to the prostate. Barium found in lipstick draws cancer to the breast. And so on.

The following toxins can be present in any organ! I consider these to be our most serious threat. Starting with the worst, they are:

1. **Freon** (same as **CFCs** or refrigerant). I have not found a single person to be entirely free of it, including persons without cancer or disease. But in cancer sufferers it is always concentrated in the cancerous organ, and facilitates the accumulation of other toxins. This makes your refrig-

erator, if it leaks even microscopically, the top cancer hazard in the country!

2. **Copper** from water pipes. All cancer sufferers have an accumulation in the cancerous tissue. This makes plumbing the second greatest hazard.
3. **Fiberglass** or **asbestos** is present in about 25% of the cancer victims I see.
4. **Mercury** as in tooth fillings.
5. **Lead** from solder joints in copper plumbing. All colon cancer sufferers test positive.
6. **Formaldehyde** as in foam bedding and new clothing.
7. **Nickel** usually from dental metal. Most prostate cancer sufferers test positive.

At first, tumors are benign—what a relief to find your tumor was benign. Its true nature is still unknown, but it contains freon, other toxins, and later propyl alcohol! Since tumors are often large, many centimeters in diameter, and toxins do not occupy much space, there is much unidentified substance. These tumors can multiply and enlarge, as in fibrocystic breast disease, all without being malignant. But what a convenient place for baby stages of the fluke to hide out and multiply, safe from your immune system. After being colonized by fluke stages, the tumors become malignant. Eventually they also become infected when metastasis sets in.

All malignancies have the same two fundamental causes: intestinal flukes and propyl alcohol. Whether you have a rhabdomyosarcoma or a mesothelioma or melanoma, you can cure it quickly, never to return.

Herbal Parasite Killing Program

Flatworms, roundworms, protozoa, even bacteria and viruses are remarkably easy to kill using a combination of zapping and this herbal program. Thus it is not just for cancer, but a general treatment that can benefit almost every illness

1. **Black Walnut Hull Tincture Extra Strength** (see *Recipes,* page 543):
   Day 1: (this is the day you begin; start the same day you receive it)
   Take one drop. Put it in ½ cup of water. Sip it on an empty stomach such as before a meal.

   Day 2: Take 2 drops in ½ cup water same as above.
   Day 3: Take 3 drops in ½ cup water same as above.
   Day 4: Take 4 drops in ½ cup water same as above.
   Day 5: Take 5 drops in ½ cup water same as above.
   Day 6: Take 2 tsp., all together in ¼ cup water. Sip it, don't gulp it. Get it down within 15 minutes. (If you are over 150 pounds, take 2½ tsp. Do not take more than 3 tsp. because no additional value has been observed.)

   This dose kills any remaining stages throughout the body, including the bowel contents, a location unreachable by electric current. The alcohol in the tincture can make you slightly woozy for several minutes. Simply stay seated until you are comfortable again. You may put the tincture in *lukewarm* *water to help evaporate some of the alcohol, but do not use* *hot* *water because that may damage its parasiticide power. Then take niacinamide 500 mg to counteract the toxicity of the alcohol. You could also feel a slight nausea for a few minutes. Walk in the fresh air or* *simply rest until it passes. You may add more water or honey or a spice to make it more palatable.*

For a year: take 2 tsp. Black Walnut Hull Tincture Extra Strength every week or until your illness is but a hazy memory. This is to kill any parasite stages you pick up from your family, friends, or pets.

Family members and friends should take 2 tsp. every other week to avoid reinfecting you. They may be harboring a few parasite stages in their intestinal tract without having symptoms. But when these stages are transmitted to a cancer patient, they immediately seek out the cancerous organ again.

You may be wondering why you should wait for five days before taking the 2 tsp. dose. It is for your convenience only. You may have a sensitive stomach or be worried about toxicity or side effects. By the sixth day you will have convinced yourself there is no toxicity or side effects.

***Going faster**. In fact, if you are convinced after the first drop of the restorative powers of Black Walnut Hull Tincture Extra Strength, take the 2 tsp. dose on the very first day.*

***Going slower**. On the other hand, if you cringe at the thought of taking an herb or you are anxious about it's safety, continue the drops, increasing at your own pace, until you are ready to brave the decisive 2 tsp. dose.*

2. **Wormwood** capsules (should contain 200-300 mg of wormwood, see *Sources*):

   Day 1: Take 1 capsule before supper (with water).
   Day 2: Take 1 capsule before supper.

Day 3: Take 2 capsules before supper.
Day 4: Take 2 capsules before supper.

Continue increasing in this way to day 14, whereupon you are up to seven capsules. You take the capsules all in a single dose (you may take a few at a time until they are all gone). Then you do 2 more days of 7 capsules each. After this, you take 7 capsules once a week forever, as it states in the Maintenance Parasite Program. Try not to get interrupted before the 6th day, so you know the adult intestinal flukes are dead. After this, you may proceed more slowly if you wish. Many persons with sensitive stomachs prefer to stay longer on each dose instead of increasing according to this schedule. You may choose the pace after the sixth day.

3. **Cloves**:
   Fill size 00 capsules with fresh ground cloves; if this size is not available, use size 0 or 000. In a pinch, buy gelatin capsules and empty them or empty other vitamin capsules. You may be able to purchase fresh ground cloves that are already encapsulated; they should be about 500 mg. Grocery store ground cloves do not work! Either grind them yourself or see Sources.

   Day 1: Take one capsule 3 times a day before meals.
   Day 2: Take two capsules 3 times a day.
   Days 3, 4, 5, 6, 7, 8, 9, 10: Take three capsules 3 times a day.
   After day 10: Take 3 capsules all together once a week forever, as in the Maintenance Parasite Program.

Take **ornithine** at bedtime for insomnia. Even if you do not suffer from insomnia now, you may when you kill parasites.

Parasite Program Handy Chart

Strike out the doses as you take them.

	Black Walnut Hull Tincture Extra Strength Dose	**Wormwood Capsule Dose (200-300 mg)**	**Clove Capsule Dose (Size 0 or 00)**
Day	drops 1 time per day, like before a meal	capsules 1 time per day, on empty stomach (before meal)	capsules 3 times per day, like at mealtime
1	1	1	1, 1, 1
2	2	1	2, 2, 2
3	3	2	3, 3, 3
4	4	2	3, 3, 3
5	5	3	3, 3, 3
6	2 tsp.	3	3, 3, 3
7	Now once a week	4	3, 3, 3
8		4	3, 3, 3
9		5	3, 3, 3
10		5	3, 3, 3.
11		6	3
12		6	Now once a week
13	2 tsp.	7	
14		7	
15		7	
16		7	
17		Now once a week	
18			3

At this point you do not need to keep a strict schedule, but instead may choose any day of the week to take all the parasite program ingredients.

Continue on the Maintenance Parasite Program, indefinitely, to prevent future reinfection.

Maintenance Parasite Program

YOU ARE ALWAYS PICKING UP PARASITES! PARASITES ARE EVERYWHERE AROUND YOU! YOU GET THEM FROM OTHER PEOPLE, YOUR FAMILY, YOURSELF, YOUR HOME, YOUR PETS, UNDERCOOKED MEAT, AND UNDERCOOKED DAIRY PRODUCTS.

I believe the main source of the intestinal fluke is undercooked meat. After we are infected with it this way, we can give it to each other through blood, saliva, semen, and breast milk, which means kissing on the mouth, sex, nursing, and childbearing.

Family members nearly always have the same parasites. If one person develops cancer or HIV, the others probably have the intestinal fluke also. These diseases are caused by the same parasite. They should give themselves the same de-parasitizing program.

Do this once a week. You may take these at different times in the day or together:

1. **Black Walnut Hull Tincture Extra Strength**: 2 tsp. on an empty stomach, like before a meal.
2. **Wormwood capsules**: 7 capsules (with 200-300 mg wormwood each) at once on an empty stomach.
3. **Cloves**: 3 capsules (about 500 mg. each, or fill size 00 capsules yourself) at once on an empty stomach.
4. Take **ornithine** as needed.

	Black Walnut Hull Tincture Extra Strength Dose	**Wormwood Capsule Dose (200-300 mg)**	**Clove Capsule Dose (Size 0 or 00)**
Day	1 time per day, on empty stomach	capsules 1 time per day, on empty stomach	capsules 1 time per day, on empty stomach
1	2 tsp.	7	3
2			
3			
4			
5			
6			
7			
8	2 tsp.	7	3
9			
10			

11			
12			
13			
14			
15	2 tsp.	7	3
and so	**on...**		

The only after-effects you may feel are due to bacteria and viruses escaping from dead parasites! Be sure to zap after taking your maintenance parasite treatment. After-effects also let you know that you did indeed kill something. Try to discover how you might have picked up parasites and avoid them next time.

Pet Parasite Program

Pets have many of the same parasites that we get, including *Ascaris* (common roundworm), hookworm, *Trichinella*, *Strongyloides*, heartworm and a variety of tapeworms. Every pet living in your home should be deparasitized (cleared of parasites) and maintained on a parasite program. Monthly trips to your vet are not sufficient.

You may not need to get rid of your pet to keep yourself free of parasites. But if you are quite ill it is best to board it with a friend until you are better.

Your pet is part of your family and should be kept as sweet and clean and healthy as yourself. This is not difficult to achieve. Here is the recipe:

1. **Parsley water**: cook a big bunch of fresh parsley in a quart of water for 3 minutes. Throw away the parsley. After cooling, you may freeze most of it in several 1 cup containers. This is a month's supply. Put 1 tsp. parsley

water on the pet's food. You don't have to watch it go down. Whatever amount is eaten is satisfactory.

All dosages are based on a 10 pound (5 kilo) cat or dog. Double them for a 20 pound pet, and so forth.

Pets are so full of parasites, you must be quite careful not to deparasitize too quickly. The purpose of the parsley water is to keep the kidneys flowing well so dead parasite refuse is eliminated promptly. They get quite fond of their parsley water. Perhaps they can sense the benefit it brings them. Do this for a week before starting the Black Walnut Hull Tincture.

2. **Black Walnut Hull Tincture (regular strength):** 1 drop on the food. Don't force them to eat it. Count carefully. Treat cats only twice a week. Treat dogs daily, for instance a 30 pound dog would get 3 drops per day (but work up to it, increasing one drop per day). Do not use Extra Strength.

If your pet vomits or has diarrhea, you may expect to see worms. This is extremely infectious and hazardous. Never let a child clean up a pet mess. Begin by pouring salt and iodine[15] on the mess and letting it stand for 5 minutes before cleaning it up. Clean up outdoor messes the same way. Finally, clean your hands with diluted grain alcohol (dilute 1 part alcohol with 4 parts water) or vodka. Be careful to keep all alcohol out of sight of children; don't rely on discipline for this. Be careful not to buy isopropyl rubbing alcohol for this purpose.

Start the wormwood a week later.

---

[15] "Povidone" iodine. topical antiseptic, is available in most drug stores.

3. **Wormwood capsules:** (200-300 mg wormwood per capsule) open a capsule and put the smallest pinch possible on their dry food. Do this for a week before starting the cloves.

4. **Cloves:** put the smallest pinch possible on their dry food.

Keep all of this up as a routine so that you need not fear your pets. Also, notice how peppy and happy they become.

Go slowly so the pet can learn to eat all of it. To repeat:

- Week 1: parsley water.
- Week 2: parsley water and black walnut.
- Week 3: parsley water, black walnut, and wormwood.
- Week 4: parsley water, black walnut, wormwood, and cloves.

	Parsley Water	Black Walnut Hull Tincture Dose	Wormwood Capsule Dose	Clove Capsule Dose (Size 0 or 00)
Week	teaspoons on food	drops on food, cats twice per week, dogs daily	open capsule, put smallest pinch on food	open capsule, put smallest pinch on food
1	1 or more, based on size			
2	1 or more	1		
3	1 or more	1 or more, based on size	1	
4	1 or more	1 or more	1	1
5 and onward	1 or more	1 or more	1	1

Parasites Gone, Toxins Next

Healing is automatic when you clean up your body tissues. Killing parasites and bacterial and viral invaders is fundamental. Removing toxins which invite them into your organs is even more fundamental.

How do you know which toxins are responsible for your cancer? Unless you use a Syncrometer to test, you can not know. So learn to use a Syncrometer, it will save your life.

The only other alternative is to move to a safer environment. Go on vacation. Stay in hotels less than ten years old (so the plumbing hasn't started to corrode) but not in new construction (give the carpets time to outgas). Do not have a freon containing refrigerator in your room. Do not use the hair drier they supply. Do not let them spray your room with anything. Launder the sheets and towels yourself at a Laundromat with borax and/or washing soda. Don't hesitate to drink the municipal water. Get busy with your dental cleanup.

When you get better on vacation, let that be your inspiration to move from your home. All of the toxins come from a civilized lifestyle. Resolve to leave it behind. Select a warm climate where you can spend your time outdoors in the shade most of the day. Have no refrigerator, air conditioner, clothes dryer, hair dryer, new clothing, detergent. Check that the plumbing is relatively new and that no pesticide is being used. Make the Easy Lifestyle Improvements (page 397). Throw away non-essential health supplements (unless tested) and drugs. The risk is greater than the benefit.

Watch For Bacteria

In the later stages of cancer the tumors are more and more infected with the common bacteria *Salmonella*, *Shigella*, and *Staphylococcus aureus*. Killing parasites prepares a feast for these ubiquitous bacteria. Now, more than ever, must you stay off dairy products (except for boiled milk), do the Bowel Program, take Lugol’s. Remove *Staphs* by doing the dental cleanup (page 409). Don't delay.

Help Your Family, Too

If you had cancer, your whole family should be freed of intestinal fluke parasites to protect you! They may not be getting cancer (yet!) but your closeness puts you at risk. Kissing on the mouth could reinfect you. Request that family members zap themselves and take at least one 2 tsp. dose of Black Walnut Hull Tincture Extra Strength while living with you.

Pets, too, can be a source of cancer fluke stages (in their drool). They get propyl alcohol from their feed. Use unflavored, uncolored feed for them to minimize pollution from processing. Add 1 tbs. vitamin C powder to the top of a 5 lb. bag; it will stick to the pellets as they pour out. Zap your pet along with yourself by holding them and touching a bare spot such as nose or paw.

Never eat rare meats or fast food chicken. Parasite stages survive heat up to the boiling point. If you have taken a risk, zap yourself as soon as you get home to minimize the damage.

Cancer could be completely eliminated in the entire country if laws required testing for solvents in animal feeds and human food and products. Presently it is allowed in the United States Code of Federal Regulations (CFR) (see page 428)!

Another reason for propyl alcohol pollution (and other pollutants) in our food are the chemicals used by manufacturers to sterilize their food handling equipment.

> **21 CFR 178.1010 (4-1-94 Edition) Sanitizing solutions.**
>
> Sanitizing solutions may be safely used on food-processing equipment and utensils, and on other food-contact articles as specified in this section, within the following prescribed conditions:
>
> (a) Such sanitizing solutions are used, followed by adequate draining, before contact with food. **[Note rinsing or drying is not required!]**

> (b) The solutions consist of one of the following, to which may be added components general recognized as safe and components which are permitted by prior sanction or approval.
>
> [Now comes (1) through (43) permissible sterilizing solutions, including several with isopropyl alcohol, like:]
>
> (25) An aqueous solution containing elemental iodine (CAS Reg. No. 7553-56-2), potassium iodide (CAS Reg. No. 7681-11-0), and isopropanol (CAS Reg. No. 67-63-0). In addition to use on food processing equipment and utensils, this solution may be used on beverage containers, including milk containers and equipment and on food-contact surfaces in public eating places.
>
> [Then in paragraph (c)(19) the exact concentration of the iodine is specified. Nowhere is the concentration of the isopropanol specified. It can be as strong as desired.]

Fig. 41 U.S. regulations on sterilizing solutions.

Even if there were regulations governing removal of sanitizing solutions, the overwhelming truth is missed: that **nothing can ever be completely removed after it has been added**. Or perhaps the lawmakers didn't miss this fact. Perhaps they believed that small amounts–too small to measure with an ultraviolet spectrophotometer–could surely do no harm.

Meanwhile, protect yourself by avoiding propyl alcohol. And by observing 2 extra rules:

1. Never eat moldy foods. **2. Always take vitamin C.**

Aflatoxin

A common mold found on bread, nuts and fruit and in beer, apple cider vinegar and syrups, produces *aflatoxin*. This is what prevents you from detoxifying tiny bits of propyl alcohol that get into your body!

Buy bakery bread or bake your own. Roast nuts after washing in vitamin C water to destroy aflatoxin and then store in refrigerator. Keep moldy fruit out of the refrigerator where the spores can spread. Use only white distilled vinegar. Use honeys instead of syrups and even add vitamin C to them.

Vitamin C helps your body detoxify all the mold toxins I have tested, including aflatoxin.

Keep powdered vitamin C in a salt shaker. It belongs on the table with salt and pepper, and at the stove. Put it in everything possible, from cereal to soup to rice (1/8 tsp. is enough). Besides this take 1/8 tsp. powdered vitamin C with each meal (500 mg).

Developing cancer is a chain of events. This explains why it is a disease of aging. For ten years or more you poisoned your body with freon, fiberglass, asbestos, mercury, lead, copper, etc. You continually ate moldy food (chips, nuts, etc.) which was toxic to the liver. But the liver regenerated the pieces that died. Eventually a mold toxin prevents the liver from regenerating. Your aflatoxin-ed liver then lets propyl alcohol build up after using it. You use more and more propyl alcohol. Somewhere, over the years, you pick up the intestinal fluke in a hamburger or from a pet or person. The stage is set and cancer is inevitable.



Fig. 42 Keep both salt and vitamin C powders in closable plastic shakers.

But pull out any one of the links in this chain and cancer is impossible. **Pull them all out for a return to good health**.

So cure yourself, prevent reinfection, heal the damage and go through life without this sword hanging over you.

Over 100 consecutive case histories of cured cancer victims are the subject of another book[16] along with more detailed instructions and suggestions.

---

[16] *The Cure For All Cancers*, by the same author, New Century Press 1993.

Curing HIV/AIDS

HIV and AIDS disease are very similar to cancer. That is why cancer is so often seen with HIV/AIDS. It is caused by the same parasite but the solvent is **benzene** instead of propyl alcohol.

HIV stands for
Human Immunodeficiency Virus

AIDS stands for
Acquired Immune Deficiency Syndrome

Many researchers believe HIV causes AIDS. I observe them both caused by parasites and solvents!

When the body can no longer detoxify benzene it soon may not be able to detoxify propyl alcohol. Food mold, at the base of the propyl alcohol problem, is also at the base of the benzene problem. Zearalenone, a mycotoxin I find in popcorn, corn chips, and brown rice specifically inhibits detoxification of benzene. None of us should be eating these foods untested.

Several common mold toxins inhibit the immune system, too, specifically those white blood cells that are supposed to eat and destroy viruses. Consequently, the HIV virus cannot be checked once it is introduced in the body.

Benzene goes to the bone marrow where T-cells are made, and to the thymus where T-cells are programmed, two big blows to the immune system.

Benzene, a most unthinkable pollutant, is widespread in extremely small amounts. But when **benzopyrenes** are added, the total is entirely too much for the liver and it begins to accumulate in your thymus.



Fig. 43 Grilled food has benzopyrenes as do hot dogs and "smoke flavored" foods.

Benzopyrenes are made right in your food by direct flame-heat. Grilled food, smoked food, hot dogs and lunch meats with "smoke flavor" all have benzopyrenes—even toast has it. Food fried in a skillet does not (even if you burn it black!). As the thymus deteriorates from its benzene burden so does your immunity.

Without benzene in your body
you can't get AIDS.
Without the intestinal fluke in your body
you can't get HIV.

After killing the parasite and its stages the HIV virus will be gone in 2 hours, almost as quickly as the cancer marker, ortho-phospho-tyrosine. It is not necessary to zap the virus itself at 365 KHz.

But the AIDS is not gone. This depends on removing benzene from your body and keeping it out of your body. Keeping it out on alternate days or 5 days of the week will not suffice. It must be out consistently. Only then can your thymus and bone marrow recover.

As your thymus recovers your immunity returns. Immunity to all the diseases that lurk at very low level in our bodies. They are already in us. We have accumulated them in a lifetime. Mumps, measles, chicken pox, CMV, *Staphylococcus aureus*, *E. coli*, are all there. Until now they have been controlled–kept down–by an ever vigilant immune system. If this system fails you are an easy target for any and all of these invaders.

Method Of Treatment

As soon as you find you are HIV positive, don't panic. It was inevitable. It is also inevitable for many others with unexplainable risk factors. If you have a source of infection with the intestinal fluke and at the same time a source of benzene, HIV and AIDS are a logical result. You must stop the source of both.

Purchase or make a zapper or use somebody's frequency generator (434 KHz to 421 KHz giving 3 minutes to each KHz). Kill your flukes immediately. Take vitamin B2 immediately to help detoxify benzene (three 100 mg. tablets 3 times a day, 9 altogether). Zap daily until you feel completely well: no night sweats, no coughing, no symptoms of any kind.

Remember parasites are all around us. We pick them up daily. And your weakened immune system lets everything gain a foothold in your body. Avoiding benzene will restore your immunity. Use the benzene pollution list to guide you.

Benzene Polluted Products

THROW THESE OUT

Your health is worth more than the fortune you spent on them!

- **Flavored food**, yogurt, jello, candies, throat lozenges, store-bought cookies, cakes
- **Cooking oil** and shortening (use only olive oil, butter and lard)
- **Bottled water**, whether distilled, spring, mineral, or name brand. Bottled fruit juice.
- **Cold cereal**, including granola and health brands
- **Toothpaste**, including health brands
- **Chewing gum**
- **Ice cream** and frozen yogurt
- **Pills and capsules**. At least a third of all I test are polluted. This includes herbal extracts and prescription drugs. Test yours and switch brands until you find a safe one.
- **Vaseline products** (Noxzema™, Vick's™, Lip Therapy™), chap stick, hand cleaners
- **Vitamins** and other **health supplements**, unless tested.

- **Rice cakes**, even the plain ones
- **Personal lubricant**, including lubricated condoms
- **Baking soda and cornstarch** (see *Sources*)
- **Soaps, hand creams**, skin creams, moisturizers
- Flavored pet food, both for cats and dogs
- Bird food made into cakes



Fig. 44 Mexican made candy with no benzene.

Fig. 45 Pollutants are in unlikely places

It is impossible for me to have tested every batch of every food and product, but so many test positive you simply can not risk any of the foods and products on the list.

Learn to use the Syncrometer to do your own testing. While you are learning, observe the rules perfectly. There is no half way measure with benzene. Take an attitude of over-compliance, not "getting away" with as much as possible. Over-compliance can bring back radiant health, strength you never knew you had, a beautiful normal body again! You will be able to resume your plans for education, professional life, personal relationships, free of the sword hanging over you. You will not be infectious to anybody. Let over-compliance enthuse you.

Fig. 46 Every brand of popcorn and corn chips I tested had zearalenone contamination.

There are 2 extra rules that help eliminate benzene buildup:

1. Never eat moldy or grilled foods including popcorn, corn chips, grocery store breads, pasta, nuts, alcoholic beverages, toast, brown rice (white is OK).
2. Always take Vitamin B_2 (three 100 mg tablets three times a day) and vitamin C (1/8 tsp. with each meal).

Plan For The Future

After you are well again, you may wish to indulge in some philosophy. How did an obscure virus–a snail virus!–become a human virus? This is not so bizarre. After all, rabies virus comes to us from animals, and many encephalitis viruses come from mosquitoes. How did HIV spread so rapidly? How did a pollutant as dangerous as benzene get to be in our very food? Are other parasites getting set to spring on us? What must be done to protect ourselves and loved ones from future disasters? Would getting away from fossil fuel be a big answer? Would getting away from preoccupation with chemistry be a big answer? Would more disclosure of industrial practices be an answer? Should the government agencies responsible for food and product safety be depoliticized? Should public inspection of food manufacturing be a right? Should disclosure of foreign origins of food ingredients be mandatory? Would communicating with other cancer and AIDS survivors be useful? The computer age would make communication possible. Communication leads to answers. Answers might lead to new policies. Policies supported at the grass roots level can bring about change.

Over 50 case histories of cured HIV victims are the subject of another book[17] along with more detailed instructions and suggestions.

---

[17] *The Cure for HIV and AIDS*, by the same author, New Century Press, 1993.

Curing The Common Cold

Sometimes you can zap *Adenovirus*, the common cold virus, at 393 KHz for three minutes with a frequency generator and be rid of your cold, magically, in five minutes. But magic and luck are not really responsible for this. And most of the time the cold will reappear a few hours later.

Homeopathy, too, can immediately banish your cold symptoms. The reason is not mysterious either. But, this time, the cold reappears later in a different location. Choose the right homeopathic remedy for that, and you can chase it away again.

Tapeworm Stage or Mites

The fascinating story of how we really "catch" a cold kept me spellbound for a year. I was hot on the heels of *Adenovirus* wherever it might be in my body. Sometimes I saw it; sometimes I didn't. Sometimes I had cold symptoms; sometimes I didn't. Sometimes I could zap it; sometimes it did no good.

It is now apparent to me that *Adenovirus* isn't our (a human) virus at all! It belongs to other parasites. Parasites as varied as tapeworm stages and mites. Perhaps it belongs to many other parasites, as well. My evidence comes from a tapeworm stage, cysticercus of *Diphyllobothrium erinacea*, the mites *Sarcoptes* and *Dermatophagoides*, and our own colon bacteria, *E. coli*.

The tapeworm stage flies in the dust as eggs, you can trap these by setting out a pint jar with a little water in it. In three days' time you are likely to find its frequency near 487 KHz in your jar. You are also likely to find it on your kitchen sponge, since you wipe up dust each day. To test it, place it in a plastic bag, wet it thoroughly and search from 510 KHz downward, one KHz at a time. The various tapeworm stages emit between 510 and 440 KHz.

If you have a household pet, you will always be able to find a tapeworm stage in your sponge or in a dust sample you collect from the table or kitchen counter in the morning. Gather dust with a damp bit of paper towel, put it in a plastic bag. Then wash your hands or you may accidentally eat some.

This, of course, happens to every household member. Eating the dust off the tables, inhaling the dust, and eating off surfaces wiped by the kitchen sponge happens to everyone. And everyone “catches” colds. If you search for *Adenovirus*, though, in your dust sample, it isn't there!

Similarly, you can search for the mites in your house dust. Search near the frequencies given for them. There is a good chance you will have one that is not given, because the list is so incomplete. Name it after yourself. Compare notes with others; maybe it is common, maybe it's a rare one. Again, you will not find *Adenovirus* beeping its characteristic frequency out of your mite specimen. Why not? Possibly, it is too faint; it must multiply and create a loud chorus before you can hear it. But multiply it will, if given a chance, in you. You must, of course, first eat or inhale the dust.

Then the tape eggs hatch into the *cysticercus* stage, which promptly gets to the liver. Sometimes it gets to other organs, like the muscles, the spleen, the pancreas. Presumably the liver screened it out of the blood originally.

Soon you will zap them, wherever they are. If you are using a slide specimen of *cysticercus* you can locate it in your body. If you are only listening to its beeps, you can't. If you can do both, you may be able to see which organ allows the virus to replicate after it emerges. Maybe only the respiratory organs do; maybe they start to replicate in the organ where they emerge, such as the liver and then get to the respiratory tract. This is a fascinating avenue I have not yet explored.

Mites are inhaled or swallowed or both, just as tapeworm eggs are. They are on your kitchen sponge, and in any food or dishes that stand uncovered anywhere in the home. Never drink water from a glass that has "stood out" all day. After finding one, you will notice it beeping in you for several days. Then the beep disappears; presumably the mite is dead.

The tapeworm stage beeps may disappear in a few days, too, presumably dead. Except in cases of disease. Muscles that are diseased will take in the newcomer and allow it to survive adding to the parasites and pollutants already there! Evidently the immune power of such diseased locations is way down.

On the day that the mite stops beeping, the day it dies, *Adenovirus* appears!

Not many *Adenovirus* at first. You will need to search several times during the day to find it in your white blood cells. (And you have no symptoms, yet, either!) Is it a coincidence that *Adenovirus* appeared directly after a tapeworm stage or mite died?

You can find out by waiting until a time when you have a tapeworm stage or mite and no *Adenovirus*. Then kill your tapeworm stage or mite by zapping for seven minutes. Within minutes after that, the beeping of the tapeworm stage or mite is gone and *Adenovirus* can be heard, loud and clear at 393 KHz! And minutes later you may feel a stuffy nose, a slight congestion developing, a certain head feeling that is different. You are "catching" a cold!

Will you really get this cold? Will it become a full blown cold of the usual kind? After seeing this happen dozens of times after killing a mite or tapeworm stage I concluded that *Adenovirus* really belongs to them; the virus is scuttling its dying host like people jumping off a sinking ship into the ocean. Our bodies are the ocean for them. They too, immediately swim and search for a hospitable island. Our respiratory tract is such an island; perhaps other organs, too.

Yes, this "baby cold" will develop into a full blown cold if, but only if, you have a mold in you!

Molds and Colds

This is part two of the cold story. You may have *Adenoviruses* quietly slipping into your blood stream and tissues from a tapeworm stage or mite you inhaled, or *E. coli* bacteria that strayed into your tissues, and which is being slowly killed by your immune system. Your immune system can keep up with them quite easily provided you don't have a mold in you at the same time. The significance of the mold is that it lowers your immunity, specifically and generally.

Mold eluded, is health improved.

This has already been studied extensively for a number of food molds. There are a variety of ways that mold toxins lower immunity. Some simply kill white blood cells. Others seem to "bind and gag" them so they just can't go about eating viruses.

So with mold toxins present, *Adenovirus,* fleeing the dead tapeworm stage, mite, or *E. coli* is not gobbled up. It has time to get to its favorite organ and enter the cells there. It may get in your lungs if they're full of arsenic or formaldehyde, in your throat if it's full of mercury from your fillings, in your spinal cord if it's full of thallium. Sometimes you feel the viral attack, sometimes you don't.

When *E. coli* is the source of your *Adenovirus*, a question pops up. Why don't you have a perpetual cold, since these bacteria are always in your colon...and should be! As long as *E. coli* stays dutifully in your colon, no *Adenovirus* is seen. But as soon as any cross the colon wall to invade your body, your white blood cells pounce on them. After this, *Adenovirus* appears and again you are catching a cold. They may go to your internal organs where you don't feel them.

One place you do feel an attack is in your respiratory tract: lungs, bronchi, sinuses, nose, Eustachian tubes, inner ear, eyes or head. And the size of the attack depends on whether you recently ate moldy food.

Human food (in general, in the U.S.) is very, very moldy. We do not taste it because manufacturers have been using more and more flavorings in food. This covers up small amounts of mold or “off” flavor. Measures to reduce mold are not effective enough.

Bread is a good example. Calcium propionate is added to bread-stuff to inhibit molding. That's fine. But then the bread is encased in plastic to hold in moisture and keep it “fresh”. The moisture acts to incubate mold spores and overwhelms the inhibitor. Vinegar is used instead of calcium propionate in some breads but, again, the plastic ruins its effectiveness.

Another good mold inhibitor is lime water. This is used in making tortillas. None of the old fashioned tortillas (made with just corn, water, lime) that I tested had any mold, even without propionate added! Other tortillas made of flour and calcium propionate frequently had molds.

Fig. 47 This Mexican bread has no molds. It is made from white, unbleached flour and is not wrapped in plastic.

Bread is such a staple we must correct its mold problem immediately. The two likely sources for the mold spores are: in the flour to begin with, or just flying about the bakery and landing on the newly baked loaves. Bread flour in the grocery store is quite free of mold spores, so maybe it is the bakery that needs to change. Perhaps it is not possible to bake 24 hours a day in the same building, year after year, without bits of flour and moisture accumulating in the millions of tiny cracks and crevices that all buildings have and germinating mold. Yet bread from small neighborhood bakeries does not have mold!

Only buy fresh bread not wrapped in plastic.

As soon as you feel a cold coming, ask yourself: what did you eat recently that might have been moldy? Cold cereal, hot cereal, bread, crackers, cookies, rice, other grains, fresh fruit, store bought fruit juice, nuts, syrups, pasta, honey? This takes up a large part of any person's diet, even in a single meal. The answer is yes, no doubt you ate moldy food recently.

So you can't catch a cold directly from some sneezy companion, or *E. coli*, or tapeworm stages, or mites. You have to eat moldy food first. This lowers your immunity, allowing any *Adenovirus* to invade your weakest tissues. If that happens to be your respiratory system, you get classic symptoms. (Those same “cold” symptoms can be caused by bacteria, for which I have preliminary evidence of arriving in a similar fashion.)

As fascinating as this whole story is, the bottom line is: how can you stop a cold, in record time?

The Cure

Remember, zapping does not kill your cells. So anything hiding in them will not be harmed by the electric current either. Viruses live inside your cells while they reproduce. You can only kill the outsiders: those stuck in your cell gateways. The rest will be killed by your own cells in time. Not much time. Five or six hours at most. Your cells do it with mucous secretion, inflammation and other unknown ways. So zapping is an imperfect solution.

Using a frequency generator to electrocute *Adenovirus* (393 KHz for three minutes) is not effective either because you are not killing the mites and tapeworm stages at the same time, and the *Adenoviruses* are coming from them.

The best advice to stop a cold is to:

1. **Eat sterile food for 24 hours.** Follow the Mold Free Diet on page 365. Do not eat one questionable item.
2. Take **vitamin C** (10 grams or 2 tsp.), a **B50 complex** (2 tablets), and niacinamide (3 500 mg tablets) to help detoxify the mycotoxins already in you. See *Sources*. It will still take five or six hours for your white blood cells to recover their ability to capture viruses, for the "gag" to wear off.
3. **Zap** for seven minutes, killing all viruses, tapeworm stages and mites together. **Wait** twenty minutes to let viruses and bacteria in the dead larger parasites emerge. **Zap** a second time for seven minutes to kill those viruses and bacteria. **Wait** twenty minutes to let any viruses infecting the killed bacteria emerge. **Zap** a third time for seven minutes to kill the last viruses.
4. Now you need only wait for your tissues to decongest and stop making mucous, etc.
5. Immediately start the Bowel Program (page 546) in case yours is an *E. coli* cold. You can't, and wouldn't want to, kill all the bacteria in your bowel. Zapping kills the escapees, though, to give a bit of relief, and the Bowel Program stops the invasive *E. coli*.
6. Do additional zapping as time permits until the Bowel Program has stemmed the invasion.

In five or six hours your cold could be gone.

Of all these measures, stopping mold consumption is the most important. If you eat peanut butter now, your cold will return with a vengeance. If you eat cheese it will add *Salmonella* to your illness and you may develop a fever. Your own immune system is the most powerful cold killer, so stop handicapping it.

Test yourself for the presence of molds to see if you are accomplishing your goal. The various molds I have tested had these emitting frequencies: 77, 88, 100, 126, 133, 177, 181, 188, 232, 242, 277, 288, 295 KHz.

In about five hours, some relief will be felt. The time it takes depends on how much mold you ate. But if you stop immediately and eat only perfectly safe food, your illness will be over in the shortest time. Shorter than merely zapping.

Mold Free Diet

Stick to this for 24 hours, even if you feel better much sooner.

Before starting to cook sterilize your kitchen sponge (microwave it for three minutes), and wash hands.

Breakfast

- 1 or 2 eggs any style. The egg carton and egg exterior have *Salmonella* on them, so remove the eggs, replace the carton, wash the exterior of the eggs and then your hands again before cracking them. You don't want a *Salmonella* infection added to your cold.
- Hash brown potatoes
- Pancakes or waffles with artificial maple syrup made with brown sugar and vitamin C.
- 1 cup herb tea with vitamin C, cinnamon, or other spice.

- Water with a tsp. of vinegar and honey.

Lunch

- Soup without noodles, without rice or any grain product.
- Homemade biscuits or bakery bread with butter.
- Homemade pudding or custard, all ingredients well cooked.

Supper

- Well cooked fish or seafood (canned O.K., like sardines, salmon and tuna).
- Fresh green vegetables, in perfect condition.
- Cooked vegetables with olive oil and salt (pure, see *Sources*).
- Canned beans, any variety.
- Baked or boiled potato (don't eat skin) with olive oil and salt as described on page 310.
- Hot water with whipping cream and cinnamon.
- A perfectly unblemished banana.
- Water with lemon.

You can “mix and match” these safe foods. If you get a hefty dose of mold at the outset of your cold, the toxicity lasts quite a long time. Repeat the diet the next day and the next until you are well. In animal experiments reported by scientists, toxicity from mold usually lasted three weeks. Sometimes the real damage was only seen after three weeks! Keep up your vigilance. When you decide to take some risks, make sure vitamin C has been added to the new food and mixed with it thoroughly.



Fig. 48 Goods baked in a panaderia (Mexican style bakery) never tested positive to molds.

Prevention

What is the best way to prevent a cold? Stop eating moldy food. We were never meant to eat rotting, spoiling food. We were meant to be repelled by the bad odor, the bad appearance, the bad taste. Our parents were supposed to teach us in childhood to distinguish between good and bad food. This system no longer works. By mixing spoiled food with good food, by adding flavors and changing the food consistency, parents can't distinguish substandard foods, nor teach their children to.

We rely on government agency assurances, like beef grades, expiration dates, approved food colors and additives. And when they fail? We land in a debacle such as the present one, where large segments of society are ill with uncontrollable behavior (called crime), suffer from hormone imbalances and sexual disturbances, are sidelined by chronic fatigue and new illness. But the greatest social disaster is lowered immunity—AIDS.

We cannot individually control the destiny of our species. But we can get ourselves out of the path of the falling human tide. We can dissent. We can say **NO** to rotten moldy food.

What about exposure to a cold? Won't you catch one if you're in a roomful of coughing, sneezing people? Or you shake hands with a coughing, sneezing person? Or you drink from the same glass as a person with a cold? Or your child plays with the same toys as sick children?

Yes, you will catch the virus, but you won't get sick. If you are tracking *Adenovirus* using the electronic techniques in this book, you will see that it infects you immediately after eating coughed-on food. It stays in you about twenty minutes. Then it disappears, evidently eaten up by your white blood cells, **provided there is no mold toxin in you**. But if you do have a mold toxin in you, the virus spreads, multiplies and gives you a cold! I have only followed *Adenovirus* behavior. There are numerous other "cold bugs" left for you to track. Each illness in your family could provide you with a specimen to research.

This throws light on self infection, too. When we cough into our hands and then eat with them, we self-infect. But it only makes us sicker if we harbor molds.

Curing Symptoms

Cold symptoms alone can be cured much faster than the cold. Taking drugs proves that. Most of the drugs on the market can cure some symptoms in less than one hour. But not without a price, such as a harmful side effect.

Homeopathy can cure cold symptoms too, without side effects. There are three or four favorite homeopathic remedies for colds and eight or nine less common ones. To use them you read the symptoms listed and take the remedy with the closest match.

Homeopathic Remedy	For These Symptoms
Aconitum	early cold with fever, headache, hoarse cough
Allium	clear runny nose with burning of lips or eyes
Arsenicum	sneezing cold, frontal headache, tickling cough
Belladonna	high fever cold with flushed face, throbbing head
Kali bi	thick post nasal drip, colored discharge, sinus headache
Spongia	croupy cough

Fig. 49 Starter set of homeopathic remedies.

There are lots more remedies with fascinating symptoms to try to match with your own. Books suggest that you start with a 6X or a 12X remedy, but success is more certain with 30X. Use three remedies simultaneously. If you get total relief at some point, stop. If the cold has moved or won't budge, try another set of three after an hour. Don't take them within 15 minutes of food or anything else. Homeopathy makes very interesting reading.

Homeopaths say they stimulate the immune system specifically. My results show they do much more. They go right to the gateways of your cells and evict the tiny parasite, bacteria or virus stuck to the latch and trying to get in. Your immune system would be able to gobble them all up if they weren't gagged by the food mold you ate.

Different homeopathic remedies go to different tissues, so you can only clear one tissue at a time. If you plan on trying this for yourself, order the set of cold remedies listed above (see *Sources*). The homeopathic method would be a beautiful cold cure if it weren't for the mold intrusion.

Herbs, too, can cure symptoms rather quickly. **Elderberry tea** mixed with **peppermint** is cited in herbal textbooks and it could probably do a lot if it weren't for the mold immunosuppression. If you plan on trying these start with a set of **thyme**, **fenugreek**, **sage** (for throat). Since both herbs and homeopathic remedies work on the principle of ejection, they could eject each other. Maybe the last one to arrive takes over. This is an exciting field for you to explore.

Ultimately, the length of time your own white blood cells are bound and gagged decides how soon you are really cured of your cold. Remember taking vitamin C (10 grams or more) helps detoxify the molds. If you find a recipe that works for everybody in less than five hours, be sure to let everybody know.

True Origins Of Viruses

Your body can eliminate any virus in a short time, such as hours or days. It can even keep up with a steady stream that is coming from tapeworm stages!

Let us apply these new insights to several diseases we are familiar with. Let us speculate what could really be happening.

Epstein Barre Virus (EBV) is a mysterious disease because in spite of building up antibodies, it attacks repeatedly. I only see EBV if the person also has *Eurytrema* (pancreatic fluke) in the pancreas. When the fluke is gone, I no longer find EBV in the white blood cells. This suggests that the virus comes from the fluke. As each fluke dies and is finally removed, the body's white blood cells can catch up with the viruses and you begin to feel better again, which can be as quick as one day. But reinfection with an EBV-carrying *Eurytrema* (plus a wood alcohol containing beverage to allow the fluke to go to the pancreas) can spark the next recurrence.

Shingles is a recurrence of chicken pox. I always find *Ascaris* in persons with shingles! Unfortunately, killing the *Ascaris* does not cure shingles. *Herpes Zoster* (the shingles/chicken pox virus) is known to hide in nerve cells. Perhaps *Ascaris* facilitates it's release, or simply suppresses the immune system in a way that allows it to suddenly multiply.

Polio was once a scourge. At that time, we can theorize that a new large parasite was making its appearance. Was a new animal association taking place in the early 1900's? Life was indeed becoming more urban with horse manure on all streets. Owning a dog for a house pet was becoming an acceptable lifestyle. Could the tapeworms of these animals give us a tapeworm stage that hosts polio virus? Many polio sufferers also had migraines. These are caused by *Strongyloides*, a horse threadworm. Does *Strongyloides* host polio virus?

The **HIV** virus infects us during the time the intestinal fluke, *Fasciolopsis buskii*, is being hosted. Persons test negative to HIV shortly after the fluke and its stages are eliminated.

Coxsackie viruses give us some of our encephalitises. I never see *Coxsackie* viruses without the bacteria, *Bacteroides* *fragilis*, and I never see *Bacteroides fragilis* without *Ascaris* (a roundworm.) I conclude that one lives inside the other!

We may be deriving viruses from all the roundworms, flukes, tapeworms and bacteria that infect us! It would be a fascinating study, simply to examine each of these parasites singly, searching for their viruses with an electron microscope. They could also be searched for using immunological methods.

Fortunately, your health improvement does not need to wait on such studies. Your electronic technique can detect them in your body long before you are made ill by them. You don't need to know their hosts in order to stop hosting them yourself.

It is a time of great change for this planet as pollution spreads from pole to pole. The growth of industrial activity, mining, chemical manufacturing, the food "industry", and personal habits like smoking have spread new chemicals to every corner of the globe. The element *polonium*, which is radioactive and in tobacco smoke, is harmful to human lungs, but may not be harmful to a small lung parasite, like *Pneumocystis carnii*.

Benzene, which is a solvent and extremely harmful to humans, may not be harmful to fluke parasites living within us. Propyl alcohol facilitates the intestinal fluke but is toxic to us.

Parasites are doing abnormal things. Is this because of pollution?

The tables are gradually being turned against us in favor of our parasites and pathogens. Such large changes are called evolutionary. Is the human species doomed, or will some of us "adapt". Will some of us survive to pass on our "better" genes to a new population of cancer-resistant, AIDS-resistant, Alzheimer's-resistant, etc.-resistant humans? How many of us will die trying?

The common cold should not be so common!

Body Wisdom and Why Bad Food Tastes Good

Don't let yourself eat junk food just because your body craves something in it. Try to figure out what it is your body craves. Could it be fat? Could it be salt? Could it be starch?

Salt

If it's salt, you might also love popcorn and other salty food. This implicates the adrenal glands. Maybe they're letting too much salt (sodium chloride) leave the body through the kidneys. Maybe they're letting too much potassium chloride through, too. A diuretic pill could certainly have a similar effect.

Help the adrenal glands do their job of regulating sodium and potassium chloride by cleaning them up. Let salt-hunger be your signal to do a kidney cleanse (page 549). This will clean adrenals too. Even a slight drop in sodium and potassium chloride in the blood (body fluids) can make you too fatigued to tie your own shoelaces.

Remember, when your body craves potato chips, it craves something in the potato chips. If you let yourself eat highly salted food while you're giving the adrenals a clean up, at least add potassium chloride to your diet. Make yourself a mixture of equal parts of sodium chloride and potassium chloride. Part of salt hunger is actually potassium hunger. Let your body (your taste) decide on the amount of potassium chloride to add. Maybe one part potassium chloride to two or three parts sodium chloride is a better mixture for you. After mixing, store it in the original containers (re-label them) to prevent caking. If you put it in an ordinary salt shaker, it will cake soon. Use a shaker with a lid that closes.

Fats

Maybe you like French fries because of the fat. If you deprive yourself of the "good" normal greases that come from plant or animal sources which would ordinarily make up 25% of your calories, of course you'll crave grease. But what a bad trade it is. Now you are getting lab-made (hydrogenated) grease with a non-biological structure, and loaded with the carcinogen nickel.

So if you're body tells you that you need grease, go back to olive oil, butter, cheese (baked only), lard, avocados, nuts and nut butters (homemade only) and seeds. Humankind has been eating these natural fats long before cholesterol was vilified. The key to cholesterol control is not fat avoidance, but a liver cleanse!

Starch

If switching to natural greases doesn't satisfy your "fat-tooth", maybe its the potato in the French fries that your body craves. Plain, pure starch. Do you also love bread and pasta (more pure starch though very inferior to potatoes)? Pure starch is very easy to digest and has a large adsorptive capability for toxins. In fact, if any family member should accidentally eat something poisonous, drinking cornstarch will quickly mop it up and keep it stuck so it can't enter your tissues. (This doesn't work for all poisons.) By craving pure starches, your body could be telling you about a need to improve your digestion (liver disorders) or to eat and breathe less toxic things.

Maybe a stomach-full of baby *Ascaris* is telling you to eat only food that doesn't need a lot of acid: "just potatoes, bread and pasta, please, and skip the sauce.” *Ascaris* inhibits acid production by the stomach. This can result in an aversion to meat.

It doesn't take much acid to digest pure starch and get it on its way out of the stomach. And out of the stomach means relief: relief of the pressure on the diaphragm and liver, heartburn, that too-full feeling, and other digestive disturbances.

Sugar

Your body runs on sugar. If you are short on sugar it will turn fat into sugar. If you are short on both, it will turn your muscles into sugar. However eating more sugar doesn't cure the craving. You have to find out why you are so short, in spite of eating it.

The first thing to try is 1 mg chromium (five 200 mcg tablets, see *Sources*) per day. If you still crave sugar after a week the problem is something else. Perhaps you have pancreatic flukes upsetting your sugar regulation. Kill them and go off commercial beverages that may contain wood alcohol. Sugar regulation is very complex, but these two approaches help most of the time.

Dislikes

Respect your body's opinion when it says, “No, I don't want to eat that.” Our education about nutritive value of food may be sound but there are other facts to consider. We should take a lesson from nursing babies: when they refuse to nurse, there is something unpalatable in the mother's milk. Usually the mother has eaten onions or members of the cabbage family. The baby tries it once, and learns to reject it immediately. The baby's liver, in its wisdom, does not want the baby to eat what it can't properly digest. The mother may feel: “Now, this breast milk is good for you and drink it you must, or you shall go hungry.” Unfortunately, this works for 2-year-olds and up. They are forced to eat carrots, peas, and other vegetables; vegetables that taste terrible, (modern agriculture has ruined the flavor). They alone taste the bitterness of PIT, a cyanide-related chemical, and very difficult for the liver to metabolize. Broccoli and onions may burn the tongue with its sulfur-containing acids. Green beans, onions, garlic, eggplant, all have unique chemicals in them. If you or your child are not ready to eat them, avoid them carefully, so you don't get a surprise dose of the toxic chemical.

The more mold a child eats, inadvertently, in peanut butter, bread, potato chips, syrups, the less capable the liver is of detoxifying foods. This will certainly increase the “pickiness” of a child's appetite. If your child has too many foods on her or his personal “off list”, let this signal you to improve liver function. Stop the barrage of chemicals that comes with cold cereals, canned soup, grocery bread, instant cheese dishes, artificially flavored gelatin, canned whipped cream, fancy yogurts and cookies or chips. Move to a simpler diet, cooked cereal with honey, cinnamon and whipping cream (only 4 ingredients), milk (boiled), bakery bread, canned tuna or salmon, plain cooked or fried potatoes with butter, and slices of raw vegetables and fruit without any sauces, except honey or homemade tomato sauce, to dip into.

It is frustrating to cook “a fine meal” for the family and find everybody likes it except Ms. Picky. The good news is that she can usually think of something she would rather eat. If it's nutritious, be thankful. If it's not say No.

Adults should hide their junk food, including everything off limits to children. Don't “hide” your junk food in the refrigerator and lower level cupboards! Treat yourself as well as your child. If a food tastes bad, don't eat it. If you crave it, try to understand the message.

Outwit The Cravings

Here are some examples. Suppose you crave these items:

- **Pickles**. They supply vinegar and are often loved by persons with little acid in their stomachs or a lot of yeast (vinegar is a yeast inhibitor). Start drinking water with lemon juice or vinegar and honey.
- **Bacon**. The fat soothes the stomach and slows down digestion. Switch to butter and cream, with meals.
- **Sugar coated cereals**. Loved by persons with disturbed sugar regulation. Kill parasites, avoid wood alcohol, use chromium tablets and a lot of cinnamon.
- **Crunchy munchies**. Your jaw and teeth want some work to do. Try salads, an apple, raw sunflower seeds (beware of moldy seeds, nuts and dried fruit).
- **Ice cream**. Ice cold food stimulates the thyroid; loved by low thyroid persons. Clean up the thyroid by doing dental work and liver cleanses.
- **Caffeine**-laced beverages. Stimulate many body tissues, raise blood pressure. Loved by low energy people. Do a general body and environment cleanup. (There are people who say coffee puts them to sleep. Insomnia has better solutions than caffeine, though.)
- **Candy**. The more you eat the more you crave because chromium is being used up as you eat it and yet it is necessary to utilize more sugar. Give yourself chromium (GTF) tablets totaling 1 mg. (1,000 mcg.) a day and watch your sugar craving shrink.
- **Pretzels**. You want salt plus crunch.

- **Potato chips**. You want salt, grease, starch and crunch. No wonder they are so popular!

If your body still has its wisdom, or most of it, why can't it detect the mold in peanuts, crackers and bread for us? There is a very sound reason. Our food manufacturers have gone to great lengths to fool our native senses. Salt and sugar, roasting and flavoring, do most of it.

Your body is accustomed, natively, to interpret sugar, salt, and flavors as “good, good, good.” Of course, the mold is “bad, bad, bad.” But when you mix them, what is your body to read? The “goods” always win; manufacturers don't stop until they do. More flavorings are added. The result is that you can be eating rotten moldy food without knowing it.

Food that is predominantly concocted can't be interpreted by your body wisdom. You must use your second-best ally, your intelligence.

How would you interpret these situations, taken from real life:

- An elderly person can't stand butter, wants and enjoys margarine.
- A child prefers canned spaghetti for the real thing.
- A child wants to eat only sweets, everything else must be coaxed down.
- A young man needs “his” beer to enjoy a cook-out.
- A young man with serious mental illness drinks half a gallon of Mellow Yellow^{TM} a day.
- A child wants ketchup on everything.
- A pregnant woman puts herself on a pickled pigs feet and white bread diet.

Back To Normal

Body wisdom was not meant to substitute for parental teaching. They must both be there. But when there is conflict, trust your wisdom. Will you ever get your primitive body wisdom back and enjoy vegetables, fruit, simple styles of cooking and baking them? Yes, to a considerable extent. You'll hold your nose at all seeds and nuts and most flour (they smell so rancid). You'll back away from cookies and cakes, especially icing (they taste like you imagine shortening tastes). You'll retreat from deep fat fried foods: the dripping grease will just undo the appetite. You'll say “No thanks” to canned food and metal cutlery (you can taste the metal now). You'd have to force yourself to eat grocery bread (it's so doughy and sour smelling). Wheat germ smells terrible (rancidity). Even vitamin tablets may smell awful.

Has life been ruined, now that plain potatoes and butter taste good? Your body wisdom has returned. You are the true gourmet. It is as different as corn on the cob is from the canned variety. Perhaps you are “spoiled” now by eating un-rotten food. Accept the charge with humor and dignity—as long as you're not expected to eat any more spoiled, moldy food.

Toxic Food

Grilled food develops *benzopyrenes* in it that are very toxic. In an age of lowered immunity, it makes little sense to deliberately poison the food with benzopyrenes. Especially for children, who will be faced with new viruses and parasites in their lifetimes. Will they be able to overcome them or succumb at middle age? Only the strength of their immune system decides this.

Benzopyrenes must be detoxified using the liver's valuable benzene-detoxification system. With so many benzene-polluted items, there is hardly enough detoxification capability to get it all taken care of. NAD enzymes (the N stands for niacin) come into play too. These are essential for alcohol detoxification. If you have consumed alcohol, like a can of beer, NAD enzymes must be shared between the alcohol in the beer and the benzene in the beer. It takes longer to detoxify both the benzene and alcohol. The time delay is a time of lowered immunity and facilitates a growth spurt for parasites and pathogens.

Foods that are raised to very high temperatures, made possible with a microwave oven, produce benzopyrenes. Ordinary bread-toasters can do this too! Old fashioned toasters had a layer of metal separating the bread from the wires. Toasting bread in a frying pan or a stove top surface protects it too. But your stove grill, whether electric or flame, will produce benzopyrenes in your food unless there is a separating wall between them.

It does not matter what kind of fuel is used, the benzopyrenes develop due to lack of shielding between the food and heat source. A metal wall between them absorbs some of the heat.

Do not burn your food in a microwave oven. Since the temperature may go higher than your regular oven, you can produce benzopyrenes. Your regular oven is thermostated so that it cannot go higher than it states. Baking and browning is never done above 425°F. This is your safety feature. If anything in your microwave has turned dark brown or black or has melted plastic, throw it out!

Supplements that help your body to detoxify the benzopyrenes are:

1. Niacin or niacinamide. These are NAD-builders. Take 50 mg with each meal.
2. Vitamin B_2 (riboflavin). Take 50 mg with each meal.

For unpolluted vitamins see *Sources*.

It would be wise to teach children the habits that maximize their immune strength. Avoiding food toxins that are specifically immune-lowering is most important. Besides the benzopyrenes, certain mold toxins and solvents do this and are found in foods.

Moldy Food

Everything that's animal or vegetable can get moldy. While living things are alive, the mold attackers can be held at bay. As soon as they are dead, molding begins. First it molds; then bacterial action sets in. This is what makes things biodegradable. It is a precious phenomenon. It does away with filth—in an exquisite manner. Without mold and decay the streets of New York would still be full of horse manure from the days of the horse and buggy and our lakes too full of dead fish to swim in.

Every grain has its molds; every fruit has its molds; tea and coffee plants have their molds; as do all herbs, and vegetables. Nuts have their molds; nuts grown in the ground (peanuts) are especially moldy because the earth is so full of mold spores. But the wind carries these spores high up into trees, and even up to the stratosphere. Molds are not very choosy. They have their preference for certain plants and conditions. But the same molds can grow on many plants. This is why aflatoxin, for instance, is found not just in your cereal, bread and pasta but in nuts, maple syrup, orange juice, vinegar, wine, etc. Where is it not? It is not in dairy products or fresh fruit and vegetables, provided you wash the outside. It is not in meat, eggs, and fish. It is not in water.

Although I find aflatoxin in commercial bread, I do not find it in carefully screened wheat that has had its discolored, shriveled seeds removed before using it for making bread, cereals and noodles. It is not in baked goods bought at bakeries, left open to air. Evidently the system of wrapping baked goods in plastic keeps moisture trapped and starts the molding process. In spite of adding mold inhibitors, American bread-stuff is far inferior to Mexican baked goods in which I do not find aflatoxin!

Here is some good news for cooks: if you bake it yourself, adding a bit of vitamin C to the dough, your breads will be mold free for an extended period (and rise higher).

Aflatoxin

What is so important about molds? Some of them produce very, very toxic chemicals wherever they grow. They produce some of the most toxic chemicals known to exist. Aflatoxin is one of these. My tests show it is always present in cancer patients; in other words it has built up due to the body's inability to detoxify it in a reasonable time. A great deal of research has been done on aflatoxin. Any library would have more information.

Aflatoxin reaches the liver and simply kills portions of it. After a hefty dose the liver is weakened for a long time—possibly years. Hepatitis and cirrhosis cases always reveal aflatoxin. The liver fights hard to detoxify aflatoxin and manage its own survival. It manages for 2 to 3 weeks; then a portion of it succumbs. So the toxic effects of a dose of aflatoxin aren't even noticeable for several weeks! And without a taste or smell to guide you, how would you know to stop eating the moldy peanut butter or spaghetti? The answer is:

1. make and bake things for yourself
2. test the things you dearly love but can't make
3. treat things that are treatable for molds
4. throw the rest out of your diet

Treatments mentioned in the industrial research journals are hydrogen peroxide, strong alkali such as lime-water, metabisulfite (a common reducing agent) and high heat. I have tried heat and vitamin C, which is also a reducing agent.

Just heating a food to the boiling point does not kill the molds. Boiling for many minutes at a higher temperature or baking does kill them (but not ergot, another mold) and also destroys aflatoxin they produced and left in the food. For foods you can't heat that high, for example nuts that are already roasted, or vinegar, vitamin C comes to the rescue. I suppose it acts a lot like the bisulfite; chemically destroying the mold toxin molecules.

Eradicating Aflatoxin

Simply sprinkling vitamin C over **roasted nuts** is not effective because the molds have penetrated the surface. Rinse the nuts in water first (a lot of mold is removed in this simple way). Cover the nuts with water, add about ¼ tsp. vitamin C powder (for a pint of nuts) and mix. Let stand for 5 minutes. The water penetrates the nuts, taking the vitamin C with it and detoxifies them. Pour off the water and dry the nuts in the oven at low heat. (Don't burn them or you will make benzopyrenes.)

Rice and **pastas** can be demolded partly by cooking and partly by adding vitamin C before or after cooking. There is no need to add so much it affects the flavor. Brown rice is especially moldy.

Vinegars can simply have vitamin C added and placed in the refrigerator.

Honey can be warmed and treated the same way (¼ tsp. per pint).

Bread cannot be salvaged. Switch to bakery breads or homemade. Use it up in a few days, left in its paper bag. Or slice and place in a plastic bag in the freezer.

Since all foods have both their own and others' molds, there must be thousands of molds. Very many have been studied besides aflatoxin producers.

Zearalenone

> Zearalenone, an anabolic and uterotrophic metabolite, is frequently found in commercial cereal grains and in processed foods and feeds, and is often reported as causative agent of naturally occurring hyperestrogenism and infertility in swine, poultry and cattle.[18]

What this means is, in animals, "zear" looks likes extra estrogen to the body. Does it affect humans the same way? Are high estrogen levels a problem for us? I find nearly every breast cancer case shows a too-high estrogen level for years before the cancer is found! It starts females maturing too early, too. It could cause PMS, ovarian cysts and infertility. Not everybody gets all of these effects. And what is the effect on men and boys of eating an estrogen-like mycotoxin in their daily diet? This female hormone could have a drastic effect on the maturing process even in small amounts.

Zearalenone ("zear") and aflatoxin both have immune lowering effects. Zearalenone can induce thymic atrophy and macrophage activation.[19] If you have low immunity (low T-cells, low white blood cell count, and so forth), immediately go off moldy food suspects.

---

[18] Bottalico, A., Lerario, P., and Visconti, A., Production of Zearalenone, Trichothecenes and Moniliformin By Fusarium Species From Cereals, In Italy. From *Toxigenic Fungi, Vol 7*, edited by H. Kurata and Y. Ueno, copublished by Kodansha Ltd, Tokyo and Elsevier Science Publishers B.V., Amsterdam, 1984, page 199.

[19] Luster, M.I., Boorman, GA., Korach, K.S., Dieter, M.P., and Hong, L. 1984. Myelotoxicity toxicity resulting from exogenous estrogens evidence for bimodal mechanism of action. Int. J. Immunopharmacol. 6:287-297.

"Zear" is the mycotoxin that prevents you from detoxifying benzene. Every AIDS sufferer I see has a crippled ability to detoxify benzene; they also have zear!

The main zear sources I have found so far are popcorn, corn chips, and brown rice. But it was absent in fresh corn, canned corn, corn tortillas, and white rice, making me wonder how it gets in our processed corn products.

Sterigmatocystin

Sterigmatocystin ("sterig") is plentiful in **pasta**. Emphasize baked pasta dishes, not boiled. This raises the temperature much higher than boiling. Better yet, make your own pasta with a pasta maker. U.S. bread flour is quite free of mold; the mold in our pastas must come from using inferior quality flour. Always add vitamin C to pasta before or after cooking.

Fig. 50 All U.S. brands of pasta I tested had mold, including health food brands like the one shown here (left). No Mexican brands of pasta, like the one pictured (right), had any molds.

Ergot

A food mold that causes strange feelings and behavior is *ergot*. Although laws regulate the amount of ergot allowed in foods,[20] this is not enough protection. Ergotoxins, for example LSD, are active in extremely minute (less than a microgram, about one thousandth of a fly speck) quantities. They are not destroyed by heat and are especially toxic to children. I found traces in cereals, whole grain breads, wines, and honey. It can be detoxified by adding vitamin C but takes longer; about 10 minutes. Detoxify all your **honey** as soon as it arrives in your house. Warm it slightly and add vitamin C (1/8 tsp. per cup). Stir with wood or plastic.

Ergot toxicity could explain "Jekyll and Hyde" behavior in children, commonly attributed to "allergies". In fact, the mechanism, inability by the liver to keep up with detoxification, fits well into the "allergic" concept. If your child has undesirable behavior, try going off the moldy food suspects for three weeks (cold cereals, nuts and nut butters, store bought breads and baked goods, syrups). Substitute cooked cereals, bakery breads, potatoes, and honeys. Add vitamin C to honey, pasta and cooked cereals. Pancakes and waffles made from scratch would be O.K.

Combining alcohol with ergot is more toxic than either is alone. Alcohol seems to drive the toxin deeper into your tissues. I have found ergot and aflatoxin in beer and wine! Perhaps some of the bizarre behavior and speech of intoxication is really due to the mold-alcohol combination. By delaying alcohol detoxification, the mold could even be responsible for deaths "due to" alcoholism. It would be safer to brew your own alcoholic beverages. Start with pristine fruit. Or at least add vitamin C (1/8 tsp. per cup) to the store bought container you are consuming.

Older children and adults are quite susceptible to ergot too. If bizarre behavior shows up, such as saying mean and cruel things, expressing unusual, irrational thoughts, feeling emotionless or unreal, try the same diet changes, but put alcoholic beverages, soy sauces and other sauces, and other grain derived foods on the "off" list. Try this diet on yourself if you have a temper or crying spells or frequent colds! Ergot can make you super religious, hearing voices of command or threat. Ergot also causes seizures!

---

[20] Canada allows one ergot grain per 300 grains of #3 or #4 wheat.

Fig. 51 All cold cereals I tested were full of mold toxins (besides solvents), health food varieties were worst.

Cytochalasin B

Cytochalasin B ("cyto B") is another immune lowering fungus. I find it mostly in pasta. It stops cells from dividing. Dead portions of the liver cannot regenerate as they otherwise would after a toxic encounter!

Kojic Acid

Kojic acid is a mycotoxin that appears to be responsible for wood alcohol build up. In other words, the toxic effect prevents you from detoxifying wood alcohol. This leads to pancreas damage, invites pancreatic fluke infestation, and typically results in diabetes. I find it in potatoes; don't eat potato skins. If you are a potato lover fix your own so you can peel them and remove any gray parts. I have also found it in regular coffee.

T-2 Toxin

T-2 toxin is a mold I have found in all cases of high blood pressure and kidney disease. It is present on dried peas and beans but it can be detoxified in 5 minutes by adding vitamin C to the water they are soaked in. Remember to throw away imperfect ones, first.

Sorghum Molds

Sorghum and millet carry these. Don't buy sorghum syrup. Rinse millet in vitamin C water before cooking, or add vitamin C to the cooking water.

These mold toxins cause hemorrhaging, appetite loss, and inability to swallow. Elderly people are more easily poisoned than others; their hemorrhages show up as strokes and purple blotches on the skin.

Patulin

is the major fruit mold toxin. It is present in most common fruits if they are bruised. It is particularly hazardous since the mold that produces it can actually grow in your intestine in patches. At these locations, bowel bacteria, *E. coli* and *Shigella*, can climb through the colon wall to invade you. These bacteria are then free to spread to regions of injury and tumors.

If you have cancer or bowel disease go off fresh fruit (bananas and lemons are OK) for a few weeks. Then choose your fruit meticulously. Peel everything so you can see and avoid every bruise. Also take a 2 tsp. dose of Black Walnut Hull Tincture Extra Strength. This kills these bowel fungi. But you can reinfect with a single soft grape.

Mold Avoidance

We should be much more critical of our food.

Crackers are notoriously moldy. Never let your child eat crackers. Make crisp things in the oven from left over bakery goods. Just sprinkle with cinnamon.

Dried fruits are very moldy. Soak them in vitamin C water. Rinse and bake to dry again. Then store in the refrigerator or freezer. When fresh fruit gets overripe, don't quickly bake it or preserve it. It's too late.

Peanut butter (store bought) and other nut butters can't be detoxified by adding vitamin C due to the mixing problem, even if you stir it in thoroughly. Make your own. Making your own peanut butter is a great adventure (see *Recipes*). Mix it with home made preserves, honey, marmalade, not very homogeneously so the bright colors and individual flavors stand out in contrast. Having three or four such spreads in the refrigerator will give your children the right perspective on food—homemade is better. Store bought jams are sweeter and brighter in color but strangely low in flavor and often indistinguishable from each other. Let your children eat the polluted foods that friends and restaurants serve (but not rare-cooked meats) so they can experience the difference. Their livers are strong enough to detoxify occasional small amounts.

Tea is quite moldy if purchased in bags. Although I used to recommend single herb teas (tea mixtures have solvents), I can now only recommend single herb teas from fresh sources in bulk (see *Sources*). This also gets you away from the benzalkonium chloride and possibly other antiseptics in the bag itself. When you get them, store them in their original double plastic bag. These herbs are so fresh, you'll only need half as much to make a cup of tea. Use a bamboo strainer (non metal). Bake the strainer occasionally or put through the dishwasher to keep it sterile.

Fig. 52 Packaged herb tea is moldy and polluted with solvents. Get yours in bulk from an herb company.

It comes as a surprise that pure, genuine **maple syrup** has the deadly aflatoxin and other molds. You can often see mold yourself, as a thin scum on the surface or an opaque spot on the inside of the glass after the syrup has stood some time, even in the refrigerator. Some mold spores were in it to begin with. Others flew in. After some time they grew enough to be visible. In my testing, aflatoxin can be cleared with vitamin C but sterig and others need to be treated with a high temperature as well. Fortunately, this is easy to do with a syrup. Heat to near boiling while in the original jar with the lid removed. Keep refrigerated afterwards.



Fig. 53 Three safe flavorings.

Artificial maple flavor did not have benzene, propyl alcohol or wood alcohol, nor molds. **Turbinado sugar** had none of these contaminants either. **Brown sugar** had sorghum mold. **White sugar** had propyl alcohol pollution. You can make your own syrup, safely, with artificial flavor and turbinado sugar. Of course, you'll be missing the taste and nutritional minerals provided by the natural maple product but in a contest between nutritional value and toxicity, always choose the safe product.

The mold in our **hot cereals** can be spotted. Pick out all dark colored, shriveled bits. This represents most of it. Add honey, and salt while it's cooking—this raises the boiling temperature and detoxifies more. At the end, turn off heat and add a sprinkle of vitamin C powder. Rolled oats never showed molds in my testing, although they have their characteristic fungi, too. Don't let grains mold on your shelves simply from aging. Nothing should be more than six months old. Remember you can't see or smell molds when they begin. Molds must have a degree of moisture. As soon as you open a cereal grain, put the whole box in a plastic bag to keep moisture out. This keeps out Weevils too, so you won't have to put the box in the freezer later to kill them.

Anything that is put in the refrigerator or freezer and then taken out develops moisture inside. Store cereals in kitchen cupboards or the freezer.

No government agency can test for all of these mycotoxins in all of our foods. Production and storage methods must be better regulated so as to be fail-safe. Simply sending inspectors out to look into the bins at grain elevators is not sufficient. Crusts of mold, sometimes several feet thick, that form on top of grain bins can be simply shoveled away before the inspector arrives. The humidity and temperature of stored grain should be regulated, requiring automated controls. This would soon be cost effective, too, in terms of reduced spoilage losses and higher quality prices earned. I believe that zear, aflatoxin and ergot require special regulations. Products that are imported should be subjected to the same tests as ours. Test results should be on the label.

Getting Away From Grains

In view of the many molds that are grain-related, and because these cannot be seen or smelled in pastas, breads, cold cereals, it would be wise to steer away from grain consumption. Always choose potatoes, because it is a vegetable instead of a grain, if you have a choice. The potato appears on your plate the way it was harvested. Whereas grain was hulled, stored for quite a long time, perhaps degerminated (the bran and germ picks up



Fig. 54 Don't eat the green on the potato.

mold the fastest). Then it was mixed with assorted chemicals (fumigation, anti oxidants), each polluted in its own way, packaged again and stored again. Grains have a more tortuous history than potatoes that simply get sprayed.

The spray isn't simple, of course. Scrub it off under the tap. If potatoes weren't heavily sprayed they'd be sprouting in the stores. The spray accumulates in the eyes. Cut away all the eyes. By the time you have done this you may as well have peeled them. But no blemish, no cut, no dark spot inside may be left for you to eat. Don't buy potatoes that show a tint of green on them (the green color is due to *scopolamine*; it is toxic). Red potatoes have different chemistry that doesn't produce the green toxin, buy these often. Store potatoes out of the light, to slow down the greening process. They are still a nutritious, vitamin C-rich food—provided you don't fry them in benzene-polluted, hydrogenated grease!

Potatoes have their molds but they are nicely visible. And washing and peeling does away with them. Old literature advises that potatoes should be harvested by moonlight so the green drug isn't produced in the white varieties. With modern mechanized harvesting this should pose no problem. But perhaps this must await the age of robots.

Fig. 55 Potato harvest of the future.

Pets Teach Health Lessons

Dogs don't eat hay and cats don't eat fruit. This is not simply due to their inability to digest them. Nor to training. Their body wisdom guides them. But we can trick them into eating corn and soybeans by adding the flavors they like and thereby defeat their wisdom the same way we defeat ours. A concoction is made for them that is called “complete nutrition” and we feed this meal after meal, day after day, a most unnatural situation. The liver is deluged with the same set of pollutants time after time and never gets a rest. Humans still obey their body wisdom about varying their meals. This gives the liver a chance to catch up with detoxifying one pollutant while the new one builds up. If the liver is absolutely unable to handle something, you are informed quite quickly with an allergic reaction to the food.

Cats and dogs with their monolithic diet get no opportunity to reject food (except by vomiting or starvation). It is not surprising they are getting cancer with increasing frequency, a situation where the liver can no longer detoxify isopropyl alcohol, a common pollutant in their food.

Should we go back to the old days and make their food for them? Yes, they deserve pure food, they deserve variety. Table scraps would be much less toxic for them than their commercial feed. But what if they like and prefer their monolithic “scientific”, “complete”, polluted diet? If our food was doused with sugar for breakfast, lunch and supper, we wouldn't care much about what was under the sugar either. And we'd continue wanting sugar, sugar, sugar the way a pet might want its favorite food and nothing else. Such is the deception of flavorings.

All change should be brought about slowly and with kindness for animals and humans alike. Learn what makes a good pet diet. Cats and dogs are both meat eaters. Cook chicken in a pressure cooker to kill all parasites. Put portions in the freezer. Add table scraps, dressed with a little butter, cheese or lard.

Don't wash the pet dishes with your own—dishwashers don't reach the boiling point. Serve fresh water daily. Standing water picks up bacteria. Don't let food get more than a day old in the dishes. It picks up molds. Don't feed pets at the table, keep them outdoors during mealtime.

After your pets have stopped eating propyl alcohol polluted food and are not getting propyl alcohol in their shampoos, there is no way they can get cancer. Whatever cancer they have will clear up by this change in diet and by giving them the pet parasite program.

Now they are back to a natural state and do not host human flukes. What a relief it is not to worry about reinfection from your pets.

Easy Lifestyle Improvements

None of us likes to change a habit. But once it is changed you are back to an automatic way of doing something. By selecting wise habits your improved lifestyle pays you back for the rest of your life.

Living Hand To Mouth

Hands do everything. They pick up things from the floor. They handle money. They touch other peoples' hands. They clean up bottoms. They touch all kinds of door knobs. And then they pick up food to eat. Some people even lick their fingers when they're sticky or just to turn a page!

What is on the hands that you don't want to eat but can't see? **Bacteria** and **viruses** from coughing and sneezing into your hands! And **cysts**! Cysts are the “eggs” made by parasites. Cysts are so tough not even bleach kills them. They hide under our fingernails when we wash our hands. Then we eat them along with our food. This is called *oral-fecal route*. They hatch in the stomach and go to the intestine to live.

To stop reinfecting yourself the little cysts under the nails need to be killed. Food grade alcohol solution kills them. Buy Everclear^{TM} or Protec (potable) alcohol and make a 5% solution (add ¼ cup of 95% alcohol to a quart of water). Keep it in a small pump bottle at the sink. After using the bathroom and washing your hands, treat your fingernails with alcohol. Pump alcohol into one palm. Put the fingernails of the other hand into it. Scratch a bit. Pour it into the other palm and do the remaining fingernails. Rinse.

- **Don't** eat with your hands! Use a fork.
- **Never** eat food off the floor!
- **Always** wash hands after petting an animal!
- **Never** touch the bottoms of shoes! Keep shoes off couch or bed or chair.
- **Always** cough or sneeze into your clothing or a tissue, not your hands.
- **Keep** your fingers out of your mouth. Don't lick your fingers to turn pages or open plastic bags.

Sick persons need a 50% alcohol solution. Add ½cup 95% alcohol to ½cup cold tap water or buy plain vodka, 80 to 100 proof. Pour the vodka into the pump bottle. Be careful that nobody tries drinking it. If there are teenagers in the house, add a hefty dose of cayenne to it.

Lugol’s iodine will also sterilize your hands. However most commercial Lugol’s is polluted with isopropyl alcohol. Ask your pharmacist to make it from scratch for you (there are only two ingredients and water, see *Recipes*). Then make a solution to wash in (1 tsp. to a quart of water). This can stain some things. Do not use “tincture of iodine.”

Better Laundry Habits

Boil your underwear. In long-ago days, all sheets, towels, table cloths, and underwear were separated and boiled.

With the convenience of our electric washing machine, we tend to overlook the fact that underwear is always contaminated by fecal matter and urogenital secretions and excretions. Mixing these with socks and towels and dishcloths is all right if you are going to kill everything anyway. But if you don't kill them, as in cold water washes, you are mixing the yeast, parasite eggs, bacterial spores, and fungus from underwear with all the other clothing you and your family wear. An enlightened system would be to add an antiseptic to the wash or rinse cycle. Lime water (calcium hydroxide) or iodine based antiseptics seem obviously simple methods to accomplish this. In the absence of this protection, use dryer heat to do your sterilizing. Underwear should be dried until too hot to handle.

Bleach can kill a lot, but doesn't kill *Giardia* spores and a lot of types of fungus. Don't rely on bleaching. Besides, your skin absorbs it from clothing, it is quite toxic to you, and can cause mental effects.

Commercial detergents are polluted with PCBs and have cobalt added. Both of these are easily picked up through your skin. Use **washing soda** and **borax** in the wash cycle. They do not clean quite as well as modern detergents, but there is less static cling, eliminating the need to put more chemicals in your dryer. For spot removal use homemade bar soap.

Better Kitchen Habits

Once a day, sterilize the sponge or cloth you use to wipe up the table, counter tops and sink. This little piece of contaminated cloth is the most infectious thing in the house, besides the toilet. It's more dangerous than the toilet because you do not suspect it. Sometimes it has a slight odor at first, which may warn you, but most pathogens do not have an odor! As we wipe up droplets of milk, we give the milk bacteria, *Salmonellas* and *Shigellas*, a new home to multiply and thrive in. We add crumbs, picking up molds this way. We add dust, picking up parasite eggs and stages. They all feed on the milk and food residue.

As the counter and table and stove get wiped “clean” a film of contamination is left everywhere. A few varieties may die but most of them don't. The general moisture in the kitchen is enough for them to survive. The cloth or sponge recolonizes the kitchen and dining room table several times a day.

No doubt, the last thing you do before leaving the kitchen is squeeze it dry with your hands. Now all the pathogens are on your hands!

Where do your fingers go? To your mouth to remove a hull or bit of something from your teeth. Or to eat a last bite of something. Or to turn a page of the telephone directory. You have just eaten a culture sampling from your own kitchen sponge. In two hours they are already multiplying in the greatest culture system of all: your body! You have given yourself your next sore throat, or cold or headache. The worst possible habit is to wipe a child's face and hands with the kitchen cloth. Or to have a handy towel hanging from the refrigerator handle.

To sterilize the sponge: **drop it into a 50% solution of grain alcohol** at the end of each day. Keep a wide mouth glass quart jar handy just for this. Keep the jar tightly closed and out of the reach of children. Dunk your sponge and plop it onto the sink. If you stand it on end in the sink it will partly dry overnight.

Another way to sterilize the sponge or cloth is to **microwave it**, after wetting it, for 3 minutes. Any shorter time simply warms and cultures the pathogens and multiplies them. Or **boil the cloth** like our grandparents did. Drying out the dish cloth helps kill many–but not all–pathogens. It takes three days of drying to kill all! Another strategy is to **use a fresh cloth** or sponge each day, putting the used one to dry until laundry day.

During the day, set the sponge on end to start drying and slow down culturing.

Don't eat food directly off the counter top or table top. You wouldn't slice a tomato or egg directly on the counter top. It would pick up something: some little particle of dust or dirt. Treat bread the same way. Always on a new clean surface, such as a plate. The counter and table top have on them whatever is in the kitchen dust and on the wipe cloth. Dust is always falling! And the sponge is always culturing. Don't eat the dust!

Keep the cutting board sterile like dishes. Wash it the same way and keep it in the cupboard.

Keep food containers closed. Milk or water glasses are picking up dust as soon as you set them out. Dust is everywhere. Every step on the carpet sends up a puff of dust. Vacuuming sends up a hurricane of dust and distributes bathroom dust to the kitchen and kitchen dust to the bedrooms. So if one person has brought in a new infection, the whole family is exposed to it in hours via the dust.

It is very helpful not to eat the new infectious pathogen. Breathing it is not so damaging. Our noses collect such pathogens and we blow them out again. Touching the infected person is not very damaging either; the pathogens can't get through our skins and since we wash hands before eating we are not at great risk of infection this way. But eating the pathogen is 100% effective in infecting us. The new pathogen is in the dust. The newly contaminated dust drops into your ready and waiting glasses on the table and the open foods. Of course, there is no defense if somebody should cough or sneeze at the table.

Teach children to cough and sneeze into a suitable collecting place like a tissue, not their hands. Pathogens live bountifully on hands. Hands not only provide moisture but often food from the last meal. Hands are second only to the dish cloth in contamination level. If you must cough or sneeze and a tissue is not within reach fast enough, use your clothing! That's what clothing is for—to protect you. Cough and sneeze into your own clothing; this protects the cougher and sneezer, as well as everybody else. A sleeve is handy for children. The inside of your T-shirt for T-shirt wearers. The inside of coat for suited persons. The inside of the neck line for dresses. Of course, paper is best, but in emergency use cloth. Never, never your hands unless you are free to immediately dash into the washroom and clean the contamination off your hands.

Teach children this old rearranged verse:

If you cough or sneeze or sniff
Grab a tissue, quick-quick-quick!
And if you're sitting at the table
Do it in your sleeve if able.

Better Housekeeping

Throw out as much of the wall to wall carpeting as you can bear to part with. It is injurious to everyone's health, even though it's comforting to bare feet and looks pretty.

Carpets clean our shoes. Modern shoes, with their deep treads, bring in huge amounts of outdoor filth which settles deep down into the carpets. In spite of vacuuming every week, the filth accumulates.

Vacuum the carpets when the children, the sick and elderly are out of the house. The dust raised and distributed throughout the house isn't just dirt, it's infectious dirt. It lands on tables and counters. These get wiped with a cloth or sponge and then applied to dishes. The dust in the kitchen falls on open food and into open containers.

Clean carpets with a “steam cleaner”. When you see how much filth is in the water and realize how much dirt you were living with, you might be willing to trade in the “beauty” of carpets for the cleaner living of smooth floors. Don't add chemicals (commercial cleaning solutions) to the steam cleaning machine; these chemicals leave a residue in the carpet which dries and flies up into the air to add to the dust. Popular stain resistance treatments contain arsenic. Cobalt, which adds “lustre” to carpets, causes skin and heart disease after it has built up in your organs. Use borax instead of detergent. Use boric acid to leave a residue that kills roaches and fleas (but not ants). Add vinegar that leaves a residue to repel ants. Nothing controls fleas reliably, except getting rid of the carpets and cloth furniture (keep pets out of bedrooms). Removing all the borax is what brings luster to the carpet. Use citric acid in the rinse water for this purpose. Adding lemon peel to the rinse also adds luster and ant deterrence. Just drop the whole lemon in the tank so it can't block the hoses.

Fleas and other vermin in the carpet simply crawl below the wetness level when you wash the carpet. Spraying a grain alcohol solution with lemon peel in it (it needs to extract for a half hour) on the damp carpet will reach and kill a lot of these, together with the residual bacteria. The damp carpet lets it spread evenly and reach all the crevices.

We are trapped in our dwellings. Primitive peoples were mobile. This got them away from accumulations of filth and rubbish in their living space. Much living was done outdoors, the cleanest space of all.

Now, air conditioning has made indoor living more comfortable. But also has added new hazards. The strong currents of air blow the dust about continuously. Molds and bacteria that grow right on the air conditioning unit get blown about for all to inhale. Never, never use fiberglass as a filter or to insulate your air conditioner around the sides. It is a carcinogen. And the danger of freon escaping from a tiny leak is another major health hazard.

Forced air heating systems are undesirable, too. All dirt brought into the house by shoes gets circulated throughout the house by forced air systems of heating or cooling. Old fashioned radiant heat from radiators or a stove did not distribute the dust so effectively. A return to linoleum floor covering for kitchen and bathroom and hardwood for other rooms would be a good step of progress for a health conscious society. Mopping, instead of the vacuum cleaner, keeps dirt to a minimum. Throw rugs at doors and bedside, easy to clean, would "catch the dirt" as was the original intention. Carpets were intended to help keep filth out of the air. These smaller rugs should be laundered weekly.

Furniture should be wood, cane, or plastic, with cushions to soften the impact. These can be washed weekly if the covers are removable. Modern cloth furniture with its foam interior is a repository of filth and fumes and a constant source of infectious dust.



This old fashioned setting is more progressive than our carpeted, modern homes.

Fig. 56 Smooth floors allow every bit of dust to be removed.

Dust your furniture with a damp paper towel. You are picking up and removing highly infectious filth (*Ascaris* and pinworm eggs, pet parasites, "dander" and house mites). Instead of distributing these from room to room, throw the paper towel away after each room is done. Use plain water or vinegar water (50%), not a chemical combination which further pollutes the air.

Clean windows with vinegar water, too. Use a spray bottle.

Keep your dishes in cupboards. This keeps them free of dust. This principle is ancient. It is tempting to leave some of them out. If you must keep the juicer or dishes outside of cupboards, keep them covered or placed upside down so they don't catch dust. Even inside cupboards, store them upside down. When using the “good” dishes or glasses, that haven't been used in a while, wash them first.

Windows Open Or Closed?

In places like Chicago where you can smell the air as you approach the city, it is wiser to keep your windows shut. You can't breath the industrial “soup” all day and night and expect to stay healthy. Of course, it all enters the houses anyway. Central air conditioning and a plain carbon filter at the furnace location (see *Sources*) may be the best solution in spite of blowing dust around the house. Keep the vents to the bedrooms closed to reduce the air turbulence there but leave the cold air return open. Clean the vents in other rooms each week along with floors and carpets by pulling up the grating and reaching down the passage as far as possible.

If you believe the air is free of highway exhaust and industrial smoke open the windows every day. This will let some of the indoor toxins blow away. Asbestos, fiberglass, freon, radon and plain dust can be reduced to a minimum by keeping windows open. If you are ill, sit outdoors (on the porch) as much as you can. Escape to a suitable climate that makes this possible.

Just a few decades ago, many people had summer living quarters that were different from winter living quarters. Gone was all the accumulated infectious dust of half a year of habitation.

Fig. 57 Moving into the summer kitchen got you away from the accumulation of filth from winter!

Don't have a basement where you stockpile toxic items. Basements invite mold, mice and radon besides toxic things. Fumes travel upward where you live! Keep your toxic things in the attic. If there is no attic, store them in the utility room. Close off the ventilation between utility room and the rest of your house. If you have none of these, perhaps because you live in a senior citizen community or condominium, don't keep any toxic things stored anywhere. Don't save any leftover paints, solvents or cleaners. Buy such small quantities that you can afford to throw it all away when you are done with them.

Live on top of the earth as was intended by nature.

Never have a basement room "finished" for actual living space. Don't buy a house that has a "lower level" built into the earth. This will be the most polluted and dangerous room in your house. If you are ill, move out of such a room. There is no way that it can be “cleaned up”. Move to the other end of the house and furthest away from an attached garage door.

What Kind Of Heat

The worst is coal. The best is none. Breathing coal fumes during the beginning of the industrial age may have brought the new lung diseases: tuberculosis (TB), and pneumonia. It may also have worsened alcohol addiction (beryllium toxicity). Choose electric heat if possible. Even though electricity is based on other fuel consumption, you don't have to breathe those fumes directly.

Wood stoves can be made safe by making sure the chimney works properly. Never use a lighter fluid. Don't fill the house with smoke when stoking.

Minimize your use of fossil fuels in every way you can.

Getting Rid of Mites

We do not tolerate external parasites like bedbugs, lice, ticks, leeches. Bedbugs were once a scourge amongst northern Europeans. I remember our parents spraying for them (kerosene) in the bedroom. This only “controlled” them. What eliminated them was a law against sale of used mattresses. Lice were originally “controlled” by frequent washing, louse combs, and ironing the seams of clothing. What eliminated them was the cutting of long hair as a societal practice. But what about **mites**? They live with us and other animals.



Fig. 58 Mite.

Mites are too tiny to see, tiny enough to ride on a dust particle as if it were a magic carpet. They resemble insects. Chiggers are really mites. Mange in animals is a mite infestation. Dust mites live on our dander (scales of dead skin).

Get rid of their breeding places: beds, cloth covered chairs and soft sofas. Humans leave enough dander behind in these places to support these ultra small insects. Cover mattresses with plastic covers. Use throws on easy chairs and sofas and wash them often. Never allow a pet into the bedroom or the dust will have tapeworm eggs as well as mites. Throw out rugs that have been pet-beds. Spray the air with a mist of 50% grain alcohol before vacuuming. If you have an illness wear a mask to vacuum. Deep, soft, wall to wall carpets compromise an ancient concept: everything should be washable and cleanable, without throwing the dirt into the air for humans to inhale. Vacuuming a carpet blasts mites and tape eggs into the air. Never shake bedding or rugs where the dust will blow back into the house behind you.

Mites don't bite us but we inhale them as they float in the ever present dust in our homes. The mucus in our lungs traps them and in a few days they die, only to release a drove of *Adenoviruses* (common cold virus) in us.

Four Clean-ups

Chronic health problems are not due to exposures of the past. They are ongoing. Your body is constantly fighting to remove pollutants. In order to stay sick, you must be constantly resupplied! These four clean-ups–dental, diet, body, home–are aimed at removing parasites and pollutants at their source. Only then can your body heal.

Dental Clean-up

(This section on dentistry was contributed by Frank Jerome, DDS)

Dr. Jerome: The philosophy of dental treatment taught in America is that teeth are to be saved by whatever means available, using the strongest, most long lasting materials. Long-term toxic effects are of little concern. The attitude of the majority of dentists is: whatever the American Dental Association (ADA) says is OK, they will do.

A more reasonable philosophy is that there is no tooth worth saving if it damages your immune system. Use this as your guideline.

The reason dentists do not see toxic results is that they do not look or ask. If a patient has three mercury amalgam fillings placed in the mouth and a week later has a kidney problem, will she call the dentist—or the doctor? Will they ever tell the dentist about the kidney problem or tell the doctor about the three fillings? A connection will never be made.

It is common for patients who have had their metal fillings removed to have various symptoms go away but, again, they do not tell the dentist. The patient has to be asked! Once the patient begins to feel well they take it for granted, and don't make the connection, either. If everybody's results were instantaneous, there would be no controversy.

Find an alternative dentist. They have been leading the movement to ban mercury from dental supplies. Not only mercury, but all metal needs to be banned. If your dentist will not follow the necessary procedures, then you must find one that will. The questions to ask when you phone a new dental office are:

1. Do you place mercury fillings? (The correct answer is NO. If they do, they probably don't have enough experience in the use of non-metal composites.)
2. Do you do root canals? (The correct answer is NO. If they do, they do not understand good alternative dentistry.)
3. Do you remove amalgam tattoos? (The correct answer is YES. Tattoos are pieces of mercury left in the gum tissue.)
4. Do you treat cavitations? (The correct answer is YES. By cleaning them.) The complete name of *cavitations* is *alveolar cavitational osteopathosis*. They are holes (cavities) left in the jawbone by an incompletely extracted tooth. A properly cleaned socket which is left after an extraction will heal and fill with bone. Dentists routinely do NOT clean the socket of tissue remnants or infected bone. A dry socket (really an infected socket) is a common result. These sockets never fully heal. Thirty years after an extraction, a cavitation will still be there. It is a form of *osteomyelitis*, which means bone infection.

Ninety percent or more of dental offices will not be able to answer ANY of the above questions correctly. If you allow the work to be done by a dentist who does not understand the importance of the above list, you could end up with new problems. Find the right dentist first even if you must travel hundreds of miles. There are 6,000 to 10,000 dentists who should be able to help. Some can do part of the work and refer you to a specialist for the rest. Five hundred to one thousand of these dentists can do it all.

Normal treatment cost is about $1,000 for replacement of 6 to 8 metal fillings including the examination and X-rays. For people with a metal filling in every tooth, or for the extraction of all teeth (plus dentures), it may be up to $3,000 (or more in some places).

Remember, the simpler the treatment, the better. If the dentist says that he or she can change your metal fillings to plastic but it would be better to crown them, say "NO!"

Guidelines For A Healthy Mouth

If you have	**What to do**
Metal fillings	change to plastic fillings
Inlays and onlays	change to plastic fillings
Crowns (all types)	change to plastic crowns
Bridges	change to plastic crowns, partials
Metal partials	change to plastic partials(Flexite^{TM})
Pink dentures	change to clear plastic
Porcelain denture teeth	change to plastic denture teeth
Badly damaged teeth	become extractions
Root canals	become extractions
Braces and implants	avoid
Cavitations	need to be surgically cleaned
Temporary crowns	use plastic
Temporary fillings	use Duralon^{TM}

Fig. 59 Dental replacements.

The guidelines can be summarized as:

1. Remove all metal from the mouth.
2. Remove all infected teeth and clean cavitations.

Dr. Clark: *Removing all metal means removing all root canals, metal fillings and crowns. Take out all bridge work or partials made of metal and never put them back in. But you may feel quite attached to the gold, so ask the dentist to give you everything she or he removes. Look at the underside. You will be glad you switched.*



The top surfaces of tooth fillings are kept glossy by brushing (you swallow some of what is removed). Underneath is tarnish and foulness. Ask to see your crowns when they are removed.

Fig. 60 Tops and bottoms of some metal crowns.

The stench of the infection under some teeth may be overwhelming as they are pulled. Bad breath in the morning is due to such hidden tooth infections, not a deficiency of mouthwash!

All metal must come out, no matter how glossy it looks on the surface. Metal does not belong in your body. It is an unnatural chemical. Do this as soon as you have found a dentist able to do it. Find a dentist with experience and knowledge about this subject. It is more than replacing acknowledged culprits like mercury-amalgam fillings. This is metal-free dentistry. Only metal-free plastic should be put back in your mouth.

Dr. Jerome: If your dentist tells you that mercury and other metals will not cause any problems, you will not be able to change his or her mind. Seek treatment elsewhere!

Your dentist should do a complete X-ray examination of your mouth. Ask for the *panoramic* X-ray rather than the usual series of 14 to 16 small X-rays (called full mouth series). The panoramic X-ray shows the whole mouth including the jaws and the sinuses. This lets the dentist see impacted teeth, root fragments, bits of mercury buried in the bone and deep infections. Cavitations are visible in a panoramic X-ray that may not be seen in a full mouth series.

The cost of removing metals should be viewed in the proper light. It took years or decades to get into your present condition. When you do a lot of dental repair in a short time, it can seem to be costly. Unfortunately, many people are in a tight financial position because of the cost of years of ineffective treatment, trying to get well.

Your dentist may recommend crowning teeth to "protect" or strengthen them. Unfortunately, the very concept of crowning teeth is flawed. First, the enamel is removed from a tooth to prepare for the crown. This is permanent and serious damage! Many teeth, up to 20%, may die after being crowned and will need to be extracted. For this reason, you should only get REPLACEMENT crowns and NO NEW crowns. Your metal crowns can be changed to plastic. (Remember, no metal must be left under the crown.)

If you have many crowns, you should have them all removed as quickly as possible. But you should not spend more than two hours in the dentist's chair at any one time. That is too much stress for your body.

Dr. Clark: *Don 't accept intravenous (IV) treatments during amalgam removal. Both IV bags and the supplements used in them are polluted with propyl alcohol, benzene, and wood alcohol.*

Dr. Jerome: It is quite all right to have temporary crowns placed on all teeth that need them in the first visit. You may then go back and complete treatment over the next 6 to 12 months. It is common to find a crowned tooth to be very weak and not worth replacing the crown, particularly if you are already having a partial made and could include this tooth in it.

Dr. Clark: *We are accustomed to thinking that plastic is metal-free. This is wrong. The original dental plastic, methyl methacrylate was metal-free. But modern plastic contains metal. The metal is ground up very finely and added to the plastic in order to make it harder, give it sheen, color, etc.*

Dr. Jerome: Dentists are not commonly given information on these metals used in plastics. The information that comes with dental supplies does not list them either. Most dentists never look at a dental materials book after they graduate. The ADA, however, has a library full of such information.[21]

Dr. Clark: *There are many lanthanide (Rare Earth) metals used in dental plastic. Their effects on the body from dentalware*

---

[21] Call the American Dental Association at (800) 621-8099 (Illinois (800) 572-8309, Alaska or Hawaii (800) 621-3291). Members can ask for the Bureau of Library Services, non-members ask for Public Information.

have NOT been studied. Yet their cancer-promoting ability is known in many cases.[22] *Only metal-free plastic is safe.*

Dr. Jerome: These are the acceptable plastics; they can be procured at any dental lab.

- Plastic for dentures: Methyl Methacrylate. Available in clear and pink. Do not use pink.[23]
- Plastic for partial dentures: Flexite™ Available in clear and pink. Do not use pink.
- Plastic for fillings: Composite Materials. This is the material that has been used in front teeth for 30 years. It has been used in back teeth for 10 years. There are many brands and there are new ones being marketed constantly. The new ones are very much superior to those used 10 years ago and they will continue to improve. They do, however, contain enough barium or zirconium to make them visible on X-rays. There are no alternatives available without these metals.

Dr. Clark: *Composites with barium are not good, but I haven't seen enough barium toxicity from fillings at this time to merit advising extraction instead. Hopefully, a barium-free variety will become available soon to remove this health risk.*

Dr. Jerome: Many people (and dentists too) believe that porcelain is a good substitute for plastic. Porcelain is aluminum oxide with other metals added to get different colors (shades). The metal DOES come out of the porcelain! It has many technical drawbacks as well. Porcelain is not recommended. Sometimes the white composite fillings are called porcelain fillings but they are not. They also require more tooth structure to be removed.

---

[22] Thulium and ytterbium have been studied for their tumor-seeking ability. See page 321 in the book *METAL IONS In BIOLOGICAL SYSTEMS, Vol. 10, Carcinogenicity and Metal Ions*. Editor Helmut Sigel 1980.

[23] The pink color is from mercury or cadmium which is added to the plastic.

If you have a large bridge, it cannot be replaced with a plastic bridge because it isn't strong enough. A large bridge must be replaced with a removable partial (Flexite™).

The methods used to remove metals and infections are technical and complicated. See dental information in *Sources*.

Dr. Clark: *I'd like to thank Dr. Jerome for his contributions to this section, and his pioneering work in metal-free dentistry. I hope more dentists acquire his techniques.*

Horrors Of Metal Dentistry

Why are highly toxic metals put in materials for our mouths? Because not everyone agrees on what is toxic at what level. Just decades ago lead was commonly found in paint, and until recently in gasoline. Lead was not less toxic then, we were just less informed! The government sets standards of toxicity, but those “standards” change as more research is done (and more people speak out). You can do better than the government by dropping your standard for toxic metals to zero! Simply remove them.

The debate still rages over mercury amalgam fillings. No one disputes the extreme toxicity of mercury compounds and mercury vapor. The ADA feels that mercury amalgam fillings are safe because they do not vaporize or form toxic compounds to a significant degree. Opponents cite scientific studies that implicate mercury amalgams as disease causing. Many dentists advocate mercury amalgam fillings simply because they are accepted by the ADA, which they believe protects them from malpractice litigation. Why risk your health and life on their opinions? Remember everything corrodes and everything seeps, so amalgams must too.

Cadmium is used to make the pink color in dentures! Cadmium is five times as toxic as lead, and is strongly linked to high blood pressure.

Occasionally, thallium and germanium are found together in mercury amalgam tooth fillings. Thallium causes leg pain, leg weakness, and paraplegia. If you are in a wheelchair without a very reliable diagnosis, have all the metal removed from your mouth. Ask the dentist to give you the grindings. Try to have them analyzed for thallium using the most sensitive methods available, possibly at a research institute or university.

I was astonished to find thallium in mercury amalgams! It couldn't be put there intentionally, look how toxic it is:

> ***TEJ500*** ***HR: 3***
>
> **THALLIUM COMPOUNDS**
>
> Thallium and its compounds are on the Community Right To Know List.
>
> THR: Extremely toxic. The lethal dose for a man by ingestion is 0.5-1.0 gram. Effects are cumulative and with continuous exposure toxicity occurs at much lower levels. Major effects are on the nervous system, skin and cardiovascular tract. The peripheral nervous system can be severely affected with dying-back of the longest sensory and motor fibers. Reproductive organs and the fetus are highly susceptible. Acute poisoning has followed the ingestion of toxic quantities of a thallium-bearing depilatory and accidental or suicidal ingestion of rat poison. Acute poisoning results in swelling of the feet and legs, arthralgia, vomiting, insomnia, hyperesthesia and paresthesia [numbness] of the hands and feet, mental confusion, polyneuritis with severe pains in the legs and loins, partial paralysis of the legs with reaction of degeneration, angina-like pains, nephritis, wasting and weakness, and lymphocytosis and eosinophilia. About the 18th day, complete loss of the hair on the body and head may occur. Fatal poisoning has been known to occur. Recovery requires months and may be incomplete. Industrial poisoning is reported to have caused discoloration of the hair (which later falls out), joint pain, loss of appetite, fatigue, severe pain in the calves of the legs, albuminuria, eosinophilia, lymphocytosis and optic neuritis followed by

> atrophy. Cases of industrial poisoning are rare, however. Thallium is an experimental teratogen [used to induce birth defects for study]. When heated to decomposition they [sic] emit highly toxic fumes of Tl [thallium]. See also THALLIUM and specific compounds.[24]

Fig. 61 Thallium excerpt.

Thallium pollution frightens me more than lead, cadmium and mercury combined, because it is completely unsuspected. Its last major use, rat poison, was banned in the 1970s. Every wheelchair patient I tested was positive for thallium! One current use for thallium is in Arctic/Antarctic thermostats. When added to mercury the mercury will stay liquid at lower temperatures. Are mercury suppliers then providing the dental industry with tainted amalgam?

The cancer causing or carcinogenic action of metals has been studied for a long time, although it doesn't get attention by our regulatory agencies. A scientific book on this subject was published in 1980.[25] One table from this book is shown on page 431. We can see that chromium and nickel compounds are the most carcinogenic metals. Nickel is used in gold crowns, braces, and children's crowns!

Note that the form of the metal is very important. For instance chromium is an essential element of *glucose tolerance*

---

[24] *Dangerous Properties of Industrial Materials*, 7th ed. by N. Irving Sax and Richard J. Lewis Sr., Van NOSTRAND, Reinhold N.Y. 1989.

[25] The title is *Carcinogenicity and Metal Ions*. It is volume 10 of a series called *Metal Ions in Biological Systems*, edited by Helmut Sigel. A university chemistry library should have this book. It has a fascinating chapter on the leukemias by two scientists from the Academy of Sciences of the USSR, E. L. Andronikashvili and L. Mosulishvili. Their brilliant work and discussion was largely responsible for my pursuit of the whole subject of cancer.

factor, but most of its other compounds are extremely toxic. In general, xenobiotic compounds (foreign) are to be avoided! Metal doesn't belong in our foods or in our bodies.



Fig. 62 More dental metal.

Dental Rewards

After your mouth is metal and infection-free, notice whether your sinus condition, ear-ringing, enlarged neck glands, headache, enlarged spleen, bloated condition, knee pain, foot pain, hip pain, dizziness, aching bones and joints improve.

Keep a small notebook to write down these improvements. It will show you which symptoms came originally from your teeth. Symptoms often come back! So go back to your dentist, to search for a hidden infection under one or more of your teeth, or where your teeth once were! That infection can be the cause of tinnitus, TMJ, arthritis, neck pain, loss of balance, and heart attacks!

Dentures can be beautiful. Of course, plastic isn't natural, but it is the best compromise that can be made to restore your mouth. At least it isn't positively charged like metals; it can't set up an electric current nor a magnetic field in your mouth, all of which may be harmful.

Do not be swayed by arguments that plastic is not as strong as metal. You see dentures everywhere and they seem strong enough to eat with. You will be told that “noble” metals like gold and platinum



Fig. 63 Beautiful plastic mouth.

and silver are OK, that they are “inert” and do not corrode or seep. Nothing could be more untrue. You may be keeping them glossy by the constant polishing action of your toothpaste. But if you look at the underside, the view is frightful. **Everything tarnishes and everything seeps.** You wouldn't expect even a gold or silver coin that was dropped in a fountain 50 years ago to be intact. As metal corrodes your body absorbs it!



Fig. 64 Ugly metal in mouth.

In breast cancer, especially, you find that metals from dentalware have dissolved and accumulated in the breast. They will leave the breast if you clear them out of your mouth (and diet, body, home). **The cysts shrink and are simply gone.** No need to do surgery!

Diet Clean-up

Breakfast

Cook your cereal from scratch. Don't eat cold cereal; it has numerous solvents and molds. Buy hot cereals that say “no salt added,” like cream of wheat, steel cut oats or old fashioned oats,[26] millet, corn meal, cream of rice, or Wheatena. Cook it with milk to add nutritive value. Add your own (non-aluminum) salt and a pinch of vitamin C before cooking. Make granola from a recipe (see *Recipes*). Use honey, or brown sugar. Add raisins that were soaked for 5 minutes in vitamin C water. Use whipping cream or butter (both boiled) if you need to gain weight. Isn't this a delicious way to start your day! Add cinnamon to flavor, or frozen fruit and honey.

---

[26] Rolled oats have 235 mcg nickel per serving of 4 ounces, picked up from the rollers, according to *Food Values* 14th ed. by Pennington and Church, 1985. I have only found nickel in the "one-minute" or "instant" variety of oats, however.



Fig. 65 Unpolluted breakfast cereals.

Or start your day with fried potatoes, an egg, and glass of milk. Don't worry about cholesterol since you will be doing liver cleanses anyway. (We have been told that eggs carry *Salmonella* bacteria. I found *Salmonellas* only on the outside shell and the egg carton—never inside! Could the researchers have accidentally transferred the bacteria from the shell to the inside while they were testing?)

The milk should be 2% or more butterfat because the calcium in milk cannot be absorbed without at least this much fat. Eat homemade yogurt and add honey or homemade preserves yourself. You need 3 cups of a milk product each day. Homemade buttermilk is fine. If you don't tolerate milk, and get diarrhea from it, try a milk digestant tablet to go with it. Start with only ¼ cup at a time. Do not choose chocolate milk. There is no substitute for milk; calcium tablets are not satisfactory. Vegetable matter, although high in calcium, does not give you *available* calcium either, unless you buy a juicer and make vegetable juice out of it. Eating fish can give you a lot of calcium, but it is in the tiny bones hidden in the fish. Don't try to remove them. Canned salmon has a lot of calcium; tuna does not. On a day that you eat fish, you would not need milk. Goat milk is probably better than cows' milk, but more difficult to get used to.

Lunch

Cook your food from scratch. Don't start with cans or packages or frozen items to make some recipe. In fact, don't bother with any fancy recipes. Just cook two or three vegetables for lunch and eat them with butter and salt or homemade sauces. Bread and milk rounds it out, plus fruit (not canned or frozen). Soup is a nice change. Cook it with all the vegetables you can find. Don't start with a can or packet or cube. Use a bit of onion and genuine herbs to give it zest. Thyme and fenugreek, together, make a flavorful combination you can purchase in capsules. Just pull apart and season.

If all this is too much work, make fresh vegetable juice once a week and freeze enough so that you can have a daily nutritious meal just by pouring a glass of it, together with bread and yogurt or milk.

Never diet during illness

This is a rule based on common sense. A weight-loss diet must wait at least two years.

Bake your own bread! I found aflatoxin in commercial bread after just four days in my bread box, but none in homemade bread even after two weeks! Aflatoxin is a most potent carcinogen and immunosuppressant. Aflatoxin is the toxin in your diet that keeps you from clearing propyl alcohol from your body (see 382)! Aflatoxin is a substance made by mold; bread starts to mold on the grocery store shelf. Don't buy plastic-wrapped bread. Don't ever salvage moldy food, whether it is fruit, breads or leftovers in the refrigerator. Throw them out. Buy a bread maker. It can do everything, including baking the bread. Use unbleached (unbrominated) flour and add ½ tsp. vitamin C powder per loaf to help retard mold further (it also makes the bread rise higher).

Supper

Cook your supper from scratch. Emphasize fish for animal food, not beef, pork, turkey or chicken. Don't buy bread crumbs, use your own. Don't buy batter, make your own. Use genuine eggs, not substitutes. Wash your hands after handling raw meat or eggs.

Make your own salad and salad dressing out of olive oil, fresh lemon juice or white distilled vinegar (apple cider vinegar has aflatoxins), honey, salt and herbs to flavor. If your digestion isn't strong enough for raw vegetables or fruit, make juice. Get a sturdy juicer and make your juice about half carrot juice and half from vegetables like celery, squash, lettuce, and broccoli. Make your own tomato sauce with pure herb seasoning, not from ajar or can (home canned foods are fine, of course, as long as they are not made in a big aluminum pot with aluminum-containing salt).

Cook real potatoes, not instant varieties. Peel them to get rid of Kojic acid (mycotoxin) and scopolamine (the green part). Make mashed potatoes from scratch, with milk, not box potatoes, nor chips nor French fries. Chips and fries were made in chemical grease called "hydrogenated." There is a large amount of nickel in hydrogenated fats.[27] Fry your potatoes in butter, lard or olive oil. Find butter that is not wrapped in foil and is not salted. Salt your own butter, using aluminum-free salt.[28] Don't wrap potatoes in foil to bake, coat with butter or olive oil. Don't eat the peels.

Eat no meat that hasn't been cooked as thoroughly as if it were pork.

Other animals are as parasitized as we, full of flukes and worms and *Schistosomes* in every imaginable stage, and if the blood carries these, would we not be eating live parasites if we eat animals in the raw state? We have been taught to cook thoroughly any pork, fish or seafood. Now we must cook thoroughly any beef, chicken or turkey. It must be at cooking temperature (212°F or 100°C) for 20 minutes. Freezing is not adequate. Canned meats are safe from living parasites, but are not recommended due to added chemicals.

Beverages

Drink 6 kinds of beverages:

- milk
- water
- fruit juices
- vegetable juices
- herb teas
- homemade (see *Recipes*)

---

[27] 114 mcg/100 g. Taken from *Food Values* 14th ed. by Pennington and Church, 1985.

[28] Salt has aluminum in it to keep it from caking. Buy salt that has magnesium carbonate as its anti-caking agent. Sea salt must be baked for 5 minutes at 400°F to destroy molds. Or buy chemically pure salt (see *Sources*).

This means getting off caffeine. And if you are already fatigued, this means you might be even more fatigued for a short time. You might have headaches from withdrawal, too. But they will only last 10 days. Mark your calendar and count off the days. Take headache medicine, if necessary, but make sure it does not contain caffeine. For energy, to replace caffeine, take one arginine (500 mg, see *Sources*) upon rising in the morning and before lunch. Soon you won't need it.

Cutting down on coffee, decaf, soda pop and powdered drinks won't do. You must be completely off. They contain very toxic solvents due to careless, unregulated production methods. Much is imported and can't be sufficiently regulated.

Even though grain (drinking) alcohol is the recommended substitute for propyl alcohol, that doesn't mean you may safely drink it. It is inadvisable to drink any form of alcohol at least until you are fully recovered.

1. Milk: 2% or higher, drink three 8 oz. glasses a day. Alternate brands. Buttermilk will do. Homemade yogurt is fine. Goat milk is also fine. Start with ¼ cup and increase gradually, if you are not used to it. If you do not drink milk because it gives you more mucous, try to drink milk anyway. If you have other reactions, like diarrhea, try milk digestant tablets (available at health food stores). Milk is too valuable to avoid: there are many unwanted chemicals in most brands of milk, but it is solvent-free, mold-free and very nutritious. The only exception should be for serious symptoms, like swelling, colitis, flu, or chronic diarrhea.

But all milk, whether goat or cow, is contaminated with *Salmonella* and *Shigella* bacteria as well as fluke parasite stages. Cattle are immunized against *Salmonella* but it does not prevent its persistence in the bowel. All these are very harmful. Pasteurization does not kill all of them. Only heating to a rolling boil makes milk safe. To do this in the easiest way, pour 1 or 2 quarts milk into an enamel double boiler or microwavable glass jar. Stay in the kitchen while the heat is on. When the bubbles have risen to indicate boiling, turn off the heat. You may throw away the “skin”. Pour into glass jar and refrigerate. Another easy way is to use a pressure cooker that holds several pint jars of milk. All dairy products that have only been pasteurized are still contaminated. Ultrapasteurization does not improve matters. Dairy products that cannot be sterilized should not be consumed. It may be possible to find sterilized milk in paper containers on the store shelf—not in the refrigerator; if it wasn't sterile it would go foul in a day! Canned milk has solvent pollution. Powdered milk has both solvent and bacterial pollution.

2. Water: 2 pints. Drink one pint upon rising in the morning, the other pint in the afternoon sometime. The cold water faucet may be bringing you cadmium, copper or lead, but it is safer than purchased water, which inevitably has solvents in it. Let it run before using it. Filters are rather useless because water pollution comes in surges. A single surge of PCB contaminates your filter. All the water you use after this surge is now polluted, so you will be getting it chronically, whereas the unfiltered water cleans up again after the surge passes. Until you can test your own water for solvents, PCBs and metals, no expensive filter is worth the investment. An inexpensive pure carbon filter that is replaced every month may improve your tap water. Inflexible plastic pitchers fitted with a carbon filter pack are available (see *Sources*). Never buy filters with silver or other chemicals, even if they are just added to the carbon. Keep the filter sterile by soaking in diluted grain alcohol weekly.

3. Fruit juice: fresh squeezed only. Some stores make it while you wait. If they freeze some of it, you could purchase the frozen containers. Bottled fruit juices have traces of numerous solvents, as do the frozen concentrates, as do the refrigerated ones, don't buy them. You have to see it being made, but watch carefully: I recently went to a juice bar where they made everything fresh, before your very eyes. And I saw them take the fruit right from the refrigerator and spray it with a special wash "to get rid of any pesticides," then put a special detergent on it to clean off the wash! So instead of getting traces of pesticide, I got traces of propyl alcohol![29] Another grocery store had a machine that squeezed the oranges while you watched. But if you did not watch them filling the jugs, you missed seeing them add a tablespoon of concentrate, from a bottle out of sight, to give it better flavor. It still qualifies as "Fresh squeezed 100% orange juice," but thanks to that concentrate it now has toluene and xylene in it! Best of all, buy a juicer, select completely unbruised fruit, wash with plain water, and make your own juice (enough for a week—freeze it in half pint plastic bottles). For stronger flavor, leave some of the peel in the juice.

4. Vegetable juice: fresh or frozen only. If you or a friend would be willing to make fresh juice, this would be much better than purchased juice. Start with carrot juice. Peel carrots (don't scrape them, it's too easy to miss small dirt spots) and remove all blemishes carefully, then rinse. Drink ½glass a day. After you are accustomed to this, add other vegetables and greens to the juice to make up half of it. Use celery, lettuce, cabbage, cucumber, beet, squash, tomato, everything raw that you normally have in your refrigerator. Then drink one glass a day.

5. Herb tea: fresh or bulk packaged. Tea bag varieties are moldy. Buy a non-metal (bamboo is common) tea strainer. Sweeten with honey or brown sugar with vitamin C added.

6. Homemade beverage. If you will miss your coffee or decaf, try just plain hot water with boiled whipping cream. Sweeten with honey. Please see *Recipes* for many more suggestions.

---

[29] Yes, I took a sample of the wash to test.

Horrors In Commercial Beverages

Commercial beverages are especially toxic due to traces of solvents left over from the manufacturing process. There are solvents in decaffeinated beverages, herb tea blends (not single herb teas), carbonated drinks, beverages with Nutrasweet™, flavored coffee, diet and health mixes, and fruit juices, even when the label states “not from concentrate” or “fresh from the orchard,” or “100% pure.”

It is allowable to use solvents to clean machinery used in bottling (please look again at page 347)! It is also allowable to use solvents to make spice oleoresins, which are used as flavoring.

> **21 CFR 173.240 (4-1-94 Edition) Isopropyl Alcohol.**
>
> Isopropyl alcohol may be present in the following foods under the conditions specified:
>
> (a) In spice oleoresins as a residue from the extraction of spice, at a level not to exceed 50 parts per million.
>
> (b) In lemon oil as a residue in production of the oil, at a level not to exceed 6 parts per million.
>
> (c) [Discusses its use in hops extract.]

Here is a summary of other solvents mentioned:

Solvent	Allowable residue in spice oleoresins	Paragraph in 21 CFR
Acetone	30 PPM	173.210
Ethylene dichloride	30 PPM	173.230
Methyl alcohol	50 PPM	173.250
Methylene chloride	30 PPM	173.255
Hexane	25 PPM	173.270
Trichloroethylene	30 PPM	173.290

Fig. 66 Lawful uses of solvents in food.

I have found all these solvents and others in commercial beverages! Some of the solvents I have found are just too toxic to be believed! Yet you can build the test apparatus yourself (page 457), buy foods at your grocery store, and tabulate your own results. I hope you do, and I hope you find that the food in your area is cleaner than mine! Remember that the Syncrometer can only determine the presence or absence of something, not the concentration. There may only be a few parts per billion, but a sick person trying to get well cannot afford any solvent intake. For that matter, none of us should tolerate any of these:

- **Acetone** in carbonated drinks
- **Benzene** in store-bought drinking water (including distilled), store-bought fruit juice (including health varieties)
- **Carbon tetrachloride** in store-bought drinking water
- **Decane** in health foods and beverages
- **Hexanes** in decafs
- **Hexanedione** in flavored foods
- **Isophorone** in flavored foods
- **Methyl butyl ketone** and **Methyl ethyl ketone** in flavored foods
- **Methylene chloride** in fruit juice
- **Pentane** in decafs
- **Propyl alcohol** in bottled water, commercial fruit juices, commercial beverages.
- **Toluene** and **xylene** in carbonated drinks
- **Trichloroethane** (TCE), **TC Ethylene** in flavored foods
- **Wood alcohol** (methanol) in carbonated drinks, diet drinks, herb tea blends, store-bought water, infant formula

If you allowed a tiny drop of kerosene or carpet cleaning fluid to get into your pet's food every day, wouldn't you expect your pet to get sick? Why would you not expect to be sick with these solvents in your daily food? I imagine these solvents are just tiny amounts, introduced by sterilizing equipment, the manufacturing process, and adding flavor or color. Flavors and colors for food must be extracted somehow from the leaves or bark or beans from which they come. But until safe methods are invented, such food should be considered unsafe for human consumption (or pets or livestock!).


PENTANE
WOOD ALCOHOL
WOOD ALCOHOL
WOOD ALCOHOL
PENTANE
ISOPHORONE
XYLENE
HEXANEDIONE
V8
PEPSI
Coca-Cola
diet Coke
7UP
CANADA DRY

Fig. 67 Some unsafe beverages.

Food Preparation

Cook your food in glass, enamel, ceramic or microwavable pots and pans. Throw away all metal ware, foil wrap, and metal-capped salt shakers since you will never use them again. If you don't plan to fry much (only once a week), you might keep the Teflon™ or Silverstone™ coated fry-pan, otherwise get an enamel coated metal pan. Stir and serve food with wood or plastic, not metal utensils. If you have recurring urinary tract infections, you should reduce your metal contact even further; eat with plastic cutlery. Sturdy decorative plastic ware can be found in hardware and camping stores. Don't drink out of styrofoam cups (styrene is toxic). Don't eat toast (many toasters spit tungsten all over your bread and make benzopyrenes besides). Don't buy things made with baking powder (it has aluminum) or baked in aluminum pans. Choose goods made with baking soda and sold in paper or microwavable pans. Don't run your drinking water through the freezer or fountain or refrigerator. Don't heat your water in a coffee maker or tea kettle. Don't use a plastic thermos jug (the plastic liner has lanthanides) the inside must be glass. Don't drink from a personal water bottle (it begins to breed bacteria) unless you sterilize it daily.

Why are we still using stainless steel cookware when it contains 18% chromium and 8% nickel? Because it is rustproof and shiny and we can't see any deterioration. **But all metal seeps!** Throw those metal pots away. Get your essential minerals from foods, not cookware.

Never, never drink or cook with the water from your hot water faucet. If you have an electric hot water heater the heating element releases metal. Even if you have a gas hot water heater, the heated water leaches metals or glues from your pipes. If your kitchen tap is the single lever type, make sure it is fully on cold for cooking. Teach children this rule.

Food Guidelines

It is impossible to remember everything about every food, but in general do not buy foods that are highly processed. Here are a few foods; see if you can guess whether they should be in your diet or not.

breads	Yes, but only from a bakery, and never wrapped in plastic.
toast	No. It has benzopyrene and tungsten. Yes, if made on a cookie sheet or in a frying pan.
cheese	Yes, if used in baked dishes.
chicken	Only if cooked for 20 minutes at boiling point, as in soup, or canned (never prepare raw chicken yourself).
wine with dinner	No.

peanut butter	Yes if you grind it yourself and add ¼ tsp. vitamin C powder as you grind.
cottage cheese	No, it can't be sterilized easily.
desserts	Yes, but again, only if flavored with safe extracts.
rice	Yes, if vitamin C is added before cooking. Use white only, brown is too moldy.
pasta	Yes, with homemade sauce and vitamin C.
Jell-O™	No, it has artificial flavor and color.
egg dishes	Yes, but not “imitation”, cholesterol-free or cholesterol-reduced varieties.
fish, seafood	Yes!
soy foods (tofu)	No. It's the extensive processing that taints it.
soup	Yes, if seasoned only with herbs (no bouillon cube).
sugar	Yes, turbinado or brown if treated with vitamin C.
herb tea	Yes, if not in a bag and not in a mixture of herbs.
cheesecake	Yes.

Fig. 68 Some good foods.

Choose brands with the shortest list of ingredients. Alternate brands every time you shop.

Fig. 69 All breads I tested had mold if they were in plastic.

Dining Out

Restaurants (excluding fast food) are generally quite safe to eat at. Here are some do's and don'ts;

Do carry your own aluminum-free salt and vitamin C powder with you.

Do ask for plastic cutlery.

Do drink the water if from the tap.

Do ask for boiled, not just steamed, milk.

Don't eat or drink from styrofoam. If getting food "to go," get it in clear plastic containers, or ask them to line the styrofoam container with paper or plastic wrap, and line the styrofoam cup with a plastic baggy.

Don't use their ketchup and condiments (they have been standing out too long).

Here is a list of things that are generally safe to order:

pancakes, French toast, waffles	Don't use their imitation syrup (has benzoate), use honey instead.
eggs	Any style except soft boiled and scrambled. The white should be solid.
hash browns	If lightly fried, not deep fried.
soup	Only if nothing else is available. (It probably came in a can and was cooked in an aluminum pot and is full of aluminized salt.)
vegetarian sandwiches	But no soy products (too processed).
baked or boiled potatoes	Use only cheese sauce, bring your own salt, don't eat the skin.
cooked vegetables	Broccoli, Brussels sprouts, beets, corn, squash, and so forth.
vegetable salads	Don't eat the croutons, bacon bits, and anything that doesn't look fresh.
vegetarian dishes	But no soy ingredients and or sauces. Fresh ketchup OK.
bread and biscuits	White only, not toasted, not “cholesterol-free” varieties.
fish and seafood	Anything but deep fried (the oil may have benzene) is fine: baked, steamed, fish cakes, seafood cocktails, etc.
Mexican food	Any of the numerous baked dishes.
Chinese food	Except dishes with tofu or MSG.
fruit cup	With honey and cinnamon.
fruit pies, cobblers	But not with ice cream (every flavor has benzene).
lemon or lime meringue pie	Indulge yourself.

Fig. 70 Good restaurant foods.

As you see your symptoms disappear, one after another, you will feel the magic of healing. Many sick persons have 50 or more symptoms to start out! They could fill two sheets of paper, one symptom to each line. It can be quite shocking to see a list of all your symptoms.

Sometimes a new symptom appears as fast as an old one disappears. The coincidence makes it tempting to believe that one symptom turns into a different one. But it is not so. If a new symptom appears, it is because another pathogen has become activated due to a new toxin. Try to identify the new item. Stop using any new food, supplement, or body product, even if it is a health variety, and see if it goes away.

Body Clean-up

We are living in a very fortunate time. We are not expected to all look alike! The 60's brought us this wonderful freedom. Freedom to dress in a variety of styles, use make-up or no make-up, jewelry or no jewelry, any kind of hair style, any kind of shoes.

You will need to go off every cosmetic and body product that you are now using. Not a single one can be continued. They are full of titanium, zirconium, benzalkonium, bismuth, antimony[30], barium[31], strontium[32], aluminum, tin, chromium, not to mention pollution solvents such as benzene and PCBs.

Do not use any commercial salves, ointments, lotions, colognes, perfumes, massage oils, deodorant, mouthwash, toothpaste, even when touted as "herbal" and health-food-type. See *Recipes* for homemade substitutes.

---

[30] Breast cancer cases show titanium, zirconium, benzalkonium, bismuth and antimony accumulation in the breast.

[31] Barium is described in the *Merck Index* as "Caution: All water or acid soluble barium compounds are POISONOUS." 10th ed. p. 139 1983.

[32] This element goes to bones.

People are trying desperately to use less toxic products. They seek health for themselves. So they reach for products that just list herbs and other natural ingredients. Unfortunately, the buyers are being duped. The Food and Drug Administration (FDA) requires all body products to have sufficient antiseptic in them. Some of these antiseptics are substances you must avoid! But you won't see them on the label because manufacturers prefer to use quantities below the levels they must disclose. And by using a variety of antiseptics in these small amounts they can still meet sterility requirements. The only ingredient you might see is “grapefruit seed” or similar healthy-sounding natural antiseptic. This is sad for the consumer of health food varieties.

- I have seen rocks sold as “Aluminum-Free Natural Deodorant”. You rub the rock under your arms. It works because the rock is made of magnesium-aluminum-silicate.
- Men's hair color has lead in it.
- Lipstick has barium, aluminum, titanium.
- Eye pencil and shadow have chromium.
- Toothpaste has benzene, tin, and strontium.
- Hair spray has propyl alcohol and PCBs. BEWARE! Stop using it today.
- Shampoo, even health varieties, has propyl alcohol! BEWARE! Stop using it today.
- Cigarettes have lead, mercury, nickel and *Tobacco Mosaic virus*.
- Chewing tobacco has ytterbium

Some of the unnatural chemicals listed are present because of residues in the manufacturing process, but others you will actually see listed on the label!

Propyl alcohol and wood alcohol are present because the tubing used to fill the bottles is sterilized and cleaned with them. Ice cream machines are “oiled” with a gel containing petroleum products. This could explain why I always find benzene in ice cream.

SUPER
TAYLOR-LUBE
TAYLOR
AMOCO OIL CO.
4 FL. OZ.
TAYLOR
LUBE

Fig. 71 Examples of commercial "food lube."

How can propyl alcohol in shampoo get into your body in significant amounts? The skin is more absorbent than we realize, and time and time again I see cancer victims who have gone off every body product except their favorite shampoo. They harbor propyl alcohol until they make that final sacrifice. It is better to switch shampoos than to not need any due to radiation and chemotherapy!

See *Recipes* for easy-to-make, natural cosmetics. But you might consider just stopping them all. Especially if you're going on vacation.

Use nothing that you wouldn't use on a new-born baby. This is a permissive age. You will be the only one feeling "naked." Others won't even notice. Don't forget advertising is aimed at you, even if other people's eyes are not!

Don't even use soap unless it is homemade soap (see *Recipes*) or borax straight from the box. Borax was the traditional pioneer soap. It is antibacterial and can be made into a solution. It is also a water softener and is the main ingredient in non-chlorine bleach. Borax can remove grease, too, and some stains.

But even borax is not natural to your body and it is therefore wise to use as little as necessary. See *Recipes* for anti-bacterial borax soap.

Dishes and clothing are primary source of PCBs.

Fig. 72 Detergents with PCBs.

MULE 20 TEAM
BORAX
100 YEARS

homemade soap pure borax

Fig. 73 Safe soaps.

Don't use toothpaste, not even health-food varieties. To clean teeth, use plain water or chemically pure baking soda (see *Sources*)—but dissolve it in water first, otherwise it is too abrasive. Or brush with hydrogen peroxide food grade, not the regular variety (see *Sources*). Don't use floss; use 2 or 4-pound monofilament fish line. Floss has mercury antiseptics (with thallium pollution!). Throw away your old toothbrush—solvents don't wash away.

Don't use mouthwash. Use saltwater (aluminum-free salt) or food grade hydrogen peroxide (a few drops in water).

Don't use hair spray.

Don't use massage oils of any kind. Use olive oil.

Don't use bath oil. Take showers, not baths, if you are strong enough to stand. Showers are cleaner.

Don't use perfumes or colognes.

Don't use commercial lotions or personal lubricants.

Stop Using Supplements

Stop using your vitamin supplements. They, too, are heavily polluted. This is the saddest, most tragic part of your instructions. I have found solvents, heavy metals and lanthanides in 90% or more of the popular vitamin and mineral capsules and tablets I test. These substances will do more harm in the long run than the supplement can make up for in benefits.



The capsule in the foreground is a notorious tryptophane capsule. It had the following pollutants: PCBs, mercury, ruthenium, thulium, strontium, praseodymium, aluminum, benzalkonium.

Fig. 74 Some polluted supplements.

Most of the varieties of vitamin C that I have tested are polluted with thulium! Until all vitamins and minerals and other food supplements have been analyzed for pollutants, after they are encapsulated or tableted, they are not safe. We need more disclosure on our products. No manufactured product is pure. We can't expect that. But at least we should be able to tell what impurities we are getting, and how much.

It is possible to do detailed analysis of foods or products at a reasonable price. Look at the bottle of common table salt, sodium chloride, that is used by beginning chemistry students to do experiments. It must be thoroughly analyzed for them because minute impurities affect their results. (Those minute impurities, like lead, affect you, too.) Look at the label on the bottle in the picture. Even after all these tests, the cost of laboratory salt is only $2.80 per pound.[33]

S-271
Certified A.C.S.
Sodium
Chloride
Fisher Scientific Company

Fig. 75 Pure salt.

It is most important not to be fooled by ingredient claims, like “made from organically grown vegetables”. Sure that's great, but the analysis *I* trust would be done on the final, cleaned, cooked and packaged product on the shelf. The package is a major unlisted ingredient.

Toxic solvents like decane, hexane, carbon tetrachloride and benzene will get more flavor or fat or cholesterol out of things than metabolizable grain alcohol. Of course, the extraction process calls for washing out the solvent later. But it can't all be washed out, and a detailed analysis on the final product would give the public the information they need to make informed choices.

---

[33] You will pay about $8.00 per pound (Spectrum Chemical Co.) for USP (United States Pharmaceutical) grade. But the same analysis is done on the cheaper grades, and my point is that the analysis is cost effective enough that it should be done on our daily foods.

All supplements must be tested for purity by yourself. If this cannot be done,
don't take them.

Polluted supplements do much more harm than good. Get your super-nutrition by juicing vegetables of all kinds and making herbal teas.

Safe Supplements

There are, no doubt, lots of safe supplements to be had. The problem is knowing which they are. The nature of pollution is such that one bottle might be safe, while another of the same brand is not. In view of this, as I found a polluted bottle, I stopped using any more of that brand. That is why I am reduced to recommending only the ones in the *Sources* at this time.



Common salt for student use is thoroughly analyzed for pollution. The label gives you the final "Actual Lot Analysis" of the product. It is not expensive.
Fig. 76 Laboratory salt label.

Vitamin C, in crystal form, is a must in your lifestyle. It helps the liver, and possibly other organs, detoxify things. It also helps retard mold, and perhaps even destroys aflatoxins! Keep some next to your refrigerator so it is handy when you put away groceries. Add 1/8 tsp. to maple syrup, vinegar, cooked cereal, fruit juice, leftovers. Have ¼ tsp. (1 gram) with each meal.

Vitamin B_2, 100 mg. This is the vitamin that helps detoxify benzene! Take one to three a day. While recovering from AIDS you need 3 tablets three times a day.

Vitamin B_6, 250 mg, and B-complex, 50 mg. Undoubtedly these help the liver and kidneys in many ways. One a day.

Magnesium oxide, 300 mg., is another must. Take one or two a day. It is a major mineral; all of our cells need lots of it. Only leafy vegetables provide it.

Hydrogen peroxide, food grade. It is advantageous to kill bacteria and viruses to some extent every day. Hydrogen peroxide lets you do this. It should never come in contact with metal, including its container or metal tooth fillings. If you get a few drops on your skin it may turn white and sting, but does no harm, so simply wash it off. Instructions for its use come with the product.

Herbs. These are excellent supplements, both in bulk and capsules, but not extracts, concentrates, or concoctions. There are many books that describe their uses.

Thioctic acid or lipoic acid. Presumably this chelates (traps and prepares for elimination) heavy metals, and helps the liver in detoxifying obscure and deadly poisons. Everyone would benefit from 100 mg. per day. I find it outstanding, and give it to many ill persons, even when not mentioned in the case histories. It comes as a 100 mg. capsule (see *Sources*). I use it at doses from one capsule, 3 times a day, to 2 capsules, 5 times a day. I have seen no side effects at these dosages, even in very sick persons.

Lugol's Iodine Solution (see *Recipes*) is old-fashioned "iodine." Iodine has a distinctive trait: it hangs up on anything and everything. In fact, it attaches itself so quickly we consider everything it touches as "stained." This is just the property we want to make it safe for use. The amount you use is immediately hung up, or attached, to your mucous and can not be quickly absorbed into the blood or other organs. It stays in the stomach. And for this reason it is so useful for killing vicious bacteria like *Salmonella*.

Do not take Lugol's iodine if you know you are allergic to iodine. It could be fatal.

Six drops of Lugol's solution can end it all for *Salmonella*. If you have gas and bloating, pour yourself ½glass of water. Add 6 drops of Lugol's (not more, not less), stir with wood or plastic, and drink all at once. The action is noticeable in an hour. Take this dose 4 times a day, after meals and at bedtime, for 3 days in a row, then as needed. This eradicates even a stubborn case of *Salmonella*.

Notice how calming 6 drops of Lugol's can be, soothing a manic stage and bringing a peaceful state where anxiety ruled before.

Lugol's is perfectly safe (if not allergic) to take day after day, when needed, because of its peculiar attaching property. It arrives in the stomach, reattaches to everything in proximity. Doomed are all *Salmonellas*; doomed also are eggs of parasites that might be in the stomach (cysts).

Naturally, one would not leave such medicine within the reach of children. Also, one would not use anything medicinal, including Lugol's unless there were a need, like cancer, AIDS, or bowel disease. When the gas and bloating problem has stopped, stop using Lugol's. If one or two doses of Lugol's cures the problem, stop. Store it in a perfectly secure place. In the past, 2/3 of a teaspoon (60 drops) of Lugol's was the standard dose of iodine given to persons with thyroid disease. Six drops is small by comparison.

Turmeric and **fennel** are herbs also used as cooking spices. They can eradicate invasive *E. coli* and *Shigella* bacteria! They are completely harmless, and are part of the Bowel Program.

Other supplements. The concept of supplementing the diet is excellent, but the pollution problem makes it prohibitive. Use only supplements and brands recommended in *Sources*, although the best approach is to test them yourself with your Syncrometer. I can't guarantee the brands in *Sources* will stay pure. If in doubt, leave it out.

Home Clean-up

This is the easiest task because it mostly involves throwing things out. Hopefully your family and friends will jump to your assistance.

- The basement gets cleaned.
- The garage gets cleaned.
- Every room in the house gets cleaned.

Your Basement

To clean your basement, remove all paint, varnish, thinners, brush cleaners, and related supplies. Remove all cleaners such as carpet cleaner, leather cleaner, rust remover. Remove all chemicals that are in cans, bottles or buckets.

You may keep your laundry supplies: borax, washing soda, white distilled vinegar, bleach and homemade soap. You may keep canned goods, tools, items that are not chemicals. You may move your chemicals into your garage. Also move any car tires and automotive supplies like waxes, oil, transmission fluid, and the spare gas can (even if it is empty) into your garage or discard them.

Seal cracks in the basement and around pipes where they come through the wall with black plastic roofing cement. In a few days it will be hard enough to caulk with a prettier color. Spread a sheet of plastic over the sewer or sump pump.

Your Garage

Do you have a garage that is a separate building from your home? This is the best arrangement. You can move all the basement chemicals into this garage. Things that will freeze, such as latex paint, you may as well discard. But if your garage is attached, you have a problem. Never, never use your door between the garage and house. Walk around the outside. Don't allow this door to be used. Tack a sheet of plastic over it to slow down the rate of fume entrance into the house. Your house acts like a chimney for the garage. Your house is taller and warmer than the garage so garage-air is pulled in and up as the warm air in the house rises. See the drawing.

In medieval days, the barn for the animals was attached to the house. We think such an arrangement with its penetrating odors is unsavory. But what of the gasoline and motor fumes we are getting now due to parked vehicles? These are toxic besides! This is even more medieval.



Fig. 77 Garage fumes.

If your garage is under your house, you cannot keep the pollution from entering your home. In this case, leave the cars and lawnmower outside. Remove cans of gasoline, solvents, etc. Put up a separate shed for these items.

Special Clean-up for Freon (CFCs)

Because I consider Freon to be the top health hazard in our home, I recommend turning in your refrigerator for a non-CFC variety. Dispose of all spare units. Remove window air conditioners or test the dust in your home (page 485) for Freon. Have your car's air conditioning system checked. Dispose of old pressurized cans. Even one whiff is too much. It never leaves the body because the body has no detoxification methods for it!

Only one useful reaction with Freon comes to mind. Freon is thought to be responsible for the ozone “hole” at the South Pole. Would Freon react with ozone supplied to your body and thereby become biodegradable? Indeed, it does! But only if you drink it as ozonated water. Other ozone routes, as intravenous or rectal, have not been observed to be as effective.

If you are following your progress with the Syncrometer, you will see that Freon now appears in the liver for the first time. (Before this, it was marooned in the parathyroids, thymus, and other organs.) You may also detect a feeling like indigestion. You must come to the assistance of your liver. Even ozonated Freon is extremely burdensome to the liver.

A combination of herbs (Liver Herb Drink in *Recipes,* page 552) rescues the liver from its plight, and prevents the indigestion. After drinking liver herbs you will see that the Freon now appears in the kidneys. Yet it is marooned there unless you assist them. Take the kidney cleanse to assist the kidneys so they can finally excrete the Freon into the urine.

It's an elaborate detoxifying program and usually takes six to eight weeks to get most of the Freon out. Afterward, continue the programs at one fourth dosage for half a year.

Forane is one of the new refrigerants. Although toxic, at least I observe it in the liver directly, suggesting that your body is capable of handling it. Remember your new refrigerator will still be using a toxic coolant, and it would be best to keep it outside or at least vented to the outside.

Special Clean-up for Fiberglass

Fiberglass insulation has microscopically small bits of glass that are free to blow into the air. When house drafts pull it into the air you will inhale them. They cut their way through your lungs and organs like millions of tiny knives, spreading through your body, since there is no way out for them. You smell nothing and feel nothing. This makes it a very sinister poison. Your body, though, recognizes these sharp, pointed bits and tries to stop their spread by sequestering them in cysts.

Most solid malignant tumors contain fiberglass or asbestos, another glass-like particle. In nearly all cases a hole can be found in the ceiling or walls, leading to fiberglass insulated parts of the house. When these holes are sealed in an air-tight manner the house air no longer is positive for fiberglass. Covering with paneling is not sufficient. Check your dwelling for uncovered fiberglass. Repair immediately. Search for small screw holes intended for pictures, or electric outlet plates that are missing.

Also remove fiberglass jackets from water heater and fiberglass filter from furnace. Replace with foam or carbon. Best of all, hire a crew to remove it all from your home, and replace insulation with blown-in shredded paper or other innocuous substance.

Never build a new house using fiberglass for any purpose.

Special Clean-up for Asbestos

The biggest source of asbestos is not building materials! It is the clothes dryer belt and hair dryer! To be safe, remove the belt from your dryer and check to see if it says “Made in USA” on the belt itself. If so, it is OK. If not, it is imported, and probably contains asbestos. Exchange it for a USA belt (see *Sources*).

Hair dryers, too, may be imported and shed asbestos. It is especially hazardous to be aiming a stream of hot asbestos right at your face! If you can't find a safe model (see *Sources*), or are unsure, don't use any. If you have cancer or are ill, no one in the house should use an unsafe hair dryer.

Turn off radiators and electric heaters and cover them with big plastic garbage bags, or paint them, or remove them. They give off asbestos if their paint is old.

Your House

To clean the house, start with the bedroom. Remove everything that has any smell to it whatever: candles, potpourri, soaps, mending glue, cleaners, repair chemicals, felt markers, colognes, perfumes, and especially plug-in air “fresheners”. Store them in the garage, not the basement. Since all vapor rises, they would come back up if you put them in a downstairs garage or basement.

Do not sleep in a bedroom that is paneled or has wallpaper. They give off arsenic and formaldehyde. Either remove them or move your bed to a different room. Leave the house while this is being done. If other rooms have paneling or wallpaper, close their doors and spend no time in them.

Next clean the kitchen. Take all cans and bottles of chemicals out from under the sink or in a closet. Remove them to the garage. Keep only the borax, washing soda, white distilled vinegar and homemade soap. Use these for all purposes. For exact amounts to use for dishwasher, dishes, windows, dusting, see *Recipes*. Remove all cans, bottles, roach and ant killer, moth balls, and chemicals that kill insects or mice. These should not be stored anywhere. They should be thrown out. Remember to check the crawl space, attic and closets for hidden poisons also.

To keep out mice, walk all around your house, stuffing holes and cracks with steel wool. Use old-fashioned mouse traps. For cockroaches and other insects (except ants) sprinkle handfuls of boric acid[34] (not borax) under your shelf paper, behind sink, stove, refrigerator, under carpets, etc. Use vinegar on your kitchen wipe-up cloth to leave a residue that keeps out ants. Do this regularly. To wax the floor, get the wax from the garage and put it back there. A sick person should not be in the house while house cleaning or floor waxing is being done.

Remove all cans and bottles of "stuff" from the bathroom. The chlorine bleach is stored in the garage. Someone else can bring it in to clean the toilet (only). Leave only the borax soap, homemade soap, and grain alcohol antiseptic. Toilet paper and tissues should be unfragranced, uncolored. All colognes, after shave, anything you can smell must be removed. Family members should buy unfragranced products. They should smoke outdoors, blow-dry their hair outdoors or in the garage, use nail polish and polish remover outdoors or in the garage.

Do not keep new foam furniture in the house. If it is less than one year old, move it into the garage until you are well. It gives off formaldehyde. So does new clothing; it is in the sizing. Wash all new clothes before wearing. If you have a respiratory illness, move all the clothes in the clothes closet out of your bedroom to a different closet.

Do not use the hot water from an electric hot water heater for cooking or drinking. It has tungsten. Do not drink water that sits in glazed crock ware (the glaze seeps toxic elements like cadmium) like some water dispensers have. Do not buy water from your health food store that runs through a long plastic hose from their bulk tank (I always see cesium picked up from flexible clear plastic). Also ask them how and when they clean their tank. Best is to observe that it is done with non-toxic methods.

---

[34] Boric acid is available by the pound from farm supply stores and from Now Foods. Because it looks like sugar keep it in the garage to prevent accidental poisoning.

If your house is more than 10 years old, change all the galvanized pipe to PVC plastic. Although PVC is a toxic substance, amazingly, the water is free of PVC in three weeks! If your house has copper pipes don't wait for cancer or schizophrenia to claim a family member. Change all the copper pipe to PVC plastic immediately. If the pipes are not accessible, ask a plumber to lay an extra line, outside the walls. This is less expensive, too.

If you have a water softener, by-pass it immediately and replace the metal pipe on the user side of the softener tank. Softener salts are polluted with strontium and chromate; they are also full of aluminum. The salts corrode the pipes so the pipes begin to seep cadmium into the water. After changing your pipes to plastic, there will be so little iron and hardness left, you may not need a softener. If the water comes from a well, consider changing the well-pipe to PVC to get rid of iron. While the well is open, have the pump checked for PCBs. Call the Health Department to arrange the testing. If you must have softening after all this, check into the new magnetic varieties of water softener (although they only work well when used with plastic plumbing).

The cleanest heat is electric. Go total electric if possible. If you must stay with gas, have a furnace repair person check your furnace and look for gas leaks before the heating season starts. Don't call the gas company even though it is free. The gas company misses 4 out of 5 leaks! The Health Department does not miss any; call them! House builders and contractors are also reliable in their gas leak detection.

Unnatural Chemicals

And where I found them...

ARSENIC



in ant & roach hives,
grains of pesticide



in carpet & furniture "treated"
for stain resistance



in wallpaper

BARIUM



in lipstick



in bus exhaust

MOLYBDENUM

in "molys"

COBALT

NEW!
WITH
MORE
BLUE
GRAINS

in laundry
detergent

in dishwater
detergent



in skin bracer

in mouthwash

ANTIMONY



in eye liner

CADMIUM and COPPER



in water running
through old metal pipes

TITANIUM

in face powder &
other powders, and
in metal dental ware

PCB's


NEW!
WITH
MORE
BLUE
GRAINS

in regular and
health store detergents

LEAD

in men's hair
color restorer



in solder at joints
of copper pipes

CHROMIUM

in eyebrow
pencil

WATER
SOFTENER
SALT

in water
softener salts





HOT
WATER
HEATER

in leaks in pipes to gas
stove, furnace, water heater

VANADIUM



in diesel fuel

in candles
(even when
they're not
burning)

NICKEL



in metal jewelry
worn on the skin



in metal glasses frames

in metal
watch bands

in metal tooth fillings
and retainers

FIBERGLASS



from insulation behind holes in ceiling or uncovered outlets, water heater jackets, stuffed around fans and air conditioners, insulation

CFC's (FREON)



in
refrigerators



in air
conditioners

in spray
cans

MERCURY and THALLIUM


DENTAL FLOSS

in tooth fillings, sanitary napkins, cotton balls, dental floss, toothpicks, cotton swabs

THULIUM


SUPER SUPERIOR VIT. C
MIX a drink with vit C

in most brands of vitamin C I tested

DYSPROSIUM and LUTETIUM



in paint, varnish, shellac

HOLMIUM



in hand cleaners

HAFNIUM



in nail polish & hair spray

RHENIUM



in spray starch

BISMUTH


Cologne for MEN
BISM STOMACH RELIEF

in cologne and stomach aids

CESIUM


CLEAR SPRING water

in clear-as-glass plastic


DISTILLED WATER DISPENSOR

after running through long plastic hose

TIN and STRONTIUM



in toothpaste

YTTERBIUM, ERBIUM, TERBIUM


GREEN POWER ENERGY


FRESHER TOBACCO

in foil packaging



in plastic tooth fillings


SUPER SUPERVITAMIN

in vitamins and supplements

PRASEODYMIUM, NIOBIUM, NEODYMIUM, YTTRIUM

in over the counter drugs

in prescription drugs

RADON, URANIUM, THORIUM



in crawlspace without open vents

in holes and cracks in basement

LANTHANUM



in duplicator and copier ink

BENZALKONIUM and ZIRCONIUM



in tea bags



in deodorant

STANNOUS FLUORIDE

in toothpaste



in mouthwash



in cosmetics

ALUMINUM


Natural Rock

in "natural" deodorant advertised as aluminum-free

in salt

in cans



in walkers for the elderly

SKIN SOFTENER

in lotions

TUNGSTEN


ELECTRIC
HOT
WATER
HEATER

corroded rod in
electric water heaters



in electric
frying pans



in hair curlers



in toasters



in tea kettles

BERYLLIUM



in hurricane
lamps



in lawn mowers



in kerosene

FORMALDEHYDE



in foam
mattresses



in new
clothing



in paneling



in foam chairs

ASBESTOS



in hair blowers



in radiator paint



in clothes dryer belts


IF ALL OUR FOOD IS TOXIC, ARE WE GOING TO DIE?
DON'T LISTEN TO THOSE DOOM-SAYERS. THE EXPERTS WILL TAKE CARE OF US.

11/17/92

Fig. 78 Our future, unless we act.

Bioelectronics

The most important electronic device to make or buy is a **zapper**—a compact pulse generator operating from a common 9 volt battery whose output is about 30 KHz. It kills all parasites, bacteria, viruses, molds, and fungi even though their individual resonant frequencies are either higher or lower (50 KHz to 900 KHz). Building a zapper is described in an earlier chapter.

The next most useful device to have is a **Syncrometer.™** It lets you diagnose yourself and monitor your progress until you are cured. It consists of an audio oscillator circuit with your body as part of the circuit. Utilizing samples of parasites or pollutants, it lets you test for them in any product or body tissue. I include a design that you can make yourself.

A third very useful device is a **frequency generator**. You can use it to electrocute individual organisms, or together with the Syncrometer™ to find an organism's particular frequency. You need one that operates in the parasite, bacteria and virus ranges, from 50 KHz to 900 KHz. It must also be able to select a particular frequency, like 434 KHz, quickly and accurately. Frequency generators are available for as little as $300.00, but it is worth paying a little more to get a digital display of the frequency.

Making A Syncrometer

This is an *audio oscillator* circuit in which you include yourself by means of a handhold. You listen to the current in your circuit with a loudspeaker. Other oscillator circuits will work, too. A lot of fascinating opportunities present themselves with this concept.

I have previously published three ways to build the Syncrometer circuit.[35] Here is the circuit diagram:


amplifier/
speaker
S
P
. 1mf
. 0047
PNP
150
4.5 V
probe
handhold
test plates

4700pf moly cap
.1 mfd 16v cap
2N2907 PNP
min output transf 8-900Ù
150 .25w res
3 AA batteries
speaker (like Radio Shack 277-1008C)

Fig. 79 Syncrometer schematic.

If you are not an electronics enthusiast, you can still assemble a Syncrometer using a hobby kit. No soldering is required. Here is what you need:

Making a Hobby Kit Syncrometer

Item	Radio Shack Cat. No.
200 in One Electronic Project Lab by Science Fair	28-262
3 AA 1½ volt batteries	

---

[35] In *The Cure for all Cancers* and *The Cure for HIV/AIDS*.

Alligator clip test jumpers	You need 2.
Handhold. A four inch length of ¾ inch copper pipe, like for plumbing. These dimensions are critical to assure maximum skin contact.	
Probe. A banana plug.	Precision Mini-Hook Test Lead Set (contains two, you only need one) 278-1160A
Pencil, new.	

Fig. 80 Syncrometer parts list.

Build The Electrosonic Human in the *200 in One Electronic Project Lab*. It takes about 10 minutes.

Later, when you use the probe to press against your knuckle you may find getting the right sound is painful. In this case try substituting the .005 microfarad capacitor for the .01 microfarad capacitor in the circuit.

Attach the Probe. The Archer Precision Mini-Hook Test Lead Set has a banana plug for the probe on one end and a mini-hook on the other end for easy attachment to the circuit. Tape a long, new pencil to the probe to make it easier to hold. Connect the Probe to middle post of the primary side of the transformer (it also connects to the negative battery post). You will not be using the two connections the instructions tell you to hold.

Attach the Handhold. Clip the Handhold to one end of an alligator clip test jumper, and clip the other end to the base (B) of the transistor used in the circuit.

Attach an alligator clip to the post of the transformer that connects to the two capacitors. This will go to the **test plates**.

Final test. Turn the control knob on and keep turning the potentiometer to nearly the maximum. (This reduces the resistance. The schematic has a 150 ohm fixed resistor in place of the potentiometer.) Make sure you have good batteries installed. Test the circuit by briefly touching the Probe to the Handhold. The speaker should produce a sound like popping corn. If it does not, check that your alligator clips are not bending the spring terminals so much that other wires attached there are loose. Finally, turn switches OFF.

Making Test Plates

This is the box you attach to the basic Syncrometer circuit. It has test plates to put your test substances and tissue samples on. The wiring in it is arranged so that you can test for a toxin in a product, as well as search in yourself. This means you can search for *Salmonella* in the milk or cheese you just ate, not just for *Salmonella* in your stomach.

Only if the resonant frequency of an item on one plate is equal to the resonant frequency of an item on the other plate will the entire circuit oscillate or resonate! This implies the two plates have something in common. By putting a known pure sample on one plate you can reliably conclude the other sample contains it if the circuit resonates.

You may build a test plate box into a cardboard box (such as a facial tissue box) or a plastic box. Here are the instructions for the cardboard box model.

Test Plates Parts List

- Stiff paper.
- Aluminum foil.
- A facial tissue box is easiest. A plastic project box, about 7” x 4” x 1½” makes a more durable product, but requires a drill, and you should discard any metal lid it comes with.

- 3 bolts (tapered heads) about 1 inch long, 1/8 inch diameter and 6 washers and nuts to fit.
- toggle switch with OFF-ON positions.
- Alligator clip test leads.

Test Plates Assembly

Cut two 3-1/2 inch squares out of stiff paper such as a milk carton. Cover them with 4½ inch squares of aluminum foil, smoothed evenly and tucked snugly under the edges. You have just made yourself a set of open capacitors. Turn the box upside down and draw squares where you will mount them at the ends of the box. Don't actually mount them, to save wear and tear on them, until the rest of the box is complete.

Mount the ON OFF switch on the front of the box, underneath the right hand plate. Line it up so ON is downward and OFF is up. (An electronics shop can determine this for you at the time of purchase.) Label the box with ON and OFF signs.

Two bolts will be reserved for the plates. The third bolt is used as a terminal where the current from the oscillator circuit will arrive. Make a hole on the side of the box, near the left hand plate and mount the bolt so it sticks half way inside and halfway outside the box. It does not matter whether the head is inside or outside. Tighten it there with a nut on each side of the box. Label it TERMINAL. It merely means connecting place.

Mark the center of each square that you drew and each capacitor you built. Pierce first with a pin; follow with a pencil until a round hole is made at the center. Mount each plate with a bolt, fastening it below with a nut. Washers are optional.

The left side connection (terminal) gets attached to the left plate (bolt) with an alligator clip. Use another clip to attach the same left plate (bolt) to the ON OFF switch (there are two connections, use either one). Finally attach the ON OFF switch connection you didn't use to the right plate (bolt). Make sure the connections at the switch are not touching each other; you might tape them to guard against this.

All these connections should be checked carefully to make sure they are not touching others accidentally. But if you leave the box open so you can see any problems and use clear tape around connections to prevent accidental touching to the wrong connection, it should work OK.

Finally, trace your current. It comes in from the Syncrometer at the main terminal on the left. It is brought to the left plate. When the switch is ON it is simultaneously brought to the right plate. Notice that the plates are not connected to anything else. They are simply capacitors, letting current in and out momentarily and at a rate that is set by the frequency of the oscillator circuit, about 1,000 hertz. This frequency goes up as the resistance (of the circuit or your body) goes down.

The probe and handhold allow you to include yourself in the Syncrometer circuit. You grasp these when testing. This makes you part of the circuit.

The speaker lets you "listen" to the current. As resistance drops, current goes higher and frequency goes up. As frequencies go higher in the circuit, pitch goes higher. You will be comparing the sound of a standard "control" current with a test current.

Using The Syncrometer

Fill a saucer with cold filtered tap water. Fold a paper towel four times and place it in this dish. It should be entirely wet.

Cut paper strips about 1 inch wide from a piece of white, unfragranced, paper towel. Dampen a paper strip on the towel and wind it around the copper pipe handhold to completely cover it. The wetness improves conductivity and the paper towel keeps the metal off your skin.

- Start with the test plate switch at OFF.
- Turn the control knob (potentiometer) on, and to near maximum.
- Touch each plate with the probe, while holding the copper pipe with one hand. Only the left plate should give you a sound from the speaker. Turn the test plate switch ON. Now both plates should give you a sound when the probe touches them.
- Turn the test plate switch OFF again.
- Pick up the handhold, squeeze it free of excess water.
- Pick up the probe in the same hand, holding it like a pen, between thumb and forefinger.

Dampen your other hand by making a fist and dunking your knuckles into the wet paper towel in the saucer. You will be using the area on top of the first knuckle of the middle finger or forefinger to learn the technique. Become proficient with both. Immediately after dunking your knuckles dry them on a paper towel folded in quarters and placed beside the saucer. The degree of dampness of your skin affects the resistance in the circuit and is a very important variable that you must learn to keep constant. Make your probe as soon as your knuckles have been dried (within two seconds) since they begin to air dry further immediately.

With the handhold and probe both in one hand press the probe against the knuckle of the other hand, keeping the knuckles bent. Press lightly at first, then harder, taking one half second. Repeat a half second later, with the second half of the probe at the same location. There is an additive effect and you get two chances to listen to the current. All of this takes less than two seconds. Don't linger because your body will change and your next probe will be affected.

Subsequent probes are made in exactly the same way. As you develop skill, your probes will become identical. Plan to practice for one or two hours each day. It takes most people at least twelve hours of practice in order to be so consistent with their probes that they can hear the slight difference when the circuit is resonant.

For reference you may wish to use a piano. The starting sound when you touch down on the skin should be F, an octave and a half above middle C. The sound rises to a C as you press to the knuckle bone, then slips back to B, then back up to C-sharp as you complete the second half of your first probe. If you have a multitester you can connect it in series with the handhold or probe: the current should rise to about 50 microamps. If you have a frequency counter the frequency should reach 1000 Hz. You should arrive at C-sharp just before the probe becomes painful.

Two things change the sound of the probes even when your technique doesn't change.

1. The patch of skin chosen for probing will change its properties. The more it is used, the redder it gets and the higher the sound goes when you probe. Move to a nearby location, such as the edge of the patch, when the sound is too high to begin with, rather than adjusting the potentiometer.
2. Your body has cycles which make the sound go noticeably higher and lower. If you are getting strangely higher sounds for identical probes, stop and only probe every five minutes until you think the sound has gone down to standard. This could take five to twenty minutes. Learn this higher sound so you can avoid testing during this period.

You may also find times when it is impossible to reach the necessary sound without pressing so hard it causes pain. You may adjust the potentiometer if that helps.

All tests are momentary.

This means less than one second. It is tempting to hold the probe to your skin and just listen to the sound go up and down, but if you prolong the test you must let your body rest ten minutes, each time, before resuming probe practice!

For our purposes, it is not necessary to locate acupuncture points.

Resonance

The information you are seeking is whether or not there is *resonance*, or *feedback oscillation*, in the circuit. If there is the test is **YES** (positive). You hear resonance by comparing the second probe to the first. You can never hear resonance on the first probe, for reasons that are technical and beyond the scope of this book. You are not merely comparing pitch in the two probes. During resonance a higher pitch is reached faster; it seems to want to go infinitely high.

Remember that more electricity flows, and the pitch gets higher, as your skin reddens or your body changes cycle. These effects are not resonance.

Resonance is a small extra hum at the high end of the probe. As soon as you hear it, stop probing. Your body needs a short recovery time (10 to 20 seconds) after every resonant probe. The longer the resonant probe, the longer the recovery time to reach the standard level again.

Using musical notes, here is a NO (negative result): F-C-B-C# (first probe) F-C-B-C# (compare, it is the same sound). Here is a YES (positive) result: F-C-B-C# (first probe) F-D (stop quickly because you heard resonance). In between the first and second probe a test substance will be switched in as described in lessons below.

It is not possible to produce a resonant sound by pressing harder on the skin, although you can make the pitch go higher. To avoid confusion it is important to practice making probes of the same pressure. (Practice getting the F-C-B-C# tune.)

Making Pure Water for Testing Purposes

Since the water you purchase is likely to have solvents in it and since your tap water may be polluted with heavy metals and since your (or a store's) filtration system may be clogged, it is important to make your own pure water.

Purchase a “filter pitcher” made of hard, opaque plastic, not the clear or flexible variety (see Sources). Fill the pitcher with cold tap water, only, not reverse osmosis, distilled, or any other water, since solvents do not filter out as easily as heavy metals. The filter should be made of carbon only. To make test substances, use fresh water in the pitcher and pour.

If your water has lead, copper or cadmium from corroded plumbing, the filter will clog in five days of normal use. So use this pitcher sparingly, just for making test substances and for operating the Syncrometer.

Lesson One

Purpose: To identify the sound of resonance in the circuit.

Materials: Potentized (homeopathic) solutions. Prepare these as follows: find three medium-sized vitamin bottles, glass or plastic, with non-metal lids. Remove any shreds of paper sticking to the rim. Rinse well with cold tap water. Then rinse again with filtered water.

Pour filtered water into the first bottle to a depth of about ½ inch. Add about 50 little grains of table salt using the tip of a plastic knife. This is a “pinch.” Replace the lid. Make sure the outside is clean. If not, rinse and dry. Now shake hard, holding it snugly in your hand. Count your shakes; shake 120 to 150 times. Use elbow motion so each shake covers about an eight inch distance. Shaken samples are different from unshaken ones, that's why this is so important. When done label the bottle on its side and lid: SALT #1. Wash your hands (without soap).

Next, pour about the same amount of filtered water into the second and third bottles. Open SALT #1 and pour a small amount, like 1/4 to 1/2 of a teaspoon (do not use a spoon) into the second and third bottles. Close all bottles. Now shake the second bottle the same as the first. Clean it and label it SALT #2. Do the same for the third bottle. Label it SALT #2 also and set aside for Lesson Four.

These two solutions have unique properties. SALT #1 always resonates. Use #1 to train your ear. SALT #2 shouldn't resonate. Use #2 to hear when you (your body's internal resistance) have returned to the standard level.

1. Turn the Syncrometer ON.
2. Place the SALT #2 bottle on the right test plate.
3. Start with the plate switch OFF.
4. Make your first probe (F-C-B-C#).
5. Flip the plate switch ON, taking only one half second. Brace your hand when switching so it is a fast, smooth, operation.
6. Make the second probe (F-C-B-C#). Total probe time is 2½ seconds. Count it out, “a thousand and one (done with first probe) a thou. (done with switching) a thousand and one (done with second probe).”
7. The result should be a NO (negative). If the second probe sounds even a little higher you are not at the standard level. Wait a few more seconds and go back to step 3.
8. If the first result was NO, remove SALT #2 and put SALT #1 on. Put the test plate switch back to OFF and repeat the test. This time the circuit was resonating. Learn to hear the

difference between the last two probes so that a resonant probe can be terminated early (reducing rest time).

9. The skin must now be rested. When SALT #1 is placed in the circuit there is always resonance whether you hear it or not. Therefore, always take the time to rest the skin.
10. How can you be sure that the skin is rested enough? Any time you want to know whether you have returned to the standard level, you may simply test yourself to SALT #2 (just do steps 3 through 6). While you are learning, let your piano also help you to learn the standard level (starts exactly at F). If you do not rest and you resonate the circuit before returning to the standard level, the results will become aberrant and useless. The briefer you keep the resonant probe, the faster you return to the standard level. Don't exceed one half second when probing SALT #1. Hopefully you will soon hear resonance within that time.

This lesson teaches you to first listen to the empty plate, then to SALT #2, to check for standard state. Then to compare the empty plate to SALT #1 to check for resonance. In later lessons we assume you checked for your standard level or are quite sure of it.

Practice hearing resonance in your circuit every day.

White Blood Cells

Checking for resonance between your white blood cells and a toxin is the single most important test you can make.

Your white blood cells are your immune system's first line of defense. In addition to making antibodies, interferon, interleukins, and other attack chemicals, they also “eat” foreign substances in your body and eliminate them. By simply checking your white blood cells for toxins or intruders you save having to check every other tissue in your body. Because no matter where the foreign substance is, chances are some white blood cells are working to remove it.

It took me two years to find this ideal indicator, but it is not perfect. **Tapeworms are a notable exception.** They can be encysted in a particular tissue which will test positive, while the white blood cells continue to test negative. Also, when bacteria and viruses are in their latent form, they do not show up in the white blood cells. Fortunately, in their active form they show up quite nicely. **Freon** is an example of a toxin that is seldom found in the white blood cells; but typically, the white blood cells are excellent indicators of toxins.

Making a White Blood Cell Specimen

Obtain an empty vitamin bottle with a flat plastic lid and a roll of clear tape. The white blood cells are not going into the bottle, they are going on the bottle. The bottle simply makes them easy to handle. Rinse and dry the bottle. Make a second specimen on a clean glass slide if available. Squeeze an oil gland on your face or body to obtain a ribbon of whitish matter (not mixed with blood). Pick this up with the back of your thumb nail. Spread it in a single, small streak across the lid of the bottle or the center of the glass slide. Stick a strip of clear tape over the streak on the bottle cap so that the ends hang over the edge and you can easily see where the specimen was put (see photo). Wipe the lid beside the tape to make sure all white blood cells are covered. For the slide, apply a drop of balsam and a cover slip (see *Sources*). Both types of preparation will give you identical results. The bottle type of white blood cell specimen is used by standing it on its lid (upside down) so that the specimen is next to the plate. The lid is used because it is flat, whereas the bottom of most bottles is not.

Lesson Two

Purpose: To add a white blood cell specimen to the circuit and compare sound.

Method:

1. Turn the Syncrometer ON.
2. Start with test plate switch OFF.
3. Place the white blood cell specimen on the left plate. Place some junk food in a plastic baggy on the right plate.
4. Eat some of the junk food.
5. After ½minute listen to the current. Flip the plate switch ON and listen again.
6. If the circuit is now resonating, the junk food is already in your white blood cells. It is toxic.

Take vitamin C and a B-50 complex to clear it rapidly; it may have had propyl alcohol or benzene in it. Test every 5 minutes afterward to see how long it takes to clear out.



Fig. 81 Bottle with white blood cells taped on top.

Lesson Three

Purpose: To determine the purity of the filtered water you are making.

Method: Pour a few tsp. of filtered water into a bottle or plastic bag. Place your white blood cell specimen on one plate and the water sample on the other. Listen to your circuit. Taste your filtered water. After ½minute, listen to your circuit again, just as in Lesson Two. If it appears in your white blood cells at any time you can conclude the water is not pure. You must have pure water available to you before continuing.

Lesson Four

Purpose: To determine your percent accuracy in listening for resonance.

Materials: The SALT #1 and SALT #2 solutions you made for Lesson One.

Method: Move the SALT #1 and SALT #2 labels to the bottom of the bottles so you can not tell which bottle is which.

1. Turn the Syncrometer ON.
2. Start with the test switch OFF.
3. Mix the bottles up, select one at random, and place it on the right plate.
4. Listen to the current.
5. Flip the plate switch ON and make your second probe.
6. Resonance indicates a SALT #1, no resonance indicates SALT #2. Check the bottom. Remember to rest after the SALT #1, whether or not you heard resonance.
7. Repeat steps 3 through 5 a number of times. Work toward getting three out of three correct. Practice every day.

Trouble shooting:

a) If you repeat this experiment and you keep getting the same bottles "wrong", start over. You may have accidentally contaminated or mislabeled the outside of the bottle, or switched bottle caps.

b) If you get different bottles wrong each time, the plates may be contaminated. Wash the outside of the bottles and rinse with filtered water and dry. Wipe the plates very gently too, with filtered water and dry. Or replace the plates.

c) If all the bottles read the same, your filtered water is polluted. Change the filter.

Preparing Test Substances

It is possible to prepare dry substances for testing such as a piece of lead or grains of pesticide. They can simply be put in a plastic bag and placed on the test plate. However, I prefer to place a small amount (the size of a pea) of the substance into a ½ ounce bottle of filtered water. There will be many chemical reactions between the substance and the water to produce a number of test substances all contained in one bottle. This simulates the situation in the body.

Within the body, where salt and water are abundant, similar reactions may occur between elements and water. For example, a strip of pure (99.9% pure) copper placed in filtered water might yield copper hydroxide, cuprous oxide, cupric oxide, copper dioxide, and so forth. These may be similar to some of the reaction products one might expect in the body, coming from a copper IUD, copper bracelet or the copper from metal tooth fillings. Since the electronic properties of elemental copper are not the same as for copper compounds, we would miss many test results if we used only dry elemental copper as a test substance.

Impure Test Substances

It is not necessary to have pure test substances. For instance, a tire balancer made of lead can be easily obtained at an auto service station. Leaded gasoline and lead fishing weights also make good test substances for lead. There is a disadvantage, though, to using impure test substances. You are including the extra impurities in your test. If your lead object also has tin in it, you are also testing for tin. Usually, you can infer the truth by some careful maneuvering. If you have searched your kidneys for leaded gasoline, fishing weights and tire balancers and all 3 are resonant with your kidneys, you may infer that you have lead in your kidneys, since the common element in all 3 items is lead. (You will learn how to specify a tissue, such as your kidneys, later.)

Using pure chemicals gives you certainty in your results. You can purchase pure chemicals from chemical supply companies (see *Sources*). Your pharmacy, a child's chemistry set, a paint store, or biological supply company can also supply some.

The biggest repository of all toxic substances is the grocery store and your own home.

You can make test substances out of your hand soap, water softener salt, and laundry detergent by putting a small amount (1/16 tsp.) in a ½ounce glass bottle and adding about 2 tsp. filtered water. (Or for quick testing just put them dry or wet in a sealed plastic baggy.) Always use a plastic spoon.

Here are some suggestions for finding sources of toxic products to make your own toxic element test. If the product is a solid, place a small amount in a plastic bag and add a tablespoon of filtered water to get a temporary test product. For permanent use put it in a small amber glass bottle. If the product is a liquid, pour a few drops into a glass bottle and add about 2 tsp. filtered water. Keep all toxic substances in glass bottles for your own safety. Small amber glass dropper bottles can be purchased by the dozen at drug stores (also see *Sources*). Seal your test bottles with tape for safety and to prevent evaporation.

Aflatoxin: scrape the mold off an orange or piece of bread; wash hands afterward.

Acetone: paint supply store or pharmacy.

Arsenic: 1/16 tsp. of arsenate pesticide from a garden shop. A snippet of flypaper.

Aluminum: a piece of aluminum foil (not tin foil) or an aluminum measuring spoon.

Aluminum silicate: a bit of salt that has this free running agent in it.

Asbestos: a small piece of asbestos sheeting, an old furnace gasket, 1/4 inch of a clothes dryer belt that does not say "Made in USA", or a crumb of building material being removed due to its asbestos content (ask a contractor).

Barium: save a few drops from the beverage given clients scheduled for an X-ray. Lipstick that has barium listed in the ingredients.

Benzene: an old can of rubber cement (new supplies do not have it). A tsp. of asphalt crumbs from a driveway.

Beryllium: a piece of coal; a few drops of "coal oil" or lamp oil.

Bismuth: use a few drops of antacid with bismuth in it.

Bromine: bleached "brominated" flour.

Cadmium: scrape a bit off a galvanized nail, paint from a hobby store.

Cesium: scrape the surface of a clear plastic beverage bottle.

CFCs (freon): ask an electronics expert for a squirt from an old aerosol can that used freon as a cleaner. (Squirt into water, outdoors, put the water in a sample bottle.)

Chromate: scrape an old car bumper.

Cobalt: pick out the blue and green crumbs from detergent. A sample of cobalt containing paint should also suffice.

Chlorine: a few drops of pure, old fashioned Clorox.™

Copper: ask your hardware clerk to cut a small fragment off a copper pipe of the purest variety or a ¼ inch of pure copper wire.

Ergot: a teaspoon of rye grains, or rye bread. Add grain alcohol to preserve.

Ether: automotive supply store (engine starting fluid).

Ethyl alcohol (grain alcohol): the purest "drinking" alcohol available. Everclear™ in the United States, Protec™ (potable) in Mexico.

Fiberglass: snip a fragment from insulation.

Fluoride: ask a dentist for a small sample.

Formaldehyde: purchase 37% at a pharmacy. Use a few drops only for your sample.

Gasoline: gas station (leaded and unleaded).

Gold: ask a jeweler for a crumb of the purest gold available or use a wedding ring.

Kerosene: gas station.

Lead: wheel balancers from a gas station, weights used on fishing lines, lead solder from electronics shop.

Mercury: a mercury thermometer (there is no need to break it), piece of amalgam tooth filling.

Methanol: paint supply store (wood alcohol).

Nickel: a nickel plated paper clip, a washed coin.

Patulin (apple mold): cut a sliver of washed, bruised apple.

PCB: water from a quarry known to be polluted with it (a builder or electrical worker may know a source).

Platinum: ask a jeweler for a small specimen.

Propyl alcohol: rubbing alcohol from pharmacy (same as propanol or isopropanol). Use a few drops only, discard the rest. Do not save it.

PVC: glue that lists it in the ingredients (polyvinyl chloride).

Radon: leave a glass jar with an inch of filtered water in it standing open in a basement that tested positive to radon using a kit. After 3 days, close the jar. Pour about 2 tsp. of this water into your specimen bottle.

Silicon: a dab of silicon caulk.

Silver: ask a jeweler for a crumb of very pure silver. Silver solder can be found in electronics shops. Snip the edge of a very old silver coin.

Sorghum mold: 1/8 tsp. sorghum syrup.

Styrene: a chip of styrofoam.

Tantalum: purchase a tantalum drill bit from hardware store.

Tin: scrape a tin bucket at a farm supply. Tin solder. Ask a dentist for a piece of pure tin (used to make braces).

Titanium: purchase a titanium drill bit from a hardware store.

Toluene: a tube of glue that lists toluene as an ingredient.

Tungsten: the filament in a burned out light bulb.

Vanadium: hold a piece of dampened paper towel over a gas stove burner as it is turned on. Cut a bit of this paper into your specimen bottle and add 2 tsp. filtered water.

Xylene: paint store or pharmacy.

Zearalenone: combine leftover crumbs of three kinds of corn chips and three kinds of popcorn.

This list gets you off to a good start. Since few of these specimens are pure, there is a degree of logic that you must apply in most cases. If you are testing for barium in your breast, a positive result would mean that a barium-containing lipstick tests positive and a barium-free lipstick is negative.

A chemistry set for hobbyists is a wonderful addition to your collection of test specimens. Remember, however, the assumptions and errors in such a system. A test for silver using silver chloride might be negative. This does not mean there is no silver present in your body; it only means there is no silver chloride present in the tissue you tested.

You are bound to miss some toxins; don't let this discourage you. There is more than enough that you can find.

The most fruitful kind of testing is, probably, the use of household products themselves as test substances. The soaps, colognes, mouthwash, toothpaste, shampoo, cosmetics, breads, dairy products, juices and cereals can all be made into test specimens. Put about 1/8 tsp. of the product in a small glass bottle, add 2 tsp. filtered water and ¼ tsp. grain alcohol to preserve it. For temporary purposes use a plastic baggy and water only. If you test positive to your household products in your white blood cells you shouldn't use them, even if you can not identify the exact toxin.

For a list of toxins and solvents I use, see page 571. To order pure substances see *Sources* for “chemicals for testing.”

Making Organ Specimens

To test for toxic elements or parasites in a particular organ such as the liver or skin, you will need either a fresh or frozen sample of the organ or a prepared microscope slide of this organ. Meat purchased from a grocery store, fresh or frozen, provides you with a variety of organ specimens. Chicken, turkey, beef or pork organs all give the same results. You may purchase chicken gizzards for a sample of stomach, beef liver for liver, pork brains for brain, beef steak for muscle, throat sweet breads for thymus, tripe for stomach lining. Other organs may be ordered from a meat packing plant.

Trim the marrow out of a bone slice to get bone marrow. Scrub the bone slice with hot water to free it of marrow to get a bone specimen. Choose a single piece of meat sample, rinse it and place it in a plastic bag. You may freeze it. To make a durable unfrozen sample, cut a small piece, the size of a pea, and place it in an amber glass bottle (½oz.). Cover with two tsp. filtered water and ¼ tsp. of grain alcohol (pure vodka will do) to preserve it. These need not be refrigerated but if decay starts, make a fresh specimen.

Pork brains from the grocery store may be dissected to give you the different parts of the brain. Chicken livers often have an attached gallbladder or piece of bile duct, giving you that extra organ. Grocery store “lites” provides you with lung tissue. For kidney, snip a piece off pork or beef kidney. Beef liver may supply you with a blood sample, too. Always wash hands and rinse with grain alcohol after handling raw meat.

I use ½ oz amber glass bottles with bakelite caps (see Sources) to hold specimens. However, plastic bags or other containers would suffice. After closing, each bottle is sealed with a Parafilm^{TM} strip to avoid accidental loosening of the cap. You may use masking tape.

To make a specimen of skin, use hangnail bits and skin peeled from a callous, not a wart. A few shreds will do. Remember, they must be very close to the test plate when in use; add 2 tsp. filtered water and ¼ tsp. grain alcohol.

Making a Complete Set of Tissue Samples

My original complete set was made from a frozen fish. As it thawed, different organs were cut away and small pieces placed in bottles for preserving in filtered water and grain alcohol. In this way, organs not available from the grocery store could be obtained. The piece of intestine closest to the anus corresponds to our colon, the part closest to the stomach corresponds to our duodenum. The 2 layers of the stomach and different layers of the eye, the optic nerve and spinal cord were obtained this way.

Another complete set of tissue samples were obtained from a freshly killed steer at a slaughter house. In this way the 4 chambers of the heart were obtained, the lung, trachea, aorta, vein, pancreas, and so forth.

Purchasing a Complete Set of Tissue Samples

Slides of tissues, unstained or stained in a variety of ways for microscope study give identical results to the preparations made by yourself in the ways already described. This fact opens the entire catalog of tissue types for your further study. See *Sources* for places that supply them.



Fig. 82 Some purchased parasite and tissue slides.

You now have a set of organ samples, either fresh, frozen, preserved or on slides. You also have a set of test substances, whether chemical compounds, or elements, or products. Your goal is to search in your own organs and body tissues for the substances that may be robbing you of health.

Keeping yourself healthy will soon be an easy, daily routine.

Body Fluid Specimens

Each of these fluids should be prepared by putting about ¼ tsp. in a ½oz amber glass bottle. Add about 2 tsp. filtered water and ¼ tsp. grain alcohol for preservation. Undiluted specimens do not work for reasons that are technical and beyond the scope of this book. It is important *not* to shake the specimen, but to mix gently.

Urine. It is desired to have a pure, uninfected urine sample as a tissue specimen. Since this cannot be proved with certainty, obtain several urine samples from different persons whom you believe to be healthy and make several test specimens in order to compare results. Label your specimens Urine A (child), Urine B (woman), Urine C (mine), and so forth.

Semen. A sample from a condom is adequate. Aged specimens (sent by mail, unpreserved and unrefrigerated) work well also. Use one to ten drops or scrape a small amount with a plastic knife.

Blood. One to ten drops of blood should be used. Clotted or chemically treated blood is satisfactory. A blood smear on a slide is very convenient.

Milk. Cow's milk is too polluted with parasites to be useful. Electronically, a dead specimen is equivalent to a live specimen, so that pasteurization of the milk does not help. A human milk specimen is preferred.

Saliva. Use your own, if you have deparasitized yourself and test negative to various fluke stages. Otherwise find a well friend or child.

Specifying a tissue is the most powerful investigative technique in your arsenal. Any of your tissue samples can be tested for any of your toxic substances.

You Can Now Test Three Different Ways!

When you test with a substance on one plate and nothing on the other, you are searching your entire body for that substance. Such a test is not very sensitive.

By putting a tissue sample on the other plate you are testing for the substance specifically in that tissue, and this is much more sensitive. The tissue need not be the white blood cells. To find mercury in your kidneys you would use a mercury sample on one plate, and a kidney sample on the other. The technique is the same as when you use white blood cells.

If you put a substance on each plate, a resonating circuit means the two samples have something in common. For example, if you have mercury on one plate and some dental floss on the other, a positive result indicates mercury in the floss.

Lesson Five

Purpose: To watch substances travel through your body.

Materials: Prepare a pint of brown sugar solution (white sugar has propyl alcohol pollution) using filtered water. Use about 1 tsp. brown sugar, 1/8 tsp. vitamin C (to detoxify sorghum mold), and a pint of filtered water. Do not shake it; gently mix. Make a sample bottle by pouring about ½inch into a clean used vitamin bottle. Rinse and dry the outside of the sample bottle. Finally wash your hands with plain water.

Method:

1. Test your skin for the presence of brown sugar, using the newly made sample bottle and your skin specimen. It should not be there (resonate) yet.
2. Prepare a paper applicator by tearing the corner from a white unfragranced paper towel. Fold it to make a wick.
3. Dip the paper wick in the pint of sugar water and apply it to the skin of your inner arm where you can rub freely.

Rub it in vigorously for about 10 seconds (otherwise it takes minutes to absorb). Leave the shredded wick on the skin and tape it down with a piece of clear tape about 4 inches long (this increases the time you have to work). Quickly wash your fingers.

4. Place your skin tissue specimen on one plate and the sugar specimen bottle on the other plate.
5. Probe for resonance every 5 seconds. As soon as you hear resonance, implying that the skin has absorbed the sugar solution (which may take a full minute), replace the skin specimen with one of liver and listen for resonance again. There should be none, yet.
6. Alternate between the skin and liver. Soon the skin will be clear and the liver will resonate. Also check the pancreas and muscles to see how quickly sugar arrives there.
7. Check white blood cells and kidneys. It should not appear here (unless it is polluted with a toxin).
8. After five to ten minutes the sugar will be gone from all of these tissues and your experiment is ended. Wash your arm with plain water.

> Notice that you have only a few minutes to get all your testing done after the skin has absorbed the test substances.

Lesson Six

Purpose: To verify the propyl alcohol and benzene lists.

Method: We will use the Syncrometer to test for a toxin in a product. Assemble the products named in the propyl alcohol list (page 335) and benzene list (page 354)...as many as you can find. Also make sample bottles of benzene and propyl alcohol.

1. Place the propyl alcohol test substance on one plate and your products, in turn, on the other.

2. Listen to the current with only one of the plates in the circuit. Then listen with both plates in (the test plate switch ON). This method can detect one part per quadrillion in concentration. It is not as sensitive as the skin test (Lesson Five).
3. Repeat, with the benzene test substance.

Even tiny amounts of solvents are toxic! They must not be consumed or be left in our environment.

I have found that too many unsuspected products test positive to benzene. This is such a global tragedy that people must protect themselves by using their own tests. Rather than assurances, regulatory agencies should provide the consumer with cheap and simple tests (dip sticks and papers so we need not lug our Syncrometers around). Even if some test should fail, not all tests would fail to find an important pollutant like benzene. It would come to public attention much faster than the present debacle has.



1) *Salmonella*, *Shigella*, aflatoxin, ergot, zearalenone, patulin test sticks; 2) ozonizer; 3) Lugol's; 4) vitamin C powder; 5) sodium/potassium salt; 6) fresh powdered herb spices; 7) food zapper; 8) benzene, propyl alcohol, wood alcohol test sticks; 9) heavy metals and lanthanides test sticks.

Fig. 83 Table of the future.

Lesson Seven

Purpose: To test for the presence of aluminum in your brain and your foods.

Materials: An aluminum measuring spoon, a tsp. of free flowing aluminized salt, a square inch of aluminum foil, a package of pork brain from the grocery store, kept frozen. (Other animal sources will do). Or a stained slide of cerebrum, cerebellum or other brain tissue.

Method:

1. Cut a piece of brain tissue (about 1 tsp.) and place in a plastic bag.
2. Place the aluminum samples in separate plastic bags. Add filtered water to each, about 1 tbs. Keep all surfaces and your hands meticulously clean (do not use soap).
3. Place the aluminum sample on one plate and the brain sample on the other plate.
4. Probe for resonance. If the circuit resonates you have aluminum in your brain.
5. If your aluminum specimen actually has cadmium or copper in it, you are also testing for these in your brain. Repeat the aluminum test with other aluminum objects. If they all resonate, you very, very likely have aluminum in your brain. If you can, test yourself to cadmium and copper, separately. If you don't have these in your brain, the aluminum test result is even more likely to be correct.
6. Of course, it would be desirable to have absolute certainty about this. To achieve this, purchase pure aluminum or an Atomic Absorption Standard. These are available from chemical supply companies.

If you do have aluminum in your brain, where is it coming from?

7. Leave your purest aluminum test substance on one plate, and replace the brain sample with these items, testing them one at a time. Remember to rest after each positive result.
    - a teaspoon of cottage cheese or yogurt taken from the top of a container of a foil-capped variety
    - a piece of cream cheese or butter that was wrapped in foil
    - a chip of bar soap or a bit of hand lotion
    - a piece of cake or rolls baked in an aluminum pan
    - a piece of turkey skin or hot dish that was covered with aluminum foil
    - anything baked with baking powder
    - a carbonated beverage from an aluminum can

Alternative Lesson:

To test for dental metal in your tissues. Use a piece of amalgam from an old tooth filling. This tests for the rest of the alloys in amalgam fillings as well as mercury. If you can't get a piece of mercury amalgam, use a mercury thermometer (don't break it, just put the bulb on the plate). Choose tissues like kidney, nerves, brain, liver, in addition to white blood cells.

I have never dissected human tissues and subjected them to confirmatory laboratory tests. It seems reasonable that because skin and tongue are directly provable, that other tissues work similarly.

Testing the Air

Fine particles and gas molecules that are in the air stick to the dust and eventually fall down onto the table, kitchen counter, and other places. Every night a film of dust accumulates, even though you can't see it. To test for air pollutants, gather some dust. Wipe the kitchen table and counter with a dampened piece of paper towel, two inches by two inches square. Place it in a resealable baggie. Do not get old dust, like from the top of the refrigerator or back shelves, because it does not represent the current air quality.

Testing Someone Else

Seat the person comfortably with their hand resting near you. Choose the first knuckle from the middle or first finger just like you do for yourself. Since you are touching this person, you are putting yourself in the circuit with the subject.

To exclude yourself, you need to add inductance to yourself. A coil of about 10 microhenrys, worn next to the skin, works well and is easily made. Obtain insulated wire and wrap 24 turns around a ball point pen (or something about that size), closely spaced. Cut the ends and tape them down securely. Keep it in a plastic bag, even when in your pocket. A commercial inductance of 4.7 microhenrys, worn touching your skin also works well. It can be worn on a string necklace. (Remember to remove the necklace when testing yourself.) The inductance acts as an RF (radio frequency) choke, limiting the alternating current that can flow through you while testing another person.

Test your inductor in this way. Repeat Lesson One with the coil next to your body. No resonance, even to SALT #1, should occur. If it does, make the coil bigger. Remove the inductor when you are not testing others.

Lesson Eight

Purpose: To detect aluminum in the brain of another person.
Materials: same as previous lesson, you wear the inductor.

Method:

1. Place the aluminum sample on one plate and the brain sample on the other plate.
2. Give the other person the handhold. You use the probe. Hold their finger steady in yours.
3. Probe the other person for resonance. The first probe is with only one plate in the circuit. The second is with both plates in the circuit. Resonance implies there is aluminum in the person's brain.

Saliva Testing

This may become your most useful test. The saliva has in it a bit of almost everything toxic that is in you. But it is not the first tissue to carry the HIV virus or a bit of a tapeworm stage. Nevertheless, *Salmonella* in your liver, mercury in your kidneys, aluminum in the brain all show up in the saliva, too. And saliva can be sent by mail or stored in the refrigerator. It should be frozen for long storage to prevent mold invasion. Or it may have grain alcohol added to preserve it. This test is not as sensitive as having the person present in the circuit, though.

To make a saliva specimen, place a two inch square piece of white, unfragranced paper towel (tear, don't cut) in a lightweight resealable baggy. Hold the open baggy near your mouth. Don't touch the paper towel with your fingers. Drool or spit onto the paper towel until half of it is damp. Zip it shut. Before testing, add enough filtered water to dampen the whole piece of paper.

Lesson Nine

Purpose: To search for shingles or *Herpes*.

Materials: A saliva specimen from the person being tested; they may be thousands of miles away. Also a specimen of the virus. This can be obtained from someone else's lesions—one droplet is enough, picked up on a bit of paper towel. The whole thing, towel and all, can be pushed into a glass bottle for preserving. Water and alcohol should be added. It can also be put on a slide, *Herpes, homemade*. A homeopathic preparation of the virus does not give accurate results for this kind of testing, due to the additional frequency imposed on it by potentizing. (However, homeopathic preparations can be used if the potency matches the tissue frequency where it resides. Hopefully, some way of using homeopathic sources will soon be found.)

Method: Place the saliva specimen in its unopened baggy on one plate. You may wish to open it briefly, though, to add enough filtered water to wet all the paper and add ¼ tsp. grain alcohol to sterilize or preserve it.

Place the virus specimen on the other plate and test as usual (like Lesson Six). A positive result means the person has active *Herpes*.

The main disadvantage of saliva testing is that you do not know which tissue has the pathogen or the toxin. You can only conclude that it is present. Usually this is enough information to carry out a corrective program.

Surrogate Testing

Although saliva testing is so easy, it is also possible to use an adult as a surrogate when testing a baby or pet. The pet or baby is held on the lap of the surrogate. A large pet may sit in front of the person. The handhold is held by the surrogate and pressed firmly against the body of the baby or pet. It can be laid flat against the arm, body or leg of a baby and held in place firmly by the whole hand of the adult. The paper covering should be wet. For a pet, the end is held firmly pressed against the skin, such as between the front legs or on the belly. The other hand of the adult is used for testing in the usual way. The adult must wear an inductor for surrogate testing as well as you, tester.

An ill or bedridden person may be tested without inconvenience or stress. He or she rests their whole hand on the skin of your leg, just above the knee. A wet piece of paper towel, about 4 inches by 4 inches is placed on your leg, to make better contact. You must use an inductor for yourself with this method. You may now proceed to probe on your hand instead of the ill person's.

Lesson Ten

Purpose: To test for cancer.

Materials: Ortho-phospho-tyrosine. Here are four ways to obtain some:

1. Order a pure sample from a chemical company (see *Sources*). Place a few milligrams (it need not be weighed) in a small glass bottle, add 2 tsp. filtered water and ¼ tsp. grain alcohol.
2. All persons with cancer have ortho-phospho-tyrosine in their urine as well as in the cancerous tissue. It is seldom found in other body fluids. Obtain a urine specimen from a friend who has active cancer. Freeze it if you can't prepare it immediately. Keep such specimens well marked in an additional sealed plastic bag. Persons who have recently been treated clinically for cancer are much less likely to have ortho-phospho-tyrosine in the urine.

   Urine cannot be considered a chemical in the same way as a sugar or salt solution. Urine is a tissue and has its own resonant frequency as do our other tissues. If combined with another tissue on the test plates, it will not resonate as if a solution of pure ortho-phospho-tyrosine were used. To use urine as an ortho-phospho-tyrosine specimen, you must:

   a) Pour a few drops of urine into your specimen bottle
   b) Add about 2 tsp. of filtered water
   c) Add a few drops of grain alcohol

   Gently mix, do not shake. Rinse and dry the outside of the bottle. Label it “urine/cancer”.

3. Cancer victims also have other growth factors being produced in their bodies. These are the same as can be found in mother's milk—for example, epidermal growth factor and insulin-like growth factor. Obtain a sample of mother's milk and use it to make another test substance for cancer. A few drops is enough.
4. There is still another way to prepare an ortho-phospho-tyrosine test sample. Common snails from a fish tank or outdoor snails are the natural hosts for *Fasciolopsis buskii* (human intestinal fluke) stages. The stages will produce ortho-phospho-tyrosine when the snails are fed fish food polluted with propyl alcohol. Over half the fish food cans I purchased had propyl alcohol pollution. Buy several brands of fish food. Test them for propyl alcohol and benzene. Obtain some snails, put them in a tank, feed them propyl alcohol polluted fish food. (Feed a separate group of snails benzene polluted fish food to obtain samples of HIV.) After two days put each snail in a zipped plastic bag, and test them individually against someone diagnosed with cancer or their saliva. The snails that the person tests positive to have ortho-phospho-tyrosine. Put these snails in the freezer to kill them humanely, then crush them and place in a specimen bottle with 50% grain alcohol to preserve. The bottles can be kept sealed and at room temperature.

   Similarly, your benzene snails can be tested against someone known to be HIV positive. Any snails that test positive can be used to prepare an HIV test specimen in the same way. The fish food must be tested for both benzene and propyl alcohol pollution, and separated appropriately, or you run the risk of making specimens that have both ortho-phospho-tyrosine and HIV.

Method:

1. Test for cancer by placing the test sample you just made (any of the four) on one plate and a white blood cell sample on the other plate.
2. If you resonate with both samples in the circuit you have cancer. Immediately, search for your cancer in your breast, prostate, skin, lungs, colon, and so forth.
3. To be more certain, test yourself to the other kinds of test samples. You should not resonate.

As you know by now, you can confirm the cancer by testing yourself to propyl alcohol and the human intestinal fluke in the liver. You should eliminate propyl alcohol from use, and zap all parasites. Keep testing yourself for cancer until it is gone. It should take less than one hour. Also continue to test yourself for propyl alcohol and the intestinal fluke in the white blood cells; make sure they are gone. Also test yourself for aflatoxin and freon.

Lesson Eleven

Purpose: To test for HIV.

Materials: Purchase a few milligrams of Protein 24 antigen (a piece of the HIV virus core) or the complete HIV virus on a slide (see *Sources*). You may use the vial unopened if only one test specimen is needed. To make more specimens, use about 1 milligram per ½ ounce bottle. Add 2 tsp. filtered water and ¼ tsp. grain alcohol. Or prepare an HIV specimen from snails as described in the previous Lesson.

Method: Search in the thymus (throat sweet breads), vagina and penis for the virus because that is where it will reside almost exclusively for the first year or two. If you don't have those tissue specimens, you could search in urine, blood, saliva, or white blood cells, but only a positive result can be trusted. Also search for the human intestinal fluke and benzene in the thymus. Of course, a positive test in these tissues is very significant. If you are positive, zap parasites immediately. You should test negative in less than an hour. Remove benzene polluted items from your lifestyle. Also test yourself to several varieties of popcorn, brown rice, and corn chips as an indication of zearalenone, which must be eliminated in order to get well. Follow up on yourself every few days to be sure your new found health is continuing. Test yourself for freon.

Lesson Twelve

Purpose: To test for diseases of all kinds.

Materials: Use slides and cultures of disease organisms. Homemade preparations of strep throat, acute mononucleosis, thrush (*Candida*), chicken pox, *Herpes* 1 and 2, eczema, shingles, warts, measles, yeast, fungus, rashes, colds, sore throats, sinus problems, tobacco virus, and so forth can all be made by swabbing or scraping the affected part. A plastic spoon or bit of paper towel works well. Put a small bit on a slide. Add a drop of balsam and a cover slip. Or put the towel in a bottle, add water and alcohol as described previously. Microscope slides can greatly expand your test set (see *Sources*).

Method: Test yourself for a variety of diseases, using your white blood cell specimen first. Then search in organs like the liver, pancreas, spleen. Notice how many of these common illnesses don't “go away” at all. They are alive and well in some organ. They are merely not making you sick!

Lesson Thirteen

To test for AIDS.

Materials: Benzene sample, slides of tissue samples like thymus, liver, pancreas, penis, and vagina. Also a collection of disease specimens such as the ones used in the previous lesson.

Method: Search in the thymus for benzene. If it is positive throughout the day, you are at risk for developing AIDS, although you may not be ill. Search other tissues for benzene. The more tissues with benzene in them the more serious the situation. Immediately search all your body products and foods for benzene.

Stay off benzene polluted items forever.

Tally up the diseases you tested positive for in Lesson Twelve. Test at least ten. If you had more than half positive you already have AIDS. (50% is my standard, you may set your own; an ideal standard for defining a healthy person should be 0% positive.)

Lesson Fourteen

Purpose: To test for aflatoxin.

Materials: Do not try to purchase a pure sample of aflatoxin; it is one of the most potent carcinogens known. Having it on hand would constitute unnecessary hazard, even though the bottle would never need to be opened. Simply make specimens of beer, moldy bread, apple cider vinegar, and any kind of peanuts using a very small amount and adding filtered water and grain alcohol as usual.

Method: Test yourself for these. If you have all of them in your white blood cells and the liver then you very, very probably have aflatoxin built up. Next, test your daily foods for their presence in your white blood cells. Those that test positive must be further tested for aflatoxin. Notice the effect of vitamin C on aflatoxin in your liver. Find a time when your liver is positive to aflatoxin (eat a few roasted peanuts from a health food store and wait ten minutes). Take 1 gram vitamin C in a glass of water. Check yourself for aflatoxin every five minutes. Does it clear? If not, take 5 or 10 grams vitamin C. How long does it take?

Lesson Fifteen

Purpose: To test for parasites.

Method: If you test positive to your pet's saliva, you have something in common–a parasite, no doubt. You must search your muscles and liver for these, not saliva or white blood cells, because they are seldom seen in these. Zap yourself for parasites until you no longer test positive to your pets' saliva.

Tapeworms and tapeworm stages can not (and should not) be killed with a regular frequency generator. Each segment, and probably each scolex in a cysticercus has its own frequency and might disperse if your generator misses it. Only zapping kills all and is safe for tapeworms.

Be sure to treat your pet on a daily basis with the pet parasite program.

Lesson Sixteen

Purpose: To test for fluke disease.

A small number of intestinal flukes resident in the intestine may not give you any noticeable symptoms. Similarly, sheep liver flukes resident in the liver and pancreatic flukes in the pancreas may not cause noticeable symptoms. Their eggs are shed through the organ ducts to the intestine and out with the bowel movement. They hatch and go through various stages of development outdoors and in other animals. But if you become the total host so that various stages are developing in your organs, you have what I term *fluke disease*. I have found that cancer, HIV, diabetes, endometriosis, Hodgkin's disease, Alzheimer's disease, lupus, MS and "universal allergy syndrome" are examples of fluke disease.

You can test for fluke disease in two ways: electronically and by microscope observation.

Materials: Cultures or slides of flukes and fluke stages from a biological supply company (see *Sources*) including eggs, miracidia, redia, cercaria, metacercaria. Body fluid specimens to help you locate them for observation under a microscope.

Method: Test for fluke stages in your white blood cells first. If you have any fluke stages in your white blood cells you may wish to see them with your own eyes. To do this, you must first locate them. Place your body fluid samples on one plate, your parasite stages on the other plate, and test for as many as you were able to procure, besides adults. After finding a stage electronically, you stand a better chance of finding it physically with a microscope.

Lesson Seventeen

Purpose: To see how sensitive your measurements can be. (How much of a substance must be present for you to get a positive result?)

Materials: filtered water, salt, glass cup measure, 13 new glass bottles that hold at least ¼ cup, 14 new plastic teaspoons, Your skin tissue sample, paper towel.

Method: Some of the best measurement systems available today are immunological (such as an ELISA assay) and can detect as little as 100 fg/ml (femtograms per milliliter). A milliliter is about as big as a pea, and a femtogram is 1/1,000,000,000,000,000th (10^{-15}) of a gram!

1. Rinse the glass cup measure with filtered water and put one half teaspoon of table salt in it. Fill to one cup, stirring with a plastic spoon. What concentration is this? A teaspoon is about 5 grams, a cup is about 230 ml (milliliters), therefore the starting concentration is about 2½(2.5) gm per 230 ml, or .01 gm/ml (we will discuss the amount of error later).
2. Label one clean plastic spoon "water" and use it to put nine spoonfuls of filtered water in a clean glass bottle. Use another plastic spoon to transfer one spoonful of the .01 gm/ml salt solution in the cup measure to the glass bottle, stir, then discard the spoon. The glass bottle now has a 1 in 10 dilution, and its concentration is one tenth the original, or .001 gm/ml.
3. Use the "water" spoon to put nine spoonfuls of filtered water in bottle #2. Use a new spoon to transfer a spoonful of salt solution from bottle #1 to bottle #2 and stir briefly (never shake). Label bottle #2 ".0001 gm/ml".
4. Repeat with remaining bottles. Bottle #13 would therefore be labeled ".000000000000001 gm/ml." This is 10^{-15} gm/ml, or 1 femtogram/ml.
5. Do the skin test with water from bottle #13 as in Lesson Five. If you can detect this, you are one hundred times as sensitive as an ELISA assay (and you should make a bottle #14 and continue if you are curious how good your sensitivity can get). If you can not, try to detect water from bottle #12 (ten times as sensitive as ELISA). Continue until you reach a bottle you can detect.

Calculate the error for your experiment by assuming you could be off by as much as 10% when measuring the salt and water adding up to 20% error in each of the 13 dilutions. This is a total error in bottle #13 of 280%, or at most a factor of 3. So bottle #13 could be anywhere from 0.33 to 3 femtogram/ml. If you can detect water from bottle #13, you are definitely more sensitive then an ELISA, in spite of your crude utensils and inexpensive equipment! Note that the starting error of using 2.5 gm instead of 2.3 gm only adds another 10% error.

If you want to calculate how many salt molecules you can detect, select the concentration at the limit of your detection, and put 2 drops on a square inch of paper towel and rub into your skin. Assume one drop can be absorbed. If you can detect water from bottle #13, you have detected 510,000 molecules (10^{-15} fg/ml divided by 58.5 gm/M multiplied by $6.02x10^{23}$ molecules/M divided by 20 drops/ml). Water in bottle #12 would therefore have 10 times as many molecules in one drop, and so forth. Even if your error is as much as a factor of 2 (100%), you can still get a good idea of what you can measure.

Atomic absorption standards start at exact concentrations; it is easy to make a more exact dilution series with them. When testing for iridium chloride by this skin test method, I was able to detect 3025 molecules!

Troubleshooting:

Always extend your set until you get a negative result (this should happen by at least bottle #18). If you always “detect” salt, then you shook the bottle!

Never try to reuse a bottle if you spill when pouring into it. Get another new bottle.

Sensitivity of Pollutant-In-Product Testing

Get some slides of *Salmonellas* and *Shigellas* and find some milk that tests positive to at least one. Make a dilution series of the milk up to bottle #14, being careful not to shake the bottles. Start with 2 drops of milk in bottle #1. Use an eye dropper to deliver 2 drops to subsequent bottles. Begin testing at bottle #14, using the slide that tested positive. You will learn to search by frequency later. My sensitivity was routinely around bottle #12, for a variety of pathogens. It was the same for toxic elements starting with standard solutions, about 1000 μg/ml, showing this method is less sensitive than skin testing.

Microscopy Lesson

Purpose: To *observe* fluke stages in saliva and urine with a microscope.

Materials:

a. A low power microscope. High power is not needed. A total of 100x magnification is satisfactory for the four common flukes, *Fasciolopsis*, *sheep liver fluke*, *human liver fluke* and *pancreatic fluke*.
b. Glass slides and coverslips.
c. A disposable eye dropper.

PRECLEANED
MICROSCOPE SLIDES
PLAIN GLASS
WARD'S
GLASS SLIDES

Fig. 84 Microscope, slides and coverslips.

d. For sanitation purposes (wiping table tops, slides, microscope and your hands) a 50% to 70% alcohol solution (not rubbing alcohol!) is best. Dilute 95% grain alcohol 7 parts alcohol plus 3 parts water. Vodka or 76% grain alcohol can be used undiluted.

e. Formaldehyde, 20%. Formaldehyde 37% is commonly available at pharmacies. Dilute this with equal parts of filtered water to get 18½%, which is close enough to 20%, for the purpose of "fixing" (killing) the specimens. Store in a glass bottle in the garage, away from sunlight. Label. Specimens that are fixed properly do not lose their life-like appearance.

f Iodine solution. This is only useful for the urine specimens. Lugol's iodine and tincture of iodine are both useful. Ask a pharmacist to prepare *Lugol's Iodine Solution* for you, as follows:

- 44 grams (1½oz) iodine crystals
- 88 grams (3 oz) potassium iodide crystals

Dissolve both in 1 liter (quart) filtered water. This may take a day of frequent shaking.

Method for saliva:

1. Pour the 20% formaldehyde into a small amber bottle or other receptacle to a depth of about 1/8 inch. Keep tightly closed.
2. The person to be tested is asked to salivate into the bottle so the organisms are immediately "fixed" without undergoing cooling first. The total volume should be about double the original amount of formaldehyde used. Make a mark on the container so the subject knows how much to produce. The resultant concentration of formaldehyde will be about 10%.
3. Shake the bottle a few times. Set it aside for 24 hours to settle (less if testing is urgent).

4. With a dropper, draw up some of the bottom settlings. Put one drop on a slide and apply a coverslip.
5. View under low power of microscope. Compare objects you observe with specimens obtained on slides from biological supply companies.

Note: Persons with HIV and moderate AIDS will show about one to ten parasite stages per slide. It requires several hours of searching. Persons with HIV and severe AIDS show 10 or more fluke stages per slide; this makes the task of finding them much easier. Persons with terminal untreated cancer have many more fluke stages than relatively well persons.

Method for urine:

1. Prepare bottles of formaldehyde fixative ahead of time. Put about ¼ to ½ inch of 20% formaldehyde in each. Keep tightly closed.
2. Add freshly voided[36] urine from cancer or HIV sufferers to the formaldehyde in approximately equal amounts, resulting in a 10% formaldehyde solution. Shake immediately. Let settle several hours. The sediment has a higher number of fluke stages. Cancer victims with cervical or prostate cancer will show higher numbers of stages in urine than other cancer types.
3. Staining the slide is optional. It helps to outline fluke stages slightly. Prepare Lugol's solution as described above.

    Slides may be stained in either of these two ways:

    - Put a drop of "fixed" urine on a slide. Add a drop of 50% Lugol's (dilute 1:1 with filtered water). Apply coverslip.

---

[36] Urine that has cooled even slightly below body temperature does not show *miracidia* and *redia* in their original shapes.

- Put a drop of “fixed” urine on a slide. Apply coverslip. Add 1 to 3 drops of 50% Lugol’s to edge of coverslip and allow it to seep in.

Note: persons who have been treated for cancer or HIV using any of the known drugs may show only 1 to 2 fluke parasite stages per drop of saliva or urine. For this reason, you may need to search through 20 or more slides to find flukes. Very ill persons may show up to 10 parasites per drop (slide).

Taking Pictures Of What You See

You may be unsure of what you see even if you have the microscope slides of labeled flukes and their stages to study and compare. In real life, they vary so much in shape and size that absolute identification is difficult without experience. Unfortunately in a few hours, just as you are getting proficient, your magnificent specimens will be drying out and unfit for observation. To preserve them longer you can seal the edges by painting around the coverslip with fingernail clear enamel. Or dribble hot sealing wax along the edges and then place them in sealed plastic bags (one per bag). Melt sealing wax in a metal jar lid. Make an applicator from a piece of coat hanger wire bent in the shape of a small square to fit around the coverslip and a handle.

Or take photographs. To take pictures of what you see under the microscope you will need a photomicrographic camera, which costs $200.00 and up (see *Sources*). It is easy to use. Remember to label your pictures so you know which slide they came from.

Even photographs do not scientifically prove identity of parasite stages, but it is very good evidence. Proof would require that the saliva or urine sample could be cultured and seen to produce the known parasite stages.

Using A Frequency Generator

Frequency generators come in all sizes and costs and capabilities. If you can purchase one that reads out the frequency for you in numbers (digital type) and lets you produce a fraction of a kilohertz by turning a dial, it meets your most elementary needs. It should also be possible to set it on positive offset (100% positive) and still give you 5 volts. Then it can be used as a zapper. You should also be able to select a sine wave or square wave.

The advantages of having a frequency generator are that you can do your own diagnosing. You can find, in a few minutes:

1. Which invaders you have by dialing in to their frequencies.
2. At what frequencies you are broadcasting to the world.
3. What frequencies are used by other living things.

The Theory

Every living animal and every cell type produces its own frequencies and responds to these frequencies as well. We may speak of frequencies but we really mean waves, waves of energy. All waves have a frequency associated with them, so it's not really misleading to say frequencies when we really mean waves.

When the animal is alive it produces them, when it is dead it still responds to some of them. It is like the opera singer and the glass goblet. The opera singer produces frequencies in the air. The goblet responds to them because of its structure, not because it's alive. The goblet "picks up" on that particular frequency of sound because its own "resonant" frequency is exactly the same. If the singer sings loud enough the goblet shatters from the vibrations set up in it. An identical goblet, made of plastic, would not have the same resonant frequency.

There is not merely a structural and chemical difference between the living and non living. Living things are transmitting energy of some unique kind. And with your simple device, you will be able to trap this energy. And measure its exact frequency. This is not the same as understanding its makeup and source. We must leave that to others. But we can observe and use our observations to track down bacteria and other parasites. We can track down pollutants. We can measure our health quantitatively and perhaps in the future predict life expectancy.



The Syncrometer at left is attached to the handhold. The frequency generator at right is also clipped to the handhold.

Fig. 85 Setup for finding resonant frequencies.

The Syncrometer traps the frequencies that match the ones in the material on the test plates and delivers them to an audio speaker in a range that you are able to hear. **Instead of test tissues or pathogens, we are now going to use pure test frequencies!** Remarkably, few things have overlapping frequencies, making this technique extremely useful for identification, even without a specimen!

Lesson Eighteen

Purpose: To search for the intestinal fluke in your body by listening to its broadcast frequency at 434 KHz.

Method: Turn on the frequency generator, select a frequency a short distance above the one you are interested in, like 438 KHz, turn the voltage (amplitude) down to less than one volt. Select sine waves. The lead coming from the frequency generator will have two connections, usually red and black (ground). We will not use the black (ground), just tape it out of the way. Pick up the handhold and probe in the usual way. Attach the red lead coming from the generator to your handhold. This makes two wires attached to your handhold. Although there is nothing on the test plates, they must be connected as usual with the switch at OFF (one plate is still ON).

Turn the Syncrometer ON. Probe yourself as usual. Your body's waves are being sent to the capacitor (plate) in the test plate box. The frequency from the Syncrometer is sent there, too. And now the 438 KHz waves from the generator are being sent there as well. Three different frequencies are mingling on the plate! If the two from your body and the generator are the same, the circuit will oscillate, and you will hear resonance. Turn the generator to 437 and probe again. Next, 436.

Sometimes, you can hear the resonance start to build. Continue on.

Next try 435. Then 434.

If your body is emitting a frequency of 434 KHz (coming from a live intestinal fluke inside you) it will be reinforced by the generator's 434 KHz. The reinforcement will put oscillations or resonance in the circuit, the same as you are accustomed to hearing with the Syncrometer. If there was none, you don't have the intestinal fluke anywhere in your body. Confirm this by starting at 430 KHz and working your way up.

If you hear resonance, you do have it. You may wish to verify this independently using a prepared slide of the fluke. Kill your flukes immediately as described in the next lesson.

Lesson Nineteen

Purpose: Killing the intestinal fluke with a frequency generator.

Materials: A frequency generator, two handholds with alligator clip leads for them.

Method: Wrap a single layer of paper towel over each of the two handholds. Wet them under the tap; squeeze out excess water. Clip them to the red and black wires of the frequency generator. (We use both wires for this purpose.) Dial up 434 KHz. Set the amplitude (voltage) at 10 volts. Grasp the handholds in each hand and hold on for three minutes. That is all. You have killed whatever tiny invader has a resonant frequency the same as the setting on the generator. Remember to zap all the stages, too; see *Pathogen Frequencies*.

If your frequency generator has a **positive offset** capability, you can use it like a zapper, and a single session will kill all pathogens, provided it is 100% offset and can give at least 5 volts at this setting. When using this technique, the generator can be set to any frequency from 2 KHz to 800 KHz, and you should go for 7 minutes. But even a small percentage of negative voltage will ruin this effect and do more harm than good! To be certain your generator is set correctly it would be best to observe the output on an oscilloscope.

Experiment with other voltage settings. Notice that less than one volt is also effective.

Lesson Twenty

Purpose: To find the bandwidth of a small living animal.

Materials: A fly, beetle or other insect, Syncrometer, frequency generator.

Discussion: Persons using a Syncrometer might have already tried putting a small insect on one of the plates. The circuit always resonates when you join the circuit at the handhold and probe. Even the tiniest ant placed in a glass bottle or plastic baggy will resonate the circuit. Unless it is too far away from the plate. If it has climbed up the side you will lose the resonance. At least one foot must be touching the bottom of the bottle. If the animal is dead this ceases. Obviously the living thing is affecting the circuit differently before and after death. Is it some kind of a wave form energy? To find its frequency you must add another frequency that will reinforce or interfere with the frequency already on the plate. Adding the generator frequency does just that.

Method: Use the same method as described in the last Lesson; however for an ant or fly, start at 1,000 KHz and proceed upward in big steps like 10 KHz. Use the right test plate which is controlled by the ON-OFF switch. Always listen to the current with the switch OFF, first, then ON. Move the frequency up and repeat. Continue until you hear resonance. Stop immediately. Rest your skin and go back down to the nonresonant frequency region. Move up in smaller steps this time. Repeat and repeat until you feel sure you know just where the resonance begins. But where does it end?

Start testing well above the suspected range taking big steps downward until you reach a resonant frequency. Rest and repeat until you find the upper limit of resonant frequencies. Record the bandwidth, for example, 1009-1112 KHz.

Lesson Twenty One

Purpose: To see if similar living things interfere with each other when put on the plate together.

Materials: Two identical living insects or very small living things.

Method: Find the broadcast range of each one separately and then together on the plate.

Note: Identical living things do not interfere with each others' frequencies.

Lesson Twenty Two

Purpose: To see if different living things interfere with each other when put on the plate together.

Method: Find the lower and upper end of the broadcast range of two different living things, such as a fly and a beetle or 2 kinds of flies or beetles. Then put them on the plate together. Notice there is no resonance in the accustomed range for either of them. They are interfering with each other on the plate.

Now add the 2 lower ends, then the two upper ends. Also subtract the 2 lower ends, then the two upper ends. For example imagine two insects, one with a spectrum of 1000 to 1090 KHz, the other with a range of 1050 to 1190 KHz. Adding the lower ends gives us 2050 KHz. Subtracting the lower ends gives us 50 KHz. Adding the upper ends gives 2280. Subtracting the upper ends gives 100. Now search for resonance at 50, 100, 2050, 2280 KHz. (These last two may be outside the range of your frequency generator. Choose more primitive life forms which have lower frequency bandwidths to stay within your limit.)

Notice that you hear resonance at exactly these frequencies and not above or below them. This is evidence for modulation of the frequencies: namely fusing them together.

Lesson Twenty Three

Purpose: To find your own bandwidth of emitted frequencies.

Materials: A frequency generator that goes up to 10 MHz. If yours only goes to 2 MHz you can still investigate the lower end of your band.

Method: You do not need to put yourself on the plate, since you are already there by being in the circuit at the handhold. However, if you are measuring someone else, they can simply touch the plate with a finger. Attach the frequency generator to the circuit at the handhold.

Since human adults begin to emit at about 1560 KHz, start searching at 1550, going upward in 1 KHz steps until you hear resonance.

Younger or healthier humans start emitting at a lower frequency and sometimes end at a higher frequency. In other words, they broadcast on a wider band.

Very young infants begin their band at about 1520 KHz. Could you ever regain this ability?

Most adults terminate at 9375 KHz

By eliminating molds from my diet, killing as many parasites and removing as many toxins as I became aware of, I have been able to expand my bandwidth from an initial 1562-9457 KHz in 1990 to 1520-9580 KHz in 1994! I hope this challenges you to accomplish a health improvement reflected in an even broader bandwidth for yourself.

Lesson Twenty Four

Purpose: To find the effect of a variety of things on the lower end of your spectrum, such as body temperature, eating, time of day, rainy weather, feeling sick. Notice that you may not change for weeks at a time, then suddenly see a shrinking of your bandwidth. You may assume you have eaten a mold.

Search for mold frequencies from 75 KHz to 295 KHz. Or test in your liver with mold samples. If this is positive go on a mold free diet—watching carefully for mold in your white blood cells. Even after removing the mold from your diet, so that no molds appear in your white blood cells, notice that your bandwidth does not recover. It regularly takes 2-3 weeks for mine to recover.

Surely, this sheds light on the poisonous effect of eating bad food.

Lesson Twenty Five

Purpose: To find an emission spectrum using a saliva sample.

Materials: A regular frequency generator.

Method: Search for the bottom of the resonant frequency band as in the previous lesson.

You may store it in the refrigerator for a few weeks without seeing a change. After that the band begins to shrink.

Lesson Twenty Six

Purpose: To observe the effect of dying on the bandwidth.

Method: Freeze the insect you tested in Lesson Twenty to kill it humanely. Repeat the search for its bandwidth. Note the bandwidth has become very narrow.

Note the bandwidth also depends on the accuracy of your particular frequency generator.

Lesson Twenty Seven

Purpose: To find unknown invaders of your body.

Method: Start at 900 KHz and proceed down to 77 KHz in 1 KHz steps, to search for all pathogens. If you find a resonating frequency, go to the Pathogen Frequency Chart (page 561) to identify likely candidates for it. Verify the identity of the invader by using a slide or culture specimen. If your pathogen remains unidentified, add it to the chart. This lets you determine whether the next illness is new or a recurrence of this one. Or just kill it.

Use the frequency generator at one pathogen's frequency. Wait ten minutes and retest all of the ones you found. Only that one will be gone. Now **zap**, wait ten minutes, and test again for all of the ones you found. Notice they are all gone. After one hour, search yet again for the pathogens you had. Any that are back must have come from an internal source not reached by the zapper current, like from the bowel or an abscess.

Lesson Twenty Eight

Purpose: To observe the action of a positive offset frequency on a very small animal. Does the animal die or is it just incapacitated?

Materials: A slug or small earthworm.

Method: Place the small animal in a plastic container like a cottage cheese carton. Add a few tsp. of water to wet the bottom. Attach a metal teaspoon to each of the generator clips. Place them on opposite sides in the carton and fasten with tape. Set the generator to positive offset at a frequency of about 30 KHz and 5 to 10 volts. Experiment with different voltages and compare effectiveness. Measure the time it takes for the animal to seem lifeless. You may try to revive it by keeping it for some time in the presence of food. Retest its emission band.

Lesson Twenty Nine

Purpose: To kill the bacteria in dairy products.

Materials: A glass of regular pasteurized milk, a carton of cottage cheese. A zapper.

Method: Search for *Salmonellas* and *Shigellas* first in the milk and cottage cheese. Search by frequency, using the chart, or with slides of these bacteria. If you don't find any, search different dairy foods until you find some bacteria. Attach metal teaspoons to the red and black leads of the generator. Place them inside the milk glass or cottage cheese carton, across from each other. Secure with masking tape. Attach the zapper. Zap them for 7 minutes. Remove the electrodes and wait 5 minutes. Test again for the same bacteria. They should be gone (but the food is not safe to eat due to the metal released from the teaspoons).

These experiments point to some exciting possibilities. Perhaps water supplies as well as foods and medicines could be sterilized this way. Perhaps sewage could be treated more efficiently, electrically. Best of all, maybe you could protect yourself from unsanitary products. If you do decide to explore this possibility, remember not to put metals in your mouth or food. Nor to use currents greater than 10 milliamps, or for longer than 10 minutes.

There are many commercially available function generators that can meet your needs. Two are shown here.





Fig. 86 Function generators.

Recipes

Read old recipe books for the fun and savings of making your own nutritious food. Change the recipes to avoid processed ingredients. Here are some I found:

Beverage Recipes

Anything made in your own juicer is fine. Experiment with new combinations to create different flavorful fruit and vegetable juices. Consider the luxury of preparing gourmet juices which satisfy your own individual palate instead of the mass-produced, polluted varieties sold at grocery stores. Remember to wash all fruit, including citrus before juicing. This removes the ever-present pesticides and common fruit mold.

Lemonade

1 cup fresh lemon juice, 1 cup honey, 1½quarts water. Bring honey and water to a boil if you plan to keep it several days. Then add lemon juice and store in the refrigerator.

All honey and maple syrup should have vitamin C added to it as soon as it arrives from the supermarket. Warm it first; then stir in ¼ tsp. per pint.

Fresh Tomato Juice

Simmer for ½hour: 12 medium-sized raw, ripe tomatoes, ½ cup water, 1 slice onion, 2 ribs celery with leaves, ½bay leaf, 3 sprigs parsley. Strain these ingredients. Season with: 1 tsp. salt (aluminum-free), ¼ tsp. paprika, ½tsp. honey. Serve thoroughly chilled. Makes about 4 servings.

Fresh Pineapple Juice

Peel a pineapple. Remove all soft spots. Cut it into cubes. Extract the juice by putting the pineapple through a food grinder or a blender. There will be very little pulp. Strain the juice and serve it on ice with sprigs of mint. Makes about 1½cups of juice. Mix the pulp with an equal amount of clover honey and use as topping (kept in freezer) for homemade ice cream (below), pancakes, or yogurt.

Maple Milk Shake

For each milk shake, blend or shake together: 1 glass of milk and 2 tablespoons maple syrup.

Remember, all milk gets boiled.

Yankee Drink

Mix together 1 gal. water, 3 cups honey, ½cup fresh lemon juice or distilled white vinegar, and 1 tsp. ginger.

Hot Vanilla Milk

Add one inch of vanilla bean and one tsp. honey to a glass of milk and bring to a near boil. You may add a pinch of cinnamon or other pure spice. You may even use vanilla extract (see *Sources*).

Red Milk

Equal parts fresh carrot juice (use a juicer) and sterilized milk. Save the carrot pulp for salads and soups.

C-Milk

Milk can absorb a surprising amount of vitamin C powder without curdling or changing its flavor. Try ½tsp. in a glass of cold milk.

My Own Soda Pop

Excellent for stomach distress. Put 1 tsp. citric acid, 2 tbs. vegetable glycerin (see *Sources*), 2 tbs. honey, and 1 lemon, juiced by hand, into a quart jar and fill with cold water. Refrigerate until ready to use. Then add 1 tsp. baking soda (chemically pure only, see *Sources*) and shake a few times, keeping the lid tight. Pour over a few ice cubes. Many variations are possible: other fruit concentrates, made in the blender, can be used along with some lemon juice; for example, 2 blended whole apples (peeled), blended pineapple, orange or grapefruit. Always add a bit of lemon to give it zip. You may add a pinch of ginger or other pure spice.

Note: The amount of sodium in ½tsp. baking soda is .476 grams. If you have heart disease, high blood pressure, or edema, use potassium bicarbonate instead. Ask your doctor what an acceptable amount of sodium or potassium bicarbonate is. I would suggest limiting yourself to one glass of soda pop a day, even if you do not have heart disease.

Another Note: the citric acid kills bacteria, while the carbonation brings relief.

My Own Super C-Pop

An excellent way to get lots of vitamin C into a child and relieve stomach distress at the same time. Squeeze 1 slice of lemon and 1 whole orange into an 8 ounce bottle that has a tight lid. Add 1 tsp. vitamin C powder (ascorbic acid), ¼ tsp. citric acid, and 2 tbs. vegetable glycerin (you may also experiment with honey for sweetness). Fill the bottle to the top with cold water. Then add ½tsp. chemically pure baking soda and close tightly. Shake briefly and serve immediately.

Half And Half

Mix equal parts whipping cream and milk or water. Boil and chill.

Buttermilk-C

Stir 1 tsp. vitamin C powder into a glass of milk. Add a pinch of potassium chloride. Additional seasoning may be pepper and herbs. Stir and enjoy.

Food Recipes

Despite the presence of aflatoxins, benzopyrenes, and solvents in many foods, it is possible to have a delicious and safe diet. Many persons need to gain weight, and with the emphasis in today's society on losing weight, consider yourself lucky in this respect. Help yourself to lots of butter, whipping cream, whole milk, avocados, and olive oil. Make your own preserves and baked goods, including breads. Remember, when you are recovering from a major illness it is essential not to diet to lose weight. You must wait two years after you are recovered to try to lose weight.

Daily Foods

Dairy products should contain at least 2% fat to enable you to absorb the calcium in them.

All milk should be sterilized

by boiling it for 10 seconds. If it makes mucous, you already have a chronic respiratory infection. Try to clear this up.

Change brands every time you shop to prevent the same pollutants from building up in your body.

If frying or cooking with fat, use only olive oil, butter or lard (the BHT and BHA preservatives in lard are OK except for seizure sufferers). Mix them for added flavor in your dishes. Never use margarine, Crisco™ or other hydrogenated fats. Do not cook over flames or grill, even when electric.

Eat lots of **fresh fruits and vegetables**. Wash them off only with cold tap water, not commercial food "wash". Scrub hard with a stiff bristled brush. Then cut away blemishes. Always peel potatoes, apples, and carrots. Modern dirt is full of chemicals and is toxic to you.

Be sure to drink plenty of **plain water** from your cold faucet throughout the day, especially if it is difficult for you to drink it with your meals. If you don't like the taste of your own tap water, try to get it from a friend with newer plumbing. Use a polyethylene (opaque) water jug from a grocery store to transport it. Never drink water that has been run through a water softener or copper plumbing or has traveled through a long plastic hose. Don't drink water that has stood in a container for a day. Dump it and sterilize the container. To further improve flavor and to dechlorinate attach a small faucet filter made of carbon only. Or buy a filter pitcher (see *Sources*). Don't drink water that has stood in the filter pitcher very long, either.

Because commercial **cold cereals** are very convenient, but have solvents, here are two replacements.

Two Granolas

7 cups rolled oats (old fashioned, not quick)
1 tsp. salt
1 cup wheat germ (fresh, not defatted)
½ cup honey
½ cup sunflower seeds, immaculate quality
½ cup milk (no need to sterilize, it is being baked)
½ cup melted butter
1 cup raisins, rinsed in vitamin C water

Mix dry ingredients together. Mix liquid ingredients and add gradually, while tossing until thoroughly mixed. Place in large ungreased pans and bake in slow (250°) oven. Stir occasionally, baking until brown and dry, usually 1-2 hours. Store in airtight container in freezer.

6 cups rolled oats
½ cup raw wheat germ
1 cup sesame seeds
1 cup sunflower seeds (raw, unsalted)
1 tsp. cinnamon
½ cup melted butter
½ cup honey

Preheat oven to 250°. Toss all ingredients in mixing bowl. Spread thinly on a baking sheet and bake 20-25 minutes. Stir often in order to brown evenly. When golden, remove and let cool. Makes 12 cups.

If you would like to add nuts to your granola recipes, rinse them in cold tap water first, to which vitamin C powder has been added (¼ tsp. per pint). This removes aflatoxins.

Peanut Butter

Use fresh unsalted roasted peanuts—they will be white on the first day they arrive at the health food store from the distributor. (Ask when they will arrive.) Or shell fresh roasted peanuts yourself, throwing away all shriveled or darkened nuts. Grind, adding salt and vitamin C (¼ tsp. per pint) as you go. For spreadability, especially for children, grind an equal volume of cold butter along with the peanuts. This improves spreadability and digestibility of the hard nut particles. This will probably be the most heavenly peanut butter your mouth has ever experienced.



Fig. 87 Light colored, roasted peanuts in the shell had no aflatoxin.

Sweetening and Flavoring

Brown Sugar. Although I am prejudiced against all sugar from a health standpoint, my testing revealed no benzene, propyl alcohol, wood alcohol. However it does contain sorghum mold and must be treated with vitamin C to detoxify it. Add ¼ tsp. to a 1 pound package; knead until well mixed.

Maple syrup. Add vitamin C to newly opened bottle, ¼ tsp. to retard mold. Keep refrigerated and use promptly.

Flavoring. Use maple, vanilla (both natural and artificial), and any pure spice. They are free of molds and solvents.

Honeys. Get at least 4 flavors for variety: linden blossom, orange blossom, plain clover and local or wild flower honey.

Add vitamin C to newly opened jar to detoxify ergot mold (¼ tsp. per pint).

Jams and jellies. They are not safe unless homemade.

Fruit syrup. Use one package frozen fruit, such as cherries, blueberries or raspberries. Let thaw and measure the amount in cups (it might say on the package). Add an equal amount of clover honey to the fruit. Also add ¼ tsp. vitamin C powder. Mix it all in a quart canning jar and store in the refrigerator. Use this on pancakes, cereal, plain yogurt and homemade ice cream too. Use to make your own flavored beverages in a seltzer maker or to make soda pop. If you wish to use fresh fruit, bring it to a boil to sterilize. Use it up in a few days or boil to sterilize it again.

Note for diabetics

Diabetics must not use artificial sweeteners. Nor can they use all the sweeteners listed. Try stevia powder instead.

Preserves

Keep 3 or 4 kinds on hand, such as peach, pineapple, and pear. Peel and chop the fruit. It should not have any bruises. If you use a metal knife, rinse the fruit lightly afterwards. Add just enough water to keep the fruit from sticking as it is cooked (usually a few tablespoons). Then add an equal amount of honey, or to taste and heat again to boiling. Put in sterile jars in refrigerator. Make marmalade the same way, slicing the fruit and peel thinly. Always add vitamin C powder to a partly used jar to inhibit mold. Never use up partly molded fruit by making preserves out of it. Throw it out.

C Dressing

½ cup olive oil
¼ cup fresh lemon juice or white distilled vinegar
1 tsp. thyme, fenugreek or both (capsules are freshest)
1 tsp. vitamin C powder
½ tsp. brown sugar

Combine the ingredients in a clean salad dressing bottle. Shake. Refrigerate. The basic recipe is the oil and vinegar in a 2:1 ratio. After mixing these, add any pure spice desired. Or add fresh tomato chunks for creaminess.

Cheese Sauce

Add milk to cheese in equal amounts. Gradually heat to boiling while stirring. Add more of either to obtain the desired consistency. Boil 10 seconds. Use immediately.

Sour Cream-C

2 cups heavy whipping cream, previously boiled
¼ tsp. citric acid
¼ tsp. vitamin C powder
1 tsp. fresh onion juice or other seasoning (optional)

Stir until smooth, refrigerate 2 hours.

Yogurt

Buy a yogurt maker. Be sure and use boiled milk.

Soups

All home made soups are nutritious and safe, provided you use no processed ingredients (like bouillon), or make them in metal pots. Use herbs and aluminum-free salt to season. Always add a dash of vitamin C or tomato juice or vinegar to draw out calcium from soup bones for you to absorb.

Fish and Seafood recipe

Any kind of fish or seafood is acceptable, provided it is well-cooked. Don't buy food that is already in batter. The simplest way to cook fish is to poach it in milk. It can be taken straight from the freezer, rinsed, and placed in ¼ inch of milk (unboiled is fine) in the frying pan. Heat until it is cooked. Turn over and repeat. Throw away the milk. Serve with fresh lemon and herbs.

Baked Apples

Peel and core carefully. Remove all bruises (this is where the patulin is). Cut in bite-sized pieces, add a minimum of water and cook or bake minimally. Add a squirt of lemon juice when done. Serve with cinnamon, whipping cream and honey.

Ice creams

from the grocery store are loaded with benzene and other solvents. Fortunately there are ice cream makers that do everything (no cranking)! Or try our recipe which uses a blender. Be sure not to add store bought flavors, except vanilla or maple.

5 Minute Ice Cream

(Strawberry) Use 2 half pints of whipping cream, previously boiled, 1 package of frozen strawberries (about 10 oz.), and ½ cup clover honey. Pour frozen strawberries into blender. Pour whipping cream and honey over them. Blend briefly (about 10 seconds), not long enough to make butter! Pour it all into a large plastic bowl. Cover with a close fitting plastic bag and place in freezer. Prepare it a day ahead. Try using other frozen fruits, such as blueberries and cherries. Keep a few berries out of the blender and stir them in quickly with a non-metal spoon before setting the bowl in the freezer. There are many ice cream recipes to be found in old cook books. Avoid those with raw eggs or processed foods as ingredients. You may add nuts if you rinse them in vitamin C water.

Cookies, cakes and pies

Bake them from scratch, using unprocessed ingredients. Use simple recipes from old cook books.

Seven Day Sample Menu

Because processed foods have many toxins, you must cook as much from scratch as possible. So for convenience sake, keep your meals simple in preparation. You may want to prepare ahead and refrigerate your dressings and toppings. Or you could make a hot soup for dinner, refrigerate, and eat the leftovers for lunch. Don't save leftovers more than two days. Make sure they are covered. Try baking several potatoes at one time, refrigerate and put them in a salad the next night. Variety is the spice of life, so combine the allowed foods in the most creative ways you can imagine. And don't forget herbs and spices; learn to use them from old cook books.

	Breakfast	**Lunch**	**Dinner**
Day 1	Granola and honey with milk, half n' half or whipping cream 1 cup fresh squeezed fruit juice Water Milk	Fresh ground peanut butter and preserve sandwich Soup Milk Water	Orange roughy fish Fresh green beans with butter Baked potato with Sour Cream-C topping or fresh chives Pie (homemade) Milk 1 cup fresh squeezed or frozen vegetable juice Water

Day 2	Egg (limit is 2) Fried potatoes 1 glass milk Peppermint herb tea Fresh orange juice	Bagel (from bakery) Sour Cream-C Tomato 1 cup vegetable juice Water Milk	Homemade bean or lentil soup Sardines Dinner roll and butter Salad Homemade dressing Ice cream (homemade) Water
Day 3	Cream of Wheat™ cooked with raisins and milk Banana Peppermint herb tea ½ cup milk Water	Tuna sandwich with olives and butter Soup Milk Water	Baked sweet potato with butter and sweetening. Fresh broccoli with cheese sauce Bread and butter Chopped, peeled pear and whipping cream 1 cup vegetable juice Milk Water
Day 4	French toast with maple syrup Egg Homemade grapefruit juice Milk Water	Avocado and sour cream sandwich ½ cup vegetable juice Bread and butter Water	Lobster or sautéed shrimp Fresh asparagus Potatoes, any style ½ cup vegetable juice Water Milk
Day 5	Cooked cereal 1 glass milk Sliced banana with whipping cream and honey 1 glass water	Cold potato salad with C Dressing Soup ½ cup vegetable juice Custard Water Milk	1 can sardines or salmon in easy-open can (can openers shed metal) Salad of lettuce, tomato, olives, avocado with homemade dressing Bread with butter Ice-cream (optional) ½ cup vegetable juice Water Milk
Day 6	Egg and homemade biscuit with honey and butter Milk Fruit juice (homemade) Water	Homemade peanut butter sandwich ½ cup vegetable juice Milk Water	Gourmet pizza: home baked bread topped with olive oil, sliced tomato or homemade sauce, grated cheese, sardines or anchovies, chopped vegetables, garlic and onion Salad Milk Water

Day 7	Pancakes Banana or chopped fruit with cream Milk Water	Salmon sandwich (from flip top can) ½ cup vegetable juice Milk Water	Stir-fry vegetables: broccoli, carrots, cabbage, in olive oil and butter Bread and butter Pie (optional) Milk Water

Remember, take vitamin C and B-complex with each meal.

Too Sick To Cook, Too Tired To Eat

Pick three meals from the sample menu that need no cooking and eat them every day.

Recipes for Natural Body Products

You can use just borax (like 20 Mule Team Borax$^{\text{TM}}$) and washing soda (like Arm & Hammer Super Washing Soda$^{\text{TM}}$) for all types of cleaning including your body, laundry, dishes and your house! You don't need all of those products you see in commercials for each special task!

Even if you have dry skin, difficult hair or some other unique requirement, just pure borax will satisfy these needs. A part of every skin problem is due to the toxic elements found in the soaps themselves. For instance aluminum is commonly added as a “skin moisturizer”. It does this by impregnating the skin and attracting water, giving the illusion of moist skin. In fact you simply have moist aluminum stuck in your skin which your immune system must remove. While borax won't directly heal your skin or complexion, it does replace the agents that are causing damage, so that healing can occur.

Borax Liquid Soap

Empty 1 gallon jug
1/8 cup borax powder
Plastic funnel

Funnel the borax into the jug, fill with cold tap water. Shake a few times. Let settle. In a few minutes you can pour off the clear part into dispenser bottles. This is the soap!

Easier way: use any bottle, pour borax powder to a depth of a ½ inch or so. Add water. Shake. When you have used it down to the undissolved granules, add more water and shake again. Add more borax when the undissolved granules get low.

Keep a dispenser by the kitchen sink, bathroom sink, and shower. It does not contain aluminum as regular detergents and soaps do, and which probably contribute to Alzheimer's disease. It does not contain PCBs as many commercial and health food varieties do. It does not contain cobalt (the blue or green granules) which causes heart disease and draws cancer parasites to the skin. Commercial detergents and non-soaps are simply not safe. Switch to homemade bar soap and borax for all your tasks! Borax inhibits the bacterial enzyme *urease* and is therefore antibacterial. It may even clear your skin of blemishes and stop your scalp from itching.

For Laundry

Borax (½ cup per load). It is the main ingredient of non-chlorine bleach and has excellent cleaning power without fading colors. Your regular laundry soap may contain PCBs, aluminum, cobalt and other chemicals. These get rubbed into your skin constantly as you wear your clothing. For bleaching (only do this occasionally) use original chlorine bleach (not “new improved” or “with special brighteners”, and so forth). Don't use chlorine if there is an ill person in the house. For getting out stubborn dirt at collars, scrub with homemade bar soap first; for stains, try grain alcohol, vinegar, baking soda.

For Dishes

Don't believe your eyes when you see the commercials where the smiling person pulls a shining dish out of greasy suds. Any dish soap that you use should be safe enough to eat because nothing rinses off clean. Regular dish detergents, including health brands, are now polluted with PCBs. They also contain harmful chemicals. Use borax for your dishes. Or use paper plates and plastic (not styrofoam) cups.

In The Dishwasher

Use 2 tsp. borax powder pre-dissolved in water. If you use too much it will leave a film on your dishes. Use vinegar in the rinse cycle.

In The Sink

Use a dishpan in the sink. Use ¼ cup borax and add a minimum of water. Also keep a bit of dry borax in a saucer by the sink for scouring. Don't use any soap at all for dishes that aren't greasy and can be washed under the faucet with nothing but running water. Throw away your old sponge or brush or cloth because it may be PCB contaminated. Start each day by sterilizing your sponge (it harbors Salmonella) or with a new one while the used one dries for three full days. Clean greasy pots and pans with a paper towel first. Then use homemade bar soap.



Fig. 88 Make a bottle of borax liquid to fill your soap dispensers and shampoo bottle. Use citric acid to rinse and condition.

Shampoo

Borax liquid is ready to use as shampoo, too. It does not lather but goes right to work removing sweat and soil without stripping your color or natural oils. It inhibits scalp bacteria and stops flaking and itching. Hair gets squeaky clean so quickly (just a few squirts does it) that you might think nothing has happened! You will soon be accustomed to non-lathery soap. Rinse very thoroughly because you should leave your scalp slightly acidic. Take a pint container to the shower with you. Put ¼ tsp. citric (not ascorbic) acid crystals (see *Sources*) in it. For long hair use a quart of rinse. Only **citric acid** is strong enough to get the borax out, lemon juice and vinegar are not. After shampooing, fill the container with water and rinse. Rinse your whole body, too, since citric acid is also anti-bacterial. All hair shampoo penetrates the eye lids and gets into the eyes although you do not feel it. It is important to use this natural rinse to neutralize the shampoo in your eyes. (Some people have stated that citric acid makes their hair curlier or reddens it. If this is undesirable, use only half as much citric acid.) Citric acid also conditions and gives body and sheen to hair.

Hair Spray

I don't have a recipe that holds your hair as well as the bottle of chemicals you can buy at the store. Remarkably a little lemon juice (not from a bottle) has some holding power and no odor! Buy a 1 cup spray bottle. Squeeze part of a lemon, letting only the clear juice run into the bottle. Fill with water. Keep it in the refrigerator. Make it fresh every week. Spraying with just plain water is nearly as good! For shinier hair, drop a bit of lemon peel into the bottle.

Homemade Soap

A small plastic dishpan, about 10" x 12"
A glass or enamel 2-quart sauce pan
1 can of lye (sodium hydroxide), 12 ounces
3 pounds of lard (BHT and BHA are OK here)
Plastic gloves
Water

1. Pour 3 cups of very cold water (refrigerate water overnight first) into the 2-quart saucepan.
2. Slowly and carefully add the lye, a little bit at a time, stirring it with a wooden or plastic utensil. (Use plastic gloves for this; test them for holes first.) Do not breathe the vapor or lean over the container or have children nearby. Above all use no metal. The mixture will get very hot. In olden days, a sassafras branch was used to stir, imparting a fragrance and insect deterrent for mosquitoes, lice, fleas, ticks.

3. Let cool at least one hour in a safe place. Meanwhile, the unwrapped lard should be warming up to room temperature in the plastic dishpan.
4. Slowly and carefully, pour the lye solution into the dishpan with the lard. The lard will melt. Mix thoroughly, at least 15 minutes, until it looks like thick pudding.
5. Let it set until the next morning; then cut it into bars. It will get harder after a few days. Then package.

If you wish to make soap based on olive oil, use about 48 ounces. It may need to harden for a week.

Liquid Soap

Make chips from your homemade soap cake. Add enough hot water to dissolve. Add citric acid to balance the pH (7 to 8). If you do not, this soap may be too harsh for your skin.

Skin Sanitizer

Make up a 5 to 10% solution of food grade alcohol. Food grade alcohols are grain (ethyl) alcohol or vodka. Find a suitable dispenser bottle. Mark it with a pen at about one tenth of the way up from the bottom. Pour 95% grain alcohol (190 proof) to this mark (for 50% grain alcohol or vodka make your mark one fifth of the way up). Add water to the top. Keep shut. You may add a chip of lemon peel for fragrance.

Use this for general sanitizing purposes: bathroom fixtures, knobs, handles, canes, walkers, and for personal cleanliness (but use chlorine bleach for the toilet bowl once a week). Always clean up after a bowel movement with wet toilet paper. This is not clean enough, though. Follow with a stronger damp paper towel. This is still not clean enough; use a final damp paper towel with skin sanitizer added. After washing hands, sanitize them too, pouring a bit on one palm and put finger tips of the other hand in it, scratch to get under nails, repeat on other hand. Rinse with water.

Do not use this recipe, nor keep any bottles of alcohol in the house of a recovering alcoholic.

Deodorant

Your sweat is odorless. It is the entrenched bacteria feeding on it that make smells. You can never completely rid yourself of these bacteria, although they may temporarily be gone after zapping. The strategy is to control their numbers. Here are several deodorants to try. Find one that works best for you:

Vitamin C water. Mix ¼ tsp. to a pint of water and dab it on. Then dab on cornstarch.

Citric Acid water. Mix ¼ tsp. to a pint of water and dab it on. Then dab on cornstarch.

Only a few drops of these acids under each armpit are necessary. If these acids burn the skin, dilute them more. Never apply anything to skin that has just been shaved!

Corn starch. Many people need only this. Dab it on.

Use only unpolluted **cornstarch** (see *Sources*).

Baking soda has been deleted as a deodorant because benzene was found in some boxes.

Lemon juice. This acid is not as strong, use what you need.

Pure alcohol (never rubbing alcohol). The food grade alcohols are grain alcohol and vodka. Dab a bit under each arm and/or on your shirt or blouse, then dab on cornstarch. If the alcohol burns, dilute it with water. Be very careful not to leave the bottle where a child or alcoholic person could find it. Pour it into a different bottle!

Pure zinc oxide. You may ask your pharmacist to order this for you. She or he may wish to make it up for you too, but do not let them add anything else to it. It should be about 1 part zinc oxide powder to 3 parts water. It does not dissolve. Just shake it up to use it. After you get it home, you can add cornstarch to it to give it a creamy texture. Heat 3 tsp. cornstarch in 1 cup of water, to boiling, until dissolved and clear. Cool and add some to the zinc oxide mixture (about equal parts). Store unused starch mixture in the refrigerator. Only make up enough for a month.

Alcohol and zinc oxide. This is the most powerful deodorant. Apply alcohol first, then the zinc oxide, then dab on cornstarch.

Remember that you need to sweat! Sweating excretes toxic substances, especially from the upper body. Don't use deodorant on weekends. Go to the sink and wipe clean the armpits like our grandparents did. Often, just plain cornstarch is enough! These homemade deodorants are not as powerful as the commercial varieties–this is to your advantage.

Brushing Teeth

Buy a new toothbrush. Your old one is soaked with toxins from your old toothpaste. Use only water or chemically pure baking soda if you have any metal fillings. Put a pinch in a glass, add water to dissolve it. Use food-grade hydrogen peroxide (see *Sources*) if you have only plastic fillings. Dilute it from 35% to 17½% by adding water (equal parts). Store hydrogen peroxide only in polyethylene or the original plastic bottle. Use 4 or 5 drops on your toothbrush. It should fizz nicely as oxygen is produced in your mouth. Your teeth will whiten noticeably in 6 months. Before brushing teeth, floss with 4 or 2 pound monofilament fish line. Double it and twist for extra strength. Rinse before use. Floss and brush only once a day. If this leaves you uncomfortable, brush the extra times with plain water and a second “water-only” toothbrush. Make sure that nothing solid, like powder, is on your toothbrush; it will scour the enamel and give you sensitive teeth, especially as you get older and the enamel softens. Salt is corrosive—don't use it for brushing metal teeth. Plain water is just as good.

For Dentures

Use salt water. It kills all germs and is inexpensive. Salt water plus grain alcohol or food-grade hydrogen peroxide makes a good denture-soak.

Mouthwash

A few drops of food grade hydrogen peroxide added to a little water in a glass should be enough to make your mouth foam and cleanse. Don't use hydrogen peroxide, though, if you have metal fillings, because they react. Don't use regular drug store variety hydrogen peroxide because it contains toxic additives. Health food store varieties contain solvents from the bottling process. See *Sources*. Never purchase hydrogen peroxide in a bottle with a metal cap.

For persons with metal tooth fillings, use chemically pure baking soda or just plain hot water. A healthy mouth has no odor! You shouldn't need a mouthwash! If you have breath odor, search for a hidden tooth infection or cavitation.

Contact Lens Solution

A scant cup of cold tap water brought to a boil in glass saucepan. After adding ¼ tsp. aluminum free salt and boiling again, pour into a sterile canning jar. Refrigerate. Freeze some of it.

Lip Soother

For dry, burning lips. Heat 1 level tsp. sodium alginate plus 1 cup water until dissolved. After cooling, pour it into a small bottle to carry in your purse or pocket (refrigerate the remainder). Dab it on whenever needed. If the consistency isn't right for you, add water or boil it down further. You can make a better lip soother by adding some lysine from a crushed tablet, vitamin C powder, and a vitamin E capsule to the alginate mix. If you have a persistent problem with chapped lips, try going off citrus juice.

Foot Powder

Use a mixture of cornstarch and zinc oxide poured into a salt shaker with a lid. Add long rice grains to fight humidity. You may also try arrow root or potato starch. If you don't have zinc oxide use plain cornstarch.

Skin Healer Moisturizer Lotion

1 tsp. sodium alginate
1 cup water

Make the base first by heating these together in a covered, non-metal pan until completely dissolved. Use low heat–it will take over an hour. Use a wooden spoon handle to stir. Set aside. Then make the following mixture:

¼ tsp. Vitamin C (ascorbic acid) (You may crush tablets)
¼ tsp. lysine (crush tablets)
2 tbs. pure vegetable glycerin
2 vitamin E capsules (400 units or more, each)
1 tsp. apricot kernel oil (olive oil will do)

1 tbs. lemon juice from a lemon or ¼ tsp. citric acid (this is optional)
1 cup water

Heat the water to steaming in a non-metal pan. Add vitamin C and lysine first and then everything else. Pour into a pint jar and shake to mix. Then add the sodium alginate base to the desired thickness (about equal amounts) and shake. Pour some into a small bottle to use as lip soother. Pour some into a larger bottle to dispense on skin. Store remainder in refrigerator. (See *Sources* for sodium alginate, vegetable glycerin and apricot kernel oil. Sodium alginate is also available in capsule form at some health food stores.)

Other Skin Healers

Vitamin C powder (ascorbic acid, not the same as citric acid). Put a large pinch into the palm of your hand. With your other hand pick up a few drops of water from the faucet. Rub hands together until all the powder is dissolved and dispensed. It may sting briefly. Do this at bedtime, especially for cracked, chapped hands. Include lips if they need it.

Vitamin E oil. Vitamin E oil from Now Foods was not polluted at the time of this writing, but for the future it would be safer to rely on capsules. Snip open a capsule and rub into skin.

50% Glycerin. Dilute 100% vegetable glycerin with an equal amount of water. This is useful as an after shave lotion.

Vitamin C liquid. Mix ¼ tsp. vitamin C powder in one pint water (crushed tablets will do). This is useful as an after shave lotion and general skin treatment.

Apricot Kernel Oil. This is a very light oil, useful as an after shave lotion and general skin treatment.

Cornstarch (see *Sources*). Use on rashes, fungus, moist or irritated areas and to prevent chafe.

Combining several of these makes them more effective.

Dry skin has several causes: too much water contact, too much soap contact (switch to borax), low body temperature, not enough fat in the diet, or parasites.

Massage Oil

Use olive oil. It comes in very light to heavy textures. Pick the right one for your purpose. Alginate mixtures can be used instead of, or added to, oil. Starch solutions are good, too.

Sunscreen Lotion

Purchase PABA (see *Sources*) in 500 mg tablet form. Dissolve 1 tablet in grain alcohol or vodka. Grind the tablet first by putting it in a plastic bag and rolling over it with a glass jar. It will not completely dissolve even if you use a tablespoon of the alcohol. Pour the whole mixture into a 4 ounce bottle of homemade skin softener. Be careful not to get the lotion into your eyes when applying it. A better solution is to wear a hat or stay out of the sun. Remember to *take* PABA as a supplement, too (500 mg, one a day).

Nose Salve

(When the inside of the nose is dry, cracked and bleeding.)

Pour ½tsp. pure vegetable glycerin into a bottle cap. Add ½ tsp. of water.

Applicator: use a plastic coffee stirrer or straw; cut a slit in the end to catch some cotton wool salvaged from a vitamin bottle and twist (cotton swabs, cotton balls and wooden toothpicks are sterilized with mercury which in turn is polluted with thallium). Dip it into the glycerin mixture and apply inside the nose with a rotating motion. Do each nostril with a new applicator.

Quick Corn Starch Skin Softener

4 tsp. corn starch (see *Sources*)
1 cup water

Boil starch and water until clear, about one minute.

Cornstarch Skin Softener

1 tsp. lysine powder or 8 tablets, 500 mg each
1 tsp. Vitamin C powder (ascorbic acid); or 8 tablets, 500 mg each
3 tsp. cornstarch (see *Sources*)
Vitamin E, 1 capsule 400 mg
¼ tsp. apricot kernel oil (optional)
1 cup water

Boil starch and water until clear, about one minute. Add other ingredients and stir until dissolved. Cool. Pour into dispenser bottle. Keep refrigerated when not in use. Apply after washing dishes and after showering.

After Shaves

Vitamin C. ¼ tsp. vitamin C powder, dissolved in 1 pint water.

Apricot kernel oil.

Vegetable glycerin. Equal parts glycerin and water or to suit your need.

Personal Lubricants

Heat these together: 1 level tsp. sodium alginate and 1 cup water in a covered non-metal pan until completely dissolved. Use very low heat and stir with a wooden spoon handle. It takes a fairly long time to get it perfectly smooth. After cooling, pour into a small dispenser bottle. Keep the remainder refrigerated.

Or, mix and heat 4 tsp. cornstarch and 1 cup water until completely dissolved in a covered saucepan. Use non-metal dishes and a non-metal stirring spoon. Cool. Pour some into dispenser bottle. Refrigerate remainder. This is many person's favorite recipe.

Baby Wipes

Cut paper towels in quarters and stack in a closable plastic box. Run tap water over them, drain the excess. Add 1 tsp. grain alcohol and/or borax liquid on top. Close. Put a dab of the Quick Cornstarch Softener recipe on top of each wipe as you use it.

People Wipes

¼ tsp. powdered lysine (you may crush tablets)
¼ tsp. Vitamin C powder (you may crush tablets)
¼ cup vegetable glycerin
1 cup water

Prepare wipes by cutting paper towels in quarters. Use white, unfragranced towels that are strong enough to hold up for this use. Fold each piece in quarters again and stack in a plastic zippered baggy. Pour the fluid mixture over the stack and zip. Store a bag full in the freezer to take on car trips. If you want to keep them a month or more, add 1 tbs. grain alcohol or vodka to the recipe.

For bathroom use, dampen a roll of paper towels under the cold tap first. Then pour about ¼ cup of the mixture over the towel roll around the middle. Store in plastic shopping bag or stand in plastic waste basket.

Recipes For Natural Cosmetics

Eye liner and Eyebrow Pencil

Get a pure charcoal pencil (black only) at an art supply store. Try several on yourself (bring a small mirror) in the store to see what hardness suits you. You may need to wet it with water or a vitamin E perle first. Don't put any chemicals on your *eyelids,* since this penetrates into your eye. To check this out for yourself, close your eye tightly and then dab lemon juice on your eyelid. It will soon burn! Everything that is put on skin penetrates. Otherwise the nicotine patch and estrogen patch wouldn't work. Not even soap belongs on your eyelids! Charcoal pencils are cheap. Get yourself half a dozen different kinds so you can do different things.

You could also use a capsule of activated charcoal. Empty it into a saucer. Mix glycerin and water, half and half, and add it to the charcoal powder until you get the consistency you like. Use a brush for eyelashes; use a finger for eyebrows.

Lipstick

Beet root powder (see *Sources*)
100% vegetable glycerin

Combine 1 tsp. vegetable glycerin and 1 tsp. beet root powder in a saucer. Stir until perfectly smooth. Then add ½tsp. of vitamin E oil. Snip open vitamin E capsules or buy vitamin E oil (see *Sources*). Very thick olive oil can be substituted. Apply liberally with your finger or a lipstick brush. Do not purse or rub your lips together after application. To make the lipstick stay on longer, apply 1 layer of lipstick, then dab some corn starch over the lips, then apply another layer of lipstick. Store in a small glass or plastic container in the refrigerator, tightly covered in a plastic bag.

Face Powder

Use cornstarch from the original box. You may also try arrow root starch or potato starch. Use your fingers or a tissue to apply because applicators can carry bacteria.

Blush (face powder in a cake form)

Add 50% glycerin to cornstarch in a saucer to make a paste. Slowly add beet root powder to the desired color. Use part of a charcoal capsule to darken it, if desired. A drop of food grade alcohol will also darken it. To make 50% glycerin, add equal parts of glycerin and water. Try to make the consistency the same as your brand name product, and you can even put it back in your brand name container.

Recipes For Household Products

Floor Cleaner

Use washing soda from the grocery store. You may add borax and boric acid (to deter insects except ants). Use white distilled vinegar in your rinse water for a natural shine and ant repellent. Do not add bleach to this. For the bathroom floor use plain bleach water—follow the label. Never use chlorine bleach if anybody in the home is ill or suffers from depression. Use grain alcohol (1 pint to 3 quarts water) for germ killing action instead of chlorine.

Furniture Duster and Window Cleaner

Mix equal parts white distilled vinegar and water. Put it in a spray bottle.

Furniture Polish

A few drops of olive oil on a dampened cloth. Use filtered water to dampen.

Insect Killer

Boric acid powder (not borax). Throw liberal amounts behind stove, refrigerator, under carpets and in carpets. Since boric acid is white, you must be careful not to mistake it for sugar accidentally. Keep it far away from food and out of children's reach. Buy it at a farm supply or garden store (or see *Sources*). It will not kill ants.

Ant Repellent

Spray 50% white distilled vinegar on counter tops, window sills and shelves and wipe, leaving residue. Start early in spring before they arrive, because it takes a few weeks to rid yourself of them once they are established. If you want immediate action, get some lemons, cut the yellow outer peel off and cover with grain alcohol in a tightly closed jar. Let stand at least one hour. Use 1 part of this concentrate with 9 parts water in a spray bottle. Mix only as much as you will use because the diluted form loses potency. Spray walls, floors, carpets wherever you see them. The lemon solution even leaves a shine on your counters. Use both vinegar and lemon approaches to rid yourself of ants.

To treat the **whole house**, pour vinegar all around your foundation, close to the wall, using one gallon for every five feet. Expect to damage any foliage it touches. Reapply every six months.

Flower and Foliage Spray

Food-grade hydrogen peroxide. See instructions on bottle.

Moth Balls

I found this recipe in an old recipe book. Mix the following and scatter in trunks and bags containing furs and woolens: ½lb. each rosemary and mint, ¼ lb. each tansy and thyme, 2 tbs. powdered cloves.

Carpet Cleaner

Whether you rent a machine or have a cleaning service, don't use the carpet shampoo they want to sell, even if they "guarantee" that it is all natural and safe. Instead add these to a bucket (about four gallons) of water and use it as the cleaning solution:

Wash water	Rinse water
1/3 cup borax	¼ cup grain alcohol
	2 tsp. boric acid
	¼ cup white distilled vinegar **or**
	4 tsp. citric acid

Borax does the cleaning; alcohol disinfects, boric acid leaves a pesticide residue, and the vinegar or citric acid give luster. If you are just making one pass on your carpet, use the borax, alcohol, and boric acid. Remember to test everything you use on an unnoticed piece of carpet first.

Health Improvement Recipes

Black Walnut Hull Tincture

This new recipe is four times as strong as the previous one, so it is called **Black Walnut Hull Tincture Extra Strength**.

Your largest enamel or ceramic (not stainless steel, not aluminum) cooking pot, preferably at least 10 quarts
Black walnuts, in the hull, each one still at least 50% green, enough to fill the pot to the top
Grain alcohol, about 50% strength, enough to cover the walnuts
½ tsp. vitamin C
Plastic wrap or cellophane
Glass jars or bottles

The black walnut tree produces large green balls in fall. The walnut is inside, but we will use the whole ball, uncracked, since the active ingredient is in the green outer hull.

Rinse the walnuts carefully, put them in the pot, and cover with the alcohol. Sprinkle on half the vitamin C. Seal with plastic wrap and cover. Let sit for three days. Pour into glass jars or bottles, discarding walnuts, and divide the remaining vitamin C amongst the jars. If the glass jar has a metal lid, first put plastic wrap over the top before screwing on the lid. Potency is strong for several years if unopened, even if it darkens.

You have just made Extra Strength Black Walnut Hull Tincture. It is stronger than the concentrate made with just a few black walnuts in a quart jar (my earlier recipe), because there are more walnuts per unit liquid. In addition, you will not dilute it before use (although when you take it, it will usually be in water).

When preparing the walnuts, rinse only with cold tap water. You may need to use a brush on areas with dirt. If you are not going to use all of them in this batch, you may freeze them in a resealable plastic bag. Simply refrigerating them does not keep them from turning black and useless. The pot of soaking walnuts should not be refrigerated. Nor does the final tincture need any refrigeration.

Exposure to air does cause the tincture to darken and lose potency. To reduce air exposure, fill the pot as much as possible, without touching the plastic wrap, while still keeping a snug fitting lid. Even more importantly, the glass jars or bottles you use to store your tincture should have as little air space as possible, without touching the plastic wrap on top. A large jar should be divided into smaller ones when you are ready to use it. The idea is not to have partial jars, with a lot of air space, sitting for longer than a month or so.

There are several ways to make a 50% grain alcohol solution. Some states have Everclear,^{TM} 95% alcohol. Mix this half and half with water. Other states have Everclear that is 76.5% alcohol. Mix this three parts Everclear to one part water. Yet another method is to buy vodka that is 100 proof. This is already 50% alcohol.

Remember, never use any kind of purchased water to make tincture.

Black Walnut Hull Tincture (Regular Strength)

This is the potency I used originally. It is included here in case you prefer it or wish to treat a pet. The Extra Strength recipe is four times as potent as the original recipe, so it must be diluted in quarters. (Similarly, if you have a lot of the Regular Strength left and want to use it in place of Extra Strength, simply take four times as much.)

Black Walnut Hull Tincture Extra Strength
Grain Alcohol, about 10%

Mix one part extra strength tincture with three parts of the 10% alcohol. Store in glass containers same as described above.

There are several ways to make a 10% grain alcohol solution. Some states have Everclear,™ 95% alcohol. Mix this one part Everclear to nine parts water. Other states have Everclear that is 76.5% alcohol. Mix this one part Everclear to seven parts water. Yet another method is to buy vodka that is 100 proof (50% alcohol) and mix one part vodka with four parts water.

Black Walnut Hull Extract (Water Based)

Because you do not know how commercially available extracts were made, and may not be able to test for solvent pollution, it is wisest to make it yourself!

This recipe is intended for alcoholic persons: cover the green balls in the 10 quart (non-metal) pot with cold tap water. Heat to boiling, covered. Turn off heat. When cool, add vitamin C, cover with plastic wrap, and the lid. Let stand for 1 day. It will be darker than the tincture. Do not dilute. Pour into freezable containers. Refrigerate what you will use in two days and freeze the rest. Add vitamin C after thawing or during refrigeration (¼ tsp. per quart).

For use: in programs calling for Extra Strength Black Walnut Hull Tincture use four times as much of this water based recipe (8 tsp. instead of 2 tsp. Extra Strength).

Important Note: do not use bottled or purchased water to make this tincture or you could pollute it with benzene!

Quassia recipe

Add 1/8 cup quassia chips to 3 cups water. Simmer 20-30 minutes. Pour off 1/8 cup now and drink it fresh. Refrigerate remainder. Drink 1/8 cup 4 times/day, until a total of ½cup of chips is consumed. Flavor with spices.

Emmenagogue (Menstrual Period Inducer)

Here are four herbs that can each bring on your period. They can be started anytime but the most-effective time is before your next calculated period time (count days as if you never missed a period).

1 oz sassafras bark
1 oz rue (cut)
1 oz marjoram herb
1 oz blue cohosh root
4½ cups boiling water

Add the herbs to the boiling water and turn down to simmer, covered, for 20 minutes. Do not boil. Strain and refrigerate in sterile glass jar. Pour one cup for yourself in the morning. Let warm to room temperature, and sip between meals, making it last until supper.

Bowel Program

Bacteria are always at the root of bowel problems, such as pain, bloating and gassiness. They can not be killed by zapping, because the high frequency current does not penetrate the bowel contents.

Although most bowel bacteria are beneficial, the ones that are not, like *Salmonellas* and *Shigellas*, are extremely detrimental because they have the ability to invade the rest of your body and colonize a trauma site or weakened organ. These same bacteria colonize a cancer tumor and delay healing after the malignancy is stopped.

Another reason bowel bacteria are so hard to eradicate is that we are constantly reinfecting ourselves by keeping a reservoir on our hands and under our fingernails.

- So the first thing to do is **improve sanitation**. For a serious problem, use 50% grain alcohol (100 proof vodka) in a spray bottle at the bathroom sink. Sterilize your hands after bathroom use and before meals.
- Secondly use **turmeric** (2 capsules 3 times a day, this is the common spice) which I find helps against *Shigella*, as well as *E. coli*. Expect orange colored stool.
- Third use **fennel** (1 capsule 3 times a day).
- Fourth use **digestive enzyme tablets** with meals as directed on the bottle. (But only as long as necessary, because these frequently harbor molds.)
- Fifth use a single 2 tsp. dose of **Black Walnut Hull Tincture Extra Strength**. Add it to a ½glass of water and sip over a 15 minute period. Stay seated until any side effect from the alcohol wears off.
- Sixth take **Cascara sagrada** capsules if constipated (start with one capsule a day, use up to maximum on label). Remember to drink a cup of hot water upon rising in the morning. This will begin to regulate your elimination.

It can take all six to get rid of a bad *Shigella* problem in a week. Afterward, you must continue to eat only sterile dairy products. Note that the Kidney Cleanse is often effective with bowel problems. Try it also.

You will know you succeeded when your tummy is flat, there is not a single gurgle, and your mood improves!

Constipation Tea

Constipation is often caused by *E. coli* and *Salmonella* from dairy foods, or from killing "good" bowel bacteria with antibiotics (killing a few by zapping actually restores good flora). Eat foods that restore the body's good bowel flora: vegetables, sterilized milk (the milk sugar is essential), lots of water.

There are a lot of remedies for constipation, but many people enjoy this tea:

1 tbs. senna tea leaves
½ tsp. mint leaves

Boil for one minute in a quart of water, add a dash of vitamin C and brown sugar to taste. Sip through the day to avoid "bellyache". It can take years for the body's flora to "right themselves" after an antibiotic session, be patient.

Weight Reduction

Here are two ancient herbal recipes for obesity. I have not personally determined their effectiveness.

Fucus

2 oz *Fucus vesiculosus*, cut (see Sources)
3 cups cold tap water

Boil for 15 minutes, covered. Cool. Dose: ¼ cup four times a day on an empty stomach. After one week increase dose to ½cup. You may add any flavoring desired.

Watch the pot carefully as it comes to a boil. If it boils over, you will have a month of stove-cleaning to do. The odor of *Fucus* boiling is wretched. So is the taste. Maybe garlic (fresh) would improve it.

Fennel

1 oz fennel seed (crushed or powdered is fine)

3 cups cold tap water

Boil water, pour over herb. Steep 30 minutes. Strain. Add 4 oz honey (optional). Drink one cup each day.

You could take them both together, along with the Bowel Program, to be more successful, but the best single weight reducer is the Liver Cleanse.

Kidney Cleanse

½ cup dried Hydrangea root
½ cup Gravel root
½ cup Marshmallow root
4 bunches of fresh parsley
Goldenrod tincture (leave this out of the recipe if you are allergic to it)
Ginger capsules
Uva Ursi capsules
Vegetable glycerin
Black Cherry Concentrate, 8 oz
Vitamin B6, 250 mg
Magnesium oxide tablets, 300 mg

Measure ¼ cup of each root and set them to soak, together in 10 cups of cold tap water, using a non-metal container and a non-metal lid (a dinner plate will do). After four hours (or overnight) add 8 oz. black cherry concentrate, heat to boiling and simmer for 20 minutes. Drink ¼ cup as soon as it is cool enough. Pour the rest through a bamboo strainer into a sterile pint jar (glass) and several freezable containers. Refrigerate the glass jar.

Boil the fresh parsley, after rinsing, in 1 quart of water for 3 minutes. Drink ¼ cup when cool enough. Refrigerate a pint and freeze 1 pint. Throw away the parsley.

Dose: each morning, pour together ¾cup of the root mixture and ½cup parsley water, filling a large mug. Add 20 drops of goldenrod tincture and 1 tbs. of glycerin. Drink this mixture in divided doses throughout the day. Keep cold. Do not drink it all at once or you will get a stomach ache and feel pressure in your bladder. If your stomach is very sensitive, start on half this dose.

Save the roots after the first boiling, storing them in the freezer. After 13 days when your supply runs low, boil the same roots a second time, but add only 6 cups water and simmer only 10 minutes. This will last another 8 days, for a total of three weeks. You may cook the roots a third time if you wish, but the recipe gets less potent. If your problem is severe, only cook them twice.

After three weeks, repeat with fresh herbs. You need to do the Kidney Cleanse for six weeks to get good results, longer for severe problems.

Also take:

- Ginger capsules: one with each meal (3/day).
- Uva Ursi capsules: one with breakfast and two with supper.
- Vitamin B6 (250 mg): one a day.
- Magnesium oxide (300 mg): one a day.

Take these supplements just before your meal to avoid burping.

Some notes on this recipe: this herbal tea, as well as the parsley, can easily spoil. Heat it to boiling every fourth day if it is being stored in the refrigerator; this resterilizes it. If you sterilize it in the morning you may take it to work without refrigerating it (use a glass container).

When you order your herbs, be careful! Herb companies are not the same! These roots should have a strong fragrance. If the ones you buy are barely fragrant, they have lost their active ingredients; switch to a different supplier. Fresh roots can be used. Do not use powder.

- Hydrangea (*Hydrangea arborescens*) is a common flowering bush.
- Gravel root (*Eupatorium purpureum*) is a wild flower.
- Marshmallow root (*Althea officinalis*) is mucilaginous and kills pain.
- Fresh parsley can be bought at a grocery store. Parsley flakes and dried parsley herb do not work.
- Goldenrod herb works as well as the tincture but you may get an allergic reaction from smelling the herb. If you know you are allergic to this, leave this one out of your recipe.
- Ginger from the grocery store works fine; you may put it into capsules for yourself (size 0, 1 or 00).

There are probably dozens of herbs that can dissolve kidney crystals and stones. If you can only find several of those in the recipe, make the recipe anyway; it will just take longer to get results. Remember that vitamin B_6 and magnesium, taken daily, can prevent oxalate stones from forming. But only if you stop drinking tea. Tea has 15.6 mg oxalic acid per cup[37]. A tall glass of iced tea could give you over 20 mg oxalic acid. Switch to herb teas. Cocoa and chocolate, also, have too much oxalic acid to be used as beverages.

Remember, too, that phosphate crystals are made when you eat too much phosphate. Phosphate levels are high in meats, breads, cereals, pastas, and carbonated drinks. Eat less of these, and increase your milk (2%), fruits and vegetables. Drink at least 2 pints of water a day.

---

[37] Taken from *Food Values* 14ed by Pennington and Church 1985.

Cleanse your kidneys at least twice a year.

You can dissolve all your kidney stones in 3 weeks, but make new ones in 3 days if you are drinking tea and cocoa and phosphated beverages. None of the beverage recipes in this chapter are conducive to stone formation.

Liver Herbs

Don't confuse these liver herbs with the next recipe for the Liver Cleanse. This recipe contains herbs traditionally used to help the liver function, while the Liver Cleanse gets gallstones out.

6 parts comfrey root, *Symphytum officinale* (also called nipbone root)
6 parts tanner's oak bark, *Quercus alba* (white oak bark)
3 parts gravel root, *Eupatorium purpureum* (queen of the meadow)
3 parts Jacob's staff, *Verbascum thapsus* (mullein herb)
2 parts licorice root, *Glycyrrhiza glabra*
2 parts wild yam root, *Dioscorea villosa*
2 parts milk thistle herb, *Silybum marianum*
3 parts walnut bark, *Juglans nigra*, (black walnut bark)
3 parts marshmallow root, *Althea officinalis* (white mallow)
1 part lobelia plant, *Lobelia inflata* (bladder pod)
1 part skullcap, *Scutellaria lateriflora* (helmet flower)

Mix all the herbs. Add ½cup of the mixture to 2 quarts of water. Bring to a boil. Put lid on. Let sit for six hours. Strain and drink 1½cups per day. Put the strained herbs in the freezer and use them one more time.

Liver Cleanse

Cleansing the liver of gallstones dramatically improves digestion, which is the basis of your whole health. You can expect your allergies to disappear, too, more with each cleanse you do! Incredibly, it also eliminates shoulder, upper arm, and upper back pain. You have more energy and increased sense of well being.

Cleaning the liver bile ducts is the most powerful procedure that you can do to improve your body's health.

But it should not be done before the parasite program, and for best results should follow the kidney cleanse and any dental work you need.

It is the job of the liver to make bile, 1 to 1½quarts in a day! The liver is full of tubes (*biliary tubing*) that deliver the bile to one large tube (the *common bile duct*). The gallbladder is attached to the common bile duct and acts as a storage reservoir. Eating fat or protein triggers the gallbladder to squeeze itself empty after about twenty minutes, and the stored bile finishes its trip down the common bile duct to the intestine.

For many persons, including children, the biliary tubing is choked with gallstones. Some develop allergies or hives but some have no symptoms. When the gallbladder is scanned or X-rayed nothing is seen. Typically, they are not in the gallbladder. Not only that, most are too small and not calcified, a prerequisite for visibility on X-ray. There are over half a dozen varieties of gallstones, most of which have cholesterol crystals in them. They can be black, red, white, green or tan colored. The green ones get their color from being coated with bile. Notice in the picture how many have imbedded unidentified objects. Are they fluke remains? Notice how many are shaped like corks with longitudinal grooves below the tops. We can visualize the blocked bile ducts from such shapes. Other stones are composites–made of many smaller ones–showing that they regrouped in the bile ducts some time after the last cleanse.

At the very center of each stone is found a clump of bacteria, according to scientists, suggesting a dead bit of parasite might have started the stone forming.

As the stones grow and become more numerous the back pressure on the liver causes it to make less bile. Imagine the situation if your garden hose had marbles in it. Much less water would flow, which in turn would decrease the ability of the hose to squirt out the marbles. With gallstones, much less cholesterol leaves the body, and cholesterol levels may rise.



Fig. 89 These are gallstones.

Gallstones, being porous, can pick up all the bacteria, cysts, viruses and parasites that are passing through the liver. In this way “nests” of infection are formed, forever supplying the body with fresh bacteria. No stomach infection such as ulcers or intestinal bloating can be cured permanently without removing these gallstones from the liver.

Cleanse your liver twice a year.

Preparation.

- You can't clean a liver with living parasites in it. You won't get many stones, and you will feel quite sick. Zap daily the week before, or get through the first three weeks of the parasite killing program before attempting a liver cleanse. If you are on the maintenance parasite program, you are always ready to do the cleanse.
- Completing the kidney cleanse before cleansing the liver is also highly recommended. You want your kidneys, bladder and urinary tract in top working condition so they can efficiently remove any undesirable substances incidentally absorbed from the intestine as the bile is being excreted.
- Do any dental work first, if possible. Your mouth should be metal free and bacteria free (cavitations are cleaned). A toxic mouth can put a heavy load on the liver, burdening it immediately after cleansing. Eliminate that problem first for best results.

Ingredients

Epsom salts	4 tablespoons
Olive oil	half cup (light olive oil is easier to get down)
Fresh pink grapefruit	1 large or 2 small, enough to squeeze 2/3 to 3/4 cup juice

Ornithine	4 to 8, to be sure you can sleep. Don't skip this or you may have the worst night of your life!
Large plastic straw	To help drink potion.
Pint jar with lid	

Choose a day like Saturday for the cleanse, since you will be able to rest the next day.

Take no medicines, vitamins or pills that you can do without; they could prevent success. Stop the parasite program and kidney herbs, too, the day before.

Eat a no-fat breakfast and lunch such as cooked cereal with fruit, fruit juice, bread and preserves or honey (no butter or milk), baked potato or other vegetables with salt only. This allows the bile to build up and develop pressure in the liver. Higher pressure pushes out more stones.

2:00 PM. Do not eat or drink after 2 o'clock. If you break this rule you could feel quite ill later.

Get your Epsom salts ready. Mix 4 tbs. in 3 cups water and pour this into a jar. This makes four servings, ¾cup each. Set the jar in the refrigerator to get ice cold (this is for convenience and taste only).

6:00 PM. Drink one serving (¾cup) of the ice cold Epsom salts. If you did not prepare this ahead of time, mix 1 tbs. in ¾cup water now. You may add 1/8 tsp. vitamin C powder to improve the taste. You may also drink a few mouthfuls of water afterwards or rinse your mouth.

Get the olive oil and grapefruit out to warm up.

8:00 PM. Repeat by drinking another ¾cup of Epsom salts.

You haven't eaten since two o'clock, but you won't feel hungry. Get your bedtime chores done. The timing is critical for success; don't be more than 10 minutes early or late.

9:45 PM. Pour ½cup (measured) olive oil into the pint jar. Squeeze the grapefruit by hand into the measuring cup. Remove pulp with fork. You should have at least ½cup, more (up to ¾ cup) is best. You may top it up with lemonade. Add this to the olive oil. Close the jar tightly with the lid and shake hard until watery (only fresh grapefruit juice does this).

Now visit the bathroom one or more times, even if it makes you late for your ten o'clock drink. Don't be more than 15 minutes late.

10:00 PM. Drink the potion you have mixed. Take 4 ornithine capsules with the first sips to make sure you will sleep through the night. Take 8 if you already suffer from insomnia. Drinking through a large plastic straw helps it go down easier. You may use ketchup, cinnamon, or brown sugar to chase it down between sips. Take it to your bedside if you want, but drink it standing up. Get it down within 5 minutes (fifteen minutes for very elderly or weak persons).

Lie down immediately. You might fail to get stones out if you don't. The sooner you lie down the mote stones you will get out. Be ready for bed ahead of time. Don't clean up the kitchen. As soon as the drink is down walk to your bed and lie down flat on your back with your head up high on the pillow. Try to think about what is happening in the liver. Try to keep perfectly still for at least 20 minutes. You may feel a train of stones traveling along the bile ducts like marbles. There is no pain because the bile duct valves are open (thank you Epsom salts!). **Go to sleep**, you may fail to get stones out if you don't.

Next morning. Upon awakening take your third dose of Epsom salts. If you have indigestion or nausea wait until it is gone before drinking the Epsom salts. You may go back to bed. Don't take this potion before 6:00 am.

2 Hours Later. Take your fourth (the last) dose of Epsom salts. Drink ¾cup of the mixture. You may go back to bed.

After 2 More Hours you may eat. Start with fruit juice. Half an hour later eat fruit. One hour later you may eat regular food but keep it light. By supper you should feel recovered.

How well did you do? Expect diarrhea in the morning. Use a flashlight to look for gallstones in the toilet with the bowel movement. Look for the green kind since this is proof that they are genuine gallstones, not food residue. Only bile from the liver is pea green. The bowel movement sinks but gallstones float because of the cholesterol inside. Count them all roughly, whether tan or green. You will need to total 2000 stones before the liver is clean enough to rid you of allergies or bursitis or upper back pains permanently. The first cleanse may rid you of them for a few days, but as the stones from the rear travel forward, they give you the same symptoms again. You may repeat cleanses at two week intervals. Never cleanse when you are ill.

Sometimes the bile ducts are full of cholesterol crystals that did not form into round stones. They appear as a “chaff” floating on top of the toilet bowl water. It may be tan colored, harboring millions of tiny white crystals. Cleansing this chaff is just as important as purging stones.

How safe is the liver cleanse? It is very safe. My opinion is based on over 500 cases, including many persons in their seventies and eighties. None went to the hospital; none even reported pain. However it can make you feel quite ill for one or two days afterwards, although in every one of these cases the maintenance parasite program had been neglected. This is why the instructions direct you to complete the parasite and kidney rinse programs first.

CONGRATULATIONS

You have taken out your gallstones without surgery! I like to think I have perfected this recipe, but I certainly can not take credit for its origin. It was invented hundreds, if not thousands, of years ago, THANK YOU, HERBALISTS!

This procedure contradicts many modern medical viewpoints. Gallstones are thought to be formed in the gallbladder, not the liver. They are thought to be few, not thousands. They are not linked to pains other than gallbladder attacks. It is easy to understand why this is thought: by the time you have acute pain attacks, some stones are in the gallbladder, are big enough and sufficiently calcified to see on X-ray, and have caused inflammation there. When the gallbladder is removed the acute attacks are gone, but the bursitis and other pains and digestive problems remain.

The truth is self-evident. People who have had their gallbladder surgically removed still get plenty of green, bile-coated stones, and anyone who cares to dissect their stones can see that the concentric circles and crystals of cholesterol match textbook pictures of “gallstones” exactly.

Lugol’s Iodine Solution

It is too dangerous to buy a commercially prepared solution. It is certain to be polluted with propyl alcohol or wood alcohol. Make it yourself or ask your pharmacist to make it up for you. The recipe to make 1 liter (quart) is:

44 gm (1½ ounces) iodine, granular
88 gm (3 ounces) potassium iodide, granular

Dissolve the potassium iodide in about a pint of the water. Then add the iodine crystals and fill to the liter mark with water. It takes about 1 day to dissolve completely. Shake it from time to time. Keep out of sight and reach of children. Do not use if allergic to iodine. Be careful to avoid bottled water for preparation.

Vitamin D Drops

1 gram cholecalciferol (see Sources)
10 cups olive oil

Mix in a non-metal container. It may take a day of standing to dissolve fully. Refrigerate. Ten drops contain 40,000 iu. Use within a year.

Pathogen Frequencies

Living creatures emit a range of frequencies, also called *bandwidth*. As they age, the bandwidth shrinks. When they die sometimes all that is left is a single frequency.

Most of the organisms listed below are dead on commercially available and prepared slides (see *Sources* for biological supply companies). However they still exhibit a 5 KHz bandwidth, probably due to testing with a frequency generator that was only accurate to 100 Hz, and also due to using more voltage than necessary (like when a powerful radio station comes in at its own frequencies and ones nearby, too). Some testing was done with a more accurate frequency generator at a lower power level so some bandwidths are reported much more narrowly.

If the same person retests the same specimens with the same equipment within a few days, the results will be absolutely identical (within 1 Hz) 90% of the time. Why a few of the results will not be identical is not known. However different people, and even the same person at different times of the year, can notice that the perceived frequencies shift by as much as 3 KHz (still less than 1% change).

Some specimens have more than one range listed; this may be characteristic of the organism or may be due to having an undocumented organism on the same microscope slide.

Blank locations represent organisms for whom there are prepared slides available, but whose bandwidth has not been determined.

Bandwidth Of Organism Families

In general, the smaller the organism the lower the frequency and narrower the bandwidth. This chart shows the major families studied and where they fall in the spectrum.



Fig. 90 Chart of bandwidths for organism families.

Mold, Mold Toxin Frequencies

Other molds and mold toxins	**KHz**
Aflatoxin	177,188
Cytochalasin B	77,91
Ergot	295
Griseofulvin	288
Sorghum syrup	277
Sterigmatocystin	88,96,133,126
Zearalenone	100

Slime Molds	**KHz**
Arcyria	81
Lycogala	126
Stemonitis	211

Bacteria and Viruses

Including locations where I commonly found them.

	Low Freq (KHz)	**High Freq (KHz)**	**Use freq gen for 3 min @**
Acetobacter aceti			
Adenovirus	393	393	393
Adenovirus (2nd range)	371.45	386.90	
Agrobacterium tumefaciens			
Alcaligenes faecalis			
Alpha streptococcus	369.75	385.4	380,375
Azobacter chroococcum			
Bacillus anthracis causes anthrax in cattle (tooth)	393.5	398.05	395,364,368
Bacillus anthracis (2nd range)	363.2	365.3	
Bacillus anthracis (3rd range)	359.4	370.5	
Bacillus anthracis spores	386.95	391.45	388
Bacillus cereus	373.65	375.85	374.5
Bacillus megaterium			
Bacillus sterothermophilus			
Bacillus subtilis spores			
Bacillus subtilis var. niger	371.85	387.1	385,380,375
Bacteria capsules (capsular strain)	416.05	418.75	417.5
Bacterial capsules	357.6	362.4	360
Bacteroides fragilis found with common roundworm Ascaris	324.3	325.0	325
Bacteroides fragilis (2nd range)	325.7	326.0	
Beta streptococcus (tooth)	380.6	387.4	385
Blepharisma	405.65	407.45	406.5
Bordetella pertussis “whooping cough” (tooth)	329.85	332.25	331
Borellia burgdorferi Lyme disease	378.95	382.0	380
Branhamella (Neisseria) catarrhalis (has hole at 398)	394.9	396.7	396
Brucella abortus			
Cabbage Black Rot			
Campylobacter fetus smear	365.3	370.6	368
Campylobacter pyloridis	352.0	357.2	355
Candida albicans (pure powder) common yeast	384.2	388.4	386
Caulobacter vibrioides			
Central spores (bacillus smear)	372.45	378.65	376
Chlamydia trachomatis	379.7	383.95	381
Clostridium acetobutylicum	382.8	391.15	389,384
Clostridium botulinum (tooth) causes food poisoning	361.0	364.55	362

Clostridium perfringens			
Clostridium perfringens spores	394.2	398.1	396
Clostridium septicum	362.05	365.6	364
Clostridium sporogenes			
Clostridium tetani (tooth) causes tetanus			
Corynebacterium diphtheriae (tooth) causes diphtheria	340	344	342
Corynebacterium pseudodiphthericum			
Corynebacterium xerosis	315.65	316.8	316.0
Coxsackie virus B-1 found with Bacteroides fragilis	360.5	366.1	364
Coxsackie virus B-4 found with Bacteroides fragilis	361.45	363.7	362.5
Coxsackie virus B-4 (2nd range)	363.9	364.9	
Crithidia fasciculata			
Cytomegalovirus (CMV) antigen	408.35	410.75	409
Cytophaga rubra	428.1	432.2	430
Diplococcus diphtheriae	357.95	264.0	361
Diplococcus pneumoniae	351.65	368.45	365,360
Eikanella corrodens	379.5	384.3	382
Enterobacter aerogenes intestinal bacterium	374	374	374
Epstein Barre virus (EBV)	372.5	382.85	380,375
Erwinia amylovora	347.2	352.1	350
Erwinia carotovora	368.1	377.0	373
Escherichia coli (E. coli) intestinal bacterium	356	356	356,393
Escherichia coli (E. coli) (2nd range)	392	393	
Gaffkya tetragena causes respiratory infections	344.85	352.5	350
Gardnerella vaginalis ovarian and genital tract infection	338.0	342.55	340
Haemophilus influenzae bacterial meningitis, infects joints	336.41	336.41	336
Hepatitis B antigen	414.55	420.8	418
Herpes simplex 1	291.25	293.05	292,345.5
Herpes simplex 1 (2nd range)	345.35	345.75	
Herpes simplex 2 (fresh smear)	353.9	362.9	360,355
Herpes Zoster "shingles"	416.6	420.2	418
Histomonas meleagridis (liver)	376.55	378.7	377
Histoplasma capsulatum	298.3	304.85	302
HIV	365	365	365
Influenza A and B (flu shot)	313.35	323.9	320,315
Iron Bacterium Sphaerotilus			
Klebsiella pneumoniae causes pneumonia	398.45	404.65	401,419
Klebsiella pneumoniae (2nd range)	416.9	421.9	
Lactobacillus acidophilus (tooth)	346.05	351.65	349

Leptospira interrogans spirochete	397.05	401.1	399
Lumpy Jaw			
Measles antigen	369.5	373.0	371
Micrococcus luteus			
Micrococcus roseus			
Mumps antigen	377.6	384.65	382
Mycobacterium para TB			
Mycobacterium phlei	409.65	410.65	410.0
Mycobacterium smegmatis			
Mycobacterium tuberculosis (infec nodule) causes tuberculosis	430.55	434.2	432
Mycoplasma	322.85	323.9	323.5,346
Mycoplasma (range 2)	342.75	349.3	
Neisseria gonorrhea causes gonorrhea	333.85	336.5	334
Neisseria sicca			
Nocardia asteroides found in Parkinson's Disease	354.95	355.35	355.1,368
Nocardia asteroides (2nd range)	363.7	370	
Propionobacterium acnes	383.75	389.0	387
Proteus mirabilis	320.55	326.0	324,349
Proteus mirabilis (2nd range)	345.95	352.1	
Proteus vulgaris urinary tract pathogen	408.75	416.45	413,336,328
Proteus vulgaris (2nd range)	333.75	339.15	
Proteus vulgaris (3rd range)	327.2	329.5	
Pseudomonas aeruginosa found in open wounds	331.25	334.6	333
Pseudomonas fluorescens			
Respiratory syncytial virus	378.95	383.15	380
Rhizobium leguminosarum			
Salmonella enteriditis intestinal infection	329	329	329
Salmonella paratyphi	365.05	370.1	368,385
Salmonella typhimurium food poisoning, nervousness, apathy	382.3	386.55	355,386,390
Serratia marcescens	349.45	352.1	351
Shigella dysenteriae intestinal problems	390.089	390.089	390.089
Shigella flexneri depression	394	394	394
Shigella sonnei invades tumors	318	318	318
Sphaerotilus natans	388.4	393.45	391
Spirillum itersonil			
Spirillum serpens	378.35	382.8	380
Spirillum sinuosum			
Spirillum volutans			
Spores in bacteria spore stain			
Staphylococcus aureus (culture)	376.27	380.85	
Staphylococcus aureus (slide) source is tooth infection, causes abscesses, heart disease, invades tumors	381	381	378,381

Staphylococcus epidermidis infects skin and mucous membranes			
Streptococcus lactis occurs in milk	382	387	385
Streptococcus mitis lung infection, tooth infection, abscesses, causes stiff knees	313.8	321.1	318
Streptococcus pneumoniae causes pneumonia and inner ear disease	366.85	370.2	368
Streptococcus pyogenes (tooth)	360.5	375.3	373
Streptococcus sp. group G (tooth)	368.15	368.85	368
Sub terminal spores bac. smear	385.15	385.95	
Terminal spores bacillus smear			
Tobacco mosaic virus (tobacco)	427.15	429.55	428
Treponema pallidum causes syphilis	346.85	347.4	347
Troglodytella abrassari	377.75	385.2	383,419
Troglodytella abrassari (2nd range)	416.9	422.2	
Veillonella dispar	401.75	405.2	403
Vibrio (photobacterium) fischeri			

Roundworms, Flatworms, One-celled Animals

	Low Freq (KHz)	**High Freq (KHz)**	**To kill, use freq. gen for 3 min. at these frequencies**
Acanthamoeba culbertsoni			
Acanthocephala			
Anaplasma marginale	386.4	388.0	387,422
Anaplasma marginale (2nd range)	415.3	424	
Ancylostoma braziliense (adult)	397.6	403.25	401
Ancylostoma caninum	383.1	402.9	400,393,386
Ancylostoma duodenale male			
Anguillula aceti			
Ascaris larvae in lung common roundworm of cats and dogs	404.9	409.15	408
Ascaris lumbricoides (m and f)			same
Ascaris megalocephala (male)	403.85	409.7	408
Babesia bigemina			
Babesia canis smear			
Balantidium coli cysts	458.8	462.9	460
Balantidium sp. trophozoites (from guinea pig) parasitic ciliate			
Besnoitia (lung sect.) protozoan	352.8	361.4	358

Capillaria hepatica (liver sect.)	424.25	430.65	428
Chilomastix cysts (rat)	388.95	390.7	389,426
Chilomastix cysts (rat) (2nd range)	425.2	427.3	
Chilomastix mesnili (trophozoites)			same
Chilomonas, whole mount	393.75	400	398
Clinostomum metacercaria			
Clonorchis metacercariae			
Clonorchis sinensis	425.7	428.75	427
Clonorchis sinensis eggs			
Cryptocotyle lingua (adult)	409.95	416.0	414
Didinium			
Dientamoeba fragilis	401.35	406.05	404
Dipetalonema perstans (microfilaria human blood)			
Dirofilaria immitis dog heartworm	408.15	411.15	409
Echinoporyphium recurvatum	418.55	423.9	421
Echinostoma revolutum	425.5	429.65	428
Eimeria stiedae			
Eimeria tenella			
Endamoeba gingivalis trophozoite	433.8	441.0	438
Endolimax nana trophozoites and cysts	394.25	397.1	396,432
Endolimax nana trophozoites and cysts (2nd range)	430.5	433.35	
Entamoeba coli cysts			
Entamoeba coli trophozoites	397.0	400.35	398
Entamoeba histolytica trophozoite	381.1	387.8	385
Enterobius vermicularis	420.95	426.3	423
Eurytrema pancreaticum	420.35	422.3	421
Eurytrema pancreaticum stages			
Fasciola hepatica	421.35	427.3	425
Fasciola hepatica cercariae	423.8	430.6	427
Fasciola hepatica eggs	422.0	427.6	425
Fasciola hepatica metacercariae			
Fasciola hepatica miracidia	421.75	424.7	423
Fasciola hepatica rediae	420.6	427.5	425
Fasciolopsis buskii adult	427.7	435.1	434
Fasciolopsis buskii eggs	427.35	435.45	434
Fasciolopsis buskii eggs unincubated			
Fasciolopsis cercariae	429.5	436.25	434
Fasciolopsis miracidia	427.35	435.2	434
Fasciolopsis rediae	427.3	433.0	432
Fischoedrius elongatus	441.75	443.2	442
Gastrothylax elongatus	451.9	457.1	455
Giardia lamblia (trophozoites)	421.4	426.3	424
Giardia lamblia cysts			
Gyrodactylus	378.75	381.8	380
Haemonchus contortus	386.8	395.5	393
Haemoproteus			

Hasstile sig. tricolor (adult)	448.05	455.1	453
Heterakis			
Hypodereum conoideum	424.45	429.55	427
Iodamoeba butschlii trophozoites and cysts	437.85	448.5	445,402
Iodamoeba butschlii trophozoites and cysts (2nd range)	398.15	404.75	
Leishmania braziliensis	400.05	405.1	403
Leishmania donovani	398.0	402.65	400
Leishmania mexicana	400.2	403.8	402
Leishmania tropica	402.1	407.4	405
Leucocytozoon	397.45	402.55	400
Loa loa	360.551	360.551	361
Macracanthorhynchus	438.85	442.8	440
Metagonimus Yokogawai	437.35	442.1	440
Monocystis agilis			
Myxosoma	409.6	416.95	414
Naegleria fowleri	356.9	364.35	362
Naegleria fowleri (brain sec.)			
Necator americanus (infect larvae)			
Notocotylus quinqeserialis			
Onchocerca volvulus (tumor)	436.3	442.1	440
Paragonimus Westermanii adult	437.8	454.2	452,447
Passalurus ambiguus	428.8	444.15	441,437
Pelomyxa carolinensis			
Plasmodium cynomolgi	417.3	424.5	422
Plasmodium falciparum smear	372.3	373.8	373.0
Plasmodium vivax smear	438.15	445.1	442
Platynosomum fastosum adult			
Pneumocystis carnii (lung)	405.75	409.15	407
Prosthogonimus macrorchis(eggs)	396.85	404.75	401
Sarcina lutea			
Sarcocystis	450.55	454.95	452
Schistosoma haematobium	473	473	473
Schistosoma japonicum eggs			
Schistosoma mansoni	353	353	353
Stephanurus dentalus (ova)	457.35	463.1	461
Stigeoclonium	404.25	415.25	412,407
Strongyloides (filariform larva)	398.4	402.0	400
Strongyloides parasitic females			
Toxocara (eggs)			
Toxoplasma (human strain)	395.0	395.0	395
Trichinella spiralis (muscle)	403.85	405.57	404.5
Trichomonas muris			
Trichomonas vaginalis	378.0	383.6	381
Trichuris sp. (male)	388.3	408.9	406
Trypanosoma brucei	423.2	431.4	429
Trypanosoma cruzi (brain tissue)	460.2	465.65	463

Trypanosoma equiperdum	434.6	451.25	448,442,438
Trypanosoma gambiense	393.75	398.7	396
Trypanosoma lewisi (blood smear)	424.5	426.0	425
Trypanosoma rhodesiense	423.5	428.55	426
Urocleidus	442.35	450.0	447

Wart Frequencies

(Most of these are from homemade slides.)

	Low Freq	**High Freq**	**Use freq gen for 3 min @**
Wart BS	402	406	404
Wart CC	426	432.35	430
Wart FR	459.3	464.75	462
Wart HA	434.8	444.1	442,437
Wart HRCm	438.9	448.55	446,441
Wart human papilloma plantar	404.7	406.75	405
Wart human papilloma virus	402.85	410.7	407
Wart JB	418.75	422.4	420
Wart L arm	343.65	345.95	344
Wart papilloma cervix smear	404.05	404.6	404.3

Tapeworms

Tapeworms are segmented. The first segment is the head, called the *scolex*. Tapeworms grow by adding a new segment to their body.

Tapeworms can have very large bandwidths (range of frequencies), and it varies by the length of the specimen! It is as if each new segment has a unique, and slightly lower, frequency.

Do not use a frequency generator to kill tapeworms. If you accidentally kill middle segments instead of working your way up from the bottom, you may conceivably promote dispersion! Use only a zapper.

	Low Freq	**High Freq**
Cysticercus fasciolaris	436.4	440.05
Diphyllobothrium erinacei (Mansoni) (scolex)	467.25	487.55
Diphyllobothrium erinacei eggs		
Diphyllobothrium latum (scolex)	452.9	472.3
Dipylidium caninum (proglottid composite)	439.55	444.3
Dipylidium caninum (scolex)	451.95	472.15
Echinococcus granulosus	451.6	461.5
Echinococcus granulosus (cysts)	441.15	446.5
Echinococcus granulosus (eggs)		
Echinococcus multilocularis	455.85	458.35
Heterophyes heterophyes		
Hymenolepis cysticercoides	478.0	481.75
Hymenolepis diminuta	445	481.15
Hymenolepis diminuta ova		
Hymenolepis nana eggs		
Moniezia (scolex)	430.35	465.2
Moniezia expansa (composite)	430.35	465.2
Moniezia expansa eggs		
Multiceps serialis	453.6	457.8
Pigeon tapeworm		
Taenia pisiformis (cysticercus)	475.2	482.1
Taenia pisiformis eggs (ova)	465.2	469.7
Taenia saginata (cysticercus)	476.5	481.05
Taenia saginata eggs		
Taenia solium (cysticercus)	475	475
Taenia solium (scolex)	444.0	448.9
Taenia solium eggs		

Mite Frequencies

These are the organisms that cold viruses ride in with!

Mite	**KHz**
Demodex folliculorum follicle mite	682
Dermatophagoides dust mite	707
Meal mite	718
Ornithonyssus bird mite	877,878
Sarcoptes scabei itch	735

Miscellaneous Frequencies

	KHz
Blue-green Algae	256
Bryozoa cristatalla	396
Mucor mucedo	288
Rhizobium meliloti	330
Rotifer	1151

It's easy to make homemade slides when you or a family member is ill. Finding out the frequencies of these illnesses helps you identify them (use the Pathogen Frequency Chart) and also lets you know if you are chronically getting them back.

Unidentified pathogens	**Low Freq**	**High Freq**
A cold virus HRC	395.8	395.8
Fungus EW	362.0	364.9
Fungus JWB	397.2	400.75
Tooth decay	384.3	387.2
Tooth decay (N)	367.9	375.05
Tooth decay (N) (2nd range)	326.95	331.5
Tooth decay (N) (3rd range)	293.2	297.4
Tooth plaque I	378.8	383.05
Tooth plaque I (2nd range)	294.7	298.25
Tooth plaque I (3rd range)	233.1	238.2
Tooth plaque II	384.95	387.05
Tooth plaque II (2nd range)	278.75	284
Tooth plaque II (3rd range)	212.15	218
Tooth plaque II (4th range)	340.15	344.8
Tooth plaque II (5th range)	305.5	310.35

Toxic Elements

Although not living, solvents and toxins must exhibit characteristic frequencies, otherwise how could the Syncrometer detect specific ones? This needs further exploration.

Most of the toxic elements I use are metals, heavy metals and lanthanides. But some are not; examples are PCBs and formaldehyde.

Some important elements are missing, like iron, zinc and manganese. This is because I never could find them present in the white blood cells, and I finally gave up searching for them.

Below is a list of the 70 or so toxic elements I use. Most of them were obtained as Atomic Absorption Standard Solutions and are, therefore, very pure. This prevents mistakes in identifying a toxin. They were stored in ½ounce amber glass bottles with bakelite caps and permanently sealed with plastic film since testing did not require them to be opened (they get close enough to the frequency field). The exact concentration and the solubility characteristics are not important in this qualitative test. The main sources of these substances in our environment are given beside each item.

Toxic Substance	**Sources**
Aflatoxin B	beer, bread, apple cider vinegar, moldy fruit, nuts
Aluminum	cookware, deodorant, lotions, soaps
Aluminum silicate	salt, water softener
Antimony	fragrance in lotions, colognes
Arsenic	pesticide, “treated” carpet, wallpaper
Asbestos	clothes dryer belt, hair blower, paint on radiators
Barium	lipstick, bus exhaust
Benzalkonium chloride	toothpaste
3,4 Benzopyrene	flame cooked foods, toast
4,5 Benzopyrene	flame cooked foods, toast
Beryllium	hurricane lamps, gasoline, dentures, kerosene
Bismuth	colognes, lotions, antacids
Boron	
Bromine	bleached “brominated” flour
Cadmium	galvanized water pipes, old tooth fillings
Cerium	tooth fillings
Cesium	clear plastic bottles used for beverages
Chlorine	from Chlorox™ bleach
Chromium	cosmetics, water softener
Cobalt	detergent, blue and green body products
Copper	tooth fillings, water pipes
Dysprosium	paint and varnish
Erbium	packaging for food, pollutant in pills
Europium	tooth fillings
Europium oxide	tooth fillings, catalytic converter

Fiberglass	dust from remodeling or building insulation
Formaldehyde	foam in mattresses and furniture, paneling
Gadolinium	tooth fillings
Gallium	tooth fillings
Germanium	with thallium in tooth fillings (pollutant)
Gold	tooth fillings
Hafnium	hair spray, nail polish, pollutant in pills
Holmium	usually found in presence of PCBs
Indium	tooth fillings
Iridium	tooth fillings
Lanthanum	computer and printing supplies
Lead	solder joints in water pipes
Lithium	printing supplies
Lutetium	paint and varnish
Mercury	tooth fillings
Molybdenum	auto supplies
Neodymium	pollutant in pills
Nickel	tooth fillings, metal glasses frames
Niobium	pollutant in pills, foil packaging for food
Palladium	tooth fillings
Platinum	tooth fillings
Polychlorinated biphenyl PCB	detergent, hair spray, salves
Polyvinyl chloride acetate (PVC)	glues, building supplies, leaking cooling system
Praseodymium	pollutant in pills
Radon	cracks in basement cement, water pipes
Rhenium	spray starch
Rhodium	tooth fillings
Rubidium	tooth fillings
Ruthenium	tooth fillings
Samarium	tooth fillings
Scandium	tooth fillings
Selenium	
Silver	tooth fillings
Sodium fluoride	toothpaste
Strontium	toothpaste, water softener
Tantalum	tooth fillings
Tellurium	tooth fillings
Terbium	pollutant in pills
Thallium acetate	pollutant in mercury tooth fillings
Thorium nitrate	earth (dust)
Thulium	pollutant in many brands of Vitamin C
Tin	toothpaste
Titanium	tooth fillings, body powder
Tungsten	electric water heater, toaster, hair curler
Uranium acetate	earth (dust)
Vanadium pentoxide	gas leak in home, candles (not necessarily lit)

Ytterbium	pollutant in pills
Yttrium	pollutant in pills
Zirconium	deodorant, toothpaste

Solvents

This is a list of all the solvents I use together with the main source of them in our environment. These are chemicals, very pure, obtained from chemical supply companies, unless otherwise stated. Those marked with an asterisk (*) were the subject of a recent book *The Neurotoxicity of Solvents* by Peter Arlien-Soburg, 1992, CRC Press.

Solvent	**Source**
1,1,1, Trichloro ethane* (TCE)	flavored foods
2,5-Hexane dione*	flavored foods
2 Butanone* (methyl ethyl ketone)	flavored foods
2 Hexanone* (methyl butyl ketone)	flavored foods
2 Methyl propanol	
2 Propanol (propyl alcohol)	see the propyl alcohol list
Acetone	store-bought drinking water, cold cereals, pet food, animal feed
Acetonylacetone (2,5 hexanedione)	flavored foods
Benzene	see the benzene list (page 354)
Butyl nitrite	
Carbon tetrachloride	store-bought drinking water, cold cereals, pet food, animal feeds
Decane	health food cookies and cereals
Denatured alcohol	obtained from pharmacy
Dichloromethane* (methylene chloride)	store-bought orange juice, herb tea blends
Gasoline regular leaded	obtained at gasoline station
Grain alcohol	95% ethyl alcohol obtained at liquor store
Hexanes*	decaffeinated beverages
Isophorone	flavored foods
Kerosene	obtained at gasoline station
Methanol (wood alcohol)	colas, artificial sweeteners, infant formula
Mineral oil	lotions

Mineral spirits	obtained from paint store
Paradichlorobenzene	mothballs
Pentane	decaffeinated beverages
Petroleum ether	in some gasolines
Styrene*	styrofoam dishes
Toluene*	store-bought drinking water, cold cereals
Trichloroethylene* (TCEthylene)	flavored foods
Xylene*	store-bought drinking water, cold cereals

Pathogen Frequency Chart

Use this chart if you know the frequency and wonder what the pathogen might be.

	KHz		5	0			1	0	0			1	5	0			2	0	0			2	5	0			3	0	0			3	5	0
Pathogen	Low	High																																
Cytochalasin B	77.00	77.00			m																													
Arcyria	81.00	81.00				s																												
Sterigmatocystin	88.00	88.00				m																												
Cytochalasin B (2nd)	91.00	91.00					m																											
Sterigmatocystin (2nd)	96.00	96.00					m																											
Zearalenone	100.00	100.00						m																										
Lycogala	126.00	126.00								s																								
Sterigmatocystin (4th)	126.00	126.00								m																								
Sterigmatocystin (3rd)	133.00	133.00									m																							
Aflatoxin	177.19	177.19													m																			
Stemonitis	211.00	211.00																	s															
Sorghum syrup	277.00	277.00																							m									
Griseofulvin	288.00	288.00																								m								
Herpes simplex 1	291.25	293.05																									v							
Ergot	295.00	295.00																									m							
Histoplasma capsulatum	298.30	304.85																									b	b						
Corynebacterium xerosis	315.65	316.80																											b					
Shigella sonnei	318.00	318.00																											b					
Streptococcus mitis	313.80	321.10																											b	b				
Influenza A and B (flusho	313.35	323.90																											v	v				
Mycoplasma	322.85	323.90																												b				
Bacteroides fragilis	324.30	325.00																												b				
Proteus mirabilis	320.55	326.00																												b				
Bacteroides fragilis (2nd)	325.70	326.00																												b				
Salmonella enteriditis	329.00	329.00																												b				
Proteus vulgaris (3rd)	327.20	329.50																												b				
Bordetella pertussis	329.85	332.25																												b	b			
Pseudomonas aeruginos	331.25	334.60																													b			
Haemophilus influenzae	336.41	336.41																													b			
Neisseria gonorrhea	333.85	336.50																													b			
Proteus vulgaris (2nd)	333.75	339.15																													b			
Gardnerella vaginalis	338.00	342.55																													b	b		
Corynebacterium diphthe	340.00	344.00																														b		
Herpes simplex 1 (2nd)	345.35	345.75																														v		
Wart L arm	343.65	345.95																														w		
Treponema pallidum	346.85	347.40																														b		
Mycoplasma (2nd)	342.75	349.30																														b		
Lactobacillus acidophilus	346.05	351.65																														b	b	
Proteus mirabilis (2nd)	345.95	352.10																														b	b	
Erwinia amylovora	347.20	352.10																														b	b	
Serratia marcescens	349.45	352.10																														b	b	
Gaffkya tetragena	344.85	352.50																														b	b	
Schistosoma mansoni	353.00	353.00																															p	
Nocardia asteroides	354.95	355.35																															b	
Escherichia coli (E. coli)	356.00	356.00																															b	
Campylobacter pyloridis	352.00	357.20																															b	
Loa loa	360.55	360.55																																p
Besnoitia (lung sect.) prot	352.80	361.40																															p	p
Bacterial capsules	357.60	362.40																															b	b
Herpes simplex 2 (fresh s	353.90	362.90																															v	v
Coxsackie virus B-4	361.45	363.70																																v

s = slime mold, m = mold, b = bacteria, v = virus, y = yeast, p = parasite (one-celled animals), t = tapeworm, x = mite

	KHz																			
			3	5	0			4	0	0			4	5	0			5	0	0
Pathogen	Low	High																		
Diplococcus diphtheriae	357.95	364.00		b	b															
Naegleria fowleri	356.90	364.35		p	p															
Clostridium botulinum	361.00	364.55			b															
Coxsackie virus B-4 (2nd)	363.90	364.90			v															
Bacillus anthracis (2nd)	363.20	365.30			b															
Clostridium septicum	362.05	365.60			b															
Coxsackie virus B-1	360.50	366.10			v															
Diplococcus pneumoniae	351.65	368.45		b	b															
Streptococcus sp. group	368.15	368.85			b															
Nocardia asteroides (2nd	363.70	370.00			b	b														
Salmonella paratyphi	365.05	370.10			b	b														
Streptococcus pneumoni	366.85	370.20			b	b														
Bacillus anthracis (3rd)	359.40	370.50		b	b	b														
Campylobacter fetus sme	365.30	370.60			b	b														
Measles antigen	369.50	373.00			v	v														
Plasmodium falciparum s	372.30	373.80				p														
Enterobacter aerogenes	374.00	374.00				b														
Streptococcus pyogenes	360.50	375.30			b	b														
Bacillus cereus	373.65	375.85				b														
Erwinia carotovora	368.10	377.00			b	b														
Central spores (bacillus s	372.45	378.65				b														
Histomonas meleagridis (l	376.55	378.70				b														
Staphylococcus aureus (c	376.27	380.85				b	b													
Staphylococcus aureus (s	381.00	381.00					b													
Gyrodactylus	378.75	381.80				p	p													
Borellia burgdorferi	378.95	382.00				v	v													
Spirillum serpens	378.35	382.80				b	b													
Epstein Barre virus (EBV)	372.50	382.85				v	v													
Respiratory syncytial viru	378.95	383.15				v	v													
Trichomonas vaginalis	378.00	383.60				p	p													
Chlamydia trachomatis	379.70	383.95				b	b													
Eikanella corrodens	379.50	384.30				b	b													
Mumps antigen	377.60	384.65				v	v													
Troglodytella abrassari	377.75	385.20				b	b													
Alpha streptococcus	369.75	385.40			b	b	b													
Sub terminal spores bac.	385.15	385.95					b													
Salmonella typhimurium	382.30	386.55					b													
Adenovirus (2nd range)	371.45	386.90				v	v													
Streptococcus lactis	382.00	387.00					b													
Bacillus subtilis var. niger	371.85	387.10				b	b													
Beta streptococcus	380.60	387.40					b													
Entamoeba histolytica tro	381.10	387.80					p													
Anaplasma marginale	386.40	388.00					p													
Candida albicans	384.20	388.40					y													
Propionobacterium acnes	383.75	389.00					b													
Shigella dysenteriae	390.09	390.09						b												
Chilomastix cysts (rat)	388.95	390.70					p	p												
Clostridium acetobutylicu	382.80	391.15					b	b												
Bacillus anthracis spores	386.95	391.45					b	b												
Escherichia coli (E. coli)	392.00	393.00						b												
Adenovirus	393.00	393.00						v												
Sphaerotilus natans	388.40	393.45					b	b												
Shigella flexneri	394.00	394.00						b												
Toxoplasma (human strai	395.00	395.00						p												
Haemonchus contortus	386.80	395.50					p	p												
Branhamella (Neisseria)	394.90	396.70						b												
Endolimax nana trophozo	394.25	397.10						p												
Bacillus anthracis	393.50	398.05						b												
Clostridium perfringens s	394.20	398.10						b												

s = slime mold, m = mold, b = bacteria, v = virus, y = yeast, p = parasite (one-celled animals), t = tapeworm, x = mite

	KHz																			
			3	5	0			4	0	0			4	5	0			5	0	0
Pathogen	Low	High																		
Trypanosoma gambiense	393.75	398.70						p												
Chilomonas, whole mount	393.75	400.00						p	p											
Entamoeba coli trophozoi	397.00	400.35						p	p											
Leptospira interrogans	397.05	401.10						b	b											
Strongyloides (filariform l	398.40	402.00						p	p											
Leucocytozoon	397.45	402.55						p	p											
Leishmania donovani	398.00	402.65						p	p											
Ancylostoma caninum	383.10	402.90					p	p	p											
Ancylostoma braziliense (	397.60	403.25						p	p											
Leishmania mexicana	400.20	403.80							p											
Wart papilloma cervix sm	404.05	404.60							w											
Klebsiella pneumoniae	398.45	404.65						b	b											
Prosthogonimus macrorc	396.85	404.75						p	p											
Iodamoeba butschlii (2nd)	398.15	404.75						p	p											
Leishmania braziliensis	400.05	405.10							p											
Veillonella dispar	401.75	405.20							b											
Trichinella spiralis (muscl	403.85	405.57							p											
Wart BS	402.00	406.00							w											
Dientamoeba fragilis	401.35	406.05							p											
Wart human papilloma pl	404.70	406.75							w											
Leishmania tropica	402.10	407.40							p											
Blepharisma	405.65	407.45							b											
Trichuris sp. (male)	388.30	408.90					p	p	p											
Ascaris larvae in lung	404.90	409.15							p											
Pneumocystis carnii (lung	405.75	409.15							p											
Ascaris megalocephala (	403.85	409.70							p											
Mycobacterium phlei	409.65	410.65							b	b										
Wart human papilloma vir	402.85	410.70							w	w										
Cytomegalovirus (CMV) a	408.35	410.75							v	v										
Dirofilaria immitis	408.15	411.15							p	p										
Stigeoclonium	404.25	415.25							p	p										
Cryptocotyle lingua (adult	409.95	416.00							p	p										
Proteus vulgaris	408.75	416.45							b	b										
Myxosoma	409.60	416.95							p	p										
Bacteria capsules (capsul	416.05	418.75								b										
Herpes Zoster	416.60	420.20								v	v									
Hepatitis B antigen	414.55	420.80								v	v									
Klebsiella pneumoniae (2	416.90	421.90								b	b									
Troglodytella abrassari (2	416.90	422.20								b	b									
Eurytrema pancreaticum	420.35	422.30									p									
Wart JB	418.75	422.40								w	w									
Echinoporyphium recurva	418.55	423.90								p	p									
Anaplasma marginale (2n	415.30	424.00								p	p									
Plasmodium cynomolgi	417.30	424.50								p	p									
Fasciola hepatica miracidi	421.75	424.70									p									
Trypanosoma lewisi (bloo	424.50	426.00									p									
Enterobius vermicularis	420.95	426.30									p									
Giardia lamblia (trophozoi	421.40	426.30									p									
Fasciola hepatica	421.35	427.30									p									
Chilomastix cysts (rat) (2	425.20	427.30									p									
Fasciola hepatica rediae	420.60	427.50									p									
Fasciola hepatica eggs	422.00	427.60									p									
Trypanosoma rhodesiens	423.50	428.55									p									
Clonorchis sinensis	425.70	428.75									p									
Hypodereum conoideum	424.45	429.55									p									
Tobacco mosaic virus	427.15	429.55									v									
Echinostoma revolutum	425.50	429.65									p									
Fasciola hepatica cercari	423.80	430.60									p	p								
Capillaria hepatica (liver s	424.25	430.65									p	p								

s = slime mold, m = mold, b = bacteria, v = virus, y = yeast, p = parasite (one-celled animals), t = tapeworm, x = mite

	KHz		3	5	0	4	0	0			4	5	0		5	0	0
Pathogen	Low	High															
Trypanosoma brucei	423.20	431.40						p	p								
Cytophaga rubra	428.10	432.20						b	b								
Wart CC	426.00	432.35						w	w								
Fasciolopsis rediae	427.30	433.00						p	p								
Endolimax nana (2nd)	430.50	433.35							p								
Mycobacterium tuberculo	430.55	434.20							b								
Fasciolopsis buskii	427.70	435.10						p	p								
Fasciolopsis miracidia	427.35	435.20						p	p								
Fasciolopsis buskii eggs	427.35	435.45						p	p								
Fasciolopsis cercariae	429.50	436.25						p	p								
Cysticercus fasciolaris	436.40	440.05							t	t							
Endamoeba gingivalis tro	433.80	441.00							p	p							
Onchocerca volvulus (tu	436.30	442.10							p	p							
Metagonimus Yokogawai	437.35	442.10							p	p							
Macracanthorhynchus	438.85	442.80							p	p							
Fischoedrius elongatus	441.75	443.20								p							
Wart HA	434.80	444.10							w	w							
Passalurus ambiguus	428.80	444.15						p	p	p							
Dipylidium caninum	439.55	444.30							t	t							
Plasmodium vivax smear	438.15	445.10							p	p							
Echinococcus granulosus	441.15	446.50								t							
Iodamoeba butschlii troph	437.85	448.50							p	p							
Wart HRCm	438.90	448.55							w	w							
Taenia solium (scolex)	444.00	448.90								t							
Urocleidus	442.35	450.00								p	p						
Trypanosoma equiperdu	434.60	451.25							p	p	p						
Paragonimus Westermani	437.80	454.20							p	p	p						
Sarcocystis	450.55	454.95									p						
Hasstile sig. tricolor (adult	448.05	455.10								p	p						
Gastrothylax elongatus	451.90	457.10									p						
Multiceps serialis	453.60	457.80									t						
Echinococcus multilocula	455.85	458.35									t						
Echinococcus granulosus	451.60	461.50									t	t					
Balantidium coli cysts	458.80	462.90									p	p					
Stephanurus dentalus (ov	457.35	463.10									p	p					
Wart FR	459.30	464.75									w	w					
Moniezia (scolex)	430.35	465.20							t	t	t	t					
Moniezia expansa (comp	430.35	465.20							t	t	t	t					
Trypanosoma cruzi (brain	460.20	465.65										p					
Taenia pisiformis eggs (o	465.20	469.70										p					
Dipylidium caninum (scol	451.95	472.15									t	t	t				
Diphyllobothrium latum (s	452.90	472.30									t	t	t				
Schistosoma haematobiu	473.00	473.00											p				
Taenia solium (cysticercu	475.00	475.00											t				
Taenia saginata (cysticer	476.50	481.05											t	t			
Hymenolepis diminuta	445.00	481.15								t	t	t	t	t			
Hymenolepis cysticercoid	478.00	481.75											t	t			
Taenia pisiformis (cystice	475.20	482.10											t	t			
Diphyllobothrium erinacei	467.25	487.55										t	t	t			

s = slime mold, m = mold, b = bacteria, v = virus, y = yeast, p = parasite (one-celled animals), t = tapeworm,
x = mite

	KHz		5	5	0			6	0	0			6	5	0			7	0	0			7	5	0			8	0	0			8	5	0
Pathogen	Low	High																																	
Demodex folliculorum foll	682.00	682.00															x																		
Dermatophagoides dust	707.00	707.00																	x																
Meal mite	718.00	718.00																		x															
Sarcoptes scabei itch	735.00	735.00																				x													
Ornithonyssus bird mite	877.00	878.00																																	

s = slime mold, m = mold, b = bacteria, v = virus, y = yeast, p = parasite (one-celled animals), t = tapeworm, x = mite

Sources

This list was accurate as this book went to press. Only the vitamin sources listed were found to be pollution-free, and only the herb sources listed were found to be potent, although there may be other good sources that have not been tested. The author has no financial interest in, influence on, or other connection with any company listed, except for having family members in the Self Health Resource Center.

Note to readers outside the United States of America:

Sources listed are typically companies within the United States because they are the ones I am most familiar with. You may be tempted to try a more convenient manufacturer in your own country and hope for the best. I must advise against this! In my experience, an uninformed manufacturer most likely has a polluted product! Your health is worth the extra effort to obtain the products that make you well. One bad product can keep you from reaching that goal. This chapter will be updated as I become aware of acceptable sources outside the United States. Best of all is to learn to test products yourself.

Item	**Source**
Amber bottles, ½ ounce	Drug store, Continental Glass & Plastic, Inc. (large quantities)
Apricot Kernel Oil	Now Foods

Arginine	Now Foods, Jomar Labs
Artemesia (wormwood) seed	R. H. Shumway
Baking soda (sodium bicarbonate)	Spectrum Chemical Co.
Beet root	San Francisco Herb & Natural Food Co.
Belts for clothes dryer	Three that tested negative to asbestos are: Maytag™ 3-12959 Poly-V belt, Whirlpool™ FSP 341241 Belt-Drum Dr. (replaces 660996), and Bando™ V-Belt A-65. Bando American makes other belts, some of which might be the right size for your dryer. Call for a dealer near you, make sure it says "Made In America", right on the belt.
Black cherry concentrate	Health food store
Black Walnut Hull Tincture	Self Health Resource Center, New Action Products
Borax, pure	Grocery store
Boric acid, pure	Now Foods, health food store, pharmacy
Cascara sagrada	Natures Way, health food store
Chemicals for testing.	Aldrich Chemical Co., Spectrum Chemical Co., ICN Biomedicals, Inc. (research chemicals only, including genistein), Boehringer Mannheim Biochemicals (research only)
Cholecalciferol	Spectrum Chemical Co.
Citric acid	Now Foods or health food store
Cloves	San Francisco Herb & Natural Food Co. (ASK for fresh)
Cornstarch	Lady Lee is the only unpolluted brand found so far
Dental information	Tooth Truth, by Frank J. Jerome, available from New Century Press.
EDTA	Spectrum Chemical Co.
Electronic parts	A Radio Shack near you.
Empty gelatin capsules size 00	Now Foods, or your health food store

Filters, pure charcoal	Pure Water Products (pitchers), Seagull Distribution Co. (faucet, shower, whole house)
Flaxseed oil	Omega Nutrition USA, Inc.
Fucus	San Francisco Herb & Natural Food Co.
Ginger capsules	Now Foods
Goldenrod tincture	Dragon River Herbals, Blessed Herbs
Grain alcohol	Liquor store, as vodka, Everclear™
Gravel root (herb)	San Francisco Herb & Natural Food Co.
Histidine	500 mg from Jomar Labs
Homeopathic remedies	Dolisos America, Inc., and others
Hydrangea (herb)	San Francisco Herb & Natural Food Co.
Hydrogen peroxide 35% (food grade)	New Horizons Trust
Iodine, pure	Spectrum Chemical Co.
Lugol's iodine	For slide staining (not internal use) from Spectrum Chemical Co., and farm animal supply store. For internal use must be made from scratch.
Lysine	Bronson Pharmaceuticals
Magnesium oxide	Bronson Pharmaceuticals
Marshmallow root (herb)	San Francisco Herb & Natural Food Co.
Microscope slides and equipment	Carolina Biological Supply Company, Ward's Natural Science, Inc., Southern Biological Supply Company, Fisher-EMD
Microscopes	Carolina Biological Supply Company, Ward's Natural Science, Inc., Edmund Scientific Co.
Milk Thistle	Herb companies.
Mullein tea	San Francisco Herb & Natural Food Co.
Niacin	100 mg or 250 mg time release, Bronson Pharmaceuticals
Ornithine	Now Foods, Jomar Labs
Ortho-phospho-tyrosine	Aldrich Chemical Co.
Ozonator	Superior Health Products, LLC
P24 antigen sample	Bachem Fine Chemicals Inc.
PABA (para amino benzoic acid)	Bronson Pharmaceuticals
Pantothenic acid	Bronson Pharmaceuticals

Peroxy	See Hydrogen peroxide.
Photo-micrographic camera and film	Ward's Natural Science, Inc.
Potassium bicarbonate	Spectrum Chemical Co., or pharmacy
Potassium chloride	Now Foods, Spectrum Chemical Co.
Potassium iodide, pure	Spectrum Chemical Co.
Rascal	Kroeger Herb Products, New Action Products (as Raz-Caps)
Salt (sodium chloride), pure	Spectrum Chemical Co., get USP grade
Sodium alginate	Spectrum Chemical Co. or health food store
Stevia powder	Now Foods
Tea	San Francisco Herbs, buy in bulk, any single herb variety.
Thallium, homeopathic	Dolisos America, Inc.
Thioctic acid (also called lipoic acid)	Maypro Industries
Uva Ursi	Natures Way or health food store
Vanilla extract	Durkee's^{TM} or Mexican brands
Vegetable glycerin	Now Foods or health food store
Vitamin B Complex	Bronson Pharmaceuticals
Vitamin B_2 (riboflavin)	Nutrition Headquarters (250 mg), or Bronson Pharmaceuticals (100 mg)
Vitamin B_6	Bronson Pharmaceuticals, EDOM Labs
Vitamin B_{12} lozenges	Bronson Pharmaceuticals
Vitamin C (ascorbic acid)	Self Health Resource Center
Vitamin D 50,000iu	From dentist, by prescription, or see Recipes.
Vitamin E capsules	Bronson Pharmaceuticals
Vitamin E Oil	Now Foods
Washing soda (sodium carbonate)	Grocery store
Water filter pitchers	Pure Water Products
Wormwood capsules	Self Health Resource Center, Kroeger Herb Products, New Action Products
Zinc	Bronson Pharmaceuticals
Zinc oxide	Spectrum Chemical Co.

Aldrich Chemical Co.
P.O. Box 355
Milwaukee, WI 53201
(414) 273-3850

Bachem Fine Chemicals Inc.
3132 Kashiwa St.
Torrance, CA 90505
(310) 539-4171

Bando American Inc.
1149 West Bryn Mawr
Itasca, IL 60143
(800) 829-6612
(630) 773-6600

Blessed Herbs
109 Barre Plaines Rd.
Oakham, MA 01068
(508) 882-3839

Boehringer Mannheim
Biochemicals
9115 Hague Rd.
P.O. Box 50414
Indianapolis, IN 46250
(800) 262-1640
(317) 849-9350

Bronson Pharmaceuticals
Div. of Jones Medical Industry
1945 Craig Road
P.O. Box 46903
St. Louis, MO 63146-6903
(800) 235-3200 retail
(800) 525-8466 wholesale

Carolina Biological Supply Co.
2700 York Rd.
Burlington, NC 27215
(800) 334-5551
(919) 584-0381

Continental Glass & Plastic, Inc.
841 West Cermak Rd.
Chicago, IL 60608-4582
(312) 666-2050

Dolisos America, Inc.
3014 Rigel Ave
Las Vegas, NV 89102
(800) 365-4767
(702) 871-7153

Dragon River Herbals
PO Box 74
Ojo Caliente, NM 87549
(800) 813-2118
(505) 583-2118

Edmund Scientific Co.
101 E. Gloucester Pike
Barrington, NJ 08007
(856) 573-6250

EDOM Labs, Inc.
860 Grand Boulevard
P.O. Box 780
Deer Park, NY 11729
(516) 586-2266
(800) 723-3366

Fisher Scientific EMD
485 S. Frontage Rd.
Burr Ridge, IL 60521
(800) 955-1177

ICN Pharmaceuticals, Inc.
Biomedical Division
3300 Hyland Ave.
Costa Mesa, CA 92626
(714) 545-0113
(800) 854-0530

Jomar Labs
251-B East Hacienda Avenue
Campbell, CA 95008
(800) 538-4545
(409) 374-5920

Kroeger Herb Products
(wholesale:)
805 Walnut St.
Boulder, CO 80302
(800) 225-8787
(303) 443-0261
(for retail call:)
Hanna's Herb Shop
5684 Valmont Rd.
Boulder, CO 80301
(800) 206-6722

Maypro Industries
2700 Westchester Ave.
Purchase, NY 10577
(914) 251-0701

Nature's Way
10 Mountain Springs Pkwy
Springville, UT 84663
(800) 962-8873
(801) 489-1500

New Action Products (USA)
P.O. Box 540
Orchard Park, NY 14127
(800) 455-6459
(716) 662-8000

New Action Products (CANADA)
PO Box 141
Grimsby, Ont. L3M4G5 Canada
(800) 541-3799
(716) 873-3738

New Century Press
1055 Bay Blvd., Suite C
Chula Vista, CA 91911
(800) 519-2465
(619) 476-7400

New Horizons Trust
53166 St. Rt. 681
Reedsville, OH 45772
(800) 755-6360
(614) 378-6366

Now Foods
395 Glen Ellen Road
Glen Ellen, IL 60108
(630) 545-9098

Omega Nutrition USA, Inc.
6515 Aldrich Rd.
Bellingham, WA 98226
(800) 661-3529

Superior Health Products, LLC
13549 Ventura Blvd.
Sherman Oaks, CA 91423
(800) 700-1543
(818) 986-9456

Pure Water Products
10332 Parkview Ave.
Westminster, CA 92683
(800) 478-7987

R. H. Shumway
P.O. Box 1
Graniteville, SC 29829
(803) 663-9771

San Francisco Herb & Natural
Food Co.
1010 46th St.
Emeryville, CA 94608
(800) 227-2830 wholesale
(510) 601-0700 retail

Seagull Distribution Co.
3372 Baltimore St.
San Diego, CA 92117
(858) 483-0264

Self Health Resource Center
1055 Bay Blvd., Suite A
Chula Vista, CA 91911
(800) 873-1663
(619) 409-9500 (USA)
(780) 475-2403 (Canada)

Southern Biological Supply
Company
P.O. Box 368
McKenzie, TN 38201
(800) 748-8735
(901) 352-3337

Spectrum Chemical Co.
14422 South San Pedro Street
Gardena, CA 90248
(800) 772-8786
(310) 516-8000

Ward’s Natural Science, Inc.
5100 West Henrietta Road
Rochester, NY 14586
(716) 359-2502
(800) 962-2660

Finale

I hope you have come to the same happy conclusion that I did a few years ago! That we humans don't have hundreds of different maladies and disturbances. **We only have two!** Things that crawl or climb into us. And toxins: unnatural chemicals that we unknowingly inhale or consume.

The living things are both large and small: from worms we can see, to microscopic bacteria, viruses and fungi. The non living things are pollutants in our air, food, dental metal and body products. Taking in a lot of pollutants hampers the body's ability to kill and get rid of the invaders. And so, gradually, as we get older or sicker, the body's invaders get the upper hand and take over. Don't be discouraged if you have lupus, cerebral palsy, cirrhosis, or any complex-sounding disease. Every disease is an example of the same process.

The good news is that our body can reclaim its sovereignty by throwing the rascals out. We must assist by throwing the pollutants out. Fortunately, we don't have to do the whole job ourselves, we only need to assist. Our body has miraculous powers to clean itself up.

By reducing chronic disease to two problems, it becomes manageable. Ill health, even aging, can be reversed. Health comes back and rewards you.

With the new electronic insights and technology, our parasitic invaders can be vanquished with the closing of a switch. Preventing reinfection is the bigger challenge. Similarly, pollutants can be uncovered in as short a time as days, short enough to turn any sick, even terminal, sufferer's verdict around before tragedy occurs.

The tragedies of surgery, organ replacements, radiation, chemotherapies, doses of drugs, even death can be avoided. Reversing illness and turning into a shining example of your former healthy self could be the most exciting adventure of your life.

Killing your invaders is an easy matter: you simply purchase or build the device that can do that and take the proper herbs. Cleaning up dentalware is under your control, too—a financial expense not beyond your reach, hopefully. Trading your body products for unpolluted varieties is a job but not insurmountable. Cleaning your environment may be the stumbling block. If you can't unpollute your air, water, carpets, furniture, move. Move to a healthier dwelling! Get rid of it all. Like a cat that moves her kittens to a safer place, just move.

The healthiest house is no house. If you have been quite ill, move far enough south to avoid heating and cooling. Sit outside in the shade all day. Use your new wisdom and sharp eye to choose a new dwelling as free of pollutants as you can. No refrigerator indoors. No window air conditioner. No fiberglass insulation. No fossil fuels. No attached garage. No carpets or stuffed furniture, no foam bedding, no fresh paint, no pesticide. Go primitive. Health is primitive. You were born primitive—with health. Even if you weren't, you can undo much of the "inherited" damage.

Don't listen to the new doomsayers, who persuade you nothing can be done unless a gene is replaced. Your genes have been reliable for millions of years. Genes are the most reliable of all biological chemicals in your body. They are not faulty. They are hampered in their tasks. They are commandeered by metals and other species' genes. Those of parasites, bacteria, and viruses. They wouldn't be there if pollutants weren't there. They allow invaders into the most jealously guarded recess of your being: your genes. But now you can throw the rascals out and reclaim your territory. It is not new genes that you need. You simply need your own genes back on the job, directed by your own body, working for you.

Index

A

abdominal pain, 99, 203, 268, 299
abscess, 54, 79, 135, 153, 158, 159, 163, 164, 216, 231, 510
Acanthocephala, 138, 274, 566
acetic acid, 296
acetone, 122, 162, 208, 320
acetylcholine, 221, 238
acidophilus, 21, 100, 564, 576
acne, 167, 192, 193, 194
acupuncture, 51, 465
Adenovirus, 13, 176, 179, 199, 357, 358, 359, 360, 361, 363, 368, 563, 577
adrenal gland, 60, 113, 114, 143, 210, 212, 217, 281, 291, 373
aflatoxin, 38, 177, 180, 186, 225, 261, 280, 348, 349, 381, 382, 383, 384, 386, 390, 392, 422, 491, 493, 494, 519
AIDS, 11, 35, 36, 90, 119, 126, 131, 149, 252, 351, 352, 353, 356, 368, 372, 385, 442, 443, 458, 493, 500
air conditioner, 40, 284, 313, 323, 346, 403, 446, 590
air filter, 137, 284
albuminuria, 417
alcoholism, 227, 228, 229, 230, 386
alkaline phosphatase, 80, 217
alkaline tide, 57
allergy, 85, 102, 105, 107, 111, 126, 135, 139, 140, 163, 169, 175, 190, 191, 216, 222, 223, 224, 225, 226, 242, 246, 258, 386, 495, 553, 558
aluminum, 37, 112, 137, 141, 171, 180, 181, 187, 189, 212, 244, 247, 269, 271, 274, 305, 310, 311, 314, 415, 421, 423, 424, 430, 431, 433, 434, 435, 436, 438, 439, 450, 461, 473, 484, 485, 486, 487, 514, 521, 525, 526, 533, 543
aluminum silicate, 37, 138, 141, 212, 271
alveolar cavitational osteopathosis, 410
Alzheimer's, 33, 219, 250, 252, 269, 270, 272, 372, 495, 526
amalgam, 37, 65, 71, 107, 115, 157, 180, 409, 410, 413, 414, 416, 417, 418, 475, 485
amalgam tattoo, 410
American Dental Association (ADA), 37, 409, 414, 416
amino acid, 85, 232, 244
ammonia, 125, 243, 244, 320, 326
amoeba, 106, 274
Ancylostoma, 256, 257, 262, 566, 578
anemia, 76, 162, 279, 285, 286
anesthesia, 90
angina, 176, 417
animal dander, 104, 135
animal feed, 125, 347, 574
ankle swelling, 68
ant repellent, 540
antibiotic, 134, 141, 170, 181, 248, 548
antimony, 105, 112, 123, 128, 140, 187, 435
antiseptic, 98, 344, 399, 436, 449
aorta, 478
appendicitis, 101, 268
appendix, 97, 101, 128
appetite, 134, 240, 268, 275, 288, 292, 300, 306, 376, 379, 388, 417
apple cider vinegar, 277, 348, 423, 493, 572
apricot kernel oil, 534, 535, 537
arginine, 120, 137, 210, 212, 425
arm, 49, 51, 118, 153, 154, 254, 255, 282, 321, 481, 482, 488, 531, 553, 576
armpit, 89, 143, 144, 193, 531, 532
arsenic, 4, 40, 68, 96, 100, 103, 110, 132, 137, 138, 141, 150, 160, 162, 168, 171, 185, 186, 187, 193, 206, 236, 242, 259, 268, 271, 282, 313, 314, 361, 403, 448
arthralgia, 417
arthritis, 51, 78, 80, 81, 82, 83, 84, 85, 86, 117, 137, 146, 151, 155, 214, 268, 419
artificial sweetener, 173, 176, 177, 252, 302, 520, 574

asbestos, 4, 39, 80, 81, 91, 100, 103, 108, 110, 133, 137, 138, 142, 143, 145, 148, 150, 167, 168, 170, 207, 209, 210, 214, 231, 271, 282, 314, 316, 336, 337, 349, 447, 448, 474, 582
Ascaris, 10, 32, 43, 76, 78, 79, 80, 82, 86, 103, 104, 105, 107, 111, 122, 127, 134, 135, 136, 137, 138, 139, 140, 141, 142, 162, 166, 167, 176, 179, 186, 187, 192, 193, 194, 196, 212, 213, 227, 230, 231, 233, 234, 235, 236, 242, 256, 257, 259, 260, 264, 266, 267, 268, 274, 285, 286, 293, 299, 343, 371, 372, 375, 404, 566, 578
ascorbic acid, 516, 534, 535, 537, 584
aspirin, 169, 170, 214, 264
asthma, 43, 44, 105, 107, 135, 136, 137, 138, 139, 140, 220, 230
athlete's foot, 247, 248
Atomic Absorption Standard, 484, 572
atrophy, 384, 418
Atypical Lateral Sclerosis, 47
autism, 263, 264, 266
auto exhaust, 222, 279, 282, 316

B

back pain, low, 68, 81, 96, 123, 131
back pain, upper, 81, 96, 151, 553, 558
Bacteroides fragilis, 135, 230, 231, 266, 372, 563, 576
baking powder, 269, 430, 485
baking soda, 57, 58, 269, 431, 438, 515, 516, 527, 532, 533
baldness, 126, 190
bandwidth, 7, 8, 10, 16, 18, 506, 508, 509, 561, 562
barium, 75, 123, 139, 143, 187, 207, 415, 435, 436, 474, 476
bath oil, 247, 439
beef, 147, 368, 423, 424, 477
beer, 194, 327, 348, 378, 380, 386, 493, 572
beet root, 539, 540
benzalkonium, 137, 138, 170, 180, 187, 244, 390, 435, 439
benzoic acid, 55, 84, 583
benzopyrene, 304, 431
beryllium, 78, 124, 138, 142, 145, 157, 166, 170, 187, 192, 224, 227, 228, 229, 235, 407
beta blocker, 289, 319
BHA, 232, 233, 265, 517, 529
BHT, 232, 233, 265, 517, 529
bile, 47, 48, 80, 88, 91, 98, 100, 129, 130, 131, 132, 150, 151, 152, 153, 191, 223, 224, 266, 267, 299, 300, 477, 553, 554, 555, 556, 557, 558, 559
bile duct, 47, 48, 98, 129, 130, 131, 150, 151, 152, 153, 191, 223, 224, 299, 300, 477, 553, 557, 558
bioradiation, 12, 13
birth control pill, 111, 116
birth defect, 111, 418
bismuth, 105, 166, 185, 208, 242, 271, 435, 474
black cherry concentrate, 549
Black Walnut Hull Tincture, 21, 101, 102, 228, 235, 338, 339, 341, 342, 344, 345, 347, 389, 543, 544, 545, 547, 582
bladder, 55, 60, 101, 108, 112, 124, 129, 130, 145, 166, 190, 196, 198, 293, 321, 550, 552, 555, 559
bleach, 40, 150, 246, 256, 258, 260, 284, 314, 397, 437, 444, 449, 526, 530, 540, 572
bleeding, 95, 96, 110, 112, 196, 249, 286, 536
bleeding gum, 95
bloating, 108, 113, 129, 254, 266, 299, 443, 546, 555
blood pressure, 19, 49, 75, 82, 95, 115, 148, 149, 210, 211, 212, 213, 273, 275, 280, 281, 282, 289, 311, 321, 377, 388, 417, 515
blood sugar, 173, 175, 176, 177, 178, 182, 187, 275, 305, 308
blood test, 5, 77, 80, 82, 106, 107, 114, 139, 145, 178, 179, 213, 235, 245, 319
blood vessel, 69, 70, 154, 163, 279, 280, 281, 282, 318, 321
body lotion, 170
bone cancer, 196
bone infection, 56, 79, 315, 410
bone marrow, 78, 181, 285, 351, 353, 477
bone spur, 86
Borellia, 170, 563, 577

boric acid, 313, 403, 449, 540, 541, 542
boron, 215
bowel, 20, 21, 32, 34, 35, 54, 77, 82, 83, 97, 99, 101, 102, 103, 104, 106, 108, 128, 129, 152, 163, 166, 169, 197, 202, 219, 223, 224, 238, 254, 256, 267, 270, 298, 301, 331, 338, 364, 388, 389, 425, 443, 494, 510, 530, 546, 547, 548, 558
bowel disease, 102, 389, 443
bowel movement, 21, 34, 35, 77, 82, 83, 98, 101, 106, 128, 129, 197, 202, 224, 238, 256, 267, 301, 331, 494, 530, 558
Bowel Program, 99, 101, 102, 127, 128, 164, 202, 237, 238, 254, 257, 262, 270, 298, 315, 328, 346, 364, 444, 546, 549
braces, 418, 476
breast, 142, 143, 144, 145, 146, 235, 332, 336, 337, 342, 376, 384, 420, 435, 476, 491
breast cancer, 143, 145, 332, 384, 420
breast milk, 235, 342, 376
breastbone, 107, 131, 149
bromine, 239, 258, 271
bronchiestasis, 138
bronchitis, 78, 140, 141, 193, 217
burning, 186, 253, 254, 369, 534
burping, 295, 550
bursitis, 51, 151, 152, 558, 559
butyl nitrite, 162

C

cachexia, 240
cadmium, 37, 47, 69, 70, 74, 75, 79, 96, 107, 112, 146, 175, 185, 192, 210, 211, 213, 267, 268, 269, 314, 415, 418, 426, 449, 450, 466, 484
caffeine, 67, 68, 75, 89, 117, 137, 145, 185, 210, 212, 213, 255, 259, 264, 276, 290, 317, 377, 425
calcium, 57, 63, 64, 65, 66, 67, 74, 80, 81, 83, 87, 88, 93, 94, 96, 106, 129, 158, 212, 215, 216, 217, 231, 255, 276, 277, 287, 299, 305, 361, 399, 421, 517, 521
calcium propionate, 361
calf cramp, 68
Campylobacter, 69, 76, 110, 114, 170, 298, 563, 576, 577
Candida, 20, 185, 186, 189, 229, 246, 247, 248, 492, 563, 577
candidiasis, 176, 246
candy, 181, 218, 219, 313, 354
carbon dioxide, 139, 242, 267, 279, 282
carbon filter, 258, 270, 283, 314, 405, 426
carbon monoxide, 267, 282
carbon tetrachloride, 96, 103, 104, 116, 122, 127, 137, 148, 162, 186, 260, 440
carbonic anhydrase, 296
carcinogen, 40, 44, 374, 403, 423
cardiomyopathy, 147
cardiovascular, 417
carpet cleaning fluid, 429
Cascara sagrada, 99, 164, 238, 301, 547, 582
cat liver fluke, 116, 268
cavitation, 117, 141, 156, 291, 410, 533
cayenne, 55, 59, 84, 180, 181, 320, 398
cercaria, 34, 111, 117, 122, 495
cerebellum, 111, 206, 208, 484
cerebral palsy, 589
cerebrum, 111, 206, 208, 271, 274, 484
cerium, 145, 162, 187
cervix, 112, 113
cesium, 104, 157, 259, 260, 449
cheese sauce, 306, 434, 524
chelation, 213, 271, 272, 288, 289, 292
chemotherapy, 437
chest, 51, 74, 78, 148, 149, 150, 151, 167, 177, 178, 192, 254
chest pain, 51, 148, 149, 151, 167, 177, 178, 254
chewing gum, 95, 218
chicken, 84, 99, 126, 139, 147, 176, 179, 233, 235, 265, 266, 268, 274, 347, 353, 371, 394, 423, 424, 431, 477, 492
chicken pox, 176, 179, 353, 371, 492
chiropractic, 86, 91, 92, 156
Chlamydia, 110, 114, 563, 577
chloride, 37, 70, 72, 139, 162, 208, 221, 269, 311, 373, 390, 428, 429, 440, 475, 476, 497, 516, 573, 574, 584

chlorine, 137, 150, 239, 246, 257, 258, 260, 271, 282, 283, 288, 314, 437, 449, 526, 530, 540
chlorofluorocarbons (CFCs), 143, 313, 446
choke, 7, 11, 486
cholesterol, 109, 122, 129, 130, 224, 374, 421, 432, 434, 440, 553, 554, 558, 559
chromium, 37, 176, 178, 184, 302, 375, 377, 418, 431, 435, 436
chronic fatigue syndrome, 111, 186
cigarette, 336
cinnamon tea, 121
circulation, 55, 59, 63, 156, 160, 182, 273, 320
cirrhosis, 382, 589
citric acid, 403, 515, 516, 521, 528, 530, 535, 542
Clostridium, 76, 206, 315, 563, 564, 577
clothes dryer belt, 39, 142, 232, 314, 447, 474, 572
clotting, 19, 259, 320
cobalt, 4, 96, 112, 128, 141, 147, 162, 189, 194, 314, 399, 474, 526
coffee, 61, 81, 82, 89, 174, 210, 268, 274, 275, 278, 308, 327, 335, 377, 381, 388, 425, 427, 428, 431, 536
cold cereal, 109, 111, 162, 178, 219, 252, 335, 376, 386, 387, 392, 420, 518, 574, 575
cold sore, 179, 180
colitis, 105, 106, 107, 167, 425
cologne, 144, 242
colon, 78, 97, 131, 164, 337, 357, 361, 389, 478, 491
comfrey, 137, 139, 552
composite, 71, 119, 126, 146, 177, 226, 254, 291, 416
condom, 480
congestive heart failure, 318
constipation, 104, 166, 178, 238, 299, 301, 548
cooked cereal, 109, 144, 178, 287, 291, 376, 386, 442, 556
cookie, 23, 269, 431
copper, 22, 26, 30, 37, 70, 96, 100, 113, 115, 116, 119, 128, 147, 157, 171, 208, 211, 212, 261, 262, 310, 314, 337, 349, 426, 450, 459, 462, 463, 466, 472, 474, 484, 517
corn, 66, 81, 106, 144, 215, 282, 302, 303, 306, 307, 308, 351, 355, 356, 361, 379, 385, 394, 420, 434, 460, 476, 492, 532, 537, 539
cornstarch, 181, 247, 249, 294, 354, 374, 531, 532, 534, 537, 540
corpus luteum, 115, 124
cortisone, 52, 59, 138, 246
cosmetics, 37, 143, 144, 208, 326, 335, 437, 476, 572
cottage cheese, 80, 201, 254, 432, 485, 510, 511
Coxsackie virus, 1, 2, 135, 137, 166, 233, 371, 564, 576, 577
cramp, 69, 111, 249, 253
crawl space vents, 127, 181
Crohn's disease, 33, 104, 106
crotch itch, 247
croup, 135, 140
crown, 411, 413, 414
Cryptocotyl, 74
cutlery, 126, 127, 379, 430, 433
cyst, 32, 33, 34, 39, 74, 90, 91, 92, 112, 145, 170, 171, 188, 189, 198, 200, 255
cysteine, 74, 94, 96, 108
cysticercus, 197, 198, 199, 200, 357, 358, 494
cystine, 69, 94
Cytochalasin B, 387, 562, 576
Cytomegalovirus (CMV), 147, 179, 184, 564, 578

D

decaffeinated, 109, 210, 269, 335, 428, 574, 575
decane, 122, 162, 188, 440
dementia, 278, 280, 322, 330
dental cleanup, 73, 78, 79, 87, 120, 127, 145, 155, 156, 220, 262, 346
dental floss, 70, 162, 481
dental metal, 68, 70, 78, 110, 112, 115, 116, 117, 119, 122, 134, 140, 141, 143, 145, 159, 162, 187, 206, 222, 223, 226, 233, 254, 261, 270, 337, 419, 485, 589
denture, 139, 295, 411, 533
denture cream, 295
deodorant, 75, 128, 138, 143, 144, 147, 162, 181, 189, 190, 193, 222, 231, 435, 531, 532, 572, 574

depilatory, 417
depression, 44, 78, 104, 113, 116, 117, 185, 186, 210, 228, 254, 256, 257, 259, 260, 261, 262, 298, 540, 565
dermatron, 6
dessert, 305, 306, 326
diabetes, 3, 35, 43, 44, 55, 173, 174, 175, 176, 177, 178, 250, 251, 278, 302, 305, 309, 388, 495
diabetic, 67, 89, 174, 175, 305, 308, 309
diaper, 189, 246, 256
diaphragm, 76, 132, 133, 192, 297, 375
diarrhea, 97, 103, 104, 107, 108, 117, 134, 152, 202, 300, 344, 421, 425, 558
diesel exhaust, 75
diet clean-up, 80
diet drink, 429
diet, 7 day diabetic, 302
diet, 7 day sample, 523
digestion, 34, 88, 104, 105, 129, 130, 131, 148, 177, 226, 255, 266, 267, 276, 277, 278, 287, 295, 296, 297, 299, 374, 377, 423, 552
digestive problem, 95, 130, 146, 268, 559
digestive tract, 103, 246, 266
Dirofilaria, 32, 80, 141, 146, 147, 148, 318, 567, 578
diuretic, 75, 213, 282, 294, 304, 321, 373
dizziness, 186, 275, 297, 298, 419
dropsy, 321
drug, 44, 82, 131, 136, 234, 238, 289, 290, 301, 312, 316, 319, 321, 322, 344, 393, 473, 533
dry skin, 525
dry socket, 410
duodenum, 34, 478
dysprosium, 254

E

E. coli, 21, 62, 97, 98, 99, 102, 116, 129, 164, 177, 266, 298, 353, 357, 360, 361, 363, 364, 388, 444, 547, 548, 564, 576, 577
ear, 6, 104, 105, 134, 140, 168, 169, 170, 217, 242, 325, 361, 419, 467
ear infection, 104, 105, 134, 140, 169
ear, inner, 6, 170, 361
earache, 169
earthworm, 10, 510
Echinacea, 99
eclampsia, 95
eczema, 140, 192, 230, 492
edema, 60, 322, 515
EDTA, 73, 271, 272, 289, 582
egg dish, 432
elbow, 51, 154, 467
electronic testing, 5
ELISA, 495, 496, 497
emphysema, 46, 139
enamel, 214, 310, 413, 425, 430, 501, 529, 533, 543
encephalitis, 1, 2, 356
Endolimax, 106, 138, 567, 577, 579
endometriosis, 33, 35, 103, 110, 111, 122, 250, 495
endometrium, 250
enema, 166
environmental illness, 43
eosinophil, 136, 139, 185, 245
eosinophilia, 417
Epsom salts, 99, 150, 151, 300, 555, 556, 557
Epstein Barre Virus (EBV), 112, 179, 182, 184, 185, 186, 204, 371, 564, 577
ergot, 162, 226, 227, 228, 229, 232, 233, 253, 263, 270, 277, 280, 383, 385, 386, 392, 520
esophageal sphincter, 297
esophagus, 131, 132, 149
estrogen, 91, 113, 116, 119, 122, 143, 144, 145, 185, 217, 384, 539
ether, 575
europium, 124, 140, 187, 207
Eurytrema, 21, 109, 173, 371, 567, 578
Eustachian tube, 168, 361
exercise, 2, 86, 92, 301, 327
eye, 3, 14, 76, 140, 160, 161, 162, 175, 186, 259, 478, 497, 498, 528, 539, 590
eye disease, 3, 161, 175
eye makeup, 140, 186
eyelid, 146, 539

F

face, 36, 123, 181, 192, 193, 194, 209, 220, 227, 231, 253, 258, 280, 283, 369, 400, 448, 469, 540

face powder, 231, 540
fallopian tube, 250
Fasciola, 43, 249, 567, 578
Fasciolopsis buskii, 33, 150, 166, 250, 331, 371, 490, 567, 579
fatigue, 2, 4, 73, 95, 111, 113, 134, 139, 176, 177, 182, 183, 184, 185, 186, 187, 204, 245, 289, 311, 368, 417
fennel, 444, 547, 548
fenugreek, 175, 176, 370, 422, 521
fetus, 258, 417
fever, 78, 201, 203, 204, 234, 365, 369
fiberglass, 39, 40, 80, 91, 100, 110, 133, 137, 143, 147, 150, 160, 168, 177, 241, 282, 284, 314, 336, 349, 403, 405, 447, 590
fibromyalgia, 51, 75, 76, 78
fibromyositis, 75
filaria, 31, 318
finger, 86, 136, 155, 195, 253, 282, 308, 321, 463, 486, 487, 508, 530, 539
fingernail, 501
fireplace lighter, 165
fish line, 95, 218, 248, 296, 438, 533
flatworm, 33, 331
flavoring, 304, 378, 428, 548, 574, 575
flaxseed, 127
floss, 70, 72, 95, 162, 218, 296, 438, 481, 532
flour, 298, 306, 310, 361, 362, 379, 385, 423, 474, 572
flu, 78, 134, 168, 176, 201, 202, 203, 275, 425, 564, 576
fluke disease, 117, 219, 221, 249, 250, 252, 494, 495
fluke egg, 145, 332
fluoride, 82, 112, 206, 296, 573
foam, 40, 194, 284, 314, 337, 404, 447, 449, 533, 573, 590
foam bedding, 314, 337, 590
foam filter, 284
foam furniture, 40, 449
folic acid, 120
Food and Drug Administration (FDA), 436
foot, 51, 57, 59, 60, 68, 247, 248, 328, 419, 506
formaldehyde, 40, 100, 108, 110, 112, 133, 137, 150, 160, 165, 168, 193, 236, 241, 282, 284, 314, 361, 448, 449, 499, 500, 571
fragrance, 105, 136, 166, 185, 247, 253, 259, 284, 529, 530, 550, 572
Freon, 100, 160, 336, 446, 469
Fucus, 239, 548, 583

G

gadolinium, 124, 140, 207
Gaffkya, 170, 564, 576
gallbladder, 80, 128, 132, 191, 477, 553, 559
gallium, 123, 124, 146
gallstone, 81, 150
galvanized pipe, 70, 210, 211, 450
ganglia, 180
Gardnerella, 69, 91, 102, 110, 114, 115, 119, 564, 576
garlic, 137, 376, 548
gas hot water heater, 431
gas leak, 105, 140, 141, 149, 165, 166, 170, 171, 175, 187, 241, 255, 260, 268, 279, 319, 450, 573
gas pipe, 96, 165
gas stove burner, 476
gas, household, 231
gasoline, 124, 127, 162, 208, 221, 224, 227, 316, 416, 445, 472, 572, 574
gene, 3, 46, 206, 207, 209, 590
genital tract, 116
germanium, 417
Giardia, 9, 103, 160, 239, 399, 567, 578
ginger, 205, 514, 515
ginseng, 259, 263
glaucoma, 146, 213, 214
glucose tolerance factor, 184, 419
glutamic acid, 228
glutamine, 228, 229
gluten, 105, 175
glycerin, 515, 516, 534, 535, 536, 537, 538, 539, 540, 549, 584
goat milk, 107
gold, 102, 103, 111, 113, 124, 126, 146, 175, 177, 184, 226, 237, 310, 412, 418, 419, 420, 475
goldenrod, 549
gonorrhea, 91, 116, 565, 576
gout, 69
granola, 186, 354, 421, 518
gravel root, 552
grilled food, 356
groin, 90, 157, 166, 248

growing pains, 69
gum disease, 81
gums, 81, 87, 95, 217

H

HA wart virus, 176
Haemophilus, 141, 242, 564, 576
hafnium, 139, 222, 573
hair dryer, 241, 282, 316, 346, 447, 448
hair spray, 122, 136, 139, 144, 187, 222, 335, 439, 573
hamburger, 219, 349
hand cream, 354
handhold, 26, 27, 30, 457, 462, 463, 464, 487, 488, 503, 504, 506, 508
hCG, 336
head, 31, 32, 52, 112, 131, 144, 156, 161, 169, 171, 184, 198, 199, 254, 283, 315, 359, 361, 369, 417, 461, 557, 569
headache, 51, 75, 105, 116, 162, 164, 165, 167, 170, 206, 257, 369, 400, 419, 425
hearing, 4, 6, 7, 242, 261, 274, 278, 324, 325, 387, 468, 504
heart, 4, 32, 59, 80, 114, 138, 139, 141, 146, 147, 148, 149, 159, 168, 176, 177, 178, 182, 194, 195, 213, 254, 278, 279, 280, 290, 291, 311, 317, 318, 319, 320, 321, 322, 323, 325, 403, 419, 478, 515, 526
heart disease, 147, 176, 194, 403, 515, 526
heart failure, 278, 318, 322
heartburn, 82, 375
heartworm (see also Dirofilaria), 32, 138, 140, 141, 146, 147, 148, 149, 167, 178, 254, 318, 319, 343, 567
heel, 61, 63, 65, 67, 68
hemoglobin, 279, 286, 287
herb tea, 63, 66, 93, 95, 140, 321, 335, 365, 390, 424, 428, 429, 432, 524, 551, 574
herbicide, 40
hernia, 90, 133, 154, 268, 297
Herpes, 9, 20, 115, 116, 161, 179, 180, 181, 182, 371, 487, 488, 492, 564, 576, 578
hexane, 440
hexanedione, 111, 148, 193, 269, 574
hiatal hernia, 133, 154, 268, 297
high blood pressure, 49, 82, 95, 149, 211, 212, 213, 311, 388, 417, 515
hip, 51, 87, 89, 275, 419
hippuric acid, 55, 84, 85, 115
histamine, 135
histidine, 127, 207
Histoplasma, 145, 166, 564, 576
HIV, 10, 33, 90, 149, 150, 189, 204, 250, 251, 252, 342, 351, 352, 353, 356, 371, 458, 487, 490, 491, 495, 500, 501, 564
hives, 68, 89, 122, 191, 553
hookworm, 78, 79, 86, 105, 139, 160, 167, 194, 260, 264, 286, 343
hormone, 2, 91, 107, 113, 115, 116, 119, 122, 216, 368, 384
hot flush, 114, 115, 117, 175, 255
human liver fluke, 33, 74, 96, 109, 111, 116, 122, 128, 186, 188, 207, 208, 224, 249, 259, 260, 498
hurricane lamp, 78, 145, 166, 227, 572
hydrazine sulfate, 240
hydrochloric acid, 296, 297
hydrogen peroxide, 95, 139, 218, 296, 383, 438, 532, 533, 542
hydrogen sulfide, 267
hyperactive, 203
hyperesthesia, 417
hyperthyroidism, 188
hypnotism, 51

I

ice cream recipe, 522, 523
ileocaecal valve, 97, 101, 128
immune failure, 286
impetigo, 46
incontinence, 75, 278, 294, 325
indigestion, 6, 103, 145, 298, 446, 557
indium, 123, 157, 162
inductance, 5, 7, 486
inductor, 11, 486, 489
infant formula, 429
infertility, 2, 117, 144, 186, 237, 384
inhaler, 139
insect, 8, 506, 509, 529
insecticide, 312
insomnia, 4, 82, 134, 244, 245, 278, 326, 340, 417, 557
insulin, 173, 174, 175, 176, 177, 178, 182, 276, 302, 308, 332, 490
interferon, 468

interleukins, 468
intestinal problem, 128, 267
iodine, 95, 136, 163, 164, 188, 202, 218, 239, 246, 248, 298, 344, 348, 398, 399, 442, 443, 499, 559, 583
iridium, 82, 123, 188, 255, 271, 497
iron, 247, 248, 277, 279, 286, 450, 572
irritability, 113, 210, 254, 262, 298
irritable bowel syndrome (IBS), 102, 103, 104
islets of Langerhans, 182
isopropyl alcohol, 251, 285, 332, 335, 336, 348, 394, 398

J

jam, 2, 38, 52, 233, 265
jaw, 56, 74, 79, 87, 88, 156, 157, 158, 159, 170, 206, 215, 226, 254, 291, 315, 377
jaw bone, 74, 79, 87, 88, 206, 215
joint, 65, 66, 70, 82, 84, 139, 155, 157, 217, 417
joint pain, 84, 417

K

kerosene, 137, 208, 224, 227, 235, 407, 429, 572
kidney stone, 48, 56, 75, 79, 94, 95, 96, 108, 127, 166, 204, 212, 291, 552
knee, 44, 68, 74, 419, 489
knuckle, 195, 459, 463, 464, 486
Kojic acid, 102, 174, 175, 226, 388, 423

L

lactic acid, 88, 184, 187, 276
Lactobacillus, 100, 564, 576
lactose, 66, 104, 202
lamp oil, 474
lanolin, 223, 225
lanthanide, 414
lard, 303, 310, 354, 374, 394, 424, 517, 529, 530
laser, 111
lateral sclerosis, 204
lead, 4, 22, 26, 37, 46, 47, 60, 69, 74, 75, 79, 81, 96, 101, 105, 116, 136, 139, 141, 146, 157, 170, 181, 197, 220, 231, 232, 234, 262, 264, 265, 267, 268, 275, 280, 290, 314, 349, 356, 416, 417, 418, 426, 436, 440, 466, 472, 475, 504
Leishmania, 107, 193, 568, 578
lemonade, 557
lesion, 9, 181
leukemia, 211
lip, 534, 535
lip soother, 534, 535
lipoic acid, also see thioctic acid, 442, 584
lipstick, 75, 123, 207, 327, 336, 476, 539, 572
lithium, 255, 259, 260, 271
liver disorder, 374
liver fluke, 33, 43, 74, 78, 96, 103, 104, 107, 109, 111, 116, 117, 122, 128, 131, 175, 182, 185, 186, 187, 188, 207, 208, 218, 220, 222, 223, 224, 225, 249, 259, 260, 268, 271, 494, 498
Loa loa, 141, 147, 148, 149, 176, 291, 318, 319, 568, 576
loss of balance, 169, 270, 419
lotion, 247, 485, 535, 536
Lou Gehrig's disease, 44
Lugol’s, 163, 202, 203, 246, 248, 271, 298, 315, 346, 398, 442, 443, 499, 500, 501, 559, 583
lung, 40, 135, 138, 336, 372, 407, 477, 478, 576, 578
lung fluke, 138
lupus, 250, 495, 589
lutetium, 141
lye, 529, 530
Lyme disease, 170, 563
lymph, 64, 89, 90, 109, 144, 156, 157, 267
lymphocytosis, 417
lysergic acid, 263
lysine, 142, 146, 180, 181, 534, 535, 537, 538

M

magnet, 155
magnetic resonance imagery (MRI), 5
maintenance parasite program, 83, 105, 106, 116, 151, 176, 271, 340, 341, 555, 558

malignant, 39, 331, 337, 447
malvin, 233, 235, 236, 265
mammary gland, 143
mammogram, 144, 145, 146
manganese, 89, 176, 277, 572
Maple Milk Shake, 514
maple syrup, 191, 243, 365, 381, 390, 441, 513, 514, 524
margarine, 378, 517
marshmallow root, 549, 551, 552, 583
massage, 51, 70, 85, 92, 435, 439
massage oil, 435, 439
mean cell volume (MCV), 212, 285
measles, 186, 353, 492
medication, 166, 203, 236
melanoma, 337
memory loss, 273, 278
Meniere's syndrome, 169
menopause, 113, 114, 143, 260
menstruation, 113
mental problem, 2, 283
mercuric chloride, 70, 72
mercury amalgam, 409, 416, 417, 485
mesothelioma, 337
metabolism, 111, 187, 238, 239, 240, 243, 244
metacercaria, 495
metal tooth filling, 73, 123, 142, 157, 188, 189, 442, 472, 533
metastasis, 337
methanol (wood alcohol), 173, 174, 429
methyl butyl ketone, 35, 96, 110, 111, 116, 122, 269, 574
methyl ethyl ketone, 35, 110, 171, 260, 574
methyl methacrylate, 414
methylene chloride, 37, 162, 208, 221, 269, 574
microscope slide, 8, 149, 210, 477, 501, 561
migraine, 162, 163, 164, 165, 168, 259
milk digestant, 80, 421, 425
millet, 388, 420
miracidia, 34, 188, 495, 500
mite, 358, 359, 360, 408, 570, 580
mitral valve, 147, 159
moisturizer, 525
molasses, 286
mononucleosis, 492
monosodium glutamate (MSG), 232, 233, 253, 255, 265, 266, 304, 434
moth ball, 104, 141, 149, 162, 271, 448
mother's milk, 133, 143, 375, 490
mouthwash, 156, 194, 218, 229, 335, 413, 435, 438, 476, 533
multiple sclerosis, 46, 204, 219, 250, 254
mumps, 176, 178
muscle, 66, 78, 93, 94, 139, 147, 158, 161, 187, 197, 218, 220, 477
muscle pain, 66
muscular dystrophy, 219, 220
myasthenia gravis, 55, 221
mycoplasma, 138, 141, 176
mycotoxin, 38, 102, 261, 351, 384, 385, 388, 423
myofibrositis, 77

N

Naegleria, 138, 271, 568, 577
nail polish, 136, 222, 254, 449, 573
nausea, 66, 121, 153, 264, 338, 557
neck, 89, 144, 156, 157, 160, 166, 206, 280, 402, 419
Neisseria, 114, 116, 119, 563, 565, 576, 577
nephritis, 417
nerve, 36, 59, 86, 154, 158, 170, 180, 181, 205, 206, 262, 329, 371, 478
nervousness, 113, 187
neurologist, 73
niacin, 68, 70, 73, 168, 279, 280, 281, 320, 380
niacinamide, 228, 233, 263, 338, 364, 380
nickel, 37, 85, 106, 115, 122, 124, 125, 126, 138, 139, 143, 145, 177, 180, 188, 190, 207, 222, 374, 418, 420, 424, 431, 436, 475
nicotine, 264, 539
night sweats, 204, 353
niobium, 146
nitrate, 573
Nocardia, 112, 159, 187, 206, 242, 260, 565, 576, 577
nose, 22, 24, 40, 105, 107, 133, 140, 193, 199, 203, 347, 359, 361, 369, 379, 536
numbness, 154, 157, 207, 209, 254, 255, 256, 417
nursing, 134, 242, 292, 342, 375
nut, 23, 25, 262, 310, 374, 386, 389, 461, 519
nut butter, 310, 374, 386, 389

O

obesity, 237, 240, 242, 548
optic nerve, 478
optic neuritis, 417
ornithine, 82, 243, 244, 259, 272, 325, 326, 340, 342, 557
osteoarthritis, 78, 83
osteomyelitis, 410
ovarian cyst, 91, 110, 255, 384
ovary, 90, 91, 92, 119
overweight, 130, 237, 238, 239, 242, 243
oxalate, 68, 69, 93, 94, 95, 96, 108, 116, 122, 128, 139, 142, 171, 188, 551
oxalic acid, 61, 93, 94, 243, 276, 551

P

P24 antigen, 583
PABA, 536, 583
palladium, 82, 138, 141, 149, 177, 187, 208
pancreatic fluke, 33, 35, 43, 102, 103, 105, 107, 109, 140, 142, 173, 174, 175, 176, 177, 178, 179, 182, 183, 186, 188, 220, 221, 249, 250, 251, 259, 302, 371, 375, 388, 494, 498
pantothenic acid, 60, 253
para amino benzoic acid (PABA), 536, 583
paradichlorobenzene, 149, 162
Paragonimus, 107, 138, 568, 579
paralysis, 417
paraplegia, 417
paresthesia, 417
Parkinson's disease, 159, 315
parsley, 304, 306, 343, 344, 345, 513, 549, 550, 551
pasta, 66, 96, 121, 204, 225, 228, 262, 306, 307, 308, 310, 356, 363, 374, 375, 381, 385, 386, 387, 432
patulin, 277, 522
PCB, 147, 162, 188, 314, 426, 475, 527, 573
peanut butter, 45, 189, 364, 376, 382, 389, 432, 519, 523, 524
penis, 250, 491, 493
pentane, 127, 162, 171, 188, 208
perfume, 190, 253
peripheral neuropathy, 209
personal lubricant, 439
pesticide, 40, 68, 96, 132, 162, 171, 185, 236, 253, 255, 268, 282, 304, 313, 346, 427, 472, 473, 542, 572, 590
pet food, 354, 574
pet parasite program, 77, 117, 122, 167, 395, 494
Peyer's patches, 267
phenylisothiocyanate (PIT), 84
phosphate, 63, 64, 65, 66, 67, 68, 73, 80, 81, 83, 86, 88, 94, 95, 96, 106, 107, 139, 142, 177, 185, 212, 213, 215, 216, 217, 255, 320, 551
phosphate crystal, 65, 67, 86, 94, 95, 96, 107, 177, 185, 212, 217, 255, 320, 551
pinworm, 220, 404
piperine, 84
placenta, 76, 258, 263
platelet, 19, 145, 286
platinum, 68, 116, 122, 123, 134, 141, 149, 185, 193, 207, 212, 419
PMS, 113, 115, 255, 384
Pneumocystis, 138, 372, 568, 578
pneumonia, 138, 142, 147, 169, 407, 564, 566
polio, 371
polonium, 372
polyethylene, 62, 517, 532
polyneuritis, 417
popcorn, 144, 181, 248, 313, 351, 355, 356, 373, 385, 476, 492
porcelain, 415
pork, 206, 423, 424, 477, 484
potassium, 58, 59, 82, 95, 139, 163, 211, 217, 218, 277, 291, 293, 294, 304, 311, 348, 373, 499, 515, 516, 559
potassium bicarbonate, 58, 515
potassium chloride, 211, 311, 373, 516
potpourri, 165, 168, 448
praseodymium, 122, 221, 244, 439
pregnancy, 76, 106, 111, 115, 119, 121, 122, 264
probe, 28, 459, 462, 463, 464, 465, 467, 468, 471, 487, 489, 504, 506
progesterone, 91, 113, 114, 115, 119
propane, 207
prostate, 69, 96, 112, 123, 124, 125, 126, 127, 128, 139, 190, 331, 332, 336, 337, 491, 500
prostate cancer, 332, 337, 500

Prosthogonimus, 139, 255, 568, 578
protein, 193, 228, 232, 553
Proteus, 94, 102, 110, 114, 565, 576, 578
Pseudomonas, 74, 565, 576
psoriasis, 193
purpura, 281
PVC, 70, 78, 211, 231, 236, 241, 262, 282, 450, 475, 573
pyloric, 297

Q

quassia, 546

R

rabbit fluke, 105, 203
radiation, 7, 437, 589
radio frequency, 6, 7, 13, 486
radon, 96, 108, 127, 142, 145, 146, 150, 181, 185, 186, 187, 405, 406, 475
rash, 36, 189, 190, 191, 220, 246
rat poison, 417, 418
red blood cell, 19, 77, 285, 286
Red Milk, 515
redia, 9, 34, 122, 495, 500
reflexology, 61
reproductive organs, 119
respiratory, 140, 142, 160, 170, 358, 360, 361, 363, 449, 517
retina, 160, 162, 213
retinitis pigmentosa, 3, 162
rhabdomyosarcoma, 337
rhenium, 139, 187
riboflavin, 380, 584
rice, 63, 66, 121, 144, 303, 306, 307, 308, 311, 349, 351, 356, 363, 366, 383, 385, 420, 432, 492, 534
ringworm, 247
room freshener, 150, 284
root canal, 79, 119, 138, 145, 158, 159, 163, 166, 187, 208, 216, 266, 318, 410, 412
roundworm, 14, 32, 76, 83, 86, 107, 139, 257, 265, 267, 274, 343, 372, 566
rubella, 189
ruthenium, 212, 244, 439

S

salicylate, 170
salmon, 307, 366, 376, 422, 524
salve, 162
samarium, 82, 157, 208
Sarcocystis, 107, 568, 579
sassafras, 529, 546
scalp, 126, 171, 190, 193, 526, 528
scandium, 206
schizophrenia, 211, 261, 262, 450
sciatic nerve, 86
scopolamine, 393, 423
seafood, 205, 307, 366, 424, 432, 434, 522
sebaceous cyst, 171, 188
seizure, 230, 231, 232, 233, 234, 235, 236, 265, 517
semen, 342
sex, 67, 121, 179, 205, 319, 342
shampoo, 105, 144, 284, 333, 335, 336, 437, 476, 528, 542
shaving supplies, 189, 284, 335
sheep liver fluke, 33, 43, 78, 103, 104, 107, 109, 111, 117, 122, 131, 175, 182, 185, 187, 188, 208, 223, 224, 225, 249, 260, 271, 494, 498
shingles, 179, 192, 371, 487, 492, 564
shoulder, 49, 150, 151, 152, 153, 255, 553
silicon, 475
silver, 37, 100, 103, 110, 116, 119, 146, 177, 185, 192, 193, 260, 310, 420, 426, 475, 476
sinus, 104, 116, 117, 138, 139, 142, 163, 167, 168, 170, 187, 245, 268, 369, 419, 492
skin cancer, 194
skullcap, 244, 552
sleep problem, 96, 107, 117, 241, 255
Smoker's Leg, 70
smoking, 67, 68, 70, 73, 177, 255, 327, 336, 372
soap, homemade, 437, 438, 444, 448, 449, 530
soda pop, recipe, 515
sodium, 58, 59, 106, 139, 146, 181, 212, 217, 232, 282, 311, 373, 440, 515, 529, 534, 535, 537, 582, 584
sodium alginate, 106, 181, 534, 535, 537
sodium bicarbonate, 58, 582
sodium carbonate, 584

sodium chloride, 373, 440, 584
sonogram, 5
sore throat, 20, 159, 160, 206, 217, 400, 492
sorghum, 226, 281, 388, 391, 475, 481, 519
soup, 106, 180, 209, 243, 287, 294, 306, 307, 310, 324, 349, 376, 405, 431, 432, 434, 521, 523, 524
sour cream, 164, 293, 305, 524
soy, 387, 432, 434
spasm, 70, 93, 150, 153, 163, 300
spastic colon, 78
speech problem, 270
sperm, 119, 123
spinal cord, 204, 205, 206, 361, 478
spine, 49, 80, 92, 93, 217
spleen, 148, 174, 195, 197, 198, 358, 419, 492
stainless steel, 431, 543
Staphylococcus, 62, 74, 76, 89, 99, 116, 147, 159, 163, 178, 187, 206, 216, 242, 291, 318, 319, 346, 353, 565, 566, 577
starch, 121, 300, 373, 374, 375, 378, 531, 532, 534, 537, 539, 540, 573
Sterigmatocystin, 385, 562, 576
sternum, 148, 149
stomach problem, 104, 105, 268
strep throat, 100, 104, 492
Streptococcus, 74, 76, 99, 117, 147, 168, 169, 170, 187, 242, 566, 576, 577
stroke, 278, 280, 281, 282
Strongyloides, 78, 79, 82, 86, 163, 164, 166, 167, 170, 186, 194, 256, 257, 258, 259, 260, 264, 343, 371, 568, 578
strontium, 124, 127, 181, 192, 244, 296, 435, 436, 439, 450
styrene, 103, 122, 148, 162, 430
styrofoam, 122, 148, 260, 292, 314, 430, 433, 475, 527, 575
sulfur, 95, 267, 376
sweat, 126, 247, 528, 531, 532
sweetening, 303, 308, 524
Syncrometer, 43, 45, 150, 182, 189, 251, 312, 346, 355, 429, 444, 446, 457, 458, 459, 460, 462, 466, 467, 470, 471, 482, 503, 504, 506, 571
syphilis, 91, 566

T

Taenia pisiformis, 75, 148, 196, 570, 579
Taenia solium, 147, 196, 570, 579
tantalum, 140, 141, 475
tapeworm, 20, 32, 50, 75, 111, 147, 161, 179, 195, 196, 197, 198, 199, 200, 201, 208, 220, 318, 357, 358, 359, 360, 363, 364, 370, 371, 408, 487, 494, 570
tapeworm stage, 20, 32, 75, 111, 147, 161, 179, 195, 196, 199, 200, 201, 208, 318, 357, 358, 359, 360, 363, 364, 370, 371, 487, 494
TC Ethylene, 96, 141, 148, 188, 193, 429
tea kettle, 310, 431
tellurium, 68, 78, 134, 142, 188, 208
temporary ischemic attacks (TIA), 207, 281
tendon, 154
teratogen, 418
terbium, 186
testicle, 20, 54, 119, 128, 178
thallium, 37, 69, 70, 71, 72, 73, 74, 79, 95, 96, 100, 111, 115, 123, 134, 189, 190, 206, 209, 220, 242, 254, 255, 264, 269, 314, 361, 417, 418, 438, 536, 573
thioctic acid, 73, 74, 82, 120, 123, 178, 207, 208, 229, 236, 237, 254, 262, 265, 269, 270, 442, 584
threadworm, 163, 371
throat, 20, 100, 104, 105, 141, 149, 150, 160, 199, 206, 227, 241, 242, 243, 268, 280, 295, 354, 361, 370, 400, 477, 491, 492
thrush, 246, 248, 492
thulium, 128, 141, 146, 177, 193, 221, 439, 440
thymus, 35, 36, 107, 131, 150, 207, 208, 221, 250, 251, 351, 352, 353, 446, 477, 491, 493
thyroid, 77, 107, 117, 170, 182, 183, 185, 187, 188, 193, 213, 217, 237, 239, 254, 266, 377, 443
thyroxin, 187
tin, 9, 139, 162, 187, 242, 296, 435, 436, 472, 473, 476
Tinea, 247
tinnitus, 6, 169, 170, 171, 419

titanium, 89, 103, 123, 143, 180, 193, 231, 254, 435, 436, 476
TMJ, 157, 158, 259, 419
toast, 178, 181, 352, 356, 430, 431, 434, 524, 572
toaster, 573
tobacco, 84, 279, 326, 372, 436, 492, 566
Tobacco Mosaic virus, 436
toe, 56, 59, 67, 68, 155, 248, 253
tofu, 432, 434
toluene, 35, 37, 103, 141, 148, 205, 209, 219, 220, 232, 251, 252, 269, 270, 271, 336, 427, 476
tomato juice, 82, 308, 521
tongue, 6, 248, 376, 485
tonsil, 268
tooth metal, 112, 123, 133, 138, 142, 149, 162, 186, 187, 206, 221, 231, 240
toothbrush, 95, 218, 248, 295, 438, 532
toothpaste, 82, 124, 127, 138, 156, 181, 187, 196, 206, 218, 242, 296, 420, 435, 438, 476, 532, 572, 573, 574
Toxoplasma, 160, 161, 162, 568, 577
trachea, 187, 478
tremor, 49, 78, 206, 207, 209, 260, 270, 278, 313, 314, 315, 316
Treponema, 114, 119, 566, 576
Trichinella, 31, 68, 76, 79, 80, 82, 86, 153, 161, 186, 192, 193, 194, 207, 257, 260, 343, 568, 578
trichloroethane, 37
Trichomonas, 102, 110, 568, 577
Trichuris, 74, 107, 142, 166, 568, 578
tryptophane, 244, 245, 439
tuberculosis, 142, 407, 565, 579
tumor, 40, 337, 415, 547
tungsten, 271, 430, 431, 449
turkey, 423, 424, 477, 485
turmeric, 547
tyramine, 164, 293, 305

U

udder wash, 98, 109, 137
ulcer, 132
underweight, 240, 268
universal allergy syndrome, 495
uranium, 142, 146
urate, 95, 122, 139, 166, 167, 255
urea, 75, 125, 243, 320
urethra, 124
uric acid, 55, 61, 68, 69, 81, 94, 171, 213, 320
urinalysis, 68, 77, 166, 185, 193
urinary tract, 77, 102, 106, 110, 114, 122, 125, 127, 163, 166, 167, 190, 255, 291, 430, 555
uterine wall, 112, 249
uterus, 35, 103, 106, 108, 109, 110, 111, 112, 113, 115, 117, 119, 122, 123, 124, 145

V

vagina, 246, 250, 491, 493
valerian, 150, 151, 152, 153, 158, 244, 272, 300, 325, 326
vanadium, 96, 105, 140, 149, 165, 170, 171, 175, 186, 187, 231, 255, 260, 268, 271, 313
vanilla, 514, 519, 522
Vanilla Milk, 514
vasectomy, 128
vegetable juice, 66, 82, 94, 237, 308, 309, 322, 422, 424, 513, 523, 524, 525
vegetarian, 197, 434
vinegar, 89, 276, 277, 288, 291, 296, 297, 303, 305, 306, 348, 349, 366, 377, 381, 383, 403, 405, 423, 441, 444, 448, 493, 514, 521, 527, 528, 540, 541, 542, 572
vitamin A, 95, 142, 154
vitamin B, 80, 88, 142, 146, 178, 217, 235, 285, 353, 551
vitamin B1, 235, 285
vitamin B12, 235, 285
vitamin B2, 88, 353
vitamin B6, 80, 142, 146, 217, 551
vitamin C, 38, 58, 73, 87, 89, 107, 110, 120, 121, 128, 141, 144, 146, 168, 177, 178, 181, 184, 193, 212, 218, 222, 228, 230, 242, 247, 263, 270, 277, 280, 281, 286, 291, 301, 302, 303, 305, 347, 348, 349, 356, 364, 365, 366, 370, 382, 383, 385, 386, 388, 389, 390, 391, 393, 421, 423, 427, 432, 433, 440, 441, 470, 481, 494, 513, 515, 516, 518, 519, 520, 521, 523, 525, 531, 534, 535, 537, 538, 543, 545, 548, 556, 573, 584

vitamin D, 64, 65, 66, 74, 81, 87, 88, 158, 217, 218, 254
Vitamin D Drops, 560
vitamin E, 120, 145, 146, 534, 539
vomiting, 105, 134, 166, 202, 394, 417

W

wallpaper, 141, 448, 572
wart, 69, 174, 176, 195, 196, 201, 478
washing soda, 57, 58, 180, 188, 269, 314, 346, 399, 431, 438, 444, 448, 515, 516, 525, 527, 532, 533, 540
water heater, 39, 319, 431, 447, 449, 573
water softener, 117, 127, 274, 437, 450, 473, 517, 572, 573
weakness, 92, 127, 139, 207, 220, 278, 293, 317, 322, 417
whip worm, 105, 107, 142
white distilled vinegar, 277, 349, 423, 444, 448, 521, 540, 541, 542
white iodine, 95, 163, 218, 248
wine, 164, 280, 327, 381, 386, 431
wood alcohol (see also methanol), 37, 102, 103, 162, 173, 174, 175, 176, 177, 178, 179, 183, 185, 186, 206, 208, 240, 251, 252, 259, 269, 302, 309, 314, 371, 375, 377, 388, 391, 414, 436, 475, 519, 559, 574
worm, 10, 105, 107, 142, 147, 163, 197, 247, 257, 318
wormwood, 339, 342, 344, 345, 582
wrist, 74, 75, 80, 154, 155, 255, 328

X

xenobiotic, 419
xylene, 35, 37, 111, 122, 141, 148, 205, 208, 209, 219, 220, 232, 251, 252, 270, 427, 429

Y

Yankee Drink, 514
yeast, 4, 115, 116, 122, 189, 246, 247, 248, 298, 377, 399, 492, 563
ytterbium, 415, 436
yttrium, 123, 127, 186

Z

zearalenone, 144, 225, 355, 492
zinc, 70, 106, 120, 123, 127, 154, 160, 181, 247, 277, 296, 532, 534, 572
zinc oxide, 181, 247, 532, 534
zirconium, 75, 89, 112, 128, 138, 147, 170, 180, 189, 193, 222, 231, 415, 435

A New Diagnostic Device…

With an audio oscillator circuit and a trained ear, you can detect parasites and pollutants in a way that no one has done before–electronically.

Leads To New Discoveries…

In every case of the "mysterious" disease diabetes, you find the not-so-mysterious parasite *Eurytrema*, and the fairly common pollutant *wood alcohol*. Every case! And never in healthy people! Similarly in cancer, HIV, Alzheimer's, endometriosis, to name a few, you can find specific parasites and/or pollutants at work.

And New Cures…

You don't need dangerous, expensive prescription drugs to get rid of the causes of your illness. Once you know what you are fighting you can pick herbal, electronic, or avoidance methods. Except for the cost of dental work, you can get well for under $100!

And New Hope…

Follow the advice in this book preventively, and never worry about your health again! Get your whole family well and keep them well. Start today!

It Took An Independent Research Scientist

to find the answers. Hulda Regehr Clark began her studies in biology at the University of Saskatchewan, Canada, where she was awarded the Bachelor of Arts, Magna Cum Laude, and the Master of Arts, with High Honors. After two years of study at McGill University, she attended the University of Minnesota, studying biophysics and cell physiology. She received her Doctorate degree in physiology in 1958. In 1979 she left government funded research and began private consulting on a full time basis. Six years later she discovered an electronic technique for scanning the human body. Today she puts her methods, results and conclusions before you. Read and recover.

New Century Press
Chula Vista, CA

1 (800) 51902465
www.newcenturypress.com

ISBN 1-890035-01-7
$21.95

About this electronic book

While creating this electronic version of The Cure for all Diseases, I encountered some inconsistencies and (small) errors in it. Below follows an overview.

Niels Willems, december 2002.
niels.w@hccnet.nl
www.rupa.demon.nl

Page	**Line**	**Hard copy**	**Electronic version**
18	Fig.2	(Di-phyllobothruim e.)	(Di-phyllobothrium e.)
25	last-2	both with a alligator clip	both with an alligator clip
255	last-3	liver cleanses(page 549) make	liver cleanses (page 552) make
360	last-7	health improv-ed	health improved
451	5	furniture"treated"	furniture "treated"
452	last	refigerators	refrigerators
467	14	SALT # 1	SALT #1
519	last	honey	honey.
562	last-7	Argyria	Arcyria
563	16	Bac. antracis spores | 391.45 | 386.95	Bac. antracis spores | 386.95 | 391.45
564	6	Corynebacterium diptheriae	Corynebacterium diphtheriae
565	18	Norcardia asteroides (2nd range)	Nocardia asteroides (2nd range)
570	last-4	folicle mite	follicle mite
575	2	Paradiclorobenzene	Paradichlorobenzene
576	(17)	missing: Aflatoxin (2nd) 188 188	(not corrected)
576	last-19	Corynebacterium diptheri	Corynebacterium diphthe
580	4	folliculorum foli	folliculorum foll

PARASITOLOGY: REVIEW FOR FINAL EXAM

LECTURE #1: TREMATODES I - SCHISTOSOMIASIS

1. What is Schistosomiasis?

- Schistosomiasis (called **bilharziasis** in non-English speaking world) is a disease syndrome caused by infection from one of several species of parasitic trematodes of the genus Schistosoma.
- **Disease** develops from the host's immune response to the shistosome eggs >>> granuloma formation >>> fibrosis (amount of fibrosis correlates to intensity of infection).
- Most granulomas develop at sites of maximal egg accumulation in the intestine and liver (if S. mansoni or S. japonicum), or in the GU tract (if S. haematobium).
- Granulomas destroy the ova, but result in fibrotic deposition in host tissues. Eggs trapped in tissues release enzymes and other antigenic substances that sensitize local host lymphocytes >>> secretion of lymphokines >>> recruits macrophages, lymphocytes, eosinophils and fibroblasts >>> forms compact cellular infiltrate.
- Early **acute granulomas** are usually composed of eosinophils and neutrophils as well as mononuclear cells.
- **Chronic granulomas** are primarily macrophages, lymphocytes, fibroblasts, and multinucleated giant cells. Collagen deposition and fibrosis cause irreversible pathology.
- Schistosomiasis is a major source of M&M for developing countries in Africa, South America, the Caribbean, the Middle East, and Asia.
- Three types of clinical disease:
    1. Swimmer's Itch: Kabure, Clamdigger's itch
    2. Katayama Syndrome: acute schitosomiasis
    3. Chronic Schistosomiasis:
        a. Intestinal tract
        b. Urogential tract



Adult Schistosoma mansoni (male and female). Note the longer thinner female held within the gynecophoric canal of the male.

2. What are the common species of Schistosoma?

- Most disease caused by:
    1. **Schistosoma haematobium:** urinary tract
    2. **Schistosoma mansoni:** colon
    3. **Schistosoma japonicum:** colon
- Less prevalent species:
    1. **Schistosoma mekongi:** colon
    2. **Schistosoma intercalatum:** colon

3. What is the life cycle of Schistosomiasis?

- Schistosomes infect particular species of susceptible freshwater snails in endemic areas.
- The infected snails release **cercariae**, which are fork-tailed free-swimming larvae (1 mm in length), which survive in freshwater up to 48 hours, during which time they must attach to human skin or to that of another susceptible host mammal, or they die.
- Cercariae attach to human hosts utilizing **oral & ventral suckers.**
- They then migrate through intact skin to dermal veins >>> w/in a few days to the pulmonary vasculature. During this migration, the cercariae metamorphose, shedding tails and outer **glycocalyces** while developing **double-lipid-bilayer teguments** that are highly resistant to host immune responses.
- The organisms (now **schistosomula**), incorporate host proteins, including major histocompatibility complexes (MHCs) and blood group antigens, in their integuments. They stop oxidative metabolism and metabolism shifts to glycolysis.
- The worms then migrate through the pulmonary capillaries to the systemic circulation, which carries them to the portal veins where they mature.

- In the portal vasculature, adults pair off, with the thin female entering and remaining in the **gynecophoric** canal of the stockier 8-mm male worm. Together they migrate along the endothelium, against portal blood flow, to the Inferior Mesenteric and Superior hemorrhoidal veins **(S. mansoni)** and Superiror Mesenteric **(S. japonicum)** or vesicular veins and veins draining the ureter **(S. haematobium)** where they begin to produce eggs (4-6 weeks post-infection, and continuing for life of worm, typically 3-5 years).
- Eggs pass from the lumen of blood vessels into adjacent tissues and many are shed in the feces (S. mansoni and S. janponicum) or urine (S. haematobium).
- The eggs are highly antigenic and can induce an intense granulomatous response, as they migrate through tissues. During this time (approximately 10 days) they begin to mature into **miracidia**.
- Eggs that are not shed successfully may remain in the tissues or be swept back to the portal circulation (from the mesenteric vessels) or to the pulmonary circulation (from the vesicular vessels via the inferior vena cava [IVC]).
- The free-swimming miracidia that are shed into freshwater survive 2-3 weeks, during which time they must infect a susceptible snail to complete the life cycle.
- In snails, miracidia drop their ciliated coat and metamorphose into 2 generations of **sporocysts,** multiply, mature into free-swimming cercariae, and exit the snail to seek a human host and begin a new cycle.


i = Infective Stage
d = Diagnostic Stage
CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx
5 Cercariae released by snail into water and free-swimming
i
Sporocysts in snail 4 (successive generations)
Penetrate skin 6
7 Cercariae lose tails during penetration and become schistosomulae
8 Circulation
3 Miracidia penetrate snail tissue
A
B
C
Migrate to portal blood in liver and mature into adults 9
♂
♀
2 Eggs hatch releasing miracidia
in feces
d
in urine
10
S. japonicum
A
S. mansoni
B
1
S. haematobium
C
Paired adult worms migrate to:
A B mesenteric venules of bowel/rectum (laying eggs that circulate to the liver and shed in stools)
C venous plexus of bladder

Eggs are eliminated with feces or urine ①. Under optimal conditions the eggs hatch and release miracidia ❷, which swim and penetrate specific snail intermediate hosts ❸. The stages in the snail include 2 generations of sporocysts ❹and the production of cercariae ❺. Upon release from the snail, the infective cercariae swim, penetrate the skin of the human host ❻, and shed their forked tail, becoming schistosomulae ⑦. The schistosomulae migrate through several tissues and stages to their residence in the veins (⑧, ⑨). Adult worms in humans reside in the mesenteric venules in various locations, which at times seem to be specific for each species ❿. For instance, *S. japonicum* is more frequently found in the superior mesenteric veins draining the small intestine A, and *S. mansoni* occurs more often in the superior mesenteric veins draining the large intestine B. However, both species can occupy either location, and they are capable of moving between sites, so it is not possible to state unequivocally that one species only occurs in one location. *S. haematobium* most often occurs in the venous plexus of bladder C, but it can also be found in the rectal venules. The females (size 7 to 20 mm;

males slightly smaller) deposit eggs in the small venules of the portal and perivesical systems. The eggs are moved progressively toward the lumen of the intestine (*S. mansoni* and *S. japonicum*) and of the bladder and ureters (*S. haematobium*), and are eliminated with feces or urine, respectively ①. Pathology of *S. mansoni* and *S. japonicum* schistosomiasis includes: Katayama fever, hepatic perisinusoidal egg granulomas, Symmers' pipe stem periportal fibrosis, portal hypertension, and occasional embolic egg granulomas in brain or spinal cord. Pathology of *S. haematobium* schistosomiasis includes: hematuria, scarring, calcification, squamous cell carcinoma, and occasional embolic egg granulomas in brain or spinal cord.

Human contact with water is thus necessary for infection by schistosomes. Various animals, such as dogs, cats, rodents, pigs, hourse and goats, serve as reservoirs for *S. japonicum*, and dogs for *S. mekongi*.



Left image: forked-tailed cercaria of Schistosoma mansoni (body 185-230 x 75-110; tail trunk 185-300 x 60-75;fork 90-130mM). This is the infective larva that emerges from the snail intermediate host. Right image: Miracidium; emerges from the egg in freshwater. They are ovoid and about 160mM long, possessing cilia on four rows of epidermal plates. They have four flame cells functioning as the excretory system and their activity serves to indicate the viability of the ovum.

4. What is the pathophysiology of Acute Schistosomiasis?

- **Acute schistosomiasis/Katayama Fever** is a serum sickness–like illness that develops after several weeks in some individuals with new schistosomal infections.
- It may correspond to the first cycle of egg deposition and is associated with marked peripheral eosinophilia and circulating immune complexes.
- It is most common with S. japonicum and S. mansoni infections and is most likely to occur in heavily infected individuals after primary infection.
- Symptoms usually resolve over several weeks, but the syndrome can be fatal.
- Early treatment with cidal drugs may exacerbate this syndrome and necessitate concomitant glucocorticoid therapy.
- Mild maculopapular skin lesions may develop in acute infection within hours of exposure to cercariae.
- "**Swimmer's itch,"** a pruritic eruption, may occur at the site of penetration of the cercariae, but is rarely seen with primary exposure. However, with prior sensitization, Schistosomes dermatitis, a pruritic rash, may result.
- The greatest pathological responses occur following avian Schistosomes, probably b/c subQ cercarial death occurs shortly after they penetrate skin.
- Symptoms: fever, urticaria, melena, marked eosinophilia, diarrhea (bloody), lymphadenopathy, nausea & vomiting, hepatosplenomegaly, hyperglobulinemia, respiratory symptoms, abdominal pain, interstitial pneumonitis.

5. What is the pathophysiology of Chronic Schistosomiasis?

- Chronic infection much more common
- Although cercarial and adult worms are minimally immunogenic, schistosomal eggs are highly immunogenic and induce vigorous circulating and local immune responses. Egg-induced immune responses result in granuloma formation, and associated fibrotic changes.
- GI Effects: Egg retention and granuloma formation in the bowel wall (usually S mansoni or S japonicum) >>> gut wall inflammation, microabscesses, and polyposis >>> diarrhea (often bloody) and cramping >>> severe disease leads to colonic or rectal stenosis.
    1. colonic polyposis can present as a protein-losing enteropathy

    2. inflammatory masses in the colon may mimic carcinoma
    3. patients with heavy bowel wall involvement have an increased rate of recurrent salmonella infection, generally with positive blood cultures and negative stool cultures.
- Liver Disease: unshed eggs are swept back to the portal circulation, lodge there and induce granulomatous reactions in the portal tracts. Heavy infestations are more likely to produce hepatic disease. **Symmers' Pipe-stem fibrosis** may occur if heavy infection for years. Although hepatocellular function is spared, periportal fibrosis can lead to **portal hypertension** with the usual possible sequelae, including splenomegaly, ascites, esophageal variceal bleeding, caput medusa, and development of portosystemic collaterals. Co-infection with hepatitis B or hepatitis C can accelerate hepatic dysfunction and raise the risk for hepatocellular carcinoma.
- Pulmonary Effects: through these collaterals (or directly from the IVC in the case of bladder wall schistosomiasis), eggs can reach the pulmonary circulation. The resulting pulmonary granulomatosis and fibrosis can lead to **Hypertrophic Osteoarthropathy (clubbing),** and **pulmonary hypertension** and **cor pulmonale** with a high mortality rate. In severe cases, patients can develop **Right HF**.
- GU Effects: egg retention and granuloma formation in the urinary tract (S. haematobium) >>> hematuria (10-12 days post-infection), dysuria, bladder polyps and ulcers, and even obstructive uropathies. Can see **sandy patches on cystoscopy** (viable eggs in inflamed bladder mucosa), which are pathognomonic. Later manifestations are proteinuria (usually in nephritic range), calcifications in bladder, obstruction of ureters, renal colic, hydropnephrosis, and renal failure. Secondary **bacterial infections** are common.
    1. S. haematobium infection is also associated with an increased rate of **squamous cell caricinoma of the bladder** tends to be well differentiated w/ local mets. Typically associated with mutations of **p53** and **cyclin-dependent kinase inhibitor 2** tumor suppressor genes.
    2. SH causes genital disease in 1/3 of infected women >>> wart-like lesions that can be mistaken for other diseases, and **vulval Schistosomiasis** can facilitate the transmission of HIV.
    3. SM and HBV >>> higher risk of **hepatocellular carcinoma**
- CNS Effects: eggs can deposit in cranial or spinal cord vasculature >>> resulting in **transverse myelitis** (S. haematobium and S. mansoni), or cerebral disease & seizures (usually S. japonicum). Steroids are important in treating these infections, because edema and inflammation cause symptoms, also use anticonvulsants.
- General: ectopic egg deposition can lead to additional clinical syndromes including involvement of skin, lung, brain, muscle, adrenal glands, and eyes.



Schistosoma mansoni in intestinal tissue, acid fast staining of the egg shell is highly characteristic.

6. What is the distribution of Schistosomiasis infections?

- Transmission: exposure to infected fresh water
- infections uncommon in US, b/c neither susceptible snail species nor chronically infected human reservoirs sufficient to infest freshwater exist.
- However, pathogenic schistosomes can survive and replicate in human hosts for years and even decades. Therefore, persons who have traveled or immigrated to the US may present to EDs with active cases of acute or chronic schistosomiasis and/or the associated end-organ complications of this disease.
- Globally, schistosomiasis is a major source of M&M, endemic areas are tropical and subtropical zones
- 250 million people have active schistosomal infection; 120 million people have symptoms, and 20 million are severely ill.

- Disease tends to be worse in areas with poor sanitation, increased freshwater irrigation usage, and heavy schistosomal infestation of human and/or snail populations.
    1. by major dams, small dams and irrigation projects in developing countries
    2. refugees and population shifts
- Schistosomal species vary with geography:
    1. **S. mansoni** and **S. haematobium** infections predominate in sub-Saharan Africa.
    2. **S. mansoni** is endemic in parts of South America and the Caribbean.
    3. **S. japonicum** is common in China, Indonesia, and the Philippines
    4. **S. mekogni** is common in Kampuchea, Laos



7. How is Schistosomiasis diagnosed?

- Detection of eggs in feces or urine – may require 3 specimens
- In patients with typical clinical presentation, but negative urine and feces specimens, a bladder biopsy is done.
- Antibody detection with FAST-ELISA is good for patients not shedding eggs, but antibodies persist after parasitologic cure.

Schistosoma mansoni egg (115-175 x 45-70mM) with large lateral spine, and a ciliated miracidium (larva) is evident within the egg.

8. What is the prognosis for Schistosomiasis infection?

- Although most individuals with chronic schistosomiasis have few or no symptoms, significant morbidity can develop – acute infection is associated with mortality rates of up to 25%.
- Hepatosplenic disease with portal hypertension is the most common long-term serious outcome, followed by cardiopulmonary involvement, obstructive nephropathy, bacteremia, and malignancy.
- End-stage hepatosplenic disease with variceal bleeding, pulmonary hypertension with cor pulmonale, and central nervous system disease are associated with high mortality rates.
- Children and adolescents are infected most often and are infested most heavily.

9. How is Schistosomiasis treated?

- **Praziquantal, a pyrazinoisoquinolone derivative,** is absorbed well, but undergoes extensive first-pass hepatic clearance.
- Mechanism: stimulates Ca2+ influx, associated with Ca2+ destruction of tegument in adults
- Side effects: nausea & vomiting
- CMI important
- Drug's precise actions unknown. It appears to cause tetanic contractions and tegumental vacuoles >>> causing worms to detach from veins and die.
- Cure rate 60-90%, with substantial decreases in egg and worm burdens in those who aren't cured.
- Patients who continue to shed viable eggs should be re-treated.
- Treat patients with CNS involvement with steroids and anti-convulsants.

10. What are the different categories of medical parasitology?

- **Medical Protozoology**
    1. parasitic ameba
    2. flagellates
    3. ciliates
    4. apicomplexans (malarial)
    5. microsporidia
- **Medical Helminthology**
    1. **Nemathelminthes (roundworms):** a phylum composed of 3 classes of roundworms. They are more advanced than flatworms, but less advanced than earthworms. They have thin, round bodies, with no segments. They live in salt water, fresh water, and soil.

        a. hookworm
        b. Pinworm
        c. trichinella
    2. **Platyhelminthes (Flatworms):** a phylum composed of three classes of flatworms. They are the simplest of the worms, and live in fresh and salt water.
        a. **Turbellaria (planarians)** is free-living
        b. **Trematoda (flukes)** is parasitic
        c. **Cestoda (tapeworms)** is parasitic
- **Medical Entomology**
    1. arthropods: insects, arachnids, crustacea, centipedes, and milipedes

11. **What are the differences between immunity to different strains of Schistosomiasis?**
- There is a difference in development of immunity between SM and SJ
- Early: blocking antibodies (IgG2, IgG4, IgM) that block binding of protective IgE and IgG2a, thereby stopping killing of infectious agents
- Later: IgE and IgG4 compete for binding sites and attack invading larvae >>> humoral immunity of host then has upper hand
- Eosinophils and macs bind via Fc receptors to specific IgE, IgA and IgG2a on Schistosomium >>> eosinophils degranulate
    1. Major Basic Protein (MBP)
    2. Eosinophilic Cationic Protein (ECP)
    3. Eosinophil Peroxidase (EPO)
    4. Reactive Oxygen Intermediates (ROI)
- C3 also acts with antibodies to enhance response

12. **Discuss the involvement of cell mediated immunity in response to Schistosoma infection.**
- Early: large volume granulomas form with Eosinophils, PMNs, and monocytes
- Later: modulation occurs with macs, lymphocytes, Giant cells and fibroblasts
- Increase in antibodies acts to trap eggs and egg antigens
- Granulomas is TH2 dominated
- Increased eosinophils levels driven by IL-4, IL-5, IL-13 secretion

13. **What are the lab characteristics of Schistosoma?**
- Stain with **acid fast** stain
- Has **lateral spine**

14. **What are some characteristics of Trematodes?**
- **Trematodes** are flukes of the class Trematoda; phylum Platyhelminthes. Trematodes are divided into the Schistosomes or blood flukes and the tissue flukes.
- Dorsoventrally flattened
- Exulusively endoparasitic
- Organs of attachment:
    1. anterior sucker (oral)
    2. ventral sucker (acetabulum)
- Complex life cycle: 1-2 intermediate hosts required, w/ first intermediate host always being a snail

LECTURE #2: TREMATODES II – LIVER FLUKES & LUNG FLUKES

1. **What are Liver Flukes?**
- There are 6 types of liver flukes
    1. **Clonorchis sinensis**
    2. **Opsithorchis felineous & viverrini**
    3. **Fasciola hepatica**
    4. **Dicrocoelium dendriticum**
    5. **Metorchis conjunctus**

2. **What is Clonorchiasis?**
   - An infection of the biliary tract by Clonorchis sinensis, the Chinese liver fluke.
   - Distribution: over 20 million infections, endemic in Japan, Korea, China, Taiwan, Vietnam
   - Source: ingestion of raw, pickled or smoked fish that have been raised in ponds contaminated with soil from human or animal feces.
   - Complications: secondary bacterial infection and cholangiocarcinoma.



Chlornorchis in bile ducts. Note periductal fibrosis, hyperplasia of biliary epithelium, and bile capillary proliferation.

3. **What is the morphology of Clonorchis sinensis?**
   - 1-2.5 cm worm that inhabits intrahepatic bile ducts
   - Uses suckers to hold on to biliary epithelium
   - Adult parasites are elongated, opalescent grey and 10-25mm in length by 3-5mm in width.
   - The tegument in the larval fluke is spiny, but in the adult parasite it's smooth, in contrast to other flukes such as *Fasciola* or *Paragonimus*.
   - The gut is bifurcated as with all flukes, but not branched.
   - The ventral sucker is smaller than the oral sucker and is situated approximately a quarter of the way down the parasite from the anterior end.
   - The testis are situated at the posterior end of the parasite and are highly branched.
   - The eggs are ~30 x 15 microns in size, and the operculum is situated in a rim with distinct shoulders.



Three Clonorchis ova (20-30 x 15-17µm) in stool.

4. **What is the life cycle of Clonorchis sinensis?**
   - Adult worms live in the distal biliary ducts (and sometimes gallbladder or pancreatic duct) of humans

- Eggs are released into bile and pass to feces
- On reaching water, eggs are eaten by a specific species of snail (the first intermediate host)
- Within the snails, **miracidia** hatch >>> develop into **sporocysts** >>> **rediae** >>> **cerceriae**
- In 4-6 weeks, cercariae are released into the water and penetrate the muscle of **susceptible freshwater scaly fish**
- In fish develop into **metacercariae**, which become infective in 6 weeks.
- Consumption of infected fish is the source of infection for the definitive hosts – humans and other fish-eating mammals.
- Once ingested, metacercariae excyst in the duodenum or jejunum and migrate through the ampulla of Vater and common bile duct to the bile ducts >>> where they mature within 4 weeks and begin to produce eggs.

Life Cycle:


CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx
Metacercariae in flesh or skin of fresh water fish are ingested by human host. ④
i
i = Infective Stage
d = Diagnostic Stage
Free-swimming cercariae encyst in the skin or flesh of fresh water fish. ③
⑤ Excyst in duodenum
Eggs are ingested by the snail. ②
Miracidia (2a)
Sporocysts (2b)
Rediae (2c)
Cercariae (2d)
d
① Embryonated eggs passed in feces.
⑥ Adults in biliary duct

Embryonated eggs are discharged in the biliary ducts and in the stool ①. Eggs are ingested by a suitable snail intermediate host ②; there are more than 100 species of snails that can serve as intermediate hosts. Each egg releases a miracidia (2a), which go through several developmental stages (sporocysts (2b), rediae (2c), and cercariae (2d)). The cercariae are released from the snail and after a short period of free-swimming time in water, they come in contact and penetrate the flesh of freshwater fish, where they encyst as metacercariae ③. Infection of humans occurs by ingestion of undercooked, salted, pickled, or smoked freshwater fish ④. After ingestion, the metacercariae excyst in the duodenum ⑤and ascend the biliary tract through the ampulla of Vater ⑥. Maturation takes approximately 1 month. The adult flukes (measuring 10 to 25 mm by 3 to 5 mm) reside in small and medium sized biliary ducts. In addition to humans, carnivorous animals can serve as reservoir hosts. (www.cdc.gov)



Clonorchis sinensis ova in uterus of worm.

5. **What are the clinical manifestations of Clonorchiasis?**
   - Commonly infected early in life and asymptomatic.
   - Benign infections are usually identified by routine stool examination revealing eggs.
   - Acute Clonorchiasis: Katayama-like, malaise, fever, WBCs and Eosinophils elevated.
   - Patients don't become symptomatic until at least the 3rd decade of infection >>> the following symptoms:
     1. dull pain in upper right quadrant – can be intermittent and last for months to years
     2. lassitude
     3. anorexia
     4. loose stools
     5. poor appetite
     6. low-grade fever
     7. hepatosplenomegaly
     8. intermittent fever
   - in advanced stages of disease, liver is enlarged, gallbladder is palpable and functioning poorly, some patients have intermittent fever and jaundice from relapsing cholangitis or **pyogenic cholangitis.**
   - **Cholangiocarcinoma** is observed in association with clonorchis and deterioration is rapid with a fatal outcome.

6. **What are some potential complications of Clonorchiasis?**
   - Intrahepatic calculi
   - Biliary obstruction due to fibrosis or cirrhosis and goblet cell metaplasia
   - Recurrent cholangitis with pyogenic abscesses, endophlebitis, and acute pancreatitis
   - Cholangiocarcinoma

7. **How is Clonorchiasis diagnosed?**
   - By finding Clonorchis eggs in the stool or biliary fluid.
   - **Endoscopic retrograde cholangiopancreatography (ERCP)**
   - **Transhepatic cholangiogram**



Image: Clonorchis sinensis egg (20-30 x 15-17µm), note the operculum or lid. This structure opens to permit the miracidium to escape.

8. **How should Clonorchiasis be treated?**
   - **Praziquantel**
   - Cure rates of 85-100%

9. **How can Clonorchiasis be prevented?**
   - Through cooking and freezing freshwater fish, or through use of salt in 10% brine solution.

- Educational efforts directed towards changing eating habits – drying, pickling and smoking are ineffective at killing organisms.

10. **What is Paragonimiasis?**
    - Paragonimiasis is infection by lung flukes of the genus Paragonimus.
    - Most common species is the **Oriental Lung Fluke, Paragonimus westermani.**
    - Paragonimiasis is a zoonotic lung infection of wild felines and canines throughout the world, but main endemic foci of human infections is in Asia, Africa, and Central & South America.
    - 20 million infections worldwide – Asia, Africa, Peru, Venezuela, US, Costa Rica
    - Adult worms usually live encapsulated in pockets in the lungs, but may be found in extrapulmonary sites.
    - Transmission: disease is acquired by ingesting **raw crayfish & crab**. Contributing factors:
        1. large number of reservoir hosts (humans and animals)
        2. abundance of first and second intermediate hosts
        3. social customs among some Asian populations of eating raw crab, crayfish or shrimp

11. **What is the morphology of the Oriental Lung Fluke?**
    - Adult parasites are reddish brown, ovoid or coffee bean shaped, with broad anterior end
    - Their tegument is covered with cuticular spines
    - They are bilaterally symmetrical and dorso-ventrally flattened, with anterior oral and ventral suckers
    - All are **hermaphroditic**
    - The eggs are golden brown, asymmetrically ovoid with a thick shell, and have a flattened **operculum**



Left image: Paragonimus westermani adult lung fluke. The living adult is reddish brown, ovoid, "coffee-bean" in appearance. It is 7-16mm in length x 4-8mm in width.
Right image: Paragonimus westermani golden brown ova (80-118µm x48-60µm).

12. **What is the life cycle of the Oriental Lung Fluke?**
    - Adult flukes live in and lay eggs within a **pulmonary cyst.**
    - The eggs are passed along a tunnel that connects to a large bronchus and are expectorated with sputum or swallowed and passed through feces.
    - On reaching water, the eggs hatch in 3 weeks to form **mircidia** >>> which invade tissues of snails (first intermediate host).
    - In snails, they undergo asexual transformation into **sporocysts >>> rediae**
    - **Cerceriae** emerge from snails and penetrate crustaceans (crabs & crayfish are 2nd intermediate host) >>> become **infective-stage metacercariae** in 6-8 weeks. Crabs can also acquire infection by eating infected snails.
    - When infected crustaceans are consumed by mammals (definitive host), the metacercariae excyst in the duodenum >>> penetrate the intestinal wall >>> migrate through abdominal wall >>> grow into flukes in 1 week >>> flukes penetrate the diaphragm and enter lung tissue >>> form **pseudocapsule** and grow into adult flukes in 5-6 weeks.
    - Then they produce eggs that appear in sputum or feces in 8-10 weeks.
    - Flukes can live up to 20 years in humans.


❺ Cercariae invade the crustacean and encyst into metacercariae. ⓘ
(4a) (4b) (4c)
Sporocysts Rediae Cercariae
CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx
Humans ingest inadequately cooked or pickled crustaceans containing metacercariae. ❻
❹
❼ Excyst in duodenum
❸ Miracidia hatch and penetrate snail
❽ Adults in cystic cavities in lungs lay eggs which are excreted in sputum. Alternately eggs are swallowed and passed with stool.
❷ Embryonated eggs
d
❶ Unembryonated eggs
i = Infective Stage
d = Diagnostic Stage

The eggs are excreted unembryonated in the sputum, or alternately they are swallowed and passed with stool ❶. In the external environment, the eggs become embryonated ❷, and miracidia hatch and seek the first intermediate host, a snail, and penetrate its soft tissues ❸. Miracidia go through several developmental stages inside the snail ❹: sporocysts (4a), rediae (4b), with the latter giving rise to many cercariae (4c), which emerge from the snail. The cercariae invade the second intermediate host, a crustacean such as a crab or crayfish, where they encyst and become metacercariae. This is the infective stage for the mammalian host ❺. Human infection with *P. westermani* occurs by eating inadequately cooked or pickled crab or crayfish that harbor metacercariae of the parasite ❻. The metacercariae excyst in the duodenum ❼, penetrate through the intestinal wall into the peritoneal cavity, then through the abdominal wall and diaphragm into the lungs, where they become encapsulated and develop into adults ❽(7.5 to 12 mm by 4 to 6 mm). The worms can also reach other organs and tissues, such as the brain and striated muscles, respectively. However, when this takes place completion of the life cycles is not achieved, because the eggs laid cannot exit these sites. Time from infection to oviposition is 65 to 90 days.
Infections may persist for 20 years in humans. Animals such as pigs, dogs, and a variety of feline species can also harbor *P. westermani*.

13. What is the pathogenesis of infection with Lung Flukes?

- Migrating larval flukes in the lungs and frequently in other tissues induce local necrosis, hemorrhage and inflammatory exudates >>> followed by fibrous encapsulation into a worm cyst.
- Pathology includes:
    1. Lung: granumolatous reactions >>> fibrosis and bronchiectasis, or bronchopneumonia, interstitial pneumonia, bronchitis, atelectasis, pleural thickening, pleural effusion, angiitis obliterans, periphlebitis.

2. Abdominal cavity: abscesses and ulcers in muscle, eggs cause pseudotubercle formation in liver, lymph nodes, gut wall.
3. CNS: abscesses in brain and spinal cord.

14. What are the clinical manifestations of Paragonimiasis?

- In light infections, most patients are asymptomatic.
- In heavy infections, patients may have few symptoms and appear well in spite of severe pathology.
- **Acute Stage:** corresponds to period of migration and invasion of young flukes. Incubation period of 2-15 days. Often passes undiagnosed, but may include diarrhea, abdominal pain, urticaria, and eosinophilia, followed by fever, chest pain, cough, dyspnea, malaise and night sweats, and last for a few weeks.
- **Pulmonary Paragonimiasis:** incubation period of 6 months, predominant symptom cough.
    1. Cough, sputum and chest discomfort increase gradually (with clinical presentation similar to chronic bronchitis)
    2. hemoptysis
    3. SOB with exertion
    4. wheezing
    5. mild fever
    6. normal hemoglobin with relative eosinophilic leukocytosis
    7. Chest x-ray: ill-defined opacities early on, and later cysts (**ring shadow w/ a crescent-shaped opacity** along one side), extensive infiltration and pleural involvement



Image: Infiltrates due to Paragonimiasis

- **Ectopic sites:** brain & spinal cord, intestinal wall, lymph nodes, and subQ
- **Cerebral & Spinal Paragonimiasis:** some mature flukes migrate from the lungs through the juguluar or carotid foramen to the temporal or occipital lobes of the brain >>> necrosis and eosinophilic granulomatous reactions. Most common in children and males. Patients can die if left untreated, if not, remission occurs in 1-2 months, but can recur. Patients present with:
    1. headache
    2. vomiting
    3. fever
    4. visual disturbances
    5. rarely, transverse myelitis
    6. spinal tap shows **eosinophilic pleocytosis**
    7. CT shows cysts

15. How is Paragonimiasis diagnosed?

- Eggs in sputum, stool, pleural effusions or cerebrospinal fluid
- Adult flukes in subQ nodules or other surgical specimens
- Chest x-ray with characteristic **ring lesions**
- Serologic testing with **ELISA** is useful for ectopic sites

16. How is Paragonimiasis treated, and how can it be prevented?

- **Praziquantel** cure rates of 100%
- High doses in cerebral disease
- Steroids may be necessary
- Prevention: cook raw crustaceans and use good hygiene

14. What is Fascioliasis?

- **Sheep Liver Fluke Disease** is an infection caused by **Fasciola hepatica**, that infects the bile ducts and gallbladder and extra-hepatic sites.
- Distribution: sheep-raising areas, 2 million infections

- Transmission: humans become infected when they eat vegetation encysted with metacercariae (such as **watercress sandwiches**).



15. What is the morphology of Fasciola hepatica?

- F. hepatica is relatively flat, leaf-like and fleshy
- 20-30 mm x 8-13 mm
- Its broader anterior portion is covered with scale-like spines.
- A distinct **cephalic cone** gives a characteristic shouldered appearance.
- The eggs are light yellowish-brown, large and ovoid with an inconspicuous operculum, measuring 130-150 micrometers x 60-90 micrometers.





Left image: stained Fasciola hepatica. Right image: unstained specimen of F. hepatica, a moderately fleshy fluke up to 30mm in length by 13mm wide.



Fasciola showing prominent integumental spines.

16. What is the life cycle of Fasciola hepatica?

- Adult parasites live in the large biliary ducts of host. Most important definitive hosts are **sheep**, but cattle, horses, camels, pigs, rabbits and deer are commonly infected.
- Eggs pass from host feces and hatch in water.

- **Miracidia** penetrate various lymnaeid snails (first intermediate hosts) and develop in 4-7 weeks from **sporocysts** >>> **rediae** >>> **daughter rediae** >>> **cercariae**
- Mature cercariae emerge from the snail and encyst on various kinds of aquatic vegetation to become **metacercariae**
- Metacercariae are ingested, excyst on duodenum >>> migrate through intestinal wall into peritoneal cavity >>> pass through Glisson's capsule >>> traverse the liver parenchyma >>> bile duct where they mature. This takes 3-4 months.
- Life span is estimated to be 9-13 years.

Life Cycle:


4a Sporocysts
4b Rediae
4c Cercariae
in snail tissue
5 Free-swimming cercariae encyst on water plants
Metacercariae on water plant ingested by human, sheep, or cattle 6
i
CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx
4 Snail
7 Excyst in duodenum
3 Miracidia hatch, penetrate snail
7
8
2 Embryonated eggs in water
d
8 Adults in hepatic biliary ducts
i = Infective Stage
d = Diagnostic Stage
1 Unembroynated eggs passed in feces

Immature eggs are discharged in the biliary ducts and in the stool ①. Eggs become embryonated in water ②, eggs release miracidia ③, which invade a suitable snail intermediate host ④, including many species of the genus *Lymnae*. In the snail the parasites undergo several developmental stages (sporocysts (4a), rediae (4b), and cercariae (4c)). The cercariae are released from the snail ⑤and encyst as metacercariae on aquatic vegetation or other surfaces. Mammals acquire the infection by eating vegetation containing metacercariae. Humans can become infected by ingesting metacercariae-containing freshwater plants, especially watercress ⑥. After ingestion, the metacercariae excyst in the duodenum ⑦and migrate through the intestinal wall, the peritoneal cavity, and the liver parenchyma into the biliary ducts, where they develop into adults ⑧. In humans, maturation from metacercariae into adult flukes takes approximately 3 to 4 months. The adult flukes (*Fasciola hepatica*: up to 30 mm by 13 mm; *F. gigantica*: up to 75 mm) reside in the large biliary ducts of the mammalian host. *Fasciola hepatica* infect various animal species, mostly herbivores. (www.cdc.gov)



17. What is the pathogenesis of Fascioliasis?

- Migrating metacercariae cause local hepatic parenchymal destruction, necrosis and abscess formation.
- Once they reach the bile ducts and mature, adult flukes may cause epithelial hyperplasia and periductal fibrosis.
- Adults in the biliary tree may lead to cholangitis and stone formation.
- The gall bladder may commonly be involved and rarely cirrhosis has been reported.
- Ectopic fascioliasis commonly involves lungs, and sometimes subQ tissues, brain and orbits.



Liver fluke (Fasciola) in liver at autopsy.

18. What are the clinical manifestations of Fascioliasis?

A. Acute Phase

- Patients may develop anorexia, nausea, vomiting, fever and right upper quadrant pain
- Hepatomegaly may occur with tenderness and marked eosinophilia
- Severe illness with prostration and jaundice is unusual.
- This phase is due to the larval flukes migrating through the liver and stopping when they penetrate the bile ducts.
- Patients may be asymptomtic during this phase.

B. Chronic Phase

- Most patients have few or no symptoms after the flukes lodge in the biliary passages.
- Some have epigastric and right hypochondrial pain, diarrhea, nausea, vomiting, hepatosplenomegaly, and jaundice.
- If the flukes lodge in extrahepatic biliary ducts, may have symptoms of cholelithiasis.
- Abnormal liver function and eosinophilia are common.
- Complications include biliary obstruction.



Fasciola ova in uterus of adult fluke.

19. What is the distribution of Fasciola hepatica?

- Fascioliasis occurs worldwide.
- Human infections with *F. hepatica* are found in areas where sheep and cattle are raised, and where humans consume raw watercress, including Europe, Cuba, the Middle East, and Asia, and also in South America.
- Infections with *F. gigantica* have been reported, more rarely, in Asia, Africa, and Hawaii.

20. How do you diagnose Fascioliasis?

- Eggs in the stool
- Serology tests are also available



Image: Fasciola hepatica egg (130-150μm x 63-90μm). The operculum can be seen in the "7 o'clock" position.

21. **How do you treat Fascioliasis?**
    - **Triclabendazole**

LECTURE #3: CESTODES I – D. LATUM, TAENIASIS

1. **What are some significant characteristics of Tapeworms/Cestodes?**
    - Infections with tapeworms are one of the oldest recognized afflictions of humankind.
    - Cestodes are dorso-ventrally flattened, and divided into sexually complete segments.
    - Adult tapeworms posess a **scolex** or head that may be modified with structures or organelles that serve as organs of attachment to the small intestine mucosa.
    - The **bothria** are sucking grooves that attach to the ileum or jejunum. They use the bothria to transfer nutrients through microvilli-like structures from host to worm, so glucose is taken directly from host's intestinal lumen.
    - The digestion portion of the scolex is termed the neck, and it is an area of intense metabolic activity. It is also the area where new segments, or **proglottids**, proliferate and form the **strobila.**
    - Cinically, the **scolex** is important because therapy is aimed at its destruction or elimination.
    - The most proximal proglottids are usually immature, while the more distant proglottids are more mature with sex organs.
    - The surface epithelium, or tegument, is actually a syncitium composed of anucleate ectocytoplasm that covers the body of the tapeworm and an underlying layer containing the nucleated cell bodies or perikarya.
    - They have circular and longitudinal muscles, a primitive nervous system, highly complex repro organs, and primitive excretory system, and complex life cycles.
    - They inhibit host enzymes, block host cell motility and limit lymphocyte mitogenic response.
    - Infections with adult oranisms typically not life-threatening, but larval infections can be.

2. **What are Diphyllobothrium latum?**
    - Diphyllobothriasis is an infection of the intestinal tract by the **Broad** or **Fish Tapeworm.**
    - Disease is found worldwide.
    - Transmission: humans become infected by ingesting D. latum pleroceroid larvae in fish or fish eggs that are raw or incompletely cooked. Varieties of freshwater as well as some marine fishes are sources of infection.
    - Intermediate hosts: **crustaceans & fish**
    - Definitive hosts: humans and fish-eating carnivores such as bear, cats, dogs.



Image: Diphyllobothrium latum scolex and immature proglottids. The scolex has a pair of grooves, termed bothria, that are used as adherence structures.

3. **What is the morphology of Diphylobothrium latum?**
    - D. latum ranges in length from 1-12 meters
    - **Proglottid**s are usually wider than they are long, and in the center of mature ones there is a characteristic **dark rosette** – egg filled uterus. The largest worms have thousands of proglottids.
    - The ovoid eggs measure 42-50 microns by 75 microns and have a lid-like **operculum** at one end and a small **knob** at the other end.

Left image: Diphyllobothrium latum egg (42-50 x 59-75μm). The egg has an operculum which opens in freshwater to allow egress of the ciliated larva or coracidium.





ht image: Diphyllobothrium latum gravid proglottid showing the uterus and the muscular uterine pore from which eggs are discharged into the fecal stream.

4. **What is the distribution of D. latum?**
   - Common in lake country in the US, central Florida, Adirondacks
   - Japan
   - Argentina
   - Africa
   - Baltic States
   - Israel
   - Finland

5. **What is the lifecycle of Diphylobothrium latum?**
   - Feces with eggs from infected hosts are discharged into fresh or brackish water that contains susceptible crustaceans or fish.
   - After the egg hatches, the motile **hexacant embryos** or **coracidia** are released into water and must find a host quickly, if successful, they are ingested by minute crustecea called water fleas >>> which are ingested by small fish.
   - The first stage larva (**procercoid larvae**) develop in the fish >>> which are then eaten by larger fish >>> develops into a **plerocercoid** or **sparganum larvae,** which is infective for final host.
   - Infection occurs when the infected fish are then eaten raw by definitive hosts.

Life Cycle:


Infected crustacean ingested by small freshwater fish Procercoid larva released from crustacean, develops into plerocercoid larva ⑤
i
Predator fish eats infected small fish ⑥
CDC
SAFER · HEALTHIER · PEOPLE™
http://www.dpd.cdc.gov/dpdx
i = Infective Stage
d = Diagnostic Stage
Procercoid larvae in body cavity of crustaceans ④
Human ingests ⑦ raw or undercooked, infected fish
scolex
Adults in small intestine ⑧
Coracidia hatch from eggs and are ingested by crustaceans. ③
d
② Eggs embryonate in water
① Unembryonated eggs passed in feces
⑨ Proglottids release immature eggs

Immature eggs are passed in feces ①. Under appropriate conditions, the eggs mature (approximately 18 to 20 days) ②and yield oncospheres which develop into a coracidia ③. After ingestion by a suitable freshwater crustacean (the copepod first intermediate host) the coracidia develop into procercoid larvae ④. Following ingestion of the copepod by a suitable second intermediate host, typically minnows and other small freshwater fish, the procercoid larvae are released from the crustacean and migrate into the fish flesh where they develop into a plerocercoid larvae (sparganum) ⑤. The plerocercoid larvae are the infective stage for humans. Because humans do not generally eat undercooked minnows and similar small freshwater fish, these do not represent an important source of infection. Nevertheless, these small second intermediate hosts can be eaten by larger predator species, e.g., trout, perch, walleyed pike ⑥. In this case, the sparganum can migrate to the musculature of the larger predator fish and humans can acquire the disease by eating these later intermediate infected host fish raw or undercooked ⑦. After ingestion of the infected fish, the plerocercoid develop into immature adults and then into mature adult tapeworms which will reside in the small intestine. The adults of *D. latum* attach to the intestinal mucosa by means of the two bilateral groves (bothria) of their scolex ⑧. The adults can reach more than 10 m in length, with more than 3,000 proglottids. Immature eggs are discharged from the proglottids (up to 1,000,000 eggs per day per worm) ⑨and are passed in the feces ①. Eggs appear in the feces 5 to 6 weeks after infection. In addition to humans, many other mammals can also serve as definitive hosts for *D. latum*.

6. **What are the clinical manifestations of infection with Diphyllobothrium latum?**
   - Most patients are asymptomatic or mildly symptomatic.
   - Small percentage develop **megaloblastic anemia.**
   - Worm is not invasive, and there is little pathologic damage associated with infection other than that related to competition between the host and parasite for absorption of **vitamin B12.**
   - Symptoms may include:
     1. weight loss
     2. increased or decreased appetite
     3. symptoms of **pernicious anemia** (weakness, fatigue, peripheral neuropathy, diarrhea, weight loss, decreased appetite, etc.)

4. massive worm can obstruct small intestine >>> **intersussception** >>> compromising intestinal circulation.

- Symptoms in children: worms secrete proteins into intestinal lumen that can lead to syncope or seizures.
  1. abdominal pain
  2. changes in appetite
  3. seizures
  4. syncopal attacks

7. **Discuss the pernicious anemia-like syndrome that can be associated with D. latum infection?**
   - D. latum has a high affinity for Vitamin B12 >>> producing a **hyperchromatic macrocytic megaloblastic anemia without thrombocytopenia**, that resembles pernicious anemia both clinically and hematologically.
   - The anemia is usually moderate, but can be severe, and is characterized by pallor, glossitis, dyspnea, paresthesia, disturbance of movement and coordination, and impairment of deep senses, subacute combined degeneration >>> decreased hemoglobin and decreased oxygen in blood.
   - Vitamin B12 absorption based on Intrinsic Factor
   - binds to ileal receptor (Ca2+)
   - pancreatic factor also increases absorption
   - 40% of infected have low B12, 2% develop anemia, worm uptake of B12 is 1000:1

8. **How is an infection with Diphyllobothrium latum diagnosed?**
   - Through characteristic eggs with operculum.

9. **How is an infection with Diphyllobothrium latum treated?**
   - **Praziquantel** or **Niclosamide** (not available in US)
   - Affects voltage-gated Ca2+ channels
   - A single dose is curative in >90% of patients

10. **How do you prevent infection with Diphyllobothrium latum?**
    - Careful cooking or freezing of fish
    - Drying or pickling in brine

11. **What is Taeniasis?**
    - The pork tapeworm is Taenia solium.
    - The beef tapeworm is Taenia saginata.
    - They are both common human parasites, and infection occurs in people who have eaten raw or improperly cooked pork or beef.
    - Humans are the only definitive hosts.
    - T. saginata is a cosmopolitan parasite, with regions of high endemnicity in Latin America , Africa, the Middle East, and Central Asia.

12. **What is the morphology of Taenia solia and Taenia saginatum?**
13. **A. T. saginata**
    - Adults 5-12 meters in length
    - 1000-2000 proglottids
    - The scolex has 4 sucking disks and lacks a crown or rostellum with hooks (**unarmed scolex**).

B. T. solium
- 1.5-8 meters in length
- 1000 proglottids
- Scolex with a well-developed crown of rostellar hooks (**armed scolex**).





Top image: T. solium with armed scolex. Bottom image: T. saginita with unarmed scolex

14. **What are the life cycles of Taenia solia and Taenia saginatum?**
    - Cattle or pigs become infected by ingesting eggs while grazing in low-lying pastures or barnyards that are contaminated with human feces >>> eggs hatching inside the animal >>> embryos then penetrate the

intestinal mucosa >>> enter animal's circulation and are transported throughout the body >>> embryos encyst in animal's striated muscle >>> develop into larvae called **cysticercus cellulosae** (in pigs) or **cystericus bovis** (in cattle), which are infectious if ingested by definitive host.

- Upon consumption of infected meet that is improperly cooked, the cystericus is activated by gastric juices and the scolex evaginates and attaches to a person's jejunal wall >>> becomes a mature tapeworm.

Life Cycle:



i Oncospheres develop into cysticerci in muscle
4 Humans infected by ingesting raw or undercooked infected meat
Oncospheres hatch, penetrate intestinal wall, and circulate to musculature
3
T. saginata
T. solium
5 Scolex attaches to intestine
6 Adults in small intestine
2
Cattle (T. saginata) and pigs (T. solium) become infected by ingesting vegetation contaminated by eggs or gravid proglottids
T. saginata
T. solium
d
1
Eggs or gravid proglottids in feces and passed into environment
i = Infective Stage
d = Diagnostic Stage
CDC
SAFER・HEALTHIER・PEOPLE™
http://www.dpd.cdc.gov/dpdx

Life cycle of *Taenia saginata* and *Taenia solium*

Humans are the only definitive hosts for *Taenia saginata* and *Taenia solium*. Eggs or gravid proglottids are passed with feces ①; the eggs can survive for days to months in the environment. Cattle (*T. saginata*) and pigs (*T. solium*) become infected by ingesting vegetation contaminated with eggs or gravid proglottids ②. In the animal's intestine, the oncospheres hatch ③, invade the intestinal wall, and migrate to the striated muscles, where they develop into cysticerci. A cysticercus can survive for several years in the animal. Humans become infected by ingesting raw or undercooked infected meat ④. In the human intestine, the cysticercus develops over 2 months into an adult tapeworm, which can survive for years. The adult tapeworms attach to the small intestine by their scolex ⑤and reside in the small intestine ⑥. Length of adult worms is usually 5 m or less for *T. saginata* (however it may reach up to 25 m) and 2 to 7 m for *T. solium*. The adults produce proglottids which mature, become gravid, detach from the tapeworm, and migrate to the anus or are passed in the stool (approximately 6 per day). *T. saginata* adults usually have 1,000 to 2,000 proglottids, while *T. solium* adults have an average of 1,000 proglottids. The eggs contained in the gravid proglottids are released after the proglottids are passed with the feces. *T. saginata* may produce up to 100,000 and *T. solium* may produce 50,000 eggs per proglottid respectively.

15. What is the distribution of Taenia solia and Taenia saginata?

- Both species are worldwide in distribution.
- Taenia solium is more prevalent in poorer communities where humans live in close contact with pigs and eat undercooked pork, and in very rare in Muslim countries.

16. What are the clinical manifestations of Taeniasis?

- Most tapeworm carriers are asymptomatic and only become aware of infection when they see proglottids in feces or notice strange sensations due to spontaneous movement of tapeworm segments through the anus.
- Mild GI symptoms can occur in some patients such as nausea and vague epigastric pain
- Also anorexia, headaches, dizziness, diarrhea
- Cysticercosis infection with the larval form of Taenia solium is a potentially serious complication of T. solium infections.

17. How do you diagnose Taeniasis?

- Infection often recognized due to elimination in feces
- The standard method for differentiating between species is to count the number of primary uterine branches in gravid proglottids
    1. T. solia has ≤10
    2. T. saginata has ≥12
- Visual demonstration of eggs in stool is not specific, b/c solia and saginata eggs appear identical under light microscope.

18. How do you treat Taeniasis?

- Treat with **Praziquantal** or **Niclosamide**
- Important to distinguish between different eggs, b/c eggs of T. solia are activated by gastric juices and **Praziquantal** can cause nausea as T. solia move to stomach, so must monitor patient in office during treatment.

19. What is the significance of, and causative agents of, Cysticercosis?

- Cysticercosis is an infection of human tissues with the larvae of the pork tapeworm, Taenia solium.
- The symptoms of cysticercosis are caused by the development of cysticerci in various sites. Of greatest concern is cerebral cysticercosis (or neurocysticercosis), which can cause diverse manifestations including seizures, mental disturbances, focal neurologic deficits, and signs of space-occupying intracerebral lesions. Death can occur suddenly. Extracerebral cysticercosis can cause ocular, cardiac, or spinal lesions with associated symptoms. Asymptomatic subcutaneous nodules and calcified intramuscular nodules can be encountered.
- Humans can be both intermediate host and main host for T. solia, not for T. saginata.

20. What is the epidemiology of Cysticercosis?

- *Taenia solium* is found worldwide, but particularly common in Mexico and other parts of Latin America.
- It is the most common parasitic disease of the CNS in the world, and the most frequent parasitic cause of seizures!
- Because pigs are intermediate hosts of the parasite, completion of the life cycle occurs in regions where humans live in close contact with pigs and eat undercooked pork.
- Taeniasis and cysticercosis are very rare in Muslim countries.
- It is important to note that human cysticercosis is acquired by ingesting *T. solium* eggs shed in the feces of a human *T. solium* tapeworm carrier, and thus can occur in populations that neither eat pork nor share environments with pigs.

21. What is the life cycle of Taenia solium?

- T. solium has separate adult (intestinal tapeworms) and larval (metacestode or cysticercus) forms (which is typical of cestodes in general). Humans can host both forms of the parasite, in contrast to other cestodes.
- In the normal life cycle (described above), the larval form is found primarily in pig muscle (intermediate host).
- Human cysticercosis follows ingestion of ova from a tapeworm carrier – typically through close personal contact or food preparation, and carriers can autoinfect also.
- Following ingestion, the oncospheres are carried to a number of organs such as skeletal and cardiac muscle, subQ tissue, and lungs. In most locations cause few symptoms, and just form calcific granulomas.

22. What are the clinical manifestations of Cysticercosis?

- Can be 3-15 years before patient becomes symptomatic.
- Cysticercosis involving CNS is neurocysticercosis.

- Clinical presentation, pathogenesis, management and prognosis varies widely based on location and number of cysticerci and associated host response.
- Neurocysticercosis is typically separated into parenchymal and extra-parenchymal disease based on whether or not there is involvement of the subarachnoid space and ventricles, but also include spinal and ocular disease.
- Parenchymal neurocysticercosis usually presents with **headaches & seizures** (most common presentation) and has a favorable prognosis.
- Neurocyticercosis due to extraparenchymal disease is more severe, often requires surgery, and can be fatal.
- Subarachnoid and ventricular diseases are often complicated by increased intracranial pressure and hydrocephalus, so patients present with headache, dizziness, altered mental status, and visual chances due to papilledema.
- Cysticerci can also involve the muscles
- Soft tissue calcifications are frequently found in all forms of Cysticercosis.
- Cystecerci often involve the SubQ tissues, where they present as palpable, painless and mobile cystic lesions that can be confused with sebaceous cysts – rare, but common in SS Africa.

23. How is Cysticercosis diagnosed?

- Through a combo of epidemiology, CT scan, MRI, and serology (**Western Blot** is highly sensitive and specific if 2+ cysts are present, **ELISA** is less specific). Serology is only 30% sensitive if only 1 cyst.

24. How is Cysticercosis treated?

- Albendazole or Praziqunatel
- **Albendazole** has been found to be superior in clinical studies. It works by inhibiting polymerization of parasitic microtubules >>> decreased glucose uptake >>> eventual death.
- **Corticosteroids** are used to control inflammation in Neurocysticercosis, and **anti-seizure meds.**
- Patients with hydrocephalus often require a ventrico-peritoneal shunt to relieve pressure.
- All patients with cysticercosis should be examined for tapeworms and their family should be examined as well.

LECTURE #4: CESTODES II - ECHINOCOCCUS

1. What is Cystic Hydatid Disease?

- **Cystic Hydatid Disease** is a zoonotic disease in humans and diverse mammalian species. It is caused by the larval form of a canine tapeworm, **Echinococcus granulosus.**
- E. granulosus is a small tapeworm (2-7 mm in length) typically of 3 segments.
- In the natural cycle, dogs and other canines are typical definitive hosts and ungulates (sheep, goats, pigs, horses, etc.) are intermediate hosts, which harbor the metacestode stage.
- The metacestode stage can also develop in mammals such as marsupials, rabbits, rodents, carnivores, primates and humans. These and other hosts play a role in the transmission cycle (intermediate hosts) or are dead ends for development (aberrant hosts).
- Important disease, b/c very common!

2. Describe the pathogenesis of an infection with E. granulosis.

- Echinococcus is caused by the metacestode stage of various strains of E. granulosus, which is a cystic structure filled with hydatid fluid.
- About 5 days after ingestion of eggs, the metacestode is a small, bilayered vesicle.
- The cyst gradually expands and induces a granulomatous reaction in the host >>> followed by a fibrous reaction and formation of a connective tissue layer or pericyst.
- The size of cysts in the human body vary (1-20 cm) and remain sterile.
- The initial phase of primary infection is always asymptomatic. Small, well encapsulated, non-progressive or calcified cysts typically do not induce major pathology, and patients may remain asymptomatic for years or permanently.
- The induction of morbidity depends on the number, size and developmental status of the cysts within an organ, the presence of cysts on surrounding tissues and structures, the defense mechanisms of host.
- Cyst growth is generally slow.
- **Hydatid fluid** is highly immunogenic, and germinal membrane is very potent >>> can form new hydatid cysts if pieces of it break off.

- Can have circulating immune complexes >>> rarely, causes **Glomerulonephritis.**
- Pressure necrosis
- Expanding, space-occupying lesions.

3. **Where do hydatid cysts form?**
   - Liver (60-70%): more frequently in right lobe, usually asymptomatic. Cysts can rupture into bile duct, resulting from obstructive jaundice and colic-like pain followed by bacterial overgrowth. Rupture into peritoneal cavity usually leads to secondary formation of numerous peritoneal cysts. Rupture and leakage of cyst fluid also causes erythematous rash or anaphylaxis, and rarely death.
   - Lung (25%): non-complicated cysts rarely produce symptoms. Symptomatic patients have chest pain, Dyspnea, fever, and hemoptysis, and can be confused with TB. Rupture of a cyst often leads to expectoration of hydatid fluid or membranes >>> bacterial overgrowth and lung abscess formation.
   - Bone
   - CNS
   - If an individual has 1 cyst, look for others!



Image: Hydatid cyst in the liver. 65-75% of hydatid cyscts are found in the liver. The cyst consists of a parasite-derived inner germinal membrane, which secretes an outer acellular membrane. A pericyst which is host derived lies outside the acellular membrane.

4. **What sort of symptoms are associated with infection with Echinococcus?**
   - Can be asymptomatic for decades
   - Signs and symptoms of hydatid disease depend on organ involvement and size of cyst.
   - Onset of symptoms varies from months to years.
   - Eosinophilia (25%)
   - Liver and biliary tract symptoms: rupture into biliary tract can lead to obstruction and pyogenic abscesses
   - Fractures of bone
   - CNS, cardiac and pulmonary symptoms due to rupture into lung, pericardium, etc.
   - Pain is typically seen, except in liver or lung because more room to expand

5. **Discuss complications of infection with Echinococcus.**
   - Hepatic and Biliary Tract symptoms / complications most common
   - Rupture into biliary tract >>> obstruction of bile ducts >>> ascending bacterial infection >>> pyogenic abscess
   - Rupture into lung, mediastinum and pericardium
   - Not a benign disease.

6. **What is the distribution of Echinococcus?**
   - **E. granulosa:** worldwide; prevalent in areas where dogs are used to herd sheep – South America, Mediterranean, southern and central Russia, central Asia, Australia, Africa, and endemic to Uruguay, Argentina, Chile, southern Brazil, and Peru.
   - **E. multilocularis:** northern hemisphere
   - **E. vogeli:** South and Central America
   - More common in areas where uncontrolled dogs are living close to people, or unsanitary living conditions, or in an area with uncontrolled slaughter of infected livestock.

7. **What is the morphology of Echinococcus granulosa?**
   - The metacestode stage of E. granulosoa is a cystic structure typically filled with a clear fluid **(hydatid fluid)**.



- It is a small vesicle (60-70 micrometers in diameter) consisting of an internal cellular layer **(germinal layer**), and an outer acellular layer (**laminated layer**).

Echinococcus granulosus, the entire adult tapeworm consists of a scolex and 3 segments: an immature, mature and gravid proglottid.

8. What is the life cycle of Echinococcus?

- Life cycle involves two mammalian hosts
- Adult cestode inhabits small intestine of a carvinore (definitive host) >>> **proglottids** containing eggs or free eggs are released from intestinal tract of carnivore into environment.
- The eggs contain the infective **oncosphere**
- After oral uptake of eggs by an intermediate host >>> the larval stage or **metacestode** develops in this host's internal organs.
- Mature metacestode produces numerous **protoscoleces** that have the potential to develop into an adult cestode if ingested by a suitable definitive host (such as dogs).
- The invasion of various organs (primarily lungs and liver) of intermediate hosts by metacestodes can cause severe and even fatal disease (echinococcus).
- Humans are the accidental intermediate host.



Left image: Protoscolices are formed by the germinal membrane of the hydatid cyst and together with internal daughter cysts, brood capsules are the **hydatid sand** all of which are suspended in the hydatid fluid. Right image: Echinococcus granulosus, protoscolex note double row of hooks.


THE LIFE CYCLE OF ECHINOCOCCUS GRANULOSUS
(HYDATID DISEASE OR HYDATIDOSIS)
The adult tapeworm is found in the small intestine of the canine (definitive) host.
The protoscolex attaches to the host's intestine and develops into a tapeworm.
The definitive host is infected when it ingests the hydatid cyst (protoscoleces).
Eggs are passed in the host's feces.
The eggs are ingested by an intermediate host. Many species of warm blooded vertebrates can be infected.
The larva develops into a hydatid cyst.
The larva hatches from the egg in the small intestine, penetrates the intestinal lining, and enters the blood stream.
The larvae can be distributed to almost any organ, but the liver is the most common.

(Parasites and Parasitological Resources)

9. **How do you diagnose Echinococcus infection?**
   - Geographic history important
   - History of canine (and also possibly sheep)
   - Serological tests (immunoblot)
   - MRI, CT, X-ray, US

10. **What are the problems with serodiagnosis?**
    - False positives using whole hydatid cyst fluid; could be other helminthic infection, could be cancer, could be immune diseases such as SLE, RA.
    - False negative results also occur 50% of time, particularly in lung, spleen and brain
    - ELISA test good for intiital screen 60-90% sensitive, but not very specific, confirm with immunoblot 8, 16, 21 kDa bands), but this is also found in 5-10% of patients with **cysticercosis.**
    - So, need geographic history, scans, etc. to make diagnosis.
    - Monitor **IgG4** for efficacy of treatment
    - In seronegative patients in which you have a high suspicion of infection, do **percutaneous aspiration of liver** looking for hyatid sand.

11. **What is the significance of intrabiliary rupture with Echinococcus infection?**

- Extremely important to diagnose intrabiliary rupture in this disease, b/c requires immediate surgery to remove cyst.
- **Endoscopic retrograde cholangiopancreatography (ERCP).**
- CT
- MRI
- US

12. How do you treat Hydatid Disease?

- Surgical resection if cyst is leaking, infected or has a biliary tree infection, or >10cm in size
- Drug therapy: **Albendazole** primarily, rarely **Mebendazole**. Albendazole is more biologically active, but they are metabolized to same compound.
- Albendazole therapy alone is unpredictable - cure rate only 30-40%
- **PAIR: percutaneous aspiration injection & reaspiration.**
- Protoscolicidal Treatment (spill) Albendazole and Praziquantel
- Percutaneous drainage + Albendazole is most effective treatment.

13. What is Alveolar Hydatid Disease?

- Alveolar Hydatid Disease is due to human infection with **Echinococcus multilocularis.**
- Humans are the abnormal, accidental, dead-end hosts of E. multicularis.
- They acquire disease by ingesting eggs shed from its final host (typically foxes).
- The primary lesion is always in liver.
- The oncosphere (embryo) hatches from egg in small intestine and is transported bias portal circulation of liver. After hepatic localization, oncospheres undergo larval development >>> forming multilocular hydatid cysts.
- These cysts grow slowly, reproducing asexually by lateral budding, and spread through the liver and contiguous organs to produce chronic space-occupying tumor-like lesions.
- These cysts occasionally metastasize – usually to lungs and brain.





Echinococcus multilocularis (in abdomen of shrew on right).

14. Where is E. multilocularis (aka Alveolar Hydatid Disease) found?

- Northern Europe including Alps
- Russia – very common in Siberia
- Northern US, Canada, Alaska
- Northern Japan

15. Compare the life cycles of Echinococcus granularis and E. multilocularis.


CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx
6
Scolex attaches to intestine
1
Adult in small intestine
5
Protoscolex from cyst
Ingestion of cysts (in organs)
Definitive Host (dogs & other canidae)
i 2
Embryonated egg in feces
Intermediate Host (sheep, goats, swine, etc.)
Ingestion of eggs (in feces)
d 4
3
Oncosphere hatches; penetrates intestinal wall
Hydatid cyst in liver, lungs, etc.
4
2
4
4
4
4
4
3
i = Infective Stage
d = Diagnostic Stage

The adult *Echinococcus granulosus* (3 to 6 mm long) ❶resides in the small bowel of the definitive hosts, dogs or other canids. Gravid proglottids release eggs ❷that are passed in the feces. After ingestion by a suitable intermediate host (under natural conditions: sheep, goat, swine, cattle, horses, camel), the egg hatches in the small bowel and releases an oncosphere ❸that penetrates the intestinal wall and migrates through the circulatory system into various organs, especially the liver and lungs. In these organs, the oncosphere develops into a cyst ❹that enlarges gradually, producing protoscolices and daughter cysts that fill the cyst interior. The definitive host becomes infected by ingesting the cyst-containing organs of the infected intermediate host. After ingestion, the protoscolices ❺evaginate, attach to the intestinal mucosa ❻, and develop into adult stages ❶in 32 to 80 days. The same life cycle occurs with *E. multilocularis* (1.2 to 3.7 mm), with the following differences: the definitive hosts are foxes, and to a lesser extent dogs, cats, coyotes and wolves; the intermediate host are small rodents; and larval growth (in the liver) remains indefinitely in the proliferative stage, resulting in invasion of the surrounding tissues. With *E. vogeli* (up to 5.6 mm long), the definitive hosts are bush dogs and dogs; the intermediate hosts are rodents; and the larval stage (in the liver, lungs and other organs) develops both externally and internally, resulting in multiple vesicles. *E. oligarthrus* (up to 2.9 mm long) has a life cycle that involves wild felids as definitive hosts and rodents as intermediate hosts. Humans become infected by ingesting eggs ❷, with resulting release of oncospheres ❸in the intestine and the development of cysts ❹, ❹, ❹, ❹, ❹, ④ in various organs.

16. Discuss the nature of infection with E. multilocularis.

- Grows slowly can be >30 years before symptoms
- Always found in liver (30% in right lobe, 60% both lobes)
- Contiguous extension
- Metastatic to lung and brain
- Clinical presentation: most common signs are:
  1. hepatomegaly
  2. palpable peritoneal masses
  3. jaundice

- Very difficult to treat, high fatality 50-75% of patients with invasive disease

17. What is the pathogenesis of E. multilocularis?

- Contrary to the term cyst, E. multilocularis occurs as 1+ firm, solid, yellow-gray cancer-like masses that are always primarily in liver.
- The lesions can occupy any area of the liver (including its surface) with multiple foci. The outer layer of the cyst has an ill-defined margin that diffuses into the host tissue.
- Larval exogenous proliferation is most active at the periphery of the lesion.
- In advanced cases, the central deeper portions of the lesions can undergo extensive hepatic degeneration with central necrosis and calcification, presenting as large, pus-filled cavities.
- 3 categories of patients:
    1. Disease with unlimited proliferation
    2. Proliferation is arrested in liver, lesion calcifies, and person is fine
    3. Seropositive patients with no lesions (+Em2 antigen), completely asymptomatic
- Pre-existing infection confers resistance (murine)

18. What is the normal intermediate host for E. multilocularis?

Rodents

19. How is E. multilocularis diagnosed?

- Usually diagnosed in people >50 years
- MRI/CT scan showing diffuse liver disease with calcifications
- Serology: immunoblot, IHA+ in >90%
- IgG1 + IgG4 correlate with active disease

20. How is E. multilocularis treated?

- Surgical resection
- Long-term medical treatment with **Albendazole** is used in some patients >>> arrests growth, but won't kill cysts.

21. Discuss some characteristics of Hymenolepsis nana.

- Hymenolepiasis is caused by Hymenolepsis nana, and is the most common cause of all cestode infections, and is encountered worldwide, and most frequent tapeworm infection in US.
- 20 million infections worldwide
- No intermediate host is required! Internal or external autoinfection occurs. This may differ from textbooks. Individuals can reinfect themselves, so can have large concentrations of eggs and 1000's of tapeworms >>> clinical symptoms.
- In temperate areas its incidence is higher in children and institutionalized groups.
- Hymenolepis diminuta, while less frequent, has been reported from various areas of the world.
- **Hymenolepis nana** is the smallest adult tapeworm to infect humans – 25-30mm in length x 0.80-1.0 mm in width.
- The entire chain of proglottids from the anterior immature to the distal gravid segments often consists of 175-220 segments.
- The minute rounded scolex possesses 4 sucking disks and a short armed retractable rostellum.
- The infective eggs are liberated when the most distal proglottids disintegrate and are found in stool. They are released by gradual disintegration of the terminal gravid proglottids and are infective immediately when passed in the feces.
- If eggs are ingested, the oncosphere is liberated in host's small intestine and penetrates villi >>> to become cysticercoid larvae.
- In 96 hours the larvae re-enters the lumen to attaché to SI villus by its scolex, usually at a more distal location.
- In 10-20 days it matures and eggs can be found in feces.
- There is evidence of hyperinfection or autoinfection when ova liberated in the SI spontaneously hatch and immediately penetrate intestinal villi to undergo a new development cycle.
- Human is definitive host. Unlike most other tapeworms that infect humans, no intermediate host is required.



Left image: Hymenolepsis nana scolex with 4 suckers & armed retractable rostellum. Right image: H. nana proglottids.

22. What is the life cycle of H. nana?


i = Infective Stage
d = Diagnostic Stage
④ Cysticerci in body cavity of insect ingested by rodent or human
i
CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx
Oncospheres hatch and penetrate intestinal wall
③
⑤ scolex
② Ingested by an arthropod intermediate host
⑥ Adults in small intestine
d
① Eggs passed in feces
⑦ gravid proglottids

Eggs of *Hymenolepis diminuta* are passed out in the feces of the infected definitive host (rodents, man) ①. The mature eggs are ingested by an intermediate host (various arthropod adults or larvae) ②, and oncospheres are released from the eggs and penetrate the intestinal wall of the host ③, which develop into cysticercoid larvae. Species from the genus *Tribolium* are common intermediate hosts for *H. diminuta*. The cysticercoid larvae persist through the arthropod's morphogenesis to adulthood. *H. diminuta* infection is acquired by the mammalian host after ingestion of an intermediate host carrying the cysticercoid larvae ④. Humans can be accidentally infected through the ingestion of insects in precooked cereals, or other food items, and directly from the environment (e.g., oral exploration of the environment by children). After ingestion, the tissue of the infected arthropod is digested releasing the cysticercoid larvae in the stomach and small intestine. Eversion of the scoleces ⑤occurs shortly after the cysticercoid larvae are released. Using the four suckers on the scolex, the parasite attaches to the small intestine wall. Maturation of the parasites occurs within 20 days and the adult worms can reach an average of 30 cm in length ⑥. Eggs are released in the small intestine from gravid proglottids ⑦that disintegrate after breaking off from the adult worms. The eggs are expelled to the environment in the mammalian host's feces. (www.cdc.gov)

23. What is the clinical presentation of infection with H. nana?

- If patient only has a few tapeworms probably will be asymptomatic, but if they have a lot of worms, will have the following symptoms:
  - Headaches
  - Dizziness
  - Anorexia
  - Pruritis ani
  - Periodic diarrhea
  - Abdominal pain (85%)
  - Restlessness and irritability (65%)
  - Eosinophilia (<5%)
  - Seizures (<1%)

24. What is the treatment of choice for H. nana?

- **Praziquantel**

25. How are public lice acquired?

- Through close personal contact.
- Not from toilet seats, or any other casual contact.
- Head lice can be transmitted from child to child through wrestling, etc.

26. How are lice treated?

- **1% Permethrin (Nix),** topical treatment
- **0.5% Malathion (Ovide)** topical
- **Pyrethrins with pipernyl butoxide (Rid)** topical treatment
- **Ivermectin (Stromectol**) – insecticide and powerful antihelminthic, taken orally, used for lice if first treatments don't work. May soon be first line of defense.

LECTURE #5: NEMATODES I – ASCARIS, HOOKWORM, VLM, CLM

1. What organisms cause hookworm disease in humans?

- **Necator americanus**
- **Ancylostoma duodenale**

2. What is the hallmark of hookworm infection?

- Iron deficiency anemia due to chronic blood loss
- A single hookworm can suck 0.3 ml of blood per day, and often person is infected with multiple worms and is concurrently malnourished.
- Uses very muscular pharyngeal complex to pump blood



Image: Hookworm sucking blood

3. What is the distribution of A. duodenale and N. americanus?

- Big global health problem, infect 1 billion people
- Impacts health of mothers and children >>> malnutrition

A. A. duodenale

- Tropical and subtropical Asia and Africa
- Middle East
- North Africa
- Southern Europe

B. N. americanus

- Tropical and subtropical Asia and Africa





- New world – Appalachia, Alabama

4. **Describe the morphology of Hookworms**.
    - Adult hookworms are small, cylindrical/spindle-shaped creamy white nematodes
    - Bilaterally symmetrical, unsegmented, acellular outer body wall w/ underlying hypodermis containing longitudinal muscle for locomotion.
    - Cuticles of different kinds smooth, spiny or striated
    - No respiratory or circulatory systems, but do have primitive digestive system (mouth, buccal cavity, esophagus, rectum, anus) and nervous system
    - Body cavity not lined by epithelial cells >>> **pseudocoelom**
    - Males 5-11 mm long, females bigger 9-13 mm long
    - Identification is based on length, number and arrangement of teeth or cutting plates, length of esophagus, and morphology of genital primordial.
    - N. americanus has a head curved opposite to the curvature of the body, giving a hooked appearance to the anterior end. The buccal capsule has a pair of dorsal and ventral semilunar cutting plates.
    - A. duodenale has a head which continues in the same direction as the curvature of the body. The buccal capsule has 2 pairs of curved ventral teeth or nearly the same size.



Necator americanus: showing male copulatory bursa

5. **What is the life cycle of the hookworm?**
    - Most actually live freely in soil, rather than as parasites.
    - Females lay millions of eggs, but very few mature
    - Complicated life cycles with obligatory intermediate hosts
    - Life stage infective for people is **filariform larvae** negatively geotrophic and positively pheotropic
    - Like to enter and live in the feet, **groundage**
    - Vertical transmission through milk and orally may be possible


CDC
SAFER • HEALTHIER • PEOPLE™
http://www.dpd.cdc.gov/dpdx
④ Filariform larva penetrates skin
i
③ Filariform larva
② Rhabditiform larva hatches
⑤
Adults in small intestine
①
d Eggs in feces
i = Infective Stage
d = Diagnostic Stage

Eggs are passed in the stool ①, and under favorable conditions (moisture, warmth, shade), larvae hatch in 1-2 days in soil. The released **rhabditiform larvae** (250-300 micrometers in length with a bluntly rounded anterior end and a long, narrow buccal cavity) grow in the feces and/or the soil ②, and after 5 to 10 days (and two molts) they become **filariform larvae** (third stage) that are infective ③. These infective larvae can survive 3-4 weeks in favorable environmental conditions. On contact with the human host, the larvae penetrate the skin and are carried through the veins to the heart and then to the lungs. They penetrate into the pulmonary alveoli, ascend the bronchial tree to the pharynx, and are swallowed ④. The larvae go through stomach to the small intestine, where they reside and mature into adults. Adult worms live in the lumen of the upper half of the small intestine, where they attach to the intestinal wall with resultant blood loss by the host ⑤. Most adult worms are eliminated in 1 to 2 years, but longevity records can reach several years. Some *A. duodenale* larvae, following penetration of the host skin, can become dormant (in the intestine or muscle). In addition, infection by *A. duodenale* may also occur by the oral and transmammary route. *N. americanus*, however, requires a transpulmonary migration phase. (www.cdc.gov)


Hookworm egg

6. What are the clinical manifestations of infection with N. americanus or A. duodenale?

- Infections last 5-10 years, but no auto-infectious cycle (infection continuous even outside of endemic area)

7. How are hookworm infections treated?

- **Mebendazole**
- **Albendazole**
- Most important thing is education >>> teaching people to wear shoes, and not to use human feces in gardening
- There may be a vaccine available soon based on Ancylostoma secreted proteins (ASP-1, ASP-2)
- **Ancylostoma caninum** infection >>> eosinophilic gastroenteritis

9. What are the characteristics of Ascaris lumbricoides, and how is it diagnosed?

- 1 billion infections worldwide
- Distribution: worldwide in tropics w/ moist and shady soils
- Pollen in the stool is indicative of Ascaris infection
- Egg is both diagnostic and infective stage!
- Live for about 2 years





Left image: Ascaris lumbricoides adult worms. The male is smaller (120-250mm x 3-4mm) than the female (200-400mm x 5-6mm), and the male's posterior end is frequently coiled or recurved. Right image: Ascaris lumbricoides ovum: The 40-60µm eggs have a characteristic **mamilated outer** coat and thick **hyaline shell.**

10. What is the morphology of Ascaris?

- Cylindrical pink or cream-colored adult worm tapers at both ends.
- Male is smaller (120-250mm x 3-4mm) than female (200-400mm x 5-6mm)
- Male's posterior end is slightly coiled
- Female produces 200,000 eggs per day



Ascaris lumbricoides decorticate eggs, note: developing larvae

11. What is the life cycle of Ascaris lumbricoides?

- Needs warm, moist shaded soil to mature

- Infectious eggs are ingested and larvae hatch in jejunum >>> penetrate intestinal wall >>> migrate via hepatic venules to right heart and pulmonary circulation >>> break into alveolar spaces and undergo 2 additional molts. Most larvae will have reached the lungs by 2 weeks after ingestion of eggs >>> from alveoli, larvae ascend to trachea and are swallowed >>> undergo another molt in intestine >>> develop into adults. Incubation period after being swallowed by human is 2-3 months.
- Very hardy eggs, can survive months without oxygen, etc.


i = Infective Stage
d = Diagnostic Stage
① d
♀
♂
②
③
④
⑤
⑥
⑦
i
Feces
② Fertilized egg d
② Unfertilized egg will not undergo biological development. d
CDC
SAFER • HEALTHIER • PEOPLE™
http://www.dpd.cdc.gov/dpdx

Adult worms ①live in the lumen of the small intestine. A female may produce approximately 200,000 eggs per day, which are passed with the feces ②. Unfertilized eggs may be ingested but are not infective. Fertile eggs embryonate and become infective after 18 days to several weeks ③, depending on the environmental conditions (optimum: moist, warm, shaded soil). After infective eggs are swallowed ④, the larvae hatch ⑤, invade the intestinal mucosa, and are carried via the portal, then systemic circulation to the lungs ⑥. The larvae mature further in the lungs (10 to 14 days), penetrate the alveolar walls, ascend the bronchial tree to the throat, and are swallowed ⑦. Upon reaching the small intestine, they develop into adult worms ①. Between 2 and 3 months are required from ingestion of the infective eggs to oviposition by the adult female. Adult worms can live 1 to 2 years. (www.cdc.gov)

12. What is the clinical presentation of infection with Ascarcis?

- **Pulmonary hypersensitivity** that manifests as asthma
- Acute symptoms: usually in children
    1. urticaria
    2. bronchospasm
    3. pneumonia
- It can cause intestinal obstruction and abdominal pain, particularly in a child
- Typically asymptomatic in adults
- It can cause peritonitis, pancreatitis, inflammation in biliary tree
- **Loeffler's Syndrome:** prolonged eosinophilia and cardiomyopathy, often caused by crack cocaine use.

13. What are the complications of infection with Ascarcis?

- Abdominal pain
- Nausea, vomiting
- Intestinal obstruction (children) >>> rarely, leads to volvulus
- Peritonitis
- Biliary and pancreatic obstruction

14. How is an Ascarcis infection treated?

- **Albendazole**
- **Mebendazole**
- **Ivermectin**
- Reduce infections by education on sanitary waste disposal

15. What is the significance of Cutaneous Larva Migrans?



- Cutaneous Larva Migrans classic for **creeping eruption**
- Dermatitis caused by invasion of skin by larval nematodes: dog hookworm, typically **Ancylostoma Braziliensis**, found in sandy areas in the Caribbean, southeast US, and elsewhere. Also caused by **A. caninum.**
- Dermatitis caused by invasion of skin by larvae of dog and cat hookworm, but doesn't penetrate any deeper than epidermis
- Life cycle: A. braziliensis & A. caninum inhabit the intestines of dogs and cats >>> embryonated eggs are passed in stool >>> if right temp & humidity >>> hatch and release rhabditiform larvae in 1-2 days >>> after feeding, growing & molting >>> become infective filariform larvae (1 week) >>> larvae penetrate skin of humans no deeper than epidermis.
- Distribution: warm tropical or substropical regions, SE US
- Humans are aberrant host.
- More common in children, bare skin contact with soil is necessary for transmission
- Clinical manifestations: itching red papule w/ serpiginous track from worm >>> inflamed edematous tissue; not deadly, but very itchy >>> scratch becomes infected with bacteria
- Diagnosis: based on history and serpiginous track
- Treatment:
  1. **Albendazole**
  2. **Ivermectin**
  3. **Topical Thiabendazole**

15. What is Toxicariasis?



- Dogs and cats have their own ascaris known as toxocara canis and toxicara cati; Tocicariasis is infection with embryonated eggs of dog ascarid T. canis or less often cat ascaris, T. cati.
- People get infected with a worm, in which humans are not the definitive host, so they don't develop into adult in human, the worm remains in larval form and cause a spectrum of disease ranging from asymptomatic to VLM and OLM.
- **VLM (Visceral Larval Migrans)**
- **OLM (Oculolarval migrans**): eye can be involved
- Soil can be contaminated with toxocara canis eggs
- Cats, dogs, and PICA
- Eosinophilic granulomas

Image: Toxocara eggs (not seen in humans only in cats or dogs).

16. What is the life cycle of Toxocaris canis or cati?

- Adult T. canis & T. cati live in dog or cat intestines >>> eggs shed in stool >>> 2-3 weeks in warm, moist soil and appropriate temps
- Tranmission to humans occurs via ingestion of embryonated eggs directly from soil or from contaminated hands >>> eggs hatch and release larvae in proximal small intestine, where they penetrate the mucosa and are carried to the liver via portal circulation >>> some larve remain in liver forming granulomas >>> other go to lungs >>> larvae enter the circulation and are carried to various parts of the body until they reach a vessel too small for passage >>> penetrate into surrounding tissue.


CDC
SAFER • HEALTHIER • PEOPLE™
http://www.dpd.cdc.gov/dpdx
Circulation
Larvae migrate to various organs where their development is arrested
Larvae released in intestine
In pregnant and lactating dogs, the larvae can be reactivated and cause:
- intestinal infection in the mother
- infection of the offspring (by transplacental and transmammary transmission)
Dogs > 5weeks (non-pregnant)
Larvae released in intestine
Circulation –> Lungs –> Bronchial tree –> Esophagus
Human (and other paratenic hosts)
In heavy infections, larvae can be passed in feces
Adults in lumen of intestine
♀
♂
Dogs < 5 weeks
Eggs Ingested
Eggs passed in feces
External Environment
Embryonated egg with larva
Eggs
i = Infective Stage

Toxocara canis accomplishes its life cycle in dogs, with humans acquiring the infection as accidental hosts. Infective eggs are excreted by dogs. Humans are paratenic hosts who become infected by ingesting infective eggs in contaminated soil. After ingestion, the eggs yield larvae that penetrate the intestinal wall and are carried by the circulation to a wide variety of tissues (liver, heart, lungs, brain, muscle, eyes). While the larvae do not undergo any further development in these sites, they can cause severe local reactions that are the basis of toxocariasis.

17. Compare and contrast the clinical presentations of VLM with those of OLM.

A. VLM

- VLM is usually found in toddlers (ages 2-4) who eat soil
- Marked inflammatory immune response to numerous migrating larvae in liver and other tissues.
- Get febrile systemic illnesses manifested by fever and chills, fleeting infiltrates in chest, may have seizures, myocarditis, or hepatitis
- Very high levels of **eosinophils (30-50%), leukocytosis, fever, hepatomegaly, hypergammaglobulinemia, Isohemagglutinins** are elevated, ery high IgE
- + ELISA test, serology is only way to make definitive diagnosis, because human is not host, won't see eggs in stool.
- High dose may end up as VLM, low dose of eggs ingested more likely to have OLM.

B. OLM

- School-age children and adults
- Sitting in school has to strain eyes to see
- Ocular lesions, strabismus, retinal scar on opthalmoscopic exam
- Diagnosis: **+ ELISA test**
- Won't have eosinophilia, isohemagglutinins or systemic manifestations



Image: Toxocariasis in the eye causing chororetinitis or ocular larva migrans (OLM).

18. How do you treat VLM and OLM?

- Eliminate source of infection VLM
- Symptomatic treatment of VLM and OLM
- Surgery or laser therapy for OLM
- Antihelminthics:
    1. **Diethylcarbazamine**
    2. **Thiabendazole**
    3. **Albendazole**

19. What is Balyis ascaris?

- is an ascaris of raccoons.
- Raccoons either enter the house or kids play in yard and eat raccoon droppings, thereby ingesting the eggs >>> eggs hatch >>> infect kids >>> **neural larval migrans**
- Typically infects CNS
- there is no good treatment, so kids often die from this

20. What is Angiostrongylus?

- It is a cause of eosinophilic meningitis.
- People get infected by eating snails, crabs or prawns >>> larva comes out and enters the brain >>> eosinophilic meningitis.
- Humans are accidental hosts.
- No serology
- No therapy
- Diagnosis made by finding larvae in CSF, history of eating raw food, travel to endemic areas.

LECTURE #6: NEMATODES II

Intestinal Nematodes

- Oral-fecal: Enterobius vermicularis (pinworm), Trichuris trichuria (whipworm), no migration in the lung
- Oral-fecal with migration to lungs: Ascaris lumbricoides
- Soil-migration to lungs: N. americanis and A. duodenales (hookworm), and Strongyloides sterocoralis, patients can get them from walking barefoot
- All are treated with Albendazole

Infection with Enterobius vermicularis (Pinworm)

- Common worldwide: including temperate and colder climates, particularly noted in cooler climates b/c worms are more unusual in N. America, found in all socio-economic groups.
- Transmission: hand to mouth transmission; egg is excreted in fairly mature form and can be passed from person-to-person, rather than requiring incubation in warm, moist soil. Humans are only host.
- Distribution: most common helminthic infection in US and W. Europe. Greatest prevalence amongst school-aged children, high population density, indoor conditions.
- Pinworm season is typically in middle of winter, b/c kids are cuddling together or sleeping together more often

Pinworm Morphology

- Female 8-13 mm in length (can be seen with naked eye) much larger than male, female has pin tail, male does not
- So as physician look for eggs on perineal skin, rather than checking stool sample
- Pinworms have ala or ventral wings
- Round = nematode
- Eggs are flattened on one side and convex on other side, have thick albuminous layer that can get attached to dust, they mature and are infective within 6 hours, and remain infective for several days, infectious egg contains first stage larvae. Look like coffee bean.





Top image: Enterobius vermicularis (pinworm) adult male demonstrating cephalic alae. Lower images: Enterobius vermicularis (pinworm) eggs on scotch tape test. The eggs are elongate-ovoidal, compressed laterally, flattened on one side and measure 50-60 x 20-30µm.

Enterobius Vermicularis Life Cycle

- Eggs contain larvae that must go through further maturation before becoming infective, atmospheric oxygen acts as a stimulus to development.
- At body temp, eggs become infective within 6 hours, and lose infectivity 1-2 days under dry warm conditions. Survival better with low temp, humid conditions.
- Infestation follows ingestion of eggs, which usually reach mouth on soiled hands or contaminated food. After being ingested, eggs hatch in upper SI >>> liberating larvae which migrate to Ileum >>> molt twice along way to become adults >>> copulation occurs in lower SI >>> adult females settle in cecum, appendix, or adjacent areas of ascending colon.
- Adult females live up to 13 weeks and most patients have a few to 100s of worms.
- Gravid female 17,000 eggs >>> detaches from cecal mucosa >>> migrates down large bowel >>> passes out of anus to perineal skin >>> migration with trail of eggs on skin
- Egg goes into environment and takes 6-8 hours to embryonate, so eggs can be shed into bed sheets and then another child sleeps in that same bed can get infection by the next night

Life Cycle:


i Embryonated eggs ingested by human
2
CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx
3 Larvae hatch in small intestine
♀
♂
Adults in lumen of cecum 4
5 Gravid ♀ migrates to perianal region at night to lay eggs
1
d Eggs on perianal folds
Larvae inside the eggs mature within 4 to 6 hours.
i = Infective Stage
d = Diagnostic Stage

Eggs are deposited on perianal folds ❶. Self-infection occurs by transferring infective eggs to the mouth with hands that have scratched the perianal area ❷. Person-to-person transmission can also occur through handling of contaminated clothes or bed linens. Enterobiasis may also be acquired through surfaces in the environment that are contaminated with pinworm eggs (e.g., curtains, carpeting). Some small number of eggs may become airborne and inhaled. These would be swallowed and follow the same development as ingested eggs. Following ingestion of infective eggs, the larvae hatch in the small intestine ❸and the adults establish themselves in the colon ❹. The time interval from ingestion of infective eggs to oviposition by the adult females is about one month. The life span of the adults is about two months. Gravid females migrate nocturnally outside the anus and oviposit while crawling on the skin of the perianal area ❺. The larvae contained inside the eggs develop (the eggs become infective) in 4 to 6 hours under optimal conditions ❶. Retroinfection, or the migration of newly hatched larvae from the anal skin back into the rectum, may occur but the frequency with which this happens is unknown.

Clinical Presentation of Pinworm Infection

- Doesn't cause a lot of pathology b/c no attachment; instead, they glide on top of the colonic mucosa >>> doesn't cause eosinophilia (which helps fight parasites).
- Cause perineal eczematous dermatitis and pruritis particularly at night, b/c female migrates out of anus at night.
- Scratching contaminates fingers and can lead to autoinfection.
- Can see folliculitis in adults.
- Very rare complication: female migrates into vagina >>> causes **vaginal pruritis & UTIs** particularly in pubescent females.
- Often major psychological impact on parents
- No association with thumbsucking
- Close association with **Dientamoeba fragilis** which is a protozoa, possibly pinworm carries the protozoa with it.

- Appendicitis is common and pinworm is common in children, but no connection between the two.

Diagnosis of Enterobius Vermicularis

- Scotch tape affixed to pernieal region as soon as kids awaken (before they go to the bathroom).
- Look at tape under microscope and see eggs.

Treatment of Enterobius Vermicularis

- **Mebendazole:** same mechanism as Albendazole.
- **Albendazole:** is much better absorbed than Mebendazole, so you get higher levels with fewer doses. Mechanism of action is bind to tubulin – do not use in pregnant women!
- **Pyrantel Pamoate** – they don't use it here in clinic, M-oxyphenol derivative that functions as a depolarizing neuromuscular blocking agent >>> spastic paralysis of worms.
- Therapy should be repeated within 2 weeks.
- Other household members should be examined and treated.

Infection With Trichuris Trichuria (Whipworm)

- One of the most common helminthic infections (vying with ascaris) in the world – 900 million infections. Can be milder forms.
- Distribution: found worldwide, and in US in rural communities of southern US, similar distribution as Ascaris
- Eggs ingested hand-to-mouth
- Transmission: from raw fruits and vegetables, in places where people fertilize produce with human feces
- Eggs are passed in feces, they need to mature in soil for 10-14 days
- About 3 months required for patent infection in human after ingestion of eggs

Morphology of Trichuris Trichuria

- 3-5 cm adults
- Anterior 3/5 are threadlike, posterior 2/5 more substantial with reproductive organs.



Life Cycle of Trichuris Trichuria

- ingestion of embryonated egg
- larvae emerge in intestine >>> penetrate the **crypts of Lieberkuhn** and migrate within the mucosal epithelium.
- On molting to adult form >>> posterior end is projected out of epithelium leaving a threadlike anterior portion embedded in syncytium created from epithelial cells.
- Mature female produces 2000-6000 eggs per day >>> eggs are passed in feces >>> mature in soil for 10-14 days
- 3 months required for infection be produced from ingested eggs.
- Adult worms may persist for years.

Life Cycle:


④ Embryonated eggs are ingested.
i
③ Advanced cleavage
i = Infective Stage
d = Diagnostic Stage
⑤
Larvae hatch in small intestine
② 2-cell stage
d
① Unembryonated eggs passed in feces.
♀
♂
⑥ Adults in cecum
CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx

The unembryonated eggs are passed with the stool ①. In the soil, the eggs develop into a 2-cell stage ②, an advanced cleavage stage ③, and then they embryonate ④; eggs become infective in 15 to 30 days. After ingestion (soil-contaminated hands or food), the eggs hatch in the small intestine, and release larvae ⑤ that mature and establish themselves as adults in the colon ⑥. The adult worms (approximately 4 cm in length) live in the cecum and ascending colon. The adult worms are fixed in that location, with the anterior portions threaded into the mucosa. The females begin to oviposit 60 to 70 days after infection. Female worms in the cecum shed between 3,000 and 20,000 eggs per day. The life span of the adults is about 1 year.



Clinical Presentation of Trichuriasis

- Local eosinophilic infiltrate in mucosa in milder form
- In very heavy infections, people can get **chronic diarrhea**, **dysentery syndrome**, abdominal pain, **pro-lapsed rectum**, bowel wall edema and mucosa may bleed >>> anemia blood loss due to friable mucosa
- Highest worm burden found in young children: children can get chronic colitis with growth retardation and it may impair cognitive abilities (can interfere with kids' schooling). Children with PICA or short stature may have had whipworm.
- Worms don't ingest blood, but can get anemia from bleeding due to mucosal damage.
- Can see clubbing.

Diagnosis of Trichuriasis

- Take 3 stool samples from 3 different days and look for eggs under microscope.



Treatment of Trichuriasis

- Put the rectum back in place, does not require surgery
- **Albendazole**
- **Mebendazole**

Infection with Strongyloides Stercoralis

- Unique among helminthes due to **Autoinfection,** can maintain persistent infection for years.
- Can get active infection 60+ years after exposure >>> so when doing a history you should always ask about where person was born, any travel, and animal (particularly rodents in the house) exposure.
- World distribution: occurs in SSA, Asia, Carribean, Mexico, southern and southeastern US, South America, Puerto Rico (heavily endemic)
- Transmission: walking barefoot penetrates skin
- Immunosuppressed (steroids or infection with **HTLV-1**) can get hyperinfection syndrome with high morbidity.
- Symptoms: cough, wheezing, bronchospasm (due to migration of worm through lungs).
- **Loffler's Syndrome**
- Can get Duodenitis >>> **peptic ulcer-like symptoms**

Life Cycle of Strongyloides Stercoralis

- Get it from the fecally-contaminated soil when walking barefoot, penetrates unbroken skin, female filariform larvae (3rd stage) migrate through venous system to lungs >>> penetrate alveoli >>> trachea >>> glottis >>> swallowed >>> burrow into Small Intestine wall and releases eggs there >>> mature eggs are released into lumen of bowel >>> egg releases rhabditiform larvae which goes out into stool >>> molts >>> becomes filariform larvae (which has the ability to penetrate unbroken skin and bowel wall, and can then go through liver, to lungs, and molt and continue).
- Autoinfection possible, so you can live with this infection for years and years after leaving endemic area.
- Infective stage: filariform larvae.


i = Infective Stage
d = Diagnostic Stage
6 Infective filariform larvae penetrate the intact skin initiating the infection.
7 The filariform larvae enter the circulatory system, are transported to the lungs, and penetrate the alveolar spaces. They are carried to the trachea and pharynx, swallowed, and reach the small intestine where they become adults.
5 The rhabditiform larvae develop into infective filariform.
8 Adult female worm in the intestine.
4 Rhabditiform larvae hatch from embryonated eggs.
New generation of adults
Development into filariform larvae
AUTOINFECTION
10 Autoinfection: Rhabditiform larvae in large intestine, become filariform larvae, penetrate intestinal mucosa or perianal skin, and follow the normal infective cycle.
3 Eggs are produced by fertilized female worms.
9 Eggs deposited in intestinal mucosa, hatch, and migrate to lumen.
1 Rhabditiform larvae in the intestine are excreted in stool.
2 Development into free-living adult worms.
CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx

The *Strongyloides* life cycle is complex among helminths with its alternation between free-living and parasitic cycles, and its potential for autoinfection and multiplication within the host. Two types of cycles exist:

Free-living cycle: The rhabditiform larvae passed in the stool ①(see "Parasitic cycle" below) can either molt twice and become infective filariform larvae (direct development) ⑥or molt four times and become free living adult males and females ②that mate and produce eggs ③from which rhabditiform larvae hatch ④. The latter in turn can either develop ⑤ into a new generation of free-living adults (as represented in ②), or into infective filariform larvae ⑥. The filariform larvae penetrate the human host skin to initiate the parasitic cycle (see below) ⑥.

Parasitic cycle: Filariform larvae in contaminated soil penetrate the human skin ⑥, and are transported to the lungs where they penetrate the alveolar spaces; they are carried through the bronchial tree to the pharynx, are swallowed and then reach the small intestine ⑦. In the small intestine they molt twice and become adult female worms ⑧. The females live threaded in the epithelium of the small intestine and by parthenogenesis produce eggs ⑨, which yield rhabditiform larvae. The rhabditiform larvae can either be passed in the stool ①(see "Free-living cycle" above), or can cause autoinfection ⑩. In autoinfection, the rhabditiform larvae become infective filariform larvae, which can penetrate either the intestinal mucosa (internal autoinfection) or the skin of the perianal area (external autoinfection); in either case, the filariform larvae may follow the previously described route, being carried successively to the lungs, the bronchial tree, the pharynx, and the small intestine where they mature into adults; or they may disseminate widely in the body. To date, occurrence of autoinfection in humans with helminthic infections is recognized only in *Strongyloides stercoralis* and *Capillaria philippinensis* infections. In the case of *Strongyloides*, autoinfection may explain the possibility of persistent infections for many years in persons who have not been in an endemic area and of hyperinfections in immunodepressed individuals.

Clinical Presentation of Strongyloides Infection

- Skin penetration by filariform larvae >>> pruritic maculopapular eruption, or rapidly migrating linear urticaria called **larvae currens.** Creeping eruptions.
- Veterans 30-40 years later
- Abdominal symptoms: epigastric pain, watery diarrhea, abdominal pain when worms penetrate intestines
- Pulmonary symptoms: wheezing, cough, SOB if worms migrate through lungs
- **Loffler's Syndrome**

What is hyperinfection syndrome?

- Eosinophils are crucial for fighting this infection. If suppress eosinophils through **steroid** treatment (for lymphphoma) rhabdidiform larvae become filariform larvae >>> **hyper-infection syndrome**
- Loss of cellular immunity allows for conversion of rhabtidiform larvae to filariform larvae with widespread dissemination through entire body
- Fever
- Vomiting (due to edematous bowel)
- Diarrhea (due to edematous bowel)
- Pulmonary infiltrates: because lots of larvae maturing in lung
- Hypoxia
- Gram negative sepsis
- **Gram negative meningitis:** go into meninges and bring coliforms with them, if you see adult with Gram negative meningitis think of Strongyloides.
- Babies and patients with catheters in brain get gram negative infections in CSF
- **HTLV-1 infection:** retrovirus very common in Carribean, may be due to a cytokine issue and they are unable to make eosinophils.
- High mortality rate if untreated.

Diagnosis of Strongyloidiasis

- Rhabtidiform larvae in stool, obtain several stool samples.
- String test (outdated) / duodenal aspirate.
- **Serology – IgG4** to strongyloides, if see patient with slight eosinophilia get serology.
- Check sputum and stool for possible Hyper-infection.

Treatment of Strongyloidisis

- **Thiabendazole** – 95% cure rate
- Ivermectin – cidal

Which worms cause Loffler's Syndrome?

- **Ascaris**
- **Strongyloides**
- Pinworm – does not
- Whipworm – does not

LECTURE #7: NEMATODES III

1. **What organisms cause Filariasis?**
    - **Wucheria bancrofti**
    - **Brugia malayi**
    - **Loa loa**
    - **Onchocerca volvulus**
    - **Mansonella species**

1. **What is Dracunculosis?**
    - Dracunculosis (also called **Guinea Worm disease**) is a painful, incapacitating disease caused by **Dracunculosis medinensis.**
    - Transmission: by drinking water containing **cyclopoid copepods**, freshwater microcrustaceans that harbor infective larvae.
    - This nematode lives in connective and subcutaneous tissue of humans.
    - The female worm emerges through the skin to discharge its larvae into water.
    - The clinical course is characterized by allergic prodromal symptoms and cutaneous ulceration.
    - Most infections are limited to a single worm.

2. **What is the morphology of Dracunculus medinensis?**

- The adult female worm is creamy white, slender cord, and is one of the longest nematodes (up to 1 meter), and 2 cm wide.
- Adult males rarely seen because they don't live long after mating. Male is half size of female.

3. What is the life cycle of Dracunculus medinensis?



- After an incubation period of 10-14 months, female worm migrates to subQ tissue (usually in feet or legs) >>> painful blister >>> when immersed in water, blister bursts and female worm protrudes through skin >>> expelling 1000's of larvae into the water by contracting her uterus.
- Larvae are ingested by intermediate host, copepod (a Cyclops microcrustacean)
- Humans become definitive host when they drink water contaminated by Cyclops infected with 3^{rd} stage larvae >>> liberated larvae penetrate human intestinal tract wall >>> migrate into abdominal or thoracic cavity >>> develop into adults >>> mate after 3 months >>> female continues to mature until its body consists almost entirely of a coiled distended uterus containing millions of rhabditiform larvae >>> female begins extensive migration that ends at site of emergence.


Human drinks unfiltered water containing copepods with L3 larvae.
1
CDC
SAFER • HEALTHIER • PEOPLE™
http://www.dpd.cdc.gov/dpdx
Larvae are released when copepods die. Larvae penetrate the host's stomach and intestinal wall. They mature and reproduce.
♂
2
♀
3
Fertilized female worm migrates to surface of skin, causes a blister, and discharges larvae.
4
L1 larvae released into water from the emerging female worm.
Female worm begins to emerge from skin one year after infection.
d
5
L1 larvae consumed by a copepod.
Larvae undergoes two molts in the copepod and becomes a L3 larvae.
6
i
i = Infective Stage
d = Diagnostic Stage

Humans become infected by drinking unfiltered water containing copepods (small crustaceans) which are infected with larvae of *D. medinensis* ❶. Following ingestion, the copepods die and release the larvae, which penetrate the host stomach and intestinal wall and enter the abdominal cavity and retroperitoneal space ❷. After maturation into adults and copulation, the male worms die and the females (length: 70 to 120 cm) migrate in the subcutaneous tissues towards the skin surface ❸. Approximately one year after infection, the female worm induces a blister on the skin, generally on the distal lower extremity, which ruptures. When this lesion comes into contact with water, a contact that the patient seeks to relieve the local discomfort, the female worm emerges and releases larvae ❹. The larvae are ingested by a copepod ❺and after two weeks (and two molts) have developed into infective larvae ❻. Ingestion of the copepods closes the cycle ❶.

4. **What is the distribution of Dracunculus medinensis?**
    - Africa, Asia, Yemen and Saudi Arabia

5. **What are the clinical manifestations of Dracunculosis?**
    - In most patients, first sign is formation of a large, reddish paule 2-7 cm in diameter with a vesicular center and an indurated margin. This is where the cephalic end of worm is approaching skin.
    - Formation of blister is accompanied by intense pruritis and burning pain >>> patient immerses affected body part in water for relief.
    - After 3-5 days, the blister ruptures and discloses small superficial ulcer - at its center is a hole with worm's head.
    - In response to contact with fresh water, a loop of uterus prolapses through the hole and releases larvae into water.
    - The principal complication is **secondary bacterial infection** – this is serious and can cause **tetanus** or **cellulitis.**
    - If in joins >>> **guinea worm arthritis.**

6. **How is a diagnosis of Dracunculosis made?**
    - Once blister has broken, diagnosis can be made by placing cold water on the ulcer or **ethyl chloride** near it >>> this results in release of larvae which can be viewed under microscope.

7. **How is Dracunculosis treated?**
    - Winding each emerging worm onto a small stick of a few centimeters each day is useful as long as it is begun when the worm first emerges.
    - Surgical removal of worm.
    - Treat with **Benzimidazoles:**
        - **Metronidazole**
        - **Niradazole**
        - **Thiabendazole**
        - **Mebendazole**

8. **What is Loiasis?**
    - Loiasis is caused by infection with the **filarial ("thread-like")" nematode Loa loa.**
    - The adult worms migrate through the subQ tissue causing intermittent **"calaber swellings"** and sometimes beneath the conjunctiva (**eye worm).**
    - **Microfilariae** are found in the peripheral blood during the day.
    - Distribution: endemic to rain forests of Central and West Africa; in some parts 100% infection rates.
    - Transmission: flies of genus **Chrysops** or **Deer Fly**, which bites in shaded areas during the day.
    - L3 larvae are infective form.

9. **What is the morphology of Loa loa?**
    - The larger, female organisms are 60 mm by 500 micrometers; males are 35mm by 300 micrometers in size.
    - The circulating microfilaria are 300 x 7 micrometers; the infective larvae in the fly are 200 x 30 micrometers.

10. **What is the life cycle of Loa loa?**
    - The life cycle of *Loa loa* is identical to that of Onchocerca except that the vector for this worm is the **deer fly.**
    - Day biting flies of the genus **Chrysops** pick up the **microfilariae** of Loa loa in their blood meals.
    - The ingested microfilariae molt twice in the fly >>> develop into **infective L3 filariform larvae** >>> when flies bite new host, larvae infect new host and develop into adult worms.
    - Adult worms are thin and transparent and migrate through subQ tissue.
    - Microfilariae are released into host bloodstream where they are most plentiful between the hours of 10am-2pm.
    - It is the presence of a sheath and 3+ terminal nuclei that distinguish the microfilariae of Loa loa from **W. bancrofti** and **Mansonella perstans.**


Loa loa
Fly Stages
Human Stages
1 Fly (genus Chrysops) takes a blood meal
(L3 larvae enter bite wound)
♂
♀
2 Adults in subcutaneous tissue
3 Adults produce sheathed microfilariae that are found in spinal fluid, urine, sputum, peripheral blood and in the lungs
d
4 Fly takes a blood meal
(ingests microfilariae)
5 Microfilariae shed sheaths, pentrate fly's midgut, and migrate to thoracic muscles
6 L1 larvae
7 L3 larvae
8 Migrate to head and fly'sproboscis
i
i = Infective Stage
d = Diagnostic Stage
CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx

The vector for *Loa loa* filariasis are flies from two species of the genus *Chrysops*, *C. silacea* and *C. dimidiata*. During a blood meal, an infected fly (genus *Chrysops*, day-biting flies) introduces third-stage filarial larvae onto the skin of the human host, where they penetrate into the bite wound ❶. The larvae develop into adults that commonly reside in subcutaneous tissue ❷. The female worms measure 40 to 70 mm in length and 0.5 mm in diameter, while the males measure 30 to 34 mm in length and 0.35 to 0.43 mm in diameter. Adults produce microfilariae measuring 250 to 300 µm by 6 to 8 µm, which are sheathed and have diurnal periodicity. Microfilariae have been recovered from spinal fluids, urine, and sputum. During the day they are found in peripheral blood, but during the noncirculation phase, they are found in the lungs ❸. The fly ingests microfilariae during a blood meal ❹. After ingestion, the microfilariae lose their sheaths and migrate from the fly's midgut through the hemocoel to the thoracic muscles of the arthropod ❺. There the microfilariae develop into first-stage larvae ❻ and subsequently into third-stage infective larvae ❼. The third-stage infective larvae migrate to the fly's proboscis ❽and can infect another human when the fly takes a blood meal ❶. (www.cdc.gov)

11. What are the clinical manifestations of Loiasis?

- With the exception of eye involvement, clinical signs and symptoms are more common in visitors to Loa endemic areas, b/c they have a heightened immune response (natives do not).
- Recurrent episodes of localized angioedema or **caliber swellings** (may not be seen in people in endemic areas due to lack of immune response).
- Subconjuctival migration of eyeworm >>> transient swelling of lid and intense conjunctivitis.
- Mostly resolves spontaneously, but rare cases of retinal artery occlusion and macular retinopathy, due to aberrant migration of adult parasite
- Serious complications: **meningoencephalitis** in patients with high circulating microfilariae. CNS involvement ranges from mild headache and meningisimus to coma and death.
- Renal involvement common: **hematuria** and **proteinuria** are commonly seen in loiasis and may be due to immune complex glomerulonephritis or mechanical trauma resulting from filtration of large numbers of microcilariae.
- High **eosinophilia**

12. How is Loiasis diagnosed?

- Demonstration of **sheathed microfilariae** (still have portion of egg around them) with nuclei extending to the tip of the tail or idenitification of adult worm removed from subQ tissue is diagnostic.
- Serology is available (unlike other filarial diseases).

13. How is Loiasis treated?

- **Diethylcarbamazine (DEC)** – will kill larvae and adults and is usually curative, but may require multiple courses.
- A serious complication of treatment with DEC is **meningoencephaliti**s, particularly in patients with high circulating microfilariae. Dying worms migrate and cause serious allergic reactions. In order to avoid this, treat preemptively with **steroids.**
- Ivermectin and Albendazole may be effective

14. What is Onchocerciasis?

- **Onchocerciasis** is known as **River Blindness,** and is an infection of humans caused by the filarial nematode **Onchocerca volvulus.**
- The parasite is transmitted by **black flies** of genus **Simulium.**
- Infection may be asymptomatic, but heavy infections are associated with disease affecting skin and eyes, and in severe cases can lead to disfigurement of skin and visual impairment or even blindness.
- Distribution: 37 countries in central Africa and northern South America, and Arabian peninsula; particularly Congo, Sierra Leone, Venezeula & Guatemala.
- World's second leading cause of blindness.
- Larvae are infective form.

15. What is the morphology of Onchocerca volvulus?

- Adult female onchocerca measure 50 cm by 300 micrometers, they are long and thin, and become encapsulated in subQ nodules (onchocercomas).
- Male worms are much smaller.
- Infective larvae of *O. volvulus* are 500 micrometers by 25 micrometers (figure 21).



Onchocerca volvulus microfilaria in subcutaneous tissue. The microfilaria are unsheathed in the tissues and depending on how they are prepared for measurement are 315-360µm long by 6µm. The anterior and posterior ends are nuclei-free.

16. What is the life cycle of Onchocerca volvulus?

- The life cycle of *O. volvulus* is identical to that of Loa loa except that the vector for this worm is the **black fly**, rather than the deer fly.
- Infection transmitted by black flies (genus Simulim), which inoculate infective larvae into host.
- The infective larvae undergo 2+ molts over the next year >>> develop into adults.
- Female worms become encapsulated in subQ nodules called **onchocercomas** and are fertilized by males. They can remaine there for up to 20 years. Location of nodules on body may depend on region in which you were infected.

- Gravid females produce 1000’s of tissue invasive microfilariae each day >>> invade subQ tissues, skin and eyes.


Onchocerca volvulus
Blackfly Stages
Human Stages
1 Blackfly (genus Simulium) takes a blood meal (L3 larvae enter bite wound)
2 Subcutaneous tissues
3 Adults in subcutaneous nodule
4 Adults produce unsheathed microfilariae that typically are found in skin and in lymphatics of connective tissues, but also occasionally in peripheral blood, urine, and sputum.
5 Blackfly takes a blood meal (ingests microfilariae)
6 Microfilariae pentrate blackfly's midgut and migrate to thoracic muscles
7 L1 larvae
8 L3 larvae
9 Migrate to head and blackfly's proboscis
♂
♀
i
d
i = Infective Stage
d = Diagnostic Stage
CDC
SAFER · HEALTHIER · PEOPLE™
http://www.dpd.cdc.gov/dpdx

During a blood meal, an infected blackfly (genus *Simulium*) introduces third-stage filarial larvae onto the skin of the human host, where they penetrate into the bite wound ❶. In subcutaneous tissues the larvae ❷develop into adult filariae, which commonly reside in nodules in subcutaneous connective tissues ❸. Adults can live in the nodules for approximately 15 years. Some nodules may contain numerous male and female worms. Females measure 33 to 50 cm in length and 270 to 400 µm in diameter, while males measure 19 to 42 mm by 130 to 210 µm. In the subcutaneous nodules, the female worms are capable of producing microfilariae for approximately 9 years. The microfilariae, measuring 220 to 360 µm by 5 to 9 µm and unsheathed, have a life span that may reach 2 years. They are occasionally found in peripheral blood, urine, and sputum but are typically found in the skin and in the lymphatics of connective tissues ❹. A blackfly ingests the microfilariae during a blood meal ❺. After ingestion, the microfilariae migrate from the blackfly's midgut through the hemocoel to the thoracic muscles ❻. There the microfilariae develop into first-stage larvae ❼and subsequently into third-stage infective larvae ❽. The third-stage infective larvae migrate to the blackfly's proboscis ❾and can infect another human when the fly takes a blood meal ❶.

17. What are the clinical manifestations of Onchocerciasis?

- Earliest manifestation is itching >>> **dermatitis** with flattened papules. Can be so severe that patients commit suicide!
- Painless, moveable nodules due to **onchocercomas**
- Atrophy is relatively common in areas of high endemnicity >>> atrophic skin looks like aged skin with wrinkling, loss of electicity, loss of hair.
    1. loss of elasticity can cause **“hanging groin”** that looks like hernia
- Depigmentation can occur >>> **“leopard skin”**
- Nodules where the female resides may be palpable over bony prominences.
- **Vision impairment,** especially in males >20; possible complications with blindness as potential sequelue:
    1. eye involvement



2. punctuate keratitis
3. anterior uveitis
4. Chorioretinal disease
5. Optic neuritis

Look for high **IgE** levels in all Filarial infections.

18. **How is Onchocerciasis diagnosed?**
    - **Skin snip** commonly used for diagnosis >>> biopsy is placed in saline and observed for emergence of microfilariae.
    - Can also be done by surgical removal of subQ nodules or aspiration of nodules.
    - A slit lamp can be used to examine eyes and demonstrate intraocular microfilariae.
    - **Serology** via PCR is possible if skin snip is negative.
    - **Mazotti Test:** give patient DEC >>> mobilizes worms >>> leads to itching >>> diagnostic of disease.



Section of onchocerca nodule.

19. **How is Onchocerciasis treated?**
    - **Ivermectin** (similar to **Strongyloides)**

20. **What is Bancroftian Filariasis?**
    - Bancroftian filariasis is caused by mosquito-borne nematode **Wuchereria bancrofti & Brugia Malayi.**
    - Adult worms live in lymphatic vessels and nodes of humans. Females produce first stage larvae called microfilariae there >>> they then circulate in blood.
    - Lymphatic drainage is caused by local damage by the highly motile adult worms.
    - With progressive infection, inflammatory immune damage to lymphatics results in a wide spectrum of clinical manifestations that depend on part affected.
    - Humans are the only natural host for Wuchereria bancrofti.
    - Adults can remain in humans for many years.



21. **What is the morphology of Wuchereria bancrofti?**
    - Adult female *W. bancrofti* found in lymph nodes and lymphatic channels are 10 cm x 250 micrometers whereas males are only half that size.
    - Microfilaria found in blood are only 260 micrometers x 10 micrometers.

22. **What is the life cycle of W. bancrofti?**
    - An infected mosquito feeds on host (at night) and infective larvae enter host's skin.
    - The larvae develop into adults within lymphatic channels.
    - Microfilariae have **nocturnal variation:** they migrate to lungs during the day b/c of higher PO2, then at night they migrate to the bloodstream b/c PO2 highest there at night. If patient works at night, cycle will be reversed.

- Mosquitos ingest microfilariae from host’s blood.


Wuchereria bancrofti
Mosquito Stages
Human Stages
1 Mosquito takes a blood meal (L3 larvae enter skin)
2 Adults in lymphatics
♂
♀
3 Adults produce sheathed microfilariae that migrate into lymph and blood channels d
4 Mosquito takes a blood meal (ingests microfilariae)
5 Microfilariae shed sheaths, pentrate mosquito's midgut, and migrate to thoracic muscles
6 L1 larvae
7 L3 larvae
8 Migrate to head and mosquito's proboscis
i
i = Infective Stage
d = Diagnostic Stage
CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx

Different species of the following genera of mosquitoes are vectors of *W. bancrofti* filariasis depending on geographical distribution. Among them are: *Culex* (*C. annulirostris*, *C. bitaeniorhynchus*, *C. quinquefasciatus*, and *C. pipiens*); *Anopheles* (*A. arabinensis*, *A. bancroftii*, *A. farauti*, *A. funestus*, *A. gambiae*, *A. koliensis*, *A. melas*, *A. merus*, *A. punctulatus* and *A. wellcomei*); *Aedes* (*A. aegypti*, *A. aquasalis*, *A. bellator*, *A. cooki*, *A. darlingi*, *A. kochi*, *A. polynesiensis*, *A. pseudoscutellaris*, *A. rotumae*, *A. scapularis*, and *A. vigilax*); *Mansonia* (*M. pseudotitillans*, *M. uniformis*); *Coquillettidia* (*C. juxtamansonia*). During a blood meal, an infected mosquito introduces third-stage filarial larvae onto the skin of the human host, where they penetrate into the bite wound ❶. They develop in adults that commonly reside in the lymphatics ❷. The female worms measure 80 to 100 mm in length and 0.24 to 0.30 mm in diameter, while the males measure about 40 mm by .1 mm. Adults produce microfilariae measuring 244 to 296 μm by 7.5 to 10 μm, which are sheathed and have nocturnal periodicity, except the South Pacific microfilariae which have the absence of marked periodicity. The microfilariae migrate into lymph and blood channels moving actively through lymph and blood ❸. A mosquito ingests the microfilariae during a blood meal ❹. After ingestion, the microfilariae lose their sheaths and some of them work their way through the wall of the proventriculus and cardiac portion of the mosquito's midgut and reach the thoracic muscles ❺. There the microfilariae develop into first-stage larvae ❻and subsequently into third-stage infective larvae ❼. The third-stage infective larvae migrate through the hemocoel to the mosquito's prosbocis ❽and can infect another human when the mosquito takes a blood meal ❶.

23. What are the clinical manifestations of Bancroftian Filariasis?

- Signs and symptoms of Bancroftian filariasis vary widely form one endemic area to another. Differences may be due to relative intensities of different vectors in different regions.
- Asymptomatic individuals are seen in endemic areas.
- Early on in disease, patients will experience acute attacks of retrograde lymphangitis, accompanied by fever, chills, and malaise lasting 3-15 days. Can occur several times per year.
- Patients give history of: pain, erythema, tenderness in area of affected lymphnodes for hours or 1 day prior to onset of lymphangitis.
- **Acute filariasis:** microfilariae in blood, eosinophilia, and increased IgE. Some individuals may only have a few attacks in a lifetime. Months to years of acute episodes ranging from very mild to severe are followed by development of chronic obstructive disease due to lymphatic insufficiency.
- **Chronic filariasis**: recurrent episodes of lymphedema of the extremeties will progress to elephantiasis **(Focal Point of O'Connor:** point of lymphagenic spread in scrotum). The lower extremities are more commonly affected. In many areas, most common chronic manifestation is a **hydrocele**. As a result of blockage of draining lymph, straw colored hydrocele fluid accumulates (sometimes in huge volumes). Can have edema in any region containing lymphatics.
    1. **Elephantiasis**
    2. NO IgE & NO Eosinophilia
    3. **Chyluria:** lymphatic varices in bladder burst >>> lymphatic fluid in bladder & urine.

Tropical Pulmonary Eosinophilia: is an allergic reaction to microfilaria (Wuchereria bancrofti) which occurs particularly in the Asian subcontinent (also Eastern Europe?). Presentation is with **cough & asthma,** fever, lassitude, and weight loss. Chest X-ray shows bilateral hazy mottling that is equally distributed throughout both lung fields. This condition is commonly accompanied by false positive serological tests for syphilis. There are high titres of cold agglutinins. Treat w/ DEC.

24. How is Bancroftian Filariasis diagnosed?

- The presence of microfilariae on blood smear.
- Serology is available.

25. How is Bancroftian Filariasis treated?

- **DEC**
- Albendazole and Ivermectin are being studied for this use.



Image: Lymph node containing adult Wuchereria.

LECTURE #8: TRICHINOSIS & AMEBIASIS

Trichinosis

- Trichinosis caused by **Trichinella** and is acquired by eating muscles of wild or domestic animals.
- Severity is related to number of larvae ingested, and characterized by:
    1. fever
    2. GI symptoms
    3. myositis
    4. swollen eyelids
    5. **Eosinophilia -** very high
- Transmission: through eating pork, bear, or horse meat
- Number of infections is declining. General drop in reported cases, but probably milder so more cases than reported.
- **Zoonosis:** swine, rats
- Distribution: Occurs all over the US and the world.



Life Cycle of Trichinella Spiralis

- Eat undercooked pork, bear, cougar, horse, walrus meat >>> cysts (resistant to stomach pH) exit muscle mass of meat >>> migrate to person's small intestine >>> burrow in tissue above lamina propria and undergo 4 molts in

36 hours >>> mature into adult males and females >>> copulation occurs >>> female gives birth to newborn larvae within 4-7 days (**viviparous event**: female gives birth to live larvae, no eggs) >>> larvae travel through bloodstream and lymphatics >>> go to person's muscle masses (can pass through any striated muscle, but do not encyst in cardiac muscle, only striated muscle) form **nurse cell** >>> then they coil around day 17 >>> encyst 2-3 weeks post-infection and within 6 months -1 year calcify >>> if you eat that calcified cyst you get sick.


Larvae are ingested in raw or undercooked meats
Normal (red) and calcified Nurse cell-larvae complexes
Larvae are released from Nurse cells in stomach
Nurse cell-larva complex formed
Larvae enter small intestine
Adults mature and live in small intestine
Larva matures in muscle
Newborn larvae are carried throughout bloodstream
Newborn larva enters skeletal muscle cell
PATHOLOGY
Female sheds newborn larvae that enter lymph or blood
Heart failure
CNS damage

"Parasitic Diseases" 4th Ed. © Apple Trees Productions, LLC., Pub. P.O. Box 280, New York, NY 10032

- Any muscle mass can get involved: masseters, exta-ocular, nuccal, intercostals, gluteus, biceps, triceps, lower extremities
- Larvae can go through CNS and myocardium, but won't encyst there
- **Nurse cell larva complex**
- **Trichinella pseudospiralis:** does not form cysts

Clinical Presentation of Trichinosis

- Common clinical findings:
    1. **enteral stage:** nausea, vomiting, diarrhea – looks like food poisoning

2. **parental stage:** weakness, myalgia, fever, periorbital edema, conjunctivitis and conjuctival hemorrhages, hemorrhages in nail beds

- uncommon complications:
    1. **myocarditis:** don't encyst there, but do pass through the heart and can rarely cause arrhythmias, EKG changes, and death
    2. **vasculitis**
    3. **meningoencephalitis**
- Even after calcification can still cause disease





Images: splinter hemorrhages and periorbital swelling seen with Trichonosis.

Laboratory Findings

- High eosinphilia (40-60% typically)
- Leukocytosis
- Elevated muscle enzymes (CPK, Aldolase, SGOT)
- Elevated IgE
- Positive serology: shows up 2-3 weeks later



Degenerating T. spiralis in muscle with calcium deposition.

Treatment

- **Mebendazole**
- **Albendazole**
- **Corticosteroids** for severe disease: if neuro or myocarditis, problem is that people think you might be interfering with natural immunological response of the host, but this is only a theoretical problem

Prevention

- Cook meat to 160 degrees F is best
- Banning of feeding garbage including animal carcasses to swine and other barnyard animals.

Amebiasis

- **Amebiasis:** Should always be in your differential diagnosis, seen frequently in the US (4%), also very common in Mexico
- Worldwide distribution, due to unclean water and poor sanitation, 10% of world infected, and up to 50% in some developing countries.
- Causes a fair amount of mortality

Entamoeba Dispar vs. E. Histolytica

- Entamoeba Dipsar is morphologically identical to Entamoeba histolytica, but completely different effects on human infection.
- E. Dispar is more common and solely asymptomatic carrier state, whereas pathogenic species E. histolytica can invade tissue and cause symptomatic disease.
- **Galactose-inhibitable adherence lectin** is absent on **Entamoeba dispar** (asymptomatic) so can't invade the host, **Entamoeba histolytica** (symptomatic) can invade and cause symptoms and mortality.
    1. important adhesion antigen
    2. highly conserved
    3. monoclonal probes differentiate the two, otherwise, morphologically indistinguishable
- First suggested in studies with **zymodemes** through electrophoresis
- Transmission: oral-fecal
- Allergies, malignancies, rheumatic diseases and parasites >>> high level of eosinophilia





Left image: Entamoeba histolytica trophozoite, note: fine uniform granules of peripheral chromatin and small central karyosome in nucleus, size over 12 uM. Right image: Entamoeba histolytica trophozoite (8-30µm), note: ingested red blood cells.

High Risk Areas

- Mexico, Columbia, Ecuador, Chile, Peru
- West Africa
- South Africa
- Middle East
- South and southeast Asia
- In part, based on poorer sanitation and nutrition.
- Lows socioeconomic status, crowding, poor nutrition, poor sanitation/plumbing, institutionalized populated (mentally ill, or elderly), communal living, sexual behavior

Life Cycle

- E. histolytica is an enteric protozoa that exists as either trophozoite or cyst.
- Infection acquired from ingestion of cysts (quadranucleate and resistive to low stomach pH) from environment >>> excysts in intestine >>> forms 8 trophozoites >>> invade large intestine feeds on bacteria and cellular debris.
- Trophozoites may then encyst
- Upon excretion, cysts remain viable for weeks to months depending on environmental conditions.
- Cyst infectious, trophozoite invades


CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx
②
Mature cysts ingested
i d
C d
B d
A d
= Infective Stage
= Diagnostic Stage
A = Noninvasive Colonization
B = Intestinal Disease
C = Extraintestinal Disease
i d
①
Cysts and tophozoites passed in feces
d
④ Trophozoites d
Multiplication
Exits host
Excystation
③
Trophozoites
④ d
⑤ Cysts
d
d
d
d

Cysts and trophozoites are passed in feces ①. Cysts are typically found in formed stool, whereas trophozoites are typically found in diarrheal stool. Infection by *Entamoeba histolytica* occurs by ingestion of mature cysts ② in fecally contaminated food, water, or hands. Excystation ③ occurs in the small intestine and trophozoites ④ are released, which migrate to the large intestine. The trophozoites multiply by binary fission and produce cysts ⑤, and both stages are passed in the feces ①. Because of the protection conferred by their walls, the cysts can survive days to weeks in the external environment and are responsible for transmission. Trophozoites passed in the stool are rapidly destroyed once outside the body, and if ingested would not survive exposure to the gastric environment. In many cases, the trophozoites remain confined to the intestinal lumen (A: noninvasive infection) of individuals who are asymptomatic carriers, passing cysts in their stool. In some patients the trophozoites invade the intestinal mucosa (B: intestinal disease), or, through the bloodstream, extraintestinal sites such as the liver, brain, and lungs (C: extraintestinal disease), with resultant pathologic manifestations. It has been established that the invasive and noninvasive forms represent two separate species, respectively *E. histolytica* and *E. dispar*. These two species are morphologically indistinguishable unless *E. histolytica* is observed with ingested red blood cells (erythrophagocystosis). Transmission can also occur through exposure to fecal matter during sexual contact (in which case not only cysts, but also trophozoites could prove infective).

Cysts

- Never see cysts in tissue, only trophozoites
- Very hardy
- Killed by boiling over 100 degrees Celsius, lives in ice
- Resistant to chlorine

- Survives for days on salads, cheeses and yogurt (20-25 degrees)
- In the stool, you see round cysts with peripheral chromatin with thick hyaline cell wall that looks like a halo (not able to differentiate from ED).
- Stacking of ribosomal RNA used as an apparatus for cell division



Entamoeba histolytica cyst demonstrating chromatidal bars and 4 nuclei.

Trophozooite

- Pathogenesis: lysis
- Non-inflammatory disease
- Amoeboid trophozoite nucleus with peripheral chromatin
- Can invade, and on contact can lyse host tissue or cause host apoptosis, can ingest debris in intestine and RBCs and WBCs due to lectin (wouldn't see RBCs in E. dispar).
- Unidirectional motion of trophozoite

Mortality and Amebiasis

- High mortality in pregnant women, children <1 year, malnourished, and patients on corticosteroids.
- Can be mistaken for IBD >> treated with corticosteroids >>> potential development of **Toxic Megacolon** requiring colectomy.

Pathogenesis of Amebiasis

- Initial lesion is cecal and then extends down to rectum.
- Can get extra-intestinal disease
    1. hepatic: pretty common
    2. pleuropulmonary
    3. pericarditis
    4. cerebral
    5. other
- adherence of trophozoites to the mucus lining of large bowel – vital role in pathogenesis
- adhere to colonic mucins, epithelial cells and leukocytes >>> **Galactose-inhibitable adherence lectin** has difficulty adhering but easier if malnourished have thinner layer of protective mucin.
- Bantu tribe lives primarily on corn, poor nutritional status >>> higher infection rates
- If in bowel can get into blood vessels and then disseminate into portal blood vessels and travel to liver
- Contact-dependent cytolysis: EM of cells pre and post infection of EH. After, see autolysis >>> release of enzymes >>> causing destruction of local tissue. So organism invades by causing host cells to autolyse >>> then organism can move easily through dead tissue.
- Phagocytoizes PMNS and other cells >>> release of lysosomal agents >>> more necrosis
- Foci of necrosis coalesce to form classic **flask-shaped amebic ulcers.**
- Deeper tissue invasion >>> vasculitis and thrombosis >>> transmural disease and tissue death
- Virulence: depends both on amoeba and host factors (someone who is healthy and gets low dose of pathogen less likely to develop disease). Nutritional status very important: immunocompromised, corticosteroids, malignancies, and malnutrition predispose to infection.



Entamoeba histolytica infection of rectum, note: ulcerative lesion, usually described as flask shaped ulcer.

Intestinal Disease

- Asymptomatic: majority pass cysts in stool with no symptoms, but cysts are infectious so it is a public health issue. Carries a low, but definite possibility of invasion.
- **Mucosal Disease:**
  1. **acute rectocolitis (dysentery):** bloody diarrhea and tenesmus
  2. **chronic non-dysenteric colitis:** person has diarrhea for months on and off, can look like inflammatory bowel disease (AI disease of colon presents with bloody diarrhea that lasts for months)
- **Transmural Disease:**
  1. **fulminant colitis** with perforation due to coalescence of ulcers >>> high M&M
  2. **Toxic Megacolon:** much more common in children, very bad complication due to transmural disease and thinning of the bowel >>> huge cecum (may require a **cecostomy** otherwise will burst and life-threatening illness).
- **Ulcerative post-dysenteric colitis**

Amoebic Colitis

- Does not have rapid onset like Salmonella and Shigella (normally associated with high fever).
- Gradual onset of 1-3 weeks, weight loss common due to gradual onset
- Abdominal pain and tenderness
- Bloody stools and tenesmus
- Fever 1/3 patients
- Path: **flask-shaped ulcers** with necrotic debris in the middle, on the edge trophozoites
- Differential diagnosis:
  1. Infectious: amebiasis, Shigella, Salmonella, Campylobacter, Enteroinvasive and Enterohemorrhagic E. coli
  2. Non-infectious: ischemic colitis, AV malformation, Diverticulitis, inflammatory bowel disease
- Treatment for IBD is steroids. Must consider amoebic colitis, b/c if patient has that and you misdiagnose and give steroids you will make patient sicker.
- **Amoebic serology** directed at 170 kD lectin will become positive with 1-2 weeks of infection, quite specific, but can remain positive for up to 10 years.
- Complications:
  1. **appendicitis**
  2. **perforation & peritonitis**
  3. **ameboma:** pain and tenderness, can present as an **apple-core lesion** on CT, usually secondary to malignancy
  4. **amebic stricture:** fibrosis secondary to healing transmural disease
  5. **cutaneous amebiasis**

Treatment

- Tissue-cidal: **Flagyl=Metronidazole** (not good for cysts, but good for invasive disease)

- Luminicidal: **Iodoquinol, Paromomycin, Diloxanide Furoate (**in other countries), good for asymptomatic cyst characteristics

Differential Diagnosis for Bloody Diarrhea

- Amoebiasis
- Shigallosis
- Campelobacter jejuni
- E. coli (Enteroinvasive, Enterohemorrhagic)
- Clostridium difficile
- Testing: stool for O&P, Assay for toxin of C. difficile, and
- Treat: with Flagyl, follow up with Luminicidal agent

Conclusion

- Dispar never invasive >>> don't need to treat
- Cyst doesn't invade (it is infective stage); trophozoite is invasive stage
- Amoebiasis: ring enhancing lesion in brain, space-occupying cystic lesions can develop in brain, lung, or liver.

Hepatic Amebiasis

- Hepatic infection results from trophozoites ascending portal venous system.
- Predilection for right lobe, usually singular, but can be multiple. Trophozoites cause cells to self destruct >>> get a lot of necrotic debris. Also, lysis of PMNs >>> release of destructive host enzymes. Only see Trophs in edge of lesion. This is called a "**liver abscess**," but misnomer (no pus, not an abscess). If grows can get elevation of hemidiaphragm. Can rupture into lung or peritoneum. If on right can rupture into heart.
- If you put a needle into an amoebic abscess, you see **Anchovy paste** or **chocolate-like paste,** vs. regular abscess see sheets of PMNs.
- Males are 10x more likely to get invasive Amebiasis than females.
- Patient presentation: RUQ tenderness and fever. Patients look really ill and toxic. (In amoebic colitis many don't have fever). On chest x-ray see elevated right hemi-diaphragm >>> something is going on in right sub-phrenic space. Typically seen in patients who have traveled to endemic location. Normally, not acute onset (4 weeks). A history of diarrhea is only present in 1/3 of patients, vs. amebic colitis where patients have bloody diarrhea. Cough present in 1/3 of patients.
- See + amebic serology, but can remain + for up to 10 years.
- Path: collapse of stroma of liver, with necrotic debris. See invasive trophozoites on edge of lesion.

Differential Diagnosis of Space Occupying Lesion & Fever

- Differential diagnosis of space occupying lesion and fever >>> bacterial abscess (older patient 50+), diabetics, underlying disease such as cancer or biliary disease, men=females), Hepatic Amebiasis (travel, younger patient, men>females), tumors (usually lower grade fever), Echinococcus (dog tapeworm) morphology looks different, or Fasciola Hepatica.
- Put a needle into abscess if think its pyogenic abscess, or if a liver abscess is >5cm or it looks as if it's going to perforate.
- Treatment: **Flagyl** + luminicidal agent such as **Iodquinol**

Lab Tests

- Leukocytosis (12,000-20,000 mm^3)
- ESR is elevated (non-specific marker of inflammation)
- Normocytic-normochromic anemia
- Alkaline phosphatase elevated
- Partial immunity develops

LECTURE #9: DIENTAMOEBIASIS, GIARDIASIS & TRICHOMONIASIS

General Notes

- Most intestinal protozoa have cyst >>> excyst in intestine >>> amplify in intestinal lumen >>> trophozoites invade >>> trophozoites can then encyst and go out into environment.

What is Dientamoebiasis?

- Dientamoebiasis is caused by **Dientomoeba fragilis,** an ameba-like flagellate closely related to the genera **Histomonas** and **Trichomonas.**
- D. fragilis has a worldwide distribution
- Transmission: unknown. May be water borne and person-to-person transmission. Close relationship between Enterobius vermicularis and D. fragilis infections.
- Non-invasive in large intestine.
- It doesn't have cyst phase, and it is a trophozoite >>> not sure how it gets around. It has been postulated that pinworm eggs or larvae may be transmitting agent for D. fragilis.

What is the pathogenesis of Dientamoebiasis?

- Does NOT seem to invade. Theory of transmission is that this protozoa gets from person-to-person via the pinworm eggs. So if patient diagnosed with either pinworm or Dientamoebiasis – look for the other parasite as well!
- D. fragilis causes symptoms by irritating colonic mucosa.
- Fibrosis is present in appendices infected by D. fragilis.

What are the clinical manifestations of Dientamoebiasis?

- Many asymptomatic
- Can present with: intermittent diarrhea, abdominal pain, anorexia, fatigue, and less commonly with fever, irritability, weight loss and vomiting.
- Occasionally see eosinophilia b/c of pinworm.

How is Dientamoebiasis diagnosed?

- Diagnosis by finding trophozoites in stool.

How is Dientamoebiasis treated?

- **Tetracycline** & **Iodoquinol,** alone or in combo
- **Paromomycine** can also be used

What is Trichomoniasis?

- It is a specific GU tract infection with **Trichomonas vaginalis.**
- The organism is highly site specific >>> vaginitis in women and urethritis in men (both sexes are equally susceptible, but women symptomatic and men tend not to be, so treat both men and women, if woman presents).
- Distribution: occurs worldwide, in both rural and urban settings.
- Transmission: it is a common STD and patients should be screened for other STDs if positive. Perinatal transmission occurs rarely in vaginal births. No cyst forms! Transmission requires intimate contact with actively motile organism. So, if find in a child, be concerned about child abuse.
- At risk groups: professional sex workers, young people who are more sexually active



Trichomonas vaginalis typically infects the vagina in women and the prostate and urethra in males.

What is the morphology of Trichomonas vaginalis?

- 3-5 anterior flagella
- One undulating membrane
- Hydrogensome
- 7-23 micrometers
- Axostyle

What is the life cycle of Trichomonas?


CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx
sexual intercourse
3
i
i = Infective Stage
d = Diagnostic Stage
Trichomonas vaginalis
d
1 Trophozoite in vaginal and prostatic secretions and urine
2 Multiplies by longitudinal binary fission
i
3 Trophozoite in vagina or orifice of urethra

Trichomonas vaginalis resides in the female lower genital tract and the male urethra and prostate ❶, where it replicates by binary fission ❷. The parasite does not appear to have a cyst form, and does not survive well in the external environment. *Trichomonas vaginalis* is transmitted among humans, its only known host, primarily by sexual intercourse ❸.

What is the pathogenesis of Trichomoniasis?

- Mechanisms of this disease poorly understood.
- Organism can be found in vagina of >95% of infected women and urinary tract alone in <5%.
- Infects **squamous epithelium**, but not columnar epithelium, and organisms are rarely isolated from endocervix.
- Urethra involved in 90% of cases, and organisms can be isolated from urine.
- Can be found in men in epididymis and prostate.
- Association with **cervical carcinoma** due to co-infection with **Papillomavirus**.

8. What are the clinical manifestations of Trichomoniasis?

- Trichomoniasis ranges in women from asymptomatic to severe inflammation. Other symptoms:
    1. vaginal discharge (often yellow due to lysed PMNs)

    2. vulvar irritation or pruritis
    3. dyspareunia
    4. lower abdominal discomfort w/ adnexal tenderness on bimanual exam
    5. sometimes **strawberry cervix**
    6. vaginal wall erythema
    7. the organism is cytolytic, and pumps out a lot of polyamines >>> **fishy odor** w/ copious discharge.
    8. pain on urination
    9. often exacerbated by menstruation
- Initially asymptomatic disease frequently becomes symptomatic >>> so asymptomatic carriers should be treated.
- Disease usually asymptomatic in men, but can rarely present as urethritis, epidiymitis or prostate involvement.
- Many patients co-infected with gonorrhea or other STDs.

What are some potential complications of Trichomoniasis?

- Usually benign
- But in pregnant women can cause premature rupture of membranes >>> early childbirth and fetal complications
- May be associated with enhanced sexual transmission of **HIV** (seroconversion), especially in developing countries.

How is Trichomoniasis diagnosed?

- Wet mount preparation of vaginal fluid
- Urine sediment
- Prostatic secretion
- pH > 4.5
- Fluorescent antibody test is most specific and sensitive
- Culture >95%, but rarely done b/c takes 3 days and patients present with acute symptoms
- Positive whiff test

How is Trichomoniasis treated?

- **Flagyl/Metronidazole:** can use single dose therapy
- Simultaneous treatment of partner!
- 90% cure rate – recurrent symptoms do not necessarily indicate resistance to Metronidazole, more likely to be reinfection.
- Prevention: using condoms, limiting number of sexual partners

What is Giardiasis?

- A **zoonotic** infection (but most commonly person-to-person transmission) of the lumen of the small intestine with the flagellate protozoan **Giardia lamblia.**
- Many patients have no symptoms (50% spontaneous cure w/o symptoms), but a smaller portion have diarrheal disease that varies in its severity (can be acute or chronic diarrhea, usually 1+ week after exposure).
    1. usually non-bloody, **explosive diarrhea** (it is an upper intestinal parasite, that is **NOT invasive,** prevents absorption).
- Distribution: occurs worldwide in temperate and tropical areas. Essentially a disease of poverty where sanitation is poor, fecal contamination of environment is common, and there is no clean drinking water. 200 million cases annually.
- Transmission: infection follows ingestion of viable parasitic cysts from contaminated food or water. Cysts can also be transmitted via fingers to mouth particularly in children (after touching ground contaminated with feces). Person-to-person transmission also occurs in children.
    1. US outbreaks: defective water treatment plants
    2. beavers and dogs
    3. tropics >>> high level of environmental contamination
    4. can get it from drinking from mountain streams
- Symptomatic disease more common in children
- Mechanism of diarrhea with Giardia is unknown. Giardia contains viruses (**mini Rotovirus**) – may be involved in diarrhea, but doesn't seem to be.

What is the morphology of Giardia lamblia?

- Cyst is oval and measures 8x12x8 micrometers

- Can see median body and 4 nuclei
- Pear-shaped trophozoite is 15 micrometers long, with curved dorsal surface and a concave ventral surface, much of which is taken up by a disk with regular striations termed the sucker disk.
- Has no mitochondria, but does have some human or mammalian genes in Giardia genome. Entameba histolytica, Trichomonas, etc also lack mitochondria >>> treat with Metronidazole b/c anaerobic.
- 2 of 8 flagella emerge near midline on the ventral surface of organism, and others around periphery (3 on each side) >>> the beating flagella produce spiraling motion and keep the organism attached to microvilli of gut epithelium





Left image: Giardia lamblia cyst (8-12 long x 7-10µm wide) with 2 nuclei. The mature cyst has 4 nuclei. Right image: Giardia lamblia trophozoite (9-21 long x 5-15µm wide). Typically found in the duodenum. It is binucleate and has 4 pairs of flagella. Giardia is a Diploid organism with 2 1N nuclei.

What is the life cycle of Giardia lamblia?


CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx
②
i
Contamination of water, food, or hands/fomites with infective cysts.
Trophozoites are also passed in stool but they do not survive in the environment.
①
i
d
Cyst
d
i = Infective Stage
d = Diagnostic Stage
Cyst
Trophozoites
③
④
⑤

Cysts are resistant forms and are responsible for transmission of giardiasis. Both cysts and trophozoites can be found in the feces (diagnostic stages) ①. The cysts are hardy and can survive several months in cold water. Infection occurs by the ingestion of cysts in contaminated water, food, or by the fecal-oral route (hands or fomites) ②. In the small intestine, excystation releases trophozoites (each cyst produces two trophozoites) ③. Trophozoites multiply by longitudinal binary fission, remaining in the lumen of the proximal small bowel where they can be free or attached to the mucosa by a ventral sucking disk ④. Encystation occurs as the parasites transit toward the colon. The cyst is the stage found most commonly in nondiarrheal feces ⑤. Because the cysts are infectious when passed in the stool or shortly afterward, person-to-person transmission is possible. While animals are infected with *Giardia*, their importance as a reservoir is unclear.

What is the pathogenesis of Giardiasis?

- Infected individuals have a range of functional and morphological changes.
- Those who are asymptomatic usually have normal absorption and normal jejunal mucosa.
- **Blunting of villi of brush border** in small intestine >>> poor absorption.
- Mild symptoms associated with some reduction in D-xylose absorption and minor histologic abnormalities without reduction of villous height.
- Impaired absorption of **fat, D-xylose** and **Vitamin B12** are common in those severely affected. There is obvious reduction in villous height, increase in crypt depth with increased numbers of mitotic figures.
- Enzyme deficiencies >>> lactose intolerance.


Giardia lamblia on intestinal biopsy.

What are the clinical manifestations of Giardiasis?

- Symptoms in acute infections begin after an incubation period of 1-2 weeks, then resolve spontaneously, and include:
    1. anorexia
    2. nausea
    3. lassitude
    4. diarrhea w/ yellow, frothy, greasy, foul-smelling stools (no blood or mucous)
    5. bad taste in mouth
    6. sulfuric flatulence and belching
    7. abdominal discomfort
    8. weight loss
    9. steatorrhea
- after infection a variety of outcomes:
    1. acute diarrheal illness that resolves spontaneously with eradication of infection
    2. continuing diarrhea and weight loss with continuing infection
    3. resolution of diarrhea with continuing cyst excretions
- complications:
    1. if symptoms present for months >>> **glottitis**, indicating **folate deficiency**
    2. food allergy

How is Giardiasis diagnosed?

- Demonstration of parasite in stool samples or path specimens (low vs. high excretors), take 3 stool samples (>95% probability of finding organism, but can be same stool 3 times)
    1. can run **monoclonal Antibodies** on stool sample
    2. **Copro-antigens** (antigens in stool) is an ELISA test, but high false positive rate.
- ELISA and monoclonal antibodies have both been used with good results.
- Enterotest: string with lead weight, swallow capsule, it dissolves in stomach, look for bile at end of capsule and get a sample of upper intestinal contents. Low-tech.
- Endoscopy and biopsy
- serology

Who gets Giardia?

- People with poor hygiene, such as children and food workers
- Backpackers or travelers
- People in areas with poor sanitation
- Male homosexuals
- Water-borne epidemics

How is Giardiasis treated?

- **Metronidazole**
- **Tinidazole**
- **Quinacrine**

- **Furazolidone**
- **Paromomycin:** if patient is pregnant
- Usually not resistant, typically re-infection, or person is immunocompromised
- Prevention: personal hygiene and prevention of fecal-oral transmission, protect water supply >>> boiling will get rid or most pathogens, iodine is effective, chlorine is less effective

Balantidium coli



- B. coli is a classic ciliate
- Invasive >>> bloody diarrhea
- Covered with rows of cilia
- Defining characteristic is nuclear dimorphism
- Sexual reproduction involving conjugation
- Primarily seen in people with exposure to pigs and other animals.
- Treatment: **Tetracycline** or **Iodoquinol**
- Diagnosis: look for cysts or trophozoites in stool

Balantidium coli, note: only ciliate infecting man, macro and micronucleus present.

Blastocystis hominis

- Life cycle unknown
- Previously called yeast, ameba, sporozoan, etc. Appears to be a **Stramenophile.**
- Pathology: on the border between commensal organism and pathogen >>> can lead to vague intestinal discomfort. Fecal-oral transmission.
- Treatment: no real treatment. Can use Iodoquinol or Metronidazole, but only 50-60% effective.

LECTURE #10: TOXOPLASMOSIS

Toxoplasmosis

- Major cause of M&M, caused by the protozoan parasite Toxoplasma gondii.
- Most infections are asymptomatic, with at most minor flu symptoms. Infections most severe in congenitally infected infants and in immunocompromised.
- Transmission:
    1. ingestion of tissue cysts containing bradyzoites in undercooked infected meat
    2. ingestion of environmentally resistant sporulated oocytes in water, raw produce, or soil
    3. transplacentally from mother to fetus
    4. tissue transplantation
- Cats (particularly younger cats and kittens) and field animals are definitive hosts (adult forms and sexual reproduction), and most warm-blooded animals can serve as intermediate hosts (immature forms and asexual reproduction).
- 22.5% of people in US have antibodies to it – very common parasitic illness.
- Treatment: drugs can treat active infection, but none kill the tissue cyst stage of parasite.
- Oocysts are environmentally stable can survive in water, etc.
- Latent tissue cyst stage parasites can reactivate and cause development of new illness in immunocompromised patients.
- Distribution: worldwide, widespread infections in mammals and birds.



Toxoplasma gondii stages; A) bradyzoite, B) tachyzoite, C) tachyzoites in tissue culture, D) oocyst [Nomarski optics].

Apicoplasts

- A class of parasites
- Apicoplast: organelle with 4 membranes, typical plastid has 2 membranes as do mitochondria (potentially b/c of joining of 2 cells). Potentially ingestion of a fungi.
- Toxoplasmosis and Malaria have several plant-like metabolic pathways >>> major potential therapeutic target!!
- Unique mechanism of replication called endogeny. Form 2 daughter cells within eukaryotes.

Life Cycle of Toxoplasma Gondii

A. Ingestion of infected meat

- When infected meat with tissue cysts is ingested, the bradyzoites are liberated from tissue cysts after exposure to the acid conditions of the stomach >>> bradyzoites penetrate the mucosa of the SI >>> multiply in cells in lamina propria.
- Bradyzoites convert to tachyzoites within a few days (rapidly reproducing form goes through reticuloendothelial system).>>> tachyzoites disseminate throughout body via lymphatic and vascular systems >>> lymphadenopathy and fever.
- Tissue cysts are then produced in various tissues such as heart, retina and skeletal muscles. They are viable for several years to life of host.


Toxoplasma gondii cyst (bradyzoites) in lymph node biopsy.

B. Ingestion of Sporulated Oocysts
- When sporulated oocysts are ingested, the sporozoites are liberated from the sporocysts inside the oocysts into the lumen of the duodenum. Sporozoites penetrate the mucosa of the SI >>> multiply >>> tachyzoites disseminated throughout body >>> tissue cysts containing bradyzoites are produced in a variety of tissues.

C. Life Cycle in Cat
- T. gondii undergoes a coccidial life cycle in enterocytes of small intestine.
- 5 distinct asexual schizont types are present in enterocytes of feline intestine and produce the sexual stages that give rise to oocysts.
- Oocysts are excreted in the feces for several weeks, but high numbers are only excreted during the first week of patency. The length of time it takes before oocysts are excreted (prepatent period) varies depending on the stage of T. gondii that was ingested by the cat. Oral inoculation of bradyzoites/tissue cysts is most efficient in inducing oocyst-producing infections in cats. Oral inoculation with tachyzoites or oocysts is less efficient.
- Oocytes then develop (sporulate) in outside environment in a few days >>> the sporulated infective oocyst has 2 sporocysts that each enclose 4 infective sporozoites.



Both oocysts and tissue cysts transform into tachyzoites shortly after ingestion. Tachyzoites localize in neural and muscle tissue and develop into tissue cyst bradyzoites. If a pregnant woman becomes infected, tachyzoites can infect the fetus via the bloodstream.

d Diagnostic Stage

1) Serological diagnosis.

or

2) Direct identification of the parasite from peripheral blood, amniotic fluid, or in tissue sections.

http://www.dpd.cdc.gov/dpdx

Members of the cat family (Felidae) are the only known definitive hosts for the sexual stages of *T. gondii* and thus are the main reservoirs of infection. Cats become infected with *T. gondii* by carnivorism ①. After tissue cysts or oocysts are ingested by the cat, viable organisms are released and invade epithelial cells of the small intestine where they undergo an asexual followed by a sexual cycle and then form oocysts, which are excreted. The unsporulated oocyst takes 1 to 5 days after excretion to sporulate (become infective). Although cats shed oocysts for only 1 to 2 weeks, large numbers may be shed. Oocysts can survive in the environment for several months and are remarkably resistant to disinfectants, freezing, and drying, but are killed by heating to 70°C for 10 minutes.

Human infection may be acquired in several ways: A) ingestion of undercooked infected meat containing *Toxoplasma* cysts ②; B) ingestion of the oocyst from fecally contaminated hands or food ③; C) organ transplantation or blood transfusion; D) transplacental transmission; E) accidental inoculation of tachyzoites. The parasites form tissue cysts, most commonly in skeletal muscle, myocardium, and brain; these cysts may remain throughout the life of the host

Pathogenesis of Toxoplasmosis

- **Tachyzoites** (proliferative stage) can be found in any cell type in the body except RBCs.

- Hundreds to thousands of **Bradyzoites** are contained in tissue cysts (latent stages), and can be found in many tissues including brain, eye, heart, kidney, liver, bone marrow and skeletal muscles.
- Domestic cats excrete the largest amount of T. gondii sporulated oocytes in their feces >>> humans can become infected after ingesting infected water, food, etc.
- Ingestion of unwashed fruits and vegetables is associated with increased risk of maternal toxoplasmosis, as is contact with soil.
- Cockroaches can pick up cysts and deposit them other places
- Pork is the most likely commercial food sources of tissue cysts in the US. Chicken (rarely), sheep, goat, deer, wild pigs, turkeys, and bear are all possible sources of infection – found in mammals. Can ingest zoites in undercooked meat.
- Cats are pivotal in transmission of parasite to herbivores and omnivores
- Only the bradyzoite stage from the tissue cyst can cause the enteroepithelial cycle in the cat's enterocytes, which terminates in occyst excretion in feces.
- Sporulation occurs in environment and depends on temp and moisture.
- Organ transplantation can transfer infection if latent cysts or bradyzoites in tissue of transplanted organ.
- Blood transfusions can transmit T. gondii only during acute stage of infection.



Toxoplasma gondii in heart tissue (tachyzoites or pseudocyst).

Clinical Manifestations of Toxoplasmosis

- Symptoms depend on age and immune status of patient. Most cases asymptomatic.
- Infections in congenitally infected patients and immunocompromised are more severe.
  1. CNS infection with encephalitis or chorioretinitis is most common manifestation.
- Acute disease and death can occur in a primary infection.
- Re-activated disease occurs in individuals who have a latent infection and subsequently become immunocompromised.
- 1-2 week incubation period; peaks 1-2 months and then declines. IgG persists for life.
- In symptomatic patients:
  1. mononucleosis-like symptoms with lymphadenitis or chorioretinitis most common
  2. rarely, myocarditis, polymyositis, septicemia, or encephalitis
- Complications: depend on age and immune status of patient.
  1. chronic behavioral changes – link made in literature, unknown
- T. gondii is important cause of chorioretinitis and posterior uveitis
- Congenital infections usually present by age 30, whereas acquired are common age 40-70.
- Prior to HAART, most frequent cause of CNS lesions in HIV+ patient. It is related to reactivation of latent infection. Need to biopsy brain for diagnosis (cannot use serology). Or, can initiate therapy based on clinical and radiographic syndrome with anti-Toxo therapy – if see response that makes the diagnosis without brain biopsy.





Left image: Chorioretinits due to Toxoplasma gondii (Congenital infection). Right image: Encephalitis due to Toxoplasma gonii, CT scan, in an AIDS patient. Note typical, but not diagnostic, ring enhancing lesion.

Congenital Infection with Toxoplasmosis

- Congenital infection occurs with women are seronegative during pregnancy
- Women who are seropositive before conception, do not transmit infection to fetus. Exception: immunocompromised women (due to HIV or steroids) can transmit latent infection during pregnancy.
- Likelihood of transmission of infection is more likely with each progressive trimester, but severity of disease in the fetus is worse the earlier in pregnancy it occurs.
- Symptoms of congenital infections:
    1. chorioretinitis
    2. strabismus
    3. epilepsy
    4. mental retardation
    5. anemia
    6. jaundice
    7. rash
    8. thrombocytopenia
    9. encephalitis
    10. microcephaly
    11. sensorineural hearing loss
    12. intracranial calcifications
    13. hydrocephalus
- part of **TORCH syndrome**.
- 2/3 asymptomatic at birth, but may develop chorioretinits or other symptoms later

Diagnosis of Toxoplasmosis

- detection of anti-T. gondii antibodies by serological tests
- detection of tachyzoites or T. gondii-specific DNA in body fluids or tissue sample
- parallel testing of specimens 4 weeks apart
- seroconversion of a 4 fold rise in IgG titer is diagnostic of acute infection.
- In polymyositis or myocarditis biopsy can be useful (so low avidity antibody is seen during acute infection).
- IgG persists for life. Titer avidity increases with time, so low avidity IgG more likely to be acute infection.
- IgM appears earlier and declines more rapidly than IgG (usually within a few months) >>> presence of IgM suggests acute infection.
- Low IgG titers in first trimester with negative IgM are consistent with chronic infection
- Positive IgM titers require further evaluation. 60% with + IgM have chronic infection.
- Amnio and US of fetus are recommended for acute infection with PCR. Fetal blood sampling does not increase diagnostic yield.

Treatment of Toxoplasmosis

- Asymptomatic or latent infection:
  1. immunocompetent individuals w/ latent disease do not require treatment
  2. AIDS patients can get encephalitis >>> treat with **TMP-SMX**
  3. cardiac transplantation treat prophylactically for 6 weeks with **Pyrimethamine**
- Acquired Toxoplasmosis:
  1. if immunocompetent treatment probably not necessary
  2. in cases of myocarditis, encephalitis, or sepsis, treat with **Pyrimethamine + Sulfadiazine** (or **Trisulfapyrimidine**) **+ Folinic Acid** (for 4-6 weeks)
- Acquired infection during pregnancy:
  1. acutely infected pregnant women treat with Spiramycin
  2. Amniocentesis, fetal blood monitoring and fetal US should also be used
  3. If + fetal diagnosis >>> treat mother with Pyrimethamine + Sufladiazine + Folinic Acid. However, Pyrimethamine should not be used during first 16 weeks of pregnancy.
- Congential Toxoplasmosis:
  1. treat with Pyrimethamine + Sulfadiazine + Folinic Acid
  2. corticosteroids should be added in patients with macular disease
- Toxoplasmosis infection in immunocompromised host:
  1. Pyr + Sulfa + FA (**Clindamycin** can be substituted for Sulfa drugs)
  2. Corticosteroids can be used to control intracranial HTN
- Alternative meds: **Atovaquone, Azithromycin, Clindamycin, gamm-interferon** (critical for almost all intracellular parasites) recombinant form is experimental therapy, plant fatty acid pathway inhibitors like **Triclosan** or **Roundup**

Prevention of Toxoplasmosis

- Don't eat raw or poorly cooked meat
- Food preparers should wash hands and cooking surfaces with warm soapy water
- Change cats' litter boxes regularly, but pregnant women and immunocompromised shouldn't do this. Also, keep cats indoors and feed only commercially prepared foods.
- Wear gloves when gardening
- Wash all fruits and vegetables

Pyrimethamine (PYR)/Daraprim

- Mechanism of Action: inhibits **dihydrofolate reductase** (Trimethoprim also inhibits this enzyme)
- Absorption: readily absorbed from GI tract
- Distribution: well distributed in most tissues, and found in CSF; t1/2= 35-175 hours
- Metabolism: hepatic
- Adverse Effects: dose-related bone marrow suppression w/ thrombocytopenia, neutropenia, and anemia. Folinic Acid given to prevent these side effects.

Sulfonamides

- Mechanism of Action: inhibit **dihydrofolic acid synthetase**, which is another enzyme involved in folic acid metabolism, so synergistic with PYR.
- Absorption: well-absorbed
- Distribution: good, with CSF
- Metabolism:
- Adverse Effects: are common (particularly in AIDS patients), bone marrow suppression (responsive to Folinic Acid), hypersensitivity reactions with rash and Stevens-Johnson syndrome.

Macrolides & Lincomycins

- Drugs: Spiramycin (SPR, available in Europe and on request from FDA in US), Erythromycin, Azithromycin, Roxithromycin, Clarithromycin
- Mechanism of Action: inhibition of apicoplast

Pneumocystis Carinii

- Originally considered a protozoa, but it is actually an atypical **fungus**.
- However, doesn't respond to anti-fungal drugs. Responds to Bactrim (TMP-SMX) and other anti-protozoal drugs.
- Host specific organism (rats and humans have 2 different species).

- Pneumocystis jirovecii is the species that infects humans, so P. carinii is not actually the infective agent in PCP seen in AIDS patients.
- Symptoms: primarily infects the lungs >>> pneumonia, SOB, chronic cough, low-grade or no fever, decreased PaO2 on room air, chest tightness or pain.
- Who does it affect?
    1. Primarily disease of immunocompromised (AIDS CD4 >200) and lethal if untreated. Occurs at less immunosuppression than other op. infections >>> bellweather of HIV epidemic.
    2. Malnourished infants
    3. Children with primary malignancies
    4. solid tumor patients, neoplasms, hematologic malignancies
    5. high dose corticosteroids !!!
    6. transplant recipients
    7. inflammatory or collagen-vascular diseases (esp. Wegener's granulomatosis)



Pneumocystis carinii, Lung section stained with Gomori methenamine silver stain; cyst wall is stained black. Know this slide!!! Classic pneumocystosis shown by silver stain. Know it isn't yeast b/c no budding.

Diagnosis of Pneumocystis

- a non-cultivatable organism, but can look for it in sputum with special stains or monoclonal antibodies
- bronchopsy for deep lung specimen
- Gallium scan
- Diffuse, foamy infiltrate in the middle of the lung
- Life cycle is not completely figured out
- Person-to-person transmission
- PCP increasing in HIV+ people in developing countries
- HAART is decreasing incidence
- Evidence for transmission form symptomatic hosts; some outbreaks in hospital settings >>> may want to isolate pneumocystis patients



Image: Pneumocystis carinii, giemsa stain; trophozoites are stained (intracystic bodies are visible).

Prevention & Treatment

- Immune reconstition – if CD4 count above 200, incidence drops dramatically
- Bactrim prophylaxis can prevent pneumocystis >>> so given to all patients with CD4 count <200.
- Primaquine & Clindamycin
- Pentamidine not used anymore
- Alternative to TMP-SMX that is widely used is Atovaquone.
- Adjunctive corticosteroids in antipneumocystis therapy

LECTURE #11: CRYPTOSPORIDIUM, CYCLOSPORA, ISOSPORA & MICROSPORA

Comparison of Cyclospora, Cryptosporidium & Isospora

Acid fast staining:

    1. Cyclospora: variable
    2. Cryptosporidium: yes
    3. Isospora: yes

UV Autofluorescence: Cyclospora blue/green

Cryptosporidium Species

- **Intracellular GI parasites** originally thought to cause disease in animals.
- Current methods of water purification do not remove Cryptosporidia.
- No effective therapy for it.
- Most cases self-limited, but can be devastating in immunocompromised, and to children in developing countries. Immunocompromised with deficient **cell-mediated immunity** are particularly vulnerable.
- Types: 10 species, but **Cryptosporum parvum** infects humans.
- Infection is a zoonosis with mainly bovine and human reservoirs.
- Transmission: humans get infection by ingesting oocysts, which are shed in stool of animals or humans either through water, food, and excreted fully infective so can be passed from person to person! Hardy cysts resistant to chlorine, UV radiation, but killed by freezing or heating.
- Epidemiology:
    1. Endemic in developing countries >>> one of most common causes of persistent diarrhea among children.
    2. In developed world, mainly in outbreaks, usually due to contaminated drinking water.
    3. Antibodies in 30% of US population.
    4. Milwaukee & Nevada outbreaks
    5. **Water outbreaks**

Life Cycle of Cryptospordium


CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx
i
③ Thick-walled oocyst ingested by host
Recreational water
Drinking water
Contamination of water and food with oocysts. ②
i = Infective Stage
d = Diagnostic Stage
① Thick-walled oocyst (sporulated) exits host d i
ⓙ Thick-walled oocyst (sporulated) exits host
ⓐ Oocyst
ⓑ Sporozoite
ⓒ Trophozoite
ⓓ
Type I Meront
ⓔ
Auto-infection
ⓚ Thin-walled oocyst (sporulated)
Asexual Cycle
Merozoite
Microgamont
Microgametes
ⓖ
Undifferentiated Gamont
ⓕ
Type II Meront
Merozoites
Sexual Cycle
Macrogamont
ⓗ
Zygote
ⓘ

Life cycle of *Cryptosporidium*.
(from: Juranek DD. Cryptosporidiosis. In: Hunter's Tropical Medicine, 8th edition. Strickland GT, Editor.)

Sporulated oocysts, containing 4 sporozoites, are excreted by the infected host through feces and possibly other routes such as respiratory secretions ①. Transmission of *Cryptosporidium parvum* occurs mainly through contact with contaminated water (e.g., drinking or recreational water). Occasionally food sources, such as chicken salad, may serve as vehicles for transmission. Many outbreaks in the United States have occurred in waterparks, community swimming pools, and day care centers. Zoonotic transmission of *C. parvum* occurs through exposure to infected animals or exposure to water contaminated by feces of infected animals ②. Following ingestion (and possibly inhalation) by a suitable host ③, excystation ⓐ occurs. The sporozoites are released and parasitize epithelial cells (ⓑ, ⓒ) of the gastrointestinal tract or other tissues such as the respiratory tract. In these cells, the parasites undergo asexual multiplication (schizogony or merogony) (ⓓ, ⓔ, ⓕ) and then sexual multiplication (gametogony) producing microgamonts (male) ⓖ and macrogamonts (female) ⓗ. Upon fertilization of the macrogamonts by the microgametes (ⓘ), oocysts (ⓙ, ⓚ) develop that sporulate in the infected host. Two different types of oocysts are produced, the thick-walled, which is commonly excreted from the host ⓙ, and the thin-walled oocyst ⓚ, which is primarily involved in autoinfection. Oocysts are infective upon excretion, thus permitting direct and immediate fecal-oral transmission.

Note that oocysts of *Cyclospora cayetanensis*, another important coccidian parasite, are unsporulated at the time of excretion and do not become infective until sporulation is completed. Refer to the life cycle of *Cyclospora cayentanensis* for further details.

Pathogenesis of Cryptospordiosis

- Infection with Cryptosporidium begins when the ingested oocyst releases sporozoites >>> attach to and invade intestinal epithelial cells (particularly jejunum and terminal ileum) >>> minimal inflammatory infiltrate (**IFN-gamma**) and **blunting of villus** (more pronounced in immunocompromised) >>> malabsorption.
- Mechanism of diarrhea is unclear.

Clinical Manifestations of Cryptosporidiosis

- Presentation variable, typically **profuse, watery diarrhea w/ abdominal pain;** sometimes asymptomatic.
- Sometimes: fever, malaise, nausea, vomiting and loss of appetite.
- Symptoms 5 days-2 weeks post-ingestion of oocysts; lasts 3-5 weeks.
- Increased risk of infection with CD4 count <200.
- **Acute Diarrheal Illness:** shedding of oocysts for 8-50 days post-resolution of clinical symptoms:
    1. watery diarrhea (+/- mucous)
    2. epigastric pain, nausea, vomiting
    3. weight loss
    4. low grade fever 50% immunocompetent
- **Chronic Diarrheal Illness:** occurs in **AIDS (CD4 <100),** hypogammaglobulinemia, or chemo patients. Similar presentation, but lasts months to years, may be severe or life-threatening. Will resolve spontaneously in patients with reversible immunosuppression.
    1. diarrhea w/ fluid losses of >20 L/day possible
    2. severe abdominal pain
    3. anorexia and major weight loss
- **Gallbladder & Biliary Disease:**
    1. cholangitis seen in AIDS patients CD4 <50 – poor prognosis
- no RBCs or WBCs in stool

Diagnosis of Cryptosporidiosis

- biopsy w/ demonstration of intracellular parasite
- **Acid-fast Kinyoun test** to identify oocysts in stool – gold standard

Treatment of Cryptosporidiosis

- **Nitazoxanide** in children and HIV patients. HIV patients also need **HAART.**
- **Azithromycin**

Isospora

- Distribution: South America, Mexico, Carribean
- Symptoms: **watery diarrhea,** flatulence, malaise, anorexia, low fever, weight loss, **Charcot-Leyden crystals** in stool, **peripheral eosinophilia** (exception to rule that protozoa don't cause eosinophilia!).
- Transmission: sporulates outside of host – probably doesn't have person to person transmission.
- Diagnosis: check stool for O&P. **Acid Fast**!
- Treatment: **Bactrim;** prophylax patients with low CD4 counts.





Left image: Isospora belli oocyst (20-33µm x10-19µm) containing 2 sporoblasts.
Right image: Isospora belli acid fast staining.

Cyclopsora

- Cyclospora is a genus in the phylum **Apicomplexa**. It is related to Cryptosporidium, Isospora, Toxoplasma, and Sarcocystis.
- Like other Apicomplexans, sporozoites have an apical complex composed of a polar ring, conoid, rhoptries, and other coccidian structures.
- Morphology: 8-10 microns in diameter.
- Life cycle: not known. Thought that sexual and asexual development occurs in human host. Cyclospora oocysts in fresh stool are NOT infectious; oocysts require days to weeks outside host in favorable environmental conditions to sporulate and become infectious.
- Transmission: through food (often fresh produce like **raspberries**), and water (highly chlorine resistant), human-to-human unlikely.
- Distribution: common in tropical and subtropical areas worldwide; endemic to Nepal, Haiti & Peru. Rainy season May to October, and in US May to July. Marked **seasonality of infection** – but with differing patterns in different regions.
- Pathogenesis: intracellular organism that parasitizes enterocytes of upper small bowel. Inflammatory cell infiltrates in lamina propria sometimes. Pathological changes are similar to tropical sprue.
- Histology: contain numerous refractile globules in membranes. Acid-fast staining variable.

Clinical Manifestations of Cyclosporiasis

- Symptoms: usually in a cyclical pattern alternating with constipation
    1. may have flu-like prodrome with myalgias
    2. **watery diarrhea:** relapsing, cyclical pattern
    3. **profound fatigue**
    4. anorexia
    5. weight loss
    6. less common: fever, chills, headache, vomiting
- self-limited infection in immunocompetent, but may last weeks
- abnormal **D-xylose** absorption in infected patients
- infection in AIDS patients is prolonged, severe and high recurrence rate >>> treat with long-term suppressive therapy.
- Acquired immunity may not be completely protective

Diagnosis of Cyclosporiasis

- Microscopic demonstration of oocysts in fecal specimens, duodenal or jejunal aspirates or biopsy specimens.
- Identify **acid-fast organisms** (variable) with modified **Ziehl-Neelsen** or **Kinyoun** stains.
- Oocysts autofluoresce and appear as neon blue circles under **UV fluorescent** microscope.

Treatment of Cyclosporiasis

- **TMP-SMX**

Microsporidiasis

- Microsporidia are **obligate eukaryotic intracellular** parasites.
- Ubiquitous in environment, infect most animal phyla.
- Probably zoonotic and/or waterborne infections.
- Produces a wide array of clinical diseases in immunocompromised hosts.
- Over 1000 species in the phylum Microsporidia.
- Morphology: form very hardy characteristic **unicellular ovioid spores** w/ chitin & protein (1-3 microns in size). A defining characteristic of all Microsporida is an extrusion apparatus consisting of a **polar tube** attached to inside of anterior spore by an anchoring disk. During germination, the polar tube everts forming a hollow tube that serves as a bridge to deliver **sporoplasm** to the host cell.
- Distribution: everywhere except Antarctica.
- Cause diarrhea.

Types of Microsporidia

- over 1,000 species in the phylum Microsporidia. Some important pathogens are:
    1. Vittaforma corneae

2. Brachiola algerae
3. Pleistophora
4. Trachipleistophora: associated with encephalitis and disseminated disease.
5. **Encephalitozoon hellem:** associated with superficial keratoconjunctivitis, sinusitis, respiratory disease, prostatic abscesses, and disseminated infections.
6. **Encephalitozoon cunicili:** associated with Hepatitis, encephalitis, and disseminated disease.
7. **Encephalitozoon (Septata) intestinalis:** associated with diarrhea, disseminated disease and superficial keratoconjunctivitis.
8. **Nosema, Vittaforma,** and **Microsporidium** have been associated with stromal keratinis due to trauma in immunocompetent.
9. Pleistophora, Brachiola, and Trachipleistophora have been associated with myositis.
10. **Enterocytozoon bieneusi:** associated with malabsorption, diarrhea, and cholangitis.

Pathogenesis of Microsporidia

- Common enteric pathogens that are usually self-limited and asymptomatic.
- Self-limited diarrhea in normal hosts.
- If immunocompromised: diarrhea, wasting syndrome, and disseminated infection.
- **Enterocytozoon bieneusi** most common, hard to treat, seen in liver and heart-lung transplant patients.
- **Encephalitozoon** species infect patients with kidney, pancreas, liver or bone marrow transplants.
- Prior to HAART, Microsporidia responsible for 1/3 of cases of chronic diarrhea in HIV+.

Clinical Manifestations of Microsporidia Infections

- GI Infections: infection of epithelium of GI tract is most common presentation, 90% due to **Enterocytozoon bieneusi,** and less commonly due to **Enephalitozoon intestinalis.** Can lead to **Sclerosing Chonlangitis, Cholangiopathy, and Cholecystitis** in AIDS patients (most patients have elevated liver function tests including alkaline phosphatase, gamma-glutamyltransferase, aspartate aminotransferase and alanine aminotransferase).
    1. **E. bieneusi** is found on apical surface of enterocytes of small intestine and epithelial cells of biliary tract and pancreas. Rarely disseminates, unlike Encephalitozooindae, which are commonly found in lamina propria and visceral organs. Symptoms: chronic diarrhea (3-10 loose watery stools per day), weight loss and bloating, no fever. Most common in AIDS patients w/ **CD4 <50**. High mortality.
    2. **E. intestinalis** is invasive and spores common on apical and basal sides of intestinal enterocytes and inside fibroblasts, macs, and endothelial cells in the lamina propria.
- **GU Infection:** Encephalitozoon species infect GU of most mammals. Transmission through contamination of environment with spores passed in urine. Infections can affect any organ (eyes, GI, liver, CNS, etc.). HIV patients with keratitis can have asymptomatic infection of urinary tract and bronchial tree.
- **CNS Infection: Granulomatous encephalitis** is classic presentation of E. cuniculi; can mimic toxoplasmic encephalitis in HIV patients.
- **Ocular Infection: E. cuniculi, E. hellem & E. intestinalis** can result in punctuate keratopathy and conjunctivitis characterized by multiple punctuate corneal ulcers, e.g. superficial epithelial keratitis.
- **Musculoskeletal Infection:** myositis with inflammation due to several different Microsporidia has been described in humans. This includes Pleisophora ronneafiei, Pleistophora species, Trachipleistophora hominis, Brachiola vesicularum and Brachiola algerae.
- **Sinus & Respiratory Infections:** in disseminated infection due to Encephalitozoonidae, respiratory involvement is often seen. The pathologic features are non-specific and may include rhinitis, sinusitis, and/or nasal polyposis in any combo.

Diagnosis of Microsporidiosis

- NOT acid fast – use **Trichome Stain!!**
- Examination of stool specimens with light microscopy
- If stool is negative after 2+ months diarrhea, do endoscopy
- Obtain urine specimens b/c shedding of spores in urine is common in all species of Microsporidia.

Treatment of Microsporidiosis

- Microsporida that disseminate (like Encephalitozoon) are usually sensitive to **Albendazole.**
- **E. bieneusi** resistant and often treated with **Fumagillin.**
- Effective **HAART** >>> patients with improved immune function can usually fight off infection on their own.

LECTURES #12-13: MALARIA

Malaria

- Malaria is an acute and chronic disease caused by obligate intracellular protozoa of the genus Plasmodium.
- Four species of Plasmodium can infect humans:
  1. **P. malariae**
  2. **P. vivax**: present in Mexico, Central & South America, India, SE Asia
  3. **P. falciparum:** associated with severe and complicated disease; predominant species in Africa, Haiti, Dominican Republic; present in Mexico, Central & South America, Indian subcontinent, SE Asia, and Oceania.
  4. **P. ovale:** mainly in Africa
- Transmission: parasites are transferred to humans via Anopheles mosquitoes.
- Clinical Presentation: illness is highly variable, but characterized by fever, chills, anemia, and splenomegaly.

Epidemiology of Malaria

- 100+ countries in Asia, Africa, Latin America, Caribbean and Pacific Islands.
- 300-500 million cases each year, 100 million annually in SSA
- 1 million death per year – mostly in infants and young children

Life Cycle of Malaria

A. Initial Infection

- **Sporozoites** (infective stage) are injected along with saliva into subQ caps when female mosquito drains blood >>> present in peripheral blood for 30 min

B. Exoerythrocytic Phase

- some sporozoites are killed by phagocytes, others enter liver parenchymal cells >>> multiply asexually there in a process known as **exoerythrocytic schizogony/merogony.**
- 6-16 days later, hepatic cells with **schizonts/meronts** rupture >>> merozoites enter circulating RBCs.
  1. P. falciparum and P. malariae schizonts rupture at about the same time, and none persist in liver. No persistent exoerythrocytic phase, so relapse does not occur.
  2. P. vivax and P. ovale have 2 types of exoerythrocytic forms:
     a. **primary type** develops and ruptures in 6-9 days
     b. **secondary type (hypnozoite),** may remain dormant in liver for weeks, months, or up to 5 years before developing and causing relapse of infection (known as **recrudescence**).

C. Erythrocytic Stage

- **Merozoites** released from tissue schizonts invade RBCs (mediated by glycophorins on RBC surface) through invagination at electron dense annular junction.
- Internal parasite organelles (rhoptries and micronemes) discharge their contents, and the merozoite moves into the invagination.
- Once inside the cell, the parasite is sheathed in the parasitophorous vacuole membrane.

D. Asexual Stages

- The youngest stages in the blood are small, rounded trophozoites, known as ring forms.
- As parasites grow, they become more irregular and amoebid, and consume hemoglobin >>> producing iron-containing byproduct **heamtin** or **hemozoin**, which is visible in cytoplasm of the parasite as dark granules.
- **Erythrocytic schizogony/merogony:** the schizont/meront stage begins when the parasite undergoes nuclear division and culminates in segmentation to form merozoites.
- The erythrocytic cycle of schizogony continues destroying more RBCs until the host's immunity or antimalarial drugs stop it.

E. Sexual Stages

- The parastite life cycle continues when subpopulations of merozoites differentiate into sexual forms known as gametocytes.
- **Female macrogametocytes** and **male microgametocytes** usually appear within 3-15 days of the onset of symptoms.


i = Infective Stage
d = Diagnostic Stage
CDC
SAFER • HEALTHIER • PEOPLE™
http://www.dpd.cdc.gov/dpdx
Human Liver Stages
Liver cell
Infected liver cell
②
A
Exo-erythrocytic Cycle
④ Ruptured schizont
③ Schizont
Mosquito Stages
⑫ Ruptured oocyst
Release of sporozoites
⑪ Oocyst
① Mosquito takes a blood meal (injects sporozoites)
C
Sporogonic Cycle
⑩ Ookinete
⑧ Mosquito takes a blood meal (ingests gametocytes)
Macrogametocyte
Microgamete entering macrogamete ⑨
Exflagellated microgametocyte
Human Blood Stages
⑤
Immature trophozoite (ring stage)
B
Erythrocytic Cycle
Mature trophozoite
⑥ Ruptured schizont
Schizont
P. falciparum
⑦ Gametocytes
P. vivax
P. ovale
P. malariae
⑦ Gametocytes

The malaria parasite life cycle involves two hosts. During a blood meal, a malaria-infected female *Anopheles* mosquito inoculates sporozoites into the human host ①. Sporozoites infect liver cells ②and mature into schizonts ③, which rupture and release merozoites ④. (Of note, in *P. vivax* and *P. ovale* a dormant stage [hypnozoites] can persist in the liver and cause relapses by invading the bloodstream weeks, or even years later.) After this initial replication in the liver (exo-erythrocytic schizogony A), the parasites undergo asexual multiplication in the erythrocytes (erythrocytic schizogony B). Merozoites infect red blood cells ⑤. The ring stage trophozoites mature into schizonts, which rupture releasing merozoites ⑥. Some parasites differentiate into sexual erythrocytic stages (gametocytes) ⑦. Blood stage parasites are responsible for the clinical manifestations of the disease.

The gametocytes, male (microgametocytes) and female (macrogametocytes), are ingested by an *Anopheles* mosquito during a blood meal ⑧. The parasites' multiplication in the mosquito is known as the sporogonic cycle C. While in the mosquito's stomach, the microgametes penetrate the macrogametes generating zygotes ⑨. The zygotes in turn become motile and elongated (ookinetes) ⑩which invade the midgut wall of the mosquito where they develop into oocysts ⑪. The oocysts grow, rupture, and release sporozoites ⑫, which make their way to the mosquito's salivary glands. Inoculation of the sporozoites into a new human host perpetuates the malaria life cycle ①.

Clinical Manifestations of Malaria

- Only asexual stages are associated with symptoms.
- Clinical outcome is usually decided by degree of parasitemia. >1% parasitemia 1% mortality, >5% parasitemia 73% mortality (P. Falciparum). Usually don't have mortality with other strains, unless elderly, atherosclerotic patient with P. Vivax.
- Flu-like prodrome: headache, malaise, myalgias, fever
- Malaria paroxysms (corresponding to rupture of RBCs) usually develop within a few days of prodrome.
    1. fever (as high as 105F)
    2. rigors
    3. severe headaches
    4. abdominal pain
    5. nausea

    6. splenomegaly
    7. hepatomegaly
    8. blood tests show: anemia, thrombocytopenia, neutropenia, hyponatremia, and mildly elevated transaminases

- When majority of parasites in RBCs undergo schizogony (maturation) at same time, paroxysms occur at 48 hour intervals (the length of life cycle for all species of malaria except P. malariae which is 72 hours). This is rare in P. falciparum >>> see irregular pattern of paroxysms.
- **Simple Tertian: Vivax & Ovale** – individual has fever every 48 hours or 3 days.
- **Simple Quartan: Malarie** – every 72 hours or every 4th day
- **Malignant Tertian:** fever less intermittent, fever just keeps going up and down, but have well days in between. **Falciparum**.
- **Uncomplicated Malaria:** 0.1% mortality rate, absence of features of severe malaria.
    1. In adults common presentation is malaise, headaches, myalgias, abdominal pain early on, and later **Triphasic paraoxysms** (severe chills, fever, sweats, vomiting & watery diarrhea). Chills particularly severe with Vivax malaria. Spleen very enlarged and soft – if you poke too hard, you can rupture it.
    2. In children: cough, tachypnea, febrile convulsions (not cerebral malaria), in addition to adult symptoms.
- **Severe Malaria:** more common in first few years of life, and les frequent with increasing age. High level of circulating proinflammatory cytokines (**TNF-alpha**, NO, IL-1, IL-6, IL-8, IL-10, IL-12). A life threatening emergency with asexual parasitemia and 1+ complications:
    1. impaired consciousness or coma (coma doesn't necessarily indicate cerebral malaria)
    2. pulmonary edema (including ARDS)
    3. metabolic acidosis (usually **lactic acidosis**, major cause of death)
    4. high parasitemia >5%
    5. circulatory collapse, shock
    6. Acute renal failure
    7. Severe anemia
    8. Hypoglycemia (<40 gm/dL, normal = 80-100 gm/dL)
    9. spontaneous bleeding
    10. hemoglobinuria
    11. generalized convulsions = 2+ seizures in 24 hours
- **lactic acidosis:** major cause of death, anaerobic metabolism of parasites, decreased lactate clearance by liver, reduced delivery of oxygen to tissues due to sequestration, resetting, and hemolysis.
- Pathogenesis of coma unclear: cerebral edema not significant, intracranial pressure increase is not a significant factor.
- **Thrombocytopenia** with all 4 species of malaria due to increased splenic platelet clearance, platelet turnover will increase w/ time, so not usually a serious complication. Etiology unclear.
- **Hypoglycemia:** young children and pregnant women, due to decreased oral intake, depletion of liver glycogen by glycogenolysis, parasite consumption of glucose, increased insulin release from the pancreas (due to **Quinine** or **Quinidine**), inhibition of glyconeogenesis (due to increased TNF-alpha and IL-1).
    1. very serious complication in pregnancy! Fetus can have permanent CNS damage, IUGR, stillbirths or spontaneous abortion. Malaraial parasites will bind to syncitiotrophoblast (but doesn't happen after second pregnancy).
- **Nephrotic Syndrome** fatal complication of malaria.

Immunity to Malaria

- Merozoite of P. vivax needs **Duffy antigen** on surface of RBC >>> lack of Duffy antigen 100% protective against PV infection.
- In West Africa, 98% of local population lacks Duffy antigen.
- P. Ovale also found in West Africa, but can invade regardless of Duffy antigen.
- **Sickle cell trait** provides 90-95% protection from malaria, b/c **HbAS** clears organisms from spleen more quickly and inhospitable pH. Spleen key site of antibody production >>> phagocytosis of merozoites, infected RBCs, and debris, and Cytotoxic killing of infected RBCs.
- **HbF** in newborns provides protection from malaria for 5-6 months.
- After a long, unbroken period of heavy exposure, strain-specific clinical immunity can develop in adults, but not permanent.

- Malaria immunity: TH1 regulated (TNF-alpha & IFN-gamma) initially >> TNF causes fever which inhibits parasite growth. Later antibody depedent TH2 regulated >>> opsonization of parasites and infected RBCs with IL-4, IL-5, IL-6, IL-10.

Complications of P. Falciparum Infection

- Life-threatening complications can develop from P. falciparum infection, because it can infect RBCs of any age, unlike other species of Plasmodium (P. vivax and P. ovale infect Reticulocytes and P. malariae older erythrocytes).
- Also, PF-infected RBCs adhere to postcapillary venules and uninfected RBCs.
- Severe anemia, parasitemia and cytoadherence >>> tissue hypoxia and organ dysfunction >>> can lead to
    1. **symmetrical encephalopathy** (known as **cerebral malaria**)
    2. **acute tubular necrosis**
    3. **Adult Respiratory Distress Syndrome (ARDS)**
- Clinical manifestations of severe PF disease include:
    1. depressed consciousness
    2. convulsions
    3. respiratory distress
    4. shock
    5. spontaneous bleeding
    6. jaundice
    7. Acute Renal Failure
    8. hematuria
- Lab values associated with severe PF disease:
    1. >2% parasite density
    2. schizonts in peripheral blood smear
    3. acidosis
    4. hypoglycemia
    5. prolonged clotting time
    6. thrombocytopenia
    7. hemoglobin <7.5 g/dL



Cerebral Malaria

- Life-threatening complication of P. falciparum infection.
- Coma or impaired neural status during malaria infection needs to be distinguished from other causes of neuro deficits such as hyperpyrexia, hypoglycemia, and concurrent infection.
- Seizures >>> coma or decreased consciousness.
- Nuccal rigidity and photophobia do NOT occur, but patients can develop neck retraction, opishotonos, gaze disorders and posturing.
- Pathogenesis: altered RBC rheology, upregulation of cytokines (TNF-alpha, IL-1), upregulation of endothelial receptors (ICAM-1, CD36, ELAM-1, Thrombosondin), cytoadhesion (high sequestration in brain capillaries correlates with high mortality).
- Corticosteroids can increase mortality.
- Antipyretics, antiemetics, and anticonvulsants can be used.

Blackwater Fever

- Etiology unknown, but may be the following:
    1. G6PD deficient individuals with ingestion of oxidant drugs +/- malaria.
    2. G6PD deficient + malaria + Quinine
    3. severe quinine-treated malaria with normal G6PD
    4. unknown how Quinine is involved.
- Hemoglobinuria
- Jaundice
- Dark urine
- Oliguria or anuria (typically <200 ml/day)
- Nausea & vomiting of bile

Malaria During Pregnancy

- Can compromise fetal development and induce premature labor or spontaneous abortion.

- Chloroquine is safe for fetus.
- Concerns about oxytocic effects, but Quinine and Quinidine can be used safely during pregnancy. The risks of malaria infection outweight concerns about drugs.
- Theoretical risk of hyperbilirubinemia and subsequent kernicterus with Sulfonamide use during pregnancy.
- Tetracycline contraindicated during pregnancy >>> treat malaria during pregnancy with Quinine and Clindamycin.
- Primaquine is also contraindicated during pregnancy >>> patients should receive Chloroquine alone and be monitored for relapse.
- Congenital transmission can occur.

Malaria & HIV

- increased HIV replication and increased viral load
- greater parasitemia
- higher fevers, greater anemias, adverse birth outcomes (all pregnancies at risk rather than just first and/or second pregnancies).

Diagnosis of Malaria

- Malaria is a lab diagnosis. Important to examine several sequential blood smears for presence of parasitized erythrocytes. Initial smear may be negative, b/c symptoms can occur a few days before the appearance of infected erythrocytes at detectable levels.
- Ideally, both **thick & thin smears** should be obtained and examined on multiple occasions over a 72-hour period before diagnosis of malaria is excluded.
- New tests can detect parasites at lower levels.
- **Rapid Diagnostic Tests (RDT),** which are immunochromatographic, are based on capture of parasite antigen from peripheral blood using monoclonal antibodies prepared against a malaria antigen target.
    1. malaria antigens currently targeted by RDT are P. falciparum **histidine-rich proteins (HRP-2), pLDH**, and **Plasmodium aldolase.**
- **Thick blood smears** are prepared with Giemsa stain in a manner that optimizes parasite detection, but is unreliable for identification of species. Uses 30-40 microliters of blood >>> can't see through it on microscope so lyse RBCs and then stain.
- **Thin blood smears** are used for species identification, and prepared same as routine hematologic smears. Uses about 10 microliters of blood, morphology of parasite in relation to RBC is preserved.
- In addition to species identification, the degree of parasitemia should be estimated >>> prognostic implications in severe PF infections. At low levels of parasitemia, this can be done via thick smears, but at higher levels smears should be examined at several oil immersion fields.
- Blood cultures should be obtained due to possible presence of coincidental bacterial infection (e.g. Typhoid).
- Should not have parasites in blood after 4-5 days of treatment >>> if there are, then organism is chloroquine resistant.





Left image: Plasmodium falciparum, ring forms. Right image: Plasmodium falciparum diagnostic sausage or banana-shaped gametocyte.

Initial Evaluation of Newly Diagnosed Case

- Percentage parasitemia
- Blood cell count
- Platelet count
- Electrolytes
- Creatinine levels
- Urea
- Ca2+
- Glucose
- Liver enzymes
- Coagulation tests
- In patients with severe malaria or symptoms of respiratory distress, lactate and blood gas analysis should be obtained.
- After treatment or before travel, **glucose 6-phosphate dehydrogenase** levels should be determined.

Differential of Flu-like Symptoms in Traveler

- Malaria
- Typhoid Fever
- Early Meningococcal disease
- Rickettsiosis (Typhus)
- Arboviral infections like Dengue Fever
- Leptospirosis

Treatment for Malaria

- Antimalarials are generally more toxic than antibiotics, but few serious adverse effects ordinarily.
- 5 broad categories:
    1. **Quinolines:** inhibit **Heme Polymerase**
        - **Quinine**
        - **Quinidine**
        - **Choloquine**
        - **Mefloquine**
        - **Primaquine**
        - **Tafenoquine**
    2. **Antifols:**
       Pyrimethamine
       Proguanil
       Trimethoprine
    3. **Artemesinin cpds:**
       Artemesinin
       Artemether
       Artesunate
    4. **Antibacterials:**
       Tetracylcines
       Sulfonamide
       Clindamycin
    5. **Atovaquone-proguanils:** combo of hydroxnapthquinone + dihydrofolate reductase inhibitor
- Patients with P. falciparum infections, mixed infections with PF, and infections with unidentifiable strain should be hospitalized.
- Patients with non-falciparum malaria should be given a course of **Chloroquine phosphate** (oral), followed by Primaquine phosphate if PV or PO (after screening for G6PD Deficiency).
- Patients with P. falciparum malaria acquired in Central America west of Panama Canal, Mexico, or Middle East can take Chloroquine – Falciparum malaria acquired anywhere else should be considered resistant.
- **Chloroquine** binds to heme with buildup of Chloroquine-heme complexes >>> irreversibly toxic. Resistance to Chloroquine is all over the world.

    1. resistance due to single mutation on **PfCRT (Plasmodium falciparum Chloroquine Resistance Transporter)** which allows pumping out of Chloroquine from lysosomal vacuole >>> allowing polymerization to occur >>> parasites are not eradicated.
- **Mefloquine** rare resistance in Asia and South America. Very effective, but major problem with side effects – particularly in those with depression or anxiety disorders >>> use Tetracylcine or Malarone instead. Also, severe nightmares.
- **Quinine** is drug of choice. For patients with CRPF, **Quinine** is best treatment for 3 days (or 7 days if acquired in SE Asia or Oceania due to demonstrated reduced sensitivity to Quinine). Regimen should be supplemented with Tetracyline, Clindamycin, or Pyrimethamine-Sulfadoxine to avoid recrudescence.
- Patients with decreased sensorium should be given IV Quinidine gluconate for 3 days with 5% glucose, and Tetracycline or Clindamycin, and should be monitored.
- Severe anemia >>> transfusion
- Hypoglycemia common in pregnant women, children and severe cases
- In non-immune patients with Falciparum malaria, mortality >60% with parasitemia >10%. Exchange transfusion or pheresis can be used to remove infected erythrocytes in cases of hyperparasitemia.
- Renal failure can occur secondary to dehydration. Peritoneal dialysis can be lifesaving for patients with ARF.
- Severe malaria can be complicated by non-cardiogenic pulmonary edema (ARDS) >>> poor prognosis.
- **Artemisinin:** very effective anti-malarial drug used in China since 371 AD, isolated from **Sweet Wormwood plant (Artemisia annua**), very effective against PF & PV (but Mefloquine is more effective against PV). Pretty cheap. Quickens parasite and fever clearance times, and shorter coma resolution than Quinine – works within 24 hours by acting on ring stages, whereas most other anti-malarials only work against schizont forms.
    1. can be used orally, parenterally or as sepository
- **Atovaquone-Proguanil (Malarone):** used for uncomplicated malaria, b/c no IV or sepository forms. Mechanism: inhibits parasite mitochondrial electron transport system at cytochrome bc1 and collapses mitochondrial membrane potential >>> kills parasite. Proguanil is a prodrug that normally functions as DHFR, but in this case it binds to Atovaquone and transports it across mitochondrial membrane.
- P. vivax and ovale need to use Chloroquine + primaquine (which kills liver stage), whereas with Falciparum & Malariae need only Chloroquine.
- Severe malaria always parenteral drug – Quinidine or Quinine (not available in US). Quinidine is much more cardiotoxic.
- **Primaquine** can be used for self-treatment of relapsing malaria.

Malaria Prophylaxis
- **Doxycycline:** problems is side effects like photosensitivity, Stevens-Johnson syndrome, and GI effects.
- **Primaquine:** good with minimal side effects, but not FDA approved yet.
- **Malarone:** most popular, few side effects, but very expensive.
- **Mefloquine:** very effective, but major problem with side effects – particularly in those with depression or anxiety disorders >>> use Tetracylcine or Malarone instead. Also, severe nightmares.

Prevention of Malaria
- Sleep in screened rooms, and use permethrin-treated bed nets
- Pyrethrum insect spraysor repellents with N, N-diethyl-m-toluamide (exposure to high levels for prolonged periods of time >>> neurotoxicity, particularly seizures in children, so use <35% DEET)
- Minimize exposed skin from dusk until dawn
- Use Mefloquine or Atovaquone-proguanil for prophylaxis (except in few areas where chloroquine resistant malaria has not been described). Alternative: Doxycycline.

Anti-malarial Drugs
- **Chloroquine phosphate (Aralen)**
- **Chloroquine sulfate (Nivaqine)**
- **Mefloquine (Larium)**
- **Quinine & Quinidine**
- **Primaquine phosphate**
- **Pyrimethamine-sulfadoxine (Fansidar)**
- **Tetracylcines: Tetracylcine, Doxycycline, Demeclocycline & Minocycline**
- **Macrolides: Erythromycin, Azithromycin, Clarithromycin**

- **Lincomycins: Clindamycin (Cleocin)**
- **Proguanil-Atovaquone (Malarone)**
- **Artemesinin (Artesunate & Artemether)**
- **Halofantrine (Halfan)**
- **Fluorquinolones**

Chloroquine

- Chloroquine phosphate (Aralen) & Chloroquine sulfate (Nivaqine) are 4-aminoquinolones that act on the erythrocytic stage of all species of Plasmodium.
- Drug of choice for treatment of susceptible strains of PF, PV, PO, and PM.
- Does not affect liver schizonts >>> doesn't prevent relapse of P. vivax or P. ovale >>> subsequent treatment with **Primaquine** should be used to avoid relapses.
- Primaquine should NOT be given to patients with **G6PD deficiency.**
- Adverse Effects: occur in 25%
    1. GI upset
    2. visual disturbances
    3. headache
    4. non-allergic pruritis
    5. Via IV, **hypotension** and **heart block** can also occur, particularly if drug is administered rapidly.

Mefloquine

- Mefloquine/**Larium** is a r-quinolinemethanol that acts on the erythrocytic stage of all species of Plasmodium - including most **Chloroquine-resistant P. falciparum (CRPF).** Does not affect liver schizonts.
- In US, recommended for prophylaxis not treatment, b/c effective treatment doses >>> CNS effects including seizures and psychosis. Can be confused with Cerebral Malaria.
- Contraindicated in patients with history of:
    1. epilepsy
    2. psych disorders
    3. cardiac conduction disorders (b/c can cause **QT prolongation**)
    4. use with caution with patients on Beta blockers
- In theory, Quinine & Quinidine may exacerbate the cardiodepressant effects of Mefloquine >>> so loading doses should not be given in patients who have recently taken Mefloquine.
- Teratogenic in rats, but has been taken in 2nd and 3rd trimesters w/o reported fetal malformations; 1st trimester effects are unknown. Should be avoided in pregnancy.
- Due to long half life, patients should wait 3 months after stopping Mefloquine before getting pregnant.

Quinine & Qunidine

- **Quinine Sulfate** (oral) and **Quinidine Gluconate** (IV) are **Cinchona Alkaloids.**
- Very effective anti-malarials against all 4 species, also active against the gametocytes of PV, PO, and PM
- First-line treatment for Chloroquine resistant malaria >>> should be used as empiric treatment in all cases where species is unknown:
- **Quinine** (650 mg 3x/day for 3-7 days)
    1. **Pyrimethamine-Sulfamethoxine, Tetracycline or Clindamycin (Cleocin)**
    2. For severe cases, IV **Quinidine gluconate + Tetracylcine or Clindamycin**
- Adverse Effects:
    1. **Cinchonism:** syndrome caused by high serum levels of Quinine or Quinidine, includes headache, nausea, abdominal pain, tinnitus, and transient loss of hearing; begins 48 hours after treatment is initiated, stops soon after treatment ends.
    2. **hypoglycemia:** give pregnant women IV glucose on these drugs
    3. **QRS widening** and **arrythmias** >>> parenteral Quinidine should be done with EKG monitoring.

Primaquine Phosphate

- Is an 8-aminoquinolone active against tissue schizonts and gametocytes
- Indication: prevent relapse of PV or PO
- Contraindicated in patients with **G6PD deficiency** (causes hemolysis), and in pregnancy

Pyrimethamine-sulfadoxine (Fansidar)

- Indication: treatment of **CRPF malaria**
- Not used for prophylaxis due to fatalities from serious cutaneous allergic reactions (**Stevens-Johnson Syndrome**) occurs in 1/20,00 patients with 5 weeks
- Patients with **G6PD deficiency** can develop hemolysis

Tetracyclines
- Types: Tetracycline, Doxycycline, Demeclocycline, Minocycline
- Indication: active against **CRPF malaria**; some activity against schizonts, but not enough to be used to prevent relapse.
- **Doxycycline (Vibramycin**) is used for prophylaxis in patients unable to take Mefloquine
- or in areas of Mefloquine resistance (Vietnam and Thai-Kampuchean border).
- Adverse Effects:
    1. GI intolerance
    2. **photosensitivity**
    3. **vaginal candidiasis** >>> women can treat with **Fluconazole**

Macrolides & Lincomycins
- Indication: active against erythrocytic schizonts of all species; Clindamycin + Quinine for treatment of **CRFP. Azithromycin** has been used prophylactically in trials.
- Adverse Effects: **Clostridium difficile** infection >>> can be managed by **Metronidazole.**

Proguanil-Atovaquone (Malarone)
- Indication: active against erythrocytic and extraerythrocytic schizonts. Atovaquone is highly effective against PF, but high recrudescence rate with development of resistance when used as monotherapy. So used in combo with Proguanil.
- Mechanism: inhibits mitochondrial electron transport.
- Adverse Effects: abdominal pain, diarrhea, nausea, coughing.

Artemisinin
- Derived from Chinese medicinal plant Qinghao (Artemisia annua)
- Rapidly acting anti-malarial effective against **multidrug resistant P. falciparum malaria**.
- Mode of delivery: IV, oral, suppository
- Not available in US

Halofantrine (Halfan)
- Is a phethrenemethanol derivative of an amine alcohol that requires fat for optimal absorption.
- Recrudescence is a reported problem after single dose treatment.
- Adverse effects: cough, pruritis, hemolytic anemia, QT prolongation, PR prolongation, Torsade de pointes. Use limited by side effects and cardiotoxicity.

Fluoroquinolones
- Have anti-malarial activity in vitro, but not proven effective in vivo.

Babesiosis
- Distribution: localized to only NE US (particularly Cape Cod, Martha's Vineyard, CT, & Long Island)
- Disease due to **Babesia microti,** which leads to infection of RBCs in wild and domestic animals with a malaria-like organism.
- Transmitted by **Ixodes ticks.** A **3 host tick**: hatches from egg >>> becomes larvae >>> feeds on animals such as mice and birds >>> molts into nymph stage >>> becomes active the following year >>> looks for another host to feed again >>> adult female feeds on **deer** and that's where males and females copulate. Deer is not a host – just site of mating and food.
- Hemolytic anemia, fever, hemoglobuinuria and malaria-like systems.
- Particularly problematic in people without spleens!
- Can have co-infection with **AIDS, Ehrlichiosis & Lyme Disease.**
- Diagnosiss: blood smear and PCR, look for **Maltese Cross** on blood smear – pathognomonic!
- Treatment: Clindamycin or Erythromycin + Quinine. **Atovaquone + Azithromycin** best treatement, particularly in AIDS patients.



Image of Babesisos: with **Maltese Cross!**

LECTURE #14: AFRICAN & AMERICAN TRYPANOSOMIASIS

Hemoflagellates/Kinetoplasts

- Have a single large organelle that is basically a mitochondria. Called a hemoflagellate because found in blood.
  1. **American Trypanosomiasis/Chagas' Disease: Trypanosoma cruzi,** vector is Reduvid bug
  2. **African Tropanosomiasis/African Sleeping Sickness Trypanosoma: Trypanosoma brucei gambiense,** vector is Tsetse fly
  3. **African Tropanosomiasis/African Sleeping Sickness: Trpanosoma brucei rhodesiense,** vector Tsetse fly
  4. Animal trypanosomiasis in Africa
  5. Leishmania: cutaneous & visceral (vector is Sandfly)

American Trypanosomiasis or Chagas' Disease

- Caused by protozoan Trypanosoma Cruzi. Vectors often called kissing bugs.
- Host response is just as important as treatment – original case (Bernice) resolved spontaneously.
- Cause pseudocysts filled with intracellular forms: round with nucleus and cigar-shaped body which is the kinteoplast. **Amastigote** – has no flagella.
- Distribution: from Mexico (or Southern US according to CDC) down into South America through Argentina. **Southern Cone Initiative:** a bunch of South American countries have gotten together to eradicate. Worst areas are:
  1. Panama
  2. Bolivia
  3. southern Mexico
- Vector: infected triatomine insect vector (or "kissing" bug)
- **Romana's sign** is a type of **Chagoma** (indurated erythematous lesion at site of entry) seen in acute phase of disease, refers to unilateral periorbital edema just after bug bite.
- Every nucleated cell in body can be infected by this organism.

Morphology of Trypanosoma Cruzi

- Large posterior staining kinteoplast
- Flagella is anterior


Flagellum
Nucleus
Kinetoplast
TRYPOMASTIGOTE
Flagellum
Kinetoplast
Nucleus
EPIMASTIGOTE
Nucleus
Kinetoplast
Flagellum
AMASTIGOTE

Fig. 1. Forms of *T.* (*S.*) *cruzi* found in nature. (Courtesy of Dr. J. P. Kreier.)

Above image: Stages of Trypanosoma cruzi: amastigote (intracellular vertebrate), epimastigote (invertebrate), trypomastigote (vertebrate, blood); metacyclic trypomastigote in insect rectum (not shown).

Transmission of Chagas’ Disease

- Normal transmission: bug bite, “kissing” bug bites at night (often lips or around eyes) typically kids.
- Other modes of transmission: blood transfusion, maternal milk, organ transplantation, lab accident, congenital, oral transmission through contaminated sugar cane

Life Cycle of Trypanosoma Cruzi

Life Cycle:


Triatomine Bug Stages
Human Stages
1 Triatomine bug takes a blood meal (passes metacyclic trypomastigotes in feces, trypomastigotes enter bite wound or mucosal membranes, such as the conjunctiva)
i
2 Metacyclic trypomastigotes penetrate various cells at bite wound site. Inside cells they transform into amastigotes.
3 Amastigotes multiply by binary fission in cells of infected tissues.
Trypomastigotes can infect other cells and transform into intracellular amastigotes in new infection sites. Clinical manifestations can result from this infective cycle.
d
4 Intracellular amastigotes transform into trypomastigotes, then burst out of the cell and enter the bloodstream.
5 Triatomine bug takes a blood meal (trypomastigotes ingested)
6 Epimastigotes in midgut
7 Multiply in midgut
8 Metacyclic trypomastigotes in hindgut
i = Infective Stage
d = Diagnostic Stage
CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx

An **infected triatomine insect** vector (or "kissing" bug) takes a blood meal and releases **trypomastigotes** in its feces near the site of the bite wound (Chagoma forms around lips or eyes of child that was bitten). Trypomastigotes enter the host through the wound or through intact mucosal membranes, such as the conjunctiva ❶. Common triatomine vector species for trypanosomiasis belong to the genera *Triatoma*, *Rhodinius*, and *Panstrongylus*. Inside the host, the trypomastigotes invade cells, where they differentiate into **intracellular amastigotes** ❷. The amastigotes multiply by binary fission ❸and differentiate into trypomastigotes, and then are released into the circulation as bloodstream trypomastigotes ❹. Trypomastigotes infect cells from a variety of tissues and transform into intracellular amastigotes in new infection sites. Clinical manifestations can result from this infective cycle. The bloodstream trypomastigotes do not replicate (different from the African trypanosomes). Replication resumes only when the parasites enter another cell or are ingested by another vector. The "kissing" bug becomes infected by feeding on human or animal blood that contains circulating parasites ❺. The ingested trypomastigotes transform into **epimastigotes** in the vector's midgut ❻. The parasites multiply and differentiate in the midgut ❼and differentiate into **infective metacyclic trypomastigotes** in the hindgut ❽.


Trypanosoma cruzi, amastigotes, in cell culture.

Clinical Presentation of Chagas' Disease

- Chagoma, indurated erythematous lesion at site of Reduvid bite 10-14 days later.
- Diagnosis often missed. In endemic areas up to 80% seropositive, but don't even remember being sick due to spontaneous resolution.
- Acute disease: most asymptomatic (can remain asymptomatic for 10-20 years), some have fever, malaise, sweating, myalgias, anorexia, lymphadenopathy, edema, hepatomegaly.
- Most patients asymptomatic, or:
    1. Chronic Phase
    2. **GI: megacolon, megaesophagus, mega-gall bladder** >>> any organ that is innervated by ANS with tubular cells can be affected.
    3. Cardiac/Chronic cardiomyopathy: **DCM, CHF, Apical aneurysm** (almost pathognomonic for Chagas!), Thrombo-embolic events, Electrophysiological abnormalities**.**
- Common EKG findings:
    1. **RBBB**
    2. **RBBB + anterior fasicular block**
- Right side of heart always more involved than left side.
- Kids that are very infected can die of meningoencephalitis or cardiac problems (arrhythmias, acute heart failure), and vasculitis.
- Prognosis: 2-5% mortality in kids, typically due to heart failure, seizures, or secondary infection. Most people go on to indeterminate period for 10-20 years, followed by onset of chronic symptoms.
- Every component of Immune System important in fighting this infection: ABs, T cells, B cells. As antibodies rise, parasitemia wanes, but have **disruption of ganglionic cells** due to surrounding inflammation (so any tubular structure in the body innervated by ANS can be affected!) >>> as patient goes into **chronic phase**, don't see parasites in blood, but see evidence of infection through PCR, and if patient is immunosuppressed get exacerbation of illness >>> so we know parasite is still there, but cant' see it. Important b/c patient will get worse with corticosteroids, HIV, or if patient donates blood, will transmit disease even though undetectable in blood.

Diagnosis of Chagas' Disease

- During acute phase can see Trypanomastigotes in blood
- **Xenodiagnosis:** take a lab Reduvid bug, have them feed on patient, 35-40 days later look at rectum of bug for parasites.
- Biopsy of various organs
- Serological tests for antibody – done here at Einstein
- Detection of parasite antigen



Left image: Trypanosoma cruzi in blood smear; note "C" shape and large posterior kinetoplast. Right image: Xenodiagnosis of Chagas' disease with Reduviid bug.

Specific Problems

- Transfusion Chagas' Disease
- HIV/AIDS: acts as OI in AIDS patients, have necrotizing encephalitis and acute myocarditis.

- Congenital Chagas' Disease
- Transplantation (organ and stem cell)

Treatment of Chagas' Disease

- **Nifurtimox & Benznidazole:** need to get from CDC. Both very toxic so add **Interferon gamma** (to arm macrophages to better kill intracellular parasites).
- Treat patients with acute disease, but not necessarily chronic cases (international panel recommends treatment for all cases).
- Other experimental drugs: Allopurinol, Antifungal Azoles

Prevention of Chagas'

- Avoid sleeping in dilapidated dwellings
- Insect repllents
- Mosquito nets
- Avoid blood transfusions in Latin America

African Sleeping Sickness

- Trypanosoma brucei rhodesians & gambiense are **kenteoplasts.**
- Distribution: endemic to **sub-equatorial Africa**
- Transmission:
    1. via **Glossnia** or **Tsetse Fly**
    2. **direct mechanical**
    3. congenital
    4. lab accident
- **Trypanosoma brucei gambiense/African Sleeping Sickness (Gambian or West African form):** evolves more slowly, over many years, is fatal untreated; human-fly-human cycle. Found in West and Central Africa. Manifests late, and can last for months to years. Diagnosis via node aspirate.
    1. **Glossnia palpalis**
- **Trpanosoma brucei rhodesiense/African Sleeping Sickness (Rhodesian or East African form):** kills host within weeks or months; maintained in wild animals, unless epidemics of disease, then human-fly-human. Found in East and Central Africa. Manifests early w/ more anemia, shock, myocarditis prior to death. Higher level of parasitemia. Diagnosis through blood.
    1. **Glosssnia morsitans**
- Unlike related species T. cruzi & Leishmania there are no intracellular forms.
- While morphologically identical, have different biological properties, b/c humans only important host for TBG, whereas animals infected by TBR.
- More likely to infect young men.
- At various stages, Trypomastigotes can be found in peripheral blood, lymphatics, lymph nodes, CSF, and neural tissue.

Morphology of T. brucei & T. Rhodesiense

- Two subspecies are morphologically identical
- They are both **kenteoplasts**
- Pleomorphic flagellates 15-30 microns x 1.5-3.5 microns
- Long, slender w/ undulating membrane and free anterior flagellum, or short, broad w/o free flagellum

Life Cycle of Trypanosomes

- **Blood forms/Trypomastigotes** are ingested by **Tsetse fly** >>> posterior midgut multiply by binary fission for 7-10 days >>> anterior foregut for 2-3 weeks >>> salivary glands replicate further >>> become **infective metacyclic trypomastigote** forms >>> fly bites human >>> trypomastigotes multiply by binary fission in human blood, lymph and extracellular space >>> invades CNS and continues to multiply.
- African Trypanosomiasis does NOT have an Amastigote phase (unlike American Trypanosomiasis)!

Life Cycle:


Tsetse fly Stages
Human Stages
1 Tsetse fly takes a blood meal (injects metacyclic trypomastigotes)
2 Injected metacyclic trypomastigotes transform into bloodstream trypomastigotes, which are carried to other sites.
3 Trypomastigotes multiply by binary fission in various body fluids, e.g., blood, lymph, and spinal fluid.
4 Trypomastigotes in blood
5 Tsetse fly takes a blood meal (bloodstream trypomastigotes are ingested)
6 Bloodstream trypomastigotes transform into procyclic trypomastigotes in tsetse fly's midgut. Procyclic tryposmatigotes multiply by binary fission.
7 Procyclic trypomastigotes leave the midgut and transform into epimastigotes.
8 Epimastigotes multiply in salivary gland. They transform into metacyclic trypomastigotes.
i
d
i = Infective Stage
d = Diagnostic Stage
CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx

During a blood meal on the mammalian host, an infected tsetse fly (genus *Glossina*) injects metacyclic trypomastigotes into skin tissue. The parasites enter the lymphatic system and pass into the bloodstream ❶. Inside the host, they transform into bloodstream trypomastigotes ❷, are carried to other sites throughout the body, reach other blood fluids (e.g., lymph, spinal fluid), and continue the replication by binary fission ❸. The entire life cycle of African Trypanosomes is represented by extracellular stages. The tsetse fly becomes infected with bloodstream trypomastigotes when taking a blood meal on an infected mammalian host (❹, ❺). In the fly's midgut, the parasites transform into procyclic trypomastigotes, multiply by binary fission ❻, leave the midgut, and transform into epimastigotes ❼. The epimastigotes reach the fly's salivary glands and continue multiplication by binary fission ❽. The cycle in the fly takes approximately 3 weeks. Humans are the main reservoir for *Trypanosoma brucei gambiense*, but this species can also be found in animals. Wild game animals are the main reservoir of *T. b. rhodesiense*.

Genetics of African Trypanosomes

- T. brucei contains 1000 genes capable of coding for **variant surface glycoproteins (VSG),** which are switched at a rate of 10^-2 to 10^-6 switches per generation >>> main mechanism of evasion of host immune responses.
- Only 1 VSG site is active at any given time.
- **Expression sites (ES)** occur 15-20 times in genome, all at subtelomeric locations. 3 types of DNA rearrangements are associated with ES switching:
  - duplicative transposition
  - telomere exchange
  - telomere conversion
- In addition to VSG genes, several upstream genes called **expression site-associated genes (ESAGs)** are also transcribed.
- Another feature of trypanosome gene is the phenomenon of **mitochondrial RNA editing**. The kinetoplast DNA is organized as interlocking supercoiled network of approximately 50 maxicircle molecules and few thousand minicircle DNA molecules. They encode small guide RNAs that serve as templates for insertion or deletion of **Uridines** in the primary RNA transcript. The maxicircle DNAs encode for a dozen different mitochondrial proteins.

Pathogenesis of Trypanosomiasis

- Blood forms increase exponentially over next 2 weeks >>> then disappears from bloodstream >>> only to return later on.
- **Antigenic Variation:** interval between waves of parasitemia is 1-8 days, with clinical symptoms accompanying each bout. Each new wave has a new antigenic variant (via VSG), that can evade host immune response.
- **B Lymphocyte Proliferation:**
    1. lymphadenopathy
    2. immune complexes
    3. anemia
    4. secondary infections dues to bacterial pneumonia or meningitis, or malaria
- Marked early **IgM response** >>> polyclonal B cell activation >>> production of wide array of antibodies including:
    1. **brain-specific autoantibodies**
    2. ABs to myelin basic protein
    3. ABs to ganliosides & cerebrosides
- Also, circulating immune complexes
- Cell mediated immunity, NO may be important in depression of T Cell responsiveness and generalized immunodepression.
- Main pathological lesions involve:
    1. CNS
    2. Posterior Cervical, Submaxillary, Supraclavicular, & Mesenteric Lymph Nodes
- **Lymphatic hyperplasia** w/ diffuse proliferation of lymphocytes, initial hemorrhage w/ large numbers of trypomastigotes >>> later nodes small and fibrotic.
- Progressive, chronic **leptomeningitis** w/ Morula cells
- Organism found in brain tissue & CSF, and lymphocytosis in CSF
- Can see: Glomerulonephritis, Myocarditis, Pericardial Effusion, Pulmonary Edema, and Hypoplastic bone marrow.

Clinical Manifestations of Trypanosomiasis

- Rhodesian infection is more fulminant and acute (weeks – 9 months), whereas Gambian infection can last for years.
- **Trypanosomal chancre** within 2-3 days at site of bite.
- Large, red, painful nodule in 1 week (7-10 cm), lasts 2 weeks
- Symptoms: intermittent fevers, chills, headaches, back pain, generalized lymphadenopathy, moderate hepatosplenomegaly, delayed deep hyperesthesia over tibia
- In Caucasians, can have erythema multiforme.
- Chronic, untreated Gambian disease: severe headaches, inability to sleep, progressive mental degeneration, tremors, psych manifestations (depression, suicidal tendencies, schizophrenia) >>> coma >>> death.
- In Gambian form: when nodes in **posterior cervical triangle** are enlarged, it is known as **Winterbottom's Sign.**

Lab Findings of African Sleeping Sicknes

- Anemia
- Thrombocytopenia
- Elevated ESR
- Elevated IgM in serum/CSF
- Trypanomastigotes in blood, CSF, LN

Diagnosis of Trypanosomiasis

- Serology and PCR – must use thick & thin smears and examine buffy coat!



Trypanosoma brucei rhodesiense in blood

Differential Diagnosis of Trypanosomiasis

- Malaria
- Typhoid Fever
- TB
- HIV

Treatment of African Trypanosomiasis

- Hemolytic stages or early stages:
  - **Suramin:** does not cross BBB
  - **Eflornithine (DFMO)**
  - **Pentamidine**
- Late stage with CNS involvement
  1. **Melarsoprol (Arsobal/Mel B):** an arsenic compound that crosses the BBB and can cause reactive arsenic-induced encephalopathy (RAS).
  2. **Eflornithine (DFMO):** inhibits ODC, the lead enzyme in polyamine pathway.
- Relapse can occur (indicated by continued high IgM levels or abrupt rise in IgM).

Pentamidine

- 10 IM injections given on alternate days.
- Effective against early stage TBG, less so for TBR, and ineffective against later stage of both organisms.
- Does not kill organisms outright.

Diminazene Aceturate (Berenil)

- Low side effects
- Significant therapeutic value.
- Effective against early stage TBR & TBG, and used in combo w/ Melarsoprol for late stage disease.

Suramin

- Early stage TBR
- Given in 5 IV injections
- Very long half life
- Binds to plasma proteins including LDL which trypanosomes avidly bind to and endocytose >>> slow decrease in parasite numbers.

Melarsoprol (Mel B or Arsobal)

- Can use to cure late stage CNS disease from TBR & TBG
- Series of 3 daily injections.
- Given IV.
- Mechanism: unclear.

- Toxicity: reactive arsenical-induced encephalopathy (RAS) >>> pulmonary edema & death in >50% cases within 48 hours. Occurs in 10% of patients. Co-administration of steroids can help.

Eflornithine (DFMO)

- Enzyme-activated inhibitor of ornithine decarboxylase (ODC), the lead enzyme of polyamine biosynthesis.
- Give IV 4 doses every 6 hours for 2 weeks.
- Short half life
- Costly and lengthy treatment
- Not trypanocidal, but blocks bloodstream division of trypanosomes.

LECTURE #15: LEISHMANIASIS

Types of Leishmaniasis

- **Visceral Leishmaniasis (VL or Kala-Azar):** fever, wasting, panctyopenia, HS, hyper-IgG
- **Cutaneous Leishmaniasis (CL):** skin ulcers
- **Mucosal Leishmaniasis (ML or MCL):** nasopharyngeal ulcers

Importance of Leishmaniasis

- Paradigm for studying cell mediated immunity, so important for scientific research.

Leishmaniasis

- Leishmania are hemoflagellates with a **promastigote stage in insect vector** and **amastigote stage in macrophages of vertebrate host** (humans).
- Leishmaniasis is a disease caused by protozoa of the *Leishmania* species, which is transmitted by the bite of a female **sandfly**. Clinically, Leishmaniasis is classified as:
    - Cutaneous Leishmaniasis (CL): skin ulcers
    - Mucocutaneous Leishmaniasis (ML or MCL): naso-pharyngeal ulcers.
    - Visceral Leishmaniasis (VL): fever, wasting, pancytopoenia, HS, hyper-IgG
- The prevalence of the disease is increasing, with estimates of 12 million people currently infected worldwide. Once thought of as a disease affecting only rural areas, the disease remains common in the face of increasing urbanization.
- Distribution: incidence is highest in tropical and subtropical regions where conditions are favorable for sandflies. Leishmaniasis is found in some parts of 88 countries within Central America, South America, Africa, India, the Middle East, Asia, southern Europe, and the Mediterranean.
    - Most Cutaneous leishmaniasis seen in Columbia, Brazil, Peru, Afghanistan, Iran, Iraq & Saudi Arabia
    - Visceral leishmaniasis is most common in Bangladesh, Brazil (epidemic in northeastern Brazil), India, Nepal, and Sudan (on-going epidemic since 1992).
- Transmission: sandfly bite.
- Of great importance is the social burden placed by the morbidity of the disease, which can cause severe deformities and disfigurment and lead to social isolation.
- Males are more commonly infected than females, with Visceral leishmaniasis in particular, having been shown to be twice as common in males.
- Opportunistic infection in AIDS patients.

Life Cycle of Leishmania Species

- Sandfly bites an infected animal (like a dog) >>> ingests blood infected with Leishmania >>> bites human and injects organism into skin >>> human is infected >>> another sandfly bites human and continues the cycle.
- The amastigote is an intracellular parasite that is ingested by fly >>> transforms into **promastigote** >>> colonizes the hindgut of fly >>> colonizes midgut >>> migrates anteriorly into foregut >>> then goes to fly's biting apparatus >>> transforms into **metacyclic Amastigote form** (change in surface membrane of promastigote that keeps it from being killed by complement in animal or human) >>> is injected into human.
- **Gp63 & LPG** on surface of organism bind complement and block membrane attack cascade of C5-C9 to avoid killing, and blocks reactive oxygen intermediates in macrophage.
- Deposits eggs and then dies within 2-3 months. Lifespan of adult female is 2-3 weeks.
- Environments vary: some sandflies are desert dwellers, but most like moist, damp environments such as forests.
- **Maxadilan:** is a polypeptide in sandfly saliva extremely potent vasodilator (7x more potent than Nitroglycerin).

- **L. chagasi** causes **Visceral Leishmaniasis** in **Brazil** >>> has lots of maxadilan >>> can get into bloodstream and go to various tissues all over the body. Whereas same organism in **Costa Rica** has lower maxadilan content leading to **Cutaneous Leishmaniasis**. So sandfly has marked influence on what kind of disease individual will present with.
- Flies also have important anti-clotting agent that keeps blood from clotting so that fly can feed on more blood in animal/human tissue.

Causal Agent:

Leishmaniasis is a vector-borne disease that is transmitted by sandflies and caused by obligate intracellular protozoa of the genus *Leishmania*. Human infection is caused by about 21 of 30 species that infect mammals. These include the *L. donovani* complex with 3 species (*L. donovani*, *L. infantum*, and *L. chagasi*); the *L. mexicana* complex with 3 main species (*L. mexicana*, *L. amazonensis*, and *L. venezuelensis*); *L. tropica*; *L. major*; *L. aethiopica*; and the subgenus *Viannia* with 4 main species (*L. (V.) braziliensis*, *L. (V.) guyanensis*, *L. (V.) panamensis*, and *L. (V.) peruviana*). The different species are morphologically indistinguishable, but they can be differentiated by isoenzyme analysis, molecular methods, or monoclonal antibodies.


Sandfly Stages
Human Stages
1 Sandfly takes a blood meal (injects promastigote stage into the skin)
2 Promastigotes are phagocytized by macrophages
3 Promastigotes transform into amastigotes inside macrophages
d
4 Amastigotes multiply in cells (including macrophages) of various tissues
d
5 Sandfly takes a blood meal (ingests macrophages infected with amastigotes)
6 Ingestion of parasitized cell
7 Amastigotes transform into promastigote stage in midgut
8 Divide in midgut and migrate to proboscis
i
i = Infective Stage
d = Diagnostic Stage
CDC
SAFER·HEALTHIER·PEOPLE™
http://www.dpd.cdc.gov/dpdx

Leishmaniasis is transmitted by the bite of female phlebotomine sandflies. The sandflies inject the infective stage, promastigotes, during blood meals ❶. Promastigotes that reach the puncture wound are phagocytized by macrophages ❷ and transform into amastigotes ❸. Amastigotes multiply in infected cells and affect different tissues, depending in part on the *Leishmania* species ❹. This originates the clinical manifestations of leishmaniasis. Sandflies become infected during blood meals on an infected host when they ingest macrophages infected with amastigotes (❺, ❻). In the sandfly's midgut, the parasites differentiate into promastigotes ❼, which multiply and migrate to the proboscis ❽.

Identificaiton & Classification of Leishmania Species

- Restriction endonuclease digestion of Kinetoplast DNA
- Isozyme patterns specific to species
- DNA-DNA hybridization techniques
- Site of growth of promastigote in sandfly
- Growth in culture
- Species specific Monoclonal antibodies
- PCR species specific primers

Immune Response to Leishmaniasis

- Protective immune response is CMI, no role for antibodies in fighting this disease >>> so, there is a spectrum of disease.
- VL & Diffuse Cutaneous Leishmaniasis: no CMI (no Delayed Hypersensitivity reaction), lots of parasites, lots of macrophages, few lymphocytes, no Lymphocyte Blast transformation >>> Montenegro skin test is negative.
- Cutaneous Leishmaniasis: fewer parasites, fewer macrophages, some lymphocyte blast transformation >>> Montenegro skin test is positive.
- Tuberculoid/ Leishmaniasis Recidivans: few parasites, few macs, LOTS of lymphocytes, lots of DH, lots of lymphocyte transformation >>> very positive Montenegro skin test.
- IL-4, IL-10 & TH2 confers susceptibility. IL-10 associated with disease progression in humans. IL-12 promotes TH-1 response. If person has good TH1 response, patient heals rapidly; if not, patient gets very sick!

Causative Organisms of Visceral Leishmaniasis

- **L. donovani:** India and East Africa
- **L. infantum:** southern Europe, northern Africa, Middle East, China
- **L. chagasi:** Western Hemisphere (probably same organism as L. infantum)
- **L. tropica:** old world
- **L. amazonensis:** new world in Central American and northern South America.
- **Post-kala-azar dermal Leishmaniasis (PKDL):** recurrence due to improper treatment

Epidemiology of Leishmaniasis

- **Canine:** Dogs in South America, Mediterranean, China, Brazil; Dogs >>> Foxes in Brazil; Central Asia: Jackals
- **Rodents** in East Africa (rats, gerbels, squirrels)
- India no reservoir; human hosts
- Congential, lab, person-to-person
- Immunosuppression: co-factor in HIV/AIDS; steroids; chemo; transplants

Visceral Leishmaniasis

- **Kala-azar**
- Mild visceral disease which does not progress
- Visceral disease as a component of **AIDS**
- **Sudanese disease** "killing disease" is very virulent **+ PKDL**
  severe burning feet
  gall bladder disease (Cholecystitis)
  congenital transmission common
  PKDL in 56% of cases within 56 days.

Clinical Presentation of VL

- Onset: gradual to abrupt
- Incubation: 3-8 months (can be years)
- **Fever**: double daily spikes that can be variable or intermittent, can be misdiagnosed as **Malaria**
- **Anemia:** very characteristic of this disease b/c RBCs are hemolysed, sequestration of RBCs by Spleen, hemorrhage, and marrow replacement.
- Leukopenia: **Eosinophils** are almost always absent, and low number of neutrophils.

- Low Platelets >>> bleeding.
- Hyperglobulinemia: CIC, RF, GN
- Hepatosplenomegaly: spleen usually enlarges before liver, and **Splenomegaly** is almost always seen with this disease.
- sometimes Lymphadenopathy
- **Grayish or blackish skin:** in African form usually hyperpigmented skin, whereas in Indian form skin is hypopigmented.
- VL, DCL & Lepromatous Leprosy all can look the same clinically >>> biopsy to differentiate.

Diagnosis of Leishmaniasis

- **Kinetoplast** makes diagnosis – have to see this, otherwise could be confused with Chagas, Toxoplasmosis or other diseases!
- **Formalin Gel Test:** not specific diagnostic test, but used frequently in field in countries where this disease is common.
- Demonstration of organism on Giemsa stained slides with bone marrow biopsy, splenic aspiration (diagnostic procedure of choice but highest risk), liver biopsy, buffy coat in blood (sometimes). Culture specimen in NNN medium. Do isozyme analysis, use species specific DNA probe and PCR, or Monoclonal antibodies.
- Serological Diagnosis
    - use antibodies with **IFA, ELISA, DAT.** Don't see ABs in CL >>> so negative, but will be positive in VL.
    - **DHR:** will be positive with CL, and negative with VL.

Treatment of Visceral Leishmaniasis

- **Pentavalent Antimony (Sb+5):** is gold standard for treatment, usually effective unless patient has resistant disease. Parenteral. Cardiotoxic & toxic to pancreas and other organs.
- **Amphotericin B:** highly effective, used with patients who fail treatment on PA. Used in India, b/c high resistance to PA, but has renal toxicities and is expensive. Parenteral.
- **Lipid formulatios of Ampho B (Ambisome):** more expensive, lower toxicities, and best treatment for AIDS patients. Parenteral.
- **Miltefosine:** highly active oral agent, but not FDA approved yet, least side effects.

Prevention of Visceral Leishmaniasis

- No immuno or chemoprophylaxis
- Vaccines not available
- Vector control
- Elimination of reservoir hosts
- Avoid sandflies, use DEET, and sleep with Permethrin impregnated bed nets

VL Association with HIV

- Co-infection with HIV reported in 31 countries
- Particularly common in Mediterranean
- See VL when CD4 count drops to <50 (sometimes <200).
- See a lot of involvement of rectum, large intestine, pulmonary tissues (none of which are common in VL w/o AIDS).
- Poor response to Antimony. Almost 100% response to **Amphotericin**, but relapse soon after treatment is stopped. Most effective treatment is probably using antiretrovirals to treat AIDS and bring CD4 count back up.

Distribution & Strains of Cutaneous Leishmaniasis

- Afghanistan (lots of cases), Brazil, Iran, Iraq, Saudi Arabia, Sudan & Syria
- Old World
    - **L. tropica:** urban disease, maintained in dogs & humans
    - **L. major:** rural disease, maintained by desert rodents, gerbils, rats
    - **L. aethiopica:** rock hyrax in Africa
    - **L. infantum & L. donovani**
- New World
    - **L. mexicana:** sp complex
    - **L. braziliensis:** sp complex
- Visceral disease is reported in Iraq, Iran & Saudi Arabia: visceral disease can be caused by L. tropica. LT can cause both CL and VL – currently being seen in soldiers coming back to US from Iraq.

Pathogenesis of Cutaneous Leishmaniasis

- Fly bites >>> in a few weeks itchy papule or nodule develops (1 cm) >>> if enough IFN-gamma and CMI then nodule heals, but if not, weeks to months later w/o CMI an ulcer will develop (up to a few centimeters in diameter) >>> in months with CMI L. major will heal, but L. tropica may take years to heal.
- LT tends to visceralize, so common practice of self-innoculation has been discontinued.

American CL

- Zoonosis
- L. braziliensis: rodents, can metastasize to mucous membranes
- L. panamensis: sloths
- L. guyanensis: sloths and anteaters
- L. peruviana: dogs
- L. mexicana: rodents
- L. amazonensis: rodents and marsupials

Diagnosis of Cutaneous Leishmaniasis

- Demonstration of organism on biopsy
- Culturing with NNN
- Isozyme analysis, or species specific DNA probes
- Serological Diagnosis: through IFA, ELISA, DAT – low or absent in CL; high in VL. DHR is positive in CL after a few months.

Treatment of Cutaneous Leishmaniasis

- **Pentavalent antimonials:** sodium stibogluconate & meglumine antimoniate
- **Amphotericin B:** very effective
- Pentamidine
- Paromycin
- Heat cuff

SURGERY OF THE

SKULL BASE



PAUL J. DONALD

Surgery of the Skull Base

Editor

Paul J. Donald, MD

Professor, Department of Otolaryngology—
Head and Neck Surgery
Director, UCDMC Center for Skull Base Surgery
University of California, Davis
Sacramento, California

Illustrations by Nelva B. Richardson

Lippincott - Raven
PUBLISHERS
Philadelphia • New York

Table of Contents

Contributing Authors
Preface
Acknowledgments

I Introduction

1 History of Skull Base Surgery 3
2 Surgical Anatomy of the Skull Base 15
3 Pathology of Skull Base Tumors 31
4 Pathophysiology of Skull Base Malignancies 51
5 Presentation and Preparation of Patients with Skull Base Lesions 73
6 Imaging of the Skull Base 87
7 Carotid Artery Assessment and Interventional Radiologic Procedures Before Skull Base Surgery 105
8 Nursing Care of Skull Base Surgery Patients 119
9 Intraoperative Neurophysiologic Monitoring 137

II Anterior Fossa Approaches

10 Transfacial Approach 165
11 Facial Degloving Approach 195
12 Extended Unilateral Maxillotomy Approach 207
13 Subcranial Extended Anterior Approach for Skull Base Tumors: Surgical Procedure and Reconstruction 239
14 Cranioorbital Approach 263
15 Extended Transfacial Subcranial Approach 287
16 Infratemporal Fossa-Middle Cranial Fossa Approach 309
17 Transmandibular Approach 341
18 Anterior Subcranial (Transbasal-Derome) Approach 347
19 Work-up and Management of the Internal Carotid Artery in Neoplastic and Vascular Lesions 359

III Posterior Fossa Approaches

20 Temporal Bone Resection 377
21 Transcervicomastoid Approach 409
22 Petroclival Approach 423
23 Evaluation and Management of Vestibular Schwannomas 443
24 Approaches to Jugulotympanic Paragangliomas 473

IV Midline Approaches

25 Extreme Lateral Transcondylar Approach to the Craniocervical Junction 491
26 Transoral Approach to the Clivus and Upper Surgical Spine 507
27 Management of the Vertebral Artery 533
28 Lesions of the Sella Turcica 555

V Adjunctive Considerations

29 Complications 585
30 Postoperative Management 599
31 Free Flaps in Skull Base Surgery 607
32 Reconstruction of the Skull Base with Regional Flaps and Grafts 623
Subject Index 641

SECTION I

Introduction

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 1

History of Skull Base Surgery

Paul J. Donald

One of the most exciting and challenging fields in modern medicine is the rapidly developing discipline of skull base surgery. Cranial base surgery, as described in this book, principally concerns those disease processes that assault the floor of the cranium. They may arise from the intracranial structures, take origin in the subcranial area, or be primarily of the bone itself. Often the problem, be it of neoplastic, inflammatory, vascular, traumatic, or congenital origin, affects the structures on both sides of this bony barrier. Surgery of the skull base is unique because by its very nature and complexity it requires the cooperation of at least two surgical disciplines in a coordinated way to execute a carefully planned and smoothly orchestrated sequence of interdependent procedures to attack lesions in the most intricate area of the body. The cooperative efforts of the head and neck surgeon or otologist and neurosurgeon need to be complemented by the skills of the reconstructive surgeon. Without the use of pedicled flaps and free vascularized tissue, the safe rebuilding of the cranial base area would not be possible and, as a direct result, manifold complications would arise.

The evolution of surgical techniques has been paralleled by explosive developments in diagnostic radiology. The innovations of computed tomography, magnetic resonance imaging, and, more recently, positron emission tomography have revolutionized our ability to delineate disease processes in the intracranial and extracranial compartments to a fine degree.

The history of skull base surgery is brief. It began with pioneers in neurosurgery and head and neck surgery who, with no blood transfusions or antibiotics, intrepidly attempted to correct selected lesions in this formidable area. It is not unusual to find an expression in a textbook of surgery written in 1896 that any lesion adjacent to the skull base was considered to be "inaccessible" (1). This has been the prevailing attitude over the decades, and is a mind set occasionally encountered even today.

ANTERIOR FOSSA AND PITUITARY SURGERY

Probably the earliest adventures into the skull base were related to pituitary gland surgery. According to McDonald and Laws (2), the first attempt at a pituitary operation was by Caton and Paul in 1893 (3). On advice from Sir Victor Horsley (Fig. 1), they approached a pituitary tumor in a patient with acromegaly by performing a temporal lobe decompression. They actually did not operate on the hypophyseal tumor per se. Horsley (4) himself did about ten resections of hypophyseal tumors by 1910, mainly for blindness. According to Landolt and Wilson (5), Horsley's first transfrontal operation in 1899 predated Caton and Paul's. He used a transfrontal route that differs little from the approach used for such tumors today. Anterior transfrontal subdural techniques were demonstrated experimentally by Krause (1) and Kil-liani (6) in the first decade of the 20th century and in 1912. Frazier (7) (Fig. 2) finally used this approach on a patient.

An extracranial assault on the pituitary was first described by the Italian surgeon Giordano (8). His approach involved the construction of an osteoplastic flap comprising the frontal sinus and the nose. All the intranasal structures were removed as the approach to the pituitary was made. In 1907, Schloffer (9) did probably the first purely transnasal excision in which he reflected the external nose to one side, removed the septum and turbinates, and went transsphenoid to remove the gland. In 1910, Von Eiselsberg (10) used a similar approach to Schloffer's, through a so-called "inverted tuning fork incision" (Fig. 3).

In 1909, Cushing (11) (Fig. 4) described his first attempt at the transnasal approach to the pituitary. In 1914, he described the sublabial approach and many of the features of the transseptal transsphenoidal operation done today. He used a submucous resection of the nasal septum, thanks to the work of Killian (12), preserving the turbinates and nasal function, a technique in marked contrast to the destructive procedures of Schloffer and Von Eiselsberg. Cushing used this route to the hypophysis for about 20 years. He then apparently abandoned the approach because of excess bleeding and went back to the transcranial route.

P. J. Donald: Department of Otolaryngology—Head and Neck Surgery, and Center for Skull Base Surgery, University of California, Davis Medical Center, Sacramento, California 95817.



FIG. 1. Sir Victor Horsley. (From Horrax GT. Neurosurgery: an historical sketch. Publication no. 117 of the American Lecture Series. In: DeBakey ME, Spurling RG, eds. *American lectures in surgery.* Springfield, IL: Charles C Thomas Publisher, 1952:61.)

FIG. 2. Charles H. Frazier. (From Horrax GT. Neurosurgery: an historical sketch. Publication no. 117 of the American Lecture Series. In: DeBakey ME, Spurling RG, eds. *American lectures in surgery.* Springfield, IL: Charles C Thomas Publishers, 1952:78.)



FIG. 3. A: Von Eiselsberg's incision, one of the earliest subcranial approaches to the pituitary. B: Using this incision, the nose is reflected to the side; the septum and turbinates are resected and the sphenoid sinuses exposed. (From Horrax GT. Neurosurgery: an historical sketch. Publication no. 117 of the American Lecture Series. In: DeBakey ME, Spurling RG, eds. *American lectures in surgery.* Springfield, IL: Charles C Thomas Publishers, 1952:3.)



FIG. 4. Harvey Gushing. A: In the Hunterian Laboratory, Baltimore, Maryland, in 1912. B: With Otfrid Foerster, 1930 (Gushing to the left of Foerster). (From Horrax GT. Neurosurgery: an historical sketch. Publication no. 117 of the American Lecture Series. In: DeBakey ME, Spurling RG, eds. *American lectures in surgery.* Springfield, IL: Charles C Thomas Publishers, 1952:73 **[A],** 105 [B].)

At the same time that Gushing described the transnasal route to the pituitary, a similar approach was being used by the Viennese otolaryngologist, Oskar Hirsch (13,14). Initially, the procedure was done entirely transnasally in three stages (see Fig. 3). Eventually, in 1911, he combined the stages through a midline sublabial approach. Hirsch emigrated to the United States in the 1930s and, in 1952, published his results (15) of 425 such procedures, with a 65% success rate and a 5.4% mortality rate.

Subsequent developments in skull base surgery occurred on a number of different fronts. The first recorded anterior craniofacial resection for a tumor was by Dandy (Fig. 5) in 1941 (16). While removing an orbital tumor through an anterior cranial fossa approach, he entered the ethmoid bloc in an attempt to improve exposure and achieve complete resection. In 1943, Rae and McLean (17) reported a transorbital/transcranial removal of a retinoblastoma. However, the landmark article in anterior cranial base surgery that involved a coordinated transfacial and transcranial approach to tumor removal was published done in 1954. Klopp, a head and neck oncologic surgeon from Washington, DC, teamed up with Smith and Williams (18) to do a planned procedure to remove what was described as a cancer of the frontal sinus. The author found that his resection was not well accepted by his peers—not an uncommon finding in the early days of skull base surgery, as well as in many other innovative procedures that have been attempted through the history of medicine. Even the pioneering Semmelweis was committed by his colleagues to an insane asylum for proselytizing the principles of antisepsis.

The definitive report that truly launched skull base surgery for malignant disease was a paper by Ketcham et al. on their

FIG. 5. Walter E. Dandy. (From Horrax GT. Neurosurgery: an historical sketch. Publication no. 117 of the American Lecture Series. In: DeBakey ME, Spurling RG, eds. *American lectures in surgery.* Springfield, IL: Charles C Thomas Publishers, 1952:93.)


Surgical approach
Frontal sinus
Line of bony resection
Crista galli
Cribiform plate
Incision
brain
Chisel
Sphenoid sinus
A
Exposed dura
Line of bony resection
incision
Palate
Transected zygomatic arch
Reflected skin flap
B

FIG. 6. The anterior skull base approach as described by Ketcham et al. A: Transfacial approach. B: Transcranial approach. (From Ketcham AS, Chretien PB, Schour L, Herdt JR, Ommaya AK, Van Buren JM. Surgical treatment of patients with advanced cancer of the paranasal sinuses. In: *Neoplasia of the head and neck: a collection of papers presented at the seventeenth annual Clinical Conference on Cancer, 1972.* Sponsored by and held at the University of Texas System Cancer Center, M. D. Anderson Hospital and Tumor Institute, Houston, Texas. Chicago: Year Book Medical Publishers, 1974:192.)

experience with 19 patients who had an anterior craniofacial resection for cancer of the nasal cavity and paranasal sinuses (19). They evaluated 30 patients with advanced paranasal sinus cancer, 22 of whom were failures of past surgery or irradiation. Six of the patients were rejected for surgery because of radiographic evidence of erosion of the sphenoid ridge or pterygoid plates. Two refused surgery, and three were considered incurable at the time of craniotomy because of brain invasion or cranial floor involvement in the region of the optic chiasm. The anterior craniotomy and Weber Fergusson exposure they used are the basis for many anterior fossa approaches today (Fig. 6). Of the 19 patients operated on, 7 were not cured of their disease, 9 were disease free at 2 to 75 months' follow-up, and 3 died of other causes. By 1966, the same group reported on the complications experienced in a group of 31 patients operated on over a 10-year period (20).

FIG. 7. A. D. Cheesman, a head and necK surgeon and pioneer in skull base surgery who described the "key hole" craniotomy for tumor exposure.



FIG. 8. Paul Tessier, a plastic surgeon, the father of modern craniomaxillary surgery for congenital anomalies.

The 3-year and longer survival rate in this group was 61%. Approximately 80% of patients sustained some form of complication. In 1976, Sisson et al. (21) reported on their 15-year experience with craniofacial resection for sinus malignancies. They had used craniofacial resection for only 8 cases in a series of over 100 malignancies of the sinuses. Three of these patients died of recurrent disease, three were long-term survivors (2-8 years), and two were being followed and were disease-free for less than 1 year. In 1973, Millar et al. (22) reported on three cases of ethmoid cancer done in Australia. In 1980, Bridger (23), also from Australia, reported on 15 cases of craniofacial resection for tumors at this same site. In Bridger's series, seven patients were alive and disease free at 2 years or more. In 1986, Cheesman et al. (Fig. 7) from Great Britain reported their 10-year experience with craniofacial resection for ethmoid carcinomas with intracranial spread using a small "window craniotomy" (24). They had a 60% 5-year cure rate.

Attempts were made to improve the exposure of the anterior fossa, especially in its most posterior extent. This often was difficult to achieve without severe retraction of the frontal lobes using the standard craniotomy. Based on the removal of a frontoorbital bandeau used in craniofacial surgery for congenital craniomaxillary anomalies developed by Tessier et al. (25) (Fig. 8) and the low frontoorbital technique for sphenoethmoid tumors described by Derome et al. (26), various skull base surgical teams devised more direct approaches. The extended anterior subcranial approach was developed by Raveh (Fig. 9) in 1978 to manage intracranial trauma (27) and then adapted it to tumor resection (28), and is excellent for midline lesions. A wider exposure was afforded by the technique developed by Maniglia and Ramina (29), in which the entire frontal bandeau was removed.



FIG. 9. Joram Raveh, a head and neck and maxillocranial surgeon who described the unique transcranial subcranial approach to the anterior midline skull base.

FIG. 10. Edwin W. Cocke, Jr., one of the founders of the Society for Head and Neck Surgeons, who in his mid-70s described a novel approach to the skull base through a Le Fort I osteotomy.

Many others, including Janecka, Cocke (Fig. 10), Robinson, Panje, and Catilano, have produced variations on these midline approaches, many of which are described in detail in this book.

POSTERIOR FOSSA-ACOUSTIC TUMORS

Another major area in skull base surgery development concerns lesions of the posterior cranial fossa. In the early 20th century, the removal of acoustic neuromas was first done in a systematic manner by Harvey Gushing, the previously mentioned skull base pioneer in pituitary surgery. According to House (30), the early reports of removal of this tumor were "meager and sketchy," and the surgery itself was usually incomplete and attended by a high mortality and morbidity rate. Horsley, Krause, and Von Eiselsberg (30) were names frequently associated with these early attempts. In London in 1894, Ballance (31) and Beevor reported the removal of an acoustic tumor with a favorable result. In America the year before, Starr and McBurney (32) teamed up for a posterior fossa exploration for such a tumor, but were unsuccessful. In the years before Gushing's resections of these lesions, a common practice was to insert a dissecting finger between the tumor and the pons in an attempt to enucleate it. In his own report, Gushing (33) found that with increasing experience, his mortality rate diminished from the death of his first patient to 20% after he had done 30 cases. This was in vivid contrast to the almost 100% mortality in other patients operated on by the surgeons of the time. However, Gushing's greatest contribution probably was the lucid and comprehensive description of the signs, symptoms, and natural history of acoustic tumors. Gushing's student, Walter Dandy (see Fig. 5), is reputed to be one of if not the greatest technological neurosurgeon of this century (30). Disappointed by the incomplete removals and frequent complications of Gushing's finger dissection technique, Dandy developed a more refined, painstaking removal of the tumor and its surrounding capsule. He resected 23 patients in this fashion in his first 9 years of practice and had 5 complete cures, an unheard-of track record at that time (34). Dandy's 1942 description (35) of acoustic tumor removal remained the standard approach until the development of the operating microscope in 1961. Unfortunately, however, this technique resulted in a total facial nerve paralysis in every case. For a more detailed and fascinating account of the development of acoustic tumor surgery, House's excellent section in his two-volume monograph on acoustic tumors should be consulted (31).

The operating microscope was first used in clinical surgery by Nylen (Fig. 11) in 1921 (36) to drain an acute suppurative otitis media by myringotomy. This was a unilocular microscope that lacked the three-dimensional visualization surgeons enjoy today. Holmgren (37), who had been doing labyrinthine procedures for otosclerosis, quickly developed the binocular microscope for middle ear surgery in 1922. In 1953, the Zeiss Company produced the prototype of the operating microscope that is universally used today. From its original use in otology, the microscope rapidly became incorporated into ophthalmologic surgery, neuro-surgery, and finally plastic surgery—all specialties that were to become important elements of the skull base surgery team. The microscope revolutionized otology and was one of the single greatest catalysts to modern otologic and neurootologic surgery.

FIG. 11. C. O. Nylen, an otologic surgeon who was the first to describe the operating microscope.

FIG. 12. W. F. House, the first modern otoneurosurgeon.

However, it was not technology that spawned modern neurootology. Credit must undoubtedly be given to the courageous, pioneering genius of William House (Fig. 12). Disturbed by the disappointing results of the standard approach to acoustic tumors developed by Dandy, he strove to design an operation that would extirpate the tumor while saving the function of the facial nerve. After practicing on cadaveric specimens in a makeshift temporal bone laboratory that he and his brother, Howard, constructed in their garage, he set out to do the first otomicroscopic approach to an acoustic neuroma. Attempts using the transtemporal approach had been made in the past. In 1904, Panse (38) developed an approach through the temporal bone, beginning with a radical mastoidectomy, followed by removal of the labyrinth, cochlea, and facial nerve, done with a mallet and gouge. Heavy bleeding and cerebrospinal fluid leakage predictably accompanied these procedures. Buix, Zange, and Schmiegelow (30) were among the few surgeons over the next 13 years who performed a small number of these dangerous procedures through the ear. At this time, a few heroic surgeons (34) did a combined postoccipital and translabyrinthine procedure, but, because of the high mortality rate, this approach was discontinued.

In 1961, House and B. B. Doyle, a neurosurgeon, did the first resection of an acoustic neuroma using the operating microscope. Because it was unprecedented for an otolaryngologist to do this type of surgery, the neurosurgery community presented no little resistance to House's desire to remove this tumor. After considerable debate, the first otoneurosurgical skull base team did the operation through the middle fossa approach. The tumor was incompletely removed and a combined suboccipital and middle fossa transotic approach was unsuccessful on two successive occasions, and the patient died 6 years later. The middle fossa appeared at the time to be a good route for facial nerve exposure, but inadequate for tumor removal. After eight attempts at the middle fossa route, sometimes accompanied by the suboccipital approach, House decided to redesign the operation and modified the original approach of Panse using the microscope, drill, and suction irrigation. He was able to preserve the facial nerve, the posterior canal wall, and the tympanic membrane. House and Doyle came to a serious disagreement over approaches, and their association dissolved in 1963. William Hitselberger (Fig. 13) then joined with House to form a solid, long-lasting relationship that was the nucleus of the first true skull base team.

The history of the evolution of acoustic tumor surgery would be incomplete without the story of the return to the modified Dandy approach by modern neurosurgeons and neurootologists. The transotic approach, by its very nature, destroys hearing; the removal of the bony and membranous labyrinth eliminates all vestiges of hearing on that side. In days gone by, when by the time the diagnosis was made most patients had little or no useful hearing in the affected ear, the loss of remaining hearing acuity was of little consequence (a position voiced by numerous otologists even today). As clinicians became more aware of this diagnosis, and computed tomography and magnetic resonance imaging improved, their ability to detect small tumors in patients whose hearing was intact markedly improved. Hearing preservation now became more important.



FIG. 13. William Hitselberger, the neurosurgeon who with House created the first skull base surgery team in North America.



FIG. 14. Mansfield F. W. Smith, an otologist who was among the first to adapt the posterior fossa approach to acoustic tumor removal and preserve hearing.

The reactivation of interest in the suboccipital retrosigmoid approach was stimulated by a desire to salvage hearing. The translabyrinthine approach developed by House preserved facial nerve function in most cases. Dandy, in his report in 1941 on 46 cases operated on with his modification of Gushing's suboccipital approach, reported that 34 of these patients had "good hearing" (36). However, most patients had no postoperative facial nerve function. Rand and Kurze (39, 40) modified Dandy's operation, preserving the facial nerve in 100% of cases when tumors were less than 2 cm in diameter, and reported these results in 1965. They called their operation the "suboccipital transmeatal approach." They also described preserving the vestibular and cochlear nerves in small intercanalicular tumors (41), but questioned the advisability of the operation in such small neoplasms. Sterkers (42) began hearing preservation surgery in 1969 and reported only a 10% favorable hearing result when he and his team used either the middle fossa or retrosigmoid approach. Smith (Fig. 14) et al. (43) modified the Rand procedure and began to popularize it in the early 1970s. Since then, considerable controversy has continued to surround the question of the optimal approach for acoustic neuroma removal, and the quality and utility of hearing when preservation is done.

MIDDLE FOSSA

A history of modern skull base surgery would be very much amiss without mention of one of the premier skull base surgeons of our time, Ugo Fisch (Fig. 15). With his background in head and neck oncologic surgery, he extended the limits of otologic surgery into the area of the infratemporal



FIG. 15. Ugo Fisch, a head and neck surgeon/otologist who developed the infratemporal fossa approach.

fossa. He and his neurosurgical colleague, Gazi Yasargil (Fig. 16), combined their skills to develop an approach through the infratemporal fossa to lesions that approached or invaded middle fossa dura. The uniqueness of this approach lay in that the lesion could be adequately exposed and resected with minimal temporal lobe retraction. Fisch is particularly noted for his pioneering work in the resection of juvenile nasopharyngeal angiofibroma with massive infratemporal fossa and middle fossa extension. He then turned his attention to resection of jugular foramen tumors, producing a workable classification of glomus jugulare tumors and a systematic solution to their extirpation.



FIG. 16. Gazi Yasargil, a neurosurgeon who along with Fisch developed the middle fossa/infratemporal fossa approach.

FIG. 17. Victor L. Schramm, a head and neck surgeon who pioneered the middle fossa/infratemporal fossa approach to skull base tumors.

A number of modifications of Fisch's approach have been made, the most notable by Victor Schramm (Fig. 17) and

FIG. 18. Laligam N. Sekhar, a neurosurgeon who together with Schramm created the first comprehensive skull base surgery program in North America.



FIG. 19, Dwight Parkinson, neurosurgeon and pioneer in cavernous sinus surgery.

Laligam Sekhar (Fig. 18) when they were together at the University of Pittsburgh. They were the prime movers of the first, organized, academically based skull base surgery center in the United States. Their refinements of Fisch's technique enabled wider exposure and more definitive resection of invasive meningiomas of the anterior and middle cranial fossae with extracranial extension and carcinomas arising in the upper aerodigestive tract invading the intracranial cavity.

FIG. 20. Ossama Al-Mefty, the neurosurgeon who developed the zygomaticofrontal approach to skull base lesions.



FIG. 21. Madjid Satnii, the neurosurgeon responsible in large part for the worldwide development of skull base surgery.

Forays into the middle fossa to resect invasive neoplasms inevitably led adventurous surgeons to chase such tumors into the cavernous sinus. Such resections were unheard-of until the courageous and innovative work of Dwight Parkinson (Fig. 19). In 1860, Holmes (44) was the first to describe a lesion at this site, a giant aneurysm; Bartholow (45) was the first to present an account of signs and symptoms of such lesions involving the sinus. Peet (46) gives Krogius credit for the first operation on a mass, presumably a neuroma, at this site, operated on in 1896. Parkinson's pioneering paper in 1965 (47) led the way for the further elaboration of anatomy and development of approaches by current experts such as Dolence, Kawasee, Rhoton, Sekhar (see Fig. 18), Al-Mefty (Fig. 20), Samii (Fig. 21), and others.

CENTRAL SKULL BASE

Surgeons have striven to elucidate more direct attacks on intracranial and skull base pathologic processes. The central skull base and adjacent intracranial structures are very difficult to approach through the three cranial fossae. The transo-ral approach to the upper cervical spine and clivus was first suggested by Scoville and Sherman (48) in 1951. A trans-oropharyngeal route was used in 1957 by Southwick and Robinson (49) to remove a tumor in the body of the second cervical vertebra (C-2). This was based on the experience of otolaryngologic colleagues who successfully and routinely used this route to drain the retropharyngeal space of abscesses at this site. However, the first description of the transoral approach applied to the cervicocranial junction did not



FIG. 22. Alan Crockard, a neurosurgeon who refined and perfected the transoral approach to the lower clivus and upper cervical spine.

appear until the presentation by Fang and Ong (50) at the PanPacific Surgical Society in 1962. In 1966, Stevenson et al. (51) used this approach to remove a clivus chordoma and expose the brainstem. In 1978, Haselden and Bryce (52) used this route to manage a basilar aneurysm. It remained for Crockard (53) (Fig. 22) to refine and perfect this approach for the optimal midline approach to the lower one third of the clivus and the upper two cervical vertebrae. Contributions to the transoral approach have been made by a number of head and neck surgeons. The median labiomandibular glossoptomy developed by Conley (54) provides excellent exposure, but is rarely necessary. The refinements described by Donald (55), Crumley and Gutin (56), and Woods et al. (57) have made the transoropharyngeal approaches easier and safer.

CONCLUSIONS

All of us who practice the challenging discipline of skull base surgery owe much to the early, pioneering efforts of our surgical predecessors. They have enabled us to apply techniques that previously were thought of as outrageously foolhardy, refine them, and use them to the betterment of our patients. Although it is an area of endeavor accepted by our medical peers, only time will reveal the verdict of society—beset by the restrictions of health maintenance organizations, the insurance industry, and governmental control—on the implementation and development of cranial base surgery. Skull base surgery offers a reasonable and significant chance for cure to patients previously abandoned as hopelessly incurable. Let us hope that we can continue to pursue this challenging and rewarding surgical enterprise.

REFERENCES

1. Johnson HC. Surgery of the hypophysis. In: Walker AE, ed. *A history of neurological surgery.* Baltimore: Williams & Wilkins, 1951:152.
2. McDonald TJ, Laws ER. Historical aspects of the management of pituitary disorders with emphasis on transphenoidal surgery. In: Laws ER, Randall RV, Kern EB, Aboud CF, eds. *Management of pituitary adenomas and related lesions with emphasis on transsphenoidal microsurgery.* New York: Appleton Century Crofts, 1982:1-2.
3. Caton R, Paul FT. Notes of a case of acromegaly treated by operation. BrMed./1893;2:1421.
4. Horsley V: On the technique of operations on the nervous system. *Br MedJ\906;2:4\l.*
5. Landolt AM, Wilson CB. Tumors of the sella and parasellar area in adults. In: Youmans JR, ed. *Neurological surgery.* Vol. 5. 2nd ed. Philadelphia: WB Saunders, 1982:3138.
6. Killiani OGT. Some remarks on tumors of the optic chiasm with a proposal how to reach the same by operation. *Ann Surg* 1904;40:35.
7. Frazier CH. An approach to the hypophysis through the anterior cranial fossa. *Ann Surg* 1913;57:145.
8. Giordano. *Compendia di chimrgia operatorio Italiana.* 2:100, 1897.
9. Schloffer H. Zur frage der operation en an der hypophyse. *Beitrage zur Klinische Chirurgie* 1906;50:767.
10. Von Eiselsberg AF. My experience about operation upon the hypophysis. *Transactions of the American Surgical Association* 1910;28:55.
11. Gushing H. Partial hypophysectomy for acromegaly: with remarks on the function of the hypophysis. *Ann Surg* 1909;50:1002.
12. Killian G. Die submucose fenesterresektion des nasenscheidewand. *Arch Laryngol Rhinol* 1904;16:362.
13. Hirsch O: Demonstration eines nach eines neuen method operiten hypophysentumors. *Verhandlungen der Deutschen Gesellschaft fur Chirurgie* 1910;39:51.
14. Hirsch O. Eine neuen methode der endonasalen operation von hypophesen-tumoren. *Wien Med Wochenschr* 1952;59:636.
15. Hirsch O. Symptoms and treatment of pituitary tumors. *Archives of Otolaryngology* 1952;55:268.
16. Dandy WE. *Orbital tumor: results following the transcranial operative attack.* New York: OskarPiest, 1941:168.
17. Rae BS, McLean JM. Combined intracranial and orbital operation for retinoblastoma. *Arch Ophthalmol* 1943;30:437.
18. Smith RR, Klopp CT, Williams JM. Surgical treatment of cancer of the frontal sinus and adjacent areas. *Cancer* 1954;7:991-994.
19. Ketcham AS, Wilkins RH, Van Buren JM, Smith RR. A combined intracranial facial approach to the paranasal sinuses. *Am J Surg* 1963;106:698-703.
20. Ketcham AS, Hoyle RC, Van Buren JM, Johnson RH, Smith RR. Complications of intracranial facial resection for tumors of the paranasal sinuses. *Am J Surg* 1966;! 12:591-596.
21. Sisson GA, Bytell DE, Becker SP, Ruge D. Carcinoma of the paranasal sinuses and craniofacial resection. *J Laryngol Otol* 1976; 1:59-68.
22. Millar HS, Petty PG, Wilson WF, Hueston JT. A combined intracranial and facial approach for excision and repair of cancer of the ethmoid sinuses. *AustNZJSurg* 1973;43:179-183.
23. Bridger PG. Radical surgery for ethmoid cancer. *Archives of Otolaryngology* 1980;106:630-634.
24. Cheesman AD, Lund VJ, Howard DL. Craniofacial resection for tumors of the nasal cavity and paranasal sinuses. *Head and Neck Surgery* 1986;8:429-435.
25. Tessier P, Guiot G. Rougerie J. Osteotomies cranio-naso-orbito-faciales hypertelorisme. *Annales de Chirurgie Plastique* 1967;12: 103-118.
26. Derome PJ, Akerman M, Anguez L, et al. Les tumeurs spheno-ethmoidales: possibilites d'exerese et de reparation chirurgicales. *Deurochirurgie* 1972;18[Suppl 1]:1-164.
27. Raveh J. Das einzeitge vorgehan bei der widerherstellung von frontobasal-mittelgesichtsfrakturen modifikatinen und behandlungsmodalitaten. *Chirurgie* 1983;54:677-686.
28. Raveh J, Laehach K, Speiser M, et al. The subcranial approach for fronto-orbital and anterior-posterior skull base tumors. *Arch Otolaryngol Head Neck Surg* 1993;! 19:385-393.
29. Donald PJ. Cranial facial surgery for head and neck cancer. In: Johnson JT, ed. *American Academy of Otolaryngology—Head and Neck Surgery: Instruction course,* Vol. 2. St. Louis: Mosby, 1989: 225-253.
30. House WF. A history of acoustic tumor surgery. In: House WF, Luetje

CM, eds. *Acoustic tumors.* Vol. I. *Diagnosis.* Baltimore: University Park Press, 1979:3^1.

31. Ballance C. *Some points in the surgery of the brain and its membranes.* London: MacMillan and Company, 1907:276.
32. McBurney C, Starr M. A contribution to cerebral surgery: diagnosis, localization, and operation for removal of three tumors of the brain; with some comments upon the surgical treatment of brain tumors. *American Journal of Medical Science C.V.* 1893;xx:361-387.
33. Cushing H. *Tumors of the nervus acusticus and the syndrome ofcere-bellopontine angle.* 2nd ed. New York: Hafner Publishing Company, 1917.
34. Dandy WE. An operation for the total removal of cerebellopontine angle (acoustic) tumors. *Surg Gynecol Obstet* 1925;41:129-148.
35. Dandy WE. Results of removal of acoustic tumors by the unilateral approach. *AMA Archives of Surgery* 1942;42:1026-1033.
36. Nylen CO. The microscope in aural surgery, its first use and later development. *Acta Otolaryngol Suppl (Stockh)* 1954;! 16:226-240.
37. Holmgren G. Some experiences in surgery for otosclerosis. *Acta Otolaryngol (Stockh)* 1924;5:460.
38. Panse R. Bin gliom des akustikus. *Arch Ohrenh* 1904;61:251-255.
39. Rand RW. *Microsurgery for acoustic tumors in Neurosurgery.* St. Louis: CV Mosby, 1969:126-155.
40. Rand RW, Kurze T. Facial nerve preservation by posterior fossa trans-meatal microdissection in total removal of acoustic tumors. *J Neural Neurosurg Psychiatry* 1965;28:311-316.
41. Rand RW, Dirks DD, Morgan DE, Bentson JR. Acoustic neuromas. In: Youmans JR, ed. *Youtnan's neurological surgery.* Vol. 5. 2nd ed. Philadelphia: WB Saunders, 1982:2967-3003.
42. Sterkers JM. Acoustic neurilemma otologic approaches. In: Sekhar L, Janecka I, eds. *Surgery of the cranial base.* New York: Raven Press, 1993:715-724.
43. Smith MFW, Miller RN, Cox DJ. Suboccipital microsurgical removal of acoustic neuromas of all sizes. *Ann Otol Rhinol Laryngol* 1973;82:407.

J4. Holmes T. Aneurysms of the internal carotid artery in the cavernous sinus. *Transactions of the Pathology Society, London* 1860-61 ;12:61.

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 2

продолжение

Surgical Anatomy of the Skull Base

Bernard M. Lyons

There is no more complex display of human anatomy than that which exists at the skull base. The surgery of tumors in this area can be difficult because of restricted access, distortion of normal anatomy, and the proximity of vital structures. The good results and low morbidity of most major series of skull base resections can be achieved only with a thorough understanding and respect for the anatomy in this region. It is essential to have a detailed, three-dimensional appreciation of skull base anatomy, and this can be gained only by spending many hours in the cadaver dissection laboratory. Tumors can distort and destroy already complex anatomy. Anatomic knowledge not only allows adequate tumor resection and preservation of vital structures, but enables the surgeon to maintain function and cosmesis better. Patterns of tumor spread can also be predicted if the clinician is familiar with the myriad basal foramina and preexisting pathways for tumor spread.

Discussion of anatomy in this chapter focuses on practical surgical anatomy, but detailed descriptions of vital structures are presented where appropriate. The three subdivisions of the skull base—anterior, middle, and posterior—are dealt with separately. Each subdivision is discussed in terms of the osteology of the skull base region and its foramina, the intracranial contents, and the subbasal regional anatomy. The latter is important when considering the type of surgical approach to the region.

ANTERIOR SKULL BASE

Osteology

The anterior cranial fossa is enclosed anterolaterally by the frontal bone. The frontal crest is a midline ridge anteriorly to which is attached the falx cerebri. This ridge can be quite prominent and can make separation of the dura and sagittal sinus tedious during anterior approaches (Fig. 1).

Most of the floor of the anterior cranial fossa is made up of the orbital process of the frontal bone, which is grooved by the frontal lobe gyri. It is mainly convex. The central portion of the anterior fossa is much deeper and is formed by the ethmoid bone, with the central area being the cribriform plate and the lateral being the fovea ethmoidalis—the roof of the ethmoid sinus. The anterior central cribriform landmark is the crista galli. Between this and the frontal crest lies the foramen cecum. Fibrous dural attachments usually plug this foramen, although rarely an anterior nasal emissary vein may persist into adult life. The cribriform plate has multiple perforations that transmit the olfactory nerve filaments and their dural and subarachnoid extensions. Tumor spread can occur through these perforations and nerve sheaths. Anterolaterally lies the cribroethmoid foramen, which transmits the anterior ethmoid artery and nerve. The posterior ethmoid artery passes the posterior portion of the plate.

The posterior anterior fossa floor is formed by the sphenoid bone. Centrally, behind the cribriform plate lies the planum or jugum sphenoidale, a flat plate of bone that is an important landmark for the sphenoid sinus and optic nerve in anterior fossa surgery (Fig. 2). This is bordered posteriorly by the chiasmatic sulcus, a groove for the optic chiasm (Fig. 3). Posterolateral is the lesser wing of the sphenoid, which roofs the optic canal and forms a sharp posterior bony border related to the lateral cerebral sulcus and sphenoparietal sinus. Medially, the lesser wing of sphenoid forms the anterior clinoid process, an important landmark for the optic nerve and supracavernous internal carotid artery (ICA). The sphenoid bone is surgically best considered with the anterior fossa, but anatomically it is part of the middle fossa.

Intracranial Contents of the Anterior Skull Base

The dura mater of the anterior fossa is firmly attached in the regions of the crista galli, cribriform plate, and lesser wing of sphenoid. Anteriorly, it forms the falx cerebri, which contains the superior and inferior sagittal sinuses. The supe-

---

B. M. Lyons: Department of Otolaryngology—Head and Neck Surgery, St. Vincent's Hospital, and Royal Victorian Eye and Ear Hospital, East Melbourne 3002, Australia.



FIG. 1. A: Osteoplastic flap approach to the anterior cranial fossa. Elevator is separating sagittal sinus from frontal crest. B: Diagram showing the anterior crest and superior sagittal sinus.

rior sagittal sinus drains the superior cerebral veins and the frontal diploic veins of Breschet and grooves the frontal crest. It is an important posterior relation to the frontal sinus (Fig. 4). The sagittal sinus usually can be safely ligated anterior to the coronal suture. In the region of the crista galli, the sagittal sinus is very tenuous or usually nonexistent.

The frontal lobes occupy the anterior fossa. The inferior surface of the frontal lobe is related to the roof of the orbit and sinonasal tract. As such, it may be involved by tumors in this area. It is marked by the olfactory sulcus, which is occupied by the olfactory bulb and tract (Fig. 5). The olfactory tract lies above the cribriform plate and planum sphenoidale (Fig. 6). The most medial frontal lobe gyrus is the gyrus rectus, a relatively "silent area" of the brain that can be resected if involved with tumor.

Subcranial Relationships of the Anterior Skull Base

The most important subcranial or extracranial relationships of the anterior fossa are the paranasal sinuses and the orbit. The detailed anatomy of the paranasal sinuses is beyond the scope of this chapter, but is dealt with adequately elsewhere (1).

The ethmoid sinuses are directly related to the orbit laterally, the anterior fossa superiorly, and the cribriform plate medially (Fig. 7). The sphenoid sinus is related superiorly to the anterior cranial fossa and is described in detail in the section on the middle fossa. The frontal sinus lies between the two plates of the frontal bone and is often used as a portal of entry in anterior craniofacial resection because of its direct proximity to the anterior fossa. Its thin posterior wall is related to the frontal lobe dura and superior sagittal sinus.

The orbit is important anatomically because it is often involved by tumors in the region and is a portal for the intracranial or extracranial spread of tumors. The bony orbit is related on three sides to the paranasal sinuses and superiorly to the anterior cranial fossa. It is roughly pyramidal in shape, although the orbital apex is closer to the medial wall than the lateral. The medial wall is made up of the orbital process of the frontal bone, and the lacrimal, ethmoid, and sphenoid



FIG. 2. Cadaver dissection demonstrating bone cuts for anterior craniofacial resection extending into sphenoid sinus and protecting optic nerves. *1,* Cribriform plate; *2,* sphenoid sinus; 3, optic nerve; *4,* internal carotid artery.



FIG. 4. Cadaver dissection demonstrating relationship of falx cerebri and sagittal sinus to the frontal bones. (Falx and sinus artistically enhanced). *1,* Sagittal sinus; *2,* falx cerebri; *3,* olfactory tracts.

bones. The foramina in this medial wall can be quite variable. The foramina for the anterior and the posterior ethmoid arteries lie 24 and 12 mm behind the anterior lacrimal crest, respectively. The optic foramen lies 6 mm behind that of the posterior ethmoid artery (2). The orbital floor is formed by the maxilla and anterolaterally by the zygoma. It contains the infraorbital groove. The lateral wall consists of the frontal, foramen caecum


Superior sagittal sin
Crista
Cribriform plate
Planum sphenoidale
Prechiasmal sulcus
Optic canal
Tuberculum sella
Anterior clinoid
Sella turcica
Posterior clinoid
Dorsum sella
Clivus

FIG. 3. Anterior cranial fossa and body of sphenoid.



FIG. 5. View of orbital surface of frontal lobes. *1,* Optic tract; *2,* gyrus rectus.



FIG. 6. The olfactory bulbs and tracts are seen here overlying the cribriform plate and planum sphenoidale. The orbit is dissected on both sides.



FIG. 7. Coronal section through orbit and ethmoid *(asterisk on* middle concha).

process of the maxilla and greater and lesser wings of sphenoid separated by the superior orbital fissure (Fig. 8). Anteriorly lies Whitnall's tubercle, to which the suspensory ligaments of the orbit attach.

It is important to realize that anteriorly the lateral wall is related to the temporalis muscle, but more posteriorly it forms the anterior wall of the middle cranial fossa and is thus related to the anterior horn of the temporal lobe. The roof is mainly formed by the orbital process of the frontal bone, with a small posterior contribution by the lesser wing of sphenoid. Detailed knowledge of the intraorbital anatomy is necessary only when removing intraorbital tumors. The lateral and superior anatomy is most important in these cases.

The motor nerves most at risk are the lacrimal nerve and the levator palpebrae superioris nerve, which arises from the superior division of the oculomotor nerve and runs medial to or through the superior rectus muscle.

Orbital apex anatomy is complex and important. It consists of three important portals: the optic canal and the superior and inferior orbital fissures. These portals are compartmentalized by the annulus of Zinn, a condensation of the tendons of the rectus muscles and levator palpebrae superioris.

The lateral part of the superior orbital fissure transmits the lacrimal, frontal, and trochlear nerves with the superior ophthalmic vein. Within the annulus, in the medial superior fissure, run the superior and inferior divisions of the oculomotor nerve and the nasociliary and abducens nerves. In the superomedial compartment of the annulus is the optic canal, which transmits the optic nerve and the ophthalmic artery. The optic canal in 40% to 80% of cases indents the lateral wall of the sphenoid, and in 7% to 13% can be encompassed completely in the posterior ethmoid cells (3).

The ophthalmic artery arises from the ICA medial to the anterior clinoid process. It runs medial to the optic nerve, within its dural sheath, and then crosses under the nerve and in the orbit lies lateral and then crosses superior to the optic nerve. In a small percentage of cases it may enter the orbit through a separate foramen (4).

The superior and inferior ophthalmic veins drain the orbit and communicate with facial veins and the pterygoid plexus. The inferior vein usually joins the superior ophthalmic vein at the orbital apex and passes through the superior orbital fissure, lateral to the annulus, and enters the cavernous sinus.

MIDDLE SKULL BASE

Osteology

The central portion of this region is formed by the body of the sphenoid. The tuberculum sellae is a transverse ridge that separates the chiasmal sulcus anteriorly from the sella turcica posteriorly. The sella turcica is a rounded hollow that cradles the pituitary gland (Fig. 9). The sides of the body of the sphenoid slope downward and laterally to meet the floor of the middle fossa. They are grooved by the sigmoid curve of the ICA as it courses from the petrous apex through the cavernous sinus. The anterior and posterior clinoid processes are important landmarks and areas of dural attachment. Occasionally a middle clinoid process exists that can be bridged to the anterior clinoid, so forming a caroticoclinoid foramen, through which passes the ICA (5).



FIG. 8. Orbital apex.



FIG. 9. A: Sphenoid bone from posterior view. *1,* Sella turcica; *2,* dorsum sellae; 3, tuberculum sellae; *4,* optic canal; 5, superior orbital fissure; 6, inferior orbital fissure; 7, foramen rotundum. B: From oblique view B.

The lateral recesses of the middle skull base are the middle cranial fossae proper. They are roughly triangular in shape. They are limited by the sphenoid ridge anteriorly and petrous ridge posteriorly. The anterior wall is formed by the greater wing of the sphenoid. The floor is made up of the greater wing of the sphenoid anteriorly and the petrous ridge of the temporal bone posteriorly. Laterally and between these two, the squamous temporal bone forms part of the floor. The lateral wall is made up of the greater wing of the sphenoid anteriorly and the squamous temporal bone posteriorly. The floor and lateral bony walls are grooved by the middle meningeal artery, curving anteriorly from the foramen spinosum to the region of the pterion, where it courses backward. The pterion is an H-shaped suture marking the confluence of the frontal bone, greater wing of the sphenoid, and the squamous temporal and parietal bones.

The superior surface of the petrous ridge has several important markings. Medially, near the apex, is an impression for the trigeminal ganglion, as it lies in Meckel's cave (Fig. 10). The ICA runs directly under this area and frequently its bony canal may be dehiscent. Dural elevation in this region should be undertaken with caution.

Laterally lies the flattened thin portion of the tegmen tympani, roofing the middle ear and mastoid. Anteromedially



FIG. 10. Middle fossa osteology. *1,* Foramen rotundum; *2,* foramen ovale; 3, foramen spinosum; *4,* carotid canal; 5, trigeminal impression.

lies the arcuate eminence, which overlies the superior semicircular canal. Further anteromedially lie the canals for the greater and lesser superficial petrosal nerves.

The arcuate eminence and the hiatus for the greater superficial petrosal nerve (GSPN) are important landmarks in middle fossa approaches to the internal auditory canal (IAC). The superior semicircular canal lies within an arc of 60 degrees to the IAC (6) or the GSPN can be traced to the geniculate ganglion and facial nerve in the IAC (7). The bone of the middle fossa floor may be dehiscent over the geniculate ganglion. The petrous ridge is longitudinally grooved by **the** superior petrosal sinus, where the tentorium cerebelli attaches.

Foramina of the Middle Fossa

Anteriorly lies the superior orbital fissure, which leads to **the** orbital apex. The foramen rotundum lies behind and inferior to the superior orbital fissure and transmits the maxillary division (VII) of the trigeminal nerve. The canal is approximately 4 mm long.

Posterolateral to the foramen rotundum is the foramen ovale, which transmits the mandibular division (VIII) of the trigeminal nerve, the accessory meningeal artery, the lesser superficial petrosal nerve (LSPN), and emissary veins to the pterygoid plexus.

The foramen spinosum lies posterolateral to the foramen ovale and transmits the middle meningeal artery and the meningeal branch of cranial nerve VII. There are two inconstant foramina in this region. The innominate foramen lies medial to foramen spinosum and may transmit the LSPN. The foramen of Vesalius lies medial to the foramen ovale in *409c* of skulls and transmits an emissary vein from the cavernous sinus (8).

The petrous apex articulates with the sphenoid and occipital bone medially and so forms a rounded opening to the carotid canal. This opening is the cranial counterpart of the foramen lacerum on the undersurface of the skull base.

Intracranial Contents of the Middle Fossa

The dural arrangement in the middle skull base is complex. It is densely adherent in the regions of the clinoid processes, the petrous and sphenoid ridges, and around the basal foramina. In the midline it forms a transverse dural plate, the diaphragma sellae, which bridges between the tuberculum sellae and dorsum sellae. It roofs the pituitary fossa and is perforated by the pituitary stalk. Laterally the dural plate forms the roof of a basin beside the body of the sphenoid, the cavernous sinus (Fig. 11).

Cavernous Sinus

The cavernous sinus is complex but critical to understand when performing skull base surgery. It is a plexus of veins that lies within the layers of the dura beside the sphenoid sinus. The lateral border of the roof is the anterior petroclinoid fold and the posterior border is the posterior petroclinoid fold.

The ICA is the main structure of importance within the cavernous sinus. It runs in an S-shaped curve forward in close relation to the lateral wall of the sphenoid sinus. It gives off two to six caroticocavernous branches. These supply the hypophysis and anastomose with middle meningeal branches.

The abducens nerve (VI) is the only cranial nerve within the cavernous sinus. This pierces the dura over the clivus and enters Dorello's canal. This leads to the cavernous sinus, where the nerve runs in close apposition to the lateral wall of the ICA.

The other cranial nerves are contained in the lateral wall of the cavernous sinus enclosed by two layers of dura. The oculomotor nerve (III) pierces the transverse plate of the dura, with accompanying sheaths of arachnoid and dura, and passes forward in the lateral wall. Anteriorly it divides into superior and inferior divisions. The trochlear nerve (IV) enters in the angle between the anterior and posterior petrocli-



FIG. 11. Cadaver dissection of the dura mater of middle cranial fossa and cavernous sinus. *1,* Anterior petroclinoid fold; *2,* posterior petroclinoid fold; 3, Meckel's cave; *4,* abducens nerve and Dorello's canal; 5, trochlear nerve.

noid folds and runs in the lateral wall. The ophthalmic (VI), maxillary (V2), and mandibular (V3) divisions of the trigeminal nerve also run in the lateral wall of the cavernous sinus. Cranial nerves III, IV, and VI are variably related to each other in the lateral wall of the cavernous sinus. Parkinson has described these variations in detail and outlined triangles that can be used to gain access safely to the cavernous sinus between these cranial nerves (9).

Anterior venous connections are the superior ophthalmic vein and the sphenoparietal sinus. Superiorly the cavernous sinus drains the superficial middle cerebral and inferior cerebral veins. Medially it connects with anterior and posterior intercavernous plexuses to form the circular sinus. Inferiorly, emissary veins pass to the pterygoid plexus. Posteriorly it drains into the superior and inferior petrosal sinuses and into the basilar plexus, between the dural layers over the clivus.

The motor and sensory roots of the trigeminal nerve pass underneath the free edge of the tentorium cerebelli and into Meckel's cave. This contains the motor root and the trigeminal (Gasserian) ganglion on the sensory root, which overlies the petrous apex and ICA. The ganglion is variably enclosed by subarachnoid space and cerebrospinal fluid. Cranial nerves VI, V2, and V3 pass from the ganglion into the lateral wall of the cavernous sinus. The motor route passes with V3 through the foramen ovale.

The temporal lobe fills most of the rest of the middle fossa and extends to a variable degree under the anterior cranial fossa.

Consideration of the venous drainage is important in middle fossa surgery. The inferior anastomotic vein (of Labbe) connects the superficial middle cerebral vein to the transverse sinus just before it becomes the sigmoid sinus. Interruption of this vein may result in cerebral infarction. The superior anastomotic vein (of Trolard) connects the middle cerebral vein to the superior cerebral veins.

The GSPN and the LSPN run along the floor of the middle fossa beneath the dura. The LSPN lies parallel but rostral to the GSPN. The GSPN parallels the course of the anterior edge of the petrous bone as it runs to the foramen lacerum to form the nerve of the pterygoid canal with the deep petrosal nerve. In the floor of the middle fossa it may be stretched during dural elevation, resulting in facial nerve paralysis. It is also a landmark for the ICA, which lies just deep and parallel to it in the temporal bone.

The temporal bone itself contains several important structures that should be considered at this point. The sigmoid sinus ends in the jugular bulb, which is considered in more detail with the posterior fossa. The facial (VII) andvestibulocochlear (VIII) nerves enter the porus acusticus and IAC. Cranial nerve VIII ends at the inner ear, whereas the facial nerve traverses the middle ear and mastoid. The eu-stachian tube arises at the protympanum and runs anterome-dially and inferiorly. The tube is one third bony and two thirds cartilaginous. Directly medial to the origin of the bony eustachian tube lies the ICA, and the bone may be dehiscent here. The eustachian tube needs to be traversed before reaching the ICA.

Internal Carotid Artery

Many vital structures are at risk in skull base surgery, but the most important is the ICA. Landmarks in the neck and temporal bone need to be recognized. The course of the ICA can be divided into four parts: cervical, intratemporal, cavernous, and supracavernous (Fig. 12).

The cervical portion of the ICA arises at the level of the third and fourth cervical vertebrae. The artery runs superiorly, posteromedial to the external carotid and deep to the digastric muscle and styloid apparatus. The styloid process and scroll of the temporal bone lead directly deeply to the carotid canal, which lies anteromedial to the jugular foramen. The glenoid fossa is a bony landmark for the higher parts of the

FIG. 12. A: Cadaver dissection demonstrating course of internal carotid artery. *1,* Sphenoid sinus; *2,* horizontal petrosal part; 3, supracavernous: *4,* area of fibrous ring; 5, vertical petrosal part; 6, abducens nerve; 7, foramen lacerum part; *8,* cavernous part. B: Diagram of course internal carotid artery.


3
6
2
8
1
7
5
4
A
Middle cerebral artery
Supraclinoid carotid
III
Cavernous carotid
IV
VI
Sphenoid sinus
Petrous carotid
Vertical carotid
Area of fibrous ring
Occipital condyle
Nasopharynx
Vertebral artery
Cervical carotid
Condyle of atlas
B

1C A at ens
branches.
The **intn**
ment. The ^
it is anchor

ICA at eustachian tube level. The cervical portion has no branches.

The intratemporal ICA has a vertical and a horizontal segment. The vertical segment begins at the carotid canal, where it is anchored very firmly by a fibrous ring and is difficult to mobilize (Fig. 13). It ascends for 5 mm and then turns anteromedially into the horizontal portion. Here it lies medial to the eustachian tube and anterolateral and slightly inferior to the cochlea. It then runs forward in the petrous bone at an angle of 45 degrees to the mid-sagittal plane. It is directly related anterolaterally to the eustachian tube in this portion. The middle fossa relationships of this portion have already been considered. This segment gives off caroticotympanic and pterygoid branches. The artery here is thin walled but



FIG. 13. Cadaver dissection of ascending internal carotid artery and fibrous ring. *1,* Fibrous ring; *2,* malleus; *3,* spine of sphenoid; *4,* mandibular division of the trigeminal nerve.

coated by a thick protective layer of periosteum and vessels.

The cavernous portion of the ICA has already been considered with the cavernous sinus. The artery in this segment is very thin walled.

The supracavernous portion of the ICA begins as the artery pierces the dura in the roof of the cavernous sinus medial to the anterior clinoid process. It passes backward below the optic nerve to the anterior perforated substance, where it ends in the circle of Willis. Branches are the ophthalmic, anterior and middle cerebral, posterior communicating, and anterior choroid arteries.

Subcranial Relationships of the Middle Skull Base

Lateral Subcranial Structures

The undersurface of the middle cranial fossa is the infratemporal fossa, and this provides access to medial skull base areas such as the nasopharynx. Many important structures lie in this area, but they lie deeply, protected by several bony and soft tissue barriers.

The first of these structures are the parotid gland and facial nerve (Fig. 14). The branch of the nerve most at risk in surgery of this area is the frontalis branch, and this can be protected by dissecting in a plane deep to the superficial layer of the temporalis fascia and so reflecting the nerve forward and downward. The nerve lies superficial to the fascia (10,11).

Two bony barriers then present themselves, the zygomatic arch and the condyle of the mandible (Fig. 15). The fan-shaped temporalis muscle arises from the temporal fossa and inserts onto the coronoid process of the mandible. When this is reflected downward, access is obtained to the infratempo-ral fossa proper. Care is needed on the deep surface because its blood supply, the deep temporal arteries from the maxillary artery, lie here and can be damaged. This may preclude the use of this muscle in reconstruction (Fig. 16).

A three-dimensional understanding of the infratemporal fossa is important, and this can be aided by the concept of the "subtemporal trapezoid" as described by Donald (12). All of the important structures emerging from the basal foramina are encompassed by imaginary lines joining (a) the base of the medial pterygoid plate anteromedially, (b) the articular eminence anterolaterally, (c) the occipital condyle and foramen magnum posteromedially, and (d) the mastoid tip posterolaterally (Fig. 17).

Immediately posterior to the styloid process lies the stylomastoid foramen, where the facial nerve exits the mastoid.



FIG. 14. Facial nerve dissection. 1, Superficial temporal artery; 2, frontalis branches of the facial nerve.



FIG. 15. Osteology of bony barriers to infratemporal fossa. *1,* Styloid process; *2,* vaginal process of temporal bone; 3, spine of sphenoid; *4,* glenoid fossa; 5, zygomatic arch.

From here the tympanic portion (vaginal process) of the temporal bone leads anteromedially, and just medial to its tip lies the carotid canal. Directly posterolateral lies the jugular foramen, where cranial nerves IX, X, and XI become intimately related to the great vessels in the neck. Posteromedial to the carotid canal lies the occipital condyle and under its lip, the hypoglossal canal, where cranial nerve XII exits into the neck.



FIG. 16. Reflected temporalis muscle demonstrating entry point of blood supply on its deep surface.

More anteriorly in the trapezoid lies the glenoid fossa. Directly medial to this lies (a) the petrotympanic fissure, where the chorda tympani exits, and (b) the spine of the sphenoid, which is an important landmark for the anteriorly situated foramen spinosum and middle meningeal arteries.

Drilling medially through the glenoid fossa leads straight into the bony eustachian tube and superiorly into the middle cranial fossa, because the bone here is very thin. Anteromedial to the foramen spinosum is the foramen ovale, where the mandibular division of the trigeminal nerve exists. Further medially lies the cartilaginous eustachian tube and more medially the carotid artery and foramen lacerum.

The orientation of these structures can be readily appreciated as three parallel lines running at 45 degrees to the midsagittal plane (along the axis of a line joining the mastoid tip to the medial pterygoid plate). The most superficial line incorporates the foramen spinosum, foramen ovale, and the lateral pterygoid plate. The middle line incorporates the eustachian tube and the deepest line the ICA and foramen lacerum (Fig. 18).

The bulk of the infratemporal fossa is occupied by the lateral and medial pterygoid muscles, which arise from the pterygoid plates and infratemporal surface of the skull. Intimately related to these are the branches of the mandibular division of cranial nerve V, the pterygoid plexus of veins, and the branches of the maxillary arteries. Deeper, arising from the skull base and cartilaginous eustachian tube, are the tensor and levator veli palatini muscles (Fig. 19). At the deepest, most anterior part of the infratemporal fossa lies the pterygoid process and, more anteriorly, the pterygomaxillary fissure. This leads into the pterygomaxillary fossa. The vidian nerve enters this through the vidian canal and the maxillary nerve through the foramen rotundum (Fig. 20). Branches of these two nerves interdigitate through the sphenopalatine ganglion. The maxillary artery enters the fossa between the two heads of the lateral pterygoid muscle.



FIG. 17. A: "Subcranial trapezoid." *1,* Medial pterygoid plate; *2,* occipital condyle; *3,* articular eminence; *4,* mastoid tip. B: Close-up view. *5,* Foramen ovale; *6,* foramen spinosum; *7,* carotid canal; *8,* jugular foramen; *9,* foramen lacerum.


LATERAL PTERYGOID
FORAMEN OVALE
FORAMEN SPINOSUM
SPHENOID SPINE
EUSTACHIAN TUBE
CAROTID
1
2
3

FIG. 18. A: Orientation lines at skull base. B: Orientation lines superimposed on skull. *Line 1,* Foramen ovale, foramen spinosum, styloid process; *line 2,* eustachian tube line; *line 3,* carotid canal, internal carotid artery, foramen cecum.

The pterygomaxillary fossa is a pathway for turnouts to spread into the infratemporal fossa. The inferior orbital fissure lies at the most anterior limit. This is formed by the greater wing of the sphenoid and the maxillary tuberosity.

Medial Subcranial Structures

Anteriorly, the sphenoid sinus is related to the middle skull base. The anatomy of this is important in respect to transsphenoidal approaches to the pituitary and clivus. The pneumatization of the sphenoid is highly variable and can influence the type of approach used. Sellar and presellar pneumatization allows ready access to the pituitary fossa (13). As mentioned previously, the ICA, optic nerve, and sometimes even the nerve of the vidian canal indent the lateral wall of the sphenoid sinus and may even be dehiscent or contained within the sinus.

More posteriorly in the midline lies the nasopharynx. This is lined by pharyngobasilar fascia that is suspended from the skull base and clivus. The clivus is formed by the basisphenoid and basiocciput, and directly posterior to this lies the vertebrobasilar artery and brainstem. The clivus is covered by dense periosteum, pharyngobasilar fascia, and mucosa. It is important to note that directly above the nasopharynx lies the foramen lacerum. This is plugged by fibrous tissue and cartilage, and directly above this lies the ICA in its canal, just before it enters the cavernous sinus.



FIG. 19. Intraoperative photograph of left-sided deep infratemporal fossa dissection. *1,* Lateral pterygoid plate; *2,* middle meningeal artery (tied); *3,* mandibular division of trigemi-nal nerve; *4,* temporal lobe; 5, remnant of glenoid fossa.



FIG. 20. Anterior face of sphenoid bone. *1,* Sphenoid ostium; *2,* vidian canal; *3,* foramen rotundum.

The lateral wall of the nasopharynx is made up of mucosa, pharyngobasilar fascia, and the superior pharyngeal constrictor muscle. The gap between the superior constrictor and the skull base is termed the foramen of Morgagni. This is a potential route for nasopharyngeal tumor spread. The potential space is largely filled by the eustachian tube and the tensor and levator palati muscles.

POSTERIOR SKULL BASE

Osteology

The anterior wall of the posterior fossa is made up of the posterior surface of the petrous bone laterally and in the midline by the clivus. The clivus is a flat, trapezoidal bone formed by the synostosis of the basisphenoid and basiocciput. The floor and posterior and lateral walls are formed by the occipital bone. The roof is made up of the tentorium cerebelli.

The cranial surface of the occipital bone is deeply grooved by the cerebellar hemispheres. The internal occipital crest runs vertically from the foramen magnum to the internal occipital protuberance. The crest marks the line of attachment of the falx cerebelli, which contains the occipital sinus. On each side of the internal occipital protuberance lies a horizontal groove for the transverse sinus. Anteroinferiorly from this is the deep groove for the sigmoid sinus ending at the jugular foramen. A sulcus for the inferior petrosal sinus lies between the clivus and the petrous apex anteriorly.

Foramina of the Posterior Fossa

On the posterior surface of the petrous temporal bone are two foramina. The first is the porus acusticus or opening of the IAC, which transmits the vestibulocochlear and facial nerves, nervus intermedius, and branches of the anterior inferior cerebellar artery (AICA) to the inner ear. The second is the vestibular aqueduct, lying posteroinferiorly to the IAC. It transmits the endolymphatic duct.

Below these two foramina lies the jugular foramen. This is formed by the occipital bone posteriorly and the sharp posteroinferior border of the petrous bone (processus jugularis) anteriorly. Posteriorly, the jugular foramen contains the termination of the sigmoid sinus and the jugular bulb. In the anterior and middle portions of the foramen, cranial nerves IX, X, and XI run through a connective tissue septum. The glossopharyngeal nerve lies most anteromedially. In this segment the inferior petrosal sinus also enters the foramen. It usually passes between cranial nerves IX and X, but its relationship to the cranial nerves is highly variable. It may even enter the internal jugular vein below the skull base. A posterior meningeal branch of the ascending pharyngeal artery frequently enters through the jugular foramen.

The hypoglossal canal lies inferior and medial to the jugular foramen. This transmits cranial nerve XII, a meningeal branch of the ascending pharyngeal artery, and the hypoglossal venous plexus. Foramina also exist for the mastoid and condylar emissary veins.

The foramen magnum provides a wide communication between the posterior fossa and the vertebral canal. Through it passes the dura, medulla oblongata, the spinal branches of the accessory nerve, the vertebral arteries, the posterior spinal arteries, and the apical ligament of the dens and membrane tectoria. Around it are attached the atlantooccipital membranes.

Intracranial Contents of the Posterior Fossa

The dura mater of the posterior fossa and tentorium cerebelli encloses the superior petrosal, transverse, occipital, and straight sinuses. The straight sinus is formed by the great cerebral vein of Galen and the inferior sagittal sinus. The midbrain, pons, medulla, and cerebellum lie within the posterior fossa. Thus, all of the exit zones of the lower ten cranial nerves lie in the posterior fossa. Of these, only the oculomotor nerve does not exit through the dura of the posterior cranial fossa. It enters the dura of the middle fossa, in the roof of the cavernous sinus, lateral to the posterior clinoid process. Only cranial nerves VII to XII, however, actually exit the cranium through the posterior fossa. Cranial nerves VII and VIII and the nervus intermedius pass through the porus acusticus, nerves IX, X, and XI through the jugular foramen, and XII exits via the hypoglossal canal.

The main arteries in the posterior fossa originate from the vertebral arteries. These ascend ventral to the roots of cranial nerves IX, X, and XII. They usually give off the posterior inferior cerebellar arteries before joining to form the basilar artery at the lower border of the pons. The basilar artery gives rise to the AICA, which pass to the inferior surface of the cerebellum and come into close relationship with cranial nerves VII and VIII in the cerebellopontine angle. This relationship, and also that of the AICA to the internal auditory meatus, is highly variable, as described by Mazzoni and Hansen, and Kim et al. (14,15). The basilar artery then gives rise to the superior cerebellar arteries and the posterior cerebral arteries, which form the posterior axis of the circle of Willis. Other branches are the pontine and, occasionally, labyrinthine arteries.

Subcranial Relationships of the Posterior Skull Base

Posterolateral Structures

Knowledge of anatomy in this area is important for surgery involving tumors of the cerebellopontine angle and vascular tumors of the temporal bone, or in far lateral approaches to the foramen magnum region.

This region is protected by the mastoid tip and the strong suboccipital musculature. The sternocleidomastoid and the digastric muscles arise from and deep to the mastoid tip, respectively. The occipital artery runs posteriorly deep to the



FIG. 21. Dissection of vertebral artery showing relationship to occipital condyle and brainstem. 7, Vertebral artery; *2,* occipital condyle partly drilled; *3,* spinal root of accessory nerve.



FIG. 22. Sagittal cadaver section showing relationship of clivus to basilar artery and pons.

mastoid tip. The splenius capitis and longissimus capitis lie deep to sternocleidomastoid. Posteriorly in the midline lies the trapezius and deep to this arises the semispinalis capitis. After these muscles are reflected off the superior nuchal line, the all-important suboccipital triangle is exposed. This triangle is bordered by the obliquus capitis superior and inferior and the rectus capitis posterior major. Within the triangle lie the dorsal ramus of the first cervical nerve and the vertebral artery with its venous plexus. The triangle is crossed by the great occipital nerve.

Dissection in this triangle allows mobilization of the vertebral artery and exposure of the occipital condyle, which can be drilled away to gain access to the foramen magnum and anterior brainstem.

Vertebral Artery

The vertebral artery arises from the subclavian artery and has four parts, cervical, foraminal, atlantic, and subarachnoid.

The cervical part runs up and backward between the longus colli and scalenus anterior to reach the transverse foramen of the sixth cervical vertebra.

The foraminal part of the artery ascends through the transverse foramina of the upper six cervical vertebrae, turning upward and laterally to enter the transverse foramen of the atlas. Its branches are to the spinal cord.

The atlantic part of the vertebral artery curves backward and medially behind the lateral mass of the atlas and onto the upper surface of the posterior arch of the atlas (Fig. 21). This portion is accessible through the suboccipital triangle and is surrounded by a plexus of veins. Branches from this part are to the suboccipital muscles. It then enters the subarachnoid space below the posterior atlantooccipital membrane.

The subarachnoid part of the vertebral artery has been considered with the posterior fossa. Branches are meningeal, posterior and anterior spinal, and the posterior inferior cerebellar artery.

Midline Posterior Skull Base

This area has partially been dealt with in the section on the middle fossa. It is important in approaches to the clivus, the basilar invagination of the odontoid process, and vertebrobasilar aneurysms.

The nasopharyngeal area is covered anteriorly by mucous membrane and dense periosteum overlying the clivus and upper cervical spine. Of particular concern are the atlantooccipital and atlantoaxial joints. The anterior arch of the atlas can be removed to expose the odontoid process. Deep to the clivus lies dura and the vertebrobasilar arterial system, with the brainstem immediately posterior (Fig. 22). Dissection too far laterally in the region of the lower clivus and occipital condyle may damage the hypoglossal nerve and, of more concern, the ICA.

REFERENCES

Ritter FN. *The paranasal sinuses: anatomy and surgical technique.* St. Louis: CV Mosby, 1978.

Neal GO. External ethmoidectomy. *Otolaryngol Clin North Am* 1985;18:55-60.

Van Alyea OE. In discussion of operation on the sphenoid. *Transactions of the American Academy of Ophthalmology and Otolaryngology* 1949;53:542-543.

4. Lang J. Structure and postnatal organization of heretofore uninvestigated and infrequent ossifications of the sella turcica region. *Acta Aval* 1977;99:121-139.
5. Lang J. The anterior and middle cranial fossae including the cavernous sinus and orbit. *Surgery of cranial base tumors.* New York: Raven Press, 1993:106-121.
6. Fisch U. Neurectomy of the vestibular nerve: surgical techniques, indications and results obtained in 70 cases. *Rev Laryngol Otol Rhino! (Bord)* 1969;! 1:661-672.
7. House WF. Surgical exposure of the internal auditory canal and its contents through the middle cranial fossa. *Laryngoscope* 1961;71:1363-1385.
8. Lang J. *Clinical anatomy of the head, neurocranium, orbit and crania-cervical regions.* New York: Springer-Verlag New York, 1983.
9. Parkinson D. A surgical approach to the cavernous portion of the carotid artery: anatomical studies and case report. *J Neurosurg* 1965:23:473-482.
10. Pitanguy I, Ramos AS. The frontal branch of the facial nerve: the importance of its variations in face lifting. *Plast Reconstr Surg* 1966;38:352-356.
11. Liebman E, Webster RC, Berger AS, Dellavechia M. The frontalis nerve in the temporal brow lift. *Arch Otolaryngol* 1982;108:232-235.
12. Donald PJ. *Head and neck cancer: management of the difficult case.* Philadelphia: WB Saunders, 1983:284.
13. Hardy J, Maina G. Microsurgical anatomy in transphenoid hypophy-*SKtomy.JNeumlSci* 1977;21:151-153.
14. Mazzoni A, Hansen CC. Surgical anatomy of the arteries of the internal auditory canal. *Archives of Otolaryngology* 1970;91:128-135.
15. Kirn HN, Kin YH, Park IY, Kirn GR, Chung IH. Variability of the surgical anatomy of the neurovascular component of the cerebellopontine angle. *Annals of Otology. Rhinology, Laryngology* 1990;99:288-296.

BIBLIOGRAPHY

Hollinshead WH. *Anatomy for surgeons.* Vol 1. *The head and neck.* 3rd ed. Philadelphia: Harper and Row, 1982. *Gray's anatomy.*
35th ed. Edinburgh: Langman, 1973.

продолжение

CHAPTER 3

Surgery Skull Base. Edited by Paul Donald,-Lippincott-Raven Publishers, Philadelpia, 1998.

Pathology of Skull Base Tumors

Regina Candour-Edwards, Silloo B. Kapadia, and Leon Barnes

INTRODUCTION

Histology

The complex diversity of tissues that interface the skull base contributes to the diagnostic challenge of skull base surgical pathology. Extracranially, the nasal cavity, nasopharynx, and paranasal sinuses are lined by squamous and respiratory mucosa as well as specialized olfactory epithelium. The submucosa includes numerous seromucinous salivary glands, blood and lymphatic vessels, peripheral nerves, and fibrous and adipose tissue. These mucosae and soft tissues are adherent to underlying bone and hyaline cartilage. Intracranially, the pituitary gland occupies a central position with surrounding meninges and intrinsic myelinated and nonmyelinated brain tissues. This extraordinary array of tissues gives rise to numerous pathologic lesions of diverse his-tologic differentiation.

Immunohistochemistry/Special Methodology

Lesions of the skull base are a challenge for both surgeon and pathologist and include several lesions that have similar or overlapping morphology. Modern pathologic techniques, including immunohistochemistry or electron microscopy, are commonly used for diagnosis. Immunohistochemistry **has** become a powerful tool for pathologic diagnosis and has proven particularly effective in the classification of the undifferentiated or small cell lesions of the skull base. It is important to appreciate, however, that no one antibody can determine whether a lesion is benign or malignant. Standard pathologic criteria of architecture, nuclear morphology, and mitotic rate remain the essential morphologic features for diagnosis. A general overview of the commonly used antibodies for immunohistochemical diagnosis is provided in Table 1.

The transfer of technology from basic research to clinical application is advancing rapidly. Molecular probes, including both *in situ* hybridization and polymerase chain reaction methodology, are being used, for example, in the study of Epstein-Barr virus in nasopharyngeal carcinoma (NPC). Current and future studies will use techniques such as DNA ploidy analysis and probes for biologic markers, including tumor suppressor genes, oncogenes, proliferation markers, and other, as yet unidentified entities.

To optimize diagnosis and patient care, it is essential that the surgeon and pathologist maintain a dialogue of mutual respect and vigilant communication. A preoperative or prebiopsy consultation with the pathologist ensures that the tissue is properly allocated and processed for special studies if indicated. Individual pathology laboratories have preferred media and fixatives for immunohistology, electron microscopy, flow cytometry, and so forth. Provision of the pertinent clinical history and precise anatomic location is mandatory.

Frozen-Section Diagnosis

Frozen-section diagnosis is uniquely challenging in skull base surgery. Frozen sections are sought for two general reasons, diagnosis or control of resection margins. Intraoperative frozen section is *not* the optimum technique for definitive initial diagnosis of an unknown process because of the potential for sampling error or interpretive error due to freezing artifact. An intraoperative consultation including frozen section or touch preparations may be indicated to ensure that adequate, representative tissue has been obtained for the diagnostic work-up.

To prevent intraoperative frozen-section discrepancies, we recommend thorough sampling and technically adequate sections (1). The pathologist, surgeon, and patient should

---

R. Gandour-Edwards, S.B. Kapadia: Department of Pathology, University of California, Davis Medical Center, Sacramento, California 95817.

L. Barnes: Department of Pathology, University of Pittsburgh, Pittsburgh, Pennsylvania 15213.

TABLE 1. *Common antibodies used in skull base pathology*

Antibody	Target tissues
Cytokeratins	Epithelial tissues (e.g., squamous and glandular mucosa, carcinomas)
Epithelial membrane antigen	Epithelial tissues, glands, poorly differentiated carcinomas
Vimentin	Mesenchymal tissues (e.g., connective tissue, muscle, sarcomas)
Human muscle actin	Smooth/skeletal muscle, rhabdomyosarcoma, leiomyoma
Leukocyte common antigen	Lymphocytes, plasma cells
L26	B-cell lymphocytes, B-cell lymphoma
UCHL-1	T-cell lymphocytes, T-cell lymphoma
S-100	Neural crest tissues (e.g., melanoma, olfactory neuroblastoma)
HMB 45	Melanoma
Chromogranin A	Neurosecretory granules (e.g., olfactory neuroblastoma)
CD68	Macrophages, histiocytes; malignant fibrous histiocytoma
Factor VIII, CD 31, *Ulex europaeus*	Endothelial cells (e.g., hemangioma, angiofibroma)
Synaptophysin	Major integral membrane protein of synaptic vesicles; paraganglioma, olfactory neuroblastoma
013	Ewing's sarcoma

also realize that, infrequently, a definitive diagnosis cannot be rendered and a deferral of diagnosis may be the most prudent interpretation.

EPITHELIAL TUMORS

Squamous Cell Carcinoma

Definition. Squamous cell carcinoma is a malignant tumor derived from squamous epithelia such as epidermis and the squamous mucosal lining of the upper respiratory tract. It is characterized by a disorganized, invasive growth of large epithelial cells with intercellular bridges and cytoplasmic keratin.

Clinical Features. Squamous cell carcinoma is the most common malignancy of the head and neck. Skull base involvement by squamous cell carcinoma has been reported from the sinonasal tract, oropharynx, and hypopharynx and from the skin of the scalp and external auditory canal (2-4). Squamous carcinoma can directly invade soft tissue and bone (as well as spread through lymphatic channels and by perineural extension through skull base foramina (Table 2).

Histopathology. Squamous cell carcinoma is graded into well, moderate, and poorly differentiated types by the degree of resemblance to normal squamous tissue. Specific criteria include definition of intercellular bridges, amount of keratinization, nuclear pleomorphism, mitotic rate, and degree of cell cohesion (sheets vs. small nests). Tumors that involve the skull base are typically moderately or poorly differentiated (Figs. 1-3).

Differential Diagnosis. Melanoma, a tumor noted for its protean manifestations, may present a pattern consisting of

TABLE 2. *Squamous cell carcinoma of the skull base: analysis of 21 consecutive cases from the Center for Skull Base Surgery, University of California,* Daw's *Medical Center, 1990 to 1994*

Age/sex	Grade	Primary site	Skull base	Neural invasion
55/M	Moderate	Hypopharynx	Middle fossa	Yes
61/M	Poor	Auricle	Middle fossa	No
61/M	Moderate	Scalp	Occiput	Yes
65/F	Moderate	Frontal sinus	Anterior fossa	No
65/F	Moderate	External ear canal	Temporal bone	Yes
77/F	Moderate	External ear canal	Temporal bone	Yes
58/M	Moderate	Tonsilar fossa	Middle fossa	Yes
47/F	Moderate	External ear canal	Temporal bone	No
63/F	Poor	Tonsilar fossa	Temporal fossa	Yes
44/F	Moderate	Maxilla	Infratemporal fossa	No
57/M	Poor	Maxilla	Infratemporal fossa	Yes
63/F	Poor	Retromolar trigone	Infratemporal fossa	Yes
60/M	Moderate	Maxilla	Middle fossa	No
69/M	Poor	Frontal sinus	Middle fossa	Yes
72/M	Moderate	Oropharynx	Infratemporal fossa	No
53/M	Moderate	Auricle	Temporal bone	Yes
44/M	Poor	External ear canal	Temporal bone	No
60/M	Poor	Skin of face	Infratemporal fossa	Yes
51/M	Moderate	Ethmoid sinus	Middle fossa	No
62/M	Poor	Oropharynx	Middle fossa	No
44/M	Poor	Hypopharynx	Infratemporal fossa	Yes



FIG. 1. Moderately differentiated squamous cell carcinoma. Cohesive nests of plump, polygonal cells are adjoined by intracellular bridges. Keratinization is not present in this section. (Hematoxylin and eosin, original magnification 400x.)

sheets of plump, polygonal cells with abundant pink cytoplasm. Melanoma may be distinguished from squamous carcinoma by the absence of intercellular bridges. Less reliable features include the characteristic nuclear inclusions of melanoma and variably present cytoplasmic brown pigmentation. Immunohistochemistry is usually definitive in distinguishing these entities, with squamous cell carcinoma reactive lo cytokeratin and melanoma reactive to S-100 and HMB-45. Benign reactive conditions that can mimic invasive squamous carcinoma include the squamous metaplasia and atypia of minor salivary ducts that can result from radiation therapy or necrotizing .sialometaplasia.

Adenoid Cystic Carcinoma

Definition. Adenoid cystic carcinoma, a tumor of salivary origin, is composed of small, basal duct lining cells and myoepithelial cells arranged in a characteristic cribriform pattern.



FIG. 2. Poorly differentiated squamous cell carcinoma. The tumor cells have markedly pleomorphic, vesicular nuclei with prominent nucleoli. Intracellular bridges are seen focally and no keratinization is present. (Hematoxylin and eosin, original magnification 400X.)



FIG. 3. Squamous cell carcinoma involving cranial nerve V at the supraorbital fissure. {Hematoxylin and eosin, original magnification 4Qx.)

Clinical Features. Adenoid cystic carcinoma is the most common malignant tumor of minor salivary glands and may occur in the sinuses and oral cavity as well as in major salivary glands. The disease is characterized by slow but relentless progression over years, with occasional late (after 10-15 years) recurrences and distant metastases. Adenoid cystic carcinoma characteristically spreads along perineural spaces, including those of the maxillary division of the trigcminal nerve, and may traverse the foramen ovale to the gasserian ganglion. Lymphatic spread is low (i.e., 13-16%); however, heinatogenous metastasis is high (40%), with lung and bone representing the most common sites of distant spread (5). In our series of 18 adenoid cystic carcinomas, the tumors most commonly originated in the maxillary sinus and demonstrated a predilection for invasion of the middle cranial fossa (6) (Table 3).

Histopathology. Histologically, three patterns have been described: tubular, solid, and cribriform, and tumors are classified by which pattern dominates. The cribriform type is the most common and is considered the "classic" pattern. Nests of cells demonstrate multiple circular spaces filled with bluish, mucinous material or pink, hyalinized material (Fig. 4). The tubular-trabecular pattern consists of cells arranged in individual ducts or tubules, whereas the solid pattern, as expected from the name, has nests or sheets of basaloid cells with little cystic formation (Fig. 5).

Per/.in et al. (7) found a correlation between these histologic patterns and survival rates as follows: tubular, 8 years; cribriform, 9 years; and solid, 5 years. Recurrence rates were tubular, 59%; cribriform. 89%: and solid. 100%. Neural invasion, in both perineural and intraneural patterns, is frequently observed and considered a diagnostic feature (Figs. 6, 7).

Differential Diagnosis. Polymorphous low-grade adenocarcinoma has a mixture of cuboidal and columnar cells with open vesicular chromatin and small nucleoli. A mixture of

TABLE 3. *Adenoid cystic carcinoma involving the skull base: combined University of Pittsburgh, University of California,* Daw's, *1988 to 1993*

Primary	Skull base	Pattern	Neural involvement	Follow-up
Nasal septum	Anterior fossa	Cribriform	Yes	No evidence of disease
Ethmoid	Middle fossa	Cribriform	Yes	Died of metastatic disease
Ethmoid	Middle fossa	Tubular trabecular	Yes	No evidence of disease
Auditory canal	Temporal bone	Cribriform	Yes	Died of other causes
Nasopharynx	Anterior fossa	Tubular trabecular	Not observed	No evidence of disease
Oral cavity	Middle fossa	Solid	Yes	Died of disease
Oral cavity	Middle fossa	Cribriform	Yes	Died of other causes
Nasal septum	Anterior fossa	Cribriform	Not observed	No evidence of disease
Left parotid	Infratemporal fossa	Cribriform	Yes	Died of metastatic disease
Nasal cavity	Middle fossa	Solid	Yes	No evidence of disease
Maxillary sinus	Infratemporal fossa	Cribriform	Yes	Died of metastatic disease
Maxillary sinus	Anterior fossa	Cribriform	Yes	Unknown
Ethmoid	Middle fossa	Cribriform	Yes	No evidence of disease
Nasopharynx	Anterior fossa	Solid	Yes	Died of metastatic disease
Maxillary sinus	Temporal bone	Cribriform	Yes	Died of metastatic disease
Oral cavity	Infratemporal fossa	Tubular trabecular	Yes	Died of disease
Maxiliary sinus	Anterior fossa	Cribriform	Not observed	Died of disease
Maxillary sinus	Middle fossa	Tubular trabecular	Yes	Unknown



FIG. 4. Adenoid cystic carcinoma, classic cribriform pattern. The tumor cells are small, uniform, and basaloid with dense nuclei and no mitoses. Bluish mucin material fills the multiple small lumina. (Hematoxylin and eosin, original magnification 200X.)



FIG. 5. Adenoid cystic carcinoma, solid pattern. The basaloid cells are present as solid nests with a peripheral palisading pattern. This pattern has been associated with a poorer prognosis. (Hematoxylin and eosin, original magnification 200X.)



FIG. 6, Adenoid cystic carcinoma involving the optic nerve. Cribriform nests of tumor are present in perineural and intraneural invasive patterns. (Hematoxylin and eosin, original magnification 200X.)



FIG. *7.* Adenoid cystic carcinoma with perineural invasion of cranial nerve III. (Hematoxylin and eosin, original magnification 200 x.)

patterns, including single-layer tubules, cribriform, tubular, trabecular, solid, papillary, and solitary cell "Indian file" types, is seen. Basal cell adenoma is an encapsulated benign growth of solid masses of basaloid cells with peripheral nuclear palisading. Mitoses usually are absent and no infiitrative pattern or neural involvement is seen.

Nasopharyngeal Carcinoma

Definition. Nasopharyngeal carcinoma (NPC) is a malignant tumor derived from the surface epithelium of the nasopharynx. It has a strong association with the Rpstein-Barr virus and a worldwide distribution, but it is especially common among residents of Southeast Asia.

Clinical Features. Nasopharyngeal carcinoma occurs in all age groups (average, 45-50 years) and is more common in men by a ratio of 3 to 1 (8.9). Ii arises primarily on the lateral wall of the nasopharynx in the region of Rosemntiller's fossa and usually presents as serous otitis media, nasal obstruction, or cpistaxis. or with asymptomatic enlargement of the cervical lymph nodes, especially those in the apex of the posterior cervical triangle (8-10).

Prognosis is related to clinical stage and histologic type. The best prognosis is associated with the undifferentiated type (60% 5-year survival) and the worse with the squamous cell variant (20% 5-year survival) (11).

Iltstopafholngy. In 1978. the World Health Organization proposed that NPC be divided into three types: squamous cell carcinoma, nonkeratini/ing carcinoma, and undifferenliaied carcinoma (12). In 1991, the classification was slightly modified f 13) (Table 4).

The Lenn "squamous cell carcinoma" is used for any NPC that shows evidence of squamous differentiation (e.g., intercellular bridges, keratini/aiion), whereas "differentiated nonkeratinizing carcinoma" exhibits no evidence of keratin formation and resembles, for all practical purposes, transitional cell carcinoma of the urinary tract.

Undifferentiated carcinoma, previously known as lymphoepithelioma, is composed of cells with large vesicular nuclei, prominent nucleoli, and amphophilic cytoplasm (Pig. 8). It is also characteristically associated with a prominent component of lymphocytes.

Based on their appearance under the electron microscope, it is apparent that all of the aforementioned types of NPC are actually variants of squamous cell carcinoma. Those tumors that show kcratinization (squamous cell carcinoma), however, have the worst prognosis and are rarely associated with Epslein-Barr virus.

TABLE 4. *Classification of nasopharyngeal carcinoma*

World Health Organization (1978)
1. Squamous cell carcinoma
2. Nonkeratinizing carcinoma
3. Undifferentiated carcinoma

World Health Organization (1991)
1. Squamous cell carcinoma
2. Nonkeratinizing carcinoma
    A. Differentiated nonkeratinizing carcinoma
    B. Undifferentiated carcinoma



FIG. 8. Nasopharyngeal carcinoma, undifferentiated type, Note central aggregate of pale-staining cells with large, round, vesicular (clear) nuclei; prominent nucleoli; and amphophilic, poorly defined cytoplasm. A prominent component of lymphocytes is apparent in the background. (Hematoxylin and eosin, original magnification 400x.)

Differential Diagnosis. Nasopharyngeal carcinoma musl he distinguished from malignant lymphoma. This is easily accomplished with the use of immunohistochemistry. NPC is positive for cytokeratin (Fig. 9) and negative for leukocyte common antigen, whereas lymphomas are positive for the latter and negative for cytokeratin.

Pituitary Adenoma

Definition. Most pituitary tumors are benign epithelial tumors or adenomas of the anterior lobe (8,14-16). Pituitary adenomas comprise 10% of all intracranial tumors. Small islands of primitive anterior lobe tissue may be sequestered



FIG. 9. Nasopharyngeal carcinoma, undifferentiated type. The tumor cells react strongly with cytokeratin. whereas background lymphocytes are nonreactive. (Immunoperoxidase stain, original magnification 100X.)

during migration and persist into adult life, where they may be found in the sphenoid bone, sella turcica outside the pituitary capsule, or nasopharynx (pharyngeal pituitary). Rarely, these remnants may give rise to true ectopic pituitary adenomas.

Clinical Features. Approximately 20% to 40% of pituitary adenomas are nonfunclioning (nonsecretory); the remainder are hormone producing. The functional status can be clinically assessed by hormonal assays. Nonfunctioning adenomas are often large and may grow beyond the confines of the sella, compressing the adjacent structures. Rarely, adenomas may invade the pituitary capsule and extend through the bone of the sella to involve the cavernous sinuses, sphenoid sinus, nasopharynx, or nasal cavity (invasive pituitary adenomas) (17). In biologic behavior, they rank between intrasellar adenomas and pituitary carcinoma. However, local invasion is insufficient to designate a pituitary tumor as carcinoma, the latter being defined by the presence of metastasis.

Histopathology. Pituitary adenomas may demonstrate a variety of growth patterns, including diffuse, papillary, festoon, or pleomorphic patterns (14-15). These patterns have no prognostic significance but are important in the differential diagnosis. Tumor cells may be eosinophilic, basophilic, or chromophobic, with round to oval nuclei and at times prominent nticleoli (Figs. 10, 11). There are no major histologic differences between invasive and noninvasive adenomas; hence, no conclusion regarding biologic behavior of pituitary adenomas can be drawn on the basis of histologic appearance alone. Invasive adenomas often may be cellular or pleomorphic or have more abundant mitoses (8,17).

The ultrastructural demonstration of neurosecretory granules or the immunuphenotypic expression of ncuroendocrine markers (neuron-specific enolase, synaptophysin, chromogranin) or pituitary hormonal markers may be essential for diagnosis. Nonfunctioning adenomas show no reactivity for pituitary hormones, but do show reactivity for neuroendocrine markers such as chromocranin, and neurosecretory granules are seen ultrastructurally. The estimated rate of gross invasion by pituitary adenomas of all types is 35% (17).



FIG. 10. Pituitary adenoma. The tumor is composed of sheets of uniform, round cells. (Hematoxyiin and eosin, original magnification 200x.)



FIG. 11. Pituitary adenoma. Higher magnification shows uniform neoplastic cells with round nuclei and clear cytoplasm. {Hematoxylin and eosin, original magnification 400x.)

Differential Diagnosis. In addition to the histologic features, the demonstration of secretory products by electron microscopy or immunohistochemistry helps distinguish pituitary adenoma from other tumors at this site, such as chordoma, plasmacytoma, lymphoma, meningioma, carcinomas, or sarcomas of the skull base.

Histologic features are not reliable predictors of pituitary tumor recurrences or invasiveness. In a study using antibodies to PCNA and K.i-67, Candour-Edwards et al. reported that compared with normal pituitary glands, the proliferalive index of intrasellar and invasive pituitary adenomas was increased. However, these proliferation markers did not distinguish between invasive and noninvasive variants of pituitary adenoma (18).

MESENCHYMAL TUMORS

Inflammatory Pseudotumor

Definition. Inflammatory pseudotumor is a nonneoplastic, reactive chronic inflammation that presents as a mass lesion. It is a somewhat controversial entity that has been reported w^ith a wide variety of histologic features and unpredictable behavior. The pulmonary lesion has been best characteri/ed as a benign, nonneoplastic tumefaction. Reported inflammatory "pseudotumors" at other sites have on occasion, however demonstrated recurrence and cytogenetic evidence supporting a neoplastic rather than inflammatory etiology, and have been better termed "inflammatory myofibroblastic tumors." The term "inflammatory pseudotumor" therefore should be used with caution and restricted to nonneoplastic lesions (19).

Clinical Features. True inflammatory pseudotumors are nonneoplastic lesions that occur most commonly in the lung.

Pseudotumors of the skull base occur most often as an extension of orbital disease. Primary lesions involving the clivus, sphenoid sinuses, infratemporal fossa, and temporal bone have also been reported. The lesions have a propensity to behave aggressively and frequently demonstrate bony erosion and cranial neuropathy (20).

Histopathology. Inflammatory pseudotumors are characterized by uniform, widely spaced fibroblasts with variable, dense collagen and small, uniform vessels with a mixed infiltrate of small lymphocytes, histiocytes, and plasma cells. Surrounding bone may exhibit erosion characterized by irregular islands of bone with osteoblastic and osteoclastic rimming. The density of the inflammatory infiltrate and of the collagen deposition is variable, with fewer inflammatory cells and increased fibrosis as the lesion ages (Fig. 12).

Differential Diagnosis. Inflammatory myofibroblastic tumors are distinguished by a cellular mixture of fibroblasts and myofibroblasts arranged in whorls and fascicles, A variable infiltrate of inflammatory cells is present, especially at the periphery, and mitoses are rare. Malignant fibrous histiocytoma is a densely cellular sarcoma with haphazard bundles of pleomorphic spindle cells and multinucleated giant cells. The mitotic rate is high and necrosis is common. Lymphoma is a cellular, monomorphic infiltrate of atypical lymphoid cells with a clonal pattern of reactivity on immunohistochemistry.

Fibrous Dysplasia

Definition. Fibrous dysplasia is a benign, fibroosseous process of bone that results in the replacement of normal bone with fibrous connective tissue and structurally weak fibrillar bone.

Clinical Features. Fibrous dysplasia may be monostotic (one bone) or polyostotic (several bones) and frequently involves the craniofacial complex. It is a self-limited process that starts in childhood, but because of slow growth may not cause symptoms until adulthood. Albright's syndrome consists of polyostotic fibrous dysplasia, pigmented skin macules, and endocrine abnormalities, typically precocious puberty (21,22).


FIG. **12.** Inflammatory pseudotumor. This clival lesion consisted of fibroblasts, myofibroblasts, and scattered lymphocytes, macrophages, and plasma cells. (Hematoxylin and eosin, original magnification 200x.)


FIG. 13. Fibrous dysplasia. This low-power view illustrates the multiple irregular bony islands, forming "C"- and "Y"-shaped fragments in a fibrous stroma. (Hematoxylin and eosin, original magnification 40x.)

In the craniofacial area, fibrous dysplasia occurs most commonly in the calvarium and maxilla. Involvement of the skull base, orbits, sinuses, and cranial ostia has been well documented, however, and can result in significant morbidity (23). Monostotic fibrous dysplasia of the temporal bone may lead to cholesteatoma (24). Malignant transformation of fibrous dysplasia to osteosarcoma has been reported, particularly after radiation therapy (25).

Histopathology. Fibrous dysplasia consists of multiple, irregular, immature fibrillar or woven bony trabeculae surrounded by loose, uniform fibroblastic spindle cells. The trabeculae often have "C" or "Y" shapes and have been described as "Chinese characters." Osteoclasts are rarely observed and osteoblasts are seen infrequently (Figs. 13, 14).

The fibrous stroma is characterized by a lack of pleomorphism and mitotic figures.

Differential Diagnosis. Ossifying or cementoossifying fibroma is a neoplastic lesion with uniform trabeculae or oval islands of new bone or cementum sharply separated from the surrounding fibrous tissue. Prominent osteoblasts rim these bony formations, although osteoclasts are scant. Some believe that fibrous dysplasia and ossifying fibroma represent a histologic spectrum of similar or closely related lesions (26). Chronic osteomyelitis has irregular bony islands that blend into the adjacent bone. Osteoblastic and osteoclastic rimming is present as well as scattered inflammatory cells and areas of necrosis. Osteosarcoma is characterized by large cells with hyperchromatic, irregular nuclei and immature, randomly distributed osteoid.

Angiofibroma

Definition. Angiofibromas (AF) are histologically benign vascular tumors that have a propensity for local aggressive



FIG. 14. Fibrous dysplasia. The higher-power view illustrates one irregular bony island with scant osteoblastic rimming. The stroma is composed of benign, moderately cellular fibroblasts. (Hematoxylin and eosin. original magnification 200 x.)

behavior and occur almost exclusively in male patients (8,27,28).

Clinical Features. Angiofibroma typically occur in male adolescents between 10 and 17 years of age (range, 1-60 years) (8). Their occurrence in women is questionable. They are rare tumors, estimated to comprise 0.5% of all head and neck neoplasms. The site of origin is the posterolateral nasal wall in the region of the sphenopalatine foramen. Initial manifestations include nasopharyngeal or nasal mass causing nasal obstruction and recurrent epistaxis. At diagnosis, approximately two thirds of patients have localized disease, and 20% have intracranial involvement (28). About 10% of AF recur after surgical resection. AF has no malignant potential. Rare sarcomatous transformation has been reported after massive doses of radiation.

Hiswpathology. On gross examination, AF are firm, rubbery, smooth, and coarsely nodular. The cut surface may show a spongy to firm, red-brown or gray-tan appearance. Histologically, AF is composed of vascular and stromal elements (Figs. 15, 16). The tumor is nonencapsulated. Interspersed in the fibrous slroma are slitlike or gaping vascular channels ("staghorn" shaped) of varying size, lined by a single layer of endothelial cells (15.16). The collagenous matrix contains round or stellate nuclei, the latter superficially resembling neurons. A fascia-like appearance to the stroma is imparted by the parallel arrangement of collagen fibers. Reactive stromal cells with nuclear byperchromatism, binucleation, and occasional mitoses may be seen and should not be mistaken for malignant criteria. Inflammatory and mucoserous glands are rare or absent.



FIG. 15. Angiofibroma. Both the vascular and stromal components are illustrated. (Hematoxylin and eosin, original magnification 200x.)



FIG. 16. Angiofibroma. Note the characteristic "staghorn"-shaped vascular channels and collagenous stroma containing stellate cells. (Hematoxylin and eosin, original magnification 400 x.)

Ultrastructurally, round, electron-dense granules are found in the stromal cell nuclei and represent tightly bound RNA-protein complexes (29). Immunohistologic studies suggest that AF are composed of myofibroblastic and vascular elements. Stromal cells invariably express vimentin and, at times, muscle-specific antigen, but are negative for endothelial markers (factor Vll-related antigen and *Ul,ex europaem}* (27,30). Hormone receptor studies have shown the presence of androgen receptor proteins in stromal cells and some endothelial cells (31). Most AF are negative for estrogen receptors.

Differential Diagnosis. Angiofibroma should be distinguished histologically from richly vascular, fibrosed inflammatory nasal polyps, lobular capillary hemangioma (so-called "pyogenic granuloma"), and sinonasal heniangiopericytoma (27). These lesions have a distinctive histologic appearance and lack the typical vascular channels and stromal characteristics of AF. Fibrosed nasal polyps are distinguished by the presence of prominent stromal edema, thickened epithelial basement membrane, eosinophils, and mucoserous glands. Pyogenic granuloma typically shows a lobular proliferation of capillaries and endothelial cells. Sinonasal hemangiopericytoma is characterized by round to short spindle cells intimately related to irregular vascular channels and a reticulin network surrounding individual tumor cells, as seen on special stains. It is not possible to predict which of the AF will have a biologically aggressive local behavior on the basis of clinical or pathologic features. To determine if DNA ploidy can be used to predict tumor behavior, Barnes et al. studied 31 AF by flow cytometry (2K). However, all of tbe tumors were DNA diploid, including those with recurrences or intracranial extension, suggesting that DNA ploidy is not useful in predicting local aggressiveness.

Meningioma

Definition. Meningiomas are generally benign tumors that arise from meningocytes of arachnoid granulations (8,32-34) They comprise approximately 15% of all intracranial tumors and 25% of intraspinal neoplasms.

Clinical Features. The mean age of patients is 45 years, with a female predominance (2-4:1). Meningiomas commonly occur in the parasagittal area along the dural sinuses, lateral cerebral convexities, sphenoid ridge, and areas of dural penetration by cranial nerves. Most develop within the neuraxis, but in 20% of cases extracranial extension may occur into the calvarium. skull base, orbit, middle ear, sinonasal passage, or parapharyngeal space. Extracranial meningiomas usually represent extension of a primary intracranial tumor, but occasionally they may originate from arachnoidal cells within the trunk or perineural sheath of cranial nerves near a neural foramen (35). Meningiomas are slow-growing tumors that compress rather than invade neural tissue. They may recur in 10% of cases, often within 5 years of therapy, because of incomplete excision or intrinsic biologic aggressiveness. When meningiomas occur in patients younger than 30 years of age or when they are multiple, the possibility of neurofibromatosis is raised.

Histopathohgy. Meningiomas are usually solitary, well demarcated, firm, gray-tan, smooth or lobulated tumors. They show a histologic diversity with four basic growth patterns: (a) syncylial (mem'ngothelial), composed of whorls of meningothclial cells displaying round to oval nuclei containing rare intranuclear cytoplasmic inclusions, and pale pink cytoplasm with indistinct cell borders (Figs. 17, 18); (b) fibroblastic, showing interwoven fascicles of spindle-shaped cells and collagen fibers: (c) transitional, having features of both of the preceding types; and (d) "angioblastic," now considered to be a meningeal hernangiopericyloma (8,32-33). Psammoma bodies and a whorled pattern are seen in all types. These histologic patterns have no prognostic significance. Mitoses are rare or absent. In meningiomas, the presence of mitoses and local invasion of dura, bone, or extracranial soft tissue does not necessarily indicate malignancy; only the presence of metastasis is sufficient evidence of malignant behavior (32).

Differential Diagnosis. The histologic diversity of meningioma can present problems in differentiating it from other tumors, namely, schwannoma, hemangiopericytoma, paraganglioma, and metastatic carcinoma (8,32-34). Immunohistochemically, meningiomas exhibit a dual epithelial and mesenchymal differentiation with positivity for epithelial membrane antigen and vimentin, and in a lesser proportion of cases, for keratin and S-100 protein (34). Tumors cells are negative for desmin, neurofilament, synaptophysin, chromogranin, and glial fibrillary acidic protein. Progesterone receptors have been demonstrated in a high proportion of meningiomas.



FIG. 17. Meningioma. The tumor is composed of spindle-shaped and whorled meningothelial cells. (Hematoxylin and eosin, original magnification 200x.)

The biologic behavior of meningioma is not always predictable from its histologic appearance. Although the presence of necrosis, brain invasion, or mitoses may indicate aggressive behavior, not all meningiomas that recur or metastasize have these features, and it is difficult to predict which of the tumors will behave aggressively. Cytogenetic studies have shown that loss of chromosome 22 (monosomy 22) represents the most common chromosomal abnormality (50-70%). In the remaining 30% of cases there is a normal



FIG. 18. Meningioma. Note the fibroblastic and whorled pattern of neoplastic cells with scattered intranuclear cytoplasmic inclusions. (Hematoxylin and eosin, original magnification 400x.)

karyotype (36). Structural changes of chromosome 1, along with numeric changes, may indicate aggressive tumor behavior. Studies have suggested that the proliferating fraction, using DNA content by digital cell image analysis and immunohistochcmical staining for the proliferating cell nuclear antigen (PCNA) or Ki-67 nuclear antigen, may be useful in predicting biologic aggressiveness of the tumor (37).

Olfactory Neurohlastoma

Definition. Olfactory neuroblastoma is an uncommon neuroectodermal tumor thai arises from the nasal olfactory epithelium. As such, it characteristically arises high in the nasal cavity and is attached LO the cribriform plate.

Clinical Features. Olfactory neuroblastoma affects both sexes equally and occurs in all age groups (median, 40-50 years) (38,39). On physical examination, it presents as a unilateral red-gray or tan, polypoid growth attached high in the nasal cavity. Nasal obstruction and epistaxis are the most common symptoms. Others include anosmia, pain, proptosis, and visual disturbances. The tumor may remain confined to the nasal cavity, but with neglect, often extends secondarily into adjacent paranasal sinuses, orbits, or base of the skull.

Metastasis to cervical lymph nodes occurs in 10% to 30% of patients during the course of the disease and systemic metastasis (lung and bone) in *K%* to 46% of cases (38-41). Local recurrences after initial therapy eventually develop in 30% to 40% of patients (38-40). Five- and 10-year survival rates of 70% to 80% and 60% to 70%, respectively, have been reported (38,39).

Histopathotogy. Microscopically, olfactory neuroblastomas are composed of small, round cells slightly larger than lymphocytes that grow in a lobular or diffuse pattern, or a combination of both. The nuclei are hyperchromatic with a uniform chromatin distribution (Figs. 19. 20). Nucleoli are inconspicuous, cytoplasm is sparse, and mitoses are rare. The stroma is highly vascular and often has a neurofibrillary appearance. **Homer Wright** and Flexner-Winlersteiner rosettes are additional features.



FIG. 19. Olfactory neuroblastoma. The lobular arrangement of tumor cells is characteristic. (Hematoxylin and eosin, original magnification 100X.)



FIG. 20. Olfactory neuroblastoma. **Note the** small round cells and neurofibrillary background. (Hematoxylin and eosin, original magnification 400x.)

Ultrastructurally. olfactory neuroblastomas contain neurosecretory granules, neurotubules, and neurofilaments. On immunostaining, they are positive for synaptophysin and neuron-specific enolasc, but only focally positive for S-100 protein (40,42). Some may also be positive for low-molecular-weight cytokeratin.

Olfactory neuroblastomas are sometimes graded hislologically on a scale of I (well differentiated) to IV (poorly differentiated). Some have found this grading system to have prognostic significance, whereas others have not.

Differential Diagnosis. The differential diagnosis includes innumerable "small round cell" tumors that occur in the sinonasal tract (43). Among the more common ones are malignant lymphoma. rhabdomyosarcoma, undifferentiated carcinoma, and malignant melanoma. Most often, these tumors can be distinguished by the use of immune stains. Malignant lymphomas are positive for leukocyte common antigen, rhabdomyosarcomas for desmin and myoglobin, undifferentiated carcinomas for epithelial membrane antigen, and malignant melanoma for HMB-45. Olfactory neuroblastomas are negative for these markers.

Paraganglioma

Definition. Paragangliomas are a group of histologically similar neoplasms that arise from neuroectodermally derived paraganglionic cells associated with autonomic ganglia (7,43-46). The extraadrenal paraganglia can be classified into (a) branchomeric, which includes the jugulotympanic, carotid body, laryngeal, subclavian, and aortopulmonary paraganglia; (b) intravagal, at the level of the jugular or nodose ganglion; (c) aorticosympathetic; and (d) visceral-autonomic paraganglia (44).

Clinical Features. In the head and neck, carotid body tumors are the most common type (60%), followed by jugulotympanic and vagal tumors (45,46). Patients are usually between 40 and 60 years of age. Head and neck paragangliomas may be multifocal (10-20%). familial (10%). expressed as an autosomal dominant trait, or malignant (2-13%). Only rarely (2-3%) do paragangliomas at this site show manifestations of norepinephrine overproduction. Occasionally, paragangliomas may be a component of the multiple endocrine neoplasia syndrome.

Histopathology. Paragangliomas have a beefy, red-brown to gray-tan appearance. Histologically, paragangliomas may have a thin capsule and are composed of two cell types: chief cells, arranged in compact cell nests *(Zell-ballen)* (Fig. 21), and sustentacular or modified Schwann cells located peripheral to the chief cells (44^-7). The chief cells have centrally located nuclei with finely stippled chromatin and a moderate amount of eosinophilic cytoplasm. Nuclear pleomorphism, necrosis, mitoses, and even vascular or neural invasion may be seen in benign paraganglioma and are not sufficient for a diagnosis of malignancy. Only the presence of metastasis, to sites such as the lymph nodes, lung, and bone, establishes a diagnosis of malignancy in these tumors. Immunohistochemical stains confirm the neuroendocrine nature of the chief cells with diffuse, strong positivity for neuron-specific enolase, synaptophysin (Fig. 22), and chromogranin, as well as other polypeptides, such as serotonin, leu-enkephalin, somatostatin, bombesin, and adrenocorticotropic hormone (46). The sustentacular cells may be positive for S-100 protein and glial fibrillary acidic protein, but are negative for neuroendocrine markers. An inverse relationship between tumor grade and sustentacular cell number has been observed. Ultrastructurally, chief cells contain small, dense core neurosecretory granules (100-200 nm), representing sites of catecholamine storage (In).

Differential Diagnosis. The typical histologic features and immunophenotype distinguish paraganglioma from other neoplasms with which it may be confused, including meningioma, nerve sheath tumor, hemangiopericytoma, adult rhabdomyoma, melanoma, or metastatic carcinoma (especially renal cell carcinoma). However, the diagnosis of paraganglioma may be made difficult by the presence of extensive fibrosis, which may mask the typical *Zellballen* pattern, or when chief cells are spindled, granular, or vacuolated. In difficult cases, the diagnosis can be confirmed by immunohistochemical or ultrastructural studies.



FIG. 21. Paraganglioma. The typical *Zellballen* pattern of :~ af cells is illustrated. (Hematoxylin and eosin, original magnification 200 x.)



FIG. 22. Paraganglioma. Note the compact nests of chief cells with a moderate amount of cytoplasm that are strongly positive for synaptophysin. (Immunoperoxidase stain, original magnification 400x.)

Unlike other neoplasms, the biologic behavior of paragangliomas cannot be predicted by the presence of atypical features. Studies of head and neck paragangliomas have shown that although DNA abnormalities are common, DNA ploidy using flow cytometry is of limited value in predicting prognosis and is not useful for assessing its malignant potential (45,46).

Rhabdomyosarcoma

Definition. Rhabdomyosarcoma is a malignancy of skeletal muscle cells (rhabdomyoblasts) with varying degrees of maturation and resemblance to normal skeletal muscle.

Clinical Features. Rhabdomyosarcoma is the most common soft tissue sarcoma in children and young adults as well as the most common soft tissue sarcoma of the head and neck.

The head and neck sites are divided into three broad groups: cranial parameningeal (50%), orbital (25%), and nonorbital-nonparameningeal (25%). The orbital tumors have the best prognosis, whereas parameningeal involvement is associated with the poorest outcome (48).

Parameningeal sites include the nasopharynx, paranasal sinuses, middle ear-mastoid, and pterygoid-infratemporal regions. Skull base involvement by tumor infiltration occurs commonly relatively early in the disease, with involvement of cranial nerves. Traditional thinking has viewed skull base involvement as a contraindication to surgery, and aggressive chemotherapy, radiation therapy, or both have been used, with overall survival rates of 57% reported in the Intergroup Rhabdomyosarcoma Study II (49). There is limited experi-



FIG. 23. Embryonal rhabdomyosarcoma. The tumor consists of large, irregular, polygonal and straplike cells with abundant pink cytoplasm and coarse, irregular nuclei. (Hematoxylin and eosin, original magnification 200x.)

ence with **skull** base surgery for rhabdomyosarcoma **in an** adjuvant selling afler chemotherapy or radiation therapy (50-53).

Prognosis is also linked It) histologic type, with the alveolar variant having a less favorable course than the embryonal type at all stages. Rhabdomyosarcoma metastasizes to regional lymph nodes as well as hematogenously to bone, lung, and brain. Overall 5-year survival rates are stage I, 83%; stage IT, 70%; stage III, 52%; and stage IV, 20% (49)

Histopathology. Three histologic subtypes are described: embryonal alveolar, and pleomorphic (54), The embryonal variant is the most common, with sheets of large round and spindle cells with abundant eosinophilic cytoplasm called rhabdomyoblasts (Fig. 23J. Cross-striations resembling those found in skeletal muscle fibers are often present. Mitoses and necrosis are commonly seen. Imrnunohistochemical reactivity for desmin, human muscle actin, and myoglobin is seen. Electron microscopy reveals primitive bundles of actin and myosin filaments with Z banding (Fig. 24).



FIG. 24. Embryonal rhabdomyosarcoma. Rhabdomyoblast with dense bundles of thick (myosin) and thin (actin) myofila-ments. (Electron micrograph, original magnification 30,000 x.)



FIG. 25. Alveolar rhabdomyosarcoma. The alveolar variant of rhabdomyosarcoma is characterized by small, round cells with scant cytoplasm. (Hematoxylin and eosin, original magnification 200x.}

The alveolar subtype consists of poorly defined groups of single, small, dense, round cells with irregular nuclei and scant cytoplasm (Fig. 25). This histologic type is included in the poorly differcntialed "small round blue cell tumors of childhood." An alveolar pattern with cell clusters resembling lung alveoli is variable, and the primitive cells may appear in solid sheets or trabecular nests. Mitoses and necrosis are common. Immunohistochemical stains are positive for desmin and human muscle actin. A characteristic translocation between chromosomes 2 and 13, thet(2;13)(q35;ql4), is found in most alveolar rhabdomyosarcomas. The translocation involves the *PAX3* gene, which is involved in segmentation and neural tube differentiation in embryogenesis and is a candidate oncogene (55).

The pleomorphic histologic type is uncommon, particularly in the head and neck, and consists of large, multinucleale, pleomorphic cells with bizarre nuclear features.

Differential Diagnosis. Embryonal rhabdomyosarcoma may be distinguished from rhabdoinyoma, its benign counterpart, by the presence of enlarged atypical nuclei and mitoses. Alveolar soft part sarcoma, a tumor of uncertain histogenesis, has uniform nuclei and characteristic ultrastructural rhomboid crystals. Granular cell tumor of Schwann cell derivation is characterized by large pink cells, but has uniform nuclei and shows reactivity with S-100. Alveolar rhabdomyosarcoma resembles several small round cell tumors, including lymphoma, Ewing's sarcoma, neuroendocrine carcinoma, and neuroblastoma. Morphologic and ultraslructural features as well as immunoriistochcmislry are used to distinguish these entities. Alveolar rhabdomyosarcoma typically does not form the thick-thin filaments seen in the embryonal type, but shows positivity for desmin or human muscle actin. A list of the characteristic-differentiation-specific markers for the common round cell tumors is given in Table 1.

Chondrosarcoma

Definition. Chondrosarcomas are malignant tumors of cartilage that may arise in bone or soft tissues. They comprise 0.15% of all intracranial tumors and 6% of skull base neoplasms (56). Approximately 75% of all cranial chondrosarcomas occur at the base of the skull, and most of these are found in the middle fossa.

Clinical Features. The tumors affect both sexes equally and occur over a broad age Taftg£, ^w\fo 'i <pe\jk distribution between 30 and 50 years (57,58). Headaches, visual disturbances, cranial nerve palsies, hearing loss, and gaii disturbances are the most frequent complaints.

Computed tomography typically shows a destructive, osteolytic lesion with variable enhancement with contrast material. The rumors are avascular on angiography and 50% to 80% contain calcific deposits (59).

The clinical course is prolonged and characterized by frequent local recurrences. Systemic metastases are unusual. Although most patients die within 4 to 8 years of diagnosis, Austin-Seymore et al. have reported a 76% 5-year disease-free survival rate in a series of 68 patients with low-grade chondrosarcomas and chordomas of the skull base (58).

Histopathology. Chondrosarcomas can be divided into five histologic types: conventional, myxoid, mesenchymal, clear cell, and dcdifferentiated. The conventional type, the subject of this discussion, is characterized by increased cellularity and the presence of one or more cells that lie within clear spaces called lacunae (Figs. 26, 27). The nuclei vary from dense and hyperchrornatic to vesicular with prominent nucleoli. Mitoses are sparse. The stroma is usually composed of a hyaline matrix but may be spindled and myxoid. Most >kull base chondrosarcomas are well (grade I) to moderately differentiated (grade II). Poorly differentiated tumors (grade III) are uncommon.

Differential Diagnosis. In the skull base, the most common differential diagnosis is chordoma. Separation of these two entities is rather straightforward with immunohistochemistry. Chondrosarcomas are negative for cytokeratin and epithelial membrane antigen, whereas chordomas are positive for both (60).



FIG. 26. Well differentiated Chondrosarcoma showing increased cellularity. (Hematoxylin and eosin, original magnification 100x.)



FIG. 27. Well differentiated Chondrosarcoma. Note the small, dark nuclei aad scattered binucleate lacunae. (Hematoxylin and eosin, original magnification 400x.)

Chordoma

Definition. Chordomas are slow-growing, locally aggressive, malignant neoplasms derived from vestigial remnants of the notochord found along the axial skeleton, They account for 1 % to 4% of all malignant tumors of bone and less than 1% of all intracranial tumors (61). Although the site of origin along the craniospinal axis varies among medical institutions, most large series indicate that about 50% of chordomas arise from the sacrococcygeal region. 35% from the base of the skull, and 15% from the vertebral column.

Clinical Features. Chordomas of the skull base affect both sexes equally and occur over a broad age range, with a peak incidence between 35 and 50 years of age (61-63). Only 5% occur in people younger than 20 years of age (64). Headaches, visual disturbances, cranial nerve dysfunction, and gait disturbances are the major complaints.

Radiographic evaluation reveals a midline mass centered around the clivus associated with osteolytic bone destruction, occasional inlralesional calcification, and varying degrees of encroachment on surrounding structures.

The average survival of patients with cranial chordomas is 4 to 8 years. Local recurrences, however, are common, and usually appear within 2 to 3 years of treatment. Systemic metastases are distinctly unusual.

Histopathohgy. Chordomas are divided pathologically into three types: (a) conventional or classic, (b) chondroid, and (c) dedifferentiated (65). Conventional chordomas are the most common type and are defined as those that show no evidence of cartilaginous or additional mesenchymal components. They exhibit a variety of growth patterns, the most characteristic of which is the lobular pattern (Fig. 28). Each lobule is composed of epithelioid cells often with vacuolated



FIG. 28. Chordoma, conventional type. Note the lobular growth pattern. (Hematoxylin and eosin, original magnification 100x.)

cytoplasm, so-called "'physaliferous cells," lying in a mucoid matrix (Fig. 29). The vacuoles contain glycogen, less often mucus, or both. The tumor cells are positive with immunoperoxidase stains for cytokeratin and epithelial membrane antigen, and on electron microscopy exhibit desmosomes.

Chondroid chordomas comprise 5% to 15% of all chordomas and 5% to *35%* of cranial chordomas. As their name implies, they contain both chordomatous and chondromatous components. The ratio of these two elements in any given tumor, however, is highly variable.

Dedifferentiated chordomas contain areas of conventional chordoma as well as an additional malignant mesenchymal component. The additional component is usually a malignant fibrous histiocytoma, fibrosarcoma, or osteosarcoma. They comprise 1 % to S% of all chordomas and are very aggressive neoplasms.



FIG. 29. Chordoma, conventional type, composed of epithelioid cells lying in a mucoid matrix. (Hematoxylin and eosin, original magnification 200x.)

Differential Diagnosis. Chordomas may be confused with chondrosarcomas or even carcinomas. The distinction between a chordoma and a chondrosarcoma, however, is relatively straightforward with immunostaining. Chordomas are positive for both cytokeratin and epithelial membrane antigen, whereas chondrosarcomas are negative for both. In addition, in contrast to chordomas, the cells of a chondrosarcoma lie within lacunae.

Because both chordomas and carcinomas may express cytokeratin, it is understandable why the two can be confused. Some chordomas (as well as carcinomas) may even express carcinoembryonic antigen. Results of immunoperoxidase stains for S-100 protein and vimentin may be helpful in this regard. Chordomas are usually positive for one or both of these markers, whereas carcinomas are usually negative (66).

LYMPHOMA

Definition. A lymphoma is a malignant proliferation of lymphoid cells characterized by a clonal population of T or B cells. Lymphomas arise in lymph nodes as well as extranodal lymphoid tissues in the head and neck. Primary lymphomas of the central nervous system have been increasing in frequency as a result of their association with immunosuppressive therapy for organ transplant and with human immunodeficiency virus infection (67).

Clinical Features. Malignant lymphomas are divided into Hodgkin's and non-Hodgkin's types, although advances in molecular biology continue to shape our understanding and classification of these tumors. Non-Hodgkin's lymphomas are classified morphologically by the Working Formulation, into low-, intermediate-, and high-grade categories; they are also classified by their B- or T-cell phenotype using immunohistochemistry and flow cytometry



FIG. 30. B-cell non-Hodgkin's lymphoma showing infiltrating sheets of large, monomorphic, individual cells with large nuclei and scant cytoplasm. (Hematoxylin and eosin, original magnification 200x.)



FIG. 31. B-cell non-Hodgkin's lymphoma. There is strong positivity for L26, a B-cell marker (CD20). (Immunoperoxi-dase stain, original magnification 200x.)

for surface marker analysis. Non-Hodgkin's lymphoma is the most common type seen in the skull base (68).

Lymphoma can involve the skull base by three routes, in decreasing order of frequency: (a) local invasion from a lymphoma of the sinonasal tract, (b) local invasion from a lymphoma of the central nervous system, and (c) primary lymphoma of the skull base. Only a few case reports have described primary skull base lymphomas in the temporal bone and parasellar region (68-70).

Histopathohgy. B-cell lymphomas are diffuse sheets of monomorphous infiltrates of large individual cleaved or immunoblastic cells that invade throughout mucosa, soft tissue, and bone (Fig. 30). The cells have large, irregular nuclei, scant cytoplasm, and an absence of cell junctions. The chromatin pattern is frequently vesicular or cleared, with peripheral ehromatin clumping and prominent nucleoli: mitoses are frequent. Reactivity with B-cell-specific surface antigens such as L26 confirms the phenotype (Fig. 31). The T-cell lymphomas are also diffuse sheets of individual atypical cells that frequently demonstrate necrosis and angioinvasion (Fig. 32). The cytomorphologic appearance is typically more varied, with large, convoluted, and hyperchromatic nuclei and a less obvious monomorphic pattern. Phenotyping with T-cell surface antigens such as UCHL-1 can be performed by immunohistochemistry (Fig. 33).



FIG. 32. T-cell non-Hodgkin's lymphoma showing infiltrating sheets of large, pleomorphic, individual cells with irregular nuclei and scant cytoplasm. (Hematoxylin and eosin, original magnification 200x.)



FIG. 33. T-cell non-Hodgkin's lymphoma. The cells react strongly with UCHL-1, a pan-T-cell antigen. (Immunoperoxidase stain, original magnification 20Qx.)

Phenotyping of unfixed cells by flow cytometry is frequently used in the diagnostic work-up of lymphomas. This requires fresh, finely minced tissue that must be handled rapidly to ensure cell viability.

Differential Diagnosis. The differential diagnosis includes numerous "small round cell" tumors of the head and neck, including alveolar rhabdomyosarcoma, poorly differentiated carcinoma, olfactory neuroblastoma, pituitary adenoma, and Ewing's sarcoma. These can be separated by morphologic and immunohistochemical characteristics. Lympbomas react with leukocyte common antigen, carcinomas with cytokeratin and epithelial membrane antigen, rhabdomyosarcomas with desmin and myoglobin. olfactory neuroblastomas and pituitary adenomas with chromogranin A, and Ewing's sarcoma with a "Ewing's-specific" marker. O13. In addition, the inflammatory pseudotumor with its mixed inflammatory infiltrate can mimic the polymorphic T-cell type of skull base lymphoma. The presence of a clonal infiltrate of T cells, confirmed by predominant UCHL-1 reactivity, or of B cells demonstrated by L26 positivity, distinguishes lymphomas from nonmalignant infiltrates.

MELANOMA

Definition. A melanoma is a malignant proliferation of melanocytes. Although most common in the skin, melanocyles reside along the mucosal surfaces of the upper respiratory tract and may give rise to primary melanomas at sites adjacent to the skull base.

Clinical Features. Melanoma can affect the skull base as a metastatic lesion or, more commonly, from extension of an adjacent sinonasal mucosal melanoma. Primary upper respiratory tract mucosal melanomas arise from melanocytes that have migrated from the neural crest. Most of these tumors occur in the nasal cavity, especially along the nasal septum, lateral wall, and inferior and middle turbinates (71). Grossly, the tumors are sessile or polypoid and may be pink, brown, or black. Mucosal ulceration is common. The traditional histologic staging system for cutaneous melanoma is not applicable to mucosal melanomas because of the lack of histologic landmarks analogous to the dermis (72). Therapy has included surgery, radiation therapy, chemotherapy, and immunotherapy in various combinations; however, the prognosis remains poor, with 5-year survival rates reported as 10% to 45% (71,72).

Rare primary intracranial melanomas have been reported in the meninges and pituitary with involvement of the skull base (73).

Histopathology. Microscopically, the tumor cells are typically large and pleomorphic with epithelioid or spindle morphology. The growth pattern may be papillary, solid, organoid, or mixed (Fig, 34). The cells have large, irregular, and often bizarre nuclei with prominent nucleoli, frequent mitoses, and necrosis. Dense brown cytoplasmic melanin granules may be seen and confirmed by a Fontana stain. A significant number (10-30%) of head and neck mucosal melanomas are amelanotic and require immunohistochemistry with S-100 or HMB-45 antibodies to confirm the diagnosis (Fig. 35). S-100 is a calcium regulatory protein found in cells of neural crest origin, whereas HMB-45 was developed from a melanoma cell line. Rarely, electron microscopy is necessary to demonstrate melanosomes or premelanosomes.

Differential Diagnosis. Melanomas are notorious for mimicking several malignant tumors, including squamous cell carcinoma, adenocarcinoma, neuroendocrine or undifferentiated carcinomas, as well as the "small round cell tumors." The papillary growth pattern can be confused with a papillary carcinoma or atypical papilloma. The diagnosis may be initially missed without a high index of suspicion for this lesion. The identification and confirmation of melanoma is, however, relatively straightforward with modern immunohistochemical techniques.



FIG. 35. Melanoma. HMB-45, a "melanoma-specific" marker, intensely decorates individual tumor cells in this nasal mucosal melanoma. (Immunoperoxidase stain, original magnification 200 x.)



FIG. 34. Melanoma. This sinonasal mucosal melanoma consists of sheets of large, markedly pleomorphic cells with large, bizarre nuclei. Melanin pigmentation is not present. (Hematoxylin and eosin, original magnification 200X.)

Definition. A metastasis is a secondary focus of tumor that has spread from an often distant primary site by lymphatic or vascular routes.

Clinical Features. A surprisingly wide variety of primary tumors can metastasize to the skull base. Often these patients



FIG. 36. Metastatic prostate adenocarcinoma. Nests of infarcted tumor within the bony clivus. The patient presented with a left hypoglossal nerve deficit and no symptoms of prostate disease.



FIG. 37. Metastatic prostate adenocarctnoma. The tumor cells react strongly to prostate-specific acid phosphatase. (Immunoperoxidase stain, original magnification 200X.)

present with cranial nerve deficits or other focal symptoms from the metastatic tumor and are without symptoms referable to the primary site. Not infrequently, the primary tumor is not identified until biopsy tissue is obtained. In a review of 26 cases of sphenoid sinus metastasis, Mickel and Zimmer-man reported prostate and lung as the most common primary sites (74). Other tumors included carcinomas of pancreas, kidney, thyroid, breast, and colon. Skull base metastases have also been reported from the stomach (75), fallopian tube (76), and liver (77).

Histopathology. The recognition of a metastatic carcinoma is relatively straightforward; such lesions are usually easily recognized as tumors "foreign" to a cranial base site. The presence, however, of hemorrhage, necrosis, or infarction may confuse the histologic appearance and create uncertainty. Immunuhistochemical studies may be of assistance by demonstrating the presence of cylokeratin positivity.

Differential Diagnosis. Pituitary adenoma may have a glandular or trabecular appearance that can be confused with metastatic carcinomas such as hepatocellular carcinoma or prostate adcnocarcinoma. Immunohistochemical studies are positive for chromogranin A or pituitary hormones in most cases. Prostate adenocarcinoma has a reliable, organ-specific marker, prostate-specific acid phosphatase (Figs. 36, 37). Metastatic renal cell carcinoma, clear cell type (Fig. 3K) can be confused with hemangioblastoma, a vascular tumor that occurs commonly in the cerebellum. Renal cell carcinoma, clear cell type is positive for epithelial markers such as cytokeratin and epithelial membrane antigen, whereas hemangioblasloma demonstrates vimentin and factor VIII.



FIG. 38. Metastatic renal cell carcinoma, clear cell type. The patient presented with a mass in the infratemporal fossa. Biopsy specimen shows the characteristic trabecular pattern of large, clear epithelial cells in a vascular stroma. (Hema-toxylln and eosin, original magnification 200x.)

CONCLUSIONS

Skull base surgical pathology is a challenging area for diagnostic surgical pathologists. This chapter has attempted to highlight the more common tumors and to emphasize the histologic diversity of tissues and lesions that have been seen in the authors' centers. A summary of the reported experiences of four skull base programs with malignancies is presented in Table 5 (78-80). Squamous cell carcinoma has been the most common lesion, but a significant number of sarcomas, melanomas, and other malignancies have been treated.

The biopsy tissues are typically small and "precious" and require the utmost attention to extract the maximum diagnostic information. It is vital that the skull base surgeon and surgical pathologist establish and maintain a working relationship based on mutual respect and vigilant communication to ensure the highest-quality care for patients with lesions of the skull base.

TABLE 5. *Pathology of malignant skull base tumors: report of recent series*

Report	SCC	ACC	BCC	ONE	Sarcoma	Melanoma	Other
Jackson 1991 (n=122)	37	7	37	3	14	7	14
Janecka 1987–1991 (n=108)	36	16		4	29	5	18
Irish 1982–1992 (n=58)	22	3	8	6	8	1	10
UCDMC 1990–1994 (n=41)	21	4	2	3	3	3	5

SCC, squamous cell carcinoma; ACC, adenoid cystic carcinoma; BCC, basal cell carcinoma; ONB, offactory neuroblastoma; UCDMC, University of California, Davis Medical Center.

REFERENCES

1. Gandour-Edwards R, Donald P, Boggan J. Intraoperative frozen section diagnosis in skull base surgery. *Skull Base Surgery* 1993;3:159.
2. Phelps PD, Beale DJ. The foramen lacerum: a route of access to the cranial cavity for malignant tumors below the skull base. *Clin Radio!* 1992;46:183.
3. Shih L, Crabtree JA. Carcinoma of the external auditory canal: an update. *Laryngoscope* 1990;100:1215.
4. Snyderman CH, Sekhar LN, Sen CN, Janecka IP. Malignant skull base tumors. *Neurosurg Clin N Am* 1990;1:243.
5. Matsuba HM, Spector GJ, Thawley SE, Simpson JR, Mauney M, Pikul FJ. Adenoid cystic salivary gland carcinoma: a histologic review of treatment failure patterns. *Cancer* 1986;57:519.
6. Gandour-Edwards R, Kapadia SB, Barnes EL, Donald PJ, Janecka IP. Neural cell adhesion molecule (N-CAM) in adenoid cystic carcinoma invading the skull base. *Otolaryngol Head Neck Surg* 1997; 117:453^156.
7. Perzin KH, Gullane P, Clairmont AC. Adenoid cystic carcinomas arising in salivary glands: a correlation of histologic features and clinical course. *Cancer* 1978;42:265.
8. Barnes L, Kapadia SB. The biology and pathology of selected skull base tumors. *J Neurooncol* 1994;20:213.
9. Kapadia SB, Janecka IP. Nasopharyngeal carcinoma. *Advances in Otolaryngology and Head and Neck Surgery* 1995;9:247.
10. Batsakis JG, Solomon AR, Rice DH. The pathology of head and neck tumors: carcinoma of the nasopharynx, part 11. *Head and Neck Surgery* 1981;3:511.
11. Weiland LH. Nasopharyngeal carcinoma. In: Barnes L, ed. *Surgical pathology of the head and neck.* New York: Marcel Dekker, 1985:453.
12. Shanmugaratnam K, Sobin L. *Histologic typing of upper respiratory tract tumours.* International Typing of Tumours No. 19. Geneva: World Health Organization, 1978.
13. Shanmugaratnam K, Sobin LH. Histologic typing of tumours of the upper respiratory tract and ear. In: *International histological classification of tumours.* 2nd ed. Berlin: Springer-Verlag, 1991; 32.
14. Scheitauer BW. Surgical pathology of the pituitary: the adenomas (parts 1 and 2). *Pathol Anna* 1984;19:269, 317.
15. Scheithauer BW. The pituitary and sellar region. In: Sternberg S, ed. *Diagnostic surgical pathology.* New York: Raven Press, 1994:493.
16. Kovacs K, Horvath E. Tumors of the pituitary gland. In: *Atlas of tumor pathology.* 2nd Series, Fascicle 21. Washington, DC: Armed Forces Institute of Pathology, 1986:57.
17. Scheitauer BW, Kovacs K, Laws ER, Randall RV. Pathology of invasive pituitary tumors with special reference to functional classification. *JNeurosurg* 1986;65:733.
18. Gandour-Edwards R, Kapadia SB, Janecka IP, Martinez AJ, Barnes L. Biologic markers of invasive pituitary adenomas involving the sphenoid sinus. *Mod Pathol* 1995;8:160.
19. Batsakis JG, El-Naggar AK, Luna MA, Goepfert H. Inflammatory pseudotumor: what is it? how does it behave? *Ann Otol Rhinol Laryngol* 1995;104:329.
20. Chen JM, Moll C, Schotton JC, Fisch U. Inflammatory pseudotumors of the skull base. *Skull Base Surgery \ *994;4:93.
21. Camilleri AE. Craniofacial fibrous dysplasia. *J Laryngol Otol* 1991:105:662.
22. DiRocco C, Marchese E, Velardi F. Fibrous dysplasia of the skull in children. *Pediatr Neurosurg* 1992;18:117.
23. Posnick JC, Wells MD, Drake JM, Buncic JR, Armstrong D. Childhood fibrous dysplasia presenting as blindness: a skull base approach for resection and immediate reconstruction. *Pediatr Neurosurg* 1993; 19:260.
24. Yagoda MR, Selesnick SH. Temporal bone fibrous dysplasia and cholesteatoma leading to the development of a parapharyngeal abscess. *J Laryngol Otol* 1994; 108:51.
25. Ruggieri P, Sim FH, Bond JR, Unni KK. Malignancies in fibrous dysplasia. *Cancer* 1994;73:1411.
26. Voytek TM, Ro JY, Edeiken J, Ayala AG. Fibrous dysplasia and cemento-ossifying fibroma: a histologic spectrum. *Am J Surg Pathol* 1995;19:775.
27. Kapadia SB, Popek EJ, Barnes L. Pediatric otorhinolaryngic pathology: diagnosis of selected lesions. *Pathol Annu* 1994;29:159.
28. Barnes L, Weber PC, Krause JR, et al. Angiofibroma: a flow cytomet-ric evaluation of 31 cases. *Skull Base Surgery* 1992;2:195.
29. Topilko A, Zakrzewski A, Pichard E, et al. Ultrastructural cytochemistry of intranuclear dense granules in nasopharyngeal angiofibroma. *Ultrastruct Pathol* 1984;6:221.
30. Beham A, Fletcher CD, Kainz J, et al. Nasopharyngeal angiofibroma: an immunohistochemical study of 32 cases. *Virchows Arch A Pathol Anat Histopathol* 1993;423:281.
31. Hagen R, Romaic G, Schwab B, et al. Juvenile nasopharyngeal fibroma: androgen receptors and their significance for tumor growth. *Laryngoscope* 1994;104:1125.
32. Barnes L, Peel RL, Verbin R. Tumors of the nervous system. In: Barnes L, ed. *Surgical pathology of the head and neck.* New York: Marcel Dekker, 1985:659.
33. Scheitauer BW. Tumors of the meninges: proposed modifications of the World Health Organization classification. *Acta Neuropathol* 1990;80:343.
34. Winek RR, Scheitauer BW, Wick MR. Meningioma, meningeal hemangiopericytoma (angioblastic meningioma), peripheral hemangiopericytoma and acoustic schwannoma. *Am J Surg Pathol* 1989; 13:251.
35. Kershisnik M, Callender DL, Batsakis JG. Extracranial, extraspinal meningiomas of the head and neck. *Ann Otol Rhino] Laryngol* 1993; 102:967.
36. Vagner-Capodano A, Grisoli F, Gambarelli D, Sedan R, Pellet W, De-Victor B. Correlation between cytogenetic and histopathological findings in 75 human meningiomas. *Neurosurgery* 1993;32:892.
37. Salmon I, Kiss R, Lavivier M, et al. Characterization of nuclear DNA content, proliferation index and nuclear size in a series of 1818 meningiomas, including benign primary, recurrent and malignant tumors. *Am J Surg Pathol 1993;IT.239.*
38. Dulgerov P, Calcaterra T. Esthesioneuroblastoma: the UCLA experience 1970-1990. *Laryngoscope* 1992;102:843.
39. Eden BV, Debo RF, Larner JM. Esthesioneuroblastoma: long term outcome and patterns of failure—the University of Virginia experience. *Cancer* 1994;73:2556.
40. Hirose T, Scheitauer BW, Lopes MDB, et al. Olfactory neuroblastoma: an immunohistochemical, ultrastructural and flow cytometric study. *Cancer* 1995;76:4.
41. Schwaab G, Micheau C, LeGuillou C, et al. Olfactory esthesioneuroma: a report of 40 cases. *Laryngoscope* 1988;98:872.
42. Taxy JB, Bharani NK, Mills SE, Frierson HF Jr, Gould VE. The spectrum of olfactory neural tumors: a light-microscopic, immunohistochemical and ultrastructural analysis. *Am J Surg Pathol* 1986; 10:687.
43. Mills SE, Fechner RE. Undifferentiated neoplasms of the sinonasal region: differential diagnosis based on clinical light microscopic, immunohistochemical and ultrastructural features. *Semin Diagn Pathol* 1989;6:316.
44. Gould VE, Sommers SC. The adrenal medulla and paraganglia. In: Bloodworth JMB Jr, ed. *Endocrine pathology: general and surgical.* 2nd ed. Baltimore: Williams & Wilkins, 1982:497.
45. Barnes L, Taylor S. Carotid body paragangliomas: a clinicopathologic and DNA analysis of 13 tumors. *Arch Otolaryngol* 1990;! 16:447.
46. Barnes L, Taylor S. Vagal paragangliomas: a clinicopathologic and DNA analysis of 13 tumors. *Clin Otolaryngol* 1991;16:376.
47. Kliewer KE, Cochran AJ. A review of the histology, ultrastructure, immunohistology and molecular biology of extra-adrenal paragangliomas. *Arch Pathol Lab Med* 1989;! 13:1209.
48. Weiner ES. Head and neck rhabdomyosarcoma. *Semin Pediatr Surg* 1994;3:203.
49. Mauer Hm, Gehan EA, Beltangady M, et al. The Intergroup Rhabdomyosarcoma Study-II. *Cancer* 1993:71:1904.
50. Callender TA, Weber RS, Janjan N, et al. Rhabdomyosarcoma of the nose and paranasal sinuses in adults and children. *Otolaryngol Head NeckSurg* 1995;112:252.
51. Nayar RC, Prudhomme F, Parise O, Gandia D, Luboiski B, Schwaab G. Rhabdomyosarcoma of the head and neck in adults: a study of 26 patients. *Laryngoscope* 1993;103:1362.
52. Au E, Ang PT, Soh LT. Adult parameningeal rhabdomyosarcoma: a case report and literature review. *Singapore MedJ* 1992;33:415.
53. Healy GB, Upton J, Black PMcL, Ferraro N. The role of surgery in rhabdomyosarcoma of the head and neck in children. *Arch Otolaryngol Head Neck Surg* 1991;! 17:1185.
54. Newton WA, Soule EH, Hamoudi AB, et al. Histopathology of childhood sarcomas, intergroup rhabdomyosarcoma studies I and II:clinicopathologic correlation. *J Clin Oncol* 1988;6:67.

55. Parham DM. The molecular biology of childhood rhabdomyosarcoma. *Semin Dlagn Pathol* 1994;! 1:39.
56. Kveton JF, Brackman DE, Glasscock ME III, House WF, Hitselberger WE. Chondrosarcoma of the skull base. *Otolaryngol Head Neck Surg* 1986;94:23.
57. Hassounah M, Al-Meefty O, Akhtar M, Jinkins JR, Fox JL. Primary cranial and intracranial chondrosarcoma: a survey. *Acta Neurochir (Wien)* 1985;78:123.
58. Austin-Seymore M, Munzenrider J, Goitein M, et al. Fractionated proton radiation therapy of chordoma and low-grade chondrosarcoma of the base of the skull. *J Neurosurg* 1989;70:13.
59. Adegbite ABO, McQueen JD, Paine KWE, Rozdilsky B. Primary intracranial chondrosarcoma: a report of two cases. *Neurosurgery* 1985;17:490.
60. Wojno KJ, Hruban RH, Garin-Chesa P, Huvos AG. Chondroid chordo-mas and low-grade chondrosarcomas of the craniospinal axis: an immunohistochemical analysis of 17 cases. *Am J Surg Pathol* 1991;16:1144.
61. Barnes L. Pathobiology of selected tumors of the base of the skull. *Skull Base Surgery* 1991;1:207.
62. Forsyth PA, Cascino TL, Shaw EG, et al. Intracranial chordomas: a clinicopathological and prognostic study of 51 cases. *J Neurosurg* 1993;78:741.
63. O'Connell JX, Renard LG, Liebsch NJ, Efird JT, Munzenrider JE, Rosenberg AE. Base of skull chordoma: correlative study of histologic and clinical features of 62 cases. *Cancer* 1994;74:2261.
64. Wold LE, Laws ER Jr. Cranial chordomas in children and young adults. *J Neurosurg* 1983;59:1043.
65. Hruban RH, Traganos F, Reuter VE, Huvos AG. Chordomas with malignant spindle cell components: a DNA flow cytometric and immuno-histochemical study with histogenetic implications. *Am J Pathol* 1990;137:435.
66. Mirchell A, Scheithauer BW, Unni KK, Forsyth PJ, Wold LE, Mc-Givney DJ. Chordoma and chondroid neoplasms of the spheno-occiput: an immunohistochemical study of 41 cases with prognostic and noso-logic implications. *Cancer* 1993;72:2943.

67. Burger PC, Scheithauer BW, Vogel FS. *Surgical pathology of the nervous system and its coverings.* 3rd ed. New York: Churchill Living-stone, 1991:360.
68. Han MH, Chang KH, Kirn IO, Kirn DK, Han MC. Non-Hodgkin lym-phoma of the central skull base: MR manifestations. *J Comput Assist* Tbmogr 1993;17:567.
69. Oyama H, Nagane M, Shibui S, Nomura K, Mukae K. Skull base malignant lymphoma: a case report and review of the literature. *Jpn J Clin* Onco/1992;22:131.
70. Tucci DK, Lamber PR, Innes DJ. Primary lymphoma of the temporal bone. *Arch Otolaryngol Head Neck Surg* 1992; 118:83.
71. Stern SJ, Guillamondegui OM. Mucosal melanoma of the head and neck. *Head Neck* 1991;13:22.
72. Lee SP, Shimizu KT, Tran LM, Juillard G, Calcaterra TC. Mucosal melanoma of the head and neck: the impact of local control on survival. *Laryngoscope* 1994;104:121.
73. Chappell PM, Kelly WM, Ercius M. Primary sellar melanoma simulating hemorrhagic pituitary adenoma: MR and pathologic findings. *AJNR Am JNeuroradiol* 1990;! 1:1054.
74. Mickel RA, Zimmerman MC. The sphenoid sinus: a site for metastasis. *Otolaryngol Head Neck Surg* 1990;102:709.
75. Hirai O, Kikuchi H, Hashimoto N. Skull base metastasis. *Head Neck* 1991;13:89.
76. Merimsky O, Inbar M, Grosswasser-Reider I, Neudorfer M, Chaitchik S. Sphenoid and cavernous sinuses involvement as first site of metastasis from a fallopian tube carcinoma. *Tumori* 1993;79:444.
77. Sims RS, Tan HK. A case of metastatic hepatocellular carcinoma of the sphenoid sinus. *J Laryngol Otol* 1994;108:503.
78. Jackson IT, Bailey MH, Marsh WR, Juhasz P. Results and prognosis following surgery for malignant tumors of the skull base. *Head Neck* 1991;13:89.
79. Janecka IP, Sen C, Sekhar LN, et al. Cranial base surgery: results in 183 patients. *Otolaryngol Head Neck Surg* 1994;110:539.
80. Irish JC, Gullane PJ, Gentili F, et al. Tumors of the skull base: outcome and survival analysis of 77 cases. *Head Neck* 1994;16:3.

45. Bartholow R. Aneurysms of the arteries at the base of the brain: their symptomatology, diagnosis and treatment. *Am J Med Sci* 1872;64:374-386.
46. Peet MM. Tumors of the gasserian ganglion: with the report of two cases of extracranial carcinoma infiltrating the ganglion by direct extension through the maxillary division. *Surg Gynecol Obstet* 1927;44:202-207.
47. Parkinson D. A surgical approach to the cavernous portion of the carotid artery: anatomical studies and case reports. *J Neurosurg* 1965;23:474^183.
48. Scoville WB, Sherman IJ. Ptalybasia: report of 10 cases with comments on familial tendency, a special diagnostic sign and the end result of operation. *Ann Surg* 1951;133:496-502.
49. Southwick WO, Robinson RA. Surgical approaches to the vertebral bodies in the cervical and lumbar regions. *J Bone Joint Surg Am* 1957;39:631.
50. Fang HSY, Ong GB. Direct approach to the upper cervical spine. *J Bone Joint Surg Am* 1962;44:1588-1604.
51. Stevenson GC, Storey RJ, Perkins RK, Adams JE. A transcervical tran-sclival approach to the ventral surface of the brain stem for the removal of a clival chordoma. *J Neurosurg* 1966;24:544-551.
52. Haselden FG, Bryce JG. Transoral clivectomy. *Journal of Maxillofa-cial Surgery* 1978;6:32.
53. Crockard HA. Transoral approach to intra/extradural tumors. In: Sekhar LN, Janecka IP, eds. *Surgery of cranial base tumors.* New York: Raven Press, 1993:225-234.
54. Conley J. *Concepts in head and neck surgery.* New York: Grune & Stratton, 1970:117.
55. Donald PJ. Infratemporal fossa and skull base. In: Donald PJ, ed. *Head and neck cancer: management of the difficult case.* Philadelphia: WB Saunders, 1984:306-311.
56. Crumley R, Gutin P. Surgical access for clivus chordoma. *Archives of Otolaryngology* 1989;! 15:295-300.
57. Woods BG, Sadar ES, Levine HL, Dohn DF, Tucker HM. Surgical problems of the base of the skull: An interdisciplinary approach. *Archives of Otolaryngology* 1980;106:l-5.

продолжение

продолжение

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 4

Pathophysiology of Skull Base Malignancies

Keith Jackson, Paul J. Donald, and Regina Candour-Edwards

There is little question that as surgery of the skull base evolves, there is a definite role for combined intracranial and extracranial excision of upper aerodigestive tract malignancies that invade the intracranial cavity. The difficulty in the compilation of meaningful survival statistics lies in the diverse group of tumor types that are involved. Each histologic variant carries with it a specific range of biologic behaviors that are idiosyncratic to it. Predictions regarding anticipated tumor aggressiveness and therefore extent of resection need to be predicated on an understanding of these behaviors. The experience of most surgeons engaged in head and neck oncologic surgery guides the parameters of subcranial resection. Regarding the neurosurgical portion of the resection, the burning question is how do these tumors get to the intracranial space? The next and more important question is that once such tumors invade or cross the skeleton of the skull base, does their biologic character become in any way altered?

There is abundant information regarding site-dependent alterations in biologic behavior of tumors of varying histologic types in the upper aerodigestive tract. For example, squamous cell carcinoma confined to the true vocal cord has a somewhat benign and innocuous behavior until it invades the supraglottic or subglottic region. Regional metastases then become more commonplace and local aggressiveness mandates wide-field resection. Basal cell carcinomas of the facial skin often maintain a relatively benign behavior unless they invade the inner or outer canthi of the eye. Squamous cell carcinoma of the upper lip usually becomes problematic only when it begins to invade the region of the nasal vestibule. Observations made over a 20-year period on over 97 consecutive patients with upper aerodigestive tract malignant tumors that crossed the barrier of the skull base revealed some patterns of pathophysiologic behavior that produce a relatively reliable degree of predictability.

Over the period 1977 to 1997, a series of over 97 patients among the authors' series of 415 skull base surgical patients have been identified who had combined intracranial/extracranial resections for malignancies of the upper aerodigestive tract at the University of California, Davis Medical Center's Center for Skull Base Surgery. Histologic materials and operative records for all patients were reviewed and methods of tumor spread through the cranial base barrier were examined. The patterns of intracranial invasiveness were thereby elucidated. Table 1 summarizes the histologic types and the numbers encountered. The most common lesion (42%) was squamous cell carcinoma. Adenoid cystic carcinoma was the next most common, at 10%.

METHODS OF INTRACRANIAL SPREAD

The intracranial routes of spread of the head and neck tumors in the authors' series are direct. These tumors are not metastatic to the intracranial space. Indeed, central metastases from head and neck carcinomas are decidedly rare. Intracranial neoplasm is a direct extension from the primary.

The most common method of spread is by tumor erosion through skull base bone. The easiest access to the intracranial cavity is through the thin osseous floor of the anterior cranial fossa, through the fovea ethmoidalis and the cribriform plate (Fig. 1). The bone of the fovea is thin and the cribriform plate has multiple perforations through which dural sleeves of the fila olfactoria pass. The usual origin for these tumors is the paranasal sinuses. Another route of spread for sinus tumors is erosion through the bone of the orbital apex and into the anteromedial reaches of the middle cranial fossa (Fig. 2). Ethmoid cancers invading the sphenoid sinus have a thin layer of bone between it and the cavernous sinus that provides an additional avenue of spread to the middle fossa. The posterior wall of the sphenoid sinus in particular, with

---

K. Jackson: Department of Otolaryngology—Head and Neck Surgery, Charles Drew University of Medicine and Science, Los Angeles, California 90059.

P. J. Donald: Department of Otolaryngology—Head and Neck Surgery, and Center for Skull Base Surgery, University of California, Davis Medical Center, Sacramento, California 95817.

R. Candour-Ed wards: Department of Pathology, University of California, Davis Medical Center, Sacramento, California 95817.

TABLE 1. *Malignant cell types*

Cell type	No. of patients
Epidermoid/squamous cell	40
Basal cell carcinoma	6
Adenocarcinoma	3
Sarcoma	1
Undifferentiated carcinoma	2
Melanoma	5
Esthesioneuroblastoma	6
Adenoid cystic	9
Mucoepidermoid	5
Lymphoma	1
Chordoma	4
Chondroma	2
Chondrosarcoma	3
Malignant schwannoma	1
Expleomorphic adenoma	1
Other:	
Renal cell carcinoma	1
Spindle cell carcinoma	2
Myoepithelial carcinoma	1
Dermatofibrosarcoma	1
Leiomyosarcoma	1
Malignant fibrosarcoma	1
Neuroblastoma	1
Total patients (July, 1985 to May, 1997)	97



FIG. 2. Direct spread of tumor from the posterior ethmoid and sphenoid sinuses across the orbital apex and into the middle cranial fossa.



FIG. 1. Avenue of direct spread of tumor through the cribriform plate and fovea ethmoidalis from the ethmoid sinuses.



FIG. 3. Sagittal magnetic resonance image showing direct spread of tumor originating in the posterior ethmoid and sphenoid sinuses through the posterior sphenoid wall into the posterior cranial fossa. This is especially important in patients with postsellar pneumatization.



FIG. 4. Routes of direct tumor spread of nasopharyngeal carcinoma. A: Clival erosion B: Foramen lacerum. C: Foramen ovale. D: Direct erosion of petrous apex.

its pattern of postsellar pneumatization, may be extremely thin, providing easy passage of tumor into the posterior cranial fossa (Fig. 3). The pontine dura is in close proximity, providing the potential for early spread of tumor to a dura that, once resected, is difficulty to repair. The bone of the clivus is commonly eroded by nasopharyngeal carcinoma (NPC), but tumor rarely reaches the posterior fossa. However, further extension laterally often results in erosion of the greater wing of the sphenoid contribution to the middle fossa floor (Fig. 4). Invasion of the foramen lacerum provides access to the canal for the internal carotid artery and the cavernous sinus: a reason why cranial



FIG. 5. Routes of spread to the temporal bone and from the bone to the intracranial space.

nerve IV palsy (see Chapter 15, Fig. 40D) is the third most common presenting sign of NPC. Another common route is through the foramen ovale, which is discussed shortly. Deep-lobe parotid malignancy and malignant connective tissue tumors in the infratemporal fossa may erode directly through the middle fossa floor.

The temporal bone is a target for direct bony extension from the parotid gland, tumors of the pinna, and adjacent facial and scalp skin. Malignancies of the external auditory canal skin, middle ear, and mastoid invade the bone early. All these lesions can then spread directly into the middle and posterior fossae. Posterior fossa spread is uncommon, presumably because the bone between the otic structures and the intracranial space is generally thicker than the tegmentum tympani and mastoideum. The petrous tip may be eroded by malignancies in the sphenoid sinus or in the nasopharynx (Fig. 5).

The cranial vault can be invaded by malignancies in the scalp. The patient in Fig. 6 had a lymphoma refractory to both chemotherapy and radiation therapy. The tumor eroded through the occiput and penetrated the occipital dura and torcular Herophili.

The most common sites of tumor passage are through the foramina in the cranial base.



FIG. 6. A: Magnetic resonance image of patient with a lymphoma and direct spread through the cal-varium to the posterior cranial fossa. B: Intraoperative photograph of invasion of torcular Herophili, showing bipolar cautery and suction of torcula. C: Resection of torcular Herophili.


Depth of the olfactory fossa
4.79 (0.6-11.7)
5.03 (0-15.56)
3.18 (0-10.1)
(mm)
Nasion
20.8 (14.5-26.7)
mm
Neonates 0.32
- Adults 8.10
mm
Cribriform plate
Age
Number
r
l
1 yr. 38 38
2 yrs. 43 (30-48) 41 (28-49)
4. yrs. 43.4 (33-59) 41.3 (30-53)
8. yrs. 41 (31-48) 40.3 (32-47)
Adults 43 (26-60) 44 (29-71)

FIG. 7. Diagram illustrating the numbers of foramina penetrating the cribriform plate. {From ref. 1, p. 121, with permission.)

The foraminal routes to the anterior fossa are through the cribriform plate and the lamina papyracea of the ethmoid bloc. The cribriform plate has 26 to 7 i (average. 43) foramina per side (1) (Fig. 7). The fila olfactoria that penetrate these foramina are first-order neurons that synapse in cell bodies in the olfactory bulbs, The fila are covered in dura and the bulbs are actual extensions of the brain. The fila then present a direct route of tumor spread to the brain. Fortunately, the olfactory bulbs are distinct and separated from the gyri of the frontal lobes above, and only occasionally will tumor spread to them. The ethmoid foramina allow passage of the ethmoid neurovascular bundles from the orbit into the nasal cavity. The unique traverse of these structures provides an intracra-nial route of spread. Emerging from the ophthalmic artery. the ethmoid arteries pierce the lamina papyracea at the suture line between this contribution to the ethmoid bloc and the frontal bone's contribution to the medial wall of the orbit. They enter the intracranial cavity, course a short distance on the floor of the anterior fossa, and then enter the nasal vault (Fig. 8) through the foramina for the olfactory nerves.

The orbital apex provides three routes of perineural spread: the optic canal, the superior orbital fissure, and the


Olfactory bulb
Posterior
Ethmoid arteries
Middle
Anterior

FIG. 8. Cribriform plate and lamina papyracea in coronal view, showing foraminal routes of spread.



FIG. 9, The foramina of the orbital apex provide an easy avenue for intracranial spread. A: View of the orbital apex showing routes of tumor spread. *1,* Superior orbital fissure; *2,* optic foramen; 3, inferior orbital fissure; *4,* vascular foramina for the ethmoid vessels. B: Sagittal cutaway view of the orbital apex with orbital floor and portion of posterior wall of the maxillary sinus removed.

inferior orbital fissure (Fig. 9). The first route is along the optic canal to the optic chiasm, and at the chiasm the proximity of the distal internal carotid artery and the anterior midbrain renders most tumors that reach this far of doubtful operability. At any point along the canal, penetration of tumor laterally into the middle fossa can occur. Similarly, the superior orbital fissure provides tumor access to the cavernous sinus and medial middle fossa. In the inferior orbit, the infraorbital canal leads to the foramen rotundum, and from there to the gasserian ganglion in Meckel's cave.

The fifth cranial nerve branch foramina provide the most common route of intracranial spread of malignancy. Because the sensory supply to me superficial and deep areas of the face is principally through the branches of the trigeminal nerve, tumors are most likely to spread intracranially along these nerve sheaths. The foramen ovale is most commonly affected, followed by the foramen rotundum (Fig. 10}, and then the superior orbital fissure.

Parotid tumor spread along cranial nerve VII is common, but rarely does this spread reach the intracranial cavity. The trigeminal branches, however, commonly provide direct access to the middle fossa. The first stop is the gasserian ganglion. The fifth nerve ganglion sitting in Meckel's cave lying in its dural pocket is frequently the arresting point of tumor spread (Fig. 11). Because of its variable investment by the cavernous sinus, tumor at this site has direct access to this highly vascular space. Tumor spread may then continue along me main trunk of the nerve toward the brain-stem (Fig. 12).

Many malignancies of the upper aerodigestive tract, facial skin, and parotid salivary gland have a propensity for perineural spread. The classic example is the adenoid cystic carcinoma of the parotid salivary gland. Although many adenoid cystic carcinomas are seen with the phenomenon, it is



FIG. 10. Spread of tumor from facial skin along infraorbital nerve to the maxillary nerve through foramen rotundum into the middle fossa.



FIG. 11. Diagram of Meckel's cave showing dural investment of the gasserian ganglion and branches of the trigeminal nerve.

also not an uncommon feature of squamous cell and basal cell carcinoma and is particularly prominent in malignant melanoma and estriesioneuroblastoma. Periodic laboratory and clinical investigation regarding the mechanism of spread along the perineural spaces has still brought no clarity to the issue. That tumor passage is through perineural spaces rather than previously presumed perineural lymphatic vessels has been largely resolved (2.3). What establishes a tumor as a perineural spreader and what gives il the "passport'[7] for such extension is unclear.

Because neuroblastomas commonly spread in the perineural spaces and they are among the few tissues in the post-neonatal period that possess polysialated neuronal cell adhesion molecules (PS-NCAM), PS-NCAMs were thought to be the possible culprits in this phenomenon. Unfortunately, a study of 110 consecutive malignant head and neck tumors showed that the presence of NCAVIs and PS-NCAMs was not statistically different in neurotropic and nonneuroiropic tumors (F.A. Troy, J. Ye, P.J. Donald. R. Gandour-Edwards, J. Mullen. The role of NCAMS in neurotropie spread of head and neck cancer. *Unpublished data,* 1997). The damage done to nerves by the presence of neurotropic tumors, as well as the incidence and some of the extracranial behavioral characteristics of these tumors is nicely elaborated by Carter et al. in an analysis of 36 patients with perineural spread (4). One of the major mechanisms of injury was by macroneu-ronal andmicroneuronal infarction. The perineural spread of head and neck tumors, especially adenoid cystic carcinoma, has the pathognomonic property of running along the afflicted nerve in isolated islands of cells with intervening skip areas. Adenoid cystic tumors are notorious for having skip areas of 1 cm or more of intervening normal nerve between one focus of perineural rumor and the next, although Carter et al. found that disease in most of their patients had spread no further than 1 cm from the primary tumor. The curious phenomenon the current authors have observed is that once the tumor reaches the intracranial compartment, this spread tends to compact, and skip areas are short (—1-2 mm) or nonexistent. This then allows a safety margin of 2 to 3 mm of cranial nerve excision when resecting the intracranial component of the tumor. In the authors' experience, whenever such a margin of rumor resection in cranial nerve was achieved, no loeal rceurrcnce ensued.



FIG. 12. Histologic section showing **spread** of tumor in the perineural space of cranial nerve V (H&E, x100).

A second property of perineural spread is also important. It has long been understood that malignancies in the perineural space remain in the space that way for a considerable time before they extend beyond the confines of the nerve. This is true also when tumor has spread intracranially. Invasion of overlying dura is relatively uncommon, and when it occurs is usually limited in amount. For example, a common route of perineural spread of a subcranial malignancy is along V3, the mandibular nerve. The tumor spreads through the foramen ovale to Meckel's cave. It is not uncommon for the malignancy to remain within the ganglion and not invade its dural covering or, when it does invade the dural covering, to remain confined to a limited area of dura on the middle fossa floor.

Tumor can also extend along blood vessels and gain access to Ihe intracranial compartment through vascular foramina. The two principal foramina lie together in the floor of the middle fossa—the jugular and carotid foramina. The jugular vein is the inferior extension of the sigrnoid sinus. At the jugular bulb area, the inferior petrosal sinus enters the bulb on the medial side. Tumor may peneirate the jugular



FIG. 13. Coronal section through the temporal bone with an obliquity demonstrating the petrous course of the internal carotid artery. (From Donald PJ, Gluckman JL, Rice DH. *The sinuses.* New York: Raven Press, 1995:460, with permission.)


Intima
Media
Adventitia
Periarterial connective tissue
Periosteum

FIG. 14. Diagram showing histologic details of the internal carotid artery in the carotid canal of the temporal bone.



FIG. 15. Fibrous ring of the internal carotid artery at the carotid foramen.

vein in the neck and extend superiorly in the vessel's lumen. The neoplasm may extend into the sigmoid sinus, but it rarely extends into the inferior petrosal sinus. Although ligation of the jugular vein in the neck is taken on with impunity, more circumspection is required when ligating the sigmoid sinus. Although usually without consequence, sigmoid obstruction can very occasionally result in cerebral infarction. The collateral veins between the internal jugular and the vertebral, paraspinous, and deep neck veins provide alternative routes of venous flow when the jugular is taken. A more limited collateral flow through the superior petrosal sinus and the torcular Herophili increases the vulnerability of the brain to vascular insult when the sigmoid sinus is occluded.

The carotid foramen leads to the carotid canal. The canal is shaped like an "L" on its side, with the short limb of the "L" representing the ascending or vertical portion, and the long limb the horizontal portion that courses the length of the petrous bone (see Chapter 2, Fig. 20). The artery emerges from the petrous tip at its articulation with the sphenoid body at the foramen lacerum (Fig. 13). Within the petrous canal, the tissues encircling the artery offer a stout barrier to tumor penetration. Prassad et al. (5) have provided an excellent description of the anatomy of the carotid canal based on a thorough histologic study (Fig. 14). They found that the lining of the canal was a substantial periosteum. Inside the canal, a layer of loose areolar tissue is interposed between the periosteum of the canal and the arterial adventitia. This layer contains the vasavasorium that nourish the vessel. The adventitia, although not as thick *as* its counterpart in the neck, offers the same resistance to tumor penetration as in the neck.

At the entrance to the carotid canal on the undersurface of the temporal bone, the internal carotid artery is encased in a thick band of fibrous connective tissue, the so-called "fibrous ring" (Fig. 15). The ring provides protection for the artery against shearing forces that occur with rapid acceleration and deceleration. This thickening is the last barrier to subcranial tumor penetration of the internal carotid. The tightly woven fibrous tissue of the ring provides tough resistance to arterial invasion, but it is also the site of further tumor extension up the canal. Intraluminal extension of tumor is exceedingly rare.

In the cavernous sinus, the internal carotid artery loses much of its protective fibrous covering (Fig. 16). On the medial side, the artery abuts the lateral wall of the sphenoid sinus and produces its characteristic bulge into the posteroin-ferior aspect of the sinus. A thicker dura is present at this site, providing a much better resistance to extension than the remaining vessel, which is invested with a flimsy layer of dura. Once the cavernous sinus is invaded, either interiorly or laterally, the media of the vessel is readily penetrated.

The next most vulnerable vessels to tumor extension are the ophthalmic veins. They may be present as inferior and superior veins or, rarely, as a single vessel. The two veins join as a common trunk at the orbital apex to drain into the anteroinferior aspect of the cavernous sinus (Fig. 17). These



FIG. 16. Histologic section showing the thin wall of the internal carotid artery in the cavernous sinus (H&E, X100). (From Sando A, Ikui A, Sudo M. Microscopic sectional anatomy with 3-D reconstruction of the temporal bone. In: Janecka I, Tiedemann K, eds. *Skull base surgery: anatomy, biology and technology.* Philadelphia: Lippincott-Raven Publishers, 1997: 173.)


Superior rectus muscle
Superior division of oculomotor nerve
Frontal nerve
Levator muscle
Trochlear nerve
Posterior ethmoidal canal
Superior ophthalmic vein
Superior oblique muscle
Lateral edge of superior orbital fissure
Optic nerve
Nasociliary nerve
Recurrent meningeal artery
Medial rectus muscle
Ophthalmic artery
Central retinal artery
Lateral rectus muscle
Inferior division of oculomotor nerve
Inferior rectus muscle
Abducens nerve
Oculomotor nerve to medial rectus muscle
Sensory root of ciliary ganglion from nasociliary nerve
Oculomotor nerve to inferior rectus muscle
Sympathetic root of ciliary ganglion from carotid plexus
Oculomotor nerve to inferior oblique muscle
Motor (parasympathetic) root of ciliary ganglion
Inferior ophthalmic vein
A
Inferior division oculomotor nerve
Optic nerve
Optic sheath
Optic strut
Superior division oculomotor nerve
Sphenoid sinus
Internal carotid artery
Levator muscle
Superior rectus muscle
Oculomotor nerve
Cavernous sinus
Lateral rectus muscle
Nasociliary nerve
Inferior rectus muscle
Frontal nerve
Abducens nerve
Periorbita
Superior ophthalmic vein (lateral wall removed)
Superior ophthalmic vein
B

FIG. 17. The inferior and superior ophthalmic veins join as the ophthalmic venous trunk leading directly into the cavernous sinus, or enter it separately. **A:** Coronal cut through orbital apex showing superior and inferior ophthalmic veins. **B:** Side view of apex showing superior ophthalmic vein entering cavernous sinus. (From Rhoton AL, Natori Y. *The orbit and sellar region.* New York: Thieme Medical Publishers, 1996:106, 203, with permission.)

veins, which lead directly into the cavernous sinus and are valveless. are the most anterior extension of this sinus. Tumor in the orbit can extend uninhibited through the superior orbital fissure by way of these veins into the cavernous sinus.

Although an uncommon route of vascular spread, the emissary veins offer additional portals of entry. Especially important is the mastoid emissary vein in the case of temporal bone carcinoma or carcinoma of the scalp. The condylar occipital emissary vein is of substantial size, but is rarely involved because of the rarity of tumors in this part of the scalp.

The middle meningeal artery, despite its proximity to the foramen ovale, which is one of the most common highways to the intracranial cavity, is rarely a route of spread superiorly. Tumor may spread to it by extension, but tumors of this region usually remain extracranial.

The foramen lacerurn exists as such only in its superior two thirds (6). Inferiorly, it is plugged with a "cork" of cartilage (see Fig. 13). The foramen, however, does provide a direct avenue of spread of carcinoma from the nasopharynx into the cavernous sinus. In that most NPC are poorly differentiated histologically and have an infiltrativc pattern, spread through this route is not uncommon. This is exemplified by the fact that the third most common presenting sign of NPC (after mass in the neck and hearing loss) is diplopia secondary to cranial nerve VI invasion. It is curious that the cartilaginous plug offers so little resistance to the penetration of NPC.

It is important to reiterate that spread to the intracranial cavity is by direct spread through the aforementioned routes, and not from metastasis.

PATTERNS OF INTRACRANIAL SPREAD

The dissolution of cranial bone by epithelial malignancies has received little attention. In most biologic systems, bone erosion is often this tissue's response to physical pressure. Pressure stimulates the differentiation of ostcoelasts, which erode bone by the elaboration of lytic enzymes such as collagenase (7). Some tumors cause bone erosion by the stimulation of granulocytes and some imacrophages to produce tumor necrosis factors, which can in turn cause bone dissolution. Certain tumor cell lines, such as those for malignant melanoma and one for a maxillary sinus carcinoma, produce granulocyte-macrophage colony stimulating factor that in turn stimulates production of tumor necrosis factor by normal leukocytes (8,9). The spread through the bone, although somewhat irregular, proceeds by relatively short, finger-like projections (Fig. 18). Therefore, it is usually easy to encompass tumor by a relatively narrow margin by using either a cutting saw or a drill (10).

Tumor spread appears to be easier in cancellous bone of the diploe than in the compact bone of the inner and outer calvarial tables. Frozen-section margins of this diploic bone can be taken by curettage because spread is usually wider here than in the overlying compact bone. Throughout this book, the controversy between those surgeons who believe an *en bloc* dissection is mandated in all cases and those who think a "modified" *en blue* resection will safely remove all tumor is apparent (see Chapter 10). Malignant invasion of the calvarial vault is easily circumscribed by the craniotome. bul sphenoid and temporal bone involvement requires the drill and rongeur for removal. This applies as well to the occipital contribution to the clivus and, at times, the atlantooccipital junction. Recurrence at the site of bony involvement after using this modified *en bloc* principle for bony resection has been a distinct rarity.


FIG. 18. Histologic section showing extension of squamous carcinoma in the temporal bone (H&E, x 100). Note the pushing border rather than extension in discontinuity.

Dural involvement has been thought in the past to carry the stigma of incurability. It is unquestionably a sign of advanced disease and carries with it the attendant risks of more frequent distant metastasis and the specter of a second primary. In the authors' scries of cases, however, overall tumor-free survival is dependent in part on dural invasion. Tables 2 through 4 describe the outcomes. Tn 71 consecutive patients (11), 53 had invasion of dura and 18 did not. The tumor-free survival rate at 2 years and longer is 39.6% for those with dural involvement, and 55.6% for those without. The local control rate at 2 years and better was somewhat better for the dura negative cohort with a local control rate of 69.8% for the group with dural invasion and 83.3% for those without.

The spread in the dura is again by continuity, and tumor extensions appear to be short and the tumor compact (Fig. 19).'Dural margins appear to be adequate when taken about 5 to 7 mm from grossly visible or palpable tumor. The secret to safe resection is in obtaining numerous frozen sections. At times, dural margins need to be closer, such as in invasion of pontine dura. In these cases, a technique similar to the Mohs micrographic technique used in the dermatologic removal of cutaneous malignancy is adopted (12,13).

Dura seems to resist penetration of tumor to the brain (14). Tn the authors' series, only 13 patients had extension to brain (11). Patients may have tumor in the dura for months and, in a few unusual cases, even years without extension into adja-

TABLE *2. Outcome of skull base surgery patients related to dura! involvement*

	A&W		DOD		DOC		DDOLD		AWD		Total	
	2^a	5^a	2	5	2	5	2	5	2	5	2	5
Dura positive	21	13	16	15	13	9	1	2	2	2	53	41
Dura negative	10	6	3	1	5	3	0	0	0	0	18	10
											71	51

A&W, alive and well without disease; DOD, dead of local disease; DOC, dead of other causes (no local disease); DDOLD, dead of distant metastasis without local disease; AWD, alive with disease. ″ Years of follow-up.

cent brain tissue. The patient in Fig, 20 had an anterior craniofacial resection in 1988 for mucuepidermoid carcinoma. She had a local recurrence in the right supraorbital area but refused further surgery and was treated with 3 cycles of chemotherapy. She continues to have no radiographic evidence of dural persistence of tumor, is alive and appears otherwise well 10 years later.

Brain invasion is a poor prognostic sign, not just because of the site of invasion, but because it speaks to the aggressive character of the malignancy. At 2 years, 13 patients were evaluated, and at 5 years or longer, 10 patients. At 2 years, 5 of 13 patients were alive without disease, but at 5 years or longer, only 1 of 10 patients was alive and tumor free (Table 5). Local control both centrally and subcranially was fairly good, but unfortunately distant metastases, intercurrent diseases, and second primary tumors were responsible for the deaths of many of the patients.

Resection of brain is feasible in large part because of the pattern of central spread. Upper aerodigestive tract and other subcranial cancers spread in the brain very differently than primary brain malignancy. Primary brain malignancies tend to extend in the brain substance by discontinuous spread. Islets of tumor cells are often detected in the brain at considerable distance from the primary, rendering complete resection incompatible with life or productive of grave morbidity. Unlike these lesions, the subcranial tumors tend to have pushing margins. They have a layer of necrosis and edema that precedes the advancing tumor front (Fig. 21), This layer of necrosis is seen as a ring of lucency surrounding the tumor on magnetic resonance imaging (MR1; Fig. 22) and computed tomography (CT) scan.

The extent of brain tissue removal obviously depends on the region of involvement. The frontal lobe or anterior temporal lobe usually can be removed with little consequence because they are considered "silent areas." The brainstem, however, is an area where tumor cannot be safely resected. Tumor, if benign, can usually be carefully dissected from its surface in limited areas, but invasion by malignancy is invariably fatal. The cerebellum can be excised but at the expense of ataxia and often persistent and sometimes debilitating headache. Removal of parts of the motor strip or pericalcarine area is almost never required because tumors of

TABLE 3. *Survival rate related to dural involvement (%*

	2 yr	5 yr
Dura positive	39.6	25.6
Dura negative	55.6	60.0
Total	43.7	47.1

TABLE 4. *Local disease-free control (%)*

	2 yr	5 yr
Dura positive	69.8	63.4
Dura negative	83.3	90.0
Total	73.3	68.6

absolute)

TABLE 5. *Survival of skull base surgery patients when brain is invaded*

	A&W	DOD	DOC	Total
2 yr	5	6	2	13
5 yr	1	4	5	10

A&W, alive and well without disease; DOD, dead of local disease; DOC, dead of other causes (no local disease).



FIG. 19. Compact nature of tumor spread in dura (H&E, x40).



FIG. 20. Anterior craniofacial resection for mucoepidermoid carcinoma done in 1988. A: Lateral rhinotomy approach to tumor. B: One year after surgery. C: Magnetic resonance image showing biopsy-proven persistent tumor in 1991. D: Frontal view of patient in 1996, apparently tumor free 6 years after chemotherapy. Patient refused further surgery.



FIG. 21. Histologic section demonstrating area of edema and necrosis (arrows) preceding advancing tumor front (H&E, X100).

the skull base rarely reach that far, but such invasion **would** be considered a sign of inoperability.

Because of the pushing nature of the tumor, brain is resected just in front of the zone of necrosis (Fig. 23). A 2- to 5-mm margin usually produces clearance beyond the lesion. Frozen section is again a vital element in guiding the resection.

Cavernous sinus invasion continues to provide one of the most formidable challenges to the complete resection of malignancy. Extension to the sinus can occur through the manifold connections and extensions of this highly vascular structure (Fig. 24). One of the principal impediments to complete resection is the rich network of interconnections between the sinuses of opposite sides: The principal connections are first through the circular sinus surrounding the pituitary gland and in the diaphragma sella, and second through the basilar plexus of veins traversing the cranial surface of the clivus. Bilateral involvement is considered by the authors' skull base team as a sign of inoperability. The cavernous sinus has connections to bridging veins from the cerebral surface and numerous extracranial connections, principally by way of the ophthalmic vein and the vein to the pterygoid plexus. It is connected to the inferior and superior pelrosal sinuses at the petrous apex.



FIG. **22.** Lateral magnetic resonance image showing area of edema and necrosis preceding tumor front *(arrows)* of poorly differentiated carcinoma.



FIG. 23. Resection of frontal lobe of brain with a 5-mm margin of normal brain surrounding tumor depicted in Figure 22.

The nature tit" the sinus has been the topic of considerable debate. Some vigorously support the notion that it is a purely venous structure, and others contend that it is a network of interconnecting vascular spaces. Johannes Lang, the noted German head and neck anatomist, at the First International Skull Base Conference in Hannover, Germany in 1992, pronounced a masterfully diplomatic anatomic compromise, stating that it was "a little of both." Sepehrnia (15) has demonstrated in an elegant anatomic study the absence of the essential criteria for a venous structure. He demonstrated the presence of fibrous trabeculations without fibrous or neural structures and could see no histologic evidence of venous tissue. Alencastro (16.17), in a series of histologic preparations, found evidence of endothelium lining trabecular structures, and at some sites found fat between this lining and the outer surface of the internal carotid artery.

продолжение



B

FIG. 24. The cavernous sinus. A: Oblique view showing connections to the opposing side through circular sinus and basilar plexus. B: Connections of cavernous sinus to cerebral vessels by bridging veins and extensions to superior orbital fissure and into foramen of trigeminal nerve.

TABLE 6. *Two-year and 5-year survival rates of patients with cavernous sinus involvement*

A&W			DOD		DOC		AWD		Total	
	2	5	2	5	2	5	*2*	5	2	5
No. Survival (%)	13 59.1	5 25	3 13.4	8 40	4 18.2	5 25	2 9.1	*2* 10	22 NA	20 NA

A&W, alive and well without disease; DOD, dead of local disease; DOC, dead of other causes (no local disease); AWD, alive with disease; NA, not applicable.

Independent of the debate, one fact is clear, and that is that surgery in the cavernous sinus is nightmarishly difficult. It is tucked away in the geographic center of the head, houses the major supply of blood to the ipsilateral cerebral hemisphere, and has cranial nerves II through VI traversing it or in close proximity.

In the authors' series of patients, 25 had cavernous sinus invasion. There are 2-year follow-ups on 22 and 5-year follow-ups on 20. The fate of these patients is described in Table 6. Survivorship obviously is related to the amount of the sinus involved. In an earlier study, seven patients who had no evidence of disease at 3-year follow-up had had an average of 24% of the sinus involved, and in the five of those seven who had recurrences in the sinus, the average involvement was 56%.

In light of the high local recurrence rate and the dismal survival of patients with extensive cavernous sinus involvement, the authors have redesigned their surgical attack in this area. With greater than 40% of the sinus involved, a complete removal of the sinus is done that includes complete removal of its lateral dural wall; resection of the carotid artery, which is replaced with an interposition graft; removal of the venous and venous sinus connections that are in the vicinity; and excision of all the bone in the proximity of the sinus. Although early signs are encouraging, only the test of time will prove the efficacy of this more radical approach.

METASTATIC DISEASE TO THE SKULL BASE

Approximately 1.2 million new cases of cancer were diagnosed in 1995. Prostate cancer was the most frequently diagnosed new cancer, followed by breast, lung, colorectal, and skin (melanoma). Over a half-million patients will die from cancer (18). A significant mortality factor is metastatic disease.

True metastasis is distinguished from secondary extension, which is a manifestation of local growth factors. Furthermore, metastasis can be divided into regional and distant types; common to each is secondary spread outside of the confines of the primary tumor.

A *single* skull base metastasis refers to an isolated lesion with no implication about the extent of cancer elsewhere in the body. The term *solitary* metastasis, on the other hand, describes the rare occurrence of an isolated lesion with no other evidence of metastatic cancer elsewhere in the body.

Skull base metastases have become a more recognized entity despite the lack of detailed studies on this phenomenon.

Incidence

The true incidence of skull base metastases is unknown; they are frequently included with cerebral metastasis data. The estimated overall incidence of brain metastasis is in the range of 12% to 35% of all cancer patients (19,20). Most authors state the incidence is underreported. In fact, many authors believe the incidence of metastatic brain tumors is higher than that of primary brain tumors (18,21,22).

The largest series dealing with skull base metastasis demonstrated breast, lung, prostate, and head and neck carcinomas as the most common malignancies (23). Table 7 illustrates the sources of the primary tumors in this series of 51 patients (23). Table 8 shows the sites of these metastases.

Skull base metastases tend to localize to certain areas. The middle fossa, jugular foramen, and parasellar sites are most frequently involved.

Specific Sites

The most detailed studies on skull base metastases were on those located in the orbit and temporal bone. Metastatic tumors to the temporal bone are uncommon and usually are seeded by the hematogenous route. Marrow-containing areas, most notably the petrous portion, may promote the development of metastatic lesions. The slow blood flow in the marrow acts as a filter mechanism, allowing tumor cells to propagate. The most common metastatic lesion in the temporal bone is breast carcinoma (24,25). Lung, prostate, and renal carcinomas are all well documented for their metastatic potential to the temporal bone (26).

Metastatic Orbital Malignancies

Malignant tumors metastatic to the orbit represent 3% to 5% of all solid orbital mass lesion (27-29). Font et al. (30),

TABLE 7. *Primary sites of cancer in patients with metastasis to the base of the skull*

Primary tumor	No. of cases
Breast	19
Lung	6
Prostate	6
Head and neck	8
Lymphoma	3
Renal	2
Miscellaneous	7

TABLE 8. *Metastases to skull base and location*

Primary tumor	Clival	Orbit	Parasellar	Middle fossa	Jugular foramen	Occipital condyle
Breast	0	3	3	7	2	4
Lung	0	? 1	1	2	1	1
Prostate	1	0	2	1	1	1
Head and neck	0	1	0	3	4	0
Lymphoma	0	0	t	1	0	1
Renal	0	1	0	0	1	0
Miscellaneous	0	0	1	2	1	2

in a study of 28 metastatic tumors to the orbit, demonstrated that 20% were breast carcinomas and 14% were lung cancers. Less common sites included kidney, prostate, testis, pancreas, and ileum.

Pathophysiology

Two major routes have been suggested for metastatic tumors to reach the brain and skull base. Blood-borne tumor emboli may reach the skull base through small arteries that freely anastomose and branch at the neural foramina. Tumor-derived factors enhance invasion of the thick arterial walls. In addition, Batson in 1940 (31) described the rich plexus of veins and anastomotic connections that allow intraabdominal neoplasms to propagate tumor emboli throughout the body. These veins are valveless and, with increased intraabdominal and intramoracic pressure, blood is shunted through the vertebral, prevertebral, and epidural venous networks. This can allow tumor emboli to reach the skull base (Figs. 25-27).

Direct extension from adjacent regions such as paranasal sinuses, external ear, and nasopharynx, although not representing true metastasis, accounts for a significant proportion of secondary skull base neoplasms. The overall incidence of skull base invasion by sinonasal malignancies appears to be approximately 15% (32) (Fig. 28). There are different routes of extension, particularly along the muscles attached to the skull base, the fibrofatty spaces between these muscles, along neurovascular bundles, and through the foramina (33) (Fig. 29).


Superior sagittal sinus
Falx cerebri
Inferior sagittal sinus
Great cerebral vein
Straight sinus
Transverse sinus
Tentorium cerebelli
Superior and inferior petrosal sinuses
Falx cerebelli
Occipital sinus
Sigmoid sinus
Posterior internal vertebral plexus
Posterior external plexus
Anterior internal plexus
Basi vertebral veins
Anterior external plexus
Basilar plexus (sinus)
Facial vein
Maxillary vein
Pterygoid plexus
Inferior ophthalmic vein
Cavernous sinus
Superior ophtlamic vein
Supraorbital vein

FIG. 25. Venous anatomy of vertebral column, skull, and skull base.


Posterior vertebral plexus
Anterior and posterior longitudinal sinuses (veins)
Lumbar vein
Ascending lumbar vein
Intervertebral vein
Anterior vertebral plexus
Basivertebral vein

FIG. 26. Venous anatomy of vertebral body.


Hemiazygos vein
Azygos vein
Subcostal vein
First lumbar vein
Ascending lumbar vein
Ascending lumbar vein
Second lumbar vein
Third lumbar vein
Inferior vena cava
Fourth lumbar vein
Iliolumbar vein
Common iliac vein
External iliac vein
Internal iliac vein
Median sacral vein

FIG. 27. Venous anatomy of vertebral column and relationship to renal and pelvic venous systems.



FIG. 28. Magnetic resonance image demonstrating na-sopharyngeal carcinoma extending to right middle cranial fossa.



CIG. 29. Orbital computed tomography scan demonstrating ;e-neural spread from supraorbital cutaneous squamous cell cancer to orbital apex and cavernous sinus.

ff



FIG. 30. Computed tomography scar, of a patient presenting with dysarthria, demonstrating destructive mass of right jugular bulb involving temporal and occipital bones. A biopsy showed renal cell carcinoma.

Presenting Signs and Symptoms

Metastases to the skull base affect the neurovascular structures entering the foramina at the basicranium. Invasion of bone by metastatic primary tumor is the most common cause of pain in patients with cancer, and such pain usually precedes neurologic signs and symptoms by weeks (34). Green-berg et al. (23) described five clinical syndromes: orbital, parasellar, middle fossa, jugular foramen, and occipital condyle (Fig. 30). The current authors include a sixth—clival.

The orbital syndrome is characterized as progressive, dull, continuous pain in the supraorbital area of the affected eye. This is followed by diplopia and hypesthesia over the ophthalmic division of the trigeminal nerve. As the metastasis enlarges, proptosis and ophthalmoplegia result.

The parasellar syndrome is characterized as a unilateral frontal headache and ocular paresis without proptosis or visual loss. Other signs and symptoms, including pituitary dysfunction and hypesthesia, can occur.

The middle fossa syndrome is characterized by facial pain and paresthesia or numbness over the second and third divisions of the trigeminal nerve. When the tumor is on the anterior surface of the petrous ridge, the abducens nerve is likely to be affected at Dorello's canal. When the lesion involves the posterior surface, the facial and vestibulocochlear nerves can be affected.

The jugular foramen syndrome is characterized by paralysis of cranial nerves IX through XII with resultant hoarseness, dysphagia, atrophy of the sternocleidomastoid and upper trapezius muscles, as well as weakness of the palate.



FIG. 31. T1-weighted, gadolinium-enhanced magnetic resonance image showing same renal cell carcinoma metastatic to the right jugular bulb as in Fig. 30.

Occipital or postauricular pain commonly occur, referred to the vertex (Fig. 31).

The occipital condyle syndrome is characterized by severe, unilateral occipital pain exacerbated with flexion of the neck and cranial nerve XII paralysis. Owing to the proximity of the jugular foramen, associated signs and symptoms may occur.

The clival syndrome is characterized by vertex headache exacerbated by head flexion. Lower cranial nerve dysfunction (VI-XII) begins unilaterally, but often becomes bilateral.

Diagnostic Assessment

Patients with skull base lesions that are radiographically suggestive of metastases but who have no known primary cancer need histologic confirmation. An extensive search for a primary is not undertaken until the diagnosis is confirmed. Once histologic study confirms metastasis, CT scans of the chest, abdomen, and pelvis may prove helpful for identifying the primary site. Likewise, sputum cytology and blood tests for more markers may aid in the diagnosis.

Patients with known cancer represent most of the patients with skull base metastases. The need for tissue diagnosis should be individualized according to the site, suspected type, and the prognosis and overall condition of the patient.

A search for leptomeningeal metastasis should be considered. Cytology is the most important examination, but high opening pressures and elevated protein can also be present. Tumor markers such as carcinoembryonic antigen and (3-glucuronidase can be helpful once the initial diagnosis of leptomeningeal metastasis is made (35).

Radiologic Evaluation

Because of their insidious onset, skull base metastases are often difficult to identify initially on MRI or CT scan. Prostate and lung cancers may produce metastases that are either lytic or blastic in nature. Most other metastases produce only lytic lesions. Radionuclide scanning is the most sensitive method for detecting skull base metastasis (36).

Computed tomography scans with high spatial resolution, bone algorithm, and bone windowing are superior to MRI for delineating osseous destruction or sclerosis (Figs. 32, 33). MRI is superior to CT for delineating the soft tissue component of metastases and for determining invasion of cranial nerves, the underlying dura, leptomeninges, and brain (Figs. 34, 35). Gadolinium enhancement further increases sensitivity. Positron emission tomography may be useful for following or distinguishing between recurrent tumor and necrosis secondary to radiation therapy or chemotherapy, provided the initial evaluation shows increased fluorodeoxyglucose uptake (22).

Surgical Management and Recommendations for Treatment

It is evident from the surgical results of the 1990s that the resection of a single brain metastasis not only can improve a patient's neurologic condition, but can increase the rates of local control and survival (37,38). Patients with a single skull base metastasis are the most appropriate surgical candidates. However, Bindal et al. have demonstrated that at least with regard to brain metastasis, removal of multiple metastatic lesions is as effective as resection of single metastasis as long as each lesion is removed in its entirety (39).



FIG. 32. Metastatic prostatic carcinoma of clivus.



FIG. 33. Metastatic breast adenocarcinoma of right parasellar region.



FIG. 35. Corresponding magnetic resonance image of metastatic breast adenocarcinoma (see Fig. 33) showing intracranial extension.

The resectability of each lesion should be assessed independently.

It is equally important to consider the tumor's radiosensitivity and chemosensitivity before proceeding with surgery. Small cell lung cancer, lymphoma, and germ cell tumors are particularly sensitive to radiation and chemotherapy. Therefore, radiation and chemotherapy protocols are indicated. On the other hand, melanoma, renal cell carcinoma, and sarcomas are radioresistant and surgical resection should be considered. Most other neoplasms are intermediately sensitive to radiation, and surgery combined with radiation therapy may be used.



FIG. 34. Corresponding magnetic resonance image of prostatic cancer (see Fig. 32) showing proximity to middle fossa dura.

Stereotactic radiosurgery remains a potential option, but no prospective, randomized trials have been performed. Additional concerns over side effects, including osteoradionecrosis, must be considered.

Not all patients with skull base metastases are candidates for surgical resection. Ultimately, ideal surgical candidates are selected carefully by analyzing the clinical status of the patient, pertinent radiographic studies, and the tumor's histologic characteristics. Based on the neurosurgical data, resection of skull base metastases seems promising. With recently developed skull base approaches and microsurgical techniques, it appears that gross total removal could approach the 90% resection capabilities quoted in the neurosurgical literature (40).

CONCLUSIONS

Epithelial and connective tissue malignancies adopt a fairly predictable method of invasion when making the transition from the upper aerodigestive tract and its supporting tissues to the intracranial space. Perineural spread is idiosyncratic of certain tumors, and this avenue of tumor extension is one of the principal means of access of the cranial cavity. Dura provides a stout barrier to tumor spread, as does the periosteum lining the carotid canal. Brain invasion of these cancers proceeds in a fashion that is in stark contrast to the behavior of primary tumors. The presence of dural invasion does not adversely affect survival results compared with skull base tumors without such invasion. Resection of invaded brain is compatible with local tumor control in a significant percentage of patients.

Cavernous sinus and internal carotid artery involvement are unfavorable prognostic signs. Local control is difficult and second primaries as well as distant metastases are not uncommon. Nevertheless, cavernous sinus and internal carotid artery invasion are not incompatible with local control and cure.

An isolated skull base lesion may represent a distant metastasis from a primary at a remote site below the clavicles. Biopsy and careful histologic analysis are necessary to rule out such a phenomenon and prevent an extensive and unnecessary surgical procedure.

Skull base surgery is in evolution. Continued study of the pathophysiologic behavior of malignancies that invade both intracranial and extracranial compartments and the modification of surgery and adjunctive measures in light of these findings should improve the prognosis of this cohort of challenging and deserving patients.

REFERENCES

1. Lang J. *Clinical anatomy of the nose, nasal cavity and paranasal sinuses.* New York: Thieme Medical Publishers, 1989:121.
2. Larson DL, Rodin AE, Roberts DK, O'Steen WK, Rappaport AS, Lewis SR. Perineural lymphatics: myth or fact. *Am J Surg* 1996;! 12:488^192.
3. Rodin AE, Larson DL, Roberts DK. Nature of the perineural space invaded by prostate carcinoma. *Cancer* 1967;20:1772-1779.
4. Carter RL, Foster CS, Dinsdale EA. Perineural spread by squamous carcinomas of the head and neck: a morphological study using antiaxonal and antimyelin monoclonal antibodies. *J Clin Pathol* 1983;36:269-275.
5. Prassad S, Barnes L, Janecka I. Anatomy of the internal carotid artery. Presented at the Third Meeting of the North American Skull Base Society, Acapulco, Mexico, Feb. 16-20, 1992.
6. Tiedemann K. Cross sectional anatomy. In: Janecka IP, Tiedemann K, eds. *Skull base surgery: anatomy, biology and technology.* Philadelphia: Lippincott-Raven Publishers, 1997:118-119.
7. Chole RA. Differential osteoclast activation in endochondral and intramembranous bone. *Ann Otol Rhlnol Laryngol* 1993;102:616-619.
8. Yoneda T, Mundy OR, Roodman GD. Induction of differentiation of the human promyelocytic HL-60 cells into cells with the osteoclastic phenotypes. *J Bone Miner Res* 1989;4:559.
9. Sabbatini M, Chavez J, Mundy GR, Bonewald L. Stimulation of tumor necrosis factor release for monocytic cells by the A-375 human melanoma via granulocyte-macrophage colony stimulating factor. *Cancer Res* 1990;50:2673-2678.
10. Kinney S, Woods BC. Malignancies of the external auditory canal. *Laryngoscope* 1987;97:158.
11. Donald PJ. The significance of invasion of key intracranial structures in skull base surgery for malignancy. Presented at the Triological Society Meeting, Scottsdale, Arizona, May, 1997.
12. Mohs FE. *Chemosurgery: microscopically controlled surgery for skin cancer.* Springfield, IL: Charles C Thomas Publisher, 1978.
13. Tromovitch TA, Stegman SJ. Microscopically controlled excision for skin tumors. *Arch Dermatol* 1974;! 10:231-232.
14. Krespi YP, Levine TM, Sisson GA. *Tumor surgery of the skull base.* AAO Instructional Program. Vol. 2. St. Louis: Mosby, 1989:279-288.
15. Sepehrnia A. True microsurgical anatomy of the human cavernous sinus. Presented at the Second International Skull Base Congress, San Diego, California, June 29-July 4, 1996.
16. Alencastro LC. The anterior loop of the carotid siphon. *Skull Base Surgery* 1991; 1:73-77.
17. Alencastro LC. Commentary on Tromovitch TA, Stegman SJ. Microscopically controlled excision for skin tumors. *Arch Dermatol* 1974;! 10:231.
18. Wingo PA, Tong T, Bolden S. Cancer statistics, 1995, *CA Cancer J Clin* 1995 ;45:8-30.
19. Galicich JH, Arbit E, Wronski M. Metastatic brain tumors. In: Wilkins RH, Rengachary SS, eds. *Neurosurgery.* 2nd ed. New York: McGraw-Hill, 1996:807-821.
20. Posner JB, Chernik NL. Intracranial metastases from systemic cancer. *Adv Neural* 1978; 19:579-592.
21. Posner JB. *Neurologic complications of cancer.* Contemporary Neurology Series, Vol. 45. Philadelphia: FA Davis Co., 1995:3-14, 77-110.
22. Walker AE, Robins M, Weinfeld FD. Epidemiology of brain tumors: the National Survey of Intracranial Neoplasms. *Neurology* 1985; 35:219-226.
23. Greenberg HS, Deck MDF, Vikram B, et al. Metastasis to the base of the skull: clinical findings in 43 patients. *Neurology* 1981;31:530-537.
24. Feinmesser R, Libson Y, IMely B, Gay I. Metastatic carcinoma to the temporal bone. *Am J Otol* 1986;7:119-120.
25. Hill BA, Kohut RI. Metastatic adenocarcinoma of the temporal bone. *Archives of Otolaryngology* 1976;102:568-571.
26. Schuknecht H, Allam A, Murakami Y. Pathology of secondary malignant tumors of the temporal bone. *Ann Otol Rhinol Otolaryngol* 1968:77:5-22.
27. Henderson JW. *Orbital tumors.* 2nd ed. New York: Brian C. Decker, 1980:451^71.
28. Reese AB. Expanding lesions of the orbit (Bowman Lecture). *Transactions of the Ophthalmological Society of the United Kingdom* 1971;91:85-104.
29. Silva D. Orbital tumors. *Am J Ophthalmol* 1968;65:318-339.
30. Font RL, Ferry AP. Carcinoma metastatic to the eye and orbit: III. a clinicopathologic study of 28 cases metastatic to the orbit. *Cancer* 1976;38:1326-1335.
31. Batson O. The function of the vertebral veins and their role in the spread of metastases. *Ann Surg* 1940; 112:138-149.
32. Weymuller E, Reardon E, Nash D. A comparison of treatment modalities in carcinoma of the maxillary antrum. *Archives of Otolaryngology* 1980; 106:625-629.
33. Vignaud J, Pharabaz C, Mourag M. Tumors of the skull base. In: Portman M, ed. *Rhino-otological microsurgery of the skull base.* Edinburgh: Churchill Livingstone, 1995:40-65.
34. Raj PP, Phero JC. Pain control in cancer of the head and neck. In: Thawley W, Panje W, Batsakis J, et al, eds. *Comprehensive management of head and neck tumors.* Philadelphia: WB Saunders, 1987: 42-68.
35. Chamberlain MC, Friedman HS. Leptomeningeal metastasis. In: Levin V, ed. *Cancer in the nervous system.* New York: Churchill Livingstone, 1996:281-290.
36. Schaefer P, Budzik R, Gonzalez G. Imaging of cerebral metastases in management of cerebral metastases. *Neurosurg Clin N Am* 1996; 7:393^116.
37. Patchell RA, Tibbs PA, Walsh JW, et al. A randomized trial of surgery in the treatment of single metastases to the brain. *N Engl J Med* 1990:322:494-500.
38. Vecht CJ, Haaxma-Reiche H, Noordijk EM, et al. Treatment of single brain metastasis: radiotherapy alone or in combination with neurosurgery? *Ann Neural* 1993;33:583-590.
39. Bindal AK, Bindal RK, Hess KR, et al. A comparison of surgery and radiosurgery in the treatment of brain metastasis. / *Neurosurg* 1995;82:355A(abst).
40. Arbit E, Wronski M. Clinical decision making in brain metastasis in management of cerebral metastasis. *Neurosurg Clin N Am* 1996; 7:447^57.

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 5

□

Presentation and Preparation of Patients with Skull Base Lesions

PaulJ. Donald

Patients presenting with lesions of the skull base can be entirely asymptomatic or in horrible pain with an obviously large tumor and dysfunction of multiple cranial nerves. The asymptomatic patient may have a radiographic finding that was discovered during routine investigation of an unrelated problem, whereas the symptomatic patient not uncommonly has had extensive prior therapy and a persistent lesion.

Many of the subsequent chapters describe some presenting signs and symptoms of patients with skull base lesions; this chapter, with a few exceptions, is designed to present as exhaustively as possible the clinical picture that typifies patients who have lesions of areas involving the anterior, middle, and posterior cranial fossae or central compartment (Fig. 1).

PRESENTATION ACCORDING TO SITE

Symptoms arise according to functional disturbances of the system involved. Obviously, multiple systems may be compromised with more advanced disease processes. Often, a single presenting symptom alerts the patient to seek medical attention. Unfortunately, the symptom may be dismissed by the primary care physician, and not until further organ dysfunction has occurred is the practitioner spurred to either a more in-depth investigation or referral to the appropriate specialist. The insidious dangers posed by the scourge of managed care, especially its most heinous variety—capitation—include discouragement of expensive investigative procedures and specialist referral. As a result, in regions of the country where these systems have heavily intruded, more and more tumors and other disease processes are not being seen until they have reached an advanced stage.

Facial Skin

With the avidity of so many people for the sun and the increasing danger posed by the diminished atmospheric protection to skin-damaging ultraviolet irradiation, cutaneous malignancy is becoming increasingly commonplace. Added to this is the popularity of tanning booths, which appear to appeal particularly to the young.

Basal cell carcinoma is the most frequent skin lesion observed. Fortunately, most of these tumors begin as an actinic keratosis and remain as such for a considerable time. However, many or most of these eventually progress to an invasive carcinoma. The early basal cell tumor is commonly very small and enlarges slowly over a period of years. Certain basal cell carcinomas are important for their implications for skull base surgery. These are the tumors in susceptible areas: those that have had multiple recurrences, sclerosing types, and neurotropic varieties. The most susceptible areas for skull base spread are the canthal areas of the eyes (Fig. 2), the nasal-facial groove, the external auditory canal, and postauricular skin (Fig. 3). Multiple recurrences speak to the aggressiveness and invasiveness of a specific tumor (see Fig. 3). Failures of well done Mohs resections are particularly worrisome. It is abundantly clear that basal cell carcinomas must be completely excised with histologically tumor-free margins (albeit narrow in Mohs resections). Opinions to the contrary are continuously refuted by the high frequency of local recurrence if total resection is not effected. Sclerosing basal cell carcinomas are characteristically aggressive and commonly recurrent. Such tumors often require a much wider resection than the nodular type (Fig. 4). When recurrent, they are especially difficult to encompass. They have a particular propensity to spread into the orbit and the anterior cranial fossa and from the ear to the middle cranial fossa. Some of these are multifocal, presenting a therapeutic dilemma that often defies solution (Fig. 5).

P. J. Donald: Department of Otolaryngology—Head and Neck Surgery, and Center for Skull Base Surgery, University of California, Davis Medical Center, Sacramento, California 95817.



FIG. 1. Diagram outlining the various regions of cranial base surgery.

Neurotropism is a property not uncommonly seen in cutaneous neoplasms, and it is seen in squamous cell carcinoma, basal cell carcinoma, and malignant melanoma. Neurotropic basal cell cancers are not seen as commonly as the other two. Any facial numbness in a patient with a history of cutaneous malignancy must be carefully investigated for the possibility of neurotropic spread (Fig. 6). As in adenoid cystic carcinoma of glandular origin, there may be skip areas along nerves in the subcranial course of these lesions. Spread as far as the cavernous sinus can occur without clinical evidence of spread beyond the nerve sheath {Fig. 7).



FIG. 2. Basal cell carcinoma of the lateral canthal skin. The patient eventually required orbital exenteration to effect complete tumor removal.



FIG. 3. Elderly patient with extensive basal cell carcinoma of the auricle after numerous prior resections requiring extensive temporal bone and skull base resection.

In patients who have had orbital exenteration, rhinectomy, or temporal bone resection for skin cancer (especially if it is recurrent), it is important to keep the cavity open, covered only with a split-thickness skin graft, for at least 2 years. Major flap reconstruction obscures deep recurrences that can be effectively treated when small and superficial. Current investigative modalities such as computed tomography, magnetic resonance imaging, and positron emission tomography still do not provide sufficient information regarding early recurrence. Early detection is obscured by flaps as well as by-postoperative and postradiation fibrosis (Fig. 8).

Nose **and Paranasal Sinuses**

Nose

Although malignancies can originate in the nasal skin and present with nasal symptoms, their gross appearance often detracts from the appreciation of the more subtle symptoms of nasal dysfunction. Nasal obstruction, epistaxis. and foul nasal drainage are the most common symptoms of intranasal and sinus tumors, whether benign or malignant. Pain is uncommon. The patient shown in Fig. 9 had symptoms of nasal obstruction for over 3 years and had been treated for allergic rhinitis until a palatal mass, bulging cheek, and proptosis alerted the treating physician to obtain a referral. Figure 10



FIG. 4. A sclerosing basal cell carcinoma required a resection much wider than initially expected. A: Original tumor in cheek adjacent to nose, with resection outlined. B: Amount resected to achieve complete removal.



FIG. 5. Sixty-four-year-old patient with face covered in multi-oie basal cell carcinomas.



FIG. 6. Magnetic resonance image of a patient who had a carcinoma of the skin resected previously. He complained of numbness over his cheek. This coronal section shows enlargement and enhancement of the infraorbital nerve, characteristic of perineural spread.



FIG. 7. Magnetic resonance image of cutaneous squamous cell carcinoma that invaded only the infraorbital nerve but remained confined by the perineural sheath and extended all the way to the cavernous sinus. Tumor in ptery go maxillary space indicated by *arrow.*



FIG. 9. Nineteen-year-old patient with a massive nasopha-ryngeal angiofibroma mistaken for allergy (see text). Note proptosis of left eye and bulging of left cheek and intracranial extension.



FIG. 8. Patient status postsurgery for tonsillar carcinoma who complained of pain in the infratemporal fossa. A: Axial magnetic resonance image showing no tumor in the infratemporal fossa, but area obscured by postradiation and postsurgical fibrosis and free flap reconstruction. B: Similar view taken 19 months later, finally demonstrating recurrent tumor.



FIG. 10. Angiogram of 14-year-old boy with a large nasopharyngeal angiofibroma, showing feeding vessels from the internal carotid system. Arrow points to feeding vessels from cavernous internal carotid artery. (From Lyons BM, Donald PJ. Intracranial juvenile angiofibroma with intradural and cavernous sinus involvement. *Skull Base Surgery* 1992:2:87-91, with permission.)

shows the angiographic appearance of the nasopharyngeal angiofibroma that had spread to the cavernous sinus in the same patient. Complete tumor removal was effected by a combination extended transpalatal and middle fossa excision.



FIG. 11. Elderly woman with large squarnous cell carcinoma :• - ssal cavity and maxillary and ethmoid sinuses presenting •- an obvious intranasal mass that causes deformity of : . e-iying soft tissues.



FIG. 12. Elderly woman with an impact tumor with esthesioneuroblastoma and squamous ceil carcinoma that has eroded the nasal bones and expanded the overlying skin.

The nasal obstruction may be entirely painless and. if extending far anteriorly, not necessarily accompanied by nasal drainage. The mass may produce an external deformity. This deformity may be simply a mechanical swelling caused by displacement of soft tissue (Fig. 11} or erosion through the nasal bones with expansion of the overlying skin (Fig. 12). The symptom of anosmia usually accompanies the obstruction.

Epistaxis is the most common presenting symptom of nasal and paranasal sinus carcinoma. It may be intermittent and scant in amount, or massive and necessitate packing and hospitalization (Fig. 13). If scant, it usually is unilateral, but



FIG. 13. Elderly man with a massive ethmoid carcinoma protruding from nostril and displacing the right eye, admitted for profuse epistaxis. Note displacement of globe.

if bilateral but still bleeding in small amounts, an extensive tumor penetrating the nasal septum would be suspected. Heavy bleeds are often bilateral and do not help in the diagnosis of sidedness of tumor. Foul smell often accompanies any epistaxis, but Lhis symptom may arise from tumor necrosis or sinus obstruction with secondary purulent sinusitis. Indeed, the fever, facial pain, purulent drainage, and nasal obstruction may lead the unwary physician to a diagnosis of sinusitis, unmindful of the possible presenting obstruction by tumor. A careful nasal examination often reveals the presence of the obturating neoplasm.

Maxillary *Sinus*

Tumors of the maxillary sinus can present in multiple ways, depending on the wall of penetration. If the sinus is envisioned as a six-sided box, transgression of each wall presents with a distinctive array of symptoms (Fig. 14). Based on this paradigm, invasion of the sinus floor produces loosening or protrusion of teeth and palatal swelling (Fig. 15). Further extension may produce an ulcerating mass (Fig. 16), Teeth may be painful or numb. Similarly, the palate and gum may be hypesthetic or anesthetic. An ill-fitting denture is a common complaint in tbe edentulous patient. Invasion of the anterior wall of the sinus "box" leads to cheek swelling (Fig. 17) and, when more advanced, overlying skin ulceration



FIG. 14. Maxillary sinus with superimposed six-sided box paradigm. (From Donald PJ. Diagnosis of tumors of the paranasal sinuses and nasal cavity. In: Thawley SE, Panje WR, eds. *Comprehensive management of head and neck tumors.* Philadelphia: WB Saunders, 1987:304-326, with permission.)



FIG. 15. Palatal swelling from squamous carcinoma of maxillary sinus.



FIG. 16. Adenoid cystic carcinoma with ulceration of palate.



FIG. 17. Massive cheek swelling secondary to large tumor of the maxillary sinus.



FIG. 18. Elderly woman with bulging and erythema of skin secondary to invasion from large squamous cell carcinoma of the maxillary antrum invading the skull base.

(Fig. 18). The proximity of the infraorbital nerve can lead to cheek anesthesia by direct invasion. Often this may be the single presenting symptom (Fig. 19). Lateral invasion of the sinus is often asymptomatic in the early stages, Then, as the infratemporal fossa is invaded, the patient complains of trismus when the muscles of mastication are invaded, especially the pterygoids and the insertions of the temporalis. Invasion **of** the mandibular division of the trigeminal nerve produces deep-scaled pain in the fossa and numbness anterior to the ear and the scalp above through compromise of the auricular-temporal nerve (Fig. 20). Posterior wall penetration is another sign of an advanced lesion. Invasion of the pterygoid muscle origins produces trismus and involvement of the maxillary nerve, resulting in mid-facial pain and numbness.



RG. 19. Axial computed tomography scan of middle-aged fttnan with an adenoid cystic carcinoma of nasal septum, r'-^oid sinuses, and orbital apex that invaded the infraor-: •- nerve and that was not apparent on scans. Patient pre-^red with the solitary symptom of cheek numbness for 1



FIG. 20. Same patient as in Fig. 19. Tumor penetration through the lateral maxillary wall reaches the infratemporal fossa and from there to the foramen ovale. Again, no tumor seen at these sites in scans.

Dry eye results from spread to the lacrimal nerve or the sphenopalatine ganglion; it is rarely complained of because concern is diverted by the severity of the other symptoms.

The final wall in the box paradigm is the roof, which comprises the orbital floor and medially is a part of the floor of the ethmoid labyrinth. Involvement of the orbit produces orbital displacement superiorly, proptosis, eye pain, diplopia, and painful movement of the eye (Fig. 21). The periorbita is quite resistant to tumor penetration and often the apex of the orbit is more involved than the anterior part, especially if tumor penetrates the posterior sinus wall as well as the roof. Diminished visual acuity, cheniosis, and ocular motility disturbance imply penetration of periorbita and a poor prognosis for ocular sparing during subsequent surgery. Epiphora is the result of invasion of the lacrimal sac or nasal lacrimal duct. Sudden blindness is very uncommon and usually is the result of vascular occlusion rather than direct nerve invasion.

The intracranial invasive route of maxillary sin



FIG. 21. Orbital displacement of maxillary carcinoma.

us cancers p sinuses into the anterior
cra

продолжение

продолжение

nial fossa, or from the pterygomaxillary space and the infratemporal fossa into the middle cranial fossa.

Ethmoid Sinus

The ethmoid labyrinth can be the *de novo* site of origin of tumors or the route of spread from maxillary sinus neoplasms (see preceding discussion). The roof of the ethmoid, the fovea ethmoidalis. contributes significantly to the anterior fossa floor. This bone is exceeded only by the lamina papyracea in its thinness. This latter bony component comprises much of the medial wall of the orbit, and orbital symptoms are common in tumors affecting this sinus. The eye is pushed laterally and out (see Fig. 13). but if the frontal sinus is also invaded, the eye may be displaced laterally and inferiorly. The ethmoid tumor, rather than invading the frontal sinus *per se,* often ends up obstructing the nasofrontal duct, producing an expanding mucocele. The mucocele, with its own distinctive bone-eroding characteristics (1), penetrates the orbital roof, displacing the globe downward and outward (Fig. 22). This is almost never accompanied by diplopia. Diplopia usually results from invasion of ocular muscles or their innervation. The exception is the rapidly growing neoplasm that produces marked displacement in a short time.

Epistaxis and foul nasal drainage are common. Pain in or behind the eye or in the bridge of the nose may be present and is often confused with ethmoid sinusitis.



FIG. 22. Frontal sinus mucopyocele secondary to obstruction from inverting papilloma with intracranial penetration displacing globe downward and outward.



FIG. 23. Tumor of frontal sinus creating a bulge of the overlying skin. Coronal incision marked out for craniotomy portion of excision.

***Frontal** Sinus*

Malignancies involving the frontal sinus are rare. Frontal and ethmoid mucoceles and mucopyoceles are much more prevalent and can result from ductal obstruction by benign or malignant tumors, as already mentioned. Extensive ethmoid tumors invading the frontal sinus are much more common than those lesions beginning as frontal sinus primaries. The tumors of this sinus have three direct routes of spread: anteriorly to the forehead skin, inferiorly into the orbit and nose, and posteriorly into the anterior cranial fossa.

Forehead extension is appreciated as a mass lesion bulging the soft tissues of the forehead (Fig. 23). Orbital in-



FIG. 24. Elderly woman with a frontal sinus squamous cell penetrating the upper eyelid.



FIG. 25. Intraoperative photograph of same patient as in Fig. 24. showing penetration of the posterior frontal sinus wall and extensive involvement of anterior fossa **dura.**

vasion not only produces the downward and outward displacement already described, but tumor may penetrate the eyelid, producing an exophytic ulceration (Fig. 24). Posterior invasion penetrates the thin bone of the wall and infiltrates the adjacent dura (Fig. 25). Penetration to the frontal lobe of the brain or occlusion of the superior sagittal sinus is extremely rare (see Chapter 4).

Forehead and retroorbital pain are common symptoms. Numbness over the forehead indicates invasion of the supraorbital, supratrochlear, or frontal nerves.

Sphenoid ***Sinus***

Slightly less rare than frontal sinus malignancies are primaries of the sphenoid sinus. Like the frontal sinus, the sphenoid is a common site of spread for malignancies from other sites. The posterior ethmoid sinuses, the maxillary sinuses (advanced tumors with posterior penetration; Fig. 26), and the nasopharynx are the usual primary sites. Pituitary tumors, lesions of the cavernous sinus, and clival tumors can spread to the sinus.



FIG. 26. Intraoperative photograph of young woman with squamous cell carcinoma of the maxillary sinus eroding the posterior sinus wall and involving the sphenoid sinus lateral

Sphenoid sinus mucoceles and mucopyoceles are often radiographically indistinguishable from solid tumors (Fig. 27). Symptoms are also similar, with headache, retroorbital pain, diplopia, and diminished vision the common presentations of both types of lesions. The characteristic sign of tumor, bone erosion, is not uncommon with chronic infections at this site.

Nasal examination, even aided by endoscopic inspection, may not reveal the presence of tumor. If the anterior wall has been breached and the sphenoethmoid recess entered, the endoscope will provide a view of the neoplasm.

The most common route of direct tumor spread is laterally into the cavernous sinus. In a capacious sinus, spread may be into the middle cranial fossa after crossing the orbital apex (Fig. 28; see also Chapter 4). It is curious that so few tumors breach the flimsy bone of the sella and invade the pituitary. The author has yet to see a patient with an advanced malignant tumor of the sphenoid sinus presenting with hypopituitarism.

Posterior wall penetration provides access to the posterior cranial fossa. The tough periosteum of the cranial side of the clivus interposes a strong barrier to further tumor penetration.

Central Invasion

Tumors of the nose and paranasal sinuses can directly invade any of the three cranial fossa floors. Often, intracranial invasion is entirely asymptomatic. A generalized headache, and especially one directed to a fossa of potential involvement, should alert the physician to intracranial spread and dural involvement. Increased intracranial pressure due to mass effect causes headache as well. This is uncommon and



FIG. 27. Axial magnetic resonance image showing mass lesion filling the sphenoid sinus with extensive bone erosion. Distinction between mature mucopyocele and tumor cannot be made.



FIG. 28. Intraoperative photograph of patient with extensive maxillary, ethmoid, and sphenoid sinus carcinoma extending across the orbital apex and reaching into the middle cranial fossa and invading the temporal lobe.

usually means the tumor has breached the dura and invaded the brain.

Primary nasal and ethmoid tumors can invade the cribriform plate, and esthesioneuroblastomas usually take origin there. Erosion may cause a cerebrospinal fluid (CSF) leak, but this is extremely uncommon. Anosmia is common, but often secondary to nasal obstruction rather than invasion of the olfactory bulbs. Frontal lobe areas, being "silent," produce few to no symptoms if invaded.

Extension of tumor to the middle fossa is usually through the foramen ovale, the superior orbital fissure, the optic canal, the foramen rotundum, or the lateral wall of the sphenoid sinus. Tumor through the foramen ovale invades Meckel's cave and, if malignant, infiltrates the gasserian ganglion. Cancers that initially presented with mandibular nerve symptomatology then produce numbness and tingling over the cheek (maxillary branch) or forehead and eyelid (ophthalmic branch).

Foramen rolundum invasion compromises the maxillary nerve, producing the symptoms described previously. Rarely, the vidian canal is involved, and may be manifested by a dry eye due to compromise of the nerve of the pterygoid canal. Patients uncommonly complain of this symptom.

Superior orbital fissure invasion presents symptoms indistinguishable from those of cavernous sinus involvement. Careful inquiry may pick up an isolated III or IV nerve palsy. Isolated lateral rectus palsies can occur as tumors erode through the lateral sphenoid sinus wall into the cavernous sinus, picking off the nerve as it courses in the medial aspect of this venous sinus. Temporal lobe invasion is usually anterior, uncommonly seen, and most often asymptomatic. More advanced extension can produce seizures and even speech disturbance.

Erosion of the posterior wall of the sphenoid sinus can produce invasion of dura and a spontaneous CSF leak (see Chapter 26, Fig. 24). Superior spread can invade the optic nerves, creating a bi temporal hornonomous hemianopsla or blindness. This is an extremely rare symptom.

Ear and Temporal Bone

The clinical presentations of the various neoplasms are well covered in the chapters devoted to lesions of the ear and temporal bone, especially those in Section IV, Midline Approaches. Malignancies of the pinna, retroauricular skin, and preaurkular area that invade the skull base are tumors of substance. They are usually exophytic and deeply ulcerative (Fig. 29). They are painful, weeping (sometimes exuding a mixture of serum and CSF), prone to bleed with minor trauma, and unsightly. Some neglected lesions even present crawling with maggots (Fig. 30). Such tumors are so unsightly that one wonders why these patients would endure such an array of symptoms before visiting a physician. Often what brings these people in is the sudden onset of facial paralysis (Fig. 31). This is usually complete, but a careful topographic localization should be made regarding the extension of tumor to the geniculate ganglion with the production of dry eye.

Hearing loss is common and may be simply a conductive loss brought about by obstruction of the external auditory canal by the bulk of the tumor, ossicular erosion, or the dampening of ossicular movement by the presence of tumor



FIG. 29. Large squamous cell carcinoma beginning in skin of auricle.



FIG. 30. Squamous cell carcinoma of the pinna in a reclusive middle-aged man. Tumor extended intracranially and into cervical muscles. Lesion was crawling with maggots at the time of presentation.

in the middle ear cleft, Erosion of the cochlea or invasion of the internal acoustic canal produces a sensorineural deafness. Involvement of the labyrinth produces vertigo. With malignancies involving the ear, this is unusual. In acoustic tumors, it is an important symptom, as is hearing loss, which is thoroughly covered in Chapter 23. Although true vertigo is uncommon, disequilibrium and a feeling of fullness and pressure are produced by tumor in the external auditory canal or middle ear and mastoid.

Erosion of tumor into the temporomandibular joint produces trismus. Auriculotemporal nerve involvement brings on numbness anterior to the ear and in the scalp above, If widespread in the occipital scalp, tumor invasion of the occipital nerve produces numbness from the nuchal line to the vertex. Tumor extension through the fissures of Santorini of the cartilaginous external auditory canal to the parotid gland often brings about facial nerve branch weakness, then branch paralysis, and finally paralysis of the main division of the entire nerve.

Spread of tumor to the jugular bulb may produce weakness or paralysis of cranial nerves IX, X, and XI with dys-phagia, hoarseness, and shoulder weakness. Thrombosis of the jugular vein and sigmoid sinus is usually asymptomatic.

Nasopharynx

Nasopharyngeal lesions may begin in the mucosa, as in the case of nasopharyngeal carcinoma, or in the bone, as in chordoma. The most common benign tumor in the nasopharynx is juvenile nasopharyngeal angiofibroma. and squamous cell carcinoma is the most common of the malignant tumors. Masses in the nasopharynx obstruct nasal breathing and either obtund or impede the function of the eustachian tube. Angiofibromas tend to block the tube and the malignancies invade it. Next to the symptom of a mass in the neck, hearing loss from serous otitis media is the second most common presenting complaint of nasopharyngeal carcinoma. Rhinor-rhea due to the lack of mucus clearance and epistaxis may be present, especially in angiofibroma. Bleeding from nasopharyngeal cancer is uncommon and usually runs down the back of the throat. Epistaxis from angiofibroma varies in severity from minor to catastrophic. Chordoma. chondromas, and chondrosarcomas of the clivus rarely protrude so far into the nasopharynx to produce this symptom.

Nasopharyngeal carcinoma has two avenues of direct access to the intracranial cavity: the foramen ovale and the foramen lacerum. The latter is close to the nasopharynx an-terolaterally. The tumor penetrates the cartilage plug at the inferior end. then travels along the artery as it exits the temporal bone and enters the cavernous sinus (Fig. 32). In doing so, it invades the abducens nerve, producing a lateral rectus palsy—the third most common initial symptom of nasopharyngeal carcinoma. Moreover, the tumor may travel along the path of the internal carotid in its horizontal course through the petrosa. The mode of entry up the foramen ovale occurs as the tumor spreads laterally from the nasopharyngeal vault through the foramen of Morgagni from the fossa of Rosenmiiller, then along the cartilaginous tube on the un-dersurface of the temporal bone. On reaching the foramen ovale, which is nearby, the tumor travels to MeckeFs cave along the mandibular branch of cranial nerve V, Lower facial



FIG. 31. Elderly man with a 10-year history of a basal cell carcinoma of the pinna who did not present until lesion caused a facial nerve paralysis.



FIG. 32. Magnetic resonance image of middle-aged man with adenoid cystic carcinoma of the nasopharynx that invaded the foramen lacerum, then followed the intrapetrous and intracavernous course of the internal carotid artery. Arrow points to internal carotid artery surrounded by tumor.



FIG. 33. Nasopharyngeal carcinoma prolapsing below the level of the right soft palate.


Digastr.
Gg. sous-digastr.
Tronc thyro-ling. fac.
Amygd. phar.
Collecteurs de la région sup.
Trompe d'Eust. (région sup.)
Coll. méd.
Lymph. du voile
Pilier post.
Amygd. palat.
Repli pharyngo-épiglott.
Vaisseaux post. (région inf.)

FIG. 34. The node of Rouviere adjacent to the jugular foramen. (From Rouvie>e H. *Anatomie des lym-phatiques.* Libraries de Pacademiede Medecine. Paris: Masson, 1932:109, with permission.)

hypesthesia, deep infratemporal pain, and masticatory weakness or trismus result.

Indirect visualization of the nasopharynx with a mirror or directly by endoscopy reveals the tumor. Occasionally the tumor is seen bulging the palate or prolapsing into the oropharynx (Fig. 33). Lesions primary to clival bone rarely produce symptoms of nasopharyngeal dysfunction. Posterior neck pain, pain over the mastoid tip, neck stiffness, and then signs of cord and brainstem compression, if the tumor begins **to** encroach on the brainstem and cord, may result. Symptoms of central involvement are described in detail in Chapters 22 and 26.

Oropharynx, Parotid Gland, and Upper Neck

Lhese three entities are described together because the mode of spread of cancer to the intracranial compartment is so similar. The common route is through the infratemporal fossa and through the foramen ovale and even foramen spinosum. Superficial lobe parotid tumors and especially deep lobe malignancies invade through the foramen spinosum along the facial nerve. Oropharyngeal primaries, most commonly from the tonsillar area, tend to invade deeply through the superior constrictor muscle to the medial pterygoid and the inferior alveolar nerve as it enters the mandible. Neurotropic tumors by perineural spread make their retrograde course through the foramen ovale. Such invasion and spread to the pterygoid muscles cause trismus. Such spread may begin as distantly as the alveolar ridge or lip. extend to the mental nerve, make its way up the inferior alveolar to the mandibular branch of the trigeminal, and traverse the foramen ovale (see Chapter 15, Fig. 34).

Similar spread is seen with high cervical lymph nodes as they extend superiorly. Spread to the jugular foramen is not uncommon, producing IX, X, and XI nerve symptoms (the so-called "jugular foramen syndrome") and not infrequently symptoms from cranial nerve XII as it exits the hypoglossal canal close by. This is a particular peculiarity of lymph nodal metastasis from the nasopharynx to the node of Rouviere, which is the highest retropharyngeal lymph node in the neck (Fig. 34). Symptoms from the metastasis may precede any from the primary tumor.

THE INTERVIEW

Much of the process of patient intake and the patient's subsequent hospital course is covered in detail in Chapter 8. It is probably prudent quickly to review the usual procedure that the typical patient with a skull base lesion goes through during the first visits to the host of consultants comprising the cranial base team.

The patient is often apprehensive, having frequently undergone multiple therapies and considered by many previous consultants to be inoperable and incurable. This is particularly germane to the head and neck oncologic patient who has usually already undergone chemotherapy, radiation therapy, and surgery. This also applies to the neurosurgical patient who may have undergone multiple less-than-complete operations (e.g., for meningioma or chordoma) and now has neurologic compromise as a result of regrowth of residual neoplasm.

A thorough history and complete examination then ensue, including a thorough head and neck and complete neurologic assessment. Meticulous examination of all cranial nerves is especially important.

A careful review of past medical records, operative reports, radiographs, and special tests is conducted, which does not always entirely agree with the referring physician's verbally presented summary that preceded the consultation. Attention is specifically directed toward the pathology report, and histologic slides should be reviewed by the designated skull base pathologist to confirm the accuracy of diagnosis. Similarly, the outside films are reviewed by the team neuroradiologist and the appropriateness of further studies is determined.

At the conclusion of the history and physical examination, the examining physician makes a tentative assessment of the case and the possibilities for subsequent treatment. Sometimes, a definitive statement regarding the nature of approach and degree of resection can be done at this first visit, but most often these decisions are contingent to some degree on the findings of more refined testing and therefore delayed until these results are in.

For those patients who are treatable, either by surgery alone or in combination with adjunctive measures (which make up the vast majority of those seen), there is often a great sense of relief in the patient and family. To be suddenly reassigned from the ranks of the hopelessly incurable to the status of possibly or probably resectable is a source of enormous joy. Soon after, the appreciation of the compromise of some functions and the possibility of complications integral to the proposed surgery serves to dampen some of this initial enthusiasm. It is essential for the surgeon realistically and dispassionately to detail to the patient and family the key elements of surgery, the risks, the potential benefits, and the possible complications. Most patients wish a complete explanation of all the facts surrounding the surgery and its consequences. Realistic expectations must be transmitted to the patient, but, when appropriate, should be suffused with an air of optimism. Undue dwelling on the possible complications (although it is essential to outline them sufficiently) only adds to the fear and apprehension from which the patient already suffers. Morbid preoccupation with these details for the sake of a sense of medicolegal security for the physician can do enormous harm to the confidence and sense of well-being in a patient already committed to surgery. In our modern, litigious society, this is a very difficult element to manage. The message is that adequate but not necessarily excessive information be transmitted to the patient and family.

Next comes the time for questions. Often, during the first visit, this takes as long as the assessment. Posing the questions does much to dissipate the anxiety built up during the physician's explanation phase. Sometimes the content of the question is of marginal relevance. The ventilating process is, however, of great benefit to the patient. The physician's answer is most beneficial when it is couched in a sympathetic and friendly tone and given in language the patient can understand. A hard, clinical, detached demeanor simply aggravates the apprehension and does little to dispel the patient's fear. The questioning also provides the physician with an opportunity to judge how realistic the patient is about his or her disease and therapeutic expectations.

One of the principal issues often raised is that of quality of life. Many times, the question arises without a clear understanding of its implications. Especially for the cancer patient, an understanding that the current day they are experiencing will probably be the best day of the rest of their life if further treatment is withheld brings a perspective that usually has not occurred to them. Predicted deficits of function and appearance must be weighed against the prospect of a deforming, agonizing, painful death from cancer.

This interview is only the first step in the total assessment of the patient. All the consultants involved in the patient's care participate in the process.

The essential role of the skull base surgery team coordinator now comes into play. The coordinator orchestrates all the consultations with the various members of the surgical team, schedules computed tomography, magnetic resonance imaging, positron emission tomography, and angiography, obtains outside radiographs and pathology specimens, and schedules and coordinates the skull base surgery team pretreatment conference. The coordinator forms an important connection with the medical insurance companies and even, at times, arranges accommodations for patients' families.

TABLE 1. *Skull base surgery team members*

Head and neck surgeon
Neurologic surgeon
Otologist/neurotologist
Plastic surgeon
Neuroradiologist
Pathologist
Ophthalmologist
Skull base surgery operating room nurse coordinator
Skull base surgery clinical coordinator
Head and neck oncologic clinical nurse specialist

All the various team members (Table 1) contribute valuable input to the management of these difficult and complex patients. The conference provides a forum for free discussion and, once all input is considered, the final formulation of the operational plan for definitive treatment.

The patient is now ready for surgical treatment. A final meeting with the intake physician, who is usually either a head and neck, plastic, or neurosurgeon, provides an opportunity for final questions and the signing of the consent form.

Constant contact with the patient and family before and during surgery and in the recovery phase provides the continuity they require through this difficult ordeal.

REFERENCE

1. Fenton WH Jr, Donald PJ, Carlton W III. Pressure exerted by mucoceles in the frontal sinus: an experimental study in the cat. *Arch Otolaryngol Head Neck Surf;* 1990;! 16:836-840.

Surgeiy of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers. Philadelphia © 1998.

CHAPTER 6

Imaging of the Skull Base

Alfred L. Weber and Hugh D. Curtin

The skull base represents a bony partition between the intracranial cavity and facial structures, including the orbits, nasal cavity, paranasal sinuses, and nasopharynx. Multiple foramina within the skull base and fissures transmit nerves and vessels that are also pathways for spread of disease processes.

Endoscopic inspection provides some information concerning lesions adjacent to the skull base, but involvement of the skull base can be assessed only by radiologic means, principally by computed tomography (CT) and magnetic resonance imaging (MRI) (1,2).

Imaging characteristics are important in the preoperative assessment of anatomic location and extent of skull base lesions. Especially with the advent of newer skull base surgical techniques, the lesion's precise location and definition of its extent and relationship to vascular structures and cranial nerves have assumed great importance (3,4).

This chapter summarizes the radiologic techniques and their indications for evaluation of the skull base, along with the most important findings of various lesions.

COMPUTED TOMOGRAPHY AND MAGNETIC RESONANCE IMAGING: TECHNIQUES AND GENERAL DIAGNOSTIC CRITERIA

Computed Tomography

Computed tomography is the method of choice for assessment of bony structures, foramina, fissures, and canals (carotid) and for evaluation of calcifications. Likewise, CT is optimal for assessment of the paranasal sinuses, nasal cavities, pharynx, and infiltrative orbital lesions. The examination is carried out using 3- to 5-mm axial and coronal sections with a bone and soft tissue window algorithm.

The disadvantages consist mainly of the inadequate display of the intracranial structures, such as dura, meninges, and brain. Furthermore, CT does not allow direct acquisition of sagittal images, which provide optimal demonstration of lesions in the sagittal and immediate parasagittal planes. These structures include the sella, clivus, foramen magnum, cribriform plate area, and nasopharynx. Reconstructed sagittal images (from 1- to 2-mm axial sections) may be applied in cases where MRI is unavailable. On CT, tumor is usually isodense with muscle, whereas secretions in an obstructed sinus cavity have low attenuation values (water density). However, secretions with a high protein content are isodense with muscle and cannot be differentiated from tumor. After the introduction of iodinated contrast material, the mucosal lining of a sinus cavity enhances, along with variable enhancement of tumor but no enhancement of secretions.

Magnetic Resonance Imaging

Magnetic resonance imaging has been the most important development in the assessment of skull base lesions. MRI superbly demonstrates the intracranial contents (dura, meninges, and brain), and lesion conspicuity is considerably improved after the introduction of gadolinium (gadopentetate meglumine).

The examination is performed in the axial, coronal, and sagittal planes with 3-mm sections. All signal intensities (Tl- and T2-weighted, and proton-density images) are used for evaluation of the anatomy (Tl-weighted images) and lesion characterization (T2-weighted images). Gadopentetate with fat suppression is mandatory for defining intracranial tumor extension and differentiation of cystic from solid lesions. Gradient-echo images and magnetic resonance angiography define the vascular anatomy in relation to tumors and cysts and may also depict hypervascularity of lesions (angiofibroma).

The cortical bone of the skull base is indicated by a signal void. Some bony structures have a medullary cavity, which contains fatty marrow and can be differentiated from the cortex by signal differences. The clivus has a fat-con-

A. L. Weber, H. D. Curtin: Department of Radiology, Harvard Medical School and Massachusetts Eye and Ear Infirmary, Boston, Massachusetts 02114.

taining marrow cavity that is characterized by high signal intensity on the Tl-weighted images. Tumor is usually of intermediate signal intensity and obliterates the marrow spaces with replacement of the high-intensity fat. If invasion of the cortex is present, the signal void of the cortex is interrupted or irregular. If the bone marrow has not been replaced with fat, however, as in a young child, differentiation is more difficult.

Tumor can usually be separated from muscle and fat using a combination of short TR (relaxation time) and short TE (excitation time)(Tl-weighted images), long TR and short TE (proton-density images), and long TR and long TE (T2-weighled images). The tumor usually has the same signal intensity as muscle on short TR sequences, but the long TR sequences differentiate the usually higher-intensity tumor from the medium-intensity muscle. If tumor invades fatty planes, the normal high-signal-intensity fat on the short TR sequences is obliterated by the more intermediate signal intensity of the tumor. This is relevant in the evaluation of the pterygoid fossa, parapharyngeal space adjacent to the base of the skull, and exit foramina of the cranial nerves (foramina rotundum, ovale, and spinosum, and the stylomastoid foramen), which all contain fatty tissue.

Perineural tumor spread obliterates the fat at the extracranial opening of the foramina (5,6). With the introduction of gadolinium, lesion detection and conspicuity are increased (7). Fat suppression techniques with contrast enhancement have been used to define tumor extent optimally in the region below the skull base (8,9). This perineural spread may originate from tumors arising in the nasopharynx, paranasal sinuses, face, orbit, palate, oral cavity, and other areas that receive branches from the trigeminal nerve. Carcinomas of the oral cavity with mandibular invasion spread along V3 to the foramen ovale, and carcinomas from the parotid extend to the stylomastoid foramen (6).

Invasion of the cavernous sinus is best evaluated with MRI (10). The cavernous sinus is composed of a tangle of small veins and venous sinusoids adjacent to the sella. The cavernous sinus is traversed by cranial nerves III, IV, and VI, and the V1 segment of the fifth nerve. Meckel's cave, which contains cerebrospinal fluid (CSF) and the gasserian ganglion of the fifth nerve, is posterior to the cavernous sinus and located at the lateral aspect of the petrous pyramid. Tumor can reach the cavernous sinus by direct extension or by spread along the nerves (nerve V most commonly) that traverse the sinus and Meckel's cave (11). If tumor reaches Meckel's cave, the high signal of the CSF on T2-weighted images is usually replaced.

Before gadolinium introduction, tumor may be difficult to delineate within the cavernous sinus because of signal characteristics similar to those of surrounding tissues. The tumor, after introduction of gadolinium and contrast enhancement, is characterized by a filling defect in the enhanced cavernous sinus. Tumor involvement may cause increased bowing of the lateral wall of the sinus, which is best seen on axial and coronal images. Tumor contiguous to Meckel's cave may compress the normal oval or triangular high-signal CSF space or completely obliterate Meckel's cave (10).

Carotid artery evaluation at the base of skull is an important consideration before surgical intervention. The carotid artery is well seen on conventional spin-echo sequences as a signal void passing through the skull base. With MRI, areas of contact between tumor and the carotid artery can be defined. Involvement of the carotid artery is indicated by narrowing of the lumen. Luminal narrowing may also indicate invasion of the arterial wall itself. For evaluation of bony details of the carotid canal and the adjacent petrous bone, however, CT is mandatory.

When tumor is located in the paranasal sinuses, the signal void of air is replaced by the most common intermediate signal intensity of the tumor (12). Inflammatory tissue and fluid can usually be optimally separated from the tumor margin with the T2-weighted image (13,14). Mucosal edema and fluid have a high signal intensity on the long TR sequences (T2-weighted image). Tumors may be relatively bright, but seldom is the intensity as pronounced as that of the secretions and edema in an obstructed sinus cavity.

Simple sinus obstruction with edema and retained fluid displays a low or intermediate signal intensity on Tl- and a high signal on the T2-weighted images. If the protein content of secretions in the sinus cavity increases, the signal may be bright on both short and long TR images. However, if a further increase in protein occurs, with loss of water, a decrease in signal intensity occurs on the T1 - and T2-weighted images (15,16). If this is pronounced, the viscous sinus secretions may mimic air in the sinus cavity. Hemorrhage as a concomitant finding in tumors has signal intensities characteristic for blood degradation products, usually reflected by high signal intensity on Tl- and T2-weighted images from methemoglobin.

COMPUTED TOMOGRAPHY AND MAGNETIC RESONANCE IMAGING FINDINGS OF LESIONS OF THE SKULL BASE

The skull base can be divided into three anatomic areas: (a) the anterior skull base, which includes the floor of the anterior cranial fossa, including the orbital roofs, the cribriform region, and the roof of the ethmoid sinuses; (b) the central region, which includes the clivus, sella, planum sphenoidale, cavernous sinus, and, more laterally, the greater and lesser wings of the sphenoid bone; and (c) the posterior and posterolateral region, which is made up of the temporal bone, jugular fossa, and foramen magnum (17).

Location

Anterior Skull Base Lesions

A variety of different lesions are encountered in the anterior skull base (18) (Table 1). The various types of meningo-cele or meningoencephaloceles may occur in the frontal sinus, cribriform plate area, ethmoid sinuses, and sphenoid sinus (19) (Fig. 1), or extend laterally through the lamina pa-

TABLE 1. *Anterior skull base lesions*

- Veningoencephaloceles
- '.'..coceles
- Benign tumors and tumor-like conditions
  - Polyps
  - Inverted papilloma
  - Langherhans' cell histiocytosis
  - Giant cell granuloma Malignant tumors from paranasal sinuses and nasal cavity
  - Carcinomas
  - Esthesioneuroblastoma
  - Lymphoma
  - Plasmacytoma
  - Melanoma
  - Malignant fibrous histiocytoma
  - Sarcomas

pyracea into the orbit (20-22). More anteriorly, lesions extend into the upper nasal cavity or ethmoid sinuses. MRI is the method of choice in the analysis of these lesions (23,24). These lesions reveal characteristic signal intensities that are displayed as CSF or brain; moreover, they can be traced from the paranasal sinuses and nasal cavity into the cranial cavity by way of bony defects. Evaluation of the presence and size of a bony defect is best accomplished with CT. Benign lesions, including mucoceles, of the sinonasal cavities can affect the skull base. Mucoceles of the frontal, ethmoid, and sphenoid sinuses may expand and extend intracranially (25). Rarely, nasal polyps have been reported to protrude



FIG. 2. Esthesioneuroblastoma of the upper nasal cavity and left ethmoid sinus with invasion of the left orbit and intracra-nial cavity. Coronal contrast-enhanced computed tomography scan through the mid-cribriform plate area demonstrates an enhancing mass in the upper nasal cavity and left ethmoid sinus with invasion of the left orbit and the intracranial cavity. The intracranial mass reveals moderate enhancement and cystic degeneration of tumor interiorly and laterally on the left.



FIG. 1. Meningocele of the sella and sphenoid sinus with extension into the pharynx and posterior nasal cavity. A: Sagittal T1-weighted magnetic resonance image (MRI) demonstrates a sharply defined, low-intensity structure extending from the anterior-inferior third ventricle through the sella into the anterior nasopharynx and posterior left nasal cavity. The low signal intensity is consistent with cerebrospinal fluid. B: Coronal T1 -weighted MRI shows the stalk of the meningocele connected to the floor of the third ventricle *(arrowheads).*

through the floor of the anterior cranial fossa (12,13). Osteomas and fibroosseous lesions may protrude into the anterior cranial fossa (most commonly from the frontal, ethmoid, and sphenoid sinuses) (26).

Malignant tumors arising in the sinuses, including nasal cavities and orbits, may extend into the anterior cranial cavity, such as carcinomas (80% of malignant sinus tumors), olfactory neuroblastomas (27,28) (Fig. 2), and various other, less common tumors, such as adenocarcinoma, plasmacy-toma, melanoma, and rhabdomyosarcoma (12). MRI fails to differentiate between the various histopathologic subtypes. Most tumors are low in signal intensity on Tl-weighted images, have moderate to increased signal intensity on the T2-weighted images, and enhance moderately to markedly on the Tl-weighted images after gadolinium introduction (Fig. 3).

In some melanomas, the diagnosis may be suggested by bright signal on the Tl-weighted image and low signal on the T2-weighted image. Tumor-like conditions, including Langerhans' cell histiocytosis and giant cell granuloma, may invade the skull base (29). They reveal low signal intensity on Tl-weighted images and high signal intensity on T2-weighted images, and enhance intensely with contrast administration.

Extensions of mucoceles and benign and malignant lesions from the paranasal sinuses and nasal cavities into the anterior cranial fossa are best evaluated with MRI using coronal and sagittal images in conjunction with axial images and gadolinium administration (18) (Figs. 4, 5). Demonstration of the proximity of the tumor to the optic nerve or the optic canal is of considerable importance in the preoperative assessment.





FIG. 3. Carcinoma of the antrum with perineural extension. A: Coronal T1-weighted magnetic resonance image (MRI) after contrast infusion shows a markedly enhancing tumor mass in the left maxillary antrum. B: Coronal post-contrast T1-weighted MRI demonstrates enhancing tumor in the left foremen rotundum *(arrow).* C: Postgadolin-ium axial T1-weighted MRI shows tumor in the maxillary nerve at the foramen rotundum *(arrow).* Also note enhancing tumor in the left maxillary antrum with extension into the area of the left pterygopalatine fossa.



FIG. 4. Frontal sinus mucocele with intracranial extension. A: Coronal computed tomography scan through the anterior intracranial cavity reveals an isodense, slightly heterogeneous mass lesion in the upper nasal cavities and both ethmoid sinuses, with bulging into both orbits and the anterior intracranial cavity. There is the suggestion of slight linear calcification at the superior aspect of the mucocele. B: Postcontrast coronal T1-weighted magnetic resonance image (MRI) through the anterior cranial fossa shows the mucocele to be nonenhancing and of low signal intensity. C: Postcontrast axial T1-weighted MRI through the frontal sinus demonstrates a nonenhancing, fluid-filled mucocele. Lateral and medial to the mucocele is enhancing polypoid tissue penetrating through the posterior frontal sinus wall into the extradural space. D: Postcontrast lateral T1-weighted MRI through the mid-frontal sinus shows expansion of the sinus cavity secondary to a fluid-filled, nonenhancing mucocele. There is inferior bulging from the frontal sinus into the adjacent nasal cavity *(arrow).* Note enhancement of the wall of the mucocele.



FIG. 5. Polypoid tissue of the paranasal sinuses extending through the roof of the left ethmoid sinus into the anterior cranial cavity. A: Postcontrast coronal computed tomography (CT) scan through the mid-nasal fossa demonstrates polypoid tissue in the upper nasal cavities and ethmoid sinuses with extension through the roof of the ethmoid sinus into the left anterior intracranial cavity. Note surgical defects in both nasal cavities from previous polypectomies. B: Axial CT scan through the frontal sinus shows extension of polypoid tissue from the sinus cavity through a defect on the left into the anterior cranial cavity.

Central Skull Base Lesions

A large group of diverse lesions is encountered in the central skull base (Table 2). Meningiomas are one of the more common neoplasms occurring in the central skull base, chiefly located in the lesser and greater wings of the sphenoid bone (30). A meningioma can arise in the dura covering the intracranial surface of the skull base or from dural sleeves, following some of the cranial nerves. The signal characteristics of meningiomas vary, but these lesions are often isointense with brain on both T1- and T2-weighted images (31). After contrast administration, meningiomas enhance, often intensely and homogeneously. The enhancement may extend along the dura beyond the edge of the main tumor mass (dural tail sign). Hyperostosis, if extensive, can be evaluated by MRI, but CT is more accurate in the assessment of minor degrees of hyperostosis. Calcifications may be present in meningiomas (20% of cases) and are detected, if of sufficient size, by absence of signal. Small calcifications, however, are often undetectable by MRI and are visualized by CT.

TABLE 2. *Central skull base lesions*

Epidermoid cyst
Cholesterol cyst
Neurogenic tumors
  Schwannoma
  Neurofibroma
Meningioma
Chordoma
Chondrosarcoma
Carcinoma of nasopharynx invading skull base
Metastases Multiple myeloma, including plasmacytoma

Lesions in the sella often are represented by pituitary adenomas, which most commonly extend into the suprasellar cistern and laterally into the cavernous sinus, but may extend into the sphenoid sinus and infrequently extend through the skull base into the nasopharynx (32,33).

Neuromas arising from cranial nerve V present as parasellar tumors and may straddle the incisura with components in the middle and posterior fossae (34-36) (Fig. 6). They are characterized by low signal intensity on T1-weighted images (see Fig. 6B), high signal intensity on T2-weighted images (see Fig. 6A), and marked enhancement after gadolinium administration (see Fig. 6C). They may display cystic degenerative areas, that fail to enhance, imparting a heterogeneous appearance to the tumor matrix. Craniopharyngiomas are usually suprasellar in location but may erode and extend into the sella, clivus, and rarely, into the nasopharynx (33). They are heterogeneous in appearance, caused by a variable combination of cystic and solid areas, with the inclusion of calcification in 80% of cases.



FIG. 6. Trigeminal neuroma of the right gasserian ganglion with extension into the right middle cranial fossa. A: Axial T2-weighted magnetic resonance image (MRI) through the middle cranial fossa shows a well defined, high-signal-intensity tumor in the right cavernous sinus and middle cranial fossa with extension through the right incisura into the prepontine cistern. B: Coronal T1-weighted MRI demonstrates the sharply defined, homogeneous low-signal-intensity tumor in the region of right Meckel's cave. C: Post-contrast coronal T1-weighted MRI demonstrates marked enhancement of the neuroma.

The aggressive angiolipoma, originating in soft tissue, rarely invades the skull base. The density or signal characteristics are reflected by fatty tissue with fibrous strands and increased vascularity (37^40) (Fig. 7).

The most common primary tumors originating in the middle cranial fossa are chondrosarcomas and chordomas (41-44). Chordomas arise from remnants of the notochord, usually in the clivus. If large, they may extend over a significant distance intracranially or into the paranasal sinuses, nasopharynx, and foramen magnum (Fig. 8). Chordomas have low signal intensity on T1-weighted images (see Fig. 8 A) and high signal intensity on T2-weighted images, and display marked contrast enhancement after injection of gadolinium (44,45) (see Fig. 8B,C). Most chordomas are heterogeneous in signal intensity, with occasional components of high signal intensity on T1-weighted images that are secondary to blood degradation products (see Fig. 8A, arrow). Low signal intensity within the lesion on T1- and T2-weighted images may represent sequestrations of cortical bone or areas of calcification. Calcification of chordomas is



FIG. 7. Angiolipoma. A: Axial computed tomography study shows a low-density mass in a defect of the left middle cranial fossa floor with extension into the middle cranial fossa and pterygopalatine fossa. The low-density areas are consistent with fat. They are traversed by linear higher-density areas within the fatty tissue. B: Sagittal T2-weighted magnetic resonance image demonstrates multiple tubular flow voids in the tumor. C: Sagittal conventional angiogram shows marked hypervascularity of the tumor.

uncommon. Chordomas are located in the clivus, but in one third of cases grow laterally and then simulate the location of chondrosarcomas.

Chondrosarcomas usually originate more laterally in the petroclival fissure. These tumors may contain calcification, which may not be obvious on MR but can easily be discerned on CT. On CT, they demonstrate cystic bone destruction (Fig. 9A). Calcifications are often increased after proton beam therapy (41). Chondrosarcomas have low signal on T1-weighted images (see Fig. 9B) and a bright signal on T2-weighted images (46). They usually reveal marked heterogeneous enhancement after gadolinium introduction (see Fig. 9C,D; Fig. 10). The signal intensities and enhancement patterns of chondrosarcomas are similar to those of chordomas (43).

Lesions of the nasopharynx not infrequently erode into the central skull base, frequently through the foramen lacerum with subsequent extension into the cavernous sinus (47,48). The foramen lacerum represents the line of least resistance. Intracranial extension may also occur by perineural spread







FIG. 8. Chordoma in the clivus with destruction of the sella turcica. A: Sagittal T1-weighted magnetic resonance image (MRI) demonstrates a destructive, heterogeneous mass lesion in the middle and upper clivus with high-intensity blood *(arrow).* There is associated destruction of the sella turcica. Note tumor extension into the prepontine cistern with flattening of the anterior border of the pons, suprasellar cistern, and posterior half of the sphenoid sinus. B: Contrast-enhanced coronal T1-weighted MRI demonstrates marked enhancement of the chordoma in the areas described. Note superior displacement of the chiasm, which is oriented obliquely *(arrow).* Also note engulfment and displacement of the left cavernous carotid artery *(arrow)* and some encirclement and lateral and superior displacement of the right cavernous carotid arteries. C: Postcontrast axial T1 -weighted MRI shows the lateral extension of the enhancing chordoma. Note erosion of both petrous apices.

(see Fig. 3). The most common tumor implicated in perineu-ral extension is the adenoid cystic carcinoma. Perineural spread can also occur in squamous cell carcinoma and lymphomas (7). Tumors around the nerves are usually low or intermediate in signal intensity on Tl-weighted images and may be bright on T2-weighted images. Obliteration of fat around the nerves occurs at the exit foramina on Tl-weighted images. Frequently, enhancement of the tumor can be seen within and at the foramina after gadolinium infusion with fat suppression (47) (see Fig. 3). Tumor extension along the nerves (most commonly VI, V2, or V3) is reflected by a thickened, enhancing, cordlike structure (see Fig. 3).

Metastases and *multiple myelomas,* including plasmacytoma, not infrequently are located in the central skull base (49). In most cases, the primary tumor is evident clinically, but occasionally the tumor may manifest first in the skull base. No specific features are recognized on CT and MRI in most cases, except for metastases from carcinoma of the prostate, which is characterized by diffuse or localized sclerosis. CT with bone algorithm is mandatory to demonstrate minor bone changes, either lytic destruction or sclerosis.

Epidermoid and *cholesterol cysts* occur in the skull base, usually at the petrous apex and adjacent clivus. They are characterized by a sharply marginated, spherical or ovoid bony defect involving the clivus, middle cranial fossa, and


SYS #MCT4
MASSACHUSETTS GEN
A125
+C
0cm
Stu: 02731
Ser: 004/0
Ima: 006+C/012
Signa 1.5T
I 30.0 mm
A90
R90
L90
B
Stu: 02731
Ser: 005/05
Ima: 004+C/0
Signa
S90
A 6
R90
I90
Stu: 02731
Ser: 002/0
Ima: 007/
34.0 mm
A90
R90
L90
P90
D

FIG. 9. Chondrosarcoma of the left petrous apex. A: Axial computed tomography scan through the temporal bones demonstrates an isodense tumor mass in the destroyed left petrous apex. B: Contrast-enhanced axial T1 -weighted magnetic resonance image (MRI) shows marked enhancement of the tumor. The scattered, low-signal-intensity areas are consistent with areas of calcification. C: Coronal T1-weighted MRI shows the enhancing tumor mass in the petrous apex with inferior extension into the uppermost portion of the parapharyngeal space. D: Axial T1-weighted MRI through the temporal bones demonstrates the homogeneous, fairly well defined tumor in the left petrous apex. Note increased signal intensity in the left mastoid from retained secretions secondary to eustachian tube obstruction.



FIG. 10. Chondrosarcoma of the right cavernous sinus and adjacent middle cranial fossa. A: Axial T1-weighted magnetic resonance image (MRI) after gadolinium introduction shows marked enhancement of the tumor in the right cavernous sinus with extension into the adjacent middle cranial fossa. Note linear, low-signal-intensity areas within the tumor, indicating calcification. B: Postcontrast coronal T1-weighted MRI demonstrates the enhancing tumor mass in the right cavernous sinus and the right middle cranial fossa.

petrous apex. They may also encroach on the sphenoid sinus, as indicated by a defect in the bony wall and an intraluminal soft tissue density. On preinfusion CT scans, epidermoids and cholesterol cysts manifest as lesions isodense with brain. On CT, as well as MRI, they may reveal a slight ringlike area of enhancement that corresponds to the pseudocapsule of the cysts. On MRI, the epidermoid has a low signal intensity on T1- and high signal intensity on T2-weighted images (50), whereas the cholesterol cyst demonstrates high signal intensity on T1- and T2-weighted images (51,52) (Fig. 11).



FIG. 11. Cholesterol cyst. A: Postcontrast axial T1-weighted magnetic resonance image (MRI) reveals a high-intensity, nonenhancing cyst in the right petrous space. B: The cyst is of high signal intensity on axial T2-weighted MRI.

Osteomyelitis

Osteomyelitis of the skull base is most commonly caused by malignant external otitis (53-56). This infectious process originates in the external auditory canal and, if unchecked because of a delay in diagnosis or inadequate treatment, extends to the nasopharynx, paranasopharyngeal space, and adjacent skull base. The disease is encountered in patients with diabetes and immunocompromised patients infected with *Pseudomonas aeruginosa,* the causative organism in most cases. On CT, there is evidence of lytic bone destruction often associated with a soft tissue mass in the lateral nasopharynx. On MRI, the inflammatory tissue displays low signal intensity on Tl-weighted images, high signal intensity on T2-weighted images, and a variable degree of enhancement after gadolinium introduction. Other causes of osteomyelitis of the skull base include fungus disease (aspergillosis, mucormycosis), and there are cases with unknown etiologies. Other than a soft tissue mass with bone destruction, these lesions have no specific imaging features.

Posterior Skull Base Lesions

Tumors of the posterior skull base can be categorized according to site of origin as (a) cerebellopontine (CP) angle lesions, (b) jugular fossa tumors, and (c) foramen magnum lesions (Table 3).

The *CP angle lesions* comprise, in order of frequency, acoustic neuroma (70-80%), meningioma (10%), and miscellaneous pathologic processes, including epidermoid cysts, arachnoid cysts, metastases, and ependymoma of the fourth ventricle with lateral extension. MRI with gadopentetate is the optimal modality to define the origin and characterize this diverse group of lesions (57). In 95% of cases, acoustic neuroma arises in the internal auditory canal and either remains within the canal or, more commonly, extends from the canal into the CP angle cistern (Fig. 12). After the

TABLE 3. *Posterior skull base lesions*

Cerebellopontine angle lesions
Acoustic neurinoma
Meningioma
Tumors of temporal bone:
  Malignant lesions
  Carcinoma
  Endolymphatic sac tumor
  Facial nerve neurinoma
Epidermoid cyst Arachnoid cyst
Vascular lesions Metastatic
disease
Ependymoma originating in fourth ventricle or cerebellum **Jugular fossa tumors** Glomus jugulare tumor Neurogenic tumors
Chondrosarcoma Meningioma
Foramen magnum lesions
Intradural extramedullary
  Meningioma
  Neurogenic tumors
Extradural
  Bone lesions
    Metastases
    Chordoma
  Inflammatory and miscellaneous lesions
    Rheumatoid arthritis Synovial cyst



FIG. 12. Acoustic neuroma in left cerebellopontine angle. Postcontrast axial T1-weighted magnetic resonance image through the temporal bone demonstrates a left acoustic neuroma encroaching on the cerebellum and pons. Note marked enhancement and intracanalicular and extracanalicular extension.

продолжение

administration of gadolinium there is marked enhancement, associated in a smaller percentage of cases with cystic degeneration or adjacent arachnoid cysts (see Fig. 12). Large lesions may indent the adjacent brainstem or cerebellum with contralateral displacement.

Facial nerve neuromas most commonly originate from the facial nerve at the geniculate ganglion (Fig. 13), but may arise at other locations in the temporal bone. Large tumors may extend into the middle or posterior intracranial cavity (58). Their imaging findings parallel those of acoustic neuromas (see Fig. 13).

The *meningioma* usually has a broad-based attachment to the medial posterior surface of the petrous bone anterior or posterior to the internal auditory canal. Meningiomas enhance diffusely and intensely after the introduction of gadolinium (Fig. 14). In a small percentage of cases, there may be slight extension of the meningioma into the internal auditory canal (57).

Epidermoid cysts in the CP angle have a low signal intensity on T1-weighted images, increased signal intensity on T2-weighted images, and a slightly greater signal intensity compared with CSF on proton-density images (50). Epidermoid cysts frequently have frondlike projections from the margin and insinuate into the adjacent structures, especially in the prepontine cistern.

Arachnoid cysts have the same signal intensities as CSF and are differentiated from a dilated subarachnoid space by the presence of a thin wall and a variable degree of mass effect on adjacent structures (59).

Metastatic lesions comprise a diverse group of primary tumors (most commonly bronchogenic carcinoma in men and carcinoma of the breast in women). They may be localized to



FIG. 13. Neuroma of the geniculate ganglion. A: Axial computed tomography scan (bone window setting) through the temporal bone shows a saucer-shaped, sharply defined defect in the geniculate ganglion area of the left temporal bone. B: Postcontrast axial T1-weighted magnetic resonance image (MRI) through the temporal bone shows a sharply defined, homogeneous, enhancing tumor mass in the geniculate ganglion consistent with a neuroma. C: Postcontrast coronal T1-weighted MRI through the temporal bone demonstrates an enhancing mass in the region of the left geniculate ganglion.



FIG. 14. Meningioma of the left cerebellopontine (CP) angle. Postcontrast axial T1-weighted magnetic resonance image demonstrates a markedly enhancing, broad-based menin-gioma in the left CP angle cistern. Note enhancement of the adjacent dura and minimal extension into the internal auditory canal.

the CP angle cistern and have also been reported to invade the internal auditory canal.

Ependymomas arising in the fourth ventricle have a tendency to spread laterally through the foramen of Luschka and manifest as a mass in the CP angle cistern. They are usually low in signal intensity on Tl-weighted images and show increased signal intensity on T2-weighted images, with heterogeneous enhancement after introduction of gadolinium. They may reveal areas of necrosis which are nonenhancing and in areas of calcification.

Jugular Fossa Tumors

The most common tumor of the jugular fossa is the *glomus jugulare tumor.* This lesion causes enlargement of the jugular foramen with irregular bone destruction, which is best delineated by CT with bone window settings (60) (Fig. 15A). The lesion frequently extends inferiorly into the upper neck but may also extend into the posterior fossa, including the CP angle cistern, if of sufficient size. The tumor most frequently extends into the middle ear cavity and can be detected as a pinkish, pulsating mass in the middle ear on otoscopic examination. The tumor may reveal multiple, tubular, undulating signal voids reflecting the increased vascularity of this lesion (61) (see Fig. 15B). The lesions are hy-pointense on Tl-weighted images and hyperintense on T2-weighted images (62) (see Fig. 15B). There is usually marked enhancement after introduction of gadolinium. Coronal images are especially useful for demonstrating the



FIG. 15. Glomus tumor of the right jugular fossa. A: Axial computed tomography scan (bone window setting) through the temporal bone reveals enlargement and erosion of the right jugular fossa. Note small area of soft tissue density, indicating tumor extension into the hypotympanum *(arrow). B:* Postcontrast axial T1 -weighted magnetic resonance image shows marked enhancement of the tumor in the right jugular fossa. Note anterior displacement of the internal carotid artery *(arrow).* Hypovascularity is reflected by low-signal-intensity tubular structures within the mass.

superiorinferior extent of the lesion, especially the CP angle component.

The second most common tumors of the jugular fossa are the *neurofibroma* and *neurilemoma*. These lesions usually are accompanied by sharply defined bony expansion of the jugular fossa (61) (Fig. 16A,B). Large lesions may extend into the CP angle cistern and simulate an acoustic neuroma, especially if they are near the internal auditory canal. Coronal images are indicated in the differential diagnosis (63). Neurilemomas show marked enhancement, occasionally with areas of cystic degeneration (see Fig. 16C,D). The neurofibroma enhances to a variable degree after gadolinium introduction.

There are a variety of less common lesions that arise in the



FIG. 16. Neuroma of the left jugular fossa. A: Axial computed tomography (CT) scan demonstrates a large, lytic, bony defect in the area of the left jugular fossa with extension to the left middle cranial fossa. B: Axial CT scan (soft tissue window) shows an isodense mass in the lytic defect. C: Postcontrast axial T1-weighted magnetic resonance image (MRI) demonstrates heterogeneous enhancement of the left jugular fossa neuroma. Note cystic-degenerative, nonenhancing areas in the tumor. D: Coronal T1-weighted MRI shows an enhancing tumor with central areas of cystic degeneration.

jugular fossa, such as hemangiopericytoma (61), which has enhancement and intensity characteristics similar to those of the glomus jugulare tumor. Meningiomas may arise in the jugular fossa and have the same radiologic characteristics as reported elsewhere (64). Chondrosarcomas rarely arise from the jugular fossa and have imaging features similar to those described previously (65). Metastases also may involve the jugular fossa and are characterized as a soft tissue mass with bone destruction or sclerosis.

Multiple lesions occur in the area of the area of *the foramen magnum.* Most frequently they represent meningiomas or neurogenic tumors that arise from the dura of the foramen magnum or from nerve roots that exit the foramen magnum or the upper cervical spine (11). Tumors that arise in the clivus, such as chordoma and chondrosarcoma, may extend into the foramen magnum, causing displacement of the medulla or upper cervical spinal cord (44). Their radiologic characteristics have been previously described.

Lesions that arise in the upper cervical spine, especially from the Cl and C2 vertebrae, may also extend into the foramen magnum. The most common lesions arising from the bony structures represent metastases and, rarely, primary bone lesions such as chordoma, Ewing's sarcoma, and chondrosarcoma (11).

Tumefactions of inflammatory origin, especially rheumatoid arthritis, may cause changes, including pannus formation with secondary encroachment on the foramen magnum (66). Synovial cysts have been reported to arise from the joint between the atlas and odontoid process with secondary extension into the foramen magnum and upper cervical spinal canal (67). On CT, they are well defined and of low attenuation, whereas on MRI, they are hypointense on Tl-weighted images and hyperintense on T2-weighted images.

Diffuse Lesions of the Skull Base

Various disease entities may affect the skull base diffusely (Table 4). Among these, metastases are the most common lesions.

Metastases in the skull base are common in advanced disease and are frequently asymptomatic. They may be lytic (breast, lung, thyroid, hypernephroma, and multiple myeloma, including plasmacytoma) or sclerotic (prostate) or mixed (breast). CT is the preferred radiologic method to demonstrate these bony lesions because the soft tissue component may be small and the bony abnormality inconspicuous on MRI.

Bone dysplasias constitute different entities, including fibrous dysplasia, Paget's disease, osteopetrosis (68,69), and metaphyseal and diaphyseal dysplasias (70,71). Fibrous dysplasia is usually localized (monostotic variety) and most commonly involves the sphenoid bone. On CT, the bone is expanded and appears sclerotic and cystic, reflected histologically by osteoid and fibrotic bundles, respectively. MRI is characterized by low signal intensity on Tl- and T2-weighted images (72). Because of hypervascularity, there is bleeding into bone, followed by cavity formation. Blood degradation products (methemoglobin) cause increased signal intensity on Tl- and T2-weighted images in the signal void of bone. There is moderate enhancement after introduction of gadolinium (73). In Paget's disease, there is usually associated involvement of the skull table. The imaging features are described as a "cotton wool" appearance produced by radiolucent and radiodense areas associated with bony expansion. Metaphyseal and diaphyseal dysplasia and osteopetrosis involve the skull table and skull base as well as the central and appendicular skeleton. A diffuse, variable sclerosis affects the base of the skull along with the skull table. The findings in the axial and peripheral skeleton allow differentiation of these entities.

TABLE 4. *Diffuse lesions of the skull base*

Fibrous dysplasia
Paget's disease
Metaphyseal and diaphyseal dysplasias
Osteopetrosis
Metastatic disease, including multiple myeloma

SUMMARY AND CONCLUSIONS

Computed tomography and MRI are the principal methods for evaluation of skull base lesions. CT in the axial and coronal planes optimally demonstrates bone detail and defines areas of calcification. Its major disadvantage is its inability to image intracranial structures, including brain, aura, and meninges, and their relationship to various pathologic entities.

Magnetic resonance imaging is the preferred modality to investigate the soft tissue component of skull base lesions. When MRI is used with gadolinium administration and fat suppression, the location and extent of various primary and secondary tumors can be precisely mapped out.

Their signal characteristics and enhancement patterns allow tumors to be differentiated from cysts. The origin and components of a meningocele or meningoencephalocele are clearly depicted on MRI. Moreover, by defining the location (anterior, middle, or posterior cranial fossae), margin, and signal characteristics of mass lesions, a preliminary or definitive diagnosis can be established. MRI and CT findings enable the surgeon to select a drainage (cysts) or biopsy site, or plan a surgical approach for partial or complete resection of the lesion. Vital structures (i.e., nerves, arteries, veins) can be identified and surgically extirpated or preserved, depending on the size, location, and nature of the lesion.

REFERENCES

1. Curtin HD, Hirsch WJ. Base of the skull. In: Atlas SW, ed. *MRI of the brain anil spine.* New York: Raven Press, 1991:669-701.
2. Ginsberg LE. Neoplastic diseases affecting the central skull base: CT and MR imaging. *AJR Am J Roentgenol* 1992:159:581-589.

Janecka IP. Surgical approaches to the skull base. *Neuroimnging Clin \Am* 1994;4:639-656.

6 Janecka IP, Sen C, Sekhar LN, et al. Cranial base surgery: results in 183 patients. *Ototaryngol Head Neck Surg* 1994;] 10:539-546.

7.Curtin HD, Williams R, Johnson J. CT of the perineural tumor exten-•iion-pterygopalatine fossa. *AJR Am J Roentgenol* 1985; 144:163-169.

8• Curtin HD, Wolfe P, Snyderman N. Facial nerve between the stylo-mastoid foramen and parotid: CT imaging. *Radiology* 1983;149: 165-169.

9 Laine FJ, Braun IF, Jensen, et al. Perineural tumor extension through the foramen ovale: evaluation with MR imaging. *Radiology* 1990; 174:65-71.

10 Tien RD. Fat suppression MR imaging in neuroradiology: techniques and clinical application. *AJR Am J Roentgenol* 1992;158:369-379. Tien RD, Hesselink JR, Chu PK, et al. Improved detection and delineation of head and neck lesions with fat suppression spin-echo MR imaging. *AJNR Am J Neuroradiol* 1991; 12:19-24. Hirsch WL, et al. Comparison of MR imaging, CT, and angiography in the evaluation of enlarged cavernous sinus. *AJNR Am J Neuroradiol* 1988;9:907-915.

11. Johnson MH, Smoker WRK. Lesions of the craniovertebral junction. *Neuroimaging Clin N Am* 1994;4:599-618.

12. Som PM, Dillon WP, Sze G, et al. Benign and malignant sinonasal lesions with intracranial extension: differentiation with MR imaging. *Radiology* 1989; 172:763-766.

13. Som PM, Curtin HD. Inflammatory lesions and tumors of the nasal cavities and paranasal sinuses with skull base involvement. *Neuroimaging Clin N Am* 1994;4:499-514.

14. Som PM, Shapiro MD, Biller HF, et al. Sinonasal tumors and inflammatory tissues: differentiation with MR imaging. *Radio/ogv* I988;167:803-808.

15. Dillon WP, Som PM, Fullerton GD. Hypointense MR signal in chronically inspissated sinonasal secretions. *Radiology* 1990;174:73-78.

16. Som PM, Dillon WP, Fullerton GD, et al. Chronically obstructed sinonasal secretions: observations on Tl- and T2-shortening. *Radiol-ogy* 1989; 172:515-520.

17. Lustrin ES, Robertson RL, Tilak S. Normal anatomy of the skull base. *Neuroimaging Clin N Am* 1994;4:465^478.

18. Paling MR, Block WC, Levine PA, et al. Tumor invasion of the anterior skull base: a comparison of MR and CT studies. *J Cornput Assist Tomogr* 1984;8:944-952.

19. Pollack JA, Newton TH, Hoyt WF. Transsphenoidal and transeth-moidal encephaloceles. *Radiology* 1968;90:442-453.

20. Byrd SE, Harwood-Nash DC, Fitz CR, et al. Computed tomography in the evaluation of encephaloceles in infants and children. *J Comput Assist Tomogr* 1978;2:81-87.

21. David DJ, Proudman TW. Cephaloceles: classification, pathology, and management. *World J Surg* 1989; 13:349-357.

22. NagerGT. Cephaloceles. *Laryngoscope* 1987:97:77-84.

23. Koch BL, Ball WS Jr. Congenital malformations causing skull base changes. *Neuroimaging Clin N Am* 1994;4:479-498.

24. Naidich TP, Altman NR. Braffman BH. et al. Cephaloceles and related malformations. *AJNR Am J Neuroradiol* 1992; 13:655-690.

25. Osborn AG, Johnson L, Roberts TS. Sphenoidal mucoceles with intracranial extension. *J Comput Assist Tomogr* 1979:3:335-338.

26. Som PM, Lidov M. The benign fibro-osseous lesion: its association with paranasal sinus mucoceles and its MR characteristics. *J Comput Assist Tomogr* 1992;16:871-876.

27 Li C, Yousem DM, Hayden RE. et al. Olfactory neuroblastoma: MR evaluation. *AJNR Am J Neuroradiol* 1993:14:1167-1171. 28 Som PM, Lidov M, Brandwein M, Catalano P, Biller HF. Sinonasal es-thesioneuroblastoma with intracranial extension: observations on marginal tumor cysts as a diagnostic MRI finding. *AJNR Am J Neuroradiol* 1994 15(7): 1259-1262.

29. Cunningham MJ, Curtin HD, Butkiewics BL. Histiocytosis of the temporal bone: CT findings. *J Comput Assist Tomogr* 1988; 12:70-74.

30. Aoki S, Sasaki Y, Machida T, et al. Contrast-enhanced MR images in patients with meningioma: importance of enhancement of the dura adjacent to the tumor. *AJNR Am J Neuroradiol* 1990;! 1:935-990.

31. Elster AD, Challa VR, Gilbert TH, et al. Memngiomas: MR and hisfopathoJogicaJ *features. Radiology 1989:170:857-862.*

32. Felsberg GH, Tien RD. Sellar and parasellar lesions involving the skull base. *Neuroimaging Clin N Am* 1994;4:543-560.

33. Zimmerman RA. Imaging of intrasellar, suprasellar, and parasellar tumors. *Semin Roentgenol* 1990:25:174.

34. McCormick PC, Bello JA, Post KD. Trigeminal schwannomas. *J Neu-rosurg* 1988:69:850.
35. Pollack IF, Sekhar LN, Jannetta PJ, et al. Neurilemmomas of the trigeminal nerve. *J Neurosurg* 1989;70:737.
36. Yuh WTC, Wright DC, Barloon TJ, et al. MR imaging of primary tumors of trigeminal nerve and Meckel's cave. *AJR Am J Roentgenol* 1988;151:577.
37. Chew FS, Hudson TM, Hawkins IF. Radiology of infiltrating angi-olipoma. *AJR Am J Roentgenol* 1980:135:781-787.
38. Matsuoka Y, Kurose K, Nakagawa O, Katsuyama J. Magnetic resonance imaging of infiltrating angiolipoma of the neck. *Surg Neural* 1988;29:62-66.
39. Takeuchi J, Handa H, Keyaki A, et al. Intracranial angiolipoma. *Surg Neural* 1988:29:62-66.
40. Wilkins PR, Hoddinott C. Hourihan MD, et al. Intracranial *angiolipoma. J Neuro/Neurosurg Psychiatry* 1987:50:1057-1059.
41. Brown E, Hug EB. Weber AL, Munzenrider J. Chondrosarcoma and other chondromatous lesions arising from the base of skull. *Neuroimaging Clin NAm* 1994;4:529-541.
42. Oot RF. The role of MR and CT in evaluating clival chordomas and chondrosarcomas. *AJNR Am J Neuroradiol* 1988;9:715-727.
43. Weber AL, Brown EW, Hug EB, Liebsch NJ. Cartilaginous tumors and chordomas of the cranial base. *Otolaryngol Clin North Am* 1995:28:453-471.
44. Weber AL, Liebsch N, Sanchez R, Sweriduk S. Chordomas of the skull base. *Neuroimaging Clin N Am* 1994;4:515-527.
45. Meyers SP, Hirsch WL Jr, Curtin HD, et al. Chordomas of the skull base: MR features. *AJNR Am J Neuroradiol* 1992:13:1627-1636.
46. Meyers SP, Hirsch WL Jr, Curtin HD, et al. Chondrosarcomas of the skull base: MR imaging features. *Radiology* 1992;184:103-108.
47. Braun IF. MRI of the nasopharynx. *Radial Clin North Am* 1989;27:315.
48. Sham JST, Cheung YK, Choy D, et al. Nasopharyngeal carcinoma: CT evaluation of patterns of tumor spread. *AJNR Am J Neuroradiol* 1991:12:265.
49. Greenberg HS. Deck MGF, Vikram B, et al. Metastasis to the base of skull: clinical findings in 43 patients. *Neurology* 1981;31:530-537.
50. Mafee ME, Kumar A, Heffner DK. Epidermoid cyst (cholesteatoma) and cholesterol granuloma of the temporal bone and epidermoid cysts affecting the brain. *Neuroimaging Clin N Am* 1994;4:561-578.
51. Gherin SG, Brackman DE. Lo W. Cholesterol granuloma of the petrous apex. *Laryngoscope* 1985:85:659-664.
52. Lo WWM. Solti-Bohman LG, Brackmann DE, et al. Cholesterol granuloma of the petrous apex. *Radiology* 1984; 153:705-711.
53. Chandler JR. Malignant external otitis and osteomyelitis of the base of the skull. *Am J Otol* 1989; 10:108-110.
54. Chandler JR, Grobman L. Quencer R, Serafine A. Osteomyelitis of the skull base. *Laryngoscope* 1977:86:417^28.
55. Gherin SG, Brackman DE, Bradley WG. Magnetic resonance imaging and computerized tomography in malignant external otitis. *Laryngoscope* 1986:96:542-548.
56. Gold S. Som PM, Lucente FE, et al. Radiographic findings in progressive necrotizing "malignant" external otitis. *Laryngoscope* 1984:94:363-366.
57. Weber AL. Magnetic resonance imaging and computed tomography of the internal auditory canal and cerebellopontine angle. *Isr J Med Sci* 1992:28:173-182.
58. Horn KL. Crumley RL, Schindley RA. Facial neurilemmomas. *Laryngoscope* 1981:91:1326-1331.
59. Weiner SN, Pearlstein AE, Eiber A. MR imaging of intracranial arachnoid cysts. *J Comput Assist Tomogr* 1987:11:236.
60. Lo WWM, Solti-Bohman LG. High resolution CT in the evaluation of glomus tumors of the temporal bone. *Radiology* 1984; 150:737-742.
61. Weber AL, McKenna MJ. Radiologic evaluation of the jugular foramen: anatomy, vascular variants, anomalies, and tumors. *Neuroimaging Clin NAm* 1994;4:579-598.
62. Olsen WL, Dillon WP, Kelly W. et al. MR imaging of paragangliomas. *AJR Am J Roentgenol* 1987:148:701-704.



FIG. 1.: T1-weighted (T1W) axial magnetic resonance image (MRI). B: T2-weighted (T2W) axial MRI. C: T1W axial MRI after gadolinium enhancement. The meningioma is isointense with gray matter on the T1W and slightly hyperintense on T2W images, with marked enhancement after gadolinium. The lesion arises from the clivus and extends into the prepontine and cerebellopontine angle cistern and Meckel's cave *(arrows).* Note encasement of internal carotid artery in the cavernous sinus *(open arrow).* In **(B),** there is edema of the adjacent pons *(curved arrows)* on the T2W image. There is posterior displacement of the fourth ventricle *(arrowhead).* In **(C)** (slightly inferior to **[A]** and **[B]),** the enhancing meningioma abuts the internal carotid artery *(open arrow).*

conventional angiography in demonstrating small vessel detail 13). Much the same information about the major vessels **and** their relationship with the lesion can be gleaned from standard, cross-sectional magnetic resonance imaging •MRI) with proton-density and T2-weighted images (Fig. 1). Large vessels appear as absent signal (flow voids). Magnetic resonance venography is an excellent modality to exclude sigmoid sinus thrombosis (13).

If the carotid artery appears invaded by tumor, cerebral angiography and temporary balloon test occlusion (BTO) are performed.

Evolution of Preoperative Carotid Occlusion

In 1911, Matas described manual compression of the internal carotid artery as a method to assess risk for carotid occlusion (14). This test was unreliable because of the difficulty of obtaining complete internal carotid artery occlusion **to** exclude the external carotid artery and to avoid confounding vasovagal responses (3). Contralateral carotid arteriogra-phy with ipsilateral carotid compression provides anatomic assessment of anterior communicating artery patency, but it fails to provide information about functional reserve (15).

The measurement of *stump pressure* in the occluded carotid artery to determine carotid flow reserve is quite unreliable. Temporary shunt placement has been advocated for stump pressures below 20 to 70 mm Hg. Stump pressures vary widely in patients with normal and decreased regional CBF. Measurement of stump pressure is inaccurate in predicting delayed neurologic compromise (4,15,16). Continuous electroencephalographic monitoring during surgery is a measure of adequate CBF (17). The sensitivity is poor because major impairment of brain perfusion may be necessary to cause an electroencephalographic abnormality (18).

Intraoperative occlusion of the internal carotid artery under direct vision was replaced by BTO with local anesthesia.

Balloon Test Occlusion

Temporary trial occlusion of the internal carotid artery has been used to identify those patients with no flow reserve who are at very high risk for neurologic sequelae if the carotid is permanently occluded. A bilateral carotid and a vertebral arteriogram are performed, using the femoral artery approach, to assess the relation of the vessels to the lesion and to evaluate the collateral circulation through the circle of Willis. Contraindications to performing BTO include severe stenosis or occlusion of the contralateral carotid artery (15), or a vascular anomaly such as an isolated middle cerebral artery or an embryonic carotid basilar anastomosis (Fig. 2). This group of patients require bypass surgery if the carotid must be sacrificed, and no further diagnostic evaluation is needed.

If there are no anatomic contraindications, then BTO is performed. The patient is anticoagulated with 5,000 to 7,000 units of intravenous heparin (6). A 5-Fr double-lumen Swan-Ganz catheter is passed through a 6-Fr introducer sheath, and the balloon catheter is flow-directed into the internal carotid to the level of Cl or C2. A 0.018-in. exchange guide wire may also be used to place the Swan-Ganz catheter in very tortuous vessels. The Swan-Ganz catheter is most commonly useUJjecause of its ease of introduction, its double-lumen configuration, which allows alternating pressure measurements and infusion^oTheparinized saline into the occluded internal carotid artery, and its relatively low cost (6). As an alternative, a single-lumen, nondetachable silicone balloon catheter manufactured by Interventional Therapeutics Corporation (ITC-NDSB [1509]) can be used. This is a very supple, 2-Fr polyethylene catheter that can be used in very tortuous vessels. Limitations of this system include the use of a larger guiding catheter (7.3-Fr minimum size) and a single-lumen configuration, which precludes infusion of hep-arinized saline and pressure measurements in the occluded internal carotid artery (6). Micro Interventional Systems has introduced a 5.4-Fr, double-lumen silicone balloon-tipped catheter with a large inner diameter (0.042 in.) that accepts standard 0.038-in. guide wires.



FIG. 2. Persistent trigeminal artery *(arrow), a* fetal carotid-basilar anastomosis, connects the cavernous internal carotid artery with the basilar artery *(curved arrow).*

If there is significant atherosclerotic disease at the common carotid artery bifurcation, then trial occlusion of the common carotid artery is elected. A baseline neurologic evaluation is performed, testing both hemispheres for motor function (cranial nerves, pronator drift, grip, foot flexion and extension, finger to nose), sensation, and higher cortical function (name, place, counting). The pressure in the carotid is monitored through the double-lumen catheter, distal to the balloon, before, during, and after balloon occlusion. The balloon is inflated with 0.1 to 0.2 ml of dilute contrast material (7) Adequate occlusion can be determined by maximal dampening of the preocclusion arterial waveform (Fig. 3). Contour change of the balloon from a round to an oval shape, as the balloon coapts the wall of the artery, is another method of judging vessel occlusion. Care must be taken not to overinflate the balloon and damage the intima. Monitoring arterial pressure waveforms is probably a safer method of determining optimal balloon inflation (6). Contrast can also be injected through the end hole to confirm a static column of contrast in the occluded carotid artery, but this is not necessary.

Heparinized saline must be infused slowly to allow retrograde flow of blood to perfuse the ophthalmic artery. Rapid saline infusion can produce the ocular ischemic syndrome (19). The patient may then experience ipsilateral orbital pain and progressive uniocular visual loss.

Close clinical monitoringxjpntinues for the 15 to 20 minutes of test occlusion. If there is any change in neurologic status, the balloon is immediately deflated and the catheter withdrawn. No further testing is done. These patients presumably have CBF less than 20 ml/100 g/minute (3-5).

Immediate neurologic deficits during BTO occur in 5% to 10% of patients. These deficits usually occur within 1 to 3 minutes of balloon inflation, often within seconds. Neurologic deficits rapidly resolve on balloon deflation (3,17)N

Tests of Cerebral Blood Flow Reserve

It is evident that BTO with clinical monitoring alone will miss a significant number of patients with inadequate flow reserves (20,21). Patients who tolerate clinical BTO need additional testing of the adequacy of collateral flow to avoid delayed neurologic complications. Ten to 20% of patients who safely tolerate 20 minutes of BTO of the carotid suffer delayed neurologic sequelae if the carotid artery is permanently occluded (3,4,20,22-24). These patients are particularly at risk if episodes of hypotension, anemia, hypoxemia, or hypoglycemia occur after surgery.

Better evaluation of collateral flow may be obtained by measuring CBF (23). Angiography with only clinical BTO and no other tests of CBF reserve resulted in a postoperative neurologic complication rate of 43% after carotid artery sacrifice (20). In one study, the postoperative neurologic complication rate fell to 0% after the addition of technetium-99m (^{99m}Tc) hexamethylpropyleneamine oxime (HMPAO) single photon emission computed tomography (SPECT) to the BTO study (21). Therefore, temporary test occlusion of the carotid artery and clinical neurologic evaluation must always be accompanied by CBF measurements.

Ideally, the measurement of CBF should be easy to perform, simple to interpret, and provide quantitative data correlating with physiologic thresholds for function and survival (5). Unfortunately, the ideal test does not exist.

Based on the Pick principle, nitrous oxide, an inert, lipid-soluble gas, was originally used to measure flow. The Pick principle states that the quantity of gas taken up in a tissue per unit time is equal to the quantity entering the tissue in the arterial blood minus the quantity leaving in the venous blood. Kety and Schmidt calculated the average CBF by knowing the time course of the change in the inert gas concentration in the arterial blood entering the brain and in the venous blood leaving it, as well as the partition coefficient. This assumes that blood flow is in a steady state during the study and is not affected by the tracer. Substituting radioactive '^{33}Xe allowed the use of external scintillation counting to measure the tracer in the brain. Xenon computed tomography^CT) uses nonradioactive Xe gas as a contrast agent during senaHZrT scanning (25).

Stable Xe is radiodense with an atomic number of 54 and a k-edge similar to iodine. Xe is a chemically inert noble gas that is highly lipid soluble and, after inhalation, moves rapidly from the blood pool to cross the blood-brain barrier and enter the brain. The concentration of Xe is an indicator of tissue perfusion (26). Although 80% Xe is an anesthetic similar to nitrous oxide, most people tolerate 33% Xe concentration with few sensory disturbances other than a mild euphoria (27). Thirty-three percent Xe has a CT density of about 10 Hounsfield units (5).

A routine CBF study can be accomplished in 30 to 40 min-



FIG. 3. Internal carotid artery pressure, measured distal to the occlusion balloon, through the end-hole of the balloon occlusion catheter. A: Preocclusion pressure of 151/39, mean 109 mm Hg. B: Occlusion pressure with balloon inflated of 89/52, mean 63 mm Hg. Note maximal dampening of arterial waveform.



FIG. 4. Normal Xe computed tomography regional cerebral blood flow study. Scan at level of lateral ventricles and foramen of Monro. **A:** Baseline study with regions of interest placed over cortex. **B:** After Xe inhalation, a color regional blood flow map is obtained. The brighter colors (yellow and red) correspond to higher blood flow in the cortex and basal ganglia.

utes and can be repeated in 20 minutes. The concentration of arterial Xe is indirectly measured by the end-tidal concentration using a thermal conductivity analyzer. CT images are obtained during 4 to 5 minutes of Xe inhalation, which is sufficiently rapid not to allow any pharmacologic effects of Xe to alter flow dynamics. Baseline images are subtracted from contrast-enhanced xenon images (3,5) (Fig. 4). The data obtained are used to solve the modified Kety equation (2,5):

$$\Delta \mathrm{CT}(t) = f\int_0^t \Delta\, Ca(u)\mathrm{e}^{-f/\lambda(t-u)}du$$

where f is flow, λ is the tissue partition coefficient, and $f = k\lambda$. Each computed tomography (CT) voxel is defined as a series of changes in CT enhancement values as a function of time, $\Delta \mathrm{CT}(t)$. $\Delta Ca(u)$ is the arterial concentration of xenon indirectly determined from the thermoconductivity detector recording of xenon end-tidal values.

Two axial levels are chosen for Xe CT CBF analysis. Contiguous 2-cm regions of interest are placed over the cortical mantle at the level of the foramen of Monro and at the top of the ventricular system. A quantitative value for each region of interest is determined, with special attention given to border zone territories between the anterior, middle, and posterior cerebral arteries (3). *Adequate CBF is defined as greater than 30 ml/100 g/minute* (5,7,17) (Fig. 5).

Regional CBF may also be evaluated with SPECT using ^{99m}Tc HMPAO (26). HMPAO is injected intravenously during test occlusion of the carotid artery. ^{99m}Tc HMPAO is a lipophilic tracer that freely crosses the blood–brain barrier. ^{99m}Tc HMPAO has an extraction fraction of 0.75 (28). Once inside the brain tissue, the compound is rapidly converted to a hydrophilic form and is retained for several hours to allow imaging. The uptake of ^{99m}Tc HMPAO is maximum within 10 minutes after intravenous injection (29). HMPAO is regionally distributed in proportion to local CBF (30,31) (Fig. 6).

When areas of regional brain perfusion in opposite hemispheres are compared, a 10% difference is considered to be a positive study (29). HMPAO SPECT provides only an assessment of asymmetry between cerebral hemispheres, and not quantitative CBF data. Some claim that SPECT may be overly sensitive and lacks adequate specificity (32). Occasionally, CBF may rise on the occluded or unoccluded side, producing asymmetries of normal or even elevated CBF. Without quantitative data, these CBF levels may be given unwarranted significance (3,33,34). The advantage of SPECT is that it is easy to perform and uses readily available technology that provides regional perfusion information (30).

Positron emission tomography depicts quantitative regional CBF and metabolism. It requires an on-site cyclotron plus the supporting technology, thereby limiting its availability.

Limitations of Preoperative Balloon Test Occlusion and Testing of Cerebral Blood Flow

Even in patients identified as safe for abrupt carotid occlusion by preoperative testing, delayed ischemic complications develop in 3% to 22% (6,34). This dilemma has caused many surgeons to forgo preoperative quantitative CBF anal-



FIG. 5. A: Preocclusion baseline Xe computed tomography cerebral blood flow study showing normal symmetric cerebral blood flow. **B:** Balloon test occlusion of right internal carotid artery for 15 minutes. Even though the patient remained asymptomatic, with a negative neurologic examination, there is a significant decrease in blood flow in the territory of the right middle cerebral artery, right anterior border zone, and the right anterior cerebral artery. (Reproduced with permission from ref. 3.)



FIG. 6. ^{99m}Tc HMPAO single photon emission computed tomography scan. The axial images are displayed from skull base to vertex. **A:** During balloon test occlusion of the right internal carotid artery, there is decreased perfusion of the right cerebral hemisphere. **B:** A baseline study performed the next day shows normal symmetric perfusion. (Reproduced with permission from ref. 29.)

;• sis. and to determine the need for shunting based on clinical and physiologic criteria of cerebral ischemia (17).

Even if the elusive goal of perfect testing for CBF is attained, other delayed conditions compromising CBF cannot **be** predicted. Critics of preoperative assessment of the carotid with BTO and CBF mapping claim that these tests can never completely define that subset of patients requiring revascularization. Tests of CBF cannot measure all the confounding variables (34-36).

The first and foremost unpredictable complication after carotid artery sacrifice is *embolization* arising from thrombus in the occluded supraclinoid segment of the internal carotid artery (6,35). Opponents site several other limitations of BTO, including (a) BTO is performed under ideal conditions that do not truly test the patient during additional is-chemic challenge such as hypotension, vasospasm, and radiation-induced vasculopathy (4); (b) regional CBF measurements are technically challenging and time consuming (35); and (c) the risk of complication from BTO alone varies from 0% to 8.3% (6,34).

In the largest series, comprising 500 BTO procedures (6), 3.2% had complications. Asymptomatic complications were seen in 1.6%, including dissection (1.2%), pseudoaneurysm formation (0.2%), and embolism (0.2%). Neurologic deficits that persisted beyond the test period were also seen in 1.6%; these were either transient (1.2%) or permanent (0.4%). In one series, approximately 50% of asymptomatic patients with a positive SPECT scan after BTO had a positive MRI scan. This suggests that patients sustain residual focal subclinical ischemia due to the test occlusion (31). The neurologic complication rate'after diagnostic cerebral angiography ranges from 1.3% to 2.6%, which is similar to the neurologic complication rate from BTO (6,37,38).

Some surgeons have abandoned internal carotid artery occlusion^laiming that it is never totally safe (36,39). Delayed ischemic neurologic complications may occur several years after carotid artery ligation (24,40-43). The natural history of carotid occlusion without revascularization in young patients is unknown (44). Aneurysm formation after carotid ligation has been described as a potential complication (45). Opponents of BTO advocate liberal revascularizaton and preservation of the carotid whenever possible (34,44).

Conclusions

1. Balloon test occlusion of the internal carotid artery with only clinical neurologic monitoring is an inadequate evaluation of cerebrovascular reserve. BTO should always be accompanied by CBF studies, such as Xe CT or SPECT.
2. Preoperative assessment assists decision making by indicating inadequate CBF reserves.
3. Causes of stroke after carotid occlusion include marginal perfusion due to inadequate collateral circulation and embolization of clot from the occluded segment of carotid artery.
4. BTO with CBF studies predict many, but not all, delayed neurologic sequelae after carotid artery sacrifice.

INTERVENTIONAL RADIOLOGIC PROCEDURES

Fine-Needle Aspiration Biopsy

Technique

Computed tomography- or MRI-guided fine-needle aspiration biopsy (FNAB) is a potent diagnostic tool in the evaluation of head and neck disease. Deep or nonpalpable lesions that would otherwise require an open surgical biopsy sampling procedure are made accessible with imaging guidance (46). FNAB is especially valuable in areas of anatomic distortion secondary to surgery or radiation (47).

Fine-needle aspiration biopsy is performed in an outpatient setting. The procedure is carefully explained to the patient. Intravenous sedation and analgesia are given with midazolam (Versed) and fentanyl. Lidocaine is used for local anesthesia.

Stainless steel needles are unsuitable for MRI because of high magnetic susceptibility and the creation of large artifacts. MRI-compatible needles have been developed that have a higher nickel content than stainless steel (48-50). Nickel stabilizes iron in a nonmagnetic form and reduces the magnetic susceptibility artifact of stainless steel (51). The advantages of MRI guidance include imaging in any plane, which makes it easy to follow the needle by imaging in a plane orthogonal to the path of the needle. MRI also has superior soft tissue contrast resolution (48).

Twenty-two- to 26-gauge needles are used for FNAB. To avoid multiple needle insertions, a coaxial needle system can be used. A 19-gauge/22-gauge combination can be used, but for areas such as the head and neck, where critical, complex anatomy is contained in a compact space, smaller needles are preferred to minimize risk to neural and vascular structures. Another benefit of a smaller needle is improved patient comfort. Lufkin and Layfield (52) describe a smaller coaxial needle system using a standard 22-gauge MRI-compatible needle that accepts a 26-gauge needle. The smaller 26-gauge needle should be chosen so the tip extends 5 to 10 mm beyond the tip of the larger 22-gauge needle. A small amount of curve is formed in the tip of the smaller needle. Once the 22-gauge needle is positioned at the margin of the lesion, no further imaging is necessary. The 26-gauge needle is inserted and multiple aspirations are performed with varying tip angulations and depths until adequate cells are obtained for cytologic diagnosis (52).

Approach

The approach depends on the area to be sampled (46,48,53-55).



FIG. 7. Fine-needle aspiration biopsy: approach to lesions of the skull base. A: Skull demonstrating anterior subzygomatic approach *(arrow).* Note foramen ovale. B: Axial computed tomography scan with needle in position to sample mass in the lateral pterygoid muscle. C: Lateral subzygomatic approach *(arrow 1)* and retromandibular approach *(arrow2).* D: Submastoid approach *(arrow).*

Anterior Subzygomatic

This approach is best for lesions in the region of the foramen ovale, parapharyngeal space, and infratemporal fossa (46,55) (Fig. 7A,B). The needle is inserted inferior to the malar eminence of the zygomatic bone parallel to the lateral wall of the maxilla. The neck should be slightly extended with a small pad placed beneath the shoulders. The head is rotated 15 to 20 degrees away from the side of the lesion. This opens a direct line from the anterior face to the foramen ovale, which does not cross vital structures. Care must be taken to avoid injury to the carotid artery and the cavernous sinus.

Lateral Subzygomatic

This approach is best for paranasopharyngeal and infratemporal fossa lesions (48) (see Fig. 7). The needle is inserted inferior to temporal zygomatic process and superior to the coronoid notch of the mandible.

Retromandibular ,

This path isjasedjbr paraesophageal, parotid, and masticator space lesions (see Fig. *1C)*. The needle is placed posterior to the mandibular ramus.

Submastoid

Skull base disease (e.g., jugular foramen lesions) may be sampled using the submastoid approach (see Fig. 7D). The needle is inserted at the inferior mastoid tip, angled cranially, and directed in a rostrad direction.

Therapeutic Techniques: Preoperative Embolization of Vascular Lesions

The goal of preoperative embolization is to decrease tumor vascularity and facilitate surgical removal (56). Embolization may also be performed for palliation and has the advantage of being readily repeatable. Embolization of the *external carotid artery* should not be undertaken lightly. There is potentially dangerous flow to the central nervous system, cranial nerves, and orbit. Risks include stroke and cranial nerve palsies and blindness (57,58). A thorough understanding of neurovascular anatomy and the important "dangerous" anastomoses is critical (58-60) (Tables 1-5).

The *ascending pharyngeal artery* supplies the pharynx, base of skull, posterior fossa, and cranial nerves IX, X, XI, and XII. There are also normal anastomoses between the ascending pharyngeal and the vertebral and internal carotid arteries (59).

The *middle meningeal artery* supplies the skull base and dura and cranial nerve VII. There are also important anasto-

TABLE 1. *Anastomoses of the ascending pharyngeal artery*

Communicates with	By way of
Occipital artery	C-1/C-2 collaterals
Vertebral artery	Odontoid and spinomuscular branches
Middle meningeal	
Meningohypophyseal trunk	Clival branches
Inferolateral trunk	
Distal internal maxillary artery	
Petrous internal carotid artery	Persistent mandibular (mandibulovidian) artery

Modified with permission, from ref. 4.

TABLE 2. *Anastomoses of the internal maxillary artery*

Communicates with	By way of
Ophthalmic artery (orbit)	Anterior and posterior ethmoidal branches (ophthalmic artery) Orbital branch middle meningeal Anterior deep temporal Infraorbital Sphenopalatine
Cavernous ICA	Inferolateral trunk Artery of the foramen rotundum Accessory meningeal artery Vidian artery
Petrous ICA	Persistent mandibular (mandibulovidian) artery

ICA, internal carotid artery.

TABLE 3. *Anastomoses of the occipital artery*

Communicates with	By way of
Vertebral artery	C-1/C-2 collaterals Costocervical, thyrocervical trunks

TABLE 4. *Anastomoses of the middle meningeal artery*

Communicates with	By way of
Ophthalmic artery	Anomalous-origin ophthalmic artery Lacrimal artery
Cavernous internal carotid artery	Falx and meningeal branches of ethmoidal arteries from ophthalmic artery

TABLE 5. *Causes of extracranial vertebral artery aneurysms*

Dissecting hematoma
Fibromuscular dysplasia
Collagen diseases (Ehler-Danlos syndrome)
Neurofibromatosis
Atherosclerosis
Trauma
Radionecrosis



FIG. 8. Common carotid arteriogram (lateral projection) showing near-occlusion of the internal carotid artery. Note retrograde filling of the carotid siphon *(curved arrow)* from the ophthalmic artery *(arrow),* which opacities through branches of the internal maxillary artery *(open arrow).*

moses with the ophthalmic artery and the cavernous internal carotid (59).

The distal *internal maxillary artery* may supply the eye by anterior deep temporal, infraorbital, and sphenopalatine branches (59) (Figs. 8, 9).

There is a consistent anastomosis between the *occipital artery* and the vertebral artery (Fig. 10).

These anastomoses may fail to appear on the initial arteriogram, but this does not mean they do not exist (58). As embolization progresses, distal perfusion decreases and the hemodynamic balance and flow patterns change, opening potentially dangerous collaterals (57,58).

The goal of embolization dictates the type of embolic agent (Table 6). Gelfoam is absorbable and is considered a temporary embolic agent, whereas coils, polyvinyl alcohol, and tissue adhesives are permanent. Therapeutic embolization is palliative but rarely curative. It must be remembered that collateral vessels will form and occluded vessels will recanalize, even after treatment with so called "permanent" embolic materials (61-64). Recanalization occurs slowly over weeks and months and should not be of clinical concern if embolization is performed several hours or days before surgery (61).

Alcohol and small particulate emboli, such as Gelfoam or polyvinyl alcohol particles, penetrate deeply distal to the point at which a surgical ligature may be applied. Liquid and small emboli produce optimal devascularization because they destroy the nidus and penetrate beyond where collateral flow may resupply the lesion (58). These are the most dangerous of the embolic agents because the liquids and small panicles may reach tiny anastomoses with major intracranial vessels or arteries supplying cranial nerves. The result is the potential for disastrous complications, such as stroke and cranial nerve palsies. Large emboli, such as detachable balloons and wire coils, achieve proximal occlusion similar to surgical ligation. Proximal occlusion may be ineffective because of recruitment of collateral vessels to supply the lesion. Proximal occlusion also blocks access to the lesion if additional embolization therapy is necessary (57).



FIG. 9. Left common carotid arteriogram, anteroposterior **(A)** and lateral (B) projections. There is occlusion of the internal carotid artery. Note filling of the distal internal carotid *(arrow)* from the vidian branch of the mandibular artery *(open arrow),* which is filled by branches of the internal maxillary artery *(curved arrow).*

FIG. 10. Common carotid arteriogram (lateral projection) showing occlusion of the vertebral artery *(curved arrow),* which fills from C1-2 collaterals *(open arrows)* by way of the occipital artery *(arrow).*

When embolization involves branches of the external carotid artery, 2 in. of nitroglycerin ointment (Nitro-paste) is applied cutaneously before the procedure to prevent vasospasm *(65).*

Before embolization, provocative testing of the arterial feeder must be performed with 25 to 50 mg of cardiac lidocaine to discover the cranial nerve blood supply (57,66). If lidocaine injection produces a cranial nerve deficit, then the vessel cannot be safely embolized with Gel foam powder or liquid agents (57). Larger particles may be used to produce a more proximal occlusion and allow recruitment of collateral vessels (67). Protection of normal vascular territories may be accomplished by using a large piece of Gelfoam or poly vinyl alcohol sponge to occlude a "dangerous anastomosis" to prevent emboli from entering the unwanted normal artery (67,68). Amytal testing (50 mg) is used if there is potential supply to intracranial structures.

TABLE 6. *Embolic agents*



- Liquid
  - 95% Ethanol
  - Tissue adhesives (e.g., *N*-butyl cyanoacrylate)
- Small particulate emboli
  - Gelfoam powder
  - Gelfoam particles
  - Polyvinyl alcohol
- Large particulate emboli
  - Suture
  - Coils (stainless steel, platinum)
  - Detachable balloons

Embolic material may be introduced by catheter or by direct puncture. Most vascular lesions of the head and neck are supplied by branches of the external carotid artery. Once the tumor has invaded the skull base, blood supply may be recruited from internal carotid or vertebral artery branches that would be difficult or impossible to approach safely with small catheters. Direct percutaneous, transoral, or transnasal puncture of these lesions under general anesthesia makes them amenable to treatment with liquid embolic agents, such as alcohol or N-butyl cyanoacrylate (NBCA) (69).

Complete surgical removal of *meningiomas* can be facilitated by preoperative tumor devascularization (56). Most meningiomas at the convexity are extremely vascular, whereas fewer than half of those at the skull base are vascular enough to warrant embolization (67). Angiographic evaluation includes study of both internal and external carotid arteries. The convexity meningiomas are supplied by ipsilateral and contralateral middle meningeal arteries. If there is extension to the falx, the anterior falx artery arising from the ophthalmic is involved. Meningiomas of the skull base are supplied by the ascending pharyngeal, occipital, and posterior auricular arteries, the posterior meningeal branch of the vertebral artery, and the posterior clival and tentorial branches of the cavernous internal carotid artery (67). Meningiomas may recruit pial blood supply from cerebral branches of the internal carotid artery.

Preoperative embolization *of juvenile nasopharyngeal angiofibromas* can reduce intraoperative blood loss. After combined embolization and surgery, tumor recurrence is reduced, probably because of more complete removal of a devascularized tumor (57).

Both internal maxillary arteries should be studied. There may also be supply from ipsilateral and contralateral accessory meningeal, ascending pharyngeal, and ascending palatine arteries. Angiography of both internal carotid arteries is necessary to define potential supply from the cavernous carotid, ethmoid, and mandibular arteries (57,68).

For *paragangliomas* originating in the temporal bone (Fig. 11), ipsilateral internal carotid, vertebral, and external carotid arteries should be evaluated. External carotid supply may arise from the posterior auricular, occipital, and ascending pharyngeal arteries (57). Intracranial extension of paragangliomas may be supplied by branches of the posterior inferior cerebellar artery or anterior inferior cerebellar branches of the vertebrobasilar system (70). For cervical lesions, the ipsilateral internal carotid, vertebral, and external carotid arteries are examined. Potential external carotid supply includes the facial, lingual, superior thyroid, ascending cervical, and both ascending pharyngeal arteries. *Carotid body* tumors are also supplied by the artery of the carotid body (57,70).



FIG. 11. Glomus jugulotympanicum. A: Axial computed tomography scan. There is erosion of the caroticojugular spine *(arrow)* and the lateral wall of the jugular fossa *(open arrow),* with extension of the mass into the middle ear *(white arrow).* B: Axial T1-weighted magnetic resonance image with gadolinium enhancement. There is an enhancing mass in the right jugular fossa *(arrow).* The signal voids *(curved arrows)* represent enlarged feeding arteries. C: External carotid arteriogram (lateral projection). There is a hypervascular tumor *(arrow)* fed by the ascending pharyngeal artery *(open arrow).* D: A Tracker catheter *(open arrow)* has been advanced into the ascending pharyngeal artery before embolization of the glomus tumor *(arrow).*

Conclusion

Preoperative embolization facilitates surgery by decreasing blood loss and allowing more complete removal of devascularized tumor. Thorough knowledge of neurovascu-W anatomy is necessary for safe, effective endovascular therapy.

\ \

ACKNOWLEDGMENT

\

The author thanks Kathy Sommers for invaluable assistance in preparing the manuscript.

REFERENCES

1. Donald PJ. Management of the internal carotid artery in skull base operations. *WestJMed* 1993;159:70-71.
2. Andrews JC, Valavanis A, Fisch U. Management of the internal carotid artery in surgery of the skull base. *Laryngoscope* 1989;99:1224-1229.
3. Linskey ME, Jungreis CA, Yonas H, et al. Stroke risk after abrupt internal carotid artery sacrifice: accuracy of preoperative assessment with balloon test occlusion and stable xenon-enhanced CT. *AJNR Am JNeuroradiol* 1994;15:829-843.
4. DeVries EJ, Sekhar LN, Horton JA, et al. A new method to predict safe resection of the internal carotid artery. *Laryngoscope* 1990:100:85-88.
5. Yonas H, Gur D, Johnson DW, Latchaw RE. Xenon/CT cerebral blood flow analysis. In: Lathcaw RE, ed. *MR and CT imaging of the head, neck and spine.* 2nd ed. St. Louis: Mosby-Year Book, 1991:109-128.

6. Mathis JM, Barr JD, Jungreis CA, et al. Temporary balloon test occlusion of the internal carotid artery: experience in 500 cases. *AJNR Am J Neuroradiol* 1995:16:749-754.

7. Mathis JM, Barr JD, Jungreis CA, Horton JA. Physical characteristics of balloon catheter systems used in temporary cerebral artery occlusion. *AJNR Am J Neuroradiol* 1994; 15:1831-1836.

8. Sundt TM Jr. Sharbrough FW, Anderson RE, et al. Cerebral blood flow measurements and electroencephalograms during carotid endarterectomy.,/ *Neurosurg* 1974:41:310-320.

9. Astrup J, Symon L, Branston NM, et al. Cortical evoked potential and extracellular K^f and H^+ at critical levels of brain ischemia. *Stroke* 1977;8:51-57.

10. Morawetz RB, DeGirolami U, Ojeamann RG, et al. Cerebral blood flow determination by hydrogen clearance during middle cerebral artery occlusion in unanesthetized monkeys. *Stroke* 1978:9:143—149.

11. Jones TH, Morawetz RB, Crowell RM, et al. Thresholds of focal cerebral ischemia in awake monkeys. *J Neurositrg* 1981;54:773-782.

12. Sekhar LN. The work-up and management of the internal carotid artery in neoplastic and vascular lesions of the cranial skull base. In: *Sacramento skull base surges symposium: a multidisciplinary approach.* Course syllabus. University of California, Davis. June 25-30, 1995: 76-80.

13. Rodgers GK, Applegate L, De la Cruz A, Lo W. Magnetic resonance angiography: analysis of vascular lesions of the temporal bone and skull base. *Am J Otol* 1993:14:56-62.

14. Mattas R. testing the efficiency of collateral circulation as a preliminary to the occlusion of the great surgical arteries. *Ann Surg* 1911:53:1^13.

15. Tarr RW. Jungreis CA, Horton JA, et al. Complications of preoperative balloon test occlusion of the internal carotid arteries: experience in 300 cases. *Skull Base Surgery* 1991; 1:240-244.

16. Kelly JJ, Callow AD, O'Donnell TF, et al. Failure of carotid artery stump pressures: its incidence as a predictor for temporary shunt during carotid endarterectomy. *Arch Surg* 1979;! 14:1361-1366.

17. Steed DL, Webster MW, DeVries EJ, et al. Clinical observations on the effect of carotid artery occlusion on cerebral blood flow mapped by xenon computed tomography and its correlation with carotid artery back pressure. *Vase Surg* 1990;! 1:38^14.

18. Askienazy S, Lebtahi R, Meder JF. SPECT HMPAO and balloon test occlusion: interest in predicting tolerance prior to permanent cerebral artery occlusion. *J Nucl Med* 1993;34:1243-1245.

19. Russell EJ, Goldberg K, Oskin J, Darling C, Melen O. Ocular ischemic syndrome during carotid balloon occlusion testing. *AJNR Am J Neurorarfio*/1994;15:258-262.

20. Mclvor NP, Willinsky RA, TerBrugge KA, Rutka JA. Freeman JL. Validity of test occlusion studies prior to carotid artery sacrifice. *Head Neck* 1994:16:11-16.

21. Nayak UK, Donald PJ, Stevens D. Internal carotid artery resection for invasion of malignant lumors. *Arch Otolarvngol Head Neck Surg* 1995:121:1029-1033. "~" -—"""""

22. Nishioka H. Report on the Cooperative Study of Intracranial Aneurysms and Subarachnoid Hemorrhage, section VIII, part 1: results of the treatment of intracranial aneurysms by occlusion of the carotid artery in the neck. *J Neurositrg* 1966;24:660-682.

23. Eckard DA, Purdy PD. Bonte FJ. Temporary balloon occlusion of the carotid artery combined with brain flow imaging as a test to predict tolerance prior to permanent carotid sacrifice. *AJNR Am J Neuroradiol* 1992:13:1565-1569.

24. Linskey ME, Sekhar LN, Horton JA, Hirsch WL, Yonas H. Aneurysms of the intracavernous carotid artery: a multidisciplinary approach to treatment. *J Neumsurg* 1991 ;75:525-534.

25. Yonas H, Gur D, Good BC, et al. Stable xenon CT blood flow mapping for evaluation of patients with extracranial-intracranial bypass surgery. *J-tjeurosurg* 1985:62:324-333.

26. Gu\D, Good WF, Wolfson SK, Yonas H, Shabason L. In vivo mapping of local cerebral flow by xenon-enhanced computed tomography. *Science* r982;215:1267-1268.

21. Yonas H Darby JM, Marks EC, Durham SR, Maxwell C. CBF measured fry Xe-CT: approach to analysis and normal values. *J Cereb Blood F\low Metab* 1991:11:716-725.

28. Nakano; S, Kinoshita K, Jinnouchi S, Hoshi H. Watanabe K. Comparative study of regional cerebral flow images by SPECT using xenon-133, \ iodinefl23 IMP, and technetium-99m HM-PAO. *J Nucl Med* 1989^0:157-164.

29. Peterman SB, Taylor A, Hoffman JC. Improved detection of cerebral hypoperfusion with internal carotid balloon test occlusion and 99m Tc-HMPAO cerebral perfusion SPECT imaging. *AJNR Am J Neuroradiol* 1991:12:1035-1041.

30. Monsein LH, Jeffrey PJ, van Heerden BB, et al. Assessing adequacy of collateral circulation during balloon test occlusion of the internal carotid artery with 99m Tc-HMPAO SPECT. *AJNR Am J Neuroradiol* 1991:12:1045-1051.

31. Simonson TM, Ryals TJ. Yuh WTC. Farrar GP, Rezai K, Hoffman HT. MR imaging and HMPAO in conjunction with balloon test occlusion. *AJR Am J Roentgenol* 1992;159:1063-1068.

32. Yonas H, Linsky M, Johnson DW, et al. Internal carotid balloon test occlusion does require quantitative CBF. *AJNR Am J Neuroradiol* 1992:13:1147-1152.

33. Witt .IP, Yonas H, Jungeis C. Cerebral blood flow response pattern during balloon test occlusion of the internal carotid artery. *AJNR Am J Neuroradiol* 1994;15:847-857.

34. Origitano TC, Al-Mefty O, Leonetti JP, DeMonte F, Reichman OH. Vascular considerations and complications in cranial base surgery. *Neurosurgeiy* 1994:35:351-363.

35. Eskridge JM. Xenon-enhanced CT: past and present. *AJNR Am J Neuroradiol* 1994;15:845-846.

36. Sekhar LN, Patel SJ. Permanent occlusion of the internal carotid artery during skull base surgery: is it really safe? *Am J Otol* 1993:14:421^122.

37. Dion JE, Gates PC, Fox AJ, Barnett HJM, Blom RJ. Clinical events ollowing neuroangiography: a prospective study. *Stroke* 1987:18: 997-1004.

38. Ernest F, Forbes G, Sandok BA, et al. Complications of cerebral angiography: prospective assessment of risk. *AJR Am J Roentgenol* l984;142:247-253.

39. Spetzler RF, Fukushima T. Martin N, Zabramski JM. Petrous carotid-to-intradural carotid saphenous vein graft for intracavernous giant aneurysm, tumor, and occlusive cerebrovascular disease. *J Neurosurg* 1990:73:496-501.

40. Roski RA, Spetzler RF, Nulsen FE. Late complications of carotid ligation in the treatment of intracranial aneurysms. *J Neurosurg* 1981;54:583-587.

41. Barnett HJ. Delayed ischemic episodes distal to occlusion of major cerebral arteries. *Neurology* 1978:28:769-774.

42. Oldershaw JB, Voris HC. Internal carotid artery ligation, a follow up study. *Neurology* 1966;16:937-938.

43. Winn HR, Richardson AE, Jane JA. Late morbidity and mortality of common carotid ligation for posterior communicating aneurysms. / *Neurosurg* 1977:47:727-736.

44. Sekhar LN, Sen CN, Jho HD. Saphenous vein graft bypass of the internal carotid artery. *J Neurosurg* 1990:72:35^-1.

45. Dyste GN, Beck DW. De Novo aneurysm formation following carotid ligation: case report and review of the literature. *Neurosurgerv* 1989:24:88-92.

46. Barakos JA, Dillon WP. Lesions of the foramen ovale: CT-guided fine-needle aspiration. *Radiology* 1992:182:573-575.

47. Abemayor E, Ljung BM, Larsson S, Ward PH, Hanafee W. CT-directed fine needle aspiration biopsies of masses in the head and neck. *Laryngoscope* 1985:95:1382-1386.

48. Duckwiler G, Lufkin RB, Teresi L, et al. Head and neck lesions: MR-guided aspiration biopsy. *Radiology* 1989; 170:519-522.

49. Lufkin R, Teresi L, Hanafee W. New needle for MR-guided aspiration cytology of the head and neck. *AJR Am J Roentgenol* 149:380-382.

50. Hathout G, Lufkin RB, Jabour B, Andrews J, Castro D. MR-guided aspiration cytology in the head and neck at high field strength. *JMagn Reson Imaging* 1992;2:93-94.

51. Mueller PR, Stark DD, Simeone JF, et al. MR-guided aspiration biopsy: needle design and clinical trials. *Radiology* 1986:161:605-609.

52. Lufkin R, Layfield L. Coaxial needle system of MR- and CT-guided aspiration cytology. *J Comput Assist Tomogr* 1989;13:1105-1107.

53. Dresel SH, Mackey JK, Lufkin RB, et al. Meckel cave lesions: percutaneous fine-needle-aspiration biopsy cytology. *Radiology* 1991;179:579-581.

54. Ljung BME, Larsson SG, Hanafee W. Computed tomography-guided aspiration cytologic examination in head and neck lesions. *Archives of Otolaryngology* 1984:110:604-607.

55. Yousem DM, Sack MJ, Scanlan, KA. Biopsy of parapharyngeal space lesions. *Radiology* 1994:193:619-622.

56. Manelfe C. Lasjaunias P, Ruscalleda J. Preoperative embolization of intracranial meningiomas. *AJNR Am J Neuroradiol* 1986:7:963-972.

6. Mathis JM, Barr JD, Jungreis CA, et al. Temporary balloon test occlusion of the internal carotid artery: experience in 500 cases. *A.INR Am .1 Neuroradiol* 1995:16:749-754.
7. Mathis JM, Barr .ID, Jungreis CA, Horton JA. Physical characteristics of balloon catheter systems used in temporary cerebral artery occlusion. *AJNR Am./ Neuroradiol* 1994; 15:1831 -1836.
8. Sundt TM Jr. Sharbrough FW, Anderson RE, et al. Cerebral blood flow measurements and electroencephalograms during carotid endarterectomy. *JNeurosurg* 1974:41:310-320.
9. Astrup J, Symon L, Branston NM. et al. Cortical evoked potential and extracellular K^+ and H^+ at critical levels of brain ischemia. *Stroke* 1977:8:51-57.
10. Morawetz RB, DeGirolami U, Ojeamann RG, et al. Cerebral blood flow determination by hydrogen clearance during middle cerebral artery occlusion in unanesthetized monkeys. *Stroke* 1978:9:143-149.
11. Jones TH, Morawetz RB. Crowell RM, et al. Thresholds of focal cerebral ischemia in awake monkeys. *J Neurosurg* 1981:54:773-782.
12. Sekhar LN. The work-up and management of the internal carotid artery in neoplastic and vascular lesions of the cranial skull base. In: *Sacramento skull base surgery symposium: a multidisciplinary' approach.* Course syllabus, University of California. Davis. June 25-30. 1995: 76-80.
13. Rodgers GK. Applegate L, De la Cruz A, Lo W. Magnetic resonance angiography: analysis of vascular lesions of the temporal bone and skull base. *Am J Otol* 1993:14:56-62.
14. Mattas R. testing the efficiency of collateral circulation as a preliminary to the occlusion of the great surgical arteries. *Ann Surg* 1911 ;53:1—43.
15. Tarr RW, Jungreis CA, Horton JA, et al. Complications of preoperative balloon test occlusion of the internal carotid arteries: experience in 300 cases. *Skull Base Surgery* 1991; 1 -*.240-244.*
16. Kelly JJ, Callow AD, 6'Donnell TF, et al. Failure of carotid artery stump pressures: its incidence as a predictor for temporary shunt during carotid endarterectomy. *Arch Surg* 1979;! 14:1361-1366.
17. Steed DL, Webster MW, DcVries EJ. et al. Clinical observations on the effect of carotid artery occlusion on cerebral blood flow mapped by xenon computed tomography and its correlation with carotid artery back pressure. Vase *Surg* 1990;! 1:38-44.
18. Askienazy S, Lebtahi R, Meder JF. SPECT HMPAO and balloon test occlusion: interest in predicting tolerance prior to permanent cerebral artery occlusion. *J NuclMed* 1993;34:1243-1245.
19. Russell EJ, Goldberg K. Oskm J. Darling C, Melen O. Ocular ischemic syndrome during carotid balloon occlusion testing. *AJNR Am J Neuroradiol* 1994:15:258-262.
10. Mclvor NP. Willinsky RA, TerBrugge K A, Rutka JA, Freeman JL. Validity of test occlusion studies prior to carotid artery sacrifice. *Head Neck* 1994:16:11-16.
21. Nayak UK, Donald PJ, Stevens D. Internal carotid artery resection for invasion of malignant tumors. *Arch Oto/arvngol Head Neck Surg* 1995:121:1029-1033.
22. Nishioka H. Report on the Cooperative Study of Intracranial Aneurysms and Subarachnoid Hemorrhage, section VIII, part 1: results of the treatment of intracranial aneurysms by occlusion of the carotid artery in the neck. *J Neurosurg* 1966:24:660-682.
23. Eckard DA, Purdy PD, Bonte FJ. Temporary balloon occlusion of the carotid artery combined with brain flow imaging as a test to predict tolerance prior to permanent carotid sacrifice. *AJNR Am J Neuroradiol* 1992;13:1565-1569.
24. Linskey ME, Sekhar LN, Horton JA, Hirsch WL. Yonas H. Aneurysms of the intracavernous carotid artery: a multidisciplinary approach to treatment. *J Neurosurg* 1991;75:525-534.
25. Yonas H, Gur D, Good BC, et al. Stable xenon CT blood flow mapping for evaluation of patients with extracranial-intracranial bypass surgery. *J Neurosurg* 1985:62:324-333.
26. Gur D) Good WF, Wolfson SK, Yonas H, Shabason L. In vivo mapping of local cerebral flow by xenon-enhanced computed tomography. *Science* 19.82:215:1267-1268.
27. Yonas H, Darby JM. Marks EC, Durham SR, Maxwell C. CBF measured py Xc-CT: approach to analysis and normal values. *J Cereb Blood flow Metab* 1991; 11:716-725.
28. Nakanb S, Kinoshita K, Jinnouchi S. Hoshi H, Watanabe K. Comparative stiidy of regional cerebral flow images by SPECT using xenon-133, iodin<j!-123 IMP, and technetium-99m HM-PAO. *J Nucl Med* 1989}30:157-164.
29. Peterinan SB, Taylor A, Hoffman JC. Improved detection of cerebral hypoperfusion with internal carotid balloon test occlusion and 99m Tc-HMPAO cerebral perfusion SPECT imaging. *AJNR Am J Neuroradiol* 1991:12:1035-1041.
30. Monsein LH, Jeffrey PJ, van Heerden BB, et al. Assessing adequacy of collateral circulation during balloon test occlusion of the internal carotid artery with 99m Tc-HMPAO SPECT. *AJNR Am J Neuroradiol* 1991:12:1045-1051.
31. Simonson TM, Ryals TJ, Yuh WTC, Farrar GP, Rezai K, Hoffman HT. MR imaging and HMPAO in conjunction with balloon test occlusion. *AJR Am J Roentgenol* 1992;159:1063-1068.
32. Yonas H, Linsky M, Johnson DW, et al. Internal carotid balloon test occlusion does require quantitative CBF. *AJNR Am J Neuroradiol* 1992:13:1147-1152.
33. Witt JP. Yonas H, Jungeis C. Cerebral blood flow response pattern during balloon test occlusion of the internal carotid artery. *AJNR Am J Neuroradiol* 1994:15:847-857.
34. Origitano TC, Al-Mefty O, Leonetti JP, DeMonte F, Reichman OH. Vascular considerations and complications in cranial base surgery. *Neurosurgery* 1994:35:351-363.
35. Eskridge JM. Xenon-enhanced CT: past and present. *AJNR Am J Neuroradiol* 1994:15:845-846.
36. Sekhar LN, Patel SJ. Permanent occlusion of the internal carotid artery during skull base surgery: is it really safe?/1m *J Otol* 1993:14:421-422.
37. Dion JE, Gates PC, Fox AJ, Barnett HJM, Blom RJ. Clinical events ollowing neuroangiography: a prospective study. *Stroke* 1987;18: 997-1004.
38. Ernest F, Forbes G, Sandok BA, et al. Complications of cerebral angiography: prospective assessment of risk. *AJR Am J Roentgenol* 1984:142:247-253.
39. Spetzler RF. Fukushima T. Martin N, Zabramski JM. Petrous carotid-to-intradural carotid saphenous vein graft for intracavernous giant aneurysm, tumor, and occlusive cerebrovascular disease. *J Neurosurg* 1990:73:496-501.
40. Roski RA, Spetzler RF, Nulsen FE. Late complications of carotid ligation in the treatment of intracranial aneurysms. *J Neurosurg* 1981:54:583-587.
41. Barnett HJ. Delayed ischemic episodes distal to occlusion of major cerebral arteries. *Neurology* 1978:28:769-774.
42. Oldershaw JB, Voris HC. Internal carotid artery ligation. a follow up study. *Neurology* 1966; 16:937-938.
43. Winn HR. Richardson AE, Jane JA. Late morbidity and mortality of common carotid ligation for posterior communicating aneurysms. *J Neurosurg* 1977:47:727-736.
44. Sekhar LN, Sen CN, Jho HD. Saphenous vein graft bypass of the internal carotid artery. *J Neurosurg* 1990:72:35^11.
45. Dyste GN, Beck DW. De Novo aneurysm formation following carotid ligation: case report and review of the literature. *Neurosurgery* 1989:24:88-92.
46. Barakos JA. Dillon WP. Lesions of the foramen ovale: CT-guided fine-needle aspiration. *Radiology* 1992:182:573-575.
47. Abemayor E, Ljung BM, Larsson S, Ward PH, Hanafee W. CT-directed fine needle aspiration biopsies of masses in the head and neck. *Laryngoscope* 1985:95:1382-1386.
48. Duckwiler G, Lufkin RB, Teresi L, et al. Head and neck lesions: MR-guided aspiration biopsy. *Radiology* 1989:170:519-522.
49. Lufkin R, Teresi L, Hanafee W. New needle for MR-guided aspiration cytology of the head and neck. *AJR Am J Roentgenol* 149:380-382.
50. Hathout G, Lufkin RB, labour B, Andrews J, Castro D. MR-guided aspiration cytology in the head and neck at high field strength. *J Magn Re-son Imaging* 1992;2:93-94.
51. Mueller PR, Stark DD, Simeone JF, et al. MR-guided aspiration biopsy: needle design and clinical trials. *Radiology* 1986:161:605-609.
52. Lufkin R, Layfield L. Coaxial needle system of MR- and CT-guided aspiration cytology. *J Comput Assist Tomogr* 1989; 13:1105-1107.
53. Dresel SH, Mackey JK, Lufkin RB, et al. Meckel cave lesions: percutaneous fine-needle-aspiration biopsy cytology. *Radiology* 1991:179:579-581.
54. Ljung BME, Larsson SG, Hanafee W. Computed tomography-guided aspiration cytologic examination in head and neck lesions. *Archives of Otolaryngology* 1984;! 10:604-607.
55. Yousem DM, Sack MJ, Scanlan, KA. Biopsy of parapharyngeal space lesions. *Radiology* 1994; 1^3:619-622.
56. Manelfe C, Lasjaunias P, Ruscalleda J. Preoperative embolization of intracranial meningiomas. *AJNR Am J Neuroradiol* 1986;7:963-972.

57. Kagetsu NJ, Berenstein A, Choi S. Interventional radiology of the extracranial head and neck. *Cardiovasc Intervent Radial* 1991; 14: 325-333.
58. Russell EJ. Functional angiography of the head and neck. *AJNR Am J Neuroradiol* 1986:7:927-936.
59. Eskridge JM. Interventional neuroradiology. *Radiology* 1989:172: 991-1006.
60. Lasjaunias P, Berenstein A. Dangerous vessels. In: *Surgical neuroangiography, vol. 1: functional anatomv of craniofacial arteries.* Berlin, Heidelberg: Springer-Verlag, 1987:239-244.
61. DavidsonGS.Terbrugge KG. Histologic long-term follow-up after embolization with polyvinyl alcohol particles. *AJNR Am J Neuroradiol* 1995;16:843-846.
62. Mathis JA, Barr JD. Horton JA, et al. The efficiency of paniculate embolization combined with stereotactic radiosurgery for treatment of large arteriovenous malformations of the brain. *AJNR Am J Neuroradiol* 1995; 16:299-306.
63. Germane IM, Davis RL, Wilson CB, Hieshima GB. Histopathological follow-up study of 66 cerebral arteriovenous malformations after therapeutic embolization with polyvinyl alcohol. *J Neurosurg* 1992;76: 607-614.
64. Purdy PD, Batjer HH. Risser RC, Samson D. Arteriovenous malformations of the brain: choosing embolic materials to enhance safety and ease of excision. *J Neurosurg* 1992:77:217-222.
65. Erba M, Jungreis CA, Horton JA. Nitropaste for prevention and relief of vascular spasm. *AJNR Am J Neuroradiol* 1989; 10:155-156.
66. Horton JA. Kerber CW. Lidocaine injection into external carotid branches: provocative test to preserve cranial nerve function in therapeutic embolization. *AJNR Am .7 Neuroradiol* 1986:7:105-108.
67. Halbach VV, Hieshima GB, Higashida RT, David CF. Endovascular therapy of head and neck tumors. In: Vinuela F, Halbach V, Dion J, eds. *Interventional neuroradiology: endovascular therapy of the central nervous system.* Raven Press: New York, 1992:17-28.
68. Davis KR. Embolization of epistaxis and juvenile nasopharyngeal angiofibromas. *AJNR Am J Neuroradiol* 1986;7:953-962.
69. Casasco A, Herbreteau D, Houdart E, et al. Devascularizaton of craniofacial tumors by percutaneous tumor puncture. *AJNR Am J Neuroradiol* 1994:15:1233-1239.
70. Valavanis A. Preoperative embolization of the head and neck: indications, patient selection, goals, and precautions. *AJNR Am J Neuroradiol* 1986;7:943-952.

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 8

Nursing Care of Skull Base Surgery Patients

Ann E. F. Sievers and Denise Borcyckowski

CARING FOR THE PATIENT WITH A SKULL BASE LESION

An entire new combined discipline of otolaryngologic and neurosurgical nursing has developed with the advent of skull base surgery. This discipline combines the most advanced and dedicated aspects of both nursing practice professions. Those who choose to practice in this setting are working on an exciting and very challenging forefront of medical practice and nursing intervention.

Patients with skull base tumors, whether benign or malignant, present with unique problems because of tumor involvement of the brain, cranial nerves, and facial structures. Deformity of appearance and alterations in function are major deficits that can occur with such tumors and the surgical procedures that correct them. With the patient at the center and as the driving force of the process, the team approach is the only possible way to deliver comprehensive care (1).

The skull base team meets regularly and frequently to present each patient and to develop team consensus and a plan of care. The skull base team comprises specialists from many different disciplines. Physicians include specialists from departments of otolaryngology, neurosurgery, plastic surgery, pathology, both neurovascular and interventional radiology, nuclear medicine, anesthesiology, and their accompanying residents and fellows. Representatives of the nursing profession include clinical nurse specialists in both otolaryngology and neurosurgery, operating room clinicians, intensive care unit staff, otolaryngology staff nurses, clinic triage, nursing discharge planners, and home care staff. Multidisciplinary professional staff members include social service workers, nutritionists, physical therapists, speech pathologists, discharge planners, and home health liaison staff.

One of the pivotal roles in the skull base team is the team coordinator. This role consists not only of team coordination, but of compiling patient information and supporting team research. The skull base team coordinator is responsible for the inner workings of the team as well as interaction with the patient and family (Table 1).

The coordinator must be chosen carefully for his or her ability to coordinate multiple schedules and deal with stressful and complicated situations gracefully. This role requires a true professional. Coordination and communication with insurance agencies are essential functions in the environment of managed care programs. This insurance interface allows the patient to concentrate on his or her medical care and not the financial morass that often can add such significant stress to an already difficult situation. To secure funding is imperative before beginning testing, evaluation, and contraction for evaluation and intervention. By attending to these functions, the coordinator enables the skull base team, patient, and the family to concentrate on the most important aspect, the care of the patient.

Funding and insurance coverage of skull base surgery and evaluation is only beginning to be understood and accepted by insurance companies. The roles of the team are to interface with the insurance carriers and elucidate the complexity of skull base surgery, to educate them about the enormity of skull base surgery, and to ensure their cooperation and their acceptance of their responsibilities for patient coverage. The skull base team should develop an information book, a treatment algorithm, and a plan of care as standard information for insurance companies. The packet could include physician qualifications, research results, length of estimated hospitalizations, as well as hospital and professional charges.

Preparation and Patient Education

The skull base surgical team has an enormous task of planning not only for the surgical procedure and care plan, but for informing and educating the patient. Patient education and obtaining informed legal consent are two very different processes. Patient education is the ongoing process of learning,

---

A. E. F. Sievers, D. Borcyckowski: Departments of Patient Care Services and Otolaryngology—Head and Neck Surgery, University of California, Davis Medical Center, Sacramento, California 95817.

TABLE 1. *Skull base team coordinator responsibilities*

- Surgical scheduling
- Team meetings
- Preoperative test coordination
  - Specialized tests: computed tomography, magnetic resonance imaging, magnetic resonance angiography, balloon test occlusion, single-photon emission computed tomography, positron emission tomographys, biopsy
- Team information
- Total quality assurance (TQA)
- Policy and procedures
- Patient and family schedule coordination
- Insurance authorization
- Research, data collection and coordination
- Postoperative clinic scheduling
- Postoperative repeat testing

for the patient and family, about the patient's diagnosis and care. This is a huge process for those who have a life-threatening illness. It becomes incumbent on the skull base team members to recognize that learning under stress is suboptimal, but that learning about the plan of care is absolutely necessary to the patient's survival and cooperation with therapy. Translation of medical terms into "the common vernacular" enables better communication regarding illness and therapy. The authors often tell patients that this is an odyssey into a foreign land that they do not want to take, and that it includes learning a foreign language, "the medical language," again not because they choose to do so. The role of the skull base coordinator and the clinical nurse specialist is to translate information and be the ongoing simultaneous translators for the patient and family.

If the medical team is sensitive to these issues, the patient's and family's odyssey turns from a nightmare into a positive journey with much support, caring, and guidance. The most important issues to discuss are those related to survival and the unique facets of skull base surgery the patient faces during recovery. Patients often ask why they got cancer, and a frank discussion related to the known issues may allay the fears of other family members. Molecular epidemiology suggests that the effects of environmental exposure and poor nutrition can be exacerbated in certain groups by inborn differences in the internal processing of carcinogens (2). Patients and family need to discuss their individual fears of cancer and of the upcoming surgery. The issues are, but are not limited to, tracheostomy, alteration in method of nutrition (oral vs. enteral), disfigurement, balance disorders, and changes from normal activities of daily living. It is the lack of information related to their life changes, and the diagnosis of tumor, that often makes patients and their families unable to cope with the rigors of skull base surgery and recovery.

Informed Consent

Informed consent is a mandated legal process to attempt to ensure that patients understand and consent to medical care. Obtaining informed consent gives another opportunity to the skull base team to interact with the patient in the information process. If the patient is properly educated, signing the consent is often an anticlimax because trust and a cooperative tenor have developed over time. If a good cooperative relationship is not present, then this signing can often be *the* most stressful time. Patients have described signing the consent as "so what," "no problem," "I already knew everything anyway," to "this was the most terrifying time" and "I felt like I was signing my life away to someone else."

The establishment of cooperative trust between the skull base team and the patient and family occurs over time. Unfortunately, this is a period where the passage of time is stressful, and often painful. With the urgency of surgery looming, the skull base team must make every attempt to educate and inform at the earliest time available.

The Role of the Clinical Nurse Specialist

The clinical nurse specialist serves as one of the clinical coordinators of the multidisciplinary team, an advocate for the patient, and clinical nursing expert through the entire process. The traditional roles of the clinical nurse specialist include clinical expert, educator of both staff and patient, community liaison, researcher, and multidisciplinary team member. The clinical nurse specialist provides continuity of care from initial contact, to discharge to home, and return to the clinic. With the skull base team coordinator, the clinical specialist acts as case manager to streamline the medical system and as an advocate for the patient. This involves an interface with insurance providers, family, clinical nursing staff, and medical teams. The clinical specialist is the nursing clinical expert for staff nurses both in-house and for home nursing intervention.

Multidisciplinary Team

The multidisciplinary team (Table 2) meets twice a week, once on Tuesdays to review inpatient care needs and plans and again at the end of the week, usually on Fridays, to coordinate with the otolaryngology tumor board, meet new patients, and plan for the following week. The Tuesday meetings include all inpatient care planning needs regarding medication, ambulation, coping, pain management, family meetings, wound care and healing, cognition, airway care,

TABLE 2. *Multidisciplinary team members*

- Clinical nurse specialist
- Skull base coordinator
- Licensed clinical social worker
- Dietician
- Physical therapist
- Speech pathologist
- Discharge planner
- Home health liaison
- Hospice (as needed)
- Staff nurses
- Administrative staff nurses
- Occupational therapists (as needed)
- Physical medicine and rehabilitation team
- Dysphagia team (as needed)

nutrition, neurologic status, consultant reports, and in-house plan of care for educating patient and family for discharge.

In this forum, the team and staff conceptualize and develop teaching plans and formulate discharge plans. The team discusses psychosocial issues specifically regarding coping strategies, psychological adaptation, and behavior of both patient and family. They address staff issues and formulate plans for intervention. This organized group functions as a team to treat patients, but also as a peer review group and internal support group. When constantly, faced with patients whose diagnosis is of such gravity, it is important for the team to be introspective and support each other.

At the Friday team meeting, in conjunction with the tumor board and clinic, the multidisciplinary team meets new patients and formulate their plan of care with the physicians. The team evaluates former patients for ongoing needs, including wound care, nutrition, coping, pain management, home care, and insurance status. Symptom control and home health problems often take precedence. The team communicates with the home health nurses, and home health plans are revised after team evaluation of the patient.

One of the critical purposes of the team meeting during tumor board is to evaluate new skull base patients who are presented at tumor clinic and discussed at tumor board. This is often the first time that a patient hears his or her diagnosis and its implications. This is also the first time the patient meets the team that will be caring for him or her throughout the hospitalization. Many patients often are unaware of the large numbers of professional staff required to care for them. In this initial meeting the beginnings of trust, education, and coping develop. Each patient receives a handbook describing the team, each member, and his or her role in the patient's care. These handbooks give patients and their families reference information, phone numbers, and contact information for use throughout hospitalization and home care.

The formal skull base team meeting occurs monthly or more often as is required by patient numbers and requirements for planning. This team meeting is primarily for medical decision making, care planning, and surgical operative planning. It is a time for the team to discuss issues of care, appropriate therapy, and coordination of surgical interventions, and the meeting provides the medical multidisciplinary team an opportunity critically to evaluate the preoperative testing results and finalize their plans. In the team meeting, both the skull base team coordinator and the operating room clinicians participate in the operative planning. This enables all parties to communicate better their requirements for care of each individual patient. „/

PREOPERATIVE NURSING CARE

Preoperative nursing care can be divided into two parts. Part I includes planning, organization, materials management, and research, and part II includes the provision of direct patient care. Part I consists of the behind-the-scenes planning that *must* make part II seamless for the patient and his or her family. Part I ensures that the collaborative care pathway is used properly and fully. A collaborative path allows for leveling of all personnel involved in the care of the patient, and also ensures that each discipline is aware of the other professional processes and plans of care.

In part II, the patient and family should see and experience team coordination without flaws or problems. In today's very complex medical systems and changes in insurance coverage, the health care system should work for the patient, not in spite of, or instead of, the patient's insurance coverage. Collaborative paths, patient information books, care plans, standing orders, and team meetings provide fundamental guidelines for the skull base team. These tools allow the practitioner to use time more efficiently to individualize the patient's immediate care needs.

Preoperative Testing

Preoperative testing for evaluation and suitability can be exhausting and can present a daunting prospect for patient and family. Nursing care is based on knowledgeable intervention with the patient regarding each test and procedure. Early identification of risk factors for postoperative pulmonary complications is extremely important. Six major risk factors have been identified as having a significant association with postoperative pulmonary complications. It is significant to have two or more of these risk factors present: (a) age 60 years or older, (b) impaired preoperative cognitive function, (c) smoking history within the past 8 weeks, (d) body mass index of 27 or greater, (e) history of cancer, and (f) any incision that was either above the umbilicus, or both above and below the umbilicus (3).

Preparation for the experience, adequate sedation (if required), and pain management may allow a person to undergo a computed tomography (CT) scan, magnetic resonance imaging, magnetic resonance angiography, or balloon test occlusion (BTO) without stress or fear. Confinement in the magnetic resonance or CT scanner is often very unsettling to many people, so the explanation of the duration and extent of the test allows the patient to understand and cooperate better with the examination. Communicating with radiology technicians regarding the person's particular concerns, such as claustrophobia, can often change the test from a frightening experience to one that is understandable and manageable. Sedation is contraindicated only if the patient has airway problems and cannot lie flat; these particular people may require significant sedation and therefore need closer observation by nursing or anesthesia staff to be able to complete the study.

When the team anticipates that the extent of surgery may include resection of the carotid artery, a BTO with single photon emission computed tomography (SPECT) scans before and after the test are necessary to evaluate the integrity of cerebral contralateral blood flow. These suitability studies themselves pose risks of stroke, and therefore require full explanations to the patient and family. The radiologist who will be conducting the study obtains consent from the patient.

The BTO is a sophisticated test involving the insertion of a balloon catheter (often a Swan-Ganz catheter) into the carotid system by the groin approach. The catheter is inserted into the involved carotid artery for an initial angiogram of the involved vessels and assessment of the integrity of collateral flow through the circle of Willis.

The second part of the test consists of inflating the catheter balloon to occlude the carotid internal artery. The patient is continually evaluated for any neurologic signs, such as eye pain, change in vision or speech, and loss of motor function or sensation to the extremities. If such signs appear, the balloon is deflated and the test suspended. The post-SPECT scan is done after 20 minutes of carotid occlusion. The nursing care of these patients focuses on site observation for arterial leaks, neurologic sequelae, and pain and stress management. BTO is an outpatient procedure, but patients are observed for 12 hours for insertion site bleeding or hematoma.

A pre-SPECT scan is a radionuclide study to evaluate the person's brain activity at normal carotid flow before balloon occlusion. The post-SPECT scan is done immediately after the BTO with the catheter balloon inflated to evaluate the blood flow from the opposite side of the brain to the brain tissue of the occluded side. This test ascertains opposite carotid flow adequacy if the involved carotid is resected. It also helps to determine whether a carotid resection is even possible and whether vein grafting replacement is a viable option.

If the patient requires a vascularized free flap for reconstruction, ultrasound mapping of the donor site is critical to define to the surgical team the position of the donor vessel and flow rates. This is not a painful procedure because it uses ultrasound technology, but the patient still must be adequately informed before the testing. The patient usually can have this procedure as an outpatient because it requires no medication or sedation.

With head and neck cancer, the initial tissue mapping study of the tumor often is a panendoscopy and tumor mapping. This is still done with skull base patients, but not as often as previously. A biopsy is critical for tissue diagnosis and planning but often takes a different direction than the traditional panendoscopy for head and neck cancer. This may be an infratemporal approach or an oral approach through the palate or posterior pharyngeal wall. The goals are still the same, to obtain tissue for diagnosis and to plan the operative procedure. Unlike in head and neck cancer patients, this pro—eedure may be omitted because the location of the tumor necessitates a more extensive surgery, and all is completed at the time of definitive surgical resection. The skull base team pathologist is in the operating room to diagnose the histo-logic type of tumor and the status of surgical margins. At this juncture, the surgeon needs to apprise the family of the plan of care, given the histologic type of the tumor. Support, understanding, and information from the clinical specialist and team coordinator make the waiting less difficult for the family. Continual updates provide on important link for the family to their family member in the operating room.

Pain Management

The issue of pain control is often the crux of nursing and medical intervention and can become one of the most difficult issues of care if not addressed promptly and efficiently. Many patients present with unremitting pain. It is incumbent on the team to address the patients' needs and prescribe adequate analgesia. This may often include the use of a pain management consultant to supplement the team's care. High doses of morphine and morphine derivatives are used along with such medications as amitriptyline (Elavil) or carbamazepine (Tegretol) to address the neuropathic pain of cancer nerve invasion. Fentanyl (Duragesic) patches are used for basal rate drug administration, and concentrated morphine sulfate (Roxinol) for breakthrough pain, if required. MS Contin, a sustained-release morphine, is another medication that can be used if the patient is able to take oral fluids and foods. This extended-release medication can produce a steady-state drug level. Given two, three, or four times a day, MS Contin can give patients consistent relief from pain. Extensive teaching and continual reevaluation are the hallmarks of pain management. Pain is what the patient says it is, and the care team should be able to respond to the needs with medication and with ongoing assessment of physical and psychological symptoms.

When patients have been on high doses of pain management before surgery, it is imperative that the anesthesiologist be aware of what dose and administration schedule the person requires. This is critical to balance anesthesia and to address basal rates of pain medication after surgery to prevent drug withdrawal, as well as the postoperative pain requirements.

After discharge, if acute pain that cannot be related to the surgical procedure continues for long periods, and the requirements for medication escalate, the possibility of infection or recurrent tumor must be entertained. This then introduces the possibility of recurrent cancer, another surgery, or, even worse, the possibility of unresectable disease. If the disease is unresectable, team intervention at this time directs the patient and family to hospice and supportive care.

Understanding, planning, and documenting the effectiveness of pain management is a critical issue for the nurse to address. As the patient transitions from hospitaJ to home, there must be good communication between in-hospital staff and clinic staff regarding pain relief measures. Assistance from the pain management team is invaluable for the patient and family. The Agency for Health Care Policy and Research guidelines on pain management, published in 1994, is a helpful document that should be included in all care plans and standards of therapy regarding the management of both acute and chronic pain (4).

Nutrition

Nutritional evaluation by a registered dietitian early on in the preoperative process accomplishes three goals in the care of the patient: (a) it establishes a current health status; (b) it establishes a plan of care throughout the hospitalization; and (c) it allows for early nutritional intervention, if required, to begin to correct defined problems. Initial evaluation begins with weight and height and the calculation of the body mass index (BMI). The equation for BMI is weight (in kilograms) divided by height (in meters) squared (kg/m^2). A healthy index is 18 to 25 (3). A BMI of 27 or greater carries nearly three times the risk of pulmonary complications. The patient is also assessed for other risk factors, in these cases a skull base tumor, as well as other comorbid conditions (e.g.., obesity, diabetes, cardiovascular diseases, gastrointestinal disturbances, osteoarthritis). The net weight gain or loss over the last year should be assessed as well as current weight versus usual weight. Significant changes in weight alert the clinician to an overall change in the patient's nutritional health status. Because of the length of skull base surgical procedures, patients who are severely underweight are at risk for pressure sore-ulcer development. Many pressure ulcers that may begin during surgery do not actually appear until 1 to 4 days after an operation (5). Early intervention and alleviation of pressure areas during the surgery may prevent such complications (6).

When data collection is complete, a nutritional treatment plan is individualized and therapy begun. Nutritional support must supply essential nutrients for growth, wound repair, immune competence, and organ function. In the absence of adequate nutrition support, protein catabolism and malnutrition can decrease organ mass and impair the function of major organ and body systems such as skeletal and respiratory muscles, liver, kidneys, heart, gastrointestinal tract, endocrine system, and immune system. Malnutrition is directly associated with morbidity and mortality (7).

Usual levels of caloric replenishment should range around 35 kcal/kg/day. The choice of enteral feeding, if necessary, is based on the nutritionist's experience with formula and the patient's response to the individual formula chosen. Patients with malnutrition and severe stress benefit most from early nutritional support (7). There are many good formulas that meet and exceed American Dietetic Association requirements. Some feedings have high caloric density, with and without fiber, and all have varying levels of osmolality. Repletion should be begun slowly to prevent refeeding syndrome in the severely malnourished. The patient's tolerance determines caloric and osmolality advancement. The choice of continuous versus bolus feeding again is determined by tolerance. Enteral feeding by bolus is usually better tolerated by outpatients, who tend to be more active. Immediately after surgery, continuous feeding is initially better tolerated, with a switch to bolus as the patient recovers. Bolus feeding can be administered in a standard three-meal and snack fashion, mimicking normal eating habits. As an example, a normal-weight woman of average nutritional requirements might tolerate 360 ml of Osmolite HN every 6 hours with 50 ml of free water flushes. A man may require more volume, such as Sustacal HC or Ensure Plus at seven cans per day, two cans at breakfast, two cans at lunch, two cans at dinner, and one can in the evening with 50- to 100-ml free water flushes after each "meal." Administer extra water if the patient's insensible water loss is significant, as with artificial airways or large amounts of oral suctioning. Free water replacement is approximately 27 to 32 ml/kg body weight; 22 ml/kg is a minimum. A general rule is 1 ml of water replaced for each 1 ml of formula delivered. This is predicated on the caloric density and osmolality of the formula and the patient's requirements and general health status. Consultation with a clinical dietitian familiar with repletion ensures that the patient's needs are being addressed properly. All patients should be on aspiration precautions and a reflux regimen. Nasogastric placement must be accurate.

Skull base patients often have significant cranial nerve deficits, some because of tumor invasion and some because of the surgical resection. Before surgery, if any swallowing dysfunction is identified, measures should be instituted to ensure safe nutrition by the oral or enteral route. After surgery, a complete swallowing evaluation is initiated to ensure that oral nutrition is safe. If the patient shows *any* signs of aspiration or inability to meet nutritional goals, enteral nutrition is begun. Early identification of nutritional problems leads to earlier intervention and an improved chance at increasing body levels of protein and albumin. It is not efficacious to push oral nutrition and further stress the patient if there is any indication of swallow dysfunction-or vocal fold dysfunction. Identification of the cause of aspiration and prevention of an aspiration pneumonia are imperative. Swallow therapy is begun as soon as the patient can follow directions and after a dynamic swallow study, so that a safe rehabilitation program can be exactly defined. As the patient improves, safe oral nutrition can be combined with enteral nutrition, and then a weaning process from the enteral nutrition is begun. The patient should be on calorie counts, have nutritional counseling, and be under observation for aspiration pneumonia.

A swallowing rehabilitation program may include such tasks as chin tuck, head turning, gravity assist, breath holding, and double swallowing. These measures must be defined by a radiographic study to ensure success in oral nutrition.

Social Service and Psychiatry

Social service intervention in the preoperative period adds an important psychosocial dimension to the total patient evaluation. Before surgery, the social service representative completes a full family and patient evaluation. Social service addresses issues of coping, adaptation, and family support, provides for the support of patients and families, and helps improve their ability to manage the illness. Discussions may include such topics as feasibility of the surgery and predicting outcomes related to quality-of-life issues and length of hospitalization (8). Details of insurance and finance can be openly discussed at this time. The patient's alcohol and drug history often are more clearly reported to the nurse and social worker than the physician. The complement of social service and nursing evaluation adds to the multidimensional care of the patient and family.

Social service intervention also aids the nursing staff in dealing with the issues of disfigurement and adaptation in skull base patients. Frequent nursing staff debriefings are very helpful in assisting the staff to be both compassionate and objective, and at the same time deal with their own human feelings toward their patients. Social service has been of invaluable assistance to the skull base team in addressing both staff and patient needs.

If, after social service evaluation, it is deemed necessary to obtain a formal psychiatric evaluation, the social worker then collaborates with psychiatry. Psychiatry is of assistance in medication administration, dealing with loss, and true psychiatric diagnosis. The psychiatric department has become an adjunct to the skull base team in difficult patients and family situations.

INTRAOPERATIVE NURSING CARE

PERIOPERATIVE NURSING CONSIDERATIONS

Preoperative Assessment *The Planning Stage*

Clinic

Seeing the patient in the clinic or on admission to the hospital the night before surgery allows the operating room (OR) nurse to begin the preoperative teaching, answer questions the patient may have forgotten or was afraid to ask the surgeon about the operative procedure, meet the family, and assess any special needs the patient may have. This is an opportunity for the patient to express any fears he or she may have about the pending operation and affords the nurse the opportunity to reassure the patient and incorporate this information into the intraoperative plan. Seeing and interviewing the patient also provides information concerning any special physical needs of the patient which may be important when considering positioning and padding intraoperatively. It also gives the patient and family a sense that the patient will be received in the OR by someone familiar to them; someone who knows something about them instead of a stranger wearing a shower cap and a mask.

Skull Base Conference

During skull base conference, the treatment options are discussed, x-rays and scans are viewed, and the surgical plan is outlined and discussed. These sessions are attended by the head and neck surgeon, the neurosurgeon, the radiologist, the pathologist, the plastic surgeon, the fellows and residents, the skull base coordinator, and the OR nurse. It is essential for the OR nurse to be part of this process. The hallmark of OR nursing is the ability to anticipate the needs of both the surgeons and the patient accurately. In order to do so, it is necessary to understand the entire operative plan. Important information to be gained is the location of the tumor, insight into the pathology of the tumor (and any special requests of the pathologist), the surgical approach (anterior vs. middle fossa or posterior fossa), any reconstruction plans (grafts or flaps), and any necessary implants. It is also important to know how many teams will be involved and whether or not they plan to work simultaneously. The OR nurse can communicate this information to the rest of the OR team in order to adjust personnel and equipment accordingly.

Intraoperative Assessment

Equipment

Understanding the plan makes gathering the necessary equipment in advance much easier. The following items are fairly standard equipment for skull base surgery:

1. Bo vie machines X 2 (in case more than one team operates simultaneously).
2. Irrigating bipolar machine (for neurosurgery). Regular bipolar machine [for plastic surgery and ear, nose, and throat (ENT)].
3. Suction canisters (sufficient for 2 teams).
4. Suction regulators X 2 for neurology.
5. Rolling, padded stools for seating (during microscopic work or drilling of temporal bone).
6. Mayfield headrest(pins or horseshoe).
7. Suture carts for all appropriate services (i.e., plastic surgery, neurosurgery, ENT).
8. Microscope and TV monitor.
9. Eggcrate mattress, pillows, elbow and heel pads, bean bag and any other necessary positioning supplies.
10. K thermia machine and blanket.
11. Appropriate OR tables to accommodate ENT and neurosurgery instrument sets and drills as well as extra tables for free flap and skin grafts as necessary.
12. Sequential compression stockings.
13. Nitrogen tanks and hoses for power equipment (there should be at least 2 separate supplies).
14. Electric shaver and multiple razors.

Intraoperative Planning

Another reason it is important to know the plan is to enable the OR nurse to gather and open the proper drapes and instruments in advance. There are many variations and possibilities and it is best to be as prepared as possible. Some considerations for the nurses are as follows:

1. What approach have the surgeons decided upon? The three most common are the anterior cranial fossa, middle cranial fossa, and posterior fossa approaches.

2. If the anterior cranial fossa approach is elected, will the surgeons need endoscopic equipment in conjunction with the standard open equipment? If so, the telescope will require sterilization by means of the steris method or a process other than a quick soak in Cidex. Using a sterile scope rather than one that has merely been decontaminated minimizes the contamination hazards associated with communication of the instrument with cerebrospinal fluid (CSF), the dura, or the brain.

3. If the middle cranial fossa approach is elected, will the surgeon need to drill the temporal bone or work on the inner ear or ear canal? Will plates and screws be required to replace bone flaps or to replace the zygoma, if it must be removed for exposure?

4. If the posterior fossa approach is elected, will the patient need to be placed in the lateral position ? Is the pin headrest necessary instead of the horseshoe?

5. What about reconstruction? Will a free flap be required or will a local flap be sufficient? If a free flap is required, from what area will it be harvested? There are multiple possibilities, including a rectus free flap from the abdomen, a forearm free flap, a latissimus free flap, or a fibula free flap if soft tissue and bone are needed. Hip grafts are also possible as are a number of other free flaps. This information is critical not only for draping, but also for prepping, positioning and instrumentation needs. Another question when reconstruction is necessary is whether it will be necessary to re-prep and re-drape as opposed to prepping and draping everything at the outset. If it is necessary to re-drape and re-prep and possibly reposition, how will this be accomplished without compromising the sterility of the surgical wound and the sterile field? If these issues are not addressed and resolved in advance, then confusion, undue consumption of time, energy, and resources will result and patient care will be compromised.

6. Another question to consider regarding reconstruction is, will a saphenous vein graft be required? If the tumor involves the carotid artery, either extracranially or intracra-nially, the carotid may have to be bypassed. If so, it is important to know who will be harvesting the vein and to have a separate sterile setup for the harvest.

7. What about implants? Will it be necessary to patch or replace the dura? Will the jaw require reconstruction? Will bone in the skull need to be replaced or reinforced? Will the patient need a gold weight for their eye if there is facial nerve involvement? There are many options to consider and it is important for the nurse to anticipate and discuss the possibilities with the surgeons, and ensure that the necessary equipment is available, especially since, more often than not, such items are required late in the evening or at night when the usual resources are not available.

Sterile Supplies find Instrumentation

Basic Pack. This pack should contain basins, suction tubing, lap tapes, 4 X 8 sponges, needle magnet, trash bag and pitcher.

продолжение

Neuro Pack or Equivalent. This pack should contain extra suction tubing, an irrigation pouch, cottonoids, bone wax, surgicel, bulb irrigators X 2, a neuro split sheet, bipolar cord, and bipolar forceps. These items can be combined in a custom pack or opened individually.

Extra Basic Packs. The number of extra basic packs required depends upon which procedures are planned. An extra pack will be needed for the free flap donor portion of the case if a free flap is planned. An extra pack will be needed if a saphenous vein needs to be harvested. Because the primary surgical procedure may involve the sinuses or oral cavity, it is important to be mindful of clean contaminated setups versus sterile setups. Also, because tumor is present in the primary surgical site, it is important to keep the primary setup separate from all donor or harvest setups to prevent possible tumor contamination of an otherwise healthy tissue site. Extra bovie pencils, suction tubings, irrigation tubing, and sponges should be opened accordingly.

Instrumentation. Standard instrumentation for skull base cases should include an instrument tray that contains a combination of basic ENT elevators, sinus instruments, facial fracture instruments, and neuro craniotomy instruments. Neuro micro instrument sets should be part of a standard setup and a drill (i.e., Midas Rex) that includes burrs, saws and drill bits, to perform multiple functions. Other instrument trays may be required depending on which procedures are planned. A second set of power equipment may be needed if bone is to be harvested (such as in fibula free flap), and a dermatome may be needed for skin grafting. A basic plastic set will be required as well as plastic micro instrumentation if a free flap is anticipated. Vascular clamps should be available if they are not included as part of the standard set. Also, depending on the approach, ear instruments may be required.

Positioning

Positioning depends upon which approach is planned and what kind of reconstruction is anticipated. The standard and most common position will be supine on a mayfield horseshoe headrest. The following issues should be considered:

1. If the mayfield horseshoe headrest is utilized, it is imperative that it either be equipped with gel pads or that the circulating nurse double pad the horseshoe with eggcrate and webril or some other material that provides adequate cushioning for the patient's head. Many of these cases can last 18 to 24 hours, so adequate padding is essential. Also, if the patient's head must be turned intraoperatively for long periods of time, it is important to be sure that undue pressure is not placed upon the ear on the opposite side, causing tissue compromise.

продолжение

2. The OR table should be arranged so that the surgeons may be seated as necessary with room to accommodate their knees. This may require turning the bed around and putting the head where the feet are ordinarily positioned; it depends upon the individual bed types in each institution. The microscope will be in use at some point and the surgeons may need to be seated. An eggcrate mattress or gel mattress pads should be used to add extra support and padding. A K ther-mia blanket should be placed on top of this padding to provide an important source of heat for the patient, since much of the patient's body may be prepped. Sheets can then be placed over the K thermia making certain that the draw sheet has plenty of length on both sides as both arms are frequently tucked.

3. The arms and heels require extra padding with eggcrate-like material. If the arms are tucked, be sure to pad them well, especially protecting the ulnar nerve near the elbow. Also, be sure that IV connectors, tubing, and blood pressure cuff tubing are not lying against the skin. These items may require padding with small pieces of foam or gauze. The arms can then be tucked by using the draw sheet and placing protective sleds over the tucked arms and secured under the mattress, not under the patient. It is also important to place a pillow under the knees to relieve pressure to the lower back. Be sure to pad the heels well. .

Prepping

It is important to be aware of all the reconstruction possibilities prior to prepping. If all the preps can be done initially, it saves money and time in terms of draping and effort. This also avoids possible wound contamination when re-prepping and re-draping. However, sometimes this is not practical. The preps should be discussed with the surgeons (all services) in order to formulate a final plan. Prior to initiating the prep, the heat in the room is increased and the K thermia machine is activated to warm the patient. If large areas are to be prepped, the patient can lose heat rapidly, making it difficult to compensate for heat loss later. The prep sets should also be warmed slightly in order to remove the chill. This can be accomplished by placing the prep sets in the warmer before the patient is brought into the room. Before beginning the preps, it is important for the circulating nurse to have adequate assistance in the event there are multiple preps, and to be sure that the scrub nurse is ready for draping with all of the appropriate supplies.

Draping

Draping can be an enormous challenge, depending upon the number of surgical procedures to be performed. Again, it is important to stress the necessity for teamwork in discussing the draping plan. All team members should be aware of the plan to facilitate a unified approach. Basic draping begins with the use of a small sheet folded in half with two towels over it. These*Sre placed under the patient's head and over the mayfield horseshoe. (If pins are utilized, this step is eliminated.) One of the towels is then brought up over the patient's head, turban style, and fastened with a towel clip. If the entire head must remain exposed, the turban is eliminated. All areas of the body that have been prepped are then squared off with sterile towels and either stapled or sewn to the patient to prevent gaps in the towels which would compromise sterility. A large reinforced split sheet is then placed over the entire body with the tails of the split fastened around the patient's head. A suction tubing is attached to the irrigation pouch and the pouch is attached to the drapes at the head after which the suction tubing is passed to the circulator who then connects it to a suction canister. If any extremity, such as an arm or a leg, is prepped, an impervious stockinette is used to drape the extremity and sterile sheets are placed beneath it. Thereafter, holes can be cut in the large split sheet to expose other areas such as the abdomen, the thigh, or the chest, which have been prepped and squared off with towels. This allows these areas to be available and sterile, while remaining covered and protected until it is necessary to expose them. It is important to remember to achieve adequate coverage while remaining able to expose all areas that are prepped without compromising sterility. This can be difficult when areas need to be covered for the initial part of the case and uncovered later when another team begins to operate. It is a judgment call whether it is easier and safer to drape everything initially or in stages. This will be decided as a team.

Sequence of Events

Arrival of the OR Team

The scrub and circulating nurse begin the case by entering the OR suite and assessing the need for equipment and supplies. If possible, it is wise to leave a list on the preceding day of all necessary items to be placed in the OR so that when the team arrives in the morning they can begin setting up immediately. Because these cases can be very lengthy, good early preparation ensures an efficient and timely start and incision time.

Once the team has checked the OR suite and determined what equipment and supplies are still required, it is important to elevate the heat in the room to 80°. This is important not only for the initial comfort of the patient upon entry into the OR suite but also to prevent hypothermia during the intraoperative phase. Hypothermia can cause changes in the behavior of anesthetic agents and can delay metabolism, thereby impeding a patient's emergence from anesthesia. As many areas of the body may be exposed during prepping and line placement, it is important from the outset to help regulate the patient's temperature throughout the entire perioperative phase. Raising the temperature in the room, using a warming blanket beneath the patient, and placing warm blankets over the patient until prepping begins will help to accomplish this. At this point, the remaining equipment and supplies can be gathered and placed in the OR suite and the circulator and scrub person can prepare to open sterile supplies.

The circulator can now prepare the OR table for the patient while the scrub person is opening the sterile packages and instrument trays. The OR table should be well padded with an eggcrate mattress over the table pads unless gel table pads are used as standard equipment. A K thermia blanket should then be placed over the eggcrate mattress or gel pads. Thereafter, a sheet is placed over the warming blanket and a second sheet is placed as a draw sheet, being careful to leave the sides of the draw sheet with plenty of length as this sheet will assist in tucking and securing the patient's arms. (See positioning, above.) This is a good time to pad the mayfield headrest with a foam donut if the headrest is not equipped with gel pads on the frame. The warming blanket should be turned on to warm the sheets and the prep sets can be placed in the warmer. If the surgeons will be seated for any part of the case, it is important to be sure they will have adequate room to place their knees under the OR table. In order to accommodate their legs, the OR table may need to be adjusted placing the headpiece at the foot of the table, making it the head of the table, eliminating obstructions underneath where the patient's upper body will be. Depending upon the type of OR tables available in each institution, this may or may not be necessary. The important thing to remember is to facilitate the smooth and orderly progress of the case without compromising the safety and comfort of the patient. If the bed must be adjusted, be sure that padding is sufficient and that the lumbar spine region has adequate support. In our institution, a board is placed under the OR table pads, within the gap in the frame that is created when the bed is turned. This board is then padded with foam to make it the same height and thickness under the pad as the rest of the frame.

Greeting the Patient

Once the above steps have been accomplished, the circulating nurse can visit the patient in the preoperating room and begin the process of checking the patient's chart. Usually, by this time the anesthesia personnel have arrived and have begun to check over the anesthesia equipment and to prepare the medications and lines to begin the case. This is a good opportunity for the circulating nurse to have a few minutes alone with the patient and family.

One of the advantages of attending the skull base conferences is that the patient's history is familiar to the circulating nurse. This leaves more time to spend reassuring the patient and answering any last minute questions the patient or family may have. The circulator should introduce him or herself to the patient at this time, even if they may have met previously, because people appear unfamiliar when dressed in green scrub clothes and a hat. After the introduction, the nurse checks the patient's identification band for the correct spelling of the patient's name, the medical record number, and the patient's date of birth. This is a very important step as this information must be consistent with the medical records and the blood bank order sheets.

Once patient identification is completed, the nurse can review the preoperative checklist to obtain all the necessary information. The nurse must ensure that the patient has had nothing to eat or drink after midnight the night before, unless there is a physician's order allowing the patient to take the medications they usually take at home (i.e., antihypertensive or cardiac medications) with a small sip of water. Any allergies to medications will be noted, and if preoperative antibiotics are ordered but have not yet been given, the nurse can alert the preoperating room staff to administer them. The operative consent is checked to be sure the patient has consented to all of the procedures that are planned. At this time, the nurse can ask the patient which surgical procedures will be performed to allow the patient to state the procedures in their own words. This assists in identifying any misconceptions or misunderstandings the patient may have. Once the consent is verified, the nurse examines the chart for the informed consent note from the surgeon stating that all the risks and benefits of surgery have been explained and the patient wishes to proceed. Next, the lab work is checked and any abnormal or questionable values are noted and discussed with anesthesia and the surgeons. Routine lab work includes a complete blood count (CBC), Chem 20, prothrombin time (PT), partial prothrombin time (PTT), and urinalysis. Availability of blood and blood products is also checked at this time. Other lab work may have been ordered as well, depending upon other medical conditions the patient may have. It is important at this time to check on x-rays, CT scans, and MRI scans, not only for a report in the chart, but also to ensure the availability of the films in the OR suite. After the check-in process has been completed, the nurse explains to any family members who are present the location of the waiting room and lets them know that the skull base coordinator will check on them every few hours and provide them with updates on the progress of the surgical procedures and the condition of the patient. This helps alleviate much of the anxiety the family members are experiencing.

Setting Up the Case

The circulating nurse can now return to the OR suite to assist the scrub person in opening any remaining sterile supplies. Once this is accomplished, the scrub nurse can perform the surgical scrub at the scrub sink and the circulator can assist the scrub nurse in gowning. The circulator can then open any remaining sterile supplies that required sterile personnel receive, such as items too large or packaged in such a way that delivery to the sterile surgical field requires assistance.

While the scrub nurse is setting up and arranging the sterile field, the circulating nurse prepares the paperwork for pathology and frozen sections.

Once the scrub nurse has cleared an area on the sterile field for sterile cups (which are diligently labeled by the scrub nurse), the circulating nurse can deliver the medications to the sterile field. Most commonly, the medications are thrombin, gelfoam, xylocaine with epinephrine, methylene blue, bacitracin, and surgicel.

If there is time before the patient arrives and the scrub nurse is ready, a count can be performed at this time. Otherwise, the count can be performed later while lines are being placed—provided the count is completed before any incision is made. Items to be counted are laps, raytecs (4 X 8s), needles, cottonoids, and dura hooks, at minimum. Instruments are not usually counted.

The Arrival of the Patient

By now anesthesia personnel have interviewed the patient, prepared their equipment, and are ready to bring the patient into the OR suite. The circulating nurse assists in transferring the patient to the OR bed, places a pillow under the patient's knees, and places a warm blanket over the patient. The safety strap is secured over the patient's thighs just above the knees, the arm boards are connected to the OR bed, and the patient's arms are placed comfortably at the patient's side. The nurse then assists the anesthesia provider in placing the blood pressure cuff, electrocardiogram (EKG) leads, and pulse oximeter on the patient for monitoring purposes.

NOTE: KEEP IN MIND THAT THE FOLLOWING STEPS MAY OCCUR IN SEQUENCE, SIMULTANEOUSLY, OR IN A DIFFERENT ORDER. THE IMPORTANT THING IS THAT EVERYONE WORKS AS A TEAM SO THAT THE CASE FLOWS WITHOUT INTERRUPTION AND THERE ARE NO UNNECESSARY DELAYS.

Induction of the patient can now begin. The circulator stands by the bedside and is immediately available to assist by administering cricoid pressure if necessary or by helping to secure the endotracheal tube once it is placed. The nurse will also provide emotional support to the patient as the anesthetics are being administered, by reassuring the patient and touching the patient's arm or holding a hand. This is a simple but very important role for the circulating nurse because the patient is probably most anxious at this time. It is important that the surgeon be present at the time of induction in case there are any difficulties in maintaining the patient's airway. The scrub nurse will also be standing by and will be prepared to assist in performing an emergency tracheostomy on the rare occasion that it is needed.

Once the anesthesia provider is satisfied with the tube placement and has appropriately secured the endotracheal tube, the bed can be rotated 180° so the head of the bed is where the foot of the bed was and the foot of the bed is in front of the anesthesia provider. This is done to give the surgeons access to the entire patient. The anesthesia provider will have extensions on the breathing circuit and also on all of the intravenous (IV) tubing. It is much easier to turn the bed before all the lines have been placed so that there is less likelihood of tangling lines. If possible, it is easiest to disconnect the EKG leads, blood pressure cuff, and pulse oximeter very briefly until the turn is made. They can be replaced immediately once the turn is complete.

The anesthesia provider can now begin to place the intraoperative lines. An arterial line, two large bore IV lines and a peripherally inserted catheter (PIC) line or long arm central venous pressure (CVP) line are placed. Communication between all the members of the team is important so that the anesthesia provider understands which areas of the body are to be prepped into the sterile field. This information will determine where the lines are to be placed.

While the anesthesia provider is placing the lines, the surgeon is injecting the neck at the site where the tracheostomy is to be performed with 1 % xylocaine with epinephrine 1: 100,000 as local infiltration to reduce intraoperative bleeding at the site. At this time, the circulating nurse and scrub nurse can complete the operative count if this has not already been done. The scrub nurse will have a separate setup for the tracheostomy and will also have a primary back table with ENT supplies and another table with neurological supplies, and perhaps, later in the intraoperative phase, there will be other setups made available for free flap or saphenous vein harvesting. Although many of these procedures and setups may begin as separate entities, the count is done as one procedure with additional counted items being added as the case progresses. This is much easier during the closing counts as everything will eventually be combined. Several closing counts may be necessary depending upon how many procedures are performed.

The temperature foley is placed and TED stockings and pneumatic sleeves are placed if the legs are not to be prepped into the sterile field. If the thighs are to be prepped into the field for skin grafting or saphenous vein harvesting, the pneumatic sleeves and TED stockings can be placed on the lower legs up to the knees. If the anesthesia provider has completed line placement, the arms are padded and tucked as described earlier in the section on positioning. If line placement has not been completed, the arm boards are lowered so anesthesia personnel can continue placing lines while the circulating nurse begins the prep for the tracheostomy.

The grounding pad is placed on whichever thigh will not be prepped into the sterile field. If both thighs are to be prepped, the grounding pad is placed on the buttocks. If more than one bovie will be needed, an additional grounding pad will be placed on the other buttock. The position of the grounding pads will have to be reevaluated after placement of the lumbar drain as the patient will be turned to a lateral position for drain placement and then back to supine and the grounding pads may become dislodged and require replacement.

Intraoperative Procedure

The circulating nurse removes a prep tray from the warmer and preps the patient's neck for tracheostomy while the surgeons are performing the surgical hand scrub. Once the prep is completed and the surgeons are gowned and gloved by the scrub nurse, the patient is draped for tracheostomy. Four towels are placed around the neck in a squared fashion leaving the anterior neck available for incision. Towel clips are used to secure the towels and a large split or U sheet is placed over the patient with the tails of the sheet forming around the patient's head. The scrub nurse then hands the cautery cord and suction tubing to the circulator who connects them to the appropriate equipment. The tracheostomy is performed as a separate procedure from the main portion of the case. An anode tube is placed in the tracheal stoma and sewn to the patient's chest with an O-silk suture to prevent the tube from being dislodged during the remaining portions of the case. Before the patient is transferred **to** the postanesthesia recovery room (PAR), the anode tube **is** replaced with a tracheostomy tube.

When the surgeons place the anode tube in the trachea, the circulating nurse summons the neurosurgeon to place the lumbar drain. The neurosurgeon will then be arriving while the tracheostomy is being completed, thereby eliminating any delays in the case. If neurosurgeon is unavailable or delayed, the anesthesia provider can place the lumbar drain.

A sterile towel is placed over the site of the tracheostomy and kept in place to keep the tracheostomy site as clean as possible until the final prep. The scrub nurse and circulating nurse perform a sponge and needle count once the tracheostomy is completed. The sponges are arranged in a sponge counting bag and remain in the OR suite as they are part of the entire count. The needles are placed in a needle magnet and saved for the same reason. These items may be counted and removed from the OR suite and a separate count can be performed for the remaining operative procedure if everyone agrees to do it that way. The problem with counting in this manner is that when the initial team of nurses has gone home, questions may arise and confusion may result if there is an incorrect count. We have found it more efficient to keep everything together so there is no question about which procedures were included in the count and which were not. This approach has worked well for us. The drapes are then removed and the team prepares for insertion of the lumbar drain.

The patient is then placed in the lateral position with pillows between the knees. The knees and head are bent toward the chest to flex the lumbar spine to facilitate placing the lumbar drain. The scrub nurse changes gown and gloves and prepares a small sterile setup for the lumbar drain placement. This includes a bayonet forcep, scissors, a needle holder, and a sponge forcep. Two small bowls are placed on this table, one containing sterile saline and the other containing beta-dine solution. A package of 4 X 4s or fluffs, O-silk, strands, and a 3-0 nylon suture are placed, as well as the lumbar drain and external drainage kit. The neurosurgeon gently washes the patient's back with the betadine solution and places the lumbar drain in the lumbar space using sterile technique. The drain is then connected to the external drainage kit fastened with an O-silk strand and handed to the anesthesia provider. The anesthesia provider checks to ensure that the drain is closed, and then fastens the drainage bag to an IV pole where it is readily accessible when and if the neurosurgeon asks the anesthesia provider to open the drain and drain CSF into the bag during the neurosurgical portion of the procedure. The surgeon then sews the drain to the patient's skin with 3-0 nylon suture and places an op site over the insertion site. The drain is then loosely coiled and taped to the patient's back. After the drain is placed, the patient is returned to the supine position with a pillow placed under the knees. It is important for the circulating nurse to remain with the patient during this procedure to ensure proper positioning and protect the patient from falling. It is also important to keep the patient covered as much as possible with warm blankets.

Once the lumbar drain has been placed and the patient is returned to the supine position, the circulating nurse can reevaluate the position of the grounding pads and replace them if necessary. The circulating nurse and the surgeons can then begin shaving the head and any other portion of the body that will be included in the sterile field, such as the legs or the abdomen. Also, at this time another surgeon can be placing frost stitches in the eyelids. This is done with a 4-0 silk suture on a small G-3 needle using a 10 french robinson catheter as a bumper to sew the eyelids together. This protects the corneas from abrasion and irritation during the long hours to follow. The eyelids are lightly prepped first with betadine solution being very careful not to allow any betadine inside the eyes. Betadine swabs work very well for this. If any betadine does enter the eyes it can be rinsed out immediately with balanced salt solution. The needle holder and suture scissors used for the frost stitches are sterile and provided by the scrub nurse. The surgeon uses sterile gloves while inserting the frost stitches.

The Mayfield headrest is now fastened to the OR table and the patient's head is placed on the headrest. If the patient's head is to be turned to the side for the majority of the case, care is taken to be sure undue pressure is not placed on the downward ear. The Mayfield horseshoe is well-padded as described earlier and is adjusted so that the patient's head fits comfortably with no areas of pressure. Positioning is completed as described earlier in the section on positioning and the circulating nurse removes the remaining prep sets from the warmer and begins to prep all the appropriate anatomy for the procedures to follow.

The surgeons return to the scrub sink for the final surgical scrub. Meanwhile, the scrub nurse has been busily setting up the rest of the surgical field. The scrub nurse separates items for a skin graft onto a small prep table and covers the table to protect it from contamination until the supplies are needed. The gelfoam is cut into pieces and added to the thrombin. Surgicel is cut into strips, labeled, and placed in a towel for easy access. Before the circulating nurse dons gloves for the prepping, the scrub nurse asks for any other needed supplies such as extra gloves or gowns for the surgeons who are scrubbing.

Once the surgeons are gowned and gloved, the draping begins. As described earlier, draping can be a challenge. Everyone must work as a team. The circulator remains available to assist with the draping and to ensure that strict aseptic technique is followed and adequate coverage is obtained with no breaks in sterile technique. Drapes around the head and neck are secured with staples and 2-0 silk sutures. This allows the head to be turned repeatedly without creating gaps in the sterile drapes. A fluid pouch is used at the head to catch blood and irrigation fluid and this is connected to suction. The remaining drapes are stapled and the prepped areas of the body that will not be operated on immediately are covered with a sterile towel for both warmth and protection. The circulator connects the bovie, bipolar, and suction and the bipolar pedal is covered and placed in close proximity to the primary surgeon. The circulator assesses the OR field to be sure everything is in place and in working order before beginning documentation and charges.

Once the procedure is underway, it is the responsibility of the scrub nurse to anticipate the needs of the surgical team for instrumentation and suture and to communicate with the circulating nurse when supplies will be needed that are not already part of the sterile setup. The scrub nurse and circulating nurse work together in anticipating when it is time to connect the power equipment, drape the microscope, or set up another sterile field for a reconstruction procedure or harvesting of tissue. The circulator may have to communicate to the nurse in charge of coordinating the staff the need for a second scrub nurse if another team of surgeons wishes to work simultaneously.

The circulating nurse is the primary coordinator of all that happens in the OR suite. He or she is the facilitator and the link between all the surgical teams and anesthesia providers. The circulating nurse is the patient advocate, assisting the entire team in providing safe and optimum care to the skull base patients, as well as being the link between other departments and the surgical suite, such as pathology, blood bank, and x-ray. It is crucial for the circulator to be aware of all the aspects of the case in order to anticipate the needs of the scrub nurse, surgeons, and anesthesia provider. This requires being aware of blood loss and communicating with anesthesia personnel by displaying the sponges where they can easily be seen and placing the suction canisters within direct vision of the anesthesia provider. The circulator also assists the surgeons in the placement of foot pedals, sitting stools, microscopes, headlights, and other equipment. He or she also will answer pagers, screen information and calls that can be handled by personnel outside of the operating room. It is also necessary to anticipate the needs of the scrub nurse for extra suture, sponges, irrigation fluid or medications.

One of the most critical roles of the circulating nurse is the responsibility of recording, collecting, and labelling the tissue specimens for frozen section and sending them to pathology in a timely fashion. Good communication between the surgeons, the scrub nurse, and the circulator is imperative. There can be as many as 100 or more specimens taken during the course of the case. It is therefore very important that everyone work together. The surgeon calls out the name of the specimen clearly to the circulator and the scrub nurse. The scrub nurse collects the specimen in a small sterile container (small paper souffle cups can be used for this). The circulator communicates to the scrub nurse which letter to label the specimen(i.e., A,B,C,D, etc.) The scrub nurse then writes only that letter on the paper cup with the specimen. The circulator writes the letter and the name of the specimen on the pathology sheet, repeating the name of the specimen to the surgeon as it is being written so the surgeon can clarify if the circulator has heard the name incorrectly or is unsure of what the specimen is. The reason the circulator writes the information rather than both the circulator and the scrub nurse is to avoid confusion. If only one person writes the name of the specimen, less opportunity for error is presented. Also, the scrub nurse is very busy collecting the specimens from the surgeons and continuing to hand instruments to the surgical team. It is critical, however, for the circulator and the scrub nurse to be working in complete harmony and to be on the same letter at the same time. If there is any confusion or doubt, it is the responsibility of the circulator to alert the surgeons and stop the case until clarification is obtained.

Accuracy of the frozen sections helps to determine the extent of the tumor whereas inaccuracy may result in major complications. Sometimes many specimens are taken at the same time and sometimes just a few are taken. In either case, the circulator writes the names of all of the specimens on the pathology sheet, labels the specimen containers, and then collects the specimens from the scrub nurse. At no time should a specimen be placed in an unlabeled specimen cup. As the circulator collects the specimen from the scrub nurse, the letter is spoken aloud by both the scrub nurse and the circulator to verify that specimen A is being delivered to the cup labeled specimen A and that B is in specimen cup B and so forth throughout the alphabet. When the letter Z is reached, the specimens are then labeled AA, BB, CC, etc., until ZZ is reached and then AAA, BBB, CCC, etc., until all specimens are collected. As each group of specimens is collected, that group is sent fresh (not in formalin) to pathology accompanied by the patient's chart. As pathology calls to state which specimens are positive and which are negative for tumor, the circulator marks a plus or minus sign in the margin of the appropriate specimen on the pathology sheet thereby creating a list to which reference may be made upon request by the surgeon.

At approximately 4-hour intervals, the circulating nurse will give a report to the skull base coordinator and the clinical nurse specialist on the progress of the surgery. The skull base coordinator can then relay this information to the family. Because these cases can be so lengthy, it is important for the family to receive periodic information so that they feel included, and so they can understand that progress is being made and even though the wait may be long, they will be kept aware of the stages of the operation.

It is very important that during the case, the circulating nurse is careful to keep track of the discarded sponges and to display them so that the anesthesia provider can assess blood loss. Keeping track on a regular basis and displaying the sponges also helps later when closing counts need to be performed. It is much easier to perform a closing count when the sponges have been accounted for periodically, rather than waiting, as it becomes very busy towards the end of the case and more mistakes are made when there is confusion and personnel are hurrying. It is of equal importance for the scrub nurse to pay close attention throughout the case to the location of sponges, needles, and cottonoids as well .as instrumentation. The scrub nurse should be counting privately at frequent intervals and should enlist the help of the circulator and the surgeons if an item cannot be accounted for. This will save a lot of time at the end of the case.

As the case progresses, it *is* important for the circulating nurse to continue to plan and organize for the remainder of the case. Before being relieved by a new team at the end of the shift, the primary circulator should verify and obtain an intensive care unit (ICU) bed, give the PAR a report regarding when they can expect the patient (even if it will be hours later) so they can adjust their staffing, and obtain any other equipment or supplies that may be needed later in the case. The circulating nurse then gives the oncoming team a full and detailed report. Information included in report is as follows:

The patient's history and diagnosis.

All of the planned procedures, including the procedures already performed, procedures pending, and the present status of the case.

Any allergies the patient may have.

Transfusion status. How many units of blood have been transfused, how many units are remaining in the blood bank, and whether or not there are other blood products available such as platelets, fresh frozen plasma or cryoprecipitate for fibrin glue.

What family members are waiting and where they are waiting and what information they have been given to date.

How much irrigation has been used on the field.

The status of the frozen sections and any other specimens.

The location of the grounding pads and which areas of the body have been prepped.

The potential use of special implants and the location of the implants if they are not already present in the OR suite, (i.e., dura substitute, plates and screws, etc.)

Anything unusual about the sponge and needle count. If it is possible a sponge and needle count should be performed by one member of the oncoming shift and a member of the shift that is leaving. Most of the time this is difficult to do since there may be more than one procedure being performed and sponges or cottonoids may be packed in a wound. This is another reason why it is so important for the primary scrub nurse and circulator to be counting on an ongqmg basis during the case.

Once a full report is given, all questions are answered and both teams are comfortable, the circulating nurse checks all the documentation and charges to be sure that everything is up to date.

Closure of the Case

As with the beginning of the case, the end of the case inevitably produces a flurry of activity with many functions being performed simultaneously. The anesthesia provider is busy preparing for the patient's emergence from anesthesia, the circulating nurse and scrub nurse are performing closing counts, and the surgeons are asking for suture and assistance in closing the wounds. At least two closing counts are performed; one count as closure is beginning and the other count as the skin is being closed. If the count is incorrect, the circulating nurse and the scrub nurse make every attempt to locate the missing item or items. The scrub nurse checks the field and enlists the help of the surgeons to check the wound. The circulating nurse checks all the sponge buckets and, if necessary, checks the linen and trash bags to ensure that a sponge or needle was not inadvertently thrown into the wrong container. If the missing item or items are still not located, an x-ray is taken to be sure the item has not been retained in the wound. An incorrect count is less likely if the team has been keeping track and counting throughout the case. However, multiple teams can be involved and this makes the process more difficult.

The circulating nurse must also call a report to the PAR at least 30 minutes before the end of the case. Transfusion status, the location of any drains or packing, allergies, line placement, and the procedures performed are all part of the report, as well as the status of the patient's condition. If a ventilator will be needed to assist the patient's breathing postoperatively, the settings are given to the PAR nurse at this time. It is also important to let the PAR nurse know where the family is waiting. The anesthesia provider will also give report to the PAR nurse regarding fluid replacement, medications and drips, and the anesthetic agents delivered during the procedure. This is usually done upon the patient's arrival to the PAR.

Once the wounds are closed, the counts are completed and the dressings are placed on the surgical sites. The drapes are carefully removed to avoid displacing any drains. A warm blanket is placed over the patient and the OR bed is slowly and carefully returned to its original position with the head of the bed directly in front of the anesthesia provider. This requires careful team work as there are lines, drains, etc., that must be kept in place. If there is adequate help and the anesthesia provider is comfortable with it, the OR bed can stay in the operative position, and emergence from anesthesia can proceed without turning the bed. This, however, requires extra personnel so that the anesthesia provider can be at the patient's head to manage the airway and another provider can be at the anesthesia machine managing the oxygen and the ambu bag.

After the patient has emerged from anesthesia and the tracheostomy tube is connected to the transport oxygen supply, the patient can be transferred onto the ICU bed. The pulse oximeter, arterial line, and EKG leads are connected to a transport monitor and the patient is taken to the PAR accomparried by the circulating nurse, the anesthesia provider, and the surgeon. The ICU bed is utilized rather than a gurney to avoid transferring the patient onto a bed twice. When the patient is transferred from PAR to ICU, they will already be settled in their bed.

On arrival to the PAR, the circulating nurse assists the PAR nurse in transferring the monitoring lines from the transport monitor to the PAR monitor. Oxygen is transferred from the transport tank to the PAR supply or the ventilator, whichever is appropriate. It is important for the OR nurse to stand by and assist when necessary until the patient is settled and an initial set of vital signs is taken. Any additional information necessary for the postoperative care of the patient can be shared at this time and any questions the PAR nurse may have about the procedure can be answered. It may also be necessary to keep the patient warm with a Bair Hugger machine or some other external device to maintain a constant normal temperature. The OR nurse can assist with this as well.

Postoperative Phase

At some point in the postoperative recovery period, the team of OR nurses should pay a visit to the patient. It is very rewarding to see the patient's progress and to discuss the intraoperative course with the nurses who are responsible for the patient's postoperative care. This provides necessary continuity for the patients and can be an excellent mechanism for continued quality improvement.

It is important for the perioperative nurse and the preoperative and postoperative nurses to work together as a team. Each nurse plays an important role in the care of the skull base patient. Each contributes their special expertise and assists in providing a truly collaborative and integrated approach to this very complex group of patients. This is a very challenging and rewarding area of nursing and one that is changing and growing every day.

POSTOPERATIVE NURSING CARE IN THE INTENSIVE CARE UNIT

Postoperative care of the skull base surgery patient is one of the most challenging roles in nursing today. The combination of intensive care expertise in otolaryngology and neurosurgical nursing demands the dedication of a very specialized group of nurses. The designation of one intensive care unit to care for these patients is critical to the consistency and performance of any group of staff. For the patient undergoing skull base surgery, nurses who are specially trained provide the optimal care for a smooth recovery and prevention of complications. Subtle changes often herald later, more significant-problems. Educated nursing staff who work closely with the surgical staff can anticipate problems in such a way that leads to effective and early solutions.

The ICU has standard orders for skull base patients that have been written in concert with the surgical staff. These orders allow for more efficient care and a significant time savings, as well as the standardization of orders that would normally take an exceptional amount of physician time to write. All orders can be individualized for the specific patient's needs, and are driven by the type of surgical procedure and the patient's response. Diagnosis, surgical procedure, and reconstruction are well defined so the nurse has a full understanding of the patient's nursing requirements. The intensive care unit flow sheets are also standardized to provide consistency in documentation in an ICU setting. As with the standard orders, each flow sheet is individualized as necessary to document the specific patient's needs and responses.

Neurologic Monitoring

Foremost in the monitoring of neurologic status is a check on neurologic vital signs every 1/2 to 1 hour in the immediate postoperative period. These signs include cognitive functioning, pupillary response, hand grasps, extremity movement, and reflexes. Cognitive functioning also is assessed by asking the patient to write (if he or she is literate). Alteration in syntax, fluency, or spelling may be indicative of postoperative deficits. The Glasgow Coma Scale is invaluable in objective management. Most patients who have had a dural entry have an epidural drain placed during the operative procedure. This epidural catheter is placed to decompress the brain and allow for careful monitoring of CSF pressure in the ventricular system. Intracranial pressure (ICP) is the pressure that is exerted by the volume of the intracranial components, namely, brain tissue, blood, and CSF. Brain tissue comprises 80%, blood 10%, and CSF 10% of the intracranial volume. According to the Monro-Kellie doctrine, the intracranial components inside the closed compartment of the skull and meninges exert a certain normal pressure, known as ICP. If any one of the components increases, there is an increase in ICP. The danger is the possible destruction of the components by such an increase in pressure (9), ultimately resulting in brain herniation if not treated. Early detection of increasing ICP allows us to react early to such problems by making volume adjustments with the external catheter, to stop bleeding, or to give medications and change ventilation pressures (10).

Nursing care includes elevation of the head of the bed to about 30 degrees. The ventricular drainage system should be kept at the level of the external ear canal, which corresponds internally to the foramen of Monro. Placement at this level equalizes drainage within the ventricular system. Neurologic monitoring includes assessment of level of consciousness, lethargy, unequal pupils, or response to light. Change in sensation to pinprick, abnormal reflex responses, or change in ability to move extremities may signal an immediate problem. Changes in heart rate and respiration may signal neurologic as well as cardiovascular changes. Headache, specifically increasing head pain, should be considered a serious symptom of increasing intracranial pressure, meningitis (chemical or mechanical), or infection.

The epidural catheter is considered sterile because of the increased risk of infectious meningitis with its use. Most skull base patients may have a wound that has traversed the facial structures and the dura, inducing a chemical meningitis from blood in the spinal fluid. Dressing changes are done under sterile conditions, including gown, gloves, and mask. Great care must be taken to avoid inadvertent removal of the drain during dressing changes, changes in the patient's position, and transfer from bed to gurney or chair.

The nurse observes the patient for a CSF leak by inspection of nasal drainage, clear drainage through the incision, any fluctuant area near the incision, salty taste in the mouth, or clear fluid leak from the external ear canal. With anterior cranial fossa resections, CSF leaks may be more obvious after the nasal packing is removed. The *halo test* is a test to ascertain if CSF is part of the fluid that collects at the leaking site. A drop of fluid is placed on a clean cloth or dressing. The serum stays in the center and the CSF creates a halo around the center circle. A CSF leak may respond to a slight increase in ventricular drainage through the epidural catheter to decompress the ventricular system. CSF leaks are treated with additional antibiotic therapy for infection prophylaxis. A leak can be detected by a CT study using metrizamide contrast, and if it does not respond to conservative therapy, surgical closure is required.

Artificial Airway

A tracheostomy decompresses the surgical site from increased pressures that are generated by coughing, sneezing, or similar increases in airway pressures. In addition, it provides a means for assisted ventilation, if necessary, as well as a means of ensuring pulmonary toilet. During skull base surgery, the entry through the cranial vault often breaches the dura, which consequently requires repair. Air in the cranial vault is called pneumocephaly. Such trapped air can compress the brain and cause alteration in the patient's level of consciousness. The upper respiratory tract is in direct contact with the skull base during the surgical procedure, although through advances in reconstruction a tissue barrier is established at the completion of surgery. A tracheostomy can decompress the upper aerodigestive tract and prevent complications. For anterior cranial vault surgeries, the tracheostomy is often left in place until the surgical packing is removed at about day 7 to 10. At that time, the integrity of the repair is evaluated, and if no CSF leaks are found, the tracheostomy can be downsized, capped, and removed. This presupposes that all other routine parameters for weaning and decanulation are met.

Reconstruction: Flaps and Grafts

Cranial base surgery creates large defects, and reconstruction is undertaken at the completion of tumor resection. Pericranium and osseous-myocutaneous flaps are often used to fill the defect. Surgical therapy in general, and specifically craniofacial skeletal surgery, is undergoing a transformation from traditional surgery to surgical tissue engineering. Tissue engineering is a paradigm for surgical therapy that uses computer-aided presurgical planning, cosmetically innovative approach techniques, tissue-integrating biomaterials, and cellular and cytokine therapy to achieve the therapeutic goal. Although adoption of this paradigm is in the early phases, continued progress in molecular medicine and macromedicine will ultimately lead to broad acceptance (11).

The reconstruction flaps commonly used are the pectoralis major myocutaneous, scapular, radial, fibular, and rectus abdominis free flaps, as well as skeletal reconstruction. These flaps require a microvascular anastomosis to an artery and a vein to survive. Nursing care of the patient with such a flap centers on preserving this microvascular reconstruction of blood supply to the flap tissue. Any decrease in blood flow created by low blood pressure or pressure on the anastomotic vessels could place the reconstructed flap vessels, both venous and arterial, in jeopardy. Maintenance of blood flow to the flap, frequent monitoring with Doppler signals, and judicious administration of blood products, albumin, and fluid all maximize blood flow during the early postoperative period. It is critical to check capillary refill with Doppler findings. Flaps often look pale in the first 12 hours after surgery, during the period of general rewarming and gradually improving vascularization of the flap. Capillary refill should be brisk and color must be maintained. Changes should be reported and discussed immediately to ascertain if the flap requires any immediate surgical intervention.

Carotid Resection

Patients who require a carotid resection during skull base surgery are at very high risk of stroke. With the advent of BTO and SPECT scanning, the skull base surgical team is better able to predict the outcomes and make the resection safer for those patients requiring a carotid resection at the time of surgery. The incidence of stroke after carotid resection has dramatically decreased because of improved surgical techniques, better preoperative evaluation, and better patient selection. But the patient is still at risk and strokes can occur, and not necessarily perioperatively.

Nursing care of patients who undergo a carotid resection during skull base surgery is predicated on intense observation, documentation of neurologic signs, and prevention of hypotension. The patient requires rigorous neurologic testing. Obvious motor weakness in extremities is a hallmark sign. Facial nerve paralysis may or may not be indicative of stroke, depending on the surgical approach and the location of the tumor. The facial nerve may have been sacrificed during the procedure. It is incumbent on nursing staff to know the cranial nerves and understand the surgical procedures and which cranial nerves are involved in each of the resections. The more subtle signs and symptoms of aphasia (expressive and receptive) are very difficult to identify in the early postoperative period, but these subtle signs can explain why patients do not "cooperate" with instructions. "Yes" and "no" questions may be simple for the nurse, but give no insight into the cognitive component of the patient's neurologic status. Incorporating the family in discussions may assist in the evaluation; the family knows the patient better than the staff and may be able to detect subtle differences in response or personality.

CASE STUDY

A 56-year-old man underwent radiation therapy for a right tonsilar squamous cell cancer in 1984. He represented in 1995 with a recurrence that encased his right carotid artery and coursed into the skull base along the mandibular branch of the trigeminal nerve, through the foramen ovale. At the surgical resection, it was found that the carotid could be preserved and the tumor fully resected with clear margins. The postoperative course was relatively uneventful, with the exception of major wound breakdown at the surgical site. This poor wound healing was due to the previous radiation therapy to the area, and low serum protein and albumin. Subsequently the carotid artery became exposed in the open wound. After a very long hospitalization, the patient went home with the carotid covered with granulation tissue that appeared pink and healthy. Nursing care in the hospital had included meticulous dressing changes every 4 hours with wet to dry dressings. The patient and his wife had been trained in wound care. The nursing staff had discussed what to do if the carotid were to bleed, and what, if any, intervention should be undertaken. Both the patient and wife were adamant about intervention, and they were educated how to treat a carotid bleed at home. They understood that even with quick action and pressure on the carotid, survival was uncertain.

The patient was home for 18 days. He was readmitted to our hospital after an episode of bright red blood spurting from his neck wound in the area of the carotid artery. Direct pressure over the carotid artery by the patient's wife had controlled the bleeding until he could be transported to the hospital. The patient came in by helicopter from 60 miles away, with his wife maintaining pressure on the carotid artery. On admission examination, the previously healed granulation tissue was clearly disrupted and the carotid was again exposed. The patient and family consented to a carotid resection, without the benefit of BTO and SPECT scanning. The surgery was undertaken immediately.

After surgery, the patient awoke moving ail extremities and appeared alert and responsive, showing no clinical signs of a stroke. He knew the routines and cooperated with care. He was unable to speak because of his tracheostomy. On postoperative days 2 and 3 he was out of bed to a chair, nodding "yes" and "no" to questions. His wife mentioned that she felt he was depressed because he was not writing notes as he had before. A more thorough evaluation elucidated that he was not writing because he was unable. He had suffered a stroke that rendered him aphasic in both writing and speech. There appeared to be no motor function deficits. He was able to complete usual hospital routines because he was aware of and remembered his last hospitalization. His speech could be fully tested only later because of the tracheostomy in the early postoperative period. During surgery or in the immediate postoperative period, the patient had an episode of hypoperfusion to the brain because of the diminished flow after carotid resection. The aphasia was his only obvious outward symptom.

Although an unusual example, this case serves to demonstrate how subtle some of the neurologic symptoms of stroke are after carotid resection. The patient underwent extensive rehabilitation and he is now able to communicate fairly well. At over 3 years after this incident, he still demonstrates no outward, physical signs of a stroke other than aphasia, and with therapy the aphasia is improving.

Wound Care

The wound care of skull base patients is determined by the extent of the resection and the reconstruction. Immediately after surgery in the ICU, wound care focuses on flap viability, suture line care, and suction drain care. No pressure dressing, tape, or respiratory equipment is placed over the reconstruction flap or its pedicle.

The surgeon places suction drains in very specific positions to drain a respective anatomic area of the resection. It is important to secure the drains in place in addition to placing stay sutures. Stomahesive or a similar skin barrier is placed on the skin, and elastoplast secures the drain to the Stomahesive (Fig. 1). Even if Silastic drains are used, they *t* should be stripped every 2 to 4 hours to ensure that clots are not obstructing them and permitting the accumulation of fluid/serum under the reconstruction flap. The drain suction is usually set at 100 mm Hg suction pressure..The determining factor in drain removal is an output volume that has fallen to less than approximately 30 ml in a 24-hour period. After drain removal, a pressure dressing is placed over the reconstruction to seal the flaps to the underlying tissue.

Home Care Planning

As the patient progresses from the intensive care unit to acute care to a homegoing goal-oriented program, the nursing care focus must be in parallel. Preparation of a patient and family for home care is a progressive teaching process that must begin early in the interaction of the patient with the health care system.

As with most patients, the step from hospital to home is usually a good progression, but not without stress. The task of coping with the rigors of skull base surgery and the resultant disfigurement and body image changes can be overwhelming. It is well proven (12) that those patients who have fewer overall illnesses and are younger are better able to adapt and cope (13). The older the patient, the more comor-



Fig. 1. Stomahesive skin protector and elastoplast tape secure the surgical drains following skull base, head and neck surgery.

bid illnesses, the harder it becomes to rebound after yet another serious illness and surgical procedure. The home care focus should be on independence with attention to goals of rehabilitation. These goals must be set before discharge by the multidisciplinary team in the hospital. It is incumbent on the team to transmit these goals to the home health team for continuation in the home setting.

The nurse's role in this adaptation process is to help patients effectively use what resources they have and use them to their best effect. Patients and families must be familiar with their care needs well before the day they are discharged. Teaching of home-oriented self-care activities of daily living, enteral feeding, and wound and tracheostomy care should become part of the patient's routine before discharge. As much as possible, no significant changes should be made immediately before discharge; such changes only add confusion for the patient and family. Written information regarding medications, specific wound care instructions, and enteral feedings should be thoroughly reviewed with the patient, family, and caregivers. Follow-up clinic appointments, emergency numbers, and resources should be given to the patient in writing before discharge.

The principles of geriatric medicine are important to in•t'.vKk, fan &«. ^sJat ffrfitvA fto-fratotoya.. The. *vtajfyi* -gswA vi to return to safe independence in their previous environment. Elderly sleep-wake cycles may be easily disrupted by medication and ongoing nursing care requirements.

If possible, home management of enteral feedings and wound and tracheostomy care should be scheduled to allow for uninterrupted sleep for both patient and family. Sleep deprivation often leads to failure of the home plan, requiring rehospitalization or admittance to a skilled nursing facility.

Home health nurses who are assigned to skull base patients are often very unfamiliar with their care needs, so the patient's written material may also help the home health nurse to understand better the care needs of the patient. Close contact with the clinical nurse specialist and the skull base coordinator should make the patient's transition from hospital to home smoother.

CONCLUSION

Care of the patient undergoing skull base surgery involves complex, advanced nursing care. As medical knowledge advances, so must the nursing professional respond with new methods of therapy. Such surgical advances are a challenge with each new patient, and stretch and expand the expertise of each nurse. Nursing must respond with science-based practice to the advances in surgical resection of skull base tumors.

It is the nurse who cares for patients, makes them feel better, tends to their wounds, and ministers to healing, Coping, cognition, pain management, and wound care are all issues and tasks that the patient must endure during recovery. It is the highly skilled nurse who will be at the patient's bedside, whether it be the operating room table, hospital bed, bedroom at home, or in the clinic, caring for the person.

REFERENCES

1. Donaid PJ. Combined **middle** fossa/infraternporal fossa surgery. *AORN J* [992:55:480-489.
2. Perera F. Uncovering new clues to cancer risk. *Sci Am* 1996:276(5): 54-62.
3. Brooks-Brunn J. Protecting the lungs. *Reflections, Sigma Theta Tan International* 1997;23(1):16.
4. Agency for Health Care Policy ;ind Research. *Clinical practice guidelinen on management of cancer pain.* AHCPR puniication no. 94-0595. Rockville. MD: U.S. Department of Health and Human Services, Agency for Health Care Policy and Research, 1994.
5. Vermillion C. Operating room acquired pressure ulcers. *Decubitus* I990:3(l):26-30.

6. Papantonio C. Sacral ulcers following cardiac surgery: incidence and risks. *Advances in Wound Care* 1995;7(2):24-36.
7. Zaloga G. *Enteral nutrition in hospitalized patients: a summary.* Ross Products Division publication A6382. Abbott Park, IL: Abbott Laboratories, 1995:44-51.
8. Dropkin MJ. Coping with disfigurement/dysfunction and length of hospital stay. *ORL-Head and Neck Nursing* 1997;15(l):22-26.
9. Cummings R. Understanding external ventricular drainage. *Journal of Neuroscience Nursing* 1992;24:84-87.
10. Clevenger V. Nursing management of lumbar drains. *Journal of Neuroscience Nursing* 1990;22:227-229.
11. Friedman C, Costantino P. General concepts in craniofacial skeletal augmentation and replacement. *Otolaryngol Clin North Am* 1994;27:847-857.
12. Dropkin MJ. Coping with disfigurement and dysfunction after head and neck cancer surgery: a conceptual framework. *Semin Oncol Nurs* 1989:15:213-219.
13. Mulgrew B, Dropkin MJ. Coping with craniofacial resection: a case study. *ORLNursing* 1991 ;Summer:8-18..

BIBLIOGRAPHY

American Association of Neuroscience Nurses. *Standards of practice.* Chicago: American Association of Neuroscience Nurses, 1997.

Association of Operating Room Nurses, Inc. *AORN core curriculum.* Denver: Association of Operating Room Nurses, Inc., 1991.

Association of Operating Room Nurses, Inc. *1991 AORN standards and recommended practices for perioperative nursing.* Denver: Association of Operating Room Nurses, Inc., 1991.

Cammermeyer M, eds. *Core curriculum for neuroscience nursing.* 3rd ed., update. American Association of Neuroscience Nurses, 1996.

Cavenee W, White R. (1995) The genetic basis of cancer. *Sci Am* 1995;275(3):72-79.

Dennison D. Thermal regulation of patients during the perioperative period. *AORN J* 1995:61:827-831.

Donald PJ. *Craniofacial surgery for head and neck cancer.* American Academy of Otolaryngology Head and Neck Surgery instructional course no. 2434. Alexandria, VA: American Academy of Otolaryngology Head and Neck Surgery, 1989.

Harris L, Huntoon M, eds. *Core curriculum.* New Smyrna Beach, FL: Society of Otolaryngology Head and Neck Nurses, 1997.

Lazarus RS. *Psychological stress and the coping process.* New York: McGraw-Hill, 1966.

Rennie J, Rusting R, eds. *What you need to know about cancer: Scientific American special issue.* 1996;276(9):56—167.

Society of Otorhinolaryngology Head and Neck Nursing Standards of Practice Committee. *Guidelines for Otorhinolaryngology nursing practice.* New Smyrna Beach, FL: Society of Otorhinolaryngology and Head-Neck Nurses, 1996.

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

□

CHAPTER 9

Intraoperative Neurophysiologic Monitoring

State of the Art

Robert J. Sclabassi, Jeffrey R. Balzer, and Donald N. Krieger

Cranial base surgery poses significant risk to the functioning of the cranial nerves, the brainstem, and the cerebral hemispheres. This risk is due both to problems associated with maintaining adequate blood supply to the brainstem and cerebral hemispheres and to the effect of various operative maneuvers aimed at, for example, adequately exposing and removing tumors. These risks may be reduced if appropriate information concerning the relationships between surgical manipulations and their impact on the functioning of the patient's central nervous system (CNS) is available to the surgeon. To provide information of this type, aimed at reducing both the probability and severity of injury to the neural tissue, methodologies have been developed and are being used to obtain and evaluate multimodal neurophysiologic measures in real time, during surgery to the cranial base.

Intraoperative neurophysiologic monitoring provides a real-time control loop around a system composed of the surgeon and the patient. The goals of this control loop are both the reduction of morbidity and a dynamic assessment of structure-function relationships of the patient's nervous system. These objectives are accomplished by making specific and sensitive measurements that reflect the interactions between the surgeon's intraoperative manipulations and the functioning of the patient's CNS. These goals require obtaining real-time measurements of CNS function that can be closely correlated with operative manipulations. To achieve these goals within a time frame that is of value to the progress of the operation, multiple channels of data need to be acquired, processed, and displayed rapidly.

This chapter reviews the intraoperative monitoring approach the authors use to provide multimodality neurophysiologic monitoring during cranial base surgery. In particular, a detailed description of the authors' overall approach to this complex monitoring problem is presented. The technical approaches to the acquisition and interpretation of these neurophysiologic measures are then presented. Finally, the implications of this approach for the successful performance of cranial base surgery are discussed.

APPROACH

The surgeon needs information about the functional status of the nervous system during surgery to adapt surgical strategy so as to minimize morbidity. Immediate knowledge of the physiologic effect of each surgical manipulation is an irreplaceable help in the pursuit of aggressive surgical techniques, such as those involved in operating at the cranial base (1). Thus, the objective of intraoperative monitoring during cranial base tumor cases is to help the surgeon reduce morbidity, and when it is necessary to produce morbidity, to do so in a controlled fashion—that is, to provide information about what is being done and what its consequences might be.

It has long been appreciated that the patient's physiologic status is dynamic, and that during surgery rapid and life-threatening changes may occur. This realization has led to sophisticated patient monitoring by anesthesiologists in which extensive physiologic monitoring is routinely used to maintain the homeostasis in the patient (2). This monitoring may be thought of as putting a control loop around the anesthesiologist and the patient for the purposes of life support. Some information is available from these procedures that also reflects the stress on the CNS, such as changes in heart rate related to both brainstem and vagal stimulation. However, the comparative ability to evaluate the nervous system by either clinical means or by the commonly used physio-

---

R. J. Sclabassi, J. Balzer, D. Krieger: Center for Neurophysiology, Children's Hospital of Pittsburgh, Pittsburgh, Pennsylvania 15213.

logic monitoring tools available to the anesthesiologist is limited during surgery.

These limitations in the ability to assess nervous system function have led to the development of neurophysiologic intraoperative monitoring techniques that add another dimension to the assessment of patient status during surgery. Intraoperative neurophysiologic monitoring also can be thought of as establishing a real-time control loop—this time between the surgeon and the patient (Fig. 1). The primary goals are to reduce morbidity and dynamically assess structure-function relationships of the patient's nervous system during surgical manipulation. This dynamic assessment can guide a surgeon by providing specific, sensitive measurements that reflect operative maneuvers and their impact on the patient's CNS functioning. These goals require real-time measures of the CNS functions that can be closely correlated to operative manipulations within a time frame valuable to the progress of the operation. Thus, multiple types of neurophysiologic data must be acquired, processed, and displayed in real time.

The various neurophysiologic measures described in this chapter provide objective measures of nervous system function and have significant potential for providing ongoing and relevant information about the status of the CNS. Neurophysiologic measures have value in many types of operative procedures (3-5); however, the ones described in this chapter are most useful in cranial base surgery, which involves particularly complex and lengthy surgical procedures.

Depending on the surgical procedure, the authors routinely measure electrical activity dependent on the functioning of the brainstem [brainstem auditory evoked potentials (BAEPs) and brainstem somatosensory evoked potentials (BSEPs)], the cortex [the electroencephalogram (EEG), median nerve somatosensory evoked potentials (MSPs), and visual evoked potentials (VEPs)], and electromyograms (EMGs) from muscles innervated by cranial nerves II, III, IV, V, VI, VII, VIII, X, XI, and XII. It is imperative that the measures used are both specific to the neural tissue being manipulated and sensitive to changes in the functioning of the neural tissue produced by the surgical manipulations. Many of these measures are obtained, displayed, and interpreted simultaneously, permitting a multidimensional assessment of the integrity of the neural structures at risk. In addition, many of these measures provide information not only about function itself but also about variables that indirectly affect function, such as blood flow, hypoxia, and hypotension.

An additional important aspect necessary for successful intraoperative monitoring is the planning and execution of surgical procedures in such a way that the neurophysiologists are in close communication with all other members of the surgical team, including surgeons, neuroanesthesiologists, and neuroradiologists. This preoperative and intraoperative communication between the members of the surgical team ensures that the appropriate neurophysiologic measures are used during the case, that the neuroanesthesiologist is prepared to switch anesthetic technique in support of the requirements imposed by each technique, and that the significance of observed changes is appreciated by all members of the operative team.

The authors' conceptual approach requires that the neurophysiologist understand the nature of the patient's disease, the operative strategy of the surgeon, and the anesthesiolo-



FIG. 1. Neurophysiologic monitoring establishes a control loop around the surgeon and the patient to reduce morbidity. The neurophysiologist may continuously interpret the monitored data, either in the operating room or remotely.

gist's approach to the management of that particular patient. It requires that the surgeon understand the level of information that the neurophysiologist can provide as the operative procedure is evolving, and it requires that the neuroanesthesiologist understand the effects of the pharmacologic manipulations on the monitoring tools available to the neurophysiologist. Thus, the keystone of the authors' approach to intraoperative monitoring is the close and continuous interchange of information between all the members of the surgical team.

Attention to detail begins before the patient is taken to the operating room. It is the authors' policy that all patients for whom intraoperative monitoring is ordered undergo preoperative neurophysiologic studies to determine baseline responses. The reasons for this are many, and include introducing the neurophysiologic monitoring concept to the patient, ensuring that the neurophysiologist understands the nature of the case to be monitored, ensuring that the peculiarities of the patient's responses are understood before arrival in the operating room, and determining the existence of unsuspected secondary lesions. Moreover, it is not uncommon for patients with large skull base lesions to present with very abnormal neurophysiologic responses. Knowledge of these abnormalities before the patient arrives in the operating room allows for a better assessment once operating room baselines are obtained. This approach has the support of the surgeons, who write specific orders for every patient who is to be evaluated and monitored.

The neurophysiologists participate in preoperative discussions concerning patient management, and also attend and participate in the surgical complications conferences. Thus, the neurophysiologist has a detailed understanding of each patient and his or her unique monitoring requirements before the surgical case, as well as an appreciation for the outcome of the case and for the role that intraoperative monitoring may have played in that outcome. This close coordination between the neurophysiologist and the surgeon not only ensures the most appropriate and highest-quality intraoperative monitoring, but facilitates the evolution of improved monitoring techniques to provide better the types of information the surgeons need and desire.

The neurophysiologists must communicate with the surgeon and the neuroanesthesiologist concerning the anesthetic requirements before the start of the case to ensure that no conflicts exist over the required anesthetic approach. For example, when will the use of paralytic or potent inhalation agents interfere with neurophysiologic monitoring? Many of the monitoring procedures requested by surgeons place competing and complex demands on the anesthesiologists. Thus, a variety of anesthesia techniques may be used at different times during a single operative procedure to enable the appropriate neurophysiologic measures to be taken when needed.

Based on this information and on anticipation of what may happen, the appropriate subset of monitoring tools from the total armamentarium must be selected before the beginning of the case. For example, if an injury to a carotid artery occurs during tumor resection and the surgeon wishes to place the patient under pentobarbital protection, the neurophysiologists must be prepared to provide a measure of burst suppression from both ongoing EEG activity and somatosensory evoked potentials (SEPs). Thus, the need for EEGs must have been anticipated before the draping of the patient. Finally, at some point before the actual beginning of surgery, the surgical team must be informed about the quality of the recordings: that is, how consistent or variable they are, and how they compare with baseline preoperative studies.

Pertinent information during the case is entered into the computer record and is appended to the operative data. These notes provide a permanent record of the case and can alert the neurophysiologist observing a case remotely of any significant changes. In addition, a continuous log sheet with the time of each saved response, stimulating sites, and any additional information relevant to the operation is maintained.

NEUROPHYSIOLOGIC METHODOLOGY

Neurophysiologic recording during cranial base procedures can rapidly become quite complex. It is not unusual to monitor as many as five different neurophysiologic variables simultaneously: for example, EEGs, BAEPs and BSEPs, MSPs, and EMGs recorded from multiple cranial nerves. This requires a well organized and theoretically parsimonious approach to monitoring. In addition, the recording of high-quality neurophysiologic data depends on the appropriate utilization of technology. In particular, attention must be paid to the electrode properties, amplifiers, and the equipment used for acquiring and displaying the data.

•?-" Electrode Properties

Where possible, all scalp electrodes are placed according to the International 10/20 system of electrode placement (6). Recording electrodes are placed symmetrically to provide for control recordings from the side contralateral to the surgery, even when electrodes may not be positioned in the standard recording sites. The patient is prepared for monitoring by measuring the head according to the 10/20 system and marking it appropriately for the desired electrode placement. This system, originally devised for EEG recordings, specifies the position of 21 evenly spaced locations on the scalp, with the sites determined as 10% or 20% of the separations between definitive bony landmarks. If possible, this is accomplished in the operating room holding area because this permits more accurate and rapid placement of electrodes in the operating room.

All recordings are performed using subdermal needle electrodes. Electrodes that are not in the operative field but that are on the scalp and not accessible during surgery, are either sutured or stapled in place. Electrodes on the face, which are placed for recording EMG activity, are taped in place. Electrodes in the operative field are placed by the surgeons using sterile technique, usually early in the procedure. The electrodes are checked for impedance values and are accepted if the impedance is less than 10,000 ohms. If electrodes fail the impedance test and all connections are intact, the faulty electrodes are identified and replaced. In all cases, every effort is made to reduce noise and artifact to obtain a robust and consistent potential. This is particularly important in measuring small signals in the electrically noisy environment of the operating room.

Needle electrodes also may be used as electrical stimulating electrodes, and the application techniques are the same in these instances as for recording purposes.

Monitoring System

The authors and others have been actively researching the development of distributed computer networks for the acquisition, integration, and assessment of neurophysiologic data for several years (7-11). This work has resulted in the development of a distributed computer system (NeuroNet) that has been extensively used at the Center for Clinical Neurophysiology of the University of Pittsburgh Medical Center (UPMC) and a number of other teaching hospitals not associated with UPMC. The system provides real-time and non-real-time capabilities, along with extensive facilities for supporting data distribution and communication remotely from the operating room. Most important, the system supports the acquisition and processing of multiple data types, simultaneously, and in real time. Thus, NeuroNet is a fully integrated system that transparently combines the collection, processing, and presentation of real-time data sources, including all of the physiologic monitoring functions, with non-real-time functions and extensive on-line database information.

Figure 2 presents a control flow diagram of the system with the major system components identified. The user station is any host that can support NeuroNet functions, ranging from workstations to personal computers. NeuroDisplay (Fig. 3) is a user interface screen and constitutes the front end to NeuroNet. NeuroDisplay is based on X-window's and Motif. The real-time application software supports those tasks that require guaranteed low-latency end-to-end performance, such as acquisition, processing, and display of neurophysiologic data. The non-real-time application software supports tasks that require average throughput and maximum average delay, such as file transfers and text-based e-mail.

Workstations are mounted in instrumentation racks and configured with appropriate electronics to support various data acquisition tasks, including EEGs, EMGs, and multimodality evoked potentials. Multiple units may be used in parallel on the same case if the number of variables to be monitored is greater than the capacity of a single system. The data being acquired on these systems are transparently accessible, in real time, across local area networks for review, analysis, and consultation.


User Station
NeuroDisplay
Real-Time Application Software
Non-Real-Time Application Software
Databases/File System
Operating System
NeuroNet Communication Support
Network Control Functions
Network Hardware

FIG. 2. Schematic representation of the NeuroNet control flow.

Below this layer are the system support modules. They include an operating system layer, a database/file system level, a communication support layer, and a network control layer. **The** communication support layer encapsulates the communication control structure, whereas network control functions provide the lowest-level access to the underlying network. The databases act as the integrating agent for all the data acquired and manipulated through the system.

NeuroNet permits simultaneous data collection and on-screen viewing of multiple modalities, each with user-determined observation intervals, collection rates, and stimulus rates that can be independently displayed and processed in real time on any other system on the network.

All NeuroNet software is integrated; that is, there is no concept of separate packages for each type of data collection. This provides maximum capability for collecting and analyzing combinations of different data types. The EEC capabilities include compressed spectral arrays on all available channels, digital filtering of EEC, and real-time spectral computations on the incoming data with arbitrary-length spectral averages. The EMG capabilities are the same. The evoked potential capabilities include multimodality data collection with individually controllable stimulation rates, sampling rates, observation intervals, digital filters, feature marking, baseline selection, noise estimation, and even/odd averaging. The system provides real-time remote viewing of all acquired data; multiway communication across local area networks, either digital audio or text; and unified user interfaces for local and remote systems that requires familiarity with only one user interface.

Instrumentation racks perform a number of functions, including stimulus control and generation, data acquisition, signal processing, and data display. Each workstation has a high-resolution (1,024 X 1.280 pixel), 24-bit color monitor. Data acquisition is accomplished through a custom-designed data acquisition system. This unit includes a 12-bit analog-digital (A/D) converter with a 16-channel multiplexer that can be expanded to 64 channels, and is used for acquir-



```
nesthesiolog                         iife
ome informat                         hat al
tress on the                         anges
elated to bo
owever, the                          tional
he nervous s                          comm
hysiological                         hesiol
hus intraope                         s anot
o assessing                          .

vskip .01in
ntraoperativ                         be th
s providing                          compos
nd the patie
he goals of                          of me
ynamic asses                         s of t
ervous syste
his is accom                         measu
ffect the i                          erative manipulations
nd their imp                         CNS.
hese goals r                         f CNS function that
an be closely correlated with operative manipulations.
o achieve these goals within a time frame that is of value to the progrss of
he operation, multiple channels of data need to be acquired, processed, and
isplayed rapidly.

vskip .01in
he function.l assessment of the pediatric CNS presents difficult and
nique problems when compared to that of the more mature adult CNS.
he pediatric CNS differs from the adult CNS in that it
is maturing over the first several years of life.
```

FIG. 3. Remote NeuroDisplay windows showing data from the operating room along with imaging data available to the neurophysiologist.

ing physiologic data from the anesthesiology monitors simultaneously with the neurophysiologic data. All data manipulations are handled by calls to the NDF (Neuro Data File) library.

Signal Acquisition and Processing

Neurophysiologic signals are most commonly amplified using differential amplifiers. This differencing has the effect of eliminating identical (in-phase) signal components that might be present at each recording electrode (presumably noise), and retaining the signals that are different (out-of-phase) and presumably produced by different physiologic generators. Apart from brain activity, bioelectric activity originating from muscles in the head, neck, and generators in the eyes and heart is present and is likely to be much greater in amplitude than the evoked potential of interest. Also present at the scalp are relatively large induced voltages of extraneous origin arising from electrical equipment. Any potentials that are picked up equally at both electrodes (common-mode or in-phase signals) are canceled out, and only the voltages developed between the two electrodes (out-of-phase signals) are separated and preferentially amplified. The common-mode rejection ratio governs the amplifiers' efficiency in discriminating between the local potentials of interest and these other, usually larger, interference potentials, picked up at both input electrodes. Differential amplifiers used in neurophysiologic investigations typically have common-mode rejection ratios greater that 80 dB (10,000:1). These amplifiers also have adjustable gains, with the range being between 20,000 and 500,000.

The analog filtering capabilities, provided as part of the input preamplifiers and amplifiers, determine the capabilities to remove or reduce electrical activity at certain frequencies in the recorded signals. The frequency response characteristics are defined by the high-pass cutoff point (i.e., that frequency above which the amplifier passes the frequency components of the signal essentially unattenuated), the low-pass cutoff point (i.e., that frequency below which the amplifier passes the frequency components of the signal essentially unattenuated), and the rate of attenuation occurring below and above these cutoff points, respectively. Care must be given to providing minimum phase shift through the filtering process.

To process the data on a digital computer, the signals must be sampled using an A/D converter, which has a maximum peak-to-peak input voltage range (e.g., 10 V) and which must be sized with respect to the characteristics of the amplifiers to provide maximum sensitivity. The sampling rate is determined by the frequency content of the signal being measured and the Nyquist sampling criterion, which specifies that the sampling rate must be at least two times greater than the maximum frequency content of the signal. The sampling of the signal at greater than the Nyquist rate avoids signal distortion produced by aliasing due to a too-low sampling rate.

Evoked potentials are typically a fraction of the size of the spontaneous brain activity appearing in the background EEG, and about one thousandth the size of the other physiologic and extraneous potentials with which they are intermixed. The most effective method for extracting the signal of interest from the noise, after amplifying the signal with differential amplifiers, is to use signal averaging, which is in effect a cross-correlation between a point-process defined by the occurrence of the stimuli and the recorded evoked activity (i.e., an optimal filter; Fig. 4). In averaging, the signal component at each point is coherent and adds directly, whereas the background and noise components tend to be statistically independent and summate in a more-or-less root-mean-square fashion.

The usefulness of averaging as a signal extraction technique depends on the assumption that the observed data are stationary, that is, the data are not changing rapidly in time. This assumption reinforces the need to acquire data as rapidly as possible for any single average. The authors have been investigating techniques for estimating time-varying evoked potentials (12), which allow evoked potentials to be extracted from nonstationary data. In addition to the classic averaging techniques, a number of modified averaging techniques have been developed and found to be useful. These include odd/even averaging (where two responses are computed for each data channel, one from the even number stimuli, the other from the odd numbered stimuli), moving averaging (which allows a sliding average to be computed), averaging to bursting trains (which allows high-frequency response properties to studied), random train stimulation (which allows nonlinear properties and system interactions to be characterized) (13), and noise estimation by plus/minus averaging (which allows the residual noise on a response to be estimated). The latter is extremely useful when a patient has particularly severe disease. Digital filters also may be used to enhance the extraction of signal from noise.

Digital filters have several significant advantages, including the ability to introduce zero or constant phase shift (important in assessing latencies in different components), and flexibility in implementation (multiple filtering routines can be used, depending on the nature of the data). These calculations are implemented either as convolutions (9), regressions (12), or as manipulations on Fourier transforms (14).

Neurophysiologic data are captured in an observation window and displayed in a window of the same length of time. However, many measures produced by the same stimulus occur at different latencies with respect to that stimulus. Useful methods of data display include being able to tailor the observation window to the expected latency of the interesting component of the response. For example, far-field potentials typically occur within 20 milliseconds (msec) of the stimulus, whereas near-field potentials occur within the first 100 msec of the stimulus presentation. Thus, the optimal observation of these different components is facilitated by the capability to specify different observation windows for different waves of interest being observed at the same time.

NeuroNet has an extensive package for evoked potential data collection and presentation to the user. All modalities



FIG. 4. Examples of (A) averaged and **(B)** digitally filtered average, demonstrating the capabilities of both averaging and digital filtering to extract signals from noise.

may be collected individually or mixed simultaneously (Fig. 5).

Data trending over time is flexible in that each channel of each modality may be independently displayed and controlled. Examples of processing available for all signals include digital filtering, standard averaging, odd/even averaging, noise estimation, and peak marking (both time and amplitude).

All stimulators must be precisely synchronized with the averaging process. This is accomplished either by triggering the stimulator from the computer or by triggering the computer data acquisition from the stimulator. The interstimulus intervals may be randomized to minimize contamination with phase-locked or quasiperiodic noise. SEPs are usually produced by electrical stimulators producing a shock through the skin. Both constant-current and constant-voltage stimulators are used. However, from the equivalent circuit perspective, there is no difference between these modes of stimulation.

Baseline responses are obtained before draping the patient and compared with the preoperative evaluation. Significant differences must be accounted for because signal deterioration may be due to patient positioning. The baseline responses are displayed as a background display on the computer monitor so that differences may be automatically calculated and displayed. A waterfall display window is used to follow the patterns of the change over a period of time during the case. New responses are automatically updated to this display as they are saved from the current data display. Thus, the waterfall display provides a comparative record of the patient's data and facilitates the process of identifying significant changes in activity.

The user may enter comments at any time during data collection and may store and retrieve comments from a list of predefined comments for quick annotation of a currently collected record through a pop-up window. Baseline data may be displayed for any waveform (both in the real-time displays and in trended displays). The baselines may be retrieved from any channel of any data file, thereby permitting the inclusion of baselines from preoperative studies. Artifact rejection is also fully user controlled. The user may define two time windows per channel for artifact rejection. Furthermore, the amplitude rejection criterion is user settable, along with a "spike allowance" parameter that permits a percentage of the data to exceed the artifact rejection limits without rejecting the trial.

Neuroanesthetic Considerations

It is well known that the type of anesthesia and the patient's blood pressure, cerebral blood flow, body temperature, hematocrit, and blood gas tensions all affect the functioning of the patient's CNS and thus the intraoperatively observed neurophysiologic measures (15).

Throughout the surgical procedures, close communication



FIG. 5. Multimodality evoked potential showing **(A)** left and right (AS and AD) auditory brainstem potentials and left and right (MS and MD) median nerve potentials along with **(B)** median nerve for field and cortical potentials, all recorded simultaneously.



FIG. 6. Somatosensory evoked potential recordings in response to left (P_4-F_Z) and right (P_3-F_Z) median nerve stimulation, where P_4-F_Z is over the right cortex and P_3-F_Z is over the left cortex. Baseline recordings appear as the last trace at the bottom of the figure. During cervical discectomy, systolic blood pressure progressively decreases and a consequent bilateral loss in cortical amplitude is noted.



FIG. 7. Somatosensory evoked potential recordings in response to left (PS) and right (PD) peroneal nerve stimulation. Immediately after administration of a morphine bolus, responses were observed to decrease bilaterally and remain reduced for approximately 15 to 20 minutes. The bilateral loss in amplitude was not coincident with surgical manipulation, and no postoperative morbidity was observed.

is maintained with the neuroanesthesiologist regarding any changes in blood pressure, temperature, heart rate, or muscle tone, because changes in any of these variables may alter the responses (Fig. 6).

Cranial base tumor procedures are typically performed using isoflurane or a modified balanced narcotic procedure (16). However, muscle relaxants are rarely used because the monitoring of EMG activity related to cranial nerve function is a major factor in the successful outcome of these cases.

The neuroanesthesiologist typically uses constant-infusion techniques to minimize the use of inhalation agents and to maintain as constant as possible a baseline level of functioning. The neurophysiologist notes whenever a medication bolus is given in anticipation of decrements in response quality (Fig. 7).

NEUROPHYSIOLOGIC MEASURES

The neurophysiologic measures routinely used by the authors provide a functional map of much of the entire neu-

продолжение

raxis. These include the EEG, an unstimulated measure of cortical function suitable for providing information concerning the degree of cortical activation related to either metabolic process (e.g., hypoxia) or to pharmacologic manipulation (e.g., pentobarbital-induced burst suppression to protect the patient's cortical function) (17); the MSPs and VEPs, which provide additional measures of cortical function specific to certain pathways and vasculature; the BAEPs and BSEPs, which provide information about the functioning of the brainstem, again specific to certain pathways (18); and, finally, EMGs produced by muscles innervated by the various cranial nerves, which provide information about both the cranial nerves themselves and their underlying brainstem nuclei (19).

Electroencephalogram

The functioning of the cerebral cortex is extremely sensitive to changes in arterial oxygenation and insufficient cerebral blood flow or an inadequate partial pressure of oxygen; this sensitivity is rapidly reflected in the EEG (20). Oxidative metabolism supplies the energy for maintenance of the membrane potential of nerve cells, and because the EEG depends directly on the transmembrane potentials of neurons, it reflects disturbances of cerebral metabolism such as hypoxia. Some factors that may contribute to ischemic events in cranial base tumor patients are decreased oxygen-carrying capacity due to hypovolemia or decreased cerebral perfusion pressure due to factors associated with decreased systemic arterial pressure, increased intracranial pressure, or mechanical obstruction of cerebral vessels (21).

продол
жение

The major use the authors have seen in monitoring EEG during cranial base cases has been related to clamping and bypassing of the internal carotid artery in patients who have failed a preoperative blood flow study. This is usually related to the repair of a tear to the internal carotid artery that can be associated with the removal of tumor from the cavernous sinus. To control bleeding during a repair of this type, proximal and distal control of the internal artery is required, potentially reducing blood flow to the brain. Associated with this decreased availability of blood may be hypoxia caused by an inability of the remaining members of the vasculature adequately to perfuse the brain. The second most useful application of EEG monitoring in these cases has been to help define the occurrence of embolic phenomena, which again are characterized by decreased blood flow and therefore potentially an ischemic event. In both of these situations, EEG monitoring can be useful both to identify the presence of an


incision 8:36
con bipolaring
cont bipolaring
EEG down left brain
139/66, 96
placing shunt
141/70, 96
shunt in place
sep's/EEG unchange
closing carotid
157/75, 110
md amp increasing/E
removing shunt
md delayed/EEG dow
MD delayed/down
EEG down
ext carotid clamp off
ext/common carotid c
int. clamp off
139/66, 97
sep's OK
600 10 11 39
A
200 ms
6 hz
B

FIG. 8. Continuous two-channel electroencephalographic (EEG) recordings. A: Raw bihemispheric EEG recorded continuously. B: The same EEG displayed as a compressed spectral array (CSA).

insult and to define the degree of burst suppression if barbiturate brain protection is instituted. The EEC also may be helpful in identifying the locus of damage when compared with the data obtained from the other modalities.

The authors routinely provide at least two channels of continuous EEG monitoring during cranial base cases. This minimal configuration is thought to be adequate because the problems of concern are not related to precise focality, but rather are of global or hemispheric importance. The electrode configuration used is P3/F_3 and P4/F_4, which provides two parasagittal planes, one on the operative side, and the other contralateral to the operative side, providing a continuous comparative control. This electrode configuration may be simplified to P_3/F_Z and P_4/F_Z, if the desired frontal sites are not available. These same electrodes may also be used to obtain cortical SEPs; the dual function served permits a reduction in the number of electrodes used during the procedure. Because the authors routinely use these same electrodes to monitor the median nerve SEPs, the bandpass of the amplifiers is set to that which is appropriate for these measures; specifically, the high-pass filter is set at 1 Hz and the low-pass filter is set at 1,000 Hz. The gain is set between 10,000 and 50,000, depending on the level of cerebral activity demonstrated by the anesthetized patient.

The EEG is observed both as the ongoing, unprocessed signal and in a Fourier-transformed representation (Fig. 8). The raw EEG is observed continuously on an oscilloscope, provided on each rack, and also may be observed on the workstation screen. The oscilloscope is set to provide a 0.1 second/division sweep speed to provide a rapid visual estimate of the continuous frequency. The Fourier-transformed data may be displayed as either a compressed spectral array or as a density spectral array, depending on the preference of the neurophysiologist. In either case, both the instantaneous frequency and the spectral edge may be estimated and overlaid on the displays. Because the signals on which the spectra are being computed have significantly higher frequency content than that normally of interest in the EEG, the spectral coefficients above an arbitrary value, typically 30 Hz, may be suppressed. Figure 8A presents an example of the EEG obtained before and during clamping of the internal carotid artery, whereas Fig. 8B shows the compressed spectral array computed on the same data. Note the preservation of EEG on the nonclamped side and the loss of amplitude and shift to the delta range on the clamped side.

The typical pattern seen in these measures during cerebral hypoperfusion is a reduction or loss in high-frequency activity and the appearance of large amplitude slow waves in the



FIG. 9. Continuous four-channel bihemispheric electroencephalographic recordings. In this example, a continuous barbiturate infusion resulted in approximately 80% burst suppression in the patient.

delta range (1^ Hz). The authors have even seen decreases in cerebral blood flow produced by radiographically verified cerebral emboli. The EEG appearances of any ischemic or hypoxic events are similar, and differentiation between the various putative causative factors is made by being particularly attentive to the clinical situation; for example, blood pressure, electrocardiography, oxygen saturation, administered drugs, and surgical manipulations may all have an observable effect. Other concurrent factors that may alter the EEG are changes in- depth of anesthesia, temperature changes, and changes in CO_2 content. These factors may be recognized by their relatively slow onset, lasting for several minutes, in contrast to the changes of ischemia, which usually occur within seconds. One must keep in mind that there are situations where the EEG may be acutely depressed on injection of an anesthetic that rapidly passes the blood-brain barrier. Such situations may be found in high-dose opioid anesthesia, where fentanyl induces an immediate and marked reduction of fast-frequency activity in the EEG, with an increase in low-frequency, high-amplitude activity in the delta range (21).

The EEG may be used to titrate the level of burst suppression, as shown in Fig. 9. Note the waxing and waning of the bursts as produced by barbiturates typically administered by bolus. While titrating the level of burst suppression, the authors routinely turn off the spectral analysis and use only the raw EEG.

A simple, but useful summary of possible changes is that decreased frequency with increased amplitude (22) implies an ischemic event to the cortex. Widespread frequency slowing and decreased amplitude usually implies brainstem ischemia (23), whereas ischemic events affecting the thalamus and the internal capsule produce unremarkable changes in the EEG (22) but can produce significant changes in SEPs.

Somatosensory System

Median nerve SEPs are used to aid in determining the functional integrity of the somatosensory cortex and the ascending somatosensory system, primarily in the region of the brainstem and forebrain. These potentials are useful both in preventing or reducing surgical morbidity during procedures that pose potential harm to the upper cervical cord and in assessing the level of hypoxia in cortical tissue (24).

Stimulation of the median nerve elicits a series of potentials that ascend from the stimulus site to the somatosensory cortex (Fig. 10). Typically, the most peripheral recording site is Erb's point, which is above the clavicle, lateral to the insertion of the sternocleidomastoid muscle. A negative potential with a latency of 9 to 10 msec can be recorded at Erb's point and is probably generated by the branches of the brachial plexus. An electrode at cervical C_7 records a complex wave at 11 to 14 msec that consists of a small negative peak at 11 msec, a larger negative peak at 12 to 13 msec, and a positive peak at approximately 14 msec. The NH, N^/ij, and P_M peaks are probably generated at the dorsal root entry



FIG. 10. Multiple-site somatosensory evoked potential recordings in response to median nerve stimulation. Responses are recorded from both somatosensory cortices (d and C_2), the brainstem (C_3), and the brachial plexus (C_4) simultaneously. A characteristic N_{20}/P_3o complex is recorded from the cortical channels bilaterally.

of the cervical spinal cord (Nn), the uppermost region of cervical spinal cord ($N_{)2}$/i3), and in the medial lemniscus of the brainstem (P_{14}) (25). Two negative peaks at 18 and 20 msec are easily seen at P_3 and P_4 parietal recording sites. These two negative peaks may appear as one negative complex in the operating room. The N_2o wave is generated in the primary somatosensory cortex along the posterior bank of the central fissure (26). At longer latencies (approximately 25-100 msec), additional positive (P_{30}) and negative peaks are seen. These waves are generated by secondary somatosensory areas in the parietal lobe, and by cortical association areas (27). The authors normally monitor the P_{14} (medial lemniscal activity) and the cortical Nao activity to assess conduction and P_{30} to assess cortical perfusion.

The recording and stimulating electrodes are applied after the patient's intubation, but before final positioning. The stimulating electrodes are needle electrodes and are applied subdermally, above the median nerve at the wrist, with the leads firmly taped to the patient's extremities to secure them during positioning. After final positioning, a forehead ground electrode and P_3, P4, F_3, and F_4 recording electrodes are applied in their optimal positions, if possible. The P_3 and P_4 recording electrodes should be placed 2 cm posterior and 7 cm lateral to C_7 on the left (P_3) and right (P_4) scalp, respectively. The F_3 and F_4 recording electrodes are placed 3 cm anterior and 7 cm lateral to C_z. Again, these positions are optimal; however, many times the planned incision does not allow these positions to be used. In those cases, the authors attempt to place the electrodes as close as possible to recording sites. In some cases, these electrodes are placed using sterile technique by the surgeon, in the operative field, after the incision is completed.

The stimulus intensity is usually preset at 30 V and adjusted as necessary to maximize the response, while producing minimal patient movement. If right and left median nerve responses are being observed concurrently, then the two stimuli are separated by 100 msec and a pulse width of 100 microseconds is used.

Ideally, baseline responses are obtained individually for each recording condition, before the draping of the patient, to alleviate any technical difficulties before the beginning of surgery. If MSPs are acquired by themselves, usually 128 stimuli are used to elicit each averaged response; however, on some patients stable responses are seen with numbers of stimuli as low as 32. A stimulus rate of 3.43 typically is used. These data are compared with the preoperative evaluation and used as baseline data throughout the case.

The N_2o and P_{30} waves are sensitive to certain types of anesthetics. Barbiturates and inhalation anesthetics (e.g., isoflurane, ethrane, and halothane) markedly decrease the amplitude of the cortically generated activity, including NIO, in a dose-dependent, but individualized manner (Fig. 11). Of the inhalation anesthetics, isoflurane produces the weakest effects on cortical activity. Thus, in those cases in which a balanced narcotic technique may not be used because of the need to measure EMG activity, isoflurane is used as the anesthetic. Balanced anesthetic (a combination of nitrous oxide, a muscle relaxant, and a minor tranquilizer) is a much preferred method for recording MSPs by themselves. In cases in which isoflurane is used to supplement another form of anesthesia, a concentration of under 0.4% end tidal produces minimal effects on the cortical somatosensory activity in adults; however, these effects are very individualized, and even low levels of inhalation agents may reduce the amplitudes of cortically generated activity in some patients (28).

Temperature changes significantly influence the SEP latency. For each degree Celsius of local cooling, the nerve conduction velocity decreases by about 2.5 m/second. During long operations of this type, a drop in temperature around the nerve being stimulated or in the brain tissue itself can result in a progressive increase in N_2o latency that is unrelated to



FIG. 11. Somatosensory evoked potential recordings in response to left (Pi-Fz) and right (P_3-F_Z) median nerve stimulation. During cervical tumor exposure, isoflurane is increased to 2.0%. Note that just after increasing isoflurane, a significant bilateral reduction in cortical amplitude is observed. On reduction of isoflurane, responses returned to baseline amplitudes.



FIG. 12. Somatosensory evoked potential recordings in response to left (P_4-F_Z) and right (P_3-F_Z) median nerve stimulation. Baseline potentials are displayed as the last trace at the bottom of the figure. In an attempt to cool this patient, ice bags were placed on the left (exposed) brachial plexus during in-tracranial aneurysm surgery. Note with the passage of time the trace in response to left median nerve stimulation becomes increasingly delayed *(arrow),* while the contralateral response remains on baseline.

surgical manipulation (Fig. 12). Latencies also may be transiently affected when the surgeon irrigates with physiologic saline at cooler temperatures; thus, it is recommended that warm saline be used for irrigation. These potentially confounding effects reinforce the usefulness of bilateral recordings to delineate surgically induced changes, which should be observed on the operative side, versus global changes in temperature, which should cause a bilateral change.

For the cortical responses, the amplitude and latency of the Nao/Pso complex are of primary concern. In general, a decrease of more than 50% in amplitude or an increase of more than 10% in latency is considered to be significant and communicated to the surgeon. Another response is taken as soon as possible to confirm the stability of the change. The neurophysiologist consults with the anesthesiologist to determine if a change in blood pressure, level of anesthesia, or type of anesthesia could have contributed to the observed changes in the amplitude or latency of the evoked potential. In the case when the potentials are completely lost, the neurophysiologist immediately reports the loss and then checks to ensure that all electrodes and their connections are intact.

Significant changes compared with preoperative studies may be seen in MSPs related to patient positioning (Fig. 13). These changes should be corrected for by repositioning the patient before the beginning of surgery because they may reflect pressure being placed on the brachial plexus, brainstem, or spinal cord as a result of improper positioning of the patient.

Significant changes in the MSPs also may be noted due to emboli lodging, for example, in the mouth of the middle



FIG. 13. Somatosensory evoked potential recordings in response to left (P_4-F_Z) and right (P_3-F_Z) median nerve stimulation. During positioning (minimal extension) of the neck, responses were observed to decrease bilaterally significantly. When the neck was subsequently flexed, responses slowly returned to baseline.

cerebral artery (Fig. 14). These changes are usually reflected in deterioration on the P_{30} amplitude, as seen in Fig. 15, and may be corrected through intraoperative lysis of the clot (29).

As mentioned previously, the authors routinely record simultaneous EEGs and MSPs, and many times these measures will change together (see Fig. 15). However, the authors have also observed many instances in which one has changed and not the other. A significant change in either modality must be treated with respect.

The authors also have found it useful to record the $P_{,4}$ BSEPs, using the same vertex-to-mastoid electrodes used to obtain the BAEPs. This allows the BSEPs to be recorded simultaneously with the BAEPs, and the cortical SEPs (MSPs). The somatosensory short-latency potentials behave similarly to those from the auditory system and are unaffected by most anesthetic manipulation.

The BSEPs are useful in providing another wave generated in the brainstem, and the authors have seen changes in the BSEPs and not the BAEPs, and conversely in the BAEPs and not the BSEPs. In addition, changes in the cortical SEPs and not the BSEPs provide additional localizing information.

Auditory System

Monitoring the function of cranial nerve VIII is useful in preserving hearing and the functional integrity of nerve VIII and of the brainstem.

The classic BAEP consists of a minimum of five and a maximum of seven peaks (Fig. 16). The first five peaks, Jew-ett waves I through V, are the principal peaks used in clinical practice, and waves I, III, and V are the principal waves used in operative monitoring. All occur with 10 msec of a brief click or tone presentation. Wave I is generated in the auditory portion of cranial nerve VIII. Its latency is approximately 1.5 to 2.1 msec in a normal adult. Wave I is present



FIG. 14. Bilateral median nerve evoked potentials obtained simultaneously from C4/F_4 and Cs/Fs to left and right median nerve stimulator. An embolus was thrown to the right middle cerebral artery. The P_{30} wave immediately changed. The patient was placed in barbiturate coma, the physiologic situation was then confirmed by intraoperative angiography, and the embolus dissolved with urokinase. The evoked potentials returned to baseline and the patient awoke without deficit.

on the ipsilateral side to the stimulus but is not usually seen on the contralateral side. Wave II is generated bilaterally at or near the cochlear nucleus. The latency between waves I and II is approximately 0.8 to 1.0 msec. The amplitude of wave II on the contralateral side may be greater than on the ipsilateral side. Wave III is generated bilaterally from the lower pons near the superior olive and trapezoid body. The latency between waves I and 111 is approximately 2.0 to 2.3 msec in a normal adult. Wave III may be smaller on the contralateral side than on the ipsilateral side. Waves IV and V are probably generated in the upper pons or lower midbrain, near the lateral lemniscus or possibly near the inferior colliculus (30). In ipsilateral recordings, waves IV and V may fuse into a complex that can vary between two identifiable components with a common base to a single wave with a tall, wide peak. On the contralateral side, the peaks tend to be more easily identified. Wave V tends to be the most robust peak and is typically the last to disappear when stimulus intensity is reduced. In addition, there tends to be a large negative-going wave after wave V, which aids the neurophysiologist in identifying wave V.

The BAEP is stimulated using one of several techniques, depending on the surgical procedure involved and, thus, whether the auricle is retracted and other considerations. Most often, the authors use miniature, open-air, high-fidelity earphones (i.e., those commonly used with personal tape players or radios) that rest in the concha of the ear. The earphones, along with the recording electrodes, are applied after the patient's intubation, before final positioning of the patient. After verifying that the earphones are working, they are securely taped in the ears with transparent tape so that they may remain visible. At the same time, the taping must be adequate to prevent fluids from getting to the earphones and into the ear canal, which might cause device failure or a conductive hearing loss, respectively. After final patient positioning, the vertex (C_z) and ear recording electrodes are placed. The contralateral ear electrode is placed over the mastoid (M_n) and the electrode for the operative side is



FIG. 15. Simultaneous Somatosensory evoked potential (SEP) and electroencephalographic (EEG) recordings during a left carotid endarterectomy. Note that a significant decrease in cortical amplitude of the SEP recordings and *a* slowing and decrease in amplitude of EEG occur with occlusion of the internal carotid artery on the operative side.



FIG. 16. Brainstem auditory evoked potentials recorded in response to click stimulation of the right ear (AD). Note that responses are recorded bilaterally and that a characteristic wave I, II, III and IV/V complex is recorded from the right side.

placed in the pinna of the earlobe (A_m). In some cases, it is not possible to place a nonsterile ipsilateral stimulating earphone and recording electrode because of the planned surgical incision. In such cases, the authors have placed sterile stimulating earphones or, in some situations, have monitored only the contralateral responses, which still provides valuable information concerning the status of the brainstem.

For a wide variety of cranial base tumors monitored, the intensity level of the click is set to approximately 70 dB nHL. However, when the patient is known to have a hearing loss, or a given patient's responses are not well defined, higher-intensity levels may be required. In such cases, an intensity level of 85 dB nHL is typical. Rarefaction and compression clicks are applied in an alternating fashion to minimize the apparent stimulus artifact. The stimulus rate is usually set between 9.3 and 19.3 Hz because of the well-known effects of higher stimulus rates on response latencies (31). The interstimulus intervals may be randomized to minimize contamination with phase-locked or quasiperiodic noise.

Baseline responses for each ear are acquired before the beginning of surgery. Usually, 1,024 stimulus presentations are used for the baseline data; however, the number of stimuli may be adjusted to as few as 256 depending on the quality of the responses. These data are compared with the preoperative evaluation and used as baselines throughout the case.

Waves I to V are relatively resistant to sedative medication and general anesthetics. Thus these responses place no constraints on the anesthesiologist. However, they are sensitive to temperature changes, with absolute and interpeak latencies increasing by approximately 0.20 msec/l°C.

The latency of wave V is the primary concern in intraoperative monitoring of the BAEPs, because this is the most robust and easily identifiable of the waves in this response. In general, any repeatable or systematic change in the latency of wave V that exceeds 0.3 msec is reported to the surgeon. However, clear changes in the morphology, even with latency shifts less than 0.3 msec, are noted. The next sample is taken as soon as possible to confirm the stability of the change. In the case that the potentials are completely lost, the neurophysiologist reports the loss and then immediately checks to ensure that both the stimulating system and the recording electrodes are intact.

The BAEPs are affected by retraction on the cerebellum, retraction on the frontal poles, and decreases in blood pressure. Figure 17 illustrates clear changes in both the latency and amplitude of wave V related to retraction on the cerebellum. Usually only minor amplitude changes occur if the latency increase is less than 0.5 msec; however, with latency changes on the order of 1 msec, the amplitude of wave V usually decreases by at least 50%. In this case, wave V disappeared entirely when the increase in latency was greater than 1 msec. However, with removal of the retractor, the wave began to return and had returned in its entirety by the end of the case.

Direct recording of compound action potentials (CAPs) from cranial nerve VIII is also useful both for distinguishing between the vestibular and cochlear portions of the nerve and for reducing the likelihood of injury to the nerve (32). This is easily done during the removal of acoustic neuromas, where the CAPs can be recorded by placing a wick electrode on the exposed nerve. The CAPs may be recorded using the same parameters as the BAEPs; however, there is no need to average the responses.

Visual System

Visual evoked potentials are used to aid in determining the functional integrity of the visual system, primarily in the region of the optic nerves, optic chiasm, and optic radiations. The recorded activity is generated either at the retina (electroretinogram; Fig. 18) or at the cortex.



FIG. 17. Brainstem auditory evoked potentials recorded in response to click stimulation of the right ear (C_Z-A_2). With retraction of the right cerebellar hemisphere, wave V *(asterisk)* is observed to increase significantly in latency with some decrease in amplitude. A latency shift and subsequent loss of wave V has been shown to be predictive of postoperative hearing deficits.

Stimulation of the visual system using a bright flash is not recommended for diagnostic purposes because of intersubject variability (33), except in selected situations; however, in the operating room, this is a very helpful and effective technique. Four waves are typically seen in the VHP: P_6o, which is thought to be generated in subcortical structures; and N_{70}, P_{IOO}, and Ni$_2$o, which are all thought to be generated in the primary visual cortex (34).

For intraoperative stimulation of the visual system, the authors use a fiberoptics system that is positioned directly under the eye, but not on the globe, and securely taped in place. This fiberoptics system was developed to allow VEPs to be obtained when a full bifrontal flap was used. The fiberoptic cables were designed to be mounted on the flash stimulator driven by a Grass photic stimulator (P22), and this stimulator is then set at maximum intensity. Recording electrodes are placed at O, and O_2, both referenced to C_7.

The stimulus rate used for the visual data is 1.3 Hz and the observation window is 200 msec. A bandwidth of I to 100 Hz and a gain of 20,000 are used. Baseline responses are obtained individually for each recording condition during the surgical preparation period so that any technical difficulties can be alleviated before the beginning of surgery. If the VEPs are acquired by themselves, usually 128 stimuli are used to elicit each averaged potential. These data are compared with the preoperative data and used as baseline data throughout the case (Fig. 19)

Electromyographic Evaluation of Cranial Nerve Function

Cranial nerve function is monitored continuously during skull base surgery for two reasons: first, to establish the location and orientation of the cranial nerves in the operative field; and second, to preserve functioning in the cranial nerves and their related brainstem nuclei (35).

The major observed variables are the EMGs from the appropriate muscle group innervated by the cranial nerves of interest. The cranial nerves, along with the associated muscle groups, that are usually monitored using EMG techniques are the facial nerve (VII), and the orbicularis oculi, oricularis oris, and the mentalis muscles innervated by the zygomatic branch, the buccal branch, and the mandibular branch, respectively; the abducens nerve (VI) and the lateral



FIG. 18. Electroretinogram in response to left eye (C-,) and right eye (C_2) stimulation. Characteristic negative (-20 msec) and positive (~50 msec) waves are recorded from both channels using contact electrodes positioned on the cornea.

rectus muscle; the trigeminal nerve (V) and the masseter muscle; the trochlear nerve (IV) and the superior oblique muscle; and the oculomotor nerve (III) and the medial and inferior rectus and inferior oblique muscles of the eye. When appropriate, the functioning of the glossopharyngeal (IX), vagus (X), spinal accessory (XI), and hypoglossal (XII) nerves are monitored by placing electrodes in the stylopharyngeus, the cricothyroid, the trapezius, and the intrinsic muscles of the tongue, respectively. In general, the cranial nerves ipsilateral to the operative side are monitored; however, when appropriate, bilateral activity is monitored.

Three different types of electrodes are used to record the EMGs. These are fine-wire electrodes, which have the highest impedance and the narrowest field of view; subdermal needles, which have an intermediate impedance and a larger field of view; and disk surface electrodes, which have the lowest impedance and the largest field of view (by field of view is meant the integrated level of electrical activity). The authors' recording techniques are essentially the same for all cranial nerves and all muscle groups. Subdermal platinum needle electrodes are used in bipolar recording configurations; that is, all recordings are done between a pair of electrodes inserted into the same muscle group. There is one exception to the bipolar recording technique in which the authors occasionally record transfacially between the orbicularis oculi and the mentalis muscles to reduce the number of channels allocated to monitoring cranial nerve VII. Bipolar recordings are used to minimize confusion regarding which cranial nerve or branch of a cranial nerve is producing the observed EMG. The electrodes are normally placed before the start of the procedure; however, occasionally electrodes are placed in a sterile field by the surgeons. The EMG electrodes are held in place with tape and benzoin. The authors favor the needle electrodes over the fine-wire and disk electrodes because of the signal characteristics they provide and their ease of application and maintenance.

The amplifier bandpass is set from 10 to 1,000 Hz, and a gain of 5,000 to 20,000 is routinely used. Unstimulated EMG activity from up to eight channels is monitored continuously throughout the case. This ongoing activity is continuously monitored on an oscilloscope, and any episode of interesting activity may be saved into a computer file.

Most important, the sound from all channels of activity is monitored continuously. The authors' system has the capability to amplify the activity on eight channels simultaneously and drive an audio system with this amplified signal. This system has gauges that measure the relative amounts of activity on each channel, allowing the channel with the most activity to be isolated and listened to by itself, if so desired. In addition, the system has circuits capable of suppressing the artifactual sounds related to bipolaring and stimulating. The importance of the audio system in identifying the level of activity in the muscle groups cannot be overstressed. These signals are listened to continuously for evaluation of nerve function both by the neurophysiologists and by the surgeons.

Four categories of EMG activity are observed: (a) no activity, which in an intact nerve is the best situation, but which also may be the case when a nerve has been sharply dissected; (b) irritation activity, which sounds like soft, intermittent flutter and is consistent with working near the nerve; (c) injury activity, which sound like a continuous, nonaccelerating tapping and which can be an indicator of permanent injury to the cranial nerve; and (d) a "killed-end" response, which sounds like an accelerating firing pattern and is an unequivocal indicator of nerve injury (36) (Fig. 20). It is important to note that a sharply cut nerve may produce only a brief burst of activity, and thus monitoring cannot be expected to replace extreme caution when working near the cranial nerves.



FIG. 19. Visual evoked potentials in response to flash stimulation of the right eye during suprasellar tumor resection. Responses are recorded simultaneously from three channels encompassing the left, midline, and right visual cortices. A characteristic negative/positive complex can be observed on all channels.

Besides these signals of interest, various electrical artifacts must be identified and ignored. These include high-frequency electrode pops, activity related to electrode manipulation, static from surgical instruments, and activity produced by irrigation.

In addition to monitoring the ongoing EMG activity related to the various cranial nerves, the cranial nerves also may be electrically stimulated. This usually is done to determine the location of the nerve in the operative field because many times the nerve is enveloped by tumor and may not be directly observable, or to determine the functional integrity of the nerve (37). The most common example of this procedure is the direct stimulation of cranial nerve VII (Fig. 21). The authors use Grass S44 or S88 stimulators to control the stimulus rate, pulse duration, stimulus intensity, and switching of the sound system. A stimulus isolation transformer is used to drive a monopolar stimulating electrode. The stimulating electrode is a low-impedance (^ 1,000 ohms) electrode, with the shaft insulated to, but not including, the tip. These devices are capable of producing currents as high a 15 mA, requiring care in their use. The return path for the stimulating current is provided by a metal electrode inserted into the adjacent muscle mass. The stimulus used is a constant voltage, with a pulse frequency of 10 Hz, and a pulse width of 100 microseconds. The voltage amplitude is typically varied between 0.1 and 1 V. In some situation in which very precise localization of the nerve is required, bipolar stimulating electrodes are used. However, most of the time the stimulating effort is directed toward determining if the nerve is located near to where the surgeon is currently working.

When cranial nerve VII is stimulated, activity on all three branches usually is observed on the oscilloscope. The parameters typically measured for the stimulated cranial nerve VII EMGs are the voltage threshold required to produce the evoked response of 0.3 to 0.5 V, the latency to onset of 8 to 10 msec, and a peak-to-peak voltage of 1.0 to 2.0 mV (38) (Fig. 22). These threshold parameters are measured at the beginning and end of the case, and whenever appropriate during the case. It is also important to distinguish between proximal and distal stimulation of the cranial nerve. Excellent thresholds voltages (< 0.3 V) obtained distally on a cranial nerve are not predictive of excellent nerve function after surgery, whereas the same results obtained by stimulating the nerve proximally usually are.



FIG. 20. Spontaneous intraoperative electromyographic (EMG) activity recorded from three branches of cranial nerve VII **(A)** and the cranial nerves III *(left)* and IV *(right)* **(B)** during posterior fossa tumor resection. In **(A),** spontaneous sustained trains of EMG activity are recorded from the mentalis branch of cranial nerve VII. In **(B),** spontaneous burst activity is observed from both cranial nerves III and IV



FIG. 21. Evoked intraoperative electromyographic (EMG) activity recorded from three branches of cranial nerve VII during removal of an acoustic neuroma. A monopolar stimulating electrode is used to evoke EMG activity. Stimulation is attained by placing the stimulator directly on cranial nerve VII.



FIG. 22. Evoked intraoperative electromyographic (EMG) activity recorded from three branches of cranial nerve VII during removal of a cerebellopontine angle meningioma. Stimulation of cranial nerve VII can result in the recording of evoked activity from all branches of the nerve.

SUMMARY

This chapter reviews the authors' approach to the intraoperative monitoring of neurophysiologic function during cranial base surgery. The commonly accepted principal goal of intraoperative monitoring is to prevent morbidity, and at a certain level this is true; however, the more fundamental goal of intraoperative monitoring is to provide the surgical team with information that allows them to accomplish the desired operative objective with as optimal a surgical strategy as possible, while having a clear idea of what surgical morbidity is being induced along the way. This latter goal is particularly important in cases in which the degree of difficulty is high and it is virtually impossible to prevent morbidity.

Essentially, the authors place a real-time feedback control loop around the dynamic, changing system comprising the surgeon and the patient. This requires a strong commitment to the concept that the patient's CNS is highly sensitive to the operative manipulations of the surgeon and that appropriately observed variables may predict lesions about to develop. This information permits the surgeon dynamically to modify his or her approach to the operation and thereby minimize the degree of morbidity induced in the patient.

Based on these considerations and viewpoints, the neurophysiologists, who support the intraoperative monitoring service for the Cranial Base Tumor Center at UPMC, have evolved an integrated approach to the problem of assessing the dynamic functional status of the patient's nervous system and of providing this information to the rest of the surgical team in as relevant and clear a fashion as possible. This approach is based on the combined experience of monitoring more than 300 cranial base surgical resections to date.

Neurophysiologic monitoring differs from and is complementary to that provided by the anesthesiologist in fundamental ways, and it is important to recognize and appreciate the distinctions. The monitoring performed by the anesthesiologist is aimed at maintaining the patient's homeostasis. That is, the anesthesiologist wishes to preserve the life of the patient and is focused on those measures that provide information concerning this most fundamental issue.

The use of evoked potentials in the evaluation and monitoring of patients with actual or potential neurologic deficits provides a set of objective measures of nervous system function that are more specific and reliable than previously used methods of nervous system monitoring (1). EMG measures are also highly specific and reliable. The EEG measures are also highly reliable; however, they are routinely used to assess more global factors than the EMGs.

Many apparently benign surgical manipulations may have significant effects on the neural responses and resultant clinical condition. For example, retraction of structures that are close to, or within, the pathway being monitored, noise and vibration from drilling, and heat diffusion from lasers, all affect the underlying neural tissue and the neurophysiologic responses.

Stringent time constraints exist in intraoperative monitoring of neurophysiologic function, and damage to the
may occur rapidly, over seconds. This constraint has ins
the development of methods for extracting and anal
evoked potential, EMG, and EEG waveforms rapidly a
ficiently. A corollary of the increased sensitivity requi
decrease the monitoring time is a higher rate of indivi
false-positive measures. These are usually rapidly ide
as such and produce no disruption in the flow of the c

In support of the intraoperative monitoring of these
sures, the authors have developed a distributed co
system, NeuroNet, specifically configured to suppo
considerations discussed in this chapter. This syste
vides both off-line and real-time signal processing an
review capabilities, and it addresses many of the pro
associated with the acquisition, processing, and disp
multivariate neurophysiologic data in these complex c

Monitoring of these measures in the operating roo
computationally based techniques and presents a signi
step forward in reducing patient morbidity due to su
Previously, the integrity of the CNS could be examine
clinically, when the patient recovered from anesthesia
ever, the measures described in this chapter provide
mediate assessment of the effects of surgery on the ne
system, with implications for modifying surgical techn

ACKNOWLEDGMENTS

The authors acknowledge the collaboration of the
leagues over the years: in particular, Laligam Sekhar, C
Sen, Donald Wright, Ivo Janecka, Carl Snyderman,
Hirsch, Steve Cass, Andrew Kofke, Mark Bloom, James
Matt Caldwell, Steve Whitehurst, Pedro Vera, Don Weis
John Durrant.

REFERENCES

1. Villani RM. Forward. In: Grundy BL, Villani RM, eds. *Evoke*
tials: intraoperative and ICU monitoring. New York: Springer-
1989:v.
2. Gerson GR. *Monitoring during anesthesia*. Boston: Little, Bro
Company, 1981.
3. Desmedt JE. *Neuromonitoring in surgery*. New York: Elsevier
1989.
4. Loftus CM, Traynelis VC. *Intraoperative monitoring techni*
neurosurgery. New York: McGraw-Hill, 1994.
5. Moller AR. *Intraoperative neurophysiological monitoring.*
bourgh: Harwood Academic, 1995.
6. Tyner FS, Knott JR, Mayer WB. *Fundamentals of EEG tec*
Vol. I: basic concepts and methods. New York: Raven Press,
7. Sclabassi RJ, Lofink RM, Doyle EL. NeuroNet: a distribute
processor network for clinical neurophysiology. In: Geisow M
AN, eds. *Microcomputers in medicine*. New York: Elsevier
1987:283–303.
8. Krieger DN, Lofink RM, Doyle EL, Burk G, Sclabassi RJ. Ne
implementation of an integrated clinical neurophysiology syste
ical Instrumentation 1987;21:296–303.
9. Krieger DN, Burk G, Sclabassi RJ. NeuroNet: a distributed
system for monitoring neurophysiological function in the me
vironment. *Computer* 1991;24(3):45–55.
10. Simon R, Krieger DN, Znati T, Lofink R, Sclabassi RJ. Mu
MedNet: a medical collaboration and consultation system. *C*
1995;28(5):65–73.

11. Sclabassi RJ, Krieger DN, Simon R, Gross G. NeuroNet: collaborative intraoperative guidance and control. *IEEE Computer Graphics and Applications* 1996;16(l):39-45.
12. Krieger DN, Sclabassi RJ. Time varying evoked potentials. *J Met! Eng Technol* 1994;18(3):96-100.
13. Sclabassi RJ, Risch H, Hinman CL, Kroin JS, Enns N, Namerow NS. Complex pattern evoked somatosensory responses in the study of multiple sclerosis. *Proceedings of the IEEE* 1977;65:626-633.
14. Sclabassi RJ, Harper RM. Laboratory computers in neurophysiology. *Proceedings of the IEEE* 1973;61:1602-1614.
15. Grundy BL. Intraoperative monitoring of sensory-evoked potentials. *Anesthesiology* 1983:58:72-87.
16. Domino KB. Anesthesia for cranial base tumor operations. In: Sekhar LN, Schramm VL, eds. *Tumors of the cranial base: diagnosis and treatment.* Mount Kisko, NY: Futura Publishing, 1987:107-122.
17. Niedermeyer E, Lopes da Silva F. *Electroencephalograpln.* Baltimore: Urban and Schwarzenberg, 1987.
18. Regan D. *Human brain electrophysiology: evoked potentials and evoked magnetic fields in science and medicine.* New York: Elsevier Science, 1989.
19. Kamura J. *Electrodiagnosis in diseases ofnen'e and muscle.* Philadelphia: FADavisCo, 1983.
20. Meyer JS, Marx PW. The pathogenesis of EEG changes during cerebral anoxia. In: Van der Drift JHA, ed. *Cardiac and vascular diseases/handbook of electroencephalography and clinical neurophysiology.* Amsterdam: Elsevier Science, l972:l4(Appendix):5-1 1.
21. Freye E. *Cerebral monitoring in the operating room and the intensive care unit.* Boston: Kluwer Academic Publishers, 1990.
22. Van der Drift JHA. The EEG in cerebro-vascular disease. In: Vinken PJ, Bruyn GW, eds. *Handbook of clinical neurology.* Vol. II. Amsterdam: Elsevier Science, 1972:267-291.
23. Roger J, Roger A, Gastaut H. Electro-clinical correlation in 36 cases of vascular syndromes of brainstem. *Electroencephalogr Clin Neurophys-iol* 1954;6:164(abst).
24. Gentili F, Lougheed WM, Yamashiro K, Corrado C. Monitoring of sensory evoked potentials during surgery of skull base tumors. *Can J Neu-rolSci* 1985:12:336-340.
25. Desmedt JE. Cheron G. Central somatosensory conduction in man: neural generators and interpeak latencies in the far-field components recorded from neck and right or left scalp and earlobes. *Electroencephalogr Clin Neurophysiol* 1980;50:382-403.
26. Allison T. Developmental and aging changes in human evoked rials. In: Barber C, Blum T, Nodar R, eds. *Evoked potentials III.* I Butterworth, 1987:72-90.
27. Goff WR, Williamson PD, Vangilder JC, Allison T, Fisher TC. origins of long latency evoked potentials recorded from the dep from the cortical surface of the brain in man. *Progress in Clinicc rophysiology* 1980;2:126-145.
28. Samra SK. Effect of isoflurane on human median nerve evoked tials. In: Ducker TB, Brown RH, eds. *Neurophysiology and sta of spinal cord monitoring.* New York: Springer-Verlag, 1988:14
29. Barr JD, Horowitz MB, Mathis JM, Sclabassi RJ, Yonas H. Intr ative urokinase infusion for embolic stroke during carotid enda tomy. *Neurosurgery* 1995;36:606-611.
30. Buchwald JS. Haung CM. Far-field acoustic responses: origins cat. *Science* 1975;189:382-384.
31. van Olphen AF, Rodenberg M, Verwey C. Influence of stimulu tition rate on brainstem evoked responses in man. *And* 1979:18:388-394.
32. Moller AR. Jannetta PJ. Auditory evoked potentials recorded fn cochlear nucleus and its vicinity in man. / *Neurosurg* 19 493-499.
33. Ciganek L. The EEG response to light stimulus in man. *Elec cephalogr Clin Neurophysiol* 1961; 13:165-172.
34. Kraut MA, Arezzo JC, Vaughan HG. Intracortical generators flash VEP in monkeys. *Electroencephalogr Clin Neurophysiol* 62:300-312.
35. Moller AR. Electrophysiological monitoring of cranial nerves ir ations in the skull base. In: Sekhar LN, Schramm VL, eds. *Tun the cranial base: diagnosis and treatment.* Mount Kisko, NY: Publishing, 1987:123-134.
36. Prass RL, Kinney SE, Hardy RW, Hahn JF, Luders H. Acoustic speaker) facial EMG monitoring: II. use of evoked EMG activit ing acoustic neuroma resection. *Otolaryngol Head Neck* 1987:97:541-551.
37. Daube JR, Harper CM. Surgical monitoring of cranial and peri nerves. In: Desmedt JE, ed. *Neuromonitoring in surgery.* Amste Elsevier Science, 1989:115-138.
38. Harner SG, Daube JR, Beatty CW, Ebersold MJ. Intraoperative toring of the facial nerve. *Laryngoscope* 1988;98:209-212.

SECTION II

Anterior Fossa Approach

Surgery of the Skull Base, edited by Paul J. Donald. Lippincott-Raven Publishers, Philadelphii

CHAPTER 10

Transfacial Approach

PaulJ. Donald

Of all the various approaches to skull base surgery, those to lesions involving the anterior cranial fossa have the greatest variety of techniques. This is in part because the anterior approaches have been in existence for the longest time. The basic goal of any procedure should be to provide the simplest technique that will provide optimal exposure so that all tumor can be safely excised, producing the minimal amount of deformity. When the lesion is malignant, surgery must be designed to excise the entire tumor with a margin of healthy tissue. Anything less guarantees a high incidence of local recurrence, even with adjunctive postoperative irradiation.

Most surgical procedures for excision of malignancies describe removal of the tumor *en bloc.* This is unarguably not only the classic method of cancer removal, but the most prudent method of ensuring tumor-free margins. However, in some areas at the skull base, it is highly impractical or impossible to perform a total *en bloc* resection. The major impediments are the obscuring effect created by large, bulky tumors of the deepest or most posterior aspects of the neoplasm, especially that portion that invades the skull base. In addition, the unnecessary sacrifice of uninvolved facial soft tissue that may have significant functional or aesthetic value can be avoided if a modified piecemeal resection is used. The objections to piecemeal resection are (a) the concern that there will be tumor spillage with malignant implantations in the tumor bed, and (b) the danger of leaving residual tumor at the margins. The techniques described here are in reality modified *en bloc* rather than piecemeal approaches. An *en bloc* resection is done whenever feasible, but if it is not, the tumor may be debulked initially to visualize where the resection margins are to be. Moreover, it may be necessary to remove about 90% of the tumor *en bloc* and then remove the deep portion, sometimes with the intracranial component as a second block.

Any form of piecemeal resection imposes the significant burden of responsibility on the surgeon of ensurin *eventually* tumor-free margins are obtained. The close eration of the pathologist is essential in this regard. N ous frozen sections are required, often late at night. Th< ence of a dedicated head and neck/skull base pathc goes a long way toward achieving this goal. At the end resection, copious lavage of the wound with sterile clears the area of residual, loose, "floating" tumor eel siduous attention to the maintenance of tumor-free m with meticulous visual inspection coupled with mi frozen sections has enabled the author's surgical team a modified *en bloc* technique with a minimal number cal recurrences. Although this in a way violates one basic tenets of oncologic surgery, it is successful in coi tumor removal and avoidance of local recurrence. S adherence to the *en bloc* principle will often result in t necessary removal of vital tissues. Moreover, it may ci mind set precluding the resection of lesions that appea inoperable by virtue of the fact that removal is not fe using the *en bloc* principle.

INDICATIONS

The tumors most commonly requiring combined ai craniofacial surgery usually begin in the nose or si Many of these tumors, to a greater or lesser degree, ai lignant. Inverting papilloma (Fig. 1) is an example of; sitional type of tumor that is locally invasive, doc metastasize, but must be resected aggressively to avc currence. Esthesioneuroblastoma varies from a very im; to a highly aggressive tumor (Fig. 2). Most tumors ofl or paranasal sinus origin are squamous cell or adenoca mas of the maxillary or ethmoid sinuses. Aggressive rotropic cutaneous malignancies present a frightenin nario in which a small, seemingly innocuous basal squamous cell carcinoma of the skin can travel the len a cutaneous sensory nerve, such as the infraorbital, an access to the intracranial cavity (Fig. 3).

P. J. Donald: Department of Otolaryngology-Head and Neck Surgery, and Center for Skull Base Surgery, University of California, Davis Medical Center, Sacramento, California 95817.

продолжение



a: 007/011
P
1
2
0
15+C/020
L
1
0
0
P100

FIG. 1. T1-weighted magnetic resonance images showing an inverting papilloma that had extensively invaded the anterior cranial fossa but remained intradural and extradural. A: Sagittal view. B: Axial view.



igna 1.5T FOR.ICO
U.C.DAVIS
x:2123
e:1/2
m:9/15
ag R8.0
M 22 1142352
09/05/92
12:34
P
1
2
0
R:600
E:16
C:1/1
ead
OV:24cm
.0thk/2.5sp
5/00:51
Ex:2123
Se:4/4
Im:6/12
Ax: I15.5+C
U.C.DAVIS
M 22 114235
09/05/9
12:5

FIG. 2. T1-weighted magnetic resonance images of patient with highly aggressive esthesioneuroblas-toma. He had bilateral cervical lymph nodal metastases and extensive intracranial and intracerebral invasion. Despite extensive skull base surgery, he died within 6 months of meningeal carcinomatosis. A: Sagittal view. B: Axial view.



FIG. 3. T1-weighted coronal magnetic resonance images showing apparently innocuous actinically activated squamous cell carcinoma of the facial skin that invaded the infraorbital nerve to the gasserian ganglion. A: Tumor along left infraorbital nerve. B: Spread to cavernous sinus and middle fossa, 1 year after initial resection.

The most common mode of anterior cranial fossa spread is *from the ethmoid sinuses through the ethmoid fovea to the* undersurface of the dura over the gyms rectus of the frontal lobe (Fig. 4). Tumors of the nasal vault, such as esthesioneuroblastoma, can proceed directly through the cribriform plate or along the filaments of the fila olfactoria. Tumors penetrating the orbit and invading the eye can proceed *through the orbital roof into the anterior fossa or tra vcl along* the optic nerve to the middle cranial fossa. Primary tumors of the frontal sinus are rare (Fig. 5). Those originating in the *anterior ethmoid and fronloeihmoid cells have a pr&penshy* to invade superiorly through the frontal sinus floor and then posteriorly through that sinus' posterior wall.

The decision to use craniofacial surgery to resect a lesion of the paranasal sinuses is not always easy. Malignant tumors" *that show* a *clear h'ne of separation* on *computed* Tomography (CT) and magnetic resonance imaging (MRJJ between tumor and the bone of the anterior cranial base are clearly not candidates for this procedure. Conversely, those with obvious bone erosion at this site should have the opera-JMW. *The ptvblem patients SFS those in whom tumor abttfs* the bone as visualized on CT and MRI, but who have no evidence of bone erosion. Despite this lack of evidence of in-tracranial intrusion, highly malignant tumors should have the combined intracranial/extracranial approach because these studies are not yet refined enough to show early bone invasion. Benign tumors usually do not require such aggressive treatment. Tumors such as inverting papilloma and es-mesioneuroblastoma stand to benefit significantly from the combined approach. Local recurrences, and thus the potential for future significant morbidity and even mortality, can *be a voided by combination surgery. Occult in vision may not* be appreciated despite the sophistication of current scanning techniques.



FIG. 4. Spread of tumor from the ethmoid sinus through the ethmoid fovea to the dura over the gyrus rectus.



FIG. 5. Patient with a primary squamous cell carcinoma of the frontal sinus with extensive invasion through the posterior frontal sinus wall, into the dura. Frontal view of patient shows tumor penetration through upper eyelid.

The issue of ocular sacrifice presents an agonizing dilemma. Routine orbital exenteration for invasion of malignant tumors into the periorbita or even through the bony orbital walls is commonplace. The work of Perry et al. (1) and Mann et al. (2) raises the possibility that orbital exenteration may not always be indicated when the orbit is invaded by malignancy. For tumors of less aggressive malignant behavior such as well differentiated fibrosarcoma and esthesioneuroblastoma, the eye can often be saved, even with extensive resection of periorbila, orbital fat, and even oculomotor muscles (Fig. 6), The preservation of the eye when the periorbita is invaded by a highly malignant tumor is, the author believes, ill advised but currently remains controversial. Invasion of fat. ocular muscles, or the nerve sheath by any malignancy is a clearly definitive indication for orbital exenteration.

Tumors with a primary intracranial origin such as meningioma, chordoma, or chondrosarcoma require combined resection when they clearly violate the anterior fossa floor. The two latter lesions take origin in bone and by their very nature violate the skull base barrier. Intracranial/extracranial meningiomas are histologically benign but locally aggressive and impossible to eradicate unless total excision is done. Purely benign intracranial lesions such as osteomas, fibrous dysplasia, or arteriovenous malformations can be better controlled with craniofacial surgery,

TECHNIQUE

The anterior transfacial approach incorporates a combination of transfacial and transcranial procedures. The facial approach consists of a graduated greater exposure depending on the extent of disease. The basic excision is done through a lateral rhinotomy approach coupled with a low craniotomy. The lateral rhinotomy incision may be extended into a We-ber-Fergusson incision if a more extensive maxillary excision is required. Most ethmoid and orbital tumors are easily managed through the lateral rhinotomy.

Lateral Rhinotomy—Denker—Medial Maxillectomy

The incision begins in the medial one third of the brow. It is carried in the inferior hairs of the eyebrow and inclined in the direction of the hair follicles. Although a complaint of "split brow" appearance is occasionally made, the usual result in the author's experience is of an excellent cosmetic result with the scar well hidden by the brow hairs. The incision is carried through a point midway between the midline of the nose and the caruncle of the eye (Fig. 7). It continues slightly on the nasal side of the nasal-facial groove, and is carried



FIG. 6. Young woman with a low-grade fibrosarcoma of the skin of the inner canthus of the orbit, invading the anterior ethmoids. A: Preoperative frontal view of patient. B: Patient without recurrence 1 year after globe-sparing surgery in which the periorbita, periorbital fat, and medial rectus muscle were taken. She has now been tumor free for 10 years.



FIG. 7. Lateral rhinotomy skin incision.

around the nasal ala and into the floor of the nose. The incision medial to ihe eye is deepened with a small hemostat and the angular vessels exposed. These are clamped, cut. and lig-ated or coagulated with the bipolar cautery. The incision is carried through the periosteum and the nasal mucosa cut up to the pyriform rim, Elevation of the maxillary periosteum is done over the maxillary face, initially preserving the infraor-bital nerve.

A curved osteotome used for rhinoplasty is placed low on the pyriform rim (Fig. 8). It is driven in a laterally inclined curvilinear manner through the frontal process of the maxilla and carried to a level adjacent 10 the infraorbital nerve. It is then inclined medially toward the nasal dorsum. This cut should cross the nasal dorsum below the level of the nasal process of the frontal bone, allowing for an easy greenstick fracture medially. If the osteotomy unluckily courses above this point, it is wise to back-cut the bone in-feriorly for ease of fracture. The 1.1-mm blade (B5) of the Midas Rex drill provides an easy-to-use alternative to the osteotome. The mucosa is incised separately along the osteotomy line and carried up to the septum. The lateral nasal fragment is greenstick fractured medially by placing a broad, flat osteotome against its mucosal surface and then gently twisting the instrument medially (Fig. 9). An anchor suture placed subcutaneously in the fractured fragment is attached to a Kelly clamp and hung over the opposite side of the face.



FIG. 8. Curved osteotome used to create bony lateral *rhinotomy incision.*



FIG. 9. The lateral nasal wall is outfractured with a broad, flat osteotome. A: Illustrated in cadaver. B: Drawing of completed rhinotomy.

The medial orbital periosteum and medial canthal tendon are elevated by sharp dissection, maintaining vigilance for the first sign of tumor. An external ethmoidectomy is done in the usual fashion until the point of tumor involvement. Healthy air cells are removed around the periphery of the tumor as much as possible (Fig. 10). Care is taken to cease dissection at the point at which tumor invades the globe. The periphery of the tumor is followed up to the point where it erodes or abuts the anterior fossa floor. If the tumor is so massive that this delineation is difficult and landmarks are obscure, then the tumor should be debulked. A rim of clearly visible tumor is left behind so that it can be encircled at the time of final, definitive *en bloc* removal. If the lacrimal sac and ducts are invaded by aggressive malignancies, the eye usually needs to be excised. Eye preservation is predicated on the malignant character of the lesion.

The ethmoidectomy is earned to the anterior face of the sphenoid. The excision of the ethmoid cells helps in establishing the superior cut for the medial maxillectomy. Orbital involvement by tumor and penetration of the ethmoid contribution to the orbital roof can be assessed.

The Denker procedure now proceeds by excision of the junction between the anterior and medial walls of the maxillary sinus with a Kerrison rongeur. This exposes the inferior portion of the maxillary sinus, allowing a clear view of its medial wall and the orbital floor. Tf tumor does not involve the infraorbital nerve, a small collar of bone is preserved around it (Fig. 11).

As an alternative to the Denker operation, an anterior wall osteotomy as described by Bagalella and Mazzoni (3) can be done. An area of bone including the pyriform rim and anterior maxillary wall is removed with a cutting tool such as the Midas Rex and preserved for later reconstruction (Fig. 12). This has become the author's procedure of preference.

The medial maxillectomy is done by driving a small osteotome along the floor of the nose through the bone of the inferior meatus from the pyriform rim to the posterior maxillary wall (Fig. 13). The anterior bone incision has already been completed with the anterior maxillary wall resection



FIG. 10. External ethmoidectomy dissected up to point of orbital invasion and invasion of anterior cranial fossa floor.



FIG. 11. Denker procedure done to expose the maxillary sinus and set the stage for medial maxillectomy.



FIG. 12. Anterior wall ostectomy done as alternative to Denker procedure, allowing preservation of bone flap with return at the end of operation.



FIG. 13. Medial maxillectomy.

and the external ethmoidectomy. A connection is made through the medial orbital floor, sparing the lacrimal fossa or including it, depending on the exigencies of tumor. If a more posterior extent of tumor becomes apparent when the medial maxillary wall is removed, this must be addressed by carrying the resection into the sphenoid sinus or pterygomaxillary space. This is discussed in the next section.

A superior cut is made close to the anterior fossa floor, usually cutting directly across tumor. Although most surgeons shudder at this maneuver, it is safe providing that eventually a wide-field resection of the tumor-bearing area is carried out, including a margin of healthy tissue, with careful assurance of tumor-free margins. The final step in the excision is to cut the posterior attachment of the medial maxillary wall. A curved scissors is introduced through the inferior cut along the floor of the nose. It is directed superiorly and a separation of the medial from the posterior wall begun (Fig. 14). A careful incision separating the medial from posterior wall is often difficult to impossible to achieve, so a large grasping forceps like the Lite forceps is used to avulse this medial wall. Any posterior remnants are removed with the Blakesly and Takahashi forceps.

Now that the lateral rhinotomy, anterior maxillotomy, external ethmoidectomy, and medial maxilfectomy have been done, an excellent exposure of residual tumor has been accomplished (Fig. 15). Residual subcranial tumor thai will not be included in the craniotomy block must be resected with visual and frozen-section control. Turner extending to the in-



FIG. 14. Final cut with curved scissors made through the posterior aspect of the medial maxillary wall.

I



FIG. 15. Initial tumor block removed, with only tumor penetrating anterior cranial fossa floor and posterior maxilla remaining.

ferior half of the maxilla often mandates a full maxiUectomy and is covered later in this chapter.

Involvement of the sphenoid sinus, anterior clivus, and posterior maxillary wall can be managed easily with this approach. The posterior maxillary wall is removed with a cutting bur, exposing the pterygomaxillary space and the greater palatine canal (Fig. 16). At this point, the internal maxillary artery- the maxillary nerve, the sphenopalatine ganglion, and some fat that invests these structures are exposed. Tumor is removed and involved structures are assessed. The pterygoid plates are removed with the cutting bur and pterygoid muscle involvement evaluated. Once these muscles are invaded, an additional approach is developed to resect them with a wide margin or to remove them completely, including their attachments to the mandible. (This is covered more completely in Chapter 15. on the Extended Transfacial Subcranial Approach.) Invasion of tumor superiorly at this point can be simply managed by drilling the origin of the pterygoid plates and the thick, substantial sphenoid bone that subtends them (Fig. 17). Delineation of involved bone from that which is tumor free is relatively easy. If doubt exists, curettage of marrow with frozen-section analysis is a useful guide, keeping in mind that only cancellous bone involvement can be adequately assessed.



FIG. 16. Posterior wall maxiUectomy done with cutting bur.

The sphenoid sinus and its floor, the anterior portion of the sphenoid contribution to the clivus, are easily removed with the drill (Fig. 18). The sphenoid rostrum is similarly removed in its entirety, exposing the anatomy of the lateral sinus wall. Tumor involvement of the lateral wall is removed with the bur. **Only** limited cavernous sinus invasion can be adequately and safely managed though this approach (Fig. 19). The cavernous sinus dura and perhaps a small amount of the sinus proper is safely excised, but the exposure is limited. Bone drilling posteriorly can be carried down to the pontine dura if necessary.

Further dissection laterally is limited by the optic canal in the patient with an intact eye. Removal of bone from the medial aspect of the optic canal in a seeing eye must be done with extreme caution to avoid trauma to the sheath and the ocular vascular supply. When the eye is removed, a much wider view is permitted with more facile exposure of the inferior orbital fissure and foramen rotundum, vidian canal, superior orbital fissure, and optic canal. Further dissection leads to the middle fossa and is covered in Chapter 16.

Orbital Exenteration

General *Considerations and* ***Indications***

Of all the organs that require excision during head and neck surgery, the eye carries with it the most profound emotional and aesthetic implications. Most patients balk to some degree at the idea of exenterating the orbit, and the idea of bilateral resection with the prospect of total blindness is anathema to most. It is surprising that despite the many successes of so many completely blind people in our society, which is common knowledge, many patients would rather face certain death than contemplate the loss of their sight. The role of the skull base surgeon is to present to the patient his or her therapeutic options and what the anticipated losses and impairments might be. Only the patient can decide in view of hie or her own sense of values whether to proceed.

Decisions regarding eye preservation based on known and anticipated tumor pamophysiology have already been discussed. The guidelines set up by the studies of Perry et al. (I), Mann et al. (2), and Carrau et al. (4) must be tempered in the face of highly malignant tumors such as squamous cell carcinoma, adenoid cystic carcinoma, and malignant melanoma. Local control of disease is key to long-term patient survival.



FIG. 17. Management of pterygoid plate and sphenoid body tumor invasion by resection with the cutting bur.



FIG. 18. Removal of anterior wall and floor of sphenoid sinus, and heavy bone of the base of the sphenoid removed until tumor exenteration complete.



FIG. 19. Resection of sphenoid sinus and lateral sphenoid sinus wall outlined. Minimal cavernous sinus invasion can be managed through this route.

I

Orbital exenteration includes in these cases the periorbita as well as some or all of the bony walls. The medial wall, the lamina papyracea, the floor, and the maxillary roof are almost always resected. Violation of the orbital roof by tumor is managed in the intracranial portion of the excision. Lateral extension into the infratemporal fossa is decidedly rare and easily managed. Tumor penetration at the orbital apex is the most challenging exigency in management. The superior aspect of the apex above and lateral to the optic canal is at the posterior limit of the anterior cranial fossa floor. The lateral wall in the posterior orbit faces the anterior reach of the middle cranial fossa; more anteriorly, it is related to the infratemporal fossa. The region of the apex contains the optic canal, the superior orbital fissure superolaterally (leading inferiorly to the foramen rotundum), and medially the thickened posterior extent of the lamina papyracea. Extending inferolaterally from the foramen rotundum is the inferior orbital fissure. Related to the medial wall are the posterior ethmoid cells, the cell of Onodi (if present), and the sphenoid sinus (see Chapter 2 for more on anatomy).

Inclusion of the lids in the resection is another important consideration. Proximity of tumor makes their inclusion mandatory. In the absence of involvement, decision making centers around the potential for rehabilitation and the opportunity for postoperative inspection of the cavity for possible complications, as well as the ability to detect any early local recurrence during the follow-up period. Because of the disappointment accompanying inadequate aesthetic rehabilitation of the eye and the ease of both cavity cleansing and inspection, the author's surgical team usually sacrifices the eyelids. Aesthetic rehabilitation is done with an onlay prosthesis, often anchored by interosseous implants.

Technique

Although the lids are sacrificed, as much periorbital skin .;-
possible is preserved for use in cavity lining. Before inci-
-:on, a 3-0 silk tarsorrhaphy suture is placed for easy trac-
::on. The secret of conducting a clean exenteration is pre-
-erving the integrity of the periorbita, thus staying outside "
e periorbital fat. Within the limits of sound oncologic judgment, an incision is made outside the limits of the tarsal :!ates, but not through the septum orbitale (Fig. 20). Dissec-on between skin and orbicularis oculi is carried up to the or-~:tal rims (Fig. 21). With lid skin involvement, incision
-rough periorbital skin directly down to the bone of orbital
m is done in a circumferential manner (Fig. 22). Much of
-.e periosteal elevation is easy, but there are three major "-
oints of tethering: the trochlea and the medial and lateral .
.mtrial tendons. Dissection into the trochlear fossa in the anerosuperior aspect of the orbit will prize out the trochlea and >
attachment to the superior oblique muscle tendon. Sharp
r.cision at the canthal tendons, especially the lateral, is nec-r-
sary to free the periorbita. Dissection with an elevator is
;one with ease until the area of the infraorbital fissure where, again, more vigor is required to complete the freeing of tissue to the apex.

A right-angled clamp is placed around the soft tissues of the orbital apex and the area transected with right-angled scissors (Fig. 23).Hemostasis is secured with a 3-0 silk suture ligature. Depending on tumor extent, a greater amount of orbital apical tissue may need to be resected. The first application of the clamp usually encompasses the tissue just anterior to the annulus of Zinn. This fibrous ring is tightly attached to the bone encircling the optic nerve. Firm dissection is required to free this origin of the ocular muscles. Once the globe is removed, the ophthalmic artery is now more easily identifiable. A second echelon of orbital tissue around the optic nerve is now removed (Fig. 24). All that is left now is the optic nerve stump and ophthalmic artery as they exit the optic canal and the stump ends of the cranial nerves and the ophthalmic vein in the superior orbital fissure. A margin of healthy, uninvolved tissue may require a burring away of the optic canal (Fig. *25).* This bone is quite thick, but often thins out as it transverses the superolateral wall of the sphenoid sinus. This dissection can be carried out all the way to the optic chiasm (Fig. 26). In general, only microscopic involvement of the nerve with tumor limited to the nerve sheath can be managed by this maneuver. Gross tumor involvement usually requires the addition of intracranial exposure.



FIG. 20. Periorbital skin incision.



FIG. 21. Dissection between lid skin and orbicularis oculi up to the periorbital rims.



FIG. 22. Wide margin of lid skin resected around tumor penetrating upper eyelid.



FIG. 23. Right-angled clamp placed around soft tissues of orbital apex, which are transected with right-angled scissors.

Similarly, tumor extension through the superior orbital fissure requires craniotomy that provides access to the middle fossa. Extension along the vidian nerve mandates drilling the sphenoid bone surrounding it, leading to the foramen lacerum and the region of the petrous .apex, thus further mandating an intracranial approach to the middle fossa and the potential need for management of the internal carotid artery. Infraorbital nerve involvement mandates a drilling out of the foramen rotundum and amputation of the nerve at the level of the dura, then a frozen-section check for tumor. If even a scant deposit of tumor is found at this site, an intracranial exploration of Meckel's cave is required.

Maxillectomy

Tumor invasion of the maxillary sinus infrastructure (Fig. 27), that is, that part of the sinus below Ohngren's line, necessitates maxillectomy. This usually takes the form of an "inferior maxillectomy," in which the eye and usually the floor of the orbit can be spared. However, the maxillectomy must be tailored to tumor extent. It is not uncommon for the nasal septum, facial soft tissues, orbital contents, and even facial skin to be involved with tumor in these advanced cases. Tumors above Ohngren's line, that is, involving the posterosuperior maxilla, carried in the past a dire prognosis (5-7). Invasion of the orbit is common. Extension through the posterior maxillary wall, with involvement of the pterygomaxillary space and infratemporal fossa, were considered by many experts to be signs of inoperability. Until the report of Ketcham et al. (8), patients with extension into the intracranial space were adjudged doomed to die of their disease. Tumors that are primary in the maxilla have commonly attained considerable size by the time they have invaded the

I* I

*



FIG. 24. Second echelon of orbital apex tissue resected to establish resection margin.



FIG. 25. Resection of optic canal with cutting bur to attain a tumor-free margin along optic nerve.



FIG. 26. Dissection along the optic nerve can be carried to the optic chiasm.



FIG. 27. Ohngren's line dividing the maxillary sinus into an infrastructure and superstructure. From a lateral view, the line runs from the medial canthus to the mandibular angle.

intracranial space. When tumor originates in the ethmoid block, the tumor may invade the superior maxilla and spare the palatal portion, and commonly invades the anterior cranial fossa. Superior maxillectomy then substantially preserves function and aesthetics.

In most cases, a complete maxillectomy is required. The Weber-Fergusson incision is used and the superior part is not unlike the lateral rhinotomy incision, except that an incision encircling the eye is made if an orbital exenteration is to be done, or a single limb extending under the lid if the eye is to be spared (Fig. 28). A dart in the nasal sill (I.P. Janecka, *personal communication*, 1994) and another in the upper lip, preserving the sucking tubercle of the vermilion, helps to prevent later scar contracture. Extending the vertical component of the incision down the philtral crest also helps to improve aesthetics. The incision is carried along the gingival-buccal sulcus, skirting any tumor penetration by a margin of at least 2 cm of healthy mucosal tissue. The cut curves around the maxillary tuberosity and stays close to the teeth on the palatal side unless tumor has extended into palatal mucosa. The 2-cm rule is used if such is the case, namely that the malignancy must be skirted by a 2-cm rim of healthy tissue.

The cut through the maxillary alveolar bone is either through the socket of the canine tooth or that of the lateral incisor. The involved tooth is extracted, taking care to preserve an intact lamina dura around the adjacent remaining tooth. This is essential because this will be the anchor for an eventual maxillofacial prosthesis.

The exposure of the nasal part, the ethmoidectomy, and maxillotomy are done in a manner similar to that described for the lateral rhinotomy. The exception is the antrostomy portion, which should be sufficient only to view the interior of the sinus. Although valuable clues to tumor extent are provided by the preoperative radiographic examination, precise appreciation of tumor extent can be achieved only through direct inspection. The antrostomy provides such an opportunity.

When tumor does not breach the walls of the sinus, a subperiosteal dissection of soft tissue is done over the anterior and lateral extent of the maxilla. When skin and soft tissue are invaded, the previously described requisite 2-cm margin is included, attached to the main specimen (Fig. 29). When the orbit is uninvolved, an uncommon occurrence in malignant tumors of the superior maxilla, a dissection of the peri-orbita from the orbital floor is done, exposing the bone to the level of posterior margin of the maxillary sinus. An attempt is made to preserve the attachments of both canthal tendons and the integrity of the lacrimal sac and fossa. These exigencies, especially the latter, are dictated by tumor extent. The palatal bone is separated from its overlying mucoperiosteum up to the midline. The muscles of the soft palate are cut away from the posterior margin of the hard palate. If the septum and nasal floor are free of tumor, a mucosal incision in the nasal floor is made from the pyriform rim to the junction of hard and soft palate. Tumor in the septum or floor requires septectomy and incision through the opposing nasal floor. Alveolar ridge excision is correspondingly tailored to tumor extent.

The bony cuts are now inscribed with a power saw or the Midas Rex blade. The cuts are outlined in Fig. 30. The lateral orbital rim, zygomatic eminence, and palate are incised. The superior medial cut connects the lateral rhinotomy cut to the ethmoidectomy. Obviously, the intracranial extension of tumor is exposed by now, and in extensive tumors, the neoplasm is cut across at this point. Smaller, more easily encompassed tumors are circumscribed in preparation for the



FIG. 28. Weber-Fergusson incision. Note darts in nasal sill and surrounding sucking tubercle of upper lip. (From Donald PJ, Gluckman JL, Rice DH, eds. *The sinuses.* New York: Raven Press, 1995:468.)



FIG. 29. Margin of healthy soft tissue including skin removed to ensure complete tumor exenteration. A: Weber-Fergusson incision drawn. Area of skin infiltration is outlined. B: Tumor resected. Cervicofa-cial rotation flap is outlined for reconstruction.



FIG. 30. Bony cuts for total maxillectomy. A: Through lateral orbital rim, zygomatic buttress, alveolar ridge, and nasal floor (ethmoid and nasal cut already done by lateral rhinotomy). B: Through palate, preserving as much palatal mucoperiosteum as possible.

intracranial exposure, In most cases, the tumor is transected at the ethmoid level. Tf only minor invasion of the zygomatic recess exists, the malar eminence can be preserved and the interior of the body of the zygoma excised with a drill, preserving a shell of overlying bone (Fig. 31) and thus maintaining the important aesthetics of this prominent facial feature. The lateral orbital wall is incised posteriorly as high up and as far posteriorly as dictated by turner extent.

As the palate is cut, care is taken to preserve as much length as possible of the mucoperiosteal flap. This flap will



FIG. 31. Minimal tumor involvement of zygomatic recess removed with the cutting bur.



FIG. 32. Residual triangular piece of bone, remnant of maxillectomy. Tumor remains and can be removed with cutting bur.



FIG. 33. A: Bicoronal scalp incision. B: Coronal incision marked out. C: Flap turned with Rainey clips in place. The flap edge is folded over by 4 x 4s and the clips applied. Inset shows clip and clip applier. (From Donald PJ, Gluckman JL, Rice DH, eds. *The sinuses.* New York: Raven Press, 1995:219-220.)

be used later to cover the cut edge of palatal and alveolar bone. This provides a durable epithelial covering that resists the trauma of the maxillary prosthesis used in subsequent re-^{h} habitation (see Fig. 30B).

The last bony incision that finally mobilizes the maxilla is the posterior cut that separates the sinus from the pterygoid plates. A curved osteotome is placed between the maxillary tuberosity and the base of the plates. Sharp blows with a mallet or separation with a power cutting tool will separate these structures. Scissors are used to remove all remaining soft tissue attachments and the maxilla is removed.

What remains now is a small, triangular area on the posterior maxillary wall that comprises a small portion of maxillary sinus and the anterior, vertically disposedjunction of the pterygoid plates on the ascending process of the palatine bone (see Fig. 16; Fig. 32). Superiorly, the floor of the orbit will have fractured at the site where it joins the posterior wall of the maxilla, near the orbital apex, during the maxillary extraction because of the thinness of this plate. The amputated stump of the infraorbital nerve is readily apparent and is an important structure to follow in the neurotropic tumors so often encountered in skull base surgery.

It can be appreciated now that with the exception of some debulking in large tumors and the cutting across of the intracranial and immediately extracranial component, the maxilla and its contained tumor are removed in one block. The intracranial portion can be outlined both from below and above and removed in a second block. In smaller tumors, the entire lesion can be removed in a single piece, with the intracranial and extracranial parts remaining connected and the *en bloc* principle preserved. This is desirable but not essential for total safe tumor removal.

In some cases, after the subcranial removal has been effected with the maxillectomy, there are tumor remnants at the orbital apex, the sphenoid sinus, and the root of the pterygoid plates. Their removal is accomplished as described in the previous section. All that now remains is the craniotomy.

Craniotomy

The craniotomy is tailored according to the extent of involvement of the anterior fossa floor, the subcranial tumor location, and the degree of dural or frontal lobe invasion. A bicoronal scalp incision is made, running 2 to 3 cm behind the hairline (Fig. 33). The incision is extended to the level of the root of the auricular helices and carried to the level of, but not through, the pericranium. The scalp is elevated posterior to the incision to provide access for the creation of a generous pericranial flap. Hemostatic clips, such as Rainey clips, are placed at the scalp edges for hemostasis. The flap is elevated in the subgaleal plane down to the brows, then to the lateral orbital walls laterally and just below the nasal glabella medially. A semicircular cuff of temporalis fascia is included in the flap to avoid injury to the ramus frontalis of the facial nerve (Fig. 34).

A large flap of pericranial tissue is created that will be used for later reconstruction (Fig. 35). Great care is exer-



FIG. 34. A semilunar cuff of temporalis fascia is included in the skin flap.



FIG. 35. Pericranial flap.

cised to keep it moist and protected during the operation to preserve its viability.

The superior orbital rim is exposed consonant with the width of the proposed craniotomy. The width, height, and position relative to the orbits are dictated by tumor factors. A variety of bone flaps have been designed to accommodate this. The flap design must take into account how far posteriorly the tumor extends. As dissection proceeds over the brows, the supratrochlear and supraorbital neurovascular bundles are exposed. Great care is taken to preserve them. Often, the supraorbital nerve emanates from a small bony canal. The canal wall adjacent to the orbital cavity is often merely composed of a small bar of bone, easily removed with a rongeur. If tumor penetrates the roof of the posterior ethmoid cells or the planum sphenoidale, intracranial exposure must accommodate dural elevation almost to the sphenoid ridge. Exposure must enable the placement of dural sutures once resection is complete because the necessity of providing a watertight closure is an absolute mandate in these cases to prevent cerebrospinal fluid leak and the possibility of infection. Bringing the craniotomy down to or even



FIG. 36. Calvarial invasion by tumor. A: Lateral magnetic resonance image showing bony invasion. B: Intra-operative photograph showing calvarial bulging from tumor invasion. C: Operative specimen showing tumor in dura and bone.

including the orbital rims and roof may be necessary to enable the visualization of the posterior limits of tumor. There may be dural involvement over the anterior convexity of the frontal lobes or in the falx. Even the superior sagittal sinus may be invaded. Occasionally, the anterior calvarium is transgressed by tumor and requires resection (Fig. 36). Adequate exposure to remove cancer in the frontal lobe requires a more extensive craniotomy. A number of different craniotomies to accommodate anterior skull base resection are illustrated in Fig. 37.

Many tumors have minimal intracranial penetration, and these are often anteriorly located. A limited, but adequate, exposure can be achieved through the frontal sinus, especially if it is capacious enough. This is accomplished by applying a template of the sinus configuration cut out of a 5-foot Caldwell-view radiograph. This procedure is similar to that done for the osteoplastic flap and fat obliteration of the frontal sinus for inflammatory disease. The shape of the sinus is outlined with methylene blue and a nonsiliconized needle. A series of holes done with a small penetrating bur



FIG. 37. Craniotomies designed for various anterior skull base exposures. A: Osteoplastic flap. B: Standard low craniotomy preserving the brow. C: Low craniotomy including supraorbital bandeau. D: Exposure after craniotomy in (C).

продол
жение



FIG. 38. Osteoplastic flap outlined.

follow this inscribed outline (Fig. 38). These are connected with a small osteotome. the Midas Rex blade, or the footed craniotomy tool. Both the bur holes and the osteotome are angled to create an oblique cut to prevent later prolapse of the flap when it is restored at the conclusion of the case. The intersinus septum is transected with a broad, flat osteotome and the osteoplastic flap fractured forward. The flap will be greenstick fractured over the anterior roofs of the orbits and through the root of the nose. Osteotome cuts judiciously placed at the lateral extremities of the frontal sinus and through the root of the nose facilitate this down-fracturing of the flap, The interior of the frontal sinus is now exposed and all mucosa is removed (Fig. 39). It is essential to bur away a thin layer of the bone of the flap's inner side to remove all mucosal remnants at the completion of tumor removal.

The posterior wall and floor of the sinus are removed, Sometimes tumor penetrates the floor, and this is included in the resected block (see Fig. 39B). Care is taken to elevate and protect dura as the removal of the posterior wall proceeds. The frontal sinus floor, which in some instances is quite extensive, is removed as well as the frontonasal ducts. With the exception of the anterior wall, the sinus has been entirely eliminated. When near the midline, it is important to remember that the superior sagittal sinus takes origin in the foramen cecum, just in front of the crista galli. The sagittal sinus arises from here as the termination of the dorsal nasal vein, then ascends along the frontal spine of the posterior frontal sinus wall. Fortunately, the vessel is of little substance near its origin and does not achieve significant size until it reaches the top of the sinus. This, however, is not true in patients with a capacious frontal sinus. Careful dissection preserves its integrity.

In those cases in which a particularly low entrance into the anterior fossa is desired, a low craniotomy combined with resection of the brow in the form of a cranial bandeau is done (see Fig. 37C). A dissection of the periorbita over the orbital roof and detachment of the trochlea provides excellent access to the horizontal portion of the osteotomy (Fig. 40).

In most cases in the author's experience, a modest low craniotomy as outlined in Fig. 37B is used. This transects the frontal sinus in most cases and requires its cranialization at the termination of the procedure.

In the elderly, dural elevation is done very carefully because of its brittleness in this age group. Delineation of dural invasion by tumor is indicated from below but is definitively established from above. Dural entry is made about I cm beyond known involvement by neoplasm. Brain retraction is kept to an absolute minimum, Brain slackness is provided by cerebrospinal fluid drainage through a lumbar drain and may be augmented by hypocapnia or diuretics. Usually the head



FIG. 39. Osteoplastic flap opened. Tumor is seen penetrating through the floor. A: Tumor seen through the floor of the frontal sinus in a patient with carcinoma of the ethmoid sinuses. B: Diagram outlining excised bone that will be removed with tumor.

and neck surgeon identifies the margin of healthy bone surrounding the tumor from below, whereas the overlying dura margin is established by the neurosurgeon by direct inspection. He or she places the osteotome and begins to cut the bone, or does so with a cutting bur or blade, while the neurosurgeon protects the brain with a retractor (Fig. 41). Any areas of tumor penetration of brain are skirted, with this part of the resection delayed to comprise the final step in the procedure. When the lesion has finally been encompassed by a margin of healthy tissue, the lesion is pushed from above down through the facial exposure (Fig. 42). Liberal use of frozen-section analysis establishes integrity of dural margins first, and, if involved, areas of invaded brain. It is essential to conduct a complete examination of the exenteration cavity on both the intracranial and extracranial aspects to be sure the tumor has been totally encompassed by the resection.

The amount of brain removal is determined by the neurosurgeon. The technique of brain removal differs somewhat from the standard approach for malignant neoplasms primary to brain substance. Malignancies of the head and neck tend to invade brain substance by a pushing margin, rather than by the diffuse extension that hallmarks the usual spread of central malignancies (see Chapter 4). A 5- to 1-mm margin of healthy tissue usually skirts the microscopic extent of disease. Tumor removal is done with sharp dissection and bipolar cautery rather than suction.

Gross total removal of tumor is not acceptable; only microscopically confirmed, tumor-free margins suffice. The



FIG. 40. Tumor arising in ethmoid sinus, penetrating the posterior wall and floor of frontal sinus, exposed by the combination of a low craniotomy and a cranial bandeau that includes the brows.



FIG. 41. The neurosurgeon protects the brain from above while the head and neck surgeon outlines the amount of bone resection from below.




Superior
Crista gali
cribriform plate
Tumor
Anterior
Posterior
Septum
Inferior

FIG. 42. A: Tumor margin outlined from above. B: Tumor delivered through the facial wound from above downward. {From Donald PJ. *Head and neck cancer: management of the difficult case.* Philadelphia: WB Saunders, 1984: 192-193.) C: Defect in cranial floor. D: *En bloc* specimen. E: Diagram of specimen.

cavities are liberally lavaged with sterile water and closure begun.

RECONSTRUCTION

Intracranial reconstruction is done first. Hemostasis is meticulously secured before dural closure is initiated. Most of the patients in the author's series were closed with a dural closure, the intracranial interposition of a pericranial flap, and a split-thickness skin graft placed from below to line the cavity.

Dural graft tissue is either natural or homograft material; fascia lata harvested from the thigh or temporal fascia obtained from the region deep to the bicoronal scalp flap is most desirable. Lyophilized homograft dura or bovine pericardium is frequently used for large defects (Fig. 43). The tragic appearance of Jacob-Creut/.feldt disease in a few patients who received lyophilized dural grafts in Europe has not been seen in North America. The fear of this dreaded disease has dissuaded a number of surgeons on this continent from using this material.



FIG. 43. Lyophilized dural patch used to replace extensive dural area of involvement over frontal lobe.



FIG. 44. Pericranial flap. A: Osteoplastic flap is used in a capacious frontal sinus, giving limited but adequate anterior cranial fossa extension. B: Sagittal view. Coronal scalp flap and pericranial flap are elevated. Bone flap is outlined. (From Donald PJ, Gluckman JL, Rice DH, eds. *The sinuses.* New York: Raven Press, 1995:466-467.)



FIG. 45. The pericranial flap is placed intracranially. A: A slot of bone is removed from the inferior edge of craniotomy flap to accommodate the pedicle. B: Pericranial flap is placed intracranially over the area of skull base defect.

The secret to the avoidance of postoperative complications in anterior skull base surgery is the insurance of a watertight dural closure. Sutures between the dura and graft are often tacked to the calvarium in aid of this goal. Posteriorly. sutures are sometimes difficult to place, especially near the sphenoid wing and under the chiasm. The use of fibrin glue may help in anchoring the dura at this site.

The keystone structure in anterior fossa floor reconstruction is a viable flap of pericranium. It is usually pedicled on the supraorbital and supratrochlear arteries (see Fig. 35; Fig. 44). Jackson and colleagues (9) suggest that inclusion of the galea with the pericranium ensures a richer and more predictable blood supply. Their very convincing research, however, is not supported by the experience of most surgeons doing craniofacial surgery. It would appear prudent to use the compound flap in those patients who are at risk for vascular compromise, such as those patients who have a history of prior radiation or in cases in which a long flap must survive on a unilateral pedicle. It is essential to ensure the viability of the flap by keeping it moist during surgery using irrigation with physiologic solution or covering the flap with a wet sponge. Preserving the pericranium on the coronal scalp until required in the reconstruction also helps in this regard.

The pericranial or compound pericranial-galeal flap is folded over the inferiorly cut edge of the craniotomy and placed across the defect in the anterior fossa floor (Fig. 45). Sometimes a narrow strip of bone is removed inferiorly so as not to SQjVieexe. the flap and compromise its vascular pedicle. The distal end is tamped between the cranial floor bone and the overlying dura. It may be secured with sutures through the bone or anchored with fibrin glue. The important point to stress is mat the flap is placed intracranially, not extracranially.

The cranial bone flap is anchored into place, usually with plates, and the bur holes effaced with a titanium bur hole cover (Fig. 46). Any retained facial bone fragments, such as the maxillary osteotomy (Fig. 47), are fixed into position with miniplates and microplates.

Epithelial lining to the cavity can be accomplished by pedicled flaps, free flaps, and split-thickness skin grafts, or by simply leaving the pericranium uncovered and allowing reepithelialization with sinus mucosa (Fig. 48). Pedicled



FIG. 46. The craniotomy flap is fixed *in situ* by square plates and the bur holes effaced by bur hole covers.



FIG. 47. The maxillary ostectomy segment is restored and fixed by miniplates and microplates.



FIG. 48. The pericranial flap is in place, the defect covered by split-thickness skin grafts, and the cavity packed. (From Donald PJ, Gtuckman JL, Rice DH. eds. *The sinuses.* New York: Raven Press, 1995:470.)

flaps and free vascularized flaps are usually unnecessary in the reconstruction. Moreover, they may preclude the detection of possible early recurrence of tumor. MRI and CT follow-up to diagnose such recurrences in these patients has been disappointing because early disease is often confused with postoperative and postradiation changes. They may, however, present the only viable solution in those cases in which there has been extensive prior radiation therapy and the residual tissues have poor vascularity.

The split-thickness skin graft most often provides a rapidly healing, durable cavity liner that can stand up to the demands of a weight-bearing prosthesis. The graft is held in place by medicated gauze packing material.

Before the placement of the pack in the cavity, attention must be drawn to the lacrimal system in those eyes that have escaped exenteration. During the medial wall maxillectomy, the nasolacrimal duct is amputated not too far from the lacrimal sac. The cut edges of the duct are sewn to any available adjacent soft tissue to evert this mucosa-lined tract. The newly markedly foreshortened duct is siented open with the instillation of a fine silastic cannula inserted into both of the lacrimal canaliculi and loosely tied in the cavity. If necessary, only one canaliculus is sufficient to maintain patency of the system.

The packing in the cavity is removed at I week under general anesthesia. An anesthetic is used to obviate pain and facilitate the best inspection possible of the newly healed cavity. Twice daily, gentle irrigations with a warm saline solution are done to remove debris and promote healing.



FIG. 49. Prosthetic rehabilitation required for the coverage of skull base defects is aided by the use of osseointegrated implants consisting of interconnecting bars and magnets. A: Large defect in patient after resection of large frontoethmoid tumor invading calvarial bone and dura. Osseointegrated implants are placed. B: Connecting bars and magnets attached. C: Prosthesis in place.

The lacrimal stent is left in place for about 12 weeks to ensure an effective drainage of tears and the prevention of troublesome epiphora.

The cavity is carefully monitored monthly to rule out early local recurrence.

Placement of a prosthesis is delayed until the cavity is healed and the skin graft matured, usually about 3 months or more. When there is substantial loss of facial skin and in some cases in which an ocular prosthesis will not be adequately retained, the use of osseous integrated implants helps. Titanium fixtures are strategically placed in bone and then, once integrated, each is mounted with an abutment cylinder. Magnets are incorporated into the abutment and these, in addition to an integrated connecting bar system, provide solid anchoring for the maxillofacial prosthesis (Fig. 49). The biggest drawback to this rehabilitation system is the time necessary for osseointegration to take place. In the unirradiated facial bones. 3 to 6 months is required between the first and second stages (implant placement until application of the abutment cylinder). In the irradiated cases in which bone healing is markedly prolonged, a delay of 12 months is not uncommon. The second drawback is cost. Reimbursement is sometimes difficult because insurance companies choose to label such techniques as cosmetic in nature rather than functionally restorative.

Complications are detailed in Chapters 29 and 30 and are not repeated here.

RESULTS

The first favorable results of skull base surgery were published by Ketcbam et al. (8). They described the results of resecting malignancies that invaded the anterior cranial fossa, usually taking origin in the nasal cavities or paranasal sinuses. Their 45% tumor-free 5-year survival rate established cranial base surgery as a reasonable approach to highly aggressive sinonasal cancers. Tumor-free survival statistics have currently improved to about 65% (10), It is important to remember that without this therapy, most of these patients would have died from their disease. The improved survival rate is even more remarkable in that the indications for anterior skull base surgery have expanded to include patients with extensive dural invasion and even brain involvement. Bohrer et al. (11) have shown that there is no statistically significant difference in the survival between patients with or without dural invasion.

The results in the resection of benign tumors are much better than in malignant disease.

REFERENCES

1. Perry C, Levine PA, William BR, Cantrell RW. Preservation of the eye in paranasal sinus cancer surgery. *Arch Otolaryngol Head Neck Surg* 1988:114:632-634.
2. Mann W, Rareshide E, Schildwachter A. Nasennebenhohlentumor mit orbitaler Beteiligung. *Laryngorhinootologie* 1989:68:667-670.
3. Bagatella F. Mazzoni A. Microsurgery in juvenile nasopharyngeal angiofibroraa: a lateronasal approach with nasomaxillary pedicle flap. *Skull Base Surgery* 1995;5:219-226.
4. Carrau RL, Segas J, Nuss DW, Johnson JT, Janecka IP. Orbital invasion by squamous cell carcinomas arising in the sinonasal tract: outcome after selective orbital preservation. Presented at the Joint Annual Meeting of German and North American Skull Base Societies, Lake Buena Vista, Florida, February 13. 1994.
5. Ohngren LG. Malignant tumors of the maxilloethmoidal region: a clinical study with special reference to the treatment with electrocautery and irradiation. *Acta Otolaryngol Suppl (Stockh)* 1933:19:1^176.
6. Sisson GA, Johnson NE, Amiri CS. Cancer of the maxillary sinus: clinical classification and management. *Annals Oral Rhino! Laryngol* 1963:72:1050.
7. Jesse RH, Butler JJ, Healy JE Jr, Fletcher GH, Chau PM. Paranasal sinuses and nasal cavity. In: Maccomb WS, Fletcher GH, eds. *Cancer of the head and neck.* Baltimore: Williams & Wilkins, 1967:329-356.
8. Ketcham AS, Wilkins RH, Van Buren JM, Smith RR. A combined intracranial facial approach to the paranasal sinuses. *Am J Surg* 1963:106:698-703.
9. Fukuta K, Potparic Z, Sugihara T, Rachmiel A, Forte RA, Jackson IT. A cadaver investigation of the blood supply of the gabal frontalis flap. *Plast Reconstr Surg* 1994;94:794-800.
10. Schramm VL. Anterior craniofacial resection. In: Sekhar LN, Schramm VL, eds. *Tumors of the cranial base.* Mount Kisco, NY: Futura Publishing Co., 1987:265-278.
11. Bohrer PS, Donald PJ, a Wengen DF, Boggan JE, Stevenson T. The significance of dural and cerebral invasion by skull base malignancies. In: Mazzoni A, Sanna M, eds. *Proceedings of the First European Skull Base Society*. Amsterdam: Kugler Publications, 1995:133-138

Surgery' of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 11

Facial Degloving Approach ☐

Joao J. Maniglia and Ricardo Ramina

Facial degloving can be defined as a surgical approach to midface structures that leaves no visible incisions and scars on the face. The name itself means a subperiosteal dissection that degloves the soft tissue, exposing the midface bone and cavities to surgical exploration and ablation (Fig. 1).

Caldwell and Luc in the early 20th century used ipsilateral sublabial incision and subperiosteal dissection for the treatment of sinusitis. Converse (1) used it in the 1950s for facial contour for benign lesions. Dencker and Kahler (2) went further and removed the medial bony facial pillar in a radical treatment for sinusitis. Portmann and Retrouvery (3) were the first to describe facial degloving for a maxillectomy as treatment for cancer, and gave credit to Sibileau for the original idea.

Those unilateral approaches cannot, however, be considered as true facial degloving. Roe and Joseph in the late 19th century established the incisions and subperiosteal/subperi-chondral dissections for rhinoplasty without external incisions. Williams (4) used rhinoplasty incisions combined with external facial incisions for treatment of intranasal tumors. The Caldwell-Luc approach and rhinoplasty techniques were widely used by ear-nose-throat-head and neck surgeons, the former for the treatment of sinusitis and the latter for aesthetic and functional nasal repair. Casson et al. (5) reported on the use of rhinoplasty and vestibular incisions combined with bilateral subperiosteal dissection of the maxilla, firmly establishing the concept of mid-facial degloving (Fig. 2).

It is fair to say that many surgeons in the 1960s and 1970s successfully used the degloving procedure for treatment of a variety of lesions (e.g., fractures, benign and malignant tumors) for many years, without officially publishing any papers. Among the surgeons who published in the 1980s, there are Alien and Siegel (6), Conley and Price (7), Maniglia (8), Price et al. (9), and possibly many others.

The next development in facial degloving came with the publication by Mikko Paavolainen et al. (10) of a procedure using lateral osteotomies and septal transection, elevating the whole nasal pyramid with degloving. In the authors' opinion, this degloving variation should only be used in the treatment of malignant tumors.

Oncologic head and neck surgeons still prefer to use the Weber-Fergusson paranasal incision procedure and its modifications (Fig. 3). The authors see many advantages to the use of the degloving technique, which gives wider bilateral exposure from the septum to the mandible and from the orbit and skull base to the hard palate. There are no visible scars, and reconstruction is very simple with very little morbidity for the patient.

The first author learned the technique from A. Maniglia in the late 1960s, having used degloving technique only for paranasal and nasal fossa tumors. The authors extended its use to removal of extensive nasophavytvgeal angiofibromas and clivus tumors, and, in combination with anterior and middle fossa craniotomy, for clival tumors and a variety of benign and malignant tumors of the anterior and middle skull base.

After degloving of soft tissues is performed, there are still the bony structures of the midface with which to contend. Bone resection is variable depending on the site and extension of the particular lesion being treated. The anterior wall of the maxilla can be removed and the antrum used as access to the pterygopalatine fossa, cavum, and sphenoid sinus. By removing the middle pillar of the maxillary bone and the medial antral wall, intranasal and ethmoid tumors can be approached, with the possibility of performing partial maxillectomy (Fig. 4). If the posterior pillar of the maxillary antrum and the pterygoid plates are removed, there is a wide approach to the nasopharynx and clivus (Fig. 5). Resection of the lateral pillar gives wide access to the temporal and infratemporal fossae and paralateropharyngeal space.

Type I Lefort osteotomies can be performed, allowing an ample bilateral approach to the cavum, clivus, and sphenoid

J. J. Maniglia: Department of Otolaryngology. Universidade Federal do Parana, Curitiba 80440-080. Brazil.

R. Ramina: Skull Base Surgery Foundation, Curitiba 80240, Brazil.



FIG. 1. Cadaver dissection: bilateral sublabial incision and periosteal displacement.

sinus in the midline. If the lesion requires it, the mid-facial bone can be split; the lesion is removed and the midface reassembled using miniplates.

In the authors' experience, the most frequent indication for degloving and a transmaxillary approach is for the surgical treatment of juvenile nasopharyngeal angiofibromas with lateral extensions. The authors usually remove the anterior wall of the maxilla and the middle and lateral pillars, preserving the inferior turbinate and membranous nasolacrimal duct (Fig. 6). A wide approach, is obtained and bony reconstruction usually is not necessary. This is the authors' favorite surgical procedure for removal of juvenile nasopharyngeal angiofibromas with intracranial extension. Occasionally, the authors have performed procedures in



FIG. 2. Cadaver dissection: complete degloving. *Empty* arrows indicate infraorbital nerve and *full arrow* shows the nasal septum.



FIG. 3. Modified Weber-Fergusson incision.



FIG. 4. Cadaver dissection showing infraorbital foramen and nerve *(black arrow)* and membranous nasolacrimal duct *(thin white arrow),* and inferior and middle turbinate *(large white arrows).*



FIG. 5. Cadaver dissection showing infratemporal fossa *(white star)* and sphenoid sinus *(black star),* pterygopalatine artery *(white arrow),* and cavum *(asterisk).*

which the anterior wall of the maxilla connected with the middle and lateral pillars are preserved; these fragments are stabilized with miniplates (Fig. 7). However, the authors have seen no advantage in preserving these structures as far as long-term facial growth is concerned.

Degloving and a transfacial approach can be used with external ethmoidectomies, frontoethmoidectomies, and craniotomies, and to remove a wide variety of anterior and middle cranial base tumors.



FIG, 6. Cadaver dissection. Hook shows opened membranous nasolacrimal duct *(white arrow),* and behind it the maxillary ostium *(white star). Asterisk* indicates the lacrimal sac.



FIG. 7. Reconstruction of anterior maxillary wall with mini-plates.

SURGICAL TECHNIQUE

General Preparation

The patient is in the supine position with 30 degrees of head elevation. Orotracheal intubation and general anesthesia are started and the tube is fixed on the contralateral maxillary or mandibular premolars with dental floss.

Incisions and Subperiosteal Elevation

After administration of lidocaine 2% plus epinephrine 1:100,000 is infiltrated, rhinoplasty incisions (intercartilaginous and transfixion) and bilateral sublabial incisions are performed (Fig. 8).



FIG. 8. Surgery: transfixion and intercartilaginous incisions. *Star* indicates caudal nasal septum.



FIG. 9. Surgery: transfixion and intercartilaginous bilateral sublabial and vestibular incisions. *Star* indicates caudal nasal septum.

The soft tissues of the nose are elevated from the bony-cartilaginous framework, and the cheek is elevated from the anterior maxillary wall up to the infraorbital foramen on both sides. The pyriform aperture mucosa is incised, and the soft tissues of the nose and cheek can be widely displaced toward the glabella and held by two large Penrose drains fixed on head drapes (Fig. 9). •

Medial to the infraorbital foramen, the soft tissue can be displaced up to the anterior orbital crest and lacrimal sac. Lateral to the infraorbital foramen, a portion of the zygomatic bone can be removed after severing the masseter muscle insertion if access to the temporal fossa is contemplated. If there is inferior extension of tumor to the paralateropharyngeal space, the posterior aspect of the sublabial incision may be extended to the anterior tonsil pillar in the retromo-lar space. If desired, the anterior attachment of the inferior lurbinate and the soft tissue lacrimal duct to the vestibular skin can be kept, displacing it for surgery and replacing it at the end of the procedure.

Bone Resection

Bone resection is planned along the walls of the maxillary anlrum. If preservation is attempted, reconstruction with miniplates can guarantee a sophisticated anatomic rearrangement.

Trammaxillary Approach

A degloving operation is not necessary to do a transmaxillary ethmoidectomy-sphenoidectomy. If more intranasal space is needed for removal of midline disease with mini-



FIG. 10. Surgery: degloving/transmaxillary approach; maxil-

nasopharyngeal angiofibroma inside maxillary sinus *(white arrow). Asterisk* indicates medial pillar.



FIG. 11. Surgery: inferior turbinate *(star)* with attached mem-
£r&/n?s!&' ^&&&te<?/?/??<&> tsb geal angiofibroma *(balls).*



FIG. 12. Cadaver dissection: pterygopalatine fossa with artery (in hook: *arrow)* passing in the rostrum of the sphenoid sinus *(star).*

ma] lateral extension, the medial pillar can be removed (as in the the Dencker operation). After removal of the anterior wal I of the maxillary antrum, a horizontal bony bulge (inferior turbinate bone) and a vertical bulge (bony nasolacrimal duct) are visible on the medial wall (Fig. 10). Between them lies the maxillary sinus ostiuni and posterior ethmoid cells. After appropriate bone removal, the mucosa of the inferior meatus can be incised, leaving the soft nasolacrimal duct attached to the inferior turbinate, which can be displaced medially or anteriorly after incision of the inferior turbinate at its mil (Fig. 11).

The orbital rim portion of the infraorbital foramen and anterior lacrimal crest can be removed, allowing displacement of the infraorbital nerve and lacrimal sac superiorly along with the mid-facial degloving. In this way, intranasal, transethmoidal, transsphenoidal, and cavum resection of tumor can be accomplished.



FIG. 13. Surgery: exposure of large juvenile nasopharyngeal angiofibroma *(balls),* showing membranous nasolacrimal duct *(arrow)* and inferior turbinate *(star).*

Advancing posteriorly, the surgeon can remove the posterior (medial) pillar of the maxillary antrum, gaining access to the pterygopalatine foramen with its arteries. If the posterior wall of the maxillary antrum. is removed, the pterygopalatine fossa is reached, where the vascular pedicle of a juvenile nasopharyngeal angiofibroma can be ligated (Fig. 12).

Extended Transmoxillary Approach

If necessary, an extended transmaxillary approach can be performed by removing the lateral facial pillar, gaining access to the temporal fossa, infratemporal and paralateropharyngeal space, and the floor of the middle cranial base and the cavernous sinus. The authors usually combine a bilateral degloving with an ipsilateral transmaxillary approach. If necessary, a bilateral bone approach with Lefort I osteotomies or mid-facial splitting can be done.



FIG. 14. Surgery: after pedicle coagulation and section *(star),* tumor removal is begun *(serrated ball).*

In general, the authors save more complicated approaches for deeper and bigger tumors (e.g., chordomas or chondrosarcomas of the clivus).

Tumor Resection

Preoperative embolization is helpful in preventing excessive tumor bleeding in surgery of large tumors.

After securing its vascular pedicles, the tumor is removed (Figs. 13, 14). Bleeding is controlled with Gelfoam, Surgicel, and light anterior and posterior nasal packings. Soft tissue is replaced. If desired, bone can be held in place by wires or miniplates.

Closure of Incisions

The authors close the transfixion and the sub-labial incisions with 3-0 chromic catgut. The vestibular incisions are closed with 4-0 chromic catgut. The nose is taped and a light cast applied, Nasal packings are removed on the third day and the cast on the fifth day.

CASE 1

A 14-year-old boy presented with a large juvenile nasopharyngeal angiofibroma involving the cavum, sphenoid sinus, infratemporal space, and temporal fossa, with intracranial invasion (Fig. 15). The tumor was removed through a degloving procedure and transmaxillary approach (Figs. 16-18).



FIG. 15. Computed tomography scan of patient from case 1. *Arrows* indicate tumor in temporal fossa.



FIG. 16. Surgical specimen of juvenile nasopharyngeal angiofibroma removed from patient from case 1. with its various extensions.



FIG. 17. Preoperative magnetic resonance image of patient from case 1. *Arrows* indicate extradural temporal lobe compression.



FIG. 18. Postoperative magnetic resonance image of patient from case 1, showing no brain compression. *Arrow* indicates normal brain position after lesion removal.

COMBINED SURGERY

The degloving/transmaxillary procedure can be combined with other approaches if the lesion extends toward the orbit. frontal sinus, or anterior or medial cranial base. To protect the orbit, optic nerve, cribriform plate, superior orbital fissure, and dura mater, safe landmarks are needed.

External Ethmoidectomy with Degloving

Ethmoid-sphenoid osteomas can be removed using periorbital and ethmoid neurovascular pedicles as landmarks to protect the periorbita and optic nerve. The remaining tumor is easily removed using degloving and a transmaxillary approach.

A 20-year-old white man presented with nasal obstruction/There was a large osteoma in the right nasal fossa and maxillary, ethmoid, and sphenoid sinuses, with orbital compression (Fig. 19). The osteoma was removed by an external ethmoidectomy-sphenoidectomy using a degloving procedure and a transmaxillary approach (.Figs. 20-22).



FIG. 19, Case 2. Axial computed tomography scan of large osteoma of right nasal fossa and ethmoid, sphenoid and maxillary sinuses *(star}.*



FIG. 20. Case 2. External ethmoidectomy-sphenoidectomy with orbital decompression and tumor removal *(star).*



FIG. 21. Case 2. Combined degloving and removal of remaining paranasal sinus osteoma *(star);* note inner canthus incision *(arrow).*



FIG. 22. Case 2. Postoperative coronal computed tomography scan; note inferior turbinate *(asterisk).*

External Frontoethmoidectomy with Degloving

Extensive, recurrent inverted papilloma can be totally removed with preservation of orbital structures and the cribriform plate and the opportunity of reconstructing the frontonasal duct.

CASE 3

A 45-year-old white man had an inverted papilloma removed from his left maxillary sinus by another physician. He subsequently had intranasal recurrence, frontal sinusitis, and a left orbital fistula (Fig. 23).

Magnetic resonance imaging revealed frontal sinus involvement with an abscess draining into the orbit (Fig. 24). An external frontoethmoidectomy associated with a degloving/transmaxillary approach was used to remove the tumor and treat the frontal sinus infection.



FIG. 23. Case 3. Patient with recurrent inverted papilloma, frontal sinus invasion, and chronic sinusitis with orbital fistula (arrow).



FIG. 24. Case 3. Magnetic resonance image showing papilloma invasion of frontal sinus *(star),* lamina papyracea erosion *(asterisk?),* and orbital fistula *(arrow).*

Anterior Craniotomy and Degloving

The authors use an anterior subcranial approach alone that encompasses one or both superior orbital rims, with a low glabellar cut and frontal sinus cranialization, to ablate osteomas, chondrosarcomas, high clivus chordomas, and esthesioneuroblastomas. If the maxillary sinus or lateral orbital fissure is involved, degloving and transmaxillary surgery can be combined with anterior or middle craniotomy for safe tumor removal.

CASE 4

A 30-year-old white woman presented with a history of loss of vision in the right eye and proptosis with nasal obstruction. Visual evoked potential examination showed signs of optic nerve involvement. Computed tomography demonstrated osteoma of the sphenoid and maxillary sinuses (Fig. 25), and magnetic resonance imaging showed middle fossa invasion (Fig. 26). A subcranial craniotomy and degloving procedure were necessary for total tumor removal and orbit and optic nerve decompression with vision improvement (Figs. 27, 28).

CASE 4 (Continued)



FIG. 25. Case 4. Large osteoma *(star)* involving maxillary sinus, orbit, and right nasal fossa.



FIG. 26. Case 4. Magnetic resonance image showing middle fossa invasion *(arrow)* by osteoma *(star).*



FIG. 27. Case 4. Axial computed tomography scan after surgical removal of osteoma. The *asterisk* indicates the previous site of osteoma.



FIG. 28. Case 4. Postoperative axial computed tomography scan showing complete osteoma removal. *Arrow* indicates bone defect in infratemporal fossa.

CASES

A 49-year-old white man presented with an inverted papilloma of the left nasal fossa and paranasal sinuses and a history of multiple Caldwell-Luc operations. He had undergone bilateral external frontal surgery, a left Weber-Fergusson incision, and sinus surgery in Boston, Massachusetts, with persistence of tumor and a left dacryocystitis (Fig. 29). Magnetic resonance imaging showed bilateral frontal sinus papilloma, meningioma (Fig. 30), residual nasal fossa papilloma, chondroma of the sphenoid sinus, and brainstem hemangioma (Figs. 31, 32). A subfrontal craniotomy and degloving/transmaxillary approach with frontal sinus cranialization allowed total tumor removal, except for the brainstem lesion (Figs. 33, 34). A dacryocystorhinoslomy corrected the lacrimal drainage obstruction in a second operation.

CASE 5 (Continued)



FIG. 29. Case 5. Patient after multiple pansinus operations (bilateral Weber-Fergusson and frontoethmoidectomies) with residual inverted papilloma and dacryocystitis *(asterisk). Arrows* indicate facial scars.



FIG. 30. Case 5. Recurrent inverted papilloma of nasal fossa and frontal sinus *(asterisk),* frontal meningioma *(star),* and chondroma of sphenoid sinus (arrow).



FIG. 31. Case 5. Cystic lesion of intranasal fossa—recurrent inverted papilloma *(star).* Chondroma *(asterisk)* in sphenoid sinus.



FIG. 32. Case 5. Inverted papilloma in cystic bony wall *(asterisk)* with frontal sinus involvement, chondroma of the sphenoid sinus *(star),* and asymptomatic angioma of the brain-stem *(arrow).*

CASE 5 (Continued)



FIG. 33. Case 5. Postoperative axial computed tomography I scan after total tumor removal. Sfanndicates sphenoid sinus.



FIG. 34. Case 5. Sagittal postoperative magnetic resonance image showing removal of frontal bone meningioma, inverted papilloma, and sphenoid sinus chondroma. Note persistence of brainstem angioma *(arrow).*

CASE MATERIAL

The authors have used the degloving procedure/transmaxillary approach, alone or combined with other procedures, for a variety of lesions:

Juvenile nasopharyngeal angiofibroma	41
Inverted papilloma	7
Osteoma	8
Fibrous dysplasia	6
Osier-Weber-Rendue (septal dermoplasty)	2
Septal tumors	
Neurogenic tumor	1
Hemangiopericytoma	1
Malignant fibromatosis	1
Trigeminal neuroma	3
Clival chordoma	1
Chondroma	1
Clival chondrosarcoma	6
Aneurysmatic bone cyst	1
Clival giant cell tumor	1
Branchial hypertrophic myositis of masticator muscles	1
Aesthesioneuroblastoma	3

CONCLUSION

The degloving/transmaxillary approach to lesions of midface structures, the orbits, and the anterior and middle cranial base, alone or in combination with other procedures, is highly satisfactory to surgeon and patient alike.

It carries a very small morbidity and no visible scars for the patient. For the surgeon, it allows a bilateral midface approach with comfortable surgery even with large bleeding tumors (e.g., juvenile nasopharyngeal angiofibroma) or extensive and deeply located tumors.

Access to the anterior and middle cranial base (by degloving alone or in surgical combinations) can be readily accomplished with safe tumor removal and reconstruction.

This procedure has been successfully used in the authors' clinic for removal of large juvenile nasopharyngeal angiofibromas with invasion of the middle fossa and cavernous sinus. In the authors' opinion, in such cases there is no need for craniotomy because most of the lesions are extradural.

Even for ablation of selected malignant tumors, it is the authors' opinion that the head and neck oncologist could use this approach more frequently.

продолжение

продолжение

REFERENCES

1. Converse JM. Restoration of facial contour by bone grafts introduced through the oral cavity. *Plast Reconstr Surg* 1950;6:295.
2. Denker A, Kahler O. *Handbuch der Hals Nasen Ohren Heilkunde.* Berlin: Springer-Verlag, 1926.
3. Portmann G, Retrouvery H. *Le cancer du nez.* Paris: Gaston Doin etcie. 1927.
4. Williams RI. Utilization of rhinoplastic technique: hemilateral rhinotomy for the removal of intranasal tumors. *Laryngoscope* 1957;67: 796-814.
5. Casson PR, Bonano PC, Converse JM. The midface degloving procedure. *Plast Reconstr Surg* 1974;53:102-113.
6. Alien G, Siegel G. The sublabial approach for extensive nasal and sinus resection. *Laryngoscope* 1981 ;91:1635-1639.
7. Conley J, Price J. Sublabial approach to the nasal and nasopharyngeal cavities. *Am J Surg* 1979;138:615-618.
8. Maniglia AJ. Indication and techniques in midfacial degloving: a 15 years experience. *Arch Otolarvngol Head Neck Surg* 1986;! 12: 750-752.
9. Price I, Holliday M, Kennedy D, Johns ME, Richtsmeier WJ, Mattox DE. The versatile midface degloving approach. *Laryngoscope* 1988:98: 291-295.
10. Paavolainen M, Malmberg H. Sublabial approach to the nasal and paranasal cavities using nasal pyramid osteotomy and septal transection. *Laryngoscope* 1986;96:106-108.

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 12

Extended Unilateral Maxillotomy Approach

Edwin W. Cocke, Jr. andjon H. Robertson

In this chapter, a technique for surgical exposure of the extracranial skull base for the removal of craniocervical lesions from the roof of the sphenoid to the fourth cervical vertebra and between the carotid canals is described in detail. Additional techniques and modifications of the original technique first described by the authors in 1990 are included. The authors' experience with 30 patients, from which the techniques have been refined, is discussed. Compared with the authors' earlier experiences, the complication and morbidity rates have diminished. A brief history is provided, and indications, preoperative and postoperative management, technique, complications, advantages, disadvantages, and comments identifying specific patient management are discussed.

The successful management of patients with skull base lesions depends on a thorough knowledge of the regional anatomy and the biologic nature of the conditions that may involve the area, as well as the accuracy of the diagnosis, the anatomic extent of the disease, and an understanding of a multitude of treatment modalities that may be expected to provide maximum relief for these patients. A multidisciplinary approach is commendable. The authors' team consists of a neurosurgeon, an otolaryngology-head and neck surgeon, an oral surgeon, and an anesthesiologist.

The authors describe an extended maxillotomy technique for skull base exposure that has proved satisfactory in their supervision of 30 patients. Techniques for improved patient care and improvements of the authors' surgical technique, permitting exposure from the roof of the sphenoid to the fourth or fifth cervical vertebra and reported in 1990 (1), are described. These improvements have resulted in additional skull base exposure and access for dural closure, facilitation of maxillary osteotomies, improved cosmesis, and a reduction in patient morbidity. Additional surgical options and expansion of the procedure, as well as the indications, advantages, disadvantages, and complications of the procedure, are discussed.

HISTORY

The original bilateral horizontal maxillary osteotomy technique was described by von Langenbeck in 1859 (2,3). He presented a case report in the medical literature in 1861 using the same technique to remove "fibroids of the pterygopalatine fossa." Cheever (4) is given credit for using in 1867 the same approach for the removal of a tumor in the nasopharynx in two patients. One patient had an incomplete unilateral horizontal maxillary osteotomy for removal of an angiofibroma; the other had an incomplete bilateral horizontal maxillary osteotomy for removal of a tumor that was not histologically diagnosed (5).

In 1893, Lanz (6) gave an account of an operation developed earlier by Kocher. The upper lip was divided in the midline as well as the maxilla. This was his palatal osteomyotomy contribution to von Langenbeck's bilateral horizontal maxillotomy, and represents an osteotomy in two sections. In 1898, Partsch (7) reported a technique for temporary mobilization of the upper jaw and eliminated Kocher's lip-splitting incision. In 1901, LeFort (8) classified facial fractures, including the LeFort I midface fracture. This fracture was described as passing through the nasal pyriform aperture transversely, the inferior meatus, the canine fossa to below the buttress of the zygoma, and along the antral wall to the pterygomaxillary fissure. It passed through the lower third of the pterygoid plates and separated the tooth-bearing upper maxilla from the cranial base. Loewe in 1902 (9) outlined a historical summary of the surgical techniques involving the superior maxilla. The basic concept of temporary mobilization and inferior displacement of the upper maxilla for the removal of a nasopharyngeal polyp was described by Pincus in 1907 (10). In 1927, Martin Wassmund performed a LeFort I

E. W. Cocke, Jr.: Department of Otolaryngology, Head and Neck Surgery, The University of Tennessee, Memphis, The Health Science Center, Memphis, Tennessee 38103.

J. H. Robertson: Department of Neurosurgery, The University of Tennessee, Memphis, The Health Science Center, and Semmes-Murphey Clinic, Memphis, Tennessee 38103.

osteotomy for correction of malocclusion, and reported the operation in the medical literature in 1935 (11). Numerous other authors have made contributions to this subject since 1934, including Axhausen in 1934 (12), Steinkamm in 1938 (13), Gillies and Rowe in 1954 (14), Dingman and Harding in 1951 (15), Cupar in 1952 (16), Obwegeser in 1962 to 1970 (17), Hogeman and Willmar in 1967 (18), and Pfeifer in 1969 (19). These historical events are beautifully described by Drommer in "The History of the LeFort I Osteotomy" (20). He makes the observation that the LeFort I osteotomy was reported 130 years before his (Drommer's) publication, and 80 years elapsed before it became a part of the surgical treatment of skeletal facial deformities, including management of the patient with cleft palate.

At the beginning of their experience in 1986, the authors were called on by a neurosurgeon to expose the skull base in a patient whose chordoma of the skull base had been incompletely removed on two previous occasions by conservative procedures. A subtotal maxillectomy through a Weber-Fergusson skin incision was carried out, along with removal of the lateral nasal wall, ethmoidectomy, and posterior nasal septectomy. After removal of the chordoma, the subsequent palatal defect was closed with an appropriate obturator. The skull base exposure was quite adequate. In selected patients with advanced disease, the surgeon still might consider it as the procedure of choice.

The authors conceived that perhaps the same surgical exposure could be obtained by mobilizing the homolateral maxilla below the level of the inferior orbital nerve and retracting the maxilla while preserving the nerve. They were concerned that the blood supply to the maxilla might be compromised, and designed a technique to preserve the attachment of the mucoperiosteum of the entire hard palate to the bone. The authors subsequently discontinued their efforts to maintain this attachment when it became obvious that it was perforated in the midline on numerous occasions, and the hard palate survived presumably from the blood supply it received only from its soft palate connection. The angiographic and radioactive microsphere studies, respectively, of Bell et al. (21-23) and Nelson et al. (24), and the clinical information obtained by Lanigan, an orthognathic surgeon, and his team (25), added to the authors' knowledge of the blood supply to the maxilla. As a result of these experiences, the authors now approach the skull base through a unilateral horizontal maxillary osteotomy with a modified LeFort I exposure (maxillotomy) that does not include a midline soft palate myotomy. The maxilla is divided through the middle meatus. The Weber-Fergusson incision has been discontinued except when the oral commissure is very small or the teeth too long. The upper lip is then divided in the midline. The incision may be extended laterally to beyond the nasal alar. The authors approach the maxilla through the sublabial transoral degloving technique (26-29) to expose not only the extracranial central and lateral compartments of the skull base, but the infratemporal fossa. This exposes the craniocervical region from the roof of the sphenoid sinus to the fourth or fifth cervical vertebra, between the eustachian tubes, carotid canals, hypoglossal canals, and condyles of the occipital bone that are adjacent to the anterior and lateral margins of the foramen magnum. This exposure is accomplished by dividing the lateral margin of the nasal pyriform aperture, removing the entire lateral wall of the nose above the middle meatus, the ethmoid and sphenoid sinuses, the posterior half of the nasal septum, sometimes the coronoid process of the mandible, and the pterygoid plates, without disturbing the cranial end of the ascending process of the maxilla. The maxilla with the lower half of the body of the zygoma is retracted inferiorly, medially, or laterally to gain adequate skull base exposure. Additional extension of the procedure with cervical spine exposure requires division and retraction of the soft tissues lateral to the palatine tonsil and its tongue base attachment. In the depths of this defect is the prevertebral fascia. The tonsil, anterior and posterior tonsil-lar pillars, superior constrictor muscle, soft palate, and maxilla are retracted toward the midline. As the degloving exposure is advanced, almost the entire zygoma may be exposed, and it can be temporarily removed and replaced. The bony foramen about the infraorbital nerve may be microfrag-mented and the nerve mobilized from its infraorbital canal, retracted, and elevated with the degloved soft tissues to a higher level. With preservation of the adjacent orbital periosteum, additional orbital floor may be divided, and the soft tissue retracted for additional exposure.

Gigli saw division of the maxilla continues to play a major role in the authors' technique. Other options for division of the maxilla have been developed.

The bilateral horizontal maxillary osteotomy with preservation of the soft palate and with a LeFort I exposure has been the procedure of choice for many skull base surgeons. The surgical literature includes reports by Wood and Stell in 1984 (30) and Archer et al. in 1987 (31). Belmont in 1988 (32) was concerned that the blood supply to the osteotomized maxilla would not be adequate. Additional experience with the bilateral osteotomy was reported by Uttley et al. (33) and Brown in 1989 (34), and Morril et al. in 1993 (35). The bilateral horizontal maxillary osteotomy with complete division of the maxilla and the soft palate in the midline has been described by Sasaki et al. (36) and Sandor et al. (37) in 1990, James and Crockard (38) and Anand et al. (39) in 1991, and O'Reilly et al. in 1993 (40). In 1990, the authors' team reported their experience with three patients with chordomas of the clivus (1). The tumors were resected by subtotal maxillectomy in two patients and a unilateral horizontal maxillary osteotomy in one patient. In the latter patient, the soft palate and the mucoperiosteum of the hard palate bilaterally remained intact. In 1993, Catalano et al. (41) reported a three-fourths horizontal maxillary osteotomy with preservation of the hard palate mucoperiosteum and the soft palate attachments.

Since 1990, the authors' approach in 30 patients for the removal of skull base tumors has been through a unilateral horizontal maxillary osteotomy (maxillotomy) with preserva-non of the soft palate attachment to the maxilla. The blood supply to the maxilla has been adequate even when the maxilla with its mucoperiosteum is divided in the midline. The maxilla and soft palate also survive if the soft palate is divided laterally beyond the anterior tonsillar pillar and tonsil, division of the superior pharyngeal constrictor muscle, retraction of the retropharyngeal tissues, and exposure of the prevertebral fascia. With this additional exposure, the surgeon must be prepared to accept a unilateral motor weakness of the adjacent soft palate.

INDICATIONS

Numerous techniques have been described to manage lesions involving the skull base. The appropriate procedure for each patient varies, as well as the objective that is to be accomplished. This objective depends on several factors, including familiarity and experience with these techniques as well as knowledge of the regional anatomy, the location, extent. size, and consistency of the tumor, and the histologic diagnosis. An understanding of the natural history of the specific disease process may influence the surgeon's decision only to biopsy the tumor or to withhold treatment in the face of an asymptomatic, slow-growing neoplasm, one that has invaded the carotid artery, or one that is refractory to radiation therapy and unresectable.

Limited access rarely permits total excision. Extracranial tumors of the middle and posterior cranial fossae require extracranial procedures. Midline skull base tumors, most lateral compartment tumors, and clival tumors involving the dura require a maxillotomy. In the authors' opinion, it is unlikely that a tumor that crosses the midline can be resected through a lateral approach, as described by Fisch et al. (42). Tumors involving bone are rarely completely removed.

The extended maxillotomy was originally designed for the removal of chordomas at the skull base. Craniospinal lesions treated by mid-skull-base approaches are listed in Table 1.

A full review of the advantages of the maxillotomy is presented later, but these advantages suggest that the indications for this operation may be extended. For these and other reasons, the extended maxillotomy may be selected as the procedure of choice.

It is rare for this approach to be selected for the correction of bony abnormalities of the skull base. Although it produces excellent exposure, more conservative procedures are preferred.

The unilateral horizontal maxillotomy (extended maxillotomy) is an excellent approach for conditions that extend between the roof of the sphenoid and the fourth cervical vertebra, between the eustachian tubes, carotid arteries, petrooccipital fissures, hypoglossal foramina, and the occipital condyles. Most frequently, the surgical procedure is performed on the side corresponding to the tumor. In rare instances, the contralateral maxilla is mobilized and retracted inferiorly for maximum exposure of lesions that primarily involve the contralateral occipital condyle and hypoglossal foramen and nerve. This approach takes advantage of a surgical exposure that permits manipulation of instruments and the operating microscope to work at an extreme angle, in contrast to the usual anteroposterior working relationship. If the extent of the disease can be anticipated, treatment may be designed for incomplete removal and palliation only, or for cure with an attempt to remove the tumor completely. Complete extirpation is rarely, if ever, accomplished. Postoperative radiation therapy may be advantageous if the tumor has been incompletely removed and is radiosensitive.

The best results are obtained when the tumor is benign, well encapsulated, exophytic, noninfiltrative, slow growing, has a pushing border, and is extradural. The clival dura may

TABLE 1. *Craniospinal lesions treated by mid-skull base approaches*

Benign tumors
Angiofibroma
Chondroma
Chordoma
Craniopharyngioma
Fibrous dysplasia
Hemangioma
Hemangiopericytoma
Lymphangioma
Meningioma
Neurilemoma
Neurofibroma
Ossifying fibroma
Osteoblastoma
Osteochondroma
Osteoclastoma
Osteoma
Paraganglioma
Pericytoma
Pituitary adenoma
Schwannoma
Teratogenic cyst (brainstem)
Malignant tumors
Acinic cell adenocarcinoma
Adenocarcinoma
Adenoid cystic carcinoma
Carcinoma
Chondrosarcoma
Chordoma
Epidermoid (x-ray resistant)
Fibrous histiocytoma
Olfactory neuroblastoma
Plasmacytoma
Rhabdomyosarcoma
Sarcoma
Other lesions
Aneurysm
Arthritis (rheumatoid)
Atlantoaxial dislocation
Basilar impression
Craniospinal malformation
Fracture with dislocation (odontoid)
Meningocele

or may not be involved, but if so, it is easily removed without damage to a compressed brainstem. A complete clival craniectomy is usually required along with limited removal of the extracranial disease. Benign tumors involving the middle and lateral compartments of the skull base, as well as the infratemporal fossa, lend themselves more frequently to complete removal. The improvement in cure rates is directly related to the completeness of removal and extent of the resection at the time of the first operation. Secondary procedures are more hazardous. The complication rate is increased and the survival rate is reduced. The extended maxillotomy may be repeated for the removal of residual disease.

The poorest results are obtained when the tumor is malignant, without a capsule, aggressive, infiltrative, and invading the multiple foramina and crevices at the skull base. In most instances, these tumors cannot be completely removed with a good margin of normal tissue without seriously threatening the life of the patient.[1] These infiltrative tumors may occur as a result of radiation failure. In other instances, the patient may be given postoperative therapy for a primary tumor that may have been incompletely removed.[2]

This approach offers excellent access for reconstruction of the surgical defect. Nasal septal and temporalis muscle flaps are frequently rotated to cover dural defects. These may be unnecessary when the dural defect is closed watertight with interrupted sutures or with a sutured fascial graft and reinforced with bilateral nasoseptal mucoperiosteal flaps.

PREOPERATIVE MANAGEMENT

Before surgery, the patient is thoroughly evaluated by state-of-the-art techniques to determine his or her general physical condition, the diagnosis, and the anatomic extent of the disease. This frequently requires high-resolution computed tomography and magnetic resonance imaging scans with contrast and, in rare instances, an arteriogram. Not only may the surgeon have the opportunity to study the adequacy of carotid arterial function, but he or she may also consider whether embolization of a part of this system would be advantageous to reduce the degree of operative blood loss. These findings are presented to the surgeons and anesthesiologists involved so that a carefully planned approach may be developed.

Unless the patient is preoperatively dependent on a tracheostomy, percutaneous esophageal gastrostomy, or a nasogastric feeding tube, the authors have discontinued their use except in rare instances.

Antibiotic coverage consists of a cephalosporin and an aminoglycoside that are administered the day of surgery.

In the operating room, the head and neck are washed with an antiseptic soap and cleansed with alcohol. Table 2 lists equipment that should be available before surgery to prepare the operative sites. Table 3 lists selective surgical equipment that should be available for each operation and should be checked before surgery.

TABLE 2. *Equipment for preoperative preparation of operative sites*

1. Head light
2. Betadine soap
3. Alcohol
4. Sponges
5. Cottonoid tapes (small and large) a.
   Vaseline b. Dry
6. Bayonet forceps
7. Nasal specula (three lengths)
8. Solution on cottonoid to nose for nasal mucous
   membrane shrinkage a. 4% Cocaine and 1% Neo-synephrine solution
9. Nasal injection
   a. 1% Lidocaine with 1:100,000 adrenaline
   b. 10-ml syringe
   c. 25-gauge 2-in. needle
   d. 25-gauge spinal needle
   e. Tonsil needle
10. Mouth retractors a.
    Jennings b. Mclver c.
    Metal tongue blade
11. Suction a. Yankauer
    b. Neurosurgical
12. Retractors a.
    Richardson i. Wide ii.
    Narrow b. Senturia
    (palate) c. Love
    (palate)
13. For temporary tarsorrhaphy a. 6/0
    Ethicon nylon b. Needle holder, small
    c. Tissue forceps and scissors
14. Vaselinized cottonoid sutured to lips a. #1
    Silk with needle
15. To shave scalp, abdomen, and thigh in selected patients a.
    Razor b. Electric clipper
16. For myringotomy and insertion of pressure ventilating tube
    a. Operating microscope x300 lens
    b. Shepard tube
    c. Ear suction
    d. Forceps
    e. Myringotomy knife

Equipment for sterile set-up

1. Betadine
2. Alcohol
3. Sponge
4. Towels
5. Drapes for head, abdomen, and thigh
6. Transparent drapes a. Face
   b. Microscope c. With
   irrigating container

[1] **Editor's note:** *These cases are not perhaps suitable for a purely subcranial approach and will be more effectively resected by some of the other intracranial/extracranial approaches described in this book.*

[2] **Editor's note:** *This may provide palliation, but rarely a cure.*

TABLE 3. *Selected operating instruments*

1. Rhinoplasty and septoplasty instruments a.
   Pierce elevator, button knife, Joseph knife b.
   Nasal scissors
2. Paranasal sinus instruments
3. Tonsil instruments
4. Retractors a.
   Richardson i. Broad ii.
   Small iii. Narrow b.
   Deaver, narrow
5. Mouth retractors a. Jennings
   b. Mclver c. Senturia d.
   Love e. Crockard f. Leylar
   g. Fish hooks h. Small and
   large rake
6. Cottonoids (all sizes)
7. For bleeding a. Bipolar
   cautery b. Bovie cautery c.
   Stick ties (3-0 chromic) d.
   Surgicel
   e. Gelfoam soaked in thrombin f.
   Wax for bone g. Clips, small, and
   applicator h. Adrenal water (half-and-half)
8. Suctions
   a. Small and large Yankauer
   b. Neurosurgery (suction, irrigation, ultrasonic
   aspirator) c.
   Electrosuction
9. Knives
   a. Bard-Parker b.
   Electro (Shaw)
10. Red rubber catheter
11. Rongeurs
   a. Double action (large) b.
   Kerrison c. Needle-nose d.
   Kofler
12. Forceps a. Bayonet b.
   Brunning c. Sphenoid
   d. Tissue e. Pituitary
   (pullers)
13. Drill
   a. Midas with points, high-speed
14. Wire carrier a. Orthopedic b. Tuohy needle #14 (prepared
   before operation and
   ready for use) i.
   Medicine glass
   c. 9-in. curved broad ligament clamp
   d. Curved, sharp-pointed large thyroid ligature carrier
15. Wire #22 and cutter
16. Urethral sound #22 and smaller
17. Saws
   a. Four new Gigli saws (noncurled)
   b. Reciprocating
   c. Stryker with small blade
18. Suture
   a. 2-0 Vicryl
   b. 3-0 Chromic gut
   c. 4-0 Plain on Keith needle (pc 3), short, long needles
19. Chisels a. Straight b.
   Curved c. Narrow d.
   Broad e. Mastoid
   gouge
20. Dressing
   a. Nasal splint
21. Ice in glove (2)
   a. Apply during and after operation
22. Elevators a.
   Narrow b.
   Large c.
   Lempert d.
   Sharp e.
   Blunt
23. Hooks a. Nasal i.
   Single ii. Double
   iii. Sharp iv. Blunt
   b. Fibroid hook, single c.
   Fish hooks
24. Miniplates
25. Dermatome
26. For abdominal fat removal a.
   Rake retractor
27. Laser, CO_2
28. Operating microscope
   a. x 400 lens for neurosurgery
29. Scissors
   a. Curved Mayo b. Suture c.
   Dissection i. For nose ii. For
   abdominal fat
30. Neurosurgical instruments a. Nerve
   stimulator b. Fluoroscope with C-arm
   attachment

A *1%* lidocaine solution containing 1:100,000 epinephrinc is injected into the area to be operated on after shrinkage of the nasal mucous membranes with cottonoid strips saturated with 4% cocaine and 1% phenylephrine hydrochloride (Neo-Synephrine). Special attention is given to injecting the lining of the interior of the nose, each greater palatine canal, the hard palate mucoperiosteum. the anterior and posterior ethmoid arteries, the posterior and lateral nasopharyngeal walls, and the soft tissues of the cheek, pterygoid region, and the lines of incision.

If a temporalis muscle flap for reconstruction of the skull base is anticipated, the homolateral scalp is shaved. This area, as well as the face, neck, abdomen, and homolateral thigh, is shaved and cleansed with povidone-iodine (Betadine) and dried with alcohol preparatory to harvesting abdominal fat or a split-thickness skin graft for reconstruction.

A bilateral temporary tarsorrhaphy is performed and an indwelling urethral catheter is inserted.

The patient is given general anesthesia. An oral endotracheal tube is introduced and made to exit from the contralateral side of the mouth, and is sutured into place.

Appropriate drapes are applied, and a large vaselinized cottonoid strip is made to cover the entire lip surface. It is sutured in *place* to protect this area from injury thai could develop from instruments used for electrocoagulation and retraction. Automatic compression stockings are applied.

In the event trauma to the eustachian tube is anticipated, a homolateral myringotomy and insertion of a pressure ventilating tube dirough the tympanic membrane is accomplished.

TECHNIQUE

The superior maxilla is exposed by a degloving technique. In the authors' experience, this technique has replaced the Weber-Fergusson incision. Not only is this surgical exposure just as satisfactory as the latter incision., but facial scarring is eliminated. It may be necessary to divide the upper lip to the alar crease in exceptional cases when the oral commissure is very small or when the teeth are exceptionally long.

Nasal Exposure

Exposure of the interior of the nose is by a standard rhinoplasty technique. One or both nasal cavities may be exposed, depending on the extent of the degloving incision. Usually the exposure is bilateral (Fig. 1).

A complete transfixation incision is used. This incision is extended infcriorly to the nasal floor and is continued through its lateral wall anterior to the bony pyriform aperture. Care is taken to leave a few millimeters of redundant mucous membrane anterior to the bony nasal floor and pyriform aperture to assist in subsequent closure of the defect.

An intercartilaginous incision is extended lo join the initial incisions, resulting in a complete circumferential anterior intranasal incision. Through these incisions, the skin and subcutaneous tissues on the nasal dorsum may be unilaterally or bilaterally elevated to the nasofrontal suture. The periosteum remains attached to the bone and is not elevated.



FIG. 1. Bilateral circumferential intranasal incisions.

Hard Palate Exposure

A vertical incision in the anteroposterior direction is made through the mucoperiosteum of the hard palate several millimeters to the contralateral side of the rnidline from the junction of the hard and soft palate to the interdental space between the central incisor teeth. The adjacent mucoperiosteum is elevated a few millimeters on each side of the incision to permit ease in subsequent closure (Fig. 2).

Through this incision, at the junction of the hard and soft palate on the homolateral side of the midline, the soft tissues are detached from the posterior margin of the hard palate to gain entrance into the nasopharynx. This defect should be large enough only to manipulate one arm of the lower Gigli saw into position.

Construction of Intranasal Flap

The mucoperiosteum of the posterior half of the nasal floor on the side of the lesion is elevated, including the dorsal lining of the soft palate. This is extended laterally to elevate the mucoperiosteum from the lateral wall of the nose to the level of the attachment of the inferior turbinate in its posterior half (Fig. 3A). The mucoperiosteum is divided hori-


Nasal dorsum
Inferior orbital rim
Infraorbital nerve
Intranasal flap incision
Zygoma perforation
Bipedicled mucoperiosteal maxillary flap (optional)
Masseter muscle retraction
Lateral pterygoid plate
Coronoid process of mandible
Anterior tonsillar pillar
Sublabial incision
Detachment of soft tissue from nasal pyriform aperture
Drill holes for mini-plates
Buccal fat
Hard palate mucoperiosteal incision (contralateral)
Hard palate bony incision (homolateral) for osteotomy
Palate perforation

EXTENDED UNILATERAL, MAXILLOTOMY APPROACH

FIG. 2. A degloving technique is used for homolateral and bilateral exposure of the anterior maxilla, nose, masseter muscle, coronoid process of the mandible, lateral pterygoid plate, and zygoma. Construction of the bipedicled maxillary mucoperiosteal flap is optional. The mucoperiosteum of the hard palate is divided vertically in an anteroposterior direction on the contralateral side of the midline. A palate perforation into the nasopharynx is created to accommodate the lower Gigli saw.

zontally in the inferior meatus on the lateral wall of the nose from its incision site anteriorly to its posterior extent immediately below the attachment of the inferior turbinate. This dissection is extended medially to elevate the mucoperiosteum from the homolateral nasal floor and nasal septum (see Fig. 3).

The anterior septal mucoperichondrium and cartilage are allowed to remain attached to the maxillary crest, nasal spine, septal cartilage, and the distal margin of the nasal bone. This will avoid a saddle nasal deformity should the cartilage support be removed. To accomplish this, a vertical incision is made at the junction of the perpendicular plate of the ethmoid and the posterior margin of the septal cartilage from the cribriform plate superiorly to the nasal floor and the lateral nasal wall in the inferior meatus interiorly. Posterior to this incision, the adjacent vomer and the perpendicular plate of the ethmoid are removed to the anterior face of the sphenoid. The contralateral septal soft tissues may also be preserved. The remainder of the cartilaginous nasal septum remains attached to the maxillary crest and adjacent nasal spine anteriorly.

The primary superior attachment of the intranasal flap is at the level of the cribriform plate. This attachment is divided transversely beneath the cribriform plate from its anterior to its posterior extent so that subsequently the flap may be elevated from the anterior wall of the sphenoid and rotated posteriorly. It remains pedicled to the soft tissue at the lateral margin of the sphenoid. The flap is designed to cover a subsequent sphenoclival defect where the dura has been closed. The *adjacent* clival defect may have been packed *with fat*, muscle, or bone. The surgeon may elect not to use this intranasal flap, which consists of mucoperiosteum originating from the lateral wall of the nose in the inferior meatus, the floor of the nose, the adjacent posterior nasal septum, and the anterior face of the sphenoid. A similar septal flap may be constructed from the opposite side of the septum to supplement coverage of the sphenoclival defect.

Anterior Maxillary Exposure

The gingivobuccal gutter is exposed and a transverse sublabial incision is made high in its apex through its oral mucoperiosteum from a point 2 cm lateral to the midline. to the homolateral retromolar region and into the anterior tonsillar pillar well lateral to the palatine tonsil (see Fig. 2).

Another 3-cm transverse mucoperiosteal anterior maxillary incision 2 cm beneath the apex incision is made adjacent


Inferior meatus
Nasal septum
Nasal floor
Nasal flap components
A
Sphenoid
Nasal flap pedicled attachment
Cribriform plate
Nasal bones
Anterior septal incision
Maxillary crest
B
Posterior nasal septum
Intranasal flap septal component
Retracted maxilla and zygoma
Intranasal flap pedicled attachment
Roof maxillary sinus
Sphenoid sinus
Pterygoid base
C

FIG. 3. Transnasal flap construction. **A:** Elevation of mucoperiosteum from lateral wall of nose in the inferior meatus, nasal floor, and septum. **B:** Septal component of the nasal flap detached from the posterior nasal septum beneath the cribriform plate and pedicled lateral to the sphenoid. **C:** Intranasal flap construction continues after the maxillotomy exposure. The flap has been elevated from the lateral inferior meatal wall, floor of the nose, and the posterior nasal septum.

to the central incisor teeth. This 2-cm-wide bipedicled mucoperiosteal flap is elevated from the maxilla and will serve as a hinge for rotation of the maxilla after the maxillary osteotomy. It may be centrally divided if manipulation of the flap or the maxilla is troublesome.

The cheek flap, consisting of skin, subcutaneous tissue, periosteum, and oral mucosa, is elevated from the anterior maxilla to the level of the infraorbital nerve and the inferior rim of the orbit, exposing the zygoma and its masseter attachment, as well as the lateral wall of the maxilla to the pterygoid plate. Medially, these tissues are elevated from the nasal dorsum to the nasofrontal suture and detached from the nasal pyriform aperture so that enough of its adjacent soft tissue will be preserved to permit closure of the defect at the completion of the operation.

Exposure of the Lateral Wall of the Maxilla, Lateral Pterygoid Plate, and Internal Maxillary Artery

The masseter muscle is detached from the body of the zygoma to its arch. Retraction of the masseter muscle exposes the coronoid process of the mandible. For additional exposure, the coronoid is usually removed to the level of the mandibular foramen with a large rongeur after division of its temporalis muscle attachment. Not only is exposure increased by removal of the coronoid, but it facilitates ligation of the internal maxillary artery and creation of a bony soft tissue tract behind the maxilla through which a Gigli saw is passed to divide the maxilla. It does not lead to limitation of jaw mobility any more than if it was not removed (Fig. 4).

With the head extended, buccal fat is removed to expose or palpate the lateral pterygoid plate. The lateral pterygoid muscle is electrocoagulated and detached from its insertion on the lower half of the lateral pterygoid plate and maxilla, with care taken to identify the internal maxillary artery. Exposure with a long Richardson or narrow Deaver retractor is helpful. The numerous veins in the area are exposed and compressed with cottonoid sponges and a large Yankauer suction. They are electrocoagulated as the internal maxillary artery is mobilized; the artery is usually identified in the upper third of the pterygomaxillary fissure deep to the attachment of the lateral pterygoid muscle to the greater wing of the sphenoid, and above the attachment of the lateral pterygoid muscle to the lower half of the lateral pterygoid plate. The artery is below the sometimes palpable infratemporal crest, and travels transversely. It lies above the foramen ovale in the pterygomaxillary fissure and must be differentiated from the mandibular nerve. Its viable posterior segment contributes blood supply to the temporalis muscle and is preserved. The artery is clipped and divided anteriorly. If not immediately identified, it may be ligated after division of the maxilla.

Positioning of Upper Gigli Saw

Each wall of the maxillary sinus below the level of the infraorbital nerve is simultaneously divided with a Gigli saw. To accomplish this, two options are available, related to whether the saw is positioned anterior or posterior to the pterygoid plates. The authors prefer to place the saw anteriorly in the pterygomaxillary fissure. In this position, the saw divides the maxilla through the middle meatus and with less difficulty than if it is positioned posteriorly. In the posterior position, it divides the maxilla through the inferior meatus in a way identical to the LeFort I fracture.

A soft tissue and bony tract is prepared for positioning the Gigli saw. After ligating the internal maxillary artery and identifying the lateral pterygoid plate, the pterygomaxillary fissure is palpated. A no. 22 urethral sound is engaged in the fissure and passed into the pterygopalatine fossa. An index finger in the nasopharynx palpates the eustachian tube. Manipulation of the sound with one hand and confirmation of its anatomic point of entrance above the eustachian tube with the other permits the sound to be passed successfully into the nasopharynx. The same may be accomplished if the sound is passed posterior to the pterygoid plates. This sound or an alternative instrument passes through the pterygomaxillary fissure and the pterygopalatine fossa into the lumen of the nasopharynx with less difficulty if its handles are positioned inferiorly and parallel with the vertical ramus of the mandible. In this position, its tip is less likely to abut the adjacent bony skull base. Should difficulty be encountered in establishing this tract, other alternatives are available. A curved, 1-in. chisel is placed in the pterygomaxillary fissure, the adjacent bone divided, and the fissure enlarged. A small mastoid gouge or chisel may be passed through the pterygomaxillary fissure, into the pterygopalatine fossa, and driven into the nasopharynx. If necessary, the pterygoid plates or the posterior wall of the maxillary sinus may be divided.

Passage of the urethral sound through this defect enlarges the tract and permits passage of the Gigli saw behind the maxilla into the nasopharynx. Creation of the tract inferiorly in the pterygomaxillary fissure reduces the risk of damage to the internal maxillary artery, unless it is clipped before this dissection.

One of several instruments may be used as a ligature carrier for positioning the Gigli saw. An orthopedic wire carrier, a no. 14 Tuohy spinal needle, a thyroid ligature carrier, or a large, curved, long (9 in.) Kelly forceps have been used.

The orthopedic wire carrier is preferred (Fig. 5A). It is a curved, partially tubed instrument that can accommodate and transport a Gigli saw when the eye loop of the saw is compressed. This instrument is introduced into the tract made by the urethral sound and chisels and into the nasopharynx. Again, the position of the point of entrance of the wire carrier into the nasopharynx is confirmed by palpation. It is visualized by elevating the soft palate with a Love or Senturia retractor. Should this maneuver be troublesome, the pterygomaxillary attachment is again divided with a chisel, and the wire carrier repositioned. Care should be taken to prevent the carrier from entering the maxillary sinus, and preferably the carrier should be positioned behind it. The Gigli loop is grasped with forceps and transported into the oropharynx.


Zygoma osteotomy
Buccal fat
Temporomandibular joint
Masseter muscle
A
Temporalis muscle
Temporomandibular joint
Zygoma osteotomy
Divided masseter muscle
Internal maxillary artery ligation
External carotid artery
Pterygomaxillary fissure
Posterior wall maxilla
Lateral pterygoid plate
B

FIG. 4. A: Buccal fat removal to gain exposure in the pterygoid region medial to the masseter muscle. B: The infratemporal fossa is exposed medial to the zygomatic arch. The anterior masseter muscle is detached from the zygoma. Retraction of these tissues permits removal of the coronoid process of the mandible and its temporalis attachment. Partial division of the pterygoid muscle reveals the posterior wall of the maxillary sinus, lateral pterygoid plate, and the pterygomaxillary fissure. The anterior internal maxillary artery is clipped.


Posterior nasal septum
Foramen lacerum
Clivus
A
Pterygomaxillary fissure
Intranasal catheter
Orthopedic wire carrier
Gigli saw
Foramen ovale
Wire stylet
B
Lateral pterygoid plate
Touhy needle

FIG. 5. A: The upper Gigli saw is positioned. An orthopedic wire carrier loaded with the medial arm of the Gigli saw is directed into the nasopharynx through the pterygomaxillary fissure anterior to the pterygoid plates. An intranasal catheter is tied to the Gigli saw loop. Soft palate retraction or manipulation of these instruments into the oropharynx for the silk tie approximation of the Gigli saw and the catheter is usually necessary. B: A no. 14 Tuohy needle threaded with a no. 20 wire stylet. The Gigli saw is attached to the stylet. Retrograde traction on the wire positions the saw anterior to the pterygoid plate as the needle and stylet are removed.

The carrier is removed. A rubber catheter is passed through the nose into the nasopharynx and oropharynx. The Gigli loop and the catheter are joined with a silk suture. Traction on the catheter elevates and positions the medial arm of the saw in the nose at the level of the ascending process of the maxilla in the middle meatus. A broad ligament clamp may be substituted for the catheter to position the saw. The body of the zygoma is perforated with a drill just below the level of the infraorbital foramen. This perforation is extended to and through the inferior margin of the zygoma. This produces a notch to accommodate the lateral arm of the Gigli saw. The Gigli saw now completely surrounds the maxilla anterior to the pterygoid plates and, if maintained in the initial zygomatic perforation when the bone is divided, ensures division of the lateral nasal wall in the middle meatus. It is important to maintain the Gigli saw in the zygomatic perforation so that the level of division of the lateral nasal wall in the middle meatus is ensured.

Should the orthopedic carrier be unavailable, a specially prepared no. 14 Tuohy spinal needle may be used (see Fig. 5B). Its stylet is removed and a no. 20 or 22 wire is substituted. With the wire in place, the needle and wire are manipulated to produce a gentle curve, with care being taken not to produce a "crack" or break in the needle at the site of the bend. The wire in the needle helps to prevent this, and molding the needle around a medicine glass or a rounded instrument handle is a helpful maneuver. As with the orthopedic carrier, the needle and the wire are passed into the nasopharynx anterior or posterior to the pterygoid plates. The needle is removed. The Gigli saw is attached to the wire extending into the nasopharynx and, by traction on this wire, the Gigli saw is positioned into the perforated zygoma. As with the orthopedic wire carrier, a nasal catheter is attached to the medial arm of the Gigli saw. Traction on the catheter positions the saw in the nose. Again, a long-bladed broad ligament clamp may be substituted for the catheter.

The authors originally used a large, curved, sharp-pointed, right-angled thyroid ligature carrier to maneuver a no. 2 silk suture and the Gigli saw into position. Sometimes the instrument was too short. A large, long, curved Kelly or a broad ligament clamp have also been used without uniform success. It is wise, however, to be aware of these various instruments and have them available should additional techniques be required. Should these instruments not be available, the maxilla may be divided with an oscillating saw after exposure of its lateral wall to the pterygomaxillary fissure and the pyriform aperture at the middle meatus. The saw divides the lateral and anterior maxillary walls and finally the medial wall of the maxilla in the middle meatus to the medial pterygoid plate. The maxilla is then separated from the pterygoid process with a curved osteotome. As previously described, the lower half of the zygoma is divided and allowed to remain attached to the maxilla (Fig. 6).

Positioning of Lower Gigli Saw

A medium-sized, curved Kelly forceps is passed beneath the already elevated nasal floor mucoperiosteum from the pyriform aperture of the nose, through the soft palate perforation at the junction of the hard and soft palate, and into the oral cavity. On occasion, the forceps may be directed through the same perforation from the oral cavity side and the Gigli saw passed through the nose with the aid of a nasal speculum. The saw is engaged between the blades of the clamp. Traction on the clamp positions the saw to divide the hard palate through the initial mucoperiosteal hard palate incision from the posterior margin of the hard palate up to the lingual side of the interdental space between the two central incisor teeth. Beyond this point, the hard palate is divided with a thin-bladed reciprocating or Stryker saw between the incisor teeth, beneath the bipedicled mucoperiosteal flap to the homolateral side of the anterior nasal spine, with care being taken to preserve the roots of the teeth and the nasal spine (Fig. 7). The attachment of the mucoperiosteum of the hard palate on each side of the initial incision remains intact. This reduces the risk of an oronasal fistula. The hard palate osteotomy and the mucoperiosteal incision should not be in apposition.

Preliminary Plating of the Maxilla

Before completely dividing the maxilla, preparation is made for its subsequent stabilization. A vertical incision is made through the zygoma from its perforation downward. This completes the division of the upper maxilla after incision of the bone between the arms of the upper Gigli saw.

Appropriate drill holes are placed on each side of the anterior hard palate, ascending process of the maxilla, and zygoma incisions to accommodate miniplates. The titanium miniplates are positioned, secured in place with screws, and removed for subsequent permanent application at the end of the procedure.

Maxillary and Pterygoid Plate Osteotomies

The angles of the Gigli saws may be varied. The saws adapt better to movement as their cutting angles are increased. Movement is initiated without tension on the saws as they are moved back and forth. Grasping the saw with a hemostat near either side of the pterygoid plates is a helpful initiating maneuver. If division of the bone is unsuccessful, the plates may be divided with chisels as previously described.

Before incision of the upper maxilla, the patient's head is rotated laterally to the contralateral side and firmly held against the operating table. Adequate retraction of the facial soft tissue prevents their injury as a sawing motion is made


Infraorbital foramen
Gigli saw posterior to pterygoid plate
Incision line for removal of coronoid process
Mandibular foramen
Zygomatic osteotomy
Lateral pterygoid plate
A
Pterygomaxillary fissure
Gigli saw anterior to pterygoid plate
Lateral pterygoid plate
Mandibular foramen
Zygomatic osteotomy
B

FIG. 6. A: The upper Gigli saw is positioned. Each wall of the maxilla below the level of the infraorbital foramen is simultaneously divided with the Gigli saw positioned behind the pterygoid plates. The saw's medial arm is placed in the inferior meatus of the nose and its lateral arm in the perforated zygoma. The coronoid process of the mandible is removed above the mandibular foramen before insertion of the Gigli saw. B: .The upper Gigli saw may be positioned anterior to the pterygoid plates. The saw's medial arm is placed in the middle meatus of the nose and its lateral arm in the perforated zygoma. Coronoid excision as above.


Nasal spine
Gigli saw
Central incisor root
Drill holes for plating
Line of incision hard palate
Palate perforation
A
Bone perforations for plating
Anterior maxillary osteotomy
Stryker blade
Nasal spine
Central incisor interdental space
B

FIG. 7. A: The lower Gigli saw is positioned for division of the hard palate. The bony incision is to the homolateral side of the midline. B: The Stryker saw blade is positioned to divide the remaining anterior maxilla between the central incisor teeth to the homolateral side of the nasal spine.

with the two arms of the Gigli saw at least 4 to 5 mm above the roots of the teeth. Fragmentation of bone in this area should be anticipated- Should it occur, the anterior wall of the maxilla should be divided with a drill. This not only prevents fragmentation, but provides solid bone for drill holes and subsequent miniplate reconstruction.

After complete division of the upper and lower maxilla, and if the upper saw has been placed anterior to the pterygoid plate, the pterygomaxillary attachment is divided with a curved chisel. If the saw is behind the pterygoid plate, the chisel incision is unnecessary (Fig. 8).

Additional Technical Options

Alternative techniques have been developed for dividing the maxilla and the malar' bones. Division of the bony nasal


Temporomandibular joint
Infratemporal crest
Pterygomaxillary fissure
Lateral pterygoid plate
Coronoid resected
A
Chisel
Drill holes for plating
Zygomatic osteotomy
Pterygomaxillary fissure
Lateral pterygoid plate
Mandibular foramen

FIG. 8. A: The coronoid process of the mandible above the mandibular foramen is resected. The pterygomaxillary fissure is illustrated. B: Pterygomaxillary disarticulation. After complete osteotomy of the upper maxilla and the hard palate, the maxilla is detached with a curved chisel from the pterygoid plates at the pterygomaxillary articulation.

Door with the gigli saw is expeditious even though the maxilla between the two central incisor teeth is divided with a reciprocating saw.

liach of the walls of the maxilla is divided with a fine-bladed Siryker saw, chisel, and a rongeur. A medial inaxilleeiomy is accomplished to include the anterior margin of the nasal pyrilbrm aperture beneath the nasal bone. The maxillary sinus is entered and its anterior bony wall is removed medial to the infraorbital foramen. The medial wall of the interior of the maxillary sinus is visualized and is divided at. the level of the middle mcaiiih to the medial pterygoid plate. The middle and superior Lurbinates arc removed,

The lateral wall of the maxillary sinus is exposed above the lower edge of its attachment to the zygoma. It is divided posteriorly to the lateral pterygoid plate. The maxillary sinus *h* entered anterior to ks posterior wall. Its posterior wall is divided to meet, the dissection from its medial side.

The zygoma is divided with the Strykcr saw below the level of the mfraorbital canal and the ptervgomaxillary junction is divided wiLh a curved chisel. This usually fragments the adjacent posterior wall of the maxillary sinus; if not, repositioning the chisel permits further fragmentation of the posterior maxillary wall to its medial wall. The osteotomies are recognized to be complete when the maxilla becomes mobile.

The authors have used this technique in one patient whose juvenile nasopharyngeal ungiofibroma extended from the roof of the sphenoid to the floor of the maxillary sinus anteriorly. The tumor measured 8 cm in its greatest dimension. It involved the entire nasopharynx and the intraLemporal fossa, and extended into the orbit through the inferior orbital fissure. The tumor was easily removed *en bkx.*- after prcopera-live emboli/ation and subsequent mobilization and inferior retraction of the maxilla.

Although the authors have nol extended the degloving approach beyond the superior level of the inferior orbital rim nnd the Irontonasal suture line, it is obvious that these facial soft tissues may he elevated along the lateral orbital wall as high as the frontozygomatic suture line, which may be divided r.o join the inferior orbital fissure. Division of the y.ygomatic arch and the inferior orbital wait lateral to the zygomalicomaxillary suture to join the inferior orbital fissure as well Trees the zygoma tor its removal and replacement alter excision of a neoplasm in its immediate vicinity that may involve the orbit and infratemporal fossa (43 45). This may be accomplished after elevation of the orbital periosteum and division of the bone with % Strykcr or Gi^li saw. As previously described, placement or the Gigli saw into the inferior orbital lissure for division of the orbiml wail may be aided with a Tuohy needle or a thyroid ligature carrier. Care should be taken to rcaLtach die lateral canthal ligament after completion of the procedure and replacement of the zygoma.

Micrudivision of bone about the periphery of the orifice of the infraorbital foramen and mobilization of the inferior orbital nerve along the Hour of the orbit further assist elevation ol' the degloved facial tissues to a higher level Tor additional exposure.

Skull Exposure

Half of the maxilla is now hinged primarily on the soft palate and secondarily on the hipedicled anterior mucope-ri os tea I maxillary flap. It consists of half of the hard palate, the inferior turbinate., each wall of the maxillary sinus except the roof, and the lower half ol' the zygoma below the level uf the infraorbital aerve. It may be retracted interiorly or rotated lo the contralatcral side ol' the defect with a large hook or tenacuium after division of its attachment to the pterygumandibular raphe and the superior pharyngeal constrictor. It is secured in position with fish hooks or a Leylar or Crock a rd scir-retaining retractor (Fig. 9).

The intranasal flap development is refined. It is retracted laterally and allowed to remain attached to the anterior lateral surface of the sphenoid and adjacent soft tissues. Additional scptal bone consisting of the perpendicular plate of the ethmoid and vomcr is removed (see Fig. 3C).

The mucopcriosteum of the septum on the opposite side may or may not be preserved. If it is preserved, it may be cl evatud from its adjacent attachment to the floor of the nose and lateral wall of the nose in die inferior meatus. Vertical division of this mucoperiosteum immediately behind the adjacent septa! cartilage and its detachment Irom the lateral wall of the nose creates a flap hinged at the lateral margin of the sphenoid, similar to the one on the opposite side. This ilap may be rotated to cover the roof of the opposite side of the nose or to join its mate at the sphcnocUval defect. Rotation of both flaps eliminates Lhc posterior third or half of the-nasal septum and exposes the entire nasopharynx and posterior nasal cavity. The anterior half of the nasal septum is undisturbed and remains attached to the maxillary crest, the nasal spine, and the nasal bones.

The remaining lateral and posterior walls of the maxillary sinus are removed, as well as the middle and superior turbinate s. The inferior turbinate is preserved ;md remains attached to the rotated and retracted maxilla. Should it have been divided or lacerated, it should be repaired, reattachcd Lo the adjacent tissues, and divided and used as a graft, or displaced into the maxillary sinus. The opposite inferior turbinate is not disturbed. The ethmoid sinus and the anterior wall of the sphenoid sinus are removed to enlarge the sinonasal defect for exposure.

Additional clips should be applied to branches of the internal maxillary artery if bleeding continues. Bleeding from bone is controlled with wax. Venous bleeding is controlled with the bipolar cautery, (icUbam saturated with thrombin. Kurgicel gauze, and cottonoid pressure. Two gloves filled with ice are tied together and draped over the patient's eyes and retracted facial tissues for the duration of the procedure.

Retropharyngeal and Cervical Spine Esposure to Tumor Excision and Dural Closure

The most frequent initial incision for exposure of lesion", of the clivus and the nasopharynx is a vertical midline pha-

EXTENDED UNILATERAL MAXILLOTOMY
APPROACH / 223


Maxilla and zygoma
retracted
Soft palate
Middle skull base
compartment
(clivus and body of sphenoid)
Foramen magnum
Occipital condyle

Cr Cribiform plate Roof

of maxillary sinus

Bipedicle maxillary flap

Ethmoid sinus defect

Contralateral septal
mucoperioteum

Hard palate

Zygoma

Sphenoid sinus - left

Sphenoid septum

Pterygoid base

Infratemporal fossa

Internal maxillary artery

Foramen ovale

Eustachian tube

Divided masseter
muscle

Mandibular nerve

Foramen lacerum

Petro-sphenoid fissure

Internal carotid canal

Resected coronoid

Palatine tonsil

FIG. 9. The maxillotomy exposure of the skull base. The lower maxilla and the lower half of the zygoma pedicled on the intact homolateral soft palate after the pterygoid and maxillary osteotomies are rotated and retracted to the contralateral side. The posterior, medial, and lateral walls of the maxillary sinus with the superior and middle turbinates are removed, along with a complete ethmosphenoidectomy. The posterior half of the nasal septum is removed. The middle and lateral skull base compartments as well as the infratemporal fossa are exposed.

b

i

ryngeal incision from the anterior sphenoid (basisphenoid) to the foramen magnum (basiocciput) with inferior retraction of the intact soft palate. The adjacent pharyngeal mucous membrane and the submucosal soft tissues, which may include the parasagittal muscles, fascia, and ligaments, are mobilized and excised or detached from the underlying bone or the tumor. The petrosphenoid fissure and the hypoglossal foramina limit the lateral margin of exposure through this incision.

Additional exposure of the remainder of the retropharyngeal area and cervical spine can be achieved by extending the retromolar incision interiorly through the superior pharyngeal constrictor muscle, pterygomandibular raphe, and anterior tonsillar pillar and its tongue attachment lateral to the palatine tonsil. An index finger inserted into the depths of this incision palpates the prevertebral fascia and the retropharyngeal space as the maxilla, soft palate, anterior and posterior tonsillar pillars, palatine tonsil, and lateral and posterior pharyngeal walls are retracted toward the midline. Retraction of these tissues increases the surgical exposure of the skull base and the cervical spine.

This additional exposure may sacrifice nerve branches from the pharyngeal plexus that supply the adjacent soft palate, resulting in some degree of velopharyngeal insufficiency. Plication of the soft palate to an adjacent, superiorly based posterior nasopharyngeal wall flap discourages these handicaps, as well as suturing buccal or abdominal fat grafts to the superior denuded surface of the soft palate.

These additional maneuvers permit uninterrupted exposure of this area from the roof of the sphenoid to the fourth or fifth cervical vertebra, the infratemporal fossa, the space between the common carotid arteries, the hypoglossal nerves, and the anterior margin of the foramen magnum without interference of exposure by the soft palate or compromise of its contralateral blood supply.

In the face of a positive preoperative diagnosis and confirmation of the extent of disease by maxillotomy exposure, an appropriate surgical technique for removal of the clearly defined tumor must be selected. This subject is discussed only partially in this chapter in the introduction, and in the sections on Indications, Technique, Advantages, Disadvantages, and Comments.

Special instruments designed to maintain continuous retraction and exposure are necessary. These include the multi-bladed Leylar and Crockard self-retaining retractors, an operating microscope with a 400-mm lens attachment, and a fluoroscope with a C-arm attachment. Special instruments for the removal of bone and tumor should be available and should include those designed for electrocoagulation, the CC>2 laser, a high-speed bone drill, an irrigation suction system, and an ultrasonic aspirator. Microtechnical instruments for dural closure are especially important.

After control of bleeding, several anatomic landmarks should be identified. Confirmation of these landmarks for orientation throughout the procedure is exceptionally helpful. The *midline of the skull base* is in line with the vomer attachment to the anterior face of the sphenoid and its continuation into the nasal septum. The midline continues to the midline of the anterior rim of the foramen magnum. *The base of the pterygoid plates* is attached to the junction of the greater wing and body of the sphenoid. Behind its medial plate is the *foramen lacerum,* which contains the internal carotid artery, and behind or lateral to its lateral plate is the *foramen ovale,* which contains the mandibular nerve. The *middle compartment* of the skull base is bounded laterally by the lateral wall of the sphenoid sinus, medial pterygoid plate, petrooccipital fissure, the anterior margin of the *occipital condyle,* and the anterolateral margin of the foramen magnum. It is primarily composed of the body of the sphenoid and the clivus. The *lateral compartment* is bounded medially by the petrooccipital fissure and laterally by the petrosphe-noid fissure. It primarily contains the petrous division of the temporal bone with its adjacent foramen lacerum anteriorly and carotid canal posteriorly. Lateral to the lateral compartment is the infratemporal fossa below the greater wing of the sphenoid and the infratemporal crest. It primarily contains the temporalis and pterygoid muscles, the internal maxillary artery, and the mandibular nerve (Fig. 10).

Complete clivectomy with tumor removal is the procedure of choice when the tumor primarily originates in or secondarily involves the bony clivus, the adjacent clival dura, or extends extracranially or intracranially to compress the brainstem (Fig. 11). Should this require incision or excision of the dura (Fig. 12), a meticulous microsurgical dural repair, as watertight as possible, should be accomplished after tumor removal (Fig. 13). This may be done by primary closure of the defect with or without a fascial graft (Fig. 14). Drilling holes in the adjacent bone to anchor sutures for dural closure is fraught with difficulty and is frequently impossible. If the dural repair is not watertight, the defect may be reinforced with transposition of a fibromuscular temporalis flap or the nasal mucoperiosteal flaps. Free grafts of fat, bone, cartilage, fascia, or muscle may be required to fill remaining surgical defects at the operative site. Postoperative lumbar spinal drainage is required in selected patients.

Extradural and extracranial tumors that are encapsulated or infiltrative, originating from the skull base or extending from the paranasal sinuses, require local excision. Cavitation with the CCh laser or the ultrasonic aspirator may be necessary depending on the consistency and vascularity of the neoplastic process.

Wound Closure

Bleeding is carefully controlled with pressure, bipolar and Bovie cautery, Gelfoam and thrombin, Surgicel, and the application of bone wax. The internal maxillary artery may require ligation with a clip. As described in the technique, the wound is packed with abdominal fat. The buccal fat is replaced. If fat is not available, the defect is lined with rayon and filled with a gauze pack saturated with an antibiotic ointment.

Miniplates are applied to the maxilla. A supplementary upper arch bar may occasionally be required for additional maxillary stability.

The gingivobuccal gutter and palate incisions are closed with interrupted chromic suture or Vicryl.

The intranasal circumferential incisions are carefully approximated with interrupted 0000 catgut to prevent stenosis.

An adhesive external nose splint is applied.

POSTOPERATIVE CARE

In the recovery room and the intensive care unit, the head of the bed is elevated. The vital signs are monitored and treated appropriately. Blood replacement may be required. In general, intensive care may be required no longer than 3 days (usually only 1 day), depending on the patient's neurologic status. In some instances, a lumbar drain is necessary if a craniotomy and dural replacement were required.

The cotton in the nares is removed and replaced as frequently as necessary to maintain nasal and facial cleanliness. An icecap to the nose and cheek discourages bleeding and edema of these structures. This is usually discontinued after 48 hours. On the third or fourth postoperative day, enough of the nasal fat is removed to provide an adequate nasal airway. The texture of the fat contributes to its ease of removal without hemorrhage/Nasal saline irrigations are begun the following week and are continued until the washing is clear.

продолжение


Foramen lacerum
Base of pterygoid
Foramen ovale
Middle compartment:
(Lateral boundary)
Lateral wall of sphenoid body
Medial pterygoid plate
Petro-occipital fissure
Anterior margin of occipital condyle
Anterior lateral wall of foramen magnum
Contents:
Body of sphenoid
Clivus
Infratemporal fossa:
Infratemporal crest (superior border)
Lateral pterygoid plate (medial border)
Zygomatic arch (lateral border)
Great wing of sphenoid and Squamous temporal bone (superior border)
Alveolar border of maxilla (inferior border line)
Sphenoid spine
Articular tubercle of temporal bone (posterior border line)
Contents:
Temporalis muscle
Pterygoid muscle
Internal maxillary artery
Mandibular nerve
Carotid canal
Lateral compartment:
Petrosphenoid fissure (lateral boundary)
Petro-occipital fissure (medial boundary)
Contents:
Petrous temporal bone
Foramen lacerum
Carotid canal

FIG. 10. Important anatomic landmarks that are helpful in preventing serious complications during aggressive surgical procedures for the removal of skull base tumors.


Retracted maxilla and zygoma
Clival tumor
Masseter muscle
Resected coronoid
Soft palate
Tonsil

FIG. 1 1 . Surgical exposure of a clival tumor beneath the dura.


Basilar artery
Incised dura

FIG. 12, Dura over the clivus is incised to expose the tumor.


Basilar artery
Tumor
Dura
Vertebral artery

FIG. 13. Tumor removal.


Fascia graft
Knot tier
A
B

FIG. 14. A: Dural closure. B: Fascia graft sutured into dural defect.

Routine nasal and sinus cleansing may be required. The adhesive nasal splint is removed in 1 week.

The oral cavity is cleansed with half-strength peroxide or other appropriate mouthwash. Cleansing of the suture line with a Water-Pik spray is advisable. Jaw motion rehabilitation with the Intraoral Therabite System (Therabite Corporation, Bryn Mawr, PA) to prevent mandibular hypomobility is begun immediately and continued for 2 to 3 months. This discourages restricted jaw motion. Additional dental care is directed by the oral surgeon.

Analgesics, sedatives, antiemetics, and continued antibiotic medications are prescribed as required.

A full liquid diet and clear fluids are begun on the day after surgery if and when bowel sounds return. Soft foods are prescribed after healing of the oral cavity wounds.

Early ambulation is encouraged and is begun the day after surgery.

Magnetic resonance imaging or computed tomography scans are ordered at the discretion of the neurosurgeon.

A lumbar drain is inserted by the neurosurgeon in appropriate patients.

COMPLICATIONS

Since 1988, the authors have used the extended maxillotomy in 30 selected cases (Table 4). Complications observed in these cases occurring immediately after surgery and within a 6-month period of follow-up involved three major areas: (a) healing of the maxilla, (b) sinonasal anatomy, and (c) neurologic function (Table 5).

The incidence of complications occurring in this series of patients included a minor degree of gingival breakdown (one patient), loss of two teeth (one), trismus (one), stiffness of the temporomandibular joint (five), nasal tip depression (two), cerebrospinal fluid (CSF) leakage (two), meningitis (one), pneumocephalus (one), new cranial nerve deficit (two), and other neurologic deficits (two). Medical complications included pneumonia and sepsis (one), pulmonary embolus (one), and myocardial infarction (one). Two deaths occurred in the series attributed to a pulmonary embolus and a myocardial infarction. Blood loss was directly related to the extent and vascularity of the neoplastic processes approached by the maxillotomy exposure, and not to the technique itself.

TABLE 4. *Maxillotomy experience (1988-1995)*

Lesion	No. of cases
Chordoma	10
Meningioma	6
Chondrosarcoma	2
Prolactin-secreting pituitary tumor	2
Juvenile angiofibroma	2
Chondromyxoid fibroma	1
Fibrosarcoma	1
Epidermoid carcinoma	1
Fibrous dysplasia	1
Craniocervical junction abnormality	3
Meningoencephalocele	1
Total	30

TABLE 5. *Complications of extended maxillotomy*[a]

Complication	No. of occurrences
Healing of the maxilla	
Necrosis of the maxilla	0
Gingival breakdown	1
Loss of teeth	1
Trismus	1
Stiffness of the temporomandibular joint	5
Nasosinal anatomy	
Nasal tip depression	2
Transient nasolacrimal duct obstruction	1
Eustachian tube dysfunction	2
Neurologic function	
Cerebrospinal fluid	2
Meningitis	1
Pneumocephalus	1
New cranial nerve deficit	2
Other neurologic deficits	2
Medical complicatons	
Pneumonia and sepsis	1
Pulmonary embolus	1 (death)
Myocardial infarction	1 (death)

[a] *Blood loss* was directly related to the extent and vascularity of the tumor, and not to the technique itself.

Side effects that may occur with the procedure are nasal crusting, stiffness of jaw motion, and transient sensory impairment of the palate and cheek. Preservation of the inferior turbinates and reduction of the size of the sinonasal defect with fat will control postoperative crusting as the result of improved nasal air humidification. Immediate rehabilitation of jaw motion after surgery, directed by the oral surgeon and using the Therabite System, eliminates ankylosis of the temporomandibular joint. Varying degrees of sensory impairment of the face ipsilateral to the maxillotomy result predominantly from manipulation of the infraorbital nerve (V2) and occasionally the mandibular division (V3) of the trigeminal nerve within the infratemporal fossa. The anesthesia of the palate is related directly to surgical trauma. Sensory impairment typically resolves over a 3- to 6-month period after surgery.

Problems with maxillary healing and sinonasal anatomy occurred in the early cases of the authors' series and have been resolved with improvement in technique. Gingival breakdown and loss of teeth have not been observed since the gingivobuccal incision was made through the mucoperiosteum at its apex, and the maxilla was divided through the middle meatus 5 mm above the apical roots of the teeth. Anticipated eustachian tube dysfunction leading to otitis with effusion may be prevented by performing a homolateral myringotomy with insertion of a pressure ventilating tube through the tympanic membrane at the beginning of the procedure. Preservation of the septal spine, the maxillary crest.

and the septal cartilage ensures that no external nasal deformity occurs. The authors have observed no permanent complications with division of the nasolacrimal duct or any velopharyngeal incompetence related to the maxillotomy exposure. Anterior nasal septal perforations are prevented by preserving the anterior half of the septum intact and removing its posterior half. Careful approximation of the nasal vestibular skin suture line has eliminated vestibular stenosis.

The preservation of neurologic function has resulted from the avoidance of unnecessary exposure, manipulation, or sacrifice of neuroanatomic structures. The ventral approach to the midline of the skull base has led to only two patients with new, transient cranial nerve VI palsies that completely resolved within several months after surgery. One patient with an extensive intradural chordoma presented with a progressive quadriparesis and lower cranial nerve deficits. After surgery, there was complete quadriplegia that partially resolved over 6 months. A patient with an intradural chondrosarcoma compressing the ipsilateral brainstem experienced a transient monoparesis of the contralateral upper extremity with tumor removal. This focal deficit resolved completely within 2 weeks after surgery.

Prevention of CSF leakage and the potential for meningitis results from watertight closure of dural defects by repair with interrupted suture or application of a sutured fascia lata graft or rotation of unilateral or bilateral intranasal flaps. In earlier cases of this series, vascularized temporalis muscle and fascia were transposed to cover the dural defects. In all cases the muscle and fascia remained viable and prevented CSF fistula formation. One case in which CSF leakage and meningitis occurred involved a patient with a recurrent chordoma previously operated on with subtotal removal, followed by proton beam radiation therapy and the chronic administration of steroids (Table 6).

In all cases in this series undergoing maxillotomy, no necrosis of the maxilla occurred. Although one greater and lesser palatine artery, posterior superior alveolar artery, and palatine branch of the facial artery have been divided, the maxillary segment continues to survive by blood supply from a palatine branch of the ascending pharyngeal artery and from the contralateral soft palate anastomosis.

TABLE 6. *Management of intradural tumors in 11 patients*



Diagnosis	Dural suture repair	Graft repair	Temporalis muscle
Chordoma	+		
Chordoma	+		
Chordoma[a]			+
Chordoma		+	
Meningioma			+
Meningioma[b]		+	
Meningioma		+	
Meningioma[b]		+	
Meningioma[b]			+
Chondrosarcoma[a]	+		
Meningoencephalocele	+		

[a] Previous surgery plus radiation therapy. [b] Previous surgery.

ADVANTAGES

The extended maxillotomy is a single-procedure, degloving, sublabial technique that is a unilateral, horizontal, modified LeFort I maxillary osteotomy without a soft palate myotomy. In contrast to the LeFort I operation, the authors prefer division of the maxilla through the middle meatus rather than the standard LeFort I incision through the inferior meatus. This permits the inferior turbinate to remain attached to the retracted maxilla. This technique produces exposure that would be gained only by the incorporation of a combination of other procedures. These include transnasal, transseptal (46-50), transethmoidal (48-51), transsphenoidal (47-53), transmaxillary (49,51,54-56), transoral (57-72), direct nasooropharyngotomy (50,52,69,72), transpharyngeal (73), transpalatal (55,74-81), subtotal maxillectomy (1,82), maxillary swing (83-87), transcranial, infratemporal fossa (42,88,89), lateral rhinotomy (90), and the medial maxillectomy (91). This maxillotomy technique also provides more exposure than the bilateral LeFort I maxillotomy with or without a vertical palate osteomyotomy (4,30-39,41,92). It is designed to permit modifications for skull base exposure. A midline soft palate myotomy with the extended unilateral maxillotomy would seem inadvisable because the soft palate contains significant blood vessels that originate from the contralateral side that primarily supply not only the soft palate but the hard palate. Displacement of the soft palate by its attachment to the retracted hard palate and the lower half of the body of the zygoma provides excellent exposure of the extracranial middle and posterior fossa skull base, especially when the posterior nasal septum, the entire lateral nasal wall, the coronoid process of the mandible, and the homolateral pterygoid plates have been removed. Additional exposure is obtained when the maxilla is retracted with its attached inferior turbinate and nasal floor. Dislocation of the entire nasal septum from the anterior maxillary spine and crest is unnecessary to gain this exposure. Even more exposure of this region is provided by division and retraction of the divided retromolar buccal mucosa, soft palate, and the superior pharyngeal constrictor muscle lateral to the palatine tonsil. This is described in the section on Technique.

The exposure of the skull base produced by the extended horizontal maxillotomy is superior to and far more comprehensive than could be achieved by using any single procedure referenced in the literature. These would include the exposure obtained using only a palatal osteomyotomy (47,59,81,92-94), a mandibulotomy (47,95-106), or a transcervical technique (107-116). The extended maxillotomy should not include an extensive craniotomy procedure. Significant additional exposure is not gained by duplicating the procedure on the contralateral side. In fact, fragmentation of the maxilla into more than one segment on one or both sides increases the risk of maxillary necrosis (25). In younger patients, if the teeth have erupted, the incision does not interfere with growth center maturation.

Importantly, the morbidity associated with the maxillotomy technique is minimal and may be compared to that associated with a transmaxillary procedure for sinus disease. The major morbidity relates to the neurosurgical procedure required for management of conditions at the skull base and cervical spine.

This procedure was primarily developed to gain adequate extracranial middle and posterior fossa exposure of the middle compartment of the skull base for the removal of clival tumors, and for the excellent view it affords of the brainstem and the anterior skull base. It provides exceptional accessibility to many structures from the roof of the sphenoid sinus to the fifth cervical vertebra, between each eustachian tube, the carotid canals, each petrooccipital fissure, the hypoglos-sal foramina, the occipital condyles, and the anterior margin of the foramen magnum. Other structures exposed by this technique are listed in Table 7.

The superior exposure of the operative field alone establishes an unexcelled mutual working relationship with surgeons in other fields, primarily the neurosurgeon. It provides an unobstructed, wide-field, direct view into a defect, the depth of field and binocular acuity of which are not restricted by the limitations and confinement of adjacent anatomic structures. This exposure of the skull base permits the manipulation of surgical instruments at a comfortable working distance in the depths of the operative field, whereas such freedom of movement is limited in many of the other techniques. This technique permits the multibladed, self-retaining Leylar neurosurgical and Crockard retractors to retract tissues in more than one direction for exposure without the necessity of using additional retractors. The mobilized maxilla and the lower half of the body of the zygoma remain attached to the soft palate and may be retracted inferiorly, medially, or laterally to gain additional exposure (117) of the medial and lateral compartments of the skull base for removal of primary skull base tumors or secondary tumors that may have extended into this region from adjacent areas. It also permits reconstruction of the defect with temporalis muscle or intranasal mucoperiosteal flaps, as well as with bone, cartilage, and skin grafts.

This access does not limit application of state-of-the-art neurosurgical techniques for the correction of surgical problems that include excision of neoplasms and correction of bony defects. The use of the laser, a high-speed surgical drill, and the operating microscope are not restricted. The carotid artery may be mobilized in its canal and covered with an appropriate graft.

Tumors extending to the medial wall of the jugular foramen may be approached. A vertebral basilar aneurysm (31) may be clipped. A clival dural defect can be sutured watertight or reconstructed with an appropriate graft.

An intradural clival tumor ventral to the brainstem may be removed. In the authors' series, there were 11 such cases. Without this exposure for management of these conditions, life-threatening complications are to be expected.

Through this approach, the entire zygoma may be temporarily excised and replaced, and the coronoid process of the mandible is frequently removed for additional exposure, as well as bone about the infraorbital foramen as it is microfragmented and the nerve mobilized, retracted, and elevated with the degloved soft tissues to a higher level. Bone from the orbital floor may be removed with preservation of its periosteum for more exposure.

Blood loss has not been a major problem and has been controlled by preoperative injection of the soft tissues in the surgical field, the greater palatine canals, the anterior and posterior ethmoid arteries, and the infratemporal fossa with lidocaine containing 1:100,000 epinephrine, and also by ligating the internal maxillary artery in the infratemporal fossa before or after division and retraction of the maxilla. Electrocoagulation of bleeding vessels and the application of topical vasoconstrictors, clotting agents, and bone wax are also helpful to control bleeding. Blood loss associated with the surgical approach has not been a major complication.

The maxilla is accessible for application of titanium plates that provide excellent dental occlusion. Appropriate management of the retracted maxilla as described in the Technique section discourages the development of an oronasal fistula. This operation preserves the apical roots of all the teeth, the nasal spine, and an adequate blood supply to the maxilla.

This exposure permits positioning of the Gigli saw in the middle meatus of the lateral nasal wall, below the infraorbital foramen, and 5 mm above the apex of the roots of the teeth to divide the maxilla. The teeth are preserved. After seating the saws into position, the maxilla may be divided in a few seconds. Other options have been developed for the removal of neoplasms that extend from the nasopharynx into the maxilla. The posterior bony nasal septum may be removed for more contralateral exposure as the bilateral septal mucoperiosteal flaps are preserved, rotated, and positioned into the sphenoclival defect. Additional fragments of the palatine bone, the attached maxillary crest, and maxilla may be removed for further exposure if there is difficulty in visualizing the adjacent lateral pharyngeal wall or positioning the retractor.

Lateral access to the retropharyngeal space with retraction of the tonsillar pillars, palatine tonsil, superior constrictor muscle, soft palate, maxilla, and zygoma is feasible for exposure of the spine to the fourth cervical vertebra. This technique may result in paralysis of the soft palate due to division of the palatal nerve branches from the pharyngeal nerve plexus. This plexus consists of nerves from the bulbar portion of the accessory nerve, and filaments from the branches of the glossopharyngeal, sympathetic, and external branches of the superior laryngeal nerve from the vagus. A sutured fat graft to the nasal surface of the soft palate compensates to some degree for the velopharyngeal incompetence.

Through this exposure, it is advantageous to pack the sur-

TABLE 7. *Anatomic structures that may be encountered in the extended maxillotomy procedure*

- **I. Bones**
  - A. Sphenoid
    - 1. Roof
    - 2. Basisphenoid
    - 3. Pterygoid processes, medial and lateral
    - 4. Greater wing
    - 5. Sinus
    - 6. Infratemporal crest
    - 7. Anterior wall
    - 8. Sphenoid crest
  - B. Ethmoid
    - 1. Sinus—anterior
    - 2. Sinus—middle
    - 3. Sinus—posterior
    - 4. Superior turbinate
    - 5. Middle turbinate
    - 6. Lamina papyracea
    - 7. Perpendicular plate
    - 8. Cribriform plate
  - C. Maxilla (sinus)
    - 1. Walls a. Anterior
      - b. Posterior c.
      - Medial d. Lateral
      - e. Superior (orbital floor) f.
      - Inferior (hard palate)
    - 2. Orbital rim
    - 3. Inferior orbital foramen
    - 4. Ascending process
    - 5. Crest
  - D. Occipital
    - 1. Basioccipital
    - 2. Clivus
    - 3. Condyles E.
  - Temporal
    - 1. Petrous F.
  - Vertebrae
    - 1. Cervical
      - a. 1, 2, 3, 4, and 5
  - G. Mandible \
    - 1. Body
    - 2. Coronoid process H.
  - Zygoma
    - 1. Inferior orbital rim
    - 2. Frontal process
    - 3. Arch I.
  - Nasal
    - 1. Right and left J.
  - Vomer K. Palatine
- **II. Muscles** A.
  - Buccinator B.
  - Facial
  - C. Longus capitus D. Levator
  - veli palatini E. Pterygoid
    - 1. Internal
    - 2. External
- F. Superior pharyngeal constrictor G.
- Temporalis H. Tensor veli palatini **III.**
- **Fascia**
  - A. Prevertebral
  - B. Pterygomandibular raphe
- **IV. Ligament**
  - A. Anterior longitudinal
- **V. Nerves**
  - A. Trigeminal
    - 1. Maxillary division a. Zygomatic b.
      - Sphenopalatine c. Posterior
      - superior alveolar d. Infraorbital
        - 1. Anterior superior alveolar
        - 2. Middle superior alveolar e.
      - External nasal
      - f. Greater superficial petrosal g.
      - Deep petrosal nerve h. Nerve of
      - pterygoid canal
      - i. Sphenopalatine ganglion
        - 1. Palatine nerves
        - 2. Posterior superior nasal branch
        - 3. Pharyngeal nerve
        - 4. Nasopalatine
    - 2. Mandibular nerve
      - a. Masseter branch
      - b. Deep temporal
      - c. Buccinator nerve
      - d. Lingual
      - e. Inferior alveolar B.
  - Abducent C. Hypoglossal
- **VI. Arteries**
  - A. External carotid
    - 1. Ascending pharyngeal a.
      - Palatine branch
    - 2. Internal maxillary a. Deep
      - temporal b. Pterygoid
      - branches c. Masseteric
      - d. Buccinator
      - e. Posterior superior alveolar f.
      - Infraorbital
  - g. Descending (greater) palatine h.
  - Pharyngeal i. Sphenopalatine B. Internal
  - carotid
- **VII. Veins**
  - A. Inferior petrosal sinus
  - B. Internal maxillary
  - C. Pterygoid plexus
- **VIII. Fossae**
  - A. Pterygopalatine
  - B. Infratemporal
  - C. Extracranial skull base
    - 1. Anterior
    - 2. Middle
- **IX. Foramina**
  - A. Infraorbital
  - B. Lacerum
  - C. Magnum ..
- D. Ovale
  - E. Sphenopalatine
  - F. Spinosum
- **X. Fissures** A.
  - Infraorbital B.
  - Petrooccipital C.
  - Pterygomaxillary

(continued)

TABLE 7. *Continued.*

XI. Space
- A. Parapharyngeal—above angle of mandible

XII. Structures
- A. Paranasal sinuses
  - 1. Sphenoid
  - 2. Ethmoid
  - 3. Maxillary
- B. Oral cavity
  - 1. Palate a.
    Hard b.
    Soft
  - 2. Teeth
  - 3. Gums
  - 4. Tongue
  - 5. Lips
  - 6. Fauces
    - a. Glossopalatine arch (anterior pillar) b.
      Pharyngopalatine arch (posterior pillar) c.
      Palatine tonsils d. Palatine aponeurosis
      - 1. Levator velum palatini
      - 2. Tensor veil palatini
      - 3. Muscle of uvula
      - 4. Glossopalatinus
      - 5. Pharyngopalatine
  - 7. Pharynx
    - a. Nasopharynx
      - 1. Pharyngeal recess
      - 2. Torus of auditory tube
      - 3. Pharyngeal osteum of auditory tube
      - 4. Adenoid
  - 8. Oropharynx
    - a. Superior pharyngeal constrictor

Nose
- 1. External
  - a. Right and left nasal bones b.
    Frontonasal suture c. Ascending
    process maxilla d. Lower lateral
    cartilage
    - 1. Medial feet
    - 2. Ala cartilage e. Upper
    lateral cartilage
- 2. Interior
  - a. Nasal spine b.
    Maxillary crest c.
    Septum
    - 1. Nasal cartilage
    - 2. Perpendicular plate of ethmoid
    - 3. Vomer
    - 4. Sphenoid crest
    - 5. Anterior nasal spine
    - 6. Posterior d.
    Lateral nasal wall
    - 1. Turbinates
      - a. Upper, middle, and lower
    - 2. Meatus
      - a. Upper, middle, and lower e.
    Cribriform plate f. Floor of nose g.
    Inferior conchus

gical defect with 2- to 4-cm strips of abdominal fat. The fat is sticky enough to adhere to the walls of the surgical defect. It is soft enough to conform to the defect, solid enough to control bleeding, and, in contrast to rayon, its surface is smooth enough to be removed with minimal discomfort and bleeding. On the fourth or fifth postoperative day, the nonadherent fat in the lumen of the nose and nasopharynx is removed to maintain a nasal airway. The magnification provided by an operating microscope is helpful in selecting the appropriate fatty material to be removed and in leaving behind fat that has already become adherent to the walls of the defect.

Removal of the posterior nasal septum and reducing the size of the sinonasal defect with fat permits an improved moisturizing effect from the remaining turbinates. This also discourages crusting and superficial infection. For this reason, whenever possible, each inferior turbinate should be preserved. Unlike in the extended maxillotomy, the inferior turbinates are routinely removed for better exposure in the LeFort I procedure. Several authors have alluded to the excessive intranasal crusting in their patients. Six of 11 reports (30-36,39,41,54,85) indicate that the inferior turbinates were removed as a routine part of the LeFort I procedure. Although each report does not address the subject as a major complication, it is likely that crusting confronted these patients and possibly could have been controlled or eliminated if the inferior turbinates had not been removed.

Unlike in the infratemporal fossa procedure, the hearing is preserved, as well as all of the cranial nerves; the only neurologic complication related to cranial nerve function is some degree of temporary sensory impairment of the cheek.

Although the access and closure times are not short, the technique is not difficult to master. The degloving technique (26,28,29,39,49,117) eliminates facial scars and may avoid complications associated with keloid formation.

The morbidity is not excessive. The operation is well tolerated by the patient, who may be discharged from the hospital in less than a week. Tracheostomy, percutaneous gastrostomy, and nasogastric feeding tubes have been discontinued. The nasal airway is adequately maintained. Dysphagia and aspiration have not been troublesome. Early ambulation is important and is readily achieved.

The extended maxillotomy exposure is less extensive than the transcervical, mandibulotomy, maxillary swing, extensive craniotomy, and craniofacial disassembly procedures. Traction on vital intracranial structures through a craniotomy for exposure and tumor removal may be life threatening, in contrast to the exposure and tumor removal afforded by this extracranial, transclival, transpharyngeal approach.

DISADVANTAGES

Infiltrative lesions of the skull base that extend into and through many fissures, foramina, and bones are rarely completely removed. *En bloc* excision of many of the malignant and aggressive tumors cannot be accomplished with a good margin of normal tissue without the risk of death from injury to important adjacent life-sustaining structures.

Except in rare instances, it is likely that the extended maxillotomy approach would be considered too extensive to be combined with an extensive intracranial procedure.

Even in the face of the adequate exposure created by the maxillotomy, the neurosurgeon must become adept at manipulating the operating microscope, appropriate instruments, and the laser in a surgical field of this depth.

Temporary restricted jaw motion does occur, but can be managed without excessive morbidity when exercises are initiated in the early postoperative period.

The lengthy duration of the procedure (7-16 hours) and the excessive blood loss (45CMKXX) ml) are attributed primarily to the nature of the skull base tumor and its adherence to highly vascular structures.

The extended maxillotomy is more extensive than the transnasal, transseptal, transsphenoidal, transsinus, transpalatal, transpharyngeal, and lateral rhinotomy techniques. If only partial exposure of the clivus is required for biopsy or palliative removal of a neoplasm, or for correction of a minor bony abnormality, a more conservative technique should be selected.

COMMENTS

A multiplicity of surgical procedures have been developed by a number of surgeons trained in different specialties that are designed to achieve a multitude of goals in the treatment of patients with craniospinal disease. Many of the conditions are life threatening. Complete eradication of the disease has been the primary goal. Unfortunately, the results have frequently been disappointing, especially in the field of oncology-

The opportunity to remove extracranial skull base neoplasms that may or may not have extended for a short distance intracranially with an exceptionally good margin of normal tissue beyond evidence of disease is limited. Contamination and seeding of neoplastic cells by extirpative techniques, including bone drills and other manipulative maneuvers, cannot be avoided as the surgeon attempts to eliminate all evidence of the neoplasm, especially for those lesions within the bony clivus. Techniques for the removal of low-grade malignant tumors or even histologically benign tumors that mimic malignant lesions by their local aggressiveness remain inadequate and unrewarding. Nevertheless, it is the obligation of the surgeon at the request of the patient to select and use a method of management that offers the best chance for cure and, if not, palliation. Radiation therapy may play an important role should the tumor be sensitive to it and if it has been incompletely removed.

The authors are unable to document in the literature reports that identify an adequate series of patients with a follow-up period sufficient to compare the different treatment modalities with the aim of selecting the one modality or combination of modalities that generates the highest percentage of cures with the least morbidity. Most reports in the skull base literature describe only a case report, or give an account of more than one, and sometimes less than ten patients with a multiplicity of diagnoses. Other reports identify small patient populations with the same diagnosis that have been followed for such short periods of time that the effectiveness of their management is indeterminate.

Gay et al. (118) have reported the largest series of chordomas and chondrosarcomas of the cranial base. A variety of extensive surgical approaches were used to effect the greatest degree of tumor removal. Staged operations with a combination of approaches were used in 52% of the cases. Only 3% of the patients had transfacial procedures. The recurrence-free survival rate for all tumors was 80% at 3 years. Couldwell and Fukushima (119) reported a retrospective study of 109 petroclival meningiomas surgically approached through a number of lateral skull base exposures. Gross total removal of tumor was achieved in only 69% of the cases, with recurrence or progression of disease occurring in 13% of the patients over a 6.1 -year follow-up. Perioperative death occurred in 4 patients, and there were 56 significant complications in 35 other patients. The ability to perform a curative operation was limited by involvement of the cavernous sinus, encasement of intracranial vasculature, and pial invasion of the brainstem. Similar observations had previously been made by Sekhar and Narayana (120).

For this chapter, the authors selected only the extended maxillotomy for discussion. It is a procedure designed to give the surgeon adequate exposure for removal of primary extracranial neoplastic disease of the skull base. It continues to have fewer limitations than most of the other beautifully developed and described anterior and lateral skull base approaches. Even with adequate exposure of the region, the surgeon continues to be challenged to remove completely all evidence of neoplastic disease infiltrating the same crevices, fissures, foramina, and fossae, regardless of how extensive or conservative an exposure is selected. The extended maxillotomy provides more exposure than most of the transseptal, maxillary swing, infratemporal fossa, bilateral maxillary osteotomy with or without palatal osteomyotomy, transoral, transnasopharyngotomy, transsinus, lateral rhinotomy, medial maxillectomy, transnasal, transpalatal, transcervical, and mandibulotomy procedures, and with minimal morbidity. In addition, the exposure can be increased by removing the homolateral pterygoid plates, coronoid process of the mandible, the posterior nasal septum, and the entire lateral nasal wall, except for the inferior turbinate and nasal floor, which are temporarily retracted with the maxilla and with the homolateral soft palate. The zygoma may also be tentatively removed and replaced. If necessary, the exposure could be repeated for removal of residual disease. It is not nearly as extensive a procedure as the translocation techniques described by Beals and Joganic (121), Janecka and Sekhar (122), and Arriaga and Janecka (123). The transfacial approach described by Wei et al. (83,84), Brown et al. (85), and Altemir (86) for the removal of extracranial disease and the craniotomy procedures (124-138) described for the removal of intracranial disease have a greater morbidity. Many of these procedures were developed and influenced by the work of Tessier et al. (139). Each of these procedures is well documented and, in selected patients, may be superior to the extended maxillotomy. Technical limitations to the removal of aggressive infiltrative disease at the skull base continue to challenge the surgeon and the patient, regardless of the exposure.

In the authors' experience, a unilateral horizontal maxillotomy (extended maxillotomy) provides more exposure than a bilateral one, especially when the entire posterior nasal septum and the homolateral pterygoid plates are removed and the inferior turbinate is permitted to remain attached to the retracted maxilla. Dislocation of the anterior septum is usually unnecessary. Retraction for exposure of the skull base, sinonasal area, and the infratemporal fossa is best accomplished with the multibladed Leylar and Crockard retractors. The maxilla is divided through the middle meatus, in contrast to the LeFort I incision, which transects the inferior meatus. To preserve the adjacent teeth, the maxilla should be divided 4 to 5 mm above their apical roots, and perhaps this is another reason for division of the maxilla at a higher level. The osteotomy does not pass through a growth center (32).

The authors have come to appreciate the importance of improved humidification of the nasal airway to limit or prevent postoperative nasal crusting associated with superficial infection of the walls of the surgical defect. Preservation of the inferior turbinate and reduction of the size of the surgical defect practically eliminate this handicap for the patient. The size of the surgical defect is reduced not only by preservation of the inferior turbinates but by the application of multiple small fat grafts. These 2- to 4-cm strips of abdominal fat are made to adhere to the wall of the defect and exposed dura. Additional fat is introduced into the lumen of the sinonasal defect. The fat not only adheres to the walls of the defect, but is soft enough to occupy space, solid enough to serve as a substitute for a rayon nasal pack to control bleeding, and its texture is smooth enough to be easily removed. Montgomery's (140) experimental evidence indicates that varying amounts of fat will survive and that the remaining fat is replaced by fibrous tissue, especially in those implants that are severely traumatized. He reports that adipose tissue seems to resist infection. It will completely obliterate a frontal sinus after sinusectomy. The fat survives by revascularization.

The authors are pleased that patient morbidity has lessened since they discontinued the use of a postoperative na-

продолжение

sogastric tube, percutaneous esophageal gastrostomy. pharyngotomy, and a tracheostomy. Ambulation and rehabilitative jaw exercises are begun the day after surgery and have eliminated restriction of jaw motion.

In light of the investigative work of Lanigan and West (141), Bell et al. (22), and Nelson et al. (24), the blood supply to the maxilla is better understood. The authors have taken advantage of this new information and their technique has been modified accordingly. As a result, the authors' patients have not been troubled with postoperative hemorrhage, maxillary necrosis, permanent oronasal fistula, loss of teeth, or nasal vestibular stenosis. Pending further investigation, care should be taken not to divide the soft palate in the midline in association with a unilateral extended maxillotomy for fear of interference with the blood supply to the homolateral palate. It seems feasible, however, that there should be abundant anastomoses between the soft palate vessels and the greater palatine artery branches, even if this artery is ligated. Division of the adjacent lateral wall of the oropharynx with its soft palate attachment and retraction of the palate toward the midline carries with it less risk of palate necrosis. On the other hand, Brown et al. (85), Wei et al. (83,84), and Altemir (861 use a similar approach with their maxillary swing procedure. They detach the maxilla from the soft palate and allow it to remain attached to the cheek flap. Its blood supply is from the transverse branch of the external maxillary artery. Necrosis of the maxilla did not complicate healing, and the soft palate remained intact.

Since elimination of the Weber-Fergusson incision, facial scarring has been eliminated. To promote maximum blood supply to the maxilla and in light of the investigative work mentioned previously, the authors make a special effort to permit as much mucoperiosteum of the maxilla as possible to remain in contact with the bone. These tissues are important for the transportation of anastomotic vessels. For this reason, the initial sublabial incision is made at the very apex of the gingivobuccal gutter. A compression dental plate applied to the hard palate would compromise its blood supply and should be avoided.

Surgical exposure and ligation of the internal maxillary artery is preferable before division of the maxilla. This exposure is sometimes difficult. It is made less difficult if the coronoid process of the mandible is removed above the level or entrance of the inferior maxillary nerve and vessels. This maneuver does not increase the limitation of postoperative jaw motion. Although ankylosis of the temporomandibular joint has been eliminated with rehabilitation of jaw motion by the Therabite device, the occasional patient experiences stiffness of jaw motion.

The development of the bilateral septal, floor of the nose, and lateral nasal wall flaps that are based on the soft tissues attached to the lateral wall of the sphenoid has proved exceptionally helpful in assisting in reinforcing the closure of the dural defect in the sphenoclival area.

продолжение

SUMMARY

Given the numerous modalities of treatment that have been designed for the management of the many craniocervical/skull base conditions affecting the patient, the surgeon must select a method of management that satisfies the goals that have been established by the surgeon and the patient. The surgical procedure selected should provide adequate exposure for correction of the abnormality, a watertight dural closure if possible, and satisfactory reconstruction of the surgical defect, and it should permit postoperative rehabilitative management. To accomplish this, the surgeon must take into account the biologic nature of the condition to be treated, the extent of the disease, his or her experience, as well as the morbidity and mortality rates and the economic resources of the patient and his or her family.

REFERENCES

1. Cocke EW Jr, Robertson JH. Robertson JT. Crook JP. The extended maxillotomy and subtotal maxillectomy for excision of skull base tumors. *Arch Otolaryngol Head Neck Surg* 1990; 116:92.
2. von Langenbeck B. Beitrage zur Osteoplastik: Die osteoplastiche Resektion des Oberkiefers. In: Goschen A, ed. *Deutsche Klinik.* Berlin: Reimer, 1859.
3. von Langenbeck B. Osteoplastische Resektion des Oberkiefers. *Deutsche Klinik* 1861;29:281.
4. Cheever DW. Nasopharyngeal polypus attached to the basilar process of occipital and body of the sphenoid bone successfully removed by a section, displacement, and subsequent replacement and reunion of the superior maxillary bone. *Boston Medical and Surgical Journal* 1867;8:162.
5. Moloney F, Worthington P. The origin of the LeFort 1 maxillary osteotomy: Cheever's operation. *Journal of Oral Surgery* 1981;39:731.
6. Lanz O. Osteoplastische Resektion bei der Oberkiefer nach Kocher. In: Lucke R, ed. *Deutsche Zeitschrift fiir Chirurgie.* Leipzig: Vogel, 1893:423.
7. Partsch C. Eine neue Methode temporarer Gaumen-Resektion. *Archiv fiirKlinische Chirugie* 1898:57:847.
8. LeFort R. Etude experimentale sur les fractures de la machoire superieure. *Revue de Chirurgie* 1901;23:208.
9. LSwe L. Weitere Mitteilungen iiber die Ausraumnug der Nase vom Munde her. In: Schech P, Schrotter L, eds. *Monatsschrift fiir Ohrenheilkunde.* Berlin: Verlag von Oscar Coblentz, 1902:420.
10. Pincus W. Beitrag zur Klinik und Chirurgie des Nasen-Rachenraumes. *Klinische Chirurgie* 1907;82:110.
11. Wassmund J. *Lehrbuch der praktischen Chirurgie des Mundes and der Kiefer.* Leipzig: Meusser, 1935:215.
12. Axhausen G. Zur Behandlung veralteter disloziert veheilter Oberkieferbrueche. *Deutsche Zahn- und Kieferheilkunde* 1934; 1:334.
13. Steinkamm W. *Pseudo-Progenie und ihre Behandlung diss.* Berlin: 1938.
14. Gillies HG, Rowe NL. L'osteotomie du maxillaire superieur envisagee essentiellement dens les cas de bec-de-liere totale. *Revue de Stomatologie* 1954;55:545.
15. Dingman RO, Harding RL. The treatment of malunited fractures of the facial bones. *Plast Reconstr Surg* 1951;7:505.
16. Cupar I. Die chirurgische Behandlung der form- und stellungsueranderungen des Oberkiefers. *Osterreichische Zeitschrift fur Stomatologie* 1952; 10:473.
17. Obwegeser HL. The temporal approach to TMJ, the orbit, and the retromaxillary-infracranial region. *Head and Neck Surgery* 1985;7:185.

18. Hogeman KE, Wilmar K. Die Vorverlagerung des Oberkiefers zur Korrektur von Gebibanomalien. In: Fortsch R, Kiefer U, eds. *Gesichtschir Hrsg.* Stuttgart: Schuchardt, K Thieme, 1967.
19. Pfeifer G. Die chirurgische Spatbehandlung des deformierten Oberkiefers nach fruheren Spaltoperationen. *Deutsche Zahn- und Kieferheilkunde* 1969:53:34.
20. Drommer RB. The history of the LeFort I osteotomy. *Journal ofMaxillofacial Surgery* 1986; 14:119.
21. Bell WH, LeFort I. Osteotomy for correction of maxillary deformities. *Journal of Oral Surgery* 1975;33:412.
22. Bell WH, Fonseca RJ, Kennedy JW III, Levy BM. Bone healing and revascularization after total maxillary osteotomy. *Journal of Oral Surgery* 1975;33:253.
23. Bell WH, Finn RA, Scheideman GD. Wound healing associated with LeFort I osteotomy. *J Dent Res* 1980;59(A):459.
24. Nelson RL, Path MG, Ogle RG, Waite DE, Meyer MW. Quantitation of blood flow after LeFort I osteotomy. *Journal of Oral Surgery* 1977:35:10.
25. Lanigan DT, Hey JH, West RA. Aseptic necrosis following maxillary osteotomies: report of 36 cases. *J Oral Maxillofac Surg* 1990;48:142.
26. Casson PR. Bonnano PC. Converse JM. The mid-face degloving procedure. *Plast Reconstr Surg* 1974;53:102.
27. Conley J, Price JC. Sublabial approach to the nasal and nasopharyngeal cavities. *Am J Surg* 1979:138:615.
28. Maniglia AJ. Indications and techniques of mid-facial degloving. *Arch Otolaryngol Head Neck Surg* 1986; 112:750.
29. Price JC, Holliday MJ, Johns ME, Kennedy DW, Richtsmeier WJ, Mattox DE. The versatile mid-face degloving approach. *Laryngoscope* 1988:98:291.
30. Wood GD, Stell PM. The LeFort I osteotomy as an approach to the nasopharynx, *din Otolaryngol* 1984;9:59.
31. Archer DJ, Young S, Uttley D. Basilar aneurysms: a new transclival approach via maxillotomy. *J Neurosurg* 1987:67:54.
32. Belmont JR. The LeFort I osteotomy approach for nasopharyngeal and nasal fossa tumors. *Arch Otolaryngol Head Neck Surg* 1988:114:751.
33. Uttley D, Moore A, Archer DJ. Surgical management of midline skull base tumors: a new approach. *J Neurosurg* 1989;71:705.
34. Brown DH. The LeFort I maxillary osteotomy approach to surgery of the skull base. *J Otolaryngol* 1989; 18:289.
35. Morril KW, Foster J, Haid RW. The LeFort I osteotomy as an approach to the mid-cranial base for tumor resection: Case report. / *Oral Maxillofac Surg* 1993:51:82.
36. Sasaki CT, Lowlitcht RA, Astrachan DI. LeFort I osteotomy approach to the skull base. *Laryngoscope* 1990; 100:1073.
37. Sandor GKB, Charles DA, Lawson VG. Transoral approach to the nasopharynx and clivus using the LeFort I osteotomy with mid-palatal split. *Int J Oral Maxillofac Surg* 1990; 19:352.
38. James D. Crockard HA. Surgical access to the base of skull and upper cervical spine by extended maxillotomy. *Neurosurgery* 1991;29:411.
39. Anand VK, Harkey HL, Al-Mefty O. Open-door maxillotomy approach for lesions of the clivus. *Skull Base Surgery* 1991;1:217.
40. O'Reilly GO, Crockard HA, Lightman S, James DR, Phillips RH, Smith M. Excision of a clival and upper cervical pheochromocytoma by an extended maxillotomy approach: a case report. *Skull Base Surgery* 1993;3:87.
41. Catalano PJ, Biller HF, Sachdev V. Access to central skull base via a modified LeFort I maxillotomy: the palatal hinge flap. *Skull Base Surgery* 1993;3:60.
42. Fisch U. Fagen P, Valvanis A. The infratemporal fossa approach for the lateral skull base. *Otolaryngol Clin North Am* 1984:17:513.
43. Schuller DE, Goodman JH, Brown BL, Frank JE, Ervin-Miller KJ. Maxillary removal and reinsertion for improved access to anterior cranial base tumors. *Laryngoscope* 1992; 102:203.
44. Mann WJ, Gilsbach J, Seeger W, Floel H. Use of malar bone graft to augment skull base access. *Archives of Otolaryngology* 1985;! 11:30.
45. Sami LL, Gircis H. Transzygomatic approach for nasopharyngeal fibromata with extrapharyngeal extension. *J Laryngol Otol* 1965; 79:782.
46. Joseph M. Pedicled rhinotomy for exposure of the clivus. In: Schmidek HH, Sweet WH, eds. *Operative neurosurgical techniques.* 3rd ed. Philadelphia: WB Saunders, 1995:469.
47. Snow RB, Patterson RR. Surgical treatment of tumors of the clivus and basioccipital region. In: Schmidek HH, Sweet WH, eds. *Operative neurosurgical techniques.* 2nd ed. New York: Grune & Stratton, 1988:635.

48. Lee KJ, Goodrich 1, Pensak M. Pituitary surgery: current status ineluding transsphenoidal surgery. *Am J Otolaryngol* 1984;5:138.
49. Papcl ID, Kennedy DN, Cohn EC. Sublabial transseptal transsphenoidal approach to the skull base. *Ear Nose Throat J* 1986:65:107.
50. Laws ER Jr. Transsphenoidal surgery for tumors of the clivus. *Otolaryngol Head Neck Surg* 1984;92:100.
51. Kennedy DW, Cohn ES, Papel ID. Transsphenoidal approach to the sella. *Laryngoscope* 1984;94:1066.
52. Lalwani AK, Kaplan MJ. Gutin PH. The transsphenoidal approach to the spheroid sinus and clivus. *Neurosurgery* 1992;31:1009.
53. Hardy J. Transsphenoidal hypophysectomy. *J Neurosurg* 1971; 34:582.
54. Crockard HA. The transmaxillary approach to the clivus. In: Sekhar LN. Janecka IP, eds. *Surgerv of cranial base rumors.* New York: Raven Press, 1993:235.
55. Crumley RL, Gutin PH. Surgical access for clivus chordoma: the Uni versity of California, San Francisco experience. *Arch Otolarvngol Head Neck Surg* 1989;! 15:295.
56. Sataloff RT, Bowman C, Baker SR, Osterholm J. Transfacial resection of intracranial tumor. *Am J Olol* 1988;9:222.
57. WeisslerMC. Transoral approaches to the skull base. *Ear Nose Throat J* 1991;70:587.
58. Miller E, Crockard HA. Transoral transclival removal of anteriorly placed meningiomas at the foramen magnum. *Neurosurgerv* 1987; 20:966.
59. Pastzor E, Vajda P, Piffko P, Horvath M, Gador I. Transoral surgery for craniocervical space-occupying processes. *J Neurosurg* 1984:60: 276.
60. Mullan S, Naunton R. Hekmat-Panah J, Vailati G. The use of an anterior approach to ventrally placed tumors in the foramen magnum and vertebral column. *J Neurosurg* 1966:24:536.
61. Crockard HA. The transoral approach to the base of the brain and upper cervical cord. *Ann R Coll Surg* 1985; 167:321.
62. Crockard HA, Bradford R. Transoral transclival removal of a schwannoma anterior to the craniocervical junction: case report. *J Neurosurg* 1985;62:293.
63. Crockard HA, Sen CN. The transoral approach for the management of intradural lesions at the craniovertebral junction: a review of seven *cases. Neurosurgery* 1991;28:88.
64. Crockard HA. Transoral approach to intra- and extradural tumors. In: Sekhar LN, Janecka IP, eds. *Surgery of cranial base tumors.* New York: Raven Press, 1993:225.
65. DeLorenzo N, Fortuna A, Guidetti B. Craniovertebral junction malformations: clinicoradiological findings, long-term results and surgical indications in 63 cases. *J Neurosurg* 1982;57:603.
66. Eisemann ML. Spheno-occipital chordoma presenting as a nasopharyngeal mass: a case report. *Annals of Otology* I980;89:271.
67. Hadley MN. Spetzler RF, Sonntag VK. The transoral approach to the superior cervical spine: a review of 53 cases of extradural cervicomcdullary compression. *J Neurosurg* 1989:71:16.
68. Haselden FG, Brice JG. Transoral clivcctomy: a case report. *Journal of Maxillofacial Surgery* 1978:6:32.
69. Handa J, Suzuki F, Nioka H, Koyamy T. Clivus chordoma in childhood. *Surg Neural* 1987:28:58.
70. Gilsbach J, Eggert HR. Transoral operations for craniospinal malformations. *Neurosurg Rev* 1983:6:199.
71. Delgado TE, Buchheit WA. Surgical management of tumors in and around clivus via transoral approach. *Contemporary Neurosurgery* 1982;4:1.
72. Cook BR, Vries JK, Martinez AJ. Malignant fibrous histiocytoma of clivus: case report. *Neurosurgery* 1987;20:632.
73. Menezes AH, VanGilder JC. Transoral-transpharyngeal approach to the anterior craniocervical junction. *J Neurosurg* 1988:69:895.
74. Guthkelch AN, Williams RG. Anterior approach to recurrent chordomas of the clivus: technical note. *J Neurosurg* 1972;36:670.
75. Precechtel A. Transpalatine operation for choanal atresia. *Annals of Otolaryngology* 1938;87:1014.
76. Ruddy LW. A transpalatine operation for congenital atresia of the choanae in the small child or infant. *Archives of Otolaryngology* 1945;41:432.
77. Tu GY, Hu YH, Xu GZ, Ye M. Salvage surgery for nasopharyngeal carcinoma. *Arch Otolaryngol Head Neck Surg* 1988;! 14:328.
78. Donald PJ, Bernstein LB. Transpalatal excision of the odontoid process. *Transactions of the American Academy of Ophthalmology and Otolaryngology* 1978:86:729.
79. Loeb HW. *Operative surgery of nose, throat and ear.* St. Louis: CV Mosby, 1917:1.
80. Wilson CP. The approach to the nasopharynx. *Proc R Soc Med* 1951:44:353.
81. Kennedy DW, Papel ID, Holliday M. Transpalatal approach to the skull base. *Ear Nose Throat J* 1986;65:125.
82. Cocke EW Jr, Braund RR. Superior maxillary resection. In: Cooper P. ed. *The craft of surgery.* 2nd ed. Boston: Little, Brown & Company. 1964:82.
83. Wei WI, Lam KH, Sham JST. New approach to the nasopharynx: the maxillary swing approach. *Head Neck* 1991;13:200.
84. Wei WI, Ho CM, Yuen PW, Fung CF, Sham JST, Lam KH. Maxillary swing approach for resection of tumors in and around the nasopharynx. *Arch Otolaryngol Head Neck Surg* 1995:121:638.
85. Brown AMS. Lavery KM, Millar BG. The transfacial approach to the post-nasal space and retromaxillary structures. *Br J Oral Maxillofac Surg* 1991:29:230.
86. Altemir HF. Temporal disarticulation pedicled to cheek of the upper maxilla(s) as transfacial way of approach to the mainly retromaxillaiy regions and other indications: a new technique. *Estoma* 1982:3:75.
87. Altemir FH. Transfacial access to the retromaxillary area. *Journal of Maxillofacial Surgery* 1986:14:165.
88. Fisch U. The infratemporal fossa approach for nasopharyngeal tumors. *Laryngoscope* 1893:93:36.
89. Donald PJ. Infratemporal fossa and skull base. In: Donald PJ. ed. *Head and neck cancer: management of the difficult case.* Philadelphia: WB Saunders, 1984:277.
90. Maran AGO. Surgical approaches to the nasopharynx, *din Otolai-yngol* 1983:8:417.
91. Denker A, Kahler O. *Handhuch.*
92. Hayakana T, Kamikawa K, Ohniski T, Yoshimine T. Prevention of post-operative complications after a transoral transclival approach to basilar aneurysms: technical note. *J Neurosurg* 1981;54:699.
93. Alonso WA, Black P, Connor GH. Transoral transpalatal approach for resection of clival chordoma. *Laryngoscope* 1971 ;81:1626.
94. DiLorenzo N, Palantinsky E, Bardelia L, Malei A. Benign osteoblastoma of the clivus removed by a transoral approach: case report. *Neurosurgery* 1987;20:52.
95. Krespi YP, Har-El G. Surgery of the clivus and anterior cervical spine *Arch Otolaryngol Head Neck Surg* 1988;! 14:73.
96. Krespi YP, Har-El G. The transmandibular-transcervical approach to skull base. In: Sekhar LN, Janecka IP, eds. *Surgery of cranial base tumors.* New York: Raven Press, 1993:261.
97. Krespi YP, Levine TM, Oppenheimer R. Skull base chordomas. *Otolargyngol din North Am* 1986;19:797.
98. Krespi YP, Sisson GA. Transmandibular exposure of the skull base. *Am J Surg* 1984; 148:534.
99. Attia EL, Bentley RC, Head T, Mulder D. A new external approach to the pterygomaxillary fossa and parapharyngeal space. *Head and Neck Surgery* 1984;6:884.
100. Biller HF, Lawson W. Anterior mandibular-splitting approach to the skull base. *Ear Nose Throat J* 1986;65:134.
101. Kremen A. Surgical management of angiofibroma of nasopharynx. *Ann Surg* 1952; 138:672.
102. Delgado TE, Garrido E, Harwick RD. Labiomandibular transoral approach to chordomas in the clivus and upper cervical spine. *Neurosurgery* 1981;8:675.
103. Arbit E, Patterson RH Jr. Combined transoral and median labiomandibular glossotomy approach to the upper cervical spine. *Neurosurgery* 1981 ;8:672.
104. Wood BG, Sadar ES, Levine HL, Dohn DF, Tucker HM. SurgkV problems of the base of the skull base. *Archives of Otolaryngolo^* 1980:106:1.
105. Yumoto E, Okamura H, Yanagihara N. Transmandibular transpter> gold approach to the nasopharynx, nasopharyngeal space and skiL base. Am? *Otol Rhinol Laryngol* 1992;101:383.
106. McAfee PC, Bohlman HH, Riley LH Jr. The anterior retropharynge.. approach to the upper part of the cervical spine. *J Bone Joint Surg A><* 1987:69:1371.
107. Southwick WO, Robinson RA. Surgical approaches to the vertebra bodies in the cervical and lumbar regions. / *Bone Joint Surg A"* 1957;39:631.
108. Stevenson GC, Stoney RJ, Perkins RK, Adams JE. A transcervica transclival approach to the ventral surface of the brainstem for removal of a clivus chordoma. *J Neurosurg* 1966;24:544.

109. Lesoin F, Jomin M, Pellerin P. Transclival transcervical approach to the upper cervical spine and clivus. *Acta Neurochir* 1986;80:100.
110. Harwick RD, Miller AS. Craniocervical chordomas. *Am J Surg* 1979;138:512.
111. Wissinger JP, Danoff D, Wisiol ES, French LA. Repair of aneurysm of the basilar artery by a transclival approach. *J Neurosurg* 1967;26:406.
112. Fox JL. Obliteration of midline vertebral artery aneurysm via basilar craniectomy. *J Neurosurg* 1967:26:406.
113. Komisar A, Tabaddor K. Extrapharyngeal (anterolateral) approach to cervical spine. *Head and Neck Surgery* 1983:6:600.
114. Fee WE Jr. Roberson JB Jr. Goffinet DR. Long-term survival after surgical resection for recurrent nasopharyngeal cancer after radiotherapy failure. *Arch Otolargyngol Head Neck Surg* 1991:117:1233.'
! 15. Fee WE Jr, Gilmer PA. Goffinet DR. Surgical management of recurrent nasopharyngeal carcinoma after radiation failure at the primary site. *Laryngoscope* 1988:98:1220.
116. Biller HF, Shugar JMA, Krespi YP. A new technique for wide field exposure of the base of the skull. *Archives of Otolaryngology* 1981:107:698.
117. Paavolainen M, Malmberg H. Sublabial approach to the nasal and paranasal cavities using nasal pyramid osteotomy and septal transection. *Laryngoscope* 1986:96:106.
118. Gay E, Sekhar LN, Rubinstein E, et al. Chordomas and chondrosarcomas of the cranial base: results and follow-up of 60 patients. *Neurosurgery* 1995;36:887.
119. Couldwell WT, Fukushima T. Petroclival meningiomas: surgical experience in 109 cases. *J Neurosurg* 1996;84:20.
120. Sekhar LN, Narayana KS. Surgical excision of meningiomas involving the clivus: pre-operative and intra-operative features as predictors of post-operative functional deterioration. *J Neurosurg* 1994;81:860.
121. Beals SP, Joganic EF. Transfacial exposure of anterior cranial fossa andclival tumors. *BNI Quarterly* 1992:8:2.
122. Janecka IP, Sekhar LN. Anterior and anterolateral craniofacial resection. In: Sekhar LN, Janecka IP, eds. *Surgem of cranial base tumors.* New York: Raven Press, 1993:147.
123. Arriaga MA, Janecka IP. Facial translocation approach to the cranial base: the anatomical basis. *Skull Base Surgery* 1992,1:26.
124. Al-Mefty O, Fox JL, Smith RR. Petrosal approach for petroclival meningiomas. *Neurosurgery* 1988;22:510.
125. Gushing HW, Eisenhart L. *Meningiomas: their classification, regional behavior, life history, and surgical end results.* Springfield, IL: Charles C Thomas Publisher, 1938.
126. Derome PJ. Guiot GL. Surgical approaches to the sphenoidal and cli-val areas. *Adv Tech Stand Neurosurg* 1979;6:101.
127. Fisch U. Infratemporal fossa approach to tumors of the temporal bone and base of the skull. *J Laryngol Otol* 1978:92:949.
128. Hitselberger WE, House WF. A combined approach to the cerebellopontine angle: a suboccipital/petrosal approach. *Archives of Otolaryngology* 1966:84:267.
129. House WF, De La Cruz A. Hitselberger WE. Surgery of the skull base: transcochlear approach to the petrous apex and clivus. *Archives of Otolaryngology* 1978:86:770.
130. Kawase T, Shiobara R, Toya S. Anterior transpetrosal/transtentorial approach for spheno/petroclival meningiomas: surgical method and results in 10 patients. *Neurosurgery* 1991 ;28:869.
131. King TT. Combined translabyrinthine/transtentorial approach to acoustic nerve tumors. *Proc R Soc Med* 1970:63:780.
132. Malis LI. Suboccipital subtemporal approach to petroclival tumors. In: Wilson CB, ed. *Neurosurgical procedures: personal approaches to classic operations.* Baltimore: Williams & Wilkins, 1992:41.
133. Sakaki S, Takeda S. Extended middle fossa approach combined with a suboccipital craniectomy to the base of the skull in the posterior fossa. *Surg Neural* 1987;28:245.
134. Samii M, Ammirati M, Mahran A. Surgery of petroclival meningiomas: a report of 24 cases. *Neurosurgery* 1989:23:12.
135. Rosomoff HL. The subtemporal transtentorial approach to the cerebellopontine angle. *Laryngoscope* 1971 ;81:1448.
136. Sen CN, Sekhar LN. An extreme lateral approach to intradural lesions of the cervical spine and foramen magnum. *Neurosurgery* 1990:27: 197.
137. Spetzler RF, Daspit CP. Pappas CTE. Combined supra- and infratentorial approach for lesions of the petrous and clival regions: experience with 46 cases. *J Neurosurg* 1992:76:588.
138. Yasargil MG, Mortara RW, Curcic M. Meningiomas of basal posterior cranial fossa. *Adv Tech Stand Neurosurg* 1980;7:3.
139. Tessier P, Guiot J, Derome D. Orbital hypertelorism: definite treatment of orbital hypertelorism by craniofacial or by extracranial osteotomies. *Scand J Plast Reconstr Surg* 1973;7:39.
140. Montgomery WW. *Surgery of the upper respiratory system.* Philadelphia: Lea and Febiger, 1971:106.
141. Lanigan DT, West RA. Management of post-operative hemorrhage following the LeFort I maxillary osteotomy. *Journal of Oral and Maxillofacial Surgery* 1984;42:367.

Surgery of the Skull Base. edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 13

Subcranial Extended Anterior Approach for Skull Base Tumors: Surgical Procedure and Reconstruction

Jo ram Raveh, Kurt Laedrach, Tateyuki lizuka, and Franz Leibinger

The extended anterior subcranial approach differs significantly from more traditional approaches to the skull base in that it allows a broad inferior-anterior access to the skull base planes with tumor exposure along all borders, as opposed to the transfrontal superior route. The authors initially used the subcranial approach in 1978 for the treatment of high-velocity skull base trauma and certain craniofacial anomalies. In 1980, the authors expanded the indications to include the subcranial-subfrontal approach for the resection of various skull base tumors. Osteotomy of the frontonaso-orbital external skeletal frame provides optimum anterior access to the orbital and sphenoethmoid planes and to the nasal and paranasal cavities, while avoiding frontal lobe retraction and external facial incisions characteristic of transcranial and transfacial approaches. The improved visualization of the anterior skull base and sphenoclival region facilitates *en bloc* tumor removal, exposure of the optic nerve, exposure of the anteromedial aspect of the cavernous sinus, and watertight realignment of the anterior cranial base dura. Because extensive frontal lobe manipulation and external facial incisions are avoided with this approach, intensive care unit and overall hospital stay is reduced, related complications are minimized, and postoperative cosmetic appearance is enhanced. The extended anterior subcranial method is therefore an excellent alternative to traditional transfacial-transcranial skull base approaches for the skull base tumors confined to these locations. The subcranial approach was first introduced in 1978 by the senior author (J.R.) for treatment of traumatic disruption of the anterior skull base (1-7). It was later used for correction of congenital and acquired craniofacial anomalies (8-12), and in 1980 it was adapted to the combined removal of various malignant and benign skull base tumors (13-16). Along the evolutionary continuum, the subcranial approach differs significantly from more traditional otolaryngologic and neurosurgical approaches (17-25) and from a number of more recently reported modifications of these techniques (26-29). The differences lie not so much in the location of the frontal craniotomy and nasoorbital osteotomies, because most of the bone flap variations that allow transfrontal access are now well known (30-35), but in the surgical exposure and direction of operative approach. The extended subcranial approach allows broad anterior and inferior exposure of all the planes, including the anterior ethmoid roof up to the clivus, as well as across both orbital roofs toward the temporal bone, which permits precise intradural and extradural tumor resection. This is accomplished by dural detachment from this approach with practically no frontal lobe retraction. The subcranial extended anterior approach enables optimal visualization of the tumor borders toward the dura as well as along the nasal and maxillary sinus extensions. The simultaneous exposure of the cranial as well as caudal aspects of the tumor enables radical *en bloc* removal as well as preservation of the optic nerve, chi-asm, and carotid arteries, if these structures are not directly involved. The avoidance of facial incisions coupled with adequate drainage of the subcranial compartment, orbital cone, and paranasal spaces reduces the incidence of such complications as visible scars, mucus retention/empyema, and infection, as well as the development of pressure within the orbital cone leading to an apex syndrome.

In this chapter, the indications for this approach, the technique, and various aspects concerning reconstruction are highlighted.

J. Raveh, K. Laedrach, T. lizuka: Department of Craniomaxillofacial, Facial Plastic and Reconstructive Surgery, Otolaryngology, Head and Neck Surgery, University of Bern, 3010 Bern, Switzerland.
F. Leibinger: Research Institute, Institute Leibinger GmbH, Friburg, Germany.

PREOPERATIVE EVALUATION

All patients are evaluated by a team that includes members from the departments of radiation therapy, otolaryngol-ogy, and neurologic surgery. Computed tomography scans with bone algorithms and magnetic resonance imaging are performed. Neuroangiography, preoperative embolization, or carotid occlusion, depending on the cerebral blood flow measurements, are performed when appropriate. After the extent of the lesion and the degree of involvement of adjacent structures are defined, the decision is made regarding surgical procedure. The choice of surgical procedure is a combined otolaryngologic-neurosurgical decision, and the location, size, and extent of intracranial expansion of the lesion dictate the borders of the proposed nasofrontal osteotomy and the necessity of combining other skull base and craniofacial approaches. Both the neurosurgical and otolaryngologic elements of the team are responsible for postoperative and follow-up patient care.

SURGICAL TECHNIQUE—TUMOR RESECTION AND RECONSTRUCTION—GENERAL ASPECTS AND RELATED ANATOMY

The subcranial approach affords anterior access to and exposure of the skull base planes and the subcranial compartment, including the nasal lumen, as shown in Fig. 1 A,B. The first step consists of raising a bicoronal flap in the subperiosteal plane, taking care to preserve the pericranium for possible use during reconstruction. The flap is dissected down to the frontozygomatic suture lines bilaterally and to the rhinion and piriform apertures in the midline. The periorbita is dissected from the superior, medial, and lateral walls of the orbit back to the apex on either side, and the anterior ethmoid arteries are ligated. Raising the scalp and face flap induces traction of the orbital contents to a certain degree, but this is harmless. In contrast, a procedure such as lateral permanent retraction of the globes that puts pressure on the orbital contents should be performed carefully and only intermittently. Damage to the optic nerve and orbital contents can be avoided, as is confirmed by the authors' results, as well as their experience with hundreds of cases of skull base trauma and hyperteloric anomalies managed using this same subcranial approach. Depending on the size and extent of both the lesion and frontal sinus, the outline of the nasofrontal segment is planned (see Fig. IB) and titanium mi-croplates or miniplates (see Fig. 1C) for subsequent bone fixation are adapted and drilled. The osteotomy line of the bone flap may be deliberately extended cranially and laterally, depending on tumor extension. Bur holes are then made, and with a dissector protecting the frontal lobe dura at all times, osteotomies are made across the frontal bone, down to and along the orbital roofs, down the medial orbital wall, and along the nasomaxillary grooves just anterior to the lacrimal duct (see Fig. 1A,D). A vertical osteotomy performed anterior to the crista galli allows detachment of the frontonasal segment, avoiding damage to the sagittal sinus or dural tears. Depending on the tumor location, two types of osteotomies are distinguished as follows:

1. *Type /*: Osteotomy of the frontonasal segment, leaving the posterior frontal sinus wall to be removed in a second step (Fig. 2A,B). This procedure is indicated if the tumor involves the posterior wall. The external skeletal frame is removed after dissection of the posterior wall under direct vision, safely and far enough from the tumor borders.
2. *Type II:* One-stage removal of the frontonasal segment, including the posterior frontal sinus (see Fig. 2A,C,D). This procedure is indicated in tumors not involving the posterior wall or having major intracranial extension, making a broad access necessary. The osteotomy borders can be deliberately extended cranially and laterally. Further, in those cases in which the posterior wall is not involved and the tumor is confined to the sphenoid and clival planes.

Both osteotomy types should be performed meticulously and the dura protected by dissectors inserted along the orbital roofs and the conjunction of the posterior frontal sinus wall and ethmoid roof so as not to sever the dura. Dural tears should be avoided by all means because during the further process this often results in a pealing-off and damaging of the dura along relatively large areas. Using the tumor borders as guides, the dura is divided circumferentially around the olfactory groove and the involved dura, followed by severing of the olfactory filaments. For unilateral tumors, the contralateral olfactory filaments may be preserved. If there is no intracranial extension, the olfactory filaments and dura are separated subcranially from the floor of the anterior cranial fossa, starting at the crista galli and back to the planum sphenoidale, without extensive frontal lobe manipulation. Bone from the orbital and ethmoid roofs is removed to facilitate this dissection. The anterior step-by-step exposure enables not only clear definition of the tumor borders but the exposure of vital structures, such as the optic nerve, lateral sphenoid walls, carotid arteries, and chiasm. The clivus can be optimally assessed as well as the nasal lumen, palate, and maxillary sinuses, enabling *en bloc* removal of tumor. With the dura protected by a slim dissector, osteotomy of the planum sphenoidale is a relatively easy procedure. The medial optic nerve canal wall is also unroofed by this access. and the optic chiasm and nerves can be exposed bilaterally. The anatomic configuration after resection is shown in Fig. 2E-H (coronal plane). A schematic drawing and cadaver dissection of the sagittal planes (see Fig. 2I,J) depict the advantages of the subcranial anterior exposure. To avoid unnecessary pressure to the globe as well as herniation and damage to the periorbital tissue during drilling and further manipulations underneath the skull base, the authors developed special retractors (Fig. 3). Both elastic blades can be shifted apart to fit the orbital cavity, thus avoiding herniation of the periorbital fat tissue.

BASIC ASPECTS OF RECONSTRUCTION

Small dural defects are sutured, whereas larger defects resulting from intradural tumor involvement are patched with fascia lata. A second large fascia lata flap is applied using fibrin glue to seal the entire anterior skull base defect, which reaches from the exposed frontal lobes up to the clival area. The lateral borders of the fascia must be adapted between the dura and the lateral resection borders of the orbital roof and sphenoid plane to avoid herniation and provide a watertight seal to the subcranial compartment. To facilitate fascia application, the authors developed an applicator (Fig. 4A) that is inserted with the fascia layer up to the clivus. The intraoperative view depicting the fascia layer *in situ* is shown in Fig. 4B—the fascia lata borders have not yet been inserted between the dura and the osseous resection borders.



FIG. 1. A: Schematic illustration of the subcranial approach and extent of the exposure along the skull base planes. B: Schematic illustration of frontonasal segment osteotomies. The frontal bone osteotomy borders *(A.B)* depend on tumor location and can be extended deliberately. *Dotted lines* indicate orbital roof and lateral nasal wall osteotomies. *Arrows* indicate the osteotomy line, which leaves an anterior part of the nasal bone intact (for indications, see text). C: Application of titanium plates (Institute Leibinger GmbH) before osteotomy enables exact repositioning of the segment. D: Coronal flap (F) and exposure of the orbital cavity and the nasal frame up to the tip of the nose. *O,* retracted orbit; *D,* dissector inserted into the bur hole to protect the dura during the osteotomies; C, chisel indicating the osteotomy anterior to the crista galli.


II
I
J. CHEN
A
B
C
O
O
D
F
O
S
O
C
E
CHEN

FIG. 2. *(Continued.)*

FIG. 2. *Continued.* A: Type I and II osteotomies. The type I osteotomy includes removal of the external frontonasal frame and leaves the posterior wall intact. The type II osteotomy includes the posterior wall. For indications, see text. B: Type I osteotomy with stepwise removal of the posterior wall. The dura is disattached and always protected by a dissector, including the orbital and ethmoid roof. C: Type II segment osteotomy, including the posterior wall. The dissectors protect the dura along the osteotomy lines. D: Removed frontonasal segment (in a patient) showing the osteotomy borders along the orbital (O) roofs. E: Intraoperative view after tumor resection showing a fascia lata layer *(F)* already applied to the frontal lobes. The sella *(arrowheads),* the posterior sphenoid wall *(S),* and superior part of the clivus (C) are clearly visible. O, retracted orbits. F: Schematic drawing indicating the extent of the exposure provided by this approach. G: Corresponding anatomic configuration in a cadaver. *Arrows* indicate osteotomy borders after removal of the nasofrontal segment. *Sp,* posterior border of the resected sphenoid plane; *S,* posterior sphenoid walls; *C,* clivus. H: Cadaver dissection shows the generous exposure that enables optimal visualization of the optic nerve and chiasm. *Arrows* indicate osteotomy borders along the frontal bone and orbital roof. O, orbit; *A,* apex; *N,* optic nerve and conjunction toward the chiasm; *L,* frontal lobe; S, posterior sphenoid wall; *C,* clivus. I: Schematic drawing of the sagittal plane. Removal of the frontonasal segment *(FS)* provides optimal visualization of the nasal lumen and sphenoclival area. J: Cadaver dissection after removal of the frontonasal segment. The posterior frontal sinus wall and the ethmoidosphenoid planes were left intact to preserve the correct anatomic configuration *(arrows).* This area is always removed to provide optimal exposure of the sphenoclival region. Exposure and visualization of the optic nerve (O), carotid artery *(A),* sphenoid (S), clivus (C), and nasal lumen by this access are optimal.



FIG. 3. A: Orbital retractor developed in cooperation with Institute Leibinger. The blades can be spread and the different elastic features of each enable optimal adjustment toward the orbital cone. B: The retractor *in situ.* The major advantage is that herniation of periorbital fat tissue toward the subcranial compartment can be avoided, as well as damage to the tissue during the drilling process.



FIG. 4. A: Fascia lata applicator developed in cooperation with Institute Leibinger. It is a pick-up with a slim branch and a broad branch that facilitates the application of fascia layers to the sphenoclival and frontal lobes. B: Intraoperative view of the anterior part of the first fascia layer *(F)* already adapted to the frontal lobes. S, sphenoid; O, retracted orbits. *Arrows* indicate osteotomy borders of the frontal segment. 7", preadapted titanium plates. C: Drawing depicting canthal ligament fixation. After replacement of the nasofrontal segment, the canthal ligament *(C)* is fixed by a thread guided underneath the skull base to the contralateral frontal sinus wall/supraorbital rim. D: Same patient as in Fig. 4B with repositioned fron-tonasal segment. *Arrows* indicate each canthal ligament thread fixed to the contralateral supraorbital rim.

Only in very extensive resections of the skeletal skull base frame or frontal lobe defects free or pedicled osseomyocutaneous flaps are necessary. Polyethylene tubes are inserted bilaterally into the subcranial compartment and externalized through the nasal lumen. These tubes are left in place for 8 months, allowing frontal drainage to avoid development of an apex syndrome or later mucus retention.

The medial orbital walls are reconstructed with lyophilized cartilage grafts only in those cases in which total removal of the wall was necessary or if the periosteum had to be resected. This procedure is unambiguous in such cases to avoid enophthalmos or strabismus. After removing all of the mucosa from the undersurface, the nasofrontal segment is exactly repositioned, reproducing the original configuration. This position is ensured by the previously adapted titanium microplates or miniplates (see Fig. 4B). Canthal ligament fixation is accomplished by placing a nonabsorbable suture through the ligament and then guiding the suture under the nasofrontal segment to the contralateral anterior frontal sinus wall (see Fig. 4C). Bilateral tightening of the -uture results in medial, downward, and inward pull, thus achieving correct positioning of the canthal ligaments along the vertical, horizontal, and sagittal planes. The intraopera-tive view after correct osteosynthesis and contralateral can-thai ligament fixation with sutures is shown in Fig. 4D.

ISSUES RELATED TO TUMOR LOCATION, CONSEQUENT OSTEOTOMY, AND RECONSTRUCTION

Tumors Located Posterior to the Ethmoid, Sphenoid, and Clivus

^

The giant cell tumor case illustrated in Fig. 5 is representative for this type of location. As depicted in axial, coronal, and sagittal magnetic resonance imaging (MRI) and computed tomography (CT) scans, the tumor extends intracranially, with partial resorption of the sphenoid plane, lateral sphenoid walls, and clivus and direct adjacency to the optic nerves, carotid arteries, and cavernous sinus. In such cases, extension of the frontonasal segment osteotomy as shown in Fig. 5B is sufficient for optimal exposure of the tumor. Furthermore, if no anterior or nasal lumen involvement is manifested, an anterior bridge of the nasal bone can be left intact. The intraoperative view after removal of the tumor (see Fig. 5C) reflects the advantage of a generous exposure. Resection of the ethmoid roof and the involved sphenoid plane enables optimal visualization of the optic nerve and chiasm conjunction, as well as the posterior sphenoid walls and clivus. Exposure and resection of the tumor from the anterior to the distal direction as well as downward enables direct visualization of the tumor borders from various angles and, as in this case, enables meticulous removal of the tumor along the medial optic nerve canal, the sphenoid wall, and the carotid prominence, despite the fact that the bone has grossly been resorbed. Histologic examination confirmed that all borders were tumor free. Comparison of preoperative and postoperative MRI and CT scans (see Fig. 5D-N) shows absence of tumor and the presence of fascia lata and Gelfoam layers. The reconstruction in such cases is relatively simple because the frontonasal segment can be exactly replaced and fixed with the titanium plates that were adapted before the osteotomy (see Fig. 5O). The further aspects of skull base management and canthal ligament fixation are the same as described previously (see Fig. 4). The patient's appearance is shown in Fig. 5P,Q. Three years after surgery, the patient is tumor free with good aesthetic and functional results.

Tumors Involving All Anterior Skull Base Planes with Intracranial as Well as Nasal Lumen and Maxillary Sinus Extension

t

In this category, multiple issues with regard to tumor resection as well as reconstruction need to be considered, including:

- Fragmentation due to tumor involvement of the frontal and, nasal bones makes replacement by bone grafts necessary.
- Tumor extension toward the nasal lumen and maxillary sinuses often makes simultaneous resection of the orbital floor, anterior maxillary sinus wall, and the palate necessary.
- Lateral infratemporal fossa and pterygopalatine extension makes a combined LeFort I osteotomy or lateral approach necessary.
- Reconstruction makes the application of free, pedicled, or revascularized grafts/flaps necessary.

The exposure afforded by the subcranial approach enables radical tumor resection and reconstruction, obviating further transfacial procedures such as lateral rhinotomy or midface splitting, thus avoiding visible skin incisions and damage to intact structures.

Each of the following cases illustrates the various factors alluded to previously, demonstrating the best choice of methods to fulfill the surgical requirements.


Warning: Due to insufficient annotation filming could lead to misdiagnosis.
Film from Display Mode.
A

FIG. 5. Representative case for the surgical management o' tumors located in the posterior ethmoid and sphenoclival region. A: Parasagittal computed tomography (CT) scan showing a giar **cell** tumor located in the sphenoid plane, posterior sphenoid wa and clivus. Bone erosion is manifested. B: Osteotomy borders c the frontonasal segment. O, retracted orbit after exposure of the cone; L, lacrimal duct canal. C: Intraoperative appearance after tumor removal. L, anterior lobes covered by a pad; O, retracted orbits revealing the defect borders after resection of the ethmoid compartment and roof and the sphenoid plane, along with intracrania, tumor extension (no intradural involvement) and the sella floor; *S.* the posterior sphenoid wall; C, partially removed anterior clivus bone. *Arrows* indicate anterior resection borders of the apertura pir-iformis. D: Preoperative axial magnetic resonance image (MRIi indicating the adjacency of the tumor with the carotid arteries, particularly on the left, and with the optic nerves (arrows). E: Postoperative MRI indicating absence of tumor and showing fascia lata layers *(arrowheads).* The medial optic nerve canal walls and the bone along the carotid arteries prominence—lateral sphenoid walls was removed and aligned with an additional fascia layer.


O
L
L
O
B
L
C
S
O
O
KLINIK LINDENHOF BER
MAGNETOM IMPAC
D
E


F
G
R
L
NEURORAD.UNIV.BERN-INSELSPITAL
MAR 28, 1994
14.0cm
kV 120
mA 170
Adult Head
FoV 200*20
Tra
600.0
15.0/1

FIG. 5. *Continued.* F-H: Additional preoperative (F) and postoperative (G) MRIs and CT scan (H) confirming radical tumor removal.

(figure continues)


I
J
K
L
M
N
04-JUN-1968
28-MAR-1994
KLINIK LINDEN
Post CM
16:03
IMAGE 128
STUDY 6
MF 1.40
FoV 200*200
256 *256
Cor
600.0

FIG. 5. *Continued.* **I-L:** Preoperative and postoperative sagittal MRIs. Note absence of tumor. Fascia lata layers applied to the frontal lobes and sphenoclival area can be seen *(arrows).* M,N: Preoperative and postoperative coronal MRIs indicating the extent of tumor, and the fascia layers *(arrowheads)* after tumor removal.



FIG. 5. *Continued.* O: Appearance after replacement and fixation of the frontonasal segment. In this case, the osteotomy *(arrows)* was performed leaving an anterior bridge *(B)* intact. For indications, see text. **P,Q:** The patient's postoperative appearance. Note correct configuration of the frontonasal area and canthal ligaments. The frontal photograph was intentionally performed at an angle to depict the slight enophthalmos. There is no double vision.

CASE 1

This case, illustrated in Fig. 6, demonstrates the surgical management of an extensive esthesioneuroblastoma. Intracranial as well as intranasal extension along with partial resorption of the nasal **buttress** are shown in Fig. 6A. Further involvement of the medial orbital walls and maxillary sinus extension including the orbital floor were evident. The intraoperative view after the removal of the tumor by the subcranial approach is shown in Fig. 6B. The extent of **me** resection along the skull base and radical tumor removal are documented in Figs. 6C-F. Because tumor extension toward the nasal lumen was well defined and encapsulated, only the nasal-maxillary sinus floor mucosa in direct contact had to be removed. Because the mucosa turned out to be tumor free, the hard palate was not resected. Alignment of the bone toward the lumen was done using a pedicled buccal fat pad layer (36) (see Fig. 6F). Reconstruction of the medial orbital wall as well as the orbital floor on the right was performed with lyophilized cartilage layers. Substitution of the tumor-involved frontonasal segment was accomplished with external table bone grafts. The Y-shaped titanium miniplate developed in cooperation with the Leibinger Institute is most suitable for the fixation of the grafts up to the tip of the nose.

CASE 1 (Continued)

Because the plate has been adapted before the osteotomy, reshaping of the grafts and their fixation enable the exact reproduction of the preoperative configuration (see Fig. 6G,H). The external table provides sufficient bone graft material even in more extensive frontal bone defects, as shown in a different case (see Fig. 611. Meticulous reconstruction is crucial for correct reproduction of an aesthetic appearance, as shown in Fig. 6J-M.



FIG. 6. Case 1. A; Preoperative sagittal magnetic resonance image (MRI) showing intracranial and nasal lumen extensions of an esthesioneuroblastoma and involvement and resorption of the nasal bone (arrows). B: Intraoperative appearance after tumor removal. *O.* retracted orbits; *L,* frontal lobes and first fascia lata layer; *S,* posterior sphenoid wall. C: Postoperative sagittal MRI. Note absence of tumor. Fascia lata layers and the nasal external table bone grafts (arrows) are seen. D: Three dimensional computed tomography scan showing the borders of the resected skull base (arrows). S, posterior sphenoid wall.

CASE 1 (Continued!





FIG. 6. Case 1. *Continued.* E: Preoperative coronal MRI showing nasal and maxillary sinus involvement. F: Postoperative coronal MRI showing fascia lata layers and lyophilized cartilage grafts along the media! orbital wall and floor (arrows). *B,* pedicled buccal fat pad for lining of the palate/maxillary sinus floor. **G,H:** Tumor involvement of the frontonasal frame necessitated reconstruction with external table bone grafts. The preadapted Y-shaped titanium plate (Institute Leibinger GmbH) for fixation of the grafts and reconstruction of the lateral nasal walls (L) is crucial for a satisfactory aesthetic result. O, orbit. *Arrows* indicate the thread applied to the left canthal ligament (C) guided underneath the skull base to be fixed to the contralateral supraorbital rim (see Fig. 4c). I: Intraoperative view showing the frontonasal reconstruction in larger defects. *E,* external table donor site (in a different patient).

(figure continues)

CASE 1 (Continued)



FIG. 6. Case 1. *Continued.* **J,K:** Frontal views before surgery and 3 weeks after surgery **(J)** with correct frontonasal configuration. Slight edema of the upper and lower eyelids is still seen **(K). L,M:** Lateral views before **(L)** and after surgery **(M).**

In this case (Fig. 7), the tumor—squamous cell carcinoma previously operated on elsewhere—involved the skull base as well as the palate and the nasal **frame** (see Fig. 7A). The intraoperative appearance after tumor removal (see Fig. 7B), including resection of the ethmoidosphenoid plane, shows the fascia lata already applied along the skull base up to the posterior sphenoid wall and clivus. as well as to the orbital roofs. By this approach, *en bloc* removal of the hard palate along with the tumor was. because of the broad exposure, relatively easy to perform. In Fig. *1C,* the tongue is pulled through the palatine defect up to the skull **base** and is clearly visible. Reconstruction of the palatine defect in such cases is best performed using a temporalis vessel-pedicled external table graft, as shown in Fig. **7D** (a different case). The flap is inserted underneath the zygomatic arch. Depending on the size of the bone



FIG. 7. Case 2. A: Sagittal magnetic resonance image (MRI) showing a squamous cell carcinoma involving the anterior skull base, nasal lumen, and palate. This patient was previously operated on elsewhere. B: Intraoperative view after tumor removal. F, fascia lata *applied* to the frontal lobes and skull base planes; *O,* retracted orbits; S, posterior sphenoid wall. *Arrows* indicate superior frontal and inferior frontonasal segment osteotomy borders. C: Appearance after tumor removal along the nasal cavity along with resection of the palate through same subcranial access. *T,* the tongue pulled through the defect up to the fascia (F) aligning the frontal lobe. D: Reconstruction of such defects: free external table grafts for substitution of the frontonasal segment, and external table flap (7) pedicled by temporal vessels and guided underneath the zygomatic bone, for reconstruction of the palatine defect (different patient).

(figure continues)

CASE 2 (Continued)

graft, the zygoma, including the arch, has to be osteotomized to permit this procedure, and is then refixed with plates and free external table grafts for the back of the nose. The postoperative CT scan in Fig. 7E (same patient as in Fig. 7A-C) shows the cavity after tumor resection as well as part of the plates used for the fixation of nasal bone grafts, which substituted for the tumor-involved frontonasal segment. Another postoperative CT scan of the same patient (see Fig. 7F) demonstrates the palatine bone grafts *in situ* with the dental implants that have simultaneously been inserted i the same primary surgical session. Thus, secondary surgery can 1 avoided and the osseointegration of the implants is optimal. Furthermore, because the dental suprastructure and dental reconstruction are applied 3 months after surgery, function and physiology loads minimize resorption of the bone grafts. Replacement of the palatine mucosa has to be done using a cutaneous revascularized ; free skin flap—in this case, a radialis forearm flap was preferred.!



FIG. 7. Case 2. *Continued.* E: Postoperative computed tomography (CT) scan showing absence of the tumor. *Arrows* indicate the anterior part of the plates used for fixation of the frontonasal free bone grafts. F: Postoperative CT (lower level) showing the pedicled external table graft *in situ* with the simultaneously applied dental implants *(arrows).*

CASE 3

The patient in case 3 presents a skull base tumor with intracranial as well as nasal and maxillary sinus extension, necessitating bone grafting for reconstruction of the orbital cone.

In this case, esthesioneuroblastoma involving the skull base, nasal lumen, and maxillary sinus (Fig. 8A) made resection of the orbital floor and anterior maxillary sinus wall, as well as hemire-section of the palate, necessary. The extent of the radical resection is manifested in Fig. 8B, which also shows absence of tumor. In this level of the MRI, the bone transplants applied in the same session are not clearly represented. The external table bone grafts for the reconstruction of the supraorbital rim, orbital floor, anterior maxillary sinus wall, and lateral palatine defect were applied by the transconjunctival and intraorbital approach (Fig. 8C). The grafts are clearly depicted in the same patient's CT scans (Fig. 8D,E).

CASE 2 (Continued)

graft, the zygoma, including the arch, has to be osteotomized to permit this procedure, and is then refixed with plates and free external table grafts for the back of the nose. The postoperative CT scan in Fig. 7E (same patient as in Fig. 7A-C) shows the cavity after tumor resection as well as part of the plates used for the fixation of nasal bone grafts, which substituted for the tumor-involved frontonasal segment. Another postoperative CT scan of the same patient (see Fig. 7F) demonstrates the palatine bone grafts *in situ* with the dental implants that have simultaneously been inserted in the same primary surgical session. Thus, secondary surgery can be avoided and the osseointegration of the implants is optimal. Furthermore, because the dental suprastructure and dental reconstruction are applied 3 months after surgery, function and physiologic loads minimize resorption of the bone grafts. Replacement of the palatine mucosa has to be done using a cutaneous revascularized free skin flap—in this case, a radialis forearm flap was preferred.



FIG. 7. Case 2. *Continued.* E: Postoperative computed tomography (CT) scan showing absence of the tumor. *Arrows* indicate the anterior part of the plates used for fixation of the frontonasal free bone grafts. F: Postoperative CT (lower level) showing the pedicled external table graft *in situ* with the simultaneously applied dental implants *(arrows).*

CASE 3

The patient in case 3 presents a skull base tumor with intracranial as well as nasal and maxillary sinus extension, necessitating bone grafting for reconstruction of the orbital cone.

In this case, esthesioneuroblastoma involving the skull base, nasal lumen, and maxillary sinus (Fig. 8A) made resection of the orbital floor and anterior maxillary sinus wall, as well as hemire-section of the palate, necessary. The extent of the radical resection is manifested in Fig. 8B, which also shows absence of tumor. In

продолжение

this level of the MRI, the bone transplants applied in the same session are not clearly represented. The external table bone grafts for the reconstruction of the supraorbital rim, orbital floor, anterior maxillary sinus wall, and lateral palatine defect were applied by the transconjunctival and intraorbital approach (Fig. 8C). The grafts are clearly depicted in the same patient's CT scans (Fig. 8D,E).

CASE 3 (Continued)





FIG. 8. Case 3. A: Preoperative coronal magnetic resonance image (MRI) showing extension of an esthesioneuroblastoma toward the nasal and maxillary sinus cavity, involving the medial orbital wall and floor as well as the palate. B: Postoperative MRI showing the extent of the resection; note absence of tumor and presence of fascia lata layers *(arrows)*. The bone grafts are only partially seen on this level. C: Intraoperative view showing the transconjunctival approach. *L,* lower lid; *N,* lateral nasal wall. The infraorbital rim, floor of orbit *(F),* and anterior maxillary sinus wall *(W) are* fixed by titanium plates. D,E: Postoperative coronal and axial computed tomography scans showing the applied pedicled palatine (P) and free orbital floor and anterior maxillary sinus wall external table grafts *(arrows)*. The advantages of the subcranial approach in avoiding additional transfacial approaches are convincing.


FOV 14.0cm
STND
R

D



E

CASE 4

In this case (Fig. 9), a juvenile angiofibroma tumor was located in the nasal-maxillary sinus lumen as well as the skull base up to the sphenoclival area. Preoperative and postoperative MRI and CT scans depict the extent of the resection. To achieve a radical resection, the medial wall and orbital floor on both sides as well as the palate-maxillary sinus floor on the right side had to be removed. An external table graft was applied to the palate defect on the right side and aligned with the maxillary sinus lumen by a pedicled fat pad layer (see Fig. 9D). For the reconstruction of the medial and orbital floor on both sides, a combination of lyophilized cartilage layers and external bone grafts was preferred (see Fig. 9E). The patient's preoperative and postoperative appearance is shown in Fig. 9F-I.



FIG. 9. Case 4. A: Preoperative sagittal magnetic resonance image (MRI) showing tumor with anterior and sphenoclival extensions. B: Postoperative sagittal MRI. Note absence of tumor and presence of fascia lata layers *(arrows).* C: Preoperative coronal MRI showing juvenile angiofibroma tumor involving the skull base, nasal lumen, and maxillary sinus. D: Postoperative coronal computed tomography scan showing absence of tumor and the extent of the resection along the sphenoid plane, as well as fascia lata layers *(arrowheads).* Through the resected retromaxillary pterygopalatine area *(arrowheads),* the pedicled buccal fat pad *(B)* is seen lining the palatine bone graft.

CASE 4 (Continued)


A59.9+C
20:
MF: 1
B
480
16
1/1 16kHz
15
0sp
NEX
180
^
G

FIG. 9. Case 4. *Continued.* E: Deeper MRI level showing absence of tumor. Note fascia lata layers applied to the dura *(arrowhead),* as well as the buccal fat pad *(B; arrows).* F-l: Patient's preoperative and postoperative appearance, indicating adequate reproduction of the preoperative appearance.

(figure continues)

CASE 4 (Continued)



FIG. 9. Case 4. *Continued.*

RESULTS

In this study, only the 104 cases surgically treated by the extended anterior approach up to 1993 are included. A further 45 cases treated between 1993 and 1995 are still in the process of evaluation. Not included are the cases operated on by the lateral approach. The follow-up corresponds to a previous publication (15).

Patient Population

The patients ranged in age from 4 to 83 years, with a mean age of 61.8 years. There were 59 male and 45 female patients. Fig. 10 shows the histologic composition of the lesion, of which 57 were benign and 47 malignant tumors. Figure 10 also shows the location of the tumors with respect to the skull base. Thirty patients received radiation therapy (11 before surgery, 19 after surgery), 3 patients underwent chemotherapy, and 9 patients had had previous operations for tumor ablation.

Patient Follow-up

The state of disease at follow-up is indicated in Table 1. Fifty-one (89%) of 57 patients with benign and 31 (68%) of 47 patients with malignant lesions were alive with no evidence of disease. Mean follow-up time in months is indicated in parentheses in the table. Because frontal lobe retraction was avoided, immediate postoperative recovery was accelerated. Even in the case of large tumors with extensive resection, the stay in the intensive care unit was reduced to an average of 2 days, and hospital stay was limited to 11 to 12 days.

Postoperative Complications

Early and late postoperative complications are listed in Table 2. Recurrent cerebrospinal fluid (CSF) leakage occurred in three patients; in one patient accidental removal of nasal packing on postoperative day 1 resulted in an immediate CSF leak. This patient was treated by lumbar CSF drainage, and the leak was successfully controlled. In the second and third cases, inadequate primary dural repair and fascia lata alignment resulted in early CSF leakage. In two other cases a pneumocranium was manifested, and revisions were necessary.

Frontal lobe contusion with edema was observed in one patient who underwent combined transfrontal-subcranial resection. Temporary postoperative seizures occurred in one patient. In two patients, epidural infections occurred and were successfully treated with antibiotic drugs. There were no brain abscesses. Cranial nerve dysfunction (other than ol-



FIG. 10. Histologic types and localization of anterior skull base tumors.

factory) was observed in eight patients and included three optic, one trochlear, two abducens, and two oculomotor nerves affected. The three cases of early optic nerve dysfunction were related to tumor removal at the optic canal or chiasm, and all resolved with time. In the other five patients, compensation occurred and no secondary corrections were necessary. The optimum inferior exposure afforded by the subcranial approach allowed preservation of contralateral olfactory filaments during unilateral tumor resection. In two patients with benign and five patients with malignant tumors, anosmia was not observed as a sequela of skull base tumor removal. None of the patients required facial incisions, and the authors have not observed nasofrontal segment bone resorption in any of their patients to date.

DISCUSSION

The subcranial extended approach and osteotomy of the frontonasoorbital external skeletal frame provides an optimum anterior access to the anterior skull base and spheno-clival region, as well as to the nasal and paranasal cavities.

TABLE 1. *Tumor diagnosis and survival'*

	State of disease				
Histology	A&W	AWD	DOD	DOC	No. of cases
Benign					
Adenoma	4 (19)				4
Angioma	6 (13)				6
Angiofibroma	7 (12)			1 (10)	7
Fibrous dysplasia	4 (21)				4
Giant cell tumor	1 (3)				1
Inverted papilloma	11 (22)	3 (20)		1 (18)	14
Meningioma	7 (24)	1 (36)			8
Neurofibroma	1 (5)				1
Osteoma	12 (10)				12
Total	51	4		2	57
Percent	89	7		4	100
Malignant					
Adenocarcinoma	6 (37)	2 (30)	3 (6)		11
Adenoid cystic carcinoma	2 (30)	2 (15)			4
Basal cell carcinoma	2 (15)				2
Clear cell carcinoma	1 (13)				1
Esthesioneuroblastoma	7 (13)			1 (63)	8
Melanoma	2 (30)	1 (14)		1 (36)	4
Non-Hodgkin's lymphoma	2 (34)				2
Sarcoma	4 (10)	1 (8)			5
Squamous cell carcinoma	6 (24)	2 (11)	2 (8)		10
Total	32	8	5	2	47
Percent	68	17	11	4	100
Total cases	**83**	**12**	**5**	**4**	**104**

A&W, alive without disease; AWD, alive with disease; DOD, died of disease; DOC, died of other causes. [a] Numbers in parentheses indicate mean follow-up period in months.

C>

Table 2. *Postoperative complications (N = 104)*

Complications	No. of cases
Early	
Cerebrospinal fluid leaks	3
Frontal lobe contusion/edema	1
Epidural infection	2
Pneumocranium	2
Pulmonary embolism	1
Partial local flap necrosis	2
Cutaneous fistula	2
Temporary siezures	2
Optic nerve dysfunction	3
Late	
Frontal sinus dysfunction	1
Epiphora	1
Cranial nerve dysfunction	
Olfactory	73
Oculomotor	2
Abducens	2
Trochlear	1
Optic	0

Accurate delineation of tumor margins and dural excision are facilitated by this approach. Because the tumor borders are exposed from the anterior to posterior as well as from the cranial to distal (and vice versa) directions, accurate visualization of the optic nerves along the canal and chiasm and the carotid arteries, and the prevention of unnecessary damage, comprise major advantages. In cases of unilateral lesions, the contralateral olfactory filaments can often be preserved. Optic nerve exposure and decompression by removal of the medial optic nerve canal walls is readily performed. The sub-cranial approach can be combined with an intraoral access or a LeFort I osteotomy for lateral retromaxillary-sphenopala-tine extensions. Thus, *en bloc* removal of virtually all tumor extensions, including those into the epipharyngeal and clival area, while sparing the optic chiasm, is facilitated.

Because of the broad exposure obtained, further transfacial approaches are unnecessary. Skull base tumors have been surgically approached in various ways since the early 1970s. The transbasal-transethmoidal approach to the skull base, initially described by Escher (19,37) and Naumann (22), has been well known to otolaryngologists since the late 1940s. In 1972, Derome et al. (18) described the transbasal removal of sphenoethmoid tumors using a similar technique. Jane et al. (38), Jackson (33), and others (30-32,34,35) have described various orbital osteotomies for access to intracranial and extracranial skull base lesions. Combinations of transcranial and transfacial approaches were initially reported by Smith et al. (39), Ketcham et al. (40), and Van Buren et al. (41), and later by Donald (42). Modifications of these techniques by Sekhar et al. (29) and Rinehart et al. (28) have appeared in the literature. All of these techniques differ slightly in the planning and positioning of the facial and cranial osteotomies, and all except the subcranial method advocate a transfrontal approach with unavoidable retraction of the frontal lobes, even when an attempt is made to minimize such manipulation. In addition, the accepted methods of transfacial approach, such as the lateral, superior, and midline rhinotomies, require significant external facial incisions that are completely avoided by the subcranial extended exposure.

Transfrontal access also implies that the tumor is exposed in a superior to inferior direction. On the one hand, particularly for tumors located underneath the sphenoid plane and clivus, this direction does not provide the necessary visualization. Apart from tumor extension toward the nasal lumen, the epipharynx and maxillary sinuses cannot be assessed. This also makes further combined transfacial procedures necessary. On the other hand, in transfacial approaches, the exposure is performed in the anterior to posterior direction, providing insufficient exposure of tumor borders, particularly for sphenoclival and intracranial tumor extensions. This factor, as well as the exposure of the optic nerves, optic chiasm, and carotid arteries, often implies a piecemeal removal of the tumor. In contrast, the subcranial extended approach provides tumor exposure from all directions, thus enabling optimal visualization of the tumor and the adjacent vital structures, and avoiding frontal lobe retraction. Delfini et al. (26) and Pinsolle et al. (27) have described and confirmed the advantages of the same subcranial exposure in small series, although they did not refer to any of the current authors' previous publications.

The subcranial exposure also allows for watertight alignment of the dura and anterior skull base after ablative surgery, with an infrequent incidence of postoperative CSF leakage and epidural infection. The frontal subcranial polyethylene drainage tube has proved effective in limiting late infectious sequelae such as chronic sinusitis, mucocele, or brain abscess. Centripetal medial canthal ligament fixation as well as the avoidance of all external facial scars has improved postoperative cosmetics tremendously, and is a distinct advantage over more traditional transfacial methods such as lateral rhinotomy and midline-midface osteotomy. Because the authors' procedure requires little or no frontal lobe retraction, postoperative brain edema and intensive care unit and total hospital stay are reduced, and postoperative recovery is accelerated.

ACKNOWLEDGMENTS

The authors thank the Department of Neuroradiology (Prof. G. Schroth) for outstanding support and cooperation, and Dr. J. Chen (Department of Otolaryngology, Sunnybrooke Health Center, Toronto, Ontario, Canada) for the superb quality of the drawings.

REFERENCES

1. Raveh J. Das einzeitige Vorgehen bei der Wiederherstellung van Frontobasal-Mittelgesichtsfrakturen. Modifikationen und Behandlungsmodalita'ten. *Chirurgie* 1983;117:779.
2. Raveh J, Laedrach K, Vuillemin T, et al. Management of combined frontonaso-orbital/skull base fractures and telecanthus in 355 cases. *Arch Otolaryngol Head Neck Surg* 1992; 118:605.

3. Raveh J, Neiger M. Die Wiederherstellung bei schweren Gesichtsschadelverletzungen. *Schweizer Monatsschrift fur Zahnheilkunde* 1981;91:206.
4. Raveh J, Rcidli M, Markwalder TM. Operative management of 194 cases of combined maxillofacial-frontobasal fractures: principles and modification. *J Oral Maxillofac Surg* 1984:42:555.
5. Raveh J, Vuillemin T. Subcranial management of 395 combined frontobasal-midface fractures. *Arch Otolaryngol Head Neck Surg* 1988; 114:1114.
6. Raveh J, Vuillemin T. The surgical one-stage management of combined cranio-maxillo-facial and frontobasal fractures: advantages of the subcranial approach in 374 cases. *J Craniomaxillofac Surg* 1988; 16:160.
7. Laedrach K, Annino D, Raveh J, Zingg M. Vuillemin T, Leibinger K. Advanced approaches to cranio-orbital injuries. *Facial Plastic Surgery Clinics of North America* 1995:3:107.
8. Raveh J. Neue Aspekte der kraniofazialen Chirurgie. *Schweiz MonatsschrZalmmed* 1986;96:406.
9. Raveh J, Vuillemin T. Advantages of an additional subcranial approach in the correction of craniofacial deformities. *J Craniomaxillofac Surg* 1988;16:350.

: 0. Vuillemin T, Raveh J. The subcranial approach for the correction of hypertelorism. *Journal of Craniofacial Surgery* 1990;! :91.

i 1. Raveh J. Specific procedures: craniofacial congenital anomalies—subcranial osteotomy approach. In: *Principles ami practice of ophthalmic plastic and reconstruction surgery.* Philadelphia: WB Saunders, 1993;16D:8;3.

12. Raveh J, Imola M, Laedrach K, Zingg M, Vuillemin T. Update on corrections of craniofacial anomalies. *Facial Plastic Surgery Clinics of North America* 1995;3:17-38.
13. Raveh J, Laedrach K, Speiser M, et al. The subcranial approach for fronto-orbital and anteroposterior skull base tumors. *Arch Otolaryngol Head Neck Surg* 1993; 119:382.
14. Raveh J, Vuillemin T. The subcranial-supraorbital temporal approach for tumor resection. *Journal of Craniofacial Surgery* 1990; 1:53
15. Raveh I, Turk JB, Laedrach K, et al. Extended anterior approach for skull base tumors: long-term results. *J Neurosurg* 1995;82:1002.
16. Laedrach K, Raveh J. Advantages of the combined subcranial/transfrontal approach for frontal skull base tumor resection. In: *Acta volume of the IV International Congress of the International Society ofCranio-Maxillofacial Surgery.* Bologna: Mondozzu Editore, 1992;4:293.
17. Blackblock JB, Weber RS, Lee YY, et al. Transcranial resection of tumors of the paranasal sinuses and nasal cavity. *J Neurosurg* 1989; 71:10.
18. Derome P, Akerman M, Anquez L. et al. Les tumeurs spenoethmoidales: possibilites d'exerese et de reparation chirurgicales. *Neurochirurgie* 1972;18[Suppl 1]:1.
19. Escher F. Ein Beitrag zur Versorgung frontobasaler Hirnverletzungen. *Pract Otorhinolaryngol* 1944;6:326.
20. Jackson IT, Marsh WR, Hide TAH. Treatment of tumors involving the anterior cranial fossa. *Head and Neck Surgery* 1984;6:901.
21. Lyons BM. Donald PJ. Radical surgery for nasal cavity and paranasal sinus tumors. *Otolaryngol Clin North Am* 1991;24:1499.
22. Naumann HH. Chirurgie der Nasennebenhohle. In: Naumann HH, ed. *KopfundHalschimrgie.* Stuttgart: Thieme, 1974;2:409.
23. Schramm VL Jr, Myers EN, Maroon JC. Anterior skull base surgery for benign and malignant disease. *Laryngoscope* 1979;89:1077.
24. Sekhar LN, Janecka IP, Jones NF. Subtemporal-infratemporal and basal subfrontal approach to extensive cranial base tumours. *Acta Neurochir* 1988;92:83.
25. Irish JC, Gullane PJ, Gentili F, et al. Tumors of the skull base: outcome and survival analysis of 77 cases. *Head and Neck Surgery* 1994; 16:3.
26. Delfini R, lanetti G, Belli E, et al. Cranio-facial approaches for tumors involving the anterior half of the skull base. *Ada Neurochir* 1993;124:53.
27. Pinsolle J, San-Galli F, Siberchicot F, et al. Modified approach for ethmoid and anterior skull base surgery. *Arch Otolaryngol Head Neck Surg* 1991;! 17:779.
28. Rinehart GC, Jackson IT, Potparic Z, et al. Management of locally aggressive sinus disease using craniofacial exposure and the galeal frontalis fascia-muscle flap. *Plast Reconstr Surg* 1993;92:1219.
29. Sekhar LN, Nanda A, Sen CN, et al. The extended frontal approach to tumors of the anterior, middle, and posterior skull base. / *Neurosurg* 1992;76:198.
30. Alaywan M, Sindou M. Pronto-temporal approach with orbito-zygomatic removal: surgical anatomy. *Acta Neurochir* 1990; 104:79.
31. Al-Mefty O. The supraorbital-pterional approach to skull base lesions. *Neurosurgery* 1987;21:474.
32. Hakuba A, Lui SS, Nishimura S. The orbitozygomatic infra-temporal approach: a new surgical technique. *Surg Neural* 1986;26:271.
33. Jackson IT. Craniofacial osteotomies to facilitate resection of tumors of the skull base. In: Wilkins RH, Rengachary SS, eds *Neurosurgery update I.* New York: McGraw-Hill, 1990:277.
34. Johns ME, Kaplan MJ, Park TS, et al. Supraorbital rim approach to the anterior skull base. *Laryngoscope* 1984;94:1137.
35. Tessier P, Guiot G, Rougerie J. Osteotomies cranio-naso-orbito-faciales: hypertelorisme. *Ann Chir Plast* 1967; 12:103.
36. Vuillemin T, Raveh J, Ramon Y. Reconstruction of the maxilla with bone grafts supported by the buccal fat pad after tumour resection. *J Oral Maxillofac Surg* 1988;46:100.
37. Escher F. Clinical classification and treatment of the frontobasal fractures. In: *Disorders of the skull base region.* Stockholm: Almqvist & Wiksell, 1969:33.
38. Jane JA, Park TS, Pobereskin LH, et al. The supraorbital approach: technical note. *Neurosurgery* 1982;! 1:537.
39. Smith RR, Klopp CT, Williams JM. Surgical treatment of cancer of the frontal sinus and adjacent areas. *Cancer* 1954;7:991.
40. Ketcham AS, Hoye RC, Van Buren JM, et al. Complications of intracranial facial resection for tumors of the paranasal sinuses. *Am J Surg* 1966;! 12:591.
41. Van Buren JM, Ommaya AK, Ketcham AS. Ten years' experience with radical combined craniofacial resection of malignant tumors of the paranasal sinuses. *J Neurosurg* 1968;28:341.
42. Donald PJ. Craniofacial surgery for head and neck cancer. In: Johnson JT, Blitzer A, Ossoff RH, et al, eds. *American Academy of Otolaryngology-Head and Neck Surgery: instruction courses.* St. Louis: CV Mosby, 1989;2:225.

Surgery of the Skull Base. edited by Paul J. Donald.
Lippincott-Raven Publishers. Philadelphia © 1998.

CHAPTER 14

Cranioorbital Approach

☐

Alfred P. Bowles, Jr. and Vinod K. Anand

The cranial base is an anatomically complex region encompassing arteries and nerves that intertwine with an irregular bony topography. To improve exposure to lesions in the cranial base, a number of frontolateral approaches have been used based on techniques that incorporate the orbital roof. Several of the techniques used have been reintroduced, modified, and revised to provide surgeons with accessible avenues to lesions in the anterior and middle fossa. With the frontolateral approaches, as with other skull base approaches, the basic premise is that the bone is expendable, not the brain, and with this philosophy, bone flaps incorporating the orbital bone can be created for improved exposure, followed by unroofing of the sphenoid wing and optic canal, with skeletonization of the anterior clinoid as needed. The advantage in removing bone extensively and gaining access under the frontal and temporal lobes is the resultant shortening of the distance to the targeted lesion with minimization of brain retraction.

Different techniques have been described for the initial bone flap to provide anterior and lateral exposure, and these techniques include frontal or frontotemporal bone with the orbital roof, with or without a zygomatic osteotomy, and with the orbital roof removed as a separate bone flap or in continuity with the frontal or frontotemporal bone flap. The frontolateral exposures have been designated by several different names (i.e., cranial-orbital, orbitocranial, supraorbital, cranioorbital-zygomatic, and others); however, the purpose of all the flaps and the subtle differences between techniques is to provide increased exposure beneath the frontal and temporal lobes.

CRANIOORBITAL ZYGOMATIC APPROACH

The cranioorbital-zygomatic (COZ) approach was introduced and popularized at the authors' institution by Dr. Ossama Al-Mefty, and the authors continue to use the COZ approach and modifications derived exclusively for lesions involving the anterior and middle fossa. The COZ approach is a composite of at least four different approaches that can be tailored to meet the specific requirements of a given lesion. The approach is ideally suited for lesions in the sellar, suprasellar, parasellar, and retrosellar regions, and for lesions extending into the cavernous sinus. Access to the floor of the middle fossa is also provided and, with extradural dissection, the petrous canal and petrous apex can be identified. The posterior aspect of the cavernous sinus is accessible, and intradural exposure of the petrous bone is available as far back as the internal acoustic meatus. Intradurally, the third and fourth cranial nerves can be exposed extending from the cerebral peduncle and entering into the cavernous sinus; drilling through the petrous tip medial to the carotid artery and anterior to the internal auditory meatus (Kawase's triangle) can provide access to the upper pons (1).

The COZ approach, which represents a modification of the supraorbital approach revised by Jane et al. (2), has been outlined and detailed in several other reports (3-10). Specific details of the techniques used at the authors' institution follow.

Patient Position

The patient is placed supine with the head at the foot end of the table and with the table rotated 180 degrees away from the anesthesiologist: rotating the operating field away from the anesthetic equipment increases the degree of operative maneuverability. With the head at the foot end of the table, the surgeon has more comfortable leg and knee space while seated at the microscope. A lumbar drain is placed that is connected to a drainage collection bag. The authors usually drain off 10 to 15 ml of cerebrospinal fluid (CSF) just before dissection of the dura away from the inner table of the bone

A. P. Bowles, Jr.: Department of Neurosurgery, University of Mississippi Medical Center, Jackson, Mississippi 39216.

V. K. Anand: Department of Surgery, Division of Otolaryngology. University of Mississippi Medical Center, Jackson, Mississippi 39216.



FIG. 1. Illustration of the bicoronal skin incision with the ipsilateral incision placed in front of the trunk of the superficial temporal artery at the level of the zygoma. The bicoronal skin incision, which starts at the level of the zygoma and is carried contralaterally behind the hairline to the supratemporal line, preserves the trunk and posterior branch of the superficial temporal artery. The incision that starts at the level of the zygoma ipsilaterally is placed so that the frontal branches of the facial nerve are also preserved.

flap. An additional 15 to 20 ml of CSF may be drained after the dura is opened for greater brain relaxation. With the lumbar drain in place, furosemide (Lasix) or mannitol usually is not given. However, the Pco_2 is maintained from 27 to 28 mm Hg. The skin over the abdomen and leg ipsilaterally is prepared and draped for a potential harvest of free fat graft, fascia lata, saphenous vein, sural nerve, or free rectus abdominis, which may be needed for subsequent reconstruction. The table is adjusted so that the patient's trunk and head are elevated 20 degrees. Once immobilized with three-point pin fixation, the head is carefully hyperextended 5 to 10 degrees and rotated anywhere from 10 to 60 degrees contralaterally, depending on the targeted lesion. The head may only need to be rotated 0 to 10 degrees for access to the floor of the anterior fossa. The head should be rotated 20 to 30 degrees to maximize access to the optic chiasm and sellar regions. The head may be rotated even further for exposure to the cavernous sinus. With the head and neck extended and rotated, the supraorbital margin and pterional region are placed at the highest point, and after opening the dura and wide sylvian fissure dissection, the frontal and temporal poles open up under the weight of gravity, exposing the sylvian cistern.

Skin Incision and Pericrania! Flap

After the head and neck have been prepared and draped, a bicoronal skin incision is made, beginning 1 cm anterior to the tragus at the level of the zygomatic arch ipsilaterally, with the incision carried behind the hairline to just below the superior temporal line contralaterally (Fig. 1). The position of the ipsilateral incision is such that only the anterior branch of the superficial temporal artery is cut, with preservation of the trunk and posterior branches, which would be located behind the incision. The superficial temporal vessels are preserved in the event that an extracranial-intracranial mi-crovascular bypass is necessary. With the incision placed 1 cm anterior to the tragus, the trunk of the superficial temporal artery lies posterior to the incision, and the superior branches of the facial nerve are anterior to the incision. The incision is carried through the skin and galea but not the pericranium. The areolar tissue is dissected away from the galea remaining adherent to the pericranium for a thicker pericranial graft. The skin flap is reflected anteriorly along with the frontal branch of the facial nerve, which has been dissected subfascially (Fig. 2). Both superficial and deep layers of the temporalis fascia are incised approximately 1.5 cm distal and parallel to the zygomatic arch and lateral rim over the orbit. The frontal branch lies within the fat pad between the superficial and deep fascial layers. Both superficial and deep layers of the temporalis fascia are incised above the zygomatic arch and posterior to the lateral orbital rim. The frontal branch lies within the fat pad between the superficial and deep fascial layers. While transitioning from the superficial to the deep layers of the temporalis fascia, the frontal branch is at considerable risk anteriorly. Therefore, this zone transitioning occurs posterior to the midpoint between lateral orbital rim and preauricular crease, and all the superficial tissue is reflected anteriorly. Incisions are then made through the pericranium, with the pericranium dissected free from the occipital bone and reflected anteriorly over the scalp flap and preserved for later reconstruction (Fig. 3A). The intact base of the pericranial flap is dissected free from the roof and lateral orbit, and the deep fascial layer with the frontal branch of the facial nerve superior to this layer is dissected subperiosteally across the frontal and malar process and body of the zygoma (see Fig. 2). With a high-speed drill (C| attachment, Midas Rex), a cuff of bone is drilled around the supraorbital foramen, freeing the supraorbital nerve, which is reflected anteriorly (see Fig. 3B). The temporalis muscle fasciae are dissected away from the superior surface of the body of the zygoma, leaving the masseter attached to the inferior surface of the zygoma. Oblique osteotomies are then





FIG. 2. Intraoperative photomicrographs of the subfascial dissection along the lateral rim of the orbit and body of the zygoma. In (A), an incision through both the superficial and deep fasciae of the temporalis muscle is cut parallel to the lateral rim of the orbit and zygomatic arch and dissected subperiosteally across the lateral rim of the orbit **(B)** and the body of the zygoma (C). The upper branches of the facial nerve continue in the superficial and deep fasciae of the temporalis muscle within the fat pad between the two fascial layers; when these layers are dissected anteriorly and subperiosteally across the bone, the upper frontal branches are preserved. With the body of the zygoma exposed {C), oblique osteotomies can be placed because the upper zygoma can be retracted interiorly.



FIG. 3. A: Intraoperative photograph of the pedicle of pericranium that has been dissected subperiosteally away from the skull along each superior temporal line. B: To protect the supraorbital nerve, a cuff of bone is drilled around the supraorbital foramen, which is reflected anteriorly with the pericranial graft.



FIG. 4. Illustration of the cranioorbital-zygo-matic approach. The frontotemporal flap is outlined in continuity with the roof and lateral rim of the orbit, with oblique osteotomies along the body of the zygoma. Osteotomy through the roof of the orbit is demonstrated *(inset).* (Reproduced from ref. 9, with permission.)

placed at either end of the zygoma (see Fig. 2C), and with retraction of the zygoma, improved basal exposure of the middle fossa is provided. The temporalis muscle is then dissected from the calvarium, exposing the junction of the zygomatic, sphenoid, and frontal bone.

Bone Flap

A supraorbital-pterional bone flap is generated that consists of frontotemporal bone in continuity with the anterior, superior, and lateral rims of the orbit (Fig. 4). Four bur holes are made, with the first placed in the location of MacCarty's keyhole. The first bur hole is made in the temporal fossa, medial to the frontozygomatic suture (keyhole), and should expose the dura of the frontal fossa, and the anterior orbital area with the periorbita separated from the dura by the root of the orbit. The second bur hole is placed in the inferoposterior portion of the squamous temporal bone just above the roof of the zygoma. The third bur hole is then placed superior to the second bur hole along the superior temporal line. The last bur hole is made in the midline just above the nasion with perforation of the anterior and posterior walls of the frontal sinus. For cosmetic reasons, the authors usually attempt to make this hole as small as possible with a small drill bit. The second, third, and fourth bur holes are connected with a cran-iotome using the footplate, and then an osteotomy is made with a high-speed drill extending along the base of the temporal fossa to the sphenoid ridge, connecting bur holes one and two.

With a high-speed drill, an osteotomy is made through the lateral wall of the orbit just superior to the malar prominence and extended to the keyhole at the level of the inferior orbital fissure. An osteotomy is then extended from the fourth bur hole above the nasion through both walls of the frontal sinus, extending inferiorly and medially to the orbital roof. The oblique osteotomy from the fourth bur hole to the orbit is directed to the supraorbital foramen, lateral to the trochlear groove on the undersurface of the orbit. Finally, the anterior roof of the orbit is cut across with an osteotome, starting from the lateral margin of the roof at the keyhole and cutting transversely across the roof to the medial border of the orbit. The supraorbital temporal bone flap is then removed.

With removal of the frontal bone, the frontal sinus is exposed. The mucosa of the sinus is exenterated with a cutting bur and the posterior wall removed (cranialization) and then plugged with muscle, fat, or antibiotic-soaked Gelfoam. All instruments exposed to the frontal sinus are removed and resterilized, and surgical attire replaced. The remainder of the orbital roof is then removed as a posterior orbitotomy with a high-speed drill (Fig. 5). A medial cut is made in the



FIG. 5. After removal of the supraorbitopterional bone flap, the remaining portion of the roof and lateral orbital wall is removed as a posterior orbitotomy and reattached to the cranial flap at the end of the procedure. (Reproduced from ref. 9, with permission.)

I



FIG. 6. Intraoperative photograph (A) of the superior orbital fissure (arrow), which has been unroofed. The optic canal has been unroofed as well, exposing the optic nerve (ON). and the anterior clinoid *(AC)* has been drilled down to its base. Another operative photograph (B) shows the intradural removal of the remaining base of the anterior clinoid in relation to anatomic landmarks—the optic nerve *(ON),* the carotid artery *(CA),* and the cavernous sinus.

roof of the orbit and extended posteriorly. The second cut is made at the base of the lateral orbital wall along the inferior orbital fissure. The cuts are then connected across the sphenoid ridge above the superior orbital fissure. A posterior orbitotomy is then reattached to the bone flap (see also Fig. 13B) for orbital reconstruction.

Drilling of the Sphenoid Bone

To provide greater access to the cavernous sinus optic canals and interpeduncular cisterns, the authors usually completely remove the sphenoid ridge, which is drilled away with a high-speed air drill under the microscope (Fig. 6A). Drilling is continued with unroofing of the superior orbital fissure and skeletonization of the anterior clinoid. The anterior clinoid may be removed extradurally or intradurally, or both, with exposure of the subclinoid segment of the carotid artery below (see Fig. 6B). After the superior orbital fissure is opened, the optic canal can also be unroofed extradurally, with exposure of the optic nerve. To unroof the optic canal safely, the authors usually use a small diamond drill bit with continuous irrigation.

Exposure of the Intrapetrous Carotid Artery

When operating on lesions involving the cavernous sinus, proximal control of the internal carotid artery (ICA) can be achieved with exposure of the intrapetrous ICA. Exposure of the ICA within the intrapetrous canal may also provide the site for potential venous bypass grafting of the cavernous ICA. With the bone flap removed and the body of the zygoma retracted inferiorly, the anterior roof of the middle fossa can be visualized after the dura is dissected away from the bone. Within Glasscock's triangle, the petrous can be carefully drilled, exposing the ICA below (Fig. 7).

With microscopic magnification, the dura is elevated from the floor of the temporal fossa in a mediobasal direction. The middle meningeal artery should be identified and followed back to the foramen spinosum. The artery is coagulated and cut, and the foramen packed with bone wax. The temporal dura is then elevated further medially, with dissection limited anteriorly by the trigeminal ganglion and cranial nerve V3. The foramen ovale is then identified with cranial nerve V3 exiting through it. Just medial and posterior to the foramen spinosum. the greater and lesser superficial petrosal nerves should be identified exiting from the facial hiatus (Fig. 8), and these nerves are sharply cut to avoid traction on the greater superficial petrosal nerve to the geniculate ganglion, which could result in facial paralysis (see Fig. 8B). The dura is then elevated posteriorly and medially to expose the arcuate eminence of the petrous bone, and with the greater superficial petrosal nerve, the posterior aspect of the trigeminal ganglion and mandibular nerve, a line drawn between the foramen spinosum and arcuate eminence forms the border of the posterolateral (or Glasscock's) triangle (11). In this triangle and just medial and parallel to the greater superficial petrosal nerve, the bone of the petrous canal is unroofed with a diamond drill bit under constant irrigation. The horizontal portion of the petrous ICA is then exposed (see Fig. 6A). In a significant number of cases, the bone is absent, and the periosteum covering the ICA is exposed when the dura is elevated. Once the petrous canal is unroofed, a 60-cm. 2-Fr Fogarty arterial embolectomy catheter (Baxter Health Care Corporation, McGraw Park, IL) can be inserted (11). In general, 1.0 to 1.5 cm of bone is unroofed to expose the ICA properly. The catheter is inserted extraarterially between the outer wall of the vessel and the wall of the carotid



FIG. 7. Illustration of the intrapetrous internal carotid artery exposed in Glass-cock's triangle; the landmarks for Glass-cock's triangle are defined by the greater superficial petrosal nerve (PA/), the trigeminal ganglion and mandibular nerve *(V_3)*, and the foramen spinosum with the middle meningeal artery *(MM)*. The dura of the middle fossa is elevated from the floor, exposing Glasscock's triangle. The foramen spinosum is located and the middle meningeal artery cut and coagulated. The petrosal nerves are sharply incised and then the carotid artery unroofed *(inset)*.

canal, 5 to 10 mm proximal to the carotid canal (Fig. 9A). The distal end of the catheter is connected to a three-way stopcock and attached to a syringe with saline. The balloon can be inflated with 0.2 ml of saline and the stopcock closed to provide temporary occlusion of the ICA (see Fig. 9B).

Intradural Dissection

Before opening the dura, an additional 10 to 20 ml of CSF is drained through the lumbar catheter for further brain relaxation as needed. A curvilinear incision is then made extending from the basal frontal region across the sylvian fissure to the basal temporal region. A large piece of Surgicel is placed over the periorbita and then the dura is reflected anteriorly over the periorbita and tacked into place, with further retraction of the orbital contents. Using sharp dissection, the sylvian fissure is opened, and the frontal and temporal poles separated, The authors usually place a self-retaining retractor lightly on the temporal lobe and begin dissection on the frontal side of the sylvian vein. The dissection is then directed in a deeper orientation, allowing identification of a cortical arterial branch, which is then followed down to the middle cerebral artery. With the middle cerebral artery identified, dissection is continued anteriorly along the middle cerebral artery with the sylvian cistern opened from a deep to superficial orientation, and with dissection progressing anteriorly.

With the superior and lateral rims of the orbit removed, the sphenoid wing and superior orbital fissure unroofed, the transsylvian dissection can be extended far superiorly. With the head and neck in 10 to 15 degrees of extension and with the bony removal and wide superior sylvian fissure dissec-



FIG. 8. Intraoperative photograph of the greater superficial petrosal nerve *(arrow)* (A), and with a subsequent incision by knife *(K)* (B). At the base of the greater superficial petrosal nerve is the suction tip *(ST)* with the nerve along the petrosal base *(PB)*.



FIG. 9. A: After the landmarks for Glasscock's triangle have been visualized and the petrous canal identified, the bone over the carotid artery is unroofed and a Fogarty embolectomy catheter (C) is placed ex-traarterially within the canal. In Glasscock's triangle, the mandibular nerve *(V_3)* is seen in relation to the catheter. B: Enhanced operative photograph shows expansion of the extraarterial catheter balloon within the canal. The suction tip (ST) is also shown at the base.

tion, the frontal and temporal poles readily separate under the influence of gravity. The frontal lobe may be gently supported with a self-retaining retractor; however, the elevation requirements are minimal, with an added distance of 1.5 cm or less required for exposure. Multidirectional viewing (Fig. 10) is then provided with surgical dissection possible by multiple routes, including subfrontal, sublemporal, and transsylvian avenues, in front of the chiasm, behind the chiasm. and into the lamina terminales.

Entering the Cavernous Sinus

The COZ approach is well suited for lesions, especially tumors, involving the cavernous sinus, providing superior and lateral entry into the cavernous sinus. In cavernous sinus surgery, proximal distal control of the carotid artery is crucial for "safe surgery"; control of the carotid artery is achieved by exposing the horizontal segment of the petrous ICA through Glasscock's triangle, and the subclinoid segment of the ICA. After the posterior roof of the orbit is removed, a thin rim of bone remains over the optic canal and superior orbital fissure. A diamond drill bit is used to unroof completely the optic canal and superior orbital fissure extradurally. and then the anterior clinoid is drilled away to expose the subclinoid segment of the ICA. The anterior clinoid is initially skeletonized to allow the diamond drill extradurally to core out the middle and leave a thin shell. Drilling is continued on the inferior strut of the lesser wing beneath the



FIG. 10. Intraoperative photographs showing the multidirectional views that may be provided from the cranioorbital-zygomatic approach, with exposure of the optic nerves, chiasm, and infundibulum **(A),** and carotid artery and cavernous sinus **(B).**



FIG. 11. After the anterior clinoid has been completely removed, the subclinoid segment of the carotid artery is exposed. With incision of the falciform fold *(inset),* the optic nerve can be mobilized medially, further exposing the ophthalmic artery and carotid artery as it enters the cavernous sinus. The carotid artery can then be followed in the cavernous sinus through the superior route in a retrograde fashion.

optic nerve and disconnects the anterior clinoid, which then can be removed by subperiosteal dissection.

Marked by proximal and distal rings, the subclinoid section of the ICA is exposed extradurally. The anterior clinoid can be removed extradurally or intradurally. For surgery involving tumors, the authors usually remove the entire anterior clinoid extradurally; for aneurysms that extend underneath the clinoid, two thirds of the anterior clinoid is removed extradurally and the remainder is drilled away intradurally.

Entry into the cavernous sinus depends on the lesion and its origin; however, in most cases, the authors enter the cavernous sinus through a superior or lateral entry, or both. With the subclinoid segment of the ICA exposed and the optic canal unroofed, the dural sheath of the optic nerve is then incised, starting at the falciform fold and extending along the length of the nerve (Fig. 11). The distal ring anchoring the ICA subdurally is untethered and, with both the optic nerve and carotid artery mobilized, excellent entry into the cavernous sinus through the superior wall is provided (see Fig. 11). Medial mobilization of the optic nerve also allows identification of the origin and course of the ophthalmic artery.

With the lateral entry, after the optic nerve and carotid artery have been mobilized by incising the dura propria, the lateral wall of the oculomotor foramen of the third cranial nerve is unroofed with a sickle knife, and the outer layer of the lateral wall of the cavernous sinus is pulled away laterally from the first and second divisions of the fifth cranial nerve, exposing Parkinson's triangle (Fig. 12A). Alternatively, with the free edge of the tentorium visualized and the course of the third and fourth cranial nerves identified entering the cavernous sinus, an incision can be made through the lateral wall of the cavernous sinus beneath the projected course of the fourth cranial nerve (see Fig. 12B). The incision extends about 7 mm anteriorly and posteriorly and, similarly, the outer layer of the lateral wall is peeled away from the first and second divisions of the fifth cranial nerve, which then provides good access to the cavernous sinus through Mullan's triangle (between cranial nerves VI and V2) and Parkinson's triangle (between nerves IV and VI). A natural gap exists between the first division of the trigeminal nerve and the fourth cranial nerve, and deep in Parkinson's triangle, the cavernous segment of the ICA can be identified with the sixth cranial nerve on the lateral wall of the ICA. The gap is usually enlarged to expose the ICA and the sixth cranial nerve; however, sometimes the ICA is located between Mullan's triangle or the gap between the first and second divisions of the trigeminal nerve.

The lateral exposure can also be increased by further peeling back the outer layer of the lateral wall. Drilling of the posterior clinoid provides an avenue to the cavernous sinus lateral to the carotid artery and third cranial nerve, and drilling of the petrous tip anterior to the internal auditory canal (Kawase's triangle) exposes the posterior aspect of the cavernous sinus and the posterior fossa.

Reconstruction and Closure

If the frontal ethmoid or sphenoid sinuses are opened during the approach or removed because of involvement with disease, communication between the paranasal sinuses and intradural space is prevented with the reconstruction using a free fat graft and fascia lata. Sinus mucosa is exenterated and packed with fat and fibrin glue. A fascial graft is then laid intradurally and secured with sutures to the basal dura, and the graft is spread to cover the frontal and temporal fossa and sutured to the frontal and temporal dura. The preserved pericranial flap in the frontal region is then turned over the frontal sinus, periorbita, and extended over any defect in the floor of the anterior fossa. The authors have also reconstructed large defects in the anterior fossa with a split-thickness bone graft sandwiched between the pericranium and galea that was dissected away from skin. Defects in the floor of the middle fossa to the infratemporal and sphenopalatine fossae are reconstructed by enveloping the defects along the floor with a pedicle of the temporalis muscle. Similarly, a pedicle graft of temporalis muscle may be sutured to close a defect through Kawase's triangle.

Several calvarial and central dural tack-ups are placed after the dura has been closed in a watertight fashion. Basal temporal dural tack-ups are also secured to the undersurface of the temporalis muscle. The bone flap with posterior orbitotomy attached is reattached to the cranial vault with plates and screws, and the temporalis muscle (if not used for re-



FIG. 12. The cavernous sinus can be entered laterally through Parkinson's triangle by mobilizing the dura and unroofing the third cranial nerve, with the outer layer of the lateral wall of the cavernous sinus peeled laterally to provide full exposure of cranial nerves III and IV and the first and second divisions of cranial nerve V (A). Alternatively, an incision can be made through the lateral wall of the cavernous sinus beneath the projected course of cranial nerve IV, with the dura peeled away over Parkinson's triangle between cranial nerves III and IV superiorly and the first division of the trigeminal nerve interiorly **(B).**

construction of the floor of the middle fossa) is returned to its anatomic position and secured at the bone along the superior temporal line. The zygomatic arch is then repositioned and secured with miniplates and screws, and galea and skin are closed.

CRANIOORBITAL APPROACHES FOR TUMORS

The cranioorbital approaches have been successfully used for several different tumors involving anterior and middle cranial fossae. Most tumors in this location are benign (i.e., meningiomas, neurilemomas) or malignant but locally confined (i.e., chordomas, esthesioneuroblastomas); however, carcinomas and metastatic lesions are also encountered. Frontolateral approaches incorporate the orbital roof and provide greater access to tumors underneath the frontal and temporal lobes. With modifications of the cranioorbital bone flap (i.e., changing the position and size of the flap), incorporation of the posterior orbitotomy or zygomatic osteotomy, and variations in the degree of sphenoid unroofing, the cranioorbital approaches can be specifically tailored to optimize the exposure of a given tumor.

The technical aspects of the COZ approach incorporate most of the techniques required for all cranioorbital approaches and, by including all or part of the steps required with or without modifications, the COZ approach can define a tailored approach specific for a tumor and can be dictated by location and disease. Several of the modifications derived from the COZ theme are grouped accordingly for tumor type and location, and are described in the following sections.

Supraorbital Approach

The supraorbital approach is well suited for small to moderately sized tumors involving the sellar and suprasellar regions and the lamina terminales. Typical tumors encountered that could be suitably exposed include tuberculum sellae meningiomas, craniopharyngiomas, and pituitary and hypothalamic tumors. Exposure is also provided for large orbital neoplasms, tumors of the orbital apex, and optic canal lesions.

With the supraorbital approach (Fig. 13), the authors typically create two separate bone flaps:

1. A cranioorbital flap that includes the superior and lateral orbital rim
2. A smaller, more posterior flap that includes the remainder of the roof and lateral wall of the orbit (posterior orbitotomy)

The technical aspects of the supraorbital approach used at the authors' institution are similar to the techniques described for the COZ, except that the bone flap is smaller and fewer steps are required.

For tumors involving the sellar and suprasellar regions and the planum sphenoidale, the patient is placed supine, brow up, with the head extended to allow the frontal lobes to fall backward. The incision, harvest of the pericranial pedicle flap, and subfascial dissection are as described for the COZ. However, only the lateral rim of the orbit is exposed to the level of the malar process of the zygoma, and the cranioorbital bone developed is smaller, omitting the incorpora-



FIG. 13. Illustration of the supraorbital bone flap (A), and with posterior orbitotomy reattached (B).

tion of temporal bone. Two bur holes are made: the first is made at the site of MacCarty's keyhole, and the second is made in the frontal bone above the nasion. With the craniotome, the cranial holes are interconnected through the frontal bone about 4 cm above the supraorbital rim with osteotomies made through the anterosuperior aspect of the roof and lateral rim of the orbits. Entry into the frontal sinus is managed as described previously. The osteotomy through the outer rim of the orbit is made at the base, just above the malar process of the zygoma (see description of COZ approach). The posterior orbitotomy, described in the COZ approach, facilitates an even lower basal approach. The superior orbital fissure can be unroofed and the anterior clinoid skeletonized and removed, if needed. Because of midline exposure, both optic nerves are easily seen, and the optic canals can be unroofed extradurally with optic nerve decompression.

In the original description of the supraorbital approach by Jane et al. (2), only a single bone flap comprising the superior and lateral orbital rim is removed. Additional removal of the posterior of the orbit, as discussed previously, has been termed the "superolateral cranioorbital approach" by Al-Mefty and colleagues (8,12). The cranioorbital flap, which includes the superior and lateral orbital rims, provides low basal exposure with minimal frontal lobe retraction. With removal of the posterior aspect of the orbital roof, basal exposure is increased, especially to the planum sphenoidale, tuberculum sellae, and optic canal. Removal of the orbital roof is required for exposure to the orbit with the supraorbital approach, anatomic landmarks are better oriented with the brow up (i.e., visualization of the optic chiasm and lamina terminales), and whether the entire roof of the orbit should be removed is determined based on the tumor at hand.

As an example, the authors have used the supraorbital approach with posterior orbitotomy for a patient with a tuberculum sellae meningioma (Fig. 14). The patient presented with headaches and declining vision. Low basal exposure was achieved so that the tumor could be easily devascularized at the base across the ethmoid plate, planum sphenoidale, and tuberculum sellae, and then removed. Both optic canals were carefully unroofed with a diamond drill bit under constant irrigation. The tumor was completely removed without leaving any residual lesion (see Fig. 14C).

Bifrontal Cranioorbital Approach

For large and giant tumors involving the anterior fossa, the supraorbital approach can be incorporated into a bifrontal flap with or without a unilateral posterior orbitotomy. Tumors extending across the floor of the anterior fossa, such as olfactory groove meningiomas, are more easily exposed by bifrontal flap. Malignant tumors that extend into the anterior fossa from the face or into the orbit can also be exposed with a bifrontal flap with craniofacial resection.

With the bifrontal cranioorbital approach, the supraorbital bone is incorporated as a bifrontal flap (Fig. 15). Five bur holes are made, the first at the location of MacCarty's keyhole, and the second through the frontal bone just above the orbital ridge. Bur holes are made through bone adjacent to the location of the superior sagittal sinus from 5 to 8 cm above the nasion. The last bur hole is placed just above the nasion. The authors use a Midas Rex drill with an *M$* attachment for the bur holes; however, for cosmetic reasons, smaller holes are made into the frontal sinus just above the nasion and in the frontal bone just above the orbital ridge. An osteotomy is made across the lateral rim of the orbit and extending into the keyhole. Although the bur holes are interconnected with a craniotome, the authors usually drill directly over the sinus, connecting adjacent bur holes with a BI attachment of the Midas Rex drill without the foot plate. As described previously, an osteotomy is made across the ante-



FIG. 14. Intraoperative photographs of a tuberculum sellae meningioma exposed through a supraorbital approach. A: The tumor is being devascularized along the base of the anterior fossa (B); with coagulation of the ethmoid branches. The tumor border is artistically enhanced. The bipolar tips are also outlined. B: The tumor has been completely removed along the anterior base and planum sphenoidale *(PS)* and the optic canal (OC). The optic canal was carefully drilled, exposing the dura overlying the optic nerve *(ON).* In this photograph, the dura over the optic nerve is being incised. The suction tip (S7) is also shown. C: The tumor has been completely removed, with identification of the optic nerve (CW) and in-fundibulum, which has been artistically enhanced *(outlined).*

rior superior roof of the orbit from the keyhole to the bur hole above the nasion, and the bifrontal supraorbital bone flap is removed. The frontal svmis encountered is cvamaU7.ed as described earlier.

A *bifrontal* supraorbitaJ approach *was used for a* patient *with a large olfactory groove meningioma (Fig. I6A). The orbital* rim was removed on the right connected lo the I Wrontal flap. With the patient's brow up and head extended, a sufficiently low basal exposure was achieved without posterior orbitotomy. After the frontal sinus was cranialized, in-| tisions were made along either side of the sagittal sinus, with **die** sagittal sinus coagulated and cut. The incision through the sinus was continued through the attachment of the falx to ::ie base of the skull base and crista galli. With a low basal exposure to the anterior sagittal sinus, the sagittal sinus was coagulated without suture ligation, and the tumor was exposed without frontal lobe resection. The tumor was devascularized at the base with coagulation of the ethmoid branches through the cribriform plate. The Lumor was internally decompressed, followed by dissection and removal of the capsule and dural attachments. The optic canals were carefully decompressed with removal of minor. The planum



FIG. 15. Illustration of a bifrontal supraorbital bone flap, which can be used for large and giant tumors involving the anterior fossa.



FIG. 16. Contrast-enhanced magnetic resonance images (MRI) of a patient with a large olfactory groove meningioma. A: The tumor extends along before the anterior fossa, with compression and displacement of the anterior cerebral arteries distally, accompanied by erosion of the planum sphenoidale. B: Post-, surgical contrast-enhanced MRI shows that the tumor has been excised.

sphenoidale was involved with tumor. The bone of the pianum sphenoidale involved with tumor was drilled away into the sphenoid sinus. Tumor and mueosa were removed and the detect packed with i'ai.. A piece of fascia lata graft was sutured over the defect and supplemented with fibrin giue; a larger fascia! graft was placed inrradurally and secured to ihc basal dura and then spread over to cover the frontal fossa and secured LO the frontal dura. The vaseulari?.ed pedicle of the pericranium was then Lunied over the frontal sinus and periorhira and extended along the floor of the anterior fossa, reinforcing the reconstruction. Excision of the tumor was confirmed liy intraoperative and radio-graphic inspection (see Fig. I6RJ.

In another case, a hi frontal cranioorbitid approach was used for a cranit)facial resection of a malignant, tumor (Fig. I7A,B). With opening of the frontal sinus, tumor was encountered and removed by debulking through the, frontal sinus and ink) the face. Because the rumor extended intradu-ralty, the dura was opened and tumor removed; additional tumor was followed through the ethmoid and sphenoid sinuses and debulked in these locations as well, Because of the extension of the tumor to the medial aspect of the periorbita, the posterior roof of the orbit was removed ipsilaterally for increased exposure. The remainder of the tumor was removed from below by a transfadal approach. Because of the large defect remaining in the anterior fossa, a sandwich of pericranium with split-thickness bone graft in the middle and the galea dissected away from the skin was placed to cover the defect. Tumor removal was verified radiograpliically (see Fig. I7CJ.

Cranioorbital Zygnmalic Approach

The. COZ approach is suitable for large tumors in the jux tasellar region (i.e., suprasellar, parasellar, and rctroscllar areas) and for lesions extending into the orbit and the cavernous sinus. For moderately sized tumors of the juxtasellar region, a cranioorbital approach without zygomatic osteotomy suffices; but as the tumors become larger, especially those that extend into the cavernous sinus {Figs. 18-22), a more extensive flap with frontotemporal bone, complete with unroofing of the superior orbital fissure and skele-toni/alion of the anterior elinoid with zygomatic osteotomies, is required for exposure. The anterior basal exposure is increased with the posterior orbitolomy. which facilitates unroofing of the superior orbital fissure, Unroof ing the superior orbital fissure facilitates skeleton!/aticm of the anterior elinoid and optic canal and also allows transsyj-vian dissection to extend far more superiorly. Skeleton!/a-lion of the anterior elinoid uncovers the subelinoid segment of the ICA, providing safe distal control of the ICA and the cavernous sinus, and also allows an avenue of entry into the cavernous sinus. Removal of the anterior elinoid also further exposes tumors that may extend underneath the anterior elinoid and onto the subelinoid segment of the carotid artery. Several of the skull base tumors that are juxtasellar in location may extend into the cavernous sinus (e.g., meningiomas, invading pituitary adenomas) and not only is exposure of the juxtasellar region required, but a more basal exposure along the floor of the middle fossa is necessary to provide an cas ier avenue of entry into the cavernous sinus. With oblique


T120
B

FIG. 17. Contrast-enhanced magnetic resonance images (MRl) of a patient with an extensive craniofacial squatnous cell carcinoma. A: The tumor extends throughout the nasopharyngeal region, with extension into the sphenoid sinus through the ethmoid ridge and well into the frontal sinuses. B: Contrast-enhanced coronal MRl shows the tumor extending medially into the or-hit. C: Using a craniofacial approach, the tumor was removed without residual disease.

продолжение

ие



FIG. 18. Intraoperative photograph of a patient whose cavernous sinus *(CS)* was filled with a chordoma. The tumor expanded the cavernous sinus, spilling out medially from the tentorial edge *(highlighted),* distorting and displacing the third cranial nerve *(outlined).*



FIG. 19. Intraoperative photograph of a patient with an invading pituitary adenoma. The cavernous sinus (CS) is filled with the tumor (7), which extends from the sella between the optic nerves and optic chiasm (OC). For reference, the supra-clinoid segment of the carotid artery *(CA)* is also shown.



FIG. 20. Contrast-enhanced magnetic resonance images (MRI) of a patient with an anterior clinoid meningioma with extension into the cavernous sinus. A: Axial MRI shows extensive involvement of the tumor in the cavernous sinus. B: Coronal MRI shows the tumor to wrap around the carotid artery in the cavernous sinus and continue underneath the anterior clinoid, wrapping around the supraclinoid portion of the carotid artery. Tumor also extends into the optic canal and the sella.



FIG. 21. Contrast-enhanced magnetic resonance images (MRI) of a patient with a recurrent sphenoid wing meningioma. A: Enhancing tumor has completely replaced the sphenoid wing, with extension through the temporal squamous bone (axial MRI). The tumor extends into the cavernous sinus and has invaded and replaced the temporalis muscle. B: Coronal MRI shows extensive involvement of the tumor, with extracranial extension replacing the temporalis muscle and engulfing the periorbita.



FIG. 22. The cranioorbital-zygomatic approach was used to expose a trigeminal neuroma within the cavernous sinus. A: Enhanced intraoperative micrograph shows the lateral wall *(LW)* being peeled back to expose the tumor (7) within the cavernous sinus. B: After the tumor has been removed, the area is replaced with fat *(F)* and the lateral wall *(LW)* resutured in place.

osteotomies placed at either end of the zygoma and with the body of the zygoma, which remains attached to the masseter, retracted inferiorly, basal exposure along the floor of the middle fossa is increased. After the sylvian fissure is widely dissected and opened far superiorly, the temporal lobe is retracted laterally and posteriorly, exposing the incisural edge of the tentorium and lateral wall of the cavernous sinus, which is centered along the third cranial nerve, essentially combining both "transsylvian" and "subtemporal" routes to the cavernous sinus. Tumors extending along the floor of the cavernous sinus also require greater basal exposure, which is achieved with zygomatic osteotomy and access to the floor of the middle fossa, thus requiring exposure of the petrous canal for proximal control of the ICA.

The COZ approach was used for an anterior clinoid meningioma with extension into the optic canal and cavernous sinus (see Fig. 20). The patient presented with progressive headaches and declining function of the ipsilateral optic nerve. The periorbital fissure was unroofed and the anterior clinoid and optic canal unroofed extradurally. A dissection plane was developed between the tumor and the supraclinoid segment of the carotid artery and was extended to the subclinoid segment of the carotid artery. The tumor was followed along the ICA and into the superior entry of the cavernous sinus. The remaining tumor of the cavernous sinus was removed by entering the cavernous sinus laterally through Parkinson's triangle. Although the tumor encased the carotid artery, it could be dissected from the ICA because of the remaining and intact arachnoid plane of the ICA.

The COZ approach was used in another patient with a recurrent sphenoid wing meningioma with erosion through the squamous portion of the temporal bone and infiltration of the temporalis muscle (see Fig. 21). The tumor replaced a portion of the lateral rim of the orbit and extended into the peri-orbita, as well as into the optic canal. The tumor involving the temporalis muscle was removed, and the tumor extending through the squamous bony defect was dissected away from the bone. The bone flap was removed, the superior orbital fissure with tumor was removed, and the optic canal with tumor unroofed. After sylvian fissure dissection, the tumor was removed in a piecemeal fashion to the lateral wall of the cavernous sinus, and then additional tumor was removed in the cavernous sinus through Parkinson's triangle. Bony defects were reconstructed with titanium plates and screws.

In another patient, the COZ approach was used for a cavernous sinus trigeminal neuroma. Proximal control of the carotid artery was gained with placement of a no. 2 Fogarty embolectomy catheter into the petrous canal and, after transsylvian dissection, the lateral wall of the cavernous sinus was peeled laterally, exposing the tumor (see Fig. 22A). Tumor was removed and dissected off the carotid artery and cranial nerve VI with an intact arachnoid plane. After the tumor was removed, free fat graft was placed into the cavity and the lateral wall sutured over the fat (see Fig. 22B).

CRANIOORBITAL APPROACHES FOR ANEURYSMS

The cranioorbital approaches have been successfully used to provide access to different skull base tumors; however, the cranioorbital approaches are also suitable for a number of different aneurysms. Debate about the timing of aneurysm surgery continues, and there are a number of factors favoring both delayed surgery (after day 10 of subarachnoid hemorrhage) and early surgery (within 48 to 96 hours of subarachnoid hemorrhage). The risk of rerupture is obvious with the delayed surgery; however, brain edema and swelling often occur acutely with subarachnoid hemorrhage and may require more forceful dissection and brain manipulation. Dissection becomes more difficult, and, at times, anatomic detail is obscured. However, with the increased exposure underneath the frontal and temporal lobes, the cranioorbital approaches provide greater exposure to the basal cisterns, so that brain retraction and manipulation are decreased and visualization of anatomic detail is improved.

The authors operate acutely on patients with ruptured aneurysms and relatively good clinical grades (Hunt and Hess, grade III or better), and use at least two cranioorbital approaches whenever appropriate. The cranioorbital approaches could probably be used to expose any aneurysm in the anterior and posterior circulation in which a pterional approach would be used. However, the cranioorbital approaches are especially well suited for aneurysms along the ICA, aneurysms that may be obscured by the anterior clinoid or optic nerve, those that may extend into the cavernous sinus, and those involving the posterior cerebral artery, superior cerebellar artery, and basilar tip. *

Another cranioorbital approach, also known as the orbitocranial approach (5,8), is used to expose carotid ophthalmic artery aneurysms. A similar supraorbital-pterional bone flap is needed; however, the flap is smaller and usually does not incorporate the frontal sinus (Fig. 23).

In this cranioorbital approach, a lumbar drain is placed, and the patient's head is immobilized with three-point pin fixation, rotated 30 degrees to the opposite side, and dropped to the floor approximately 10 to 15 degrees. With a smaller cranioorbital flap, three bur holes are placed; however, the more midline frontal bur hole is placed above and lateral to the nasion, lateral to the supraorbital nerve and lateral to the edge of the frontal sinus (if the frontal sinus is not large). A similar osteotomy is made across the lateral orbital rim and, with the osteotomy extending across the roof of the orbit and the craniotome used to interconnect the bur holes, a smaller supraorbital pterional bone flap is removed that includes less frontal and temporal bone than the standard COZ approach.

The authors use a bicoronal skin incision, although Al-Mefty and Smith describe the use of an eyebrow incision for this approach (8). To obtain increased basal exposure, the posterior roof of the orbit is removed, with the osteotomy placed just above the superior orbital fissure. With a high-



FIG. 23. Illustration of the bone flap for the cranioorbital approach used to provide exposure for carotid artery ophthalmic segment aneurysms and anterior communicating artery aneurysms. Compared with the cranioorbital-zygo-matic approach, the bone flap is smaller and usually does not incorporate the frontal sinus, and the zygomatic osteotomy is not needed.

speed drill, the sphenoid wing is drilled to the base or" the anterior clinoid to unroof the superior orbital fissure. About one half to one third of the anterior clinoid is skeletonized or removed extradurally, and the remainder removed intradurally. The optic canal is unroofed extradurally with a high-speed drill so that it can be more easily mobilized intradurally.

A frontotemporal semicircular incision is made in the dura and extended into the temporal fossa, and then the sylvian fissure is widely split 1.5 to 2 cm from the base of the anterior clinoid and the incision extended superiorly. The middle cerebral artery is identified disially and followed proximally to the supraclinoid segment of the ICA. The 1C A is dissected to the base of the anterior clinoid, allowing visualization of the anterior choroid and posterior communicating arteries. Proximal control of the ICA is obtained before intradural opening; either an occlusion balloon catheter is placed in the ICA intraoperatively before opening the dura, or a Fogarty embolectomy catheter is placed extraarterially in the petrous canal. If the petrous segment of the carotid artery is to be exposed, then a zygomatic osteotomy is made with the zygoma retracted to improve access to the floor of the middle fossa.

An incision is made across the dura overlying the residual anterior clinoid and the dura is separated from the bone, exposing the roof of the optic canal to the tuberculum sellae. With a diamond drill bit, the remainder of the anterior clinoid, optic canal, and lesser wing are removed. When drilling the anterior clinoid over the aneurysm, the underlying dura is preserved, thereby protecting the aneurysm. The falciform fold of dura is incised and extended along the optic nerve, which is mobilized out of the optic canal medially (usually off of the dome of the aneurysm), allowing visualization of the ophthalmic artery and subclinoid segment of the ICA emerging from the cavernous sinus.



FIG. 24. Patient presenting with declining vision on the right with a carotid ophthalmic artery aneurysm shown on a T2-weighted axial magnetic resonance image (A). Intraoperative photograph (B) defines the aneurysm *(A)* extending underneath the optic nerve *(ON).* Reference landmarks show the supraclinoid portion of the carotid artery *(CA)* and the third cranial nerve *(III)* entering beneath the lateral wall of the cavernous sinus, which was removed intradurally.

In a patient presenting with declining vision, a cranioorbital approach was used to expose a carotid-ophthalmic artery aneurysm (Fig. 24). After intradural dissection, the aneurysm was visualized extending well under the optic nerve and remaining anterior clinoid (see Fig. 24B). The remainder of the anterior clinoid was removed intradurally, and the aneurysm was clipped after the optic nerve was mobilized medially, exposing the ophthalmic artery and dome of the aneurysm.

In another case, at surgery, a giant paraclinoid aneurysm was found concealing the carotid artery and optic nerve (Fig. 25). After removal of the remaining anterior clinoid intradurally. arterial flow through the aneurysm was temporarily occluded while the patient was maintained on burst suppression with barbiturates for a total of 15 minutes (i.e., three 5-minute intervals). With temporary occlusion, the aneurysm became softer and easier to dissect and more maneuver able, so that it could be clipped. Distal control from temporary



FIG. 25. Angiogram and intraoperative photographs documenting a giant paraclinoid aneurysm. Preclipping an-giograms show the aneurysm on lateral (A) and anteroposterior (B) views. The aneurysm neck was successfully clipped, as shown in the postciipping lateral angiogram, which demonstrates obliteration of the aneurysm with excellent flow through parent arteries **(C).** At surgery (D), the aneurysm was found to conceal the carotid artery *(CA)* and optic nerve. The frontal lobe *(F)* and temporal lobe (7) are also labeled for reference.



FIG. 26, Intraoperative photograph of a superior hypophy-seal aneurysm exposed through a cranioorbital approach. The anterior clinoid was removed both extradurally and in-tradurally. A fenestrated clip was placed underneath the carotid artery *(CA)* to obliterate the aneurysm *(A).*

occlusion was achieved by placing a temporary clip on the carotid artery proximal to the posterior communicating artery. In this case, proximal control was obtained by placing the no. 2 Fogarty embolectomy catheter extraarterially into the petrous canal: the balloon was inflated with saline to a volume of 0.2 ml. Figure 26 shows a superior hypophyseal aneurysm exposed after the anterior clinoid was removed extradurally. A fenestrated clip was applied and the aneurysm clipped.

The cranioorbital approaches can also be used to expose anterior cerebral (Fig. 27} and anterior communicating arteries. After sylvian dissection has been extended superiorly, the Al segment at the origin of the 1C A is isolated and dissected medially to expose the anterior communicating artery, the contralateral Al segment, and both A2 segments. With the head turned contralaterally 30 degrees and dropped to the floor 10 to 15 degrees, and with the anterior and lateral rim of the orbit removed, the frontal lobe falls away from the orbital roof with gravity, further exposing the basal region with minimal retraction. Sliding along the orbital roof by the chi-asm, the interhemispheric fissure can be opened, and with the removal of the posterior roof of the orbit, basal exposure is increased. In several cases, anterior communicating artery aneurysms have been visualized without rectus gyms incision. The orbitocranial approach can be used to expose proximal anterior cerebral artery aneurysms, anterior communi-



FIG. 27. The cranioorbital approach was also used to expose an anterior cerebral artery aneurysm in a patient who presented with a subarachnoid hemorrhage and intracerebral hematoma, as shown on computed tomography scan (A). The angiogram showed an anterior communicating artery aneurysm that projected posteriorly (B); however, at surgery the aneurysm *(A)* was found to extend along the lateral

(figure continues)



FIG. 27. *Continued*, posterior wall of the anterior cerebral artery between segments A! and A_2(C). The aneurysm was successfully clipped and obliterated with good filling of parent arteries, as shown in the postclipping angiogram (D).

eating aneurysms, and distal aneurysms along the first 2 cm of the A2 segment.

The use of the COZ approach for posterior circulation aneurysms is well described by Bowles et al. (9). With this approach, both the transsylvian and subtemporal routes are provided, with wide exposure to the interpeduncular cisterns and multiple viewing angles. Exposure is also provided along the carotid artery, posterior communicating artery, posterior cerebral artery, superior cerebellar arteries, and basilar tip; however, the working space around the posterior communicating artery, posterior cerebral artery, and third cranial nerve can be increased by skeletonising the posterior clinoid. Maneuverability and dissection to the basilar tip can also be improved by untethering the third cranial nerve in the oculomotor foramen and by working underneath the third cranial nerve to expose the back wall of the basilar tip aneurysm, or working anterior to the third nerve to expose the ipsilateral PI segment and trunk of the basilar artery.

A COZ approach was used to expose a giant, partially thrombosed posterior cerebral aneurysm (Fig. 28). The anterior clinoid was removed extradurally. and the dura forming the roof of the oculomotor foramen in the lateral wall of the cavernous sinus was incised, untethering the third cranial nerve. The posterior clinoid was also carefully skeletonized and removed to increase the working space to the aneurysm (see Fig. 28C) for subsequent clipping.

The COZ approach was also used to expose a ruptured basilar tip artery aneurysm that projected superiorly and anteriorly. The third cranial nerve was untethered and the hack wall of the aneurysm was dissected, with perforators identified. The neck of the aneurysm was isolated, the ipsilateral and contralatera! PI segments identified (Fig. 29A), and the basilar trunk visualized (see Fig. 29B), resulting in subsequent aneurysm clipping.

CRANIOOR13ITAL APPROACHES FOR TRAUMA

The cranioorbital approaches can be used to repair traumatic lesions to the skull base that would require decompression or reconstruction. The report by Anand et al. (]3) describes the usefulness of the supraorbital approach for optic nerve decompression. With this approach, direct visualization of the optic canal and nerve is provided, allowing medial and lateral unroofing of the canal and wide decompression of the optic nerve. Again, use of the supraorbital approach with removal of the orbital roof provides low basal exposure, minimizing the disadvantage of brain retraction in a cranial procedure for optic nerve decompression.

The supraorbital approach exposes the orbital roof and optic canal. As an example, the supraorbital approach was used to repair a traumatic encephalocele through the orbital roof. In this case, a patient was involved in a motor vehicle accident and received multiple facial fractures, including an orbital roof fracture that entailed dural laceration and the subsequent development of a traumatic encephalocele (Fig. 30). After the supraorbital bone flap was removed, 20 ml of CSF



FIG. 28. Angiograms and intraoperative view of patient with a giant posterior cerebral artery aneurysm. Angiograms show an-teroposterior (A) and lateral **(B)** views. {Reproduced from ref. 9, with permission.) Intraoperative photograph **(C)** shows the giant posterior cerebral artery aneurysm along the posterior cerebral artery between P1 and P2. Reference landmarks include the carotid artery *(CA)*, posterior clinoid (PC), the third cranial nerve *(III)*, and posterior cerebral artery *(P_2)*.

was drained from the lumbar drain. With gentle extradural elevation of the frontal lobe, the roof of the orbit was visualized. The bony defect through the roof could be seen in the area of the dural laceration, and the .enc.qDhaloc.ele was identified. The traumatized area was debrided and then a fashioned piece of fascia lata graft was secured and placed to repair the dural defect. The vascularized pedicle of the pericrania! flap was then placed underneath the frontal lobe extradurally, and the bone flap was replaced and secured with plates and screws.

With the provision of a low basal exposure and vascularized pericranial graft reconstruction, fractures involving the anterior fossa, ethmoid plate, and frontal sinuses (with and without CSF fistula) are also reconstructed and repaired using cranioorbital approaches. Figure 31 shows a bifronlal cranioorbital craniotomy that was performed to repair a frontal sinus fracture involving the posterior wall and extending into the orbital roof. The patient also had a CSF fistula .through the bony defect. The frontal sinus was cranial-ized and packed with antibiotic-soaked Gelfoam. As the dura was dissected away from the bone, multiple fractures through the floor of the anterior fossa were visualized. The dura was also torn and lacerated in multiple areas. The dura was incised basally along either side of the sagittal sinus, which was coagulated and disconnected from bone. The bone fragments along the floor were debrided and then a dural graft (fascia lata) was placed over the defects and secured to the basal dura. A pedicle graft of pericranium was then placed on top of the dural graft along the floor of the anterior fossa. Figure 32 shows a bifrental cranioorbital approach



FIG. 29. Intraoperative photographs of a patient with a superiorly and anteriorly oriented basilar tip artery aneurysm exposed through a cranioorbital-zygomatic approach. Reference landmarks include the third cranial nerve *(III)*, the carotid artery *(CA)*, and suction tip (S7). A: The posterior communicating artery (PCo) is exposed, as well as the dome of the aneurysm *(A)* and the basilar artery *(BA)*. B: The dome of the aneurysm and the contralateral and ipsilateral posterior cerebral arteries are exposed (P_T).



FIG. 30. Coronal computed tomography scan of a patient with a traumatic encephalocele. Fracture through the orbital roof is seen with herniation of intracranial contents. The traumatic encephalocele was reconstructed and repaired using a supraorbital approach.



FIG. 31. Axial computed tomography scans (bone window) of a patient with a frontal sinus fracture with extension into the roof of the orbit. A: Fractures extend through both the anterior and posterior walls of the frontal sinus. B: Fractures extend into the roof of the orbit.



FIG. 32. A bifrontal cranioorbital approach was used to repair a traumatic cerebrospinal fluid (CSF) fistula in a patient with fractures through the anterior fossa. She presented with lethargy and CSF rhinorrhea. Unenhanced computed tomography scan shows bifrontal pneumocephalus.

that also was used to repair a traumatic CSF fistula through the anterior fossa. Computed tomography revealed the presence of significant pneumocephalus. The frontal sinus was cranialized and defects through the ethmoid plate were covered and secured with fascia lata, incorporating pericranial flap reinforcement underneath the frontal lobe extradurally.

CONCLUSIONS

The cranioorbital approaches that incorporate removal of part of the orbital bone can be used to provide a variety of exposures to lesions involving the anterior and middle fossae. The advantage of removing orbital bone is the provision of lower basal exposure, accompanied by greater access under the frontal and temporal lobes. The results are shortening of the distance to the targeted lesions and minimization of brain retraction. The cranioorbital approaches can be adjusted and tailored to specific lesions and provide greater access to the anterior or temporal fossa, or both, and, in general, opening of the sphenoid bone improves the exposure to the juxtasel-lar and cavernous sinus lesions. Most cranioorbital approaches have been successfully used to expose tumors of the skull base. However, the approaches are equally suited for a number of traumatic lesions and aneurysms requiring frontotemporal exposure.

REFERENCES

1. Kawase T, Shiobara R, Toya S. Anterior transpetrosal-transtentorial approach for sphenopetroclival meningiomas: surgical method and results in 10 patients. *Neurosurgery* 1991;28:869-876.
2. Jane JA, Park TS. Pobereskin LH, Winn HR, Buller AB. The supraorbital approach: technical *note. Neurosurgery* 1982; 11:537-542.
3. Al-Mefty O. The cranio-orbital zygomatic approach for intracranial lesions. *Contemporary Neurosurgery* 1992;14:l-6,
4. Al-Mefty O. Supraorbital-pterional approach to skull base lesions, *Neurosurgery* 1987:21:474-477.
5. Al-Mefty O. *Surgery of the cranial base.* Boston: Kluwer Academic Publishers, 1989.
6. Al-Mefty O, Ayoubi S, Schenk MP. Unlocking and entering the cavernous sinus. *Perspectives in Neurological Surgery* 1991;2:49-68.
7. Al-Mefty O, Holoubi A, Rifai A, Fox JL. Microsurgical removal of suprasellar meningiomas. *Neurosurgery* 1985;16:364-372.
8. Al-Mefty O, Smith RR. Tailoring the cranio-orbital approach. *Keio J Med* 1990;39:217-224.
9. Bowles AP Jr. Kinjo T, Al-Mefty O. Skull base approaches for posterior circulation aneurysms. *Skull Base Surgery* 1995;5:251-260.
10. DeMonte F. Al-Mefty O. Anterior clinoidal meningiomas. *Neurosurgical Operative Atlas* 1993;3(1):49-61.
11. Wascher TM, Spetzler RF, Zabramski JM. Improved transdural exposure and temporary occlusion of the petrous internal carotid artery for cavernous sinus surgery: technical note. *J Neurosurg* 1993; 78:834-837.
12. Al-Mefty O, Fox JL. Superolateral orbital exposure and reconstruction. *Surg Neural* 1985;23:609-613.
13. Anand VK, Sherwood C, Al-Mefty O. Optic nerve decompression via transethmoid and supraorbital approaches. *Operative Techniques in Otolaryngology-Head and Neck Surgery* 1991 ;2:157-166.

Surgery of the Skull Base. edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 15

Extended Transfacial Subcranial Approach

Paul J. Donald

One of the easiest and quickest approaches to skull base tumors is the anterior transfacial subcranial approach. The width of exposure varies between that afforded by a lateral rhinotomy incision, the Weber-Fergusson, and, finally, the most elaborate exposure, which includes splitting the lower lip and traversing the neck. For purely anterior cranial fossa approaches, only the first two are used. They give aesthetically acceptable scars while providing excellent access. Unfortunately, these approaches have limited applicability and should be used only when there is a small amount of cranial base invasion. This is especially true with the first approach described. The most elaborate technique, that involving mandibulectomy and maxillectomy, gives a wider exposure but is still restricted compared with a formal craniotomy. In many cases, intracranial disease extent does not permit adequate encompassment of disease or effective dural closure using this technique. On the other hand, when limited cranial base involvement is encountered, this is a quick, safe, and easy approach.

The anterior subcranial technique is in actuality a series of approaches of graduated complexity, producing increasingly wider exposure. These evolve as progressively aggressive resections are performed, dictated by the extent of disease (Table 1). These techniques obviate the need for the usual classic craniotomy through the calvarial vault. Instead, central exposure is accomplished by removing the calvarial floor, the skull base, in the areas of tumor penetration to a sufficiently wide degree to permit total, safe encompassment of central tumor extension. This technique requires little in the way of brain retraction, resulting in the early recovery phase in a more alert patient and an overall much smoother postoperative course.

The narrower exposures mandated by limited intracranial disease likewise allow only for narrow-field intracranial resection. Extensive intracranial tumors characteristic of those lesions primary to the tissues of the skull base, such as meningiomas originating from basal dura, chondroma, and chondrosarcoma emanating from the clivus, are usually not suitable for this approach. These approaches are most often applied to lesions of the upper aerodigestive tract, especially from the paranasal sinuses, that have only minor intracranial involvement. The standard type of craniotomy can still be done if large lesions with wide-field intracranial spread are inadequately exposed using this subcranial approach.

INDICATIONS

The most conservative and least traumatic technique begins with the simplest exposure, which is afforded by a lateral rhinotomy. It is used in those cases in which the disease is minimal and the eye is not involved (Fig. 1). Intracranial extension is small and the subcranial exposure of the dura and cranial nerves is limited. A typical example of this is the sphenoethmoid tumor whose skull base involvement is restricted to the lateral wall of the sphenoid sinus. Figure 2 illustrates a case of inverting papilloma that invaded the lateral wall of the sphenoid sinus and approximated the internal carotid artery. A subcranial transfacial approach with orbital preservation resulted in complete tumor ablation and no recurrence at 8-year follow-up (Fig. 3).

In such cases, preoperative computed tomography (CT) and magnetic resonance imaging (MRI) show a restricted area of cranial floor bone erosion and no involvement of the foramen ovale or the third division of the trigeminal nerve (V3). Limited involvement of the second branch of the trigeminal nerve (maxillary nerve or V2) may be approached in the patient with an intact eye, but this is often difficult. Tumor erosion of the clivus or lateral sphenoid sinus wall, with minimal involvement of the cavernous sinus or planum sphenoidale, are suitable for this approach.

In malignant tumors, invasion of the eye usually mandates orbital exenteration. Bone invasion without periorbital involvement allows for preservation of the eye if frozen-section analysis of periosteum adjacent to the tumor encroach-

P. J. Donald: Department of Otolaryngology—Head and Neck Surgery, and Center for Skull Base Surgery, University of California, Davis Medical Center, Sacramento, California 95817.

TABLE 1. *Types of transfacial subcranial surgical approaches*

Type I
  A Lateral rhinotomy-anterior maxillotomy-medial maxillectomy
  B Lateral rhinotomy and orbital exenteration
Type II Total maxillectomy-orbital exenteration-posterior maxillectomy-sphenoidotomy
Type III Total maxillectomy and composite resection of mandible

ment is negative. Similarly, the eye can be saved if a low-grade malignancy such as a well differentiated fibrosarcoma invades the periorbita or even, to a very slight degree, the periorbital fat (see Fig. 6, Chapter 10). Periorbital invasion of aggressive tumors, such as squamous cell carcinoma or malignant melanoma, is a definitive indication for orbital exenteration if the periorbital fat or apical periorbita is reached (Fig. 4).

Resections of the globe greatly expand the potential for subcranial exposure of cranial base invasion. Even through just the lateral rhinotomy approach, the superior orbital fissure, optic foramen, and foramen rotundum can be resected to dura. Figure 5 illustrates the usual tumor that extends in most instances from the ethmoid sinus and may extend into the posteriorly located sphenoethmoid area. MRI and CT scanning provide excellent preoperative clues to the orbital extent of disease (Fig. 6).

As tumor becomes more widespread and no longer remains confined to the ethmoid block and orbit, but invades the maxilla, a maxillectomy is required. In a few cases only. the upper maxilla is involved (Fig. 7), and a superior maxillectomy encompasses the disease. Preoperative assessment supplementing radiography with endoscopic evaluation through an expanded medial wall antrostomy or through a very limited Caldwell-Luc approach that does not enter into


FIG. 1. Limited lesion that can be addressed using the simplest of the anterior subcranial approaches.



FIG. 2. Coronal computed tomography scan of elderly man with inverting papilloma of the sphenoid and ethmoid sinuses invading the lateral sphenoid sinus wall and approximating the internal carotid artery.



FIG. 3. Follow-up of patient in Fig. 2 after limited anterior transfacial subcranial approach with resection of the lateral sphenoid sinus wall and limited excision of cavernous sinus dura. Axial computed tomography scan 2 years after surgery shows no evidence of sphenoid or ethmoid residuum.



FIG. 4. A: A lesion extending through the periorbita is best approached by the next gradation in radicality of tumor excision. B: Common mode of spread is through the orbital apex.



FIG. 5. Invasion of apex of orbit by aggressive tumor from the posterior ethmoids.



FIG. 6. Computed tomography scan of patient with squamous cell carcinoma with early orbital invasion requiring orbital exenteration.



FIG. 7. A: Tumor invading upper maxilla requiring superior maxillectomy. B: Computed tomography scan in this patient reveals tumor confined to the superior maxilla suitable for alveolar arch preservation.

tumor establishes the feasibility of preserving the alveolar ridge. Lack of bone erosion and the absence of a soft tissue density on radiography in the inferior maxilla and especially below Ohngren\s line (see Fig. 27, Chapter 6) usually indicates the safety of preserving the maxillary dental arch.

Most commonly, the entire maxillary sinus is involved with tumor. **In** these instances of malignant invasion, a total maxillectomy, usually with orbital exenteration, is indicated. *In* cases in which the total maxilleclomy is most commonly combined with a subcranial resection and inferior craniotomy, there is transgression of the posterior maxillary sinus wall by the neoplasm. The pterygoid plates are often eroded and a soft tissue density presents in the pterygomax-illary space and inferolalerally in the inferior aspect of the infratemporal fossa (Figs. 5, 8). The cranial base of the middle fossa is often invaded, as evidenced by erosion of the sphenoid bone or expansion of the foramen ovale or rotundum on the CT scan. The MRI better displays the soft tissue detail, delineating tumor invasion in Meckel's cave and the cavernous sinus, as well as adjacent dura and brain (Figs. 9, 10).

The most elaborate procedure using the anterior subcranial approach is used only occasionally and applies to those patients with maxillary sinus carcinoma that has invaded the pterygoid muscles or the rainus or condyle of the mandible (Fig. I I). The removal of the mandibularramus *en bloc* with the maxilla permits exposure of the entire middle fossa floor, cavernous sinus, and the complete length of both the petrous and cavernous segments of the internal carotid artery. CT and MRI are essential in helping to delineate full tumor ex-



FIG. 8. Coronal magnetic resonance image of patient with extensive nasopharyngeal carcinoma invading the posterior maxillary sinus, transgressing the posterior maxillary wall, and extending into the pterygomaxillary space but not invading the pterygoid muscles. Tumor invaded along the infraor-bital nerve into the gasserian ganglion and cavernous sinus.



FIG. 9. Coronal magnetic resonance image of patient with nasopharyngeal carcinoma demonstrating tumor extension through the foramen ovale.



FIG. 11. Coronal magnetic resonance image with gadolinium contrast of a patient with malignant schwannoma of the deep soft tissues of the cheek, showing tumor invasion of maxillary sinus, pterygoid muscles, mandibular ramus, buc-cal mucosa, middle cranial fossa floor, cavernous sinus, and petrous carotid artery.

tent. Balloon test occlusion coupled with either a xenon blood flow scan or single-photon emission computed tomography scan indicates the feasibility of internal carotid artery sacrifice (see Chapter 8). In most instances, however, carotid grafting is done.

Although the initial resection is an attempt at *en bloc* resection, in these cases a portion of the procedure often is a piecemeal type of resection to provide visualization. In the final phase of resection, the extensive use of frozen-section analysis establishes tumor-free margins. This philosophy and principle has been extensively alluded to in both Chapters 3 and 10. The initial block resection removes approximately 80% to 90% of the tumor with its margins of healthy tissue. Once this main tumor bulk, which has visually obscured the deep margins, is excised, the remaining neoplasm and margins are removed in the next block. The cranial floor and margins of the key foramina are drilled away to healthy bone, and the last subcranial and intracranial remnants are removed and margins checked.



FIG. 10. Coronal magnetic resonance image outlining Meckel's cave and cavernous sinus in patient in Fig. 9.

Not all the tumors to which the subcranial approach can be applied begin in the nose and paranasal sinuses. This is especially true of the most extensive approach when mandibulectomy is required. Tumors originating in the tongue base, tonsil, and pharynx may extend superiorly to the skull base. The usual pattern is direct extension into the posterior hard palate, maxillary tuberosity, pterygoid muscles, pterygoid plates, and posterior maxilla. This leads to the undersurface of the sphenoid bone and possibly the petrous tip. The clearance of the pharynx, the neck dissection, mandibulectomy, and posterior maxillectomy open the exposure first described by Krespi and Sisson (1) in their mandibulotomy approach to the skull base, and is extensively described by Gluckman et al. in Chapter 17 of this text. A total maxillectomy and orbital exenteration open the skull base to even wider exposure, as previously described.

There is nothing new about any of these operations. It is simply their combination, providing access to a portion of the midline skull base, that is perhaps a novel aspect.

TECHNIQUE

Type IA: Anterior Maxillotomy-Sphenoethmoid-Medial Maxillectomy Approach

The limited type IA approach is used in those aggressive benign tumors, such as inverting papilloma, or small malignant lesions that invade the posterior limits of the anterior cranial fossa base or middle fossa near the midline. Exposure is reduced because of preservation of the eye. This introductory technique is the basis for most of the remaining subcra-nial approaches. Type IB differs from type A only in that the eye is removed.

The incisions and details of the initial part of the type IA approach are no different from those described for the transfacial part in Chapter 10, dealing with the combined transcranial-transfacial approach to the anterior skull base. The type IA approach is probably little different from the approach to ethmoid tumors used decades ago when surgeons, unequipped with CT and MRI, determined tumor extent on the basis of plain films and linear tomography. Their inability to anticipate the intracranial penetration of tumor led to the "peek and shriek" phenomenon of arriving suddenly in the intracranial space, debulking the tumor, and retreating as soon as possible. The patient was then sent to radiation therapy in hopes of eradicating the disease. Dismal survival statistics such as a 20% or less 5-year tumor-free survival rate are a reflection of this desperate philosophy. It is curious today that some centers still espouse this philosophy of de-bulking and radiation therapy. However, among some of the surgeons of that era, there were those courageous individuals who attempted to encompass a tumor of limited intracranial extent, then excised and grafted the involved dura [G.A. Sisson, personal communication. American Association of Otolaryngology—Head and Neck Surgery (AAO-HNS) Instructional Program: Tumor Surgery of the Skull Base, 1989J. The Type IA and B resections differ little from the procedure used by those pioneers. To avoid needless repetition, a detailed description of the cutaneous incision, lateral rhinotomy, and bony excisions is eliminated. For orientation, the diagrams depicting these steps are reproduced (Fig. 12).

The exposure of the anterior fossa floor is restricted to the cribriform plate and the fovea ethmoidalis (Fig. 13). Early tumor invasion in these areas is best encompassed by removing the first block, which encompasses over 90% of the tumor in addition to tumor-free margins around the neoplasm's subcranial periphery. Now, only that small area where the tumor penetrates the bony barrier between the subcranial and intracranial spaces remains. The area of tumor involvement of bone is outlined with a small osteotome, cutting bur, or the cutting blade of the Midas Rex, clearing visible tumor by at least 5 mm (Fig. 14). Care is taken not to penetrate dura. If dura is invaded, then a 5-mm area of grossly unaffected tissue is removed. If brain invasion is obvious, then the subcranial approach is abandoned and a frontal craniotomy performed. When the tumor extension is limited to dura, the final block of excision includes the aforementioned cuff of healthy dura and bone as well as residual tumor (Fig. 15). Frozen-section margins are checked to ensure complete tumor excision. Even if only the bone of the cribriform area is involved, invasion of the fila olefactoria is inevitable, and some dura requires excision. Those amputated dura projections that lie outside of the tumor encroachment area usually require some form of suture to ensure a watertight seal.

The dural defect is closed by suturing in a patch of fascia lata or lyophilized dura (Fig. 16). Any questionable areas of leakage are secured with tissue glue to prevent cerebrospinal fluid rhinorrhea. A skin graft is placed over all raw surfaces and the cavity packed. If a maxillary ostectomy is used, the anterior wall of the maxilla is replaced, anchored with a microplate to the nose and with a miniplate to the maxilla (Fig. 17).

One of the major drawbacks of this technique is the lack of vascularized tissue used in the reconstruction. If the nasal septum is intact, it provides excellent cover and support. The mucosa is denuded from the tumor side. The septal skeleton and nontumor-side mucosa are cut on three perimeters through-and-through and pedicled on the mucosa of the nasal vault on the nontumor side. A greenstick fracture is created at the junction of the perpendicular plate of the ethmoid and the nasal vault. The flap is tipped superiorly, hinged on the mucoperiosteum of the nasal vault, and placed denuded skeletal surface first into the defect. A couple of anchor sutures are placed, and the flap packed into position (Fig. 18). The bone and cartilage of the nasal septum face the dural graft and the mucosa faces the cavity. When feasible, this is an excellent flap, offering both skeletal covering and cavity-lining membrane with an excellent pedicle.

The cutaneous incision is closed with interrupted sutures and dressed with antibiotic ointment.

Occasionally, especially in the case of more benign tumors such as inverting papillomata, the tumor does not invade the globe, but has considerable posterior extension in the region of the upper posterior maxilla, the posterior ethmoids, the sphenoid sinus, and even the nasopharynx (Fig. 19). The type IA operation is feasible if invasion of the anterior fossa floor is minimal, involvement of the planum sphenoidale is minor, or when the lateral sphenoid wall is invaded with only limited encroachment on the medial wall of the cavernous sinus, as is seen in Fig. 2. The details of resection at this site are elaborated in the section describing the type II dissection.

Type IB: Type IA Plus Orbital Exenteration

This procedure is seldom done because tumors with enough extension to involve the skull base and orbit usually



FIG. 12. Initial steps in tumor exposure using subcranial \rans1acia\ approach type IA. A: Lateral rhinotomy incision. B: Lateral rhinotomy done with powered cutting blade. C: Denker resection using anterior maxillary ostectomy. D: Ethmoidectomy and initial tumor debufking. E: Medial maxillectomy, inferior cut. F: Medial maxillectomy, posterior cut.



FIG. 13. Exposure of residual tumor on anterior cranial fossa floor in area of cribriform plate and fovea ethmoidalis.



FIG. 15. Resection specimen containing last block of subcranial tumor anterior fossa floor, and dural invasion.



FIG. 14. Tumor invasion of anterior fossa floor is encompassed with a margin of healthy bone using powered cutting blade.



FIG. 16. Fascia lata patch replacing excised dura.



FIG. 17. Maxillary ostectomy repaired by osteosynthesis with microplates.



FIG. 18. Nasal septal flap used to repair anterior cranial floor defect.



FIG. 19, Limits of tumor resection possible with the type IA approach, which is usually used for more benign but locally aggressive lesions like inverting papilloma.

involve a substantial amount of the maxilla and require total maxillectomy. Occasionally, only the superior maxilla is involved and the alveolar ridge can be spared (see Fig. 13). Initially, the tumor is debulked to ascertain the necessity of orbital exenteration and to judge the amount of cranial floor involvement to see if the subcranial route is suitable (Fig. 20).

The details of orbital excnteration are described in Chapter 10 and need no further elaboration here. Resection of the globe greatly expands the access to the anterior cranial fossa floor. One of the areas of serious visual impediment for the surgeon is the anteriormosL limit of the anterior fossa floor, where it joins the vertical part of the posterior frontal sinus wall. Tumor involvement here mandates some form of anterior craniotomy. albeit low and limited. The osteoplastic flap technique described by Schramm (2) or the frontonasal orbital osteotomy approach of Raveh et al. (3) can be used effectively (see also Chapter 13).

Dural invasion through the orbital roof is readily identified and can be followed back to the lesser wing of the sphenoid. Posteromedial disease should be managed only if it falls short of the planum sphenoidale. The optic chiasm is too close to manage safely in a blind fashion from below, and dural involvement cannot be safely resected or repaired using this approach.

The posterior and posterolateral aspects of the orbit face the middle cranial fossa. Only very limited involvement at this site can be handled by the subcranial approach (see Fig. 4). The superior orbital fissure leads directly into the cav-



FIG. 20. Tumor has been debulked in type IB procedure, and assessment of ocular involvement and involvement of the anterior fossa floor ascertained.

ernous sinus. Some early invasion at this site can be excised by drilling bone and excising the sheath of the cranial nerves as they enter the orbit. The ophthalmic veins will be a problem whose magnitude reflects the rapidity of their development into a significant contribution to the anterior aspect of the cavernous sinus.

Management of the optic nerve requires special attention. Progress along the nerve quickly leads into the lateral wall of the sphenoid sinus. The bone is particularly thick at the orbital apex, but thins as the sphenoid sinus is entered. The bone here is often dehiscent, especially if there is an Onodi cell that invaginates the anterior aspect of the sphenoid sinus. In neurotropic tumors, following the optic nerve, the maxillary nerve through the foramen rotundum and the vidian nerve through its canal may be taken to the point where they become negative on frozen-section analysis, without a formal *craniotomy. Without* a superior *maxillectomy*, however, the vidian nerve is hard to identify and trace. Following these nerves to the point at which they pierce the dura is done through this approach, but if the nerve is positive by frozen-section analysis at this point, an initial foray into the middle fossa is done in a limited way. If tumor cannot be encompassed with this minimal exposure, a formal craniotomy is required. Resection of tumor in the superior orbital fissure can be done as well but, again, only a limited resection can be performed because the cranial nerves here enter the cavernous sinus.

Erosion of the lateral sphenoid sinus wall can be managed with the eye removed. The sphenoid bone, which usually obscures the lateral wall, can be removed. The optic canal, optic chiasm, and internal carotid bulge are identified. Bone can be removed with a small cutting or diamond bur, exposing the medial dura of the cavernous sinus. Minimal invasion of the sinus can be managed with this approach, but more extensive tumor necessitates middle fossa craniotomy with the infratemporal fossa-middle fossa approach.

Tumor invasion of the floor of the sphenoid sinus and its posterior wall can be removed with the bur. The floor can be resected with impunity, and the resection can be carried down to the level of the nasopharynx along the length of the clivus if necessary. The posterior wall of the sinus as well as the clival bone beyond the cavity of the sphenoid needs to be removed more judiciously. A preoperative check of the CT scan verifies the thickness of bone between the nasopharynx and pontine dura (Fig. 21). If substantial bone has been eroded or there is extensive postsphenoid pneumatization, prudence must be exercised in bone removal. Pontine dura can be removed, bearing in mind that obtaining a watertight seal with a dural patch is extremely difficult. In addition, the basilar artery is very close to the dura (Fig. 22). Mobility in this region is restricted without a maxillectomy, and extensive clival resections are rarely done without one.

Closure is effected by repairing the dura and skin grafting the defect with a thin split-thickness graft. Any dural resec-



FIG. 21. Coronal magnetic resonance image showing very thin and absent bone in the clivus and proximity of tumor to clival dura.



FIG. 22. Axial magnetic resonance image showing proximity of tumor to basilar artery and pontine dura.

tion is necessarily small through this approach, and the hole is patched with fascia. The rich blood supply to the orbital bony walls allows for the usually easy take of the graft. The orbit is packed with medicated gauze and the wound closed as previously described.

Type II

The type II operation incorporates a maxillectomy. This is done through the modified Weber-Fergusson incision (Fig. 23). The standard maxillectomy described in Chapter 10 is performed, and for the sake of clarity and continuity, these steps are repeated in Fig. 24.

The maxillectomy is usually done leaving a residual small triangle of posterior maxillary wall to which the pterygoid plates are fixed inferiorly. The maxillectomy is usually combined with an orbital exenteration because of the advanced nature of these tumors. The optic nerve, infraorbital nerve, and vidian nerve can now all be clearly identified with this exposure. The posterior wall of the maxilla and the pterygoid



FIG. 23. Modified Weber-Fergusson incision.



FIG. 24. Steps in total maxillectomy. A: Bony cuts through the lateral orbital rim, zygomatic buttress, alveolar ridge, lateral wall of nose, and ethmoid block. B: Dissection through palate between maxillary tuberosity and pterygoid plates.

plates are removed with the cutting bur (Fig. 25), exposing the pterygomaxillary space, the contents of which are removed lo expose the palatal muscles (Fig. 26).

The triangular configuration created by connecting the op-cic foramen, the foramen rolundum, and the vidian canal, with the apex at the optic foramen superiorly and the base comprising the latter two foramina, produces a strategic anatomic region over the base of the sphenoid bone (Fig. 27). This triangle becomes apparent when the posterior maxilla is excised, exposing the pterygomaxillary space, the pterygoid plates individually, and the pterygoid muscles. Pterygoid muscle invasion must be excised from and including the plates to the muscular insertions on the mandible. If the lateral pterygoid is significantly involved, the condyle and icmporomandibular joint structures usually require excision. This necessitates the addition of a neck incision and carries the procedure beyond the type II approach into the type Til approach. A minor degree of medial pterygoid invasion can be effectively managed through this incision, biu much more requires the wider exposure of type II!. Superiorly, the invasion of the sphenoid base in the area of the optic-vidian-ro-tundurn triangle is removed with the bur. The bone here is particularly thick, and tumor can often be totally resected without an intracranial exposure.

The addition of the maxillectomy markedly improves the clival exposure as well as the exposure of the orbital apex. More dura of the anterior fossa floor and the middle fossa, especially over the anterior tip of the temporal lobe of the brain, can be exposed and resected with good control (see Fig. 25).

Much more of the bone at the floor of the middle fossa is accessible once the pterygoid plates are removed (see Fig.



FIG. 25. Removal of posterior maxillary wall and pterygoid plates with the cutting bur.



FIG. 26. The pterygoid plates are removed, the pterygoid muscles retracted, and the palatal muscles exposed.


Optic canal
Foramen rotumdum
Vidian canal

FIG. 27. The posterior wall of the maxilla and orbital apex demonstrating the triangle formed between the optic canal, foramen rotundum, and vidian canal.

продолжение

продол
жение



FIG. 26. The pterygoid plates are removed, the pterygoid muscles retracted, and the palatal muscles exposed.


Optic canal
Foramen rotumdum
Vidian canal

FIG. 27. The posterior wall of the maxilla and orbital apex demonstrating the triangle formed between the optic canal, foramen rotundum, and vidian canal.

26). The pterygoid muscles retract and a view of the undersurface of the medial aspect of the middle fossa floor is obtained. Tumor invading the under/surface of the sphenoid bone can be removed. Tumor extending along the optic nerve can be traced back to the chiasm. The cartilaginous eustachian tube is visualized from the nasopharyngeal end to its interdigitation with its medial bony components. Part of the view is obscured by the presence of the palatal muscles. These can be dissected off their origins on the undersurface of the sphenoid and temporal bones, respectively (Fig. 28). The cartilaginous tube can be completely dissected off and tumor infiltration of any bone posterior or superior to it can be removed (Fig, 29). Further dissection laterally is limited by the condyle of the mandible and the retracted lateral pterygoid muscle. Exposure of the foramen ovale and V3 can be often achieved, but the view obstructed in some cases by the condyle and lateral pterygoid.

Only limited dural involvement can be resected here, but more so than in the exposure afforded by the type IB operation.

Removal of bone in the region of the cartilaginous eustachian tube (Fig. 30) must be carefully done because of the proximity superomedially of the internal carotid artery. Carotid exposure up to and through the foramen lacerum can be achieved by drilling through the petrous tip and interdigitaling sphenoid. The problem lies in the lack of control of the proximal artery and the incomplete exposure of the lateral aspect of its petrous portion. As previously mentioned, however, small degrees of tumor invasion of the carotid canal can be removed through this route. The optic nerve may be involved by perinerual spread, and it can be dissected to the optic chiasm (Fig. 31)



FIG. 28. Following tumor resection. *S,* sphenoid sinus; *ICA,* internal carotoid artery; *OA,* orbital apex; OC, optic canal; *D,* temporal lobe dura; 71, temporal lobe brain.



FIG. 29. A: Resection of palatal .muscles off their origins on the sphenoid and temporal bones. B: Resection of cartilaginous eustachian tube.



FIG. 30. Limited resection of small remnants of tumor invading the bony eustachian tube done with the cutting bur.



FIG. 31. Optic nerve dissected to the optic chiasm.



FIG. 32. Septal flap pedicled posterosuperiorly and rotated into nasopharyngeal defect.

Dural closure is performed in the fashion previously outlined. The orbit and denuded cheek area are skin grafted. Exposed dura, especially when grafted, and carotid must be covered by viable tissue. The sphenoid sinus is packed with a free abdominal tat graft and the anterior opening plugged with a bone or cartilage graft from the nasal septum or maxillary bone uninvolved by tumor and removed previously for exposure. A septal flap of mucoperiosteum pedicled on the vomer, or even preserved rostral sphenoid mucosa, the nasopharyngeal vault, or the nasal side of the soft palate can be rotated 180 degrees into the defect (Fig. 32).

A preformed palatal obturator is fixed to the remaining teeth or residual palate.

Type m

The most extensive type of subcranial approach includes resection of both the maxilla and the mandible. The exposure



FIG. 33. Type III incision. A: Facial incision. B: Intraoral incision.



FIG. 34. Extensive perineural spread of cancer of lip along mental and inferior alveolar nerve, requiring hemimandibulectomy as part of type III excision.

of the subcranial floor of both the anterior and middle fossa afforded by this approach is extensive. This resection is done for very large, invasive upper aerodigestive tract malignancies whose intracranial involvement, is usually small compared with the subcranial component. A radical neck dissection is done in continuity with the subcranial block if metastasis is present or if a high frequency of occult nodal spread is anticipated.

A Weber-Fergusson incision is extended intraorally and into the pharynx to encompass whatever oral or pharyngeal tumor exists. It is carried along the gingivobuccal sulcus through the oral buccal mucosa from the pharynx to the midline of the lip (Fig. 33). The lower lip is split, creating a dart in the vermilion border, and the incision is carried around the natural crease of the chin button, extending in a curvilinear manner into the upper neck.

The maxillectomy is performed, often with an orbital exenteration (done in 50% of the author's cases) as previously described. The extent of partial mandibulectomy varies with local extent of tumor. Because most neoplasms originate in the lateral oropharynx, nasopharynx, palate, or deep in the infratemporal fossa, most mandibular resections include the condyle, ramus, and angle. Occasionally, a recurrent tongue cancer or alveolar ridge tumor with extensive perineural spread may require mandibular body resection as well (Fig. 34),

On some occasions, only the posterior maxilla is involved, and a Weber-Fergusson incision is not required. The distal alveolus and posterior wall with pterygoid plates attached are removed intraorally, similar to the procedure described by Day and Donald (4). The exposure of the skull base is then similar to that described by Gluckman et al, in Chapter 17 of this text,

In the standard type III approach, a much wider extent of the skull base is exposed. The internal carotid artery and internal jugular vein are isolated in the upper neck and are individually loosely encircled by soft catheters. Pharyngeal, lingual, palatal, and buccal soft tissues are resected in continuity with the mandible and maxilla. The immediate subcranial and intracranial portion of the tumor is amputated from the main specimen in the "modified *en bloc'* resection method described previously (Fig. 35). Bearing in mind the amount of bony destruction and soft tissue tumor extension portrayed in the preoperative CT and MRI scans and that visualized with the main tumor specimen removed, subcranial and intracranial resection proceeds.

Bony limits of tumor invasion are defined, keeping in mind that although direct bone erosion occurs with aggressive neoplasms, the most common avenues of spread are



FIG. 35, Example of tumor extension visualized after main mass of neoplasm resected. *Solid arrow* shows petrous carotid artery with tumor on it.



FIG. 36. Drilling away of the bone of the carotid canal.

through vascular and neural foramina. Therefore, careful exploration of the carotid canal, jugular foramen, foramen spinosum, and especially the foramen ovale is important. A clear view of the foramen ovale may now be obtained because of the removal of the hetnimandibule and pterygoid muscles. The foramen rotundum and optic canal may also be involved. Extension of tumor along the trigeminal nerve branches is commonly seen. Gross Meeker s cave and cavernous sinus involvement are often revealed in the preoperalive MRI scans, but microscopic invasion is rarely portrayed (5). The internal carotid artery may be followed from the carotid canal to the foramen lacerum and thence to the cavernous sinus by drilling away the carotid canal bone from below (Fig. 36). Starting at the fibrous ring in the upper extremity of the neck, the artery is followed superiorly through the foramen until it starts to make its bend into its horizontal course. Bone is further removed up to the foramen lacerum, where the vessel again becomes vertical as it enters the intracranial cavity in the cavernous sinus (Fig. 37). If the carotid is invaded by tumor, it is removed and replaced with a saphenous vein graft (Fig. 38). If the cavernous sinus is invaded, it is removed in its entirety with frozen-section control of margins.



FIG. 37. Internal carotid artery is exposed from the cavernous sinus to the fibrous ring in the neck.



FIG. 38. Diagram showing vein graft.

Jugular vein invasion is followed into the jugular foramen, with care taken to plug the inferior petrosal sinus with hemostatic gauze as dissection proceeds subtemporally into the sigmoid sinus. Once in the sigmoid, hemostasis in the sinus is ensured by a plug of hemostatic gauze (Fig. 39). Figure 40 illustrates a patient with malignant schwannoma who underwent a type III resection. Compromise of the lower cranial nerves emanating from the jugular foramen is inevitable when resecting malignancy in this area. Thyroplasty and cricopharyngeal myotomy may be done at a later time to improve speech, prevent aspiration, and aid in swallowing.

Meckel's cave dissection may need to be followed by trigeminal trunk dissection over the petrous ridge. Such extensive dissection may need to be aided by a temporal or temporal-occipital craniotomy. The latter might best be done as a second stage. Eustachian tube involvement can be resected from the nasopharyngeal to the tympanic end using this approach.

Temporal lobe dura and a portion of the lobe itself can be removed with this exposure. The amount of temporal lobe resection is limited to the silent areas, and extent of tumor is usually predictable by MRI.

Wound closure requires a watertight seal between the in-



FIG. 39. Jugular vein resection with a hemostatic gauze plug in the inferior petrosal sinus. A: Carotid retracted with graft and tumor being resected from jugular fossa. B: Jugular bulb occluded, internal jugular vein tied off, and inferior petrosal sinus sealed with hemostatic plug.



FIG. 40. Tumor involvement of middle fossa floor and internal carotid artery in patient with a malignant schwannoma of the infra temporal fossa. A: Initial incision marked out. B: Incision made.

(figure continues)



FIG. 40. *Continued.* C: Tumor exposed. D: Tumor removed. E: Skull base exposure with internal carotid artery involvement. Suction pointing to the tumor on the carotid artery in the foramen lacerum. F: Saphe-nous vein graft in place.



FIG. 41. Latissimus dorsi free flap used to repair massive subcranial defect after type Flap resection. A: elevated and about to be placed in defect. B: Flap sutured into defect.

tracranial cavity and the widely exposed, extensively exenterated upper aerodigestive tract. These patients are usually failures of past surgery and radiation therapy, so wound healing may be a problem. Vascularized free tissue transfer is the answer to this problem in most cases. Resected dura is replaced with fascia or preserved cadaveric dura. Large soft tissue replacement is often required for the subcranial repair. The latissimus dorsi free flap (Fig. 41) provides excellent bulk with an epithelial lining. The rectus abdominis flap with an overlying skin graft or intact abdominal skin is useful as well. The muscle is turned to the side of the dural repair and the skin is sutured to any cutaneous defect or used as a cavity liner. A deepithelialized bridge interposed at the level of the skin repair can provide both facial cutaneous replacement and cavity lining.

The results of this approach vary according to the extent of tumor involvement, with the most favorable lesions being the small ones that have minimal subcranial extent, and the large ones requiring type III excision carrying the worst prognosis.

REFERENCES

1. Krespi **YP,** Sisson GA. Transmandibular exposure of the skull base. *Am JSurg* 1984:148:534-538.
2. Schramm VL Jr. Anterior craniofacial resection. In: Jackson **CG,** ed. *Surgery of skull base tumors.* New York: Churchill Livingstone. 1991:67-83.
3. Raveh J, Turk JB, Ladrach K, ei al. Extended anterior subcranial approach for skull base tumors: long term results. *J Neurosurv* I995;82:]Q02-1010.
4. Day T, Donald PJ. Posterior bimaxillary composite resection for squamous cell carcinoma of the retrotnolar irigone. *Head Neck (submitted for publication).*
5. Nemzek W, Hecht S. Grandeur-Ed wards R. Donald PJ. Perineural spread of head and neck tumors: how accurate is **MR** imaging? *Am J Neuroradiol (in press).*

Surgery of the Skull Base, edited by Paul J. Donald.
LippmcoU-Raven Publishers, Philadelphia © 1998.

CHAPTER 16

□

Infratemporal Fossa—Middle Cranial Fossa Approach

PaulJ. Donald

Probably the most difficult and complex of all the approaches in skull base surgery is the infratemporal fossa-middle cranial fossa approach. It is also the most versatile, giving access not only to all of the subcranial tissues that underlie the middle fossa floor from the zygoma to the nasopharynx, but to the contents of the middle cranial fossa from the lesser sphenoid wing to the tentorium, including the petrous ridge and cavernous sinus. The clivus is widely exposed, and cutting the tentorium can expose the upper brainstem.

Considerable credit must be given to the originators of this operation. Ugo Fisch of Zurich designed the infratemporal fossa approach and first presented it in 1977 (1). It forms the basis for all the approaches to the lateral and inferolateral skull base that have been developed since. The first well coordinated intracranial and extracranial approach to this region was designed by Victor Schramm (2) and Laligam Sekhar when they were both at the University of Pittsburgh. They modified Fisch's approach, creating an excellent simultaneous exposure of the intracranial and extracranial aspects of the middle fossa through a small but strategically placed craniotomy. The removal of this bony barrier improved maneuverability in both the intracranial and extracranial compartments. The procedure described in this chapter is markedly similar to Schramm and Sekhar's operation, with some modifications.

Patients who require this operation for malignant disease usually have a more extensive lesion than those who need anterior fossa skull base surgery. They often require longer periods of time in the intensive care unit and a more prolonged hospital stay. The keystone structures that are responsible for many of the problems arising from this surgery are the cavernous sinus and the internal carotid artery (ICA). Resection of either or both of these structures may leave the patient with substantial deficits. In malignancy, the entire sinus often needs to be removed, creating an immobile and sometimes insensate eye with ptosis of the upper lid. The cornea, therefore, is extremely prone to injury, not only from unappreciated trauma but also from sympathetic dystrophy secondary to autonomic denervation. If the original tumor is an extension from a lesion in the paranasal sinuses, then the orbit is usually exenterated and these sequelae are not an issue. Management of the carotid is still unsettled, but arterial invasion usually mandates resection in cases of malignancy and grafting rather than sacrifice, even in the presence of a negative balloon test occlusion (BTO) and favorable single-photon emission computed tomography (SPECT) scan (see Chapter 7).

It is only fair to interject at this juncture that the resection of the cavernous ICA and cavernous sinus in the face of malignancy, especially squamous cell carcinoma, remains highly controversial.

CLINICAL PRESENTATION

Patients who require this approach present with a wide variety of disease processes. The primary consideration in this chapter is tumor. The tumors may be benign or malignant, and may originate intracranially from dura or calvarial bone or extracranially from the manifold soft tissues that occupy the subcranial area. Chapter 3 describes the types and behavioral characteristics of these various tumors. Most common among the intracranial neoplasms that extend extracranially are meningioma, chordoma, chondroma, and chondrosarcoma. Among the extracranial tumors that extend intracranially are schwannoma, often of the trigeminal nerve; parotid tumors, both benign and malignant, especially from the deep lobe; and squamous cell carcinomas from the paranasal sinuses, nasopharynx, and temporal bone. Meta-

P. J. Donald: Department of Otolaryngology-Head and Neck Surgery, and Center for Skull Base Surgery, University of California, Davis Medical Center, Sacramento, California 95817.

static deposits in high lymph nodes from any head and neck site, but more often from the nasopharynx or paranasal sinuses, may erode through the middle fossa skull base. Rarely, metastases from distant sites such as breast, prostate, or kidney may present as a pathologic node at the skull base. A rather curious inflammatory lesion may present itself as a skull base neoplasm both in symptomatology and in radiographic appearance. This is a variant of the so-called Tolosa-Hunt syndrome (Fig. 1). The author's team has had four such patients in their experience, all of whom resolved on steroid therapy.

Unfortunately, the presenting symptoms of lesions in this area are often subtle. Many patients complain of pain only in the region of the infratemporal fossa, ear, or behind the eye. This symptom is often passed off as myofascial dysfunction or "temporomandibular joint" (TMJ) syndrome. Trismus secondary to pterygoid muscle invasion or direct involvement of the mandibular branch of the trigeminal nerve may still be mistaken for these syndromes. Any patient with a past history of carcinoma of the nasopharynx or oropharynx must be viewed with a high index of suspicion when presenting with pain in the infratemporal fossa.

Special attention should be focused on the patient with oropharyngeal carcinoma who, after the standard therapy of composite resection and postoperative radiation therapy, presents with pain deep in the infratemporal fossa. The clinician should especially be alerted if the pain is new. There is often little to find on physical examination other than an occasional increase in trismus. Because the inferior alveolar nerve has been sacrificed in the initial resection, the only remaining sensory nerve from V3 is the auriculotemporal, which may also have been injured at surgery. Such patients should have magnetic resonance imaging (MRI). Because of the obscuring distortions of the past surgery and radiation, it is often difficult to distinguish fibrosis and edema from tumor, even with gadolinium contrast (see Fig. 8, Chapter 5). Often, serial MRIs at 6-week to 3-month intervals are the only means by which to make a diagnosis. Unfortunately, valuable time may be lost as the tumor continues to grow and is constantly at risk of metastasis. Analysis by positron emission tomography (PET) scanning may be of great assistance here (3).



FIG. 1. Magnetic resonance image in coronal plane showing what appears to be a tumor of the infratemporal fossa involving the mandibular branch of the trigeminal nerve and the cavernous sinus. Surgical exploration revealed only inflammation.



FIG. 2. Magnetic resonance image showing extensive, recurrent tumor in deep lobe of parotid gland that resulted in facial nerve paralysis and extension to the odontoid of C2.

Carcinoma of the temporal bone may be subtle or patently obvious (see Figs. 3 and 30, Chapter 5). The symptom of painful otorrhea unresponsive to vigorous local therapy is highly suspect. Temporal bone carcinoma is covered in Chapter 20, but it is important to mention that anterior extension can involve the infratemporal fossa.

As in temporal bone carcinoma, malignancies in the infratemporal fossa may present with a facial nerve paralysis. This is especially true of parotid gland carcinomas. Recurrent carcinoma or tumors of the deep lobe often involve the facial nerve. Paresis or complete paralysis of the entire nerve, indicating main trunk invasion, is usually the rule (Fig. 2).

Extension of tumor through the foramen ovale along the third division of the trigeminal nerve can produce numbness over its sensory distribution and, by spread through the gasserian ganglion, hypesthesia of both the second and first divisions of the trigeminal nerve. This manifests itself initially as numbness over the chin and lower face and then advances to numbness over the midface, especially the area subserved by the infraorbital nerve with V2 involvement and the forehead and cornea if V1 is affected. Once the tumor has reached the gasserian ganglion in Meckel's cave, extension



FIG. 3. Patient with extension of squamous cell carcinoma along the infraorbital nerve to produce numbness of all three divisions of the trigeminal nerve, as well as complete ophthalmoplegia and ptosis of the upper eyelid. A: Frontal view of patient. B: Computed tomography scan showing cavernous sinus invasion.

into the cavernous sinus is imminent. Once this occurs, paralysis of the oculomotor, trochlear, and abducens nerves often follows. Ptosis and ophthalmoplegia are the result (Fig. 3).

Tumor extension directly from the nasopharynx usually follows the foramen lacerum. The subsequent invasion of the cavernous sinus commonly produces abducens nerve paralysis with a lateral rectus palsy (Fig. 4). Invasion of the lateral wall of the sinus results in affliction of cranial nerves III and IV, and eventually involvement of V2. V3. and the optic nerve with extension superiorly.

Invasion of the carotid artery is usually asymptomatic. Rarely is the tumor so advanced as completely to occlude the vessel. Were that to occur, a stroke may ensue. This is possible even with reduced flow in a patient with already compromised cerebral circulation.

Involvement of temporal dura commonly produces unremitting, intense headache (Fig. 5). Because much of the temporal lobe is "silent," brain invasion gives little in the way of differentiating signs and .symptoms.

With metastatic tumor to high internal jugular, parapharyngeal, or retropharyngeal lymph nodes, lower cranial nerves may be affected. Extracapsular tumor spread from these nodes may erode skull base bone and invade the jugular foramen, producing symptoms secondary to affliction of cranial nerves IX, X, XL and, with spread to the adjacent hypoglossal canal, XII. The cervical sympathetic may be involved, producing Homer's syndrome. Clinical investigation of these patients, after a thorough head and neck and neurologic examination, includes a thorough general medical assessment, If a tumor is deemed operable, two other medical circumstances preclude an attempt at infratemporal fossa-middle cranial fossa excision. The first is the presence of distant metastasis and the second is general lack of medical fitness. General debility from extensive physiologic aging, severe cardiovascular disease, poorly controlled diabetes, or incipient renal or hepatic failure is a contraindication to surgery. A final contraindication to surgery is lack of patient commitment. Some natural reluctance to undergo such an extensive procedure is anticipated, but a lackluster attitude on the part of the patient, coupled with perhaps overzealous enthusiasm of family or friends, should be carefully assessed before consideration of surgery.

Magnetic resonance imaging with gadolinium contrast and, if indicated, fat suppression should be complemented by fine-cut computed tomography scanning through the skull base. The coronal plane is most helpful in clearly outlining carotid involvement and cavernous sinus invasion. Bony detail is best delineated with computed tomography, and soft tissue invasion by MRI. Gadolinium contrast is extremely helpful in differentiating minor from adjacent soft tissue, especially in recurrent or persistent disease. A word of warning is necessary, however, regarding these studies; there are false-negative and false-positive scans. Moreover, the studies do not always accurately delineate the extent of tumor.

Chapter 19 of this text is already devoted to the management of the ICA. There are many methods of evaluating the patency of the circle of Willis but, more important, the surgeon must assess the amount of blood flow from collateral circulation if the ICA on the tumor side is removed. The gold standard has been BTO of the ICA using radioactive xenon





FIG. 4. Patient with a lateral rectus muscle palsy of the eye secondary to direct invasion of the cavernous sinus through the foramen lacerum by a nasopharyngeal carcinoma. A: Straight-ahead gaze. B: Lateral gaze, revealing lateral rectus palsy of left eye. C: Computed tomography scan demonstrating carcinoma of nasopharynx invading cavernous sinus.



FIG. 5. A: Middle-aged man with recurrent temporal bone carcinoma presenting with excruciating cranial pain. B: Magnetic resonance image showing extensive dural involvement and brain invasion.

TABLE 1. *Sensitivity of positron emission tomography scanning in head and neck and skull base cancer*

Type of disease	False-positive results	False-negative results	Error rate
Primary Recurrent	1/8 2/22	2/8 1/23	38% 14%
Regional metastases	3/12	2/18	17%
Distant metastases	2/11	1/18	10%

to provide a calculation of cerebral blood flow before and after temporary occlusion. Xenon studies are notoriously difficult to perform because of frequent fluctuations in gas concentrations and problems with the measuring equipment. Much more practical has been the use of SPECT with technetium-99m hexamethylpropyleneamine oxime (HMPAO) contrast (see Chapter 7). This has produced predictable results for the author's team, and is their investigative method of choice. For a more complete analysis of investigation of the ICA, see Chapters 7 and 19.

The investigative tool most recently incorporated into the team's armamentarium is the PET scan. Because of the avidity of tumor cells for glucose, a nonmetabolizing, radioactive, fluoridated analogue is given and subsequent PET scans are done. In the author's experience, the accuracy for the detection of previously untreated primary disease is 87%, and for recurrent or persistent disease, 86%. The false-positive and false-negative rates and sensitivity are given in Table 1.

As with all skull base tumor patients, extensive discussion between the patient and the head and neck surgeon, the neurosurgeon, and the plastic surgeon ensues. It is important for the patient to understand the arduousness of the procedure, what functions will be lost, what cosmetic deformities will result, and what other treatment options exist. For malignant tumors, skull base surgery often remains the only chance for cure. The surgeon must be realistic—not overenthusiastic, but encouraging—when discussing options with these often desperate patients.

SURGICAL PROCEDURE

Preparation

As in most of the author's skull base patients, there is a routine preoperative set of procedures that includes tracheostomy, the placement of a lumbar subarachnoid drain, and instillation of Frost temporary tarsorrhaphy sutures in the eyelids (see Fig. 2, Chapter 29). Unless fixation pins are insisted on by the neurosurgeon, a Mayfield horseshoe head rest is used for ease of surgical access. Central venous pressure and arterial lines are usually placed, and any cranial nerve monitoring devices inserted. Electroencephalography electrodes are sutured or stapled to the scalp to monitor cerebral electrical activity in cases of possible ICA sacrifice.

An extensive surgical preparation is usually necessary, including a head shave with a scrub of the entire face, head, neck, and anterior chest. The abdomen is also prepared if a rectus abdominis flap is to be used as a vascularized free tissue transfer for reconstruction. Often, both legs are scrubbed in anticipation of the possible harvest of split-thickness skin, fascia lata. or saphenous vein grafts (Fig. 6).

Incision

The standard skin incision can be of two types, depending on the location of the lesion. For more anteriorly located lesions such as deep-lobe parotid tumors, lesions invading the foramen ovale, or nasopharyngeal carcinoma, the incision extends in a curvilinear fashion from the vertex of the skull, in front of the ear in a preauricular crease, and under the lobule of the ear. then curves forward in the upper neck, resembling a modified Blair incision for parotidectomy (Fig. 7A,B). The posterior incision goes behind the ear 2 to 4 cm, similar to the incision described by Fisch and extending into the neck toward the hyoid. Lesions such as temporal bone carcinomas, extensive glomus jugulare tumors, and clival chordomas are examples of when to use the posterior incision (see Fig. 7C,D). A lazy-S is subtended into the neck if a radical neck dissection is to accompany the procedure.



FIG. 6. Patient with multiple sites surgically prepared, including the site of craniofacial cervical incision and graft or flap donor sites.

t



FIG. 7. Incision for middle temporal fossa-infratemporal fossa approach. A: Line drawing of anterior incision. Lazy "S" incision added if neck dissection is required. (From Donald PJ. Craniofacial surgery for head and neck cancer. In: Johnson JT, Blitzer A, Ossoff RH, Thomas JR, eds. *AAO-HNS instructional courses.* Vol. 2. St. Louis: CV Mosby, 1989:244, with permission.) B: Anterior incision in patient with recurrent deep lobe parotid carcinoma extending into the middle cranial fossa. C: Line drawing of posterior incision. D: Posterior incision in patient with glomus jugulare tumor with marked intracranial extension. Dotted line outlines mastoid periosteal flap for closure of the external auditory canal.

The scalp incision goes to the level of the pericranium. As the flap is developed, the temporalis muscle is identified {Fig. 8). The superficial and deep temporalis fascia are incised in a semilunar manner to include the frontal branch of the facial nerve, which emerges approximately 1.5 cm in front of the auricle and arches into the frontalis muscle approximately 2 to 2.5 cm above the brow (Fig. 9). This protects the nerve from injury.

The cervicofacial portion of the incision proceeds superficially to the platysma and superficial muscular aponeurotic system (SMAS) fascia in a plane similar to that in a superficial plane face lift. This is carried forward anteriorly to a point from the angle of the mandible to the lateral orbital rim (Fig. 10). When using this anterior incision, a decision whether to cut across the external auditory canal (EAC) is made, usually predicated on the necessity of exposing the ICA. The posterior incision always cuts across the canal because carotid exposure is usually necessary (Fig. 11).

External Auditory Canal Obliteration

In most instances of both the anterior and posterior incision, exposure of the petrous portion of the ICA is required. This is best facilitated by exposing and later obliterating the eustachian tube. A decision regarding elimination of the middle ear cleft and the EAC or preservation of a nonvenlilated middle ear cleft and the permanent instillation of a ventilating tube is often difficult. For ease of management and decreased frequency of complications, there is little question that obliteration is the treatment of choice. In those patients desiring hearing preservation and in young patients, maintenance of the integrity of the middle ear and EAC and the use of a ventilating lube is preferable.

If the EAC is to be obliterated, it is best done at this juncture. The obliteration technique described by Fisch is easy to perform with predictable results, and is illustrated in Fig. 12. This is certainly the preferable technique in nasopharyngeal carcinoma or in patients who are failures of prior radiation therapy.

Internal Carotid Artery and Internal Jugular Vein Exposure

Attention is now turned to the neck where the internal jugular vein (1JV) and ICA are identified and dissected superiorly as close as possible to the skull base foramina through which they pass. Care is taken to avoid damage to cranial nerves IX through XT1 during the dissection. Soft rubber catheters are placed around these vessels for later control of bleeding, if necessary (see Fig. 3, Chapter 29). The upper end of this dissection may need to be postponed until the mandibular condylectomy is done. Eventually the ICA needs to be exposed to visualize the fibrous ring and the entrance of the artery into the skull at the carotid foramen (Fig. 13). Similarly, the IJV is dissected to the jugular foramen.

Temporalis Elevation

The temporalis muscle body is exposed in its entirety. In over half the cases, it serves as the major reconstructive flap that separates the middle cranial fossa from the upper aerodigestive tract. Maintaining its viability is essential, andinte-



FIG. 8. Temporalis muscle. Note the large, fan-shaped configuration of the muscle, with the bulk of its insertion being on the coronoid process. (From Goss CM. *Gray's anatomy.* 29th American ed. Malvern, PA: Lea & Febiger, 1973, Figure 6.5, with permission.)



FIG. 9. Incision of temporalis fascia to include the frontal branch of the facial nerve, precluding it from injury. (From Donald PJ. Skull base surgery for sinus neoplasms. In: Donald PJ, Gluckman JL, Rice DH, eds. *The sinuses.* New York: Raven Press, 1995:479.)

gral to that is an understanding of its blood supply. The superior supply from the superficial temporal artery and branches of the postauricular artery is unavoidably eliminated during the muscle elevation. The integrity of the inferior supply through the deep temporal branches is assiduously maintained. These deep branches emerge from the internal maxillary artery both directly posteriorly and anteriorly to the foramen ovale (Fig. 14). The posterior artery exits the internal maxillary just anterior to this artery's emergence from under the neck of the mandible. The anterior deep temporal leaves the internal maxillary just before its disappearance into the pterygomaxillary fissure. In an attempt to achieve hemostasis of the prolific bleeding often en-

продолжение

countered from the pterygoid plexus of veins, indiscriminate cautery in this area may compromise the anterior deep temporal artery. The use of bipolar cautery is advised.

The temporalis muscle is elevated in its entirety, usually with a 2-cm cuff of pericranium. Careful elevation with a broad, flat elevator like the von Langenbeck helps to maintain the integrity of the muscle (Figs. 9, 15). The muscle is elevated along the calvarium as it curves from a vertical to an oblique plane. Further dissection, and thus exposure of the deep inferior part of the infratemporal fossa, is impeded by the presence of the zygomatic arch.

In highly invasive tumors, infiltration of the temporalis muscle may be observed at this point (Fig. 16). The muscle

продолжение



FIG. 36. Internal carotid artery (ICA) replaced with saphenous vein. A: Vein graft being sewn in place. B: Flow in graft restores continuity of ICA flow.

ensured. Total mobilization of the artery from the cervical part to the cavernous portion facilitates this. Once both anastomoses are completed, the clamps are removed, the leaks oversewn, and Gelfoam patches soaked in thrombin are placed around the suture lines.

Cavernous Sinus

The cavernous sinus resection often precedes the management of the carotid. The artery is freed from its canal, and if tumor persists beyond the petrous part, the cavernous sinus is resected. Small outpouchings of the sinus (see Figs. 10 and 24. Chapter 4) project along the three branches of the trigem-inal nerve as they enter their foramina. In addition, there are a myriad of connections to other veins and dural sinuses. Minimal invasion at these sites can limit the amount of the sinus removed. Frozen-section examination of these margins is critical.

Major invasion of the sinus (Fig. 37) tends to compress the venous structures within, and dissection proceeds rather easily until the invasive edge is reached. The profuse hemor-ifaage characteristic of this structure is then encountered. Not only must the soft tissue component of the sinus be removed, but the adjacent bone as well.

Cavernous dissection is done under the operating microscope in a slow and methodical manner. Because of its propensity for brisk hemorrhage, it must be removed piecemeal. Once the relatively avascular areas of frank tumor involvement are passed, the sinus that still possesses microscopic residua is systematically removed. Bleeding is often profuse and troublesome. A small area of sinus is cleared, thrombin-soaked Gelfoam pledgets are placed and held over that area with a cottonoid, and the adjacent area of the sinus then removed. Liberal use of the bipolar cautery and hemostatic gauze aids in hemorrhage control. Each grossly normal piece of tissue removed is submitted for frozen-section analysis. In this way, little by little, the entire cavernous sinus is removed. With major involvement of the sinus, the carotid will need removal in most cases. The lateral wall of the sphenoid sinus, a portion of the middle fossa floor, a portion of



FIG. 37. Cavernous sinus *(arrow)* full of nasopharyngeal carcinoma.

the petrous tip, and, at times, the bone surrounding the superior orbital fissure are removed. Hemostasis is required at the basilar plexus, the superior petrosal sinus, the circular sinus, ophthalmic veins, and the vein of Vesalius. In addition, two or more cerebral veins enter the sinus as well and may require control.

Dura and Brain Resection

Dural invasion varies from minimal involvement at the neural and vascular foramina at the sites of entry into the intracranial space, to widespread involvement characteristic of recurrent tumors after full-course radiation therapy. Sometimes the dura is replaced almost entirely by tumor tissue. The pushing nature of the upper aerodigestive tract tumors has been fully discussed in Chapter 4. A cuff of 5 to 10 mm of grossly healthy dura is excised and the periphery examined by frozen-section analysis. Often grossly normal dura has tumor extensions and requires further resection as dictated by the pathologist'^ report.

Certain limitations to resection are imposed by vital central structures and the restrictions of certain reconstructive


Superior anastomotic vein (Trolard)
Superior sagittal sinus
Inferior anastomotic vein (Labbé)
Tranverse sinus
Superficial middle cerebral vein
A



FIG. 38. A: The inferior anastomotic vein of Labbe draining into the sigmoid sinus. B: The vein of Labbe, seen in a patient with a dural tear.

options. In the middle fossa, the two major structures that impede further dural excision are the vein of Labbe and the superior sagittal sinus. The vein of Labbe, or interior anastomotic cerebral vein, drains into the lateral sinus at a variable distance from the sigmoid sinus (Fig. 38). If the superior anastomotic vein of Trolard is not patent or is of small caliber, the vein of Labbe will be the only vein draining the entire ipsilateral cerebral hemisphere. To sacrifice it would th.en result in a massive infarction and often death. Cerebral venography may establish the venous drainage pattern in those patients in whom the vein of Labbe is in jeopardy.

The superior sagittal sinus can usually be safely obliterated in the anterior fossa from the anterior fossa floor up to the coronal suture. The middle fossa component cannot be ligated because in most instances it will lead to quadriplegia and often death. Fortunately, few skull base tumors extend that far (Fig. 39).

The second dural restriction concerns the potential for dural reconstruction and the provision of a watertight seal. As dural resection along the clivus and under the brainstem increases in extent, there is a progressive increase in difficulty in obtaining a sound dural closure. A cerebrospinal fluid (CSF) leak at this site is an open avenue to the nasopharynx, .which possesses one of the highest concentrations of pathogenic bacteria in the entire upper aerodigestive tract (5.6). Tissue glue helps, but a suture line is superior in strength. For most fibrin glues, the adhesive strength is lost in about 1 week.

Brain resection is controversial. Much of the reluctance is a reflection of the neurosurgical experience with primary brain tumors. Most of these lesions are multifocal in characjer. with a large primary site and multiple satellite lesions in discontinuity. A sufficient margin of healthy, uninvolved tissue that skirts all areas of tumor involvement is often not feasible without engendering serious neurologic side effects. As detailed in Chapter 4. upper aerodigestive tract carcinomas have a more pushing type of edge and can be encompassed by a narrower resection margin.



FIG. 39. Adenoid cystic carcinoma with extensive spread in dura close to the superior sagittal sinus *(arrow).*

Silent areas of the brain such as the frontal lobes and the anterior part of the temporal lobes can be sacrificed with impunity. As the more posterior aspect of the temporal lobe is reached, especially on the dominant side, speech disturbance may be encountered. As seen in Chapter 4, local control can be achieved with brain resection in a high percentage of patients. Meningeal carcinomatosis in the author's experience is a distinctly rare event, having been seen in only two cases.

Reconstruction

The key procedure in the reconstruction is to separate the intracranial cavity from the upper aerodigestive tract with a watertight seal whenever possible. Infection will not only produce meningitis or, worse, an abscess, but may cause spontaneous rupture of the 1C A. An arterial graft is particularly vulnerable to such exposure. Fascia lata, temporalis fascia, or allograft is used to patch resected dura (Fig. 40). Careful suturing, especially on the inferior aspects above the clivus, is essential. The closure may be augmented with tissue glue.

The next layer comprises muscle. The temporalis muscle, if preserved, is placed under and across the craniotomy site. The pericranial cuff is sutured to the basipharyngeal fascia of the nasopharynx (Fig. 41). In this way, the potential dead space left by resected soft tissues under the sphenoid bone



FIG. 40. Dura of temporal lobe patched with lyophilized dura.



FIG. 41. A: Temporalis muscle flap. B: The temporalis muscle is placed across the craniotomy defect below the middle fossa floor and into the nasopharynx. C: Craniotomy flap restored and muscle flap turned in. D: Coronal view showing suture of pericranial attachment of the temporal muscle to the basipharyngeal fascia. (From Donald PJ. Skull base surgery for sinus neoplasms. In: Donald PJ, GJucK-man JL, Rice DH, eds. *The sinuses.* New York: Raven Press, 1995:487.)

can be obliterated. The integrity of the muscle is carefully ensured before this step.

Other myogenous or niusculocutaneous flaps can be alternatively used if the temporalis flap has questionable viability. The sternocleidomastoid muscle has been used when die resection has not progressed too far medially from the foramen ovale. It is too short to reach the nasopharynx. Its blood supply from the occipital artery should be preserved. A cuff of clavicular periosteum helps hold the sutures.

The posterior trapezius flap has been well described by Nettcrville and Jackson (see Chapter 32) and provides excellent muscle bulk and cutaneous cover when skin involvement requires wide excision. The drawback lies in the repositioning of the patient that is needed during this phase of the operation. The pectoralis major musculocutaneous flap produces satisfactory reconstruction, especially if there is extensive pharyngeal resection or cutaneous loss (Fig. 42). The patient's upper torso and neck length must, however, be compatible so that there is sufficient flap length to allow a tension-free closure. The muscle bulk of both this and the trapezius flap amply efface the subcranial deficit. Unfortunately, flap length has often been a problem.

The most utilitarian flap is the rectus abdominis myogenous free flap, which can bring skin if required (Fig. 43). Bringing fresh vascularized tissue into the wound greatly enhances healing. Although there is often a resulting facial asymmetry created by the muscle bulk and the skin paddle that is commonly brought up as an indicator of flap viability, this can be revised at a later date, producing a fine cosmetic result (Fig. 44). The flap is usually pedicled on the deep inferior epigastric artery and vein and is sewn into the external carotid artery and IJV. The donor site is reinforced with Marlex mesh when below the arcuate line. The anterior rectus sheath remnants are approximated when possible, and the skin usually closed primarily. The flap is inset so that the muscle extends into the resected nasopharynx, and secured as well as possible to the pharyngobasilar fascia. The vital point is to ensure thai: an adequate paddle of soft tissue is interposed between the dural repair, the exposed ICA, and the upper aerodigestive tract. Sometimes, the skin paddle is required to line the pharynx when it is extensively resected. Whenever possible, muscle is carried superiorly into the infralemporal fossa to aid in ablating the cosmetic defect caused by the absence or atrophy of the temporalis muscle.



FIG. 42. Pectoralis major musculocutaneous flap used to reconstruct infratemporal fossa and undersurface of the middle fossa. A large skin paddle was required to reconstruct the pharynx from the nasopharynx to the vallecula.



FIG. 43. Rectus abdominis flap being elevated.

The skin paddle is checked frequently in the first 36 hours for viability and the pedicle monitored with Doppler ultrasonography. This is a vigorous flap that usually has excellent vessels of large caliber; flap failure is rare.

The zygoma and the craniotomy bone flaps are returned and secured with miniplates (Fig. 45). The inferior aspect of the L-shaped craniotomy flap is often partially missing because of bone erosion by tumor and subsequent osseous resection to ensure tumor-free margins. The muscle flap fills in the dead space and adds support.

Skin closure is then done and the wound drained with a closed system of suction drainage. Careful attention is paid to removing all eustachian tube remnants before wound closure. If the middle ear space is to be maintained, a ventilating tube is placed. If the ear is to be ablated, all middle ear mucosa and ossicles are removed as well as the tympanic membrane and residual canal skin. A mastoidectomy is done if not already performed, with the usual precautions taken to protect the facial nerve.

The lumbar drain is usually discontinued at about 72 hours unless a CSF leak occurs. If a leak does not stop in 3 days, the patient is returned to the operating room for repair. Antibiotic prophylaxis is continued for 24 hours after surgery, then discontinued. Suction drains are removed once the output is below 20 ml daily. Wounds are dressed with antibiotic ointment daily. The tracheostomy and nasogastric tube are discontinued as soon as airway jeopardy has passed and oral alimentation can ensue.



FIG. 44. **A,B:** Patient, 1 year after infratemporal fossa-middle cranial fossa resection and reconstruction with a rectus abdominis flap. The skin monitor has been removed and the scar revised in a manner similar to rhytidectomy.



FIG. 45. Zygoma and craniotomy flaps restored and fixed in place with miniplates. (From Donald PJ, Gluckman JL, Rice DH, eds. *The sinuses.* New York: Raven Press, 1995:487.)

I

CONCLUSIONS

The middle cranial fossa-infratemporal fossa procedure is a somewhat complex and elaborate operation. In the author's opinion, it provides the best exposure to the middle fossa floor and contents. Carotid and cavernous exposure is optimized and subcranial resection can extend from the posterior ethmoids to C2 and include all the subcranial soft tissues, including those adjacent to the posterior maxillary wall and the posterior aspect of the maxillary sinus itself.

Two-year tumor-free survival rates are approximately 40%. The complications regarding carotid artery resection and the cavernous sinus have been described. CSF leaks are uncommon; meningitis and epidural and brain abscesses are rarer still. (See Chapter 29 for a complete discussion.)

REFERENCES

1. Fisch U. Infratemporal fossa approach for extensive tumors of the temporal bone and base of the skull. In: Silverstein H, Horell H, eds. *Neurological surgery of the ear*. Birmingham: Aesculapius, 1997:34-53.
2. Schramm VL. Infratemporal fossa surgery. In: Sekhar LN, Schramm VL, eds. *Tumors of the cranial base: diagnosis and treatment.* Mount Kisco, NY: Futura Publishing Co., 1987:421-«7.
3. Nyak UK, Donald PJ, Stevens D. Internal carotid artery resection for invasion of malignant tumors. *Archives of Otolaryngology* 1995; 121:1029-1033.
4. Biller HF, Urken M, Lawson W, Halimov M. Carotid artery resection and bypass for neck carcinoma. *Laryngoscope* 1988;98:181-183.
5. Rice DH. Microbiology. In: Donald PJ, Gluckman JL, Rice DH, eds. *The sinuses.* New York: Raven Press, 1995:57-64.
6. Tierno PM. Microbiology of the nose and paranasal sinuses. In: Goldman JL, ed. *Rhinology.* New York: John Wiley & Sons, 1987:79-97.

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 17

Transmandibular Approach

1

Jack L. Gluckman, Lyon L. Gleich, and Keith M. Wilson

Access to large tumors involving the middle compartment of the extracranial skull base, particularly if there is lateral extension into the infratemporal fossa and parapharyngeal space, can be difficult. The transmandibular-transcervical approach permits not only wide exposure of this area but control of the great vessels that traverse this region.

The key to this technique is the mandibular osteotomy and lateral swing of the mandibular segments, which has been used by head and neck cancer surgeons for many years. It was first described in 1936 by Roux and then modified and refined over the years (1,2) to the point that it is now a standard component of the surgical armamentarium for cancers of the oral cavity and pharynx. This evolution has been facilitated by newer techniques of mandible stabilization, particularly the use of plates, which have minimized the morbidity and particularly the nonhealing originally associated with this technique.

In 1981, Biller et al. (3) first described this approach for wide-field exposure of the anterior skull base and infratemporal fossa. This technique, which included a median labiomandibulotomy with "mandibular swing" and detachment of the pharynx from the skull base by dividing the eustachian tube, resulted in excellent exposure and great safety, and since that time has been embraced by many skull base surgeons. In the authors' institution, it remains a commonly performed approach for large anterior skull base tumors with lateral infratemporal fossa extension.

RATIONALE

»

The extracranial skull base can best be regarded as consisting of a midline compartment and two lateral compartments separated by the internal carotid arteries (4) (Fig. 1). The lateral compartments consist of the greater wing of the sphenoid and the petrous portion of the temporal bone. The middle compartment consists of the body of the sphenoid, clivus, and occipital condyles. Although many approaches are available to the middle compartment, they are limited in their ability to attain lateral exposure and safe control of the great vessels. Likewise, the lateral approaches to the lateral compartments are limited in their inferior and medial exposure.

The transmandibular approach provides an excellent wide-field exposure to this area with easy identification and control of the great vessels and cranial nerves. Its major indication is in large tumors involving both the middle and lateral compartments.

The exposure that is achieved with the transmandibular approach extends from the ipsilateral infratemporal fossa to the contralateral medial pterygoid plate, and from the anterior cranial fossa to the lower clivus and anterior cervical spine down to C7.

INDICATIONS

Tumors arising in the midline from the sphenoid, clivus, anterior foramen magnum, and upper cervical vertebra with extension into the lateral compartment; tumors arising in the lateral compartment (i.e., lesions of the infratemporal fossa, inferior surface of the temporal bone, and pterygomaxillary fossa), as well as parapharyngeal space tumors can all be easily accessed using the transmandibular approach (3,5-7).

Which tumors are amenable to wide-field craniofacial resection is the subject of some debate; suffice to say that the high-grade carcinomas and sarcomas with extensive skull base invasion probably should not be subjected to this type of surgery except under certain circumstances, but many low-grade malignant and benign tumors can be completely resected by this technique. In addition, other conditions, such as invagination of the odontoid process, internal carotid artery aneurysm, and foreign bodies, can be approached this way.

J. L. Gluckman, L. L. Gleich, K. M. Wilson: Department of Otolaryngology-Head and Neck Surgery, University of Cincinnati, Cincinnati, Ohio 45267.



FIG. 1. The compartments of the extracranial surface of the skull base separated by the internal carotid arteries.

PREOPERATIVE EVALUATION

Evaluation of the Tumor

The preoperative evaluation depends on the individual patient and usually includes full clinical examination, computed tomography scan, magnetic resonance imaging, and biopsy. If the possibility exists for carotid artery resection or resection of the cavernous sinus, the cerebral blood flow should be assessed by arteriography, and balloon occlusion performed if deemed necessary.

Evaluation of the Mandible

The status of the patient's dentition should be carefully assessed because this may determine the site and type of the osteotomy (i.e., which toolh to extract, and whether the teeth can be used for fixation), In older patients, the degree of atrophy of the mandible may also dictate the type of osteotomy and the plating configuration to be used for fixation.

Evaluation of the Patient

As in all surgery, the patient's general physical and mental health must be evaluated before undertaking any procedure. Informed consent should be obtained, including all risks and realistic expectations of success. This should include the risks of bleeding, injury to cranial nerves, and impaired healing at the osteotomy site.

TECHNIQUE

Depending on the type and extent of the tumor, the craniotomy is usually performed first to ensure rescctability. Once it is deemed appropriate to proceed with the transmandibular-transcervical approach, a tracheostomy is performed.

Labiomandibulotomy

A curvilinear incision is made from the mastoid lip to the submental region, passing two fingerbreadths below the mandible. The incision should extend through the platysma and fascia overlying the submandibular gland and the superior flap elevated in this plane to protect the marginal mandibular nerve. The lip-splitting incision can be made vertically through the midline or curved around the ipsilateral mental crease, which is the authors' technique of choice (**Pig.** 2).

The sternocleidomastoid muscle is then retracted laterally and the carotid sheath and its contents identified. Vascular loops are loosely placed around the common and internal



FIG. 2. Cervical and lip-splitting skin incision options.

carotid arteries as well as the jugular vein to facilitate control of these vessels if this should become necessary. Care is taken to expose and protect the vagus, spinal accessory, and hypoglossal nerves.

The lip-splitting incision is completed and the mandibular periosteum is incised anterior to the mental foramen. The periosteum is elevated anteriorly and posteriorly, ensuring that the mental nerve is not compromised (Fig. 3). A decision now has to be made as to the optimal site and configuration of the osteotomy. The state of dentition and the amount of mandibular atrophy govern this decision.



FIG. 3. Exposure of the potential osteotomy site with preservation of the mental nerve.

The mandibulotomy may be performed in a stair-step or notched fashion to increase postoperative stability; however, with newer plating techniques, a straight vertical midline osteotomy probably yields comparable stability (8) (Fig. 4). The optimal site for the osteotomy is anterior to the mental foramen up to and including the midline. If the patient has dentition, it is possible to create the osteotomy directly between two teeth; however, it is the authors' opinion that it is best to remove a tooth (usually the lateral incisor or canine) at the osteotomy site, rather than risking losing both teeth on either side of the osteotomy. If possible, the osteotomy should be made at the site of a previous extraction. Once the configuration and site of the osteotomy have been decided, the plates are chosen and placed, and holes drilled. The bone cut is made with an oscillating saw and fine chisel.

At this stage, a mucosal incision is made in the lateral floor of the mouth extending posteriorly toward the anterior tonsillar pillar. It is important to preserve a cuff of mticosa on the alveolar ridge to permit a watertight closure when the incision is closed (Fig. 5). The mandible is now swung laterally by dividing the mylohyoid and digastric muscles. The mucosal incision is then progressively extended along the anterior pillar until adequate exposure is obtained. The pterygoid muscles may need to be divided to obtain adequate visualization of the infratemporal fossa. Note that the floor of mouth mucosal incision is lateral to the submandibular duct and gland, which arc kept intact.

Skull Base Exposure

As the mandible is retracted, the parapharyngeal space comes into view. The styloid process is fractured at its base and removed. The internal carotid artery, internal jugular



FIG. 4, Types of osteotomies. A: Vertical. B: Stair-step. C: Notched.

vein, and vagus, spinal accessory, hypoglossal, and glossopharyngeal nerves are then traced superiorly to the skull base.

As the dissection continues superiorly, the pharynx is noted to be tethered by the cartilaginous eustachian tube and levator veil palatini and tensor veli palatini muscles. These structures can then be divided if necessary, with care taken to protect the internal carotid artery. The pharynx can then be rotated medially, exposing the midline compartment of the skull base (Fig. 6).

The approach can be extended to expose the posterior nasal cavity by removing the pterygoid plates and posterior hard palate and incising into the posterior nasal mucosa. Removal of the maxillary tubcrosily facilitates exposure of the pterygopalatine fossa. The sphenoid and maxillary sinuses can also be exposed by this approach, and of course various maxillotomy and maxillectomy procedures can be combined with this approach.

The craniofacial resection of the tumor is then accomplished. The intrapetrous internal carotid artery may be completely exposed in its vertical and horizontal segments. Although portions of the skull base can be removed piecemeal from below, usually the entire thickness of bone is removed with a combined craniofacial resection.



FIG. 5. Release incision through the mucosa of the floor of mouth.

Closure

The age-old axiom that the key to successful craniofacial surgery is successful closure, certainly holds true in this technique.

If a significant skull base defect has been created, then this has to be meticulously reconstructed. Dura should be reconstructed and then various muscle flaps, either pericranial or temporalis, used to reinforce this. If the defect is large, a free rectus abdominis flap may be necessary. The authors rarely replace the resected bone.

If a significant pharyngeal wall defect results, it is reconstructed using a pectoralis major myocutaneous flap or cutaneous free flap, depending on the size and site of the defect.

The superior constrictor muscle is then reattached to the base of the skull and the pharynx sutured to the preverlebral fascia. When closing the floor of mouth incision, it is important to suture the floor of mouth mucosa not only to the cuff of the alveolar ridge mucosa, but to the alveolar ridge periosteum to prevent dehiscence. The mandible is then reap-



FIG. 6. Exposure of the infratemporal fossa and parapharyngeal space, together with midline compartment after retraction of the pharynx.

proximated using the previously fitted plates. In general, the authors do not put the patient into intermaxillary fixation.

A dermal graft may be placed for carotid protection and the neck incisions closed in layers. The lip is re approximated by first reattaching the orbicularis oris by means of a permanent suture (e.g.. 3.0 nylon) and then realigning the vermilion border accurately. The tracheosLomy tube is maintained until the patient clearly has a safe airway. A nasogastric tube is maintained until the patient can tolerate an oral diet: if multiple cranial nerve palsies have occurred, placement of a caslrostomy should be considered.

COMPLICATIONS

Serous Otitis

This results if the eustachian tube has been transected; a long-term tympanostomy tube is needed for relief of this problem.

Cerebrospinal Fluid Leak, Intracranial Infection, and Pneumoeephalus

As in all craniofacial resections, inadequate reconstruction can result in intracranial infection, cerebrospinal fluid leak, and even the development of pneLimocephalus. This procedure is no exception. Prevention is very important and consists of a meticulous, watertight closure. Most leaks settle spontaneously, but, if not already present, a lumbar drain will need to be inserted, and occasionally open exploration and direct closure are indicated.

Cranial Nerve Injury

Cranial nerves may be intentionally sacrificed or inadvertently injured during the tumor resection. Of these, vagal injury with secondary dysphonia and dysphagia with aspiration is the most devastating. Although some suggest that prophylactic vocal medialization should routinely be performed (9), the authors usually do not perform this but rather give the patient a trial of swallowing. Older patients with multiple cranial nerve palsies usually require surgical intervention including gastrostomy, but the younger patients do quite well without surgery.

Temporomandibular Joint Dysfunction

Temporouiandibular joint dysfunction can result from excessive lateral traction during the mandibular swing. This is due to disruption of the joint ligaments and compression of the articular capsule. In addition, division of the muscles of mastication for exposure can result in functional asymmetry and further malocclusion. aggravating the temporomandibu-lar joint dysfunction. Early initiation of range-of-motion exercises of the jaw may reduce joint fibrosis. Splints, dentures, bite blocks, and antiinflammatory agents may be used to reduce these symptoms (10-12). The prophylactic injection of intraarticular steroids seems to reduce this complication.

Complications

Healing of the mandible after osteotomy requires appropriate repair and fixation. Although most osteotomies heal well without any sequelae, malunion or nonunion can have devastating consequences. For this reason, the following steps should be taken:

1. Avoid excessive elevation of the mandibular periosteum at the osteotomy site, which may devascularize the osteotomy site.
2. Design the osteotomy with care. Stair-step and notched osteotomies result in improved contact surface and good alignment and stabilization. Vertical osteotomies result in less bone removal, but are associated with greater rotational forces from distractional influences (8,13,14). Tf a vertical osteotomy is used, intermaxillary fixation should perhaps be used. Although it is technically possible to perform the osteotomy between two teeth, it is probably safer to remove a tooth to avoid the potential for infection at the site (15).
3. Ensure adequate stabilization. Although both wires and plates have their proponents for optimal stabilization (16,17), most favor plating as the technique of choice (14). Tension bands can be placed in dentate patients for added fixation.

Improper stabilization can result in malpositioned segments and nonunion. If movement of the mandibular segments is detected early in the postoperative period, exploration and refixation should be performed (15). Although malpositioned segments may not result in major problems in the edentulous patient because a denture can be fashioned to accommodate the malunion, in the dentulous patient the resulting malocclusion may cause pain at the osteotomy site and at the temporomandibular joint (10).

Rarely, osteomyelitis may develop at the osteotomy site, in which case necrotic tissue and nonviable bone should be debrided, antibiotics commenced, and external fixation applied. After the infection is controlled, bone grafting is indicated. Hyperbaric oxygen may aid healing in these patients.

In conclusion, the authors believe that the transmandibular-transcervical approach has an important role in contemporary skull base surgery, and should be included in the armamentarium of all who perform this surgery.

REFERENCES

1. Trotter W. Operations for malignant diseases of the pharynx. *Br J Surg* 1929:16:485^195.
2. Spiro RH, Gerold FP, Strong EW. Mandibular "swing" approach for oral and oropharyngeal tumors. *Head and Neck Surgery* 1981:3:371-378.
3. Biller HF, Shugar JMA, Krespi YP. A new technique for wide-field exposure of the base of the skull. *Archives of Otolaryngology* 1981:107:698-702.
4. Som PM, Shugar JMA, Parisier SC. A clinical radiographic classification of skull base lesions. *Laryngoscope* 1979;89:1066-1076.
5. Krespi YP, Sisson GA. Transmandibular exposure of the skull base. *Am JSurg* 1984:148:534-538.
6. Yumoto E, Okamura H, Yanagihara N. Transmandibular transpterygoid approach to the nasopharynx, parapharyngeal space, and skull base. Ann *Otol Rhinol iMiyngol* 1992:101:383-389.
7. Franklin DJ, Moore GF, Fisch U. Jugular foramen peripheral nerve sheath tumors. *Laryngoscope* 1989;99:1081-1087.
8. McGregor IA, MacDonald DG. Mandibular osteotomy in the surgical approach to the oral cavity. *Head and Neck Surgery* 1983:5:457^62.
9. Netterville JL. Stone RE, Luken ES. Civantos FJ, Ossoff RH. Silastic medialization and arytenoid adduction: the Vanderbilt experience. *Ann Otol Rhinol Laryngol* 1993;102:413^24.
10. Sataloff RT, Myers DL, Roberts BR. Pain following surgery of the skull base. *Otolaryngol Clin North Am* 1984:17:613-625.
11. Niparko JK, Mattox DE. Complications of lateral skill base surgery. In: Eisele DW, ed. *Complications in head and neck surgery.* St. Louis: Mosby-Year Book, 1993:619-620.
12. Bell WE. *Temporomandibular disorders: classification, diagnosis, management.* 3rd ed. St. Louis: Mosby-Year Book, 1990.
13. Komisar A, Shapiro BM. Complications of midline mandibulotomy. *Ear Nose Throat.I* 1988:67:521-523.
14. Sullivan PK, Rabian R, Driscoll D. Mandibular osteotomies for tumor extirpation: the advantages of rigid fixation. *Laryngoscope* 1992:102:73-80.
15. Sessions RB, Hudkins C. Complications of surgery of the oral cavity. In: Eisele DW, ed. *Complications in head and neck surgery.* St. Louis: Mosby-Year Book, 1993:218-222.
16. Shah JP. Kumaraswamy SV, Kulkarni V. Comparative evaluation of fixation methods after mandibulotomy for oropharyngeal tumors. *Am J Surg* 1993:166:431-34.
17. McCann KJ, Irish JC, Gullane PJ. Complications associated with rigid fixation of mandibulotomies. *J Otolaryngol* 1994;23:210-215.

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 18

Anterior Subcranial (Transbasal—Derome) Approach

Ricardo Ramina, JoaoJ. Maniglia, Ari A. Pedrozo, and Murilo S. Meneses

Editor's Note: *The editor's treatment philosophy regarding the management of aggressive malignant tumors invading the intracranial space is at variance with the authors of this chapter. Combined chemotherapy and radiation therapy is usually met with failure when the cancer is this advanced. Aggressive resection of the cavernous sinus and excision of the petrous and cavernous carotid artery is done when these structures are invaded. The artery is replaced with a graft of Gore-tex or saphenous vein (see Chapter 16).* En bloc *resections of many skull base malignancies with significant central spread are usually impossible. A modified* en bloc *resection with frozen-section monitoring is a highly successful method of control (see Chapter 4) and is the editor's method of choice. The insurance of tumor-free margins is the goal— however achieved.*

Tumors of the anterior skull base frequently may involve the paranasal sinuses, orbit, and clivus. Surgical treatment of these lesions is often difficult and requires a multidisciplinary approach to achieve radical tumor removal and adequate reconstruction of the skull base. These tumors are located in a "frontier region," involving extracranial and intracranial structures. When they are treated independently by ear-nose-throat, head and neck surgeons, neurosurgeons, and ophthalmologists, only incomplete tumor removal or a biopsy is most frequently achieved. Multidisciplinary treatment by a skull base team, however, gives the best chance for total removal of the lesion, preservation of important neurovascular structures, and reconstruction of the skull base. Choosing the correct surgical approach is one of the most important ways of achieving the best result.

The transbasal approach was initially developed by Tessier et al. (1) in 1960 for treatment of craniofacial abnormalities. In 1963, Ketchman et al. (2) described a combined intracranial and extracranial approach to the anterior skull base for the treatment of malignant tumors. Derome (3,4) modified and used it for surgical removal of tumors of the anterior and middle skull base. Several modifications have been introduced, and many denominations, such as frontobasal, subcranial, transbasal, craniofacial, and others have been used (5-9). Since these early reports, several authors have extended the indications and modified this surgical approach (8-13). This procedure has become the approach of choice for tumors involving the craniofacial region, and can be extradural, intradural, or combined (14).

The major advantages of this procedure are wide exposure of the anterior cranial base with minimal retraction of the brain, and the possibility of reconstructing the whole anterior skull base with a galea-periosteum flap and bone, which provides an excellent cosmetic result with no visible skin scar. The main disadvantage of this approach can be loss of olfaction (15), which is seen with large lesions that require bilateral olfactory denervation. In small and more laterally situated lesions, it may be possible to preserve at least one olfactory nerve. The possibility of creating a communication between the intradural space and the paranasal sinuses is the most dangerous complication. Meningoceles or encephalo-celes with brain herniation may develop if the skull base is not adequately reconstructed.

INDICATIONS AND CONTRAINDICATIONS

The indications for this surgery are very broad and include congenital abnormalities, traumatic lesions, CSF fistulas, infection, some vascular lesions, and tumors (9,11,16-18). Lesions of the midline that involve the paranasal sinuses, orbit, anterior portion of the clivus, anterior cranial fossa, and sellar and suprasellar regions can be surgically treated using this procedure. This approach permits wide exposure from

R. Ramina, A. A. Pedrozo, M. S. Meneses: Skull Base Surgery Foundation, Curitiba 80240, Brazil.

J.J. Maniglia: Department of Otolaryngology, Universidade Federal do Parana, Curitiba, Parana 80440-080, Brazil.

the frontal sinus down to the foramen magnum/Cl region (4,14). Lesions extending lateral to the internal carotid artery, cavernous sinus, petroclival region, and the posterior inferior portion of the clivus can be removed by a combined approach in the same or a second operative procedure (9,11,14).

The rumors can be benign or malignant. Another group comprises the very large (usually recurrent) benign lesions and the slow-growing malignancies. For benign tumors, radical piecemeal or *en bloc* resection with maximal preservation of nerves and vessels is the goal of surgery. With malignant processes, the lesion has to be removed *en bloc,* with a safety margin of healthy tissue. A major surgical procedure is justified in these cases only if total removal of the lesion can be anticipated with acceptable morbidity.

Invasion of the cavernous sinus or the internal carotid artery by high-grade malignant tumors usually is a contraindication to surgery. Pallialive surgery may be indicated in cases of large, recurrent, benign tumors and slow-growing malignant lesions. Sacrifice of one infiltrated, but functioning, optic nerve or internal carotid artery is justified only if radical removal of the lesion can **be** achieved.

SURGICAL CONSIDERATIONS AND OPERATIVE TECHNIQUE

Surgical Considerations

The *extradural* subcranial approach is used for extradural tumors such as osteomas, fibrous dysplasia, chordomas, and chondrosarcomas, malignant tumors of the paranasal sinuses, traumatic lesions, CSF fistula, infections, and congenital abnormalities. Small dural lacerations (traumatic lesions) are repaired through this procedure.

The *inlmduml* subcranial approach is indicated when the lesion remains solely intradural. The indications include craniopharyngiomas, large pituitary adenomas, olfactory groove and tuberculum sellae meningiomas, and others.

The *combined* subcranial approach is used when the tumor invades the skull base dura and bone and its removal establishes a communication between die intradural space and the paranasal sinuses. Eslhesioneuroblastomas, invasive meningiomas, and malignant processes are examples of tumors that may require this approach.

Operative Technique

The Approach

General anesthesia with oral endotracheal intubation is used in all patients. Tracheostomy is rarely used. The oral cavity is packed with gauze. Both the face and the head are prepared with povidone-iodine solution. Antibiotic therapy, beginning the night before, is routinely used and continued for 3 days after the surgery. The patient is placed in the dorsal decubitus position with the neck extended, and the head secured in a head holder above heart level. A bicoronal incision is made beginning anterior to the tragus at the level of the zygoma. The skin flap is dissected in the subperiosteal plane and turned down anteriorly at level of the orbital rims and glabella, The galea and periosteum are incised at a level higher than the skin incision to obtain a very long flap. The supraorbilal foramen is identified, and the supraorbital nerve and artery are preserved (Fig. 1). This foramen is frequently incomplete, and the nerve and artery are dissected free with the pericranium. Sometimes the foramen is opened using a small osteotome and the neurovascular pedicle released with the bicoronal flap.

A large galea-periosteum flap that includes a small portion of the anterior temporalis fascia is dissected, remaining attached to the supraorbital region. It is used to cover the floor of the anterior fossa, me paranasal sinuses, and orbits to reconstruct the dura at the end of the operation. This flap is a modification of the traditional galea-periosteum flap because it includes the temporalis fascia. This large, vascular-ized flap is very useful for covering the whole anterior cranial fossa and supports the bone fragments used for reconstruction of the surgical defect in the anterior fossa (Fig. 2).

A bicoronal craniotomy is carried out; the frontal bone includes both orbital rims and a large portion of the orbital roof on both sides. Three bur holes are drilled: two holes are placed in the "key point" (after coagulating and dissecting a small portion of the lemporalis muscle), 1 cm below the superior temporal line, in the temporal fossa, behind the lateral orbital rim. The third bur hole is placed over the sagittal sinus approximately 6 cm from the nasion. A bur hole over the frontal sinus is avoided by cutting the bone in the region of the glabella with a small cutting bur or an oscillating saw (Fig. 3). The bur holes are connected using the Gigli saw or craniotome. The periorbita is bilaterally dissected from the orbital roof. The anterior two thirds of the orbital roof is cut using a small curved osteotome and high-speed drill. Both



FIG. 1. Cadaver specimen showing both supraorbital nerves *(arrows).*



FIG. 2. Modified galea-periosteum flap. The temporal fascia *(T.F.)* remains attached to the "classic flap" *(asterisks)* periorbita.

orbital roofs are connected with the opening in the nasion region using a high-speed drill. The bicoronal craniotomy bone is removed (Fig. 4). The frontal sinus mucosa is totally removed with a bur from its inner table. The frontal sinus is completely cranialized by removing the posterior wall of the sinus with rongeur and cutting burs. In cases in which the frontal sinus is infiltrated by the tumor. This portion of the lesion can be easily resected at this point. At this stage of the operation, surgical variations are performed according to the histologic type and extension of the lesion.

Extradural Approach

The basal dura mater is detached from the anterior cranial fossa floor and crista galli. One or two olfactory nerves are sectioned, depending on the lesion's extension. The dura over the lamina cribrosa, ethmoid roof, and orbit is elevated up to the planum sphenoidale and the anterior clinoid processes, exposing both optic nerves extradurally. The crista galli and the lamina cribrosa are removed using the high-speed drill and a fine leksell, If the lesion infiltrates the olfactory bulbs, they are resected intradurally. Possible dural lacerations during this dissection are sutured or grafted using temporalis fascia. Self-retaining retractors are positioned. This extradural approach completely exposes the anterior cranial base from orbit to orbit. It allows exposure of nasal septum, both nasal fossae, and the nasopharynx. Removal of the facial portion of the lesion is often possible without any





FIG. 3. Bicoronal craniotomy. The bone in the region of the glabella is cut with an oscillating saw *(arrows)*.

продолжение

FIG. 4. Craniotomy bone including both orbital rims and a portion of the orbital roof.

продолжение



FIG. 5. Exposure of the clinoid portion of the internal carotid artery and dural ring around the vessel *(asterisk)*. The anterior clinoid process was removed intradurally *(arrows)*. *ON*, optic nerve.

additional facial approach. The medial aspect of the orbit can be approached after removal of the lamina papyracea and ligature of the anterior and posterior ethmoid vessels. The optic nerve canal is identified and decompressed under the microscope using diamond burs and irrigation. The superior orbital fissure may be opened.

Both ethmoid sinuses can be totally removed, and the sphenoid sinus is exposed by resection of the planum sphenoidale. Tumors in the sphenoid sinus region and in the clivus (midline) are removed using this procedure.

Some lesions (e.g., adenoid cystic carcinoma) may extend into the middle fossa, following the second branch of the trigeminal nerve (V2) into the gasserian ganglion. Extradu-ral dissection of the floor of the middle fossa is carried out and the .second division of the trigeminal nerve (V2) identified. In some cases, a small temporal craniectomy may be necessary to expose the third division of the trigeminal nerve (V3) after coagulation and cutting of the middle meningeal artery. The superior orbital fissure and the clinoid portion of the internal carotid artery are identified by extradural dissection with removal of the lateral aspect of the greater sphenoid wing and intradural drilling of the anterior clinoid process (Fig. 5). This gives access to the cavernous sinus and in-fratemporal fossa.

The sphenoid sinus can be entered in two ways: through a midline approach after removal of planum sphenoidale. or laterally through the floor of the middle fossa between V2 and V3. The intcrsphenoid septum is resected with a rongeur, and tumor in the sphenoid sinus and lower clivus can be removed with microsurgical techniques. Some lesions, such as chondrosarcomas and chordomas, may extend down to the jugular foramen. The extradural portion of these tumors can be removed using this approach.

Case Reports

CASE1

A 9-year-old girl complained of visual loss in the right eye. Neurologic examination showed amaurosis on the right eye and visual decrease on the left. Atrophy of ihe right optic papilla was noted, Magnetic resonance imaging **(MRI)** demonstrated a very large cystic lesion in the sphenoid sinus and pituitary region (Fig. 6). On July 10, 1994, an exlradural subcranial approach was performed. A huge cystic mass was completely removed and the cranial base reconstructed. The postoperative visual acuity improved in the left eye. The right amaurosis remained unchanged.

Histologic examination of the specimen was diagnostic for aneurysmatic bone cyst. Follow-up examination 18 months after the surgery with computed tomography (CT) scan confirmed total removal of the lesion (Fig. 7). The visual acuity remained unchanged in the right eye.



FIG. 6. Case 1. Preoperative T1-weighted magnetic resonance image with gadolinium administration shows a large cystic lesion in the sphenoid region with extension and destruction of the clivus. No contrast enhancement was observed. The histologic diagnosis was aneurysmatic bone cyst.

CASE **1 (Continued)**



FIG. 7. Case 1. Postoperative computed tomography scan showing total removal of the aneurysmatic bone cyst in the sphenoid sinus/clivus region.

CASE 2

This 17-year-old boy presented with a progressive visual **loss** in :lie left eye over a period of 4 months. Visual acuity in the right .AC started to decrease, and 2 months before admission to the authors' clinic, he complained of loss of olfaclion. CT scanning re••calcd a very large tumor occupying the sphenoid and ethmoid si•uises, anterior portion of the clivus. and both orbits (Hig. 8). No Jural invasion could be demonstrated by CT.

In December. 1989, the lesion was completely removed through .;ii extradural subcranial approach. The medial orbital walls and ^rbital roofs were inlillraled by the lesion and were removed. The ..irbiial fissure and oplic canals were opened on both sides. After :^tal resection of the lesion, the anterior cranial base was reconstructed with a galea-pcriosteum flap (Figs. 9, 10). The histologic diagnosis was chondrosarcoma.

The patient underwent radiation therapy after the surgery, and a local frontal abscess developed secondary to a bony sequestrum. Fragments of bone used for reconstruction of Ihe fronlal sinus had to be removed and the infection was successfully treated with antibiotics. The bone used for reconstruction of the anterior fossa floor was covered by temporalis fascia, was not infected, and could be left in place. On follow-up examination and CT scan (Fig. 11} 6 years after surgery, there was no evidence of tumor recurrence and the patient had no additional neurologic deficit.



FIG. 8. Case 2. Preoperative computed tomography scan showing a large tumor in the ethmoid/sphenoid sinus region with extension to both orbits. Calcifications can be observed. The histologic diagnosis was chondrosarcoma.



FIG. 9. Case 2. Intraoperative photograph after total removal of a large chondrosarcoma showing the large defect in the anterior cranial base and both orbits *(O).*

CASE 2 (Continued)



FIG. 10. Case 2. Reconstruction of the anterior cranial base with vascularized galea-periosteum flap.



FIG. 11. Case 2. Postoperative computed tomography scan after total removal of chondrosarcoma showing the bone fragments used for reconstruction of the anterior cranial base.

Intradural Approach

The subcranial approach is also used for intradural tumors like pituitary adenomas, craniopharyngiomas, meningiomas. chordomas, chondrosarcomas, and others. In cases of severe craniofacial trauma with contusion or laceration of the frontal lobes, this procedure allows wide exposure for inspection of the intradural compartment and dural reconstruction.

After bilateral craniotomy involving both orbital rims and frontal sinus cranialization, dural incision is performed over the frontoorbital region and the superior sagittal sinus is double ligated and cut. Under the microscope, the anterior aspect of the sylvian fissure is opened to release CSF and reduce brain retraction. Both frontal lobes are elevated by gentle retraction, exposing the whole anterior fossa, the olfactory nerves, optic nerves, carotid arteries, and the pituitary region. In cases of sellar lesions (e.g., craniopharyngiomas, pituitary adenoma, and tuberculum sellae meningiomas). at least one olfactory nerve can be preserved,

Removal of the lesion in the sellar and parasellar region is possible after identification of the optic nerves and internal carotid arteries. An ultrasonic aspirator is used for the intracranial portion of the tumor. In some cases, such as in malignant lesions, the anterior portion of the cavernous sinus i^ invaded through the superior orbital fissure. This intracavernous portion of the tumor can be exposed and removed through this approach. The internal carotid artery is idenii-fied in the clinoid region by intradural removal of the anterior clinoid process after opening the superior orbital fissure. Resection of invaded internal carotid artery and nerves of the superior orbital fissure may be carried out in cases of malignancy. A preoperative balloon occlusion test is performed and, if necessary, a bypass between the petrous portion or cervical portion of the internal carotid artery and the middle cerebral artery (Ml and M2 segments) can be performed using a saphenous graft. In the authors' opinion, however, thi> procedure should be carried out only in cases of benign tumors or low-grade malignancies.

Case Reports

CASE 3

This is an example of an extradural subcranial approach combined with an intradural presigmoid access. A 42-year-old man presented with numbness around the mouth and cervical pain. CT scanning and MR1 showed a very large tumor in the clivus region, reaching the jugular foramen and extending into the sphenoid sinus. The lurnor caused compression of the brainstcm (Fig. 12).

On October 22. 1992, an extradural suhcrnnial approach was can-ied out (Figs. 13-15). Total removal of the extradural portion of the lesion was possible. The dura was infiltrated in the posterior clivus region, and no attempt was made to remove this part of the lesion because of danger of **CSF** fistula. Reconstruction was performed using galea-periosteuin flap, bone, and abdominal fat. The

CASE 3 (Continued)

remaining intradural portion was removed in a second stage using a presigmoid approach (Fig. 16). The histologic diagnosis was chordoma. In spite of radical removal and postoperative radiation therapy, the lesion recurred and **the** patient died *2.5* years after the operation.



FIG. 12. Case 3. Preoperative T1-weighted magnetic resonance image with gadolinium administration showing a large chordoma of the clivus compressing the brainstem (arrows). Minimal gadolinium enhancement is observed.



FIG. 13. Case 3. Intraoperative photograph showing extradural approach to the sphenoid sinus filled by the tumor (T). The intersphenoid septum is being removed with a Kerri-son rongeur. The planum sphenoidale was drilled out. O, orbit.



FIG. 14. Case 3. Intraoperative photograph after removal of the extradural portion of a clival chordoma that extended into the jugular foramen *(arrow). ON,* extradural exposure of both optic nerves.



FIG. 15. Case 3. Intraoperative radiograph showing the extradural subcranial approach from the frontal sinus, through the sphenoid sinus and reaching the jugular foramen.

CASE 3 (Continued)



FIG. 16. Case 3. Postoperative T1-weighted magnetic resonance image with gadolinium administration demonstrating total removal of the extradural portion of the lesion. The ethmoid and sphenoid sinuses are filled with abdominal fat. The intradural (retrosellar) portion of the lesion was removed in a second surgical procedure using a presigmoid approach.

CASE 4

This 6-year-old girl showed signs of hypopanpituitarism and progressive visual loss in both eyes. Neuroradiologic and endocrinologic evaluation revealed the presence of a very large tumor in the sellar region with compression of the brain-stem (Fig. 17). The diagnosis of a craniopharyngioma was suspected.

On August 20, 1992, an intradural subcranial approach was performed (Figs. 18, 19). Radical removal of the lesion was possible with preservation of the pituitary stalk (Fig. 20).

After surgery, the patient's vision improved markedly, and hormonal reposition with cortiron, tirotin, and growth hormone was initiated.



FIG. 17. Case 4. Preoperative T1-weighted magnetic resonance image with gadolinium administration showing a huge tumor in the sellar, suprasellar, and prepontine regions. The lesion had solid portions that enhanced with gadolinium, and cysts. The tumor extended from the sella up to the lateral ventricles. The histologic diagnosis was craniopharyngioma.

CASE 4 (Cuntiniwdl



FIG. 18. Case 4. Subcranial intradural exposure of a large craniopharyngioma (7) with preservation of both olfactory nerves *(stars).*



FIG. 19. Case 4. Intraoperative photograph. The craniopharyngioma was totally removed using a subcranial intradural approach. The optic chiasm (C) and the pituitary stalk *(asterisks)* were preserved.



FIG. **20.** Case 4. Postoperative T1 -weighted magnetic resonance image with gadolinium administration after total removal of a large craniopharyngioma. The optic chiasm *(arrow,* OC) and the pituitary stalk *(arrow, PS)* can be observed.

Combined Approach

If necessary, the authors use transfacial approaches in combination with the subcranial exposure to extend the operation to include access to the maxillary sinus, pterygopalatine fossa, intratemporal fossa, and middle cranial fossa. The authors prefer to use degloving techniques and transmaxillary access for benign tumors and slow-growing and low-grade malignant rumors. The Weber-Fergusson incision is used for more malignant lesions in which a radical operation is necessary (e.g., for total maxillectomy including orbital exenteration and reconstruction). In cases of esthesioneuroblastomas, the dura is opened for resection of the olfactory bulbs, with intraoperative frozen-section histologic studies obtained to ensure safe margins and removal of intradural tumor (19). Some aggressive meningiomas invade the floor of the anterior cranial base, the paranasal sinuses, and the intradural compartment. Removal of the lower part (maxillary sinuses) of these lesions requires transfacial approaches. Aggressive pituitary adenomas may infiltrate the ethmoid and the sphenoid sinuses. In these cases, a combined subcranial-transfacial approach is also used. Reconstruction of dura and cranial base is one of the most important steps of this approach. Communication of the intradural compartment with the paranasal sinuses may cause CSF fistula and meningitis.

Case Report

CASES

This 42-year-old man presented with bleeding from the nose. Rhinoscopy and CT scan (Fig. 21) revealed a large tumor occupying the nasal fossa with infiltration of the right nrhit and anterior cranial base. A biopsy was taken and an csthesioneuroblastoma was diagnosed.

In November 1988. a combined (rontobasal/degloving approach was performed and the lesion completely removed (Figs. 22, 23}. Radiation therapy was administered after the operation. The patient had no additional neurologic deficit or signs of recurrence in the control MRI examination 7 years after surgery (Fig. 24J.



FIG. 21. Case 5. Coronal computed tomography **scan** with contrast enhancement showing a tumor in the nasal fossa, sphenoid sinus, and right orbit. The histologic diagnosis was esthesioneuroblastoma.



FIG. 22. Case 5. Intraoperative photograph showing total removal of the lesion using a combined subcranial/degloving approach. O, orbit; *N*, nasopharynx.



FIG. 23. Case 5. Surgical specimen of both resected olfactory nerves and bulbs. Both nerves were infiltrated **by the** tumor.



FIG. 24. Case 5. Postoperative computed tomography scan after **radical** removal of esthesioneuroblastoma. The anterior cranial base was reconstructed with bone fragments.

Reconstruction

Reconstruction of the large defect in the frontobasal approach is of paramount importance. The dura is sutured primarily whenever possible, or a temporalis fascia graft is used. The modified pedicled galea-pericranium flap is then rotated to cover the whole anterior fossa. Reconstruction of large bone defects of the anterior fossa is necessary in the authors' experience because of the resulting dead space and to avoid delayed meningoceles, encephaloceles, and meningitis. Bone for this purpose is taken from the inner table of the frontal craniotomy bone. It is removed with an oscillating >a\v or small high-speed drill. In some cases, such as in children, it can be obtained from the iliac bone; this has the advantage of providing both cancellous and cortical bone. Over this flap, bone grafts from the inner table of the frontal bone are placed and covered with the temporalis fascia attached to the galea-pericranium flap (Fig. *25).*

Reconstruction of the supraorbital margins and orbital roofs is not necessary because they remain in the craniotomy in one piece. If they are infiltrated by the lesion and have to be removed, they can be reconstructed with iliac graft or -'. ith split rib graft. The nasal cavities and the oropharynx are racked with tetracycline-soaked gauze. This packing is left m place for 7 days.

For patients with a large defect of the anterior skull base, j spinal lumbar catheter for continuous CSF drainage is inserted. This system is usually removed 3 days after surgery. The bifrontal craniotomy is closed in routine fashion.



FIG. ***25.*** Reconstruction of the anterior skull base with galea-periosteum flap (from below) and temporalis fascia ifrom above). In between are bone fragments from the inner table of the frontal bone.

TABLE 1. Cases *operated on using subcranial approach*

Lesion	No. of cases
Menigiomas	12
Pituitary adenomas	8
Craniopharyngiomas	7
Chordomas/chondrosarcomas	5
Malignant tumors	8
Fibrous dyplasia	4
Osteoma/ossifying fibroma	2
Esthesioneuroblastoma	2
Aneurysmatic bone cyst	1
Cerebrospinal fluid fistula	4
Trauma	4
Total	57

CASE MATERIAL

From 1987 to 1995, 57 patients were operated on using a subcranial approach in the authors' institution (Table 1).

COMPLICATIONS

Complications related to this approach include CSF fistula and meningitis, infection, postoperative enophthalmos, hypertensive extradural pneumocephalus, cosmetic defects, and loss of olfaction.

In the authors' series, there were two cases of postoperative extradural infection. These patients had delayed extradural infection in the frontal sinus region. One of these patients with a malignant tumor underwent radiation therapy after the operation; the other patient was successfully treated with antibiotics. Meningitis, CSF fistula, postoperative enophthalmos, and pulsatility of the eyeball were not observed in the authors' patients. The cosmetic results are very satisfactory because the orbital rim and the bifrontal craniotomy are removed in one piece. Avoiding the bur hole over the frontal region gives a better aesthetic result. There was no mortality in this series.

CONCLUSION

The subcranial approach is the procedure of choice for most patients with anterior skull base lesions. The presence of intracranial and extracranial invasion with involvement of the clivus, pterygoid plates, anterior cavernous sinus, and sellar region is not a contraindication to this approach. Such an extensive surgical procedure, however, is not indicated when a highly malignant tumor is present or when it invades the cavernous sinus bilaterally. The use of this procedure or its combination with different approaches depends on the exact location of the lesion as well as its histologic nature (5,16,20-22).

In malignant lesions and giant benign tumors, the decision between complete tumor removal or subtotal resection for decompression of intracranial structures, with radiation therapy and chemotherapy, is based on careful preoperative evaluation. CT and MRI are performed for precise determination of tumor extension and involvement of neurovascular structures at the skull base. Digital subtraction angiography with balloon occlusion test is indicated when sacrifice of the internal carotid artery may be necessary. Intranasal biopsy should be considered when a malignant lesion is suspected. In cases of highly malignant tumors, the authors do not recommend a very large surgical procedure. Alternative therapy with radiation therapy and chemotherapy is carried out after biopsy. In cases of large benign lesions, radical removal is always attempted. Radical removal is not possible in some patients because of invasion of vital structures. In these cases, decompression of the involved structures and postoperative radiosurgery or radiation therapy may be the best treatment option.

The main advantages of this surgical approach are exposure of the whole anterior cranial base and paranasal sinuses with minimal retraction of the frontal lobes; the possibility of combining other surgical procedures for removal of tumors that invade the paranasal sinuses, clivus, middle fossa, and anterior portion of the cavernous sinus and nasopharynx; and very good reconstruction of the anterior cranial base with excellent cosmetic results.

The "one-piece" frontoorbital bone craniotomy permits reconstruction of the orbital roof, avoiding pulsatile exophthalmos. An excellent cosmetic result is obtained because the orbital rims remain attached to the frontal bone. Reconstruction of the large bony defect of the anterior cranial base should always be done to prevent meningoceles and encephaloceles that may cause delayed CSF fistula and meningitis.

For pure intradural lesions, such as aggressive pituitary adenomas, meningiomas, and craniopharyngiomas, this approach is also useful because dissection of both olfactory nerves is performed and wide bilateral exposure is obtained with minimal brain retraction. Both internal carotid arteries and optic nerves are identified and can be preserved. Removal of tumor infiltration into the sphenoid sinus is possible after drilling of the planum sphenoidale.

Tumor infiltration of the petrous bone, posterior fossa, intradural clivus region, and cavernous sinus with involvement of the internal carotid arteries are the main limitations for this procedure. In these cases, the authors effected the sub-cranial exposure with different surgical approaches. Anterior facial and lateral approaches are performed, usually during the same operative procedure. Posterior fossa approaches are carried out in a second operation some days later.

Loss of olfaction is produced in most patients when there is infiltration of the lamina cribrosa. It is, however, well tolerated in most cases. It can be avoided if there is no tumor infiltration in at least one olfactory nerve. In cases of large pituitary adenomas, craniopharyngiomas, and tuberculum sellae meningiomas, careful dissection of the olfactory nerves with preservation of function may be possible and should always be attempted. The mortality and morbidity associated with this surgical procedure are very low and usually related to postoperative CSF fistula and infection. The multidisciplinary teamwork of neurosurgeons. ear-nose-throat, head and neck surgeons, ophthalmologists, and plastic surgeons permits a more radical and safer approach to avoid these complications.

REFERENCES

1. Tessier P, Guiot G, Derome P. Orbital hypertelorism: definite treatment of orbital hypertelorism by craniofacial or by extracranial osteotomies *Scandinavian Journal of Plastic and Reconstructive Surgery* 1973:" 39-58.
2. Ketchman AS, Wilkins RH, Van Buren JM, Johnson RH, Smith RR. A combined intracranial facial approach to the paranasal sinuses. *Am J Surg* 1963:106:698-703.
3. Derome P. Les tumeurs spheno-ethmoidales. *Neurochirurgit* 1972;18[Suppl 1]:1-164.
4. Derome P.I. Transbasal approach to tumors invading the skull base. In: Schmidek HH, Sweet WH, eds. *Operative neurosurgical technique?.* 3rd ed. Philadelphia: WB Saunders, 1995:427-441.
5. Benzil DL, Robotti E, Forcht DT, Sullivan *P,* Bevivino JR, Knucke> NW. Early single-stage repair of complex craniofacial trauma: experimental and clinical study. *Neurosurgery* 1992;30:166-173.
6. Cheesman AD, Lund VJ, Howard DJ. Craniofacial resection for tumor* of the nasal cavity and paranasal sinuses. *Head and Neck Surger.* 1986;8:429-435.
7. Jackson IT, Marsh WR, Hide TA. Treatment of tumors involving the anterior cranial fossa. *Head and Neck Surgery* 1984;6:901-913.
8. Raveh J, Vuillemin T. The subcranial-supraorbital and temporal approach for tumors resection. *Journal of Craniofacial Surger.* 1990:1:53-59.
9. Sekhar LN, Sen C, Snyderman CH, Janecka IP. Anterior, anterolateral. and lateral approaches to extradural petroclival tumors. In: Sekhar LN. Janecka IP, eds. *Surgerv of cranial base tumors.* New York: Raven Press, 1993:157-223.
10. Persing JA, Jane JA, Levine PA, Cantrell RW. The versatile frontal sinus approach to the floor of the anterior cranial fossa. *J Neurosure* 1990;72:513-516.
11. Raveh J, Vuillemin T, Sutler F. The subcranial management of combined fronto-basal-midface fractures. *Arch Otolaryngol Head Neck Surg* 1988;! 14:1114-1122.
12. Samii M. Neurosurgical aspects of tumors of the base of the skull. In: Youmas JR, ed. *Neurosurgical surgery.* Philadelphia: WB Saunders. 1990:3639-3653.
13. Sundaresan N, Sachdev V, Krol G. Craniofacial resection for anterior skull base tumors. In: Schmidek HH, Sweet WH, eds. *Operative neurosurgical techniques.* 3rd ed. Philadelphia: WB Saunders, 1995: 415^125.
14. Ramina R. The transfrontal basal approach to skull base surgery. Presented at the Sacramento Skull Base Surgery Symposium, Sacramento. California, June 25-30, 1995.
15. Spetzler RF, Herman JM, Beals S, Joganic E, Milligan J. Preservation of olfaction in anterior craniofacial approaches. *J Neurosure* 1993;79:48-52.
16. Delfim R, Missori P, lannetti G, Ciapetta P, Cantore G. Mucoceles of the paranasal sinuses with intracranial and orbital extension: report of 28 cases. *Neurosurgery* 1993;32:901-904.
17. Jan M, Dweik A, Destrieux C, Djebbari Y. Fronto-orbital sphenoidal fibrous dysplasia: case report. *Neurosurgery* 1994;34:544-543.
18. Morita A, Ebersold MJ, Olsen KD, Foote RL, Lewis JE, Quast LM. Esthesioneuroblastoma: prognosis and management. *Neurosurger* 1993;32:706-711.
19. Meneses MS, Thurel C, Mikol J, et al. Esthesioneuroblastomas with intracranial extension. *Neurosurgery* 1990;27:813-820.
20. Delashaw JB Jr. Tedeschi H, Rhoton AL. Modified supraorbital craniotomy: technical note. *Neurosurgery* 1992:30:954-955.
21. Lalwani AK, Kaplan MJ, Gutin PH. The transsphenoethmoid approach to the sphenoid sinus and clivus. *Neurosurgery* 1992;31:1008-1012.
22. Price JC. The midfacial degloving approach to the central skull-base. *Ear Nose Throat J* 1986:65:174-180.

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 19

Work-up and Management of the Internal Carotid Artery in Neoplastic and Vascular Lesions

Laligam N. Sekhar and Sorin D. Bucur

When the internal carotid artery (ICA) is extensively involved by neoplasms or vascular lesions of the cranial base area, a careful preoperative work-up, a plan of intraoperative management, and well developed microsurgical techniques are essential to avoid complications. The most dreaded complications of such management are carotid blowout resulting in severe hemorrhage and death, or, more commonly, stroke secondary to the ischemia produced by occlusive or embolic problems.

PHYSIOLOGY OF CEREBRAL CIRCULATION

The brain receives a blood flow averaging 50 to 55 ml/100 g of brain tissue/minute. The blood flow is much higher to the gray matter, in the range of approximately 70 to 75 ml/100 g/minute, and much lower in the white matter, in the range of 15 to 20 ml/100 g/minute. The blood flow to the brain is closely coupled to its metabolic state; the requirements of blood flow to the brain decrease with decreasing cerebral metabolic rate. Situations of decreased metabolic rate are anesthesia, barbiturate coma, hypothermia, and coma due to severe brain injuries. When the brain tissue does not receive adequate blood flow, permanent injury and cell death can occur, producing neurologic deficits. This is called a "stroke."

The brain can tolerate a range of lowered blood flows for varying periods of time. In experimental models, the electrical activity of brain cells ceases when the blood flow drops to between 15 to 20 ml/100 g/minute. When such reduction is prolonged, permanent damage can occur. In the human brain, a reduction of the blood flow below 15 to 20 ml/100 g/minute results in a burst suppression pattern on the electroencephalogram (EEG) and a prolongation of somatosensory evoked potential (SSEP) responses to the hemispheres. Reduction of brain blood flow below a threshold of 10 ml/100 g/minute, even for a short period of time, can result in permanent brain damage. Such brain injury is due to excessive activation of the calcium ion system in the brain cells and eventually results in loss of cellular membrane integrity, with the intravascular transudation of sodium ions and permanent disabling of the electrical conducting mechanism. This leads to a cascade of events that include lipid peroxidation, the generation of free radicals, and other deleterious events that are mostly irreversible. The goal of ICA management before and during surgery is to prevent the reduction of cerebral blood flow below a critical flow threshold.

At a vascular level, strokes from carotid occlusion can occur because of the severe reduction of blood flow, or because of the occurrence of a thromboembolic phenomenon. The latter is a more common mechanism of stroke. In this situation, a clot forms inside the carotid artery and propagates up into the middle cerebral artery (MCA) and its branches, or small pieces of clot break off and migrate into the peripheral vessels, blocking the blood flow to the various vessels.

When a carotid artery is temporarily occluded, collateral circulation in the brain can frequently provide blood flow for varying periods of time. Such collateral circulation is derived from the external carotid artery, the contralateral ICA, or the basilar artery, through the arteries of the circle of Willis and the ophthalmic artery. Unfortunately, such collateral circulation is inadequate in 10% to 30% of patients. The collateral circulation can be improved for periods of time by artificially inducing hypertension, about 30 to 40 mm Hg above the baseline. In addition, during anesthesia, the re-

---

L. N. Sekhar, S. D. Bucur: Department of Neurological Surgery, The George Washington University Medical Center, Washington, D.C. 20037.

quirements for blood flow can be diminished by reducing the metabolic demand using barbiturate- or etomidate-induced coma, or by means of mild or even severe hypothermia with cardiac circulatory arrest.

If the carotid artery is permanently occluded, however, thromboembolic mechanisms can operate conjointly with ischemic mechanisms to cause a stroke.

GENERAL PRINCIPLES

The goal of the management of a carotid artery involved by a neoplasm or giant aneurysm is, first, to preserve the artery, and second, if the artery cannot be preserved, to replace it with an alternative source of blood flow. Another method that has been used by others and also by the current authors in the past is to occlude the artery permanently, based on the presumed adequacy of the collateral circulation.

Whether the carotid artery can be dissected free of tumor depends on several factors: the arterial segment involved, whether the artery is completely encased or encased and narrowed, whether an arachnoid plane is present around the artery to enable its dissection, the histologic nature of the tumor, and previous treatment.

Encasement of the upper cervical and petrous segments of the ICA allows the artery to be dissected in some cases because of the presence of a periadventitial plane in the upper cervical segment and periosteum of the petrous internal artery canal. Encasement of the intracavernous carotid artery can be more problematic. Even though there is an adventitial plane present, there is no periadventitial tissue to protect the artery from invasion. Tumors that encase this segment of the artery may invade the adventitia, which also carries the vasa vasorum (blood supply to the wall) of the artery. The supraclinoid ICA lies in the subarachnoid space, and a delicate arachnoid plane is present between the artery and tumor, in a previously unoperated or nonirradiated patient. In such previously untreated cases, the artery can be dissected free of tumor.

The nature of the tumor encasing the artery is important. Meningiomas encasing the carotid artery frequently invade the adventitia, but the artery is protected by the arachnoid membrane in the subarachnoid space. Previous surgery or radiation therapy destroys the arachnoid plane, making the dissection impossible. Chordomas and chondrosarcomas, if they have not been previously operated, can frequently be dissected away from the ICA even when they completely encase it. However, when previous radiation therapy has been used, dissection is frequently impossible. Schwannomas encase the ICA rarely, but when such encasement occurs, they can always be dissected from the artery. Cavernous an-giomas are rare lesions, but can be dissected free from the artery when they encase it. Malignant tumors, such as adenoid cystic carcinomas and squamous cell carcinomas, may be dissectable from the artery, but for oncologic reasons the artery frequently has to be excised when it is encased by the tumor.

PREOPERATIVE EVALUATION

The magnetic resonance imaging scan is the most important noninvasive test in evaluating carotid artery and other vascular encasement. T2-weighted images are particularly useful. Magnetic resonance imaging can also provide information about the water content of the tumor; in the case of benign tumors, this can be a useful indicator of whether the tumor can be dissected from the artery. Magnetic resonance angiography can also reveal the course of the artery through the tumor.

Cervical and cerebral angiography are important elements of the preoperative work-up. During angiography, the radiologist evaluates the blood supply to the tumor and the collateral pathways. If the artery is encased by tumor, an occlusion test of the artery with clinical evaluation is frequently performed. The value of the carotid occlusion test is controversial, but in the hands of experienced neuroradiologists. the test seems to be quite safe. Intravenous heparin is administered before the test (one tablet of aspirin also may be administered orally) to prevent any endothelial injury form the test. The test is carried out by temporary occlusion of the carotid artery for 15 to 20 minutes. Simultaneously, the other sources of collateral supply—namely, the external carotid artery, the contralateral ICA, and the vertebral artery—are injected with contrast to see which vessels are supplying the hemisphere during the period of test occlusion. The patient is examined clinically to determine if there are any neurologic deficits. If any develop, the test is terminated immediately. Some investigators perform balloon occlusion tests with induced hypotension to simulate dire perioperative conditions; however, because this process increases the risk of the test, the authors do not favor it.

The balloon occlusion test may be combined with other measurements of the adequacy of collateral flow. The gold standard here is xenon blood flow examination, which is not available in most institutions. Single-photon emission computed tomography (SPECT) scanning, which is available in most institutions, provides a qualitative indication of the adequacy of blood flow. Only a qualitative comparison of the information from the ipsilateral hemisphere with that of the contralateral hemisphere is possible, and no quantitative information is available from SPECT scanning. However, SPECT scans can be performed quite easily and are widely available. Transcranial Doppler ultrasound studies of MCA flow velocity have also been obtained as an indicator of collateral flow, but no correlation studies between transcranial Doppler and xenon-determined blood flow have been performed. It appears that transcranial Doppler is probably too sensitive to reductions in flow. No studies correlating transcranial Doppler or SPECT with the risk of carotid occlusion have been reported. The authors' protocol is simply to perform a clinical balloon occlusion test with simultaneous demonstration of the angiographic source of collateral circulation.

MANAGEMENT OF THE INTERNAL CAROTID ARTERY

Before and during an operation, the surgeon has to make a decision about whether the artery can be preserved. In the case of malignant tumors encasing the carotid artery, this decision is made before the surgery. In such patients (e.g., those with squamous cell carcinoma or adenoid cystic carcinoma encasing the carotid artery), the authors place a saphenous vein bypass graft from the cervical ICA, bypassing the region of the tumor, to the M3 segment of the MCA. The tumor-involved segment of the ICA is simultaneously occluded (Figs. 1-5). Approximately 1 or 2 weeks later, the operation to remove the tumor is performed without any complications.

With other tumors, such as meningiomas, chordomas, and chondrosarcomas, the authors usually make an attempt to peel the tumor from the artery during the operation. Normally, such dissection is carried out from the normal to the abnormal area, with preparation made for proximal and distal control to trap the artery temporarily in the event of vascular injury. The anesthesiologist must also prepare for the induction of barbiturate or etomidate coma, induced hypertension, and mild hypothermia to protect the brain during temporary vascular occlusion. If the artery is not dissectable, it is replaced with a saphenous vein graft. Such a graft may be a direct interposition graft (Figs. 6,7), or a bypass graft as previously described.

The authors no longer perform elective carotid artery occlusion based on preoperative assessment of collateral circulation; their experience in this area has been reported previously. The authors found that despite the best measures of collateral circulation, the incidence of stroke was still unacceptably high.



FIG. 1. Schematic drawing showing the trajectory of the graft through a tunnel shaped in the retroauricular area. (Copyright 1995 Laligam N. Sekhar, MD.)



FIG. 2. Schematic drawing showing the strategy of saphe-nous vein graft bypass from the petrous internal carotid artery (ICA) to the M2 segment of the middle cerebral artery in case of complete encasement of the petrous and cavernous ICA by a tumor. (Copyright 1995 Laligam N. Sekhar, MD.)





FIG. 4. Schematic drawing showing arteriotomy at the level of the M2 middle cerebral artery bifurcation, and the position of the graft to ensure additional retrograde flow. (Copyright 1995 Laligam N. Sekhar, MD.)

FIG. 3. Schematic drawing showing cervical internal carotid artery (ICA) to supraophthalmic ICA vein graft bypass, with the ICA sacrificed. (Copyright 1995 Laligam N. Sekhar, MD.)



FIG. 5. Schematic drawing showing the saphenous vein bypass strategy between the external carotid artery and the M2 segment of the middle cerebral artery, with different modalities of internal carotid artery (ICA) ligation, in a case of giant cavernous ICA aneurysm. (Copyright 1995 Laligam N. Sekhar, MD.)



FIG. 6. Schematic drawing showing cervical internal carotid artery (ICA) to cervical ICA interposition graft bypass for a giant cervical ICA aneurysm or pseudoaneurysm. (Copyright 1995 Laligam N. Sekhar, MD.)



FIG. 7. Schematic drawing showing petrous internal carotid artery (ICA) to supraophthalmic ICA interposition graft bypass in a case of giant cavernous ICA aneurysm. (Copyright 1995 Laligam N. Sekhar, MD.)

CASE REPORTS

CASE 1

This 30-year-old woman presented with a cavernous sinus syndrome secondary to a recurrent chondrosarcoma involving the sphenocavernous area (Fig. 8). The intracavernous ICA was encased and narrowed by the tumor (Fig. 9). An initial operation was performed to replace the ICA with a saphenous vein bypass graft from the cervical ICA to the M2 segment of the MCA (Figs. 10, 11). At a subsequent operation 5 days later, the tumor was resected completely. The patient recovered well, but with a worsening of her cranial nerve IV function. No recurrence has been observed over the last 3 years (Figs. 12-14).

CASE 1 (Continued)



FIG. 8. Case 1. A,B: Preoperative enhanced computed tomography scans showing tumor in the left sphenocavernous area.


MAGNETOM IMPACT
22-MAR-1993
LT CHORDOMA
POST GADOLINIUM 11CC

FIG. 9. Case 1. A-D: Preoperative coronal magnetic resonance images showing extension of the tumor with encasement and narrowing of the cavernous internal carotid artery.



FIG. 10. Case 1. Intraoperative angiogram demonstrates good flow through the graft.



FIG. 11. Case 1. A,B: Postoperative angiogram.

продолжение

продолжение

CASE 1 (Continued)



FIG. 12. Case 1. A: Postoperative axial magnetic resonance image (MRI) showing complete resection of the

tumor. B: Postoperative axial MRI showing the position of the vein graft.



FIG. 13. Case 1. A,B: Postoperative coronal magnetic resonance images showing complete resection of the tumor. The enhanced region represents the fat graft used for reconstruction.

CASE 1 (Continued)



FIG. 14. Case 1. A,B: Follow-up magnetic resonance angiograms demonstrating patency of the vein graft.

CASE 2

This 40-year-old patient had been treated with biopsy and radia-:ion therapy 8 years previously for an extensive adenoid cystic carcinoma. He presented with an extensive regrowth involving the cavernous sinus, petroclival area, and the infratemporal fossa (Figs. 15-17). The petrous and cavernous 1C A segments were involved by the tumor. He tolerated balloon test occlusion of the left ICA clinically with good collateral flow demonstrated from the other side (Figs. 18, 19). Because of the risk of stroke and ICA



FIG. 15. Case 2. A,B: Preoperative coronal magnetic resonance images show extension of the tumor into the cavernous sinus and infratemporal fossa.

CASE 2 (Continued)

rupture, a saphenous vein graft bypass running behind the ear was performed initially (Fig. 20), and this was followed by gross total tumor resection through a preauricular infratemporal approach, and reconstruction with a rectus abdominis free flap (Fig. 21). The patient recovered well without additional neurologic deficit. Follow-up intravenous chemotherapy was performed. However, 2 years later, he had extensive local and systemic tumor recurrence and died, despite further chemotherapy.



FIG. 16. Case 2. Preoperative sagittal magnetic resonance image (MRI) **(A)** shows extension of tumor in the petroclival area, and coronal MRI (B) demonstrates encasement of the internal carotid artery by the tumor.



FIG. 17. Case 2. Preoperative axial magnetic resonance image.

CASE 2 (Continued)


L Asc Pharyn. + L ICA Balloon
L Asc Pharyn, post E3
B

FIG. 18. Case 2. Preoperative supraselective angiograms showing vascularization of the tumor from the left ascending pharyngeal artery **(A),** and injection after embolization **(B).**


RICA with L ICA occluded

FIG. 19. Case 2. Anteroposterior view of right internal carotid artery (ICA) injection during balloon test occlusion of the left ICA, showing excellent collateralization through anterior communicating artery.

CASE 2 (Continued)



FIG. 20. Case 2. **A,B:** Intraoperative angiograms demonstrating the patency of the graft.


B
D
MAGNETOM IMPACT
28-DEC-1993
STUDY 3
STUDY 4
R
Post CM
HEARING LOSS

FIG. 21. Case 2. **A–D:** Postoperative axial magnetic resonance images showing gross resection of the tumor, and the muscle flap in the middle fossa used for reconstruction.

CASE 3

This 31-year-old woman had an extensive meningioma of the jugular foramen and the upper cervical area. A biopsy had been performed at another institution, after which she sustained a spinal accessory nerve palsy. The tumor was growing progressively in size (Figs. 22, 23). The upper cervical ICA was encased and narrowed by the tumor, and she failed a carotid occlusion test, manifesting a neurologic deficit during the occlusion. An ICA to MCA bypass was performed in preparation for the tumor resection, after dissection of the ICA from the tumor proved impossible. However, this graft exhibited poor flow (Fig. 24), and eventually occluded 2 weeks after surgery. The tumor was subsequently resected by a combined transjugular, infratemporal, and upper cervical approach. The abnormal segment of ICA was resected and reconstructed by means of a vein graft from the cervical to the petrous ICA (Figs. 25, 26). During temporary ICA occlusion, induced hypertension, mild hypothermia, and barbiturate-induced coma were used for brain protection. Her postoperative course was complicated by cranial nerves IX and X palsy, but she made an excellent recovery without having a stroke. The brain protection techniques used during the operation were effective in preventing a stroke during the period of temporary ICA occlusion.



FIG. 22. Case 3. A,B: Preoperative coronal magnetic resonance images showing extension of the tumor in the infratemporal fossa.

CASE 3 (Continued)



FIG. 23. Case 3. A,B: Preoperative sagittal magnetic resonance images demonstrate encasement and displacement of the cervical internal carotid artery by the tumor.



FIG. 24. Case 3. Postoperative angiogram of the first stage, demonstrating poor flow through the graft.



FIG. 25. Case 3. Postoperative angiogram after complete removal of the tumor and reconstruction of the cervical internal carotid artery. *Arrows* indicate locations of the proximal and distal anastomoses.

CASE 3 (Continued)



FIG. 26. Case 3. Postoperative three-dimensional computed tomography scan showing the graft.

OPERATIVE TECHNIQUE

Patients who require a significant ICA dissection during tumor removal undergo neurophysiologic monitoring using EEC and SSEP. The patient's head is placed in a radiolucent-pin head holder and a femoral artery sheath is placed by the neuroradiologist, in preparation for intraoperative angiography. The cervical internal and external carotid arteries are exposed. The greater saphenous vein is either exposed in the thigh for a distance of 20 cm, or the thigh area is at least prepared for possible extraction of the vein graft. If saphenous vein is not available, the radial artery can be used.

During the operation, dissection of the tumor is attempted if it is a benign tumor or of the cartilaginous variety (chordoma or chondrosarcoma). With malignant tumors, a bypass is performed electively if ICA resection will be required during the tumor resection.

If a saphenous vein bypass of the ICA is performed, the authors prefer a vein graft from the cervical ICA to the M2 segment of the MCA because the temporary occlusion time of the ICA is minimized. Occlusion of the M2 segment of the MCA for less than 50 minutes under brain protection techniques is well tolerated. If the patient has absolutely no collateral circulation, the external carotid artery or the vertebral artery may be used for the proximal anastomosis. If the M2 segment of the MCA is less than 3 mm in diameter, the supraclinoid ICA is used for the distal anastomosis, or a radial artery graft may be used.

During vascular occlusion, the patient's blood pressure is raised 20%, 2,000 U of heparin and 1 g of methylprednisolone are given intravenously, and metabolic suppression of the brain is induced with barbiturate, etomidate, or propofol, to achieve burst suppression on the EEG. If changes occur in the SSEP during the operation, ischemia of the deep brain regions is indicated, and the temporary clips may need to be repositioned, or the blood pressure raised further.

The distal anastomosis is performed first, with the graft preferably placed into a bifurcation of the MCA. After completing the anastomosis, a temporary clip is placed on the vein graft close to the MCA, and flow is resumed through the MCA. The vein graft is then brought to the neck through a retroauricular tunnel, and the proximal anastomosis is performed.

After the anastomosis is completed, the temporary clips are removed, and graft flow is checked by means of intraoperative Doppler probe and angiography. If adequate flow is not demonstrated, the problem must be corrected during surgery.

After surgery, the patient is maintained on subcutaneous heparin for a week, and then perpetually on 325 mg of aspirin daily.

RESULTS OF VEIN AND RADIAL ARTERY GRAFTING

One hundred twenty-two vein and artery grafts were performed by the senior author from 1985 through 1997 for the management of skull base tumors and aneurysms of the anterior or posterior circulation. The results of the grafting procedures cannot be compared with those of vascular occlusion procedures because many patients with poor collateral circulation were treated by grafting. Intraoperative angiography, and the lessons learned from the correction of intraoperative vein grafts, improved the patency rate of the grafts from 90% to 98% and reduced the stroke rate from 13% to 9%, even though more and more complex lesions have been treated in more recent years. Strokes with major deficits (Glasgow outcome score of 3) have occurred in only 5% of the group.

CONCLUSION

Management of the 1C A in skull base and vascular surgery has been greatly improved by vein and artery bypass techniques. Further improvements in brain protection techniques and in our understanding of vascular physiology will result in further benefits for patients with difficult lesions.

BIBLIOGRAPHY

DeVries EJ, Sekhar LN, Janecka IP, Schramm VL, Horton JA, Eibling DE. Elective resection of the internal carotid artery without reconstruction. *Laryngoscope* 1988:989:960-966.

Erba SM, Horton JA, Latchaw RE, et al. Balloon lest occlusion of the internal carotid artery with stable xenon/CT cerebral blood flow imaging. *AJNR Am J Neuromdiol* 1988;9:533-538.

Gormley WB, Sekhar LN. Augmentation of cerebral vascular reserve with bypass grafting in the treatment of tumors, aneurysms, and occlusive disease. *Critical Reviews in Neurosurgery* 1995:5:333-341.

Iwai Y, Sekhar LN, Goel A, Cass S. Vein graft replacement of the distal vertebral artery. *Acta Neurochir <Wien)* 1993:120:81-87.

Kotapka MJ, Kalia KK. Martinez AJ, Sekhar LN. Infiltration of the carotid artery by cavernous sinus meningioma../ *Neurosurg* 1994;81:252-255.

Sekhar LN, Iwai Y, WrightD, Bloom M. Vein graft replacement of the middle cerebral artery after unsuccessful embolectomy: case report. *Neurcsurgery* 1993:33:723-727.

Sekhar LN, Patel SJ. Permanent occlusion of the internal carotid artery during skull-base and vascular surgery: is it really safe? [Editorial]. *Am J Oral* 1993:14:421^22.

Sekhar LN, Sen CN, Jho HD. Saphenous vein graft bypass of the cavernou-internal carotid artery. *J Neurosurg* 1990:72:35^1.

Sen C, Sekhar LN. Direct vein graft reconstruction of the cavernouv petrous, and upper cervical internal carotid artery: lessons learned frotv 30 cases. *Neurosurgery* 1992:30:732-743.

Steed DL, Webster MW. DeVries EJ, et al. Clinical observations on the effect of carotid artery occlusion on cerebral blood flow mapped by xen. computed tomography and its correlation with carotid artery back pic-sure. / *Vase Surg* 1990; 1:38^4.

SECTION III

Posterior Fossa Approaches

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 20

Temporal Bone Resection

1

1 Aongus J. Curran, Patrick J. Gullane, Manohar L. Bance, and Paul J. Donald

Malignant tumors affecting the temporal bone are rare and account for only 0.05% of head and neck carcinomas (1). Owing to this rarity, a complete understanding of the pathophysiology of the disease is lacking. Diagnosis is usually at a late stage because the signs and symptoms of malignancy are often initially similar to those associated with chronic suppurative otitis media or otitis externa. The lack of a coherent staging system when comparing different reports makes an accurate comparison of the various treatment options difficult. Politzer gave the first detailed account of the disease in 1883, and is also credited with recognizing the importance of chronic suppurative otitis media as a common etiologic factor in its development (2). In this century, Parsons and Lewis contributed significantly to the surgical principle of *en bloc* resection of the lateral skull base, and Lederman introduced the important role radiation therapy has to play in the management of this aggressive group of tumors (3,4).

Since the late 1970s, there have been significant technical refinements and advances in cranial base surgery (5,6). The improved exposure and safety of approaches coupled with better anesthesia and an ability to reconstruct large defects with free and pedicled myocutaneous flaps has resulted in a reduction in functional and aesthetic morbidity. Modern imaging involving both computed tomography (CT) and magnetic resonance imaging (MRI) allows more precise localization and treatment planning for these tumors, which are now frequently managed by a multidisciplinary team that usually involves a combination of head and neck surgeons, neurosurgeons, and plastic surgeons. The most widely accepted operative concept is to free the involved temporal bone from its surrounding venous sinuses, protect the internal carotid artery (1CA) and brainstem, and avoid injury to cranial nerves. Typically, the patient also receives preoperative or postoperative radiation therapy. Although this has resulted in an improved quality of life for patients, the impact of these advances on survival is unknown. A recurring theme in previous reports is that diagnosis is often late in the natural history of the disease, and this is reflected in the frequently encountered poor prognosis.

The aim of this chapter is to present the clinical features of temporal bone malignancy that necessitate temporal bone resection, the options in management, and the controversies that surround this area. Particular emphasis is placed on tumors arising in the external auditory meatus, middle ear, and mastoid, and no attempt is made to detail the clinical features and management of malignancies involving the pinna. Although these lesions are much more common, the principles of management and complications associated with these tumors are somewhat different. Benign tumors are mentioned for completeness, whereas the management of glomus tumors is described elsewhere (see Chapter 24).

ANATOMY

Temporal Bone

The temporal bone occupies the center of the lateral skull base, with vital neurovascular structures passing to and from the brain through its substance (Fig. 1). It is a single bone that possesses tympanic, mastoid, zygomatic, and petrous portions. Each temporal bone articulates with its neighboring sphenoid, parietal, occipital, and zygomatic bones. It articulates with the condyle of the mandible by the glenoid fossa on the undersurface of the squamous portion of the bone as the temporomandibular joint (TMJ).

The temporal bone has many important relationships to neighboring structures, including:

1. *Medially,* the cerebellopontine angle and the brainstem are found.

A. J. Curran, P. J. Gullane, M. L. Bance: Department of Otolaryngology, The Toronto Hospital, and the University of Toronto, Toronto, Ontario, M5G 2C4 Canada.

P. J. Donald: Department of Otolaryngology—Head and Neck Surgery, and Center for Skull Base Surgery, University of California, Davis Medical Center, Sacramento, California 95817.

2. *Inferiorly* are the great vessels and the contents of the neck.
3. *Laterally* are the external auditory meatus and auricle.
4. *Anteroinferiorly* lies the infratemporal fossa, which contains the pterygoid muscles, the mandibular division of the trigerninal nerve, the internal maxillary artery, and the pterygoid venous plexus.
5. *Posteriorly*, the cerebellum is housed in the posterior cranial fossa, with the lower cranial nerves (V1I-XI1) surrounded by venous sinuses.
6. *Superiorly*, the temporal lobe is housed in the middle cranial fossa with cranial nerves II to VI.

The ICA enters the skull base at the carotid foramen (Figs. 1, 2). Here it passes through the petrous pan of the temporal bone anteromedial to the jugular foramen and medial to the styloid process. The vessel then turns through 90 degrees, becoming horizontal medial to the eustachian tube within the temporal bone. It then turns again to emerge at the foramen lacerum as it enters the cavernous sinus. During its intratem-poral course, it gives off the caroticotympanic artery, and within the cavernous sinus it gives off cavernous arteries. Vascularized tumors such as glomus tumors and nasopharyngeal angiofibroma are often supplied by these vessels, which can subsequently become significantly enlarged.

The temporal bone is closely related to the jugular bulb and the sigmoid sinus. At its superior end, the sigmoid sinus receives venous blood from the transverse (lateral) and superior petrosal sinuses (see Fig. 2). Mastoid emissary veins often communicate across the calvarium between the sigmoid sinus and posterior auricular veins. The jugular bulb becomes the internal jugular vein after the union of the sigmoid and inferior petrosal sinuses, and only a thin plate of bone separates it from the ICA.

The facial nerve has the longest bony course of any peripheral nerve in the body. Meatal, labyrinthine, middle ear. and mastoid components make up its intratemporal course. With the eighth cranial nerve (cochleovestibular), it leaves the pons and enters the porus of the internal auditory canal accompanied by the nervus intermedius and the internal labyrinthine artery and vein (see Fig. 2). It lies in the anterosuperior quadrant at the fundus above the cochlear branch of the eight nerve superior to the crista transversalis. The nerve then courses anteriorly to the geniculate ganglion and is ensheathed hy an extension of the subarachnoid space with cerebrospinal fluid (CSF) to this point. The geniculate ridge, a sharp, bony prominence, separates the labyrinthine from the tympanic segments. The latter begins at the geniculate ganglion, where the nerve makes its first extraaxial turn (internal genu) and begins a posterior course. The cochleariform process marks its most anterior limit and is a valuable landmark to locate the nerve in the middle ear. In as many as



Oval window

FIG. 1. Coronal section through temporal bone showing relationships of major vessels, brain, mandible, and middle ear.



FIG. 2. Temporal bone viewed posteriorly, demonstrating the internal auditory canal and major venous sinuses.

50% of cases, the bone is dehiscent over the nerve during its course through the middle ear. At the pyramidal eminence, the nerve makes its second turn (second genii) to begin its vertical mastoid course to the stylomastoid foramen. As the facial nerve passes through the temporal bone, it supplies the siapedius muscle. Later, it supplies the posterior belly of the digastric muscle and, extratemporally, the muscles of facial expression. In its vertical course, the facial recess lies lateral :o the nerve. This is the space bounded between the facial nerve and the chorda tympani nerve, and is an important surgical concept in lateral temporal bone resection. Figure 3 shows the surgical anatomy of this area as seen during mastoidectomy. Entry into the middle ear through this space allows visualization of the middle ear and removal of the middle ear and lateral ear with preservation of the facial nerve. Preganglionic parasympathetic secretomotor and special sensory afferent fibers are carried in the nervus intermedius, which travels with the facial nerve, and are then distributed by the greater superficial petrosal nerve and the chorda tympani. The pterygopalatine ganglion acts as a relay station, carrying secretomotor function from the greater superficial petrosal nerve to the nasal and lacrimal glands. The chorda lympani carries secretomotor fibers to the submandibular ganglion before these fibers reach the sublingual and submandibular glands, and also taste fibers from the anterior two thirds of the ipsilateral tongue.

On the anteromedial surface of the petrous temporal bone Ues a shallow depression called Meckel' s cave, in which sits the ganglion of the trigemmal nerve (V). Spread of disease to the petrous apex may result in some patients experiencing changes in facial sensation or facial pain. At ihe jugular foramen, the glossopharyngeal (IX), vagus (X). and accessory (XI) nerves leave together at the base of the temporal bone. A plexus (Jacobson's) is formed on the middle car promontory by sensory afferent fibers from cranial nerve IX before they exit anteriorly as the lesser petrosal nerve. This inner-vation of the middle ear by the glossopharyngeal nerve accounts for the phenomenon of referred pain experienced in some pharyngeal disorders.

External Auditory Canal

The external auditory canal (EAC) measures approximately 2.5 cm in an adult and extends from the concha to the tympanic membrane. Cylindrical!}' shaped, the outer one third is cartilaginous and the inner two thirds is bony. The latter is formed by the squamous portion of the temporal bone in its posterosuperior portion, and the remainder by the tympanic plate. The cartilaginous portion extends medially from the concha. Both parts are lined by closely applied skin. Pilosebaceous and ceruminous glands are found only in the outer third, in the cartilaginous portion.

Middle Ear

The middle ear is an air-filled space within the temporal bone containing the malleus, incus, and stapes ossicles with



FIG. *3.* Surgical anatomy of the mastoid, showing labyrinth (opened), fossa incudis, facial nerve, and facial recess.

their supporting ligamentous attaehments, Shaped like a biconcave disc approximately 15 mm in diameter, it is lined by ciliated, columnar, mucus-secreting epithelium. It also contains two muscles, the stapcdius and the tensor tympani. Laterally, it is bounded by the tympanic and squamous portions of the temporal bone with the tympanic membrane and medially by the petrous portion and inner ear structures. The medial wall has a number of important landmarks, such as the promontory, the round and oval windows, the ridge of the facial canal and the processus cochleariformis. Superiorly lies the tegmen tympani, and often only a thin layer of bone separates this space from the middle cranial fossa. The floor of the middle car is usually made of a layer of bone overlying the jugular bulb. Posteriorly, the middle ear opens into the aditus ad antrum. which passes into the mastoid air cell system. A number of bony canals leave the middle and inner ears and act as potential routes of spread of disease through the skull base. The eustachian tube joins the anterior wall of the middle ear to the nasopharynx, opening posterior to the medial pterygoid plates. From the anterior wall, the caroticotympanic plexus also leaves the middle ear. The eustachian tube lies superolateral lo the carotid canal and is separated from the ICA by a thin lamina of bone, Two bony canals, the vestibular and cochlear aqueducts, leave from the inner ear. The former transmits the endolymphatic duct, which leads to the endolymphalic sac on the posterior surface of the temporal bone. The latter connects the perilymph of the scala tympani with die CSF of the posterior fossa.

Lymphatic Drainage of the External Auditory Canal and Middle Ear

The anterior half of the external auditory meatus drains to the lymphatics of the preauricular. superficial, and deep parotid lymph nodes. Drainage then proceeds to the upper echelon of deep cervical nodes. The posterior portions of the canal drain typically to the retroauricular nodes overlying the sternoeleidomastoid muscle, and then to upper deep cervical nodes from this site.

The middle ear mucosa with the tympanic portion of the eustachian tube drains primarily to the parotid nodes and then to the upper deep cervical chain. The remainder of the eustachian tube at the nasopharyngeal end drains to the retropharyngeal lymph nodes (including the node of Rouvier), and to the upper deep cervical nodes.

INCIDENCE

The reported incidence of temporal bone malignancy, including tumors involving the BAG, is 0.01% of all reported neoplasms. Ninety percent represent primary tumors and 10% are metastases. Because of the increased numbers of head and neck surgeons, few relatively recent reports contain large numbers of patients compared with early descriptions.

For malignant tumors affecting the EAC, the male:female preponderance varies from 1:1 to 1:15 (7-11), with age ranges between 40 and 75 years (median, 62-68 years) (9,10). Most are squamous cell carcinomas, with approximately 20% being adenoid cystic or adenocarcinomas. Primary basal cell carcinoma arising in the external auditory meatus is unusual, and malignant melanoma is rare (7). There are no reliable data regarding racial preponderance.

A number of reports state that malignant disease in the middle ear and mastoid is twice as common in men than women (7.12,13). Up to 20% of cases are in the pediatric age group, and thus the average age of involvement is altered by this statistic. Most tumors in the pediatric age group are rhabdomyosarcornas. whereas most in the adult group are squamous cell carcinomas. This results in a bimodal distribution of tumor incidence, with one peak for childhood non-squamous malignancies and another in the fifth to sixth decades for squamous cell carcinomas.

ETIOLOGY

External auditory canal malignancy is associated with chronic inflammatory conditions such as otitis externa. It is possible that carcinogens such as aflatoxin produced by the *Aspergillus* fungus may have a role to play in some cases (14). Chronic chromate burns from repeated matchstick abuse and accidental exposure to radium paint used during World War II for illuminating watch dials are other known potential causes of such malignancies (15).

Politzer in 1883 first noted that malignancy of the middle ear and mastoid had a definite association with chronic suppurative otitis media (2). In 38% to 57% of patients, a chronic discharge is present before the development of malignancy (10,13). It is hypothesized that chronic inflammation alters the immunologic behavior of the middle ear cleft, resulting in a propensity for malignant change. Rarely is carcinoma identified in the presence of a normal intact tympanic membrane or without a prior history of otorrhea. Conventional external-beam radiation therapy for unrelated head and neck disease and therapeutic radium implants can also lead to the development of middle ear malignancy (15,16). In the past, radium seed implants were used to treat adenoid hyperplasia, predisposing the mastoid and middle ear to malignant change by the slow emission of radioactive alpha particles (15).

CLINICAL FEATURES

Cancer of the external auditory meatus and temporal bone is rarely diagnosed at an early stage. Tumors involving the temporal bone usually originate from the external canal and invade inward. Often, prolonged medical therapy for nonspecific symptoms such as otorrhea and pruritus occurs. When more advanced symptoms such as intractable pain, facial paralysis, sensorineural hearing loss, severe vertigo, or tinnitus with bloody discharge occur, the clinician is usually alerted to the diagnosis. Unrelenting and deep temporal bone pain is characteristic and signifies bony or dural invasion. The duration of symptoms until diagnosis varies from 4 months to 4 years (10). A history of previous mastoid surgery is not uncommon, and often the diagnosis is made after several biopsy attempts because secondary infection, hemorrhage, and tissue necrosis distort the histopathologic assessment. Clinical examination usually reveals an ulcer or polypoid tissue in the external auditory meatus associated with a tympanic membrane perforation. In up to 50% of cases the tumor is not visible otoscopically. Hearing loss may be conductive, sensorineural, or mixed, depending on tumor location (1). Trismus is usually indicative of disease extending into the TMJ or the infratemporal fossa, affecting the medial or lateral pterygoid muscles. The fissures of Santorini within the canal enable disease to transgress this area without difficulty, and parotid extension may present with a slight fullness in the gland substance. Tumors of the mastoid tend to advance rapidly through the cellular system to the posterior cranial fossa, and palsies of cranial nerves VII, IX, X, and XI represent advanced disease and poor prognosis (17,18). On occasion, tumor can spread down the eustachian tube and mimic a nasopharyngeal primary. The inner ear, being composed of compact bone, is resistant to invasion until late in the disease process.

PATIENT EVALUATION

Once histologic confirmation has been achieved by biopsy, the extent of disease is determined clinically and radiologically. A complete head and neck examination is necessary and includes examination of both ears and an evaluation of hearing with tuning forks and audiometry. The nose, oral cavity, pharynx, and larynx are examined. Facial nerve function is evaluated and the neck palpated for nodal involvement. Although assessing the local extent of the disease is often the first priority, it is important to exclude secondary lung, liver, and bone involvement. In general, if radical excision is contemplated, distant metastases are usually considered a contraindication to surgical cure. Radiography of the chest (posteroanterior and lateral) is necessary to assess for metastases, a second primary tumor, and acute or chronic pulmonary disease. Radiologic assessment with plain films of the mastoid and skull base has no role to play with the advent of CT and MRI, and is mentioned only in a historical context. Hypocycloidal tomography, once the gold standard for providing detailed views of temporal bone anatomy, has largely been superseded by high-resolution CT. Combining thin-slice (1.5 mm), high-resolution CT and MRI has revolutionized imaging of the temporal bone.

A CT scan and MRI assess the extent of the primary: its relationship to the dura, brain, facial nerve, carotid artery, and sometimes the presence of cervical metastases (Fig. 4). CT findings vary from demonstrating localized areas of bony erosion in the walls of the external auditory meatus, to involvement of the middle ear and mastoid. It is important to determine by CT if the bony septum between the eustachian tube or the floor of the middle ear and the ICA is eroded. Extension through the tegmen to the middle cranial fossa and posteriorly to the lateral sinus, as well as petrous apex, carotid canal, and jugular fossa involvement also can be assessed. An accuracy rate of 98% was reported when preoperative assessment of tumor extent was checked against operative and histologic findings (8). CT is also a valuable tool in delineating spread to the infratemporal fossa, parotid gland, and the retropharyngeal or cervical nodal chain. Similar to other head and neck sites, a limitation arises in the ability of CT to differentiate soft tissue inflammation from tumor in the absence of bony erosion.



FIG. 4. Recurrent carcinoma of right temporal bone in a 52-year-old man. Computed tomography scan demonstrates erosion of temporal bone from carcinoma and previous mastoidectomy.

The superior soft tissue differentiation afforded by MRI is a major advantage of this imaging modality over CT, especially with the tumor-enhancing effects of paramagnetic contrast agents such as gadolinium-DPTA. The use of this agent helps to define tumor from brain and from the inflammatory and reactive changes frequently seen before and after surgery. In addition, MRI provides valuable information concerning ICA or sigmoid sinus patency by the presence or absence of flow void signals, which is also helpful when combined with contrast enhancement for determination of cavernous sinus involvement. MR angiography, with its absence of ionizing radiation and detailed information, is beginning to replace conventional angiographic techniques. As CT and MRI continue to complement each other and technological advances such as three-dimensional reconstructions, it is conceivable that further refinements will improve surgical and radiation therapy planning, as well as postoperative assessment.

i

STAGING

No coherent staging system for temporal bone malignancy has been accepted by either the American Joint Committee on Cancer or the Union Internationale Contre le Cancer. This makes any rational comparison of previous reports difficult and any meaningful statistical analysis impossible. Previous attempts at staging systems have been criticized principally because reported series included small numbers, an assortment of differing histologic types, metastatic lesions, and differing anatomic sites (18,19). Both Goodwin and Jesse (18) and Stell and McCormick (19) proposed staging systems based on their series of cases. The latter found no difference in survival between patients with tumors of the external ear and those with middle ear tumors when corrected for stage. Despite the pitfalls of previous staging systems, advances in diagnostic imaging have greatly aided preoperative assessment and staging of patients with temporal bone malignancy. Arriaga et al. (8) found high-resolution CT was an accurate indicator of histopathologically proven tumor invasion. Twelve anatomic sites of the temporal bone were studied. When radiologic findings were compared with operative and histopathologic findings, there was a 98% correlation. The 12 sites for EAC malignancy and the proposed staging system are documented in Table 1.

TABLE 1. *Proposed anatomic/radiologic staging system for external auditory canal malignancy*

Anatomic regions

External auditory canal Anterior canal Superior canal Posterior canal Inferior canal Infratemporal extension Middle ear Otic capsule Mastoid Jugular fossa Carotid canal Tegmen ± middle fossa Posterior fossa **Propsed staging system** T1 Limited to the EAC without bony erosion or soft tissue extension. T2 Tumor with limited EAC erosion or CT evidence of less than 0.5 cm soft tissue involvement. T3 Tumor eroding the full thickness of the EAC with greater than 0.5 cm soft tissue involvement or with tumor involvement of the middle ear, mastoid, or facial nerve.

T4 Tumor eroding the cochlea, petrous apex, medial wall of the middle ear, carotid canal, jugular foramen or dura, or extensive involvement of soft tissue > 0.5 cm.

N Any nodal involvement is a poor prognostic factor. Despite an early T staging, the presence of positive nodes implies advanced disease. M When distant metastases are present.

EAC, external auditory canal.

No staging system for temporal bone malignancy proper exists at present, although a number of conclusions can be made from previous reports. The extent of local disease, the patient's general medical condition, the histologic type, lymphatic involvement, and the presence of distant metastases are all important prognostic factors (19). Five-year survival rates vary from 28.3% with disease of the EAC to 36.8% with primary middle ear involvement (7,8,20). At the time of diagnosis, temporal bone malignancy must be considered aggressive and at an advanced stage.

продолжение

TABLE 2, *Common malignancies of the external auditory canal and temporal bone*

- Squamous cell carcinoma
- Basal cell carcinoma
- Malignant tumors of glandular origin
  - Adenoid cystic
  - Ceruminous adenocarcinoma
- Sarcomas
  - Rhabdomyosarcomas
  - Chondrosarcomas
  - Osteosarcomas
- Rare tumors
  - Malignant melanoma
  - Lymphomas
  - Langerhans' cell histiocytosis
  - Carcinoid tumors
  - Verrucous carcinoma
  - Giant cell tumors
  - Chordoma

Tumors of Glandular Origin

For many years, "ceruminoma" has been used to denote both benign and malignant tumors arising in the ceruminous glands. This has led to confusion regarding the prognosis of neoplasms arising in the ceruminous glands. Benign lesions, ceruminous adenomas, and pleomorphic adenomas (mixed tumors) tend to arise in the sixth decade of life and are less common than malignant glandular tumors of the canal and middle ear (21}. The latter types, adenoid cystic carcinomas and ceruminous adenocarcinomas, arise earlier in life and are believed to develop from eccrine sweat glands or ceruminous glands.

Adenoid Cystic Carcinoma

This tumor is the most common malignant lesion of glandular origin to arise in the EAC. Historically, the lesion was often misdiagnosed, resulting in inadequate treatment and numerous recurrences. Commonly, the lesion involves cranial nerves and intracranial contents by the time it is diagnosed because of the affinity of adenoid cystic carcinoma for invading perineural tissue. Adenoid cystic carcinoma occurs in middle-aged people, with equal distribution between men and women. In over 90%' of cases, severe pain is a presenting feature. Despite wide resection, local recurrences and pulmonary metastases are typical features.

When found in the middle ear cleft, these tumors have usually arisen as a result of perineural spread from another site. It is possible that tumors can arise *de novo* in the middle ear cleft because ectopic glandular tissue, known as choristoma, has been described. In theory, ectopic glandular tissue can become trapped within the developing temporal bone, and may proliferate in later life. This salivary tissue is associated with anomalies of the seventh nerve pathway and congenital ossicular abnormalities (22). Another suggestion has been that the tissue represents an aberrant bud of parotid gland (23).

Similar to other sites in the head and neck region, there are three histologic patterns of adenoid cystic carcinoma that correlate with prognosis. The well differentiated, unencapsulated variety is the most common, with a propensity for infiltrating neural structures and perivascular spaces and invading tissue plains. This type gives a "Swiss cheese" histologic appearance to the affected tissue. A better prognosis is often associated with a cribriform pattern when a mantle of cells surrounds a central core of hyalinized tissue. Those tumors with a solid cellular pattern and an anaplastic appearance have the worst prognosis clinically (24).

The timing of metastatic spread varies considerably, and reports of systemic metastases appearing 30 years after the diagnosis exist. The lungs are the most common site of spread, although kidney, brain, cervical nodes, and bone are also affected. Surprisingly, patients may live for considerable periods with pulmonary metastases without significant symptoms, in contrast to other tumor types that have spread to this site.

Ceruminous Adenocarcinomas

These rare tumors affect men and women with equal frequency and usually around the fifth decade of life. The presentation is similar to other tumors of the EAC. Histologically, the finding of invasion of surrounding structures distinguishes them from benign ceruminous adenomas, which they resemble. Microscopic glandular, cystic, or papillary patterns are found.

Adenocarcinoma

This tumor is rarely found arising from the middle ear and occurs more commonly in women than men. The average age at presentation is approximately 40 years, and it is important to consider a metastatic origin (14). When arising behind an intact tympanic membrane, this lesion may initially have the appearance of a facial neuroma, a cholesterol granuloma, or a glomus tumor (25). Glomus tumors typically have a "moth-eaten" appearance on CT and may exhibit a smooth, scalloped enlargement of the jugular fossa. Malignant invasion by adenocarcinoma tends to show a more aggressive pattern of bony invasion.

Sarcomas

Sarcomas are rare tumors that arise primarily from poorly differentiated connective tissue, fat, muscle, synovium, vascular endothelium, or the supporting tissue of peripheral nerves. Those involving the EAC and temporal bone are extremely rare. The introduction of immunohistochemical staining in conjunction with conventional histologic methods has helped pathologists to reach accurate diagnoses in cases that in the past had been diagnostic dilemmas. Children (male more than female) are most often affected, with the usual presentation being a polyp in the external auditory meatus. Rhabdomyosarcoma is the most common tumor in this group, and the prognosis is generally poor. Other sarcomas affecting the temporal bone include neurofibrosarcomas, malignant fibrohistiosarcomas, leiomyosarcomas, and malignant schwannomas.

Rhabdomyosarcoma

This highly aggressive malignant tumor occurs primarily in children and accounts for 5% to 15% of childhood neoplasia. These tumors are locally destructive and invasive. In contrast to adults, in whom rhabdomyosarcomas involve the limbs, most children are affected in the head and neck region. The orbit, paranasal sinuses, and oral cavity are the most frequently affected sites, with temporal bone involvement accounting for 7% (26). In the middle ear, the stapedius and tensor tympani muscle are thought to be the sites of origin of this tumor. Twenty-five percent of cases originate near the eustachian tube and may not cause aural symptoms until late in the disease (27).

The median age for tumor occurrence is around 4 years. with a slight male over female preponderance. A typical presentation is with a purulent aural discharge, a mass in the EAC, and hearing loss. Failure of an attack of acute otitis media to subside with the presence of a mass should alert the clinician to this diagnosis. Because of the similarities with common middle ear disease, the diagnosis is often missed. Often a general anesthetic is necessary in young children to make an accurate tissue diagnosis. Multiple cranial nerve palsies are indicative of skull base involvement, and unfortunately 20% of patients have systemic metastases at the time of diagnosis. Meningeal involvement is associated with a poor prognosis because brain parenchymal spread has often occurred at this stage (28). Four tumor types are found histologically: pleomorphic, embryonal, alveolar, and botryoid. The embryonal subtype is the most common, and usually a mixture of each type is present in any individual lesion. A combination of chemotherapy (vincristine, dactinomycin. cyclophosphamide, and doxorubicin) and high-dose radiation therapy (4,000 cGy) is the treatment of choice. Limited resection may also be necessary in selected cases. A 47% 5-year survival rate can be achieved with this modality of treatment. Intrathecal chemotherapy and intracranial radiation therapy are being evaluated in an attempt to reduce tumor recurrence (28).

Chondrosarcoma

These tumors of cartilaginous origin usually arise during the sixth decade of life, primarily from the external auditory meatus. They are believed to originate from persistence of fetal cartilaginous chondrocranium, which develops during the fifth week of fetal life (29). Benign chordomas have a similar histologic appearance with chondroid matrices, and can cause confusion in the initial pathologic diagnosis. A pattern of aggressive clinical behavior distinguishes chondrosarcomas from the benign lesion. A radical surgical resection to prevent recurrence is usually necessary. Radiation therapy is not a reliable treatment option as a primary modality, although it can be used for residual disease; there are reports of remissions in some low-grade lesions.

Osteosarcoma

Osteogenic sarcoma represents the most common malignant tumor to involve bone, although the head and neck region is rarely affected. Typically the mandible is the site of involvement when the head and neck area is involved. Rare cases of temporal bone involvement have been described in the literature, and require a radical resection with combined radiation therapy when identified.

Rare Tumors

A number of rare tumors involving the EAC and temporal bone have been described in the world literature as case reports. Some benign tumors that have a locally aggressive nature are also described for completeness.

Malignant Melanoma

Primary malignant melanoma arising in the EAC is a rare entity compared with its incidence in other body sites (30). The lack of exposure to ultraviolet radiation in this region presumably has a protective influence against malignant transformation. Melanoma involving the middle ear reflects metastatic spread, and facial nerve palsy as a result of neural invasion has been reported.

Chordoma

Chordomas are rare tumors thought to develop from the embryonic remnants of the notochord. Some cases of these lesions arising in the temporal bone have been described, although they usually arise in the axial skeleton. More commonly seen is direct spread of chordoma to the petrous bone from the clivus. A high local recurrence rate after resection is reported, although they tend to grow slowly, if aggressively. The chondroid chordoma is a well differentiated variety that has a better prognosis than a true chordoma (31).

Fibrous Dysplasia

Monostotic or, less commonly, polyostotic fibrous dysplasia may involve the temporal bone in 20% of patients with head and neck involvement by this condition. The hearing loss is primarily conductive as a result of narrowing of the EAC and usually presents in the first two decades of life. Radiologic expansion of the temporal bone is characteristic, with cortical narrowing. Progressive canal narrowing may lead to cholesteatoma formation and necessitate surgical intervention.

Carcinoid Tumors of the Middle Ear Cleft

Eleven case reports in the literature describe primary carcinoid tumors of the middle ear, with a slight male preponderance. Presentation is with a sensation of aural fullness and hearing loss. Usually the tympanic membrane is not perforated but laterally displaced. Systemic features of carcinoid, such as flushing, wheezing, or diarrhea, are not described. The tumor is slow growing and behaves in a benign manner, with a 96% 5-year survival rate after resection (32). Radiation therapy is not recommended unless the disease has spread beyond the temporal bone or resection margins were incomplete. Reresection is preferable to radiation therapy.

Verrucous Carcinoma of the Middle Ear

This clinically aggressive and locally invasive tumor is histologically classified as benign. No basement membrane invasion or cytologic evidence of atypia are present microscopically. Verrucous carcinoma exhibits a papillomatosis, keratinizing squamous epithelium with acanthosis, hyperkeratosis, and parakeratosis (33). Grossly, the lesion is indistinguishable from well differentiated squamous cell carcinoma, with a soft, friable appearance and papillary frond formation.

A wide surgical resection is recommended to prevent local recurrence. Radiation therapy is not recommended. A progression to invasive squamous cell carcinoma has been described after radiation therapy for these lesions in other head and neck sites.[1]

Langerhans' Cell Histiocytosis

Eosinophilic granuloma, Hand-Schiiller-Christian disease, and Letterer-Siwe disease make up a group of disorders called Langerhans' histiocytosis (histiocytosis X). A localized pattern of histiocytic proliferation is seen in eosinophilic granuloma, with a diffuse pattern in Hand-Schuller-Christian disease and Letterer-Siwe disease. Over 70% of eosinophilic granulomas are diagnosed before the age of 20 years, and most before 5 years of age (29). Letterer-Siwe disease presents before the age of 3 years, and Hand-Schiiller-Christian disease before the age of 5 years. A history of chronic otorrhea with a friable EAC mass are the typical features. CT scanning demonstrates lytic, circumscribed bone lesions. Localized eosinophilic granuloma can be treated with surgical curettage and low-dose radiation therapy. Systemic disease requires chemotherapy with prednisolone, vinblastine, methotrexate, or cyclophosphamide. A poor prognosis is associated with presentation at a younger age group and systemic disease, but the prognosis is excellent in localized eosinophilic granuloma (34).

---

[1] **Editor's note:** *The editor does not recommend radiation therapy in the case of recurrent disease. Reresection is the treatment of choice.*

Secondary Carcinoma of the Temporal Bone

Occasionally the temporal bone is the site of secondary tumor involvement by direct invasion, hematogenous dissemination, or lymphatic or CSF spread. The temporal bone contains marrow, and sites such as the petrous apex with a constant sluggish blood flow may serve as prime areas for metastatic growth. Carcinoma of the breast, thyroid, lung, stomach, larynx, prostate, uterus, nasopharynx, and kidney are known to spread to the temporal bone.

Tumors in adjacent anatomic sites may invade the temporal bone directly. Carcinoma of the parotid may spread to bony channels or potential anatomic spaces such as the fissures of Santorini and Huschke's foramen. Lymphomas may invade from the nasopharynx and produce symptoms from perineural invasion or eustachian tube dysfunction. Meningeal carcinomatosis or intracranial primary tumors may spread to involve the temporal bone. The former is usually associated with multiple cranial nerve palsies due to diffuse infiltration of the subarachnoid space.

The presentation is not dissimilar to that of primary malignancy of the temporal bone. Often, severe pain, facial paralysis, and otorrhea are the the initial symptoms. Gradenigo's syndrome (affecting cranial nerves V and VI) or variations of Collet-Sicard syndrome (involving cranial nerves IX, X, XI, and XII) may be seen. Inner ear extension is associated with sensorineural hearing loss, tinnitus, and vertigo. Trismus is present when the TMJ is invaded.

MANAGEMENT

The Carotid Artery

Central to the successful management of the patient with temporal bone malignancy is correct management of the carotid artery. Before any attempted surgical resection, a detailed knowledge of the carotid artery and its possible involvement must be obtained. Whether the carotid artery can be preserved or should be resected, reconstructed, or both, are key questions in the oncologic decision-making process. Despite the advances in diagnostic imaging since the late 1970s, it is still difficult to predict which patients are likely to have permanent neurologic damage (i.e., stroke) as a consequence of ICA occlusion, and also which patients are likely to benefit from a revascularization procedure.

Clearly, a patient with a history of amaurosis fugax, a previous cerebrovascular accident, or transient ischemic attacks is more likely to suffer a permanent neurologic deficit should ICA occlusion be necessary. Conventional angiography, dynamic brain scans, and balloon occlusion techniques with somatosensory cortical evoked potentials (SCEP), transcranial Doppler ultrasonography, SPECT scanning, or stable xenon/CT cerebral blood flow imaging are valuable investigations to assess the risks of ICA occlusion (35-37).

Conventional Angiography

During this procedure, the patency of the circle of Willis and the collateral circulation of the cerebral hemispheres are assessed by studying the ipsilateral and contralateral ICAs in addition to the vertebral arteries. An indication of the collateral circulation may be gained by compressing the ipsilateral ICA and simultaneously injecting dye into the contralateral artery. Tumor invasion may be seen as a stenosis or an irregularity of the vessel wall. The presence of an atherosclerotic plaque in the contralateral artery is usually considered to be an indication for a carotid endarterectomy. Unfortunately, angiography reveals the anatomic details of the circle of Willis as well as vessel diameters, but gives no information on blood flow, and is thus a poor predictor of the vigor of cerebral circulation when one carotid is occluded.

Dynamic Brain Scans

Intravenous injection of technetium-99 glucoheptonate is performed while the ipsilateral ICA is occluded digitally. The collateral blood flow through the circle of Willis to the hemisphere with its blood supply occluded is compared with that of the opposite, unoccluded side.

Carotid Occlusion Studies

Studies determining the effect of ICA occlusion on intracranial circulation and the indications for vascular reconstruction were initially performed in the operating room during a major ablation. Changes in the SCEPs and the arterial pressure recorded in the distal stump of the ICA were used as parameters to decide if reconstruction was necessary. Cortical potentials were recorded 2 minutes before ICA occlusion and then every 90 seconds after occlusion of the vessel for 10 minutes. Maintenance of stump pressure above 50 mm Hg and unchanged SCEPs were indicative of adequate collateral circulation, and reconstruction of the artery was not undertaken. A drop in stump pressure below 50 mm Hg and a greater than 50% attenuation in SCEPs were indications for reconstruction of the ICA. It is now known that SCEPs do not predict which patients will tolerate a permanent occlusion of the ICA, and merely indicate the ability to tolerate a transient occlusion of blood flow (35).

At present, preoperative evaluation of clinical responses and SCEPs is performed using balloon occlusion angiography. A nondetachable balloon is introduced on a double-lumen Swan-Ganz catheter and the patient responses to occlusion are recorded. In the presence of neurologic symptoms or alterations in SCEPs, complete ICA resection without prior bypass surgery would be contraindicated. Attempts to improve the predictive ability of balloon occlusion testing have centered on inducing controlled hypotension, which reflects perioperative cerebral perfusion. In addition, Erba et al. have described xenon/CT cerebral blood flow imaging (37). This investigation is believed to give reliable information on cerebral blood flow reserve after occlusion. A number of patient groups were defined on the basis of this test:

- Group I: No change in cerebral blood flow after occlusion of the ICA
- Group II: A mild to moderate symmetric reduction in cerebral blood flow in all parts of the brain
- Group III: A significant reduction in blood flow that was greater in the cerebral hemisphere on the side of the occlusion
- Group IV: Occurrence of neurologic abnormalities when the balloon was initially inflated, requiring termination of the investigation

Despite negative findings in these investigations, approximately 10% of patients experience permanent neurologic deficit after resection of the ICA. Some of these episodes are related to reduced cerebral blood flow during periods of hypotension. Brain retraction, vascular spasm, emboli, and intraoperative hypotension may account for this damage. The risk of emboli can in theory be reduced by keeping the distal stump of the ICA as short as possible.

Surgical Considerations

In the absence of a widely accepted staging system, clinical experience dictates the management decisions in these rare and diverse malignant tumors. In general, surgery or radiation therapy, alone or in combination, are the treatment options. Tumors confined to the EAC are considered localized in the absence of middle ear cleft invasion or facial nerve involvement. The steps in the decision-making process involve the following:

1. Histopathologic confirmation of malignancy
2. Radiologic determination of disease extent and metastatic spread
3. A realistic appraisal of whether surgery is aimed at palliation or cure
4. The need to include the parotid, TMJ, infratemporal fossa, neck exploration, carotid artery, and dural or cerebral resection or reconstruction as part of the planned resection
5. The necessity or type of reconstruction options
6. A radiation oncology consultation in anticipation for postoperative radiation
7. A neurosurgery consultation if skull base surgical resection needed
8. An internal medicine, cardiology, or anesthesiology consultation

A number of surgical approaches are feasible that largely depend on the extent of the tumor. Complete surgical resection with a clear microscopic margin is the preferred initial primary treatment goal in a patient with a resectable cancer. For small tumors, radiation therapy is an alternative. When resection is contemplated, a team comprising a head and neck surgeon, neurosurgeon, neurootologist, and plastic surgeon may be required. In general, four types of resection are performed. These are excisional biopsy (including sleeve resection), lateral temporal bone resection, subtotal temporal bone resection, and total temporal bone resection. Figures 6 and 7 schematically depict lateral temporal bone resection and subtotal temporal bone resection, the two most commonly performed procedures.[2]

Excisional Biopsy

Rarely, when a tumor is small and does not invade bone or cartilage, it can be excised with an adequate margin of normal skin. This is usually basal cell in type. A so-called sleeve excision can be done (Fig. 8).

Lateral Temporal Bone Resection

The aim of this procedure is to resect a tumor confined to the EAC or tympanic membrane while conserving both labyrinthine and facial nerve function without compromising tumor margins. Ideally, this procedure is of value when a tumor arises in the postauricular sulcus, the concha, and the EAC, or when disease has just invaded the mastoid cortex or tympanic plate, but has not invaded the middle ear and mastoid air cells. When tumor is confined to the EAC, a more extensive resection does not improve survival (38). The following steps are necessary successfully to complete this resection, which involves a progressive dissection to verify the extent of the tumor and resecting only the temporal bone that is adjacent to tumor.

The first step of the procedure is to outline the lesion emanating from the EAC with an adequate margin of skin and conchal cartilage (Fig. 9). Incisions are extended superiorly and inferiorly to permit adequate exposure for mastoidectomy, condylar resection, and parotidectomy, when these latter two adjunctive procedures are required. The superior extension into the scalp is required if the zygomatic root is invaded or limited middle fossa exposure is necessary. The remnant of the pinna is left attached to the skin flap (Fig. 10).

---

[2] **Editor's note:** *Radiation therapy for small lesions is selected only if patients refuse surgery. Surgery for small lesions results in better than a 90% local control rate.*


Zygomatic arch
Foramen ovale
Sulcus for middle meningeal artery
Foramen spinosum
C
B
A
Superior petrosal sinus
Inferior petrosal sinus
Mastoid tip
Sigmoid sinus

FIG. 6. Axial schematic representation of extent of resection for lateral *(A)*, subtotal *(B)*, and total (C) temporal bone resections.



FIG. 7. Coronal schematic representation of extent of resection for lateral *(A)*, subtotal *(B)*, and total (C) temporal bone resections.



FIG. 8. Patient with invasive basal cell carcinoma of the auricular skin with early invasion of cartilage of the external ear canal. A sleeve resection is done with Moh's micrographic control to establish a tumor-free margin. (From Donald PJ. *Head and neck cancer: management of the difficult case.* Philadelphia: WB Saun-ders, 1984:228-230.) A: Basal cell carcinoma of the auricular concha with indistinct borders. B; Sleeve resection with tumor-free margins established. C: Post-operative result. Patient is 15 years post-surgery without recurrence.

In rare instances, there may be CT or MRI evidence of invasion of the mandibular condyle. In other instances, condylar resection may be required 10 achieve an adequate margin in the mesotympanum or even the anterior canal wall. In such cases, an incision in the fascia over the condyle is made to resect it. The temporalis fascia is elevated over a broad plane to avoid injury to the temporal branch of the facial nerve (Fig. 11). The fascia over the joint capsule is incised (Fig. 12A) and the capsule itself transected (see Fig. 12B), exposing the condylar head and overlying meniscus. A subpe-riosteal dissection encircles the neck of the mandible, and the condyle is surgically isolated (see Fig. 12C).

The next step in the procedure, which many times will precede the condylectomy, is to do a complete mastoidectomy (Fig. 13). The basic landmarks in the standard mastoidectomy are exposed, but the completeness of air cell removal is not necessarily as thorough as in surgery for cholesteatoma. The exception to this is the anterior part. Careful skeletonization of the fallopian canal is done such that the facial recess can be exposed with maximum exposure of the middle ear, especially the mesotympanic side of the tympanic membrane. An atticotomy is done, the incudostapedial joint severed, and the incus removed. If the zygomatic root is invaded, extension of the atticotomy is required to expose this portion of the disease (Fig. 14). If the disease falls short of the tympanic membrane, the incus and malleus are preserved and the ailicotomy is done meticulously, drilling the hone to a fine shell over the ossicles and carefully removing the chinned bony plate with a stapes curette. If tumor is found to invade the TMJ, then, as previously



FIG. 9. Incisions for lateral temporal bone resection outlined. Superior and inferior extensions are necessary if condylec-tomy and parotidectomy are to be done. Superior extension also is required if the zygomatic root is invaded.



FIG. 10. The tumor is encompassed by a soft tissue cuff down to the mastoid cortex. The remnant of the pinna remains with the scalp flap.



FIG. 11. If a condylectomy is to be done, an incision over the superficial muscular aponeurotic system (SMAS) facial covering and adjacent temporalis fascia is elevated on a wide base to protect the temporal branch of the facial nerve.



FIG. 12. Condylectomy. A: Remaining fascial cover over joint is incised. *(Continued,)*



FIG. 12. *Continued.* B: Joint is entered. C: A subperiosteal dissection encircles the neck of the mandible. The underlying internal maxillary artery is protected with a malleable retractor.



FIG. 13. Standard mastoidectomy. *1*, sinodural angle; *2*, cerebellar plate; *3*, zygomatic root.



FIG. 14. Mastoidectomy completed, but zygomatic root shows evidence of invasion.

mentioned, a mandibular condylectomy is done that includes the condyle, meniscus, glenoid fossa, capsular ligaments, and insertion of the lateral pterygoid muscles (see Fig. 12). Although controversial, it is probably wise to do a parotidectomy with facial nerve sparing in most cases of carcinoma of the EAC. The easy passage of tumor through the fissures of Santorini in the cartilaginous external canal to the parotid make the gland particularly vulnerable to tumor spread, and thus parotid resection is an important aspect of safe tumor clearance.

The final stage of tumor resection is at hand. In the usual type of tumor without zygomatic extension, a fissure is cut with the bur from the anterior attic into the glenoid fossa. A similar fissure is made from the inferior extremity of the facial recess toward the hypolympanum, taking care to stay lateral to the facial nerve (Fig. 15). In most cases, the tympanic membrane requires excision. In those few cases in which the membrane is spared, the fissure cut is made lateral to the tympanic ring. A series of osteotome cuts superiorly, interiorly, and posteriorly is made (Fig. 16A). The final osteotome is placed in the posterior fissure and driven into the glenoid fossa (see Fig. 16B). The specimen fractures away from the main body of the temporal bone and is removed from the last soft tissue attachments at the TMJ (see Fig. 16C),

With zygomatic extension, mandibular condylectomy is usually necessary and a more extensive resection is required. The resection is outlined in (Fig. 17). Great care must be taken to stay lateral to the eustachian tube and to come across the mesotympanum close to the tympanic annulus to avoid injury to the internal jugular vein and ICA. Fissures are cut through the glenoid fossa and tympanic bone, connecting the posterior fissure made inferior to the facial recess and the fissure at the zygomatic root. A fascia graft is placed over the stapes in an attempt to reconstruct the tympanic membrane. Split-thickness skin is applied to the mastoid cavity, and the scalp advanced into the defect as well (Fig. 18).

Complete Temporal Bone Resection

The next most common operation done after the lateral temporal bone resection is the subtotal operation. This procedure is done when tumor invades the middle ear and mastoid. This operation is based on the principles established by Lewis in the original operation (3). The importance of his contribution of this procedure—heroic in proportion at the time—cannot be overemphasized. One of the basic modifications to Lewis' original procedure is the use of the high-speed air drill.

A complete mastoidectomy is done despite the fact that the origin of the tumor may have been the auricle or the periauricular skin. The first resection block before the mastoidectomy will then be the margin of healthy skin and soft tissue surrounding the tumor, and the tumor is amputated at



FIG. 15. Fissure cuts into the glenoid fossa from the anterior aspect of the at-ticotomy to the glenoid fossa and from the inferior aspect of the facial recess toward the hypotympanum lateral to the facial nerve.



FIG. 16. Lateral temporal bone resection with zygomatic root, condyle. and glenoid fossa removed. A: Fissures cut and osteotomes placed. Note successive osteotome cuts superiorly, inferiorly, and finally anteriorly. B: An osteotome is placed in the fissure inferior to the facial recess and driven anteriorly into and through the anterior bony canal into the glenoid fossa.



FIG. 16. *Continued.* C: Resection completed,



FIG. 17. More extensive involvement of tissues adjacent to external auditory canal is diagrammed and cuts in the calvarium, zygomatic arch, and condyle are outlined. Dashes over the temporal squama indicate the craniotomy, and the dots outline the proposed ostectomy,



FIG. 18. Patient 6 months after extended lateral temporal bone resection with partial resection of zygoma, as outlined in Fig. 17. Wound was closed with scalp advancement and healed split-thickness skin graft.



FIG. 19. First block resection of lateral tissues, including involved auricle, periauricular skin, and soft tissues, to facilitate more precise temporal bone resection. A: Soft tissue block. B: Mastoidectomy done. Residual cancer left in temporal bone before subsequent complete removal.

the level of the cartilaginous canal and tumor-breached mastoid cortex (Fig. 19). As is mentioned throughout this text, total clearance of tumor by negative frozen-section and J eventually negative permanent-section margins ensures total tumor removal and a low incidence of local tumor recurrence. To struggle with a large tumor mass that interferes • with adequate visualization, especially when that necessitates unnecessary sacrifice of normal uninvolved tissue for the sake of the *en bloc* principle, is unwarranted. A series of 1 ~*en bloc* resections" with tumor only at the deep margin continues until all malignancy is cleared.

Complete encompassment of all disease in the mastoid is effected. Invasion through the tegmen mastoideum and tympani is not uncommon because this route presents a path of least resistance to tumor spread (6) (Fig. 20). Tumor may invade the sigmoid sinus or the lateral sinus through the sigmoid plate (Fig. 21). The resection of the lateral sinus must proceed with great care because the vein of Labbe enters the sinus at a variable distance from the top of the sigmoid sinus. Removal of the vein may result in severe motor deficits or even death, depending on the integrity of the superior cerebral vein of Trollard.

Below the tentorium, extension of tumor may penetrate :he cerebellar dura, and a more extensive removal of the oc.ipital bone will be necessary to provide exposure for resec::on (Fig. 22). The exposure may require a dissection folowing the sigmoid sinus to the jugular bulb and even into :he neck. Penetration from the jugular fossa into the carotid .anal often means the addition of the infratemporal fossa aprroach for optimal exposure.

Exposure of the zygomatic root, mandibular condylecomy, and parotidectomy are done in a similar fashion to the lateral resection.



FIG. 20. Coronal magnetic resonance image showing penetration of tumor through tegmen mastoideum and overlying dura and into brain.



FIG. 21. Axial computed tomography scan showing temporal bone and scalp tumor penetrating the skull in region of lateral venous sinus on the left.

Control of the medial aspect of resection is accomplished by a small, limited middle fossa craniotomy whose size is dictated by the extent of dural invasion (Fig. 23).

Temporal Craniotomy

The temporal craniotomy is most expeditiously outlined according to the method described by Montgomery (39). A cutting bur is used to outline a small bony incision in the temporal squama. The incision should extend in a smooth arc from the sinodural angle to a point 4 cm above the EAC, and then arch forward to the cut in the zygomatic arch (see Fig. 23). Before extending the cut to the dura, the intracranial fluid volume is diminished by extracting CSF through a previously placed lumbar drain, through a lumbar puncture, or by use of an osmotic diuretic such as mannitol.

Next, the inner table of skull is carefully cut through and the bone flap carefully dissected from the underlying dura. This is usually fairly easy to do, except in the elderly, in whom the dura is brittle and adherent to the skull. This part of the procedure may be done either by the neurosurgeon or the head and neck surgeon. The author prefers to cut the bone flap himself and leave the rest to the neurosurgeons, because they seem to think that a bigger craniotomy is desirable. The purpose of this operative step is to control the superior petrosal sinus and the middle meningeal artery, detect and resect any dural invasion or temporal lobe extension if possible, and establish the medial margin of resection. As the temporal lobe dura is elevated from the floor of the middle fossa and retracted with a Teflon-coated retractor, the superior petrosal sinus is prized from its fissure in the posterosu-



FIG. 22. More extensive posterior craniotomy must be carried into the occiput to resect effectively cere-bellar dura invaded by tumor. A: Modified postauricular incision. Extended mastoidectomy; pointer on tumor. B: Occipital craniotomy as an extension of the presigmoid exposure achieved by complete mastoidectomy. (From Donald PJ. *Head and neck cancer: management of the difficult case.* Philadelphia: WB Saunders, 1984:248.) C: Drawing illustrating exposure and cerebellar retraction.



FIG. 23. A: The temporal craniotomy is outlined with the cutting bur. B: Craniotomy flap removed. The glenoid fossa is cut across medially, and the incision often transects the eustachian tube and proceeds into the middle cranial fossa. The inferior aspect of the fissure is carried down to the level of the medial aspect of the styloid process. C: The five osteotome cuts necessary to excise the bone are outlined. D: Defect after excision. (From Donald PJ. *Head and neck cancer: management of the difficult case.* Philadelphia: WB Saunders, 1984:241-243.)

perior extremity of the temporal bone (see Figs. 7-23). This elevation proceeds toward the cavernous sinus and Meckel's cave, judiciously avoiding both.

Exposure of the middle fossa floor to the portion of temporal bone medial to the arcuate eminence is done with the dural elevator.

All aspects of the circumference of the temporal bone are now outlined, and final bony cuts may now be made.

Final Bony Cuts

This critical part of the resection is where most surgical disasters occur, The problem is that the internal cuts that sever the temporal bone from the skull run adjacent to the course of the ICA and the jugular bulb. Injury to the latter structure is no great problem because bleeding can be controlled from below by the umbilical tape and from above through tamponade of the sigmoid or lateral sinuses. However, hemorrhage from a rent in the ICA can be life threatening because bleeding can be only partially controlled in the neck. Moreover, occlusion of the vessel may result in stroke and even death.

Osteotome cuts are initiated at the following sites (see Fig. 23C):

1. A cut is made posteriorly through the back surface of the bone at its most medial aspect, through the most medial limit of cerebellar plate skeletonization.
2. From cut no. 1, a superiorly directed bony incision is made to the sinodural angle. A cut through the tegmen mastoideum connects this to the craniotomy and is carried medially.
3. A cut is then made inferiorly just lateral to the styloid process and directly lateral to the jugular bulb. This cut is directed superiorly and slightly medially.
4. A cut is made anteroinferiorly through the fissure in the glenoid fossa.
5. For the "coup de grace," a cut is made superiorly through the floor of the middle fossa, just medial to the arcuate eminence.

These bony incisions are best made with an osteotome. The instrument is guided toward the theoretical center of the temporal bone near the internal acoustic meatus by being angled slightly medially. A gentle tapping with the mallet is followed by a slight twisting of the osteotome. This results in a more controlled type of incision. The cut medial to the arcuate eminence has to penetrate the otic capsule and thus requires a more brisk blow with the hammer.

Anteroinferiorly, the cutting and twisting motion of the osteotome usually results in the bone splitting along the plane of the initial ascending portion of the ICA. The bone is most commonly transected through either the cochlea or the internal auditory canal.

Cavity Ablation

If the bone transection is too medial in the internal auditory canal, a CSF leak may result. A fat graft taken from the subcutaneous area of the abdomen and placed at the site of the leak is usually an effective plug.

Temporalis muscle flaps may be used to ablate the cavity. However, the cavity should not be so effaced that possible tumor recurrences might be obscured in their early stages.

The most important aspect of closure is the careful replacement of any resected dura with fascia, together with the securing of a watertight closure of any rents.

Hypoglossal-to-Facial Nerve Anastomosis

Full temporal bone resection always necessitates transection of the facial nerve. Although some thought may be given to cable grafting the nerve, this connection must extend from the proximal internal acoustic canal to the transected main trunk near the resected parotid bed. This is a difficult maneuver, and the author elects in most cases to do a hypoglossal-to-facial nerve crossover anastomosis.

The hypoglossal nerve is cut as far down in the neck as possible so the anastomosis will be tension free. The ap-



FIG. 24. Total temporal bone resection with hypoglossal-to-facial nerve crossover anastomosis. (From Donald PJ. *Head and neck cancer: management of the difficult case.* Philadelphia: WB Saunders, 1984:244.)

>ximation is made under microscopic control using 10-0 nylon sutures. Approximately 10 sutures are placed through the epineurium ofthe.se nerves (Fig. 24).

Closure

When a portion of the auricle remains, the flap is returned and the gap created by the conchal and external canal skin excision is bridged with a split-thickness skin graft. The graft is inverted into the cavity and packed with iodoform- or antibiotic-impregnated gauze packing. The graft is sutured to the auricular cut edges, and the remaining wound in the neck and scalp is closed with interrupted sutures.

The neck is drained and a large pressure dressing applied, or suction drains are used. Excision of the entire auricle occasionally presents a problem in closure. Because most patients with temporal bone carcinoma are elderly, an elevation of the facial skin similar to that of a face lift enhances flap advancement. When this is not enough, a relaxation incision can be done and a bipedicled scalp flap advanced into the wound. The donor site on the skull is skin grafted, and the wound closed and drained.

Total *Petrosectomy*

The most extensive temporal bone cancers are fortunately rarely seen. These tumors involve all or some of the internal acoustic canal, the ICA. the superior or inferior petrosal sinuses, the cavernous sinus, and any of the surrounding dura, the falx, or the temporal lobe of the brain. Controversy continues concerning the advisability of brain, ICA, and cavernous sinus resection. In the authors' experience, the prognosis is adversely affected by involvement of these areas, but resection is still considered warranted even if only as a palliative effort. Details of carotid resection and the management of cavernous sinus involvement are found in Chapter 16. and these issues are not discussed in detail here.

The preparation for the resection is similar to that for the subtotal temporal bone resection (Fig. *25).* Posteriorly, cerebellar plate removal continues to a point just lateral to the porus acusticus. Superiorly, the superior petrosal sinus is elevated to its point of entrance into the cavernous sinus. In the process, Meckel's cave is exposed and the proximity of Dorello's canal is reached. If uninvolved, cranial nerves V and VI are carefully protected. Involvement of the cranial nerve V is not uncommonly seen, and the gasserian ganglion may need to be removed.

Careful elevation of the lateral aspect of the cavernous sinus is necessary so that the final osteotome cut does not lacerate the sinus. The various extensions of the sinus to the foramina of the third and sometimes second divisions of the trigeminal nerve may need to be coagulated with the bipolar cautery and packed off with thrombin-soaked Geltbam pledgets or hemostatic gauze.



FIG. 25. Patient after complete mastoidectomy and parotidectomy with cranial nerve VII exposure and middle fossa craniotomy, now ready for complete petrosectomy.

Anteriorly, exposure of the middle fossa floor provides exposure of the foramen spinosum. The middle meningeal artery can be clipped, tied, or coagulated. Exposure of the foramen ovale requires zygomatic ostectomy to provide infratemporal fossa exposure.

inferiorly, careful attention is given to clear delineation of the ICA and internal jugular vein, and rubber catheters are used to circle these vessels in the neck. If either vessel is invaded at this point, the "modified *en bloc'* resection principle is invoked, and in the initial phase of total petrosectomy. any tumor involvement of either the vein or artery is left to be addressed at the next phase of resection.

Osteotome cuts are made lateral to or just through the most lateral aspect of the internal auditory canal. These are done both posteriorly and superiorly (Fig. 26) near the petrous apex. The fracture along the carotid canal is even easier in those cases with ICA invasion by tumor. The bone tends to fracture along this line of weakness, With removal of the bone, CSF begins to leak from the internal auditory canal.

With removal of bone, only a rudiment of the petrous apex remains (Fig. *21).* The remaining bone, and that of its articulation with the sphenoid, is removed with a drill. The carotid canal is drilled away if involved and the carotid removed and grafted. The cavernous sinus is removed by the neurosurgeon. Clival erosion is removed by the drill. Per-



FIG. 26. Osteotome cuts *(1)* through cerebellar plate, *(2)* along tegmen mas-toideum, *(3)* through tympanic bone just lateral to the internal carotid artery and internal jugular vein, (4) through the glenoid fossa, and (5) medial to superior semicircular canal adjacent to cavernous sinus.

ineural invasion is traced in a central direction until tumor-free margins are obtained.

Reconstruction involves dural grafting, but a watertight seal between the often incomplete dural closure and the nasopharynx is not uncommon. Complete eustachian tube removal is usually necessary. Closure from the nasopharynx and augmentation of dural closure may occasionally be achieved with fat grafts. Usually a temporalis muscle flap or a rectus abdominis free flap effects closure and seals any CSF leakage. Meticulous postoperative eye care is essential, especially when the facial nerve and trigeminal ganglia have been resected.

The Neck

Management of the neck is an important issue in the management of these tumors. Unfortunately, it is often not addressed in publications in this area. Although many publications quote cervical lymphatic metastases in the range of 10% to 20%, the authors[1] belief is that, this incidence is higher. The American Society for Head and Neck Surgery and The Society of Head and Neck Surgeons have published guidelines for management of the neck (40). For NO neck disease, an ipsilateral upper neck dissection (level 2 and 3 nodes) is recommended. For Nl disease, an ipsilateral modified radical dissection with preservation of cranial nerve XL



FIG. 27. Bony remnant after total petrosectomy.



FIG. 28. Pectoralis major myocutaneous flap reconstruction of temporal bone defect. A: Before resection. B: After insetting of flap. C: Postoperative appearance at 3 years.

the sternocleidomastoid muscle, and internal jugular vein is preferred. For N2,3 disease, preservation of these structures is also recommended whenever possible, although a radical neck dissection may be necessary.[3]

Editor's note: *The editor's philosophy is more radical than that of the other authors of this chapter. The N1 disease is treated by a radical neck dissection modified by preservation of the spinal accessory nerve when possible. For N2 and N3 disease, not only is a radical neck dissection done, but the occipital nodes are removed.*

Reconstruction

The head and neck surgeon of the 1990s has a vast array of reconstructive techniques available after ablative resections, and these may involve regional, primary, and free flap reconstruction. Reconstruction aims at covering exposed dura, preventing CSF leakage, and replacing surgical dead space with healthy, vascularized tissue. This reduces the morbidity associated with these procedures by reducing complications, and thus improves quality of life. Myocutaneous axial flaps such as the pectoralis major flap (Fig. 28) largely replaced local temporalis and deltopectoral flaps during the 1980s (41). To reach the lateral skull base, this flap (based on the pectoral branch of the acromiothoracic artery) must be stretched to an extreme, and thi.s may result in partial necrosis at a critical anatomic site. As free tissue transfer became more widely available, this flap became less widely used. The trapezius myocutaneous flap (Fig. 29) based on the transverse cervical vessels and the latissimus dorsi flap provide excellent bulk and soft tissue cover. They remain alternatives less commonly used to reconstruct the lateral skull base. The need to alter the position of the patient during the procedure, coupled with a technically difficult elevation, has not led to widespread adoption of these reconstructive options. Free tissue transfer is the preferred reconstructive option for lateral skull base defects. Free rectus abdominis or myocutaneous flaps provide reliable one-stage reconstruction of complex temporal bone defects. Vessels suitable for anastomosis can be easily obtained from the cervical vessels, and good tissue bulk is provided by these flaps. Larger and more extensive tumors previously deemed inoperable are now being resected. Complications such as CSF leakage are reduced, and the provision of healthy tissue to the ablation site allows postoperative radiation therapy to be safely instituted (42). Patients requiring complete resection of the auricle may be candidates for the osseointegrated, bone-anchored implants developed by Branemark et al. (43). These implants are placed once good tissue cover has been achieved, and cosme-sis is excellent once a bone-anchored prosthesis is placed.

Despite the advances in technical aspects of surgery for these tumors, it is not known whether long-term survival is improved. No single institution has sufficient data to allow a meaningful analysis of results. Resection in cases of petrous apex involvement appears to be of reasonable value. In a series of 14 total temporal bone resections reported by Malata et al. (44), 9 (64%) had a tumor free survival when followed for an average of 70 months.

COMPLICATIONS

By paying careful attention to preoperativc evaluation and adhering to sound oncologic principles, many of the complications and emergencies associated with the treatment of temporal bone malignancies can be avoided. Intraoperative hemorrhage, cerebrovascular accidents, and CSF leakage are the primary complications associated with temporal bone surgery. Hemorrhage during surgery usually occurs from the jugular bulb or sigraoid sinus. The immediate importance of this bleeding stems from the fact that air embolism may occur witb consequent life-threatening arrhythmias or hemodynamic changes, Simple pressure, a muscle plug, or bone wax packed into the area is often enough to tamponade these low-pressure bleeds. Occasionally, the sigmoid sinus needs to be ligated below the entry of the superior petrosal sinus for adequate venous control.

Cerebrospinal fluid leakage may result whenever the subarachnoid space is opened, and carries a risk of meningitis. Complete obliteration of the middle ear space, repairing torn dura, sealing dead space with vascularized tissue, and observing meticulous wound closure help to minimize this complication. If CSF rhinorrhea occurs, a compression dressing and trial of a lumbar drain for a number of days may be warranted to reduce the CSF pressure and allow spontaneous closure. Rarely, a second surgical exploration with attention to the region of the eustachian tube may be needed.

Whenever the ICA is ligated, resected, or both, despite reconstruction, a full-blown cerebrovascular accident (stroke) may develop and have devastating consequences for the pa-



FIG. 29. A,B: Trapezius myocutaneous flap reconstruction of temporal bone defect.

продолжение

tient. Thromboembolic phenomena from atheroma, air embolism, or blood clot are potential causes. Cerebral bypoper;usion caused by perioperative hypotension and vascular spasm may have detrimental sequelae in a patient with a marginal collateral circulation. Bypass grafts need to be kept .:s short as possible when used, and anastomosed in an end-to-end fashion to reduce turbulent blood flow.

After major resections, patients often lose any residual cochleovestibular function, Vertigo in the immediate postoperative period is not uncommon, and ataxia from the abrupt vestibular loss may persist for several months until compensation from the functioning opposite labyrinth occurs. Elderly patients are particularly prone to this persistent disequilibrium.

Single or multiple cranial nerve deficits may he present before surgery as a result of tumor invasion of the skull base or after surgery because of surgical trauma. Early recognition of swallowing dysfunction and potential aspiration is important because appropriate preventive means can minimi/,c aspiration pneumonia.

Facial Nerve Injury and Rehabilitation

Loss of facial nerve function with its associated psychological sequelae, alterations in speech, and mastication problems is expected after major resections. Primary intraoperative reconstructive options include interposition sural or greater auricular nerve cable grafts between the proximal and distal ends of the facial nerve. Other reconstructive options include facial-to-hypoglossal (VII-XI1), facial-lo-accessory (VII-IX), or a cross-facial sural nerve interposition graft. Depending on the individual case, these procedures are usually performed at a laier stage and usually within 6 months of the initial surgery (45).

Myths and misconceptions surround the role of these reconstructive methods in the delayed case. Usually when a useful facial nerve is absent or long-term facial paralysis has resulted in mimetic atrophy and fibrosis, alternatives to reinnervation are required. In these cases, the rehabilitation techniques include static and dynamic procedures (46).

Dynamic procedures involve regional muscle transfer (masseter or lemporalis) when available. Gold-weight lid-loading and eyelid-spring implantation help to prevent cornea] abrasion and are useful as early rehabilitation methods for the paralyzed eye. Although tarsorrhaphy is a time-honored method of corneal protection, it has an unpleasant cosmetic result and may restrict lateral visual fields.Tarsorrhaphy has to a large degree been replaced by the preformed upper-eyelid gold-weight implants (0.75-1.2 g) which provide adequate corneal protection in patients with minimal lid retraction. A major advantage of this method is the ease with which the implant can be removed should facial nerve function recover spontaneously. Failure rates (including extrusion) are usually less than 10% (46.47). Eyelid springs are indicated for a more complete or permanent facial paralysis when there is marked lid retraction and a poor Bell's phenomenon. They are technically difficult to insert and remove, if required. Failure rates (including extrusion) are estimated at 15% (46,48).

Static procedures involve the use of fascia! or alloplastic (i.e.. Cortex) slings and cosmetic procedures such as face lift, brow lift, and lid tightening. An advantage of the alloplastic slings is that they can be temporarily inserted to improve oral competence and minimi/c drooling in a patient with a facial paralysis. At a later stage, removal is possible should facial function improve.

When facial function is not expected to recover, a combination of static and dynamic procedures is usually required. Every patient requires an individualized approach to rehabilitation, and multiple procedures are usually the norm to achieve a satisfactory cosmetic and functional result.



FIG. 30. A,B: Prosthetic reconstruction of the pinna 3 years after a lateral temporal bone resection.

Other Rehabilitation Problems

Hearing rehabilitation may become an issue if the neoplasm is in an only hearing ear. Younger patients may object to cosmetic appearance of a skin graft that may influence the choice of free flap. Osscoimegrated prostheses are also an option for long-term cosines is (Fig. 30). Dental consultation is very useful in managing some of the long-term problems with TMJ dysfunction and masticatory pain. Swallowing therapy and vocal therapy may be useful in the presence of postoperative swallowing dysfunction and aspiration.

RADIATION THERAPY

The precise role of prcoperative or postoperative radiation therapy for malignancy involving the temporal bone is unclear. A review (38) has indicated that the addition of radiation therapy to patients with disease confined to the EAC and treated with a lateral temporal bone resection confers no survival advantage. The role of radiation therapy in patients treated with subtotal temporal bone resection was unclear. Radiation therapy is seldom advocated as the sole treatment modality for malignancy of the EAC or temporal bone. Its overall effectiveness is diminished if the bone is invaded by tumor (49). Postoperative radiation therapy may help in improving local control rates in resectable disease, but does not appear to affect recurrence and survival rates if the surgical margins are involved with residual tumor. Lederman (50) and others have recommended that radiation therapy should be used after variants of lateral temporal bone resections have been performed.

Guidelines from The American Society for Head and Neck Surgery and The Society of Head and Neck Surgeons (40) for postoperative radiation therapy include when resection margins are close (less than 5 mm), when proximity of tumor to important structures such as TCA or facial nerve preclude "wide margins." when margins of resection are microscopically positive, and, finally, when there is perincural invasion. In general, these conditions apply to most resections for temporal bone carcinoma.

Radiation therapy is also indicated if there are multiple hislologically positive nodes, or evidence of extracapsular spread. In addition, radiation therapy is indicated for most adenoid cystic carcinomas.

Five-year survival rates from radiation therapy alone of 11% contrast to 34% when combined radiation therapy and surgery is used. In theory, suspected micrometastatic disease in the lateral skull base, parotid, or neck may be sterilized by a course of radiation treatment. Once the extent of the tumor has been defined, the optimal target volume can be decided. A typical plan is shown in Fig. 31, Typically, two wedged cobalt-60 fields are applied at right angles, producing a circumscribed high-dose volume. The dose beyond the 130 line reduces rapidly (51).

Complications of radiation treatment include osteoradionecrosis of the surrounding bone, EAC stenosis, and sensorineural hearing loss. Necrotizing otitis externa progressing to skull base osteomyelitis has been described with fatal outcome if untreated. Inadvertent injury to the eyes, brainstem, and central cortex (Fig. 32) may occur because of the radiation fields required for extensive disease control. This type of injury typically occurs in a delayed manner (i.e., ra-



FIG. 31, Typical radiation field plan for treatment of external ear canal and middle ear. High-dose volume is delivered to line 130. Dose beyond this reduces rapidly, minimizing radiation effect to brainstem and cranial nerves.



FIG. 32. Coronal and axial computed tomography scans demonstrate radiation necrosis affecting right temporal lobe.

diation-induced cataracts, progressive brain and brainstem necrosis). The facial nerve is usually not affected, although progressive cochleolabyrinthitis may involve the inner ear. Temporal bone malignancy tends to have an unpleasant natural history if left untreated. With time, the tumor becomes gradually larger, more painful, ulcerated, and necrotic. Often a malodorous discharge is socially unacceptable. Once the dura is invaded, intolerable pain makes adequate analgesia an imperative part of the management of these patients. A well planned resection may not provide cure, but will result in good palliation of pain secondary to recurrent or residual disease.

CONCLUSIONS

Temporal bone carcinoma is a relatively rare disease. It is a difficult disease to treat and should be managed at major centers with experienced staff, for several reasons. It is difficult for anyone outside these centers to acquire enough experience to manage the complexities of the problem. Concentration of experience also allows patterns to be observed that may be pertinent to staging and trials of different treatment modalities.

The main problems in the treatment of this disease are:

1. Early diagnosis: General otolaryngologists and other physicians treating ear disease need continuing education about the often subtle presentation of these neoplasms, and need to maintain a high index of suspicion.
2. Inadequate staging system: It is difficult to compare outcomes of different treatment modalities without a common language in which to describe the extent of the disease. Also, lack of a staging system makes prognostication less scientific.
3. Frequently, dilemmas arise with the management of the carotid artery and facial nerve. These have been addressed in the text, but are another reason these lesions should be treated by experienced surgeons.

Free and myocutaneous flaps have reduced complications such as CSF leaks and wound infections, and improved cosmesis. This has probably been the most significant advance in the surgical treatment of these lesions in the recent past.

Combined radiation therapy and surgery should be considered the treatment of choice for all but early lesions.

REFERENCES

1. Arena S, Keen M. Carcinoma of the middle ear and temporal bone. *Am JOtolaryngol* 1988;9:351-356.
2. Politzer A. *Textbook of diseases of the ear.* London: Balliere Tindall & Cox. 1883. Cassells JP, translator.
3. Lewis JS. Cancer of the ear. *Laryngoscope.* J960;70:551-560.
4. Lederman M. Malignant tumors of the ear. *J Laryngol Otol* 1965:79:85-119.
5. Nuss D. Janecka I, Sekkar L, et al. Craniofacial disassembly in the management of skull base tumors. *Otolaryngol Clin North Am* 1991;24:1465-1497.
6. Shah J. Indications, complications, sequelae and results of cranial base surgery. In: *Proceedings of the 4th international conference on head and neck cancer.* Arlington, VA: The Society of Head and Neck Surgeons, 1996:74-78.
7. Conley J, Schuller D. Malignancies of the ear. *Laryngoscope* 1976;86:1147-1163.
8. Arriaga M, Curtin H, Takahashi H, et al. Staging proposal for external auditory meatus carcinoma based on the preoperative clinical examination and computed tomography findings. *Ann Otol Rhinol Laryngol* 1990;99:714-721.
9. Chen KTK, Dephner LP. Primary tumors of the external and middle ear. *Archives of Otolaryngology* 1978;104:247-252.

10. Boland J, Paterson R. Cancer of the middle ear and the external auditory meatus. *J Laryngol Otol* 1955;69:468-478.
11. Shih L, Crabtree J. Carcinoma of the external auditory canal; an update. *Laryngoscope* 1990;100:1215-1218.
12. Conley J. Cancer of the middle ear. *Annals of Otolaryngology* 1965;74:555-572.
13. Tucker W. Cancer of the middle ear. *Cancer* 1965;! 8:642-650.
14. Stell P. Epithelial tumors of the external auditory meatus and the middle ear. In: Booth J , ed. *Scott Brown's otolaryngology.* 4th ed. London: Butterworth, 1987:534-545.
15. Ruben R, Thaler S, Holzer J. Radiation induced carcinoma of the temporal bone. *Laryngoscope* 1977;87:1613-1621.
16. Applebaum E. Radiation-induced carcinoma of the temporal bone. *Otolaryngol Head Neck Surg* 1979:87:604-609.
17. Parsons H, Lewis L. Subtotal resection of the temporal bone for cancer of the ear. *Cancer* 1954;7:995-1000.
18. Goodwin W, Jesse R. Malignant neoplasms of the external auditory canal and temporal bone. *Archives of Otolaryngology* 1980; 106:675-679.
19. Stell P, McCormick M. Carcinoma of the external auditory meatus and middle ear: prognostic factors and a suggested staging system. *J Laryngol Otol* 1985;99:847-850.
20. Paaske P, Witten J, Schwer S, et al. Results in treatment of carcinoma of the external auditory canal and middle ear. *Cancer* 1987; 59:156-160.
21. GW. Tumors arising from glandular structures of the external auditory canal. *Laryngoscope* 1983;93:326-340.
22. Cannon CR, McLean WC. Salivary gland choristoma of the middle ear. *Am J Otol* 1980; 1:250-252.
23. Hociota D, Atamar T. A case of salivary gland choristoma of the middle *car. J Laryngol Otol* 1975;89:1065-1068.
24. Perzin K, Gullane P, Conley J. Adenoid cystic carcinoma involving the external auditory canal. *Cancer* 1982;50:2873-2883.
25. Goebel JA, Smith PG, Kemick JL. Primary adenocarcinoma of the temporal bone mimicking paragangliomas: radiographic and clinical recognition. *Laryngoscope* 1987;96:231-238.
26. Wiatrak BJ, Pensak ML. Rhabdomyosarcoma of the temporal bone. *Laryngoscope* 1989;99:1188-1192.
27. Canalis R, Gussen R. Temporal bone findings in rhabdomyosarcoma with predominantly petrous involvement. *Archives of Otolaryngology* 1980:106:290-293.
28. Raney RB, Lawrence W, Maurer H, et al. Rhabdomyosarcoma of the ear in childhood. *Cancer* 1983;51:2356-2361.
29. May J, Fisch U. Neoplasms of the ear and lateral skull base. In: Bailey BJ, ed. *Head and neck surgery-otolaryngology.* Philadelphia: JB Lippincott, 1993:1564-1577.
30. Freidmann I, Radcliffe A. Otosclerosis associated with malignant melanoma of the ear. *.1 Laryngol Otol* 1954;68:114-119.
31. Hasegawa M, Nishijima W, Watanabe I, et al. Primary chondroid chordoma arising from the base of the temporal bone. *J Laryngol Otol* 1985;99:485^t89.
32. Krouse J, Nadol J, Goodman M. Carcinoid tumors of the middle ear. *Ann Otol Rhinol Laryngol* 1990;99:548-552.
33. Woodman G, Jurco S, Alford B, et al. Verrucous carcinoma of the middle ear. *Archives of Otolaryngology* !98l;107:63-65.
34. Cunningham M, Curtin H, Jaffe R, Stool S. Otologic manifestations of Langerhan's histiocytosis. *Archives of Otolaryngology* 1989;! 15:807.
35. Atkinson D, Jacobs L, Weaver A. Elective carotid resection for squamous cell carcinoma of the head and neck. *Am J Surg* 1984;148:483^88.
36. Sekhar L, Sen C, Jho H. Saphenous vein graft bypass of the cavernous internal carotid artery. *JNeurosurg* 1990;72:35-41.
37. Erba S, Horton J, Latchaw R, et al. Balloon test occlusion of the internal carotid artery with stable xenon/CT cerebral flow imaging. *AJNR Am J Neuroradiol* 1989;9:533-538.
38. Prasad S, Janecka I. Efficacy of surgical treatments for squamous cell carcinoma of the temporal bone: a literature review. *Head Neck* 1994;110:270-280.
39. Montgomery WW. *Surgery of the upper respiratory tract.* Vol. 1. Philadelphia: Lea & Febiger, 1971:471.
40. The American Society for Head and Neck Surgery and The Society of Head and Neck Surgeons. *Clinical practice guidelines for the diagnosis and management of cancer of the head and neck.* The American Society for Head and Neck Surgery and The Society of Head and Neck Surgeons, 1996.
41. Ariyan S, Sasaki C, Spencer D. Radical en-bloc resection of the temporal bone. *Am J Surg* 1982; 142:443^447.
42. Irish J, Gullane P, Gentille F, et al. Tumors of the skull base: outcome and survival analysis of 77 cases. *Head Neck* 1994;16:3-10.
43. Alberktsson T, Branemark P, Jacobson M, et al. Present clinical applications of osseointegrated percutaneous implants. *Plast Reconstr Surg* 1987:9:721-731.
44. Malata CM, Cooler RD, Towns GM, Batchelor AGO. Petrosectomy for invasive tumors: surgery and reconstruction. *Br J Plast Surg* 1996;49:370-378.
45. Fisch U, Mattox D. Petrosectomy and facial nerve rehabilitation in malignant tumors of the retromandibular fossa. In: Bull TR, Myers E, eds. *Plastic reconstruction of the head and neck.* London: Butterworth. 1986:79-97.
46. May M, Sobol S. Reanimation of the paralysed face without the facial nerve. In: Sekhar LN, Janecka IP, eds. *Surgery of cranial base tumors.* New York: Raven Press, 1993; 449-460.
47. May M. Gold weight and wire spring implants as alternatives to tarsorrhaphy. *Archives of Otolaryngology* 1987;13:656-660.
48. May M. Paralysed eyelid reanimation with a close eyelid spring. *Lanngoscope* 1988:98:382-385.
49. Arthur K. Radiotherapy in carcinoma of the middle ear and external auditory canal. *J Laryngol Otol* 1976;90:753-762.
50. Lederman M, et al. Cancer of the middle ear; technique of radiation treatment. *Br J Radial* 1965;38(456):895-905.
51. Harwood A, Keane T. Malignant tumors of the temporal bone and external ear: medical and radiation therapy. In: Alberti PW, Ruben RJ. eds. *Otologic medicine and surgery.* Vol. 2. New York: Churchill Livingstone, 1988:1389-1408.

Surgeiy of the Skull Base, edited by Paul *1.* Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 21

Transcervicomastoid Approach

Gale L. Gardner, Edwin W. Cocke, Jr., andjon H. Robertson

Historically, the surgical management of tumors involving the jugular foramen has constituted a difficult surgical problem. Beginning in the early 1970s, the authors began a multidisciplinary effort to overcome the problem. Using the methods of head and neck surgery, otologic surgery, and neurosurgery, a procedure has evolved that is described in this chapter; it is termed the transcervicomastoid (TCM) approach to the jugular foramen. The authors discuss this evolution of the procedure and the surgical efforts made by others on which the procedure is based. Diagnosis, preoperative evaluation and treatment, surgical anatomy and technique, and outcome and complications are presented.

INDICATIONS AND ALTERNATIVE FORMS OF TREATMENT

The TCM approach is indicated for the removal of any tumor or lesion involving the jugular bulb and adjacent skull base that is thought to be suitable for surgery. The authors have used the procedure for the following conditions:

Types of Tumors	Number
Carcinoma	2
Chondrosarcoma	1
Glomus jugulare tumor	32
Glomus jugulare and vagale tumors	3
Glomus jugulare, vagale, and carotid body tumors	1
Glomus jugulare and carotid body tumors	2
Meningioma	3
Neurofibroma	2
Neuroma of cranial nerve X	1
Total	47

The authors believe surgery to be contraindicated when the patient's general health or age precludes a major surgical procedure, when intracranial extension is deemed to be nonresectable, when the tumor involves the vagus nerve and the opposite vagus is nonfunctional, and when internal carotid artery involvement is present and there is inadequate collateral circulation as demonstrated by balloon occlusion test.

Alternative treatments for glomus tumors include radiation therapy and embolization. Although the authors now use preoperative embolization in nearly every instance in which they perform TCM, it may also be considered for palliative purposes under unusual circumstances. In their early experience with TCM for large glomus tumors, the authors used preoperative radiation therapy to reduce vascularity. They continue to use radiation therapy alone for glomus tumor management in patients unable to undergo surgery because of age or poor general health.

EVOLUTION OF THE TRANSCERVICOMASTOID PROCEDURE

This procedure is designed to accomplish tumor removal by (a) resection of overlying soft tissue, (b) removal of bone from over the jugular bulb, and (c) resection of the jugular bulb with *en bloc* removal of tumors involving the bulb or located adjacent to it.

Efforts to develop a systematic surgical approach to the jugular foramen and adjacent skull base began shortly after Guild (1) and Rosenwasser (2) identified glomus tumors as occurring in the temporal bone in the early 1940s. In 1949, Lundgren (3) suggested resection of the jugular bulb. He made reference to Seiffert, who in 1934 reported a case in which he had explored the bulb in a patient having a jugular foramen syndrome, and found tumor filling the bulb.

In 1951 Weille and Lane (4) correctly recognized that glomus tumors may arise from the dome of the jugular bulb. They recommended removal of bone from around the tumor so as to avoid trauma to the tumor itself, but did not recom-

G. Gardner, E. W. Cocke, Jr.: Department of Otolaryngology, Head and Neck Surgery, The University of Tennessee, Memphis, The Health Science Center, Memphis, Tennessee 38103.

J. H. Robertson: Department of Neurosurgery, The University of Tennessee, Memphis. The Health Science Center, and Semmes-Murphey Clinic, Memphis, Tennessee 38103.

mend removal of the bulb because of the risk of significant hemorrhage.

Capps (5) in 1952 reported a case in which he had approached the skull base for removal of a glomus tumor. He described mobilizing the facial nerve, packing the lateral sinus, ligating the upper end of the internal jugular vein, and attempting unsuccessfully to remove the jugular bulb.

In 1961, Gastpar (6) reported resection of the jugular bulb. Shapiro and Neus (7) in 1963 described operating on a patient with recurrent glomus tumor of the jugular bulb in which they had used an extended incision, rerouted the facial nerve, exposed the hypotympanum and bulb, and accomplished total tumor removal without significant complications and with minimal blood loss.

Gejrot (8) in 1965 described a similar procedure in four cases. He described packing of the upper sigmoid sinus and removal of the lateral wall of the sinus inferiorly, with preservation of the medial (dural) wall to avoid entry into the posterior fossa. He ligated the internal jugular vein in the neck and isolated and removed the tumor, working both from above and below.

In 1968, House (9) reported extensive experience removing glomus tumors through the mastoid and extended facial recess with preservation of the posterior bony canal wall, but without rerouting of the facial nerve.

Portmann (10) in 1968 described removal of a large glomus tumor of the skull base with extension both into the temporal bone and posterior fossa, and pointed out the advantages of combined otologic and neurosurgical participation. In 1974, Glasscock et al. (11) reported on their experience in which they had combined the methods of House and Shapiro, and had carried out tumor removal with transposition of the facial nerve and preservation of the posterior bony ear canal with exposure through an extended facial recess exposure.

The current authors (12) reported their experience treating 10 patients with glomus tumors of the skull base in 1976 to The Triological Society, and published this in 1977. The authors emphasized removal of soft tissue from the lateral base of the skull adjacent to the jugular foramen, wide removal of bone from over the mastoid and lateral skull base with exposure of the jugular bulb, transposition of the facial nerve, lig-ation of the upper sigmoid with resection of the lateral wall of the sigmoid inferiorly, ligation of the internal jugular vein in the neck, and resection of the tumor with attempted preservation of cranial nerves IX through XII.

Simultaneously in 1977, Fisch (13) described a similar procedure, but emphasized infratemporal fossa exposure to facilitate exposure of the internal carotid artery and to allow extension of the exposure anteriorly for more extensive and anteriorly placed tumors.

Since that time, the authors and others have continued to use these techniques with various modifications for the surgical management of various lesions occurring in and adjacent to the jugular foramen. It has been the authors' experience that wide exposure of the tumor using the methods developed as early as the 1940s, and the use of preoperative embolization combined with careful identification of the lower cranial nerves at the jugular foramen, allow total removal of a high percentage of tumors occurring in this area, with acceptable morbidity in properly selected patients.

TABLE 1. *Most common presenting symptoms for tumors of the jugular foramen*

Symptom	No. of cases	Mean duration (mo)
Tinnitus	38	48
Hearing loss	35	66
Dizziness	26	41
Ear pressure	22	76
Ear pain	21	28

DIAGNOSIS AND IMAGING

The clinical presentation of tumors originating in or proximate to the jugular bulb is related not only to the adjacent neurovascular structures present in this area, but to the nature of the tumor mass that is involved. In the authors' series, glomus tumors predominate and produced symptoms reflecting their tendency toward local invasiveness.

This series constitutes 46 patients who underwent surgery for tumors of the jugular foramen, with 1 patient undergoing bilateral surgery for bilateral tumors. All underwent a work-up that included a medical history, head and neck examination, audiometric evaluation, and radiographic evaluation. Sampling of the tumor for biopsy through the ear canal was performed before treatment early in this study when preoperative x-ray therapy was being used, for confirmation of type of tumor. All but a few patients in this series underwent preoperative evaluation and postoperative follow-up by a single internist.

The most common presenting symptoms in this series have been tinnitus, hearing loss, dizziness or imbalance, ear blockage, and otalgia, with a mean duration of 53 months (Table 1). The incidence of preoperative cranial nerve dysfunction is indicated in Table 2.

Early in this series, radiographic examination included plain films of the skull base and occasional arteriography and venography. Computed tomography became available in

TABLE 2. *Preoperative cranial nerve dysfunction*

Cranial nerves	No. of cases
VI	1
VII	6
VIII	23
IX	6
X	12
XI	11
XII	12



FIG. 1. Magnetic resonance image. *Arrow* indicates soft tissue mass in left jugular foramen area.

the late 1970s and was used with occasional angiography. The authors now depend on magnetic resonance imaging for diagnosis and operative planning (Fig. 1), with occasional computed tomography for bone definition (Fig. 2). Angiography is used if embolization is planned, or if the internal carotid artery is significantly involved (Fig. 3).



FIG. 2. Computed tomography scan. *Arrow* indicates bone defect in left jugular foramen area.



FIG. 3. External carotid arteriogram. Note vascular mass typical of glomus jugulare tumor.

PREOPERATIVE MEDICAL EVALUATION

Preoperative medical evaluation in patients with jugular foramen tumors is predicated on the high incidence of lower cranial nerve deficit before and after surgery in these patients. Emphasis is placed on preoperative evaluation of the upper gastrointestinal tract and lungs because of the high risk of postoperative aspiration secondary to injury to the vagus nerve, particularly in patients with preexisting disease, including hiatal hernia, gastroesophageal reflux, and chronic pulmonary disease. Early in this series, tracheostomy was performed prophylactically in such situations, but much less frequently now.

In older patients with large tumors, in whom blood pressure fluctuation would constitute a problem, a preoperative 24-hour urinary study for norepinephrine and serotonin secretion is performed to rule out a catecholamine-secreting tumor. The authors believe this study should be carried out regardless of whether the patient has a clinical history suggesting pheochromocytoma or carcinoid apudoma. Because medications and physical stress may invalidate test results, time must be allowed for performance of this test under suitable conditions to produce valid results. The alternative is to run the risk of tachycardia and hypertension due to release of norepinephrine by a pheochromocytoma, or hypotension due to the vasodilatory effects of a carcinoid apudoma, as a result of tumor manipulation.

Because of the possibility of significant blood loss, the authors have patients bank two or more units of autologous blood. Hemorrhagic disorders are screened for simultaneously, and treated before surgery. Aspirin is not allowed within 1 week of surgery.

Patients with essential hypertension, in the absence of renal contraindication, are given angiotensin-converting enzyme inhibitors before surgery, thus allowing perioperative and postoperative continuity of intravenous therapy with enalapril. When norepinephrine secretion is identified, a-adrenergic antagonist treatment for 7 to 10 days may control blood pressure elevation. Short-half-life (3-adrenergic antagonist is added before and through surgery for control of arrhythmia.

After surgery, the authors emphasize elevation of the head of the patient's bed to prevent cerebrospinal fluid leakage and aspiration. When aspiration is so great a problem as to interfere with deglutition, and nutrition is impaired, a percutaneous endoscopic gastrostomy is placed, either before surgery if this problem is strongly anticipated, or, more frequently, after surgery when the problem occurs.

Preoperative antibiotic treatment is with cefazolin (a cephalosporin), 1 g given intravenously the night before surgery, the morning of surgery, and every 8 hours after surgery.

EMBOLIZATION AND RADIATION THERAPY

Early in this series, the authors treated patients with preoperative x-ray therapy in an effort to reduce vascularity at surgery. Currently, irradiation is used only as a primary mode of therapy for patients who are not surgical candidates because of advanced age or severity of health problems. Sixteen patients in this series have received preoperative radiation therapy.

The authors have used preoperative embolization since the 1970s. It has been particularly helpful with the advent of newer embolization techniques using microcoils and polyvinyl alcohol as the embolizing agents. The authors have noted a striking reduction in bleeding during surgery, and now use embolization on a virtually routine basis. Twelve of the patients in this series received preoperative embolization (Fig. 4).



FIG. 4. External carotid arteriogram after embolization. Compare with Fig. 3 (same patient); note marked reduction in vascularity.

The authors prefer to embolize those patients with glomus jugulare tumors before surgery. The procedure is performed 1 to 2 days before surgery, and is carried out using subselec-tive arterial catheterization and angiography with a 3-Fr microcatheter to embolize the external carotid branches feeding the tumor. The embolizing material most commonly used is polyvinyl alcohol with or without platinum microcoils.

The most frequent problems associated with this procedure have been nausea with vomiting and facial pain, which have typically resolved within 12 to 18 hours after the procedure. There have been no instances of cerebral injury or cranial nerve dysfunction in this series.

ANESTHESIA CONSIDERATIONS

Anesthesia should be carried out in anticipation of a prolonged surgical procedure with the possibility of sudden, dramatic blood loss or air aspiration in a patient subject to probable lower cranial nerve stimulation as well as epinephrine or serotonin secretion. In addition to basic anes thetic monitoring, an arterial line, Foley catheter, peripheral nerve stimulator, and central venous pressure line are placed. Because the jugular vein on one side, if not occluded by tumor, will be surgically divided, the authors use a peripheral vein for central venous pressure monitoring, with placement of a femoral introducer and passage of a Bungedin-Albin air aspiration catheter into the right atrium. A Zoll external pacemaker is also placed to address lower cranial nerve stimulation.

The patient is placed on an egg-crate-padded operating table, with thigh-length thromboembolic stockings and sequential compression boots placed on the lower extremities. Unless the patient is advanced in age or cachectic, an external warming device has not been used.

Anesthesia is induced and maintained by a combination of large doses of narcotic at the beginning of the procedure coupled with reduced inhalation agent and the inclusion of a continuous nonpolarizing muscle relaxant infusion. An armored endotracheal tube is placed in anticipation of frequent need for manipulation of the head.

The vasomotor effects of secreting tumors have been managed with /8 blockade and antihypertensive agents. Esmolol is the authors' agent of choice for the former, and intravenous nicardipine for the latter.

The goal is to have the patient as alert as possible at the end of the procedure to assess neurologic status promptly. /3 Blockade and antihypertensive treatment are continued into the postoperative period as indicated.

SURGICAL ANATOMY

An understanding of the neurovascular structures of the neck is important to the exposure of the jugular bulb. Inferior to the bulb, the lower cranial nerves are close to the facial and hypoglossal nerves, the internal jugular vein, and internal carotid artery. Successful dissection in this region is enhanced by recognition of several relatively constant anatomic relationships. The stylomastoid foramen through which the facial nerve exits the skull base is located postero-lateral to the base of the styloid process. Cranial nerve IX occupies the medial aspect of the jugular foramen, extends into the neck, and passes lateral to the internal carotid artery. Cranial nerve XI exits the jugular foramen, first lying medial to the jugular vein, and then passing over the anterior surface of that structure before continuing inferiorly under the medial surface of the sternocleidomastoid muscle. Cranial nerve XII exits the hypoglossal canal, passes behind the vagus nerve, and then courses anteriorly toward the tongue. In summary, the nerves exiting the jugular foramen all travel medial to the jugular bulb. In the neck, cranial nerves VII, IX, and XII pass lateral to the internal carotid artery. Cranial nerve X courses in the groove between the jugular vein and the internal carotid artery. Cranial nerve XI crosses anterior to the jugular vein (occasionally posterior) on its way through the ster-nomastoid muscle, to the posterior triangle of the neck and the trapezius.

The jugular foramen, located in the posterolateral skull base, is bounded anterolaterally by the petrous portion of the temporal bone and posteromedially by the occipital bone. The two jugular foramina are not symmetric, the right side being larger in over two thirds of cases (14,15). This is believed to result from the asymmetry in the size of the transverse and sigmoid sinuses. The jugular foramen is divided into two segments by a fibrous septum, which is infrequently ossified, connecting the jugular process of the occipital bone with the jugular spine of the petrous bone. Di Chiro and colleagues (14) studied 129 dry skulls and noted a bony septum unilaterally in 13.2% of these, and bilaterally in 4.7%. The posterolateral segment, designated the pars venosa, is the larger of the two and contains the jugular bulb, cranial nerves X and XI, as well as the posterior meningeal artery. The anteromedial segment of the jugular foramen is smaller, is designated the pars nervosa, and contains cranial nerve IX and the several venous channels of the inferior petrosal sinus.

Although the exact anatomic location of cranial nerves IX, X, and XI as they traverse the jugular foramen may be variable, in essentially every case they pass medial to the jugular bulb. Cranial nerve IX travels alone, and is located medially and anteriorly to the cranial nerves X and XI, which are closely adherent. Cranial nerve IX exits the skull through a separate bony canal in 6% of cases (15).

The venous structure of the jugular foramen comprises the medial extension of the horizontal limb of the sigmoid sinus into the venous jugular bulb, which extends superiorly, and then inferiorly to pass into the neck as the internal jugular vein. The jugular bulb is housed in the bony jugular fossa, the superior portion of which separates the dome of the jugular bulb from the hypotympanum of the middle ear. The superior extent of the jugular bulb above the level of the horizontal segment of the sigmoid sinus varied between 0.25 and 0.75 in. in a study by Graham (16). The thickness of the bony covering over the dome of the jugular bulb depends on the size of the bulb, a small bulb having a relatively thick bony roof, whereas with a large bulb, the bone may be thin or even dehiscent, so that the venous wall of the bulb may occasionally reach the round window (16). The fallopian canal and contained facial nerve lie just lateral to the jugular bulb, and may be as close as 1 mm to the bulb.

The largest vessel to empty into the jugular bulb, with the exception of the sigmoid sinus, is the inferior petrosal sinus, which opens into the anterior aspect of the jugular bulb usually by multiple channels that pass through the fibrous septum between the pars nervosa and venosa. Occasionally, the vein of the cochlear aqueduct or a branch from the occipital sinus empties into the jugular bulb as well (16). These multiple channels constitute an expected source of bleeding during removal of the tumor and attached jugular bulb from the surrounding jugular fossa and enclosed cranial nerves. Controlled dissection of the tumor from the cranial nerves depends on management of these vascular channels.

SURGICAL TECHNIQUE

Skull Base Exposure

The patient is placed in supine position on the operating table with the head raised 30 degrees to reduce bleeding. The patient's head is placed at the "foot" end of the table in preparation for the otologic phase of the procedure to follow. The shoulders are slightly elevated with padding to improve visibility of the skull base. Hair is shaved from about the ear, neck, and chest to the nipple line. The surgical area is thoroughly cleansed and prepared with agents of the surgeon's choice.

Lidocaine 1% with epinephrine 1:100,000 is injected into the skin and subcutaneous tissues of the upper neck, mastoid, parotid gland, and facial nerve regions, to reduce bleeding during the skin incision and soft tissue phase of the procedure.

The surgical area is again prepared and covered with transparent and cloth drapes that are sutured in place. The abdomen is also prepared and draped in anticipation of harvesting adipose tissue for later wound closure.

Two suctions, a Malis cautery unit, and a Shaw cautery knife should be available during the initial phase of the procedure. The latter has been found to be useful in dissecting the structures of the neck, and particularly in dissecting the adjacent soft tissues from bone as well as from vital structures.

An oblique incision is made through the skin, subcutaneous tissues, and platysma of the upper neck. This incision is placed in an obvious skin crease and extends from the postauricular region almost to the hyoid bone below the level of the tail of the parotid gland. The superior skin flap is elevated, with the skin and subcutaneous tissues being elevated to the mastoid bone and from the parotid fascia to the region of the mandibular angle. A periosteal flap is elevated inferi-orly and kept in continuity with the sternocleidomastoid muscle and later used in wound closure. The greater auricular nerve is identified for possible later use as a nerve graft.

The main trunk of the facial nerve is exposed by elevating the tail of the parotid gland from the lateral surface of the sternocleidomastoid muscle and detaching the gland from the cartilaginous canal of the external ear to the tympanomastoid fissure. The sternocleidomastoid muscle is partially detached from the mastoid bone as the parotid tail is retracted forward and the mastoid attachment of the posterior belly of the digastric muscle is exposed (Fig. 5).

FIG. 6. Exposure of internal jugular vein. Note mastoid tip being resected with Gigli saw.





FIG. 5. Superficial dissection of skull base area. Note extensive dissection of facial nerve to its first genu. The authors no longer do this, but rather leave the nerve attached to adjacent soft tissue.

The main trunk of the facial nerve is identified above and medial to the anterior superior attachment of this muscle to the mastoid bone, and deep to the tympanomastoid fissure. The facial nerve is no longer dissected to its first major division, but rather is left attached to the adjacent soft tissue, as advocated by Brackmann (17). The mastoid tip is removed with a Gigli saw after complete detachment of the sternocleidomastoid muscle and the posterior belly of the digastric muscle from it. Ligation of the occipital artery may be required (Fig. 6).

The styloid process is identified and its attached tendons resected. With the facial nerve and the internal jugular vein in clear view, the styloid process is resected from the skull base with a rongeur. This resection is carried out medial to the stylomastoid foramen and as close to the jugular foramen as possible. The tympanic bone may be removed at this point, or may be removed during the otologic phase to follow.

The neurovascular structures of the upper neck are mobilized as a unit and dissected superiorly to the carotid canal and jugular foreman. The tributaries of the internal jugular vein are mobilized and ligated. Ligation of the internal jugular vein in the neck is deferred until immediately before tumor removal.

The soft tissues of the base of the skull are resected to permit bony exposure of the posterior three fourths of the circumference of the jugular foreman (Fig. 7). The rectus capi-tis lateralis muscle and the atlantooccipital ligaments are detached from the jugular process of the occipital bone.

An elevator is used to separate the jugular vein from the posterior margin of the jugular foramen and partially from the neurovascular bundle anteriorly. This separation is completed at a later stage when the vein is excised. If the neck is short, the authors prefer to amputate the lateral process of the first cervical vertebra. Before this, the soft tissue on the lateral surface of the transverse process is divided, with care taken to avoid injury to the vertebral artery.

Temporal Bone Exposure

The otologic phase of this procedure is begun by first repositioning the patient and bringing in the microscope and other otologic equipment. For tumors that are 2 cm in diameter or smaller, the membranous ear canal is preserved. The neck incision is continued superiorly as a wide, C-shaped postauricular incision. The soft tissues are elevated and the auricle turned forward. A high-speed electric drill is used to perform a simple mastoidectomy. The sigmoid sinus and mastoid segment of the facial nerve are skeletonized (Fig. 8).



FIG. 7. Soft tissue exposure of skull base. Note that dissec-• tion extends to the margin of the jugular foramen.



FIG. 8. Initial simple mastoid exposure. Note that membranous and bony ear canal are retained. The sigmoid sinus and mastoid segment of the facial nerve have been skeletonized. Horizontal and posterior semicircular canals are visible.

For a tumor larger than 2 cm, the original neck incision would have been continued as a wide, C-shaped postauricular incision initially, with transection of the membranous ear canal at the bony cartilaginous junction, as shown in Fig. 9. Cartilage is excised from the membranous meatus and the meatus closed primarily in two layers.

A diamond bur is used to remove the remaining bone from over the upper two thirds of the sigmoid sinus and from over the mastoid and tympanic segments of the facial nerve (see Fig. 9). If the surgery is being performed for a glomus tumor, and if the tumor has extended posteriorly into the mastoid air cells, either superficial or deep to the facial nerve, great care may be required to differentiate the nerve from the glomus tissue, and to preserve the nerve. The authors are reluctant to sacrifice the facial nerve in this situation when dealing with a benign tumor.

For tumors larger than 2 cm in diameter, the posterior bony canal wall is now removed. The facial nerve is elevated from the fallopian canal, extending from the geniculate ganglion to the stylomastoid foramen, and then turned forward



FIG. 9. Dissection for large tumor. Membranous ear canal is being transected and auricle turned forward. Bone has been removed from over the upper sigmoid sinus and from over the mastoid and tympanic segments of the facial nerve.

(Fig. 10). The skin of the external auditory canal is elevated to the level of the tympanic membrane, the middle ear entered, and the incudostapedial joint and tensor tympani tendon sectioned. The ear canal skin, tympanic membrane, malleus, and incus are removed.

For small tumors, the canal wall is preserved, as shown in Fig. 9. As Brackmann has recommended (17), large scissors are used to dissect the nerve and its adjacent soft tissue from the underlying bone. Only the mastoid segment of the facial nerve is mobilized, as Farrior has described (18).

Bone is now removed from the posterolateral skull base, including the base of the lateral aspect of the temporal bone and the jugular process of the occipital bone. Specific landmarks that are removed include the tympanic bone, digastric groove, stylomastoid foramen, posterolateral lip of the jugular foramen, and the lateral wall of the jugular fossa and hypotympanum. This bone removal exposes the soft tissue of the lower one third of the sigmoid sinus, jugular bulb, and tumor within the hypotympanum (see Fig. 10).

The orifice of the eustachian tube is identified, and its mucosal surface carefully denuded. Bone wax and small pieces of temporalis muscle tissue are used to occlude the eustachian tube. This completes the otologic phase of the tumor exposure, with the sigmoid sinus, jugular bulb, internal jugular vein, and associated tumor fully exposed through the base of the skull.

Tumor Removal and Reconstruction

The internal jugular vein is now ligated beyond any intraluminal tumor extension in the neck, passed beneath the spinal accessory nerve, and dissected to the jugular foramen as the neurovascular structures are retracted anteriorly (see Fig. 10). Two small incisions are made in the dura immediately anterior and posterior to the sigmoid sinus, well above any intraluminal tumor mass. Two silk sutures are carefully passed through one of these incisions, into the subarachnoid space medial to the sinus, and brought out through the second dural incision, and the sinus ligated (Fig. 11). The lateral wall of the sigmoid sinus is then resected inferiorly from the point of sinus ligation down to the tumor (Fig. 12).



FIG. 10. Continued dissection for large tumor. Facial nerve has been elevated from fallopian canal and turned forward. Bone has been removed from the posterolateral skull base, exposing the lower sigmoid, jugular bulb, and tumor within the hypotympanum. Note that the internal jugular vein has been divided in the neck and dissected to the jugular foramen.

Typically, there is a preserved plane of dissection between the medial surface of the tumor and the lower cranial nerves. Working circumferentially in this plane, using sharp tissue dissection, the surgeon gently dissects the tumor mass free (Fig. 13). Care should be taken to avoid damage to the lower cranial nerves from excessive bipolar coagulation and overpacking with Surgicel. Often there is brisk venous bleeding at this point from the several entrances of the inferior pet-rosal sinus into the jugular bulb. This should be controlled by packing Surgicel into the venous openings of the sinus (Fig. 14). The tumor cavity is inspected, and any remaining tumor remnants are removed (Fig. 15). If tumor has extended into the posterior fossa, it is removed in continuity with the primary tumor mass in the skull base. If it is necessary to resect dura, a dural graft of pericranium or temporalis fascia is sutured in place.

As Fisch has described (13), a small diamond drill is used to create a groove in the anterior attic wall, and the proximal tympanic segment of the facial nerve is permanently placed within this groove (see Fig. 14) The authors perform this step of the procedure at the time of displacement of the nerve from the fallopian canal, thus protecting it from injury throughout the remainder of the procedure.



FIG. 11. Sigmoid sinus has been ligated. Note that dural openings anterior and posterior to the sinus are individually closed with sutures.



FIG. 12. Lateral wall of the sigmoid sinus is resected inferi-orly to the level of the tumor.

If the tumor involves the carotid canal, bone over the lower aspect of the anterior wall of the mesotympanum adjacent to the eustachian tube orifice may be removed to allow exposure of this portion of tumor (see Fig. 15). This step may be performed after primary tumor removal, or may be earned out earlier in the procedure as bone is removed from the surface of the tumor.

The middle ear and mastoid are carefully inspected for residual tumor, which is removed separately, along with any remaining remnants of mucosa. When the posterior canal wall has been removed for a larger tumor, the mastoid and middle ear space is packed with fat and covered by downward rotation of the posterior temporalis muscle and upward mobilization of the previously prepared sternocleidomastoid musculoperiosteal flap. For smaller tumors with preservation of the canal wall, adipose tissue is placed only in the tumor bed, and the middle ear either left undisturbed or the os-sicular chain and tympanic membrane reconstructed, depending on the extent of the tumor into the middle ear.

The skin edges are closed in layers, and a Hemovac drain placed into the subcutaneous plane. A spinal drain is placed at the end of the procedure if a dural graft was required, to avoid postoperative cerebrospinal fluid leakage.



FIG. 13. Tumor dissection. Note use of sharp dissection of the jugular bulb and tumor, with lower cranial nerves in clear view.



FIG. 14. Primary tumor mass has been removed. Surgi-cel has been packed into lumen of inferior petrosal sinus. Note groove in anterior attic wall for placement of facial nerve.



FIG. 15. Completed tumor removal. Facial nerve is permanently displaced anteriorly. Note removal of bone over vertical segment of internal carotid artery, inferior to eustachian tube orifice, when carotid canal is involved by tumor.

TABLE 4. *Postoperative complications*

Complication	No. of patients
Surgical death	1
Cerebrospinal fluid leak	§
Meningitis	3
Penumonitis	4
Wound problems	8
Eye problems	9
Sensorineural hearing loss	3
Abdominal wall hematoma	'1
Seizure	1
Hemiparesis	2
Radiation chrondritis of auricle	1
Pulmonary embolus	3
Tumor recurrence	9
Aspiration problem	**10**
Ear canal stenosis	2
Septicemia	. 1
Cranial nerve dysfunction	
VI	4
VI!	43
m	16
X	**29**
XI	**20**
XII	20

Note: These complications occurred in 43 patients.

RESULTS AND COMPLICATIONS

The conditions requiring this surgery have been listed previously. Between September, 1972, and July, 1994, 46 patients underwent 47 primary skull base surgical procedures using variations of the approach described in this chapter. One of these patients had bilateral tumors and underwent bilateral surgery. Three additional patients also had bilateral skull base tumors, but underwent only unilateral surgery. Eight patients had multicentric tumors (Table 3). Forty-two of the 46 patients are alive. Of the four deaths, three were for reasons unrelated to the skull base tumor or to the surgery, one because of pneumonitis and two of cardiovascular causes. The fourth patient died 2 weeks after surgery of a pulmonary embolus secondary to surgery.

Nine patients in this series experienced a total of 13 complications recognized during surgery, including damage to cranial nerves VII (six), IX (one), X (one), and XI (one); injury to the internal carotid artery (two); and displacement of the stapes (two). All postoperative complications are indicated in Table 4.

Of the 47 cases in the series, the facial nerve was anatomically intact after surgery in 38 (81%). In the remaining nine patients (19%), continuity of the facial nerve was lost, and was restored by either end-to-end reanastomosis or by use of a nerve graft. Facial nerve function at the time of the most recent postoperative examination is indicated in Table 5.

Eleven patients have undergone revision surgery (Table

TABLE 3. *Number of multicentric tumors*

Patient	Glomus jugulare	Glomus vagale	Carotid body	Neurofibroma	Meningioma
1	1	1	1		
2	2				
3	1		1		
4				4	1
5	1	1			
6	2	2	2		
7	1	1	1		
8	2	1	2		

TABLE 5. *Postoperative facial nerve function—house classification*

House class	No. of tumors
I	4
II	2
III	28
IV	3
V	0
VI	5
No follow-up	4
Postoperative death	1
Total	47

6). Four patients have received postoperative radiation therapy, and two received postoperative embolization therapy.

Of the 42 living patients in this series, 20 (48%) have been seen in follow-up within the past year; 14 (33%) have been seen within the last 2 to 5 years; 6 (14%) within the last 6 to 10 years; 1 (2%) 12 years ago; and 1 (2%) was never seen after surgery and has been lost to follow-up. Thus, 81% of the patients in this series have been seen in follow-up within the past 5 years (Table 7).

Twenty-six patients (having 27 tumors) were thought to have had total tumor removal at the time of initial surgery, and 20 patients (having 20 tumors) were considered to have had subtotal removals. Tumor recurrence has been diagnosed in 7 of the 26 patients (27%) thought to have undergone total tumor removal initially, with 4 undergoing secondary surgery for this reason. Of the 20 patients undergoing what was considered to be subtotal surgery initially, only 5 have had residual tumor on postoperative imaging studies, and 3 have undergone secondary surgery. Of the total series of 42 living patients, 32 are considered free of disease based on postoperative imaging studies, and 10 are being followed for residual disease.

Further analysis of the 20 patients undergoing what was thought to be subtotal surgery showed 18 to be living at the time of this study. Of these, 7 either had no follow-up imaging studies available or the studies were equivocal, leaving 11 living patients with definitive imaging results. Definite residual disease was shown in 5, but 6 of the original 20 were apparently free of disease. Two of these had received preoperative irradiation, and four had not.

TABLE 6. *Revision surgeries*

Reason for revision surgery	No. of patients	Surgical procedures
Recurrent disease	4	6
Cerebrospinal fluid leakage	3	3
Wound problem	2	5
Hearing problem	3	3
Total	11[a]	17

[a] One patient had two procedures.

DISCUSSION

In the early 1970s, the authors became interested in developing a better method of dealing with jugular foramen tumors in general, and glomus jugulare tumors in particular. The authors proceeded to develop the method described in this chapter, not realizing that many of the features incorporated in this method had been developed a number of years earlier, principally in Scandinavia and the United Kingdom. The authors have attempted to give credit to these efforts in an earlier section of this chapter.

Surgical Approach

It has seemed best to the authors to approach a jugular fossa tumor with surgery directed toward the primary tumor mass in the jugular fossa and foramen, rather than primarily from above through the mastoid. The authors believed that the latter approach would not allow as wide exposure of the primary tumor mass as was preferred. The concept rather was first to remove soft tissue widely over the bone of the skull base that covered the tumor; next, to remove this overlying bone to expose the tumor itself as widely as possible; and finally to remove the tumor. For non-glomus tumors of the jugular foramen that are less vascular, correspondingly less exposure may be required.

The authors have referred to this approach in several ways in the past, originally calling it a combined approach, and later a skull base approach, which they now think is now too generic a term. It is referred to here as a transcervicomastoid approach so as better to identify it as a direct approach through the neck, temporal bone, and skull base. Unless there is extensive involvement of the internal carotid artery, which is usually not the case, there is no necessity to remove the ramus of the mandible and enter the actual infratemporal fossa. The authors therefore do not believe that referring to this and similar approaches as infratemporal fossa approaches is appropriate.

Ancillary Forms of Treatment

Initially, the authors found bleeding to be a major problem in performing this operation for glomus jugulare tumors. For this reason, preoperative radiation therapy was initially used. When embolization became available in the late 1970s, and particularly when its improved methods became available in the 1980s, the authors abandoned preoperative radiation therapy.

In the process, however, x-ray therapy was used as a single mode of therapy for glomus jugulare tumors in older patients and in patients with significant health problems, and the authors have been greatly impressed with how well these patients have done. In fact, several younger, healthy patients were given radiation therapy, with planned surgery to fol-

TABLE 7. *Follow-up results*

Years operated	No. of patients	No. of patients/% seen within: 0–1 year	2–5 years	6–10 years	10–12 years	No follow-up
1972–1974	3	1	1	1	0	0
1975–1979	7	2	2	2	1	0
1980–1984	7	3	3	1	0	0
1985–1989	11	5	3	2	0	1
1990–1994	14	9	5	0	0	0
Total	42	20	14	6	1	1
Percent		48%	33%	14%	2%	2%

low. Radiation, however, became the only form of treatment when the patients refused the planned follow-up surgery. Although the authors do not advocate such treatment for younger patients, it is impressive how well these patients have done over time.

Conservation of Function

The authors have been aware of Glasscock and colleagues' (11) and Farrior's (18) advocacy of preservation of the posterior canal wall with limited mobilization of the facial nerve, to preserve the conductive mechanism and hearing in suitable cases. Until relatively recently, the authors have chosen to remove the posterior canal wall in all cases, to fully mobilize the facial nerve, and to close the ear canal at the meatus. More recently, the authors have pursued Glasscock's and Farrior's concept in treating several patients with smaller tumors, and have been gratified with the results. The authors recommend this approach for smaller tumors, and plan to continue its use.

The authors have referred earlier to Brackmann's method of preserving the soft tissue attachments to the facial nerve to preserve blood supply and facial nerve function. Since adopting this method, the authors have been gratified with the improved postoperative facial nerve function that has resulted, and plan to continue its use as well.

Complications

Early in the authors' series, several instances of postoperative cerebrospinal fluid leakage were encountered that were major problems to manage. Since beginning the use of temporalis muscle and periosteal flaps for closure of the tumor area, this has been a much less frequent and significant problem.

As the results demonstrate, postoperative facial nerve dysfunction has also been a major problem in this series, particularly immediately after surgery. The authors are hopeful that reduced dissection of the facial nerve distal to the stylomastoid foramen, as just discussed, will improve future results.

Recurrence of Tumor

The data indicate a 27% recurrence rate in those patients in whom what the authors believed to be gross total tumor removals were carried out. In the case of glomus tumors, the authors do not believe it is possible, except in rare circumstances, and with very small tumors, to accomplish total histologic tumor removal, even with the sacrifice of adjacent important neurovascular structures; nor do they believe it is justified to sacrifice these structures in glomus tumor surgery, in light of the natural history of these predominantly slow-growing tumors. For example, it would be preferable to treat recurrent disease later, rather than risk life-threatening complications initially by sacrificing the internal carotid artery. The authors suspect that as patients are followed for long periods of time after skull base surgery, particularly for glomus tumors, recurrence rates similar to the one reported here will not be unusual. For this reason, the authors believe that patients who have undergone skull base removal for glomus jugulare tumors should be followed indefinitely. For other tumor types, such as neuromas, long-term follow-up may not be such a critical factor.

Surgical Technique

Early in this series of cases, the surgery was staged because of the duration of the procedure. As the surgical team's experience increased, this became unnecessary, and it is no longer done.

When this procedure was first developed, the authors used a Fogarty catheter to occlude the superior end of the sigmoid sinus while the sinus was divided and then closed. The authors no longer manage the sigmoid sinus in this way, but rather pass two suture ligatures medial to the sinus, and divide the sinus between the ligatures, as Fisch described in his first report (13).

Occasionally in dealing with glomus jugulare tumors, the tumor extends intravascularly either inferiorly down the internal jugular vein or superiorly up the sigmoid and perhaps even into the lateral sinus. Obviously, this must be taken into account and the dissection extended sufficiently to allow complete resection of the intravascular component of the tumor. The authors have not seen this feature with other types of skull base tumors.

Intracranial extension of skull base tumors has not been a significant problem in this series. The authors believe that the wide exposure achieved with this approach, and the participation of a neurosurgeon on the operative team, have allowed intracranial extension to be dealt with in a relatively routine manner.

These data demonstrate a relatively high incidence of immediate postoperative dysfunction of cranial nerves IX through XII, reflecting the fact that tumors of the jugular foramen, particularly glomus tumors, are densely adherent to these nerves. During the authors' early experience, long-term lower cranial nerve dysfunction was a major problem. Because of this, since the early 1980s the authors have made an effort to apply microdissection techniques to separate the tumor from the cranial nerves in the jugular foramen area. The authors believe that this, along with the markedly reduced bleeding seen with more recent embolization techniques, has improved the long-term results in this regard.

If a patient has lost vagus nerve function as a result of pre-operative tumor growth, compensation will have usually occurred before surgery, and these cases are less critical in terms of the necessity to preserve nerve structure. The availability of the percutaneous endoscopic gastrostomy technique during the latter part of this study has been a major benefit in dealing with those situations in which it is necessary to sacrifice a functional vagus nerve, and has virtually eliminated the need for tracheostomy.

The authors have no enthusiasm for sacrificing the internal carotid artery for what are generally benign tumors of the skull base, and have rarely done so. Instances in which this artery has been significantly involved by tumor have been quite infrequent in this series. When such is the case, however, an infratemporal fossa approach for exposure has been used, with an attempt to preserve the artery. When preoper-ative studies indicate significant involvement of the artery by tumor, the authors perform preoperative balloon occlusion studies, and ligate and resect the artery only if feasible and absolutely necessary. The authors have had no experience in repair of the internal carotid artery by grafting.

CONCLUSIONS

During the 25 years that the authors have been engaged in the management of skull base tumors using this approach, they have been gratified by the technical advances that have become available. There is no doubt that further advances will be made. The authors suspect that these will include intravascular interventional methods, which could conceivably make surgery as we know it unnecessary. In the meantime, conventional methods of tumor removal will continue to be used, and will be benefited by adequate surgical exposure. The authors believe that the TCM approach fulfills the requirements for dealing with tumors in this relatively inaccessible area, and recommend its use in appropriate cases.

ACKNOWLEDGMENT

The surgical illustrations were prepared by Daniel Slotton (Los Angeles, CA) at the time of the authors' original report on this work in 1977 (12). Several of the illustrations have been revised by Mr. Slotton for this publication to reflect modifications that have been made in the procedure since its original description.

REFERENCES

1. Guild SR. A hitherto unrecognized structure, the glomus jugularis, in *mun.AnatRec* 1941;79[Suppl 2]:28.
2. Rosenwasser H. Carotid body tumor of the middle ear and mastoid. *Archives of Oto/aryngology* 1945;41:64-67.
3. Lundgren N. Tympanic body tumors in the middle ear: tumors of carotid body type. *Acta Otolaryngol (Stockh)* 1949;37:366-379.
4. Weille FL, Lane CS Jr. Surgical problems involved in the removal of glomus-jugulare tumors. *Laryngoscope* 1951 ;61:448^59.
5. Capps FCW. Glomus jugulare tumors of the middle ear. *J Laryngol Otol* 1952;66:302-314.
6. Gastpar H. Die Tumoren des Glomus Caroticum, Glomus Jugulare-Tympanicum und Glomus Vagale. *Acta Otolaryngol* 1961;[Suppl 167].
7. Shapiro MJ, Neus DK. Technique for removal of glomus jugulare tumors. *Archives of Otolaryngology* 1964;79:219-224.
8. Gejrot T. Surgical treatment of glomus jugulare tumors: with special reference to the diagnostic value of retrograde jugularography. *Acta Otota,yngol* 1965;60:150-!68.
9. House W. Panel discussion (McCabe BF, moderator): Rosenwasser H, House W, Witten RM, Hamberger C-A. Management of glomus tumors. *Archives of Otolaryngology* 1969;89:170-178.
10. Portmann M. In: Hamberger C-A, Wersall J, eds. *Disorders of the skull base region.* New York: John Wiley & Sons, 1969:297-298.
11. Glasscock ME, Harris PF, Newsome G. Glomus tumors: diagnosis and treatment. *Laryngoscope* 1974;84:2006-2032.
12. Gardner G, Cocke EW, Robertson JT, Trumbull ML, Palmer RE. Combined approach surgery for removal of glomus jugulare tumors. *Laryngoscope* 1977;87:665-688.
13. Fisch U. Infratemporal fossa approach for extensive tumors of the temporal bone and base of the skull. In: Silverstein H, Norrell H, eds. *Neurological surgery of the ear.* Birmingham, AL: Aesculapius Publishing Co., 1977:34-53.
14. Di Chiro G, Fisher RL, Nelson KB. The jugular foramen. *J Neurosurg* 1964;21:447.
15. Rhoton AL, Buza R. Microsurgical anatomy of the jugular foramen. *J Neurosurg* 1975:42:541-550.
16. Graham MD. The jugular bulb: its anatomic and clinical considerations in contemporary otology. *Archives of Otolaryngology* 1975;101:56u-564.
17. Brackmann DE. The facial nerve in the infratemporal fossa. *Otolaryngol Head Neck Surg* 1987;97:15-17.
18. Farrior JB. Infratemporal approach to skull base for glomus tumors: anatomic considerations. *Ann Otol Rhinol Laryngol* 1984;93:616-622.

продолжение

продолжение

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 22

Petroclival Approach

Madjid Samii and Marcos Tatagiba

The petroclival region is a complex area situated at the junction of the adjacent parts of the sphenoid, temporal, and occipital bones. There has been much discussion about the best way to approach this region, which reflects the difficult challenge this region represents. Different ways have been described in the past, and new approaches have arisen in concert with the modern skull base philosophy.

A number of lesions may originate in the petroclival region, including meningiomas, schwannomas, chordomas, chondrosarcomas, carcinomas, aneurysms, and others (1-4). Before the microsurgical era, tumors involving the petroclival region were considered inoperable (5,6). High surgical mortality and morbidity characterized these lesions, mainly related to large tumor size and involvement of important neurovascular structures (7).

Developments in neuroradiology, skull base approaches, and intensive care have led to a breakthrough in the management of the petroclival lesions. Increasing experience with these lesions has resulted in much information about patient selection for surgery, surgical strategies, and postoperative management.

Different approaches exist to access the petroclival region (8-19). The most important include the transpetrosal retrolabyrinthine (presigmoid), translabyrinthine, and transcochlear approaches, the suboccipital retrosigmoid approach, the subtemporal approach, the combined subtemporal-retrosigmoid approach, the combined subtemporal-presigmoid approach, the middle fossa (anterior transpetrosal) approach, and the preauricular infratemporal approach.

Most of these approaches have been described in other chapters of this text. In this chapter, the authors present a detailed description of the combined subtemporal-presigmoid approach and brief descriptions of the retrosigmoid and the middle fossa approaches to the petroclival region.

M. Samii, M. Tatagiba: Department of Neurosurgery, Hannover Medical School, 30625 Hannover, Germany.

PATIENT SELECTION AND SURGICAL CONCEPT

Petroclival tumors may become very large and extend into the middle cranial fossa, cavernous sinus, tentorial incisura, cerebellopontine angle, internal auditory canal, jugular foramen, foramen magnum, and extracranial spaces (Fig. 1). Using appropriate skull base approaches, a number of these lesions can be totally resected. These lesions still represent a surgical challenge, however. Increasing experience has demonstrated that the indications for surgery may be limited in some patients who do not tolerate an extensive tumor resection.

The most important factors with an impact on surgical resection are the nature and extension of the lesion, involvement of the cavernous sinus and vertebrobasilar system, and the patient's age and condition. Accurate clinical and radiologic investigations are essential to select the patients who can profit from the surgery.

On the basis of the preoperative clinical and radiologic data, the surgical plan is drawn. The strategy, however, may vary according to intraoperative findings. During the surgical procedure, tumor resection largely depends on tumor biology and the interface between tumor and normal tissue.

Despite all advances in neuroradiology, no preoperative tests can depict the tumor consistency exactly, the closeness of the tumor-nerve relation, or involvement of the arachnoid and pial sheaths. Therefore, in deciding whether to perform a radical or partial tumor resection, the surgeon must rely on his or her previous experience with similar cases, and consider both the tumor-intrinsic factors and the patient's expectations.

It is the authors' belief that all attempts should be made at radical resection of these lesions. However, if the tumor shows an infiltrative growth pattern and major neurovascular structures are involved without clinical deficits, the authors prefer a subtotal resection, and not to risk major functions or even the patient's life.



FIG- 1. A: Axial gadolinium-enhanced magnetic resonance image (MRI) of a petroclival meningioma showing extension into the posterior and middle fossae, the cavernous sinus, and extracranial spaces. B: Coronal MRI showing craniocaudal tumor extension and extension into the internal auditory canal and the jugular foramen.


Oculomotor nerve
Trigeminal nerve
Tentorium edge
Trochlear nerve
Third ventricle
Clivis
Brain stem

FIG. 2. Cadaver dissection showing the petroclival region from a medial view. The petroclival region is a complex area containing important neu-rovascular structures, situated at the junction of the clival and petrous bones.

SURGICAL ANATOMY OF THE PETROCLIVAL REGION

The petroclival region is the area situated between the middle and posterior skull base at the junction of the adjacent parts of the sphenoid, temporal, and occipital bones (Fig. 2).

The *extradural* structures related to the petroclival region that affect the surgical approaches are basically the temporal bone and its petrosal structures. The *intradural* structures related to the petroclival region can be divided into three spaces (17): the inferior petroclival space, consisting of the lower clivus and foramen magnum; the middle petroclival space, which comprises the cerebellopontine angle and prepontine area; and the superior petroclival space, which corresponds to the anterior part of tentorial incisura, the sella and parasellar regions, and the floor of the third ventricle.

The petrous bone is the key extradural structure of the petroclival region. Differing from classic descriptive anatomy, the surgical anatomic scheme divides the petrous bone into anterior and posterior portions, according to the major available transpetrosal approaches (20,21).

Anterior Portion of the Petrous Bone

Major anatomic structures of the anterior portion of the petrous bone include the foramen spinosum with the middle meningeal artery anteriorly; the arcuate eminence posteriorly; the petrous carotid artery, which is mostly only partially covered by a thin bone layer; and the superior petrosal sinus, which runs along the medial border of the upper surface of the petrous bone.

The greater petrosal nerve passes below the lateral margin of the trigeminal ganglion. Drilling along the course of the greater petrosal nerve in a dorsal direction exposes the geniculate ganglion, which can be followed in a medial direction to expose the labyrinthine portion of the facial nerve through its course into the internal auditory canal (Fig. 3).

Opening the internal auditory canal and the dura surrounding the contents of the internal auditory canal exposes the intracanalicular portions of the facial and superior vestibular nerves superiorly, and the cochlear and inferior vestibular nerves inferiorly. The superior vestibular and the facial nerves are separated at the fundus of the internal auditory canal by the vertical crest (the so-called "Bill[1] s bar"). The facial and cochlear nerves are in the anterior half, and the superior and inferior vestibular nerves are in the posterior half of the canal. The cochlea lies between the internal auditory canal and the petrous carotid artery, beneath the geniculate ganglion. The labyrinth with the vestibule and the superior semicircular canal lie close posterior to the fundus of the internal auditory canal. The length of the internal auditory canal varies from 8 to 12 mm (average, 10 mm). The average distance between the posterior semicircular canal and the edge of the canal is 7 mm (17).

The bony area between the greater petrosal nerve anteriorly, the carotid artery and the cochlea laterally, and the internal auditory canal and the semicircular canals posteriorly,



FIG. 3. Cadaver dissection showing the surgical anatomy of the anterior petrous bone. The bone covering the greater superficial petrosal nerve was drilled away, and the nerve followed to the fundus of the internal auditory canal.



FIG. 4. Cadaver dissection of the anterior petrous bone after drilling the bone between the internal carotid artery and the internal auditory canal, which exposes the cerebellopontine angle structures.

has been called Kawase's triangle. Bone removal at that area exposes the posterior fossa and cerebellopontine angle from above (Fig. 4).

Posterior Portion of the Petrous Bone

The posterior approaches to the petrous bone involve bone removal behind the sigmoid sinus in the retrosigmoid approach, and between the wall of the external auditory canal and the sigmoid sinus in the preaigmoid approach.

Decortication of the mastoid and removal of most mastoid air cells exposes the middle fossa plate and the superior petrosal sinus superiorly, the anterior portion of the sigmoid sinus posteriorly, and the plate covering the labyrinth block and facial nerve anteriorly (Fig. 5).

The otic capsule consists of the vestibule, the semicircular canals, and the cochlea. The lateral semicircular canal runs perpendicular to the facial nerve, and the posterior semicircular canal runs parallel to the sigmoid sinus. Lateral to the otic capsule lies the antrum, and inferior to it, the digastric ridge.

The vestibule is separated from the apex of the jugular bulb by an approximately 6-mm bone. The height of the jugular bulb may vary considerably, sometimes reaching the internal auditory canal. Penetration of a high-lying jugular bulb may be the source of severe bleeding or air embolism during surgery. Preoperative identification and careful intraoperative dissection are essential to control this problem (22).

The vertical segment of the carotid artery runs upward in the carotid canal, then curves anteromedially to form the horizontal segment.

CLINICAL ASPECTS

The clinical picture in petroclival lesions is primarily related to the origin and major extension of the lesion (23). Chordomas and chondrosarcomas usually cause diplopia because of cranial nerve VI involvement, whereas meningiomas, trigeminal schwannomas, and epidermoid cysts more frequently produce trigeminal symptoms and hearing problems (2,24,25),

From a topographic point of view, petroclival lesions can be divided into three main types in relation to the middle and posterior fossae.

The first group presents with a major extension into the posterior fossa and cerebellopontine angle. These tumors are more likely to produce hearing loss, tinnitus, cerebellar signs, and facial weakness as early symptoms. The lower cranial nerves may also be affected, producing swallowing dysfunction and hoarseness.

The second group of petroclival tumors presents with major extension into the middle fossa and usually involves the cav-



FIG. 5. Cadaver dissection of the posterior petrous bone after drilling away the mastoid to expose the sigmoid sinus, the middle fossa dura, the semicircular canals, and the facial nerve in the fallopian canal.

ernous sinus. These tumors frequently cause trigeminal symptoms (pain or hypesthesia) and diplopia at first presentation.

Finally, large tumors extending both into the middle and the posterior fossae constitute the third group of petroclival lesions. They may affect cranial nerves II through XII, but the most common symptoms are hearing loss and trigeminal problems. In a series of 36 patients with large petroclival meningiomas, 75% of the patients presented with hearing loss, and half of them had trigeminal symptoms (1).

Headache is common to them all.

RADIOLOGY

Computed tomography (CT) and magnetic resonance imaging (MRI) are complementary diagnostic tools in skull base surgery, High-resolution CT with soft tissue and bone algorithms provides indispensable demonstration of bony landmarks of the petrous bone and clivus (Fig. 6). Spiral CT technology allows for three-dimensional representation of the tumor, the intracerebral vessels, and bone structures. When planning the surgical approach, the three-dimensional imaging of spiral CT adds significant spatial information to that obtained by MRI and conventional CT (Fig. 7).



FIG. 6. Axial postoperative computed tomography scan with bone algorithms through the petrous bone. This technique well demonstrates the amount of bone removal and the preserved inner ear structures.



FIG. 7. Spiral three-dimensional computed tomography scan of a trigeminal schwannoma involving the petroclival region. This technique provides excellent spatial information about the tumor's relation to the skull base and surrounding vessels.

Magnetic resonance imaging demonstrates the relationship between tumor and surrounding vascular and neural tissues (Fig. 8). Magnetic resonance angiography depicts the involvement of major arterial and venous vessels, making cerebral angiography obsolete in individual cases (Fig. 9). Cerebral angiography demonstrates tumor vascularization and the displacement and involvement of important vessels, and provides the necessary information for preoperative embolization.

Once radiologic investigations have depicted both the extension of the lesion and the involvement of normal surrounding structures, the surgical strategy can be precisely planned.

PETROCLIVAL APPROACHES

Skull base tumors arising from the petroclival region may result in destruction of bony structures and compression of the brainstem. Tumor extension into the middle and posterior fossae frequently occurs, and involvement of the cavernous sinus is not unusual. Different approaches to the petroclival region have been described that consider the major extension of the lesion. A number of reports have ap-



FIG. 8. Coronal magnetic resonance images before **(A)** and after **(B)** intravenous contrast injection, demonstrating the relation between tumor and surrounding brain tissue and vessels. Note the involvement of the basilar artery in this case.



FIG. 9. Magnetic resonance angiogram of the patient in Fig. 8.

peared indicating improvements in tumor resection and postoperative outcome (1,8,12-14,16,21,23,25-30).

For didactic purposes, access to the petroclival region may be divided into four major approaches (31,32):

1. Middle fossa approaches
    a. Primary extradural (extended middle fossa)
    b. Primary intradural (subtemporal transtentorial)
2. Posterior fossa approaches
    a. Primary extradural (presigmoid)
    b. Primary intradural (retrosigmoid)

All these approaches can be combined with the others to enlarge the exposure. For most petroclival cases, the authors use the *combined subtemporal transtentorial-presigmoid approach.* These approaches are described in the following sections.

Posterior Fossa Primary Extradural-Presigmoid Approach

Indications

The *presigmoid approach* is the authors' approach of choice for most petroclival lesions. It is used in combination with a subtemporal approach. The major indications are lesions centered in the lateral incisural space extending infratentorially to the upper and mid-clivus, and lesions situated in the anterior part of the posterior pyramis extending supratentorially to the middle fossa. Frequent lesions include petroclival meningiomas, and large, dumbbell-shaped trigeminal schwannomas. Vascular processes such as aneurysms of the upper and middle basilar artery can also be accessed with this exposure.

The major advantages of the presigmoid approach are less brain retraction and the shorter route to the petrous apex provided by the bone removal, and the multiangle approach to the petroclival area that is afforded. The major disadvantages are the potential for hearing and facial damage during pyramidal bone drilling, and the possibility of vascular injuries, particularly to the vein of Labbe. For processes reaching the lower clivus and foramen magnum, the presigmoid approach can be combined with the retrosigmoid approach.

The *combined supratentorial—infratentorial approach with division of the sigmoid sinus* gives the same large exposure as the presigmoid approach combined with the retrosigmoid route. The main advantage of the transsigmoid approach is that the vein of Labbe is retracted upward along with the transverse sinus. This avoids the stretching and possible rupture of the vein, which may occur in the presigmoid approach when the vein is tethered to the transverse sinus during upward retraction of the temporal lobe. A major disadvantage of the transsigmoid approach compared with the presigmoid method is that transection of the sigmoid sinus may not be tolerated by a number of patients.

Operative Technique

Patient Position

The authors perform the presigmoid approach with the patient in semisitting position, and the head turned 60 degrees toward the side of the lesion and slightly anteflected. The legs are elevated to the level of the right cardiac atrium, and the head is fixed in place with Mayfield pins. Some surgeons prefer to operate with the patient in either the supine or the park-bench position.

Anesthesia and Monitoring

Intravenous anesthesia with isoflurane is induced. Prophylactic antibiotic is administered, and treatment with dexamethasone is initiated to reduce the risk of postoperative edema. Sensory evoked potentials are monitored continuously in the median nerve. Preoperative flexion-extension radiographs of the cervical spine are made to rule out craniocervical instability. All body parts subject to pressure are supported with cushions.

Major additional precautions during semisitting surgery include monitoring for air embolism using electrocardiography, oximetry, capnometry, precordial Doppler ultrasonography, catheterization of the right atrium, and central venous catheterization. Hearing is monitored by measurement of brainstem auditory evoked potentials. Subdermal needle electrodes are implanted for continuous electromyographic monitoring of the orbicular muscles of the eye and mouth.



FIG. 10. Patient in semisitting position. The scalp is shaved, and the skin marked for the incision.

Skin Incision and Craniotomy

Part of the temporal, occipital, and suboccipital region of the scalp is shaved, and the skin is marked for the incision (Fig. 10). A curvilinear skin incision starting 2 cm above the upper part of the auricle is carried backward along the temporal line, and is curved downward in a linear fashion to the suboccipital area about 3 cm behind the ear, extending 2 cm under the mastoid tip.

The skin Hap is reflected forward to the level of the external auditory canal. The temporalis muscle is cut in the area below the fascia insertion at the bone and reflected downward. The muscles over the mastoid and occipital bone are swept downward using subperiosteal dissection.

The first bur hole is placed at the region of the asterion. exposing the transition border of the transverse to sigmoic sinuses. The dura is slightly detached from the bone in the urea around the bur hole using the dissectors. A temporal anc suboccipital craniotomy is done with a high-speed craniotome, exposing the transverse sinus, The bone flap is elevated carefully, taking care to free dural adhesions along the transverse sinus. Small sinus lacerations are packed with fibrin sponge.



FIG. 11. Intraoperative photograph after the craniotomy flap is removed and the mastoid is drilled. The dura anterior to the sigmoid sinus is exposed (Trautmann's triangle).


Vein of Labbe
SPS
TT
Vein of Labbe
SPS
Labyrinth block
Dura opening
III
IV
V
SCA
Temp. lobe
Basilar art.
Tentorium
Tumor
VII & VIII
AICA
PICA
IX & X
SPS = superior petrosal sinus
TT = Trautman's triangle
III = Oculomotor nerve
IV = trochlear nerve
V = trigeminal nerve
VII = facial nerve
VIII = vestibulocochlear nerve
IX = glossopharyngeal nerve
X = vagus nerve

FIG. 12. Artist s depiction of the combined subtemporal-presigmoid approach. The dura is opened in a T-shaped fashion with division of the superior petrosal sinus. The temporal lobe is then retracted upward and the cerebellum backward.

Petrous Bone Drilling

From now until the dura is closed, the operation is conducted using the operating microscope. Using a high-speed air drill, a mastoidectomy is done with exposure of the sigmoid sinus as low as the jugular bulb (Fig. 11). The posterior wall of the petrous pyramid is drilled away in a lateromedial direction as far anterior as possible without opening the posterior semicircular canal or the fallopian canal. The distance between the posterior semicircular canal and the anterior border of the sigmoid sinus varies from a few millimeters to] cm. In cases of preoperative hearing loss, a wider exposure can be done with resection of the labyrinth. Care should be taken not to injure the facial nerve.

In most petroclival lesions, there is no need to open the fallopian canal or reroute the facial nerve.

Dural Opening

After the drilling procedure is completed, the exposure reveals the temporal, presigmoid, and retrosigmoid dura, and the transverse, sigmoid, and superior petrosal sinuses. The dura is then cut over the transverse sinus toward the temporal dura while preserving the junction of the vein of Labbe with the transverse sinus. The infratentorial dura is opened anterior to the sigmoid sinus in Trautmann's triangle. The lateral cerebellomedullary cistern is opened, and cerebrospinal fluid (CSF) is withdrawn to provide more space. The posterior temporal lobe is retracted superiorly, and the cerebellum is held backward. The superior petrosal sinus is ligated and divided (Fig. 12).

Division of Tentorium

The tentorium is cut in a lateromedial direction anterior to the transverse sinus (and the vein of Labbe") and parallel to the petrous ridge (Fig. 13). The incision is extended through the medial tentorial edge behind the area in which the trochlear nerve penetrates the tentorium. Care is taken not to injure the trochlear nerve running close to the tentorial edge. Tentorial sinuses may sometimes bleed significantly and should be packed with fibrin sponges. No bipolar coagulation is used to stop bleeding because of risk of injury to the trochlear nerve.

Brain Retraction and Tumor Exposure

The cerebellum is then gently retracted posteriorly along with the sigmoid sinus and the edge of the divided tentorium. The rumor is exposed in its full extension along with the cranial nerves and vessels in the cerebellopontine angle (Fig. 14). Tumor is removed using the cavitron and microsurgical techniques. The dissection of tumor away from the vessels and nerves is carried out respecting the arachnoid planes. The combined presigmoid approach allows complete tumor resection in most cases, with preservation of normal struc-



FIG. 13. After division of the superior petrosal sinus (A), the temporal lobe and cerebellum are retracted, exposing the tumor (B). The tentorium is then transected in lateromedial direction (C).



FIG. 14. The lumor is now exposed supratentorially and infratentorially in a single compartment.

tures (Fig. 15). However, particularly in meningiomas, if the arachnoid sheath surrounding nerves and vessels is absent or the brainstem pia mater is infiltrated, no attempt at radical surgical removal is made because of the risk of severe postoperative deficits.

The presigmoid approach has also been used for aneurysms of the middle basilar trunk. This approach provides good exposure of the middle and lower basilar artery from the vertebrobasilar junction to the basilar trunk above the anterior inferior cerebellar artery origins (4). The surgeon works between the cranial nerves V and the VII to VIII complex, or between the latter and the lower cranial nerves. There is enough space for temporary clipping if necessary.

Technical Aspects of Tumor Resection

Meningiomas. Resection of petroclival meningiomas includes alternating intratumoral decompression using the ultrasonic aspirator, bipolar coagulation, and microscissors, with dissection of the tumors from the surrounding structures (see Figs. 13-15). To minimize the risk to neurovascular structures, the dissection is carried out outside the arachnoid. In small petroclival meningiomas, cranial nerves VII and VIII are usually easily identifiable in the posterior aspect of the tumor. In large meningiomas, cranial nerves VII through XII may be engulfed by the tumor, and careful microsurgical dissection is necessary to preserve function.



FIG. 15. Intraoperative photograph showing complete tumor resection with preserved cranial nerves.


Tumor
VII-VIII cranial nerves
Cerebellum

FIG. 16. Intraoperative photograph of a trigeminal schwannoma exposed using the combined subtemporal-presigmoid approach. Cranial nerves VII and VIII are displaced downward by the tumor.


Trochlear nerve
Trigeminal nerve roots
Basilar artery
VII-VIII nerves

FIG. 17. Complete tumor resection with preservation of some trigeminal roots and surrounding neurovascular structures.

Trigeminal Schwannomas. Trigeminal schwannomas have been classified into four major types, depending on the major tumor extension (2). Dumbbell-shaped trigeminal schwannomas extending into the middle and posterior fossae are best resected by the presigmoid approach. The tumor is exposed as described previously (Fig. 16). It is then debulked and separated from the stretched fascicles of the trigeminal nerve. These tumors frequently have a good arachnoid plane, and it is usually possible to resect it and preserve most nerve fascicles (Fig. 17). Resection of the nerve fascicles results in postoperative numbness and disabling keratitis. If the tumor enters the cavernous sinus, every attempt should be made to remove it through the posterior approach. It is also essential to open Meckel's cave to achieve a radical resection.

Hemostasis and Closure

After tumor removal is completed and before the dura is closed, the jugular vein is compressed to elicit possible venous bleeding that may not be obvious in the semisitting position. Any venous bleeding should be stopped by bipolar coagulation, or packing with fibrin sponge or Surgicel. Once the hemostasis is secured, the dura is closed in watertight fashion. When the dural defect cannot be closed primarily, a dural reconstruction is done and lumbar spinal drainage is used for 5 to 7 days. A compressive dressing is applied for 1 week.

Posterior Fossa Primary Intradural Approach

Indications

The retrosigmoid approach is used only in cases of petroclival meningiomas with major extension into the posterior fossa and little involvement of the supratentorial surface of the tentorium, or in cases of large tumors in older patients, in which the only aim is brainstem decompression.

Operative Technique

The authors operate with the patient in the semisitting position, as described previously. The head is moved anteriorly and turned 30 degrees toward the side of lesion. After the skin incision is done approximately 3 cm behind the ear and the neck muscles are detached and retracted, suboccipital craniectomy or craniotomy is performed, exposing the margins of the transverse and sigmoid sinuses. The dura is opened some millimeters away and along the transverse and sigmoid sinus.

The inferior border of the cerebellum is elevated as a first step, and the cerebellomedullary cisterns are opened to allow CSF drainage. The cerebellum is now relaxed and can be easily retracted medially without major compression. This approach allows visualization of cranial nerve V through the lower cranial nerves, depending on tumor size and extension (Fig. 18).



FIG. 18. Cadaver dissection showing a view of the lower cerebellopontine angle from the retrosigmoid approach. The cerebellum is held with a retractor. Cranial nerves VII and VIII are seen between the internal auditory meatus and the brainstem. The lower cranial nerves are seen between the jugular foramen and the brainstem.

Petroclival meningiomas usually displace cranial nerves V, VII, and VIII dorsally and must be removed between the cranial nerves. The technique of arachnoid sheath dissection is used for tumor resection.

Epidermoid tumors may fill the entire cerebellopontine angle and even extend to the contralateral side, caudally to the foramen magnum, and cranially to the middle fossa. The cerebellopontine angle is divided into four floors, based on the cranial nerves: the first floor lies between the tentorium and cranial nerve V; the second floor between cranial nerve V and the complex of nerves VII and **VIII;** the third floor between the complex of nerves VII and VIII and the caudal cranial nerves; and the fourth floor below the caudal cranial nerves. The tumor is removed between these floors, mostly between the second and the third floors. In 40 cases of cerebellopontine angle epidermoids, 75% of the tumors were completely removed, but in 25% of the cases, very adherent tumor capsule could not be resected. An attempt to remove the capsule in these cases may produce severe, permanent neurologic deficits.

Middle Fossa Extradural Approach

Indications

This approach is mostly indicated for extradural processes involving the petroclival region, such as chordomas and chondrosarcomas.

Operative *Technique*

The patient's head is turned 90 degrees, positioned parallel to a horizontal line and slightly extended. A temporal craniotomy anterior to the ear and above the zygoma is performed. The dura is elevated from the floor of the middle fossa until the arcuate eminence and the greater petrosal nerve are visualized. Identification of the internal auditory canal involves drilling along the greater petrosal nerve, which indicates the geniculate ganglion. At this point, the drilling is turned medially to expose the labyrinthine portion of the facial nerve up to the fundus of the internal auditory canal (see Fig. 3). Another technique to locale the internal auditory canal is to subtend an angle of 60 degrees from the plane of the superior semicircular canal.

To reach the petroclival region, parts of the petrous apex are drilled away: between the trigeminal nerve anteriorly, the carotid artery and cochlea laterally, and the labyrinth block posteriorly (Kawase's approach). The bone removal is extended to the lateral side of the clivus, exposing the inferior petrosal sinus. The width of the bone resection from the trigeminal impression to the posterior wall of the internal auditory canal averages 13 mm (17). The dura is then opened anterior to cranial nerves VII and VIII.

The view can be widened by dividing the tentorium. The dural leaflets of the tentorium are retracted with sutures. This approach gives a view of cranial nerves III to VTII, the basilar artery, the posterior cerebral artery, the superior cerebellar artery, and the anterior inferior cerebellar artery (see later). The exposure, however, is small and may require significant temporal lobe retraction. Another disadvantage is the relatively high risk of facial nerve injury.

Middle Fossa **Intradural (Transtentorial) Approach**

Indications

1i.

This approach is mainly indicated for petroclival lesions with extension intradurally and brainstem displacement, such as meningiomas, schwannomas (cranial nerve VII). and epidermoid cysts. It may also be indicated for aneurysms of the basilar tip, Advantages of this approach include a more anterior angle and widened visualization of the interpeduncular area, the basilar apex and upper trunk, the ventral lateral brainstem, and the upper petroclival area. The disadvantage lies in the potential for injury to important bridging veins running from the temporal lobe to the base of the skull.



FIG. 19. Cadaver dissection of the middle fossa approach after drilling the petrous apex and division of the tentorium, exposing the region's anatomy.

Operative Technique

The head is positioned as described previously for the middle fossa approach, with the difference that the head is turned to form an angle of 15 degrees with the horizontal line (with the nose elevated). The craniotomy is done above and anterior to the ear. The zygomatic arch may be divided and reflected inferiorly with the attached muscle and fascia to allow for a low craniotomy and less temporal lobe retraction.

After the dura has been opened, the temporal lobe is gently elevated to visualize the tentorial edge. The tentorium is elevated to show the course of the trochlear nerve running into the dural tunnel at the tentorial edge (see Fig. 2). The tentorium is then divided 1 to 2 cm posterior to the entry point of cranial nerve IV. The dural tunnel of the trochlear nerve is opened, freeing the nerve. One of the key steps in the subtemporal transtentorial approach is the dissection of the trochlear nerve from the edge of the tentorium. The superior petrosal sinus can be divided after double clipping, bipolar coagulation, or packing with Surgicel. The tentorial flaps are then widely reflected, which provides visualization of the interpeduncular and prepontine cisterns between cranial nerves IV and V (Fig. 19). Temporal lobe retraction exposes the basilar artery apex and the oculomotor nerve.

The dura around the petrous bone can be resected to perform a partial petrosectomy by drilling part of the petrous apex at Kawase's triangle. Care should be taken not to injure the carotid artery and the cochlea.

MANAGEMENT **OF COMPLICATIONS**

Major complications of petroclival surgery include cranial nerve injury, vascular injury, and CSF leakage. The anterior approaches may be complicated by injury to the vein of Labbe, temporal lobe, and facial nerve. The posterior approaches may be complicated by injury to the labyrinth block, sinus thrombosis, and CSF leakage.

Cerebrospinal fluid leakage is avoided by watertight dural closure, or dural reconstruction and placement of lumbar drainage for about 1 week. The mastoid air cells are closed with muscle fragments and fibrin glue.

Thrombosis of the transverse or sigmoid sinus is a life-threatening complication that must be immediately recognized and treated (1). This complication can be prevented by avoiding severe sinus compression during the surgery.

Injury to the labyrinth has been related to postoperative hearing loss. However, labyrinth injury does not invariably result in complete hearing loss (33). Once part of the labyrinth is injured, suction of its contents should be avoided and the opening area immediately closed with muscle fascia and fibrin glue.

Review of the literature revealed that in most series, complete tumor removal was achieved in 70% of cases. Indeed, approximately 30% of meningiomas were not resectable. Incomplete tumor removal and surgical morbidity have been largely related to absence of the arachnoid sheath because of tumor infiltration, which may result in rupture of the pia and pial vessels of the brainstem with consequent brainstem infarction. Awareness of these risks and the surgical limitations is essential for management of petroclival lesions.

CASE REPORTS

CASE 1: PETROCLIVAL MENINGIOMA

A 56-year-old man presented with a 2-year history of progressive hearing loss and unsteady gait. Neurologic examination demonstrated a decreased hearing of 30 dB at 1 to 3 kHz, slight facial weakness, and diminished sensation on the face. The gait was unsteady with a broad base. CT and MR1 scans showed a large petroclival mass extending to the middle and posterior fossae and compressing the brainstem (Fig. 20).

Through a combined supratcntorial-presigmoid approach, the tumor was exposed and completely resected. At discharge from the hospital, no additional deficits were found. Postoperative CT showed total tumor resection (Fig. 21).



FIG. 20. Case 1. Serial enhanced computed tomography scan of a large

CASE 1 (Continued)



FIG. 21. Case 1. Serial enhanced computed tomography scan after tumor resection by the combined subtemporal-presigmoid approach.

CASE 2: TRIGEMINAL SCHWANNOMA

This 31 -year-old man presented with a 2-year history of numbness of the left hemiface, and progressive headache and hearing loss of 1 year's duration. MRI showed a large, dumbbell-shaped tumor with compression of the brainstem and involvement of the cavernous sinus (Fig. 22). By a combined subtemporal-presig-moid approach, the lesion was resected with preservation of most trigeminal fascicles. The postoperative outcome was uneventful. Immediate postoperative CT depicted the amount of bone resection and tumor removal (Fig. 23).



FIG. 22. Case 2. Enhanced magnetic resonance image of a large, dumbbell-shaped trigeminal schwannoma extending into the middle and posterior fossae.



FIG. 23. Case 2. Computed tomography scan after tumor resection.

CASE 3: PETROCLIVAL CHORDOMA

This 48-year-old man had been operated on twice for a clivus chordoma before he was referred to our department with a tumor recurrence. The patient had complete deficit of cranial nerves VI through VIII on the left side. Preoperative MRI showed large tumor extension in the left petroclival area up to the foramen magnum (Fig. 24). By a combined presigmoid-transpetrosal (translabyrinthine, transcochlear) approach, the lesion was radically resected. Postoperative CT showed the degree of tumor and bone resection (Fig. 25). A 3-year follow-up did not show tumor recurrence.



FIG. 24. Case 3. Sagittal magnetic resonance image of a large chordoma of the clivus extending from the middle fossa up to the lower clivus.



FIG. 25. Case 3. A,B: Postoperative computed tomography scan with bone algorithms showing degree of bone resection after radical tumor removal.

ACKNOWLEDGMENTS

The authors thank Mr. Stefan Brinkmann for preparing the photographic material and Mrs. Marianne Faust for the illustrations.

REFERENCES

1. Samii M, Tatagiba M. Experience with 36 surgical cases of petroclival meningiomas. *Acta Neurochir(Wien)* 1992;! 18:27-32.
2. Samii M. Migliori M, Tatagiba M, Babu R. Surgical treatment'of trigeminal schwannomas. *J Neurosurg* 1995;82:711-718.
3. Weber AL, Liebsch NJ, Sanchez R, Sweriduk SJ. Chordomas of the skull base: radiologic and clinical evaluation. *Neuroimaging din North Am* 1994 ;4:515-527.
4. Martin N. Vascular lesions. In: Samii M, Cheatham M, Becker D, eds. *Atlas of cranial base surgery.* Philadelphia: WB Saunders, 1995: 201-211.
5. Castellano F. Ruggiero G. Meningiomas of the posterior fossa. *Acta Radial (Suppl)* 1953;104:1-177.
6. Outline B, Ebersold M, Scheithauer B. Neoplasms of the intracranial meningcs. In: Youmans JR, ed. *Neurological surgery.* Vol. 5. 3rd ed. Philadelphia: WB Saunders, 1990:3250-3315.
7. Yasargil M, Mortara R, Curcic M. Meningiomas of basal posterior cranial fossa. *Adv Tech Stand Neurosurg* 1980;7:3-115.
8. Al Mefty O, Ayoubi S, Smith RR. The petrosal approach: indications, technique, and results. *Acta Neurochir Suppl (Wien)* 1991;53:166-170.
9. Arriaga MA, Brackmann DE, Hitselberger WE. Extended middle fossa resection of petroclival and cavernous sinus neoplasms. *Laryngoscope* 1993;103:693-698.
10. Canalis RF, Black K, Martin N, Becker D. Extended retrolabyrinthine transtentorial approach to petroclival lesions. *Laryngoscope* 1991; 101:6-13.
11. Hakuba A, Liu S, Nishimura S. The orbitozygomatic infratemporal approach: a new surgical technique. *Surg Neurol* 1986;26:271-276.
12. Kawase T, Shiobara R, Toya S. Middle fossa transpetrosal-transtento-rial approaches for petroclival meningiomas: selective pyramid resection and radicality. *Acta Neurochir (Wien)* 1994; 129:113-120.
13. King WA, Black KL, Martin NA, Canalis RF, Becker DP. The petrosal approach with hearing preservation. *J Neurosurg* 1993;79:508-514.
14. Samii M, Ammirati M. The combined supra-infratentorial pre-sigmoid sinus avenue to the petro-clival region: surgical technique and clinical applications. *Acta Neurochir (Wien)* 1988:95:6-12.
15. Sanna M, Mazzoni A, Saleh EA, Taibah AK, Russo A. Lateral approaches to the median skull base through the petrous bone: the system of the modified transcochlear approach. *J Laryngol Otol* 1994;108: 1036-1044.
16. Sekhar LN, Pomeranz S, Sen CN. Extradural petrous bone and petroclival neoplasms. *Acta Neurochir Suppl (Wien)* 1991;53:183-192.
17. Tedeschi H, Rhoton AJ. Lateral approaches to the petroclival region. *Surg Neural* 1994;41:180-216.
18. Thedinger B A, Glasscock ME, Cueva RA. Transcochlear transtentorial approach for removal of large cerebellopontine angle meningiomas. *Am JOtol* 1992:13:408^115.
19. Rhoton AJ, Tedeschi H. Lateral approaches to the cerebellopontine angle and petroclival region (honored guest lecture). *Clin Neurosurg* 1994:41:517-545.
20. Day JD, Fukushima T, Giannotta SL. Microanatomical study of the extradural middle fossa approach to the petroclival and posterior cavernous sinus region: description of the rhomboid construct. *Neuro-surgery* 1994:34:1009-1016.
21. Miller" CG. Van Lovereu HR, Keller JT, Pensak M, El-Kalliny M. Tew JJ. Transpetrosal approach: surgical anatomy and technique. *Neu-rosurgery* 1993;33:461-469.
22. Shao K, Tatagiba M. Samii M. Surgical management of high jugular bulb in acoustic neurinoma via retrosigmoid approach. *Neurosurgery* 1993:32:32-37.
23. Spetzler RE. Hamilton MG, Daspit CP. Petroclival lesions. *Clin Neurosurg* 1994:41:62-82.
24. Samii M, Tatagiba M. Piquer J, Carvalho G. Surgical treatment of epidermoid cysts of the cerebellopontine angle. *J Neurosurg,* 1996;84:14-19.
25. Samii M, Ammirati M, Mahran A, Bini W, Sepehrnia A. Surgery of petroclival meningiomas: report of 24 cases. *Neurosurgery* 1989: 24:12-17.
26. Al Mefty O, Fox JL, Smith RR. Petrosal approach for petroclival meningiomas. *Neurosurgery* 1988:22:510-517.
27. Bncolo AP, Turazzi S, Talacchi A, Cristofori L. Microsurgical removal of petroclival meningiomas: a report of 33 patients. *Neurosurgery* 1992:31:813-828.
28. Cantore G, Delfini R, Ciappetta P. Surgical treatment of petroclival meningiomas: experience with 16 cases. *Surg Neural* 1994;42: 105-111.
29. Kawase T, Shiobara R. Toya S. Anterior transpetrosal-transtentorial approach for sphenopetroclival meningiomas: surgical method and results in 10 patients. *Neurosurgery* 1991:28:869-875.
30. Pensak ML, Van LH, Tew JJ. Keith RW. Transpetrosal access to meningiomas juxtaposing the temporal bone. *Laryngoscope* 1994: 104:814-820.
31. Samii M, Tatagiba M. Neurosurgical aspects of tumors of the base of the skull. In: Youmans J, ed. *Neurological surgery.* Philadelphia: WB Saunders, 1996:3024-3040.
32. Samii M, Ammirati M. *Surgery of skull base meningiomas.* Berlin: Springer-Verlag, 1992:87-96.
33. Tatagiba M, Samii M, Matthies M, El Azm M, Schonmayr R. The significance for postoperative hearing of preserving the labyrinth in acoustic neurinoma surgery. *J Neurosurg* 1992:77:677-684.

продолжение

Surgery of the Skull Base,
edited by Paul]. Donald.
Lippincott-Raven Publishers. Philadelphia © 1998.

CHAPTER 23

Evaluation and Management of Vestibular Schwannomas

Hilary A. Brodie and Pamela Bohrer

In the early 1800s, Jean Cruveilhier presented a fascinating yet tragic account of a young woman with an acoustic neuroma. He carefully documented her progressive symptoms, both localized and generalized. The local symptoms resulted from direct tumor pressure and included progressive hearing loss, trigeminal neuralgia, and facial spasms. The generalized symptoms were caused by the increased intracranial pressure, and included headaches, blindness, hyposmia, and dysgeusia. She lived with these symptoms from age 19 until her death at age 26 years. Cruveilhier subsequently performed a postmortem examination and provided a remarkable description of a large acoustic neuroma: a firm, benign lesion arising from the internal auditory canal. It had eroded the temporal bone and compressed the surrounding nervous tissue, but true invasion was not seen. This detailed account is the first well documented case of the clinical and pathologic findings of a cerebellopontine angle (CPA) lesion.

It was Harvey Gushing, in the early 1900s, who brought focused attention to CPA lesions and took the first large steps toward successful surgical removal of these tumors (1). He emphasized early detection through high clinical suspicion, careful history taking, and thorough physical examination. However, surgical techniques of the time were poorly suited to dealing with lesions in the CPA, and his surgical results were relatively poor. To minimize the high morbidity associated with total tumor removal, he advocated debulking and partial tumor excision. Indeed, this tactic lowered morbidity rates, but tumor recurrence was common.

The modern era of surgical removal for CPA lesions began in the 1960s, with the work of William House. Before that time, mortality and morbidity rates were quite high using the suboccipital approach. House and Hitselberger advocated the use of the operating microscope and described and refined the translabyrinthine and middle fossa approaches to the CPA (2,3). Using these techniques, they achieved total tumor excision with acceptable morbidity and mortality. During this same time, the suboccipital approach was being refined, with the aid of the operating microscope, by the neurosurgical community. Today, the multidisciplinary skull base team is well versed in a variety of surgical approaches and tailors the surgical planning for each individual patient. Mortality rates have dropped to 1 % in large series, and morbidity has been steadily decreasing.

The most common lesion in the CPA is an acoustic neuroma, or, more properly renamed, a vestibular schwannoma. In a large series of 1,354 lesions reported by Brackmann and Bartels in 1980, 91% of the tumors were vestibular schwannomas, 3% were meningiomas, 2% were primary cholesteatomas, and the remaining 4% were of widely varied histologic types (4). Magnetic resonance imaging (MRI) has significantly improved the preoperative evaluation of tumor type.

Magnetic resonance imaging has also enabled the detection of CPA tumors at a much earlier stage. Lesions of only a few millimeters in size, at a time when symptoms may be limited to mild hearing loss or even simply unilateral tinnitus, are being identified with MRI with gadolinium enhancement. In the modern era, the goal is early detection of vestibular schwannomas while patients are manifesting symptoms limited to unilateral hearing loss and tinnitus with mild unsteadiness, and before facial and trigeminal symptoms, hydrocephalus, and mass effects from very large tumors appear.

The emphasis on early detection and treatment of CPA lesions while small results from the fact that the morbidity of microsurgical excision is directly correlated to the size of the lesion. Unfortunately, microsurgical tumor excision can produce the same neurologic defects as the enlarging tumor.

H. A. Brodie: Department ot'Otolaryngology, University of California, Davis Medical Center, Sacramento, California 95817.

P. Bohrer: Department of Otolaryngology, Kaiser Permanente Medical Group, Santa Rosa, California 95403.

The following sections review the clinical presentation, diagnosis, treatment options, and microsurgical techniques for vestibular schwannomas. The challenge for the modern skull base team is to achieve total tumor extirpation with maximal preservation of function.

CLINICAL PRESENTATION

Hearing Loss

Vestibular schwannomas are varied in their presentation. Typically, patients present with a gradual, progressive, unilateral or asymmetric high-frequency sensorineural hearing loss, often with associated tinnitus. The rate of progression of hearing loss ranges from sudden onset to progressive over many years. Ten to 22% of patients with vestibular schwannoma present with sudden-onset sensorineural hearing loss (5-8). If questioned closely, up to 26% of patients report having had an episode of transient hearing loss at some point in their history (9). However, the overall incidence of vestibular schwannoma in patients with sudden sensorineural hearing loss is low. In one series of 836 patients with sudden sensorineural hearing loss, the incidence of vestibular schwannoma was 1.5% (10). In general, in patients with vestibular schwannoma there is no improvement in hearing thresholds after the acute loss, but there are subsets of patients who demonstrate fluctuating thresholds or recovery of hearing loss (6). In one series of 133 patients, 17 patients (13%) had a sudden sensorineural hearing loss, of whom 23% (4/17) recovered auditory function before resection of the vestibular schwannoma (6). Presentations suggestive of Meniere's syndrome occur in approximately 3% of patients with vestibular schwannoma (11). One case report describes a patient with recovery of hearing thresholds to normal levels on four separate occasions after steroid therapy. The patient had a 1.5-cm vestibular schwannoma (8).

As imaging techniques improve and MRI scans are obtained more readily, the incidence of vestibular schwannoma detected in patients with normal hearing is increasing. Five to 15% of patients with vestibular schwannoma have normal pure tone thresholds (9,12,13). Many of these tumors have been incidental findings. One report describes 10 patients with vestibular schwannoma and normal hearing thresholds (7). The most common presenting complaint among these patients was subjective hearing loss accompanied by tinnitus. Vertigo and dizziness, without any cochlear symptoms, were also frequently encountered. The average duration of hearing loss before the diagnosis of a vestibular schwannoma is approximately 4 years (9).

Given the significant variability in otologic presentation of patients with vestibular schwannomas and the relatively low incidence of vestibular schwannoma in patients with asymmetric sensorineural hearing loss, an efficient and cost-effective algorithm must be used to identify patients early in their clinical course, and to minimize false-negative work-ups

Tinnitus

Tinnitus associated with vestibular schwannoma is usually high pitched, continuous, and unilateral or asymmetric. However, as with hearing loss, the tinnitus also may be variable. Tinnitus is usually mild to moderate in severity and rarely incapacitating. Aside from the tendency to localize to one ear, there is nothing characteristic about the tinnitus to indicate an underlying vestibular schwannoma. The incidence of tinnitus ranges in the literature from 53% to 70% (14-17). i(.. . . ..

Vertigo T".::

The actual perception of motion, or true vertigo, is much less common in patients with vestibular schwannoma than is disequilibrium. When present, disequilibrium tends to be mild to moderate in severity. The disequilibrium is rarely incapacitating, except in very large tumors with cerebellar and brainstem compression. The incidence of vertigo varies widely in the literature, from 18% to 58% (9,14-17). The incidence of vestibular dysfunction is a function of tumor size. Selesnick et al. demonstrated that vertigo was much more common in patients with smaller tumors, whereas disequilibrium was more prevalent in patients with larger tumors (9). They reported a 27% incidence of vertigo in patients with tumors less than 1 cm in size, as contrasted to a 19% incidence of vertigo in patients with tumors 1 to 3 cm in size. The incidence of vertigo decreased to 10% of patients with tumors greater than 3 cm in size. The incidence of disequilibrium with vestibular schwannomas less than 1 cm, tumors 1 to 3 cm, and tumors greater than 3 cm was 37%, 47%, and 71%, respectively (9). The incidence of cerebellar symptoms in the older literature ranges from 65% to 85% (14-16). More recent reports with a greater proportion of smaller tumors reflect a lower incidence of disequilibrium of 45% to 48% (9,18).

Trigeminal Nerve Dysfunction

Involvement of the trigeminal nerve may manifest as hypesthesia, paresthesia, or, rarely, anesthesia, typically in the mid-facial region. Historically, the incidence of trigeminal nerve involvement was quite common, with approximately 50% of patients manifesting symptoms of trigeminal nerve involvement, and 88% demonstrating evidences of trigeminal dysfunction on physical examination (15-17). The incidence of trigeminal nerve involvement is clearly proportional to the tumor size. Thomsen and Tos reported an incidence of trigeminal nerve involvement in 14% of pa-dents with vestibular schwannomas less than 4 cm in size, and in 53% of patients with tumors greater than 4 cm in size (18).

Headache In older series, headache was a common complaint of patients with vestibular schwannomas. The incidence of headache ranged from 65% to 85% (14-16). The incidence of headache in more recent studies reveals a lower incidence of 19% to 38% (9,19). The incidence of headache also is proportional to tumor size. In their series of patients with vestibular schwannomas less than 1 cm in size, Selesnick et al. reported no patients complaining of headache (9). Twenty percent of patients with tumors between 1 and 3 cm in size complained of headaches, and 43% patients with tumors greater than 3 cm in size experienced headaches.

Facial Nerve Dysfunction

Facial paresis is in general a late sequela of vestibular schwannomas. The weakness is typically gradual in onset and may be preceded by facial twitching, most commonly in I the zygomatic branch distribution. Early series report a 15% incidence of symptomatic facial nerve involvement, with up , to 65% of patients demonstrating subtle facial nerve in-I volvement on physical examination (1,15,16). The incidence of facial nerve dysfunction in more recent series is significantly lower, at 10% (9,19). Sensory fibers are less resistant to the effects of compression and, consequently, manifest earlier clinically. This is the basis of Hitselberger's sign, which is a hypesthesia of the concha or external auditory canal (20,21). Hitselberger reported the presence of hypesthesia in 85% of patients with vestibular schwannomas. Another manifestation of sensory fiber dysfunction in the facial nerve is aching in the region of the mastoid. This symptom has been reported to occur in 25% of patients with vestibular schwannoma (22).

DIAGNOSTIC TESTING

Audiogram

The classic audiologic presentation of a patient with a vestibular schwannoma is a unilateral or asymmetric sensorineural hearing loss. The frequency pattern of loss is relatively nondiagnostic. Fifty-three to 66% of patients demonstrate a high-frequency sensorineural hearing loss, with most of the remainder typically manifesting a flat loss across all frequencies or profound loss (11,23-25). U-shaped or low-tone patterns of loss are less common (11,23). The severity of hearing loss is a poor indicator of tumor size (11). Deterioration of speech discrimination is typically disproportionate to the amount of threshold impairment, although the overall positive predictive value of speech discrimination remains low. Approximately 70% of patients with vestibular schwannoma have speech discrimination abilities of 60% or worse (11). Stapedial reflexes can provide additional support for a diagnosis of a cerebellopontine tumor. Absent stapedial reflex, elevated thresholds, or stapedial reflex decay are present in 75% to 98% of patients with vestibular schwannoma (11,26,27). Despite the relatively high sensitivity of acoustic reflex testing for retrocochlear disease, the test is of limited overall value because of its lack of specificity. Thomsen et al., in 1983, were unable to demonstrate a significant difference in reflex decay in patients with vestibular schwannomas, and in those patients who were being evaluated for the presence of a vestibular schwannoma but were later found to be negative (27). The most specific stapedial reflex abnormality in retrocochlear disease is absent reflexes across all frequencies (11,28).

Electronystagmography

Vestibular testing with electronystagmography (ENG) is in general a sensitive test for demonstrating vestibular disease in patients with retrocochlear lesions, but it lacks specificity and is of questionable value. One use of ENG is to determine whether the inferior or superior vestibular nerve is the site of origin for the vestibular schwannoma. This information is useful when approaching an intracanalicular tumor with a goal of hearing preservation. Caloric testing reveals the status of the horizontal semicircular canal and the superior vestibular nerve. Consequently, normal caloric testing results suggest that the inferior vestibular nerve is the site of origin. An abnormal caloric test result is less useful because, even if the tumor originates in the inferior vestibular nerve, the tumor compression of the superior vestibular nerve within the internal auditory canal may still yield an abnormal test result. If the ENG reveals a normal caloric, suggesting an inferior vestibular nerve site of origin, some surgeons prefer to approach these tumors through a suboccipital, as opposed to a middle cranial fossa, approach because of the position of the tumor relative to the facial nerve. Odkvist reviewed the ENG results of 78 patients with vestibular schwannomas (29). Fifty-eight percent manifested spontaneous nystagmus; 43% had positional nystagmus and 88% demonstrated caloric asymmetry (29).

Auditory Brainstem Response

Auditory brainstem response testing (ABR) has been an effective screening tool for retrocochlear lesions since the late 1970s. It is a sensitive test for retrocochlear disease, with a sensitivity of 90% to 100% (1 1,30-33). ABR is an excellent test to identify larger vestibular schwannomas but is less effective in demonstrating intracanalicular tumors or CPA meningiomas. The sensitivity of ABR in detecting small intracanalicular tumors drops to 63% to 67% (34,35). Another limitation of the ABR is detecting nonacoustic CPA tumors. The false-negative rate is 25% with CPA meningiomas. The specificity of ABR testing ranges from 54% to 78% (33,36,37). Because of the relatively low incidence of vestibular schwannomas, the probability of vestibular schwannoma in a patient with an abnormal ABR result is only 4% to 18% (33,38,39).

Cerebellopontine Angle Imaging

Before the availability of gadolinium-enhanced MRI, computed tomography (CT) scanning with air contrast cisternography was the gold standard for the diagnosis of CPA tumors. Contrast-enhanced CT scanning is a relatively sensitive test for CPA tumors. The region of lower sensitivity is small intracanalicular tumors; air cisternography is often required to identify these more occult lesions. However, the morbidity of adding air cisternography is quite high (40,41). Smith et al. report that 80% of patients are symptomatic after the procedure, and 62% require 3 or more days to return to normal health (41).

Today, MRI of the internal auditory canal and CPA with Tl -weighted gadolinium enhancement has replaced the CT scan with air contrast cisternography as the gold standard in the diagnosis of vestibular schwannomas. MRI often demonstrates lesions for which conventional assessment provided ambiguous or negative results (42). MRI is also helpful in differentiating vestibular schwannomas from meningiomas (43). Meningiomas are typically sessile with a broad contact against the petrous apex, which is contrasted to the globular shape of vestibular schwannomas. Meningiomas may demonstrate hyperostosis of adjacent bone and may contain areas of calcification. Meningiomas are often eccentric to the internal auditory canal and are less likely to erode the internal auditory canal (43). A "dural tail" is often associated with meningioma but is not pathognomonic in that these dural tails have also been reported to occur with vestibular schwannomas (44,45). MRI, using a T2-weighted, fast spin-echo protocol, significantly improves the spatial resolution of the internal auditory canal and CPA. This technique has been advocated as a first-line investigation to rule out vestibular schwannomas without the need for gadolinium enhancement (46). When an equivocal T2-weighted, fast spin-echo image is obtained, the recommendation is to proceed with a Tl-weighted, gadolinium-enhanced axial sequence.

Summary of Evaluation Algorithm

'i Patients presenting with a history of explained unilateral or asymmetric sensorineural hearing loss, sudden sensorineural hearing loss, or unexplained, persistent, unilateral tinnitus are evaluated directly with MRI. The imaging includes a gadolinium-enhanced, Tl-weighted sequence and a T2-weighted, fast spin-echo sequence. ENG, ABR, electrocochleography, and audiologic site of lesion testing are not performed. Low-risk patients with mild asymmetric hearing or with a reasonable explanation for the hearing loss or tinnitus are evaluated either with an ABR or a screening T2-weighted, fast spin-echo MRI. This screening MRI can be performed at a cost similar to that of an ABR.

Patients in whom MRI cannot be obtained because of morbid obesity or retained magnetic metal are evaluated with ABR and, if abnormal, a contrast-enhanced CT scan is obtained. Air cisternography can be performed if there is a high index of suspicion and the initial CT scan does not reveal a CPA tumor.

TREATMENT OPTIONS

The treatment options for CPA tumors include surgical resection, radiation therapy, and, in elderly or high-surgical-risk patients, observation with sequential MRI.

Observation with sequential MRI is considered in patients with a vestibular schwannoma in an only hearing ear and in patients with advanced age and limited life expectancy, or significant cardiovascular, pulmonary, or other systemic disease. For such patients, the nonsurgical option of watchful waiting is a viable alternative.

A 1994 study reviewed the natural history of vestibular schwannomas in 51 patients with unilateral vestibular schwannomas who were followed by serial scanning for an average of 2.6 years (range, 0.5-11 years) (47). Thirty-nine patients (78% of the study group) demonstrated slow tumor growth rates of less than 0.2 cm per year. Of these, 16 had no growth of their tumor during the study period. One patient in the slow-growth group showed no change in tumor size for 6 years; however, the tumor then doubled in size over a 2-year period. This was the only exception to the observation that if tumor growth was demonstrated to be slow at the beginning of the study, it remained slow. Twelve patients (24%) eventually required microsurgical or radiosurgical treatment. This study suggests that up to 75% of patients who are poor surgical candidates may be successfully treated with watchful waiting. Because the follow-up period was short (an average of 2.6 years), it is recommended that MRI scans be performed 6 and 12 months after diagnosis, and then yearly, if a pattern of slow growth is established.

Since the late 1980s, there has been a surge of interest in stereotactic radiation therapy for the treatment of vestibular schwannomas. The therapy uses a focused beam of radiation to kill tumor cells while attempting to preserve the adjacent structures. Radiosurgery avoids much of the morbidity such as prolonged hospitalization, loss of productivity, cerebrospinal fluid (CSF) leaks, and wound infections associated with surgical resection of vestibular schwannomas. However, the structures adjacent to the tumors do not escape free of injury. Facial nerve paresis or complete paralysis occurs in 10% to 32% of patients, and maintenance of useful preoperative hearing is reported to occur in 50% of patients (48-52). Facial numbness occurs in 19% to 34% of patients. Other cranial nerve deficits are uncommon. Hydrocephalus requiring shunt placement occurs in 3%. It is interesting to note that the status of the hearing continues to change up to *2* years after radiosurgery. Initial hearing preservation rates are excellent, but by 2 years have dropped to 50%. The effects on neural tissue, vasculature, and presumably also on the tumor, are slowly progressive, and extended follow-up periods are necessary to evaluate long-term results. These results compare favorably with perioperative complication rates for microsurgery. There is a trend toward decreasing the radiation dose to decrease morbidity (51,53). Once again, long-term tumor control rates are not available.

The reluctance to support radiation therapy for a wide range of patients stems from the uncertainty regarding long-term tumor control. The longest available follow-up suggests a recurrence rate of approximately 17% (48). There is also the disturbing experience that when surgical excision is required postradiation because of continued tumor growth, there is an increased severity of postoperative deficits (54).

Selection of Surgical Approach

The choice of approach to resection of vestibular schwannomas and other CPA tumors is guided by the degree of residual hearing, hearing status in the contralateral ear, location of the tumor, size of the tumor, cell type, and age of the patient.

The first factor considered is the status of the patient's hearing. In choosing a hearing conservation approach (i.e., middle cranial fossa or retrosigmoid), the authors usually adhere to the 50:50 rule: less than 50 dB pure tone thresholds and better than 50% discrimination. The lack of consistency on the definition of useful hearing and the variability of the subjective appreciation of various levels of hearing loss by patients lead to controversy in applying this definition of useful hearing in the selection of approach. Patients with good hearing in the contralateral ear and less than 50% discrimination in the affected ear do not wear a hearing aid on the affected side because of the distortion. In addition, they do not maintain the ability to localize sound with greater than a 30-dB asymmetry between the two ears. Another factor on the audiogram that should be taken into account is the degree of "roll-over," which is common with these retrocochlear lesions. Roll-over is the phenomenon of diminished discrimination with increased sound intensity. Therefore, if a patient has a 40-dB hearing loss with 60% discrimination and severe roll-over, once adequately amplified, his or her discrimination will significantly deteriorate. The patient will be left with unusable hearing. There are clear exceptions to application of the 50:50 rule. In patients with poor hearing in the contralateral ear or neurofibromatosis, in which bilateral disease is common, every effort is made to preserve any residual cochlear function.

The second factor in choosing an approach is the location of the tumor. If the tumor extends into the lateral one third of the internal auditory canal and does not protrude greater than 0.5 cm into the CPA, and hearing conservation is indicated, the authors choose a middle fossa approach. The retrosigmoid approach can safely access only the medial two thirds of the internal auditory canal without damaging the labyrinth. Blevins and Jackler demonstrated that in the typical surgical exposure using a retrosigmoid approach, an average of 3.Omm (range, 1.1-5.3 mm) must be left unexposed to avoid injury to the labyrinth (55). If the tumor is more medial in the internal auditory canal, either the middle fossa or retrosigmoid approach is appropriate. In tumors extending greater than 5 mm into the CPA and if hearing conservation is indicated, the retrosigmoid approach is used. Some authors advocate an extended middle fossa approach for tumors extending greater than 1 cm into the CPA (56-58). They use a wider resection of the petrous ridge and division of the superior petrosal sinus, yielding a modest exposure of the CPA. Jackler and Pitts point out that this approach for larger tumors provides insufficient exposure of the inferior aspect of the CPA and requires vigorous and prolonged temporal lobe retraction, increasing the potential for postoperative neurologic deficits (59). Consequently, the current authors limit their use of this approach to tumors protruding less than 5 mm into the CPA.

The third factor to be considered is the tumor size. Large tumors can be accessed by either the retrosigmoid or translabyrinthine approach. The decision on approach for vestibular schwannomas greater than 2.5 cm no longer takes into account attempts at hearing preservation, given the very poor prognosis for hearing conservation, unless it is an only hearing ear. In patients with contracted mastoid cavities, high jugular bulbs, or a history of chronic otitis media, the retrosigmoid approach is chosen. In large tumors with significant inferior extension, the retrosigmoid approach is also preferred. In the absence of these factors, the translabyrinthine approach is used. The translabyrinthine approach is also used in patients with smaller tumors and no salvageable hearing.

Vestibular schwannomas account for 85% to 95% of CPA tumors. However, when a CPA tumor of other origin is suspected on the preoperative evaluation, the surgical algorithm is modified. Preservation of useful hearing with vestibular schwannomas greater than 2 cm is rare, whereas with larger meningiomas and epidermoids, preservation of auditory function can occasionally be achieved. Consequently, tumors other than vestibular schwannomas are accessed by a retrosigmoid approach.

Another factor guiding the management of vestibular schwannomas is the patient's age. In general, the middle fossa approach is avoided in patients older than 60 years of age because of the more tenuous nature of the temporal lobe dura. Elderly patients are placed at increased risk of temporal lobe injury as well as postoperative CSF fistula with the middle fossa approach. In general, elderly patients are not treated surgically or with stereotaxic radiosurgery unless the tumors are demonstrated with sequential MRI scans to be growing at a rate significant enough to interfere with the patient's projected longevity. The translabyrinthine approach is the preferred procedure in the elderly patient.

The indications for the use of stereotaxic radiosurgery remain controversial. The authors' current indications for stereotaxic radiosurgery are limited to patients who are poor surgical candidates because of underlying medical conditions. As newer protocols yield improved tumor control and reduced cranial nerve involvement, and longer-term follow-up data become available, the indications for the use of stereotaxic radiosurgery may broaden significantly.

The differences in complication rates between the various approaches also influence the choice of procedure. Informed patient input and choice of approach can only take place after a thorough discussion of the complication rates.

Complications

The surgical mortality rate before the popularization of microsurgical technique in vestibular schwannoma resection by William House was 10% to 20%. Current techniques have lowered the mortality rate to 1% to 2%. The occurrence of severe complications resulting in mortality is influenced by factors such as tumor size and complexity, patient age, and underlying medical conditions, as opposed to the surgical approach (59). With the significant reduction in mortality, much more attention has been focused on the differential morbidity from the different approaches.

Facial paralysis is one of the most dreaded of the complications from the patient's perspective. The incidence of this disfiguring complication has dropped significantly with the onset of facial nerve monitoring (60-63). Comparing results from various centers using the different approaches has been hampered by the lack of standardization in evaluation of postoperative facial function. The House-Brackmann grading system is an excellent attempt at standardization; however, subjective variations between centers interfere with the effectiveness of this tool (64). Most large series report a 95% or greater postoperative anatomic preservation of the facial nerve regardless of the surgical approach. The percentage of patients with House-Brackmann grade I or II facial function, 1 year after surgery, ranges from 70% to 90%. These statistics are easily skewed by the percentage of large tumors in the series. The incidence of normal function decreases with tumor size (65). It has been argued that the translabyrinthine approach can improve facial nerve preservation because the nerve is identified before tumor dissection. However, empirically, there is no apparent difference in long-term facial nerve outcomes using the different approaches (63).

Cerebrospinal Fluid Fistula

The incidence of CSF fistula varies considerably throughout the literature and has decreased since the late 1970s with the improvements in closure techniques. There does not appear to be a significant difference in the incidences of CSF fistula between the retrosigmoid and translabyrinthine approaches reported since the late 1970s. However, this remains controversial, with advocates of both approaches arguing lower rates of CSF fistula. The incidence of CSF fistula after the retrosigmoid and translabyrinthine approaches ranges from 7% to 21% (66-72). CSF fistula occurs significantly less frequently with the middle cranial fossa approach, with a rate of 4% to 6% (73,74).

Two thirds of CSF fistulas close with medical management and lumbar drains without the need for surgical intervention (75,76). Medical management consists of bed rest, elevation of the head of the bed 30 degrees, and stool softeners. Pressure dressings are reapplied to patients with CSF leaks after translabyrinthine approaches and to patients with CSF collections below the skin flap after any of the approaches. Lumbar drains are typically left in place for 5 days. Fistulas persisting for greater than 7 to 10 days are reex-plored and the fistula closed. There is no difference in the incidences of persistent fistula requiring surgical closure after a translabyrinthine or retrosigmoid approach (77).

Various modifications of the standard approaches have effectively reduced the frequency of postoperative fistula. Removal of the ear canal and tympanic membrane, as performed in the transotic approach described by Fisch, allows for excellent exposure of the eustachian tube. Using this exposure, the middle ear mucosa is removed, the eustachian tube mucosa is inverted, and the orifice of the eustachian tube is securely sealed. This modification has been reported to decrease the incidence of CSF fistula to as low as 2% (78). The authors include this additional step in their translabyrinthine approach.

The frequency of CSF fistula can be diminished by careful inspection of the temporal bone for exposed air cells. Symon and Pell reported a reduction in the incidence of CSF fistula from 16% to 5% by packing air cells with bone dust and Surgicel soaked with fibrin glue (79). Sealing of air cells with ionomeric bone cement has also been reported to reduce significantly the incidence of CSF fistula (80). Regardless of whether bone wax or one of these other materials is used to seal the exposed air cells, the key factor in minimizing postoperative CSF fistula is the identification of exposed air cells. The angle of view, using the operating microscope, frequently misses exposed air cells with the retrosigmoid approach. Improved detection and sealing of these air cells can be achieved using 30-degree endoscopes, thereby reducing the incidence of postoperative CSF fistula.

Headache

Persistent, severe, postoperative headache occurs more frequently after vestibular schwannoma removal using the retrosigmoid approach. Harner et al. reported postoperative headache in 23% of patients at 3 months, 16% at 1 year; and 9% at 2 years (81). One of the factors that contributes to the pathophysiology of postoperative headache is the resection of the bone window. The absent bone window allows adhesions to develop between the dura and the prior muscle attachments to the skull base. This potential relationship to postoperative headache has been addressed by replacing the bone window with bone chips, methylmethacrylate, calcium phosphate cement, or other synthetic materials (82-84). Harner et al. reduced their incidence of postoperative headache from 17% to 4% by performing a methylmethacrylate cranioplasty (84).

TRANSLABYRINTHINE APPROACH

Removal of vestibular schwannomas by a translabyrinthine approach was developed and popularized by William House in the early 1960s (3). This technique has grown in acceptance because of its many advantages. The main advantage is excellent access to the CPA without retraction of the cerebellum. The translabyrinthine approach provides easy identification of the facial nerve in a constant location before tumor dissection. The approach minimizes the risk of recurrence of tumor as a result of residual tumor in the lateral aspect of the internal auditory canal. Using the current techniques of eustachian tube ablation, the risk of CSF fistula is less than with the retrosigmoid approach. One of the most significant advantages of the translabyrinthine approach is the reduction of postoperative headache, as discussed previously. The obvious disadvantage of the translabyrinthine approach is the obligate sacrifice of hearing. Other limitations of the approach include the reduced exposure in patients with a high jugular bulb or significantly contracted mastoid air cell system.

Preparation

At the outset of the procedure, the MR I scan is hung in the view box and the name of the patient and the site of the lesion are verified. Perioperative antibiotics are not routinely administered. Dexamethasone 0.1 mg/kg body weight is administered intravenously every 8 hours for 48 hours, with the first dose given before surgery. General anesthesia is induced and maintained by tracheal intubation after the administration of a short-acting muscle relaxant. No further muscle relaxants are used for the remainder of the procedure. The patient is placed supine on the operating table with the head turned away from the surgeon approximately 45 degrees. The patient's head is placed in Mayfield tongs with the neck slightly extended. The patient's hair is shaved 3 cm above the auricle and 6 cm posteriorly. The ear canal is injected with 2 ml of 1% lidocaine with epinephrine (1:100,000) in a four-quadrant block. The ear is also injected postauricularly. Two monopolar electromyography needle electrodes are inserted into the orbicularis oris and a second set into the orbicularis oculi. A fifth electrode is placed in the skin over the sternum as a ground. The electrodes are secured with tape. The left lower quadrant of the abdomen or the periumbilical area is prepared and draped for harvesting of the abdominal fat graft. If prior abdominal scars are available, these may be used instead. The entire postauricular region, auricle, external auditory canal, and preauricular skin is cleaned with a standard povidone-iodine preparation. This is followed by the application of benzoin, which is allowed to dry. In addition to the normal draping, an lodoban plastic drape is used to cover the entire surgical field.

Procedure

A curved postauricular incision is made from the mastoid tip up to a point 1 cm above the auricle. Posteriorly, the incision is placed 3 cm posterior to the postauricular crease (Fig. 1). The incision is carried down through the skin and subcutaneous tissue, but not through the periosteum overlying the mastoid cortex. The postauricular skin flap is elevated forward up to the skin of the external auditory canal. An incision is made through the periosteum 2 cm posteriorly along the inferior temporal line. A second incision 1.5 cm inferior to the inferior temporal line is created parallel to this initial incision. The two parallel incisions are connected posteriorly with a perpendicular incision, creating an anteriorly pedicled periosteal flap attached to the external auditory canal (see Fig. 1). The periosteal flap is elevated up to the external auditory canal. The external auditory canal is then transected medial to the attachment of the periosteal flap (Fig. 2). After sectioning of the anterior canal wall, the plane of dissection is carried laterally between the parotid gland and the cartilaginous canal. The auricle is reflected anteriorly. The skin of the lateral portion of the external auditory canal is dissected off of the cartilage and everted out of the external auditory canal. The cartilage is then excised. The excess canal skin is excised and the remaining skin closed with 3-0 Vicryl suture. The second layer of closure is provided by the periosteal flap, which is reflected medial to the external auditory canal and sutured anterior, inferior, and superior to the opening into the canal (see Fig. 2). A moist sponge is placed



FIG. 1. An incision is created 3 cm posterior to the postauricular crease and extended 1 cm above the superior aspect of the helix. The incision is carried down to the temporalis fascia superiorly and the periosteum covering the mastoid cortex interiorly. Parallel, horizontal incisions are created above and below the level of the external auditory canal. The incisions extend 2 cm posteriorly, at which point they are connected by a vertical incision.

over the periosteal flap and two Weitlander retractors are positioned to maintain exposure.

A complete mastoidectomy is performed with a large cutting bur, skeletonizing the tegmen superiorly and the sigmoid sinus posteriorly (Fig. 3). The skin of the bony external auditory canal is elevated down to the level of the annulus and the tympanic membrane elevated (Fig. 4). The incudostapedial joint is separated and the incus, malleus, and tympanic membrane resected. The incus is saved in a saline-soaked sponge for later use.

The entire sigmoid sinus is skeletonized, leaving a thin sheet of bone covering the sinus laterally (Fig. 5). Dura is exposed anterior to the sigmoid sinus and for 2 cm posterior to the sinus. The sinus is exposed superiorly at the junction of the superior petrosal sinus and transverse sinus, and inferiorly, adjacent to the retrofacial air cell tract. Creating this circumferential trough allows depression of the sigmoid sinus while maintaining a protective barrier against the drill shaft later in the procedure. This technique was originally described by William House, and the protective sheet of bone is now referred to as "Bill's island." The remaining air cells of the mastoid tip are removed, as are the air cells of the retrofacial air cell tract. , ,

A labyrinthectomy is performed with a cutting bur, beginning with the horizontal semicircular canal, then the posterior semicircular canal, and finally, the superior semicircular canal (Fig. 6). A coarse diamond bur is used to skeletonize the second genu of the facial nerve. Drilling proceeds superior and inferior to the internal auditory canal to skeletonize the canal 210 degrees along the superior, posterior, and inferior circumference (Fig. 7). The dissection is carried medially to include the posterosuperior and posteroinferior lips of the porus acusticus. The jugular bulb is identified and the superolateral surface skeletonized as well. The cochlear aqueduct is an important landmark in this region. The aqueduct proceeds from the medial wall of the jugular foramen superomedially to the basal turn of the cochlea adjacent to the round window. At the level of dissection, it lies inferior to the porus acusticus and superior to the jugular bulb. The cochlear aqueduct remains superior and lateral to cranial nerves IX, X, and XI, as they exit the jugular foramen. Consequently, minimal bone is removed anteromedial and inferior to the cochlear aqueduct to minimize injury to these nerves. A thin sheet of bone is left covering the posterior fossa dura, intralabyrinthine section of the facial nerve, and internal auditory canal until the entire bony dissection has



FIG. 2. The periosteum posterior to the ear canal is elevated up to the ear canal and the ear canal is severed medial to the attachment of the periosteum. The ear canal is severed at the bony-cartilaginous junction. The lateral canal skin is elevated and reflected out of the external auditory canal. The skin is sutured laterally and the periosteal flap is reflected over the medial aspect of the canal and sutured anterior to the anterior lip of the canal, creating a two-layer closure.



FIG. 3. A complete mastoidectomy is performed, skeletonizing the legmen superiorly and the sigmoid sinus posteriorly.


Tympanic membrane
Malleus
Incus

FIG. 4. The skin of the external auditory canal is elevated down to the annulus and the annulus raised. The incu-dostapedial joint is then separated and the malleus and the remainder of the ear canal skin are resected with the tympanic membrane.


Posterior canal wall
Horizontal semicircular canal
Superior semicircular canal
Posterior semicircular canal
Bill's island

FIG. 5. The sigmoid sinus is skeletonized, leaving only a thin sheet of bone covering the sinus laterally. Dura is exposed anterior and *2* cm posterior to the sigmoid sinus.



e'ina

FIG. 6. A labyrinthectomy is performed with *a* cutting bur and the vestibule opened.

, ;ea *s* ilia 10



I

FIG. 7. The internal auditory canal is skeletonized with a coarse diamond bur. The canal is skeletonized 210 degrees along the superior, posterior, and inferior circumference. Interiorly, the dissection proceeds between the jugular bulb and the inferior aspect of the internal auditory canal.



FIG. 8. After exposure of the posterior fossa dura and complete removal of the bone covering the skeletonized portion of the internal auditory canal, dural incisions are created. At the lateral aspect of the internal auditory canal, the facial nerve is separated from the superior vestibular nerve by the vertical crest, or "Bill's bar."

been completed, to minimize inadvertent injury to the underlying structures. The distal portion of the internal auditory canal is skeletonized as it projects laterally.

The final area of bony dissection is superior to the lateral portion of the internal auditory canal in the region of the intralabyrinthine portion of the facial nerve. The facial nerve exits the lateral portion of the internal auditory canal superior and slightly anterior to the superior vestibular nerve. The two nerves are separated by a bony septum, the vertical crest or "Bill's bar" (Fig. 8). It is at this point that the facial nerve enters the intralabyrinthine portion of the fallopian canal, the narrowest section of the pathway. To decrease the incidence of delayed postoperative facial paresis, this intralabyrinthine portion of the facial nerve is decompressed.

The remaining eggshell of bone covering the dura between the lateral sinus and porus acusticus is removed with a Duckbill elevator. To facilitate removal of bone covering the dura between the sinus and porus acusticus, the lateral sinus is gently compressed. This maneuver improves the exposure for drilling and also increases the anteroposterior dimension of the eventual window to the CPA. A Greenberg retractor is occasionally used to aid in the retraction. The bone covering the posterior fossa dura anterior to the lateral sinus is removed superiorly up until the superior petrosal sinus. An eggshell sheet of bone is left intact over the middle fossa dura. If additional superior exposure is required, this remaining sheet of tegmen can be removed and the temporal lobe dura retracted superiorly. All of the remaining bone covering the posterior 210 degrees of the internal auditory-canal is elevated off the dura and removed. The entire wound and mastoid cavity are thoroughly irrigated with bacitracin solution to decrease the risk of postoperative infection and minimize subsequent CSF contamination with bone dust.

An incision is made in the dura extending from the sismoid sinus to the porus acusticus with Jacobson scissors (see Fig. 8). The dura is elevated with a sharp hook to minimize the risk of injury to an underlying vessel. The undersurface of the dura is inspected as the dura is cut to avoid injury to any underlying vascular structures. The edges of the dura are cauterized using bipolar cautery. The dura is quite thick in the region around the porus acusticus, and these fibers are also severed.

The facial nerve is most easily identified in a relatively constant location in the intralabyrinthine segment of the fallopian canal. Verification of the position of the facial nerve is aided by stimulation of the nerve with the nerve probe set at 0.05 mA. Stimulation at this point in the procedure also verifies that the facial nerve monitor system is functioning properly. Once the facial nerve is clearly delineated, the superior vestibular nerve is sharply dissected away from the facial nerve with a tab or sickle knife. The tumor in the internal auditory canal is dissected off the facial nerve (Fig. 9i. Typically, the facial nerve splays out anterior to the tumor as it is reflected anteriorly around the anterior lip of the porus acusticus. Adhesions to the nerve are dissected sharply with a round knife or scissors. Bipolar cautery is minimized in



FIG, 9. The vestibular schwan-noma is visualized within the internal auditory canal extending into the cerebellopontine angle. The distal free end of the vestibular nerve and tumor are dissected out of the internal auditory canal and off of the facial nerve.

controlling hemorrhage adjacent to the nerve; cottonoids or epinephrine-soaked Gelfoam is the first-line method for hemostasis adjacent to the nerve. Moist cottonoids are placed over the cerebellum. Once the tumor in me internal auditory canal is separated from the facial nerve, a piece is sent to pathology for frozen-section examination. The centers of small tumors are debulked with forceps, bipolar cautery, and suction. In larger tumors, intracapsular debulking is accomplished with the addition of the Cavitron ultrasonic aspirator. In larger tumors, additional exposure may be required in the CPA. This can be achieved with gentle retraction of the cerebellum posteriorly 1 to 2 cm. Retraction of the cerebellum can be minimized by draining CSF from the cisterna magna as well as by the infusion'of intravenous mannitol. If CSF does not flow readily from the CPA after incision of the overlying dura, the inferior aspect of the cerebellum is elevated and the arachnoid over the cisterna magna is incised.

Once most of the intracapsular tumor mass is debulked, the tumor capsule is dissected off the remainder of the course of the facial nerve and brainstem. Small penetrating branches of the anterior internal carotid artery are cauterized with the bipolar cautery in the capsule of the tumor and incised with microscissors. Vessels coursing over the capsule, but not penetrating, are dissected free. A loop of anterior inferior cerebellar artery usually courses between cranial nerves VIT and VIII. Cranial nerve VIII is identified and cauterized with bipolar cautery as it exits the tumor. The nerve is severed with microscissors. At the conclusion of the resection, cranial nerves V, VII, VIII, IX, X, and **XI** usually are visualized (Fig. 10).

Closure

The mucosa of the middle ear and protympanum is removed. The mucosa, lining the eustachian tube, is inverted as distally as possible. A small piece of temporalis muscle is harvested and inserted into the eustachian tube, filling the entire lumen. The long process of the incus is snipped and the incus is inserted into the eustachian tube, wedging it into place. A small piece of temporalis fascia is then placed over the incus and eusiachian tube. The flaps of posterior fossa dura are reapproximated and a large piece of temporalis fascia is placed over the dura and draped over the facial nerve as it proceeds laterally in the internal auditory canal. The abdominal fat graft is trimmed to fill the entire mastoid cavity and middle ear cleft. The cavity should be mildly over-packed.

The mastoid periosteum is sutured with 3-0 Vicryl suture, forming a watertight closure. The skin is closed with 4-0 nylon suture. No drains are used for the mastoid wound. A pressure dressing is applied and left in place for 5 days. The abdominal fat graft site is closed with a deep closure of interrupted 3-0 Vicryl suture and a 4-0 nylon suture skin closure. The abdominal wound is drained with a Penrose drain and a pressure dressing applied.



FIG. 10. The vestibular schwannoma has been resected. The facial nerve is visualized extending from the brainstem into the intralabyrinthine portion of the fallopian canal. The vestibular nerves have been resected with the tumor and the lower cranial nerves are visualized entering the jugular foramen.

Postoperative Care

Overnight, the patient is monitored in the intensive care unit and typically transferred out of intensive care on the first postoperative day. The patient is maintained on dexamethasone (0.1 mg/kg body weight) for 48 hours after surgery. Perioperative antibiotics are not routinely administered. The patient is maintained on Colace to minimize straining with bowel movements. A combination of metoclopramide and droperidol or ondansetron is used for nausea. Diazepam is used to control vertigo on a PRN basis. The head of the bed is elevated 30 degrees at all times. The physical therapist trained in techniques of vestibular rehabilitation begins working with the patient before discharge from the hospital and continues therapy after discharge as needed. If a patient has a postoperative facial palsy, an eye humidification chamber is applied. Lacrilube eye ointment is used at night and Celluvisc eye drops are applied every 2 hours while awake. This regimen continues at home until the facial palsy has resolved.

TRANSOTIC APPROACH

The initial exposure for the transotic approach, as described by Fisch, includes resection and two-layer closure of the external auditory canal, resection of the tympanic membrane and ossicles, and enclosure of the eustachian tube. The authors use this initial exposure in the translabyrinthine approach as well, to reduce the incidence of postoperative CSF fistula. This portion of the technique is described in the previous section. The transotic approach is an extension beyond the translabyrinthine technique. The entire translabyrinthine approach is completed before the transotic portion. The additional exposure of the transotic approach is achieved by drilling through the cochlea, skeletonizing the external auditory canal anteriorly. The bone between the external auditory canal posteriorly and the carotid artery anteriorly is removed with a cutting bur, followed by a coarse diamond bur (Fig. 11). The hypotympanic bone superior to the jugular bulb and posterior to the carotid artery is removed. Additional bone removal in the region of the retrofacial air cell track results in a bridge of suspended bone encasing the descending portion of the facial nerve (see Fig. 11). As in all of the approaches, the direction of bur rotation is away from the facial nerve to avoid inadvertent injury to the nerve. The dura is not incised until all of the bony work is completed and the bony cavity is copiously irrigated with bacitracin solution. The thin eggshell of bone covering the internal auditory canal is removed with a microraspatory or small round knife. An incision in the dura is created to extend from anterior to the sigmoid sinus through the posterior ring of fibrous tissue of the porus acusticus, as was described for the translabyrinthine approach. In addition, the fibrous ring of the porus acusticus is severed anteriorly and the dura is cut anteroinferior to the internal auditory canal. The dural edges are reflected and secured with 4-0 silk sutures.

This technique allows 300 degrees of exposure of the internal auditory canal. The anterosuperior wall of the internal auditory canal is the only segment to remain. Dissection anterior to the internal auditory canal allows for visualization of the facial nerve as it is splayed anteriorly before entering



FIG. 11. The cochlea is removed, skeletonizing the internal carotid artery anteriorly, the jugular bulb inferi-orly, and the internal auditory canal posteriorly and superiorly. Only a thin sheet of bone remains over the facial nerve to protect it from the shaft of the bur. The internal auditory canal is skeletonized 300 degrees around the circumference of the internal auditory canal, leaving only a small segment of bone in the anterosuperior wall of the internal auditory canal.

the porus acusticus. Tumor dissection is performed in a way similar to the technique described for the translabyrinthine approach. The technique differs in the increased exposure anteriorly and the visualization of the facial nerve as it is splayed over the anterior capsule of the tumor.

After completion of tumor removal, the facial nerve is stimulated at the brainstem. If good stimulation occurs with 0.05 mA, the prognosis for normal postoperative facial function is excellent.

Closure for the transotic approach is the same as that used for the translabyrinthine approach. A large piece of temporalis fascia is placed over the exposed area of dura and dural defect. A second, smaller piece of fascia is placed anterior to the facial nerve over the dural defect. After inversion of the eustachian tube mucosa into the eustachian tube, muscle is inserted into the orifice. The muscle is wedged in place with the modified incus. A third piece of temporalis fascia is then placed over the protympanum, covering the eustachian tube orifice. An abdominal fat graft is divided into two pieces. The first piece is wedged firmly under the bony canal of the facial nerve and used to obliterate the medial portion of the mastoid cavity. The second piece of abdominal fat is then placed lateral to the first graft and obliterates the remainder of the cavity. Again, the cavity is slightly overfilled to minimize dead space and potential CSF leakage into the cavity. The skin is closed in two layers and a pressure dressing is applied for 5 days.

RETROSIGMOID APPROACH

The retrosigmoid approach to the posterior cranial fossa is the latest of numerous modifications of the classic suboccipital approach originally popularized by Harvey Gushing (1). The approach was modified by Dandy in 1941, with a significant reduction in mortality and morbidity (85). The approach traditionally used a sitting position and a large bone window extending from the midline to the sigmoid sinus, and necessitated partial cerebellar resection. With the advent of the operating microscope and accompanying improvement in microsurgical technique, improved results were obtainable with less morbidity and smaller craniotomies. The suboccipital approach is augmented by the "transmeatal" opening of the internal auditory canal to gain access to the intracanalicular portion of the tumor. In some temporal bones, the anatomic configuration of the labyrinth and canal makes it impossible to expose the most lateral portion of the tumor without entering the labyrinth (55). Failure to access and resect tumor in the lateral aspect of the internal auditory canal may result in recurrent tumor.

Preparation

The preparation for the retrosigmoid approach is similar to that described for the translabyrinthine approach. At the outset of the procedure, the MRI scan is hung in the view box and the name of the patient and the site of the lesion are verified. Perioperative antibiotics are not routinely administered. Dexamethasone 0.1 mg/kg body weight is administered intravenously every 8 hours for 48 hours, with the first dose given before surgery. General anesthesia is induced and maintained by tracheal intubation after the administration of a short-acting muscle relaxant. No further muscle relaxants are used for the remainder of the procedure.

The first important step in the suboccipital approach is surgical positioning, because an oblique line of sight from a



FIG. 12. The patient is placed in the three-quarters lateral position with the head placed in Mayfield tongs. A "lazy-S" incision is created four fingerbreadths behind the postauricular crease.

posterior lateral viewpoint is necessary for adequate exposure of the CPA. The patient is placed in the three-quarters lateral, or park bench position, with the head in pinions (Fig. 12). Care is taken to cushion and support the upper leg and arm to prevent pressure sores. A roll is placed under the dependent axilla, and an eggcrate or similar mattress pad is suggested. The patient should be firmly secured to the table so that it may be rotated toward and away from the surgeon. This is achieved with straps across the shoulders, hips, and legs. The shoulder is gently depressed using tape extending from the shoulder to the foot of the bed. The Mayfield head rest with pinions is engaged with the dual pins placed on the occiput, and the single pin on the forehead. The spine is maintained in a straight line; there is no lateral twisting of the head. A 4-cm rim of hair is shaved above and behind the ear. The facial and auditory function monitors are then positioned, before sterile preparation. , . *tl* _......;.

Procedure

The surgical incision is *a* "lazy-S" configuration four fingerbreadths behind the postauricular crease, extending below the bony occiput into the upper neck (see Fig. 12). After the subcutaneous layer has been divided, a small amount of undermining is performed, in anticipation of a two-layer closure (Fig. 13). The insertions of the neck musculature are freed from the skull with electrocautery and reflected inferiorly. Dissection proceeds onto the inferior surface of the occiput; the periosteum is elevated off the lateral mastoid and occiput, along with the muscular attachments. Self-retaining retractors are inserted, one in the skin, and one in the muscular layer.

A craniotomy is then created with the sigmoid sinus as its anterior border and the transverse sinus as its superior border, measuring approximately 4 X 4 cm in extent (Fig. 14). Either a craniotomy or craniectomy may be performed. If a craniotome is used to create a bone flap, it is still prudent to use a bur when removing bone over the sigmoid sinus (Fig. 15). This allows careful dissection of the delicate dural sinus and emissary vein with less risk of bleeding, and easier exposure when bleeding occurs. Mastoid air cells are usually encountered lateral or anterior to the sigmoid sinus. They should not be avoided because of a concern over CSF leak, because the sinus must be well exposed to gain adequate anterior exposure. The air cells are occluded with bone wax at the end of the procedure. Once the bone has been removed, the dura is opened. The dural incision forms an anteriorly pedicled dural flap (Fig. 16). The corners of the dural flaps are retracted with silk stitches. A moist cottonoid pledget is placed over the cerebellum and a flat blade retractor is used gently to retract the cerebellum. The arachnoid tissue is incised and decompression of the posterior fossa is achieved at the cisterna magna inferiorly or at the CPA cistern. CSF is



FIG. 13. The skin and subcutaneous tissue flaps are elevated and retracted with a self-retaining retractor.



FIG. 14, A 4 x 4 cm craniotomy is created with the sigmoid sinus as the anterior border and the transverse sinus as the superior border.

__ .i

W



FIG. 15. The transverse sinus and sigmoid sinus are skeletonized using large cutting and coarse diamond burs.



FIG. 16. Dural incisions form an anteriorly pedicled dural flap that is secured with silk suture.



FIG. 17. After the lysis of arachnoid adhesions, the flat-blade retractor is advanced into the cerebeltopontine angle. The tumor is visualized in the cerebello-pontine angle obscuring the view of the porus acusticus. The facial nerve is depicted splayed out over the anterior surface of the tumor.

aspirated until adequate working space is exposed. Some surgeons choose to use mannitol to enhance intracranial decompression; this is usually administered in a dose of 1 gm/kg body weight intravenously before opening the dura. Arachnoid adhesions between the cerebellum and dura are lysed, and the flat-blade retractor is advanced into the CPA. When the tumor (or the audiovestibular nerve complex) can be well visualized, the retractor is stabilized, using a large, saline-soaked cottonoid to protect the cerebellum (Fig. 17).

With small tumors, several landmarks may be visible at this time. Cranial nerves VII and VIII are seen passing from the brainstem into the internal auditory canal. Superior to this, the trigeminal nerve may be seen, with the abducens and trochlear nerves anteriorly. Interiorly, cranial nerves IX, X, and XI create a fan-shaped formation before they pass into the jugular formation, and are covered by an arachnoid sheath. Larger tumors often obscure these landmarks and require debulking before all of these structures can be identified. Once adequate exposure of the posterior face of the petrous bone and the operculum is achieved, the dura overlying the internal auditory canal is incised, elevated, and reflected as superiorly and inferiorly based flaps (Fig. 18).

Before exposure of the internal auditory canal, tumors greater than 1.5 cm, measured from the porus acusticus, are debulked with a Cavitron ultrasonic aspirator (Fig. 19). Tumor debulking remains within the confines of the capsule to avoid inadvertent injury to surrounding structures. Smaller tumors are debulked with bipolar cautery and cup forceps. A biopsy is obtained at this point in the procedure and sent for frozen-section histologic examination.

Bone removal is then performed with a 3- or 4-mm coarse diamond bur and copious suction-irrigation. In hearing conservation procedures, it is imperative to avoid entering the posterior semicircular canal and vestibule. One important landmark is the operculum, a bony projection along the posterior face of the petrous bone at which point the endolymphatic duct enters the bone (Fig. 20), Remaining medial and anterior to the endolymphatic duct and following it through its "inverted J"-shaped course reduces the risk of inadvertent entry into the vestibule and posterior semicircular canal. As the bony dissection proceeds, care is taken to identify the "blue lines" of these structures before their damage. In general, up to 7 mm of bone can be removed safely from the medial aspect of the internal auditory canal. The anatomy of the labyrinth and degree of lateral extension of the tumor may prohibit hearing conservation. Often, undesirable anatomy and very lateral tumor extension can be assessed before surgery on the gadolinium-enhanced MRI. In situations in which patients have no usable hearing or extremely poor prognostic factors for useful hearing conservation, wider bone removal is performed. If the most lateral extent of tumor cannot be accessed without labyrinthine injury because of the anatomic relationships, the hearing is sacrificed.

As the internal auditory canal is skeletonized along its entire length, an eggshell thickness of bone is left over the dura. This final layer of bone is removed by careful dissection with



FIG. 18. Incisions are created in the dura over the petrous bone, creating superiorly and inferiorly based flaps.



FIG. 19. The Cavitron ultrasonic aspirator is used to de-bulk the intracapsular tumor in the cerebellopontine angle.



FIG. 20. The internal auditory canal is skeletonized using the operculum and endolymphatic duct as landmarks. Dissection of bone is performed medial and anterior to the endolymphatic duct to avoid inadvertent entry into the vestibule and posterior semicircular canal. In general, up to 7 mm of bone can be removed safely from the medial aspect of the internal auditory canal.

a diamond bur. **The** area is then copiously irrigated to remove all bone dust.

At the lateral extent of the internal auditory canal, "Bill's bar" is identified, which delineates the superior vestibular and facial nerves. The location of the facial nerve is ascertained by stimulation. The dura of the internal auditory canal is incised along the edges of the canal. The superior vestibular nerve is removed from its attachments to the labyrinth, and retracted medially. Dissection of tumor and vestibular nerve then proceeds in a lateral to medial direction along the length of the canal (Fig. 21). At this point, the location of the facial nerve has been verified. It typically is displaced anteriorly and splayed over the anterior surface of the tumor capsule as it exits the porus.

After removal of the intracanalicular portion of the tumor, the cerebellopontine component of the tumor is debulked. Depending on the extent of tumor, debulking is performed with cup forceps and bipolar cautery or the Cavitron ultrasonic aspirator. As the contents of the tumor are excised, the capsule is rolled inward and dissected off of the underlying facial and cochlear nerves. As debulking progresses, the brainstem origination of cranial nerves VII and VIII is identified and the tumor dissected off of the brainstem.



FIG. 21. The vestibular nerves and intracanalicular tumor are dissected off of the facial and cochlear nerves.



FIG. 22. Endoscopy is performed with a 30-degree, 2.7-mm ridged endoscope to inspect carefully the bone edges around the internal auditory canal. All visualized air cells are sealed with bone wax.

Closure

After completion of tumor removal, a careful check is performed to ensure hemostasis. Valsalva maneuvers and irrigation are used to identify sites of bleeding and bipolar cautery and hemostatic agents such as Surgicel or Avitene are used as necessary.

Bone wax is carefully placed into all air cells around the internal auditory canal and the mastoid air cells at the edge of the craniotomy to prevent CSF leak through the mastoid and middle ear. A continuous sheet of the bone wax reduces the risk of gaps allowing penetration of CSF into air cells (Fig. 22). It is often difficult to see the entire face of bone around the internal auditory canal to inspect for exposed air cells because of the angle of exposure. Consequently, a 30-degree, 2.7-mm rigid endoscope is used to inspect the bone and ensure that the air cells are sealed (see Fig. 22).

The dura that had originally been on the face of the petrous apex, overlying the internal auditory canal, is reflected into the surgical defect. A piece of temporalis fascia is then placed over the internal auditory canal. The large, anteriorly based dural flap is closed with a watertight closure, if possible, using 4-0 silk. The craniotomy bone flap is secured into position with nylon sutures from the bone flap to the edges of the craniotomy. The bone chips that were saved in normal saline are placed around the remaining exposed perimeter (Fig. 23). The attachments of the neck musculature are reat-

продолжение

I

I



FIG. 23. The craniotomy bone flap and bone chips are replaced into the craniotomy defect before wound closure.

продолжение

tached to the skull by suspension sutures, which pass through holes at the edge of the craniotomy. The skin is closed in three layers: galea, subcutaneous, and skin. A pressure dressing is applied, and left in position for 48 hours.

Postoperative Care

The postoperative management is the same as with the translabyrinthine approach, as outline previously.

MIDDLE FOSSA APPROACH

The middle fossa approach to the internal auditory canal was first described by Parry in 1904 (86). It was not until the 1960s, after the advent of the operating microscope, that William House popularized this approach for resection of vestibular schwannomas. The approach is ideal for small intracanalicular tumors. However, it was not until the development of gadolinium-enhanced MRI that small intracanalicu-lar tumors were frequently identified. Consequently, since the mid-1980s, the frequency of middle fossa approaches has increased significantly. The middle fossa approach is primarily used in candidates for hearing preservation, for intracanalicular lesions that extend no more than 5 mm into the CPA (see section on Selection of Surgical Approach). Elderly patients are poor candidates for middle fossa surgery because of the more tenuous nature of their dura, and because retraction of the temporal lobe is more likely to cause postoperative seizures. A relative contraindication to this approach is a tumor originating from the inferior vestibular nerve. The tumor location is inferred from ENG findings (further discussion of this issue is found in the Diagnostic

auditory monitoring devices are placed, and sterile preparation is performed. Mannitol is useful to decrease intracranial pressure and should be administered intravenously at the beginning of the craniotomy (1 g/kg body weight).

Testing section). The reason a tumor on the inferior vestibular nerve is more difficult to approach through the middle fossa is because the facial nerve is between the surgeon and the tumor. This makes tumor dissection with cranial nerve preservation more difficult.

Preparation

In the middle fossa approach, the surgeon is positioned at the vertex of the patient's head, facing down the long axis of the table. The patient is positioned supine, with the head turned so the affected ear is upward. If there is concern that torsion of the neck is excessive, the three-quarters lateral position (described for the suboccipital approach) may be used. The Mayfield head rest with pinions affords stability and accessibility. It is engaged with the dual pins on the contralateral occiput, and the single pin on the ipsilateral supraorbital rim. The scalp is shaved from the ipsilateral mid-pupillary line, to the vertex, and extending to the occipital condyle. In this fashion, almost half of the scalp is exposed. Facial and

Procedure

The "lazy-S" skin incision extends from the preauricular crease to the vertex, first extending anteriorly, then posteriorly (Fig. 24). The skin flaps are undermined in the plane above the temporalis fascia, and held with Weitlander self-retaining retractors. The temporalis fascia is reflected inferi-orly (see Fig. 24). The temporalis muscle is split vertically and elevated off of the squamosal portion of the temporal bone with a wide periosteal elevator. Dissection should extend underneath the zygomatic arch to allow adequate exposure for the craniotomy. The self-retaining retractors are adjusted to hold both muscle and skin.

A bone window is created with a 5- or 6-mm cutting bur and suction irrigation. This bone window is 4 X 4 cm in size and is set at the level of the zygomatic root (Fig. 25). Two thirds of the window is anterior to the vertical plane of the external auditory canal, and one third of the window is posterior to the canal. This relationship is important because it is usually the anterior extent of the exposure that is most difficult. The cutting bur is used to remove the bone around the edges of the bone flap until only a thin membrane of bone remains. Using a coarse diamond bur, dura is exposed around the perimeter of the bone flap. The window of bone is then elevated with the joker, and the dura tethered to the undersurface of the edges of the craniotomy is dissected free (Fig. 26). At the time the bone flap is removed, it is convenient to create holes in the edge of the flap and the craniotomy that will be used to suture the flap into position at the end of the procedure. A rongeur is used to remove the bone at the inferior edge of the craniotomy to the level of the middle fossa floor (Fig. 27). This allows for the optimal surgical line of site with minimal temporal lobe retraction.

The House-Urban middle fossa retractor is engaged with the prongs in the edge of the craniotomy. The blade is gradually advanced as the dura is elevated off the floor of the middle fossa (Fig. 28). It is common to encounter dural venous bleeding at the anterior extent of the dissection. This can usually be controlled with a hemostatic agent such as Surgicel. The landmarks in the middle fossa are the middle meningeal artery at the foramen spinosum, the greater superficial petrosal nerve at the facial hiatus, and the arcuate eminence (see Fig. 28). The geniculate ganglion may be exposed without a bony covering on the floor of the middle fossa, so care should be exercised during dural elevation. When these landmarks have been identified, the retractor blade is stabilized.

The landmark for the superior semicircular canal is the

I



FIG. 24. A "lazy-S" skin incision extends from the preauricular crease toward the vertex. The incision is carried down to the temporalis fascia, which is elevated and reflected inferiorly. The temporalis muscle is split vertically, anterior to the plane of the external auditory canal.



FIG. 25. A 4 x 4 cm window is created in the squamosal portion of the temporal bone. Two thirds of the window is anterior to the vertical plane of the external auditory canal, and one third is posterior to the canal.



FIG. 26. Dura tethered to the undersurface of the edges of the craniotomy is dissected free around the perimeter of the window.



FIG. 27. Bone rongeurs are used to remove the remaining portion of the squamosal bone down to the level of the tegmen. Removal of this lip of bone provides an optimal surgical line of site with minimal temporal bone retraction.


Greater superficial petrosal nerve
Superior semicircular canal
Arcuate eminence
Internal auditory canal

FIG. 28. Dura of the middle cranial fossa is elevated off the petrous bone. The locations of the greater superficial petrosal nerve, internal auditory canal, and superior semicircular canal have been ghosted in this illustration.

arcuate eminence (see Fig. 28), but the precise location of the canal does not uniformly correspond with the arcuate eminence. A coronal CT scan may be helpful in ascertaining the relationship between the two. It will show the contours of the middle fossa floor as they relate to the superior semicircular canal and the distance between the superior semicircular canal and the floor of the middle fossa. The canal may have very little bone coverage and can be seen as a blue line after simple dural elevation, or there may be a large number of air cells between the canal and the surface of the tegmen. If the superior semicircular canal cannot be located by drilling over the arcuate eminence, two other methods may be considered. First, the tegmen tympani may be opened, exposing the ossicles. The location of the superior semicircular canal can be established by the spatial relationships (Fig. 29). Second, the greater superficial petrosal nerve can be followed retrograde back through the facial hiatus to the geniculate ganglion. The intralabyrinthine portion of the facial nerve passes between the cochlea and the ampulla of the superior semicircular canal.

The bone over the superior semicircular canal is removed using suction irrigation and diamond burs. A 4-mm bur is a good choice for the initial dissection. A light medial-to-lateral stroke is used until the blue line of the superior canal is identified. After the superior canal has been identified, dissection proceeds along the "meatal plane," which is the bone within a 60-degree angle from the blue line of the superior canal (Fig. 30). Drilling within the confines of this plane reduces the risk of inadvertent injury to the cochlea. Note that much wider drilling may be performed medially, whereas at the lateral extent of the internal auditory canal, there is very little space between the cochlea and ampulla of the superior semicircular canal. The bur should hug the line of the superior canal as bone removal progresses. The dissection will appear quite deep before the internal auditory canal is encountered. Bone should be removed 180 degrees around the internal auditory canal, from the lateral aspect of the meatus to the porus acusticus. An eggshell thickness of bone should be left on the dura. The last steps are in exposure of the canal is careful removal of this bone and copious irrigation to remove bone dust (Fig. 31).

At the most lateral extent of the internal auditory canal the vertical crest or "Bill's bar" is identified, with the facial nerve anteriorly and the superior vestibular nerve posteriorly (see Fig. 31). The location of the facial nerve is confirmed by electrical stimulation set at 0.05 mA. The dura of the internal auditory canal is incised in a longitudinal fashion, along the posterior edge, away from the facial nerve. Under direct visualization, the dura is reflected. At this point the tumor and facial nerve should be visible. Cranial nerve VII is expected to be anterior or superior to the body of the tumor, and its location must be confirmed before tumor dissection. The superior vestibular nerve is then removed from its lateral attachment to the labyrinth and is retracted medially. Careful



FIG. 29. The legmen tympani has been removed, exposing the underlying attic containing the head of the malleus and body of the incus. These additional landmarks can be helpful when the arcuate eminence is not appreciated and the superior semicircular canal has not been located.



FIG. 30. Once the "blue line" of the superior semicircular canal has been identified, dissection proceeds over the meatal plane superior to the internal auditory canal. The internal auditory canal lies within a 60-degree angle from the blue-lined semicircular canal.



FIG. 31. The internal auditory canal is skeletonized around the superior 180 degrees of its circumference. In the lateral aspect of the internal auditory canal, "Bill's bar" separates the facial nerve anteriorly from the vestibular nerve posteriorly.

dissection then removes the vestibular nerve and tumor from the facial and cochlear nerves, in a lateral-to-medial direction.

Closure

After complete removal of the tumor, hemostasis is secured. Bone wax is used to fill exposed air cells. A piece of temporalis muscle is placed in the bony defect, and the pedicled temporalis fascia flap is reflected over the floor of" the middle cranial fossa. The temporal lobe is released, compressing the fascia over the bony defect. The extradural nature of the surgery together with the rccxpansion of the temporal lobe explain the relatively low incidence of postoperative CSF fistulas. The bone flap is secured to the edges of the craniotomy with silk sutures. The temporalis muscle is closed superiorly, leaving a gap inferiorly where the temporalis fascia is passing. The skin is closed in two layers. Fine nylon is recommended in the non-hair-be an ng skin of the preauricular area. A pressure dressing is applied and left in position for 48 hours.

SUMMARY

Tremendous progress has occurred in the diagnosis and management of vestibular schwannomas over ihe past century. The advent of the operating microscope, improved microsuTgical techniques, and the development of MRT has dramatically changed the focus of the management of these tumors. Focus has shifted from mortality to morbidity. Farly detection, facial nerve preservation, and hearing conservation are die main areas of advancement. Four surgical techniques—translabyrinthine, transotic, retrosigmoid, and middle fossa—have evolved in the treatment of vestibular schwannomas. The differential indications, complications, and advantages have been reviewed. All of these techniques play an important role in the overall management of CPA tumors.

REFERENCES

1. Gushing. H. *Tumors oi the nervux acusticus and the syndrome of the cerebellopontJle angle-* Philadelphia: WB Saunders. 1917.
2. House WF. Exposure of the internal auditory canal and its contents through the middle cranial fossa. *Laryngoscope* 1961:71:1363-1385.
3. House WF. Evolution of the trans temporal bone removal of acoustic tumors. *Archives ufQtohiryngology* 1964:80:731-742.
4. Brackmann DE. Bartels LJ. Rare tumors of the cerebellopontine angle. *Otoltu-yngol Haiti Neck Surg* I980;88:555-559
5. Pensak ML. Glasscock ME, Josey AF, Jackson CO, Gulya AJ. Sudden hearing loss and cerebclloponline angle tumors. *Laryngoscope* 1985:95:1 188-1193.
6. Berg MM. Cohen XL. Hammcrschlag PE, Waltzman SB. Acoustic neuroma presenting as sudden hearing loss with recovery. *Otolaryngol Head Net k Surg* !9S6;94:15-22.
7. Ogawa K, Kan/aki .1, Ogawa S, Tsuchihashi N, Inoue Y, Acoustic neuromas presenting as sudden hearing loss. *Acta Otolaryngol Suppt (Stockh)* 1991:487:138-143.
8. Berenhol/ LP. Eriksen C. Hirsh HA. Recovery from repeated sudden hearing loss with corticusteroid use in the presence of an acoustic neuroma. *Ann OtolRhinol faryngoi* 1992:101:827-831.
9. Selcsnick SH. Jackler RK. Pitts LW. The changing clinical presentation of acoustic tumors in the MR1 era. *Laryngoscope* 1993; 103:431^136.
10. Saunders ,IH. Luxford WM, Devgan KK. Fetterman BL. Sudden hearing loss in acoustic neuroma patients. *Otolaryngol Head Neck Surg* 1995;! 13:23-31.
11. Porlmann M, Dauman R. DuriezF, Portraann D. DhillonR. Modem diagnostic strategy for acoustic neuromas. *Arch Qtarhinolarvngol* 1989:246:286-291.
12. BeckHJ. Bcatty CW, Hamer SC, llstrup DM. Acoustic neuromas with normal pure tone hearing levels. *Otolaryngol Head Neck Surg* 1986:94:96-103.
13. Selesnick SH. Jacklcr RK. Atypical hearing loss in acoustic neuroma patients. *Laryngoscope* 1993:103:437^41.
14. Olsen A. Horrax G. The symptomatology of acoustic tumors with special reference to atypical features. *J Neurosurg* 1944; 1:371-378.
15. Edwards CH. Patterson JH. A review of the symptoms and signs ot acoustic neurofibromata. *Brain* 1951;74:144-190.
16. Erickson LS, Sorcnson GD, Mcgavran MH. A review of 140 acoustic ncurinomas (neurilemmoma). *Laryngoscope* 1965:75:601-627.
17. Selesnick SH. Jackler RK. Clinical manifestations and audiologic diagnosis of acoustic neuromas. *Qtvlarvngol C/in North Am* 1992;25: 521-551.
18. Thomsen J. Tos M. Acoustic neuroma: clinical aspects, audioveslibular assessment, diagnostic delay, and growth rale. *Am J Otol* 1990:1 1: 12-19.
19. Harrier SG. Laws ER. Diagnosis of acoustic neurinoma. *Neuroxurgen* 1981:9:373-379.
20. Hitselbergcr WE, House WF. Acoustic neuroma diagnosis: external auditory canal hypesthesia as an early sign. *Archives ofOtolarytigologv* 1966:83:218-221.
21. Hitselberger WE. External auditory canal hypesthesia. *Ann Surg* !966;32:741-743.
22. l.eonetti.IP. The diagnosis and management of acoustic neuromas: contemporary practice guidelines. *Compr Ther* 1995;21:68-73.
23. Johnson EW. Auditory test resulis in 500 cases of acoustic neuroma. *Archive* of Ofolaryngology* 1977;103:152-158.
24. Brunas RL. Yhkoski J, Morra B. Pure lone audiogram configurations in acoustic tumor patients. *Rev Larvngul Oro! Rhino! (Rord)* 1984;]05: 113-116-
25. Moffat DA. Hardy DC, Baguley DM. Strategy and benefits of acoustic neuroma searching. *J Laryngol Otol* 1989; 103:51—59.

26. Kanzaki J, Ogawa K, Ogawa S, Yamamoto M, Ikeda S, O-Uchi T. Audiological findings in acoustic neuroma. *Acta Otolarvngol Suppl (Stockh)* 1991 ;487: 125-1 32.
27. Thomsen J, Terkildsen K, Tos M. Acoustic neuromas: progression of hearing impairment and function of the eighth cranial nerve. *Am J Otol* 1983;5:20-33.
28. Clemis JD. Acoustic reflex testing in otoneurology. *Orolaryngol Head NeckSurg* 1984;92:141-144.
29. Odkvist LM. Otoneurological diagnostics in posterior fossa lesions. *Acta Otolaryngol Suppl (Srockh)* 1988:452:12-15.
30. Clemis JD, Me Gee T. Brain stem electric response audiometry in the differential diagnosis of acoustic tumors. *Laryngoscope* 1979;89:

Legatt AD, Pedley TA, Emerson RG, Stein BM, Abramson M. Normal
brain-stem auditory evoked potentials with abnormal latency-intensity
studies in patients with acoustic neuromas. *Arch Neural* 1988;45:
1326-1330.
Josey AF, Glasscock ME, Musiek FE. Con-elation of ABR and medical
imaging in patients with cerebellopontine angle tumors. *Am J Otol*
33. 1988;9LSuppl]: 12-16.
Kotlarz JP, Eby TL, Borton TE. Analysis of the efficiency of retrocochlear
34. screening. *Laryngoscope* 1992:102:1108-11 12.
Wilson DF, Hodgson RS, Gustafson MF. Hogue S, Mills L. The sensitivity
of auditory brainstem response testing in small acoustic neuromas.
35. *Laryngoscope* 1992;102:961-964.
Levine SC, Antonelli P.T, Le CT, Haines SJ. Relative value of diagnostic
36. tests for small acoustic neuromas. *Am J Otol* 1991; 12:341-346.
Swan IR. Diagnostic vetting of individuals with asymmetric sensorineural
37. hearing impairments. *J Laryngol Otol* 1989;103:823-826.
Harder H. Audiovestibular tests in the diagnosis of cerebellopontine angle
38. tumours. *Acta Otolaryngol Suppl (Stockh)* 1988:452:5-1 1.
Weiss MH, Kisiel DL, Bhatia P. Predictive value of brainstem evoked
40. response in the diagnosis of acoustic neuroma. *Otolaryngol Head Neck Surg* 1990;103:583-585.
4]. Gstoettner W, Neuwirth-Riedl K, Swoboda H, Mostbeck W, Burian M.
Specificity of auditory brainstem response audiometry criteria in acoustic
neuroma screening as a function of deviations of reference values in
42. patients with cochlear hearing loss. *Eur Arch Otorhinolaryngol*
1992:249:253-256.
Greenberger R, Khangure MS, Chakera TM. The morbidity of CT air
43. meatography: a follow-up of 84 patients. *Clin Radial* 1987:38:
535-536.
Smith IM, Tumbull LW, Sellar RJ, Murray JA. CT air meatography: review
44. of side effects in 60 patients. *J Laryngol Otol* 1989:103:173-174.
Saeed SR, Woolford TJ, Ramsden RT, Lye RH. Magnetic resonance
imaging: a cost-effective first line investigation in the detection of
45. vestibular schwannomas. *Br J Neurosurg* 1995:9:497-503.
Lalwani AK, Jackler RK. Preoperative differentiation between meningioma
of the cerebellopontine angle and acoustic neuroma using MR1.
46. *Otolaryngol Head Neck Surg* 1993:109:88-95.
Lunardi P, Mastronardi L, Nardacci B, Acqui M, Fortuna A. "Dural
47. tail" adjacent to acoustic neuroma on MRI: a case report. *Neuroradiology*
1993;35:270-271.
Kutcher TJ, Brown DC, Maurer PK, Ghaed VN. Dural tail adjacent to
48. acoustic neuroma: MR features. *J Comput Assist Tomogr* 1991;15:
669-670.
49. Phelps PD. Fast spin echo MRI in otology. *J Larvngol Otol*
1994;108:383-394.
50. Strasnick B, Glasscock ME, Haynes D, McMenomey SO, Minor LB.
The natural history of untreated acoustic neuromas. *Laryngoscope*
1994:104:1115-1119.
51. Noren G, Greitz D, Hirsch A, Lax I. Gamma knife surgery in acoustic
tumours. *Acta Neurochir Suppl (Wien)* 1 993;58: 104-107.
Lunsford LD, Kondziolka DS, Flickinger JC. Radiosurgery of tumors
of the cerebellopontine angle. *Clin Neurosurg* 1994 ;41: 168-1 84.
Pollock BE, Lunsford LD, Kondziolka D, et al. Outcome analysis of
acoustic neuroma management: a comparison of microsurgery and
stereotactic radiosurgery. *Neurosurgery* 1995;36:215-224.
Hirato M, Inoue H, Nakamura M, et al. Gamma knife radiosurgery for
acoustic schwannoma: early effects and preservation of hearing. *Neurol
Med Chir (Tokyo)* 1995;35:737-741.
Foote RL, Coffey RJ, Swanson JW, et al. Stereotactic radiosurgery using
the gamma knife for acoustic neuromas. *Jnt J Radial Oncol Biot Phvs* 1995:32:1153-1160.

53. Flickinger JC, Lunsford LD, Linskey ME, Duma CM, Kondziolka D. Gamma knife radiosurgery for acoustic tumors: multivariate analysis of four year results. *Radiother Oncol* 1993:27:91-98.
54. Slattery WH, Brackmann DE. Results of surgery following stereotactic irradiation for acoustic neuromas. *Am J Otol* 1995:16:315-319.
55. Blevins NH, Jackler RK. Exposure of the lateral extremity of the internal auditory canal through the retrosigmoid approach: a radioanatomic study. *Otolaryngol Head Neck Surg* 1994;lll:81-9().
56. Wigand ME, Haid T, Berg M. The enlarged middle cranial fossa approach for surgery of the temporal bone and of the cerebellopontine angle. *Arch Otorhinolaryngol* 1989:246:299-302.
57. Rosomoff HL. The subtemporal transtentorial approach to the cerebellopontine angle. *Laryngoscope* 1971:81:1448-1454.
58. Kanzaki J, Kawase T, Sano K, Shiobara R, Toya S. A modified extended middle cranial fossa approach for acoustic tumors. *Arch Otorhinolaryngol ^11 ;2\1:\* 19-121.
59. Jackler RK, Pitts LH. Selection of surgical approach to acoustic neuroma. *Otolaryngol Clin North Am* 1992;25:361-387.
60. Harner SO, Daube JR. Ebersold MJ, Beatty CW. Improved preservation of facial nerve function with use of electrical monitoring during removal of acoustic neuromas. *Mayo Clin Proc* 1987;62:92-102.
61. Harner SG, Daube JR, Beatty CW. Ebersold MJ. Intraoperative monitoring of the facial nerve. *Laryngoscope* 1988:98:209-212.
62. Jellinek DA, Tan LC, Symon L. The impact of continuous electrophysiological monitoring on preservation of the facial nerve during acoustic tumour surgery. *Br J Neurosurg* 1991;5:19-24.
63. Lalwani AK, Butt FY, Jackler RK, Pitts LH, Yingling CD. Facial nerve outcome after acoustic neuroma surgery: a study from the era of cranial nerve monitoring. *Otolaryngol Head Neck Surg* 1994;! 11:561-570.
64. House JW, Brackmann DE. Facial nerve grading system. *Otolaryngol Head Neck Surg* 1985;93:146-147.
65. Uziel A, Benezech J, Frerebeau P. Intraoperative facial nerve monitoring in posterior fossa acoustic neuroma surgery. *Otolaryngol Head NeckSurg* 1993:108:126-134.
66. Harner SG, Ebersold MJ. Management of acoustic neuromas, 1978-1983. *J Neurosurg* 1985:63:175-179.
67. Robson AK, Clarke PM, Dilkes M, Maw AR. Transmastoid extracranial repair of CSF leaks following acoustic neuroma resection. *J LaryngolOtol* 1989;103:842-844.
68. Hardy DC, Macfarlane R, Baguley D, Moffat DA. Surgery for acoustic neurinoma. An analysis of 100 translabyrinthine operations. *J Neurosurg* 1989:71:799-804.
69. Bryce GE, Ned/.elski JM, Rowed DW. Rappaport JM. Cerebrospinal fluid leaks and meningitis in acoustic neuroma surgery. *Ololaryngol Head Neck Surg* 1991:104:81-87.
70. Cohen NL. Retrosigmoid approach for acoustic tumor removal. *Otolan'ttgol Clin North Am* 1992:25:295-310.
71. Rodgers GK, Luxford WM. Factors affecting the development of cerebrospinal fluid leak and meningitis after translabyrinthine acoustic tumor surgery. *Laryngoscope* !993;103:959-962.
72. Hoffman RA. Cerebrospinal fluid leak following acoustic neuroma removal. *Laryngoscope* 1994; 104:40-58.
73. Gantz BJ, Parnes LS, Marker LA, McCabe BF. Middle cranial fossa acoustic neuroma excision: results and complications. *Ann Otol Rhinol Laryngol* 1986:95:454^159.
74. Shelton C, Brackmann DE, House WF, Hitselberger WE. Middle fossa acoustic tumor surgery: results in 106 cases. *Laryngoscope* 1989:99:405^108.
75. Tos M, Thomsen J. Cerebrospinal fluid leak after translabyrinthine surgery for acoustic neuroma. *Laryngoscope* 1985;95:351-354.
76. Cohen NL. Retrosigmoid approach for acoustic tumor removal. *Otolaryngol Clin North Am* 1992;25:295-310.
77. Hoffman RA. Cerebrospinal fluid leak following acoustic neuroma removal. *Laryngoscope* 1994;104:40-58.
78. Chen JM, Fisch U. The transotic approach in acoustic neuroma surgery. *J Otolaryngol* 1993:22:331-336.
79. Symon L, Pell MF. Cerebrospinal fluid rhinorrhea following acoustic neurinoma surgery: technical note. *J Neurosurg* 1991;74:152-153.
80. Ramsden RT, Herdman RC, Lye RH. lonomeric bone cement in neurootological surgery. *J Laryngol Otol* 1992:106:949-953.
81. Harner SG, Beatty CW, Ebersold MJ. Headache after acoustic neuroma excision. *Am J Otol* 1993;14:552-555.
82. Schessel DA, Rowed DW, Nedzelski JM, Feghali JG. Postoperative pain following excision of acoustic neuroma by the suboccipital ap-

proach: observations on possible cause and potential amelioration. *Am] Owl* 1993; 14:491-494.
83. Kamerer DB, Hirsch BE, Snyderman CH, Costantino P, Friedman CD. Hydroxyapatite cement: a new method for achieving watertight closure in transtemporal surgery. *Am J Otol* 1994:15:47—49.
84. Harner SG, Beatty CW, Ebersold MJ. Impact of cranioplasty on headache after acoustic neuroma removal. *Neurosurgery* 1995:36: 1097-1099.
85. Dandy WE. Results of removal of acoustic tumors by the unilateral approach. *Arch Siirg* 1941;42:1026.
86. Parry RH. A case of tinnitus and vertigo treated by division of the auditory nerve. *J Laiyngol Owl* 1904:19:402.

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 24

Approaches to Jugulotympanic Paragangliomas

Rick A. Friedman and Derald E. Brackmann

BACKGROUND

The first descriptions of "swellings" or "ganglions" associated with the tympanic nerve appeared in the middle and late 1800s (1,2). It was not until 1941 that, in his address to the American Association of Anatomists, Guild described the "presence of a previously unrecognized structure" that he called the "glomus jugularis" or jugular body (3). In his first report, he described glomus formations along the course of lacobson's nerve from its beginning near the adventitia of the jugular bulb, to the cochlear promontory. Soon thereafter, he noted these formations along the course of Arnold's nerve from the skull base into the mastoid canaliculus and fallopian canal.

In Guild's report of 1953, he made several more observations about the glomus bodies of the temporal bone. He found the average number of glomus formations, which measured approximately 0.5 X 0.25 mm in size, was 2.82 per ear, with the largest number appearing in midlife and a marked decrease in number after the age of 60 years. He found no racial or gender differences in the number or size of glomus formations. Although he found these glomus formations along the entire course of both Jacobson's and Arnold's nerves, he found that most were within the adventitia of the jugular bulb in the jugular fossa.

The first clinical description of a "carotid body tumor of the middle ear and mastoid" came in 1945 (4). Rosenwasser described a 36-year-old man with a "growth" in the external canal of the left ear and deafness. The tumor had eroded a significant amount of the mastoid bone and had exposed the facial nerve. The tumor bled significantly when manipulated. After pathologic review, Rosenwasser proposed that this tumor may have arisen from the glomus jugularis described by Guild 4 years earlier.

A variety of terms have been used to describe glomus formations and their tumorous counterparts. Lattes and Waltner, in 1949, attempted to clarify the nomenclature and wrote of Guild's "glomus jugularis": "The correct Latin diction should be glomus jugulare, and not glomus jugularis, because the Latin noun glomus is neuter (5)." He proposed the term "nonchromaffin paraganglioma," indicating that these structures and their tumors arise from paraganglionic tissue. Unlike the chromaffin paraganglia associated with the adrenal medulla, these nonchromaffin paraganglia had no affinity for dichromate stains. Despite these debates, several reports of "glomus jugularis" tumors appeared in the literature over the next few decades (6,7). By 1965, approximately 200 cases had been described (7).

BIOLOGY

The chief cells, the principal cells of paraganglionic tissue, are derived from the neural crest and migrate in close association with the ganglia of the sympathetic nervous system (8). The term "glomus" was applied because of an original belief that the chief cell was derived from specialized pericytes, as seen in true arteriovenous (glomus) complexes (8). This theory is no longer thought to be true, and hence the correct term is "paraganglia." Tumors of the paraganglia, paragangliomas, can be divided into two main groups, adrenal and extraadrenal (9) (Table 1). Adrenal paragangliomas are also known as pheochromocytomas. Extraadrenal paragangliomas are associated with sympathetic ganglia in the abdomen, chest, retroperitoneum, and mediastinum. Classification of paragangliomas of the head and neck (branchiomeric) is based on their anatomic location and includes carotid body, Jugulotympanic, vagal, laryngeal, nasal, and orbital paragangliomas. The most common location in

R. A. Friedman: House Ear Clinic, Inc., Los Angeles, California 90057.

D. E. Brackmann: Department of Otolaryngology, Head and Neck Surgery, University of Southern California, Eos Angeles, and House Ear Clinic, Inc., Los Angeles, California 90057.

the head and neck is the carotid body, followed by those of the jugulotympanic region (10).

Le Compte. in 1949, was one of the first to suggest catecholamine secretion by paraganglion cells (1 I). Initially, jugulotympanic paragangliomas, as well as the other branchiomcric paragangliomas, were thought not to be producers of catecholamines based on their failure to react with dichro-mate salts. Although once thought to indicate the presence of catecholamines in a tissue, this reaction has proven to be an insensitive measure of catecholamine presence and has been replaced by form aldehyde-induced fluorescence microscopy (12). Electron microscopic data have clearly demonstrated dense secretory granules known to contain catecholamines in the cytoplasm of chief cells. Chief cells have since been classified as members of the diffuse neuroendocrine system, a system of neuropeptide- and catecholamine-secretlng cells (8). Immunohistochemical studies corroborate this by demonstrating chief cell staining forchromogranin, synaptophysin, neuron-specific enolase, ncurofilaments. and a variety of neuropeptides (10).

Paragangliomas display a characteristic histologic pattern (Fig. 1). Light microscopy demonstrates clusters of chief cells *(Zellballen)* and suslentacular cells, with abundant .small blood vessels and unmyelinated nerve fibers presumably derived from the glossopharyngeal nerve (10.13).

Tbe main focus of this chapter is the management of paragangliomas arising in the temporal bone, the so-called jugulotympanic paragangliomas. This group of paragangliomas includes those of the jugular bulb region (jugulare) and the tympanic cavity (tympanicum). These tumors are considered the most common tumors of the middle ear and the second most common tumors of the temporal bone, after acoustic neuromas. Most of these tumors arise in the jugular bulb (10).

TABLE 1. *Paraganglioma classification scheme*

Adrenal
- Pheochromocytoma

Extraadrenal
- Branchiomeric
  - Aorticopulmonary
  - Coronary
  - Intercarotid
  - Jugulotympanic
  - Laryngeal
  - Orbital
  - Pulmonary
  - Subclavian Intravagal
- Aorticosympathetic
- Visceroautonomic



FIG. 1. Histologic slide demonstrating clusters of cells *(Zellballen)* separated by a fibrovascular stroma.

CLINICAL CHARACTERISTICS

Paragangliomas appear to be most common in whites, although there is no clear-cut racial predilection (13). These tumors occur more commonly in women and. although they have been described in patients as young as 6 months and a> old as 88 years, they are typically identified in the fourth or fifth decades of life (8.13,14).

Multiple or synchronous tumors occur in 3% to 10% of patients (13,15.16). The most common combination noted in one series included a tympanicum tumor associated with an ipsilateral carotid body tumor (15). A hereditary component to some tumors has been described with an autosomal dominant mode of transmission (17). These patients display a much higher incidence of synchronous paragangliomas (25-35%). Furthermore, they are frequently associated with other lumors, both benign and malignant, most notably, pheocbromocytomas (17).

Paragangliomas demonstrate a slow and insidious pattern of growth (13.14,18). The time to onset of symptoms depends on the site of origin of the tumor. However, there are typically few symptoms until the lesion is far advanced (18). The signs and symptoms have been placed into three groups based on the tumor characteristics and location (14):

1. Those due to the presence of tumor in the middle ear—conductive hearing loss, **aural polyp,** and aural di^-charge.
2. Those due to the vascularity of the tumor—pulsatile tinnitus, aural bleeding, and a positive Brown's or Aquino's sign (18,19) (the former consists of cessation of tumor pulsation and tumor blanching with positive pressure on pneumotoscopy, and the latter consists of cessation of tumor pulsation with ipsilateral carotid artery compression).

TABLE 2. *Presenting symptoms in 73 patients with tympanicum tumors studied at the House Ear Clinic, Inc.*



Symptom	Percentage
Pulsatile tinnitus	50
Hearing loss	30
Otalgia	7
Aural fullness	4
Otorrhea	3
Other	3
Asymptomatic	3

From ret. 20, with permission.

3. Those that suggest tumor extension to vital structures—sensorineural hearing loss, vertigo, aural pain, and cranial neuropathy.

Otologic symptoms are by far the most common presenting complaints and consist of pulsatile tinnitus and conductive hearing loss (13,16,18,20,21) (Tables 2. 3). Tympanicum tumors present earlier than those of the jugular bulb region because of earlier involvement of the umbo with resultant transmission of pulsations and subsequent conductive hearing loss (21).

Paragangliomas rarely metastasize *(3-4%)* and most often spread along paths of least resistance (13,22,23). They tend to migrate through the temporal bone by vascular channels, naturally occurring fissures, foramina, and, most important, along air cell tracts (14,24). Spector et al. have described two "dangerous triangles" that may allow tumors access to the intracranial cavity (14).

The first triangle is located in the protympanum and is bounded by the eustachian tube and tensor tympani muscle above, the great vessels below, and the cochlea behind. Tumors in this area can follow the peritubal air cells that lead directly to the petrous apex, they can grow into the nasopharynx through the eustachian tube, or they can follow the petrous carotid artery into the middle cranial fossa and cavernous sinus.

The second triangle, the hypotympanic, is in the area of the great venous sinuses and includes the jugular bulb, die inferior petrosal sinus, the sigmoid sinus, and the jugular vein. This pathway provides access lo the skull base and its foramina, the carotid artery, and the various venous channels.

Paragangliomas can also invade the mesotympanum extensively, enveloping, but rarely destroying the ossicular chain, and, as stated previously, erode through the tympanic membrane and into the external auditory canal (18,21,24) (Fig. 2). Rarely, a tumor in the middle ear invades die otic capsule through the round window, leading to sensorineural hearing loss.

Neurologic deficits are the second major group of symptoms and signs, often appearing after considerable tumor growth. The incidence of cranial nerve involvement by tumor is approximately 37%, and that of intracranial extension is 15% (25). Medial and posterior extension of the tumor into the mastoid through the facial recess and retrofacial air cell tract may result in envelopment of the facial nerve in its horizontal and vertical segments (25). Facial paralysis has been noted in 21% to 66% of patients, usually several years after initial symptom onset (18,25).

Tumors originating in the jugular bulb, or those from the middle ear that extend inferiorly to involve this region, make

TABLE 3. *Presenting symptoms and signs in 52 patients with jugulare tumors studied at the House Ear Clinic, Inc.*



Symptoms and signs	Percentage
Pulsatile tinnitus	98
Hearing loss	63
Otalgia	12
Hoarseness	28
Dysphagia	17
Dizziness	21
Middle ear mass	94
External auditory canal mass	6
Neck mass	4
Facial hypesthesia	14
Decreased gag reflex	23
Vocal cord paresis	34
Trapezius/sternocleidomastoid muscle weakness	18
Tongue deviation	20

From ref. 16, with permission.



FIG. 2. Tympanicum tumor protruding through an intact tympanic membrane.

themselves apparent by their compression of cranial nerves IX, X, XI, and XII, either at the jugular foramen and hypoglossal canals (Vernet's and Collet-Sicard syndromes), or in the carotid sheath after extension into the parapharyngeal space. Involvement of the internal carotid artery either in the neck or in the petrous portion of the temporal bone can lead to Horner's syndrome by involvement of the sympathetic plexus (25). Spector et al. found posterior fossa extension in 50% of patients with jugular foramen syndrome and in 75% of patients with hypoglossal nerve involvement (25). Horner's syndrome was associated with a 50% incidence of middle cranial fossa invasion.

RADIOLOGIC DIAGNOSIS

Radiologic evaluation is essential for the proper diagnosis and management of jugulotympanic paragangliomas. Techniques such as plain films of the mastoid and polytomography have been supplanted by high-resolution computed tomography (HRCT) and magnetic resonance imaging (MRI). Furthermore, unless the tumor is embolized or envelopes much of the internal carotid artery, HRCT and MRI obviate the need for angiography.

The CT appearance of paragangliomas is highly variable. HRCT scans in the axial and coronal planes, including soft tissue and bone algorithms, provide information critical to the differential diagnosis and approach to management of these tumors (26-28). HRCT supplements clinical otoscopy in defining the extent of tumor beyond the microscopically visible limits of the tympanic annulus, and it aids in the differentiation of tumors from vascular anomalies. Furthermore, HRCT helps to define the extent of involvement of the temporal bone by the tumor and can assist in identifying intracranial extension. Last, HRCT with contrast helps to differentiate paragangliomas from other benign and malignant tumors of the skull base, and identifies synchronous tumors of the skull base and neck.

Because tympanicum tumors typically present early, they often appear as well circumscribed, soft tissue masses in the middle ear without bony erosion (29) (Figs. 3, 4). Jugulotympanic paragangliomas often display involvement of the hypotympanum and erosion of the jugular plate and carotid spine (24).

More extensive bone destruction is associated with tumors of the jugular bulb, which demonstrate an irregular or "moth-eaten" pattern of erosion of the jugulocarotid spine, the jugular foramen, or the hypoglossal canal (Fig. 5). HRCT demonstrates destruction of the pars nervosa medially and involvement of the inferior petrosal sinus along the petrooc-cipital suture (see Fig. 5). Although tumor may involve the hypotympanic air cells extensively, the hard bone of the otic capsule is often spared.

Magnetic resonance imaging is superior to HRCT in its ability to characterize the vascular nature of tumors involving the jugular bulb and skull base without the use of contrast and without the artifact from the petrous bone typically seen on CT (30). MRI displays the important relations of the tumor to the surrounding great vessels, including venous invasion (Fig. 6). Tl-weighted images, with and without contrast, display the highly vascular nature of the tumor matrix, and T2-weighted images provide excellent soft tissue contrast (Fig. 7). For lesions larger than 2 cm, T2-weighted images often display the "salt-and-pepper" appearance characteristic of paragangliomas (30).

Stagnant blood in the jugular foramen can be mistaken for tumor, as can postenhancement images (30). Differentiation of these two entities can often be facilitated by magnetic resonance venography and HRCT (31). Magnetic resonance angiography, although helpful in the differential diagnosis of pulsatile tinnitus, does not reliably demonstrate the tumor vascularity seen on conventional angiography (32).

Detection of multicentric or metastatic lesions has been facilitated by radionuclide scintigraphy with indium-111-



FIG. 3. Noncontrast coronal high-resolution computed tomography scan demonstrating a paraganglioma limited to the promontory.



FIG. 4. Axial high-resolution computed tomography scan of the tumor shown in Fig. 3. Note the intact jugular plate in the hypotympanum.



FIG. 5. Noncontrast axial high-resolution computed tomography scan displaying a "moth-eaten" pattern of destruction of the jugular foramen and extension of the tumor along the petrooccipital suture within the inferior petrosal sinus.

octreotide (33). Although it is useful in cases with high risk of multicentricity, such as hereditary tumors, the authors do not routinely screen patients before surgery.

PERIOPERATIVE MANAGEMENT

Secretion

Although all glomus tumors have the potential for catecholamine secretion, clinically significant secretion is identified in only 1% to 3% (34,35). Norepinephrine is the most commonly secreted substance, although dopamine secretion has been reported (34). Glomus tumors lack the ability to convert norepinephrine to epinephrine. Thus, if high levels of the latter are detected in the patient's serum, a search should be made for a concomitant pheochromocytoma (34).

The evaluation of a patient with a paraganglioma should include detecting the symptoms and signs of catecholamine secretion, which include the following: headaches, pallor, excessive perspiration, palpitations, hypertension, nausea, and orthostatic changes in blood pressure. Clinical suspicion of catecholamine secretion can be verified by measuring serum catecholamine levels and 24-hour urinary metanephrines (normetanephrine and metanephrine) and vanillylmandelic acid (34). Preoperative screening is essential in tumors originating from the jugular bulb. There is little evidence for secretion of catecholamines by tympanicum tumors, and routine screening for these tumors is unnecessary (20).

Management of patients with secreting tumors includes perioperative blood pressure management with a-blocking agents, including phentolamine and phenoxybenzamine, and intraoperative invasive hemodynamic monitoring (34).

Embolization and Assessment of Collateral Circulation

Although preoperative arteriography has largely been supplanted by noninvasive imaging, it continues to play a role in the embolization of large tumors involving the jugular foramen and skull base. The authors have found preoperative embolization of selected tumors significantly reduces operating time and intraoperative blood loss (36). The embolization is typically performed 24 to 48 hours before surgery.

For tumors abutting the internal carotid artery, it is often necessary to assess the cross-perfusion from the contralateral vessels when the potential for carotid sacrifice exists. Cross-compression angiography, measurement of stump pressures, oculoplethysmography, and balloon occlusion testing are all



FIG. 6. Gadolinium-enhanced, T1-weighted axial magnetic resonance image demonstrating tumor involvement of the right inferior petrosal sinus up to the petroclival junction.



FIG. 7. Gadolinium-enhanced axial T1-weighted magnetic resonance image revealing several flow voids in this vascular tumor in the right jugular foramen.

methods of assessing the risk of cerebrovascular accident after carotid occlusion. Many of these studies have proven to be unreliable predictors of postoperative morbidity (37). ^{99m}Tc-hexamethylpropyleneamine oxime (HMPAO) cerebral perfusion single-photon emission CT imaging or xenon CT studies offer a more precise assessment of collateral blood flow and the risk of subsequent cerebrovascular accident (38-40). Patients requiring sacrifice of an extensively involved internal carotid artery and who perform well on these studies can be managed by preoperative permanent balloon occlusion (41). Those patients who fail the preoperative perfusion studies may require revascularization at the time of resection.

DIFFERENTIAL DIAGNOSIS

When considering the differential diagnosis of paragangliomas, two different presentations must be considered: (a) intratympanic vascular masses, and (b) lesions of the skull base causing caudal cranial nerve deficits. Radiographic imaging is an essential aid to the differential diagnosis, with HRCT the preferred modality for the former and MRI for the latter.

Vascular anomalies of the middle ear may present in a fashion identical to that of an intratympanic paraganglioma. The principal anomalies include the aberrant or laterally displaced internal carotid artery, the dehiscent or high-riding jugular bulb, and the congenital or acquired intratympanic carotid artery aneurysm (42-47).

The aberrant internal carotid artery can be distinguished by HRCT (48). HRCT displays the four features that establish the diagnosis: (a) enlargement of the inferior tympanic canaliculus by the aberrant vessel at its entry into the middle ear, (b) an enhancing mass in the hypotympanum, (c) absence of the vertical segment of the internal carotid canal, and (d) absence of the bony covering of the internal carotid artery (44). Aberrant internal carotid arteries are most frequently identified in women (90%) and in right ears (75%) (43,44).

The high-riding jugular bulb is the most common vascular anomaly of the middle ear and is readily recognized on HRCT (43). It is defined as a jugular bulb extending above the inferior tympanic annulus and is present in approximately 6% of patients.

Intratympanic carotid aneurysms are rare. They are thought to arise from congenital arterial anomalies, although posttraumatic and postinfectious aneurysms have been described (45-47).

These anomalies can often be differentiated from tumors by a careful microscopic examination. However, radiographic imaging is essential to their delineation. Ill-advised biopsy procedures performed on aberrant vessels have resulted in massive hemorrhage and hemiplegia (44,45).

The differential diagnosis of jugular foramen masses includes a variety of benign and malignant neoplasms and is beyond the scope of this chapter. In brief, schwannomas of cranial nerves IX, X, XI, and XII, and meningiomas can all present with caudal cranial nerve deficits. A variety of primary and metastatic lesions of the skull base can also lead to caudal cranial nerve deficits. Here, too, radiography is essential to the differential diagnosis.



TABLE 4. *Classification scheme devised by Antonio De la Cruz, MD*

Anatomic classification	Surgical approach
Tympanic	Transcanal
Tympanomastoid	Mastoid–extended facial recess
Jugular bulb	Mastoid–neck (possible limited facial nerve rerouting)
Carotid artery	Infratemporal fossa
Transdural	Infratemporal fossa/intracranial

TUMOR CLASSIFICATION AND SELECTION OF SURGICAL APPROACH

Numerous classification schemes have been devised for the clinical characterization of paragangliomas. These schemes are largely based on anatomic location and tumor extent. The classification described by Antonio De la Cruz has been extremely useful in the treatment planning of these tumors. In this classification scheme, tumors are described by their anatomic extent, and each group of tumors has a corresponding operative approach (Table 4).

Tympanic tumors are those arising in the middle ear and confined entirely to the mesotympanum. The complete extent of the tumor is visible through the tympanic membrane; hence, tumor excision can be performed through a transcanal approach. In contrast, a *tympanomastoid* tumor arises from the middle ear but has extended into the posterior tympanum or the hypotympanum beyond the visible confines of the tympanic annulus. Radiographically, these tumors do not involve the jugular bulb, and they can be excised through a mastoid-extended facial recess approach.

Jugular bulb tumors are confined to this region and may extend to the middle ear and mastoid. They do not involve the carotid artery or the intracranial compartment. These tumors are excised through the mastoid-neck approach. Large tumors may require limited rerouting of the facial nerve to the second genu, as described in the section on Surgical Approaches. *Carotid artery* and *transdural* tumors are far more extensive and require an infratemporal fossa approach and excision of the intracranial component.

SURGICAL APPROACHES

Transcanal Approach

The transcanal approach is used for intratympanic paragangliomas limited to the mesotympanum (21). Although the entire extent of the tumor is visible microscopically, HRCT scan is a useful adjunct for distinguishing the other vascular lesions of the middle ear described previously.

The tympanomeatal flap is incised with the inferior incision extending farther anterior than usual to allow exposure of the hypotympanum (Fig. 8). The tumor is identified on the promontory. The inferior tympanic branch of the ascending pharyngeal artery is often seen supplying the tumor. This vessel may be controlled with bipolar cautery or occlusion with a small piece of oxidized cellulose placed into the inferior tympanic canaliculus. Unipolar cautery should not be used on the cochlear promontory because this may result in sensorineural hearing loss.

The tumor can now be removed with a cupped forceps, and further bleeding, usually from small caroticotympanic arteriolar branches, can be controlled with Gelfoam. The tympanomeatal flap is replaced and the ear is lightly packed with Gelfoam or ointment. These patients are often ready for discharge a few hours after surgery. Accurate preoperative assessment of tumor extent is critical to the successful removal through the transcanal approach.

Mastoid-Extended Facial Recess Approach

The mastoid-extended facial recess approach is used for tympanomastoid tumors (21) (Fig. 9). Preoperative HRCT is essential to the surgical planning with this approach (20). Patient preparation and draping are identical to that for a routine tympanoplasty with mastoidectomy. A wide postauricular shave is performed, and an incision is made approximately 1 cm posterior to the postauricular crease. After complete mastoidectomy, the facial recess is opened in the usual fashion, using the chorda tympani, the facial nerve, and the fossa incudis as landmarks. The extended facial recess is performed by severing the chorda tympani nerve and following the tympanic annulus into the hypotympanum. This approach allows complete exposure of the middle ear and hypotympanum from a posterior direction without the need for a tympanomeatal flap. After identification of the tumor, bipolar cautery is used to shrink the tumor and control the feeding vessels. The tumor is removed with cupped forceps. Tumor involving the incus and stapes can be stripped free with the forceps. After complete tumor removal, any further bleeding can be controlled with Surgicel or Gelfoam.

Tumor extension into the retrofacial air cell tracts can be managed by direct exposure in the mastoid. Using a cutting bur, the air cells inferior to the posterior semicircular canal, medial to the facial nerve, and superior to the jugular bulb can be removed. A thin layer of bone surrounding the facial nerve should remain for support. Tumor in this area can then be removed using a mastoid curette.

Extensive tumor involvement in the middle ear may necessitate removal of the malleus, incus, or tympanic membrane. In these circumstances, a tympanoplasty and ossicular reconstruction can be performed in the same sitting. At the conclusion of the procedure, a mastoid dressing is applied, and the patient can be discharged on the first postoperative morning.



FIG. 8. Transcanal exposure of a tympanicum tumor limited to the promontory.



FIG. 9. Extended facial recess exposure of a tympanicum tumor that has extendea into the hypotympanum. The retrofacial air cells have been removed to expose tumor medial to the facial nerve.

Mastoid-Neck Approach

The mastoid-neck approach is used for small jugulare tumors that do not involve the carotid artery or the posterior cranial fossa (49). Intraoperative electromyographic cranial nerve monitoring is an essential adjunct to this approach. Continuous intraoperative facial nerve monitoring is routinely used. Additional monitoring of cranial nerves IX, X, and XI by electrodes in the lateral pharyngeal wall, the vocalis muscle, and the trapezius muscle, respectively, can be used to assist in nerve preservation. This approach begins in the same fashion as the mastoid-extended facial recess approach (see Fig. 9).

The periosteum of the digastric is exposed posteriorly toward the occiput and anteriorly toward the stylomastoid foramen. Skeletonization of the digastric muscle facilitates amputation of the mastoid tip. The postauricular incision is carried down into the neck in a favorable neck crease, allowing exposure of the sternocleidomastoid muscle (SCM) and, ultimately, the great vessels and the lower cranial nerves. The SCM is dissected free of the mastoid tip by grasping the tip lateral to the digastric muscle with a Kocher clamp, rotating the tip posteriorly, and sharply dissecting the SCM attachments off the mastoid periosteum with a curved Mayo scissors. The posterior belly of the digastric is dissected free and reflected anteriorly to allow exposure of the great vessels and the lower cranial nerves. The internal jugular vein is isolated and ligated with multiple 2-0 silk sutures. The vein is then freed from inferior to superior over the transverse process of the first cervical vertebra and under the spinal accessory nerve into the jugular foramen. Blunt and sharp dissection in this area allows preservation of cranial nerves IX, X, and XI when they are not infiltrated by tumor. Exposure of the sigmoid sinus and jugular bulb is completed using diamond burs, with care taken to preserve bone over the proximal sigmoid sinus to facilitate extraluminal packing. Although limited tumors do not involve the medial wall of the jugular bulb, these tumors arise from the adven-titia and require resection of the lateral bulb in continuitv with the tumor. Before opening the sigmoid sinus, it is packed extraluminally under the bone preserved proximally. The sinus is opened just distal to the packing. Despite the extraluminal packing proximally and the ligation of the jugular vein in the neck, brisk bleeding from the inferior petrosal sinus and the condylar vein often ensues. Oxidized cellulose is gently but firmly packed into the jugular bulb in an effort to occlude the inferior petrosal sinus and the condylar vein while avoiding compression and subsequent injury to the lower cranial nerves on the medial aspect of the jugular foramen. Overly vigorous packing of the inferior petrosal sinus can lead to damage to the glossopharyngeal nerve in the pars nervosa, leading to potential postoperative aspiration.

The tumor is now ready for complete removal. Bipolar cautery is useful for hemostasis and shrinkage of the tumor. After tumor removal, residual bleeding can be controlled with oxidized cellulose packing. If tumor extirpation required removal of the tympanic membrane or ossicles, these can be repaired as described previously (Fig. 10).

After surgery, these patients are managed in an intensive care setting for 24 hours to allow early identification of lower cranial neuropathy or postoperative hemorrhage. The patients are often ready for discharge on the third or fourth postoperative day.

Preoperative radiographic assessment is essential for this approach. The mastoid-neck approach is too limited for the removal of tumors involving the petrous carotid artery.

Mastoid-Neck Approach with Limited Facial Nerve Rerouting

For slightly larger tumors of the jugular bulb not involving the carotid artery or posterior cranial fossa, limited rerouting of the facial nerve to the second genu can facilitate removal with no added morbidity (49,50). After decompression of the vertical segment of the facial nerve, the eggshell of bone remaining is removed. The facial nerve is dissected free of its fibrous attachments within the canal from the second genu to the level of stylomastoid foramen. The periosteum at the foramen is preserved such that after mobilization of the posterior belly of the digastric, the muscle and the soft tissue surrounding the stylomastoid foramen are reflected anteriorly as a whole, preserving the blood supply in this region. A suture placed through the periosteum allows anterior displacement of the nerve without tension (Fig. 11). This modification allows complete removal of the air cells in the retrofacial area inferior to the posterior semicircular canal.

Infratemporal Fossa Approach

The development of the infratemporal fossa approach to large skull base tumors has contributed greatly to their safe surgical removal (51). Removal of the external auditory canal and rerouting of the facial nerve allows complete exposure of tumors involving the internal carotid artery. There are eight distinct steps in the infratemporal fossa exposure: (a) patient preparation, (b) management of the ear canal and tympanic ring, (c) mastoidectomy, (d) initial preparation of the jugular vein and neck exposure, (e) transposition of the facial nerve, (f) completion of the neck exposure and identification of the lower cranial nerves and skull base carotid artery, (g) tumor removal and intracranial extension, and (h) wound closure (49). Continuous facial nerve monitoring and electromyographic monitoring of the lower cranial nerves are used as previously described.


Facial nerve in fallopian canal
Digastric muscle and parotid gland retracted

FIG. 10. Completed mastoid-neck approach demonstrating resected jugular bulb.



FIG. 11. Mastoid-neck approach with limited rerouting of the facial nerve for larger tumors of the jugular bulb.

A wide shave is performed in the preoperative waiting area. The area is prepared and draped such that wide exposure of the postauricular area and complete ipsilateral neck is facilitated. A large, postauricular C-shaped incision is made that is extended into the neck within a neck crease two fingerbreadths below the angle of the mandible. The ear is dissected forward and the ear canal is transected just medial to the bony-cartilaginous junction. The cartilage around the meatus is removed to facilitate eversion of a cuff of ear canal skin. The everted skin is closed with several interrupted 4-0 nylon sutures (Fig. 12). An anteriorly based mastoid periosteal flap is elevated and transposed anteriorly medial to the ear canal, providing another layer of closure (Fig. 13). After this soft tissue work, a mastoidectomy with an extended facial recess is performed to allow separation of the incudostapedial joint. The posterior external auditory canal with its overlying skin can now be safely removed using a rongeur and large cutting bur. The remaining skin, the tympanic membrane, and the malleus and incus are removed. The facial nerve can now be skeletonized from the geniculate ganglion to the stylomastoid foramen, leaving a thin eggshell covering. Caution must be exercised in the region of the oval window to avoid stapedial injury and subsequent sensorineural hearing loss. Using a combination of cutting and diamond burs, the bone of the tympanic ring is removed superiorly, anteriorly, posteriorly, and inferiorly. The facial nerve must be kept in view to avoid injury to its anterior surface. Complete bone removal in this way allows identification of the jugular bulb, the petrous carotid artery, and the temporomandibular joint (Fig. 14).

The postauricular incision can now be carried into the neck as described, allowing exposure of the SCM. The mastoid tip is removed as illustrated previously, and the internal jugular vein, internal and external carotid arteries, and cranial nerves IX, X, XI, and XII are identified and preserved. Ligatures are placed around the internal carotid artery and the jugular bulb for identification and vascular control. The posterior belly of the digastric is dissected free from the digastric groove.

The next step involves transposition of the entire facial nerve to the geniculate ganglion using a modification of the approach originally described by Fisch (50,51). The facial nerve is not dissected out to the pes anserinus as previously described; rather, the tail of the parotid is separated from its fibrous attachments to the SCM. The posterior belly of the digastric is dissected forward in continuity with the periosteum of the stylomastoid foramen. The eggshell of bone is removed from the entire facial nerve using a Rosen needle or sickle knife. The fibrovascular attachments of the facial nerve within its canal are sharply dissected and the nerve elevated to the second genu. The tympanic segment is elevated more readily because it does not have the fibrovascular attachments. The entire nerve is transposed forward along with the posterior belly of the digastric and the parotid tail. A large silk suture is placed through the stylomastoid perios-


Silk 2-0 catgut
4-0 nylon
Skin closed
Cartilage c
*
Periosteal flap folded over meatus and utured anteriorly
A
B
B
\
C

FIG. 12. A: Postauricular approach demonstrating preservation of an anteriorly based periosteal flap, and dissection of lateral canal skin from cartilage. B: Everting stitches placed superiorly and interiorly that are grasped with a hemostat through the ear canal and brought out laterally. C: Complete closure of the everted canal skin.

FIG. 13. A,B: The anteriorly based mastoid periosteal flap is folded anteriorly and sutured in place, providing another layer of closure medial to the everted canal skin.


Tumor
ICA
Jugular vein

FIG. 14. Completed dissection. The facial nerve has been skeletonized, the tympanic ring has been removed, and the great vessels are exposed.

teum to the soft tissue surrounding the zygomatic root (Fig. 15). The use of continuous facial nerve monitoring during rerouting has dramatically improved postoperative facial nerve function (52).

A large Perkins retractor is placed beneath the mandibular angle, and the entire mandible is retracted anteriorly. The exposure offered by this maneuver obviates the need to resect the mandibular condyles, even with large tumors that extend into the infratemporal fossa. Attention is now directed to the sigmoid sinus, jugular bulb, and petrous carotid artery. Using diamond burs, the bone over these structures is removed, preserving a bony shelf over the proximal sigmoid sinus.

The jugular vein and external carotid artery are now doubly ligated proximally and distally in the neck. If the tumor extends intradurally, the proximal sigmoid sinus is doubly ligated with silk sutures passed through openings in the dura with an aneurysm suture passer (Fig. 16). If the tumor is extradural, the sigmoid sinus is packed extraluminally with oxidized cellulose, using the shelf of bone left remaining proximally. The jugular vein is then dissected from inferior to superior under the spinal accessory nerve to the level of the jugular bulb. Tumor is freed from the carotid artery and bleeding from the caroticotympanic vessels is controlled with bipolar cautery. If the tumor intimately involves the carotid artery, a small portion is left attached until the conclusion of the procedure. Delaying this subadventitial dissection allows complete exposure and direct repair of small entry sites into the carotid artery in the areas of the caroticotympanic branches (Fig. 17). The tumor is dissected superiorly off of the lower cranial nerves in continuity with the jugular bulb. Oxidized cellulose is used to pack the inferior petrosal sinus and condylar vein.

The management of intracranial tumor extension depends on the size and location of the tumor, and the status of the patient. Small intracranial tumor extensions are removed with the jugular bulb because this is typically the site of dural penetration. The decision to remove large intracranial extensions is based on the hemodynamic status of the patient. Blood loss in excess of 3 liters usually prompts a second-stage approach to total tumor removal. More often, the intraoperative blood loss is less than 3 liters, and the authors proceed with total tumor removal in a single stage.

Removal of the intracranial portion is facilitated by the earlier steps in the procedure, which have significantly devascularized the remnant. The remaining vessels can be cauterized discretely and the tumor removed from the posterior fossa (Fig. 18). Closure is accomplished by closure of the eustachian tube with oxidized cellulose and a temporalis muscle plug. The dural defect is approximated as closely as possible, and thin strips of abdominal fat are used to plug the remaining dural dehiscences and the lateral soft tissue defect. The wound is closed over a Penrose drain, and a pressure dressing is applied.

Lateral skull base defects from paraganglioma removal are rarely large enough to require regional or free flap coverage. Larger dural defects can be managed with a variety of local grafts and flaps, including temporalis fascia grafts, temporoparietal fascial flaps, or temporalis muscle flaps (53). Regional and free flaps are reserved for large lateral skull base defects in previously irradiated fields.


Periosteum of stylomastoid foramen tacked superiorly
Facial nerve rerouted anteriorly
Tumor

FIG. 15. The facial nerve has been transposed to the first genu and the periosteum of the stylomastoid foramen has been sutured anteriorly to support the nerve without tension.

продолжение

продолжение



FIG. 16. The jugular vein and sigmoid sinus are doubly ligated. If the tumor is completely extradural, the sigmoid sinus is packed extraluminally in its more proximal course.


Tumor dissected from internal cartoid artery
Tumor delivered posteriorly

FIG. 17. The remaining piece of tumor is removed from the petrous carotid artery. The caroticotympanic branches can be closed at this

time with vascular sutures.



FIG. 18. The devascularized intracranial portion can now be removed. The feeding vessels are controlled with bipolar cautery.

If cerebrospinal fluid (CSF) is encountered, continuous lumbar drainage is placed for approximately 5 days after surgery. Once the epidural catheter is placed through the L4-5 interspace, intravenous tubing is attached in reverse direction through an intravenous infusion pump (54). The pump is set at 10 ml/hour and a continuous slow flow of CSF is withdrawn.

RESULTS Tympanicum

Tumors

O'Leary et al. reviewed 64 cases of tympanicum tumors treated at the House Ear Clinic between 1957 and 1990 (20). Eighty percent of these tumors were removed through a mastoid-extended facial recess approach. The preoperative mean air-bone gap was reduced from 10 dB to a postoperative mean of 4 dB. There were only five complications, including two tympanic membrane ruptures, one cholesteatoma, and one transient facial palsy that resolved to a House grade II/VI after decompression.

Jugulare Tumors

Green et al. reviewed the surgical outcome in 52 previously untreated jugulare tumors managed at the House Ear Clinic between 1980 and 1991 (16). The surgical approach most commonly used was the infratemporal fossa approach (83%). Twenty-nine percent of the tumors extended intradurally, and 21% involved the internal carotid artery. Complete surgical removal was possible in 85%, and there were no surgical mortalities. Of the eight patients with incomplete removal, three had involvement of the internal carotid artery and five had significant intraoperative blood loss prohibiting complete tumor removal in a single stage.

Postoperative complications are infrequent (Table 5). Long-term facial nerve function was good (House grade I/VI or II/VI) in 95% of the patients treated. Approximately 19% of the patients required vocal cord augmentation, and four required enteric feeding because of aspiration. No patient required immediate postoperative tracheotomy and, overall, 85% of the patients were able to resume their preoperative level of activity.

TABLE 5. *Postoperative complications in 52 patients with jugulare tumors studied at the House Ear Clinic, Inc.*

Complication	Percentage
Pneumonia	6
Stroke	0
Cerebrospinal fluid leak	4
Meningitis	4
Aspiration	4
Pulmonary embolus	2
Wound infection	6
Seroma	4

From ref. 16, with permission.

COMPLICATIONS

Tympanicum Tumors

The complications of tympanicum tumor removal are similar to those of tympanomastoid surgery for chronic ear disease. Tympanic membrane perforation, facial nerve injury, cholesteatoma, and bleeding are managed as they would be in all tympanomastoid surgery.

Jugulare Tumors

As described in the Results section, postoperative complications are infrequent (see Table 5). Intraoperative complications can be classified as cranial nerve, carotid artery, and intracranial injury. Continuous intraoperative facial nerve monitoring and modifications to facial nerve rerouting have led to improved postoperative results (16,52). Direct infiltration of the facial nerve requires excision and grafting. The authors have rarely found the need for tracheotomy or gastrostomy (<4%). Early vocal cord augmentation is recommended for new vagal paralyses, especially in the setting of glossopharyngeal nerve dysfunction (55).

The risk of vascular injury can be ascertained before surgery with the appropriate imaging studies. Although preoperative embolization diminishes intraoperative blood loss, the possibility of significant blood loss must be anticipated. The authors' patients are counseled on the utility of autologous donation in the weeks before surgery.

Intracranial removal of paragangliomas must be coordinated with a neurosurgeon. The possibility for intracranial hemorrhage, meningitis, or a CSF leak must be anticipated and may require neurosurgical management.

RADIATION THERAPY

The role of radiation therapy in the treatment of jugulotympanic paragangliomas is controversial. Many reports have appeared in the old and more recent literature reporting tumor control rates of 70% to 90% with radiation as primary, adjunctive, or salvage therapy (56-58). The doses given in these studies are between 3,500 and 5,000 cGy. The primary effect of radiation therapy appears to be on the vascular and stromal elements of the tumor, with little effect on the tumor cells (59). Viable tumor cells remain after radiation, and tumors have been known to recrudesce after more than a decade (58). With the advent of microsurgical techniques, the authors have identified few specific indications for radiation therapy. This form of treatment is recommended for elderly patients with symptomatic tumors or for patients who are unsuitable for or unwilling to undergo surgical resection.

CONCLUSIONS

Jugulotympanic paragangliomas are the most common tumors of the middle ear and the second most common tumors of the temporal bone. The diagnosis and management of these tumors have been facilitated by modern imaging techniques. Microsurgical techniques with electromyographic cranial nerve monitoring, coupled with the multitude of reconstructive options, make surgical excision the preferred method of treatment.

ACKNOWLEDGMENT

The authors thank Karen I. Berliner, Ph.D. for her editorial assistance.

REFERENCES

1. Valentin G. Ueber eine gangliose Anschwellung in der Jacobsonchen Anastomose des Menschen. *Archiv Fur Anatomie Physiologie Und Wissenchaftliche Median* 1840;89:287.
2. Krause W. Die Glandula Tympanica des Menschen. *Zentralblatt Fur Die Medicinischen Wissenchqften* 1878;16:737.
3. Guild SR. The glomus jugulare. a nonchromaffin paraganglion, in man. *Ann Otol Rhinol Lan-ngol* 1953;62:1045.
4. Rosenwasser H. Carotid body tumor of the middle ear and mastoid. *Archives of Otolaryngology* 1945;41:64.
5. Lattes R, Waltner JG. Nonchromaffin paraganglioma of the middle ear. *Cancer* 1949;2:447.
6. Winship T, Klopp CT, Jenkins WH. Glomus-jugularis tumors. *Cancer* 1948:1:441.
7. Steinberg N. Holz WG. Glomus jugularis tumors. *Archives of Otolaryngology* 1965:82:367.
8. Gulya AJ. The glomus tumor and its biology. *Laryngoscope* 1993;103[Suppl60]:3.
9. Glenner GG, Grimley PM. Tumors of the extra-adrenal paraganglion system (including chemoreceptors). In: *Atlas of tumor pathology.* 2nd series, fascicle 9. Washington, DC: Armed Forces Institute of Pathology, 1974;!.
10. Wenig BM. Neoplasms of the ear. In: Wenig BM, ed. *Atlas of head and neck pathology.* Philadelphia: WB Saunders, 1993:368.
11. LeComptePM. Tumors of the carotid body. *Am J Pathol* 1948:24:305.
12. Grimley PM, Glenner GG. Histology and ultrastructure of carotid body paragangliomas. *Cancer* 1967;20:1473.
13. Alford BR, Guilford FR. A comprehensive study of tumors of the glomus jugulare. *Laryngoscope* 1962;72:765.
14. Spector GJ, Sobol S, Thawley SE, Maisel RH, Ogura JH. Glomus jugulare tumors of the temporal bone: patterns of invasion in the temporal bone. *Laryngoscope* 1979:89:1628.
15. Spector GJ, Ciralsky R, Maisel RH, Ogura JH. Multiple glomus tumors in the head and neck. *Laryngoscope* 1975:85:1066.
16. Green JD, Brackmann DE, Ngu'yen CD, Arriaga MA, Telischi FF, De la Cruz A. Surgical management of previously untreated glomus jugulare tumors. *Laryngoscope* 1994:104:917.
17. Parkin JL. Familial multiple glomus tumors and pheochromocytomas. *Annals of Otology, Rhinology and Laryngology* 1981;90:60.
18. Brown LA. Glomus jugulare tumor of the middle ear: clinical aspects. *Laryngoscope* 1953:63:281.
19. Aquino J. Glomus jugulare tumors. *Archives of Otolaryngology* 1957:65:263.
20. O'Leary MJ, Shelton C, Giddings NA, Kwartler J, Brackmann DE. Glomus tympanicum tumors: a clinical perspective. *Laryngoscope* 1991:101:1038.
21. House WF, Glasscock ME. Glomus tympanicum tumors. *Archives of Otolaryngology* 1968;87:550.
22. El Fiky FM, Paparella MM. A metastatic glomus jugulare tumor. *Am J Otol* 1984;5:197.

23. Druck NS, Spector GJ, Ciralsky RH, Ogura JH. Malignant glomus vagale. *Archives of Otolaryngology* 1976; 102:634.
24. Wright JW, Wright JW, Hicks GW. Radiologic appearance of glomus tumors. *Laryngoscope* 1979;89:1620.
25. Spector GJ, Gado M, Ciralsky R, Ogura JH, Maisel RH. Neurologic implications of glomus tumors in the head and neck. *Laryngoscope* 1975;85:1387.
26. Lo WWM, Horn KL, Carberry JN, et al. Intratemporal vascular tumors: evaluation with CT. *Radiology* 1986;!59:181.
27. Lo WWM, Shelton C, Waluch V, et al. Intratemporal vascular tumors: detection with CT and MR Imaging. *Radiology* 1989;171:443.
28. Lo WWM, Solti-Bohman LG, Lambert PR. High-resolution CT in the evaluation of glomus tumors of the temporal bone. *Radiology* 1984; 150:737.
29. Som PM, Reede DL, Bergeron T, Parisier SC, Shugar JMA, Cohen NL. Computed tomography of glomus tympanicum tumors. *J Comput Assist Tomogr* 1983;7:14.
30. Olsen WL, Dillon WP, Kelly WM, Norman D, Brant-Zawadzki M, Newton TH. MR imaging of paragangliomas. *AJNR Am J Neuroradiol* 1987:148:201.
31. Vogl TJ, Juergens M, Balzer JO, et al. Glomus tumors of the skull base: combined use of MR angiography and spin-echo imaging. *Radiology* 1994;192:103.
32. Rodgers GK, Applegate L, De la Cruz A, Lo W. Magnetic resonance angiography: analysis of vascular lesions of the temporal bone and skull base. *Am J Otol* 1993; 14:56.
33. Kwekkeboom DJ, Van Urk H, Pawn BKH, et al. Octreotide scintigraphy for the detection of paragangliomas. *J Nud Med* 1993;34:873.
34. Schwaber MK, Glasscock ME, Jackson CG, Nissen AJ, Smith PG. diagnosis and management of catecholamine secreting glomus tumors. *Laryngoscope* \984;94:1008.
35. Cantrell RW, Kaplan MJ, Winn HR, Atuk NO, Jahrsdoerfer RA. Catecholamine-secreting infratemporal fossa paraganglioma. *Ann Otol RhinolLaryngol* 1984;93:583.
36. Murphy TP, Brackmann DE. Effects of preoperative embolization on glomus jugulare tumors. *Laryngoscope* 1989;99:1244.
37. Mclvor NP, Willinsky RA, TerBrugge KG, Rutka JA, Freeman JL. Validity of test occlusion studies prior to internal carotid artery sacrifice. *Head Neck* 1994;16:11.
38. Peterman SB, Taylor A, Hoffman JC. Improved detection of cerebral hypoperfusion with internal carotid balloon test occlusion and 99mTc-HMPAO cerebral perfusion SPECT imaging. *AJNR Am J Neuroradiol* 1991;12:1035.
39. Monsein LH, Jeffery PJ, van Heerden BB, et al. assessing adequacy of collateral circulation during balloon test occlusion of the internal carotid artery with ^{99m}Tc-HMPAO SPECT. *AJNR Am J Neuroradiol* 1991;12:1045.
40. de Vries EJ, Sekhar LN, Horton JA, et al. A new method to predict safe resection of the internal carotid artery. *Laryngoscope* 1990; 100:85.
41. Andrews JC, Valvanis A, Fisch U. Management of the internal carotid artery in surgery of the skull base, *laryngoscope* 1989;99:1224.
42. Sinnreich Al, Parisier SC, Cohen NL, Berreby M. Arterial malformations of the middle ear. *Otolaryngol Head Neck Surg* 1984;92:194.
43. Glasscock ME, Dickins JRE, Jackson CG, Wiet RJ. Vascular anomalies of the middle ear. *Laryngoscope* 1980;90:77.
44. McElveen JT, Lo WWM, El Gabri TH, Nigri P. Aberrant internal carotid artery: classic findings on computed tomography. *Otolaryngol Head Neck Surg* 1986;94:616.
45. Conley J, Hildyard V. Aneurysm of the internal carotid artery presenting in the middle ear. *Archives of Otolaryngology* 1969;90:61.
46. Goodman RS, Cohen NL. Aberrant internal carotid artery in the middle ear. *Annals of Otology, Rhinology and Laryngology* 1981 ;90:67.
47. Stallings JO, McCabe BF. Congenital middle ear aneurysm of internal carotid. *Archives of Otolaryngology* 1969;90:65.
48. Lo WWM, Solti-Bohman LG, McElveen JT. Aberrant carotid artery: radiologic diagnosis with emphasis on high-resolution computed tomography. *Radiographics* 1985;5:985.
49. Brackmann DE, Arriaga MA. Surgery for glomus tumors. In: Brackmann DE, Shelton C, Arriaga MA, eds. *Otologic surgery.* Philadelphia: WB Saunders, 1994:579.
50. Brackmann DE. The facial nerve in the infratemporal approach. *Otolaryngol Head Neck Surg* 1987;97:15.
51. Fisch U. Infratemporal fossa approach for glomus tumors of the temporal bone. *Ann Otol Rhinol Laryngol* 1982;91:474.
52. Leonetti JP, Brackmann DE, Prass RL. Improved preservation of facial nerve function in the infratemporal approach to the skull base. *Otolaryngol Head Neck Surg* 1989;101:74.
53. Netterville JL, Civantos FJ. Defect reconstruction following neurotologic skull base surgery. *Laryngoscope* 1993;103[Suppl 60]:55.
54. Brackmann DE, Rodgers GK. Management of postoperative cerebrospinal fluid leaks. In: Brackmann DE, Shelton C, Arriaga MA, eds. *Otologic surgery.* Philadelphia: WB Saunders, 1994:701.
55. Netterville JL, Civantos FJ. Rehabilitation of cranial nerve deficits after neurotologic skull base surgery. *Laryngoscope* 1993;103[Suppl 60]:45.
56. Mendenhall WM, Parsons JT, Stringer SP, Cassisi NJ, Singleton GT. Million RR. Radiotherapy in the management of temporal bone chemodectoma. *Skull Base Surgery* 1995;5:83.
57. de Jong AL, Coker NJ, Jenkins HA, Goepfert H, Alford BR. Radiation therapy in the management of paragangliomas of the temporal bone. *Am J Otol* 1995:16:283.
58. Cole JM, Beiler D. Long-term results of treatment for glomus jugulare and glomus vagale tumors with radiotherapy. *Laryngoscope* 1994;104:1461.
59. Brackmann DE, House WF, Terry R, Scanlan RL. Glomus jugulare tumors: effect of irradiation. *Ophthalmology and Otolaryngology* 1972;76:1423.

SECTION IV

Midline Approaches

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 25

Extreme Lateral Transcondylar Approach to the Craniocervical Junction

Chandranath Sen and Peter J. Catalano

Tumors arising ventral and ventrolateral to the brainstem and the cervicomedullary junction pose some special problems for the neurosurgeon, including difficulty of access and involvement of the vertebral artery and lower cranial nerves, either by the tumor itself or the path of the surgical approach. Some of these tumors may also invade extradural tissues. Most of the tumors, either benign (e.g., meningiomas, schwannomas, glomus tumors) or locally aggressive (e.g., chordomas and chondrosarcomas), are amenable to radical resection, which provides the best chance for long-term control or cure. Aneurysms arising from the vertebral artery and vertebrobasilar junction may also present surgical difficulties.

A standard lateral suboccipital approach may not be adequate to achieve a radical tumor resection or safely clip an aneurysm with full visualization. A more lateral approach, along with control and mobilization of the vertebral artery as it enters the dura, with or without some resection of the occipital condyle, allows better visibility anterior to the brainstem and favorably influences the safety and completeness of the operation.

ANATOMIC CONSIDERATIONS The

Bony Anatomy

The shape of the bony foramen magnum can be round or oval, and thus the surface in front of the brainstem may be deep or shallow, depending on this shape. The occipital condyles form the anterolateral margins of the foramen magnum and are directed anteromedially, whereas the articular surfaces point anterolaterally. The hypoglossal canals run in the medial third of the condyles and a large condylar emissary vein exits posteriorly, joining the jugular bulb with the extracranial venous system. The shape of the foramen magnum determines how much of an obstacle the occipital condyle poses to surgical access of the area anterior to the brainstem. The occipital condyle is more of a hindrance in a deep and oval foramen magnum than a shallow one. This in turn determines the trajectory of the surgical approach—whether a lateral or a posterolateral approach with or without partial condyle resection is needed for the lesion.

The Vertebral Artery

The third portion of the vertebral artery begins at the foramen transversarium of C2 and ends where it enters the dura. Within the foramen transversarium of C2, the artery turns laterally and posteriorly and exits C2 at a different plane than the one at which it enters. The artery ascends to enter the transverse foramen of Cl, after which it turns sharply backward, traveling along the upper surface of the Cl posterior arch. It curves around the occiput-Cl articulation and enters the dura on the lateral surface of the thecal sac. Between C2 and Cl, as well as above Cl, the artery may be redundant to a variable extent. This fact should be taken into account during surgery to avoid inadvertent injury to the artery. Up to the point where the artery enters the dura, it is surrounded by a periostea! and venous sheath. Below Cl, the artery is crossed on its lateral surface from posterior to anterior by the ventral ramus of the C2 nerve root. Above Cl, the artery closely adheres to the occiput-Cl joint capsule as it goes around to enter the dura. The artery pierces the dura in an oblique fashion, and this must be noted while the dura is being opened in this area.

C. Sen: Department of Neurosurgery, Mount Sinai Medical Center, New York, New York 10029.
P. J. Catalano: Department of Otolaryngology, Mount Sinai Medical Center, New York, New York 10029.

Because the jugular and hypoglossal foramina are immediately above the occipital condyle, cranial nerves IX to XII are often either directly involved by the tumor or in the field of the surgical approach. Within the jugular foramen, cranial nerves IX, X, and XII are medial to the jugular bulb. The inferior petrosal sinus joins the jugular bulb from a medial direction, and may enter by traveling in between the cranial nerves. This may be a troublesome source of bleeding in dealing with tumors in this area, and requires careful packing to avoid injuring the nerves. Cranial nerve XII exits separately inferior and medial to the jugular foramen. Within the bony canal, cranial nerve XII travels upward and laterally, whereas cranial nerves IX, X, and XI travel inferiorly and laterally. This relationship is important in dealing with extradural tumors. The hypoglossal nerve is accompanied by an emissary vein and a branch of the ascending pharyngeal artery.

PRINCIPLES OF THE SURGICAL APPROACH

1. Control and mobilization of the vertebral artery is a key step in the approach to lesions at the anterior surface of the foramen magnum.
2. To accomplish control and mobilization, the artery needs to be circumferentially freed from the dura at its entry.
3. Because the vertebral artery enters the dura close to the posterior edge of the occipital condyle and C1 lateral mass, some amount of bone removal from the condyle facilitates freeing up the vessel.
4. Extradural tumors that have invaded the condyle and are in the hypoglossal and jugular foramina require resection of the entire condyle and the diseased bone.
5. If the lower cranial nerves are involved by the tumor, they should be dissected from a normal to the abnormal area in their respective foramina, and this means exposing them proximally and distally.

PREOPERATIVE EVALUATION

A detailed neurologic evaluation is an essential baseline. Special attention is directed to the status of lower cranial nerve function because this is the most common cause of surgical morbidity. High-resolution computed tomography (CT) and magnetic resonance imaging (MRI) demonstrate, respectively, the bony and soft tissue relations of the lesion. Arteriography is performed to assess the relations between the vertebral arteries, tumor vascularity, and the status of the sigmoid sinus and jugular bulb. Improvements in MRI capabilities make it possible to assess MR angiograms stereoscopically, giving excellent three-dimensional visualization of the tumor and its surroundings. The shape of the foramen magnum as seen on CT scan can be useful in determining the directions of the approach and whether and how much removal of the occipital condyle may be necessary for adequate visualization.

THE SURGICAL APPROACH (1,2)

Position

Proper positioning is an important aspect of foramen magnum tumor surgery. Flexion and extension of the head on r"^ spine causes changes in the dimensions of the foramen m. _ num. Thus, when there is a tumor impinging on the brainstem, there can be further compromise of neural function because of improper positioning. Rotation of the head on the spine leads to distortion of the vertebral artery anatomy at the occiput-Cl-2 areas. Therefore, for tumors in this region, the patient is positioned in full lateral decubitus with the head and neck in a neutral position (Fig. 1). Somatosensory evoked potentials are monitored during positioning as wel! as during surgery.

Soft Tissue Dissection and Vertebral Artery Exposure

Usually, a C-shaped incision (see Fig. 12a) is used behind the ear such that the incision reaches the midpoint between the inion and the mastoid. If an occipitocervical fusion is planned, as might be necessary when the entire occipital condyle is resected, an inverted horseshoe incision is made (see Fig. 1). This is made with one of the limbs along the midline and the other limb at the side of the neck. The horizontal limb is at the level of the upper border of the ear. Muscle dissection in the posterior cervical triangle is preferably performed in anatomic layers, detaching each muscle from its cephalic attachment and reflecting it inferiorly (Fig. 2). This type of muscle dissection has two main benefits: it maintains the surgeon's orientation to the area of the approach during isolation and control of the vertebral artery: and it clears away the muscles from a wide arc so that the surgeon may view the area from a lateral and a medial trajectory instead of being restricted to only one line of view.

The transverse process of Cl and the muscles attached to it (i.e., levator scapulae, superior and inferior oblique) form an important landmark for the third segment of the vertebral artery. The internal jugular vein is in front of the transverse process of Cl and the accessory nerve curves around lateral to the vein in this area before entering the sternocleidomas-toid muscle. The vertebral artery can be isolated for proximal control below or above C1, depending on the level of the lesion. If the inferior border of the inferior oblique muscle is followed anteriorly between the transverse process of Cl and the lateral mass of C2, the ventral ramus of the C2 root is seen crossing the vertebral artery. The portion of the artery above C1 is deep to the superior oblique muscle. The vertebral artery is surrounded by a plexus of veins that can be left



FIG. 1. The patient is positioned in a lateral decubitus position with the head fixed in a three-point head rest in a neutral position without rotation or flexion. The inverted horseshoe incision is shown.


Sternomastoid muscle turned anteriorly
Lateral aspects of the articular facets, ipsilateral laminae and V3 segment of the vertebral artery

FIG. 2. The lateral view illustrates the muscle dissection in layers. The muscles are detached from their attachments to the occiput and C1 and reflected anteroinferiorly or postero-inferiorly.

intact if mobilization of the anew is not necessary. However, if the artery needs to be mobilized and displaced from its position, the venous plexus is stripped from the artery that is needed; otherwise, the venous bleeding can be troublesome, A rubber vessel loop passed around the artery provides an atraumatic handle on the vessel. Because the artery is thin walled, isolation and manipulation of the artery is preferably performed under magnification. The artery is intimately related to the occipul-Cl joint capsule and must be carefully freed from this for circumferential control. If access to the anterior aspect of C1 is also required, the vertebral artery is freed up from the foramen transversarium of CI and the transverse process is then rongeured away so that the artery can be displaced out and posteriorly, providing clear access to the area in front.

Bony Exposure

The extent of the bony exposure is determined by the size and location of the lesion. If the tumor in the posterior fossa is large, a large craniectomy that extends up to the sigmoid and transverse sinuses is performed. The sigmoid sinus is completely unroofed down to the jugular bulb (Fig. 3). Tumor extension into the jugular foramen can be accessed by this exposure. Collaboration with an otologist is helpful for the temporal bone drilling. Tumors that are at the foramen magnum or lower do not require such extensive posterior fossa exposure. Hemilaminectomy of Cl may be necessary for low-lying tumors. After the vertebral artery has been fully exposed as needed, the bone in front of it, which is the posterior part of the condyle, is carefully drilled away to gain room in front of the artery as well as access to the anterior surface of the foramen magnum (Fig. 4). Venous bleeding i> frequently encountered while working in this area and can arise from the condylar emissary vein. Packing with Surgicel usually suffices, along with careful elevation of the head. For purely intradural lesions, usually less than one third of the condyle needs to be drilled away for access. However, extradural tumors like chordomas and chondrosarcomas invading the condyle may necessitate removal of the entire condyle (Fig. 5).

Tumor Removal

The dura is opened medial to the sigmoid sinus and the jugular bulb and caudally. behind the vertebral artery entrance. After inspecting inside the dura, the dura is incised circumferentially around the vertebral artery entrance so that the artery is completely freed to be moved anteriorly and posteriorly, facilitating its dissection from the tumor or exposure of the aneurysm (Fig. 6). For intradural tumors, standard microsurgical techniques are used to debulk the tumor progressively and then dissect it off the brainstem, cranial nerves, and blood vessels. Extradural tumors may invade the dura and extend inside. Removal of the extradural tumor requires drilling of the temporal bone so that all the soft portion of the tumor and the infiltrated bone is removed. The jugular and hypoglossal canals may need to be skeletonized while carefully protecting the cranial nerves. Before entering the jugular bulb, the sigmoid sinus and the internal jugular



FIG. 3. A suboccipital craniectomy and a mastoidectomy have been performed. Only the posterior portion of the sigmoid sinus is usually unroofec unless the tumor extends into the jugular foramen, in which case the entire sigmoid sinus is unroofec


Occiput -
joint exposed after excising capsule
Extradural
XII
Surgicel
A
B
🟥 to be drilled
to be drilled *it* tumor excision **requires it**

FIG. 4. A: A portion of the joint capsule of the occipital condyle and C1 is excised in preparation for the drilling. B: Most of the occipital condyle has been drilled away before opening the dura. The extradural cranial nerve XII has been exposed. The extent of drilling is tailored to the individual case. If the tumor is extradural, at the level of C1 the vertebral artery is displaced from the foramen transversarium of C1 and reflected posteriorly to improve the access to the anterior part of C1.


Int. carotid a
V
VI
Petr
IC
VII, VIII
IX, X, XI
XII

FIG. 5. A view of the interior of the skull at the foramen magnum region. The shaded area indicates the region of the condyle drilled away by this approach.



FIG. 6. Diagram showing that the internal jugular vein and the sigmoid sinus have been ligated and the infralabyrinthine bone and the occipital condyle have been drilled away to access the jugular foramen and foramen magnum.

vein should be ligated. All the infiltrated bone is drilled away as far as possible and the involved dura is also excised.

Closure involves measures to avoid a postoperative cerebrospinal fluid fistula. The mastoid air cells are heavily waxed and the aditus to the middle ear, if opened, should be well sealed. The dura is closed as well as possible, although watertight closure is almost impossible. A piece of autologous Tat is placed over the dural defect and the muscles are closed in layers.

Stabilization of the Craniocervical Junction

If the remainder of the craniocervical articulation is normal, partial condyle resection does not render the joint unstable. Complete removal of the condyle usually warrants an occipitocervical fusion. Several methods of occipitocervical stabilization are available and can be used despite the posterior fossa craniectomy. Titanium hardware is preferable so that MRI is possible to monitor the patient for tumor recurrence. The stabilization procedure can be performed at the same sitting as the tumor removal, or at a later stage. Even though hardware is used for the stabilization, there must be enough bone laid in contact with the bony surfaces because the ultimate success of the fusion depends on the bony union.

POSTOPERATIVE CARE

A lumbar spinal drain is inserted the day after the operation and is kept in place for 5 days to minimize the development of a cerebrospinal fluid fistula or a pseudomeningocele. The function of the lower cranial nerves must be closely monitored in the early postoperative period, especially if they have been manipulated. If there is any sign of dysfunction, airway protection and deglutition must be carefully evaluated. A low threshold for performing a tracbeostomy or gastrostomy should be maintained because either one ensures a rapid convalescence and is a temporary measure.

CASE 1: MENINGIOMA

This 68-year-old woman had undergone resection of a large meningioma in the posterior fossa extending down to Cl 4 years before her uurrent recurrence. The recurrence was detected because of severe neck pain and gait difficulty. MRI showed a large tumor in the foramen magnum region completely encasing the vertebral artery on her left side (Fig. 7).

The operation was performed by completely skeletonizing the vertebral artery outside the dura and then following it into the dura and the tumor. A minimal amount of condyle resection was necessary to gain this exposure (Fig. 8). The tumor was completely freed from the artery and the brainstem. but a small piece was left on the lower cranial nerves because their function was intact, and at her age a sudden palsy would be poorly tolerated (see Fig 8B,C).

Comment: This patient had a shallow foramen magnum and therefore only a small amoum of condyle needed to be resected for the approach. The importance of control and mobilization ol the vertebra] artery before its entry into the dura and at its dural entry is evident here. Without this, it would have been very difficult to dissect out the vessel from the tumor, considering its complete encasement.

CASE 1 (Continued)



FIG. 7. Case 1. Axial **(A)** and coronal **(B)** magnetic resonance images of recurrent meningioma after administration of gadolinium show the tumor in the anterior intradural space; the vertebral artery is in the tumor *(arrow)* as soon as it enters the dura.

CASE 1 (Continued)


SINAI MEDICAL CENTER, NYC
11/02/95
13:10
L
1
1
0
6kHz
Ex:624
Se:5/5
Im:4/22
Ax I75.9+C
R
1
1
0
SE/cs
TR:450
TE:16
EC:1/1 16kHz
HEAD
SINAI MEDICAL CENT
Signa 1.5T
MEDICAL CENTER
A
EC:1/1 16kHz
HEAD
B
C

FIG. 8. Case 1 A: Postoperative magnetic resonance image showing that only a minimum amount of condyle was resected for the approach. B,C: Except for a small amount of tumor left on the lower cranial nerves, excellent tumor removal was achieved despite encasement of the vertebral artery.

CASE 2: GLOMUS JUGULARE TUMOR

This 38-year-old woman had symptoms for 3 years before her admission. These involved atrophy of the left side of the tongue, hoarseness of voice, and decreased hearing. MRI showed an extensive tumor in the clivus, posterior cavernous sinus, jugular foramen, and neck (Fig. 9). The angiographic appearance was that of a glomus tumor, and the external carotid artery feeders were embolized.

The operation was performed in two stages because of the tumor's size and multiple cranial nerve involvement. At the first operation, the temporal bone was partially drilled away to unroof the internal auditory canal, and the cochlea was drilled away to expose the genu of the petrous internal carotid artery. The vertebral artery was displaced posteriorly from the foramen transversarium of Cl up to its entry into the dura (Fig. 10). This considerably im-

CASE 2: (Continued)



FIG. 9. Case 2. A-C: Glomus tumor extending from C2 to the posterior cavernous sinus, and into the internal auditory canal. D: Although the external carotid feeders had been embolized, the supply from the vertebral artery and internal carotid artery could not be occluded before surgery. By following the vertebral artery from the normal area at C1 into the tumor, the blood supply *(arrow)* could be directly interrupted.

CASE 2: (Continued)

proved access to the portion of the tumor that was coming down from the jugular foramen. A portion of the occipital condyle was drilled away to access the tumor in the hypoglossal canal. All the tumor that was caudal to the internal auditory canal was removed at this stage. At the second stage, the tcntorium was divided and, through a combined subtemporal and posterior fossa approach, ihe tumor from the upper clivus and posterior cavernous sinus was removed.

Comment: The tumor followed the venous channels all the way up to the posterior cavernous sinus. It also extended into the clivus and petrous segment of the internal carotid artery. Taking the vertebral artery out of the Cl transverse foramen and moving it posteriorly provided additional room and permitted less facial nerve mobilization, so excellent tumor removal was achieved without any facial nerve morbidity. Because the tumor rose up to the posterior cavernous sinus, the operation was performed in two stages.



FIG. 10. Case 2. Posterior mobilization of the vertebral artery from the foramen transversarium of C1 and partial drilling of the occipital condyle improves the access to the tumor, reducing the amount of facial nerve mobilization.

CASE 3: CHORDOMA

This 66-year-old man was evaluated for difficulty swallowing and unsteadiness of gait. More recently, he complained of severe pain in his occiput and posterior neck. On examination. The right half of his tongue was atrophied and his gag reflex was diminished. He had a conductive hearing loss on audiumetric evaluation. CT and MRI showed a large tumor in the clivus. foramen magnum, and Cl with severe brainstem compression (Fig. 11). Angiography showed distortion of the vertebral arteries and good communication of the transverse sinuses at the lorcular.

The operation was performed in two stages (Fig. 12). At the first operation, the exposure was carried out. This included temporal and posterior fossa craniotomies. closure of the external car canal, mastoideclomy, and labynnthcctomy. The petrous internal carotid artery was exposed through the cochlea, the jugular bulb was fully skeletonized, and the vertebral artery was taken out of the Cl foramen transversarium and folloxved to its durai entrv. An elective tracheostomy and percutaneous gastrostomy was performed in view of his prcoperative deficits and anticipated cranial nerve problems after surgery. The tumor resection, which was done at the second stage, was carried out through both intradural and extradural routes. Thejugular bulb and the lower cranial nerves were skeletonized and the invaded dura was excised. The involved bone was drilled away, including the occipital condyte and part of the lateral mass and anterior arch of CI. An occipito-cervical fusion with titanium instrumentation was performed after the tumor resection (Fig. 13).

Commeni: Hearing on the right side was sacrificed because of the large size of the tumor. The entire occipital condyle and part of the lateral mass of CI and its anterior arch were resected. The occipitocervical fusion was performed to reestablish the stability of the craniovertebral junction.

CASE 3: (Continued)


SINAI MEDICAL CENTER, NYC
SE/cs
TR:800
TE:15
HEAD
FOV:16×16
3.0thk/1.0sp
SINAI MEDICAL CENTER, NYC
SE/cs
TR:800
TE:15
HEAD
FOV:16×16
Ex:984
Se:8/8
Im:6/12
TR:6000
HEAD
FOV:18×18
3.0thk/1.0sp
12/09:36
B
C

FIG. 11. Case 3. A-C: Preoperative magnetic resonance imaging and computed tomography (CT) show a chordoma extending intradurally as well as extradurally, involving the carotid and vertebral arteries on the right side. It severely indents the brainstem and reaches across the midline. CT shows that the right lateral mass of C1 is also invaded.

CASE 3: (Continued)



FIG. 12. Case 3. A,B: A large incision is used to provide access to the middle fossa, posterior fossa, and the neck. The external auditory canal was transected and closed. In (B), the exposure is shown with the vertex to the viewer's left and nose to the top. 7, temporal dura; *F,* vertical portion of cranial nerve VII; C, cerebellum seen after the dura was opened; V, vertebral artery at C1; *IJ,* internal jugular vein. C: After the second stage, the tumor has been resected and the orientation is the same as in (B). F, vertical portion of cranial nerve VII; *L,* cranial nerves IX, X, and XI at the jugular foramen and below; *H.* cranial nerve XII in the hypoglossal canal; *V,* vertebral artery at C1. D: Occiput-to-C4 fusion with titanium hardware.

CASE 3: (Continued)





FIG. 13. Case 3. A-C: Postoperative computed tomography scan and cervical spine film showing the extent of bony resection through the combined approaches. The occipital condyle and anterior part of the lower clivus have been drilled away *(arrows).* Stabilization with internal hardware is needed in such extensive bony resection.

DISCUSSION

Among intradural tumors, meningiomas, schwannomas, and glomus tumors, whereas among extradural tumors, chordomas and chondrosarcomas comprise the majority found at the craniovertebral junction. There are several special problems posed by tumors in this region. These are access to the ventral area of the lower clivus and cervicomedullary junction, involvement of the vertebral artery on one or both sides, involvement of the lower cranial nerves, and invasion of extradural soft tissues and bone. The problem of access is also common to aneurysms of the vertebral artery and vertebrobasilar junction. For many of the intradural tumors, the standard retrosigmoid approach usually suffices, but truly ventral tumors are inadequately resected by this approach. In addition, involvement of the extradural tissues cannot be addressed by the standard approaches because of the limitation of the jugular bulb, the occipital condyle, and the vertebral artery within the foramen transversarium of Cl.

The concept of a laterally directed approach with partial resection of the occipital condyle to improve visibility to the


Sphenoid sinus
COULTER
Ring divided
Int. carotid a.
Sphenoid sinus
V2
V3
Clival area
Dura
XII
Int. jugular v.
IX,X
Eustachian tube
Middle ear
Geniculate ganglion
Hypoglossal canal
Cochlea

FIG. 14. **A,B:** The subtemporal and preauricular infratemporal approach through the left side of the head is shown. The petrous internal carotid artery is exposed and mobilized laterally to provide access to the clivus and petrous apex. C: An axial diagram showing the route of access anterior to the important temporal bone structures; shading indicates the area of the clivus that can be approached this way. Comparing this figure with Fig. 5. note how the approaches can be combined such that the inner ear structures are not damaged while accessing the area anterior to the craniocervical junction.

anterior surface of the foramen magnum was perhaps initially described by George et al. (1,2). A closer appreciation of the local anatomy shows the intimate relation of the vertebral artery to this region (3,4). The vessel closely skirts the occiput-Cl joint as it turns around this structure to enter the foramen magnum. It is adherent to the joint capsule in this course, and enters the dura obliquely just behind this articulation. Therefore, mobilization of the artery involves displacing it from the transverse foramen of C1, freeing it up from the joint capsule of atlantooccipital joint, and freeing it up circumferentially from the dural attachment, where it enters the dura. This opens up the passage to the ventral area for a variety of tumors. A laterally placed skin incision and lateral detachment of the muscles, moving them medially, removes any soft tissue bulk from the path of vision (5,6,7).

For purely intradural tumors, the amount of occipital condyle that may need to be resected to have enough room in front of the vertebral artery varies from minimal to none. In this situation, only a short portion of the extradural vertebral artery above Cl needs to be exposed. The limited condylar resection not only allows the surgeon to get in front of the artery, but improves the exposure to the anterior aspect of the foramen magnum (8). During resection of large glomus jugulare tumors, exposure and mobilization of the vertebral artery from the foramen transversarium of Cl improves access to the extracranial part of the tumor and can reduce the degree of facial nerve mobilization required (9). Chordomas and chondrosarcomas are predominantly extradural tumors, and therefore the operative approach should be directed primarily to this compartment. Such tumors may be extensive and also may have intradural extensions; therefore, a combination of approaches, either simultaneously or in a staged fashion, may be necessary. It is not sufficient simply to remove the soft portion of the tumor; the approach or combination of approaches must allow access to the involved bone, which needs to be drilled away, and the invaded dura should be resected if possible.

For a more extensive extradural access, the additional approaches that may be considered depend on the status of the patient's hearing (10). If the hearing is intact, a subtemporal preauricular infratemporal approach can be performed as a first stage to come in front of the ear, freeing up the internal carotid artery in the petrous bone and drilling away the involved bone in front of the labyrinth and cochlea (11) (Fig. 14). The subsequent operation can be done as described previously, coming from behind the inner ear. The infra-labyrinthine bone drilling allows access to the jugular and hypoglossal canals. If no hearing is present or hearing is sacrificed, the temporal bone may be drilled away from behind and clear access is obtained from the vertebral artery to the carotid artery, and the in-depth exposure can be taken across the midline.

If the entire condyle is resected, which sometimes includes the articular mass of C1, a stabilization procedure is necessary. This can be performed either at the same sitting or at a separated stage. A midline posterior incision is necessary for this procedure. Titanium hardware should be used to allow MRI scanning because regular follow-up imaging of these tumors is needed.

Thus, there are several advantages to using the extreme lateral approach: (a) simultaneous lateral and posterolateral avenues of exposure are obtained on the lesion at the lower clivus, Cl, and C2, allowing radical tumor resection; (b) the approach does not traverse contaminated areas such as the pharynx or the paranasal sinuses; (c) it permits excellent control and mobilization of the vertebral artery to allow its safe dissection from the tumor or elimination of the aneurysm; and (d) this operation can be combined with other approaches to enhance the completeness of tumor resection and is equally useful for intradural and extradural tumors.

REFERENCES

1. George B, Dematons C, Cophignon J. Lateral approach to the anterior portion of the foramen magnum. *Surg Neural* 1988;29:484-490.
2. George B, Lot G, Velut S, Gelbert F, Mourier KF. Tumors of the foramen magnum. *Neurochirurgie* 1993;39[Suppl l]:1-89.
3. de Oliveira E, Rhoton AL Jr. Peace D. Microsurgical anatomy of the region of the foramen magnum. *Surg Neural* 1985;24:293-352.
4. Lang J, Kessler B. About the suboccipital part of the vertebral artery and the neighbouring bone-joint and nerve relationships. *Skull Base Surgery* 1991; 1:64-72.
5. Sen C, Sekhar LN. An extreme lateral approach to intradural lesions of the cervical spine and foramen magnum. *Neurosurgerv* 1990;27: 197-204.
6. Sen C, Sekhar LN. Surgical management of anteriorly placed lesions of the craniocervical junction: an alternative approach. *Acra Neurochir (Wien)* 1991;108:70-77.
7. Babu RP, Sekhar LN, Wright DC. Extreme lateral transcondylar approach: technical improvements and lessons learned. *J Neurosurg* 1994:81:49-59.
8. Spetzler RF, Grahm TW. The far lateral approach to the inferior clivus and the upper cervical region: technical note. *BN1 Quarterly* 1990;6:35-38.
9. Patel SJ, Sekhar LN, Cass SP, Hirsch BE. Combined approaches for resection of extensive glomus jugulare tumors. / *Neurosurg* 1994;80: 1026-1038.
10. Fisch U. Infratemporal fossa approach for extensive tumors of the temporal bone and base of the skull. In: Silverstein H, Non-ell H, eds. *Neurological surgery oflhe ear.* Birmingham, AL: Aesculapius Publishing Co., 1977:34-53.
11. Sekhar LN, Schramm VL Jr, Jones NF. Subtemporal and preauricular infratemporal fossa approach to large lateral and posterior skull base neoplasms. *J Neurosurg* 1987;67:488^99.

продолжение

продолжение

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 26

Transoral Approach to the Clivus and Upper Cervical Spine

Paul J. Donald

ANATOMY

The anatomy of the elements of the occipitoatlantoaxial complex is covered superficially in a number of chapters or in depth in a few of the chapters (see Chapters 2, 25, and 27). For an exposition of anatomy of those key areas such as the vertebral artery, the reader is directed to those sections.

Embryologically, the occipital bone takes its origin in the most rostral three or four sclerotomes that form on the ventromedial surface of the primitive notochord (1,2). They fuse cranially with the chondrocranial anlage to the basiocciput to form the occipital bone (Fig. 1). The spinal sclerotomes that will become the provertebrae have a relatively loose cellular dorsal half and a more dense ventral half. The clear dorsal half of one spinal sclerotome fuses with the adjacent ventral half to form a provertebra. An intervertebral disk, which forms from a primordium called the intervertebral fissure, develops between each pair.

The atlas does not develop according to this schema followed by the other provertebrae. The dense caudal half of the first spinal sclerotome unites with the clear half of that adjacent to it, but the clear cranial half of the proatlantal sclerotome remains attached. Because the atlas does not form a body, the embryologic tissue otherwise destined to form it is the primordium of the dens. The dens then fuses with its base in the body of the axis. The tip of the odontoid process is thought to take origin in the clear cranial half of the proatlantal sclerotome. An early ossification site at the odontoid tip occurs that occasionally fails to fuse with the rest of the dens and is called the "ossiculum terminale." (3) This may be mistaken in some patients for a fracture. The final developmental quirk of the atlas that distinguishes it from the rest of the spine is that a portion of the anterior arch of this bone appears to develop from a condensation of sclerotomal mesenchyme ventral to it that is mostly destined to form the hypochondrial bow (4).

The Atlas

From this complex and confusing origin, the first cervical vertebra that supports the head and articulates with it through the occipital condyles takes its formation. Figure 2 illustrates the salient anatomic features of the atlas. Unlike the other cervical vertebrae, the atlas is essentially an osseous ring with a posterior tubercle on the dorsal part of the arch that corresponds to the spinous process of the vertebrae below it. The lack of this process permits free movement of the cranium on the spine. The dorsal superior part of this arch provides a groove for the attachment of the posterior atlantooccipital membrane. The inferior aspect has a groove for the posterior atlantoaxial membrane. The atlas does not possess a vertebral body, and the main bulk of the vertebra is made up by the lateral masses. The concave superior condylar facets articulate with the convexly shaped occipital condyles above and bear the weight of the cranium. The inferior facets of the lateral mass articulate with the axis. Projecting laterally from the lateral masses are the transverse processes, which have a foramen transversarium through which passes the vertebral artery. The artery curls around behind the lateral mass in a groove on the superior surface of the atlas, and then curves in a medial and upward direction to gain entry into the skull (see Chapter 27). The dorsal ramus of the first spinal nerve (the lesser occipital nerve) passes through this same groove with the artery.

The anterior arch of the atlas is relatively short, comprising only one fifth of its circumference. The anterior face of the arch has a tubercle to which the longus colli muscles are attached. The inner surface has a smooth articular facet for the dens, and posteriorly the attachment for the transverse at-

P. J. Donald: Department of Otolaryngology—Head and Neck Surgery, and Center for Skull Base Surgery, University of California, Davis Medical Center, Sacramento, California 95817.



FIG. 1. Embryologic development of the craniocervical junction according to List. The occipital bone and condyles are seen from below. The axis and atlas are seen from above. (From ref. 4, with permission.)

lantal ligament that runs around the posterior surface of the dens. The anterior superior surface of the anterior arch has an attachment for the atlantooccipital membrane and inferiorly the insertion of the atlantoaxial ligament.

The Axis

The axis forms the pivot or swivel point of the head and atlas onto the spine (Fig. 3). The odontoid process is a substantial peglike process projecting superiorly from the body at the apex to accept the apical dental ligament. A smooth facet anteriorly articulates with a corresponding facet on the posterior surface of the anterior arch of the atlas. A shallow groove on the posterior surface accommodates the transverse ligament of the atlas. Rough surfaces on the lateral aspects are for attachment of the alar ligaments. The dens projects from the vertebral body, which has a curious inferior dip that overlaps the body of the third cervical vertebra and provides a further attachment for the longus colli muscle. The laminae, transverse processes, and pedicles are thick and strong. The superior facets are directed more horizontally and the inferior facets directed in the same oblique direction as the rest of the cervical vertebrae.

The Craniocervical Junction

The bony articulation of the occiput-atlas and axis has been already alluded to. The ligamentous attachments are multiple and complex, providing strength and flexibility to this complex. The atlantooccipital capsular ligaments that surround the condylar attachments are thin and loose. Anteriorly, the anterior atlantooccipital ligament connects the anterior aspect of the occipital bone at the foramen magnum with the cranial aspect of the anterior arch of the atlas (Fig. 4A). A thickening of the ligament connects the anterior tubercle of the atlas to the occiput above. Two lateral atlantooccipital ligaments connect the transverse processes to the occiput above. These strong ligaments reinforce the weaker capsular ligaments

On the posterior surface (see Fig. 4B), a much thinner, broad, flat posterior atlantooccipital ligament forms an attachment between the cranial surface of the posterior arch of the atlas and occiput above. There are dehiscences bilaterally to admit the vertebral arteries. The inner surface of the posterior ligament is in intimate contact with the spinal cord dura.

The ligaments on the anterior aspect of the atlas are much more complex (see Fig. 4C). Directly opposite the chordal dura anteriorly is the tectorial membrane, which is the superior extension of the posterior longitudinal ligament of the spinal canal inferiorly. Although adherent to the posterior surface of the vertebral body of the axis, it is free over the transverse ligament of the atlas and broadens as it ascends into the intracranial surface of the occipital bone just inside the foramen magnum. It is inserted into the bone and blends with the dura of this aspect of the cranial base. Anterior to the tectorial membrane is the transverse ligament, which overlies the dens. It has two lateral components that connect one tubercle of the anterior atlas at one extremity of the anterior arch of the atlas to its fellow on the opposite side. A central slip of the ligament extends superiorly to the lip of the foramen magnum and is intimately associated with the tectorial membrane. An inferior slip descends and inserts on the axis. Together, these ligaments form a continuous cross-shaped configuration. Laterally, the dens is connected to the inner surfaces of the occipital condyles by the thick, tough alar ligaments that take the form of check ligaments, preventing overrotation of the head and atlas around the atlantoaxial axis. The alar ligaments blend laterally with the anterior atlantooccipital ligament.

The atlas and axis are bound together by the anterior atlantoaxial membrane, which is a continuation of the anterior longitudinal ligament of the spine. It is thick and strong, and further reinforced by a central ligamentous thickening that connects the anterior tubercles of the atlas and axis and continues on to the undersurface of the occiput. In contrast, the posterior atlantoaxial membrane, which connects the laminae of C2 to the arch of C1, is somewhat thinner and more loosely constructed. It is the superior substitute of the ligamentum flavum.

The final ligament stabilizing the cervical spine and indirectly the craniocervical junction is the ligamentum nuchae. It connects the external occipital protuberance to the atlas and the spinous processes of the cervical vertebrae all the way to C7. It divides the posterior cervical muscles in the midline and is a midline source of attachment of the trapezius muscle.

The rectus capitis minor originates on the occiput and inserts into the posterior tubercle of the atlas. From a similar

Text continues on page 513


Atlas
From above
Anterior tubercle
Dens fossa
Transverse ligament insertion
Transverse process
Articular facet
Foramen transversarium
Posterior tubercle
From below
B

FIG. 2. **A:** The atlas from above. **B:** The atlas from below.


Dens
Axis
From above
Articular facet
Posterior spine
A
From below
B
Atlas
Axis
C3
C

FIG. 3. **A:** The axis from above. **B:** The axis from below. ***C:*** *C1, C2, and C3 articulated from the side.*


Anterior atlanto-occipital ligament
Vertebral artery
Capsules

A


Atlanto-occipital membrane
Capsules
Atlanto-axial ligament
— Vertebral artery
Ligamentum flavum

B


Tectorial membrane
Posterior longitudinal ligament
Posterior view

C


Apical odontoid ligament
Upper limb of cruciate ligament
Apical odontoid ligament
Transverse limb of cruciate ligament
Lower limb of cruciate ligament
D
Tectorial membrane
Superficial tectorial membrane
Upper limb of cruciate ligament
Apical ligament
Transverse limb of cruciate ligament
Lower limb of cruciate ligament
Posterior longitudinal ligament
E

FIG. 4. A: Anterior view of the craniocervical junction. B: Posterior view of the craniocervical junction. C: Posterior view of the craniocervical junction with the laminae and spinal cord removed, showing tectorial membrane. D: Same view with tectorial membrane removed. E: Craniocervical junction from three-quarter view.



FIG. 5. Midas Rex TAG attachment. This is an innovative instrument that enables a deep dissection in confined exposures, permitting easy bone removal in the transoropharyngeal approach to the clivus. A: Photograph of instrument showing curved shaft. B: Close-up view.



FIG. 6. The Crockard instrument set. A: Mouth gag. B: Mouth gag blades and self-retaining retractors.



FIG. 6. *Continued.* C: Crockard self-retaining retractors and mouth gag articulated. D: Dingman mouth gag and Crockard retractors in a patient.

origin, the rectus capitis major inserts into the spinous process of the axis, as does the inferior oblique muscle. The superior oblique inserts into the transverse process of C2. The overlying posterior cervical muscles further stabilize the spine.

The upper cervical spine, especially the region of C1 and C2 and the lower clivus, occupies an anatomically central position, and by virtue of this location is difficult to access through most approaches. The oral cavity and oropharynx provide the most direct route to this otherwise surgically obscure area. The lesions requiring resection or structures needing correction are only 1 to 2 cm from the epithelial incision used to gain the exposure. Concern regarding oral contamination of the wound, especially if dura is exposed, is usually unfounded, especially in the face of vigorous antisepsis in the mouth and systemic coverage with antibiotics. One of the major impediments to effective surgery in this area has been the lack of appropriate surgical instrumentation. With an increasing interest in skull base surgery, more instruments are being developed to facilitate an easier and more effective dissection. Especially important has been the introduction of the Midas Rex drill, and in particular the TAC attachment (Fig. 5). The curved carrier tube protects the soft tissues from the rotating shaft that carries the small match-head cutting bur. The high speed of the bur reduces chatter and shortens dissecting time. The curve of the shaft removes it as a visual obstruction and permits a clear view of the bur at all times. The Crockard instrument set has a unique series of self-retaining retractors that produce maximal exposure in this restricted area (Fig. 6). The Raveh dissecting instruments are both long and strong, and allow the operator's hand to be outside the mouth while the working end can be constantly seen, even while working in the depths of the resection cavity (Fig. 7). The Cob elevator used in orthopedic surgery is sturdy and very effective in elevating the periosteum from the clivus and cervical bodies, An adaptation by the author allows the hand to be removed from the line of sight (Fig. 8).



FIG. 7. Raveh skull base dissectors.



FIG. 8. Cob clival periosteal elevator.

PATHOLOGY

A wide diversity of lesions afflict this area and include congenital anomalies, trauma, benign and malignant tumors, inflammatory conditions, and those of uncertain etiology. Their common denominator is the production of cord compression or spinal instability.

Congenital

Congenital anomalies include basilar impression syndrome, odontoid malformations, and a group of cranial anomalies of the posterior skull base. Their common denominator is the resultant brainstem and upper cord compression. Basilar impression, although uncommon, is one of the more usual indications for odontectomy. This may also need to be combined with a craniectomy to provide adequate brainstem decompression. Basilar impression is the "pushing up" or invagination of the normally convex occipital bone by the upper cervical spine. This results in an impingement of the odontoid onto the undersurface of the brainstem as well as an infolding of the occipital bone, adding further compression to this structure (Fig. 9). This lesion can either be congenital or acquired. A number of congenital syndromes, albeit often very rare, carry with them the problem of basilar impression. Hajdu-Cheney syndrome or acroosteolysis combines dolichocephaly, an unusual protuberance of the squamous part of the occipital bone (bathrocephaly), and progressive basilar invagination with characteristic unusual facies and extremity abnormalities (4), including dissolution of the terminal phalanges. Cloverleaf skull or Klieblattschadel is another rare genetic syndrome in which thanatophoric dwarfism and multiple extremity anomalies are combined with a bizarre trilobed skull (5). These anomalies of the calvarium, with petrous tips that are level with the floor of a posterior cranial fossa markedly reduced in height, are coupled with basilar impression. Sjogren-Larsson syndrome and pyknodysostosis are further rare syndromes that may be associated with basilar impression; the latter disorder was the putative affliction of the famous Impressionist Toulouse-Lautrec (6). Achondroplastic dwarfism has a number of associated cranial anomalies, one of which may be basilar impression.



FIG. 9. Lateral radiograph of basilar impression syndrome. Note prior craniectomy. Odontoid is anterior to the craniectomy and is compressing the brainstem through a crumbling clivus. *Arrows* indicate site of odontoid.

Acquired disorders of the cranial bones such as osteomalacia, osteogenesis imperfecta, cretinism, and rickets cause bone softening. This produces a malleability of the bone that may lead to progressive invagination of the occiput as the weight of the cranium and its contents impinges on the upper cervical spine (7). Gardner contends that all basilar impression is acquired in that all the congenital syndromes are without basilar impression until the weight of the head begins to be imposed on the cervical spine as the person assumes the upright position (8).

Congenital anomalies of the odontoid are associated with a number of disorders, including Morquio's syndrome (mucopolysaccharidosis type IVB), Aarskog's syndrome, Dyggve-Melchior-Clausen syndrome, pseudoachondroplasia. cartilage-hair hypoplasia, congenital spondyloepiphysial dysplasia, and spondylometaphysial dysplasia (9). Morquio's syndrome has multiple spinal anomalies including severe kyphoscoliosis and shortened cervical vertebrae. The odontoid may be hypoplastic, absent, or anomalously formed, causing upper cord compression. In Aarskog's syndrome (facial-digital-genital syndrome), the posterior arch of C1 may be unfused and ascend with the articulated odontoid into the foramen magnum on cranial extension. Dyggve-Melchior-Clausen syndrome is also associated with dwarfism. There is instability of the atlantoaxial joint that can lead to cord compression. Although the appearance of these patients resembles that of Morquio's syndrome, they have no mucopolysacchariduria or corneal clouding, but have microcephaly and mental retardation. Although the remaining disorders mentioned previously may be accompanied by odontoid malformations, the dens is usually hypoplastic in nature and predisposes the patient more to instability than impingement of this structure against the brainstem.

Traumatic

The traumatic lesion most commonly requiring this exposure is the odontoid fracture, but it is rarely seen. This is an uncommon injury and may also be seen as part of a "hangman's fracture," a fracture-dislocation of C2 on C3. If the dens is fractured, the craniocervical junction may be destabilized and the cord acutely compressed. These fractures are most often the result of automobile accidents in the young



FIG. 10. Three types of odontoid fracture.

and falls in the elderly, and may be asymptomatic or present with cord compression.

There are three types of odontoid fractures (10) (Fig. 10). Type I is a fracture of the odontoid tip and may be confused with the congenital anomaly of os odontoideum. The anomaly is differentiated by its characteristic radiographic appearance of a diamond-shaped image with smooth sides (Fig. 11). The fracture looks like a normal tip with a separating line between it and the remainder of the dens. Type II fractures are those that go through the base of the process, and the mechanism of fracture commonly places the dens anteriorly onto the body of C2. The type III fracture goes through the odontoid and enters the marrow space of the body of C2. These fractures usually stabilize and are treated only with analgesics and immobilization. When combined with a C2-3 fracture-dislocation, the type III fracture is very unstable and difficult to treat (11,12).

If the odontoid fractures are displaced, they are slightly more commonly flexion in type with displacement of the tip anteriorly. Occasionally, a posterior fracture occurs with the head forced back against the upper end of the spine, which may result in instant death from respiratory arrest. When force is applied anteriorly, a fracture of the atlantal ring may in turn fracture the odontoid posteriorly. Force from behind can fracture the odontoid by the sudden impaction transferred by the transverse atlantal ligament. The eventual position of the odontoid may be related more to the subsequent motion of the patient's head after the fracture rather than to the mechanism of injury. In addition, degrees of displacement may be entirely unrelated to spinal stability. Neurologic symptoms are less likely to develop with anterior displacements than with those that occur in a posterior direction (11,13,14) (Table 1). In Dunn and Seljeskog's (13) series of 110 odontoid fractures, only 20% of patients with no subluxation had neurologic deficits.



FIG. 11. Lateral computed tomography scan of os odontoideum. *Arrows* indicate separate ossification site at tip of dens.

Most odontoid fractures are reduced by traction and immobilization. Only selected, symptomatic fractures in which the odontoid remains displaced require resection. Type I fractures usually require collar immobilization or simply analgesics. In Dunn and Seljeskog's (13) series, 14 patients were treated with open reduction and internal fixation and 80 patients with external fixation. No patients with a type III injury had a nonunion. A nonunion occurred in 70% of posterior dislocations of the type II variety. A similar experience was noted by Altholl and Bardholm (15). Of the 48 fractures with a nonunion, 41 had successful bone healing. It appears from the literature that the posterior dislocations do better with an open operation. The transoral approach for upper

TABLE 1. *Facial subluxation related to neurologic deficit (110 patients)*

Neurologic deficit	No. of patients	with subluxation fractures	of odontoid
	None	Anterior	Posterior
Present Absent Total	5 33 38	5 37 42	15 15 30

From ref. 10, with permission.



FIG. 12. Arthritic pannus compressing upper cervical cord.

cord or brainstem compression is reserved for those cases in which the dens does not relocate after traction or a posterior approach for relocation and fusion.

Inflammatory

The principal inflammatory condition of concern here is the pannus, secondary to rheumatoid arthritis. Unfortunately, many of these patients have been severely debilitated by the systemic effects of this disorder. Peripheral joints are commonly badly afflicted before upper cervical cord symptoms become manifest. The pannus is an infiltration of a vascular granulation tissue, chronic inflammatory cells, and fibroblasts that covers the joint surfaces. The pannus produces cytokines (granulocyte-macrophage colony-stimulating factor) and tumor necrosis factor-a that result in the stimulation of polymorphonuclear leukocytes and dissolution of articular cartilage. In peripheral joints, this process is seen as an irregular, deforming bulge of the skin overlying the affected joint. The joints have a tendency to sublux, and fibrosis causes joint fusion. At the top of the cervical spine, the pannus may produce an atlantoaxial subluxation and compression of the upper cervical spinal cord by pushing the transverse ligament against the dura, thus indenting the cord (Fig. 12). In addition, joint degeneration and migration of the odontoid superior form a type of acquired basilar impression (Fig. 13).

Neoplastic

A variety of tumors can begin in the craniocervical junction. They may be either benign or malignant, and the malignancies may be either primary or secondary (Fig. 14). The importance of a biopsy cannot be overstressed because of the frequency of uncommon and rare lesions at this site. Sufficient tissue must be harvested to perform electron microscopy and special stains. The most common epithelial lesion is squamous cell carcinoma, and the most common bony lesion, although uncommon in general, is chordoma. Squamous cell carcinomas are usually of nasopharyngeal or oropharyngeal origin. Fortunately, the stout pharyngobasilar fascia provides a formidable barrier to tumor penetration Tumors of nasopharyngeal origin have more of a propensin



FIG. 13. A: Lateral radiograph of elderly woman showing migration of the upper cervical spine with sub-luxation at C1 and C2. B: Lateral magnetic resonance image showing upper cord compression.



FIG. 14. Axial computed tomography scan showing prostate carcinoma metastatic to the clivus.

to invade clival bone than those of the oropharynx do the cervical spine (Figs. 15, 16). Squamous tumors extend laterally along the eustachian tube or under the skull base, which may carry them out of reach of the transoropharyngeal approach. Squamous cell carcinomas primary to the posterior wall of the oropharynx are rarely amenable to this approach because; complete tumor resection with adequate margins is difficult to impossible unless the lesion is very small.



FIG. 15. Coronal magnetic resonance image of nasopharyn-geal carcinoma with invasion of clival bone and extension into cavernous sinus.



FIG. 16. Coronal magnetic resonance image showing extension of a carcinoma of the nasopharynx through foramen lace rum.

Chordoma is an enigmatic lesion thought to originate in primitive notochordal remnants and characterized histologically by a fat-filled, foamy-appearing cell described as a "physaliferous cell" (Fig. 17) (see also Chapter 3). In the skull base, this tumor uncommonly metastasizes, (In a review by Chambers and Schwinn [16]. 30% of chordomas metastasized within 3 to 4 years of diagnosis, but only 7% of these primaries originated in the skull base,) In behavior, they are a sort of transition-type tumor, similar to the ameloblastoma of the jaws and inverting papilloma of the nose and paranasal sinuses. Radiographic examination reveals a soft tissue density replacing clival bone with occa-



FIG. 17. Chordoma of clivus demonstrating the characteristic physaliferous cell. (Hematoxylin and eosin; original magnification 400x).



FIG. 18. Lateral magnetic resonance image showing extensive clival chordoma from the posterior clinoid processes to C2, with brainstem compression.



FIG. 20. Axial computed tomography scan showing fibrous dysplasia of clivus *(arrows).*

sional focal areas of calcification, although not as commonly seen at this site as in those tumors involving the vertebrae (Fig. 18). If the tumor is completely resected with a narrow margin of uninvolved tissue, it will not recur. The problem with clival and C1 chordoma is the difficulty of adequate exposure and access to effect total tumor removal. The tumor freely erodes bone, may invade adjacent soft tissue, and may become attached to dura. Transdural spread is most often the result of prior surgery with breaching of the dura and incomplete removal. The tumor is slow growing and relatively resistant to radiation therapy. In contrast to squamous cell carcinoma and most other epithelial neoplasms, which are white and hard, chordomas are gray and soft. Neither type is encapsulated, and both readily invade adjacent tissue.

A biologic behavior similar to that of chordoma is seen ir chondroma and chondrosarcoma. In these tumors of cart: laginous origin, the malignant variety is far more commc



FIG. 19. Magnetic resonance images of elderly man with chondrosarcoma of clivus. A: Axial view. B: Coronal view.

than the benign. Grossly, the tumor is firm to hard, white, tan, or grayish-blue and usually seen under an intact mucosa. Radiographically, they present a variable picture of radiolucency, radiodensity, and focal calcification. Local irregular bone destruction is obvious (Fig. 19). Histologically, the chondroma resembles normal cartilage but may be more cellular, although the cells have a normal configuration. There may be foci of ossification, thereby qualifying them as osteochondromas. The chondrosarcomas are highly cellular, and these cells are irregular, pleomorphic, with hyperchromatic and occasional multiple nuclei, but with infrequent appearance of mitotic figures (17). Histologically, the lesion is sometimes difficult to differentiate from a chondroid chordoma. They rarely metastasize and are radioinsensitive.

Secondary malignancies such as those originating in the prostate or kidney or from cutaneous melanoma may show up as a lytic lesion in the clivus. A computed tomography (CT) scan of the head and neck stimulated by the patient's complaint of occipital or posterior neck pain may reveal such a finding as the only initial manifestation of an otherwise occult primary malignancy. The importance of biopsy is paramount (see Chapter 3). Meningiomas can invade the clivus from the cranial side and can have significant osseous involvement. Neurologic symptoms occur as the tumor compresses the brainstem or migrates through the foramen magnum (18). A number of other disparate lesions may present as clival masses. Fibrous dysplasia (Fig. 20) and nonspecific inflammation resembling the Tolosa-Hunt syndrome (Fig. 21) may present with clival erosions as their primary objective findings.



FIG. 21. Computed tomography scan of Tolosa-Hunt syndrome showing invasion of clivus extending into the cavernous sinus.

CLINICAL PRESENTATION

Lesions in the clivus may be purely incidental findings on a CT scan or routine head film, with little or no clinical manifestations. Odontoid lesions and disease of the atlantooccipital or atlantoaxial axis are usually symptomatic.

Clival lesions may simply present as a history of posterior cervical pain or occipital cephalgia. One patient in the author's experience presented with a 5-year history of postauricular pain over the mastoid process (Fig. 22). Encroachment on the hypoglossal canal may produce paresis or paralysis of cranial nerve XII, resulting in slurred speech and oral dysphagia. These symptoms often tend to be transient because the patient usually rapidly accommodates to unilateral lingual paralysis. Further expansion into the skull base laterally produces the jugular foramen syndrome with compromise of cranial nerves IX, X, and XL This well known constellation of symptoms, consisting of shoulder weakness secondary to sternocleidomastoid and trapezius paralysis, and hoarseness, aspiration, and pharyngeal dysphagia resulting from vagal paralysis, with the dysphagia additionally aggravated by glossopharyngeal paralysis, can be severely debilitating. The presence of a nasopharyngeal mass may cause nasal obstruction and eustachian tube dysfunction, the latter producing a middle ear effusion. The second most common symptom after a mass in the neck in the manifestations of nasopharyngeal carcinoma is a conductive hearing loss sec-



FIG. 22. Computed tomography scan of elderly woman with erosive lesion of clivus producing postauricular pain (see text). Biopsy revealed clival chordoma.



FIG. 23. Magnetic resonance images of massive prolactinoma in a late middle-aged man. He presented with massive epistaxis, visual disturbance, and semicoma. These symptoms were preceded by months of nasal obstruction. A: Axial view. B: Coronal view.

ondary to this effusion. If a nasopharyngeal mass is of clival origin, alteration of the mucosa is very uncommon and bleeding rarely a presenting symptom. Mucosal malignancies such as nasopharyngeal carcinoma are commonly ulcerative, and bleeding, although rarely massive, is a frequent symptom. Lesions such as large pituitary tumors (Fig. 2. and nasopharyngeal angiofibromas (Fig. 24), although no originating in the clivus, may spread to it, causing erosion and presenting not only with nasal obstruction but massive. life-threatening epistaxis. Posterior extension of clival tu-



FIG. 24. A: Preoperative photograph of 13-year-old with nasal obstruction, epistaxis, proptosis, and bulging in left cheek secondary to a massive angiofibroma. B: Magnetic resonance image showing tumor invading middle cranial fossa and cavernous sinus.



FIG. 25. McGregor's line *(solid line)* compared with Chamberlain's line *(dotted line).*

mors may cause brainstem compression. Early symptoms may be simply suboccipital pain and vague dysesthesia in the arms. The syndrome is often initially misdiagnosed as degenerative disease of the spine (18). Upper extremity weakness and gait disturbance may occur, as well as cranial nerve XI palsy, as lower clival compression progresses. In the upper and middle clivus, cranial nerve VI disturbance, vertigo, ataxia, syncopal episodes, and even hydrocephalus may develop.

Basilar impression syndrome produces brainstem compression and may result in the cerebromedullary syndrome with ataxia, vertigo, oscillopsia, and vertical nystagmus. Lower cranial nerve involvement may also be present (3,19,20).

Pressure against the pons can produce sudden cardiorespiratory arrest. One patient in the author's experience (21) experienced repeated cardiorespiratory arrests requiring cardiopulmonary resuscitation, finally relieved temporarily by traction using Crutchfield tongs and permanently by odontectomy and spinal fusion (see Fig. 9). Compression in the atlantoaxial area can result in lower limb paralysis, upper limb paresthesia, weakness, and complete tetraparesis.

Radiographic evaluation can provide useful information in the diagnosis and estimate of severity of basilar impression syndrome. A lateral skull CT or plain film can portray the position of the odontoid tip relative to the skull base. Chamberlain's line (22) connects the dorsal lip of the foramen magnum to the posterior termination of the hard palate (Fig. 25). The tip of the odontoid process should be below that line. Because the dorsal lip may be difficult to visualize, McGregor (23) defined another line that connects a point at the inferior convexity of the occiput to the distal tip of the hard palate. McGregor calculated that the odontoid should project no more than 4 to 5 mm above this line (see Fig. 25). Fischgold's line is also a useful measurement (24). This is produced on a posteroanterior film. The mastoid tip of one side is connected to that of the opposite side, and the line thus produced should pass through the atlantooccipital joint and the tip of the dens (Fig. 26, dotted line). Metzger's line connects each digastric groove, and if the condyles or dens reach this point, this is a definite sign of basilar impression (24) (see Fig. 26, solid line.) Current magnetic resonance imaging technology has rendered these measurements less important than formerly in that soft tissue compression can be so precisely displayed. It is important at this juncture to clarify the distinction between platybasia (a term used often in the past as a synonym for basilar invagination) and the often separate entity of basilar impression. "Platybasia" refers to an obtuse angle between the floor of the anterior cranial fossa and the midplane of the clivus. The Boogard and Me Rae angles describe this abnormality (Fig. 27). The Boogaard angle (25) is at the point that connects the standard cephalo-metric line S-N with a line passing from point S to the cranial portion of the distal tip of the clivus (normal = 120-140 degrees). The McRae (26) angle is similar and is at the point that connects a line that runs along the anterior cranial fossa floor from the point N to the tip of the anterior clinoid process and a line from the tip of the anterior clinoid to the upper surface of the distal clival tip (normal = 118-147 degrees). An increase above normal limits indicates platybasia, but, as previously mentioned, not necessarily basilar impression.



FIG. 26. Fischgold's line *(dotted line)* and Metzger's line *(solid line).*

Odontoid fractures, especially with posterior dislocation, can result in a cardiorespiratory arrest and sudden death (7,13). Severe posterior neck pain made much worse with coughing or stooping, upper limb paresthesia and weakness, lower extremity weakness or paralysis, or complete tetraparesis may result.

OPERATIVE TECHNIQUE

Preparation

The patient is operated on in the supine position. A C-arm fluoroscope should be put into position before the start of the surgical sterile preparation of the patient. The apparatus is at times a cumbersome nuisance but provides immediate information regarding surgical orientation. The fluoroscope is not essential in all cases, and spot films can be taken instead with a mobile machine during the course of the procedure. Spinal cord monitoring is wise during the procedure, especially when any spinal or atlantooccipital instability is anticipated.

Head position during the conduct of the operation is extremely important, as is the maintenance of its stability. Unlike many of the interdisciplinary procedures involving head and neck surgery and neurosurgery, in which stabilizing cranial pins are avoided to permit free movement of the head necessary for optimal visualization during the subcranial portion of the surgery, these operations need fixation. The head is manipulated into the surgically most advantageous position while the electrical activity of the spinal cord is carefully monitored. For the transoropharyngeal approach, the best position is with as much head extension as possible.

Before surgery, the extent of jaw opening is assessed, as is the size of the oral cavity and the oropharyngeal isthmus. In patients with rheumatoid arthritis, involvement of the temporomandibular joint with disease is not uncommon. Restriction of jaw motion may require surgical mobilization of the joint (21) or an approach using a median labial mandibuloglossoptomy (Fig. 28).

A tracheostomy is often done, for a number of reasons. With elimination of the endotracheal tube from the oral cavity, more room can be obtained and the pervasive concern regarding tube compression can be avoided. The tube also acts as a source of bacterial contamination because it is rarely inserted under sterile technique. The presence of the tube also adds to the pressure on the tongue already created by the blade of the mouth gag, leading to the possibility of increased postoperative lingual swelling. Most important, postoperative tongue edema with airway compromise and the necessity for sputum expectoration after coughing in the face of the pharyngeal closure are the major postoperative reasons for tracheostomy. Often the patient is stabilized in a halo brace. These patients not uncommonly have both dysphagia and aspiration. Airway protection in the early postoperative days is afforded by the tracheostomy.



FIG. 27. Boogard line *(solid line)* and McRae line *(dotted line).*

Eye protection is best served by the use of Frost stitches (see Chapter 10). Corneal shields are adequate for short cases, but for a procedure going beyond 3 or 4 hours, these sutures will prevent any corneal irritation that may result from prolonged use of the shields.

A lumbar subarachnoid drain is placed, as in most skull base cases, at any time when dural resection is anticipated. Many of the transoropharyngeal procedures are done extradurally because the lesion is one of bone and adjacent muscle and mucosa. If a dural resection is anticipated, intraoperative cerebrospinal fluid (CSF) drainage, usually extended 2 to 3 days after surgery, is routine.

The surgical sterile preparation includes the head and neck and any anticipated donor sites, such as the thigh for a fascia lata graft and the abdomen for fat grafting. The patient is encouraged to brush his or her teeth vigorously for some days in anticipation of the surgery. Obviously, all grossly infected teeth or gums must be remediated before surgery. Povidone-iodine-soaked sponges are placed in the mouth at the time of the sterile preparation.

Operative Procedure

In most cases, excellent exposure is obtained through the oral cavity. The Crockard or Dingman mouth gag is placed to retract the tongue and cheeks and prop open the mouth. Care is taken to protect the tongue tip from compression against the teeth. After the gag has been in place for 5 minutes or so, maximal jaw opening can be achieved with a couple of additional opening "clicks" of the gag as relaxation and stretching of the perioral tissues and jaw musculature proceeds.

Injection of the posterior pharyngeal wall, the soft palate, and the hard palate is done with 0.5% lidocaine in 1/100,000 or 1/200,000 epinephrine. The hard palate injection is done only if superior extension is required. The initial injection is in the proposed incision line, and a further infusion is made over the areas of planned soft tissue elevation. The incisions



FIG. 29. Outline of soft and hard palate incisions.

through the superior constrictor muscle to the alar fascia. The incision is made as far lateral in the pharynx as possible, just medial to the posterior pillar of the tonsil, and extends from the nasopharynx to the level of the tip of the epiglottis. Care is taken to avoid accidental incision of the ascending pharyngeal artery. The alar fascia is identified as a glistening, white, fibrous layer on the outer aspect of the constrictor muscle, yet anterior to the cervical prevertebral fascia. In the oropharynx, the muscle is clearly and easily identifiable and the alar fascia is obvious. In the nasopharynx, the muscle becomes tendinous and inserts into the pharyngeal tubercles of the clivus. The right-angled scissors dissect the muscle layer from the incision to the opposite lateral pharyngeal wall (Fig. 31). Hemostasis is ensured with the suction cautery. Once the wound is dry, a parallel incision is created on the opposite side and of the same length as its fellow. Hemostasis is again established. The two incisions are connected superiorly, with this incision placed in such a fashion that closure near the nasopharynx can easily be effected at the end of the operation. This incision is usually located just behind the choanae. Sharp dissection connects the free retropharyngeal plane into the nasopharynx to create an in-feriorly based posterior pharyngeal flap, as first described for this operation by Crumley and Gutin (27). The flap is dissected inferiorly, folded on itself, and temporarily tamped into the hypopharynx. The author has found that the flap can be secured in this position throughout the remainder of the procedure by placing a suture at each corner of the flap superiorly, running the suture through a small square of lead, and stuffing the lead into the hypopharynx (Fig. 32).

A drill is now used to remove enough palatal bone to achieve the required exposure of the upper clivus. This exposure may extend as far anteriorly as the cribriform plate, if so desired. The nasal mucoperiosteum of the posterior nasal floor is rather delicate and difficult to preserve; however, the septal mucoperiosteum over the vomer is much tougher. Once sufficient palate is removed, the inferior aspect of the



FIG. 30. Palatal incisions made and greater palatine neu-rovascular bundle ligated.



FIG. 31. A: Crockard self-retaining retractor inserted. Inferior-based pharyngeal flap on posterior pharyngeal wall outlined. B: Lateral incision made with superior pharingeal wall outlined. B: Lateral incision made with superior pharyngeal constrictor in the plane of the alar fascia.

продолжение

продолжение



FIG. 32. The pharyngeal flap has sutures with small squares of lead placed on its distal end, then stuffed into the hypopharynx to stabilize the flap during subsequent dissection.

nasal septum becomes obvious. It is split on the choanal side right up to the sphenoid rostrum, and dissection of the septal mucoperiosteal leaves is carried up this high and the posterior septal bone removed (Fig. 33). The Crockard palatal retractor is now inserted.

The midline posterior septal incision becomes continuous with a midline incision through the tough, tendinous tissue over the clivus and the prevertebral fascia and muscles of the upper cervical spine. The heavy elevator is now used to dissect this soft tissue over the clivus and upper two or three cervical vertebrae (Fig. 34). The Crockard retractor is reapplied and the soft tissue held in place, exposing the site of proposed bony resection or tumor.



FIG. 33. The palate is drilled away to an amount sufficient to provide adequate exposure of the clival involvement by tumor. The posterior septum is removed to expose the sphenoid contribution to the clivus.



FIG. 34. The heavy elevator is used to dissect the tough soft tissues off the clivus and cervical spine. The Crockard retractor is then reapplied to give enhanced exposure of the tumor and surrounding bone.

If such exigencies as a very small oropharynx, severe trismus, or severe microgenia and retrognathia are present, or if exposure to the C4 to C6 level is also required, additional exposure may be gained by using the median labial niandibuloglossoptomy originally described by Trotter (28-30). A skin incision through the middle of the lip, using a dart in the vermilion descending vertically to the chin button, circling the chin and into the submental area, is created (see Fig. 28A). The mandible is exposed in the midline and a stairstep incision is etched in the symphysis. Drill holes for two parallel plates are placed to secure the bone at the end of the case (see Fig. 28B). Care is taken that the uppermost plate screw holes are below the roots of the incisor teeth, which are generally double the crown length of the tooth. A saw cut begins between the central incisor teeth either with a fine saw blade or the Midas Rex B5 cutting tool, assiduously avoiding the lamina dura of either tooth. Once the saw cut has bisected the mandible, the anterior floor of the mouth tissues is cut in the midline and the tongue is split down the midline raphe to the hyoid bone. With improved exposure inferiorly, the pharyngeal flap can be dissected to the postcricoid area, providing the improved access desired. At the end of the resection, the mandible is secured by two plates (see Fig. 31C). This exposure is rarely needed.

Once the paraspinous tissues have been retracted, drilling of clival and spinal bone may ensue to expose or provide access to tumor or the odontoid. The curved drill of the TAG attachment of the Midas Rex is ideal for this dissection (Fig. 35). Coupled with continuous suction irrigalion, bone removal is fast, efficient, and safe.

Tumor Excision

Most tumors addressed by this approach are chordomas and chondrosarcomas (see Fig. 22). The author has also encountered fibrous dysplasia, nonspecific fibrogranulomatous lesions similar to those of Tolosa-Hunt syndrome (see Fig. 21), and metastatic carcinoma (see Fig. 14).

Often the tumor is present under the periosteum. Additional exposure is gained by progressive resection of bone with the cutting drill. Long dissection instruments developed by Raveh and the author are long enough for this task and remove the hand from obscuring the view. In removing a chor-doma, great care is exercised to avoid penetrating the dura (Fig. 36). Although every attempt is made to remove the entire tumor, local recurrences unfortunately are common and. if intradural, exceedingly difficult to eliminate. Fortunately, the anterior longitudinal ligament provides some barrier to penetration during tumor dissection.

Lateral extension of neoplasm at the skull base toward the hypoglossal canal is a serious impediment to complete excision, and a second staged operation such as a lateral approach may be needed for complete tumor removal. Superior resection can be carried into the sphenoid sinus and up to the sella turcica.

Surgical stabilization of the spine may be necessary for a few weeks after surgery.

Odontectomy

Removal of the dens is done in some cases of fracture, but most commonly for brainstem and upper cervical cord compression from an arthritic pannus (see Fig. 13). It is also done for decompression in basilar impression syndrome (see Fig. 9).

The exposure almost never requires the median labial mandibuloglossoptomy. Removal of palatal bone is minimal or not necessary. Exposure is from the lower clivus to the level of C2. In basilar impression syndrome, cases of other congenital spinal anomalies, and even in rheumatoid arthritis, where collapse of the spinal bodies is not uncommon, landmarks are often difficult to define. Identification of the arch of C1 is sometimes problematic and the frequent use of the fluoroscope is encouraged to register position.

An exposure similar to that described for tumor is done, but usually only a soft palatal split is required, without the necessity of removing hard palatal bone. Once identified, the anterior arch of Cl is removed with the drill (Fig. 37). In basilar impression, the bony distortion is often so great that the lower clivus must be excised before the odontoid can be reached. The occipital clivus in these cases is often crumbly and weak. It and the arch of Cl are removed until the pe-



FIG. 35. The curved Midas Rex TAG attachment is used to remove bone from the clivus and cervical spinous bodies to expose the limits of tumor.



FIG. 36. Tumor is removed completely and great care is taken to avoid injury to the dura.



FIG. 37. A: Diagram of basilar impression. B: The areas of the C1 arch and adjacent clivus to be resected are marked out.



FIG. 38. A: Arch of C1 and adjacent clivus drilled away with cutting bur, exposing deformed dens. B: Dens grasped with Crockard instrument and removed with drill.

riosteum over the odontoid is reached. The odontoid is grasped with the Crockard forceps and the dens drilled away (Fig. 38).

In cases of rheumatoid arthritis, although the dens is often deformed, there is no migration of the spine. The pannus projects against the brainstetn. The Ci arch and only a small portion of the clivus need resection (Fig. 39). Once the ligament is reached, much inflammatory reaction is present and the pannus becomes obvious, requiring sharp dissection (Fig. 40). Excessive vigor in this endeavor may lead to a breach in the transverse ligament and laceration of dura. This must be avoided, if possible, because dura! leaks here are difficult to repair. Checking depth of dissection with the fluoroscope is very helpful.

Closure

Once the resection is finished, any dural disruption is repaired by suturing a fascia graft augmented by fibrin glue. The dead space created by the resection must be obliterated. Surgicel is often placed against the dura and the defect filled with Gelfoam. The defect may be filled with cancellous bone from the hip.



FIG. 39. A: Pannus surrounds deformed dens in a patient with rheumatoid arthritis. B: Area of bone removal outlined.



FIG. 40. A: Midas Rex drill used to excise arch of C1 and small amount of clivus. B: Sharp dissection is needed to remove pannus.



FIG. 41. Paraspinous muscles and connective tissue approximated in midline. *Inset:* Pharyngeal closure. Note bridging sutures in choanal mucoperiosteum.

The paraspinous muscles and connective tissue are approximated in the midline with absorbable sutures (Fig. 41). This closure is not as tidy over the clivus as it is over the cervical spine. The pharyngeal flap is retrieved from the hypopharynx, the lead weight keepers removed, and the flap restored to its original position. Lateral sutures are placed with little difficulty, but the uppermost ones in the transverse incision in the nasopharynx are harder to secure. The nasopharyngeal mucosa is more friable than that of the oropharynx, so that bridging sutures to the mucoperiosteum of the choanal vault may be necessary to anchor the upper portion of the flap.

To avoid fistulization, it is essential to close the soft palate in three layers. The nasopharyngeal side of the palate is closed initially with interrupted absorbable sutures from the posterior nasal septum to the tip of the uvula. The palatal muscle and the oral mucosa are closed with four horizontal mattress sutures in a fashion similar to the closure of a cleft palate. More accurate approximation of the oral mucosa is done with fine suture material (Fig. 42).

The tough mucoperiosteum of the hard palate is secured with a few interrupted sutures. The anteriormost part of the wound is often difficult to close because the tissue is thin and attenuated and the angle makes suturing mechanically difficult. Because the bony resection is designed to come short of the mucosal incision, sufficient overlap of mucoperiosteum prevents fistula formation.

Closure of the median labial mandibuloglossoptomy is relatively simple. The deep tongue musculature is approximated with 3-0 absorbable sutures and the mucosal surface with 4-0 sutures. The mandibular split is repaired with low-profile titanium plates and screws. Skin and mucosal closure are meticulous to avoid deforming scars. It is essential to accurately approximate the white roll of the lower lip because this is the keystone to good aesthetic repair. Interrupted sutures in the skin produce a much better scar than a running closure.

The tracheostomy is maintained after surgery until the pharyngeal and palatal wounds have healed. No pharyngeal diversion is necessary and nasogastric tube feeding is avoided. Oral alimentation can often resume in about 5 days. If complications preclude oral feedings, then a nasogastric tube is placed, taking great care to avoid disruption of the palatal and pharyngeal wounds. If necessary, fiberoptic control can be used.

In most cases, the atlantooccipital junction is unstable and later upper cervical fixation through a posterior approach will be necessary. In the intervening period, the patient's spine is stabilized with halo-type fixation.

COMPLICATIONS

This surgery is more difficult in the elderly than the young. Elderly patients with rheumatoid arthritis of the severity requiring odontectomy are often functioning marginally. They are more prone to complications of aspiration and dysphagia in the early postoperative period, and are slow to recover because of their diminished mobility.



FIG. 42. Closure of soft palate is carefully done in three layers: the nasal mucosa, horizontal mattress sutures in the soft palatal mucosa, and a simple suture in the oral side

Tongue swelling is common immediately after surgery, and resolves spontaneously within a few days. The temptation to use systemic steroids should be suppressed because of the inhibitory effect of these medications on wound healing.

Wound complications include CSF leak, wound infection, and wound breakdown. CSF leakage may stop with lumbar drainage, semi-Fowler's position, and cessation of oral alimentation. If the drainage has not stopped in 3 to 5 days, resuturing of the dura must be done. Wound infection is fortunately very uncommon. Some of the sutures must be released (one of the virtues of placing interrupted sutures at the time of closure) to drain any purulent collection. Appropriate antibiotic therapy is instituted and the patient taken off oral alimentation until the wound is clean and granulating.

Palatal dehiscence is probably the most common complication. If a T-type incision is required for exposure, breakdown at the trifurcation occurs almost 50% of the time. The patient is often distressed at the nasal regurgitation on swallowing and the air escape during speech, creating a denasal quality to the voice. The use of a dental obturator is encouraged and closure of the fistula delayed until wound epithelialization and maturation is completed. This may be as long as *6* to 12 months.

REFERENCES

1. Sperber OH. Craniofacial embryology. In: *The cranial base.* Chicago: Year Book, 1976:78-87.
2. Prader A. Die frubembrymal Entwicklung der menschlichen Zwischenwirbelscheibe. *Acta Anar* 1947:3:68-83.
3. List CF, Neurologic syndromes accompanying developmental anomalies of Ihe occipital bone: atlas and axis. *AMA Archives of Neurology and Psychiatry* 1941;45:577-616.
4. Gorlin RJ, Cohen MM, Lenin LS, eds. *Syndromes of the head and neck.* 3rd ed. New York: Oxford University Press, 1990:258-260.
5. Salmon MA, Lindenbaum RH, eds. *Developmental defects and syndromes.* Exeter, United Kingdom: M&M Publishers, 1978:32-34.
6. Maroteaux P, Lamy M. The malady of Toulouse Lautrec. *JAMA* 1965;191:715-717.
7. Ber,trand G. Anomalies of the craniovertebral junction. In: Youmans JR, ed. *Neurological surgery.* Vol. 3. 2nd ed. Philadelphia: WB Saunders, 1982:1482-1508.
8. Gardner WJ. Anomalies of the craniovertebral junction. In: Youmans JR, ed. *Neurological surgery.* Vol. 1. Philadelphia: WB Saunders. 1973:628-644.
9. Sperber GH. *Craniofacial embryology.* In: The cranial base. Chicago: Year Book, 1976:110-113.
10. Anderson LD, D'Alonzo RT. Fractures of the odontoid process of the axis. *J Bone Joint Surg Am* 1974:56:1663-1674.
11. Clark K. Injuries of the spinal cord. In: Youmans JR, ed. *Neurological surgery.* Vol. 4. 2nd ed. Philadelphia: WB Saunders, 1982:2318-2337.
12. Larson SL. Post traumatic spinal instability. In: Pitts LH, Wagner FC. eds. *Craniospinal trauma.* New York: Thieme Medical Publishers. 1990:159-185.
13. Dunn ME, Seljeskog EL. Experience in the management of odontoid process injuries: an analysis of 128 cases. *Neitrosurgery* 1986; 18: 306-310.
14. Hadley MN, Browner C. Sonntag VKH. Axis fractures: a comprehensive review of management and treatment in 107 cases. *Neurosurgery* 1985:17:281-290.
15. Altholl B, Bardholm P. Fracture of the odontoid process: a clinical and radiographic study. *Acta Orthop Scand Suppl* 19xx;177:61-95.
16. Chambers PW, Schwinn CP. Chordoma: a clinicopathological study of metastasis. *Am J Pathol* 1979;72:765-776.
17. Barnes LB, Pul LR, Verbin RS, Goodman MA, Appel BN. Diseases of the bones and joints. In: Barnes LB, ed. *Surgical pathologv of the head and neck.* Vol. 2. New York: Marcel Dekker, Inc., 1985:957-962.
18. Samii M, Ammirate M. Meningiomas involving the lower clivus and the foramen magnum. In: Samii M, ed. *Surgery of skull base meningiomas.* New York: Springer-Verlag 1992:61-67.
19. Garcin R, Oeconomos D. *Les aspects neurologigues des malformations congenita/es de la charniere cranionachidienne.* Paris: Masson, 1953.
20. Wallin DG. The osodontoideum, separate odontoid process. *J Bone Joint Surg Am* 1963;45:1459-1471.
21. Donald PJ, Bernstein LB. Transpalatal excision of the odontoid process. *Transactions of the American Academy of Ophthalmology and Otolaryngology* 1978;86:729-731.
22. Chamberlain WE. Basilar impression (platybasia). *Yale J Bio! Med* 1939:11:487-^96.
23. McGregor MB. The significance of certain measurements of the skull in the diagnosis of basilar impression. *Br J Radial* 1948;21:171-181.
24. Fischgold H, Metzger J. Etude radiotomographique de 1'impression basilaire. *Rev Rhum* 1952;3:261-264.
25. Boogaard JA. Basilar impression: its causes and consequences. *Ned* 7V-*jdschr Geneeskd* 1865;2:81-108.
26. McRae DL. Bone abnormalities in the origin of the foramen magnum: correlations of the anatomic and neurological findings. *Acta Radial* 1953:40:335-354.
27. Crumley RL, Gutin PH. Surgical access for clivus chordoma. *Archives of Otolaryngology* 1980; 106:1 -5.
28. Trotter W. Operation for malignant disease of the pharynx. *Br J Surg* 1929;16:485.
29. Donald PJ. Infratemporal fossa and skull base surgery. In: Donald PJ. ed. *Head and neck cancer: management of the difficult case.* Philadelphia: WB Saunders, 1984:277-312.
30. Martin H, Tollefson HR, Gerold FP. Median labial mandibular glossoptomy. *Am J Surg* 1961;102:753-759.

Surgery of the Skull Base, edited by Paul J. Donald.
Lippintott-Raven Publishers, Philadelphia © 1998.

CHAPTER 27 ☐

Management of the Vertebral Artery

Bernard George

The vertebral artery (VA) is the most important vascular structure in the vicinity of the craniocervical junction. At this level, its course is complex and may present several variations and anomalies. The VA may be directly involved by different lesions, mostly tumors. Control of the VA allows for the safe and adequate treatment of these lesions, as well as permitting the preservation of VA flow. Moreover, controlling the VA may improve the access to different parts of the skull base, such as the foramen magnum (FM) or the jugular foramen.

HISTORICAL DATA

As early as 1888, Matas (1) reported surgical treatments for distal VA posttraumatic aneurysms. In 1917, a route to the Cl-2 segment of the VA was described by Henry (2), who concluded that "it was a cure for which there is no disease." Since then, many reports on cervical VA surgery have been published (3-5), but most relate to the two proximal VA segments. Although many pathologic processes, including occlusive vascular disease, craniocervical junction malformations, vascular malformations, and FM or jugular foramen tumors have been treated (3,6-16), distal VA exposure is rarely considered. The deep location of the VA and the danger of bleeding from the perivertebral venous plexus explain why this exposure is usually considered difficult and hazardous.

ANATOMIC DATA

The VA segments close to the skull base are the third (suboccipital segment), extending from the transverse foramen of C2 to the FM dura, and the fourth (intracranial segment), running from the FM to the vertebrobasilar junction.

Course

Third Segment

The VA comes out the transverse foramen of C2 in a posterolateral direction, immediately turns vertically, and courses through the transverse foramen of the atlas. Inside this foramen, the VA curves medially and posteriorly to reach the V A groove lying behind the lateral mass of the atlas. At the end of this groove, the VA runs in an oblique superior and anteromedial direction toward the FM dura (17).

Fourth Segment

After piercing the FM dura, the VA proceeds in the same superior and anteromedial direction in the subarachnoid space to reach the lateral side of the medulla oblongata (MO). It then passes around the MO and joins the contralateral VA in front of the MO at approximately the level of the pontomedullary junction, to form the basilar artery.

Relationships

In the third segment, the VA is surrounded by a venous plexus, and it is noteworthy that both the VA and its venous plexus are enclosed in a continuous periosteal sheath. This periosteal sheath is continuous with the periosteum of the transverse foramina of C1 and C2, with the deep aponeuro-sis of the muscles between these transverse foramina, with the posterior atlantooccipital membrane that arches over the VA groove of the atlas, and with the FM dura mater. There, the VA and its periosteal sheath invaginate the FM dura before perforating it, making a double sleeve of periosteum and dura around the VA of 3 to 5 mm. Intracranially, the VA wall is directly in contact with the cerebrospinal fluid. There are no more satellite veins or periosteal sheath.

Between Cl and C2, the VA is crossed by the ventral ramus of the second cervical spinal nerve root. Above C1, the

B. George: Department of Neurosurgery, Hopital Lariboisiere, 75475 Paris, France.

first cervical spinal nerve root, which pierces the dura with the VA or separately, runs along the posteroinferior aspect of the VA and merges under it posteriorly in the middle of the groove. Intracranially, the VA proceeds under the arch made by the first two digits of the dentate ligaments, and successively courses ventral to the rootlets of cranial nerves XII, X, and IX. The spinal part of cranial nerve XI ascends in the spinal canal posterior to the dentate ligaments, crosses the posterior aspect of the VA, and finally joins its cranial part below the cranial nerve IX and X rootlets.

Branches

Along the suboccipital VA segment, there are usually no important branches. The anterior meningeal artery arises at the C2-3 level (18). Radiculomuscular branches originate between Cl and C2, at the outlet of the transverse foramen of the atlas and at both ends of the V A groove. The intracranial VA segment gives rise to the anterior spinal artery and to the posteroinferior cerebellar artery (PICA), which, respectively, arise from its first few millimeters and at the level of the lateral aspect of the MO (15 mm in average from the dura perforation). Branches of various size and number supplying the MO may arise either directly from the VA or from the PICA (Fig. 1).

Variations and Anomalies

Size

Vertebral artery diameter varies greatly from large to very small (2-8 mm). A small VA is termed hypoplastic when it joins the opposite VA, and atretic if not (see Fig. 1). In general, a small VA is inversely related to a large contralateral one; the former is called the minor VA and the latter the dominant VA. VA of equal size on both sides are observed in 40%. Bilateral small VA are uncommon and suggest the presence of a persistent congenital anastomosis between the basilar trunk or the VA and the internal carotid artery (19). In descending order of frequency, those connections are the trigeminal, otic, hypoglossal, and proatlantal arteries. The two caudal ones are connected with the VA; the hypoglossal artery is intracranial and the proatlantal is extracranial. The proatlantal artery may join the VA with either the external or the internal carotid artery (19-22).

Course

Occasionally, the VA may enter the dura mater at the Cl-2 level. In fact, there is a VA duplication with an atretic branch that follows the normal extracranial course, and a normal-sized branch that takes the abnormal intradural course (23-26).

The VA course is also modified by craniocervical junction malformations such as malposition, segmentation, fusion, or agenesis of different bone elements (27-30).

Above the posterior arch of the atlas, calcification or ossification of the posterior atlantooccipital membrane may turn the VA groove into a bony tunnel (31), raising some difficulties for VA exposure.



FIG. 1. Atretic vertebral artery ending at the occipital artery, with very small connection with the posteroinferior cerebellar artery. Note all the vascular branches connecting with branches of the external carotid artery and ascending cervical artery.

Branches

In addition to persistent congenital anastomosis between the VA and the carotid artery, variations in the origin of the PICA and the anterior spinal artery may be observed. The site of origin of the PICA is extracranial in about 20%, arising mostly from the VA above the posterior arch of the atlas or between Cl and C2 (32-34), and rarely from the external carotid artery. Intracranially, the PICA may arise anywhere along the VA or from the basilar trunk (by a common trunk with the anteroinferior cerebellar artery). The origin of the anterior spinal artery may be located on either side of the dura; when the origin is extradural, it pierces the dura with or without the VA.

Dynamic Changes

The suboccipital VA segment has a particular course, showing a double bayonet shape and a horizontal "U" shape on lateral and anteroposterior angiographic views, respectively. This course allows VA flow to be preserved during head movements. Moreover, the VA wall is untethered to the periosteal sleeve, whereas the periosteal sheath is fixed at each transverse foramen. At the FM level, the VA wall is adherent to the periosteal sheath in continuity with the dura mater, Therefore, this is the only fixed point of the VA during head movements. The two parts (above C1 and between C1 and C2) of the suboccipital VA segment are stretched during extension and rotation toward the opposite side but are compressed during flexion and ipsilateral rotation. Therefore, the course of the VA and its anatomic relationships with the periosteal sheath have many consequences for VA surgery.

Initially, these factors influence the surgical positioning of the patient. In the anterolateral approach (ALA), the patient is supine with the head extended and rotated to the opposite side. In this position, because only the atlas follows head rotation, while the axis does not, the two VA parts (above C1 and between C1 and C2) are stretched and almost parallel with the posterior arch of the atlas between them (Fig. 2).



FIG. 2. Dynamic changes of the vertebral artery (VA) during contralateral rotation of the head. A: Dry bone with the VA *(red bundle),* the venous plexus *(blue bundle),* and the accessory nerve *(yellow bundle).* B: Cadaver view. C: Surgical view. *Asterisk,* posterior **arch of** atlas; *star,* VA; *arrow,* **accessory** nerve.

There are several anatomic and radiologic reports in the literature on changes in VA diameter during head movements. Some of them, especially the anatomic ones, demonstrate VA occlusion during extension and contralateral rotation of the head (35-38). In living patients, it occurs rarely unless there is a pathologic condition that worsens the VA stretch. These pathologic conditions include osteophytes, fibrous bands, nerve compression, bony malformations, or tumors. In fact, this is seldom observed on the third VA segment. In the author's experience, there have been only two cases of intermittent VA compression during head movement due to craniocervical junction malformation.



FIG. 3. Schematic drawings of the main steps of the posterolateral approach. A: Skin incision. B: Exposure of the occipital bone and posterior arch of the atlas. C: Control of the vertebral artery and resection of the posterior **arch** of **the** atlas and **occipital bone.**

I

The VA's course also allows the surgeon to pull a few millimeters of the artery out of the transverse foramen after opening the periostea) sheath. This provides more VA length between the two transverse foramina, making it easier to apply clips when performing an anastomosis.

Finally, the adherence between the dura, periosleal sheath, and the VA wall at the FM level makes dissection of the VA very difficult. It is in general much safer to cut dural and periosteal sheaths 2 or 3 mm around the VA.

EXPOSURE

The lateral location of the VA along its entire course makes its surgical exposure easier using the lateral approaches. The medial approaches, either anterior (the transo-ral approach) or posterior (the standard posterior approach), are too limited laterally to reach the VA.

The lateral approaches include two main routes, posterolateral and anterolateral, according to the VA side approached.

The Posterolateral Approach

The patient is placed in a sitting, prone, or lateral position (3,9,39) (Fig. 3). The incision begins on the midline, ascends vertically up to the occipital protuberance, bends laterally along the occipital crest, and descends toward the mastoid process. The laminae of C2, the posterior arch of the atlas, and the occipital bone are exposed initially. The exposure is then extended subperiosteally up to the transverse processes of C2 and C1. The C1-2 VA segment is identified following the C2 spinal nerve root, which divides in ventral and dorsal rami running on either side of the V A. These rami of the C2 spinal nerve root are very good landmarks because they are in direct contact with the periosteal sheath. The VA segment above C1 is exposed in its groove lying on the posterior arch of the atlas. The medial end of this groove is clearly identified by the marked increase in height of the posterior arch of the atlas. The safest way to proceed is to split the periosteum on the inferior aspect of the posterior arch from the midline toward the transverse process; then, the exposure is extended



FIG. 4. Schematic drawings of the main steps of the anterolateral approach. A: Skin incision. B: Opening of the plane between the sternocleidomastoid muscle and the internal jugular vein with identification and mobilization of the accessory nerve. C: Resection of the muscles inserted on the transverse process of the atlas, exposing the vertebral artery (VA) between C1 and C2, and above C1. D: Opening of the transverse process of the atlas. *(Continued.)*



FIG. 4. *Continued.* E: Complete resection of the transverse process of the atlas with VA transposition. F: Resection of the posterior arch of the atlas and occipital bone up to the sigmoid sinus.

toward the superior aspect of the posterior arch of atlas. If necessary, the Cl transverse foramen is opened.

Anterolateral Approach

The patient is placed in a supine position with the head slightly extended and rotated to the opposite side (3.9,13) (Fig. 4). The skin incision is made along the anterior edge of the upper part of the stcrnocleidomastoid muscle (SCM), extended over the masloid process, and then taken approximately along the occipital crest. The dissection proceeds between the SCM and the internal jugular vein. The accessory nerve (cranial nerve XI) is identified at its junction with the SCM and dissected up to the skull base. Cranial nerve XI is usually retracted inferiorly and medially by the fatty sheath covering the depth of the field, which is freed and wrapped around the nerve. The transverse process of the atlas is then clearly visible and the oblique muscles inserted on it are cut, exposing the two VA segments. The Cl-2 VA segment is crossed by the ventral ramus of the C2 spinal nerve root. The Cl spinal nerve root merges under the VA in the groove of the atlas.

VERTEBRAL ARTERY MANAGEMENT

According to the lesion and its location, VA management differs. It may consist of VA control alone, or mobilization and transposition, or revascularization.

Control

At the least, all VA management requires VA control, and in many cases, VA control alone is enough.

The key points in VA control are, first, to stay outside the periosteal sheath as long as possible and, second, to obtain adequate VA control proximal and distal to the lesion. The VA segments exposed must be long enough to be able to clip the artery if necessary. Tn general, it is necessary to control the VA up to the next proximal and distal transverse processes or up to the FM dura.

Cl-2 Segment

The landmark for the Cl -C2 segment is the ventral ramus of the C2 spinal nerve root, which crosses the Cl-2 segment just before the VA periosteal sheath. The C2 spinal nerve root often needs to be divided. Because the distal branches have already been cut subcutaneously during the skin incision, this adds no sensory deficit. The numerous anastomoses and the overlapping cutaneous territories of the superficial cervical plexus explain why the long-term results of C2 spinal nerve root division are limited to hypesthesia of the earlobe and a small area of the jaw angle. To obtain complete control of this segment, dissection must be done all around the VA with control of the radiculomuscular branch. which usually arises from the posterornedial aspect.

Segment Above Cl

The groove of the atlas must be subperiosteally exposed to preserve the VA periosteal sheath. Freeing the inferior aspect of the V A periosteal sheath from the groove usually is easy. It is much more difficult to free the superior aspect, however, because the periostea! sheath is adherent to the posterior atlantooccipital membrane. It is even more difficult if that membrane is calcified or ossified.

At the medial end of the VA groove of the atlas, the VA proceeds anteromedially and superiorly toward the FM dura mater. There are often radiculomuscular branches at both ends of the VA groove (9,11-14,40-42) (Fig. 5).

The Cl spinal nerve root which is always very small. i> often cut inadvertently without serious consequences.

Some difficulties may arise when there is an extracranbl origin of the PICA or the anterior spinal artery. These must be identified and dissected along their course up to the dura.

Intracranial Segment

Intracranially, the difficulties arise from the lower cranial nerves crossing the posterior aspect of the VA. The VA has thus to be controlled as it passes between the network of cranial nerve rootlets. To enlarge the operative field and obtain a wider angle that allows control of the distal VA, the bone opening must be widened laterally. The occipital bone is resected up to the sigmoid sinus, therefore including a partial mastoidectomy. The lateral wall of the FM above the VA (i.e., the condyle and jugular tubercle) also has to be partially drilled. This drilling is extended up to the vicinity of the condylar and jugular foramina. It is often useful to check the intradural space while drilling extradurally to control the location of the condylar and jugular foramina and avoid any nerve injury. At its maximum, drilling can be done completely around cranial nerve XII or nerves IX, X, and XI, which permits extradural access to the lower part of the clivus.

Mobilization or Transposition

The VA may be displaced to reach different structures. Obviously, mobilization and transposition require previous complete control of the VA and cutting of all collateral branches (9,11-14,40-42) (see Fig. 5; Fig. 6).

Mobilization or transposition is performed to improve access to the FM or jugular foramen or to facilitate tumor resection close to the VA.

Mobilization concerns the VA segment above C1 and may be either in a superior or inferior direction. The VA and its periosteal sheath must be completely freed from the C1 transverse foramen to the FM dura.



FIG. 5. Three examples of control and mobilization of the vertebral artery (VA) above C1 through PLA. A: Extradural extension of a neurinoma (7) and the C1 nerve root (open *star).* **A-C:** Notice the change in the height of the posterior arch of the atlas at the medial end of the VA groove (arrow). *Black star.* VA.



FIG. 6. Two examples of transposition of the vertebral artery (VA) after resection of the transverse process of the atlas. A: Chordoma. B: Aneurysmal cyst. *Star,* VA; *arrow,* accessory nerve.



FIG. 7. Revascularization. A: Saphenous vein graft *(asterisk)* bypassing the common carotid artery *(sma)l arrow)* and the vertebral artery (VA) between C1 and C2 (star). Notice the accessory nerve wrapped in the fatty sheath *(arrow).*



FIG. 7. *Continued. B:* Angiographic control of a bypass between the common carotid artery and the VA between C1 and C2. C: Angiographic control of a bypass between the carotid bifurcation and the VA above C1.

Transposition applies to the whole suboccipital segment from C2 to the FM dural penetration; consequently, it requires the opening of the C1 transverse foramen. After controlling the two parts of the suboccipital segment on each side of the Cl transverse foramen, the periosteal sheath is followed inside the foramen, splitting the periosteum from the bone. Then, the transverse foramen is unroofed, biting its external wall progressively using the Kerrison rongeur. To achieve the transposition, the medial wall must also be resected to provide space in the concavity of the VA loop and allow the VA to be pulled without damaging the periosteal sheath.

Revascularization

Occlusion of a dominant VA may lead to vertebrobasilar insufficiency (3,6-10,14) (Fig. 7). To restore adequate flow and pressure, revascularization of the VA is necessary. This is usually achieved by common carotid-to-distal VA venous bypass grafting. The usual site of graft implantation is the Cl-2 VA segment, and occasionally the VA segment above Cl or even the intracranial VA segment. In general, an end-to-side anastomosis between the saphenous vein graft and the distal VA is used; an end-to-end anastomosis is reserved for situations in which a proximal temporary clip cannot be placed. Complete exposure and control of the VA is essential to perform such an anastomosis. This is obtained by opening the VA periosteal sheath and coagulating the peri vertebral venous plexus.

PATHOLOGY

Vertebral artery management is required in two different circumstances: when the VA is directly involved by the pathologic process, and when the VA precludes access to the pathologic process. In addition, VA exposure helps to control the vascular supply to some vascular lesions (3,14,41,43,44), or allows a VA revascularization procedure to be performed.

Vertebral Artery Involvement

Many pathologic processes involve the VA, including tumors, infection, bone malformations, and traumatic lesions.

Tumors

Many tumoral types grow close to the VA (Fig. 8); they sometimes even encase the VA with or without invading its periosteal sheath. It is never possible to determine radiologically whether the periosteal sheath is invaded. Therefore, the VA must always be controlled proximal and distal to the tumor (or at least proximal, if distal control appears difficult). Then, the dissection proceeds along the VA, trying to stay outside the periosteal sheath as long as possible. Usually, a good plane can be developed between the tumor and the periosteal sheath, avoiding any troublesome bleeding from the perivertebral venous plexus. Venous bleeding caused by small tears of the sheath can be stopped by direct bipolar coagulation of the sheath, applying the bipolar forceps on each side of the laceration. In most benign tumors and in many malignant ones, preservation of the periosteal sheath is possible even if the VA segment involved supplies the tumor. The feeding branches can be coagulated and divided outside the periosteal sheath. In the rare instances in which the periosteal sheath is invaded by the tumor, proximal control of the VA allows coagulation or packing of the perivertebral venous plexus and dissection of the tumor from



FIG. 8. Histiocytosis with invasion of the periosteal sheath of the vertebra! artery *(star). Asterisk* indicates posterior arch of the atlas; *small arrows* indicate the tumor inside the pe-sheath; arrow imircates the accessory nerve.

TABLE 1. *Lesions involving the vertebral artery*

Lesion	Total	Stenosis	Occlusion
Neurinoma	18	3	—
Meningioma	5	2	—
Sarcoma	5	3	3 perioperative
Angiomyolipoma	1	—	—
Lymphoma	1	—	1
Chordoma	12	—	—
Osseous tumor	13	3	1
Infection	2	—	1
Craniocervical junction malformation	2	—	2[a]
Aneurysm	8[b]	—	—
Arteriovenous fistula	2	—	—

[a] Intermittent occlusion.
[ft] Six intracranial and two **extracranial.**

the wall of the artery. However, in some sarcomas, and particularly in recurrent ones, no plane can be found between the tumor and the wall of the VA, which makes it necessary to sacrifice the VA. Resection of the VA may also be necessary in some malignant tumors to achieve a radical removal. This situation must be anticipated, and the patient's tolerance of VA occlusion must be assessed by preoperative balloon occlusion testing. The occluding balloon must be applied precisely at the designated level of surgical ligation. A balloon placed too far from the tumor may spare some collateral branches that could feed me VA dislally. Ideally, the occlusion test is performed proximal and distal to the tumor. Most of the time, the VA occlusion test is perfectly tolerated and no revascularization is necessary. In the author's series of 156 tumors involving the cervical VA. the VA was sacrificed in 5 cases without complications, and a revascularization was performed only once, in the case of an osteoblas-toma in a 6-year-old boy that involved both VA and that had already been operated on in another center.

Table 1 gives the distribution of tumors involving the VA, the number of patients who had surgical VA occlusion, and the number of patients with preoperative VA stenosis or occlusion.

The most common tumor involving the VA is neurinoma of the Cl or C2 spinal nerve root (42). Neurinomas often have an extradural component and are distinguished by multiplicity and bilateral!ty owing to a frequent association with neurofibromatosis (see Fig. 5 A; Fig. 9). Meningiomas of the craniocervical junction usually are intradural. but occasionally are either entirely extradural or both intradural and extradural (39,40,41,43) (Fig. 10). In a series of 42 mcningiomas of the FM region, the author observed 1 extradural and 4 intradural-extradural cases. Similarly, in a French cooperative study, the author's team collected 106 mcningiomas that included 4 extradural and 11 intradural-extradural occurrences (40). Meningiomas with an extradural component often behave very aggressively and may invade the bone and cervical soft tissues, including the VA. Malignant tumors are frequently characterized by invasiveness. but meningioma is the only benign tumor that may have thi> invasive feature; this is explained by the continuity between the dura and periosteum. Among nonosseous tumors, the author observed a few cases of sarcomas (rhabdomyosarcomas and undifferentiated sarcomas) and one case of angiomyolipoma (Fig. 11).



FIG. 9. Intradural-extradural neurinoma *(N)* in contact witr the vertebral artery *(arrow).*



FIG. 10. Two examples of meningioma involving the vertebral artery (VA). A: Intradural foramen magnum meningioma. B: Extradural meningioma with cervical extension. T, tumor; *arrow,* VA.



FIG. 11. Nonosseous tumors involving the vertebral artery. A: Sarcoma. B: Neurinoma. C: Angiomyolipoma.

There are many types of osseous tumors, but metastasis from carcinoma is the most common (Fig. 12). Chordomas usually develop on the midline, but in the author's experience, they can also present with lateral (and sometimes bilateral) extension with VA encasement; this was observed in 12 cases (Fig. 13).

Vertebral artery stenosis or occlusion produced by tumoral compression is rare, and induced ischemic manifestations are exceptional (14,26). In the author's series, occlusion was noticed in 2 cases (one osteochondroma and one Hodgkin's disease) and stenosis was observed in 11 cases. They were never associated with any ischemic symptoms. The slow growth of tumors always permits the development of collateral flow to compensate for VA occlusion. The only ischemic event seen was an embolism in the posterior cerebral artery after VA occlusion by a low-grade chondrosar-coma of the lower part of the neck.

Nontumoral Processes

Nontumoral processes at the C2-1 and FM levels can induce permanent or intermittent VA compression. Intermittent VA compression may be symptomatic during head and neck movements, usually rotation. To consider a process compressing the VA as the cause of clinical symptoms, the



FIG. 12. Osseous tumors involving the vertebral artery. A: Metastasis. B: Histiocytosis (see Fig. 8). C: Aneurysmal cyst (see Fig. 6B).



FIG. 13. Unilateral (A) and bilateral **(B)** chordomas involving the vertebral artery *(arrow).*

same movement carried out during angiography must produce a severe VA compression associated with the usual clinical symptoms. The author observed two such cases, including a bilateral one, that were both related to a craniocervical junction malformation: a Cl -2 fusion in one case and a supplementary condyle in the other.

In the case of the Cl-2 fusion, the patient could not rotate her head to either side without experiencing vertigo and often fainting. On angiography, there was a complete blockage of contrast in both VA at the Cl level during rotation toward the opposite side. Surgery using the bilateral posterolateral approach (PLA) revealed a tortuous course of both VA along Cl-2. The transverse foramina of Cl and C2 were opened on both sides, and all the fibrous bands crossing the VA were resected from C2 to the FM. The laminae of C2 were completely fused with the posterior arch of C1, making it impossible for the atlas to rotate with the head. After surgical decompression, the patient could move her head in every direction without clinical symptoms, and angiography showed an almost normal VA diameter along its entire course and on both sides in any head position.

The second case was a 12-year-old girl with a supplementary condyle. She presented with occasional posterior headaches and stiffness, followed one day by a sudden and transitory coma after physical exercise. The author did not dare perform angiography in different head positions because three-dimensional computed tomography obviously demonstrated the dominant V A traveling around the supplementary condyle. Surgery using unilateral PLA showed a stretched VA around the abnormal bony piece, which was extensively drilled. Because there was some doubt about the stability of the craniocervical junction, a fusion was done using iliac bone grafts placed between the occipital bone and the posterior arches of C1 and C2.

In the author's personal series, there was also a case of tuberculosis involving C1 and C2 inducing a V A occlusion on one side and a severe stenosis on the other (3). This patient presented with repeated transient ischemic deficits in the vertebrobasilar system that disappeared totally after medical therapy. Both VA repermeabilized completely without any surgical treatment.

Vertebral artery compression may also be due to neural elements, as in the case reported by Carney at the Cl-2 level (6). In the author's material, there is one asymptomatic case probably due to the second cervical spinal nerve root (3).

The author's team also has dealt with three cases of acute VA injury. Two cases occurred during posterior fossa opening with inadvertent VA laceration. The exposure was enlarged laterally to control and temporarily clip the VA proximal and distal to the tear. Then, in one case, the repair was done with simple stitches, and in the other case with a small venous patch. The third case was an extradural hematoma of the posterior fossa with a fracture of the occipital bone. A piece of bone was displaced inferiorly, compressing the VA. The VA had to be exposed in its groove above Cl before the bony compression could safely be released. The periosteal sheath was opened but the arterial wall itself was intact. In all three cases, the follow-up was uneventful.

To release VA compression, the PLA or ALA can be used according to the extent of the lesion (39,40). The PLA is preferred when the lesion has an intradural extension and when the extradural component is rather limited. On the contrary, the ALA is the better choice if the extraspinal-extracranial part is large, and especially if it extends toward the retropharyngeal space. A lesion of limited size in the bone or the extradural space near the V A can be exposed by any of the approaches. When the lesion is bilateral, the PLA can be done on both sides by the same incision, whereas two ALA have to be done separately or require separate incisions.

продолжение

продол
жение

Vertebral Artery Obstructing Surgical Access

Control of the VA helps in getting access to different neighboring regions, including the FM, upper cervical, and jugular foramen regions (Tables 2, 3).

Foramen Magnum Region

The VA is the key point in the approach to tumors of the FM region (Fig. 14). Control of the VA gives access to-the FM lateral wall, including the jugular tubercle, condyle, lateral mass of the atlas, and the C1-2 joint. Mobilization of the VA upward or downward allows the surgeon to drill the bony structures located below or above, respectively. Consequently, it is very important before surgery to define the location of the tumor with regard to the VA. Using the PLA, drilling allows access to the subarachnoid spaces lateral and anterior to the neuraxis (3,39,40,41,43-46). In most cases, these spaces are naturally enlarged by the tumor, which displaces the MO and spinal cord in the direction opposite to tumoral growth. Usually, drilling does not need to extend beyond the media] third of the bony structures. Lateral tumors displace the neuraxis toward the opposite side, enlarging the subarachnoid space naturally. In anterior tumors, the neuraxis is shifted posteriorly and must be circumvented; therefore, more drilling of the FM lateral wall is needed to reach anterior tumors without retraction of neural structures. Dural opening must also be done according to the relationship between the tumor and the VA. The dura is cut vertically with a horizontal contraincision toward the VA above or below it, or even on both sides (Fig. 15).

The relationship between FM tumors and the VA improves anticipation of the location of the lower cranial nerves. In tumors located below the VA, the nerves are always displaced upward with the VA, whereas in those located above the VA, displacement of the nerves is unpredictable. Therefore, in the former case, the nerves are always found on the superior pole of the tumor; in the latter case, they must be searched for all around the tumor.

The lower third of the clivus is usually included in the FM region. In some cases, the PLA can be used to resect tumors extending up to the clivus. Removal can be done using the space made by the tumor and starting inferiorly. For this purpose, it is often useful to combine the PLA with a retrosigmoid approach or, occasionally, with a presigmoid or transsigmoid approach (retrolabyrinthine or translabyrinthine route).

With the ALA, the posterior arch of the atlas, the mastoid process, and the occipital bone can be exposed posteriorly. Again, mobilization of the VA then gives access to the jugular tubercle and condyle above the VA, and to the lateral mass of the atlas below it (3,10,39,40). Moreover, if the VA is transposed posteriorly and medially, the surgeon can reach the odontoid, Cl-2 facet joint, anterior arch of the atlas, and tip of the clivus. Therefore, drilling of the bone at this corresponding level exposes the dura in front of the medulla or upper spinal cord. In most of the author's cases, this exposure was facilitated by the tumor itself, which invaded or even destroyed the bony structures.

As a general principle, the PLA is used for intradural processes and the ALA for osseous or extradural ones. Table *4* lists the lesions for which these two surgical approaches were respectively used. However, in some extradural lesions, the PLA was chosen (see Table 4). For instance, small, bilateral extradural tumors like neurinomas were always removed by PLA. One case of synovial cyst on the anterior midline, extradural but protruding intradurally, was resected by PLA; the transoral approach could have been an alternative, but it involves greater risks of postoperative instability.

TABLE 2. *Nonosseous tumors contiguous to the vertebral artery*

Tumor	Total	Intradural	Intradural–extradural	Extradural
Meningioma	41	36	4	1
Neurinoma	23	6	8	9
Hemangioblastoma	2	2	—	—
Epidermoid cyst	3	3	—	—
Melanoma	1	1	—	—
Angiomyolipoma	1	—	—	1
Lymphoma	1	—	—	1
Ependymoma	2	2	—	—
Jugular foramen tumors				
Paraganglioma	8	—	6	2
Neurinoma	6	—	5	1
Meningioma	4	—	4	—



FIG. 14. Intraoperative view of exposure (A) and resection (B) of a meningioma using the posterolateral approach. *T,* tumor; *star,* vertebral artery.



FIG. 15. Posterolateral approach for a meningioma with extension on both sides of the vertebral artery (VA). A: Extradural exppsure with some drilling of the condyle *(circle)* and of the lateral mass of the atlas *(asterisk). B:* Intradural exposure. Note the dural incision on both sides of the VA. *T,* tumor; *star,* VA; *arrow,* cranial nerve XI.

TABLE 4. *Indications for surgical approaches*

Lesion	Total	Posterolateral approach	Anterolateral approach
Foramen magnum area			
Intradural tumors	50	50	—
Intradural–extradural tumors	12	12	—
Extradural tumors	12	1	11
Osseous tumors	22	4	18
Chordoma	12	—	12 (3[a])
Osseous lesions	7[b]	5 (1[a])	1
Jugular foramen area			
Jugular foramen tumors	18	3	15

[a] Bilateral approach.
[b] One case (tuberculosis) treated medically.

Similarly, for a small osteoid osteoma medial to the lateral mass of the atlas, the author's team chose the PL A with upward mobilization of the VA. rather than the ALA with drilling of the lateral mass of the atlas. Bone malformations like odontoid malposition or supplementary condyle were also treated by PLA owing to their bilateral development or to the difficulty of extending the head as required in the ALA. However, no strictly mtradural lesion was treated by the ALA. Large extradural tumors required ALA on one or even both sides if they had extensive bilateral extension, as was the case in three cases of chordoma. Therefore, there are no absolute criteria for one or the other technique. They must be discussed after a precise radiologic work-up that establishes the tumor's size and location in relation to the dura and the VA (40).

Upper *Cervical Spine*

Using the ALA, the anterior aspect of the upper cervical spine (above C3) can be exposed (3JO, 11,12) (Fig. 16). The opening between the jugular vein and the SCM is extended downward. The prevcrtebral muscles (longus colli and anterior rectus) covering the lateral aspect of me vertebral bodies of C2 and C3 are resected, exposing the transverse processes. Before this, the sympathetic trunk must be identified under the prevcrtebral aponeurosis and retracted medially with all the neurovascular elements (carotid artery, jugular vein, and vagus nerve); to do so, the sympathetic trunk's anastomosis with the cervical spinal nerve roots must be divided. This may induce a transient and always very limited Homer's syndrome if the main trunk of the sympathetic chain was preserved. Next, the transverse foramina of C2 and C3 are opened, taking care to preserve the VA periostea! sheath. The course of the VA changes abruptly at the outlet of the C3 foramen, running posteriorly and superiorly and thus becoming more remote from the lateral side of the vertebral bodies. The VA may then be pulled out of the transverse foramina or kept in place, protected by a spatula, to work on the cervical bodies. This approach permits resection of a bone tumor, oblique drilling of the cervical bodies (47), access to the anterior aspect of the spinal cord, and removal of anterior extradural tumors like neurinomas, meningiomas, or chordomas.

Jugular ***Foramen Region***

Corona] computed tomography or magnetic resonance imaging clearly shows the transverse process of the atlas projecting exactly below the jugular foramen (Fig, 17). Therefore, proceeding successively along the lateral mass of the atlas, the condyle, and the jugular tubercle, the surgeon can reach the lower part of the jugular foramen. This permits the jugular foramen to be opened without any petrous bone drilling (Fig. 18). The approach is similar to the ALA in its first steps, using the same patient positioning and the same skin incision. The VA is exposed from C2 to the FM dura. The internal jugular vein and the accessory nerve are also identified. Then, the vagus (X), glossopharyngeal (IX). and hypoglossal (XI3) nerves are dissected as much as possible



FIG. 16. Intraoperative view after removal of a meningioma at the C1 -2 level using the anterolateral approach. *Stars,* vertebral artery; *1,* transverse process of atlas; *2,* transverse process of axis; *circle,* dura mater.



FIG. 17. Magnetic resonance angiogram showing the superimposition of the loop of the vertebral artery in the transverse process of the atlas and the jugular bulb in the jugular foramen *(arrow).*

up to the skull base. The mastoid process is partially resected to expose the sigmoid sinus. At this stage, the tip of the Cl transverse process, which is always much bigger than the other transverse processes, obstructs the route to the jugular foramen. To enlarge the access, the mastoid process and the petrous bone must be drilled more extensively, and thus an infratemporal approach is performed. This permits the opening of the superior and lateral aspects of the jugular foramen. However, if the Cl transverse process is resected, the inferior and posterior sides of the jugular foramen may be exposed and drilled. To do so. the Cl transverse process must be completely removed, leaving bone only on the medial side. Sometimes, the space gained by the Cl transverse process resection is not sufficient, and the VA must be transposed. This juxtacondylar route to the jugular foramen (48) is mainly useful to resect tumors located in the jugular foramen without extension to the petrous bone; this is especially the case in neurinomas and meningiomas, and occasionally



FIG. 18. Jugular foramen neurinoma. A: Coronal magnetic resonance image. Note the vertebral artery (VA) in the transverse process of the atlas and the jugular vein (arrows). B: Intraoperative view of the same case. C: Postoperative computed tomography scan control. *Star,* VA; *T,* tumor; *V,* internal jugular vein; *arrow,* accessory nerve; *circle,* sigmoid sinus.

in paragangliomas. However, paragangliomas usually arise from the middle ear promontory and the dome of the jugular foramen and therefore invade the petrous bone, which has to be drilled. For paragangliomas, the juxtacondylar approach is used as a complement to the standard infratemporal technique (49).

Vascular Control and Revascularization

Whatever the lesion and its relation with the VA may be, VA exposure and control may decrease its vascular supply. This is principally useful in vascular tumors like meningiomas or paragangliomas (Fig. 19). In these tumors, the vascular feeders may arise from branches of the ascending and deep cervical arteries and the external carotid artery, which are easily controlled through the ALA (or occasionally by embolization). Vascular feeders may also come from the VA itself, which shares with the ascending pharyngeal artery the vascular supply to the FM and jugular foramen regions. For example, anterior meningiomas of the FM are always mainly fed by the anterior meningeal artery, which branches from the second interspace radicular artery. Moreover, paragangliomas of the jugular foramen also are primarily supplied by the VA. Control of the VA combined with resection of the atlas transverse process not only enlarges the space to reach the posteromedial aspect of the jugular foramen but simultaneously divides all the tumoral feeders.

Surgical treatment of vascular malformations, when required, also needs VA control. Arteriovenous malformations



FIG. 19. Tumoral vascular supply from the vertebral artery. A: Angiomyolipoma (see Fig. 11C). B: Angioblastic meningioma. C: Meningioma fed by the anterior meningeal artery *(arrows).*

are essentially fistulas between the VA and neighboring veins, most commonly the perivertebral venous plexus and the jugular vein. Those fistulas often seem very complex on angiography, but usually are simple, unique fistulas that may be obliterated by endovascular techniques (3,50,51). Surgical treatment was, in the author's experience, very rarely required (2 of 41 cases of fistula above C2) (3,9). One case was a stab wound with a direct fistula between the VA and the internal jugular vein. The other was a posttraumatic (fall) aneurysm at the Cl-2 level fed by the C2 radicular branch of the VA and the occipital artery and draining into the epidu-ral venous plexus. Therefore, occlusion by embolization must always be attempted first, because even if it fails, it permits identification of the exact site of the fistula. Another type of arteriovenous malformation is angiodysplasia, which is a complex lesion involving the skin, muscle, bone, and sometimes the dura. It usually only results in cosmetic problems. Indications for treatment are limited because it often requires extensive resection of muscles and skin followed by plastic reconstruction. Cutaneous ulceration with bleeding is the only condition requiring surgery.

Aneurysms of the VA include different types of lesions, each one having a particular prognosis and requiring a specific treatment.

Vertebral artery aneurysms must be separated into extracranial and intracranial aneurysms, which have different origins and presentations. Extracranial aneurysms are caused by many pathologic processes, of which the dissecting hematoma is the most frequent (Table 5).

Dissecting hematoma most often induces tubular stenosis, but occasionally causes aneurysm. The two usual locations are the transversary canal inlet (C6) and the suboccipital segment (C2-FM).

Stenosis usually heals spontaneously in few weeks or months. On the contrary, aneurysms are very unlikely to decrease in size. Therefore, as with aneurysms of any other cause, the risk of embolism persists and must be prevented by surgical exclusion. Treatment is best achieved by a common carotid artery-to-VA bypass, distal to the aneurysm, using a saphenous vein graft. Direct repair is not recommended because the arterial wall is dysplastic and therefore difficult to suture. The author has treated two cases of aneurysm above C2. One was on the VA segment above Cl, probably of congenital origin, and was treated by common carotid-to-distal VA bypass. The other one was a traumatic dissection on the C2 radicular branch with a 2-cm-diameter aneurysm draining slowly in the perivertebral venous plexus, and was treated by direct resection.

TABLE 5. *Causes of extracranial vertebral artery aneurysms*

Dissecting hematoma
Fibromuscular dysplasia
Collagen diseases (Ehler-Danlos syndrome)
Neurofibromatosis
Atherosclerosis
Trauma
Radionecrosis

Intracranial aneurysms are of two main types, saccular and dissecting aneurysms. Intracranial dissecting aneurysms are recognized by the usual angiographic features of dissecting hematoma and by their usually more-or-less fusiform aspect. Their most common mode of presentation is not ischemia from embolism, as in extracranial aneurysms, but subarachnoid hemorrhage. Because of their high tendency to rebleed, they must be treated as soon as possible to exclude the arterial segment involved. This can be achieved surgically or by interventional radiologic means, either by proximal occlusion or by trapping of the involved arterial segment. Occlusion or trapping must be discussed according to the size of the VA and to the site of origin of the PICA and of branches to the medulla. In most of the author's cases, proximal occlusion with coil or balloon is the chosen treatment because fixing a distal coil is often hazardous. The balloon is placed distal to the PICA whenever possible. Obviously, definitive occlusion is performed only when the tolerance test with clinical and angiographic control in normal and hypotensive conditions is successful. In case of poor tolerance, the balloon is drawn back and placed more proximally. In the author's experience, it is always possible to find a place (even extracranial) where the occlusion is well tolerated.

Saccular aneurysms of the V A have the same presentation as aneurysms in other locations. However, VA aneurysms (like internal carotid artery aneurysms) are more commonly observed in women and are associated with fibromuscular dysplasia. Multiplicity is also a very common feature. Endovascular technique is the first choice if the angiographic appearance is suitable—that is, a narrow neck compared with the size of the aneurysm and the diameter of the parent vessel. Surgery was chosen in the author's experience when, with similar or lower risks, a major artery (VA or PICA) could be preserved by surgery but could not be by endovascular treatment. This is particularly true for VA-PICA junction aneurysms, where the endovascular material often cannot completely treat the lesion without stenosing or occluding the parent vessels.

For surgery, how distal the aneurysm is along the VA is the main point to consider. VA aneurysms proximal to the lateral side of the MO are easy to reach. On the contrary, distal aneurysms anterior to the MO raise much greater difficulties. In fact, the two most frequent locations are the VA-PICA junction and the VA-basilar junction. Aneurysms located on the intermediate segment are more likely to be dissecting aneurysms than saccular ones. The exposure is always done by the PLA with a variable degree of lateral enlargement. The more distal the aneurysm, the more lateral is the opening extension. For proximal aneurysms, the posterior arch is resected up to the lateral mass of the atlas, with little drilling of the condyle and lateral mass. For distal aneurysms, the VA is exposed up to the transverse foramen of the atlas and the bone opening is extended as far as the sigmoid sinus, with more drilling of the occipital condyle and lateral mass of the atlas. The dura is then opened by a paramedian vertical incision with three horizontal contraincisions: one at the lower and upper extremities and one toward the VA dural penetration. The dissection proceeds along the V A; with the PLA, the angle of work is quite lateral and there is no need to retract the neuraxis. Therefore, the main problem is the lower cranial nerves. VA-PICA aneurysms are most commonly located at the level at which the VA and the nerves cross, and thus nerve rootlets must be displaced superiorly or inferiorly to place the clip properly. To reach distal VA aneurysms, the surgeon must find the most appropriate access between the lower cranial nerves; the access is sometimes very easily found. However, in some cases, the surgeon has to deal with multiple rootlets and arterial branches; they must be dissected along their length from the brainstem to the jugular foramen so that they can be displaced upward or downward without stretching. Exposure of the aneurys-mal neck may raise some difficulties in VA-PICA forms in separating it from the PICA origin, and in VA-basilar trunk junction aneurysm if they point inferolaterally over the distal VA, thus hiding the neck. It is often very useful to perform selective distal angiography to anticipate the anatomic disposition and clip position. Fenestrated clips are often used to pass around the cranial nerves or the PICA.

Revascularization has very limited indications because, as previously mentioned, VA occlusion is usually very well tolerated and compensated for by the contralateral VA and by extracranial as well as intracranial anastomoses (1,6-9,16). Moreover, the need to sacrifice one VA is very rare because in most lesions, separation with preservation of the VA can be achieved. Among the lesions observed at the skull base (above C2), there was only one case of aneurysm at the Cl level requiring carotid artery-to-VA bypass (1). In addition to this case, the author's team did 42 distal VA revascularizations for proximal lesions, mostly atherosclerotic occlusive disease (N = 37) and few cases of aneurysm (N = 1), arteriovenous fistula (N = 1), dissection (N = 1), and tumor (N = 1 bilateral; Table 6).

	Treatment	
Lesion	Revascularization	Direct repair
Occlusion	30	—
Stenosis	7	—
Dissection	1	—
Aneurysm	2	1[a]
Arteriovenous fistula	1	1[b]
Tumor	1[c]	

[a] Plus arteriovenous fistula.
″ Plus aneurysm.
[c] Bilateral revascularization.

TABLE 6. *Vascular lesions of the vertebral artery*

MORTALITY AND MORBIDITY

With regard only to the technical problem of VA management, mortality and morbidity are very limited. The surgical approach, particularly the ALA, may produce some nerve dysfunction. The C2 spinal nerve root may be cut either proximally near the C1-2 VA segment or distally at the level of its subcutaneous branches. The resulting sensory deficit is usually very mild and restricted to a small area around the jaw angle and the earlobe. The sympathetic chain dissected at the suboccipital level produces a Homer's syndrome that resolves in few weeks. Dissection and, moreover, retraction of cranial nerve XI may induce pain and stiffness of the SCM muscle that generally do not last more than 1 or 2 months. Motor deficit of the SCM and trapezius muscles means there was too strong retraction of cranial nerve XI if there was no particular involvement by the lesion. The author observed 4 cases of painful stiffness, all regressive, and 2 cases of mild muscular deficit in his series of 60 cases using the ALA.

Control, mobilization, and transposition of the VA should not result in any particular complications because either the VA flow is preserved or its occlusion is anticipated by a balloon occlusion test. The author never observed any unintentional occlusion, even after VA transposition.

The total resection rate is 98% in the series of benign tumors and 92% in the malignant ones (including chordomas).

Therefore, control of the VA is a safe and reliable technique that greatly increases the surgeon's possibilities at the level of the craniocervical junction and in contiguous areas where the VA is a key anatomic structure.

REFERENCES

1. Matas R. Traumatisms and traumatic aneurysms of the vertebral artery, and their surgical treatment with report of a cured cases. *Ann Surg* 1893:18:477.
2. Henry AK. Exposures of long bones and other surgical methods. Cited in the author's book: *Extensive exposures* (Wright 1927). Edinburgh: Livingstone, 1966:58.
3. George B, Laurian C. *The vertebral artery: pathology and surgery.* Springer-Verlag: Wien, New York, 1987:258.
4. Chiari, 1829. Cited by Chassaignac EPM. *Traite clinique et pratique d'operations chirurgicales.* Vol. 1. Paris: Masson, 1861:334.
5. Maisonneuve JG, Favrot A. Observation de ligature de 1'artere vertebrale. *Journal ties Connaissances Medico-Chirurgicales* 1852; 11(2):181.
6. Carney AL. Vertebral artery surgery: historical development, basic concepts of brain hemodynamics, and clinical experience of 102 cases. *Adv Neural* 1981;30:249.
7. Clark K, Perry MU. Carotid vertebral anastomosis: an alternative technic for repair of the subclavian steal syndrome. *Ann Surg* 1956;1963: 414.
8. Corkill G, French BH, Michas C, Cobb CA, Mims TJ. External carotid vertebral artery anastomosis for vertebro-basilar insufficiency. *Surg Neural* 1977;7:109.
9. George B, Laurian C. Surgical possibilities on the third portion of the vertebral artery above C2. *Acta Neurochir (Wien)* 1979:28:263.
10. George B, Laurian C. Surgical approach to the whole length of the vertebral artery with special reference to the third portion. *Acta Neurochir (Wien)* 1980:51:259.
11. George B, Laurian C, Cophignon J, Rey A. Traitement des tumeurs en rapport avec 1'artere vertebrale dans sa portion transversaire. *Neurochirurgie* 1982:28:173.
12. George B, Laurian C, Keravel Y, Cophignon J. Extra-dural and hourglass cervical neurinomas: the vertebral artery problem. *Neurosurgery* 1985:16:54.

13. George B, Dematons C, Cophignon J. Lateral approach to the anterior portion of the foramen magnum. *Surg Neural* 1988;29:484.
14. George B, Laurian C. Impairment of VA flow caused by extrinsic lesions. *Neurosurgery* 1989;24:206.
15. Powers SR, Drislane TM, Kevins S. Intermittent vertebral artery compression: a new syndrome. *Surgery* 1961;49:257.
16. Spetzler RF, Hadley MN, Martin NA, et al. Vertebro-basilar insufficiency. Part 1: microsurgical treatment of extracranial vertebrobasilar disease. *J Neurosurg* 1987:66:648.
17. Francke JP, Dimarino V, Pannier M, Argenson C, Libersa C. Les arteres vertebrales: segments atlanto-axoidien V3 et intra-cranien V4 collaterales. *Anatomia Clinica* 1980;2:229.
18. Lasjaunias P, Moret J, Theron J. The so-called anterior meningeal artery of the cervical vertebral artery. *Neuroradiology* !978;17:51.
19. Tasi FY, Mahon J, Woodruff JV, Roach JP. Congenital absence of bilateral vertebral arteries with occipital basilar anastomosis. *AJR Am J Roentgenol* 1975;124:281.
20. Lasjaunias P, Theron J, Moret J. The occipital artery: Normal anatomy, arteriographic aspects, embryological significance. *Neuroradiology* 1978;15:31.
21. Ritter VH, Grossman K, Basche S, Heerklotz I, Schiffmann R, Schumann E. Die perkutane transluminale Angioplastik (PTA) von Aortenbogenasten. *Fortschrafl Rontgenstradiologie* 1982;136:365.
22. Rao TS, Sethi PK. Persistent Pro-atlantal artery with carotid vertebral anastomosis: case report. *J Neurosurg* 1975;43:499.
23. Hasegawa T, Kuboto T, Ito H, Yamamoto S. Symptomatic duplication of the vertebral artery. *Surg Neural* 1983;20:244.
24. Lasjaunias P, Braun .IP, Hasso AN, Moret J, Manelfe C. True and false fenestration of the vertebral artery. *J Neuraradiol* 1980;7:157.
25. Mizukami M, Tomita T, Mine T, Mihara H. By-pass anomaly of the vertebral artery associated with cerebral aneurysm and arteriovenous malformation. *J Neurosurg* 1972;37:204.
26. Rogers LA. Acute subdural hematoma and death following lateral cervical spinal puncture: case report. *J Neurosurg* 1983;58:284.
27. Djindjian R, Clay R, Hurth M, Vedrenne Cl. Etude clinique, arteriographique et anatomique d'un cas de malformation de lacharniere cervico-occipitale. *Presse Med* 1964:72:3013.
28. Djindjian R, Hurth M. L'arteriographie vertebrale dans les malformations de la charniere cervico-occipitale. *Ann Radial (Paris)* 1964;7:887.
29. Heerschaft H, Duus P. Die obstruierenden Erkrankungen der Arteria vertebralis in ihrer zervikalen Verlaufstrecke. *Folia Angiologica* 1972;20:22.
30. Janeway R, Toole JF, Leinbach LB, Miller HS. Vertebral artery obstruction with basilar impression: an intermittent phenomenon related to head turning. *Arch Neural* 1966;15:211.
31. Radojevic S, Negovanovic B. La gouttiere et les anneux osseux de 1'artere vertebrale de Fatlas. *Acta Anat* 1963;55:186.
32. Lasjaunias P, Guilbert-Tranier F, Braun JP. The pharyngo-cerebellar artery or ascending pharyngeai artery origin of the PICA../ *Neuroradiol* 1981;8:317.
33. Franckhauser H, Kamano S, Hanmura T, Amano K, Hatnaka H. Abnormal origin of the PICA: case report. *J Neurosurg* 1979;51:569.
34. Margolis MT, Newton TH. Borderlands of the normal and abnormal PICA. *Acta Radiologica: Diagnosis* 1972; 13:163.
35. Lazorthes G, Gouaze A, Santini JJ, Lazorthes Y, Laffont J. Le modelage du polygone de Willis: role des compressions des voies arterielles d'apport dans les mouvements de la colonne cervicale et de l'extremite cephalique. *Neurochirurgie* 1971 ;17:361.
36. Schneider RC, Gosch HH, Taren JA. Blood vessel trauma following head and neck injuries. *Clin Neurosurg* 1972;19:312.
37. Schneider RC, Crosby EC. Vascular insufficiency of brain stem and spinal cord in spinal trauma. *Neurology (Minneapolis)* 1959:9:643.
38. Toole JF, Tucker SH. Influence of head position upon cerebral circulation. *Arch Neural* 1960;2:616.
39. George B, Lot G, Velut S. Tumors of the foramen magnum. *Neurochirurgie* 1993;39:1.
40. George B, Lot G. Anterolateral and posterolateral approaches to the foramen magnum: technical description and experience from 97 cases. *Skull Base Surgery* 1995;5:9.
41. George B, Lot G. Foramen magnum meningiomas: a review from personal experience of 37 cases and from a cooperative study of 106 cases. *Neurosurgery Quarterly* 1995;5:149.
42. George B, Lot G. Neurinomas of the two first cervical nerve roots: a series of 42 cases. *J Neurosurg* 1995:82:917.
43. George B. Meningiomas of the foramen magnum. In: Schmidek HH, ed. *Meningioma and their surgical management.* Philadelphia: WB Saunders, 1991:459.
44. Bertalanffy H, Seeger W. The dorsolateral, suboccipital, transcondylar approach to the lower clivus and anterior portion of the craniocervical junction. *Neurosurgery* 1991:29:815.
45. Spetzler RF, Graham TW. The far lateral approach to the inferior clivus and upper cervical region: technical note. *BNl Quarterly* 1990;6:35.
46. Sen C, Sekhar LN. An extreme lateral approach to intradural lesions of the cervical spine and foramen magnum. *Neurosurgery* 1990;27:197.
47. George B, Zerah M, Lot G, Hurth M. Oblique transcorporeal approach to anteriorly located lesions in the cervical spinal canal. *Acta Neurochir (Wien)* 1993;121:187.
48. George B, Lot G, Tran Ba Huy P. The juxta-condylar approach to the jugular foramen (without petrous bone drilling). *Surg Neural* 1995:44:279.
49. Fisch LI. Infratemporal fossa approach for glomus tumours of the temporal bone. *Ann Otol Rhinol Laryngol* 1982;91:474.
50. Reizine D, Laouti M, Guimaraens L, Riche MC, Merland JJ. Vertebral arteriovenous fistulas: clinical presentation, angiographical appearance and endovascular treatment. A review of twenty-five cases. *Ann Radial (Paris)* 1985;28:425.
51. Vinchon M, Laurian C, George B, D' Arrigot G, Reizine D, Ayrnard A. Vertebral arteriovenous fistulas: a study of 49 cases and review of the literature. *Cardiovasc Surg* 1994;2:359.

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 28

Lesions of the Sella Turcica ☐

Andrew E. Sloan, Keith A. Black, and Donald P. Becker

The treatment of sellar lesions is one of the more challenging and satisfying aspects of skull base surgery. The wide variety of lesions that occur in this region and the complexity of their treatment necessitates a thorough understanding of sellar anatomy, as well as the clinical symptoms and diagnostic evaluation of the myriad disease processes involving the pituitary gland.

ANATOMY

Sphenoid Bone and Sella Turcica

The sphenoid bone is located at the base of the skull, posteroinferior to the anterior cranial fossa and anterior to the temporal and occipital bones (Fig. 1). The sella itself is a midline depression in the mid-portion of the sphenoid bone. It is bounded anteriorly and inferiorly by the sellar floor, anterolaterally by the anterior clinoid process, laterally by the cavernous sinuses, posteriorly by the dorsum sellae and the posterior clinoid processes, and superiorly by the diaphragma sellae. The floor of the sella is lined with an endocranial layer that is continuous with the diaphragma sellae superiorly, and contains the intercavernous or circular sinuses. These are highly variable, but typically develop in the anterosuperior and posterosuperior regions of the sella. The cavernous sinuses drain into the basilar venous plexus posterior to the dorsum sellae along the upper clivus, which joins the superior and inferior petrosal sinuses.

The sphenoid sinus is just anterior and inferior to the sella, and is divided by one or more vertical septa that are often asymmetric (Fig. 2). The degree of pneumatization of the sphenoid sinus varies among individuals and is classified as conchal, parasellar, or sellar (1,2) (Fig. 3). The sellar type is well pneumatized beneath the entire sella, which bulges into the sinus and is found in 70% to 86% of adults. The presellar sphenoid sinus extends only to the mid-portion of the sella, has no sphenoid bulges, and is found in 11 % to 24% of adults. The conchal sphenoid sinus has minimal pneumatization and at least 10 mm of bone between the undeveloped sphenoid sinus and the sella turcica. This configuration is common in prepubertal children, but occurs in only 3% of adults.

Nasal Cavity

The nasal cavity provides access to the sphenoid sinus for transsphenoidal approaches. The most important anatomic features for the surgeon are the medial structures comprising the anterior septum that support the nose. These consist of the septal cartilage ventrally and superiorly, the vomer posteriorly and inferiorly, and the perpendicular plate of the ethmoid (Fig. 4).

Pituitary Gland and Hypothalamus

The pituitary gland resides in the sella turcica and is attached to the hypothalamus by the pituitary stalk. The stalk enters the sella through an opening in the diaphragma sellae, a membrane of basilar dura stretched between the tubercu-lum sellae and the posterior clinoids that separates the cranium from the sella. A small outpouching of the arachnoid accompanies the stalk through the central opening in the diaphragma in about 50% of specimens, to form a small pituitary cistern anterosuperior to the adenohypophysis (3). This is a potential source of cerebrospinal fluid (CSF) leak in the transsphenoidal approach to sellar lesions.

A. E. Sloan: Division of Neurosurgery, Wayne State University, Detroit Medical Center, and The Karmanos Cancer Institute, Detroit, Michigan 48201.
K. A. Black: Department of Surgery, Cedars-Sinai Medical Center, Los Angeles, California 90048.
D. P. Becker: Division of Neurosurgery, University of California, Los Angeles Medical Center, Los Angeles, California 90095-7039.


Jugum sphenoidale
Chiasmic groove
Optic canal
Superior orbital fissure
Lesser wing
Foramen rotundum
Greater wing
Foramen ovale
Anterior clinoid process
Foramen spinosum
Posterior clinoid process

FIG. 1. Anatomy of the sphenoid bone.



FIG. 2. Variations in the septation of the sphenoid sinus. **A:** Midline vertical septum. **B:** Dual vertical septum. **C:** Oblique. **D:** Honeycomb pattern.


Conchal
A
Presellar
C
Sellar
B

FIG. 3. Degree of pneumatization of sphenoid sinus. A: Chonchal. B: Presellar. C: Sellar.


Quadrangular cartilage
Perpendicular plate of ethmoid bone
Sphenoid sinus
Vomer

FIG. 4. Anatomy of the nasal septum: anatomic relationship between the vomer, perpendicular plate, and quadrangular cartilage.



FIG. 5. A,B: Differential concentration of cell types in the pituitary gland.

The pituitary is composed of two lobes, distinct in embryologic origin, structure, and function, which come together during embryogenesis. The adenohypophysis is yellowish in color, and has a relatively firm consistency. It arises from the primitive stomodeum as Rathke's pouch, which grows toward the neural tube to form the craniopharyngeal duct. The anterior portion of Rathke's pouch develops into the pars distalis, the functional portion of the anterior pituitary. A thin sleeve of tissue derived from the adenohypophysis extends upward along the pituitary stalk to form the pars tuberalis, which rises a short distance above the diaphragma sellae. The posterior wall of Rathke's pouch develops into the intermediate lobe, a cystic structure, vestigial in function, lined by ciliated, mucus-producing adenohypophyseal cells. Although the adenohypophysis is uniform in structure., the cells are differentially concentrated in three regions. The cells in the central "mucoid wedge" produce thyroid-stimulating hormone (TSH) anteriorly and adrenocorticotropic hormone (ACTH) posteriorly, and are basophilic (Fig, 5). Some of these ACTH-producing cells invaginate the posterior pituitary with increasing age, a phenomenon known as "basophilic invasion." The cells of the lateral "acidophilic wings" produce primarily the peptide growth hormone anteriorly and prolactin posteriorly. Gonadotropic cells producing luteinizing hormone and follicle-stimulating hormone are located diffusely throughout the gland.

The adenohypophysis is vascularized predominately by the superior hypophyseal artery by way of the hypophyseal portal system (Fig, 6). This venous plexus originates in the anterior inferior portion of the hypothalamus and the floor of the third ventricle, where capillaries with a specialized fenestrated epithelium arise from branches of the superior hypophyseal arteries. These capillaries are associated with the terminals of the tuberoinfundibular neurons, which synthesize the hypothalamic-releasing hormones and secrete them into the capillary network. These vessels drain into the hypothalamic portal veins, which descend to the adenohypophysis along the anterior portion of the stalk, giving it a striated appearance. In the adenohypophysis, the portal veins develop into a second capillary network that supplies the secretory cells of the adenohypophysis and drains into the cavernous sinus.

The neurohypophysis, or posterior lobe, appears gray in color and has a soft, gelatinous consistency. It arises from the median eminence, a downpouching in the floor of the third ventricle. The upper portion becomes the pituitary stalk, whereas the distal end fuses anteriorly with the adenohypophysis and remnants of the craniopharyngeal duct and becomes the neurohypophysis. The stalk comprises unmyelinated axons from the tuberoinfundibular neurosecretory neurons of the supraoptic and par a ventricular nuclei of the hypothalamus, which transport granules of vasopressin and oxytocin synthesized by these neurons to the posterior pituitary. These granules are stored in the nerve terminals of the neurohypophysis until released by action potentials generated in the cell bodies of the hypothalamic nuclei. The neurohypophysis is vascularized primarily by the inferior hypophyseal arteries, although the portal vessels also form some anastomoses with capillaries of the neurohypophysis.

Parasellar Structures

Parasellar structures include the optic nerve and chiasm: the internal carotid artery and its branches; the cavernous sinus and the cranial nerves contained within it; and the medial temporal lobes (Fig. 7). Symptoms and signs of sellar and parasellar lesions are often the result of involvement of these structures. The optic chiasm overlies the diaphragm in about 80% of people. The remainder are equally split between prefixed chiasms overlying the tuberculum sellae and postfixed chiasms overlying the dorsum sellae. The cavernous sinuses are lateral to the sella, and contain the carotid artery and the sixth cranial nerve suspended by fibrous trabecula. The third and fourth cranial nerves, and the ophthalmic and maxillary divisions of the trigeminal nerve, lie within the lateral walls of the cavernous sinus.


Optic chiasm
Superior hypophyseal artery
Primary portal system
Long hypophyseal veins
Anterior lobe
Posterior lobe
Efferent veins (to cavernous sinus)
Inferior hypophyseal artery

FIG. 6. Vascular supply of the infundibulum and pituitary gland.


II
Sphenoid sinus
Middle fossa
1CA
Cavernous sinus
Dorsum sella
III
IV
VI
V

FIG. 7. Relationship of sellar and parasellar structures in cross-section.

TABLE 1. *Differential diagnosis of sellar and parasellar masses*

Neoplastic lesions
Pituitary neoplasms
  Pituitary adenomas
  Pituitary carcinomas
  Granular cell tumors
Nonpituitary neoplasms
  Craniopharyngiomas
  Meningiomas
  Chordomas
  Dermoid cysts
  Epidermoid cysts
  Germinomas
  Teratomas
  Lipomas
  Melanomas
  Metastases
Nonneoplastic lesions
Cysts
Rathke's cleft cysts
Mucoceles Arachnoid
cysts
Inflammatory and infectious lesions
Lymphocytic hypophysitis Sarcoidosis
Giant cell granulomas
Langerhans' cell histiocytosis (histiocytosis X)
Abscesses **Vascular lesions** Aneurysms
Carotid cavernous fistulas
Cavernous angiomas

PATHOLOGY

The close apposition of neural, endocrine, vascular, and meningeal tissue in the confined region of the sella gives rise to a large number of pathologic entities. Many of these are listed in Table 1. A complete pathologic description of each of these lesions, many of which are rare, is beyond the scope of this chapter. The pituitary adenoma and the craniopharyngioma, the most common sellar lesions, are discussed in detail. Other common neoplastic, cystic, inflammatory, and infectious lesions are addressed only briefly.

Neoplastic Lesions

Pituitary Adenomas and Carcinomas

Pituitary adenomas are the most common sellar neoplasm, accounting for 15% of all intracranial tumors. The annual incidence of these lesions is about 15 per 100,000 population (4). It is likely, however, that these symptomatic adenomas represent only a fraction of the true incidence of these neoplasms, because their prevalence in unselected autopsies is 22.5% (5). The highest incidence occurs in the third to sixth decades of life. Statistically, there appears to be an increased incidence in premenopausal women, though many contend that this is merely because of the sensitivity of the menstrual cycle to the relatively minimal endocrinologic imbalances often produced by these neoplasms. The symptoms produced in men are far less conspicuous and often ignored.

RADIOLOGICAL CLASSIFICATION OF PITUITARY TUMORS



*J. Hardy and J.L. Vezina[19] "As suggested by C.B. Wilson

FIG. 8. Radiologic classification of sellar neoplasms. (From ref. 59, with permission.)

Pituitary adenomas have been classified by radiologic appearance, clinical presentation, and pathologic characteristics. The radiologic classification, known as the Hardy classification, distinguishes adenomas based on size and gross pathoanatomic relationships (6) (Fig. 8; Table 2). Adenomas 10 mm or less in diameter are classified as microadenomas; those greater than 10 mm as macroadenomas. Other investigators have classified adenomas greater or equal to 40 mm in diameter, or ascending to within 5 mm of the foramen of Monroe as giant adenomas (7). Although the original classification was based on lateral skull tomograms, these have been supplanted by computed tomography (CT) and magnetic resonance imaging (MRI) without formally altering the classification scheme.

Microadenomas are classified as being grade O or I depending on the presence of sellar bulging. Macroadenomas are graded from II to IV based on the degree of sellar enlargement and destruction. Macroadenomas are further staged A to E according to the degree of suprasellar and extrasellar extension. This classification scheme has proven useful in surgical planning and correlates with operative risk and outcome (8).

Pituitary adenomas can be classified clinically in accordance with symptomatic endocrinologic activity. Endocrinologically active adenomas are those that produce and release endocrinologically active anterior pituitary hormones such as prolactin, growth hormone, ACTH, and TSH. These typically present with symptoms of endocrinopathy. In contrast, endocrinologically inactive adenomas either fail to produce hormone (i.e., null cell adenomas); produce hormone that is inadequately secreted (i.e., a-subunit only [9]) or biologically inactive (i.e., silent corticotropic adenomas); or fail to produce symptoms (i.e., follicle-stimulating hormone or luteinizing hormone in male patients).

TABLE 3. *Pathologic classification of pituitary adenomas*

Prolactin cell adenomas
Growth hormone cell adenomas
Mixed prolactin cell-growth hormone cell adenomas
Acidophilic stem cell adenomas
Mammosomatotropic cell adenomas
Corticotropic cell adenomas
Gonadotropic cell adenomas
Thyrotropic cell adenomas
Plurihormonal adenomas
Null cell adenomas

Pathologic grading schemes for pituitary adenomas originally used cytoplasmic staining affinities to distinguish tumor subtypes. More recent studies have demonstrated, however, that cytoplasmic staining affinities correlate not only with the contents of the secretory granules, but with their density. The classification scheme currently in use uses immunohistochemistry, supported in some cases by ultrastructural morphology, to classify adenomas into 10 types based on the storage and secretion of granules filled with pituitary hormones (10) (Table 3).

The invasiveness of adenomas has been classified radiographically, surgically, and histologically. Although radiologic and gross surgical invasiveness appear to correlate with poor outcome, there appears to be no correlation between microscopic dural invasion, ploidy, mitotic index, and the aggressiveness of these neoplasms, which occasionally invade locally into bone, vessels, dura, or the brain (11).

TABLE 2. *Classification of pituitary adenomas*

	Radiologic	Anatomic	Surgical
	Sella Turcica		
Grade 0	Intact, normal contour	**Micro**	**Enclosed**
Grade I	Intact, focal bulging		
Grade II	Intact, enlarged	**Macro**	
Grade III	Destroyed, partially		***Invasive***
Grade IV	Destroyed, totally		
(Grade V)	(Distant spread through cerebrospinal fluid or blood)		
	Extrasellar Extension		
	Suprasellar (symmetric)		
	A. Suprasellar cistern		
	B. Recesses third ventricle		
	C. Whole anterior third ventrical		
	Parasellar (asymetric)		
	D. Intracranial–intradural		
	Anterior		
	Midline		
	Posterior		
	E. Extracranial–extradural (lateral cavernous)		

From ref. 59, with permission.

Carcinoma of the pituitary is extremely rare, and impossible to diagnose based on histologic features alone. It is thought to arise from pituitary adenomas of all types and is defined as Hardy grade V by distant spread through blood or CSF. These tumors typically present with multiple local recurrences followed by metastatic dissemination to the subarachnoid space or extraneuronal sites such as bone, liver, lymph node, lung, or kidney.

Primary Neoplasms of the Posterior and Intermediate Lobes of the Pituitary

The neurohypophysis is rarely the site of clinically significant primary neoplasms. The most common of these is the granular cell tumor, also referred to as choristoma. The histogenesis of these lesions is uncertain, but they are found in 6.8% to 17% of pituitary glands of asymptomatic people at autopsy (12), and may also occur in the stalk. They most often present in the fifth decade of life. Gliomas, gangliocytomas, and hamartomas of the neurohypophysis are extremely rare (13).

Craniopharyngiomas

Craniopharyngiomas comprise 1% to 3% of intracranial tumors. They most commonly present as suprasellar masses, although approximately 20% are primarily intrasellar, and they are the most frequent parasellar lesions of children and adolescents and the second most common sellar lesions in adults. They are thought to be derived from cell rests of the intermediate lobe that arise from remnants of Rathke's pouch and are typically filled with a viscous fluid, rich in lipid and cholesterol, grossly resembling motor oil. They are frequently calcified and surrounded by intense gliotic reaction.

Meningiomas

Meningiomas are the third most common sellar lesions, comprising 1 % to 3% of lesions in this region (14). Peak incidence of meningiomas is between 40 and 50 years of age, and women outnumber men by fourfold or more. Purely intrasellar meningiomas are rare (15). More commonly, meningiomas arising at the tuberculum sellae, medial sphenoid wing, olfactory groove, diaphragma sellae, or cavernous sinus invade the sellar and parasellar structures.

Chordomas

Chordomas are slowly growing, expansile, extradural neoplasms thought to arise from notochordal remnants. Median age at presentation is 45 years, and there is a slight male predominance. About 40% arise in the skull base, and of these, 33% involve the sellar or parasellar region (16). These tumors typically originate in the clivus and erode through the posterior clinoids and dorsum sellae into the sella and sphenoid sinus. Primary sellar lesions also occur (16,17). Metastatic dissemination is a late occurrence in 10% to 20% of cases.

Other Primary Neoplasms

Gliomas of the optic nerve and chiasm, germ cell tumors, and hamartomas also occur in the parasellar region and should be considered in the differential diagnosis of sellar lesions, particularly in children. Epidermoid and dermoid cysts comprise approximately 1% and 0.1%, respectively, of all intracranial neoplasms, and occasionally present as sellar lesions in adults.

Metastatic Neoplasms of the Sella

The sella is a common site of systemic metastasis. Gross evidence of sellar metastasis occurs in 1 % to 10% of patients dying of systemic cancer (10), although microscopic analysis reveals an incidence approaching 27% (18,19). However, sellar metastases usually occur in the context of advanced systemic disease and are rarely symptomatic (20). The most common manifestation of metastatic disease is osseous involvement of the sella. Metastatic deposits also occur in the pituitary gland and neurohypophysis, but two thirds of these result from contiguous spread. Hematopoietic metastases commonly arise as meningeal lesions, particularly in non-Hodgkin's lymphoma (21).

Nonneoplastic Lesions

Cysts

Benign cysts of the pituitary are identified in 13% to 23% of routine autopsies (22). These include Rathke's cleft cysts, mucoceles, and arachnoid cleft cysts.

Rathke's cleft cysts are epithelial cysts derived from the remnants of Rathke's pouch. Although the involution of the craniopharyngeal duct is usually accompanied by the involution of Rathke's pouch, persistent, discontinuous, cystic remnants of the intermediate lobe are common. These usually are not large enough to be symptomatic. Those that are. presumably grow by progressive accumulation of their colloidal content. They are typically lined with cuboidal epithelium, but cysts lined with squamous epithelium indistinguishable from craniopharyngioma have also been described. They present over a wide range of ages and have no gender predilection.

Mucoceles are epithelial cysts arising from the paranasal sinuses. They are histologically indistinguishable from Rathke's cleft cysts, and differentiation relies on anatomic evidence of extension from a paranasal sinus obtained radiologically or at surgery.

Arachnoid cysts consist of distended areas of arachnoid filled with CSF that occasionally become symptomatic because of mass effect. They can be sellar, suprasellar, or both. Their pathogenesis is unclear: some believe them to be congenital, whereas others contend they are acquired.

Inflammatory and Infectious Lesions

Inflammatory Lesions

The most common inflammatory lesions of the pituitary are lymphocytic hypophysitis, Langerhans' cell histiocytosis, giant cell granuloma, and sarcoidosis. Lymphocytic hypophysitis is a destructive inflammatory process affecting the anterior pituitary that is presumed to be an autoimmune phenomenon. It occurs mainly in women, either during pregnancy or in the first postpartum year, and is often associated with autoimmune diseases of other endocrine glands. It also occurs in older patients of both genders (23).

Langerhans' cell histiocytosis, formerly known as histiocytosis X, consists of a group of poorly understood eosinophilic granulomatous disorders that may be localized or diffuse. Involvement of the central nervous system in patients with disseminated disease is not uncommon, although isolated lesions of the sella are extremely rare (13,24). These granulomas appear to have a predilection for the stalk and adenohypophysis; the posterior pituitary is usually spared.

Giant cell granuloma and sarcoidosis are also granulomatous lesions. Giant cell granulomas are noncaseating granulomas of the adenohypophysis and infundibular stalk. They are typically multiple and have neither a sexual predilection nor an association with pregnancy (25). Sarcoidosis of the central nervous system occurs in 5% of patients with systemic sarcoidosis. Although neuritis is the most common presentation, inflammation of both the anterior and posterior lobes of the pituitary, as well as the stalk and hypothalamus, also occurs in about 1% of patients (26).

Infectious Lesions

Infection of sellar structures occurs only rarely. Bacterial abscesses may arise hematogenously or by secondary extension from an anatomically contiguous focus. Acute sphenoid sinusitis or osteomyelitis are the most likely niduses for contiguous spread. The most frequent organisms are *Staphylococcus aureus, Streptococcus pneumoniae,* group A *Streptococcus,* and *Klebsiella (21).* There seems to be a predilection for abscesses to occur in the bed of a preexisting sellar lesion such as pituitary adenoma or craniopharyngioma (28). Tuberculosis, still endemic to certain areas, typically involves the sella in a dense, basilar meningitis, with or without arteritis. Intrasellar tuberculomas are usually associated with systemic tuberculosis and can result in pituitary destruction. Aspergillosis may also present with an inflammatory sellar mass (29), as can parasitic diseases such as cysticercosis (30) or echinococcosis (31).

Vascular Lesions

Aneurysms of the sellar region usually derive from the infraclinoid or intracavernous carotid artery. They are readily diagnosed by MRI and mentioned here merely as a diagnostic consideration to be excluded.

CLINICAL PRESENTATION

Patients with sellar lesions present with a myriad of symptoms and signs. These can be classified as general or specific.

General Symptoms and Signs

The general symptoms and signs produced by sellar lesions result from mass effect, which stretches or compresses the densely packed neurovascular structures of the sella. These structures include the internal carotid artery and its proximal branches; the optic nerve, chiasm, and tracts; the pituitary gland; the infundibular stalk; the hypothalamus; the cavernous sinus and the cranial nerves within; the frontal and medial temporal lobes; the pons and midbrain; and the ventricular system.

Visual Manifestations

The most common manifestation of sellar or parasellar lesions in adults is visual impairment. Chiasmal compression produces a deficit of the bilateral superior temporal visual quadrant initially, followed by involvement of the inferior temporal quadrant. A junctional scotoma consisting of ipsilateral central scotoma with a contralateral superior temporal quadrantanopsia may also be produced by involvement of optic nerve fibers crossing into the chiasm at acute angles (Von Willebrand's knee). Further compression may lead to irreversible chiasmal damage, resulting in total blindness. Isolated compression of the prechiasmal optic nerve results in an afferent pupillary defect known as Marcus Gunn's sign.

Hypothalamic and Pituitary Dysfunction

Compression of the hypothalamus may lead to dysregulation of pituitary secretion as well as a myriad of other physiologic processes regulated by the hypothalamus. These include water balance, body temperature, level of consciousness, and behavior.

Compression of the median eminence or infundibular stalk may result in the impairment of synthesis of hypophysiotropic hormones or their transport to the pituitary gland itself. This results in varying degrees of hypopituitarism as well as diabetes insipidus. By interfering with the transport of dopamine—the predominant prolactin-inhibiting factor— to the lactotrophs, stalk compression also produces a paradoxical mild to moderate hyperprolactinemia (typically

30-150 ng/ml). This may present as hypogonadism or galactorrhea in women or men.

Compression of the pituitary gland itself also commonly results in hypopituitarism. The clinical symptoms depend on the cell types affected, and the degree of hyposecretion. The gonadotrophs are the most vulnerable and are usually affected first, leading to amenorrhea or oligomenorrhea in women, gonadal atrophy in men, and loss of libido in both sexes. Thyrotrophs and somatotrophs are usually affected next. Corticotrophs have the greatest functional reserve, and addisonian symptoms of nausea, vomiting, and postural hypotension usually present only in severe panhypopituitarism.

Cavernous Sinus Involvement •

Sellar lesions extending into the cavernous sinus may involve the third, fourth, and sixth cranial nerves, resulting in partial or complete ophthalmoplegia. This is more commonly found in meningiomas than pituitary adenomas or craniopharyngiomas. The oculomotor nerve is the most commonly affected nerve in the cavernous sinus, followed by the abducens and trochlear nerves. Involvement of the first two branches of the trigeminal nerve results in numbness or pain in these distributions.

Headache

Headache results from stretching or compressing the dura of the diaphragma sellae, tentorium, cavernous sinus, or the base of the skull, all of which are innervated by the first division of the trigeminal nerve. Other mechanisms by which sellar lesions produce headache are inflammation or pressure on other pain-sensitive dural structures, and elevated intracranial pressure due to mass effect or obstructive hydrocephalus.

Hydrocephalus

Sellar lesions with significant suprasellar extension may obstruct the foramen of Monro, producing unilateral or bilateral obstructive hydrocephalus. This may result in headache, papilledema, and decreased levels of consciousness. Stretching of the sixth cranial nerve may also produce an abducens palsy.

Cortical Involvement

Sellar lesions with significant suprasellar or parasellar extension may compress adjacent brain. Usually, slow-growing lesions reach large size before becoming symptomatic. Compression of the frontal lobes produces personality change and memory loss, whereas temporal compression or irritation may induce seizure.

Apoplexy

Pituitary apoplexy is a clinical manifestation of hemorrhage or infarction of a pituitary adenoma. The syndrome is characterized by the acute onset of severe headache and meningismus, often accompanied by nausea and vomiting. Partial or complete ophthalmoplegia is common, and a decreased level of consciousness may also occur. This clinical emergency results from the acute onset of mass effect on parasellar structures such as the optic chiasm or the cavernous sinus. This occurs in about 1% to 2% of pituitary adenomas and appears to be more frequent in clinically nonfunctional macroadenomas.

Specific Symptoms and Signs

Specific symptoms and signs may be diagnostic of certain endocrinologically active pituitary adenomas.

Prolactinomas

Prolactinomas account for about 30% to 40% of all pituitary adenomas and are the most commonly encountered endocrinologically active adenomas. They present differently in men and women. Women present threefold more frequently than men and complain of oligomenorrhea or amenorrhea, often with infertility and galactorrhea. They are typically 20 to 30 years of age and have microadenomas with moderately elevated prolactin levels (>200 ng/ml). In contrast, men typically present between 40 and 50 years of age, with general symptoms of mass effect. Men often harbor invasive macroadenomas with significantly higher prolactin levels. They often admit to decreased libido or impotence, but rarely present with this as a chief complaint. Galactorrhea also occurs occasionally in men.

Growth Hormone-Secreting Adenomas

Excess growth hormone due to pituitary adenoma results in giganticism if manifested in childhood before fusion of the epiphysis of the long bones. In adults, these tumors present with acromegaly, resulting in gross enlargement of soft tissues of the face and the extremities. Bone density also increases, resulting in degenerative joint disease, spinal stenosis, and compressive neuropathies. Acromegaly is also associated with systemic illness, including brittle diabetes, hypertension, severe atherosclerosis, and organomegaly. Poorly understood respiratory disease and cardiomyopathy result in decreased life expectancy for these patients.

Adrenocorticotropic Hormone-Secreting Adenomas

Hypercortisolism, or Gushing's syndrome, results in a myriad of clinical features, including moon facies, centripetal obesity, "buffalo hump," hirsutism, abdominal striae, poor wound healing, frequent infections, atrophy, weakness, acne, oligomenorrhea, amenorrhea, and behavioral changes. Associated metabolic disturbances include impaired glucose tolerance, hypertension, left ventricular hypertrophy, anasarca, hypokalemia, osteoporosis, erythrocytosis, immunosuppression, and eosinophilia. These conditions are severe and usually fatal if the condition is untreated.

Unlike the aforementioned endocrinopathies, which are essentially pathognomonic for pituitary adenomas, Gushing's syndrome has several possible etiologies. Gushing's disease, defined as hypercortisolism due to an ACTH-producing pituitary adenoma, accounts for only 60% of cases of Cushing's syndrome (32). Nearly 25% of cases of Cushing's syndrome result from primary cortisol hypersecretion by adrenal adenoma or carcinoma, whereas 15% of cases are due to ACTH secretion from ectopic sources, including bronchogenic carcinoma, carcinoid tumors, and pancreatic tumors (32,33). latrogenic and factitious hypercortisolism also occur.

Nelson's syndrome is an iatrogenic condition caused by unopposed growth of an ACTH-secreting pituitary adenoma after bilateral adrenalectomy. Patients typically are hyperpigmented, with characteristic copper-colored skin and advanced symptoms and signs of Cushing's disease. Often, they have manifestations of mass effect as well. The incidence of Nelson's syndrome has declined because of recognition of the pathophysiology of this morbid condition, as well as improved diagnosis and treatment of Cushing's disease.

Thyroid-Stimulating Hormone-Secreting Adenomas

Thyroid-stimulating hormone-secreting adenomas are extremely rare, accounting for less than 1% of pituitary adenomas (34). Patients present with clinical symptoms of hyperthyroidism, and typically have microadenomas (35). As with Cushing's syndrome, other etiologies must be excluded before making this diagnosis.

DIAGNOSTIC EVALUATION

Because of the close approximation of structures influencing neurologic, endocrine, and visual function in the sellar region, the evaluation of patients suspected of having a sellar mass is best approached as an interdisciplinary effort. Guided by findings obtained during the clinical evaluation, the diagnostic process begins with the determination of an anatomic diagnosis and an endocrine diagnosis.

Radiologic Evaluation

Magnetic Resonance Imaging

The superior anatomic resolution of gadolinium-enhanced MRI has made it the imaging modality of choice in the evaluation of sellar lesions. High-resolution, multiplanar MRI can routinely detect lesions as small as 3 mm in diameter. MRI also gives excellent resolution of the critical spatial relationships between the sellar lesion, normal gland, and surrounding cisterns and neurovascular structures. The relative positions of the carotid arteries, chiasm, infundibulum, pituitary remnant, hypothalamus, and the third ventricle relative to the lesion are particularly important. These features enable the clinician precisely to determine the location of the lesion, and thus facilitate the differential diagnosis. Moreover, the extent of suprasellar and parasellar extension, the relative position of the chiasm, and the degree of pneumati-zation of the sphenoid sinus are critical in planning the operative approach, if surgery is indicated.

The soft tissue imaging characteristics of MRI also help the clinician narrow down the diagnostic possibilities in the evaluation of sellar lesions. For example, the characteristic appearance of an aneurysm on MRI enables this diagnostic possibility to be immediately included or excluded in most cases. Likewise, the appearance of a "dural tail" may be strongly suggestive of a meningioma.

Computed Tomography

Although MRI provides better anatomic resolution of soft tissues, high-resolution CT, with or without image reconstruction, remains superior to MRI in the resolution of bony anatomy. Thin-section (1.5-mm) cuts with coronal and axial reconstruction are useful for evaluating the thickness of the sellar floor, the presence of hyperostosis or bony destruction, pneumatization of the sphenoid sinus, and the position of sphenoid septa. CT is also superior to MRI in detecting dystrophic calcification, making it valuable diagnostically as well as for planning the surgical approach. Contrast-enhanced CT is also critical in the evaluation of patients with contraindications to MRI imaging, such as the presence of ferromagnetic foreign bodies in the form of aneurysm clips, pacemakers, or cochlear implants.

Skull Radiography

Lateral skull radiography has been largely supplanted by MRI and CT. Although it does not provide additional information, it is more readily obtained than MRI or CT, and thus useful for specific indications. These include intraoperative imaging and the serial evaluation of pneumocephalus in the postoperative setting.

Angiography

Although angiography was once essential in the work-up of sellar lesions for evaluating mass effect and excluding the presence of sellar aneurysms, this function has been largely supplanted by MRI and magnetic resonance angiography.

Angiography is now indicated only rarely for the immobilization of particularly vascular lesions, and for petrosal sinus sampling in the evaluation of Gushing's syndrome.

Metrizamide Cisternography

Cisternography, once routinely used for imaging, has also been replaced by high-resolution CT and MRI. The only remaining indication for this technique is the evaluation of CSF rhinorrhea.

Ophthalmologic Evaluation

A complete neuroophthalmologic evaluation should be obtained in all patients with visual symptoms or signs, as well as any patient with lesions that have extrasellar extension. Visual acuity and perimetry are formally assessed, and the presence of optic atrophy and visual field deficits is documented. These examinations may then be performed serially to document the course of the disease and the response to treatment.

Endocrinologic Evaluation

Every patient with a suspected or known sellar lesion should have an initial endocrine screening examination. This should include measurements of baseline levels of plasma electrolytes and osmolarity as well as prolactin, growth hormone, cortisol, ACTH, luteinizing hormone, follicle-stimulating hormone, a-subunit, thyroxine, and TSH. This allows the clinician to evaluate the integrity of the various hypotha-lamic-pituitary-target organ axes. Further provocative testing or special hormone assays designed to diagnose particular endocrinopathies may then be indicated for further evaluation (36).

SURGICAL APPROACHES TO THE SELLA

Management options for sellar lesions include observation, surgery, pharmacologic treatment, and radiation therapy. The decision to operate should be based on the patient's clinical diagnosis, age, medical condition, and prognosis. In patients with endocrinopathies, the diagnosis can often be made based on history and clinical findings combined with laboratory and radiologic tests consistent with acromegaly, Gushing's disease, or marked hyperprolactinemia, as noted previously. In many cases, however, definitive diagnosis itself requires a surgical specimen.

Approaches to the sella can be classified as extracra-nial-extradural and transcanial-intradural. The choice of approach depends on the clinical diagnosis, the relationship between the lesion and the critical juxtasellar structures, and

продолжение

the goals of surgery (Fig. 9). In most cases, the transsphe-noidal procedure, an extradural approach, is the treatment of choice because of its simplicity and safety. Transsphenoidal surgery offers excellent sellar exposure and enables the surgeon to remove the lesion while preserving normal gland, which is rarely possible with the transcranial approach. Transsphenoidal surgery is faster, with equal chiasmal decompression equal to, and endocrine preservation superior to, that obtained with transcranial surgery (8,37^40). Moreover, transsphenoidal surgery has a lower morbidity and mortality than transcranial surgery, and thus shortens hospital stays. Occasionally, however, other approaches are required for increased superior or lateral exposure, or for lesions with intradural extension. This section addresses the techniques of the surgical approaches and concentrates primarily on the transsphenoidal approach. The management of specific lesions is addressed in a later section.

Extracranial-Extradural Approaches ***Transsphenoidal Approach***

The transnasal, transsphenoidal (TNTS) approach to the sella was introduced in 1907 by Schloffer (41), and popularized by Hardy (6), and is regarded as the procedure of choice for midline lesions of the sella with limited lateral or posterior extension (42). The contraindications to the transsphenoidal approach are acute sinusitis; ectatic intrasellar "kissing" carotids; an "hourglass" configuration of tumor, with extensive suprasellar extension and a normal sella; a suprasellar mass too fibrous or calcified to collapse into the sella; and significant extension of the lesion into the subfrontal, retrochiasmatic, middle, or posterior fossae (Table 4). Rhinoplasty or previous transnasal surgery is not a contraindication to the transsphenoidal approach, nor is a con-chal sphenoid sinus, which can be opened with a high-speed drill.

Before surgery, the patient is given a single dose of antibiotics (usually a first-generation cephalosporin) and intubated with an orotracheal tube placed on the left side of the mouth. Patients with neural or endocrine compromise are given high-dose corticosteroids (hydrocortisone, 100 mg). The patient is positioned in the supine position with the head in a donut, tilted 15 degrees to the right, and elevated 15 degrees above the heart (Fig. 10). The donut permits small ad-

TABLE 4. *Contraindications to the transsphenoidal approach*

Acute sinusitis
"Kissing" carotids
"Hourglass" tumor with normal sella and extensive suprasellar extension
Fibrous suprasellar mass
Extension into frontal, middle, or posterior fossa
Gross dural invasion

продолжение


Pterional or
Frontotemporal
Subfrontal
Transethmoida
Tran spheroidal
Transmaxillary
Subtemporal

FIG. 9. Surgical approaches to the sella turcica.


Nurse
Surgeon

FIG. 10. Position of the patient and operating team for the transnasal-transsphenoidal approach.



FIG. 11. Transsphenoidal approach to the sella turcica. A: The gingival mucosa is incised from canine to canine with a no. 15 blade. B: After dissection, the pyriform aperture is enlarged as required. **C,D:** The mucosa is elevated off the left side of the quadrangular cartilage ventral to the anterior boarder of the perpendicular plate. E: After freeing the quadrangular cartilage from the vomer and the perpendicular plate, the left anterior and inferior submucosal tunnels are sharply dissected, and the quadrangular cartilage is retracted to the right using the nasal speculum.

justments of the head to facilitate improved visualization. Further flexion of the head improves access to the posterior sella and clivus, whereas extension improves exposure of the tuberculum and planum sphenoidale. The left thigh is positioned on a bolster to expose the superolateral aspect of the leg from the hip to the knee to facilitate a graft of fat and fascia lata, if needed. In very thin people, it may rarely be necessary to remove additional fat from the anterior abdominal wall. A lumbar subarachnoid drain may also be inserted before surgery for injection of saline or air to aid in bringing down a suprasellar mass. This has been used extensively by some surgeons (43) but is rarely done at the authors' institution. Preoperative ventriculostomy may also be indicated for patients with hydrocephalus due to obstruction of the foramen of Monro or the third ventricle by a suprasellar mass. The fluoroscopy unit may also be used, although this is usually required only for patients with a conchal sphenoid sinus or patients lacking the usual anatomic landmarks, such as patients who have previously undergone transsphenoidal surgery or rhinoplasty.'

The face and mouth are prepared with povidone-iodine from the bridge of the nose to the jaw to create a L'semister-ile" field. A vaginal pack is inserted in me oropharynx to prevent blood from entering the throat, and the gingiva and nasal mucosa are injected with 0.5% lidocaine with 1/200,000 epinephrine using a 25-gauge spinal needle until they blanch. The sphenopaiatine ganglia and the ethmoid nerves are blocked with] X3 cm cottonoids soaked with 4% cocaine to vasoconstrict the mucosa and shrink the nasal turbinates. Usually, the dissection is done on the left side for the convenience of the right-handed surgeon. However, if

---

[1] **Editor's note;** *The transnasal portion of the. operation is best done by an otolaryngologist and the intrasellar par! by the neurologic surgeon. This* r'i *especially important when prior septa! surgery or septorhinoplasty has been done, or if there is a significantly deviated septum.*



FIG. 11. *Continued.*

the septum is deviated significantly to the left, the right side should be used. Because the thigh is a sterile field, it is prepared separately. Two separate operative fields are maintained, each with a separate set of instruments that arc not to be shared.

There are two variations of" the transsphenoidal approach, die transseptal and the sublabial. The transseptal incision is quicker but gives a narrower exposure. It is useful when the nostril is large and the tumor is small. The sublabial incision, which the authors use exclusively, was introduced by Gushing and gives a wider exposure with better access to the superior aspect of the sella. Using a headlight for illumination, the gingival mucosa is incised from canine to canine down to the periosteum the maxilla (Fig. 11 A), The mucoperiostcum is then dissected superiorly in a subperiosleal fashion to expose the pyriform aperture. The spine and any superomedial extension of the maxillary rostrum is then removed with a Kerrison rongeur as required to flatten the view of the floor of the nose (see Fig. 1 IB).

Bilateral inferior tunnels are made first. The mucosa is first dissected from the nasal floor up to the maxillary crest of the septum using Cottle, Woodson, and Freer elevators. Next, the quadrangular cartilage is exposed sharply in the midline by incising the mucosa with a no. 15 blade. The subperiosteal dissection then proceeds posteriorly and superiorly to free die quadrangular cartilage from the interdigita-tion of the septal perichondrium with the periosteum of the maxillary crest (see Fig. 11C). These connections are typically concentrated along the junctions between the crest, the vomer, and the perpendicular plate of the ethmoid. The mucoperichondrium of the septal cartilage is extended beyond its bony septal attachments. This creates an anterior submucosal tunnel. The connective tissue bands connecting the quadrangular cartilage to the superior vomer and the anterior perpendicular plates are then sharply dissected with a Freer knife (see Fig. 11D). The quadrangular cartilage is then retracted laterally to the right with the nasal speculum (see Fig. HE). The contralateral nasal mucosa and superior aspect of the quadrangular cartilage remain intact. The mucosa of the nasal floor is elevated into the inferior meatus on each side. The perpendicular plate is fractured, removed, and saved for possible use during closure. As the final septal mucoperiosteal dissection proceeds over the vomer to the posterior termination of the nasal septum, nasal specula of increasing length are used for the exposure. Care is taken to provide wide access to the sphenoid rostrum superiorly. By preserving a small, short spike of vomer or ethmoid plate protruding from the maxillary crest, a guidepost is maintained to the midline of the nasal cavity.

The long Cottle speculum is now replaced by the Hardy retractor. Careful dissection of mucoperiosteum over the face of the sphenoid is carried down to the sphenoid sinus os-tia exposes bilaterally. The ostia are opened with a Kerrison rongeur until the sphenoid face begins to change its attitude from a vertical to a horizontal plane (Fig. 12). The speculum is continuously readjusted with the help of the "persuader" to capture the sphenoid face mucosa precisely under the tips of the retractor and to prevent "ballooning" of the mucosa into the visual field. Placement of the speculum in the sphenoid sinus should be avoided because fractures may result in traction damage to the optic nerve or the carotid artery. The entire anterior wall of the sphenoid sinus is removed. In patients with a conchal sphenoid sinus, a high-speed drill is used to open the sphenoid bone using fluoroscopic monitoring. Fluoroscopy may also be useful in other patients whose bony anatomy has been similarly obscured by previous transsphenoidal surgery or rhinoplasty. The sphenoid sinus mucosa is then removed using a pituitary rongeur or Decker.

The bulge of the sella is readily appreciated, as is the floor of the optic canal and the bony prominence of the carotid arteries (Fig. 13). Often, expansile sellar masses erode through the sellar floor, and resection can begin after merely opening the anterior wall of the sphenoid sinus. The carotid arteries may erode through the bone as well, however, particularly in older, hypertensive patients. When the sellar wall is intact, it is perforated and removed using a small osteotome and Kerrison rongeurs. The sphenoid septa are also removed when present. The bony resection can be extended superiorly to the tuberculum when there is a large degree of suprasellar extension.

After the bony resection is complete, the dura is coagulated transversely with a bipolar cautery, then incised in a cruciate manner (Fig. 14). The intercavernous sinuses are often encountered at the superior and inferior margins of ex-



FIG. 12. The sphenoid ostia are identified and enlarged using a rongeur. The entire rostrum of the sphenoid is removed in this fashion.



FIG. 13. Appearance of the sella after removal of the sphenoid rostrum.

posure, resulting **in brisk** bleeding. **This** is controlled by coagulating the leaves **of the dura with** a bipolar cautery.

Once access to the sella has been achieved, the lesion can be sampled for biopsy and gently resected using Hardy microinstruments, bayonetted ring curettes, and aspiration. Pituitary adenomas are nonencapsulated. soft, and gelatinous, with the consistency of jam, and are readily removed using this technique. Great care is taken to preserve the normal gland, which is often seen as orange-tinged tissue abutting the stalk or the posterior wall of the sella. Cystic lesions, such as craniopharyngiomas. are drained with a needle under direct visualization before resecting the solid portion of the mass. Intermittent Valsalva maneuver by the anesthesiologist or injection of saline or air through a lumbar drain expedites tumor removal by elevating the intracranial pressure, **which forces the mass inferiorly. The** integrity of the arachnoid is maintained, when possible, to avoid a CSF **fistula.**

When lesions involve only the sella or the medial cavernous sinus, the standard transsphenoidal approach is sufficient. However, when lesions extend more laterally into the cavernous sinus (Hardy grade D), exposure can be improved by enlarging the pyriform aperture or performing a medial maxillotomy contralateral to the invaded cavernous sinus (44). This allows the speculum and the resection itself to be directed laterally (Fig. 15). The medial wall of the cavernous sinus consists of a single thick layer, contiguous with the lateral layer of sellar dura. Neoplasms invading the medial cavernous sinus typically obliterate the venous sinuses and can be removed using fine ring curettes and microdissectors. These instruments can be passed around the carotid artery to



FIG. 14. After removing the sellar floor with rongeurs, the dura is opened in a cruciate fashion,

vomer, and the perpendicular plate of the ethmoid. The mucoperichondrium of the septal cartilage is extended beyond its bony septal attachments. This creates an anterior submucosal tunnel. The connective tissue bands connecting the quadrangular cartilage to the superior vomer and the anterior perpendicular plates are then sharply dissected with a Freer knife (see Fig. 11D). The quadrangular cartilage is then retracted laterally to the right with the nasal speculum (see Fig. 1 IE). The contralateral nasal mucosa and superior aspect of the quadrangular cartilage remain intact. The mucosa of the nasal floor is elevated into the inferior meatus on each side. The perpendicular plate is fractured, removed, and saved for possible use during closure. As the final septal mucoperiosteal dissection proceeds over the vomer to the posterior termination of the nasal septum, nasal specula of increasing length are used for the exposure. Care is taken to provide wide access to the sphenoid rostrum superiorly. By preserving a small, short spike of vomer or ethmoid plate protruding from the maxillary crest, a guidepost is maintained to the midline of the nasal cavity.

The long Cottle speculum is now replaced by the Hardy retractor. Careful dissection of mucoperiosteum over the face of the sphenoid is carried down to the sphenoid sinus os-tia exposes bilaterally. The ostia are opened with a Kerrison rongeur until the sphenoid face begins to change its attitude from a vertical to a horizontal plane (Fig. 12). The speculum is continuously readjusted with the help of the "persuader" to capture the sphenoid face mucosa precisely under the tips of the retractor and to prevent "ballooning" of the mucosa into the visual field. Placement of the speculum in the sphenoid sinus should be avoided because fractures may result in traction damage to the optic nerve or the carotid artery. The entire anterior wall of the sphenoid sinus is removed. In patients with a conchal sphenoid sinus, a high-speed drill is used to open the sphenoid bone using fluoroscopic monitoring. Fluoroscopy may also be useful in other patients whose bony anatomy has been similarly obscured by previous transsphenoidal surgery or rhinoplasty. The sphenoid sinus mucosa is then removed using a pituitary rongeur or Decker.

The bulge of the sella is readily appreciated, as is the floor of the optic canal and the bony prominence of the carotid arteries (Fig. 13). Often, expansile sellar masses erode through the sellar floor, and resection can begin after merely opening the anterior wall of the sphenoid sinus. The carotid arteries may erode through the bone as well, however, particularly in older, hypertensive patients. When the sellar wall is intact, **it** is perforated and removed using a small osteotome and Kerrison rongeurs. The sphenoid septa are also removed when present. The bony resection can be extended superiorly to the tuberculum when there is a large degree of suprasellar extension.

After the bony resection is complete, the dura is coagulated transversely with a bipolar cautery, then incised in a cruciate manner (Fig. 14). The intercavernous sinuses are often encountered at the superior and inferior margins of e\-



FIG. 12. The sphenoid ostia are identified and enlarged using a rongeur. The entire rostrum of the sphenoid is removed in this fashion.



FIG. 13. Appearance of the sella after removal of the sphenoid rostrum.

posure, resulting in brisk bleeding. This is controlled by coagulating the leaves of the dura with a bipolar cautery.

Once access to the sella has been achieved, the lesion can be sampled for biopsy and gently resected using Hardy micro instruments, bayonetted ring curettes, and aspiration. Pituitary adenomas are nonencapsulated, soft, and gelatinous, with the consistency of jam, and are readily removed using this technique. Great care is taken to preserve the normal gland, which is often seen as orange-tinged tissue abutting the stalk or the posterior wall of the sella. Cystic lesions, such as craniopharyngiomas, are drained with a needle under direct visualization before resecting the solid portion of the mass. Intermittent Valsalva maneuver by the anesthesiologist or injection of saline or air through a lumbar drain expedites tumor removal by elevating the intracranial pressure, which forces the mass inferiorly. The integrity of the arachnoid is maintained, when possible, to avoid a CSF fistula.

When lesions involve only the sella or the medial cavernous sinus, the standard transsphenoidal approach is sufficient. However, when lesions extend more laterally into the cavernous sinus (Hardy grade D), exposure can be improved by enlarging the pyriform aperture or performing a medial maxillotomy contralateral to the invaded cavernous sinus (44). This allows the speculum and the resection itself to be directed laterally (Fig. 15). The medial wall of the cavernous sinus consists of a single thick layer, contiguous with the lateral layer of sellar dura. Neoplasms invading the medial cavernous sinus typically obliterate the venous sinuses and can be removed using fine ring curettes and microdissectors. These instruments can he passed around the carotid artery to



FIG. 14. After removing the sellar floor with rongeurs, the dura is opened in a cruciate fashion.

remove tumor that has extended laterally. Significant venous bleeding is usually not encountered until the patem portion of the cavernous sinus is exposed in the final phase of the resection, and is well controlled with Surgicel and direct pressure, Although this technique can often be used safely to resect neoplasm lateral to the carotid, narrowing of the caliber of the cavernous carotid on MRI suggests invasion of the vessel wall and is a relative contraindication to aggressive exploration using this technique.

After maximal resection has been completed, the sella and the pituitary gland itself are systematically inspected. If the tumor capsule prolapses into the sphenoid sinus, or there is a gross CSF leak visible, fascia lata, fat, and bone are used to reconstruct the sellar floor (Fig. 16). The fascia lata is placed in the sellar opening and sealed with fibrin glue after packing the sella with a small amount of fat or Surgicel. The fascia is then buttressed within the sella by the wedge of bon\ septum removed earlier. The integrity of the closure is then tested by having the anesthesiologist maintain a Valsalva maneuver at 40 mm Hg pressure. If the closure is satisfactory, the speculum is removed and the nasal mucosa is reapproximated and tamponaded using gauze impregnated with petroleum jelly. The gingival mucosa is reapproxirnated using 3-0 chromic suture, and a "mustache" dressing consisting of a folded gauze is placed below the nostrils. In cases with extensive CSF leaks, lumbar drainage is continued for 2 to 3 days. For large suprasellar lesions, the sella is packed regardless of whether a CSF leak is present. This is necessary because the resection may produce an "empty sella" secondarily. This may result in collapse of the diaphragma sellae and consequent traction on the chiasm, leading to decreased vision.



FIG. 15. The extended transsphenoidal approach for lesions extending lateral to the carotid artery (Hardy grade D). The pyriform aperture is enlarged contralateral to the lesion, facilitating improved lateral exposure of the neoplasm.



FIG. 16. Repair of cerebrospinal fluid (CSF) fistula. If a CSF leak is identified during surgery, it may be patched with fascia lata and held in place with Gelfoam or fat, tamponaded with bone.

After surgery, patients are managed in the neurosurgery step-down unit, where close attention is paid to the ophthalmologic examination and the detection of diabetes insipidus. New deficits are rare, and improvement in the visual field examination is sometimes noted early in the postoperative period. Diabetes insipidus usually does not appear before 12 to 24 hours after surgery, and polyuria is not treated unless the diagnosis of diabetes insipidus is clear: urine output greater than 300 ml/hour for 2 consecutive hours with a specific gravity less than 1.005, urine osmolarity of 50 to 150 mOsm/L, and a serum Na of at least 145 and rising. The patient is allowed to drink *ad libitum*, and treated with aqueous DDAVP (vasopressin). 1 (Jig every 12 to 24 hours intravenously or subclUaneously as needed. In the immediate postoperative period, serum sodium and osmolarity and urine output are monitored closely. The patients are encouraged to ambulate the night of surgery, and the Foley catheter is removed after 24 hours unless diabetes insipidus makes this inconvenient. Intravenous antibiotics are continued until the nasal packing is removed on the third postoperative day, after which the patient undergoes a postoperative MRI. Patients without complications are routinely sent home on the second or third postoperative day on a tapering dose of steroids, with follow-up appointments for both the neurosurgery and endocrinology clinics.

The most frequent complications of the transsphenoidal approach are CSF leaks and damage to the carotid artery or cranial nerves. CSF leaks can usually be avoided using the techniques outlined previously. Persistent leaks are usually controlled with prolonged lumbar drainage and elevation of the head. Reoperation for repair of a CSF leak refractory to conservative management is sometimes required and is usually done using the TNTS approach. Tension pneumocephalus, a related complication, occurs because of continual accumulation of intracranial air through a dural tear with a ball-valve mechanism that prevents its egress. This is far more rare, but more deadly, and this possibility should be considered in patients whose postoperative mental status deteriorates, particularly when a lumbar drain is in place. After the lumbar drainage is discontinued, and the diagnosis is confirmed, the patient is placed on 100% oxygen. The pneumocephalus gradually resolves over several days. Tension pneumocephalus may also be decompressed with a spinal needle transnasally or transcranially in emergent circumstances.

Laceration of the intracavernous carotid is another rare but serious complication that occurs more frequently in cases requiring cavernous sinus exploration. Because of the narrowness of the field, temporary occlusion and primary repair of the carotid are impossible in the transsphenoidal approach. Lacerations are treated by holding direct pressure with Surgicel and cotton pledgets until the bleeding stops. An intraoperative angiogram should be obtained when possible to document patency of the carotid and rule out contrast extravasation. Follow-up angiograms should be obtained before discharge and at 3 months to rule out pseudoaneurysms. Cranial nerve palsies as well as lesions of the brainstem and hypothalamus are also possible, although rare. After ruling out hematoma or pneumocephalus, they are managed expectantly. Recovery is variable.

Because of the versatility and low morbidity of the TNTS approach, it can be used even in the presence of extensive suprasellar extension. When the lesion is soft (as pituitary adenomas usually are), the suprasellar mass often collapses into the sella, where it can be safely resected at the initial procedure. Occasionally, when the tumor does not descend immediately, the residual neoplasm may collapse further into the sella with time (Fig. 17), allowing the residual to be resected by repeat TNTS if further surgery is indicated.

Facial Degloving and Extended Maxillotomy Approaches

Lesions invading the superior clivus above the hard palate and medial to the carotid arteries, such as chordomas, medial chondrosarcomas. and juvenile angiofibromas can be approached using facial degloving or extended maxillotomy approaches either alone or in combination. These procedures are detailed in Chapters 11 and 12.

Transsphenoethmoidal Approach

The transsphenoethmoidal approach to the sella was introduced by Chiari (45). This option is discussed in detail in Chapter 14, and is covered here only briefly. The advantage of this approach over the transsphenoidal approach is the shorter operative distance to the sella (46). However, it requires a facial incision, provides a narrower axial exposure.



FIG. 17. Two-stage removal of pituitary macroadenoma with suprasellar extension. (Adapted from ref. 43, with permission).

and carries a risk of injury to the optic nerve. One version combines this with medial maxillectomy for improved axial exposure of the sella (47). However, this combination holds little benefit over maxillotomy with midface degloving, which has a lower risk and superior cosmesis.

A 3-cm incision is made along the medial border of the nose, beginning from the inferior margin of the eyebrow, and the lacrimal sac is retracted laterally. The anterior ethmoid artery is sacrificed, and the lamina papyracea over the lacrimal fossa is removed, as is the underlying middle turbinate. The ethmoid mucosa is removed to identify the sphenoid ostia. The anterior and posterior walls of the sphenoid are then removed to expose the sella. The operation then proceeds as in the standard TNTS approach.

Transcranial-Intradural Approaches

The indications for transcranial-intradural approaches to the sella consist primarily of patients for whom transsphenoidal surgery is contraindicated for reasons discussed previously. Lesions invading the cavernous sinus laterally, with secondary sellar invasion; lesions that frankly violate the dura; and residual suprasellar or lateral cavernous sinus lesions that could have been only partially resected from the transsphenoidal approach are additional indications for transcranial approaches. In addition, repair of CSF leaks may also require a transcranial approach.

There are several possible transcranial approaches to the sella turcica, but the most useful are the transbasal, pterional, and subtemporal approaches (see Fig. 9). The choice of approach is determined by the location of the lesion with respect to the sella, and to some extent by the personal preference of the surgeon. These approaches are described in other chapters (Chapters 20, 18, and 24, respectively), and are discussed briefly in the following sections specifically in terms of their utility for the resection of sellar and parasellar lesions.

Transbasal Approach

The transbasal approaches to the sella are versions of the anterior subcranial approach. A unilateral or bilateral frontal craniotomy is performed with or without orbitofrontal craniotomy. The tuberculum sellae is removed anterior to the chiasm with a high-speed drill (Fig. 18). This minimizes the effect of a prefixed chiasm, when present, and gives the surgeon an unobstructed view of the sella between the optic nerves with minimal brain retraction. In contrast to the other transcranial approaches, the pituitary stalk is easily identified and avoided, as are the carotid arteries and their branches. This approach is particularly useful for extradural lesions such as esthesioneuroblastomas and craniopharyn-giomas, as well as for tuberculum sellae and olfactory groove meningiomas with secondary sellar involvement. There is a high risk of anosmia due to avulsion of the olfactory nerves with this approach, as well as a small risk of optic nerve or carotid injury. Frontal lobe swelling can usually be avoided by proper positioning, lumbar drainage, and minimizing brain retraction.



FIG. 18. The subfrontal approach to the sella turcica. The tuberculum sellae is removed with a highspeed drill to facilitate exposure of a suprasellar mass.

Pterional Approach

The pterional approach is the shortest route to the parasellar region. This is usually done on the side of either the greatest tumor extension, or the patient's worst vision. If neither of these are considerations, the craniotomy is done on the *non-dominant side. After* performing a standard pterional craniotomy, the sphenoid ridge lateral to the superior orbital fissure is removed extradurally with a high-speed drill. The sylvian fissure is widely split and the frontal and temporal lobes are gently retracted to maximize exposure of the sellar region, and the anterior clinoid process is drilled away (Fig. 19). This gives excellent exposure of lateral parasellar lesions such as meningiomas or eccentric pituitary macroadenomas spilling into the middle fossa. Access to the sella itself, however, is somewhat impeded by the optic nerve, third cranial nerve, and carotid artery, which lie in the surgeon's line of sight. In addition, the contralateral optic nerve may be poorly visualized. The risks of this approach include damage to the carotid artery as well as the optic and third cranial nerves.

Subtemporal Approach

The subtemporal approach gives superior access to the posterior aspect of the sella, including the posterior clinoid process and the top of the clivus. It is most useful for lesions with retrochiasmatic extension such as chordomas and chondrosarcomas of the uppermost clivus, as well as meningiomas in that region. The approach begins with the standard pterional craniotomy. Aggressive temporal bone resection is used to minimize brain retraction. A zygomatic osteotomy may further enhance exposure. After opening the dura, the sylvian fissure is widely split, and the median temporal lobe is retracted laterally to reach the upper clivus and posterior clinoid process. The disadvantage of this approach is that the


Reflected dura
Extent of bony resection
Anterior clinoid process
Posterior clinoid process
A
Subclinoidal segment of ICA exposed

FIG. 19. The pterional approach to sellar lesions. The anterior clinoid process can be removed intradurally with a high-speed drill to facilitate exposure of the lateral parasellar region.

ipsilateral third and fourth cranial nerves are interposed between the surgeon's line of sight and the sella. In addition, visualization of the contralateral posterior cerebral artery (PCA) and superior cerebellar artery (SCA) is poor. The major risk of this approach is temporal lobe damage due to excessive retraction.

The aforementioned three approaches can also be combined.

Adjunctive Surgical Techniques: Frameless Stereotaxy

The authors have also employed frameless stereotactic devices extensively for complex cases. This has been useful for intraoperative determination of the trajectory required for resection of certain skull base lesions, allowing the exposure to be optimized. It is also useful for intraoperative confirmation of the limits of resection and for determining the proximity of critical neurovascular structures in regions with distorted anatomy. Although brain "shift" after the dura is opened (48) limits the accuracy of this technique for deep intraparenchymal lesions, this technique is accurate for localizing skull base lesions.

TREATMENT

Pituitary Adenomas

The goals of treatment for patients with pituitary adenomas are to remove the mass effect (if present) and to normalize or restore hormonal function. Endocrinologically inactive microadenomas are usually discovered incidentally and rarely require treatment. The treatment of endocrinologically active microadenomas depends on their endocrine activity. Pharmacologic therapy has proven useful for shrinking some of these adenomas and reducing excess hormone levels. However, none of these cytotoxic agents is curative, and symptoms usually resume shortly after the drug is discontinued. Surgery, particularly through the transsphenoidal approach, is effective and relatively benign, and remains the mainstay of therapy for most pituitary adenomas other than prolactinomas. Radiation therapy has a delayed effect and is complicated by damage to the optic nerves and hypothalamic-pituitary axis as well as by radiation necrosis. Impaired mental status and radiation-induced tumors have also been described. Focused-beam radiation therapy is useful in patients with recurrent or residual tumor, or poor operative candidates whose tumors cannot be controlled with medical therapy. The treatment of specific subtypes of pituitary adenoma is addressed in the following sections.

Prolactinomas

The treatment of prolactinomas remains controversial. Medical therapy with bromocriptine, an ergot derivative, not only shrinks the tumor but also decreases prolactin synthesis and release (49), and is considered first-line therapy for most prolactinomas. This produces relief of symptoms, including galactorrhea and amenorrhea, and can restore fertility. Although accelerated tumor growth can occur during pregnancy, this is rarely significant in microprolactinomas. There have been no teratogenic effects reported from use of bromocriptine to achieve conception. The drug can be discontinued during pregnancy, then reinstituted after delivery. Patients with microprolactinomas desiring fertility can also be treated with transsphenoidal surgery. Surgical cure and subsequent fertility has been reported in 83% of patients (50). Surgery is also indicated for patients with macroadenomas with persistent mass effect despite maximal tolerated dose of bromocriptine; patients who are noncompliant, have serious side effects from bromocriptine, or do not want to continue medical therapy; and women with macroprolactinomas desirous of pregnancy. Preoperative prolactin levels correlate both with tumor size and operative success: surgical cure is achieved in 70% of patients with preoperative prolactin levels of 200 to 500 ng/ml, and 14% of patients with prolactin levels over 1000 ng/ml (51).

Bromocriptine is useful for treatment of residual or recurrent prolactinomas in patients who are poor surgical candidates. One caveat is that bromocriptine induces tumor fibro-sis, which makes resection difficult and reduces the surgical cure rate by approximately half (52,53). Radiation therapy is effective at relieving symptoms and reducing prolactin levels. However, because of the effectiveness of surgery and pharmacotherapy for this disorder, radiation therapy is rarely indicated. It is reserved for symptomatic patients with recurrent or residual tumor who are not surgical candidates and are unable or unwilling to control their tumor using bromocriptine.

Growth Hormone-Secreting Adenomas

Excess growth hormone secretion produces not only the visibly obvious deformities of giganticism or acromegaly but also results in severe, systemic metabolic effects that result in a significant decrease in life expectancy. These include atherosclerosis, cardiomyopathy, cerebrovascular disease, respiratory disease, and diseases of the muscles, joints, and peripheral nerves. Thus, the goals for managing growth hormone-secreting adenomas are normalization of growth hormone and somatomedin C levels, in addition to elimination of mass effect.

Two agents have been used for medical therapy of growth hormone-secreting adenomas: bromocriptine and somatostatin. Bromocriptine decreases growth hormone production in 74% of patients, but normalizes levels in only 20% (54). Shrinkage occurs only in isolated cases (55) and requires higher doses of bromocriptine than those used for prolactinomas. These tumors probably represent mixed prolactin cell/growth hormone cell adenomas.

More recently, octreotide, a somatostatin analog, has demonstrated its effectiveness in suppressing growth hormone levels to below 5 mg/ml in 50% of patients, and less than 2 mg/ml in 25% of patients (56). However, this drug must be given by subcutaneous injection two to three times per day, making it suitable only for intelligent, highly motivated patients who can administer the injections themselves. Because of the inconvenience and morbidity of medical treatment, and the effectiveness of surgery in curing most of these patients (57,58), pharmacologic therapy is reserved for patients who are poor surgical candidates or those with recurrent or residual disease who are unwilling or unable to undergo reoperation. Radiation therapy is reserved for patients in whom an endocrinologic cure cannot be achieved by surgery combined with medical therapy.

Adrenocorticotropic Hormone-Secreting Adenomas

In contrast to hyperprolactinomas, the endocrinopathy of Gushing's disease is life threatening. When untreated, the 5-year mortality rate is 50%; thus, the goal of therapy must be endocrinologic cure. Because most corticotropic adenomas are microadenomas, radiologic diagnosis by gadolinium-enhanced MRI is achieved in only 40% to 60% of cases. When a pituitary mass is noted by MRI of the sella, or suggested by diagnostic petrosal sinus sampling in the absence of pulmonary or adrenal lesions on radiologic examination of the thorax and abdomen, transsphenoidal surgery is almost always the treatment of choice. Tumor noted on MRI is usually easily found and resected, while sparing the normal gland. Systematic exploration and sectioning of the gland is indicated to locate radiographically occult adenomas. Usually, several deep vertical and horizontal incisions are made in the gland to find the abnormal tissue. This technique is often successful. When it is not, a total hypophysectomy is usually recommended for older adults, from whom consent should be obtained for this eventuality before surgery. Children and young adults in whom no tumor is found are treated conservatively with medical management and reimaging before further surgery or radiosurgery. However, hypophysectomy is sometimes required by the severity of the endocrinopathy. Resection of the central "mucoid wedge" has also been reported (46,59). Unilateral hypophysectomy is also an option in patients with occult ACTH-secreting adenomas that have been localized to one side by petrosal sinus sampling (35). Surgical cure has been reported in 90% of microadenomas and 65% of macroadenomas using this technique, with a recurrence rate of 8.5% (60). Successfully treated patients have had an immediate fall in blood cortisol levels with gradual resolution of cushingoid features.

In patients who are refractory to surgical cure, or who are poor operative candidates, pharmacologic treatment or radiation therapy can be used to achieve endocrinologic control. Medical therapy consists primarily of agents that pharmacologically block adrenal steroidogenesis. Ketoconazole is the most useful of these and has been used to stabilize severely ill patients as a preparation for surgery or radiation therapy (61). Other pharmacologic agents such as metyrapone (62), cyproheptadine, a serotonin inhibitor (63), aminoglutethemide, and mitotane (64) have been used to control serum cortisol levels with variable degrees of success.

The delayed effect of radiation therapy makes this modality inadequate as the primary treatment. However, radiation is reported to control disease in 50% to 70% of patients by 3 years (33,65). This makes it useful as adjuvant treatment when combined with pharmacologic treatment in patients who are poor operative candidates or have persistent or recurrent disease. Bilateral adrenalectomy is immediately effective in curing hypercortisolism, but because of the severe metabolic consequences and the possibility of inducing Nelson's syndrome in patients with occult pituitary adenomas, this procedure is reserved as a last resort in most patients.

Although pituitary adenomas producing Nelson's syndrome are usually macroadenomas and easily visualized, they are characteristically invasive and difficult to cure. Normalization of ACTH and hyperpigmentation occur in less than half the cases (66). Although data are sparse, there is some suggestion that radiation therapy may be somewhat helpful in patients with Nelson's syndrome.

Thyrotropic Adenomas

Thyrotropic adenomas are the least common adenomas, accounting for less than 1% of all pituitary adenomas. They can be microadenomas but often are invasive macroadenomas, particularly in patients who have undergone thyroid ablation. Surgical excision is the treatment of choice and can be achieved in most microadenomas. The surgical cure rate for invasive macroadenomas is only about 40% (67). Octreotide has been reported to reduce TSH levels but does not significantly reduce mass effect, and adjuvant radiation therapy should be used in these cases.

Endocrinologically Inactive Adenomas

Endocrinologically inactive adenomas consist of null cell adenomas and gonadotropin-producing adenomas, which do not produce symptoms of excess endocrine secretion. These collectively account for 25% of all pituitary adenomas. Patients typically present with macroadenomas with mass effect, although they may present with symptoms of mild hyperprolactinemia due to stalk compression. Symptoms of hypopituitarism are often more evident. The goal of surgery is reduction of mass effect, and the treatment of choice is surgery. Although gross total resection is the surgeon's intuitive goal, the fact that these tumors occur mainly in the elderly and are slow growing with a high incidence of cavernous sinus invasion suggest that therapy be individualized. The transsphenoidal approach is usually the procedure of choice, and near-total to gross-total resection can usually be achieved, although microscopic invasion is usually present (68). Vision improves or stabilizes in over 90% of these patients (69), and headache and cranial nerve palsies due to cavernous sinus compression often resolve. The patients presenting with panhypopituitarism seldom regain normal pituitary function (70), and they require long-term hormonal therapy. Bromocriptine may decrease prolactin levels through a direct effect on the hypothalamic-pituitary axis. However, it does not shrink these tumors and has no role in the treatment of mass effect. Adjuvant radiation therapy has been advocated by some. However, given the benign nature of these neoplasms, their slow growth rate, and the success of reoperative surgery, the authors prefer conservative management, or "watchful waiting," of any residual tumor. If the tumor grows, consideration is given to reoperation before instituting radiation therapy.

Giant Adenomas

The management of giant adenomas is both complex and controversial. These are usually a subset of endocrinologically inactive adenomas presenting with mass effect and obstructive hydrocephalus. Giant adenomas producing prolactin and other hormones have also been reported. Treatment is surgical, but these patients tend to do poorly with a high incidence of morbidity, and a 20% mortality rate (7,71). The pathophysiology of this phenomenon is unclear, but it is thought to be due to exacerbated hydrocephalus, seemingly related either to tumor swelling after an incomplete resection, or due to a traction effect on the third ventricle. These tumors should be managed conservatively, with debulking through a transsphenoidal approach. Ventriculostomy can be done before or during surgery if hydrocephalus is present. Complete resection is rarely required or achieved. Regional radiation therapy may be useful in poor operative candidates.

Apoplexy

Pituitary apoplexy is a clinical emergency requiring urgent surgical decompression of the sella and parasellar structures, usually through a transsphenoidal approach.

Pituitary Carcinoma

Pituitary carcinoma is rare, with less than 40 cases reported (72). They appear to arise from pituitary adenomas of all types, although endocrinologically active adenomas predominate. They typically present with multiple local recurrences followed by metastatic dissemination to the subarachnoid space or extraneuronal sites such as bone, liver, lymph node, lung, or kidney. This is usually accompanied by an escalation of histologic grade. The most symptomatic region is usually the sella, and the therapy is directed at control of the primary neoplasm. Aggressive reoperation is used with adjuvant radiation therapy and pharmacologic therapy as indicated by the characteristics of the original adenoma (66). In most cases, death from pituitary carcinoma results from a failure of local control with progressive local invasion, rather than from metastatic disease.

Tumors of the Posterior Pituitary

Granular cell tumors, or choristomas, are usually benign and asymptomatic, although malignant transformation has been reported. Symptomatic granular cell tumors most often present with visual disturbance, although hypopituitarism, hyperprolactinemia, precocious puberty, and acromegaly also occur. Diabetes insipidus is rare. Transsphenoidal surgery is usually indicated for diagnosis and resection. There is no evidence that these tumors are radiosensitive (13).

Management of metastatic lesions is more complex. Although most metastases to the neurohypophysis are asymptomatic, metastases to the stalk may present with hypopituitarism or mass effect (13). Treatment is palliative, and consists of surgery, radiation therapy, chemotherapy, or combinations of these modalities depending on the need for tissue confirmation, tumor type, and the medical condition of the patient. Usually, metastases are amenable to excision using the transsphenoidal approach if this is clinically indicated, and surgery can prolong survival.

Craniopharyngiomas

Craniopharyngiomas are among the most challenging tumors to treat. Although they are slow growing, benign, extraaxial neoplasms, some consider them malignant by virtue of location. Their tenacious attachment to pial vessels and critical neurovascular structures increases the morbidity of aggressive resection. Yet, the high recurrence rate and consequent morbidity after subtotal resection make this option equally distasteful.

The presenting symptoms depend on the size and location of the tumor. Craniopharyngiomas present with mass effect and symptoms of increased intracranial pressure in 80% of children, and with visual symptoms in 80% of adults. Endocrine dysfunction, including partial or complete hypopituitarism and diabetes insipidus, occurs in most patients of all ages, although it is usually not the presenting symptom.

Craniopharyngiomas are classified as endosellar, suprasellar, or intraventricular based on their position relative to the sella, chiasm, and third ventricle (73). Endosellar Craniopharyngiomas are subdiaphragmatic and confined to the sella. They comprise 3% to 8% of Craniopharyngiomas (74). Suprasellar Craniopharyngiomas arise from the midportion of the stalk and typically enlarge beneath the third ventricle, elevating the third ventricular floor. Intraventricular Craniopharyngiomas arise from the infundibulum. They invade the floor of the third ventricle and often extend into the interpeduncular fossa. The latter two types are considered retrochiasmatic Craniopharyngiomas.

There is general agreement that surgery is the treatment of choice for craniopharyngiomas. However, the choice of approaches, the extent of resection, and the use of adjuvant radiation therapy remain controversial. The difficulty is that these tumors recur unless gross total resection is achieved, and many believe that the initial operation represents the only opportunity for cure. However, the tumor capsule is tenaciously attached to vital structures such as the optic chiasm, optic tract, infundibulum, pituitary, hypothalamus, third ventricle, and the vessels that supply these critical structures. Despite advances in microsurgical technique, aggressive resection of these densely adherent tumors has resulted in a high rate of neurovascular and endocrine complications. Even in experienced hands, the mortality rate for primary craniopharyngiomas has been reported to be as high as 8% to 15%, with varying degrees of visual compromise in 50% to 60% of patients, and 80% of patients require postoperative endocrine replacement (75,76). This morbidity is thought to result from devascularization of critical structures due to aggressive resection of tumor capsule. Thus, it is preferable to leave densely adherent capsule attached to critical neurovascular structures rather than pursue more aggressive resection that may lead to unacceptable morbidity.

The choice of surgical approach depends on the location, shape, and size of the tumor. Endosellar lesions with an enlarged sella and a prominent cystic component can be safely approached through the transsphenoidal route. Because of their subdiaphragmatic position, these tumors are not attached to the hypothalamus or optic chiasm. After draining the cystic component under direct vision, the intracapsular contents are removed with a grasping forceps and curettes. The capsule collapses and can be detached from the undersurface of the diaphragma sellae. Normal preoperative pituitary function is a relative contraindication to the transsphenoidal approach because the gland is often situated anteriorly within the sella and damaged during tumor resection. The stalk can usually be preserved.

Suprasellar craniopharyngiomas are best resected using transcranial approaches. If hydrocephalus is present, ventricular drainage should be instituted before definitive therapy. The most useful approaches are the pterional and the subfrontal. Both have the advantage of allowing direct visualization of the optic nerve and chiasm. The pterional approach is the shortest and offers superior visualization of the retrochiasmatic region. The subfrontal approach provides better visualization of the optic pathways by way of the subchiasmatic pathway, as well as a midline route to the lamina terminalis. The opticocarotid pathway may also be useful. In addition, access to the sella can be achieved by removing the tuberculum sellae with a high-speed drill.

Intraventricular craniopharyngiomas are best approached by the subfrontal-lamina terminalis approach, the interhemispheric-transcallosal approach, or a combination of these. The subfrontal-lamina terminalis approach allows direct visualization of the chiasm and permits good access to the anterior third ventricle. However, this approach also carries the greatest risk of hypothalamic damage. The interhemispheric-transcallosal approach utilizes the foramina of Monro, which are usually enlarged due to hydrocephalus. to resect the intraventricular portion of the tumor. Alternately, if the foramina of Monro is not enlarged, the interforniceal approach may be used. Although the latter two approaches minimize the risk of devascularizing the hypothalamus, they carry the risk of bilateral forniceal damage and consequent memory impairment. Because these approaches give access only to intraventricular tumor, they are often combined with pterional or subfrontal approaches. The transcortical approach is associated with a high risk of hydrocephalus and postoperative seizures, in addition to the aforementioned risk of bilateral forniceal injury, and should be avoided except in cases of marked preoperative ventricular dilatation.

In all approaches, the presence of a subarachnoid plane facilitates complete resection and preservation of the normal vasculature. Electrocautery often disrupts this interface and should be avoided whenever possible. Although radiation therapy has been effective in reducing recurrence and increasing survival in some series with minimal morbidin (77), the risks of radiation therapy have prompted the author to follow patients with serial examination and imaging studies, and individualize treatment of recurrence.

Meningiomas

Usually, parasellar meningiomas are large, and present predominantly with mass effect. Visual loss is the predominant symptom. Pituitary insufficiency is uncommon and usually mild. Because resection of parasellar meningiomas requires resection of the dura itself, an intradural approach if required for complete resection. The choice of approach is governed by the location and orientation of the lesion Meningiomas of the tuberculum sellae, olfactory groove, and anterior clinoids are best approached through a subfrontal approach. Meningiomas of the medial sphenoid wing and cavernous sinus require a pterional approach, wherea> retrochiasmal meningiomas are usually best resected using the subtemporal approach. The transsphenoidal approach may be indicated for diagnostic biopsy.

Chordomas

Chordomas of the sella typically present with symptoms of mass effect and hypopituitarism depending on their **size** and direction of growth. Occasional small tumors confined to the sella can be resected through the transsphenoidal approach alone. At the end of such an operation, the clivus should be drilled beyond the obvious tumor margin because of invasion within cancellous lumen. A tumor-free margin of well vascularized bone should be observed. The clival dura should be exposed and prolapse freely into the bony defect. However, most chordomas involve parasellar structures as well. Because gross total resection is associated with increased survival (16), such patients require a more extensive extradural or transcranial approach than can be achieved by the transsphenoidal approach alone. An extended transsphenoidal, transmaxillary, or transoral approach may be required to maximize exposure in these cases. There are some studies suggesting that adjuvant proton-beam radiation therapy may also prolong survival (78).

Nonneoplastic Cysts

Rathke's cleft cysts, mucoceles, and arachnoid cysts are the most common nonneoplastic cysts of the sella. They are usually asymptomatic. Occasionally, however, patients do present with symptoms of mass effect, hypopituitarism, or mild hyperprolactinemia due to stalk compression. Suprasel-lar extension may occasionally produce visual loss or hypothalamic dysfunction. Transsphenoidal decompression of the cyst, or marsupialization, without excision of the cyst wall is usually curative.

Inflammatory and Infectious Lesions

Inflammatory Lesions

Lymphocytic hypophysitis, Langerhans' cell histiocytosis, giant cell granuloma, and sarcoidosis are the most common inflammatory lesions of the sella turcica. These sellar lesions are often indistinguishable from pituitary adenoma on MRI. Transsphenoidal biopsy is required for diagnosis, but radical resection is rarely indicated. Lymphocytic hypophysitis typically presents with mass effect, symptoms of moderate hyperprolactinemia, and varying degrees of hypopituitarism, although diabetes insipidus is unusual. At surgery, the adenohypophysis is yellow, rubbery, and firm, and the inflammatory mass frequently extends into the suprasellar region. Patients are started on hormonal replacement and treated with steroids.

Langerhans' cell histiocytosis (histiocytosis X) of the sella usually presents with diabetes insipidus because of its preferential involvement of the stalk and posterior pituitary gland. Mild to moderate hypopituitarism may also be present. These lesions should be resected. Adjuvant radiation therapy has also been used (13).

Granulomatous lesions such as giant cell granuloma and sarcoidosis present with hypopituitarism and, occasionally, hyperprolactinemia. Sarcoidosis may also produce mass effect, diabetes insipidus, and even hypothalamic dysfunction. After biopsy to exclude infectious processes, they are treated conservatively with endocrine replacement, if required, and steroids.

Infectious Lesions

Abscesses of the pituitary typically present with symptoms of mass effect and moderate to severe hypopituitarism. In the setting of meningitis, this diagnosis should always be considered. The transsphenoidal approach is used to debulk and to obtain a diagnostic specimen for aerobic, anaerobic, acid-fast, and fungal cultures. Patients are then treated with the appropriate antibiotic, antituberculous, or antifungal agents.

Vascular Lesions

Aneurysms and carotid cavernous fistulas of the infraclinoid or cavernous carotid may present with a clinical picture indistinguishable from that of an endocrinologically inactive pituitary adenoma. Visual deficit, mild hyperprolactinemia, and hypopituitarism are common. Fortunately, the diagnosis is readily made by MRI, magnetic resonance angiography, or conventional angiography. The treatment of aneurysms and carotid-cavernous fistulas is beyond the scope of this chapter.

REFERENCES

1. Renn WH, Rhoton AL Jr. Microsurgical anatomy of the sellar region. *J Neurosurg* 1975;43:288-298.
2. Tindall GT, Barrow DL, eds. *Disorders of the pituitary.* St. Louis: Mosby, 1986.
3. Lang R. Anatomy of the sellar region. In: Samii M, Draf W, eds. *Surgery of the skull base: an interdisciplinary approach.* Berlin: Springer-Verlag, 1989:27-35.
4. Annegers JF, Coulam CB, Abboud CF, et al. Pituitary adenomas in Olmsted County, Minnesota, 1935-1977. *Mayo Clin Proc* 1978;53: 641-643.
5. Costello RT. Subclinical adenoma of the pituitary gland. *Am J Pathol* 1936;12:205-216.
6. Hardy J. Transsphenoidal microsurgery of the normal and pathologic pituitary. *Clin Neurosurg* 1969;! 6:185-217.
7. Symon L, Jakubowski J, Kendall B. Surgical treatment of giant pituitary adenomas. *J Neurol Neurosurg Psychiatry* 1979;42:973-982.
8. Wilson CB. Neurosurgical management of large and invasive pituitary tumors. In: Tindall GT, Collins R, eds. *Clinical management of pituitary disorders.* New York: Raven Press, 1979:334-342.
9. Ridgeway EC, Klibanski A, Ladenson PW, et al. Pure alpha-secreting adenomas. *NEnglJMed* 1981;304:1254-1259.
10. Kovacs K, Horvath E. Tumors of the pituitary gland. In: *Atlas of tumor pathology.* 2nd series, fascicle 21. Washington, DC: Armed Forces Institute of Pathology, 1986.
11. Scheithauer BW, Kovacs K, Laws ER Jr. The pathology of invasive pituitary tumors with special reference to their functional classification. *J Neurosurg* 1986:65:733-744.
12. Luse SA, Kernohan JW. Granular cell tumors of the stalk and posterior lobe of the pituitary gland. *Cancer* 1955;8:616-622.
13. Albrecht S, Bilbao JM, Kovacs K. Nonpituitary tumors of the sellar region. In: Melmed S, ed. *The pituitary.* New York: Blackwell Science, 1995:591-676.
14. Canbas B, Akar N, Ciplak G, et al. Tumors of the sellar-parasellar region: analysis of 238 cases. In: Samii M, ed. *Skull base surgery.* Basel: Karger, 1992:317-320.
15. Grisoli F, Vincentelli F, Raybaud C, et al. Intrasellar meningioma. *Surg Neurol* 1983:20:36^1.
16. Gay E, Sekhar LN, Rubinstein E, et al. Chordomas and chondrosarcomas of the cranial base: results and follow-up of 60 patients. *Neurosurgery* 1995;56:887-897.
17. Mathews W, Wilson CB. Ectopic intrasellar chordoma. *J Neurosurg* 1974;40:260-263.
18. Max MB, Deck MDF, Rottenberg DA. Pituitary metastasis: incidence in cancer patients and clinical differentiation from pituitary adenoma. *Neurology* 1981;31:998-1002.
19. Roessmann U, Kaufmann B, Friede RL. Metastatic lesions in the sella turcica and pituitary gland. *Cancer* 1970;25:478-480.

20. Branch CL, Laws ER. Metastatic tumors of the sella turcica masquerading as primary pituitary tumors. *J Clin Endocrinol Metab* 1987;65:469-474.
21. Buchmann E, Schweisinger G. Hypophyse und Hamoblastosen. *Zentralbl Neurochir* 1979;40:35-40.
22. Shanklin WM. On the presence of cysts in the human pituitary. *Anat Rec* 1949; 104:379-407.
23. Lee JH. Laws ER Jr, Guthrie BL, et al. Lymphocytic hypophysitis: occurrence in two men. *Neurosurgery* 1994;34: 159-163.
24. Nishio S, Mizuno J, Barrow DL, et al. Isolated histiocytosis X of the pituitary gland. *Neurosurgery* 1987:21:718-721.
25. Taylon C, Duff TA. Giant cell granuloma involving the pituitary gland. *JNeurosurg* 1980:52:584-587.
26. Stern B.I, Krumholtz A. Johns C, et al. Sarcoidosis and its neurological manifestations. *Arch Neural* 1985;42:909-917.
27. Berger SA, Edberg SC. David G. Infectious disease in the sella turcica. *Rev Infect Dis* 1986;8:747-755.
28. Domingue JN, Wilson CB. Pituitary abscesses: report of seven cases and review of the literature. *J Neurosurg* 1977;46:601-608.
29. Ramos-Gabatin A, Jordan RM. Primary pituitary aspergillosis responding to transphenoidal surgery and combined therapy with amphotericin-B and 5-fluoro-cytosine: case report. *J Neurosurg* 1981;54:839-841.
30. Del Brutto OH, Guevar J, Sotelo J. Intrasellar cysticercosis. *J Neurosurg* 1988:69:58-60.
31. Osgen T, Bertan V, Kansu T, et al. Intrasellar hydatid cyst: case report. *Neurosurgery* 1984;60:647-648.
32. Martin JB. Management of hypersecretory pituitary adenomas. *Clin Neurosurg* 1980:27:99-247.
33. Orth DN, Liddle CW. Results of treatment in 108 patients with Gushing's syndrome. *N Engl J Med* 1971;285:243.
34. Wilson CB. Role of surgery in the management of pituitary tumors. *Neurosurg Clin North Am* 1 990; 1 : 1 39-1 59.
35. Benoit R, Pearson-Murphy BE, Robert F. et al. Hyperthyroidism due to a pituitary TSH secreting tumor with amenorrhea-galactorrhea. *Clin Endocrinol* 1980;12:1 1-14.
36. Melmed S, ed. *The pituitary.* New York: Blackwell Science, 1995.
37. Ciric I, Mikhael M, Stafford T, Lawson L, Grarces R. Transsphenoidal management of pituitary macroadenomas with long term follow-up results. *J Neurosurg* 1982; 59:395-401.
38. Cohen AR, Cooper PR, Kupersmith MJ, et al. Visual recovery after transsphenoidal removal of pituitary adenomas. *Neurosurgery* 1985; 17:446-452.
39. Nicola G. Transsphenoidal surgery for pituitary tumors with extrasellar extension. *Progress in Neurological Surgery* 1975:6:149-164.
40. Symon L, Jakubowski J. Transcranial management of pituitary tumors with extrasellar extension. *J Neurol Neurosurg Psychiatry* 1979:42: 123.
41. Schloffer H. Erfulgreiche Operation eines Hypophysentumors suf Nasalm Wege. *Wien Klin Wochamschar* 1907;20:621.
42. Weiss MH. Transnasal transsphenoidal approach. In: Apuzzo MJ, ed. *Surgery of the third ventricle.* Baltimore: Williams & Wilkins, 1987: 476-494.'
43. Hardy J. Transsphenoidal approach to the sella. In: Wilson CD, ed. *Neurosurgical procedures.* Baltimore: Williams & Wilkins, 1992:
44. King WA, Becker DP. Transphenoidal resection of cavernous sinus tumors. In: Samii M, ed. *Skull base surgery.* Basel: Karger, 1992: 458^63.
45. Chiari O. Ueber eine Modifikation der Schloffer' schen Operation von Tumoren der Hypophyse. *Wien Klin Wochenschr* 1912:25:5-6.
46. Black PM, Zerevas NT. Surgical management of sellar and parasellar lesions. In: Schmidik R, Sweet R, eds. *Operative neurosurgical techniques.* 2nd ed. New York: Grune & Stratton, 1988:300-307.
47. Lalwani AK, Kaplan MJ, Gutin PH. The transphenoethmoid approach to the sphenoid sinus and clivus. *Neurosurgery* 1992;3 1:1008-10 14.
48. Galfinos JG, Fitzpatrick BC, Smith LR, et al. Clinical use of a frameless stereotactic arm: results of 325 cases. *J Neurosurg* 1995;83: 197-205.
49. Landolt AM. Prolactinomas: preoperative bromocriptine treatment. *Perspectives in Neurologic Surgery* 1990;!: 105-1 15.
50. Laws ER Jr, Fode NC, Randal RV, et al. Pregnancy following transsphenoidal resection of prolactin-secreting pituitary tumors. *J Neurosurg* 1983:58:685-688.
51. Tindall GT, McLanahan CS, Christy JH. Transphenoidal microsurgery for pituitary tumors associated with hyperprolactinemia. *J Neurosurg* 1978:48:849-860.
52. Landolt AM. Keller PJ, Froesch ER, et al. Bromocriptine: does it jeopardize the result of later surgery for prolactinomas? *Lancet* 1982:2: 657-652.
53. Landolt AM, Osterwalder V. Perivascular fibrosis in prolactinomas: is it increased by bromocriptine? *J Clin Endocrinol Metab* 1984;58: 1179-1182.
54. Besser GM, Wass JAH, Thorner MO. Bromocriptine in the medical management of acromegaly. *Adv Biochem Psychopharmacol* 1980;23: 191-198.
55. Oppizzi C, Luizzi A, Chiodini P, et al. Dopaminergic treatment of acromegaly: different effects of hormone secretion and tumor size. *J Clin Endocrinol Metab* 1984;58:988-992.
56. Ezzat S, Snyder PJ, Young WF, et al. Octreotide treatment of acromegaly: a randomized multicenter study. *Ann Intern Med* 1992: 117:711-718.
57. Laws ER Jr, Piepgras DO, Randall RV. Neurosurgical management of acromegaly: results in 82 patients treated between 1972 and 1977. 7 *Neurosurg* 1979:50:454-461.
58. Laws ER Jr, Randall RV, Abboud CF. Surgical treatment of acromegaly: results in 140 patients. In: Givens J, ed. *Hormone secreting pituitary tumors.* Chicago: Year Book, 1982:225-228.
59. Hardy J. *Atlas of transsphenoidal microsurgery in pituitary tumors.* New York: Igaku-Shoin, 1991.
60. Salassa RM, Laws ER Jr, Carpenter RC, et al. Transsphenoidal removal of pituitary microadenoma in Cushing's disease. *Mayo Clin Proc* 1978;53:24-28.
61. Sonino N, Boscaro M, Merola G, et al. Prolonged treatment of Cushing's disease by ketoconazole. *J Clin Endocrinol Metab* 1985;61: 718-722.
62. Jeffcoate WJ, Rees LH, Tomlin S, et al. Metyrapone in long-term management of Cushing's disease. *Br Med J* 1977:2:215-217.
63. Krieger DT, Amorosa L, Linick F. Cyproheptadme-induced remission of Cushing's disease. *N Engl J Med* 1975:293:893-896.
64. Luton JP, Mahoudeau JA, Bouchard P, et al. Treatment of Cushing's disease by o,p'-DDD: survey of 62 cases. *N Engl J Med* 1979:300: 459^464.
65. Edmonds MW, Simpson WJK, Meakin JW. External irradiation of the hypophysis for Cushing's disease. *Can Med Assoc J* 1972;107: 860-862.
66. Thapar K, Smith M, Elliott E, et al. Corticotroph adenomas of the pituitary: long term results of operative treatment. *Endocrine Pathology* 1992:31:553-555.
67. Thapar K, Laws ER Jr. Pituitary tumors. In: Laws ER Jr, ed. *Brain tumors: basis for individual management.* Philadelphia: JB Lippincott. 1995:759-773.
68. Selman WR, Laws ER Jr, Scheithauer BW, et al. The occurrence of du-ral invasion in pituitary adenomas. *J Neurosurg* 1986:64:402^407.
69. Trautmann JC, Laws ER Jr. Visual status after transsphenoidal surgery at the Mayo Clinic, 1971-1982. *Am J Ophthalmol* 1983;96:200-208.
70. Nelson AT Jr, Tucker H St G, Becker DP. Residual anterior pituitary function following transsphenoidal resection of pituitary macroadenoma.yAfeMrom/-g 1984:61:577-580.
71. Decker RE, Chalif DJ. Progressive coma after the transphenoidal decompression of a pituitary adenoma with marked suprasellar extension. *Neurosurgery* 1991;28:154-158.
72. Pernicone PJ, Scheithauer BW. Invasive pituitary adenomas and pituitary carcinomas. In: Lloyd RV, ed. *Surgical pathology of the pituitary gland.* Philadelphia: WB Saunders, 1993:121-136.
73. Northfield DWC, Rathke-pouch tumors. *Brain* 1957:80:293-301.
74. Litofsky NS. Levy ML, Apuzzo MLJ. Craniopharyngioma. In: Apuzzo MLJ, ed. *Brain surgery: complication avoidance and management.* New York: Churchill Livingstone, 1993:313-378.
75. Yasargil MG, Curcic M, Kis M, et al. Total removal of craniopharyngiomas: approaches and long-term results in 144 patients. *J Neurosurg* 1990:73:3-11.
76. Baskin DS, Wilson CP. Surgical management of craniopharyngiomas: a review of 74 cases../ *Neurosurg* 1986;65:22-27.
77. Hug EB. Fitzek MM, Liebsch HJ, Muzenrider KJE. Locally challenging osteo- and chondrogenic tumors of the axial skeleton: results of combined proton and photon radiation therapy using three-dimensional treatment planning. *Int J Radiat Oncol Biol Phys* 1995;31:467^76.
78. Austin-Seymour M, Munzenrider J, Goitein M, et al. Fractionated proton radiation therapy of chordoma and lowgrade chondrosarcoma of the base of the skull. *J Neurosurg* 1989;70:13-17.

SECTION V

Adjunctive Considerations

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 29

Complications

PaulJ. Donald

The initial reluctance to accept skull base surgery by the medical community was in part based on the fear that there would be an unacceptably high complication rate. This is especially because of the exposure of the delicate structures in the intracranial space to the sea of microbes that reside in the nose, paranasal sinuses, nasopharynx, and oral cavity. Table 1 is a compilation of reports of the most important complications in skull base surgery, cerebrospinal fluid (CSF) leak, and meningitis. Another deterrent was related in particular to malignant tumors and the notion that dural or brain involvement portended a hopeless prognosis.

Unfortunately, complications do indeed occur, and every chapter on surgical technique in this book has outlined what the complications are, and briefly how to manage them. The purpose of this chapter is to give a more detailed discussion of the prevention and management of each complication. In the instances when such problems and their solutions have been well described, the section is simply referred to and only briefly mentioned here.

The chapter first discusses how to prevent complications, and second, if they occur, how to treat them. The focus is directed toward the complications at the operative site, and little attention is given to other systemic complications such as pneumonia, cardiac decompensation, and the like, except when they arise directly as a result of another complication of the surgery such as cranial nerve compromise. Detailed accounts of these latter problems are found in Chapter 30, on postoperative management, and Chapter 8, on nursing care.

PREVENTION

Preoperative Preparation

The prevention of intraoperative and postoperative complications begins at the preoperative assessment. A thorough history and physical examination and a complete review of past records, radiographs, and pathology reports is essential. The initial encounter with the average skull base surgery patient takes about 45 to 60 minutes. As mentioned in Chapter 5, most patients have already received some form of prior therapy. It is essential to review all operative records and discharge summaries as well as the patient's and the family's own interpretation of these events.

As previously mentioned, not only are the pathology reports reviewed, but it is essential that the tissue block and histologic slides be reviewed by the skull base team's own head and neck pathologist.

The patient's intercurrent disease status must be carefully reviewed and the function of all organ systems optimized before surgery. Cardiac, pulmonary, renal, and hepatic function must be fine tuned for the rigors of skull base surgery. Moreover, if the patient's intercurrent disease processes are too severe, skull base surgery is contraindicated. The appropriateness of type and dosage of all medications is reviewed. A careful inquiry concerning the use of salicylates and other anticoagulant medications is made, and these medications stopped in sufficient time before surgery to prevent bleeding during surgery.

All radiographs are reviewed, keeping in mind the fact that these studies not infrequently inaccurately represent the extent of disease.

The patient is mentally prepared as best as possible before surgery. A relaxed, confident, reassured patient will do much better than a frightened one. A carefully coordinated, orderly surgical plan is conceptualized, bearing in mind the prevention of complications. The surgeons, anesthetists, and nurses must organize their efforts to have an effective therapeutic plan that ablates the disease but is continuously cognizant of the fine details that preclude the development of a complication.

Surgical Preparation

The prevention begins in the initial phases of surgical preparation. An early, quick start to the case goes a long way to ensuring a timely ending. Often, the longer the procedure

---

P. J. Donald: Department of Otolaryngology—Head and Neck Surgery, and Center for Skull Base Surgery, University of California, Davis Medical Center, Sacramento, California 95817.

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers, Philadelphia © 1998.

CHAPTER 31

Free Flaps in Skull Base Surgery

Jonathan E. Aviv and Mark R. Sultan

The field of cranial base surgery, although originating in the 1960s, has been expanding greatly since the mid-1980s (1,2). There are several reasons for this expansion. First, diagnostic tools such as magnetic resonance imaging (MRI) and high-resolution computed tomography (CT) scanning have improved markedly (3-5). Second, advances in interventional neuroradiology have enhanced both the ability to map precisely the extent of neoplasms as well as the ability to decrease their vascularity through superselective embolization (6). Third, surgical approaches to the skull base through new transfacial and craniofacial incisions have greatly improved the head and neck surgeon's safe access to the skull base. As the techniques for diagnosis and extirpation of skull base lesions have become more sophisticated, tumors previously deemed "unresectable" are now being pursued vigorously. However, without an ability to definitively and reliably reconstruct defects resulting from the resection of skull base tumors, the oncologic strides made would not be realized. Fortunately, concomitant with advances in radiographic imaging and surgical approaches, there has been an equal interest and development of expertise in reconstructive microvascular surgery.

Clearly, not all cranial base defects require free tissue transfer for their closure. In many cases, local flaps such as temporalis muscle and fascia or pericranium can provide adequate vascularized tissue to reconstruct small defects of the anterior or posterior cranial fossae (7). However, for defects involving exposure of the paranasal sinuses, nasopharynx, oropharynx, or hypopharynx, local, regional, or pedicled flaps from the trunk are often insufficient to safely achieve the goals of the reconstructive effort.

HISTORY

The description of free flaps for use in skull base reconstruction began in the early 1970s with a report by McLean and Buncke describing the use of omentum to reconstruct a large scalp defect (8). Since then, studies describing the application of free flaps for skull base reconstruction have proliferated. With refinements in microvascular surgical techniques, variations in the use of muscle flaps—the rectus abdominis in particular—have been described that have increased the versatility of various donor sites for application to geometrically complex skull base defects. These variations include using free muscle with overlying skin, fat, and deepithelialized skin (9).

For complex defects of the cranial base that involve the midface, free latissimus dorsi flaps have been described (10,11), either alone or in combination with other subscapu-lar system flaps (12).

In addition to muscle-only and myocutaneous free flaps, cutaneous free flaps have been advocated for skull base reconstruction (13-15).

PATIENT SELECTION FACTORS

Considerations such as age, cardiopulmonary status, nutritional status, and underlying competency of the immune system, although germane to free flap reconstruction in general, are particularly important in patients undergoing skull base tumor surgery.

In skull base cases where the primary tumor is not in the neck, the recipient vessels for a microvascular anastomosis are readily and easily found in the neck. Typically, branches of the external carotid arterial system, and the facial artery in particular, are readily accessible for the artery from the flap. The external jugular vein and its venous tributaries, such as the posterior facial vein, are extremely reliable recipient vessels for the venous anastomosis. In cases where the neck has been irradiated, the possible use of vein grafts needs to be

J. E. Aviv: Department of Otolaryngology, Head and Neck Surgery, College of Physicians and Surgeons, Columbia University, and Columbia Presbyterian Medical Center, New York, New York 10032.

M. R. Sultan: Department of Surgery, St. Luke's/Roosevelt Hospital, New York, New York 10019.

considered because it has been demonstrated experimentally that radiation therapy may injure blood vessels, thereby increasing the chance for a failed microvascular anastomosis (16). The superficial temporal vessels may be considered as potential recipient vessels because of their proximity to the lateral skull base. However, the artery, and particularly the vein, may be of moderate caliber or poor quality, thus precluding reliable use. Because most of the commonly used free flaps in skull base reconstruction have long pedicles, the superficial temporal vessels can usually be avoided in preference to larger-caliber neck vessels without the need for vein grafts.

GOALS OF CRANIAL BASE RECONSTRUCTION

When faced with massive, composite defects of the craniofacial region, it is important to keep in mind the goals of the reconstructive effort. The primary goal is to seal the intradural space from the extradural space, thus preventing cerebrospinal fluid (CSF) leak, ascending infection, and fulminant meningitis.

The choices of tissue that can be used to restore form as well as function depend on a number of factors, including the nature of the defect, the underlying disease process, the available donor sites, and the preferences and skills of the reconstructive surgeon.

Local free grafts of dermis, fascia, or muscle may be satisfactory when applied to small defects. However, in irradiated, scarred recipient beds, or in chronically infected cavities with large defects, regional pedicled flaps or distant free flaps provide a greater volume of reliable tissue. The distinct advantage of free flaps is that they have independent vascularity and can be more accurately contoured to the defect. Also, the problem of gravitational pull from the donor site is avoided.

The ideal donor site for restoring form and function to craniofacial defects should offer a substantial amount of pliable tissue that has a long vascular pedicle with large-diameter vessels. In addition, two surgical teams should be able to work simultaneously: the oncologic team at the head, and the reconstructive team harvesting tissue from a donor site that will not functionally or cosmetically impair the patient. Although no single flap consistently meets all of these criteria, the latissimus dorsi, serratus anterior, radial forearm, rectus abdominis, and scapular system free flaps are among the most commonly chosen free flaps for skull base defect reconstruction because they often best fulfill the aforementioned criteria. Other, less commonly used free flaps for this purpose are the omental, gracilis, and deep circumflex iliac artery flaps.

RADIAL FOREARM FREE FLAP

For limited defects with complex geometry, thin, pliable tissue is required, and the fasciocutaneous radial forearm free flap is very useful.

Anatomy

The radial forearm flap is based on the radial artery and cephalic vein and can be designed to transfer the skin of the volar aspect of the forearm extending from the antecubital fossa to the level of the flexor retinaculum (13). In addition, one of the sensory nerves to the forearm, either the medial or lateral antebrachial cutaneous nerves, can be harvested as well, should a sensate flap be desired (14).

Vascularized bone can also be provided by this flap by inclusion of a cuff of the flexor pollicis longus over the radius. In a man, one third of the diameter of the radius with a length approaching 14 cm is available. However, the relatively high incidence of donor site morbidity, including pathologic fracture of the radius, coupled with the fact that better sources of vascularized bone exist, preclude its widespread use for this purpose (17).

Although the radial forearm free flap usually is not bulky enough when reconstructing large cranial base defects, it has been shown to be a very reliable method of reconstructing geometrically complex cranial base defects (15). Figures 1 through 7 illustrate the application of a radial forearm free flap in reconstructing a complicated, contained defect of the anterior cranial fossa.

CASE1

A 64-year-old man had an adenoid cystic carcinoma of the ethmoid sinus that extended superiorly into the anterior cranial fossa. The patient had originally undergone a craniofacial resection and orbital exenteration and was to undergo a secondary cranioplasty. However, a nasocutaneous .fistula as well as an extradural-cuta-neous fistula developed in the patient (see Fig. 1), resulting in pneumocephalus (see Fig. 2) and severe headaches. Before the cranioplasly, the patient required closure of the communication between the orbital cavity, the nasal cavity, and the extradural space. To secure such a reconstruction, a radial forearm free flap was planned (see Fig. 3). The skin paddle was designed with a central cutaneous portion with two "tabs" on either side of the central skin paddle (see Fig. 4). The purpose of this design modification was to tuck vascularized, deepithelialized tissue into the geometrically complex confines of the nasal and orbital cavities, thereby sealing the nose and orbit from intracranial exposure (see Figs. 5, 6). The donor vessels were tunneled subcutaneously under the skin of the cheek into the neck (see Fig. 4). The recipient vessels for the microvascular anastomoses were the external jugular vein and the facial artery.

After surgery, the patient did well with resolution of headache. With the patient's infection controlled, he subsequently underwent a cranioplasty with an acceptable cosmetic result 1 year after surgery (see Fig. 7).

CASE 1 (Continued)



FIG. 1. Case 1. Preoperative lateral view of patient status resection of adenoid cystic carcinoma of ethmoid sinus that extended into the anterior cranial fossa.



FIG. 2. Case 1. Magnetic resonance image demonstrating extensive pneumocephalus.



FIG. 3. Case 1. Harvested radial forearm free flap demonstrating the radial artery and its venae comitantes, the cephalic vein, and the lateral antebrachial cutaneous nerve.



FIG. 4. Case 1. Radial forearm free flap being inset into nasal and orbital cavities. The neurovascular structures are shown along the cheek, directed toward the recipient vessels in the neck.

CASE 1 (Continued)



FIG. 5. Case 1. Deepithelializing portions of the radial forearm free flap allowed the nasal and orbital cavities to be sealed from intracranial communication.



FIG. 6, Case 1. Immediate postoperative view.



FIG. 7. Case 1. Patient about 12 months after surgery, free of headache and after cranioplasty.

Advantages

The advantages of the radial forearm free flap include the thin, pliable tissue it provides as well as the fact that its vascular pedicle is long and has a large diameter. The fact that the llap has sensate potential may be relevant only when reconstructing cranial base defects involving the nasopharynx.

Disadvantages

The greatest shortcoming of this flap is that its surface area is limited, which makes the flap unsuitable for resurfacing large defects.

RECTUS ABDOMINIS

The rectus abdominis free flap has emerged as the "workhorse" flap for reconstructing most extensive cranial base defects because it offers several distinct advantages over other soft tissue flaps (11). These include its long, large, and constant vascular pedicle, its large size, and low donor site morbidity. Furthermore, with the patient in the supine position, ils distant location from the head and neck allows for simultaneous harvest as the skull base resection is being performed.

Anatomy

The blood supply to this flap is the deep inferior epigastric artery and vein, which enter the lateral border of the rectus muscle halfway between the pubis and umbilicus, just below the arcuate line (18). Although the superior epigastric vessels also supply the rectus abdominis muscle, the deep inferior epigastric vessels are a more reliable and accessible vascular supply for this free flap (19).

CASE 2

A 40-year-old diabetic woman weighing over 350 pounds had a recurrent meningioma of the frontal lobe resected and. after surgery, lost her frontal bone flap to infection (Pig. 8). Subsequently. CSF rhinorrhea, fulminant meningitis, and a large frontal lobe abscess developed in the palient (Fig. 9).

The patient was taken to the operating room to drain the abscess and to separate the nasal cavity from the dura and brain (Pig. 10). To cover the defect and lo seal the intradural space from the exlradural space, a large volume of vascularized tissue was required. Therefore, a rectus abdominis muscle free flap was harvested (Figs. 11, 12).

The muscle was placed carefully along the anterior cranial fossa and tacked into position (Fig. 13). The vascular pedicle was oriented along the preauricular region and anastomosed to recipient vessels in the neck (Fig. 14).

In closing the facial skin flap, a small portion of rectus muscle was left exposed in the preauricular region to monitor the flap. Within 72 hours after surgery, there was no further CSF leak and the patient ultimately recovered from her meningitis.



FIG. 8. Case 2. Preoperative view, from above, of diabetic patient who has lost her frontal bone flap secondary to infection.



FIG. 9. Case 2. Forehead skin flap is elevated and what is being visualized is a sea of pus overlying, and adherent to, the dura of the frontal lobe. At the center of the wound is the superior aspect of the nasal cavity, which contains remnants of polypoid sinus mucosa.



FIG. 10. Case 2. The sinus mucosa was completely removed and the infected material on the dura was carefully de-brided, leaving a sizable dural defect.



FIG. 12. Case 2. Rectus abdominis muscle harvested with the vascular pedicle exiting laterally,



FIG. 11. Case 2. These are the landmarks of the anterior abdominal wall that allow an approximate mapping of the topographic anatomy of the rectus abdominis muscle. The rectus muscle is shown extending from the pubis to the inferior costal margin. Also shown is the linea alba, which represents the medial extent of the rectus muscle, extending from the pubis to the midline of the xiphoid process. The linea semilu-narts, which represents the lateral extent of the rectus muscle, is located about halfway between the anterior superior iliac spine (ASIS) and the midline. Note also the arcuate line—below which the posterior rectus sheath is composed only of transversus abdominis aponeurosis. It is located roughly at the level of the ASIS.

CASE 2 (Continued)



FIG. 13. Case 2. The rectus abdominis muscle free flap placed along the floor of the anterior cranial fossa.



FIG. 14. Case 2. The vascular pedicle was brought along the preauricular region and anastomosed to recipient vessels in the neck.

CASE 3

A 64-year-old man had a recurrent squamous cell carcinoma of the orbital and nasal skin that grossly involved the eye, forehead, nasal dorsum, and underlying facial and frontal bones (Figs. 15, 16). An *en bloc* orbital exenteration was performed, including full-thickness loss of skin, muscle, and bone involving the nasal dorsum and forehead, as well as a portion of the dura of the frontal lobe (Figs. 17, 18). The reconstructive challenge included separation of the intracranial space from the nose and paranasal sinuses. A vascularized pericranial flap was used to patch the dura. A free rectus muscle flap was used to reconstruct the anterior cranial base defect (Fig. 19), with the ipsilateral superficial temporal vessels serving as the recipient vessels. A split-thickness skin graft was placed over the rectus muscle (Fig. 20). After surgery, in the intensive care unit, the patient had an acute myocardial infarction and hypotension. The patient was immediately and successfully resuscitated with no loss of flap viability or development of CSF leak. On follow-up examinations, he did quite well, with primary healing of his wound (Figs. 21, 22).



FIG. 15. Case 3. Preoperative view of a large left orbital squamous cell carcinoma involving the globe and frontal bone.



FIG. 16. Case 3. Magnetic resonance image showing gross involvement of the entire left orbital cavity with tumor.



FIG. 17. Case 3. Outline of resection margin of tumor.



FIG. 18. Case 3. Surgical defect after *en bloc* orbital exenteration with surrounding skin, muscle, and bone.

CASE 3 (Continued)



FIG. 19. Case 3. Reconstruction of defect from Fig. 18 with free rectus muscle flap.



FIG. 20. Case 3. Postoperative anteroposterior view of patient 4 months after surgery.



FIG. 21. Case 3. Lateral postoperative view of patient showing contralateral extent of reconstructed nasal dorsum. Note proximity of reconstructed region to remaining orbit.



FIG. 22. Case 3. Lateral postoperative view of patient.

Advantages

The rectus abdominis free flap can be harvested with the patient in a supine or semiseated position, which is the usual position for most neurosurgical and head and neck procedures. It is located at a sufficiently remote distance from the head so that a simultaneous two-team approach can be carried out comfortably. The vascular pedicle is long and has a large diameter, and the surface area that can be harvested is extremely large, second only to the latissimus dorsi-scapula (12).

Disadvantages

The primary disadvantage of the rectus abdominis free flap is its bulk when it is used with its overlying skin because of the width of the subcutaneous tissues of the abdominal wall. This is particularly true in women or overweight patients. This may be avoided by harvesting muscle only and covering the muscle with a skin graft as needed.

LATISSIMUS DORSI AND SERRATUS ANTERIOR FREE FLAPS

Both the latissimus dorsi and serratus anterior muscles should be considered as potential donor flaps when the skull base defects are extensive. Either alone and certainly the two1 in combination can provide a large amount of well vascil ized muscle with long vascular pedicles.

Anatomy

The latissimus dorsi muscle is a large muscle that originates from the thoracic spinous processes and posterior iliac crest and inserts into the posterior portion of the humerus. it is supplied by the thoracodorsal nerve and vessels. The vessels originate from the subscapular artery and vein. Although its function is to adduct and inwardly rotate the arm, virtually the entire muscle may be used as a flap with little impact on shoulder function (20).

The serratus anterior muscle is also a large muscle that originates from the lateral border of the upper eighth to ninth ribs and inserts on the undersurface of the scapula. The serratus anterior thus assists in stabilizing the shoulder during rotation. Because of this, the upper three or four slips of the muscle and their innervation by the long thoracic nerve should be spared whenever possible to prevent winging of the scapula. The serratus anterior is vascularized by crossing branches of the thoracodorsal vessels. The thoracodorsals are routinely included in the vascular pedicle harvest to increase its length (21).

CASE 4

A 64-year-old man presented with a frontal lobe abscess and frontal bone flap osteomyelitis {Fig. 23). Twenty years previously, he underwent resection of a frontal lobe meningioma. Five years later he underwent a second resection and radiation therapy for recurrent disease. Subsequently, he had right-sided weakness and expressive aphasia. An MRI revealed an abscess in his frontal lobe (Fig. 24). Operative debridement of all devitalized brain, the overlying bone flap, and the necrotic scalp was carried out (Fig. 25), A free latissimus muscle flap was then used to obliterate the potential space in the frontal lobe and to reconstruct the scalp (Fig. 26). The



FIG. 23. Case 4. Preoperative view of scalp of patient with frontal bone osteomyelitis and frontal lobe abscess.

CASE 4 (Continued)

thoracodorsal vessels were anastomosed to the facial vessels primarily without vein grafts. The muscle was covered with split-thickness skin grafts (Figs. 27, 28). No bony reconstruction was **carried** out. The patient's postoperative course was uneventful.



FIG. 24. Case 4. Preoperative coronal magnetic resonance image demonstrating abscess in the frontal lobe of the brain.



FIG. 26. Case 4. Free latissimus dorsi muscle flap inset into cranial defect with overlying split-thickness skin graft.



FIG. 25. Case 4. Defect after debridement of devitalized brain, overlying bone flap, and necrotic scalp.



FIG. 27. Case 4. Postoperative aerial view of patient 6 months after surgery.

CASE 4 (Continued*



FIG. 28. Case 4. Postoperative lateral view of patient 6 months after surgery.

Advantages

The latissimus dorsi muscle flap is used frequently in reconstructive surgery because of its large size, ease of dissection, length and caliber of its vascular pedicle, and minimal donor site morbidity. These characteristics make it ideal as a free flap for closure of large skull base defects. Rarely are vein grafts needed to reach appropriate recipient vessels in the neck.

The serratus anterior muscle flap shares the same long vascular pedicle as the latissimus dorsi, and therefore can easily be included with the latissimus as one flap when a great deal of vascularized muscle is needed. The serratus flap provides less muscle surface area than the latissimus but does not have the bulky tendinous portion of the latter, thereby making it better suited for the reconstruction of some skull base and scalp wounds.

Disadvantages

As with subscapular system free flaps, the principal disadvantage of the latissimus dorsi and serratus anterior flap is the need to harvest the flaps with the patient in the lateral decubitus position. When used as a myocutaneous flap, the latissimus dorsi flap is too bulky. Use of muscle only covered with skin grafts negates this problem. Winging of the scapula often leads to chronic shoulder pain. When harvesting a serratus anterior muscle free flap, the potential for this complication could be avoided by using only the lower one half of the muscle.

SUBSCAPULAR SYSTLM FREE FLAPS

When the surgeon is faced with massive composite defects of the scalp and midface, the rectus abdominis free flap usually does not provide enough versatility in the selection of tissue for use in reconstruction. In such cases, the system of flaps based on the subscapular artery and vein can be used. The flaps that can be harvested based on this single vascular pedicle include the scapular and parascapular skin flaps (22). the serratus anterior and latissimus dorsi muscle flaps (23). and the lateral scapular bone flap (24,25).

By combining the latissimus dorsi myocutaneous flap with the scapular or parascapular cutaneous or osteocutaneous flap, massive composite cranial base defects can be reconstructed.

Anatomy

The subscapular artery divides into the circumflex scapular artery and the thoracodorsal artery. The circumflex scapular artery provides the blood supply to the scapular skin, parascapular skin, and lateral scapular bones. The thoracodorsal artery supplies the latissimus dorsi muscle and skin.

CASE 5

A 53-year-old man presented with a neglected basal cell carcinoma involving a large segment of his scalp, underlying bone and dura, the right frontal and elhmoid sinuses, and his orbit and globe (Fig. *29)*. He underwent an extensive resection including all of the aforementioned structures (Fig. 30). Reconstruction therefore mandated definitive separation of the sinuses from the dura and brain as well as restoration of the bony and cutaneous defects.

The dura was first repaired with a tensor fascia lata graft. This was followed by a split-rib cranioplasty. A complex subscapular system free flap was then harvested. This was composed of a bipennate skin flap based on the transverse and descending fasciocutaneous branches of the circumflex scapular vessels, the latissimus dorsi muscle, and a 10-cm segment of the lateral scapula vascularized by the angular branches of the thoracodorsal vessels (Figs. 31-33). All segments were joined at their common origin at the subscapular artery and vein. The muscle was used to reinforce the dura! defect and separate the dura from the paranasal sinuses. The scapular bone restored the supraorbital bar and the fasciocutaneous component replaced the scalp. A single set of microanastamoses was completed to the facial artery and external jugular vein without vein grafts. The patient healed all wounds primarily without any evidence of CSF leak (Fig. 34). Unfortunately, he was lost lo follow-up soon thereafter.



FIG. 29. Case 5. Preoperative view of large basal cell carcinoma involving scalp, bone, dura, paranasal sinuses, orbit, and globe.



FIG. 30. Case 5. Defect after *en* ***bloc*** **orbital** exenteration **including** surrounding skin, muscle, bone, and dura.



FIG. 31. Case **5. Outline** of bipennate scapula skin flap based on the transverse and descending fasciocutaneous branches of the circumflex scapular vessels.



FIG. 32. Case 5. Harvested, combined scapula-latissimus dorsi skin, muscle, and bone free flap all based on the sub-scapular vessels. Note the latissimus dorsi muscle and a 10-cm segment of the lateral scapular bone vascutarized by the angular branches of the thoracodorsal vessels. Compare with Fig. 33.

CASE 5 (Continued)


Circumflex scapular a.
Angular branch
Thoracodorsal a
Subscapular a.

FIG, 33. Case 5. Schematic of flap shown in Fig. 32, emphasizing versatility of the scapular bone when based on the angular branch of the thoracodorsal vessels.



FIG. 34. Case 5. Postoperative view of patient 2 weeks after surgery.

Advantages

The combined latissimus dorsi-scapular free flap offers the largest surface area of composite tissue based on one pedicle. Another advantage is the three-dimensional maneuverability of its components because of their independent vascular pedicles.

A potential advantage of this flap is the ability to transfer innervated muscle to maintain bulk or dynamic activity for use in facial animation.

Disadvantages

The most important disadvantage of this combined flap is that it requires the lateral decubitus position for flap harvesting.

Donor site is another potential disadvantage. Scapular-humeral rotation can be severely limited after a scapular osteocutaneous flap, so physical therapy is essential for the rehabilitation of these patients (26).

CONCLUSION

Free tissue transfer techniques increase the reconstructive options available in treating patients with extensive, often disfiguring tumors. These reconstructive options may allow a greater chance for palliative or curative resection of select lesions and may ultimately result in better care for the head and neck cancer patient.

REFERENCES

Tessier P. Osteotomies totales de la face: syndrome de Crouzon, syndrome d'Apert, oxycephalies, scaphocephalies, turricephalies. *Annales de Chirugie Plastique* 1967:12:273-286.

Ketcham AS, Wilkins RH, Van Buren JM. A combined intracramal facial approach to the paranasal sinuses. *Am J Surg* 1963; 106:698-703. Olsen WL, Dillon WP, Kelly WM, Norman D, Brant-Zawadzki M, Newton TH. MR imaging of paragangliomas. *AJNR Am J Neuroradiol* 1986:7:1039-1042.

Som PM, Dillon WP, Sze G, Lidov M, Biller HF, Lawson W. Benign and malignant sinonasal lesions with intracranial extension: differentiation with MR imaging. *Radiology* 1989:172:763-766. Oot RF, Melville GE, New PFJ, et al. The role of MR and CT in evaluating clival chondroma and chondrosarcomas. *AJNR Am J Neuroradiol* 1988;9:715-723.

6. Zanella FE, Valavanis A. Interventional neuroradiology of lesions of the skull base. *Neuroimaging Clin N Am* 1994:4:619-637.
7. Baker SR. Surgical Reconstruction after extensive skull base surgery. *Otolaryngol Clin North Am* 1984:17:591-599.
8. McLean DH, Buncke HJ. Autotransplant of omentum to a large scalp defect with microsurgical revascularization. *Plant Reconstr Surg* 172;49:268-274.
9. Izquierdo R. Leonetti JP, Origitano TG, Al-Mefty 0, Anderson DE, Reichman OH. Refinements using free-tissue transfer for complex cranial base reconstruction. *Plast Reconstr Surg* 1993;92:567-574.
10. Jones NF, Hardesty RA, Swan?. WM, Ramasastry SS, Heckler FR, Newton ED. Extensive and complex defects of the scalp, middle third of the face, and palate: the role of microvascular reconstruction. *Plast Reconstr Surg* 1988:82:937-950.
11. Jones NF, Sekhar LN, Schramm VL. Free rectus abdominous muscle flap reconstruction of the middle and posterior cranial base. *Plast Reconstr Surf;* 1986:78:471-477.
12. Aviv JE, Urken ML, Vickery C, Weinberg H, Buchbinder D, Biller HF. The combined latissimus dorsi-scapular free flap in head and neck reconstruction. *Arch Otolaryngol Head Neck Surg* 1991;! 17:1242-1250.
13. Song R, Gao Y, Song Y, Yu Y. The forearm flap. *Clin Plast Surg* 1982;9:21-26.
14. Urken ML, Weinberg H, Vickery C, Biller HF. The neurofasciocutaneous radial forearm free flap in head and neck reconstruction: a preliminary report. *Laryngoscope* 1990:100:161-173.
15. Chicarilli ZN, Ariyan S, Cuono CB. Single-stage repair of complex scalp and cranial defects with the free radial forearm flap. *Plast Reconstr Surg* 1986:77:577-585.
16. Watson JS. Experimental microsurgical anastomosis in radiated vessels: a study of patency rates and the histopathology of healing. *Plast Reconstr Surg* 1979:63: 525-533.
17. Boorman JG, Brown JA, Sykes PJ. Morbidity in the forearm flap donor area. *Br J Plast Surg* 1987:40:207-212.
18. Taylor GI, Corlctt RS. Boyd JB. The versatile deep inferior epigastric (inferior rectus abdominous) flap. *Br J Plast Surg* 1984;37:330-35().
19. Boyd JB. Taylor GI, Corlett RS. The vascular territories of the superior epigastric and the deep inferior epigastric systems. *Plast Reconstr Surg* 1984:73:1-14.
20. Hardesty RA, Jones NF, Swartz WM, et al. Microsurgery for macro defects: microvascular free-tissue transfer for massive defects of the head and neck. *Am J Surg* 1987;154:399^05.
21. Takajangi T, Tsukie T. Free Serratus anterior muscle and myocutaneous flaps. *Ann Plast Surg* 1982:8:277-283.
22. Nassif TM, Vidal L, Bovet JL, Baudet J. The parascapular flap: a new cutaneous microsurgical free flap. *Plast Reconstr Surg* 1982;69: 591-600.
23. Haril K, Yamada A, Ishihara K, Miki Y, Itoh M. A free transfer of both latissimus dorsi and serratus anterior flaps with thoracodorsal vessel anastomosis. *Plast Reconstr Surg* 1982;70:620-629.
24. Swartz WM, Banis .1C, Newton ED. Ramasastry SS, Jones NF, Acland R. The osteocutaneous scapular flap for mandibular and maxillary reconstruction. *Plast Reconstr Surg* 1986;77:530-545.
25. Baker SR, Sullivan MJ. Osteocutaneous free scapular flap for one stage mandibular reconstruction. *Arch Otolaryngol Head Neck Surg* 1988:114:267-277.
26. Sullivan MJ, Baker SR, Crompton R. Smith-Wheelock M. Free scapular osteocutaneous flap for mandibular reconstruction. *Otolaryngol Head Neck Surg* 1989:115:1334-1340.

Surgery of the Skull Base, edited by Paul J. Donald.
Lippincott-Raven Publishers. Philadelphia €> 1998.

CHAPTER 32

Reconstruction of the Skull Base with Regional Flaps and Grafts

James L. Netterville and C. Gary Jackson

With the advancement of surgical and rehabilitation techniques, more extensive tumors of the skull base can be successfully removed. Significant tissue loss is common during these procedures, mandating some form of reconstruction. Often, after a resection that results in dural loss or carotid exposure, bulk replacement alone is inadequate. Dural closure, as well as carotid isolation and coverage, must be carefully addressed. Infrequently, to complete the resection, the sinuses or the pharynx must be entered. Adequate tissue transfer to seal this region is mandatory to prevent salivary contamination of the exposed carotid or the dural reconstruction.

Reconstruction of this area is complicated by several factors. First, there is a dearth of local tissue that can be transferred into the defect that will provide significant bulk. The temporalis fascia, which is discussed subsequently, is excellent for dural closure, but minimal bulk is provided by its transfer. The authors have found, contrary to previous reports, that the temporalis muscle does not provide the necessary tissue volume when rotated into most temporal defects. It is most useful in repairing defects in the clival and middle fossa region. However, its rotation leaves a significant cosmetic defect in the temporal fossa, necessitating further reconstruction. There are no other local muscle transfers that can dependably be rotated with an intact vascular supply. Vascular ligation or injury of the external carotid system or the superficial temporal artery further limits the use of the temporalis muscle and fascia.

Second, previous radiation treatment to the parapharyngeal region significantly decreases tissue perfusion, which interferes with normal postoperative healing. Previous treatment with radiation is a strong indication for vascularized tissue reconstruction. With previous radiation, free nonvascularized fascial grafts with fat transfer for bulk may result in reconstruction failure with a resultant cerebrospinal fluid (CSF) leak.

Finally, many of these patients have undergone one or more surgical procedures before referral. Previous surgery not only increases the difficulty of the procedures but also adds to poor tissue perfusion secondary to scar tissue. With revision surgery it is necessary to perform a more comprehensive resection to clear the recurrent disease embedded within the scar tissue after the previous procedure. This increases the need for vascularized tissue transfer.

There are five basic principles guiding the reconstruction effort: (a) to provide coverage of vital structures; (b) to seal the CSF within the intradural space; (c) to reconstruct cosmetically the tissue loss; (d) if hearing is retained, to maintain an aerated middle ear space with eustachian tube function; and (e) to keep it as simple as possible. If these principles can be adhered to, then the postoperative rehabilitation phase is significantly decreased. Rather than tailoring the defect to the latest fad in reconstruction, the simplest form of reconstruction consistent with the aforementioned principles is used. This protocol is modified by the health of the patient, which must be taken into account when considering the added risk of additional procedures. A graduated sequence of reconstructive techniques is used to accomplish these goals (Table 1). Whenever possible, local vascularized fascia is rotated to seal the dural defect. This includes pericranial or galeal-frontalis rotation for the anterior cranial region, and either superficial or deep temporal fascia for the lateral skull base region. In nonirradiated patients, free fascial grafts may perform just as well as rotation flaps. In small defects in the lateral skull base or temporal region, a nonvascularized transfer of abdominal fat on top of the fascial graft may add sufficient bulk to prevent CSF leak. This fat atrophies over time and results in a concave appearance of the defect. When nonvascularized fat transfer is inadequate, a myocutaneous or free flap transfer is considered. The addition of these techniques has greatly reduced the incidence of

TABLE 1. *A graduated sequence of reconstruction options for skull base defects*

1. Nonvascularized facial grafts
2. Fibrin glue
3. Nonvascularized fat transfer
4. Vascularized facial flaps
   a. Superficial temporoparietal fascia b.
   Deep temporoparietal fascia c.
   Pericranial d. Galeal-frontalis
5. Temporalis muscle transfer
6. Myocutaneous flaps a.
   Pectoralis b. Lower

J. L. Netterville: Department of Otolaryngology, Vanderbill Medical Center, Nashville, Tennessee 37232.

C. G. Jackson: Department of Otolaryngology, Head and Neck Surgery, Vanderbuilt University School of Medicine, and The Otology Group, Baptist Medical Center, Nashville, Tennessee 37203.

    trapezius c. Latissimus dorsi
7. Free tissue transfer

postoperative CSF leak with its attendant complications (1). In a stepwise fashion, the use, advantages, and disadvantages of each of these techniques are described.

Although this chapter concentrates on reconstructive methods, the manner in which overlying structures are mobilized for tumor exposure can save tissue layers, greatly improving the quality of the reconstruction.

INITIAL SURGICAL EXPOSURE

During anterior skull base surgery the authors are careful, throughout the initial exposure, to protect and mobilize the pericranial and galeal layers for later use in reconstruction. During lateral skull base approaches, this same careful consideration during initial tumor exposure can greatly facilitate the reconstruction. Several steps in the surgical approach that facilitate reconstruction are highlighted.

The postauricular "C" incision is used to approach most tumors involving the temporal bone and its surrounding structures (Fig. 1). This incision is laid out approximately 5 cm above the helix, curving behind the helix into a cervical crease line. With standard technique, an incision in this region extends through the superficial temporal fascia to the plane overlying the deep temporal fascia. Thus, an incision so outlined foreshortens the superficial temporal fascial flap to 5 to 6 cm, which is not enough length to reline most lateral skull base defects. To remedy this, the authors initially moved this incision up to 10 cm above the helix. The superficial temporal fascia was elevated up with the skin in standard fashion until needed for reconstruction. It was then harvested off the deep surface of the elevated skin flap. Although this provided excellent length and size of the superficial temporal fascial flap, the authors noted significant scalp loss on the superior edge of the scalp flap in 5% of patients. To rectify this, the incision is now outlined 5 cm above the auricle, but the initial incision is carried down only through the subcuticular fat. Elevation of this flap is carried out superficial to the superficial temporal fascia, deep to the subdermal fat and the hair follicles down to the temporal line. This creates a much shorter segment of the "C" flap that depends on the dermal plexus for its sole vascular supply. At the end of the tumor resection, if the superficial temporal fas-



FIG. 1. The lateral skull base incision is outlined either 8 to 12 cm above the helix with the superficial temporal fascia elevated with the flap, or 5 to 6 cm above the helix, elevating deep to the hair follicles and leaving the superficial temporal fascia down until needed for reconstruction.

cia is needed for reconstruction, a vertical incision is extended as far superiorly as necessary to allow harvest of the fascial flap.

When approaching small temporal bone lesions, the cervical extension of the incision can be stopped before section of the great auricular nerve. The sensory nerve is then preserved by elevating it up onto the skin flap, allowing dissection of the internal jugular vein, carotid artery, and lower cranial nerves deep to this flap. As more exposure of the cervical structures is needed, the great auricular nerve is carefully sectioned and reanastomosed at the end of the procedure.

Elevation over the mastoid region is carried out more superficially in a subcutaneous plane to create a strong, thick sternocleidomastoid muscle fascial flap. This is in contradiction to the mastoid fascial flap recommended by others. They recommend elevating the mastoid periosteum up with the skin flap to use as a covering over the transected ear canal. Harvesting this tissue as recommended destroys a valuable layer in closure, leaving a fascial defect over the mastoid region. With a careful imbricating closure of the ear canal, this small fascial flap is not necessary.

After the skin flap has been elevated up to the ear canal, or through the canal as planned, the sternocleidomastoid muscle fascial flap is created by cutting along the temporal line up to the ear canal, then down the anterior surface of the mastoid (Fig. 2). This sturdy flap is elevated off the mastoid, digastric, and occipital regions to expose widely the skull base.

The insertion of the splenius muscle is included in this elevation. Care is taken when dissecting along the anterior temporal line superior to the ear canal to avoid injury to the distal branches of the superficial temporal artery, which supplies both temporalis fascial flaps. At the time of closure, the sternocleidomastoid muscle fascial flap is reapproximated to the deep temporal fascia and the posterior edge of the parotid gland to provide a strong buttress containing the fat implant under pressure, thus decreasing the incidence of CSF leaks (Fig. 3).

To decrease the incidence of facial nerve paralysis, the extratemporal exposure of the nerve is limited. The facial nerve is dissected out to the pes-anserinus without removal of the superficial lobe of the parotid. This further decreases cosmetic and functional tissue loss in the preauricular region.

While dissecting through the parapharyngeal space, care is taken to prevent division of the external carotid artery. This preserves the blood supply to both of the temporal fascial flaps as well as the temporalis muscle.

With anterior extension of these tumors, removal of the temporomandibular joint (TMJ) is often necessary for exposure. Amputation of the condyle can result in significant functional loss. Rather than excise the TMJ, the authors' preference is to mobilize this region, then reconstruct it at the end of the procedure. The TMJ, including the condyle, disc, and joint space, is elevated out of the glenoid fossa in a subperiosteal dissection. The mandible is then displaced downward by dividing the sphenomandibular and stylomandibu-



FIG. 2. A: The sternocleidomastoid muscle fascial flap is outlined by incising on the temporal line up to the posterior aspect of the ear canal and then down along the anterior surface of the mastoid. B: The flap is then elevated up off the mastoid tip and the digastric and occipital regions to expose the entire inferolateral skull base.



FIG. 3. The sternocleidomastoid muscle fascial flap is closed over the free fat graft to the deep temporal fascia, the temporails muscle, the posterior edge of the parotid, and the lower cervical fascia. This forms a very tight closure and firmly holds the fat in place with pressure against the dural defect. When the ear canal has been preserved, the flap is sutured to the ear canal at the bony-cartilaginous junction *(inset).*

lar ligaments. If necessary, the parotid gland is elevated up off the lateral surface of the masseter, which allows for more inferior displacement of the mandibular complex. The articulating surface of the glenoid fossa is then preserved by drilling down into the eustachian tube from the floor of the middle fossa. This cut then extends further forward around the attachment of the base of the zygomatic arch. After the anterior arch is divided away from the lateral orbital rim, the entire glenoid fossa, still connected to the zygomatic arch, can then be mobilized, pedicled on the masseter muscle.

After the resection is complete, the glenoid-zygomatic arch complex is secured back into position with miniplate fixation (Fig. 4). The TMJ is allowed to slide back into its anatomic position. Active range of motion is strongly encouraged in the postoperative period, which presents a decrease in TMJ excursion.

RECONSTRUCTION

After tumor excision is complete, to outline the best reconstructive plan the defect is analyzed for (a) size of dural defect, (b) degree of tissue loss, (c) functional loss, (d) vascular exposure, and (e) sinopharyngeal exposure. These parameters help to dictate the reconstruction. As stated previously, a graduated protocol from simple to complex is followed in tissue transfers, as dictated by the defect. Each of these tissues and procedures is described, and the relative advantages and disadvantages are discussed.

Lateral and Central Skull Base

Fat-Dermal and Fat Grafts

Abdominal fat is the most commonly used bulk replacement in lateral skull base surgery. This transfer is successful because most of these resections result in a sterile defect with excellent cutaneous cover. The fat is easily harvested and maintains approximately 50% of its size with time. Its initial benefit, as well as adding bulk to the residual defect, is to



FIG. 4. A: The entire glenoid fossa is mobilized with the zygomatic arch still pedicled on the masseter by drilling medial to the joint on the middle fossa floor. B: After completion of the resection, the glenoid fossa is secured back into its anatomic position with miniplate fixation, allowing the temporomandibular joint to slide back into its normal position.

provide pressure at the site of dural reconstruction, decreasing the incidence of CSF leak. It is often harvested through a horizontal incision in the left lower quadrant to prevent postoperative confusion with other abdominal operations. However, the authors allow patients to help dictate the site of this incision so that it can be hidden under their clothing. To harvest fat in young women, a suprapubic incision is used to prevent unnecessary abdominal scarring. The authors' preference is to incise deep to Scarpa' s fascia to remove the fat. This helps to prevent dimpling of the abdomen at the site of resection. If redundant abdominal tissue exists, the fat can be removed with its overlying skin, which is deepithelialized to produce a dermal-fat graft. The only significant disadvantage of fat is that it may act as a nidus for infection. Nonvascularized fat transfer does not increase the incidence of wound infection, but once a postoperative infection does occur, the fat must be removed and an alternate form of reconstruction performed.

Nonvascularized fat should not be used in any area that is contaminated by a pharyngeal opening. Previous radiation therapy to a region is a relative contraindication to the use of nonvascularized fat transfer.

Temporal Fascia

Depending on the size of the dural defect, either a free fascial graft or a pedicled vascularized rotation flap of temporal fascia can be used for closure. Small defects of less than 6 mm are covered with free fascia or plugged with fat. For larger defects, a rotation flap of vascularized superficial or deep temporal fascia is used. A brief review of this anatomy, as outlined by Abul-Hassan et al., aids in the use of these flaps (2).

As the superficial temporal artery passes through the parotid gland, it gives off two branches. The transverse facial artery, the more proximal of the two, arises just inferior to the zygomatic arch and runs forward parallel to the arch (Fig. 5). Approximately 1 cm distal to the transverse facial artery, the middle temporal artery takes its origin from the superficial temporal artery and passes into the deep temporal fascia, just above the zygomatic arch. The superficial temporal artery then passes into the superficial temporal fascia and divides into an anterior and posterior branch. The superficial temporal fascia is a part of the subcutaneous muscu-loaponeurotic system and thus is contiguous with the other structures that are a part of this system (Fig. 6), the galea above the frontalis muscle anteriorly, occipitalis muscle posteriorly, and the submuscular aponeurotic system layer of the face.



FIG. 5. The extensive potential size of the superficial temporal fascia supplied by the superficial temporal artery can be seen overlying the smaller deep temporal fascia supplied by the middle temporal artery.

The nomenclature of this fascia is diverse. It is often referred to as the temporoparietal fascia, epicranial aponeurosis, and galea, as well as the superficial temporal fascia. This layer of fascia lies just deep to the hair follicles and the subdermal layer of fat. The superficial temporal artery runs within the layers of this fascia, whereas the veins lie on the lateral surface of the fascia. There are no communications between the superficial temporal artery system and the middle temporal artery lying in the deep temporal fascia. Approximately two thirds of the way from the top of the ear canal to the superior midline, the distal superficial temporal artery system perforates through the fascia up into the subdermal plexus of the scalp. To harvest this flap, these small branches must be divided. To prevent injury to the flap, a bipolar cautery is used to divide these branches. The flap can be harvested reliably almost to the midline. The flap, with approximately 10 cm of length, can cover all dural defects of the jugulomastoid region.

The rationale behind the scalp incision the authors use in lateral skull base surgery was outlined previously. The integrity of the superficial temporal fascia must be considered with any incision on the lateral skull base or the temporal bone region. For preservation of the flap during lateral skull base surgery, an incision is outlined 5 cm above the auricle. This incision is carried down into the postauricular region and into the cervical region as needed. The initial incision is carried down only through the subcuticular fat. Elevation of this flap is carried out superficial to the superficial temporal fascia, deep to the subdermal fat and the hair follicles down to the temporal line. As noted previously, this creates a much shorter segment of the "C" flap that depends on the dermal plexus for its sole vascular supply. At the end of the tumor resection, if the superficial temporal fascia is needed

FIG. 6. The layers of the temporal region are illustrated. The superficial temporal fascia is seen just deep to the subcutaneous fat and hair follicles.


Superficial temporal fascia
Deep temporal fascia
Temporalis m.
Superficial temporal a.
Temporal branch
of facial n.
Parotid gland



FIG. 7. A: With a short "C" incision 5 to 6 cm above the helix, the superficial temporal fascia is initially left down, and the scalp is elevated superficial to this fascia. B: At the end of the resection to harvest the flap, a vertical incision just through the subcutaneous tissue is created to allow exposure of a flap 10 to 12 cm in length.

for reconstruction, a vertical incision is extended as far superiorly as necessary to allow harvest of the fascial flap (Fig. 7).

For use of the flap in anterior skull base repair, when no bicoronal incision has been performed, a separate vertical incision is created starting at the preauricular level of the zygomatic arch and extending superiorly until the necessary length of flap is acquired. During a standard bicoronal flap for the approach to the anterior skull base, the surgeon can save the posterior three fourths of the flap by limiting the depth of the incision over the temporal region down to the superficial temporal fascia. The elevation of the forehead flap is followed forward until the posterior vertical branch of the superficial temporal artery is cleared. The anterior branch, passing forward toward the forehead, is identified and divided as the incision is carried deeper to the level of the deep temporal fascia. The elevation of the bicoronal flap proceeds in a normal fashion after the ascending branch of the superficial temporal artery is preserved. To gain optimum exposure of the zygomaticoorbital region, the deep temporal fascia is divided in a line parallel but 2 cm superior to the frontal branch of the facial nerve. Elevation progresses deep to this fascia toward the orbit. The attachments of the fascia are removed from the lateral orbital rim and the zygo-matic arch. If the temporal muscle needs to be mobilized away from the rim, care is taken not to injure or remove more muscle than necessary.

After the resection is complete, it is important carefully to fill in the temporal fossa adjacent to the lateral orbital rim by reattaching the temporal muscle and the deep temporal fascia to the rim. This is accomplished with sutures placed through small holes drilled in the rim with a wire-pass bur. Care is taken to draw the fascia up over the lateral rim to realign the normal contours of the rim-temporal fossa junction. Tf this unit is not realigned anatomically, the anterior temporal fossa will sink in with marked overprominence of the lateral orbital rim. This results in a very emaciated appearance that demands secondary reconstruction.

After the access incisions have been completed, preventing injury to the vascular arcade of the flap, the plane of elevation is just deep to the dermal fat and the hair follicles; care must be taken to prevent injury to the superficial temporal veins. This tedious dissection must be performed slowly to prevent injury to the flap or the hair follicles. The anterior one fourth of this fascia is usually left intact by dividing the anterior branch of the superficial temporal artery, which protects the temporal branch of the facial nerve. During the elevation of the scalp off the fascia, the surgeon will find very few vascular connections up into the fat during dissection of the lower 4 to 5 cm above the auricle. As the dissection proceeds superiorly, the vessels send numerous perforators into the subcuticular tissue. These branches are too small for individual ligation. If the flap is elevated with loupe magnification, these branches can be cauterized with bipolar cautery without injury to the fascial blood supply.

The scalp can be elevated as superior as necessary to acquire as large a flap as needed. Flap lengths from 9 to 12 cm reconstruct most defects from the temporal fossa to the orbit and cavernous sinus region. After completion of the dermal elevation, the superior extension of the superficial temporal artery is divided as the incision down through the superficial fascia progresses to the pericranium. This superior fascial division usually progresses superior to the deep temporal fascia overlying the temporalis muscle. The deep fascia extends only 6 to 8 cm above the zygomatic arch, producing a much shorter fascia flap. The perimeter of the superficial flap is outlined and divided down to a narrow 1.5-cm pedicle over the zygomatic arch. Elevation of the flap occurs right on the pericranium and the deep temporal fascia to acquire as thick a superficial flap as possible. If more length is needed, the surgeon can divide the middle temporal branch off the superficial artery at the level of the zygomatic arch, dissecting the vessels down to the point where they pass deep to the upper division of the facial nerve. This is rarely necessary.

Reconstruction of temporal bone defects is the most common use of this flap in the authors' hands. It is large enough to wrap easily around an intact ear canal, sealing the middle ear space, and still cover a dural defect in the region of the pars nervosa of the jugular foramen (Fig. 8). This allows for the future potential of an aerated middle ear space. Less abdominal fat is needed because of the bulk of the flap in the defect.



FIG. 8. The flap is isolated down to a 1 -cm-wide pedicle surrounding the superficial temporal artery and vein. The length of this flap easily wraps around an intact ear canal and the open middle ear space, isolating it from, as well as covering, the dural defect.

Dural defects in the anterior skull base along the roof of the orbit, cribriform region, cavernous sinus, upper clivus, and sphenoid sinus are common areas for use of this flap. It does not supply much bulk, but it provides a reliable source of vascularized tissue to separate the intradural contents from the sinuses.

Transfer of the flap can be accompanied by several complications. The most common is hair loss along the incisions. This is common for a 5-mm region on either side of the incisions. Over time, this area narrows to the point that most normal hairstyles in men and women completely cover the loss. Scalp loss can occur along the edge of the incisions. As noted previously, the authors have modified their incisions to decrease the length of the scalp flap that must be supplied by the dermal plexus. When this loss occurs, it is most commonly limited to less than 1.5 cm of the lower flap, which heals by secondary intention with minimal long-term sequelae. Rarely, a larger portion of the scalp can undergo necrosis, resulting in the need for delayed reconstruction. Previous radiation therapy or excessive smoking are relative, not absolute, contraindications to using this flap.

One final sequela occurs commonly with this flap when used in the temporal bone region. Ptosis of the ear can develop because of the loss of superior support. This is usually minor, but on several occasions patients have complained of the obvious difference in height of their ears. The authors have had to correct this in only one person.

The deep temporal fascia overlying the temporalis muscle attaches to the zygomatic arch and coronoid process of the mandible below and terminates distally at the superior edge of the temporalis muscle. This is the fascia traditionally used in otologic surgery for free fascial grafts. Because of its smaller size, it does not dependably reach the jugular foramen region, if the ear canal is intact. When the ear canal has been removed, it readily covers the entire temporal defect. These two flaps can be used singly or in combination as the defect dictates.

Temporalis Muscle

The temporalis muscle derives its main blood supply from the deep temporal arteries that, after branching off the internal maxillary artery, extend into the muscle on its deep surface along the base of the sphenoid wing. This muscle is very useful for rotation into the middle fossa floor, the nasopharynx, and infratemporal fossa regions. On rotation, it can protect an exposed carotid from the nasopharynx and seal moderate-sized dural defects. Although it has been recommended for temporal bone reconstruction, the authors have not found it very useful in this region. With an intact ear canal, the muscle length is not adequate to reach down into a defect of the jugular foramen region. Even when the canal is divided, posterior rotation of the muscle over the zygomatic arch and TMJ is difficult. If adequate rotation is accomplished, the muscle bulk is not sufficient to fill the mastoid defect and avoid free fat grafts. It does not appear to offer any advantage over superficial temporal fascia rotation with free fat grafting, which prevents the cosmetic defect of temporalis muscle rotation.

During mobilization of the muscle from the temporal fossa, care is taken to elevate the two branches of the deep temporal artery out of the deep recesses that they lie in on the undersurface of the sphenoid bone. It is often necessary to divide the muscular attachments on the coronoid process or divide the coronoid, leaving the tip attached to the mobilized muscle to rotate the muscle into the sphenoclival region. It is difficult to transfer the muscle without injury to its nerve supply arising from the third division of the trigeminal nerve. Often in lateral-infratemporal skull base surgery, the entire contents of the foramen ovale have been sacrificed during the approach or the resection. Thus, in most cases the transferred muscle atrophies over 6 to 12 months. The temporalis muscle flap is useful for sealing skull base defects, but because of this atrophy it is not as useful for filling defects where volume is needed.

One disadvantage with the use of this muscle is the defect in the temporal fossa after this muscle is transferred. If the resection does not involve entry into the sinuses or the pharynx, the defect can be reconstructed by an implant of either dermal-fat, methylmethacrylate, or silicone rubber carved to fill the temporal fossa. Care must be taken to ensure close approximation of the implant to the lateral orbital rim to prevent a very noticeable "step-off in this region. It would be risky to place either one of these implants into a potentially contaminated field. Nonvascularized fat can be used to reconstruct the temporal defect, but it atrophies over 6 to 12 months.

Fibrin Glue

Suture fixation of a dural graft in the jugular foramen region is difficult, and thus a waterproof glue to secure these grafts would be helpful. In the United States, there is no Food and Drug Administration-approved concentrated fibrin glue available for use, such as Tisseal, which is used in Europe and Canada. Tisseal, which is manufactured from pooled serum, carries a theoretic risk of disease transmission. The technology to produce concentrated fibrin glue from autogenous serum is on the horizon but not yet universally available. Often, a weaker form of fibrin glue is used to help seal the fascia and fat in place before closure. The glue is produced by reconstituting a 1-g bottle of thrombin powder with 10 ml of saline. This is alternately instilled into the wound with 10 ml of concentrated cryoprecipitate to form a gelatinous glue, which aids in sealing the grafts in place. Just how much this aids the security of the closure is not known. A safe, concentrated fibrin glue would be an excellent addition to dural closure.

Myocutaneous Flaps

The introduction of myocutaneous flaps for reconstruction of head and neck defects significantly decreased the morbidity and mortality of oropharyngeal oncologic surgery. Although they were initially used extensively in reconstructive surgery of the skull base, time has shown the free tissue transfers to be better suited in most defects. The use of free tissue transfer for skull base reconstruction is outlined in Chapter 31.

Of the myocutaneous flaps, the three that have an arc of rotation long enough to be useful in skull base reconstruction are the pectoralis, lower trapezius, and the latissimus dorsi flaps. Each of these flaps has its usefulness in defects of the lateral skull base. Defects of the central skull base-clival region, which are difficult to reconstruct with pedicled flaps, are most often reconstructed with free tissue vascularized flaps.

Pectoralis Myocutaneous Flap

Although the pectoralis major myocutaneous flap is the workhorse of oropharyngeal reconstruction, there are several shortcomings to its use in lateral skull base reconstruction. Extension of this flap superior to the level of the ear canal is difficult. With this extension, the inferior tension on the flap pulls it in an inferior direction over time, leaving inadequate bulk in the superior aspect of the reconstruction. The main use of the flap is in parotid malignancy that has invaded the lower temporal bone region. The defect from this tumor usually spares the auricle with sacrifice of the mastoid region. Because of the common use of this flap in head and neck reconstruction, the techniques used in harvesting this flap are not outlined. The harvest of this flap is very familiar to most head and neck surgeons.

Lower Trapezius Flap

The lower trapezius myocutaneous flap is much better suited to reconstruct lateral skull base defects than the pectoralis (3,4). With the inclusion of the blood supply from the dorsal scapular artery in the flap, the skin paddle may be positioned low enough on the muscle, inferomedial to the scapula, to prevent loss of trapezius function with its use. A thorough understanding of the vascular anatomy of this region is essential to the successful use of this flap. This anatomy is well outlined in the authors' previous publication on the use of this flap (5).

Based on this anatomy, a surgical technique is outlined for isolating and using the dorsal scapular artery during harvest of the lower trapezius flap. The patient is positioned on a bean bag in the lateral decubitus position, then prepared and draped so that the back is visible down to the iliac crest and past the midline, as identified by the spinous processes (Fig. 9). After draping, the bean bag is deflated to allow the patient to rest in a 45-degree position for the resection. The patient is then easily repositioned without repreparation of the sterile field, if the flap is needed. The ipsilateral arm is kept free of arterial or venous access lines and is draped sterilely into the field. This allows for its mobility during the procedure. After the arm is placed in an anteriorly rotated position, the flap is outlined over the lower medial trapezius fibers. The medial edge of the flap is placed as close to the midline as possible, which allows a greater distal extension of the flap still overlying the inferior aspect of the trapezius muscle. The flap is purposely outlined too long and later tailored to fit the size of the surgical defect. This increase in paddle length allows for more cosmetic closure of the back incision with less dog-ear formation at each end, as well as allowing for the inclusion of more potential perforators into the subcutaneous aspect of the flap. The distal aspect of the flap may extend 15 cm below the tip of the scapula, which creates a significant random extension on the inferior lateral aspect of the skin paddle. The outlined skin paddle is incised and elevated over the latissimus dorsi, starting on the inferior lateral border. Following this plane medially, the surgeon can readily identify the lower trapezius fibers. The flap is further elevated deep to the trapezius until the lower border of the



FIG. 9. The patient is positioned in the lateral decubitus position with exposure of the back down to the spinous processes. The skin paddle is laid out close to the midline to overlie the inferior aspect of the trapezius muscle. It can extend 15 cm below the inferior tip of the scapula.

rhomboid major is identified. In most situations, this muscle is left in place, which prevents postoperative winging of the scapula. At this point, the distal arcade of the dorsal scapula artery is usually identified lying in the deep fascia on the un-dersurface of the trapezius muscle. The vessels are followed up until they depart from the muscle at the interface between the rhomboid minor and the rhomboid major muscles, adjacent to the medial portion of the scapular spine. Rarely, when the major branch of the dorsal scapular artery perforates more inferiorly through the body of the rhomboid major, the muscle is divided to free up the vessel.

In most cases, additional pedicle length is needed at this point. The descending branches of the dorsal scapular artery that pass deep to the rhomboid major are ligated with fine vascular clips and divided (Fig. 10). In most of the cases, there are two or three sets of descending vessels that must be divided. After this division, gentle dissection along the dorsal scapular artery allows it to uncoil

FIG. 6. The layers of the temporal region are illustrated. The superficial temporal fascia is seen just deep to the subcutaneous fat and hair follicles.



FIG. 7. A: With a short "C" incision 5 to 6 cm above the helix, the superficial temporal fascia is initially left down, and the scalp is elevated superficial to this fascia. B: At the end of the resection to harvest the flap, a vertical incision just through the subcutaneous tissue is created to allow exposure of a flap 10 to 12 cm in length.

for reconstruction, a vertical incision is extended as far superiorly as necessary to allow harvest of the fascial flap (Fig. 7).

For use of the flap in anterior skull base repair, when no bicoronal incision has been performed, a separate vertical incision is created starting at the preauricular level of the zygomatic arch and extending superiorly until the necessary length of flap is acquired. During a standard bicoronal flap for the approach to the anterior skull base, the surgeon can save the posterior three fourths of the flap by limiting the depth of the incision over the temporal region down to the superficial temporal fascia. The elevation of the forehead flap is followed forward until the posterior vertical branch of the superficial temporal artery is cleared. The anterior branch, passing forward toward the forehead, is identified and divided as the incision is carried deeper to the level of the deep temporal fascia. The elevation of the bicoronal flap proceeds in a normal fashion after the ascending branch of the superficial temporal artery is preserved. To gain optimum exposure of the zygomaticoorbital region, the deep temporal fascia is divided in a line parallel but 2 cm superior to the frontal branch of the facial nerve. Elevation progresses deep to this fascia toward the orbit. The attachments of the fascia are removed from the lateral orbital rim and the zygo-matic arch. If the temporal muscle needs to be mobilized away from the rim, care is taken not to injure or remove more muscle than necessary.

After the resection is complete, it is important carefully to fill in the temporal fossa adjacent to the lateral orbital rim by reattaching the temporal muscle and the deep temporal fascia to the rim. This is accomplished with sutures placed through small holes drilled in the rim with a wire-pass bur. Care is taken to draw the fascia up over the lateral rim to realign the normal contours of the rim-temporal fossa junction. Tf this unit is not realigned anatomically, the anterior temporal fossa will sink in with marked overprominence of the lateral orbital rim. This results in a very emaciated appearance that demands secondary reconstruction.

After the access incisions have been completed, preventing injury to the vascular arcade of the flap, the plane of elevation is just deep to the dermal fat and the hair follicles; care must be taken to prevent injury to the superficial temporal veins. This tedious dissection must be performed slowly to prevent injury to the flap or the hair follicles. The anterior one fourth of this fascia is usually left intact by dividing the anterior branch of the superficial temporal artery, which protects the temporal branch of the facial nerve. During the elevation of the scalp off the fascia, the surgeon will find very few vascular connections up into the fat during dissection of the lower 4 to 5 cm above the auricle. As the dissection proceeds superiorly, the vessels send numerous perforators into the subcuticular tissue. These branches are too small for individual ligation. If the flap is elevated with loupe magnification, these branches can be cauterized with bipolar cautery without injury to the fascial blood supply.

The scalp can be elevated as superior as necessary to acquire as large a flap as needed. Flap lengths from 9 to 12 cm reconstruct most defects from the temporal fossa to the orbit and cavernous sinus region. After completion of the dermal elevation, the superior extension of the superficial temporal artery is divided as the incision down through the superficial fascia progresses to the pericranium. This superior fascial division usually progresses superior to the deep temporal fascia overlying the temporalis muscle. The deep fascia extends only 6 to 8 cm above the zygomatic arch, producing a much shorter fascia flap. The perimeter of the superficial flap is outlined and divided down to a narrow 1.5-cm pedicle over the zygomatic arch. Elevation of the flap occurs right on the pericranium and the deep temporal fascia to acquire as thick a superficial flap as possible. If more length is needed, the surgeon can divide the middle temporal branch off the superficial artery at the level of the zygomatic arch, dissecting the vessels down to the point where they pass deep to the upper division of the facial nerve. This is rarely necessary.

Reconstruction of temporal bone defects is the most common use of this flap in the authors' hands. It is large enough to wrap easily around an intact ear canal, sealing the middle ear space, and still cover a dural defect in the region of the pars nervosa of the jugular foramen (Fig. 8). This allows for the future potential of an aerated middle ear space. Less abdominal fat is needed because of the bulk of the flap in the defect.



FIG. 8. The flap is isolated down to a 1 -cm-wide pedicle surrounding the superficial temporal artery and vein. The length of this flap easily wraps around an intact ear canal and the open middle ear space, isolating it from, as well as covering, the dural defect.

Dural defects in the anterior skull base along the roof of the orbit, cribriform region, cavernous sinus, upper clivus, and sphenoid sinus are common areas for use of this flap. It does not supply much bulk, but it provides a reliable source of vascularized tissue to separate the intradural contents from the sinuses.

Transfer of the flap can be accompanied by several complications. The most common is hair loss along the incisions. This is common for a 5-mm region on either side of the incisions. Over time, this area narrows to the point that most normal hairstyles in men and women completely cover the loss. Scalp loss can occur along the edge of the incisions. As noted previously, the authors have modified their incisions to decrease the length of the scalp flap that must be supplied by the dermal plexus. When this loss occurs, it is most commonly limited to less than 1.5 cm of the lower flap, which heals by secondary intention with minimal long-term sequelae. Rarely, a larger portion of the scalp can undergo necrosis, resulting in the need for delayed reconstruction. Previous radiation therapy or excessive smoking are relative, not absolute, contraindications to using this flap.

One final sequela occurs commonly with this flap when used in the temporal bone region. Ptosis of the ear can develop because of the loss of superior support. This is usually minor, but on several occasions patients have complained of the obvious difference in height of their ears. The authors have had to correct this in only one person.

The deep temporal fascia overlying the temporalis muscle attaches to the zygomatic arch and coronoid process of the mandible below and terminates distally at the superior edge of the temporalis muscle. This is the fascia traditionally used in otologic surgery for free fascial grafts. Because of its smaller size, it does not dependably reach the jugular foramen region, if the ear canal is intact. When the ear canal has been removed, it readily covers the entire temporal defect. These two flaps can be used singly or in combination as the defect dictates.

Temporalis Muscle

The temporalis muscle derives its main blood supply from the deep temporal arteries that, after branching off the internal maxillary artery, extend into the muscle on its deep surface along the base of the sphenoid wing. This muscle is very useful for rotation into the middle fossa floor, the nasopharynx, and infratemporal fossa regions. On rotation, it can protect an exposed carotid from the nasopharynx and seal moderate-sized dural defects. Although it has been recommended for temporal bone reconstruction, the authors have not found it very useful in this region. With an intact ear canal, the muscle length is not adequate to reach down into a defect of the jugular foramen region. Even when the canal is divided, posterior rotation of the muscle over the zygomatic arch and TMJ is difficult. If adequate rotation is accomplished, the muscle bulk is not sufficient to fill the mastoid defect and avoid free fat grafts. It does not appear to offer any advantage over superficial temporal fascia rotation with free fat grafting, which prevents the cosmetic defect of temporalis muscle rotation.

During mobilization of the muscle from the temporal fossa, care is taken to elevate the two branches of the deep temporal artery out of the deep recesses that they lie in on the undersurface of the sphenoid bone. It is often necessary to divide the muscular attachments on the coronoid process or divide the coronoid, leaving the tip attached to the mobilized muscle to rotate the muscle into the sphenoclival region. It is difficult to transfer the muscle without injury to its nerve supply arising from the third division of the trigeminal nerve. Often in lateral-infratemporal skull base surgery, the entire contents of the foramen ovale have been sacrificed during the approach or the resection. Thus, in most cases the transferred muscle atrophies over 6 to 12 months. The temporalis muscle flap is useful for sealing skull base defects, but because of this atrophy it is not as useful for filling defects where volume is needed.

One disadvantage with the use of this muscle is the defect in the temporal fossa after this muscle is transferred. If the resection does not involve entry into the sinuses or the pharynx, the defect can be reconstructed by an implant of either dermal-fat, methylmethacrylate, or silicone rubber carved to fill the temporal fossa. Care must be taken to ensure close approximation of the implant to the lateral orbital rim to prevent a very noticeable "step-off in this region. It would be risky to place either one of these implants into a potentially contaminated field. Nonvascularized fat can be used to reconstruct the temporal defect, but it atrophies over 6 to 12 months.

Fibrin Glue

Suture fixation of a dural graft in the jugular foramen region is difficult, and thus a waterproof glue to secure these grafts would be helpful. In the United States, there is no Food and Drug Administration-approved concentrated fibrin glue available for use, such as Tisseal, which is used in Europe and Canada. Tisseal, which is manufactured from pooled serum, carries a theoretic risk of disease transmission. The technology to produce concentrated fibrin glue from autogenous serum is on the horizon but not yet universally available. Often, a weaker form of fibrin glue is used to help seal the fascia and fat in place before closure. The glue is produced by reconstituting a 1-g bottle of thrombin powder with 10 ml of saline. This is alternately instilled into the wound with 10 ml of concentrated cryoprecipitate to form a gelatinous glue, which aids in sealing the grafts in place. Just how much this aids the security of the closure is not known. A safe, concentrated fibrin glue would be an excellent addition to dural closure.

Myocutaneous Flaps

The introduction of myocutaneous flaps for reconstruction of head and neck defects significantly decreased the morbidity and mortality of oropharyngeal oncologic surgery. Although they were initially used extensively in reconstructive surgery of the skull base, time has shown the free tissue transfers to be better suited in most defects. The use of free tissue transfer for skull base reconstruction is outlined in Chapter 31.

Of the myocutaneous flaps, the three that have an arc of rotation long enough to be useful in skull base reconstruction are the pectoralis, lower trapezius, and the latissimus dorsi flaps. Each of these flaps has its usefulness in defects of the lateral skull base. Defects of the central skull base-clival region, which are difficult to reconstruct with pedicled flaps, are most often reconstructed with free tissue vascularized flaps.

Pectoralis Myocutaneous Flap

Although the pectoralis major myocutaneous flap is the workhorse of oropharyngeal reconstruction, there are several shortcomings to its use in lateral skull base reconstruction. Extension of this flap superior to the level of the ear canal is difficult. With this extension, the inferior tension on the flap pulls it in an inferior direction over time, leaving inadequate bulk in the superior aspect of the reconstruction. The main use of the flap is in parotid malignancy that has invaded the lower temporal bone region. The defect from this tumor usually spares the auricle with sacrifice of the mastoid region. Because of the common use of this flap in head and neck reconstruction, the techniques used in harvesting this flap are not outlined. The harvest of this flap is very familiar to most head and neck surgeons.

Lower Trapezius Flap

The lower trapezius myocutaneous flap is much better suited to reconstruct lateral skull base defects than the pectoralis (3,4). With the inclusion of the blood supply from the dorsal scapular artery in the flap, the skin paddle may be positioned low enough on the muscle, inferomedial to the scapula, to prevent loss of trapezius function with its use. A thorough understanding of the vascular anatomy of this region is essential to the successful use of this flap. This anatomy is well outlined in the authors' previous publication on the use of this flap (5).

Based on this anatomy, a surgical technique is outlined for isolating and using the dorsal scapular artery during harvest of the lower trapezius flap. The patient is positioned on a bean bag in the lateral decubitus position, then prepared and draped so that the back is visible down to the iliac crest and past the midline, as identified by the spinous processes (Fig. 9). After draping, the bean bag is deflated to allow the patient to rest in a 45-degree position for the resection. The patient is then easily repositioned without repreparation of the sterile field, if the flap is needed. The ipsilateral arm is kept free of arterial or venous access lines and is draped sterilely into the field. This allows for its mobility during the procedure. After the arm is placed in an anteriorly rotated position, the flap is outlined over the lower medial trapezius fibers. The medial edge of the flap is placed as close to the midline as possible, which allows a greater distal extension of the flap still overlying the inferior aspect of the trapezius muscle. The flap is purposely outlined too long and later tailored to fit the size of the surgical defect. This increase in paddle length allows for more cosmetic closure of the back incision with less dog-ear formation at each end, as well as allowing for the inclusion of more potential perforators into the subcutaneous aspect of the flap. The distal aspect of the flap may extend 15 cm below the tip of the scapula, which creates a significant random extension on the inferior lateral aspect of the skin paddle. The outlined skin paddle is incised and elevated over the latissimus dorsi, starting on the inferior lateral border. Following this plane medially, the surgeon can readily identify the lower trapezius fibers. The flap is further elevated deep to the trapezius until the lower border of the



FIG. 9. The patient is positioned in the lateral decubitus position with exposure of the back down to the spinous processes. The skin paddle is laid out close to the midline to overlie the inferior aspect of the trapezius muscle. It can extend 15 cm below the inferior tip of the scapula.

rhomboid major is identified. In most situations, this muscle is left in place, which prevents postoperative winging of the scapula. At this point, the distal arcade of the dorsal scapula artery is usually identified lying in the deep fascia on the undersurface of the trapezius muscle. The vessels are followed up until they depart from the muscle at the interface between the rhomboid minor and the rhomboid major muscles, adjacent to the medial portion of the scapular spine. Rarely, when the major branch of the dorsal scapular artery perforates more inferiorly through the body of the rhomboid major, the muscle is divided to free up the vessel.

In most cases, additional pedicle length is needed at this point. The descending branches of the dorsal scapular artery that pass deep to the rhomboid major are ligated with fine vascular clips and divided (Fig. 10). In most of the cases, there are two or three sets of descending vessels that must be divided. After this division, gentle dissection along the dorsal scapular artery allows it to uncoil from its serpentine path under the scapula. This allows for an additional 2 to 3 cm of pedicle length. If further rotation is needed, the rhomboid minor is divided on either side of the vascular pedicle, which allows for several more centimeters of rotation with no venous tension. The upper trapezius fibers are divided superiorly just enough to rotate the distal portion of the skin paddle into the defect, protecting the superior portion of the muscle. This allows for normal postoperative shoulder elevation. The flap can then be passed through a subcutaneous tunnel over the remaining superior trapezius fibers into a na-sopharyngeal defect, or rotated onto a temporal cutaneous defect. With the flap in position, the skin paddle is outlined and tailored to fit the defect (Fig. 11). If the proximal portion of the cutaneous paddle is too long, then the necessary amount of skin is deepithelialized, leaving the subcutaneous tissues on the muscle, thus allowing for a greater subcuta-


Rhomboid Major
Descending Branch of Dorsal Scapular A.&V.
Rhomboid Minor
Dorsal Scapular A.&V.
Transverse Cervical A.
Latissimus Dorsi
A
Transverse Cervical A
Cut Edges of *Rhomboid Minor*
Levator Scapula
Dorsal Scapular A.&V.
Descending Branch of Dorsal Scapular A.&V.
Rhomboid Major
B

FIG. 10. A: The descending branches of the dorsal scapular artery often need to be divided to gain adequate length of the flap. B: If further length is needed, the rhomboid minor is divided and mobilized up with the pedicle.



FIG. 11. A: The mobilized flap can easily cover most temporal defects. The distal and proximal aspects of the oversized skin paddle are deepithelialized to adjust the flap to the defect. B: The flap is inset with primary closure of the donor site on the back.

neous muscle interface, which ensures more perforators into the cutaneous tissue. The distal end of the flap can either be divided or deepithelialized using the distal subcutaneous tissue for bulk. The back is closed primarily, and after surgery the patient is positioned on a pillow that contacts the back inferior to the scapular spine, with a second pillow under the head. This prevents pressures on the vessels as they rotate over the superior trapezius fibers.

The flap is excellent for cutaneous reconstruction in the temporal region when either skin or the entire auricle is resected along with the tumor. When the skin cover is intact, with substantial tissue loss resulting in exposed, unprotected vital structures, complete deepithelialization allows the flap to maintain excellent bulk and be safely buried. The flap has been used in this fashion for patients with persistent CSF leaks, postoperative wound infections, extensive dural loss with exposed cerebral and cerebellar tissue, and reconstruction of poorly vascularized tissue after radiation failure.

In the authors' series, significant flap loss has occurred in 3 of 52 flaps used for head and neck reconstruction. In the first case, a 40% distal flap loss occurred secondary to fat necrosis. The second patient was found the first morning after surgery lying on the pedicle rotation point with a pale dusky flap. A slow, creeping necrosis of the entire skin paddle occurred over the next 7 days. The final flap loss was due to inadequate blood supply after a previous radical neck dissection, in which the dorsal scapular artery was resected.

Latissimus Dorsi Myocutaneous Flap

The latissimus dorsi myocutaneous flap is reserved for extensive defects of the skull base. Free flap reconstruction is often preferred for defects of this magnitude. However, when there are factors that preclude the use of the free flap, the latissimus dorsi flap is an excellent choice. Details of this flap for use in the head and neck are outlined in series by Maves et al. (6), Sabatier and Bakamijian (7), and Chowdhury et al. (8). The potential size of the flap is its greatest advantage. A skin paddle can be elevated large enough to cover the entire hemicranium if needed. The harvest of the flap is fairly simple, with a large, easy-to-follow vascular pedicle. The major disadvantage of this flap is the long tunnel through which the pedicle must pass on its way to the head and neck defect. In the early postoperative period, the position of the arm is critical to prevent occlusion of the vein as it passes through the region of the pectoralis major and minor. Because of the pedicle and the weight of the flap, it has a tendency to "sag" over time, with a thinning-out of the superior area of the reconstruction. Because of the less frequent use of this flap, a brief account of the flap harvest is included.

The patient is positioned in the lateral decubitus position using a bean bag for support. The contralateral axilla is carefully padded with a wrapped bag of intravenous fluids, with the contralateral arm supported on an arm rest. No intravenous or intraarterial access is allowed in the ipsilateral arm so that it can be prepared into the field. This allows for ease of intraoperative positioning of the arm during flap dissection and closure of the donor defect. During resection of the head and neck primary, the bean bag may be deflated, allowing the patient to settle into the 45-degree position. After the completion of the resection, the patient is shifted back into the lateral decubitus position and the bag is refilled with air.

The latissimus muscle has a dual blood supply, with the dominant vascular source formed by the thoracodorsal artery and veins. The secondary blood supply is from the posterior paraspinous perforators. Both of these systems are diffusely interconnected. The myocutaneous flap for use in the head and neck is based on the thoracodorsal pedicle, necessitating sacrifice of the paraspinous perforators.

The subscapular artery, which is a branch off the third portion of the axillary artery, gives rise to the thoracodorsal artery, which enters the latissimus muscle on its anterior lateral margin and yields a vascular pedicle 10 to 12 cm in length. The first branch of the subscapular is the circumflex scapular artery, which rarely restricts the rotation of the flap and thus is not usually sacrificed during flap rotation. Several centimeters distal to its takeoff, the branch to the teres major is seen passing laterally. This vessel is usually sacrificed during flap harvest. Distal to this, one or two branches to the serratus anterior are encountered just before the entry of the thoracodorsal artery into the latissimus muscle. These vessels are divided unless the serratus muscle is harvested with the flap for unusually large defects.

The thoracodorsal artery divides into two major intramuscular divisions. The superior branch travels parallel to the upper border of the muscle about 3 cm inferior to the upper edge. The lateral branch travels parallel to the lateral margin of the muscle approximately 2 to 3 cm back from the lateral edge. This intramuscular division allows for a bipedicled flap to be developed as necessary.



FIG. 12. The latissimus flap is outlined over the anterior border of the muscle, extending down too long to allow for later contouring into the defect. An extensive flap can be harvested with primary closure of the donor site.

After the conclusion of the resection, the anterior border of the latissimus muscle is palpated and outlined on the skin. The cutaneous paddle is outlined over the lateral inferior aspect of the muscle to allow for the added length needed to reach the head and neck defect (Fig. 12). The skin paddle is created too large to allow for later tailoring into the defect. An initial incision that is created along the anterior lateral border of the flap is extended up to but not into the axillary region. The anterior border of the muscle is isolated and followed up to the tendinous insertion onto the humerus. With careful dissection into the axillary fat pad, the thoracodorsal vessel is identified along with the associated vein and nerve. The neurovascular pedicle is developed proximally, ligating the vessels supplying the teres major and the serratus. The circumflex scapular vessels are identified but left intact. After flap rotation, they can be divided if further pedicle length is needed.

The skin island is incised down to the muscle and the surrounding skin is elevated to expose the muscle. The latissimus is separated from the serratus from superior to inferior, where the plane between the two muscles becomes less distinct. After the remaining distal attachments of the muscle are separated, the humeral head is divided. The flap, which is now attached only by the neurovascular pedicle, is passed through the axilla through a tunnel created between the heads of the pectoralis major and minor. If more room is needed in the tunnel, the head of the pectoralis minor can be divided. The surgeon can create a path through the pectoralis major for passage of the pedicle by either spreading apart the muscle fibers or dividing some of the central fibers. Care is taken to prevent injury to the thoracoacromial vascular pedicle during this dissection in case future use of the pectoralis flap is needed. The flap then passes over the clavicle into the defect (Fig. 13). After initial inset of the flap into position, the pedicle is examined in the tunnel to see if any compression is isolated. The arm is abducted and adducted to see if the tunnel needs enlargement to prevent vascular compres-





FIG. 13. A,B: The latissimus myocutaneous flap is large enough to cover extensive defects of the lateral skull base. C: Over time, revision of this flap is necessary because of the inferior pull of the pedicle, resulting in "sagging" of the skin paddle.

sion. The thoracodorsal nerve is divided only if atrophy of the muscle is desired, or if it results in venous compression during the rotation of the flap.

The flap is tailored into the defect and the back is closed primarily over several closed-suction drains. If needed, the tendinous humeral portion of the muscle is attached to the chest wall or the pectoralis minor tendon to prevent further pull on the pedicle. Rarely after harvest of an extensive flap, the defect must be resurfaced with a split-thickness skin graft. Because of the constant movement in this area of the chest wall, the results of skin graft healing are often frustrating. After surgery, the ipsilateral arm is positioned in a neutral position, resting on a pillow, for several days, to prevent venous compression.

Anterior Skull Base

With the limitation of this chapter to reconstruction of the skull base with regional and pedicled flaps, this section dedicated to the anterior skull base is very brief. This region includes defects in the frontal bone and the cribriform region. Only the latissimus flap reaches this area, but it is a poor choice for reconstruction of this region. To reach this area well, the pedicle would have to pass externally, with a second stage necessary to take down the pedicle.

Most defects encountered in anterior skull base surgery are in the region of the cribriform plate as a result of craniofacial surgery. With defects limited to the roof of the nasal vault, reconstruction can be accomplished by use of local flaps. However, with loss of large volumes of soft tissue or frontal skull and overlying skin, reconstruction can be accomplished better using free tissue transfer.

Pericranial and Galeal Frontalis Flaps

The anterior scalp provides two different layers for reconstruction of the cribriform region. The major benefit of both these flaps is that they can be easily preserved along with their inferior blood supply during the standard bicoronal approach to lesions of the anterior skull base. The length of the flaps is determined by how high up on the scalp the bicoronal incision is outlined.

The most commonly used of the two is the pericranial flap, consisting of the periosteum of the anterior skull, based on branches of the supraorbital artery. The flap can be separated from the overlying scalp at the beginning of the procedure, or it can be raised up with the bicoronal flap, elevating it off the scalp at the end of the surgical resection of the tumor (Fig. 14). The latter provides better protection of the flap during the resection. During elevation, as the supraorbital region is approached, care is taken to include several of the branches of the supraorbital artery in the flap. With care, the sensory branches of the supraorbital nerve can be preserved passing into the scalp flap. The flap is inserted through the inferior lip of the frontal craniotomy after a few millimeters of the inferior aspect of the bone flap are removed to ensure adequate room for postoperative swelling of the base of the flap. The flap can be secured in place by drilling several 1.5-mm holes in the residual planum sphenoidale, taking care not to injure the optic nerves.

The major drawback to the pericranial flap is its limited blood supply. Often during postoperative examination of the nasal roof, the flap appears to have undergone partial necrosis with eschar formation. In spite of the postoperative appearance of the flap, very few CSF leaks occur. This area seems to be a very forgiving of this poorly vascularized reconstruction.

The galeal-frontalis flap offers a better-vascularized flap with more volume to reconstruct this same region. The frontal galea is the same layer anterior as the superficial temporal layer is over the temporal region. As the temporal region is left behind, the galea divides into two leaves enveloping the frontalis muscle. The major branches of the supraorbital artery and nerve pass into this layer. The flap is raised up with the bicoronal flap and elevated away from the scalp when needed. Because of the increased thickness of this flap, a wider slit in the bone flap should be created to prevent postoperative swelling from strangulating the blood supply to the flap.

The increased bulk and vascularity of this flap make it appear to be a far superior flap than the pericranial flap for reconstruction of anterior defects. However, this loss of the galea and the frontalis muscle from the undersurface of the frontal scalp leaves a very thin, poorly vascularized flap of skin to cover the bone flap. With the transfer of this flap, sensation and animation of the frontal scalp are lost. Any defects in the frontal bone reconstruction such as bur holes and craniotomy bone cuts are readily seen through the thinned skin. Previous radiation therapy is a contraindication to the use of this flap.

The authors recommend that the pericranial flap be used as the first-line reconstruction in most anterior cranial defects, with the galeal-frontalis flap reserved for defects that warrant the extra bulk and vascularity it provides.

The superficial temporoparietal flap as outlined previously can be used in the anterior skull base as well. It is excellent for orbital lining and reconstruction after orbital exenteration. By extending the length of the flap during



FIG. 14. A: The pericranial flap is elevated away from the scalp after the resection has been completed. B: It is inset over the cribriform defect and attached with sutures to small holes drilled in the remnant of the roof of the sphenoid sinus.

harvest, the flap can reach across the midline to reconstruct the cribriform region.

Nerve Grafts

Nerve grafting, a common procedure in the rehabilitation of lateral skull base surgery, is most often performed for facial nerve loss. Although cranial nerves IX, X, XI, and XII are at significant risk during the resection of glomus. jugu-lare tumors, they are not often grafted because the proximal stumps adjacent to the brainstem are either unavailable for grafting or extremely difficult to graft to. Grafting in this situation has not been shown to be of benefit in the return of function of these nerves. However, during resection of glomus vagale tumors, if cranial nerves IX and XII are resected, their proximal stumps are often suitable for grafting. An interposition to reconstitute the vagus nerve has not been shown to effect return of laryngeal function. This was based on the observation that there was no return of vocal cord motion. No electromyographic follow-up has been performed on a group such as this to test for return of electromyographic activity. Maintenance of muscle bulk and motor tone, with the absence of motion, benefits voice and swallowing results. Thus, if the proximal stump of the vagus is available, either mobilization and proximal division of the recurrent laryngeal nerve to anastomose it directly to the vagal stump, or transfer of one of the ansa branches is recommended.

Infrequently, the facial nerve is resected in its mastoid portion secondary to malignant parotid, temporal bone, or glomus tumors, necessitating grafting. Three peripheral nerves are most often used for graft replacement in the lateral skull base: (a) the great auricular, (b) the sural, and (c) the medial antebrachial cutaneous.

Proximity to the operative site is the major advantage of the great auricular nerve. Often, it has to be divided for access to the lateral skull base, and thus no loss of function occurs with its use in these cases. The major disadvantage is the limited length of nerve available for the transfer. With proximal resection of the lower cranial nerves, its length is often insufficient for a tension-free graft. Also, if it has not been divided for tumor excision or access, the morbidity of sensory loss to the auricle is a complaint that will resurface as long as the patient is followed.

The sural nerve offers the advantage of increased length and size. It is formed by the union of the lateral sural cutaneous and the medial sural cutaneous nerves in the midcalf (9). It then descends along with the lessor saphenous vein to pass posterior and inferior to the lateral malleolus of the ankle (Fig. 15). The dissection, which is performed through a longitudinal incision to expose the nerve, is facilitated by a pressure cuff around the thigh. To gain adequate length, the branches are followed onto the dorsum of



FIG. 15. A: The course of the sural nerve is demonstrated passing posteroinferior to the lateral malleolus and then ramifying onto the dorsal surface of the foot. B: It has excellent size, but the branching pattern is not as good a match for total facial nerve replacement as the antebrachial nerve.



FIG. 16. A: The course of the medial antebrachial cutaneous nerve is demonstrated on the medial aspect of the arm. The use of the anterior branch is preferred over the ulnar branch. B: The size and branching of the nerve produce a good match for facial nerve replacement after extensive facial nerve resection.

the foot. The resultant sensory defect on the dorsal region of the foot is little noticed by the patient. The major disadvantage of this graft is the increased connective tissue-to-nerve fiber ratio seen in all nerves of the lower extremity compared with nerves of the upper extremity (10). This provides less opportunity for nerve regrowth.

Because of this, the authors' preference is the medial antebrachial cutaneous nerve, which descends through the arm, anterior and medial to the brachial artery in the medial intermuscular septum. At the junction of the middle and lower thirds of the arm, it pierces the brachial fascia along with the basilic vein and divides into an anterior and ulnar branch, providing sensation to the anterior forearm and posteromedial aspect of the forearm, respectively (Fig. 16). To dissect the nerve, a vertical incision is performed over the palpable groove between the biceps anteriorly and the triceps posteriorly on the medial aspect of the arm. The branches are identified and followed superiorly until the nerve is seen passing deep to the brachial fascia. The nerve can be followed further superior if necessary.

The distal ramification of the nerve is an excellent replacement for the facial nerve. The large size of the two major branches also makes for an excellent cable graft for any of the lower cranial nerves. The sensory loss on the medial aspect of the arm and elbow with use of the ulnar branch is more noticeable than the loss on the dorsal forearm from use of the anterior branch. For this reason, some have recommended use of the anterior division alone. This area of sensory loss gradually decreases with time. Care must be taken not to dissect deep into the intermuscular septum where the median motor nerve lies. Nerve stimulation with no paralysis under anesthesia before resection can ensure that the sensory antebrachial nerve has indeed been isolated. Its major advantage over the sural nerve is the decrease in the connective tissue-to-nerve fiber ratio seen in upper extremity nerves. This increase in neural tubules allows for greater nerve regeneration with improved return of function. The resultant sensory defect on the forearms is better tolerated than auricular sensory loss.

In summary, preoperative planning to keep all of the possible reconstructive options available is a very important part of skull base surgery. The patient and the family are always fully informed about each of the options that may be used during the reconstruction. Adequate reconstruction significantly decreases both the short- and long-term morbidity of these procedures.

REFERENCES

1. Jackson CG, Glasscock ME, Carrasco VN, et al. Defect reconstruction and CSF management in neurotologic skull base tumors with intracranial extension. *Laryngoscope* 1992:102:1205-1214.
2. Abul-Hassan HS, Ascher GD, Acland RD. Surgical anatomy and blood supply of the fascial layers of the temporal region. *P/ast Reconstr Surg* 1986:77:17-23.
3. Netterville JL, Panje WR, Maves MD. The trapezius myocutaneous flaps. *Archives ofOtolaryngology* 1987;! 13:271-281.
4. Urken ML, Naidu RK, Lawson W, Biller HF. The lower trapezius is-

land musculocutaneous flap revisited. *Arch Owlaryngol Head Neck Surg* 1991;! 17:502-511.

5. Netterville JL, Wood DE. The lower trapezius flap: vascular anatomy and surgical technique. *Archives of Otolaryngology* 1991;117:73-76.
6. Maves MD, Panje WR, Shagets F. Extended latissimus dorsi myocutaneous flap reconstruction of major head and neck defects. *Otolaryngol Head Neck Surg* 1984;92:551-558.
7. Sabatier RE, Bakamjian VY. Transaxillary latissimus dorsi flap reconstruction in head and neck cancer. *Am J Surg* 1985;150:427^O4.
8. Chowdhury CR, Mclean NR, Harrop-Griffiths K, Breach NM. The repair of defects in the head and neck region with the latissimus dorsi flap. *J Lan'iigvl Otol* 1988; 102:1127-1132.
9. Ortiguela ME, Wood MD, Cahill DR. Anatomy of the sural nerve complex. *J Hand Surg [Am]* 1987;12:1119-1123.
10. Slingluff CL, Terzis JK, Edgerton MT. The quantitative microanatomy of the brachial plexus in man: reconstructive relevance. In: Terzis JK, ed. *Microreconstruction of nerve injuries.* Philadelphia: WB Saunders, 1987:285-324.


A
Rhomboid Major
Descending Branch of Dorsal Scapular A.&V.
Rhomboid Minor
Dorsal Scapular A.&V.
Transverse Cervical A.
Latissimus Dorsi
B
Transverse Cervical A
Cut Edges of Rhomboid Minor
Levator Scapula
Dorsal Scapular A.&V.
Descending Branch of Dorsal Scapular A.&V.
Rhomboid Major

FIG. 10. A: The descending branches of the dorsal scapular artery often need to be divided to gain adequate length of the flap. B: If further length is needed, the rhomboid minor is divided and mobilized up with the pedicle.



FIG. 11. A: The mobilized flap can easily cover most temporal defects. The distal and proximal aspects of the oversized skin paddle are deepithelialized to adjust the flap to the defect. B: The flap is inset with primary closure of the donor site on the back.

neous muscle interface, which ensures more perforators into the cutaneous tissue. The distal end of the flap can either be divided or deepithelialized using the distal subcutaneous tissue for bulk. The back is closed primarily, and after surgery the patient is positioned on a pillow that contacts the back inferior to the scapular spine, with a second pillow under the head. This prevents pressures on the vessels as they rotate over the superior trapezius fibers.

The flap is excellent for cutaneous reconstruction in the temporal region when either skin or the entire auricle is resected along with the tumor. When the skin cover is intact, with substantial tissue loss resulting in exposed, unprotected vital structures, complete deepithelialization allows the flap to maintain excellent bulk and be safely buried. The flap has been used in this fashion for patients with persistent CSF leaks, postoperative wound infections, extensive dural loss with exposed cerebral and cerebellar tissue, and reconstruction of poorly vascularized tissue after radiation failure.

In the authors' series, significant flap loss has occurred in 3 of 52 flaps used for head and neck reconstruction. In the first case, a 40% distal flap loss occurred secondary to fat necrosis. The second patient was found the first morning after surgery lying on the pedicle rotation point with a pale dusky flap. A slow, creeping necrosis of the entire skin paddle occurred over the next 7 days. The final flap loss was due to inadequate blood supply after a previous radical neck dissection, in which the dorsal scapular artery was resected.

Latissimus Dorsi Myocutaneous Flap

The latissimus dorsi myocutaneous flap is reserved for extensive defects of the skull base. Free flap reconstruction is often preferred for defects of this magnitude. However, when there are factors that preclude the use of the free flap, the latissimus dorsi flap is an excellent choice. Details of this flap for use in the head and neck are outlined in series by Maves et al. (6), Sabatier and Bakamijian (7), and Chowdhury et al. (8). The potential size of the flap is its greatest advantage. A skin paddle can be elevated large enough to cover the entire hemicranium if needed. The harvest of the flap is fairly simple, with a large, easy-to-follow vascular pedicle. The major disadvantage of this flap is the long tunnel through which the pedicle must pass on its way to the head and neck defect. In the early postoperative period, the position of the arm is critical to prevent occlusion of the vein as it passes through the region of the pectoralis major and minor. Because of the pedicle and the weight of the flap, it has a tendency to "sag" over time, with a thinning-out of the superior area of the reconstruction. Because of the less frequent use of this flap, a brief account of the flap harvest is included.

The patient is positioned in the lateral decubitus position using a bean bag for support. The contralateral axilla is carefully padded with a wrapped bag of intravenous fluids, with the contralateral arm supported on an arm rest. No intravenous or intraarterial access is allowed in the ipsilateral arm so that it can be prepared into the field. This allows for ease of intraoperative positioning of the arm during flap dissection and closure of the donor defect. During resection of the head and neck primary, the bean bag may be deflated, allowing the patient to settle into the 45-degree position. After the completion of the resection, the patient is shifted back into the lateral decubitus position and the bag is refilled with air.

The latissimus muscle has a dual blood supply, with the dominant vascular source formed by the thoracodorsal artery and veins. The secondary blood supply is from the posterior paraspinous perforators. Both of these systems are diffusely interconnected. The myocutaneous flap for use in the head and neck is based on the thoracodorsal pedicle, necessitating sacrifice of the paraspinous perforators.

The subscapular artery, which is a branch off the third portion of the axillary artery, gives rise to the thoracodorsal artery, which enters the latissimus muscle on its anterior lateral margin and yields a vascular pedicle 10 to 12 cm in length. The first branch of the subscapular is the circumflex scapular artery, which rarely restricts the rotation of the flap and thus is not usually sacrificed during flap rotation. Several centimeters distal to its takeoff, the branch to the teres major is seen passing laterally. This vessel is usually sacrificed during flap harvest. Distal to this, one or two branches to the serratus anterior are encountered just before the entry of the thoracodorsal artery into the latissimus muscle. These vessels are divided unless the serratus muscle is harvested with the flap for unusually large defects.

The thoracodorsal artery divides into two major intramuscular divisions. The superior branch travels parallel to the upper border of the muscle about 3 cm inferior to the upper edge. The lateral branch travels parallel to the lateral margin of the muscle approximately 2 to 3 cm back from the lateral edge. This intramuscular division allows for a bipedicled flap to be developed as necessary.

After the conclusion of the resection, the anterior border of the latissimus muscle is palpated and outlined on the skin. The cutaneous paddle is outlined over the lateral inferior aspect of the muscle to allow for the added length needed to reach the head and neck defect (Fig. 12). The skin paddle is created too large to allow for later tailoring into the defect. An initial incision that is created along the anterior lateral border of the flap is extended up to but not into the axillary region. The anterior border of the muscle is isolated and followed up to the tendinous insertion onto the humerus. With careful dissection into the axillary fat pad, the thoracodorsal vessel is identified along with the associated vein and nerve. The neurovascular pedicle is developed proximally, ligating the vessels supplying the teres major and the serratus. The circumflex scapular vessels are identified but left intact. After flap rotation, they can be divided if further pedicle length is needed.



FIG. 12. The latissimus flap is outlined over the anterior border of the muscle, extending down too long to allow for later contouring into the defect. An extensive flap can be harvested with primary closure of the donor site.

The skin island is incised down to the muscle and the surrounding skin is elevated to expose the muscle. The latissimus is separated from the serratus from superior to inferior, where the plane between the two muscles becomes less distinct. After the remaining distal attachments of the muscle are separated, the humeral head is divided. The flap, which is now attached only by the neurovascular pedicle, is passed through the axilla through a tunnel created between the heads of the pectoralis major and minor. If more room is needed in the tunnel, the head of the pectoralis minor can be divided. The surgeon can create a path through the pectoralis major for passage of the pedicle by either spreading apart the muscle fibers or dividing some of the central fibers. Care is taken to prevent injury to the thoracoacromial vascular pedicle during this dissection in case future use of the pectoralis flap is needed. The flap then passes over the clavicle into the defect (Fig. 13). After initial inset of the flap into position, the pedicle is examined in the tunnel to see if any compression is isolated. The arm is abducted and adducted to see if the tunnel needs enlargement to prevent vascular compres-





FIG. 13. A,B: The latissimus myocutaneous flap is large enough to cover extensive defects of the lateral skull base. C: Over time, revision of this flap is necessary because of the inferior pull of the pedicle, resulting in "sagging" of the skin paddle.

sion. The thoracodorsal nerve is divided only if atrophy of the muscle is desired, or if it results in venous compression during the rotation of the flap.

The flap is tailored into the defect and the back is closed primarily over several closed-suction drains. If needed, the tendinous humeral portion of the muscle is attached to the chest wall or the pectoralis minor tendon to prevent further pull on the pedicle. Rarely after harvest of an extensive flap, the defect must be resurfaced with a split-thickness skin graft. Because of the constant movement in this area of the chest wall, the results of skin graft healing are often frustrating. After surgery, the ipsilateral arm is positioned in a neutral position, resting on a pillow, for several days, to prevent venous compression.

Anterior Skull Base

With the limitation of this chapter to reconstruction of the skull base with regional and pedicled flaps, this section dedicated to the anterior skull base is very brief. This region includes defects in the frontal bone and the cribriform region. Only the latissimus flap reaches this area, but it is a poor choice for reconstruction of this region. To reach this area well, the pedicle would have to pass externally, with a second stage necessary to take down the pedicle.

Most defects encountered in anterior skull base surgery are in the region of the cribriform plate as a result of craniofacial surgery. With defects limited to the roof of the nasal vault, reconstruction can be accomplished by use of local flaps. However, with loss of large volumes of soft tissue or frontal skull and overlying skin, reconstruction can be accomplished better using free tissue transfer.

Pericranial and Galeal Frontalis Flaps

The anterior scalp provides two different layers for reconstruction of the cribriform region. The major benefit of both these flaps is that they can be easily preserved along with their inferior blood supply during the standard bicoronal approach to lesions of the anterior skull base. The length of the flaps is determined by how high up on the scalp the bicoronal incision is outlined.

The most commonly used of the two is the pericranial flap, consisting of the periosteum of the anterior skull, based on branches of the supraorbital artery. The flap can be separated from the overlying scalp at the beginning of the procedure, or it can be raised up with the bicoronal flap, elevating it off the scalp at the end of the surgical resection of the tumor (Fig. 14). The latter provides better protection of the flap during the resection. During elevation, as the supraorbital region is approached, care is taken to include several of the branches of the supraorbital artery in the flap. With care, the sensory branches of the supraorbital nerve can be preserved passing into the scalp flap. The flap is inserted through the inferior lip of the frontal craniotomy after a few millimeters of the inferior aspect of the bone flap are removed to ensure adequate room for postoperative swelling of the base of the flap. The flap can be secured in place by drilling several 1.5-mm holes in the residual planum sphenoidale, taking care not to injure the optic nerves.

The major drawback to the pericranial flap is its limited blood supply. Often during postoperative examination of the nasal roof, the flap appears to have undergone partial necrosis with eschar formation. In spite of the postoperative appearance of the flap, very few CSF leaks occur. This area seems to be a very forgiving of this poorly vascularized reconstruction.

The galeal-frontalis flap offers a better-vascularized flap with more volume to reconstruct this same region. The frontal galea is the same layer anterior as the superficial temporal layer is over the temporal region. As the temporal region is left behind, the galea divides into two leaves enveloping the frontalis muscle. The major branches of the supraorbital artery and nerve pass into this layer. The flap is raised up with the bicoronal flap and elevated away from the scalp when needed. Because of the increased thickness of this flap, a wider slit in the bone flap should be created to prevent postoperative swelling from strangulating the blood supply to the flap.

The increased bulk and vascularity of this flap make it appear to be a far superior flap than the pericranial flap for reconstruction of anterior defects. However, this loss of the galea and the frontalis muscle from the undersurface of the frontal scalp leaves a very thin, poorly vascularized flap of skin to cover the bone flap. With the transfer of this flap, sensation and animation of the frontal scalp are lost. Any defects in the frontal bone reconstruction such as bur holes and craniotomy bone cuts are readily seen through the thinned skin. Previous radiation therapy is a contraindication to the use of this flap.

The authors recommend that the pericranial flap be used as the first-line reconstruction in most anterior cranial defects, with the galeal-frontalis flap reserved for defects that warrant the extra bulk and vascularity it provides.

The superficial temporoparietal flap as outlined previously can be used in the anterior skull base as well. It is excellent for orbital lining and reconstruction after orbital exenteration. By extending the length of the flap during



FIG. 14. A: The pericranial flap is elevated away from the scalp after the resection has been completed. B: It is inset over the cribriform defect and attached with sutures to small holes drilled in the remnant of the roof of the sphenoid sinus.

harvest, the flap can reach across the midline to reconstruct the cribriform region.

Nerve Grafts

Nerve grafting, a common procedure in the rehabilitation of lateral skull base surgery, is most often performed for facial nerve loss. Although cranial nerves IX, X, XI, and XII are at significant risk during the resection of glomus. jugu-lare tumors, they are not often grafted because the proximal stumps adjacent to the brainstem are either unavailable for grafting or extremely difficult to graft to. Grafting in this situation has not been shown to be of benefit in the return of function of these nerves. However, during resection of glomus vagale tumors, if cranial nerves IX and XII are resected, their proximal stumps are often suitable for grafting. An interposition to reconstitute the vagus nerve has not been shown to effect return of laryngeal function. This was based on the observation that there was no return of vocal cord motion. No electromyographic follow-up has been performed on a group such as this to test for return of electromyographic activity. Maintenance of muscle bulk and motor tone, with the absence of motion, benefits voice and swallowing results. Thus, if the proximal stump of the vagus is available, either mobilization and proximal division of the recurrent laryngeal nerve to anastomose it directly to the vagal stump, or transfer of one of the ansa branches is recommended.

Infrequently, the facial nerve is resected in its mastoid portion secondary to malignant parotid, temporal bone, or glomus tumors, necessitating grafting. Three peripheral nerves are most often used for graft replacement in the lateral skull base: (a) the great auricular, (b) the sural, and (c) the medial antebrachial cutaneous.

Proximity to the operative site is the major advantage of the great auricular nerve. Often, it has to be divided for access to the lateral skull base, and thus no loss of function occurs with its use in these cases. The major disadvantage is the limited length of nerve available for the transfer. With proximal resection of the lower cranial nerves, its length is often insufficient for a tension-free graft. Also, if it has not been divided for tumor excision or access, the morbidity of sensory loss to the auricle is a complaint that will resurface as long as the patient is followed.

The sural nerve offers the advantage of increased length and size. It is formed by the union of the lateral sural cutaneous and the medial sural cutaneous nerves in the midcalf (9). It then descends along with the lessor saphenous vein to pass posterior and inferior to the lateral malleolus of the ankle (Fig. 15). The dissection, which is performed through a longitudinal incision to expose the nerve, is facilitated by a pressure cuff around the thigh. To gain adequate length, the branches are followed onto the dorsum of



FIG. 15. A: The course of the sural nerve is demonstrated passing posteroinferior to the lateral malleolus and then ramifying onto the dorsal surface of the foot. B: It has excellent size, but the branching pattern is not as good a match for total facial nerve replacement as the antebrachial nerve.



FIG. 16. A: The course of the medial antebrachial cutaneous nerve is demonstrated on the medial aspect of the arm. The use of the anterior branch is preferred over the ulnar branch. B: The size and branching of the nerve produce a good match for facial nerve replacement after extensive facial nerve resection.

the foot. The resultant sensory defect on the dorsal region of the foot is little noticed by the patient. The major disadvantage of this graft is the increased connective tissue-to-nerve fiber ratio seen in all nerves of the lower extremity compared with nerves of the upper extremity (10). This provides less opportunity for nerve regrowth.

Because of this, the authors' preference is the medial antebrachial cutaneous nerve, which descends through the arm, anterior and medial to the brachial artery in the medial intermuscular septum. At the junction of the middle and lower thirds of the arm, it pierces the brachial fascia along with the basilic vein and divides into an anterior and ulnar branch, providing sensation to the anterior forearm and posteromedial aspect of the forearm, respectively (Fig. 16). To dissect the nerve, a vertical incision is performed over the palpable groove between the biceps anteriorly and the triceps posteriorly on the medial aspect of the arm. The branches are identified and followed superiorly until the nerve is seen passing deep to the brachial fascia. The nerve can be followed further superior if necessary.

The distal ramification of the nerve is an excellent replacement for the facial nerve. The large size of the two major branches also makes for an excellent cable graft for any of the lower cranial nerves. The sensory loss on the medial aspect of the arm and elbow with use of the ulnar branch is more noticeable than the loss on the dorsal forearm from use of the anterior branch. For this reason, some have recommended use of the anterior division alone. This area of sensory loss gradually decreases with time. Care must be taken not to dissect deep into the intermuscular septum where the median motor nerve lies. Nerve stimulation with no paralysis under anesthesia before resection can ensure that the sensory antebrachial nerve has indeed been isolated. Its major advantage over the sural nerve is the decrease in the connective tissue-to-nerve fiber ratio seen in upper extremity nerves. This increase in neural tubules allows for greater nerve regeneration with improved return of function. The resultant sensory defect on the forearms is better tolerated than auricular sensory loss.

In summary, preoperative planning to keep all of the possible reconstructive options available is a very important part of skull base surgery. The patient and the family are always fully informed about each of the options that may be used during the reconstruction. Adequate reconstruction significantly decreases both the short- and long-term morbidity of these procedures.

REFERENCES

1. Jackson CG, Glasscock ME, Carrasco VN, et al. Defect reconstruction and CSF management in neurotologic skull base tumors with intracranial extension. *Laryngoscope* 1992:102:1205-1214.
2. Abul-Hassan HS, Ascher GD, Acland RD. Surgical anatomy and blood supply of the fascial layers of the temporal region. *Plast Reconstr Surg* 1986:77:17-23.
3. Netterville JL, Panje WR, Maves MD. The trapezius myocutaneous flaps. *Archives of Otolaryngology* 1987;! 13:271-281.
4. Urken ML, Naidu RK, Lawson W, Biller HF. The lower trapezius is-

land musculocutaneous flap revisited. *Arch Owlaryngol Head Neck Surg* 1991;! 17:502-511.

5. Netterville JL, Wood DE. The lower trapezius flap: vascular anatomy and surgical technique. *Archives of Otolaryngology* 1991;117:73-76.
6. Maves MD, Panje WR, Shagets F. Extended latissimus dorsi myocutaneous flap reconstruction of major head and neck defects. *Otolaryngol Head Neck Surg* 1984;92:551-558.
7. Sabatier RE, Bakamjian VY. Transaxillary latissimus dorsi flap reconstruction in head and neck cancer. *Am J Surg* 1985;150:427^O4.
8. Chowdhury CR, Mclean NR, Harrop-Griffiths K, Breach NM. The repair of defects in the head and neck region with the latissimus dorsi flap. *J Lan'iigvl Otol* 1988; 102:1127-1132.
9. Ortiguela ME, Wood MD, Cahill DR. Anatomy of the sural nerve complex. *J Hand Surg [Am]* 1987;12:1119-1123.
10. Slingluff CL, Terzis JK, Edgerton MT. The quantitative microanatomy of the brachial plexus in man: reconstructive relevance. In: Terzis JK, ed. *Microreconstruction of nerve injuries.* Philadelphia: WB Saunders, 1987:285-324.

продолжение

JAYPEE

SRB's Surgical Operations
Text & Atlas





Sriram Bhat M

Forewords
K Ganesh Pai
Ashok Pandit

SRB's
Surgical Operations
Text and Atlas

SRB's
Surgical Operations
Text and Atlas

Sriram Bhat M MS (General Surgery)
Professor
Department of Surgery
Kasturba Medical College
Mangalore, Karnataka, India

Honorary Surgeon
Government Wenlock Hospital Mangalore, Dakshina Kannada, Karnataka, India
e-mail: meera_sriram2003@yahoo.com

Forewords
Dr K Ganesh Pai
Dr Ashok Pandit

JAYPEE

JAYPEE BROTHERS MEDICAL PUBLISHERS (P) LTD

New Delhi • London • Philadelphia • Panama

Jaypee Brothers Medical Publishers (P) Ltd

Headquarters

Jaypee Brothers Medical Publishers (P) Ltd
4838/24, Ansari Road, Daryaganj
New Delhi 110 002, India
Phone: +91-11-43574357
Fax: +91-11-43574314
Email: jaypee@jaypeebrothers.com

Overseas Offices

J.P. Medical Ltd
83, Victoria Street, London
SW1H 0HW (UK)
Phone: +44-2031708910
Fax: +02-03-0086180
Email: info@jpmedpub.com

Jaypee-Highlights Medical Publishers Inc
City of Knowledge, Bld. 237, Clayton
Panama City, Panama
Phone: + 1 507-301-0496
Fax: + 1 507-301-0499
Email: cservice@jphmedical.com

Jaypee Medical Inc
The Bourse
111 South Independence Mall East
Suite 835, Philadelphia, PA 19106, USA
Phone: + 1 267-519-9789
Email: jpmed.us@gmail.com

Jaypee Brothers Medical Publishers (P) Ltd
17/1-B Babar Road, Block-B, Shaymali
Mohammadpur, Dhaka-1207
Bangladesh
Mobile: +08801912003485
Email: jaypeedhaka@gmail.com

Jaypee Brothers Medical Publishers (P) Ltd
Bhotahity, Kathmandu
Nepal
Phone: +977-9741283608
Email: kathmandu@jaypeebrothers.com

Website: www.jaypeebrothers.com
Website: www.jaypeedigital.com

© 2014, Jaypee Brothers Medical Publishers

The views and opinions expressed in this book are solely those of the original contributor(s)/author(s) and do not necessarily represent those of editor(s) of the book.

All rights reserved. No part of this publication may be reproduced, stored or transmitted in any form or by any means, electronic, mechanical, photocopying, recording or otherwise, without the prior permission in writing of the publishers.

All brand names and product names used in this book are trade names, service marks, trademarks or registered trademarks of their respective owners. The publisher is not associated with any product or vendor mentioned in this book.

Medical knowledge and practice change constantly. This book is designed to provide accurate, authoritative information about the subject matter in question. However, readers are advised to check the most current information available on procedures included and check information from the manufacturer of each product to be administered, to verify the recommended dose, formula, method and duration of administration, adverse effects and contraindications. It is the responsibility of the practitioner to take all appropriate safety precautions. Neither the publisher nor the author(s)/editor(s) assume any liability for any injury and/or damage to persons or property arising from or related to use of material in this book.

This book is sold on the understanding that the publisher is not engaged in providing professional medical services. If such advice or services are required, the services of a competent medical professional should be sought.

Every effort has been made where necessary to contact holders of copyright to obtain permission to reproduce copyright material. If any have been inadvertently overlooked, the publisher will be pleased to make the necessary arrangements at the first opportunity.

Inquiries for bulk sales may be solicited at: jaypee@jaypeebrothers.com

SRB's Surgical Operations: Text and Atlas

First Edition: **2014**

ISBN 978-93-5025-121-8

Printed at

This book is dedicated to
My beloved father

Late Mr Krishna Bhat Muguli

from whom I have learnt *simplicity, contentment, humility and dedication*.

and

Mangala Hospital and Mangala Kidney Foundation, Mangalore, India

MANGALA HOSPITAL

Contributors

Dr Ashok Shetty
Cardiothoracic Surgeon
Mangalore
Contributed to Chapter on Surgeries of Arterial Diseases

Dr Ashok Pandit
Urologist
Mangala Hospital, Mangalore
Contributed to Chapter on Urologic Surgeries

Dr K Venkatesha Udupa
Department of HPB Surgery and Liver Transplantation
St Vincent's University Hospital, Dublin, Ireland
Contributed to Chapter on Surgeries of Liver and Gallbladder especially Liver Transplantation.

Dr Meera Karanth P
Consultant Gynaecologist, Mangalore
Wrote the Chapter on Surgeries of Obstetrics and Gynaecology

Dr Keshavaprasad
Associate Professor in Surgery
KMC, Mangalore
Contributed to Chapter on Basics in Laparotomy and Laparoscopy and Surgeries of Liver and Gallbladder and Surgeries of Pancreas

Dr Arun Kumar
Consultant Surgical Gastroenterologist, Cochin
Contributed to Chapter on Surgeries of Liver and Gallbladder and Surgeries of Pancreas

Foreword

It is my pleasure to write a foreword for *SRB's Surgical Operations*. Let me, at the outset, congratulate Dr Sriram Bhat M for launching this fantastic book. Dr Bhat belongs to a rare breed of surgeons, who has not only mastered the art of excellence of teaching but also bestowed with superb skill in surgery and documentation. This facet has been put on record by bagging Good Teacher Award twice from Kasturba Medical College, Mangalore, a constituent college of prestigious university, MAHE Manipal and churning out about half a dozen textbooks related to surgery. These books have been well received and sold like cakes within India and abroad.

I have gone through the contents of this book and it is quite fascinating. It has about 1,400 pages containing colored illustrations of operative procedures spread across fields of general surgery, GI tract surgery, urology, vascular surgery, and basic laparoscopy. A study of this book, at the very least, stimulates surgeons to think about their own technique. It is unlikely that a surgeon who is expert in a particular operation will turn to this book for advice about that operation, but it is to be expected that the same surgeon will obtain useful information from this book when called upon to operate in less familiar field. I sincerely appreciate and applaud with deep admiration the efforts put in by Dr Bhat (fondly referred as SRB by his students and colleagues) devoting his valuable time at the cost of his family and professional life towards this esthetic collection, which in a nutshell is extremely par excellent.

I, therefore, wholeheartedly support this book and recommend its use by undergraduate and postgraduate students, general surgeons and all those who need guidance in the field of operative surgery and basic laparoscopy.

Dr K Ganesh Pai
Senior Pediatric Surgeon and Pediatric Urologist
Emeritus Professor of Pediatric Surgery
KMC, Mangalore

Foreword

No matter how well read and proficient in clinical skills, the ultimate test of a surgeon is the operation theatre. Although a mastery of operative surgery does require a lifetime's practice, having a good teacher/mentor and access to a thorough text on operative surgery, will shorten the learning curve. This textbook with its exhaustive coverage of practically all surgical procedures (common and otherwise) will definitely be useful to both undergraduate and postgraduate students of surgery as well as practitioners of the art. The plentiful illustrations are simple and enhance the understanding.

It is my distinct privilege to have been associated with Dr Sriram Bhat since his time as a postgraduate in surgery and has a great love for teaching. The large number of students who flock his weekly bedside clinics in district Wenlock hospital, ever since he joined the faculty of general surgery, are a testament to his ability to impart knowledge. Having worked with him for over 20 years, I have seen him grow in stature and knowledge as a surgeon. He picks up new skills like laparoscopy through sheer hard work. Dr Sriram also has prodigious literary output. He has written more than five books in relation to surgery for medical, dental and nursing graduates. His *SRB's Manual of Surgery* has proved hugely popular among undergraduates in India and abroad. Having seen his labour day and night at documenting the various surgical procedures and, of course, the laborious collating, writing and proofreading often into the wee hours of the morning reminded me of Duke Elder (of the classic ophthalmic text) who reputedly made with barely an hour's sleep! I thank Dr Sriram for giving me this unique honour of writing the foreword for this operative book which I am certain will also prove equally popular and useful.

Dr Ashok Pandit
Consultant Urologist,
Mangala Hospital and Mangala Kidney Foundation,
Kadri, Mangalore

Preface

It was my long dream after writing *SRB's Manual of Surgery* to pen in relations to operative technique in detail from simplest procedure to essential advanced major procedures needed to general surgeons and surgical postgraduates. I took nearly 4 years to make my dream near true in the form of *SRB's Surgical Operations*. I have included umpteen numbers of illustrations and photographs. Basic principles and techniques of suturing and dissection also dealt with in detail. It will be useful to all categories of students and consultants to learn basic. Gastrointestinal surgery is discussed in detail with illustrations. Urology mainly open methods are discussed adequately if not extensively. Basic laparoscopy and usual laparoscopy surgeries are discussed with highlighting the robotic surgeries, liposuction and so on. It differs from other operative surgery books by its unique presentations in detail with surgical anatomy and operative photographs of most of the procedures. I presume students and consultants will enjoy its reading. I am always grateful to Shri Jitendar P Vij for his support and encouragement towards me to bring out this book. Any comments and healthy criticisms are well accepted.

Sriram Bhat M
e-mail: meera_sriram2003@yahoo.com

Acknowledgements

I thank our Chancellor (MAHE) Dr Ramdas M Pai; Pro Chancellor Dr HS Ballal; our beloved Dean Professor Venkatraya Prabhu our Vice Dean Professor Anand Kini of Kasturba Medical College, Mangalore, India, for their academic support.

I thank Dr Ganapathy, Medical Director and renowned Senior Anaesthesiologist, Mangala Hospital and Mangala Kidney Foundation Kadri, Mangalore, for his continuous help and encouragement.

I thank the Head of Department of Surgery, KMC, Mangalore, Professor Alfred Augustine, for his constant encouragement in academic work and progress.

I always remember my senior teachers, Professor CR Ballal and Professor Suresh Kamath, Professor K Prakash Rao, Professor Subramanya Bhat, Professor Bhaskar Shetty and Professor Ramachandra Pai, for their constant help.

I thank Dr Professor K Ganesh Pai, Paediatric Surgeon, for his encouragement and writing foreword to this book. He was my thesis guide and a very renowned surgeon too.

Professor Prakash Rao, as a guide and encourager to everybody, will be remembered as a special person by me always.

I thank my beloved friend, well-known popular urologist, Dr Ashok Pandit, Mangalore, who has been helping me in all aspects of my surgical career.

My special thanks to Dr Jayaram Shenoy and Dr Jayaprakash Rao, for their affection and support.

Dr Ashok Shetty, MCh, Cardiothoracic Surgeon, has helped me by adding contributions in chapter on surgeries of arterial diseases. I thank him a lot.

I appreciate District Medical Officer and Resident Medical Officer of Government Wenlock Hospital, Mangalore, for their kind help.

I am grateful to all my teachers and colleagues in surgery department who directly or indirectly helped me to bring out this book.

Surgical unit heads in our college Dr BM Nayak, Dr Thangam Verghese, Dr Harish Rao, Dr Shivaprasad Rai, Dr Yogish Kumar, and Dr Shivananda Prabhu are always supportive for my work and are worth to be remembered always. Dr Manohar Pai, Dr Ashfaque Mohammed, and Dr Keshavaprasad are of special mention. Dr Keshavaprasad has helped by adding contributions in few chapters of his interests.

I thank Dr K Venkatesha Udupa, Department of HPB Surgery and Liver Transplantation, St Vincent's University Hospital, Dublin, Ireland, contributed to chapter on surgeries of liver and gallbladder especially liver transplantation. I also thank Dr Arun Kumar MCh, Surgical Gastroenterologist, for contributing a lot of GI photographs. I thank Dr Ravishankar, Surgical Gastroenterologist, Bengaluru, for helping by providing photographs in chapter on surgeries of liver and gallbladder.

My wife Dr Meera Karanth helped me day and night by contributing the chapter of surgeries in obstetrics and gynaecology and without her help this could not have been possible. My beloved daughter Ananya helped me in drawing new diagrams artistically. I enjoy her love and affection towards me.

I thank Dr Suresh Pai, MCh, Dr Divakar Rao (Neurosurgeon), Dr C K Bantwal (Neurosurgeon), Dr Muralidhar Pai, MCh (neurosurgery), Dr Laxman Prabhu, Urologist, Dr Ranjith, Urologist, Late Dr Vivekanand Prabhu (Paediatric Surgery), Dr Sadashiva Rao, Paediatric Surgeon, and Dr Narayana Bhat, Paediatric Surgeon, for their help and contributions.

I thank Professor Anitha Ganapathy Bhat, Mangala Hospital, Kadri, Mangalore.

I thank my friend Dr Jagadish MDS for his contributions on dental and faciomaxillary topics.

I sincerely thank Professor Navinchandra Shetty, and staff of Radiology Department KMC, Mangalore and also other faculty of the department for their help in providing and guiding me in X-rays, CT scans and imaging methods.

I thank Dr Kalpana Sridhar, Dr Harischandra, Dr Shivashankar, Dr Devidas Shetty, Dr Ramesh, Dr K Akbar, Dr Achaleshwar Dayal, Dr Raghav Pandey, Dr Shibu Mohan, Dr Poornachandra, Dr Sunilkumar Shetty, Dr Venkatesh Shanbogh, Dr Ranjith Rao, Dr Irshad, Dr Amar, Dr Rajesh, Dr Suyog, Dr Chandini, Dr Adithya, Dr Javahar, Dr Ashok Hegde, Dr Rajesh Ballal, Dr Devidas Shetty, Dr Venkstesh Sanjeeva, Dr Shanbogh, Dr Harish Nayak, Dr Subraya Kamath, and Dr Sampath, for their help in various aspects.

I sincerely appreciate Dr Raghavendra Bhat and Dr Ravichandra, Consultants in Radiology Department, Yenepoya Medical College, Mangalore, for their contribution and affectionate help. My special thanks to Dr Prashant Mallya, Anaesthetist, for guiding me in many places.

My postgraduates are of special mention as they constantly helped by in taking photographs and proofreadings to mention Dr Aromol C, Dr Hemanth Makineni, Dr T Sudheendra, Dr Sunil Math, Dr Srikanth Soma, Dr Guruprasad Reddy, Dr Anand R Baid, Dr Nanjundiah, Dr Abid Ali Mirza, Dr Rama Mani Lam, Dr Vijay, Dr Ashish, and all others. I appreciate them for their affectionate help.

I remember my students Dr Ravi CR, Dr Ashwini Polnaya, Dr Ishwara Keerthi, Dr Sudesh, Dr Narasimha Murthy, and Dr Ashish Singh, for their special contributions.

I thank all my students especially postgraduates of surgery department who were helping regularly in bringing out this book.

I thank all staff in operation theatre and others in Mangala Hospital, Mangalore, for their help in taking needed photographs of the different procedures.

Words are not sufficient to remember all my patients who are the main material for the book. I pray for their good health always.

I appreciate Shri Jitendar P Vij Sir (Group Chairman), Mr Ankit Vij (Managing Director), Mr Tarun Duneja (Director-Publishing) of M/s Jaypee Brothers Medical Publishers (P) Ltd, New Delhi, India. My sincere thanks to editing team members—Ms Sunita Katla (Publishing Manager), Mr KK Raman (Production Manager), Ms Seema Dogra (Cover Designer), Ms Geeta Srivastava and Mr Laxmidhar Padhiary (Proofreaders), Mr Kapil Dev Sharma and Mr Kulwant Singh (DTP Operators), and Mr Gopal Singh Kirola and Mr Rajesh Ghurkundi (Graphic Designers) of M/s Jaypee Brothers Medical Publishers (P) Ltd, New Delhi, India, for their dedicated and affectionate work in bringing out this book. Also, my appreciation to working team in the Branches of Jaypee Brothers Medical Publishers at Bengaluru and Mangalore, for their timely help.

Contents

Chapter 1: Introduction and Principles in Operative Surgery **1**
Chapter 2: Preoperative Preparation, Operation Room, Postoperative Care **9**
Chapter 3: Basic Principles of Incision, Dissection, Suturing and Haemostasis **34**
Chapter 4: Day Care Surgery, Ambulatory Surgery, Outpatient Surgery **68**
Chapter 5: Instruments **71**
Chapter 6: Energy Sources in Surgery **121**
Chapter 7: Basic Surgical Procedures **132**
Chapter 8: Principles of Surgical Management in Trauma **198**
Chapter 9: Principles of Surgical Treatment in Infections **226**
Chapter 10: Amputations **247**
Chapter 11: Surgeries in Arterial Diseases **273**
Chapter 12: Surgery in Venous Diseases **345**
Chapter 13: Surgeries of Nerves, Muscles and Tendons **376**
Chapter 14: Surgeries of Face, Head and Neck **388**
Chapter 15: Surgery for Thyroid and Parathyroid **440**
Chapter 16: Surgeries for Breast Diseases **470**
Chapter 17: Surgeries of Salivary Glands **499**
Chapter 18: Basic Principles in Laparotomy and Laparoscopy **515**
Chapter 19: Surgery of Oesophagus **579**
Chapter 20: Surgery of Stomach and Duodenum **634**
Chapter 21: Surgeries of Small Bowel and Appendix **696**
Chapter 22: Surgeries of Liver and Biliary System **754**
Chapter 23: Surgeries of Pancreas and Spleen **866**
Chapter 24: Colonic Surgeries **938**
Chapter 25: Anorectal Surgeries **979**

Chapter 26: Retroperitoneal Surgeries **1045**
Chapter 27: Urologic Surgeries **1049**
Chapter 28: Obesity and Morbid Obesity **1101**
Chapter 29: Adrenal Gland Surgeries **1106**
Chapter 30: Surgeries in Hernia **1121**
Chapter 31: Surgeries of Penis, Scrotum and Testis **1190**
Chapter 32: Basic Surgeries in Obstetrics and Gynaecology **1240**
Chapter 33: Other Procedures **1305**
Index ***1311***

Chapter

1

Introduction and Principles in Operative Surgery

Surgery is an *art,* but it is not just an art; it is an art with principles, dedication, determination, gentleness, tissue respect. It is an *irreversible art* work which if improperly done can be counter-productive. Doing surgery without principle is like an operator doing job without knowing the outcome.

It is often wrongly considered that quicker the surgeon, better he is. *Fast surgery* is probably *glamour* than an essentiality. *Speed* of the operator is only a *short term* impression. Rapid operator concept itself is a *myth*. It is the *accuracy and delicacy* of the procedure which is more important. Speed comes eventually by practice, experience, skill and knowledge. One should not force the speed; it should be spontaneous. It is the *precision* which is more important than speed. *However* quickness is needed in surgical emergencies especially in trauma and torrential bleeding situations. It again doesn't mean that one can violate the principles. *Art of surgery* means knowing proper surgical anatomy, surgical pathology, tissue respect and handling technique, gentleness, proper haemostasis, asepsis, good knowledge of different instruments and skill. *A surgeon* should be artistic, innovator, teacher, principled and superb operator.

Every surgical condition may not require surgery. Individual patient is assessed and planned for surgery individually. *Planning, thinking, skill, execution* are the assets of proper surgery. Doing wrong procedure in wrong time, with *wrong need* even through a brilliant technical execution will give a poor result. He may be considered as a *good operator* but a *poor* surgeon.

Often there are many surgical procedures as therapy for a single disease. *Merits and demerits* of each and which is ideal to that particular situation should be analysed prior to deciding the procedure. The so called '*decision making'* is very important since olden days.

Adequate length of incision; proper retraction; *minimum touch* technique (means dissection is done with instruments mainly and with fingers when needed and avoid unnecessary rough tissue handling); haemostasis; tissue respect; gentleness; patience; tolerance; avoiding restlessness; adequate exposure; safety methods; proper knowledge of different techniques; anticipation of problems; so prevention of problems; tackling ability of on table complications; taking help of additional/senior/experienced surgeons when needed without any ego—are the basic essentials of a *quality* surgeon.

Safe surgery needs–clear surgical anatomy; right anaesthesia; haemostasis; asepsis; skill with patience; learning attitude; dedication and determination.

Surgery should not be a glamour; but it should be a dedicated profession.

■ POSITION OF THE SURGEON

Surgeon has to spend hours of time continuously in the operation theatre. So he needs both physical as well as mental stamina for this. He should be comfortable, and relaxed. Posture is important while doing surgery. Otherwise surgeon may develop back/neck pain or other postural abnormalities. Many procedures like surgeries of hand and brain are often comfortably done in sitting position. It is good practice to make assistant and scrub nurse also to sit during such procedures as assistants also should be comfortable while doing procedure. Shoulder should be relaxed and elbow should be relaxed and flexed at 90°.

Suturing involves using of biceps muscle to move hand from a pronated to a supinated position in a natural rolling motion and is called as *forehand suturing.* So right hand surgeon assumes his body and foot for greatest efficiency. Suturing is done from right side with needle position aiming towards surgeons left foot. Both feet are placed perpendicular to the table; both parallel to each other.

Backhand manoeuvre is done by moving hand from supinated position to roll backward to reach pronated position. Position of feet and body of the surgeon should be reversed or altered depending on the convenient of technique like backhand suturing. Often both feet may be required to be placed parallel to the table. Scalpel blade is usually used in backhand movement. Suturing is preferred in *forehand* movement. Scissor is pointed towards left of the right hand surgeon. Electrocautery cutting is directed towards right foot like scalpel blade.

Position *of right hand* surgeon and *left hand* surgeon even though vary; it is better every surgeon to have a fair skill of using both hands effectively. Which side of the patient surgeon should stand even though is a matter of convenience; but in usual practice is surgeon stands on right side of the patient if he is a right hand surgeon or left hand surgeon. But surgeon should be flexible enough to *change the side* as required or as when difficulty arises during the procedure. There should not be prejudiced or have a prefixed idea about these things as *comfort of the surgeon* is the priority.

There are *separate instruments* manufactured for left hand surgeons. But due to limited availability and cost factor because of less number of left hand surgeons overall (even though exact ratio is not known, probably left hand surgeons are less than 1%) makes left hand surgeons compulsorily use right hand instruments successfully.

Even though it is often categorised as minor and major operations, it should be considered that *all surgeries are major*. By experience and knowledge surgeon may feel that surgery is minor. Practically if one looks in patient's angle; for each patient whatever procedure he/she is undergoing is important and is always for the first time. For surgeon again it is imperative to execute enough care and skill whether the procedure/surgery are small or big. So optimum care is mandatory for all procedures, without any shortcomings.

HISTORY OF SURGERY

It is interesting to know little bit of the history in relation to surgery. Its evolvement was gradual, slow with lot of trial and errors. Acceptance, criticism were the problems in developing the newer avenues. There are so many contributors for development and progress of surgery since many centuries **(Figs 1-1 to 1-26)**.

Wound closure has originated as early as 17th century BC.



Fig. 1-1: Hippocrates (400 BC). He described umbilical hernia, acute abdomen, terminal ill patient in peritonitis, his famous oath.



Fig. 1-2: Courvoisier. He did extensive work on biliary surgery. He originated his famous Courvoisier's law.

Sushruta in ancient India gave the concept of nasal reconstruction after punishment loss of nose in 600 BC. He repaired intestine perforation using ant heads–natural stapling. It was called as ' Sushruta era' **(Fig. 1-4)**. *Sushruta Samhita* is premedieval period treatise in surgery. Book had five sections.



Fig. 1-3: Joseph E Murray. He got Nobel Prize in 1990 for organ and cell transplantation along with E Donnall Thomas. He did first successful human kidney transplantation between identical twins in December 23, 1954 on patient Richard Herric who lived and married recovery room nurse.



Fig. 1-4: Sushruta.

Abu Kassim (1000 BC) used animal intestine suture material to close the bowel. In 12th century silk became a suture material

Successful human skin graft was done by **Sir Astley Cooper** in 1817.

Andreas Vesalius from Padua, Italy (1514 - 1564) gave the importance of human anatomy in surgery **(Fig. 1-5)**. He gave concept of human dissection in learning anatomy and surgery. He wrote anatomy book 'De Humani Coporis Fabrica Libri'.



Fig. 1-5: Andreas Vesalius.



Fig. 1-6: Chester B McVay. He did extensive work on hernia surgery.

Ambroise Pare (Paris; 1510 - 1590) did revolution in surgery by practicing ligation of individual vessels doubly especially in amputation **(Fig. 1-7)**. He said, "I treated him; God cured him". He started concept of controlled experimentation.



Fig. 1-7: Ambroise Pare.

Albucasis, Moorish clinician (A.D. 952, Arab) did first successful thyroidectomy; was bold, venturesome operator. He wrote that time famous medical book '*al-Tasrif*'. He also used catgut, cotton sutures. He also used to do small bowel anastomosis.

John Hunter (Glasgow, England; 1728–1793) an excellent surgeon **(Fig. 1-8)** of that time wrote many books on surgery, war wounds. He had outstanding collections of 13,000 specimens which were present in the Museum of Royal College of Surgeons which was destroyed during World War II by Nazi bombing. He described aneurysms and, its treatment, shock, phlebitis, nasogastric feeding, and respiratory assisting. He died of inoculation of syphilis and gonorrhoea by mistake. He thought of transplantation and angiogenesis and did experiments on it. He gave the importance of experimental surgery, study of anatomy and natural history in surgery.



Fig. 1-8: John Hunter.

Joseph Lister (Scotland/England; 1827–1912) evoluted the concept of asepsis and antisepsis. He started chemical antisepsis using carbolic acid. He originated proper cleaning of the wound and area prior to surgery to improve the results and reduce the sepsis. He started use of sterile sutures in surgery. His era is called as *Listerism*. He invented Lister's sinus forceps, pointed scissors, catgut ligature. He is rightly known as the father of modern surgery **(Fig. 1-9)**.



Fig. 1-9: Joseph Lister.

William T G Morton, a Boston dentist, on October 16th in 1846, first gave ether anaesthesia successfully to a patient operated by John Collins Warren on patient Gilbert Abbott to remove jaw tumour **(Fig. 1-10)**.



Fig. 1-10: William T G Morton.

Wilhelm Conrad Roentgen (1845–1923) invented X-rays (1895) also called as Roentgen rays as basic diagnostic tool. He got Nobel Prize for the same **(Fig. 1-11)**.



Fig. 1-11: Wilhelm Conrad Roentgen.

Rudolph Matas (America 1860–1957) **(Fig. 1-12)** was a pioneer in vascular surgery; started endoaneurysmorrhaphy.



Fig. 1-12: Rudolph Matas.

William S Halsted (America 1852–1922) **(Fig. 1-13)** did extensive work on surgeries of breast and hernia. Halsted concept in carcinoma of breast and Halsted's radical mastectomy has ruled surgical era for a century until concept has changed from 1980 onwards. He started the use of gloves during surgery. He also started residency training in United States. He did works on hernia surgery also.



Fig. 1-13: William S Halsted.

Bernard von Langenbeck (German 1810–1887) **(Fig. 1-14)** did lots of contributions to surgery in technique, precision and instruments. He did first successful cholecystectomy in 1882.



Fig. 1-14: Bernard von Langenbeck.

Theodor Billroth (Vienna 1829–1894) **(Fig. 1-15)** did extensive work in abdominal surgery. Billroth anastomosis after gastrectomy is good old popular method.

Fig. 1-15: Theodor Billroth.

Schlatter first did successful total gastrectomy in 1897.

Senn did successful appendicectomy in 1889.

Lester Dragstedt did vagotomy for peptic ulcer.

Allen Oldfather Whipple (1881–1963) **(Fig. 1-16)** did successful pancreaticoduodenectomy for pancreatic cancer in 1935.

Franke in 1900 did total pancreatectomy.

Wendell did first successful hepatic resection in 1911.

Lembert (1826, France) started inverting seromuscular sutures.

Edoardo Bassini (1844–1924) started classical Bassini's repair for inguinal hernia in 1884 as tissue repair which dominated hernia treatment for nearly a century; but now becoming surgical legacy **(Fig. 1-17)**.

Fig. 1-16: Allen Oldfather Whipple.



Fig. 1-17: Edoardo Bassini. He did lot of work in hernia surgery. Tissue repair for inguinal hernias under his name ruled the system for a century and now slowly becoming surgical legacy.

Theodor Kocher (Berne; Switzerland, August 25, 1841–1917) He was the *first surgeon to get Nobel Prize* (1909) (Fig. 1-18).

He did extensive work on thyroid surgeries and designed present technique of thyroid surgeries. He was from Switzerland. He first did excision of thyroid in 1876. By 2012 he did more than 2000 thyroidectomies with eventual mortality rate as 0.18%. He has written Kocher's Textbook of Operative Surgery in 1892. Many surgical avenues are after his name—Kocher's vein; Kocher's forceps (has got tooth in the tip); Kocherisation (duodenal mobilisation); Kocher's incision (Right subcostal for open cholecystectomy); Kocher's thyroidectomy incision; Kocher's test; Kocher's method for reduction of shoulder dislocation; Kocher's arched incision for opening the knee joint; Kocher's method of fixation of uterus; Kocher's invagination technique for inguinal hernia; Kocher's eye sign of thyrotoxicosis (on starring accentuation of lid retraction); Kocher-Debre Semelaigne syndrome (myxoedema, generalized muscle hypertrophy, cretinism, short stature); Kocher Lorenz elbow fracture (osteochondral fracture of capitellum). He did experimental works on gunshot injuries. Theodor Kocher Institute, Kochergasse, Kocher Park, are his memories in the city of Berne.



Fig. 1-18: Theodor Kocher.

Harvey Cushing, Halsted's resident, started the practice of experimental surgery. He was interested in the field of neurosurgery. He started and showed the essentiality of electrocoagulation in neurosurgery.

John H Gibbon (1903–1973) **(Fig. 1-19)** developed extracorporeal circulation for cardiac surgery.



Fig. 1-19: John H Gibbon.

Alfred Blalock (1889–1964) **(Fig. 1-20)** was a pioneer in cardiac surgery. He discovered successful surgical therapy for Fallot's tetralogy.

Fig. 1-20: Alfred Blalock.

Owen H Wangensteen, a very popular surgical teacher pioneered in colonic surgery **(Fig. 1-21)**.



Fig. 1-21: Owen H Wangensteen.

Francis D Moore (Fig. 1-22) gave importance of metabolism in surgery.

Jonathan Rhoads (Fig. 1-23) did extensive work on surgical nutrition and surgical oncology.

Charles Huggins (Chicago) **(Fig. 1-24)** got Nobel Prize for effects of hormones on tumour growth and use of orchidectomy in advanced carcinoma prostate.



Fig. 1-22: Francis D Moore.



Fig. 1-23: Jonathan Rhoads.



Fig. 1-24: Charles Huggins.

Alexis Carrel (1873–1944) **(Fig. 1-25)** got Nobel Prize in 1912 for his work on vascular anastomosis.

Christian Bernard pioneered in heart transplantation. He did first successful heart transplantation in 1967.

Ullmann in Vienna did first kidney transplantation (1902).



Fig. 1-25: Alexis Carrel.



Fig. 1-26: Michael D Bakey. He did extensive work on vascular surgery and aneurysms.

George Kelling (Dresdon, 1901) did first laparoscopy using cystoscope in dog and called as celioscopy. Hans Christian started it in humans. Zollikofer (1924) brought CO_2 for pneumoperitoneum. *Kalk* is father of laparoscopy surgery. Janos Verres (Hungary 1938) used spring needle to create pneumoperitoneum. Fourestier, Gladu and Valmiere used cold light fiberglass illumination (France, 1952). Kurt Semm (German, 1977) used automatic insufflation device.

Semm in 1983 did first successful *laparoscopic appendicectomy*.

Mouret P did first *laparoscopic cholecystectomy* in France in 1987.

Surgeons who got Nobel prize are Theodor Kocher (1909); Alexis Carrel (for his work on vascular anastomosis–1912), Charles Huggins (urologist and oncologist for management of carcinoma prostate and hormone therapy–1966); Joseph Murray (organ transplantation–1990).

ETHICS IN SURGERY

Ethical principles are important. Finalising the accurate diagnosis or possibilities, recommending the treatment, explaining the merits and demerits of different procedures or recommended procedure, risks, complications should be explained to the patient.

Community values, its basic knowledge is essential to a surgeon in influencing the patient about the illness. In many countries, states and communities, relatives of a patient do not want to inform the patient about the major disease like cancer or life threatening illness. Here decision making is done by close relative of the patient like son/father/mother/brother/sister. The so called *truth telling* to the patient is purposely avoided to maintain the will power of the patient or details about the illness is informed to the patient gradually so that the patient is made to understand and accept the reality of the situation. It is always better to explain the patient that in many diseases, it is only possible to *give adequate care* but not complete cure.

Resources; individual identity of the patient; education of the patient; help of relatives; patient's ability to understand; planning are the important factors needed. Often it is better to reveal the details of the disease in presence of two attendees/relatives/caregivers. In the court of law/*legally* it is better to take signature of the witness for informed consent with date. Surgeon should have a registered *legally permissible recognised degree* certificate to perform different operations

Behavior of the surgeon with the patient, relatives of the patient, hospital staff, theatre staff, residents, students and colleagues should be proper. Shouting, abusing, manhandling should be avoided as much as possible even under stress.

Avoid negligence like retaining of mops during surgery, not giving adequate postoperative care, etc. Negligence is not accepted in court of law. In difficult situations surgeons should not hesitate to take the help of another surgeon. Reasonable care is essential. Act of omission or act of commission both are considered in negligence.

Documenting in detail about the surgery in case sheets, daily follow up, progress with timings, informed consent are important. It is better every surgeon should have a clear idea about legal aspects of his practice. It is also better to have a legal advisor to clarify the doubts whenever needed.

It should always be remembered that surgeon is basically a part of the *public life*. He should respect the dignity of patient and caregivers; psychological, social and spiritual aspect of the patient should be considered; refrain from committing crimes; competence, compassion should be present; should educate the patient and community; teach the *future learners* of surgical profession with love and interest. One should *never* bring cast, community, religion, race during practice. *Only human life* and humanity should be goal.

Oaths used in medical field are Hippocratic oath; Sushruta and Charaka oath of India; declaration of Geneva.

Medical Ethics

Medical ethics is a system of principles governing medical conduct. (1) Doctor-patient relationship is moral trust between two. Doctor is considered as close to God in India. (2) Professional confidence and secret about the patient is important. (3) Ethical practice is a must from the surgeon. Unethical practices are—advertising; selling medications; accepting gifts, commissions, bonus etc; unnecessary criticising professional colleagues; conflicts of interests. (4) In dealing with medical insurance. (5) In undertaking newer innovative techniques. (6) Ethics in blood transfusions: Permission should be sought before blood transfusions. Jehovah's witnesses are people with special faith as they never accept blood transfusions which is said to be against their eternal life. Care should be used in managing critical patient of such faiths. (7) Doctor should not refuse treatment and care based on certain diseases like–HIV infection. (8) Risk and benefits of surgery should be weighed before deciding the procedure. (9) Following proper legal backgrounds in organ transplantation–The transplantation of human organ act 1994. (10) Information about need for use of ventilator, duration, chances, risks, when to discontinue the ventilator need should be discussed with patient's close relative properly with informed consent. (11) Avoiding **medical negligence**–One should remember that anything that goes wrong is not negligence. *Reasonable standard of care and skill* is needed in treating the patient. Breach of duty by the doctor/surgeon to achieve standard care and skill is called as negligence. If there is damage, then only patient is allowed to claim the negligence. Without damage, patient cannot claim the negligence. General and special damages can be claimed by the patient as financial compensation. Act of commission or act of omission–both are considered in negligence. Surgeon is responsible for negligence of nurses, assistants, theatre staffs or technicians.

Res Ipsa Loquitur is obvious negligence–'thing speaks for itself' like retaining mop/gauze. Contributory negligence is due to act of omission.

Usually **section 304 A** is filed which is a bailable warrant in court of law with summons to the surgeon as accused. Expert witnesses and other documents like case sheets, medicine bills, and certificates are used in examination and cross examination.

Consumer Protection Act (1986) deals medical negligence cases. It is basically based on documents and affidavits provided by the patient and the doctors.

Often surgeons can be called as **expert witness** in the court of law. He should act fair and accurate without siding anybody. He should have enough proofs and evidences of standard books or journals about what he is telling and documenting in the court. He should be prepared prior about his witness role.

Consent

Permission granted by the patient to the surgeon to make a diagnostic or therapeutic intervention or to have therapy is called as **consent.**

Informed consent is more valid. All relevant information should be provided about benefits, risks of the procedure, present condition in acute cases, need for repeat procedures, intensive care, approximate expenses, probable period of hospital stay, etc. Abiding patient from taking the decision is not correct. *Prevailing silence* between doctors and patients is not right in present day of modern practice. During rounds patient or relative of the patient should be informed about the progress, response or any complications every time. It is always better to explain the patient about the illness in patient's own language.

Valid consent–Operating surgeon himself should obtain the consent; patient should understand the discussion/details given to give informed consent; patient must be free from coercion to give consent; details about the procedure, risks, benefits, complications of the procedure; patient should be allowed to query his/her doubts or to clarify his/her suspicions. Person giving consent should be above 18 years, conscious and mentally alert. Parents should give consent if patient is below 18 years. In handicapped or mentally retarded patients, parents or guardians can give consent. In an *emergency condition or in unconscious patient*, procedure and treatment can be done without consent even in the absence of any relative, but after informing and taking written permission from the hospital authority.

Patient presenting himself in surgeon's clinic itself is consent for examining–**implied consent**. When patient cannot give consent, consent taken from close relative is called as **substituted consent**. Consent taken for one procedure can be considered as consent for additional inevitable essential procedure (decided during initial procedure) and is called as *extension doctrine*.

Chapter

2

Preoperative Preparation, Operation Room, Postoperative Care

Operations may be *elective* wherein patient is properly prepared with all investigations and precautions or *emergency* wherein immediate surgery is required to save the life of the patient like perforation of bowel, haemorrhage and trauma.

Patient is admitted prior to date of the elective surgery. In young individual it is sufficient to admit the patient on the day of surgery, provided evaluation is done earlier on out patient basis. If patient is elderly or asthmatic or with systemic problems, it is better to admit him earlier and manage the systemic problems with the help of physicians, cardiologists and anaesthetists. Patient is evaluated with essential investigations like haemogram, urine analysis, ECG, blood electrolytes, chest X-ray, echocardiography, physician and cardiologist's opinion taken and required treatment given. If patient is anaemic prior to surgery, blood transfusion is required. Asthma, respiratory diseases, diabetes has to be managed properly. Electrolyte supplement prior to surgery is required

Prior to shifting the patient to operation theatre following rules should be followed:

- Correct identification of the patient–identification tag is a must.
- Consent for the surgery should be taken.
- Preparation of the patient according to the requirement. Present concept is preparation should be done just before surgery on the operation theatre table, even though what usually followed is preparation in the ward often on previous night which is convenient rather than a right way.
- Nothing should be given orally 6-8 hours before surgery.
- Bladder should be empty before sending patient to the theatre. If required the patient is catheterised.
- Enema, as by instruction should be given.
- Ornaments, dentures, nail polish, hearing aids; contact lenses should be removed before shifting the patient.
- The patient must wear head cover, feet covers, theatre dress.
- Pre-medication, as per instruction should be given.
- Ward nurse should accompany the patient to theatre and should hand over the patient to theatre nurse.

PREOPERATIVE ASSESSMENT

History

1. Chronic cough, smoking, alcohol, drug intake, drug allergy.
2. Any previous diseases like hypertension, diabetes mellitus, epilepsy, bronchial asthma, tuberculosis, hepatitis, cardiac diseases, bleeding disorders and renal diseases.
3. Drug therapy: Steroids, antihypertensives, sedatives, antibiotics, antiepileptics.
4. History relevant to different systems–cardiovascular; renal; hepatic; thyroid disease; endocrinal like adrenal; metabolic; nutritional.
5. History suggestive of fluid loss like diarrhoea, vomiting; obstruction; burns; haemorrhage; trauma.
6. Past history of surgery, its detail and if possible one should collect the old records.
7. History suggestive of coagulation disorders like haemophilia, anticoagulant therapy.

Patient with history of recent myocardial infarction should avoid surgery for six months unless it is an emergency. Patients with valvular heart disease/on prosthesis need prophylactic antibiotic. Patient with coagulative diseases need specific corrections as needed prior to surgery.

Examination

General: Posture, teeth, mouth opening, dilated veins, neck movements, tremor, airway, anaemia, oedema, jaundice and cyanosis.

Respiratory system: To look for asthma, tuberculosis, emphysema, COPD.

Airway: Mouth opening, Malampatti scoring, tyromental distance, temporomandibular joint assessment.

Cardiovascular system: Hypertension, ischaemic heart disease, arrhythmias, cardiac failure, valvular diseases.

Spine: Curvature, intervertebral space**,** skin over the back for any infection.

Other systems: Abdomen, skeletal system.

Preoperative Investigations

Haematocrit, blood sugar, blood urea, serum creatinine, electrolytes, chest-X ray, ECG, blood grouping, blood-gas analysis, cardiac assessment.

Prothrombin time, bleeding time, clotting time, platelet count, liver function tests, pulmonary function tests, arterial blood gas assessment, serum calcium, T3, T4, TSH—in specific surgical diseases.

Different imaging methods for confirming the diagnosis.

Preoperative Care and Treatment

Control of respiratory and cardiac diseases taking special care from cardiologists, chest therapists, and respiratory physiotherapist. Smoking should be stopped (at least 15 days prior to surgery, but ideally one month prior to elective surgery); prophylactic antibiotics; bronchodilators; steroid inhalers are given. Asthmatic patients are often on steroid therapy and may need intravenous hydrocortisone prior to surgery.

- Renal assessment with blood urea, serum creatinine, urine analysis (albumin, specific gravity) and serum electrolytes is done. In compromised kidney function, nephrologist's opinion and therapy is asked for. Adequate hydration, catheterisation in major surgery for hourly urine output monitoring, avoidance of nephrotoxic drugs in patients with renal failure are the steps to be remembered.
- Improvement of haemoglobin status, if anaemia is present. Minimum haemoglobin *ideally* needed for elective surgery is 10 gm%. (*Safer zone* for anaesthesia tolerance is 7 gm% haemoglobin). Nutrition should be adequate. Proper protein diet in elective surgery is good. In emergency situation, parenteral nutrition is given.
- Preoperative antibiotics are given as per instructions of the surgeon. It is used only if there is existing infection like abscess, skin infection or in peritonitis. In elective cases perioperative antibiotics are given like in inguinal hernia mesh repair.
- Blood should be kept ready for major surgeries for transfusion.
- Control of diabetes mellitus and cardiac diseases is important. It is better to take physician's help/cardiologist's opinion prior to surgery. An echocardiography or treadmill test is better for cardiac evaluation. On the day of surgery (two hours prior to surgery) fasting sugar should be checked. Urine sugar, urine *ketone bodies* and *serum potassium* estimation are relevant in diabetic patients. It is better to start on insulin therapy if the patient is on oral hypoglycaemic drugs prior to surgery. Often intravenous infusion of 5 units plain insulin in 5% dextrose and 5 mEq of potassium chloride at rate of 50 ml/hour are needed. Hourly blood sugar and serum potassium estimation is needed to maintain blood sugar level at 100- 180 mg% and potassium level at 4 -5 mEq/ml.
- **All smokers should be asked to stop smoking ideally** *four weeks prior to surgery* in elective surgeries even though patient may not follow the instruction.
- Any preoperative fluid deficits should be corrected with proper monitoring. Monitoring is done using estimation of *hourly urine output*, electrolyte estimation. Usually normal saline or ringer lactate is used.
- Purgatives/enema are given prior to surgery as sphincter relaxation occurs during general anaesthesia or spinal anaesthesia.
- Skin preparation is done by shaving the area, or by using depilation creams. Ideally it should be done just prior to surgery *in the operation theatre* using clippers. Patient should take proper bath prior to surgery.
- Patient should be kept nil oral for 8 hours (In children upto 4 hours prior liquid can be given for short duration procedures). Fasting prior to surgery is essential to prevent life threatening aspiration. In emergency surgical situations (like in trauma), nasogastric tube is passed to remove the gastric content; prokinetic drugs are given to rapid the gastric emptying; drugs which decrease the pH of the stomach and to decrease the gastric secretions are given.
- *Prophylactic antibiotics* are given in cardiac surgeries, prosthetic surgeries, trauma, gastrointestinal surgeries, gynaecological surgeries, and oral cavity surgeries. Overuse of antibiotics should be avoided due to development of resistance. Based on their features, wounds should be classified as clean, clean contaminated, contaminated and dirty infected. Clean wound has got less than 2% infection rate whereas dirty infected wound has got 30% infection rate. Common bacteria contaminating the surgical wounds are *Staphylococcus aureus, Staphylococcus epidermidis* and Gram negative organisms. Prophylactic antibiotics are given on the operation theatre table at the time of induction of anaesthesia. Further doses may be given during surgical procedure if operation time is more than 4 hours. Usually low toxic antibiotics like 2nd generation cephalosporins and metronidazole are given. Concept of antibiotics in contaminated dirty wounds, severe cellulitis, abscess, sepsis, peritonitis is different where patient is prone for septicaemia and its life threatening problems. Therefore higher dose of higher generation antibiotics should be used without any hesitation. Sepsis is more common in AIDS or immunosuppressed patient.
- Hyper/hypothyroidism both are equally dangerous for any surgery. Both should be corrected prior to surgery. Toxicity is controlled by proper antithyroid drugs. Hypothyroidism is corrected by oral L thyroxin once a day daily morning. Toxicity if not controlled may precipitate toxic crisis which has got very high mortality.
- Patients with long term steroid therapy for any cause should have injection hydrocortisone intravenously 100 mg 6th hourly prior to surgery, at the time of induction of anaesthesia and later 6th hourly for two days of postoperative period which gradually reduced and withdrawn.
- Special preparations for gastric/colonic or biliary surgeries should be done.
  – *Colonic preparation*—low residue diet for 72 hours; bowel wash with saline; gut irrigation using oral polyethylene glycol with electrolytes taken in two litres of water in 2 hours to clear the entire bowel. It acts by osmotic hygroscopic action. It is also achieved by oral intake of mannitol for 2-3 days. Bowel antiseptics like neomycin 1 gram three times/day prior to surgery is given. *Total gut irrigation* is done by passing nasogastric tube through which normal saline is infused. It is infused (8 litres of saline) until clear saline is passed per anum. [*On-table colonic lavage* can be done by passing a tube through performed appendicectomy opening (purse string suture is placed) and another opening in distal colon just proximal to obstruction and saline is irrigated from first to second tube continuously to achieve proper cleaning of the colon].
  – *Gastric preparation in gastric outlet obstruction*–Patient is having hypokalaemia, hyponatraemia, hypomagnesaemia, hypochloraemia, hypocalcaemia with metabolic alkalosis and *paradoxical aciduria*. Correction of dehydration, electrolytes, anaemia (blood), hypoproteinaemia (amino acids, total parenteral nutrition), hypocalcaemia (intravenous calcium gluconate) and alkalosis is essential in these patients. Gastric lavage is done for 5 days prior to surgery by passing stomach (Ewald's) tube using normal saline to remove residual food, to decrease mucosal oedema, to maintain gastric tone.
  – *In obstructive jaundice*–specific problems are altered prothrombin time (bleeding tendency), hypoalbuminaemia and malnutrition, sepsis, anaemia, dehydration and diminished carbohydrate reserve. *Hepatorenal syndrome* is specific problem postoperatively–due to endotoxaemia, acute tubular necrosis due to toxins, sludging of bile salts in the renal tubules, hypovolaemia. Management is by–adequate fluid infusion

(*hydration*), fresh frozen plasma; mannitol infusion; antibiotics; injection vitamin K 10 mg intramuscular once a day for 5 days; intravenous dextrose to improve the carbohydrate reserve. Albumin infusion is usually *not needed* in these patients.

Note: Informed consent is absolute need.

OPERATIVE RISK ASSESSMENT

It is important in children, old age; obesity; liver, renal, respiratory and cardiac dysfunctions; sepsis; chronic illness; malignancy. If patient is undergoing surgery for some other disease like hernia which may be elective, here *risk due to concomitant disease* like of cardiac or respiratory or renal problems is important.

If patient is undergoing surgery for surgical problem like perforated appendicitis or acute gallbladder disease like empyema gallbladder or peritonitis, *here risk is of primary disease* (appendicitis/empyema gallbladder) due to sepsis.

Premedication

It is given one hour before surgery.

For sedation and relief of anxiety— Pethidine 50 mg/ morphine 10 mg/ diazepam 10 mg. Midazolam 1-2.5 mg.

To suppress vagal activity— Atropine 0.6 mg. IM.

To reduce vomiting—Promethazine (phenergan) 12.5 mg.

ASA (American Association of Anesthesiologists) grading of the patient for surgery:

1. Normal individual.
2. Mild–moderate one systemic disease under control - Diabetes and hypertension under control; mild obesity, alcohol intake, smoking.
3. Severe systemic disease/multiple systemic diseases–uncontrolled diabetes and hypertension; activity limited due to disease.
4. Incapacitating systemic disease–high risk.
5. Moribund status–imminent risk of life–surgery as life saving procedure.
6. Brain dead patient.

Class ‘ E’ is added to each type if it is an Emergency surgery.

OPERATION THEATRE

Asepsis

Asepsis means organisms are prevented to access the patient or individual.

Sterilisation

It is freeing an article from pathogens by removing or killing all bacteria, spores, fungi and viruses.

Disinfection

It is killing of all bacteria, fungi and viruses but not spores.

Antisepsis

Antisepsis is inhibition of growth of microorganisms.

Different Methods of Disinfection

a. Physical Agents:

Burning or incineration is used to disinfect contaminated articles like dressings.

Hot-air oven: Here temperature used is 160 to 180 degrees for one hour.

Boiling: It kills bacteria but not spores and viruses. Temperature is between 90 to 99 degrees. It is used to disinfect syringes, utensils. It is not useful for gloves, rubber materials.

Autoclave: It is sterilisation using steam under pressure. Temperature attained is between 120-135 degrees. It is sterilised for 20 minutes with 15 pounds/sq.inch (2 kg per square cm) pressure. It kills all organisms including spores. Completeness of sterilisation is confirmed by using specific gelatin protein which precipitates only in steam under pressure for 20 minutes. Green coloured strip turns black if autoclave is complete (*The Bowie-Dick test) (signaloc)*. Surgical gloves, linen, cotton, paper, bottles, plastics, dressings, surgical instruments are sterilized by this method. Sharp and plastic instruments cannot be sterilized by this method. *Bacillus thermophillus* spores are used to assess the completeness of the sterilisation in mass scale. Double autoclaving is done for instruments of orthopaedic or ophthalmic surgeries. Modern rapid autoclaves can sterilise in 3 minutes with 143 degree temperature or in 10 minutes at 121 degree temperature **(Fig. 2-1)**.



Fig. 2-1: Autoclave machine used for sterilisation.

Radiation:

- *Ionising type of radiation:* Atomic gamma radiation is used for commercial purpose to sterilise suture materials, disposable materials in packets. It is viable, safe and cheaper. All disposable materials like gloves, tubes are sterilized by this method.
- *Non-ionising radiation,* either infra-red radiation or ultra-violet radiation is used to reduce the bacteria in air, water. Bacteria and virus are vulnerable to ultra-violet rays below 3000A°. Exposure to eyes and skin can cause burn injury.

Materials	*Methods of sterilisation*
All theatre appliances	Autoclave
Sharp instruments (scissors, needles, blades), plastic materials	Glutaraldehyde 2 %, Lysol
Endoscopes	Glutaraldehyde
Rubber equipments	Glutaraldehyde
Syringes	Autoclave, hot air oven, gamma radiation
Heart-lung machine	Ethylene oxide
Disposable articles	Gamma radiation
Operation theatre and rooms	Ideally by U-V radiation or by formaldehyde
Sera and biological materials	Filtration
Lab glassware	Hot-air oven
Ward, sick room, furniture	Formaldehyde, iodophor spray, glutaraldehyde
Clothes, bed sheets especially for burns patients	Autoclaving
Soiled dressings, materials, animal carcasses	Incineration, Lysol, iodophors
Excreta	Lysol, iodophors
Cleaning of skin before surgery	Iodophors 2%, savlon and spirit
For cleaning infected wounds	Iodophors, acriflavine, savlon, H_2O_2
To remove slough from the wounds	EUSOL, H_2O_2
Before injection	Spirit is used to clean the skin
Cleaning the ward	Phenol, cresol, Lysol
Hand wash	Chloroxylenol, savlon, spirit, iodophors
Bladder wash	0.1 % potassium permanganate solution (Condy's lotion), solution of acetic acid and silver nitrate
Water	Chlorination, potassium permanganate
Fruits, vegetables	Potassium permanganate

b. Chemical Agents:

Phenol: It is used as standard to compare the efficacy of other agents.

Cresol is more powerful and nontoxic. 5% solution is used.

Lysol is emulsified cresol with soap. 2% solution is effective.

Chlorhexidine (hibitane) is useful antiseptic.

Hexachlorophane: It is not used in infants and children because it can get absorbed through intact skin in this age group causing severe neurotoxicity.

Dettol (chloroxylenol) 5% solution is used.

Cetrimide is cationic surfactant (cetavlon). 2% solution is used.

Savlon is combination of cetrimide and hibitane. It is very commonly used antiseptic in operation theatres and wards.

Halogens:

- Bleaching powder.
- Sodium hypochlorite.
- *EUSOL: Edinburgh University Solution* contains sodium hypochlorite, boric acid and calcium hydroxide.

Eusol bath is dipping the ulcer bearing part in dilute eusol solution for 30 minutes 2-3 times a day.

- Iodine.
- *Iodophors:* These are antiseptics and also sporicidals. They are non-irritant and do not stain skin. *Povidone-iodine* is a good example, which is commonly used.

Alcohols: Ethyl or isopropyl alcohols are used.

Formaldehyde: It is useful to disinfect the rooms like operation theatre. It is effective at a high temperature and humidity of 80-90%. It is commonly used to fumigate the room. 500 ml of formalin with one liter of water is boiled to get formaldehyde vapour. Adding potassium permanganate to the same solution can create formaldehyde vapour. Room is kept closed for 12 hours.

Glutaraldehyde (cidex 2%): It is used to sterilise sharp instruments. Instruments should be dipped for 10 hours to achieve complete sterilisation. It is potent bactericide, sporicide, fungicide and viricide.

Hydrogen peroxide (H_2O_2): It is used as topical oxygen therapy. Because of its effervescence and release of nascent oxygen it removes the tissue debris. It is used to clean wounds, cavities, ulcers and as mouth wash, as ear drops to clear earwax.

Acriflavine and proflavine are orange-red coloured dyes used as antiseptics. It is effective against gram positive and few gram negative organisms. It retains its activity in pus and body fluids.

Ethylene oxide sterilisation (ETO): Here instrument is packed in a sealed plastic cover. It is kept in the ethylene oxide steriliser. Total 12 hours sterilisation is needed. 6 hours for gas sterilisation and another 6 hours for gas to come out. It is good way of sterilization. Once instrument is sterilized, it can be kept and used for 6 months. Problem is cost factor, time duration needed (minimum 12 hours) for sterilisation **(Figs 2-2A and B)**.



Figs 2-2A and B: Ethylene oxide steriliser.

OPERATION THEATRE ROOM

Operation theatre is like a temple to all surgeons.

Theatre Plan

Every operation theatre should have a waiting area, entrance, surgeon's changing and relaxing room, separate changing room and relaxing room for nurses, autoclave and sterilisation room, OT scrub area, all sets of instruments, instruments for anaesthesia, adequate number of racks, toilets, air–conditioned ventilator, OT tables, trolleys to shift patients, OT laundry, good light, ultrasound machine, C-ARM image intensifier.

Operation theatre should have an adjoining post-operative ward. This ward should be close to the OT, easily accessible (surgeon and anaesthetist should able to rush to the postoperative ward in short period without changing their OT dress).

In many theatres light music is played to calm the patient just before inducing anaesthesia.

It should be easy to clean floor, roof and walls. An individual unit for instrument cleaning, washing, and arranging should be present where the instruments are kept ready, packed and autoclaved as directed.

A separate room for pathologists with facilities for frozen section and relaxing should be present.

Principles of an Operation Theatre

- An air-conditioning is a must to have a filtered continuous flow of air.
- Doors and windows should be kept closed as much as possible.
- Ward nurse should hand over the patient to theatre nurse with all details, case sheets, tag, side of surgery, blood to be transfused, and pre-medication details. While shifting the patient ward nurse must take care of the air way and IV line of the patient, must keep tongue depressor, swabs, airway in the trolley.
- Patient should be shifted to theatre always in a trolley. Patient should remove all ornaments and wear theatre gowns, cap, and feet covers.
- Patient must be transferred from ward trolley to theatre trolley, which should have modern accessories like oxygen, side guards, drip stand, oxygen masks, pulse oximeter placing area, tiltable couch.
- Patient's trolley and ward blankets should not be taken inside the operation theatre.
- Initially patient should be kept in preoperative room and later should be shifted to theatre. Anaesthetist and surgeon and also theatre nurse should accompany the patient. .
- Theatre nurse should confirm the consent form, case sheets, site and side of the surgery etc.
- Separate theatre shoes should be worn by surgeons, anaesthetists, theatre nurses and assistants.
- Unnecessary movements, speaking loudly, laughing, should be avoided as patient inside the theatre may be awake especially when spinal anaesthesia is given.
- All persons entering the theatre should wear theatre dress (pant and shirt), cap, mask, footwear or shoes (shoes are ideal). Material for dress should be smooth, non-woven fabric, which is easily boilable. Cap should cover and conceal hair fully.
- Clothes, dresses should be washed, cleaned, ironed and kept ready every day. Fresh, clean cotton blanket should be used for the patient in theatre.
- Ideally all mobile phones should be switched off inside the theatre.
- Any public person or relative of the patient should not be allowed inside the theatre. Selected people may be allowed only by prior permission from medical director of the hospital and from operating surgeon.
- One ***senior nurse*** is made in charge of all activities in the theatre like shifting patients, arranging theatre tables, autoclave and other sterilisation methods, cleaning the instruments, packing the instruments for autoclave. She decides the duties of her junior nurses and makes a list of nurses for that day surgical scrubbing. ***Operation theatre assistant and technicians*** are also under her supervision and should follow her instructions strictly. She should be answerable for any default and problems in the theatre occurred or created by her fellow nurses and theatre boys.
- ***Scrub nurse*** is the one, who washes to assist the surgeon, arranges the instrument table and gives instruments to surgeon during procedure. She should be well aware of the steps of surgery and instruments required. She should be alert, quick, and understandable
- One nurse in each theatre works as a ***circulating nurse*** who provides additional instruments required during surgical procedure. She also takes care of the counting of the surgical mops and swabs used. Used mops or swabs should be kept hanging in mop rack or swab rack which should be visible to the operating team. Name, procedure and number of mops collected and used should be written on a blackboard. Scrub nurse and circulating nurse are fully in charge and responsible for swab counts. *She also will be legally questioned and penalized along with the surgeon if there is negligence in mop count.*
- Theatre nurse and OT assistant should accompany the patient while handing over to postoperative nurse from OT.
- Patient should be shifted outside the OT once anaesthetist confirms the fitness for shift. It is the anaesthetist who decides when to shift, how to shift and how long the patient should be in postoperative ward.

Modes of infection and sepsis in OT

- Patient's skin
- Surgeon, nurses and OT technicians, by unclean hands, nostrils, throat, skin
- Contamination of OT floor and wall
- Improper sterilisation
- Poor handling of instruments
- Poor packing and poor storage of instruments
- Theatre clothes, footwear and shoes
- Not disinfecting the OT properly and adequately after using the OT for infected cases.

Scrubbing and Wearing of OT Gown and Glove

Both hands, forearms up to elbow joints should be rinsed with running water and soap. Any ring, jewellery, wristwatch should be removed prior to the scrub. Using brush and soap, finger nails, hands on both sides are cleaned. Then forearm is brushed and washed. Procedure is repeated three times (presently whether need to brush the hands are *controversial*). After thorough rinsing the hands by running water, hands are washed with antiseptic solution and then with warm water. Once fully scrubbed, she/he should not touch with hands any objects or his/her own face or parts of body. She should keep her hands and fingers tucked with each other with forearm and hands outstretched. Using a sterile towel, forearm and hands are dried up. Both hands are inserted into the armholes of the sterile gown. The gown is not touched or pulled but both arms are kept outstretched. Circulating nurse will pull back the tapes of the gown and ties it over the back.

A *back wrap gown* has got two tapes to tie on the front aspect. After wearing gloves, one tape is given to the scrub nurse/surgeon who has already with gown and gloves (**Figs 2-3 and 2-4**). She/he will encircle the gown round and bring it in front and give to the surgeon to tie it with other tape.

Circulating Nurse

One who supplies all additional instruments and mops. She also keeps the mop counts.



Fig. 2-3: Figure showing the correct method of wearing gloves.

Theatre technique of wearing gloves

- After using glove powder, with the bare hand inner aspect of the cuff of the glove is held. It is pulled over the hand. It should not be wrapped over the wrist cuff of the gown at this stage.
- Fingers of this gloved hand should hold the cuff of the other glove from outside and it is slided over the fingers and hand.
- Now cuff of the glove is pulled proximally over the wrist of the gown using other gloved fingers.

Duties of Circulating Nurse

- Keeping counts of instruments, and mops given to scrub nurse. Instruments are kept in bundles of five, ten and so on. So counting will be easier.
- Taking care of swab rack, collecting the used mops from scrub nurse and hanging the mops in groups of five. Mops presently used in many theatres are having radio opaque threads and so can be easily identified when needed by taking X-ray or through a C-ARM.
- Collection of specimens, pus, fluids and labeling with name, unit, number. It may be for culture, cytology or for histopathology.
- Keeping account of the disposable instruments and suture materials, drugs and fluids used in each procedure.
- Noting the duration of the surgery, quantity of blood transfused and type of anaesthesia given.
- Documenting in record book or theatre computer.

Theatre nurse should not discuss outside or reveal about the procedure or technique done in theatre with anybody. It is surgeon's duty to explain about the patient's condition, procedure done and problems. She should never comment about anything in theatre (Figs 2-5A to 2-6D).

Septic Operation Theatre

- All infected cases like abscess drainage, amputation for gangrene, slough excision, dressing of large ulcers should be done in a separate OT. Otherwise clean surgeries may get infected. It is especially important when orthopaedic surgeries are going on.
- Entrance to septic OT must be separate from that of main OT.
- Staffs working in septic OT should not enter main OT.



Figs 2-5A and B: OT mop rack to keep used mops during surgery.



Fig. 2-4: Photos showing method of wearing glove.



Figs 2-6A to D: Different materials required to give anaesthesia– (A) airway; (B) Boyle's apparatus; (C) Direct laryngoscope; (D) Laryngeal mask airway (LMA)–a special device tube to give anaesthesia.

- Instruments should be kept separate for septic OT.
- Drapes, towels, mops should be placed in a plastic bag after use and sent to laundry immediately. It should be labeled as *infected.*
- Circulating nurse should wear gloves while working in a septic OT.
- Disinfection of shoes is essential once it is used in septic OT.
- Daily disinfection of OT is essential.
- Swab culture of the OT materials at regular intervals is needed.
- Separate Boyle's apparatus is used in septic OT.
- Dress is changed when one comes out of septic OT and enters the main OT.

Prevention of infection

- Cleaning of the patient's skin where incision is placed by povidone iodine, cetrimide, spirit.
- Isolation of surgical area by proper draping with green towels.
- Transparent sheeting of the skin through which skin incision is placed.
- Adhesive films to the skin.
- Use of on table parenteral antibiotic in major cases.
- Always clean cases are done first and then infected cases.
- Proper sterilisation.
- Double autoclaving for orthopaedic and ophthalmology cases.



Fig. 2-7: Adhesive plastic draping in operation theatre reduces the chances of wound or deeper infection.

Precautions in an Operation Theatre

- In the absence of proper safety measures and precautions, OT is a place where one is prone for accidental trauma and injuries, which may be danger to patient as well as to theatre personnel.
- Main danger exists in some anaesthetic agents, which may cause life-threatening explosions. It may cause burns, loss of vision, hearing loss, damage to OT, may also sometimes cause death. Ether is one, which can be explosive.
- An OT has got high power electric supply for its basic needs like air condition, lights, machines, cautery, suction apparatus, other modern instruments like laparoscope, C- ARM, etc. Because of the presence of too many electric circuits and possibility of dangers of static electricity, theatre staff should take enough precautions to prevent any electric injury to patients and theatre personnel.
- Good earthing is essential.
- It is ideal to use theatre dresses made of cotton (cotton clothes) to patient, surgeon and nurses. Drapes and other materials should also be made of cotton **(Fig. 2-7)**.
- Rubber should be used wherever required like in wheel of trolley, Boyle's apparatus, mattresses, floor, wall of the theatre.
- When cautery is used, electric shock is common and so enough precautions have to be taken. Often cautery burns can occur to the patient.
- An electrician should be immediately available whenever there is problem like power failure, short circuit, and default in any of the electrical instruments.

Beware of possible anaesthetic explosions and electrical injuries in OT.

Most important people in OT

- First and foremost is the ***patient***.
- Next are surgeon and anaesthetist.
- Essential are theatre nurses and theatre assistant.
- Surgery is a team work. All are important.

POSTOPERATIVE CARE

In all major prolonged surgeries, patient is kept in postoperative ward. Postoperative set up is clean, air conditioned, well equipped set up with restricted entries. Rules followed in operation theatre should be followed here also. Postoperative ward should be adjacent to the main operation theatre. It should be equipped with all essential life saving drugs, tubes, ventilators, oxygen supply line, suction devices, and monitors to each bed. One nurse should exclusively attend one patient. An anaesthetist should be in charge of the postoperative ward. Nurse should be well trained, quick, and observant and should able to manage emergency situation. Defibrillator and needful things to manage cardiac arrest should be available in postoperative ward **(Figs 2-8 and 2-9)**.



Fig. 2-8: Infusion pump is used in postoperative period to have a proper control about the infusion of fluids, drugs, etc.



Fig. 2-9: Pulse oximeter. It is usually portable. Different types may be available. One showing just O2 saturation and pulse rate to cardiac waves is available. It is non-invasive, continuous real time device. Amount of light absorbed by a solution is directly proportional to the amount of solute in it. It contains two light emitting diodes–660 nm (for reduced haemoglobin absorption) and 940 nm (for oxyhaemoglobin absorption). Ratio of absorption of these two wavelengths is oxygen saturation. Normal saturation is 98-100%. It is monitored in fingers, toes. Limitations are patient movements, electrical interference, and vasoconstriction, presence of carboxyhaemoglobin or methaemoglobin.



Figs 2-10A and B: Postoperative drain should be taken care of.

Following care should be taken:

- Use of dry bed sheets, clean beds and clothing, waterbeds/air mattresses, change of position, leg exercises, needed positioning which depends on obesity, respiratory reserve, and type of surgery the patient underwent should be taken care of. Oxygen is given through mask or cannula.
- *Proper monitoring* with oxygen saturation, pulse, blood pressure, respiration, and urine output is needed. CVP line is often required for major cases.
- *Drains, tubes* (Nasogastric tube, urinary catheters) should be observed for quantity and colour of the contents. Intercostals tubes, abdominal drains, tubes like T tube, stenting tubes should be taken care of **(Figs 2-10A and B)**. Often if patient is having many tubes in postoperative period it is better to label each tube for better nursing purpose. Nasogastric tube is placed in most of the abdominal surgeries to decompress stomach, to prevent aspiration, and as a therapy for ileus. It is usually kept connected to a bag/bottle allowing continuous flow. Intermittent suction also should be added to clear the stomach at 4th hourly interval. Tube is removed once bowel sounds are heard, patient passes flatus or stool and once total aspiration becomes less than 200 ml per day.
- Surgical cases done under spinal anaesthesia or in case of small procedures, patient can be kept for 3 hours in recovery room for observations before sending to bed. But it is surgeon's discretion to decide how long to keep the patient in postoperative ward. For example, patient who underwent transurethral resection of prostate (TURP) under spinal anaesthesia is usually kept in postoperative ward for minimum of 12 hours to watch for irrigation and bleeding.
- *Postoperative fluid management* should be proper and adequate. It is decided on individual patient depending on type of surgery, on table complications, duration of recovery, respiratory reserve, electrolyte status etc. Fluid need is monitored by hourly urine output and CVP measurement. *Extracellular fluid loss and third space fluid loss* occurs in first postoperative period. *Commonest electrolyte deficit* in postoperative period is *potassium* which usually occurs after 48 hours. Potassium supplement is started when needed, after confirmation by estimation usually at the end of 2nd postoperative day. It is given by *slow infusion* as 1 mEq/Kg body weight. Experienced nurse should give this supplement as bolus push of potassium may cause cardiac arrest. Sodium also commonly gets deranged. It is corrected after estimation, using double strength saline. Calcium and magnesium supplement is also often needed. *Sensible loss of fluid* is obvious loss of fluid by nasogastric tube, drains, urine output; *insensible loss* is due to metabolism, temperature, and hyperventilation. Both should be carefully calculated for adequate fluid therapy.
- *Postoperative assessment chart*—regular recording of blood pressure, pulse, respiration, urine, drain, etc is a must. Postoperative examination of respiratory system for crepitations (pulmonary oedema), of legs for DVT (pain, swelling and tenderness in calf), cardiovascular system and of abdomen is done daily.
- *Postoperative respiratory physiotherapy* is given to remove secretions. Respiratory distress may be due to cough, secretions, pain causing poor diaphragmatic movements, drugs like atropine. Proper pain relief; coughing, removal of secretions, breathing exercises using balloons or spirometer, steam inhalation, saline nebulisation, bronchodilators, mobilisation are encouraged **(Fig. 2-11)**. To prevent DVT leg exercises and early mobilisation are done. It is better to take the help of a physiotherapist for the same.
- Postoperative investigations are done as and when needed based on clinical and monitoring grounds. Haemoglobin %, total count, serum electrolytes, serum creatinine, serum bilirubin are commonly done. In critical patients arterial blood gas analysis,



Fig. 2-11: Flow based incentive spirometer is commonly used as it is light weight and portable. Three chambers has got three balls one in each of different colours. Each registers an air flow of 600/900/1200 cc/second respectively. Volume inapired can be calculated. Rise of the ball in chamber indicates the extent of flow of air. It is used in postoperative lung expansion. It is also used to prevent atelectasis, preoperative improvement of respiratory reserve. Larger device indicating inhaled air volume also in use.

haematocrit, platelet count, prothrombin time are done at regular intervals. Chest X-ray should be done if pneumonia, effusion or ARDS is suspected postoperatively. ECG should be taken when needed.

- *Antibiotics* are continued for 48 hours and stopped. It is continued in infective/septic cases or in septicaemia.
- Diabetes should be managed depending on blood sugar level using insulin. Later it can be changed to oral hypoglycaemic drugs after consultation with physician in charge.
- *Postoperative nutrition*–oral feeding is started in usual surgeries in 6-8 hours once patient is conscious and without any nausea. Initially to start with 50 ml/hour liquid, later semisolid and finally solid normal diet is used. It takes 2 days to have normal diet in surgeries other than gastrointestinal. In abdominal surgery it is delayed until, bowel sounds appear, patient passes flatus and nasogastric tube aspiration becomes less than 200 ml per day. Early oral feeding in abdominal surgery is under trial at present. In gastrointestinal surgery, it takes usually 5 days to start oral feeding. In major gastrointestinal surgeries, intestinal fistulas, total parenteral nutrition is a must (TPN) with all essential elements, otherwise sepsis, wound dehiscence, anastomotic leak can occur.
- *Postoperative pain* relief is essential. If pain is not relieved tachypnoea, tachycardia, pneumonia, atelectasis, hypertension, aggravate cardiac problems. Pain units are there in hospitals to manage pain by analgesics like NSAIDs and tramadol, sedation like morphine and pethidine, epidural analgesia. Often *continuous intravenous infusion* of analgesics is needed. *Patient controlled analgesia* is training patient to self-administer the drug using triggering button which delivers the controlled dose of analgesics. Opioids can cause nausea and vomiting and so antiemetic should be given. NSAIDs can be nephrotoxic especially in elderly and gastric irritant and so patient should be monitored. Antihistamine injection like ranitidine (50 mg intravenously) or injection of proton pump inhibitors should be given along with NSAIDs. Pain reduces in intensity in 48 hours after surgery. If pain persists after 48 hours, it should be evaluated for sepsis, haematoma, ileus, collection, nerve irritation, pneumonia, DVT, etc.
- *Prevention of postoperative DVT* is important. Risk of DVT is 30% in postoperative period. It is more common in orthopaedic surgeries, surgeries for malignancy, in obese patients, in elderly. Risk is categorised as low (age less than 40 years; short time surgery without immobilisation); moderate risk (age more than 40 years; major surgeries; patient taking oral contraceptives); high risk (age above 40 years, cardiac illness, major operation, pelvic surgery, malignancy, prolonged postoperative immobilisation). Prophylactic low dose heparin/low molecular weight heparin can be given on the day of surgery and continued for 5 days post-operatively. Early mobilisation, compression stockings to legs during surgery and postoperative period, leg exercises, pneumatic compression devices are other modalities used. Patient should stop oral contraceptives 4 weeks prior to major surgery.
- *Postoperative fever* is the one surgeon is really worried about. Fever in 24 hours may be due to intravenous fluid, inflammatory response, atelectasis, DVT, inflammation at the site of intravenous cannula, urinary infection. Upto 5 days it may be due to pneumonia, catheter induced infection, cellulitis at infusion site, thrombophlebitis, DVT. After 5 days it may be due to collection at operative site, bacteraemia, septicaemia, pneumonia. Total count, liver function tests, urine analysis, chest X-ray, blood culture, ultrasound of the site like abdomen, occasionally CT scan is needed for proper evaluation to identify the cause of fever. Higher generation antibiotics are needed. Proper monitoring is needed. Anastomotic leak, subphrenic abscess, pelvic abscess has to be thought of. Empyema, late DVT has to be ruled out. Doppler scan of both limbs should be done if suspected. Drainage of pus, re-surgery has to be considered.
- *Surgical wound management* is also important. Clean surgical wound is inspected only after 48 hours. Infected wound should be inspected in 24 hours. Timing of suture removal depends on type of surgery, site of surgery. It is removed usually in 4-5 days in face, in 7–10 days in the abdomen, back, limbs. There may be danger of wound dehiscence in early removal of sutures. Very late removal may cause wound infection. Timing is decided by surgeon on individual basis. Suture is removed with all aseptic precautions. It is removed from deeper part of the knot which is pulled towards the line of incision **(Figs 2-12A and B)**.

A
B
Ulcer
Eusol solution

Figs 2-12A and B: Dressing solutions used in different dressings. Patient dipping his ulcer leg in dilute eusol solution—Eusol bath (Edinburgh University Solution–boric acid, sodium hypochlorite, calcium hydroxide).

SURGICAL COMPLICATIONS

It is said that complications tend to occur in spite of adequate precaution and care in surgical practice. If any surgeon tells that he had zero percent of complications then it is logic that he has not operated at all. But complications can be reduced; often can be prevented by proper preoperative care and preparation. One has to remember that complication is not negligence. Complications during postoperative period is categorised as respiratory, cardiac, renal, hepatic, gastrointestinal, generalised, postoperative fever, deep venous thrombosis and so on.

It is usually classified as (1) ***Intraoperative*** complications. (2) ***Immediate postoperative*** complications. (3) ***Late postoperative*** complications.

Respiratory Complications

It is the *most common* postoperative complication. Precipitating factors are old age, obesity, smoking, asthma, bronchitis, associated cardiac illness, postoperative pain, aspiration. 25 % of postoperative deaths are due to respiratory infection.

Atelectasis

Atelectasis is collapse of basal lung alveoli which can be prevented by respiratory physiotherapy, control of pain, effective coughing. It is the most common postoperative respiratory complication. Narcotics, anaesthetic agents, abdominal/thoracic wound pain cause pulmonary shunt development eventually leads into atelectasis, pneumonia, respiratory failure, etc. It is common in smokers, and obese individuals. Pneumonia can develop eventually in these patients. Deep breathing, proper coughing, usage of spirometer, respiratory physiotherapy are the important ways to treat and prevent it.

Aspiration

Aspiration *i*s common in postoperative period causing collapse of lung, bronchopneumonia–***Mendelson's syndrome***. Large quantity of aspiration can cause complete blockage of airway and instant death. Often it is due to chemical (acid) induced and severe laryngeal spasm. Immediate ventilation using intubation and ventilator; suction and clearing of airway, bronchoscopy and clearing are the measures needed. *Postoperative pneumonia* is commonly due to nosocomial infection by pseudomonas, klebsiella and enterobacter. Both lung pneumonia/atelectasis may be life threatening and an emergency situation. Prevention of aspiration is important. Keeping the patient nil oral in postoperative period for 12 hours is beneficial. Sideward positioning of the patient; prokinetics, passing nasogastric tube are often needed. Once aspirated sudden laryngeal spasm, sepsis, bronchospasm, respiratory failure may develop. It is treated with antibiotics, immediate bronchoscopy, bronchodilators, and ventilator support. Role of steroid support is *not well* accepted even though commonly practiced.

Pulmonary Oedema

Pulmonary oedema with accumulation of fluid in the alveoli causing hypoxaemia is common postoperative complication. It is due to fluid overload, cardiac cause and acute lung injury due to toxins, sepsis. Pulmonary capillary wedge pressure (PCWP) is ideal to identify it with abnormal chest X-ray. It is treated with restricted fluid, diuresis, and oxygen supplement often with ventilator support.

ARDS (Acute/Adult Respiratory Distress Syndrome)

Acute/Adult Respiratory Distress Syndrome (***ARDS***) is a form of respiratory failure with fluid accumulation in the alveoli, widened/thickened alveoli–capillary space, diffuse inflammatory response in both lungs with PaO_2/FIO_2 ratio less than 200 and PCWP less than 18 mmHg. It is critical entity leading into respiratory failure and death. Patient develops tachypnoea, tachycardia, dyspnoea, cyanosis with coarse crepitations all over the lungs on both sides. Patient will be on respiratory failure with reversal of arterial PaO_2 and $PaCO_2$. *Management*: Patient needs ventilator with initial FIO_2 at 100%; PEEP (positive end expiratory pressure); tidal volume 6-8 ml/Kg; peak pressure at 35 cm of water; $PaCO_2$ is maintained at 40 mmHg; inspiratory/expiratory ratio is at 1:2. Later FIO_2 is weaned to 60%. ARDS is now classified as classical type III respiratory failure. Chest X-ray is useful tool to diagnose. Monitoring of pulmonary capillary wedge pressure (PCWP) is needed. Fluid restriction and diuretics are part of the therapy. Complications of ventilator have to be watched for–dependency, sepsis with resistant bacteria, endotracheal tube blockage. Tracheostomy if needed is *always* better. TPN, enteral nutrition, prevention of thrombocytopenia and bleeding by transfusing FFP or platelets whenever needed is essential. Development of uraemia should also be watched for by assessing the renal functions repeatedly.

Criteria for weaning ventilator are–respiratory rate less than 25/minute; PaO_2 more than 70 mmHg; $PaCO_2$ less than 45 mm Hg; minute ventilation 8 liter/minute; tidal volume 6 ml/Kg; negative inspiratory force is minus 25 cm of H_2O.

Acute lung injury is similar but PaO_2/FIO_2 ratio is less than 300 and PCWP is less than 18 mmHg. It is little less severe than ARDS.

Respiratory Failure

Respiratory failure is defined as a status with arterial partial pressure of oxygen less than 60 mmHg; arterial partial pressure of CO_2 more than 60 mmHg. Aspiration, pneumonia, sepsis, lung injury, transfusion, ARDS, acute lung injury, fat embolism are common causes. There is diminished diffusion across alveolar membrane causing cyanosis and hypoxia. *Type I respiratory failure* is *hypoxic condition* with reduced PaO_2 but normal $PaCO_2$. There is hypoventilation, AV shunts, ventilation perfusion mismatch, and low venous oxygen. *Type II hypercapnic respiratory failure* is reduced PaO_2 with increased $PaCO_2$. There is also increased CO_2 production with widened dead space. *Type III respiratory failure is typical ARDS* with development of hyaline membrane; reduced diffusion; decrease in surfactant; raise in pulmonary arterial pressure; progressive atelectasis; respiratory arrest. Management is similar to ARDS. Monitoring at regular intervals is essential. Tracheostomy may be a life saving need **(Figs 2-13 to 2-15)**.

Other than above measures, nitric oxide inhalation; partial liquid ventilation; fluorocarbon assisted gas exchange; extracorporeal membrane oxygenators are used.

Fat Embolism and Pulmonary Complication

Fat embolism and pulmonary complication occurs after fracture of femur/tibia. Cutaneous petechiae, bilateral respiratory involvement due to small/medium sized emboli; cerebral/retinal/renal problems are the other features. It is treated with ventilator, steroids, and heparin.



Fig. 2-13: On table tracheostomy tube placement.



Fig. 2-14: Synthetic tracheostomy tube–PVC.



Fig. 2-15: Fuller's biflanged tracheostomy tube having outer tube and inner tube. Inner tube is having an opening on the convex surface. Inner tube is longer than outer tube.

Pulmonary Embolism

Pulmonary embolism is often life threatening complication in postoperative period. Its incidence is 30% with death rate 10%. Endothelial damage, stasis, hypercoagulable status are the *risk factors*. Trauma, fractures, major surgery, obesity, old age, post partum period, pregnancy, malignancy, venous catheters, neurologic causes, varicose veins, inherited thrombophilia are *main causes*. Commonest origin is deep venous thrombosis (DVT) in *iliofemoral* region. Pulmonary embolism may be *massive* in 10% of cases blocking pulmonary artery and instant death. *Medium and small emboli* block the lung capillaries at periphery causing infarction. *Presentations are*–pain, swelling, tenderness in the leg; pleuritic chest pain; sudden onset dyspnoea; tachycardia; haemoptysis; inspiratory crackles; loud second heart sound; audible fourth heart sound; tachypnoea. *ECG* shows right bundle branch block, right axis deviation, P wave pulmonale. Chest X-ray may show infarction in lung (*wedge shaped*). Change in arterial blood gas is obvious. Venous duplex US shows evidence of DVT in legs. *Pulmonary CT angiography* even though is *gold standard*, ideal most sensitive investigation; it is not commonly done as it is invasive, not available, needs expertise to do it. *Echocardiography* is noninvasive, can be done bed side, available in most of the centers. It shows hypokinesia and dilatation of right ventricle, paradoxical motion, pulmonary hypertension; but it is not as sensitive as pulmonary angiography. *D-dimer* assay is typical as negative result excludes pulmonary embolism; but positive result will not confirm the diagnosis. D-dimer is degraded product of a cross-linked fibrin blood clot. *Helical CT angiogram* is technically easier, commonly done CT than CT pulmonary angiogram. *V/Q lung scan* is the initial test of choice but it is not available. Echocardiography, helical CT angiogram scan, venous Doppler scan, D-dimer assay are commonly practiced evaluatory methods. *Treatment*–heparin; LMWH; fondaparinux (synthetic pentasaccharide anticoagulant which inhibits factor Xa. *Ultrafractionated heparin* is very useful as a bolus 70 units/Kg followed by 1000 units/hour intravenously with maintaining partial thromboplastin time two times the control. Warfarin, oral anticoagulant 5-10 mg daily is started as an *overlap therapy* with heparin for 2 days before stopping heparin. *Thrombolytic agents* like streptokinase, urokinase, and recombinant tissue plasminogen activator that dissolves the clot rapidly is useful in massive pulmonary embolism. Transcatheter thrombolysis and embolectomy is also useful. IVC filter placement is better method to prevent embolism in high risk groups.

Cardiac Complications

Elective operation in a patient who had myocardial infarction recently should be ideally deferred for 6 months. In an emergency situation such rule can not be applied.

Myocardial Infarction (MI)

Myocardial infarction can develop on table preoperatively which has got high mortality; or in postoperative period. Old age, obesity, patient already with history earlier of ischaemic attacks are more prone to develop MI. In suspected cases repeated cardiac isoenzymes–CPK MB should be done. ECG and echocardiography, immediate call for cardiologist is a must. Often MI is precipitated by surgical stress, shock, haemorrhage, hypovolaemia, hypoxia, electrolyte imbalance and prolonged anaesthesia. Measures taken are–pain relief, oxygen, nebulisation, CVP monitor, avoiding fluid overload, vasopressors, emergency angiogram and angioplasty by balloon or stent.

Postoperative Hypertension

Postoperative hypertension may be due to pain, hypoxia, hypothermia, fluid overload, trauma (head), internal bleeding, and crisis of certain disease like pheochromocytoma. *Hypertensive crisis* in postoperative period is dangerous. There is severe raise in blood pressure (diastolic > 110 mmHg); organ dysfunction; cerebral and subarachnoid haemorrhage; stroke; acute cardiac problems; bleeding from surgical wound site. Sodium nitroprusside, nitroglycerin, labetalol, esmolol, enalaprilat, nicardipine are the different drugs tried. At time 25% of blood pressure is controlled, which then is gradually allowed to become normal. Rapid control may lead into stroke, organ hypoperfusion.

Cardiac Arrest

It is the cessation of the heart. Heart stops contracting. Causes: All causes for shock. Structural causes like coronary artery diseases, myocardial hypertrophy, carditis, cardiomyopathy; conduction problems; valvular heart diseases; hypoperfusion status due to shock of any cause; metabolic causes; sudden reduction in cardiac output due to tension pneumothorax, pulmonary embolism, anaphylaxis, acute blood loss; toxins; drugs. There will be finally *ventricular fibrillation* before leading into cardiac arrest. Profound circulatory failure develops causing typical features.

Features of cardiac arrest

- No palpable pulse–radial/femoral/carotid.
- Heart sounds not heard.
- Cessation of respiration, apnoea — cyanosis occurs.
- Development of unconsciousness with convulsions.
- Pupils start dilating.
- Cessation of bleeding.
- ECG shows asystole/ventricular fibrillation.

Critical period—Once heart and lungs stop, brain death occurs in 3 minutes.

Immediate measures–Cardiopulmonary resuscitation (CPR)

- **Airway** open by head tilt–chin lift; jaw thrust manoeuvre; clean the airway by finger or Heimlich method
- **Breathing**–spontaneous/mouth to mouth/bag and mask
- **Cardiac** compression
- **Drugs** and **Defibrillator**
- **ECG**, **Endotracheal** tube and Monitor

Basic life measures:

- **External cardiac compression (massage)** — Patient is laid flat on a *hard surface (never on soft surface)*. Manual compression is exerted over the lower sternum, using both hands one over other without bending the elbow at a rate of 60 to 70 per minute. Rib cage damage during procedure can very well be ignored. (Heel of right hand is placed over the sternum 5-8 cm above xiphoid process and left hand is placed over it) **(Fig. 2-16)**.



Fig. 2-16: Technique of cardiac massage.

- At the same time, another person should give *mouth to mouth breathing* at a rate of 10-20 per minute after clearing the airway by removing froth, and dentures if present **(Fig. 2-17)**. A bag with mask can be used to ventilate using air or oxygen.
- Endotracheal intubation and ventilator support.



Fig. 2-17: Technique of mouth-to-mouth respiration. Note patient's nose should be held closed with right hand of the doctor/ assistant and with left hand lower jaw should be pushed forward.

Observations to be made are:

- Groin pulse
- Respiration and breath sounds
- Blood pressure
- Pupillary reaction
- ECG activity

Once patient recovers, the cause and sequelae has to be managed properly.

Sequelae are due to hypoxia and circulatory collapse

- Cerebral oedema and permanent brain damage.
- ARDS (Acute/Adult Respiratory Distress Syndrome)
- Renal failure.

Advanced life support

- Intubation, 100% oxygen support.
- Proper venous line ideally central or peripheral as an emergency should be assessed.
- Endotracheal administration of epinephrine/atropine/lignocaine in 10 ml saline is given twice as intravenous dose. Intracardiac drugs are *not used* now.
- **Internal open cardiac massage:** This method is used when cardiac arrest occurs in the operation theatre during surgery, acute tamponade, and acute bilateral pneumothorax. Left side thorax is opened through a *rapid lengthy* incision along 4th or 5th intercostals space. Initially heart with intact pericardium is rhythmically compressed and relaxed using left hand against sternum. Mean time costal cartilages above and below are cut with a knife to have a better exposure. Pericardium is opened in front of the phrenic nerve. Direct cardiac massage is undertaken until heart regains its function and later shifted to ventilatory support and critical care **(Fig. 2-18)**.



Fig. 2-18: Left thoracotomy for open internal cardiac massage.

- **Defibrillation technique:** Jelly is applied to the site of electrodes. One electrode is placed at the base of heart to the right of the sternum, other over the estimated area of the apex of the heart **(Fig. 2-19)**. ***Ensure that nobody is in contact with the patient***. The defibrillator is activated. Ventilation and ECG monitoring is resumed immediately. Defibrillation upto 3 times (200; 300 and 360 Joules) is done.
- Injection of 1:10,000 adrenaline (1 mg IV) and 10% calcium chloride intravenously. It is repeated every 3 minutes. Lignocaine 1.5 mg/Kg IV; repeated every 3 minutes. Procainamide 30 mg/minute up to a total dose of 17 mg/Kg; atropine I mg intravenously.
- Correction of hypoxia, acidosis, hypothermia, hypotension, hypovolaemia, potassium imbalance.
- Sodium bicarbonate 8.4% injection, hydrocortisone injection.
- Analysis of blood gas (PCO_2 and PO_2), and assessment of serum electrolytes at repeated intervals.
- Urinary catheterisation, Ryle‘s tube insertion.
- Monitoring the patient with BP, pulse, respiration, and temperature chart–critical care in ICU.



Fig. 2-19: Defibrillator is used in case of cardiac arrest.

Renal/Urinary Complications

Postoperative Retention of Urine

Twenty percent of postoperative patients develop retention of urine. Perineal, gynaecological, pelvic surgeries are common causes. Surgery done under spinal anaesthesia is also common cause. Wound pain, difficulty in straining, pre-existing prostate enlargement, stricture urethra, phimosis, drugs (sympathomimetics, anticholinergics, antihistamines) and constipation are the reasons. Hot water bag placement over hypogastric region, relieving anxiety, mobilisation, doing rectal examination may make the patient to pass urine. If still retention persists then Foley's catheterisation is done. Alpha adrenergic blockers, prazocin are also used often.

Acute Renal Failure in Postoperative Period

Acute renal failure in postoperative period is common and often it is real challenge to manage. It is increase in serum creatinine level–relative increase of 50% or absolute increase by 1 mg%. It can be oliguric ARF (output less than 480 ml/day) or nonoliguric ARF (isosthenuric urine output more than 2 liter/day but does not clear toxins). Both cause electrolyte and haemodynamic imbalance. True volume depletion in postoperative period is the *common* prerenal *cause*. It may be due to vomiting, diarrhoea, inadequate postoperative fluid replacement, haemorrhage presenting as tachycardia, hypotension, low jugular venous pulse, dry tongue. ARF can develop due to associated pulmonary oedema, congestive cardiac failure, as hepatorenal syndrome, nephritic syndrome, renal disease itself. It can be also immunologic, idiopathic, transfusion induced; *septicaemia induced* (decreased peripheral vasoconstriction, increased renal vasoconstriction, toxins) also. Aminoglycosides, *NSAIDS* (inhibits glomerular afferent vasodilatation) are nephrotoxic and renal parameters have to be monitored in these patients. Haemolysis or rhabdomyolysis can cause renal failure. It needs adequate fluid therapy, mannitol therapy–25 gram intravenous, sodium bicarbonate intravenous to keep urine pH more than 6.5 so that pigment heme gets dissolved. *Investigations*: **Prerenal ARF** is identified by low urinary sodium (less than 20 mEq/liter), less than 1% of fractional excretion of sodium, high serum sodium, and blood urea nitrogen and creatinine ratio is more than 20:1. In **renal cause of ARF**, fractional excretion of sodium is higher than 1% due to tubular damage. Urinary sodium level is more than 50 mEq/liter. Creatinine clearance test is ideal. *Treatment:* Haemodynamic management; *fluid challenge* using 500 ml normal saline infusion in 30 minutes; frusemide 100–400 mg intravenously; 20% mannitol; *dopamine i*nfusion at a rate of 3 μg/kg/minute; haemodialysis until kidney regains its function adequately. During haemodialysis, fluid intake should be monitored properly by taking help of a nephrologist; twice a day monitoring of serum electrolytes; *sudden hyperkalaemia* more than 5.5 mEq/dl is a risk for cardiac arrest and so potassium supplement should be avoided and IV calcium, DNS with insulin should be started. Adequate calorie is essential and is supplemented orally or parenterally **(Fig. 2-20)**.

Gastrointestinal Complications

Acute Erosive Gastritis

It is seen in critically ill patients; ICU patients; severe trauma; burns *(Curling's ulcer);* head injury and intracranial diseases (Cushing's

Fig. 2-20: Haemodialysis to a renal failure patient.

ulcer); drugs like aspirin, NSAIDs. It is due to gastric mucosal disruption, ischaemia, decreased gastric epithelial turnover, and reduced prostaglandin production (PG increases epithelial turnover, bicarbonate, mucus, mucosal blood flow). Gastroduodenoscopy confirms the diagnosis. It is treated by nasogastric aspiration, saline wash, proton pump inhibitors or H2 blockers. Sucralfate is an aluminium salt of sulfated sucrose binds only to ulcer bed but not to normal gastric mucosa, which increases the prostaglandin level, binds pepsin and bile acids, blocks the back diffusion of hydrogen ions, and protects stomach from colonisation by bacteria. Vasopressin, misoprostol (It is PGE1 used in NSAIDs-induced gastritis), laser coagulation using gastroscope are other methods. Vagotomy, total gastrectomy to control postoperative bleeding is rarely needed nowadays.

Postoperative Ileus

Ileus is a complicated process involving altered gastrointestinal nervous system, local hormonal factors, inflammatory factors, bowel handling and narcotic analgesia. Resection and anastomosis of bowel temporarily ceases the bowel activity due to inability to transmit the peristaltic waves from duodenal. Small bowel ileus recovers usually in 48 hours. Colonic ileus recovers in 4 days, gastric ileus in 4-5 days. *Note:* Patient without ileus, recovery of motility of small bowel occurs in 12 hours; of stomach in 48 hours; of colon in 72 hours. Observation, correction of electrolytes, sepsis control, and nasogastric aspiration is usually sufficient. Aspiration through nasogastric tube less than 200 ml; passing of flatus, return of bowel sounds are signs of recovery. Rarely if ileus causes abdominal compartment syndrome laparotomy may be required and decompression is done using decompressor. *Bowel obstruction* occurring within 30 days after surgery is called as *early postoperative* bowel obstruction. It can be due *to primary ileus* without any precipitating factors or *secondary ileus* with precipitating factors or *mechanical bowel obstruction* commonly due to adhesions (90%). *Ileus* is a complicated process involving altered gastrointestinal nervous system, local hormonal factors, inflammatory factors, bowel handling, and narcotic analgesia. Resection and anastomosis of bowel temporarily ceases the bowel activity due to inability to transmit the peristaltic waves from duodenal pacemaker. *CT abdomen* is ideal to diagnose type of bowel obstruction, complications, peritonitis and also to decide whether surgical intervention is needed. *Treatment* is initially conservative– fluids, correction of electrolytes, sepsis. But if needed re-exploration is done to correct the mechanical obstruction of the bowel.

Acute Abdominal Compartment Syndrome

It is increased intraabdominal pressure more than 12 mmHg (Normal pressure is about 5 mmHg) with hypoxia, increasing peak airway pressure, poor ventilation, oliguria. *Causes:* Ascites, pancreatitis, bowel wall oedema, fluid collection, major abdominal procedures, liver transplantation, contents of large long standing hernias once reduced into the peritoneal cavity, non-compliant abdominal wall when closed with tension, trauma, packing abdomen, paralytic ileus, coagulopathies. Diaphragm gets displaced upwards causing hypoxia, hypercapnia, and acidosis. Pressure more than 25 mmHg causes compression of IVC and portal vein leading into reduced venous return to heart and increased peripheral resistance. Right atrial and pulmonary arterial occlusion pressure decreases. Kidneys get compressed directly leading into decreased GFR and urine output. Mesenteric vein compression → decreased perfusion → intramucosal acidosis, bowel wall oedema. Increased CVP reduces the cerebral blood outflow and increases the intracranial pressure. *Features:* Difficulty in breathing, oliguria, tense distended abdomen, reduced cardiac output, deterioration in level of consciousness, acidosis and respiratory failure. *Investigations:* Measurement of pressure using a transducer through a urinary bladder Foley's catheter; measurement through gastric catheter; abdominal perfusion pressure measurement; assessment of renal infiltration gradient; CT abdomen. Pressure is graded as Grade I–10–15 cm H_2O; Grade II–15-25 cm H_2O; Grade III–26–35 cm H_2O; Grade IV–> 35 cm H_2O. *Treatment:* Emergency surgery and decompression, drainage of the abdominal fluid, muscle relaxant, ventilator, laparostomy, mesh/ biomesh/sterile bag cover, vacuum assisted closure are methods available.

Postoperative Gastrointestinal Bleeding

It may be upper gastrointestinal or lower gastrointestinal bleeding. Upper GI bleed may be due to peptic ulcer, stress gastritis, variceal bleed, Mallory Weiss bleeding, AV malformations and anastomotic bleed. Bleeding stress ulcers can occur, when gastric pH is less than 4.0. Lower GI bleed may be due to diverticulosis, colitis, bowel ischaemia, AV malformations. Precipitating factors are trauma, burns, head injury, coagulopathies, sepsis, DIC, drugs. Tarry coloured stool/melaena and haematemesis or blood in the nasogastric tube is the feature of upper GI bleed. Haematochezia, loose stool are the features of lower GI bleed. Rapid bleed can cause hypotension, tachycardia and shock. Gastroscopy or colonoscopy confirms the diagnosis. *Treatment:* Blood transfusion; conservative therapy by saline wash, intravenous H2 blockers (Ranitidine 50 mg/Famotidine), proton pump inhibitors, sucralfate, monitoring and maintaining the clotting factors, antibiotics, maintaining the INR using injection vitamin K or fresh frozen plasma, platelet transfusion; endoscopic control of bleeding by tamponade, epinephrine, laser, clips, banding, heater probe; angiographic embolisation using gel foam, clot, coils through superior or inferior mesenteric arteries. Occasionally surgical intervention is needed especially when there is refractile anastomotic leak. Re-anastomosis or subtotal gastrectomy, vagotomy are the procedures used.

Stomal Complications

It can be early or late. Early can be retraction, necrosis, abscess formation, high output systemic failure, and leak. Late can be prolapse, stenosis, parastomal hernia, fistula, excoriations, and bowel obstruction.

Anastomotic Leak

It is a common complication in gastrointestinal surgery often dreadful and life threatening. It may be intestinal or pancreatic or biliary fistulas/leak.

Factors: Poor blood supply, sepsis, emergency resections, malignancy, old age, obesity, smoking, immunocompromised patients, fluid collection or abscess formation, steroid therapy (steroid prevents collagen formation and healing), hypotension and hypoxia on table and in immediate postoperative period, presence of drains, shock, malnutrition, deficiencies, stapler related factors, specific diseases like carcinoma, tuberculosis, Crohn's disease, diverticulitis. Uncontrolled leak, abscess formation, electrolyte imbalance, anaemia, malnutrition, sepsis are the effects. Renal failure, multiorgan failure and death can occur if not controlled. Fistula should be *classified as low output or high output* depending on the quantity of fluid effluent in the fistula. If it is less than 500 ml it is called as low output fistula; if more than 500 ml it is high output fistula. Often it is *also* classified as *low* (below 200 ml/24 hours); *moderate* (between 200–500 ml); *high* (more than 500/day). In pancreatic fistula if less than 200 ml it is classified as low or more than 200 ml it is high. *Skin excoriation* (effluent dermatitis) initially allergic later with skin infection is common presenting as pain, ulcers, intractable itching. In proximal fistula electrolyte imbalance, fluid loss, malabsorption is severe whereas in distal fistula (colonic) it is less severe.

Investigations: CT abdomen, CT fistulogram, contrast GI studies, enteroclysis, endoscopies, cystoscopy to see enterovesical fistula.

Treatment: TPN; evaluation of site of leak as whether it is end/lateral/low/high fistula; antibiotics; skin care with zinc oxide cream, adhesives, barriers, sealants, pouches; blood transfusion; rest to bowel by keeping the patient nil orally so that luminal secretions are reduced. If there is abscess, bleeding, peritonitis, bowel ischaemia re laparotomy is done. Timing of re exploration is in 24–48 hours once patient is stabilized. Thorough peritoneal wash with warm saline is given. Site of leak is identified. Ileostomy, colostomy or internal by pass procedures are done depending on individual patients and site of pathology. *Spontaneous closure* of fistula is expected in 60% of patients. *Favorable factors for spontaneous closure of fistula are*–tract more than 2 cm, single straight tract, lateral type, non-epithelialised tract, without sepsis or abscess or foreign body, defect in the bowel wall less than 1 cm, without distal obstruction and absence of specific diseases, adequate nutrition. Forty percent cases *surgical intervention* and correction is needed. *Unfavorable factors are*–short tract less than 2 cm, multiple tracts, associated internal tracts, end fistula, epithelialisation, presence of infection or abscess, and bowel wall defect more than 1 cm, presence of specific diseases, foreign body, and malnutrition. Somatostatin and its analogues help in reducing the GI secretions to reduce the fistula output. Enteral nutrition can be very well used in low proximal fistulas or in colonic fistulas. *Fistuloclysis* is a newer method of infusing the nutrient fluid directly through the fistula into the GI tract.

Bile Leak

Bile leak is related to biliary surgery. It is 0.2% in open cholecystectomy and 0.7% in laparoscopic surgery.

Causes may be–leak from cystic duct stump, leak from accessory duct, injury to common bile duct or hepatic duct, biliary anomalies, thermal injury to CBD, late disruption and leak. Complete transection of CBD or hepatic ducts, avulsion of cystic duct, complex injuries with laceration of CBD can occur. *MRCP is diagnostic*. ERCP and CT abdomen is also done to assess proper pathology, site of disruption and to plan the proposed therapy. Pathology may be bilioma formation, biliary peritonitis, biliary fistula through drain site or through the wound, formation of abscess **(Fig. 2-21)**.

Presentations are–initially asymptomatic but later jaundice, cholangitis, abdomen pain and tenderness, features of sepsis.

Treatment: ERCP and stenting, aspiration of bilioma, in partial injury T tube with repair by open method, in complete transaction then choledochoenterostomy should be done. It needs proper care, skill, patience and meticulous dissection. Drains must be placed at the site.

Clostridium Difficile Colitis

Clostridium difficile is a Gram positive spore bearing anaerobic bacillus. Spores exist in the environment and GI tract as a dormant status. *Antibiotic use* disturbs the microflora of the colon allows this organism to get released from germinated spores. Bacteria release toxins - toxin A (enterotoxin) and toxin B (cytotoxin) cause various effects. *Effects are*–asymptomatic, mild colitis; pseudomembranous colitis; fulminant colitis; toxic megacolon. Its incidence is increased by over use of antibiotics. Its mortality is also increased now (15%). It is common in general surgery, vascular surgery, old age, patients in ICU, HIV, patients



Fig. 2-21: Biliary fistula in a difficult postoperative laparoscopic cholecystectomy patient. It needs ERCP and stenting.

on chemotherapy. Patients with long duration or multiple antibiotic therapies are more prone to its infection. Even single dose antibiotic therapy is known to cause *Clostridium difficile* sepsis. *Features:* Pain abdomen, foul smelling loose stool, fever, distension of abdomen, septic shock, dehydration, toxaemia are the features. *Treatment:* Careful use of antibiotics, aseptic precautions are important to prevent the infection. It is treated with *vancomycin (*orally/enema/IV) or metronidazole or rifampicin. Use of *lactobacillus acidophilus and saccharomyces cerevisiae* is also helpful. Occasionally surgical intervention with total colectomy and ileostomy may be needed as a life saving measure.

Postoperative Psychosis

Acute postoperative psychosis is often seen. Presentations are either depression or mania or like schizophrenia with delusions. It is often difficult to differentiate the condition from electrolyte imbalance and other metabolic derangements. Proper evaluation and then help of a psychiatrist is needed. Usually patient becomes alright once he recovers from the actual illness and postoperative period, but needs counseling and drug therapy.

Postoperative Fever (See above)

It is the common problem in postoperative period. ***Malignant hyperthermia*** is rapidly increased metabolic crisis during/after exposure to anaesthesia which is often life threatening (10% mortality). It is usually inherited as *autosomal dominant* disease where there is increased calcium efflux in skeletal muscle from sarcoplasmic reticulum to myoplasm. *Triggering anaesthetic agents* (halothane, enflurane, isoflurane, desflurane) and depolarising muscled relaxants like succinyl choline causes increased calcium concentration in myoplasma. It leads into uncontrolled hypermetabolism in muscles leading into hypoxia, lactic acidosis, hypercapnia, breaking of ATP (adenosine triphosphate), excessive heat generation, hyperkalaemia, myoglobulinuria, DIC, systemic ischaemia and failure. Commonly susceptibility runs in family, with earlier or family history of recurrent myalgia, pain and fever after exercise, and often caffeine intolerance. Muscle biopsy (creatine kinase assay), halothane/caffeine contraction tests are useful. Such susceptible patients should have trigger-free anaesthesia like barbiturates, benzodiazepines, propofol, ketamine, nitrous oxide, non-depolarising neuromuscular blockers). *Manifestations* usually develop *immediately* after administering the triggering drugs like tachycardia, arrhythmias, temperature, and muscle rigidity, inability to open the mouth with masseter spasm, tachypnoea, hypotension, and hyperthermia. *Treatment strategies* are–discontinuation of the surgery, stop and use alternate anaesthetic agent, dantrolene intravenously 2.5 mg/Kg bolus and repeated once in 5 minutes until recovery, hyperventilation, surface cooling by different methods like tepid sponging of entire body, coolant usage, cool parenteral fluids, correction of acidosis, beta blockers, lignocaine injection, correction of hyperkalaemia, hypercalcaemia, hypercapnia, dialysis if needed, ICU care.

Postoperative Hypothermia

A 2° C drop in the core temperature causes hypothermia with metabolic derangements.

Causes of hypothermia are prolonged surgical procedure, transfusion, intravenous fluids, low room temperature (air condition), anaesthesia (propofol), and vascular phenomenon.

Effects of hypothermia–vasoconstriction, poor organ perfusion, arrhythmias, decreased coagulation function (risk of bleeding), altered macrophage action and sepsis, reduced oxygenation of tissues, poor healing, neurological disturbances, acid base imbalance, poor cardiac and respiratory effort, bradycardia, coma. A temperature *below 35° C* is critical. Shivering with coldness is the initial presentation. Core temperature is *monitored* in pulmonary artery blood, tympanic membrane, oesophagus, pharynx, rectum and urinary bladder. Warm intravenous fluids, warmed clothes, humidifier/warmer, usage of warming device, covering of the head, humidifying inhalation gases, warm saline wash in surgical fields, rewarming infusion devices, rarely cardiopulmonary bypass–are the *treatment plans.* Single dose hydrocortisone may be helpful.

Surgical Wound Complications

Seroma Formation

A seroma is a collection of liquefied fat, serum, lymph fluid in a closed surgical wound under the skin in subcutaneous plane and is clear, yellow and viscous. It is often seen after skin grafting, mastectomy, surgery in inguinal region, after lymph node dissections, after mesh placing surgery. Suction drains prevent seroma formation. Once seroma is formed, it is aspirated. If there is failure even after two times of aspiration, then open drainage is done. Often seroma can get infected when it should be drained and fluid should be sent for culture. When mesh is present underneath, it need not to be removed in every patient. Mesh should be removed only when there is resistant infection. Only if resistant infection is there then mesh should be removed **(Figs 2-22A and B)**.



Figs 2-22A and B: Postoperative flap necrosis.

Haematoma Formation

It is an abnormal collection of blood either under the wound (traumatic or surgical) or in a potential space developed pathologically or after surgery. It can occur in subcutaneous plane, in the muscle, deep to muscle or in cavities like in the abdomen, thorax or intracranially **(Fig. 2-23)**.



Fig. 2-23: Postoperative haematoma formation.

Causes: Inadequate haemostasis during surgery, slipping of ligatures, drug induced (anticoagulants, aspirin, clopidogrel), depleted clotting factors.

Presentations: Pain, localised bluish or purple swelling, skin discoloration, tenderness often fluctuant. Large haematoma at different locations can cause different problems like airway obstruction in neck; paralytic ileus in the abdomen, features of raised intracranial tension in brain; respiratory distress in thorax etc. Anaemia, DIC, sepsis are other problems. Often bleeding may not get controlled and may be life threatening especially in the cavities. It can get infected also.

Investigations: Haematoma is confirmed by ultrasound, aspiration or CT scan (inside cavities). Prothrombin time, partial thromboplastin time, platelet counts, haemoglobin estimation, are other needed evaluation methods.

Treatment: It should be treated by surgical drainage, correction of clotting factors. Patients on heparin therapy should stop the heparin 3 hours before surgery; Low molecular weight heparin (LMWH) 15 hours before surgery; warfarin therapy 3 days before surgery; clopidogrel 6 days before surgery. International normalised ratio *(INR)* should be *less than 1.5* before surgery.

Surgical Site Infection

It may be (superficial) in skin and subcutaneous tissue; (deep) in fascia and muscles; internal cavities at the site of operation (Organ space*). Superficial wound infection* will show purulent discharge with erythema, pain and oedema involving skin and subcutaneous infection in less than 30 days. *Deep wound infection* is purulent discharge from deeper plane, with clinical or sonological or radiological evidence of deeper abscess, fever, pain, tenderness or wound dehiscence through deeper plane in less than 30 days. *Organ space infection* is purulent discharge from a drain placed at organ space, bacteria cultured from fluid from organ space, confirmed abscess in organ space clinically or by evaluation methods with infection in less than 30 days without an implant or with infection less than one year with an implant. *Commonest bacteria* are group D enterococcus, *Staphylococcus aureus,* and *Escherichia coli*. *Commonest time* of postoperative infection is 5-6 days postoperatively. 80% of infections occur within 30 days. *Factors related to surgical wound infection–(Patient factors)* old age, obesity, smoking, alcohol intake, ischaemia, poor blood supply, diabetes mellitus, anaemia, malnutrition, immunosuppression, steroid therapy, associated malignancy, hypoxia, hyperlipidaemia, radiotherapy site*; (Treatment/Hospital factors)* foreign body in the wound, improper sterilisation, poor asepsis methods, presence of drains, emergency surgery, surgery in sepsis, lengthy surgical procedure, nosocomial infection. Surgical wounds are classified as clean, clean contaminated and dirty **(Table 2-1)**.

Management of infection: Features of *infected wound* are presence of pus/infected fluid in the main wound, pus spontaneously draining from disrupted wound, fluid culture positive for bacteria. For infected wounds *therapeutic antibiotics* are given. For clean contaminated wounds preoperative antibiotics are indicated. It is given 30 minutes before surgery and is continued every 4 hours until surgery is over and later standard dose is continued. Only in certain clean surgical cases like mastectomy *prophylactic antibiotics* are given preoperatively; but it should be stopped in immediate postoperative period (usually antibiotics are not necessary in clean cases except in certain occasions) **(Figs 2-25 to 2-28)**. Wound sutures are opened. Fluid/pus are drained. Fluid is sent for culture study (controversial). Open wound debridement is done and thorough warm saline wash is given. Wound is packed and dressed. Regular dressing is done until wound granulates well. Wound may close spontaneously by epithelialisation or scarring or may need secondary suturing or skin grafting if wound area is wide. Wound vacuum dressings are very useful in large, deep wounds **(Fig. 2-24)**. Use of drain in surgical wound is controversial. Closed suction drains in deep spaces are advised. In usual surgical wounds drain is not necessary.

Table 2-1: Surgical wounds–classification

Clean wound	*Clean contaminated*	*Contaminated*	*Dirty wound*
Primary closure of the wound	Primary closure of the wound	Open/traumatic wound	Open–suppurative wound
No hollow viscus injury	Controlled hollow viscus injury	Evidence of inflammation is present	Evidence of severe inflammation
No evidence of inflammation	No evidence of inflammation	Spillage of viscus is present–uncontrolled	Untreated, uncontrolled spillage of the content
Proper aseptic methods used	Mechanical drain usage	Infection rate – 25%	Pus in the surgical field
Elective surgery	Infection rate–< 8%		Infection rate–40%
Infection rate–< 3%			



Fig. 2-24: Vacuum dressing.

Prevention of surgical wound infections

- Proper aseptic care.
- Proper meticulous dissection, haemostasis, preservation of blood supply, gentle tissue handling.
- Proper wash, irrigation using warm saline.
- Avoiding foreign body in the wound, maintaining normal temperature.

Chronic Wound

A wound which is not healed completely in 30 days is called as chronic wound **(Fig. 2-29)**.

Causes: Debilitating illness, steroid therapy, immunosuppression, poorly nourished patients, obesity, malignancy, radiotherapy. These wounds are covered with granulation tissue may be healthy, unhealthy or exuberant. Once granulation tissue becomes healthy with clear discharge skin grafting is done to cover the defect. Often if area is not wide, then secondary suturing is done.



Figs 2-25A and B: Clean wound (see Table 2-1).



Figs 2-26A and B: Clean contaminated wound (see Table 2-1).



Fig. 2-27: Contaminated wound (see Table 2-1).



Figs 2-28A and B



Fig. 2-28C

Figs 2-28A to C: Dirty wound (see Table 2-1).



Fig. 2-29: Chronic wound.

Wound Dehiscence

It is *acute wound failure* in postoperative period with separation of wound edges including *all layers*. For all practical purposes it is observed in abdominal wound and so it is synonymous with *burst abdomen/abdominal wound dehiscence* **(Fig. 2-30)**. It is sudden, rapid all layer wound giving way precipitated by severe cough or vomiting causing salmon coloured serosanguinous discharge. Intraabdominal



Fig. 2-30: Burst abdomen/acute wound failure/abdominal wound dehiscence.

anastomotic leak has to be considered other than usual causes of wound sepsis. Under anaesthesia, thorough exploration of the contents is done. After warm saline wash, wound is closed primarily with interrupted non-absorbable monofilament sutures or using absorbable mesh or biologic prosthesis (decellularised porcine submucosa/dermis or human cadaveric dermis). Wound vacuum system using cell foam, semiocclusive drape and suction over the wound can be very useful. It gives immediate cover to the contents; removes the interstitial fluid, reduces the bowel oedema; increases the perfusion and healing; lessens the bacterial contamination. Intestinal fistulas, late hernia formation are the problems.

Adrenal Insufficiency

Acute Adrenal Insufficiency

Acute adrenal insufficiency in postoperative period may be due to destruction of gland by haemorrhage, necrosis, thrombosis which is secondary to sepsis, toxins, antiphospholipid syndrome or postpartum necrosis; critically ill patients; abrupt stopping of long-term steroid therapy; surgical adrenalectomy. Acute adrenal insufficiency is *difficult to diagnose* in a critically ill patients. Unexplained hypotension, haemodynamic instability, hyponatraemia not responding to normal saline, hypoglycaemia and uraemia persistent inflammation are the features. *Treatment* is high dose intravenous hydrocortisone or methylprednisolone, volume correction, correction of hyponatraemia. Sodium level *below* 120 mmol/Litre is dangerous.

Chronic Adrenal Insufficiency

Chronic adrenal insufficiency may be primary or secondary. *Primary* is due to primary adrenal gland destruction by autoimmune disease (Addison's disease). *Secondary* is due to diseases of hypothalamous or anterior pituitary or due to chronic use of steroids causing suppression of hypothalamo-pituitary-adrenal axis inducing adrenal atrophy. *Features*: Fatigue, weakness, anorexia, weight loss, diarrhoea, decreased libido, depression, dizziness hyponatraemia, hypoglycaemia, hyperkalaemia, acidosis. *Primary type* shows increased pigmentation of skin and mucous membrane due to elevated ACTH. *Secondary type* shows headache, visual disturbances, hypoadrenalism, and decreased ACTH level, loss of hair, pallor, hypothyroidism, oligomenorrhoea, and diabetes insipidus. Morning plasma cortisol level less than 3 μg/dl (83 mmol/Litre) is diagnostic (Normal is more than 19 μg/dl); between 3–19 is equivocal but suspicious of adrenal insufficiency; above 19 μg/dl rules out adrenal insufficiency. In primary type ACTH level in plasma is more than 100 pg/ml. In secondary type ACTH level is less. Aldosterone level in plasma may be reduced. *Rapid ACTH stimulation test* is useful. 250 μg cosynthropin is injected IV/IM and serum cortisol is measured in 60 minutes which will be 20 μg/dl or more in normal individual. If cortisol secretion is not increased then it is adrenal insufficiency. *Metyrapone test*: After oral administration of metyrapone, if there is insufficient increase in plasma 11–deoxycortisol and low plasma cortisol level (< 8 μg/dl) then it is secondary adrenal insufficiency. Condition is treated by IV hydrocortisone and fludrocortisone.

Other Complications

Hyperthyroid Crisis or Hypothyroidism

Hyperthyroid crisis occurs in improperly controlled hyperthyroid patient undergoing surgery of thyroid or other surgery. It causes dehydration, shock, hyperthermia, hypotension, cardiac arrhythmias. It is treated in critical care unit with beta blockers, antithyroid drugs, hydrocortisone, tepid sponging, antipyretics, Lugol's iodine, digitoxin, fluid therapy, heparin, plasmapheresis, proper monitoring. *Hypothyroidism* is not rare and is equally dangerous in anaesthetised patient. It should be confirmed by assessing T3, T4 and TSH levels. It is treated with l thyroxin therapy.

Syndrome of Inappropriate ADH Secretion (SIADH)

It causes chronic normovolemic hyponatraemia (serum sodium less than 135 mmol/Liter). *ADH* is arginine vasopressin synthesised in hypothalamus transported to and stored in posterior pituitary; secretes into blood to regulate water excretion. ADH is secreted by thirst, nausea, hypoglycaemia, hypovolemia and drugs like ACE inhibitors, dopamine, NSAIDs. SIADH is caused by trauma, stroke, ADH producing tumour, drugs. *Features* are anorexia, lethargy, convulsions, hyponatraemia, hypotonic plasma, urine osmolality in excess of plasma osmolality, increased urinary sodium excretion, absence of oedema, normal kidney function. *Treatment:* Fluid restriction is the main therapy, IV normal saline in significant symptomatic SIADH (not to every patient), or acute SIADH of less than 3 days duration. Slow gradual correction is the principle as rapid correction of sodium level causes permanent neurological damage. Frusemide occasionally can be used.

Postoperative Convulsions

It could be *primary* related primary intracranial diseases like tumour/trauma/haemorrhage in the brain. It could be *secondary* due to electrolyte imbalance, metabolic derangements, sepsis, systemic diseases, MODS, hypoxia, hypoglycaemia, hypomagnecaemia, drugs. Intravenous diazepam or phenytoin sodium is used. In refractory cases gabapentin is used. Later patient is assessed with CT head and electroencephalogram.

Postoperative Stroke

It is due to either ischaemia (common) or haemorrhage. Ischaemia is due to hypotension, thrombosis or emboli from heart. Haemorrhagic stroke (less common) is due to bleeding disorders, hypertension and anticoagulants. Patient is evaluated with CT head, echocardiography and cardiac evaluation, blood analysis (bleeding time, clotting time, prothrombin time and platelet count), carotid angiogram (CT angiogram). It is managed with the help of cardiologists and neurologists using mannitol, dexamethasone, anticonvulsants, cardiac management, thrombolytics.

Postoperative Epistaxis

It may be due to blood dyscrasias, anticoagulants, hypertension and trauma during intubation (nasal) or during insertion of nasogastric tube. *Anterior epistaxis* is due to septum and turbinates and is commonly due to tubes. It is controlled by pressure using thumb and fingers or packing using gauze. Posterior nasal bleeding (*posterior epistaxis*) is more dangerous and is torrential; difficult to manage. It needs posterior nasal packing; Foley's catheter insertion per nostril and inflating balloon with 30 ml distilled water to cause tamponade for 3-5 days; blood transfusions; occasionally ligation of sphenopalatine and ethmoidal arteries is needed.

Postoperative Sinusitis

Postoperative sinusitis commonly involving the maxillary sinus is of nosocomial origin mainly due to *Staphylococcus aureus* and Pseudomonas bacteria. It is also common in patients with ventilator. It is often dangerous as it may lead into life threatening postoperative pneumonia or brain abscess. Purulent nasal discharge, facial pain (if patient is awake), fever are the features. CT sinus and discharge study confirms the diagnosis. Proper antibiotics, often sinus drainage are the treatment needed.

Postoperative Parotitis

Postoperative parotitis is not an uncommon entity especially in elderly postoperative patients and in diabetic and immunosuppressed patients. Pain, tenderness, diffuse swelling, trismus, stridor due to airway obstruction, oedema of floor of the mouth, dysphagia are the features. Often it can cause toxaemia and septicaemia. Once abscess forms it needs proper incision and drainage through proper incision under general anaesthesia. Tracheostomy is often a need.

Intensive Care in Surgery

A critically ill patient is one who has life threatening illness or injury with one or more failing organs, essentially needing intensive care support **(Figs 2-31A and B)**.

Mortality is 50% if there is two organ failures; 85% if there are three organ failures; near 100% if there is four organ failures.

Monitoring

Arterial Blood Pressure

Non-invasive measurement of blood pressure is commonly done using either manual cuff or automated device. Measurement by invasive direct intra-arterial blood pressure is done by placing a cannula into the artery (radial artery) and connecting to a pressure transducer to record every beat accurate blood pressure. Intra-arterial cannulation can cause complications like haematoma, thrombosis of artery, infection, bleeding, arteriovenous fistula and pseudoaneurysm.

A
Monitor
Fluid/TPN
Ventilator
Infusion pump
B

Figs 2-31A and B: Intensive care unit showing ICU bed with facilities. *Courtesy:* Unity Health Complex, Mangalore.

Monitoring Heart Rate, Respiratory Rate and Temperature

Heart rate and respiratory rate are assessed through monitor in the ICU. Temperature is assessed by placing the thermometer in the axilla. Special temperature monitoring devices are also available. Continuous ECG monitoring gives heart rate (above 100 is tachycardia; below 60 is bradycardia). Lead II is used to assess P wave. Chest leads are used to assess infarction and dysrhythmias.

Central Venous Pressure (CVP)

It is a method to measure the right atrial pressure by placing a venous catheter (20 cm) into the SVC. Commonly for CVP monitoring, a venous catheter is passed through right internal jugular vein or infraclavicular subclavian vein to the SVC (used for TPN purpose). Or occasionally a long catheter (60 cm) can be passed through basilic vein (not commonly done). Under radiological guidance, initially a needle is passed 3 cm above the medial end of the clavicle, in the hollow between the two heads of sternomastoid muscles, directing towards the suprasternal notch into the right internal jugular vein. Then through a guidewire, a venous catheter is passed into the SVC through right internal jugular vein, which can also be confirmed by changes in flow during inspiration and expiration. Catheter is connected to saline manometer, taking manubriosternal angle (*angle of Louis*) as zero point. Normal value is 2-10 cm of water/0-4 mmHg. CVP has got a, c and v upwards waves; x and y downwards waves. *'a'* is atrial contraction (absent in atrial fibrillation); *'c'* is tricuspid valve bulging during ventricular contraction; *'x'* is atrial relaxation; *'v'* is atrial filling; *'y'* is tricuspid valve opening and ventricular filling. If less than 2 cm, more fluid is infused. If more than 10 cm, fluid infusion should be restricted. Right atrial pressure is directly related to ventricular end diastolic pressure, i.e. filling pressure of right ventricle which is directly related to ventricular end diastolic volume, i. e. evidence of overall volume of fluid in the body. *CVP monitoring is used* for fluid resuscitation in shock, patients with hypotension of any cause; for multiple drug therapy; for TPN. CVP is a useful indicator of cardiac filling if both right and left ventricles are functioning equally well. In ischaemic heart disease, cardiomyopathies, cardiac valvular disease left ventricular function is affected. In pulmonary hypertension right ventricular function is affected. Response to bolus of 500 ml fluid administration shows transient rise with a fall of central venous pressure suggests low circulating volume **(Figs 2-32A to C)**.

Complications of CVP: Pneumothorax; haemothorax; injury to brachial plexus and vessels; bleeding; sepsis; air embolism; catheter erosion into bronchus, right atrium; catheter displacement.

Pulmonary Capillary Wedge Pressure (PCWP)

It is a better indicator of circulating blood volume and left ventricular function. Catheter used *is Swan Ganz* triple channel pulmonary artery balloon catheter. It is used to differentiate right and left ventricular failure, pulmonary embolus and septic shock; to measure cardiac output, to monitor fluid therapy, inotropic agents and vasodilators. **Procedure**: Under strict aseptic precaution, using cannula and guidewire, catheter is passed through internal jugular vein, into the right atrium. Balloon is inflated by 1.5 ml of air and then negotiated into pulmonary artery, until it reaches a small branch and wedges it. Pressure at this point is called as *pulmonary capillary wedge pressure. PCWP* normally is 8-12 mmHg, considering midaxillary point as zero reference point. After that balloon is deflated to get pulmonary artery pressure which is normally 25 mmHg systolic and 10 mm Hg diastolic. PCWP catheter can be kept *in situ* only for 72 hours. PCWP gives left atrial pressure and filling pressure of left ventricle. Present pulmonary artery floatation catheter (PAFC) has got a lumen at superior vena cava or right atrium to give CVP also **(Fig. 2.33)**.



Figs 2-32A to C: Central venous pressure (CVP) is used to monitor the patient. Note the location of the central venous catheter. Note the CVP wave pattern.



Fig. 2-33: Pulmonary capillary wedge pressure (PCWP) is better index of shock. But it is technically difficult and cannot be kept for more than 72 hours. It cannot be used for perfusion purpose unlike CVP line.

Complications of PCWP: Arrhythmias; heart block; pulmonary artery thrombosis; pulmonary artery rupture; balloon rupture; pulmonary infarction; pneumothorax; haemothorax; bleeding; sepsis; thrombosis.

Arterial Oxygen Saturation Measurement

Pulse oximeter gives continuous reading of the oxygen saturation which is placed on the pulp of the finger. It is by using diode light probe having two wavelengths–red band of 660 nm for reduced haemoglobin; infrared band of 940 nm for oxygenated haemoglobin. Difference in absorbance of both gives saturation. It is easier rapid way of assessing the oxygen saturation. *Limitations of pulse oximeter* are–it is not accurate once saturation is below 70%; vasoconstriction, hypovolaemia, hypothermia, drugs, carboxyhaemoglobin, shivering, improper positioning will give false values.

Arterial Blood Gas Analysis

It is ideal way of assessing the metabolic or hypoxic or oxygenation status. It includes pH (7.30–7.44); PCO_2 (35–45 mmHg); PaO_2 (75–100 mmHg); PAO_2 (alveolar partial pressure of oxygen); CO_2 concentration (TCO_2 24–28 mmHg); bicarbonate estimation (22–26 mmol/Liter); O_2 saturation (95%) and temperature. Normal capnograph shows initial steep upstroke (sudden increase in CO_2 in expired gas); slow raising plateau (suggests alveolar emptying); a rapid fall (during inspiration). 6th hourly ABG analysis is needed in critical patient.

Core Temperature Assessment

Core temperature is measured by placing thermometer in oesophagus or rectum or at tympanic membrane. Rectal temperature is 0.5°C more than oesophageal temperature. Temperature below 35°C cannot be measured with standard thermometers but needs low reading thermometers.

Urine Output Measurement

Hourly urine output should be measured. It should be more than 1.0 ml/kg/hour which indicates good cardiac output. Urine output less than 0.5 ml/kg/hour indicates poor cardiac output.

Cardiac Monitoring

Continuous cardiac monitoring is essential. It indicates rhythm changes, rate, wave forms, etc.

Other Assessments

Assessment of blood urea, serum creatinine, serum electrolytes, urinary electrolytes, urinary urea and creatinine. In *prerenal failure* urinary sodium is less than 10 mmol/Liter. Urinary urea and serum urea ratio is 10:1. It is more than this when there is inability to concentrate urine. Assessment of liver function, *coagulation profiles* (bleeding time—BT, clotting time—CT, prothrombin time—PT, activated partial thromboplastin time—APTT, thrombin time—TT, fibrin degradation products—FDP, D dimer assay, platelet count) are also important. Total count may be increased in sepsis but it is a poor indicator as it may not be raised in cold septic shock. Neutrophil count is more reliable. Intracranial pressure monitoring (ICP) is ideal in patient with head injury, with encephalopathy using invasive ICP bolts. Acidosis/alkalosis should be assessed.

Scoring of Illness

Therapeutic intervention scoring system *(TISS)* is used. Scoring is between 1-4. More the score means more intervention is needed and worse outcome. *APACHE* (Acute Physiology Assessment and Chronic Health Evaluation) is another scoring system used in places. APACHE 3 is the present version used. *APS* (Acute Physiology Score) is also used with 34 parameters and each having 0-4 grading.

ICU Management

Fluid Management

Initially it is with crystalloids like normal saline or ringer lactate; later by colloids, blood. It is decided at regular intervals in individual patients in individual diseases.

Inotropic Agents

Inotropic agents like dopamine, dobutamine, adrenaline, noradrenaline or isoprenaline are used in hypotension and altered cardiac status. *Dopamine* is given as 2 to 5 μg/kg/minute (low dose) in oliguria to improve urine output as it causes renal and splanchnic *vasodilatation*. Moderate dose of 5 to 10 μg/kg/minute is *inotropic* through $\beta 1$ receptors of the heart. High dose of more than 10 μg/kg/minute causes peripheral *vasoconstriction* through $\alpha 1$ receptors. Dopamine is mainly used in septic shock. *Dobutamine* has mainly inotropic effect on heart without vasodilatation or vasoconstriction effects. Dobutamine is mainly used in cardiogenic shock.

Management of Respiration

It is second most important in ICU. Respiration should be assessed for existing problems. Endotracheal intubation, tracheostomy, management of ARDS, placement of intercostals tube when needed, assessment of respiratory failure, antibiotic therapies are important. Laryngoscopes, endotracheal tubes, Magill's forceps, fiberoptic intubation set, CO_2 detector should be available in ICU. If initial oxygen therapy is not adequate, then artificial ventilation is started using endotracheal intubation. Tracheostomy *is ideal* if prolonged ventilation is needed (more than 7 days). Problems with these tubes are–infection, bleeding, blockage and causing crisis, disconnection, acute gastric dilatation.

Management of renal failure, hyperkalaemia, acidosis, electrolyte derangements as required. Often haemodialysis may be needed.

Nutritional Support

Polymeric diet (proteins, glucose, triglycerides) or elemental diet (free amino acids, glucose, fat soluble medium and long chain fatty acids) or disease specific diet are given. Patient on ventilator are given with low carbohydrates, proteins and high fat diet. Patient with hepatic encephalopathy are given more branched chain amino acids with less aromatic amino acids. Enteral nutrition *is ideal* either orally or through nasogastric tube or through gastrostomy or jejunostomy. *Total parenteral nutrition (TPN)* is used *when needed*–poor GI absorption; acute pancreatitis; severely malnourished and catabolic patients; when oral food/enteral nutrition cannot be given for 10 days; GI fistulas. TPN is given through central vein like subclavian or internal jugular vein. ***Harris Benedict equation*** is used to calculate the required calorie [For men = 66 + (113.7 × weight in Kg) + (5 × height in cm)–(6.8 × age in years). For women = 655 + (9.6 × weight in Kg) + (1.8 × height in cm)–(4.7 × age in years)]. 60% of total calorie needed is provided from glucose and 40% of calorie is from fat. Protein is given to maintain the nitrogen to calorie ratio as 1:150. TPN fluids contain 20% dextrose, 20% fat in emulsion; 20% amino acids, electrolytes, vitamins, trace elements. *Complications of TPN* are–catheter displacement, sepsis, bleeding, pneumothorax, electrolyte imbalance, trace element deficiency (zinc, copper, chromium and selenium), essential fatty acid deficiency, biotin deficiency, hyperosmolarity, catheter block, cholestasis.

Other Supportive Methods

Often neuromuscular blocking agents may be required to paralyse the patient. Sedation is commonly used to reduce anxiety, reduce oxygen demand, to improve ventilation. Analgesics are often given to reduce pain. Antacids/H2 blockers/proton pump inhibitors/sucralfate are given orally or parenteral (H2 blockers and proton pump inhibitors) to keep gastric pH above 4.

Chapter 3

Basic Principles of Incision, Dissection, Suturing and Haemostasis

PRINCIPLES OF INCISION

Holding the Instruments

Surgical instruments are essential armamentarium for proper surgery. Instruments are held in two ways. *Better method* is by *finger tip pressure* wherein thumb and ring fingers are placed in finger bows of the instrument. Precise fine relaxed movements are essential for proper work up of the instruments. Bizarre hurried movements will not give precision. *Second method* of holding the instruments is tight *vise like grip* using fist of the hand. It gives a good grip but precision may not be adequate. Surgical trainee to begin with prefers this method as he will think that grip is essential part in holding the instrument. Even though this method may be useful in some situations, it is ideal to use the method of finger tip pressure and practice it for eventual smooth precise work **(Figs 3-1A and B)**. Middle finger of the surgeon is kept behind the handle and index finger is extended along the length of the handle. It is said that slow, definitive, precise and non-repetitive movements actually gives faster surgery than haphazard, frenzied, rapid movements. (Please refer chapter 5–Instruments for details about each instruments).

Surgeon should be like *an artist* (creative/innovative worker) *not just an artisan* (skilled worker).

One should remember that surgeon *risks the lives* of others daily and so optimum *efficiency* is needed in him. Both sin of commission or sin of omission should be avoided as much as possible.

Anaesthesia and Positioning of the Patient

Surgeon or assistant should be present beside the patient while giving anaesthesia even though it is commonly not followed. Once anaesthesia is given, proper positioning of the patient depending on the surgery which he does should be done by surgeon itself. For example proper positioning for thyroidectomy, nephrectomy, sympathectomy, laparoscopic surgeries should be done and confirmed by the surgeon himself as it is important to have a proper position while operating **(Figs 3-2A to C)**. Surgeon should be physically and mentally comfortable while operating.



Figs 3-1A and B: Holding needle holder by fingertip pressure (ideal) and also by tight vise grip (acceptable method).



Figs 3-2A to C: During anaesthesia surgeon should be present beside the patient. After anaesthetist gives permission positioning of the patient done. Surgeon himself should do the positioning. He should be fully satisfied with the position of the patient. Proper positioning makes surgery easier.



Figs 3-3A and B: Cleaning the surgical field using povidone iodine. It is cleaned first at the site of incision; later outer area of the field. Three times cleaning should be done. Last one is used to clean mainly at the site of incision.

Cleaning and Draping the Surgical Field

Area of surgical incision should be cleaned with antiseptic solutions. Usually povidone iodine solution is used. Cleaning is started initially at the site of incision using antiseptic soaked gauze held in sponge holding forceps. Smooth soft straight strokes are used. Eventual cleaning is done on the places away from the line of incision on either side. Adequate wider area should be cleaned. Usually cleaning is done two times. Often two separate antiseptics are used each time like povidone iodine first and surgical spirit next **(Figs 3-3A and B)**. It is matter of surgeon's choice than any standard. Care should be taken while cleaning crevices like umbilicus or skin folds. After cleaning, draping is done using sterile surgical towels. Towels of different colours are used - green/blue/violet etc. Green is the commonly preferred colour. Sterile disposable plastic sticking sheets (*adhesive plastic drapes*) are also used in deeper part of the towel. Often incising area is covered with such sterile sticking plastic sheets and incision is made through this plastic **(Figs 3-4A to C)**. All these different methods are used to prevent sepsis. Towel clips are used in the corners to hold the drapes.

Making the Incision

Ideally incision should be marked using sterile marking ink. Its length, type, placing should be decided depending on the proposed surgical technique **(Fig. 3-5)**. Scalpel is used to make the incision. Depth control is better when belly of the scalpel is used.



Figs 3-4A to C: Draping is important to reduce infection. Adhesive plastic drapes are ideal. Incision is made through it. Photos show draping at abdomen, thorax, and back (spine).



Fig. 3-5: Knife with blade should be given to the surgeon in a kidney tray. Same should be returned to scrub nurse. It should not be kept over the patient. It should be kept only in a kidney tray on a instrument trolley.



Fig. 3-7: Pen holding position.



Fig. 3-6: Dinner knife position.

- *Dinner knife position* is used while making lengthy incision. Sustained pressure by the index finger over the knife with depth control is the technique **(Fig. 3-6)**.
- *Pen holding/writing position* is used to make incision over the vessels/nerves/tumors. Skin flap or tissues without natural plane can be dissected using this method **(Fig. 3-7)**.
- *Fiddle bow position* is used to make incisions with less pressure on delicate tissues. It is with least pressure, fine dissection is done with firm grip **(Figs 3-8A and B)**.
- *Stab position of the knife* is used in draining an abscess or making an incision to pass drains. No 11 blade is usually used **(Fig. 3-9)**.
- *Grasping position* is used to make long sweeping cuts.

Incision should be in a single stroke cutting both skin and subcutaneous tissues. Repeated superficial flimsy strokes should be avoided. Once adequate incision is made small bleeders in the cut edges of the incision is cauterised using coagulation current. Many bleeding points stop spontaneously by pressure. Further incision is carried out with scalpel or cutting cautery. Cutting cautery transects the fat and tissues precisely but only partially haemostatic with least tissue trauma. Many surgeons prefer to use coagulation current to



Figs 3-8A and B: Fiddle bow position.

Principles in making incision (Figs 3.10A and B)

- Incision should be planned well prior to surgery for adequacy, for possible need for extension during course of the surgery, and indeed be cosmetically acceptable. Ideally incision site should be marked using sterile marker or methylene blue.
- Incision is done to access the deeper structure. It should be done parallel to crease lines. It should not cross across flexor aspects of the joints.
- It should be planned in such a way that scars are cosmetically accepted.
- Clean single stroke firm incision should be made with required depth. Repeated strokes and movements should be avoided. Blade should be at right angle to the surface.
- Knife should be perpendicular to skin to begin with blade pointing perpendicular to skin. But later blade should be parallel with curvature/belly of the blade on the site of the incision.
- While making lengthy incision like in abdomen, incision area should be stretched between thumb and index fingers of the other hand of surgeon.
- Another method is–using the fingers of left hand with the gauze, one lateral part of the marked incision line is held with traction; opposite side is similarly held by the assistant; deep stroke incision is placed using belly of the scalpel (22), cutting full thickness of skin and subcutaneous tissue, extending into the entire proposed length of the line of incision. It is commonly used in the abdomen.
- While making incisions care should be taken to avoid injuries to deeper structures like muscle/nerves/vessels/bowel.
- Patient should be symmetrically lying down on the operating table.
- In the abdomen with a previous laparotomy scar, present incision should be at a newer site. If skin is incised over the same scar, often excision of scar is needed. Dissection in the deeper plane and opening of the peritoneum should be started at fresh site so as to prevent injuries to deeper contents like bowel.
- Length of the incision should be adequate. There is no point in struggling in small holed blind surgeries.
- During surgery, if need arises, one should not hesitate to extend the incision.
- Use of diathermy in skin incision is controversial although cutting diathermy is used for this purpose. Thermal injury of the skin may result in poor scar.
- Incision should be parallel to natural lines/ Langer lines/hair lines/eyebrow.



Fig. 3-9: Stab position of knife for drainage of an abscess.



Figs 3-10A and B: Methods of making incisions. Surgeon can stretch the skin between thumb and fingers with left hand and with the right hand incision is made. In second method, assistant holds the skin stretched by traction on each side by placing fingers of the hands over gauze and surgeon makes incision.

transect fat and fascial layers. It is good haemostatic but causes more tissue damage, oedema, infection. Blended cautery is ideal in such situation rather than coagulation cautery. Blended cautery cuts well with adequate haemostasis but with lesser tissue damage. Cautery is used for dissection in most places even in depth and all laparoscopic procedures. Good quality cautery, proper settings and earthing (in monopolar), precaution to avoid inadvertent injury of important adjacent structures are most important while using the cautery.

In the abdomen *upper midline incision* is commonly used extending below across *left of the umbilicus* **(Figs 3-11A and B)**. Linea alba is cut using scalpel or cutting cautery. Peritoneum is held between two artery forceps. It is felt with fingers to confirm that no abdominal contents are grasped. Peritoneum is cut using scalpel blade holding obliquely. Cut edges on either side are held using artery forceps. Long curved scissor (Metzenbaum) with closed blades is passed under the entire length of the incision to confirm that there no adhesions. Blades are opened and peritoneum is cut in the line of incision. Peritoneum is opened on left of the falciform ligament because this area is vascular. 5 mm wide of linea alba should be left attached to the umbilicus so that while closing proper bites are taken at this point to prevent incisional hernia at this site **(Figs 3-12A to C)**.



Figs 3-11A and B: Midline incision is universally used in the abdomen. Adequate incision is a must. Extension below is done from left of the umbilicus.

In the *lower midline incision,* lower part of the incision should be done carefully. Rectus sheath should be opened up to the pubis bone beyond the pyramidalis muscle. Preperitoneal fat is adherent to the peritoneum and urinary bladder in the lower most part. This part is vascular and thickened. This part of the peritoneum need not be incised as it will not improve the exposure further instead it will cause unnecessary troublesome bleeding.

Holding the Skin and Tissues

Skin is held using toothed dissecting forceps. *Fine Adson's toothed forceps* are available. Tough structures are also held using toothed forceps. Structures like subcutaneous tissue, fascia, bowel wall, vessel wall are held using non toothed forceps. Holding pressure and grip should be only optimum in such a way that after releasing it should not show the imprint of the forceps tip. Forceps is held over the serrations on the outer surface like as a pen holding fashion. It is the *fine grip* which holds the tissue rather than force. Haemostat (Artery forceps) is also used often to hold fascia, peritoneum, aponeurosis, etc. As much as possible tissues should be held using instruments to avoid unnecessary tissue trauma. But fingers must be used when you need '*tissue touch/tissue feel*', to confirm the surgical anatomy/to confirm the operability or extent of the pathology/to confirm the relation. *Finger dissection* is a well accepted surgical method but unnecessary usage should be avoided. Artery forceps should not be used to hold skin, bowel or delicate structures. Allis tissue forceps is used to hold skin flaps and tough structures. It is not used to hold bowel and delicate structures.

Retraction

Retraction of tissues in the depth is essential while doing surgery. Langenbeck retractor is used to retract skin and subcutaneous tissues. Different retractors are available to use in the deeper plane. Non-self retaining retractor (manual) when used needs the constant help of assistant. When self-retaining retractor is used, assistant's hands are free to help surgeon during surgery. Surgeon's both hands should be free to do the procedure. Often many general surgeons do surgery with one hand while retracting the tissues with other hand. This should be avoided as much as possible. But when traction to the tissue is needed then surgeon should hold or retract the tissues with traction to undertake further steps of the dissection **(Figs 3-13 and 3-14)**.



Figs 3-12A to C: Opening the peritoneum using knife or scissor after confirming on intra-abdominal contents are held with artery forceps.



Fig. 3-13: After draping proper retraction is needed to continue with surgery. Assistant holds the retractors. Two hands of the surgeon should be free for dissection and proceeding with surgery.



Fig. 3-14: Retraction of tissues is important using different retractors as needed.

Adequate incision of *sufficient length* and proper *stable exposure* are *the two basic essentials* of good surgical practice.

Exposure and Isolation of the Surgical Dissecting Area of Interest

Adequate exposure using proper incision, proper positioning, good retraction, by assistants, proper packing and keeping away other adjacent organs/tissues/structures. For example in open method of cholecystectomy with Kocher's subcostal incision, mops are placed medially over the stomach and below over the colon and above the liver to expose the field adequately.

DISSECTION

Dissection means identifying and separating the anatomical planes. Delineating right plane in right way is a real surgical craft. It comes by constant repetitive work, dedication and thinking. A beginner becomes master only once he masters this basic asset of surgical handicraft. Dissection should be least traumatic and with least blood loss.

Different methods available are–

Finger dissection: Left index finger is used for finger dissection. Gentle smooth finger strokes or sweeps are good way of dissection especially in the abdomen during Kocherisation, gastrectomy, adhesion removal, vagotomy, hiatus hernia surgery, pelvic surgery. However when there are adhesions blind finger dissections close to the vessels and forcible finger dissections are to be avoided **(Fig. 3-15A)**.

Scalpel dissection: It is ideal one to create a plane which is not natural. Scalpel is held in 45° angle to the line of incision. It is used to raise skin flaps in mastectomy, thyroidectomy. It is useful in dissecting dense scar tissue, tough structures. Scalpel is also used (no 15) in cutting the bowel during resection **(Figs 3-15B and C)**.

Peanut dissection (Kutner): It is very popular method of dissection in many place like dissection of Calot's triangle in cholecystectomy, urinary bladder dissection, to dissect the planes in pedicles during thyroidectomy, to skeletonise the lymphatics, to dissect the loose areolar tissue to achieve proper plane **(Figs 3-16A and B)**. It is small 1.5 cm wet gauze held firmly in a long artery forceps.

Large folded wet gauze (10 × 10 cm) in a sponge holding forceps is also used for dissection to push avascular loose areolar tissue while separating urinary bladder from uterine cervix; to elevate the peritoneum during lumbar sympathectomy, to separate stomach from pancreas posteriorly **(Fig. 3.17)**.

Scissor dissection: Closed blades of scissor is commonly used to dissect the tissues which also give proprioception feel of the tissues. Dense tissues are dissected and cut with scissors. Gentle precise controlled movements are necessary. It achieves a clean sharp dissection **(Figs 3-18A to D)**.



Fig. 3-15A: Finger dissection is one of the methods of dissection. It gives anatomical feel (tissue feel); depth can be assessed; extent of the pathology can be assessed; blunt dissection can be carried out. It should be gentle, careful dissection. Rough usage of finger should be avoided as it may injure adjacent tissues often causing unpleasant bleeding.



Figs 3-15B and C: Scalpel dissection is used commonly when there is no natural plane.



Figs 3-16A and B: Peanut dissection is commonly used to dissect loose areolar tissue.



Fig. 3-17: Gauze dissection is used along loose areolar tissues; to separate urinary bladder from uterine cervix during hysterectomy, etc. It is used with gentle sweep movements over the tissues.

Cautery dissection: It is presently commonly used method of dissection. Cutting cautery is used for dissection. Coagulation is used in between as and when needed to control bleeding. It is not advisable to use coagulation current for dissection as it causes too much charring and tissue destruction. So infection and flap necrosis will be higher. Many surgeons are habituated to use coagulation current for dissection as it is easier and bloodless **(Figs 3-19A and B)**.

Note

Proper anaesthesia; good exposure; adequate retraction; meticulous dissection; patience; decision making skill on the operation table; skilled assistant; taking help of another surgeon without any ego–are the need for *successful surgery* and to become *successful surgeon*. ***'SEE AND CUT and CUT AND SEE'***



Figs 3-18A to D: Various methods of holding and using scissor during dissection. Scissor dissection is one of the good controlled methods of dissection.



Figs 3-19A and B: Cutting cautery is used for dissection. Coagulation current may cause charring. Coagulation is used to control bleeding. Cautery dissection here used to raise skin flaps in mastectomy.

SUTURING TECHNIQUE

Suturing is an art. It is technique of approximating tissues or ligating the vessels using specifically designed materials. Catgut and silk are good old suture materials (1887). Silk is non-absorbable and catgut is absorbable. Polypropylene, polyglactic, polydioxasone sutures (PDS) are newer sutures.

It is essential to avoid damage to suture strand when handling. One should touch strands only with gloved hand or closed blunt instrument. One should not crush or crimp sutures with instruments except when grasping the suture during instrument tie. Suture material should not be held using needle holder or artery forceps except during knotting **(Figs 3-20 to 3-23)**.



Fig. 3-20: Holding the needle holder properly and knowing its movement in rotational axis is important for proper suturing and knotting. It is the precise gentle rotation which is essential; not pushing flimsy movement.



Fig. 3-21: Holding the suture material using needle holder unnecessarily should be avoided.



Fig. 3-22: While suturing needle bite should be taken correctly with adequate depth. Deeper part should be wider to have proper apposition.



Fig. 3-23: Taking wrong bite of needle with inadequate depth, width and inequality will cause poor apposition and alignment and also creating dead space in the deeper plane causing seroma formation or poor scar later.

Proper selection of the needle holder, type of needles (size, curve, etc), and suture material is important. Needle is placed in the needle holder at the junction of *proximal 2/3rd to distal 1/3rd* of the needle holder to have optimum grip and precision. If held more proximal, then grip will be good but precision is inadequate. If needle is more distally placed, precision is good but with poor grip. Needle is held *half the distance from swaged end*. Grasping of the needle should be neither too tight nor too loose. Optimum *grasp* should be there. Alignment of needle holder jaw should be proper. Needle should not rotate during grasping. Needle and needle holder should function as a *single unit* **(Figs 3-24A and B)**.

Needle is passed through smaller thickness of the tissue. Excess tissue bite should be avoided. It is the smooth, rotation movement than the movement with force which is important. Proper sized needle



Figs 3-24A and B: Holding the needle with a needle holder.



Fig. 3-25: Holding the needle tip with needle holder should be avoided. It is held only during knotting process.

should be taken depending on the thickness and texture of tissue/tissue resistance which is to be apposed. *Rotation force* should be in the direction of the curvature of needle. Twisting or bending needle tip should be avoided. Holding the needle tip with instrument will cause blunting or breaking of the tip and if such broken tip is entangled in the tissue it is very difficult to identify it **(Fig. 3-25)**.

Cutting needles are used for skin, tough structures, mucoperiosteum. *Round bodied needles* are used for smooth tissues like fat, peritoneum, muscle, bowel, vessel anastomosis, etc. Usual *width of the tissue* taken is 5 mm. But finally it depends on the thickness, tissue strength and condition to which patient is getting operated upon. In retention sutures of abdomen or Smead - Jones closure width taken is 3 cm. Distance between each bite is important. It should not be too closer or too far. In the skin 1 cm gap sutures are sufficient. In the bowel 5 mm gap sutures are needed to have complete sealing of the bowel edge and also haemostasis. Tissue should be handled carefully. Only required tissue should be grasped. Bulk grasping should be avoided. Smaller sized suture is better **(Figs 3-26 and 3-27)**.

Size of the suture material is decided in relation to the strength of the tissues. Usually 3 zero is used. Thicker tissues may need 2 zero sutures. Abdominal wall closure needs 1 or zero or 1 zero suture material.

Ideally interrupted sutures are better. It holds and apposes well. It maintains the blood supply of the tissue edge. But in many places like gastrojejunostomy continuous sutures can be used.

It is better to take bite from each edge of the tissue *separately* even though it looks more time consuming. When both edges are held together and needle is forced through them, there are chances of having lateral movements which can cause tear at the first point of entry of the needle resulting in poor apposition of the tissue. It can be used safely if the edges are close enough without tension and if one can avoid lateral movements while taking bite of second edge **(Fig. 3-28)**.

Learner *should practice* holding the tissues with instruments than hand. It is common that beginner prefers to use hands than instruments as it is easier, but holding tissues with instruments is better. In certain occasions hand is used to hold the tissues; otherwise by enlarge instruments are used.

Type of suture material used depends on the tissue and condition for which suturing is done. Once wound attains maximum strength sutures are no longer required. Slow healing wounds need non-absorbable sutures. Rapidly healing wound need absorbable sutures. Rapid healing, least irritation is achieved by smaller sized, monofilament, inert suture material. In bowel absorbable suture material used–3 zero is ideal; often 2 zero is also used. Silk is also used in many centers. Interrupted sutures are better especially in oesophagus, colorectum, and contaminated field. Continuous sutures are used in stomach and jejunum. Single layer is well accepted; it gives wider lumen; maintains blood supply. Double layer using silk/linen for outer seromuscular; full thickness Connell/Gambee sutures for inner layer using absorbable sutures like 3 zero vicryl is also equally good. It is time consuming, may lessen the luminal diameter. But it is more secure. In biliary tree and urinary system rapidly absorbing sutures like 3 zero vicryl are used. Patient age, nutrition, immunosuppression, malignancy, sepsis, acute nature–are other factors which decide the type of suture material used **(Fig. 3-29)**.

Note: After suturing needle should be returned to scrub nurse with needle holder.

Different Types of Suturing

Simple everting suture: It is used in skin. Bites at deeper plane should be wider than superficial plane. Edges should be everted once this stitch is placed **(Fig. 3-30)**.

Simple interrupted fascial suture: It is used in abdominal wall like in closure of *Mc'Burney* incision by taking about 5-8 mm of tissue bite **(Figs 3.31A and B)**.

Vertical mattress suture (Stewart): Deep bite is taken from one edge; passed through deeper part of opposite edge and brought out on the opposite edge surface; again close to the superficial margin of opposite side bite is taken and is passed through similar edge of same side to bring out as mattress suture **(Figs 3-32 to 3-34)**.

Horizontal mattress suture: It is not commonly used in skin. It is often used in retention sutures (tension sutures), fascial closure, and ventral hernia repair, to achieve haemostasis. Here bite is taken like a square with two time bites on each side one below the other **(Fig. 3-35)**.

Haemostatic figure of eight suture: It is basically used for haemostasis. It is used in circumcision to ligate frenular artery, bleeders withdrawn into the soft tissues. Vicryl or polypropylene (2 zero/3 zero) is used.

Continuous over and over simple suture: It is continuous suture used in peritoneum, fascia, aponeurosis. Vicryl is used usually.


A
Needle bite
on the same side
B
C
Needle bite
on the other side
D
E
F
G
First knot
Squaring of the knot
H
Second knot
I
Third knot
J
Ready to cut the remaining ends short
K
Cutting the ends short
L

Figs 3-26A to L: Instrument suturing and knotting—simple suture.


Mattress suture
third bite
A
Mattress suture
fourth bite
B
Mattress suture
first knot - squaring
C
Mattress suture
second knot
D
Mattress suture
third knot
E
Mattress suture ready for
cutting remaining ends short
F

Figs 3-27A to F: Method of placing mattress sutures and knotting with squaring.



Fig. 3-28: By marking the corresponding points of each edge of the wound before suturing, makes it easier to take bites at proper anatomical level to achieve good wound alignment and apposition without causing disparity.



Fig. 3-30: Bite should be equidistant on both edges of the wound to achieve eversion of the wound edges. Inversion of the edge should be avoided.


– 1 cm width
1cm gap
Thumb or
toothed forceps
Counter pressure

Fig. 3-29: Equidistant, proper correct bite, counter pressure using thumb or toothed forceps on the opposite edge, rotation precise gentle movements are the basic principles of suturing.



Figs 3-31A and B: Simple interrupted suture.



Fig. 3-32: Vertical mattress sutures.



Fig. 3-33: Scar of interrupted sutures–vertical mattress sutures.



Fig. 3-34: Vertical mattress suture (Stewart).



Fig. 3-35: Horizontal mattress sutures.

Subcuticular suture: It is used in skin closure. Needle bite is taken initially at one corner; it is continued by taking bites at the white dermis each side alternatively to reach the other end of the wound; which is then brought out through the corner of the wound. Usually absorbable polyglycolic acid is used (3 zero) using curved cutting needle **(Figs 3-36A to D)**. It is difficult to place subcuticular sutures using round body needle. Absorbable suture is not removed. Nonabsorbable monofilament suture can also be used. Its ends are left long or tied loosely over gauze. It is removed in 10 days. Often there may be difficulty in pulling out the sutures. Subcuticular suture gives cosmetically better scar. But if sutures thicker than 3 zero is used it will cause inflammatory reaction in the apposed wound causing no cosmetic benefit. Subcuticular sutures should not be used in trauma, infective areas, and emergency surgeries. There is controversy whether it has got advantage over interrupted sutures using fine material except in avoiding (in absorbable subcuticular)/easier (non-absorbable subcuticular) suture removal.

Skin staplers: It is stainless steel staplers applied using specialized disposable devices to the skin. It is quicker and apposes well. It is used in major surgeries. It saves time compared to suture closure of the skin. Two wound edges should be held in proper alignment before applying skin staplers. Removal needs special instrument. It gives good cosmetic result **(Figs 3-37A to D)**.

Continuous locking sutures (Continuous blanket sutures): It is not commonly used in skin. It is used in closure of fascial layer. It holds well and is haemostatic. It is commonly used in closure of rectus sheath. Nonabsorbable suture material is usually used. It does not cause bunching of the wound **(Fig. 3-38)**.

Continuous over and over suture: It is continuous sutures taken at equidistant. It should not be very tight as more tightening may cause strangulation of the wound edge; it may cause bunching of the wound; but it saves time **(Fig. 3-39)**.

Continuous 'mass closure' using one or zero monofilament nonabsorbable suture material commonly used in closure of abdominal incisions especially midline. Bites are taken at 1 cm width from wound edge; with each bite at 1 cm interval. Single strand or loop suture material can be used for this. This method is commonly used **(Fig. 3-40)**.

Note: *Jenkin's rule*–Length of the suture material used is 4 times the length of the wound.

The three point suture: It is used in suturing triangular flap/flaps to have correct apposition. Dermal bites should be at the same levels on both edges **(Fig. 3-41)**.

Retention sutures (Tension sutures): It is even though practiced in many centers, ideally it should be avoided. It is used during closure of laparotomies done for acute conditions like peritonitis, obstruction wherein patient's general condition is not good; layer by layer closure may cause acute wound failure with burst abdomen; when quick closure is a need of the day. Its use is getting replaced by *Smead-Jones*


Epidermis
Dermis
Suture material
A
B
C
D

Figs 3-36A to D: Technique of subcuticular suture placing.


PROXIMATE PLUS MD
35w
A
B
C
D

Figs 3-37A to D: Skin stapler is used to close large surgical skin incision. It is faster and cosmetically accepted.



Fig. 3-38: Continuous locking suture.



Fig. 3-39: Continuous over and over suture.



Fig. 3-40: Continuous mass closure of the abdomen.



Fig. 3-41: Three point suturing is used in apposing junction of the triangular flaps.

sutures or interrupted single layer deeper sutures. Retention sutures are taken as full thickness sutures placed 3-5 cm away from the wound. Large curved cutting needle is used. Number zero or one monofilament suture material like polyethylene is used. First bite is taken away from the wound from skin to peritoneum into the peritoneal cavity; needle is then brought back 3-5 cm away from the opposite edge of the wound; suture material is passed through a supportive sterile tube (cut drip set tube) of 2-3 cm length; near the edge of the skin of the existing side needle and suture material is passed; similar bite is taken on the same side of skin edge; suture is passed through one more sterile tube of 2-3 cm size and is kept ready for knotting after completion of placing all sutures. Each suture is placed with a gap of 1.5 to 2 cm. Knotting is started from one corner; but if closure is difficult then central knots is put first. While knotting in deeper plane, bowel and omentum should be guarded with finger or placing mop or using a special curved bow-like instrument (*Sergeant Instrument*) so as to prevent entangling or injuring these structures. Sutures are cut once all knots are tied on one side of the wound. Skin may be apposed using separate sutures **(Fig. 3-42)**.



Fig. 3-42: Sergeant retractor used during closure of the abdomen to prevent abdominal content coming out.

In *vertical mattress retention sutures,* tubes cross the wound. *In horizontal mattress retention sutures*, bites are taken like a square and sterile tubes are placed parallel to the wound (not crossing). In this type number of sutures needed is less than vertical type. Distinct advantages of horizontal mattress retention suture type are not clear but it is said that it is stronger than vertical mattress retention suture. But chances of bowel or omentum getting trapped are higher in this **(Figs 3-43 and 3-44)**.

Modified Smead-Jones closure: It is interrupted specialised suture used in the closure of abdomen as single layer excluding the skin. Linea alba is held with Allis' forceps. *Number one* polyethylene or PDS suture material is used. First bite on one side taken 3 cm away (width) from the margin from outside to inside; it is then passed through the corresponding opposite edge with 3 cm width from inside to outside; later again one small loop of 5 mm width from the edges of each side of the wound from first bite site to second bite site is taken; suture is knotted on the free edge of the first bite side. Full thickness bite holds the suture and maintains the tension in the wound. Smaller loop keeps the linea alba in apposed place. Large curved *Ferguson needle* is better to place these sutures. Each suture is placed at 2 cm interval. This is the type of suturing used at present in acute abdominal conditions instead of the retention sutures. Here also it is better to place all sutures under proper vision and knotting is done at the end **(Fig. 3-45)**. At least four knots should be placed. Excessive tension should be avoided. In upper abdomen peritoneum need not be included in the bite; but in lower abdomen as linea alba is indistinct, peritoneum is included in this.

LE Hughes double near and far suture: It is similar with same indications as Smead-Jones, with double near and far sutures placed to have a strong loop with knot on one side **(Fig. 3-46A)**.

Single layer seromucosal suture of bowel: It is now well practiced method of suturing of the bowel. Interrupted seromucosal sutures using three zero/two zero vicryl or PDS takes up well. Nonabsorbable silk or linen also can be used. These nonabsorbable sutures are good old suture materials which are even now well accepted. Only drawback presumed is formation of suture granuloma at the anastomotic site **(Fig. 3-46B)**.

Gambee single layer full thickness (all layers) sutures using vicryl are also used in bowel anastomosis. It can also be used as continuous sutures especially during gastrojejunostomy. *Continuous suturing* is quicker; alternate bites should be locked to prevent purse string effect; anterior layer is closed with inverting sutures. *Interrupted suture* is more stable and stronger with less chances of anastomotic disruption. It also maintains the blood supply better than continuous sutures. Width of suture bite taken should be less over mucosal part than seromuscular part. Bites are taken 3 mm from the cut edge of the serosa; each bite is taken in a 5 mm gap **(Fig. 3-47)**.

Lembert suture: It is the commonly used seromuscular suture. Silk 3 zero or vicryl 3 zero is used. Deep seromuscular suture including submucosal layer is taken at a point 5 mm from the cut edge of the serosa; this bite emerges at same line closure at 2 mm from the cut edge of serosa; bite is taken on the opposite part of the bowel at 2 mm from the serosal cut edge as seromuscular which emerges at 5 mm point away in the same longitudinal line and knot is placed. It can be used as continuous suture also **(Fig. 3-48)**.

Cushing suture: It is similar to Lembert suture wherein seromuscular bites are taken parallel to the cut edge of the serosa (at 2 mm from the cut edge). Thickness of tissue taken is 5 mm. Both interrupted and continuous sutures can be taken **(Fig. 3-49)**.

Halsted suture: It is actually seromuscular horizontal mattress suture. Care must be taken to avoid excessive tension over the suture line as this may lead into ischaemia of the anastomotic site **(Fig. 3-50)**.



Fig. 3-43: Vertical mattress retention sutures. It is full thickness single layer suture.



Figs 3-44A and B: Horizontal mattress suture.



Fig. 3-45: Modified Smead Jones sutures. These sutures are better than placing retention sutures.


Inbox
Showing exact technique

Fig. 3-46A: LE Hughes double near and far suture.



Fig. 3-48: Lembert suture.



Fig. 3-46B: Single layer seromucosal layer suturing of the bowel.



Fig. 3-49: Cushing suture.



Fig. 3-47: Gambee suture.



Fig. 3-50: Halsted suture.

Connell suture: Here suture material passes through all the layers of the intestine from serosa to mucosa; again brought out through all layers of the intestine on the same side from mucosa to serosa; passed over opposite segment of the bowel; passing from serosa to lumen/mucosa and from mucosa to outside towards serosa; again coming towards same side to repeat the technique. It is very good technique to invert the mucosal part of the anterior layer. It is commonly used in double layer anastomosis but can be used in single layer anastomosis **(Fig. 3-51)**. Connell suture apposes well; achieves good mucosal inversion. But it is *not adequately haemostatic* and so bleeders on the cut edge of the bowel should be ligated or cauterized individually.

KNOT TYING TECHNIQUE

Principles

The knot must be simple, firmly tied and should not slip. Knots must be as small as possible and ends should be cut as short as possible in the tissues. Skin sutures which are to be removed should be kept around 1 cm length so that removal is easier. But keeping too long sutures will abut into adjacent knots causing problem. In tying the knot one should avoid friction between strands to avoid weakening of the suture; one should avoid damage to the suture while tying knot. Excessive tension while tying knot will lead to suture breakage or tissue damage. Strength should be optimum; neither too tight nor too loose. Beginners tend to put too tight knots. Too tight sutures may cause tissue strangulation. After tying the first loop tension should be maintained on the strand to avoid loosening of knot. Final throw should be as nearly horizontal as possible. The surgeon should not hesitate to change stance or position in order to place secure flat knot. Usually three knots are sufficient. First knot is the best knot. In retention sutures or if polypropylene is used as suture material, then maximum 4/5 knots has to be placed. Any additional knots will not help in stability of knot or do not add to the strength of a securely tied square knot.

First throw/knot should be gently pushed and guided using index finger **(Fig. 3-52)**.



Fig. 3-51: Connell suture for bowel anastomosis.



Fig. 3-52: First throw/knot should be gently pushed and guided using index finger.

Remember about suturing

- Width of the bite of suture on each side of the wound edge should be equal–coarse adjustment.
- Gap between the sutures should be equal. It may be 1 cm gap in skin; 3-5 mm gap in bowel; 1-2 mm gap in vessel.
- Slight eversion of the wound edge causes proper apposition.
- Deeper bite in the tissue by the needle should be wider than superficial to achieve adequate eversion.
- Inversion of edges may cause overlapping, delayed healing, delayed wound gap and poor scarring.
- Knots should be on one side of the bites on the corner of the optimal side which is the wound edge which is on lower level–gives fine adjustment.
- Bites should be adequate and deep enough; superficial unequal bites will cause improper apposition.
- Thumb can be used to push the skin against the needle bite from opposite side.
- Suturing is done from more mobile edge of the wound towards relatively immobile side.
- Flap of the tissue/skin when sutured, knot should be on the opposite side of the edge of the flap.
- Vertical mattress sutures give a good eversion.
- Improper alignment of the wound edges in a curved or lengthy wounds can be prevented by placing the key sutures at salient points which are identified by holding the edges taut using skin hooks or marking corresponding points on each edge to have proper adjustment and to prevent distortion.
- Wound tension should be distributed equally.
- Optimum tension at suture line will not cause blanching of the skin and will only leave thin/least suture mark whereas more tension with abnormally tight suture will blanch the skin causing obvious suture mark.
- Least tissue trauma, atraumatic handling, optimum precision are the need.
- Suturing and knotting is an art; a craft; is a fine work.
- Slow, precise, first bite should be careful and best bite; rapid, clumsy bite is not a good bite; one should avoid repetition.
- Matching landmarks on either sides of the wound should be identified properly.
- Suturing is easier with multifilament suture material like silk than monofilament suture material. Silk has got best handling ability, knot holding property, least memory. Suture insertion and passage through tissues is easier with silk.

Different Knot Tying Techniques

Hand Knot Tying

Two hands and single hand techniques are used. Two hands technique is ideal. *Aberdeen hand knot* is also used to end the continuous suture.

Two hands technique is commonly used. It is done using left hand in right hander; end of the thread/suture material is held between thumb and index finger of left hand; this part of the thread will pass behind the little finger of left hand, encircling it, and coming forward towards between thumb and index finger. Opposite end of the thread which is held in right hand is looped in front across middle finger; middle finger stretching and holding this right hand loop will be flexed at the distal interphalangeal joint and looped around the left hand thread end to create first knot which is held between apposed middle and ring fingers. These two fingers with the thread are pulled towards left to release the knot; knot is squared by directing the left hand towards the opposite side; knot is tightened by gentle push using pulp of left index finger. Further two knots are also placed similarly **(Figs 3-53 and 3-54A to D)**.

Single hand technique is done using left hand index finger. Thread is held similarly but between left thumb and left middle finger; looping is done using left index finger. This method is used whenever thread is small or there is less space in the area. It is little cumbersome to do compared to two hands technique **(Figs 3-55A to H)**.

Two hand technique and single hand is also done in another method: With the left hand between thumb and index finger one end of the thread is held (held proximal to the pulp these two fingers) with loop coming in front from below; other end of the thread holding in right hand is passed across index finger of left hand coming from behind up and forward close to the other end of the thread in left hand; apposed pulps of the thumb and index finger is looped around it and left hand thread tip is passed between these two finger pulps to achieve the



Figs 3-53A to I: Hand knotting using two hands technique.



Figs 3-54A to D: Two hands technique use and placing surgeon's knot with two loops/throws in the knot with squaring.

knot. Further knots are repeated similarly. Surgical knots can also be placed. Knots can be placed in similar way by single hand technique **(Figs 3-56A to S)**.

Aberdeen knot is used in continuous sutures at the end. Thread end is passed through the loop created in earlier last bite/turn; end is passed through this loop to create a new loop; once it is repeated 4-5 times thread end is pulled firmly tightly to tighten the knot. It is used while closing linea alba/rectus sheath using nonabsorbable continuous sutures **(Figs 3-57A to M)**.

Instrument Knot Tying

This is the basic essentiality for surgery. Different types of knot tying are there. Needle holder is held with one hand; long limb side of the suture is held with other hand; instrument (needle holder) is looped (throws) around the suture usually twice for surgical knot (first knot ideally should be *surgical knot*–means two loops are taken); instrument is crossed to opposite side to square the knot and gently knot is tightened; tightening of the knot should be adequate enough means neither too tight to strangulate the tissue nor too loose so as to create a gap; this first knot is *essentially the knot* in knotting; gentle traction should be held to the strand to avoid loosening of the first knot; two ends of the suture should be pulled in opposite direction with equal gentle traction. Second knot is taken as a single loop which is usually taken from behind the suture material (opposite direction and squared in opposite direction) and is tightened; third knot is again single loop (or often double loop like surgeon's knot) taken from front of the suture material (alike first knot single or double loop) and is tightened. One has to remember that usually three firm proper knots are sufficient. It is always considered that even though first knot is the holding knot total two knots (only one additional knot) are *insufficient* and *so three knots* are a must **(Figs 3-58A to K)**.

Only in suture material like polypropylene which has highest *memory* (recoiling tendency and so poor knot holding ability) five knots are put. Any further knots put will not help in strengthening the knot further; so it is waste of energy by the surgeon and unnecessary creating bunch in the knot. After placing first knot it is always better to fix the knot with surgeon's index finger to confirm the adequacy of tightness of the knot **(Figs 3-59A to H)**.

Instrumental knotting is more precise than hand knotting; as it creates optimum regulated tension at the suture line; and knot guidance and placement is better with instrument.

Laparoscopic Knot Tying

Problems with laparoscopic suturing are–lack of tissue perception, depth; limitation of movement of the instruments; difficulty in suturing and knotting inside; restricted space of working; need for high skill level by the laparoscopic surgeon.

Prerequisites for laparoscopic suturing

- Perfect health–mentally and physically.
- Hand-eye coordination.
- Visual perception, ability to concentrate and dedication, determination.
- Precision, proper camera operator.
- Learning curve, repetitive training, motivation, discipline, willpower.
- Proper instruments and their usage.
- Triangulation of two working instruments are important.

Types of Laparoscopic Suturing/Knotting

(A) *Intracorporeal suturing and knotting*–It is technically demanding one. Fine needle with suture is used. *Ski needle* with rounded curved tip and triangular straight shaft is used. Needle is held at triangular shaft so that needle will not swivel. *Dundee 'Ski' needle* with flattened proximal cross section instead of triangular makes improved locking and fixation of needle into needle holder without much difficulty, which makes positioning of the needle easier **(Fig. 3-60)**. Standard curved needles are also commonly used but with swiveling problem. Polyfilament, coloured (black or fluorescent white), and 3 zero suture materials are ideal. Polyfilament material holds well with easy knotting ability.

Excellent needle holder is an asset for intracorporeal knotting. Semm, Wolf, Ethicon, Cook, MBG are different needle holders available. Szabo and Berci needle holder gives 360° rotation with precise manoeuvring. *Self righting needle holder* with a notch inside allowing self positioning of the needle is also available.

Needle with suture material is placed inside the peritoneal cavity through–5 mm reducer cross 10 mm port; direct percutaneous (only straight needle); Reich method through 5 mm port (5 mm port is removed, gently needle with 5 mm needle holder is directly pushed along the track of the removed port into the peritoneal cavity under laparoscope guidance and 5 mm port is again slid into the abdominal cavity across needle holder); through 10 mm port directly. Needle entangling in the tissues, needle cutting, separation of the suture material from the needle, injury to the vital organs are the problems which may occur while introducing the needle.

Entrance bite and exit bite in the tissue should be taken separately. Knot is formed by either through 'C' loop or 'O' loop. *Square knot, square slip knot* (square knot untumbled to form slip knot), ligature slip knot, surgeon's knot are placed. Jamming slip



Figs 3-55A to H: Making knot with single hand technique. Even though surgeon should learn this technique as it is used when suture ends are short. It is not necessary to use this technique for fascination purpose. It is always better to use two hands technique which is more comfortable.

knot, Aberdeen knot (terminal knot) are other knots which can be placed. *Intracorporeal twist technique* is another method used in laparoscopic suturing. One end of the suture is rotated over the needle holder with suture tip holding for three loops; other grasper/ needle holder holding other end of the suture is released to hold tip of the looped suture material; needle holder of the looped suture releases the tip of the looped suture and is allowed to hold and create a loop of the free other end of the suture which after releasing the loop across this loop forms a knot; further pull releases the loop achieving a firm knot **(Figs 3-61 to 3-63)**.

Jamming slip knot is a starter knot used in continuous suturing. After double looping through needle holder, little away from the end, the suture is grasped to form a loop to which knot is slipped and further knots tighten it. This knot near the end of the suture material acts as a first knot of the continuous suture which avoids intracorporeal knotting and hastens the suturing **(Fig. 3-63)**.

B. *Extracorporeal knotting:* It is commonly advocated in laparoscopy as it is convenient, safe and effective. Long 90 cm suture is used; needle with suture may be passed through tissue inside under laparoscopic vision and brought out through the 5 mm/10 mm port. Similarly ligature also can be looped around the specific structure and ends of the suture are brought out for knotting. After placing extracorporeal knotting, it is pushed to the required site through a knot pusher. Additional knots similarly can be placed. Different types of extracorporeal knots are–

1. *Roeder's knot* (By Roeder used for tonsillectomy in 1918): Semm used this in laparoscopy. Catgut is commonly used. Silk also can be used. Initial half knot (single loop) →3½ turns over the loop →second half knot →pushing towards first loop →tightening



Figs 3-56A to I



Figs 3-56J to S

Figs 3-56A to S: Two hands technique hands knotting using mainly thumb and index finger; here apposed thumb and index fingers move across loop to create knot.



Figs 3-57A to I



Figs 3-57J to M

Figs 3-57A to M: Photos showing how exactly Aberdeen knot is placed. Usually used at the end of linea alba suturing.



Figs 3-58A to K: Placing reef knot using needle holder instrument. Knot should be squared for proper secure knot to get.



Figs 3-59A to H: Instrumental placing of surgeon's knot (double throw of first loop with squaring)



Fig. 3-60: Dundee Ski needle.



Fig. 3-61: Square knot untumbled to form slip knot–square slip knot. It has got ability to secure the knot in difficult places. It can be placed using monofilament suture material. It maintains adequate tissue tension. It is pushed in place by sliding.

creates good Roeder's knot which can be slid over the suture material easily →pushed after loop is passed around the structure like base of appendix using knot pusher **(Fig. 3-64)**.

2. *Melzer knot* (Melzer Germany 1991): It is modification of Roeder's knot. Here double initial half knot (double loop) →3½ turn over the limbs of the loop →double second half knot →staking of turns and pushing to tighten the knot →ready for use with a loop. It is used with PDS and is *stronger* than Roeder's knot **(Fig. 3-65)**.
3. *Tayside knot*: Initial half knot →4½ turn loop on standing part →tail is passed through first loop →tail is again passed through the first loop →tail is pulled to tighten the knot and ready for use. It is modified Fisherman's utility knot (Scotland) **(Fig. 3-66)**.
4. *Duncan slip knot:* Half hitch is added to the loop after 3½ turn **(Fig. 3-67)**.
5. *Texas Endosurgery Institute Knot (TEI Knot):* It is useful for many suture materials like PDS but it is difficult to do and several methods are present.

C. *Pre-formed slip knots*–Endoloops. It is prelooped sutures which are commonly used in appendicectomy, cholecystectomy or ligating blood vessels. Chromic catgut is the material commonly used here. It is introduced and placed using 5 mm endoloop pusher. Disposable pushers with pre-knotted endoloops are available. Metal knot pusher is not disposable (reusable) with a Roeder's knot.



Figs 3-62A to G: Intracorporeal twist knotting.



Fig. 3-63: Jamming slip knot.


Shorter end
Longer end

Fig. 3-66: Tayside knot.


Shorter tail end
Longer standing end

Fig. 3-64: Roeder's knot.



Fig. 3-65: Melzer knot.



Fig. 3-67: Duncan slip knot.

Different Knots

1. *Reef knot* with squaring is ideal knot and commonly used. Correct squaring is essential. If it is not done knot gets spoiled and loosened **(Fig. 3-68)**.
2. *Granny knot* is not safe when second loop is taken from the same side **(Fig. 3-69)**.
3. *Surgeon's knot* with one extra loop in the first knot with squaring. It prevents loosening and slipping of the knot and maintains strength and tension required with the tissue and so becomes a more secure knot **(Figs 3-70A and B)**.
4. *Modified fisherman's knot:* First knot has got three loops/throws with surgeon's knot with squaring; second knot is squared single loop; third knot is squared double throw surgeon's knot **(Fig. 3-72)**.
5. *Triple modified reef knot:* It is the reef with three knots instead of two. It is actually the commonly used knot **(Fig. 3-71)**.

Dog-Ear

After excision of a circular lesion while closing the wound, the ends of the wound gets elevated like pronouncement called as 'dog-ear.' If this is sutured as it is, it causes a prominence resulting in unsatisfactory cosmetic scar. Such wound is sutured until dog ear is formed; later dog-ear is excised with lengthening of the wound; suturing continued to create lengthier clean sutured wound eventually leading into a scar **(Fig. 3-73)**.

Principles in knotting

- Optimum grip; optimum control; optimum precision–is essential.
- Hold the suture with needle holder only during knotting (not in other time).
- Knot must be as small as possible.
- In skin after knotting ends of interrupted sutures are cut neither too short nor too long; usually 1 cm of length kept is equivalent to gap between sutures. In deeper plane it should be kept short.
- One should avoid friction between strands while knotting. This can be minimised by holding sutures loosely; not tightly like a string. If so it will cause sawing effect and reduces the strength of the suture.
- Holding the suture with excessive tension will break the suture and traumatise the tissues. Folding with minimum tension allows free movement of the suture for finer suturing.
- First knot is the important knot; after placing first knot gentle traction to the strand is needed to avoid loosening of the first knot. Two ends of the suture should be pulled in opposite direction with equal gentle traction.
- Knotting is for proper apposition and approximation of the tissues; not for strangulation; so too tight suture should be avoided. Optimum tension should be used. It comes to a surgeon by repeated practice and experience. Surgeon should adjust his stance and position to place the knot properly.
- All knots ideally should be squared for stability by pulling in opposite direction.
- Friable edges of the wound cause poor knot holding and placement.


Pulling towards left side is wrong
Pulling towards right side is correct
Improper direction–wrong knot
Proper direction–correct knot

Fig. 3-68: Reef knot.



Fig. 3-69: Granny knot. It is not commonly used.



Figs 3-70A and B: Typical surgeon's knot is taking two loops/throws in first knot with squaring. It holds well without slippage.



Fig. 3-71: Reef with three knots is used here which is more secure.



Fig. 3-72: Squaring of knot should be done to make it secure, especially first throw/knot should be squared.



Fig. 3-73: Dog-ear often develops at the end of the wound. It is rectified by cutting excess skin and suturing creating a lengthy scar.

SUTURE REMOVAL

Suture cutting scissor is used with sharp tips. Suture is cut on one side deep to the knot; it is pulled using forceps *towards the wound line* so that to prevent entering the exposed part of the suture to get into the deeper part of suture line during removal and also to prevent wound dehiscence. Cut suture if pulled away from the wound line, chances of wound dehiscence is likely. Surgeon should use wrist and finger movements. B P handle with *11 number pointed sharp blade* also can be used. Patient should be always in lying down position. Suture removal is also an art **(Figs 3-74A to E)**.

HAEMOSTASIS

Control of bleeding is essential part of the surgical technique. Small oozing gets controlled on its own by natural haemostatic methods. All other bleedings may be small or large vessel bleeding needs proper secure control before further proceeding with surgery. There are many methods to control bleeding.


No 11 blade: Straight pointing cutting scissors
A
Pull towards the wound/scar
B
No 11 blade: Suture removal
C
D
E

Figs 3-74A to E: Suture removal is an art. It is done with all aseptic precautions. Suture is cut behind the knot and suture holding at the knot using dissecting forceps or haemostat, it is pulled towards the wound so that wound dehiscence will not occur and outer part of the suture material is not dragged inside the track during removal to reduce the possible chances of infection along the track.

Gauze/Mop Pack

Wet gauze packed over the diffuse area with pressure over it controls the diffuse bleeding. Size of the gauze needed is decided based on the area of ooze. Small gauze/large gauze/mop/mops can be used. Small saline wet gauze is used in small area like raising thyroid flap. Large gauze may be used in wider area with fat disposition like raising flaps in mastectomy. Mops are used in the abdomen and in brisk torrential bleeding like liver injury. Often mops are kept in place to develop adequate tamponade and haemostasis and are removed in 24–48 hours once patient is well stabilised. During surgery when sudden bleeding occurs by inadvertent cutting of the vessel, hurried applying of the haemostat should be avoided as it is blind application. Instead it is better to pack the area with mop with firm pressure, after few minutes mop is removed gently to identify the point of bleeder which is held using a haemostat **(Fig. 3-75)**. Suction device should be used to keep field clean and clear to identify the severity and point of bleeding. *Note:* Mopping is the essential part of the surgery. *Rubbing* over the tissues using mop *should not* be done.

Use of Haemostat

Usually medium sized curved haemostat is used. In the depth large sized artery forceps can be used. Occasionally right angle forceps also is used. Mosquito forceps is also used for small bleeders like in head, face and neck surgery. Commonly bleeder should be identified precisely and caught with the artery forceps like a point. When identifying is difficult due to retraction or presence of fat, convex part of the artery forceps is used to hold the tissue with the bleeder. Again unnecessary holding of extra tissues should be avoided in this method as it may lead into deeper tissue destruction. After applying the haemostat it should be confirmed that bleeding has stopped by mopping and suction. While placing the ligature around the haemostat tip of the haemostat should be pointing forward (assistant should hold the haemostat gently and carefully and surgeon will place the ligature). Always make sure that haemostat is not catching the vital adjacent structure which may be incorporated in ligature **(Figs 3-76A to F)**.



Fig. 3-75: Packing is common method to control bleeding temporarily. Small gauze, large gauze or mop/mops are used depends on the area, depth and severity of bleed.

In scalp bleeding or scalp incision galea should be held with straight or curved artery forceps/haemostat at many points and turned back over the skin to stop bleeding.

Bleeding area can be lifted with non-toothed forceps and underneath tissue can be cross clamped with haemostat.

Use of Ligature

Ligation of bleeding vessel is essential in many places. Small vessel is cauterized after holding with haemostat. Wider vessel should be ligated. Polyglycolic acid 2 zero or 3 zero can be used. Silk also can be used as it holds well with good strength. Once surgeon places the first knot, assistant *gently* releases the haemostat and removes it. Haemostat should not be released suddenly.

Mounted tie is used for small or medium vein ligation. Here two ligatures are placed with 0.5or 1cm gap around the vein using two haemostats and tied securely. Vein in between is cut safely. If it is artery two ligatures are placed proximally and one ligature distally before cutting in between. Larger vein ligation also needs double ligation proximally **(Fig. 3-77)**.

Ligating the larger vessel like left gastric artery, branches of mesenteric vessel and superior thyroid artery needs additional care as slippage in reality is a definitive risk. In such occasions ideal method could be to dissect the vessel from adjacent tissue and fat for 1.5 cm (*skeletonisation of the vessel*) length and ligating it. Ligation of such vessel needs special care. Initially vessel is cross clamped using *Mixter/Miegster* clamp. Using long haemostat lengthy ligature (silk or polyglycolic acid) is passed around the Mixter clamp and tied using hand knot. One more ligature is placed again 2 mm proximal to earlier ligature. Stump of the vessel should be around 1 cm beyond the distal ligature **(Fig. 3-78)**.

Often in resection of the tissue like gastrectomy, mastectomy, colectomy, intestinal resection, main vessel (gastric artery/gastroepiploic artery/mesenteric vessel branch) is isolated and dissected for about 2 cm length and ligature is passed using Mixter clamp as a feeding ligature and tied. Proximal two ligatures are placed at 2 mm apart. Distal ligature is placed away at 1.5 cm gap. Vessel is cut using curved scissor or with no. 15 blade (part behind the vessel should be guarded by placing flat surface of the dissecting forceps or any other instrument) leaving 1 cm vessel proximally and 0.5 cm vessel distally. Two firm proper proximal ligatures are sufficient even though many surgeons have got the habit of placing 3 or more proximal ligatures. Only one proximal ligature is technically sufficient but is not advisable; so two proximal ligatures are probably ideal **(Fig. 3-79)**.

Transfixation Ligature

Transfixation prevents the slippage of the suture. It is used in big vessel ligation or when oozing tissues are held and ligated. Gastric vessels, mesenteric branches, in obese patients where ligature may not hold, in vessels in the depth–are the indications. It is better to use transfixation suture whenever surgeon feels that just ligature may not be sufficient to secure.

Needle with the suture is passed underneath the haemostat over middle of the grasped tissue, first knot encircles the half of the tissue on one side; suture is looped around on the opposite side of the grasped tissue and knot is placed. Once such *figure of eight stitch* is completed then only haemostat is released by the assistant. Further knots are placed over it. Still safety of the ligature can be achieved by passing the needle *second time* underneath the tissue again before knotting **(Fig. 3-80)**.


A
B
C
Ligature
Bleeding vessel
Haemostat
D
E
F
Ligature
Haemostat
Tissue with bleeder

Figs 3-76A to F: Haemostat is used in two ways. Holding is done on the tip when bleeder point is visualised and is ligated. If tissue is bleeding, tissue is held over the convex part of the haemostat and ligated.


Ligature proximal side (2 in number)
1 cm
0.5 cm
Specimen side

Fig. 3-77: Vessel is cut between knots with adequate gap in between to prevent knot slippage. Ideally proximal two ligations and distal one ligation are needed.

Underrunning of the Tissue

It is not possible to catch the area and control the bleeding if bleeding point is not identified and is not pointed. Any blind struggle to hold the area with haemostat will aggravate the bleeding without achieving any thing. In such occasion it is wiser to place continuous locking sutures in tissue bed where bleeding occurs using 3 zero polyglycolic acid/silk/polypropylene sutures. Repeated mopping and suction of the area is essential. However surgeon should take care and be aware of presence of some major vessels and vital structures in that deeper plane. Depth control in these sutures is also important. Usually bleeding stops by placing few locking sutures. Locked loops should be held by the surgeon himself so that tearing through the tissues by the suture material is avoided and gentle traction to lift the tissue to facilitate further bites is achieved.

Diathermy

Diathermy is most commonly used tool for haemostasis at present. Monopolar cautery or bipolar cautery is used for haemostasis. It is high density current which is made to pass into the tissue in need (target tissue) to cut or control bleeding (coagulate).

In monopolar cautery current passes through a grounding electrode kept behind thigh/buttock of the patient. Monopolar device delivers two types current–cutting and coagulation. *Cutting* is continuous, high frequency low voltage current causing rapid heating of tissue leading into tissue disintegration and cutting. Haemostasis is not adequate


Mixter right angled clamp
Long ligature
Long artery / haemostat
Tying ligature under clamp
Note:
Guiding the first knot
with index finger to get
a secure knot is always
ideal
Needs two proximal ligatures

Fig. 3-78: In the depth vessel should be dissected first properly. Mixter/ Miegster clamp is applied. Ligature is passed underneath using long haemostat. Ligature is placed by firm knot which is directed using index finger.



Fig. 3-79: Once adequate length of the vessel is dissected properly from surrounding tissues, using Mixter clamp ligatures are placed–two proximally; one distally. Vessel in cut between proximal and distal ligatures.


Figure of eight transfixation
First needle bite
Twice needle bite transfixation
Single needle bite
Second needle bite

Fig. 3-80: Transfixation suture. It is done by two methods. Single bite, figure of eight suture or double bite transfixation is used. Both hold knots in place with minimal chance for slippage.

in cutting cautery. *Coagulation* is pulsed wave, low frequency, high voltage current causing slow tissue heating, protein coagulation and vessel sealing. Coagulation in *fat tissue causes more charring* as fat is poor conductor of electricity, destruction and more prone for infection of the wound. Coagulation cautery may cause lateral heat significant enough to cause heat injury to adjacent vital structure/tissue. It is often dangerous in bowel, bile duct, major vessels. Burn injury due to default in earthing plate can be dangerous. Proper earthing and connections should be checked by surgeon himself. It is legally important also. Bleeding point is grasped using specialised fine non-toothed forceps called as cautery forceps. Cautery blade is touched to the instrument and cautery peddle is pressed to achieve desired effect of coagulation. Tip of cautery blade can be touched directly over the oozing tissue area to achieve haemostasis. Use of cautery should be avoided in epidermis and dermis as it causes severe thermal injury. Vessels more than 2 mm diameter cannot be cauterised. If attempted it may cause more bleeding; or may temporarily seal the vessel but later disruption can occur to cause re bleeding in postoperative period.

In bipolar cautery, current passes from one blade of the bipolar forceps across the grasped tissue in between towards other blade directly without earthing. It causes heating only in between blades of the bipolar forceps. Lateral heat and adjacent tissue injury is less. It is much safer to use bipolar cautery to prevent hazardous injury to adjacent vital structures (bowel, CBD, IVC, Major artery/vein). It causes coaptive coagulation. It is not used for cutting. It is very useful in laparoscopic surgery. Earthing plate is not needed in bipolar cautery. Bipolar coagulation is slower compared to monopolar coagulation. It often checks the surgeon's patience.

Ligasure/Ligaseal/Ultrasonic Shears/Laser/Harmonic Scalpel (Focus)

These are the different energy sources presently available to control bleeding which coagulate and seal wider vessels even up to 5-7 mm diameter. It is very useful in hysterectomy, colectomy, gastrectomy, resections, pancreatic surgery, thyroidectomy and advanced laparoscopic surgeries.

Haemostatic Clips

Haemoclips are applied directly over the vessel circumferentially. It is useful in thyroidectomy, gastrectomy, colectomy, oesophagectomy, etc. It should not be applied blindly without visualising the vessel/bleeding vessel. Improper application may cause uncontrolled bleeding. Before applying it direction of the clip, structure underneath should be assessed properly. It may injure adjacent structures, or lacerate the vessel clipped if not placed properly. Precise gentle placement assures the haemostasis and speeds the surgery. Haemoclips are used in open as well as laparoscopic surgery.

Tourniquets

Tourniquet means to turn (Greek). It is used to cut off the blood supply to a limb temporarily so that a bloodless field is created while performing the surgery. Limb should be exsanguinated before applying/inflating the tourniquet. It is done using a bandage or pressurised Rhys–Davis exsanguinator. A tourniquet is applied in midthigh above the elbow in upper limb. It should not be closer to joints. It is not applied over the forearm or leg. It is applied over layers of gauze/cotton, but not over bare skin. Pressure used in upper limb is 250 mmHg; in lower limb is 300 mmHg. In general 50 mm Hg above the systolic pressure of the patient used in many places, even though it may be inadequate as fluctuation in blood pressure can occur during procedure (in children it is 150 mmHg for upper limb and 250 mmHg for lower limb). *Uses* - To attain bloodless field in limb surgeries of upper and lower limbs, orthopaedic surgeries, soft tissue tumors, amputations. It is used (rubber tourniquet) to get assess to veins for IV injections and IV sampling. Tourniquet is used in diagnostic tests for varicose veins, purpura (ITP), etc. It is used as a first aid in bleeding conditions of limbs, snake bite (it is controversial). Tourniquets are also often used for small procedures in fingers and toes. *Types:* (1)

Rubber tourniquet - Simple red rubber catheter is used for drawing blood, to have access to veins. (2) *Pneumatic tourniquet* - Used in limbs, will give the arterial pressure and also acts as a tourniquet. (Sphygmomanometer cuff is simpler and easily available type). (3) Esmarch rubber *elastic bandage tourniquet* **(Fig. 3-81)**. (4) Specialised sophisticated tourniquets are available which gauge pressure, timing accurately **(Figs 3-82A and B)**. *Contraindications:* In all peripheral vascular diseases and atherosclerosis; infection; DVT; crush injuries; sickle cell disease. *Complications:* Crushing effect on muscles in thigh may lead on to crush syndrome; tourniquet palsy (radial nerve) in upper limb; infection; improper application of tourniquet will lead to more bleeding; forgetting the removal of tourniquet or using more time to release may compromise the blood supply of the limb leading to severe ischaemia and gangrene.



Fig. 3-81: Esmarch rubber tourniquet.



Figs 3-82A and B: Automatic gauged pressure tourniquet.

Note: Tourniquet time for upper limb is one hour and for lower limb is two hours.

Control of Sudden Severe Bleeding during Surgery

It is often encountered problem in major surgery like pancreatic surgery, nephrectomy, splenectomy, oesophagectomy, biliary surgeries, surgeries in neck, and surgeries for malignancies. Methods used to control haemorrhage temporarily are–(1) *Finger pressure* and packing: Applying pressure directly over the site is the ideal method as immediate pressure instead of struggling to catch the bleeder using haemostat. *Pringle manoeuvre* by holding the foramen Winslow between thumb and fingers is one of the methods to control bleeding in liver. Iced sterile saline pack can be used in kidneys to reduce the metabolic activity and so to increase the compression period. (2) Usage of clamps carefully with proper suctioning: Satinsky clamp and other vascular clamps are soft and stable which can be applied effectively across a bleeding major vessel like portal vein/IVC/major artery. (3) Proximal and distal control using vascular clamps or umbilical tapes in major vessels like aorta. (4) Extend the incision to expose the area adequately. Visualisation, suction should be optimized. Adequate number of blood should be arranged for transfusion. Needed assistants may be increased. If felt surgeon should not hesitate to call another experienced surgeon for help. (5) Permanent control of bleeding by vascular suturing using fine 4 zero polypropylene sutures or other definitive procedures. (6) Monitoring the patient for DIC, coagulation changes, further bleeding, sepsis, cardiac arrest, ARDS, respiratory problems, metabolic consequences.

Other Methods

Topical agents–They are collagen or cellulose matrix which stimulates clot formation over the oozing surface. They also


SURGICEL* W1913T
Absorbable Haemostat
(OXIDIZED REGENERATED CELLULOSE)
Johnson-Johnson
Wound Management
CE 0086 STERILE R
5cm x 7.5cm
NOT FOR EXPORT TO USA
Production site: Ethicon SARL, 2000 Neuchatel, CH
©2005 Johnson&Johnson Medical Ltd,
Gargrave, North Yorkshire, BD23 3RX, UK
LGN 016520-C

Fig. 3-83: Surgicel.

prevent disruption of clot already formed. *Microfibrillar collagen powder* (Avitene) can be sprinkled over bleeding surface through forceps. It is used when oozing surface is irregular. But it is costly. *Oxidized cellulose* (surgicel) is placed over the bleeding area **(Fig. 3-83)**. *Gelatin* sponge, topical thrombin, gelatin matrices (floseal), topical cryoprecipitate, topical EACA (Epsilon amino caproic acid), alginate materials, temporalis muscle patch (neurosurgery) are other materials used. *Bone wax* is bees wax with almond oil; it is used in bleeding bone marrow.

Endoscopic control of haemorrhage using laser, sclerotherapy, clips, etc. are tried. Angiogram and therapeutic embolisation using coils, gel foam, clot is used in bleeding duodenal ulcer, colonic bleeding.

Endostaplers and endoclips are used in laparoscopic surgery safely.



Figs 3-84A and B: Gel Form.



Fig. 3-85: Cutting the end of the knot.



Figs 3-86A and B: Clip removal in skin stapling.

Chapter

4

Day Care Surgery, Ambulatory Surgery, Outpatient Surgery

DEFINITION

It is a confusing entity with so many words with difficult understanding. It is fast developing and so equally important.

Day care surgery or ambulatory surgery is discharge within 23 hours of admission (USA); or surgery done without night stay (UK). It is often also called as *ambulatory surgery/minimal stay surgery.*

Even though all are similar technical meanings are little different.

Day care surgery means patient is fit to return home in 23 hours usually with or without overnight stay. *Ambulatory surgery means* patient recovers after surgery and returns home in the same evening. *Office surgery means* patient recovers from surgery and returns home in few hours. *Outpatient surgery* is different from day care surgery in that patient is not previously fully assessed in outpatient surgery. Only minor procedures are done in this. Patient is not admitted in out patient surgery. In day care and ambulatory surgery patient is admitted in the hospital.

Day care surgery has been defined by *the Royal College of Surgeons* as when the surgical day case patient is admitted for investigation or operation on a planned non-resident basis and who do not require facilities for recovery. This definition excludes upper and lower GI endoscopies, outpatient procedures such as flexible cystoscopy, and minor superficial surgery under local anaesthetic, none of which require full day case facilities for recovery.

It is a *unique upcoming field* in surgery wherein surgeon, general practitioner, nurse at care centre, anaesthetist work in hand so that hospital stay and cost is reduced. Patient who has prepared prior by all evaluation methods comes to the hospital, undergoes surgery/procedure, gets discharged at evening.

The cases are usually carried out under local, regional or general anaesthesia (monitored anaesthesia). Facilities and standards of care in the day care surgical unit must be alike to those provided for inpatient. The patient is to be formally admitted to day care unit, full work up and documentation is done and there should be facilities to observe the patient for 12 hours.

INTRODUCTION

In 19th century (1903) Glasgow surgeon James Nicoll did many day care surgeries in children. Dr RM Waters of Sioux City of Iowa in 1918 did first day care surgery under general anaesthesia. Dudley Street ambulatory surgical centre started in Providence Rhode Island in 1968 by Charles Hill. Society for Ambulatory Anaesthesia has established in 1984 for safety and undertaking of ambulatory surgery.

Ambulatory surgical set up may be:

- Hospital integrated.
- Hospital separated but accessible to the hospital.
- Satellite ambulatory unit.
- Free standing unit–totally independent.
- Office based unit–mainly in USA (20 % surgeries) but are said to be inadequately equipped.

Levels of ambulatory surgery are:

Minor (LA); Major (GA/Epidural); Inpatient ambulatory surgery.

Assessment done prior to surgery are by—*pre-anaesthetic clinics* with system evaluations; *health questionnaire* by surgeon and physician; *telephonic interviews*.

Patient selection, patient information, patient acceptance are important parts in day care surgery.

Procedures done in day care surgery set up are:

Excision of deep swellings; lymph node excision biopsy; therapeutic endoscopies; all procedures for haemorrhoids; hydrocele surgery; circumcision; hernia surgery; gynaecologic procedures; minor amputations; orthopaedic procedures like reduction, minor plating and screwing of bones, arthroscopies, surgeries of peripheral joints, surgeries for carpal tunnel syndrome, ear surgeries, small laryngeal and nasal surgeries, many ophthalmic surgeries like cataract surgeries, laser, etc.

Inguinal hernia, femoral hernia, small umbilical hernia, excision of skin tumours, many plastic surgeries are done in day care surgery.

Basic requirements are–in house anaesthesiologist; recovery room; theatre and recovery room/ward nurse; all essential surgical set up including monitor, ventilator.

The procedures that can be undertaken as day care surgical procedures are as per the BADS or Audit Commission of UK which came up with 'Basket of 20' surgical procedures to provide a more consistent measure of performance. The 25 procedures included as found updated in the report of the Audit Commission of UK, 2000 are as follows: (Updated report, 2001) —

1. Orchidopexy. 2. Circumcision. 3. Inguinal hernia repair. 4. Excision of breast lump. 5. Anal fissure dilatation or excision.

6. Haemorrhoidectomy. 7. Laparoscopic cholecystectomy. 8. Varicose vein stripping or ligation. 9. Transurethral resection of bladder tumour. 10. Excision of Dupuytren's contracture. 11. Carpal tunnel decompression. 12. Excision of ganglion. 13. Arthroscopy. 14. Bunion operations. 15. Removal of metalware. 16. Extraction of cataract with/without implant. 17. Correction of squint. 18. Myringotomy. 19. Tonsillectomy. 20. Submucous resection. 21. Reduction of nasal fracture. 22. Operation for bat ears. 23. Dilatation and curettage/hysteroscopy. 24. Laparoscopy. 25. Termination of Pregnancy. *The British Association of Day Surgery (BADS)* has recommended inclusion of another fifty procedures under the name of Trolley of procedures.

Selection criteria are–

American Society for Anaesthesiologist (ASA) category I and II patients can be taken up for day care surgery. ASA III/or beyond are contraindicated for day care surgery.

ASA (American Society of Anesthesiologists) grading of the patient for surgery

1. Normal individual
2. Mild–moderate systemic disease-Diabetes and hypertension under control
3. Severe systemic disease–uncontrolled diabetes and hypertension
4. Incapacitating systemic disease
5. Moribund status

Class E—Emergency surgery

Exclusion criteria for day care surgery are

- ASA grade beyond III or more.
- Obesity (BMT>35).
- Hypertension–not controlled.
- Surgery requiring more than one hour.
- Surgery with anticipation of major fluid/blood loss or needs postoperative critical care.
- Preterm babies and infants less than 3 month's age.
- Patient living in far and not easily reachable or able transport easily.
- Unstable psychiatric illness. If proper caregiver is not available.
- Uncontrolled diabetes, alcohol abuse, COPD, severe asthma, epilepsy.
- Pregnancy.

Final evaluation is done just prior to the date of surgical procedure. Patient should be assessed by surgeon, anaesthesiologist, and a physician. Once evaluation is done surgery should be undertaken ideally within 2 weeks.

Haematocrit, ECG, renal function tests–Blood urea and serum creatinine, blood sugar level, chest X-ray are to be taken. Other relevant investigations are done depends on specific diseases patient is having or suspected like cardiac (Echocardiography, cardiologist opinion) and respiratory diseases.

Patient should be asked to stop smoking at least 2 weeks prior to surgery.

Type anaesthesia should be decided by surgeon and in house anesthesiologist. Local anaesthesia is commonly used at present for small procedure like tapping, excisions, circumcision and hydrocele. Open inguinal or femoral hernia surgery is commonly done at present under local anaesthesia unless hernia is irreducible/large or patient is contraindicated for local anaesthesia. Laryngeal mask airway (LMA) or combined oropharyngeal airway are commonly used. Minimal or no premedication is the usual practice in day care surgery.

Laparoscopic hernia repair (TEP/TAPP) is also can be done under day care surgery but under general anaesthesia.

Proper written consent for anaesthesia, procedure, day care surgery with consent for possible needed admission if at all due to some complications should be taken.

Spinal or epidural anaesthesia also can be used in many procedures.

List of day care surgery for the day should be decided previous day after collecting clear information from the patient about him being coming for surgery without fail. Some inadvertent reasons if patient fails to turn up, then person on waiting list can be called upon for surgery if he is prepared and ready to do so.

TECHNIQUE

Technique is same as like any theatres. There is no deviation in principles and methodology of the procedure.

Sutures can be interrupted or absorbable subcuticular. Dressings are placed. Patient is asked to remove dressing in 3 days and is allowed to take bath normally in 3 days.

Ward nurse will monitor the patient properly about the recovery and should document it. Once she is sure of proper recovery then patient is discharged with proper intimation about oral drugs, diet, and rest in the house, to call and attend immediately in dire problems. Usually patient is discharged in 6 hours if procedure is done under local anaesthesia; in 8-12 hours if procedure is done under general/epidural/spinal anaesthesia. Clear cut discharge criteria should be followed and should be decided by anaesthesiologists and surgeons. *Aldrete scoring system* is used for fitness for discharge and safe transfer of the patient to the house.

Care Once at Home

This is equally important as patient has undergone surgery just few hours back. It is mainly be the patient, family members.

Patient should take rest that date (night) once he reaches home; diet should be initially liquid and later normal diet. Patient should be informed about one or two episodes of possible development of vomiting postoperatively due to anaesthesia which usually subsides eventually.

Informed caregiver mostly one the close family member is essential part of the day care surgery.

All instructions should be given properly in *a written form* clearly in understanding simple way.

Driving, decisive works, exercises should be avoided for 24 hours.

Any additional instructions should be taken as when needed over the phone by the patient.

Follow up by telephone in 12 hours, 24 hours and 48 hours should be done by the day care center (by nurse or anaesthetist or surgeon) as a mandatory.

Patient should be called for suture removal and if needed postoperative evaluation depends on the condition to which patient undergoes surgery.

General practitioner/family physician of the family/patient should aware of the patient undergoing surgery; he should visit give care to the patient. Extra responsibility comes to general practitioner.

Present Trend for Day Care Surgery

It is rapidly emerging field in surgery–in different specialties also. It *reduces cost*, mental agony to patient and family members. *Minimal hospital stay* makes it acceptable to the patient. 30% (in USA) - 40% (in UK) cost savings occur by day care surgery.

70% surgeries in USA and 60% surgeries in UK are done by day care surgery, and 20% surgeries in India.

Home diet given with care and feeling of away from hospital makes better recovery.

Infection rate comes down drastically in day care surgery because of avoidance of hospital acquired resistant infection.

Day care surgery probably reduces the disability.

Postoperative nausea and vomiting (50%); postoperative pain and postoperative drowsiness/dizziness (50%) are the *common complications* in day care anaesthesia.

But proper selections, proper follow up, immediate reaching facility to the hospital is done as day care procedure in case of emergency mainly *postoperative bleeding*, often vomiting, dehydration due poor intake, pain, discomfort and sedation–are the prerequisite cares.

It is developing field which needs modern anaesthetic and surgical set up with outstanding team and set up.

Alertness; ambulation; analgesia and alimentation–*basis for* day care surgery.

Chapter 5

Instruments

Surgical instruments are essential for any surgery, whether minor or major. All instruments should be sterilized prior to use to prevent infection.

Parts of an instrument (Fig. 5-1)

- Two finger bows for holding
- A ratchet or lock
- A pair of shaft or body
- Joint either box type (with a slot) or pivot (attached by a screw)
- Pair of blades at terminal part



Fig. 5-1: Parts of an instrument.

CHEATLE'S FORCEPS

It is used to pick sterilized articles like instruments and drapes so to avoid touching the instruments while transferring them from one tray/table to other. It is kept dipped in antiseptic solutions like savlon/cidex. It does not have lock. It is heavy metallic forceps with curved blades with serrations. One blade of the proximal handle has got rounded ring for inserting finger and other blade may be having ring or often has got free hook to have proper grip **(Figs 5-2A to C)**.



Figs 5-2A to C: Cheatle's forceps.

SPONGE HOLDING FORCEPS (RAMPLEY'S)

It has got fenestrated, serrated flat round distal end. It is 22.5 cm long; has a ratchet and two long blades **(Figs 5-3A to C)**.

It is used to clean the operative field. Because of the length, the surgeon's hand will not get contaminated while cleaning the patient, it is also used to swab the cavities, to mop the oozing area, to hold gall bladder or cervix or tongue or bowel or stomach during surgeries, for blunt dissections or as ovum forceps. It can also be used to dry the operative field using gauze. It can be used for blunt dissection with a wet firm swab held on the tip in vagotomy, sympathectomy. It can be used as haemostatic with a large gauze at the tip. It is used to hold Hartmann's pouch in open cholecystectomy. It is used to clean the vaginal cavities.



Figs 5-3A to C: Sponge holding forceps—(Rampley's) both curved and straight and also photo of the same.

MAYO'S TOWEL CLIP

It is used to fix drapes in operative field. It is light but strong with small curved blades. Curvature helps to hold entire thickness of drapes firmly and easily. Two sharp teeth one on each blade cross each other but do not approximate (cross action tip) **(Figs 5-4A to C)**.

It is used to fix suction tubes, diathermy wires and laparoscopic cables on operative table.

It is used to fix ribs in flail chest.

It can be used to hold cord in hernia or to hold tongue if specific instruments are not available.

It can be used to hold dental wiring; patella during patellectomy; in faciomaxillary fractures.



Figs 5-4A to C: Mayo's towel clip.

BACKHAUS' TOWEL CLIP

It has got a ratchet catch, curved sharp ends which approximate each other, but do not cross each other (Approximating tip, but no cross action in tip) **(Fig. 5-5)**.

MOYNIHAN'S TETRA TOWEL CLIP/ FORCEPS

It is used to hold the cut edges of the skin incision to the four corners of the draped tetra towels so as to isolate the operative field. Isolation also can be achieved by suturing the drape margins to the subcutaneous tissue at different points or using adhesive plastic drape to skin through which the drape skin incision is made **(Fig. 5-6)**.

DOYEN'S TOWEL CLIP

It is a short instrument with curved ends with sharp points. Handles join at proximal ends. When handles are pressed tips open, when handles are released tips close and firmly grip the towel **(Figs 5-7A and B)**.



Fig. 5-5: Backhaus towel clip.



Fig. 5-6: Moynihan's tetra towel clip –it is with long blades with a curvature with two teeth in each blade (total four).



Figs 5-7A and B: Doyen's towel clips.

Towel clips

- Mayo's—cross action tip; no approximation.
- Backhaus'—approximating tip; no cross action
- Doyen's—tension blades open when pressed and vice versa
- Moynihan's tetra forceps/towel clip to isolate cut edge of the skin incision for isolation; has got two teeth on each blades
- Bull dog towel clip—has got cross section action with tapering points
- Gray's towel clips—not used now.

ARTERY FORCEPS (HAEMOSTAT)

Types (Figs 5-8 and 5-9)

Based on size—

- Small or mosquito artery forceps–*Mosquito forceps* is so called because of its fine tip which can even catch the proboscis of a mosquito.
- Medium sized artery forceps.
- Large artery forceps.



Fig. 5-8: Artery forceps: (a) Straight, (b) Curved, (c) Mosquito (Halsted).



Fig. 5-9: Small sized curved Halsted haemostat–Mosquito artery forceps.

Based on shape—

- Straight artery forceps.
- Curved artery forceps.

Features of artery forceps—

- Distal blades are having transverse serrations which are well apposed.
- Lock in the proximal part.

Uses—

- To catch bleeding points.
- To open the facial planes in different surgeries.
- To pass a ligature and to hold it

- To hold fascia, peritoneum, aponeurosis.
- To hold sutures.
- To drain an abscess like a sinus forceps.
- To hold gauze as pea-nut.
- To crush the base of the appendix.
- To clamp a catheter in between the hinge and ratchet of the haemostat.
- To catch prepuceal skin in circumcision.
- Mosquito forceps *(Halsted)* is used in paediatric surgery/microsurgery/cleft surgery/plastic surgery.

Instrument can also be used to catch arteries/veins/capillaries and so ideally should be called as *haemostat*. But common word used is artery forceps. Haemostat has got serrations on the distal half of the each blade (In pedicle clamp entire blade has got serrations) **(Figs 5-10A to C)**.



Figs 5-10A to C: Artery forceps showing its inner aspect with transverse serrations–Spencer-Wells haemostat/pedicle clamp. It is better called as haemostat. Many named artery forceps/haemostats are available with little different in features. More or less all serve similar functions. Serrations in entire length of the distal blades is traditionally a stout haemostat or pedicle clamp (Spencer-Wells) whereas traditional artery forceps has got serrations only near the tip/distal half of the inner blade. There is no need to remember such confusing entities even though these are facts.

Medium sized, curved half serrated haemostat, called as *Kelly's artery forceps* **(Figs 5-11 and 5-12)**.



Fig. 5-11: Kelly's artery forceps–commonly used haemostat.



Fig. 5-12: Different sized curved haemostats.

NEGUS ARTERY FORCEPS

It is stout long jawed instrument (forceps) with distal part of the jaws bent like a hook with transverse serrations. It is used to catch bleeding part of the tissues prior to ligation. Initially bleeding area is clamped with haemostat, later Negus artery forceps is clamped underneath and artery is released. It facilitates easier passage of the ligature across the bleeding vessels or tissues **(Fig. 5-13)**.



Fig. 5-13: Negus artery forceps.

RIGHT ANGLE FORCEPS–MEIGSTER'S/LAHEY'S

It has got 90° curves in terminal 1 cm part of the blades. Blades are *longitudinally* serrated. It has got a ratchet. Tip is blunt. It is used to dissect pedicles and to pass ligatures, to dissect the vagus and ligate in vagotomy, to hold bleeding vessels in depth, to dissect major vessels, to dissect and pass ligatures to cystic duct and cystic artery in cholecystectomy and in thyroid, biliary, splenic, gastric, renal and pelvic surgeries **(Figs 5-14A to D)**.



Fig. 5.14A



Figs 5.14B to D

Figs 5-14A to D: Meigster right angle forceps.

WELL'S ARTERIAL CLAMP

It has got doubly right angled distal blades with longitudinal serrations in the jaw. It is used to clamp pedicles like in nephrectomy or splenectomy **(Fig. 5-15)**.



Fig. 5-15: Well's arterial clamp.

BULLDOG CLAMP

Light bulldog clamp has got pinch cock action to open and close. Blades have got fine transverse serrations. Pott's bulldog clamp is paper clip like instrument with strong jaws (with serrations) with spring loaded handle which permits a secure grip of the vessel. Bulldog clamp is used to clamp vessels during vascular anastomosis like for creating AV fistula in patient with renal failure; major vessel surgeries as for aorta, inferior vena cava, portal vein, etc. With a firm grip it blocks the vessel without injuring the vessel wall and without any chance for slippage. Pott's bulldog clamp is used for large vessels like aorta, vena cava **(Figs 5-16 and 5-17)**.



Fig. 5-16: Bulldog clamp.



Fig. 5-17: Pott's bulldog clamp.

SATINSKY VASCULAR CLAMP

It is light atraumatic long instrument with C shaped distal blades which has got fine teeth within. It has got a ratchet. It can be applied to part of the circumference of the vessel in portal vein, iliac veins, inferior vena cava while removing tumor thrombus in renal cell carcinoma, in pancreatectomy, major vessel surgeries. Vascular anastomosis can be done using it **(Fig. 5-18)**.



Fig. 5-18: Satinsky vascular clamp.

DE BAKEY'S VASCULAR CLAMP

Its blades are long and well angulated so that it can be used to clamp vessels/bleeders in the depth with good grip without damaging the vessel wall **(Fig. 5-19)**.



Fig. 5-19: De Bakey's vascular clamp

PEDICLE CLAMPS

A pedicle clamp is a stout haemostat with straight or curved blades with a ratchet. Entire blades are serrated here. It can be with or without teeth.

- *Spencer-Wells pedicle clamp/artery forceps*— has blunt tip without teeth. It can be straight or curved. Its blades are entirely serrated. It can be small/straight/large **(Fig. 5-20)**.



Fig. 5-20: Spencer-Wells's clamp/artery forceps.

- *Robert's pedicle clamp*—It is stout curved instrument with transverse serrations in the distal blades on entire length with a ratchet. Tip is without teeth. It is used to clamp major pedicles during surgeries like nephrectomy/splenectomy **(Fig. 5-21)**.



Fig. 5-21: Robert's pedicle clamp.

- *Maingot's pedicle clamp* has got longitudinal ridge on one of the distal blades and a groove to receive in the other blade. Tip has got one–in–two teeth. It has got ratchet. It is a crushing clamp **(Fig. 5-22)**. It is stronger than Kocher's forceps/clamp.
- *Kocher's forceps/clamp*–It has got transverse serrations with one–in–two teeth at the tip. It has got a ratchet. It can be curved/straight.
- *Mayo's pedicle clamp* is stout and large with curved long blades with serrations. It is useful in clamping major pedicles.



Fig. 5-22: Maingot's pedicle clamp.

KOCHER'S FORCEPS

It has got serrations in the distal blades and apposing tooth in the tip. It holds the tissues/pedicle well and prevents slippage of the tissues and retraction of the vessels/bleeders. It can be straight or curved; small/medium or large type **(Figs 5-23A to C)**.



Figs 5-23A to C: Kocher's forceps (Theodor Kocher from Switzerland got Nobel prize for his extensive work of thyroid surgery–also refer chapter one).

It is used to hold pedicles, tough structures, cut ends of the muscles like—in thyroidectomy/haemorrhoidectomy/mastectomy/polypectomy/hysterectomy.

It is used to hold tough/fibrous structures like in palms/soles/scalp to prevent retraction of vessels during surgery.

It is used to hold peanuts (gauze pellets of 3-4 mm sized used in blunt dissection).

It is used to hold gauze for blunt dissection; to hold resected bowel; to hold ribs during rib resection.

ALLIS' TISSUE HOLDING FORCEPS

Here distal blades are not apposing each other.

Tip has got teeth in each straight blade which are apposing.

It has got *ratchet*.

It is used to hold skin flaps, fascias, fibrous tissue, aponeurosis, galea (in craniotomy) and bladder wall **(Figs 4-24A to C)**. It is essential instrument in any surgery whether major or minor. It can be small/medium/large. Large Allis is used in hysterectomy to hold vaginal wall and tough structures. It is better not to use this instrument to hold delicate structures like bowel/vessel wall.



Figs 5-24A to C: Allis' tissue holding forceps.

BABCOCK'S FORCEPS

The distal parts of distal blades are curved with triangular fenestra in it which allows soft tissues to bulge out. Tip is non-traumatic with transverse serrations/ridges on it. It has got a ratchet.

It is used to hold any part of the bowel, fallopian tubes, appendix, urinary bladder, ureter, spermatic cord, lymph node **(Figs 5-25A to C)**.



Figs 5-25A to C: Babcock's forceps.

LANE'S TISSUE HOLDING FORCEPS

It has got thick, stout distal blades with oval fenestra in each blade with a broad expanded curvature at the end. It has got apposing tooth (one in two) at the tip and a ratchet **(Figs 5-26A to C)**.

It is used to hold bulky and tough structures (like to hold breast during mastectomy; to hold salivary glands while excising); to hold lymph nodes; to hold tumour tissue. It is also used as towel clip and sponge holding forceps. It is used to hold linea alba and aponeurosis.

MORRANT-BAKER'S APPENDIX HOLDING FORCEPS

It is like Lane's forceps but with apposing serrations proximal to the tooth. These serrations give a good grip on mesoappendix while holding appendix in appendicectomy. Its use is replaced by Babcock's forceps **(Fig. 5-27)**.



Figs 5-26A to C: Lane's tissue holding forceps.



Fig. 5-27: Morrant-Baker's tissue holding forceps.

MOYNIHAN'S TISSUE FORCEPS

It is the tissue holding forceps with thinner and curved blades. Its uses are like Allis' forceps **(Fig. 5-28)**.



Fig. 5-28: Moynihan's tissue forceps.

KOCHER'S GLAND HOLDING FORCEPS

It has got terminal curved rings on each blade with two spikes on each with inward direction. These spikes create a secure grip of lymph nodes while holding **(Fig. 5-29)**.



Fig. 5-29: Kocher's gland holding forceps.

YOUNG'S GLAND FORCEPS

It has got long blades with each blade having rounded flat end with a fenestra without any serrations on its inner aspect. It is atraumatic. It has got ratchet. It is used to hold lymph nodes, cyst wall during surgical excision **(Fig. 5-30)**.



Fig. 5-30: Young's gland holding forceps.

DISSECTING FORCEPS

It is basic essential instrument. It can be toothed or non-toothed. Its outer surface has got serrations/grooves in the middle part. Over this area fingers are placed like a pen to get a good firm grip of the instrument. It is used to hold the tissues and different layers like skin, fascia, aponeurosis, peritoneum, bowel, vessel, nerve, muscle, etc. Toothed dissecting forceps is used to hold skin and other tough structures. It can be one in two/two in three toothed forceps. It is also used for suture removal **(Figs 5-31A and B)**.


Adson's forceps
Non-toothed dissecting forceps
Toothed dissecting forceps
A
B

Figs 5-31A and B: Different types of dissecting forceps. Photo showing how to hold dissecting forceps.

Plain Non-toothed Dissecting Forceps

It is used to hold delicate soft, friable structures like peritoneum, vessels, bowel, nerves, and tendons. It cannot be used to hold skin or tough structures. During surgical dissection it is used to hold/fix/steady/stretch the structures as needed. It is also used to hold and cauterize small bleeding vessels **(Figs 5-32A to F)**.

Toothed-dissecting Forceps

It is used to hold skin and tough structures like fascia, aponeurosis; to remove sutures. It is not used to hold delicate structures like bowel/vessel/nerve. It can have one in two teeth or two in three teeth. Small, fine forceps used for fine works is called as Adson's forceps. *Adson's forceps* can be toothed or non - toothed. *Victor–Bonney's* forceps is heavy toothed dissecting forceps.

KOCHER'S THYROID DISSECTOR

It has got a curved blade with vertical grooves on it. There is an eye on its tip. It is used to dissect the upper pole of thyroid in thyroidectomy and to place as a surface while cutting the superior pedicle. Through eye ligature can be passed **(Fig. 5-33)**.


A
Non-toothed Adson's forceps
B
Non-toothed forceps
C
Toothed Adson's forceps
Toothed forceps (two in three)
D
E
Toothed forceps (one in two)
F
Toothed forceps (Heavy Victor/Bonney's)

Figs 5-32A to F: Dissecting forceps (A) Non-toothed Adson's fine forceps, (B) Non-toothed forceps, (C) Toothed Adson's fine forceps, (D) Toothed forceps–two in three type, (E) Toothed forceps-one in two type, (F) Toothed forceps - heavy Victor Bonney's type.



Fig. 5-33: Kocher's thyroid dissector.

SINUS FORCEPS (LISTER'S)

It has got straight, long blades with serrations in the tip. It does not have ratchet. Serrations allow it hold and break the loculi or wall of the abscess cavity. It is a blunt instrument and so least traumatic and so adjacent neurovascular bundle will not get damaged **(Figs 5-34A to D)**.

It is used to drain pus from abscess cavity (*Hilton's method)*. It is called as sinus forceps because it is initially originated to pack the sinus cavities. It is also used to pack nasal cavity and ear. It is less traumatic.

RUSSIAN FORCEPS

This forceps has got clubbed tip in the blades with serrated inner surface. It is used to hold skin while skin suturing. It gives a very good grip over the skin while suturing without injuring it **(Fig. 5-35)**.



Figs 5-34A to D: Lister's sinus forceps. It does not have lock. It has got serrations on the inner aspect of the distal blades.



Fig. 5-35: Russian forceps used to hold skin while suturing.

RETRACTORS

A retractor is an instrument used to retract tissues away from the operating field; to expose surgical field properly; to carry out surgery precisely and also to prevent damage to adjacent structures while conducting operation. It also prevents the unnecessary handling of the adjacent tissues **(Fig. 5-36)**.



Fig. 5-36: Self-retaining retractor.

Types of retractors –

- *Light retractor* is used to retract vessels, nerves, tendons or any delicate structures.
- *Heavy, stout retractors* are used to retract abdominal wall, ribs, sternum, etc.
- *Broad, flat retractors* are used to retract at curved different angles like for liver, spleen, kidney, bowels, etc.
- *Hook retractors* are used to retract soft tissues.

Retractor may be *plain/non-self-retaining/manual* (which is held by an assistant and its position is adjustable time to time) or *self-retaining* (fixed retraction and continuous non-altered/mechanical). Retractor can also be self-illuminating also with a power lamp at the corner of the blade. Drawback of the manual retraction is that assistant can get fatigue by continuous retraction. Over retraction and injury is possible here.

Self-retaining retractor will not allow regular relaxation of tissues and non-adjustable. It is also bulky. But it maintains fixed position and assistant hands are free for additional work. It may inflict tissue trauma underneath. Placing mops under these instruments will reduce such adverse effect. Fixed deep blades may injure deeper structures like bowel in abdomen. These fixed retractors can be of different types. Chain retractor is cheap good retractor used to retract costal margins in abdomen with blade placing under the costal margin/lower sternum. Its proximal end is connected to an ordinary chain which is fixed to upper end of the table through a stirrup. It is used for surgeries for hiatus hernia, achalasia cardia and lower oesophagus; surgeries of spleen, biliary systems. Upper hand retractors, Omni retractors are different complex retractors used with ends attached to both sides of the operating table. These retractors provide stable exposure of the surgical field to operating surgeon.

Remember–retraction should be gentle and adequate. Over retraction can cause injury to the retracted organ/tissues and often bleeding

Uses of retractors

- Retraction of cut edges of the incision.
- To hold important structures like liver/spleen, etc. away from surgical field.
- To steady the tissues.
- To control bleeding.
- To avoid inadvertent trauma to adjacent structures.

SINGLE HOOK RETRACTOR

It is used to retract the skin. It is used in excision of swellings like cyst, lipoma and neurofibroma. It is used to hold skin flaps while raising the flaps **(Fig. 5-37)**.



Fig. 5-37: Single hook retractor.

VOLKMANN'S RETRACTOR/CAT'S PAW

It is used to retract fascias in soles and palms. There are multiple hooks with pointed edges. Uses are same as single hook retractor. Handle has got serrations. It cannot be used to retract delicate tissues due to presence of sharp teeth at the retracting end **(Fig. 5-38)**.



Fig. 5-38: Volkmann's retractor.

FISCH NERVE HOOK

It is a fine delicate blunt nerve hook used to retract nerves during surgery. Examples: Spinal accessory nerve and hypoglossal nerve retraction in block dissection; ilioinguinal nerve in hernia surgery; lingual and hypoglossal nerves in submandibular surgeries; facial nerve in parotidectomy **(Fig. 5-39)**.



Fig. 5-39: Fisch nerve hook.

SKIN HOOK

It has got sharp curved tip to hold skin with a single puncture. It is used to hold skin flaps during its raise. It is essential instrument in plastic surgery **(Fig. 5-40)**.



Fig. 5-40: Skin hook.

LANGENBECK'S RETRACTOR

It has got a long handle and a small solid blade. It is used in hernia surgery or any superficial surgeries to retract skin, fascia and aponeurosis, etc. It can be single bladed or double bladed. It is a superficial retractor. It is used to retract structures like skin, fascia or muscle **(Figs 5-41A and B)**.



Figs 5-41A and B: Langenbeck's retractor.

CZERNY'S RETRACTOR (HERNIA RETRACTOR)

This retractor has got thick and small blade on one side and biflanged hook on the other side in opposite directions. It is used in surgeries like hernia, laparotomy especially during closure. Bleeders in the edge can be identified and cauterized easily. It is a superficial retractor. Biflanged end facilitates placing the terminal stitch on the end of the wound during closure **(Fig. 5-42)**.



Figs 5-42A and B: Czerny's retractor.

RIGHT ANGLE RETRACTOR

Here handle and blade are at right angle to each other **(Figs 5-43A and B)**.



Figs 5-43A and B: Right angle retractor.

MORRIS' RETRACTOR

It may be single blade type or double blade type. It has flat transversely curved blade. There is a blunt projecting ridge with backward projection to have a better hold.

It is used to retract abdominal wall incisions/loin incisions/ subcostal wounds/any wounds in depth. Beak end of the retractor end prevents it from slipping from depth of the wound and holds well to wound. It needs an assistant to retract as it is manual retractor. Its use in many places is replaced by self-retaining retractor **(Figs 5-44A and B)**.



Figs 5-44A and B: Morris retractors - single blade (one sided) and double blade (both sided).

'C' SHAPED RETRACTOR—ROUX

It is C shaped with curve at both ends. It is used to retract wounds like in hernia, appendicectomy, wide excisions, oral surgery, etc. C shape gives a proper grip **(Figs 5-45A and B)**.



Figs 5-45A and B: C shaped retractor.

'S' SHAPED RETRACTOR

Here blunt curves on each end are in opposite directions. Uses are like C shaped retractor **(Fig. 5-46)**.



Fig. 5-46: 'S' shaped retractor.

DEAVER'S RETRACTOR

It is an instrument in shape of question mark (?). It is stout but atraumatic. Its action is *levering* of the tissues not by push or pull or traction. Moist mops should be kept underneath prior to placing this retractor. It is a retractor with a broad, gently curved long blade. It has got strong handle **(Figs 5-47A to C)**.

It is used to retract the abdominal wall. It is used to retract liver, spleen and other abdominal viscera. It is atraumatic and gives adequate exposure of the surgical field. All major abdominal surgeries like vagotomy, cholecystectomy, gastrectomy, pancreatic surgeries, colonic surgeries, kidney surgeries, anterior resection/abdominoperineal resection, bladder surgeries, lumbar sympathectomy need this instrument.

KEYLAND'S RETRACTOR

It has got flat wide blade with a right angle handle. It is manual retractor. It is used like Deaver's retractor **(Fig. 5-48)**.



Figs 5-47A to C: Deaver's retractor (manual)/Deaver liver retractor.



Fig. 5-48: Keyland's retractor (manual).

DOYEN'S RETRACTOR

It is used in pelvic surgeries and in laparotomies. It has a curved blade with convex edge with a long handle. It is used to retract urinary bladder **(Figs 5-49A to C)**.



Fig. 5-49A



Figs 5-49B and C

Figs 5-49A to C: Doyen's retractor.

BALFOUR'S SELF-RETAINING RETRACTOR

It has got different adjustable blades so as to retract abdominal wall and tissues during surgery. It has got quadrangular metal frame. Two side heavy blades are hook shaped to fit into the wound sides **(Fig. 5-50)**. There is a detachable third blade to retract the viscera. One of the side blades has got screw to adjust the width of the retraction by side blades. Detachable blade is also fixed through an adjustable screw with a slot. Closed instrument is inserted into the wound and adequately widened as required to have its use. Tissues/bowel/organs should not be trapped while widening and adjusting.



Fig. 5-50: Balfour's self-retaining retractor.

MILLIN'S SELF-RETAINING RETRACTOR

It has got three sided triangular metal frame with two flat side blades and one long S shaped adjustable blade which has got two curves to retract urinary bladder or lower abdominal wall by each as needed. It is used in Millin's open prostatectomy and other pelvic surgeries **(Fig. 5-51)**.



Fig. 5-51: Millin's self-retaining retractor.

JOLL'S THYROID RETRACTOR

It is a self-retaining retractor specifically used for thyroid/parathyroid surgeries. It is a semicircular retractor with two blades attached with a handle. End of the blades are sharp like a towel clip with a catch/ratchet on it. Handle has got a screw by which instrument can be opened or closed. Upper and lower skin flaps can be retracted well in thyroid surgery using this instrument **(Fig. 5-52)**.



Fig. 5-52: Joll's thyroid retractor.

KOCHER'S THYROID RETRACTOR

This instrument has got two side adjustable multihooked terminals (adjustable with screws) over two side flanges which are connected with a lockable joint. It is used in thyroidectomy **(Fig. 5-53)**.



Fig. 5-53: Kocher's thyroid retractor.

MOLLISON'S MASTOID RETRACTOR

It is stout instrument with curved long blades which has got sharp outward curved teeth to retract tissues. Proximal shaft has got ratchet with finger bows. It is self-retaining, haemostatic and gives wide exposure of the field. It is used in mastoid surgery, laminectomy, to retract scalp in neurosurgery, limb surgeries etc. When shafts are approximated blades will open **(Figs 5-54A to C)**.



Figs 5-54A to C: Mastoid retractor.

BLADDER NECK RETRACTOR

It is thin, long instrument with two thin long distal blades. Proximal thin shafts have got a ratchet. When ratchet closes, the blades will open. It is used in retracting bladder neck in bladder surgeries **(Fig. 5-55)**.



Fig. 5-55: Bladder neck retractor.

CHEEK RETRACTOR

It is single piece instrument with acutely angled blade with inward curled round margin. It is used to retract cheek to inspect the oral cavity as well as to take biopsy of a lesion for diagnosis; dental extractions; interdental wiring; excision of lesions in jaw, gums and oral cavity (epulis, papillomas, mucus cysts, etc.) **(Fig. 5-56)**.



Fig. 5-56: Cheek retractor.

SCAPULA RETRACTOR

It has got a long stout handle with broad right angled blade with serrations. It is used to retract scapula during thoracotomy **(Fig. 5-57)**.



Fig. 5-57: Scapula retractor.

KIDNEY HILUM RETRACTOR

It has got curved C shaped small blade with a long malleable shaft which is slightly curved. It is used in extended pyelolithotomy (Gilvernet's) to retract renal hilar tissues so as to reach the pelvis. Intrarenal pelvis is approached by this manner to remove the stone **(Fig. 5-58)**.



Fig. 5-58: Kidney hilum retractor.

MORRIS KIDNEY RETRACTOR

It has got blade of 6.5 × 5 cm in size with a curve. There is a blunt projecting ridge directed inwards. It is used in renal surgeries like nephrolithotomy, pyelolithotomy, pyeloplasty and nephrectomy **(Fig. 5-59)**.



Fig. 5-59: Morris kidney retractor.

ALLISON'S LUNG RETRACTOR

It has got long handle with light blade. Blade is made up of wires. Blade is at right angle to the handle. It is used to retract lungs. Lung can expand between wires of the blade. It is atraumatic. It is used in oesophageal surgery, thoracic sympathectomy, mediastinal surgery **(Fig. 5-60)**.



Fig. 5-60: Allison's lung retractor.

RIB RETRACTOR (TUFFIER'S)

There is a strong short shaft with blades attached to it at right angles. One blade is fixed whereas other one is adjustable which can be fixed with a screw at required width. Blades are deep with outer flanges so as to hold with a proper grip. It is used in thoracotomy in lung/ oesophageal and cardiac surgeries (trauma, tumors, mitral valvotomy, mediastinal tumors, diaphragmatic hernia, oesophagectomy, etc.). It is a self retaining retractor **(Fig. 5-61)**. Other rib retractor used is Quervain's rib retractor which is stronger with wing-like blades, fixed with a screw.



Fig. 5-61: Self-retaining rib retractor.

DOYEN'S RIB RASPATORY

It has got a stout handle with a curved semicircular distal blade to pass under the rib surface for separating the periosteum after incising the periosteum of the rib. Using periosteal elevator periosteum is elevated and raspatory is passed under the periosteum from upper margin of the rib to prevent injury to intercostal vessels. There are separate instruments for right side and left side. Handle is held with blade facing forward and upward to determine the side **(Fig. 5-62)**.



Fig. 5-62: Doyen's rib raspatory.

FARABEUF'S RASPATORY

It is a periosteal elevator with a corrugated thumb rest, flat grooved handle and a broad rectangular blade (beveled edge). It is used in elevating the periosteum in cervical rib resection, rib resection for empyema, rib resection in chondromas, in kidney exposure, in osteomyelitis of ribs. Periosteum is retained so that regeneration and remodeling can occur; intercostal vessels and nerves are protected. It is not used to elevate the inner surface of the ribs where Doyen's raspatory is used **(Fig. 5-63)**.



Fig. 5-63: Farabeuf's raspatory with thumb rest.

RIB SHEAR

It has got large rough handles. One blade has got groove with serrations and is blunt. It is passed underneath the rib as a protector to the adjacent tissues. Other blade is cutting one which apposes over the groove of first blade. It cuts the rib from front. Instrument is used for rib resection **(Figs 5-64A to C)**.



Figs 5-64A to C: Rib shear used to cut the ribs.

RIB APPROXIMATOR

It has two strong curved blades with teeth; proximal blade is mobile but can be fixed by a screw whereas distal blade is fixed. It is used to approximate the ribs during closure of thoracotomy. Two blades are placed adjacent to ribs and proximal blade is apposed adequately and fixed with screw. Thoracotomy wound is closed in layers. Screw is loosened to remove the rib approximator **(Fig. 5-65)**.



Fig. 5-65: Rib approximator.

DUVAL'S LUNG HOLDING FORCEPS

Its distal blades have triangular aperture with its inner surface being finely serrated to have firm grip on the lungs without any trauma. Blades are gently curved which imparts a smooth action. It is used to hold the lung during lobectomy/pneumonectomy **(Fig. 5-66)**.



Fig. 5-66: Duval's lung holding forceps.

FRIEDRICH'S LUNG HOLDING FORCEPS

It has got four pronged blades. Each prong is having sigmoid curve with a ball at the tip. It is atraumatic because of smooth ball. It is used to hold wider area of lung tissue **(Fig. 5-67)**.



Fig. 5-67: Friedrich's lung holding forceps.

BICKFORD'S BRONCHIAL CLAMP

It has got long distal blade which has got two bends with longitudinal serrations and spikes on the inner surface. It is used to clamp the bronchus as it holds the cartilaginous part firmly **(Fig. 5-68)**.



Fig. 5-68: Bickford's bronchial clamp.

SURGICAL NEEDLES

Types (Figs 5-69 to 5-71)


Traumatic cutting type needle
Cutting needle with eye
Round-body needle
Atraumatic needle
Straight needle

Fig. 5-69: Different types of needles.

Based on the edge

- *Round body needle*—It is round and smooth on cross section. It is used to suture muscles/intestines/soft tissues/vessels/nerves/tendons/peritoneum.
- *Conventional cutting needle*—Here needle is triangular on cross section with apex facing inward. It is used to suture skin/aponeurosis/tough structures.
- *Reverse cutting needle*—Here needle is triangular (reverse) on cross section with apex facing outward. It increases the strength and is less likely to bend while suturing.
- *Taper cut needle*—Here tip of the needle is reverse cut in section but eventually tapers into the body as round in section. It improves the penetration of needle but minimizes the trauma.
- Blunt pointed needles are used to suture friable organs like liver/spleen/kidneys.
- *Spatulated side cutting needle* (saber lock)—is like a spatula with two lateral side cutting edges.
- *Micropoint needles*, either round bodied or reverse cutting or spatulated are used in ophthalmic and microsurgery. It has got an extra honing process.
- *Trocar point needle* is stout strong cutting end with a robust round body. It is used in obstetrics and gynecology.
- *Tru taper needle* is one with tip angle of needle is at 22 degrees (unlike conventional angle is 32 degrees). It is used in vascular surgery.
- *Visiblack needles*—Needles coated with black so that they are visible better in red background. It also prevents the glare from the focus lights by the needles.
- *Dolphin nose needle* is specially designed needle used for surgeries in patients with hepatitis and AIDS which minimizes the risk of puncturing the gloves and fingers of the surgeon.
- *JB needle* (Juergen-Breunner needle)—oval round bodied needle with a steep curve at the distal half to have easy passage of the needle through bowel in gastrointestinal surgeries.
- *Port closure needle* in laparoscopic surgeries.
- *Ski needle* with a ski shaped curvature in the distal part so as to have easy passage through the port for laparoscopic intracorporeal suturing.

Based on curvature:

- Straight needle.
- Curved needle. Half circle; 5/8 circle, etc.

Based on existence of the eye:

- *Atraumatic needle* is eyeless. Here suture material is attached to the needle by *swaging* (Mr Merson of England). Size of the suture material and that of needle is same and so tissue trauma is less. Needle once used is disposed (Not reusable). It is available as sterilized pack. These needles can be round body or cutting.


Round body
Conventional cutting
Reverse cutting
Taper cut
Blunt-pointed needle
Eyeless needle
Needle with eye
1
2
3
4
5
6
Parts of needle
1. Needle point
2. Needle chord length
3. Needle suture end / eye
4. Needle radius
5. Needle length
6. Needle body
7. 1/4th circle
8. 3/5 circle
9. 1/2 circle
10. 5/8 circle
10
9
8
7
Shapes of needles

Fig. 5-70: Different types of needles. Diagram also shows the eyeless/eyed needles and gives the meanings of 1/4th, 1/2, 3/8th and 5/8th circle needles.



Fig. 5-71: Surgical needle.

- *Traumatic needle:* It is eyed needle. Needle in the eye area is wider than the body of the needle and so tissue trauma is more. These needles are re-usable.

Parts of a surgical needle

- Eye or suture end
- Body–straight/curved
- Needle point is tip
- Circumferential length of the needle
- Needle chord length–distance between the tip and eye

Note:

- Weakest part of the needle is part near the eye.
- Needle is sterilized in cidex/Lysol. It should not be autoclaved as tip gets blunt.
- The needle is held at its center by placing it at the junction of the proximal 2/3rd and distal 1/3rd to have optimal grip, control and precision.
- Needles can be 1/4 circle, 1/2 circle, 3/8 circle or 5/8 circle at their curvatures. (Refer diagram for the same). Needles of different curvature are used at different places depending on the depth of the suturing.
- Needles are made up of stainless steel.
- Atraumatic needles are available as sterilized packs. They are sterilized by ethylene oxide or gamma sterilization along with the sutures which they coexist.
- *Gallie's needle* is large eyed needle which was earlier used in hernias to suture the defect using fascia lata strips.
- *Lane's needle* is half circle cutting needle with a large eye.
- *Mayo needle* is obstetric needle with a large square eye and is strong.
- *Hagedorn reverse flattened point fish hook needle* used for suturing inaccessible sites.
- Symonds round bodied fish hook needles.
- *Bonney Reverdin needle* is a special needle with an eye which is open to one side with small slender shutter which can slid and closed after passing the suture material.
- *Kous Netzoff aluminium needle is* used to suture the liver tear.

NEEDLE HOLDER

Smaller distal blades with criss-cross serrations often with a groove in the middle are the features of a needle holder. Often there is a longitudinal groove in the middle of the distal blade between serrations. Ratio of length of handle to blades is 4:1.

It may be straight or curved. It may be available in different sizes. While holding a needle in a needle holder one should get a good control and good grip. This is achieved by placing the needle at junction of proximal 2/3 and distal 1/3 of the blade. Needle holder should be held between thumb and ring finger. Curved needle holders are available to hold the needles and work at the depth like in pelvis/thoracic cavity for better manoeuvrability and visualisation. Needle holder is sterilised by autoclave **(Figs 5-72A to C)**. *Tungsten–carbide inner surface coated needle holder* is available which has got longer duration of life due to reduced wear and tear of the instrument because of tungsten coating.



Figs 5-72A to C: Needle holder.

BARD-PARKER'S HANDLE (BP HANDLE)

Bard-Parker's handle is a flat stainless steel instrument with a slot on narrower side on both surfaces to attach scalpel blade. 3, 4, 5 and 7 numbered blades are available. Number 4 handle is wider. Scalpel blades 10, 11, 12, and 15 fit into Bard-Parker handle numbers 3, 5 and 7. Scalpel blades 18, 19, 20, 21, 22, 23 and 24 fit into slot of Bard-Parker's blade number 4. New blade is used into the slot of the handle for each patient and so sharpness of the blade is maintained. B P handle is sterilised by autoclave **(Figs 5-73 and 5-74)**.



Figs 5-73A and B: Bard-Parker's handles–3, 4, 5 and 7.



Figs 5-74A and B: Bard-Parker handles number 3 and 4. Blades used are no 2 and no 1.

SURGICAL BLADES

They are detachable blades. Number 11 blade is stab knife blade which is used in incision and drainage of an abscess and in making small incision like for drains. Number 12 blade is curved one, used for tonsillectomy. Here cutting edge faces surgeon. Number 15 is used in plastic surgery, head and neck surgery, face surgeries. Numbers 20, 22 and 24 used in skin incisions of major surgeries like laparotomy, thoracotomy, craniotomy, incisions in limb. Blades are sterilised by gamma radiation with aluminum foil packing. Commonly blades are used only once and then disposed. If sterilisation is needed it is done using cetrimide/Lysol immersion (not autoclave or boiling). Scalpel is also used for dissections of fascial planes, raising skin flaps, hernial sac, etc. Fine lateral oblique strokes are used for such dissections. One should have a control over the depth of dissection. When scalpel is used in the abdomen like while cutting the bowel, it should be used in such a way that sharp edge of the blade should face forward so that to avoid inadvertent injury to deeper vital structures. Bowel is cut from mesenteric margin towards anti-mesenteric surface **(Figs 5-75 and 5-76)**.

Different Ways of Placing Incisions

- *Dinner knife position* is used while making lengthy incision.
- *Pen holding/writing position* is used to make incision over the vessels/nerves/tumors.
- *Fiddle–bow position* is used to make incisions with less pressure on delicate tissues.
- *Grasping position* is used to make long sweeping cuts.
- *Stab position* is used to drain an abscess using no 11 blade with no 3 BP handle. It is also used to make an incision to pass a drain corrugated or tube.



Fig. 5-75: Surgical blades of different numbers. Blades are detachable and used only once.



Fig. 5-76: Different positions/methods used to hold knife while making incisions or doing dissections in different surgeries.

Principles in making incision

- Incision should be planned well prior to surgery for adequacy, for possible need for extension during course of the surgery, and indeed be cosmetically acceptable. Ideally incision site should be marked using sterile marker or methylene blue.
- Clean single stroke firm incision should be made with required depth. Repeated strokes and movements should be avoided.
- Knife should be perpendicular to skin to begin with blade pointing perpendicular to skin. But later blade should be parallel with curvature/belly of the blade on the site of the incision.
- While making lengthy incision like in abdomen, incision area should be stretched between thumb and index fingers of other hand of the surgeon.
- Care should be taken to avoid injuries to deeper structures like muscle/nerves/vessels/bowel while making incisions.

TENOTOMY KNIFE

Tenotomy knife straight/curved with a short cutting edge with a fixed handle is used in congenital torticollis to cut sternomastoid muscle, congenital talipes equino varus, adductor tenotomy and lateral sphincterotomy for fissure in ano **(Fig. 5-77)**.



Fig. 5-77: Tenotomy knife.

ANEURYSM NEEDLE

Aneurysm needle is stout instrument with a deep hook in one end with an eye opening in the blunt tip. Eye proceeds as a deep groove in the needle proximally which allows the ligature to stay firmly. This facilitates the passage of the ligatures across the deeper plane around the blood vessels; to ligate the vessel in continuity; in venesection; to pass the ligature around any tubular structures. Earlier it was used to ligate the artery while treating the aneurysm. It is sterilised in glutaraldehyde or lysol but never by boiling or autoclave **(Fig. 5-78)**.



Fig. 5-78: Aneurysm needle.

SCISSORS

Scissors has got various purposes in surgical field like dissection, cutting tissues, cutting suture materials, opening tissue planes, venesection, cutting bandages, corrugated/tube drains and dressing, ophthalmic or microsurgeries, etc. It can be straight, curved, small, medium or long scissors **(Figs 5-79 to 5-83)**.



Fig. 5-79: Different scissors used in surgical practice.



Fig. 5-80: Straight scissors used for suture cutting.



Fig. 5-81: Scissor showing method of holding it.



Fig. 5-82: Lister's bandage cutting scissor. Distal blades are bent at angle so that it is passed easily under the bandage. Lower blade has got flat blunt atraumatic tip. This part is passed under the bandage as it is atraumatic. Scissors are sterilised by chemical method using Lysol or glutaraldehyde. Scissors are not autoclaved; not boiled.



Fig. 5-83: Heath's suture cutting scissor with toothed forceps.

Different scissors are–

Mayo's scissors–are long and stout scissors. It can be blunt tipped/pointed tip/straight or curved.

Mc Indoe scissor–is having fine small blade. It is used mainly for dissection and in cutting delicate structures.

Metzenbaum scissor–has got long blades in comparison to shaft. It is used in depth dissection like vagotomy, cholecystectomy, pelvic surgeries, etc.

Heath suture cutting scissor–has got long shaft, small curves angled blades with tip is having fine serrations which ensures the proper grip of the suture material to be cut. Suture is held with dissecting forceps and is cut using Heath's scissor between knot and skin where suture enters.

Steele's scissor is like Metzenbaum scissor with similar use.

Lister's bandage/dressing cutting scissor has got flat lower blade to avoid damage to skin. Lower blade has got a knob at the terminal.

BOWEL OCCLUSION CLAMPS

Different types of occlusion clamps are discussed as follows **(Figs 5-84 to 5-90):**


Transverse serrations
Longitudinal fenestration

Fig. 5-84: Moynihan's occlusion clamp.



Fig. 5-85: Doyen's occlusion clamp.



Fig. 5-86: Lane's paired gastrojejunostomy clamps with hook and screws used for gastrojejunostomy.


Slot
Screw
Carwardine's two clamps shown separately with slot and screw
Carwardine's twin clamps attached

Fig. 5-87: Carwardine's twin intestinal occlusion clamp with screw and slot to fix. It is used to have easier intestinal anastomosis.


Ball like projections
Longitudinal serrations

Fig. 5-88: Payr's gastric occlusion clamp.


Placement of jejunum
Placement of stomach

Fig. 5-89: Moynihan's gastrojejunostomy clamp.



Figs 5-90A and B: Occlusion clamps.

Moynihan's occlusion clamp (gastric)

- It has got long distal blades with transverse serrations with a longitudinal fenestration one on each blade.
- It may be straight or curved.
- It is non-traumatic, non-crushing type.
- It occludes lumen of the bowel/stomach and so prevents spillage of the content of the bowel.
- It also occludes the vessels in the wall of the bowel and so prevents bleeding during surgery.
- It is used during anastomosis of the stomach and other parts of the bowel.

Kocher's occlusion clamp (gastric)—Blades have longitudinal serrations without fenestration.

Doyen's intestinal occlusion clamps (straight or curved)—Have longitudinal serrations with apposing blades.

Lane's paired gastrojejunostomy clamps (straight or curved)—It is used in gastrojejunostomy. It steadies the anastomosing parts well. It has got a hook at the tip and a screw on the blade to fix each other.

Carwardine's twin intestinal occlusion clamps— It has got a slot on one part shaft and a corresponding screw on the other part shaft. These slot and screw fits into each other to facilitate proper intestinal anastomosis.

Payr's gastric occlusion clamp–It has got longitudinal serrations on the inner surface of the blades with several ball-like projections along the sides which interlock each other of the opposite blade to have a firm grip on the stomach/bowel while using.

Moynihan's gastrojejunostomy clamp–It has got long fenestrated blades with oblique serrations. Central and one lateral blade are straight where jejunum is placed while doing gastrojejunostomy and third lateral blade is 'L' shaped within which stomach occupies while using. Serrations and L shape prevents slippage of the bowel while anatomizing.

CRUSHING CLAMPS

Payr's crushing clamp–gastric/intestinal/appendix crushing

- It is stout and heavy instrument with double lever in the handle with longitudinal serrations.
- Once applied it crushes the bowel. So before applying it, line of resection of stomach/bowel should be assessed properly. It is applied to the part which has to be removed. Viability of the bowel is lost once it is applied.
- It is used in gastrectomy, resection and anastomosis of the bowel.
- It can be gastric crushing or intestinal crushing or appendix crushing clamp. All are similar; only size of the blades is smaller in intestinal and appendix crushing clamps **(Figs 5-91 and 5-92)**.



Fig. 5-91: Payr's crushing clamp.



Fig. 5-92: Parker-Kerr crushing clamp.

Parker-Kerr crushing clamp–It is a stout and heavy crushing clamp with longitudinal serrations.

DESJARDIN'S CHOLEDOCHOLITHOTOMY FORCEPS

It has got long distal blades with smooth serrations and fenestra in the tip. It does not have lock and so accidental damage to CBD mucosa or crushing of the CBD stone are avoided.

It is used for choledocholithotomy (removal of CBD stones). Length and curve facilitate the stone extraction better. In laparoscopic cholecystectomy, it can be used to remove stones from gall bladder by passing through the 10 mm port so that makes delivery of the gall bladder easier. Disadvantage is that instrument may dilate the CBD significantly while manipulating **(Figs 5-93 and 5-94)**.



Fig. 5-93: Desjardin's choledocholithotomy forceps.



Figs 5-94A and B: Desjardin's forceps with Bakes dilator.

Lawson-Tait choledocholithotomy forceps/Alligator forceps is used which has got alligator jaws that facilitate passage through a narrow duct with lesser chances of dilating the duct.

BAKES DILATOR

It is long malleable metallic instrument with club at the terminal end. It is available in different sizes.

It is used to assess the CBD, duodenal papilla for patency or block. Dilator is passed through the choledochotomy opening downwards to reach the metal tip (olive blunt tip) to duodenum. It signifies the patency. It is called as *steel sign*. Dilators are passed gradually from lesser diameter to higher diameter size **(Fig. 5-95)**.



Fig. 5-95: Bakes dilator.

CHEATLE'S GALLSTONE SCOOP WITH OR WITHOUT HOOK

It is flexible long instrument with a blunt scoop on one side with a handle. Few instruments often contain a hook on other side. Scoop is to remove the debris from the gall bladder or common bile duct; and also to support or push the stone while removing. Hook is used to dislodge the impacted stone **(Figs 5-96A and B)**.



Figs 5-96A and B: Cheatle's gallstone scoop and also scoop with a hook.

CHOLECYSTECTOMY FORCEPS

These instruments are used to hold the fundus and Hartmann's pouch of the gall bladder during cholecystectomy. It is also used to dissect the cystic duct and artery and to pass ligature around the cystic duct and artery.

Types (Fig. 5-97)

Moynihan's cholecystectomy forceps has long shafts with slight curve at the short distal blades like a parrot beak with oblique serrations inside.

Henry-Gray's cholecystectomy forceps is similar but has right angled blades with transverse serrations.

GALLSTONE PROBE

It is a long malleable instrument with an olive on one or both ends with a handle. Its diameter is 6 mm. It is used to explore the common bile duct to look for patency in hepatic, and presence of stones. Small stones in common bile duct can be pushed into the duodenum. If stone is impacted, its exact location can be found by passing it **(Fig. 5-98)**.



Fig. 5-97: Cholecystectomy forceps–two types–Henry Gray's right angled; Moynihan's parrot beak curved.



Fig. 5-98: Gallstone probe is available as one side or both sides olive tip which is flexible, long and thin.

MAYO-ROBSON'S CHOLECYSTOENTEROSTOMY CLAMP

It has got long curved semicircle-like blades. It is used while bypassing the biliary tree–*cholecysto-enterostomy* done as a palliative procedure in obstructive jaundice (in carcinoma head of the pancreas or periampullary or carcinoma distal common bile duct) **(Fig. 5-99)**. This clamp is used to clamp the gall bladder to keep in position while doing cholecystojejunostomy. But choledochojejunostomy Roux n Y is a better palliative bypass procedure because narrow cystic duct may get blocked later causing re-obstruction of the biliary tree. Cystic duct may end into the common bile duct lower down and its junction may get involved by the tumour invasion causing re-block and so failure of the palliative procedure.



Fig. 5-99: Mayo-Robson's cholecystoenterostomy clamp.

KEHR'S 'T' TUBE

- It is used after opening of CBD (choledochotomy). CBD is closed with 'T' tube in situ.

- It is made up of latex or red rubber. 'T' tube has got horizontal part which is kept in the CBD and vertical part which is allowed to come out to drain bile **(Fig. 5-100)**. Amount of bile draining is measured daily.
  Before removal of 'T' tube, patency of CBD should be confirmed.



Figs 5-100A to C: Kehr's 'T' tubes.

It is done by following methods:

- The vertical limb (done in 10-14 days) is clamped and observed for development of pain, fever and jaundice in 24 hours. If normal then one can presume that there is no obstruction in the CBD.
- Water soluble iodine dye is injected through the tube to visualise biliary tree and free flow of dye into the duodenum. (Postoperative 'T' tube cholangiogram). It is done in 14 days which is the time required to develop fibrous track. Once there is free flow tube is removed and track gets closed on its own.

Complications/problems of T tube

- Kinking/block/break in T tube
- Displacement/slipping of T tube out of common bile duct may cause biliary peritonitis
- Improper pancreatic duct drainage due to tube
- Impaired enterohepatic circulation
- Biliary infection, secondary haemorrhage, bile leak and peritonitis, foreign body reaction
- Difficulty in removal even after adequate pressure is managed by gradual continuous pressure and occasionally exploration may be needed.

SUCTION INSTRUMENTS

These are essential instruments needed in all surgical practice to suck out blood from the surgical field, pus, infected fluid, fluid in peritoneal/ thoracic/cranial cavities. It has got a *suction tip* of varying types, *suction tube* which connects tip to the *suction apparatus* and suction creating system, either central suction system *or* power suction system with two suction glass bottles connected to each other *or* manual suction apparatus (now not used). Suction tip has got a long bent tube with openings at one end to suck the fluid, with a stout handle which has got a proximal ridged part at the other end to which suction tube (rubber or plastic) is attached, which is in turn is connected to suction apparatus. Suction tip and suction tubes should be sterile. They are sterilised by autoclave **(Fig. 5-101)**.



Fig. 5-101: Suction tip.

Types of suction tips–

- *Adson's fine suction tip*–It is angled with a vent/thumb rest to control the suction as needed. It is a fine suction tip which is used in meticulous surgeries like plastic, vascular and reconstructive surgeries. It cannot be used when large quantity of blood/pus/ fluid/clot needs to be sucked out **(Fig. 5-102)**.



Fig. 5-102: Adson's suction tip.

- *Yankauer suction tip*–It is large suction tip used mainly in peritoneal cavity after lavage; in haemoperitoneum; in peritonitis; in pelvis; in thoracotomy; etc. It has got central hole with outer small multiple holes. It creates strong suction and so may suck omentum; bowel wall, etc. So with one hand bowel and omentum should be pushed aside while sucking the fluid. Often its tip is supported by a rubber tube. When it is present, care is taken to see that it is not left inside the peritoneal cavity by inadvertent slippage **(Fig. 5-103)**.



Fig. 5-103: Yankauer suction tip.

- *Poole's multiperforated suction tip*–It has got outer and inner tubes–one inside the other. Outer tube has got multiple holes with blunt closed tip so that bowel/tissues will not be sucked inside. Inner tube has got one terminal and another proximal side holes. Inner tube will be inside the outer tube attached with a screw on proximal aspect. Outer tube has got a thumb rest hole/vent which when closed with thumb, only then the suction tube will function. With thumb placed on the vent suctioning is done in the peritoneum or other cavities, thumb is released while removing the suction tube so that sucking effect on the bowel or omentum or vessels or over the stoma is prevented while withdrawing the suction tip. It acts by sump action principle. It can also be used for decompressing the distended bowel **(Fig. 5-104)**.



Fig. 5-104: Poole's suction tip.

TRACHEOSTOMY TUBE

Types (Figs 5-105 to 5-108)

1. *Fuller's bivalved tracheostomy tube*: It has got outer tube and inner tube. Outer tube is biflanged and so insertion is easier. Inner tube is longer with an opening on its posterior aspect. Inner tube can be removed and re-inserted easily whenever required. Outer tube flanges are weak and sharp and can break or cause trauma to the tracheal wall. It cannot be used during radiotherapy.
2. *Jackson's tracheostomy tube*: It has got outer tube, inner tube and an obturator. Outer tube has got lock mechanism for inner tube with holes on either side for straps and shield for protection. Inner tube is longer than outer tube. Obturator guides insertion of tube. It is not used in radiotherapy. With tube in place patient cannot speak.
3. *Red-rubber tracheostomy tube.*
4. *PVC tracheostomy tube.*

Modern tracheostomy tubes are made of plastic. They are soft, least irritant and disposable. They have inflatable cuff which makes it easier to give assisted ventilation. Cuff should be deflated at regular intervals to prevent tracheal pressure necrosis of trachea (For assisted ventilation endotracheal tube can be kept for 7 days. Beyond that period patient needs tracheostomy for further ventilation).

Indications for tracheostomy

- In head, neck and facial injuries.
- Tetanus.
- Tracheomalacia after thyroidectomy.
- Laryngeal oedema/spasm.
- Major head and neck surgeries like commando's operation, block dissection, etc.

TRACHEAL DILATOR (TROUSSEAU'S)

Here blades open up while approximating the handle. Blades have got club shaped blunt tip. It is used to dilate the tracheal opening during tracheostomy and to keep it open while introducing the tracheal dilator **(Fig. 5-109)**.



Fig. 5-105: Tracheostomy tubes (a) Fuller's tube; (b) Jackson's tube.



Fig. 5-106: Synthetic disposable tracheostomy tube. Usually number 8.0 or 8.5 is used.



Figs 5-107A and B: Fuller's biflanged tracheostomy tube. It is made up of German silver. Outer biflanged tube is compressible and so acts like a tracheal dilator. Inner tube is longer than outer tube with opening on the convex part which allows phonation and re-education during decannulation. Inner tube cab removed out cleaned properly and can be replaced again with ease. Tracheostomy opening in the neck when blocked with finger, patency of airway and phonation can be checked.



Fig. 5-108: Chevalier Jackson's trachesostomy tube.



Fig. 5-109: Tracheal dilator.

TRACHEAL HOOK

It is single blunt hook/sharp hook with a handle which is used to stabilise the trachea, retract strap muscles and isthmus during tracheostomy by placing under the cricoid to pull it upwards. Sharp hook is used to stabilize the trachea. Blunt hook is used to retract strap muscles **(Fig. 5-110)**.



Fig. 5-110: Tracheal hook.

CRICOID HOOK

It has got thin shaft and two curved prongs at the end of the blade with a handle. It is used to retract the isthmus during tracheostomy **(Fig. 5-111)**.



Fig. 5-111: Cricoid hook.

ENDOTRACHEAL TUBE

It is a gently curved tube used to pass into the trachea via the nasal/oral route. It is made up of India rubber or portex. It may be cuffed or non-cuffed (plain). Cuff is present on the distal part of the tube which is inflated using air through a fine tube present on the body of the endotracheal tube. Small pilot balloon on the proximal part is present to check the tension of the cuff. Cuff prevents aspiration and air leak. Capacity of the cuff is 4 ml and often tip is radiopaque. When non-cuffed tube is used, ribbon gauze should be packed around it to protect air way from aspiration. Its distal end is beveled–38 degrees towards left as tube is passed from the right angle of the mouth of the patient. It has got a thick black mark which should pass just beyond the vocal cords. Cuff should be 3 cm beyond vocal cords in adult and 1 cm beyond vocal cords in infants. Different sized tubes are available depending on age of the patient. Number 6.5 to 8.0 in females and 8.0 to 9.5 in males are used. Styllet is often used while passing the endotracheal tube for easy intubation **(Figs 5-112A to C)**.



Figs 5-112A to C: Endotracheal tube.

It is used in general anaesthesia, to maintain airway in emergency in patients with trauma, in patients with respiratory distress, in cardia arrest. It is a life saving tube used during resuscitation. It is usually kept for 7 days. Tracheostomy is done if patient needs further continuation of artificial ventilation.

Types

- *Cole tube*–Here distal part is narrow and is used in paediatric anaesthesia.
- *Lindholm tube*–It has 90 degree curve at oropharynx.
- *Rae preformed tracheal tube*–There is bending in the part of the tube that remains outside. It can be oral or nasal bends.
- *Spiral embedded/armored/reinforced*–Middle segment of the tube is spirally embedded with nylon/metal filaments to make it resistant for kinking and tolerable in high pressure.
- *Endotrol tube* has got cable like mechanism to have a control over the tip.
- *Hi-low jet three*–lumen tracheal tube with main lumen for ventilation, second for jet ventilation, suctioning, oxygenation and bronchoscopy, third one for irrigation and sampling from trachea.
- *Laser shield endotracheal tube* which is made up of silicon with impregnation of metal particles.
- *Oxford endotracheal tube*–Here 2 cm of nasal end of the tube is bent at 90 degrees and is used in cleft lip and cleft palate surgeries.

Complications of Endotracheal Tube

- Oesophageal intubation–most dangerous and should be identified by ventilation, auscultation, absence of vapour in the proximal part of the tube. It should be removed and reintroduced immediately.
- Trauma to oral/nasal/pharynx/larynx.
- Right sided intubation as right bronchus is shorter, wider than left and it is in line with tracheal lumen. Left side will not get ventilated in this situation.
- Bronchial obstruction/aspiration.
- Infection–bronchopneumonia, septicaemia.
- Kinking, blocking of the tube.
- Tracheal dilatation/erosion.
- Inadvertent extubation/difficult extubation.
- Laryngeal/pharyngeal oedema, laryngitis.
- Vocal cord dysfunction/laryngeal or tracheal narrowing.

DIRECT LARYNGOSCOPE

It is to visualise larynx; consists of a handle and blade. Handle contains batteries as light source. Blade can be straight or curved and detachable. It contains an illuminating bulb at the tip. Light gets on only when blade is straightened when ready for use when it comes in contact with handle.

MacIntosh blade is commonly used which is curved with a flange to push the tongue to opposite side. Blade is designed for right hander to push the tongue towards left. For left hander separate laryngoscope with blades are used. Bulb at the blade comes in contact with handle once blade is opened right angle to cause illumination. Fiberoptic laryngoscope is brighter with bulb in the handle so that bulb falling into oropharynx or larynx is prevented. Tip of the blade is used to press vallecula so that epiglottis gets lifted to view the glottis. Blades may be small, medium, large or extra large **(Figs 5-113A and B)**.



Figs 5-113A and B: MacIntosh laryngoscope.

Miller blade—Straight blade which is used in children and in difficult cases with tip is passing behind the epiglottis to view glottis. Miller blades are available as 0, 1, 2, 3 and 4.

Problems–Trauma to oropharynx, tachycardia, hypertension, arrhythmias. Inadvertent loosening of the bulb and falling into oropharynx or larynx is real risk.

MAGILL'S FORCEPS

It is long, sidewise angulated with fenestrated blades with rings in the handle without ratchets. Angulation helps while using in proper vision of oropharynx. It is used to assist in endotracheal intubation, nasotracheal intubation, removal of dentures, teeth, foreign body from the oropharynx in anaesthetised patient. It is used to pass nasogastric tube under vision in anaesthetised patient. Oropharyngeal packing is done under vision using Magill's forceps **(Figs 5-114A and B)**.



Fig. 5-114A



Fig. 5-114B

Figs 5-114A and B: Magill's forceps.

DRAINS

A drain is a created channel which allows any collected fluid to come out after closure of the main wound **(Fig. 5-115)**.



Fig 5-115: Drains: (a) Corrugated rubber drains, (b) Multiple perforated drains, (c) Tube drain.

Types (Figs 5-116 and 5-117)

1. *Corrugated rubber drain:* It drains by capillary action and gravity. It is cheaper and technically easier. But it allows soakage of dressings and causes discomfort to the patient **(Fig. 5-116)**.



Fig. 5-116: Corrugated drain.



Figs 5-117A and B: Romovac suction drain. Here suction is created by pressing the suction corrugation. There is a sharp metallic introducer to pass the tube into the required area after puncturing the skin. It is used for thyroidectomy, mastectomy, radical dissection, wide excisions, flap surgeries etc.

2. Tube drains:
   - Malecot catheter can be used as tube drain
   - Penrose soft latex rubber tube
   - Multiple perforated tubes
3. Closed suction tube drain system
4. *Glove drain*
5. *Wick drain* is a gauze drain to drain pus, discharge, etc.

Advantages of Tube Drains

- Quantity of fluid like bile, pus can be measured
- It can be kept for longer time
- Skin excoriation will not occur
- Patient will be more comfortable
- Infection rate is less
- Removal is easier
- Dye can be injected and cavity or communication can be assessed using 'C-ARM.'

Classification of drain system:

1. *Open (static) drains:* e.g. corrugated drain, Penrose drain (soft latex rubber tubing). Infection rate is higher.
2. *Closed siphon drains:* Here drain is connected to a sterile bag with or without one-way valve. It reduces the infection.
3. *Closed suction drain:* Here negative pressure of –100 to –500 mm Hg is used to create vacuum to drain the secretions.
4. *Sump suction drain:* Here negative suction with a parallel air-vent is used to prevent the adjacent soft tissues being sucked into the lumen of the drain.
5. *Under water seal drain* to drain pleural space.

Indications for drains:

- In drainage of an abscess.
- In bleeding surgical conditions like trauma, per-operative bleed.
- In haemo, pyo or pneumothorax.
- In acute abdominal conditions like peritonitis, haemoperitoneum.
- In major abdominal surgeries like of pancreas, biliary tree, stomach, etc.
- In thyroid surgery.
- In hydrocele surgery.

Problems in drains:

- Infection through the drain.
- Displacement.
- It may not drain adequately and can give false information.
- It may interfere with healing process inside.

Presently keeping a drain itself is a questioned debate and controversy all over. Older dictum was 'when in doubt keep a drain and the surgeon can sleep happily'–is questioned at present.

Drains if not used properly may be counterproductive.

Note:
A drain should be placed always in most dependent position and should be brought out through shortest straight route with a separate stab incision. It should be anchored to skin securely. Corrugated drain should be kept with adequate length otherwise it may get into the abdominal cavity during phases of respiration.

INTERCOSTAL DRAINAGE TUBE

It is made up of portex with proximal end having multiple holes which is inserted into the pleural space. Other end is connected to a glass tube the tip of which is dipped inside the under water bottle which allows the expulsion of air outside. This tube end should be dipped in the water column properly. Smaller glass tube often bent in between is not dipped inside the water column which allows the air to go out. It is used in haemothorax/pneumothorax/empyema/after thoracic/oesophageal surgeries. In haemothorax/empyema, chest tube is inserted in the midaxillary line in 6th intercostal space. It is easier to pass the tube in this line as muscles are thin and patient will be comfortable if tube is in this position **(Fig. 5-118)**.



Fig. 5-118: Intercostal drainage tube with underwater seal bottle.

PAUL'S DRAINAGE TUBE

It is a bent glass tube with two ends. Edge with two collars is passed through the enterotomy into the intestine and fixed with a purse string suture. End with a single collar is attached to a rubber tube to remove the bowel contents from distended bowel. It is not used now **(Fig. 5-119)**.



Fig. 5-119: Paul's drainage tube.

CATHETERS

They are hollow tubes used to relieve urinary retention, obtain urine for analysis, irrigate bladder and to instill drugs into bladder **(Fig. 5-120)**.



Fig. 5-120: Different urinary catheters—Non-self-retaining red rubber catheter; Self-retaining Malecot's catheter; self-retaining Foley's catheter.

Uses

- To pass per urethrally in retention of urine of any cause [BPH, stricture, trauma)
- To measure the urine output in renal failure, postoperative patients and terminally ill patients, and patients under critical care
- After prostatectomy or TURP–three way catheter is used for irrigation also. Here it is also used as haemostatic by inflating more distilled water into the balloon and giving traction causing tamponade effect
- Paraplegia/neurogenic bladder–initially Foley's catheter is used later condom drainage is better
- To give bladder wash in haematuria, infection, etc.
- Percutaneous suprapubic cystostomy
- Cholecystostomy
- To drain fistulas
- To control bleeding from nostrils/post-haemorrhoidectomy secondary haemorrhage
- In children to give enema or to do barium/contrast enema X-rays
- In obstructed labour, during caesarean section surgery, prior to abdominal hysterectomy (for 1 day), at the end of vaginal hysterectomy (for 5 days), post-partum haemorrhage, during abortion often
- To check cervical incompetence 8 F Foley's catheter is used
- After vesicovaginal fistula repair it is kept for 7-10 days
- After Wertheim's operation it is kept for 14 days
- After bladder injury repair it is kept for 10-14 days.

Types

- *Nonself-retaining catheter*- Simple red rubber catheter.
- *Self-retaining catheter*: Foley's catheter**,** Malecot's catheter, Gibbon's catheter, De-Pezzer catheter.

Types of Catheterisation

a. *Indwelling catheterisation*: When a catheter is left behind in bladder and remains so it is called an indwelling catheter
   It is achieved by:
   – Balloon tip of catheter
   – Foley's catheter
   – Flower tip of catheter
   – Malecot's catheter, De- Pezzers
   – Strapping catheter externally
   – Gibbon's catheter.

b. *Intermittent catheterisation*: A sterile catheter is introduced intermittently by the patient or by others.

FOLEY'S CATHETER (FREDRICK EUGENE BASIL FOLEY-AMERICAN UROLOGIST)

It is a *self retaining* urinary catheter made up of *latex*. It has got a balloon near the tip into which distilled water is infused to make it

India rubber catheter	Latex rubber	Metal catheters	Polyethylene catheters
• Red in color contains high sulfur • Heat resistant • Causes more irritation	• Softer, smooth, less irritant • Can be kept for long time • Sterilized by boiling, autoclave or gamma radiation	• Female and male catheters • are different • Used in difficult catheterization • To empty bladder prior to vaginal hysterectomy	• Transparent and stiffer **Gum elastic catheters** • From gum resins with cotton/silk impregnated • Formalin vapor sterilization • Boiling or autoclave can not be done • Not used now

self retainable. Usually Foley's catheter is kept for 7 days. It is *sterilised* by radiation **(Fig. 5-121).**

Size:	Adults	16 F.
	Children	8 F or 10 F.

(**F-** *French unit, Charriere unit, where each unit equals 0.33 mm)*. 16 F means circumference of the catheter is 16 mm. Diameter is on-third of circumference).



Fig. 5-121: Foley's catheter.

Types:

1. Two-way Foley's **(Fig. 5-122)**.
2. Three way Foley's—To give bladder irrigation, e.g. Following TURP.
3. Silicon coated Foley's—To reduce reaction and so as to keep for longer period (3 months).



Fig. 5-122: Two way Foley' and Three way Foley's catheters.

Procedure

After cleaning under strict asepsis, lignocaine gel is lubricated into the urethral meatus. Catheter is passed into the urethra. Sometimes *Maryfield introducer* is used to pass Foley's catheter. Once catheter is in the bladder, urine will flow out. It is now connected to an *urosac bag* **(Fig. 5-123)**. Balloon is inflated with 20-30 ml (amount is written on the catheter) of distilled water to make it self-retainable. During removal of the catheter same amount of water should be removed from the balloon before pulling out the catheter. After passing catheter, prepucial skin should be placed backwards otherwise iatrogenic paraphimosis can develop **(Figs 5-123 to 5-125)**.



Fig. 5-123: Urosac bag.

Complications

- Infection
- Encrustation
- Bleeding
- Stone formation
- Blockage, false passage
- Stricture
- Difficulty in removal of the catheter due to blockage of the balloon channel. Here bulb of Foley's can be punctured from above under ultrasound guidance or ether can be injected into the balloon so as to burst it but it may cause chemical cystitis or a stilette (ureteric catheter stillete) can be passed into the channel.



Fig. 5-124: Maryfield Foley's catheter introducer. It has got groove on the convex surface over which catheter is placed. Tip of catheter is hooked on to projection on the tip of the introducer. Once catheter with introducer is inside, introducer is released and removed retaining the catheter which is inflated adequately.



Fig. 5-125: Iatrogenic paraphimosis developed after Foley's catheterisation due to failure to place back the prepucial skin.

MALECOT'S CATHETER

It is self-retaining urinary catheter with an umbrella or flower at the tip. It is made of red rubber, contains sulphur and so it is radiopaque **(Fig. 5-126)**.

It is never introduced per urethrally. It is sterilized by boiling.



Fig. 5-126: Malecot's catheters.

Uses

- Suprapubic cystostomy (SPC).
  - In case of urinary retention when Foley's catheterisation fails (after two trials)
  - For diversion of urine following bladder, prostate or urethral surgeries
- For continuous drainaige of abscess cavities–
  - Perinephric abscess
  - Pyonephrosis
  - Subphrenic abscess
  - Amoebic liver abscess
- Cabot's nephrostomy
- Cholecystostomy
- Infected pseudocyst of the pancreas
- Gastrostomy, caecostomy (tube type)

Advantages

- Malecot's catheter can be kept for a long period of time (3 months).
- It drains fluid adequately.
- Less infection rate.
- Removal is easier.

Disadvantage

Surgery (Open method) is required to insert the catheter.

Suprapubic Cystostomy (SPC)

It is placing of Malecot catheter into the bladder above the pubis by open method, or percutaneously under guidance using Foley's catheter. It is a temporary opening through the abdomen into the bladder.

Prerequisite: Bladder must be full and is confirmed by dullness below the umbilicus or by ultrasound.

Indication: Retention of urine when urethral catheterisation fails.

Procedure: Under local anaesthesia (Xylocaine 2% above the pubis, in the midline) or G/A, a vertical midline incision of 3 cm in length is placed through linea alba. Skin, fascia, anterior rectus sheath are incised. Recti are retracted. In extraperitoneal space, peritoneum with pad of fat is reflected upward. Bladder is identified by the pattern of detrusor muscle and vesical venous plexus and is confirmed by aspirating urine through a syringe. The bladder is opened near the fundus. Urine is aspirated. Bladder wall is inspected for any pathology. Malecot catheter is straightened using artery forceps and placed in the bladder. Sutures are placed around the Malecot catheter. Wound is closed in layers.

In percutaneous SPC, Foley's catheter is passed into the bladder using trocar and cannula.

Complications

- Injury to bowel, peritoneum.
- Infection.

SIMPLE RED RUBBER CATHETER

It is a non self-retaining urinary catheter. It is stiffer than Foley's catheter. Its tip is rounded and blunt. Opening is only on the side wall (In flatus tube opening is present on both sides and also at the tip). Here *English unit* is used to number–diameter is 1 + catheter number/2 **(Fig. 5-127)**.

Uses:

- Used to drain urine from the bladder temporarily in retention of urine.
- To find out residual urine. After passing urine, catheter is introduced into the bladder. The amount of retained urine is measured. If it is more than 30-50 ml it signifies obstruction. It often increases more than 200 ml in conditions like BPH and indicates significant obstruction that needs surgical intervention like TURP.
- While doing cystography to infuse dilute iodine dye into the bladder.
- Single gentle passage of the red rubber catheter is tried as a diagnostic method to identify the urethral/bladder/renal injuries.

Haematuria signifies urinary tract injury. Measured normal saline is infused into the bladder and return volume is collected; if it is less, then it indicates injury to bladder.



Figs 5-127A and B: Simple non self-retaining red rubber catheter.

- For administration of intravesical chemotherapy or therapeutic BCG infusion into the bladder per urethral in bladder carcinoma.
- To collect urine from the bladder for culture and sensitivity.
- To identify the urethra in perineal surgery/urethral surgery/penectomy.
- To dislodge and push back the calculus impacted in the urinary meatus or in the urethra.
- To administer nasal oxygen.
- For suction of throat/endotracheal tube/tracheostomy tube.
- As a tourniquet for venesection and surgeries of fingers and toes.
- Used as a sling in many places like to hold cord, to hold vagus, to hold pedicles, to hold oesophagus/bowel/ureter.
- To irrigate and clear the pus after opening the abscess cavity/or any other cavities in depth.
- To irrigate common bile duct after choledochotomy; to irrigate ureter/renal pelvis after stone removal.
- In pregnancy, labour, puerperium.
- Just prior to vaginal hysterectomy after draping to empty the bladder red rubber or female metal catheter is used.
- Often to diagnose tracheo-oesophageal fistula.

DEPEZZER'S CATHETER

It is a self-retaining catheter with a bulb at the end which makes it self-retaining. Its uses are like Malecot's catheter. It cannot be passed per urethral. Usually 24 French size is used **(Fig. 5-128)**.



Fig. 5-128: Depezzer's catheter.

CATHETER INTRODUCER

It is used to negotiate the catheter into the urethra or in other places wherever it is used.

Two types:

- Long slender metallic type with rounded tip **(Fig. 5-129)**.
- Maryfield introducer–it is long curved flat metallic introducer with a longitudinal groove over its convex surface over its entire length which ends at the tip as a blunt projection. This projection helps in hooking the catheter tip (Foley's catheter) and the groove accommodates the body of the catheter and prevents it from slipping away **(Fig. 5-129)**.



Figs 5-129: (A) Rounded catheter introducer, (B) Maryfield introducer.

GIBBON'S CATHETER

It is a self retaining catheter made up of plastic with a stillete in it which makes its passage easier through urethra. There are different sizes for males and females because of the difference in length of the urethra in male and female. Catheter has two ribbons attached which can be used to fix to the genitalia by adhesive plaster. Gibbon's catheter is least irritant to urethra **(Fig. 5-130)**.



Fig. 5-130: Gibbon's catheter. Note the look and method of fixing in male and female.

TIEMANN CATHETER (FIG. 5.130A)

It is made up of PVC with beaked, stiff tip. Different color codes are used on the beaked tip for different numbers of the catheter. Side holes are located proximal to the color codes.



Fig. 5-130A: Tiemann catheter.

No. 12—White
No. 14—Green
No. 16—Vermilon
No. 18—Red
No. 20—Yellow
No. 22—Maroon
No. 24—Blue

METAL CATHETERS

They are metal catheters which are stiff and can be passed into the urethra even if other catheters fail.

Two Types

a. *Male metal catheter*
It is long tube with a curve at the tip. Tip is rounded and blunt with side holes. Two rings near the base help in holding the catheter. It is used to empty the bladder in retention of urine when other types of catheter fail. With prior lubrication of urethra using adequate quantity of lignocaine jelly, it is passed like a dilator with all aseptic precautions. Catheter is passed through the external meatus into the urethra. Once it reaches the bulbar urethra a resistance is felt, then handle is rotated across the inguinal ligament, groin towards the midline over to the abdomen. Sudden release of resistance is felt as catheter enters the bladder. Urine will come out of the catheter easily. Catheter will stay there firmly only if entered properly **(Fig. 5-131)**.



Fig. 5-131: Diagram showing male and female metal catheters.

b. *Female metal catheter*
It is short metallic catheter. Tip is rounded with multiple side holes. It has got one flat curved handle. It is used to empty the bladder in pelvic surgeries like vaginal hysterectomy.

URETERIC CATHETER

It is thin slender flexible radiopaque tube of 70 cm length with a black mark at every 5 cm junction. French unit is used. 3-8 French (F) are available. Initially cystoscope is passed and under visualisation ureteric catheter is passed through ureteric orifice with a stillete. Stillete maintains the stiffness and patency of the catheter. It can be olive tipped; whistle; coude'; or open ended. It is used while doing retrograde pyelography (RGP); to do collect selective urine sampling in tuberculosis; to assess and relieve the ureteric obstruction; as an ureteric stent **(Figs 5-132A and B)**.

URETHRAL DILATORS

- Lister's dilator
- Clutton's dilator
- Filiform bougies
- Gum elastic bougies
- Olive tip bougies
- Whip bougies



Figs 5-132A and B: Ureteric catheters.

LISTER'S URETHRAL DILATOR

It has got olive tip with a rounded handle. Handle is rounded with numbers marked. Denominator is circumference in mm at the base of the Lister's dilator **(Figs 5-133A and B)**. Numerator signifies circumference just proximal to the olive tip (narrowest point). Difference between denominator and numerator is 3 mm. So each dilator is narrowed for 3 mm from base to proximal end of olive tip. Circumference of olive tip is equal to circumference in the base. Numbering is based on English scale (diameter in mm) = Number/2 + 1. It is used to dilate stricture urethra; to pass catheter by open rail road technique in rupture urethra.



Figs 5-133A and B: Lister's urethral dilator.

With all aseptic precautions urethral dilatation is done (proper cleaning and draping). It is done under local lignocaine jelly application or under general anaesthesia. Dilator is passed up to the bulb when a resistance is felt. Then handle is gently curved over the inguinal ligament, groin and over the abdomen towards midline. A feel of entry into the bladder is felt while entering the bladder. Once left like that dilator stays there firmly with free side-to-side movement otherwise it will fall back.

Persistent pain; severe resistance and bleeding per urethra are the features to consider failure of the dilator entering into the bladder.

False passage; bleeding; infection and fistula formation are the complications of urethral dilatation.

CLUTTON'S DILATOR

It is a long metallic instrument with a curve and blunt tip at the end. Handle is violin shaped. It is numbered in English units. Denominator of the part signifies the circumference in the base and numerator suggests the circumference in the tip **(Fig. 5-134)**. Difference between denominator and numerator is 4. Numbers are like 6/10; 8/12; 10/14 — so on. Set 12 of dilators are available.



Fig. 5-134: Clutton's dilator.

FILIFORM BOUGIES

It is a small cylindrical hygroscopic instrument used in tight strictures to negotiate one of the bougies. Bougies are passed in bunches into the urethra. One of the bougies will be negotiated across the stricture by trial and error manoeuvre. That particular bougie is left in place which absorbs the urethral fluid and secretions; and gets swollen causing required dilatation. Later metallic dilators like Lister's or Clutton's dilators are passed to achieve adequate dilatation **(Fig. 5-135)**. Many types of filiform bougies are furnished with threaded hollow mounts at the proximal ends. Larger sized screw ended gum elastic bougie can be attached to the filiform follower thread to do the subsequent dilatation.



Fig. 5-135A



Fig. 5-135B

Figs 5-135A and B: Filiform bougie with followers. One of the bougie can be negotiated through the tight strictures and which helps in further dilatation through metallic dilators.

BLADDER SOUND

It is used to explore the bladder for the presence of stones by sound—hence the name. It is not used now. It can be used as urethral dilator **(Fig. 5-136)**.



Fig. 5-136: Bladder sound.

THOMPSON-WALKER'S SUPRAPUBIC CYSTOLITHOTOMY FORCEPS

It has got a spoon shaped elongated concave blades with spikes on the inner surface which gives secure grip of the stone from the bladder. It has no ratchet. Shaft has got a ring for placement of thumb and another is curved open to place four fingers. It is used to hold and remove stones from the urinary bladder in suprapubic cystolithotomy **(Fig. 5-137)**.



Fig. 5-137: Thompson-Walker suprapubic cystolithotomy forceps.

BOOMERANG NEEDLE

It is sharply curved needle attached to a special holder with a spring within it. Needle has got sharp point and a slot. Suture material is passed through the slot to pass deep in to the tissues. When handle is compressed through spring, needle rotates inwards passing through the tissues in front. It is used in suturing prostatic capsule in open prostatectomy **(Fig. 5-138)**.



Fig. 5-138: Boomerang needle used to suture prostatic capsule in open prostatectomy.

NASOGASTRIC TUBE/RYLE'S TUBE

It is one meter long which is made up of red rubber or plastic. Original Ryle's tube was made up of moulded red rubber **(Figs 5-139A and B)**. Presently used nasogastric tubes are made up of polyethylene or portex. Tip is blunt without opening. Subterminal multiple openings are present on all the sides. It is sterilised by gamma rays.



Figs 5-139A and B: Ryle's tube.

It has got three lead shots in the tip which makes it radiopaque. It also facilitates easy passage of the tube through the oesophagus. Once tube is inside the stomach, bile/gastric juice will come out of the proximal end, often confirmed by aspiration. Stethoscope is placed over the stomach; syringe with air is pushed into the tube; if tip of the tube is in the stomach air entering into the stomach can be heard through the stethoscope.

It is passed through one of the nostrils using xylocaine 2% jelly. Under anaesthesia it is passed using Magill's forceps. It should be fixed securely to the nostrils otherwise it may get displaced or come out. It should be replaced with new tube in 2 weeks. Intermittent suction or continuous open drainage can be done depending on requirement. In postoperative period it is removed once patient passes flatus; or adequate bowel sounds are heard; and content in the tube is reduced to less than 50 ml.

It has got markings at different levels:

- At 40 cm distance, indicates the level of gastro-oesophageal junction.
- At 50 cm distance, indicates the level of body of the stomach.
- At 60 cm distance, indicates the level of the pylorus.
- At 65 cm distance, indicates the level of the duodenum.

Indications

Diagnostic:

- For gastric function tests. To assess free acid and total acid–in gastric/duodenal ulcers; pyloric obstruction/carcinoma stomach (exfoliative cytology); achylia; Zollinger–Ellison syndrome; pernicious anaemia; saline load test to confirm gastric motility and outlet obstruction; small bowel enema.
- Hollander's test for completion of vagotomy.
- To diagnose tracheo-oesophageal fistula.
- Baid test for pseudocyst of the pancreas.

Therapeutic:

- In acute abdominal conditions like peritonitis/ obstruction, etc.
- In abdominal trauma.
- After abdominal surgeries.
- In pyloric stenosis.
- In upper GIT bleeding.
- In paralytic ileus, gastric dilatation to decompress the bowel
- For feeding purpose in comatose patients, faciomaxillary injuries, major head and neck surgeries, head injuries, pharyngolaryngeal surgeries; surgeries for cleft palate.

Ryle's tube is British type, made up of red rubber, usually 75 cm in length, with lead shot in the tip. It is available as different sizes from 8 French to 18 French units.

Levin's tube is American tube made up of portex, 125 cm in length. *Now it is commonly used tube.*

Complications

- Injury to nostrils and bleeding.
- Pharyngitis/rhinitis.
- Discomfort/unacceptancy.
- Ulceration in the pharynx/oesophagus.
- Aspiration pneumonia as lower sphincter is kept open–dangerous complication—may cause death also.
- Perforation of oesophagus.

Nasogastric tube is contraindicated in corrosive oesophageal burns in initial phases for 2 weeks.

INFANT FEEDING TUBE

It does not have lead shots and no markings. It is used in children and infants similar to Ryle's tube **(Fig. 5-140)**. Length: 52 cm
Sizes: FG 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18



Fig. 5-140: Infant feeding tube.

FLATUS TUBE

It is made up of India rubber, 45 cm in length. There is one opening in the tip and another on the side proximal to the tip (Urinary catheter like red rubber catheter has no opening on the tip, only side opening is present) **(Fig. 5-141)**. It is used in sigmoid volvulus to decompress and derotate; in paralytic ileus; in subacute intestinal obstruction. It is passed per anal into the rectosigmoid area. Proximal end is connected to water container to observe the quantity of air bubble which signifies the amount of gas getting deflated.



Fig. 5-141: Flatus tube.

HERNIA BISTOURY

It has got a handle and a flat blade with a small cutting edge on one side near the tip. Tip is blunt. Instrument is used to divide constriction band in strangulated hernia, to cut lacunar ligament in femoral hernia. It helps to protect adjacent structures while cutting the band **(Fig. 5-142)**.



Fig. 5-142: Hernia bistoury.

COLLINGWOOD STEWART'S RING SHAPED BLADE HERNIA FORCEPS

It has got semicircular tips which when approximated forms as ring. It has got a ratchet to have a proper grip. It is used to hold cord structures during inguinal hernia surgery so that hernioplasty/herniorrhaphy can be done effectively **(Figs 5-143A and B)**.



Figs 5-143A and B: Cord holding forceps/ring forceps used to hold cord structures in inguinal hernia surgery.

POLYPROPYLENE MESH

It is polypropylene white coloured monofilament, non absorbable, inert, malleable, strong, synthetic mesh used for herioplasty. Presently prosthetic mesh repair is standard except probably Shouldice repair. Mesh is fixed using polypropylene suture material which is blue in colour **(Figs 5-144A and B)**.

TROCAR AND CANNULA

Trocar has got stout handle with a sharp pointed distal end. Trocar passes through the cannula of different sizes and snugly fits into proximal end of cannula. Trocar with sheath is punctured into the needed place and trocar is removed. Through sheath fluid is evacuated. Through the sheath Foley's catheter can also be passed to keep in place. It is used in per cutaneous cystostomy, draining hydrocele fluid, draining pus from gallbladder, pleural cavity, maxillary antrum, etc. **(Figs 5-145A and B)**.



Figs 5-144A and B: Polypropylene mesh used for hernioplasty.



Figs 5-145A and B: Trocar and cannula.

HERNIA DIRECTOR

Hernia director is used to protect the bowel in strangulated/obstructed hernia while releasing the narrow constricting band. Key's hernia director has got grooved gently curved long blade with ridged stout handle. Childe's hernia director has two wings on sides of the blades as a guard with a handle. Constriction ring is cut using hernia bistoury **(Fig. 5-146)**.



Fig. 5-146: Key's and Childe's hernia directors.

PROCTOSCOPE (KELLY'S)

Indications

- *Diagnostic:* Piles, fissure in ano, polyps, stricture, to see internal opening in fistula, carcinoma or any rectal bleeding
- *Therapeutic:* Injection therapy for partial prolapse or piles, cryotherapy for piles, banding for piles, polypectomy, biopsy for carcinoma rectum or anorectum.

Types

- *Illuminating* with a bulb at the distal part
- *Non-illuminating.*

Parts

Proctoscope is conical shape, with proximal diameter more than the distal, so as to illuminate the light at the required site properly. *Obturator* is the inner part which allows the easy insertion of the proctoscope. Usual medium sized proctoscope is 10 cm in length with proximal diameter of 3.5 cm and distal diameter of 2.5 cm–tapering. This tapering allows light to reflect and pass distally. Proximal funnel shaped flange is 5 cm in diameter **(Figs 5-147A and B)**.



Fig. 5-147A



Fig. 5-147B

Figs 5-147A and B: Proctoscope.

Positions for Proctoscopy

- Left lateral position (common),
- Right lateral,
- Lithotomy,
- Knee-elbow position.

Technique of proctoscopy

After doing digital examination, proctoscope with the obturator is introduced inside; through the anal canal in the direction towards the umbilicus. The obturator is removed. Proctoscope is withdrawn and during the course of withdrawal, any pathology has to be looked for.

Acute anal fissure is contraindication for proctoscopy.

SAINT MARK'S ANAL DILATOR

It is hollow conical instrument with both ends closed. Distal end is tapered, smooth and rounded. It is available in three different sizes. It is used for anal dilatation in post-anorectal surgeries and in anal stenosis. Xylocaine jelly is applied to the blunt tip and is gently passed through the anal canal to achieve dilatation **(Fig. 5-148)**.



Fig. 5-148: Saint Mark's anal dilator.

FISTULA BISTOURY

It is a long blade with solid knife with a cutting edge. It is used to lay open the fistula in ano along with Brodie's fistula probe **(Fig. 5-149)**.



Fig. 5-149: Fistula bistoury.

BRODIE'S FISTULA DIRECTOR

It is a long instrument with a winged flat handle. Shaft is curved, gradually tapering to form a pointed tip with a groove along the curvature longitudinally which allows the knife to pass to do fistulotomy. It is used in probing and treating fistula in ano; to release tongue tie as a guide and protector and in external urethrotomy **(Figs 5-150A and B)**.



Figs 5-150A and B: Brodie's fistula director.

PILE HOLDING FORCEPS

It has got long distal blades ending as a ring. Each has got fenestra with a groove on its inner surface. It is used to hold pile mass during haemorrhoidectomy. It differs from sponge holding forceps which has got serrations on the inner aspect of the ring. Tongue holding forceps is also similar but without groove or serrations on the inner aspect of the ring **(Fig. 5-151)**.



Fig. 5-151: Pile holding forceps has got groove on the inner aspect of the rings in the distal blades.

YEOMAN'S PUNCH BIOPSY FORCEPS

It has got two short stout jaws on the tip. Upper jaw is rectangular, mobile and cutting. Lower jaw is fixed and is having a cup. Through a handle (without ratchet) jaws can be closed and opened. Mobile jaw takes punch biopsy from the rectal lesion whereas fixed jaw accommodates the biopsy tissue in the cup **(Fig. 5-152)**. It is used to take biopsy from rectal lesions like carcinoma, ulcers, polyps, etc.



Fig. 5-152: Yeoman's punch biopsy forceps.

MOYNIHAN'S GLASS TUBE

This glass tube of 20 cm in length with a beveled one end and other end connected to a rubber tube with a two circular ridges to facilitate the holding of the purse string suture around the tube. It is used to decompress the proximal bowel in intestinal obstruction without contaminating the peritoneal cavity **(Fig. 5-153)**.



Fig. 5-153: Moynihan's glass tube to decompress bowel in intestinal obstruction.

DUPUYTREN'S ENTEROTOME

It has a stout distal blade with longitudinal serrations. It has got butterfly nut and screw on the proximal end which when tightened causes crushing effect on the structure between the blades. It is specifically used in *colostomy closure extraperitoneally* by placing this instrument over the spur of the colostomy. It is kept in place for 5-7 days and if needed further tightening can be done using screw. Spur gets necrosed and colostomy closes gradually on its own or by placing few sutures in front **(Fig. 5-154)**. Presently colostomy closure is done intraperitoneally by formally suturing bowel wall either single layer or two layers.



Fig. 5-154: Dupuytren's enterotome used for extra peritoneal closure of the colostomy by crushing the spur.

SPIGOT

It is a glass rod of 10 cm length, with one end narrow and blunt. In colostomy, once a loop of the colon is delivered through the abdominal wound it is used to pass through the mesocolon. It stabilises the loop of colon in position and prevents it from slipping into the peritoneal cavity **(Fig. 5-155)**. It is rarely used now.



Fig. 5-155: Spigot used in as colostomy glass rod to prevent the slipping of the colon into the peritoneal cavity.

HUDSON BRACE WITH PERFORATOR AND BURR

Hudson's brace is used to do burr holes in skull bone. Using brace initially perforator is used to reach and open the inner table. Perforator should be carefully used to avoid injury to deeper structures. Later burr is used to widen the hole made by perforator **(Fig. 5-156)**.



Fig. 5-156: Hudson's brace perforator and burr.

SUTURE MATERIALS

Features of Ideal Suture Material

- Adequate tensile strength.
- Good knot holding property.
- Should be least reactive.
- Easy handling property.
- Should have *less memory*. Recoiling tendency of the suture material after removal from the packet is called as memory of suture material. Suture material should have poor memory. More memory causes recoiling, difficulty in handling and knotting.
- Should be easily available and cost effective.

Classification I

Absorbable

- Catgut—*Natural absorbable monofilament suture material*
  It is 99% collagen derived from the submucosa of jejunum of the sheep or serosa of beef (*Kit* means sheep). After washing, intestine is slit longitudinally into four strands; muscle and fat are removed using water spray–*slimming*. Chemical bath saponification is also used to remove fat. Strands are spun together, dried with tension and electronically polished**.** It is absorbed by inflammatory reaction and phagocytosis.
  Plain catgut is yellowish white in colour. Absorption time is 7 days. It is used for subcutaneous tissue, muscle, circumcision in children.
  Chromic catgut is catgut with chromic acid salt. 20% chromium salt in water with 5 parts of glycerine is used to treat the catgut. It is brown in colour. Its absorption time is 21 days. It is used in suturing muscle, fascia, external oblique aponeurosis, ligating pedicles, etc. Atraumatic sutures are manufactured either by swaging or by entangling the suture material into the grooved proximal part of the needle by mechanical pressure. Wound suture material in a support card is packed in a foil envelope with isopropyl alcohol. It is sterilised by gamma radiation.

- Polyglactic acid/polyglactin 910/vicryl - *Synthetic braided multifilament absorbable*
  It is synthetic absorbable suture material–copolymer of glycolide and lactide. It has got excellent tensile strength, long tensile half life, low reactivity, less memory, easy handling and knotting.
  It gets absorbed in 90 days. Absorption is by hydrolysis. It is violet in color. Coating consists of 50% calcium stearate which acts as a lubricant. It is multifilament and braided. It is very good suture material for bowel anastomosis, suturing muscles, closure of peritoneum. It is sterilised by ethylene oxide.
  Vicryl plus is vicryl coated with antibacterial material (triclosan). Vicryl rapide is low molecular weight vicryl with rapid absorption of suture material. It is used in circumcision and in subcuticular suturing.
- Polyglycolic acid/Dexon/Synthetic polymer of glycolic acid is multifilament absorbable suture material (braided) like vicryl. Usually it is colored green/natural beige. It is sterilised by two stage ethylene oxide process. It is not affected by infection. Its knot security is poor and so at least 5 knots should be placed for security.
- Polyglyconate/Maxon is a monofilament absorbable copolymer of glycolic acid and trimethylene carbonate. It has got good knot holding/security; suppleness and flexibility. It is used in soft tissues and skin. It cannot be used in cardiac/vascular/neural/ophthalmic surgeries. It can be colourless or green coloured.
- Poly Dioxanone suture material/PDS is synthetic monofilament absorbable suture material. It is cream/blue/violet/in colour or colorless with properties like vicryl. It is coustly but better suture material than vicryl. It is relatively inert.
- Polyglecaprone 25/Monocryl is monofilament containing 75% glycolide and 25% caprolactone. It has got smooth surface, excellent handling property, good knot security and adequate tissue compatibility.
- Glycomer/Biosyn monofilament

Uses of absorbable suture materials

- In bowel anastomosis like gastrojejunostomy, resection and anastomosis Vicryl (2 zero) is used
- In cholecystojejunostomy (CCJ), choledochojejunostomy (CDJ), pancreaticojejunostomy - Vicryl is used.
- In suturing muscle, fascia, peritoneum, subcutaneous tissue, mucosa.
- In ligating pedicles, e.g. ligation of pedicles during hysterectomy. 1–zero chromic catgut or vicryl are used.
- In circumcision usually 3-zero plain or chromic catgut or vicryl rapide are used.

Absorbable suture materials should not be used in suturing tendon, nerves, vessels (vascular anastomosis) or in hernia surgery where tissue approximation under stress is needed.

Nonabsorbable suture materials

- Silk is natural multifilament braided nonabsorbable suture material derived from cocoon of silkworm larva. It is black in color, a coating got from a vegetable dye. It is coated suture material to reduce capillary action. Serum proofing of the suture material is also done to reduce the capillary attraction. It has got less memory; good knot holding property; easy handling ability.
- Cotton is twisted multifilament natural nonabsorbable suture material. It is white in colour.
- Linen is derived from bark of cotton tree (natural nonabsorbable twisted multifilament suture material). It is made from flax and cellulose in nature. It has got excellent knotting property and is commonly used as ligatures.
- Polyamide is monofilament synthetic non absorbable polymer. Nylon (New York and LONdon) is a polyamide. Multiple pre-cut nylons are available for skin suturing/ligatures. It has got less tissue reaction, easy handling ability, inertness, adequate elasticity and can be used in presence of infection. Ethilon/surgidek/dermalon/sutupak pre-cut sutures are different polyamides. Memory is high like that of polypropylene and so causes problem. *Polyethylene* (Ethylene) is synthetic monofilament nonabsorbable suture material. It is black in colour.
- Polyester is synthetic multifilament braided polymer–nonabsorbable suture material. Polyester has got high tensile strength and good knot holding property. But it is stiff with difficulty in handling and may cause sawing effect to tissues. Dacron is made up of untreated polymers. It is white in colour. Ethibond is polyester coated with polybutylate–polytetramethylene adipate. It is green in colour. Polydek/tevdek are coated with polytetra flouro ethylene (PTFE). They are green in colour. Black sutulene is impregnated with wax. Silicon treated ticron is white/blue in colour.
- Polypropylene (Prolene) is synthetic monofilament suture material. It is blue in color. It has got high memory. (Prolene mesh used for hernioplasty is white in color). It is inert, flexible, strong and least reactive. It can be re-sterilised by autoclave once or twice.
- Polybutester–Novafil is monofilament, blue colored, synthetic suture material which has got adequate flexibility, suppleness and strength.
- Stainless steel metallic non-toxic suture/wire (steel, tantalum, silver) are useful in approximating bones and tough structures, in orthopedic and thoracic surgeries (sternotomy or thoracotomy), in reconstructive surgeries, surgeries of skull base or head and neck, sinus surgeries, in dental surgeries. Monofilament is called as steel suture/metallic suture. Multifilament is called as metallic/steel wire which can be twisted or braided. Metallic sutures/wires are difficult to handle and to use, may cause injury to surgeons but they are very high tensile strength and low reactivity. Kinking is another problem.

Uses of nonabsorbable suture materials

- In herniorrhaphy for repair.
- For closure of abdomen after laparotomy.
- For vascular anastomosis (6—zero), nerve suturing, tendon suturing.
- For tension suturing in the abdomen.
- For suturing the skin.

Classification II

a. Natural
- Catgut
- Silk
- Cotton
- Linen
- Collagen sutures are derived from collagen fibrils of flexor tendon sheaths/tendo Achilles of beef. It can be plain or chromic.
- Homologous sutures derived from the patient's fascia like strips of fascia lata used for hernioplasty or blepharoplasty.
- Cargile membrane is derived from the submucosa of caecum of ox. It is used to cover peritoneum/pleura and to prevent adhesions. It is not used now.
- Kangaroo tail tendon has got high tensile strength–not used now.

b. Synthetic
- Vicryl, Dexon, PDS, Maxon
- Polypropylene, polyethylene, polyester, polyamide

Classification III

a. **Braided:** Polyester, Polyamide, Vicryl, Dexon and Silk.
b. **Twisted:** Cotton, Linen.

Classification IV

a. **Monofilament:** Polypropylene, Polyethylene, PDS, Catgut and Steel.
b. **Multifilament:** Polyester, Polyamide, Vicryl, Dexon, Silk and Cotton.

Classification V

a Coated
b. Uncoated.

Numbering of suture material:

2—	Thick. For pedicle ligation.
1—	
1—zero.	
2—zero.	For bowel suturing.
3—zero.	
4—zero.	
5—zero.	For vascular anastomosis.
6—zero.	”
7—zero.	
8—zero.	
9—zero.	For ophthalmic surgery. Requires microscopy

Different types of suture materials are shown in **Figure 5-157**.

A
B
VP 2347
VICRYL Plus
ETHICON
PW 2601

Figs 5-157A and B: Photo showing different types of suture materials (with pack).

- Length of the suture material is written on the packs. It can be 45 cm; 76 cm; 90 cm or 152 cm so on
- Company code for a particular suture material is important to identify it in detail
- Lot number, batch number, needle description, needle curvature, needle size are mentioned on the packs.
- Name of manufacturing company, license number, manufacture date and expiry dates are mentioned on the pack.

Types of Suturing (Fig. 5-158)

1. Continuous suturing
2. Interrupted simple suturing
3. Interrupted mattress suturing
4. Subcuticular suturing
5. Horizontal tension suturing
6. Vertical tension suturing


Continuous
Horizontal tension sutures
Interrupted simple sutures
Interrupted mattress sutures
Vertical tension sutures
Subcuticular

Fig. 5-158: Types of suturing.

Types of Knots (Fig. 5-159)

1. Reef knot.
2. Granny knot.
3. Surgeon's knot.



Fig. 5-159: Types of knots

MITCHEL'S CLIP DEVICE

- *Mitchel's metal clip:* It has got two sharp points on their teeth to grip the edges of the skin wound when applied.
- *Mitchel's clip applicator:* It has got a groove on the inner surface of each blade with a tooth on the ends of the blades to apply the clips to the edges of skin wound.
- *Mitchel's clip extractor:* It has got short distal blades, one blade has a hood which comes in front of the clip while another blade is flat which comes under the clip, with pressure on the finger rings clip is extracted. It does not have ratchet.
- *Mitchel's clip magazine:* Here clips are arranged in a row and other end with teeth is used to hold the skin margins together like a toothed forceps **(Fig. 5-160)**.



Fig. 5-160: Mitchel's clip devices with clip, applicator, extractor and clip magazine.

SYRINGES

It is basic instrument in medical practice used to give injections through any route, aspirate fluids, to give wash over surface or deeper places.

Types

Bectin Dickenson syringe (BD syringe): It is a glass syringe with a glass piston and barrel having a nozzle at the end to fit into the BD needle. Proximal end of the barrel has got a rim with one side being flat that prevents from rolling and breakage. It is sterilised by boiling. Disposable plastic BD syringes are commonly used now which is sterilised by gamma radiation. BD injection syringes are available as 2 ml, 3 ml, 5 ml, 10 ml, 20 ml, 50 ml and 100 ml capacity. 1 ml tuberculin/insulin syringes, Luer–lock BD syringes (needle can be locked near the nozzle to prevent slipping of the needle) are other modifications **(Fig. 5-161)**.

Record syringes: It is like BD syringe with a metallic screw at the proximal end of the barrel which can fix the barrel of the syringe so that piston will not come out.

Indications for sclerotherapy in piles	Contraindications for sclerotherapy
• 1st and early 2nd degree piles	• Infection at the site
• Piles in pregnancy and old individuals	• Secondary piles
	• Association of fissure in ano or fistula in ano



Fig. 5-161A: Bectin Dickenson syringe (BD syringe).



Fig. 5-161B: Gabriel syringe.

Gabriel syringe: It is used for injection sclerotherapy for internal piles using 5% phenol in almond/olive oil (almond/vegetable oil acts as a vehicle which holds phenol for long period of action). It is a stainless steel syringe with two metallic finger brims near the proximal end. One more metallic finger brim is present on the proximal end of the piston to place thumb while injecting. Special needle which may be straight or curved and sharply pointed is used for injection of haemorrhoids. Patient is placed in left lateral position. Using proctoscope pedicle/upper part of the piles is identified. Sclerosant is injected into the submucosal plane only which is confirmed by pale bleb with thin vessels over it. If it turns as white patch it means it is more superficial and needle is withdrawn and replaced in submucosal plane. 4 ml at each site with two piles in one sitting is done and further injections are given if needed with a 3 weeks gap until complete sclerosis and obliteration of piles occurs.

Asepto Syringe/Dakin's Syringe

It is made up of glass with broad flanged proximal end to which a rubber bulb can be fitted into it. It has got a tapered tip through which tubes/catheters can be fit to give wash, to suck the contents. It is used to give bladder wash in infection, in post-prostatectomy period, to give wash in different cavities and in depth, to instill methylene blue into the bladder to find out any fistula, to remove clots from prostate or other cavities during surgery **(Fig. 5-162)**.



Fig. 5-162: Asepto syringe used for bladder wash.

Toomy Syringe

It is used to give bladder wash through cystoscope while doing transurethral resection of prostate (TURP). It has got a metallic nozzle which fits well into the cystoscopic sheath. It creates a strong suction force to suck the irrigated fluid **(Fig. 5-163)**.



Fig. 5-163: Toomy syringe.

DOYEN'S MOUTH GAG

It has got flat, broad, strong, curved distal blades which has got serrations on the outer aspect so as to have proper grip over teeth. Blades are covered with rubber tubes to prevent injury to enamel. It is used for biopsies in oral cavity, dental extraction, tonsillectomy, excisions of small oral cavity lesions **(Figs 5-164A to C)**.



Figs 5-164A to C: Doyen's mouth gag.

JENING'S MOUTH GAG

It is a self-retaining mouth gag with a thin rim and ratchet. Blades fit into the alveolar margins not on the teeth. So it is useful in edentulous patients. It has got a gap to pass endotracheal tube **(Fig. 5-165)**.



Fig. 5-165: Jening's mouth gag.

TONGUE DEPRESSOR

It is a flat steel atraumatic plate with a 90 degree angle at the centre. Ends are rounded with smooth edge. It is used to inspect posterior third of tongue, oral cavity, tonsils, to take biopsy, etc. Anterior-two-third of the tongue is depressed gently with tongue depressor **(Fig. 5-166)**.



Fig. 5-166: Tongue depressor.

AIRWAY

It is curved metal/plastic hollow instrument with broad proximal end and curved tapered distal end. It helps breathing to patient during postoperative period, and when patient is in intensive care. It also promotes the suction of secretions through the hollow. It prevents fall back of tongue in unconscious patient, in patient with head injury and during induction of general anesthesia. In a patient with epilepsy it is used to prevent fall back of tongue during convulsion period **(Figs 5-167A and B)**.

It is oropharyngeal airway. It has got a flange (prevents swallowing of airway and keeps it in place), bite block (prevents biting and kinking) and curved body. *Guidel disposable airway* is available in different sizes. *Ovassapian airway* is modified with round channel to facilitate easy passage of fiberoptic bronchoscope. Airway which is cuffed is another modification of airway which can be connected to breathing circuits.



Figs 5-167A and B: Airway.

HUMBY'S KNIFE

It is used to take split skin graft from donor site. Usually it is taken from thigh. Often it can also be taken from arm, leg, and forearm. Humby's knife has got stout handle, two flat leaves in blade, one of which is fixed and other can be rotated **(Figs 5-168A and B)**. Disposable skin grafting blade is passed between the rods into the flat leave which has got three knobs which fits exactly into the openings of the blade. Front leaf has got slots which when pushed gets fixed over the blade. Using firm constant pressure with sawing action split skin is harvested from the thigh. Punctuate bleeding over the donor area confirms the proper skin harvesting. Donor graft is placed over the sterile wooden board. Multiple small window cuts are made to prevent formation of seroma. Skin is placed over the recipient bed and fixed using polypropylene sutures or skin staples. Dressing is placed and part is immobilised. Graft is inspected on 5th day for take up. Donor area is inspected after 10 days and kept open without dressing. Stages of graft intake are–stage of plasmatic imbibition, stage of revascularisation and stage of circulation.



Figs 5-168A and B: Humby's knife to harvest skin graft.

Other knives used for harvesting skin graft are:

- Braithwaite's skin grafting knife–disposable blade
- Watson's skin grafting knife–disposable blade
- Thiersch's skin grafting knife–It has got knife with permanent blade.
- Electrical dermatome .

MYER'S VEIN STRIPPER

It is used strip off varicose vein usually long saphenous vein. It is passed from above just below the saphenofemoral junction. Usually stripping is done up to the middle of the leg. Saphenous neuralgia is a rare complication **(Fig. 5-169)**.



Fig. 5-169: Myer's vein stripper.

BONE CUTTING FORCEPS

It has got short blades with sharp firm cutting edges to cut bones; with a stout handle with ridges. It gives optimum mechanical force to cut bones/bone spurs. Some instruments are supported with leverage system **(Fig. 5-170)**.



Fig. 5-170: Bone cutting forceps.

BONE ELEVATOR/BONE LEVER

It has got curved blade with blunt edge and serrations on concave surface. Proximal long shaft has got ring for grip. Some bone lever has got proximal knife-like handle instead of ring. It is used in manipulating the fracture segments in open reduction and so to isolate fracture ends from surrounding soft tissues. It is also used to elevate the fracture segments/bone from the depth for placement of nails/fixation **(Fig. 5-171)**.



Fig. 5-171: Bone elevator/bone lever.

BONE NIBBLER

It has got sharp edges in the tip with blades being concave. It may be having single action/double action joint. It is used to nibble the bone in pieces like in craniectomy, rib resection, amputations of small bones, etc. **(Figs 5-172A and B)**.



Figs 5-172A and B: Bone nibbling forceps/bone nibbler.

SEQUESTRECTOMY FORCEPS/ SEQUESTRUM HOLDING FORCEPS

It has a stout blade with thick transverse serrations with a groove in the middle without a ratchet. It is used to remove sequestrum in osteomyelitis. Sequestrum should be formed before removal X-ray should show clear radiolucency around dense dead bone–a sign of complete separation of the sequestrum **(Fig. 5-173)**.



Fig. 5-173: Sequestrectomy forceps/sequestrum holding forceps.

FERGUSSON'S BONE HOLDING FORCEPS/ LION FORCEPS

It has got curved blade with stout blunt teeth, looks like jaw of a lion. Bone is held in the gap between the jaws. It is used to hold bones in open reduction of fractures, maxilla in maxillectomy, and mandible in mandibular fixation **(Fig. 5-174)**.



Fig. 5-174: Fergusson's bone holding forceps/lion forceps.

CHISEL

Chisel has got proximal rounded flat head which receives the blows of a mallet. Handle is stout, 10 cm in length. Shaft is of equal size of handle which ends as one side beveled only (abrupt beveling). It is used to chip the bone using mallet blow. It is also used in bone grafting, sequestrectomy, etc. (**Figs 5-175A and B**).



Fig. 5-175A and B: Chisel.

OSTEOTOME

It is similar to chisel but both sides is bevelled and beveling is gradual. Shaft has got the marks to find out the length of the osteotome inside the wound. It is used for all osteotomies in different congenital and acquired conditions **(Figs 5-176A and B)**.



Fig. 5-176A



Fig. 5-176B

Figs 5-176A and B: Osteotome.

MALLET

Mallet is a hammer made up of stainless steel or lead. It is lighter than conventional hammer. It is used to give repeated blows on the flat surface over the head of chisel or osteotome. Blow should be flat without rebound **(Fig. 5-177)**.



Fig. 5-177: Mallet.

GIGLI'S SAW

It is 14 inches long with four flexible metal wires braided together with rough sharp surface. It has got loops on either ends to hook the handles on it which is essential while cutting the bone. It is used to cut the bones like mandible, maxilla, amputation of femur/tibia, skull bones between the trephine holes. It is originally used to cut the pubic bone in narrow pelvis **(Fig. 5-178)**.



Fig. 5-178: Gigli's saw/Gigli's wire saw.

KIDNEY TRAY

It is the tray which is kidney shaped. It is used to collect material like fluid, clots, pus, foreign body, gauze, to keep BP handle with blade, to collect daughter cysts in hydatid cyst surgery, in necrosectomy of pancreas etc. It is sterilised and kept in instrument trolley **(Fig. 5-179)**.



Fig. 5-179: Kidney tray.

GALLIE CUP

It is used as a sterilised cup in the instrument trolley to provide antiseptic cleaning solution like povidone iodine, surgical spirit; to keep needles, gauze in the trolley, to collect material, to keep saline needed during surgery. It is essential instrument in all surgery **(Fig. 5-180)**.



Fig. 5-180: Gallie cup.

MAYO'S TABLE

It is the table which is fixed to the side of the operating table and it crosses across the OT table so that draping is done over it to keep instruments over it. Instruments will not fall down if surgeon uses it. It is used when position of the patient is in such a way that it is difficult to place instruments over direct draping. Examples are surgeries in kidney position, lateral position, head and neck surgeries **(Fig. 5-181)**.



Fig. 5-181: Mayo's table.

VOLKMANN'S SCOOP

It is spoon shaped strong stout instrument with serrations in the middle part. Ends are spoon shaped with cups. Spoons on the ends are of different sizes. It is used to scoop granulation tissue, ulcer bed, before skin grafting, to collect tissues, scoop sinus cavities, clearing necrotic materials from abscess cavities, curette cavities and sinus track in chronic osteomyelitis **(Figs 5-182A and B)**.



Figs 5-182A and B: Volkmann's scoop.

FINE LENGTHY STRAIGHT AND BAYONET FORCEPS

Toothed and no toothed lengthy straight or *bayonet* (French–dagger/long blade of rifle) forceps are used in fine dissection and holding tissues and cauterising tissues. Many cautery instruments are fine and often with bayonet. Bayonet shape gives proper vision in depth to proceed with procedure or cautery **(Fig. 5-183)**.



Fig. 5-183: Straight lengthy and bayonet forceps.

CYSTOSCOPE

It is the instrument used by urologists, to visualise urinary bladder, for removal of urinary bladder stones, for TURP, for stricturotomy in urethral stricture, for taking biopsy **(Fig. 5-184)**.



Fig. 5-184: Cystoscope.

AMBU BAG

It is a manual resuscitator with self-inflating bag, bag inlet and non-rebreathing valve. Self-inflating bag returns back into its original shape after compression. During compression air/oxygen enters the patient through non-breathing valve. When compression is released air enters through unidirectional valve to return the bag to its original shape. Exhaled air of the patient returns to atmosphere through non-breathing valve. It is *assisted manual breathing unit*. It can be connected to oxygen reservoir or to atmosphere air. It is used in cardiopulmonary resuscitation, during transporting critically ill patients **(Fig. 5-185)**.



Fig. 5-185: Ambu bag.

LAPAROSCOPIC INSTRUMENTS

There is separate set of laparoscopic instruments with 3 chip camera, telescope light source, CO_2 insufflator, various instruments, harmonic scalpel etc. Details about that are discussed in appropriate places **(Figs 5-186 to 5-199).**



Fig. 5-186A



Fig. 5-186B

Figs 5-186A and B: Laparoscopic instrument trolley and set.



Fig. 5-187: Laparoscopic trocars–10 mm and 5 mm.



Fig. 5-188A



Fig. 5-188B

Figs 5-188A and B: Laparoscopic camera, light cable, camera cable and telescope.



Fig. 5-189: Laparoscopic Hassans cannula.



Fig. 5-190: Laparoscopic port closure needle. First one is curved needle; second one is standard laparoscopic closure needle.



Fig. 5-191: Laparoscopic instruments. They are long fine rotating instruments–scissor, Maryland dissector, grasper, Babcocks forceps, toothed grasper, right angled dissector, etc.



Fig. 5-192: Laparoscopic reducer (10 mm to 5 mm), and bipolar instrument.



Fig. 5-193: Laparoscopic needle holder.



Fig. 5-194: Laparoscopic suction device.



Fig. 5-195: Veress needle.



Clip applicators

Fig. 5-196: Clip applicators



Clips
Disposable port

Fig. 5-197: Disposable port



10 mm to 5 mm reducers of different lengths

Fig. 5-198: Reducer



KARL STORZ Germany
KARL STORZ Germany
A
30 degree telescope
0 degreee telescope
B

Figs 5-199A and B: Telescope

Chapter 7

Basic Surgical Procedures

URINARY CATHETERISATION

Catheters used—Simple non self-retaining red rubber catheter, Foley's self-retaining catheter, Gibbon's catheter, metal catheter.

Indications—Retention of urine due to BPH, stricture urethra, trauma (with all care and precaution gently one trial is done); in major surgery post-operative period; in patients with acute conditions and shock patients to measure the hourly urine output.

Causes of retention of urine

Bladder outlet obstruction

- BPH, Carcinoma prostate.
- Prostatitis, prostatic abscess.
- Bladder carcinoma close to bladder neck.
- Bladder stone obstructing bladder neck.
- Hypertrophy of bladder neck muscle.
- Stricture at bladder neck.

Causes at urethral level

- Urethral stricture- may be due to trauma or inflammatory (gonococcal/nonspecific) or neoplastic or after catheterisation/cystoscopy or after surgery (TURP/urethral surgery/perineal urethrostomy).
- Urethral stone.
- Tumors.
- Posterior urethral valve.
- Urethral trauma.
- Meatal stenosis.
- Pinhole meatus/phimosis.

Other causes

- Post-operative period.
- Post-surgery—After haemorrhoidectomy/fissurectomy/fistulectomy.
- Spinal injury/spinal surgery/spinal anaesthesia.
- Drugs like anticholinergics, antidepressants or antihypertensives.

Foley's catheter is commonly used. Urosac bag, gloves, sterile towel, 2% xylocaine gelly and distilled water are needed.

Procedure

The patient is explained about the procedure. Sterile gloves are worn after hand wash. Patient will be in supine position with legs apart. Genitalia are cleaned with povidone iodine solution. Draping is done using sterile towel. Prepuce is retracted and glans is cleaned again. 20 ml of 2% xylocaine is taken in a syringe and pushed into the urethra through the external meatus. After 5 minutes, penis is held vertically (so that urethra gets straightened to make easier passage of the catheter) and Foley's catheter tip is lubricated with jelly and is gently passed into the urinary bladder. Urine flow through the catheter confirms that it is inside the bladder. It is advanced further more and balloon near the tip is inflated *using distilled water*. Air is not used for this purpose. Normal saline may get crystallised and so ideal is distilled water. (Note: in endotracheal tube only air is used to inflate the balloon. Water should never be used because if balloon bursts aspiration can occur). Quantity inflated should be noted in the case sheet. Usually 20 ml is used. It is actually written in the Foley's catheter. After inflation catheter is pulled out to confirm that balloon is inflated properly. Catheter is connected to urosac bag. Prepuce is placed in normal position otherwise paraphimosis can develop.

In adult 16 F catheter is used. F-French unit- 16 mm circumference (Charriere unit). Often Foley's catheter is kept for 7-10 days. If there is a need to keep catheter for more than 10 days then silicon coated Foley's catheter is used as it is least reactive. Foley's catheter is made up of latex. In children 10 F or 8 F is used.

Three-way Foley's catheter is used to irrigate the bladder with normal saline/glycine solution continuously in post TURP (Transurethral Resection of Prostate) or after bladder surgery or after bladder trauma.

Foley's catheter often is reinforced with tension wires to prevent block and is called as haematuric Foley's catheter.

Maryfield introducer is used often to pass the Foley's catheter into the bladder. It has got a curve with a groove over the convex part to accommodate the catheter.

Balloon should be *deflated completely* before removal of the catheter otherwise urethral injury and haematuria can occur.

In females labia majora are retracted apart to identify the urethral orifice to pass the catheter.

Complications of Catheterisation

Infection, false passage, bleeding, inability to deflate the balloon while removing the catheter. In such occasions, following methods are used—Inflating the balloon further with ether/air/water to cause bursting of the balloon; passing guidewire of the ureteric catheter via the inflating channel; Traction is to catheter so as to make balloon nonmobile and fixed. Long, fine needle is passed per-abdomen in suprapubic place so as to puncture the balloon.

Causes for Inability to Pass the Catheter

Urethral stricture, BPH, non-cooperation by the patient and meatal stenosis

INSERTION OF A NASOGASTRIC TUBE

Indications

For decompressing stomach in intestinal obstruction, after abdominal surgery. It prevents aspiration and distension of intestines.

For Gastric Function Tests

In gastric outlet obstruction to decompress the stomach and also to give stomach wash. Stomach tube is better (Ewald's tube) for this.

For Feeding Purpose

Baid test: Passed Ryle's tube will be palpable per abdomen in pseudocyst of pancreas as stomach is stretched forward.

Ryle's tube will not enter the stomach in Boerhaave's syndrome.

Procedure

Procedure is explained to the patient. Usually no. 16 tube is used in adult. It is one meter long usually of plastic (earlier red rubber) with three lead shots in the tip. Lead shots in the tip make it easier to pass (Infant feeding tube does not have lead shots). It has got different marking ring/rings (2, 3 and 4). First ring signifies O-G junction (40 cm). Two rings for body of stomach (50 cm), three for the pylorus (60 cm) and four for duodenum (70 cm).

Xylocaine jelly 2% is applied to the tube. It is passed through one of the nostrils (wider one) horizontally until it reaches the posterior pharyngeal wall. Patient is asked to swallow if needed with the help of cup of water. Tube passes through the relaxed cricopharyngeus and then into oesophagus. Afterwards it is easier to pass down the oesophagus. Once it is adequately in the oesophagus tube is fixed to nostril.

Confirmation of the tube in the stomach is done by aspirating the bile and also by injecting 30 ml of air through the tube which can be heard in the epigastrium with a stethoscope as a gurgling sound **(Fig. 7-1)**.

Tube can be used for continuous drainage or drainage hourly or at regular intervals.

Problems with Ryle's Tube

Discomfort to the patient; blockage; coiling in the mouth; displacement.

ABSCESS DRAINAGE

Abscess is a localised collection of pus lined by granulation tissue covered by pyogenic membrane. It contains pus in loculi **(Fig. 7-2)**.

Bacteria causing abscess—Staphylococcus aureus, Streptococcus pyogenes, Gram-negative bacteria (*E. coli, Pseudomonas, Klebsiella*), and anaerobes.

Factors precipitating abscess formation—General condition of the patient: Nutrition, anaemia, age of the patient. Associated diseases: Diabetes, HIV, immunosuppression. Type and virulence of the organisms. Trauma, haematoma, and road traffic accidents.

Abscess should be drained once it is formed only under the cover of antibiotics.



Fig. 7-1: After passing the Ryle's tube I to the stomach, air from the syringe should be infused through the tube and when auscultated gush of air into the stomach can be heard which confirms that tube tip is in the stomach.



Fig. 7-2: Pyogenic abscess—Parts.

Features of formed abscess

- Pointing tenderness
- Visible pus
- Excruciating pain
- Localised swelling
- Induration (browny induration).

Abscess is Drained by Hilton's Method

Under general or regional anaesthesia, after cleaning and draping, using needle with syringe pus is aspirated and confirmed. Adequate incision is made over the skin longitudinal to neurovascular bundle. Pyogenic membrane is opened using sinus forceps. Pus is collected for culture and sensitivity. All loculi should be broken. Wound is washed with saline or povidone iodine. Gauze drain or corrugated drain is placed in the wound. Antibiotics are continued. Wound is allowed to granulate and heal **(Figs 7-3 to 7-5)**.



Figs 7-3A and B: instruments used for drainage of a pyogenic abscess—Syringe with needle for aspiration; 11 number blade; toothed dissecting forceps; Lister's sinus forceps; scoop; scissor; roller pack soaked in povidone iodine.

Local anaesthesia may not act as pus is acidic in nature and xylocaine will not be effective in this acidic media.

Complications—Improper drainage and residual abscess; septicaemia; sinus formation; if abscess is located near major vessels, sloughing of the wall of the vessel and torrential haemorrhage can occur occasionally.

Sarcoma and aneurysms may mimic pyogenic abscess especially when it is deep seated and so necessary investigations like CT scan and aspiration of the content should be done before incision and drainage **(Figs 7-6 and 7-7)**.

Abscess in special locations may not show features of formed abscess. In those locations abscess should be drained without waiting for features of formed abscess- pointing, fluctuation. They are—Parotid abscess; breast abscess; Ludwig's angina—it is actually a cellulitis not an abscess but needs exploration and decompression; thigh abscess; ischiorectal abscess.

Parotid Abscess

Parotid abscess presents as severe pain and tender swelling in the parotid region in front of the tragus. Often patient will be toxic, dehydrated with trismus. Parotid abscess is drained under general anaesthesia with endotracheal tube in place. *Blair's* vertical incision is placed in front of the tragus. Abscess cavity is opened using sinus forceps with multiple horizontal incisions in deeper plane. Care should be taken not to traumatise the facial nerve. After draining pus and proper saline wash drain is placed into the wound. Loose sutures in the skin may be placed. Facial nerve injury, septicaemia, laryngeal oedema and local spread of sepsis are the complications. Infection when spreads to pharynx/larynx/parapharyngeal space needs tracheostomy **(Fig. 7-8)**.

Breast Abscess

Breast abscess is commonly due to *Staphylococcus aureus*. It is common in lactating women. It should always be drained under general anaesthesia. There will not be any localisation. Diffuse swelling and tenderness all over the breast is common. Occasionally tender axillary lymph nodes may be palpable. After cleaning and draping, pus is aspirated and confirmed initially. Either circumareolar or submammary incision is made. After draining pus and breaking loculi, a counter-incision is made on the upper part. After proper saline wash of the wound, drain is placed across the *incision and counter-incision*. If patient is lactating, suppression of lactation is done using Bromocryptine 2.5 mg. Regular expression of milk either manually or using breast pump should be done. Otherwise recurrent infection or fistula can occur.

Acute breast abscess may mimic mastitis carcinomatosis/inflammatory carcinoma of breast.

Breast abscess which is not drained but treated with antibiotics may form organised, hard, non-tender swelling in the breast called as Antibioma which will mimic carcinoma breast. Antibioma contains thick walled fibrous tissue with sterile pus as flaques inside. It needs excision **(Figs 7-9 to 7-12)**.

Axillary Abscess

Axillary abscess is drained under general anaesthesia with axilla in hyperextended position and a sandbag under the shoulder. A 5 cm incision is made under the anterior axillary fold longitudinally. Skin and superficial fascia is incised. Using sinus forceps deep fascia is opened in parallel to the line of the axillary vessels. Care is taken not to injure axillary vessels (vein). After draining pus and saline wash, gauze/corrugated drain is placed. Antibiotics are continued. Complications are sinus formation, bleeding, shoulder stiffness.

Ischiorectal Abscess

It is drained under general/spinal anaesthesia. Procedure is done in lithotomy position. After cleaning and draping, cruciate incision is placed over more indurated/more prominent area of the ischiorectal fossa. Incision is deepened. Parts of the angles of the flaps are excised (diamond shaped wound) so as to prevent it to close to form recurrent


A
B
C
D
E
F
G
H
I
J
K

Figs 7.4A to K



Figs 7.4L to Q

Figs 7-4A to Q: Technique of draining pyogenic abscess. 11 number blade is used to make incision. Lister's sinus forceps is used to drain abscess. Often scoop is used gently to remove unhealthy tissues from the wall of the abscess cavity. Cavity is packed with gauze. Dressing placed. Pus sent for culture.



Figs 7-5A and B: Incision should be longitudinal along the line of neurovascular bundle. Loculi should be broken using little finger or blades of sinus forceps.



Fig. 7-6: Aspiration of abdominal wall abscess. Aspiration of abscess prior to making incision is absolute need.



Figs 7-7A to C: Abscess in the perineum which is drained and packed.


Skin incision
Parotid sheath incision

Fig. 7-8: Blair incision used to drain the parotid abscess.


Drain
Incision
Counter-incision

Fig. 7-9: Incision and counter incision for breast abscess.



Fig. 7-10: Photo showing placement of drain in breast abscess.



Figs 7-11A to C: Typical breast abscess showing features of acute inflammation. Drain should be placed after incision and drainage in such abscesses. Often gauze drain can be used.



Fig. 7-12: Breast abscess in a male patient. Breast abscess even though is uncommon in male, it can occur during puberty.



Fig. 7-13: Anatomy of ischiorectal fossa. Note the boundaries and Alcock's canal.



Figs 7-14A to C: Ischiorectal abscess drainage under general anaesthesia. Note the cruciate incision placed and pus is gushing out.



Fig. 7-15: Ischiorectal abscess cavity packed after drainage. Cruciate incision and creation of diamond shaped wound is essential.

abscess formation. Sinus forceps is inserted to enter the fossa and to drain the pus. Using finger all loculi are broken. Rectal examination is done to find out the possibility of existing fistula. Cavity is packed with gauze and dressing is done using 'T' bandage. Antibiotics and regular dressings are required **(Figs 7-13 to 7-15)**.

Digital examination of the rectum should be done to see for fistula. If fistula is present, fistulectomy is done at same or later period.

Ludwig's Angina

It is an inflammatory oedema of submandibular region and floor of the mouth, commonly due to streptococcal infection. There is bilateral brawny cellulitis of sublingual and submandibular region. It is common in severely ill and in advanced malignancy, causing *trismus, laryngeal oedema.* Extension of infection into *parapharyngeal space* may lead to dreaded internal *jugular vein thrombosis.* As the infection is deep to the deep fascia in a closed fascial plane; it spreads very fast causing dangerous complications.

Clinical features: Fever, toxicity, diffuse swelling, dysphagia, dyspnoea, and trismus.

Treatment: Antibiotics-penicillns (high dose 20 lacks 4th-6th hourly), cefaperazone, sulbactum, metronidazole-antimicrobial; IV fluids for adequate hydration **(Figs 7-16 and 7-17).**

Decompression of the submandibular region is done, by making a deep incision extending into the deep fascia and also *cutting both the mylohyoid muscles.* Either it is left open or *delayed suturing is done,* (better option) or it is loosely sutured with a drain in situ.

Complications—Laryngeal oedema and respiratory distress may require tracheostomy; septicaemia; Extension of infection into parapharyngeal space.

Cold Abscess

It is due to caseation necrosis and localisation due to tuberculous infection. There will not be any signs of inflammation. It is well localized, soft, cystic, non-tender swelling without any warmness. It is commonly due to tuberculous lymphadenitis, but can occur in tuberculosis of spine, kidney or other areas. FNAC shows caseation necrosis, macrophages and typical epithelioid cells. Cold abscess is drained using *non-dependent incision.* After drainage wound is sutured without placing a drain **(Figs 7-18A to D)**.



Fig. 7-16: Incision for draining Ludwig's angina.

Treatment of cold abscess—When there is cold abscess; initially it has to be aspirated. [Needle is introduced into the cold abscess in a nondependent site along a *'Z' track* (in zigzag pathway) so as to prevent sinus formation]. But if it recurs, then it should be drained. Drainage is done through *a* nondependent *incision***.** After draining the caseating material, *wound is closed without placing a drain***.** *Surgical removal of tuberculous lymph nodes*- It is done by raising skin flaps and removing all caseating material and lymph nodes. Care should be taken not to injure major structures.

Indications for surgical removal of tubercular lymph nodes

- There is no local response to chemotherapy
- When sinus persists.

TRACHEOSTOMY

Tracheostomy is making an opening in the anterior wall of trachea and converting it into a stoma on the skin surface. It is done for airway maintenance. It is a life saving procedure.



Figs 7-17A to C: Ludwig's angina is drained by decompression incision in the submandibular region with cutting of both mylohyoid muscles. Patient after recovery could open the mouth.



Figs 7-18A to D: Cold abscess and abscess with a sinus in two different patients. It is aspirated in a zigzag track manner. Open drainage is done through non-dependent incision; wound later closed without placing any drain.

Types

- Emergency tracheostomy
- Elective tracheostomy
- Permanent tracheostomy.

High tracheostomy—above the level of isthmus. It can cause tracheal stenosis. It is above 2nd tracheal ring.
Mid-tracheostomy—ideal and commonly used. It through 2nd and 3rd rings behind isthmus. It is approached by dividing thyroid isthmus.
Low-tracheostomy—below the isthmus level. It is deep and impinges the suprasternal notch. It can cause torrential bleed which is difficult to control.

Tracheostomy Tubes

1. ***Fuller's bivalved tracheostomy tube***: It has got a outer tube and an inner tube. Outer tube is biflanged and so insertion is easier. Inner tube is longer with an opening on its posterior aspect. Inner tube can be removed and re-inserted easily whenever required. Using inner tube patient can speak. It is not used in radiotherapy.
2. ***Jackson's tracheostomy tube***: It has got outer tube, inner tube and an obturator. Outer tube has got lock mechanism for inner tube with holes on either side for straps and shield for protection. Inner tube is longer than outer tube. Obturator guides insertion of tube. It is not used in radiotherapy. With tube in place patient cannot speak.
3. Red-rubber tracheostomy tube.
4. ***PVC tracheostomy tube.***

Tubes can be cuffed or noncuffed. It can be fenestrated or nonfenestrated. It can be metal or polyvinyl chloride. Metal tubes are commonly used for permanent tracheostomies. Inner tube can be removed for cleaning purpose. They don't prevent patient from developing aspiration. It is not used for mechanical ventilation purpose.

Shiley's fenestrated tube has got inner and outer tube. Outer cannula has got cuff which can be inflated if mechanical ventilation is needed. Inner tube is changeable and can be nonfenestrated or fenestrated. Nonfenestrated tube is used when mechanical ventilation is needed (outer tube cuff should be inflated). Fenestrated inner tube is used when needs to speak (with deflated outer tube). One way speaking valve may be used along with this to allow air to enter from atmosphere but air exits through fenestra into upper airway. Oxygen can be attached to this speaking valve **(Figs 7-19 to 7-22).**

Modern tracheostomy tubes are made of plastic. They are soft, least irritant and disposable. They have inflatable cuff which makes it easier to give assisted ventilation. Cuff should be deflated at regular intervals to prevent tracheal pressure necrosis. For assisted ventilation, endotracheal tube can be kept for 10-14 days. Beyond that period patient needs tracheostomy for further ventilation as endotracheal tube *in situ* beyond this period may be damaging to trachea, larynx and also precipitate life threatening sepsis.

Indications for Tracheostomy

In head, neck and facial injuries; tetanus; tracheomalacia after thyroidectomy or bilateral recurrent laryngeal nerve palsy; laryngeal oedema/spasm; major head and neck surgeries like Commando's operation, block dissection; acute laryngitis as in diphtheria; carcinoma larynx, foreign body larynx, burns mouth, pharynx, larynx; respiratory paralysis like bulbar palsy; respiratory failure due to asthma, ARDS.



Fig. 7-19: Figure showing the position of tracheostomy tube.



Fig. 7-20: Tracheostomy tube with inflation part and syringe (inflated with air)—polyvinyl chloride.

Technique of Tracheostomy

Approaches—(1) *Vertical midline* incision—It extends from cricoid cartilage to sternal notch. It is used in emergency and often in elective tracheostomy. Tracheal stenosis less likely in this incision and spontaneous closure is much rapid in this compared to horizontal incision. It gives rapid access with less dissection but leads to poor scars. (2) *Horizontal* incision—It can be used in elective tracheostomy. It is placed two—three finger breadths/midway between cricoid cartilage and suprasternal notch with a length of about 5 cm transversely. It has got a better cosmetic scar. Need for more dissection is the drawback but is commonly used now for elective tracheostomy. (3) *Percutaneous approach* using a needle, cannula, guidewire, and serial plastic dilators then tracheostomy tube is inserted **(Fig. 7-23)**.

Neck of the patient is *hyperextended* by placing sandbags under the shoulder. Vertical (midline) or horizontal incision is made. Deep fascia is opened. Strap muscles are retracted laterally. Isthmus is divided or retracted *upwards*. Inferior thyroid veins may cause bleeding and needs careful ligation. A few drops of lignocaine are instilled into the trachea to suppress the cough reflex. Trachea is fixed with tracheal hook. 2nd and 3rd or 3rd and 4th tracheal rings are opened and circular opening is made or a tracheal flap (*B'jork flap*—flap sutured to inferior margin of the incision) with base downwards is made. In elderly with calcified stiff tracheal, cartilage rings are excised otherwise flap is commonly used. Tracheostomy tube is placed. It is tied around the neck. Usually 8.0 or 8.5 sized tracheostomy tubes are used. If the patient is having endotracheal tube as it is common in many situations, anesthetist will remove the endotracheal tube and tracheostomy tube is inserted and connected to ventilator immediately. Proper suctioning of the trachea prior to insertion of the tube is better. Skin incision is sutured or packed to prevent formation of subcutaneous emphysema **(Figs 7-24A to I)**.



Fig. 7-21: Fuller's biflanged tracheostomy tube.



Fig. 7-22: Chevalier Jackson's tracheostomy tube.

Indications for tracheostomy
Respiratory obstruction due to:
- Acute infections causing oedema larynx.
- Trauma
- Neoplasms- benign/malignant
- Foreign body
- Bilateral abductor palsy
- Congenital causes.

Respiratory secretions due to:
- Inability to cough-tetanus, head injury, neurological causes, strychnine poison
- Painful cough in chest injuries, pneumonia
- Aspiration of secretions.

Respiratory insufficiency due to chronic lung diseases like emphysema, chronic bronchitis, bronchiectasis.



Fig. 7-23: Vertical midline or transverse incisions are used for tracheostomy. ***Vertical midline*** extends from cricoid cartilage to sternal notch. It is used in emergency and often in elective tracheostomy. Tracheal stenosis less likely in this incision and spontaneous closure is much rapid in this compared to horizontal incision. It gives rapid access with less dissection but leads into poor scar. ***Transverse incision*** can be used in elective tracheostomy. It is placed two–three finger breadths/midway between cricoid cartilage and suprasternal notch with a length of about 5 cm transversely. It has got a better cosmetic scar. Need for more dissection is the drawback but is commonly used now for elective tracheostomy.

Note

- First tracheal ring should never be used to do tracheostomy as perichondritis of cricoid cartilage with stenosis can occur—subglottic stenosis.
- Skin should not be sutured or loosely sutured to prevent development of subcutaneous emphysema.
- Cautery should be used during tracheostomy as much as possible to prevent oozing/bleeding from places like muscles, tracheal cut edge. Often torrential haemorrhage known to occur which may need a reexploration to control bleeding.
- In children trachea is soft and compressible and may get displaced easily and dissection may injure recurrent laryngeal nerve or carotid. Procedure is done under general anaesthesia with endotracheal tube in place or after insertion of bronchoscopy. Neck extension in children may cause innominate vein, thymus and pleura to pull upward allowing their possible injury. Silk sutures should be placed on the trachea prior to incising it. Trachea should


Position- Neck extended with sand bag under shoulder
After cleaning and draping local anaesthesia is injected
A
Vertical midline or horizontal (2-3 fingerbreadth above the suprasternal notch) incision is placed
B
Dissection subcutaneous plane, deep fascia and strap muscle planes
C
Dissection and exposure of trachea with retraction of the wound
D
Exposing and cutting the tracheal cartilage as a flap
E
Raising the flap and exposing the tracheal lumen
F
Insertion of the tracheostomy tube
G
Fixing of the tube and inflating the balloon
H
I

Figs 7-24A to I: Steps in tracheostomy.

not be excised in children; only it should be incised. Tracheostomy tube size should be carefully selected. Too lengthy tube will impinge on carina. Only portex tube should be used. Metallic tube is not advisable in children.

Tracheostomy Care

Regular suctioning and cleaning of the tube is needed. Humidification of the inspired air is done using normal saline/ringer lactate/acetylcystine mucolytic agent to liquefy secretions or crusts so as to prevent blockage. Constant observation of the patient for block, bleeding, and periodic deflation of the cuff of the tube for short period to prevent pressure necrosis of tracheal mucosa, prevention of infection are the other care required.

Decannulation of tracheostomy should be done with care especially in children as sudden respiratory distress can occur and in such occasion emergency re-insertion of the tube should be done. Cuff deflation and decannulation is done when patient is able to maintain airway and regains adequate swallowing reflex. Initially it can be changed to metal tracheostomy tube. Once patient breathes well properly, regains normal cough reflex tracheostomy tube is entirely removed and wound is sealed with dressing. Opening closes spontaneously in few days on its own. Tracheostomy set is kept ready at bedside for emergency insertion in case if patient finds difficult to breathe again. Post-decannulation respiratory distress may be due to sustenance of existing pathology; tracheal obstruction due to granulation tissue, oedema, subglottic stenosis, tracheomalacia, tracheostomy dependency.

Flexible bronchoscopy may be needed to clear the lower airway through the tracheostomy tube **(Figs 7-25 to 7-28)**.

Functions of the tracheostomy

- Alternate pathway for respiration bypassing the upper airway.
- It decreases the dead space by 50% and reduces the resistance to airflow so as to improve the ventilation.
- It prevents aspiration in bulbar palsy, coma, and haemorrhage from larynx/pharynx.
- In injuries of head, chest, abdomen, in respiratory paralysis lower airway is kept clean and patent by doing suction of the secretions through the tracheostomy tube.
- Tracheostomy is better and ideal for intermittent positive pressure respiration (IPPR).
- To give general anaesthesia when endotracheal intubation is not possible.

Complications of Tracheostomy

Bleeding, aspiration of blood and secretions, sudden apnoea which is due to sudden washing out of CO_2 (sudden removal of the respiratory stimulant). 5% CO_2 in oxygen is administered in such situation, Pneumothorax, surgical emphysema in the neck, mediastinal emphysema, injury to adjacent structures like oesophagus, recurrent laryngeal nerve, thyroid gland, tracheal stenosis, laryngeal stenosis due to perichondritis of cricoid cartilage, tracheitis/tracheobronchitis, displacement/blockage of the tube or erosion of the tube into major vessels, tracheooesophageal, tracheoarterial fistula.

In children thymus and innominate vein may be in the lower neck crossing the trachea which may be injured during tracheostomy.



Fig. 7-25: Advanced secondaries in neck with tracheostomy tube to control respiratory stridor.



Fig. 7-26: Permanent tracheostomy is done in a patient who underwent total laryngopharyngectomy for carcinoma larynx. Patient is on nasogastric tube for feeding purpose.



Fig. 7-27: Tracheostomy in position connected to ventilator.



Fig. 7-28: Tracheostomy track without tube in situ.

Nursing care

- Consent should be taken
- Materials like tracheostomy tubes (8.5 size), sterile gown, drapes, gloves, cap, mask, tracheostomy sterile set, gauze, local anesthetic agent, suction apparatus and tubes, connecting tubes to ventilator, sterile syringes should be kept ready.
- During procedure the patient is monitored for vital signs.
- Proper nursing care of the tracheostomy tube is done like, humidifying, cleaning, suction, care of the wound, checking of cuff pressure.
- Tracheal dilator and additional tracheostomy tube should be kept ready at bedside in case of blockage of existing tube/balloon not getting inflated to replace with a new one.
- Absolute asepsis like scrubbing hands, using sterile equipments are essential.
- Sterile suction tubes should be used.
- Care of inner tube is essential in case of metal tracheostomy tube.
- Regular dressing of the wound is needed. Antibiotics are required to prevent pulmonary sepsis.

CIRCUMCISION

Indications

- Religious.
- Phimosis.
- Paraphimosis after doing initial dorsal slit.
- Balanitis and balanoposthitis (common in diabetics).
- Early carcinoma of prepuce or glans penis - both diagnostic as well as therapeutic purpose.
- Certain sexually transmitted diseases, e.g. Herpes infection.

Procedure

In children it is done under general anaesthesia. In adults it is done under local anaesthesia.

After cleaning and draping, Local anaesthesia (1% lignocaine *(plain)* is injected circumferentially near the root of the penis (ring block). Dorsal skin is cut up to the corona and later circumferentially and ventrally. The skin is cut with inner layer. Care is taken to see that only optimum (less) skin is cut ventrally to prevent the occurrence *of chordee*. Frenular artery is transfixed and ligated ventrally using chromic catgut (2-0 or 3-0). Small bleeders are also ligated. Skin is apposed to the cut edge of corona using interrupted chromic catgut sutures—3 zero. Postoperatively, antibiotics and analgesics are given **(Figs 7-29 and 7-30)**.

Plastic Cap—Hollister Bell Cap Technique

This cap is fitted over the glans penis and prepuce is rolled over it. A tight ligature is tied over it near base of the prepuce. In 7 days skin and prepuce sloughs off and is shed with the cap. Bleeding will not occur due to thrombosis of prepuceal vessels. Technique can be used for religious circumcision/balanoposthitis without phimosis. It is contra-indicated in phimosis and paraphimosis.

Complications

(1) Reactionary haemorrhage due to slipping of ligature from frenular artery or dorsal vein—Here patient presents with pain, swelling, dressing soaked with blood. Vitals are normal. Wound reopened under local anaesthesia; bleeder is identified after removal of the clot; it is securely ligated and wound closed again. (2) Infection. (3) Stricture urethra near the external meatus in children. (4) Chordee due to removal of excess skin on the ventral aspect. (5) Rarely priapism can occur.

DORSAL SLIT OF PREPUCE

Indications

Paraphimosis; to do biopsy from a growth underneath the prepuce either in the glans or in prepuce itself.

After cleaning and draping, xylocaine plain (1%) is injected into the root of the penis circumferentially. Using two mosquito forceps oedematous prepuceal skin is held. Dorsally skin in midline is cut. Fibrous ring/constriction ring proximally is identified and is cut. Once released properly skin will move freely. 'V' shaped cut edge is sutured with continuous plain/chromic catgut. Dressing is placed over the wound. Patient needs formal circumcision at a later period (after 3 weeks) once oedema subsides **(Figs 7-31 and 7-32)**.



Fig. 7-29: Circumcision technique.


A
B
C
D
E
F
G
H
I
J
K
L

Figs 7.30A to L



Figs 7.30M to X

Figs 7-30A to X: Operative steps of circumcision.



Fig. 7-31: Paraphimosis developed after urethral catheterisation. It needs manual reduction using lignocaine jelly or dorsal slit to release it by cutting the constriction band on the dorsum of the penis.

EXCISION OF THE SWELLING

Swellings like sebaceous cyst, lipoma, pyogenic granuloma, papilloma are excised usually under local anaesthesia. Dermoid cyst which is extending into the deeper plane should be excised under general anaesthesia.

After cleaning and draping, xylocaine 1% injection is infiltrated around the swelling and underneath the swelling by lifting the swelling.

Incision

The following incisions are indicated in different situations **(Figs 7-33 to 7-36):**

- In sebaceous cyst *elliptical incision* is placed encroaching the punctum.
- In swellings like lipoma/ganglion *linear incision* is placed.
- In swelling like papilloma/pyogenic granuloma *circumferential elliptical incision* covering the entire lesion is placed.


A
Constriction ring
B
Dorsal slit
C

Figs 7-32A to C: Paraphimosis showing constriction ring and dorsal slit over the ring.


Elliptical incision partially occupying the swelling - includes punctum in this
Straight incision over swelling
Elliptical incision occupying the entire swelling (circumferential)
Circular incision widely away from the lesion with lesion at the centre

Fig. 7-33: Different incisions used as surgical approaches to remove swelling.



Fig. 7-34: Excision of papilloma with circumferential incision.


Marking incision
Making incision
Ganglion exposed and wound edges are retracted
Dissection using 15 no blade and fine curved scissor
Suturing skin wound and applying 4" crepe bandage
A
B
C
D
E

Figs 7-35A to E: Steps in excision of ganglion.

- *Circular or oval incision* is used whenever wide excision is needed or skin grafting is planned over it like excision of basal cell carcinoma lesion, etc. Such excision once done it is often difficult to close the defect primarily but needs skin grafting or flap locally.

Procedure

Skin flaps on either side are raised adequately until edge of the swelling is clearly seen. Using scissor sharp dissection is done to remove the entire swelling. Bleeding points are cauterised/ligated. Skin is closed using non-absorbable monofilament polypropylene/polyethylene 3-zero sutures.

In a ***sebaceous cyst***, capsule should be removed completely otherwise recurrence can occur. Often avulsion of the capsule also is done to complete the procedure. Punctum should be in the centre of the elliptical incision; length of the ellipse should be equal to the diameter of the cyst. Width of the incision varies, depends on the proper skin apposition achievement during closure. Stretched skin over the cyst (scalp, face) allows wider ellipse; in unstretched skin like in back, narrow ellipse is made. It is easier to begin the dissection at the ends of the elliptical incision than on the summit. Natural plane should be reached by sharp dissection and later blunt dissection can be used over the surface of the capsule. Sharp dissection is done using cautery or scissor or no 15 blade. Artery forceps or mosquito forceps (Halsted) are used to create the plane. Skin hook, fine retractors are needed. If cyst punctures, cyst wall is held up for traction to visualize the plane for dissection. Often cyst is deliberately punctured on the summit and traction is given to the cyst wall to proceed with dissection. If there is more inflammation, wound is left open to granulate and heal. In infected sebaceous cyst, excision is not done; only incision and drainage is done. It is difficult to identify the cyst capsule and poor scarring results if any attempt is made. Often it is observed that cyst wall lining gets destroyed completely causing no recurrence even by only drainage in severely infected cyst **(Figs 7-37 and 7-38)**.

In lipoma linear incision is deepened until capsule of the lipoma is reached. Colour of lipoma is different from surrounding fat and lobules are larger. Squeezing out or winkling of lipoma through the incision can be done using finger which minimises the length of the incision. Retraction, counter traction, sharp and blunt dissection is needed for excision. Large lipoma also can be easily excised under local anaesthesia. Diffuse lipoma needs general or regional anaesthesia for excision. Lipoma in certain locations like back often is adherent to muscles or has extension into muscle plane. In such occasion, muscle should be spilt and small vessels should be ligated or cauterized for proper complete excision (general anaesthesia is needed). In a large swelling like of large lipoma drainage tube may be kept for 48 hours. Dressing is placed. Antibiotics and analgesics are given. Suture removed in 5-8 days. Liposuction for removal of lipoma is not ideal.

In wide excision of basal cell carcinoma (BCC), circular incision around the lesion is made with 5 mm clearance. Deeper plane should have 3 mm clearance. Depth clearance is very important as BCC is locally invading tumour. Frozen section biopsy to confirm the clearance of the margin and deeper layer is important. After excision raw area is covered with split skin grafting or by local flaps, depends on the extent and site of raw area. Rhomboid flap, transposition flap, other local flaps, skin grafting are the methods used to cover the defect. Recurrence rate for BCC is 2%. *MOHS*—Microscopically oriented histographic surgery is used often in BCC, SCC and solar keratoses which is described by Mohs. It is excision in layers with horizontal frozen section control. BCC is sensitive for radiotherapy but lesions in pinna, lacrimal canaliculi and those in close proximity to eye are contraindicated for radiotherapy **(Figs 7-39A to I).**


Cleaning the area over the swelling
Draping the area
A
Injecting local anaesthesia Xylocaine 1 or 2%
B
Incision
C
Dissection
D
Dissection
E
Dissection
F
Wound after excision
Suturing
G
Specimen with content
Dressing
H

Figs 7-36A to H: Excision of cyst—steps. Often it is necessary to place elliptical incision around the punctum in case of excision of sebaceous cyst with punctum.

In wide excision of squamous cell carcinoma it is similar like BCC. Clearance margin kept is 1 cm. Frozen section biopsy for confirmation of clearance from margin and depth is a must. Defect is closed by transposition/rotation flap/skin grafting depends on location of the carcinoma. Disarticulation of the toe/ray amputation/forefoot amputation/below knee amputations are done for recurrent or wider or deeper or aggressive disease. Regional lymph node block dissection is done (ilioinguinal/axillary/neck) if nodes are positive by FNAC. It is usually/ideally done in same sitting now; but may be postponed for 3 weeks. Radiotherapy/cryosurgery/laser are other methods used


Elliptical incision
Punctum
Sebaceous cyst
A
B

Figs 7-37A and B: Sebaceous cyst with elliptical incision encroaching the punctum.


Giving local anaesthesia and making elliptical incision
Dissection at the corners and sides and underneath to excise the cyst
A
Suturing the wound with mattress sutures
B

Figs 7-38A and B: Steps in sebaceous cyst excision.

for primary disease. Chemotherapy using 5 fluorouracil/adriamycin/vincristine/cis platin are also added **(Figs 7-40A to D)**.

Mohs surgery, also known as **chemosurgery**, originated by a general surgeon, ***Dr Frederic E Mohs***, is microscopically controlled surgery (*Microscopically oriented histographic surgery*) used to treat common types of skin cancer. Complete *circumferential peripheral and deep margin* assessment is the key feature. *Mohs micrographic surgery* is an advanced treatment process for *non-melanotic skin cancer* (basal cell cancer, squamous cell cancer, sebaceous carcinoma, extramammary Paget's disease, dermatofibrosarcoma


A
B
5 mm margin clearance
3 mm depth clearance
C
Making circular incision around using 15 no blade
D
Excision using cautery, no 15 blade, scissor
E
Excised specimen
F
Raw area
G

Figs 7.39A to G

protuberans, etc.) that offers the highest possible cure rate for many skin cancers and simultaneously minimises the sacrifice of normal tissue. Mohs section should include 100% of the epidermal margin, but greater than 95% is often accepted. Ideally 100% of the epithelial margin should be available to be reviewed on serial sectioning of the Mohs specimen. The team consists of the Mohs surgeon, histotechnician, pathologist and the reconstructive surgeon. The *Mohs surgeon* identifies the cancer and its margin, often with the aid of dermatoscopy. He removes the cancer under local anaesthetic and prepares it for histology processing. This is accomplished by cutting the specimen (if required), staining the specimen for orientation, and sending it to the lab. The *histotechnician* prepares the tissue for Mohs processing by flattening the surgical margin on a flat surface first. Then the flat surgical surface is mounted on a cryostat to be sectioned and prepared for glass slides to be read by the pathologist. The *pathologist* examines the slide for residual tumours, and marks the location of the tumour on the pathology report and sends it back to the Mohs surgeon. Completion of surgery with margin clearance is informed to Mohs surgeon by the pathologist. Defect is covered by a reconstructive/*plastic surgeon.*



Figs 7.39H and I

Figs 7-39A to I: Wide excision of BCC and split skin grafting over it with tie over dressing. Graft has taken up well when seen after 5 days.

Mohs surgery is performed *in four* levels—(1) Surgical removal of tissue (Surgical Oncology). (2) Mapping the piece of tissue, freezing and cutting the tissue between 5 and 10 micrometers using a cryostat, and staining with hematoxylin and eosin (H&E) or other stains (including T. Blue). (3) Interpretation of microscope slides (Pathology). (4) Reconstruction of the surgical defect (Reconstructive Surgery). The procedure is usually performed under local anaesthesia, can be as day care surgery. A small scalpel is utilised to cut around the visible tumour. A very small surgical margin is utilised, usually with 1 to 1.5 mm of free margin or uninvolved skin. The amount of free margin removed is much less than the usual 4 to 6 mm required for the standard excision of skin cancers. After each surgical removal of tissue, the specimen is processed, cut on the cryostat and placed on slides, stained with H and E and then read by the Mohs surgeon/ pathologist who examines the sections for cancerous cells. If cancer is found, its location is marked on the map (drawing of the tissue) and the surgeon removes the indicated cancerous tissue from the patient. This procedure is repeated until no further cancer is found. Anticoagulants are commonly used along with Mohs surgery.

Mohs procedure is very useful for BCC (98-100% cure rate). It is also useful in SCC (90-94% cure rate).

In excision of melanoma—clearance is needed is more than BCC/ SCC as it is more aggressive. Clearance to be achieved is decided based on thickness and penetration of the lesion. 1 cm clearance is done for less than 1 mm thickness lesion; 1-2 cm clearance for 1-2 mm thickness; 2 cm clearance for 2-4 mm thick lesion. As incision biopsy of the primary lesion is not done, in clinically suspected lesion initial 2 mm clearance excision of suspected lesion is done with immediate *paraffin section* study. Once report confirms the diagnosis with depth/thickness accurately in mm definitive wide excision and reconstruction is done at a later period. Frozen section


A
B
Defect in the scalp after wide excision
Excised specimen outer look
Excised specimen inner look
C
Transposition flap in the scalp with skin grafting
D

Figs 7-40A to D: Squamous cell carcinoma scalp. Wide excision is done. Transposition flap is done to cover the defect. Flap donor area is covered with split skin graft.

is of no use for depth/thickness assessment, paraffin section study is essential to plan the final clearance and predict the prognosis. Thickness in mm is the most essential factor in melanoma as far as primary is considered. Reconstruction may be by flap or ski grafting depending on the location of the lesion. Donor area should be from opposite side limb in case of lesion in the limb as secondary deposit may occur over the denuded donor raw area. Digital amputation/disarticulation are needed for digital melanoma. Amputation of proximal phalanx may be sufficient if lesion is in the subungual site otherwise disarticulation is needed. Presently prophylactic regional node dissection is not done as systemic spread is also deciding factor in melanoma prognosis. Sentinel node biopsy is better and ideal to decide for block dissection. Radiolabelled colloid is injected to the lesion around day before the surgery. Preoperative scintigraphy is done or node is identified using hand held gamma camera. Radiolabelled colloid slowly reaches the node but stays there long time. It is often done in combination with blue dye injection intraoperatively which reaches the node rapidly in 10 minutes but disappears from the node early. Positive sentinel node biopsy indicates regional block dissection. Melanoma is not radiosensitive and so it is used only in intracranial and spinal secondaries. Chemotherapy has also got fewer roles but is commonly used postoperatively using melphalan and DTIC. Isolated limb perfusion even though practiced in many centers, its benefits are not proved. Laser, MOHS, cryosurgery has not commonly used in melanoma **(Figs 7-41 and 7-42)**.


Melanoma under little toe and in interdigital space
A
Lesion
Incision for wide excision with disarticulation for toes
B
Deepening the incision
C
Deepened incision on the plantar aspect
Lesion
D
Defect after wide excision
E
Split skin donor area from opposite thigh
F
SSG placed over the defect with long ties from the edge for tie over
G
Tie- over dressing
H
Specimen of melanoma in interdigital space
I

Figs 7-41A to I: Wide local excision of melanoma with disarticulation of toes. Skin grating is done to cover the defect. Flap is ideal in many places like plantar aspect of the foot but technically difficult.

Note:

- *Enucleation* is removal of the swelling within the tissue of origin with normal part of tissue of origin is being retained. Example—Enucleation of prostate in benign prostatic hyperplasia (BPH).
- *Excision* is removal of tissue/tumour entirely with its capsule.
- *Wide excision* is removal of tumour with surrounding tissue margin adequately for clearance.
- *Compartment excision* is removal of tumour/diseased tissue with all adjacent soft tissues in one compartment except neurovascular bundle. It is done in limbs for soft tissue sarcoma as a curative but limb saving procedure.
- *Radical excision/radical block dissection* is removal of tumour widely with adjacent soft tissues with lymph node dissection.
- *Retraction, traction/counter traction, sharp* and *blunt* dissection is needed for excision. In inflammatory area or adherent area sharp dissection using diathermy or scissor or no. 15 blade is done. When there is proper plane with loose areolar tissue, blunt dissection is done using finger or peanut. Blind dissection should be avoided.

LYMPH NODE BIOPSY

Indications

- Lymphoma to find out the grade, type of lymphoma.
- Secondaries in the lymph node only when FNAC is inconclusive but clinically node is significant. Significant node is one which is based on size (variable in different locations and type of primary



Figs 7-42A and B: Wide excision of a melanoma in sole with split skin grafting.

but hard node > 1 cm is significant) and texture (hard) probably harbouring tumour spread. FNAC is the first choice in secondaries as biopsy of node may block the lymphatics and may allow spread of tumour to next level of nodes.

- Tuberculosis of lymph node.
- Rare lymphatic diseases.

Site of Node Selection for Biopsy

- Neck nodes—superficial/deep.
- Axillary node.
- Groin node—these nodes can often be non-specific because of repeated recurrent inflammation. Hard, large sized node can be considered as significant.
- Abdominal nodes are biopsied using laparoscopy. Thoracoscopic biopsy or mediastinoscopic biopsy of lymph node is also done.

Procedure

Lymph node biopsy *ideally* should be done under *general anaesthesia*. Superficial nodes/nodes in upper posterior triangle may be removed under local anaesthesia—xylocaine 1%.

After cleaning and draping, incision is placed. Incision is decided depending on the site of the lymph node. It is usually horizontal in the neck over the lymph node. It is better to mark the incision line using marking ink. Adequate incision is a must otherwise technique will be difficult. After skin incision, fascia is incised. Lymph node is identified based on shape, color and texture. Node is separated from adjacent structures. Node is held using Lane's tissue holding forceps. One should avoid breaching the capsule as much as possible to retain the lymph node architecture. After removal haemostasis is maintained. Diathermy or ligation using fine absorbable sutures (polyglactic acid) is used. (Earlier surgeon used to cut the node to see the interior texture and to get imprint cytology over a slide; but now pathologists prefer to send the node without cutting). It is fleshy in Hodgkin's lymphoma. It is yellowish caseating in tuberculosis and dark, haemorrhagic in secondaries. Skin is closed with interrupted sutures using monofilament non-absorbable sutures or absorbable subcuticular sutures. Sutures removed in 7 days.

Ideally entire one node with its intact capsule should be removed especially in lymphomas. Many times it may be difficult because of fibrosis and adherent lymph nodes **(Figs 7-43A to F)**.

Lymph node can be studied as histology slides, culture, AFB staining, AFB culture or other special staining for fungal infection. Immunohistochemistry has got major role in lymphoma.

Often when result is inconclusive repeat biopsy may be needed.

Complications and Difficulties

Bleeding is due to injury to small or major vessels (jugular veins in neck; femorals in groin; axillary vein or branches in axilla). Adjacent nerves also may get injured (accessory, intercostobrachial, femoral). Sepsis, haematoma formation, lymph ooze, fungation may be other problems.

LIVER BIOPSY

It is removal of bit of the liver tissue percutaneously for histological purpose.

Prerequisites

Prothrombin time should be normal before doing liver biopsy, otherwise severe bleeding can occur. Normal value of prothrombin time is 12-16 seconds (It is compared to control and difference should be less than 4 sec between test and control). It is corrected by giving injection vitamin K 10 mg IM for 5 days. Even after that if repeat PT is still high then fresh blood transfusion (FFP) is transfused to correct it.

If ascites is present, tapping should be done prior to liver biopsy.

Blood grouping and cross matching should be done.

Indications

(1) Cirrhosis, chronic hepatitis, haemochromatosis, Wilson's disease. (2) Hepatoma. In secondaries liver biopsy is usually not done as it may precipitate failure or ascites formation. (3) Granulomatous liver diseases, metabolic and storage diseases, familial diseases. (4) Unexplained long-term fever wherein all other usual investigations are normal. (5) Chronic hepatitis, biliary atresias.


Lymph node biopsy-general anaesthesia position, incision mark
A
Cleaning, draping, incision
B
C
Retraction, exposing the lymph node
D
Dissecting the lymph node clamping the vessel
E
Entire lymph node is removed-intact
Wound sutured
F

Figs 7-43A to F: Technique of lymph node biopsy.

Contraindications

Bleeding diathesis, platelet count below 60,000, widened prothrombin time, Hydatid disease, wherein it will precipitate anaphylaxis, haemangiomas, ascites, infection in close proximity—lung/diaphragm/peritoneum and liver congestion.

Procedure

Patient should be nil oral for 6 hours. Injection atropine 0.6 mg intramuscularly should be given. Patient will be lying on his back very close to the edge. Often 30° propped up position is used. After cleaning and draping, 9th intercostal space in the midaxillary line is marked. Xylocaine 1% is injected into the skin, subcutaneous tissue, deeper tissues up to liver capsule. He or she is then asked to lie on the back with the right elbow to the side and the right hand under the head. The patient is instructed to lie as still as possible during the procedure. He or she is warned to expect a sensation resembling a punch in the right shoulder, but to hold still in spite of the momentary feeling. Needle used is either *Vim-Silverman needle or Menghini needle* (better option).

Using Vim Silverman's needle—It has got three parts—trocar, cannula and split (biflanged) needle **(Fig. 7-44)**. Trocar snugly fits properly into the cannula. Trocar with cannula is passed into the liver tissue when patient holds the breath in deep inspiration. Trocar entering


Trocar with cannula
– both of equal size - snugly fits
Trocar
Cannula
Cannula
Split needle (Biflanged) is longer than cannula

Fig. 7-44: Vim-Silverman needle.

the liver tissue can be felt. Patient is asked to breath comfortably relaxed. Trocar is removed. Split needle is much longer than cannula. It is held in the hand to keep ready for penetration into the liver. Patient is again asked to hold the breath properly. Split needle is passed fully to core the liver tissue beyond the existing cannula; cannula is pushed further over the split needle to include the cut liver tissue; cannula with split needle is rotated 180°; cannula with needle is removed entirely. Split needle is carefully removed and opened to collect the cut liver tissue for biopsy. Patient is asked to breath normally afterwards. Procedure can be repeated once again. Further repetitive procedure to get more tissue in the same sitting is not advisable due to risk of liver injury and bleeding. Tissue is often collected in *Bouin's solution* which contains 75% picric acid.

Presently guided liver biopsy is commonly recommended and popular i.e. U/S guided, CT guided, laparoscopy guided.

Menghini needle method—Percutaneous liver biopsy is done with a special hollow needle, called as Menghini needle, attached to a suction syringe. 3 ml sterile saline is taken into the syringe with specific Menghini needle **(Fig. 7-45)**. Once needle is inside the intercostal space after injecting local anesthesia, 2 ml of saline is injected to clear the skin fragments in it. Aspiration vacuum is created in the syringe and kept like that and needle is forwarded into the liver. Meantime patient should hold his breath completely in expiration. Needle is connected the syringe with already created vacuum and withdrawn immediately. It will contain sucked liver tissue which is carefully collected on a glass receptacle containing saline. This method is safer and reliable.

The traditional Menghini needle is 6 cm long with an oblique tip slightly convex towards the outside. A retaining device is incorporated into its proximal end to prevent liver tissue from being aspirated into the syringe. The diameter of the needle usually does not exceed 1.4 mm. A penetration limiter is often utilised in children and thin adult patients to limit the depth to which the needle advances. The patient is asked to inhale slightly and exhale maximally and then hold his breath in a maximum exhaled position. At this point, steady suction is applied to the syringe, which is connected to the needle, and the needle is advanced into the liver and withdrawn.

Features of biopsied liver tissue are—float in water in fatty liver; fragmented small pieces in cirrhosis; dull white coloured in malignancy; green coloured in biliary cirrhosis; chocolate coloured in Dubin-Johnson's syndrome.

Post-Procedure Observation

Complications develop commonly within 24 hours. Rest, observation with monitoring of pulse, blood pressure and respiration is essential. Heavy work and exercise should be avoided for 7 days. Routine work after 24 hours is safer. Shoulder pain on right side may be warning sign and needs evaluation using chest X-ray and ultrasound.



Fig. 7-45: Menghini needle.

Complications

Haemorrhage, bile leak and biliary peritonitis, infection, injury to gallbladder, colon, kidney. Hepatic coma/failure may be precipitated in cirrhotic patients

Causes of Failure in Liver Biopsy

Cirrhosis, emphysema, uncooperative patient, improper technique.

KIDNEY BIOPSY

Kidney biopsy is done as diagnostic or prognostic indications.

Indications are—asymptomatic proteinuria, nephritic syndrome, glomerulonephritis. It is mainly used in medical causes.

Contraindications are—unilateral kidney, totally shrunken kidney, infections, cystic diseases, hypernephroma, bleeding diathesis. Prothrombin time and platelet count should be assessed. X-ray KUB, ultrasound is done to assess the size of the kidney.

Procedure is done *in prone lying down position* under ultrasound guidance. Procedure is done on the diseased side; in bilateral disease *left side* is preferred. Point of entry of needle is decided under US guidance. Xylocaine local anaesthesia is injected. Needle is passed across skin, subcutaneous tissue, and muscles. While patient is asked to hold the breath, needle is entered into the kidney. When patient breathes back needle moves with respiration. Tissue is aspirated with negative pressure. Needle is removed. Post-procedure period patient is observed for pain, haematoma and bleeding. Bed rest is needed for 24 hours.

Complications

Pain, haematuria, infection, abscess formation, perirenal haematoma, injury to colon, etc.

BONE MARROW ASPIRATION

It is done for diagnostic and prognostic purpose in various conditions aplastic anaemia, aleukaemic leukaemia, lymphomas, myeloproliferative diseases, myelofibrosis, multiple myeloma, agranulocytosis. It can be done in refractory or iron deficiency anaemias, leukaemias, tropical diseases, storage diseases. Bone marrow transplantation is a therapeutic method. Blood dyscrasias are contraindications.

Usual *site* is sternum (mid manubrium). Other sites are—spinous process of lumbar vertebra, iliac crest. After injecting local anaesthesia, bone marrow aspiration needle with the guard at 1.5 cm from the tip of the needle is punctured through the skin at sternum perpendicularly. *Guard* prevents inadvertent deeper penetration of the needle. Needle is pushed in boring/screwing movements. Sudden giving way suggests the entry of the needle into the bone marrow. Stillete is removed. 0.5 ml of bone marrow fluid is aspirated using 1 ml syringe. Material is smeared in slides also. After removal of the needle, pressure is applied over the site to prevent bleeding and haematoma formation.

Complications

Bone pain, haematoma, infection, injury to great vessels. Normal compositions of bone marrow are—blood cells, blood vessels, reticulum and fatty tissue.

Causes for *dry tap*—technical; myelosclerosis, carcinoma, hyper or hypoplasias. *Analysis of bone marrow is done for*—erythropoiesis, leukopoiesis, megakaryocytes; cellularity, myeloid-erythroid ratio (3:1); presence of parasites and different bodies.

LUMBAR PUNCTURE

It is aspiration and collection of cerebrospinal fluid (CSF) from the spinal subarachnoid space by passing a needle into the space between lumbar 2nd and 3rd vertebra or 3rd and 4th vertebra.

Indications

Meningitis, subarachnoid haemorrhage, neurosyphilis, unexplained coma, Guillain Barré syndrome, multiple sclerosis, during myelography, to introduce drugs into the CSF, for spinal anaesthesia, in hypertensive encephalopathy.

Contraindications

In raised intracranial hypertension if lumbar puncture is done, herniation of brain trough foramen magnum can develop leading into sudden death. Suspected cord compression is also a contraindication. Back pain, sciatica, syringomyelia, sepsis, allergy are other contraindications.

Procedure

Patient is positioned in lying down side position with knee fully flexed and head flexed. Sitting and bending forward is another position often used. 3rd lumbar vertebra is at the level of highest point of iliac crest. Entire back is cleaned with savlon/povidone iodine and draped. Xylocaine injection is infiltrated (5 ml) subcutaneously and up to ligamentum flava. Lumbar puncture needle with stillete is introduced into the space. Cutting edge of the bevel of the tip of the needle should be parallel to fibres of ligamentum flava. It is directed upwards and forwards at 5° through resistance of supraspinous ligament. Needle is then passed through interspinous ligament, ligamentum flavum and dura mater of spinal cord. Giving way sensation of entering the subarachnoid space is typical. Stilette is withdrawn. *Spinal fluid* is collected for biochemical, cytological and serological studies. Fluid will be clear with continuous drops (0.5 ml/second flow rate). A manometer is attached to lumbar puncture needle; pressure is applied over one jugular vein and then the other which causes raise in intracranial venous pressure and then intraspinal venous pressure which reflected in manometer. There is raise in fluid level in manometer quickly for about 100 mm and falls down slowly. It is possible only if pathway between lumbar puncture site and cranium is patent. Delay in this means spinal block—*Queckenstedt's test* **(Figs 7-46 and 7-47)**.

Normally CSF is formed at choroids plexus of lateral ventricle (95%), of 3rd and 4th ventricle, perivascular spaces of brain. It circulates from choroids plexus of lateral ventricle → foramen of Monro → lateral ventricle → Sylvian duct → 3rd ventricle → 4th ventricle → foramen of Luschka and Magendie → subarachnoid space → basal cisterns → circulations over brain and spinal cord. CSF is *absorbed* by arachnoid villi. *CSF* maintains intracranial pressure, gives shock absorption to cranium, and gives nutrition and excretion. *Normal CSF* formation is—1500 ml/day; total volume of CSF is 150 ml; clear in colour; 60-150 mm is the pressure in lying down and 200 mm in sitting position; pH is 7.35; specific gravity is 1.007; proteins is 20-40 mg%; sugar is 40-60 mg%; chlorides is 720-750 mg%; cells are 0-5 epithelial lymphocytes like cells. In CSF sugar, proteins, cholesterol, urea, calcium and phosphorus are less than that of blood; chlorides and magnesium are more than that of blood. Antibodies and enzymes are not seen in CSF. Penicillins, streptomycin will not cross blood-brain barrier and so not found in CSF.

Findings

CSF is turbid in pyogenic meningitis; cobweb in tuberculous meningitis; bloody in subarachnoid haemorrhage/trauma/bleeding disorders. Yellow CSF *(xanthochromia)* is seen in haemorrhage in CSF, high protein content like Guillain-Barré syndrome, spinal block or neurofibroma; jaundice patients; spinal tumours. *Proteins* in CSF are raised in meningitis, Guillain-Barré syndrome, intracranial tumours, spinal cord compression, disseminated sclerosis. Sugar in CSF is increased in diabetes mellitus, encephalitis. It is decreased in meningitis. Chlorides in CSF are decreased in meningitis and metabolic conditions.

Cohen's law of meningitis—Substances which are more in CSF than blood will reduce in meningitis and substances which are low in CSF than blood will raise with exception of sugar (sugar is less in CSF than blood normally; it reduces further in meningitis).

While giving *spinal anaesthesia* (xylocaine 5% in 6% dextrose of 2 ml; or bupivacaine 0.5% in 5% dextrose of 3 ml), bevel should face upwards (360° rotation). Syringe is aspirated to get clear CSF into it and the anaesthetic drug is injected. Needle is removed, area is cleaned and sealed.

Complications

Headache is the commonest complication. Plenty of oral fluids, intravenous fluids, head down position, bed rest, and analgesics are used to control it. Back pain, infection, meningismus, coning, bleeding, rarely paraplegia, converted to total spinal in spinal anaesthesia are other complications.

PLEURAL TAP (THORACOCENTESIS)

Indications

Pleural effusion both diagnostic as well as therapeutic. The fluid is sent for culture, cytology, microscopy, specific gravity, biochemical analysis like proteins for diagnosis of tuberculosis, malignancy. In empyema thoracis, for diagnostic purpose before placing an ICT, intrapleural administration of drugs pleural tap is being done.

Position

In sitting position, leaning forward over a wooden support.

Site

Tip of scapula at 7th intercostal space (posteriorly—scapular line), in midaxillary line.

Procedure is done in sitting and leaning forward over a support. Tapping is done from behind. After giving local anaesthesia (xylocaine 2% into skin, subcutaneous tissue, up to parietal pleura) wide bore needle (Abraham needle) is used to tap the fluid. Needle is passed


Posterior longitudinal ligament
Intervertebral disc
Anterior longitudinal ligament
L2
L3
L4
Vertebra
Spinal cord
Skin
Supraspinous ligament
Interspinous ligament
Lumbar puncture (LP) needle
Ligamentum flavum
Spinous process
Dura mater of spinal cord
Subarachnoid space

Fig. 7-46: Diagram showing lumbar puncture needle passing through different layers.



Fig. 7-47: Photo showing position and aspirating the CSF through lumbar puncture.

at right angles to the skin; in the intercostal space between two ribs; typical '*giving way*' feel of puncturing the parietal pleura is felt. Needle with stopcock (3-way) is used. 50 ml syringe is connected to the stopcock. Fluid is aspirated to syringe from pleura with stopcock in straight position. Then knob is turned right angle to empty the syringe to reservoir. Procedure is repeated to clear the fluid **(Fig. 7-48)**.

For diagnostic tap, 50 ml of fluid is aspirated to send for biochemical/cytological analysis and culture.

For therapeutic aspiration—750-1000 ml per day is aspirated. If more quantity is aspirated rapidly, pulmonary oedema may develop leading to often ARDS which may be life threatening.

Post tapping, patient should be monitored for change in breathing, tachycardia **(Fig. 7-49)**.



Fig. 7-48: Pleural tap. Note the position of the patient and placement of the needle.

Complications

Complications are Infection, dry tap or bloody tap, bleeding, development of pneumothorax occasionally, sudden vagal shock, pain and respiratory distress.

PERICARDIAL TAP (PERICARDIOCENTESIS)

Indications

Pericardial effusion due to any cause—viral, tubercular, rheumatic (rapidly progressive or not regressing in 4 weeks); haemopericardium; purulent pericardium **(Fig. 7-50)**.

Procedure

Atropine injection 0.6 mg with injection pethidine 100 mg intramuscularly half an hour prior to tapping is given. In supine position after giving xylocaine local anesthesia 1-2% needle is passed. A 16 or 18-gauge needle is passed into the pericardium just below the xiphoid process directing upwards and backwards towards left side—in the direction of midclavicular line with an angle of 45° to the surface. Under ECG and US guidance needle position is confirmed. Negative deflection in the ECG means needle is touching the heart and so needle should be withdrawn a little. ECG should show normal tracing. Post procedure monitoring is a must.


Position
A
Cleaning and draping -feeling the tip of scapula
B
Marking the site and injecting the local anaesthetic drug
C
Injecting the local anaesthesia-xylocaine
D
Pleural tap needle insertion
E
3 way stopcock
F

Figs 7-49A to F: Steps in pleural tapping with instruments used—needle, syringes, 3 way stopcock.


Heart border
Pericardial border
Pericardial fluid
Xiphoid process
Aspirating syringe with needle

Fig. 7-50: Pericardial tap—diagrammatic look.

This site is used because it is - most dependent for aspiration; unlikely to traumatize heart; pleura is not punctured; coronary vessels are not injured. Occasionally other sites are used—anteriorly in the left 5th intercostal space just outside the apex beat but within the cardiac dullness; posteriorly near inferior angle of scapula; in the left 4th intercostal space lateral to the sternum.

Presently U/S guided aspiration is commonly done. Procedure should be done under ECG monitor.

Complications

Injury to heart causing bleeding/ventricular fibrillation; infection; injury to coronary vessels. Life threatening haemopericardium may develop which may need immediate thoracotomy, pericardiotomy by cardio-thoracic surgeons. Air embolism, pulmonary oedema, vagal shock, circulatory collapse, injury to intercostal vessels, pneumothorax are other complications.

PERITONEAL TAP (ASCITIC TAP)

Indications

For diagnosis—abdominal tuberculosis, peritoneal secondaries, ascitic fluid study.

For therapy—in massive ascites to relieve distress and cardiopulmonary discomfort by removing fluid—in malignancy, portal hypertension. It is done in refractory ascites with failure of medical line of therapy.

Site

In the spinoumbilical line lateral to rectus abdominis muscle **(Fig. 7-51)**.


Liver
Rectus muscle
Ascites
Umbilicus
Anterior superior iliac spine
Ascitic tapping point - in spinoumbilical line, lateral to rectus muscle margin
Urinary bladder
- Bladder should be emptied
- Gradual decompression should be done
- Fluid should be sent for analysis and cytology

Fig. 7-51: Ascitic tap.

Procedure

Patient is asked to *empty the urinary bladder* or should be catheterized. Abdomen is percussed to confirm the dullness in the flank. Site of tapping is marked. Xylocaine 1% injection local anaesthetic is infiltrated. 20 gauge long needle is inserted into the peritoneal cavity. Ascitic fluid comes into the syringe. Syringe is connected to the 3 way stopcock to have controlled tapping.

For diagnostic purpose 50 ml of fluid is aspirated. Fluid is sent for culture/cytology/AFB/biochemical analysis.

To relieve distress 1500 ml/day is aspirated. If more quantity is aspirated sudden hypotension and cardiac arrest can occur. It is always safer to do procedure with an intravenous line with fluids flowing.

Complications and Difficulties

Infection and peritonitis can occur. Bleeding from the puncture site into the peritoneal cavity causing haemoperitoneum. Puncture into the bowel causing bowel injury. Protein depletion occurs after tapping of large quantity of fluid. Tapping may precipitate hepatic failure and coma in jaundice and severe liver cell dysfunction patients.

Negative tapping—In *loculated ascites* due to (commonly) abdominal tuberculosis, fluid may not get aspirated and so ultrasound guidance is needed to aspirate fluid. In females tense ascites should be differentiated from *large ovarian cyst* before tapping.

INTERCOSTAL TUBE DRAINAGE (ICT DRAINAGE)

It is the method of draining collections in the pleural cavity safely so as to make the lung to expand.

Indications

Haemothorax (trauma/malignancy), pneumothorax, haemopneumothorax, empyema thoracis, traumatic lung contusion, after thoracotomy to drain pleural cavity.

Procedure

Patient is in 30°-45° partial lying positions with backrest support. Under local anaesthesia (5 ml of 1% xylocaine injection), an ICT is placed in 6th intercostal space in case of haemothorax and pyothorax and in pneumothorax ICT is placed in 2nd or 3rd space.

A small (3 cm) transverse incision is made in midaxillary line (as the muscle bulk is less here and so passage of ICT is easier), parallel to intercostal space (above the rib, i.e. lower part of intercostal space to avoid injury to neurovascular bundle which are located in the groove in the lower part of rib). By blunt dissection using a haemostat, deeper layer is dissected; pleura is punctured. Air/blood/pus may gush out. Finger is inserted into the pleural space to confirm that pleural cavity has reached. 20 French size tube for air; 32 French size tube for blood is used. Tube with side openings is pushed into the pleural cavity. Other end is connected *to under water seal (200 ml of sterile water). Air –water column moving* with respiration can be observed. Tube is fixed with skin sutures. *Heimlich valve* is a plastic container with collapsible rubber tube that acts as a one way rubber tube also can be used. Ultrasound or CT guided placement of chest tube is done in loculated posterior or inferior pleural collection. Patient should be in sitting position in this posterior tube placement. *Three bottle chest drain system* is also often used **(Figs 7-52 and 7-53)**. First one is fluid collection chamber; second one is under water seal to prevent air entering into the pleura; third one acts as manometer for adjusting the suction transmission to the patient. Moulding disposable plastic units are available.

Usually for pneumothorax ICT is kept for 2-3 days (until lung expands—confirmed by check chest X-ray and air leak is not observed). For haemothorax and pyothorax it is kept for 4-6 days or until it stops draining (less than 100 ml/24 hours) and lung expansion is confirmed by repeat chest X-ray. To have a proper expansion of lungs patient is asked to blow football bladder/spirometer (balloon) breathing exercise). If there is broncho-pleural fistula, ICT should be placed for longer time until fistula heals **(Fig. 7-54)**.



Fig. 7-52: Intercostal tube drainage with under water seal.



Fig. 7-53: Intercostal tube drainage using three bottle thoracic drainage.



Fig. 7-54: Intercostal tube drainage in a patient with haemothorax.

Complications and Problems

Different complications are—Infection, displacement and inadequate functioning, injury to intercostal vessels and bleeding, injury to intercostal nerves, lung and mediastinum and pain at the site of ICT placement.

BRONCHOSCOPY

Indications

Diagnostic: To take biopsy in carcinoma lung, lung abscess, pulmonary tuberculosis.

Therapeutic: To remove foreign body, to suck out the bronchial secretions, tracheobronchial stenting in fistulas like tracheooesophageal fistula, malignancy, etc. **(Fig. 7-55)**.



Fig. 7-55: Bronchoscope.

Types

Rigid bronchoscopy (Negus type)—It is used for removal of foreign body, bronchial wash, etc. It reaches up to the third generation bronchioles. It is useful to take biopsy from carcinoma of proximal divisions but not from carcinoma of peripheral lung. Rigid scope has got multiple holes to allow ventilation during procedure (oesophagoscope does not have side holes). It is done under general anaesthesia. *Negus* type has got proximal illumination. *Chevalier Jackson* type has got distal illumination. 2.4/3.5/4.5 are paediatric sizes available. 6.5/7.5/8.5 are adult sizes available.

Flexible bronchoscopy—It reaches up to 5th generation bronchioles. It can be done under local anaesthesia. It is mainly used for diagnosis, biopsy and suctioning, removal of clot from the trachea, endotracheal tube clearing, clearing of tracheobronchial tree through tracheostomy. It is also used to facilitate difficult endotracheal intubation.

Complications

Bleeding, infection, perforation of trachea and bronchospasm.

VASECTOMY

Indications

Vasectomy is done commonly for family planning purpose. Consent of both partners is needed. One should look for any hernia/hydrocele—if present vasectomy should be done along with specific surgeries for these conditions. Previously while doing prostatectomy vasectomy was the procedure used to prevent retrograde infection of testes. Occasionally, in specific diseases like tuberculosis of vas, vasectomy may be done for biopsy purpose.

There are no specific contraindications for vasectomy but if patient is having hernia or hydrocele, it is better to do vasectomy along with surgery for hernia or hydrocele.

Types

Classical method—Scalpel technique.
No scalpel technique (Shunqiang Li-China).

Classical method: After cleaning and draping the scrotum, 2-5 ml of xylocaine plain 1% is injected into root of the scrotum lateral aspect. Skin, dartos are incised (1-2 cm vertical incision). Once spermatic fascia is incised cord structures are identified. Vas deferens is seen and felt as thickened whitish cord like structure. It is dissected using mosquito artery forceps. It is held using Babcock's forceps as loop outside the wound. Vas is clamped in two different places with a gap in between using two artery forceps. A piece of the vas (5 -10 mm) is excised. Cut ends are ligated using non-absorbable sutures like silk. Skin is closed with sutures. Procedure is repeated on the other side. Dressing is placed. Sutures removed after 7 days **(Fig. 7-56)**.

No scalpel technique: Two special instruments are used here. An extracutaneous ring clamp and Chongquing's sharpened curved mosquito clamp. After cleaning and draping, xylocaine 2% of 2-3 ml is injected under the skin of midline raphe proximal aspect. Vas deferens of one side is felt and pushed under the raphe. It is carefully held with extracutaneous ring clamp. Skin is incised using sharp tip of the curved mosquito clamp. Whitish cord-like vas which is held with ring clamp is dissected → clamped → a small piece of 5 mm is cut. Cut ends are ligated using silk. Opposite vas is also similarly brought into the same wound by manipulation and clamped and ligated after cutting. Skin is not closed. It gets apposed automatically and heals on its own. Postoperatively antibiotics and analgesics are given **(Fig. 7-57)**.

Excised small pieces of both sides should be sent for histology for confirmation.

Advice: Contraception should be used to have protected intercourse for a minimum of 6 weeks/15 ejaculations.

Complications

Infection, pyocele, bleeding, haematoma, haematocele, sperm granuloma, recanalisation and failure

VASO-VASOSTOMY (RECANALISATION PROCEDURE)

Indications

Patient who has undergone vasectomy earlier if needs fertility (one more child) again.

Technique

Under general/spinal anaesthesia incision over the front of the scrotum is made. Cord is dissected. Cut ends of the vas are identified. Both ends are carefully mobilised. Cut ends are trimmed to see the clear lumen. Fine 3 zero polypropylene suture material is passed through the lumen to act as a stent. Cut ends are sutured using 4 zero polypropylene continuous sutures. Stent is brought out through vas and through scrotal skin away from main wound. Skin is closed with sutures. Procedure is commonly done on both sides. Stent is kept for 3 weeks and removed. Success rate of vaso-vasostomy is 30%.


Internal ring
Ligatures using silk/ polypropylene
Incision at root of the scrotum –lateral part
Vas deferens
Testis
Both sides are done with separate incisions
Skin incision is sutured –on both sides

Fig. 7-56: Classical method of vasectomy.

Complications

Infection, haematoma and failure

STAPLERS IN SURGERY

Staplers are used for apposition of tissues. It is used in skin, bowel, lungs, etc. It is useful in depth and quick surgery. It is equal to suturing as far as final outcome is considered (neither better nor worse).

Types

Cutaneous staplers give clean apposition. It is faster and technically easier. Problem is removal as it requires specific instrument and costlier than sutures **(Fig. 7-58)**.

Linear staplers are used to close the bowel either completely or partially.

Circular staplers also called as E.E.A. Stapler—**E**nd to **E**nd **A**nastomosis. It is commonly used for colorectal anastomosis in anterior resection for carcinoma rectum, oesophagogastric anastomosis after oesophagogastric resection in case of carcinoma at O-G Junction.

Parts are *stapler gun,* and *cartridge* with two rows of stapler pins for apposition. Loaded cartridge is detachable. Cut ends of bowel are placed over *gun and cartridge*. Once gun is shot, cartridge moves to the gun and creates anastomosis **(Fig. 7-59)**.

GIA stapler (Gastrointestinal anastomosis stapler) for *side to side* anastomosis like small bowel or ileocolic anastomosis.

Stapler for lung apposition.

Endostaplers: Staplers used during laparoscopic surgeries. It is commonly used for bowel anastomosis. ***Endovascular staplers*** are used to ligate vascular pedicles like renal pedicles during laparoscopic nephrectomy.

Disposable staplers are available but are costly.

Advantages

It is technically easier and faster. Main advantage is speed. Stapler gastrointestinal anastomosis takes 2-5 minutes which saves lot of time especially in critically ill patients. It is useful in the depth.

Disadvantages

Cost factor, availability are the problems. It is not completely haemostatic and so bleeding can occur. Leak from anastomosis, improper apposition, intestinal obstruction are other problems. It is uncomfortable to use stapler in biliary anastomosis, pancreatic anastomosis. Staplers are not safer in too thick or too diseased bowel like in Crohn's disease. Suture anastomosis is more appropriate and accurate in such situations.

Principle

Staples enter the tissue straight and then made to bend to 'B.' Blood flow to tissues is maintained through the gap. Standard linear stapler is available in two standard staple sizes—3.5 mm and 4.8 mm size. Each is 4.0 mm in width and 3.5 mm and 4.8 mm leg length respectively. 4.0 mm × 3.5 mm closes to a size of 1.5 mm (used for small and large bowel); 4.0 mm × 4.8 mm closes to 2 mm size (used for stomach). These cartridges are coloured differently for identification purpose. Endoscopic linear stapler compresses tissues up to 1.75 mm thickness. Stapling can be done in inversion or in eversion. Circular and linear cutting stapler creates inverted staple line. Stapling in eversion is used in anastomosis **(Fig. 7-60)**.

Linear Devices

Linear stapling devices are of 55 mm or 90 mm or rarely 30 mm (smaller only for short sutures). Each applies two staggered row of staples of 55 mm/90 mm/30 mm length respectively. Staples could be 3.5 mm or 4.8 mm depending on need and thickness of the tissue. Aligning pin on the tip confirms the proper meeting of the anvil accurately on either sides of the tissue which device is holding. The device that just staples without cutting is called as a linear stapling device without cutting. It is used in closure of duodenal stump, during partial gastrectomy and gastrojejunostomy in creation of new lesser curve, closure of bowel in end to side or side to side anastomosis, during ileostomy, creation of gastric pouch in morbid


Injection of local anaesthesia-over midline raphe proximal part of the scrotum
A
B
Chongquing's sharp curved mosquito clamp
Extracutaneous ring clamp
C
Making incision using sharp curved clamp
D
Feeling vas deferens and holding with ring clamp
E
Holding, lifting vas deferens and dissecting it from adjacent structures of the cord
F
Separating the vas for adequate length-1 cm
G

Figs 7-57A to G


Holding vas
Clamping with haemostats
Cutting with scissor
Excising a piece of vas
Ligating the cut ends with silk/thread
Ligating the cut ends with silk/thread
H
Opposite vas is also dealt with similarly through the same wound
I
Wound with ends of the ligatures of the both side vas deferenses
J
Final wound not sutured left alone
K

Figs 7-57H to K

Figs 7-57A to K: Technique of no scalpel vasectomy—it is done with single incision as sutureless procedure.


PROXIMATE PLUS MD
35W
Skin staple extractor
Extraction method-
Inset
Extracted staples
Skin staple extractor
device

Fig. 7-58: Skin stapler, technique and stapler extraction instrument. Note the shape of the removed staples.



Fig. 7-59: Circular stapler is used for colorectal anastomosis.


3.5 mm
leg length
4 mm base width
4.8 mm
leg length
4 mm base width
1.5 mm apposition after stapling
2.0 mm apposition after stapling
Smaller cartridge (Blue coloured)
Larger cartridge (Green coloured)

Fig. 7-60: Usually two sized stapler pins are available. 4 mm × 3.5 mm is smaller sized, blue coloured. 4 mm × 4.8 mm is larger sized, green coloured.

obesity. Laparoscopic linear stapling device is used stapled ligation and division of the vessels.

Linear cutting stapler device is used for cutting and anastomosis simultaneously. Knife within it divides the tissue; cartridge places two rows of staples on either side of the cut tissue. This linear cutting device is used for side to side anastomosis. It is very useful for gastrojejunostomy, colonic anastomosis, pouch creation, etc. Incisions made to pass the blades into bowel parts need to be closed **(Figs 7-61 and 7-62)**.



Fig. 7-61: Linear cutting stapler device.

Circular Stapling Device

It is used for end to end anastomosis. It creates a two layered stapled anastomosis with inversion, with a circular knife inside the device cutting the tissue between, completing the anastomosis. It is very useful for low colorectal anastomosis after low anterior resection for carcinoma of rectum, sigmoid resection, oesophagogastric/oesophagojejunal anastomosis, gastroduodenal anastomosis (Billroth I). Device is available at varying sized ranges from 12 to 24 mm. Usually 20 mm is used. Thickness of apposition achieved is usually 2.0 mm. Thickness here in some devices can be adjusted. It has got two parts—head/anvil and cartridge which fires and cuts. Head is inserted into the cut end of the colon in colorectal anastomosis from above **(Fig. 7-63)**. Bowel is firmly fixed into the proximal part of head using purse string suture or using a device called furnace through which polypropylene suture is passed. Large main instrument is passed through the anal canal above towards the abdominal cavity. Distal rectal stump is fixed to this using spike in the instrument or by another purse string suture. Care should be taken not to leave excess tissue protruding to prevent incomplete stapling. Two spikes on either side are locked; two parts are apposed; device fired for completing the anastomosis. Device with head is removed through the anus. Doughnut should be carefully removed from the device for inspection for completed circular intact piece which suggests proper anastomosis.

Stapler haemorrhoidopexy (PPH) instrument is a circular stapling device.

Prerequisites for Stapling

- Adequate blood supply in the tissue is the essential part of stapling.
- Thickness of the tissue stapled is also important factor. Thicker the tissue, more chance of tissue strangulation.
- Selection of the size of the cartridge and size of the staple should be proper for ideal stapling result.


Stomach
Transverse colon
Posterior surface of the stomach
Mesocolon
Jejunum
Linear cutting stapler device
Gastrojejunostomy stoma site

Fig. 7-62: Posterior gastrojejunostomy is being done using linear cutting stapler device.



Fig. 7-63: Oesophagogastric anastomosis with resection using end to end circular stapler device.

- Avoidance of linear tension, if needed additional supportive few seromuscular sutures over stapled line makes often a big difference.
- Technical problems in the instruments which may occur rarely may cause failure in spite of proper stapling. Improper firing of the staples may cause anastomotic leak.
- Often knife in cutting device may cut the tissue partially leading into narrow lumen and obstruction at the anastomotic site.
- Avoid incorporating mesentery or mesenteric fat in the anastomosis.
- After stapling, if there is bleeding point on the staple line one should place additional sutures using 3 zero polyglycolic suture or PDS.
- One should avoid bunching of the tissues between cartridge blades in linear device or between head and main instrument in case of circular device. If it occurs it causes improper stapling and leak.
- Stapled stoma has difficulty in dilating naturally while food/stool passes through it and so adequacy of stoma size is important. In sutured anastomosis, stoma can dilate, accommodate and allow passage of content significantly better.
- Doughnut in circular stapling should be inspected. Entire circumference of the stapled line should be inspected. Lumen patency should be checked by invaginating the bowel into the stoma using index finger.

GRAFT

It is transfer of tissue from one area to other without its blood supply or nerve supply. *Autograft* is tissue transferred from one location to another on the same patient. *Isograft* is tissue transfer between two genetically identical individuals, i.e. between two identical twins. *Allograft* is tissue transfer between two genetically different members, e.g. Kidney transplantation. *Xenograft* is tissue transfer from a donor of one species to a recipient of another species. Composite graft is graft with skin, fat and other tissues like cartilage.

Skin Grafting

It is transfer of skin from one area (donor area) to the required defective area (recipient area). It is an autograft.

Types

1. Partial thickness graft (Split thickness graft, SSG)

It is also called as **Thiersch graft**, which is removal of full epidermis + part of the dermis from the donor area. It may be *thin* SSG, *intermediate* SSG or *thick* SSG - all depends on the amount of thickness of dermis taken. Thick SSG withstands late trauma to recipient area better than thin SSG. *Indications:* (1) Well granulated ulcer. (2) Clean wound or defect which cannot be apposed. (3) After surgery to cover and close the defect created, e.g. After wide excision in malignancy, after mastectomy, after wide excision of squamous cell carcinoma, etc. Graft can survive over periosteum or paratenon or perichondrium. *Pre requisites:* (1) Healthy granulation area. (2) Streptococci load less than 10^5 per gram of tissue, otherwise graft failure will occur. *Contraindications:* SSG cannot be done over bone, tendon, cartilage, joint, etc. *Donor areas used are*—commonly *thigh*, occasionally arm, leg and forearm. Knife used is *Humby's Knife*. Blade is *Eschmann blade*, Down's blade **(Figs 7-64 to 7-68)**.

Different instruments used to harvest the skin graft

- Humby knife.
- Watson modification of Humby knife.
- Power dermatome is also used (Brown).
- Sterilised razor blade can be used with a specialised device to harvest small grafts under local anaesthesia—Silver knife.



Fig. 7-64: Commonest donor area for spilt skin grafting is thigh.



Fig. 7-65: Donor area of split skin graft immediately after harvesting graft showing punctate bleeding.



Fig. 7-66: Donor area dressing is not removed for 10 days. If soakage is observed an over dressing is done on earlier dressing without removing it.



Fig. 7-67: Split skin graft donor area—10 days after removal of the dressing. Dressing from donor area is removed only after 10 days and left open after that.


Instruments needed for skin grafting
SSG knife (Humby's)
SSG blade (Eschmann's/Down's)

Fig. 7-68: Instruments needed for split (Thiersch) skin grafting. Humby's knife, Eschmann blade; skin spreader; wooden boards; scoop; kidney tray; saline to keep harvested split skin; forceps; scissors.

Donor Area

Donor area and recipient area is cleaned and draped properly. If recipient area is a raw area after wide excision of malignant lesion in the lower limb, then donor area should be on opposite side as there are chances of deposition of malignant cells over donor area through opened up cutaneous lymphatics. Selected blade is placed on the slot of the knife. Blade and gap in the sliding rod is adjusted by markings on the knob on the handle. Markings are made to select thin/intermediate/thick split thickness graft. Knobs are tightened properly. Assistant holds the thigh on its posterior aspect using both his hands firmly making anterior aspect or donor area convex and firm. Usually graft knives are made for right hand. Blade and guard rod of the knife is soaked with Vaseline. Using wooden board soaked with Vaseline to facilitate smooth movements of the boards, stretched donor skin is held apart with a gap in between. In the gap graft knife is placed. Initially blade is deepened to pierce the epidermis and part of the dermis and with continuous firm constant pressure knife is moved to and fro repeatedly with sliding progressively forward to get a required split skin graft. Once graft is taken, *punctate bleeding* is observed which says that proper graft has obtained. High density small bleeding points are features of thin graft; low density larger bleeding points are the features of thick graft. In the thigh, lateral and distal area gives thicker graft than medial and proximal. Clinically on table thickness is assessed based on translucency of the graft. Thinner the graft more it is translucent. Donor area is dressed (using Sofra-Tulle/ bactigras, absorbent gauze, roller cotton, crepe bandage/bandage), and *after 10 days* dressing is opened, not earlier than that. Commonly the donor area and dressing becomes hard, dry and adherent to donor area. Ideal donor dressing should be moist, absorbent to promote epithelial migration but such aseptic dressings are not available. Alginate dressings are better when available. (Moist area in temperate climate due to humidity may cause *Pseudomonas aeruginosa* infection). Dressing gets separated in 10-12 days spontaneously. Over dressing can be done if whenever needed but entire dressing should not be removed.

Resurfacing of the donor area occurs on its own. Remnants of the pilosebaceous apparatus are *active component* in epithelial regeneration than sweat gland remnants. Thin graft donor area contains more pilosebaceous glands making it to heal rapidly and early in 7-9 days; whereas thick split skin graft donor area contains mainly sweat gland components with less pilosebaceous glands making it to heal slowly in 14 days. Donor area infection may destroy the pilosebaceous or sweat gland remnants causing inability to resurface leaving a granulation tissue in the floor. Once donor area dressing is removed healing raw area is left open with application of emollients/oil for 4 weeks. *Problems in donor area* - Postoperative pain is more in donor area than recipient bed. Pain subsides in 5-7 days. Deep raw area when not epithelialised leave an ulcer which may require regular dressing later. Pigmentation, colour changes and hypertrophic scar formation are the usual problems **(Fig. 7-69)**.

Recipient Area

Recipient area is scraped well and graft is placed after making *window cuts* (fenestrations with multiple cuts; it is not mandatory to place such cuts; it is optional) in the graft to prevent seroma development. Graft is fixed and *tie-over* dressing is placed. If graft is near the joint, then part is immobilised to prevent friction which may separate the graft. On 5th *day* dressing is opened and observed for graft take up. *Healthy granulation tissue* in recipient area with red, flat, vascular look with good marginal healing is essential for proper graft take up. Presence of *Streptococcus pyogenes* is absolute contraindication for skin grafting. It causes gelatinous glaze granulation tissue. Slough excision, systemic antibiotics, local application of chlorhexidine is effective way of eradicating it (only systemic antibiotics may not be adequate). It causes *100% graft failure*. Even raw area looks healthy clinically but culture shows positive for *Streptococcus pyogenes*, then grafting is contraindicated as graft will not take up. *Streptococcus pyogenes* should be completely eliminated prior to grafting. *Pseudomonas aeruginosa* infection reduces the graft take up by *10%* but not like of *Streptococcus pyogenes* infection. One has to remember that positive culture of Pseudomonas in the discharge is not a contraindication for skin grafting. If granulation tissue clinically looks healthy skin grafting can be done. If granulation tissue is pale with greenish discharge then grafting is not done. Once healthy granulation tissue forms area should be grafted earliest otherwise infection, fibrosis of area can occur causing recurrent problems.

Stamp graft is in perineum, axilla, etc. It is small, sized grafts placed in the recipient bed. Such grafts are usually not fixed.

Mesh graft is used in wide areas like burn wounds. It takes up well. But cosmetically it is poor. Fixing of mesh is cumbersome.


Humby's knife
Skin graft
Wooden board
A
Technique of holding Humby's knife by the surgeon and assistant supporting the thighs using both hands firmly
B
C
D
E
F
Humby's knife
Wooden board with split skin ready for graft with window cuts
Graft spreader
G
H

Figs 7-69A to H: Technique of split skin grafting. Graft harvesting from donor area—thigh; making window cuts; placing graft over recipient area.

Quilted grafting—It is commonly used in places where immobilisation is impossible like in oral cavity (cheek) and tongue after wide excision. Split skin graft is placed over the defect. Edge is sutured to the margin of the defect. Multiple additional sutures are placed through the graft to the muscle underneath to anchor both together. It looks like a 'quilt'. Fenestrations/window cuts in the graft prevent seroma formation and mobility of tongue or cheek can be undertaken without graft displacement **(Figs 7-70 to 7-73)**.

Causes for poor graft take up/contraindications for skin grafting

- Unhealthy granulation tissue.
- Infection—*Streptococcus pyogenes* mainly, *Pseudomonas aeruginosa* less severely.
- Haematoma and seroma formation.
- Graft over the joint surface—not immobilised.
- Poor blood supply.
- Haemoglobin of patient if less than 10 gram%.
- Poor nutrition, hypoalbuminaemia (Albumin level less than 3 gram %).

Graft Application

Applied graft is stabilised into the recipient bed by various methods (or dressings). They are:

Bolus dressing/bolus grafting—If there is ooze and chances of haematoma or seroma formation, commonly observed over granulation tissue, then pressure dressing is used. It is done using 'tie over' dressing and crepe bandaging. Tie over dressing over a graft is called as *bolus grafting*. Crepe bandage over 'tie over' gives immobilisation and additional pressure. In full thickness grafting, graft edge is properly apposed exactly over the recipient area without any overlapping. Few of sutures all round are kept long to place tie over. In split thickness grafting graft is kept *overlapping over the defect* and tied over from the defect edge. Overlapped skin is trimmed during graft inspection in 5th postoperative day. After placing the tie over sutures all round the edge, tulle gras layer is applied. Later bolus material consisting of cotton soaked in saline dilute povidone iodine or cotton soaked in liquid paraffin or polyurethane or flavine wool material (flavine


SSG graft harvesting
A
SSG preparing recipient bed by scooping granulation tissue
B
SSG making window cut over the graft on a wooden board to prevent seroma formation
C
Placing graft over recipient bed gently
D

Figs 7-70A to D: Harvesting skin graft; scooping the granulation tissue from the recipient bed; making window cuts over the graft to prevent seroma formation; placing the harvested skin.


SSG dressing using sofratulle/bact.grass
Tie over dressing
SSG recipient area dressing with immobilisation and pressure dressing- dressing will be opened in 5 days to check graft take up

Fig. 7-71: Split skin grafting and covering the grafted area with sofratulle, povidone iodine soaked dressing pads, tie over dressing, bandaging, crepe bandage or immobilisation using plaster of Paris slab/cast.



Fig. 7-72: Split skin graft in the leg - taken up well observed in 5 days.



Fig. 7-73: Split skin grafting taken up which is observed after one month.

emulsion, Gamgee, cotton wool are used here. Cotton wool sheet is soaked with warmed flavine emulsion to impregnate over it and Gamgee is placed over it and dried and autoclaved) placed firmly. Long sutures tied over it at different places. Further cotton roll is placed over it. Roller bandaging and crepe bandaging is done over it to diffuse equal effective pressure and also immobilisation. Bolus grafting is used in limbs and face. It is often difficult to place in trunks and groin. *Tie over also can be* achieved in limbs by placing continuous circular ties circumferentially over the dressing pads kept on the graft. It is quicker and easier. It does not require placement of any sutures over the edge **(Fig. 7-74)**.

Exposed grafting: It is often used in trunk and groin. By exposed method shearing movements between recipient bed and graft are prevented. Here natural fibrin formation prevents to and fro movement between bed and graft. Exposed grafting is used mainly in raw area created after excision of a lesion wherein haemostasis is achieved properly by cautery or ligation. Often after initial excision of the lesion, dressing is done for 48 hours and then graft is placed with *delayed exposed grafting*. As haematoma and seroma formation *can not* be prevented in this method it is not usually used in ulcer bed. Patient cooperation is essential in his type of graft management. This method is useful for single safe surface. It is not useful in circumferential or wide raw areas.

Stages of Graft Intake

Stage of Plasmatic imbibition: Thin, uniform, layer of plasma and fibrin forms between recipient bed and graft. *Stage of inosculation*: Linking of host and graft which is temporary. *Stage of neovascularisation*: New capillaries proliferate into graft from the recipient bed which attains circulation later.

***Disadvantages of SSG*:** (1) Contracture of the graft—It is of two types: (A) *Primary contracture* means SSG contracts significantly once graft is taken from donor area (20-30%). Thicker the graft more is the primary contracture. (B) *Secondary contracture* occurs after graft has taken up to recipient bed during healing period, due to fibrosis. Thinner the graft more is the secondary contracture. (2) Seroma and haematoma formation will prevent graft take up. (3) Infection. (4) Loss of hair growth, blunting of sensation. (5) Dry, scaling of skin due to nonfunctioning of sebaceous glands. So after healing oil (coconut oil) should be applied over the area. (6) Graft failure.

Advantages: (1) It is technically easier. (2) Wide area of recipient can be covered. To cover large area like burns wound, graft size is increased by passing the graft through a ***Mesher*** which gives multiple openings to the graft which can be stretched on the wider area like a net. It can cause expansion up to 6 times. (3) Graft take up is better. (4) Donor area heals on its own **(Figs 7-75 and 7-76)**.

Note: Graft can be stored in low temperature 4° C for up to 21 days. It is stored in normal saline. But usually it is not used beyond 10 days.

Full Thickness Graft (Wolfe Graft)

It includes both epidermis + entire dermis. It is used over the face, hands, fingers, over the joints or for small defects like ectropion, eyelid/nasal/cheek defects and deformities, injury and contractures of fingers, syndactyly. It is removed using scalpel blade. Underlying *fat*


Defect
Split skin graft
Graft placed over the defect with overlapping
Long polypropylene sutures placed from defect edge and also taking bites from grafted skin at the defect edge level leaving overlapped graft free
Grafted skin over defect area is covered with tulle, cotton wool soaked with saline
Final 'tie-over' dressing over the graft leaving overlapped graft free

Fig. 7-74: 'Tie-Over' dressing after split skin grafting.



Figs 7-75A to D: Mesher used in split skin grafting to increase its surface area of coverage for wider areas like burns wound. A large defect can be covered by this. It can cause expansion upto six times. Photo also shows exact look of meshed split skin graft.


Mesh graft with tie over sutures on the edge to tie them over dressing pads
Mesh graft take up look

Fig. 7-76: Mesh grafts placed over donor areas and their take up look.

should be cleared of properly. No epidermal elements are found in left out donor area. So resurfacing of the donor area cannot take place on its own. Deeper raw area is closed by primary suturing. If larger area is taken then that donor area has to be covered with SSG which is a disadvantage in full thickness graft. Defect and donor required sized site should be marked using Bonney's blue properly. Size matching is important. Area may be infiltrated with normal saline with or without 1 in 200000 noradrenaline to balloon the skin which will facilitate the raising of the graft. While raising the graft using blade, with skin hooks, the edge of the graft should be held. Full thickness graft has got colour and look of cadaver skin. Graft edge is properly apposed exactly over the recipient area without any overlapping. Few of sutures all round are kept long to place tie over. Tie-over dressing is a must in full thickness graft. Common sites of donor area are—(1) Postauricular area. (2) Supraclavicular area. (3) Other areas like—infraclavicular, lateral groin, upper eyelid part, antecubital fossa, inframammary area in females also often used **(Figs 7-77 to 7-79)**.

Advantages: (1) Colour match is good especially for face. (2) No contracture (unlike in SSG) and so remains in its original size. (3) Sensation, functions of sebaceous glands, hair follicles are retained better compared to SSG. Texture, colour, durability is better.


Postauricular area
Supraclavicular area
Upper eyelid

Fig. 7-77: Common donor areas for Wolfe graft.


Full thickness graft from postauricular donor area
Donor defect is closed primarily
Skin is harvested using scalpel blade no 15. Full thickness graft should be devoid of fat.
Full thickness graft taken from donor area
Recipient defect area
Full thickness graft cover over the defect

Fig. 7-78: Technique of Wolfe—Full thickness graft.

Disadvantages: (1) Only for small area it can be used. (2) Wider donor area has to be covered with SSG to close the defect. (3) It cannot be used to cover ulcers.

FLAPS

Flaps are transfer of tissues from one area to another with their blood supply.

It is transfer of donor tissue with its blood supply to the recipient area.

Parts of flaps: Base, pedicle, tip of flap. Vasculature is usually through the pedicle in the centre of the flap. Tip is the place where often flap goes for necrosis **(Figs 7-80A to C)**.

Congruity, configuration, components, circulation, conditioning are the *different aspects* of the flap.

Indications

(1) To cover the wider, deeper defects. (2) To cover over bone, tendon, cartilage. (3) If skin graft repeatedly fails.


Defect
Full thickness graft
Suturing edge of the defect to the margin of the graft without overlapping. Few sutures in the edge are kept long for tie over
Dressing over the grafted skin - tulle, cotton wool soaked in saline
Final 'tie-over' dressing of full thickness skin graft

Fig. 7-79: 'Tie-over' dressing for Wolfe graft (full thickness graft).


Flap
Donor area
A
B
SSG over donor area
Flap
C

Figs 7-80A to C: Typical flap, method of raising it; and donor area being wide is covered with split skin graft.

Types

(1) *Random pattern flaps*: Here vascular basis is subdermal plexus of blood vessels. Known blood supply is not present. It is usually a rectangular flap with length to width ratio is ***1:1*** or 1.5:1. This flap has got limitations in its dimensions. (2) *Axial pattern flaps*: Here superficial vascular pedicles pass along their long axes, e.g. Forehead flap, deltopectoral flap, groin flap. A known anatomical blood vessel supplies the flap. It is *long lengthy* flap **(Figs 7-81 to 7-84)**.

Anatomical Types Depending on the Types of Tissue in the Flap

(1) Cutaneous flap: Forehead flap, deltopectoral flap. (2) Fasciocutaneous flap: Radial forearm flap, scapular flap, lateral arm flap. (3) Muscle flap: Gluteus maximus muscle flap, gracilis flap, tensor fascia lata muscle flap. (4) Myocutaneous flap: Pectoralis major myocutaneous flap, latissimus dorsi flap. (5) Osteo myocutaneous flaps: Radius with brachioradialis and skin; rib with intercostal muscles and skin. (6) Local rotation flaps. (7) 'Z' plasty.(8) Free flaps: Vascular pedicle of the flap both artery and vein are anastomosed to recipient vessels using operating binocular microscopes.(9) Omental flaps. (10) Island flap **(Figs 7-85 and 7-86)**.


Dermal-Subdermal plexus
Segmental artery
Musculocutaneous and perforator arteries

Fig. 7-81: Anatomy and blood supply of a skin flap.


Random pattern flap
Here length: breadth ratio is 1:1. No specified named vessel found
Axial pattern flap
Here lengthy flap can be taken. Length is more than breadth. Specified vessel is found axially in the flap

Fig. 7-82: Types flap based on vascular pattern—Random pattern and axial pattern.



Fig. 7-83: Flap which has taken up well placed over the defect on the bone with osteomyelitis.



Fig. 7-84: Traumatic exposure of the bone. Flap is needed to cover this defect. It could be cross leg flap or rotation flap. Skin grafting is not possible in this situation.



Fig. 7-85: Bilobed flap is used in lesions of the nose commonly.



Fig. 7-86: On table marking of glabellar flap to place after excising a lesion in the root of the nose.

Areas where Commonly Flaps are Used

Oral cavity, neck, breast, limbs (leg), buttock, bedsores, etc.

Flaps mobilised from donor area with its pedicle is placed and sutured to recipient area. Once flap gets taken up usually in 3-6 weeks, base of the flap is cut and sutured to recipient area.

Saltatory flap is mobilising the flaps in stages from distant donor area towards recipient area. It requires many staged surgeries and long-term hospitalisation. Intermediate tissue is used as '***carrier***' **(Figs 7-87 and 7-88)**.

Advantages of Flaps

(1) Good blood supply, good take up. (2) It gives bulk, texture, and color to the area. (3) Allowing the required movements in the recipient area, e.g. Jaw movements after pectoralis major flap after wide excision with hemimandibulectomy for carcinoma cheek. (4) Cosmetically better.

Disadvantages of Flaps

(1) Long-term hospitalisation is needed. (2) Infection. (3) Kinking, rotation and flap necrosis. (4) Staged procedure.

Positioning of the patient for long time is important to have a good flap take up which is a real discomfort to the patient.

Waltzing is a technique wherein flap is moved from donor area and attached adjacent to the recipient defect area. Later in 2nd stage it is moved towards the defect formally. It reduces the tension on the flap and increases the success rate **(Fig. 7-89)**.

Delaying of the Flap/Conditioning the Flap

Flap is raised properly as required and re-sutured to same place so as to allow the formation of reorientation of vasculature near the tip of the flap. *This delayed flap* is raised again in 10-14 days to place in required area. It is used both in random pattern as well as axial pattern flap. In random pattern flap delay improves the length-breadth ratio. In axial pattern flap, delaying enhances the blood flow across the distal attachment of the flap. It is often used in deltopectoral flap **(Fig. 7-90)**.

Different Flaps

Flap lying immediately adjacent to the defect is called as *local flap*. Flap moved from adjacent anatomical area is called as *regional flap*. Flap when moved from distant anatomical site is called as *distant flap*.


Defect
From the wrist carrier flap is transferred to cheek defect
Flap raise from donor
Transfer to wrist
Transfer to cheek

Fig. 7-87: Saltatory flap. Flap raised from the abdomen is reached to the cheek in stages—from abdomen to wrist; from wrist to cheek.


Groin flap trasferring to wrist carrier
Defect
From the wrist carrier flap is transferred to cheek defect
From the wrist carrier flap can be trasferred to a defect in leg to cover
Defect

Fig. 7-88: Transferring the groin flap to the defect area either in cheek or in leg using wrist as carrier. It is the staged procedure. In each stage flap is divided in 3 weeks period.


Lesion/Defect
Deltopectoral flap

Fig. 7-89: Waltzing flap.


Delayed flap
Random pattern blood supply
Raising the flap
Resuturing the flap at the same area
Flap raise after 14 days for transfer at recipient area - delaying causing reorientation and enhanced blood supply of flap

Fig. 7-90: Delaying the flap for 10-14 days to reorient the blood supply. It is done in random pattern flap to improve length to breadth ratio or in axial pattern flap to improve distal blood supply.

Pedicled flap is flap which is moved with intact tissue bridge to support it. Deltopectoral flap is a pedicled flap.

Islanded flap is a flap which is moved to a site which is non-contiguous from the donor flap area but flap is moved under the skin bridge through a tunnel. Pectoralis major myocutaneous flap is an islanded flap. Localised flap is swung around a stalk from the donor area to the recipient area often with the pedicle buried underneath the skin bridge in between.

Transposition/rotation flap: When the flap moves laterally it is called as *transposition flap*. Transposition flap is squarely designed which moves laterally to close the defect creating a larger area on its original place which can be covered with split skin graft. Mobility of the transposition flap depends on the laxity, flexibility, mobilisation and blood supply. When the flap rotates laterally towards defect it is called as *rotation flap.* It is commonly used in covering bedsores in buttock and sacral region and also in scalp. Flap needed is much wider in relation to the size of the defect **(Figs 7-91 to 7-94)**.



Fig. 7-91: Transposition flap.



Fig. 7-92: Rotation flap. It is commonly used in gluteal region in managing bedsores.

Advancement flap: It is advancing the flap from one angle towards the defect in longitudinal direction. Here flap transferring area is less but useful. It is used commonly in fingers **(Figs 7-95 and 7-96)**.

'*Z' plasty*: It is a procedure which involves transposition of two interdigitating triangular flaps. There is change in direction as well as gain in length of the common limb of Z. Angle size and length of the limb is the most important factors. With an angle of 60° there will be increase in length by 75%. It is used in managing contracted scars, facial scars, Dupuytren's contracture and cover the excised defects like pilonidal sinus (example). There should be transverse skin slack available equal to the length between the axes of Z. It can be single or multiple Z plasty. Multiple Z plasty shows overall 2 cm lengthening but shortening only of 0.5 cm in transverse axis whereas single Z plasty causes 2 cm lengthening and 2 cm shortening in parallel line. Lateral tension is diffused in multiple Z plasty but it is concentrated in single Z plasty. Complications are flap necrosis near the angle tip, infection, failure. Vascularity of the flaps is essential need. Side limbs of the flaps can be curved and broadened to improve the blood supply **(Figs 7-97 and 7-98)**.

Deltopectoral flap (Bakamjian flap): It is a *fasciocutaneous flap* (axial pattern) based on first three perforating branches of the internal mammary artery (mainly 2nd perforator) **(Fig. 7-99)**. Flap runs horizontally across the chest wall anteriorly towards shoulder tip from its base over the sternal border. Its upper border is along the line of the clavicle; its lower border is along the anterior axillary fold line. Raw area often requires a spilt skin grafting. It is usually rotated upwards often with waltzing. It is tubed and attached above. Tube is drained to prevent any collection to occur. Rotation angle is important to prevent any kinking on the pedicle. It is usually used to cover the



Figs 7-93A to E: Rotation flap for gluteal defect/bedsore.

defects in cheek, chin, mastoid and parotid region. *Pivot point* of rotation is located in upper medial aspect. Often flap is delayed to get adequate length. Upper medial point is rotating pivot point. It moves a *quarter circle*. Flap can be reached as high as defect over the zygomatic region, as rotating lower border of the flap slack and lax (as it is near anterior axillary fold which is lax). Occasionally it is also used to transfer below to the chest or abdomen.

Groin flap: It is a *cutaneous flap* (axial pattern) based medially on *superficial circumflex iliac artery* which is 2-3 cm below and parallel to the inguinal ligament. Artery originates from femoral artery over medial border of the sartorius and ends at anterior superior iliac spine. Deep branch is at the margin of the sartorius and superficial branch continues towards anterior superior iliac spine. 1:1 rectangular flap with deep fascia is used. Dissection of raising the flap is done up to the medial border of the sartorius. Secondary defect can usually be closed with sutures. It is used mainly for defects in wrist/forearm where positioning is easier. Often *tubed groin flap* can be transferred to cheek or leg using wrist as carrier **(Figs 7-100 and 7-101)**.

Hypogastric flap: It is a *cutaneous flap* (axial pattern) based on superficial epigastric vessel directing upwards from the inguinal ligament in the lower abdomen. It is used for wrist similar like groin flap **(Fig. 7-102)**.

Latissimus dorsi muscle/myocutaneous flap: It is based on thoracodorsal artery, a branch of subscapular artery. Skin over the upper and anterior border of the muscle is used for transfer **(Fig. 7-103)**. It is commonly used to cover the defect after mastectomy. But it does not give the bulk. It is technically easier. It can be used as muscle flap also. It helps as skin cover. Prosthesis (submuscular silicone) is needed to place underneath to provide bulk in post-mastectomy defect. Muscle arises from iliac crest upwards to mid-thoracic spine. Muscle is like a fan below forming tendinous fibres above to insert into humeral shaft. Subscapular artery a largest branch derived from 3rd part of axillary artery runs along posterior wall of the axilla giving circumflex scapular vessels at 4 cm distance and later continuing as thoracodorsal artery for about 6 cm enters the muscle giving many branches. Flap is usually taken as myocutaneous flap with elliptical skin on the surface. Skin part is either horizontal ellipse when taken from upper margin of the muscle or vertical when taken from the anterior margin of the muscle. Point of origin of the subscapular artery is the pivot point of the flap. Artery accompanies the vein also. During raising the flap after islanding it with skin, only pedicle can be retained cutting muscle above to attain extra length (but commonly anterior attachment is retained) and flap is rotated to the needed area. Donor area can be sutured primarily or covered with a split skin graft. In LD flap nerve is not retained (as if retained it causes unpleasant muscle contractions) and so it will not maintain the bulk but gives well coverage of the defect. Flap harvesting is done in lateral position. Subscapular vessels maintain the adequate length and calibreand so it is often used as *free flap* based on subscapular vessels.

Pectoralis major myocutaneous flap (PMMF): It is based on the pectoral branches of *thoracoacromial artery*. Usually skin below and



Fig. 7-94: Bilobed flap taken from abdominal wall and placing to the hand and wrist area over two defects.



Fig. 7-95: Advancement flap is used in distal defects.



Fig. 7-96: Technique of V-Y plasty and Y-V plasty.

medial to nipple over the muscle is used. Muscle pedicle is made as broad as skin. It is used to cover the defect over the cheek/neck/pharynx/intraoral lesions after wide excision with removal of skin over the tumor. Vessel marking is 2 cm medial to coracoid process, obliquely below the clavicle at the junction between middle third and outer third. Line runs towards the xiphoid process. Oblique downwards incision is placed encroaching the ellipse of the needed skin in the flap. Often skin incision begins below the line of 3rd rib to retain the deltopectoral flap area in case of need in future. Lower border of the muscle is raised by dissecting beneath the pectoral fascia. While raising the flap of the chest wall thoracoacromial vessels can be visualised. Enough care should be taken not to injure it. Flap is raised over the medial and lateral margins of the pectoralis major muscle. In front it is dissected off from the deep fascia. Skin with muscle is dissected from the deeper structures like ribs, intercostal muscles and pectoralis minor. Flap is raised upwards up to the coracoid. Lateral pectoral vessels if possible are retained otherwise can be sacrificed. Pectoral nerves should be retained. Defect below is usually closed primarily with sutures. Often it needs spilt skin grafting. Flap is tunneled in subcutaneous plane towards neck or oral cavity. Postoperatively flap is observed for colour changes, seroma, and infection. Neck is flexed towards the flap side during postoperative period to prevent tension. Suction drain should be placed which is removed once drainage stops or in 72 hours. In the neck flap covers the carotids protecting it. In oral cavity if flap is of large sized, its skin can be split into half to cover both inner and outer aspect of the oral cavity. It gives bulk and adequate movements of the jaw. Pectoralis major flap can be used along with deltopectoral flap with proper planning **(Figs 7-104 to 7-106)**.



Fig. 7-97: Technique of 'Z' plasty. It is used in contracture release; Dupuytren's contracture and pilonidal sinus. Angle of rotation here is 60°. Note the z plasty done for Dupuytren's contracture. Fingers can be retracted using finger bows of the haemostats.

Gastrocnemius muscle flap: It is either medial or lateral and is commonly used to cover the upper part of the tibia and knee joint. It is technically easier and functional deficit occurring at donor area is insignificant. It is rarely used as myocutaneous flap.

Transverse rectus abdominis muscle flap (TRAM flap): It is either superior pedicle based on the superior epigastric vessels or inferior pedicle based on the inferior epigastric vessels. Superior pedicle based flap is used to cover postmastectomy area or chest wall defect. To cover post-mastectomy area opposite sided superior pedicle is used to reduce the arc through which flap has to rotate (but rotating from opposite side is technically difficult). Inferior pedicle flap is used to cover the defects in groin and thigh. Proper marking of the flap is essential **(Fig. 7-107)**. Skin incision is made like an ellipse. Anterior rectus sheath is cut in the line of incision and is raised upwards carefully of the rectus muscle up to the xiphisternum. Muscle is gently separated of the posterior rectus sheath with care not to injure the epigastric vessels. Once dissection is complete lower part of the muscle is cut in superior pedicle to rotate upwards carefully. In the upper


Incisions from multiple Z plasties
Final result is increase in length but only limited shortening of 0.5 cm in parallel plane

Fig. 7-98: Multiple Z plasties are done to diffuse the tension and to improve the lengthening.

part again anterior rectus sheath is opened to pass the flap towards the defect in subcutaneous plane. TRAM flap gives bulk and contour to the defect. But it is technically difficult. Usually opposite side of the defect is taken as flap as it is easier to rotate from opposite side. Defect in the abdomen usually needs mesh to support and close. It is not possible to do this flap in obese and if patient has underwent laparotomy earlier (with a lengthy scar). Below the flap cut end of the inferior epigastric artery in superior pedicle flap can be anastomosed to a vessel in recipient bed to improve the perfusion *(supercharging)*. Inferior epigastric artery in inferior pedicle can be additionally perfused using opposite inferior epigastric artery *(recharging)*.

Radial forearm flap: It is perfused from the radial vessels and raised on the flexor aspect of the forearm. Perforating branches of these vessels supply deep fascia and skin over it. Flap can be fasciocutaneous or osteofasciocutaneous/osteomyofasciocutaneous if radial bone is also used as part of the flap. Radial forearm free flap is commonly used for mandible defects. It is technically easier and safer. Flap is raised along with skin, segment of the radius along its intermuscular septum through which vessels pass and brachioradialis as components. Care is taken in dissecting vessels of the bed


Defect after surgery in cheek
Clavicle
2nd, 3rd, 4th perforators of internal mammary artery
Vascular pattern and area of deltopectoral Bakamjian flap
Bridge segment often tubed
Pivot point of DP flap
Split skin graft sutured to edge in deltoid part of the defect
Temporary raw area
Flap is raised, rotated into the defect and sutured to it. Summit of the secondary defect is covered by split skin graft—as delayed exposed graft.
Defect covered with flap
After 3 weeks flap is disconnected and part of its base (bridge segment) is replaced into the original place—temporary raw area medial to grafted area.



Fig. 7-99: Deltopectoral cutaneous flap (Bakamjian flap).



Fig. 7-100: Groin flap is based on superficial circumflex artery. It can be used for defects in hand and forearm. It is a cutaneous flap.

and not to injure the radial nerve. In free flap artery is sutured to the recipient artery like facial artery using microscope. Other similar flaps are—ulnar forearm flap, scapular flaps, and vascularised fibular transfer.



Fig. 7-101: Groin flap used for burns defect in the hand.

Limberg flap is a type of rhomboid flap used in—pilonidal sinus with base at gluteal skin; defects in face after surgical wide excision **(Fig. 7-108)**.

Cross leg flap: It is commonly used to cover the defect in the opposite foot/leg. It is random pattern flap. Limb should be immobilised for 3 weeks by plaster of Paris or external fixation. Raw donor flap area needs split skin graft cover. It is direct flap with 1:1 length breadth ratio **(Fig. 7-109)**. It is commonly used in post-trauma defects in younger individuals. Joint stiffness due to immobilisation may be a problem.

Free Flaps

Flap with a single lengthy wide calibered arteriovenous system is transferred with its vascular pedicle. Here vascular pedicle is transected with flap; both artery and vein of the flap is anastomosed to



Fig. 7-102: Diagram showing hypogastric flap based on superficial epigastric artery.


Humerus
Twisted fibrous tendon
Upper border of the latissimus dorsi
T7
LD muscle
T12
Lumbar spines
L4
Anterior border
Iliac crest
Lumbar fascia
Upper horizontal flap
Thoracodorsal artery
Anterior vertical flap
LD muscle

Fig. 7-103: Latissimus dorsi myocutaneous flap.



Fig. 7-104: Diagrammatic look of pectoralis major myocutaneous flap.


Primary tumour
PMM flap
Donor site

Fig. 7-105: Pectoralis major myocutaneous flap used for carcinoma cheek.

the specific artery and vein at recipient area to re-attain its perfusion through newer blood vessel. *Length and calibre of the vessels* are deciding factors here. Often associated nerves either motor or sensory are also anastomosed. *Healthy vessel wall and adequate pulse volume* are essential in recipient vessel. Presence of *infection* in recipient area is *absolute contraindication*. It can cause thrombosis of the vessel and flap necrosis. Vein ideally should be as large as artery. Often if possible a second vein is also anastomosed. Calibre of the vessels of both recipient and donor parts should be reasonably corresponding. Recipient bed and vessel preparation and donor flap raising should be done simultaneously. *The ischaemic time* (time between division of the donor vessel and restoration of perfusion at recipient) should be kept minimum as much as possible.


Recurrent mobile neck secondaries
Wide dissection done exposing carotid with skin loss
A
B
Skin incision and dissection from below deep to pectoralis major muscle
C
Raising the flap deeper part
Dissection over the margins
D

Figs 7-106A to D


Dissection in front of the flap
E
F
Subcutaneous tunnelling
Recepient defect in neck
PMMC flap and donor area
G
H
Flap at recipient site and suturing it to the defect edge

Figs 7-106E to H



Figs 7-106I and J

Figs 7-106A to J: Incision marking, flap raise and steps in pectoralis major myocutaneous flap.

Factors deciding the adequacy of a flap

- Blood supply of the flap.
- Avoiding mechanical tension and kinking.
- Flap geometry with limited angulation at pivot point of the flap.
- Marking the flap and using cut gauze equal to the size of the flap mock transfer and placing of the flap.
- Postsurgery positioning, prevention of infection.
- Compression of flap should be avoided while passing through a tunnel-like pectoralis major myocutaneous flap.
- Avoiding injury to feeding vessel while raising the flap.
- Thinning of flap if needed should be done with utmost care.
- Prevention of haematoma formation.
- Proper placement of suction drain under the flap.
- Dressings should not be too tight to compromise the blood vessel.
- Delaying the flap especially in random pattern flap.
- Careful tubing of the flap, proper selection of carrier site when needed.
- Positioning of the part and immobilisation.

Anastomosis is done *end to end or side to end* to the flap vessel from recipient vessel (side of the recipient vessel to end of flap vessel). When diameters of the both vessels are equal end to end anastomosis is done. When diameter is unequal, then side to end anastomosis is done. End to end in such situation may cause turbulence blood flow due to unequal diameter and leads to thrombosis of the vessel. Instruments used for anastomosis are—spring handled needle holder; spring handled scissors; fine dissecting and cutting scissors; blunt tipped forceps as vessel dilator; microclamps.

Vessel wall should be healthy, atheroma free, without any branches near to the suturing site, without any valves in veins near the site. Any factor which is likely to cause turbulence should be avoided. Vessel should be held using fine forceps on the periadventitia. *Only bipolar cautery* should be used. Main vessel should not be handled directly. Unnecessary handling of the vessel may cause *vasospasm* which should be avoided. During dissection of the vessel, to prevent spasm area is irrigated with local anaesthetic agents (lignocaine) or using papaverine. Tension, kinking, torsion of the both recipient and flap vessels should be carefully avoided. Only once recipient vessel is ready, flap vessel is divided after applying a *microclamp*. Once vessels are ready then only microscopy should be used for anastomosis. Now periadventitia is removed for 3 mm from the cut margin in end to


Superior epigastric artery
IV
II
I
III
Inferior epigastric artery

Fig. 7-107: Transverse abdominis myocutaneous flap to cover post-mastectomy area.


Lesion/Defect
Flap
Flap

Fig. 7-108: Rhomboid flap.



Fig. 7-109: Cross-leg flap.

end anastomosis and 1 cm in end to side anastomosis. Entrapment of periadventitia into the suture line will induce thrombosis. Final trimming of the cut ends is done. *Flushing of the lumen* with heparinised Ringer lactate or Hartmann's solution is done to remove small thrombi and to maintain wet operating field. Vessel ends are *dilated using forceps* to prevent spasm.

Suturing is done using 8 zero/9 zero *monofilament polypropylene* suture material. *Interrupted sutures* are used. Distance of the needle bite from the cut margin should *be twice* the thickness of the vessel wall. Bite is taken from adventitia outside into the lumen on one side then from lumen towards outside through adventitia on opposite side. Knot should *be always outside*. Carrel's triangulation technique with placement of three key stitches at equidistance in the circumference of the cut edges of the vessels. First two key stitches are placed at 120° gap; additional sutures are placed in this gap; vessels are turned over to visualize the remaining gap; in the middle 3rd key stitch is placed; further stitches are placed in the gap. Vessels should be completely apposed to prevent blood leak. Knots should be *on one side* of the suture line in end to end anastomosis; and should be on the *flap vessel side in end to side* anastomosis. In end to side suturing first posterior row is sutured; then anterior row is sutured. Deeper vessel in the area should be sutured first; then superficial one. Only after suturing of the both artery and vein is completed, then microclamps are released. Always microclamp distal to the suture line should be released. Again first venous clamps should be released then arterial. Last clamp to be released is arterial microclamp proximal to anastomosis. After release small leak at suture site will subside **(Fig. 7-110)**. Significant blood leak when observed is controlled by few additional sutures. *Bounding arterial pulse, pink flap, filled vein* suggests good perfusion. Local anaesthetic or papaverine instillation over the area may relieve or prevent spasm. If still features are not obvious refashioning of the anastomosis is needed. Two fine forceps are placed over the emptied vein with a gap in between; and releasing the proximal one if causes filling of vein distally, it means anastomosis is patent. Kinking, compression over the site should be avoided.

Complications are flap oedema, cyanosis, venous block, arterial spasm/block, flap failure. Flap temperature, oxygen tension assessment percutaneously, Doppler study are the methods used to assess the flap. When doubt exists *re-explore the flap immediately*; do not waste time by watch and wait policy.

Uses and advantages—free flap is used in reconstruction of cheek, mandible, neck, etc. Once flap takes it is cosmetically better. Perfusion is well maintained. Osteomyocutaneous flap like radial forearm flap, myocutaneous flap, fasciocutaneous flaps can be used as free flaps.

EAR LOBE REPAIR

It is commonly used cosmetic simple surgical procedure. Ear stud pierced point gets widened and will not hold the earring any more and lobule sags downwards. Problem is common in those who use overweight earrings/studs; in old people.

Technique: Xylocaine 1% plain (without adrenaline) is injected into the root of lower part of the ear lobule (lobule is supplied great auricular nerve) and directly over the margin of the defect (upper 2/3rd of lateral surface of external ear is supplied by auriculotemporal nerve and lower 1/3rd by great auricular nerve; upper 2/3rd of medial surface is supplied by lesser occipital nerve; lower 1/3rd by great auricular nerve). Elliptical circumferential defect area in the ear lobule is excised using no 11 sharp pointed blade. Tip of the ear lobule is held using a stay suture. Skin parts of the cut wound both in front and behind are approximated using 4 zero polypropylene sutures (interrupted mattress). Bites should not be taken


End-to-end interrupted suturing
1
2
Carrel's triangulation technique
Three key suture
3
End (of donor flap vessel) -to-side (side of recipient vessel) suturing
Posterior row suturing - First
Knots should be towards donor flap vessel

Fig. 7-110: Technique in end-to-end and end-to-side vascular anastomosis in free flap.

from the cartilage. Dressing is placed. Sutures are removed after 5-7 days. Re-piercing of the ear lobule is done only after 3 months **(Figs 7-111 to 7-113)**.

TOE NAIL EXCISION

It is done for trauma, infection and in ingrowing toe nail. *Ingrowing toe nail* is a real problem as it is often recurring, distressing due to pain, infection and tenderness. Hypertrophy of soft tissue with formation of protruded unhealthy granulation tissue is common. Often foul smelling pus exudes out. Medial or lateral or both margin/margins are ingrown on the edge causing soft tissue injury and irritation. It is common in great toe often bilateral.

Zadik's excision (Frank Raphael Zadik) of the toe nail is done. Procedure is done using finger tourniquet under digital local anaesthesia block using injection xylocaine 2% plain without adrenaline. Nail from the margin is carefully lifted using haemostat or Allis forceps and is avulsed off the nail bed. Here after avulsion of the nail, germinal matrix is also removed. Germinal matrix is located on the proximal third of the nail bed. It extends proximally under the skin fold and extending much more over the proximal corners. Entire germinal matrix should be removed carefully. Incision should extend more proximally near the edge. Flap is raised from the skin fold. Glistening whitish germinal matrix is identified and it is excised. Flap is placed back. Suturing is not done. Careful phenolisation of the specified area without any spillage into the surrounding tissues prevents the recurrence. Phenol applied is allowed to settle for 5 minutes and is neutralised using alcohol. Application of phenol is useful in presence of infection. Often only medial or lateral margin of the nail is removed. Here nail is retained in the centre. But problem here, even though cosmetically better is, recurrence of ingrowing toe nail **(Figs 7-114 to 7-116)**.

DERMABRASION

Dermabrasion is a cosmetic medical procedure in which the surface of the epidermis of the skin (the stratum corneum) is removed by abrasion (sanding). The instrument used to perform the procedure is called a dermabrader. It is used to remove sun-damaged skin, to remove or lessen scars and dark spots on the skin. The procedure is very painful and usually requires a general anaesthesia or twilight anaesthesia, in which the patient is still partly conscious. Afterward, the skin is very red and raw-looking, and takes several months for the skin to regrow and heal. Dermabrasion is useful for scar removal especially when the scar is raised above the surrounding skin, but is less effective in sunken scars. In the past, dermabrasion was done using a small, sterilised, electric sander. In the past decade, it has


Syringe with 26 G needle
No 11 blade
Needle holder with 4 zero prolene in cutting needle
Skin hooks
Mosquito forceps

Fig. 7-111: Instruments used in ear lobe repair.


Defect may be a hole-like or through and through
Cutting the edge elliptically both in front and behind
After trimming the edge of the defect
– – margin of the raw defect
Stay suture on the summit
Suturing both front and behind
Stay suture on the summit
Suturing in through and through defect
In through and through defect
Final mattress sutures in front and behind

Fig. 7-112: Diagram showing steps in ear lobe repair.

become more common to use a CO_2 or Erbium:YAG laser. Laser dermabrasion is much easier to control, much easier to gauge, and is practically bloodless compared to classic dermabrasion. Microdermabrasion, crystal dermabrasion, diamond dermabrasion are different types. Even though healing is slow, eventual result is cosmetically better **(Fig. 7-117)**.

VENEPUNCTURE

Forearm veins are commonly used. Venepuncture is needed for fluid therapy, parenteral drug therapy, transfusions, etc. Clothing of the arm and forearm is removed. Hairs are shaved from the site. Area is cleaned with spirit. Tourniquet is applied above in the arm. Patient is asked to fist the fingers. Needle is passed obliquely into the skin with its bevel facing front and to the prominent vein. Skin puncture is 5 mm distal to the site of entry of the vein. Blood will enter the syringe. Intravenous cannula when used needle is removed once it is inside the vein which is confirmed by the blood flow; cannula is pushed into the vein entirely; needle is removed; cannula is connected to IV set and fluid. Cannula is fixed using plasters. Small dose of heparin should be flushed into the cannula daily to prevent thrombophlebitis.

Problems with venepuncture: Veins may not be visible. Flow may not be sufficient. Circulatory overload, thrombophlebitis, local haematoma, infection are common problems. Infection may be often hospital acquired and severe enough to cause septicaemia. Abscess at local site, oedema are also common. Air embolism if IV set is not closed once drip fluid gets over is a real danger.

VENESECTION

It means accessing the vein by *open surgical* approach. It is done in a patient inshock where peripheral vein or central vein cannot be cannulated. It aids in rapid fluid therapy in shock, monitoring of central venous pressure, administration of different drugs.

Incision: Usually upper arm on lateral aspect or in the leg on medial, posterior lower aspect is used. In the upper arm cephalic vein is used (if CVP monitoring is needed cephalic vein is selected); in the leg long saphenous vein is used. Cephalic vein is used in upper/mid-arm aspect, laterally between triceps and biceps muscles. Long saphenous vein is cannulated 1-2 cm above and posterior to the medial malleoli. *Saphenous vein* is superficial in the subcutaneous plane. But *cephalic vein* is deep and needs deeper dissection. Inadvertent dissection may cause injury to brachial vessels and so one should be careful.

Procedure: Area is cleaned and draped with aseptic precautions. *Transverse incision* is made. Skin, subcutaneous tissue is incised. Vein is identified by its bluish nature. It is dissected using mosquito forceps and freed of from adjacent tissues for 2 cm. Two thread or silk sutures are passed under the vein, each with 1 cm gap. Distal thread is ligated. Aneurysm needle may be helpful for proper dissection and passing ligatures around the vein. Front aspect of the vein is opened using a scalpel blade no 11. Venous cannula or venous catheter or polythene tube or infant feeding tube with cut tip is passed adequately. Its tip is empirically adjusted to place at subclavian vein or at superior vena cava. C-arm monitoring may confirm it if needed (usually not used). Patency of the vein is


Widened ear lobule stud opening
A
Xylocaine plain and fine needle used to give local anaesthesia
FOR SINGLE USE ONLY
caine Hydrochloride Injection IP
ylocaine® 2%
% 30 ml
C
FOR SINGLE USE ONLY
Injecting local anaesthesia
D
Elliptical skin of the margins of the defect
is removed through and through
B
Removal of elliptical skin from the defect edge
E

Figs 7-113A to E


4 zero prolene is used for suturing. Initially stay suture over the summit-
later interrupted mattress sutures infront and behind separately are placed
F
Front
Suturing front and behind separately-interrupted mattress sutures
Placing dressing
Behind
G

Figs 7-113F and G

Figs 7-113A to G: Operative steps in ear lobe repair.

confirmed by pushing the saline and rapid flow of fluid through the drip. Proximal thread is tied around the cannula. Skin is closed and cannula is secured firmly **(Figs 7-118 and 7-119)**.

Complications-Problems—Often difficult to get vein as vein may be collapsed due to shock or vein may be thrombosed due to repeated earlier venepuncture. Thrombosis of vein, blockage, bleeding, sepsis, failure, displacement of cannula are other complications.


Eponychium
Root of nail
Germinal matrix
Lunula
Hyponychium (Subungual space)

Fig. 7-114: Anatomy of the nail.



Figs 7-115A and B: Ingrown toe nail with hypertrophied soft tissue.


Nail
Incision
Incision
Germinal matrix
Hypertrophied infected tissue
Skin nail fold flap
One side ingrowing toe nail with hypertrophied tissue. Partial excision of nail and germinal matrix Cosmetically good procedure
One margin partial excision
Germinal matrix
Hypertrophied infected tissue
Hypertrophied infected tissue
Skin nail fold flap
Both medial and lateral margins – ingrowing toe nail. Nail and germinal matrix in both margins are removed– Cosmetically better
Germinal matrix
Both margins of the nail of the toe — Excised — Partial excision
Hypertrophied infected tissue
Skin nail fold flap
Disease ingrowing both margin – Total excision of nail and germina matrix – This is IDEAL. But not cosmetic
Excision of the entire nail with germinal matrix
Germinal matrix

Fig. 7-116: Technique of excision of nail, partial and complete with removal of adjacent or entire germinal matrix. Note the incision used for removal of the germinal matrix.



Figs 7-117A and B: Rhinophyma—typical look. Also observe after scraping/ dermabrasion.

INTRAOSSEOUS FLUID THERAPY

Intraosseous fluid therapy is useful in children whenever intravenous access has failed completely. Through vascular bone marrow fluid is infused which reaches main circulation in 10 seconds. Specific needles *(Sussmane-Raszynski needle)* are available for this purpose. 18 G spinal or bone marrow aspiration needle is also can be used. Local anaesthesia is injected under the skin. Tibia is ideal site. Children *below* 5 years, *upper end of tibia* is used—anteromedial aspect just below the tibial tuberosity with direction of the needle will be *caudal*. In *children above 5 years* and in adult, *lower end of tibia* 5 cm above the medial malleolus is used. Here direction of needle will be *cephalad*. This part of the bone is thin and flat and so it is easier to puncture. Lower end is not used in children below 5 years. Intraosseous fluid flow is usually at the rate of 10-15 ml/ minute **(Fig. 7-120)**.


Clavipectoral fascia
Cephalic vein
Medial basilic vein
Median cubital vein
Medial cutaneous nerve of forearm
Lateral cutaneous nerve of thigh
Accessory cephalic vein
Cephalic vein
Median vein of forearm
Radial nerve
Basilic vein
Dorsal branch of ulnar nerve
Dorsal venous arch
Upper limb ventral aspect
Upper limb dorsal aspect

Fig. 7-118: Venous anatomy of the upper limb. *Cephalic vein* (preaxial vein of upper limb) is formed at lateral part of the dorsal venous arch runs upwards along the anatomical snuff box, lateral part of the forearm, lateral margin of the biceps brachii, lateral aspect of the arm. At lower margin of the pectoralis major, after piercing the deep fascia, it passes through deltopectoral groove, clavipectoral fascia to enter the cephalic vein. *Median cubital vein* is a large communicating vein begins from cephalic vein 2.5 cm below the elbow crossing obliquely from lateral to medial side to reach the basilic vein 2.5 cm above medial epicondyle. Median cubital vein is located in front of the bicipital aponeurosis, through which a constant perforator vein from deep veins pierces. This perforator vein fixes the median cubital vein making this vein ideal for intravenous injections, drawing blood. Median cubital vein is absent in 30% of individuals; in such occasions basilic vein is used in drawing blood than cephalic vein as it is more efficient. Cephalic vein is mainly used for venesection. *Basilic vein* is post-axial upper limb vein; begins at lateral aspect of the dorsal venous arch; runs medially along forearm, elbow, medial border of the biceps brachii, medial part of the arm. In middle of the arm it pierces the deep fascia running along the medial aspect of the brachial artery; continues as axillary vein at the lower margin of the teres major.


(1)
Cephalic vein
Transverse incision
(2)
Exposure of the vein
(3)
Dissection of the vein for 2 cm length
(4)
Proximal ligature
Distal ligature
Separate incision to pass venous catheter
Passing silk ligatures-distal ligature is tied
(5)
Opening the front of the vein using scissor or no 11 blade
Opened vein wall
(6)
(7)
Passing venous catheter through separate incision into the opened vein
(8)
Proximal ligature is tied over the venous catheter
(9)
(10)
Final wound suturing and fixation of the venous catheter

Fig. 7-119: Venesection—steps (Venous cutdown)—shown here is in cephalic vein.

SUBCUTANEOUS INFUSIONS AS FLUID THERAPY

It is rarely used but in dire time can be used only for fluid therapy. Sites used are—outer aspect of the thigh, abdominal wall, and lateral chest wall. After cleaning the wide skin area, needle is inserted (20 G needle) into the subcutaneous tissue and is connected to drip. Usual infusion rate possible is 80 ml/minute. *Problems are*—pain, swelling, infection and slow absorption of the fluid.

LOCAL/REGIONAL ANAESTHESIA

Carl Koller, an *ophthalmologist* introduced cocaine as local anaesthetic in ophthalmic practice. Mode of action: It causes temporary conduction block of the nerve, thus preventing the propagation of nerve impulse. *Advantages* of local anaesthetic agents are—It is technically simpler; general anaesthesia is avoided; patient's consciousness is retained; Patient can have food earlier after surgery.



Fig. 7-120: Intraosseous fluid therapy sites.

Drugs used:

Cocaine, procaine, cinchocaine— amino esters.
Lignocaine, prilocaine, bupivacaine, ropivacaine–amino amides.

Lignocaine/lidocaine/xylocaine: It is the commonest local anaesthetic agent used. It is available as 0.25-5% concentrations. It is metabolised in the liver and excreted in the kidney as xylidines. It is also an antiarrhythmic drug and so commonly used in cardiology and cardiac surgery.

Side effects: Giddiness, headache, postural hypotension, tinnitus, circumoral anaesthesia, rarely anaphylaxis, convulsions and cardiac arrest if it becomes inadvertently intravenous.

Local anaesthesia infiltration is painful; intradermal injection of the drug is effective but much more painful. Using fine gauge needle (24 G/26 G) will reduce the pain. Adding bicarbonate into the drug increases the efficacy and reduces the pain. A combination of lignocaine and prilocaine (EMLA) topical agent prior to injecting the drug (one hour prior) prevents such pain.

Dose: 4 mg/Kg. Its effect lasts for 90 minutes.

Uses:

- Topical: 4%.
- Infiltration block: 0.5-2%.
- Field block: 0.5-2%.
- Nerve block: 1.0%.
- Epidural: 1.5, 2.0%.
- Spinal: 5%.

It can be used with or without adrenaline. Xylocaine with adrenaline (1 in 200000) has got longer duration of action. It creates relatively bloodless field. Higher dose can be injected as absorption is slow (7 mg/Kg). But it should not be used in places where end arteries are present like glans penis, ear lobule, tip of the nose, lip, fingers and toes.

Bupivacaine (Marcaine): It has got prolonged action. It is a vasodilator also. It is used as 0.25-0.5%. It takes more time to begin its action but has got prolonged action of 8 hours. Dose: 3 mg/Kg. For epidural block: 0.5%; spinal 0.5% of 3 ml solution.

Topical Anaesthesia

It is used for minor surgeries of eye, laryngoscopy, bronchoscopy, cystoscopy, gastroscopy, submucus injection. It is available as instillation, spray, viscous, ointment, gel, *EMLA* (Eutectic mixture of local anaesthetic).

Infiltration Block

Direct injection of local anaesthetic under the skin for small procedures.

Field Block

It is achieved by blocking the entire field of excision where lesion is located.

Nerve Block

- Block of inferior dental nerve and lingual nerves in the region of the mental foramen for extraction of teeth.
- Finger block of digital nerves. Here plain xylocaine is used (without adrenaline)—*digital nerve block*. It is injected just distal to web space near base of the finger on either side into palmar and dorsal digital nerves.
- Intercostal block.
- Ankle block.
- Median and ulnar nerve block.
- Brachial plexus block (Winnie's block)—It can be given through Interscalene, axillary, supraclavicular approaches. Supraclavicular approach is commonly used. 1 cm above the mid-point of the clavicle, needle is passed downwards, backwards and medially towards first rib. Once needle hits the first rib, 15-20 ml of 1.5% xylocaine is injected (with walking or stepping over the first rib). Complications are pneumothorax and injury to the great vessels.

Other Blocks

Cervical plexus block; sciatic nerve block; femoral nerve block.

Intravenous Regional Anaesthesia (Bier's Block)

Limb is exsanguinated and occluded with tourniquet. Pressure in the tourniquet must be 30 mm Hg more than the systolic pressure of the patient. Needle is placed in the selected vein. 40 ml of 0.5% xylocaine for upper limb and 80 ml of 0.25% of xylocaine for lower limb is injected into the vein. *Xylocaine with adrenaline should not be used.* It gives very good analgesia for 2 hours. Side effects: Sudden release of drug into the circulation can cause hypotension, convulsions and often death. Bupivacaine should not be used.

Indications: For upper and lower limb surgeries it can be used without general or spinal anaesthesia.

Spinal Anaesthesia

Xylocaine or bupivacaine is injected into subarachnoid space using long (disposable needles are available now) needle (***Quincke spinal needle***). It is 10 cm long with stillete inside it. Transparent hub needle is available now. 25 G/27 G needles are finer and better with lesser complications especially headache and backache. *Refer lumbar puncture* for details.

Saddle block: It is used for surgeries in perineal and anorectal region. It is spinal anaesthesia using xylocaine or bupivacaine given in sitting position. It is low spinal block.

Epidural Anaesthesia

It is a potential space between dura anteriorly and ligamentum flavum posteriorly which has got negative pressure inside. It extends from foramen magnum to sacral haitus. ***Touhy needle*** is used for epidural anaesthesia. Once the needle is in the space there will be sudden indrawing of air or saline drop. An epidural catheter is placed in the space and fixed. 2% xylocaine with adrenaline or 0.5% bupivacaine is injected into the space to achieve anaesthesia up to the desired level **(Fig. 7-121)**.



Fig. 7-121: Epidural anaesthesia is being given.

Advantages: It can be used for continuous repeated prolonged anaesthesia. It can be used for post-operative analgesia. It can be kept for several days.

Caudal Anaesthesia

Caudal space is the sacral component of *epidural space* and access is through the sacral hiatus. *Indications:* Haemorrhoidal surgery; circumcision; small procedures in the perineum like cystoscopy. *Procedure:* It is given in lateral position. Needle is inserted through the sacral hiatus to enter the caudal epidural space. Drug is then injected into the space. It takes 20 minutes to act and so surgeon has to wait for this to act. *Complications:* Trauma to anal canal, intravascular injection, failure of caudal block is common.

Chapter

8

Principles of Surgical Management in Trauma

Trauma is the major cause of death worldwide. It can be road traffic accidents, stab injuries, thermal injuries, and gun shot related injuries.

Inexperienced motor skills, alcohol consumption; aggressive driving, influence of drugs are the common factors for RTA. Gun shot injuries becoming more common due to usage of guns for fights. Gun shot can cause local injury, compression injury, cavitational injury (10 times the diameter of the bullet), burn injury. Fall from height is also a major cause as it leads into spinal injury, internal organ injury. Fall from 10 meters height has got impact velocity of 50 kph. Fall from more than 15 meters height carries more than 50% mortality. Nature of landing surface, part of the body coming into contact with the surface first, deceleration force, body's position during landing.

Trauma is categorised as group trauma like in earth quake, train accidents, fire injury, etc. or individual trauma **(Fig. 8-1)**.

War injuries are of special type could be missile wounds, low velocity missile wounds or high velocity missile wounds or blast injuries.

Dictum in trauma is '*first save life; then think of limbs; later worry about sufferings*'.

ASSESSMENT OF SEVERITY OF THE INJURY

AIS (Abbreviated Injury Scale) scoring system is used once all injuries of the patient is identified. Each injury is scored from 1 to 6. An AIS score of 6 anywhere in the body is not compatible with life. So maximum score assessed in a live patient is 5. Square of three highest AIS scores within six areas in the body – head and neck; abdomen and pelvic contents; bony pelvis and limbs; face; chest and body surface is called as *Injury Severity Score* (ISS). Maximum ISS score is 5 × 5 + 5 × 5 + 5 × 5 = 75. Glasgow coma scale and revised trauma scale [RTS = respiratory weight × 0.2908 + systolic blood pressure weight × 0.7326 + GCS (Glasgow Coma Scale) weight × 0.9368] are commonly used in head injury patients.

Trauma and Injury Severity Score (TRISS) system is used by combining anatomical and physiological injuries **(Figs 8-2 and 8-3)**.

Severe trauma may be entrapment, high speed impact, collision, fall from height of more than 3 meters, ejection from a moving vehicle and penetrating injuries.



Fig. 8-1: Thorough warm saline wash is a must to all open wound. Wound excision is done by removing all devitalized tissue. Viable skin part should be retained for future reconstruction. Often such flap can be rotated as quilting into the defect area.



Fig. 8-2: Scalp trauma exposing outer table partly.



Fig. 8-3: Black eye. It may be a sign of intracranial bleed.

Baton round injury occurs during police firing in mob dispersion. It is rubber bullet/plastic compound injury occurring during police firing. It can cause bruising, lacerations or life threatening blunt injuries/penetrating injuries also. So *baton round injury* cannot be ignored.

Table 8-1: Glasgow coma scale (GSS)

Eye opening		*Verbal response*		*Motor response*	
Spontaneous	4	Oriented	5	Obeys commands	6
To Speech	3	Confused	4	Localises pain	5
To Pain	2	Inappropriate words	3	Flexion to pain	4
None	1	Incomprehensible words	2	Abnormal flexion	3
		None	1	Extension to pain	2
				None	1

Total score—15.
Mild head injury: 13—15.
Moderate head injury: 9—12.
Severe head injury: less than 8 [3—8].

Score 1—dead or dying.
Score 2—vegetative state.
Score 3—severe disability.
Score 4—moderate disability.
Score 5—good recovery.

PREHOSPITAL TRAUMA CARE

It is the initial safe resuscitation and proper arrangement and planning for transport as early as possible. It is done by police and fire service people. They should be trained for initial resuscitation. Transportation and ambulance service is essential. Well equipped ambulance should be available. Transport is done by vehicles, ambulances and helicopters. Careful transport is essential depending on the type of trauma. It is essential in spine injury, chest/abdominal/head injuries. A dedicated resuscitation team is ideal. 3 doctors, 2 nurses, 2 technicians are essential in the team with all essential facilities like central line, fluid therapy, emergency drugs, etc.

TERTIARY HOSPITAL CARE

Airway – Suctioning, clearing throat, clearing foreign bodies/dentures, oxygen, endotracheal intubation, percutaneous cricothyrotomy, tracheostomy are done, depending on need.

Breathing – Breathing is assessed and if needed intercostal tube drainage in case of pneumo or haemothorax should be inserted.

Circulation – It is assessed by pulse, blood pressure, capillary filing and monitoring. Proper perfusion and blood transfusion is needed. Two 12 or 14 G cannulas should be passed to have proper intravenous access. In difficult situations when patient is in shock with collapsed peripheral veins, long saphenous vein, cephalic vein, basilic vein, external jugular vein or femoral vein cannulation should be tried. Definitive venous cut down of long saphenous vein or cephalic vein should be done. Percutaneous puncture of internal jugular vein is also possible. Blood samples should be collected for electrolyte estimation, haematocrit, blood urea and creatinine, blood group and cross matching. Central venous catheter should be passed after that in all patients. It is passed through subclavian vein or through internal jugular vein. In children *intraosseous* route is possible to perfuse in emergency **(Fig. 8-4)**.

Initially isotonic crystalloid such as normal saline / Ringer's lactate is used. Once around 1500 ml of crystalloids are infused to bring up the volume, then colloids and blood are given. Dextrans, other volume expanders are also used in emergency but not more than 1500 ml. It is better to give warmed fluid of any of these forms to prevent hypothermia. Intravenous warmer devices are available. If patient is responding for initial 2 liters of fluid therapy means blood loss is more than 40% suggesting severe circulatory failure. *Blood transfusions* are given to maintain haematocrit at 30%.



Fig. 8-4: Intensive care is needed in critical trauma patient.

Nasogastric tube and urinary catheter placement is a must.

Monitoring is done by pulse, oxygen saturation, urine output with a indwelling catheter in situ (should be > 1 ml / kg / hour), platelet count, coagulation factors, serum electrolytes estimation, ECG monitoring, CVP and PCWP assessment, arterial blood gas analysis.

Further assessment is done by assessing neurological status, specific injuries in head, skull base, thorax, abdomen, pelvis and fractures. CT of part is ideal investigation. Usually plain CT without contrast is done. Hypoxia, hypercapnia, hypotension are the important critical factors. Spine injury may be missed very often in initial assessment. It should be carefully assessed and if needed/suspected should be evaluated by CT imaging. MRI is not possible in initial phase of resuscitation which should be done at later period.

Often endotracheal intubation, ventilator or tracheostomy may be needed and should be utilized without any hesitation to save the life.

Adequate analgesia is important. Morphine/dimorphine/NSAIDs intramuscularly can be given. *Temporary immobilization* using proper splintage for long bone fractures reduces the pain severity. Fixation in pelvic fractures with external fixator reduces the pain. Medical anti shock trouser (MAST) is used for shock.

Three primary X-rays are done even though they have got limitations. Chest X-ray to see pneumothorax/haemothorax/fracture ribs. But 30-40% of fracture ribs will be missed in X-ray. Cervical spine lateral X-ray and pelvis anteroposterior X-rays are taken.

Ultrasound abdomen, CT of chest, pelvis and abdomen is ideal. Diagnostic peritoneal lavage (DPL) is useful in blunt injury abdomen.



Fig. 8-5: X-ray should be taken to see the fracture. Soft tissue injury should be assessed properly.

ASSESSMENT OF THE WOUND

Size of the injury; extent of the damage – nerve, vessels, viscera, peripheral ischaemia especially in the limbs, presence of haematoma, extent of deeper injury including bones, entry wound and exit wound in missile injury are carefully assessed **(Fig. 8-5)**.

First Aid Management of the Wound

Large occlusive firm pressure dressing of the wound, compression bandage, control of haemorrhage, occasionally tourniquet application, positioning of the patient are the first aid measures often required.

Wound will be minimally contaminated in 0-6 hours; significantly contaminated in 6-12 hours; grossly contaminated in more than 12 hours **(Fig. 8-6)**.



Fig. 8-6: Skull bone is exposed without any retained periosteum. Such bone will not show any granulation tissue. Burr holes in many places on the outer table allow marrow to proliferate as granulation tissue; later area is covered with flap. Care should be taken while doing burr drills to avoid injury to the venous sinuses.

WOUND EXCISION AND MANAGEMENT

Wound excision should be done under *general* anaesthesia. Local anaesthesia should be avoided. Here dead/damaged or contaminated tissues are excised. All foreign bodies should be removed. Exception for this is probably bullet injuries/pellet injuries. It is often difficult to remove a bullet or multiple pellets. They may be in close proximity to the major vessel or often difficult to identify and remove. During entry they are in high temperature and so are absolutely sterile; will not precipitate any contamination. Control of bleeding is also an essential part in wound excision.

Tourniquet during surgery (wound radical excision) is used only if it is inevitable; otherwise should be avoided as it is difficult to differentiate dead and living tissue under tourniquet. Hairs should be removed 1 cm beyond the margin of the wound. Skin and wound should be thoroughly scrubbed with soap, water and saline for 5–10 minutes until it appears clean and then area is widely cleaned with povidone iodine before draping. Proper initial irrigation of the contaminated wound often using pressure devices is important to remove dirty particles from the surface. Incision placed in the wound should be enlarged/extended liberally without any hesitation especially in penetrating wounds, war wounds, bullet wounds, crush wounds, entry wound of bullet, multiple deep wounds. Exploring the entire wound is very important. Excision is done until healthy bleeding live tissue is reached. Excision should be done by sharp dissection using knife or scissor. Underlying nerves and major feeding vessels should be protected. Skin is excised for 2 mm from the contaminated edge. There is no use in retaining the dead tissue and no point in cutting healthy skin which is again essential for future closure or reconstruction. Wound can be re-inspected for further wound excision if needed especially skin after 48 hours.

Often *flap-like injury* when found with a wide base it can be retained provided it is relatively healthy. Crushed skin may not be vital for placing. Flap should be washed, irrigated and placed over the raw area. When such flap sustenance is not sure, the flap can be cut fully, fat underneath should be cleared and sutured like a free full thickness graft. It is also possible take split thickness graft taken from the surface of such flap using a Humby's knife, can be very well placed on the defect area which often takes properly. Fat in the entire area should be excised otherwise it is a sure way of causing necrosis and contamination of the area in later period. Fascial layers should be split. Ragged devitalised part should be excised. Oedema underneath the fascial layer causes initial impairment of venous and lymphatic drainage later blocking arterial function leading into distal ischaemia, necrosis and gangrene. Lengthy liberal fasciotomy is a must in these patients. All *devitalised, dying and dead muscles* should be excised without fail. There is no reason to retain the dead muscle at all. Dead muscle is a sure way for infection like Clostridium bacteria. All haematomas should be evacuated liberally. After radical wound excision if there spurting bleeders, it should be ligated securely using fine absorbable sutures **(Figs 8-7 to 8-10)**.



Fig. 8-7: Crush injury of ankle.



Fig. 8-8: Degloving injury of buttock region. It is eventually covered using a flap.



Fig. 8-9: Extensive injury in a child due to dog bite. Wound debridement should be done under general anaesthesia.



Fig. 8-10: Injury to the lower lip causing defect in its central part which is primarily repaired.

Nerve injury is dealt in different ways. If wound is clean and healthy it is sutured primarily with non-absorbable sutures; otherwise it is trimmed and tethered to the adjacent soft tissues loosely using non-absorbable sutures to prevent recoiling. Later once wound clean it is taken up for repair. Many nerves are injured it should be tagged in different coloured sutures for eventual identification purpose.

Exposed tendons can be left alone; but if with denuded paratenon as tendon will necrose it should be excised. Repair of tendon may be done at later period in such occasion. If it is a clean incised tendon injury then only primary repair of tendon is done.

Bone even though injured until periosteum is intact, it heals well. Skin can be covered over periosteum. If periosteum is denuded then flap is needed to cover it. Bone fixation, prevention of sepsis and flap cover is needed plan in these patients.

Joint injury needs early immediate cover to prevent from anticipated infection. Synovium should be sutured with interrupted sutures. Proper wound cleaning with adequate ideal antibiotics are mandatory.

Major vessel injury should be sutured as per vascular anastomosis rule.

Body cavities when opened by trauma should be closed. Dura should be closed by temporalis fascia graft.

Primary closure means closure done immediately after wound excision. Delayed primary closure in 5 days after wound excision. Secondary late closure is closure done after 5 days. When in doubt do not close the wound immediately—is the principle.

PRINCIPLES IN USAGE OF ANTIBIOTICS

It is a debate whether use to it or not. In minor wounds it is not necessary to take antibiotics or single intravenous dose is sufficient. In major wounds it is essential to give antibiotics intravenously; an oral antibiotic in initial phase of therapy is less preferred one than intravenous one. Intravenous penicillin or cephalosporins are given conventionally. Higher generation antibiotics are used depending on the need and contamination.

One should remember that antibiotics are not a substitute for adequate wound care. There is no short coming in proper wound care to have a good final outcome.

Gas gangrene is more common in deep ragged wounds, crush injuries, war wounds, blast injuries. Radical wound excision and closure of wound only at later period are the important preventive measures. In suspected cases anti-gas gangrene serum should be injected.

Immobilisation is often very important in major wounds even if there is no bony injury. Immobilisation improves healing; reduces the pain; possibly decreases the infection rate.

MANAGEMENT OF FOREIGN BODY

Unlike many think it is usually not an emergency procedure unless it is causing life threatening problems. Image intensifier (C-arm) should be used to remove foreign body. It should be done under general anesthesia. Tourniquet is used when it is in the limbs. Adequate incision with wide exposure is a must. Gentle finger exploration is better than of instruments as feel of the foreign body is more appreciable than through the instrument. Every foreign body need not be removed (like bullets/pellets). Even if in 45 minutes foreign body is not retrieved, procedure should be abandoned.

TRIAGE

Triage: Triage means `*To sort' in `French'*.
Triage was formulated by a committee of Trauma of the American College of Surgeons.

***Advanced Trauma Life Support (ATLS)** is essential for first hour care of an inujred patient.*

***Pre-hospital Trauma Life Support (PHTLS)** is to prevent deaths while injured patients are transported to the hospital.*

Types of Triage System

Multiple casualties – Staff and facilities are sufficient, net priority is given to life threatening injuries.

Mass casualties – Staff and facilities are not sufficient to manage. Here those who are likely to have highest chance of survival are given priority.

CONCEPTS IN TRAUMA MANAGEMENT

Concept of 'golden hour' to treat the trauma patient is important. Multidisciplinary approach; planning, setting up, organizing, team work; assessing respiratory system; circulation; bleeding areas – as priority; assessing also whether patient is haemodynamically stable or unstable; arranging fluids, blood, catheters, ventilator, etc. Further definitive therapy is undertaken depending on severity and site of injury.

DAMAGE CONTROL SURGERY

It includes - Resuscitation and early therapy in operation theatre itself; minimum but essential surgery to control bleeding and prevent contamination; Secondary definitive surgery at a later period to have final control.

Assessing four components

i. Physiologic response.
ii. Anatomical injury.
iii. Biomechanical injury.
iv. Comorbid factors.

Triage algorithm

STEP ONE (Assess physiological impact)

- Measure vital signs and level of consciousness.
  - By Glasgow coma scale.
  - Systolic blood pressure.
  - Respiratory rate.
  - Revised trauma score. It is based on airway, laryngeal injury, spine injury, maxillofacial injury.

STEP TWO (Assess anatomical impact)

- All penetrating injuries to head, neck, thorax, major burns, fracture bones, pelvic fractures, paralysis.

STEP THREE (Assess mechanism)

- Automobile accidents, crash or blast injuries, high energy injuries, fall from more than 20 feet.
- Bullet injury.

Contd...

Contd...

STEP FOUR (Assess history)

- Patient`s age below 5 years or age more than 55 years.
- Cardiac diseases, respiratory and metabolic diseases.
- Pregnancy.
- Patients with bleeding disorders.
- Immunosuppressed individuals.

BASED ON THE STEP CONSIDER TO SHIFT THE PATIENT TO TRAUMA CENTER & TRAUMA TEAM SHOULD BE KEPT ALERT.

It is important in multiple and mass casualities (fire, blasts, automobile accidents, train accidents).

Management includes – Goals; Primary management; Investigations; Secondary survey; Definitive care.

Tag the patient accordingly

Red colour: Immediate treatment is required.
Yellow colour: Urgent treatment is required.
Green colour: Delayed treatment is required.
Blue colour: Expectant treatment is required.
Black colour: Deceased.

Primary management - ABCDEF

AIRWAY
Chin lift.
Jaw thrust.
Nasal airway.
Oral airway.
Endotracheal intubation.
Tracheostomy.
[Assess airway patency].

BREATHING
100% oxygen.
Assess bilateral chest raise.
Assess breath sounds.
Use pulse oximetry.
Treat flail chest, pneumothorax.
Intercostal tube drainage.

CIRCULATION
Monitor vitals.
Heart sounds.
ECG.
IV fluids Blood transfusion.
Treatment of shock.
Control of external bleed.
Use two IV lines-14G/16G.]

DISABILITY EVALUATION
Neurological examination.
Glasgow coma scale.
Pupillary reaction.

EXPOSE THE PATIENT FULLY
Undress the patient.
Hypothermia assessment.

Assess injuries.
Examine joints, bones, abdomen, other systems.
Look for identification marks.

FINGERS and TUBES
Examine all orifices like P/R,P/V, etc.
Use required tubes like catheter, Ryle`s tube.

GOALS	INVESTIGATIONS
Identify life threatening conditions.	X-ray spine, chest, pelvis, extremities.
Decide and implement appropriate treatment to the area of trauma.	CT scan.
First think of salvage of life, then think of salvage of limb.	Blood group and cross matching.
Rapid assessment, rapid resuscitation, rapid stabilisation.	Arterial blood gas analysis.
Optimum, complete care.	Serum electrolytes.
Transport efficiently to higher trauma center.	U/S abdomen.

Contd...

Contd...

Categorise the patient.	
i. Deceased.	
ii. Walking wounded.	
iii. Immobile wounded.	
iv. Trapped wounded.	
SECONDARY SURVEY	DEFINITIVE CARE
Re-evaluate the patient completely again.	

NECK INJURIES

Neck is divided into zones for managing neck injuries. *Zone I* is from clavicle to cricoid cartilage. Injury here may extend into the mediastinum/thorax. *Zone II* is from cricoid cartilage to angle of the mandible. *Zone III* is above the angle of the mandible. Injury here may extend into cranial cavity or skull base; extended vascular injuries here are quite difficult to manage **(Fig. 8-11)**.

Indications for neck exploration in injuries are - Expanding haematoma; uncontrolled external haemorrhage; decreased carotid pulse; stridor, hoarseness, dysphonia, haemoptysis; severe dysphagia, odynophagia; blood in oropharynx. Vital structures in compact area make neck injury an area of priority. Penetrating injuries of major vessels (20%), trachea, oesophagus, thyroid, and nerve plexus can cause severe problems. Exact anatomical extent of the injury should be assessed. Extension into pharynx, larynx, chest or mediastinum should be thought of. Anterior triangle injuries pose a high threat than posterior triangle injury. CT neck is the ideal investigation for neck injuries. One must also think of possible injuries like Le Fort facial injuries; cervical spine injuries; skull base injuries which should be assessed clinically and radiologically properly before jumping into hurried intervention.

Treatment

Patient with aerodigestive and vascular injury needs neck exploration. It is the exploration of the neck rather the wound as such is important. Oblique incision along the anterior border of the sternomastoid is done in unilateral injury. Bilateral connecting collar incision along the anterior borders of the both sternomastoid muscles is used for bilateral injuries of the neck **(Fig. 8-12)**.

Intraoperative endoscopy to identify injuries of trachea and oesophagus is beneficial. Methylene blue instillation into the oesophagus will identify the oesophageal tear. Neck is explored with adequate incision under general anaesthesia. Suturing of the injured structure like carotid, oesophagus, trachea, muscles, etc. is done. External carotid artery can be safely ligated. Internal carotid or common carotid requires repair often using vein or PTFE graft. Tracheal injury up to two rings can be repaired primarily using interrupted non-absorbable sutures like polypropylene. Loss of more than two rings needs tracheostomy. In laryngeal injuries cartilage fractures should be reduced; mucosal lacerations should be sutured. Oesophageal injury if identified within 12 hours of injury is repaired primarily in two layers of interrupted PDS/vicryl with nasogastric tube in situ. Drain to the wound is a must. Injury identified after 12 hours of trauma or extensive injury of cervical oesophagus needs; initial cervical oesophagostomy and later reconstruction. Often total oesophagectomy with gastric/jejunal colonic interposition may be needed. Antibiotics, blood transfusion, nasogastric tube passing—as required.

THORACIC TRAUMA

Thoracic trauma is the cause of 25% of all trauma deaths. Cardiac injury is the cause for early deaths. Airway obstruction, tension pneumothorax, massive haemothorax, cardiac tamponade are other causes of death which are actually preventable in *golden hours*. Chest trauma causes *hypoxia, hypercapnia and acidosis*. Chest X-ray,



Fig. 8-11: Neck zones used in neck trauma.



Fig. 8-12: Incision in neck trauma is oblique one along the anterior border of sternomastoid muscle.

CT chest and ultrasound chest are diagnostic methods in chest trauma. But in severe critical cases one should not wait for these investigations. Instead it is better to take up straight a way the therapeutic parts like *intercostal tube drainage* (tube thoracostomy), aspiration of tension pneumothorax and cardiac tamponade.

The thoracostomy (ICT drainage) is done in midaxillary line in 6th intercostal space. In slight head up position, after injecting xylocaine 1% local anaesthesia, 1 cm incision is made in the space in lower part of the space to avoid injury to the intercostal vessels. External and internal intercostal muscles are split; pleura is opened; finger is inserted and blunt finger dissection is done; mattress stay suture is loosely placed using polyethylene suture; 40 French IC tube with end and side holes is introduced. Tube is directed above and posteriorly. Tube is secured to the skin by tying the tube. Tube is connected to under water seal apparatus. If pre-insertion suture is not placed, suture is placed later after inserting the tube. Postoperative air column movement is observed. *Absence of air leak; fluid drain less than 100 ml/day; chest X-ray* if shows adequate expansion then tube can be removed safely.

Twenty percent of chest trauma patients *need thoracotomy* and definitive repair of injured intrathoracic structures. *Indications are* – massive haemothorax with more than 1500 ml of blood in ICT when passed or hourly drainage if more than 300 ml/hour; pericardial/cardiac injuries; thoracic cage open wounds; thoracic vascular injury; tracheobronchial tree injury; oesophageal injuries. All these indications are critical and life threatening situations. But still if proper cardiothoracic set up is available and timely intervention is done, life can be saved **(Fig. 8-13)**.



Fig. 8-13: Open communicating wound in thorax/chest wall.

Rib fractures are the commonest type of chest trauma. But commonly it does not cause problem unless there is haemothorax or pneumothorax. 4th to 10th ribs are commonly fractured. Rib fracture causes severe *pain, reduces the ability to cough, and reduces vital capacity causing atelectasis and pneumonia*. Pain on *inspiration* is the main feature in rib fracture along with *crepitus.* Proper pain control is essential using intravenous analgesics, epidural analgesia. *Flail chest* (15%) with fractures in two or more ribs, with each rib having two or more fracture sites causes chest wall instability → paradoxical movement of the chest wall (during inspiration flail segment is drawn in) → pendular movement of the air → mediastinal flutter → sudden kinking of great vessel → respiratory failure and cardiac arrest. It can be anterior, lateral or posterior. Pain and pulmonary contusion is common. Endotracheal intubation, ICT placement, tracheostomy, prevention of movements of flail segment is needed.

Pulmonary contusion is a different typical recognised entity. It can be commonly due to blunt trauma or often due to penetrating injury. It commonly causes respiratory failure. So along with management of mechanical problem, respiratory problems also should be dealt with carefully. Arterial blood gas analysis is a must. *Measures are*—Crystalloid infusion, oxygen support, avoiding fluid overload, maintaining the tissue perfusion, blood transfusion, ventilator support, transfusion of packed cells and blood products.

Pneumothorax – It can be *small* pneumothorax with volume loss is 1/3rd of normal lung volume*; large* pneumothorax with complete collapse of the lung on one side but without any tracheal/mediastinal shift; *tension* pneumothorax which is a critical emergency situation with tracheal mediastinal shift towards opposite side causing *hypotension* decreased cardiac venous return and cardiac arrest and acute respiratory distress or *open pneumothorax* with a large chest wall *sucking open wound*. Pneumothorax needs ICT placement in 4th space in midaxillary line. Tension pneumothorax needs emergency placement of *wide bore needle in midclavicular line in 2nd intercostal space* with a glove finger placed over the hub of the needle to prevent air getting sucked inside during expiration; later ICT should be placed. Open pneumothorax needs open *surgical closure* of the chest wall defect with an ICT in place **(Fig. 8-14)**.

Haemothorax – 80% of haemothorax is treated by ICT placement. Remaining 20% needs thoracotomy and control of bleeding like resection of lung.

Pulmonary injury - Small lacerations of the lung are common but are treated with ICT. 10% of patients will have large significant lacerations with massive air leak through ICT. It needs thoracotomy, lung sparing resections like nonanatomic resection or tractomy using stapling device. Extensive lung injury occasionally needs lobectomy or pneumonectomy as life saving measure. Persistent air leak in ICT may be due to broncho-pleural fistula.

Tracheobronchial tree injury is difficult to mange. It needs initial bronchoscopy to identify the site and extent. Later thoracotomy is done to explore entire tracheobronchial tree, depends on the side of injury. Small injury heals spontaneously. Injury more than 1/3rd of


Collapsed lung
Needle in midclavicular line in 2nd intercostal space
Pleura
1
2
3
Heart
Air (tension pneumothorax)

Fig. 8-14: Emergency aspiration through 2nd intercostal space in midclavicular line is life saving measure in tension pneumothorax.

the circumference of the tracheobronchial tree needs primary repair using polypropylene interrupted sutures with selective intubation of the opposite bronchus. Collapse of lung, stricture of tracheobronchial tree, pneumonia and septicaemia are distressing complications.

Cardiac injury – Blunt injury to anterior chest wall causes cardiac trauma. It may be minor contusion of the wall, major contusion, cardiac chamber rupture, haemopericardium and death. Right ventricle is commonly affected as it lies near to the anterior chest wall. If patient reaches the hospital it is diagnosed by US chest, echocardiography, CT chest and ECG. ECG and raised serum troponin I level suggests early or late myocardial damage. *Treatment* in small contusions continuous ECG monitoring and observation. Major injuries need *urgent thoracotomy* and surgical repair by cardiac surgeons. *Pericardial tap* may be helpful in haemopericardium. Mortality rate is more than 80% in major cardiac injuries. During admission if pulse is felt survival rate increases to 70% with proper intervention and care. Even cardiac tamponade due to haemopericardium needs early open surgical intervention as tamponade itself is a temporary natural haemodynamic compensatory mechanism.

Oesophageal injuries – Thoracic oesophageal injuries are rare as it is located in posterior mediastinum. It occurs due to deep penetrating injuries. It is often difficult to diagnose. It is always associated with other thoracic injuries. Oesophagoscopy and oesophagography, increased oesophageal pressure, CT chest may reveal oesophageal injury. Problems with oesophageal injury are – empyema, mediastinitis and septicaemia. If identified within 24 hours of trauma, early debridement, primary repair, and drainage with nasogastric placement is the treatment. If identified after 24 hours, mediastinal sepsis is likely and so needs diversion with cervical oesophagostomy, feeding jejunostomy, oesophageal resection, later colonic/gastric transposition.

Diaphragmatic injury can occur in thoracic or abdominal injuries. It can be diagnosed by CT scan. But more often it is identified during laparotomy or thoracotomy. It is sutured using interrupted horizontal mattress sutures with polypropylene sutures.

ABDOMINAL TRAUMA

Abdominal trauma is a major emergency surgical problem which surgeons face. It is often associated with head, chest, pelvic and bone injuries. Often patient may be unconscious causing difficulty in diagnosing the condition. Often while giving more importance to other systems like head, thorax and bones and abdominal injury is not addressed properly causing life threatening consequences. When patient is conscious, history related to abdominal trauma is useful. Abrasion over the abdominal skin suggests possibility of internal injury (*London's sign*). Distension, tenderness, rebound tenderness, fullness and dullness in the flank, when present one should presume internal injury. Tachycardia, hypotension, shock may be evident when there is significant haemoperitoneum. Injuries may be organ injuries like of liver, spleen, kidney, pancreas. etc; or bowel injury or retroperitoneal injury which is often under diagnosed or missed. Major vessel injury like inferior vena cava, mesenteric vessels can cause real threat to life unless it is identified and managed early. 25% of entire trauma patients need surgical exploration of the abdomen.

Abdominal trauma can be *blunt or stab/penetrating or abdominal wall injuries*. Spleen is the commonest organ involved in *blunt trauma*. Often in blunt trauma first part of the jejunum or ileocaecal junction gives way (blow out effect) due to traction causing often complete transection of bowel horizontally close to the junction. It is due to force of the mobile part of the bowel over fixed part of the bowel. Liver is the commonest organ involved in *penetrating injuries* **(Fig. 8-15)**.


Fig. 8-15: Haemoperitoneum on table.

Injuries of the abdomen may be *closed injuries, compression injuries and penetrating injuries*. Penetrating injury may be low velocity injury like stab or high velocity injury like gunshot injury. Blunt weapon penetration causes lesser deep trauma than sharp weapon trauma (sickle, knife). In sickle injury tip and sharp edge moves in curved pattern and so it is often difficult to predict the depth, track and organs injured **(Figs 8-16 and 18-17)**.


Fig. 8-16: Penetrating injury of the abdomen and chest right sided. Patient fell over a tree which had its top end cut. Tree has penetrated into her abdomen and chest wall. Patient was brought after cutting the tree from its root. Patient survived after surgery.


Fig. 8-17: Stab wound in the abdomen with omentum protruding through the wound.

Blunt trauma is common in accidents. It is often missed or lately diagnosed. Ultrasound / CT abdomen or diagnostic peritoneal lavage (DPL) is useful. In many cases on clinical grounds direct exploratory laparotomy is done. Plain X-ray abdomen may show gas under diaphragm.

Difficulty arises in *deciding about the need for laparotomy* in abdominal trauma in *unconscious* patients. If external injury is not severe in proportionate to the existing severe shock then exploratory laparotomy is indicated in an unconscious patient. It is also often difficult to diagnose bowel injury in such patients. If it is suspected laparotomy should be undertaken in such patients.

Routinely followed indications in abdominal trauma are – hypotension without any other cause; bleeding through wound; continuous bleeding from nasogastric tube; evisceration of abdominal content through the open wound except in case of protruded omentum without any hypotension and features of peritoneal irritation; air under diaphragm in blunt abdominal injury (not in penetrating injury as external air gets sucked into the peritoneal cavity through the wound).

Ultrasound abdomen is very useful, simpler, non-invasive method of evaluating the abdomen. Negative ultrasound means no immediate further work is needed and also can be treated conservatively. *Advantages of ultrasound are* - there is no danger of radiation; it can be done at bedside; it can be repeated many times; it is cost effective. It is less useful in obesity, with gas interposition, intraperitoneal fluid less than 500 ml; retroperitoneal injuries and bowel injuries. Its sensitivity is 90%; specificity is 98%. Focused Abdominal Sonar (ultrasound) for Trauma *(FAST)* is very useful method. FAST is rapid, noninvasive, portable bedside method of investigation focusing on pericardium, splenic, hepatic and pelvic areas. Blood more than 100 ml in cavities can be identified. It is not reliable for bowel or penetrating injuries. It often needs to be repeated.

Diagnostic peritoneal lavage (DPL) (by Perry) is useful in *blunt injury* abdomen. It is not very useful in penetrating injury, bowel injury, retroperitoneal and pelvic injuries. It is the *procedure of choice in physiologically unstable patient* with blunt abdominal injury (like with spinal injury, unconscious patient, in situations where clinical signs cannot be interpreted, where injuries of more priority are in other areas like head or chest). 10 French polyvinyl catheter is used. Urinary bladder is emptied by passing a catheter. After injecting xylocaine local anaesthesia in subumbilical region, 2-3 cm vertical subumbilical midline incision is made. Skin, linea alba is incised. Local anaesthesia is infiltrated into the peritoneum again. Peritoneum is held with two haemostats and a purse string suture is placed using polylactic acid absorbable suture material. Peritoneum is incised for 3 mm length. Catheter (standard peritoneal dialysis catheter) is introduced into the peritoneal cavity. If blood enters the catheter immediately, it means early laparotomy is needed and carried out without continuing the peritoneal lavage. If otherwise, one liter of normal saline is infused into the peritoneal cavity rapidly in few minutes through the catheter using a drip set with elevation of the fluid bottle/bag. Patient is moved well to mix the fluid in all four quadrants. Now bag is lowered below so that fluid from the peritoneal cavity reenters/siphoned into the bag. Collected fluid is analysed for red cells, leukocytes, etc. (see box). DPL may not be useful in bowel injury, retroperitoneal injury, diaphragmatic injury, organ haematoma (subcapsular splenic haematoma). If patient is decided for observation catheter can be left in situ for repeat DPL after 6 hours. One has to remember that DPL is not a substitute for clinical assessment and monitoring. In *Lazarus–Nelson approach* Teflon catheter with a guidewire is used **(Fig. 8-18)**.

Diagnostic Peritoneal Lavage (DPL)

Significant positive lavage –
- 10 ml of gross blood.
- Red cells more than 1, 00,000/cu mm.
- WBC count more than 500/cu mm.
- Amylase more than 175 ml/dl.
- Presence of bacteria, bile, food particles, foreign body.

Indeterminate lavage –
- Red cells between 50,000 to 1, 00,000/cu mm.
- WBC between 100 to 500/cu mm.

Lavage not significant –
- Red cells less than 50,000/cu mm.
- WBC less than 100/cu mm.

Strongly positive means –
- Red return solution in the bag.
- Always needs laparotomy.
- Features mentioned above.

Weakly positive means –
- Pink or just red tinged fluid.
- Laparotomy chances are 10%.
- Observation / repeat investigations/repeat DPL later.
- Retroperitoneal haematoma may be present.

Lavage negative –
- Return fluid is crystal clear.
- No need of laparotomy here. Patient is observed.

False positive
Occurs when bleeding from retroperitoneum into peritoneal cavity occurs. It may lead into negative laparotomy.
Abdominal wall bleeding into the peritoneal cavity can cause false positive result.

Contraindications for DPL –
- When laparotomy is indicated definitely.
- Previous laparotomy history.
- Pregnancy and obesity.

CT scan of abdomen is most commonly used and better investigation for abdominal trauma. It is useful in blunt/penetrating trauma, suspected pancreas, spleen, liver, duodenal, retroperitoneal injuries. Smaller injuries, early haemoperitoneum are better detected. It is non- invasive, highly specific, highly accurate (96%), with low false positive/low false negative, non-invasive. It is very essential investigation when solid organ injuries are treated nonoperatively. Three dimensional helical CT is needed to identify mesenteric or bowel injury and to find out site of injury. It is obviously not necessary to do CT when there is clear indication for immediate laparotomy. In such occasions ultrasound is more than sufficient.

Other investigations are - (1) *Abdominal diagnostic paracentesis* (Drapanas and McDonald): Here 18 G short bevel spinal needle is inserted into the peritoneal cavity after injecting local anesthetic agent into the abdominal wall. With continuous suctioning through syringe needle is passed at various sites. Positive tap means return of minimum of 0.1 ml of nonclotted blood. False positive result occasionally can occur due to needle puncture of abdominal wall vessels. Needle should not be inserted close to previous abdominal scar as bowel may be adherent underneath the scar. Change of direction of needle is done by withdrawing the needle tip outer to peritoneum and again puncturing the peritoneum. Puncture of non-distended bowel will seal without


Normal saline infusion
Subumbilical incision
Urinary catheter
Peritoneal dialysis catheter
Saline infusion
Siphoned return fluid collection
Return fluid (Red/pink/ clear)

Fig. 8-18: Diagnostic peritoneal lavage - incision and technique.

any leakage in 18 G needle. If there is distended bowel peritoneal tap should be avoided **(Fig. 8-19)**. *Bilateral flanks tap/four quadrant tap* is also done with similar result. Rectus sheath haematoma and false negative results are problems **(Fig. 8-20)**. (2) *Diagnostic laparoscopy* is very useful. It can be done under local anaesthesia. Haemoperitoneum and solid organ and diaphragmatic injuries are well assessed. But bowel and retroperitoneal injuries are more likely to be missed. (3) *Arteriography* through Seldinger technique is useful in suspected cases of renal arterial injury (thrombosis/spasm); intimal tears, traumatic aneurysm and aortic occlusion (after seat belt injury) are well diagnosed with arteriography. Often it can be therapeutic also. Pelvic bleed extending into retroperitoneum is not uncommon which can be assessed by arteriography to identify the bleeding vessel. But venous bleed cannot be assessed by this. (4) *Doppler assessment of major vessels* may be beneficial especially for IVC, aorta, iliac vessels, portal system; but with haemoperitoneum visualisation window may be poor and vessels can be better identified by contrast CT scan.

Management Concepts in Abdominal Trauma

Evaluation of extent of the injury; number of organs injured and severity; haematocrit assessment (haemoglobin drop up to 6 gm% is tolerated well with adequate tissue oxygenation. Rapid drop of haemoglobin needs adequate number of blood to be kept ready like 5/10/more); central line with volume replacement; urinary catheterisation; systemic antibiotics administration.

Autotransfusion of blood is very useful in such situation as a life saving procedure. Blood from the cavity is sucked out into a sterile bottle which contains 150 ml of 3.8% sodium citrate dextrose solution. This blood is strained/filtered through gauze and retransfused. If there is colonic and small bowel injuries autotransfusion is not possible in fear of sepsis due to contamination.

Upper midline incision extending down across the left of the umbilicus is the preferred incision. But surgeon should not be hesitant to extend into the thorax or make horizontal T or as needed depending on the internal organ injury **(Fig. 8-21)**.



Fig. 8-19: Abdominal paracentesis.



Fig. 8-20: Four quadrant aspiration of the abdomen.



Fig. 8-21: Lengthy midline incision with extension on the left side of the umbilicus is used.

First priority after opening the abdomen *is immediate control of profuse bleeding using finger or mop* or pressure. Later once field is clean; area is assessed for the extent of the injury without releasing the compressed finger on the bleeding site. A vascular clamp or bulldog clamp is helpful in such situation. Once it is applied over the site of bleeding, compressing finger can be removed. Vascular suturing using 4 zero or 6 zero polypropylene/resection of the tissue; reconstruction of the area; persistent pressure mop in situ with closure of the abdominal wall with an option for second look surgery in 48 hours are different options. Individual organs are assessed and graded for injuries and managed accordingly.

During laparotomy entire abdomen should be inspected/ palpated carefully for any additional missing injuries. Lesser sac, retroperitoneum, duodenum, pancreas and diaphragm should be checked for. Often peritoneum on the margin of the duodenum and right side colon is incised to and duodenum and colon are reflected medially to visualise the retroperitoneum. Pelvic structures need special attention. Rectum and urinary bladder injuries may be missed. If on catheterisation, urine is clear it means usually urinary system is normal. Portal venous system should be assessed.

Resection or repair should be decided afterwards once haemostasis is maintained. Whether injury to bowel or organs (liver/spleen/kidney, etc.) resection or repair approach is decided depends on the individual organ injury (based on scale or grade) severity.

Mesenteric tear may be the cause for haemoperitoneum. Tear may be perpendicular or parallel to the bowel. If it is perpendicular, haemostasis and approximation of the mesentery is sufficient; if it is parallel tear, then blood supply to corresponding bowel may be compromised and resection of that part is indicated. When mesenteric haematoma is small and non-progressive, it is left alone. Colour changes if any in the adjacent bowel should be observed. If haematoma is large and is progressive causing compromised blood supply of the adjacent bowel, then it should be gently evacuated. Mesenteric leaf is opened using curved scissor; using gentle finger dissection clot is evacuated; bleeder is identified and ligated. If there is compromised bowel function, it should be resected. Bleeding from the major vein like superior mesenteric vein is disastrous as tear may not be localised but may be extensive; even during gentle dissection and may cause more tear. It is carefully mobilised; vascular clamps are applied and repaired using 5 zero polypropylene sutures **(Figs 8-22 to 8-24)**.


Longitudinal mesenteric tear is perpendicular to the bowel wall
Transverse mesenteric tear is parallel to (in line to) bowel wall
Haemostasis and apposition of mesentery is done
Blood supply to the bowel wall may be compromised - needs resection of the bowel part and anastomosis

Fig. 8-22: Transverse mesenteric tear is risky as it may compromise the blood supply of adjacent bowel. In such tear adjacent bowel should be resected.


Mesenteric haematoma - large

Fig 8-23: Large mesenteric haematoma which is progressive needs to be intervened. Gentle evacuation by finger dissection and ligation of bleeding vessel is the option.


Mesenteric vein tear
Gentle evacuation of haematoma with suturing of the vein using 5 zero polypropylene suture

Fig. 8-24: Major mesenteric vein tear should be sutured using 5 zero polypropylene. Vascular clamps should be used to control bleeding. Gentle approach is needed as tear may extend and get worsened.

Aortic Clamping

Catastrophic bleeding found after opening the abdomen which cannot be controlled and bleeding with profound hypotension are the indications for aortic clamping. Profuse intraperitoneal bleed comes under control temporarily by tamponade effect of tense abdominal wall and it itself temporarily helps to the patient. The moment abdomen is opened tamponade is released causing further rapid bleed leading into critical catastrophe. If such event is expected prior to opening the abdomen a very quick rapid thoracotomy (*prelaparotomy thoracotomy*) through left 5th intercostal space is done; left lung is deflated and displaced; pleura over the thoracic aorta is incised; aorta is dissected using finger; vascular clamp or soft intestinal occlusion clamp is applied to occlude the thoracic aorta. Later laparotomy is performed to go ahead with management of the bleeding. If profound bleeding is observed after laparotomy necessitating the aortic clamping, it is done by applying the clamp in infradiaphragmatic part of the aorta. Peritoneum is incised on the right of the abdominal oesophagus in infradiaphragmatic area; aorta is dissected using finger high up close to diaphragm to avoid injury to celiac plexus; clamp is applied across (infradiaphragmatic aortic occlusion) **(Figs 8-25A and B)**.

Usually drainage using tube drains on either side of the abdomen is used even though it is controversial. ICT should be placed if thoracotomy is also undertaken.

Jejunostomy for enteral nutrition is ideal in all major abdominal injuries. Often gastrostomy is also done along with jejunostomy in case of duodenal and pancreatic injuries.

LIVER INJURY

Liver is the commonest organ injured in penetrating abdominal trauma. Mortality is 10%. It is less in isolated liver injury but increases up to 25% when it is associated with other injuries.

Grade and type	*Injury*
I – Haematoma – Laceration	Subcapsular haematoma less than 10% surface area. Capsular laceration less than 1 cm in depth.
II – Haematoma – Laceration	Subcapsular haematoma 10-50%; intraparenchymal less than 10 cm diameter. Capsular laceration 1-3 cm in depth; less than 10 cm length.
III – Haematoma – Laceration	Subcapsular haematoma more than 50%; intraparenchymal more than 10 cm diameter - expanding. Capsular laceration 3 cm in depth.
IV – Laceration	Parenchymal disruption 25-75% hepatic lobe; 1-3 Couinaud segments.
V – Laceration – Vascular	Parenchymal disruption more than 75% or more than 3 Couinaud segments. Major hepatic veins or retrohepatic venacaval injuries.
VI – Vascular	Hepatic avulsion.

Management

Initial Conservative Nonoperative Management

It is done in non-progressive liver injuries who are haemodynamically stable, low grade liver injury, need for transfusion less than 2 units. However, CT abdomen (absence of contrast extravasation during arterial phase can be treated nonoperatively) and repeat CT or regular ultrasound follow up is a must. Replacement of lost blood; prevention of sepsis; regular monitoring by haematocrit, liver function tests, prothrombin time are needed. *Angiographic embolisation* increases the success rate of nonoperative therapy. Initial critical care (ICU) management for 2-5 days; repeat CT scan after 5 days; bed rest to be continued; patient can have normal activity only after 3 months. When any time patient's condition worsens, he should be taken up for laparotomy.

Surgical Management

If bleeding continues, if patient deteriorates, if major hepatic injury with vascular lacerations, surgical intervention is done. Lengthy midline incision is better if other parts of the abdomen like bowel are


Prelaparotomy thoracotomy
Aorta
Clamp
A
Infradiaphragmatic aortic occlusion
Aorta
B

- Done in anticipation
- Through left 5th intercostal space
- Done rapidly just prior to laparotomy
- Better control of bleeding

- Decided after opening the abdomen
- Done above the coeliac plexus level
- Done through laparotomy

Figs 8-25A and B: Aortic clamping is done when there is dangerous bleeding. Prelaparotomy thoracotomy is done just before laparotomy in anticipation through left sided 5th intercostal space. Aorta is clamped in the thorax. Abdomen is opened later. Infradiaphragmatic aortic clamping is done just above the celiac plexus level; it is decided after laparotomy because of the torrential uncontrollable bleeding. Vascular clamp is placed behind the abdominal oesophagus from right side.

also need intervention. Bilateral subcostal/bucket handle or often thoracoabdominal incision is also needed **(Fig. 8-26)**.


Bucket handle (bilateral subcostal) incision with upward extension
Thoracoabdominal incision
Upper midline incision

Fig. 8-26: Incisions used for different liver injuries. Wide exposure is the basic need in these patients.

Small lacerations are apposed using simple sutures with haemostatic agents. Polyglactic or PDS is used with a gel foam or surgicel support. *Kous Netzof aluminium needle* is used for these *co-opting sutures*. Initially mattress sutures parallel to the tear is placed. Row of perpendicular sutures to the tear to co-opt these mattress sutures are placed. Large lacerations need deep suturing. It is not necessary or often risky to try to bring the margins together **(Fig. 8-27)**.


Parallel mattress sutures on either side
Coopting sutures perpendicular to laceration
Liver injury

Fig. 8-27: Coopting sutures are placed perpendicular to already placed parallel mattress sutures.

Packing is a good old method of controlling bleeding in critical patients. It can be done quickly, controls bleeding well by *tamponade*. Reexploration is done in 48-72 hours. Pack is removed. Necrotic tissue is removed. Proper saline irrigation is done. Haemostasis is achieved using bipolar cautery, argon beam ligaseal, harmonic, etc. Risk of abscess formation in packing is 15%.

In *deeper lacerations*, ligation of bleeding vessel individually on the cut surface is needed and is called as *tractotomy*. Biliary ductules are also ligated. As vessels are supported by *fibrous adventitia* suture ligation holds well in these vessels even though liver parenchyma is soft and friable.

Pringle manoeuvre is occluding the porta at foramen Winslow to control bleeding temporarily. It is done using fingers and thumb or vascular clamps or vascular loops. During Pringle, if bleeding gets controlled means it is bleeding from portal vein or hepatic artery branches, and if bleeding continues it is due to hepatic vein or retrohepatic IVC injury. It needs bypass (venovenous bypass between femoral vein and superior vena cava) and vascular repair. As access is technically difficult in these patients with retrohepatic caval injury, a wide tube placed across from atrial appendages to IVC just above the renal vein level may be appropriate (*intracaval catheter placement*). Pringle manoeuvre can be used continuously maximum only for one hour beyond that hepatic ischaemia may occur. But usually it is wiser to release the occlusion once in 10 minutes to reperfuse the liver and clamping the porta again. Pringle manoeuvre also helps to control bleeding while suturing the liver surface. In surface injury, liver can be wrapped with absorbable mesh (*mesh hepatorrhaphy*) to achieve haemostasis. Segmental resection is done often when needed. Hepatectomy and hepatic artery ligation is *rarely used* nowadays. Such an extensive injury can be treated initially by packing and further therapy is planned at later dates. *Push* (direct compression), *plug* (plugging the deep track injuries using silicone tube or SB tube), *Pringles*' manoeuvre, *pack* (liver wound is directly packed with mop) are basic principles in initial management **(Figs 8-28 to 8-30)**.

Management of liver trauma

- Control of haemorrhage – packing; tractotomy; mesh hepatorrhaphy; debridement of devitalized tissue; segmentectomy, vein repair with venovenous bypass; transfusions.
- Management of metabolic disturbances – prevention of acidosis, DIC, FFP; platelets.
- Monitoring – repeat US; repeat CT; urine output; LFT; Prothrombin time; platelet count; haematocrit.
- Prevention of sepsis – proper debridement; irrigation of liver wound with warm normal saline; antibiotics.
- Identification and management of complications of liver injury

Porta Hepatic Injury

It is life threatening even though rare. Penetrating injuries commonly cause this injury. It is commonly associated with organ injuries. Isolated porta injury is rare. It is difficult to manage with mortality 50-80%. Portal vein is sutured after venovenous bypass. Common bile duct injury involving less than half the circumference can be sutured over a T tube. Injury more than 50% or transection needs choledochojejunostomy.

Complications of Liver Injury

Shock, blood loss, DIC, sepsis, intraabdominal abscess or liver abscess formation, bile leak, biliary peritonitis, biliary fistula, hepatic artery aneurysm, haemobilia, hypoalbuminaemia, electrolyte imbalance, respiratory problems, liver failure, stricture of common bile duct are common complications.


Diaphragm
Mop (radioopaque) placed above the liver tear under diaphragm
Liver
Liver injury
Haemoperitoneum

Fig. 8-28: By placing 3-5 mops between injured liver and diaphragm tamponade effect can be achieved to control bleeding from the liver. After 48-72 hours electively abdomen is reexplored for further intervention. Often bleeding will be controlled by then and further management becomes easier. Sepsis should be taken care of by higher generation antibiotics.


Pericardium
IVC
Intracaval catheter
Liver with multiple injuries
Portal triad clamp
Left renal vein
Right renal vein
Intracaval catheter
IVC

Fig. 8-29: Intracaval catheter placement is the only life saving option in case of hepatic vein or retrohepatic IVC injuries.

SPLENIC INJURY

It is the most commonly affected intraabdominal organ in blunt injury. Any injury towards left side of the chest or abdomen should suspect splenic trauma. Stab injuries also can cause splenic injury. Splenic injury is often associated with fracture lower ribs (30%), haemothorax, liver injury (left lobe), jejunal, pancreatic and left kidney injuries.


Suture fixation
Mesh hepatorrhaphy
Absorbable mesh wrap to right lobe
Absorbable mesh wrap to left lobe
Suture fixation
Falciform ligament
Multiple surface lacerations of the both lobes of liver

Fig. 8-30: Mesh hepatorrhaphy using absorbable mesh wrap around the liver surface. Right and left lobes are separately wrapped with mesh and fixed to falciform ligament.

Left side diaphragmatic injury is also known to occur. Injury is more common and severe in already enlarged spleen like of malaria, tropical splenomegaly, etc. Spontaneous rupture of spleen can occur in malaria. *Larang* was used for killing by the murderers in Far East where malaria is endemic leading to splenomegaly, ruptured spleen more easily **(Fig. 8-31)**.



Fig. 8-31: Splenic laceration on one side. Splenorrhaphy/partial splenectomy is possible here.

Types of Splenic Injury

Splenic subcapsular haematoma – After initial injury patient remains asymptomatic for a short period. But this haematoma may rupture often later after few days- causing torrential haemorrhage. *Clean incised wound on the splenic surface* may be treated by nonoperative methods or by splenorrhaphy. *Splenic lacerations* when occur its extent of involvement and depth is important. If it is less than 50% part of the spleen can be salvaged by partial splenectomy. *Splenic hilar injury* often needs emergency splenectomy **(Figs 8-32 and 8-33)**.



Fig. 8-32: Types of splenic injury – (A) Subcapsular haematoma. (B) Incised tear / wound on the surface. (C) Lacerated wound. (D) Hilar injury.



Figs 8-33A and B



Fig. 8-33C

Figs 8-33A to C: Extensive splenic laceration which needed splenectomy.

Presentations

Common presentations in severe splenic injury are features of shock; left upper abdominal pain and tenderness; referred pain over left shoulder due to irritation of left side diaphragm and left phrenic nerve (Kehr's sign); dullnes over left side abdomen which is not shifting due to presence of clot formation (Ballance's sign); tenderness between left sternomastoid and scalenus medius (Saegesser's tender point); formed haematoma in perisplenic area is initially localised by omentum and bowel and so patient shows delayed presentation of severe haemorrhage once clot dislodges off the omentum (latent period of Bandet).

Splenic organ injury scale

Grade I	Haematoma	Non-expanding subcapsular haematoma <10% surface area.
	Laceration	Non-bleeding capsular laceration with <1 cm depth.
Grade II	Haematoma	Non-expanding subcapsular haematoma 10-50% surface area. Nonexpanding intraparenchymal haematoma < 5 cm.
	Laceration	Capsular tear; 1-3 cm depth parenchymal injury not involving trabecular vessel.
Grade III	Haematoma -	Expanding subcapsular or intraparenchymal haematoma. Bleeding subcapsular haematoma or subcapsular haematoma > 50% area or intraparenchymal haematoma > 5 cm.
	Laceration -	Parenchymal laceration >3 cm depth.
Grade IV	Laceration -	Ruptured intraparenchymal haematoma with active bleed; laceration involving segmental or hilar vessels with > 25% devascularisation.
Grade V		Shattered or avulsed spleen; hilar devascularisation with separation of entire spleen.

Complications

Complications of splenic injury are – haemorrhage and its consequences; disseminated intravascular coagulation; sepsis like subphrenic abscess, pancreatitis; splenic artery pseudoaneurysm; splenic arteriovenous fistula.

Investigations

Ultrasound is the basic investigation to initially identify splenic trauma.

CT scan should be done in all patients to confirm the type of injury. CT with contrast to see blush in arterial phase of the contrast is very significant.

Haematocrit, blood grouping and cross matching samples and often to keep ready needed quantity of blood are basic requisites. Angiogram with possible need for angiographic embolisation is commonly used in some centers as diagnostic as well as a nonoperative method of treatment. Diagnostic peritoneal lavage as discussed earlier is also helpful.

Chest X-ray with plain X-ray abdomen is older method of evaluation with higher chances of missing the splenic injury. However, features in X-ray looked for are – obliteration of splenic outline and left sided psoas shadow; indentation of fundic gas shadow; fracture ribs; elevation of left sided diaphragm; dilated intestinal coils in the left side.

Treatment

Initial Management

Central venous line for perfusion and monitoring; transfusion of blood as needed; antibiotics coverage; urinary catheterisation; nasogastric tube aspiration.

Nonoperative Management

When facilities are available, splenic injury can be managed conservatively by nonoperative method. Clinically close observation, serial haematocrit evaluation, serial CT abdomen/US abdomen at regular intervals to assess the progress or regress of the bleeding spleen has to be done. Initial abdominal CT with intravenous contrast is essential to see contrast extravasation and contrast blush in arterial phase. If in later period bleeding persists it is again repeated. Presence of blush is whether an indication for surgical intervention or not is a controversy. In a set up where all facilities are available for intervention, patient still be managed with nonoperative method. Absolute bed rest, sedation, antibiotic coverage and proper monitoring are needed. It is often supported by angiographic embolisation to improve the splenic salvage rate. But it may cause pain, splenic abscess or infarction. Routine angiographic embolisation is also advocated but whether it is needed is a doubtful entity. 70% of stable splenic injury patients can be treated by nonoperative method. Decreasing haematocrit, hypotension, and persistent paralytic ileus may be an indication for surgical intervention. *Indications for nonoperative treatment* - Only splenic injury - no other associated injuries; Grade I, II and selected grade III injuries. Absolute bed rest for 10 days and avoiding over physical activity for 3 months is mandatory.

Surgical Management

Splenorrhaphy

Especially in a clean incised wound spleen can be salvaged by suturing the wound carefully with placement of gel foam, topical thrombin, absorbable mesh wrap over the wound. PDS or vicryl is used as interrupted horizontal mattress sutures. Fibrin glue and use of argon beam coagulator on the surface is also beneficial. But in class/grade III, IV or V injuries splenorrhaphy is not possible **(Fig. 8-34)**.



Fig. 8-34: Splenorrhaphy is ideal in surface injury and simple injuries.

Advantages of splenorrhaphy

- It avoids OPSI.
- It avoids dead space and so prevents potential space for subphrenic abscess.
- Cellular components of blood are better maintained.

Partial splenectomy (upper/lower)

It can be done by retaining either of the upper or lower polar branches of the splenic artery depending on the location of the injury whether in lower or upper part of the spleen. Hilum is carefully dissected to identify the division of the splenic artery into polar vessels. Isolated artery is individually ligated. Accompanying veins are also ligated. Injury extending across both poles is difficult to manage by partial splenectomy. Surface of the spleen is sutured with PDS or vicryl and cut surface is cauterised or small bleeders are controlled using Ligaseal. Gelfoam/spongistan which are placed over the raw area **(Fig. 8-35)**.



Fig. 8-35: Partial splenectomy can be done if injury is on one pole of the spleen.

Emergency splenectomy

It is done through midline / left subcostal incision. Thoracoabdominal extension of incision may be needed for rapid control of bleeding for injury to a large tropical spleen with severe bleeding. Other associated injuries should be looked for and dealt with (injury to left lobe liver/pancreas/intestine/colon). Abdomen is opened rapidly; splenic hilum is held between thumb and fingers to control bleeding immediately; blood/clots in the peritoneal cavity is sucked out and washed to clear the field; often a soft vascular clamp can be placed across hilum including the tail of the pancreas to free the surgeon's hand. With this splenic hilum will be clearly seen and bloodless hilum is dissected carefully and artery and vein and branches are individually ligated using silk or vicryl (2 zero). Spleen is dissected from the short gastric vessels by ligating it and also from splenorenal and phrenicocolic ligaments. Few surgeons also prefer to use polypropylene but knot holding may be difficult **(Fig. 8-36)**.



Fig. 8-36: Technique of splenectomy.

Mass ligature of the entire splenic hilum, even though is commonly used by many surgeons, is a controversial and not universally accepted; however, if patient is haemodynamically *unstable* due to exsanguination and adequate quantity of blood is not available, quick mass ligature can be done using silk. In such situation abdomen is also closed as single mass closure instead of layer by layer **(Fig. 8.37)**.



Fig. 8-37: Mass ligature of the splenic pedicle is often used in emergency splenectomy in splenic trauma.

Salutary effect

In traumatic rupture of spleen, spleen is cut into pieces of 0.5 cm and placed in omental pockets. This autotransplantation is still experimental and controversial.

Complications of Splenic Injury

Metabolic imbalance, acidosis, shock, renal failure, sepsis, DIC, splenic artery pseudoaneurysm, splenic arteriovenous fistula.

Splenectomy can cause DVT, OPSI, haematemesis, left sided pleural effusion, pancreatitis, pancreatic fistula, subphrenic abscess left sided, left lung atelectasis (commonest), left colonic and rarely gastric injury, severe sepsis.

PANCREATIC INJURY

It is rare entity as pancreas is retroperitoneal and well protected. However, penetrating injury and blunt seat belt injury (due to close proximity to vertebral column) can cause pancreatic trauma. It is commonly associated with other abdominal injuries and so commonly missed also. It is often difficult to diagnose the pancreatic trauma clinically, sonologically or CT scan wise. DPL is also not much beneficial. High degree of suspicion is needed. Isolated pancreatic injuries are rare. It is usually associated with duodenal injury. Superior mesenteric vessel injury is common association. Repeat CT, persistent elevation of serum amylase (repetitive assessment of serum amylase) is helpful. MRI/MRCP may be beneficial. *Pancreatic duct injury* is the main deciding factor in managing and predicting the outcome. If injury is right of the superior mesenteric vein, it is called as *proximal pancreatic injury*. If it is towards left it is called as *distal pancreatic injury*.

Proximal injury is treated by surgical debridement; suture ligation of bleeding area; drainage of the pancreatic bed. If there is associated duodenal injury, then pancreaticoduodenectomy is also done. Debridement, closure of duodenal wound and pylorus exclusion is also done. Pancreatic fistula (40%), pancreatic abscess, pancreatitis (15%) septicaemia, pancreatic ascites, pancreatic pleural effusion are common complications which can occur in survived patient.

Distal injury is managed by distal pancreatectomy. Role of pancreaticojejunostomy, ERCP stenting is controversial.

Pancreatic injury	
Grade I – Haematoma – Laceration	Minor contusion without duct injury. Superficial laceration without duct injury.
Grade II – Haematoma – Laceration	Major contusion without duct injury or tissue loss.
Grade III Laceration	Distal transection or parenchymal injury with duct injury.
Grade IV Laceration	Proximal transection or parenchymal injury involving the ampulla.
Grade V Laceration	Massive disruption of the parenchymal head.

DUODENAL INJURIES

Duodenal injuries are 5% common; commonly penetrating; commonly associated with other abdominal injuries like liver, pancreas, major vessels, etc. Isolated injury of the duodenum even though is rare, causes difficulty in diagnosing as it does not cause early peritonitis or haemodynamic instability. But late life threatening intraabdominal abscess or peritonitis develops. Raised serum amylase; plain X-ray abdomen showing mild scoliosis, obliteration of psoas shadow, *presence of air in retroperitoneum around kidney*, absence of air in duodenal bulb; gastrograffin study; CT abdomen with oral intravenous contrast; or dilute barium (microbar solution) study are the investigations needed. CT may show extravasation which is an absolute indication for laparotomy. *Extraluminal air in the CT is diagnostic* **(Fig. 8-38)**.



Fig. 8-38: Duodenal injury often associated with pancreatic injury; haematoma in duodenum, and retroperitoneum, around right kidney, mesentery.

Duodenal haematoma causes radiologically coiled spring or stacked coin sign; but is not a sign to do surgery; only haematoma causing obstruction is operated. It occurs on the convex surface of the duodenum extending into the retroperitoneum. If it is causing obstruction, it can be carefully evacuated without opening the mucosa; gastrostomy and jejunostomy is a must **(Fig. 8-39)**.



Fig. 8-39: Duodenal haematoma. It is treated by gastrostomy; feeding jejunostomy. It is intervened when it causes duodenal obstruction.

Duodenal injury grading	
Grade I – Haematoma – Laceration	Involving single portion of the duodenum. Partial thickness injury without perforation.
Grade II – Haematoma – Laceration	Involving more than one portion. Disruption less than 50% circumference.
Grade III – Laceration	Disruption 50-75% of the circumference of 2nd part of the duodenum; disruption 50-100% of the 1st, 3rd or 4th part of the duodenum.
Grade IV – Laceration	Disruption more than 75% of 2nd part of the duodenum and involving the ampulla or distal common bile duct.
Grade V – Laceration – Vascular	Severe disruption of duodenopancreatic complex. Duodenal devascularisation.

Procedure

When decided for surgery; after laparotomy with a lengthy midline incision, extended Kocherisation is done (peritoneum on the right of the 2nd part is cut and duodenum is mobilised in front and medially in front of the IVC and up to left margin of the aorta completely); hepatic flexure and right part of the transverse colon is mobilized fully; 3rd and 4th parts of the duodenum are visualised properly. Any haematoma or injury or presence of associated pancreatic injuries is looked for. Duodenojejunal junction is mobilised more proximally by dissecting the peritoneal fold to get the proximal length.

Eighty percent of duodenal injuries are *sutured primarily* using polyglactic acid or PDS interrupted sutures horizontally **(Fig. 8-40)**.



Fig. 8-40: Simple duodenal injury is closed using interrupted single/double layer sutures horizontally. Jejunostomy is usually needed.

Single layer suturing is proved to be sufficient. But many advocates two layer suturing. Often many use silk; silk holds the bowel wall well with low rate of leak; but being a nonabsorbable multifilament braided suture it has got tendency to form small granulomas in the anastomotic line even though said to be safer.

Injury on the medial/inner aspect of the duodenum especially in 3rd and 4th parts is sutured transduodenally using continuous single layer PDS sutures. Incision made in the anterior wall is closed horizontally **(Fig. 8-41)**.

In grade I and II injuries - just suturing if opened within 6 hours or if opened after 6 hours suturing with jejunostomy is done. Often tube duodenostomy is preferred by many **(Fig. 8-42)**.


- Duodenotomy;
- Continuous single layer PDS sutures
Injury on the inner/medial part of the duodenum
Closure of duodenotomy using PDS/Polyglactic acid suture

Fig. 8-41: Injury on the medial wall of the duodenum is closed with continuous PDS sutures after doing duodenotomy. Duodenotomy is closed with interrupted vicryl sutures.


Duodenal haematoma
Duodenal injury sutured
T tube duodenostomy
Gastrostomy to empty and aspirate stomach
Feeding jejunostomy

Fig. 8-42: Duodenal injury with T tube duodenostomy; closure of the injury; gastrostomy and feeding jejunostomy.

In grade III injury - Duodenojejunostomy or pyloric exclusion with gastrojejunostomy drainage procedure is done. Serosal patch of the jejunum is useful. Roux en Y duodenojejunostomy with feeding jejunostomy is also beneficial **(Figs 8-43 to 8-45)**.

In grade IV injuries – Duodenal repair; repair of CBD with T tube having lower part of the horizontal limb of T tube into the duodenum across the injury is done. Other option is duodenal repair with or without pyloric exclusion with ligation of the CBD; later during second stage dilated proximal CBD is used for choledochoenteric anastomosis.

Grade V injury needs pancreaticoduodenectomy. It carries high mortality. But one has to remember that if overall duodenal injuries are considered, pancreaticoduodenectomy is rarely needed **(Fig. 8-46)**.


Right vagus
Left vagus
Pyloric exclusion with absorbable sutures 3 zero vicryl or 3 zero PDS
Stomach
G J stoma
Duodenal injury
Duodenum
Colon
Jejunum
Doing just gastrojejunostomy is condemned

Fig. 8-43: Pyloric exclusion with gastrojejunostomy with feeding jejunostomy is one of the options can be used in duodenal injury. Just doing gastrojejunostomy is not advised.


Duodenal injury
Anastomosis
Roux en Y jejunal loop
Jejunojejunostomy

Fig. 8-44: Roux n Y loop duodenojejunostomy on to the site of the injury with a feeding jejunostomy is another alternative.

Small Bowel Injury

Blunt injury abdomen causing small bowel trauma is often difficult to identify at initial phases when patient arrived to the hospital. London's sign (abrasion over the abdominal wall; Monk's localizing zones in the abdomen may be useful features but not clear cut evidence of small bowel injury). Once peritonitis develops patient presents with typical features. Junction of fixed proximal jejunum or terminal ileum is commonly injured due to shearing force. Often it is like a blow out injury causing complete transection of the bowel at the junction **(Fig. 8-47)**.


Injury
Jejunal serosal patch
Jejunal loop
Colon
Tn mesocolon

Fig. 8-45: Jejunal serosal patch over the injury site reduces the risk of duodenal leak. Feeding jejunostomy is also added.


Liver
Stomach
1
2
3
Duodenum
Jejunum
Resected specimen
Pancreas
Haematoma
Duodenal injury
1. Choledochojejunostomy
2. Gastrojejunostomy
3. Pancreaticojejunostomy

Pancreaticoduodenectomy is done only in grade V duodenal disruption and/or severe devascularisation

Fig. 8-46: In extensive injury only pancreaticoduodenectomy is done.

Penetrating injury can often cause not just single perforation **(Fig. 8-48)** but multiple perforations with mesenteric injury **(Fig. 8-49)**.

Plain X-ray abdomen shows gas under diaphragm in blunt injury abdomen. DPL may not be diagnostic. CT may be useful. Best way is to explore if there are features of peritonitis.

Formal laparotomy using midline incision is done. Entire small and large bowel and mesentery and other organs are examined for any injury.

Small single tear in the small bowel is sutured horizontally using polyglactic acid (vicryl) interrupted *single layer* sutures (preferred). In *two layer method* – inner continuous absorbable sutures with outer interrupted seromuscular interrupted mattress sutures can be placed. One should not miss additional tears in other part of the bowel **(Fig. 8-50)**.


Duodenojejunal junction injury
Caecal injury
Ileal injury
Sigmoid injury

Sites of blunt injury in small and large bowel.
Penetrating injury can occur anywhere

Fig. 8-47: Sites of bowel injury in blunt trauma abdomen. Proximal jejunum, terminal ileum, caecum, sigmoid are the common sites.



Fig. 8-48: Transection of the jejunum in blunt injury abdomen due to shearing force/blow out effect.



Fig. 8-49: Small bowel injury causing multiple perforations due to penetrating trauma.


Tear/injury
Single tear in small bowel
Inner layer
Outer layer
Single layer interrupted sutures using vicryl or silk horizontal closure
Two layer closure - Inner continuous absorbable full thickness seromucosal; Outer interrupted silk - seromuscular

Fig. 8-50: Single small tear in the small intestine is closed horizontally using silk/vicryl either as single layer interrupted sutures or two layer closure with inner continuous suture and outer interrupted sutures.

When there are *multiple perforations (10%)* located very closely in the bowel loop; shattered injury in one segment; adjacent mesenteric injury which may probably compromise the blood supply of the bowel are the indications for *resection* and anastomosis. Drainage is used only if there is contamination. It is a controversial topic. Literature opines that drainage is not needed in routine cases; but most surgeons prefer to place a tube/corrugated drain **(Fig. 8-51)**.

LARGE BOWEL INJURY

Penetrating injury of colon is common. It causes faecal peritonitis. It needs essentially colostomy/ileostomy depending on the site of injury. Small tear can be closed primarily using silk/vicryl horizontal interrupted mattress sutures. Primary repair is done only if early diagnosis is done in 6 hours of injury; without any hypotension; without gross contamination of the peritoneal cavity; without colonic vascular injury.

Low risk colonic injuries are one without much contamination of peritoneal cavity and without vascular injury. It is treated by primary closure or resection and primary anastomosis. Stapled or hand anastomosis has equal results in colonic trauma.

Plain X-ray abdomen, presence of blood during digital examination is typical and one can suspect colonic injury.

Blunt trauma of colon is rare. Caecum and sigmoid colon are commonly affected. Pericaecal haematoma can cause late bowel wall ischaemia → necrosis → perforation → peritonitis. In critically ill patient due to trauma, initially there is only serosal injury without mucosa, but due to persistent hypotension and hypoperfusion late ischaemic necrosis and perforation can occur. It is common in sigmoid colon.


Tears/injuries
Multiple tears in small bowel/extensive injury
Occlusion clamps on either sides
Crushing clamps
Injury
Resection of the part is ideal
Anastomosis- single or two layers
Sutures in mesentery

Fig. 8-51: When extensive/multiple tears at close proximity, resection of the involved bowel segment and anastomosis is done. But one should remember that massive small bowel resection may cause short gut syndrome due to less than required (120 cm) length of the small bowel is retained.

Exteriorization either ileostomy or colostomy should be always kept in mind by the surgeon whenever needed. If extensive injury is found right or left hemicolectomy is the need. Splenic or hepatic flexure is commonly used for colostomy as a loop. Ileostomy is done usually as end type **(Figs 8-52 to 8.54)**.


Colostomy site
Sigmoid injury
Primary closure/resection with primary anastomosis but ALWAYS with a diversion colostomy at splenic flexure level is done

Fig. 8-52: Injury to sigmoid colon needs diversion colostomy at splenic flexure or proximal level. Tear in the sigmoid colon is sutured using interrupted silk/vicryl. Often sigmoid resection and anastomosis is done if injury is extensive.


Site of colostomy
- Hepatic flexure
Site of injury in colon
Primary closure or resection with primary anastomosis but ALWAYS with diversion colostomy at hepatic flexure level is ideal

Fig. 8-53: If injury is in the splenic flexure level then colostomy is done at hepatic flexure level.

Maintenance of nutrition, TPN, antibiotics, fluid and electrolyte management are the other main required management for good outcome. Transfusion of blood may be required.

Rectal injury when it is high needs colostomy for 6 weeks. If it is low rectal injury, primary repair can be done perineally after thorough wound debridement and wash using warm normal saline.

Closure of the exteriorisation is done once sepsis is under control; patient recovers well.

Complications after surgery are – anastomotic leak; pelvic / intrapeitoneal abscess, sepsis, wound dehiscence, mortality.

RECTAL INJURIES

Rectal injuries are commonly penetrating type. It is often associated with pelvic injuries, urinary system injuries. It is difficult to manage. Blood on rectal examination is diagnostic. Injury should be assessed under general anaesthesia. Prior to that associated injuries and ultrasound abdomen for haemoperitoneum should be checked. Haematuria when present suspects associated bladder injury. Proctosigmoidoscopy should be done for proper assessment of rectal injuries.

Rectal injury can be *extraperitoneal or intraperitoneal.*

Treatment

Treatment is diversion colostomy, proper saline wash (very important), primary closure of the accessible rectal injury either perineally or through laparotomy. Unless rectal injury is small and low, diversion colostomy is a must. Presacral drainage after through wash of this space is a must. Otherwise retrorectal abscess may develop which is rather difficult to manage. Colostomy closure is done only after sepsis settles down and one must confirm that rectal or urinary fistulas will not develop **(Fig. 8-55)**.


End ileostomy
Caecal/ascending colon injury
Primary suturing with end ileostomy
Small caecal linear tear can be sutured primarily around a tube caecostomy - done only if there is no contamination
Colonic mucus fistula
End ileostomy
Resected part
Caecal/ascending colon injury
Resection; end ileostomy; and colonic mucus fistula is also done
End ileostomy
Resected part
Caecal/ascending colon injury
Resection and closure of the colonic end with end ileostomy
Resection of ileocaecal segment with colonic mucus fistula with end ileostomy or resection and closure of colonic end with end ileostomy is done. Later continuity is maintained in 12 weeks

Fig. 8-54: Injury at caecal level needs ileostomy. Ileocaecal resection with end ileostomy with colonic mucus fistula or after resection colonic end is closed with end ileostomy. Ileostomy is closed in 3 months. If injury is not extensive tear can be sutured primarily with an end ileostomy. If linear small tear is present in the caecum without peritoneal contamination then closure of the caecal tear around a tube caecostomy can be done. All decisions are taken on table during surgery on individual case basis.


Sites of colostomy (One of the sites selected)
B
Urinary catheter
A
Peritoneum
Sacrum
Presacral drain
Sites of rectal injuries-
(A) Extraperitoneal
(B) Intraperitoneal
Primary closure with thorough saline wash, with diversion colostomy (must), with presacral tube drain

Fig. 8-55: Rectal injury can be intraperitoneal or extraperitoneal. Diversion colostomy; thorough saline wash; presacral drainage are the essential steps.

Associated urinary injury should be dealt with the help of urologists. Rectourinary fistula as a late complication is not uncommon.

Complications

Complications are abscess, sepsis, fistula, rectal incontinence, rectal stricture, sexual dysfunction, associated urinary incontinence due to damage to nerves and puborectalis.

RENAL INJURIES

Commonly it is due to a blunt injury. Often it is associated with other abdominal injuries—of liver, spleen, bowel, mesentery, etc. *Per se renal injury is extraperitoneal.*

Types

Small subcapsular; large subcapsular; cortical laceration; laceration with perinephric haematoma; medullary laceration with bleeding into the renal pelvis; corticomedullary complete rupture; hilar injury (most dangerous) **(Fig. 8-56)**.

Eighty five percent of renal injuries are minor. Minor injuries are treated nonoperatively. Major injuries means—deep corticomedullary injury with extravasation and renal pedicle injuries.

Grading of renal injury

1 – Subcapsular non-expanding haematoma without parenchymal laceration.
2 – Cortical laceration < 1 cm of parenchymal depth, no extravasation; perirenal haematoma.
3 – Cortical laceration > 1 cm depth; no urine extravasation.
4 – Parenchymal laceration extending through cortex and medulla with collecting system; with extravasation of urine.
5 – Renal pedicle avulsion; shattered kidney.



Fig. 8-56: Renal injuries: A: Small subcapsular. B: Large subcapsular. C: Cortical laceration. D: Laceration with perinephric haematoma. E: Medullary laceration with bleeding into the renal pelvis. F: Corticomedullary complete rupture. G: Hilar injury - most dangerous.

Clinical Features

Features of shock; Haematuria – may be mild to profuse depending on the type of injury; clot colic; bruising, swelling and tenderness in the loin; paralytic ileus with abdominal distension occurs due to retroperitoneal haematoma implicating splanchnic nerves.

Investigations

IVU (high dose) - Is the investigation of choice. Function of not only the injured kidney but also of the contralateral kidney can be seen. Often it is observed that opposite renal artery undergoes a reflex spasm, temporarily ceasing of function of the contralateral kidney occurs.

***US abdomen*:** Is done to see the type of injury, amount of haematoma and other associated injuries in the abdomen. US should be repeated at regular intervals to see the progress (at 12-24 hourly). Blood urea and serum creatinine should be repeated again at regular intervals. Acute renal failure is known to occur even in one sided renal injury; it responds well for temporary few haemodialysis until same side or/and opposite side kidney start functioning. Blood grouping and cross matching is needed for blood transfusion.



Fig. 8-57: Injury to the kidney causing near transection requiring emergency nephrectomy.

Treatment

I. Initially always conservative – patient is catheterized and urine colour and output is observed; blood transfusion; strict observation with regular monitoring of the pulse, blood pressure, temperature; sedation, analgesic and antibiotics. 75% of patients respond to conservative management. While treating conservatively, regular monitoring of blood urea and serum creatinine is a must. If the patient goes in for renal failure, haemodialysis should be done for 6-8 weeks. Meanwhile, the other kidney will start functioning again and patient will recover without any further problem.

II. *Indications for surgical intervention* **(Fig. 8.57)**:
  1. When there are signs of progressive blood loss with the condition of the patient deteriorating.
  2. Formation of progressive perinephric haematoma.
  3. When there are associated other injuries.
  4. Hilar injury.

Surgery

Options:

a. Gentle suturing of the laceration. Often as kidney is friable, this is not easier technically. Here initially before opening Gerota's fascia and evacuating the haematoma, *renal vessels should be isolated* and either bulldog clamp or umbilical tape should be placed around. Suturing, wrapping, gelfoam, spongiston are other materials tried **(Fig. 8.58)**.

b. Then nephrostomy (Cabot`s) is done.

c. When the injury is in the poles - partial nephrectomy.

d. In hilar injury and severe laceration nephrectomy is the only choice **(Fig. 8.59)**.



Fig. 8-58: Renal pedicle should be isolated and either using bulldog clamp or vascular clamp or umbilical tape renal artery and vein should be individually clamped. Renal artery clamp is most important.



Fig. 8-59: Tube nephrostomy is better when there is significant renal and perinephric haematoma.

Type	*Treatment*
1. Only bruise/contusion	Conservative
2. Breach in calyceal system/rupture of one of the small branches of renal artery.	Conservative/nephrectomy
3. Rupture of pelvicalyceal system/renal substance.	Nephrectomy

Complications of renal injury

1. Clot retention in the bladder and may go for renal failure.
2. Pararenal pseudohydronephrosis.
3. Infection.
4. Perinephric abscess.
5. Aneurysm of the renal artery.
6. Renal failure.
7. Post injury renal hypertension.

ABDOMINAL COMPARTMENT SYNDROME

It is increased intraabdominal pressure more than 12 mm Hg. It is common in multiple traumas. Ileus and bowel oedema are the factors causing it. It is also seen in retroperitoneal haemorrhage, pancreatitis, long standing hernia after reduction into the peritoneal cavity. Upward displacement of the diaphragm, hypoxia, hypercapnia, acidosis, compression of IVC, decreased venous return to heart, increase in peripheral resistance, decrease in cardiac output and right atrial pressure, decreased renal blood flow and glomerular filtration, mesenteric venous hypertension, bowel wall oedema and ischaemia – are the effects. Oliguria, respiratory failure, cardiac arrest ensures if abdomen is not decompressed.

Intraabdominal pressure is measured using a *urinary catheter in the urinary bladder*. Pressure is graded *(Busch)* as I – 10-15 cm of H_2O; II – 16-25 cm of H_2O; III – 26–35 cm H_2O; IV – more than 36 cm H_2O.

Beyond grade III immediate decompression is needed. Initial volume preload is essential otherwise sudden decompression may cause cardiac arrest in asystole.

URETHRAL INJURY

It can be in membranous or bulbar urethra. It can be complete/incomplete; total/partial.

Rupture of Membranous Urethra (Posterior Urethra)

It is usually associated with pelvic fractures. Instrumentation, catheterisation, stone, obstetric causes are other etiologies. In complete rupture urethra puboprostatic ligament may be disrupted causing *floating prostate – Vermooten's sign*. *Maccullum – Colapinto classification* is based on ascending urethrogram findings – Type I: Elongation of posterior urethra but intact; Type II: Floating prostate; Type III: Total disruption of the urethra with extravasation urine above and below the sphincter.

Features

Difficulty and failure in passing urine; blood in external meatus; urinary extravasation into perineum/scrotum/abdominal wall are typical features. Digital examination of rectum reveals impalpable prostate—floating. X ray pelvis shows fracture. Urethrogram is diagnostic.

In Floating Prostate

As rupture is complete, bladder is opened from above. A metal bougie is passed from above through the bladder and one more metal bougie is passed from below through urethra and both are manipulated so as to meet each other. Lower bougie is negotiated along the upper one and so into the bladder. Red rubber catheter is tied to the tip of the lower (urethral) bougie which has already entered into the bladder. When lower bougie is pulled out per urethrally, catheter tied to it will pass through urethra from above, to which Foley`s catheter is tied and pulled up, so as to keep it in position. Bladder is closed with a SPC using Malecot's catheter **– *Railroad technique.***

In Incomplete Rupture

Two approaches:

First approach proposed by Mitchell: *Do not pass catheter from below* as it may further damage the urethra and also may damage sphincter mechanism and so may cause incontinence later. Here SPC is done using Malecot`s catheter. After three to six weeks, a urethrogram is done. Using endoscopy or along with open method Foley`s catheter is passed, often after dilatation.

Second approach advocated by Blandy: *Single attempt to pass a small soft catheter per urethrally* gently may lead into the bladder, which will be kept in situ, to maintain the continuity. If this fails SPC is done. On second day, in operation theatre, bladder is opened from above and flexible cystoscope is passed from below and using this, catheter is passed from below. Bladder is closed with a SPC. If patient with incomplete rupture presents later, then manage it once a stricture forms, accordingly as stricture urethra, after 3 months. Until then patient may require SPC. Other measures: Antibiotics, blood, fluid replacement, treat other injuries.

Complications

Urinary incontinence; impotence; stricture urethra; infection.

Rupture of Bulbous Urethra (Anterior Urethra)

Usually due to a fall astride a projecting object, like in sailing ships, cycling, over loose manhole cover, gymnasium.

Clinical Features: Triad

(1) Blood in external meatus (Urethral haemorrhage). (2) Perineal haematoma. (3) Retention of urine. X-ray pelvis and US abdomen are investigations. Condition is diagnosed clinically **(Figs 8-60 and 8-61)**.

Treatment

Patient should be told not to try to pass urine, if passed, then extravasation of urine occurs. In operation theatre, *one attempt of urethral catheterisation is tried gently*. If able to pass a catheter, then it is left in place. Often perineal haematoma which occurs has to be drained. Antibiotics should be given to prevent sepsis. *If catheter fails to pass*, then under general anaesthesia, in lithotomy position, SPC is done. Bulbous urethra is exposed through perineal midline incision and tear is sutured with an indwelling Foley`s catheter. Drain is then placed into the perineum. If suturing is not possible (sometimes), then *perineal urethrostomy* is done and at later stages continuity is maintained (usually after 3 months).

Complications

Infection, extravasation of urine, stricture urethra.



Fig. 8-60: Urethral injury showing blood in the external meatus with extravasation.



Fig. 8-61: Penetrating injury in the perineum causing rectal and urethral injury which is communicating. Note the catheter passed per urethral has gone into the rectum and come out into the anal canal. It needed colostomy and suprapubic cystostomy diversions (*Courtesy:* Dr Ashfaque Mohammad DNB, KMC, Mangalore).

RUPTURE BLADDER

Causes

Blow, kick or fall; road traffic accidents; stabs, gunshot injuries; endoscopic trauma; instrumentations. **Bladder injury can also occur** during hysterectomy both abdominal and vaginal, surgery of colon or rectum, repair of direct inguinal or femoral hernias.

Types

I: *Intraperitoneal rupture*—20% common. It occurs in fully distended bladder due to blow, kick, or fall.

II: *Extraperitoneal rupture*: 80% common. It is due to road traffic accidents, golf playing, fall over the manhole. Its features and management are same as rupture of posterior (membranous) urethra **(Figs 8-62 to 8-63)**.



Fig. 8-62: Bladder rupture: (A) Intraperitoneal rupture. (B) Extraperitoneal rupture.

Intraperitoneal Rupture

It is 20% common. *It occurs in full bladder.*

Features: Sudden pain in suprapubic region; shock and syncope; diffuse abdominal pain; urine leaks into the abdominal cavity causing distension of abdomen; later it causes features of peritonitis, with guarding, rigidity, tenderness and rebound tenderness, dull flank. *Patient does not have the desire to micturate.*

Investigations: (1) Plain X-ray shows ground glass appearance. (2) Peritoneal tap to collect urine. (3) After passing a small catheter gently per urethra, water soluble iodine dye is passed to visualise the tear in the bladder and entry of the dye into the free peritoneal cavity. This can be done now through C-arm image intensifier easily. (4) US abdomen to look for other injuries in the abdomen.



Fig. 8-63: Extraperitoneal bladder rupture with extravasation of the urine.

Treatment: Emergency laparotomy is required. Bladder tear is sutured using polyglactic acid (vicryl) in two layers. Peritoneal wash is given. Malecot`s catheter is placed from above as SPC. Prevesical space and peritoneal cavity are drained separately. Foley's catheter from below is also passed. Adequate specific antibiotics are given to prevent sepsis.

Surgery is the only treatment for intraperitoneal rupture of the bladder. Without surgery mortality is 100%.

Complications of rupture bladder: Cystitis/and pyelonephritis; peritonitis; pelvic abscess; fistula formation (vesicovaginal or recto-vesical); paralytic ileus; haemorrhage.

Extraperitoneal Rupture of the Bladder

It is 80% common. It occurs in road traffic accidents, in a non-distended bladder.

Features: There is collection of urine and blood in the extraperitoneal space in front, with fullness, diffuse pain and tenderness in lower abdomen; swelling in the scrotum or labia and abdominal wall; strangury and inability to pass urine; often blood in the external meatus is noted. Features of shock and of other associated injuries may be noted.

Investigations: Plain X-ray pelvis shows fracture pelvis. Cystogram shows leak from the bladder. **During cystoscopy**, (1) Bladder cannot be distended; (2) Endoscopy light may be shining through the abdominal wall; (3) Irrigating fluid cannot be retrieved back.

Treatment: The bladder is exposed extraperitoneally, the tear is identified and sutured and the extraperitoneal space is irrigated with saline. Bladder is closed with a SPC using Malecot's catheter and a drain is placed in prevesical space (cave of Retzius). If there is urethral injury it should be treated accordingly.

SEAT BELT INJURIES

In an individual with tied seat belt, during impact *violent deceleration* of human body occurs. Seatbelt impinges heavily on its point of contact with trunk and viscera continue to move forward. It leads into severe contusion of abdominal contents; *detachment of bowel from its mesentery* due to free forward rapid mobility of the bowel over a relatively fixed mesentery. Solid organ injury occurs only occasionally.

Two point anchorages causes solid organ injuries like of liver/spleen. *Lap belt* causes contusion and bowel injury commonly.

It is often difficult to identify the injuries due to presence of more obvious other injuries. CT chest and abdomen diagnostic peritoneal lavage (DPL) are very useful.

Petechiae around iliac crest or costal margin are signs wherein one can suspect seat belt injuries.

Distraction fracture of lumbar spine (*chance fracture*) with hyperesthesia of T12 and L1 level is often associated. 10% of such fractures are associated with intraabdominal injuries.

Treatment is immediate laparotomy and proceed – bowel suturing/resection/suturing of the organ injuries/splenorrhaphy/splenectomy.

Chapter 9

Principles of Surgical Treatment in Infections

Infections in different parts of the body are dealt in different ways. Infections may be in limbs, in body cavities or extending from outside to inside or multiple site infections.

It can be surface infections in skin and subcutaneous tissue. It can be deeper infection in the muscle, bone, joint and fascial planes. It can be infection in cavities like in peritoneum, pleura and cranial cavities.

PRINCIPLES

Once there is abscess, it should be drained. Abscess should be formed before drainage in most of the places except in breast, parotid, ischiorectal fossa, hand, and thigh. Pointing pus, excruciating pain, fluctuation, induration are the features of formed abscess. Pus is drained under general or regional anaesthesia. Digital block, brachial plexus block, Bier's block, wrist block, ankle block, sciatic blocks can be used. Local infiltration at the site even though is commonly practiced is unsatisfactory as it may not act due to acidic pus media and due to oedema at the site. Hilton's method of drainage is used to drain an abscess **(Figs 9-1 and 9-2)**.

Digital block is given using xylocaine 1–2% *without adrenaline* (plain) 1-2 ml on each prick site. By diluting with equal quantity of normal saline 0.5% strength can be made. 3 mg/kg is the dose.

Tourniquet should be used in limbs while draining or doing fasciotomy. Pneumatic tourniquet is used. Limb is elevated for 2 minutes for venous emptying prior to applying the tourniquet. Tourniquet inflated to a pressure 30 mm Hg more than systolic pressure of the patient. Tourniquet time for upper limb is 60 minutes; for lower limb it is 90-120 minutes.

Principles

- Always pus should be aspirated for confirmation.
- Adequate incision is the priority. One should not compromise the incision.
- Expose all layers in deeper abscess like psoas abscess, groin abscess, loin abscess.
- Drain should be placed – wick/tube/corrugated depending on need.
- All loculi should be broken. All communications should be drained.
- Proper saline (warm) irrigation to the cavity is essential.
- Pus should be sent for culture.
- In superficial/surface abscess wound is left open. In deep abscess like psoas abscess wound is closed in layers or single layer with a drain.
- Antibiotics should be started prior to drainage.
- General/regional anaesthesia is used.
- Deeper abscess can be confirmed by CT scan or ultrasound. Repeat ultrasound/CT scan for completion of drainage may be needed.

Hand Infection

Hand should be properly examined clinically for tendon functions; neurological problems – sensations (sweat test, two point discrimination test); for circulation (Allen's test); joint movements; examination of entire upper limb; opposite hand; axillary lymph nodes and relevant systemic examinations.

The principles of treatment are elevation to reduce oedema; splintage to prevent contracture; rest during initial stage of diffuse infection; early movements once inflammation subsides; early exploration of wound or surgical drainage of infective area; regional anaesthesia; usage of tourniquet; incisions when cross the flexor creases, it should be at 45° angle.

Rest is achieved by *plaster of Paris* applied on the ventral aspect of the hand. Elevation is achieved by suspending the arm from an overhead support. Flucloxacillin 500 mg 6th hourly, metronidazole 400 mg 8th hourly orally is given initially until pus culture sensitivity report is available.

During surgical drainage *site of incision should be marked* properly prior to anaesthesia. Length of the incision should be adequate. Superficial part of the deep abscess should be drained initially (collar stud part); and then deeper part is reached and drained properly. Pus should be collected for culture and sensitivity. Skin edge is trimmed using a fine scissor to create a *diamond shaped opening*. Thorough saline irrigation is done. Dressing is placed. Tourniquet is released. Arm is elevated. Dressing is opened and wound is inspected after 24 hours. Further dressings are done once in 1-2 days, depending on need. Continuation of antibiotics for longer period is done only if abscess is large; signs of bone or spreading infection **(Figs 9-3 to 9-6)**.

Apical Subungual Infection

It is infection of the space between subungual epithelium and the periosteum. It occurs after minor trauma or rarely after formation of subungual haematoma. Beneath the free edge of the nail, pus comes to the surface. Excruciating tenderness with small visible pus under the tip (summit) of the nail is the feature. Drainage with transverse incision at the tip of finger with removal of V shaped of wedge of nail over the summit is the treatment along with antibiotics. Osteomyelitis is *not common* here **(Fig. 9-7)**.



Fig. 9-1: Abscess is drained by Hilton's method of drainage. Abscess should be aspirated prior to making incision. Longitudinal adequate length incision is made over the skin. Pyogenic membrane is opened using sinus forceps. All loculi are broken using little finger or sinus forceps. Warm saline wash is given. Cavity is packed with gauze or drain. Pus should be sent for culture and sensitivity.

Paronychia

It is infection of nail fold. It can be acute or chronic. Acute is usually bacterial. Chronic is commonly fungal. Acute is usually due to Staphylococcus or Streptococcus. It occurs under the eponychium. Pus spreads under the nail causing hang nail or floating nail. Condition is precipitated by minor trauma. Excruciating throbbing pain and tenderness under nail root are the features. Digital block anaesthesia is used. Using fine scissors lateral nail fold is elevated; loose skin portion is removed; pus extrudes out; portion of this base of nail should be removed in floating nail as it is usually dead. Keeping drain or gauze wick is not needed. Pus is sent for culture. Dressing is done. In chronic paronychia entire nail may required to be removed **(Fig. 9-8)**.

Pulp Space Infection (Felon)

Terminal pulp space infection is common. Throbbing pain is common; but pointing pus may not be clear initially. It is initially treated by rest, elevation and antibiotics. Once pus points or maximum tender point is determined, drainage is done. But undue delay in draining should be avoided as osteomyelitis of terminal phalanx can occur due to blockage of the end artery of the terminal phalanx by infective thrombosis. Oblique deep incision directly over the pulp is needed. Superficial collar stud part is opened; then deeper part is opened adequately **(Fig. 9-9)**.

Web Space Infection

It is initially treated with splinting, elevation and antibiotics. It is drained under general or regional anaesthesia. A transverse incision is placed on the palmar aspect opposite the interdigital space and 1 cm proximal to the free edge of the web. Only skin is incised using no 11 blade. Deepening of the wound is done using sinus forceps by blunt dissection. It is important to go deeper to palmar aponeurosis otherwise drainage is incomplete. Dorsal counter incision is not needed. Vertical incision in the web should not be placed as it will cause bad contracture **(Figs 9-10 and 9-11)**.

Deep Palmar Space Infection

Midpalmar Space Infection

Midpalmar space (triangular shape) is bound by palmar aponeurosis in front; medial three metacarpals behind; a vertical line from lateral margin of middle finger (intermediate palmar septum) laterally; medial palmar septum medially **(Figs 9-12 to 9-14)**.

Proximally it begins from flexor retinaculum; distally it extends into distal palmar crease along 3rd and 4th lumbrical canals. It is on the inner half of the hollow of palm. It contains flexor tendons, lumbricals and neurovascular bundles. Posteriorly it is bounded by 3rd, 4th, 5th metacarpals and fascia covering interossei muscles of


Abscess back
Aspiration of pus prior to drainage
Incision through No 11 blade
Making incision - adequate length
Draining pus by sinus forceps - collecting pus for culture
Draining through sinus forceps
Breaking all loculi using little finger
Washing abscess cavity using saline or povidone
Pack the abscess cavity or keep a drain

Figs 9-2: Drainage of an abscess in the back.



Fig. 9-3: Finger infection causing oedema, discharge. It can lead into stiffness, osteomyelitis, and gangrene of the digit due to infective thrombosis of the digital artery.

3rd and 4th intermetacarpal spaces. Pain and tenderness in the palm; obliteration of the concavity of the palm; oedema of dorsum of hand (frog hand) due to lax skin and plenty of lymphatics; painful movements of metacarpophalangeal joint are the features. *Complications* like osteomyelitis of metacarpals, stiffness of hand, suppurative arthritis are common.

It is *drained* under regional/general anaesthesia by placing horizontal/oblique incision parallel to the palmar crease. One should avoid as much as possible to cross the crease line. Palmar aponeurosis is vertically incised carefully to avoid injury of the neurovascular bundles. Alternatively one of the *interdigital web spaces* is incised horizontally*; lumbrical canal* (3rd or 4th) is opened to reach the deep palmar space. Pus is drained. Thorough saline irrigation is a must.

Thenar Space Infection

Thenar space (triangular shape) is located anterior to the lateral two metacarpals. It is on the outer half of the hollow of the palm. Proximally it extends from flexor retinaculum; distally it extends to transverse palmar crease. It communicates to fascial sheath of 1st lumbrical. It is often associated with midpalmar space infection. It is drained similarly by placing incision on the lateral aspect of the palm or through the first web space incision along the *first lumbrical canal* on the radial side of the index finger **(Fig. 9-15)**.

Space of Parona Infection

Forearm space of Parona is a rectangular space situated in the lower part of the forearm above the wrist, in front of pronator quadratus, deep to long flexor tendons. Above it extends upto oblique origin of flexor digitorum superficialis, below upto flexor retinaculum communicating with midpalmar space. Flexor tendon sheath extends proximally into this space. Pus in this space is drained through lateral incisions in the lower part of the forearm.



Figs 9-4A to C: Different types of hand infections – ulcer, abscess, ulcers.


Position of rest
Position of function
Position of immobilisation
Position of function

Fig. 9-5: Position of rest, function and immobilisation. Position of rest and immobilisation are same.



Figs 9-6A to C: Hand infection showing oedema, swelling and elevation after drainage.


Nail
Subungual abscess
'V' incision

Fig. 9-7: Apical subungual infection and pus formation. Note the `V' shaped incision to drain the same.

Acute Suppurative Tenosynovitis (Tendon Sheath Infections)

Radial bursa is synovial sheath of flexor tendon of thumb which extends into the *digit*. Ulnar bursa is synovial sheaths of the medial four flexor tendons of hand which extends into the digit of the *little finger*. Radial and ulnar bursas communicate with each other in 80% of cases. Extensor tendons are *devoid* of sheaths. It presents with symmetrical swelling of entire finger. *Hook sign* with flexion of finger is typical. Oedema of the



Figs 9-8A to D



Fig. 9-8E

Fig. 9-8: Acute paronychia. Pus even though is in small quantity, it should be drained.



Fig. 9-9: Anatomy of pulp space. Artery supplying the terminal part of the distal phalanx of the finger passes through the septae on the pulp. This artery is an end artery. So infection in the pulp space increases the pressure inside leading to infective thrombosis and blockage of end artery causing osteomyelitis of the terminal phalanx. Terminal pulp space infection should be drained through an oblique pulp incision. Decompression with breaking of septae is important.




Deroofing
abscess surface
Incisions

- No 11 blade only for skin incision
- Deroofing the web
- Use only blunt sinus forceps for deepening

Fig. 9-10: Transverse incision is used to drain web space infection. Deroofing of the incision and web space is done.


Wrong
incisions

- Do not place vertical web incisions

Fig. 9-11: Vertical incision to drain web space infection is *avoided.*


Palmar aponeurosis
Flexor retinaculum

Fig. 9-12: Flexor retinaculum – anatomy.


Flexor pollicis
longus tendon
Thenar muscles
Flexor tendons of
index finger
Thenar space
Dorsal
subcutaneous space
Dorsal
subaponeurotic
space
Septum
Midpalmar space
Palmar aponeurosis
Superficial palmar arch
Digital nerves
Hypothenar muscles
Flexor digitorum
superficialis tendons
Flexor digitorum
profundus tendons
A
First
lumbrical canal
Thenar space
Lumbrical canals–
2nd, 3rd, 4th
Midpalmar space
Flexor retinaculum
Incisions to drain pus
from space of Parona
Space of Parona
B

Figs 9-13A and B


Thenar space
Flexor retina-culum
Space of Parona
Midpalmar space
C
Thenar space
Flexor retina-culum
Space of Parona
Midpalmar space
D

Figs 9-13C and D

Figs 9-13A to D: Anatomy of palmar spaces of the hand and forearm. Midpalmar space is on the medial aspect; thenar space is on the lateral aspect. Space of Parona is on the lower forearm.


Web space incision—through lumbrical canal
Incisions
- Skin incision parallel to crease line
- Never cross the crease line
- Palmar aponeurosis is opened vertically
- Space can be approached through lumbrical canal through horizontal web space incision

Fig. 9-14: Incisions to drain midpalmar space infection.


Incision through first web space – radial side of index finger – through first lumbrical
Incision

Fig. 9-15: Incision and drainage of thenar space abscess.

dorsum of the hand, tenderness extending into the little finger in infection of ulnar bursa; extending into the thumb in infection of radial bursa; swelling extending proximal to flexor retinaculum; positive Kanavel signs are obvious. *Kanavel signs* – swollen finger held in flexion; exquisite pain on passive extension; tenderness over tendon sheath; greatest point of tenderness is between two transverse creases. *Complications* are proximal spread to forearm; hand and finger stiffness; suppurative arthritis; osteomyelitis; median nerve palsy; septicaemia **(Fig. 9-16)**.


Radial bursa
Ulnar bursa

Fig. 9-16: Radial and ulnar bursae in hand. Radial bursa communicates with the sheath of the thumb; ulnar bursa communicates with sheath of little finger.

It is *drained through two incisions* - one over the proximal part of the sheath; other over the distal part of the sheath in the digit - along the crease lines. A fine catheter is passed into the sheath from proximal incision and irrigated with normal saline through this catheter. This catheter is left in situ for further regular irrigations, splinting of hand is necessary with boxing glove dressing **(Fig. 9-17)**.

Compound Palmar Ganglion

It is chronic tenosynovitis of flexor tendon sheaths due to tuberculosis or rheumatoid arthritis. Smooth, soft, non-tender cross fluctuant swelling


Incisions for digital synovial sheath drainage
Incision for radial bursa
Incision for ulnar bursa
Digital incision
Irrigation polythene catheter
Exposed tendon
Synovial sheath (infected)
Incision in the palm
Syringe with saline for wash
Digital incision
Synovial sheath exposed in the digit
Irrigation polythene catheter
Exposed tendon
Synovial sheath (infected)
Incision in the palm
Syringe with saline for wash

Fig. 9-17: Suppurative tenosynovitis is drained through incision at proximal part and another at digital sheath. Often by placing fine polythene catheter into the sheath saline wash is given into the area.

in the hollow of palm is typical. *Melon seed bodies* are characteristic. It is treated surgically after beginning of the antituberculous drugs. But surgical treatment is not easy. With tourniquet in place, under general anaesthesia, tendon sheath is exposed widely by a vertical incision. Diseased tendon sheath shows adhesions and ramifications on the median and ulnar nerves. With meticulous careful dissections, tendon sheath is excised. All diseased tissues and melon seed bodies are removed. Thorough irrigation is given. Often fine polythene catheter is placed over the sheath for further irrigations postoperatively. Streptomycin irrigation is often used in case of tuberculosis.

Fasciotomy for Compartment Syndrome

Compartment syndrome is a special entity; common in leg, forearm, thigh and arm; is due to increased intracompartmental pressure within a limited space area. *Causes* are – narrowed space due to tight dressings/plaster cast, lying on one limb in comatous patient; increased content of the compartment due to trauma/fractures, oedema, ischaemic injury, haematoma, positioning after trauma, burn injury, etc; high pressure injection injuries like gun injury, oil based material injury as in extravasation of chemotherapeutic drugs; snake bite. It compromises circulation mainly of muscle and nerves. It often maintains the normal colour and temperature of the fingers and distal pulses may not be obliterated in spite of severe muscle ischaemia. Muscle ischaemia for more than 4 hours causes muscle death and myoglobinuria. Irreversible nerve damage develops if ischaemia persists for 8 hours. Progressive, persistent severe pain which is aggravated by passive muscle stretching is the diagnostic sign. Tense tender regional lymph node is typical. Pulse is usually normally felt in compartment syndrome; but may become absent if there is associated arterial injury. Compartment pressure more than 30 mm Hg is an indication for fasciotomy **(Fig. 9-18)**.



Fig. 9-18: Fasciotomy is done in compartment syndrome. Often incision has to be extended into the arm also.

Fasciotomy of anterior compartment of forearm is specific method. Carpal tunnel *should be released* by *cutting flexor retinaculum*. Incision begins at the junction of the thenar and hypothenar area; extends proximally initially transverse across flexion crease of the wrist at the ulnar border; then across forearm towards radial side of forearm; then in proximal forearm towards medial side creating convex flap towards lateral side. In the elbow it crosses along the medial border to reach the arm where it runs along the medial side of the anterior arm. Injury to major nerves, palmar cutaneous branch of median nerve should be avoided while placing the incision. Incision should be deepened by cutting the deep fascia along the entire length of the incision **(Fig. 9-19)**.



Fig. 9-19: Incision for fasciotomy in upper limb begins at flexor retinaculum extending into the forearm with a convex flap towards radial side eventually leading towards medial epicondyle of the elbow joint.

Dorsal fasciotomy should be added by placing longitudinal lengthy incision in the midline. Two longitudinal incisions on the dorsum of the hand also should be made **(Fig. 9-20)**.



Fig. 9-20: Fasciotomy on the dorsum of forearm.

In lower limb also lengthy fasciotomy is done. Often multiple fasciotomies are required. Longitudinal, deep, lengthy incisions to expose the muscle underneath are required. Fasciotomies are done in different compartments – anterior, posterior and lateral **(Fig. 9-21)**.

Delayed secondary suturing in 5-10 days with split skin grafting is needed. Blood transfusions, antibiotics, hyperbaric oxygen are needed. Mannitol may be needed to prevent renal failure.

Chronic ischaemic contracture, gangrene, sepsis, renal failure, disability are the complications.



Fig. 9-21: Fasciotomies done for lower limb.

DRAINAGE OF AN ABSCESS

Drainage of an abscess depends on location of the abscess; whether abscess is formed or not. Superficial/surface abscess is drained by *Hilton's method* of drainage.

Deeper abscess: It is drained after confirmation by CT scan/MRI, etc. It is approached by layer-by-layer incision and drainage. Thorough warm saline irrigation is given. Drain is placed and closed in layers. Pus should be sent for culture.

Pus in the joint: It is confirmed by X-ray/total count, MRI features like pain, warmness, swelling, tenderness, oedema, restriction and pain in all movements of joint . It is usually aspirated under guidance. **Arthroscopy** and wash can be given. Often open drainage is done.

Intraabdominal Abscess

It can be drained percutaneously by placing percutaneous catheter under guidance. Open drainage when needed should be undertaken if aspiration or percutaneous drainage fails.

Laparotomy is done to drain intraabdominal abscesses. Abscess may be in bilateral subphrenic, lesser sac, prepancreatic, interloop, anastomotic site, mesenteric or pelvic. Except pelvic abscess all are drained transperitoneally, and is through upper midline incision **(Figs 9-22 to 9-24)**.



Fig. 9-22: Different intraabdominal abscesses.



Fig. 9-23: Pus in the peritoneal cavity is drained through laparotomy incision.



Fig. 9-24: Upper midline laparotomy incision is used for transperitoneal drainage of intraabdominal abscesses. It is also used for open drainage of liver abscess, transperitoneal drainage of subphrenic abscess when needed.

Technique

Urinary catheter and nasogastric tube should be passed. Anaesthetist often prefers a central line. General anaesthesia with epidural support is used. Lengthy midline incision is used. If patient has undergone recent laparotomy, same incision with extension above and below is used. Peritoneum is opened over new extended part of the incision as it is virgin and chances of bowel adhesions underneath is less likely. Falciform ligament is identified and used as a guide for further dissection. By lifting the ligament dissection is carried out gently using pulp of the finger and gauze. Care should be taken as much as possible to avoid opening of bowel lumen during separation. Right and left suprahepatic and infrahepatic spaces are reached to clear the pus. Lesser sac is approached through gastrohepatic ligament along the lesser curvature of the stomach or through the omentum along the greater curvature of the stomach. Both right and left paracolic gutters are exposed to clear the pus. Often entire small bowel should be freed to clear the pus from interloop areas. Pelvis is reached by pulling the entangled bowel upwards from the pelvis. Pus should be sent for culture and sensitivity. Thorough warm saline wash (10 litres) is given. *Feeding jejunostomy is always* better to be done. Two tube drains/sump drains are placed on either side. Abdomen is closed by *Smead – Jones closure* method.

Subphrenic Abscess

Early diagnosis; considering that subphrenic abscess is thoracoabdominal in extension; drugs and early drainage; initial percutaneous guided catheter placement; when needed open surgical drainage are essential parts always to be remembered in dealing with subphrenic abscesses **(Figs 9-25 to 9-27)**.



Fig. 9-25: CT scan showing subphrenic abscess.

Percutaneous Catheter Drainage

It is the standard initial treatment for subphrenic abscess. US or CT guided placement of catheter is done. One has to remember that *aspiration alone is not done* in subphrenic abscess.


4
3
7
7
Subphrenic abscess
2
6
5
7
Colonic resection
7
7
1
Gangrenous bowel
1. Appendicitis
2. Perforated duodenal ulcer
3. Cholecystitis
4. Amebic liver abscess
5. Pancreatitis
6. Splenectomy
7. Postoperative
- Cholecystectomy
- Gastrectomy
- Biliary surgery
- Pancreatic surgeries
- Colonic surgeries
- Surgery for peritonitis, gangrene bowel
- Pelvic surgery

Fig. 9-26: Causes of subphrenic abscess.


Sternum
Lung
Diaphragm
Pleural effusion
Ribs
Liver
Subphrenic abscess

Fig. 9-27: Subphrenic abscess – common site.

Open Drainage

It is drained by extraperitoneal and extrapleural (*extraserosal*) approach. Aspiration/placing percutaneous catheters under guidance (CT/US) are also used. *Preoperative preparation* - CT scan is very essential diagnostic. Antibiotics should be given – aminoglycosides, amoxicillin, metronidazole. Nasogastric tube should be placed.

Anaesthesia – Procedure is done under general anaesthesia with epidural support for postoperative pain relief.

Technique – Subphrenic abscess is second common intrabdominal abscess. 30% of subphrenic abscess patients can be asymptomatic. *Boyd* classified subphrenic spaces into right suprahepatic and infrahepatic; left suprahepatic and infrahepatic **(Fig. 9-28)**.

Position – Lateral position with body kept obliquely no the table. Patient should be supported properly before cleaning and draping.


1
7
2
3
GB
4
5
6
1. Rt anterior space
2. Lt anterior space
3. Lt posterior space
4. Rt posterior space
5. Rt perinephric space
6. Lt perinephric space
7. Bare area of the liver

Fig. 9-28: Subphrenic spaces anatomy.

Incision – *Anterior extraserous* approach is like a subcostal incision (10–12 cm) from the outer margin of the rectus muscle laterally up to the anterior axillary line towards tip of eleventh rib. *Left anterior extraserous* approach is called as *Clairmount approach*.

Posterior extraserous approach is oblique incision 2 cm from the midline over the bed of 11th rib with opening the periosteum and resecting the rib. Care must be taken not to enter the pleura.

Layers – Skin, subcutaneous tissue, superficial fascia, external oblique muscle, internal oblique muscle are cut. Skin is incised using no. 22 blade. Remaining layers are cut using cutting and coagulation monopolar cautery. 9th intercostal nerve is visualised and often needs to be cut. Transverse abdominis muscle is usually split but can be cut if needed. Splitting is started from behind from posterior aspect as here muscle is not adherent to peritoneum unlike in front. Once muscle is split transversalis fascia with peritoneum can be visualised clearly. Transversalis fascia is cut using blade. One must take care *not to open the peritoneum*.

Technique - Using gauze in sponge holding forceps or finger peritoneum is pushed downward and medially to reach under the costal margin above the liver towards the surface of the subphrenic abscess. Area of induration is felt with finger. Abscess surface is opened using long sinus forceps or by blunt finger dissection. Pus gushes out. Loculi are broken carefully using finger or sinus forceps. Pus is collected for culture and sensitivity. Abscess cavity should be opened widely. Warm saline wash is given into the abscess cavity using 50 ml syringe. Tube drain is placed. One tube drain is sufficient if cavity collapses after drainage. Many tube drains are placed if abscess cavity is large and do not collapse after drainage. Wound is closed in layers using polyglactic acid zero or no 1 suture. Layer by layer closure is done. Many advocate a mass single layer continuous suture which is also accepted. Skin is closed with interrupted sutures or using skin staplers **(Figs 9-29 and 9-30)**.


Skin
SC tissue
Transverse abdominis
Internal oblique
External oblique
Splitting/cutting transversus abdominis
Transversalis fascia with peritoneum
Finger dissection to reach subphrenic space abscess

Fig. 9-29: Subphrenic abscess – open drainage steps – extraserosal approach.


Subphrenic abscess
Incision
Liver
Ribs
Left lobe of the liver
Tube drain in the cavity
Abscess cavity drained
Incision closed

- Lateral position
- Extraserosal approach
- Incision from the tip of 11th rib
- Closure with a drain

Fig. 9-30: Subphrenic abscess – incision, approach and closure.

If the abscess cavity has large thick rigid wall, it takes long time to collapse and often needs regular irrigation of the cavity using one of tube drains **(Fig. 9-31)**.


Pleural effusion
Malecot's tube
Extraserosal approach
Diaphragm
Subphrenic abscess
Peritoneum

Fig. 9-31: Subphrenic abscess – open drainage by placing a tube.

Drain is *removed* in 10–14 days or after collapse of abscess cavity or after confirmation of the obliteration of the cavity by ultrasound or CT scan or contrast dye study using C ARM.

Often it is advised to keep a drain in the subcutaneous tissue. If there is more contamination, skin and subcutaneous tissues are left without suturing but covered with a dressing until healthy granulation tissue develops and wound becomes clean to take up for secondary suturing. Antibiotics are continued.

Complications

Injury to pleura, colon, liver, spleen; bleeding; sinus/fistula formation; incomplete drainage. Other intraperitoneal abscesses may be missed through extraserosal approach.

Transperitoneal Approach

Often transperitoneal approach is needed. Now it is proved that transperitoneal approach is safer. Bilateral subphrenic abscesses, multiple abscesses/more than one cavity or more loculations or subphrenic abscess due to anastomotic leak postoperatively (wherein leak site can be inspected and necessary repair can also be undertaken) are sure indications for *transperitoneal approach*. Upper *midline* approach is used.

Liver Abscess

In developing countries amoebic liver abscess accounts for 80%. In western countries pyogenic abscess accounts for 80%. Fever, chills, abdominal pain, tender hepatomegaly, decreased right sided diaphragmatic movement, sympathetic pleural effusion are the presentations. Raised total count; abnormal liver function tests; anaemia; effusion in chest X-ray are common. US (90% sensitivity) and CT (95% sensitivity) are useful methods. MRI is useful when associated biliary pathology is suspected and when multiple follow-ups are needed **(Figs 9-32 to 9-34)**.


Amoebic abscess
Liver
Amoebic abscess
Liver
Portal vein
SV
Spleen
SMV
IMV
Flask-shaped amoebic ulcer
Caecum
Sigmoid colon
Flask-shaped amoebic ulcer

Fig. 9-32: Amoebic liver abscess is common in right lobe of the liver. Trophozoites reach liver from the colon.


Liver
Abscess
Transverse section
Liver
Abscess
Long section

Fig. 9-33: Amoebic liver abscess ultrasound picture.



Fig. 9-34: CT scan showing multiple liver abscesses.

Aspiration

It is aspirated under US/CT guidance. Wide bore needle is used. Prothrombin time should be corrected if elevated using transfusion of FFP or by injection vitamin K. Needle is placed directly over the abscess or in right intercostal space in midaxillary line **(Fig. 9-35)**.


Aspiration through 8th intercostal space in midaxillary line
US guided aspiration from front—**Ideal**
Amoebic abscess
Liver

Fig. 9-35: Amoebic liver abscess aspiration is commonly done under ultrasound guidance. Prothrombin time should be normal prior to aspiration; if it is widened injection vitamin K 10 mg IM once a day for 5 days or 3 units of FFP should be given to make prothrombin time normal. While passing the needle into the abscess cavity, patient should hold the breath. After aspiration patient is monitored for 6-8 hours. Repeat US is needed after 7 days and 14 days to confirm that abscess has not reformed again.

Percutaneous Drainage

Under US guidance pigtail catheter is placed into the abscess cavity percutaneously to drain the pus. Catheter tube and abscess cavity has to be washed and irrigated at regular intervals with normal saline. It may fail if there is thick pus, multiloculated abscess, and multiple abscesses. Procedure may cause bleeding and infection **(Fig. 9-36)**.

Surgery

Open drainage is done only when indicated. Indications are –filling of cavity after repeated aspirations; thick pus; multiloculated pus; left lobe abscess; ruptured abscess; caudate lobe abscess; multiple abscesses. It is done usually transperitoneally.

Procedure: Through transperitoneal approach, abscess area is opened, pus is evacuated. Malecot's catheter/suction tube drain/sump drain is placed and brought out through a separate wound. The catheter/tube is kept in situ until it completely stops draining. Complete drainage of pus will be confirmed by repeat US. During discharge, advice is given to avoid alcohol. Chloroquine 250 mg bd for 10 days and Diloxanide furoate 500 mg tid is given for 10-14 days **(Figs 9-37 and 9-38)**.

Complications

Anaesthetic problems; bleeding; liver failure (in cirrhotic patients); intraperitoneal abscess formation; bile leak – bile peritonitis and fistula.

Follow up: At regular intervals is important. Avoiding alcohol; repeat LFT; repeat ultrasound to confirm the complete resolution of the abscess cavity.

Laparoscopic drainage of liver abscess is becoming popular.

Pelvic Abscess

It is commonest intraabdominal abscess. Postoperative being the commonest cause, pelvic diseases, pelvic surgeries, gastrointestinal causes, perforation and peritonitis are other different causes. Tenesmus, diarrhoea, lower abdominal pain, tenderness, guarding and rigidity, fever and tachycardia are the features. US/CT is diagnostic. It is initially treated with antibiotics. When it is progressive or symptoms persist it should be drained.

It is drained pervaginally through posterior colpotomy or per rectally in males. Urinary catheter should be passed prior to surgery. Under general or spinal anaesthesia cleaning and draping is done in lithotomy position. Gloved finger is passed into the rectum to feel the soft boggy swelling in front above the prostate level. Incision is made over the swelling in the rectal mucosa to reach the abscess cavity. Pus is drained; collected for culture. Thorough saline irrigation is given. Often tube drain is placed in the cavity across rectum, which is removed in 24 hours. Follow up US in 4-5 days is needed to confirm the resolution of the abscess cavity. In females it is drained in lithotomy position. Incision is made over the posterior fornix pervaginally; pus is drained **(Fig. 9-39)**.

Drainage through laparotomy is usually not necessary.


Percutaneous drainage
Collected pus (Anchovy sauce)

Fig. 9-36: Ultrasound guided percutaneous drainage is commonly used in amoebic/pyogenic liver abscess.


5
10
15
20 ml
Tube drain into the cavity in liver
Corrugated drain into the peritoneal cavity

Fig. 9-37: Amoebic liver abscess on table look. Upper midline transperitoneal approach is used. Abscess is identified. Often on table ultrasound may be useful. Initially abscess cavity is aspirated and confirmed. Liver tissue on the surface is incised using cautery. Anchovy sauce pus is drained; collected for culture; for trophozoites last part of the pus should be collected. After giving saline/metronidazole wash to the cavity separate tube. Malecot's catheter drain is placed into the abscess cavity. Peritoneum is drained separately using a tube. Abdomen is closed in layers.


Malecot's catheter
Open drainage
Liver
Amoebic abscess

Fig. 9-38: Open drainage of amoebic liver abscess. Typical Anchovy sauce pus of amoebic liver abscess contains dead liver cells, RBCs, necrotic material.



Fig. 9-39A


Urinary bladder
Intestine
Pelvic abscess
Rectum
Drainage through anterior wall of the rectum
In male patient
B
Uterine cavity
Urinary bladder
Intestine
Pelvic abscess
Rectum
In female patient
Posterior colpotomy to drain pelvic abscess
C

Figs 9-39B and C

Figs 9-39A to C: CT scan of pelvic abscess. Pelvic abscess is drained through rectum in males and through posterior fornix of the vagina in females.

Perinephric Abscess

It is pus in the perinephric region. Trauma, haematoma, tuberculosis of kidney, blood spread, extension from other area and lymphatic spread are the causes. Fever, loin fullness, tenderness and rigidity, scoliosis towards same side are the features. Loss of downward displacement of kidney is observed in intravenous urogram (*Mathe's sign*). CT is useful to confirm. It is drained percutaneously by placing catheters or by open drainage. Lateral position is used for open drainage. Lumbotomy incision is placed behind over the loin (lumbar incision) to reach the perinephric area. Drain (tube drain/*Malecot catheter*) should be placed **(Fig. 9-40)**.

Pyonephrosis

It is drained by nephrostomy – ***Percutaneous/Cabot's open method/ Tresidder's method***. Percutaneous method is done under guidance. Cabot's nephrostomy is open method; is done under general anaesthesia through loin incision with patient in lateral position. Tube/Malecot's catheter is placed into the renal pelvis across posterior convex surface of the kidney parenchyma. In Tresidder's method, tube is passed across renal parenchyma and pelvis and comes out in two places. Its advantages are – it drains from two places through a single tube; it can be replaced with a similar new tube by railroad technique. But it is technically more difficult. *Complications* – bleeding, sepsis, blockage of nephrostomy tube **(Fig. 9-41)**.



Fig. 9-40: Perinephric abscess. It is drained through a lumbotomy incision.



Figs 9-41A to C: Different types of nephrostomies used to drain pelvis of the kidney in obstruction/pyonephrosis.

Psoas Abscess

It can be pyogenic or tuberculous origin. *Psoas spasm*, with typical flexion position, tender swelling in the iliac fossa are *typical* features. It should be differentiated from iliac artery aneurysm, ovarian cyst, and soft tissue tumour. It is drained extraperitoneally through incision at lumbar region **(Fig. 9-42)**.

CT confirms the diagnosis **(Figs 9-43 and 9-44)**.

It is drained under general anaesthesia or spinal anaesthesia.

Position of the patient is slight lateral tilt. *Urinary catheter* should be passed. Antibiotics should be started.

Technique – *Oblique incision* at the level of the umbilicus extending medially and downwards up to the rectus muscle. Skin, subcutaneous tissue, superficial fascia, external oblique, internal oblique is incised in the line of incision using cautery. Transverse abdominis is split or cut. Often abscess wall is adherent to transverse abdominis and opens while incising the transversus abdominis. Peritoneum is pushed medially without opening it – *extraperitoneal approach*. Abscess



Fig. 9-42: Anatomical location of psoas abscess.



Fig. 9-43: CT scan showing left sided psoas abscess – unilateral.



Fig. 9-44: CT scan showing bilateral psoas abscess.

cavity is opened. Pus drained and collected for culture and AFB. Often biopsy from the abscess wall is done. Occasionally psoas abscess will be located within the psoas muscle sheath or in the muscle. In such occasions sheath is opened longitudinally or muscle fibres are split to reach the abscess cavity. After draining pus properly, thorough warm saline wash is given. In tuberculosis of spine anterolateral decompression of the vertebra followed by vertebral fixation is done. Antituberculous drugs should be started. Tube drain is placed; wound is closed in layers **(Fig. 9-45)**.

Drain is removed in 10-14 days after confirming of obliteration of the cavity (Fig. 9-46).

Complications

Peritoneal opening may cause peritoneal contamination. Injury to iliac vessels often can occur. Often iliac vein wall undergoes pressure necrosis and causes life threatening haemorrhage. In such occasions it is difficult to do repair of the vein with sepsis underneath. Best way is putting a pack or ligating the vein.


Psoas abscess with flexion of hip/inability to extend due to psoas spasm
Psoas abscess
Tn abdominis
External oblique
Skin
Internal oblique
Aspirating and opening abscess cavity
Abscess cavity
Putting finger into abscess cavity to break loculi
Send pus for culture and sensitivity and also often biopsy from the wall may be needed
Pus for AFB is also done
Thorough warm saline wash is given
Ideally tube drain is placed
Closed in layers
Polyglactic acid-2 zero-continuous or interrupted

Figs 9-45A to N: Drainage of psoas abscess is done extraperitoneally through oblique incision at the level of the umbilicus.



Fig. 9-46: Confirmation of pus in psoas abscess by needle aspiration. Drainage of psoas abscess by placing Malecot's catheter.

Other Abscesses

Pancreatic abscess is aspirated under CT guidance or drained by transperitoneal open drainage method or laparoscopic method.

Mesenteric abscess/bowel interloop abscess are drained through laparotomy – midline incision.

Abscess neck is drained under general anaesthesia. Usually horizontal incision is placed.

Abscess in the axilla is drained under general anaesthesia through crease incision placed in the lower part of the axilla.

Intracranial abscess is drained through craniotomy/burr holes using Dandy's brain cannula. It may be due to trauma, infective endocarditis, spread from infected sinus, untreated suppurative otitis media. CT brain localizes the site of abscess. Headache, fever, localising symptoms, convulsion, systolic hypertension, vomiting and drowsiness are the typical clinical features. Antibiotics, anticonvulsants, supportive treatment are essential **(Fig. 9-47)**.



Fig. 9-47: Intracerebral abscess is drained by burr hole and passing Dandy's brain cannula into the abscess cavity.

Lung abscess is difficult to drain. It needs thoracotomy; exploration; often lobectomy. Empyema is drained using intercostal tube drainage.

Brodie's abscess is abscess in the bone (metaphysis). It is drained by open methods—saucerisation and sequestrectomy.

Bartholin cyst is retention cyst due to blockage of duct of the gland. Bartholin glands are greater vestibular glands (similar to Cowper's glands in males) lying in superficial perineal space, overlapped by the posterior ends of the bulbs of the vestibule. Each gland on either side has a 2 cm long duct which opens on either side on the margin of the labia minora posteriorly. Once it gets infected abscess forms. Drainage with marsupialisation is the treatment. 2 cm elliptical incision is made on the skin over the inner side of the cyst. Skin is excised; corresponding elliptical incision is also made over the cyst wall. It is often difficult to incise skin and cyst separately even though it is ideal; in such situation both skin and cyst wall are incised together. Cyst content with pus is drained. Edge of the incised cyst wall is sutured to the corresponding part of the incised edge of the skin using fine – 4 zero absorbable polyglactic acid to create a stoma. *Marsupialisation*—Stoma drains, granulates and heals with less chances of recurrence **(Fig. 9-48)**.


Mons pubis
Clitoris
Labia majora
Labia minora
Urethra
Vestibule of vagina
Opening of Bartholin gland
Bartholin abscess
Marsupialization

- Elliptical incision on the inner aspect
- Both skin and cyst wall elliptically incised and removed. Edges correspondingly sutured-interrupted polyglycolic acid sutures
- Stoma of 2 cm in size

Fig. 9-48: Bartholin abscess occurs on the posterior aspect of the vestibule over labia minora. It is drained by marsupialisation.

Chapter 10

Amputations

Amputation is done as life saving procedure especially in sepsis, diabetic gangrene, gas gangrene, etc. It is also often a therapeutic approach for malignancies in distal limb wherein conservative approach is not possible. Olden days amputation was a procedure done for leprosy and ergotism. Amputation needs proper planning of the flaps, prosthesis, initial mobilisation later rehabilitation and psychological support. It is one of the ancient surgical procedures. Sir William Fergusson in 1867 said, "Amputation is the one of the meanest, yet one of the greatest operations in surgery; mean, when resorted to where better may be done great, as the only step to give comfort and prolong life". Ambroise Pare in 16th century did functional stumps and used the ligatures for major vessels. In World War I and II amputations were commonly done procedures along with invention of prosthesis.

Amputation is a procedure that removes a part through one or more bones. With exception of penectomy for carcinoma of penis which is called as amputation of penis.

Disarticulation is removal of part through the joint.

INDICATIONS

(Dead, dying, devitalized or dead, deadly/dead loss)

Gangrene due to atherosclerosis, embolism, thromboangiitis obliterans, diabetes, ergots, frostbite, trauma (complete devitalised distal tissues); to save life in crush injuries; severe electric burns; neoplasms; osteosarcomas; Marjolin`s ulcer; melanomas; gas gangrene; severe sepsis; after nerve injury if part of the limb is completely paralysed with disabling trophic ulcers occasionally severe elephantiasis, madura foot, osteomyelitis, septic arthritis when all other methods were not of help. Disabling congenital deformities like complete fibular hemimelia, tibial hemimelia, femoral deficiencies and severe acquired deformities are also rare indications for amputations.

Types

Cone bearing
End bearing
Weight bearing
Non-weight bearing.

Types of Flaps

Long posterior flap like in below knee amputation **(Fig. 10-1)**.
Equal flaps like in above knee amputation.

Elective amputation is planned one with flap. Infection should be absent. Viability of muscles and healthy skin are basic requisites for elective amputation. Level of amputation should be decided properly. Major blood vessels are ligated individually at same level. Nerve is pulled down adequately and cut without ligation. Cut bone margin should be made smooth using a rasp. Muscles should be closed over the bone. Suction drain ideally or corrugated drain is inserted on the lateral margin of the same wound which is removed in 48 hours. After removal of drain, firm pressure dressing is needed to control oedema and to prevent haematoma formation and which is left in situ undisturbed for 5 days. Early temporary prosthetic device may be used. Later permanent prosthesis is used after 3 months once stump forms a smooth round surface.



Fig. 10-1: Below knee amputation stump with long posterior flap.

Emergency amputation is done in trauma, gangrene leg or severe sepsis. Here skin, muscles and bone are cut at the same level without suturing as in *guillotine amputation*. Later once sepsis subsides and patient recovers stump is revised for a proper flap.

In vascular diseases tourniquet should not be used during amputation.

Present Classification of Amputation

Present classification of amputation is as –
Open or closed amputation.

Open Amputations

- Open amputation with skin flaps.
- Circular open amputation.
- Guillotine amputation.

Open amputation with inverted skin flaps – Skin flaps are elevated longer than normal. Muscles are divided distal to the intended level of bone transection. After amputation, edge of skin flap is sutured at the corresponding level along with subcutaneous tissue and fascia using interrupted absorbable sutures creating rolled flaps. Once good granulation tissue appears, infection subsides, flaps are closed after 14 days.

Circular open amputation – Skin and muscles are divided circularly at a lower level than bone and left alone. Flap is closed at a later date once sepsis comes under control.

Guillotine amputation – Here all tissues of the limb are divided at the same level and left exposed. It is used in machinery trapping or severe sepsis. It is primitive type of amputation. Revision amputation is needed at a later period. *Definitive closure* is done using reamputation at proximal level; revision amputation; repair of the stumps.

Closed Amputations

It is widely used definitive amputation wherein stump is covered with flaps which should be ideal, highly functional and suitable for proper prosthesis. *Tourniquet* is used except in vascular cases. General/spinal/epidural anaesthesia is used.

Level of amputation is decided based on the identification of the level of adequate perfusion. It is assessed by skin temperature; systolic pressure (ankle systolic pressure should be more than 40 mm Hg); Doppler; transcutaneous oxymetry (PO2 more than 40 mm Hg); arteriography; digital plethysmography; thermography; isotope clearance and dye attenuation studies.

IDEAL STUMP

- It should have adequate blood supply. It should heal adequately by first intention.
- It should have rounded gentle contour; with adequate muscle padding, conical shape with distal tapering is better. Stump should be free from tenderness and conical.
- Opposing groups of muscles should be fixed together over the end of the bone to attain optimum power and control of the muscles at the stump. Smooth, pain free/tenderness free stump should be obtained.
- Joint proximal to the amputation stump should show full range of movements without any contractures. Skin should have a clean incision which should be sutured tension free. Freely mobile skin over the bone and soft tissues should be achieved to get free movement of the prosthesis to be placed later. Socket of prosthesis with mobile skin creates a piston to bone to move like a joint. Transverse posterior scar is better which will not expose to pressure.
- It should have sufficient (optimum) length to bear prosthesis. For below knee amputation (B-K) 7.5 (minimum) to 12.5 cm from ischial tuberosity; for above knee amputation (A-K) 23 cm from greater trochanter. For above and below elbow 20 cm stump is used.
- It should have thin scar which does not interfere with prosthetic function. Scar should be in a place where it is not exposed to pressure. Skin should not be folded. Redundant soft tissue should not be there.
- It should have adequate adjacent joint movement.

Conical bearing

- Here healing is by primary intention.
- Bone should not be projecting.
- Myoplastic.
- Neuroma formation is not there.
- Scar should not be tender.
- Proximal joint should be supple.

Postoperative Period

Physiotherapy is advised. Regular dressings are done. Crutch is used initially, after 3 months prosthesis is placed. Rehabilitation is important.

COMPLICATIONS OF AMPUTATIONS

- **Early**
  Haemorrhage, haematoma, infection.
- **Late**
  Pain, ulceration of stump, ring sequestrum formation, flap necrosis, painful scar. ***Phantom Limb*** - Feeling of amputated part in toto or partially with pain over it.

Haematoma is identified by pain, swelling over the stump underneath the flap. It is aspirated using a wide bore needle. Haematoma may delay healing; may precipitate infection or flap necrosis due to pressure. After aspiration, pressure dressing is needed. If haematoma reforms after 2-3 aspirations, it should be drained by opening the wound on one corner and inserting haemostat into the wound.

Infection of the stump may cause abscess formation, delay in healing of wound, flap necrosis, giving way of the wound. Removing few or all sutures to relieve pressure and draining the pus underneath is needed. Infection may also lead into poor scar, adherent scar which causes difficulty in placing the prosthesis **(Fig. 10-2)**.

Flap necrosis is *common* complication. Main causes for flap necrosis are poor blood supply, infection, haematoma underneath, inadequate length of the flap causing stretching of flap. Small area of necrosis can be excised. Wider area needs laying open of the wound or revision of the stump or higher level amputation. Anaemia, poor nutrition, deficiencies, diabetes mellitus, immunosuppression, smoking and old age are other factors causing flap necrosis.

Stump neuroma can occur due to proliferation of the nerve fibrils beyond the point of nerve division and is usually due to failure of cutting of the nerve more proximal to the level of division of the bone. It causes pain and tenderness over the stump. It is usually relieved by analgesics, reassurance and prosthesis. Occasionally it may require reexploration of the wound, excision of end neuroma and also cutting of nerve more proximally.



Fig. 10-2: Infection of the below knee stump exposing the cut end of tibia.



Fig. 10-3: Ulcer in amputated stump.

Stump pain after amputation is *a common problem*. Causes are – infection, poor blood supply, causalgia, stump neuroma, phantom pain/limb, deep vein thrombosis, adherent scar, formation of spurs and osteophytes at amputated bone end. Scar adhesion to bone is prevented by keeping adequate length of deep fascia underneath intact. Spurs and osteophytes are confirmed by X-ray and needs removal using bone nibbler after appropriate skin incision.

Phantom limb is *typical* awareness of sensation that as if amputated part is still present; often such part may be painful or disturbing or hyperaesthetic. Exact cause is not known; but it is probably due to presence of severe pain at the amputated part just prior to amputation making brain area for the part in alert situation causing phantom limb. Reassurance, prosthesis, analgesics control the condition. It is said that it can be prevented by proper pain control for 24 hours prior to amputation; but it is often difficult.

Ulceration over the stump is *not uncommon*. It is due to necrosis, infection, lengthy bone stump pressing on the summit of the flap, prosthesis, deficiencies, diabetes mellitus, ischaemia. Ulcer may be small/large; superficial/deep. Callous chronic ulcer at the end of the stump is called as *Douglas ulcer*. Small ulcer is treated by regular dressings and suturing later. Large ulcer needs flap to cover the defect. *Osteomyelitis of the stump* should be ruled out in chronic stump ulcer. *Ring sequestrum* may be typical in such situation. Revision amputation is needed for stump amputation **(Fig. 10-3)**.

Contracture of the joint proximal to the amputated stump is *common*. It is mainly due to improper positioning after amputation; due to pain, poor exercise and occasionally due to inflammation of surrounding soft tissues. Contracture interferes with proper fitting and functioning of the prosthesis and delays rehabilitation. Proper positioning, passive stretching and strengthening exercises correct it. Rarely needs surgical release of the contracture.

Other complications like scar hypertrophy, skin thickening, hyperkeratosis, papilloma, eczema, lymphoedema, boils, bursae over bony point can occur, which are treated accordingly.

Evaluation of the patients who need amputation

- Haematocrit, control of anaemia by transfusing blood/packed cells.
- Control of infection using antibiotics.
- Decision of level of amputation by skin temperature, arteriography, arterial Doppler, transcutaneous Po2, laser evaluation.
- Informed consent.
- Plan for prosthesis and rehabilitation by physiotherapist and rehabilitation team.

Different incisions for amputations

- *Circular incision amputation*– skin and muscles are divided circularly at a lower level than that of bone
- *Elliptical/oval incision* amputation
- *Racquet incision amputation*–for digital disarticulation
- *Amputation using flaps*–it may be of equal flap (above knee amputation) or with long posterior single flap (below knee amputation). Total length of single flap or combined length of two flaps should be equal to $1^1/2$ times the diameter of the limb at the line of amputation. Flap should be semicircular to get a conical stump, not rectangular

PRINCIPLES IN AMPUTATION

- Adequate blood supply of the flap should be maintained.
- Proper marking of the skin incision is essential. Skin should not be crushed or traumatised. Clean cut on the flap is essential. Opposing two equal flaps or long single flap is used. Total length of single flap or combined length of two equal flaps should be 1½ times the circumference of the limb at the level of bone section. Equal anterior and posterior flaps (above knee amputation) or long posterior flap (below knee amputation) is commonly used. Tension free flap suturing should be achieved.
- When unequal flaps are used, shorter flap should be broader than longer flap so that skin edges sutured as equal length. Adequate blood supply of the flap should be ensured.

- Tourniquet *should not be used* if amputation is done for vascular diseases. Other cases like in trauma and tumour it can be used. When it is used, it should be released before skin closure to achieve proper haemostasis.
- Proximal part of the flap contains muscle component but distal part should contain only skin and deep fascia. Deep fascia is cut along with the skin and reflected along with skin. Earlier in conventional amputations, muscles are cut at the level of transection of bone. But now myodesis or myoplasties are routinely done. In *myodesis,* opposing muscle groups are sutured/anchored to bone end using drill holes. Myodesis is contraindicated in peripheral vascular disease. In *myoplasty*, opposing muscles which are divided 5 cm distal to bone transection are sutured to one another adjacent to bone end. It is preferred in peripheral vascular disease.
- Flap length should be adequate; not short. It should be ideally *semicircular* not rectangular to get a conical stump.
- Nerve should be pulled down and cut using a sharp knife and allowed to retract into the soft tissue otherwise neuromas may develop.
- Major vessels should be individually isolated and ligated. Mass ligature should be avoided.
- In crush injury/entrapment injury/sepsis - *guillotine amputation* is done. Later skin is pulled down by using skin traction, eventually to have better skin coverage.
- Bone should be cut with beveling and all sharp margins should be rounded using rasp. *Osteoplasty* can be done by raising a sleeve of periosteum over the bone; after cutting the bone periosteum is closed over the bone end.
- Usually drain is placed (tube drain) through the wound which is removed in 48-72 hours. *Conventional soft dressing* using gauze, wool and crepe bandage is used. Amputation in weight bearing area like lower limb*, rigid dressing* using plaster of Paris cast is used to reduce oedema, stump pain, early stump maturation and proper healing. Rigid dressing may cause pressure necrosis, ischaemia and infection. *Intermittent pressure* as a controlled environment chamber in a plastic sleeve is also used. A *true prosthetic cast* may be used if weight bearing ambulation is anticipated in immediate postoperative period **(Fig. 10-4)**.
- Postoperatively patient is mobilised using axillary crutches. After 3 months, once scar has matured and stump has become supple, proper prosthesis is fit. *Berlamont* first started immediate postoperative fitting of prosthesis to leg for early mobilization. *Plaster pylon* is applied to the stump and a prosthetic extension is fit to facilitate partial weight bearing immediately after surgery. It has got more stump complications and so it has not become popular **(Fig. 10-5)**.
- Position of the stump in postoperative period is important. Stump should be elevated by raising the foot end of the bed. In above knee amputation avoid placing pillow below or on inner aspect of the stump so as to prevent fixed flexion or abduction contracture.
- Stumps can be side bearing (sutures are on the side); end bearing/conical (sutures are on the end) or cylindrical.
- Postoperatively active exercise should be given to the proximal joint so that prosthesis can be fit to it properly.
- If there is sepsis especially in gangrene limb, flaps should be left open or loosely sutured otherwise flap necrosis occurs.
- Proper anatomy of muscles and neurovascular bundle around should be known in all amputations.



Fig. 10-4: Rigid and soft dressings used for amputation stump.



Fig. 10-5: Pylon is plaster cast with walking component used for immediate mobilization after below knee amputation.

DIFFERENT AMPUTATIONS (FIGS 10-6 AND 10-7)


8
7
Gritti-Stokes
6
5
4
3
2
1
1. Ray's
3. Tarsometatarsal (Lisfranc's)
5. Syme's
7. Transcondylar
2. Transmetatarsal (Gillies)
4. Midtarsal (Chopart's)
6. Below-knee (Burgess)
8. Above-knee

Fig. 10-6: Different levels of amputation in lower limb.


25 cm from
G trochanter
17 cm from
knee joint

Fig. 10-7: Levels of bone transactions in above knee and below knee amputations.

Toe Amputation

In conditions like trauma, other than vascular or septic causes toe can be amputated at the base of first phalanx so the joint capsule of metatarsophalangeal joint is kept intact. One or two toes can be amputated with retaining remaining toes. If three or more toes need amputation then all toes should be amputated. When only 2nd toe is amputated it is done at or close to the first interphalangeal joint, otherwise if amputated more proximally it will cause valgus deformity of great toe which can be distressing **(Figs 10-8 to 10-10).**



Fig. 10-8: Second toe amputation.



Fig. 10-9: Lateral two toes (4th and 5th) amputation.



Fig. 10-10: Great toe amputation in vascular disease. Here flap is kept open; not sutured.

Ray Amputation

Amputation of toe is done with removal of corresponding head of metatarsal or metacarpals. Amputation of one or more toes causes loss of push off power during walking. Racquet incision is placed at metatarsophalangeal joint. Incision is deepened directly to the bone; then proximally flap is raised close to the bone. It is important to keep the scissor/knife blade to keep close to bone to maintain the blood supply of flap. Digital vessels of the toe are ligated near distal end of the wound. Head of the respective metatarsal should be removed as granulation tissue may not form over it when wound is left open like in vascular cases; or necrosis of metatarsal head can occur; or extra callus may be formed once walking is started. Metatarsal head can be cut using bone cutter. Alternatively toe is amputated with same racquet incision initially at the metatarsophalangeal joint level; then head of the metatarsal is removed using bone nibbler by piecemeal. In vascular cases it is better not to suture the flap rather than closing it. Suturing when done, only skin flap is closed using 3 zero polypropylene or polyethylene sutures. Dressing placed. Sutures removed in 7-10 days **(Fig. 10-11)**



Fig. 10-11: Ray amputation for toes – racquet incision.

Transmetatarsal Amputation (Gillies')

Here amputation is done proximal to the neck of the metatarsals, distal to the base. It is done if skin over the distal part of the dorsum of foot between toes is necrosed and non-viable. Patient can wear a normal shoe with this amputation. But volar and proximal parts of the foot should be viable for this amputation. Plantar part of the incision is close to digits. Dorsal part of the incision is much more proximal than plantar one – 3 cm distal to the base of toes. First plantar incision is placed which is deepened up to the metatarsals and flexor tendons. Flexor tendons are individually divided. Volar flap is raised close to the metatarsals. All metatarsals are transected 2 cm from the base. Dorsal incision which is much proximal is deepened to cut soft tissues to remove the distal part of the foot to retain the stump. Deep fascia is sutured. Skin is sutured with suture line on the dorsal aspect. Drain is placed underneath **(Fig. 10-12)**.


Incision plantar aspect
Dorsal incision 3 cm from the base
Line of cutting on the bone 2 cm from base
Bases of matatarsals
Incision dorsal aspect

Fig. 10-12: Transmetatarsal amputation.

Lisfranc's Amputation

Tarso metatarsal amputation – Here tarsometatarsal joint is disarticulated with a long volar flap (between tarsals and metatarsals). Long plantar sole flap is used. Tarsometatarsal joint is disarticulated. Flexors and extensors are sutured to soft tissues. It needs a surgical boot. But there is inevitable development of equinovarus deformity. So stabilisation of midtarsal and ankle joints is needed. In *Hey's modification*, 2nd metatarsal is cut at base instead of disarticulation.

Chopart's Amputation (Midtarsal Amputation)

Here talonavicular joint and calcaneocuboid joints are disarticulated (only talus and calcaneum are preserved). Tibialis anterior muscle is sutured to drilled neck of the talus bone. A long volar flap is used and limb is immobilized for 6 weeks after surgery with ankle in neutral position. *Equinovarus deformity* is the problem **(Fig. 10-13)**.

Syme's Amputation

It is removal of the foot with calcaneum and cutting of tibia and fibula just above the ankle joint with retaining heel flap (dividing both malleoli). Heel flap is supplied by medial and lateral calcaneal vessels (branches of posterior tibial artery). *Elephant boot* is used for the limb after Syme's which is inexpensive. Many patients walk well with Syme's stump without difficulty. It is presently mainly used in trauma (crush injury), congenital deformities of foot wherein amputation is inevitable, nonischaemic damage of foot and malignancies in distal part of the foot. In vascular diseases, calcaneal vessels may not be adequate to maintain the viability of the flap. Ulcer in the heel, cosmetic view if considered, Syme's amputation cannot be done.



Figs 10-13A to C: Forefoot amputation.

Incision is from the tip of lateral malleolus to a point 2 cm below the medial malleolus. While raising the flap knife should be very close to the calcaneum so as to avoid injury to calcaneal vessels and to maintain the flap vessels viable – subperiosteal dissection of the calcaneum along posterior flap. Anteriorly retinaculum and tendons are divided. Anterior joint capsule of the ankle is incised; medial and lateral ligaments are divided. Tibia and fibula are cut just 0.6 to 1.0 cm above the ankle. Plantar fascia is sutured to soft tissues in front of tibia. In *Wagner's method* deep fascia of heel is sutured to drill holes made on the anterior edge of tibia and fibula. *Above knee cast* is essential. Drain placed is removed after 48 hours. Plaster cast to heel pad in 7th day; weight bearing rocker is added in 3rd week; definitive prosthesis is used after 8 weeks.

Advantages are – It is an end bearing stump having good proprioception. Patient can walk without prosthesis. Low energy consumption ambulation is possible.

Disadvantages – Posterior displacement of heel pad; poor cosmesis **(Figs 10-14 to 10-16)**.



Figs 10-14A and B: Incision for Syme's amputation and level of amputation.

Two stage Syme's amputation is done when there is gross forefoot infection. First stage – With an incision 1 cm distal and anterior to malleoli, ankle joint is disarticulated with closure of flaps with suction irrigation. Second stage – Formal elliptical incision and removal of malleoli.

Boyd's amputation – Anterior part of the calcaneum is excised (osteotomy) just distal to the peroneal tuberosity and calcaneotibial arthrodesis is created. It is done to prevent posterior migration of heel pad.



Figs 10-15A to F



Figs 10-15G and H

Figs 10-15A to H: Syme's amputation technique.



Fig. 10-16: Elephant boot used after Syme's amputation.


Level of bone cutting
(tibia and fibula just
above malleoli)
Incision for modified Syme's

Fig. 10-17: Modified Syme's incision is elliptical one.

Modified Syme's Amputation

Here heel flap is elliptical. Tibia and fibula are divided slightly higher. But variation here is the elliptical flap **(Fig. 10-17)**.

Pirogoff's Amputation

It is like Syme's amputation except posterior part of the calcaneum is retained along with heel flap. It provides longer stump than Syme's amputation **(Fig. 10-18)**.

Below Knee Amputation

It is done in peripheral vascular disease, trauma, infections and tumors. In peripheral vascular disease, posterior flap is used. In trauma equal flap may be a choice. It is contraindicated in stump if


Cut ends tibia
and fibula
Heel flap
Incision
Calcaneum part

Fig. 10-18: Pirogoff's amputation.

becomes less than 7.5 cm, flexion deformity of 30^0 or more, restricted knee joint movement, motor neurological diseases which prevents prosthesis function.

Here long posterior flap with scar placement over anterior aspect is used. Prosthesis placement is better here with greater range of movements without limp and without support. It is also called as *Burgess amputation*. Fibula should be divided first; higher (1 cm) than the proposed site of cut of tibia otherwise its sharp end will press on the skin flap. Tibial stump should be beveled anteriorly. Its edge is smoothened using rasp. Vessels are isolated and individually ligated using silk at the level of the stump. Nerve is pulled down sufficiently and cut at more proximal level without any ligature. Muscle is cut tapering towards the distal end of the flap. Soleus muscle is cut, gastrocnemius is trimmed on the edge to reduce the bulk. Posterior muscles are sutured across the bone end, to the periosteum in front. In more proximal type of below knee amputation, fibula often is removed to allow the proper use of flap. Length of the flap should be $1^1/_2$ times the circumference of the site (around 12 cm). Stump length is 14-17 cm from knee joint. Minimum length required for prosthesis is 8 cm. Anything proximal, it is better to do above knee amputation. Suction drain ideally or corrugated drain on the edge of the same wound is placed and kept for 72 hours. Adequate dressing pads should be placed over the stump and pressure bandage using crepe is placed. Often posterior slab/cast are used up to mid thigh to prevent patient from keeping the knee in flexed position. Stump maturation occurs in 8 weeks. Modern artificial limbs like *suction socket prosthesis* are used now **(Figs 10-19 to 10-21)**.



Fig. 10-19: Below knee amputation technique – incision, flap and levels of cutting bones.

Skew flap with skin flaps are equal on medial and lateral aspects but single posterior muscle flap is sutured anteriorly to the tibia. Flap is along long saphenous vein and saphenous nerve medially; and along small saphenous vein and sural nerve laterally **(Fig. 10-22)**.

Periosteum from tibia can be raised from distal to the level of transection of the tibia which is swung over the cut end of fibula to create a synostosis bridge of periosteum between tibia and fibula. This is used when amputation is done in young individual.

Prosthesis fit to below knee stump makes patient to walk normally **(Figs 10-23 to 10-26)**.



Fig. 10-20: Incision for below knee amputation.

'Peg-Leg' Amputation

It is amputation 5 cm below the knee level – proximal most below knee amputation. It is *not practiced* nowadays. Here anterior flap is rotated posteriorly like a hood and patient kneels and bears weight which is well accustomed to pressure. It is done whenever prosthesis cannot be used probably due to economic causes (in developing countries) **(Fig. 10-27)**.

Knee Joint Disarticulation

It is done in non-functional damaged knee joint wherein below knee amputation is not possible; amputation in non- ambulating bedridden patient; very ill patients; patients who need locked knee prosthesis or *end bearing stump*. It is *preferred in children* than doing above knee amputation. Its bulbous end allows suspension of prosthesis without thigh corset.

It is contraindicated in ischaemic conditions. It is cosmetically inferior; less vascular; poor healing; prosthesis controlled gait is difficult to achieve **(Fig. 10-28)**.

It is done in *prone position* through an anterior incision from a point mid way between lower pole of patella and tibial tubercle to a point 5 cm laterally below the joint line. Incision posteriorly curves towards midline in popliteal fossa 2.5 cm above joint line. Flaps are *medial and lateral*; medial is larger. Incision is deepened in posterior aspect first; vessels and nerves are divided; posterior muscles and joint capsule is cut; joint is opened; cruciate, medial and lateral ligaments are cut; patellar tendon is cut; patella is retained. Once joint is disarticulated patellar tendon is sutured to cruciate ligaments and retinaculum is sutured to hamstrings. Anteroposterior longitudinal scar is formed. Drain should be placed.


Incision for BK amputation
A
Raising the flap after deepening the incision
B
C
D
E
F
G
Giglie's saw
H
I
J
K
L
M
O
P
N
Q
Bone wax
R

Figs 10-21A to R


S
T
U
Suction drain is ideal
V
W

Figs 10-21S to W

Figs 10-21A to W: Technique of below knee amputation.


Anterior view
Posterior view
Incision
Oblique flap
Fibula
Tibia
Medial flap
Muscle
Lateral flap
Myocutaneous flap
Longer muscle is sutured in front on the periosteum of tibia
Tibia
Muscle
Skin suture line (Oblique antero-posterior)
Flap
Oblique skin flap (Skew) is sutured over the summit

Fig. 10-22: Skew flap for below knee amputation.



Fig. 10-23: Below knee amputation – long posterior flap. Note the placing of the drain.



Fig. 10-24: Below knee amputation flap necrosis has occurred which eventually granulated with regular dressings. Area is ready for skin grafting.



Fig. 10-25: Below amputation with flap necrosis in which later wound got granulated well. Knee joint contracture is a great problem in rehabilitation.

Transcondylar/Gritti-Stokes Amputation with Long Posterior Flap

It is done in supine position; long anterior flap extending below the patella is used (flap is not raised posteriorly). Patellar tendon is cut; joint is entered from front; posterior soft tissues and muscles are divided. Femur is divided just above the articular surface; articular surface of the patella is shaved off; patella is anchored to the divided femur through drill holes with wires passed through drill holes; patellar tendon is sutured to hamstrings. Femur may be divided 30° obliquely anteroposteriorly as a modification. There is risk of non-union between patella and femur. This procedure is *no longer performed* **(Figs 10-29 and 10-30)**.

Above Knee Amputation

It is done in ischaemia, trauma, sepsis and gangrene which is spreading above. Often patient might have undergone below knee



Fig. 10-26: Below knee amputation stump which is badly infected, this may need above knee amputation.



Fig. 10-27: 'Peg leg' amputation is below knee amputation done close to the knee joint (5 cm stump) with folding flap and metallic support down. It is not used now.

amputation earlier but now as indicated for above knee amputation as either BK flaps are not good or sepsis is extending above. It is usually contraindicated in children (done only in undue definitive indication) or if stump is less than 7.5 cm.

Advantages are technically easy, healing chances are better and faster. Disadvantages are cosmetically poor, rehabilitation is difficult, and prosthesis fitting is not proper, patient needs a third support for walk with often a limp.

Usually equal anterior and posterior flaps are used. Alternatively long anterior flap may be used.

Lower third and middle third level amputations are done. Ideally the required length of the femur as stump is 25 cm from the tip of the greater trochanter. Length lesser than 10 cm is not possible and one needs to do hip disarticulation. In children as growing epiphysis of femur is at the lower end, as much length of femur as possible should be preserved.



- Medial and lateral flaps
- Medial flap is 2 cm longer
- Anteroposterior suture line/scar
- Procedure in prone position

Fig. 10-28: Technique of knee disarticulation.

Femoral vessels are individually ligated two times. Femur is cut with anterolateral bevel. Sciatic nerve is pulled and cut; accompanying artery, arteria nervi ischiadii when needed should be ligated separately not along with sciatic nerve. Quadriceps is sutured to hamstrings or the drill holes made in cut distal end of the femur. This myodesis prevents muscle imbalance. Suction drain and soft crepe bandage dressing is placed. Patient is advised to lie prone for 15–30 minutes a day to prevent flexion contracture of hip joint **(Figs 10-31 to 10-34)**.

Hip Disarticulation

It is done whenever it is not possible to save the minimum 10 cm length of the femur. Incision used is either single posterior flap – Solcum's approach (better) or anterior racquet incision – Boyd's approach. Posterior flap stump is better to fit prosthesis. Anterior racquet incision begins as a vertical incision along the femoral vessels with medial and lateral flaps curving posteriorly; medial flap is longer. Scar here will be away from perineum. In the posterior flap the length of the flap should be 1½ times the anteroposterior diameter of the limb at



Fig. 10-29: Incision for Gritti-Stokes amputation.



- Long anterior flap
- Femur is cut just above the condyles straight or obliquely
- Patellar articular surface is shaved and apposed to cut surface of femur
- Quadriceps/patellar tendon is sutured to hamstrings
- Procedure is done in supine position

Fig. 10-30: Gritti-Stokes amputation.



Fig. 10-31: Above knee amputation incision and approach.

hip joint level. The anterior part of the incision is 2.5 cm below and parallel to inguinal ligament. Anterior part of the incision is deepened; muscles are divided in the line of incision; joint is opened from front; adductors, hamstrings and gluteus maximus are divided with retaining part of it in posterior flap. Joint capsule and short muscles are cut to complete the disarticulation. Muscles and flaps are sutured to create a stump **(Fig. 10-35)**.

Hind Quarter Amputation

Interinnominoabdominal amputation (Sir Gordon Taylor amputation): Removal of one side pelvis with innominate bone, pubis, muscles and vessels. Original ligation of common iliac artery is modified to individual ligations of external and internal iliac vessels. Internal iliac artery is ligated beyond the origin of the superior gluteal artery to keep the large posterior flap viable. *Now hind quarter name is replaced by hemipelvectomy*. It may be *standard hemipelvectomy* with classic gluteal flap; *extended hemipelvectomy* with removal of posterior part of the sacrum; *conservative hemipelvectomy* with retaining part of the pubis, ilium bones on that side. *Internal hemipelvectomy* is new method wherein hemipelvectomy is done with preserving the limb.

It is done in malignant diseases of soft tissues of pelvis or thigh; severe congenital malformations; failed above knee amputation or hip disarticulation. Procedure needs proper prior preparation of the perineum and limb to prevent sepsis. 6 units of blood should be kept ready as bleeding is common. Initial position is supine with long narrow sand bags placed under shoulder and buttock of same side. Later patient is rolled to lateral position for posterior flap dissection.

Standard hindquarter amputation is done with an elliptical incision with anterior abdominal muscles are divided in the line of incision. Inferior epigastric vessels are ligated. Pubic symphysis is divided. Peritoneum and ureter are pushed medially with blunt dissection. Internal iliac artery is ligated distal to origin of the superior gluteal artery. External iliac vessels are divided. Ilium is divided across greater sciatic notch. Main part of the gluteus maximus is retained in the flap supplied by superior gluteal artery. Remaining soft tissues and nerves are cut. Obturator, pudendal, other gluteal vessels are ligated. Flap is sutured after proper haemostasis **(Fig. 10-36)**.

UPPER LIMB AMPUTATIONS

Upper limb amputations are less commonly done (3-15%) as compared to lower limb amputations. Trauma, malignant tumour, gangrene are the indications. All possible length should be preserved to improve the efficacy of the prosthesis. In distal amputations, prosthesis function will be better **(Fig. 10-37)**.


A
B
C
D
E
F
G
H
I
J
K

Figs 10-32A to K


L
M
N
O
P
Q
R
S
T
U
V
W

Figs 10-32L to W


X
Y
Z
A1
A2
A3
A4
A5
A6
A7
A8
A9

Figs 10-32X to A9



Figs 10-32A10 and A11

Figs 10-32A to A11: Steps in above knee amputation.



Figs 10-33A and B: Above knee amputation wound which is infected in a diabetic patient with exposed cut end of femur. After above knee amputation is seen in another photo.



Fig. 10-34: Above knee amputation for osteosarcoma of upper end of tibia.

HAND AMPUTATIONS

Loss of blood supply is the only absolute indication. Five tissue areas are observed – skin, tendon, nerve, bone and joint. If three or more tissues are damaged then amputation may be needed. In traumatised finger if skin is retained but not bone and tendons, then this skin with its blood supply can be used to cover defect locally. Any retained tissue may be used for reconstruction in the hand elsewhere like bone, tendons.

Flaps used for amputations in hand are usually long volar with scar on the dorsal aspect. Digital nerves should be cut 6 mm proximally. Digital arteries are ligated using 3 zero polyglactic acid or cauterised using bipolar cautery. Tendons are drawn distally to divide and later to retract proximally. Condyles should be trimmed when amputation is done through joints. In amputation of distal phalanx distal interphalangeal joint is preserved so that tendon functions are retained; in middle phalanx proximal interphalangeal joint is preserved. In middle and ring fingers amputations of proximal phalanx



Fig. 10-35: Anterior and posterior incision in hip disarticulation procedure.



Fig. 10-36: Incision for hindquarter amputation.

are done so that stump retained in proximal phalanx can be used for power grip of hand using active flexion by intrinsic muscles. In index and little fingers proximal phalanx amputation is waste and such stump prevents the proper pinch by thumb and fingers. So amputation through respective metacarpals is done **(Fig. 10-38)**.

Amputation of Index Finger

Here proximal phalanx is never retained. Second metacarpal is divided at its distal part proximal to metacarpophalangeal joint. Volar flap incision is placed. Dissection is started from dorsal aspect. Dorsal digital nerve and digital vessels are divided. Extensor digitorum and extensor indices tendons of index finger are divided. Dorsal and palmar interossei of 2nd metacarpal is divided; distal transverse metacarpal ligament is cut; 2nd metacarpal bone is divided obliquely 2 cm from the end (one should not disarticulate the metacarpophalangeal joint). Flexor tendons, palmar digital nerve and vessels are divided. Dorsal interossei tendon is anchored to base of 3rd proximal phalanx (of middle finger). It should not be attached to severe extensor tendon. Other muscles are sutured each other and skin is closed.

Middle and Ring Finger Amputations

Here proximal phalanges should be preserved to maintain the grip of fingers and hand. 3rd and 4th metacarpals heads are important as they provide attachment to metacarpal arch. Here transverse volar flap is used. Digital neurovascular bundles are cut. Extensor tendon/hood, flexor tendons are divided. Bone is cut near the base. Muscles/tendons



Fig. 10-37: Level of bone transaction in upper limb amputations.

are sutured. Flap should not have any tension as if tension develops it interferes with functioning of adjacent fingers also.

Wrist Amputations

Wrist amputation is preferred to forearm amputation as retained distal radioulnar joint facilitates pronation and supination.

Transcarpal amputation – It is the amputation – disarticulation between proximal and distal rows of the carpal bone complex. Long palmar and short dorsal flap with 2:1 ratio is used. Once incision is deepened all flexors and extensors are divided. Radial and ulnar arteries are ligated. Median, ulnar and radial nerves are cut. Small muscles and tendons remaining are divided. Open the transcarpal joint space and complete the amputation. Skin flap is sutured. Flexor and extensor tendons are anchored to the proximal carpal bones.

Wrist disarticulation - Long palmar and short dorsal skin flap incision which is 1.3 cm distally curved from radial and ulnar styloid processes on the palmar aspect with a connecting straight incision on the dorsal aspect. Dorsal incision is deepened; radial and ulnar arteries are ligated; joint capsule incised to enter the wrist joint; styloid processes of the radius and ulna are resected without opening the radioulnar joint. Median, radial, ulnar nerves are cut after pulling it distally. All tendons are divided at wrist joint level circumferentially. Long palmar flap is sutured back on the posterior aspect after placing a suction drain.

Forearm Amputations

In forearm amputation length as much as possible should be preserved. Distal amputation is done at the junction of distal ⅓ and proximal ⅔ of the forearm. In proximal amputations as proximal as 3.8 cm stump is retained. Both distal and proximal amputations are done with equal flaps **(Fig. 10-39)**.

Krukenberg Amputation

It is done in upper limb following any trauma. Here forearm amputation is done in such a way that it creates a gap between radius and ulna like a claw to have a hold or grip. Krukenberg amputation does not require any prosthesis. But it is cosmetically poor.


Incision for transcarpal amputation
Incision for wrist disarticulation

Wrist amputation are preferred than forearm amputation as pronation and supination are preserved



Index and little fingers
– Amputation through 2nd or 3rd metacarpals is done
Ring and middle fingers
– MCP joints are preserved
– Amputation through proximal phalanx is done

Amputations through distal or middel phalanges
– Here distal or proximal IP joint should be preserved

Fig. 10-38: Different amputations in the hand.

Elbow Disarticulation

It is done as equal flap at the level of humeral epicondyles. Posterior flap is 2.5 cm distal to the tip of the olecranon process. Anterior flap is just distal to the attachment of bicipital aponeurosis. Brachial artery is ligated medial to the biceps tendon. Triceps is divided near the tip of olecranon. Triceps is sutured to tendon of brachialis and biceps after disarticulation. Common extensor origin with remnants on the lateral epicondyle which is kept about 6 cm length is sutured to retained remnant of common flexor origin on the medial epicondyle.

Arm and Shoulder Amputations

Amputation in the arm can be done at any level from supracondylar region to axillary fold proximally. Usual/ideal level is 20 cm from acromion. Distal amputation close to condyles function like elbow disarticulation. Amputation proximal to axillary fold functions like shoulder disarticulation. Prosthesis placement for arm amputation should contain elbow lock mechanism to stabilise the joint in extension/flexion/varying positions; hernatable mechanism as a substitute for humeral rotation. Usually amputation is done as equal



Figs 10-39A to C: Various upper limb amputations.

flap with length of the flap 1½ times the circumference of the arm. Elbow lock mechanism of prosthesis if needed then amputation level should be 3.8 cm proximal to the elbow joint. Brachial artery, nerves and muscles are cut. Bone is divided using Giglie's saw. Triceps muscle is kept long to rotate across cut bone end to suture to anterior fascia or muscles **(Fig. 10-40)**.



Fig. 10-40: Upper limb amputations of both sides in a patient due to trauma. Right side he underwent forearm amputation; left side amputation at arm level.

Shoulder Amputation

It is amputation at the level of surgical neck of humerus. Incision is made anteriorly from coracoid process along the anterior border of the deltoid muscle to its insertion; then superiorly along the posterior border of the deltoid muscle to reach posterior axillary fold; two anterior and posterior incisions are joined by one more incision passing through axilla. Cephalic vein in deltopectoral groove is ligated. Deltoid and pectoralis major muscle is separated. Deltoid is retracted laterally. Pectoralis major muscle is divided at its insertion to lateral lip of bicipital groove of the humerus. Axillary vessels located between coracobrachialis and pectoralis minor are ligated individually (double ligation with transfixation) distal to the level of pectoral nerves. Deltoid muscle is divided at its insertion. Teres major and latissimus dorsi muscles are divided at their insertion to bicipital groove. Biceps, triceps and coracobrachialis are cut 2 cm distal to the line of bone division. Humerus is cut at its surgical neck. Biceps, triceps and coracobrachialis are sutured over the end of the cut humerus. Pectoralis major is swung laterally to suture to bone. Skin flaps are closed.

Shoulder Disarticulation

It is similar like shoulder amputation but at later period by keeping arm in internal rotation external, rotator muscles and posterior joint capsule is divided. Anterior aspect of the joint capsule and subscapularis and triceps are cut. At the end inferior part of the joint capsule is cut. Unduly prominent acromion process may be trimmed to achieve smooth rounded contour. Muscles are sutured into the glenoid cavity.

Interscapulothoracic Amputation (Forequarter Amputation) (Little Wood's Posterior Approach or Berger's Anterior Approach)

It is removal of entire upper limb with scapula and lateral ⅔ of the clavicle and muscles attached to it. It is done in malignancies involving scapula, upper part of humerus and near shoulder joint.

In posterior approach patient is kept in lateral decubitus position. Incision begins at medial end of the clavicle extending laterally along the length of the clavicle → over the acromion → posterior axillary fold → along the axillary border of the scapula → below the scapular angle. It is curved medially to end 5 cm from midline of the back. Flap is elevated medially to vertebral border of the scapula. Trapezius and latissimus dorsi muscles are identified and divided. Scapula is retracted away from the chest wall and levator scapulae and rhomboids are divided. Serratus anterior is divided along the vertebral border of the scapula. Brachial plexus cords are divided close to spine; subclavian vessels are ligated and divided individually; omohyoid muscle is divided. After completion of posterior dissection, anterior incision is made from the middle of the clavicle downwards along the lateral and parallel to deltopectoral groove across anterior axillary fold below and posteriorly to join the posterior incision at lower ⅓ of axillary border of the scapula. Pectoralis muscles are divided to complete the forequarter amputation. Flaps are sutured with a suction drain **(Figs 10-41A and B)**.



Figs 10-41A and B: Forequarter amputation.

REHABILITATION

Rehabilitation after amputation needs a team approach – surgeon, physiotherapist, occupation therapist, psychologist, social worker, etc.

Exercises should be started by physiotherapist from the 2nd or 3rd day after surgery. It is for both muscle setting and joint mobilisation.

Construction of a new organ of locomotion is essential and should be a planned one. Preservation of joint is more important then only of length. Level of amputation should eliminate pathology for which amputation was done.

Split skin grafting over the raw stump area is often done only as a temporary measure. Otherwise it should be avoided as it may repeatedly breakdown by prosthesis.

Joint movement especially adequate extension is a pre-requisite for good prosthesis. More than 30° fixed flexion at knee is contraindication for below knee amputation. Flexion contracture development after amputation is common and it should be avoided by proper rigid dressing (cast/posterior slab using plaster of Paris) and exercises (quadriceps exercises).

Proper tension free skin flap over the stump and thin linear scar are important for proper prosthesis placement **(Figs 10-42 and 10-43)**.



Fig. 10-42: Crutches used for lower limb amputation.

Prosthesis

Prosthesis is *the substitution* to a part of the body to achieve its optimum function (Orthroses are *supplement* for limb function). It can be *end bearing* or *side bearing*. Prosthesis can be suction type or non-suction type. *Suction type* is placed above the stump. It is better and well tolerated. *Non-suction type* prosthesis is placed at the ends. It requires additional support. Prosthesis can be *external* where prosthesis is placed outside; or *internal* where prosthesis is placed inside into the joint or structure related by open surgery method **(Fig. 10-44 and 10-45)**.



Fig. 10-43: Elbow crutches are used as support after lower limb joint/ bone surgeries during rehabilitation.

Its functions are – cosmesis, relative achievement of the function of the part, ambulation in lower limb prosthesis. Infection, pressure ulcers, joint instability are the disadvantages.

Syme`s amputation - Elephant boot.
Below knee amputation - Patellar tendon bearing (PTB) prosthesis.
Above-knee amputation - Suction type prosthesis. It is placed above the stump. It is better and well tolerated.
Hind-quarter amputation - Tilting table prosthesis (TTP) is used here or Canadian prosthesis



Fig. 10-44: X-ray showing bilateral hip prosthesis.

Prosthesis gives structural strength to the limb. Three groups of prostheses are available: (1) *Endoskeletal/modular limb:* It has got central structural tube to which socket and joints are attached and covered with shaped form to match the contour of the contralateral limb as closely as possible. The foam is covered by skin of silicone, PVC woven material. Load bearing tube is made up of carbon graphite fibre or aluminium in conjunction with titanium for highly stressed components. (*2) Exoskeleton/conventional limb:* The outer visible skin is main structural element and such limbs are hollow. Materials used are willow, plastic laminates. Upper limb prostheses are commonly exoskeletal type. (3) *Temporary pylon type:* It is used for lower limb with two self locking jointed side struts, resembling a traditional above knee calipers.

Socket of the prosthesis transmits all loads in both swing and stance phases of walk between prosthesis and stump. Socket is the most important part of the prosthesis. Women take time to adjust to



Fig. 10-45: Below knee amputee with prosthesis. It gives good range of movements, normal walk and comfort.

prosthesis as they are having less muscle bulk and more subcutaneous fat and stump volume may fluctuate due to hormonal changes during menstrual cycle and pregnancy. Sockets have got tolerant areas for increased loading pressure like ischial tuberosity or patellar tendon and intolerant areas for reduced pressure like head of fibula or adductor tendon. Polypropylene, fibre glass, aluminium alloy, plastic are different materials used for sockets. Socket is worn over a stump sock of cotton or wool. Thickness of sock for proper fitting of the socket is important. Sock is not used in suction or myoelectric sockets. Polyurethane gel layer incorporated or silicone impregnated socks are also used to reduce the skin shearing and stump sweating.

Prosthesis requires *suspension* to hold it place with a belt, cuff or sleeve. Self suspending or suction sockets are also available. Rotational alignment around the central axis of the limb, angular alignment in coronal and sagittal planes and mediolateral and anteroposterior shift must be optimised.

Prosthesis for Below Knee Amputation

Ideal below knee stump is 15-18 cm. Longer stump causes alignment problem. Minimum length is 9 cm. If after flexing the knee joint to right angle, residual tibial length more than three fingerbreadth beyond the hamstring insertion, means stump is adequate for use. Robinson skew flap is better for fitting early definitive prosthesis. Bone bridge between tibial and fibular cut ends is better for prosthesis. Excess bulbous soft tissue on the end of the stump is not good for prosthesis. Stable mobile knee joint is essential for proper prosthesis.

Patellar tendon bearing prosthesis (PTB prosthesis): Here all the weight bearing is done below knee; movement is controlled by his own knee joint. Patellar tendon is the main key weight bearing area within the socket; stump posteriorly up to the popliteal fossa is also important to provide counter pressure so that patellar tendon is kept in place. Medial and lateral paratibial areas and medial condylar flare also bear significant weight. Head of the fibula, tibial tubercle, cut ends of tibia and fibula are pressure intolerant areas. Socket should have proper relief areas to these intolerant parts.

Computer assisted designing and computer assisted manufacturing (CAD – CAM) socket is an automated processing method which fulfills all above criteria accurately with modifications. It is more comfortable and is made up of thermoplastic or laminated plastic with closed cell polyethylene foam.

Suspension for below knee amputation prosthesis is leather cuff strap above femoral condyles. Exoskeleton or endoskeleton is used. For athletics endoskeleton is preferable.

SACH (Solid Ankle Cushion Heel) foot: It is multiaxial, optimizes gait, and facilitates walking on rough ground. It needs minimal maintenance. It is preferred in old people. Energy storing foot is often used wherein ankle joint is replaced by a plastic spring **(Fig. 10-46)**.

Below knee prosthesis with a thigh corset is used in patients who cannot bear full weight below knee may be due to extensive scarring, presence of skin graft, loss of sensation, damaged knee. Leather thigh corset is joined to lower part of the prosthesis by side steel incorporating joints at knee level to transmit body weight above knee; but retaining entire knee movement and control. Ischial tuberosity is also used often additionally to high corset to minimise below knee weight bearing **(Fig. 10-47)**.

Prosthesis for Above Knee Amputation

Above knee prosthesis is heavier and bulkier and needs more energy for walk (50% more than normal). Minimum length of the above knee stump needed for prosthesis placing is 8 cm measured from the origin of the adductor longus on pubis to the cut end of the femur. *Ischial tuberosity* is the key weight bearing part for above knee amputation prosthesis. Anterior wall of the socket must extend more proximal than ischial tuberosity to prevent slipping. Rigid plastic or Ireland Sweden Newyork (ISNY) socket is used. ISNY socket contains a flexible plastic liner in a rigid carbon fibre reinforced frame. It controls the shape of the socket brim extending down the medial side of the socket as narrow strut to provide strength and attachment to knee mechanism. Contoured adducted trochanteric controlled alignment method socket



Fig. 10-46: Prosthesis used for lower limb amputation.



Fig. 10-47: Below knee amputation – prosthesis.

(CAT – CAM) has main weight bearing in ischial tuberosity but the stability of the stump is in coronal plane with a bone lock between medial aspect of the ischial tuberosity and greater trochanter.

Knee joint mechanism system is added to all above knee prosthesis. Locked prosthesis knee which flexes on sitting is used in elderly. Simple friction system with a spring or pneumatic unit to assist extension may be used. Self retaining suction socket or soft neoprene leather belt or rigid pelvic band or shoulder brace is used for suspension system for above knee amputation prosthesis.

Prosthesis for other Lower Limb Amputations

Lisfranc's and Chopart's amputations have tendency to develop equinovarus deformity. So they need ankle joint fixation/obliteration.

In Syme's amputation, person can walk for short distances without prosthesis. Heel pad fat preservation is very important. Projections of malleoli should be preserved to act as suspension. Compliant linear closely fitting polyethylene foam prosthesis is used. Sockets are end weight bearing but extends proximally to patellar tendon level. SACH foot variant is used.

Through knee disarticulation is cosmetically poor. Endoskeletal prosthesis is longer than the natural side and causes limp. Exoskeletal prosthesis with hinge knee joint shows poorer knee control. Rigid plastic socket with compliant linear inside which suspends condyles is used.

In Grittistokes amputation lateral/side weight bearing prosthesis over ischial tuberosity is used.

In through hip amputation endoskeletal prosthesis is used with ischial tuberosity as weight bearing. Socket wrap around both iliac crests in through hips and self suspending is used.

In hind quarter amputation endoskeleton prosthesis with contralateral ischial tuberosity as weight bearing point is used. Socket wrap around with shoulder brace is needed.

Prosthesis for Upper Limb Amputations

Upper limb prosthesis provides grip. But sensation and movements are limited. It is very difficult to achieve complex movements of the natural hand. Every part of the upper limb should be tried to preserve. More the preservation betters the rehabilitation outcome. Pinch grip is totally lost if there is loss of thumb. Opposition prosthesis is helpful. Even when all digits are lost wrist should be preserved for prosthesis plate suitable for pinch and oppose.

In forearm/below elbow amputation ulna length should be at least 8 cm from tip of the olecranon. This gives 4 cm flexor stump beyond the insertion of the biceps tendon. There is not much problem if radius is not preserved. Junction of middle and distal third level is the ideal level of amputation in the forearm to achieve proper function. Laminated prosthesis and socket with cotton sock is used. Prosthesis may be – body powered split look operated; or mechanical hand with active three point grip between thumb, middle and index finger; or myoelectric hand wherein electrical signals are picked up by skin electrodes placed over common flexor or extensor origin; powered wrist rotation.

Above elbow amputation should have stump length of 3 finger width below the anterior axillary fold measured with arm by side. Clearance from stump end to the tip of olecranon should not be less than 9 cm. Prosthesis for above elbow is heavier and bulkier with poor and variable functional outcome. Plastic exoskeleton functional prosthesis with plastic/leather socket over the top of the shoulder is used.

Chapter 11

Surgeries in Arterial Diseases

Surgery for arterial diseases is a complicated one. Artery is always surgically mobilised deep to the adventitia. Tunica adventitia contains fibrous and elastic tissue with periarterial sympathetic nerves. It is attached loosely to the tunica media. Tunica media contains smooth muscle and elastic tissue. Elastic tissue is more in large vessels. Tunica intima is inner thin endothelial layer that lies on an elastic tissue basement membrane which comes in contact with tunica media.

Alexis Carrel in 1912 got Nobel Prize for establishing principles of vascular suturing. Arterial repair is needed in trauma, aneurysm, and block surgery for malignancy in many anatomical places like neck, axilla, abdomen; limbs may need vascular reconstruction while doing radical surgery. All general surgeons should know the technique of vascular suturing which will be handy while operating.

PRINCIPLES IN VASCULAR SURGERY

Gentle handling of all vessels using non-toothed fine forceps is essential. Intima can get damaged without adventitial injury which may lead to thrombosis.

Artery should be mobilised adequately including proximal branches to have adequate control.

In emergency situation like bleeding speed of surgery is very important especially in major arterial injury. Rapid access, quick proximal control is essential to save the life.

Blind clamping of bleeding area in a hurry due to stress should be avoided. It may damage more or injure adjacent structures.

Resuscitation should be undertaken simultaneously by a critical care team with adequate venous accesses including a central line in major vascular bleeding.

Precision and gentle handling is essential in vascular surgery.

Vascular clamps or tapes are used at the site of an arteriotomy. While applying clamps, adjacent vein should be taken care off as thin walled vein may get injured. Vascular clamps available occlude lumen to control bleeding without injuring the vessel wall; but diseased atheromatous vessel may develop breakage of the plaque often causing embolus. Injury to the plaque itself may precipitate the thrombosis of the vessel. Clamp should be held properly or should be fixed to the drape as twisting or traction of the instrument may injure the vessel. Side clamp is also used often in major vessels like in aorta, and inferior vena cava. Prelaparotomy thoracotomy for aortic clamping or intraabdominal per laparotomy aortic clamping in torrential bleeding is often advocated as life saving procedure (Refer Chapter 8 - Principles of Surgical Management in Trauma).

Slings or tapes of different colours are used to control haemorrhage in elective vascular surgical procedure **(Figs 11-1 and 11-2)**.

Severe ischaemia with muscle death is contraindication of arterial repair. It is also better avoided in presence of sepsis.

Atraumatic but firm vascular clamps should be used. Size and type of clamps should be selected depending on need, site, size of the vessels **(Figs 11-3 and 11-5)**.

Needle holder for arterial suturing should be of high quality material like tungsten with fine points. Monofilament non-absorbable synthetic suture material is used. 3 zero to as fine as 7 zero suture materials are used. For aorta 3 zero or 4 zero is used; for iliac arteries 4 zero; for femoral artery 5 zero; for popliteal and brachial arteries 6 zero; for distal vessels 7 zero is used. Always atraumatic needle is used. Polypropylene suture material is ideally used. It is very smooth, slips through tissues easily. Brittleness, memory, knot slipping should be taken care of. Minimum 5 knots should be placed. Polytetrafluoroethylene (PTFE) sutures are very strong but knot slips easily.

Usually continuous sutures are placed as it is haemostatic. But often interrupted sutures are also placed safely especially in medium sized and small sized arteries. Single needled suture material is used for closure of longitudinal arteriotomy; double needled suture material (double armed suture with needle at both ends) is used for end-to-end closure or patch closure.

Use of magnifying loops may be necessary for fine suturing. But once habituated it is difficult to do suturing in the absence of loops.

In suturing of diseased vessels thicker suture material is used (3 zero/4 zero). Needle should be passed from within outside of the artery.

During arterial suturing, interposition of the adventitia should be avoided as it may initiate thrombosis.

End of the suture material should not be held directly by fine haemostat but with jaws protected by fine rubber or plastic tubes. Unprotected metal instruments should never be used to hold the end of fine suture.

Before application of clamps 5000 IU of heparin is given intravenously. Often half the dose is reversed using protamine sulphate but not necessarily always. Heparinised saline solution should be used for irrigation of opened vessels. 5000 IU of heparin is mixed with 500 ml of normal saline to prepare such solution.



Figs 11-1A to C: Silk slings or fine coloured rubber or synthetic slings/ loops can be used to control haemorrhage.


Haemostat
Sling
Snub
Artery
Sling

Fig. 11-2: Sling with snub also can be used to control the haemorrhage.


Satinsky vascular clamp
Tear
Artery

Figs 11-3: Satinsky vascular clamp and its use in vessel tear.


A
Soft jaw Fogarty vascular clamp

Fig. 11-4A



Figs 11-4B to D

Figs 11-4A to D: Different vascular clamps – Soft jaw Fogarty clamp; Satinsky vascular clamp.

Arteriotomy

Artery is opened (*arteriotomy*) longitudinally. *Longitudinal arteriotomy* is easier to close. Thrombus formed in suture line will be thin and longitudinal and so will not block the lumen. Longitudinal arteriotomy is easy to extend as needed. It is commonly used in thrombectomy and endarterectomy. *Transverse arteriotomy* is difficult to appose. Circular suture line thrombus formed at one place may block the lumen. Intima retracts much more than deeper layers so that often it is difficult to take suture bite. Intima may get dissected in transverse arteriotomy. But in many situations like in trauma, in surgeries of malignancies end-to-end anastomosis is needed. Often it is done using interrupted sutures especially in medium sized vessel of less than 4 mm size **(Fig. 11-6)**.



Figs 11-5A to C: Bull dog clamp and its application. It temporarily occludes vessel firmly and completely. Different sized and type of clamps-straight and curved types are available.


Longitudinal arteriotomy—which is always better
Transverse arteriotomy—is difficult to suture

Fig. 11-6: Arteriotomy is opening of artery surgically. Longitudinal arteriotomy is better than transverse one.

Sterile field, good retraction, light and access, control of bleeding are essential parts of vascular surgery. Non-absorbable monofilament polypropylene is used as a suture material. Round body needle is used for arterial anastomosis. Tapercut needle can be used if suturing is done through a thick graft.

Intima should be included in all bites during sutures except in endarterectomy. Needle should be passed from within out across the vessel to prevent intimal flap formation and dissection. When bite is taken from without in towards intima, intima should be supported firmly using fine instrument to prevent intimal separation.

Arterial ligation is done in different methods: (1) Direct ligature of the vessel using nonabsorbable or delayed absorbable sutures. Silk/polyglactic acid/thread may be used. (2) Transfixation sutures across the vessel using polypropylene or polyglactic acid sutures. (3) Over sew technique is continuous running sutures over a large vessel to have a firm safe/secure closure of the vessel **(Fig. 11-7)**.

DIFFERENT METHODS OF ARTERIAL SUTURING

All layer simple lateral sutures are used for closure of longitudinal arteriotomy. Turning intima outwards, firm uniform tension on suture line, proper spacing of the bite and optimum width of the bite are essential.


Tying ligature under clamp
Ligature
Ligature
Ligature proximal side
(2 in number)
1 cm
Single needle transfixation
Double needle transfixation
Over- sew technique

Fig. 11-7: Different methods of arterial ligation. Secure ligation is important. Type of ligation is used individually in each surgery. For definitive arteries like uterine or cystic or gastric, proper 2 or 3 ligatures should be placed. Transfixation suture also can be placed. In bulky tissues bleeding is controlled by double transfixation or over sewing method.

Closure using a venous (autologous) or prosthetic (Dacron or PTFE) patch is used in smaller arteries like brachial artery or deep femoral artery (profundaplasty). Oval or rectangular patch should be used; not elliptical one with sharp point which may narrow the artery at the corners **(Fig. 11-8)**.

End-to-end suturing of the cut ends of artery is done by Carrel's triangulation technique. Three sutures are placed; one on the posterior deeper part; one on each at equidistant on the corners. Continuous sutures are placed keeping these three stay sutures as guiding points. Everting mattress sutures also can be placed. Deepest parts of the triangulation should be sutured first. Larger arteries are sutured with continuous sutures; medium and small arteries are sutured with interrupted sutures. Whether continuous or interrupted sutures are used, triangulation should be done at the beginning **(Figs 11-9 and 11-10)**.

Single stitch, end-to-end suturing of large artery can be done by placing continuous sutures beginning from the nearest cut end progressing posteriorly towards other cut end and commencing later on anterior aspect to complete the end-to-end suturing. Double needle suture may be used which is started at midpoint posteriorly proceeding on either sides towards in front to complete the end-to-end suturing.

Inlay method of suturing is usually practiced in reconstruction of abdominal aorta using graft wherein horizontal mattress sutures are placed with needle passing from graft to aorta. Parachute technique is a method where double end sutures are placed without initial tying of the knot.



Figs 11-8A and B: Simple suturing of the vessel; often venous or prosthetic patch may be required in smaller arteries.



Fig. 11-9: Technique of end-to-end suturing.



Carrel's triangulation technique with three stay sutures

Continuous sutures

Interrupted sutures

Fig. 11-10: Carrel's triangulation technique in arterial suturing.

End-to-side suturing of the arteries is done in arterial bypass procedures with oblique stoma which is twice the diameter of the artery/graft to have a spatula end with cobra head look.

Four quadrant technique with double ended suture at the heel of the anastomosis; the end with acute angle of the anastomosis is called as *heel* and the end with obtuse angle is called *as toe* of the anastomosis.

Parachute end-to-side suturing is also done whenever there is poor access or poor visualisation; is done using double ended vascular running stitches continuously which later is pulled tight for approximation of the vessel/graft parts **(Fig. 11-11)**.



Initial anchoring sutures at 'heel' and 'toe' ends

- Suture begins at both sides of the 'heel'; then at the end at 'toe'
- Near the 'toe' interrupted sutures can be placed

End to side four quadrant technique

End to side parachute technique

- It is done in difficult places where access and vision at depth is poor
- Continuous running sutures are initially placed and only later tightened

Figs 11-11A and B: Different end-to-side suturing technique. Note the *heel and toe end* of the arterial suturing.

In an endarterectomy special ***Kunlin suture*** is inserted to prevent intimal dissection. Suture initially passed from outside to inside through endarterectomised part then from inside out through atheromatous part to tie outside. It fixes the intima properly **(Fig. 11-12)**.

In calcified artery often additional fine adventitious sutures may be required. In a friable artery suture holding may be inadequate; so to hold sutures and to prevent haemorrhage, additional *buttressing under the sutures* can be done using Dacron in larger artery or muscle piece in small artery **(Fig. 11-13)**.


Atheroma in the edge of the artery
Arteriotomy for endarterectomy
Atheroma in the edge of the artery
Endarterectomised part of the artery

Kunlin suture is placed from outside inside of endarterectomised part; then from inside out of the atheroma edge of the artery

Fig. 11-12: Kunlin suture.


Dacron or muscle piece buttressing
Interrupted sutures (Polypropylene)

Fig. 11-13: Buttressing under suture is done using Dacron or muscle piece.

Nonsutured anastomosis is a new method used in aorta during surgical treatment of aneurysm to keep in place of the synthetic graft. A rigid Dacron covered polypropylene ring is passed using an applicator within the lumen. Tapes are ligated outside the aorta also.

Peripheral aneurysms are approached by different methods – Matas aneurysmorrhaphy; excision of aneurysm and Dacron graft; ligation and exclusion using vein; excision of aneurysm and bypass using autologous vein **(Figs 11-14 and 11-15)**.



A Matas aneurysmorrhaphy for saccular aneurysm



B Excision and graft in fusiform aneurysm (Dacron graft)

Figs 11-14A and B


C Ligation and exclusion using autologous vein by-pass graft
D Excision of aneurysm and by-pass using autologous vein graft

Figs 11-14C and D

Figs 11-14A to D: Different surgical approaches for managing peripheral aneurysm. Basic principles are similar – meticulous dissection proximally and distally; heparinization on table; proper clamping of artery on either ends; right selection of the technique; avoidance of sepsis; synthetic (Dacron or PTFE) or venous graft placement; proper postoperative positioning; prevention of postoperative sepsis and thrombosis.

ENDARTERECTOMY

It is a procedure where diseased atheromatous plaque with intima is excised through an adequate arteriotomy. It is often called as *reboring/disobliteration*.

It is done in short stenotic lesion commonly; often it is done in long arterial blocks where graft is contraindicated. It is done commonly in *carotid artery*.

Preoperative *angiogram* is a must to evaluate exact site, extent and nature of the arterial stenosis.

Procedure

Artery is exposed with proper incision. Patient is heparinised. Arterial clamps are applied on both ends. Longitudinal incision is made over the artery using No. 15 blade. Incision deepened with same blade until fresh blood oozes out. Incision is further extended on either ends using *Pott's* scissor.

Arteriotomy edges are held and lifted using fine instruments by surgeon and assistant. A plane between arterial wall and diseased intima with plaque is created.



Fig. 11-15A


Radial artery aneurysm dissected
B
Radial artery ligated proximal to aneurysm
Radial artery ligated on either sides of the aneurysm
Radial artery on either sides ligated with excision of aneurysm
Excised aneurysm specimen
C

Figs 11-15A to C: Radial artery aneurysm. It is excised with ligation of the artery proximally and distally. Usually there is no need to repair as collateral circulation through ulnar artery and palmar arch will maintain the distal circulation.

Dissector is passed at distal end around the plaque which is then continued proximally. Proximal end of the plaque is cut circumferentially. Proximal to this point of cut, intima should never be lifted off and if done it will cause flap dissection as complication. Then distal end of the plaque is cut taking similar care like done for proximal part. In the distal part often it is necessary to place few interrupted anchoring sutures from endarterectomised part to nonendarterectomised part. Usually removal of the plaque is done from proximal to distal part of the artery. Only in difficult situations like in carotid endarterectomy (often), it is done from distal to proximal part **(Fig. 11-16)**.

Each clamp is released once and reapplied to check the forward flow and backflow.

Arteriotomy is closed using 3 zero polypropylene in large artery, 5 zero polypropylene in small arteries. Artery lesser than 5 mm is closed with a venous or synthetic graft patch to prevent re-stenosis at the site. A holding single interrupted suture is placed first at proximal site. Then closure of arteriotomy is done using continuous sutures from *distal to proximally*.

Always proximal vascular clamp is first released to empty the air from the arteriotomy segment. Then distal clamp is released. Artery distal to the arteriotomy is palpated for adequate pulsation. Distal part of the arterial wall is inspected for few minutes for possible formation of bluish discoloration as an evident of intimal flap lift distally. Here distal pulse is absent but pulsation may be well felt over dissected intimal flap part.

Postoperative Management

Closed suction drain is placed. Blood pressure monitoring to prevent/control hypertension is needed so that to reduce hyperperfusion syndrome. Heparin should be given for 5–10 days. Later warfarin may be needed. Infection should be prevented. If infection develops proper antibiotics should be given. One should watch the area for haematoma. Distal pulse warmness should be checked at regular intervals. Postoperative Doppler should be done for assessment. Immobilisation of the part and positioning is required for 2 weeks.

Problems and Complications

Intimal flap dissection is an on table problem. Procedure may be insufficient and on table decision may be taken to change over to graft interposition.

Haematoma, torrential bleeding, infection, reblock, thrombosis formation and suture breakdown are the complications.

Semiclosed Endarterectomy (Fig. 11-17)

It is used in lengthy occlusions of the artery. Initial heparinisation → clamps on either sides →arteriotomy distal to distal part of the occluded part → extension of the incision towards distal occluded part → dissection and cutting of the distal part of the plaque → passing of the loop endarterectomy stripper around the plaque towards proximal part (often arc stripper is also used) → plaque is broken gently using artery forceps or using thumb and fingers → care must be taken that outer wall of artery is not damaged → plaque is gently removed using loop. If fragments of plaque are left in the wall, which can be confirmed by feeling, can be removed using Martin's thrombectomy forceps. Undue traction or more should not be executed as it may injure the vessel wall. In such difficulties another arteriotomy may be made over the proximal end of the occluded artery. Arteriotomy is closed from distal end to proximal end. When two arteriotomies are present, proximal one is closed first, then the distal one.

Wiley's Eversion Endarterectomy (Fig. 11-18)

Here artery is transected completely (transversely) so that right plane between diseased intimal plaque and media is created


Proximal end
Distal end
Proximal end
Distal end
Proximal end
Distal end
Atheroma plaque adherent to intima
Vascular clamps applied
No 15 blade is used for arteriotomy
Cutting with Pott's scissor
With Watson Cheyne dissector plane deep to intima is created
Dissection around near proximal end
Cutting intima proximally
Cutting intima distally
Endarterectomy plaque
Anchoring sutures distally to prevent intimal flap
Stay suture proximally. Later continuous suture from distally
Completion of arteriotomy suturing
Release of proximal clamp first
Release of distal clamp next

Fig. 11-16: Open endarterectomy technique.

circumferentially. Once plane is created all around arterial wall is everted to exteriorise the plaque completely. Everted artery is reduced later. Cut ends of the artery is sutured using polypropylene interrupted sutures with bite taking from outside-in of the endarterectomised segment to inside out of the unendarterectomised segment.


Proximal end
Distal end
Lengthy occlusion
Arteriotomy along the distal part of the block
Thrombus plaque is dissected all around
Loop stripper is passed and migrated proximally
Using artery forceps inner plaque is broken gently and plaque is removed

Fig. 11-17: Semiclosed/semiopen endarterectomy.


Proximal end
Distal end
Occluded segment with clamps
Transection/transverse arteriotomy is done
Eversion of adventitia and media off the plaque
Plaque dissection extended proximally and plaque is removed
Arteriotomy is sutured from outside in to inside out of distal normal vessel—interrupted sutures

Fig. 11-18: Eversion endarterectomy technique.

CAROTID ENDARTERECTOMY

Indications

- Asymptomatic carotid stenosis more than 60% by angiography or more than 70% on Duplex ultrasound.
- Symptomatic carotid stenosis with cerebrovascular accident/transient ischaemic attacks/amaurosis fugax with > 50% block.

Carotid endarterectomy *prevents development of stroke* for significantly long period.

Evaluation

Blood parameters, lipid profile, duplex ultrasound are the usual needed investigations. Duplex ultrasound is sensitive method of assessing the carotid artery. Angiogram is done only in selected patients with re-stenosis, neck irradiation, earlier neck lymph node block dissection, and atypical cases.

Procedure

Patient is placed in semi-sitting position with round pillow under shoulder to extend the neck. Head is rotated towards opposite side. Arm on the same side is tucked over the chest or side of the table. Ear lobe, mastoid, mandible, sternal notch and clavicle area should be prepared and exposed as landmarks.

Procedure is done under general anaesthesia with routine or selective shunting as needed. Intraoperative EEG monitoring is essential. Regional anaesthesia is often used.

Incision is oblique one along the anterior margin of the sternocleidomastoid muscle. Transverse incision is also often used. But it is not useful in higher lesions. Platysma once divided; medial margin of the sternomastoid muscle is dissected from its upper tendon part to the level of the omohyoid. Internal jugular vein is dissected by sharp dissection along its medial edge. Common facial vein, middle thyroid vein and hypoglossal veins are ligated carefully. Sternomastoid and IJV are retracted laterally. Ansa cervicalis is cut near its origin. Superior thyroid artery is dissected near its origin. Common, external and internal carotid arteries are dissected all round circumferentially at the confluence. Each artery is held with vascular tape (sling with snub). Superior thyroid artery is held with a loop of silk suture. Hypoglossal nerve is identified by tracing the ansa hypoglossal part above. It is further mobilised after ligating the occipital and sternomastoid arteries. Digastric muscle is divided only when there is a need to expose distal part of the internal carotid artery. Internal carotid artery *should be exposed adequately when needed prior to arteriotomy*. It is difficult to expose internal carotid artery distally once arteriotomy is already done.

Internal carotid artery distally is occluded with a vascular clamp/clip. Routine or selective shunting of the carotid (internal) artery is done. Longitudinal arteriotomy is done → plaque is dissected off the media → proximal portion is first dissected circumferentially → extended towards distal part of the internal carotid artery → eversion endarterectomy is done in external carotid artery plaque → heparinised saline irrigation of the bed of the opened artery is done → with fine forceps small pieces of plaques are removed → Dacron or bovine pericardium patch graft is placed over the defect → sutured to vessel using polypropylene suture material 4 zero or 5 zero. Prior to completion of suturing near the end shunt is removed and back bleed is allowed. First blood flow is allowed to external carotid artery then only internal carotid artery.

Nasotracheal intubation and mandibular subluxation may be needed in difficult cases.

Risk and Problems

It is not possible to do endarterectomy for most distal part of the internal carotid artery in the neck.

Perioperative stroke risk is 1.5%.

Hypoglossal nerve injury, non-recurrent laryngeal nerve (anomaly) injury (it is mistaken for ansa cervicalis and is cut), superior laryngeal nerve injury, marginal mandibular branch (facial nerve) injury, glossopharyngeal nerve injury and spinal accessory nerve injury are neurological complications in relation to cranial nerves.

Distal end of the stenosis should be assessed properly as distal exposure is often difficult. It is quite difficult to expose unusual high bifurcation of the carotid.

Postoperative bleeding, myocardial infarction and carotid re-stenosis are other complications.

Eversion Carotid Endarterectomy

It is done in well localised severe lesions. Type I transection is done as oblique near vertical cut when main block is in the internal carotid artery. Type II transection is done as oblique near transverse cut when main block is in common carotid artery. Shunt is needed during the procedure. After endarterectomy end to end anastomosis is done often with a synthetic patch.

AORTOILIAC THROMBOENDARTERECTOMY

Open (Dos Santos), semi-closed, eversion methods are used. Often aortofemoral bypass has replaced this procedure. Even though commonly performed procedure is bypass graft in cases with localised disease at distal aorta and iliac arteries, thromboendarterectomy is also done. In a *contaminated field* endarterectomy is *better* than graft.

Evaluation is done with duplex ultrasound, angiography of entire abdominal aorta, visceral and renal branches. Both anteroposterior and lateral views are essential as origin of the celiac and superior mesenteric arteries and posterior aortic plaques are well identified by lateral views. To assess the extent of the disease oblique films are taken. Distal tibial films are taken to check distal run off. Pull back pressure gradient more than 10 mm Hg after injection of vasodilator like papaverine suggests significant block. Transfemoral Seldinger method is used for both angiogram and pressure gradient assessment. If there is complete block, transbrachial or lumbar transaortic approach may be used. Arterial digital subtraction angiography can be used. Venous DSA is less informative. Systemic assessment like of renal, cardiac and respiratory should be done.

Prophylactic antibiotic is given intravenously one hour before surgery.

General anaesthesia with epidural supplements is used.

Approach: Retroperitoneal standard or transabdominal approach is used.

Procedure

Left side 45° elevated position is used. Break table (reverse flexion/jack knife) position will give additional access.

↓

Incision is from a point just medial to the lateral margin of the left rectus muscle just below the umbilicus level extending laterally to the tip of the 12th rib. Incision is deepened to superficial fascia and fat.

↓

Anterior rectus sheath is incised to expose rectus muscle. Rectus muscle is either transected or retracted medially. Care should be taken not to open the peritoneum.

↓

External oblique, internal oblique and transverse abdominis muscles are cut in the line of incision. Glistening peritoneum is visualised. It is swept/pushed using gauze or finger and retracted medially. Psoas major muscle and genitofemoral nerve is identified **(Fig. 11-19)**.

↓



Fig. 11-19: Extraperitoneal approach for aortoiliac segment.

Inferior mesenteric artery is identified, ligated and divided. Aorta and iliac arteries are mobilised properly along full/adequate length. 3 cm proximal and 3 cm distal to the level of occlusion should be isolated.

↓

Common, external and internal iliac arteries are dissected; middle sacral and lumbar arteries are identified.

↓

Vascular clamps are placed at all ends.

↓

Arteriotomy incisions are made in the aorta and iliac arteries in different methods. (A) Here two incisions are used – (1) From right of the inferior mesenteric artery extending down along the origin of right common iliac artery. (2) Second incision is separately along the left common iliac artery. This is done to avoid injury to preaortic autonomic plexus which is located to the left side of aortic bifurcation. (B) In this type three separate arteriotomies are made in the aorta and both common iliac arteries. Arteriotomy incisions in iliac arteries should extend beyond their bifurcations.

↓

Endarterectomy is begun at proximal part using a spatula circumferentially; then extending distally along the diseased segment of the artery.

↓

Initially it is cut transversely at proximal point; later at distal point using Pott's scissor.

↓

Endarterectomised part of the vessel is inspected, loose debris and thrombus are removed, and part is irrigated with heparinised saline solution.

↓

Often intima at distal cut margin should be anchored to the artery using non-absorbable polypropylene interrupted mattress sutures which are tied outside. It is done to prevent *intimal flap* dissection.

↓

Repeated irrigation using heparinised solution is needed.

↓

Arteriotomies are closed using continuous 4 zero polypropylene sutures from proximal to distal. Vascular clamps are released just prior to last suture bite; first distal clamp is released then proximal clamp is released.

↓

Arteriotomy often is closed using Dacron or PTFE (Polytetrafluoroethylene) graft as a patch.

↓

Once after release of vascular clamps if bleeding points are found over the sutured arteriotomy, then it is controlled by interrupted 6 zero sutures/liquid thrombin/collagen/light pack and pressure **(Figs 11-20A to I)**.

Anticoagulant effect is reversed using protamine sulfate.

Postoperative Care

ICU monitoring for 2 days. CVP line, pulmonary artery catheter line, radial artery line, urinary catheter is a must.

Complications

- It is technically more demanding. It is done in only selected localised disease.
- Bleeding can occur which occasionally requires re-exploration. Hypovolemia is common.


Position: Left side elevation with a rolled towel underneath
Incision: From just inside to lateral margin of the rectus extending upwards laterally
A
Skin
Subcutaneous fat
External oblique muscle
Internal oblique muscle
Transverse abdominis
Rectus abdominis muscle
Peritoneum (Should not open)
Transversalis fascia with peritoneum
B
Peritoneum- reflected towards right
IVC
Abdominal aorta
Inferior mesenteric artery
Common iliac artery
Left renal vein
Kidney
Perinephric fat with Gerota's fascia
Psoas major muscle
Left ureter
Genitofemoral nerve
C
IVC
Aorta
Left renal vein
Vascular clamp to aorta
Renal artery
Gonadal artery- clamped with bull dog
Inferior mesenteric artery- ligated
Common iliac artery
External iliac arter—clamped
Internal iliac artery—clamped
D

Figs 11-20A to D



Two incisions

1. First incision is on the aorta along the right of origin of the inferior mesenteric artery extending along the right common iliac upto external iliac artery
2. Second arteriotomy incision along left common iliac artery

Three incisions

Here three separate incisions—one in the aorta and one each in common iliac arteries upto external iliac artery—1, 2 and 3

E



Intima with thrombus (endarterectomy) is separated from media throughout the length of the arteriotomy incisions both proximally and distally and cut across on both ends.

F



After extraction of endarterectomy specimen, mattress anchoring sutures at the distal end intima with knots outside—are placed to prevent intimal flap.

G

Figs 11-20E to G



Closing the arteriotomy using continuous polypropylene 4 zero sutures.

Completed closure of arteriotomy with release of clamps.

H



When the lumen is narrow arteriotomy can be closed with PTFE/Dacron vascular graft patch to widen the lumen.

I

Figs 11-20H and I

Figs 11-20A to I: Technique of aortoiliac endarterectomy.

- Rethrombosis and failure is also a known complication.
- Distal ischaemia and gangrene can occur. Doppler study of limbs is done to assess the distal perfusion.
- Embolism due to atheroma dislodged when it occurs with intact pulse needs embolectomy.
- Injury to aortic nerve plexus may cause impotence but it is less common.
- Wound infection, haematoma and abscess formation are other complications. Progressive haematoma needs re-exploration.
- *Colonic ischaemia* mainly left sided (sigmoid) can occur. Only mucosal ischaemia is treated by nasogastric aspiration; deeper level ischaemia needs laparotomy and resection.

ARTERIAL SUBSTITUTES

Ideal arterial substitute is not yet developed. Ideal arterial substitute should be strong, durable for patient's life, biocompatible, non-thrombogenic, should have resistant for infection, easily available, should have a long-term patency rate and elastic property of normal artery.

Features of ideal graft

Strong
Durable for patient's life
Non-thrombogenic
Biocompatible
Resistant to infection
Flexible
Should maintain long-term patency
Should have elastic property of normal artery
Should be leakproof on restoration of blood flow
Should not chemically or physically degenerate
Should not cause any abnormal reaction to surrounding tissues
Should not occlude when flexed
Should not damage blood contents

Carrel and Guthrie first did venous autograft into arteries of dogs. They did extensive histological study of viable and non-viable grafts. Lexer in 1907 used saphenous vein for axillary artery repair. Murray started to use intraoperative heparin. Enaz Moniz and dos Santos originated technique of arteriography. Gross and his colleagues in 1948 started to use viable arterial allografts. Later it was found that as far as graft is considered tissue viability is not essential for success of graft take up.

Classification of Arterial Substitutes

1. Arterial allograft – Not used.
2. Arterial autograft – Internal mammary artery (common), internal iliac artery.
3. Arterial xenograft – Bovine carotid artery graft – not used.
4. Venous autograft – Long saphenous vein (common), small saphenous vein, basilic vein, cephalic vein.
5. Venous allograft – Umbilical vein graft.
6. Prosthetic grafts:
   a. Textile grafts -
      - Dacron graft – Knitted or woven or crimping or velour types.
      - Teflon graft – Knitted or woven or crimping or velour types.
   b. Non-textile semi-inert polymer graft -
      - ePTFE graft – Expanded polytetrafluoroethylene graft.

Arterial Allograft

As aorta contains more collagen and elastin long-term graft function is more than in femoral artery which contains more smooth muscle. Arterial allograft loose endothelium rapidly with formation of platelet fibrin coagulum. Over the years graft becomes less cellular with thinning of the wall. Late thrombosis, calcification, aneurysm formation and rupture can occur. Arterial allografts are not used now.

Arterial Autografts

Arterial autografts has the *advantages of* intact blood supply, resistance for infection, maintenance of flexibility, absence of degeneration, growth potential when used in pediatric age group. Wylie in 1965 first used arterial autograft. There is very less incidence of intimal thrombosis in autograft. Small initial thrombus formed around suture line will get absorbed in 20 days.

Inner most 500 µ thickness of arterial wall gets its nutrition directly from luminal blood through diffusion. Thickness outer to this level gets its blood supply through vasa vasora, a complex system derived from arterial side branches. So in arterial autograft few side branches should be retained.

Arterial autografts are used in *coronary artery bypass*, renal artery bypass (in pediatric age group), in places where graft is needed in infected field.

Internal mammary artery is the commonest and *preferred autograft* used. Internal iliac artery can be used in pediatric age group and in adults if it is not atherosclerosed.

Internal mammary artery is commonly used for CABG (coronary artery bypass graft). It shows superior long-term patency (95%) and is very suitable in emergency situation. Both internal mammary arteries are used commonly. They are dissected from chest wall retaining wide pedicle. *Distal internal mammary artery anastomosis* is done as end-to-side into the coronary artery using 8 zero polypropylene interrupted sutures. *Sequential internal mammary artery grafting* is also done when more than two anastomoses are needed. Free internal mammary arterial graft also can be used wherein internal mammary artery is cut at its origin and is sutured to proximal part of the aorta if extra length is needed. A combination of bilateral internal mammary artery graft with sequential and free mammary graft is called as *complex mammary grafting.*

Internal mammary artery (internal intercostal) arises from inferior aspect of the first part of the subclavian artery 2 cm above the sternal end of clavicle. It runs downwards, forward and medially behind sternal end of clavicle, internal jugular vein, brachiocephalic vein, first costal cartilage and phrenic nerve. Below and behind the first costal cartilage artery runs vertically downwards upto 6th intercostal space. Here it is related in front to pectoralis major, upper six costal cartilages, external intercostal membrane, internal intercosatl muscles and upper six intercostal nerves. Behind it is related to endothoracic fascia and pleura upto 3rd costal cartilage; further it is separated from pleura by sternocostalis muscle. At 6th intercostal space it divides into two terminal branches as superior epigastric artery and musculophrenic artery. Below 3rd intercostal space artery is accompanied by two venae commitantes which join together to form internal mammary vein which runs on the medial side of the artery to join brachiocephalic vein. Internal mammary lymph nodes are located along the artery. Its branches are – pericardiophrenic artery, mediastinal arteries, and two anterior intercostal arteries (upper and lower) for each upper six spaces, perforating branches and terminal branches **(Figs 11-21 and 11-22)**.

Arterial Xenograft

Xenograft from other species causes immense immunologic reactions leading to graft rejection. A modified xenograft (*Rosenberg*) is derived from *bovine carotid artery* which is treated by proteolytic enzyme ficin. Ficin removes smooth muscle and elastic tissue retaining collagen tube which has got equal tensile strength and is nonantigenic. This collagen tube is tanned with dialdehyde starch. But this graft has got high rate of aneurysm formation (6%) and high infection rate (6%) and patency rate is 40% after 6 years. So this type is also inferior to autograft and synthetic grafts.

Venous Autograft

Saphenous vein autograft is commonly used autograft as arterial substitute successfully. Normal ***long saphenous vein*** in adult is 60 cm in length and thigh part is a single trunk. 8-12 valves of LSV is mainly located at below knee level. Its average diameter is 5.5 mm after gentle distension in thigh. Minimum diameter required for grafting is 4 mm. In 10% of individuals LSV is too small for grafting; in another 20% patients it cannot be used due to phlebitis, varicosity, and prior surgery. So only in 70% of people it is available for grafting. In 30%


Thyrocervical trunk
Subclavian artery
Internal mammary artery
Clavicle
1st
2nd
3rd
4th
5th
6th
Superior epigastric artery
Musculophrenic artery
Musculophrenic artery
Internal mammary/thoracic artery is the commonest arterial autograft used

Fig. 11-21: Arterial autograft. Internal mammary artery is commonly used.


IMA
Coronary artery
(A) Distal internal mammary artery anastomosis– end-to-side.
IMA
Coronary artery
Coronary artery
(B) Sequential IMA anastomosis– side-to-side.
Aorta
IMA
Coronary artery
(C) Free mammary graft – Aorta to IMA—side-to-end with sequential anastomosis.
Aorta
Left IMA
Right IMA
Coronary artery
(D) Complex mammary graft – Bilateral IMA to aorta end-to-side; sequential anastomosis.
IMA: Internal mammary artery

Principles:
- 1.5 mm arteriotomies
- 8 zero polypropylene
- 8 stitch technique
- Anastomosis starts on the opposite side/end of the surgeon
-Interrupted/running sutures

Fig. 11-22: Technique of internal mammary artery graft to coronary artery.

of non-available LSV category, small saphenous vein, basilic vein or cephalic vein can be used as a graft. But these alternate veins are not as good as LSV. Saphenous vein graft is used for small and medium sized arterial replacement – mainly in coronary artery bypass and lower limb bypass surgeries (superficial femoral and popliteal). *Standard reversed saphenous vein graft or modified in situ saphenous* vein grafts may be used. It is excellent for coronary and femoropopliteal artery bypass.

Carrel observed that after vein graft there will be marked subintimal and medial hyperplasia of the venous graft called as 'arterialisation' of vein graft.

Venous Allograft

Saphenous vein allograft was not successful. ***Umbilical vein allograft*** is successful after glutaraldehyde tanning of the graft which increased collagen wall strength and also made graft nonantigenic. Complications are aneurysm formation, separation and infolding of inner lining causing luminal narrowing. Its only advantage over prosthetic graft is availability and cost.

Prosthetic Grafts

Voorhees in 1952 developed nylon related porous textile graft Vinyon N and used as arterial replacement in animals.

Later Dacron and Teflon synthetic grafts were evoluted. Dacron looses up to 10% of its tensile strength. Teflon does not lose its tensile strength **(Figs 11-23 and 11-24A and B)**.



Fig. 11-23: Arterial prosthetic Dacron graft placed to aorta.

Prosthetic grafts are manufactured by weaving or knitting multifilament yarns of Dacron or Teflon.

Woven type is compact one with small interstices and low porosity. Woven graft has difficult in handling **(Fig. 11-25)**.



Fig. 11-24A



Fig. 11-24B

Figs 11-24A and B: Dacron arterial graft placement.



Fig. 11-25: Woven Dacron graft.

Knitted graft is more porous and needs preclotting prior to use. It *should not be used* in patients with platelet and coagulation defects, hepatic disease, and ruptured aortic aneurysm. Knitted graft has got better handling ability due to its softness and it does not fray while cutting **(Fig. 11-26)**.

Crimping textile grafts (1955) are available now which shows greater flexibility without kinking. But it may reduce the graft diameter and may be thrombogenic **(Fig. 11-27)**.

Velour surface graft (1960) was evoluted later with loops of yarn extending perpendicular to graft surface. It provides a better preclotting and gives scaffold for fibroblast proliferation and so makes graft firmly adherent to surrounding tissues **(Fig. 11-28)**.

Both knitted and woven grafts are commonly used. Surgeons prefer to preclot both grafts.

Preclotting the ***non-coated knitted*** or woven Dacron graft is done to seal the graft and to prevent leak and to create a smooth lining at graft - blood interface. This step is not necessary for PTFE or newer grafts. Preclotting is done by collecting 100 ml of patients' blood prior



Fig. 11-26: Knitted Dacron graft.



Fig. 11-27: Dacron crimping graft.



Fig. 11-28: Velour graft.

to heparinisation from aorta or IVC using a syringe which is collected in a bowl. Selected graft is clamped at one end; from other end fresh blood collected in the bowl is forced into the graft using a fine catheter or syringe until leakage from the pores stops. Later graft is flushed using heparinised saline. Deposited platelet fibrin layer in the interstices on inner part of the graft after implantation is slowly replaced by fibrous in growth. Cooley described a *modified version of pre-clotting* of the prosthetic graft. Knitted Dacron graft is soaked with patient's own platelet rich plasma and which is steam autoclaved for 5 minutes to produce a blood impervious graft in which denatured protein is slowly resorbed.

Expanded Polytetrafluoroethylene Graft (ePTFE)

Soyer (1972) first used ePTFE as arterial graft. PTFE is a fluorocarbon polymer manufactured by paste extrusion method containing solid nodules with interconnecting small fibrils. Standard pore size presently in use is 17 μ. Fluorine gives high electronegative surface charge to the polymer to prevent thrombosis. It is mainly used in lower limb arterial disease **(Fig. 11-29)**.


Cut ends of femoral artery
PTFE graft proximal anastomosis
PTFE graft distal anastomosis—completed

Fig. 11-29: PTFE graft. PTFE graft used in the lower limb in a patient.

Complications of Graft

Neointimal fibrous hyperplasia at suture lines of the graft is due to surgical trauma, PDFG, arterial smooth muscle proliferation.

Graft infection incidence is 2%. It is more in lower limb graft than abdominal graft. Peroperative cephalosporin administration reduces the rate of graft infection. If infection occurs graft should be removed and revascularisation is achieved using a saphenous vein graft.

Graft failure is rare but can occur. It is due to fibre degeneration, manufacturing defect, diffuse dilatation of graft (is due to expansion of the knit in knitted Dacron).

Anastomotic false aneurysm (3%) occurs just adjacent to suture line towards host artery. It is tearing of the artery adjacent to suture line due to mismatched graft artery compliance, improper suture placement, and arterial degeneration. There will be partial or total separation of the graft from the host with blood collection in a covering of the fibrous capsule. It eventually will rupture/may cause thrombosis and embolism. Treatment is graft–artery re-anastomosis with insertion of additional piece of graft **(Fig. 11-30)**.


Graft
Artery- graft anastomosis
False fibrous capsule
Tear occurs in host artery adjacent to suture line
Pseudoaneurysm (anastomotic)

Fig. 11-30: Anastomotic pseudoaneurysm can occur at disrupted suture line.

Basic Principles in Arterial Graft Surgery

Type of surgery should be selected properly based on site, extent and severity of block.

Site for inflow anastomosis should be having adequate inflow of blood. Site of outflow anastomosis is also important to accommodate the graft blood flow. If it is too diseased graft failure can occur.

Type of graft selected is also important. Size, quality, length, preclotting should be proper.

Adequate imaging in the form of Duplex scan, angiogram, CT angiogram and MR angiogram (contrast or non-contrast) are needed. In critical limb with extensive arterial involvement contrast may precipitate total block and gangrene and in such situation non-contrast MR angiogram is ideal to delineate the site. However, much hope cannot be given to the patient as far as limb salvage is considered.

AORTOFEMORAL BYPASS GRAFT

It is commonly used technique at present. Aortofemoral bypass is preferred as often block extends to distal iliac arteries. Dacron or PTFE is commonly used. Knitted/woven Dacron when used needs preclotting before use. Collagen impregnated Dacron/PTFE does not require preclotting.

Transperitoneal approach: Transabdominal/transperitoneal approach is ideal for graft placement. Lengthy midline incision from xiphisternum to pubic symphysis is needed. Femoral arteries are exposed from above the level of the inguinal ligament down, below and beyond the level of the common femoral bifurcation. When there is a need to expose the external iliac artery additionally, it is achieved by extending the femoral incision above, laterally curving parallel to inguinal ligament with or without cutting the inguinal ligament.

↓

Omentum and transverse colon are pushed upwards; small intestine is shifted towards right; duodenojejunal junction is exposed properly. Retroperitoneum is incised adjacent to duodenum lateral to fourth part of the duodenum. Duodenum is mobilised to expose the aorta. Lymphatic vessels are ligated. Proximal aortic clamp is placed here *from left side* after heparinisation and after clamping distally at femoral vessels.

↓

Proximal dissection is done up to the level of renal vein. It is identified by left renal vein crossing the aorta *in front* to reach IVC. Occasionally as a variation left renal vein may be retroaortic. Left renal vein should be mobilised adequately without division by ligating left gonadal and left adrenal veins. Rarely in high lesions left renal vein may need to be divided at its entry into the IVC. In such occasion ligation of left gonadal and left adrenal veins should be avoided as these two veins are essential to drain left kidney.

↓

Inferior mesenteric vein is mobilised and retraced away from the field.

↓

Infrarenal aortic dissection is done up to 3 cm beyond the block or level of graft anastomosis. During dissection care should be taken not to injure IVC and lumbar veins. Lumbar arteries can be ligated if needed.

↓

Preclotting the noncoated knitted or woven Dacron graft is done to seal the graft and to prevent leak and to create a smooth lining at graft - blood interface. This step is not necessary for PTFE or newer grafts. Preclotting is done by collecting 100 ml of patient's blood prior to heparinisation from aorta or IVC using a syringe which is collected in a bowl. Selected graft is clamped at one end; from other end fresh blood collected in the bowl is forced into the graft using a fine catheter or syringe until leakage from the pores stops. Later graft is flushed using heparinised saline.

↓

Retroperitoneal *tunnel* is made by blunt finger dissection extending down into the femoral incision. This tunneling should pass *behind ureter* and *in front* of iliac artery. Umbilical tape on each side is placed along the length of the tunnel.

↓

Intravenous heparin is injected 150 units/kg body weight to anticoagulate the patient. First distal part of the artery is clamped to prevent embolism; then proximal part.

↓

Proximal anastomosis: End-to-end or end-to-side anastomosis can be done. *End to end is preferred* as it causes uniform blood flow with less turbulence and stable accurate suturing is possible. It also allows proper inspection of the proximal part with limited endarterectomy at proximal site which gives more stable suture line. Aorta is transected between two vascular clamps at the site of anastomosis; distal cut end of the aorta is sutured with double layer 4 zero polypropylene continuous sutures – first like a sewing machine method; second as a oversewing/over and over sutures at cut edge (like closure of duodenal stump in gastrectomy).

↓

Graft should be of *same size or smaller than the size* of the aorta. Ideally it should not be larger. 4 zero polypropylene continuous sutures are placed posteriorly and anteriorly. Needle bites should be smooth, single stroke, precise with needle piercing the aorta *from intimal side towards adventitia*; in the graft *from outside towards inside.* Interrupted mattress sutures are often used but it is not popular.

↓

Once proximal anastomosis is completed, graft is filled with blood by releasing the proximal clamp and later clamp is reapplied to the aorta proximal to suture line. Another vascular clamp is applied on the graft distal to suture line and proximal clamp over aorta is again released for short period to check the bleeding at the site suture line. Small bleeders can be controlled by pressure; persistent or large leaks are controlled by additional interrupted sutures. Proximal aortic clamp is reapplied and clamp over the graft just distal to proximal suture line is also released. Repeated clamping of the graft is not advisable. Often a cuff of graft additionally placed over the graft to prevent aortoenteric fistula as complication.

↓

Distal anastomosis: It is done over *common femoral artery commonly*; near the origin of the deep femoral artery to improve the long-term patency rate. Allowing an area of flexion along the length of the graft at groin is small but less significant drawback. (In aortoiliac graft such flexion problem is not present).

↓

Tunneling is completed by passing long vascular clamp from thigh wound below towards abdominal wound above. It is done on both sides. An index finger is passed gently in front of common femoral artery; gentle finger dissection upwards is done to create a tunnel. Deep circumflex iliac vein runs over external iliac artery which should be taken care of as injury to it can cause torrential bleeding. Tunnel usually of two fingerbreadth size is created deep to inguinal ligament. Peritoneum is pushed upwards from upper wound; ureter is also pushed aside. A long Robert clamp is passed from thigh wound across groin to abdominal wound. Often umbilical tape is kept in place on the tunnel till graft is passed down.

↓

Through the vascular clamp each side limb of the aortofemoral graft is pulled gently downwards towards thigh (femoral) wound on respective sides avoiding any twist or undue pull **(Figs 11-31A to L)**.

↓

Distal anastomosis is *end-to-side* one. Distal end of the graft is bevelled like 'S' using heavy scissor and sutured to the arteriotomy made at the junction of common femoral artery. Both superficial and deep femoral arteries should be dissected adequately. Vascular clamps are placed on the two branches distally. Arteriotomy done at the junction can be extended towards deep femoral artery, if needed. Orifices of branches should be exposed and any block at the orifices can be cleared. Continuous 6 zero polypropylene sutures are placed either tied running or as parachute technique. Suturing should be done from inside out at arterial side and from out to inside at graft side. Usually four corner sutures are placed; two in middle and two at angles. Then running sutures are proceeded towards angle posteriorly then towards anteriorly. Initial mattress suture may be placed at the heel of the graft for proper alignment of the graft over the artery.

↓



Incision:
(A) Lengthy midline incision from xiphisternum to pubic symphysis.
(B) Femoral exposure is vertical incisions on both sides from inguinal ligament along mid-inguinal point in on thigh.
(C) If external iliac artery need to be exposed then lateral upward extension is needed.

Fig. 11-31A


Approach incision for suprarenal aorta
IVC
Aorta
16
17
18
1
2
3c
3b
13
5
12
14
2
3
11
3a
20a
20b
20c
20d
19
Kocherisation of duodenum
4
6
7
8
6
10
10
9
15
15
Approach incision in retroperitoneum for infrarenal aorta
1. Inferior phrenic artery
2. Middle suprarenal artery
3. Coeliac trunk
3-a. Hepatic artery
3-b. Splenic artery
3-c. Left gastric artery
4. Superior mesenteric artery
5. Renal artery
6. Gonadal artery
7. Lumbar artery
8. Inferior mesenteric artery
9. Median sacral artery
10. Common iliac artery
11. IVC
12. Left renal vein
13. Left adrenal vein
14. Left gonadal vein
15. Common iliac vein
16. Liver
17. Diaphragm
18. Oesophagus
19. Right kidney
20. Duodenum: 20a- 1st part; 20b- 2nd part; 20c- 3rd part; 20d- 4th part.

Suprarenal aorta

- Difficult to approach and manage
- But not commonly involved

Infrarenal aorta

- Easier to approach and manage
- But commonly involved by disease

Surgical anatomy and exposure of abdominal aorta

Fig. 11-31B


Left adrenal vein
Adrenal gland
Kidney
Left gonadal vein
Left renal vein
Left adrenal vein
IVC
Aorta
Left gonadal vein

Colon is pushed upwards; intestines towards right side.

4th and 3rd parts of duodenum are mobilised above and medially to identify the left renal vein and aorta.

- Left renal vein is retracted above.
- Left gonadal and adrenal veins are ligated.

- If disease is extending close to renal vessel level, then left renal vein may need to be transected close to its entry into IVC. In such situation left gonadal and adrenal veins should be retained to maintain venous drainage of left kidney. But it is rarely needed.

Fig. 11-31C



Two vascular clamps are placed at infrarenal portion of the aorta from left side.

Fig. 11-31D



Aorta is transected between two vascular clamps.

Fig. 11-31E



Lower cut end is closed using continuous polypropylene 4 zero sutures—initially sewing machine method then over and over sutures are placed.

Vascular clamp in the lower cut/sutured part is released.

Fig. 11-31F


Pre-clotting creates leakage proof smooth fibrin lining to the graft.
Non-coated Dacron graft
Bulb syringe
100 mL non-heparinised fresh blood of the patient drawn from aorta or IVC on table
Blood passing through the graft
Leaks on the surface will stop once pre-clotting is adequate
Graft clamp
Pre-clotted graft
Heparinised saline is flushed/washed after that.
Smooth fibrin inner lining after pre-clotting
Heel end
Toe end
Graft clamps are removed and clot and debris are allowed to flush out using heparinised saline.
Distal ends of the graft are cut using heavy scissor as 'S' shaped to facilitate end to side anastomosis.

Fig. 11-31G



End-to-end anastomosis using 4 zero polypropylene sutures.

End to side anastomosis (End of graft to side of aorta).

Fig. 11-31H


Proximal suture line
Proximal limb of the graft
Distal limbs of the graft

Peripheral/distal limbs of the graft are clamped.

Proximal aortic clamp is released for short period to fill the graft with blood.


Aortic clamp
Clamp in the graft

Aorta is reclamped and graft just distal to the graft – aorta suture line is also clamped gently.

Aortic clamp is released to check the graft suture line security. If needed additional sutures may be added.

Fig. 11-31I



Vascular clamps are applied to both branches of femoral artery of one side. Aortic clamp is kept in place. End to side anastomosis is done.

Clamps over the femoral branches are released to allow retrograde flow of blood to opposite limb of the graft to remove clots and debris. Aortic clamp should be in situ.

Fig. 11-31J



Clamp applied over to the opposite limb of the graft.

Aortic clamp is released to allow blood flow to sutured limb.

Fig. 11-31K



With aortic clamp in place, clamps are applied on superficial and deep femorals on both sides. Arteriotomy is done on left side femoral near origin of deep femoral. End to side anastomosis is done using 5 zero or 6 zero polpropylene.

Distal clamps on the side (left) is released. then proximal aortic clamp and later opposite (right) side femoral clamps are removed. Any bleeding points are tackled by further few sutures.

Fig. 11-31L

Figs 11-31A to L: Aortofemoral bypass graft.

Distal clamps of the superficial and deep femoral arteries are released to allow retrograde flow of blood along the limb of the same side of the graft; towards the limb on the opposite side of the graft to clear clots and debris.

↓

Now opposite limb of the graft is clamped near its bifurcation/origin of the branching. Proximal aortic clamp is slowly released so as to avoid sudden fall in blood pressure beyond 20 mm Hg.

↓

Opposite side superficial and deep femorals are clamped; arteriotomy is done near its origin; opposite graft limb is trimmed as 'S.' Anastomosis is done similarly. Femoral clamps are released just before last sutures. Proximal clamp at the graft limb is slowly released to perfuse across the graft. Any leak is dealt with similarly.

↓

Inferior mesenteric artery, if needed, should be reimplanted into the proximal limb of the graft. Large artery, artery with less back bleeding after transection, and when there are poor collaterals need reimplantation of inferior mesenteric artery. Colour of the bowel wall and Doppler study by placing the probe on the antimesenteric part of the bowel after clamping the artery will decide the need for reimplantation.

↓

Retroperitoneum is *closed over the graft*. It prevents the contact of the graft into intestines or duodenum to prevent aortoduodenal or aorto-intestinal fistula. Omental pedicle may be placed between aorta and intestines. Meticulous haemostasis in all layers is important **(Fig. 11-32)**.

Complications

Bleeding can occur which occasionally requires re-exploration. Hypovolaemia is common.



Fig. 11-32: End-to-side aortic graft. It is not commonly used; but it maintains the spinal cord blood supply to reduce the chance of spinal cord ischaemia.

Re-thrombosis and graft failure are also known complications.

Distal ischaemia and gangrene can occur. Doppler study of limbs is done to assess the distal perfusion.

Embolism due to dislodged atheroma when occurs, with intact pulse needs embolectomy.

Injury to aortic nerve plexus may cause impotence but it is less common.

Wound infection, haematoma and abscess formation are other complications. Progressive haematoma needs re-exploration.

Colonic ischaemia mainly left sided (sigmoid) can occur. Only mucosal ischaemia is treated by nasogastric aspiration; deeper level ischaemia needs laparotomy and resection. If preoperatively suspected by wider diameter of inferior mesenteric artery or artery with poor back bleeding then *reimplantation of inferior mesenteric artery is done.* Inferior mesenteric artery at its origin is cut with cuff/button of adjacent aorta. Corresponding graft at the site is opened like a buttonhole to which inferior mesenteric artery origin cuff is sutured using polypropylene to achieve reimplantation **(Fig. 11-33)**.



Inset showing distal cut end of the aorta deeper to sutured graft with origin of inferior mesenteric artery. This origin with a cuff of the aortic wall is excised and aortic wall is sutured. This excised cuff is sutured into the similar button created in the front of the sutured graft. Confirmation of perfusion is done using Doppler study on the left side colon.

Fig. 11-33: Inferior mesenteric artery origin can be reimplanted into the aortic graft in case if colonic ischaemia possibility suspected.

Graft failure and leak when occurs, needs re-exploration and regrafting. Sepsis is the major cause for graft failure.

Disruption of the parasympathetic nerves near aortic bifurcation leads into impotence or retrograde ejaculation. Care is taken during the dissection around bifurcation so as not to injure the nerve plexus **(Fig. 11-34)**.



Parasympathetic nerves around aortic bifurcation.

Disruption of this parasympathetic nerve around aortic bifurcation can cause impotence.

Fig. 11-34: Impotence can occur after aortofemoral grafting due to parasympathetic disruption.

Spinal cord ischaemia can occur due to severe arterial insufficiency. It leads into paraplegia. It is more common in end-to-end anastomosis of the proximal part of the graft into aorta. In *proximal end-to-end anastomosis,* distal to distal cut end of the aorta gets its perfusion through retrograde blood flow along hypogastric arteries. But in severe bilateral iliac disease, such retrograde perfusion is not adequate as it leads to poor perfusion of the lower spinal arteries causing spinal cord ischaemia. It can be identified prior to surgery by preoperative angiogram; if detected it is better to add on revascularisation procedure of the hypogastric artery. In *end-to-side proximal graft – aorta anastomosis* incidence of spinal cord ischaemia is less **(Fig. 11-35)**.



End-to-end anastomosis more commonly causes spinal cord ischaemia than end to side anastomosis.

Usually after closing distal cut end of the aorta perfusion is maintained through cruciate anastomosis between branches of internal iliac artery and deep femoral artery.

1. Internal iliac artery (Hypogastric).
2. Posterior division of IIA.
3. Anterior division of IIA.
4. Superior gluteal artery.
5. Inferior gluteal artery.
6. Anastomotic branches.
7. Deep femoral artery (profunda femoris).
8. Medial circumflex iliac artery.
9. Lateral circumflex iliac artery.
10. First perforating branch.
11. Closed end/distal aorta.
12. Graft-proximal suture line.
13. Graft distal suture line.

Fig. 11-35: Diagrammatic representation of collaterals and possibility of developing spinal cord ischaemia.

Aortoduodenal/aortointestinal/aortovenacaval fistula can occur which is often life threatening. It is treated by immediate surgery, redoing of graft, resection, etc., but it is technically demanding with high mortality.

OTHER GRAFT PROCEDURES

Other grafts in the lower limb/aortoiliac femoral segments can be done using same principles. Bypass grafts are classified as anatomical bypass graft and extra-anatomical bypass graft.

Anatomical bypass graft is the one which is along the normal course of the artery. Examples are aortobifemoral, aortoiliac, ileofemoral, femoropopliteal grafts.

Extra-anatomical bypass graft is the one which traverses through different than normal arterial pathways. Examples are cross over femoral graft, axillofemoral bypass graft.

Duplex ultrasound scanning, segmental limb pressures and segmental limb plethysmography are needed investigations to assess accurate physiological status of the vessel. Cardiac assessment is essential in all these patients.

Prophylactic antibiotics are started 24 hours prior to surgery; entire abdomen both lower limbs and chest below nipples should be prepared.

AORTOILIAC BYPASS GRAFT

Aortoiliac bypass graft can be done if there is unilateral common iliac artery block. Often unilateral aortofemoral graft is preferred although graft has to pass across groin crease.

Aorta and iliac artery is exposed *through retroperitoneal* (occasionally transperitoneal) approach using oblique groin muscle cutting incision (peritoneum is not opened, instead is pushed above towards left). Lower end of aorta with bifurcation and common, external and internal iliac arteries on that side are exposed and dissected. Vascular clamps are applied over aorta above the level of aortic anastomosis, on to opposite common iliac artery to prevent retrograde flow, and distal part of the external iliac artery distal to the line of anastomosis **(Figs 11-36A and B)**.



A

An oblique lower abdomen incision is made. Muscles (all three and rectus) are cut. Peritoneum is pushed upwards and towards left to expose the aorta and iliac vessels. Opposite iliac artery is also exposed to place vascular clamp if needed. Aortoiliac graft is done as side-to-side anastomosis.



B

Figs 11-36A and B: Aortoiliac graft.

Pre-clotting of the selected graft is done. Aorta is opened longitudinally and side-to-side graft to aorta anastomosis is done. Its integrity is confirmed by once releasing aortic clamp for a short period and later reapplied. External iliac artery just proximal to distal clamp is opened and side-to-side anastomosis is done between lower end of graft and external iliac artery. Just prior to completion of last suture distal clamp is released to remove clot and debris. Proximal clamp and clamp on the opposite common iliac artery is released. Suction drain is placed and kept for 72 hours. Complications are similar to other graft procedure.

ILEOFEMORAL GRAFT

It is done when disease is limited to one common iliac artery. Common iliac artery near its origin should be patent and free of disease to do ileofemoral graft. Aortic bifurcation also should be normal. It is often preferred method than cross femoral graft as opposite limb dissection is avoided here.

Incisions may be suprainguinal (*retroperitoneal commonly*, transperitoneal occasionally) to expose the aorta and common, external and internal iliac arteries; or vertical thigh incision along midinguinal point across inguinal ligament. External and internal oblique and transversus abdominis muscles are split to reach retroperitoneal area; by blunt finger dissection, vessel is dissected adequately; common iliac or external iliac artery is used for proximal graft placement **(Figs 11-37 to 11-39A to C)**.



Incision:
(A) In the abdomen obliquely from lateral above downwards towards midline just above the pubic symphysis. Usually retroperitoneal approach is used. After cutting all three layers of muscles and rectus abdominis, peritoneum is pushed above and towards left to expose the aorta and iliac vessels fully. In difficult situation trasabdominal approach is used by opening the peritoneum.
(B) Vertical thigh incision at midinguinal point across inguinal ligament.

Exposure of the both wounds to delineate the aorta, IVC, iliac vessels and femoral vessels.

Fig. 11-37: Incision and exposure for ileofemoral graft.



Fig. 11-38: Iliac artery exposure.


A
1
2
3
4
5
6
7
3
4
5
6
7
1. Aorta
2. IVC
3. Common iliac artery
4. External iliac artery
5. Internal iliac artery (Hypogastric)
6. Superficial femoral artery
7. Deep femoral artery (Profunda femoris)
B
Proximal arteriotomy
Distal arteriotomy
Transection at CIA origin
Closure distal end
Distal arteriotomy
C
Proximal end-to-side
Distal end-to-side
Proximal end-to-end
Distal end-to-side

Usually done:
Usually common iliac artery adjacent to its origin is clamped. Internal iliac branches of common femoral artery are also clamped.

Alternate method:
If disease is to close to origin of the common iliac artery, then aorta above the bifurcation and opposite common iliac artery, internal iliac artery, femoral branches are clamped.

Arteriotomy is done at common iliac artery distal to its clamp and at common femoral artery bifurcation.

Here origin of common iliac artery is transected; distal cut end is closed; proximal cut end is kept for end-to-end anastomosis with graft.

Ilio femoral bypass graft with proximal side-to-end; distal end-to-side anastomosis.

Iliofemoral bypass graft with proximal end-to-end; distal end to side anastomosis.

Figs 11-39A to C: Ileofemoral graft—technique.

Initial heparinisation is done. Vascular clamps are applied on the origin of the common iliac artery, internal iliac artery and femoral branches. If the origin of iliac artery is diseased then clamps are placed on aorta above the bifurcation and on opposite common iliac artery to prevent retrograde blood flow from opposite common iliac artery. Cut end of its origin is sutured using 4 zero polypropylene sutures (If end-to-side anastomosis is proposed method, transection of artery is not done). Usually 10 mm graft is used. Internal iliac, superficial and deep femoral arteries are also clamped beyond their origin.

Proximal anastomosis can be done as end-to-side or end-to-end if common iliac artery is transected. Continuous 4 zero polypropylene sutures are placed. Distal part of the graft is tunneled deep to inguinal ligament across femoral triangle into common femoral artery near its division towards deep femoral artery. Distal anastomosis is done as end-to-side using 4 zero polypropylene continuous sutures.

Wounds are closed with a suction drain. *Complications* are bleeding, graft leak, haematoma, thrombosis of graft, intimal dissection, infection and impotence.

Ileofemoral cross over graft is used from one side common or external iliac to opposite side femoral artery wherein graft is passed usually in front of (or underneath) the opposite inguinal ligament **(Fig. 11-40)**.


Aorta
CIA
IIA
EIA
Common femoral artery
Inguinal ligament
Ileofemoral graft passing in front of the inguinal ligament

Fig. 11-40: Ileofemoral cross over graft.

FEMOROPOPLITEAL BYPASS GRAFT

It is done in lower limb ischaemia as a limb saving procedure if disease segment is in superficial femoral artery from its origin to below knee popliteal segment. There should be adequate good blood flow in iliac arteries to do femoropopliteal bypass. *Adequate distal run off* is also needed. If there is associated localised profunda femoris (deep femoral) artery block, then profundaplasty with a vein or graft patch should also be added to improve collateral circulation. Vein graft is always better than prosthetic graft in below knee segment revascularisation. Main artery is left in situ to retain whatever existing functions as it is. Side-to-end femoro graft anastomosis proximally and end-to-side graft to popliteal anastomosis is done **(Fig. 11-41)**.

Procedure

Under regional/general anaesthesia preparation of entire limb from umbilicus up to ankle is done.

First *recipient popliteal segment* is dissected. *Medial approach* is commonly used. Initially *proximal segment of artery* is exposed.



Fig. 11-41: Femoropopliteal bypass graft.

Incision is on the medial aspect from upper part of femoral condyle proximally for 10 cm. Dissection is deepened between vastus medialis and hamstring muscles (semitendinosus, semimembranosus). Sartorius, gracilis, vastus medialis are retracted in front. Artery passing through the adductor hiatus under femur is found. In popliteal fossa artery is found in a fatty area. It is separated from popliteal vein. Genicular branches are identified and safeguarded **(Fig. 11-42)**.

Distal segment of artery is dissected next by medial approach through an incision which is vertical and 1 cm posterior to medial subcutaneous border of the tibia. Often flexion and abduction of hip joint and flexion of knee joint at 90^0 is needed. As long saphenous vein is very close to this incision it should not be injured as it is needed to use as a graft for bypass. After skin incision, long saphenous vein is fully mobilised. Medial head of the gastrocnemius is retracted posteriorly. Dense fascia connecting it to tibia is divided to expose the lower part of the popliteal fossa **(Fig. 11-43)**.

Division of guy ropes (semitendinosus, semimembranosus and gracilis) is only occasionally needed; retraction only suffices. Anterior tibial vein is ligated; artery is dissected carefully including its divisions – anterior tibial artery and tibioperoneal trunk. Popliteal artery is medial to posterior tibial nerve and popliteal vein. Small tributaries are ligated using double loop silk sutures *(Pott's sutures/ties)*. Both branches are isolated and occlusion slings are placed. Fascia anterior to sartorius is incised and using blunt finger dissection tunnel is created to pass the graft **(Fig. 11-44)**.

Adductor canal is an intermuscular space (*Hunter's canal*, John Hunter – 1793) situated on the medial side of middle ⅓ of the thigh extending from apex of femoral triangle to tendinous opening (adductor magnus hiatus) in the adductor magnus below. It is formed anteriorly by vastus medialis; posteriorly (floor) by adductor longus above and adductor magnus below; medially (roof) is formed by strong fibrous membrane joining anterior and posterior walls, which is covered by sartorius. Canal contains femoral artery and vein, saphenous nerve, nerve to vastus medialis, two divisions of obturator nerve. Descending genicular artery originates in the canal from femoral artery which divides into saphenous artery which accompanies the saphenous nerve and muscular branch to vastus medialis **(Fig. 11-45)**.

Proximal dissection at femoral artery level is done through a vertical incision with convexity laterally at midinguinal point. Convexity towards lateral side prevents damage to lymphatic vessels. Lymphatic vessel disruption can cause lymphorrhoea, lymphocele, lymph fistula and wound infection. If lymph vessels are injured, it should be ligated with fine silk suture. LSV can be dissected through same incision on its medial margin. Long saphenous vein may be dissected through a separate vertical incision 1 cm below and lateral to the pubic tubercle directly on LSV. Skin flaps should not be raised as much as possible to prevent development of skin necrosis.

Usually vein graft is used. Long saphenous vein is commonly used. If it is not available by disease or previous surgery, then small saphenous vein or cephalic vein is used. Vein graft is better than prosthetic graft in relation to graft take up and long-term efficacy in femoropopliteal bypass. However technical precision and availability of good graft makes prosthetic graft also equally effective **(Figs 11-46A to F)**.

SAPHENOUS VEIN GRAFT

Both in situ and reversed vein graft is used. LSV is divided in the wall of the common femoral vein to achieve maximum width at the LSV opening. Junction is clamped using Satinsky vascular clamp. All tributaries are ligated at 1 mm distance. It should not be less nor more than 1 mm; if less, it may narrow the graft or block; if more, it may precipitate the thrombus at the stump of the tributary. Care should be taken not to injure the adventitia of the vein **(Figs 11-47 to 11-51)**.


Incision for distal popliteal artery
Incision for proximal popliteal artery
Medial incision in supine knee flexed position
A
Incision to expose femoral artery
Incision to dissect long saphenous vein
Sartorius
B
C

Distal incision/incisions for recipient artery site—Popliteal artery is made first. Supine semiflexed knee with medial incision is preferred. Incision for proximal popliteal artery is vertical just above the femoral epicondyle two fingerbreadths behind the femur along the anterior margin of sartorius. Incision for distal popliteal artery is vertical, medial and just behind the tibial margin of 15 cm length.

Proximal incision to expose femoral artery—It is vertical incision in the thigh at midinguinal point with lateral convexity to avoid disruption of lymphatics. LSV can be dissected through same incision on medial flap or through separate vertical incision below and lateral to pubic tubercle.

Donor LSV may be taken from opposite side if same side LSV is not amenable for graft.

Figs 11-42A to C: Incisions and approaches for femoropopliteal bypass graft.


Anterior tibial artery
Popliteal artery
Popliteal vein
Tibioperoneal trunk
Gastrocnemius muscle
Anterior tibial vein - ligated
Soleus muscle
Medial side of the limb
Dissection of the distal popliteal artery below knee level for femoropopliteal bypass graft

Fig. 11-43: Dissection of the distal artery for femoropopliteal artery bypass.

In Situ Saphenous Vein Graft

Here proximal part of the graft is anastomosed to the femoral artery above the level of the block without disturbing the LSV graft anatomical location. But as LSV junction is often at lower level than site of anastomosis to artery, proximal part of the LSV often needs to be mobilized.

Since valves are present in the LSV graft, they need to be destroyed using valvulotome. First valve is usually at 1 cm from SFJ. Its translucent central part is excised under direct vision using Pott's scissor. Second valve is 3-5 cm from SFJ. If saphenous vein is 3 mm or more in diameter *valve cutter method* can be used to destroy the valves. A guide catheter is passed from ankle level of the saphenous vein upwards towards proximal cut end of the LSV. Proximal pulled out catheter is connected to a heparinised saline delivery system which inflates up to the next proximal valve and valve cutter should float in the lumen freely. Vascular loop kept around proximal part of the saphenous vein is snugged. Valve cutter is rotated 90° to cut the valve leaflets using cutting edge. Once valve is cut, distal next level valve will become prominent due to saline distension and cutter is gently pulled down distally to feel the resistance by the valve. Valves are cut to feel a popping sensation with vein getting distended below up to the next valve level **(Figs 11-52A and B)**.

During valvulotomy, intima of the vessel may be damaged. Retained tributary of in situ saphenous graft is a potential anatomical area of *arterio venous fistula* formation.

Vascular clamps are applied on proximal part of the femoral artery and proximal cut end of saphenous vein. Distal part of the popliteal artery is also clamped. *Side-to-end proximal anastomosis* is done between side of the femoral artery and proximal cut end of saphenous vein (cobra head) using 6 zero polypropylene sutures first 'heel' of the graft is sutured; then sides and at the end 'toe' of the graft. Often parachute technique is used. Arterial vessel loops/slings/ clamps are released to allow blood flow through saphenous vein up to proximal valve. It is confirmed by pulsation which stops at first valve level. Venotomy is done at the side branch of distal end of the vein. *Valvulotomy* instrument (*Le Maitre's valvulotome* – blunt tipped) is passed carefully through it with 90° rotations without traumatizing the intima. Proximal graft anastomosis is pinched by assistant's finger to prevent valvulotome entering into the anastomotic site. If it enters anastomotic site, it will snag the sutures and cut. Valve with distended proximal vein segment is identified; valve is cut carefully by rotating the valvulotome 90°. Blood now flows towards next level of valve which is cut again and is repeated until all valves are cut. *All tributaries should be identified carefully and ligated.* Full length of the


A and B: Femoropopliteal graft bypass showing diseased/blocked artery with bypass graft
A
B
C: Proximal anastomosis to CFA
C
C and D: Proximal and distal anastomosis of the graft to common femoral and popliteal arteries
D: Distal anastomosis to popliteal artery
D

Figs 11-44A to D: Femoropopliteal bypass graft.


Psoas major
Iliacus
Sartorius
Tensor fascia lata
Pectineus
Adductor longus
Adductor magnus
Gracilis
Vastus lateralis
Adductor canal - site
Rectus femoris
Vastus medialis
Patella
Ligamentum patellae
Femoral triangle
Sartorius
Nerve to vastus medialis
Muscular branch
Hiatus in adductor magnus
Semimembranosus
Semitendinosus
Medial head of gastrocnemius
Adductor longus
Femoral vein
Femoral artery
Anterior and posterior divisions of obturator nerve
Saphenous nerve
Descending genicular artery
Saphenous artery
Deep muscular branch
Biceps femoris muscle
Popliteal fossa
Lateral head of gastrocnemius

Fig. 11-45: Anatomy of femoral triangle and adductor canal in relation to femoropopliteal bypass graft.


Femoral artery exposed proximal to aneurysm
Dissecting the aneurysm
Aneurysm
Exposing the aneurysm and distal artery
Exposing the aneurysm and distal popliteal artery
Reverse saphenous vein bypass graft proximal anastomosis into common femoral artery
Distal anastomosis of reversed vein into the popliteal artery distal to aneurysm

Fig. 11-46(1)


Clot in the aneurysm which is opened after bypass
Cleared aneurysm cavity with reversed vein bypass in front
Exposed aneurysm sac
Removed aneurysm clot

Fig. 11-46(2)

Figs 11-46(1 and 2): Femoropopliteal aneurysm—clot evacuation after placing reverse saphenous vein femoropopliteal venous bypass graft.


Superficial external iliac vein
Superficial epigastric
Superficial external pudendal
LSV
Anterior vein
Posterior vein
Perforators
SP junction
Perforators
SSV

Fig. 11-47: Anatomy of long and short saphenous vein.


Femoral nerve
Femoral artery
Femoral vein
Sartorius
Cribriform fascia
Adductor longus
Long saphenous vein

Fig. 11-48: Surgical anatomy of saphenofemoral junction and femoral triangle.



Incisions for long saphenous vein harvesting for saphenous vein femoropopliteal graft. LSV may be exposed by (A) longitudinal incision along the LSV or (B) by multiple small longitudinal incisions. It is technically easier with single lengthy incision. In situ saphenous vein graft cab be done with multiple incisions. All tributaries should be ligated at 1 mm distant from the surface of the LSV using 4 zero polypropylene sutures.

Figs 11-49A and B: Incision for exposing the long saphenous vein.



Harvesting of LSV is done by ligating the saphenofemoral junction very close to the femoral vein so that to achieve wide LSV opening for proximal (in 'in situ' graft) or distal (in reverse graft) anastomosis to artery. Satinsky clamp is applied at SFJ; LSV is cut using No. 15 blade; continuous underrunning over and over sutures on the Satinsky clamp is done using 4 zero polypropylene suture to close the SFJ.

Fig. 11-50: Saphenofemoral ligation for harvesting the LSV graft.


Femoral vein
LSV-SFJ sutured with 4 zero polypropylene
LSV
Tributary is ligated 1 mm away
(Correct method)
Ligation away may cause thrombosis
of the remnant
Ligation very close can cause narrowing
of the main vessel

Fig. 11-51: Proper ligation of tributaries is essential in harvesting the saphenous vein.



SFJ is ligated close to the femoral vein; proximal saphenous vein is looped; through distal venotomy valvulotome is passed; next to proximal valve is cut gently.



Proximal anastomosis is done into the common femoral artery; valvulotome is further pulled down along each valve to cut it; till lower end valves are cut.

Figs 11-52A and B: In situ saphenous vein graft for femoropopliteal bypass.

vein is exposed and tributaries are ligated. Tributaries in the deeper aspect of the vein should be identified and ligated. Angiogram is done to identify and ligate the site of tributaries. Tributaries are identified using a Doppler probe; pinching the graft distal to probe, flow to the tributary proximally can be recognized **(Figs 11-53A to D)**.

Distal anastomosis between end of the saphenous vein and side of the artery (end to side) is decided. It may be either lower popliteal, anterior tibial, tibioperoneal or posterior tibial depending on the site and extent of the block. Vein end is tailored like a cobra head. Magnifying loop or glass may be used for distal anastomosis. Small bulldog clamps or vascular loops are used to occlude the vessel all around prior to anastomosis. 6 zero or 7 zero polypropylene sutures are used for distal anastomosis. Any arteriovenous fistula in 'in situ saphenous graft' is carefully felt (by thrill); if present identified and ligated securely. It can also be identified by doing on table angiogram or on table Doppler study.


A

Tributaries are ligated 1 mm away using 4 zero polypropylene sutures on venous side and polypropylene/silk/clips on other side.

Vein is clamped using bulldog clamp at proximal part.

LSV after mobilisation is reversed so that effects of the valves are nullified and made ready for anastomosis.


Femoropopliteal reverse vein graft showing distal anastomosis - usually first distal anastomosis is done; then later proximal anastomosis.

B


Cutting the end for anastomosis - creating the cobra head end.

Doing the anastomosis at heel end.


Continuing anastomosis towards toe end.

Completion of anastomosis.

C

Figs 11-53A to C



(A) Reversed vein is filled and passed with cold heparinised patient's blood using syringe with ball tipped needle. Any bleeding point is sutured using fine 6 zero polypropylene suture to make vein ready (B) for graft.

D

Fig. 11-53D

Figs 11-53A to D: In situ saphenous vein graft for femoropopliteal bypass graft.

In 'In Situ Saphenous Vein Graft' usually *proximal anastomosis is done first*; later distal anastomosis.

Free Reversed Saphenous Vein Graft

LSV is used commonly. LSV should be available as a normal vein. Opposite LSV can also be taken as graft. Diseased vessel cannot be harvested. Preoperative Duplex/venous Doppler scan should be done. Procedure is done under spinal/epidural anaesthesia. It may be a single long incision along the course of the vein or skip incisions or interrupted incisions. Saphenous vein is divided at saphenofemoral junction; cut vein end on femoral vein side is closed using 4 zero polypropylene suture.

Vein is dissected; all large and small tributaries are ligated at 1 mm distance. Creating flaps under the skin or undermining the skin should be avoided as necrosis of skin flap can occur. Vein should be irrigated continuously using saline to prevent desiccation. Vein should be held very carefully without causing any adventitial injury. Vein is completely dissected off the surrounding tissue and rotated 180° to reverse it. Fine needle (*ball tipped* needle) with syringe containing *cold heparinised patient's blood* is passed through the distal aspect of the vein (reversed vein proximal part). Plain saline solution should not be used. Solution containing saline, albumin, heparin and papaverine can be used. Vein is gently flushed with the heparinised blood causing distension of the vein. Care should be taken not to force blood/fluid rapidly to create over distension which may lead into intimal damage. A pressure over 200 mm Hg is not advisable (rapid force in usual syringe creates pressure more than 200 mm Hg). Any leaking points are identified and securely ligated using 8 zero polypropylene suture without narrowing the lumen. *Magnifying lens* may be used for suture ligation.

Short/small saphenous vein when needed is harvested in prone position. Flexion and inward rotation of the hip is also used which avoids change of position for graft suturing. Small saphenous vein which is located behind the lateral malleolus is identified. Longitudinal skin incision (from lateral malleolus up to mid calf level) is made; skin should not be undermined; identified vein is dissected off the adjacent tissues with ligation of tributaries. In proximal ⅓ of leg vein penetrates the deep fascia. Continuous papaverine irrigation into the vein is needed to prevent spasm.

If both LSV and SSV are not good for graft then *cephalic vein* is used as autologous vein graft. Cephalic vein is harvested from lateral side of wrist to deltopectoral triangle. Anatomical variations are common in upper limb veins. Upper limb veins are more adherent to skin compared to lower limb veins and so it is more difficult to harvest them without traumatizing. Both cephalic and basilic veins can be used as one conduit. Lateral lengthy single incision or multiple incisions may be used.

Tunneling to pass the graft is done either in deeper plane or superficial subcutaneous plane. Graft placed in deeper plane avoids kinking and block; but access for possible eventual stenosed area becomes difficult. Above knee popliteal graft is placed in superficial plane where vein is harvested upon. Below knee popliteal graft is passed through deeper plane to avoid kinking by hamstrings. *Twist in the vein should be avoided.* After proximal anastomosis clamp is released; twist can be made out during blood flow. Often *ink marking* is done on the surface of the vein to identify the twist if it develops. *Completion angiogram* also shows twist along with leak.

Common, superficial and deep femoral arteries are exposed properly through thigh incision. These arteries are occluded using vascular clamps. Arteriotomy is done (No. 11 blade) on the common femoral artery with lower end of incision *directed towards* deep femoral artery. Incision can be easily extended into deep femoral artery if there is localized stenosis of the orifice of the deep femoral artery.

Anastomosis is done either as distal anastomosis first and later proximal anastomosis or as proximal anastomosis first. Many surgeons prefer to do distal anastomosis first. Either way is acceptable.

Proximal side-to-end anastomosis is done. Proximal cut end of the vein is made oblique by cutting on one edge. It reduces the tension on the anastomotic line and also makes the stoma wider. Sutures are placed from inside of the artery towards outside to avoid intimal flap formation. 'Heel' *should be distal* part of the anastomotic stoma and '*toe' should be proximal* part. Before last suture, clamp is released to confirm the back flow and down flow. Anastomosis is irrigated with heparinised saline. Clamp is reapplied and anastomosis is completed. Clamp on the venous side distal to the anastomosis is applied.

Distal anastomosis is done as end-to-side. End of the vein is cut and spatulated like a '*cobra head'* to widen the stoma at end-to-side anastomosis into the arteriotomy of distal popliteal artery. Here '*heel' end* of anastomosis is proximal; '*toe' end* is on distal side. Arteriotomy is done in the popliteal artery either above knee or below knee. As anastomotic site is smaller than proximal part, three initial stay sutures are placed near 'toe end' to achieve perfect anastomosis. Parachute or sliding technique may be also used beginning at the 'heel' end of the anastomosis in difficult situation. Back flow is checked during completion of anastomosis and heparinised saline irrigation is done **(Figs 11-54A to C)**.

Completion angiogram is a must to check for leak, adequate filling, and twist. 20 ml of water soluble iodine dye is injected. C-arm imaging is used. Suction drain is placed and kept for 72 hours. Wound is closed.

Intraoperative heparin or dextran is given to prevent formation of clot. Heparin is given 100 units/kg body weight at cross clamping. It is continued daily for 4 days **(Fig. 11-55)**.


Distal anastomosis to popliteal artery
Proximal anastomosis to SFA
A
B
C

Figs 11-54A to C: Femoropopliteal bypass reverse vein graft.



Fig. 11-55: Femoral artery to popliteal artery saphenous vein bypass graft.

Postoperative Care and Follow-up

It is common use to take oral anticoagulants and antiplatelet drugs even though graft survival by these drugs alone is not entirely proved.

ICU care, postoperative low molecular dextran are needed for 48–72 hours.

Smoking should be stopped to improve the graft survival.

Circulation should be checked by regular checking of pulse or using Doppler. Duplex scan is very useful to identify the stenosed areas. Stenosis is commonly observed at anastomotic site, at the level of valves. Duplex scan is done 3 weeks after surgery; then afterwards once in three months for one year. Late occlusions are less in 'in situ graft' than in reversed saphenous vein graft or synthetic graft.

Complications

Bleeding, thrombosis, graft leak, graft thrombosis, infection and failure are known complications.

Early occlusion of the graft – If occlusion occurs within 30 days of graft it is called as early occlusion. It is commonly due to technical cause, poor selection of patient, inadequate 'run–in' and/or inadequate 'run–off'. A revision procedure may be tried; but amputation is commonly needed in such patients as revascularisation is impossible. Catheter thrombectomy, angioscopy, angiographically guided thrombolysis are tried to revascularise the limb. Balloon angioplasty, short jump bypass graft are all tried to salvage the limb.

Late occlusion can occur which is due to progression of disease, smoking, persisting precipitating factors. Angiogram confirms the occlusion. It is difficult to manage late occlusion.

AXILLOFEMORAL GRAFT

Prerequisites

Donor axillary artery should be disease free. Blood pressure measuring in both arms is done; duplex scanning of axillary artery is essential. It is *extra anatomical indirect graft.*

Surgical Anatomy of Axillary Artery

It is the continuation of subclavian artery from outer border of first rib to lower margin of teres major muscle with its 1st part occupying superior, 2nd part behind and 3rd part is inferior to pectoralis minor muscle. When the arm is held at right angle to body with palm facing upwards, surface marking is done as a straight line from midpoint of clavicle to a point at the junction of anterior ⅓ and posterior ⅔ of lateral wall of axilla. Here axillary artery is palpated against humerus. Superficial relations in first part are skin, superficial fascia, supraclavicular nerves, clavicular part of pectoralis major, clavipectoral fascia with cephalic vein, lateral pectoral nerve, thoracodorsal vessels, communicating loop between medial and lateral pectoral nerves; in the second part it is deep to pectoralis minor muscle; in the third part it is deep to pectoralis major muscle. Deeper relations are first intercostals space, external intercostal muscle, serratus anterior digitations, brachial plexus, latissimus dorsi and teres major below. Axillary vein is below, medial and superficial to artery. Axillary artery is covered by axillary sheath which is derived from prevertebral layer of deep cervical fascia. Axillary vein is not covered by axillary sheath.

Of *6 branches of axillary artery* one (superior thoracic) branch arises from first part; two (acromiothoracic/thoracodorsal and lateral thoracic) from 2nd part and three branches (subscapular {*largest branch*}, anterior circumflex humeral, posterior circumflex humeral) arise from 3rd part of axillary artery.

Incision – A small transverse incision below the middle of the clavicle extending laterally to a point below the medial part of the deltopectoral groove.

Procedure – Skin and pectoral fascia are incised; pectoralis muscle is split along the line of fibers and retracted. Clavipectoral fascia is identified and split to reach pectoralis minor muscle. Pectoralis muscle is cut or retracted to feel the axillary artery pulsation. Axillary vein is below and superficial to artery with close relation. Posterior minor branches of the artery should be ligated; fine sling is passed around the artery to have gentle traction over the artery **(Figs 11-56A to D)**.

Axillofemoral tunnel is created to place the prepared selected graft in the tunnel. Tunnel is created using finger under the pectoralis major in front of chest wall along the midaxillary line and later medial to anterior superior iliac spine to reach the groin below the inguinal ligament into common femoral artery. If both common femoral arteries are needed to perfuse then bifurcation axillofemoral graft can be used; or use a cross over graft from axillofemoral graft of one side to opposite common femoral artery. In between additional horizontal small incisions may be made as needed to facilitate the proper graft placement in the tunnel without kinking. Length of the graft should be adequate enough to prevent shortening and to allow adequate range of movements of shoulder and hip joints. Prior heparinisation is done; vascular clamps are placed to vessels; arteriotomy is done to both axillary and femoral arteries. Anastomosis is done first at proximal and then distally using polypropylene sutures.

Indications and Advantages

- It is done in conditions where already placed aortic graft is infected or as an alternate to aortofemoral graft.
- Advantages are major muscles are not incised; abdomen is not opened; aorta is not dissected and clamped.
- If it is done in case of infected aortofemoral graft original graft should be removed with ligation of aorta and proximal femoral arteries. Tunneling should avoid infected field.

FEMOROFEMORAL CROSSOVER GRAFT

It is done when one side vessel is diseased but other side is relatively normal with adequate perfusion. Initial angiogram and Duplex scanning are done to assess the flow and success of the procedure.

It is done in spinal or epidural anaesthesia as an *extra anatomical graft* technique.

Both sides' common femoral arteries are exposed through vertical groin incision. Arteriotomies are done in common femoral arteries. *Oblique* arteriotomies are preferred so as to place anastomosis obliquely to maintain the curve of the placed graft. Donor arteriotomy is slightly at higher level than recipient arteriotomy. Both arteries are clamped; tunnel is created in the suprapubic region with a curve; graft is placed in the tunnel. Care must be taken not to injure the urinary bladder (catheterization is a must). Graft is anastomosed to donor artery and then at recipient artery in similar fashion as side-to-end. Clamps are released. Drains are placed on both wounds.


Axillary artery
Clavicle
Axillary vein
Coracoid process
Anterior axillary fold
Incision to expose axillary artery
Posterior axillary fold
Pectoralis minor muscle
Incision to expose the common femoral artery
Axillary artery
Clavicle
Pectoralis minor (cut)
Synthetic (Dacron/PTFE) arterial graft
Multiple incisions to create tunnel
Common femoral artery is exposed in the groin
Anastomosis of graft proximally to axillary artery
Synthetic graft
Anastomosis of graft distally to common femoral artery

Axillobifemoral graft using bifurcation graft from same side axillary artery.

Axillobifemoral graft with additional cross graft placed from main graft to opposite common femoral artery crossing across the groin.

Axillobifemoral graft with each side graft is separately connected between respective axillary and common femoral arteries.

Fig. 11-56: Axillofemoral bypass graft. It is an extra anatomical graft.


Aorta
CIA
IIA
EIA
Femoral artery
Inguinal ligament
Femorofemoral graft passing in front of the inguinal ligament

Fig. 11-57: Femorofemoral crossover graft.

Advantages

It is an extra-anatomical graft; easier to place; simple and effective.

Disadvantages

One side artery should be relatively adequate and normal to perfuse both limbs.

Injuries to urinary bladder, graft failure/blockage are the problems.

DISTAL ARTERIAL BYPASS

Block distal to popliteal artery is difficult to manage. Reconstruction is difficult and is possible only if artery distally is patent. Commonly it is done to anterior tibial, posterior tibial, peroneal arteries and rarely to dorsalis pedis artery.

Anterior Tibial Artery Exposure

It is small terminal branch of popliteal artery beginning at lower part of the popliteus opposite tibial tuberosity; enters the anterior compartment of the leg by passing close to the fibula (2.5 cm below the medial side of the fibular head) through an opening in upper part of the interosseous membrane. At midway between two malleoli it continuous as dorsalis pedis artery (at distal margin of superior extensor retinaculum). It lies between tibialis anterior and extensor digitorum longus; middle third between the tibialis anterior and extensor hallucis longus; lower third between extensor hallucis longus and extensor digitorum. Artery is crossed from lateral to medial side by extensor hallucis longus tendon. Deep peroneal nerve is lateral to artery. Anterior tibial artery may be partially or completely replaced by perforating branch of peroneal artery and perforating branch of posterior tibial artery. Artery gives muscular branches, anastomotic branches; medial and malleolar network branches. Artery is accompanied by two venae comitantes.

Incision – Vertical incision is made between the lateral subcutaneous margin of tibia and anterior border of fibula. Incision is deepened between tibialis anterior and extensor digitorum. Artery is exposed at various levels as needed either at middle third or lower third of the leg. Graft is passed from common femoral artery in thigh crossing from medial to lateral to pass onto lateral aspect of the knee joint to reach the leg. Alternatively graft can be crossed in the upper part or in the lower part of the leg.

Posterior Tibial Artery Exposure

It is larger terminal branch of the popliteal artery beginning at lower border of popliteus (in the midline on the back of calf at the level tibial tuberosity) between tibia and fibula deep to gastrocnemius; runs between medial malleolus and medial calcaneal tubercle deep to flexor retinaculum to divide as medial and lateral plantar arteries. It is related superficially to gastrocnemius, soleus and superficial transverse septum in the upper ⅔ of leg; it is in front and on medial border of tendoachilles in lower ⅓ of the leg. In the ankle it lies on capsule of ankle joint; between flexor digitorum longus and flexor hallucis longus. Artery is accompanied by two venae comitantes. Artery is accompanied and crossed by tibial nerve from medial to lateral side. It gives several branches - largest being peroneal artery; others are muscular artery, nutrient artery, anastomotic arteries, circumflex fibular artery, communicating branches, malleolar and calcaneal branches and terminal medial and lateral plantar arteries.

Incision – Vertical incision 1 cm posterior to medial subcutaneous border of the tibia extending like a 'hockey stick' under the medial malleolus. Lower down it is located between flexor digitorum longus and flexor hallucis longus. It is commonly used for 'in situ saphenous vein graft' **(Fig. 11-58)**.

Peroneal Artery Exposure

It is the largest branch of posterior tibial artery. It begins 2.5 cm below the lower margin of the popliteus; runs towards fibula → along the medial crest of the fibula → behind inferior tibiofibular joint and ankle joint → medial to peroneal tendons → ends as lateral calcaneal branches. Variations are common. It may replace posterior tibial/ dorsalis pedis artery. It gives muscular branches, fibular nutrient artery, and anastomotic branches. Peroneal artery runs lateral to the tibial nerve in the groove between the fibular origin of flexor hallucis longus and tibialis posterior.

Both medial and lateral approaches are used. Graft placement is easier through medial approach.

In *lateral approach* incision is placed over lower part of lateral aspect of the leg; often segment of the fibula may need to be excised to pass the graft towards the peroneal artery. Once fibula is removed artery is directly seen.

In *medial approach*, as peroneal artery runs lateral to the tibial nerve in the groove between the tibialis posterior and fibular origin of flexor hallucis longus.

Dorsalis Pedis Artery Exposure

It is the main artery of dorsum of foot begins as continuation of the anterior tibial artery; extends from a point midway between the two malleoli to a point at the proximal end of first intermetatarsal space. It runs on the medial side of the foot lateral to extensor hallucis longus tendon to dip deep between two heads of first dorsal interosseous muscle at first intermetatarsal space to end in the sole as plantar arterial arch. It is palpated over intermediate cuneiform bone. Extensor hallucis brevis crosses the artery from lateral to medial. Medial branch of deep peroneal nerve is lateral to the artery. Artery may be replaced by perforating branch of the peroneal artery in 14% of individuals. It runs over talus, navicular and intermediate cuneiform bones. Branches are medial and lateral (larger) tarsal arteries; arcuate artery which gives 2nd, 3rd, and 4th dorsal metatarsal arteries and first dorsal metatarsal artery.


Reverse saphenous vein graft into
distal artery - to posterior tibial artery
Distal anastomosis adjacent
to medial malleolus
into posterior tibial artery
Proximal anastomosis into
the femoral artery after tunnelling
in the subcutaneous/deeper plane
Completed anastomosis

Fig. 11-58: Saphenous vein graft (reverse) into the posterior tibial artery through femoral artery.

Dorsalis pedis artery is exposed by vertical incision on the medial dorsal aspect of the foot for needed type of reconstruction.

ABDOMINAL AORTIC ANEURYSM

Indications for Surgery

Size more than 5.5 cm transverse diameter is an indication. Risk of rupture is 1% if size is less than 5.5 cm; it is 20% if size is 7 cm. Mortality in rupture is 90% at community level; 50% if they reach hospital and undergoes surgery immediately.

Symptomatic aneurysm like pain/tenderness—whatever the size of aneurysm is.

Ruptured aortic aneurysm is *an emergency situation* with high mortality. It needs immediate surgery and aneurysm repair. Rupture may be anterior (20%) into the peritoneal cavity or posterior (80%) with formation of retroperitoneal haematoma.

Preoperative Preparation

It is essential in relation to cardiac, renal and pulmonary functions. Mass in the abdomen may be palpable clinically with a bruit over it. Lower limb ischaemia often may be evident on both sides. Thrombus from the aneurysm may cause emboli. CT abdomen or CT angiogram is a must. Size, thickness of the wall, course of ureter, site of left renal vein and status of visceral arteries are important findings to be assessed.

Preoperative bowel (colonic) preparation is essential **(Fig. 11-59)**.

Prophylactic antibiotics are given just during incision time.

Central line, an arterial line, nasogastric tube, warming blanket to upper body, urinary catheter - are needed **(Figs 11-60 and 11-61)**.

Epidural catheter with general anaesthesia is used. Both hands are tied over chest wall.



Fig. 11-59: CT scan showing abdominal aortic aneurysm.



Fig. 11-60: Aortogram showing aortic aneurysm.



Fig. 11-61: Reconstructed CT angiogram showing abdominal aortic aneurysm.

Surgical Procedure

Midline incision from xiphisternum to pubic symphysis. Occasionally horizontal incision or midline incision extending across the costal margin is done. Abdomen is explored for additional pathologies, if any to confirm. Manipulation of the aneurysm should be avoided. Surgeon usually stands on left side of the patient but can stand on right side if he feels comfortable. Entire small bowel is mobilised towards the right side of the abdomen to visualise the base of mesentery; gut is wrapped with sterile towel and placed in a gut bag. Transverse colon is lifted above packed superiorly. Posterior peritoneum is divided at the junction of small bowel mesentery on right and large bowel mesentery on left. Division is continued up towards duodenojejunal junction which is identified by inferior mesenteric vein. Duodenum should not be injured. Left renal vein should be identified above, which runs usually in front of the aorta from left side. Rare anatomical variation of retroaortic left renal vein should be remembered. Inferior mesenteric vein is displaced above or ligated at its orifice. Left renal vein is usually above the level of the neck of the aneurysm. Left gonadal and left adrenal veins are not ligated but occasionally there will be a need to ligate left renal vein if neck of the aneurysm extends above this level. In such situation left gonadal and adrenal veins should be intact to drain left kidney **(Fig. 11-62)**.



Fig. 11-62: Aneurysm if extensive blood flow can be diverted temporarily by placing arterial catheter from proximal to distal part.

Junction of aorta where it enlarges as aneurysm is identified in upper part. 1 cm of normal aorta above is dissected carefully. Sides of the normal proximal aorta is only dissected; never posteriorly. Posterior dissection by finger or instrument will unnecessarily injure lumbar vessels to cause torrential bleeding. Often renal arteries arise from the neck of the aneurysm at upper end. Renal arteries should be preserved.

Dissection below is done by exposing both iliac arteries. Ureters run in front of iliac arteries. Ureters should not be disturbed; dissection is done on either side of the ureter. Stretched ureter falls aside once aneurysm is dealt with. Blood supply of the ureter should be kept intact. Left iliac artery is often difficult to dissect due to presence of sigmoid colon. Sigmoid is mobilised by incising the sigmoid mesentery laterally and mobilising it entirely towards right side. It is important especially if there is extended aneurysm towards left iliac artery.

Vascular clamps are applied to iliac arteries on both sides at sufficient distance from aortic bifurcation. If there are aneurysms extending to common iliac arteries then external and internal iliac arteries are dissected separately and clamps are applied individually to them. It is often difficult to dissect the internal and external iliac arteries off their accompanying veins as veins are closely adherent to arteries at this level. In such occasion both arteries and veins are clamped together. Intraluminal balloon tamponade also can be used. If aneurysm extends down into both branches of common iliac arteries then femorals including deep femorals should be dissected for clamping. Deep femorals should be retained especially if bilateral internal iliac arteries are having aneurysm.

Preclotting of knitted Dacron graft is done. Patient is heparinised before clamping the aorta and arteries by giving 5000 to 10000 units of heparin. First iliac arteries are clamped. Aortic clamp is placed above the neck of the aneurysm. Glover's clamp can be placed easily from front to back instead from side-to-side. Aortic clamp should be tightened only to stop the distal pulsation.

Aorta is opened towards right side in front at the level of inferior mesenteric artery; it is extended above along the midline; downwards and below towards right side. At the neck of the (upper part) aneurysm anterior wall is cut transversely to open the aneurysmal sac. Also just above the bifurcation below, aortic anterior wall is cut transversely. Thrombus is scoped out. Origin of inferior mesenteric artery is held in the left flap of the aneurysm sac with vascular clamp to prevent bleeding (retrograde) from the inferior mesenteric artery. Initial profuse bleeding from the posterior wall of the aneurysm wall is from the lumbar arteries which are securely ligated using 4 zero polypropylene sutures. All origins of lumbar arteries should be ligated as once graft is placed its continuity cannot be restored **(Fig. 11-63)**.

Proximal part of the graft is sutured to the neck of the aneurysm using 3 zero polypropylene continuous sutures. Bites should be at 1 mm gap. Bite is taken from inside aorta to outside and from outside graft towards inside graft. Edge bite should be 2 mm from cut margin of aorta and also of graft. Knot should be towards left side to avoid closeness towards duodenum to prevent the possible aortoduodenal fistula.

Graft is clamped just distal to anastomosis and aortic clamp is released to check any leaks. Distal end of the graft is measured and cut adequately. It should not protrude beyond the bifurcation. Posterior bites of the suture material should be taken carefully as left common iliac vein lies close to its posterior wall. Continuous 4 zero or 3 zero polypropylene sutures are used often by parachute technique. Just prior to finishing the distal anastomosis, all clamps are released to clear clots and debris. First iliac artery clamp is released; and after few minutes clamp on other iliac artery is released. This is to avoid rapid



Fig. 11-63: Infrarenal aortic aneurysm repair.

fall in blood pressure after releasing the clamp which is due to return of cold deoxygenated blood, activated white cells, CO_2 and lactic acid causing cardiac depression and pulmonary vasoconstriction. A drop of 20 mmHg blood pressure is accepted. Back bleeding from inferior mesenteric artery is checked before ligating it. If it is not adequate then it needs to re-implant into the graft at proper place to maintain the adequate colonic perfusion. Sac is closed around the graft to prevent direct contact of the graft and gut **(Fig. 11-64)**.

If aneurysm is extending into both common iliac arteries then bifurcation graft is placed; both distal ends are sutured at the junction of origins of external and internal iliac arteries. Graft should be placed within the aneurysmal sac. If there is aneurysm at iliac bifurcation but not involving internal iliac artery then external iliac artery distal to the aneurysm level is transected; its distal cut end is anastomosed to the similarly cut end of the internal iliac artery; graft is sutured to side of external iliac artery as 'end-to-side'. If internal iliac artery is also aneurysmal then it is ligated; graft is sutured to distal cut end as 'end-to-end' anastomosis **(Fig. 11-65)**.

Postoperative Care

ICU monitoring, measurement of output, assessment of clotting factors, pain management, antibiotic coverage are usual requirements in postoperative period. Heparin is used to prevent DVT. FFP, platelet and blood are often needed. Patient is observed for bleeding and when suspected evaluation by haematocrit, US or CT abdomen is done. Any leak/disruption needs re-exploration.

Complications

Immediate Complications

Haermorrhage can occur from leak or bleeding from the branch vessels like lumbar arteries. Occasionally it may be due to injury to adjacent veins. It needs re-exploration and control of bleeding appropriately.

Later Complications

Colonic ischaemia (10%) develops if there is poor back bleeding in the cut inferior mesenteric artery origin. In such occasion, it is better to do re-implantation of the inferior mesenteric artery origin to the graft in front. Once ischaemia develops patient needs laparotomy and resection which carries high mortality due to sepsis.

Myocardial infarction is the commonest complication in first 2 days of surgery. Strict cardiac monitoring and management is required.

Renal failure is not uncommon especially if aneurysm extends up near the origins of the renal arteries. Patient may often require dialysis. It is the commonest non-cardiac complication.

Massive transfusion may cause complications like hyperkalaemia, electrolyte imbalance.

Tracheostomy may be needed for prolonged ventilation.

Sexual dysfunction may develop when internal iliac arteries are involved.

Aortoduodenal fistula/aortoenteric fistula at anastomotic site can occur. It is prevented by proper closing the sac over graft and placing knot of the suture away from the bowel site towards left side. It presents with haematemesis, melaena or hematochezia which is often massive. It needs blood transfusion, exploration and correction of the fistula. It carries high mortality.

Infection is major problem which needs graft removal. It is often a challenging situation to manage.

Microemboli from aneurysm site are called as '*thrash' emboli*. Early clamping of the distal parts of the aneurysm area, flushing out of debris prior to placing last suture bite may prevent this. If it occurs then embolectomy or prostacyclin infusion may be required.

Graft leak, graft thrombosis and graft failure may require regrafting.

Spinal cord ischaemia can develop leading to paraplegia. It is due to block in the perfusion of spinal cord at its localized segment.

Prosthetic infection or migration may occur which needs graft removal.


A
B
Large aortoiliac aneurysm
C
Abdominal wound
Femoral artery
Femoral artery
D
Slings around the femora and its branches
E
Abdominal aortic aneurysm exposed
F
Right femoral artery dissected
Aneurysm
Left femoral artery dissected
G
Dissecting the aneurysm by opening the retroperitoneum
H
Aneurysmal sac with clot

Figs 11-64A to H


Opened aneurysm sac with clot
I
Clot removal and exposing the sac
J
Removed clot
K
Aortobifemoral Dacron graft (Woven) with right femoral exposed
L
Graft in place in retroperitoneum
M

Figs 11-64I to M

Figs 11-64A to M: Abdominal aortic aneurysm. Operative steps.

Ruptured Aortic Aneurysm

Ruptured aortic aneurysm is a surgical emergency. Intraperiton rupture though less common (20%) has got very high mortality. In *retroperitoneal rupture* which is *more common,* after initial temporary bleeding, it stops due to tamponade effect of peritoneum and so patient can reach the hospital for definitive procedure on emergency basis. Central line, arterial line, urinary catheter and blood (10–20 bottles) for transfusion should be kept ready as preoperative measures. Emergency CT scan can be done if patient is stabilized.

Management of retroperitoneally ruptured aortic aneurysm is same as elective approach. But heparin is not given during procedure. It is administered at all only after clamping the aorta. Heparin solution can be flushed down the iliac vessels to prevent thrombosis of these vessels. Intra-operative complications like persistent ooze, disseminated intravascular thrombosis, myocardial infarction and cardiac arrest are dreaded complications which are not possible to reverse.

In intraperitoneal rupture which is much more critical as there is no temporary tamponade effect by peritoneum, emergency laparotomy is done. Direct pressure is applied over the neck of the aneurysm. A Foley's catheter may be passed into the aorta and inflated at the neck to control bleeding until patient is reasonably resuscitated. Alternatively vascular clamp may be applied directly over the aorta under the diaphragm at the level of crus to have an effective control. Once everything is under control, if patient is stable or reviving, then only repair of aneurysm may be undertaken. Massive blood transfusion is required. Patient may develop cardiac arrest and succumb at any stage of the procedure.

Aorto-Vena Caval Fistula

Aorto-vena caval fistula is a late dreaded complication of aneurysm. Often it is identified during ruptured aortic aneurysm also. It presents with bruit, poor perfusion of both lower limbs, hyperdynamic cardiac status. CT/MR angiogram is diagnostic. Aneurysmal sac is opened from the graft and is sutured using running 3 zero polypropylene sutures. Aorto-caval fistula is a complication of aneurysm repair itself often wherein fistula can occur at graft aorta junction with IVC. On table bleeding is controlled by vena caval finger occlusion or by passing a balloon over the fistula across saphenous vein.

ENDOVASCULAR ANEURYSM REPAIR (EVAR)

In 1991 Juan *Parodi* and Julio Palmaz first did endovascular aneurysm repair. It is less invasive, less morbid with less mortality rate and shorter hospital stay. It is basically aneurysm exclusion method. It is useful in old age and patients who are not fit for surgery. EVAR is basically a prophylactic procedure.

Femoral artery is cannulated; retrograde angiogram is done to evaluate the entire abdominal aorta including renal arteries. Cannulation → guidewire → stent device/graft placement are the steps. Special endovascular prosthesis/device is used and placed in place under guidance. First proximal part at infrarenal level is secured; then distal part


Exposure of abdomen and visualisation of aneurysm
A
Aneurysm
C
Femoral artery is exposed
B
Aneurysm dissection
D

Figs 11-65A to D


E
H
Suturing the proximal limb of the graft into aorta - posteriorly
F
Distal graft to femoral artery anastomosis - right side
I
Suturing the graft anteriorly
G
Distal anastomosis - left side
J

Figs 11-65E to J

Figs 11-65A to J: Aortic aneurysm exposure and placing aortofemoral graft.

of the prosthesis is secured on the femoral artery. Contralateral femoral artery is cannulated and prosthesis limb to opposite common iliac artery and femoral artery is placed. Suprarenal endovascular prosthesis needs fenestration for placement to maintain renal perfusion.

Percutaneous femoral artery puncture for device placement is also done. But open method is commonly advocated and safer.

Iliac vessels are also often used as access vessel.

EVAR is indicated if aneurysm is less than 5.5 cm in men and less than 5.0 cm in women. It is usually done in patients after 65 years.

Dacron or ePTFE is the material used as stent. Stent graft type, delivery system and skill for technique are essential. Many anatomical requirements are designed for successful EVAR.

Infrarenal neck is part of aorta between lowest renal artery and beginning of the aneurysmal sac. Anatomical requirements for effective EVAR are – proximal neck length should be more than 15 mm; diameter should be 18-32 mm; suprarenal angulation should be less than 60 degrees; infrarenal angulation should be less than 70 degrees; distal neck diameter should be more than 20 mm; common iliac vessel should be more than 15 mm in length; diameter is 8-25 mm.

Proper preoperative assessment is essential about site, extent and morphology of the aneurysm. Entire technique is done under radiological guidance and so C arm and radiologist's help is essential.

Technique

General or spinal or epidural or local anaesthesia is needed. Abdomen and both groins are prepared. After exposing both common femoral arteries with a small vertical groin incision, using loops proximal and distal control is achieved. Heparin infused as 100 units/kg dose. Both side femoral arteries are cannulated using 18 gauge needle and flexible J guidewire is passed under C arm guidance into thoracic aorta. Needle is removed; 7–9 French sheath is passed across guidewire; guidewire is removed; superstiff specialised guidewire (Meier wire) is inserted into the catheter and kept just below the left subclavian artery. Intra-operative intravascular ultrasound (IVUS) is very sensitive method of evaluating the aortic wall. Angioscaled pigtail catheter is passed through opposite common femoral artery into the abdominal aorta upto L_1, i.e. level of the renal arteries and aortogram is done to confirm the position of the renal arteries. Selected aortic endovascular graft is marked properly to identify upper part, right (same) side/limb and left limb. Graft is passed through *same side first* common femoral artery along superstiff guidewire; upper most part of the graft is positioned just below the level of renal arteries. Main body of the graft and same side limb of the graft are released and position is confirmed by C arm image. Superstiff guidewire is removed from same side common femoral artery. Position of opposite limb gate of the graft is confirmed by passing an angled guidewire and guide catheter through opposite limb into main body of the graft followed by injecting contrast agent. A balloon catheter passed through opposite limb of the graft and once balloon is in the body of the graft its position can be confirmed if inflated. IVUS is also very useful to confirm the position across opposite limb gate. Superstiff guidewire is passed through opposite common femoral artery across graft and aorta unto left subclavian artery level. *Opposite limb of graft* is inserted and deployed. Using a compliant balloon inflation upper end and lower ends of the graft is made to seat and seal properly into the aortic wall. A final check angiogram is done to find out endoleaks and confirm position. Sheaths and wires are pulled out. Arterial puncture site may often need polypropylene suture closure. Wound is closed. Distal pulses are checked.

Patient is discharged in 2 days. In postoperative period patient is monitored for leak, thrombosis, embolism and infection.

In suprarenal aneurysms branched or fenestrated aortic grafts are placed. But it is technically demanding.

EVAR is under trial in ruptured aortic aneurysm **(Figs 11-66A to D)**.

Problems and Complications

Problems are cost, displacement/malposition of graft, dissection, thrombosis, infection, iliac artery avulsion, need for replacement later often and endoleak. *Other complications* are – myocardial infarction; infection either local or wound or urinary or respiratory; ischaemia of sigmoid colon; distal embolisation; clamp injuries; renal failure; stent migration, stent fracture and kinking are other complications.

Endoleak is blood leak across the placed endovascular prosthesis material. Four types can occur in abdominal aortic endovascular prosthesis leak. Type I – Leak from proximal or distal ends from sides of the graft into aneurysm (Ia – proximal; Ib – distal; Ic – iliac plug site). Type II – Back bleeding from lumbar or inferior mesenteric artery into the aneurysmal sac which is the most common leak (IIa – single vessel bleed; IIb – multiple vessel inflow and outflow bleed). Type III – Leak from inadequate graft to graft overlap at junctions (IIIa – modular junction leak or disconnection; IIIb – graft fabric tear). Type IV – Leak from graft itself due to porosity of graft. All type I and II leaks need intervention; type III is mostly treated conservatively.

COMPLICATIONS OF REVASCULARISATION IN ACUTELY ISCHAEMIC LIMB

- *Reperfusion* injury
- 'No reflow' phenomenon – It is due to severe capillary oedema causing poor peripheral tissue hypoperfusion in spite of major vessel revascularization.
- Acute compartment syndrome can occur due to massive ischaemic oedema especially of skeletal muscles deep to deep fascia which compress on venules exceeding tissue interstitial pressure causing further compromise in tissue perfusion. Compartment pressure when measured using transducer needles will be more than 40 mm Hg or > 30 mm Hg for 3 hours or above the mean arterial pressure. Muscle weakness, sensory changes, leg pain which is aggravated by dorsiflexion of toes.
- Other complications are – sepsis, reblock, bleeding and catheter related complications.

Reperfusion Injury

- It occurs after reestablishment of arterial flow to an ischaemic tissue bed which further leads to tissue death causing specifically *peripheral muscle infarction*. It is due to sudden release of oxygen free radicals which block the microcirculation, with release of high levels of potassium (hyperkalaemia) and myoglobin (myoglobinaemia and myoglobinuria). Haemodynamically patient becomes unstable with lactic acidosis, intracellular changes, interstitial oedema and cardiac dysfunction. It is often life threatening.
- *Haimovici triad* of revascularisation injury (1960) – (1) Muscle infarction; (2) Myoglobinuria; (3) Acute renal failure.
- Severe ischaemia causes oedema in the muscular compartment with raise in compartment pressure more than the essential capillary perfusion pressure causing *acute compartment syndrome*. It is common in the anterior compartment of the leg. It is basically in the skeletal muscles deep to deep fascia. Compartment pressure when measured using transducer needles will be more than 40 mm Hg or > 30 mm Hg for 3 hours or above the mean arterial pressure. Muscle weakness, sensory changes, leg pain which is aggravated by dorsiflexion of toes.
- *No re-flow phenomenon* due to tissue oedema causing to capillary perfusion block. Even though compartment syndrome and 'no reflow' phenomenon are separate entities they are always seen together along with reperfusion injury.
- Metabolic acidosis, acute tubular necrosis causing acute renal failure and cardiac arrhythmias set in and become life threatening.
- **Features are** – toxaemia; oliguria; persistent pain and oedema in the leg with muscular tenderness; raised blood urea and serum creatinine with features acute ischaemia in the limb.
- **Treatment** –
  - Mannitol to prevent renal failure; fluid therapy.
  - Fasciotomy to reduce raised compartment pressure. All four compartments of lower limb should be decompressed surgically. Long vertical lateral deep fasciotomy incision in the calf behind the fibula along the deep fascia and its fibular attachments


A
B
C
D
Ipsilateral side:
Here main graft body
and ipsilateral side graft
is deployed.
Aorta
Contralateral side:
Here (opposite) common femoral
artery (CFA) is cannulated; later
after completion of deploying main
graft on the ipsilateral side this side
branch graft is deployed.
Renal
arteries
Aneurysm
Common
iliac artery
Internal
iliac artery
Common
femoral artery
Superstiff guidewire
Catheter
Renal arteries
Main
graft body
Aneurysm
Contralateral separate
modulus branch
Ipsilateral
attached
branch

(A) CFA of same side (ipsilateral) is exposed by open method; arteriotomy is done; (percutaneous method is also can be tried); arterial needle is passed into CFA.

(B) 18 G flexible guidewire is passed; needle is removed.

(C) 7/9 French sheath is passed into the artery.

(D) Catheter (vascular) is passed through guidewire; guidewire is removed.

(E) Superstiff guidewire is passed along the catheter upto thoracic aorta to pass main body and same side branch of the graft.

Catheter, superstiff guidewire is passed with ready to deploy the main graft body and same side iliac branch graft.

(A) Contralateral side CFA is cannulated to pass catheter; and ipsilateral side main graft body and same side CIA branch is ready for deploying into the place.

(B) Completion of deployment of body graft and branch graft of ipsilateral side; contralateral side CIA branch graft is deployed through opposite CFA using - needle - guidewire - sheath - catheter - superstiff guidewire - deploying the branch graft to attach to main graft.

(A) Opposite side (contralateral side) branch CIA graft is deployed through superstiff guidewire.

(B) Completion of procedure with graft in place. Arteriotomy is closed and skin incision is closed.

Figs 11-66A to D: Technique of endovascular aneurysm repair (EVAR).

is a must. Bleeding as patient is heparinised is common after fasciotomy. Infection of the wound can occur. Later once patient is stabilized and oedema subsides with healthy wound, secondary suturing or skin grafting is done. If fasciotomy is not done and if patient survives, it is with eventual Volkmann's ischaemic contracture.

- Antibiotics and supportive therapy.

ACUTE ISCHAEMIA

Acute ischaemia is a surgical emergency. It is common in lower limb but can occur in upper limb, mesenteric vessels, kidney, brain, etc.

Acute Limb Ischaemia

Acute limb ischaemia is either due to embolus or thrombosis. In embolic block critical period is 6 hours otherwise ischaemic damage is likely to occur. So early intervention to remove the block and to achieve revascularisation is needed. Once limb is non-viable and gangrenous attempt to revascularisation should be avoided as it will lead into multiorgan failure and death. Thrombolysis is not a suitable option in acute limb ischaemia as it takes time to act; before that limb becomes nonviable. Emergency Doppler is sufficient. If facilities are available angiogram can be done; but for the sake treatment cannot be delayed. On table angiography is very useful. Immediate anticoagulation is done with 10,000 units of heparin. C*ommon sites of embolus block* in limbs are—common femoral artery in the groin and brachial artery in elbow. Embolus block precipitates thrombus formation proximally and distally which propagates on both directions **(Figs 11-67 to 11-69)**.

Femoral Embolectomy

It is done under local anaesthesia. *C arm imaging facility* should be there ideally in theatre while doing embolectomy. If additional procedure like bypass graft is required then spinal or general anaesthesia is needed. Entire limb should be prepared for the procedure to observe distal perfusion. Oblique or vertical incision is made in the thigh along the line of femoral artery; skin, subcutaneous tissue, Scarpa's fascia is incised. Common femoral, superficial femoral and profunda femoris arteries are identified; dissected and slings are placed around each. Longitudinal or oblique arteriotomy is done in the common femoral artery often extending into the profunda femoris artery in case if profundaplasty with venous patch is needed. Size 4 Fogarty catheter is passed along the iliac artery proximally to clear the thrombus to achieve good inflow; immediately iliac artery is flushed with heparinised saline (2000 units in 500 ml of saline). Size 3 Fogarty catheter is passed distally along the superficial femoral artery; small fragments or ribbon arterial cast with propagated thrombus is extracted from distal part. It is repeatedly passed until all fragments are cleared with adequate back bleeding. Usually catheter is passed around 40 cm distally to achieve good embolectomy **(Fig. 11-70)**.



Fig. 11-67: Digital subtraction angiogram showing block in left aortoiliac segment. It is corrected by PTA (percutaneous transluminal angioplasty).



Fig. 11-68: Digital subtraction angiogram showing superior mesenteric artery block/stenosis which is corrected by PTA.



Fig. 11-69: Percutaneous transluminal angioplasty (PTA) balloon catheter in place.

A completion angiogram is done to confirm the adequacy of the flow, if reperfusion is poor, if Fogarty cannot be passed beyond adductor hiatus. Adherent clot can be lysed by direct injection of the tissue plasminogen activator (TPA) 10 mg in 20 ml saline, into the clot for 30 minutes. Profundaplasty may be added to prevent narrowing and rethrombosis.

Brachial Endarterectomy

Usual site of embolic block is at its bifurcation in antecubital fossa. Procedure is done usually under local anaesthesia. Entire limb should be cleaned from shoulder and axilla to hand. A lazy S incision is made from medial part of lower arm across biceps tendon down into the forearm. Brachial artery is deep to bicipital aponeurosis which can be divided. Median nerve should be taken care of and retracted. Brachial artery with its bifurcation branches is dissected and isolated with slings/loops. Bulldog clamps are applied to arteries. A transverse



Fig. 11-70: Technique of arterial embolectomy.

arteriotomy is made 1 cm proximal to bifurcation over brachial artery. Fogarty catheter is passed proximally and block is removed to clear inflow which is infused with heparinised saline. Distal arteries are also cleared by passing Fogarty catheter into ulnar and radial arteries. Clamps are released—first the proximal clamp and then distal clamps. Good back feeding should be achieved. Completion angiogram is done. Arteriotomy is closed using 6 zero polypropylene sutures. *Complications* are – bleeding, thrombosis, infection and failure.

Saddle Embolus

It is the large embolus blocking at bifurcation of aorta presenting with acute ischaemic features in both limbs. Doppler and angiogram is diagnostic. It is usually due to large mural thrombus blocking at the bifurcation. Cardiac opinion and echocardiography is a must **(Fig. 11-71)**.


Saddle embolus at aortic bifurcation
Embolus retrieval through bilateral femoral artery approach

Fig. 11-71: Saddle embolus at the aortic bifurcation. It is retrieved by embolectomy from bilateral femoral artery approach.

Embolectomy is done by passing Fogarty catheter balloon through both femoral arteries. Patient should be heparinised. On table angiogram is a must.

THORACOABDOMINAL ANEURYSM

Type I – It involves descending thoracic aorta and abdominal aorta up to the origin of visceral vessels.

Type II – Aneurysm involving entire descending thoracic and entire abdominal aorta.

Type III – It involves lower part of descending thoracic aorta and entire abdominal aorta.

Type IV – Entire abdominal aorta including suprarenal portion (but aorta above the diaphragm is normal) **(Fig. 11-72)**.



Fig. 11-72: Classification of thoracoabdominal aneurysm.

Exposure - Patient is placed of left side thorax and abdomen upwards with thoracoabdominal approach. Spleen with left kidney is rotated medially to access the abdominal aorta upper part. Left lung is collapsed to visualise the thoracic aorta. Inflow may be maintained by temporary shunting or left heart bypass to femoral artery which will maintain visceral perfusion. Cooling of the kidneys and diuretics is needed as an additional protection. Aneurysm is opened. Pair of intercostal vessels is reimplanted into the graft first to maintain the blood flow of spinal cord. Graft is sutured proximally into the thoracic aorta after proximal clamping distal to bypass. Visceral arteries (coeliac trunk, SMA, IMA, right renal artery) are anastomosed with a part of native aorta at their origin into the hole made in the graft. Left renal artery origin is separately implanted into the graft with a similar patch of native aorta. Distal end of the graft is anastomosed to distal end of the aorta distal to aneurysm level. Procedure is done usually by a cardiothoracic or vascular surgeon.

Problems are – spinal cord ischaemia with paraplegia; myocardial ischaemia; reperfusion injury.

RENAL REVASCULARISATION

Renal artery stenosis more than 70% will deteriorate the kidney function. Angioplasty is ideal in stenosis due to fibromuscular dysplasia.

Renal endarterectomy can be done with a venous patch over the stenosed area.

A graft can be used between terminal renal artery and infrarenal part of the aorta. Renal artery is ligated at its origin. Distal end of renal artery is anastomosed into the end of the arterial graft, the other end of it to side of the infrarenal portion of the aorta. If aorta is very much diseased, then right renal artery is anastomosed to hepatic artery and left renal artery is anastomosed to splenic artery after splenectomy **(Fig. 11-73).**

EXPOSURE OF CAROTID ARTERY

It is indicated in endarterectomy to prevent stroke; excision of carotid body tumour; carotid artery aneurysm repair; in trauma of carotid artery.

Anaesthesia – general or local (in case of emergency).

Position – supine with head extended and turned away from the side of the surgery with sandbag under the shoulder.

Incision – from upper margin of the medial end of the clavicle along the anterior margin of the sternocleidomastoid muscle to the angle of the jaw extending above further backwards. Transverse skin crease/S shaped incision are also helpful for a better cosmetic look.

Anatomy

Right CCA begins as a branch of brachiocephalic artery behind the right sternoclavicular joint. *Left CCA* arises from arch of aorta in the thorax in front of trachea and behind left of the manubrium to continue in the neck under left sternoclavicular joint. In the neck it runs upwards along and deep to inner border of sternocleidomastoid muscle; in front of transverse processes of lower four cervical vertebrae. At the level of thyroid cartilage it divides into external and internal carotid arteries. In front it is related to superior belly of omohyoid (crosses artery), descending hypoglossi nerve, superior thyroid vein, sternothyroid, ansa cervicalis, sternohyoid, anterior jugular vein, middle thyroid vein and sternomastoid. Behind the CCA sympathetic chain descends and ascending cervical artery ascends behind the CCA; inferior thyroid artery crosses medially behind the CCA; left side thoracic duct crosses CCA laterally behind. *Carotid sheath* encloses CCA, IJV (lateral to artery) and vagus nerve (behind). *Carotid sinus* is dilated terminal CCA and beginning of ICA which has got thin media and thick adventitia with rich glossopharyngeal and sympathetic innervations which act as baroreceptor. Carotid body is a small, oval reddish brown body located behind bifurcation of CCA with glossopharyngeal innervation; acts as chemoreceptor.



After applying side vascular clamp, renal artery is opened; endarterectomy is done; venous patch is placed on to the arteriotomy site to widen the narrowed segment

Fig. 11-73: Renal endarterectomy with venous patch over the stenosed area.

ECA begins as one of the terminal branches of CCA and runs as anteromedial to ICA in lower part and anterolateral to ICA in upper part. ECA is convex towards front in lower part; concave towards front in upper part. In the carotid triangle, ECA is crossed in front by cervical branch of facial nerve, hypoglossal nerve, facial, lingual and superior thyroid veins; deeply it is related to pharynx, superior laryngeal nerve with its external and internal branches. Above the carotid triangle ECA enters the parotid gland; here it is related in front to retromandibular vein and facial nerve; behind to (1) ICA; (2) styloglossus, stylopharyngeus, glossopharyngeal nerve, pharyngeal branch vagus, styloid process (which passes between ECA and ICA); (3) superior laryngeal nerve and superior cervical sympathetic ganglion (are deep to ICA). Branches of ECA (8) are – In front are superior thyroid, lingual and facial; behind are occipital and posterior auricular; medial is ascending pharyngeal and terminal are larger maxillary and smaller superficial temporal.

ICA is one of the terminal branches of CCA beginning at upper level of thyroid cartilage opposite C3 and C4 vertebral disc entering into carotid canal to reach the cranial cavity. It has got 4 parts – cervical; petrous; cavernous; and cerebral. At the beginning there is dilatation called as carotid sinus. In the carotid triangle below it is related in front to sternomastoid muscle, hypoglossal nerve, descending hypoglossi, occipital artery, common facial and lingual veins, and ECA (anteromedial). In the digastrics triangle above it is related in front to posterior belly of digastric, stylohyoid, posterior auricular artery, stylopharyngeus, styloid process, parotid, glossopharyngeal nerve, pharyngeal branch of vagus, cartilaginous part of auditory tube, tensor veli palatine. Posteriorly it is related to longus capitis, superior cervical ganglion, superior laryngeal nerve, carotid sheath, pharyngeal veins, vagus (posterolateral), glossopharyngeal, hypoglossal and accessory nerves. There are no branches to ICA in neck.

Exposure (Fig. 11-74)

Cervical branch of facial nerve should not be injured in upper most part of the incision especially in transverse incision (upper posterior part of the incision should be 1.5 cm below the angle of the mandible in transverse). Platysma and deep fascia are incised in the line of incision → external jugular vein is divided between ligatures → flaps are raised → anterior margin of sternomastoid is dissected and retracted behind → common facial vein which crosses CCA just below the bifurcation in front is identified and divided (supraorbital and supratrochlear veins join to form angular vein which continues as facial vein down and is joined by deep facial vein which is an extension vein from pterygoid plexus; this facial vein is joined by anterior division of retromandibular vein to form common facial vein which joins IJV. Posterior auricular vein joins posterior division of retromandibular vein to form external jugular vein which joins subclavian vein below) → IJV is identified as bluish tubular structure with thin wall and is retracted backwards → carotid is identified → descending branch of hypoglossal nerve (can be cut if needed) and main hypoglossal nerves (just above CCA bifurcation) are identified and retained. Thyroid and strap muscles are retracted anteromedially to expose superior thyroid artery and superior laryngeal nerve (deeper); posterior belly of digastric and parotid and greater auricular nerve are identified above. ICA above in the neck is dissected properly (if needed) by dividing digastric tendon, stylohyoid muscle; or often with subluxation of jaw in forward direction **(Figs 11-75 and 11-76)**.


Longitudinal incision
Horizontal incision
'S' incision
Digastric (posterior belly)
Hypoglossal nerve
ECA
Common facial vein (ligated)
ICA
Sternocleidomastoid muscle (retracted behind)
Superior thyroid artery
Common facial vein (ligated)
Strap muscles (retracted front)
CCA
Descending hypoglossi
IJV

Fig. 11-74: Incision and exposure of carotid artery.


IJV
ECA
Superior thyroid artery
Aneurysm
Right lobe of thyroid
Right common carotid artery
Inferior thyroid artery

Fig. 11-75: Carotid artery aneurysm and its repair using graft.



Fig. 11-76: Carotid-axillary bypass. It bypasses the subclavian artery in its stenosis/blockage.

Different procedures of carotids can be undertaken like repair of carotid using venous patch, endarterectomy, carotid artery aneurysm repair using graft, graft reconstruction, ligation of ECA. *ECA ligation* is done just above the level of the superior thyroid artery to avoid turbulence effect on the carotid and so formation of thrombus proximally. ECA is ligated in torrential bleeding in face, antrum, larynx, traumatic damage of the ECA. CCA and ICA should not be ligated but should be reconstructed as chance of the person developing hemiplegia is 40%.

EXPOSURE OF VERTEBRAL ARTERY

Anatomy

It originates from first part of subclavian artery ends by joining the opposite vertebral artery to form basilar artery. It has got 4 parts. First part extends from its origin to transverse process of 6th cervical vertebra. First part is located in vertebral triangle bound by scalenus anterior and longus colli muscles; runs upwards and backwards; related (anteriorly) to carotid sheath, vertebral vein, inferior thyroid artery and thoracic duct on left side; posteriorly to transverse process of C_7 vertebra, inferior cervical ganglion and ventral rami nerves of C_7,C_8. Second part runs through foraminae of transverse processes of upper six vertebrae. It is accompanied by venous plexus and large branch of stellate ganglion. Third part lies in suboccipital triangle lying on the posterior arch of the atlas bone extending from transverse foramina of atlas to vertebral canal across lower arched margin of posterior atlanto occipital membrane. It is related to atlas, vertebral muscles, and first cervical nerve. Fourth part extends from atlantooccipital membrane to lower part of pons to join opposite vertebral artery to form basilar artery. It pierces the dura, arachnoid in front of roots of hypoglossal nerve, medulla to reach lower margin of pons. Branches are – spinal, muscular, anterior spinal, posterior inferior cerebellar (largest), often posterior spinal and medullary.

Exposure

Oblique incision lateral to the sternocleidomastoid muscle → lateral part of the muscle is cut → IJV is exposed → vagus is identified → both IJV and vagus are retracted laterally → carotid artery is identified and dissected meticulously to retract medially → dissection is done between carotid and IJV → vertebral vein runs crossing the artery in front from medial to lateral → vertebral artery is identified behind the vein with crisscrossed cervical sympathetic chain. Vertebral vein can be divided to expose the artery properly. Sympathetic fibers crossing the artery can be divided **(Fig. 11-77)**.

Distal part of the artery is also exposed by extending the same incision above; levator muscle is identified and is divided after protecting the accessory nerve which crosses the muscle. Anterior ramus of C2 nerve is seen crossing the artery which can be divided.

EXPOSURE OF SUBCLAVIAN ARTERY

Anatomy

Subclavian artery arises on the right side from brachiocephalic artery and left side from arch of aorta. It begins behind the sternoclavicular joint curving with convexity upwards reaching outer part of the first rib to continue as axillary artery. Left artery has got thoracic part behind the left side of manubrium and left of left common carotid artery. Artery is divided into three parts by scalenus anterior muscle. First part is medial; second part is behind; third part is lateral to scalenus anterior.

Artery is related *in front* from medial to lateral to – CCA, ansa cervicalis, cardiac branches of vagus, sympathetic trunk, vagus, vertebral vein, IJV, phrenic nerve (left side it is in front of first part; right side it is in front of second part) and thoracic duct (left side), scalenus anterior, transverse cervical artery, suprascapular artery, subclavian vein, anterior jugular vein, suprascapular vessels, external jugular vein, transverse cervical vein, subclavius muscle, middle ⅓ of clavicle, sternocleidomastoid muscle.

Behind it is related to suprapleural membrane, cervical pleura, apex of lung, ansa subclavian, right recurrent laryngeal nerve (right side), scalenus medius, lower trunk of brachial plexus. *Above* it is related to inferior belly of omohyoid, upper and middle trunks of brachial plexus. *Below* it is related to first rib.

Branches are usually four – vertebral (largest), internal thoracic and thyrocervical arteries arise from first part of the subclavian artery. Thyrocervical artery gives inferior thyroid, suprascapular and transverse cervical branches. Costocervical artery arises from second part of the subclavian artery on right side (from first part on left side) which gives superior intercostal and deep cervical arteries. Occasionally dorsal scapular artery as a 5th branch may arise from third part of the subclavian artery.


Basilar artery
Atlas (C1)
Axis (C2)
C3
C4
C5
C6
C7
T1
T2
Scalenus anterior
First rib
Subclavian artery
Common carotid artery (right)
Brachiocephalic artery
Vertebral artery
Incision - oblique along the posterior border of sternomastoid
Incision
Vertebral vein
Sternocleidomastoid muscle
Common carotid artery (retracted medially)
Cervical sympathetic chain
Vertebral artery
Vagus
IJV (both retracted laterally)
Exposure

Fig. 11-77: Anatomy and exposure of vertebral artery.

Right subclavian artery may originate from descending thoracic aorta passing behind the oesophagus causing dysphagia called as *dysphagia lusoria*.

Exposure

Arm is placed to the side of the patient and drawn downwards to depress the shoulder with head turning to opposite side. Incision is made just above (1 cm) and parallel to clavicle from sternal head of sternocleidomastoid to anterior margin of trapezius. Superficial fascia, platysma and deep fascia are divided in the line of incision. External jugular vein is ligated. Supraclavicular nerve is identified and cut or retracted. Omohyoid is retracted above. Suprascapular artery, vein and nerve are identified crossing the third part of the subclavian artery superolaterally. Subclavian artery is identified along with upper and middle trunks of brachial plexus. To expose the 2nd and 3rd parts clavicular head of sternomastoid and scalenus anterior are cut. Care should be taken not to injure phrenic nerve which crosses the scalenus anterior in front from lateral to medial. Nerve is gently slinged and retracted. IJV is retracted medially to expose the subclavian artery. Division of sternal head of sternocleidomastoid and median sternotomy is needed to approach the origin of subclavian artery and brachiocephalic artery **(Figs 11-78 and 11-79)**.

Distal 3rd part of subclavian and proximal 1st part of the axillary artery is exposed by infraclavicular incision or supraclavicular incision extending laterally and across the clavicle. Division of clavicle in this exposes the entire subclavian artery. In inevitable situation 3rd part of subclavian artery can be ligated.

EXPOSURE OF AXILLARY ARTERY

Axillary artery as a continuation of subclavian artery extends from outer border of first rib to lower border of teres major muscle. It is


Sternocleidomastoid muscle
Clavicle
Incision
Extension of incision if needed - clavicle should be cut

Fig. 11-78: Incision for subclavian and axillary artery exposure. If needed clavicle is cut.


Scalenus anterior
First rib
Axillary artery
CCA
Right subclavian artery
Left subclavian artery
Brachiocephalic artery
Descending thoracic aorta
Arch of aorta
A
First rib
Scalenus anterior
Phrenic nerve
Inferior thyroid artery
Transverse cervical artery
Vertebral artery
Suprascapular artery
CCA
Axillary artery
Brachiocephalic artery
Costocervical trunk (origin is from behind)
Subclavian artery
Internal mammary (thoracic) artery
Thyrocervical trunk
B
Incision—1-2 cm above and parallel to the clavicle
Sternocleidomastoid cut part
Sling
Phrenic nerve
Scalenus anterior is cut over a blunt spatula placed underneath; phrenic nerve should be safeguarded using a sling.
C

Figs 11-79A to C



Fig. 11-79D

Figs 11-79A to D: Anatomy and exposure of subclavian artery.

divided into three parts by pectoralis minor as above (first part), behind (second part) and below (third part). It is related in front to skin, superficial fascia, platysma, supraclavicular nerves, deep fascia, pectoralis major, and clavipectoral fascia with cephalic vein, lateral pectoral vein and thoracoacromial vessels and pectoralis minor. Behind it is related to parts of brachial plexus, serratus anterior digitations, coracobrachialis, tendons of latissimus dorsi and teres major. Medially it is related to axillary vein. Axillary sheath encloses the axillary artery and brachial plexus which is derived from prevertebral layer of deep fascia. Axillary sheath *does not enclose* the axillary vein.

Branches of axillary artery are—superior thoracic artery (first part), thoracoacromial artery (second part), lateral thoracic artery (second part), subscapular artery (largest branch, third part), and anterior circumflex and posterior circumflex arteries (third part) **(Fig. 11-80)**.



Fig. 11-80: Anatomy of the axillary artery.

Surface Marking of Axillary Artery

Arm is held at right angles to the trunk with palm facing forward; it extends from midpoint of the clavicle to a point at the junction of anterior 1/3rd to posterior 2/3rd of the lateral wall of axilla at its lower limit.

Exposure

Two incisions can be used. One is lengthy incision along the deltopectoral groove from lower border of clavicle to lower border of anterior axillary fold. Another is small incision in infraclavicular area horizontally placed along the clavipectoral fascia. This incision is also used to expose the third part of the subclavian artery. Often in trauma more extensive exposure of axillary and subclavian arteries together is needed and in such situation lengthy deltopectoral groove incision extending upwards into the neck across clavicle with resection of the middle third of the clavicle is done **(Fig. 11-81)**.

EXPOSURE OF BRACHIAL ARTERY

Anatomy

Brachial artery is the continuation of the axillary artery extending from lower border of teres major to a point in front of the elbow at the level of neck of radius just medial to the biceps brachii. It runs downwards and laterally to end in front of elbow bifurcating into radial and ulnar arteries. It is superficial throughout its extent and is accompanied by two venae comitantes. In the upper part it is related to medial cutaneous nerve of the forearm; in the middle part it is crossed by median nerve from lateral to medial side; in front of the elbow it is crossed/covered by bicipital aponeurosis (crosses artery from lateral to medial side). Posteriorly it is related to triceps, radial nerve, profunda brachii artery, coracobrachialis, brachialis. Medially in the upper part it is related to ulnar nerve, in the lower part to median nerve (crosses the artery from lateral to medial in front). Laterally it is related to coracobrachialis, biceps, median nerve in the upper part; tendon of biceps in the lower part. In the elbow, structures from lateral to medial are—radial nerve, biceps tendon, brachial artery and median nerve. It divides as terminal branches in *cubital fossa* in the elbow. It is a triangular hollow situated in front of the elbow; its lateral border is formed by medial margin brachioradialis; medial border is by lateral margin of pronator teres; base is directed upwards is formed by line joining the two epicondyles of humerus with apex pointing downwards **(Fig. 11-82)**.

It gives muscular branches, profunda brachii artery, superior ulnar collateral branch, nutrient artery, inferior ulnar collateral branch, radial and ulnar arteries. Brachial artery may divide into radial, ulnar, common interosseous branches at higher level than usual; or as radial and common trunk of ulnar and common interosseous branches.

Exposure (Fig. 11-83)

Incision is made in the upper arm along its medial border just behind the biceps muscle. Once skin and deep fascia is incised, identified biceps muscle is retracted in front; triceps posteriorly; artery is identified with median nerve lying superiorly and laterally which later crosses the artery in front towards medial side. Basilic vein will be lying medial to the artery in the upper part; two venae comitantes accompany the artery in the lower part. Basilic vein is retracted posteriorly to identify the ulnar nerve.

Bifurcation is exposed at cubital fossa using an S shaped incision; not with vertical incision. A transverse incision can also be used.


Axillary artery
aneurysm-angiogram
Aneurysm bypassed using
a reverse venous graft
Axillary artery aneurysm is
bypassed using a reverse
vein graft-
graft is shown after suturing

Fig. 11-81: Exposure of axillary artery aneurysm and repair and reconstruction using graft.

Bicipital aponeurosis which runs in front from lateral to medial side is divided. Median nerve will be posteromedial to the artery.

EXPOSURE OF RADIAL AND ULNAR ARTERIES

Anatomy

Radial artery is a smaller terminal branch (and more superficial compared to ulnar) of brachial artery extending from a point in front of the elbow at the level of neck of the radius medial to the tendon of the biceps brachii to a point at the wrist between anterior border of the radius laterally and the tendon of the flexor carpi radialis medially. It runs downwards to the wrist and enters the anatomical snuff box turning posteriorly. It is overlapped by brachioradialis above and skin, superficial and deep fascia below. Posteriorly it is related to biceps tendon, supinator, pronator teres tendon, radial origin of flexor digitorum superficialis (FDS) and flexor pollicis longus (FPL), pronator quadratus, lower end of radius. Medially it is related to pronator teres above and flexor carpi radialis in the lower 2/3rd; laterally to brachioradialis entirely and radial nerve in the middle third. Artery


Radial nerve
Teres major muscle
Ulnar nerve
Brachial artery
Median nerve
Biceps brachii tendon
Neck of the radius
Radial artery
Bicipital aponeurosis
Ulnar artery
Biceps brachii
Radial nerve
Deep branch
Radial artery
Brachial artery
Pronator teres heads
Deep
Superficial
Ulnar nerve
Ulnar artery
Median nerve
Lateral side
Medial side
Biceps brachii
Brachial artery
Radial artery
Radial nerve
Ulnar artery
Ulnar nerve
Median nerve
Flexor carpi redialis tendon

Fig. 11-82: Anatomy and branches of brachial artery.


Brachial artery
Axillary artery
Clavicle
Incision
Lateral axillary fold

Fig. 11-83: Incision for exposure of brachial artery.

is accompanied by a pair of venae comitantes. *Branches are* – radial recurrent, muscular, palmar carpal, superficial palmar.

Ulnar artery is the larger terminal branch of brachial artery beginning at cubital fossa running obliquely downwards and medially in upper 1/3rd of forearm; vertically in lower 2/3rd of forearm enters the palm by passing superficial to flexor retinaculum. At lateral part of the pisiform bone it enters the palm. Artery in its upper half is covered by pronator teres with median nerve, flexor carpi radialis, Palmaris longus, flexor digitorum superficialis, flexor carpi ulnaris; lower half is covered by skin, superficial and deep fascia and palmar cutaneous branch of ulnar nerve; posteriorly above brachialis and below flexor digitorum profundus; medially to ulnar nerve and flexor carpi ulnaris; laterally flexor digitorum superficialis. *Branches are* – anterior and posterior ulnar recurrent arteries, common interosseous artery, anterior interosseous artery, muscular branches, palmar and dorsal carpal branches **(Fig. 11-84)**.

Both arteries are *exposed* through different vertical incisions on either side of the forearm. Radial artery is exposed by retracting the brachioradialis medially and flexor carpi radialis laterally. Ulnar artery is exposed by dissecting pronator teres and brachioradialis laterally and flexor digitorum medially.


'S' shaped incision in cubital fossa to expose brachial artery end
Exposure incisions for radial and ulnar arteries at forearm and wrist

Fig. 11-84: Exposure of brachial bifurcation and branches (radial and ulnar arteries).

EXPOSURE OF ASCENDING AORTA AND ARCH OF THE AORTA

Anatomy

Five cm long ascending aorta originates from upper end of left ventricle enclosed with pericardium; it begins at the level of lower border of 3rd costal cartilage behind the left half of the sternum, runs upwards, forwards and right continuing as arch of aorta at the upper border of the 2nd costal cartilage. At the root of the aorta there are 3 sinuses (dilatations) – right and left posterior and anterior. Right coronary artery arises from anterior sinus; left coronary arises from left posterior aortic sinus.

Arch of aorta is situated in superior mediastinum behind the lower half of the manubrium sterni. From the upper end of ascending aorta it runs upwards, backwards and to left of trachea near carina, then passing behind the left bronchus arching over the root of left lung to continue as descending aorta at the level of left side lower border of the body of 4th thoracic vertebra. It begins anteriorly and ends posteriorly. Anteriorly it is related to left phrenic nerve, lower cervical branch of left vagus, upper cervical cardiac branch of left sympathetic chain, left vagus; left superior intercostal vein between phrenic and vagus nerves; left pleura and lung, thymic remnants. Posteriorly it is related to trachea, deep cardiac plexus, tracheobronchial lymph nodes, oesophagus, left recurrent laryngeal nerve, thoracic duct and vertebra. Below to pulmonary trunk bifurcation, left bronchus, ligamentum arteriosus and left recurrent laryngeal nerve. Branches are—brachiocephalic artery, left common carotid and left subclavian arteries; often thyroidea ima artery and occasionally vertebral artery.

Exposure (Fig. 11-85)

Vertical sternotomy incision is used. After skin incision, a Robert's or Kocher's clamp is passed underneath the sternum along the free space underneath to pass a Gigli saw by which sternum is divided. Electric saw also can be used. Sternum is retracted using self retaining retractor; brachiocephalic vein is retracted downwards. Aortic arch, roots of brachiocephalic, left carotid and subclavian arteries are exposed.

Aortic arch branches are exposed through an additional transverse neck incision on the upper part of the sternotomy. Through this transverse incision if sternocleidomastoid and scalenus anterior is divided, subclavian artery can be exposed at neck in its entire length.

EXPOSURE OF DESCENDING THORACIC AORTA

Anatomy

It is continuation of the arch of aorta at the level of 4th thoracic vertebral body, descending downwards with right side inclination in posterior mediastinum at the lower border of the 12th thoracic vertebra. It is related anteriorly to root of left lung, pericardium, heart, oesophagus in the lower part and diaphragm; posteriorly to hemiazygos vein and vertebrae; to the right side oesophagus in upper part, azygos vein, thoracic duct, right lung and pleura; to the left side left lung and pleura. Branches are – 3rd to 11th intercostal arteries (total 9 × 2 = 18); two subcostal arteries one on each side; two left bronchial arteries (*Note*: Right bronchial artery is arising from right 3rd posterior intercostal artery usually, occasionally from upper left bronchial artery); oesophageal branches; pericardial branches; superior phrenic arteries.

Exposure

Descending thoracic aorta is exposed through left posterolateral thoracotomy through 5th or 8th intercostal space. Usually rib is removed and thoracic cavity is entered; lung is displaced forward; descending aorta will be seen posteriorly running vertically **(Fig. 11-86)**.


-Skin is retracted;
-Sternum is exposed;
-Long Kocher's forceps is passed underneath the sternum.
-Gigli's saw is passed underneath to cut the sternum.

Brachiocephalic artery
Right brachio-cephalic vein
Left brachio-cephalic vein
SVC
Left CCA
Ascending and arch of aorta

Fig. 11-85: Exposure of ascending aorta technique.


Incision can be extended down into the abdomen if upper abdominal aorta exposure is needed simultaneously
7
5
5th or 7th intercostal space approach

Fig. 11-86: Exposure of descending thoracic aorta either through 5th or 7th intercostal space which can be extended down into abdomen if needed to expose the proximal abdominal aorta also.

Same incision can be extended down in middle over the abdomen to expose the *upper abdominal aorta along with thoracic aorta.* Diaphragm is divided transversely close to the costal margin to avoid damage to phrenic nerve. Vertical incision in the costal margin will expose better but often damages the phrenic nerve. Through the wound liver, spleen, abdominal contents are visualised; peritoneum lateral to the spleen is incised to mobilise the spleen, colon, pancreas towards the right. It exposes the upper abdominal aorta with its branches in the upper part namely coeliac artery, superior mesenteric artery and renal vessels with left renal vein crossing the aorta in front towards IVC.

EXPOSURE OF ABDOMINAL AORTA AND BRANCHES

Anatomy

Abdominal aorta begins from aortic opening of diaphragm at the level of lower border of T12 vertebra, running downwards and slightly left in front of lumbar vertebra ending at lower border of L4 vertebra about 1 cm left of midline by dividing into two common iliac arteries.

Its surface marking is – from a point 2.5 cm above the transpyloric plane in midline to a point 1.25 cm below and left of the umbilicus.

Anteriorly abdominal aorta is related to celiac plexus, aortic plexus, body of pancreas, splenic vein, left renal vein, 3rd part of the duodenum, retroperitoneum and intestine in abdominal cavity. Posteriorly it is related to bodies of upper four lumbar vertebrae, anterior longitudinal ligament, left lumbar veins, origin of lumbar arteries; towards the right related to IVC with sympathetic chain behind, right crus of diaphragm, cisterna chyli, azygos vein, lumbar lymph node; towards left it is related to left crus of diaphragm, pancreas, 4th part of the duodenum, left sympathetic chain, lumbar lymph nodes.

Branches of abdominal aorta – *Ventral (supply gut)*: Coeliac trunk, superior mesenteric artery (SMA), inferior mesenteric artery (IMA); *Lateral (supply structures from intermediate mesoderm)*: Inferior phrenic arteries, middle suprarenal arteries, renal arteries, gonadal arteries; *Dorsal (somatic)*: 4 pairs of lumbar arteries, median sacral artery.

Infrarenal aorta is more mobile and accessible than suprarenal. IMA and gonadal arteries can be sacrificed. Origins of major arteries prevent mobilisation of upper abdominal aorta. Celiac trunk, pancreas, splenic vein, left renal vein, duodenum all obscure proper mobilisation.

Exposure

Lengthy midline (common) or transverse or oblique incision is used. Once peritoneum is opened, omentum and transverse colon is pushed upwards; small bowel is displaced to the patient's right; duodenojejunal flexure is identified and an incision is made lateral to the 4th part of duodenum; retroperitoneum is opened; entire small bowel with duodenojejunal flexure is mobilised medially towards right (medial mobilisation of the viscera). Aorta is identified and mobilised; infrarenal aorta is occluded with vascular clamp with finger guidance with care about IVC and left renal vein.

Coeliac axis is exposed through lesser omentum. Crura are dissected and divided. With careful blunt and sharp dissections coeliac trunk is identified **(Figs 11-87 and 11-88)**.

It is artery of foregut supplying lower oesophagus, stomach, duodenum up to sphincter of Oddi, liver, pancreas and spleen.


Liver
Oesophageal branches
Left gastric artery
Splenic artery
Short gastric arteries
Coeliac trunk
Common hepatic artery
GB
Cystic artery
Right hepatic artery
Proper hepatic artery
Right gastric artery
Gastroduodenal artery
Aorta
Spleen
Arteria pancreatica magna
Right
Left
Gastroepiploic arteries

Fig. 11-87: Anatomy of coeliac trunk and branches.


Coeliac trunk
Renal arteries
SMA
IMA
Aorta
Aortic graft

Patch of native aorta with origin of visceral arteries and separate patch with origin of left renal artery are taken and implanted into the graft

Fig. 11-88: Origin of visceral branches of aorta with a cuff of native aorta can be removed and reimplanted into the aortic graft.

It originates just 1 cm below the aortic opening (T12 vertebra) at intervertebral disc level between T12 and L1. Trunk is *very short* in length (1.25 cm). It divides into three terminal branches—left gastric, common hepatic and splenic arteries. *Smallest left gastric artery* runs upwards to the left behind the lesser sac to reach OG junction where it turns forwards into the lesser omentum along the lesser curve towards right to anastomose with the right gastric artery. It gives oesophageal branches and gastric branches. Once branch enters the lesser omentum, it is often called as descending branch of left gastric artery. *Common hepatic artery (CHA)* runs forward, downward and towards right behind the lesser sac and at upper border of the duodenum it enters the lesser omentum in front of the portal vein and left of CBD to end as right and left hepatic arteries. Gastroduodenal artery is the first main branch of the CHA which arises at upper part of the first part of the duodenum as a large branch, runs downwards behind the 1st part of the duodenum dividing at its lower border as right gastroepiploic artery (runs along the greater curvature in the greater omentum to anastomose with left gastroepiploic artery) and superior pancreaticoduodenal artery (often 2 in number as anterior and posterior; runs in the pancreaticoduodenal groove ending by anastomosing with inferior pancreaticoduodenal artery, a branch of SMA). CHA distal to gastroduodenal artery is called as proper hepatic artery (PHA) which gives right gastric artery just distal to the origin of gastroduodenal artery runs towards left along the lesser curvature to anastomose with left gastric artery. *Small supraduodenal artery* often may be present to supply proximal duodenum. Cystic artery arises from right hepatic artery, runs behind the CHD and cystic duct to reach neck of the gallbladder and dividing into superficial and deep branches. *Splenic artery is the largest branch* of the coeliac trunk runs transversely towards left along the upper border of the pancreas behind the lesser sac crossing left adrenal gland and kidney entering lienorenal ligament and splenic hilum dividing into many branches to enter into the spleen. Splenic artery branches are—numerous pancreatic branches; arteria pancreatica magna; arteria caudae pancreatis; 5-7 short gastric arteries along the gastrosplenic ligament to supply gastric fundus; left gastroepiploic artery **(Fig. 11-89)**.



(A)
Incision to expose celiac trunk and SMA along the lateral border of descending colon and spleen

(B)
Incision to expose SMA along the margin of duodenojejunal flexure


Incision in the lesser omentum to expose the coeliac trunk
Incision in the greater omentum close to the spleen to expose the splenic artery

Fig. 11-89: Exposure of coeliac axis and its branches.

SMA origin is exposed by incising the peritoneum vertically lateral to spleen and colon and mobilising the spleen and pancreas in front of left kidney towards right side. Origin of SMA will be well exposed. SMA distal to its origin is exposed once small intestine is mobilised towards right; mesentery with its free edge is identified; mesenteric leaf is incised to expose the artery with superior mesenteric vein. SMV is towards the right of the SMA. SMA is the artery of midgut. It originates from the front of the aorta at the level of L1 behind the body of pancreas usually 1.0 cm below the origin of coeliac trunk. It descends down behind the pancreas body, in front of the uncinate process crossing the duodenum to enter the root of mesentery directed towards right with a convexity towards left, ends by anastomosing with ileocolic artery at right iliac fossa. Above and in front it is related to the body of pancreas, splenic vein; above and behind to aorta, left renal vein, uncinate process and duodenum. In the mesentery it crosses IVC, right ureter, right psoas; it is associated with SMV which is towards right. Superior mesenteric nerve plexus surrounds the artery. *Branches of SMA are* – middle colic artery originates from the right side of SMA just below the pancreas level, runs downwards and forwards in the transverse mesocolon dividing into right and left branches. Inferior pancreaticoduodenal artery arises from SMA at the upper margin of 3rd part of the duodenum running in the pancreaticoduodenal groove divides into anterior and posterior branches; later anastomose with its superior counterpart. Right colic artery arises from SMA occasionally from a common trunk with middle colic artery directs towards the ascending colon divides into ascending and descending branches. Ileocolic artery arises from SMA close to caecum divides into superior and inferior branches; inferior branch apart from anastomosis into the terminal branch of SMA also gives ascending colic, anterior caecal, posterior caecal and an appendicular and ileal branches. SMA from its left side gives around 15 jejunal and ileal branches.

EXPOSURE OF ILIAC ARTERIES

Anatomy

Common iliac arteries are terminal branches of abdominal aorta; right is longer than left. It begins at the level of L4 vertebra 1.25 cm to left of the midline passing downwards and laterally ending at the level of lumbosacral intervertebral disc over the sacroiliac joint by dividing into external and internal iliac arteries. Right CIA passes in front of lower end of IVC, right common iliac vein which is medial to artery below. Left CIA is crossed by inferior mesenteric vessels at its middle.

Internal iliac artery (IIA) is smaller, 4 cm long supplying mainly pelvic organs (other than ovaries and superior rectal artery), perineum, gluteal region, iliac fossa. It begins in front of the sacroiliac joint at the level of L5 – S1 disc, medial to psoas major muscle running downwards and backwards ends at upper margin of greater sciatic notch by dividing into anterior and posterior divisions. It is related in front to ureter and ovaries and Fallopian tube (in females); behind to internal iliac vein, lumbosacral trunk and sacroiliac joint; laterally to external iliac vein and obturator nerve; medially to peritoneum. Branches of anterior division are—superior vesical; obturator; middle rectal; inferior vesical; inferior gluteal (largest branch of anterior division) and internal pudendal (In females inferior vesical artery is replaced by vaginal artery; also uterine artery as an additional branch). Posterior division branches are – iliolumbar, two lateral sacral, superior gluteal arteries.

External iliac artery continues downwards and laterally on the psoas major muscle; under the inguinal ligament continues as femoral arteries. Branches are—inferior epigastric artery and deep circumflex iliac artery. External iliac vein is medial to the artery.

Exposure

Transabdominal approach is used for emergency situation like aorto-iliac surgery, trauma and ruptured aneurysm. Abdomen is opened through midline or oblique incision depends on whether only one side or both sides' iliac arteries need to be exposed. Peritoneum over the vessels is incised and dissected to expose the vessels. Ureter overlies the vessel. On left side sigmoid should be mobilised medially by dividing the pelvic mesocolon laterally to expose the vessel.

Extraperitoneal approach is used for isolated exposure of the iliac vessel in iliofemoral bypass or reconstruction. Oblique incision is placed in the skin above the inguinal ligament below the umbilicus with patient tilted 45° towards opposite side after placing sandbags behind. Skin, two layers of superficial fascia, external oblique and internal oblique are incised; transverse abdominis is split to visualise the peritoneum; it is swept above and medially using blunt finger or gauze dissection to expose the retroperitoneum. Ureter is safeguarded. Artery is exposed adequately as needed. Care should be taken while dissecting close to iliac veins.

EXPOSURE OF FEMORAL ARTERY AND BRANCHES

Anatomy

It is the continuation of external iliac artery behind the inguinal ligament at mid-inguinal point, coursing downwards and medially in the femoral triangle and adductor canal; at lower end of adductor canal at the junction of middle and lower third of thigh it passes through the opening in the adductor magnus to continue as popliteal artery. In front it is related to skin, superficial and deep fascia and femoral sheath; behind it rests on psoas major, pectineus and adductor longus. Femoral artery proximal to origin of profunda femoris artery is called as *common femoral* and distal to that is called as *superficial femoral artery*. Femoral vein is medial to artery to begin with, but at the apex of the femoral triangle it becomes posterior to artery and later becomes lateral. Femoral nerve is lateral to artery. Femoral branch of genitofemoral nerve is lateral to the femoral artery. *Branches* – Superficial: superficial external pudendal, superficial epigastric, superficial circumflex iliac; Deep: profunda femoris, deep external pudendal and muscular.

Profunda femoris is the largest branch of femoral artery, arising from the lateral part of the femoral artery 4 cm below the inguinal ligament in front of the iliacus muscle; it passes behind the femoral vessels leaving the femoral triangle deep to adductor longus, then between adductor longus and brevis, then between adductor longus and magnus with terminal part piercing the adductor magnus to anastomose muscular branches of popliteal artery. *Branches are* – medial and lateral circumflex femoral arteries and four perforating branches **(Figs 11-90 to 11-92)**.

Popliteal artery begins at the junction of the lower third and middle third of the thigh from the opening/hiatus of the adductor magnus, running downwards and laterally to reach lower border of the popliteus muscle ending as anterior and tibioperoneal trunk which gives perineal artery and posterior tibial arteries. Superficially it is



Fig. 11-90: Profundaplasty. It is done when there is localized stenosis at the origin of deep femoral/profunda femoris artery. It is done after proper exposure of the common femoral bifurcation through a vertical thigh incision. Proximal and distal parts of superficial and deep femoral arteries should be exposed to apply vascular clamps. Heparinisation is done. Arteriotomy is done at profunda femoris origin. Endarterectomy is done at the orifice adequately. A venous or prosthetic graft is sutured continuously into the arteriotomy wound to widen the origin of profunda femoris. Clamps are released. Check angiogram may be ideally done afterwards.



Fig. 11-91: Thrombectomy of femoral artery. It is not a common technique. Thromboendarterectomy is commonly done procedure.


Trauma (blunt) right thigh causing femoral artery contusion
A
Common femoral; deep femoral and superficial femoral arteries are dissected and slings are placed to each
B
Traumatised artery exposed
C
PTFE graft placement
D

Figs 11-92A to D: Femoral artery trauma causing arterial contusion which is corrected by PTFE graft.

related to the tibial nerve which crosses the artery from lateral to medial side; popliteal vein which also crosses the artery from lateral to medial. Popliteal artery is overlapped by semimembranosus in the upper part and medial head of the gastrocnemius in the lower part. It lies on the knee joint and popliteus muscle in the deeper plane.

Exposure (Fig. 11-93)

Femoral artery is exposed by a vertical skin incision from mid-inguinal point downwards up to the apex of the femoral triangle. Skin, superficial and deep fascia is incised. Great saphenous vein is identified and retracted. Sartorius muscle is dissected and retracted laterally. Femoral sheath is incised to expose the common femoral artery and profunda femoris origin. Superficial femoral artery is exposed by retracting the sartorius medially and by cutting the fibrous bridge underneath roofing over the subsartorial canal.

Popliteal artery is *usually* exposed by *medial approach*. Patient is in supine position with knee slightly flexed – 15 -25°, hip externally rotated. Skin is incised 1 cm behind the tibial medial condyle extended upwards along the anterior border of the sartorius and distally 1 cm behind the posteromedial border of the tibia. Deep fascia is incised along the anterior border of the sartorius and is retracted behind. Division of adductor magnus tendon is needed to expose the femoropopliteal junction. Below deep fascia along the tendinous



Fig. 11-93: Incision for exposure of femoral artery.

part of three muscles sartorius, gracilis and semitendinosus is incised; tendinous insertion is retracted in front. Medial head of the gastrocnemius is retracted posteriorly **(Figs 11-94 and 11-95)**.

Extensive exposure of popliteal artery needs division of tendinous insertion and medial head of gastrocnemius. After separation of popliteal fat, popliteal fascia is incised longitudinally to expose the popliteal vein which should be dissected very carefully and gently as its tear leads into torrential bleeding. Tibial nerve is dissected and retracted with a sling. Bifurcation or trifurcation of the popliteal artery can be exposed by dividing soleus muscle and tibial vein. Anomalies of popliteal vein should be remembered. *Posterior approach* is limited and is used in treating popliteal entrapment. A transverse skin crease incision with medial upward and lateral downward extensions is used. Deep fascia is incised vertically to reach the popliteal fossa.

ARTERIOVENOUS FISTULA FOR HAEMODIALYSIS (HAEMODIALYSIS ACCESS)

End stage renal failure needs haemodialysis. For regular haemodialysis well perfused venous access is essential. AV fistula is created at different levels to achieve this hyperdynamic circulation so that regular venous access will not be a problem.

Scribner shunt (1921) is the shunt created by Dr Belding H Scribner and Dr Wayne Quinton (Quinton – Scribner shunt) using *Teflon tubes* as circulatory access placed into the adjacent artery and vein. Access is kept patent by connecting two tubes outside the body with a *U shaped Teflon tube*. It will shunt the blood from arterial side to the venous side. Infection and subcutaneous erosion of the tube are the complications. In 1962 Scribner started his first dialysis center (*Seattle Artificial Kidney Center*).

Dr Willem Kolff did first successful dialysis in 1943 to a 67-year old woman with uremic coma for 11 hours. Dr Nils Alwall also did extensive work on dialysis in University of Lund from 1946 to 1960.



Fig. 11-94: Popliteal fossa anatomy.



Fig. 11-95: Incision and exposure of popliteal artery.

Anatomy

Dorsal venous arch is formed from dorsal digital veins and dorsal metacarpal veins. Its efferent veins are cephalic (laterally; preaxial vein like GSV of lower limb) and basilic vein (medially; post-axial like SSV of lower limb) **(Fig. 11-96)**.

Cephalic vein begins at the lateral border of dorsal venous arch running upwards along the roof of the anatomical snuff box, lateral border of distal part of forearm, in front of the elbow, along the lateral border of the biceps brachii, piercing the deep fascia at lower margin of the pectoralis major muscle. Then it runs in the deltopectoral groove up to the infraclavicular fossa, piercing the clavipectoral fascia to join the axillary vein. Cephalic vein is accompanied by lateral cutaneous nerve of forearm and terminal branches of radial nerve. It communicates into basilic vein through median cubital vein. *A communicating vein* between cephalic vein and external jugular vein (neck) is present which runs across the clavicle. It is important for draining the upper limb in axillary vein removal (in carcinoma breast segment may be removed)/blockage.

Basilic vein begins at the medial side of the dorsal venous arch running upwards along the medial border of the forearm, near the elbow winds round towards the ventral aspect, continues upwards along the lateral border of the biceps brachii, in the middle of the arm


Cephalic vein on lateral side ends at clavipectoral fascia into axillary vein
Axillary vein
Bicipital aponeurosis
Basilic begins medially, ends as axillary vein at teres major muscle level
Median cubital vein
Clavipectoral fascia
Cephalic vein
Median cubital vein
Lateral cutaneous nerve of forearm
Medial basilic vein
Medial cutaneous nerve of forearm
Median vein of forearm
Accessory cephalic vein
Cephalic vein
Radial nerve
Basilic vein
Dorsal branch of ulnar nerve
Dorsal venous arch
Upper limb ventral aspect
Upper limb dorsal aspect

Fig. 11-96: Venous anatomy of upper limb to have vascular access for haemodialysis. Proper venous mapping is essential to create AV fistula.

it pierces the deep fascia, running along the medial side of the brachial artery becoming axillary vein at the lower border of the teres major. It is accompanied by posterior branch of the medial cutaneous nerve of the forearm and terminal part of the dorsal branch of the ulnar nerve. Basilic vein is the more efficient venous channel than cephalic vein.

Median cubital vein begins 2.5 cm below the lateral part of the elbow as a large communicating vein from the cephalic vein running obliquely upwards and medially in front of the bicipital aponeurosis (deep to this brachial artery is present) ending at basilic vein 2.5 cm above the elbow (medial epicondyle) at medial aspect of the arm. Perforator veins from deep veins pierce the bicipital aponeurosis to enter the median cubital vein which fixes the vein firmly to make the IV cannulation easier and stable. Median cubital vein is absent in 30% of individuals.

Median vein of forearm begins at palmar network ending at cephalic or basilic vein.

Variations: Entire cephalic vein may drain into basilic vein (20%); separate cephalic and basilic veins without communications (10%).

Principle

Usually upper limb is used for creation of AV fistula (*Cimino-Brescia fistula*). Radiocephalic; brachiocephalic; brachiobasilic; PTFE forearm graft prosthesis and upper arm prosthetic graft fistula are different sites for creation of AV fistula.

Fistula should be done initially as distal as possible (radial artery). Even first fistula may be at anatomical snuff box level (Snuff box fistula).

Nondominant side should be used first. One should avoid placing any venous lines in the proposed side/part of the fistula.

Graft fistula should be avoided as much as possible; it should be kept as reserve in inevitable need.

Donor artery should have an adequate pulsation, volume and devoid of calcification to make successful fistula.

Intravenous 3000 units heparin is given in all these patients on table. *Heparinised saline irrigation* to target artery and vein and wound is used during procedure.

Venous mapping and arterial Doppler is necessary in all patients **(Figs 11-97 to 11-99)**.

Radiocephalic AV Fistula (Cimino – Brescia)

Doppler is done to evaluate cephalic vein and radial artery. Preoperative vein mapping is a must. Ideally *target vein* should be


Arterial Pressure
-6
Venous Pressure
103
mmHg
+600
+500
+400
+300
+200
+100
0
-100
-200
-300
Press a button to SELECT
Heparin Pump ON
2.0
mL/h
Dialysate Flow
500
mL/m
Conductivity
13.6
mS/cm
Temperature
36.6
°C
Elapsed Time
2:46
h:m
UF Removed
2.21
L
TMP
138
mmHg
UF Rate CALCULATED
.80
L/h
SET LIMITS
MENUS
MUTE
DIALYZE
100 200 300 400 500 600
ON
Blood Pump
230
mL/min

Fig. 11-97: Dialysis machine used for haemodialysis.



Figs 11-98A and B: A V fistula access during haemodialysis.

3 mm or more in diameter. But adequate good flow with proper patency may be sufficient. Allen test is done to confirm adequacy of ulnar artery blood flow to the hand. It is better to avoid any cannulation or needle prick for IV injections in the planned limb for several weeks. Access fistula is created first in nondominant upper limb; should begin always from distal to proximally. Vein transposition, PTFE graft fistula are the other alternatives should be kept in mind.

Procedure

It is done usually under local anaesthesia; brachial block can be given if needed. Regional anaesthesia causes venous dilatation to make venous identification and dissection easier. Preoperative antibiotics are given. Good light, using loupes may be better. Proper surgical anatomy of vein and artery should be valuable **(Fig. 11-100)**.

Patient is supine with arm placed on arm board. Either transverse skin incision or ***longitudinal incision*** between artery and target vein area is used. Skin flaps are raised adequately. Radial artery is identified deep to deep fascia and mobilised for 2 cm length. Small branches if present requires secure ligation using 4 zero silk. Proximal and distal control is obtained using silastic loops or bulldog clamps. Cephalic vein is identified and mobilised as distally as possible. Small tributaries are ligated using 4 zero vicryl or silk. Vein is also secured with silastic loops if needed. It is flushed with heparinised saline. Intraoperative US may be useful to identify and assess the patency of the vein. Cephalic vein may be divided as distally as possible if needed. Vein is brought close the artery to keep without any tension or kinking. Arteriotomy is done in radial artery. Venotomy is done in cephalic vein in case of side-to-side anastomosis **(Fig. 11-101)**.

End-to-side or side-to-side anastomosis (*Cimino-Brescia*) is done using 6 zero polypropylene sutures continuously. In end-to-side – distal end of the vein is ligated; proximal cut end is spatulated and its end is anastomosed to the side of radial artery. In side-to-side arteriotomy and venotomy wounds are approximated using 6 zero polypropylene continuous sutures. Once clamps (bulldog) are removed (proximal clamp is removed first and then distal clamp) cephalic vein is palpated for presence of thrill. On table venogram or Doppler is needed to confirm adequate flow. Wound is closed in layers.

Complications are—steal syndrome; bleeding; thrombosis and occlusion of the fistula; sepsis and failure to achieve sufficient arterialisation of venous network.

Brachiocephalic AV Fistula (Fig. 11-102)

After cleaning and draping, local anaesthesia xylocaine 0.5% plain is injected into the antecubital fossa. 6 cm transverse skin incision is made. Cephalic vein is identified; dissected for 5 cm length and stabilised with silastic loops. Deep fascia is opened; tendinous bicipital aponeurosis is identified and incised. Brachial artery is dissected and isolated using silastic loops. 3000 IU of heparin is injected intravenously. Area is irrigated with heparinised saline. Cephalic vein is ligated distally. 6 mm arteriotomy over the isolated brachial artery is done. Proximal cut end of the cephalic vein is spatulated and anastomosed to the brachial artery using 6 zero polypropylene continuous sutures. Forward flush and back bleed is done. Fistula and wound is irrigated with heparin saline.

Brachiobasilic AV Fistula (Fig. 11-103)

Here basilic vein is mobilised and tunneled in subcutaneous plane and then fistula is created through brachial artery. Initial Doppler venous mapping is done. Basilic vein is not superficial; it is deep in the basilic tunnel in the medial aspect of the arm. So it should be kept in the tunnel in subcutaneous plane to have access.

It is done in brachial block or general anaesthesia. With supine 90° outstretched arm position, after cleaning and draping, longitudinal incision is made in arm medially from antecubital fossa to axilla. Basilic vein in the lower part of its tunnel is identified and dissected with freeing all tributaries up to the axilla. It is also mobilised across the cubital fossa downwards. Brachial artery is identified in the antecubital fossa and distal part of the arm; it is dissected for about 3 cm circumferentially. IV heparin 3000 units given; heparin saline irrigation into the vessels and wound is also needed. Basilic vein distal to the cubital fossa is cut and ligated. Its proximal part is passed through the created tunnel in the subcutaneous plane (at 4 mm depth) in the anterior aspect of the arm downwards to the cubital fossa where it is passed through the deep fascia into the mobilised brachial artery. It is dilated manually. Kinking should be avoided while tunneling it. 6 mm arteriotomy is done in the brachial artery after placing silastic loops; spatulated proximal mobilised tunneled cut end of the basilic vein is anastomosed into the brachial artery as end-to-side. Thrill is checked in the venous side. Distal, radial and ulnar pulses are checked.



Fig. 11-99: Instruments used for AV fistula creation.


Cephalic vein
Incision
Radial artery
Silastic loops
Venotomy
Arteriotomy
Side-to-side anastomosis (Cimino-Brescia)
End-to-side anastomosis

Fig. 11-100: Radiocephalic AV fistula creation.



Fig. 11-101: Radiocephalic AV fistula.


Bicipital aponeurosis
Incision
Cephalic vein
Median cubital vein
Brachial artery
Radial artery
Ulnar artery
Ligated distal part of cephalic vein
Proximal free cut end of cephalic vein sutured to side of brachial artery

Fig. 11-102: Brachiocephalic AV fistula.

PTFE Graft AV Fistula in Forearm for Haemodialysis Access (Fig. 11-104)

It is done when primary AV fistula is not possible due to inadequate venous length/size/pattern. Graft interposition for creation of fistula between artery and vein is needed. Basilic or cephalic vein can be used. Brachial artery is usually used.

After Doppler venous mapping of the upper limb, under regional anaesthesia, transverse or longitudinal incision is made in the forearm. Brachial artery at the antecubital fossa or just above is dissected for 2-3 cm and isolated with silastic loops. Basilic vein on the medial and upper part of the forearm is dissected for 2-3 cm with ligation of tributaries. PTFE 6 mm graft is used of adequate length. Place where graft crosses the joint should be ringed. Subcutaneous tunneling is done using finger or haemostat or tunneling device. Graft is passed through the subcutaneously created tunnel without any kink. IV heparin 3000 units injected. Arteriotomy and venotomy



Fig. 11-103: Dissection of vessels for brachiobasilic AV fistula.


Brachial artery
Incision
Basilic vein
Brachial-forearm basilic vein PTFE graft
Subcutaneously placed PTFE graft

Fig. 11-104: AV fistula in forearm using PTFE graft between brachial artery and basilic vein.


Graft to basilic vein anastomosis
(6 mm diameter PTFE graft)
Basilic vein
Incision in upper arm 4 cm
Subcutaneously placed PTFE graft
Brachial artery
Graft to brachial artery anastomosis
Incision in the antecubital fossa 4 cm

Fig. 11-105: Upper arm prosthetic AV fistula.

of 6 mm length is done. Graft is anastomosed to target artery (brachial) and target (basilic) vein as end-to-side using 6 zero polypropylene sutures. First graft to artery anastomosis is done; Graft is palpated ***for thrill***. Adequate distal pulse in radial/ulnar should be confirmed. Venogram may be needed at a later date if stenosis is suspected.

PTFE Graft in Upper Arm Prosthetic AV Fistula Access (Fig. 11-105)

It is done under general or regional anaesthesia. Patient is in supine position with arm at 90°. After cleaning and draping, a 5 cm incision is made on the medial aspect of the upper arm towards axilla. Basilic vein is identified in deeper plane medially and 4 cm length of the vein dissected, isolated circumferentially and silastic loops are placed. Brachial artery is identified and dissected through a 3-5 cm length incision over the antecubital fossa after incising bicipital aponeurosis. 2-3 cm of brachial artery is dissected to place silastic loops. A curved tunnel is created in the subcutaneous plane directed laterally to connect these tow wounds to place the prosthetic graft. Patient is heparinized (with 3000 units IV). 6 mm arteriotomy is done in brachial artery; 6 mm sized PTFE graft is spatulated to anastomose with arteriotomy as end-to-side using 6 zero polypropylene continuous sutures. Wound and site is irrigated with heparinized saline. Graft is passed through the tunnel to reach the basilic vein proximally. 10 mm venotomy is done; obliquely cut other end of the graft is sutured similarly to the venotomy. Backward bleeding from the venous side and forward bleeding from the graft was done. Thrill in the basilic vein is checked. Radial and ulnar pulses are also checked. Doppler is used to confirm adequacy of flow.

Complications are – sepsis, bleeding, finger ischaemia, nerve injury, fistula thrombosis and block.

Graft Revision after Graft Block

Graft may get blocked by graft thrombosis. Doppler is done to identify the site of block. Incision is made over the graft site extending above and below. Proximal and distal control is obtained. Patient is heparinised. *Balloon thrombectomy* is done through venous side and later through arterial side of the graft. Pulsation is checked after that to confirm the flow over the graft. Fistulogram is done to rule out distal stenosis. If it is present a *jump graft* is placed to bypass stenosis.

Note

- Fistula requires 6 weeks to mature; and 2 weeks in case of graft. Any swelling in the fistulas site after 2nd week should be evaluated for complications. Venous side branches in the fistula may prevent maturation, and so needs proper ligation of side branches.
- If fistula has not matured in 6 weeks, it should be assessed by Doppler study and fistulogram. Rule of 6's criteria in AV fistula if matured are – flow more than 600 ml/min; diameter > 6 mm; depth < 6 mm.
- Patient should do isometric hand exercise and should do daily self examination of fistula for thrill and features of infection.
- Vein should be checked for distension; nondistensible fistula is sclerotic and will not mature.
- Noncompressible veins are thrombotic.
- While dissecting the major target artery care should be taken not to injure adjacent nerves.
- Steal syndrome is more common when fistula is created above elbow level; when fistula is done with graft than vein; and in diabetic, Steal syndrome may cause gangrene of fingers or entire hand. In such situation access fistula may require to be ligated to save the hand. Otherwise interval ligation of artery distal to fistula level is done with revascularisation of artery distally using another graft from artery above the level of fistula to artery below the level of ligation.
- Possible sites of future access should be preserved and cannulas or venous catheters should be avoided at such sites.
- Proper documentation with a diagram of the fistula is a must in all these patients.

PERITONEAL DIALYSIS ACCESS

Peritoneal dialysis catheter can be placed as an emergency temporary one done in ICU or open placement of the catheter done in operation theatre or laparoscopic assisted catheter placement or totally laparoscopic catheter placement.

In emergency and laparoscopy, trocar placement is blind. So risk of bowel injury should be taken into account.

Tenckhoff or Missouri swan neck catheter (has got intraperitoneal ball deeper to cuff to position underneath the peritoneum whereas cuff comes in front of the peritoneum) is used.

Open Method

With patient in supine position entire abdomen is cleaned and draped. Site for trocar and exit trocar should be marked before making incision by placing the catheter on the abdomen with curl end placing on the pubic symphysis going upward with inflow cuff above the umbilicus on the rectus and exit cuff trocar below the umbilicus lateral to the rectus muscle. Incision is deepened to anterior rectus sheath which is incised vertically and rectus muscle is split. Purse string suture is placed in the posterior fascia which is later incised in the centre of the purse string. Peritoneal dialysis catheter with a guidewire or a stylet is lubricated with jelly. Catheter white line should face anterior upward. Catheter is inserted into the abdominal cavity along the posterior surface of the abdominal wall towards the iliac crest and then towards pubic symphysis. Curl of the catheter is placed in the pelvis just deep to the pubic symphysis close to the abdominal wall. Guidewire is removed; heparinised saline is flushed into the catheter. Fluid should flow without interruption and one should able to instill, aspirate or siphon the fluid easily if catheter curl is placed properly (Patient is placed in reverse Trendelenburg position). Purse string is tightened around the catheter (Missouri swan neck catheter). A tunnel is created through rectus muscle and subcutaneous tissue to reach exit site. Catheter is passed through this tunnel. Cuff of the exit site of the catheter should be 1 cm proximal to the exit point. Upper wound is closed completely. Suture is placed around catheter at exit wound **(Fig. 11-106)**.

Patient can undertake dialysis at home. Patient cannot go for swimming and bath should be avoided. Shower can be used. Dialysis is done usually 2 weeks afterwards. Initial low volume dialysis is done increasing the volume gradually to therapeutic level.

OMENTOPLASTY

Indications

To improve circulation in peripheral vascular disease, to improve lymphatic drainage from the limb in case of lymphoedema, in revascularisation of the pharynx, cranial cavity.

Surgical Anatomy

Common hepatic artery → Gastroduodenal artery → Right gastroepiploic artery.

Coeliac artery *Omental vessels.*

Splenic artery → Left gastroepiploic artery

Omentum has got 4 layers of omental arcades with rich lymphatics. By retaining one of the pedicles either right or left gastroepiploic arteries, omentum is mobilised for adequate length to maintain the circula-


Exit site
Catheter trocar site
Marking the catheter trocar site and exit site
A
Peritoneal dialysis catheter
Placing the catheter curl intraperitoneally just above the pubic symphysis
B
Positioning the cuff and ball with bringing out the exit end of the catheter subcutaneously and through the exit site
Exit site
Catheter in S C tunnel
Skin
S C tissue
Rectus muscle
Cuff
Disc
Catheter in the pelvis with curl
Peritoneum

Fig. 11-106: Technique of peritoneal dialysis (open method).

tion. It controls the ischaemia, promotes the wound/ulcer healing and reduces the pain. It can also be used in upper limb ischaemia. It can be used in bilateral lower limb diseases as two pedicles. But if patient continues to smoke these omental vessels may acquire the disease (TAO) and recurrence of symptoms can occur.

Procedure

Preoperative antibiotic is given. Under general or epidural anaesthesia, entire abdomen and entire lower limb is cleaned and draped. Through upper midline incision abdomen is opened. Omental vessels/arcades are assessed. Omentum is separated from colon through avascular plane. Omentum is also carefully separated from mesocolon through omental bursa. Gastroepiploic arcade along the greater curvature is identified. Branches entering the stomach from gastroepiploic arcade are carefully ligated using 3 zero vicryl. One of the pedicles usually right is retained as pedicle to perfuse the arcade. Omentum is lengthened with careful planning. Bleeding and haematoma formation within omentum should be avoided as much as possible. Cauterisation should be minimum only if at all using bipolar cautery **(Fig. 11-107)**.

Incision is made just above the groin which is deepened across abdominal wall muscles and peritoneum to reach abdominal cavity. Mobilised omentum is brought out of the groin wound into the subcutaneous plane. Multiple transverse incisions are made in the limb downwards to reach the lower part of leg. Subcutaneous tunnels are created to pass the omentum. In the calf/leg deep fascia is opened to bury the tip of the omentum into the muscle. Abdomen is closed in layers. In the limb only skin is sutured without injuring the omental pedicle in the subcutaneous plane.

Patient is kept nil orally for 24 hours.

Doppler study at regular period will reveal the perfusion in the omentum.

Complications

Abdominal sepsis can occur due to removal of omentum from the abdominal cavity. Patient is observed for peritonitis (primary) and septicaemia. It is treated usually with proper antibiotic therapy. Incisional hernia, adhesions, intestinal obstruction can occur. Wound infection in the limb and cellulitis, thrombosis of the omental vessels and failure of the procedure can also occur **(Fig. 11-108)**.


Cleaning draping and exposure of abdomen and limb
Upper midline incision
Liver
Stomach
Omentum is spread out to plan the omental harvesting
Colon
Omentum is separated from colon through avascular plane

Figs 107(1)


Omentum is dissected from mesocolon along the omental bursa
Omental arcades are identified
Gastroepiploic arcade on the greater curvature is identified
Arcade
Arcade branches
Arcade branches entering the stomach are clamped carefully and ligated without injuring gastroepiploic arcade
Mobilised omentum with pedicle
Stomach with freed arcade branches along greater curvature

Figs 107(2)


Further lengthening of the omentum by careful dissection
Stomach
Right gastroepiploic artery pedicle
Adequately lengthened omentum with pedicle - right gastroepiploic artery
Colon
Right gastroepiploic artery pedicle
Making incision in the abdominal wall just above the groin level to create tunnel to pass omentum
Incision

Figs 107(3)



Incision is dissected and deepened through all layers of abdominal wall into peritoneal cavity

Long artery forceps is passed from below upwards to pass the tip of the mobilised omentum

Omentum tip is brought out through lower wound

Subcutaneous tunnel is created along the limb below to reach the leg as below as possible

Figs 107(4)


Greater curvature ligated
arcade branches area is
often buried using
vicryl suture
Multiple incisions in the skin are made to create
subcutaneous tunnel and to pass mobilised omentum below
Distal end of mobilised
omentum is buried deep
to deep fascia of leg


Abdomen is closed
in layers
Other wounds are closed - only skin -
without injuring omentume in S C plane

Figs 107(5)

Figs 11-107(1 to 5): Technique of omentoplasty.



Fig. 11-108: Hernia after omentoplasty along the upper medial part of thigh with colon as content. On percussion it was resonant. Barium enema X-ray showed colon in the hernial sac.

Chapter
12

Surgery in Venous Diseases

VENOUS DOPPLER

With the patient standing; the Doppler probe is placed at saphenofemoral junction and later wherever required. Basically by hearing the changes in sound, venous flow, venous patency, and venous reflux can be very well identified. A *uniphasic signal* means flow is in one direction. A *biphasic signal* means flow in both forward and reverse direction suggesting incompetence. Reversal can often be better appreciated by releasing a tourniquet applied earlier at saphenofemoral junction. An *audible whoosh signal > 0.5 sec* on performing the Valsalva manoeuvre with probe kept at the SFJ suggests incompetence.

Venous Doppler in varicose veins

- To find out DVT- very important
- To find out sapheno-femoral, sapheno-popliteal incompetence
- To find out perforator incompetence
- Uniphasic signals signify flow in one direction – normal; Biphasic flow signifies reversal flow with incompetence.

DUPLEX SCAN

Duplex scan is a highly reliable U/S Doppler imaging technique (Here high resolution B mode ultrasound imaging and Doppler ultrasound is used) which along with direct visualisation of veins, gives the functional and anatomical information, and also color map. Examination is done in standing and lying down position and also with *Valsalva manoeuvre*. Hand held Doppler probe is placed over the site and visualised for any block and reversal of flow. DVT is very well identified by this method. All patients with varicose vein should be assessed preoperatively by ultrasound with *proper venous mapping (Venous haemodynamical mapping; VHM; Cartography)*—i.e. marking on the patient's limb manually using permanent marker under ultrasound guidance. All surgeries should be done with on table ultrasound guidance. Postoperatively, all patients should be assessed using ultrasound for result, and for residual venous diseases. VHM is done in standing; in warm room with adequate time **(Figs 12-1 to 12-4)**.

Air Plethysmography

Patient is initially in supine position with veins emptied by elevation of leg. Air filled plastic pressure bladder (inflatable polyurethane cuff filled with air) is placed on calf to detect volume changes. Minimum volume is recorded. Patient is turned to upright position and venous volume is assessed. Maximum venous volume divided by time required to achieve maximum venous volume gives the *venous filling index (VFI)*. VFI is a measure of reflux. *Ejection fraction* is volume change measured prior and after single tiptoe manoeuvre, which is a measure of calf pump action. *Residual venous fraction* is an index of overall venous function which is venous volume in the leg after ten toetip manoeuvres divided by venous volume prior to manoeuvre. Patients with *increased VFI and diminished ejection fraction will benefit from surgery* **(Fig. 12-5)**.


Ideally duplex scan should be used on table during all interventions for varicose veins
Preoperative duplex scan evalution is must in varicose vein diseases

Fig. 12-1: Duplex scan (with Doppler) machine used for varicose veins and DVT. Preoperative duplex scan, marking of veins and on table duplex scan is a must in managing varicose vein diseases.



Fig. 12-2: U/S showing IVC thrombosis



Fig. 12-3: Saphenous eye – as seen in US duplex scan.



Fig. 12-4: Venous haemodynamic mapping (VHM) of the lower limb.



Fig. 12-5: Air plethysmography.

Venography/Phlebography

Ascending venography was a very common investigation done earlier to Doppler period.

A tourniquet is tied above the malleoli and the vein of dorsal venous arch of the foot is cannulated. Water soluble dye injected flows into the deep veins (because the applied tourniquet prevents its flow into superficial veins). X-rays are taken below and above the knee level. Any block in deep veins, its extent, perforator status can be made out by this.

Note: In the presence of Duplex scan ascending venography is not a necessary investigation. If DVT is present, surgery or sclerotherapy are contraindicated.

Descending venogram is done when ascending venogram is not possible and also to visualise incompetent veins. Here contrast material is injected into the femoral vein through a cannula in standing position. X-ray pictures are taken to visualise deep veins and incompetent veins.

Phlebography

- Ascending phlebography defines obstruction
- Descending phlebography identifies valvular incompetence
- Regularly not required to be done

Levels of Investigations

Level I – History, examination with Trendelenburg test, hand held Doppler scanner.

Level II –Noninvasive – Duplex scan, air plethysmography.

Level III – Invasive and complex imaging – descending and ascending venography; venous pressure measurement; CT scan; venous helical scanning; MRI.

Note:

Advanced CEAP classification is used now rather than basic CEAP. VCSS (Venous Clinical Severity Scoring) is also useful.

Table 12-1: VCSS system

	None – 0	*Mild – 1*	*Moderate – 2*	*Severe – 3*
Pain	None	Occasional; no restriction of daily activity	Daily that only interferes with daily activity	Daily pain that prevents from working
Varicose veins	None	Few scattered branch vein varicosities; > 5 blue telangiectases on the inner part of foot – ankle flare	Multiple varicosities of calf or thigh	Multiple varicosities of both calf and thigh
Inflammation	None	Perimalleolar area	Lower 1/3rd calf	More than lower 1/3rd of calf
Induration	None	Perimalleolar area	Lower 1/3rd calf	More than lower 1/3rd of calf
Active ulcer duration	No active ulcer	< 3 months	3-12 months	> 12 months
Other parameters similarly				


Diagnosis
Anamnesis
Family and heredity (antecedents)
Habits and addictions
History
Examination
Clinical
Hand held Doppler; US and Duplex; US abdomen; Blood–coagulation profile; PTMRI/CT
Other—Relevant to cause and need

SURGICAL ANATOMY OF LOWER LIMB VEINS (FIG. 12-6)


Perforators
Short saphenous system
Long saphenous system

Fig. 12-6: Anatomy of lower limb veins.

Superficial Venous System

It is located in the saphenous compartment which is between subcutaneous plane and deeper aponeurotic plane. GSV and SSV are in this plane.

Great (*Long*) *saphenous vein* (*GSV*)*:* It runs from the medial end of the dorsal venous arch up along the anteromedial aspect of the leg and thigh until it empties into the femoral vein. There is one valve at the junction – is called as *ostial* /*terminal* valve and reflux through it is called as *ostial reflux*. One more valve proximal to the main junctional tributary veins is called as *preterminal valve*. More than 50% reflux occurs at preterminal valve (*preterminal reflux*).

Small (*Short*) *saphenous vein* (*SSV*)*:* It runs from the lateral end of the dorsal venous arch up along the posterolateral aspect of the calf until it passes through the popliteal fossa behind the knee and empties into the popliteal vein just above the knee.

Tributaries are located in the subcutaneous plane which joins the saphenous system. Superficial circumflex vein (often joins AAGSV), superficial external pudendal vein, superficial inferior epigastric vein, anterior vein of the leg, posterior arch vein of the leg (joins GSV), posterolateral venous chains of leg – are different tributaries. Long intersaphenous communicating vein often exists between cranial extension of SSV to join GSV and can be varicose and pathological and is called as *communicating vein of Giacomini- Cruveilhier*. *Anterior accessory great saphenous vein (AAGSV, Anterolateral vein of thigh)* is communicating vein into the GSV anteriorly and laterally. AAGSV communicates into GSV usually just proximal to preterminal valve (60%); often at confluence (39%); rarely onto femoral vein (1%). In many patients with varicose veins, it is this vein which is diseased than GSV. It often receives superficial circumflex vein before joining the GSV **(Fig. 12-7)**.


Superficial circumflex iliac
Superficial epigastric
Superficial external pudendal
LSV
Anterior vein
Posterior vein
Perforators
SP junction
Perforators
SSV

Fig. 12-7: Great saphenous vein (GSV/LSV), small saphenous vein (SSV) and perforators.

Perforator system of veins (communicating veins): They pass through the deep fascia carrying blood from superficial to the deep system. One way flow of blood is maintained through valves. Incompetence of these valves leads to appearance of superficial varicosity during exercise.

Deep venous system: It comprises femoral and popliteal veins; pairs of venae commitantes of the tibial, posterior tibial and peroneal arteries (total 6 venae commitantes, soleal and gastrocnemius veins join to form popliteal vein); valveless blood lakes within the calf muscles communicates with superficial system via saphenofemoral junction, mid-thigh perforators, short-saphenopopliteal junction and calf perforators.

The calf muscle pump: It is often referred to as "*peripheral heart*". Its inflow into a segment of deep vein is through intake valves of the perforating veins and segment of deep vein below. Its outflow is through outflow valve to the deep vein segment above. It has got soleal veins (blush up the blood) and gastrocnemial veins (*Gilot*) (push up the blood) to have effective motor venous return **(Fig. 12-8)**.

DIFFERENT TYPES OF PERFORATORS

Para Achillean (*Bassi);* **Ankle perforators**; (*May or Kuster*); **Lower leg perforators** between deep veins and posterior arch vein *(Cockett*): I (posteroinferior to medial malleolus), II (10 cm above the medial malleolus), III (15 cm above medial malleolus); **Gastrocnemius perforators** between GSV and deep veins - upper proximal paratibial *(Boyd)-b*elow knee; **Lower and medial paratibial** (*Sherman*); *24 cm perforator* between deep veins and GSV; **Mid-thigh perforator** between deep vein and GSV *(Dodd);* **Hach perforator in the posterior thigh***;* **Hunter`s adductor canal perforator** in the thigh **(Fig. 12-9)**.


Inferior vena cava
Common iliac veins
Internal iliac veins
External iliac vein
Common femoral vein
Superficial circumflex vein
Anterolateral thigh tributary vein
Anterior thigh vein
Anterior branch vein
Dorsal venous arch
Saphenofemoral junction (SFJ)
Superficial epigastric vein
Superficial external pudendal vein
Posteromedial thigh tributary vein
Long saphenous vein (LSV)
Posterior branch vein
LSV
Deep venous system
Superficial epigastric vein
Superficial venous system
Ext iliac vein
Femoral vein
SFJ
Femoral vein
Popliteal vein
Ant tibial vein
Post tibial vein
Peroneal vein
Lateral perforator
Small saphenous vein
Superficial circumflex vein
Great saphenous vein
Sup ext pudendal vein
Ant lat accessory GSV
Hunter's perforator
Dodd perforator
BK perforator- BOYD
Posterior arch vein
Anterior vein of leg
Lower leg perforators (Cockett I, II, III)
Ankle perforators (May/Kuster)
Dorsal venous arch

Fig. 12-8(1)


Subcutaneous compartment
Saphenous compartment
Muscular compartment
Skin
Tributary
Great sapheous vein
Fascia
Aponeurosis
Perforator vein
Valve
Deep vein
Perforator vein
Valve
Deep vein
Muscular compartment
Skin
Fascia
Great sapheous vein
Subcutaneous compartment
Saphenous compartment
Tributary
Aponeurosis
Valves normally functioning
Unidirectional flow (normal)
Incompetent valves causing reflux
Reversal flow pathological (reflux)

Fig. 12-8(2)

Fig. 12-8: Diagrams showing venous anatomy of the lower limb. Also note the functioning of the valve in the vein.

PHYSIOLOGY OF VENOUS BLOOD FLOW IN LOWER LIMB

Veins are thin walled vessels with collapsible walls that assume an elliptical configuration in collapsed state and circular configuration in the filled state. Venous valves are abundant in the distal lower extremity and the number of valves decreases proximally, with no valves in superior and inferior venacava.

Factors affecting venous return are – (a) Arterial pressure across the capillary increases the pumping action of vein; (b) *Calf musculovenous pump*: During contraction phase of walking, pressure in the calf muscles increases to 200-300 mm Hg; This pumps the blood towards the heart; During relaxation phase of walking, pressure in the calf falls and so it allows blood to flow from superficial to deep veins through


Proximal thigh Hunterian perforator
Distal thigh Dodd perforator
Below knee Boyd's perforator
Posterior arch vein
Cockett's perforator

Fig. 12-9: Diagram showing different perforators.

perforators; Normally while walking, pressure in the superficial system is 20-30 mm Hg at the level of ankle; During walking, foot pump mechanism propels blood from plantar veins into the leg; (c) Gravity. Pressure in the vena cava where it enters the right atrium is very low (-5 mm Hg) which allows rapid filling of vena cava from high pressure peripheral veins.

Factors responsible for venous return: Negative pressure in thorax; Peripheral pump—calf muscle; *Vis-a-tergo* of adjoining muscle; Non-refluxing valves in course of veins.

VENOUS PATHOLOGY

Venous pathology develops when venous return is impaired. It can be of *deep, superficial or mixed types*. It can be due to primary muscle pump failure, venous obstruction, and venous valvular incompetence. It may be segmental or affecting the entire leg. Here venous wall shows increase in collagen and reduction in elastin. *Causes of primary muscle pump failure are* - muscle wasting, neuromuscular disease, deep fasciotomies, local vein valve failure. It leads to nonreduction of postambulatory pressure; causes increased hydrostatic pressure and thus decreased arterial inflow. Present concept is inflammatory pathology of the venous wall and valve. Present theory is a changed concept from top to bottom with segmental pathophysiology. So VHM (venous mapping) is essential prior to surgical intervention.

Incompetence can be of *three types* – perforator; superficial and deep.

Perforator incompetence is reversal of normal flow across the perforators. Normal flow is from superficial veins to deep veins. Perforator valve failure causes deep to superficial reflux causing congestion and venous hypertension. It causes transmission of extreme high pressure (150–200 mm Hg) generated at the deep veins into the superficial veins. This high pressure reflux *(hydrodynamic reflux*) causes distal valvular incompetence of the superficial venous system causing varicosity and its problems. Problems here are more rapid and progressive than just superficial vein incompetence.

Superficial vein incompetence is the most common form of the venous disease. It shows retrograde flow (*hydrostatic reflux*) due to malfunctioning valves. It is the tributaries which commonly become incompetent and diseased as it is in subcutaneous plane with less support and also has thin muscle layer in the wall. Here effects are slow and gradual.

Deep incompetence may be isolated incompetence of deep veins or may be associated with incompetence of superficial venous system. Here blood pumped out in normal volumes but extremity refill includes normal arterial inflow and also pathological reflux. Venous refill is rapid with normal or elevated ambulatory venous pressure **(Fig. 12-10)**.


Superficial ext pudendal vein
Femoral vein
Ant accessory GSV (AAGSV)
Superficial epigastric vein
Superficial circumflex vein
Terminal/ ostial valve
Preterminal valve
AAGSV
GSV
Normal SFJ anatomy
Terminal/ostial reflux
Preterminal valve reflux
Both terminal and preterminal valve reflux

Fig. 12-10: Great saphenous vein anatomy at its saphenofemoral junction showing reflux.

MANAGEMENT OF VARICOSE VEIN DISEASE

One has to remember that varicose vein is a disease with progressive deterioration. Surgeon should not jump to do surgery to every patient with varicose vein. Selection of the case for surgical intervention is very important. It is done to relieve significant symptoms, reverse or reduce skin changes, to promote healing of the ulcers. Cosmesis and treating the asymptomatic uncomplicated varicose veins for prophylaxis are also the mentioned indications, but surgeon should be careful and should clearly discuss with the patient properly the drawbacks of interventions.

Venous mapping *is mandatory* prior to surgery. *Duplex scan with Doppler should be used always during all intervention procedures for varicose veins* **(Figs 12-11 and 12-12)**.

Contraindications for Surgery

DVT is an *absolute contraindication* for surgery.
Pregnancy, females taking contraceptive pills and recent episode of superficial thrombophlebitis are *relative* contraindications.

Indications for interventional procedures –
Complaints which are relevant like pain, discomfort;
Complications;
Cosmesis.

Endovenous ablation can be thermal or chemical. Thermal ablations (TA) are – radiofrequency (RFT) or laser ablation. Chemical are liquid


C5
CR 10
8
10
8
6

Fig. 12-11: Venous mapping should be done prior to any intervention to varicose veins. It is done using US scan with patient in *standing position*.



Fig. 12-12: Air plethysmography.


Modalities of management
Bandaging
Elastic
Nonelastic
Stockings
Crepe/
Pneumatic
bandages
Endostents
Unna boots
Sclerotherapy
Liquid
Foam
CO₂/air/
O₂+CO₂
microfoam
Surgery
Ablative
Conservative
Deep venous
Stripping
Endovascular
EVLT/RFA
Phlebectomy
CHIVA/
ASVSAL
Reconstructive
valvuloplasty
IVC filters

or foam sclerotherapy (FS). Venous mapping is mandatory for all mapping. Presently recommendation is all endovenous therapies should be done under US guidance. FS is simpler than TA. TA and FS both are effective, simple and safe. TA is more effective for vein > 5 mm. FS is appropriate for recurrent and complex varicosities.

TRENDELENBURG OPERATION (SAPHENO-FEMORAL CROSSECTOMY) AND/OR STRIPPING

It is *juxta femoral flush ligation* of long saphenous vein (flush with femoral vein) after ligating named (superficial circumflex, superficial external pudendal, and superficial epigastric vein) and unnamed tributaries. Anomalies of GSV should be remembered. Double saphenous vein is the commonest anomaly occurring near SFJ.

Procedure

It is done under spinal/epidural/general anaesthesia. Just prior to giving anaesthesia all dilated veins and perforators should be marked with proper marker in standing position. Marking can be done using Duplex scan with Doppler. It is ideal to use Doppler with duplex scan during procedure also.

Entire limb, groin and perineum from ankle is cleaned and draped. Patient is placed in supine position with knee slightly flexed and rotated externally. Saphenous opening is marked which is 3-4 cm below and lateral to pubic tubercle. Horizontal incision of 6 cm length is placed at this point at the crease. Subcutaneous fat, membranous layer of superficial fascia (Scarpa's fascia) is incised. GSV is identified on the medial side of the wound. Wound edges are retraced. Dissection is done proximally to identify the cribriform fascia and saphenofemoral junction (SFJ). Once SFJ is delineated, SFJ is dissected all round and femoral vein is identified in deeper plane. Femoral vein is medial to femoral artery. Colour of femoral vein differs from that of GSV. A small external pudendal artery often may cross between femoral vein and GSV. Feeling the femoral arterial pulsation may be beneficial to identify the femoral vein. Care should be taken not to injure the femoral vein. There is a possibility of developing inadvertent tear at SFJ causing severe bleeding. In such situation blind application of the haemostat should be avoided. First head end is lowered to reduce the venous pressure; firm pressure over the site using a mop facilitates proper identification of the site of bleed which is ligated using polypropylene sutures. Superficial external pudendal, superficial external (circumflex) iliac, superficial epigastric veins are identified and dissected until they reach to their further tributaries. These smaller tributaries are dissected individually, ligated and divided. Other unnamed tributaries along the length of 3 cm of GSV from SFJ are also dissected, ligated and divided. All these smaller tributaries are ligated using 3 zero / 2 zero vicryl. Finally main named tributaries are ligated. Often it is done after transecting the GSV away from tributaries level and lifting the divided proximal end of the GSV. Once three main tributaries are ligated, proximal GSV is lifted to visualise the deep external pudendal vein which joins femoral vein or SFJ on medial side. This vein is carefully dissected, double ligated and divided. Avulsion of this vessel may occur causing torrential bleeding from the femoral vein. Femoral vein is dissected carefully adjacent to SFJ for 2 cm proximally and distally. Anatomical variations should be considered in all patients while dissecting which are not common **(Figs 12-13A to J)**.

GSV is transfixed and ligated using 2 zero vicryl suture on the wall of the femoral vein as a flush but without creating any kink to the vein and also one should not allow to form a blind pouch by doing ligation little distal to the SFJ which may later create *saphena varix*. Additional simple ligature is also placed **(Figs 12-14A to I)**.

Lower part of the wound is retracted to expose the posteromedial deep external pudendal vein and other tributaries of GSV which are


Position of the patient is supine; Trendelenburg; knee slightly flexed and hip and knee externally rotated.
Incision is 3 cm below the pubic tubercle and inguinal ligament; Skin crease 6 cm length horizontal.
Incision is deepened through subcutaneous fat, membranous layer of deep fascia.
Mastoid self retaining retractor
GSV exposed
A
B
C

Figs 12-13A to C


Superficial circumflex vein
Femoral vein
Superficial epigastric vein
Superficial external pudendal vein
GSV
D
Tributary
Subdivisions
Subdivisions
Tributary
Tributary
Subdivisions
Each tributaries at SFJ are dissected for their subdivisions; these subdivisions are first ligated with vicryl; then main tributaries are ligated.
E
Subdivisions and tributaries are divided.
F
GSV is clamped using haemostats.
G
Clamped GSV is divided; proximal end is elevated up to visualise the deep external pudendal vein (at the SFJ). It is with its subdivisions is ligated and divided.
Deep external pudendal vein.
H
SFJ is transfixed and ligated using 2 zero vicryl.
I
Double ligation of SFJ—in flush to femoral vein is done.
Distal clamped part of SFJ is either ligated; or stripping is done through it.
J

Figs 12-13D to J

Figs 12-13A to J: Diagram showing steps of saphenofemoral flush ligation.

securely ligated. Remaining tributaries up to the middle of the calf (or up to 4 cm/hand breadth below the knee joint line to include Boyd's perforator) are addressed either by stripping or by series of small incisions along the line of GSV (ablation). Stripping the GSV below the mid-calf will likely to injure the saphenous nerve causing *saphenous neuralgia*. Stripping *should preferably be done* from above downwards after passing stripper from below upwards. *Many advocate* stripping of the vein from below upwards and is said to be technically easier with keeping limb elevated. But here injury to saphenous nerve and stripper entering the deep system are likely complications to occur even though incidences are low. *Stripping avulses all significant thigh perforators.* It is advisable to complete all planned procedures like foam sclerotherapy/multiple avulsions and close the skin wounds with stripper placed ready for stripping; at the end vein is stripped with limb in elevated position. Immediately after stripping the vein soft cotton pads and roller dressing pads are


Marking of the veins under US guidance
A
Cleaning of the entire leg
B
Draping of the leg
C
Completed draping
D
Incision
E
Membranous layer
Subcutaneous tissue
GSV
F
Retractor
Exposed GSV
G
H
SFJ with all communicating veins
I

Figs 12-14A to I


Ligation of communicating veins with their branch tributaries at SFJ
J
SFJ
K
Tributary
L
GSV
SFJ
M
Clamping the GSV
N
O
Cutting the GSV
P
Q
GSV (transected)
Deep external pudendal vein
R
Ligated deep external pudendal vein
S
Transfixing the SFJ using vicryl 1 zero
T
Additional ligature at SFJ
U

Figs 12-14J to U



Figs 12-14V to Y

Figs 12-14A to Y: Saphenofemoral flush ligation for varicose veins—operative steps.

placed from toes to groin and bandage and crepe bandage or stockings are placed. Stripping is done in elevation to prevent haematoma formation. Limb should be kept in elevated position adequately (3 pillows) during postoperative period.

Two Types of Stripping Techniques

Extraluminal collision technique using Myer's stripper (Acorn head stripper, 73 cm long) is practiced since long time; but it damages the adjacent tissue, causes infection, postoperative pain and discomfort and haematoma along the stripped tract with possibility of revascularization of the tract haematoma.

Invagination technique is better with less damage to adjacent tissue. *Codman's stripper* is used for invagination technique. Stripping avulses the vein and obliterates the tributaries.

A small transverse incision is made at mid-calf level along the line of GSV. Vein is identified and dissected. Saphenous nerve which is very close to the vein should be separated and should not be injured. Vicryl ligature is passed to distal part of the isolated vein. After ligating it, the ends of the ligature are lifted using haemostat. Proximal to this, an additional 2 or 3 zero vicryl ligatures are passed around and temporarily held with two haemostats without tying. Proximal to ligature vein is held by two haemostats and anterior part of the vein is incised between two haemostats. It is better to place two 3 zero vicryl stitches instead of two haemostats and vein is incised between these two ties. Olive tip of the Myer's stripper is passed through the vein from below upwards towards groin crease wound. Depending on surgeon's choice *acorn head* is threaded into the lower end if stripping is done from below upwards (practiced by many surgeons) or acorn head is threaded to upper end if stripping is done from above downwards (*technically ideal*) **(Figs 12-15 and 12-16)**.



Figs 12-15A to C


Pubic tubercle
Incision
Incision
D
Stripper end (knob)
Long saphenous vein
Stripping from below upwards
Stripping from above downwards – **Ideal and better**
Stripper handle
E
Distal cut end
SFJ is ligated after ligating all communicating veins
F
Stripper is entering the distal cut end
Acorn head is threaded to other end
Stripped vein in the stripper
G

Figs 12-15D to G

Figs 12-15A to G: Technique of extraluminal stripping of the varicose vein using Myer's stripper.

Proximal vicryl ligature in the mid-calf wound vein is ligated around the threaded acorn head of desired size. Wound is closed over the acorn head. Cleaning and soft dressing pads (roller dressings are placed to the wounds and leg) along with elevation of the limb is done. An elastic crepe bandage is applied from toes to groin up to the level just below the groin wound. Groin wound is also closed in two layers except for the part where stripper end with handle is coming out. With full elevation stripper is pulled with jerky movements from below upwards towards groin wound. Stripper with vein will come out. Part of the groin wound which is left open is sutured.

Problems with SFJ Ligation and/or Stripping

Often it is not possible to pass the stripper to entire required length of the vein. In such occasion stripper with olive tip is passed until resistance develops and a small incision is made on it to expose the vein. The vein is opened and stripper is further guided along the vein or stripping of this segment is done and later next segment of the vein is stripped in 2-3 parts.

Bruising, discomfort, pain, haematoma and oedema of leg can occur. Usually they resolve spontaneously in few days; rarely do they require drainage. Elevation and stockings are essential needs.


Intraluminal stripper
A
Intraluminal stripper
is passed into the vein
B
Stripper is negotiated
up to knee or below
knee level
Incision is made over
stripper end
Vein is opened and stripper
end is delivered out.
C
Stripper end is tied to proximal cut end of
the vein, distal cut end of vein is ligated
D

Figs 12-16A to D


E
F
Suturing of the wound before stripping
Stripper is pulled out invaginating and stripping the vein

Figs 12-16E and F

Figs 12-16A to F: Intraluminal stripping of the varicose vein – operative steps. It is better than Extraluminal stripping but chances of neovascularisation are more due to exposure of the endothelium during invagination.

Multiple leg ulcers adjacent to lower part of the shin is possible especially if stripping is done in lower leg and at ankle, as here, GSV is close and adherent to skin.

Saphenous neuralgia even though mentioned, its incidence is less than 1%. It occurs when stripping is done from distal to proximal. It is more common if stripping is done up to ankle level. Ideally stripping should not be done below the midcalf level. Saphenous neuralgia is hyperesthesia and burning sensation along the distribution of the saphenous nerve – along lower medial part of leg, ankle and foot. Saphenous nerve is a branch of the posterior division of the *femoral nerve* which pierces the deep fascia along the medial side of the knee between sartorius and gracilis and descends *downwards in front* of the GSV. *Small areas of numbness and tingling* along the distribution are common occurrence but it is tolerable and acceptable to the patient.

DVT after varicose vein surgery and stripping can occur. Elevation and stockings prevent formation of DVT. It is advisable to have prophylactic heparin therapy 5000 units subcutaneously 6th hourly especially in patients who are in high risk group like those who are on oestrogen therapy.

Infection, cellulitis, abscess and limb oedema are other complications which are treated accordingly.

Recurrence of the disease is common (30%). It is not due to any technical default but is due to progression of disease itself by *neoangiogenesis and revascularisation*.

Other complications - Injury to femoral vein, inadvertent ligation of femoral vein, thrombosis of femoral vein, haematoma in groin wound are basically technical complications. It can be prevented by proper identification of vein and branches, haemostasis and taking proper care while ligation.

Wound *infection* in groin is common due to close proximity to perineum, more fat in subcutaneous area and lymphatic disruption. Often *lymph ooze* can occur for short periods.

Oesch Pin Stripping

Oesch pin stripping (perforate invaginate) is better as postoperative pain and haematoma formation are less common. But there is a possibility of inverted endothelium triggering neoangiogenesis and recurrence. SFJ is dealt as usual. Oesch pin stripper has got a bend near the tip and an eye at proximal end. Bent tip is passed through the vein from above downwards up to midcalf or just below the knee level. Through a small incision tip is brought out through the skin. Thick vicryl (No. 1) is passed through the eye of the stripper. Vicryl is tied around the proximal part of the vein, keeping suture long. Tip of the stripper is pulled down to invert the vein which will be extracted through the lower incision. Wound at SFJ is closed. Steri-strip is placed to lower small incision **(Fig. 12-17)**.

Groin Reoperation for Recurrent Disease

Recurrence after SFJ ligation is due to incomplete disconnection at SFJ and neovascularisation. Recurrence also can occur whenever stripping of the distal part of GSV is not done which may create a new communication between common femoral vein and GSV. Recurrence


Proximal end
with an eye
Bend tip end
Oesch stripper is passed through GSV from proximal to below knee level where bend tip is brought out through skin incision.
Vicryl is passed through proximal eye and is tied to the vein.
Stripper is pulled out through lower bend end to invert the vein.
Completed part of the stripping.
Pin stripper with removed invaginated GSV with tied vicryl in the eye of stripper.

Fig. 12-17: Diagram showing technique of Oesch pin stripping.

also can occur through a mid-thigh perforator. If SFJ is not ligated in flush or tributaries in groin are left in situ recurrence reflux at groin can occur. Neovascularisarion occurs always in front of the femoral vein and these vessels are adherent and thin walled. Duplex scan and varicography are ideal investigations for assessing recurrent diseases **(Fig. 12-18)**.


Old scar
Curved incision for reoperation
Recuurent varices at SFJ is reexplored using curved incision through old scar extending it downwards medially.

Fig. 12-18: For reoperation at saphenofemoral junction a curved incision placed with vertical part at medial side of thigh.

Incision for groin SFJ reexploration is done through same transverse scar or through a vertical incision or combination of both. Vertical incision gives better exposure. First femoral artery is identified and then femoral vein is identified. Careful sharp dissection is ideal than blunt dissection as blunt dissection may cause significant obscuring of visibility of the field. Adequate length of the femoral vein is dissected from lateral and medial sides. All tissues with scar are ligated in front of the femoral vein to clear all tributaries and neovascularisation. SFJ is re-ligated flush with femoral vein. If GSV is not stripped in earlier surgery, it should be stripped properly up to mid-calf level.

Complications of reexploration of groin are – haemorrhage, haematoma/seroma formation, lymph ooze, infection, injury to femoral vein and DVT.

LIGATION OF SAPHENOPOPLITEAL JUNCTION AND STRIPPING OF SSV

It is needed if SSV varicosity is evident. Semiprone or prone position is needed. SPJ should be marked using duplex scan preoperatively. Variation of entering of the small saphenous vein into popliteal vein is common. It may enter high up more proximally above the level of knee joint in 25% of patients. In 15% of patients SSV joins GSV. Transverse incision is placed in the popliteal fossa 2-3 cm above the transverse skin crease. Deep fascia is opened vertically; SSV is identified; one superficial tributary will be present which runs in middle from back of the thigh which often may connect above to posteromedial thigh vein or may connect through a perforator vein into deep femoral vein. SSV entering the fossa is identified. It is accompanied with sural nerve which should be dissected and safeguarded. Sural nerve arises from tibial nerve at middle of the popliteal fossa leaving the fossa at its inferior angle to supply the skin of the lower half of back of leg and entire lateral part of the foot till tip of little toe. SSV is dissected up to the SPJ if there is no variation. It is always ideal to ligate the SPJ at junction. If variation is present it is often difficult to reach SPJ. In such situation many advocate ligation in the popliteal fossa deep to deep fascia to proceed further for stripping of the varicose vein. Gastrocnemius veins instead of normal draining into the popliteal vein may drain into the SSV and in such situation these veins should not be ligated as ligation may cause troublesome venous claudication and discomfort in the calf. Stripping of the SSV is easier. It is ideal to use intraluminal stripper to reduce injury to sural nerve. Stripping is done from above downwards even though many surgeons strip the vein from below upwards. Stripping of the SSV obliterates the midcalf perforator vein which reduces the recurrence.

SUBFASCIAL LIGATION

It is ligation of perforator where it enters the deep fascia (deeper to deep fascia). It is done for perforator incompetence. Perforators are marked prior to procedure using duplex scan. Different approaches are available to tackle perforators **(Fig. 12-19)**.



Fig. 12-19: Dodd (mid thigh) and Boyd (below knee) perforators.

Subfascial Ligation of Cockett and Dodd

Perforators are clearly marked prior to surgery by Fegan's clinical method or ideally using duplex Doppler scan. Multiple small transverse incisions are made on the sites of perforators. Perforators are ligated deep to deep fascia using vicryl **(Fig. 12-20)**.

Subfascial Ligation of all Perforators by Linton's Vertical Approach (1938)

Here vertical incision is made on the medial side of the calf at the anterior margin of the soleus little away from tibia. Often incision over the ankle is divided like in an inverted 'Y' or a posterior 'stocking seam' incision. Skin, subcutaneous tissue and deep fascia are incised without raising any flaps under the skin. Perforators passing across gastrocnemius and deep fascia will be clearly seen. All perforators are identified, ligated using vicryl and divided. Deep fascia is closed using vicryl. Problem with this procedure is lengthy scar which is cosmetically poor even though wound heals well **(Fig. 12-21)**.

Stab Avulsion of the Perforator (Multiple Phlebectomies)

Multiple *small vertical* incisions are made over all marked varicose veins in the leg. Veins are identified. Using vein hook or mosquito artery forceps vein ends are held and gently avulsed using rotation and pulling movements. Often it needs 50-70 incisions to clear the veins. Usually there is no need to suture the wounds as they get closed naturally. Steri-strip placing is sufficient. Postoperative compression bandage is a must. During hook avulsion of the vein, care should be taken not to injure the common peroneal nerve near the neck of fibula, tibial nerve near medial malleolus, saphenous nerve in medial part of leg, and sural nerve on the lateral part of the calf **(Fig. 12-22)**.





Fig. 12-20: Cockett and Dodd perforator ligation using small multiple transverse incisions.

Subfascial Endoscopic Perforator Surgery (SEPS)

A special telescope is introduced deep-to-deep fascia through a single small vertical incision at proximal leg selecting healthy skin. Technique is done under tourniquet. Endoscope is advanced down along the medial border of the tibia. Perforators travelling in subfascial vein are identified and fulgurated using bipolar cautery or clips can be applied into the perforators. It is recommended in chronic venous insufficiency (CVI). But its limitation is difficulty in getting 'lift off' the skin in cases with severe lipodermatosclerosis to identify the perforators.


Different incisions for Linton's perforator ligation.
Vertical incision
Inverted 'Y' incision
'Stocking seam' incision
Subcutaneous tissue
Skin
Deep fascia
Perforator vein
Gastrocnemius muscle
Perforators entering the deep fascia across gastrocnemius
Gastrocnemius muscle
Skin hooks holding the skin with deep fascia
Deep fascia
Deep fascia
All perforators are ligated at this level
Perforators entering the deep fascia across gastrocnemius
Perforator vein

Fig. 12-21: Linton's vertical approach for subfascial ligation of perforators.



Fig. 12-22: Stab avulsion of the vein and perforators (Multiple phlebectomies). It is becoming popular and shows good result.

Complications are – infection, haematoma formation, neuralgia **(Fig. 12-23)**.


Through working channel clip applicator or diathermy instrument is passed
Visual side may be connected to a monitor
Incision for SEPS
Perforators

Fig. 12-23: Subfascial endoscopic perforator ligation surgery (SEPS).

AMBULATORY SELECTIVE VARICES ABLATION (ASVA/ASVAL) (Ablation Sélective Des Varices Sous Anésthesie Locale)

It is based on newer haemodynamic concept – antegrade haemodynamic evolution of saphenous vein incompetence from suprafascial compartment to great saphenous vein. Evolution of disease starts in collateral veins and their reflux leads into varicose reservoir. If varicose reservoir is abolished saphenous reflux will stop—a newer concept. Procedure is done under local anaesthesia (Ambulatory Selective Varices Ablation under Local anaesthesia/ ASVAL).

CHIVA*:* It is one of the methods used to achieve ASVA. (Cure Hemodynamique de'l Insufficiency Veineuse en Ambulatoire). *Pittaluga technique* is used (Dr Paul Pittaluga, A French vascular surgeon, founder of Riviera Vein Institute). Here attention has focused on surgical treatment of tributaries retaining the main trunk – ambulatory conservative haemodynamic management of varicose veins.

Saphenofemoral and saphenopopliteal junctions are identified and marked under US guidance. Individual gastrocnemius, intersaphenous, popliteal area veins are identified and marked; longitudinal 3 mm stabs are made using No. 11 blade; phlebectomy is achieved. Selective targeted diseased veins only are removed with preservation of healthy veins. Minimum pain, minimum haematoma, microincision and so minimum scar **(Fig. 12-24)**.


Reversed flow
Deep vein
Venovenous shunt with revascularisation
Superficial vein
Venovenous shunt with revascularisation
Perforating vein
Fragmentation of venous column
Deep vein
Interruption of venovenous shunt
Superficial vein
Ligation of below perforator vein
Preservation of re-entry perforator veins

Fig. 12-24: CHIVA – Pittaluga technique.

ENDOVENOUS THERMAL ABLATION

Thermal ablation works by generating heat energy within the vein, which inflicts direct thermal damage to inner wall of the vein causing destruction of intima and collagen denaturation of media eventually leading to fibrosis and occlusion. Radiofrequency ablation (RFA) and endovenous laser ablation (EVLA) are two methods used. Thermal ablation is used for varicosities of great, short, accessory saphenous veins, perforating veins as well.

RADIOFREQUENCY ABLATION (RFA) METHOD (VNUS CLOSURE METHOD) (VNUS Medical Technologies Inc; Sunnyvale, CA, USA—By Goldman 2000)

Politowski described this method 50 years ago. Electric energy is converted into heat to denature the collagen tissue in the vein in a bloodless field.

VNUS closure system is the present RFA device used. This procedure is done under general or regional anaesthesia. A RFA catheter is passed into long/short saphenous vein near saphenofemoral or saphenopopliteal junction under US guidance. A special heater probe is inserted into the vein which obliterates 6 cm of vein at a time using 'pull–back' technique. The catheter has a central core for irrigation which prevents coagulum accumulation during the procedure. Temperature of 85°C is used for longer duration of time to cause endothelial damage, collagen denaturation and venous constriction. Phlebectomy is done while withdrawing the catheter. Wall of the vein is destroyed through its full thickness. Vein forms a cord, which gets dissolved by macrophages and immune cells. Procedure is slow one as it will take 25 minutes to obliterate 45 cm vein **(Figs 12-25 and 12-26)**.

Newer generation device VNUS Closure FAST is used with high temperature of 120°C and can be done under general anaesthesia. In this, 45 cm of vein will be obliterated in 5 minutes. It has got VNUS Closure RFS Stylet to tackle perforator veins. It can be done under local anaesthesia. It is better than pull back technique. 7 cm segment is fired in 20 seconds. Catheter is passed 10 cm below the knee by percutaneous access under US guidance or by venesection. Nitroglycerine (NTG) spray may be used to dilate vein and make it easier to cannulate. RFA catheter is passed into the vein up to 2 cm below the SFJ. Tumescent anaesthesia is infiltrated – 10 cc per 1 cm vein length. Vein should be made 1 cm depth from the skin. Tumescent



Fig. 12-25: Set up required for radiofrequency ablation of varicose vein (VNUS – RFA).



Fig. 12-26: Steps in VNUS RFA closure therapy.

creates thermal buffer around the vein; compresses and empties the vein. Initially patient is in reverse Trendelenburg position (Head up) until catheter is passed; then 15° Trendelenburg position is done (head down). RF is fired as 20 seconds for 7 cm segment length. During firing compression over the vein is achieved from outside (external pressure) by pressing with the US probe longitudinally and by pressing the vein line distal to the probe using two fingers. Above knee compression bandage (grade II – 30-40 mm Hg pressure) is applied for 2 weeks. Patient can walk in 1 hour. Running, jumping, straining and weight lifting are avoided for 2 weeks. Analgesics can be taken. Usually antibiotics and analgesics are not needed.

RFA is better in relation to pain, quality, speed of recovery and recurrence compared to open surgery. It is done as outpatient procedure; can resume work early; no hospitalisation; no scar; no sutures.

CELON RFITT – Celon Radio frequency induced thermal therapy with a bipolar applicator is still newer technique. Probe diameter is 1.8 mm which fits to 6 French sheath with a total length 120 cm and electrode length 15 mm. Vein wall is used as a conductor between both poles top reach a temperature of 650–950°C within the vein wall but applicator remains cold. Power (P) of 18–20 W and an applicator time (T) of ≥1.5 sec/cm is used.

Complication rates are 7% in RFA compared to EVLT (20%) but recurrence rate is more compared to EVLT.

ENDO VENOUS LASER ABLATION/ TREATMENT (EVLA/EVLT)

It causes direct and indirect thermal injury of the venous wall with endothelial denudation, contraction of collagen and fibrosis creating a nonthrombotic occlusion of the vein. EVLA is done for truncal varicosities and large branch veins and tributaries.

EVLA is first described by Bone in 1999. The Diomed 810 nm diode laser received US FDA approval in 2002. It is as effective as surgical stripping but with shorter recovery time and less side effects. Vein wall destruction occurs by conductive and convective heating. Direct contact, steam bubble and carbonisation occur. Thermal energy is absorbed by haemoglobin or water. Bare tipped, radial, jacketed, self centering tulip fibres are available. Single use/multiple uses fibres are also available. 400/600/1100 microns fibre size are available.

It is done ideally under *local anaesthesia* with US/duplex scan guidance. Spinal/general anaesthesia can be used. Vein should be marked with marker pen. It is done as an outpatient procedure or as day-care surgery. *System* contains endovenous generator with wavelengths of either 810 nm or 1064 nm, laser firing fibre, monitor showing all the needed parameters related to laser foot switch. Diode laser is used. Procedure is done under US guidance. Hyper Diode 1470 with atraumatic and 360° optical fibres are also now available for faster precise ablation **(Fig. 12-27)**.

Patient lies supine with diseased leg flexed, hip externally rotated and knee flexed. With aseptic precaution, under US guidance LSV is cannulated (18 G cannula) above or just below the knee at the level of Boyd's perforator; needle is removed keeping cannula in place; a 0.035" J guidewire is passed beyond SFJ; 18 G cannula is removed; 5- French introducer catheter/ sheath is passed over guidewire; tip is placed 1 cm distal to the junction; guidewire is removed; laser fibre is inserted into the catheter up to the tip of the catheter and catheter is withdrawn for 2 cm and laser fibre protrudes for 2 cm beyond the sheath / catheter. Catheter and laser fibre tip positions are confirmed using US. Vein can be cannulated at ankle also **(Fig. 12-28)**.

Tumescent anaesthesia (500 ml of cold saline, 30-50 ml of 1% xylocaine with adrenaline, 30 ml of 8.4% sodium bicarbonate) is prepared and injected along the entire length of the GSV to be fired. Injection is done manually using 50 cc syringe or tumescence pump or using as drip set. It should form a *cushion* surrounding the vein along its entire length to provide local anaesthesia, to give protection like a 'heat sink' preventing thermal damage of skin and soft tissues, to provide adequate venous compression to create complete apposition of the venous wall and so effective venous obliteration. Tumescent anaesthesia is given under US guidance.

Laser fibre is fired step by step using diode laser, 1-3 mm withdrawal in 2-3 seconds. Introducer sheath/catheter having mm markings on the surface with the laser fibre are slowly withdrawn. Intermittent pulsed mode firing or continuous mode firing set ups


Laser machine
biolitec
biolitec ELVeS
Laser fibre with introducer sheath
in place inside the GSV
Injecting the tumescent solution
Laser fibre tip inside
the GSV near SFJ
Laser fibre connected
to laser machine
Laser machine
Withdrawing and firing of laser through fibre
Foot switch with
connecting cable
Technique of firing laser

Fig. 12-27: Laser machine and its setting to patient.

are available in the generator. Proximal thigh 14 mm Watts; lower thigh 12 mm Watts; knee and upper leg 10 mm Watts energy are used. Presently it is approved ablation of entire great saphenous vein even though up to midcalf level is commonly done by surgeons. But thermal injury to saphenous nerve is a possible problem. Once procedure is over, catheter is removed. Total obliteration of the vein should be confirmed using ultrasound. Pressure bandage is applied for 2 weeks **(Fig. 12-29)**.


-19G cannula is inserted into the vein
-Needle is removed
-0.035" J guidewire is passed
-5 French introducer sheath
is passed along the guidewire
A small incision is made at the
site of guidewire entering the skin
Sheath is negotiated across
the skin into the vein
Laser fibre tip glowing inside the sheath
Guidewire is removed and laser
fibre is passed into the sheath

Fig. 12-28: Laser fibre insertion - initial procedure.


Cleaning and draping of the leg with proper marking of the vein
Vein should be marked properly
Cannulation of the vein and removal of the needle retaining the cannula
-19G cannula
Passing 5 F introducer sheath along the guide-wire into the vein under US guidance
Passing the guidewire under US guidance
0.035" J guidewire
Introducer sheath is inside the vein
Laser fibre passed through the sheath with tip placing 1-2 cm prior to SFJ. Laser tip should be projecting 1-2 cm beyond the end of the sheath US guidance is needed
Laser fibre tip 1 cm prior to SFJ
Laser fibre tip 1 cm prior to SFJ
Laser tip
Sheath with laser fibre

Figs 12-29(1)


Injecting tumescent solution around the vein close to laser fibre
Injecting tumescent solution around the vein close to laser fibre
Laser generator
Injecting tumescent solution
Laser fibre tip glowing red
Pulling the laser fibre every 3 mm with keeping firing for 3 seconds
Laser fibre tip glowing red
Finishing the laser firing
Laser fired area after completion

Figs 12-29(2)

Figs 12-29(1 and 2): Technique of endovenous laser treatment/ablation.

Heat produced (729°C – 1000°C at tip) by the laser produces steam bubbles with thermal damage of endothelium leading into occlusion of the vein. Laser energy acts on the blood within the vein rather directly through the wall and heats the blood and in turn heats the vein wall.

Advantages of EVLA are—minimally invasive; cosmetically acceptable; no large wounds or scars; done under local anaesthesia; done as day care procedure; easier to do the procedure; rapid recovery and rapid return to work; less chances of neovascularisation and so less chances of recurrence (2% in 2 years) as compared to surgery (30-40%). Technique has got 95% efficacy.

Disadvantages of EVLA are—inability to create flush occlusion allowing tributaries to open up to cause possible recurrence; cost factor, laser fibre kit costs 15,000 Rupees and is disposable; difficulty in cannulating the vein; multiple punctures often may be needed; need of duplex scan in operation theatre; need of trained surgeons to do venous duplex scan and Doppler. One should remember that it is not totally 'pain free'.

Complications of EVLA are—transient postoperative pain; skin ecchymosis; haematomas; thermal injury of the skin; DVT; residual varicosities; sensory disturbances if 1064 nm generator is used **(Figs 12-30 and 12-31)**.



Fig. 12-30: Ecchymosis due to laser ablation of varicose vein.



Fig. 12-31: Wearing stocking is a must after any procedure. Wearing of stocking for minimum of 6 months is needed. It is better to advice to wear stockings during day time for life long to reduce recurrence and neovascularisation.

HEAT ABLATION FOR CLOSURE OF INCOMPETENT PERFORATOR VEIN (ICPV)

Mark Whiteley has invented thermoablation device which is passed into the incompetent perforator to occlude the vein by heat – Transluminal Occlusion of Perforating Veins (TRLOP) or Percutaneous Ablation of Perforators (PAPs). Technique is useful in recalcitrant venous ulcers.
Complications of PAPs are—paraesthesia, DVT, infection.

TRIVEX METHOD

Under subcutaneous illumination and local anaesthesia, a large quantity of fluid is injected percutaneously to identify the underneath superficial veins. Tumescent anaesthesia created causes hydrodissection. Trivex resector and illuminator are placed under the skin. Resector gently extracts veins by suction and morcellation. Further stages of tumescence flushes all blood and delivers vasoconstricting solutions. Solution is passed through 18 gauge needle to clear all blood underneath. Method is cosmetically acceptable; removes all sized veins; achieves good pain relief; with minimal complications like bruising, induration which gets resorbed eventually; can be used when there are venous ulcers.

OTHER METHODS

Transilluminated phlebectomy is done by passing transilluminating light under the skin and passing a rotating blade through another small incision. Veins are grasped and removed by rotating movements.

Ambulatory phlebectomy is done through tiny small incisions using special phlebectomy instruments. *Ramelet's hook* is used. It has sharp harpoons to grip the perivenous collagen tunica externa of the vein to grip and lift. Ambulatory phlebectomy is very useful OP procedure with minimal pain, safety, effectiveness and complications mainly useful in vein collaterals, reticular/perineal/foot and small perforators.

Electrodessication using weak electric current through a fine needle directly into the spider veins (telangiectasis) is also used.

Obliteration of saphenous veins with hyperheated steam is simple and cost effective which is designed by Milleret et al (France). Here water is pressurized at 600 atmospheres which is forced through a narrow tube into the needed vein to cause coagulation and sealing of the vein. Vapour once condenses turns into harmless water.

Cryostripping of the vein is also tried. Cryo probe is used only in part of the therapy while stripping.

INJECTION SCLEROTHERAPY FOR VARICOSE VEINS (FEGAN'S)

Sclerosants are injected into the vein to achieve complete sclerosis of the venous wall. It is used since 100 years as *liquid sclerotherapy.*

It is *indicated* in uncomplicated perforator incompetence; in managing reticular and thread veins; recurrent varicosities; isolated varicosities; in aged and unfit patients. Presently it is said that all types of varicose veins are amenable to sclerotherapy. It is very useful in managing spider veins less than 3 mm. In veins more than 3 mm sclerosant may get washed away.

Contraindications for sclerotherapy are—saphenofemoral incompetence, deep venous thrombosis; huge varicosities – may precipitate DVT; peripheral arterial diseases; hypersensitivity/immobility; pregnancy; venous ulcer – relative contraindication.

Sclerosants used are **sodium tetradecyl sulphate 3% or polidocanal 1%** or sodium morrhuate or ethanolamine oleate.

Sclerosants cause aseptic inflammation, perivenous fibrosis, endothelial obliteration.

Procedure – A 23 gauge needle is inserted into the vein; vein is emptied; 0.5 to 1.0 ml of sclerosant is injected into the vein with limb in elevated position; immediate compression is applied to prevent thrombosis; complete endothelial apposition and sclerosis is achieved. Injection is started at ankle level and later proceeded upwards. Compression stockings for 6 weeks should be used. Repeated sessions of injections with 2-4 weeks intervals can be given. It is called as *macrosclerotherapy*.

Microsclerotherapy: Very dilute solution of sclerosing agent like STDS, polidocanal is injected into the thread veins and reticular veins followed by application of compression bandage (30 G needle). Dermal flare will disappear well by this method.

Note: Sclerotherapy can be – liquid or foam. Foam type may be with air or with CO_2.

Foam Sclerotherapy by Tessari

Cabrera introduced foam sclerotherapy using CO_2 in 1997. In 2000, Tessari started creation of foam from liquid sclerosant through three way stopcock and two syringes. It is simple, affordable, safe, efficient and repeatable. Foam fills the vein, stays longer and also causes spasm prolonged contact with the endothelium exposes subendothelium and causes fibrosis of venous wall. Thick consistency of foam makes it easier to treat large and bulging veins.

Foam displaces blood but never dilutes it; foam doesn't get mixed with blood and so won't get deactivated; causes wider area of chemical ablation of trunk veins. Gas embolism is a rare complication.

STD taken in a syringe is passed rapidly in to another syringe which contains air that results in formation of foam. This foam in much larger quantity is injected in to the superficial vein. Air gets absorbed between foam and endothelial lining is destroyed. Foam is created by different methods. Entire procedure is done under US guidance even through foam sclerotherapy without US guidance is also accepted method.

One of the methods which is followed by many is as follows – 1 ml of STDS is taken in a 5 ml syringe; 4 ml of air is taken in another 5 ml syringe; both syringes are connected through a stopcock; by repeated to and fro movements between two syringes air gets mixed with sclerosant causing soap like foam. Usually 12-15 strokes are needed to create optimum foam. Large quantity of foam can be created by using 20 ml syringe using 4 ml of STDS in one and 16 ml of air in another 20 ml syringe to create 20 ml foam. Maximum sclerosant used is 6 ml for one sitting with 30 ml foam. Response to treatment is assessed by ulcer healing, disappearance of symptoms, US showing disappearance of varices. Leg should be raised during injection to prevent air embolism. Immediate stockings should be applied and should be continued for 6 weeks. Even though DVT can develop, its incidence is less. Foam which is dense gets coaxed into venous wall and so unlikely to flow to distant; so DVT and air embolism usually will not occur **(Fig. 12-32)**.

Foam minimises thrombosis by pushing the blood out of the site of the vessel where action is needed. Polidocanol or sodium tetradecyl sulphate is used for foam sclerotherapy.


1 ml sclerosant + 4 ml air are taken in
two 5 ml syringes with a connecting stopcock
Repeated to and fro
movements between
two syringes are done
Foam
Foam is created

Figs 12-32(1)


Foam is injected to the vein through a cannula
Creation of foam
Injection of foam under duplex US guidance

Figs 12-32(2)

Figs 12-32(1 and 2): Technique of foam sclerotherapy. Stockings and elevation of the limb is important in post-procedure period.

In small veins, magnifying glasses can be used to cannulate the vein. US guided foam sclerotherapy is standard which makes visualisation of foam and its passage.

Pharmaceutical microfoam is available now. It is low density uniform small bubbles of 100 µm. it is generated from O_2/CO_2 gas mixing with low nitrogen and gas gets absorbed in blood faster minimising gas embolism. Incidence of gas embolism is very less with this microfoam compared air based manually created foam.

Complications are—anaphylaxis, headache, transient blindness, stroke, air embolism are rare but specific to foam sclerotherapy. Thrombophlebitis, DVT, skin discolouration, skin necrosis is other complications.

Advantages are—cheap, easier, anaesthesia is not needed, done on day care/OPD basis, can be combined with other procedures for varicose veins.

Echosclerotherapy

Sclerotherapy is done under duplex ultrasound image guidance.

Transillumination Microsclerotherapy *(vein – lite)*

It is better to image the veins using light generated by halogen bulb with high quality fibre with uniform illumination over the skin and passing 30 gauge needle for microsclerotherapy.

Catheter Directed Sclerotherapy

It was devised at Miami Vein Clinic, with specific catheter for sclerotherapy. This catheter has got side holes all around the specific length for uniform contact of venous wall with the foam. It also has got a balloon at the tip which after inflation blocks the SFJ thus preventing embolisation of foam. It has got three external ports one for balloon inflation; one for bladder valve port; one for injection. This technique is under trial **(Fig. 12-33)**.



Fig. 12-33: Catheter directed sclerotherapy.

Remember about sclerotherapy

- Current place of sclerotherapy is mainly for recurrent varicosities and thread/telangiectatic veins
- Sodium tetradecyl sulphate (STDS) is most commonly used sclerosant
- Hyperpigmentation is common after STDS
- Anaphylaxis is common after sodium morrhuate
- Anaphylaxis is least with polidocanol
- Extravasation (presence of pain/irritation/burning) should be avoided as it will cause skin necrosis
- Postsclerotherapy walking immediately after injection for 30 minutes with elastic bandage in place prevents/minimizes the chances of DVT
- Compression bandage should be worn for minimum period of 6 weeks
- Sclerotherapy can be – macrosclerotherapy; microsclerotherapy; echo (ultrasound guided) sclerotherapy; foam sclerotherapy; transilluminated sclerotherapy

Note

- Non-chromate glycerin is better for sclerotherapy of telangiectatic veins.
- 5 ml syringe should be used.
- Ideally finer needle should be used; 30 gauge is better.
- Light and magnification if used it will be better in telangiectatic sclerotherapy.
- Liquid sclerosant is better for smaller veins less than 3 mm.
- Injection should be felt rather than flash back in hub.
- Injection should be stopped if there is white pallor formation in the skin.
- Leg should be elevated while injecting.
- Larger and deeper veins should be injected first before smaller and superficial veins.
- Trapped blood source should be evacuated.
- 3 way stopcock should be used to create foam.

MANAGEMENT OF VENOUS ULCER

Venous ulcer is a complication of chronic venous hypertension occurring around ankle in *Gaiter's* zone. (Gaiter – French – a covering of cloth/leather around ankle and lower leg). 80% of leg ulcers has got venous component. Prevalence of ulcer increase with age and in females. Recurrence of venous ulcer is 60–70%. It is due to CVI, obesity, DVT, phlebitis, trauma. There is abnormal wound healing mechanism in terms of matrix formation with disrupted cell formation. Venous leg ulcer (VLU) limits work, causes pain, immobility, social and psychological impairment.

Treatment strategy consists of—compression; elevation, adequate walking; control of bacterial burden, improvement in nutrition, wound care by dressing; skin grafting. Apligraf application produce more cytokines and growth factors to promote wound healing in venous ulcer. Compression is always better; high compression is better than low; multicomponent system is more effective than single component system. Ulcer is treated initially with *Bisgaard's method*; later by split skin grating. Graft can be taken from same side thigh. It should be combined with definitive procedure for varicose veins **(Fig. 12-34)**.

COMPRESSION THERAPY FOR VARICOSE VEINS

- Compression reduces the venous wall tension; prevents reflux; controls the venous over distension; decreases ambulatory venous hypertension; improves microcirculation; improves filtration and exchange dynamics.
- Compression diverts the blood towards deep veins through perforating veins; prevents the outward flow of blood in perforator incompetence; improves the efficacy of calf muscle pump. Compression reduces the oedema and improves the venous and lymphatic drainage; improves venous elasticity; improves the microcirculation and more important is that it prevents further damage of the venous wall.
- Compression may be elastic/inelastic/combination of elastic and inelastic (*Unna boot*)/multilayered (four layered) compression system which can provide sustained high compression for several days—usually up to a week / intermittent pneumatic compression. Unna boot is three layered paste gauze compression dressing containing calamine, zinc oxide, glycerin, sorbitol, gelatin and aluminium silicate which has mainly inelastic inner component with partly elastic outer layer wrap.
- *Inelastic type* is used for continuous use in severe chronic venous disease. *Elastic type* is used as self applied at day time. Elastic types are – short stretch < 70%; medium stretch 70-140%; long stretch > 140%.
- Recommended pressure in mild varicose veins, pregnancy and postoperative period is 20 mm Hg; in symptomatic varicose veins and after sclerotherapy it is 30 mm Hg; in venous ulcer and post-phlebitic leg it is 40-45 mm Hg; in phlebolymphedema (venous oedema with lymphatic oedema which is more dangerous) it is more than 45 mm Hg.
- Skin maceration, excoriation, dryness, infection, ulceration and failure are the complications of compression therapy.

Remember

- Compression improves rate of ulcer healing.
- Supplementation of phlebotonic drugs in conjunction with compression therapy is accepted.
- Inelastic compression causes more improvement (reduction) in venous filling index (VFI) than elastic compression. But elastic compression is more commonly used because it is better accepted.
- Multilayered bandage system is most effective.
- Ankle – arm pressure index less than 0.6 is contraindication for compression therapy as it may precipitate ischaemic ulcer formation.
- Exercise may improve the muscle–pump action.

Compression garments standard

British standard

- Class I: 14-17 mm Hg
- Class II: 17-24 mm Hg
- Class III: 24-35 mm Hg

International (European) standard

- Class I: 20-30 mm Hg
- Class II: 30-40 mm Hg
- Class III: 40-50 mm Hg
- Class IV: 50-60 mm Hg

Compression Bandages

- *Type 1*—Light weight confirming stretch bandages. These comprise light weight elastomer with high elasticity but little power. It is used to retain dressings.
- *Type II* (Short stop)—Light support bandages. Minimal stretch. Exhibit limited elasticity but tends to lock out on minimal extension. In ambulant patient with CVI they form an essentially inelastic covering to the leg which will exert pressure during calf systole but not during diastole. They are unsuitable for control of oedema.
- *Type III* (Long stop)—are extensible elastic and powerful to a varying degree **(Fig. 12-35)**.

SURGICAL TREATMENT FOR DEEP VENOUS THROMBOSIS AND VENOUS THROMBOEMBOLISM (VTE)

Palma Operation

In iliofemoral thrombosis, common femoral vein below the block is connected to opposite common femoral vein using opposite great saphenous vein **(Fig. 12-36)**.


Venous ulcer
Multiple window cuts are made in the graft
Scraping and preparing donor area
Split skin graft
Donor area
Graft (SSG) is placed over the recipient bed
Graft is fixed to recipient bed edge by clips/sutures
Graft has taken up well

Fig. 12-34: Split skin grafting can be used to cover the venous ulcer after treating the varicose veins.

May – Husni Operation

When popliteal vein is blocked popliteal vein below the block is anastomosed to great saphenous vein as end-to-end bypass **(Fig. 12-37)**.

Venous Thromboembolism (VTE)

Incidences in DVT

- 20% of hospitalised patients; 50% of orthopaedic surgery patients; 1% of adult population after 40 years; 40% of patients undergoing abdominal or thoracic surgeries; one out of 100 DVT patients will die of pulmonary embolism.
- 5% of pulmonary embolism forms chronic thromboembolic pulmonary hypertension with right ventricular failure.
- More than 50% of DVT leads into chronic venous insufficiency (CVI).
- 30% DVT recurs 10 years after discontinuation of the anticoagulant therapy.
- Post-thrombotic syndrome (PTS) occurs in 50% of DVT patients with leg oedema, pain, nocturnal cramping, venous claudication, skin pigmentation, dermatitis and ulceration on the medial side of the lower leg.
- VTE can be provoked or unprovoked (idiopathic).


Stages of applying crepe bandage to leg

Fig. 12-35: Stages of applying crepe bandage immediately after intervention procedure. Elevation of the limb is also equally important.


IVC
CIV
EIV
Iliofemoral block
IIV
Femoral vein
LSV
LSV

Fig. 12-36: Palma operation for iliofemoral block. Using opposite great saphenous vein femoral vein is connected to other femoral vein.

Well's criteria for DVT probability is based on – active ulcer; paralysis/ recent immobilisation; bedridden for > 3 days; recent surgery within 1 month time; swollen leg; tenderness along deep veins; calf girth difference > 3 cm; pitting oedema; others.

SMART tool – Surgical and Medical Assessment of Risks for Thrombosis.


IVC
Common iliac vein
External iliac vein
Internal iliac vein
Inguinal ligament
Common femoral vein
Great saphenous vein (GSV)
Deep femoral vein (profunda)
Superficial femoral vein
Popliteal vein
Block in popliteal vein
Popliteal vein ligated below the block
Distal end of the popliteal vein is anastomosed to distal GSV—as end-to-end
GSV (ligated)

Fig. 12-37: May – Hunsi operation.

DVT risk can be :

Low risk – < 10% (minor surgery in mobile patients); *moderate risk* – 10-40% (general; gynaecologic/urologic surgeries) – needs LMWH or mechanical thrombophylaxis if there is high bleed; *high risk* – 40-80% (hip / knee arthroplasty, fractures, major trauma) needs LMWH, mechanical thrombophylaxis. Dose of LMWH is full dose (5000 units) 2 hours prior to surgery, then half or full dose for 10 days.

High risk can be brought down to 5% by prevention and prophylaxis.

Calf vein thrombosis is defined as any clot involving the deep veins of the calf that did not extend to the popliteal veins. Calf has got three paired veins – posterior tibial, anterior tibial and peroneal. Calf also has got two unpaired muscular veins – soleal and gastrocnemial. Peroneal veins are commonly involved. Isolated calf muscle vein thrombosis (ICMVT) occurs when thrombosis is confined only to muscular veins; when thrombosis present in paired calf veins, it is called as deep calf vein thrombosis (DCVT). If both paired veins and muscular veins are involved then it is called as isolated distal deep vein thrombosis (IDDVT). Its prevalence is 5-30%. Incidence of propagation of thrombus from deep veins to proximal vein is 5-30%. But post-thrombotic syndrome is not common in IDDVT (calf). Thromboembolism is more common once thrombus extends to proximal vein. Present recommendation is – ultrafraction heparin intravenously or LMWH subcutaneously for 10 days; then vitamin K antagonist (Warfarin) for 3 months. INR should be maintained between 2.0 to 3.0 (2.5). Extended therapy for 6 months may be done depending on the risk factors.

Noncompressible clot in compression ultrasound (duplex) is very useful method of evaluation.

In a confirmed case, thrombectomy may be needed using Fogarty catheter.

Catheter directed thrombolysis (CDT) can be done after cannulating (5F or 6F, US guided, multihole catheter) popliteal vein to reach clot area under ultrasound and also fluorescence guidance and injecting tissue plasminogen activator (tPA) and reteplase into the clot (intraclot). Short saphenous vein or post-tibial veins are also can be used.

IVC filters are used when anticoagulation has failed (recurrent pulmonary embolism), anticoagulation has caused bleeding, when anticoagulation is contraindicated (intracranial haemorrhage).

Pulmonary embolism causes acute dyspnoea, haemoptysis, chest pain, shock, right ventricular dysfunction, severe respiratory distress and death. Well's and modified Geneva criteria are used. CT angiogram is very useful. Treatment is – Heparin, thrombolysis, catheter directed thrombolysis, surgical embolectomy with cardiopulmonary bypass.

Leg elevation, stockings and early ambulation are preventive measures. In confirmed DVT cases massage and hot fermentation are contraindicated.

Duration of anticoagulation in isolated calf vein DVT is 6 weeks; in provoked DVT it is 3-6 moths with risk factor it is with extended therapy of more than 6 months; unprovoked DVT duration is 3-6 moths, if 2nd episode extended therapy for > 6 months. For recurrent DVT it is for life long.

In patients with acute proximal DVT of limb, anticoagulant therapy (LMWH) alone is suggested over systemic/catheter directed thrombolysis or venous thrombectomy.

Thrombolysis is indicated in extensive thrombosis of iliofemoral or proximal sites, threatened limb viability, venous anatomical anomaly.

In pregnancy LMWH is used for DVT. Ultrafraction heparin, vitamin K analogue (Warfarin), direct thrombin (dabigatran) inhibitors and Anti-Xa (rivaroxaban, apixaban) are not used in pregnancy.

VTE treatment is categorised as – initial; long term; extended.

Chronic DVT

It leads into chronic venous insufficiency (CVI). It presents as non healing ulcer over malleoli and lower leg; lymphovenous oedema; ankle fibrosis; pigmentation; lipodermatosclerosis of leg; joint osteoarthritis; quadriceps and calf muscle wasting. It is evaluated by discharge culture study, Doppler study, CT/MRI of part; D dimer test; biomarkers P; selectin/CRP.

It is managed by elevation to reduce edema; compression devices; venous stenting; venous valve repair (valvuloplasty).

Venous ulcer is treated by – compression therapy – 40 mmHg multilayered (four) sustained graduated compression or 2 layered zinc oxide impregnated 25 mm Hg compression; debridement; infection control; colloid silver dressing.

Post-Thrombotic Syndrome (PTS)

PTS is late effect of DVT. It can occur in ileofemoral or femoropopliteal or calf vein DVT. But ileofemoral DVT is more commonly involved with PTS. Residual thrombus increases the risk. It develops in 50% of DVT patients as late effect usually in 2 years. Around 3% of PTS patients develop venous ulcers (post-phlebitis ulcers). It can occur in a DVT patient in spite of anticoagulation therapy. PTS is measured by Villalta scale and Ginsberg measures are used for the assessment of PTS. CEP, VCCS, Wildmer classification is used for chronic venous insufficiency (CVI) assessment. PTS incidence can be reduced by initial treatment of heparin/LMWH for DVT, Warfarin, and early ambulation with compression stockings. Active thrombus removal (thrombectomy) and thrombolysis should be done. US Duplex scan is diagnostic tool. Near infrared spectroscopy (NIRS) is also useful in early detection **(Fig. 12-38)**.

Treatment—drugs, elastic bandage and deep venous reflux surgery – valvuloplasty.



Fig. 12-38: Near Infrared spectroscopy.

IVC Filters

IVC filters are used to prevent dislodged thrombus from entering into right atrium. ACP 2012 (American College of Chest Physicians) and ACR – SIR 2010 (American College of Radiologists and Society for Interventional Radiologists) guidelines are used.

IVC filters are used in pulmonary embolism and DVT when anticoagulants are contraindicated and symptomatic pulmonary embolism with thrombotic load in the limb. IVC filters are indicated in recurrent DVT and pulmonary embolism despite therapeutic anticoagulation; may be useful in free floating thrombus in ileofemoral segment or IVC. IVC filter is indicated in pregnancy when anticoagulants are contraindicated and when there is extensive thromboembolism. If patient had recent history of VTE and he has to undergo some other surgery, then IVC filter is indicated. Chronic thromboembolic pulmonary hypertension needs IVC filters. Retrievable IVC filters are placed.

Prophylactic filters may be used in trauma like closed head injuries, spinal cord injuries, and multiple long / pelvic bone injuries. Infrarenal IVC thrombus, duplication of IVC, larger [pelvic mass prior to surgery if IVC mobilisation is needed, in pregnancy when filters are indicated—suprarenal IVC filters are placed. IVC filters are placed under Duplex US and fluoroscopic guidance **(Fig. 12-39)**.

Retrievable filters are commonly used now. Retrieving is done in 6-12 months or once chances of re DVT have become less. Retrieving is technically easy and safe.

Different filters are – Mobin Uddin; Greenfield; Bard, etc.



Fig. 12-39: Different IVC filters.

Chapter

13

Surgeries of Nerves, Muscles and Tendons

MUSCLE REPAIR

Longitudinal clean incision of the muscle can be left alone or loose 2 zero vicryl sutures are placed. But deep fascia in front should be sutured, muscle hernia can occur otherwise **(Fig. 13-1)**.



Longitudinal tear in the muscle
Such tear can be left alone or sutured transversely using interrupted vicryl 2 zero sutures.

Fig. 13-1: Longitudinal muscle tear is simpler and safer.

It is *the transverse cut/incision* of the muscle which is *more* problematic. It should be sutured using *figure of eight sutures* using vicryl. Direct simple suturing will tear and will not hold. It is often ideal to take the bite of the *adjacent fascia* of the muscle to achieve a proper strength on suturing. Kocher's, horizontal, bucket handle incisions create horizontal cuts in the abdominal muscles. If transverse cut of muscle is not sutured, muscle fibres retract and may atrophy. *Partial transverse cut* may cause hypertrophy of remaining muscle fibres to compensate and function like earlier. Partially cut muscle retracts and forms a '*tumour like*' *swelling* which should be left alone without any surgical intervention. All *complete transverse cuts* in muscle need proper suturing using vicryl. 6 weeks of splintage is necessary **(Fig. 13-2)**.

MUSCLE DEBRIDEMENT (MUSCLE EXCISION)

When muscle is dead or badly infected, entire necrosed muscle should be excised until proper bleeding occurs. All unhealthy, pale, lusterless grey muscle tissues should be liberally excised. Excised muscle bed should be thoroughly irrigated and washed with warm normal saline. A corrugated drain should be placed before suturing. Only skin suturing will suffice; if at all loose apposition sutures using interrupted vicryl 2 zero sutures can be used. One should not place continuous sutures in an infected bed. Proper adequate antibiotics, prevention of tetanus or gas gangrene is also important.



Deep fascia covering the muscle
Muscle fibre
Partial tear often causes a 'tumour like' bulge on one side and compensatory hypertrophy of the remaining muscle fibres. It can be left or few sutures can be placed; but it is often difficult to place sutures.
Complete tear should be sutured.
Figure of eight sutures is used to appose transversecomplete tear of muscle. Deep fascia adjacent also should be sutured.

Fig. 13-2: Transverse muscle tear is difficult to manage either partial or complete.

COMPARTMENT SYNDROME

It occurs due to oedema, haematoma deep-to-deep fascia, in muscular compartment. It is common after trauma, infection, burns. Fracture of bone with haematoma is also a precipitating cause. Pressure within the compartment increases causing poor perfusion of the tissues locally and distally often by blocking the main artery. It is common in *leg*, forearm, thigh and arm. Early emergency decompression by *fasciotomy* is needed. Pain which gets aggravated on muscle action; pallor; absence of distal pulse are typical features. *Lengthy deep multiple fasciotomy incisions* are needed. It releases the pressure, improves the perfusion, and reduces the oedema. Later secondary suturing is done once wound becomes clean and oedema subsides completely.

Fasciotomy in the Calf

It is done by a deep vertical incision placed behind the medial margin of the tibia to release posterior compartment; another deep vertical incision is placed 4 cm lateral to tibia to release anterior and peroneal compartments **(Fig. 13-3)**.


Two incisions—one just behind the medial margin of tibia;
another 4 cm lateral to the tibia are commonly used

Fig. 13-3: Fasciotomy incision in the leg.

Often *flaps can be raised at the level of deep fascia* through a single lateral incision over the fibula (with elevation of flaps) to reach all four compartments of the leg **(Fig. 13-4)**.


Single lateral incision over the fibula with elevation of flaps
can be used to open all 4 compartments

Fig. 13-4: Single lateral incision with elevation of the flap can be used to reach all compartments.

TENDON REPAIR

Tendon heals either by *intrinsic method* when there is no stress to tendon or by *extrinsic method* when there is stress to tendon. Extrinsic healing often causes fibrous mass called *tenoma* which may interfere the tendon gliding.

Tendon injury may be a clean incised injury, or laceration, or tendon rupture due to blunt force or tendon avulsion from the bone.

Flexor and extensor tendons of the fingers are commonly affected. Achilles tendon is commonly injured in the lower limb.

Tendon repair can be primary (within 24 hours); delayed (within a week after 24 hours); secondary (after one week).

Two types of tendon suturing are here.

(1) In Kessler method knot stays in the cut part of the tendon.

(2) In Goldner method knot comes away from cut ends of the tendon **(Fig. 13-5)**.


Cut ends of tendon
Suture knot
Suture
Suture knot

1. Kessler method 2. Goldner method

Fig. 13-5: Types of tendon suturing – 1. Kessler method. 2. Goldner method.

Suture material used for tendon repair is *polypropylene with round body needle*. 3 zero or 4 zero suture is used for smaller tendons; 2 zero is used for tendons like Achilles tendon. Absorbable sutures *should not* be used as with suturing, full tensile strength of the tendon is achieved only after 8 months of the injury. Silk is not used because it causes extensive tissue reaction. In olden days strips of fascia were used (now not used). *Continuous suturing* is done.

Postoperative splintage for 4-6 weeks is needed. Later passive and active exercises are started with proper advice of physiotherapy.

Complications are – infection, adhesion, stiffness and failure.

In avulsion injury of tendon, it is attached to bone by drilling holes in the bone through which tendon is passed. Often this tunneled tendon is buttressed with suture and a button which are removed after 4-6 weeks **(Figs 13-6 and 13-7)**.


Muscle
Tendon
Drill hole in the bone through which
tendon is passed which is sutured/tied
using polypropylene suture.

Fig. 13-6: Suturing of the avulsed tendon into the bone is done by passing tendon across the drilled holes in the bone.


Button which is buttressed
Suture with the knot
Tendon is passed through the drilled bone
with polypropylene suture at its tip

Fig. 13-7: Tendon is passed through the bone and buttressed using a button outside which is removed later.

TENDON RELEASE

It is done for stenosing tenosynovitis of finger (middle or ring) or thumb. Surgical release of the tendon is done, if steroid injection fails. Procedure can be done under local anaesthesia. Release of adjacent soft tissue is often required.

Either transverse or longitudinal incision can be placed over the site just distal to transverse palmar crease.

Similarly tendon release is done for de Quarvain's stenosing tenosynovitis.

TENDON TRANSFER

It is the transfer of one tendon from its existing site to another site where its function is required to have a new function required at the newer site (restore the lost function at the newer site). Function of the transferred tendon should be maintained by other tendons. Tendon should able to acquire the function at the newer site properly. Tendon should be strong enough to have a newer function and should have adequate amplitude of movements. For example, in ulnar claw hand, flexor digitorum superficialis (FDS of index finger) is transferred to lumbrical canal of the digits to have flexion at MCP joint and extension of proximal IP joint. Extensor indicis tendon can be used to replace extensor pollicis longus tendon **(Fig. 13-8)**.


Opening is made near the end of one tendon; through which end of other tendon is passed through.
Looped tendon end is again sutured to the surface of the other tendon proximally.

Fig. 13-8: Method of suturing of the transferred tendon.

Examples

Paul Brand's operation is done for claw hand. Here extensor carpi radialis brevis is transferred with a graft to extensor hood through lumbrical canal. Graft is taken from Palmaris longus.

Stye Bunnell's operation is done for ulnar claw hand only. Here flexor digitorum superficialis is transferred to extensor hood.

Foot drop is corrected by tendon transfer using tibialis posterior muscle with intervening plantaris tendon graft. Tendon is inserted to cuboid and cuneiform bones. *Ober's and Barr's procedures* are different routes of transfer of the tendon into the cuboid and cuneiform bones.

TENDON GRAFT

When tendon suturing or transfer is not possible because of inadequate length, tendon of a muscle which is not functionally much useful (non-essential tendon) is taken as a graft to obtain required length. ***Common grafts used are*** palmaris tendon in forearm and plantaris tendon in leg.

Example - Extensor carpi radialis brevis (ECRB) is lengthened using tendon graft to transfer to lumbrical canals in claw hand.

Problems in tendon graft: Infection, adhesions, graft failure, stiffness of the part.

TENDON LENGTHENING

It is done when existing tendon is short or has become shortened by trauma/infection. It is commonly used in Achilles tendon, hand, forearm etc. Tendon is slit like a lengthy 'L' and is sutured with lengthening **(Fig. 13-9)**.


Lengthy 'L' cut on the tendon
Longitudinal limbs of two 'L' are sutured as required at appropriate lengths

Fig. 13-9: Tendon lengthening technique.

NERVE REPAIRS

Types of Nerve Suturing

Epineurorrhaphy:
Only epineurium is sutured using interrupted sutures. It is commonly used.

Epi-perineurorrhaphy:
Initially perineural sheath and then epineurium is sutured. It is not commonly used.

Repair should be delayed if nerve is lacerated; *marker stitches (using silk)* are then placed at the cut end site to identify the nerve for suturing at a later period. Usually microscope or loup is used for nerve suturing **(Fig. 13-10)**.



Fig. 13-10: Cross section of a peripheral nerve.

Note:

Incomplete injury usually does not require any suturing. Initial management is conservative. Though incised injury commonly transects the nerve; but possibility of nerve injury in blunt trauma should also be remembered. Proper clinical examination for nerve injury is essential.

All suspected nerve injury should be explored under anaesthesia, general or regional. Tourniquet can be used if there is no evidence of ischaemic injury.

Primary repair is done immediately after injury. Nerve ends are minimally trimmed very close using a blade. All fascicles of the nerve are oriented correctly. Two stay sutures are placed to keep the orientation properly. Usually epineural suturing is done using 8 zero polypropylene interrupted sutures. It needs magnification. 6 – 8 sutures are placed for large peripheral nerve like median or ulnar nerve. For small nerve like digital nerve, only 2-3 sutures are placed **(Fig. 13-11)**.


Severed nerve ends are trimmed just close to the ends. Guide/stay stitches are placed on both sides of each end.
Orientation of fascicles are done in both cut ends. Epineural sutures are placed with knots are on outside. Polypropylene interrupted sutures are used.
Completed epineurorrhaphy.

Fig. 13-11: Primary nerve repair.

Secondary repair is done at a later period. It is done in a preexisting scar tissue. Here first nerve ends, both proximal and distal are identified, carefully dissected adequately. Proximal neuroma and distal glioma are trimmed for 1 cm to expose the normal fascicles of the nerve ends. Often guide sutures of silk may be present which were placed earlier during exploration of the trauma. Once nerve ends are clean, it is sutured alike primary suturing with stay sutures, with proper alignment of fascicles, followed by epineural suturing. Here as epineurium is thicker, suturing is easier **(Fig. 13-12)**.


If cut ends are without any undue tension (tension free), then ends are sutured with orientation of fascicles.
Neuroma/glioma formation at the cut ends of nerve.
Neuromas are trimmed for 1-2 cm to get normal fascicles at the nerve ends.
If there is tension then nerve graft is necessary using sural nerve.

Fig. 13-12: Secondary nerve repair.

All nerve suturing should be done *tension free*. If there is tension, it should be corrected by various methods - relaxing incisions; transpositioning of the nerve (like of ulnar nerve in elbow joint); shortening of the bone; nerve graft - usually sural nerve is used for nerve graft (often saphenous nerve is used); positioning of the limb; doing initially *neurolysis* (release of the scar tissue adjacent to injury). Nerve graft is needed if gap is more than 2 cm between the cut ends.

Immobilisation of the part is a must for 3-6 weeks. Adjacent joint should be kept in flexed position; later extension is achieved slowly and gradually. Denervated distal part should be taken care of properly as there may be paralysis, loss of sensation, with possible development of contracture.

Prognostic factors in healing of the nerve injury –

Higher the lesion worse the prognosis (more the distance nerve has to grow means less chance of complete recovery); more the gap between the cut ends worse the prognosis; associated injuries alter the prognosis; children do better with nerve injury; type of the injury also decides the prognosis; technical precision also decides the outcome of the surgery.

If nerve suturing fails or cannot be done, then tendon transfer is done at a later period after 4-6 months.

Different Nerve Injuries

Facial nerve injury occurs during parotidectomy. It may be neuropraxia or complete injury. If it is neuropraxia, it is treated conservatively with steroid, tarsorrhaphy. If it is complete injury, it is repaired using nerve graft. Grafts used are great auricular nerve or hypoglossal nerve.

Recurrent laryngeal nerve injury is seen after thyroidectomy, oesophagectomy, tracheal surgery, mediastinal surgery. Its management is discussed in Chapter 15 'Surgery for Thyroid and Parathyroids'.

Radial nerve injury causes wrist drop. Its primary suturing is effective as it is mainly motor. But it takes a year time for recovery. So tendon transfer is often done.

Median and ulnar nerves can be damaged at wrist, forearm or at elbow. They are repaired primarily. If lacerated or crushed, guide stitches are placed and later secondarily repaired. Ulnar nerve when injured at the elbow is sutured in front of the elbow to reduce the tension.

Brachial plexus injury is complicated injury as it may be supraclavicular/infraclavicular; pre-ganglionic or post-ganglionic. It needs a combined, specialised, multidisciplinary approach.

Tibial and common peroneal nerves are also repaired using similar principles. *Sciatic nerve* suturing does not give good result even though it looks technically sound.

Autonomic nerves being non-myelinated, axonal growth will not occur and so nerve repair is not effective.

Classification of Nerve Injuries

Seddon's Classification

Neuropraxia: It is temporary physiological paralysis of nerve conduction. Here recovery is complete. There is no reaction of degeneration.

Axonotmesis: It is division of nerve fibres or axons with intact nerve sheath. There is reaction of degeneration distally with near complete recovery. Patient can present with sensory loss, paralysis of muscles or causalgia.

Neurotmesis: Here complete division of nerve fibres with sheath occurs. Degeneration occurs proximally up to the first node of *Ranvier* as well as distal to the injury. Recovery is incomplete even after nerve suturing. There is complete loss of motor and sensory functions with loss of reflexes. If the nerve is mixed type other than pure motor or sensory recovery is still poorer.

Sunderland's Classification

i. Conduction block—temporary neuronal block.
ii. Axonotmesis but endoneurium is preserved.
iii. Axonotmesis with disruption of endoneurium but perineurium is preserved.
iv. Here disruption of endo and perineurium has occurred but epineurium is intact.
v. Neurotmesis with disruption of endo, peri and epineurium has occurred.

TINEL'S SIGN

It is the clinical sign (*prognostic indicator*) used to assess the level of regeneration. It is elicited 3 weeks after the nerve injury (regeneration begins after the completion of nerve degeneration). Tapping over the course of the nerve is done *from distal to proximal* to elicit a sensation of *`pins and needles' or hyperaesthesia*. If sensation is felt at the site as well as distally along the distribution of the nerve that means *good recovery* can be expected. If sensation is felt only at the site of tapping, then result is *equivocal*. If no sensation is felt it means no recovery.

MANAGEMENT OF NERVE ENTRAPMENT/ COMPRESSION (NERVE RELEASE)

Nerve entrapment and specific nerve injury is commonly due to trauma, constriction bands, fibrosis. It is treated by steroid injections, surgical release of entrapped nerve. Examples are median nerve entrapment in carpal tunnel syndrome, meralgia paraesthetica of thigh, tardy ulnar palsy causing ulnar nerve compression.

Carpal Tunnel Syndrome

It presents with median nerve palsy. Median nerve is deep to flexor retinaculum which gets entrapped under the flexor retinaculum due to causes like trauma (lunate dislocation, malunited Colle's fracture), myxoedema, acromegaly. Flexor retinaculum is also called as *transverse carpal ligament* which extends laterally from trapezium and scaphoid, medially to pisiform and hook of hamate. Flexor retinaculum maintains the concavity of the wrist. It is diagnosed clinically and confirmed by nerve conduction studies. Cervical rib and cervical spondylosis are the differential diagnosis **(Fig. 13-13)**.

Surgery is usually done under *local anaesthesia*. General or brachial block can be used. Tourniquet is commonly used. *Vertical crease incision* is made in the proximal part of the palm with convexity of the incision towards the ulnar side **(Fig. 13-14)**.

Skin incision is deepened. Palmar cutaneous branch of the median nerve should be preserved. Incision is deepened to identify the flexor retinaculum. *Entire length, both superficial and deep parts* should be cut properly. It is cut towards ulnar side of the wound. *Only skin* is sutured using interrupted nonabsorbable 3 zero polypropylene or polyethylene sutures.

Complications are incomplete fasciotomy and recurrence, nerve injury.

Using small proximal incision, endoscope can be passed to visualise and cut the entire flexor retinaculum – *minimal access surgery*.

Anterior Transposition of the Ulnar Nerve

Ulnar nerve is behind the medial epicondyle (behind common flexor origin). Medial epicondylitis causes tardy ulnar palsy. In such situation common flexor tendon is released from its origin; ulnar nerve is placed in front of the flexor origin; detached common flexor tendon is reattached to medial condyle. It is called as anterior transposition of ulnar nerve. It is also used in ulnar nerve injury. Elbow is immobilised for 3 weeks.

Meralgia Paraesthetica

It is entrapment neuropathy of lateral cutaneous nerve of thigh under the inguinal ligament. It arises from posterior divisions of lumbar plexus (L2, 3); runs over the quadrates lumborum and iliacus muscles; emerges behind the lateral part of the inguinal ligament; divides into anterior and posterior branches, supplying skin over anterolateral part of the thigh and anterior part of the gluteal region. Patient presents with loss of sensation at the area of distribution of the lateral cutaneous nerve of thigh (upper lateral part of the thigh). It is treated by reassurance and steroid injection. Nerve release is routinely not required **(Fig. 13-15)**.



Fig. 13-13: Anatomy of the carpal tunnel and flexor retinaculum.



Fig. 13-14: Incision for carpal tunnel syndrome.



Fig. 13-15: Lumbar plexus showing origin of lateral cutaneous nerve of thigh.

LUMBAR SYMPATHECTOMY

Indications

It is mainly used to improve the healing of cutaneous ulcers in patients with vascular disease like TAO; in causalgia of lower limb (it is common in upper limb). Its benefits are temporary. It causes cutaneous vasodilatation by sympathetic blockage. It may also be used to improve the blood supply of skin flaps in amputations.

Contraindications

It is contraindicated in patients with bleeding disorders and patients who are on anticoagulants.

Principles

It is a pre-ganglionic sympathectomy. Ganglia L2 and 3 supply leg below the knee level. L1 supplies buttock and upper thigh. L1 lies under the crus of diaphragm. L4 lies under the common iliac vessels.

Procedure

General or spinal anaesthesia is used. Patient should be strapped to table in lateral tilt position. Incision is transverse or oblique at the level of the umbilicus extending obliquely downwards. External and internal oblique muscles are divided; transverse abdominis muscle is initially split from posterior part, then towards anterior part (as peritoneum is adherent to muscle in anterior part but free in posterior aspect and so to avoid opening of the peritoneum it is split from behind). Peritoneum is pushed medially by finger dissection. If peritoneum is opened it is closed using vicryl continuous sutures. It is swept in front of the psoas major muscle towards medially. Genitofemoral nerve and ureter are identified. Ureter along with peritoneum is retracted medially using Deaver's retractor. Additional Deaver retractor is used to tract the upper part of the wound. Self retaining retractor may be useful at this stage. IVC is visualised as a bluish structure. Its posterior aspect is gently dissected using peanut and fine dissections. One should not injure the lumbar veins which if injured may cause torrential bleeding and obscure the surgical field. On the left side sympathetic chain is behind the aorta, which is mobilised to reach the chain. Sympathetic chain is identified as stiff vertically placed structure behind the IVC/aorta in front of the vertebrae which can be felt by rolling the finger. *L2 is identified* as it is largest ganglion. L1 is high up behind the diaphragmatic crus and it should not be removed. L2, 3 and 4 are removed. L5 is often below which may or may not be removed. Chain is dissected off the vertebrae using scissor for adequate length and is cut using scissor. It is not necessary to ligate the chain on either side. After removal specimen chain is sent for histology for confirmation. Haemostasis is confirmed. Wound is closed in layers using 1 zero vicryl. Drain is usually not necessary unless there is bleeding **(Fig. 13-16)**.

Postoperative Period

Patient is monitored for bleeding. Temperature of the limb is checked which will become warmer (becomes warmer immediately after sympathectomy). Sutures removed in 7-10 days.

Problems and Complications

Often, reaching the sympathetic chain may be problematic. Injury to IVC (rarely aorta on left side) may be dangerous. If IVC is injured, it should be clamped using Satinsky clamp; and sutured using 4 zero polypropylene suture. Injury to peritoneum, bowel, and ureter can occur. Bleeding lumbar veins is quite difficult to tackle. Bipolar diathermy fulguration is useful. If it is identified it can be ligated gently. Often it is ligated during surgical dissection itself to avoid bleeding. Spasm of spinal cord vessel and spinal cord ischaemia and paraplegia can develop rarely. If L1 ganglia of both sides are removed, ejaculatory failure can develop (dry ejaculation). Haematoma formation, wound infection are other complications.

Effects of lumbar sympathectomy are *temporary* (*3-4 weeks*). By improving the cutaneous blood supply it promotes ulcer healing. But it may reduce the blood supply of deeper muscles (as it is diverted towards skin), and hence claudication is not benefited by lumbar sympathectomy but may get aggravated.


Position of the patient:
- Sand bag behind lumbosacral region
- Hip and knee flexed
- Pillow between thighs
Incision is at the level of umbilicus obliquely from lateral (anterior axillary line) to medial (up to lateral margin of rectus)
External oblique muscle
Internal oblique muscle
External oblique
Internal oblique
Transverse abdominis
Split the transversus abdominis at posterior aspect
Peritoneum is visible
- Do not open peritoneum
- But reflect it with finger dissection/sweeping
Deaver retractor medially
Psoas major muscle
Retractor below
Deaver retractor above

Figs 13-16(1)


Gonadal vessel (vein)
Ureter
Genitofemoral nerve
Psoas major
IVC
Lumbar sympathetic chain behind the IVC
Finger/gentle peanut dissection behind IVC. Care about lumbar veins
IVC
IVC
Lumbar sympathetic chain
Holding the lumbar sympathetic chain with long artery forceps
Applying two long artery forceps to cut in between

Figs 13-16(2)



Figs 13-16(3)

Fig. 13-16: Operative steps in lumbar sympathectomy.

Laparoscopic Retroperitoneal Lumbar Sympathectomy

Lumbar sympathectomy also can be done using laparoscopic retroperitoneal approach with same position by placing three ports. One port is placed at anterior axillary line (10 mm port for camera); two 5 mm ports are placed medially above and below. Dissection is done in front of the psoas major muscle towards medially reflecting the peritoneum, ureter in front. IVC is identified. Dissection is done behind the IVC. Sympathetic chain is identified and removed.

Chemical Sympathectomy

It is done in lateral position using a long spinal needle. Local anaesthesia is infiltrated first. Position of the chain is confirmed under fluoroscopy by injecting dye. 5 ml of phenol in water or absolute alcohol is injected lateral to the vertebral bodies of 4th and 2nd lumbar vertebrae. Needle should not enter the IVC or aorta. Limb becomes warmer immediately. Initial trial injection of the lignocaine to confirm the benefit may be done. Technique should not be done in bleeding disorders and in patients who are on anticoagulants.

CERVICOTHORACIC SYMPATHECTOMY

It is the removal of 2nd and 3rd thoracic ganglia which contain postganglionic fibers supplying the upper limb. Preganglionic white rami communicantes fibres of 2nd and 3rd sympathetic nerves enter thoracic T1 ganglion supplying the head and neck region through upper part of the stellate ganglion. Pre-ganglionic sympathetic nerve entering the 2nd and 3rd ganglia from below supplies sympathetic fibres of upper limb through lower part of the stellate ganglion.

In cervical sympathectomy for upper limb ischaemia, lower part of the stellate ganglion and Kuntz nerve is divided. For head and neck hyperhidrosis entire stellate ganglion is removed which leads to development of Horner's syndrome.

For hyperhidrosis of axillary region stellate ganglion, upper four thoracic ganglia are removed.

Surgical Anatomy

Preganglionic fibres arise from lateral horns of the T_1 to T_{12} segments of spinal cord. T_1 to T_{12} lateral horns → Preganglionic fibres → Ventral roots of spinal cord → Beginning of ventral rami → White rami communicantes (14 on each side)

↓ ↓ ↓ ↓

Relay in sympathetic trunk ganglia which gives post ganglionic fibers as grey rami communicantes	Pass through ganglia without any connection to higher or lower ganglia where it communicates.	Synapses in ganglia to supply viscera – heart, lungs, aorta, oesophagus (T1-5).	White rami pass through corresponding ganglia without relay and emerges out as greater (T5-9); lesser (T9-10); lowest/least (T11) splanchnic nerves to supply abdomen through splanchnic ganglia.

Ganglia are connected to respective spinal nerves through white rami (from spinal nerve to ganglia) and grey rami (from ganglia to spinal nerves) communicantes.

In the neck there are 3 cervical sympathetic ganglia – *superior,* at the level of greater cornu of hyoid; *middle,* at the level of cricoid; *inferior,* 3 cm above the sternoclavicular joint. Sympathetic chain here is located behind the carotid sheath in front of the prevertebral fascia. Superior is the largest of the three – 2.5 cm; located below the skull opposite 2nd and 3rd cervical vertebrae behind carotid sheath; which actually is fused upper 4 cervical ganglia. It communicates with 9th, 10th, 12th cranial nerves and external and recurrent laryngeal nerves. It sends branches to plexus around ECA, ICA and other branches in the neck; branches to otic, submandibular, ciliary and pterygopalatine ganglia in neck; to pharynx. Middle cervical ganglion is very small, often it is branched or absent; situated in front of the C6 vertebra above inferior thyroid artery behind the carotid sheath. It is formed by 5th and 6th ganglia; is connected to inferior cervical ganglion through a looped ansa subclavia and also directly. It gives branches to C5 and C6 spinal nerves, thyroid, parathyroid, trachea, oesophagus and middle cervical cardiac branch. Inferior cervical ganglion is formed by 7th and 8th cervical ganglia; often it is fused with 1st thoracic ganglion to form stellate ganglion. It is located between transverse process of C7 vertebra and neck of first rib. It gives branches to C7, C8 ventral nerves, vertebral and subclavian artery plexus, inferior cervical cardiac branch **(Fig. 13-17)**.

Sympathetic outflow to upper limb is from T2 to T9; T1 also may contribute to supply arm in 10% of cases. A direct communication may be present between 2nd and 3rd thoracic ganglia and brachial plexus through *nerve of Kuntz*.

Indications

Hyperhidrosis (very useful), causalgia (very useful), autonomic nerve dystrophies, cervical rib with vascular manifestations (useful), Raynaud's phenomenon (useful), other causes of upper limb ischaemia (useful), acrocyanosis (useful), Sudeck's osteodystrophy (useful). Conditions with vasospasm will get benefited rather than conditions with obliterative digital vessel occlusion.

Approaches

Supraclavicular, transthoracic/axillary approach *(Hedley Atkins),* thoracoscopic approach (better) are the different approaches used.


External carotid artery
Pharynx
Internal carotid nerve
Grey rami to cervical ventral rami
Superior cervical ganglion (largest)
Right superior cardiac branch
Left superior cardiac branch
Middle cervical ganglion (smallest)
Thyroid
Trachea
Oesophagus
Vertebral artery
Ansa subclavia
Subclavian artery
Inferior cervical ganglion (stellate)
Superficial cardiac plexus
Middle cardiac branch
Deep cardiac plexus
Inferior cardiac branch

Fig. 13-17: Cervical sympathetic chain – surgical anatomy.

Supraclavicular Approach

It is done under general anaesthesia. Patient is positioned supine with head end of the table elevated by 15°to reduce venous congestion and head is tilted to opposite side; arms are placed on the sides of the patient. Incision is placed a fingerbreadth (1.5 cm) above the clavicle from anterior border of the sternocleidomastoid muscle extending laterally for 7-8 cm. It is usual but not mandatory practice to pull/drag the skin downwards below the clavicle and make incision on the clavicle from medial to lateral; and when pulled skin is released after making incision, incision will be in supraclavicular area. It is said to prevent inadvertent injury to deeper structures. Incision is deepened; Platysma is incised. External jugular vein is divided with ligatures. Supraclavicular nerves are retained. Exposed sternocleidomastoid muscle is identified for its full width. The clavicular head is divided using scissor/cautery/or by piecemeal using fine forceps (used in olden days). IJV behind the muscle should not be injured. Scalene pad of fat is dissected. Inferior belly of omohyoid muscle is divided. IJV is mobilised and retracted medially. Bipolar cautery dissection is done in front of the scalene muscle. Phrenic nerve is identified in front of the scalenus anterior muscle deep to deep fascia running vertically downwards from lateral to medial side. Phrenic nerve is retracted medially (should not be retracted laterally as it may cause traction injury to upper trunk of brachial plexus). Dissected scalenus anterior muscle is cut layer by layer carefully using scissor / by piecemeal method to protect subclavian artery underneath. Medial part of the brachial plexus is dissected carefully. Subclavian artery is dissected on its summit and pushed downwards. Occasionally thyrocervical trunk may have to be ligated. Often subclavian artery is dissected and slinged upwards; but one should be careful while pulling the sling especially in atherosclerotic vessel. Head light may be better used for further dissection. Subclavian artery is retracted downwards. In the triangle between brachial plexus, subclavian artery and IJV, suprapleural membrane (Sibson's fascia) is felt with index finger which is divided using finger dissection by pushing it downwards against vertebra (*Sibson's fascia* also called as vertebropleural fascia is tent like thickening of the prevertebral fascia extending from transverse process of C7 to first rib). Once it is divided, retropleural space is dissected by pushing the pleura downwards using finger and pleura and Sibson's fascia is retracted downwards. Stellate ganglion is identified at the neck of the first rib. By finger and swab dissection entire ganglion is exposed. Right angle is passed underneath; sympathetic chain below is dissected up to 3rd ganglion. Intercostal veins crossing the chain should be carefully separated or ligated between haemoclips. Entire ganglion is not removed for upper limb diseases as it will cause Horner's syndrome. Lower part of the ganglion, where rami from 1st thoracic nerve enters is divided. Lower end is dissected downwards below the level of thoracic 3rd ganglion and chain is cut again at this level. Chain is sent for histology. Lung is inflated. Wound is closed in layers. Drain is usually not necessary **(Fig. 13-18)**.

Complications

Complications are bleeding; injury to subclavian artery and nerves; pneumothorax and haemothorax; Horner's syndrome presenting as ptosis, miosis, anhydrosis, enophthalmos, loss of ciliospinal reflex. Chest X-ray is taken during postoperative period when suspected to rule out pneumothorax. If pneumothorax is present, intercostal tube should be placed. Left sided sympathectomy may cause thoracic duct injury. Neuropraxia of brachial plexus is known to occur due to traction during procedure.

Advantages

Postoperative recovery is faster with less duration of hospital stay and less disability.

Disadvantage

Difficult narrow space approach is the limitation.


Clavicular head
Sternal head
Sternomastoid muscle
Clavicle
Incision
Sternum
External jugular vein ligated
Clavicular head of sternomastoid muscle is cut
Sternal head kept intact
IJV
Phrenic nerve is crossing in front of the scalenus anterior muscle from lateral to medial and above downwards.
Brachial plexus
Phrenic nerve is retracted medially (not laterally)
IJV
Subclavian artery
Dome of the pleura with Sibson's fascia
Line of cutting is either above T2 or at lower part of stellate ganglion
Stellate (cervico thoracic) ganglion
T2 ganglion
T3 ganglion
T4 ganglion
Lower line cutting of the chain is below the T4 commonly or below T5 occasionally
T5 ganglion

Fig. 13-18: Cervicothoracic sympathectomy – through supraclavicular approach.

Transaxillary Approach

It is better approach but needs prolonged hospitalisation and has slow postoperative recovery. Either extrapleural or transpleural approaches are used.

Transaxillary extrapleural approach is done using standard thoracotomy position. Arm of the same side is fully abducted to expose the entire axilla. Arm, chest, back, shoulder area is cleaned and draped. Incision is placed at lower margin of the axillary hair line from margin of pectoralis major in front to margin of latissimus dorsi behind **(Fig. 13-19)**.



Fig. 13-19: Incision for the transaxillary extrapleural approach – It is in the axilla placed at lower margin of the hairline from pectoralis major to latissimus dorsi muscle along the first rib.

Incision is deepened to reach the first rib. Intercostobrachial nerve is divided. A branch from axillary artery is divided. Anterior scalene muscle is divided to expose the superior surface of the first rib. Intercostal muscles are stripped off from the inferior surface of the first rib using periosteal elevator. First rib is excised using bone cutter and end is smoothened using rongeur. Pleural dome is pushed away from the mediastinum using finger dissection. Subclavian vessels are identified. Sympathetic chain is identified between T1 nerve root and subclavian artery. Sympathectomy is done from lower half of the stellate ganglion to lower margin of T 3 ganglion. One should confirm that there is no pleural tear and pneumothorax, if it so chest tube may be placed and wound is closed in layers. Postoperative chest X-ray is a must.

Transaxillary transpleural approach is done through 3rd intercostal space. Position is same as extrapleural approach. Incision of 15 cm in length is made along the line of 3rd rib from posterior axillary fold to anterior axillary fold downwards and forwards. Incision is deepened to periosteum of the 3rd rib **(Fig. 13-20)**.

Pectori are retracted forward; latissimus dorsi, teres major, subscapularis and long thoracic nerve are retracted backward. Lateral thoracic artery near the posterior portion of the wound is divided. Attachment of serratus anterior is removed from 3rd rib. Using cautery, periosteum of the 3rd rib is incised throughout its full length. Often 3rd rib is resected deep to its periosteum. Pleura is opened through the periosteum of the 3rd rib to avoid injury to intercostal neurovascular bundle. Thorax is opened widely using a rib spreader. Lung is deflated to visualise the mediastinal and dome of the pleura. Thoracic vertebrae (upper five) and corresponding ribs are exposed to visualise the sympathetic chain beneath the pleura on the necks of the ribs. Parietal pleura is opened vertically on the sympathetic chain using long fine scissor. Nerve is held with nerve hook below the 4th thoracic ganglion and cut and rami communicantes are divided. Chain above the 2nd or lower half of the stellate ganglion is cut to remove needed segment of the sympathetic chain. Dissection along the chain should be careful and gentle as intercostal vessel bleeding, if occurs, is often difficult to control. If bleeding occurs, bleeding point is carefully identified by proper suction and haemoclips are applied. Bipolar cautery is used for fulguration if needed. Care should be taken not to injure or cauterise the intercostal nerve which will cause troublesome neuralgia. Chest tube is inserted to pleural cavity and wound is closed in layers. Bilateral sympathectomies, if needed, should be done in different sittings.



Fig. 13-20: Incision for transaxillary transpleural approach is through 3rd rib.

Thoracoscopic Sympathectomy

It is preferred method than open method as there is better visualization and identification of the sympathetic chain, faster recovery, and small incisions. Procedure is done under general anaesthesia with open thoracotomy position with operating side of the patient elevated. Double lumen or bronchial blocker is used to facilitate the deflation of the same side of the lung. Zero or 30° telescope is used through 10 mm port at the centre of 4th or 5th intercostal space in anterior or mid-axillary line. Two 5 mm ports are placed side wards above and below the 10 mm port through intercostal spaces which will be in front of the 10 mm camera port to provide adequate triangulation. Lung is deflated by anaesthetist. If not deflated properly then CO_2 insufflation may be used. Sympathetic chain is visualised properly on the necks of the ribs. Overlying pleura is opened using cautery, harmonic scalpel or scissor. Care should be taken not to injure intercostal vessels and nerve. Chain from T4 to T1 is removed. Haemostasis is maintained. Chest tube is placed. Difficulties lie in identifying the chain, lifting the pleura, haemostasis. Advantages are fast recovery, good magnification, and less painful.

Chapter 14

Surgeries of Face, Head and Neck

SURGICAL ANATOMY OF NECK

Neck has got anterior and posterior triangles on each side. Skin over the anterior triangle is supplied by anterior cutaneous nerve of neck (C_2, C_3).

Superficial fascia in anterior triangle contains *platysma*, cervical branch of facial nerve, anterior jugular vein and few superficial lymph nodes. Flaps in the neck are usually elevated in *subplatysmal plane*.

Platysma is a wide thin subcutaneous muscle running upwards and medially from *deltoid and pectoral fascia* to the *base of the mandible*. It is supplied by cervical branch of facial nerve. It prevents the skin pressing into superficial veins. Superficial vessels and nerves lie deep to platysma.

Anterior jugular vein is located in superficial fascia which begins below the chin runs vertically downwards 1 cm from the midline; 2.5 cm above the sternum, it pierces the deep fascia to reach suprasternal space where it communicates with opposite anterior jugular vein through jugular venous arch and travels above the clavicle behind the sternocleidomastoid muscle to join external jugular vein.

Structures above the hyoid bone are – anterior belly of digastric, submandibular salivary gland, mylohyoid nerve and vessels, submental branch of facial artery, hyoglossus, intermediate digastric tendon with pulley, stylohyoid muscle tendon, and hypoglossal nerve. *Subhyoid bursa* is located between posterior surface of the body of hyoid bone and thyrohyoid membrane to reduce the friction between the two during swallowing **(Figs 14-1 and 14-2)**.

Structures below the level of hyoid bone are – infrahyoid muscles [sternohyoid (medial front), omohyoid [lateral in front], sternothyroid (lateral deep, below), thyrohyoid (lateral, deep, above); pretracheal fascia (with thyrohyoid membrane, thyroid cartilage, cricothyroid membrane, cricoid arch, cricothyroid muscle, trachea and carotid sheath).

Anterior triangle of neck is bound by midline, sternocleidomastoid muscle laterally, base of mandible and line joining angle of mandible and mastoid process above. Triangle is divided by digastric muscle and superior belly of omohyoid muscle as muscular, submental, carotid and digastric triangles. Suprahyoid muscles are digastric, mylohyoid, stylohyoid and geniohyoid muscles **(Fig. 14-3)**.

Submental triangle is median in location and is bound by anterior bellies of digastric muscles of both sides with the base on the hyoid bone. Floor is formed by right and left mylohyoid muscles. It contains submental veins and submental lymph nodes (*located in superficial fascia*) which drain from superficial tissues below chin, central part of lower lip, adjacent gum, anterior part of floor of the mouth, and tip of tongue. These lymph nodes drain into submandibular lymph nodes.


Mandible
Ant jugular vein in superficial fascia
Ant jugular vein piercing deep fascia
External jugular vein
Sternocleidomastoid
Platysma
Sternum
Jugular venous arch in deep fascia

Fig. 14-1: Anatomy of anterior jugular vein and platysma.


Pulley of digastric
Hyoid bone
Thyroid cartilage
Omohyoid
Superior belly
Inferior belly
Superior margin of scapula
Sternohyoid
Manubrium sternum
Anterior belly of digastric
Mylohyoid muscle
Hyoglossus muscle
Posterior belly of digastric
Thyrohyoid
Oblique line of thyroid cartilage
Sternothyroid
Clavicle
First rib

Fig. 14-2: Strap and front muscles of the neck.



Fig. 14-3: Different triangles in neck.

Digastric triangle is formed by two bellies of digastric muscle, posteriorly also by stylohyoid muscle, base above is by the base of mandible and line joining the angle of mandible and mastoid process. Its roof is formed by skin; superficial fascia with platysma, cervical branch of facial nerve and ascending branch of anterior cutaneous nerve; deep fascia splits to enclose submandibular salivary gland. Its floor is formed by mylohyoid muscle in front, hyoglossus behind and middle constrictor partly. Structures superficial to mylohyoid and hyoglossus are – submandibular salivary gland (superficial part), facial vein, submandibular lymph nodes, submental artery and mylohyoid nerve and vessels, intermediate tendon of the digastric muscle and stylohyoid, hypoglossal nerve. Facial artery is deep to mylohyoid muscle. In the posterior part of digastric triangle lower pole of the parotid and external carotid artery entering the parotid are in superficial location; whereas structures passing between ECA and ICA (styloglossus, stylopharyngeus, glossopharyngeal nerve, pharyngeal branch of vagus, styloid process) are in deeper plane. ICA, IJV and vagus are located still in deeper plane. Submandibular lymph glands are located *deep* to deep fascia on the surface of submandibular salivary gland which drains from forehead, nose, frontal, maxillary and ethmoidal air sinuses, inner canthus of eye, upper lip, anterior cheek with adjacent gums and teeth, outer part of lower lip with adjacent teeth and gums except incisors, anterior 2/3rd of tongue except tip of tongue and floor of the mouth, from submental lymph glands. Efferent vessels drain mainly into jugulo omohyoid lymph nodes.

Carotid triangle is bound above and in front by posterior belly of digastric and stylohyoid muscle; below by superior belly of omohyoid; behind by sternocleidomastoid muscle. Its roof is formed by skin; superficial fascia with platysma, cervical branch of facial nerve and transverse cutaneous nerve; deep fascia. Its floor is formed by thyrohyoid, hyoglossus, and middle and inferior constrictor muscles. It contains – arteries (CCA, ICA, ECA, superior thyroid, facial, ascending pharyngeal, occipital arteries); veins (IJV, common facial vein entering the IJV, pharyngeal vein entering IJV or common facial vein, lingual vein entering the IJV); nerves (Vagus, superior laryngeal nerve and its branches, spinal accessory nerve, hypoglossal nerve, ansa cervicalis, sympathetic chain behind carotid sheath); carotid sheath with its contents; lymph nodes (jugulodigastric is below the posterior belly of digastric and jugulo omohyoid above the inferior belly of digastric).

Investing layer of deep fascia is attached above to external occipital protuberance, superior nuchal line, mastoid process; fascia splits between angle of mandible and mastoid process to enclose parotid. Above the parotid the outer lamina (split part) which is dense and thick gets attached to zygomatic arch. Thin deeper lamina is attached to styloid process, mandible and tympanic plate. Deeper lamina is condensed between angle of mandible and styloid process to form stylomandibular ligament. Below, investing layer is attached to scapular spine, acromion, clavicle, manubrium in front. Behind it is attached to ligamentum nuchae and C_7 spine; in front to symphysis menti and hyoid bone. Investing layer of deep fascia *encloses* trapezius and sternocleidomastoid muscles, parotid and submandibular salivary glands, supraclavicular and suprasternal spaces. Deep fascia forms digastric and omohyoid *pulleys*. Suprasternal *space of Burns* contains tendinous sternal heads of both sternocleidomastoids; jugular venous arch, a lymph node and interclavicular ligament.

Prevertebral fascia is in front of the prevertebral muscles is attached above to the base of skull; below extends into the superior mediastinum to attach to anterior longitudinal ligament and body of T_4 vertebra. In front it is separated from pharynx by retropharyngeal space. Laterally, it merges deep into trapezius. Cervical and brachial plexus of nerves lie behind this fascia. Four cutaneous branches of cervical plexus pierce this fascia. Subclavian artery and brachial plexus runs between scalenus anterior and medius carrying with them prevertebral fascia as *axillary sheath*. Subclavian and axillary veins are away and below this fascia and so are not inside the axillary sheath.

Posterior triangle is the space located between sternocleidomastoid muscle, trapezius and middle 1/3rd of clavicle. Its *roof* is formed by investing layer of deep fascia. Superficial fascia in posterior triangle contains platysma, external jugular and posterior jugular veins.

External jugular vein is located in superficial fascia deep to platysma; begins at lower part of the parotid by union of posterior auricular vein and posterior division of retromandibular vein; descends downwards in front of the sternocleidomastoid muscle; enters the roof of posterior triangle – investing layer of deep fascia at anteroinferior angle of roof to join subclavian vein. Deep fascia is densely adherent to vein at the point of entering the roof and so external jugular vein when cut, opening cannot be closed, as a result of which air is sucked inside causing air embolism. Before ligating the vein deep fascia should be cut to collapse the vein. Tributaries of external jugular vein are—posterior external jugular vein, transverse cervical vein, suprascapular vein and anterior jugular vein. An oblique jugular vein connects between external jugular vein and IJV at anterior margin of sternocleidomastoid at middle third of the muscle. Surface marking of the vein is from below and behind the angle of the mandible to a point lateral to the posterior border of the sternocleidomastoid near clavicle.

Floor of the posterior triangle is formed by prevertebral fascia over splenius capitis, levator scapulae, scalenus medius, and often scalenus posterior **(Fig. 14-4)**.



Fig. 14-4: Structures forming the floor of posterior triangle.

Posterior triangle is divided by inferior belly of omohyoid into a *smaller lower supraclavicular* / subclavian triangle and a *larger upper* occipital triangle. *Contents of the posterior triangle* are: The nerves—the spinal accessory nerve; four cutaneous branches of cervical plexus (lesser occipital (C_2), great auricular ($C_{2,3}$), anterior cutaneous nerve of the neck ($C_{2,3}$), supraclavicular nerves ($C_{3,4}$)); muscular branches to levator scapulae and trapezius ($C_{3,4}$); nerve to rhomboideus (C_5); nerve to serratus anterior ($C_{5,6,7}$); nerve to subclavius ($C_{5,6}$); suprascapular nerve ($C_{5,6}$); three trunks of brachial plexus. Arteries, from above downwards are – occipital artery at the apex of the posterior triangle superficial to splenius capitis, transverse cervical artery, suprascapular artery and subclavian artery. Transverse cervical artery arises from thyrocervical trunk, crosses scalenus anterior, phrenic nerve, upper trunks of brachial plexus, nerve to subclavius, suprascapular nerve, and scalenus medius. It is deep to inferior belly of omohyoid muscle. At the anterior margin of levator scapulae it divides into superficial and deep branches. Posterior triangle also contains many deep lymph nodes of the neck (level V) **(Fig. 14-5)**.



Fig. 14-5: Location of spinal accessory nerve.

BASIC PRINCIPLES IN HEAD AND NECK SURGERY

General anaesthesia with intubation is essential in all head and neck surgeries. Only surgeries like superficial excision (cyst/lipoma excision) can be done under local infiltration anaesthesia. Cervical block is often used by few experts for laryngeal surgeries, carotid endarterectomy, and thyroidectomy. Fitness for prolonged anaesthesia, arranging adequate amount of blood, proper assessment of the lesion by CT scan, usage of different energy sources, need for tracheostomy should all be thought of.

Extension of the head is usually needed in most of the head and neck surgeries which is achieved by placing a sandbag/rolled up towel/round pillow under the shoulder. Arms are pulled down with the shoulder depressed and both hands tugged under the buttock. Neck may require to be turned towards opposite side. Head end of the table is raised 15^0 in order to reduce venous congestion and bleeding.

Cleaning is done over entire neck in front, face, upper chest up to the nipple line, both shoulder area. Head is draped with sterile double towel technique. Two towels are placed under the head; towel in front is folded over the head up to chin in neck surgery, up to eyebrow in face surgery **(Fig. 14-6)**.

Skin incisions in the neck are usually placed along the lines of natural skin crease which are horizontal in front of the neck, horizontally oblique on the side of the neck. So, most of the neck incisions are horizontally placed to achieve better scar. Vertical incision causes scar contraction, hypertrophy and results in poor scar. Vertical incision is used for major vascular access (for carotids), and in trauma. In such occasions, incision is placed along the anterior border of the sternocleidomastoid muscle or along the anterior border of the trapezius.

Surgical dissection in head and neck is done using 15 number scalpel blade or fine scissor or fine monopolar/blended cautery tip. Skin hooks are used while elevating the skin flaps. Dissection should be perfect with meticulous haemostasis. Proper knowledge of surgical anatomy of neck is essential. Usually subplatysmal plane is raised. Finally closure is also equally important to achieve cosmetically acceptable good healthy scar.

Since neck is a compact area, small incision should be avoided. An adequate incision which will expose the surgical area is essential. Proper haemostasis by ligature/cautery harmonic energy is needed. *Haematoma in the neck under the deep fascia* will compress trachea and can cause life threatening respiratory arrest. A *suction drain* is usual practice to prevent this. Drain is removed in 48 hours. *Haematoma superficial to deep fascia* also can occur but is not life threatening. It may cause fibrosis and poor scarring. During closure, deep fascia, platysma are closed in layers using absorbable 3 zero vicryl interrupted sutures.

Skin is closed with interrupted sutures (using monofilament nonabsorbable suture material) in major surgeries. Skin clips also can be used. Subcuticular absorbable 3 zero vicryl or monocryl or PDS sutures can be placed if there is sure about complete haemostasis. These sutures are not removed. Additional advantage of subcuticular suture over interrupted suture is doubtful. Often it causes troublesome induration and discomfort. Interrupted sutures are removed in 5-7 days.

Surgery of larynx and laryngectomy are beyond the scope of this book as it s a specialised subject as such. But basic anatomy of larynx and principles should be remembered by general surgeon **(Fig. 14-7)**. Incision used for laryngectomy, *Gluck Sorenson's incision* is shown in **Figure 14-8**. Different surgeries are done for laryngeal



Fig. 14-6: Position, cleaning and draping of the neck for neck surgery.

cancers – partial or total. Neck node dissection also should be done. Permanent tracheostomy is needed. In case of pharyngeal involvement laryngopharyngectomy with tracheostomy, gastric pull up as pharyngooesophageal substitute. Speech therapy, tracheostomy care, prevention of respiratory infection are essential post operative care needed in these patients.

HEAD AND NECK TRAUMA

It can be open trauma or a closed one. Open trauma is usually penetrating. It can be from knife, sickle, and bullet injuries. Injury can occur to major vessels, trachea, oesophagus, soft tissues, thyroid, nerves, cervical and brachial plexus. External wound/stab may be small but deeper injury may be extensive.


Epiglottis
Hyoid bone
Aryepiglottic fold
Thyrohyoid-membrane
Arytenoid cartilage
Thyroid cartilage
False vocal cord
True vocal cord
Trachea
Oesophagus

Fig. 14-7: Anatomy of the larynx.


Incision for block dissection
Laryngectomy incision

Fig. 14-8: Gluck Sorenson incision for laryngectomy.

Closed trauma may be to cervical spine, carotid artery leading to an intimal tear which may cause *carotid blowout* at a later period. Slowly expanding haematoma may be possible with blunt injury to neck. Only external bruising may be evident in such occasion. Unstable fracture of cervical spine may be present; spine should be protected mechanically in such suspected cases.

Injury to oral cavity, pharynx can cause bleeding into the airway causing life threatening airway block. Maintenance of the airway is a crucial need here.

Major vessel injury can cause torrential bleeding. Digital compression, early exploration and vessel repair is the treatment.

Management of Head and Neck Trauma

General condition should be assessed. Immediate resuscitation by inserting a central venous line, and an airway is done. Adequate blood should be arranged for transfusion. Other injuries in the body should be looked for – abdomen/thorax/head/limb fractures. Duplex US scan of neck is a good way of assessing the neck injuries. *Assessment* is done as 3 categories - vascular, tracheal, oesophageal injuries.

Airway is maintained by endotracheal intubation or tracheostomy or cricothyroidotomy as an emergency procedure.

Bleeding is controlled by pressure, packing, early exploration, ligation of external jugular vein, IJV, ligation of small vessels. Torrential bleeding in face, and proximal neck can be controlled by ligating the external carotid artery distal to origin of superior thyroid artery. ECA has got branches whereas ICA does not have branches in the neck. Wounds in lower neck zone (zone 1) may be associated with injury to mediastinal major vessels and so exploration of mediastinum with *median sternotomy* is needed. Angiography should be done for all zone 1 penetrating injury. CT chest and neck is also often desirable if patient is stable. Penetrating injuries in zone 3 may include injury to ICA extending onto the intracranial cavity. Neurosurgical approach may be needed in such injury. Lateral injury in zone 2 causes carotid injuries which require wound exploration. Wound should be explored with an adequate lengthy incision. All haematomas are gently evacuated. Suction should be used to identify the bleeding point. Vascular clamps should be used if carotid injury is present. Intraluminal stent is better to maintain the brain circulation until repair is over. Small tear in the carotid is sutured using continuous polypropylene 3 or 4 zero suture material. Occasionally venous patch or graft is required. Intimal injury of carotid is observed for formation of pseudoaneurysm, haematoma, late rupture, thrombosis and blockage. Follow up duplex US scan is essential at repeated sittings. If such significant findings are found, exploration and vascular reconstruction is done **(Fig. 14-9)**.

Laryngeal injury is identified by CT neck. Hyoid fracture is treated conservatively. Injury to thyroid cartilage may require repair using wires or plates with a covering tracheostomy. *Tracheal injury* in proximal part is repaired using interrupted polypropylene or vicryl sutures. Tracheostomy is often needed. Tracheal injury in lower neck needs median sternotomy ,mediastinal exploration and tracheal suturing.

Small *oesophageal injury* is managed by placing nasogastric tube for 2-3 weeks. Large injury needs proper exploration of posterior neck, suturing of the oesophagus. A feeding gastrostomy with or without diversion oesophagostomy in neck which can be corrected at later period once patient's condition stabilizes is the other option.

Nerve injuries are corrected electively at a later period by nerve suturing using microscope by skilled meticulous method.

Complications of Neck Injury

Airway block, bleeding, haematoma, infection, retro or parapharyngeal haemato ma or abscess formation.

RETROPHARYNGEAL ABSCESS

Surgical Anatomy

The wall of the pharynx has got 5 layers. Mucosa, submucosa, pharyngobasilar fascia, muscular layer (contains 3 constrictors and stylo, salpingo, palatopharyngeus muscles) and buccopharyngeal fascia covers outer part of constrictors and extends over buccinator. Buccopharyngeal fascia is adherent to prevertebral fascia posteriorly in the midline. Retropharyngeal lymph nodes are located between buccopharyngeal fascia and prevertebral fascia in paramedian (eccentric) position (not midline). Retropharyngeal space is situated between pharynx and posterior layer of deep fascia, extending from base of the skull to the level of tracheal bifurcation in the posterior mediastinum. Abscess in this plane can be acute or chronic **(Fig. 14-10)**.

Acute is seen in children; abscess lies on either side of the midline. It is due to bacterial infection like staphylococci or streptococci. It is drained under general anaesthesia (with intubation) through oral cavity.



Fig. 14-9: Incisions used in head and neck trauma.


1
2
3
4
5
6
Normal anatomy
Acute abscess
Acute retropharyngeal abscess
Chronic abscess
Chronic retropharyngeal abscess
1. Pharyngeal wall 2. Buccopharyngeal fascia 3. Retropharyngeal lymph node 4. Prevertebral fascia 5. Median septum 6. Vertebra

Fig. 14-10: Note acute and chronic retropharyngeal abscess. Normal anatomy is also shown. Acute is eccentric and is due to suppuration of retropharyngeal lymph nodes. Chronic is central, midline and is due to tuberculosis of the cervical vertebra.

Chronic retropharyngeal abscess is usually due to tuberculosis of the cervical spine which is in the midline; confirmed by CT scan; it is drained through neck incision under general anaesthesia. Horizontal incision is made 2 cm below the angle of the jaw. Sternomastoid muscle is separated from tail of the parotid and is retracted behind. Carotid sheath is identified and retracted behind. Superior constrictor is identified; finger is passed behind the muscle to reach retropharyngeal space; pus is drained and collected for culture and AFB staining. Antituberculous drugs are started.

PARAPHARYNGEAL ABSCESS

Parapharyngeal space is cone-shaped space with its base at base of skull and apex at greater cornu of hyoid bone. Medial wall is formed by superior constrictor; lateral wall by lateral pterygoid, angle of mandible and parotid gland; posteriorly by carotid sheath, below by submandibular salivary gland. Abscess in this region usually is spread from tonsils, infected lower 3rd molar tooth. Thrombosis of internal jugular vein, erosion of ICA and bleeding, and septicemia are the possible complications **(Fig. 14-11)**.

It is drained under general anaesthesia with neck extended and turned to opposite side. Horizontal incision is made over the anterior margin of the sternomastoid muscle 2 cm below the jaw. After retracting the muscle behind, deep fascia is opened to reach the abscess cavity. All loculi are broken using finger. After thorough warm saline irrigation drain is placed and dressing is done. Wound is not closed usually but allowed to heal spontaneously. Often secondary suturing may be required. Causative pathology should be addressed.

TREATMENT OF LUDWIG'S ANGINA

It is an inflammatory oedema of submandibular region and floor of the mouth causing diffuse swelling and brawny oedema of the submandibular region usually due to dental or oral infection. It presents with toxicity, trismus, brawny swelling in upper neck, dysphagia and dyspnoea, putrid halitosis and fever.



Fig. 14-11: Drainage of parapharyngeal abscess through neck incision.



Fig. 14-12: Incision for Ludwig's angina drainage.

It should be drained by making a *transverse skin incision* in submental region; incision is deepened through deep fascia and mylohyoid muscle is cut *vertically*. Wound is left open and delayed suturing is done. Often it is difficult to intubate the patient for anaesthesia due to trismus, and tracheostomy may be needed **(Fig. 14-12)**.

TREATMENT OF TUBERCULOUS LYMPHADENITIS AND COLD ABSCESS IN THE NECK

In cold abscess, initial *aspiration* is done through a wide bore needle in a nondependent site using 'Z'/zigzag track (to prevent sinus formation). If aspiration is not effective then *drainage* is done through a nondependent incision; all caseating material is removed; wound is closed without a drain. *Surgical removal of tuberculous lymphadenitis* is indicated whenever patient is not responding to drugs and in persistence of sinus. It is done by elevating skin flaps and removing all diseased lymph nodes. Due to chronic inflammation adhesions are common. Injury to IJV, nerves can occur. In a *chronic long standing tuberculous sinus*, treatment is surgical excision of the entire track through an elliptical incision. It is done under general anaesthesia **(Figs 14-13 and 14-14)**.



Fig. 14-13: Tuberculous cold abscess and its aspiration.



Fig. 14-14: Excision of tuberculous sinus in the neck.

EXCISION OF THE BRANCHIAL CYST AND FISTULA

Branchial Cyst

It is due to remnants of second branchial cleft. Cholesterol crystals are typical. Branchial cyst is situated in the anterior border of the upper third of the sternomastoid muscle. It is seen in adolescent period **(Figs 14-15 and 14-16)**.

Excision of cyst is done under general anaesthesia. Neck is slightly extended and head turned towards opposite side. After cleaning and draping, horizontal incision is made 2 cm below the mandible; deepened across skin and platysma without elevating the flap to avoid injury to marginal mandibular nerve. Adjacent to anterior margin of the sternomastoid muscle deep fascia is incised carefully to reach the cyst. Cyst is dissected gently and carefully. Often extension of the track between ICA and ECA towards tonsillar fossa will be found which should be dissected carefully using fine scissor and bipolar cautery. Such extended track should be entirely removed. Incomplete removal will lead into fistula formation **(Fig. 14-17)**.



Fig. 14-15: Anatomical location of branchial cyst and fistula.



Fig. 14-16: Branchial cyst.

Branchial Fistula

It is usually congenital; its external opening is adjacent to lower third of anterior border of the sternocleidomastoid muscle. Its internal orifice is near posterior pillar of the tonsil. Fistulogram / CT fistulogram and discharge study are the needed investigations. Often it is bilateral **(Fig. 14-18)**.

Stepladder excision - It is excised under general anaesthesia. Position is similar to branchial cyst. An elliptical horizontal incision is placed in the lower neck which includes the external orifice of the fistula. Often methylene blue dye is injected through the external orifice to identify the track during dissection. Track is dissected carefully upwards. Another horizontal incision is made 2 cm below the lower margin of the mandible. Further dissection of the track is done through upper incision. Entire track is dissected up to internal opening at posterior pillar of the tonsil. During dissection, carotids, IJV, hypoglossal, accessory and glossopharyngeal nerves should be taken care of. After excision of the track skin incisions are sutured. Often suction drain may be used. Bilateral fistula can be operated in the same sitting.

Complications are bleeding, incomplete excision of the track injury to nerves **(Figs 14-19 and 14-20)**.

PHARYNGEAL POUCH

Progressive symptoms, respiratory distress and dysphagia are definitive indications for surgery **(Fig. 14-21)**.

Procedure

Under general anaesthesia endoscope is passed to identify the opening of the pouch. Pouch is packed with acriflavine soaked gauze for identification. Nasogastric tube is passed into the oesophagus under visualisation. Pouch is approached through neck incision for proper removal. As pouch is usually left sided, left sided lower third horizontal incision is made. Gauze filled pouch sac is felt which is dissected with sharp and finger dissection. Opening of the pouch is located usually behind/on posterior aspect of the oesophagus. Entire pouch is dissected to visualise fundus, neck and junction. Neck is partially opened to identify the nasogastric tube. Traction over the pouch sac stretches the cricopharyngeus. Vertical posterior midline 4 cm myotomy is done to this muscle. Both recurrent laryngeal nerves which are on lateral walls are safeguarded. Sac/pouch at the neck are divided and pouch is removed. Defect in the posterior oesophagus is closed using 2 zero vicryl or silk interrupted sutures. Wound is closed with a drain.

In *Dohlman's operation* pharyngeal pouch is excised endoscopically.

Postoperatively nasogastric tube left in place for 7–10 days. Nasogastric feeding can be started early. Drain is removed in 5–7 days.

Problems and Complications

Often there will be dense adhesions between pouch wall and adjacent structures due to recurrent infection and inflammation which makes dissection difficult. Injury to surrounding structures can occur.

Infection, mediastinitis, pneumonia, lung abscess can occur as often fundus of the pouch may be in the mediastinum. Abscess neck itself can occur postoperatively. Pharyngeal fistula may develop whenever there is sepsis and dense adhesions. Stenosis of oesophagus leading into recurrence is known to occur.



Fig. 14-17: Excision of branchial cyst.

SURGICAL TREATMENT OF CYSTIC HYGROMA

Excision is done under general anaesthesia with extended neck, head turned towards opposite side. Transverse skin incision in the supraclavicular region of adequate length is made. Subplatysmal plane is reached. Circumferential meticulous dissection with slow gradual mobilisation of cyst is done. Cyst does not occupy the natural planes; but encroaches vital neurovascular structures. Often it extends into mediastinum also. After complete excision, drain is placed, antibiotics are given. Higher lesion may extend to parotid region often causing risk of facial nerve injury. In spite of proper dissection there is high recurrence rate (20–30%) due to incomplete excision, inability to identify the entire lesion during excision. Aspiration of the cyst and injecting sclerosant OK – 432 (*picibanil*) will cause pronounced inflammation and fibrosis which facilitates complete excision at a later period.

Staged surgery / repeated surgery / adding superficial parotidectomy are additional things needed to achieve complete cure.


IJV
ICA
Dissected branchial fistula
ECA
Hypoglossal nerve
CCA

Fig. 14-18: Branchial fistula – photo and diagram.



Fig. 14-19: Branchial fistula surgery in a child/boy.



Figs 14-20(1)



Figs 14-20(2)

Figs 14-20(1 and 2): Branchial fistula surgery in an adult.



Fig. 14-21: Anatomy of pharyngeal pouch.

TONGUE TIE

It is short, thick fibrous frenum linguae. Tip and lateral margins of the tongue during protrusion will be everted with dorsal mid part heaping. It causes difficulty in speech and cleaning the inner part of the lower teeth. It is treated surgically either under local or general (in child) anaesthesia. Stay suture is placed at the tip of tongue to lift it upwards. Fibrous frenum is divided using fine scissor. Linear wound is either left alone or closed longitudinally using fine 4 zero catgut continuous sutures from the tip of the wound towards the margin of the floor of the mouth **(Fig. 14-22)**.

SURGICAL MANAGEMENT OF CERVICAL RIB (THORACIC OUTLET SYNDROME/TOS)

It is done in case of thoracic outlet syndrome (TOS) which is due to cervical rib. Rib compresses the neurovascular bundle causing neurological and vascular manifestations. Arterial TOS is mainly caused by cervical rib or rudimentary first rib. Venous TOS is due to costoclavicular ligament and subclavius muscle compressing subclavian vein. Neurogenic TOS is caused by congenital anatomical factors like cervical rib, long C_7 transverse process, anomalous first rib, anomalous insertion of scalene muscles, split scalenus anterior,



Fig. 14-22: Tongue tie and its release.

scalenus muscle hypertrophy, presence of scalenus intimus muscle (is seen 55% of individuals), abnormal bands and ligaments, brachial plexus anomalies, sagging shoulder; neck trauma (clavicle, callus, first rib, scalene muscles, old scars); soft tissue tumours.

Surgical Anatomy

Scalene triangle is between scalenus anterior, medius and first rib contains brachial plexus and subclavian artery. *Costoclavicular space* contains artery, vein and nerve **(Fig. 14-23)**.

Evaluation

TOS is evaluated by X-ray neck and chest along with X-ray cervical spine; Doppler study, nerve conduction studies, electromyography, CT angiogram, CT neck. Normal nerve conduction velocity is 85 m/second.



Fig. 14-23: Surgical anatomy of cervical rib.

Conservative Treatment

Initially it is managed conservatively with exercises like—neck stretching, breathing and postural exercises, analgesics, muscle relaxants, antidepressants. Conservative approach is used if nerve conduction velocity is more than 60 m/second.

Surgery

Surgical intervention is required when symptom persists and vascular features are severe with ischaemia of the fingers. Removal of cervical rib and middle portion of first rib with scalenotomy relieves the symptoms. If nerve conduction velocity is less than 60 m/second surgery is indicated.

Approaches

Transaxillary, supraclavicular; combined; supraclavicular and infraclavicular for arterial reconstruction; posterior high thoracoplasty approach for recurrent TOS.

Transaxillary Approach

Roos (1966) popularised this approach. It is mainly used to excise the first rib. Release of lower brachial plexus and vascular compression is done better through this approach. After giving general anaesthesia patient is positioned laterally with arm abducted. Transverse skin incision is made on the 3rd rib level. Axillary tunnel is developed by blunt dissection to reach the first rib and scalenus anterior **(Fig. 14-24)**.

Intercostobrachial nerve is cut. Subclavian vessels and brachial plexus are safeguarded. Vessels are separated by gentle dissection to expose the insertion of the scalenus anterior. Muscle is divided at its attachment. 1–2 cm length of the muscle should be excised to prevent development of fibrosis and recurrence of symptoms. Scalenus medius and intercostal muscles are pushed off the first rib. Subclavius muscle tendon can also be released. C_8 and T_1 nerve roots are identified before dividing posterior part of the first rib behind these nerves. Neurolysis of C_7, C_8 and T_1 is done with fine specialised instruments. Often resection of the costoclavicular ligament is needed.

Supraclavicular Approach

It is used for excision of cervical rib or upper brachial plexus decompression wherein extensive scalenotomy is needed or if there



Fig. 14-24: Incision for cervical rib excision through transaxillary approach.

is a need of arterial (subclavian) reconstruction. It is done under general anaesthesia. Patient is positioned supine with head end of the table elevated by 15º to reduce venous congestion and head is tilted to opposite side; arms are placed on the sides of the patient. Incision is placed a fingerbreadth (1.5 cm) above the clavicle from anterior border of the sternocleidomastoid muscle extending laterally for 7-8 cm. It is usual but not mandatory practice to pull/drag the skin downwards below the clavicle and make incision on the clavicle from medial to lateral; and when pulled skin is released after making incision, incision will be in supraclavicular area. It is said to prevent inadvertent injury to deeper structures. Incision is deepened; Platysma is incised **(Fig. 14-25)**.

External jugular vein is divided with ligatures. Supraclavicular nerves are retained. Exposed sternocleidomastoid muscle is identified for its full width. The clavicular head is divided using scissor/cautery/ or by piecemeal using fine forceps (used in olden days). IJV behind the muscle should not be injured. Scalene pad of fat is dissected. Inferior belly of omohyoid muscle is divided. IJV is mobilised and retracted medially. Bipolar cautery dissection is done in front of the scalene muscle. Phrenic nerve is identified in front of the scalenus anterior muscle deep to deep fascia running vertically downwards from lateral to medial side. Phrenic nerve is retracted medially (should not be retracted laterally as it may cause traction injury to upper trunk of brachial plexus). Dissected scalenus anterior muscle is cut layer by layer carefully using scissor/by piecemeal method to protect subclavian artery underneath. Medial part of the brachial plexus is dissected carefully. Subclavian artery is dissected on its summit and pushed downwards. Scalenus medius is also excised. Cervical (accessory) rib is cleared of scalenus medius with its tendinous attachments to it and first rib. T_1 nerve root is identified carefully to avoid injury. Cervical rib is divided posteriorly in level with its transverse process. Central portion of the 1st rib is also excised. Wound is closed with a suction drain **(Fig. 14-26)**.

Posterior High Thoracoplasty

Vertical high paraspinal incision is made at the level of C_7 to T_4 between medial margin of the scapula and spinous process. Through muscle splitting approach, accessory (cervical) rib and first ribs are identified and resected. Neurolysis of C_7, C_8 and T_1 is done. If needed posterior dorsal sympathectomy is also added **(Fig. 14-27)**.



Fig. 14-25: Incision for cervical rib excision through supraclavicular approach.

Complications

- Haemorrhage—due to venous or arterial injury.
- Pain in the wound mainly in transaxillary approach.
- Pleural injury if occurs, ICT should be placed.
- Injury to nerve roots brachial plexus.
- Fibrosis can cause recurrence of symptoms.

CAROTID BODY TUMOUR

It was first described by *Von Haller* in 1743. *Riegner* in 1880 described the first surgical removal of carotid body tumor. Carotid body is *3–5 mm* in diameter size, reddish brown or tan coloured body found in the adventitia of the common carotid artery at its posteromedial wall at bifurcation with a feeding vessel through *Meyer's ligament*. Its size may be larger in individuals in high altitude. It gets its afferent nerve supply from glossopharyngeal nerve. Cells – *Type I – chief cells* store and release catecholamines; *Type II – sustentacular cells*. Carotid body has got autonomic control over cardiovascular and respiratory systems. Hypoxia, hypercapnia, low pH stimulates chief cells to begin autonomic reflex. It gets stimulated also by raise in body temperature, cyanide and nicotine.

Carotid body tumour is usually 4-6 cm in size, behind the bifurcation of the CCA splaying it and extending along the ICA as it enlarges towards skull base. Its incidence is < 0.5% of all neoplasms. It is common in females and in high altitudes. *Presentations* are—neck mass (75%) which shows *transmitted pulsation* and headache, neck pain, dizziness, tinnitus, hoarseness, dysphagia, syncope. It moves sideward but not longitudinally. Thrill and bruit (25%) may be present. Aneurysmal dilatation of the carotids is *not common*. 90% of them are benign; 10% malignant type, spreads to regional nodes, lungs, liver, kidneys, pancreas, thyroid, heart. *Shamblin classification*—Type I – Localised, resectable easily (25%); Type II – Adherent, resectable with difficulty (45%); Type III – Adherent and surrounds the carotids, difficult resection and needs bypass during procedure and carotid to ICA interposition vein graft. It is diagnosed by angiogram which shows widening of the carotid bifurcation with tumour blush—*Lyre sign*. CT/ MR angiogram is useful. FNAC/biopsy are contraindicated **(Fig. 14-28)**.

Surgical Treatment

Excision is done under general anaesthesia. *Nasotracheal intubation* is ideal to facilitate better retraction beneath the mandible. Often CCA with bifurcation and carotid body tumour area is divided into 3 zones – lower, at the level of CCA bifurcation as zone I; upper front, towards ECA as zone II; upper behind towards ICA as zone III. Vagus, hypoglossal nerve, sympathetic chain will be very close during dissection and should be taken care of.

Whenever high exposure of the carotid is needed, ipsilateral mandible should be subluxated. Thigh and leg should be prepared for harvesting long saphenous vein if interposition vein graft is needed. Carotid shunts should be kept ready if temporary bypass is needed. ECA is usually ligated above the origin of the superior thyroid artery.

In small tumour less than 4 cm, incision is along the anterior margin of the sternocleidomastoid muscle; in large tumour 'T' incision is preferred to have adequate exposure **(Figs 14-29 and 14-30)**.


Scalenus anterior
Phrenic nerve
Scalenus anterior
Scalenus anterior-cut
Subclavian artery

Fig. 14-26: Cervical rib excision through supraclavicular approach.



Fig. 14-27: Incision for cervical rib excision through posterior high thoracoplasty approach.


ICA
Carotid body tumour
Splaying of carotid
CCA
ECA

Fig. 14-28: Location of the carotid body tumour.



Fig. 14-29: Incision for excision of carotid body tumour.



Fig. 14-30: Relations of carotid body tumour.

CCA, ECA, ICA with tumour is dissected and isolated carefully and meticulously with proper haemostasis. Bipolar cautery should be used. Loops/slings are passed around CCA proximally and ECA and ICA distally. Hypoglossal nerve is identified and separated and held using a fine sling gently. *Subadventitial plane* is created to dissect the tumour carefully from the carotid bifurcation from below upwards. All vessels entering the tumour should be individually secured and ligated. Vagus is identified at this stage which is dissected and isolated and held with a sling. ICA should be preserved with care. If injured, it should be repaired. In case of tumour encasement, temporary shunt from CCA below to ICA above is achieved to maintain the cerebral perfusion. Segment of the bifurcation with ICA and ECA with tumour is removed en mass. ECA is doubly ligated using silk above. Great saphenous vein is harvested from the thigh and is interposed as vein graft between CCA below and ICA above.

Complications

- Injury to vagus and hypoglossal nerves – 40%.
- Vascular injuries.
- Stroke due to compromised cerebral perfusion (3%).

BIOPSY IN HEAD AND NECK DISEASES

Biopsy in head and neck diseases needs a comprehensive approach as many lesions are easily amenable but many are in deeper places and often not visible.

Lesions which are easily accessible are biopsied with open incision biopsy. Usually more than two biopsies from the edge are taken. Often biopsy site may require suturing using 3 zero vicryl to control bleeding. Cautery is avoided or used only when essential as much as possible (especially in suspected melanoma lesions) to prevent tissue getting desiccated. Suction should always be used during biopsy. Posterior lesions should be biopsied under general anaesthesia with endotracheal intubation.

Nasopharyngoscopy, laryngoscopy, oesophagoscopy are needed to take biopsy from these sites.

CT guided biopsy is done in base skull tumours or deep seated primaries.

Blind biopsy of different suspected areas in the fossa of Rosenmuller, pyriform fossa, lateral wall of pharynx is done in a clinically unknown primary but confirmed secondaries in neck by FNAC.

Maxillary tumour biopsy is done using Caldwell–Luc operation.

Secondaries in neck node are usually confirmed *not by* open biopsy but *by FNAC*. Fungating secondaries can be biopsied by open method **(Fig. 14-31)**.

CERVICAL LYMPH NODE BIOPSY

Indications

Cervical lymph node biopsy is done mainly in patients with suspected lymphoma. Lymph node biopsy is done in patients where FNAC is inconclusive like in tuberculosis, rare lymph node diseases, and chronic inflammation. Staging, grading and histochemistry are needed in lymphoma and so biopsy is mandatory.

Lymph node secondaries are usually not an indication for open biopsy especially in squamous cell carcinoma. Diagnosis is usually done by FNAC. Open biopsy may aggravate the spread to further lymph nodes altering the prognosis and survival. Malignant supraclavicular



Fig. 14-31: Incision for Caldwell-Luc operation which is used for taking biopsy from maxillary tumour. Incision is not used for definitive therapy for carcinoma maxilla. Incision also used in benign conditions to approach maxillary sinus. Gingivobuccal mucosa is incised and mucoperiosteum is raised. Bone of canine fossa is cut to reach the maxillary antrum.

lymph nodes are considered as advanced with primary in breast/chest/abdomen. So excision biopsies of these lymph nodes are acceptable as it will not alter the prognosis.

Principles

All nodes in deep cervical and supraclavicular region should be biopsied under general anaesthesia. Biopsy of occipital and posterior triangle nodes can be done under local anaesthesia as these nodes are superficial and not much vital structures are present in this region. However accessory nerve is under risk in this location and should be taken care of while doing excision. Skin incision should be marked prior to injecting local anaesthesia, otherwise node may get masked making it difficult to identify it during surgery. Xylocaine 1% with adrenaline can be used **(Fig. 14-32)**.

Procedure

Position is supine with head turned towards opposite side. After cleaning and draping, an adequate transverse incision is made. Skin and platysma are incised. Sternomastoid is retracted. Deep fascia is incised. Lymph node is held gently using nontoothed forceps. Lymph node is dissected all around. Bipolar cautery may be used to control small bleeders. Earlier surgeons used to cut the node into half to take imprint cytology. Nowadays it is not done. Large adequate '*wedge excision'* of the lymph node is done if lymph node is large, if there are adhesions, if nodes are matted, if node is in close proximity to a vital structure. After removal haemostasis is maintained. Wound is closed in layers. Skin is closed using interrupted nonabsorbable or subcuticular absorbable sutures **(Fig. 14-33)**.

Complications

Haemorrhage and haematoma formation can occur which often needs reexploration and controlling of the bleeder. Injury to adjacent nerves can occur. Infection and sinus formation are other complications.

RADICAL NECK DISSECTION (RND)

It is removal of all neck nodes with fat, fascia, internal jugular vein, sternomastoid muscle, spinal accessory nerve, submandibular salivary gland and lower pole of parotid gland with dissection in front of the prevertebral fascia leaving behind structures deep to prevertebral fascia (brachial plexus, cervical nerves, prevertebral muscles); pretracheal fascia; carotid artery; vagus nerve and strap muscles. It is an important oncological clearance surgery in the neck. For operable mobile metastatic neck nodes neck dissection is ideal method. Radiotherapy is not a prime approach whatever the type of primary.

Principles

Primary should be treated independently by wide local surgical excision or curative radiotherapy depending on the site of the primary.



Fig. 14-32: Technique of lymph node biopsy.



Fig. 14-33: Neck lymph node biopsy. Spinal accessory nerve should be kept intact during nodal biopsy. Biopsy is done under general anaesthesia.

RND or MRND is the choice for all confirmed positive nodes in all oral malignancies.

Supraomohyoid neck dissection (SOHND) is done for oral squamous cell carcinoma with clinically negative nodes. On table frozen section biopsy is needed. If nodes become positive, then MRND I is carried out immediately.

Extended supraomohyoid neck dissection is done when primary is in lateral border of the tongue which also includes level IV, as lateral margin of tongue cancer can cause skip metastasis in the level IV lymph node.

Anterolateral neck dissection is done for laryngeal and pharyngeal cancers (in clinically node negative disease) with level II, III, IV dissection; if primary is in midline, it is done bilaterally.

Posterolateral neck dissection is done for primary cutaneous malignancies of the scalp (posterior aspect) like melanoma or SCC.

In thyroid malignancy, total thyroidectomy (MRND type III/ selective neck dissection) with bilateral and central node clearance is done.

Indications

Secondaries in the neck which are mobile (not fixed); common site of primary in head and neck malignancies, thyroid malignancy, malignancy of skin in head and neck region, malignant parotid tumours, etc. Secondaries in the neck with occult primary is initially treated with radical neck dissection; regular follow up is done later, until primary gets revealed; and once primary reveals it is managed accordingly depending on location. Here one cannot wait for primary to reveal as by then metastatic nodes become advanced and inoperable resulting in poor prognosis.

Table 14-1: Nodal staging in secondaries in neck

Nodal stage in secondaries in neck nodes	*Involvement of nodes in different stages*
N_x	Assessment of regional nodes not possible
N_0	Regional nodes not involved by spread
N_1	Spread to single same side < 3 cm sized node
N_{2a}	Spread to single same side 3-6 cm sized node
N_{2b}	Spread to multiple same side nodes each < 6 cm in size
N_{2c}	Spread to bilateral/opposite side nodes each < 6 cm in size
N_3	Spread to any node with size > 6 cm

Contraindications for Radical Neck Dissection

Fixity of metastatic nodes, distant spread and advanced uncontrollable primary disease are the contraindications **(Fig. 14-34)**.

Levels in Neck Nodes

(Memorial Sloan –Kettering Cancer Center leveling of neck nodes) **(Figs 14-35 to 14-37)**.

Structures removed in classical RND –
- All neck nodes
- Fat, fascia
- Internal jugular vein
- Sternomastoid muscle
- Spinal accessory nerve
- Submandibular salivary gland
- Lower pole of parotid gland.

Plane of dissection
- Anteriorly deep to platysma
- Posteriorly with dissection from the prevertebral fascia leaving behind prevertebral fascia and structures deep to it (brachial plexus, cervical nerves, prevertebral muscles), pretracheal fascia, carotid artery, vagus nerve, and strap muscles.

Table 14-2: Types of neck dissection

Type of neck dissection	*Nodes removed*	*Structures preserved*
Comprehensive –		
Radical neck dissection (RND)	Level I-V	None
MRND type I	Level I-V	Spinal accessory nerve
MRND type II	Level I-V	Spinal accessory nerve; sternomastoid muscle
MRND type III	Level I-V	Spinal accessory nerve; sternomastoid muscle; IJV
Bilateral RND	Level I-V (both sides)	
Selective node dissection –		
Supraomohyoid neck dissection (N_0)	Level I-III	Spinal accessory nerve; sternomastoid muscle; IJV
Extended supraomohyoid dissection (N_0)	Level I-IV	Spinal accessory nerve; sternomastoid muscle; IJV
Anterolateral neck dissection ($N_{0)}$	Level II-IV	Spinal accessory nerve; sternomastoid muscle; IJV
Posterolateral neck dissection (N_0)	Level II-V with suboccipital, retroauricular nodes	Spinal accessory nerve; sternomastoid muscle; IJV
Anterior/central dissection	Level VI	Spinal accessory nerve; sternomastoid muscle; IJV

Level I – Submandibular lymph nodes and submental lymph nodes – from lower border of mandible to hyoid bone and posterior belly of digastric muscle.

Level II - Lymph nodes in upper deep cervical region. (It extends from base of skull to hyoid bone and from lateral margin of sternohyoid muscle to posterior margin of sternomastoid muscle).

Level III - Lymph nodes in middle cervical region (from hyoid bone to cricothyroid membrane).

Level IV - Lymph nodes in lower cervical region (from cricothyroid membrane to clavicle).

Level V - Lymph nodes in posterior triangle including supraclavicular region.

Level VI - Lymph nodes in the midline neck—pretracheal and prelaryngeal – from hyoid bone above to suprasternal notch below; laterally medial border of carotid sheath on both sides.

Level VII - Lymph nodes in the mediastinum; from suprasternal notch to inferior mammary artery.



Fig. 14-34: Surgical field after completion of neck node dissection with preservation of the IJV. Carotid artery, digastric muscle, lower margin of the mandible is visualised.



Fig. 14-35: Surgical (oncological) levels of neck lymph nodes.

Note: Level II and V are now subdivided into Level IIa / Level IIb and Level Va / Level Vb; depending whether these nodes are above the level (Level IIb / Level Va) of the spinal accessory nerve or below (Level IIa / Level Vb).

Preparation

General assessment like anemia and nutritional status is done. Cardiac and respiratory assessment; improvement of intraoral hygiene by mouth wash using povidone iodine or hydrogen peroxide is done. When primary is in larynx/pharynx, tracheostomy may be needed. It is done usually on table just prior to surgery. Shaving of the chest,


Preauricular
Submental
Submandibular
Mid deep cervical
Sternomastoid
Lower deep cervical
Supraclavicular

Fig. 14-36: Different lymph nodes in the neck.

	N0 — Regional nodes involved
	N1 — Spread to single same side < 3 cm sized node
	N2a — Spread to single same side 3-6 cm sized node
	N2b — Spread to multiple same side nodes each < 6 cm in size
	N2c — Spread to bilateral/ opposite side nodes each < 6 cm in size
	N3 — Spread to any node with size > 6 cm

Fig. 14-37: Staging of neck lymph nodes in secondaries.

neck and face is done on the day of surgery. If there is need for reconstruction of the wide area of excision of the primary area like cheek, it also should be planned and area should be prepared.

Anaesthesia

General anaesthesia is used with endotracheal intubation. Tracheostomy may be needed depending on the site of primary which is being operated. Some prefer hypotensive anaesthesia. But even though surgical field is clean, postoperative bleeding and haematoma due to eventual bleeding from small vessels, which was not cauterised at the time of surgery, is known to occur.

Position of the Patient

Patient is placed in supine position with hyperextended neck turned to opposite side with sandbags under the shoulder. Head end is elevated to 15° to reduce venous bleeding during surgery. Hands are tucked under the buttock. There should be adequate space near head end to allow assistants and scrub nurse to work on. Anaesthetist and Boyle's apparatus should be on opposite side of the dissecting area.

Incision

Many incisions are used. Modified triradiate incision is commonly used. Mac Fee incision is also used. Selection of incision is of individual surgeon's choice. Centre of the lateral aspect of the neck is the least vascular area for skin flap. One should avoid making incision in this part of the skin **(Figs 14-38 and 14-39)**.

Technique

Flaps are elevated (*subplatysmal*). Posterior flap, anterior, upper and lower flaps are elevated in subplatysmal plane. Flaps are raised


1
2
2
3
4
1. Schobinger
2. Conley/Schechter
3. Hockey stick
4. Hayes Martin
(two break down point—
good exposure)
7
5
7
6
5
5. Triradiate
6. Apron incision
7. Fischel T-J/Circles
'T' incision/Blair brown 'z'

Fig. 14-38: Different incisions used in radical neck dissection.


Triradiate incision
Upper incision
Lower incision
2 cm
Mac Fee approach (incision)

Fig. 14-39: Mac Fee and trifurcate incisions used for radical neck dissection.


Brachial plexus
Upper trunk
Middle trunk
Lower trunk
Nerve to subclavius
Transverse cervical artery
Supraclavicular artery and nerve

Fig. 14-40: Structures in supraclavicular triangle.


Great auricular nerve
Erb's point in neck
Anterior cutaneous nerve
Omohyoid (superior belly)
Sternocleidomastoid
Tendinous sternal head
Muscular clavicular head
Supraclavicular nerves
Lesser occipital nerve
Greater occipital nerve
Trapezius
Spinal accessory nerve
Omohyoid (inferior belly)
Acromion
Clavicle

Fig. 14-41: Nerves in relation to posterior triangle which come across during neck dissection.

by holding skin hooks. Fine scissor/cautery are used. Trapezius is exposed fully on posteriorl aspect. While elevating superior flap care should be taken not to injure the marginal mandibular nerve which lies parallel to lower border of the mandible. This nerve crosses the anterior facial vein and vein is ligated. Inferior flap is elevated up to the clavicle. All elevated flaps are retracted or sutured to the drape margin temporarily **(Fig. 14-40)**.

Sternocleidomastoid muscle is cut at its attachments to clavicle (muscular) and sternum (tendinous). Care should be taken not to injure the IJV in the deeper plane. Layer by layer cutting of the muscle is usually practiced. External jugular vein and supraclavicular nerves are divided. Anterior border of the trapezius muscle is dissected to identify the spinal accessory nerve at its lower end. Nerve is traced by careful dissection above towards posterior border of the sternomastoid muscle which is 1 cm above the *Erb's point* or 5 cm below the inferior lobule of the ear. *Erb's point* is located 6 cm below the ear lobule where cutaneous branches (lesser occipital, great auricular, anterior cutaneous and supraclavicular little below) of cervical plexus comes out from posterior border of the sternomastoid muscle. Nerve is dissected upwards through the sternomastoid muscle by cutting the muscle fibres, along the lateral margin of the IJV, behind the posterior belly of the digastric muscle up to a point where it comes out of the skull to skull base through jugular foramen **(Fig. 14-41)**.

Upper attachment of the sternomastoid from mastoid process is detached. It is cut at a line extending from tip of mastoid to angle of jaw. Facial nerve may be existing at higher level in deeper plane. Fibrofatty tissue is dissected off from lateral to medial from splenius capitis, levator scapulae which is passed under the spinal accessory nerve; then dissected off from posterior scalene muscle. Inferior belly of omohyoid muscle is cut from its attachment to upper border of the scapula. Transverse cervical vessels are ligated and divided. Tissues are reflected off from middle and anterior scalene muscles to expose brachial plexus between these two muscles. Phrenic nerve is seen running lateral to medial from above downwards on the anterior surface of the scalenus anterior muscle. Cutaneous cervical nerves are cut adjacent to sternomastoid muscle.

Sternomastoid muscle is dissected off in upward direction to reach carotid sheath. Lateral border of strap muscles are retracted medially to expose carotid sheath from medial side. Carotid sheath is opened to expose CCA, IJV and vagus nerve. IJV is clamped and divided. Ends are doubly ligated with transfixation using 2 zero silk or vicryl. Lymphatics lateral to IJV are ligated using silk and divided. Transverse cervical vessels at its proximal part are also ligated. On left side thoracic duct if encountered is ligated safely to prevent chyle leak.

Fat, fascia, lymphatics with nodes, sternomastoid muscle, ligated IJV are dissected upwards from the carotid and vagus. Middle thyroid vein is identified, ligated and divided. Superior belly of omohyoid is identified, detached from hyoid bone. Superior thyroid vessels are dissected; only superior thyroid vein is ligated retaining the artery **(Fig. 14-42)**.

Upper flap is further elevated deeper to submandibular fascia (fascia in front of submandibular salivary gland) and posterior facial vein. Vein is ligated and retracted along with flap above. Flap is elevated along the lower border of the mandible. Fascia along the margin and angle is cleared. Facial lymph nodes are dissected. Facial artery and facial vein are ligated (at posterosuperior part of submandibular salivary gland). Anterior bellies of same and


Position of neck
Subplatysmal plane
IJV is ligated below
Sternomastoid muscle is cut

Figs 14.42(1)



Figs 14.42(2)

Figs 14-42(1 and 2): Steps in radical neck node dissection using Mac Fee incision approach.

opposite side digastric muscles are identified and exposed. Nodes in submental triangle are removed. Nodes with tissues dissected off the submental triangle towards the side to reach and identify mylohyoid neurovascular bundle which is ligated and divided. Gentle traction to submandibular salivary gland is applied using Allis tissue forceps to expose the lingual nerve, secretomotor fibres to submandibular ganglion, submandibular salivary duct. Secretomotor fibres are cut. Duct is cut and often ligated. Fascia over the hyoglossus muscle is kept intact to safeguard the hypoglossal nerve. Submandibular gland is further retracted laterally from posterior belly of the digastric muscle. Proximal part of the facial artery is identified at posteromedial part of the posterior belly of digastric muscle at deeper plane which is doubly ligated using silk and divided. Further retraction of the dissected tissue behind allows ligation of small pharyngeal veins and complete retraction of the posterior belly of digastric muscle. Occipital vessels (artery and vein) are ligated to visualise the upper end of the IJV. Transverse process of atlas can be felt at this level. IJV is dissected around and double ligation is done using 2 zero silk and divided. If upper attachment of sternomastoid muscle is not divided earlier, it is detached now to complete the surgery. Specimen is removed. After proper haemostasis and saline irrigation of the area suction drains are placed; one in front of trapezius and another along the strap muscle in front of carotid artery. Wound is closed using interrupted 3 zero polypropylene sutures.

Drains are kept for 4-7 days. Sutures are removed in 7-10 days **(Fig. 14-43)**.

Complications

Haemorrhage can occur due to small bleeders, carotid blow out in 7-14 days. Shock, haematoma formation, dyspnoea and compression are the features. Arranging adequate blood and immediate exploration is essential to save the life of the patient. Bleeders are ligated, carotid blow out is treated by ligating carotid artery. Since it is due to infective necrosis of carotid wall, graft reconstruction of the carotid is difficult.

Flap necrosis can occur; if a wide area of flap necrosis develops then some flap reconstruction is done using PMMC flap/deltopectoral cutaneous flap **(Fig. 14-44)**.

Infection, lymph ooze, carotid blow out, seroma formation, frozen shoulder are other complications. Drooping of shoulder can occur due to trapezius muscle paralysis. Pneumothorax and chylous fistula are rare complications.

Note:

To control haemorrhage in head and neck cancers and during head and neck surgeries (like radical parotidectomy, commandos and operation, maxillectomy) ligation of external carotid artery is often required. ***Ligation should be done distal to the origin of the superior thyroid artery***. It should never be ligated below the origin of the superior thyroid artery as this will lead to *eddy current* and thrombus formation at the carotid bifurcation resulting in intracranial embolism through ICA. Ligation of ECA to control bleeding is usually done in continuity **(Fig. 14-45)**.


First lower dissection is done
Mac Fee incision
Dissection of specimen/block with IJV
IJV
Digastric muscle
Carotid
Vagus

Fig. 14-43: Structures observed in neck node dissection.



Fig. 14-44: Postoperative look after radical neck dissection.

Carotid Blow Out

Carotid blow out is most dangerous complication. It is due to sepsis, wound breakdown, arterial adventitious stripping and necrosis and drying of the artery. Ligation of the carotid is done to save the life of the patient but procedure itself has got 20% mortality and 50% morbidity (hemiplegia).


ICA
ECA
Ligature
Superior thyroid artery
CCA

Fig. 14-45: Ligation of external carotid artery should be done when needed distal to the origin of the superior thyroid artery.

Bilateral Neck Dissection

It is done in carcinoma tongue or pharynx where lesion is in midline. In such case of bilateral neck dissection, internal jugular vein has to be preserved on one side. *Always the side where the vein is preserved is operated first.* Ligation of both the jugular veins will cause cerebral congestion leading to cerebral oedema which is dangerous.

During surgery if both IJV are ligated due to injury as an inevitable consequence, the patient has to be kept in propped position; antibiotics, diuretics and steroids are given; repeated CSF taps are done to control the cerebral oedema.

SURGERY OF HEAD, FACE AND JAW

This is a wide surgical topic which is basically practiced by ENT surgeons/faciomaxillary surgeons/plastic surgeons/ophthalmologists. Extensive descriptions are beyond the scope of this book however basic principles needed for general surgeons or a surgery postgraduate are given in this topic.

Principles in Face Injuries

Initial complete assessment is done like in any polytrauma. Resuscitation should be done accordingly.

Facial wounds retract widely giving false impression of wide area defect. It is due to elastic nature of facial skin and retraction by facial muscles.

All wounds by trauma in face should be cleaned thoroughly using adequate amount of warm saline; wound debridement is done; tissues are apposed layer by layer to create proper acceptable scar. Wound debridement is done using number 15 blade or fine scissor. All foreign bodies in the wound should be removed meticulously. One should avoid unnecessary excision of tissues. It is better to clean and scrub under general anaesthesia to achieve proper thorough cleaning.

If injury involves entire thickness of the face involving skin, muscle and mucous membrane, suturing is done layer by layer from mucous membrane, muscle and skin in order.

Injury to facial nerve, parotid ducts should be identified. If terminal branches of facial nerve are severed, it is not necessary to approximate it. But main branches or trunk should be sutured using fine (6 zero) polypropylene sutures using microscope. Specialised reconstructive surgeons are better to be called to handle such cases. Parotid duct is also sutured with interrupted polypropylene sutures (6 zero) using microscope.

Skin is sutured with interrupted sutures using 5 zero polypropylene sutures. It is placed close to skin edge with deeper fat plane to prevent dead space. Sutures are placed every 5-8 mm gap. Knots should only be adequate to approximate the skin. One should not strangulate the skin.

In the lip, vermillion border should be sutured first to get accurate apposition.

Sutures are removed in 5 days in face. Later wound support may be given using steri strip **(Fig. 14-46)**.



Fig. 14-46: Reconstruction of the mandible after segmental resection of the mandible for ameloblastoma using fibular microvascular flap.

SURGERY OF THE EYELIDS/ORBIT/ EYEBALL

Eyelid is sutured accurately using fine interrupted sutures. Grey line of tarsal conjunctiva should be approximated accurately. If it is not accurate 'a step deformity' in the eyelid margin will develop. Tarsal plate should be approximated using fine 5 zero vicryl or PDS sutures (absorbable). If lacrimal canaliculus is injured, a lacrimal probe is passed to assess the injury; then a fine silicone tube is passed across punctum in the lid. Suturing is done over it using magnifying lens. Silicone tube is kept in place for 6 months.

Eyebrows *should never be shaved* in trauma or in any surgeries. If shaved original eyebrow will not come back.

Tarsorrhaphy is a common procedure done as temporary basis. It is done in facial nerve palsy as there is improper closure of eyelids during blinking, trauma, hyperthyroidism with proptosis, burn injury. Lateral 1/3rd of upper and lower eyelid margins are incised between eyelashes and Meibomian glands. Created raw margins are sewed together.

Ectropion is everting of the eyelid due to scarring. It may be due to excision of an infraorbital swelling which causes scarring and ectropion. Scar tissue is released and full thickness (Wolfe) graft is placed.

Entropion is inverting of the eyelid due to conjunctival scarring (trauma, trachoma). Eyelashes get inverted and irritate the cornea. Scarred conjunctiva is excised and full thickness mucosal graft taken from oral cavity is placed on the defect. Deformed tarsal plate should be divided and everted. Radical excision of inverted eyelashes can also be done as a simple procedure. Temporary relief can be achieved by placing everting sutures through skin, tarsal plate and conjunctiva.

Eyelid tumour is excised as a full thickness. If length of excised area is less than 1/4th of the length of the eyelid, then primary suturing of the eyelid can be done. If excised defect is more than 1/4th then proper reconstruction of the defect is needed.

Excision of the external angular dermoid is done under general anaesthesia. Prior X-ray of skull or CT head in suspected intracranial extension is a must. Incision is just below and parallel to the eyebrow. Eyebrow should not be shaved. Incision within the eyebrow should not be done as scarring of hair follicle will cause eyebrow deformity with poor cosmetic outcome. Cautery usage is better during surgery. Two layer closure of the wound is done **(Fig. 14-47)**.

Periorbital lesion / swelling in the lower eyelid are excised circularly and a full thickness Wolfe graft is placed. Primary closure of the defect can cause ectropion of the lower eyelid with exposure of the lower punctum of the eyelid exteriorly; with its inability to come in contact with eyeball can cause continuous watering of the eye **(Fig. 14-48)**.

Evisceration of eye is done to prevent sympathetic ophthalmia (on opposite normal eye). Here cornea is incised and all contents are curetted. All uveal tissues should be removed completely otherwise sympathetic ophthalmia can occur. Evisceration is better to have cosmetic result.

Enucleation is done by removing the entire eyeball. Conjunctiva is incised at the corneal junction. Plane is created around the eyeball. All intrinsic muscles are detached from orbit by hooking forward. At the end optic nerve is cut. Conjunctiva is sutured.

SURGERY OF THE EAR

It is basically done by an ENT surgeon.

Haematoma of the ear is aspirated under aseptic precaution using a syringe and large bore needle. Clot gets slowly organised. Due to



Fig. 14-47: Incision to excise external angular dermoid. Eyebrows should not be shaved.



Lesion in the lower eyelid (infraorbital)
Lesion excised using circular incision
Full thickness skin graft (Wolfe) is placed to cover the defect
Note: Primary closure may cause ectropion so Wolfe graft is better.

Fig. 14-48: Full thickness Wolfe graft is needed after excision of the periorbital lesion to prevent ectropion.


Swelling in the ear lobe is excised along with cartilage adjacent
Skin incision
Incision on cartilage
Cartilage is removed wider than the skin to allow tension free suturing
Skin on either side is sutured separately without suturing the cartilage

Fig. 14-49: Excision of benign lesion in the ear lobe.

pressure ischaemia of underlying cartilage and necrosis can occur. Multiple small incisions should be made. Repeated aspirations and pressure dressings are needed. Two sterile shirt buttons are placed on either sides of the ear and sutured to achieve adequate compression. *Perichondritis and cartilage necrosis* are dreaded complications. *Cauliflower ear* may develop if not treated properly.

Injury to ear is sutured on both surfaces separately using fine polypropylene sutures (interrupted). Cartilage is not usually sutured. Proper antibiotics (anaerobic infection of cartilage is common) should be given to the patient.

Swellings/tumours in the ear is excised with V shaped incision. Underlying cartilage is excised more widely than skin to facilitate the tension free suturing of the skin on either side. Cartilage is not sutured **(Fig. 14-49)**.

Accessory auricle is excised with its deeper core cartilage and skin is sutured. It is done for cosmetic purpose. *Keloid in the ear* should not be excised.

Ear lobe repair is discussed in chapter 7 (Please refer).

CLEFT LIP AND CLEFT PALATE

Problems in Cleft Lip and Cleft Palate

There is difficulty in sucking and swallowing. This is commonly observed in cleft palate than in cleft lip. Speech is defective especially in cleft palate, mainly to phonate B, D, K, P, T and G. Problems in cleft disease are—altered dentition or supernumerary teeth, recurrent upper respiratory tract infection, respiratory obstruction (*Pierre Robin syndrome*), chronic otitis media, middle ear problems, cosmetic problems, hypoplasia of the maxilla, problems due to other associated disorders **(Fig. 14-50)**.

Treatment for Cleft Lip

Millard criteria are used to undertake surgery for cleft lip.

Millard criteria (Rule of `10')
- 10 pound in weight
- 10 weeks old
- 10 gm % hemoglobin

a. *Millard cleft lip repair* by rotating the local nasolabial flaps.
b. Management of associated primary or secondary cleft palate deformity.
c. Proper postoperative management like control of infection, training for sucking, swallowing and speech.



Fig. 14-50: Cleft lip and palate.

d. Tenninson's 'Z' plasty (Tenninson-Randall triangular flap) **(Fig. 14-51)**.



Fig. 14-51: Steps of cleft lip repair.

Principles of cleft lip repair
- 'Rule of 10' should be fulfilled
- It should be operated before 6 months
- Infection should not be present
- Millard advancement flap is commonly used for unilateral cleft lip repair
- Bilateral cleft lip repair can be done either in single or two stages (with 6 months gap between each stage)
- One stage bilateral cleft lip repair is done using Veau III method / Millard's single stage/Black method
- Proper markings are made prior to surgery and incision should be over full thickness lip
- Often 1:2,00,000 adrenaline injection is used to achieve haemostasis
- Three layer lip repair should be done (mucosa, muscle and skin)
- Cupid's bow should be horizontal
- Continuity of white line should be maintained
- Vermilion notching should not be there

Note:

Delaire timing of the cleft surgery – Unilateral / bilateral cleft lip alone, in one stage operation done in 4-6 months. Cleft palate alone involving only soft palate, is one stage surgery done in 6 months. Cleft palate alone but involving both soft and hard palates – soft palate in 6 months; hard palate in 18 months. In combined cleft lip and palate, unilateral or bilateral, done in two stages – cleft lip and soft palate in 6 months; hard palate in 18 months.

Treatment for Cleft Palate

Criteria for surgery

- 10 Kg weight
- 10 months of age (10–18 months)
- 10 gm % hemoglobin

Cleft palate is usually repaired in 12–18 months. Early repair causes retarded maxillary growth (probably due to trauma to growth centre and periosteum of the maxilla during surgery if done early). Late repair causes speech defect. Both soft and hard palates are repaired. Abnormal insertion of tensor palati is released. *Mucoperiosteal flaps* are raised in the palate which is sewed together. If maxillary hypoplasia is present then *osteotomy of the maxilla* is done. With *orthodontic help teeth extraction and alignment* of dentition is done. Regular examination of ear, nose and throat during follow up period is needed. Postoperative speech therapy is essential. Whenever complicated problems are present, staged surgical procedure is done.

Wardill-Kilner push back operation—here mucoperiosteum flaps based on greater palatine vessels is raised, a better method **(Figs 14-52 and 14-53)**.

Secondary management – Hearing support using hearing aid is given if defect is present. Control of otitis media when present. Speech problems occur due to velopharyngeal incompetence; articulation problems also can occur – speech therapy is given. It is corrected by pharyngoplasty, veloplasty or speech devices. Dental problems like uneruption, nonalignment are common. They should be corrected in a proper way by a dentist, along with reconstructive surgery. Orthodontic management with alveolar bone graft, maxillary osteotomy – done in 8-11 years of age. Veloplasty, dental implants, rhinoplasty, orthognathic surgeries, etc. are done based on requirement.

Principles of palatoplasty

- Timing is between 10–18 months
- Mucoperiosteum flap is raised
- Palatal defect is closed using 3 layers—nasal, muscle and oral layers
- Hook of pterygoid hamulus is fractured to relax tensor palati muscle to relieve tension on suture line


Cleft palate with palatine artery
Cleft palate repair V-Y palatoplasty

Fig. 14-52: V-Y palatoplasty



Fig. 14-53: Cleft palate and its repair.

SURGERIES OF THE ORAL CAVITY

Oral surgeries have become a specialty approach. So in detail discussion of each surgery is beyond the scope of this book. However common procedures and approaches are discussed here. Interested students have to refer specialised books for reference. Laser is often used in oral surgery other than cautery **(Fig. 14-54)**.



Fig. 14-54: Excision of lesion in the lip using laser.

Surgical approaches to carcinoma cheek (buccal mucosa)/oral cancers –

- Transoral/intraoral approach.
- Lip-split incision.
- *Patterson* approach.
- *Visor* flap approach for anterior mandible, floor of the mouth and tongue. Here skin over the anterior curved margin of the mandible is incised to approach the floor of the mouth for needed procedure. (*Visor* is derived from French word which means mobile lower part of the helmet which covers the chin).
- Mandibulotomy approach (*Kocher's*) for lesion over the floor of the mouth and large tongue which gives very good access **(Figs 14-55 and 14-56)**.

Different mandibular resections

- Rim resection of mandible
- Marginal mandibulectomy
- Segmental resection
- Partial mandibulectomy
- Hemimandibulectomy
- Resection of the anterior mandible through visor approach





Figs 14-55A and B



Figs 14-55A to C: Lip-split incision is used for wide excision of the carcinoma cheek, hemimandibulectomy, approach to lateral part of the floor of mouth and alveolus.



Fig. 14-56: *Visor flap approach* is used for lesions in the floor of the mouth and posterior tongue. Flap necrosis, fistula formation are less, functional results are better in relation to tongue mobility, articulation, swallowing, mastication.

Principles

Surgical approach to primary tumour whether external or transoral; adequacy of clearance in margin and depth; involvement of mandible or requirement of mandibular resection and if so extent of mandibular resection; lymphatic involvement present or not and the plan to address the neck nodes with decision for type of neck node dissection – are to be thought of while approaching the patient with oral cancers. External approaches may be Patterson / lip split / mandibulotomy.

All oral cancers are treated by *multidisciplinary approach*. For surgical treatment it is considered as early and advanced. Involvement of mandible and nodes are also considered in approaching surgically. Staging of the disease is also essential.

Early superficial oral cancers are treated by wide local excision with 1-2 cm clearance. Frozen section biopsy is essential. Small defect can be closed primarily using 3 zero vicryl continuous sutures. Larger defect can be left alone safely to granulate and heal by secondary intention. Split skin graft (on to underlying buccinators muscle) to a wider area in cheek is useful way of covering the defect. It can be fixed to cheek by passing sutures from outside in and from inside out with knot placing outside which will be removed in 5-7 days **(Fig. 14-57)**.

T1 and T2 lesions are approached with wide local excision with supraomohyoid neck node dissection if N0 OR if nodal status is N1 / N2 radical or modified radical neck dissection I (MRND I - preservation of spinal accessory nerve) is done with or without mandibular resection depending on whether mandible is involved or not or close proximity of primary tumour to mandible. Type of mandible resection is decided by the extent of the mandible involvement.

T3 or T4 lesions are treated probably after initial chemoradiation by surgical wide excision with hemimandibulectomy with neck node dissection (RND). As mucosa, submucosa, buccinators, subcutaneous fat and skin are possibly involved after wide excision a through and through defect will be created. Extension into masseteric space by tumour is common and this area should be cleared meticulously. Reconstruction is essential using free radial forearm flap, rectus abdominis flap, fibular flap, plating, rib flap (opposite 11th rib), etc. Forehead flap may be used for mucosal side with pectoralis major myocutaneous flap for outer coverage. Large PMMF can be split on the skin part after harvesting to fold to cover mucosal as well as cutaneous parts of the defect **(Figs 14-58 to 14-60)**.

Transoral Approach

It is best approach for small lesions in the cheek or lesion in the tongue. As there is no incision outside it is cosmetically acceptable. Lesions less than 2 cm can be approached per orally. Larger lesion also can be approached through oral cavity but dissection and reconstruction is difficult. Nasotracheal anaesthesia is ideal. Often endotracheal tube can be placed on the opposite side of the lesion. Neck is turned towards opposite side. Mastoid retractor is used to retract cheek. C retractor is also helpful. Proper suctioning, adequate good light, cautery is essential. Lesion is excised with 1-2 cm clearance. Depth of the clearance also should be adequate. After excision, small defect can be left like that. Larger defect is covered with a quilted split skin graft from inside.

Transfacial - Patterson Operation (Fig. 14-61)

It is used in carcinoma cheek of early stage when only mucosa is involved. Incision is placed over the (lower border) base of mandible or just above the base parallel to it, often extending vertically over the margin of the ramus. Skin flap is elevated adequately upwards. Tumour with 1-2 cm clearance is excised widely. Skin flap is sutured back. Mucosal defect can be closed primarily. Often may require a skin graft inside. Skin is fixed by quilting sutures from outside in and inside out which are removed after 5 days. Skin graft gives the range of movements and prevents mucosal fibrosis and post operative trismus development which is distressing. Skin is taken from thigh (Split skin graft). Procedure is technically easier with less complications and faster recovery.

Transfacial Lip Split Incision Approach (Fig. 14-62)

In a wider lesion, transfacial lip split incision is needed to have a wider exposure of the cheek and tumour which facilitates adequate clearance. Inside defect can be reconstructed with forehead flap or SSG; outside, if there is defect, PMMF flap or deltopectoral flap can be used. Hemimandibulectomy or other mandibular resections can be carried out through this incision **(Fig. 14-63)**.

Hemimandibulectomy

Surgical Anatomy of Mandible (Fig. 14-64)

It is the largest and strongest bone of face. It has got horse shaped body with two rami from its posterior ends projecting upwards. Outer surface of body contains symphysis menti, mental protuberance, mental foramen, oblique line and incisive fossa. Inner surface contains mylohyoid line, submandibular fossa (below), sublingual fossa (above) and genial tubercles. Upper alveolar border bears sockets for teeth. Quadrilateral ramus has got medial and lateral surfaces, anterior, posterior, upper and lower borders and coronoid and condyloid processes. Medial surface of ramus contains mandibular foramen above the centre of the ramus at occlusal surface of teeth (transmits inferior alveolar nerve and vessels across mandibular canal to mental foramen on the outer surface); lingula (bony projection of mandibular foramen gives attachment to sphenomandibular ligament); mylohyoid groove (medial pterygoid is inserted below and medial to this groove). Lateral surface of ramus is flat (attachment of the masseter muscle). Upper border of ramus forms curved mandibular notch; lower border containing angle of mandible is the continuation of the base of mandible. Posterior border of ramus is thick; anterior is thin. Anterior projection is called as *coronoid process* (temporalis is inserted on its apex and medial surface); posterior projection is called as *condyloid process*. Condyloid process is strong with expanded upward head which articulates with temporal bone to form temporomandibular joint. Anterior part of neck of condyloid process has got pterygoid fovea for the insertion of lateral pterygoid muscle. Oblique line on the outer surface of the body gives origin to buccinator; mylohyoid line on the inner surface of body gives origin to mylohyoid and superior constrictor muscles; upper genial tubercle gives origin to genioglossus and lower to geniohyoid; digastric fossa gives origin to anterior belly of digastric muscle. Investing layer of deep fascia and platysma is attached to lower border (base) of the mandible. Masseteric vessels and nerve passes through mandibular notch; mental foramen transmits mental vessels and nerve; inferior alveolar vessels and nerve passes through the mandibular canal; mylohyoid vessels and nerve are related to mylohyoid groove; lingual nerve is related on the medial surface; auriculotemporal nerve is related to medial side of the neck of the mandible. Mandible is the second bone to ossify in the body after clavicle. Ossification centre (*only one centre*) appears in 6th week of intrauterine life, one on each side near mental foramen. Entire *body* ossifies from *membrane* except only near incisor teeth; ramus *above the mandibular foramen* ossifies from *cartilage*. Site at canine socket is weak and is the *commonest site of fracture* which may involve inferior alveolar nerve causing neuralgic pain and loss of sensation over the distribution of mental nerve.


Skin incision
Tumour area involving skin
Raising the skin flap
Entering the oral mucosa
Oral growth with adjacent involved skin is excised
Teeth adjacent to growth are removed
Defect in the oral mucosa and adjacent skin after wide exicision
Mucosal defect inside
Split skin graft from the thigh is taken to cover the mucosal defect in cheek
Skin defect is closed using sutures
SSG placed over the mucosal defect inside

Figs 14.57(1)


SSG edge is sutured to mucosal edge using vicryl
Folded sofra gauze is placed on the surface of SSG in the cheek oral cavity
Sofra inside is fixed to skin of the cheek using a deep suture

Figs 14.57(2)

Fig. 14-57: Wide excision of the carcinoma cheek with placement of split skin graft on the mucosal aspect.



Fig. 14-58: Carcinoma cheek extending into the skin and soft tissues cleared widely. It needs PMMF to cover the defect from outside; split skin grafting or forehead flap to cover from inside.



Fig. 14-59: Forehead flap is also often used to cover the defect from outside.



Fig. 14-60: Pectoralis major myocutaneous flap is used commonly to cover the cheek defect.


Tumour-intraorally
Patterson incision
Skin incision
Upper flap is elevated.
Lesion is excised with clearance margin.
Defect is closed primarily often with a split skin graft from within.

Fig. 14-61: Transfacial—Patterson operation.

Muscles of mastication (derive from mesoderm of 1st branchial arch, supplied by 1st arch nerve – mandibular) are –

1. *Masseter*—A quadrilateral muscle covering outer surface of mandible has got 3 layers – superficial layer arises from anterior 2/3rd of lower margin of zygomatic arch; middle from anterior 2/3rd of deep surface and posterior 1/3rd of lower margin of zygomatic arch; deep layer from deep surface of zygomatic arch. it is inserted into lower, middle and upper part of the ramus of the mandible and coronoid process of mandible. It is supplied by masseteric branch of the anterior division of mandibular nerve. It elevates the mandible **(Fig. 14-65)**.

2. *Medial pterygoid muscle* – It is quadrilateral muscle with superficial and deep heads. Superficial is arising from tuberosity of maxilla; deep head arises from lateral pterygoid plate and adjoining palatine bone. Fibre runs downwards and backwards to reach medial surface and angle of the mandible below and behind the mandibular foramen and mylohyoid groove. It is supplied by nerve to medial pterygoid, a branch from main trunk of mandibular nerve. It elevates and protrudes

mandible. Lateral pterygoid plate, lingual and inferior alveolar nerves and lower head of lateral pterygoid lie superficial to the upper part of the muscle; ramus of the mandible, mandibular nerves, maxillary artery and sphenomandibular ligament lie superficial to the lower part of the muscle. Tensor veli palatini, superior constrictor of the pharynx, styloglossus and stylopharyngeus attached to the styloid process are deep to the muscle.

3. *Lateral pterygoid muscle* – It is a short conical muscle with upper and lower heads; upper arises from infratemporal surface and greater wing of sphenoid bone; lower from lateral surface of lateral pterygoid plate. It runs backwards and laterally to insert into pterygoid fovea on the anterior surface of neck of the mandible and anterior margin of articular disc and capsule of temporomandibular joint. It is superficially related to ramus of the mandible, temporalis muscle tendon and maxillary artery. Its deeper relations are mandibular nerve, middle meningeal artery, sphenomandibular ligament and deep head of pterygoid muscle. Deep temporal nerves and masseteric nerve emerges at its upper margin. Maxillary artery passes upwards and buccal nerve passes downwards between the two heads. Two deep temporal arteries run on the outer surface of upper head. Masseteric artery and nerve passes on the surface of lateral pterygoid towards mandibular notch to enter the masseter muscle from its deeper plane. Masseteric artery arises from maxillary artery and nerve from mandibular nerve. Lingual and inferior alveolar nerve descends from deeper plane of lateral pterygoid at its lower border. Middle meningeal artery runs upwards from its lower border at deeper plane **(Figs 14-66 and 14-67)**.



Fig. 14-62: Raising the flap after lip split incision for carcinoma cheek.



Figs 14.63(1)


Saline irrigation
Cutting the part of the mandible using electric saw
Marginal mandibulectomy
Part of the mandible chipped is drilled and resutured to remaining mandible using wire
Tongue flap is used to cover the mucosal defect
Tongue flap is raised
Tongue flap is sutured to the mucosal edge to cover the defect
Closure of skin flap
Specimen showing growth with part of the mandible

Figs 14.63(2)

Figs 14-63(1 and 2): Wide excision with marginal resection of the mandible with bone fixing using steel wires. Mucosal defect is covered using tongue flap based posteriorly.


Condyloid process
Coronoid process
Mandibular notch
Temporalis
Ramus
Masseteric vessels and nerve
Buccinator
Masseter
Body
Mentalis
Angle
Mental foramen for mental vessels and nerve
Platysma
EXTERNAL SURFACE
Auriculotemporal nerve
Lateral pterygoid
Temporalis
Inferior alveolar nerve
Superficial temporal artery
Lingula
Sup constrictor
Lingual nerve
Ext carotid artery
Maxillary artery
Sublingual fossa
Mandibular foramen
Genioglossus
Geniohyoid
Medial pterygoid
Mylohyoid groove
Ant belly of digastric
Submandibular fossa
Mylohyoid
INTERNAL SURFACE

Fig. 14-64: Surgical anatomy of the mandible.


Zygomatic arch
Masseter — origin
Outer surface of the ramus and coronoid process of mandible
Masseter-insertion

Fig. 14-65: Anatomy of masseter muscle.


Deep temporal nerve and arteries
Masseteric nerve and artery
Lateral pterygoid
Pterygomaxillary fissure
Middle meningeal artery
Buccal nerve
Lingual nerve
Maxillary artery
Sphenomandibular ligament
Inf. alveolar nerve and artery

Fig. 14-67: Outer/superficial relations of the lateral pterygoid muscle.


Lateral pterygoid
Upper head
Lower head
Articular disc of TM joint
Medial pterygoid
Superficial head
Deep head
Pterygoid fovea
Medial surface of the angle and ramus of mandible

Fig. 14-66: Origin and insertions of the medial and lateral pterygoid muscles.

4. *Temporalis muscle* – It is fan-shaped muscle arising from temporal fossa of temporal bone and temporal fascia passing deep to zygomatic arch towards its insertion at deep surface of coronoid process and anterior ramus of mandible. It is supplied by two deep temporal branches from anterior division of mandibular nerve. It elevates the mandible, retracts the protruded mandible; and facilitates side-to-side mandible movement **(Fig. 14-68)**.

Temporomandibular joint (TM joint): It is synovial condylar joint. Upper part of the articular surface is formed by the temporal bone, articular eminence and anterior part of the mandibular fossa; lower articular surface is formed by the head of the mandible. Joint cavity is divided into upper and lower part by articular disc. *Ligaments of the joint are* – temporomandibular, sphenomandibular and stylomandibular. TM joint is related laterally to skin, fascia, parotid, temporal branches of facial nerve; medially tympanic plate (separates from ICA), spine of sphenoid, upper part of sphenomandibular ligament, auriculotemporal and chorda tympani nerves, middle meningeal artery; posteriorly parotid, external auditory meatus, superficial temporal vessels and auriculotemporal nerve from deep to superfi-


Temporalis arising from temporal fossa
Insertion into the coronoid process of mandible

Fig. 14-68: Origin and insertion of the temporalis muscle.

cial; superiorly middle cranial fossa and middle meningeal vessels; inferiorly maxillary vessels. Joint movements are divided between two compartments created by the articular disc – upper meniscotemporal, lower meniscomandibular. Both right and left joints usually move simultaneously. *Movements are* – protraction, retraction, elevation, side-to-side movements **(Fig. 14-69)**.

Procedure

In mandibulectomy, growth with the mandible is removed. It is done in carcinoma cheek (oral carcinomas) which is extending into the mandible. Extent of mandible resection depends on the extent of mandibular involvement by growth and grading of the tumour. It may be rim resection of the mandible, marginal mandibulectomy, segmental resection, partial mandibulectomy, hemimandibulectomy (refer figures). Primary closure is cosmetically poor even though it gives good range of mouth opening. Reconstruction is done by various methods – like plating, bone graft, microvascular fibular graft. If there is defect in the skin and soft tissues, then pectoralis major myocutaneous flap (PMMF) or deltopectoral cutaneous flap is used. Mucosal defect if present is covered by simple split skin graft or forehead cutaneous flap. Reconstruction is done with the help of plastic surgeon.

Incision for hemimandibulectomy is 2 cm below the base of the mandible, parallel and extending towards the ear lobule along the ramus of the mandible. Often lip spilt incision is used. Flap is elevated both upper and lower. Bipolar and monopolar cautery is needed to elevate the flaps. Mandible is transected just adjacent to the mentum towards the side of the lesion using Gigli saw or ideally electric rotary saw. Resected mandible is elevated upwards to facilitate visibility of the soft tissue attachment to the base. Carcinoma lesion can be seen on the mucosal surface of the cheek which is dissected with adequate clearance. Lower flap is elevated to expose the submandibular salivary gland. The submandibular salivary gland in often removed along with the mandible during hemimandibulectomy. Once soft tissue is freed from below, medial pterygoid is cut near its attachment on the inner surface of the mandible. Temporalis is detached from the coronoid process. Small branches of the maxillary artery on the deeper surface of the masseter muscle will be ligated. Masseter muscle is cut from the upper part of its attachment to the mandible. Temporomandibular joint is dissected and lateral pterygoid is detached from its attachment to pterygoid fovea on the anterior surface of the condyloid process of the mandible. Specimen is removed. All bleeders are ligated or fulgurated. Primary closure or ideally reconstruction is planned. Nasogastric tube should be passed which is used for feeding during postoperative period. Tracheostomy is usually not required but when indicated one should not hesitate to do it especially in case if radical neck dissection is combined with hemimandibulectomy **(Fig. 14-70)**.

Flap is sutured. One or two bottles of blood may be required which should be kept ready in theatre. Mandible is reconstructed using cortical bone graft, fibular microvascular flap, synthetic material like, titanium, stainless steel plate **(Figs 14-71 to 14-73)**.

If radical neck dissection is added, a vertical incision in the neck to the existing incision is sufficient to clear the nodes. Technique of neck dissection is same as described above.

Less aggressive surgeries like segmental resection, marginal mandibulectomy, and partial mandibulectomy can be done depending on the extent of bone involvement **(Figs 14-74 to 14-78)**.

Complications of Surgeries

Bleeding, infection, flap necrosis, complications of reconstruction, stiffness, contracture, cosmetic problems, swallowing problems and speech problems are the complications observed. Respiratory


Anterior extension
Anterior band
Posterior band
Bilaminar extension
Tympanic plate
Head of mandible
Lateral pterygoid
Temporal bone
Middle meningeal artery
Sphenoid spine
Sphinomandibular ligament
Chorda tympani
Mylohyoid nerve and artery
Pharynx
TM joint
Auriculotemporal nerve
Maxillary artery
Inferior alveolar nerve and artery
Medial pterygoid

Fig. 14-69: Anatomy and relations of temporomandibular joint.


Cleaning and draping
Lip split incision
Flap is raised laterally and above to expose the mandible and tumour
Gigli saw is passed under the mandible at midline using a Kocher's forceps
Gigli saw
During sawing of mandible using Gigli saw saline irrigation should be done on to mandible cut area to prevent saw getting jammed in the bone
Head of mandible at TM joint

Figs 14.70(1)


Resected mandible specimen
Defect after hemimandibulectomy can be closed either primarily or using PMMF or DP or forehead flap

Figs 14.70(2)

Figs 14-70(1 and 2): Hemimandibulectomy technique using lip split incision with wide excision of primary tumour in the cheek.



Fig. 14-71: Hemimandibulectomy is done in this patient. Reconstruction is not done in this patient leading into poor cosmetic outcome. But mouth opening and jaw movements will be adequate.

complications like aspiration and bronchopneumonia are often life threatening. Anaesthetic complications and deep venous thrombosis are other complications.

Approach to Floor of the Mouth

Anatomy - It is U shaped area bounded by lower gum and oral tongue. It ends posteriorly at the insertion of anterior tonsillar pillar into the tongue. Sublingual papilla is present on each side of the frenulum; on summit of which is the opening of the duct (*Wharton's*) of submandibular salivary gland. Laterally and behind this papilla, sublingual fold is present which overlies the sublingual gland. Genioglossus and geniohyoid muscles are deeper to it. On either side mylohyoid muscles form the muscular part of the floor of the mouth. It arises from mylohyoid ridge of the mandible extending up to the 3rd molar tooth. Submandibular salivary gland rests on the external surface of mylohyoid muscle; only small deeper part extends into the internal surface. Submandibular salivary duct runs about 5 cm between sublingual gland and genioglossus to end in papilla. Lingual and hypoglossal nerves are closely related to gland and duct. Alveolingual sulcus is valley shaped space between tongue and mandibular alveolar bone.



Fig. 14-72: Hemimandibulectomy specimen as viewed both from outer and inner surface.

In carcinoma floor of the mouth adjacent to ventral part of the tongue, alveolus, submandibular ducts and opposite nodes are involved early. CT scan is a must to assess the stage and plan the therapy.



Fig. 14-73: Reconstruction of the mandible is done using plates, screws and bone graft.


Tumour
Mandible rim
-for resection
Mandible

Fig. 14-74: Extent of removal in mandible rim resection.



Fig. 14-75: Extent of resection in marginal mandibulectomy.


Part resected

Fig. 14-76: Extent of bone removal in segmental resection of the mandible.



Fig. 14-77: Extent of removal in partial mandibulectomy.



Fig. 14-78: Extent of resection in hemimandibulectomy.

T1 and T2 lesions are treated with wide excision with 2 cm clearance with frozen section biopsy confirmation. Lesion deeper than 4 mm needs elective neck node dissection - N_0. Transoral/lip split/mandibulotomy/visor approaches are used. Reconstruction is done using radial forearm flap.

T 3 or T 4 lesions when treated surgically needs a well planned approach. *Primary tumour* is approached with lip split and anterior stair step mandibulotomy. Wide excision with 2 cm clearance is done. If bone margin is involved marginal mandibulectomy is done. Cut mandible is distracted to expose the area widely. Hypoglossal nerve visualised in the deeper plane entering the tongue is preserved. Lingual artery is visualised and doubly ligated. Frozen section biopsy should be done for clearance confirmation. *Supraomohyoid neck dissection* one side or both in N_0 nodes is done and frozen section biopsy should be done for nodes. If positive, RND should be done. *Tracheostomy is essential* in all patients. *Nasogastric tube insertion* is also essential for later feeding purpose. Often *percutaneous gastrostomy,* if needed, should be done.

Approach to Tongue Cancers

Surgical Anatomy

Tongue is a muscular, glandular, vascular flat organ. Anterior 2/3rd is termed as body; posterior 1/3rd is base/root. Superior surface *is dorsum of the tongue*. It is an essential organ of taste. Tongue is important in speech, mastication and swallowing. Oral and pharyngeal parts are separated by V-shaped sulcus terminalis. Oral part is anterior 2/3rd and pharyngeal part is posterior third which is lymphoid tissue. Posterior tongue is connected to epiglottis by median and right and left lateral glossoepiglottic folds. Root of the tongue is attached to mandible and hyoid bone below. *Filiform papillae* are located in anterior 2/3rd of the dorsum of tongue and are numerous, fine and hair like. *Fungiform papillae* are mushroom shaped, deep red, larger, sparsely located near the tip of the tongue. Large, red, leaf-like *foliate papillae* are located in posterior third of tongue on lateral aspect which contains taste buds. *Circumvallate papillae* are 8-12 in number, mushroom shaped, arranged in large V-shaped row near posterior third of the dorsum tongue and contains plenty of taste buds. Small circular opening just posterior to this V row in the midline is called as *foramen caecum* which is the remnant of thyroglossal duct. Shallow groove just behind the circumvallate papilla on either sides of the foramen caecum is called as *terminal sulcus*. Numerous mucin glands and lymph follicles in the posterior third of the dorsum of tongue is called as lingual tonsil. *Posterior third of the tongue is difficult to inspect;* it needs head light, and spatula. It is better felt than seen. *Ventral surface* is smooth, has a median fold, *frenulum linguae* and deep lingual veins on either side. *Lingual frenulum* is attached about 10-15 mm below the mandibular central incisor tooth.

There are four extrinsic and four intrinsic *muscles of the tongue*. Extrinsic muscles are – genioglossus, hyoglossus, styloglossus, palatoglossus; intrinsic muscles are – superior longitudinal, inferior longitudinal, transverse, and vertical. Genioglossus is fan-shaped muscle arising from the genial tubercle of the mandible. It fans out and backwards. Upper fibres are inserted to tip; middle to dorsum of tongue; lower to hyoid bone. Upper fibres retract the tip; middle fibres depress the tongue; lower fibres by pulling the posterior part of the tongue forward helps in protruding the tongue.

Arterial supply is from lingual artery, a branch of ECA. Tonsillar and ascending pharyngeal arteries supply root of the tongue. Two venae commitantes accompany the lingual artery; one accompanies the hypoglossal nerve. Deep lingual vein is seen on the ventral surface of the tongue. All these veins join together at posterior border of the hyoglossus below the hypoglossal nerve to form lingual vein which enters either the common facial vein or IJV.

Lymphatic drainage – tip is to submental nodes; remaining anterior part to submandibular lymph glands; posterior third to jugulo-omohyoid nodes. Lymphatics in the midline of the tongue freely cross and communicate each other.

Nerve supply – all intrinsic and extrinsic muscles are supplied by hypoglossal nerve except palatoglossus which is supplied by cranial root of accessory nerve through pharyngeal plexus. Lingual nerve, a branch of mandibular nerve supplies general sensation and chorda tympani for taste of the anterior 2/3rd of the tongue except vallate papillae; glossopharyngeal nerve supplies general and taste sensation of posterior third of the tongue; internal laryngeal nerve of vagus supplies posterior most part of the tongue. Taste buds are numerous on the sides of vallate papillae, foliate papillae and posterior third of the tongue; are very less/sparse in fungiform papillae, soft palate, epiglottis, pharynx; are absent in mid-dorsal region of the oral part of the tongue.

Anterior 2/3rd of the tongue develops from two lingual swellings and one tuberculum impar, developed from first branchial arch (lingual nerve supply); Posterior 1/3rd from 3rd arch (glossopharyngeal nerve); posterior most from 4th arch (vagus nerve).

Principles and Types of Tongue Cancer Surgery

Anaesthesia - Nasotracheal anaesthesia is preferred. Throat packing should be done. Both monopolar and bipolar cautery and proper suction apparatus, adequate light source are needed. If neck dissection is done together then extension of the neck is needed. Turning of the neck towards opposite side of the RND/MRND is done after wide excision of primary lesion.

Intraoral approach is sufficient for small lesions. Lip split or mandibulotomy may be needed for larger and extensive tumour. Total glossectomy even though possible, it is very morbid and distressing surgery to the patient and so usually not practiced unless proper reconstruction is planned and implemented including voice restoration, and swallowing. Composite excision, commando operation requires tracheostomy, nasogastric intubation, often gastrostomy for feeding purpose.

Small lesion less than 1 cm in the lateral margin is excised widely with 1 cm clearance. Margin and depth clearance should be confirmed by frozen section. Defect is closed *vertically primarily* using 3 zero vicryl or chromic catgut continuous locking sutures or interrupted sutures. Cautery is used for excision. Laser may be used if available. *Vertical closure* maintains the mobility well. *Horizontal closure* is technically easier and practiced by many surgeons but causes tethering of the dorsal of tongue to the floor of the mouth restricting the mobility. Interrupted sutures are better as continuous sutures may get torn off from the tissue. Supraomohyoid dissection is added (N_0) in all tongue cancers as they are usually aggressive **(Figs 14-79 and 14-80)**.



Fig. 14-79: Wide excision of the tongue lesion lesser than 1 cm.



Fig. 14-80: Suturing of the raw area can also be done after excising the lesion.

Lesion in the lateral margin of size 1-2 cm is treated with partial glossectomy with 2 cm clearance. Defect can be sutured primarily or raw area can be left to granulate on its own. Split skin grafting to cover the defect can be done. Supraomohyoid dissection is done for N_0 lesion **(Figs 14-81 and 14-82)**.

Tumour larger than 2 cm in the lateral margin is treated by hemiglossectomy where anterior 2/3rd of the tongue in front of the sulcus terminalis and lateral to midline one side is removed using cautery. Lingual vessels should be doubly ligated using vicryl or monocryl. Reconstruction is done by cheek flap or simply rotating remaining half of the tongue (retained) over the defect. It gives good range of movements of the tongue. Supraomohyoid dissection (N_0) or MRND I/RND are done if nodes are positive **(Fig. 14-83)**.

If mandible is involved hemimandibulectomy and RND is done along with hemiglossectomy which is often called as *commandos operation.*

Composite resection of the tongue cancer (*Commando operation*) with resection of the mandible with RND is done using lip split incision after elevating the skin flaps above.

Dorsal tongue cancer is not common. It is treated by sagittal resection and closed primarily.

Posterior third of the tongue is approached through lip split and anterior mandibulotomy approach.

Pull through visor flap approach to the tongue is another approach for deep rooted tumour. It needs preliminary tracheostomy, nasogastric intubation, gastrostomy for feeding. Bilateral neck dissection is done. One side RND other side MRND II with retaining IJV is done. Side where IJV should be retained is decided prior and should be operated first. A visor flap of skin is elevated up to the inferior margin of the mandible. Mucosa on the uninvolved side floor of the mouth is incised and extended to involved tongue side with 2 cm margin. Mylohyoid muscle is cut and anterior and lateral cuts are communicated. Tongue with tumour is delivered under the mandible through an external neck wound. Lesion is excised with 2 cm clearance taking care of clearance in depth. Reconstruction is essential using radial forearm and PMMF flaps. Postoperative speech therapy and training for swallowing are needed.



Fig. 14-81: Partial glossectomy is done if lesion is 1-2 cm in size over the lateral margin.


Tongue fixation
Lesion
Placement of retractor
Incision using 15 no blade from posterior to anterior
Deeper dissection using cautery
Dissection in the depth
Tumour removal
Suturing the base
Raw defect area

Figs 14.82(1)



Fig. 14.82(2)

Figs 14-82(1 and 2): Partial glossectomy technique.



Fig. 14-83: Hemiglossectomy is done if lesion is more than 2 cm in lateral margin.

Approach to Hard Palate Cancers

Surgical Anatomy

Roof of the mouth is formed by hard palate and soft palate. *Hard palate* is firm anterior part of the roof of the mouth ending opposite 3rd molar anterior to fovea palatine. *Soft palate* is mobile posterior part of roof of the mouth. Junction between hard and soft palate is called as *vibrating line*. Small rounded elevation of tissue in the midline behind the central incisors is called as *nasopalatine papilla* which is over incisive foramen through which nasopalatine nerve traverses to supply anterior hard palate. Slightly elevated central line is called as *palatine raphe*. Here mucosa is firmly adherent to underneath periosteum without any fat and so it is harder area of hard palate. Sides of hard palate contain fat and minor salivary glands (there are around 350 minor salivary glands in posterior hard palate). Series of elevations in hard palate are called as *palatine rugae* useful for food positioning and aiding tongue to produce specific sounds. Hard palate is partition between nasal and oral cavity. Anterior 2/3rd is formed by palatine process of maxillae; posterior 1/3rd is by horizontal plates of palatine bones. Anterolateral margins continue with alveolar arches and gums. Posterior margin attaches to soft palate.

Soft palate is redder than hard palate due to its vascularity. There is no bone in soft palate behind vibrating line. Soft palate vibrates or moves. It is mobile muscular fold. It has got anterior and posterior surfaces, superior and inferior margins. Uvula is small fleshy part projecting from center of the posterior margin of the soft palate. Pair of pits on either side of the centre of the soft palate just behind the vibrating line is called as *fovea palatini* to which palatine mucous glands opens. Side of the uvula has got anterior and posterior folds. Anterior palatoglossal arch contains palatoglossus muscle which ends as anterior pillar of fauces (in front of tonsils). Posterior palatopharyngeal arch contains palatopharyngeus muscle which ends as posterior pillar of fauces (behind tonsils). Soft palate contains mucous glands and taste buds. Soft palate contains following muscles – tensor veli palati; levator veli palati; musculus uvulae; palatoglossus; palatopharyngeus. All muscles except tensor palati are supplied through pharyngeal plexus by cranial part of accessory nerve; tensor palati is supplied by the mandibular nerve. General sensory nerves are derived from middle and posterior palatine nerves which are branches of maxillary nerve and from glossopharyngeal nerve. Gustatory special sensations are carried through lesser palatine nerve →greater petrosal nerve →geniculate ganglion of facial nerve→nucleus of solitary tract. Secretomotor fibres are derived from superior salivatory nucleus through greater palatine nerve and lesser palatine nerves. Paralysis of the soft palate (vagus nerve lesions) causes nasal regurgitation of liquids, nasal twang in voice and flattening of palatal arch.

Maxillectomy

Surgical Anatomy

Maxilla is the 2nd largest bone of the face (after mandible). Two maxillae form upper jaw with formation of face, nose, mouth, orbit infratemporal and pterygopalatine fossae. Maxilla has got a body and 4 processes – frontal, zygomatic, alveolar and palatine. Body is pyramidal in shape with base directed medially towards nasal surface and apex directed laterally at zygomatic process. Anterior surface contains incisive fossa and canine fossa. Above the canine fossa there is infraorbital foramen with infraorbital vessels and nerve. Posterior surface forms the anterior wall of the infratemporal fossa. Posterior superior alveolar nerve and vessels are near the centre of the surface. Posteroinferiorly rounded maxillary tuberosity articulates with pyramidal process of the palatine bone. Maxillary tuberosity gives origin to superficial head of medial pterygoid. Anterior wall of the pterygopalatine fossa is above the maxillary tuberosity and is grooved for maxillary nerve. Superior surface forms the floor of the orbit; its medial border forms nasolacrimal canal with lacrimal bone; its medial border articulates with lacrimal, labyrinth of ethmoid, orbital process of palatine bone; superior surface has got infraorbital groove, canal and foramen to transmit infraorbital nerve and vessels. Medial surface forms lateral wall of the nose; posterosuperiorly there is hiatus for maxillary sinus. Above the hiatus parts of ethmoidal and lacrimal air sinuses are present. Inferior nasal meatus is below the hiatus. Medial surface below the hiatus articulates with perpendicular plate of palatine bone forming greater palatine canal for greater palatine vessels and anterior, middle and posterior palatine nerves. Nasolacrimal groove is present in front of the hiatus to form nasolacrimal canal with the lacrimal bone and inferior nasal concha to transmit nasolacrimal duct to the inferior meatus of the nose. The pyramidal shaped large cavity of 3.5 × 3.5 × 2.5 cm dimension, the maxillary sinus (maxillary antrum) has its base medially and apex laterally. Maxillary sinus opens into the middle nasal meatus with two openings. Roof is formed by the floor of the orbit; floor is formed by alveolar process of maxilla. Floor has got conical elevations by roots of upper molar and premolar teeth. Root of canine tooth projects into the anterolateral wall. Maxilla articulates above to nasal, frontal and lacrimal bones; medially to ethmoid, inferior nasal concha, vomer, palatine bones and opposite maxilla; laterally to zygomatic bone. Maxilla ossifies in membrane from 3 centres - one for maxilla just above the canine fossa during 6th week of intrauterine life; one of the two for premaxilla arise just above the incisive fossa during 7th week of intrauterine life and another at ventral margin of nasal septum during 10th week. Mucosa of the maxillary sinus is lined by squamous epithelium.

Procedure (Fig. 14-84)

Endotracheal general anaesthesia is used. Weber Ferguson incision is made. Entire thickness of upper lip, cheek and lower eyelid is elevated as a lateral flap. The periosteum on the floor of the orbit is elevated. Orbital contents are protected by placing a spatula between the periosteum and the bone. Ala of the nostril is drawn medially after separating from the bone. Nasal process of maxilla is divided at its junction with the nasal bone. Later it separated from the lacrimal and ethmoid bones towards inferior orbital fissure. After dividing zygomatic bone, mouth is widely opened with a gag. Alveolus and hard palate are divided in midline and then from pterygoid process. Maxillary artery and nerve are cut; soft tissues are divided. Gauze pack is placed. Cheek flap is placed on the pack and sutured. Often ligation of external carotid artery in continuity is needed to prevent haemorrhage. In olden days, 7 days prior to surgery ECA used to be ligated. With proper prosthesis and obturator cosmetically it sounds good.



Fig. 14-84: Weber Ferguson incision for maxillectomy.

Maxillectomy Procedure – Types

Partial maxillectomy: It is removal of portions of maxilla, incisive bone, palatine bone with or without portions of the zygomatic and lacrimal bones.

Premaxillectomy: It is unilateral or bilateral with removal of incisive bone and perhaps rostral maxilla.

Central maxillectomy: Here maxilla and portions of hard palate resected.

Caudal maxillectomy: Here maxilla, hard palate, zygomatic, and lacrimal bones removed.

Hemimaxillectomy: It is removal of entire maxilla on one side extending dorsally to ventral orbit.

Orbitectomy: It is removal of orbit with or without caudal maxilla and vertical mandibular ramus.

Maxillectomy can be –

Unilateral rostral – Done when lesions are confined to hard palate on one side. Here one layer closure is done.

Bilateral rostral – Done in bilateral lesions of rostral hard palate.

Lateral – Done in laterally placed midmaxillary lesions; it needs viable buccal mucosa for closure of flap.

Bilateral – Done in bilateral palatine lesions. Defect closure needs formal reconstruction. Closure dehiscence and oronasal fistula is common.

SURGERY FOR LIP LESIONS

Lip being a *complex anatomical structure* needs comprehensive approach to excise the lesion and reconstruct it. Upper lip reconstruction is *more difficult* and demanding as it *involves* in oral competence, speech and phonation. Dynamically upper and lower lips are independent. Lower lip functions in many axes. Thickness, location, size of the lip is important. Mucosa, muscle and skin should be approximated each separately as an individual layer. Defect <30% will be closed with local advancement flaps; defects > 60% need complicated complex approaches. Grafting, local flaps, regional flaps, free flaps are the options. Grafting is not ideal as it creates scarring and poor cosmesis. Contracture, microstomia, adynamic flap in relation to dynamic flap, often need of a second surgery like reconstruction of the commissure are the *problems*.

Simple cyst of the lip derived from mucus gland is excised under local anaesthesia (xylocaine without adrenaline) and sutured primarily using fine absorbable sutures either continuously or intermittently **(Fig. 14-85)**.

Surgical Anatomy of Lip

Lip is the area between the nasolabial folds from the gingivolabial sulcus to the labiomental fold. Vermilion is coverings of lip margin. Its wet part comes into contact with opposite lip; dry part is external lip. Orbicularis oris which origins from modiolus and inserts to philtrum maintains the oral competence. Its horizontal fibres compress the lip; oblique one everts the lip. Elevation of the upper lip is achieved by levator labii superioris, zygomaticus major and levator



Fig. 14-85: Simple cyst in the lip is excised under local anaesthesia and sutured primarily.

anguli oris. Lower lip depression is brought about by depressor labii inferioris; movement of commissure below and lateral is brought about by depressor anguli oris. Central lip is elevated by mentalis. Muscles around mouth are – orbicularis oris, levator labii superioris, zygomaticus major and minor, levator anguli oris, depressor anguli oris, depressor labii inferioris, mentalis, risorius and buccinators. Motor supply of orbicularis oris is by facial nerve – buccal branch. Depressors are supplied by marginal mandibular branch. Sensory supply of upper lip is infraorbital nerve a branch of ophthalmic division of trigeminal nerve, lower lip is by mental nerve, a branch of mandibular division of trigeminal nerve. Blood supply of lip is by superior and inferior labial arteries, branches of facial artery. Upper and lateral parts of lower lip drain into submandibular lymph nodes; central lower lip drains to submental lymph nodes **(Fig. 14-86)**.



Fig. 14-86: Surgical anatomy of the lip.

Principles in lip surgeries are – restoration of oral competence to achieve control of secretions, drinking, eating and speech; cosmetic achievement of lip; achieving good muscular function; scar placement; prevention of microstomia; creating adequate labial buccal sulcus to prevent drooling. It is impossible to achieve perfect normal lip in texture. Only optimum lip can be achieved by reconstruction.

Indications for lip reconstruction are – carcinoma of lip after wide excision; trauma; dog bite; vasculitis; septic necrosis of lip; congenital anomaly.

Anaesthesia for lip surgery—general or local field block can be used. Upper lip is entirely anaesthetized using bilateral infraorbital nerve block using 26 G needle at a point lateral to alar base and medial to nalolabial fold 7 mm below the infraorbital margin of the medial limbus. This nerve can also be blocked intraorally. Lower lip can be anaesthetised by regional block of mental nerve. Local anaesthetic agent is infiltrated 1 cm lateral to the canines into buccal sulcus.

Defect Less Than One-third of the Lip

Primary Closure

Excision of lower lip up to 1/3rd is sutured primarily without causing any microstomia. Vermilion border of the lip should be kept in opposition. Lip is sutured in layers; deeper layer with 3 zero vicryl; outer layer with 3 zero polypropylene sutures. It is used in upper lip lateral defect and lower lip defects **(Fig. 14-87)**.

Skin grafting, ear composite graft and Abbe flaps are used for upper lip central defects less than 1/3rd.

Defects between One-third to Two-third of the Lip

Here primary closure will cause microstomia, speech, eating and drinking problems. So it should be avoided.

In the upper lip central defect skin grafting, composite graft of ear, Abbe flap, perialar crescent, cheek advancement flaps are used. *In the upper lip lateral defect* Abbe-Estlander flap, perialar crescent, cheek advancement flap, nasolabial flap, reverse Karpandzic flaps are used.

In the lower lip central defect Abbe flap, Schuchardt flap, Webster flaps are used. *Lower lip lateral defect* is covered with Estlander flap, Gillies flap, Karapandzic flap, or McGregor flaps **(Fig. 14-88)**.

Defect More than Two-third of Lip

In upper lip defect – Abbe-Estlander with perialar crescent, cheek advancement flap; nasolabial flap; reverse Karapandzic flap; forehead flap; deltopectoral flap; radial forearm free flap are used **(Fig. 14-89)**. *In lower lip defect* - Abbe-Estlander flap, Webster flap; Bilateral Gilles flap; deltopectoral or radial forearm flaps are used **(Figs 14-90 and 14-91)**.

Different Procedures

Estlander's (Abbe-Estlander's) rotation flap of upper lip is based on upper labial artery. It is used when defect is less than half of lip



Fig. 14-87: Primary closure of the defect in the lip is possible when defect is less than 1/3rd.


Lesion at lower lip angle
Flap marking
Wide excision
Defect after wide excision
Defect after wide excision
Flap mark
Raising Abbe flap
Flap ready for transposition
Flap reconstruction

Figs 14.88(1)



Figs 14.88(2)

Figs 14-88(1 and 2): Abbe–Estlander flap – reconstruction of the defect in the lip after wide excision. Here 2nd stage base division is not done.


SSG over donor flap area
Flap

Fig. 14-89: Forehead flap can be used for defect after excision of upper lip lesion of more than 2/3rd in size.


Inferiorly based nasolabial flap bilateral
Tumour in the floor of the mouth removed defect
Flap rotated into the defect in the floor of the mouth

Fig. 14-90: Nasolabial flap can be used in large central defect.

but more than 1/3rd. It is done in lateral lip defects, upper or lower, involving commissure. Flap is denervated and so sensation is absent and drooling of saliva is possible **(Fig. 14-92)**.

Frie's modified Bernard facial flap is done using lateral facial flaps. It is used when defect is more than ½ of lip, midline defect and for commissure reconstruction. Two triangles are excised and cheek flap is rotated and advanced. Vermilion is constructed using advancement of oral mucosa **(Fig. 14-93)**.

Different microvascular flaps are used to cover the defect. Free radial artery flap also can be used.



Fig. 14-91A



Figs 14-91B and C

Figs 14-91A to C: Abbe-Estlander flap.



Fig. 14-92: Abbe–Estlander flap for lateral defects in the lip.



Fig. 14-93: Bernard lateral flaps for central defect.

Nasolabial flap is used when defect is more than ½ of lip and lateral or defect is in the floor of the mouth.

Cheek flap can be rotated when lesion is near the angle of the mouth.

Abbe flap (switch flap) is used in upper/lower lip lesion – central defect. It is taken from lower/upper lip with inferior/uperior labial artery as base. It is transfer of myocutaneous lower/upper lip to upper/lower lip in two staged technique. In first stage myocutaneous full thickness lip flap is elevated with labial artery pedicle to suture into the upper / lower lip defect. Pedicle is divided after 2 – 3 weeks and rotation is completed (switch) with suturing of the further flap **(Fig. 14-94)**.

"W' flap plasty – It is done for lower lip middle tumour which is less than 1/3rd of the lip **(Fig. 14-95)**.

Gillies fan flap – It is a cheek flap usually bilateral but can be unilateral. Incision is full thickness around commissures extending into nasolabial fold and upper lip up to upper lip vermilion border. Flap which is based on labial vessels is advanced towards the defect. Vermilion is reconstructed with tongue mucosal flap which is divided in 3 weeks. Flap is denervated and so sensation is absent and drooling of saliva is possible **(Fig. 14-96)**.


Abbe flap
Tumour
A
Rotated flap
Excised bed
Donor flap area
B
Rotated flap
Excised bed
Donor flap area
C
Rotated flap
Donor flap area
D
Suture lines
E

Fig. 14-94: Abbe switch flap.


Tumour
'W' flap

Fig. 14-95: 'W' flap is used for lower lip central defect which is less than 1/3rd of the lip.


Tumour removed
Gillies fan flap

Fig. 14-96: Gillies fan flap is a cheek flap which can be unilateral or bilateral.

Karapandzic flap – It is modified (myocutaneous) version of the Gillies flap used for lower lip defect with less angulation towards upper lip. It preserves motor and sensory supply of flap and so drooling is avoided. Reverse Karapandzic flap is used for upper lip defect.

McGregor and Nakajima flaps modified Gilles flap (denervated) pivot around commissure which prevents microstomia but drooling of saliva can occur.

Zisser technique – Cheek tissue is moved medially after excising two upper and lower triangles later to upper and lower lip. Horizontal incision is made along the commissure to advance de-epithelialised two triangles.

Platz and Wepner method is similar like Zisser's where nasolabial and submental areas are excised triangularly to advance superior and inferior cheek flaps.


A
Tumour in upper central lip
B
Wide excision is done
with a central defect
C
Cheek advancement perialar crescent excision

Fig. 14-97: Cheek advancement with perialar crescent excision.

Johansen 'step ladder' procedure is used for extensive carcinoma of lower lip.

Cheek advancement with perialar crescent excision is done for wide upper lip defect **(Fig. 14-97)**.

Other regular flaps like forehead flap, deltopectoral flap also can be used.

Upper Lip Reconstruction

Due to presence of philtrum, upper lip reconstruction is more demanding than lower lip. Wound close to philtrum if primarily sutured, will shift the philtrum to the lesion side.

Lateral defect less than 1/3rd is either closed primarily or V Y flap or nasolabial flap is used. In males nasolabial flap being hairless may be problematic for upper lip.

Central lip defect needs reconstruction of Cupid's bow to prevent flattening. Abbe lip switch flap, skin graft, ear cartilage composite grafts are required to reconstruct Cupid's bow.

Defects between 1/3rd to 2/3rd are corrected using Abbe flap, perialar excision cheek advancement flap.

Defect more than 2/3rd in upper lip is repaired by bilateral reverse Karpandzic flaps, bilateral nasolabial flaps, and forehead flap. First two flaps denervate the lip and may precipitate drooling of saliva. But insensate lower lip is more problematic than insensate upper lip as saliva collects in lower lip and drooling occurs from gravity across the lower lip. Other methods used are perialar crescent excision and cheek advancement; radial forearm free tissue flap with microvascular and nerve anastomosis (anterior cutaneous nerve of forearm to mental nerve).

Lower Lip Reconstruction

It is easier to reconstruct the lower lip than upper as lower lip is devoid of central structure.

Defect less than 1/3rd is closed primarily. One should avoid formation of dog ear or incision crossing the labio mental fold. W flap can be used in central defect less than 1/3rd.

Defect between 1/3rd to 2/3rd is covered using Abbe switch flap from upper lip lateral 1/3rd. 1/4th or 2 cm of upper lip tissue can be transferred. Width of donor lip needed is 1/2 of width of the recipient defect. Recipient site attains pain, temperature, touch and sweating functions in 2 years. Upper lip donor defect can be reconstructed additionally using perialar excision and cheek advancement if needed. *Schuchardt technique* may be used with a modified wedge resection with advancement of the lip contralateral to the lip switch. Webster flap with triangular excisions of skin along the nasolabial crease of the upper lip to mobilise cheek can be used. *Johansen stepwise/stepladder excisions* of 2-4 fold skin around labiomental fold can be used. This avoids microstomia. Unilateral advancement is done for smaller defects; bilateral advancement is done for larger defects.

Defect more than 2/3rd is corrected using bilateral Karpandzic flap or McGregor flap or Webster modification of Bernard burrow flap. Here cheek is advanced medially by triangular excision of skin. Nasolabial fold skin is excised triangularly. Inferiorly based nasolabial Fujimori gate flap, bipedicled tongue flaps, deltopectoral flap and free flaps are other flaps used.

Vermilion Reconstruction

White roll is the mucocutaneous junction. Any defect even of 1 mm size in vermilion is easily seen. White roll should be marked using 25 G needle tip dipped in methylene blue prior to injecting the local anaesthetic drug. One should not place sutures directly on white roll as healing erythema will mask the white roll. Sutures on either side of the white roll should be placed one on vermilion side other on cutaneous side. White roll should cross 90° while placing the incision. Resection of the entire vermilion from the white roll to wet-dry junction of vermilion is called as *lip shave/ total vermilionectomy* which is done for premalignant conditions and actinic lip involvement. Buccal mucosa is advanced above orbicularis oris as bipedicled flap. V Y advancement of labial or buccal mucosa is commonly used. Mental nerve runs in submucous gland plane and so plane of dissection is between submucous gland plane and orbicularis oris. Lip switch or tongue flaps are also often used. Ventral tongue flap is used in females to facilitate application of the lipstick; dorsal tongue flap is used in males. Full thickness palatal mucosal graft and tattooing are other options for vermilion reconstruction.

Commissure Reconstruction

It is done using Estlander flap, Fries technique, Zisser procedure, or Platz and Wepner technique **(Fig. 14-98)**.


Wide excision of the
tumour at commissure
Excision of two triangles lateral to upper
and lower lips with horizontal full thickness
incision lateral to commissure
Two de-epithelialised triangles are advanced
medially to create new comissure

Fig. 14-98: Zisser commissure reconstruction method.

Chapter

15

Surgery for Thyroid and Parathyroid

SURGICAL ANATOMY OF THYROID (*THYROID – 'SHIELD LIKE'*)

Development

Thyroid gland develops (*origin*) from columnar cells of pharyngeal floor as a median down growth between 1st and 2nd pharyngeal pouches; point which later forms foramen caecum at the base of primitive tongue (*thyroid primordium*). These columnar cells form a tube which gets canalised to form thyroglossal duct. While descending downwards (*by migration*) it gets displaced forward by developing hyoid bone and below the hyoid bone it descends further slightly towards left side which eventually bifurcates into one on each side to form two lateral lobes. Part present at its junction of bifurcation forms isthmus. Once gland is formed remaining portion of the duct obliterates; part of the duct on left side forms pyramidal lobe.

> Origin → migration → obliteration of duct mostly except lower most part which forms pyramidal lobe → Differentiation of the gland, isthmus and pyramidal lobe.
>
> Neural crest → along the ultimobranchial body → incorporation of parafollicular C cells in the thyroid adjacent to follicles.

Ectopic thyroid tissue can occur and may be the only thyroid tissue which is present along the line of the duct in the posterior tongue (lingual thyroid) or suprahyoid region. It is identified by radioisotope scanning.

Thyroglossal cyst occurs due to persistence of a portion of the thyroglossal duct. Entire duct and centre portion of the body of the hyoid bone has to be removed with removal of suprahyoid portion of the duct up to the foramen caecum.

Agenesis of one lateral lobe or both can occur. Only existing one lateral lobe may present as toxic or nontoxic solitary nodule.

Anatomy (Thyroid Means – Shield)

It is a butterfly shaped, brownish red coloured, vital endocrine gland situated in the central compartment of neck. It is located in anterior triangle of neck, 5 (height) × 3 (depth) × 1.5 (width each lobe) cm in size weighing about 20-25 gram (slightly more in women). Gland may get enlarged during menstruation and pregnancy. It has got right and left lateral lobes occupying the thyroid space between trachea and oesophagus medially and carotid sheath laterally extending from middle of thyroid cartilage to 6th tracheal ring. Right lobe is larger than left. Isthmus is connecting part between two lateral lobes extending from 2nd to 4th tracheal rings. Isthmus is around 1.5 ×1.5 cm in size. It is absent in 10% of individuals. Gland extends from C5 to T1 vertebral level behind; from middle of thyroid cartilage to 5th/6th tracheal rings in front. Thyroid space is between trachea and oesophagus medially and carotid sheath laterally. Normal gland is soft and supple. *Pyramidal lobe* is an extension of gland upwards on the surface of the cricoid towards left side which often extends above to the hyoid bone as a fibrous or muscular strand from the junction of isthmus and left lateral lobe. It is present in only 33% (1/3rd) of individuals. Fibromuscular extension to hyoid bone is called as *levator glandulae thyroideae*. Gland is invested by pretracheal fascia. It is supported by a strong condensed vascular connective tissue between lateral lobe and cricoid cartilage on each side called as *Berry's ligament*. True thyroid capsule is peripheral condensed connective tissue and blood vessels are deeper to it. True capsule is covered by false capsule which is derived from pretracheal layer of deep cervical fascia. It is thin in front; thick behind and forms Berry's ligament above and behind. Surgical avascular plane is located between true and false capsule. (In prostate, surgical cleavage plane is located deep to true capsule) **(Figs 15-1 to 15-5)**.

Each lateral lobe has got lateral, medial and posterolateral surfaces; anterior and posterior borders; apex and base. Lateral surface is covered by sternocleidomastoid, sternohyoid and omohyoid; and sternothyroid in deeper plane. Medial surface is related to trachea, oesophagus, cricothyroid and inferior constrictor; external laryngeal and recurrent laryngeal nerves. Anterior jugular veins run on the anterior surface in front of muscles **(Fig. 15-6)**.

Deep fascia of neck has got four compartments – investing layer; prevertebral fascia; pretracheal fascia; carotid sheath.

Muscles in the anterior aspect of the neck are classified as –

Suprahyoid muscles

- Stylohyoid
- Geniohyoid
- Mylohyoid.

Infrahyoid muscles – Strap muscles

- Sternohyoid – in front


Hyoid bone
Levator glandulae thyroideae
Thyroid cartilage
Ligament of Berry
Cricoid cartilage
Pyramidal lobe (Left side)
Lateral lobe
Isthmus
False capsule
True capsule
Trachea

Fig. 15-1: Parts of the thyroid with their locations and relations. Two lateral lobes; one isthmus; one pyramidal lobe.


Thyroid
False capsule
Prostate
Venous plexus
Plane of cleavage
True capsule
Venous plexus
Plane of cleavage
Gland

Fig. 15-2: Surgical avascular plane in thyroid is located between true and false capsule. In prostate surgical cleavage plane is located deep to true capsule.


Left side
General investing layer
Right side
Strap muscle
General investing layer of fascia coli
Superior thyroid artery
Strap muscles
Sternocleidomastoid muscle
Lateral lobe of thyroid gland
Sternocleido-mastoid muscle
True capsule
Lateral lobe of thyroid gland
Internal jugular vein
False capsule
Vagus
Oesophagus
Internal jugular vein
Vagus
Trachea
Common carotid artery
Inferior thyroid artery
Recurrent laryngeal nerve
Common carotid artery
Inferior thyroid artery
Parathyroid gland

Fig. 15-3: Fascia around thyroid with true and false capsules.

- Omohyoid - in front
- Sternothyroid – deep to above muscles
- Thyrohyoid – deep to above muscles

Arterial supply is –

1. ***Superior thyroid artery*** which is a branch of external carotid artery enters the gland near the superior pole as a larger anterior superficial branch and a smaller posterior branch. It is accompanied by external laryngeal nerve, a branch of superior laryngeal nerve (a branch of vagus), which supplies cricothyroid muscle.


Investing layer of deep fascia
Strap muscles
Pretracheal fascia (False capsule)
Anterior
Posterior
True capsule
Suspensory ligament of Berry
Thyroid gland (One lateral lobe)

Fig. 15-4: True and false capsules of thyroid and suspensory ligament of Berry.


Tongue
Foramen caecum
Hyoid bone
Thyroglossal duct
Thyroid cartilage
Parathyroid (Superior)
Thyroid
Pyramidal lobe
Parathyroid (Inferior)
Trachea
Thyro-thymic ligament
Thymus

Fig. 15-5: Anatomy of thyroid gland, thyroglossal duct and parathyroids.


Recurrent laryngeal nerve
Oesophagus
Carotid sheath
Parathyroid
Carotid artery
Vagus
Sympathetic chain
Trachea
Thyroid
Internal jugular vein
Internal jugular vein
Thyroid cartilage
Superior thyroid vein
Middle thyroid vein
Thyroid
Inferior thyroid vein
CCA
Lt brachiocephalic vein
A

Fig. 15-6A


Hyoid bone
Thyrohyoid membrane
Thyroid cartilage
Cricothyroid muscle
Cricoid cartilage
Thyroid gland outline
Trachea
Superior laryngeal nerve
Internal laryngeal nerve
External laryngeal nerve
Inferior constrictor muscle
Oesophagus
Recurrent laryngeal nerve

Fig. 15-6B

Figs 15-6A and B: Relations of thyroid gland–diagrammatic look.

2. ***Inferior thyroid artery*** is a branch of thyrocervical trunk of subclavian artery runs upwards, medially then downwards behind the carotid sheath and middle cervical sympathetic ganglion, in front of vertebral vessels divides into 4-5 terminal branches which pierce the pretracheal fascia separately to supply and enter the lower pole of the thyroid. Its ascending branch also supplies the parathyroid glands (both lower and upper).

3. *Thyroidea ima* artery (3-10%) also called as lowest thyroid artery arises from arch of aorta or brachiocephalic artery enters the gland and isthmus.

4. *Accessory thyroid art*eries arise from tracheal and oesophageal arteries also supply the gland **(Fig. 15-7)**.

Venous supply is by –

1. *Superior thyroid vein* from upper pole accompanying the artery to join IJV or common facial vein.

2. *Middle thyroid vein* is a short, wide, thin walled vein begins from mid-lateral aspect of the lateral lobe running a short distance in front or behind the carotid artery, immediately enters into the IJV. Secure ligation of the vein is needed and if it tears, it may extend into IJV causing torrential haemorrhage. As it is the one that holds the gland posteriorly, it should be ligated first to mobilise the gland. Occasionally this vein may be absent. One should also remember that there is no middle thyroid artery.

3. *Inferior thyroid veins* begin at lower pole of isthmus form a plexus in front of trachea later joining the respective brachiocephalic vein. These veins are not accompanied with inferior thyroid artery. Occasionally both inferior thyroid veins form a common trunk – thyroidea ima vein which joins left brachiocephalic vein.

4. *Kocher's 4th thyroid vein* may be present occasionally between middle and inferior thyroid vein, joins either IJV or middle thyroid or inferior thyroid vein.

Note:
Anterior jugular vein is a small but variable vein begins at submental region below the chin, descends vertically in superficial fascia 1 cm from midline. At 2.5 cm above the sternum, it pierces the deep investing fascia to enter the suprasternal space. Here it is connected by a communicating vein to opposite side called as jugular venous arch. Later the vein runs laterally deep to sternocleidomastoid towards its posterior border up to the clavicle to join the external jugular vein. Anterior jugular vein is variable – may be absent; may be in midline; may be quite large drained by common facial vein. This vein is important in thyroid surgeries even though it is not related to venous drainage of thyroid gland **(Fig. 15-8)**.

Nerve Supply

It is mainly from middle cervical ganglion partly from superior and inferior cervical ganglion.

Lymphatic Drainage

(1) *Primary nodes* are trachea- prelaryngeal nodes (*Delphian*), pretracheal and paratracheal nodes, oesophageal nodes, and mediastinal nodes (brachiocephalic also called as superior mediastinal nodes). (2) *Secondary nodes* are deep cervical, supraclavicular and occipital nodes **(Fig. 15-9)**.

Note:
Recurrent laryngeal nerve is in trachea-oesophageal groove in relation to Berry's ligament and is very important structure in thyroidectomy. Parathyroid glands are four in number, two on each side – often embedded in thyroid gland. Removal of all four glands in thyroidectomy may lead into severe hypoparathyroidism and hypocalcaemia.


Omohyoid muscle
Superior thyroid vein
Superior thyroid artery
Middle thyroid vein
False capsule
True capsule
Inferior thyroid vein
Internal jugular vein
Common carotid artery
Inferior thyroid veins

Fig. 15-7: Vessels of the thyroid gland.


Mandible
Anterior jugular vein in superficial fascia
Sternocleidomastoid
Anterior jugular vein piercing deep fascia
Platysma
External jugular vein
Sternum
Jugular venous arch in deep fascia

Fig. 15-8: Anatomy of anterior jugular vein.


JV
CCA
Superficial nodes
Deep nodes
Superior thyroid artery
Delphian nodes
Tracheo-oesophageal nodes
Inferior thyroid artery
Thyroid
Trachea
Supra-clavicular nodes
Mediastinal nodes

Fig. 15-9: Lymphatic drainage of thyroid gland.

Anatomy and Relations of Nerves with Thyroid Gland

External Laryngeal Nerve

External laryngeal nerve is a branch of superior laryngeal nerve. Vagus gives superior laryngeal nerve branch from its inferior ganglion of vagus which is at the level of greater cornu of hyoid bone, which in turn divides into internal laryngeal and external laryngeal nerves. Internal laryngeal nerve pierces the thyrohyoid membrane and gives sensory supply to larynx above the vocal cord and hypopharynx. External laryngeal nerve runs close to superior thyroid vessels to supply cricothyroid muscle which is tensor of vocal cord. It may get injured while ligating superior pedicle causing defective pitch of the voice. So the upper pedicle of thyroid should be ligated close to gland but after identification and dissection of the nerve **(Fig. 15-10)**.

Recurrent Laryngeal Nerve

Recurrent laryngeal nerve is a branch of vagus which hooks around *ligamentum arteriosum* on the left with arch of aorta and right subclavian artery on the right side. It runs in the tracheo-oesophageal groove near the posteromedial surface close to thyroid gland. Nerve lies in between branches of inferior thyroid artery. On the right side, the nerve runs between branches of the artery in approximately 50% of patients, anterior to the artery in 25% and posterior in 25%. On the left, the nerve runs posteriorly to the artery in 50% of patients, in 35% the nerve runs between branches, in 15% it is anterior to the artery. So the nerve is always near the artery, but the exact relationship cannot be determined. Hence inferior thyroid artery should be ligated away from the gland (old theory, not practiced now). Anomalies of the nerve should be remembered. In 5% of cases nerve passes through the gland. Nerve may be much more away from the gland. Nerve may be closely


Superior vagal ganglion
Superior laryngeal nerve
Jugular foramen
Inferior vagal ganglion
Internal laryngeal nerve
External laryngeal nerve
Cricoid
CCA
Vagus
Thyroid
Inferior thyroid artery
Right subclavian artery
Left recurrent laryngeal nerve
Lateral subclavian artery
Right recurrent laryngeal nerve
Trachea
Arch of aorta

Fig. 15-10A


Carotid artery
Inferior thyroid artery
– 50%
Thyroid
Rec laryngeal nerve
– 25%
Thyroid
Rec laryngeal nerve
– 20%
Thyroid
Rec laryngeal nerve
– 1.5%
Thyroid
Rec laryngeal nerve
– 0.25%
Thyroid
Vagus
Non–recurrent–Rec laryngeal nerve
B
Thyroid cartilage
Thyroid
Trachea
Rec laryngeal nerve
C

Figs 15-10B and C

Figs 15-10A to C: Anatomy of recurrent laryngeal nerve and external laryngeal nerve.

adherent to gland posteriorly. Nerve may lie within the ligament of Berry (25%). Redd in 1943 described 28 variations in RLN relation to inferior thyroid artery. In his observation – RLN is deep to artery in 40%; superficial in 20% and in between branches in 35%; only in 17% of cases pattern were same in both sides.

Nonrecurrent laryngeal nerve may be present in 1 to 5 in 1,000 cases with a horizontal course. In 5 of 1000 patients, a nonrecurrent laryngeal nerve is found on the *right side*. This arrangement occurs when a retroesophageal right subclavian artery arises from the dorsal side of the aortic arch. *The non-recurrent laryngeal nerve branches* from the vagus at approximately at the level of the cricoid cartilage and directly enters the larynx without looping around the subclavian artery. A left-sided non-recurrent laryngeal nerve can occur only when a right-sided aortic arch and ligamentum arteriosum are concurrent with a left retroesophageal subclavian artery.

RLN supplies all muscles (abductors, adductors) of the larynx except cricothyroid and also sensory supply of larynx below the vocal cords **(Fig. 15-11)**.

Muscles of the Larynx

- Cricothyroid – It is the only muscle which is located on the external aspect of the larynx. It is supplied by external laryngeal nerve. It is tensor and mild adductor of the vocal cord.
- Abductors of the vocal cord – Posterior cricoarytenoids.
- Adductors of the vocal cord – Lateral cricoarytenoids, transverse arytenoid, thyroarytenoids and cricothyroids.
- Relaxant of vocal cords – Thyroarytenoids and vocalis.
- Muscles which close the laryngeal inlet – Oblique arytenoids and aryepiglottic.
- Muscles which open the laryngeal inlet – Thyroepiglotticus **(Fig. 15-12)**.

Positions of vocal cord –

Median; paramedian (1.5 mm); normal; cadaveric/neutral (3.5 mm); gentle abduction (7 mm); completely abducted (9.5 mm).


Superior thyroid artery
Thyroid cartilage
Thyroid gland
Trachea
Carotid artery
External laryngeal nerve
Vagus nerve
Recurrent laryngeal nerve
Inferior thyroid artery
Thyrocervical trunk
Subclavian artery

Fig. 15-11: Nerves and arteries related to thyroid gland. External and recurrent laryngeal nerves and superior and inferior thyroid arteries are important structures while doing thyroidectomy. Parathyroid glands are also equally important.


Hyoepiglottic ligament
Hyoid bone
Lateral thyrohyoid membrane
Opening for internal laryngeal nerve
Thyrohyoid membrane
Thyroid cartilage
Cricoid cartilage
Cricotracheal ligament
Oblique part of cricothyroid muscle
Straight part of cricothyroid muscle
Trachea with rings/ cartilage

Fig. 15-12: Thyroid and cricothyroid cartilages with cricothyroid muscle. Cricothyroid has got straight and oblique parts. Straight originates from arch of cricoid cartilage to posteroinferior margin of the thyroid lamina. Oblique part runs from cricoid cartilage to inferior horn of thyroid cartilage. Cricothyroid is supplied by external branch of superior laryngeal nerve. Branch is closely associated with superior thyroid vessels.

Assessment of voice change

- Pitch of the voice- whether raised/lowered or pitch locked
- Breath support during speaking is adequate or not
- Ability to alter the rapidity of speech – slow/fast/medium
- Altered laryngeal and neck muscle tension
- *Indirect laryngoscopy*- with tongue pulled out using gauze, warmed ILS is introduced into the oral cavity to see vocal cords. Patient is asked to say 'e' to see the vocal cord movements

Rule of '2' in thyroid

- 2 lobes
- 2 origins – Thyroglossal duct, C cells neural crest
- 2 capsules – true, false
- 2 arteries
- 2 nerves related deep
- 2 tubes related deep
- 2 muscles related deep
- 2 lymphatic drainage area – central and lateral
- 2 parathyroids each lateral lobe
- 2 triangles – BHEARS; JOLLS
- 2 hormones (T3/T4; Calcitonin)

Jolls triangle	**BHEARS triangle**
Formed by midline; strap muscles; sup thyroid pedicle. Its floor is cricothyroid. It contains external laryngeal nerve.	RLN; CCA; inferior thyroid artery; at anteromedial aspect of the thyroid.

Hyoid Bone

It is U shaped bone located in the middle of the anterior aspect of the neck between chin and thyroid cartilage. It develops from 2nd and 3rd branchial arches. It is suspended by tips of the styloid processes of two temporal bones by stylohyoid ligament. It lies at the level of base of the mandible in front and 3rd cervical vertebra behind. It provides attachment to tongue and floor of the mouth above; larynx below; epiglottis and pharynx behind. It has got central body and two pairs of greater and lesser cornua.

Anterior surface of the body is convex and is directed forwards and upwards. Posterior surface of body is directed backwards and downwards. There is a transverse ridge in the body which divides the body of the bone into upper and lower parts and deep cervical fascia is attached to it. Geniohyoid, mylohyoid, genioglossus, hyoglossus, sternohyoid, omohyoid and thyrohyoid muscles are attached to body. Thyrohyoid membrane is attached to upper border from behind and below. Pretracheal fascia is attached to lower border. Greater cornua gives origin to middle constrictor medially and hyoglossus laterally; insertion of stylohyoid muscle; attachment of fibrous loop (pulley) of central tendon of the digastric muscle. Two small conical spike like projections lesser cornua give attachments to stylohyoid ligaments one on each side.

Thyroid moves upwards during deglutition –

- During 1st stage of deglutition
  ↓
- Hyoid moves upwards by constrictor action
  ↓
- Pulls pretracheal fascia upwards
  ↓
- Pulls ligament of Berry
  ↓
- Pulls thyroid upwards

Note:

All structures enclosed in pretracheal fascia will move with deglutition –

- Thyroglossal cyst
- Pretracheal lymph nodes
- Subhyoid bursa

EXCISION OF THYROGLOSSAL CYST

Thyroglossal cyst is due to congenital incomplete regression of the thyroglossal duct along its pathway, persisting as tubulodermoid cystic swelling in the midline towards left which causes a 'tug' while protruding the tongue and also moves upwards while swallowing. Often gland will be present only in the wall of the cyst with empty thyroid fossa. Ultrasound neck, radioisotope study, T3, T4, TSH and FNAC of cyst is needed before surgical removal. Entire track up to the foramen caecum of tongue (at the junction of middle and posterior third of the tongue) should be excised to prevent recurrence or fistula formation **(Fig. 15-13)**.

Technique (Sistrunk Operation) (Fig. 15-14)

It is done under general anaesthesia. Position is supine with neck extended. Through transverse neck incision placed over the cyst, skin flap is raised above along with platysma. Care should be taken not to open the cyst. Deep fascia is opened vertically in midline. Cyst with surrounding tissues is dissected up to the hyoid bone. Sternohyoid and thyrohyoid muscles are separated and retracted. Cyst is mobilized upwards along with the track. Track is densely adherent to the body of hyoid bone above. Hyoid bone is separated from the thyrohyoid membrane through a clean fascial plane without fear of opening the pharyngeal wall. Geniohyoid and mylohyoid muscles superiorly and sternohyoid inferiorly are divided off from the hyoid. Central 1 cm part of the hyoid bone is resected along with intact track within it. Track with adjacent tissues is dissected above up to the foramen caecum. Adjacent tissues also should be removed because of possibility of multiple tracks which otherwise lead to recurrence or fistula formation. Often anaesthetist is asked to apply digital pressure over base of the tongue near foramen caecum to facilitate the dissection and to confirm the reach up to the foramen caecum. Track is ligated at foramen caecum using 3 zero vicryl and removed. Recurrence rate by removal of only track without central hyoid is 25%. Removal of track with central hyoid reduces the recurrence rate to 5%. Haemostasis is maintained using bipolar cautery. A suction drain is placed.



Figs 15-13A and B: Thyroglossal cyst when present commonly normal lateral lobes will be present. But occasionally normal lateral lobes may be absent and only thyroid tissue existing in these patients will be in the wall of the thyroglossal cyst.

Complications of Neck Injury

Complications are recurrence, thyroglossal fistula formation, haemorrhage/haematoma formation and infection. Occasionally two transverse incisions are needed to allow proper dissection

THYROIDECTOMY

Thyroidectomy is a surgery of *precision, patience and perfection*.

Principles are –

- Absolute haemostasis. Bipolar cautery should be used. Minimise/avoid using monopolar cautery in main dissection as lateral heat may damage RLN or parathyroid blood supply.


A
Horizontal incision on the cyst - Should not open the cyst.
Often anterior jugular veins need to be ligated.
B
Raise the flap with platysma above the hyoid bone up to the level of foramen caecum of tongue.
Cyst
Thyroglossal track
C
Dissect the cyst from lower flap - then upwards along with the thyroglossal track with cut central 1 cm of body of hyoid bone using stout scissors on both sides.
D
Anaesthetist may need to push the base of tongue from above to feel foramen caecum - at this level track is excised.
E
Specimen with central hyoid bone.
Wound closed in layers - deep fascia, platysma and skin.

Fig. 15-14: Thyroglossal cyst excision steps – A to E.

- Prevention of injury to recurrent laryngeal nerve and external laryngeal nerve.
- Preservation of parathyroid glands.
- Cosmesis.
- Meticulous technique.
- RLN and ELN should be identified during dissection. All vessels should be ligated individually. One should avoid mass ligation even though it is commonly practiced.
- Middle thyroid vein, superior thyroid artery and vein then inferior thyroid vessels are ligated in order.

Preoperative preparation

- Blood grouping, cross matching and required blood should be kept ready.
- Indirect laryngoscopy. Patient is asked to tell 'E' to check the abduction of vocal cord. IL scope should be soaked in warm water to prevent fogging and blurring of the IL scope.
- Serum calcium estimation; T3, T4, TSH; Thyroid antibodies, endocrinologist's opinion.
- ECG and cardiac fitness especially in toxic goiter.
- Radioisotope iodine scan; FNAC.

Different Types of Thyroidectomies

Hemithyroidectomy

It is removal of one lateral lobe with entire isthmus. It is done in benign disease involving only one lobe like solitary nodule thyroid either toxic or nontoxic (adenoma/colloid goitre of one lobe/colloid cyst). After hemithyroidectomy, if histology report comes as differentiated malignancy either papillary or follicular then completion thyroidectomy is done immediately within one week. If histology report comes after one week then completion thyroidectomy is done after 3 weeks. Reexploration is not advisable in 2nd and 3rd weeks **(Fig. 15-15)**.

Subtotal Thyroidectomy

It is removal of most of both lateral lobes including isthmus, except around 8 gram of tissue (or tissue equal to pulp of little finger) in lower


Part removed
Part retained
Entire one lateral lobe and isthmus
Sternomastoid muscle

Fig. 15-15: Hemithyroidectomy: Entire one lateral lobe and entire isthmus are removed retaining entire opposite lateral lobe. It is done in solitary nodule/toxic or non-toxic adenoma in one lobe.


Part removed
Part retained
Pulp of the finger or 4-8 gm
thyroid in lower pole both sides
Sternomastoid muscle

Fig. 15-16: Subtotal thyroidectomy.

pole. It is done in toxic thyroid and often in nontoxic multinodular goitre. It reduces the incidence of hypoparathyroidism and injury to recurrent laryngeal nerve **(Fig. 15-16)**.

Partial Thyroidectomy (Thomas)

It is removal of mobilised gland in front of trachea including entire isthmus. It was the procedure done earlier in nontoxic multinodular goitre. It is at present *not commonly used* **(Fig. 15-17)**.

Near Total Thyroidectomy

Here both lateral lobes except small tissue in lower pole are removed. It is to safeguard the recurrent laryngeal nerve and *parathyroid blood supply*. It is advocated in papillary carcinoma of thyroid (usually in young individuals). Isthmus is entirely removed. Tissue is retained either in one or both sides **(Fig. 15-18)**.


(Thyroid tissue in tracheo-oesophageal groove)
Part retained
Part removed
Part of both
lateral lobes and
entire isthmus
Sternomastoid muscle

Fig. 15-17: Partial thyroidectomy is removal of mobilized gland in front of the tracheal level. Glands in trachea-oesophageal grooves are retained. It is not commonly done now.


Except small tissue in lower
pole near rec nerve and parathyroids (one or both sides-1 g/1 cm)
(Both sides)
Part removed
Rec L nerve
Both lateral
lobes and isthmus
Part retained
Parathyroid
Sternomastoid muscle

Fig. 15-18: Near total thyroidectomy.

Total Thyroidectomy

Here entire gland is removed without retaining any tissue. It is the *present procedure of choice in most of the thyroid diseases* except benign disease limited to one lateral lobe. It is done at present in nontoxic multinodular goitre, toxic goitre, carcinoma thyroid (follicular/ medullary/papillary/operable/anaplastic) **(Fig. 15-19)**.


Part removed
Both lateral
lobes and isthmus
Sternomastoid muscle

Fig. 15-19: Total thyroidectomy. It is done in follicular carcinoma and medullary carcinoma of thyroid.

Hartley Dunhill Operation

It is removal of one entire lateral lobe, isthmus and partial/subtotal removal of opposite lateral lobe. It is used in nontoxic multinodular goitre **(Fig. 15-20)**.

Isthmectomy

It is done in advanced carcinoma or occasionally in Riedel's thyroiditis to treat severe stridor due to tracheal narrowing.

Note: Isthmus should be removed in entirety in any type of thyroidectomy, and if it is retained partially it gets adherent to wound in front creating a cosmetically poor scar **(Fig. 15-21)**.


(One side partial–in tracheo-oesophageal groove)
Part removed
Isthmus, one entire lateral lobe and other side-partial /subtotal (4 grams retained)
Part retained
Sternomastoid muscle

Fig. 15-20: Hartley Dunhill operation.

Fig. 15-21: Emil Theodor Kocher – Father of thyroid surgery.

Procedure (Fig. 15-21)

Anaesthesia

General anesthesia is used. Occasionally local anaesthesia can be used in patients who are not fit for general anaesthesia. Oesophageal stethoscope often may be required to place in case of retro/para-oesophageal goitres.

Position

Neck is extended by placing sandbag/round bolus/Dunhill pillow/folded sheet/*inflatable thyroid pillow*/inflatable intravenous fluid cuff underneath the shoulder. Ring should be kept under the occiput. Both arms are kept beside patient's body and hands are tugged/tucked under the patient's buttock. Cotton pads are placed under the elbow to prevent ulnar nerve compression. Head end of the table is elevated to 15° to improve venous return so as to reduce venous congestion in the neck and so oozing (reverse Trendelenburg/Rose/Barking dog/Kocher's position). This increases the risk of air embolism due to negative pressure created in neck veins. Veins should be ligated securely and then only cut. Any doubtful air in IJV should be aspirated immediately **(Fig. 15-22)**.

Anaesthetists are on the head end away from the field of surgery with sides kept free for surgeon, assistant and scrub nurse.

Cleaning of the area – neck, face, chest up to nipples is done. Draping is done on all sides. *Double towel* is placed under the head and one of the towels (outer one) is covered over the outer part of the endotracheal tube. Sterile transparent plastic drape is ideal if available. Surgeon stands on right side, assistant on left side and scrub nurse on right side at foot end of the patient. Energy sources like cautery (both unipolar and bipolar)/ ligaseal/harmonic, etc. are kept ready. Suction apparatus with fine suction tip is needed **(Fig. 15-23)**.

Incision

Horizontal crease incision is placed two fingerbreadth (2-3 cm) above the sternal notch extending from posterior border of one sternocleidomastoid to opposite side. Incision is marked by placing stretched thread or silk over the skin. It can be marked using marking ink. Often few surgeons use 60 ml of 1 in 400000 adrenaline saline to inject into the superficial fascia to reduce bleeding while raising the flap. Skin is incised using no 15 blade. In women with heavy breasts incision is placed slightly at higher level than usual as subsequent scar may be dragged downwards close to sternum creating ugly scar. Platysma is identified and incised slightly at higher level than skin to prevent it getting adherent to scar at a later period **(Fig. 15-24)**.

Raising the Flaps

Upper flap (*subplatysmal flap*) is raised up to thyroid cartilage (platysma is absent in the midline); lower flap up to sternoclavicular joint/clavicular heads and suprasternal notch **(Figs 15-25 and 15-26)**.

Rising of flap is done either using cautery or no. 15 blade or curved sharp scissor or blunt gauze dissection using finger. All bleeders are fulgurated properly. Care should be taken not to injure anterior jugular veins running on either side of the midline. There may be chance of air embolism if it is injured. In the lower part of the wound near lower flap both anterior jugular veins communicate through a communicating vein which if injured may cause bleeding and air embolism. In such situation anterior jugular veins distal to the communicating vein level should be ligated to prevent air embolism. Later veins are ligated proximally **(Fig. 15-27)**.

Retraction of the Flaps

A self-retaining Joll's thyroid retractor is placed. Silk skin sutures to upper and lower flaps can be placed to retract instead of Joll's retractor. Hamburger–Brennan–Mahorner self-retaining retractor can also be used **(Figs 15-28 to 15-30)**.

Dissection

Deep fascia is incised vertically in midline/median raphe. Strap muscles are retracted (sternohyoid and omohyoid are in outer plane; sternothyroid is in deeper plane). Midline plane is blood less. Incision is done and plane is opened using either cautery or 15 no blade or fine scissor. Strap muscles are retracted laterally using a deep retractor. If gland is large and if there is difficulty in mobilising gland then strap muscles can be cut between two Kocher's clamps at their upper part (as nerve supply to strap muscles is at lower part through ansa hypoglossi) **(Figs 15-31 and 15-32)**.


Extended neck
Sandbag under the shoulder
Head end 15 degrees elevated
1. Head end elevated 15°
2. Sandbag under the shoulder
3. Head rest under the occiput
4. Hands tugged under the buttocks
Area of cleaning for thyroidectomy
Double towel to drape head end
Double sterile towel draping
Completed draping with 15° head end elevation

Figs 15-22(1)

Figs 15-22(2)

Figs 15-22(1 and 2): Position of the patient in thyroidectomy. Neck is extended by placing the sandbag under the shoulder. 15° head up position is used. After cleaning, draping is done using double sterile towels to the head.


Two finger breadth


- Neck extended
- Head end elevation
- Cleaning neck and upper chest

Fig. 15-23: Position and cleaning the area.


Crease incision 2-3 cm above the sternal notch
Incision line is marked by stretching silk/thread

Fig. 15-24: Incision for thyroidectomy.

Thyroid fossa lateral and deep to the lateral lobe is dissected using blunt (peanut) and sharp dissection. Lateral lobe of the thyroid is held using gauze or Babcock's forceps to retract medially. Short stout middle thyroid vein is identified and ligated securely (double ligation is better) using 3 zero silk/vicryl. Blind dissection (should be avoided) near middle thyroid vein may tear or avulse it from IJV causing torrential haemorrhage. This allows proper mobilization of the gland to identify parathyroid glands and recurrent laryngeal nerve **(Fig. 15-33)**.

Gland is now retracted downwards and laterally to expose the superior pole. It is dissected with sharp and peanut dissections. Superior thyroid artery and vein supplies the gland from superior pole. This space in front of cricothyroid is called as cricothyroid *space of Reeves*. In this space external laryngeal nerve which is just proximal to superior pole deviates towards cricothyroid muscle. Cricothyroid muscle is tensor of vocal cord which maintains the pitch of the voice. This nerve should not be injured. So artery and vein are *individually*


Fig. 15-25: Subplatysmal plane is used while raising the flap in thyroidectomy.



Fig. 15-26: Raising of upper flap and lower flaps in subplatysmal plane.


Flap raising using monopolar cautery
Flap raising using scalpel blade no 15
Flap raising using scissor
Flap raising using gauze

Fig. 15-27: Flaps are raised using monopolar cautery or scissor or gauze or finger dissection.


Joll's thyroid retractor
Lock is opened to open the tip of the blade
Blades
Tips of the blades
Screw knob is turned to widen the blades
Blades are widened
Tips of the blades
After applying the Joll's retractor

Fig. 15-28: Joll's thyroid retractor is commonly used to retract the upper and lower flaps.


Side arm for lateral retraction of strap muscles
Strap muscles
Skin
Thyroid gland
Subcutaneous tissue
Retraction of skin, subcutaneous tissue and platysma.

Fig. 15-29: Hamburger – Brennan – Mahorner self retaining retractor with side arm to retract strap muscles.



Fig. 15-30: Retraction of the elevated flaps in thyroidectomy using silk sutures.

ligated close to the gland to avoid injuring the nerve. Individual ligation of artery and vein also prevents rare problem of AV fistula. Artery should have 2 or 3 zero vicryl ligatures proximally. Often clips/ligaseal device are used to the vessel. Slipping of the ligature postoperatively can cause life threatening haemorrhage or compressing haematoma. *Often by many*, superior pedicle is ligated en mass. Prior to this Kocher's grooved director when available is passed underneath so that deeper tissues are safeguarded while cutting the pedicle. It is *advisable to identify the external laryngeal nerve* with careful dissection to safeguard it to prevent developing *altered pitch of voice (timber of voice).*

Inferior pole of the thyroid is exposed and inferior thyroid veins are ligated adjacent to gland. Often thyroid ima venous plexus may be present in front of the trachea in midline which should be ligated properly **(Fig. 15-34)**.

Both blunt and sharp dissection using peanut, fine scissor, mosquito forceps with gentle traction over the gland medially will expose the recurrent laryngeal nerve and parathyroid glands. Recurrent laryngeal nerve passes behind the inferior thyroid artery in tracheooesophageal groove. But one should be aware of different variations which can cause nerve injury. Inferior thyroid artery arises from thyrocervical trunk of subclavian artery, running upwards, downwards and then medially under the carotid artery to reach the gland in front of the recurrent laryngeal nerve. To control any bleeders in this region *bipolar cautery* should be used (*never unipolar*). Branches of inferior thyroid artery while entering the gland should be ligated using 3 zero vicryl or silk. Ligating inferior thyroid artery or its branches close to gland avoids injury to the artery of parathyroid from inferior thyroid artery (*capsular dissection or orange peel dissection)*. Olden day's classical method of ligating the inferior thyroid artery away from the gland just after crossing behind the carotid artery (ligation in continuity using absorbable suture – catgut) is *not commonly practiced* now **(Fig. 15-35)**.


Straight
Kocher's
clamps
Strap muscles
Thyroid gland
Strap muscles
Kocher's
forceps
Kocher's clamps are applied to
strap muscles near upper end
Kocher's clamp
Cautery- monopolar
Kocher's clamps are applied
to strap muscles near upper
end and muscles are cut in
between using monopolar
cautery or scalpel or scissor
Strap muscles
Suturing of the strap muscles
after thyroidectomy using vicryl
- 2 or 3 zero

Fig. 15-31: Cutting the strap muscles near upper end and later after thyroidectomy apposition of the strap muscles using vicryl.


Lesser occipital nerve
C1
Superior root of
ansa cervicalis
C2
Great
auricular
nerve
Transverse
cervical nerve
C3
C4
Inferior root of
ansa cervicalis
To C5
Supraclavicular
nerve
Phrenic nerve
Clavicle

Fig. 15-32: Ansa cervicalis/hypoglossi and other neck nerves.



Fig. 15-33: Middle thyroid vein.



Fig. 15-34: Ligation of superior thyroid artery is done close to the gland individually after identifying the external laryngeal nerve.



Fig.15-35C

Figs 15-35A to C: Location of parathyroids and their variations should be remembered. Parathyroids should be retained during thyroidectomy. It is also important to retain their blood supply also.



(A) Inferior thyroid artery is ligated after origins of its branches to superior and inferior parathyroid glands - Present technique. Ideal and better.

(B) Inferior thyroid artery is ligated away from the gland immediately after coming behind the CCA - ligation in continuity using absorbable (catgut) suture - older/earlier technique.

Figs 15-35A and B

Berry's ligament which is adherent to thyroid is cut with care to mobilise the gland properly medially as recurrent laryngeal nerve is very close to the Berry's ligament. RLN should be identified unlike older concept ('nerve not seen is not damaged' is *disproved*; present concept is '*nerve not seen is damaged*') **(Fig. 15-36)**.

Parathyroid glands vary in their position on the surface of the gland but can be easily identified by its different colour (golden yellow/caramel like). Glands should be dissected off the thyroid with their blood supply. ⅓ of one gland is sufficient to maintain the function (calcium metabolism by releasing PTH). Ideally *all four parathyroids should be preserved*. Due to vasospasm of vessels of the parathyroids temporary hypoparathyroidism is common but reversible. Unnecessary handling of parathyroids should be avoided. Handling of the gland makes it congested. Viability of parathyroid can be checked by carefully incising it using fine scalpel. Doubtful gland should be sliced adequately and transplanted into same side sternocleidomastoid muscle.

Inferior pole vessels are individually ligated.

Opposite lateral lobe is also dissected similarly. It is surgeon's choice to decide on which side to stand while dissecting on opposite side. In difficult thyroids it is often preferred to go to opposite side and dissect the gland.

Thyroid is dissected from anterior surface of trachea using cautery or fine scissor. If part of the gland is retained in the tracheooesophageal groove (subtotal) it should be oversewn using 3 zero vicryl. Fine clamps are placed in series on the thyroid capsule. Gland is transected using no 15 blade. Retained gland is undersewn using vicryl continuous locking sutures. Anterior part of this retained gland is sutured to trachea **(Fig. 15-37)**.

In hemithyroidectomy, one lateral lobe and entire isthmus is removed. Junction of isthmus and opposite lateral lobe is clamped using haemostat/Kocher's clamp and gland is cut. Clamped retaining gland is under run using vicryl **(Fig. 15-38)**.


Thyroid gland
RLN


Thyroid gland
RLN

Fig. 15-36: Recurrent laryngeal nerve should be identified in all thyroidectomies.

Proper haemostasis is done using bipolar cautery. Pedicles are inspected again for their security **(Fig. 15-39)**.

Closure

Sandbag is removed. Again haemostasis is confirmed. Often stretched neck prevents bleeding from small veins but once sandbag is removed they may bleed which should be controlled. Traditionally suction drain is placed which is brought out through a separate stab incision or one of the ends of the main wound. Drain should pass under the strap muscles to reach the thyroid fossa. If proper haemostasis is done drain can be avoided. Controversy still surrounds the use of drains after thyroid surgery. Strap muscles are approximated using interrupted 3 zero vicryl sutures. Platysma is sutured using 3 zero vicryl interrupted sutures. Subcuticular absorbable 3 zero monocryl suture is used for skin. Dressing with pressure using dynaplast is the usual practice. But a dressing that covers the wound *may mask* haematoma formation, delaying its recognition. Placing soft light dressing or without any dressing may be ideal even though it is not practiced by most surgeons **(Fig. 15-40)**.

The *prevention of postoperative bleeding* depends on good intraoperative hemostasis. Hemostasis in thyroid surgery is achieved by means of clamp and tie, surgical clips, diathermy - unipolar initially


Trachea
Thyroid nodules
RLN
CCA
IJV
Inferior thyroid artery
Series of haemostats applied over thyroid capsule
Each lobe of the gland is sutured on the surface of trachea
Trachea

Fig. 15-37: Partial or subtotal thyroidectomy is done by applying series of haemostats on the thyroid capsule to facilitate the removal of the gland in front. Retained gland is under run using vicryl sutures.


Kocher's clamps are applied on the isthmus
Diseased side lobe
Normal side lobe
Superior pedicle
Middle pedicle
Inferior pedicle
After cutting the isthmus, junction of normal side lobe and cut isthmus is under run using 3 zero vicryl. Diseased side lobe is dissected off the trachea and is removed.

Fig. 15-38: Isthmus at its junction to retaining lobe of the thyroid gland is transected between clamps and retaining cut part of the thyroid tissue is under run using vicryl.


Positioning and cleaning
Incision line is marked by stretching silk/thread
Incision line can be marked with ink 2-3 cm above the suprasternal space
Subplatysmal plane
Elevation of upper flap
Flaps are retracted using Joll's retractor or silk sutures
Joll's retractor in place
Opening the deep fascia vertically in midline using cautery
Holding and dissecting the strap muscles
Exposing the thyroid gland
Middle thyroid vein ligation
Superior pole dissection at space of Reeves
Here mass ligation is shown but individual ligations of artery and vein are IDEAL
Ligate superior pedicle close to gland using vicryl/silk
Cutting the superior pedicle
Ligation of superior thyroid vein and artery separately close to the gland IDEAL METHOD
Mass ligation of pedicle close/over the superior pole of the gland- NOT IDEAL METHOD But practiced by many commonly
Superior thyroid artery
Superior thyroid vein
Second ligation
Middle thyroid vein
First ligation
Thyroid gland
Pedicle ligation is done by-
- Clips
- Harmonic scalpel
- Ligaseal
- Double ligation using vicryl
- Transfixation using vicryl
Inferior thyroid artery
Inferior thyroid vein
Trachea
Third/final ligation

Figs 15-39(1)


Opposite side dissection
After removal of the gland, retained part (if like in subtotal) is sutured (under run) using vicryl sutures
Strap muscles (cut)
Trachea
Just after thyroidectomy before closure
Strap muscles are sutured using vicryl
Strap muscles
Strap muscles - sutured
Kocher's clamps are removed
Strap muscles- sutured
Tube drain under the strap muscles
Approximation of midline deep fascia using interrupted sutures- vicryl
Sutured strap muscles
Midline suturing- interrupted sutures

Figs 15-39(2)

Figs 15-39(1 and 2): Technique of thyroidectomy.

and bipolar in the depth, ultrasonic coagulating-dissection such as a harmonic scalpel (HS) or electrothermal bipolar vessel sealing systems (EBVSS) **(Figs 15-41 and 15-42)**.

Thyroidectomy with Lymph Node Dissection for Carcinoma Thyroid

Level VI (cervico - central/pretracheal and tracheooesophageal) nodes are removed routinely in all thyroid cancers. Frozen section biopsy of level III deep cervical node is done. If it is involved, a modified radical neck dissection preserving IJV, accessory nerve and sternocleidomastoid muscle is done. Same thyroid incision extended laterally and above towards mastoid process is usually sufficient to do additional lymph node dissection. For bilateral neck dissection, incision is extended on both sides. Sympathetic chain and hypoglossal nerve above will come into picture during dissection which should be preserved.

In medullary carcinoma of thyroid, central node dissection, often modified radical neck dissection with dissection of upper mediastinal nodes (level VII) and thymus is done. Meticulous dissection is needed to preserve recurrent laryngeal nerve and parathyroids.

In any malignancy with clinically significant palpable neck nodes confirmed by FNAC modified radical neck dissection is done along with total thyroidectomy.


Drain is placed under strap muscles in thyroid fossa
Drain
Joll's retractor
Drain is usually passed through separate incision
Suction drain bag
Wound can be left open without dressing or soft dressing may be used
Suction drain
Subcuticular suturing of the skin using monocryl- absorbable

Fig. 15-40: Placing the drain in thyroidectomy. Wound is left open or soft dressing may be placed. Compression dressing is commonly used even though practiced is not necessary/ideal.


Bipolar cautery should be used in deeper dissection
Argon-laser coagulation

Fig. 15-41: Bipolar cautery is used in deeper dissection. Monopolar cautery is used only during raising flaps and incising the deep fascia in midline. Often argon laser coagulation may be used on the surface.


Thyroidectomy scar

Fig. 15-42: Thin linear scar usually forms after thyroidectomy which is cosmetically acceptable.

Lateral Approach Thyroidectomy

Lateral approach is used in large thyroid enlargement/recurrent thyroid disease/often thyroid carcinoma instead of classical neck approach. After lengthy skin incision, plane is created between anterior border of sternomastoid muscle and lateral to strap muscles to proceed with surgery. Often sternocleidomastoid muscle may need to be removed.

Removal of Retrosternal Goitre

Usually there will be enlarged neck thyroid of similar pathology. As retrosternal thyroid receives its blood supply from neck it is usually delivered to thyroid incision of neck with blunt dissection and removed. Occasionally in large/vascular/adherent retrosternal goitre a median sternotomy may be added to remove it.

Postoperative Care

Patient is kept in postoperative room with head end tilted 30° upwards. Once patient is fully awake with normal breathing (in 4-6 hours), patient is shifted to ward. Patient should be observed for bleeding, formation of haematoma, stridor, drop in O_2 saturation, tachycardia or tachypnoea. Tetany may be observed in 3-4 days. *Hungry bone syndrome* can cause severe hypocalcaemia in immediate post-operative period. Drain is removed in 24–48 hours depending on the quantity of collection in drain.

Remember in thyroidectomy

- Middle thyroid vein is present only in 30% of cases.
- Bipolar cautery or harmonic scalpel (harmonic wave) are better to control bleeding and to prevent injury to RLN
- RLN should be identified in both sides. Variations should be remembered.
- Parathyroids should be retained and also their blood supply.
- Parathyroid autotransplantation may be needed if their blood supply is compromised.
- Rapid influx of serum calcium into bones in immediate postoperative period may cause severe hypocalcaemia – hungry bone syndrome which is initially corrected by IV calcium gluconate – 10 ml of 10%. It is more commonly observed in patients with beta blockers. It is due to sudden drop in PTH level after surgery.
- Tension haematoma under strap muscles is very dangerous and should be relieved by removing sutures from the skin and strap muscles. It can be life saving with immediate intervention otherwise it can be life threatening.
- Permanent hypoparathyroidism is rare (0.5-1%) even though temporary hypoparathyroidism and hypocalcaemia is common (25%) which is corrected well with calcium for certain period of 3-6 months.
- External laryngeal nerve injury is more common than RLN injury. There is loss of tension of vocal cords causing reduced power and range in voice (pitch).
- Thyroid insufficiency develops in 25-45% cases. It is confirmed by doing serum T3, T4 and TSH after 2, 3 and 6 months.

COMPLICATIONS OF THYROIDECTOMY

Complications can be intraoperative or immediate/in early post-operative period or late postoperative.

Haemorrhage (1%)

It may be due to slipping of ligatures either of superior thyroid artery or other pedicles or of small veins. It is often precipitated by vigorous coughing or retching in postoperative period. It causes tachycardia, hypotension, and breathlessness, tracheal compression due to progressive tension haematoma formation in thyroid fossa under sutured strap muscles causing severe respiratory obstruction, cyanosis, hypoxia, respiratory failure and cardiac arrest. Tension haematoma is a condition which is often missed in postoperative ward by the monitoring nurse or intensivist. Early identification of the problem with immediate bedside removal of skin and *deeper sutures* prevents further compression of the trachea relieving the respiratory obstruction. US of neck may be useful but unnecessary time should not be wasted just to do sonology. It is essentially life saving procedure which is often failed to undertake causing mortality. Later patient is shifted to operation theatre and wound is inspected under anaesthesia; bleeding vessel is caught and securely ligated. Often transfusion of blood is also required.

Respiratory Obstruction

It may be due to haematoma or due to laryngeal oedema or due to tracheomalacia or due to bilateral recurrent laryngeal nerve palsy. Evacuation of clot, emergency tracheostomy is required. *Fiberoptic laryngoscopy* is useful to assess the vocal cord palsy.

Recurrent Laryngeal Nerve Palsy

It can be *transient or permanent*. During extubation anaesthetist should be asked to visualise the movements of vocal cord to confirm that there is no recurrent laryngeal nerve injury. It should be documented both by anaesthetist and surgeon in the case sheet. Distressing change in voice should be assessed and treated by *steroid* (in case of neuropraxia), *speech therapy* and counseling. In malignant condition it is better to inform the patient about voice change as there would be possible need for transecting the nerve to clear the disease. However in benign diseases, nerve should be retained with all care. If nerve injury is identified on table during the procedure it *should be repaired* using microscope with 9 zero polypropylene sutures. Incidence of transient RLN palsy is 3%. It usually recovers in 3 weeks to 3 months. Permanent palsy is rare but do can occur. RLN palsy can be – unilateral; bilateral; unilateral combined RLN and external laryngeal nerve palsy; bilateral combined RLN and external laryngeal nerve palsy **(Fig. 15-43)**.

Unilateral RLN palsy causes median or paramedian vocal cord position. Here all intrinsic muscles of larynx except cricothyroid on one side are paralysed. Cricothyroid, which is the only retained muscle is a weak adductor of the vocal cord causing median or paramedian



Fig. 15-43: Recurrent laryngeal nerve should be identified in all thyroidectomies and safeguarded.

position of vocal cords (*Wagner–Grossman hypothesis*). Abductor fibres (nerve supply of posterior cricoarytenoid) of the RLN which are phylogenetically newer are more susceptible and paralysed than adductors (*Semon's law*). It causes change in voice (hoarseness) which gradually gets corrected by compensatory action of opposite vocal cord. Speech therapy will benefit for these patients. Short course of steroid in immediate postoperative period is used. 33% of unilateral RLN palsy patients are asymptomatic. Aspiration and airway obstruction will never occur **(Fig. 15-44)**.

Unilateral combined RLN and superior laryngeal nerve palsy - All muscles of larynx on one side is paralysed. Vocal cord will be in cadaveric position, 3.5 mm from the midline. It leads into hoarseness of voice, ineffective glottis causing aspiration, ineffective cough and respiratory congestion. Treatment is speech therapy, Teflon injection to paralysed vocal cord, placement of muscle/cartilage implant to paralysed cord, arthrodesis of cricoarytenoid joint.

Bilateral RLN palsy – Both side intrinsic muscles of larynx are paralysed except cricothyroids. Unopposed actions of both cricothyroids cause vocal cord in median/paramedian position. Condition causes voice change, severe dyspnoea, airway block and respiratory arrest. Treatment: Emergency tracheostomy; lateralisation of cord by arytenoidectomy; vocal cord lateralisation, cordectomy by open or laser method; sternohyoid implantation; thyroplasty.

Bilateral combined RLN and superior laryngeal nerve palsy – Here there will be total paralysis of the intrinsic muscles of larynx and total laryngeal anaesthesia, causing aphonia (no voice), severe glottis incompetence causing aspiration, absence of cough, retention of lung secretions leading into severe distress. It is treated by emergency tracheostomy, fixing epiglottis to arytenoids, vocal cord plication and often by total laryngectomy.

Assessing the vocal cord palsy – It is done by indirect laryngoscopy, direct fibreoptic endoscopy, laryngeal electromyography (EMG). EMG may be useful to distinguish vocal fold paralysis from injury to the cricoarytenoid joint secondary to intubation. EMG may help in assessing the prognosis of the patient with RLN injury. Thick connective tissue called the *Berry ligament* attaches the thyroid to the trachea at the level of the second or third tracheal ring. This is the most common site of injury to the RLN. The nerve may run deep to the ligament, pass through it, or even penetrate the gland a short distance at this level. Retraction of the thyroid lobe may result in traction injury and make the nerve susceptible to transection. The path of the nerve must be clearly identified. An endotracheal-tube electrode and an RLN-postcricoid-laryngeal surface electrode may be used in difficult thyroid surgeries to have continuous electrophysiologic monitoring to reveal the location of RLN. Proper identification of the RLN minimises the risk of injury. During thyroidectomy, when the nerve is identified and dissected, the reported RLN injury rate is 0-2.1%; if surgery is repeated (re-thyroidectomy) it is 2-12%; if the nerve is not identified it is 4-6.6%. Intraoperative haemostasis and a thorough understanding of the anatomy are essential for identifying and preserving the nerve.



Fig. 15-44: Different vocal cord positions and also RLN palsy.

Bilateral RLN palsy	***Most dangerous.***
Bilateral combined RLN and superior laryngeal N palsy	*Dangerous*.
Unilateral RLN palsy	Not dangerous.
Unilateral combined palsy	Not dangerous.

For unilateral vocal cord paralysis corrective procedures are not done until at least 6 months after thyroidectomy because a reversible injury improves by that time. If the nerve was definitely transected during surgery, treatment for the paralysed fold may be performed sooner than this.

Medialisation of the vocal cords is the most commonly performed. Medialization of the impaired vocal fold improves contact with the contralateral mobile fold. It is done by injection laryngoplasty or laryngeal framework surgery. Type I thyroplasty is probably the most common procedure. A window in the thyroid cartilage is created at the level of the true vocal fold. An implant is then placed to push the vocal fold medially. Medialization with an injection of absorbable gelatin sponge may be performed before 6 months. But gelatin sponge gets absorbed after sometime and is a temporary treatment.An implant made of silicone or polytetrafluoroethylene is permanent. The implant may be removed if nerve function recovers later.

Reinnervation procedures are done for permanently injured RLN. These procedures maintain/restore tone of the intrinsic laryngeal muscles. When the true vocal fold atrophies after denervation, it loses contact with the contralateral fold and the voice weakens. By preventing atrophy, re-innervation procedures help to improve the patient's voice.

Primary neurorrhaphy is done immediately to repair the transected RLN.

In bilateral vocal-cord paralysis, initial treatment involves obtaining an adequate airway by *emergency tracheotomy*. Often first endotracheal intubation is done; neck is explored to ensure that there are no reversible causes of nerve injury; if RLNs show good preservation, a trial of extubation may be performed after several days. Intravenous steroids are used. If nerve function has not recovered after a second trial of extubation, tracheotomy is certainly needed.

In bilateral vocal cord paralysis in order to improve airway patency, *cordotomy and arytenoidectomy* are the common procedures done. These procedures enlarge the airway and allow de-cannulation of a tracheostomy. However, the patient must be counseled that his or her voice will likely worsen after surgery.

Hypoparathyroidism—Types

Types		
Temporary	More common (2-50%) average 10%	Usually lasts for 2 months maximum up to 6 months.
Permanent	Less common (0.4-13%) average 1%	Permanent – continues beyond 6 months.
Hungry bone syndrome	Common (5-13%)	Severe, rapid begins in immediate postoperative period.

The parathyroid glands produce parathyroid hormone (PTH), which is involved in the regulation of serum calcium. PTH increases serum calcium levels by causing bone resorption, increasing renal absorption of calcium, and stimulating the synthesis of the biologically active form of vitamin D (1, 25-dihydroxy vitamin D). 1, 25-dihydroxy vitamin D increases serum calcium levels by increasing the intestinal absorption of calcium. PTH also increases renal excretion of phosphorous. Low PTH levels result in high serum phosphorous levels.

Inadequate production of PTH leads to hypocalcaemia. Hypoparathyroidism, and the resulting hypocalcaemia, may be permanent or transient. The rate of permanent hypoparathyroidism is 0.4-13%. Causes are - direct trauma to the parathyroid glands, devascularisation of the glands, or removal of the glands during surgery.

The rate of *temporary hypocalcemia* is reportedly 2-50%. The cause of transient hypocalcaemia after surgery is due to temporary hypoparathyroidism caused by reversible ischaemia to the parathyroid glands, hypothermia to the glands, or release of endothelin-1. Endothelin-1 is an acute-phase reactant which suppresses PTH production. Other hypothesis is - calcitonin release and hungry-bone syndrome. Calcitonin is produced by the thyroid C cells which inhibits bone breakdown while stimulating renal excretion of calcium (opposite of PTH).

Risk factors for hypocalcaemia after thyroidectomy include Graves disease, malignancy, type of procedure performed (total thyroidectomy, thyroidectomy with neck dissection, repeat thyroidectomy, subtotal thyroidectomy, near-total thyroidectomy).

Initially asymptomatic for 4-5 days, later develop circumoral paresthesia/numbness, change in mental status, tetany, carpopedal spasm,*Chvostek's sign* (tapping the region of the facial nerve in the preauricular area results in facial contractions), *Trousseau's sign* (carpal spasm that is elicited by inflating blood pressure cuff on the upper arm), laryngospasm (stridor), seizures, prolongation of QT on ECG, and cardiac arrest.

An effective method of evaluation of parathyroid function is to assess ionised calcium (or total calcium and albumin) levels in the perioperative period. A normal postoperative PTH level can accurately predict normocalcaemia after thyroid surgery. Immediate postoperative PTH level if <1.5 pmol/l and morning serum calcium <2.0 mmol/l, then patient is at risk of hypocalcaemia. Other causes like renal failure, hypomagnesaemia, medications should also be considered. Serum phosphorous levels are elevated in patients with hypoparathyroidism secondary to decreased renal excretion; this difference may help in distinguishing low PTH levels due to other etiologies of hypocalcaemia. PTH levels may be checked repeatedly till 6 months during the follow up period. Identifying the glands on table and maintaining their blood supply is essential and also crucial to prevent hypoparathyroidism. 77% of superior parathyroid glands were at the cricothyroid junction and intimately associated with the RLN; 22% were on the posterior surface of the upper lobe of the thyroid; 1% was behind the junction of the hypopharynx and upper oesophagus.

Location of the inferior parathyroid glands was variable. 42% were on the anterior or lateral surfaces of the lower lobe of the thyroid, hidden by vessels or creases in the thyroid; 39% were located within the superior tongue of the thymus. 15% were extra-thyroidal and lateral to the lower lobe; 2% were in the mediastinal thymus; another 2% were in other ectopic positions, such as in the carotid sheath.

The inferior parathyroid glands and the thymus both develop from the third branchial pouch, causing close association of these structures. The inferior parathyroid glands receive their blood supply from the inferior thyroid artery. The superior parathyroids also usually receive their blood supply from the inferior thyroid artery. The superior parathyroids may also receive their vascular supply from the superior thyroid artery, the anastomotic loop between the inferior and superior thyroid arteries, or direct branches from the thyroid gland.

The parathyroids should be identified and their blood supply should be preserved by ligating all vessels distal to them. The vessels are ligated as close to the thyroid gland as possible. The parathyroid glands are identified by their *caramel-like* colour and size. When blood supply of parathyroids is lost, they appear darkened. The surgical wound and the excised thyroid gland should be carefully examined for parathyroid tissue. The devascularised gland (pathologically confirmed with frozen-section), should be removed, cut into 1- to 2-mm pieces, and re-implanted into the sternocleidomastoid muscle or strap muscle. The location may be marked with a permanent suture or a metallic hemoclip for easier identification in any future surgeries.

Patients who have *asymptomatic hypocalcaemia* in the early postoperative period *should not* be treated with supplemental calcium. The hypocalcaemic state may stimulate the parathyroid glands to produce PTH.

Patients who have *symptomatic hypocalcaemia* in the early postoperative period or whose calcium levels continue to fall rapidly need treatment. In symptomatic patients, intravenous calcium gluconate 10 ml 10% solution (1 gm) is administered over 10 minutes. A calcium infusion is started at a rate of 1-2 mg/kg/h if symptoms do not resolve. Rate of infusion is decided by repeated analysis of serum calcium and clinical features. One to two grams of elemental oral calcium should be given each day. Calcium carbonate 1250 mg provides 500 mg of elemental calcium; the patient should take 2500-5000 mg/day. The patient needs vitamin D supplementation with calcitriol 0.25-1 mcg/d. The calcium supplementation should be divided 4-5 times per day rather than in a single dose to maximise absorption by the GI tract.

In 2 months, trial weaning of oral calcium can be made to identify whether the hypoparathyroidism is temporary. Need for calcium supplementation longer than 6 months, indicates *permanent* hypoparathyroidism.

Hungry Bone Syndrome

It occurs usually in patients with preoperative hyperthyroidism. They have increased bone breakdown in their hyperthyroid state. When a patient's thyroid hormone level drops acutely after surgery, stimulus to breakdown bone is removed. The bones are now "hungry" for calcium, remove calcium from the plasma rapidly.

It usually occurs after parathyroidectomy; thyroidectomy for toxic thyroid; prostate cancer patients on estrogen therapy. Sudden cessation of existing increased bone breakdown makes bones to absorb calcium, magnesium and phosphorus rapidly. Calcium levels in blood prior to operation cannot predict hungry bone syndrome. Hypocalcaemia, hypophosphataemia, hypomagnesaemia and hyperkalaemia are four typical features in these patients. Estimation and correction of all these four factors is essential. ECG changes can occur. Hyperkalaemia should be treated judicially. Magnesium infusion is needed. There is an unusually high need for calcium, with a low calcium excretion in the urine. Bone-specific alkaline phosphatase (ALP) continues to rise in the first few weeks indicating increased bone reconstruction. Supplementation of vitamin D and elemental calcium is needed during discharge for 6 months. Postoperatively they need calcitriol (gradually increased to 16 mg in 1 month, then gradually can be reduced) with 2 gm calcium supplement. Monitoring is done by evaluating serum calcium, albumin, magnesium, and phosphorus and bone specific alkaline phosphatase.

Thyrotoxic Storm/Crisis

Thyrotoxic storm is an unusual complication of thyroid surgery. This condition may result from manipulation of the thyroid gland during surgery in patients with hyperthyroidism. It can develop preoperatively, intraoperatively, or postoperatively. It is observed in thyrotoxic patients who are inadequately prepared/controlled; it begins due to surgery (thyroidectomy) or any other stress or operations other than thyroidectomy. Thyrotoxic storm is potentially lethal and must be dealt with utmost care. It can be seen in toxic nodule or toxic nodular goitre or more commonly in Grave's disease. Mortality is more than 50%. There is exacerbation of hyperthyroidism with decompensation of organ systems.

Features

Features of thyrotoxic storm in the anaesthetised patient include evidence of increased sympathetic output, such as tachycardia and hyperthermia. In an awake postoperative patient features are nausea, tremor, severe dehydration, circulatory collapse, hypotension, hyperpyrexia, out of proportion tachycardia, cardiac arrhythmias/failure and altered mental status. Cardiac arrest may also occur. If treatment is not adequate, the patient may progress to coma. Prevention is by restoring the thyroid status as close to euthyroid as possible. Morbidity and mortality rates in adequately prepared patient are low.

Intraoperative Management

The first step in managing a thyrotoxic crisis during thyroidectomy is to stop the procedure. Intravenous beta-blockers, PTU, sodium iodine, and steroids are administered to control sympathetic activity, the release of thyroid hormone and hyperthermia. Cooling blankets and cooled intravenous fluids are used to reduce the patient's body temperature. Oxygen demand increases dramatically during a thyroid storm.

Treatment of thyrotoxic crisis postoperatively

- Injection hydrocortisone 500–1000 mg intravenously.
- Proper fluid therapy to maintain hydration, blood pressure.
- Control of hyperpyrexia by total body sponging, cooling blankets, cooled intravenous fluids, steroids (dexamethasone), antipyretic injections.
- Sedation using chlorpromazine.
- Digoxin and diuretic therapy with monitoring of blood pressure.
- Intravenous heparin in case of atrial fibrillation.
- Beta blockers – oral propranolol – 80 mg 4th to 6th hourly (through nasogastric tube if needed); or oral diltiazem. Heart rate should be kept below 100/minute. Often to achieve this intravenous esmolol may be needed. Refractory cases require reserpine therapy.
- Antithyroid drugs – orally. Propylthiouracil or methimazole or carbimazole is given. Lugol's iodine is given 4 hours after propylthiouracil. Injection propranolol also can be given.
- Plasmapheresis and charcoal plasma perfusion or exchange perfusion is used if patient does not respond in 48 hours.
- Intravenous injection of sodium iodide 1 gram is often used.
- ICU care, oxygen, ventilator support, cardiac monitoring; electrolyte/blood gas/liver and renal function/thyroid hormone estimation at regular intervals is needed.
- Prevention of second episode of crisis by continuing the therapy is needed.

External Laryngeal Nerve Injury

The superior laryngeal nerve has two branches—internal and external. The internal branch provides sensory innervation to the larynx. It enters the larynx through the thyrohyoid membrane and not at risk during thyroidectomy. The external branch supplies cricothyroid muscle after passing through cricothyroid space of *Reeves* and is at risk during thyroidectomy. This muscle causes elongation of the vocal folds (tensor). Injury to this branch causes inability to lengthen the vocal fold and creates a high-pitched sound. The external nerve is probably the nerve most commonly injured in thyroid surgery (0-25%).

Features

Most patients do not notice any change. Patient may present with mild hoarseness or decreased vocal stamina. However, for a singer or a person who professionally relies on his or her voice (teachers), paralysis of this nerve may threaten his or her career. The most damaging consequence is loss of the *upper* register.

Diagnosing an external laryngeal nerve injury with indirect or fiber-optic laryngoscopy is difficult. Posterior glottic rotation towards the paretic side and bowing of the vocal fold on the weak side may be noted. The affected vocal fold may be lower than the normal vocal fold. Use of videostroboscopy and laryngeal EMG will help to diagnose ELN paralysis. Videostroboscopy demonstrates an asymmetric, mucosal traveling wave. EMG demonstrates denervation of cricothyroid muscle.

Prevention and Treatment

The external branch of SLN travels inferiorly along the lateral surface of the inferior constrictor until it terminates at the cricothyroid muscle. This branch is intimately related to the superior thyroid artery, though its exact relation to the artery varies. Study suggests that the nerve may cross the superior thyroid artery more than 1 cm above the upper pole of the thyroid gland (42%), less than 1 cm above the upper pole (30%), or under the upper pole (14%). In some people, the nerve runs dorsal to the artery and crosses only its terminal branches after the artery has ramified (14%). The critical area, 1.5-2 cm from the thyroid capsule is described. In this area, the ELN is most intimately involved with the branches of the superior thyroid artery.

Most surgeons agree that identifying the ELN, in contrast to the RLN, is unnecessary even though by principle it is ideal and must. Instead the terminal branches of the superior thyroid artery are ligated as close to the thyroid capsule as possible to avoid nerve damage. Direct trauma to the cricothyroid muscle can cause fibrosis and poor muscle function, which may result in a presentation similar to that of a patient with an injury to the ELN, even when the nerve is preserved. Therefore careful dissection near this muscle is advised to avoid damage due to electrocautery. Treatment for ELN palsy is speech therapy.

Hypothyroidism

Systemic thyroid hormone levels are low in hypothyroidism. It may be *primary* due to thyroidectomy/radioactive iodine ablation/primary thyroid diseases or may be *secondary* due to hypopituitarism or *tertiary* due to hypothalamic diseases.

Presentation

Untreated hypothyroidism causes symptoms such as cold intolerance, fatigue, constipation, and muscle cramping, brittle hair, dry skin, sluggishness, hypothermia and weight gain. CVS manifestations are important which present as bradycardia, hypotension and conduction problems and pericardial effusion. Hypothyroidism secondary to thyroid surgery should never be left untreated long enough to elicit signs and symptoms of myxoedema (e.g. hair loss, large tongue, cardiomegaly). One should suspect, diagnose and promptly treat postoperative hypothyroidism.

Hypothyroidism will worsen the situation of critically ill patient causing severe pulmonary dysfunction, pleural effusion and hypothermia.

Renal insufficiency can occur in hypothyroidism and so renal function tests should be done.

Evaluation

The most useful laboratory test for detecting or monitoring hypothyroidism in a patient whohas undergone thyroidectomy is the measurement of thyrotropin, thyroid-stimulating hormone (TSH) levels. Total T4 and T3 levels may be useful to fine-tune the dosing of levothyroxine, but may be unhelpful in the typical postoperative patient. In primary type T4, free T4, free T3 are low; but TSH level is high. In secondary type, free T4 index, free T3 and TSH are all low. *Adrenal insufficiency* is associated with *secondary* type.

Features of myxoedema coma	*Precipitated by*	*Treatment*
Hypothermia – skin is *deadly cold* like a toad. Hypotension Hyponatraemia Hypoventilation Hypoglycaemia Bradycardia Loss of tendon reflexes Cardiopulmonary collapse Coma	Cold infection, trauma.	Drug of choice – IV T3 10 µg Levothyronine 300 µg IV; later 1000 µg orally – large dose. Glucocorticoids – IV Antibiotics Slow warming Fluid and electrolyte therapy Monitoring; ICU care; ventilator

Prevention

Hypothyroidism is an expected sequelae of total thyroidectomy. In goitre surgery, the extent of thyroidectomy is controversial. The main goal of surgery is to prevent recurrent hyperthyroidism because recurrent hyperthyroidism after surgery is more difficult to manage than permanent hypothyroidism. Because of this fact, the present authors recommend total thyroidectomy in this setting.

Treatment

Levothyroxine (about 1.7 mcg/kg/d) 100-150 µg/daily (single dose, morning) is started. Their thyrotropin level is checked in 4-6 weeks to adjust the dosage. Patients who are to receive postoperative radioiodine therapy with scanning must stop taking levothyroxine before the procedure. In cardiac patients initially 50 µg/day is started; later gradually increased to required dose.

In myxoedema coma, IV hydrocortisone, IV levothyroxine, IV levothyronine is started.

Types of hypothyroidism
Primary – Thyroidectomy or thyroid diseases like thyroiditis – free T4, T4, and free T3 are low; TSH is high.
Secondary – Hypopituitarism – TSH, free T3 are low.
Tertiary – Hypothalamic diseases.

Presentations
Asymptomatic.
Chronic hypothyroidism status.
Myxoedema coma – Acute presentation with loss of deep tendon refluxes, respiratory problem, cardiac irregularities, coma with 50% mortality.

Causes
- Agenesis or dysgenesis.
- Enzyme deficiency.
- Iodine deficiency.
- Hashimoto`s thyroiditis.
- Antithyroid drugs.
- Radioiodine.
- Drugs: Lithium, Amiodarone.
- *After thyroidectomy.*

Clinical features
- *General:* Tiredeness, weight gain, cold intolerance, goitre, hyperlipidaemia.
- *Cardiovascular:* Bradycardia, angina, cardiac failure, pericardial effusion.
- *Haematological:* Anaemia.
- *Dermatological:* Dry skin, vitiligo, alopecia, erythema.
- *Reproductive:* Infertility, menorrhagia, galactorrhoea.
- *Gastrointestinal:* Constipation, ileus.
- *Developmental:* Growth and mental retardation, delayed puberty.
- *Other features:* Carpal tunnel syndrome, myalgia, hoarseness, deafness, ataxia, depression, psychosis (myxoedema madness).

Infection

Infection is rare due to good aseptic methods. Perioperative antibiotics are used in many centres. Bleeding from vascular thyroids, haematoma, infected suture material are the causes of infection. In large malignant thyroid during thyroidectomy injury may occur to oesophagus which causes severe localised sepsis in the neck. Gastrografin study, CT scan/MRI may reveal the site and extent of the injury. Pus culture, starting higher generation antibiotics, nasogastric tube insertion, and endoscopic identification of the injured area are needed management in such rare patients. Usually they recover but may need to keep the nasogastric tube (feeding can be done through the tube) for few weeks.

Recurrent Thyrotoxicosis

Recurrent thyrotoxicosis is difficult to manage. It is more common with subtotal thyroidectomy (4-15%) than with total thyroidectomy. So at present, total thyroidectomy is commonly done for toxic thyroid. Management is proper anatomical assessment of the residual thyroid tissue by using radioisotope scan, MRI neck and radioactive iodine ablation of residual thyroid tissue if patient's age is more than 45 years or surgical reexploration and complete removal of residual thyroid tissue on both sides. It carries higher risk of injury to recurrent laryngeal nerve and parathyroids. Meticulous dissection, adequate exposure and proper retraction is needed.

Minor Complications

Small seromas can be left as such to resorb. Large seroma may require repeated aspirations. Wound infection and poor scar are other complications.

Minimally Invasive Video-assisted Thyroidectomy

Minimally Invasive Video-assisted Thyroidectomy (MIVAT) is becoming popular for small nodules and gland without thyroiditis. But it is costly.

The development of videolaparoscopic surgery in the last decade has allowed several operations to be performed with minimally invasive techniques. After the first parathyroidectomy procedure performed endoscopically in 1996, this minimally invasive approach was applied to thyroid surgery. MIVAT was described in 1998. The technique was described using a central access with a 1.5 cm incision and external retraction. Postoperative morbidity rates in patients seem to be equivalent to those of patients who have undergone conventional surgery.

Chao et al (2004) prospectively compared video-assisted thyroid lobectomy and conventional lobectomy in 116 patients with thyroid nodules. Transient RLN palsy occurred in 5 (8.5%) patients who underwent conventional surgery versus 3 (5.8%) patients in the video-assisted group; the difference was not significant. Patients in both groups were discharged home on the second postoperative day.

In a 5-year study, Miccoli et al (2004) selected 579 patients to undergo MIVAT.The operation consisted of total thyroidectomy in 312 patients and lobectomy in 267. The mean operative time was 41 minutes (range, 15-120 min) for lobectomy and 51.6 minutes (range, 30-140 min) for total thyroidectomy. The postoperative hospital stay was 24 hours (overnight discharge) for all patients. Complications included postoperative bleeding (0.1%), recurrent nerve palsy (1.3%), and definitive hypoparathyroidism (0.2%). Some have suggested that pain following VAT is less when compared to conventional thyroidectomy because of limited dissection, retraction, and injury to tissues.

MIVAT provides endoscopic magnification of nerves and vessels, potentially decreasing the risk of injury to these structures. The endoscopic technique cannot be used in nodules larger than 3.5cm because the specimen is too large to retrieve through the incision. In addition, this technique is not ideal for removing carcinomas in which an intact capsule is desired for oncologic reasons and for accurate histological assessment.

In summary, if the general principles of conventional thyroid surgery are followed, video assistance may help in identifying structures and in minimising the incision. Experienced surgeons may consider using this technique when the equipment and additional surgical staff is available for patients with small follicular nodules/adenomas, or well-differentiated papillary carcinoma, or when prophylactic thyroidectomy is being performed in oncologically needed patients.

PARATHYROID SURGERY

Surgical Anatomy of Parathyroid

Two pairs of parathyroids are located within the false capsule and posterior border of thyroid gland. Superior parathyroids develop from endoderm of 4th pharyngeal pouch and called as *parathyroid IV*; inferior parathyroids are called as *parathyroid III* (3rd pouch). Each parathyroid is lentiform/pea sized in shape with 6 × 4 ×2 mm in size weighing 50 mg and red brown in colour. Glands lie in close relation to anastomotic branch of superior and inferior parathyroid arteries. *Superior* usually lies in constant position at the middle of posterior border of the thyroid, *behind recurrent laryngeal nerve*. *Inferior* lies in variable positions – within the thyroid capsule below the inferior thyroid artery/outside the thyroid capsule above the inferior thyroid artery/within the thyroid substance in posterior border. Inferior is usually *in front of the recurrent laryngeal nerve*. Inferior parathyroid and thymus develop from 3rd pharyngeal pouch and so can also be occasionally located in mediastinum. Parathyroids receive their blood supply from inferior thyroid artery (80%) and anastomotic artery. Single end artery is the common method of supply **(Fig. 15-45)**.

Glands (chief cells) secrete parathormone (PTH) which controls the calcium metabolism.

PTH

- Increases absorption of the calcium from the gut.
- Mobilises calcium from the bone.
- Increases the calcium reabsorption from the renal tubules.
- Half life is 4 minutes.

Indications for Parathyroidectomy

Primary hyperparathyroidism – Criteria (2002) for surgical intervention are –raise in serum calcium level more than 1 mg/dl of upper limit of the normal calcium range; 24 hour urinary calcium if more than 400 mg; creatinine clearance when reduced more than 30%; bone density greater than two standard deviations below peak bone mass in lumbar spine/hip/lower end of radius; age below 50 years; when medical therapy is not possible.

Common cause for primary HPT is single benign parathyroid adenoma (85%). 95% of such adenomas are single in one gland. 5% cases are having double adenomas each one in two glands. Proliferation causing hyperplasia involving all four glands (15%) also causes primary HPT. This type may be associated with MEN syndrome type I and IIA. Slow growing invasive parathyroid carcinoma accounts for 1% of primary HPT.

Four dimensional CT, PET scan, Technetium 99m sestamibi scintigraphy are the present methods of evaluation in these patients. On table methylene blue injection (5 mg/kg over an hour infusion) will make only the parathyroid gland blue to identify it.

Secondary HPT is an indication for removal of all four glands with autotransplantation of parathyroid only in severe cases or with renal osteodystrophy.



Fig. 15-45: Anatomy of parathyroid glands.

Indications for parathyroidectomy

- Severe symptoms
- Young age group
- Markedly reduced bone density
- Serum calcium more than 11 mg %
- Urinary calculi
- Neuromuscular presentations
- Urinary calcium more than 400 mg/24 hours

Preoperative Preparation

Vocal cords should be assessed by preoperative indirect laryngoscopy.

High calcium levels preoperatively may require treatment with hydration; diuresis; steroids (prednisolone 20 mg TID for 5 days before surgery); 100 mmol phosphate infusion in 6 hours; 200 units calcitonin subcutaneous injection for 5 days twice daily before surgery; diphosphanate – etiodronate disodium 7.5 mg/kg daily as slow IV infusion for 3 days; mithramycin 25 µg/kg as single dose.

Anaesthesia and Position

General anaesthesia is used with neck hyperextension by placing rolled sheet under the shoulder blades. Head is placed on the head – ring; head end of the table is raised to semi–erect position (*Semi-Fowler position).*

Incision and Dissection

It is same as for thyroidectomy. Flaps are raised in similar way. Strap muscles are separated after opening the deep fascia in the midline. Thyroid gland is mobilized to identify the parathyroid adenoma. Parathyroid having adenoma is mobilized which is close to recurrent laryngeal nerve. End artery of the parathyroid is identified and ligated. Adenoma is separated from adjacent thyroid tissue using gauze dissection. Either on table venous sampling for PTH assay is done or venous sample from cubital vein is done for PTH assay.

Parathyroid may be confirmed by frozen section biopsy or on table aspiration of parathyroid tissue which is analyzed for PTH assay which will be more than 1500 pg/ml (confirms removed tissue as parathyroid).

Total parathyroidectomy is done for parathyroid hyperplasia by removing all four glands and ⅓ of one gland is autotransplanted into the forearm muscle (brachioradialis) or sternocleidomastoid muscle with marker stitch. Transplanting gland is sliced into 1 mm pieces and around 18 pieces are embedded in decided muscle with a marker stitch or clip. If in postoperative period patient still presents with primary HPT features; transplanted area is re-explored and further reduction in parathyroid tissue is done.

Wound is closed with proper haemostasis.

Effects of Surgery

Among neuromuscular symptoms of primary HPT, proximal muscle weakness responds better than respiratory muscle weakness by parathyroidectomy.

Among psychiatric illnesses, depression and spatial learning and processing improve well by surgery.

Complications

Haemorrhage, recurrent laryngeal nerve palsy, hypocalcaemia and hungry bone syndrome are known to occur.

Persistent HPT (serum calcium is not normalized immediately after surgery leading total failure) or *Recurrent HPT* (serum calcium after surgery becomes normal but in 6-12 months, it again increases) may be a problem.

Hypoparathyroidism with severe hypocalcaemia is a problem when all glands are removed (3½) with bilateral neck exploration. 10 ampoules of calcium gluconate is diluted with one liter of normal saline and given as continuous infusion at a rate of 30 ml/hour – initial method of management. Hypomagnesemia should also be corrected.

Migration or inability to identify the transplanted parathyroid is often a problem in autotransplantation of parathyroid.

Bone mineral density in hip and lumbar spine becomes better.

Nephrocalcinosis is improved by surgery; but hypertension and renal excretion will not improve much.

Half life of PTH is 4 minutes. On table serial PTH assays are done at several intervals – before dissection of the gland, during dissection and after dissection. 50% reduction in PTH level from baseline in post removal sample is a 96% predictor of complete removal.

Operative failure rate is 1.5 to 6%. Intra-operative PTH assay improves the success rate very much (76% to 94%). Cure rate is defined as normocalcaemia in 6 months postoperative period.

Radio guided parathyroidectomy using intravenous injection of 20 mCi of 99mTc sestamibi 2 hours before surgery is not routinely practiced but may be useful for removal of adenoma appropriately. Hand held quantitative gamma counter is used intraoperatively on the neck over all parathyroid tissues.

- Primary HPT is commonly sporadic than familial
- Histological difference between adenoma and hyperplasia is difficult to assess
- Gross on table look is preferred method
- Adenoma is usually single. Multiple adenomas occur in elderly
- Hyperplasia involves all four parathyroids
- Parathyroid cyst may be developmental/secondary to degeneration of nodule or adenoma. Cyst aspiration shows clear fluid with high PTH level in the content fluid
- Preoperative IV methylene blue 5 mg/kg in 500 ml dextrose saline which stains parathyroids is often used to localize glands
- 50 mg of one gland is sufficient to maintain function
- Persistent HPT is one in which HPT persists immediately even after initial surgery,
- Recurrent HPT (initially after first surgery HPT is corrected but recurs 6 - 12 months after surgery) is due to parathyromatosis, development of new adenoma, and hyperplasia of transplanted parathyroid. *Parathyromatosis* is due to rupture and spillage of parathyroid tissue in neck, mediastinum and forming functioning nodules there
- Re-exploration and removal in persistent/recurrent HPT needs on table PTH assay. On table PTH level drop more than 50% of preoperative value indicates the success of surgical removal
- CT, MRI, PET scan and selective angiography are usually done only for recurrent diseases

Problems in parathyroidectomy

- Permanent hypoparathyroidism
- Recurrent hyperparathyroidism-hypercalcaemia 12 months after parathyroidectomy
- Recurrent laryngeal nerve injury
- Often needs additional thyroidectomy
- Variations in positions of the gland especially lower—may be in mediastinum
- Sudden drop in calcium level after surgery due to increased absorption of calcium by bones—***hungry bone syndrome***.

Approaches

Classic Approach (Traditional Approach)

It is under general anaesthesia exploring bilateral neck to remove parathyroid tissue which is confirmed by frozen section biopsy. It shows 95% cure rate with 2% complication rate.

Minimally Invasive Parathyroidectomy (MIP)

It is done in case of *single adenoma* of parathyroid under regional cervical block anaesthesia usually in ambulatory set up. It is actually unilateral parathyroidectomy with removal of adenoma and involved entire that particular one parathyroid gland using limited neck exploration (small incision of 2-4 cm). Procedure is not useful in multiple adenomas or hyperplasia. Preoperative localization with sestamibi combined with SPECT is a must. Intraoperative PTH assay is a must to confirm drop in PTH level to required level. Cervical block is given by infiltrating the xylocaine (1%) with adrenaline along posterior and deep to sternocleidomastoid muscle and also along the neck incision. Direct field block along the anterior border of the sternocleidomastoid and over the incision is also used. Postoperative serum calcium and PTH level should be assessed until 7th day.

Median Sternotomy (3%) Extension

Median sternotomy is often needed when parathyroid is in anterior mediastinum along with thymus. Often parathyroids may be 5, 6 or 7 in numbers instead of four.

Video-assisted Parathyroidectomy (Paolo Miccoli)

It is done in *localized single adenoma* using multiple ports on one side with intermittent CO_2 insufflation and suction irrigation. 1.5 cm incision 1 cm above the sternal notch helps in tactile assessment and dissection. Strap muscles are retracted laterally and thyroid is retracted medially. Conversion rate is 11%; RLN palsy is 2%.

Endoscopic Parathyroidectomy

Entire parathyroidectomy is done using laparoscopy. It is first used (1994) for a mediastinal parathyroid adenoma. In 1996, it was used for neck parathyroid hyperplasia by Gagner for removing 3½ glands. Now technique is *limited to single adenoma* to remove tumour and gland. Low pressure insufflations with 5 mm four trocars are used. Placement of trocars is dependent on the need of the operating surgeon. Many place trocars on one side only; but few prefer to place working trocars on opposite side.

Remedial Parathyroidectomy

It is done for persistent HPT (serum calcium is not normalized immediately after surgery leading total failure) or recurrent HPT (serum calcium after surgery becomes normal but in 6-12 months, it again increases). It is done through lateral approach (*Feind*) between anterior margin of sternocleidomastoid and strap muscles so that scar tissues are avoided from initial dissection. On table localisation methods, on table PTH assay are needed. Median sternotomy often may be needed to explore the mediastinum for complete removal of the gland. Parathyroids in such situations may be embedded in the tissue of thyroid or thymus. So removal of these glands also may be a need in such situations.

Subtotal Parathyroidectomy

It is indicated in hyperplasia or secondary HPT wherein 3½ glands are removed, retaining ½ of one gland.

Total Parathyroidectomy with Parathyroid Autotransplantation

It is done alternatively in hyperplasia wherein all four glands are removed; ⅓ or ½ of one gland is transplanted into sternocleidomastoid or brachioradialis muscle with a marker. Disease control will not occur if more part of the gland is transplanted. It is removing all four glands and 1/2 or 1/3 of one gland is autotransplanted into the forearm muscle (brachioradialis) or sternocleidomastoid muscle with marker stitch. Transplanting gland is sliced into 1 mm pieces and around 18 pieces are embedded in decided muscle with a marker stitch or clip. If postoperatively still patient presents with primary HPT features; transplanted area is re-explored and further reduction in parathyroid tissue is done. Migration or inability to identify the transplanted parathyroid is often a problem in autotransplantation of parathyroid.

PARATHYROID CARCINOMA

It is rare but shows marked hypercalcaemia (more than 14 mg/dl). Renal and bone complications are more common. Palpable neck swelling, features of hypercalcaemia, high PTH level are typical. Lymph nodes in neck may be involved. Tumour is large grayish white, invasive to adjacent thyroid. Distant spread occurs to lung, liver and bone. *En bloc parathyroid resection, ipsilateral thyroid lobe removal, adjacent soft tissue resection* along with ipsilateral neck lymph node dissection if needed – is the treatment. Simple parathyroidectomy should not be done as it shows high recurrence rate (50%) and spread. Recurrence rate for en bloc removal is 8%. Nodal and distant spread carries poor prognosis. *Cinacalcet* (30-180 mg/day) is used for symptomatic control of hypercalcaemia. Removal of metastatic area may be needed to control severe hypercalcaemia. Chemotherapy is not useful. External radiotherapy may be used to neck and metastatic area; but results are not adequate.



Figs 15-46(1)



Figs 15-46(2)



Figs 15-46(3)

Figs 15-46: Technique of parathyroidectomy for adenoma in two different patients.

Chapter 16

Surgeries for Breast Diseases

SURGICAL ANATOMY OF BREAST

Breast, a *modified sweat gland* lies in superficial fascia in pectoral region with a small extension called as *axillary tail of Spence* into the axilla through *foramen of Langer* in deep fascia. It extends from 2nd to 6th rib; from lateral border of sternum to midaxillary line. Deep to breast, structures related are – retromammary space containing loose areolar tissue, pectoral deep fascia, muscles (pectoralis major, serratus anterior, external oblique), chest wall **(Fig. 16-1)**.

Retromammary bursa/space is located between deep layer of superficial fascia and pectoral (deep) fascia allowing free mobility of breast.

Nipple is located at the level of 4th intercostal space just below the centre/summit of the breast. It contains circular and longitudinal muscles to make nipple stiff or flat. It is pierced by 15 – 20 lactiferous ducts. Each duct independently opens into the nipple. It has rich sensory nerve endings. It also contains modified sweat and sebaceous glands. Nipple is supplied by 4th intercostal nerve.

Areola is circular pigmented area around the nipple. It is rich in modified sebaceous glands which enlarge during pregnancy and lactation as *Montgomery tubercles*. They secrete oily lubricant to nipple and areola. Areola and nipple do not contain hair and fat beneath.

Breast parenchyma contains 15-20 lobes. Each lobe contains alveoli, lactiferous sinus and lactiferous duct. Alveolus is lined by cuboidal (in rest) and columnar (in lactation); smaller duct is by single layer columnar; larger ducts by many layered columnar; lactiferous duct (2-4 mm in diameter) is by stratified squamous epithelium. *Myoepithelial cells* lie between epithelium and basement membrane from alveoli to duct. *Stroma* contains fibrous tissue and fat. Fibrous stromal septa, anchoring from skin to pectoral fascia, is called as *suspensory ligament of Cooper*. Fat is distributed all over the breast *except* under nipple and areola **(Fig. 16-2)**.

Arterial Supply

It is by - Internal thoracic mammary artery (60%), branch of subclavian artery through its perforators; lateral thoracic (30%), superior thoracic and acromiothoracic branches of axillary artery; lateral branches of posterior intercostal arteries. Thoracodorsal branch of subscapular artery is not supplying the breast but its location and pathway is



Fig. 16-1: Axillary tail of Spence, located deep to deep fascia, is an extension of main breast from superficial fascia through foramen of Langer.



Fig. 16-2: Cooper's ligament.

important because it is very close to central and scapular (posterior) axillary lymph nodes. So during lymph node dissection injury of this vessel can cause significant damage; and it is essential to retain this branch. If LD flap is needed at a later period **(Fig. 16-3)**.


Axillary artery
Superior thoracic artery
Acromiothoracic artery
Lateral thoracic artery (30%)
Branches of intercostal arteries
Perforating branches of internal thoracic (mammary) artery—a branch of subclavian artery—60% supply

Fig. 16-3: Arterial supply of breast.

Venous return is by - Posterior intercostals with perforating branches which is also in continuity with Batson's vertebral plexus; axillary vein (primary); internal mammary vein. Venous network form an anastomotic venous circle near base of the nipple which eventually sets into superficial and deep veins. Superficial veins drain into internal thoracic vein; deep into internal thoracic, axillary and posterior intercostal veins.

Nerve supply of breast is from anterior and lateral cutaneous branches of the 4th to 6th intercostal nerves. They supply skin, smooth muscles, and blood vessels. They do not control milk secretion. Nipple is supplied by 4th intercostal nerve.

Milk secretion is controlled by prolactin.

Lymphatic drainage of breast – Superficial lymphatics drain skin over the breast except nipple and areola. Deep lymphatics drain parenchyma, nipple and areola. 75% drain into axillary nodes; 20% into internal mammary nodes (parasternal – along internal thoracic vessels deep to the costal cartilage); 5% to posterior intercostal nodes. In axilla, lymphatics mainly drain to pectoral nodes (anterior/external mammary along the lateral thoracic vessels); then to posterior (along subscapular vessels), lateral (along axillary vein), central (in the fat in centre of the axilla) and apical (subclavicular/*Halsted)* nodes (along pectoralis minor tendon). Supraclavicular, deltopectoral (cephalic), posterior intercostal nodes, subdiaphragmatic lymph plexus are other drainage areas. Sappey's subareolar lymphatic plexus drains into pectoral group of lymph nodes. Central group is the *most properly clinically palpable* axillary node. *Internal mammary nodes* are located in retrosternal intercostal spaces 1-2 cm lateral to the sternal margin; it is vertically placed parallel to internal mammary vessels in relation to endothoracic fascia; its efferent ends in subclavicular nodes.

Intercostal lymph nodes are located posteriorly in intercostal spaces near the origin of ribs. Its efferent drains into the right lymphatic duct or thoracic duct.

Diaphragmatic nodes are located on the thoracic surface of the diaphragm. Anterior prepericardial nodes are located under xiphoid process; lateral one is located on each side, right side near IVC, left side near oesophageal hiatus; posterior group is located near crura of diaphragm.

Axillary reverse mapping (ARM) – Here blue dye is injected on inner upper part of the arm to achieve a mapping of axillary lymphatic drainage **(Fig. 16-4)**.



- 75% of lymph from breast drain to axillary nodes
- 20% into internal mammary nodes
- 5% to posterior intercostal nodes
- Internal mammary drains not only from inner but also from outer quadrant
- Lymphatics from deep part of breast pass through PM muscle and clavipectoral fascia to reach apical nodes and internal mammary nodes
- Lymphatics from lower inner quadrant of the breast communicate with subdiaphragmatic and peritoneal lymphatics across costal margin and linea alba.

Fig. 16-4: Lymphatic drainage of the breast.

Axilla

Axilla is pyramidal in shape with apex, base and four walls – anterior, posterior, medial and lateral. Apex (*cervicoaxillary canal*) is bound by clavicle, scapula and outer border of first rib. Anterior wall is formed by pectoralis major, clavipectoral fascia; posterior wall by subscapularis, teres major and latissimus dorsi; medial wall by upper four ribs with intercostal muscles, upper part of serratus anterior muscle; lateral wall by shaft of humerus, coracobrachialis, short head of biceps. It contains axillary artery with its branches, axillary vein with its tributaries, axillary groups of lymph nodes, and long thoracic nerve of Bell to serratus anterior, intercostobrachial nerve, fat and fascia. Subscapular vessels run along the lower border of the subscapularis with its nerve and thoracodorsal nerve. Medial wall is related to long thoracic nerve and intercostobrachial nerve. Anterior/pectoral group of lymph nodes lie along the lower border of pectoralis minor on lateral thoracic vessels. Lateral group of nodes lie posteromedial to axillary vein. Central group lies in the fat of the axilla towards medial side. Apical nodes lie behind, above the pectoralis minor, medial to axillary vein. *Axillary sheath* covers axillary artery and brachial plexus *but not* axillary vein.

Note: A communicating vein between cephalic vein and external jugular vein (neck) is present which runs across the clavicle. It is important in draining the upper limb in axillary vein removal (in carcinoma breast, segment may be removed)/blockage **(Fig. 16-5)**.



Fig. 16-5: Surgical levels of lymph nodes (Berg's) in the axilla draining from breast.

Levels of the axillary nodes (Berg's)

- Level I—Below and lateral to the pectoralis minor muscle—anterior, lateral, posterior
- Level II—Behind the pectoralis minor muscle—central
- Level III—Above and medial to pectoralis minor muscle—apical – Halsted's node

Note in carcinoma breast

- Spread restricted to Level I nodes carries better prognosis
- Spread to Level II has poor prognosis
- Spread to Level III indicates worst prognosis

Nerves Related to Axillary Dissection

Long thoracic nerve arises from C5, 6, 7 nerve roots of brachial plexus, enters the axilla running on the lateral surface of the serratus anterior muscle invested by serratus fascia and supplies serratus anterior which on division during axillary dissection causes *winged scapula* with inability to fix the shoulder.

Thoracodorsal nerve arises from posterior cord of brachial plexus runs posteriorly downwards to supply latissimus dorsi muscle. Its division may cause difficult in extending the shoulder but more importantly reconstruction with latissimus dorsi myocutaneous flap (LD flap) after mastectomy is not possible.

Intercostobrachial nerve is communicating nerve between lateral cutaneous branch of 2nd intercostal nerve and medial cutaneous nerve of arm, denervation of this nerve causes sensory loss of skin of upper medial and inner aspect of the arm, apex and lateral axilla. Second intercostobrachial nerve may be present occasionally arising from anterior branch of 3rd lateral cutaneous nerve.

Medial pectoral nerve arising from medial cord of the brachial plexus runs along the lateral margin of the pectoralis minor supplying pectoralis minor mainly and pectoralis major muscle partly. It often may pass through the fibres of the pectoralis minor muscle at its lateral aspect. It should be preserved during axillary dissection otherwise atrophy of pectoral muscles occur.

Lateral pectoral nerve arises from lateral cord of the brachial plexus after running on the medial aspect, supplies the medial part of the pectoralis major muscle (Lateral pectoral nerve is medial; medial pectoral nerve is lateral. They are not named on anatomical location but on their origin of cord).

Muscles Related to Breast/Breast Surgery

Pectoralis major muscle – It arises from medial half of clavicle (clavicular fibers), anterior part of manubrium and sternum up to 6th costal cartilages (sternal fibres), 2nd to 6th costal cartilages (costal fibres). It is inserted as bilaminar tendon into lateral lip of bicipital groove of the upper end of humerus. It is supplied by lateral and medial pectoral nerves. Fibres are mainly placed as *transverse* and oblique. It is adductor and medial rotator of the shoulder; clavicular fibres flex the arm also. Deeper relations are pectoralis minor, clavipectoral fascia which is pierced by cephalic vein, thoracoacromial artery and lateral pectoral nerve. Anterior axillary fold is formed by twisted fibres of the pectoralis major muscle **(Fig. 16-6)**.

Pectoralis minor muscle – It arises from 3rd, 4th and 5th costal cartilages near costochondral junctions. It is inserted to medial upper part of the coracoid process (along with coracobrachialis). It is supplied by medial and lateral pectoral nerves **(Fig. 16-7)**.

Serratus anterior muscle – It arises from 8 digitations from upper eight ribs and intervening intercostal fascia. It is inserted into the costal surface of the scapula; first to superior angle; 2-4 to medial margin of the scapula; last 4 into inferior angle of the scapula. It is supplied by long thoracic nerve to serratus anterior (*of Bell)* – C5, 6 and 7. Muscle pulls the scapula forward in pushing and punching movement; it rotates the scapula forward; it helps in raising the arm above the head; it steadies the scapula during weight carrying. Its paralysis causes inferior angle and medial border of the scapula to become more prominent during the pushing movement causing '*winging of the scapula*'.

Latissimus dorsi muscle – It arises from posterior third of outer lip of iliac crest; lumbar fascia; T7 to T12 spines; lower four ribs; inferior angle of scapula. It forms posterior fold of the axilla, with twisted tendon inserted into the floor of the intertubercular sulcus of the upper end of the humerus. It is supplied by thoracodorsal nerve (C6, 7 and 8). It causes adduction, extension and medial rotation of the shoulder. It is a muscle of climbing, swimming and rowing. Muscle is important in mastectomy while creating the L D myocutaneous flap.


Clavicular fibres
Sternal fibres
Costal fibres
Lateral lip of bicipital groove
Bilaminar tendon as a crescentic fold
Pectoralis major muscle after mastectomy and axillary dissection
Pectoralis major muscle
Clavipectoral fascia
P. minor muscle

Fig. 16-6: Pectoralis major muscle.

FNAC (Fine Needle Aspiration Cytology)

Often, 22 gauge needle with 20 ml syringe with syringe holder (aspiration gun) is used. Two syringes are usually required. After cleaning the area, needle is passed into the required tissue/mass obliquely; - 40 cm of H_2O suction is created into the syringe. Needle is manoeuvred at different angles at same site to allow cells to enter the needle. Cells should fill the needle not the syringe. Before removal of the needle from the tissue suction is released. Needle is withdrawn; contents are carefully expressed into glass slides. 5 mm drop of contents are placed over the slides, smear is created by rubbing another slide over it. One slide is air dried; other slides are fixed with 95% ethanol. Remaining cells in the needle can be used for culture, cytocentrifugation. Complications of FNAC of breast are rare. Rarely pneumothorax, haemothorax, haematoma and acute mastitis can develop. Sensitivity is 98%. Specificity and positive predictive value is near 100%.


Clavicle
Coracoid process
1
2
3
4
5
6
7
Pectoralis minor tendon
Pectoralis minor

Fig. 16-7: Pectoralis minor muscle.

OPEN BIOPSY OF BREAST LESION

Indications – Lesions with atypia; LCIS; radial scar; atypical papillary lesions; high risk group with suspected lesions; radiologic-pathologic discordance; phylloides tumour; inadequate tissue harvesting; negative FNAC/core biopsy but doubtful lesion; failure of infection to subside in spite of proper treatment plan; mammographically suspected lesion.

Anaesthesia – Xylocaine 1% local (plain) anaesthetic agent is used (with adrenaline may cause epidermolysis). Infiltration is done deep into retromammary space. General anaesthesia is used when mass is not palpable or deeply placed; apprehensive non-cooperative patient; if one stage procedure (biopsy – frozen section confirmation – definitive surgical procedure) is planned.

Procedure – Incision is placed as periareolar or circumferential along the Langer lines which is cosmetically acceptable and should able to include the specimen of the eventual anticipated mastectomy. Sharp dissection is preferred method in biopsy. Bipolar cautery can be used (unipolar cautery should be avoided). Surrounding 1 cm margin of normal breast parenchyma is included with the lump. A 'figure of eight' suture may be placed on the mass to facilitate the dissection around. Holding the mass with crushing/damaging instruments should be avoided. Skin edge is retracted using hook retractor. After excision, haemostasis is achieved by bipolar cautery. Wound is irrigated with saline and drain is placed if required. Skin is sutured with subcuticular or interrupted sutures. Specimen should be oriented with marker stitches **(Figs 16-8 and 16-9)**.



Fig. 16-8: Circumferential incision is preferred in breast biopsy.


Incision-
circumareolar or
circumferential
Incision close to the lesion
Flap deep to subcutaneous fat is raised
beyond the lesion
Traction sutures on the lesion
Wound sutured
Specimen is marked

Fig. 16-9: Excision biopsy of the lump.

Incision biopsy instead of excision biopsy is done when tumour is more than 4 cm in size.

When there is nipple discharge suspicious of malignancy without any mass lesion, duct can be cannulated with a fine probe and circumferential excision of the duct with the lobe is done. Haematoma (10%), infection are the complications of breast biopsy.

Definitive surgery if done within 2 weeks of biopsy, it will not alter the recurrence rate or survival benefit.

EXCISION OF BENIGN BREAST LUMP

Palpable cyst can be aspirated. Recurrent cysts, solid benign masses need to be excised. Fibroadenoma, cysts, indicated fibrocystadenosis, traumatic fat necrosis are the common indications. Circumareolar, circumferential, lateral submammary incisions are commonly used. Smaller lesions are excised using circumareolar incision *(Webster's)*; larger lesion is excised using submammary incision (*Gaillard Thomas incision)*. Type of incision is decided on individual patient basis. Superomedial incision is usually avoided as scar may become hypertrophic **(Figs 16-10 to 16-13)**.

Procedure

General anaesthesia is usually used. Patient is placed in supine position, cleaning and draping is done. Both monopolar and bipolar cautery can be used. Incision is made depending on the location and size of the lump. In *circumareolar incision*, dissection under the nipple should be done in deeper plane otherwise areolar necrosis may occur. Fine scissor and cautery dissection is done around the lump. Freely mobile and encapsulated fibroadenoma will easily come out of the wound with dissection around the capsule. *Figure of eight traction suture* on the swelling is beneficial to facilitate proper dissection around. It prevents destruction of the swelling/tissue to be removed by multiple applications of forceps. When cautery is used for excision, it should be wider to prevent coagulation artifacts in the specimen surface. Haemostasis achieved using cautery. Suction drain is placed. Deeper subcutaneous tissue is apposed using absorbable sutures (3 zero vicryl). Skin is closed using monofilament nonabsorbable (3 zero polypropylene) or 3 zero monocryl. Compression dressing applied. Drain is removed in 48 hours. Specimen should sent for histology after making proper markings. Special sports bra is used in postoperative period until recovery occurs. An icepack over the breast may be useful to relieve the pain in immediate postoperative period **(Fig. 16-14)**.

Complications

Seroma, haematoma, areolar necrosis, nipple deformity, asymmetry of breasts

Subcutaneous Mastectomy

It is removal of entire breast with retaining skin over the breast, areola and nipple. It is done through a submammary *Gaillard Thomas incision*. Adequate skin flap is raised with flap containing subcutaneous fat which maintains the blood supply of the flap and prevents flap necrosis. Entire breast is removed using fine scissor dissection or cautery dissection. It is done in gynaecomastia, as a prophylactic mastectomy in high risk patients. After haemostasis drain is placed. Breast implant can be placed in subcutaneous/submuscular plane either immediately or as delayed reconstruction.



Fig. 16-10: Circumareolar (Webster's) incision. Areolar flap is raised carefully in deeper plane otherwise areolar necrosis can occur.



Fig. 16-11: Areolar necrosis developed after circumareolar incision.



Fig. 16-12: Incisions used for breast lump excision. Circumareolar *(Webster's)* incision is cosmetically better and is used for small lumps. *Gaillard Thomas* submammary incision is used for excision of the large lump.

Indications for subcutaneous mastectomy are – fibrocystadenosis with epitheliosis, sclerosing adenosis, persistent nodules, gynaecomastia and DCIS. Breast implants (silastic) are placed in the subcutaneous/submuscular plane **(Fig. 16-15)**.

Complications

Nipple/areolar ischaemia, nipple distortion, saucer deformity of nipple, haematoma, seroma, wound infection, skin necrosis, asymmetry of breasts.



Fig. 16-13: Submammary incision is used to remove large benign swelling like fibroadenoma.



Fig. 16-14: Fibroadenoma is well capsulated and so easier to excise/enucleate. Circumareolar incision is used for small fibroadenomas. Submammary incision is used for large/multiple fibroadenomas.


Incision
Raising the flap
Flap
Excising the mass
Excised specimen

Fig. 16-15: Excision of gynaecomastia – steps. Drain may be placed if needed.

DRAINAGE OF A BREAST ABSCESS

Both subareolar and intramammary breast abscess should be drained. Drainage is done under general anaesthesia. Subareolar abscess is drained with a subareolar incision. Intramammary abscess is drained with a deep incision. Once cavity is reached all loculi should be broken using a sinus forceps/finger/scoop. Pus should be sent for culture. *Counter incision is* often needed to achieve complete drainage of the abscess cavity. Corrugated drain is placed for 72 hours or more or as required. Since intramammary abscess is common in lactating women, milk fistula may be a sequelae. It is often very difficult to manage such case. Milk from opposite breast should be expressed at regular intervals either manually or using breast pump. Only occasionally suppression of milk is needed using bromocryptine 2.5 mg for 5 days **(Figs 16-16 to 16-18)**.



Fig. 16-16: Different types of breast abscesses – subareolar, intramammary and retromammary.



Fig. 16-17: Drainage of subareolar breast abscess.

Indications for drainage in mastitis/breast abscess

- Mastitis not resolving with antibiotics in 48 hours
- Persistent fever and progression of mastitis
- Brawny induration

Do not wait for abscess to form (fluctuation to develop)

Surgical Treatment of Mammary Fistula

Mammary fistula develops in a chronic abscess cavity at the drainage site or where abscess has pointed and opened. A probe is passed through the fistula towards the apex of the nipple. Track is laid open by cutting tissues along the probe. Opened wound is left to granulate. Often it requires major duct excision **(Fig. 16-19)**.

MICRODOCHECTOMY

It is excision of the entire lactiferous duct (single duct disease). It is done for duct papilloma. In a duct papilloma when there is no palpable mass, duct is expressed to see the discharge. A fine probe/stiff nylon suture (as a probe) is passed gently into the duct. Probe is fixed to nipple skin using silk sutures so that it will not displace during procedure. A triangular area is cut 1 mm away from the probe using fine scissor to raise the skin flaps. The duct with the probe is excised with the skin flap for 5 cm till the papilloma is identified. Papilloma will be always situated within 5 cm from the duct orifice. Wound is closed without a drain. Compression bandage is applied. It is ideal to rule out DCIS by frozen section biopsy.

MAJOR DUCT EXCISION (ADAIR–HADFIELD OPERATION)

It is done mainly for duct ectasia with involvement of many ducts or multiple papillomas. A circumareolar incision is made usually along lower half of the areola not exceeding more than 3/5th of circumference. After incising the subcutaneous tissue, with blunt dissection terminal lactiferous ducts are circumferentially dissected. All dissected ducts are divided at the junction of nipple. A cone of tissue of 4 cm depth and 2 cm width is removed with base deep in the breast parenchyma. Excised entire lactiferous ducts are sent for histology. Cavity in the breast is obliterated with vicryl sutures. Wound is closed with a suction drain. Bruising, infection, haematoma and recurrence of the disease – 15% (duct ectasia) are the complications **(Fig. 16-20)**.

Melhem Novel modified breast ductal system excision is also done for duct ectasia. Here only lactiferous ducts are excised after raising the areolar flap through circumareolar incision.

SENTINEL LYMPH NODE BIOPSY/DISSECTION (SLNB/SLND)

The first axillary (SLN) node draining the breast (by direct drainage) is designated as the *sentinel node*. SLN is first node involved by tumour cells and presence or absence of its histological involvement, when assessed will give a predictive idea about the further spread of tumour to other nodes. The incidence of involvement of other nodes without SLN is less than 3% and so if SLNB is negative nodal dissection can be avoided but regular follow up is needed. SLNB is done in all cases of


Drain
Incision
Counter incision
Incision
Counter-incision

Fig. 16-18: Drainage of intramammary breast abscess. Incision and counter incision is used commonly to prevent cavity getting closed early which may cause recurrence.


Fistula
Probe in the fistula

Fig. 16-19: Mammary fistula excision.


Lower circumareolar incision
Exposure of all major ducts
Excision after raising flap and dissection of all major ducts

Fig. 16-20: Adair–Hadfield major duct excision.

early breast cancers, T1 and T2 *without clinically palpable node.* It is not done in clinically palpable axillary node as there is already distortion of lymphatic flow due to tumour. It is also not done in multifocal and multicentric tumours, as there is involvement of many lymphatic trunks from different places of breast, and chances of false negative is high. Sentinel node is localised by preoperative (within 12 hours prior) or peroperative injection of patent blue (Isosulfan vital blue dye 2.5 – 7.5 ml) or 99m TC radio isotope labeled albumin (one mCi on previous day)/sulphur colloid (6 hours before) near the tumour (peritumour area) or over subdermal plexus around the nipple. Marker will pass through the sentinel node which can be detected visually as blue staining or with a hand held gamma camera; and is biopsied with a small incision directly over it. Frozen section biopsy or touch imprint cytology is done for presence of malignant cells. If there is no involvement of sentinel node by tumour then further axillary dissection is not required as *skip lesions* (skipping sentinel node) occur only in less than 3% cases. Detection rate of sentinel node for blue dye and radioisotope is 90% and 98% respectively. Subdermal/subareolar injection of radioisotope *has got better* sentinel node localisation than peritumour injection. But better imaging is obtained by peritumour injection and so *peritumour injection is usually* practiced. Radioisotope tracer injection done in the early morning of the day of surgery into peritumour area and perioperative injection of patent blue dye in subareolar region – as a *combined method* is often used in many centres. After injection of patent blue, breast is massaged continuously to enhance the uptake. *Incision* is made after 5-7 minutes between pectoralis major and latissimus dorsi to identify blue stained lymphatics which are traced to 2-3 blue lymph nodes. Hand held radio probe is used to identify the sentinel node which is later excised. Often 2-3 nodes are removed. *Paraffin section histology is better* than frozen section to identify positive sentinel lymph node. If report comes negative immunohistochemistry test is done to confirm that lymph node is negative for tumour. Sentinel lymph node biopsy *should be done before* wide local excision of the primary tumour.

Wide local excision of the primary tumour is done after SLNB in the same sitting.

SLNB is *less invasive* than axillary dissection. It is ideal in early invasive carcinoma. Positive SLNB is again classified as macrometastasis (> 2 mm) or micrometastasis (< 2 mm).

SLNB is *contraindicated* in patients who are allergic to vital blue dye or radio-colloid, in pregnancy and in inflammatory carcinoma of breast.

Complications

Complications of SLNB are rare they are - blue tattooing of skin which gradually fades; blue – green urine and stool for short periods; allergic reactions; anaphylaxis (0.1%); seroma formation. Blue dye binds to oxyhaemoglobin artificially registers in oximeter as hypoxaemia

Axillary Sampling

It is done before wide local excision of primary tumour. Incision is made between pectoralis major and latissimus dorsi muscles. Deep fascia is opened. 10 – 15 nodes of level I are dissected and removed. Often this procedure is done along with sentinel lymph node biopsy. Occasionally when level I nodes are not found, level II or III nodes are removed to identify 3-5% skip metastases.

BREAST CONSERVATIVE SURGERY (BCS)

In early breast cancer, breast conservative surgeries like quadrantectomy, axillary dissection (level I and II) and postoperative radiotherapy (to the breast) are used which prevents the disfigurement and psychological trauma of mastectomy to the patient. It is very well acceptable cosmetically. When disease outcome is considered, it is equivalent to mastectomy if patient is carefully selected. Tumour is removed with a rim of 1 cm normal tissue (macroscopic margin). Wide excision and QUART therapy are different procedures (Use of word lumpectomy is a debate and not well accepted).

Tumour size is *better* estimated by ultrasound or MRI breast than by clinical examination or mammography.

Breast conservative surgery

Indications	*Contraindications*
• Lump ≤ 4cm • Clinically negative axillary nodes • Mammographically detected lesion • Well differentiated tumour with low S phase • Adequate sized breast to allow proper RT to breast • Breast of adequate size and volume • Feasibility of axillary dissection and radiotherapy to intact breast • Absence of tumour multicentricity • Achieving tumour negative margin	• Tumour > 4 cm • Positive axillary nodes > N1 • Tumour margin is not free of tumour after breast conservative surgery • Poorly differentiated tumor • Multicentric tumour • Earlier breast irradiation • Tumour/breast size ratio is more • Tumour beneath the nipple/ central tumour • Extensive intraductal carcinoma • Existing collagen vascular disease as RT may be problematic • Strong family history of breast cancer

Principles and Technique of Conservative Breast Surgery

Curvilinear *non-radial incision* (radial incision should not be placed, if there is a need to convert into total mastectomy, and then incision plan may be difficult) is used to remove primary tumour. Separate incision is used for axillary dissection. Undermining of the skin flap must be avoided. Tumour clearance should be confirmed by frozen section. It may be often difficult and so tumour is cut and only margin which is close and doubtful is advocated for frozen section. Radiotherapy is a must to breast and chest wall region (locally). Consent for total mastectomy should be taken in case if need arises **(Fig. 16-21)**.


Correct incisions
Radial and directly axillary extended incisions should not be used in conservative breast surgery
Axillary incision
Wrong incisions
Curvilinear incisions

Fig. 16-21: Curvilinear incision should be placed in conservative breast surgeries. Never place wrong radial incisions. If conversion to total mastectomy is needed, it will be difficult in placing incision if radial incision is placed. In conservative breast surgery for axillary dissection separate incision in the axilla should be placed.

Ultrasound is good way of assessing the size of the tumour. If mammography shows calcification, this calcification should be localised using hook wires. Impalpable lesions are localised preoperatively by blue dye injection, hook wires, radioisotope markers. Intraoperative ultrasound also can be used. By mammography or ultrasound controlled injection of technetium labeled human serum albumin or sulphur colloid into the tumour and using hand held gamma probe intraoperatively lesion is located and excised.

Quadrantectomy and wide local excision are two types of BCS. Breast is distributed into segments with each segment draining into one major duct. Removal of *one entire segment with ductal system with 2 cm clearance* is *quadrantectomy* which is much wider and extensive removal than wide local excision. But presently quadrantectomy is not advocated as it is cosmetically poorer and there is no difference in outcome between quadrantectomy and ***wide local excision***.

Incision over the breast should be circumferential along the *Langer's line* or parallel to the lines of maximum resting skin tension in the breast (*dynamic lines of Kraisl*) **(Fig. 16-22)**.



Fig. 16-22: Langer lines and dynamic lines of Kraisl.

If there is previous open biopsy scar, it should be included in the specimen as 'en bloc'. *Mexican hat incision* of the preexisting scar gives better scar. Otherwise routine skin excision is *not* done **(Fig. 16-23)**.



Fig. 16-23: Mexican hat incision is used to include previous scar area.

Skin flaps are deepened straight up to 1-2 cm beyond the lump margin. Only rising skin flaps is *not* advised. Skin with subcutaneous tissue can be raised judiciously.

Dissection is done around the tumour with a volume of normal breast tissue all around. Pectoral fascia *should not* be opened in deeper plane. Tumour with surrounding normal clearance tissue is lifted off the pectoralis fascia and breast tissue in deeper plane can be dissected off the fascia. Bipolar cautery is better than monopolar cautery. After removal of the specimen, it is properly marked using coloured markers or paints as superior, inferior, medial, lateral, anterior and posterior for identification of the clearance margins and *orientation*. Entire specimen is coated in India ink. Specimen should be inspected properly for tumour relation to margins. All marked surfaces and margin which is close to the tumour should undergo frozen section biopsy for confirmation of clearance. Doing *specimen mammography* is often better. Specimen may be kept in an *orientation – grid* and mammography of the specimen is taken. If few margins are close to the tumour, then re-resection at that particular margin is sufficient which again should be confirmed by frozen biopsy. Achieving margin clearance all around the tumour is essential but *width of cleared margin is not important*. Once confirmed, specimen is sent for receptor/molecular/cellular/biochemical study. Wound is closed without a drain. *Small defect* in the breast tissue (tumour area) less than 10% of volume can be left alone; *larger defect* in breast more than 10% of breast volume should be apposed by proper sutures. If many margins are invaded or very close to tumour, then total mastectomy should be planned **(Fig. 16-24)**.


Traction sutures placed on the tumour
Clearance margin
1 cm
Tumour
If clearance is inadequate re-excision is done at the place where margin is not cleared.

Fig. 16-24: Technique of wide local excision.

Complications of wide local excision are – haematoma (2%); seroma; infection (5%); incomplete excision (15%); poor scar.

Recurrence after BCS is usually at primary site. Young age, family history, small volume breast are the patient related factors for recurrence. Grading of the tumour, lymphatic or vascular invasion (two times more), extensive in situ component (4 times more), multifocal tumours are the *tumour factors* for recurrence of the tumour. Delay in radiotherapy to breast area, further chemotherapy and hormone therapy also influence the local recurrence rate. Radiotherapy to breast is a *must* after BCS. Recurrence is treated by total mastectomy.

Microscopic disease free margin is defined as at least 1 mm rim of normal tissue around the tumour in all directions. Area lesser than 1 mm is considered as inadequate clearance and such area should be re-excised and confirmed for clearance. It is done either through same scar or modified elliptical incision which includes the scar – `*Mexican hat incision*'.

QUART Therapy

It is quadrantectomy, axillary dissection of level I and II nodes with separate axillary incision and postoperative radiotherapy to breast (5000 cGy) and axilla (1000 cGy). First it was started by Umberto Veronesi from Milan.

Axillary dissection is done to identify the nodal involvement of the disease which is an indicator of metastatic breast disease. It is also done for staging of malignancy. Number and level of nodes involved are independent predictors of the outcome of the disease. Therapeutic benefit of axillary dissection is a debate. It is done basically for infiltrating carcinoma of breast. In situ carcinomas do not require axillary dissection as incidence of nodal spread in situ carcinoma is less than 2%. Axillary flaps are elevated superiorly and inferiorly. Level I and II nodes are removed with fat and fascia. External mammary, lateral, subscapular and central nodes are removed. A minimum of 10 nodes should be removed. Wound is closed with a suction drain.

AXILLARY DISSECTION

It is done under general anaesthesia. Sandbag is placed under the shoulder to elevate the axilla. Arm, axilla, shoulder and same side chest wall is cleaned and draped. Forearm and hand are draped to facilitate holding and moving it as needed.

Incision is along the crease just below the hair bearing area of axilla. A lazy S incision between pectoralis major and latissimus dorsi muscle or an incision along the anterior axillary fold also can be used **(Fig. 16-25)**.



(1) Skin crease incision distal to hair bearing skin of the axilla.
(2) Lazy S incision between pectoralis major and latissimus dorsi.
(3) Anterior axillary fold incision.

Fig. 16-25: Different incisions for axillary dissection.

Skin flap is elevated behind up to the edge of latissimus dorsi muscle. Upper skin flap is raised. Medial part of the dissection is done by identifying the pectoral muscles. Medial pectoral nerve which winds the lateral margin of the pectoralis minor muscle is identified. One must remember that medial pectoral nerve arises from the medial cord of the brachial plexus and often passes through the fibres of the lateral part of the pectoralis minor muscle. Medial margin of the pectoralis minor is reached above to identify the part of clavipectoral fascia which contains few lymph nodes. It is upper medial limit of the dissection. Axillary vein meets the subclavius muscle here. When required pectoralis muscle should be divided from its insertion to coracoid process; index finger is passed around the insertion of the pectoralis minor tendon and muscle is traced towards coracoid process and is divided. Axillary vein is dissected to clear adipose tissue and lymph nodes on it. Now dissection should be done from lateral to medial using sharp and blunt dissection. Apex of the axilla should be cleared. Blood supply to pectoralis major muscle should be retained. Lower flap is dissected further to identify the serratus anterior muscle. Intercostobrachial nerve is identified and is preserved. Long thoracic nerve of Bell is 2 cm posterior to intercostobrachial nerve. It is in the serratus fascia. It should be identified and preserved. Further dissection exposes the thoracodorsal nerve (nerve to latissimus dorsi). Thoracodorsal vein is first identified; thoracodorsal nerve is most medial in thoracodorsal neurovascular bundle. This entire neurovascular bundle should be preserved if latissimus dorsi flap is needed at later period to patient. Dissection is continued laterally and behind to remove all the tissues up to the axillary tail. Specimen is removed. Its directions are marked. Single suction drain is placed. Skin flap is sutured from its deeper plane to chest wall as quilting to prevent seroma formation. Wound is closed in layers. Pressure dressing is placed.

Complications

Seroma formation, prolonged drainage through the drain for many days often weeks, frozen shoulder, lymphoedema of upper limb (10%), pectoral muscle atrophy due to injury to medial pectoral nerve, atrophy of latissimus dorsi muscle due to injury to thoracodorsal nerve, *winged scapula* is due to damage to long thoracic nerve.

Seroma formation is more common in obesity, when axillary nodes are positive, extensive mobilisation.

SKIN SPARING MASTECTOMY (SSM)

It is like a key-hole surgery of breast. Skin sparing/limited skin excision (5-10%) will not alter/affect the recurrence rate.

Indications are- central tumour/multicentric/extensive intraductal/ T1/not feasible for breast conservation.

It includes excision of nipple-areola complex with very limited skin removal; marginal skin excision over the tumour/biopsy site; total glandular mastectomy; axillary dissection using either same (extension of SSM incision) or separate incision in the axilla.

Incision is either periareolar/tennis racquet/modified elliptical. Tennis racquet has got lateral extension to axilla. Reduction mammoplasty incision is also used with a periareolar incision extending vertically into an inframammary horizontal incision. Prior biopsy site should be included in the mastectomy incision or should be removed widely through a separate elliptical incision **(Fig. 16-26)**.

Skin flaps are elevated between breast parenchyma and subcutaneous adipose tissue allowing 5-10 mm thick skin flap. Circumferential flap is raised around using scissor/no. 15 scalpel blade/cautery (cutting is used; coagulation can cause cautery artifact). Skin hooks and retractors are used to facilitate the dissection. Headlight may be used to have a better visualisation during dissection. Parasternal and infraclavicular perforating vessels are preserved to maintain adequate blood supply of the retained skin. Superiorly dissection is done up to second rib; medially to sternum; below to inframammary crease; laterally to latissimus dorsi muscle. Entire breast tissue, nipple areolar complex


Periareolar incision
Incision in the axillary fold
Tennis racquet incision
Reduction mammoplasty incision
Modified close elliptical incision

Fig. 16-26: Incisions used for skin sparing mastectomy (SSM).

are removed. Usually pectoral fascia is removed except in case of superficial tumours. Breast is raised off the pectoralis major muscle from the medial end towards lateral side. As it is raised it is delivered out of the wound to reach the dissection towards axillary tail. Axillary tail of Spence is separated from pectoralis major, minor and serratus anterior muscles. Junction of axillary tail and axillary tissue is clamped, ligated and cut. Axillary dissection may be added as decided. Wound is closed with a suction drain.

Immediate reconstruction with latissimus dorsi or TRAM flap is done with tissue expanders placed underneath the subcutaneous or submuscular plane.

Problems with SSM are – difficulty in raising flaps, haematoma/seroma formation, infection **(Figs 16-27 and 16-28)**.

INDICATIONS FOR TOTAL MASTECTOMY/ MODIFIED RADICAL MASTECTOMY IN BREAST CANCER

- When tumour is more than 4 cm.
- Multicentric tumour.
- Poorly differentiated tumour.
- Tumour margin is not clear of tumour after breast conservative surgery.
- Recurrence after BCS.
- Prior radiotherapy to breast.
- Scleroderma or association with other collagen disease.
- Stage I invasive/Stage II, III diseases.

MODIFIED RADICAL MASTECTOMY (MRM)

In MRM, breast tissue, nipple areolar complex, skin over the breast tissue are removed along with axillary clearance with or without removal of pectoralis minor.

Patey's operation – It is total mastectomy with clearance of all levels of axillary lymph nodes with removal of pectoralis minor muscle.

Scanlon operation – Here along with total mastectomy, pectoralis minor is not removed but incised to reach level III lymph nodes

*Auchincloss operatio*n – It is total mastectomy with axillary clearance (level I and II) keeping pectoralis minor intact. It is commonly advocated now.

Patey's operation: It is total mastectomy along with clearance of all levels of axillary nodes and removal of pectoralis minor muscle. It is *en bloc* dissection of breast and axilla.

General anaesthesia is used for the procedure. Patient lies in *supine position* with sandbag under the same side thorax and shoulder. Side of the chest wall, breast area, axilla, neck and sides are cleaned and draped. Same side entire arm and forearm is cleaned and is covered with drape and stockings. Shoulder should have free movement as needed during dissection of the axilla. Shoulder is kept in abducted and extended position. Surgeon stands on the side; first assistant near the shoulder on the same side; second assistant on opposite side; scrub nurse stands next to the surgeon near the leg side.

Different incisions are used as shown in **Figures 16-29 to 16-35**. *Classic elliptical Stewart incision* is commonly used. Incision is decided by the surgeon who is operating.

An elliptical incision is made from medial aspect of the second and third intercostals space enclosing the nipple, areola and tumour extending laterally into the axilla along the anterior axillary fold. Upper and lower skin flaps are raised. Flap is raised mainly using scissor/scalpel/cutting cautery along with blunt gauze dissection in between. It extends medially up to the midline on the sternum; laterally to anterior margin of the latissimus dorsi muscle; above up to second rib/subclavius muscle; below 3 cm down the inframammary fold. Skin with subcutaneous fat is dissected off while raising the flap.


Incision for axillary dissection
Deep tumour (retained after biopsy)
Incision scar of excision biopsy
Re-excision incision with 1 cm margin after excision biopsy
Nipple-areolar incision
Re-excision incision with 1 cm margin
SSM incision
Tumour
Skin sparing mastectomy (SSM) incision
Tumour
Incision scar of previous biopsy
Incision for axillary dissection
Re-excision incision with 1 cm margin
Tumour
Skin sparing mastectomy (SSM) incision (1 cm margin)
Tumour

Fig. 16-27: Skin sparing mastectomy for carcinoma breast- different approaches. Skin sparing mastectomy (SSM) does not affect the recurrence rate.

Breast with tumour is raised from the medial aspect of the pectoral major muscle with pectoral fascia by making a deep incision close to midline, adjacent to sternum. Dissection is proceeded laterally ligating perforating vessels derived from lateral thoracic and anterior intercostal arteries. Once dissection reaches axilla, lateral border of pectoralis major muscle and pectoralis minor is exposed in deeper plane. Medial pectoral nerve (is lateral arises from medial cord of brachial plexus) which supplies lateral part of the pectoralis major muscle is identified here and preserved.

Axillary lymph node dissection is now started in continuity with mastectomy. Investing layer of deep fascia is divided. Fascia in front of the axillary vein is dissected to expose the vein in front. Small tributaries are ligated. Pectoralis major is retracted superomedially. Finger is swept between the two pectori to clear the Rotter's nodes. Lateral pectoral nerve is identified and preserved (it arises from lateral cord and is located medially supplies the medial part of pectoralis major). Attachment of pectoralis minor tendon is felt with index finger and with finger dissection it is hooked round the finger close to coracoid process



Fig. 16-28: Skin sparing mastectomy incision with prosthesis implant for placement.


Tumour
Incision
Incision
Tumour

Fig. 16-29: A horizontal or oblique incision is commonly used for total mastectomy or modified radical mastectomy.


Tumour
Incision

Fig. 16-30: Gray incision crosses the midline towards the opposite side.


Incision
Tumour

Fig. 16-31: Greenough incision.


Incision
Tumour

Fig. 16-32: Kocher's incision for mastectomy.


Incision
Tumour

Fig. 16-33: Orr incision for mastectomy.


Tumour
Incision

Fig. 16-34: Rodman incision for mastectomy with two branches in the final wound.


1-2 cm
Incision
Tumour
Incision

Fig. 16-35: Classical Stewart incision for mastectomy.

and is divided from coracoid process to clear level II nodes. Later from the apex of axilla level III nodes are cleared. Pectoralis minor muscle, after cutting from the coracoid process may or may not be removed. Axillary vein is cleared up to subclavius muscle medially. Posterior and lateral group of lymph nodes are cleared. Subscapularis medially and teres major laterally are exposed posteriorly. Nerve to serratus anterior (long thoracic nerve of Bell), nerve to latissimus dorsi with vessels (thoracodorsal neurovascular bundle), intercostobrachial nerve, axillary vein, cephalic vein and pectoralis major muscle are preserved. Long thoracic nerve is located in front of the subscapularis medially on the chest wall within the investing fascia. Once specimen is removed it is marked with orientation markers or clips **(Figs 16-36 to 16-38)**.



Fig. 16-36: Nerve to serratus anterior (long thoracic nerve of Bell), thoracodorsal nerve, medial pectoral and lateral pectoral nerves and intercostobrachial nerves usually come across during MRM. Medial pectoral nerve arising from medial cord of brachial plexus (hence the name) winds around the lateral margin of the pectoralis minor muscle (40%) or passes through its lateral part of fibres (60%), supplies part of the pectoralis major muscle. Lateral pectoral nerve arising from lateral cord of the brachial plexus runs close to the medial margin of pectoralis minor muscle to supply mainly pectoralis major muscle as its dominant nerve.

Wound is washed with saline. Haemostasis is maintained. *Two silastic suction drains* are placed, one laterally adjacent to latissimus dorsi muscle; another in front of the pectoralis major muscle. Wound is closed with a suction drain. Suction drain is kept for 5 – 7 days or until drainage becomes less than 30 ml per day **(Fig. 16-39)**.

Complications of MRM/mastectomy

- Injury/thrombosis of axillary vein
- *Seroma*- 50% - It should be aspirated repeatedly supported with compression dressing.
- Shoulder dysfunction 10%
- Pain (30%) and numbness (70%)
- *Flap necrosis*/infection
- Haematoma formation – If large needs drainage under general anaesthesia.
- Lymphoedema (15%) and its problems – Dissection above the axillary vein level increases the incidence of lymphoedema.
- Axillary hyperesthesia (0.5-1%)
- *Winged scapula* – Prominent medial border and inferior angle of scapula during punching action.

Contd...

Contd...

- *Stewart – Treves syndrome* is development of lymphangiosarcoma of upper limb in patient who develop lymphoedema (after 5 years) after mastectomy
- *Weakened shoulder adduction* due to injury to thoracodorsal nerve.
- Anaesthesia over the medial aspect of the upper arm (dysesthesia) due to injury to intercostobrachial nerve.
- Atrophy of pectoralis major muscle with loss of chest wall contour due to injury to medial pectoral nerve.

Mastectomy specimen should be carefully inspected and sent to pathology department

- Specimen is sent in formalin for histology.
- It is sent in saline in low temperature for ER/PR/Her 2 neu status study (histochemistry).
- Tumor grading, tumor clearance, nodal involvement - its number and capsular breach are assessed histopathologically.

Points to be remembered

Subcutaneous fat is included while elevating the flap of the breast skin; but it should be removed in axillary flaps.
Dissection in the axilla should be kept below the level of axillary vein.
All nerves in the axilla which will come across should be preserved as much as possible.
Subscapular/thoracodorsal vessels should be retained if LD flap is planned.
Proper haemostasis is essential.
Double tube silastic drain is a must. Drain is removed when only the discharge drained becomes less than 30 ml/day for 2 days.

DIFFERENT MASTECTOMIES

Total mastectomy also called as simple mastectomy – Here tumour, entire breast, nipple areola complex, axillary tail are removed. Axillary dissection is not done.

Extended total (simple) mastectomy is doing total mastectomy with clearance of level I axillary lymph nodes.

Modified radical mastectomy (MRM) is total mastectomy with axillary clearance. In *Patey's MRM* all levels of axillary nodes are cleared with division of tendon of pectoralis minor muscle close to coracoid process with or without removal of the pectoralis muscle. In *Scanlon's MRM* pectoralis minor is incised to reach the level III nodes. In *Auchincloss MRM* only level I and II are removed, pectoralis minor is left intact.

Breast conservative surgery (BCS) is done only when indications mentioned earlier is met with. It is often added with axillary dissection. Radiotherapy to breast is a must. Wide local excision is the commonly done procedure. Veronesi designed quadrantectomy, axillary dissection and radiotherapy (QUART) in BCS.

Skin sparing mastectomy (SSM) is keyhole surgery in which total mastectomy is done with removal of nipple areolar complex, earlier biopsy scar and entire breast and tumour. Skin over the breast is retained as the outcome of the disease will not be altered by removal or not removal of the skin widely over the breast.

Radical mastectomy (Halsted) is removal of tumour, entire breast, nipple, areola, and skin over the breast and tumour, pectoralis major and minor muscles, fat, fascia, nodes in the axilla. Axillary vein, long thoracic nerve and cephalic vein are retained **(Fig. 16-40)**.


First assistant
Second assistant
Surgeon
Scrub nurse
Position of first assistant
Position of surgeon
Position of scrub nurse
Area to be cleaned for MRM
Draping for MRM
Incision for MRM
Mass
Incision
Skin hooks
Cautery
Scissor
Knife and blade

Figs 16-37(1)


Cautery
Scissor
Flap
Pectoralis major muscle
Upper flap is raised up to clavicle
Clavicle
Clavicle
Mass
Elevation of lower flap
Opening the pectoral fascia
Medial side
Pectoralis major muscle
Removing the tumour, breast with pectoral fascia from pectoralis major muscle
Pectoralis major muscle
Axilla
Tumour with breast tissue
Opening the pectoral margin to reach axilla and interpectoral tissue

Figs 16-37(2)


Breast with tumour
P major muscle
Axillary dissection
Upper limit of dissection is axillary vein
Breast with tumour
P major muscle
Interpectoral tissue and nodes
P minor muscle
Axillary vein
Finger dissection in axilla
Peanut dissection in axilla
Medial pectoral nerve
Axillary vein
Lymph node
Thoracodorsal nerve
Long thoracic nerve of Bell
Intercostobrachial nerve
Hooking of the P minor tendon using finger close to the coracoid process

Figs 16-37(3)

Figs 16-37(1 to 3): *Technique of modified radical mastectomy (MRM).* Skin over the breast, whole of ipsilateral chest wall, axilla, shoulder, supraclavicular region with neck, part of abdomen and part of opposite chest wall are prepared with antiseptic solution. Slight head up (Fowler's) position with same side tilting of the table upwards often with a sandbag under the shoulder region is used. Hand and forearm is often covered with a sterile towel so that to achieve a free movement of the arm and shoulder during axillary dissection. Incision placed depends on the need, either transverse or oblique which will be 5 cm beyond the tumour margin as an elliptical type. Upper flap is elevated first usually up to the level of clavicle above; up to sternum medially. Lower flap is elevated up to rectus sheath and costal margin below. Lateral flap is elevated up to the margin of latissimus dorsi muscle. Flaps are elevated using either cautery or scissor or scalpel or often with gauze dissection. In axillary region, subcutaneous tissue and fat is also cleared. Fascia on the lateral margin of pectoralis major is incised to expose the pectoralis minor. Deeper part of the pectoralis minor is dissected to expose the axillary vein beyond the subscapular vessels. Clavipectoral fascia is incised to clear the nodes, taking care not to injure the medial pectoral nerve which passes through the pectoralis minor (60%) or its lateral margin (40%) to supply pectoralis major muscle. Main supply of pectoralis major is lateral pectoral nerve which passes medial to the pectoralis minor close to acromiothoracic artery. Pectoralis minor is retracted to clear the apical nodes. Often pectoralis minor tendon is detached from its insertion to coracoid process (Patey's). The fascia over serratus anterior is cleared without injuring long thoracic nerve. Intercostobrachial nerve, if possible, is saved. Posteriorly dissection is continued over subscapular muscle preserving the subscapular vessels and thoracodorsal nerve. At the end specimen is freed from latissimus dorsi.


Incision
Cautery
Elevation of the upper flap
Scissor/scalpel dissection
Gauze dissection
Flap is elevated up to clavicle superiorly
Lower flap dissection
Scissor
Gauze
Cautery
Medial dissection up to sternum
Pectoral fascia is opened
Dissection in front of pectoral is major muscle
Dissection of the pectoralis major muscle using cautery/scissor/scalpel
Opening the lateral margin of the pectoral muscle to reach the axilla
Dissection in the axilla
Pectoralis major
Interpectoral space
Medial pectoral nerve

Figs 16-38(1)


Hooking the pectoralis minor tendon near its insertion to coracoid process
Cutting the pectoralis minor tendon
Pectoralis major (retracted)
P minor (cut)
Lymph node
Axillary vein
Intercostobrachial nerve
Dissected breast tissue (specimen)
P major muscle
Axillary vein
S anterior muscle
Long thoracic nerve
Thoracodorsal nerve
Pectoralis major muscle
Axilla after dissection
Specimen just prior to final dissection (removal)
Thoracodorsal nerve
Long thoracic nerve
Breast (primary tumour)
Axilla with nodes
Specimen outer view
P minor muscle
Silastic double tube drain
Breast tumour
Axilla with nodes
P minor muscle
Specimen- deeper surface

Figs 16-38(2)

Figs 16-38(1 and 2): *Patey's modified radical mastectomy*. Here pectoralis minor tendon is detached from coracoid process. It achieves better approach and clearance of apical nodes.

Toilet mastectomy is done in locally advanced tumour with removal of tumour and possible breast tissue to prevent fungation.

Extended radical mastectomy is doing radical mastectomy with removal of internal mammary nodes of same side or opposite side. It is not practiced.

Nipple sparing mastectomy is done with preservation of nipple and areola.

Areola sparing mastectomy is done preserving areola with resection of the nipple.

RECONSTRUCTION OF THE BREAST

Breast reconstruction is done either as *immediate or delayed procedure*. Immediate reconstruction is done in early breast cancer or after prophylactic mastectomy. Reconstruction is delayed for 6 months in advanced cases.


Tube drain infront of pectoralis major muscle
Double silastic suction drain
Tube drain in the axilla

Fig. 16-39: Double tube silastic drain is kept. One tube is in front of the pectoralis major muscle; other in the axilla. Bulky dressings with elastic bandage support are usually used. Drain is removed once drainage is less than 30 ml per day for two consecutive days.

Skin is closed primarily as wound closure. If skin is removed widely and apposition is not possible then *skin graft* is ideal as it will tolerate radiotherapy very well **(Fig. 16-41)**.

Implant is placed under the pectoralis major, serratus anterior, external oblique and rectus abdominis myofascial plane **(Fig. 16-42)**.

Myocutaneous flap with or without breast implant in submuscular plane is good reconstructive approach. Latissimus dorsi myocutaneous flap (LD FLAP) or Transverse abdominis myocutaneous flaps (TRAM FLAP) are used with or without implants. LD flap usually needs implant. TRAM flap dose not require implant usually.

Silicone gel implant under pectoralis major muscle or expandable saline prosthesis may be used. Placement of implants is technically easier. One should take care to achieve symmetry. *Complications* of implants are pain, rupture, displacement, infection and capsular contracture.

TRAM flap can be standard lower TRAM or upper TRAM. Vertical RAM flap is also used as variation. Contralateral submammary flap is also used.

Factors deciding the reconstruction are – amount of skin retained; stage of carcinoma; need of radiotherapy or earlier radiotherapy; need for implant.

Standard lower abdominal TRAM flap is placed horizontally with upper incision at the level of umbilicus; lower incision below su-



Fig. 16-40: *Halsted radical mastectomy.* It is not used now. Here entire breast with tumour, skin over the breast both pectoralis major and minor muscles, axillary fat, lymph nodes and fascia are removed. Axillary vein, nerve to serratus anterior (Bell's) and cephalic vein are retained.



Fig. 16-41: Split skin graft is done after mastectomy on one side. Other side primary closure was done. It was a bilateral carcinoma of breast.



Fig. 16-42: Breast implant used for reconstruction. It is placed either subcutaneous or submuscular plane.

prapubic region with an ellipse. Even though theoretically opposite TRAM flap is better, it is technically not practicable and so ipsilateral TRAM is commonly used. Bilateral TRAM flaps are used to reconstruct both breast areas. Upper incision is deepened through subcutaneous and superficial fascia. Flap is raised often in front of the anterior rectus sheath up to the costal margin and xiphisternum. Anterior rectus sheath protects the muscle. Many advocate the cutting of the anterior rectus sheath and flap is raised in front of the muscle carefully. Small branches of intercostal vessels are ligated. Lower flap is deepened through the rectus muscle which is cut just below the semicircular line. Inferior epigastric vessels are identified which are securely ligated. Muscle with skin is raised from deeper plane above towards xiphisternum as myocutaneous flap. Tunnel for the passage of mobilised flap is done along the midline above. Muscle need not be cut above but can be done so if needed. Skin part of the flap on same side moves towards the axilla and skin part of the flap on opposite side moves towards lower medial part of the defect. Defect is sutured to flap. Suction drains are placed under the flap. Abdominal defect is closed meticulously in layers often placing a synthetic mesh underneath **(Figs 16-43 and 16-44)**.

Vertical RAM/upper TRAM/Contralateral submammary flap are variations of the same, depending on the need. Free TRAM flap can be used to revascularise through internal mammary artery. *Deep inferior epigastric perforator flap (DIEP)* is used as a free flap in breast reconstruction. Revascularisation is done using internal mammary or thoracodorsal vessels **(Figs 16-45 and 16-46)**.

Latissimus dorsi muscle/myocutaneous flap- It is based on thoracodorsal artery, a branch of subscapular artery. Skin over the upper and anterior border of the muscle is used for transfer. It is commonly used to cover the defect after mastectomy. But it does not give the bulk. It is technically easier. It can be used as muscle flap also. It helps as skin cover. Prosthesis (submuscular silicone) is needed to place underneath to provide bulk in postmastectomy defect. Muscle arises from iliac crest upwards to midthoracic spine. Muscle is like a fan below forming tendinous fibres above to insert into humeral shaft. Subscapular artery a largest branch is derived from 3 part of axillary artery runs along posterior wall of the axilla giving circumflex scapular vessels at 4 cm distance and later continues as thoracodorsal artery for about 6 cm, enters the muscle giving many branches. Flap is usually taken as myocutaneous flap with elliptical skin on the surface. Skin part is either horizontal ellipse when taken from upper margin of the muscle or vertical when taken from the anterior margin of the muscle. Point of origin of the subscapular artery is the pivot point of the flap. Artery is accompanied by the vein. While raising the flap after islanding it with skin, only pedicle can be retained cutting muscle above to attain extra length (but commonly anterior attachment is retained) and flap is rotated to the needed area. Donor area can be sutured primarily or covered with a split skin graft. *Often* in LD flap nerve is not retained (if retained it causes *unpleasant muscle contractions* and so it will not maintain the bulk but gives good coverage of the defect). Flap harvesting is done in lateral position. Subscapular vessels maintain the adequate length and caliber and so it is often used as *free flap* based on subscapular vessels **(Fig. 16-47)**.



Lower abdominal transverse elliptical incision to raise upper and lower flaps. Flap is based on superior epigastric artery. Inferior epigastric artery is ligated.

Scar will be in the lower abdomen. Flap will cover the defect and also provide adequate bulk. Usually may not require to place prosthesis underneath.

Fig. 16-43: Standard TRAM flap is used from ipsilateral side. It is infraumbilical and is based on superior epigastric artery.



Upper TRAM flap is based on superior epigastric artery with transverse flap raised just above the umbilicus. It is used whenever there is infraumbilical scar and people who do not accept blood transfusion (religious reason). But it cosmetically creates a midabdominal scar.

Ipsilateral upper TRAM flap ratated to mammary defects.

Fig. 16-44: Upper TRAM flap is often used with flap incision in upper abdomen – horizontal.



Vertical rectus abdominis myocutaneous (RAM) flap is based on superior epigastric vessels. It is easier and safer. But it provides less skin and subcutaneous tissue to simulate breast mound and so needs an implant. Abdominal contour is not improved with this flap.

Fig. 16-45: Vertical rectus abdominis myocutaneous flap.



It is cosmetically acceptable contralateral flap with superior epigastric artery as base taking upper most part of rectus abdominis muscle with sufficient skin. Arc of rotation towards opposite side is short and so often needs removal of one or two costal cartilages. It needs implant for size. It provides inframammary scar; useful in young/ small breasts.

Fig. 16-46: Submammary TRAM flap is used from opposite side with least scar.



Fig. 16-47: Latissimus dorsi myocutaneous flap.

LD flap	*TRAM flap*
Myocutaneous flap based on subscapular artery Easy to perform Reliable flap, well vascularised Can be placed over prosthesis Low complication rate, but causes unsightly donor area on the back	Transverse rectus abdominis myocutaneous flap based on superior epigastric artery. Ipsilateral or contralateral TRAM flap is used It gives the bulk needed for reconstruction and so implant is not needed Donor site morbidity and fat necrosis can occur. Free TRAM flap into internal mammary/thoracodorsal axis can be done Limitations to position, shape and rotate; needs mesh placement in the abdomen wound to prevent the formation of incisional hernia

Nipple is created using— Local breast flaps, 3 months after breast reconstruction; nipple sharing from contralateral nipple using composite graft; *skate flap*: local flap with de-epithelialised donor site around the periphery over which a full thickness graft is applied; nipple prosthesis.

Areola pigmentation is created using (*it is done 3 weeks after nipple creation*) – Full thickness skin graft from non-hairy skin lateral to *labia majora,* as the pigmentation of this graft matches that of the areola; from contralateral areola if reduction mammoplasty is done on that side; *tattooing* – colour tends to fade with time and may need to be repeated; split skin graft from retroauricular area or from thigh.

Chapter 17

Surgeries of Salivary Glands

SURGICAL ANATOMY OF PAROTID (PARA – AROUND; OTIC – EAR) GLAND

Parotid, *pyramid* shaped largest of salivary glands (15 gram) is located below the external acoustic meatus, between ramus of the mandible and the sternomastoid. Gland overlaps these structures and masseter muscle. Gland is of ectodermal origin.

Surface marking of the gland: Line joining from a point at upper margin of mandibular head; along a point at the center of the masseter muscle; to a point at posteroinferior angle of the mandible and at a point at upper part of anterior margin of the mastoid process. *Parotid duct* is marked in the middle third of a line joining the lower border of tragus to a point which is at the middle of the line joining the nasal ala to margin of upper lip. *Facial nerve* is marked from a point at middle of the anterior border of mastoid process (stylomastoid foramen lies 2 cm deep to this point) to a point behind the neck of the mandible **(Fig. 17-1)**.

Investing layer of deep fascia of neck splits at the lower posterior margin of the gland into two layers, as a thick adherent superficial lamina, and a thin deep lamina. Superficial part is attached to zygomatic arch above. *Parotid capsule* otherwise is superficial lamina is thick, inelastic and unstretchable. Deep lamina is attached to styloid process, mandible, and forms thick *stylomandibular ligament* to separate it from submandibular salivary gland **(Fig. 17-2)**.


Zygomatic arch
External auditory meatus
Masseter muscle
Parotid duct
Parotid gland
Sternocleidomastoid muscle

Fig. 17-1: Location of the parotid in relation to masseter muscle.


Facial nerve
Masseter
Parotid gland
Posterior belly of digastric


Superficial temporal vein
Superficial temporal artery
Transverse facial vein
Maxillary artery
Transverse facial artery
Parotid duct
Retromandibular vein
Maxillary veins
Posterior auricular vein
Parotid gland
Posterior auricular artery
Facial vein
External jugular vein
External carotid artery

Fig. 17-2: Anatomy of parotid and structures passing through it.

Parotid gland has *4 surfaces* – superior/base; superficial; anteromedial; posteromedial. *Apex* is directed downwards; *3 borders* are – anterior, posterior and medial. Apex lies on the posterior belly of digastric and partly extends into the carotid triangle. Cervical branch of facial nerve and divisions of retromandibular vein emerges at the apex. Upper small concave superior surface is related to auriculotemporal nerve, superficial temporal vessels, temporomandibular joint (posterior part), and cartilaginous part of external acoustic meatus. Largest superficial surface is related to skin, superficial fascia, preauricular/superficial parotid lymph nodes, platysma, risorius, and parotid fascia. Anteromedial surface is related to masseter, lateral part of temporomandibular joint, posterior margin of the mandibular ramus, medial pterygoid, branches of facial nerve. Posteromedial surface is related to mastoid process, sternomastoid, posterior belly of digastric musle, styloid process. External carotid artery enters the gland through this surface. Internal carotid artery is deep to styloid process.

Parotid gland is divided conventionally into two lobes – *superficial lobe* (80%) is also called as *exofacial lobe* which is outer to facial (7th cranial) nerve plane; *deep lobe* (20%) is also called as *endofacial* which is deeper to facial nerve plane. Deep lobe is located adjacent to masseter muscle along the ascending ramus of the mandible. *Isthmus* of the parotid is that portion which is between temporofacial and cervicofacial branches. Tail of the parotid is the portion which extends posteroinferiorly over mastoid tip and sternocleidomastoid muscle **(Figs 17-3 and 17-4)**.



Fig. 17-3: Lobes of parotid.



Fig. 17-4: Relations of the parotid gland.

Parotid gland is *bounded* above by zygoma, below by styloid process, styloid muscles, internal carotid artery and internal jugular vein, behind by external auditory canal. Fascia deep to deep lobe is extension of the fascia from deeper part of the digastric muscle and is called as *stylomandibular membrane* which occupies between mandible in front, styloid process behind and stylomandibular ligament below. This membrane separates parotid from submandibular salivary gland. Deep lobe tumour extends to parapharyngeal space through this membrane.

Structures passing through the anterior margin are – parotid duct, facial nerve branches and transverse facial vessels.

Structures within the parotid gland are –**Arteries** (deepest) – ECA enters the gland through posteromedial surface of the gland; maxillary artery (begins at neck of the condylar process of mandible) leaves the gland through anteromedial surface of the gland medial to gland to reach infratemporal fossa; superficial temporal artery comes out through superior surface passing between external acoustic meatus and TM joint to reach temporal fossa where it is accompanied by auriculotemporal nerve. Transverse facial artery arises from superficial temporal artery runs horizontally above the parotid duct. Posterior auricular artery arises from ECA passing posteriorly deeper and at upper margin of the posterior belly of digastric to reach posterior auricular region. Posterior auricular artery gives stylomastoid branch which runs in front and along the facial nerve to enter the stylomastoid foramen to supply tympanic cavity, mastoid air cells and semicircular canals. **Veins** (outer to arteries) – superficial temporal vein and maxillary vein (formed by pterygoid venous plexus at lateral pterygoid muscle) joins to form retromandibular vein (posterior facial vein/temporomaxillary vein) within the gland which descend and divides into anterior and posterior divisions which emerge at apex of the gland; anterior division after emerging joins facial vein to form common facial vein which runs superficial to digastric to reach IJV; posterior division joins the posterior auricular vein to form external jugular vein which runs downwards in front of posterior belly of digastric muscle, sternocleidomastoid, great auricular nerve to reach subclavian vein. *Patey's faciovenous plane* is important during surgical dissection. **Facial nerve** (outer to venous plane) – comes out of stylomastoid foramen where it is accompanied with stylomastoid branch (in front of facial nerve) of posterior auricular artery (artery enters, nerve comes out). Here it gives posterior auricular branch to supply posterior auricular and intrinsic muscles of the ear and branches to posterior belly of digastric and stylohyoid. Nerve after traveling for 1 cm enters the gland through its posteromedial surface and again runs for 1 cm in the gland dividing within gland into two terminal branches – zygomaticotemporal (larger) and cervicofacial (smaller). Terminal temporal (auricularis anterior and superior part of frontalis) and zygomatic (frontalis and orbicularis oculi) branches arise from larger zygomaticotemporal division. Upper buccal, lower buccal (buccinator, orbicularis oris and elevators of lip), marginal mandibular (lower lip muscles), cervical (platysma) arise from smaller cervicofacial branch/division which emerge through the anteromedial surface. Multiple communications are common between branches especially in zygomatic and temporal branches (*pes anserinus/goose foot*). They supply muscles of facial expression and platysma. **Deep parotid lymph glands** – They are embedded in the superficial lobe of the gland. *Faciovenous plane of Patey* is a plane where vein and facial nerve branches lie within the parotid with nerve lying superficial to vein in this plane **(Figs 17-5 and 17-6)**.

Parotid duct (Niels *Stenson's—Anatomist Copenhagen; father of geology)* is 5 cm in length (2-3 mm diameter) with thick wall which after


Facial nerve branches
Superficial temporal vessels
Tn. facial artery
Auriculotemporal nerve
Temporal
Accessory parotid
Parotid duct
Zygomatic
Parotid gland
Posterior auricular nerve and artery
Upper buccal
Lower buccal
Posterior auricular vein
Posterior division
Marginal mandibular
Retromandibular vein
Anterior division
Cervical branch
Facial vein
Common facial vein will join IJV
External jugular vein

Fig. 17-5: Structures passing out of the parotid gland.



Fig. 17-7: Accessory parotid gland is above the parotid duct.



Fig. 17-6: Patey's faciovenous plane.


Superficial temporal artery
Maxillary artery
Transverse facial artery
Parotid duct
Posterior auricular artery
Parotid gland
External carotid artery
Internal carotid artery
Common carotid artery

Fig. 17-8: Arterial supply of parotid gland and arteries related to parotid.

beginning at deep and behind the angle of mandible 1.5 cm below the zygoma runs forwards and emerges from the anterior border running forward and downward on the masseter muscle up to its anterior margin where it pierces obliquely the buccal pad of fat, buccopharyngeal fascia, buccinator muscle and opens into the vestibule of the mouth opposite the crown of 2nd upper molar tooth. During its course it receives interlobular from above and one duct from accessory parotid gland. Above it is related to *accessory parotid gland*, upper buccal branch of facial nerve, transverse facial vessels; below to lower buccal branch of the facial nerve **(Fig. 17-7)**.

Blood Supply

Parotid is supplied by ECA through its direct branches and also branches of ECA in the parotid region; venous drainage is into the external jugular vein **(Figs 17-8 and 17-9)**.

Lymphatic Drainage

Superficial parotid lymph glands lie outer to parotid (deep fascia); *deep parotid lymph glands* are located deep to parotid sheath in *superficial*


Superficial temporal vein
Maxillary vein
Retromandibular vein
Parotid duct
Posterior auricular vein
Parotid gland
Facial vein
External jugular vein
IJV

Fig. 17-9: Venous drainage and veins related to parotid.

lobe. Drainage area are – temple, side of the scalp, lateral part of ear, external acoustic meatus, middle ear, parotid gland, upper part of cheek, eyelids partly, orbit. Efferent from these nodes drain into upper deep neck nodes.

Nerve Supply

Parotid fascia sheath is supplied by great auricular nerve (C2); *sensory supply* to gland is through auriculotemporal nerve; *sympathetic* vasomotor fibres are from plexus around ECA; *parasympathetic supply* is through otic ganglion with complex pathway. Inferior salivatory nucleus → Preganglionic fibres → glossopharyngeal nerve → tympanic branch → tympanic plexus → lesser petrosal nerve → otic ganglion → post-ganglionic fibres → through auriculotemporal branch of mandibular division of trigeminal nerve → parotid gland **(Fig. 17-10)**.

FACIAL NERVE

It is 7th cranial nerve (2nd branchial arch). It is the '*queen of the face*'. It arises from 4 nuclei at lower pons. Sensory (nervus intermedius) and motor roots run along with 8th cranial vestibulocochlear nerve to enter the internal acoustic meatus with labyrinthine vessels. In the meatus two roots join to lie in the petrous temporal bone. In the canal it has got 2 bends. First bend is called as *genu* which is related to geniculate ganglion. Nerve leaves the skull through stylomastoid foramen. *Stylomastoid foramen* is located medial to mastoid tip and lateral to styloid process. Stylomastoid branch of posterior auricular artery (branch of ECA) is just in front of the facial nerve trunk which also enters the stylomastoid foramen. Here facial nerve runs lateral to styloid process to enter the parotid gland; divides into branches behind the neck of the mandible. ***Branches*** *–in the canal* are greater petrosal, nerve to stapedius, chorda tympani; branches immediately *after coming out of stylomastoid foramen* - are posterior auricular (to post auricular muscles), digastric (to posterior belly) and stylohyoid; *terminal* branches are - temporal, zygomatic, buccal, marginal mandibular and cervical. Buccal branch is in relation to the parotid duct; marginal mandibular branch crosses over the anterior facial vein. *Chorda tympani* originates from facial nerve 6 mm above the stylomastoid foramen; enters middle ear close to tympanic membrane, then petrotympanic fissure to reach infratemporal fossa where it joins lingual nerve to distribute secretomotor fibres to submandibular ganglion (parasympathetic secretomotor) and submandibular and sublingual glands. It also gives taste fibres to anterior 2/3rd of the tongue **(Figs 17-11 to 17-14)**.

Greater petrosal nerve pathway is - superior salivatory nucleus → facial nerve → greater petrosal nerve → opening in the petrous temporal bone for greater petrosal nerve → joins sympathetic deep petrosal nerve to


Inferior salivary nucleus
Middle ear
Tympanic branch
Glosso-pharyngeal nerve
Tympanic plexus
Lesser superior petrosal nerve
Auriculotemporal nerve
Foramen ovale
Superficial temporal artery
Mandibular nerve
Otic ganglion
Middle meningeal artery
Maxillary artery
Lingual nerve
Inferior alveolar artery and nerve
ECA
Parotid

Fig. 17-10: Parasympathetic supply of parotid gland.


Labyrinthine vessels
Nervus intermedius
Facial nerve (motor root)
Dura
Arachnoid mater
Vestibulocochlear nerve

Fig. 17-11: Structures in the internal meatus (Left).


Canal for facial nerve
Geniculate ganglion
1st part
Aditus to mastoid antrum
2nd part
3rd part
Promontory
Stylomastoid foramen
Stylomastoid branch of posterior auricular artery
Facial nerve

Fig. 17-12: Course of facial nerve to reach face.


Temporal branch
Zygomatic branch
Upper buccal branch
Parotid duct
Lower buccal branch
Marginal mandibular branch
Cervical branch
Facial nerve trunk

Fig. 17-13: Facial nerve and its branches.



Fig. 17-14: Facial nerve – on table look.

form nerve of the pterygoid canal → through canal reaches pterygopalatine ganglion (largest peripheral parasympathetic ganglion) → postganglionic fibres supply lacrimal gland and mucous glands of nose, sinuses, palate and pharynx.

PAROTIDECTOMY

Indications

Parotidectomy is done in benign/malignant tumours of parotid including adenolymphoma of parotid. Superficial parotidectomy is done only in benign tumours of superficial lobe. In tumours (benign) involving both superficial or deep lobe and only deep lobe total conservative parotidectomy is done. In malignant tumour invading facial nerve radical parotidectomy is done. Presently even in malignant parotid tumours, sacrificing only the involved/infiltrated branches of facial nerve and retaining uninvolved branches, with wide clearance and neck dissection is contemplated; as evidence suggests that there is no survival benefit between removing all branches and removing only the involved branches. In aggressive tumour radical parotidectomy is done sacrificing the trunk of facial nerve with nerve graft.

Occasionally superficial parotidectomy is added as part of radical neck dissection in case if primary tumour is in head and neck region and in skin malignancies of face and scalp. First branchial cleft cyst excision involves removal of the parotid. Type I first branchial cyst is located in the external auditory canal in relation to angle of the mandible and parotid.

Some surgeons even though not well accepted advocate total parotidectomy for chronic parotitis, sialorrhoea, fistula, refractory parotid stones.

Types of Parotidectomy

Superficial/lateral parotidectomy (Patey) – It is removal of superficial lobe of the parotid in front of the faciovenous plane of Patey.

Total conservative parotidectomy – Here both superficial and deep lobes of the parotid are removed preserving the facial nerve. Dissection along the faciovenous plane is carried out to identify the branches of the facial nerve retaining the isthmus/tumour bearing area. Nerve branches are retracted aside to reach the deep lobe which is removed entirely by dissecting off the branches of facial nerve carefully without injuring them. This is the right technique even though many advocate removing superficial lobe initially then deep lobe separately. Retromandibular vein is ligated here.

Radical parotidectomy – Involves removal of both lobes of parotid with facial nerve, fat, fascia, masseter, pterygoid, buccinator along with neck lymph node dissection. Facial nerve is sacrificed. Its branches whenever possible can be saved as additional advantage of survival not thereby removing uninvolved branches. On table frozen section biopsy of cut ends of nerve are needed. Ends of the cut nerve branches are tagged by fine sutures for eventual nerve grafting using great auricular nerve or sural nerve. Often radical parotidectomy is combined with removal of temporomandibular joint, mastoid process and external auditory meatus with less additional benefit. Mastoidectomy is done to visualize the clear proximal part of the facial nerve. Reconstruction of the main trunk, marginal mandibular, temporal and buccal branches are done to maintain eye closure and good oral competence.

Suprafacial parotidectomy is done for benign tumour at lower pole wherein all branches of facial nerve need not be dissected.

TECHNIQUE OF PAROTIDECTOMY

Position and Anaesthesia

Procedure is done under general anaesthesia. Paralytic agents used for intubation purpose are of short acting only as during surgery facial nerve branches are identified and confirmed by stimulation to achieve contraction of facial muscles. Neck is extended by placing a sandbag under the shoulder with a head support using a ring. After cleaning, draping is done to expose the face and eyelids to see the contractions of muscles whenever needed. Head is extended with face turning opposite side. Head end of the table is elevated 15° to reduce venous congestion. In many centres of China procedure is done under local anaesthesia also. Nerve monitor device is used. Its electrode tips are placed into orbicularis oculi and orbicularis oris muscles. Nerve either the main trunk or branches are stimulated using nerve stimulator whenever needed.

Incision

Standard incision is '*Lazy S*' incision (*modified Blair/Sistrunk* incision). It begins in front of tragus closely running vertically to the ear lobule;

curving on the margin of the ear lobule towards middle of the mastoid (mastoid tip) along postauricular part; again curving back downwards along the margin of the sternocleidomastoid muscle in the superior cervical crease 2 cm below the angle of the mandible. *Inverted T and modified Y incisions* are also used. '*Face lift' incision*' can be used in benign tumours of the tail or middle part of the parotid. It begins at tragus running vertically downwards curving the ear lobule and extending in the postauricular region along the hair line **(Figs 17-15 to 17-18)**.



Fig. 17-15: Modified Blair incision for parotidectomy.



Fig. 17-16: Inverted 'T' incision for parotidectomy.



Fig. 17-17: Modified Y incision for parotidectomy.



Fig. 17-18: Face lift incision for parotidectomy.

Usual plane used is *subplatysmal* in the *neck* area. Incidence of Frey's syndrome and flap necrosis are higher if flap is raised in front of the platysma. Ear lobule is held under traction with suture. Skin flap is raised anteriorly superficial to parotid fascia in *face* by holding with skin hooks up to the anterior margin of the parotid with visualisation of the masseter muscle. While elevating the flap anteriorly close to the masseter, branches of facial nerve will be close to skin flap and care should be taken not to injure them. Posterior skin flap is raised to expose the anterior border of the sternocleidomastoid muscle and mastoid process **(Fig. 17-19)**.

Even though *great/greater auricular nerve* has to be cut, it is cut close to the parotid gland or after it gives the posterior branch (it is the largest branch of cervical plexus). Adequate length of the great auricular nerve is dissected for the possible need of nerve graft in case of facial nerve injury. *External jugular vein* with its tributaries is visible which can be retained or transected. Fascia along the anterior border of the sternocleidomastoid muscle is incised to expose the upper part of the muscle. After retracting sternocleidomastoid, once posterior belly of digastric muscle is identified; both muscles are retracted; dissection is done in front of the mastoid along the tragal cartilage. Dissection begins from the posterior part of the gland near tail of the parotid. Gland is freed of the fibrous attachments and with blunt dissection bony cartilaginous junction of the auditory canal, tympanomastoid suture/fissure (groove between mastoid tip and tympanic portion of the temporal bone) and tragal pointer is felt and identified. Parotid tissue between superior border of posterior belly of digastric muscle and tympanomastoid fissure is dissected and separated carefully layer by layer by blunt and sharp dissection. Temporoparotid fascia from tympanomastoid fissure to parotid is cut to visualize facial nerve. Facial nerve is 1 cm below and medial (or *anterior and inferior*) to tip of the tragal cartilage **(Fig. 17-20)**.

Identification of Facial Nerve

Facial nerve trunk is identified by different techniques – (1) Facial nerve is 5 – 10 mm deep and below from the tip of the cartilaginous canal – *Conley's point*. (2) Sternocleidomastoid muscle is retracted behind, gland is retracted front; posterior belly of digastric is identified where nerve is anterior to this. (3) Nerve is lateral to styloid process. (4) Tracing branch from distal to proximal – *Hamilton-Bailey* technique through buccal branch or marginal


Ear lobule traction
Skin hooks
Facial nerve
Retromandibular vein

Fig. 17-19: Incision and subplatysmal plane for parotidectomy.


Cavernous sinus
Supraorbital vein
Supratrochlear vein
Angular vein
Anterior facial (facial) vein
Deep facial vein
Pterygoid plexus
Common facial vein
Internal jugular vein (IJV)
Superficial temporal vein
Maxillary vein
Retromandibular vein
Anterior division
Posterior division
Posterior auricular vein
External jugular vein
Subclavian vein

Fig. 17-20: Venous anatomy of face is important in parotidectomy.

mandibular branch. (5) Using Faradic or mechanical stimulation (pinching tissues) muscle movements/twitching can be observed. (6) Stylomastoid branch of posterior auricular artery is just in front of the facial nerve trunk which also enters the stylomastoid foramen. Facial nerve after coming out of stylomastoid foramen travels for 1 cm forward and below between mastoid process and membranous portion of external auditory canal and divides into temporofacial/temporozygomatic and cervicofacial branches behind the neck of the mandible. This bifurcation may be often distal or often proximal before coming out of the stylomastoid foramen. Cervicofacial branch divides into cervical (for platysma) and marginal mandibular branch which runs below the horizontal ramus of the mandible within the platysma muscle to supply lower lip. This branch *does not have any communicating* branch unlike other branches of facial nerve. This branch is more often superficial to posterior facial vein. Buccal and zygomatic branches have numerous communications which supply periorbital and upper lip muscles. Temporal branch supplies frontalis muscle but does not have cross communications and has got weak regenerative power and so often paralysis of frontalis stands permanent in facial nerve palsy. Buccal branch is situated close to parotid duct and so if duct is identified it is easier to look for buccal branch. Dissection from distal to proximal is more difficult than dissection from proximal to distal.

Separation of Gland off the Facial Nerve Branches

It requires patience and fine dissection. There are two methods to dissect the facial nerve. (1) Forward/*antegrade* technique – Dissection from main trunk of facial nerve; (2) *Retrograde* technique – Dissection from branches towards main trunk (it is followed in many centres in China).

Dissection using fine haemostat and fine scissor is ideal with tip of the instrument facing forward. Tiny oozing points need ligation using fine vicryl. Bipolar cautery can be used carefully away from the nerve branches. All parotid tissue is cut only with visualisation of nerve branches. One of the division and its branches are separated and dissected completely first; later other division and branches. Monopolar cautery *should not* be used. Dissection is first started along the upper divisions of the facial nerve. Dissection is carried out up to the anterior margin along the faciovenous plane of Patey to remove the entire superficial lobe. Deep lobe (20% of total gland) is nicely visualised. Haemostasis is achieved. If deep lobe needs to be removed after partial dissection of superficial gland from facial nerve branches, branches are gently retracted to dissect beside the isthmus of the parotid gland to reach deep lobe which can be removed. Often this is technically difficult and so many advocate removal of superficial lobe first followed by identification of deep lobe; facial nerve branches are retracted and deep lobe is dissected and removed. Parotid duct is located in relation to deep lobe. Upper buccal branch is above the duct which is larger than lower buccal branch. Ideally all the branches should be identified and dissected. In malignant parotid, branches which are invaded are sacrificed. Main trunk if divided then nerve graft is done using great auricular nerve or sural nerve. Operating microscope is needed for nerve suturing. Even though nerve is not injured post operative neuropraxia is common which recovers completely at a later period. Many use short term steroid therapy to prevent this. In removal of deep lobe retromandibular vein should be ligated. The parotidectomy should be done with the tumour 'en bloc' **(Fig. 17-21)**

Removal of the Deep Lobe in Total Conservative Parotidectomy

Branches of facial nerve which are dissected are gently retracted away using nerve hook or smooth loops to visualize the deep lobe. Parotid duct is transected at its anterior part and ligated. One should not injure upper buccal branch of facial nerve. Duct may be dissected up to the mucosa through buccinator if needed before ligation. Deep lobe is separated from nerve branches from its deeper plane. Often it is required to ligate the retromandibular vein to facilitate easy dissection and reduce bleeding. Deeper part of the deep lobe is dissected of the stylopharyngeus and stylohyoid muscles by blunt dissection while retracting the deep lobe. Superficial temporal vessels, maxillary artery deep to ramus of mandible, the occipital artery, posterior auricular artery and pterygoid venous plexus are deep to deep lobe. Deep lobe can be extirpated superior/inferior/in between nerve branches. Haemostasis should be achieved using bipolar cautery.

Main trunk of the facial nerve is stimulated with 0.5 mA to confirm the anatomical and physiological integrity of the branches of the facial nerve.

Points to be remembered are -

Dissection of the facial nerve should be done just superficial to the nerve to expose it clearly. Dissection deep to the nerve is inadvisable. The sheath of the facial nerve should not be opened to avoid damage to the nerve fibers.

Using *wet gauze* is better than dry gauze for haemostasis. Clearing of blood from the operative field should be done by mild pressure absorption of the blood rather than scrubbing. The dissected nerve should be covered by wet gauze to avoid dryness following exposure to air.

Bleeding from capillary vessels should be stopped by the pressure of wet gauze, as some blood vessels are distributed along with the nerve. The facial nerve is readily damaged if artery forceps are used for haemostasis. The dissection is continued in the other areas of the gland while attaining this haemostasis.

The bifurcation of the nerve is close to the retromandibular vein, and its fine branches should be ligated. Suction is used to achieve a clear surgical field. Any bleeding vessel should be carefully clipped or ligated.

The branching ducts of the gland must be distinguished from the facial nerve. The nerve is *white and shiny,* while the duct is *grey and dull.*

The parotid duct if ligated like done by many, in traditional superficial parotidectomy, then remaining deep lobe of parotid atrophies spontaneously. But it is possible to preserve the duct so that the saliva secreted from the parotid remnant will be made to extrude into mouth. So that partial function of the retained gland is achieved. It is important to ligate the interlobular ducts identified during the dissection carefully to prevent the formation of salivary fistula.

After parotidectomy, even though not practiced widely, parotid remnant is often sutured by absorbable sutures to achieve proper haemostasis and to prevent formation of salivary fistula. If the duct and function of the parotid remnant are to be preserved, deep sutures should be avoided in order to prevent ductal ligation.

The wound is irrigated with hypertonic saline/distilled water probably to destroy spilled tumour cells. The integrity of the facial nerve is checked by finger pinch or nerve stimulator. If the nerve has been disrupted, an end to end anastomosis of the nerve is carried out or with suitable graft immediately.

Closed suction drainage is used with suction tube placed away from the dissected facial nerve to prevent damage to the nerve. Compression bandage is kept often for 3 days.

Deep lobe mass may appear as lateral oropharyngeal masses. Tail of the parotid mass mimics cervical lymph node. Common site of the parotid tumour is tail of the parotid.

Only FNAC and imaging (CT scan) are the investigations done for parotid tumour. Open biopsy is not done in parotid tumour.

Enucleation of the parotid tumour should not be done. This increases the risk of facial nerve injury, risk of tumour recurrence.

Loupe or microscope is useful in dissecting the branches especially in reoperation.

Nerve stimulator should be used judiciously otherwise it itself can cause neuropraxia.

Closure

Proper haemostasis is achieved using fine vicryl ligatures or bipolar cautery. Often it is of practice to pour distilled water in the parotid bed and keep it for few minutes to kill spilled tumour cells from the capsule. *Digastric flap* is often used to cover the area of facial nerve. Posterior belly of digastric is detached from its hyoid/pulley attachment and rotated upwards over the facial nerve and attached to zygoma. An *acellular dermal matrix graft* can be placed into the wound prior to skin closure to cover the facial nerve trunk and auriculotemporal nerve area to prevent scar adhesion into the facial nerve trunk and formation of Frey's gustatory sweating. Suction drain is placed before closure which is removed in 3 days. Drain should not come into contact with the facial nerve main trunk. Skin is closed with interrupted polypropylene or polyethylene 4 zero or 3 zero sutures. Slight pressure dressing is often used **(Fig. 17-22)**.

Postoperative Care

Drain is removed in 48 hours. Facial expressions are observed for features of facial palsy. Temporary facial nerve paralysis is common in the postoperative period for which the surgeon should not worry. If closure of eyes is inadequate due to neuropraxia, repeated saline drops to eye and eye cover is needed to prevent exposure keratitis. Neuropraxia recovers in 4 weeks.


Position and incision for Parotidectomy
Traction suture on ear lobule
Skin incision for parotidectomy (modified Blair)
One should use skin hook, bipolar cauteryfine scissor and haemostat for dissection, Monopolar cautery should never be used.
Dissect up to the anterior margin of the gland
Dissect up to the anterior margin of the gland
Greater auricular nerve
Dissection between mastoid and tragal cartilage
Parotid gland
Greater auricular nerve
Dissection and identification of facial nerve trunk
Facial nerve trunk

Figs 17-21(1)


Bipolar cautery is used
Facial nerve branches
Excised specimen (superficial parotidectomy)
Skin flap
Ear lobule
Parotid bed
Parotid bed
Distilled water wash over parotid bed
Suction drain is placed
Skin suturing

Figs 17-21(2)

Figs 17-21(1 and 2): Technique of parotidectomy.

COMPLICATIONS OF PAROTIDECTOMY

Haemorrhage

It is rare, usually of venous origin and ooze from the bed. Major arterial injury is rare. When haematoma once develops, patient presents with swelling, pain, distress with blood in the drain. It is usually due to bleed from retromandibular vein or its tributaries. If haematoma is progressive then wound is reopened under general anaesthesia. Retromandibular vein is ligated both proximally and distally. Ligation of this vein causes ipsilateral facial oedema which gradually subsides in few weeks.

Facial Nerve Injury

It is the most important, common and worried complication. It may be due to simple neuropraxia due to handling during dissection or nerve injury at various levels either of the main trunk in case of neoplastic conditions or few of branches. *Incidence* of temporary facial nerve palsy due to neuropraxia is 40%; whereas permanent palsy is 4%. *Features* are – inability to close the eyelid, difficulty in blowing and clenching; drooping of angle of the mouth; obliteration of nasolabial fold; loss of forehead wrinkles; wide palpebral fissure and epiphora. Effects of temporary facial nerve injury/neuropraxia will recover in few days to few weeks (12 weeks). Oral or intravenous steroids with vitamin B_1 and B_{12} injection are often tried. Permanent facial nerve injury needs specialised methods to correct the deformity. Nerve grafting is done using greater auricular, sural, lateral cutaneous or hypoglossal nerves. It needs operating microscope and is done using 6 zero polypropylene sutures. Angle of mouth can be suspended to zygomatic bone using temporal facial sling. Corneal ulceration is prevented using lateral tarsorrhaphy. Epiphora is controlled by reconstruction of medial canthus. Dynamic surgery like neurovascular muscle graft can also be used **(Fig. 17-23)**.


Final wound
with suction drain

Fig. 17-22: Suction drain is placed after parotidectomy.



Fig. 17-23: Facial nerve palsy after parotidectomy.

The House–Brackmann Score

It is a score to grade the degree of nerve damage in facial nerve palsy. The measurement is done by measuring the upward movement of the middle portion of the top of the eyebrow, and the outward movement of the angle of the mouth. Each reference point scores 1 point for each 0.25 cm movement, up to a maximum of 1 cm. The scores are then added together, to give a number out of 8. It is a measure of the range of intentional movement of the patient's facial muscles. It is based largely on the observations of the physician as a subjective scale. So there may be discrepancies between assessments by different clinicians. But overall reliability is good and is the most commonly used scale. Electroneuronography is the other method used **(Fig. 17-24)**.

Grade	*Description*	*Measurement*	*Function %*	*Estimated function %*
I	Normal	8/8	100	100
II	Slight	7/8	76–99	80
III	Moderate	5/8–6/8	51–75	60
IV	Moderately severe	3/8–4/8	26–50	40
V	Severe	1/8–2/8	1–25	20
VI	Total	0/8	0	0

Surgeries for facial nerve palsy

- Static
  - Suspension surgeries using temporal fascia
  - Correction of medial canthus
  - Lateral tarsorrhaphy to prevent exposure keratitis
  - Upper lid gold weights to protect cornea.
- Dynamic
  - Muscle transfer-temporal to masseter
  - Free muscle graft like gracilis muscle neurovascular transfer
  - Cross facial nerve transplant from opposite facial nerve to injured facial nerve using sural nerve
  - Nerve grafts.


Upward movement of the
middle portion of the eyebrow
Facial nerve
with branches
Parotid gland
with duct
Outward
movement
of the angle of
the mouth
1 score = 0.25 cm movement

Fig. 17-24: Diagram showing how to look for House–Brackmann score.

Local Accumulation of Saliva under the Wound and Salivary Fistula Formation

It can occur in superficial parotidectomy as deep lobe is retained. This often subsides on itself. Aspiration of collected saliva and compression dressing is usually sufficient. Atropine is useful. Avoidance of spicy and acidic food; injection atropine 0.3 mg 30 minutes prior to food intake is helpful. Repair or reinsertion of duct into the oral mucosa can be done. *Newman–Seabrock's operation*- A probe is passed into the parotid duct through the opening in the mouth. Another probe is passed through the fistula. Duct and fistula are dissected over the probe. After removal of the fistula track severed duct ends are identified; and ends are trimmed. Probes are removed. A tantalum wire is passed into the duct across the severed ends and duct is sutured over it using 4 zero vicryl. Tantalum stent is removed after 3 weeks. If still persists, auriculotemporal nerve which supplies secretomotor component of parotid is cut. If there is stenosis at the orifice of the Stenson's duct, papillotomy at the orifice may help. Total conservative parotidectomy is done in failed cases.

Loss of Sensation of Ear Lobule

It is due to cutting of the great auricular nerve. Numbness of ear lobule causes difficulty in wearing ear ring. It slowly subsides and ear lobule gains its sensation in 1½ to 2 years. It can be prevented by preserving greater auricular nerve or its posterior branch.

Flap Necrosis

It is not uncommon. It usually heals on its own.

Frey's Syndrome

It is also called as *auriculotemporal syndrome or gustatory sweating* (*Lucie Frey – Polish surgeon 1032)*. It is probably due to injury to auriculotemporal nerve wherein postganglionic parasympathetic fibres from the otic ganglion become united to sympathetic nerves from the superior cervical ganglion creating pseudosynapsis. Auriculotemporal nerve has got two branches. Auricular branch supplies external acoustic meatus, tympanic membrane surface, skin of auricle above external acoustic meatus. Temporal branch supplies hairy skin of the temple. Sweating and hyperaesthesia occurs in this area of skin. Whenever salivation is stimulated or during mastication, flushing, sweating, pain and hyperaesthesia occur in this area of skin. Involved skin is painted with iodine and dried. Dry starch applied over this area will turn blue in Frey's syndrome due to more sweat (*Minor's Starch iodine test*). It is usually treated with conservative treatment with reassurance, drugs like antiperspirants like aluminium chloride, injection of botulinum toxin to skin, topical scopolamine. 10% of such patients later need surgical intervention. Tympanic branch of glossopharyngeal nerve below the round window of middle ear is cut – *intratympanic parasympathetic neurectomy (Jacobsen)*. Condition can be prevented by raising skin flap deep to platysma or deep to parotid fascia or by placing sternocleidomastoid/posterior belly of digastric or temporal fascia or artificial membranes over parotid bed.

DRAINAGE OF PAROTID ABSCESS

Parotid abscess being within the tense parotid fascia will not show fluctuation and fluctuations should not be awaited. Brawny induration with tenderness over the parotid is diagnostic; often with trismus.

It is drained under *general anaesthesia* (intubation may be difficult if there is trismus) with a small *vertical* skin incision in front of the tragus with a *transverse* incision/*split* on the parotid fascia to allow pus to drain. Sinus forceps is used to break the loculi; pus should be sent for culture. Facial nerve should not be injured. Irrigation of the cavity with normal saline and packing is needed. Facial nerve palsy and salivary fistula are the *complications* **(Fig. 17-25)**.

SUBMANDIBULAR SALIVARY GLAND

It is J shaped salivary gland situated in the anterior part of the digastric triangle which is indented by posterior border of the mylohyoid with larger part is located superficial to it and smaller part is deep to it.

Submandibular region extends 1.5 cm above the base of the mandible and below to the greater cornu of the hyoid bone. Gland is marked outside as an oval area posterior half of the base of the mandible and posterior border of the ramus.

Superficial lobe fills the digastric triangle extending above to mylohyoid line deep to mandible. Superficial lobe is covered by superficial and deep lamina of deep fascia of neck; deep lamina is



Fig. 17-25: Incision for parotid abscess. Vertical skin incision and horizontal parotid sheath incision.

attached to mylohyoid line; superficial lamina is attached to base of the mandible. Inferior surface is covered with skin, platysma, cervical branch of facial nerve, deep fascia, facial vein and submandibular lymph glands. Medial surface is related to mylohyoid muscle, vessels and nerve anteriorly; hyoglossus, styloglossus, lingual nerve, submandibular ganglion and hypoglossal nerve in the middle; styloglossus, stylohyoid ligament, 9th (glossopharyngeal) nerve and wall of pharynx.

Smaller deep lobe lies deep to mylohyoid and superficial to hyoglossus and styloglossus, continuing posteriorly with superficial part after winding round the posterior border of mylohyoid muscle. Anterior end of deep lobe is close to sublingual gland.

Wharton's submandibular salivary gland duct is 5 cm long with thin wall begins at the anterior end of deep part of the gland running over hyoglossus muscle between lingual and hypoglossal nerves. Duct is crossed by lingual nerve at the anterior border of the hyoglossus muscle; duct later opens on the floor of the mouth on the side of tongue frenum on the summit of the sublingual papilla.

Secretomotor fibres of submandibular salivary gland: Preganglionic fibres from *superior salivary nucleus* → facial nerve → chorda tympani nerve → lingual nerve → *Langley's* submandibular ganglion → post ganglionic fibres → submandibular and sublingual salivary glands **(Figs 17-26 to 17-28)**.

Suprahyoid muscles are –

Digastric muscle has got anterior belly which arises from the digastric fossa of the mandible running downwards and backwards towards intermediated tendon on the fibrous pulley of the hyoid bone; posterior belly arises from mastoid notch of temporal bone runs forward and downwards towards intermediate tendon. Anterior belly is supplied by nerve to mylohyoid; posterior belly is supplied by facial nerve.

Stylohyoid muscle arises from posterior surface of the styloid process to insert into the greater cornu of hyoid bone at its junction to the body. Its tendon is perforated by the tendon of the posterior belly of digastric muscle. It is supplied by facial nerve.

Mylohyoid is triangular muscle arising from mylohyoid line of mandible runs medially downwards to get inserted to body of hyoid bone and median raphe in the midline connecting to opposite mylohyoid muscle forming floor of the moth. It is supplied by nerve to mylohyoid.

Geniohyoid muscle arises from genial tubercles/inferior mental spine runs backwards and downwards to insert on the anterior surface of the body of the hyoid bone. It is supplied by C1 nerve through hypoglossal nerve.

Hyoglossus arises from entire length of greater cornua and lateral part of the hyoid bone running upwards and forwards to attach to side of tongue between styloglossus and inferior longitudinal muscle of the tongue. It is supplied by hypoglossal nerve.

Facial Artery

It was earlier called as *external maxillary artery* arises from external carotid artery just above the tip of greater cornu of hyoid bone (just above the origin of the lingual artery) in the carotid triangle. It shows tortuous course running beneath the digastric and stylohyoid muscles, grooving posterior surface of the groove of the submandibular salivary gland in front of hypoglossal nerve. It curves over the body of the mandible at anteroinferior angle of the masseter muscle, running across the cheek to the angle of the mouth, side of the nose, medial


Tongue
Lingual nerve
Styloglossus muscle
Stylohyoid ligament
Glossopharyngeal nerve
Langley's sub-mandibular ganglion
Deep part of the submandibular salivary gland
Hypoglossal nerve
Lingual artery
Hyoglossus muscle
Hyoid bone
Geniohyoid muscle
Genioglossus muscle
Wharton's duct
Tongue
Mylohyoid muscle
Styloglossus muscle
Lingual nerve
Wharton's duct
Hyoglossus muscle
Hypoglossal nerve
Digastric tendon
Greater cornua of hyoid bone
Investing layer of deep fascia
Subplatysmal plane
Platysma
Cervical branch of facial nerve
Facial artery
Anterior facial vein
Superficial part of submandibular salivary gland
Sublingual gland
SMSG duct
Submandibular ganglion
Lingual nerve
Digastric muscle
Lingual artery and vein
Deep submandibular gland
Hypoglossal nerve (12)
Deep lobe SMSG
Styloglossus
Digastric
Mid constrictor
Hyoglossus
Mylohyoid
Hyoid bone

Fig. 17-26: Surgical anatomy of submandibular salivary gland.


Anterior belly of digastric muscle
Geniohyoid muscle
Sublingual salivary gland
Genioglossus muscle
Hyoglossus muscle
Mylohyoid muscle
Skin
Platysma
Deep fascia
Deep part superficial part
Submandibular salivary gland

Fig. 17-27: Relations of the submandibular salivary gland.


Anterior belly of digastric
Superficial part of submandibular salivary gland
Mylohyoid
Geniohyoid
Sublingual salivary gland
Genioglossus
Deep part of submandibular salivary gland
Hyoglossus

Fig. 17-28: Submandibular and sublingual salivary glands and their muscular relations.

commissure of the eye to end as angular artery. Its tortuosity in neck and face allows movements of pharynx, mandible, cheek and lips. In the neck it lies on middle and superior constrictors of pharynx. In the face it is deep to platysma, risorius, and zygomaticus major but superficial to buccinator and levator labii superioris. Anterior facial vein is posterolateral to the facial artery in the face; but anterior to facial artery in neck. It communicates with dorsal nasal artery of internal carotid artery.

Branches of facial artery are – *in the neck:* ascending palatine artery, tonsillar artery, submental artery, glandular branches; *in the face*: inferior and superior labial arteries, lateral nasal branch (to nasalis) and terminal *angular* artery. Most of the facial muscles are supplied by facial artery.

One has to remember that *transverse facial artery* is a branch of *superficial temporal artery* (not from facial artery) while in the parotid gland. It runs horizontally in the parotid gland substance, between parotid duct and lower border of zygomatic arch resting on the masseter to supply parotid gland and duct and anastomose with facial, masseteric, buccinator and infraorbital arteries.

Excision of the Submandibular Salivary Gland

It is done under *general* anaesthesia. Neck should be *extended* with chin towards opposite side. *Incision* is made 2-4 cm below and parallel to margin of the mandible of 6-8 cm in length **(Fig. 17-29)**.


Submandibular salivary gland
2-4 cm
Incision

Fig. 17-29: Incision for submandibular salivary gland excision.

Marginal mandibular nerve is in subplatysmal plane in neck; incision should be deepened *across* deep fascia *without* raising subplatysmal plane to avoid injury to this nerve. *Anterior facial vein* (*facial vein anterior tributary of common facial vein*) crossing the superficial part of the gland is ligated using silk or vicryl. Superficial lobe of the gland is exposed fully in *digastric triangle* between two bellies of digastric and stylohyoid muscles below and margin of the mandible above with gland overlapping over mylohyoid muscle medially. Deep fascia of neck covering the gland is visible. Common facial vein with its anterior (facial vein) and posterior (anterior division of retromandibular vein) tributaries are visible deep to deep fascia in close relation to sternocleidomastoid muscle. Few lymph nodes may be present outer to deep fascia also. Dissection begins at the lower end of the gland by incising the fascia just above the digastric muscle. Superficial lobe of the gland is mobilised upwards. *Facial artery* lies in the groove on the deeper aspect of the gland, often either embedding in the gland or runs around the gland with a variable course and so artery has to be ligated twice above anteriorly and below posteriorly. Posterior part of the artery is ligated first using silk or vicryl ligatures. While reflecting the gland upwards from posterior surface hyoglossus with *hypoglossal nerve* is seen and nerve is safeguarded. Hypoglossal nerve at lower part very close to the digastric tendon which is accompanied with lingual vein (*lingual vein* should be ligated) and *lingual nerve* at upper part is identified and safeguarded. Mylohyoid muscle is retracted so as to remove the deep portion of the gland which is in front of the hyoglossus and mylohyoid. Submandibular ganglion is often seen just above the gland which can be sacrificed. Wharton's duct identification and ligation is done. Dissection is done using fine scissor and monopolar cautery. Closer to nerves it is better to use bipolar cautery instead of monopolar especially whenever there is lot of adhesions due to chronic inflammation. *Chronic inflammation* with fibrosis makes dissection difficult risking the injury of hypoglossal and lingual nerves. *Structures in view* after elevation of the submandibular salivary gland are – lingual nerve, chorda tympani, submandibular ganglion and Wharton's duct above; hypoglossal nerve, digastric and stylohyoid muscles below **(Fig. 17-30)**.

Complications of Submandibular Salivary Gland Excision

Complications of submandibular salivary gland excision include—Haemorrhage; infection; injury to marginal mandibular nerve (drooping of saliva with deviation of the angle of the mouth), lingual nerve and hypoglossal nerve (deviation of tongue towards same side); injury to mylohyoid nerve causing anaesthesia over the submental skin.



Fig. 17-30: Submandibular salivary gland stone on X-ray and gross specimen after excision. Here excision of the gland through external approach is the treatment.

Radical Excision of Submandibular Salivary Gland

Radical excision is done in malignant tumours of the submandibular salivary gland. Here gland with soft tissues aound is removed. However nerves are sacrificed only if they are infiltrated. It is difficult to retain marginal mandibular nerve in these patients as oncological clearance is priority. Radical neck lymph node dissection is also usually added along with that. Incision is same but much lengthier; it is often extended below posteriorly on the anterior margin of the trapezius or in the centre of the incision if neck dissection is additional added procedure.

Extraction of Stone from the Submandibular Salivary Duct (Wharton's)

Stone in the Wharton's duct is removed per orally under local anaesthesia. Intraoral X-ray or orthopantomogram is done prior to that. Stay suture using 4 zero vicryl is placed on the duct proximal to the stone. A fine dilator or probe is inserted into the duct opening. Longitudinal incision is placed on the duct over the stone. Stone is extracted using fine haemostat. Saline wash is used to clean the duct and clear any debris. Duct is not sutured instead left open into the oral cavity. Patient is sent with antibiotic coverage **(Figs 17-31 and 17-32)**.

MINOR SALIVARY GLANDS

There are around 450 minor salivary glands which are distributed in lips, cheeks, palate and floor of the mouth. Glands also may be present in oropharynx, larynx, trachea and paranasal sinuses. They contribute to 10% of total salivary volume. *Sublingual salivary glands* are minor salivary glands (almond shaped, weighs 4 gram) one on each side; located in the anterior aspect of the floor of the mouth in relation to mucosa, mylohyoid muscle, body of the mandible near mental symphysis, lateral to genioglossus muscle. Gland drains directly into mucosa through around small ducts or through a duct which drains into submandibular duct. This duct is called as *Bartholin duct.* Mikulicz's disease is common in sublingual salivary gland. Minor salivary glands are *not present* in gingivae and anterior portion of the hard palate.

Incision biopsy of minor salivary gland tumour is done under general anaesthesia if it is posterior. Wide excision of minor salivary gland tumour is done under general anaesthesia with nasal intubation. Wide mouth gag is placed to oral cavity for retraction of jaws. Lesion is excised with 1 cm clearance up to the mucoperiosteum when lesion is in the palate. Raw area is allowed to granulate and heal. If palate is involved by disease, palate is excised. Later proper reconstruction is done with the help of reconstructive surgeon **(Fig. 17-33)**.

ECTOPIC SALIVARY GLAND

Ectopic salivary gland also called as aberrant salivary gland/migrant salivary gland is nothing but ectopic lobe of the juxtaposed salivary gland. It is commonly seen in relation to submandibular salivary gland. Commonest ectopic salivary tissue is *Stafne bone cyst*. It is



Fig. 17-31: Submandibular salivary duct (Wharton's) stone on X-ray and on clinical examination.


Toungue ventral surface
Stay suture on the duct
Frenulum
Wharton's duct
Stone in the Wharton's duct
Floor of the mouth
Incision in the duct
Fine dilator passed into the duct opening
Incised duct is laid open
Extracted stone

Fig. 17-32: Technique of extraction of submandibular salivary duct (Wharton's) stone extraction.


Specimen
Tumour excised area

Fig. 17-33: Minor salivary gland tumour. It needs incision biopsy. It is excised as – wide excision under general anaesthesia. Raw area usually granulates and heals by epithelialisation. Larger defect needs reconstruction. Deeper infiltrating tumours need maxillectomy.

invagination of the juxtaposed submandibular salivary gland into the mandible bone on its lingual aspect. X-ray shows radiolucent area due to the cyst below the angle of the mandible, lower to inferior dental vessels and nerve. Jaws, eyelids, middle ear, paranasal sinus, nose, rarely skin of face and neck are other sites wherein ectopic salivary tissue can be demonstrated.

Chapter

18

Basic Principles in Laparotomy and Laparoscopy

GENERAL PRINCIPLES IN LAPAROTOMY

Laparotomy is opening the abdomen for surgical intervention. Laparotomy can be –

1. *Elective laparotomy*

Elective laparotomy wherein proper preoperative diagnosis has been established with various imaging and biochemical analysis. Even though it is done with proper preoperative diagnosis, being a magic box, in spite of all newer diagnostic aids, finding and diagnosis on opening may be entirely different from what was thought during evaluation. At that stage surgeon should be ready to alter the treatment strategy depending on the need.

2. *Emergency laparotomy*

It is done in trauma and acute abdomen like peritonitis. Even here basic investigations like USG/CT abdomen and haematological assessment are done to proceed with laparotomy at the earliest. Midline vertical incision centered on the umbilicus with curve at umbilicus towards left side is done. This incision is called as *incision of indecision/registrar's incision*. It can be extended above or below easily depending on the need. It also can be extended horizontally if needed **(Figs 18-1 and 18-2)**.



Fig. 18-1: Incision of indecision/registrar's incision.

Proper Bowel Preparation

Proper bowel preparation is essential depending on the type of surgery and condition to which surgery is done. In gastrectomy, pancreatic and biliary surgeries stomach wash, correction of electrolytes is needed; in colorectal surgeries bowel preparation using polyethylene glycol or sodium phosphate is needed. For simple perineal surgeries enema is sufficient. Hydration, bowel antiseptics, keeping ready necessary amount of blood for surgery, antibiotics perioperatively is needed.

Proper Planning

Proper planning should be done in all laparotomy cases. Patient should take proper scrub bath on the morning of the surgery. Skin preparation even though is done on previous night or early morning of the day of surgery, evidence suggests that it should be done on table.

Anaesthesia: General anaesthesia is required. Epidural supplement may be used. Spinal or epidural anaesthesia is sufficient for lower abdominal surgeries.

Position of the Patient

Position of the patient in laparotomy is very important. It may be – *supine*; supine with *one side tilt*; *lateral position* (for kidney/adrenal); *lithotomy position* (for APR/LAR/AR/perineal surgeries/cystoscopic procedures, etc); position for *thoracoabdominal* approach (in Ivor Lewis operation/diaphragmatic surgery/liver surgeries, etc). Head down position is needed in colorectal surgeries to keep small bowel away from surgical dissection field. For upper abdominal surgeries like cholecystectomy head up position is needed often with right up tilt. Strapping of the pelvis and chest wall to the table is needed in patients who need steep head down position.

Other Needs and Principles

Nasogastric tube, urinary catheterisation, central venous line and often arterial line (radial) is needed in major procedures. Often two or three venous lines are needed in major surgery and trauma patients. *Stockings* to both legs from foot to proximal thigh are essential to reduce the incidence of DVT.


Middle midline incision (indecision/ registrar's incision)
Rectus sheath is exposed
Anterior rectus sheath/ linea alba is opened
Peritoneum is held and felt between thumb and index finger
Incised peritoneum is held using haemostats
Balfour retractor

Fig. 18-2: Emergency laparotomy is done using middle-midline incision which can be extended above or below depending on need.

Right selection of the procedure; right way executing it with right principles at right time is important. Selection; execution; timing; implementing; skill are the essential features of successive surgery with best outcome.

Selection of incision; adequacy of incision; good retraction; exposure of the surgical field; proper dissection; no touch or minimum touch technique; haemostasis; on table decision in relation to surgical principles – are the basic need.

Anticipation of problems; perfection in surgical anatomy; tissue touch are important. Live anatomy differs from cadaveric or clinical anatomy (Live anatomy bleeds and gets injured; cadaveric anatomy does not bleed).

In present era speedy surgery is not important; perfect proper surgery is more crucial. But then undue slowness should not be there, as it causes unnecessary increase in the anaesthesia and field exposure time. Accuracy is more important than speed in surgery.

Proper light; proper position; adequate height of the table; good assistants; avoiding repetitive movements; clean bloodless surgical field; knowing the next step – are needed.

Holding the instrument - Fingertip pressure (finger grip) is better to hold instruments than vise grip

Incision is made using scalpel belly while keeping two fingers of the other hand apart

Depth of the incision is assessed by feel and by vision.

During dissection traction by surgeon's other hand and counter traction by assistant's hand helps rapid separation/creation of the tissue planes.

Dissection can be done using scalpel, scissor, and cautery. It is done using cutting cautery. But cutting cautery may not be haemostatic. Haemostasis is achieved using coagulation cautery. Dissection using coagulation cautery will be haemostatic but causes boiling of fat more tissue trauma leading into wound infection. Over coagulation of tissues during cautery dissection ideally should be avoided.

Tissues are held using forceps by gentle maneuver. Skin and tough structures are held using toothed forceps; soft, smooth, delicate structures should be held using non-toothed forceps.

Needle holder should be held between thumb and ring fingers to achieve rotation movement using wrist (not pushing movement). Index and middle fingers are used to steady the handle. Needle is laced at the junction of proximal 2/3rd and distal 1/3rd of the distal jaws **(Figs 18-3 and 18-4)**.

Cleaning and Draping

Cleaning is done using povidone iodine. Solution is collected in a sterile small bowl, sterile folded/rolled gauze or sponge with Rampley's sponge holding forceps is used to clean the abdomen. In perineal surgery cleaning with proper scrubbing should be done after lithotomy position by OT technician prior to formal cleaning by surgeon. Draping is done using sterile green towel. Often sterile plastic sheet (ioban sheet/plastic surgical adhesive drape/plastic incisive drape) is used on the abdomen over the green cloth drape and incision is made through it. Many studies show that plastic adhesive drape reduces the bacterial contamination of the wound and deeper part compared to cloth drape. There is controversy about pricking the towel clip into the skin of that particular corner point or placing interrupted skin sutures over the drape margins to fix it. It may break the barrier into the deeper plane away from the surgical site incision and it is not much confirmed that such fixation will reduce/prevent the bacterial contamination across **(Fig. 18-5)**.



Fig. 18-3: Finger grip holding is better to hold the instrument than vise grip.



Fig. 18-4: Vise grip to hold the instrument. It is used when extra power is needed while using the instrument.



Fig. 18-5: Draping the surgical site using sterile towels.

Incision

Type of incision; possible need for extension of incision, direction of extension – all to be thought of prior to starting the incision.

Principles in abdominal surgery

- Adequate incision - Incision should be long enough for a good exposure
- Splitting the muscle is better than cutting, except rectus muscle
- Avoid cutting nerves and vessels in the abdominal wall
- Adequate retraction - Retract muscle, abdominal organs towards the neurovascular supply
- Adequate exposure of surgical site and surrounding field
- Adequate meticulous dissection
- Adequate haemostasis
- Adequate proper closure; if required with a drain (tube). Insert a drainage tube through a separate incision.
- Transverse incisions are better than vertical incisions.

Requirements

- Accessibility
- Extensibility
- Security.

Surgical Anatomy of Abdominal Wall

Anterior Abdominal Wall

The anterior abdominal wall is a musculofascial dynamic structure which maintains intra-abdominal pressure for various physiological functions. It has got three paired flat muscles, two recti abdominis muscles and linea alba in midline. These are anteriorly related to skin, subcutaneous tissue and superficial fascia; posteriorly related to transversalis fascia and peritoneum. *External oblique fascia* (external layer of the fascia of external oblique muscle is also called as *innominate fascia of Gallaudet*) is thin fascial covering of external oblique muscle and fascia which forms intercrural fibres of the superficial inguinal ring; and it extends below into the scrotum as external spermatic fascia. *Anterior abdominal wall* has got anterolateral part which consists of external and internal oblique and transversus abdominis muscles; and a midline part containing rectus abdominis and pyramidalis muscles **(Fig. 18-6)**.



Fig. 18-6: Layers of the abdominal wall – as seen in paramedian incision.

External Oblique Muscle

It arises from middle of body of lower eight ribs running below/downwards, front/forwards and medially inserting into xiphoid process, linea alba, pubic symphysis, pubic crest, pectineal line of pubis and anterior 2/3rd of outer lip of the iliac crest. It is supplied by lower 6 thoracic nerves. Lower free border of the external oblique aponeurosis forms inguinal ligament. Triangular opening in its aponeurosis above the pubic crest is called as superficial inguinal ring **(Fig. 18-7)**.


ORIGIN
Linea alba
External oblique muscle
External oblique aponeurosis
Posterior free border
Iliac crest
Inguinal ligament (lower free border)
INSERTION
Superficial inguinal ring

Fig. 18-7: External oblique muscle.

Internal Oblique Muscle

It arises from lateral 2/3rd of inguinal ligament, anterior 2/3rd of intermediate part of iliac crest, thoracolumbar fascia; runs upwards, forwards and medially to insert into lower 4 ribs and cartilages, xiphoid process, pubic crest, pectineal line of pubis. It is supplied by lower 6 thoracic nerves, 1st lumbar nerve. Aponeurosis below the level of umbilicus remains as a single layer forming the anterior rectus sheath and lineal alba. Above aponeurosis splits into anterior lamina which passes medially in front of rectus abdominis and posterior lamina which passes behind rectus abdominis which ends below midway between umbilicus and pubic symphysis as linea *semicircularis of Douglas* (arcuate line). *Semilunar line of Spieghel* lies in lateral border of the rectus sheath from pubic tubercle to the tip of the costal cartilage of 9th rib **(Fig. 18-8)**.


Xiphoid
INSERTION
Linea alba
Aponeurosis
Internal oblique muscle
Thoracolumbar fascia
Arcuate line
ORIGIN
Conjoint tendon
Inguinal ligament

Fig. 18-8: Internal oblique muscle.

Transverse Abdominis Muscle

It originates from lateral 1/3rd of inguinal ligament, anterior 2/3rd of inner lip of iliac crest, thoracolumbar fascia, lower 6 cartilages with fibres running horizontally forwards inserting into an aponeurosis extending from xiphoid process, linea alba, pubic crest, pectineal line of pubis. Lowest fibres fuse with lowest fibres of internal oblique to form conjoined/conjoint tendon. It is supplied by lower 6 thoracic and first lumbar nerves. Neurovascular plane of abdomen lies between internal oblique and transverse abdominis muscles **(Fig. 18-9)**.

Rectus Abdominis Muscle

It arises from lateral part of pubic crest (lateral head) and anterior pubic ligament (medial head) runs vertically upwards to insert into xiphoid process and 7th, 6th and 5th costal cartilages. It is supplied by lower 6 thoracic nerves. There are three tendinous intersections one at xiphoid, one at umbilicus level and another one between two which are adherent to anterior half of muscle and anterior wall of rectus sheath. They are due to embryologic segmental origin of muscle which adds to the power of muscle. Tendinous intersections *do not extend* into the posterior rectus sheath **(Fig. 18-10)**.

Rectus sheath is an aponeurotic sheath which covers the rectus abdominis muscle in front and behind. Rectus sheath contains rectus abdominis muscle and pyramidalis in its lower part. Pyramidalis lies in front of the lower part of the rectus muscle. Superior epigastric artery enters the sheath by passing between the costal and xiphoid origins of the diaphragm crossing upper margin of transversus abdominis muscle behind the 7th costal cartilage running behind the rectus muscle in front of the posterior rectus sheath to anastomose with the inferior epigastric artery. Inferior epigastric artery enters the sheath behind the muscle by passing across the arcuate line. Superior and inferior epigastric veins also accompany the arteries. Terminal branches of the lower 5 intercostal nerves and subcostal nerve enter the sheath after piercing the posterior rectus sheath at its lateral part running in front of the epigastric vessels to pierce the rectus muscle.

Anterior rectus sheath is complete covering rectus entirely from origin to insertion. Its upper ¾ is formed by external oblique


Xiphoid
Linea alba
7th rib
Aponeurotic posterior rectus sheath
Transversus abdominis muscle
INSERTION
INSERTION
ORIGIN
12th rib
ORIGIN
Thoracolumbar fascia
Inguinal ligament
Arcuate line
Conjoint tendon

Fig. 18-9: Transverse abdominis muscle.



Fig. 18-10: Rectus abdominis muscle.

aponeurosis and anterior lamina of internal oblique. Its lower ¼ is formed by all three aponeurosis. In this part aponeurosis of transversus and internal oblique muscles are fused; aponeurosis of external oblique remains separate.

Posterior rectus sheath is deficient above the costal margin and below the arcuate line. Between the costal margin and arcuate line it is formed by posterior lamina of internal oblique aponeurosis and transversus abdominis aponeurosis. Midway between the umbilicus and pubic symphysis posterior rectus sheath ends as arcuate line/ linea semicircularis /fold of Douglas which is concave downwards.

In upper ¾ of the abdominal wall – right and left recti are separated; both anterior and posterior rectus sheaths are present; anterior rectus sheath is formed by external oblique aponeurosis and anterior lamina of internal oblique; posterior rectus sheath is formed by posterior lamina of internal oblique aponeurosis and transversus abdominis aponeurosis; linea alba is well developed; external oblique aponeurosis and fascia is weak.

In the lower ¼ of the anterior abdominal wall - right and left recti are very close to each other; anterior rectus sheath only is present which is formed by all 3 muscular aponeurosis; posterior rectus sheath is absent; external oblique fascia is stronger; lineal alba is not well developed.

Muscles of the Posterior Abdominal Wall

They are psoas major, psoas minor, quadrates lumborum and iliacus.

Psoas major arises from body and transverse processes of all lumbar vertebrae to insert into the tip and medial part of the lesser trochanter of the femur after passing behind the inguinal ligament along with the iliacus tendon (lateral part of the lesser trochanter). It is supplied by L_2, L_3, L_4 spinal nerves.

Psoas minor is small muscle in front of the psoas major arises from bodies of T_{12} and L_1 vertebrae to insert into the pectin pubis and iliopubic eminence. It is supplied by L_1. *Iliacus* arises from upper 2/3rd of inner aspect of fossa of ilium, upper lateral part of the sacrum to insert into lateral part of the lesser trochanter along with psoas major. It is supplied by femoral nerve.

Quadratus lumborum arises from transverse process of L_5 vertebra and inner lip of iliac crest to insert into medial part of the anterior surface of 12th rib and transverse processes of upper 4 lumbar vertebrae. It is supplied by spinal nerves T_{12} to L_4.

Fascia Transversalis (Cooper's Fascia)

It is the fascia that lines the inner surface of the transversus abdominis muscle separated from the peritoneum by extraperitoneal connective tissue. In front it is adherent to linea alba above the umbilicus; behind merges with anterior layer of thoracolumbar fascia and renal fascia; above with diaphragmatic fascia; below it is attached to inner lip of iliac crest, inguinal ligament; medially it is attached to pubic tubercle, pubic crest and pectineal line which prolongs down as anterior layer of femoral sheath. It also forms internal spermatic fascia around the cord. Deep inguinal ring is U/lambda/oval shaped opening 1.25 cm above the midinguinal point (between pubic symphysis and anterior superior iliac spine) which is lateral to inferior epigastric artery, transmits spermatic cord in males and round ligament in females. In the inguinal area transversalis fascia is *bilaminar* enclosing the inferior epigastric vessels. *Space of Bogros* is extension of the retropubic *space of Retzius* which is located beneath the posterior lamina of transversalis fascia and in front of the peritoneum. Inlay preperitoneal mesh repair is done by placing mesh in this space. Thickening of the transversalis fascia at medial side of the internal ring and in front of the inferior epigastric vessels is called as *interfoveolar Hesselbach's ligament*.

Endoabdominal Fascia

Endoabdominal fascia is connective tissue that lines inner aspect of the entire abdominal musculature. Part in relation to transversus abdominis is called as fascia transversalis. It forms iliac, diaphragmatic and renal fascia.

Deep Nerves of the Abdominal Wall

Lower 5 intercostal and subcostal (Lower 6 thoracic primary rami) nerves and iliohypogastric and ilioinguinal nerves supply the anterior abdominal wall. *Lower 5 intercostal nerves* pass through the slips of origin of transversus abdominis muscles; run between transversus abdominis and internal oblique; pierce the posterior lamina of internal oblique aponeurosis to reach rectus sheath; then pass behind the rectus sheath in front of the epigastric vessels, pierce the rectus muscle to continue as anterior cutaneous nerve. Before piercing it supplies the anterior rectus sheath, transversus abdominis, internal oblique, external oblique and rectus abdominis. During its course it also gives lateral cutaneous nerve of the abdominal wall through flat abdominal muscles. *Battle's incision* which is pararectal incision will injure these nerves causing weakening of the rectus muscle and so is avoided.

Subcostal nerve, anterior primary ramus of 12th thoracic nerve after traveling behind the diaphragmatic lateral arcuate ligament, passes in front of the quadrates lumborum and then pierces the transversus abdominis to run like other intercostal nerves. It supplies pyramidalis muscle and gluteal region as lateral cutaneous branch.

Note: There are 11 intercostal nerves and one subcostal nerve.

Blood Supply of Abdominal Wall

It is divided into superficial and deep vessels.

Superficial vessels are superficial epigastric, superficial circumflex iliac and superficial external pudendal arteries – are branches of femoral artery. They travel towards umbilicus in subcutaneous plane. Superficial epigastric artery communicates with opposite superficial epigastric artery and all three communicate with deep arteries.

Deep arteries are posterior intercostal arteries (10, 11), anterior branches of 4 lumbar and subcostal arteries and deep circumflex iliac artery. Deep arteries travel between transversus abdominis and internal oblique muscles. Rectus sheath is supplied by superior and inferior epigastric arteries. *Superior epigastric artery* is one of the two terminal branches of the internal thoracic/mammary artery. It originates at 6th intercostal space enters the abdomen between costal and xiphoid origin of the diaphragm, enters the rectus sheath from above behind the 7th costal cartilage. It descends downwards communicating with inferior epigastric artery behind the rectus muscle. Branches are muscular, cutaneous, hepatic along the falciform ligament and anastomotic to opposite side artery.

Inferior epigastric artery (IEA) originates from external iliac artery just above the inguinal ligament runs upwards and medially in the extraperitoneal connective tissue between peritoneum and posterior lamina of transversalis fascia initially medial to internal ring; pierces the transversalis fascia at the lateral border of the rectus muscle; runs in front of the arcuate line supplying the rectus and ends by anastomosing with superior epigastric artery. Branches are – muscular, cremasteric, pubic, and cutaneous. *Cremasteric branch* after travelling laterally towards deep ring supplies cremaster and runs along the spermatic cord. Pubic branch runs medially along the pubic bone to communicate with pubic branch of anterior division of obturator artery. Often obturator artery may be replaced by this pubic branch of inferior epigastric artery as abnormal/aberrant obturator artery. This pubic branch crosses over femoral ring and Cooper's ligament. This may be injured during fixation of mesh in TEP repair or femoral hernia repair causing torrential bleeding from both cut ends. As medial cut end retracts deep into the obturator fat and fascia it is difficult to control bleeding. This area is often called as *circle of death*. Inferior epigastric vein is medial to IEA.

ABDOMINAL INCISIONS

Principles in Abdominal Incision

- Incision should give adequate proper *access* to the surgical site in the abdomen – well planned; with adequate exposure of adequate length. Patient should lie symmetrical the operation theatre table.
- It should be amenable for *extension* as needed. Muscle should be split as much as possible, not cut in vertical and oblique incisions.
- Incision should be chosen with plan so as to have proper accessibility, extensibility, safeguard of function, cosmetically acceptable and with possible least complications like dehiscence and incisional hernia.
- Care should be taken while opening the peritoneum. Abdominal contents should not be injured especially bowel. This is more important aspect in previous laparotomy patients. Peritoneum should be incised using fine scissor or scalpel after feeling the site of incision using fingers for any adherent bowel or omentum. One should not use cautery to incise peritoneum.
- If there is previous incision scar (re-laparotomy), care should be taken not to injure bowel while opening the peritoneum; it is better to open the peritoneum at a new site.
- Layer by layer incision should be done.
- Extension across umbilicus is done from left side of the umbilicus.
- Further cutting of the peritoneum after incising should be done under vision with two fingers underneath the peritoneum to prevent injury to bowel.
- Wound dehiscence is less in transverse incision than vertical incision.
- Drain should be kept through a separate incision; not through the main wound. If drain is passed through the main wound it will prejudice the strength of the final scar.
- Proper anaesthetic relaxation is essential before closure of the abdomen otherwise closure will be troublesome.

Exploratory Laparotomy

All opened abdomen should be explored by putting hand inside (right hand usually) – It is done through a proper method called as *laparotomy circuit*.

Outer laparotomy circuit	*Inner laparotomy circuit*
Begins at oesophagogastric junction	Ligament of Treitz
↓ *Anticlockwise*	↓ Oblique from left to right
Stomach duodenum, liver, gallbladder	Small bowel – jejunum and ileum with their mesentery
↓	↓
Right colon, caecum, pelvis	To reach Ileocaecal junction
↓	↓
Sigmoid colon, descending colon, splenic flexure	*Completion of inner circuit.*
↓	
Spleen, left kidney, pancreas, aorta and transverse colon	
↓	
Completion of outer circuit.	

Complications of Abdominal Incision

- Wound infection.
- Surgical site infection (SSI).
- *Fascial dehiscence* – (Burst abdomen): Dehiscence is due to infection, severe cough and vomiting and sudden raise in intra-abdominal pressure. Initially sudden severe pain occurs; feeling of giving way with serosanguineous discharge is common. Abdominal viscera (bowel) will be visible through the given away wound. Occasionally evisceration occurs with intestine coming out of the abdominal wound. Patient is shifted to operation theatre. Under general anaesthesia, bowel contents are placed inside the abdominal cavity. All layer through and through monofilament interrupted sutures are placed after a through wash. Previously retention (tension) sutures are practiced. Usually patient recovers well unless there is bowel injury. *L. E Hughes double near and far suture* or *modified Smead-Jones* single layer sutures are better in such situation.
- *Incisional hernia* – It is due to wound sepsis, peritoneal cavity infection, malnutrition and deficiencies, nerve injuries, weak rectus, obesity, precipitating causes like cough, straining, urinary problem and constipation.

- Injury to bowel during laparotomy.
- Fistula formation. Gastrointestinal fistula may be biliary, faecal or pancreatic. It may be end or lateral; high or low output.
- *Nerve injury* - Wound pain. Nerve injury can occur in muscle cutting incisions, lateral incisions, laparoscopic dissection. Ilioinguinal nerve may get injured after appendicectomy causing right sided direct inguinal hernia. Open inguinal hernioplasty may cause inguinodynia postoperatively. Intercostal nerves may get injured in Kocher's subcostal incision or thoracoabdominal incision. Pfannensteil incision may injure hypogastric nerve.
- Adhesion and its complications.
- *Paralytic ileus* – it is common after 12-24 hours; but depends on the type and condition for which surgery is done. Causes like electrolyte imbalance, sepsis should be ruled out. Often nasogastric aspiration and flatus tube insertion may be required.

Factors affecting the strength of the scar

- Type of surgery (acute abdomen, surgery for malignancy, major surgery)
- Obesity
- Pregnancy
- Straining
- Cough
- Ascites
- Nutrition
- Diabetes
- Immunosuppression
- Type of incision

Abdominal Incisions may be –

- Vertical or transverse. Vertical may be midline or paramedian. Horizontal incisions are better.
- Incision may be with extension or without extension.
- Incision may be upper or lower. Upper incisions are better.
- Muscle retraction or muscle splitting or muscle cutting **(Fig. 18-11)**.

Different Abdominal Incisions (Figs 18-12 to 18-14)

- Upper midline.
- Upper right paramedian.
- Upper left paramedian.
- Kocher's incision (right subcostal).
- Left subcostal.
- Bucket handle.
- Upper horizontal.
- Thoracoabdominal.
- Umbilical crease incision.
- Subumbilical.
- Incision for lumbar sympathectomy.
- Lower midline.
- Lower right or left paramedian.
- Incisions for appendicectomy—McBurney's, Rutherford Morison's, Lanz, laparoscopic.
- Pfannenstiel incision.
- Lower horizontal .

Classification of abdominal incisions

Vertical incision

- *Midline incision* – upper, lower or entire length from xiphoid to pubis
- *Paramedian incisions* – right, left, upper, middle, lower. Muscle retracting/muscle splitting/pararectal (Battle's)

Transverse incisions

- *Upper abdominal* transverse – one or both sides
- *Lower abdominal* transverse
  - – Transverse muscle dividing lower abdominal incision
  - – Maylards incision
  - – Joel Cohen's incision
  - – Pfannenstiel incision
  - – Cherney's incision
  - – Kustner's incision

Contd...


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
1. Right subcostal incision
2. Left subcostal incision
3. Upper midline
4. Right upper paramedian
5. Subumbilical
6. Left lower paramedian
7. Lower midline
8. Left thoracoabdominal
9. Rooftop (Chevron) incision
10. Upper horizontal
11. Left lumbar sympathectomy incision
12. Lower horizontal
13. Lanz incision
14. McBurney's incision
15. Pfannenstiel incision
16. Incision for inguinal hernia

Fig. 18-11: Different abdominal incisions.

Contd...

  - Turner Warwick's incision
  - Subumbilical incision

Oblique incisions

- *Kocher's* subcostal Incision
  - Classical rectus muscle cutting
  - Modified rectus muscle retracting
  - Mini lap Kocher's incision
- Chevron (Roof top modification) incision
- Mercedes Benz modification
- Appendicectomy incisions
  - *McBurney's* /Mac Arthur's Grid iron muscle splitting incision
  - *Rutherford Morrison's* muscle cutting (laterally upwards) incision
  - *Rocky Davis or Elliot's* muscle cutting (medially and downwards) incision
  - *Lanz crease* (interspinous crease) line incision
  - Oblique iliac incision (*Abbernethy's*), muscle cutting incision

Abdominothoracic incisions



Fig. 18-12: Incision for liver resection.

MIDLINE INCISION

It is commonly advocated incision. It can be upper midline/lower midline or both upper and lower lengthy midline incision. Midline incision is easier to reach across linea alba with rapid access, minimum blood loss, and also quicker and easier to close. Extension above or below will be easier and faster. In emergency surgeries and common elective surgeries midline incision is better. Midline incision gives excellent adequate exposure of the abdomen. It can be extended below, above, horizontally or obliquely or as thoracoabdominal when needed. Gastrectomy, pancreaticojejunostomy, hiatus hernia repair, pseudocyst surgery, exposure of aorta, colectomy and biliary tract surgeries can be done with midline incision **(Figs 18-15 to 18-18)**.

Upper Midline Incision

Skin is incised vertically in midline from xiphoid to umbilicus. Superficial fascia, external oblique fascia is incised. Whitish crisscross tough linea alba is visible. It is incised using monopolar cautery or 22 no. blade. Once incised in full depth linea alba separates away to visualise the extraperitoneal pad of fat and peritoneum. Extraperitoneal pad of fat is separated of the peritoneum gently. Peritoneum appears like a shiny whitish thin structure. It is carefully held using a haemostat during expiration phase. One should be sure not to hold the deeper contents. Another haemostat is applied 5-10 mm away on the peritoneum horizontally so that peritoneum fold is lifted properly. Lifted fold of peritoneum is gently moved to make any content if at all to get dislodged and fold is pinched between the thumb and fingers to confirm that no content is felt. Peritoneum is incised using blade obliquely or using scissor towards just left of the midline which is avascular. Once peritoneum is opened air enters inside to distend peritoneum and content to fall deep. Both haemostats are reapplied to cut edges of the peritoneum. Using scissor peritoneum is cut above and below under vision or by placing fingers under the peritoneum to guard the contents with forward lift of the abdominal wall. One should be careful about the adhesions in the peritoneum in the line of cut. Extension down is done by curving the incision left side of the umbilicus. Right side of umbilicus is vascular and falciform ligament is attached towards right side hence incision is made on the left side of the umbilicus. Few advocate incision vertically through the umbilical midline. Only abdominoperineal resection (APR) for carcinoma rectum incision is extended above from right side of the umbilicus as permanent colostomy is placed on the left side in left iliac fossa. Occasionally when approach to the OG junction is inadequate


McBurney's incision
Lanz crease incision
Rutherford Morrison's extension
Rocky Davis extension/ incision

Fig. 18-13: Incisions used for open appendicectomy.



Fig. 18-14: Horizontal incision at umbilical level.


Midline incision
Rectus muscle
Superficial fascia
Skin
Subcutaneous fat
External oblique fascia
Anterior rectus sheath
Epigastric vessels
Transversalis fascia
Peritoneum
Extraperitoneal fat
Peritoneal cavity
Posterior rectus sheath

Fig. 18-15: Layers which will come across while making the midline incision.


Colostomy site
Upper midline
Lengthy midline xiphoid to pubis
Upper midline extension down across left of the umbilicus
Lower midline extending above across left of the umbilicus
Lower midline extending above across right of the umbilicus in APR to facilitate colostomy

Fig. 18-16: Different types of midline incisions.

proximal extension is done by cutting the xiphoid process. Care must be taken not to injure terminal branches of internal mammary artery which can cause bleeding **(Fig. 18-19)**.

Lower Midline Incision

In the lower midline incision posterior rectus sheath is deficient, making incision downwards needs care as urinary bladder may get injured. Prevesical fat should not be incised. This fat cannot be separated of the deeper bladder. Bladder should be emptied before giving anaesthesia or an indwelling urinary catheter may be needed.

Midline Incision Closure

It is done using nonabsorbable monofilament suture material *number zero or 1*. Polyethylene/polypropylene/nylon/PDS (polydioxanone) is used. Silk and catgut are not used. Many advocate delayed absorbable suture material like no. 0 or 1 vicryl; but it is not as ideal as nonabsorbable monofilament suture material. *Continuous mass closure* is sufficient. Often locking sutures are placed. Peritoneum bite is not always necessary/compulsory as it will appose naturally when anterior layers are sutured. During continuous suturing in between supporting knots are placed at few points to prevent loosening and giving way of the suture line. Minimum distance to be kept between each bite is 1 cm; each bite should be taken 1 cm away from the cut margin. Linea alba/anterior rectus sheath may retract after incision; and often bite is taken only from external oblique fascia of Gallaudet's instead of rectus sheath especially in the lower abdomen. This fascia is not strong and so will eventually dehisce to cause incisional hernia. One should maintain adequate uniform tension on the suture material. Over pulling may cause tissue strangulation. Length of the suture material required is 3 times the length of the abdominal wound. One should be careful while closing incision close to pubis due to close proximity of bladder. Inadvertent bite of the urinary bladder should be avoided. Similarly closing incision adjacent to umbilicus should be perfect otherwise defect may be left leading to incisional hernia at that site **(Figs 18-20 to 18-22)**.

Ending of the continuous suture is done using needle holder by knotting to the previous bite loop. It is better and stronger. At least 4-5 knots should be placed to make it stronger. Knot of the nonabsorbable suture material will persists and may project towards skin causing pain on the skin later and so knot should always be buried under the rectus sheath. Many use Aberdeen knot at the end in continuous suture. Interrupted single layer mass closure using nonabsorbable suture material is also used with each suture 1 cm apart. Again often peritoneum is closed first by continuous suturing using 2 zero vicryl and rectus sheath is closed by continuous or interrupted (*layer by layer)* suturing. But now it is proved that there is no additional advantage by layer by layer closure.


Skin
Subcutaneous tissue
Superficial fascia
External oblique fascia
Linea alba
Extraperitoneal pad of fat
Peritoneum
Extraperitoneal pad of fat

Fig. 18-17: Upper midline incision. It can be extended downwards from left of the umbilicus.



Extension on to the rectus horizontally

Extension horizontally in subcostal region

Extension towards subcostal angle left side

Extension across chest wall as thoracoabdominal

Fig. 18-18: Extension of midline incision in different ways – horizontally, obliquely, or as thoracoabdominal.


Opening the linea alba using cautery
Exposed peritoneum is held with two haemostats
Linea alba
Peritoneum
Peritoneal fold is felt between fingers to confirm adhesions are not present
Incising the peritoneum using blade holding it obliquely
Holding the cut edges with haemostats
Cutting the remaining peritoneum using scissor

Fig. 18-19: Midline incision approach to peritoneal cavity.


Sergeant retractor is used during abdominal closure
Skin stapler used here to close the skin Interrupted mattress nonabsorbable sutures can also be used

Fig. 18-20: Technique of closure of the midline.


Continuous all layer closure
Continuous all layer locking suture closure
Interrupted suture closure

Fig. 18-21: Different methods to close the midline.

Fig. 18-22: Counting mops properly is very important prior to closure. Number of mops taken to theatre table should be written in the theatre board.



Fig. 18-23: Left paramedian incision scar.

PARAMEDIAN INCISION

In olden days paramedian incision was the most commonly advocated one; but now it is not commonly used. Paramedian incision is placed vertically parallel and 2.5 cm away from midline. It can extend from costal margin to pubis.

Right upper paramedian incision is used for cholecystectomy, biliary surgery, pyloroplasty, approach to right adrenal gland and liver cyst. Right mid-paramedian is used for laparotomy in doubtful/unknown/unsure diagnosis, approach to intestines and this approach is later extended depending on the pathology found after opening the abdomen. Right lower paramedian is used in burst appendicitis with peritonitis, right hemicolectomy. Left upper paramedian incision is used in vagotomy, gastrectomy, hiatus hernia repair and splenectomy. Left lower paramedian incision is used in left hemicolectomy **(Fig. 18-23)**.

Skin, subcutaneous tissue, superficial fascia, external oblique fascia, anterior rectus sheath are incised layer by layer using no. 22 blade with no. 4 knife handle. Medial edge of the anterior rectus sheath is held upwards using series of haemostats. Rectus muscle is retracted laterally. In the upper part anterior rectus sheath is adherent to muscle on the medial part through tendinous intersections. These intersections should be released using monopolar cautery or sharp dissection. Posterior rectus sheath is visible behind rectus muscle. Vessels and nerves are in the middle level of the rectus muscle. Vessels run vertically. Segmental nerves after piercing posterior rectus sheath run laterally in front of the vessels and enter the muscle at same level just lateral to the middle of the rectus muscle. Posterior rectus sheath is deficient below the arcuate line. Fascia transversalis and extraperitoneal fat is incised; peritoneum is held using two haemostats and incised using blade after confirming that no content is present; cut edges are held using haemostats and by guarding abdominal contents using two fingers peritoneum is opened at both ends along its entire length of incision **(Figs 18-24 to 18-27)**.

Modifications of Paramedian Incision

Rectus muscle may be split in the line of incision on the medial part of the muscle bulk to avoid injury to nerves and also be used for quick access.

Battle's incision which is pararectal incision will injure these nerves causing weakening of the rectus muscle and so is avoided.

Mayo–Robson incision: Right upper paramedian incision may extend upwards towards xiphoid process in midline as Mayo–Robson incision. One should ensure that in such extension, superior epigastric artery is not injured or otherwise should be securely ligated to prevent troublesome haemorrhage.

Paramedian incision can be extended into the thorax whenever needed as thoracoabdominal incision **(Fig. 18-28)**.


Rectus muscle
Anterior rectus sheath
Skin
Subcutaneous tissue
Superficial fascia
External oblique fascia
Segmental nerves
Transversalis fascia
Extraperitoneal fat
Peritoneum
Epigastric vessels
Posterior rectus sheath
Peritoneal cavity
A
Right paramedian rectus retracting (laterally) incision
Left paramedian rectus splitting incision
B

Fig. 18-24: Layers in paramedian incision approach.

Closure of Paramedian Incision

Paramedian incision is closed in layers. First posterior rectus sheath with peritoneum is closed using monofilament nonabsorbable or *delayed absorbable* like vicryl suture material. Anterior rectus sheath is closed using *monofilament nonabsorbable suture* no. zero polyethylene or polypropylene or nylon as continuous sutures.

Advantages

Paramedian incision is safe without cutting the muscle. It creates strong scar with 'trap door' effect.

Disadvantages

Rectus muscle is exposed and dissected and so there are chances of muscle getting atrophied. Incision is laborious and time consuming and difficult to extend above and below which invariably damages muscle and often nerves. Access to the contralateral abdomen is usually inadequate.

TRANSVERSE INCISIONS

It may be upper transverse or lower transverse incision. It is the incision used in infants and early childhood. It is muscle cutting incision. Muscle is cut in line of incision.

Upper Transverse Abdominal Incision

It is placed at transpyloric plane or midway between xiphoid and umbilicus. It is muscle cutting incision. Rectus muscle is cut; but its nerve supply is not interfered as it has got segmental nerve supply. Rectus muscle in upper abdomen after cutting will not retract due to tendinous intersections. It extends from anterior axillary line on one side to other side; but length depends on the side of the pathology which can be variable as needed. Skin, subcutaneous tissue, fascia, superficial fascia, anterior rectus sheath on both sides, recti on both sides, external and internal oblique muscles on both sides, transverse abdominis muscles on both sides are cut. Vessels deeper to rectus muscle are ligated securely. Posterior rectus sheath and transversalis fascia are incised. Peritoneum is held with two haemostats and incised. It is cut in the line of incision transversely. Muscles are cut using monopolar cautery. Postoperative pain is less and chances of wound dehiscence and incisional hernia are rare.

In infants and early childhood, costal angle is obtuse, abdomen is small and wide, muscles are thin, and pelvis is not yet developed and so not deep. Approach to entire abdomen is possible; contracture will not occur compared to vertical scar; cosmetically better. Umbilical vein in falciform ligament may be patent and so requires firm ligation. (In infants while putting infraumbilical transverse incision, one has to be aware of that two umbilical arteries in paramedian positions on either side may be patent and so needs ligation).

Closure of upper transverse incision is done either as layer by layer using vicryl; or lateral muscles are closed as mass closure with suturing posterior rectus sheath, rectus muscle and anterior rectus sheath.


Right upper paramedian incision
Right midparamedian incision
Right lower paramedian incision
Right full length paramedian incision
Left sided paramedian incision

Fig. 18-25: Different types of paramedian incision.


Skin
Subcutaneous tissue
Anterior rectus sheath
Rectus muscle
Anterior rectus sheath
Posterior rectus sheath with peritoneum
Rectus muscle retracted medially
Tendinous intersections
Tendinous intersections are cut using scalpel blade or scissor or cautery
Medial cut edge of anterior rectus sheath
Posterior rectus sheath with peritoneum
Laterally retracted rectus muscle

Fig. 18-26: Technique of paramedian incision.



Fig. 18-27: Right paramedian incision.


Mayo-Robson incision
Thoraco-abdominal extension incision

Fig. 18-28: Extensions which can be done in paramedian incision.


Lower transverse incision
Maylard's/Mackenrodt's incision
Joel Cohen's incision
Pfannenstiel incision
Cherney's incision

Fig. 18-29: Different types of lower abdomen transverse incisions.

Advantages

It gives good exposure of the upper abdomen. Healing is supported by muscle contraction which pulls it transversely. Segmental nerve supply is preserved. Scar contracture is less here compared to vertical.

Disadvantages

Bleeding from epigastric and muscular vessels is troublesome. It takes long time to complete the incision.

Lower Transverse Abdominal Incisions

It is not commonly used; instead Pfannenstiel incision is used. Lower infraumbilical transverse incision is often used in infants and children; here posterior rectus sheath is not formed; recti muscles will retract as there are no tendinous intersections; and so often cause difficulty in apposing the recti firmly. Layers are closed in similar fashion as upper transverse incision **(Fig. 18-29)**.

Pfannenstiel Incision (Pfannenstiel Hermann Johann 1862–1909; German Gynaecologist)

It is rectus *muscle separating/retracting* transverse incision. It is used to approach pelvis. It is commonly used in gynaecological surgery like caesarean section or hysterectomy. In urology procedures also this incision is used like in retropubic urethroplasty.

Incision is placed in suprapubic region 1 cm above the pubis with slight convexity downwards. Laterally incision extends beyond outer margin of the rectus muscle. Skin, subcutaneous tissue and superficial fascia are incised. Anterior rectus sheath is incised in the line of incision; upper flap of the sheath is raised upwards towards umbilicus using scissor; lower flap is raised up to the pubis. Recti are separated from midline laterally. Peritoneum is visualised with extraperitoneal pad of fat. Urinary bladder is visible in the lower part. Peritoneum is held with two haemostats in the upper part midline. It is incised and opened vertically in both directions above and below. Below it is incised until the dome of the urinary bladder. One should be careful below not to incise urinary bladder. Head down position with self retaining retractor facilitates further operative steps **(Figs 18-30 and 18-31)**.

Closure of Pfannenstiel Incision

Closure of Pfannenstiel incision is done layer by layer; peritoneum vertically using vicryl continuous suture; rectus muscle is just apposed using few interrupted vicryl sutures (it should not be very tight so as to strangulate the muscle); anterior rectus sheath is closed using continuous monofilament nonabsorbable sutures. Subcutaneous tissue is closed using interrupted 3 zero vicryl; skin is closed using subcuticular suture.

Advantages

It is cosmetically better; less painful; heals rapidly; less chance of incisional hernia compared lower midline incision.

Disadvantages

It is difficult to extend more laterally if needed in case large gynaecological tumours. It may cause injury to inferior epigastric vessels causing troublesome bleeding. It may injure the T 11 nerve, iliohypogastric nerve and subcostal nerve causing muscle weakness. Entrapment of ilioinguinal or iliohypogastric nerve can occur. Lateral extension may predispose to inguinal hernia. Haematoma, seroma, abscess formation can occur. Femoral nerve injury can occur occasionally. This incision *should not be used* in oncological surgery due to limited access to lymph node clearance. Its proximity to infected area (perineum) may predispose sepsis.

Joel Cohen's Straight Transverse Lower Abdominal Incision

It is used for caesarean section delivery. It is a straight transverse incision through skin only, 3 cm below the level of the anterior superior iliac spines (higher than the Pfannenstiel incision). The subcutaneous tissue is opened only in the middle 3 cm. The fascia is incised transversely in the midline then extended laterally with blunt finger dissection. Finger dissection is used to separate the rectus muscles vertically and outwards laterally and to open the peritoneum. All the layers of the abdominal wall are stretched manually to the extent of the skin incision. The urinary bladder is pushed below by gentle blunt finger dissection. The uterine muscle is incised transversely in the midline but not to breach the amniotic sac, then opened and extended laterally with finger dissection. It is found that this approach for caesarean section delivery reduces the operating time, blood loss and postoperative hospital stay.

Cherney's Incision

Incision is like Pfannenstiel but still lower than it with *tendon detaching approach*. After incising the skin and subcutaneous tissue above the pubic symphysis, anterior rectus sheath is incised transversely which is separated from underlying rectus and pyramidalis muscles above and below. Posteriorly these muscles are separated from the urinary bladder by blunt finger dissection. Tendons of these muscles are cut 5 mm above the pubic symphysis. Muscles with tendons are retraced and reflected above to expose the peritoneum which is incised transversely. Cherney's incision provides excellent access and exposure to the retropubic space of Retzius for retropubic urethropexy and paravaginal repair. Exposure is the main advantage to Cherney's incision. It is more time consuming due to the dissection required to separate the muscles and tendons from the underlying tissues. Injury to inferior epigastric arteries is a possibility. Reattachment of the tendons to the pubic symphysis is a must during closure which is tedious.

Maylard's Incision

It is muscle cutting transverse incision. It is also called as *Mackenrodt incision*. Incision is placed at the level of anterior superior iliac spine with convexity downwards. Anterior rectus sheath is incised but not separated from the rectus muscle to prevent it from getting retracted on either sides; (often after cutting the rectus muscle, its edge is sutured to cut edge of the anterior rectus sheath to prevent retraction using mattress vicryl sutures). Incision over the anterior rectus sheath is extended laterally through the aponeurosis of the abdominal wall up to 2 cm medial to the anterior iliac crest. Rectus muscle is cut transversely using cautery or scalpel. Inferior epigastric vessels are dissected, ligated and divided. Transversalis fascia and peritoneum are incised transversely to expose the abdomen. All layers are cut at the level of anterior superior iliac spine. Here exposure to lateral pelvis is excellent and so oncological procedures like pelvic lymphadenectomy and staging can be done exponentially. It is also very useful for pelvic endometriosis. This incision should be placed with a preoperative plan. Pfannenstiel incision cannot be modified as Maylard's incision. Drain is kept usually after Maylard's exposure as oozing and collection is common in this incision.

Disadvantages: Haemorrhage, haematoma, seroma formation and infection can occur. Injury to ilioinguinal and iliohypogastric nerves or their entrapment during closure can occur. Lateral femoral cutaneous, genitofemoral and femoral nerves can get compressed during retraction causing neuropraxia.

Kustner's Incision

A transverse incision is made 5 cm above the symphysis pubis and below the anterior iliac spine. The subcutaneous tissue is then separated in the midline to expose the linea alba. A vertical midline incision is made through the linea alba. Superficial epigastric vessels are ligated. This incision is not commonly used as there are no advantages over Pfannenstiel incision and it limits in adequate exposure and cannot extend if needed also.


Umbilicus
Pfannenstiel incision
Pubic symphysis
Anterior rectus sheath is opened horizontally
Exposed recti on both sides
Anterior rectus sheath is incised horizontally
Suprapubic horizontal skin incision
Raising upper flap up to umbilicus
Lower flap is elevated up to pubic symphysis
Raised anterior rectus sheath above
Recti muscles
Pyramidalis muscle
Pyramidalis muscle
Pubic symphysis
Lower flap of rectus sheath
Peritoneum is exposed
Recti are retracted outwards

Figs 18-30(1)


Both recti are retracted
from midline. Peritoneum
is exposed
Peritoneum is opened vertically
Care is taken not to injure urinary bladder below
It is ideal to catheterise prior to start
Anterior
rectus sheath
Vertically opened peritoneum
from above downwards
Peritoneal
cavity
Urinary bladder area
Retracted rectus

Figs 18-30(2)

Figs 18-30(1 and 2): Pfannenstiel incision – steps.



Fig. 18-31: Pfannenstiel incision closure.

Turner-Warwick's Incision

Incision is placed 2 cm above the symphysis pubis and within the lateral borders of the rectus muscles. The sheath overlying the rectus muscles at the symphysis pubis is released for about 4 cm transversely, and the incision angled up to the lateral borders of the rectus muscles. The lateral edges of the incision remain medial to the internal oblique muscles. The recti are separated and the incision is made in the midline. This type of incision is good for exposure of the retropubic space. Pelvis and abdomen is not exposed adequately in this incision.

OBLIQUE INCISIONS

Kocher's Subcostal Incision (Emil Theodor Kocher)

Right subcostal incision is used for open cholecystectomy and to approach biliary system and liver. Incision extends from anterior axillary line towards xiphisternum up to midline 2–2.5 cm below the costal margin. Skin, subcutaneous tissue, superficial fascia, anterior rectus sheath, rectus muscle, external and internal oblique muscles and transverse abdominis muscle are cut using monopolar cautery. Anterior rectus sheath once cut in front of the rectus muscle, long haemostat (artery forceps) is passed behind the rectus muscle and lifted forward to cut the muscle horizontally using cautery. Superior epigastric vessels deep to rectus muscle are ligated securely. 8th thoracic nerve which is smaller is cut. It is ideal to identify larger 9th thoracic nerve and preserve it to prevent weakening of abdominal muscles. Peritoneum is incised in the line of incision. Large bowel will be very close to this incision and so care should be taken not to injure it inadvertently while opening the peritoneum.

Incision is often *modified* by not cutting the rectus muscle but retracting it after incising the anterior rectus sheath **(Figs 18-32 and 18-33)**.

Smaller subcostal incision < 10 cm in length is used by many surgeon as *mini lap cholecystectomy* without incising the rectus sheath. It causes less postoperative pain, early recovery and good cosmesis. But Calot's dissection is difficult and often is done blindly. Advent of laparoscopic cholecystectomy as standard approach made this a surgical legacy.


Right subcostal
Left subcostal

Fig. 18-32: Right and left subcostal incision.

Closure of Kocher's incision is done by closing posterior and rectus sheaths separately and rectus muscle with vicryl sutures. Rectus has got segmental nerve supply and due to its upper tendinous intersections it will not retract and fibrous scar itself causes additional support to the muscle.

Advantages: It gives very good exposure to Calot's and biliary system. It can be extended towards opposite side if needed.

Disadvantages: Injury to 9th thoracic nerve causes muscle weakness and loss of sensation below the scar. Hernia if develops in Kocher's incision is difficult to manage **(Fig. 18-34)**.

Left Subcostal Incision

Left subcostal incision is used for splenectomy, distal pancreatectomy.


Medially up to the midline
Incision- 2 cm below the right costal margin
Rectus muscle
Anterior rectus sheath
Rectus muscle is cut using cautery with finger underneath
External oblique- cut
Posterior rectus sheath
Cut rectus muscle
Internal oblique
Internal oblique
Anterior rectus sheath
External oblique
Rectus muscle
Posterior rectus sheath
Peritoneum
Transversus abdominis

Figs 18-33(1)


Medial retraction of stomach
Deaver's retractor
Downward retraction of the colon
Kocher's subcostal wound- sutures removed
Drain site healed wound
Umblicus
Kocher's subcostal healed wound- scar
Umbilicus

Figs 18-33(2)

Figs 18-33(1 and 2): Typical right subcostal Kocher's incision and scar.



Fig. 18-34: Incisional hernia along Kocher's incision scar.



Fig. 18-35: Rooftop incision.



Fig. 18-36: Mercedez Benz incision.

Chevron Incision (Rooftop Incision)

In this incision a cut is made on the abdomen below the rib cage. It is actually bilateral subcostal incision. The cut starts from the mid-axillary line below the ribs on the right side of the abdomen and continues all the way across the abdomen to the opposite mid-axillary line leading into cutting of entire width of the abdomen providing access to the liver for liver resection/transplantation, oesophagogastric junction for oesophagectomy, surgery for renovascular hypertension, pancreatic surgeries, bilateral adrenalectomy. The average length of the incision is about 60-80 cm **(Fig. 18-35)**.

Mercedes Benz Incision

It is bilateral lower Kocher's incision (about 3-5 cm below the costal margin) with a middle vertical upper limb passes towards and through the xiphisternum. It gives very good exposure to liver, oesophageal hiatus **(Fig. 18-36)**.

Oblique Iliac Incision (Abbernethy's/Modified Gibson's)

It is used for *extraperitoneal approach* for ureteric stone, urinary bladder and lumbar sympathectomy. It is muscle cutting incision. It can be used as transperitoneal also **(Figs 18-37 and 18-38)**.

Position is partial or complete lateral, depends on the side surgery is needed. Incision is placed from mid-axillary line at the level of the umbilicus directing downwards and forwards towards



Fig. 18-37: Oblique iliac incision.

pubic symphysis up to the lateral margin of the rectus muscle. Skin, subcutaneous fat, superficial fascia, external oblique muscle and aponeurosis below are incised layer by layer in the line of incision. Internal oblique and transverse abdomen muscles are also cut in the line of incision. Under transversalis fascia extraperitoneal fat and peritoneum is visualised. In extraperitoneal approach, peritoneum is swept forward from behind by blunt finger dissection. Psoas major muscle, genitofemoral nerve and inferior vena cava are identified. Ureter with its typical look and peristalsis is also identified. Depending on the type of surgery further procedure is undertaken. Muscle is retracted using self retaining retractor. Peritoneum if inadvertently opened, it can be sutured using 2 zero vicryl.

LOIN INCISIONS

It is mainly used to approach kidney, adrenal and retroperitoneum. Patient is placed in loin position. Full lateral position with kidney bridge raise with flexion of the knee of the leg which is on the theatre table is done. Flat wide pillow should be kept between legs. Arm facing upwards is positioned towards head end with a support. Patient is strapped firmly to prevent tilting or changing the position during surgery. Back support is often needed. Mayo's table is placed on the leg side after draping which facilitates to keep instruments safely. After cleaning and draping, incision begins posteriorly behind the posterior axillary line in posterior subcostal line extending forward towards the outer margin of the rectus muscle. Rectus is usually not cut. Skin, subcutaneous tissue and superficial fascia are cut. Posteriorly latissimus dorsi, serratus posterior inferior and quadratus lumborum are cut; anteriorly external and internal oblique muscles are cut. Usually 12th or 11th is cut. Rib is identified. Incision is made over its periosteum. Periosteum is reflected using periosteal elevator. Care should be taken to avoid injury to vessels underneath which often need proper ligation. Rib after mobilization, is cut using bone cutter. Cut end is often smoothened using bone file. Pleura is very close to the rib which should not be opened. If opened pneumothorax develops; which is usually managed by placing vicryl sutures to pleura while anaesthetist is ventilating the lung with adequate expansion. Usually intercostal tube is not necessary. Postoperative check chest X-ray needed for the evidence of pneumothorax. Transverse abdominis muscle is usually split from posterior to anterior. Peritoneum is adherent to the abdominal wall in front. So care should be taken not to tear on the anterior aspect. Peritoneum is swept forward to reach the Gerota's fascia **(Fig. 18-39)**.



Fig. 18-38: Oblique iliac incision and closed wound also.

Closure of the Loin Wound Approach

It is done in two layers. Transversus abdominis and internal oblique muscles are closed using continuous vicryl suture as inner layer. External oblique is closed using nonabsorbable or delayed absorbable



Fig. 18-39: Lateral kidney position to approach kidney for various surgeries like nephrectomy, pyeloplasty.

continuous suture as outer layer. Covering fascia should be included in the bite which is stronger than muscle itself. Drain when needed should be kept below the lower margin of the wound and on the anterior aspect in front of the level of the anterior superior iliac spine; through a separate stab incision.

Incision can be extended into the thorax or into the peritoneal cavity as needed.

High 11th rib excision approach is called as *Nagamatsu approach* which is used in approaching upper pole renal cell carcinoma (RCC).

Lumbotomy Incision (Gil-Vernet)

It is vertical posterior incision from 12 rib level to iliac crest. Incision is along the lateral border of the sacrospinalis. It is deepened through latissimus dorsi, serratus posterior inferior, lumbosacral fascia, quadratus lumborum. It is done in prone position. Both sides' two separate incisions can be placed in bilateral approach. It is used bilateral partial nephrectomies and bilateral adrenalectomies.

PRINCIPLES IN CLOSURE OF THE ABDOMINAL INCISION WOUND

Layer by layer closure is good old standard. But it is now proved that peritoneum closure is not necessary.

In Layer by Layer Closures

Peritoneum is closed using vicryl or polypropylene; rectus sheath is closed with continuous locking monofilament nonabsorbable sutures; (interrupted sutures may be better if there is sepsis); subcutaneous tissue is closed using 3 zero rapid vicryl (ideal) or plain catgut; skin closed using interrupted mattress sutures. Skin stapler can be used as it is quicker and easy to remove; but it is not haemostatic, skin edge bleeding may occur.

Single Layer

Mass closure is also used. It is also equally good; rapid. Usually continuous suture is placed; but interrupted sutures also can be used. Skin is apposed separately.

Retention sutures, used earlier after an emergency surgery, is more often replaced by modified Smead Jones sutures. Retention suture is still practiced in many centers of world.

Modified Smead–Jones Sutures

It is interrupted specialised sutures used in the closure of abdomen as single layer excluding the skin. Linea alba is held with Allis' forceps. *Number one* polyethylene or PDS suture material is used. First bite on one side taken 3 cm away (width) from the margin from outside to inside; it is then passed through the corresponding opposite edge with 3 cm width from inside to outside; later again one small loop of 5 mm width from the edges of each side of the wound from first bite site to second bite site is taken; suture is knotted on the free edge of the first bite side. Full thickness bite holds the suture and maintains the tension in the wound. Smaller loop keeps the linea alba in apposed place. Large curved *Ferguson needle* is better to place these sutures. Each suture is placed at 2 cm interval. This is the type of suturing used at present in acute abdominal conditions instead of the retention sutures. Here also it is better to place all sutures under proper vision and knotting is done at the end. At least four knots should be placed. Excessive tension should be avoided. In upper abdomen peritoneum need not be included in the bite; but in lower abdomen as linea alba is indistinct, peritoneum is included in this **(Fig. 18-40)**.

L. E. Hughes Double Near and Far Suture

It is similar with same indications as Smead-Jones, with double near and far sutures placed to have a strong loop with knot on one side **(Fig. 18-41)**.

While taking bite from the peritoneum, care should be taken not to take bites from bowel; if inadvertently taken leads into dangerous faecal fistula. Guarding the bowel using finger lift or using mop or using sergeant retractor is a must. Before finishing the final bites it is



Fig. 18-40: Modified Smead-Jones sutures. These sutures are better than placing retention sutures.


Showing exact technique

Fig. 18-41: L E Hughes double near and far suture.

ideal to place index finger under the sutured peritoneum to confirm that suture line is perfect and without any bowel entangling.

Drain if needed to place, it should be placed away from the min incision; usually along the anterior axillary line; side and site (upper or lower) is decided depending on the type and area of surgery. Often double drains are placed on the same or both sides.

Retention Sutures

In this suturing the all abdominal layers are held together without tension; the sutures take the tension off the wound edges.

Uses

It is used for patients who are debilitated (malnutrition, old age, immune deficiency or advanced cancer); patients suffering from conditions associated with raised intra-abdominal pressure like obesity, asthma or chronic cough; those with impaired healing; burst abdomen.

Material used

Monofilament nonabsorbable suture material no. 1 (nylon/polyethylene/polypropylene) is used **(Fig. 18-42)**.

Technique

Retention sutures are inserted through the entire thickness of the abdominal wall leaving them untied in the beginning. All sutures are passed first. Sutures are through and through all layers from skin, rectus sheath, rectus muscle and peritoneum on one side and back on the opposite edge with a sufficient gap of 1.5-2 cm from the edges of the wound. Sutures may be simple or mattress. Later peritoneum is closed with continuous vicryl sutures and then continuous or interrupted anterior rectus sheath, subcutaneous tissue and skin (interrupted).

After completion of skin suture, each untied retention suture is threaded with (sleeve) 1-2 cm length of plastic or rubber tubes/sleeves. Plastic sleeves can be placed earlier itself; often it is practiced to place two tubes/sleeves on either sides of the wound to complete the vertical mattress sutures. Now sutures are apposed and tied but without any tension. Undue tension may compromise the blood supply of the tissues at wound edges. Horizontal mattress retention sutures are also used by many.

Retention sutures are left in place for 14 days.

Many surgeons advocate closure only by placing retention sutures with skin sutures without placing the apposition sutures on peritoneum and rectus sheath **(Fig. 18-43)**.


Horizontal tension/retention sutures

Fig. 18-42: Retention sutures – horizontal.

Controversy

Presently use of retention sutures is controversial. Hughes far and near sutures or Smead-Jones sutures are said to be better. However retention sutures are used wide worldwide even now **(Fig. 18-44)**.


All layer through and through sutures
Threading the plastic or rubber tubes/sleeves
Layers are sutured separately; then retention sutures are tied as - TENSION FREE
Single bead/sleeve in each suture
Two beads/sleeves in each suture

Fig. 18-43: Retention sutures.


Vertical tension/retention sutures

Fig. 18-44: Burst abdomen – placing retention/tension sutures using monofilament nonabsorbable sutures.

Note

Continuous sutures are started from far point of the wound towards surgeon.
Forehand suturing is better during closure which makes shoulder, arm and wrist less straining allowing surgeon to do more precise firm strong sutures at specified sites. Here forearm moves from pronated to supinated position.
In *backhand suturing*, supinated hand rotates to pronated position; here needle should be directed towards surgeon's right foot (right hand surgeon). Scalpel incision and dissection needs backhand movement.
Proper foot positioning is important in various levels of suturing to make suturing easier and perfect.
During scissor dissection, scissor tip should be directed towards surgeon's left foot.
By changing the body and foot position in perpendicular direction (parallel to table) forehand movement can be used in all forehand suturing.
Left foot of the surgeon should be more close to the operating table; right foot should be more lateral.
All instruments should be held in fingertip position.
Instruments should be held with finger grip rather than tight vise grip. Relaxed wrist movements are essential to avoid wrist tremors.
When suturing comes towards the end of the abdominal wound; last few sutures should not be tied if they are interrupted or last few bites and their loops is kept loose until last bite is taken to avoid injury to deeper structures (bowel).
Suture bite and stitch should not be taken blindly without seeing the tip (point) of the needle at all the time.
Optimum tension only used; excessive tension should be avoided.

ABDOMINAL RETRACTORS

Retractors are essential for all abdominal surgeries. Simple Langenbeck to complex self retaining chain retractors are used in various procedures. Retraction facilitates the surgery in the deeper plane.

Self-retaining or Manual Retractors

Manual retractor is held by assistant constantly. It fatigues the assistant in lengthy procedures and retraction varies depends on the assistant who holds the retractor. But retractor can be temporarily relaxed when not needed so that tissues underneath (muscle) can be allowed to relax in between to reduce crushing effects on the muscle mass. Its position is adjustable in time to time.

Self-retaining retractors are either fixed through its own beams or bars or through a specialised devices strong chain or handle to the side beam of the operation table. They are continuous non-altering (in-position) mechanical retractors. These self-retaining retractors allow assistant's hands to be free for other works like suctioning, passing ligatures, cauterising, etc. But self-retaining retractors may cause more damage to the muscle as retraction is persistent and constant for long period. *Upper hand retractor* is often used with a steel bridge which is attached to both sides of the operating table crossing across the sternum at 5 – 10 cm height. Retractor blades are placed and fixed on to this steel bridge to facilitate the retraction at the operating site **(Figs 18-45 to 18-47)**.

Precautions

While using the retractor care should be taken to avoid entangling of the vital structures bowel, soft tissues, organs, etc.



Fig. 18-45: Balfour's self-retaining retractor.

Undue retraction may injure the wound edges leading into wound infection, dehiscence, etc.

Deeper ends of the retractors may not be visible and often assistant won't be having proper control on it allowing ends of the retractors to injure organs like liver or spleen.

It is often better to place a mop underneath the deep retractor to avoid injury to organs underneath.

DRAINS IN LAPAROTOMY

Even though advantages are under *debate and controversial*, drain is used to prevent the collection in dead space; to allow the escape of fluid or air from the cavities; to prevent infection; to promote healing.

When there is an abscess or pus inside peritoneal cavity, drain is a must. Here it is therapeutic. Drains commonly advocated are tube drains which are connected outside to a sterile bag or container. Drains placed in other situations are rather prophylactic.

Drain is placed to allow escape of bile, pancreatic and intestinal juices, lymph, serum, blood and pus from peritoneal cavity. Drain



Fig. 18-46: Finochietto retractor.

creates a track and walls off the leaking/infected site from peritoneal cavity and so prevents the spread of infection. This is said to promote the healing of the area, preventing the sepsis by fluid collection. It is no doubt that it is useful in sepsis, peritonitis, and in abscess. Prophylactic peritoneal drainage is controversial even though it is done in anticipation of possible disruption of the anastomotic site and so that to reduce its dangerous consequences. Drain creates a controlled fistula so that peritoneal cavity is safeguarded from sepsis or contamination. But concept of drain preventing wound infection and promoting faster wound healing is questioned/disproved? Drain as a foreign body action, can be a focus for infection from outside. Drain may erode vessels, bowel or organs.

Drains may be passive or active. *Passive drain* like Penrose or corrugate function depending on the pressure difference between inside and outside abdominal cavity and high pressure inside forces the fluid outside. *Active drains* use low or high negative pressure (suction) to remove accumulated fluid from a wound. Active drains require some special device and maintenance. The collection reservoir of an active drain expands as fluid is collected by exchanging negative pressure for fluid; if the vacuum is lost, the drain will lose its effectiveness. The fluid collection reservoir is either a manually activated, or through bulb evacuator or a spring-loaded device that has variable preset suction levels.



Fig. 18-47: Mop should be kept under retractor to prevent trauma to the viscera.



Fig. 18-48: Corrugated drain is a passive drain which drains by gravity and capillary action. It is rather an overflow.

Drains may be *closed or open system*. Drains may be allowed to function naturally by gravity or by capillary action (corrugated drain) or by suction device. It may be connected to wall suction to have continuous or intermittent vacuum suction in wounds.

Drain should be observed daily for its nature and volume of content accurately. Depending on the quantity of the drain, duration of keeping the drain in situ is decided. Open drains like Penrose and corrugated should have protective dressings over it. Amount of soiling should be assessed for possible quantity of drainage and type – bile/faecal/serous/serosanguineous/purulent/gastric.

Passive Drains

Passive drains even though used by many surgeons, are not very suitable as their efficacy is inadequate and complications are more. Penrose drain and corrugated rubber drains are commonly used. Tube drains like Malecot's/Foley's catheters/nasogastric tubes are also often used for this purpose. Flat drains outside are covered by dressing pads. Tube drains are connected to sterile container (urosac bag) or sterile glove outside. Tube drains are better than flat drains **(Figs 18-48 to 18-50)**.

Penrose Drain

A *Penrose drain* is a named for the American gynecologist Charles Bingham Penrose (1862–1925), placed in a wound to drain fluid. It consists of a soft rubber tube placed in a wound area, to prevent the buildup of fluid. It is a passive open drainage system. A Penrose drain removes fluid from a wound area. It is used after a surgical procedure is complete to prevent the area from accumulating fluid, such as blood, which could serve as a medium for bacterial infection. In podiatry (diseases and management of foot diseases), a Penrose drain is often used as a tourniquet during a nail excision or ingrown toenail excision. It can also be used to drain CSF in a hydrocephalus patient. It is a quadrangular flat tube made up of radiopaque thin rubber sheet. It is available as prepacked sterile drain with a safety pin. Safety pin prevents drain getting retracted into the wound while in use. Head of the safety pin should be crimped and closed to prevent injuring the patient's skin. Different sized Penrose drains are available. Multiple Penrose tubes can be placed. It is inexpensive and creates fibrosis to form a tract in 10 days. It drains passively by mere gravity and overflow. In oozing area blood may clot and block the drain. Infection into the area from outside is a possible drawback **(Fig. 18-51)**.



Fig. 18-49: Tube drains placed in the peritoneal cavity.



Fig. 18-50: Tube drain placed in biliary surgery. Note the bile collected in the reservoir bag (urosac).

Active (Negative Pressure) Drains

Negative pressure causes – continuous wound cleaning thereby decrease the bacterial burden in the wound, remove substances that inhibit wound healing; promotes continuous removal of fluid like exudates so that prevents the mechanical compression by accumulated exudates into the capillaries at the site which restricts the flow of blood into wound site; causes wound retraction and approximation of wound edges; creates externally applied mechanical stress in the tissues stimulating matrix synthesis and cell proliferation; promotes healthy granulation tissue formation; decreases interstitial oedema which improves the blood flow.

Negative Pressure Wound Therapy

It is used in infected wounds often in abdominal wall. It creates continuous or intermittent suction of the wound content to keep the wound surface drain which promotes formation of healthy granulation tissue and so wound healing.

Low Pressure Vacuum Drain

Low-pressure vacuum drains have a plastic bulb-shaped reservoir or spring reservoir and a drainage tube (Jackson-Pratt or Romovac), with multiple side holes in the end of the tubing that is inserted into the wound. When the bulb is compressed, air is forced out, which creates low negative pressure to evacuate excess fluid and air gently **(Fig. 18-52)**.



Fig. 18-51: Penrose drain.



Fig. 18-52: Low suction drain.

Jackson-Pratt Drain

It is often called as *JP drain*/bulb drain is the flexible plastic tube which connects to an internal plastic drainage tube; it drains excess fluid by constant low suctioning. Due to low pressure vacuum system, intraabdominal contents like omentum and bowel will not get sucked through the drain thus preventing the possibility of ischaemia of bowel and perforation. Air pressure within the drainage system is removed by removing the plug and squeezing the bulb. Drain is kept folded during uncapping and recapping.

High Negative Pressure Vacuum Drains

They are sealed, closed circuit drain systems (bottled vacuum system) that are easily monitored and allow safe disposal of the drainage. This type of system consists of a clear, plastic/bottled reservoir with a rubber cap and indicator wings that monitor the presence of vacuum pressure and an opening in which the drainage tube connects. When a vacuum is present in the system, the wings on the rubber cap are close together; when the vacuum is lost, the wings are apart. The end of the drainage tube inserted in the wound has numerous openings to evacuate fluid from the wound. The wound should be closed before opening the clamps on the drain; otherwise the vacuum will be lost as the tube pulls in atmospheric air. Bottled vacuum drains are available **(Fig. 18-53)**.

Drain Insertion

Technique of insertion of drain is important. When a drain is required, it is inserted at the end of the surgical procedure just prior to closure of the wound. Drain is inserted through a separate stab wound, which is created a few centimeters away from the primary incision which reduces the risk of a postoperative wound infection and dehiscence. Skin incision for drain is usually made at anterior axillary line. Incision is usually of within 1 cm in length, transversely placed. Drain should not be inserted towards posterior side as supine position of the patient may be difficult and also drain may get kinked preventing its function.

Drain that has a sharp trocar attached to the tube is inserted by piercing the attached trocar to the skin from inside the wound/peritoneal cavity at the desired site; the attached tube is then pulled out through the stab wound; the inner end of the tube is placed at the required site and the trocar is detached. Drain is secured into skin with proper suture (shoe lace suture). Once the wound is closed, tube is connected to the reservoir; suction is attached to facilitate the drainage.

Drains that do not have an attached trocar is placed by passing a long haemostat across the abdominal wall from inside out and skin over it is incised using a scalpel to allow tip of the haemostat to come out which is opened and drain is passed by holding through the haemostat towards inside. Drain is placed in desired location and is fixed to skin securely. Once wound is closed, the drain tube is connected to a reservoir.

Drain without trocar can often also be inserted from outside in. Skin is incised first at separate site from primary incision. Long curved haemostat is gently forced with rotation movements inside into the peritoneal cavity while surgeon or assistant's one of the hands should keep bowel away from the site of puncture and guides the tip of long haemostat inside the cavity. Once peritoneum is punctured drain is held and pulled out under vision to prevent entangling of any content into the drain site wound **(Fig. 18-54)**.

Complications of the Drain

Drain may cause retrograde bacterial contamination of the abdominal cavity. Drain may erode into the bowel or vessels. Drain acts as a foreign body. Suction drain may suck the bowel or omentum. Drain site after removal forms a puckered scar due to healing by secondary intention. Breakage of drain can occur and inner broken part may be left inside which can cause sepsis. Breakage usually occurs only if drain used is already damaged due to nick by scissor or scalpel. Damaged drain should never be used.

While inserting the drain, injury to bowel or vessel can occur and so care should be taken.

Drain may get blocked giving false impression of healing inside. Blocked drain when suspected should be checked properly either by irrigating the tube with saline or changing the position of the drain. Drain tube can be gently squeezed and released at different points to remove small clogging. If it is presumed that already track is formed then drain can be removed and a newer blunt tipped (Foley's) tube drain can be gently replaced with care along the same tract.

Pain and discomfort at the drain site is common which often hinders the early mobilisation of the patient.


Wings will be closer with suction
Wings will be apart without suction

Fig. 18-53: High vacuum suction device. When vacuum is present, wings will be closer together; when vacuum is not present wings will be apart.



Fig. 18-54: Insertion of drainage tube (without trocar) into the peritoneal cavity.

Drain may fall of on its own either by insecure fixation or by pulling by patient himself. In such situation first thing to be confirmed is whether drain has come out completely or not should be checked. If part of the drain is left inside, then formal exploration of drain site wound into deeper plane is needed to remove the retained part of the drain.

Inadvertent pulling of drain while transferring the patient or by entangling into linen or clothes or by patient himself may cause bleeding and pain.

Skin around drain site may get excoriated with redness and pain. Often leak occurs on the side of the drain. Skin in such situation around the drain should be dressed using zinc oxide cream.

When drain is kept for long time removal may be difficult due to adhesions and entrapment into the tissue. In such situation exploration at the site may be required to remove the drain.

Drainage may suddenly stop or suddenly increase which should be assessed seriously for the proper cause. It may be more leak or blockage or erosion. Change in colour and odour after more drainage is also important to be noticed. Nowadays drains commonly used are radiopaque, X-ray of part or ultrasound helps in finding out the cause, site of drain or any collection. Often contrast CT imaging maybe required to reassess the situation.

Since drain is passed across the fascial plane, drain site hernia can occur. If pathology in the deeper plane or distal obstruction persists then leak at the drain site may occur.

Removal of Drains

Drains should be removed once purpose is served. Drain placed to cover preoperative bleeding is removed in 48 hours; to drain serous collections it is removed in 2-5 days; in intestinal anastomosis it is removed in 7 days; T tube is removed in 10-14 days. If leak persists it is kept until leak stops after confirmation that source is cleared by imaging method. Drains are removed when draining is of negligible amount (less than 25 ml per day; less than 1 ml per hour).

Skin suture (stay suture) is cut using sterile scissor and drain is gently pulled using continuous constant traction. Drain wound is covered with sterile dressing. Wound usually heals fast without any problem. If drain wound site shows large quantity of drainage then stoma bag can be placed until drainage of fluid stops.

BASIC LAPAROSCOPY

In laparoscopic surgery the prime difference of indirect access to the internal structures means that we have to acquire different set of skills to tackle the given surgical problem. Since there is no open access to the viscera it is very important to have the right kind of instrumentation before we embark on doing laparoscopic surgery. As the most versatile of all the working instruments, the surgeons "hand" is out of bound. Knowing about few technical details about laparoscopic instrumentation helps a long way as often in the operating room the surgeon knows best about electronic equipment. This also ensures proper handling of the expensive equipment and prolongs the life of the same.

History of Laparoscopic Surgery

First laparoscopic cholecystectomy was done by Muhe of Germany in 1985 and by Mouret in Lyon in 1987. McKeran and Saye performed the first laparoscopic cholecystectomy in USA in 1988. First laparoscopic appendicectomy was done by Semm as prophylaxis. First laparoscopic appendicectomy for acute appendicitis was done by Schreiber in 1987.

Semm changed 75% open gynaecological surgeries into laparoscopic surgeries.

Prof TE Udwadia, Mumbai did first laparoscopic cholecystectomy in India.

Advantages of Laparoscopic Surgery

It is relatively less painful compared to open surgery. Trauma of access is very less. Shorter hospital stay and early return to work; faster postoperative recovery; better visualisation of the anatomy, i.e. better approach for dissection and visualisation of other parts of abdomen for any other pathology; instrumental access to different abdominal locations is many times better compared to open method and minimal scar on the abdomen – makes laparoscopy more acceptable than open method. Trauma of dissection is also less. Bowel manipulation and exposure is less. Less postoperative ileus facilitates early feeding. Need for intravenous infusion and analgesic is lesser.

LAPAROSCOPIC SET

The most basic to the best equipment shall be briefly described for the reader to get over all picture of equipment. The laparoscopy set up consists of 5 important components.

1. Laparoscopy camera and telescope.
2. Light source and cable.
3. Carbon dioxide insufflator.
4. Monitor.
5. Hand instruments **(Fig. 18-55)**.

Instruments Used

- *Zero* degree laparoscope is commonly used. Side viewing scopes are also used to have better visualisation 30°.
- Cold lights source either halogen lamp or Xenon lamp is used. Halogen lamp is used commonly and is cheaper. Xenon lamp gives high visualisation.
- Camera: 3 chip camera is commonly used with high resolution.
- Video-monitor to display images.
- CO_2 insufflator.
- Long fine dissectors like in open surgical techniques.
- Hooks and spatulas are used along with cautery for dissection.
- Clip applicators.
- Needle holders.
- Endostaplers.
- Veress needle.
- Suction-irrigation apparatus.
- Trocars of different sizes—10 mm, 5 mm.
- Reducers to negotiate smaller instruments through larger parts.

Laparoscopy Camera and Telescope

The laparoscopic camera is like the retina for perception of images during surgery. Without a good camera it is dangerous to embark upon laparoscopic surgery as there cannot be safe surgery without clear vision of the structure on which you operate. The laparoscopic camera has three different components.

a. Camera head
b. Coupler
c. Connector


Myomectomy screw
Blunt tipped rod
Veress needle
Liver fan retractor
Lap working instruments
Scissor curved
Maryland dissector
Piston handle
Babcock's forceps
Bipolar forceps
Bipolar Maryland
Hook- monopolar
Aspiration needle
Toggle type suction irrigation apparatus
Clip applicators
10 mm toothed stout grasper
Maryland with ratchet/lock
Clip applicator

Figs 18-55(1)


Uterine manipulator
Monopolar spatula
10 mm myoma screw
Different trocars
Different cannulas/ports
10 mm port
Reducer sleeve
5 mm port
Clips
Disposable port
Trumpet type suction irrigation apparatus
Port closure needle
also used in placing sutures
in fixing mesh intraperitoneally
in ventral hernia repair
Port/cannula caps
- 10 mm, 5 mm
Detachable handle can be used to
any 5 mm working instrument

Figs 18-55(2)

Figs 18-55(1 and 2): Different instruments used in laparoscopic surgery.

Camera Head

As mentioned already the camera is the most important component of the equipment which makes the procedure comfortable for the surgeon and safe for the patient. The camera is responsible for production of quality pictures in all dimensions such as clarity, colour reproduction and contrast. The light reflected from the viscera is captured by the camera head and is transmitted to the console via the connecting cable. The camera head contains what is termed as charged coupled device or CCD. This chip perceives light and converts the signal into digital form. The basic cameras contain only a single chip or CCD which perceives light as a whole without dividing it into its component red, green and blue light like in a 3 CCD *(Charged Coupled Device)* camera. The resolution of a 3 chip camera is better because the 3 chips individually produce pixels thus increasing the resolution from 470 lines (single chip) to up to 1080 lines which is HD (high definition) quality. Single monochrome CCD chip creates alternate red, green and blue illumination to form a colour image; 3 chip camera has got three separate colour filters which create high quality image with better resolution. Higher resolution can make a difference between a good surgery and a great one only in the hands of an expert with sufficient skills and while performing advanced procedures. For day to day practice and for small set ups latest generation single chip camera is adequate. Karl Storz single chip camera and Stryker single chip cameras are the more popular ones but there are always other makes available.

Monitor resolution needs 400-600 lines. White balancing should be done before introduction of the camera into the abdominal cavity. With light source on Camera with telescope is focused on a white gauze and white balance button in the camera source is pressed until 'white balancing is complete' sentence appears on the monitor. Zoom adjustment also can be done in the camera **(Fig. 18-56)**.

A good camera is always complemented by a good telescope/ laparoscope. This is akin to the lens of the eye. The clearer the optics of the lens of the telescope better is the vision. A poor telescope with improper optics makes the picture look bad and the illumination is inadequate. The telescope incorporates the Hopkins rod lens system where in the sheath of the telescope is packed with series of glass lens with air pockets intervening to produce magnified images at the opposite end. The rod lens system is surrounded by optic fibres carrying light from the camera end to the tip of the telescope. If these optical fibres are damaged then the illumination produced at the distal end is poor. Telescopes are available in a variety of diameters and in different forward viewing angles.

Semiflexible and flexible laparoscopes are available. It may be *conventional fibre optic flexible type* but in which image undergoes distortion. In newer type, *digital monochrome CCD single chip camera* is used wherein image is changed to electric signals which maintain the image quality high. It increases vision four ways improving the viewing angles.



Fig. 18-56: Single Chip camera Karl Storz.

1. Power switch.
2. Automatic white balance.
3. Abridged instructions.
4. Camera cable receptacle.
5. BNC video output connector.
6. S- Video output connector.
7. Accessory control outputs.
8. Power cord receptacle.
9. Potential equalization connector.
10. Power fuse holder.
11. Grasping mechanism.
12. Focusing ring.
13. C-Mount connection.
14. User control buttons.

Telescope/Laparoscope

In 1952 Hopkins British physicist invented the laparoscope. Originally conventional lenses were used separated by air gaps which give poor quality images. Present laparoscope has got rod lens system with an outer rim of optical fibre. Light is passed through the optical fibres inside the cavity and image is transmitted through rod lens system to the camera which is processed there and projected at monitor. 10 mm scopes are commonly used either end viewing or side viewing. 5 mm scope transmits lesser light (10-30% of 10 mm scope). 3mm scope is used in paediatric surgery. 2 mm scope is also available.

Cold laparoscope when introduced into the peritoneal cavity, *fogging* of the lens at the end of the telescope occurs (it is also due to passage of the cold CO_2 through camera port) which is prevented by dipping the tip of telescope into warm saline kept in a thermo flask. Cleaning the tip using warm saline soaked gauze and povidone iodine solution prevents this problem. Antifogging solutions, electric warmer flasks are available. Once other ports are placed it is better to change the CO_2 insufflation tube to one of the other ports **(Fig. 18-57)**.



Fig. 18-57: Telescopes of various diameters and viewing angles.

Commonly used in basic surgeries is the 10 mm 0 degree (end on viewing) telescope. This is a versatile telescope and can be handled by a scrub nurse as well. The 30 degree oblique viewing telescope is good for viewing the Calot's triangle during posterior dissection and also in viewing the lateral sides during TEP (Total extra peritoneal) inguinal hernia repairs. They are also used for dissection at gastro-esophageal junction and rectal mobilisation. Suturing is better aided by 30° telescope. 45 degree oblique viewing scopes are commonly used in bariatric surgeries. The usual working length of the telescopes is around 330 mm. The telescopes used in bariatric surgeries can be up to 450 mm in length to provide access to stomach at a depth. 5 mm diameter laparoscopes are used in patients according to the convenience of the operating surgeon. This further reduces the size of the umbilical incision. Although the light transmitted via the 5 mm telescope is only 10% of that transmitted by a 10 mm telescope, a good camera and suitable monitor can provide a clear operating field. A 3 *CCD (Charged Coupled Device)* camera and xenon light source are good enough to produce clear pictures even in a 2 mm needle scope. These scopes are used for entry site port in paediatric cases and in patients with previous laparotomy wounds.

Light Source and Cable

Having a good light source is a priority as the entire surgery is dependent on the images received on the monitor. It is an important component of the triad of camera, light source and monitor. For performing safe surgery visualization of structures in its best colour contrast is essential. For this white light produced by a *xenon light source is best*. The light source is composed of replaceable bulb, a heat filter (as the light is condensed by a lens before output, the temperature generated at the tip can be as high as 6000K in xenon lamps) and an intensity control. Depending on the make of the light source the intensity of the light can be either manually or automatically controlled. The average life of the xenon bulb is around 500 hours and some light sources even track the life of the bulb. Xenon lamps are of either 175 or 300 Watts. 300 Watts is ideal and standard. Even though xenon light source is cold light source it produces significant heat at the tip of the telescope and hence tip should not touch bowel, vessels, drapes and skin as burn injury and its dangerous consequences can occur. *Halogen light sources* are country cousins of xenon sources. They are inexpensive and can be acquired for a fraction of the cost. The main disadvantage is the yellow colour of the light that is produced. The field appears yellow and the distinction of vessels becomes difficult in cases such as cholecystectomies. Besides this the intensity of the light is less compares to xenon and the peripheries of the visual field are much darker making identification of structures difficult. Halogen light sources can be used for performing diagnostic laparoscopy and laparoscopic appendectomies but xenon light source is recommended for doing cholecystectomies and inguinal hernia repairs **(Fig. 18-58)**.

Transmission of the light from the source to the telescope is equally important. Two types of light cables are available for use:

1. Fibre optic cable.
2. Fluid filled/ gel filled cable.

The fibre optic cable is used frequently. Multiple tiny fibre optic cable are bundled together to transmit light. The individual fibre optic cables are fragile and during use there is gradual loss for fibres thus ending the useful life of the cable. This can be assessed by pointing the light at white surface and observing for the dark spots within the field. It is recommended that the light cable be changed if there is loss of more than 20% of the optical fibres in the bundle. The tip of the light cable becomes extremely hot after a while and due precaution should be taken while handling it to prevent burn injury to the patient or operating staff. Transparent case around the optical fibres makes fibres visible for any damage.

The fluid or gel filled cable transmits more light than the fibre optic cable but also has the disadvantage of transmitting more heat and being more fragile and difficult to handle than the fibre optic cable. It is also more expensive than the fibre optic cable. It cannot be sterilized by autoclave; it shows poor flexibility and fragile and so causes difficulty in manoeuvring the camera.

Carbon Dioxide Insufflator

Creation of pneumoperitoneum is the first step in any laparoscopic surgery. Although gasless laparoscopy can be performed, pneumoperitoneum causes fewer traumas and the equipment is easily available and easy to use. Carbon dioxide is ideally suited as it is non-combustible, absorbed by the body, inexpensive and easily available. Air insufflators have been used by many and are still being used by few but carbon dioxide insufflators are safer for the patient as there is risk of air embolism if there is any injury to vascular structures during the procedure. The standard insufflators has an indicator for amount of CO_2 present in the cylinder. It is wise to know the stock of your CO_2 cylinder before proceeding as it avoids the embarrassing situation where the case is converted due to empty CO_2 cylinder **(Fig. 18-59)**.



Fig. 18-58: Karl Storz Xenon light source.



Fig. 18-59: Karl Storz Thermoflator.

There are three indicators in the console. First one denotes the intra-abdominal pressure with setting. This can be set from 0 to 25 mmHg in most insufflators. The usual intra-abdominal setting used is of 12 mmHg. Higher pressure setting may be used in case of TEP hernia repair to maintain the pre-peritoneal space. The calibration of the instruments is required for patient's safety point of view as the cut off flow of CO_2 at set pressure is important. The second indicator is for the flow rate. The flow rate can be set from 0 to 16, 25, or even 40 with high flow insufflators. For routine procedures a 16 lt/min insufflator is adequate although some prefer high flow insufflator for TEP hernia repair, one can manage to successfully perform the surgery with 16 lt/min insufflator. The third indicator is for the total amount of CO_2 used for the particular case. In addition to these standard indicators some newer insufflators has come with additional feature of warming the carbon dioxide to body temperature before it enters the abdomen. This reduces the temperature difference when the telescope is introduced into the abdomen thus preventing fogging of the telescope.

Monitors

The final picture emerging out of a good telescope and camera is complemented by a suitable medical monitor. For a single chip camera which produces images of resolution of around 470 lines, a standard monitor of resolution around 400 lines and above is required. This can easily be substituted by use of our regular television sets. Although a 14 inch colour television is adequate, a 21 inch flat television increases comfort level of the surgeon and the team. For the 3CCD cameras however the television monitor is not adequate as the camera produces up to 1080 lines (HD) and the picture would not translate well on ordinary television. A HD television or a HD monitor is required for a three chip camera to produce best results with a resolution of > 1600 lines. Various types of output signals are delivered out of the camera console. There are RGB out, Y/C out, S video out, composite out and some camera consoles even have a USB out so they can be directly connected to a computer or laptop. Commonly used are composite or RGB out for connecting a television monitor and S video out to connect to a medical monitor. Presence of a USB out can make digital recording of the surgical procedure very simple and inexpensive. A parallel out to the computer allows for recording in the computer thus eliminating the need for a separate recording device.

Hand Instruments

Once the main consoles of the laparoscopy set are arranged we turn out attention to hand instruments. They are available in various makes and qualities. Imported as well as locally manufactured indigenous instruments are available. Imported instruments such as those provided by Karl Storz although expensive lasts very long without any problems and in the long run are better value for money than the local instruments. However, the locally made instruments are inexpensive and can be replaced with ease in case of any problem. Trocars and often instruments are available as disposable and reusable. Disposable trocars are single use precise one making insertion of trocar very easy, quick and perfect.

Following is an indicative list of instruments suggested for basic laparoscopic surgeries:

1. Veress needle.
2. Trocars
   10 mm – 2 in number
   5 mm – 2 in number
3. Reducer sleeve 10 mm to 5 mm.
4. Maryland dissector.
5. Atraumatic grasper (Universal grasper) 5 mm.
6. Traumatic (Toothed) grasper 5 mm.
7. Gallbladder extracting forceps 10 mm.
8. Curved scissors 5 mm.
9. Suction irrigation system 5 mm/10 mm
10. Clip applicator for LT300/ LT400
11. Monopolar hook and spatula
12. Aspiration needle.
13. Bipolar forceps.
14. Knot pusher.
15. Port closure needle (Optional).

Veress Needle

Veress needle was first developed in 1932 by *Janos Veress*, a Hungarian internist working with tuberculosis patients. At the time, one of the mainstays of treatment was to collapse an infected lung and allow lesions to heal. The needle was introduced as a safer technique to give patients such pneumothoraces. It was in 1938, he published his invention in the German literature. Veress needle is a spring locked needle with a cutting sheath and a blunt tip. It is 2 mm in external diameter and 12-15 cm in length usually. The outer cannula consists of a beveled needle point for cutting through tissues of the abdominal wall. A spring-loaded, inner stylet is positioned within the outer cannula. This inner stylet has a dull tip to protect any viscera from injury by the sharp, outer cannula. Direct pressure on the tip, when penetrating through tissues, pushes the blunt stylet into the shaft of the outer cannula. When the tip of the needle enters a space such as the peritoneal cavity, the blunt, inner stylet springs forward. *Parts are* – beveled needle; stylet; spring action part; lock for valve; head or knob proximally. Instrument should be held below the lock at proximal part of the needle as – guard position. Central sheath has got connector which connects to insufflation tube.



Fig. 18-60: Veress needle and methods of holding it.

Veress needle is available at various diameters and lengths. It may be disposable or reusable **(Fig. 18-60)**.

It is used as closed method to access peritoneal cavity for laparoscopic procedure. Before using the Veress needle its patency should be checked by flushing it with saline. Spring mechanism has to be checked before every use. The spring action in the blunt tip prevents the sheath from injuring the viscera once it enters the peritoneal cavity. Lock for the valve should be in open position. Patient is in supine position as in this position bowel will be in uniform spread inside the peritoneal cavity (Many use Trendelenburg position with 15° tilt; but often it is presumed that bowel may come closure to umbilicus in this position). After making the subumbilical incision, Veress needle is passed inside across abdominal wall by holding it only slightly oblique, with other hand holding the abdominal wall forward to act initially as counter pressure. Abdominal wall should be held at the level of the umbilicus laterally (not very close to umbilicus) either one side or both sides or below. Assistant can help in holding the abdominal wall. Abdominal wall is held firmly using thenar eminence and fingers of the hand. Length of the needle needed is often assessed by finding the thickness of abdominal wall fat (thickness in cm + 4 cm conventionally). Veress needle should be held below the knob (*gurading position*), not at the head/knob. Initially needle is passed inside with 90° direction; later made obliquely. Often 45° oblique angle towards anus is also used to avoid injury to the major vessels. Passing through the layers of the abdominal wall – rectus sheath, transversalis fascia and peritoneum can be felt while pushing the needle. Once peritoneum is reached due to loss of resistance, blunt tip springs forward thus preventing injury to viscera and vessels. Two click sounds can be heard (if there is no noise in theatre) and felt; one during passage of the rectus sheath and other during forward springing of the blunt tip. With 5 ml syringe, initially aspiration through the needle is done to check for any blood or bowel contents will come or not. Then normal saline is flown by pressure using syringe into the needle and aspirated; if saline does not return then it is in the peritoneal cavity; if saline returns back that means needle tip is not inside the peritoneal cavity. Again drop wise saline is allowed to enter the proximal part of the Veress needle to confirm free entry of the saline into the peritoneal cavity (water/saline drop test; hanging drop test). Saline filled syringe can be connected to the Veress needle knob to observe free flow of the saline into the peritoneal cavity. Veress is connected to CO2 insufflator tube to create pneumoperitoneum. Veress needle will not allow insufflation flow more than 2.5 litre of CO_2 /minute. Veress needle should not be passed in close vicinity of the previous scar.

Confirmation of proper positioning of the Veress needle

- Two click sounds are heard and/or felt.
- Irrigation – aspiration method.
- Hanging drop test.
- Free flow of saline through a syringe.
- Through distension of abdomen while gas is on flow by confirming the resonant all over the abdomen

Note:

81% gynaecologists use Veress needle to create pneumoperitoneum (due to lax abdomen in females); whereas only 48% of surgeons use the same.



Fig. 18-61: Veress needle available in 120 mm and 150 mm lengths.

Veress needle can be used for port closure also. It is also used to pass stay suture to retract internal organs like in gallbladder in single incision laparoscopic surgery (SILS) or two port laparoscopic surgery **(Fig. 18-61)**.

Trocars

Trocars are needed to access the peritoneal cavity during the surgery and for maintaining pneumoperitoneum when the instruments are exchanged. Various types of trocars are now available. Commonly used are reusable trocars which can be autoclaved. The disposable ones are convenient to use but the cost factor has to be borne in mind. The trocar has an obturator with pyramidal cutting tip which pierces the sheath and muscle during entry. Bladeless trocars are available in disposable type which cause minimum damage to the muscle and leave a minimum defect on removal. Trocars are available in various sizes with outer diameter of 11 mm, 5.5 mm ones being used frequently in most procedures. Special devices such as endo GI staplers are introduced into abdomen through 13 mm trocars. Tip of trocars may be conical or pyramidal. Pyramidal tip penetrates the wall by sharp dissection and thus reducing the insertion force. Optical view trocars are passed under visual guidance by passing laparoscope into the trocar. Electrosurgical trocars are available wherein thermal energy is used to create track rather than conventional physical force. There are plastic tip trocars with a diathermy loop on the tip. Similarly ultrasonically activated trocars are also available in the market.

Hasson's trocar and cannula is used as an alternate for open method instead of Veress needle approach. It contains three parts – a cone shaped sleeve; plastic or a metal sheath with a trumpet or flat valve; blunt tip obturator. On the sheath or sleeve two struts are present to fix fascial sutures tightly around to fix trocar firmly and to prevent gas leak. Skin is incised subumbilically. Rectus is incised vertically. With haemostat open dissection is done to reach peritoneum which is opened under vision and Hasson's cannula with blunt obturator is passed. Obturator is removed. Hasson's cannula can be passed and used as an outer sheath with other 10 mm cannulas also. Incidence of vessel injury is very much less in Hasson's cannula; but bowel injury can occur if bowel is adherent to port insertion site. But overall injury rate is less compared to Veress needle method **(Fig. 18-62)**.



Fig. 18-62: Hasson's cannula used for open method to get pneumoperitoneum and to achieve primary port insertion during laparoscopic surgery.

Hasson's cannula technique (Open access for primary port – Harry Hasson, Chicago 1974)

Periumbilical vertical/horizontal incision → With retraction, rectus sheath is identified → Two 2 zero vicryl stay sutures are placed in the rectus sheath on either side of the planned vertical incision → Rectus sheath/fascia is incised vertically using 15/11 no blade → Extraperitoneal tissues are dissected using haemostat → Peritoneum is held with haemostat or forceps and opened using 15 no blade or scissor → Blunt finger dissection is done under the peritoneum circumferentially to release any adhesions → Hasson's cannula is placed into the peritoneal cavity and 2 zero vicryl sutures is wrapped around the cannula hub to secure it in place firmly → The camera with telescope is passed through the Hasson's cannula to confirm that cannula tip is inside the peritoneal cavity → CO_2 pneumoperitoneum is created

Contraindications

Previous prosthetic mesh; previous surgery with dense adhesions.

Problems and Complications

Bowel injury

Vessel injury – very rare.

Difficulty in keeping cannula in place.

Repeated gas leak.

Special trocar and cannulas are used while using endo GI staplers, morcellator and laparoscopic ultrasound. Radiolucent disposable trocars are available in situation where obstruction of the vision needs to be avoided like intraoperative cholangiogram.

Valve design: In *trumpet valve*, outer knob is pressed fully to release the block to allow passage of the instrument. It may damage insulation of the instrument and is very crude to use. In *flap valve*, spring loaded device is utilized as a seal and is manually controllable. But it is difficult to control the instrument from outside while passing and removing the instruments. Tissues may get caught in the valve making its sealing ineffective and causing gas leak. In *passive valves*, valves open and close automatically with passage of instruments. In disposable type, plastic or rubber sleeves are used. Magnetic flap valve, multifunctional valve systems are also available. Integrity of valve is checked by pressing and releasing it to get a sound; if sound is rubber like it is good; if it is metallic then valve is improper.

Note:

Reusable metal cannula/port with pyramidal trocar with flap/passive valve is commonly used in laparoscopic surgical practice.

Fascial sheaths of all 10 mm and above ports should be sutured using 2 zero vicryl. Different closure techniques are available – direct vision closure; using different port closure devices; using Veress needle also. If these layers are not closed properly incidence of port site hernia is very high – 2-3% for 10 mm; 4-10% for 12 mm; > 40% for 15 mm port site **(Fig. 18-63)**.

Working Instruments

Other instruments are the working instruments which are the miniature versions of hand instruments used in open surgery. Surgical principles of using various instruments are the same as in open surgery. 5 mm sized working instruments are used. They are long (usual one is 33 cm), well insulated and articulated. Insulation should be perfect as any damage in insulation can cause electrosurgical hazards while performing laparoscopic surgery.

Hand instruments are available as reusable or disposable ones. Both have advantages and disadvantages. Disposable ones are expensive but work well every time. Reusable ones are more suited for our practice as they are cost effective. Instruments such as scissors and Maryland dissectors should be in top working condition before taking up a case for surgery. They are also available in 3 mm diameter. These are not required for performing cases in adults and all instruments of 5 mm diameter are used.

Instruments with locks are used for retraction, suturing and tissue holding. Instruments without lock are used for dissection and cutting (scissors). *Hand grip* may be ring, shank and piston types. Ring and handle may be in line (coaxial) or in an angle (radial) with the shaft. Commonly working instruments are having radial handles with an angle of 70°-90° to the shaft line.

Dissecting instruments can be curved or straight with rotating shaft. Curved Maryland dissector is commonly used. Rotating shaft allows easy dissection with lesser strain to surgeon's wrist.

Scissors must be sharp and insulated. When cautery is used in scissor blades should be opened to prevent blunting of the scissor. Straight scissor is used to cut the suture material. Straight suture cutting scissor is often noninsulated. Microscissor and hook scissors are also used. Bipolar scissor is also available.

Nontoothed, toothed graspers, curved long blade dissectors, blunt dissector, right angle dissector, short and long bowel holding forceps, Allis and Babcock's forceps and claw forceps are other instruments used.



Fig. 18-63: Trocars of various sizes are available in 11 mm, 7 mm and 5.5 mm outer diameter.

Hook is an insulated instrument which is used for dissection. It is connected to monopolar cautery. Bipolar hook is also available. *Spatula* is used again for dissection, coagulation by connecting to monopolar cautery. Its shaft is insulated.

Stone holding forceps, liver retractor, hydatid trocar, needle holders, clip applicators, loop applicators, clips, endostaplers, and endosutures are other specialised instruments used. Needle holder can be 5 mm or 3 mm; can be straight or curved; can be having coaxial or radial handles.

Suction irrigation apparatus is essential to wash and clean the surgical field using warm normal saline. Two types are available – *trumpet type* where suction and irrigation is done using trumpet like action. *Toggle mode type* where suction and irrigation is done through levering bolt in the system. *Toggle mode is commonly used*. 5 mm and 10 mm apparatus are available. 5 mm is better as it does not cause sudden complete loss of pneumoperitoneum obscuring the field. Here with high flow rate of CO_2 gas pneumoperitoneum can be maintained and so image will be visible in spite of suctioning. 10 mm apparatus even though causes rapid suction and not get blocked by blood clots easily, it causes rapid loss of pneumoperitoneum leading to loss of image causing discomfort to surgeon. Few surgeons use heparinised saline for irrigation to prevent clotting and thereby preventing clot block in the suction apparatus; but it is not that essential.

Newer instruments like auto endosuturing instrument, tackers and fixation devices are available. Usually tackers and anchors are 5 mm devices. They are used in hernia repair to fix the mesh in position **(Figs 18-64 to 18-66)**.

Instruments are devised to carry cautery current to the tissue and are available in either unipolar or bipolar mode. Cautery in unipolar mode is used for coagulating bleeders and for dissection of gallbladder from its bed. Bipolar current is used to coagulate mesoappendicular vessels while doing an appendicectomy as we need to minimize lateral thermal damage.

The instruments are insulated over its entire length except the tip and the insulation needs to be checked from time to time as any damage to it can produce leakage of current at that point and inadvertent damage to surrounding structures. The instruments are available in metal or plastic handle. The handles come with or without ratchets. Instruments like the dissector have handles without ratchets allow free movements; toothed graspers are usually with ratchets **(Figs 18-67 and 18-68)**.

Needle holders are available with curved or straight tip and angled or straight handles. Using needle holder is essential for developing skills and going on to the next step in laparoscopic surgery.

Physiologic Changes due to Pneumoperitoneum

CO_2 causes hypercarbia, acidosis and hypoxia. Pneumoperitoneum exerts pressure on the IVC, decreases the venous return and so the cardiac output. It increases the arterial pressure also. It compromises the respiratory function by compressing over the diaphragm impairing the pulmonary compliance.

Respiratory changes are due to – pneumoperitoneum, head down (Trendelenburg) position, increased intra-abdominal pressure reducing cardiac output, reduced venous return (even though CVP in raised).

Raise in intra-abdominal pressure causes reduction in perfusion of spleen, mesentery, and bowel mucosa. So bowel function recovery delays and also renal blood flow.


Atraumatic forceps
Grasping forceps
Scissors

Fig. 18-64: Atraumatic (dissector, bowel holding, Maryland forceps); traumatic forceps and scissors.



Fig. 18-65: Various needles, electrodes (spatula, hook monopolar and bipolar) and suction irrigation cannula set.



Fig. 18-66: Bipolar forceps of different types.



Fig. 18-67: Various common handles with and without ratchets in both plastic and metal handles.


KARL STORZ Germany
KARL STORZ Germany

Fig. 18-68: Needle holders with curved and straight tip. Handles are either straight or angled.

Intraoperative hypothermia (for 50 liter gas flow 0.30°C reduction of body temperature) and prolonged warming using warmer is needed. Warming of insufflation gas will be helpful.

ACCESS TO THE PERITONEAL CAVITY

Access is the key for success – in laparoscopic surgery. Access for camera telescope is for primary trocar which is usually at umbilicus. Access for working trocars are called as secondary trocars which are either 10 mm or 5 mm. Secondary trocars are passed *always* under direct vision **(Fig. 18-69)**.

The first step in a laparoscopic procedure is to access the peritoneal cavity in order to establish pneumoperitoneum. It is done by one of the following two methods.

Closed Technique (Using Veress Needle)

After nasogastric suction and drainage of the urinary bladder, a stab incision is made at the umbilicus, followed by the blind passing of a Veress into the abdominal cavity. *Umbilical incision* may be horizontal supra/infraumbilical or superior crease/inferior crease umbilical or transumbilical vertical/horizontal depending on the surgeon's preference and type of surgery being done. *Supraumbilical incision* is 5 cm above the umbilicus 10 mm horizontal and is used in laparoscopic approach for oesophageal hiatus. *Infraumbilical incision* is 3-5 cm below the umbilicus and is used for pelvic approaches. *Superior umbilical crease incision* is called as crying incision which is used for cholecystectomy. *Inferior umbilical crease incision* is called as smiling incision which is commonly used access incision. Infection rate and bleeding is less common in inferior crease incision. *Transumbilical transverse or vertical incision* is also used. Position of the needle within the peritoneal cavity can be confirmed by aspiration through a water filled syringe and by the water drop test. Once the surgeon is comfortable that the needle is in the peritoneal cavity, pneumoperitoneum is established and trocars are inserted. Flow rate used for initial creation of pneumoperitoneum in 1 liter/minute (maximum 2.5 L/min). Quadro manometry in the insufflator machine is used to check this. Preset pressure should not be more than 18 mm. Usual pressure created is 12 mm. Peritoneal cavity is distended slowly not rapidly. Rapid creation of pneumoperitoneum may compress IVC causing decreased cardiac input. 200 ml of CO_2 once enters the peritoneal cavity causes obliteration of liver dullness which is sure sign of proper positioning of the Veress needle and creation of the pneumoperitoneum (Percussion over the abdomen will be resonant).

Quantity of gas needed to create adequate pneumoperitoneum so as to show pressure of 12 mm is 1.5 liters to 6 liters. Need is less in males and young. It is more in females (multipara) and elderly due to lax abdomen. Size of the abdomen, sex, pregnancy, age and adequate abdominal wall relaxations are the deciding factors.

Open Technique

1. Hasson's open method

After making the umbilical skin incision, the anterior abdominal fascia is incised and the peritoneum is identified under direct vision which is opened carefully using scissor or no 11 blade. Any adhesions prior to insertion of the first trocar is appreciated and released with blunt dissection. The fascia closed around the trocar can be sutured to prevent gas leak which is more common in open method than closed method. The wedge-shaped Hasson trocar can be used to establish a seal in order to allow and maintain the pneumoperitoneum.

2. Scandinavian technique

Here small incision is made directly into the scar tissue of the umbilicus and this is dilated using blunt conical tip trocar and cannula to enter into the peritoneal cavity.

3. *Direct layer by layer dissection* method with subumbilical crease incision

Here after making subumbilical incision, using deep retractors layer by layer dissection is done; rectus sheath is incised horizontally at the junction of the rectus and umbilical fold; peritoneum is adherent to umbilical fold and so can directly enter the peritoneal cavity. Blunt tipped instrument is passed through which 10 mm cannula is passed. Blunt instrument is removed. Cannula is connected to CO_2 insufflator **(Figs 18-70 to 18-75)**.

CO_2 is commonly used to create pneumoperitoneum as --
- It is readily available
- It is cheaper
- It suppresses the combustion
- It is easily absorbed by tissues
- It has a high diffusion coefficient
- It is quickly released via respiration

Other gases used are:

Air, nitrous oxide, helium, argon.

Pneumoperitoneum is created up to a pressure of 15 mmHg which distends the abdominal cavity adequately to have proper visualisation of the abdominal contents.


Horizontal transumbilical
Vertical transumbilical
Supraumbilical
Superior umbilical crease
Inferior umbilical crease
Infraumbilical

Fig. 18-69: Different incisions used to place laparoscopic primary port depending on the type of surgery patient is undergoing.

STORZ
KARL STORZ - ENDOSKOPE
electronic endoflator
264305 20

Fig. 18-70: CO_2 insufflator used for laparoscopic surgery to create and to monitor pneumoperitoneum.



Fig. 18-71: Light source, camera panel and CO$_2$ insufflator used for laparoscopy.

BRAVIA
SONY

Fig. 18-72: Laparoscopic monitor. Good monitor is essential; flat/medical monitors will give clear images.

Note:
Stomach and bladder should be empty prior to trocar insertion.

Gas leak – Gas leak may be from the trocar wound site or from the faulty valve of the trocar. Carefully if observed, sound of leaking gas can be appreciated. If saline is poured at the suspected site air bubbles can be seen. To confirm whether leak is from valve or wound, all instruments including telescope are removed from the ports. Respective trocars of the cannulas are partially passed again. If leak stops then it is due to leak from one of the valves of the cannulas. Suspected cannula trocar is kept and other trocars are removed which will maintain the pneumoperitoneum. Once it is confirmed particular port cannula should be changed. If even after placing trocars of all cannulas in place gas leak continues that means it is from wound site. That particular trocar wound is identified and deep nonabsorbable temporary stitches are placed to prevent leak. Often Allis' forceps is placed to that particular wound edge. Often 10 mm to 5 mm reducers are used to pass 5 mm instruments. As reducers are valveless, if rubber cap on the reducer is damaged, leak can occur. Cap should be changed immediately.



Fig. 18-73: Laparoscopic set trolley used during procedure.

Open access for primary port is usually done through umbilical incision. But it is often *contraindicated* in previous midline scar; portal hypertension with cirrhosis as umbilical artery may be recanalised; congenital umbilical abnormalities like urachal diseases, vitellointestinal diseases.

Secondary working ports are placed on direct vision. These working ports are usually on right and left sides of the camera (primary) port. It should be at adequate distance from camera port to prevent instrument touching the telescope leading to blockage of free movements of the working instruments. Smaller diameter trocar is usually placed at surgeon's dominant hand side to allow proper wrist movements and also to avoid tremor during procedure. Initially site is pressed with finger on the abdominal wall while visualising the indentation in the monitor. Skin incision must be 1½ times larger than size of the trocar. Dermis should be cut adequately using no 11 blade stab incision. Trocar is held with the palm of the hand and thumb and index finger. Middle finger is extended along the shaft of the cannula/trocar towards the tip to achieve good control of the trocar while piercing the abdominal wall and also to prevent sudden rapid entry into the peritoneal cavity. Trocar is pierced with rotating screwing movements, (not by pushing) at 90° to skin; once it reaches the peritoneal surface it is angled 45° obliquely while entering the peritoneal cavity. Entire procedure should be done under vision in monitor.

Other Approaches to Access Peritoneal Cavity

Approach Using Visiport

Access can be done under direct vision *using visiport* wherein telescope is passed through it. Tip of the visiport contains fine retractile blade which on firing makes small fine incisions in the tissue allowing movement of the port under vision towards the peritoneal cavity. It is very useful in accessing the peritoneal cavity with previous surgery and also in obese patient **(Fig. 18-76)**.


30° telescope
0° telescope
KARL STORZ Germany
Attaching telescope to camera by rotating its head part
Connecting the light source cable to telescope
Open method to place the 10 mm camera port
Sub or supra umbilical curved incision
Often blunt tip rod is passed through peritoneal opening into the peritoneal cavity
Through this rod 10 mm port is passed inside.
CO_2 insufflation tube is connected. Gas is flown into the cavity initially at slow rate to create pneumoperitoneum gradually. Later flow rate can be increased.
White balance is done by focusing the telescope tip onto a white gauze until "white balance OK" - sentence comes in the monitor.
White balance is under process
SONY

Figs 18-74(1)


White Balancing.....
PRESSURE
mmHg
ACTUAL
SET
VOLUME
Ltr
TEMP
ERROR
START
HEATER
VOL RESET
START STOP
HEATER ON
FLOW
Ltr / Min
ACTUAL
SET
WER
STORZ
Inset

Distended abdomen after pneumoperitoneum; on percussion resonant note all over will be evident

Inside hot water filled flask sterile gauze should be kept to safeguard telescope tip

Hot saline filled sterile flask

Telescope is warmed by dipping it inside hot saline flask so that image inside peritoneal cavity will be clear by preventing tip getting fogged.

Entering and visualisation of peritoneal cavity. Liver, gallbladder, spleen, entire cavity should be inspected

Telescope is focused on the site where additional ports are placed; site is pressed with finger to visualise an indent inside

10 mm skin incision to place working port

Holding the 10 mm trocar with port to insert into peritoneal cavity

Figs 18-74(2)


Trocar with port is inserted with gentle drilling movement into the peritoneal cavity under vision
Trocar tip reaching the peritoneum causing indent
Trocar and port entering the peritoneal cavity
Trocar is removed to keep working port in place
10 mm camera port
10 mm working port
Placing additional 5 mm port
Bipolar cautery is safer
Reducer (10 to 5 mm port)
5 mm instrument (bipolar cautery here)
Inserting reducer through the 10 mm port with 5 mm instrument
5 mm suction irrigation instrument
For irrigation using normal saline
For suctioning - connected to suction apparatus
Suction tip inside

Figs 18-74(3)

Figs 18-74(1 to 3): Laparoscopic access technique – steps.



Fig. 18-75: After completion of placing primary and secondary ports, ready for needed surgical technique.

Left Palmer Point Approach

In abdomen with previous surgeries especially for incisional hernia and adhesiolysis, *left Palmer point* (left subcostal point) is used as direct method to access the peritoneal cavity.

COMPLICATIONS IN LAPAROSCOPY

Complications of Access

The rate of complication associated with Veress needle or trocar insertion is approximately 0.3%. They are - injuries to major retroperitoneal vessels and to bowel (0.2%), which are associated with significant morbidity and mortality; abdominal wall hematoma (2%); wound infection (1.2%); fascial dehiscence and herniation (port site/umbilical – 1.5%). Open technique leads to less frequent wound complications in laparoscopic surgery. Though major vascular injuries and bowel injuries with trocar placement are quite rare, use of the open technique may decrease the incidence of these dangerous complications **(Fig. 18-77)**.

Physiologic Complications of Pneumoperitoneum

Pneumoperitoneum causes several local and systemic effects, as reviewed by *Hackam* and *Rotstein*. The majority of these effects are beneficial for patient recovery, such as an observed decrease in postoperative pain and metabolic stress response, as measured by serum glucose and insulin levels and the hepatic catabolic response, measured by functional hepatic nitrogen clearance.



Fig. 18-76: Visiport can be used to pass primary port.



Fig. 18-77: Primary port which has passed through small bowel which was adherent abdominal wall due to previous surgery.

Physiologic Complications of Laparoscopic Surgery

- Carbon dioxide pneumoperitoneum causes respiratory acidosis from absorption of the gas. Subcutaneous emphysema, pneumothorax, pneumomediastinum and pneumopericardium are other problems.
- Deep venous thrombosis (DVT - with 40% having calf DVT and 15% having axial vein DVT).
- Cardiac output decreases by up to 30% during laparoscopic surgery, due to a decrease in stroke volume. Pneumoperitoneum also causes an increase in systemic vascular resistance. As a result, mean arterial pressure remains unchanged or increases up to 16%. Patients with marginal cardiac performance may warrant invasive cardiac monitoring to assure they tolerate pneumoperitoneum. This is partly due to intravascular volume status, and could be ameliorated by preloading patients with isotonic fluid and achieving pneumoperitoneum in the supine position rather than the reverse-Trendelenburg position. Treating these patients with clonidine blunted the increase in mean arterial pressure, systemic vascular resistance and the release of catecholamines. Cardiac arrhythmias (more common if halothane is used) are most common cardiac complication.

Complications of laparoscopic surgery	*Relative contraindications*
• CO_2 narcosis and hypoxia. • Sepsis—subphrenic abscess, pelvic abscess, septicaemia. • IVC compression. • Bleeding. • Leak from the site, e.g. bile leak. • Organ injury during insertion of ports, e.g. major vessels, bowel, mesentery, liver. • Subcutaneous emphysema and pneumomediastinum. • Gas emboli, though is rare but fatal. • Gastric content aspiration. • Hypothermia. • Postoperative shoulder pain due to irritation of diaphragm. • Hyperabduction of arm can cause stretching of the brachial plexus and neuropraxia. • Trendelenburg position can cause common peritoneal nerve injury. • Cardiac dysfunction due to decreased venous return. • Injury to the abdominal wall vessels and nerves. • Cautery burn to abdominal structures. • Abdominal wall hernias – port site hernias. • Wound infection. • Mortality—0.5%.	• Patients with compromised cardiac status. • Peritonitis. • Previous abdominal surgeries. • Bleeding disorders. • Morbid obesity. • Third trimester pregnancy. • Portal hypertension, cirrhosis. • Raised intracranial pressure. • Glaucoma. • Peritoneo-jugular, ventriculo peritoneal shunts. **Limitations** Lack of tactile sensation; tissue feel is absent. Only eye-hand coordination is the method.

- *Gas embolism* – It can occur (but very rare) by direct entry of CO_2 through inadvertent injury by Veress needle or trocar; when small gas bubbles enter the injured vein; absorption of large quantity of gas into the portal system which forms bubbles that get trapped in the portal system as well as in the pulmonary circulation at a later period. Smaller bubbles block pulmonary circulation; larger one causes gas lock in IVC and right atrium (may cause sudden death). On table patient develops tachycardia, hypotension, arrhythmias, convulsions, metallic/*mill wheel* murmur (heard through precordial or oesophageal stethoscope). Foaming of blood in CVP catheter, precordial Doppler (detects passage of even 2 ml of gas), oesophageal Doppler (detects even 0.5 ml of gas). $P_{ET}CO_2$ raises in *capnometry* which is the most valuable non-invasive method to detect gas embolism. 20% of such patients during recovery may show blindness. Once on table gas embolism is diagnosed, immediately pneumoperitoneum is stopped and gas is released; patient is kept in steep head down and left up position; hyperventilation; CVP catheter gas aspirations are done. Nitrous oxide should be stopped.

DIAGNOSTIC LAPAROSCOPY

With the availability of diagnostic modalities like helical CT and MRI scans the role of laparoscope in diagnosing occult abdominal pathologies has greatly reduced. Most often the laparoscope is used as confirmatory investigation before the pre-planned procedure such as appendicectomy or adhesiolysis for subacute intestinal obstruction. The other area where the laparoscope is helpful is to ascertain the anatomical origin of masses in the right iliac fossa in women of reproductive age where there is suspicion of tubo-ovarian pathology. Even abdominal tuberculosis can be now diagnosed with ancillary investigations such as PCR for tubercular DNA. Laparoscopy is now a precursor to appendicectomy or adhesiolysis in case of chronic vague abdominal pain where other investigations have not yielded a diagnosis **(Figs 18-78 to 18-80)**.

Preparation

- It is done always under general anaesthesia. It can be done under local anaesthesia also but it is cumbersome and painful to the patient. Other preparations are same as for open method.
- Pressure bandages are applied to both legs to improve the venous return and to decrease the stasis.
- Head end of the table is lowered to have easier insertion of Veress needle and scope.
- Ryle's tube and Foley's catheter are essential before insertion of the trocars.
- Pneumoperitoneum is created using Veress needle through umbilical incision. Access can be achieved by open method through an umbilical incision.

Procedure

Peritoneal access is gained by either open or closed method. Before proceeding to place accessory ports attention is given to the suspected pathology. Placement of working port is generally guided by the proposed site of the pathology and also the planned procedure. Lower abdominal pathology demands ports placed on either side of the rectus muscle at or just below the umbilicus. If pathology is anticipated or seen in stomach, liver, spleen on preliminary screening then the ports should be placed above the



Fig. 18-78: Laparoscopic set showing trolley, telescope and monitor instruments.

umbilical level in suitable position. Bowel should be inspected along its entire length by alternately moving the working instruments on the bowel and both sides should be inspected for pathology. The method of inspection is similar to that of exploratory laparotomy. Laparoscopy gives great advantage when inspecting the diaphragm and the pelvic structures. The procedure is converted to a definitive procedure when the pathology is identified. Routinely the procedure culminates in an appendicectomy even when no other obvious pathology is evident as it prevents diagnostic difficulties at later date **(Figs 18-81 to 18-83)**.

Note

- Instruments should be checked prior to procedure for proper functioning.
- Cardiac, respiratory fitness should be assessed.
- Position, preparation is a must.
- Adequate pneumoperitoneum should be created; gas leak should be prevented or tackled effectively.
- Telescope should be warmed before insertion to prevent fogging.
- Tip of light cable is very hot and should not touch drapes or patients' skin. It may cause deep burn injury.
- Camera operator should hold the camera firm and strong to have good view of surgical site.
- Telescope tip can be cleared by obscuring blood by touching her tip to omentum or abdominal wall or solid organ like liver. Otherwise it should be removed and cleaned with savlon and warm saline. Tip of telescope should never be touched to the bowel as it may injure the bowel.
- Insufflation gas inlet can be changed to working port instead to camera port to prevent undue fogging.

LAPAROSCOPIC ULTRASOUND

Fukuda in 1981 used laparoscopic ultrasound. Transducer in ultrasound is made up of piezoelectric cells. USG flexible probes are used which are 7 cm in length and 12 mm in diameter. Two monitors are required; one for laparoscope other for ultrasound. Now single monitor is available where both laparoscope and ultrasound images are seen which allows better hand-eye coordination.

Laparoscopic USG probes are sterilized by glutaraldehyde or through ethylene oxide.

Laparoscopic USG is useful in assessing the liver tumours, biliary tree, hepatic nodal status, pancreas, lymph nodes in different areas of the abdomen, spleen, kidneys and adrenals. Laparoscopic ultrasound is very useful in assessing the solid organs, its use is not very much in assessing the small bowel and colon because of the gas in the bowel. It is used to identify the lesions accurately with its size, vasculature; to stage the disease; to assess the resectability of tumour; to identify the vessels and its relations to the organs like hepatic veins in liver resection.

Laparoscopic USG can be used in different therapeutic purposes in liver like radiofrequency ablation and deroofing of the liver cyst. Laparoscopic USG is very useful in identifying biliary stones and is better than intraoperative cholangiogram. Endocrine pancreatic tumours are well identified by laparoscopic USG. Identification of pancreatic duct during pancreaticojejunostomy is better with laparoscopic USG. Laparoscopic guided biopsy is even though done, but it is controversial. Laparoscopic FNAC is a good diagnostic tool. 3D ultrasound is now available with better clarity of images **(Fig. 18-84)**.

3 D LAPAROSCOPY

3 D laparoscopy is now available with more clarity and 3 dimensional look. 3 D camera available at present is heavy (1 Kg). It is often difficult for cameraman to hold it and negotiate. Suturing and image quality is good in this but it is costly.

There is marked and significant improvement in operative time with a stereoscopic 3 D laparoscopic view of the operative field. As procedure is performed with identical mechanical instrumentation like in 2 D laparoscopic instruments the difference attributable is only to the changes in depth perception obtained with the 3 D laparoscope. This skill obtained with this finally will be beneficial in advanced procedures like laparoscopic radical prostatectomy, laparoscopic pyeloplasty, or other complex reconstructive procedures. One of the biggest challenges in laparoscopic surgical training is adaptation to a 2 D flat view of the surgical field. 3 D laparoscopic visual systems have been developed to augment laparoscopic skills. Suturing skill will be much more precise and accurate and also will be faster.

SINGLE INCISION LAPAROSCOPIC SURGERY

Single incision laparoscopic surgegy (SILS) is an advanced minimally invasive surgical procedure wherein surgeon operated exclusively through a single umbilical entry port. It is also called as single port access surgery (SPA), one port umbilical surgery (OPUS), and single-port incisionless conventional equipment-utilising surgery (SPICES), natural orifice transumbilical surgery (NOTUS).

It is used in cholecystectomy, appendicectomy, gynaecologic procedures, hernia surgery and other selected procedures.

It needs general anaesthesia, specialised umbilical large trocars which accommodates working instruments also, flexible laparoscope, rotatable instruments, articulating handles, harmonic scalpel.

Here through a large 2 .5 cm umbilical vertical incision dissection is done by open method to reach peritoneal cavity. Through this is passed a specialised port where one can pass 10 mm telescope and two 5 mm instruments for laparoscopic work. Instruments are angled and flexible to meet the ergonomic principles to certain extent. Dissection of gallbladder is done in similar fashion like four port technique.


5 mm trocar
5 mm port
5 mm
10 mm trocar
10 mm port
10 mm
10 to 5 mm reducers of different lengths

Fig. 18-79: Different instruments used for diagnostic laparoscopy.

Specimen is easily retrieved through umbilical port as it is wider enough. If difficulty arises any time one can add additional ports as required.

SILS is now used in appendicectomy, ovarian cyst excision, selected cases in hernia and other procedures also.

Advantages

- There is no visible scar like a traditional multiport.
- Faster recovery time, early return to work.
- Cosmetically better **(Fig. 18-85)**.



Fig. 18-80: Diagnostic laparoscopic view in ascites (tuberculosis); twisted ovarian cyst, ovary and Fallopian tube; undescended testis with inguinal hernial opening at internal ring.



Fig. 18-81: Adhesiolysis.

Disadvantages

- Expensive trocars and instruments.
- Skilled work, learning curve.
- Dissection against normal surgical ergonomics.

Complications

- Umbilical wound pain, infection.
- Umbilical hernia.
- Time consuming because of limited visibility.
- During learning curve complications of cholecystectomy or other procedures and conversion rate may be more.

GASLESS LAPAROSCOPY (LAPAROLIFT)

Dan Kruschinski is the *Preceptor of Gasless Lift-Laparoscopy* since 1991 with an ongoing process of establishing excellent vision with new abdominal lift devices to ensure a cost-effective laparoscopic start-up system.

It is forward retraction of the anterior abdominal wall so as to create the effective working cavity inside the peritoneum to facilitate the dissection. It may be useful for pelvic and lower abdominal surgeries (APR/ovarian surgeries), appendicectomy, etc.

Advantages

Complications of CO_2 pneumoperitoneum are not present. It can be done under regional anaesthesia. It provides appropriateness, equity, accessibility, availability, affordability to the rural people wherein cost is also a main factor. In developing countries 80% rural



Fig. 18-82: Laparoscopic view of twisted ovarian cyst.



Fig. 18-83: Laparoscopic procedure in progress showing camera, telescope, ports, working instruments.

population is provided by 20% of surgeons. Laparolift will be useful to these patients considering their need (as they need to return their work earlier) and economy. Valveless trocars can be used. Suction usage can be unlimited. Conventional instruments can be used when need arises. During induction of anaesthesia increased ventilator pressure is not needed. It shows less infection rate; equally cosmetic; less postoperative pain; early faster recovery; shoulder pain will not be present; safer and precise.

Disadvantages

Movement of the viscera during inspiration causes difficulty in targeting the proper dissection unlike in dissection with pneumoperitoneum which is motionless. Technique even though is used in many places, is less popular due to difficulties in developing adequate lift.

HAEMOSTASIS IN LAPAROSCOPIC AND OPEN PROCEDURES

As there is no direct access to the bleeders, it is often difficult to control the bleeding during haemostasis. Often difficulty in controlling the bleeding becomes an indication for conversion into open at least during learning curve period. It is better to have an idea about different haemostasis methods during laparoscopy. Proper ergonomics and triangulations are very important in laparoscopy. One should able



Fig. 18-84: 3 D laparoscopy camera and monitor. Present 3 D camera is heavy weight – nearly one kilogram in weight.



Fig. 18-85: Single incision laparoscopic surgery (SILS) for cholecystectomy/appendicectomy and also for other procedures.

to grasp and coagulate the bleeding the tissue properly. Meantime blood from bleeding point if spills over the laparoscope tip, it will blur the image and situation becomes panic as bleeding point/area is not visualised. Surgeon should console the cameraman and ask him to stay steadily on the site of bleeding until it is well controlled. While achieving haemostasis, it is also important not to injure the adjacent structures either with clip or energy source. In cholecystectomy with cystic artery bleed, clips may be applied in a hurry to control bleeding over the common bile duct partially injuring it; cautery when used, especially monopolar cautery may cause lateral thermal damage to closely existing common bile duct wall which eventually leading into necrosis of its wall causing disastrous bile leak.

Laparoscopic haemostasis may be achieved by different means.

a. **Mechanical devices** – Clips, lineal stapling devices, pretied suture loops (endoloop/loop done in theatre table as extracorporeal knot which is pushed towards the site as ligature), intracorporeal ligature placement, transfixation suturing intracorporeally.
b. **Energy sources** – Electrocautery, ligasure, laser, ultrasonic dissection (Harmonic), cavitron ultrasonic surgical aspirator (CUSA).

Mechanical Devices

Mechanical Clips

They are made up of titanium inert, least reactive clips available which are applied through 10 mm clip applicator. Clips are available in 7mm (medium), 9 mm (medium large) and 11 mm (large) size. Medium size is usually used. Size usage is decided as needed by the surgeons. Same clip applicator can be adjusted for different size clip placement by adjusting the applicator gap at the end. Reusable clip applicator is commonly used even though preloaded clip applicator is available. Preloaded disposable clip applicator contains 20 clips in a row which can be applied consecutively, one after other which makes surgery faster. Absorbable clips are available mainly to apply onto the continuous suture intraperitoneally to hold it at the beginning and at the end. Usually two clips are applied proximally close to each other. Third distal clip is applied at 3-5 mm gap. Tissue is cut between proximal two clips and distal clip. While applying the clip, both ends of the clip should encroach the tissue/duct/vessel completely and clip should be applied under vision with confirmation that it is not entangling any other tissues and ends are clearly seen before compressing the clip firmly. While cutting the tissue, gap should be kept distal to proximal two clips to prevent slipping of the clip. At least 5 mm of tissue should be present freely proximal to proximal clips to prevent clip migration (example – while applying clips in cystic duct). Clip applicator is usually straight but angled one is also available. Even though it is of practice that application of ligature along with or after applying the clip; it will loosen the clip due to tissue distortion. In such situation suture ligature should be finished first and then clips should be applied at needed place **(Figs 18-86 to 18-88)**.

Lineal Stapling Devices

Lineal stapling devices are very useful to deal with splenic, renal, inferior mesenteric vessels in respective laparoscopic surgeries. Different sizes are available – 2.5 mm vascular; 3.5 mm intestinal; 4.5 mm intestinal/colonic **(Fig. 18-89)**.



Fig. 18-86: Plain X-ray abdomen showing clips of laparoscopic cholecystectomy.



Fig. 18-87: Applying clip for a vessel in the abdominal surgery.



Fig. 18-88: Clip applied for appendicectomy.



Figs 18-89(1)



Figs 18-89(2)

Figs 18-89(1 and 2): Endostapler device with cartridges for stapling the bowel during resection.

Pretied Loops

Pretied loops are available as manufacturing which are made up of chromic catgut. It is mainly used in appendicectomy. Same loop can also be used in passing ligature around a specified bleeder. Bleeder is held using a Maryland instrument through a working port; pretied loop is passed through another 10 mm working port through a reducer. Instrument which was holding the bleeder is once released and passed through the loop and held again (if additional working port is there bleeder can be held using another grasper little proximally) to allow the loop to encircle the bleeder/bleeding tissue and loop is tied firmly by releasing and tightening the control shaft proximally outside. Often Roeder's knot can be made outside using vicryl suture keeping its proximal length long which is looped in the same way and knot is pushed into the site using a knot pusher or a Maryland instrument **(Fig. 18-90)**.

Extracorporeal Ligature

Extracorporeal ligature can be made and is pushed through 10 mm working port through a reducer into the tissue. Here initially long suture material is passed through 10 mm port into tissue and is encircled properly and other end is brought out through the same working port



Fig. 18-90: Endoloop is often used to pass a ligature. It may be pre-ttied endoloop (chromic catgut) or endoloop is made using Roeder's knot with vicryl.



Fig. 18-91: Bleeder is held using a Maryland which can be later fulgurated using cautery.

through reducer outside to make both ends of the suture material is outside. Knot is tied outside the port which is pushed across the reducer into the looped tissue to form a firm strong knot **(Fig. 18-91)**.

Intracorporeal Suture

Intracorporeal suture is done using intracorporeal knotting technique. It needs a proper training. It is essential for all advanced laparoscopic surgical procedure.

Energy Sources

Diathermy (Electrosurgery)

Electrosurgical units (ESU) used in operating rooms convert standard electrical frequencies from the wall outlet, which are 50 to 60 Hz, to much higher frequencies, 500,000 to 3,000,000 Hz. This is important to minimize nerve and muscle stimulation, which occurs at electrical currents below 10,000 Hz. High frequency (3 lakh to 6 lakh Hz) current, is allowed to pass through the tissue to create conduction heat achieving haemostasis. *In monopolar type*, current flows from generator to patient through active electrode and returns back through the return electrode to the generator. It is *pulsed wave, low frequency and high voltage* current for *coagulation cautery*. It is *continuous wave, high frequency and low voltage in cutting* type of monopolar cautery. Active electrode passes through a fine probe to the needed tissue area; whereas return electrode is with 22 square inches of surface area flat plate placed under muscular surface with gel conductive coating. Active electrode contacts in less area than return electrode. Current gets concentrated in less area in active electrode to achieve needed effects. Effects may be coagulation or cutting. Coagulation is achieved by protein denaturation and coagulation necrosis. Cutting is due to rapid focal tissue heating causing tissue disintegration without any coagulation necrosis. So cutting cannot cause coagulation. Coagulation at the tip of probe can cause cutting but with more charring. *In laparoscopy mainly coagulation monopolar cautery is used.* Coagulation in hook or spatula can cause cutting by proper holding and positioning the instrument while creating the contact with tissues. Cutting cautery has got limited role. Pulsed coagulation in blend mode is better. During laparoscopic usage of monopolar cautery, one should be careful as instrument which has cautery cable attached is visible only at its distal 10%. During usage, one should always confirm that proximally insulation is visible. Instrument should have proper insulation without any damage otherwise severe burns of the abdominal wall at port site or damage to adjacent tissues or bowel perforation, injury to great vessels can occur. Often it may be life threatening. Direct coupling and capacitance coupling can occur. Lateral thermal damage is equally dangerous. Lateral thermal injury can occur up to 8 mm of tissues beyond; in pedicle coagulation thermal injury and vessel spasm can occur at the base of that particular pedicle **(Figs 18-92 and 18-93)**.

In bipolar cautery active and return electrodes are separated by few mm passing through the hand probe, not through the body. So conduction (earthing) plate is not needed in bipolar. Bipolar reduces the adjacent tissue damage. It has got less lateral thermal heat. Bipolar can be used only for coagulation but not cutting. Bipolar is very important in laparoscopic surgery as it reduces inadvertent vital structure injury **(Figs 18-94 and 18-95)**.

Problems and Complications of Cautery

Injury to bowel due to heat, direct or lateral, may be unnoticed or not obvious which may later be able to cause full thickness ischaemic necrosis and perforation with peritonitis. This can occur often as late as 10 days also.

Direct injury into the major vessel and vital structure through cautery can occur while instrument touches these structures and cautery got on inadvertently by assistant or scrub nurse or surgeon himself. Ideal is to disconnect the cable from the instrument when not in use.



Fig. 18-92: Monopolar hook is commonly used in dissecting the peritoneum, creating the plane, dissecting the gallbladder from its bed. Bipolar hook is also available. It is biflanged.



Fig. 18-93: Monopolar is used for dissection as well as dissection. Bipolar is mainly used for coagulation; but dissection is also possible.



Fig. 18-94: Bipolar cautery in use. Here active and return electrodes are very close by.

Insulation failure due to damage to the insulation and damaged part may be in direct contact with bowel. Prior checking the instrument for its insulation and function is essential always **(Fig. 18-96)**.

Direct coupling can occur when instrument which is connected to cautery (e.g. Maryland) touches instrument in the port which is not insulated like laparoscope which is passed through a plastic cannula as plastic port cannula prevents passage of current into return electrode. Current is directed into different tissues which get fulgurated as injury **(Fig. 18-97)**.

Capacitive coupling injury can occur if cautery is activated before the instrument tip makes contact with the tissue with a metal cannula and plastic sleeve which prevents return current to reach return electrode across body causing bowel injury. Capacitor is two conductors separated by an insulator. Electrosurgical device is one conductor; metal cannula is another conductor; with insulator sleeve.

If return electrode is inadequate (inadequate surface area in plating) then return current will pass through other surface metals causing severe surface burns.

If bowel injury occurs and suspected it is better to convert into open to identify proper site of heat injury which needs excision with adequate margin and proper re-suturing using interrupted silk or vicryl sutures.

Ultrasonic Dissector

The *Harmonic scalpel* is a high frequency ultrasonic transducer. The active titanium blade vibrates at 55,000 cycles per second. Electric power is applied into a device which contains piezoelectric crystal to create high frequency vibration waves. From this crystal vibration is carried to a rod to instrument tip to move its long axis. Induction of mechanical vibration at cellular level using high frequency waves more than 55,000 Hz leads into friction and shear injury leading to needed effects. When applied to tissue it causes protein denaturation and coagulum formation at lower temperature (up to 80° C). It seals and cuts the tissues including vessels up to 2 -5 mm. There is no risk of electric burn or lateral thermal injury. Charring is less here compared to electrocautery and so less smoke in comparison. Field is clean and bloodless.

Hand instruments are available in 10 mm and 5 mm size in harmonic scalpel. 5 mm harmonic probe is commonly used now even though initially only 10 mm probes were available. It can be used as a grasper, coagulator, dissector and cutting instrument so that exchange of many instruments is minimised leading to faster, cleaner and better surgery. Hand instrument contains an ultrasonically activated blade which can be rotated as sharp/round/flat edges. Non-activated pad opposes this active blade to hold the tissue to create friction and shearing. Power level setting is needed in the instrument to create appropriate action. Level 1 – coagulation only; level 5 – cutting only; median power of 2-3 is usually used; usually rounded blade is used. Device is very useful in many dissections like mesoappendix in appendicectomy, cystic artery and Calot's dissection in cholecystectomy. Prior using the instrument activation is essential each time **(Fig. 18-98)**.

Harmonic ace is a modified 5 mm harmonic probe with more transection speed and haemostasis and vessel sealing capacity with



Fig. 18-95: Monopolar cautery used for haemostasis by coagulation current and for cutting by cutting current.



Fig. 18-96: Insulation failure causing direct diathermy injury to adjacent bowel through the 5 mm working instrument.



Fig. 18-97: Direct coupling.



Fig. 18-98: Harmonic scalpel with its use.

additional hand activating system. 5 mm blade is available as a hook, straight and curved electrodes. Versatile curved blade is commonly used. As compared to the other devices listed, the Harmonic Scalpel is FDA approved to seal vessels up to 5 mm.

Precaution – Harmonic scalpel is very safe instrument; but integrity of instrument should be touched at the active blade; its sheathing (Teflon pad) should be adequate. While operating tip should not touch other instruments or metallic parts as tip may blast by short circuiting.

Ligasure (Valleylab)

This bipolar electrosurgical device delivers high current, low voltage along with pressure from the jaws to tissue. It can seal vessels up to 7 mm in size. This differs from the high voltage, low current energy used in standard monopolar and bipolar cautery. The system monitors the energy expended while denaturing the collagen and elastin within the vessels walls. During the cooling phase of the cycle, cross-linking reoccurs creating a new seal. The instrument is available in 5 or 10 mm sizes. Tissue sensing technology in the Ligasure makes use of a computer algorithm to adjust the current and voltage based on real-time measures of tissue impedance. This results in a constant delivery of voltage over a broad range of tissue types. Grounding pad is not needed. Power comes from electrosurgical generator. Through hand set it reaches the blade. Sealing capacity is more here. It has got the highest burst pressure, low thermal spread, fast sealing time, and low smoke production. But smoke production is more than harmonic scalpel and instrument is not as fine as harmonic. Tissue is held with blades and is locked in handle. Foot switch is pressed to activate ligaseal. Generator gives an audible tone at the completion of cooling period. After that there is a blade in the jaw which moves to cut the tissue through a system in the handle. After that blades are unlocked. Lateral thermal spread is only up to 1.5 mm adjacent tissues. Open seal instruments are also available for haemorrhoidectomy, thyroidectomy, open GI surgeries. It is useful to seal safely uterine, splenic, inferior mesenteric arteries **(Fig. 18-99)**.

Problems – It cannot be used for dissection; takes more time; after repeated use it becomes sticky, opening the jaw after sealing often becomes difficult and forcible opening results in tissue tear and bleeding.

LAPAROSCOPIC TISSUE APPROXIMATION

Laparoscopic suturing is discussed in chapter 3. Other methods of tissue apposition are briefed here.

Laparoscopic suturing – Coaxial handled needle holder is better piston handled for intracorporeal suturing and knotting. Needle holder is held in dominant hand; supporting grasper (5 mm atraumatic, without ratchet) is held with non-dominant hand. Length of the suture material is 10 cm for first suture bite and knot with 2 cm for additional each needed suture. Lengthy suture material creates problem in manipulation inside the peritoneal cavity. Usually 2 zero vicryl is used. Needle often needs some bending (straightening) to allow it to pass through the reducer of 10 mm port; otherwise it can be pierced directly across the abdominal wall into the peritoneal cavity under direct vision. 3 zero vicryl is used to suture in pyeloplasty or in bile duct suturing. Triangulation and proper ergonomics are very important for proper endosuturing. Two instruments should meet at 60° angulation. Additional trocars should be placed to create triangulation to prevent sword fighting and crowding. 30° angled camera is better. Zoom in is done while taking bite; zoom out is done while knotting. 3 D laparoscope may be much more useful.



Fig. 18-99: Ligasure instrument.

Needle is passed into the peritoneal cavity through 10 mm port across reducer. Thread 1 cm away from the needle is held in a grasper or Maryland or needle holder which is already passed across the reducer; needle is pulled into the reducer sleeve; reducer is passed across the port into the peritoneal cavity; needle is released into the place under vision. Needle can be directly punctured separately across the abdominal wall under direct vision in thin individual and children. Needle is also can be passed across the 5 mm port wound after removing the 5 mm port temporarily through a 5 mm instrument needle holder or Maryland in which suture material of the needle is held 1 cm away from needle. Holding the needle at proper site in the needle holder, needle bite taking across tissue, putting a tight proper knot is an art in intracorporeal suturing. Learning curve, dedication and concentration is needed to this technique. Eye-hand coordination is important. Creation of C loop and passing the opposite instrument and pulling the end thread is initial technique to create first knot. Similarly further 2 knots are placed. Roeder's knot, extracorporeal knot creations are all other knotting techniques used.

Endostaplers are used in resection of bowel, gastrojejunostomy, anterior resection, stapling of vessels in splenectomy, nephrectomy, etc.

Autosuture endostitch devices are available wherein suturing and knotting is done easily with this.

LAPAROSCOPIC PORT SITE CLOSURE

Port site is closed by different methods. Fascial plane at any port site more than 5 mm size should be closed using 2 zero vicryl. Different methods are available with different instruments. Direct closure is also possible. Curved stout eyed port closure needle with a stout handle is often used wherein suture material is passed into its eye which is pierced across the both edges of the fascia and later tied. Fine long straight specialised port closure needle is also available which is pierced across the fascia and peritoneum into the cavity under laparoscopic vision; when its fine jaws are opened vicryl suture material which is passed across the port is grasped and pulled out; similarly it is repeated on other side and later knot is placed **(Fig. 18-100)**.

Skin is sutured with absorbable subcuticular suture (monocryl) or clips or interrupted monofilament sutures or cyanocrylate glueing **(Fig. 18-101)**.

STERILISATION/DISINFECTION OF LAPAROSCOPIC INSTRUMENTS

Laparoscopic Instruments are having complex design, delicate, increase bioburden in crevices, difficult to clean. They are used in complex laparoscopic procedures. It is difficult to clean, sterilise or maintain these instruments.

Sterilisation is a process that destroys all forms of microbial life (including spores) absolutely by physical/chemical methods; steam under pressure (autoclave), dry heat, ETO, Gas plasma;



Fig. 18-100: One of the methods of port closure technique.


STERILE UNI PACK
ISO AMYL 2-CYANOACRYLATE
Marvilyte

Fig. 18-101: Cyanocrylate glueing to close the skin.

liquid chemicals. Some disinfectants on prolonged exposure can destroy spores.

Disinfection is a process that destroys many or all pathogenic bacteria but not their spores; used on inanimate objects; use of liquid chemicals (Disinfectants).

Splauding Classification of Objects and Level of Sterilisation

Critical	*Semicritical*	*Non-critical*
Entry or penetration into sterile tissue, cavity or bloodstream	Entry to mucous membrane or non-intact skin	Entry to intact skin Noncritical patient care Noncritical environmental surfaces
Surgical instruments, Cardiac/ Urinary Catheters, Implant, USG probes	Laparoscopes, Endoscopes, respirator and anaesthesia equipment	Bed pans, blood pressure cuffs, Furniture, bedside table, utensils
Sterility required	Objects to be free of all microorganisms but not spores.	Objects to be clean

DISINFECTION

Disinfection may be -

High Level Disinfection (HLD)

At same concentration as chemical sterilants, but shorter exposure, the same disinfectant can kill only the microorganisms and ***not*** spores. E.g. Glutaraldehyde, OPA, per acetic acid, hydrogen peroxide.

Intermediate Level Disinfection

Can kill mycobacteria, vegetative bacteria, most viruses, most fungi but ***not*** the spores, e.g. Ethyl/isopropyl alcohol, sodium hypochlorite, iodophors, phenolic compounds.

Low Level Disinfection

Can kill most vegetative bacteria, some fungi, and some viruses within 10 minutes. Same as above and quaternary ammonium compounds.

For laparoscopic instruments high level disinfection may be sufficient. *Reasons are* – Only a limited number of organisms (usually $\leq$10) are introduced into the peritoneal cavity during laparoscopy; minimal damage is done to inner abdominal structures with little devitalized tissue; peritoneal cavity tolerates small numbers of spore forming bacteria; these equipments are easier to clean and disinfect; natural bioburden on rigid lumen devices is low. There are no evidence exists that high-level disinfection instead of sterilisation increases the risk for infection.

But sterilisation is proposed by many. *Reasons are* – degree of tissue damage and bacterial contamination is greater; possibility of transmitting infection by spore-forming organisms; increased bioburden due to complex design; risk of bio film formation.

Choice whether sterilisation or disinfection is needed depends on—type of instrument material; intended use and function; instrument design; compatibility with various sterilization processes.

Disinfectant/ sterilant	*Advantages*	*Disadvantages*
Glutaraldehyde	• Relatively inexpensive • Excellent materials compatibility	• Respiratory irritation from vapour • Pungent and irritating odour • Relatively slow mycobactericidal activity • Coagulates blood and fixes tissue to surfaces • Allergic contact dermatitis • Glutaraldehyde vapour monitoring
Ortho-phthalaldehyde (OPA) – 0.55%	• Fast acting high-level disinfectant • No activation or mixing is required • Odour not significant • Excellent materials compatibility claimed • Good mycobactericidal activity • 20 minutes soak time at room temperature for reprocessing	• Stains skin, mucous membranes, clothing, and environmental surfaces • Repeated exposure may result in hypersensitivity in some patients with bladder cancer • More expensive than glutaraldehyde • Eye irritation with contact • Slow sporicidal activity
Per acetic acid (Per oxygen compounds)	• Rapid sterilisation cycle time (30-45 minutes) • Low temperature (50-55°C) liquid immersion sterilisation • Environmental friendly by-products • It is bactericidal, fungicidal, virucidal, sporicidal and tuberculocidal • It is highly corrosive and corrosion inhibitor should be used in the formulation.	• Potential material incompatibility (e.g. aluminium anodized coating becomes dull) • Used for immersible instruments only • Serious eye and skin damage (concentrated solution) with contact • Point-of-use system, no sterile storage
Hydrogen peroxide	• No activation required • Removal of organic matter and organisms • No disposal issues • No odour or irritation issues • Does not coagulate blood or fix tissues to surfaces • Inactivates *Cryptosporidium*	• Material compatibility concerns (brass, zinc, copper, and nickel/silver plating) both cosmetic and functional • Serious eye damage with contact
Superoxide saline	• It is hypochlorous acid derived from salt through electrolysis. It is sporicidal, mycobactericidal until there is no soiling	

Note:

- *CDC Guidelines States:* Laparoscopes, arthroscopes, and other scopes that enter normally sterile tissue should be sterilized before each use; if this is not feasible, they should receive at least high-level disinfection. Objective should be free of microorganisms.

Technique of Achieving Sterilisation/ Disinfection

Cleaning

Cleaning of instruments is the main and important initial method of all disinfection or sterilisation. Cleaning is removal of visible soil - organic/ inorganic by manual or mechanical method using soap/ detergents/ enzymatic solutions; is essential presterilisation/predisinfection procedure.

Cleaning should begin during surgery itself or immediately after finishing the surgery. Instruments should never be allowed to dry; instrument is rinsed with sterile distilled water on the sterile field itself especially channel and lumen bearing instruments. It facilitates removal of blood from joints, hinges and crevices. *Saline should not be used.*

After use, the instruments are placed gently in a basin; heavy instruments at the bottom; delicate and fibreoptic instruments on top or preferably in another container. Coils to be loosely wound. Sharp end instruments should be kept separately so that personnel handling them are not injured.

Cleaning process is done in a methodical way: Pre-cleaning→ Soaking in enzymatic detergent → Washing → Rinsing → Drying.

Precleaning is done immediately after the procedure.

The instrument is wiped with a disposable cloth dampened in an enzymatic detergent solution. Enzymatic detergent solution is aspirated through the suction/biopsy channels with alternate suctioning of fluid and air which prevents drying of organic and inorganic debris on lumen surfaces and assists in the removal of large numbers of micro-organisms and it also dislodges debris from internal lumens. Air/water channels are purged. Removable components are detached. All valves/buttons/caps are removed and soaked in enzymatic detergent solution. Instruments are transported to the cleaning area in a container (without water).

Manual cleaning: It is done using brush and detergent. It is used for fragile instruments, mechanical cleaners are not available. But instruments may get degraded/blunt; it is time consuming and causes friction and fluidics. Nylon brushes of different types and sizes are used. Ports, accessories should be cleaned with brush **(Fig. 18-102)**.

Mechanical cleaning: It is done by - Ultrasonic cleaning, washer decontaminator, washer- sterilizer. **Ultrasonic cleaner is a mechanical cleaning device** highly efficient on surfaces with crevices, locks, serrations but should be used only after the debris is removed. Solution should be changed frequently as endotoxin contamination of solution can occur. It is unsuitable for plastic as ultrasound waves are absorbed by plastic. It may produce infective aerosols. Instruments of dissimilar metals should not be used together and instruments should not be overloaded.

Laparoscopic instruments require both manual and mechanical cleaning **(Figs 18-103A to C)**.

Soaking in Enzymatic Detergent

Enzymatic detergents are good to clean all debris. Single or multienzymes can be used. Formation of foam, pH of the detergents are deciding factors. Thorough washing is essential. Fast-acting enzymatic cleaning agent (ENZOL) which has mild pH and low foaming feature (contains proteolytic enzymes) which can be used in automated equipment: endoscope reprocessors, ultrasonic cleaners, and washer-sterilizers/decontaminators. Minimum 1 minute soak time is sufficient. One-step process reduces the need for mechanical cleaning which may reduce exposure to contaminated equipment. Mild pH reduces likelihood of corrosion of equipment.



Fig. 18-102: Cleaning with brush is very important part in precleaning process.

Water Rinse

Outer surfaces of the instrument and all removable parts are rinsed with water; all channels are flushed thoroughly with water (water jet); clean running water should be used to remove all traces of detergent prior to disinfection and limit cross infection.

Drying

External/outer surfaces of the instrument is dried with a soft, lint-free disposable cloth. All internal channels are purged with air to remove rinsing water. Removing water from all channels and the exterior of the instrument prevents dilution of the biocide used for disinfection. This process can be completed using a syringe or compressed air.

Decontamination

It is removal of all visible soil, tissue, blood and foreign particle causing reduction of bioburden (microbial load and endotoxins); protects instruments against corrosion; allows safe movement of equipment and materials. It results in reduction in pathogenic bacteria from objects so as to make it safe to handle, use or discard. Cleaning reduces bioburden very significantly.

High Level Disinfection (HLD)

Disinfection clears or reduces the number of microorganisms in the instruments but bacterial spores are not completely killed even though it reduces spore numbers. Adequacy of disinfection depends



OPERATING INSTRUCTIONS

- DO NOT OPERATE THE MACHINE WITHOUT FILLING THE TANK COMPLETELY.
- DO NOT RUN THE MACHINE IF THE LIQUID TEMPERATURE HAS GONE ABOVE @ 55°C. AS IT CAN LEAD TO FAILURE.
- DO NOT PUT ANY HEAVY OBJECT ON THE BOTTOM OF THE TANK AS IT CAN DAMAGE THE TRANSDUCERS. ALWAYS USE TRAY SUPPLIED WITH THE MACHINE.
- PLEASE ENSURE THAT LIQUID DOES NOT SPLASH ON CONTROLS & SWITCHES.
- PLEASE ENSURE THAT THE MACHINE IS USED WITHIN 170 V AC TO 250 V AC VOLTAGE RANGE FOR LONG LIFE. OTHERWISE A C.V.T. IS RECOMMANDED. IN AREAS WITH WIDE VOLTAGE VARIATIONS.

Figs 18-103A to C: Ultrasonic cleaning device.

on number of microorganisms in the instrument; bactericidal property of the disinfectant; concentration, pH and temperature at the site; type and design of the instrument (hinges/joints). HLD reduces the bioburden significantly with bactericidal, fungicidal, virucidal and partly sporicidal features.

Disinfectants may be aldehydes; alcohols; per oxide compounds; chlorine dioxide; super-oxidised saline solutions.

Glutaraldehyde

It is noncorrosive aldehyde available as 2.4% alkaline solution. It is bactericidal, fungicidal, virucidal and only slow sporicidal agent. It is used at room temperature. HLD occurs in 45 minutes and sterilisation occurs in 10 hours. It has got 14 days maximum reuse life (Cidex). *Cidex plus* is 3.4% alkaline glutaraldehyde which has got 28 days of maximum reuse life. Entire activator (a rust inhibitor) is added to the solution to make colour of the solution green. Activated solution can be used only for 14 days. Date of activation and date of expiration should be recorded. After cleaning, with detergent, rinsing and drying, instrument is dipped in prepared glutaraldehyde solution; time is 20 minutes for high level disinfection (HLD). Hollow instruments should be dismantled and immersed. Immersion time is 10 hours for sterilisation with container being properly covered to prevent evaporation. Disinfectant should touch and soak all parts of the instrument properly. Instruments should never be placed on the top of the other. After specified time immersed instrument is removed by wearing sterile gloves and rinsed with sterile water for three times and kept in the case table. Water which is boiled for 20 minutes and filtered and cooled can also be used instead of sterile water. Final rinsing can be done using 60-90% ethyl or isopropyl alcohol **(Fig. 18-104).**

Hazards – It can cause on inhalation cough, headache, wheezing and nausea. It can cause skin redness, redness and pain in eyes. Prevention is – proper ventilation, fresh air, wearing gloves and goggles while working on glutaraldehyde. Room should have vapour extraction equipment.

Advantages are – low cost; low temperature; availability.

Disadvantages are – minimum effective concentration (MEC) of 1.5% should be regularly checked and confirmed on the prepared solution each time. Sterilisation process cannot be validated. Moisture sensitive instruments like cameras, power cords and cables cannot be sterilized. Instruments cannot be stored after sterilisation.

Alcohols

Alcohol 70% solution is bactericidal, fungicidal, virucidal and tuberculocidal also. It is fast acting but will not penetrate into organic materials and so is mainly used on clean surfaces. Camera head, cable and plug can be kept in alcohol for sterilisation. Water resistant cap should be covered to the part of the plug which needs to be protected. Ethanol and isopropanol are used.

Problems of Chemical Disinfection

Recontamination of instruments is possible as disinfectants are reusable. Both patients and theater staffs are exposed to adverse effects of the chemicals. Organic matter retained in the instrument may not be properly disinfected as disinfectant itself may get inactivated in such situation. Resistant to organisms; incompatibility of some disinfectant to instruments, corrosive nature; difficulty in determining the concentrations in reused disinfectants are the further problems.

CIDEX
14 Days Solution



CIDEX® - Activ ed Glutaraldehyde Solution

ACTIVE INGREDIENTS: Contains 2 % w/v Glutaraldehyde
CHEMICAL NAME: Pentane - 1, 5-d
INERT INGREDIENT: Purified Water
DISPOSAL: Discard residual solution in drain or as per hospital policy.
CONTAINER DISPOSAL: Do not reuse empty container, rinse with water and
per hospital policy.
⚠ **INSTRUCTIONS FOR USE:**
NOTE: Entire contents of the Activator vial attached to the container must be
Solution and mixed before this product is ready for use. Please refer IFU for
for Use.
NOTE: CIDEX® Activated Glutaraldehyde Solution can be reused for up to a
14 days.
WARNINGS: THIS PRODUCT IS HAZARDOUS TO HUMAN BEINGS AND
ANIMALS.
DANGER: Keep out of reach of children.
CAUTION: Contains Glutaraldehyde. Harmful by inhalation and if swallowed.
respiratory system and skin. Risk of serious damage to eyes. May cause
inhalation and skin contact. In case of contact with eyes, rinse immediately
water and seek medical advice. Wear suitable protective clothing, gloves and
protection. In case of accident or if you feel unwell, seek medical advice
(show the label where possible).
HARMFUL: Use only in well ventilated areas (refer to the material
(MSDS) for additional information). Avoid release to the environment
FOR EXTERNAL USE ONLY

Fig. 18-104: 2.45% glutaraldehyde w/v contains pentane – 1, 5 dial. Glutaraldehyde tray having activated solution.

Disinfection of Endoscopic Instruments

High level disinfection is commonly used in endoscopes/laparoscopes. Immediately after use telescopes, light source, cable, tubes are cleaned and wiped gently using 90% ethyl or isopropyl alcohol soaked cloth. Alcohol kills HIV, HBsAg viruses. All equipments are dismantled completely which are placed in a basin of water with nonabrasive soap. Instruments are washed gently using cotton cloth. Channels of the instruments are cleaned using specified brushes with circular movements to clear all organic materials. All instruments and their parts are rinsed with running water properly. Soap should be cleared completely while rinsing with water; brush may be useful while final rinsing with water to clear the retained soap. Instruments are dried with dry cloth or air dry. While cleaning lenses, it should not be touched with fingers; they are cleaned after removing the plastic covers/eyepieces using acetone or 90% alcohol; lenses should be cleaned weekly even if not in use.

Autoclave and boiling the laparoscopes is not advisable. During autoclave each instrument should be wrapped separately with clothing and kept, otherwise touching of each instrument with one another will cause damage to instruments or their insulation. Chemical sterilisation is the best. ETO, gas plasma sterilisation can also be done. After disinfection rinsing with sterile water or cooled boiled water 3 times is essential otherwise instrument may get stuck due to retained chemical. While handling the instruments sterile gloves should be used not forceps which may damage the laparoscopes. Only one telescope should be held one time; holding in groups should be avoided. *Savlon should not be used* as it will cause clouding and it will not cause HLD.

Storage of Laparoscopic Instruments

Instruments are cleaned; washed; decontaminated; dried and stored in a padded container in a cool dry place. When needed for use, stored instruments should be cleaned, sterilized or disinfected (HLD) then used.

STERILISATION

Steam Sterilisation

It kills by denaturation and coagulation of protein in the cells. Autoclave is steam under pressure. It is done with either 135°C for 5 minutes or 121°C for 15 minutes with 15 pounds pressure. There are flash and vacuum types. All instruments that are insulated, all silicone tubing, all cables and cords should be wrapped in double lined lining (double cloth wrapped).

Advantages - It is economical, fast, age old practice for sterilisation of linen and metallic instruments, very effective, and is well monitored. Nonplastic materials, instruments which will not lose their temper are autoclaved. It is ideal for reusable instruments.

Disadvantages - Sharp instruments may get blunt by autoclaving. Heat and moisture sensitive instruments (glass syringes) cannot be sterilized. Rigid endoscopes can be sterilized by porous loaded autoclaves. Instruments with narrow lumen should be sterilized using porous loaded autoclave. Endoscopes/telescopes sterilized by autoclave should not be cooled rapidly as it may cause stress damage to the instruments. It cannot be used for heat sensitive instruments and wet surfaces **(Fig. 18-105)**.



Fig. 18-105: Autoclave for sterilisation.

Ethylene Oxide Sterilisation (EO/ETO)

It kills by alkylation—Interfering with the metabolism and reproductive process of cells. Sterilisation temperature is 37-55°C; sterilization time 3-5 hrs; aeration time 12-16 hours **(Fig. 18-106)**.

Technique – Initial chamber evacuation, humidification and ethylene oxide charging phase → dwell sterilisation phase → chamber evacuation phase with aeration. It is commonly sterilized at 54.4°C for 3 hours. Heat sensitised instruments are sterilised at much lower temperature of 37.8°C for 5 hours. After sterilization, trapped or absorbed gas is removed by aeration using aeration chamber in the set. Aeration is done by continuous flow of warm air at 50–60°C for 12 hours. Personnel should take utmost care to avoid exposure toxicity.

Advantages – It is low temperature sterilization, can sterilise all kinds of instruments. It does not corrode instruments. It is suitable for all disposable instruments, insulated hand instruments and tubes used for gas, suction and irrigation. Cold or warm ETO is possible. It is material compatible, especially optics.

Disadvantages - It needs aeration and is toxic and carcinogen. Prolonged aeration periods impact instrument availability at right time for surgeries. It is costly. It causes exposure of theatre staff to toxic ethylene oxide gas. Presence of water droplets on the instruments during ethylene oxide sterilisation would form toxic chemical called ethylene glycol. Set is not mobile.

Hazards – Inhalation of ethylene oxide vapour (1000 ppm exposure) can cause pulmonary oedema and respiratory distress; damage to eyes (burns, conjunctivitis, cataract); headache, recurrent vomiting; muscle weakness; neurological manifestations (rare). Direct contact to skin can also cause similar effects by absorption but slowly. It also can cause skin irritations, redness, frostbite like burns (if contaminated shoes or gloves are used), and dermatitis.

Gas Plasma Sterilisation

It is killing of microorganisms using highly active gas ions and free radicals. It uses hydrogen peroxide and plasma which is generated by radiofrequency/ MW (Vapour phase hydrogen peroxide/VHP). It causes generation of free radicals; uses low temperature; by products are safe; aeration is not necessary; short sterilisation cycle even though vary depends on H_2O_2 concentration; good material compatibility; ready to use/store always; requires only an electrical hook up **(Fig. 18-107)**.

Advantages – It is economical; can sterilize all kinds of instruments including the heat and moisture sensitive instruments; it is fast and helps in inventory reduction; it is safe for environment, healthcare workers and patients. It does not require monitoring. It is mobile, simple for installation.

Disadvantages – It cannot sterilize cellulose materials like linen, wood, powders and liquids.


Ethylene Oxide Steriliser
Process Indicators
Mains On
System Ready
Door Closed
Compressed Air Fault
Low Temperature
Heater Control On
Sterilisation On
System Temperature
System Pressure
Aeration Timer
Heater On
Vacuum On
Gas On
Fresh Air On
Aeration On
QC

Fig. 18-106: Ethylene oxide sterilisation device.



Fig. 18-107: Gas plasma sterilisation device.

Chapter 19

Surgery of Oesophagus

SURGICAL ANATOMY

Oesophagus is a hollow muscular tube which begins at the lower edge of the cricoid cartilage (C6 vertebra) and ends at oesophagogastric junction (T12 vertebra). It is 25 cm in length. Upper end is closed by cricopharyngeus muscle which is 18 cm from upper incisors. Lower end is 40 cm from the upper incisors (Upper jaw is fixed and so is used as the landmark to measure, but not the lower jaw which is mobile). It lies anterior to vertebral column and posterior to the trachea. It lacks serosal layer but is surrounded by a layer of loose fibroareolar adventitia.

Anatomical specialities

- Lacks serosa (other structure without serosa is rectum).
- Contains 2 different types of muscles (striated and smooth at proximal 1/3 and distal 2/3, respectively)
- Contains 2 different types of epithelium.
- Segmental blood supply.
- Only part of GIT which shows *very thinly scattered* Meissner's plexus.
- Longitudinal arrangement of veins and lymphatics.

It is lined by non-keratinising stratified squamous epithelium throughout the length except the last 3 cm (OG junction) which is lined by columnar epithelium. Submucosa of the oesophagus is thick and strongest part.

Mucosa → basement membrane → lamina propria → muscularis mucosa (causes wrinkling/folding of mucosa) → submucosa containing mucous secreting glands with thin Meissner's plexus of nerves → two layers of muscles inner thick circular and outer thin longitudinal muscles (in between two layers lies the Auerbach's myenteric nerve plexus) → outermost loose adventitial coverings (no serosa; no mesentery). Endoscopic ultrasound is very useful tool to identify and evaluate different layers of the oesophagus. During anastomosis bites from submucosa and lamina propria should be adequate. Transection of the oesophagus at hiatal level causes retraction of the proximal cut end into the posterior mediastinum due to contraction of the longitudinal layer as it is fixed superiorly.

Muscles are striated in proximal 1/3rd of oesophagus; smooth muscles in distal 1/3rd and mixture of two in middle 1/3rd. This is mainly observed in circular muscle fibres.

Parts

1. ***Cervical oesophagus:*** It extends from cricopharyngeus which is the horizontal part of inferior constrictor muscle. Upper oblique part is called as thyropharyngeus. Gap between the two is called as *Killian's dehiscence* which is a *site of occurrence of pharyngeal pouch.* Cricopharyngeus originates from thyroid and cricoid cartilages. Cervical oesophagus is related to trachea and recurrent laryngeal nerve. It is 6 cm in length extends from C6 to T1. It projects towards left of trachea and so left side is easier to approach oesophagus than right. Its end is 15 cm from upper incisor extends from hypopharynx to level of sternal notch. *Laimer's triangle* is formed with base above by cricopharyngeus and on either side divergent longitudinal oesophageal muscles. Laimer's triangle lies in the posterior part of the oesophagus midline **(Fig. 19-1)**.
2. ***Thoracic oesophagus:*** It lies initially towards the right side. It extends from T1 to T11 vertebrae. It is located in superior and posterior



Fig. 19-1: *Killian's dehiscence* which is a *site of occurrence of pharyngeal pouch. Laimer's triangle* is formed with base above by cricopharyngeus and on either side divergent longitudinal oesophageal muscles. Laimer's triangle lies in the posterior part of the oesophagus midline.

mediastinum. In lower third it deviates towards the left and continues as abdominal oesophagus. It is related to azygos vein, thoracic duct (which crosses the oesophagus posteriorly from right to left), aorta, pleura and pericardium.

3. ***Abdominal oesophagus*** is 2.5 cm long and grooves behind the left lobe of the liver. It lies over T11 and T12 vertebral level. Oesophageal hiatus is at T10 level. Anteriorly it is related to left lobe of the liver, left vagus and oesophageal plexus; posteriorly crura of diaphragm, left inferior phrenic artery and aorta; to the right related to caudate lobe of liver; to the left to fundus of stomach. Abdominal oesophagus is more or less retroperitoneal with peritoneum covering its anterior and towards left only. In the hiatus oesophagus lies on the left/deep pillar of the right crus of the diaphragm. Angle of entry of oesophagus to stomach is called as *angle of His* which is 30° to 70°. Fundus of stomach is that part of the stomach which lies above an imaginary line drawn horizontally through angle of His. Gastro oesophageal junction is called as cardia.

***AJCC has classified oesophagus as cervical; upper thoracic; middle* thoracic; lower thoracic.**

Cervical – same as original anatomical nomenclature.

Upper thoracic oesophagus extends from level of sternal notch (thoracic inlet) to lower border of azygos vein.

Middle thoracic oesophagus extends from lower border of azygos vein to level of inferior pulmonary veins below.

Lower thoracic oesophagus extends from inferior pulmonary veins to stomach. It is older abdominal oesophagus. It includes OG junction.

Three areas of anatomic narrowing

Cervical constriction—occurs at the level of cricopharyngeal sphincter—*narrowest point of GIT*—15 cm from upper incisor—site of F/B impaction.

Bronchoaortic constriction—located at the level of T4 – 25 cm from upper incisor—site of endoscopic perforation. Here left main bronchus (T5) and arch of aorta (T4) crosses it in front. Even though it is considered anatomically as one it has got two components – aortic at T4 and bronchial at T5 level.

Diaphragmatic constriction—occurs where oesophagus traverses the diaphragm (Level of T10)—40 cm from upper incisor.

There are minor constrictions also – retrosternal between cervical and bronchoaortic constrictions; cardiac behind the pericardium; supradiaphragmatic by tortuous aorta.

In the neck it initially deviates towards the left side; then at the level of 5th thoracic vertebra it deviates towards midline; then again it deviates towards left to end as abdominal oesophagus.

Arterial supply of oesophagus

It is segmental and is supplied by inferior thyroid artery, oesophageal branches of the aorta, gastric arteries and inferior phrenic arteries. Cervical part is mainly supplied by inferior thyroid artery and partly by pharyngeal, subclavian, vertebral, common carotid, superior thyroid, and costocervical trunk. Upper part of thoracic oesophagus is supplied by mainly inferior thyroid artery (mainly right side artery) and partly by anterior oesophagotracheal branch. Middle oesophagus is supplied by superior branchial artery and branches directly from aorta. Lower thoracic oesophagus is supplied by single bronchooesophageal artery arising from aorta. Left gastric and left inferior phrenic artery also supplies abdominal oesophagus. These vessels are *small* and form a rich network in submucosa. Communicating branch between inferior phrenic artery and left gastric artery is called as *Belsey's artery* which should be preserved in Belsey Mark IV surgery **(Fig. 19-2)**.


Descending artery
Clavicle
Horizontal artery
Ascending artery
SVC
Azygos vein
Oesophageal venous plexus
Left gastric vein
Portal vein
Splenic vein

Fig. 19-2: Blood supply of the oesophagus.

Venous drainage of oesophagus

It is both longitudinal and segmental by inferior thyroid vein, brachiocephalic vein, and hemiazygos vein, azygos vein, coronary vein, bronchial, posterior intercostal, splenic vein and inferior phrenic vein. Veins are longitudinal and they lie in submucosal plane in lower third and in muscular plane above. Subepithelial longitudinal venous plexus in lamina propria → submucous intrinsic venous plexus → extrinsic venous plexus → larger veins. Venous plexus in lower oesophagus communicates with portal venous system **(Fig. 19-3)**.

Lymphatic drainage

Lymphatic arrangement in oesophagus is longitudinal and so spread of carcinoma to distant lymph nodes occurs early. Longitudinal lymphatics are 6 times more than transverse one. There are *more lymph vessels* in submucosa than blood vessels **(Fig. 19-4)**.


Right brachio-cephalic vein
Left brachio-cephalic vein
1-11 are posterior intercostal veins
Azygos arch
SVC
1
2
3
4
5
6
7
8
9
10
11
Oesophagus
Accessory azygos vein
T8 vertebra
Hemiazygos vein
Azygos vein
IVC
Right subcostal vein
Left subcostal vein
Lumbar azygos vein
Right ascending lumbar vein
Left ascending lumbar vein
Right renal vein
Left renal vein

Fig. 19-3: Venous drainage of oesophagus.


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
1. Cervical group
2. Lateral cervical group
3. Deep cervical group
4. Upper thoracic group
5. Paratracheal group
6. Subcarinal group
7. Hilar group
8. Middle thoracic group
9. Lower thoracic group
10. Posterior mediastinal (para-aortic) group
11. Diaphragmatic group
12. Paracardial group
13. Lesser curvature group
14. Coeliac left gastric group
15. Common hepatic group
16. Greater curvature group
17. Suprapyloric group

Fig. 19-4: Lymph nodes draining the oesophagus.

Lymph nodes are:

Paraoesophageal groups located in the wall of the oesophagus and are cervical, thoracic, paraoesophageal and paracardial nodes.

Perioesophageal groups located immediately adjacent to oesophageal wall. They are deep cervical, scalene, paratracheal, mediastinal, diaphragmatic, gastric and coeliac lymph nodes.

Lateral oesophageal groups receive lymph from para- and perioesophageal lymph nodes.

Upper oesophagus drains into supraclavicular nodes. Thoracic oesophagus drains into paraoesophageal and tracheobronchial nodes in thorax. Abdominal oesophagus drains into coeliac nodes.

However due to longitudinal arrangement of lymphatic plexus in the wall of oesophagus, any group of (neck/thorax/coeliac) lymph nodes can get involved in diseases at any level. In T1a only mucosa is involved by carcinoma and so metastasis is rare. In T1b submucosa is involved by tumour and so nodal metastases is up to 30-50%. AJCC has adapted different lymph node stations for oesophageal carcinoma (1-19).

Anatomical Relations of Oesophagus

Oesophagus begins at lower edge of cricoid cartilage at C6 vertebral level and ends at oesophagogastric junction at T11 vertebral level. OG junction is at the level of 7th intercostal space anteriorly. Above it lies the cricopharyngeal sphincter which is 18 cm from upper incisor. Lower oesophageal sphincter is 40 cm from upper incisor.

Relation in the neck

Oesophagus along with trachea is covered with pretracheal fascia which also encloses the thyroid gland. So anterior relations are larynx and trachea. Posteriorly buccopharyngeal fascia separates it from prevertebral space and this fascia extends laterally as carotid sheath. Recurrent laryngeal nerve lies in tracheooesophageal groove. Left RLN is closer to oesophagus than right. Thoracic duct is towards left of the oesophagus and its upper end is 4 cm above clavicle. Laterally relation from lateral to medial are – carotid sheath, inferior thyroid artery, lateral lobe of thyroid gland, recurrent laryngeal nerve **(Fig. 19-5)**.

Retropharyngeal space continues below towards posterior mediastinum and so infection can cause mediastinitis. Cervical oesophagus is closely related to trachea through *tracheal pars membranacea* and so during transhiatal dissection injury to this membranacea can cause tracheal perforation. Oesophageal perforation within the pretracheal fascia may extend into mediastinum causing mediastinitis.

Relation in the thorax

Thoracic oesophagus is related in front from above downwards are: trachea; aortic arch; right pulmonary artery; left main bronchus; pericardium and left atrium; anterior vagus; oesophageal hiatus. Posterior relations are: vertebral column; longus coli muscles; right posterior intercostal arteries; thoracic duct (crosses it from behind); right pleura; azygos, hemiazygos and accessory azygos vein; aorta; posterior vagus. Laterally – on right side are: mediastinal pleura, azygos vein, right main bronchus, root of right lung, right vagus nerve; on left side are: aortic arch, left subclavian artery, left recurrent laryngeal nerve, thoracic duct from T4 to C7, pleura, descending thoracic aorta. Arch of azygos vein (azygos arch) crosses the right main bronchus.

In thorax oesophagus descends posterior and medial to the aortic and azygos arches and left main bronchus. Right and left mediastinal pleura are on both sides. Left recurrent laryngeal nerve is lateral and


Oesophagus
Trachea
Thoracic duct
Right pulmonary artery
Right bronchus
Aorta
Left pulmonary artery
Left bronchus
Pulmonary trunk
Heart border
Diaphragm
Crus
Stomach

Fig. 19-5: Oesophageal relations in thorax.

thoracic duct is posteromedial. At the carinal level, oesophagus is separated from tracheal carina by subcarnial nodes, and thoracic duct crosses it from behind. Below oesophagus is behind the fibrous pericardium and right of the descending aorta. Both vagi run longitudinally on the surface of the oesophagus in front and behind (left anterior; right posterior).

Phrenooesophageal ligament or membrane is condensation of pleura, endothoracic fascia, phrenooesophageal fascia of Lamier, transversalis fascia and peritoneum into two sheaths; upper one is attached to the outer muscular layer of oesophagus; lower one into cardia extending into gastric serosa and gastrohepatic and gastrosplenic ligaments. Pleura and peritoneum maintains airtightness; other components provide strength and flexibility. Membrane is well developed in front than behind. Superficial layer is peritoneum; deeper layer is thick fibrous tissue. It provides barrier between oesophagus and thorax. When the peritoneum in front of the hiatus is stretched with downward traction, the ligament becomes obvious as a white line; division of it allows access to mediastinum **(Fig. 19-6)**.


Phrenooesophageal ligament
Pleura
Crus of diaphragm
Transversalis endoabdominal fascia
Peritoneum
Oesophageal muscular layer

Fig. 19-6: Phrenooesophageal membrane.

Gastrohepatic ligament is the peritoneal reflections on the right side enclosing the oesophagus. It contains left gastric artery and vein, left vagus with branches and lymph nodes. Occasionally it can contain branches of right gastric artery, left hepatic artery when it is arising from left gastric artery (20%).

Gastrosplenic/gastrolienal ligament is formed by peritoneal reflections on the left side **(Fig. 19-7)**.

Relations in abdomen

Right crus of diaphragm arises from the first 3-4 lumbar vertebrae running upwards and divides into superficial and deep slings to enclose the oesophagus. Superficial right pillar of the right crus gets attached to central tendon of the diaphragm; deeper left pillar encircles the oesophagus and joins the right pillar. Left crus arises left of the upper 2-3 lumbar vertebrae, runs vertically upwards to the diaphragm without any divisions. Left crus runs left of the aorta and is actually not in direct relation to the oesophagus even though variations are common. Right crus is longer than left. Right is supplied by right phrenic nerve and left is supplied by left phrenic nerve. Median arcuate ligament is tough 2 mm wide condensed medial fibrous margins of the both right and left crura of the diaphragm. It is just proximal to the origin of coeliac artery encircling the descending aorta; but origin of coeliac artery may vary in 30% of individuals either at or above the median arcuate ligament **(Fig. 19-8)**.

Angle of His is angle between fundus of the stomach and oesophagus. Tendinous tissue binds between right and left crus


Left CCA
Left IJV
C7
Left subclavian vein
Valve
Thoracic duct
Oesophagus
T5
T6
T7
Accessory hemiazygos vein-T8
Azygos vein
Hemiazygos vein–T8—T9
Descending thoracic aorta
Crus of the diaphragm
L1
L2
Cisterna chyli
Left lumbar lymph trunk
Intestinal lymph trunk
Right lumbar lymph trunk
Para-aortic nodes
Pre-aortic nodes
Abdominal aorta
IVC

Fig. 19-7: Relations of the oesophagus.


Right crus
Superficial pillar
Deep pillar
Oesophagus
Median arcuate ligament
Left crus
Coeliac trunk
Medial arcuate ligament
Superior mesenteric artery
Psoas major muscle
Aorta

Fig. 19-8: Oesophageal hiatus — anatomy.

inferior and posterior to oesophagus to form median arcuate ligament. This tissue is important in hiatus hernia repair while placing anchoring sutures. Both pillars of the right crura have got muscular and tendinous parts. Tendinous part is more posterior than muscular part which is in front. It is important to take bites deep enough to include tendinous parts in anchorage stitches. Tendinous parts, which are posterior, are better visible through thoracotomy incision.

Antireflux mechanism is both anatomical and physiological. LOS mechanism at terminal oesophagus as a high pressure zone is physiological. Anatomical are – thickening of gastric oblique fibres; Rosette like gastric mucosal folds; angle of His; phrenooesophageal membrane and pinching action of crura.

Principles in Oesophageal Surgery

Upper half of the thoracic oesophagus is approached through right thoracotomy as aortic arch is present on left side. Lower half can be approached by right or left thoracotomy incision. Azygos vein should be double *ligated at arching of the oesophagus to reach* superior vena cava. Azygos vein enters the SVC on its posterior surface. Injury to SVC should be avoided and SVC cannot be ligated.

Left side *oesophageal triangle* (only on left side) is present on the left upper mediastinum which is formed by descending aorta, left subclavian artery and vertebral column. Floor of the triangle is mediastinal pleura under which part of oesophagus is located.

Triangle of Truesdale is formed by diaphragm below, pericardium above and in front, descending thoracic aorta behind **(Fig. 19-9)**.

Two pleura both right and left approximates behind (posterior approximation) oesophagus and aorta as mesooesophagus in the lower part of the thorax. Anterior approximation of both pleura occurs at sternal angle level.

Right pleura is very closely related to lower oesophagus up to the oesophageal hiatus. During hiatal dissection, right pleura may get torn to cause pneumothorax **(Fig. 19-10)**.

Mobilisation of distal oesophagus – Adequate exposure of the OG junction (cardia) is done. Stomach is retracted downwards and towards left using hand. Usually clean mop is used under the fingers to achieve proper grip and prevent injury to stomach. Assistant retracts the stomach. Left triangular ligament is cut by folding the left of the liver which is retracted towards right and down. Peritoneum over the phrenooesophageal ligament is held using long nontoothed dissecting forceps; using long curved scissor peritoneum and phrenooesophageal ligament is cut horizontally across the full length of the anterior aspect of the oesophagus. Ligament with peritoneum is reflected upwards to expose the cardia. Cautery can be used for dissection but should avoid injuring the bowel wall. Anterior vagus can be felt by running the index finger horizontally on the lower oesophagus with maintaining the traction on the stomach. Often anterior vagus lies very closely to oesophageal wall or often embedded in the wall. Anterior vagus is dissected along the length of the lower oesophagus. Right index finger is passed behind the oesophagus gently and loose areolar tissue is separated with blunt finger dissection to reach right of the oesophagus to create a window. A scissor cut may be needed while entering the right index finger towards right from left from behind. Posterior right vagus is little away from the oesophageal tube and usually will not come into the hooked index finger. To feel the posterior vagus index finger should be rolled with traction on the stomach. Usually posterior vagus which is thicker is dissected using finger. Often perioesophageal scarring may be present behind due to hiatal disease like reflux. In such situation sharp scissor dissection under vision is better to avoid tear in the muscle or mucosa of the oesophagus. Mobilisation further can be obtained by cutting the hiatus either anteriorly or posteriorly (*median phrenicotomy*). Care should be taken not to injure the pericardium and anterior branch of inferior phrenic vein which crosses the hiatus in front to reach IVC or hepatic vein. This vein should be ligated during phrenicotomy. But most of the time it is not necessary. Distal end of the cardia is mobilised downwards but it is limited by *gastric trinity – left gastric artery and vein (coronary vein) and coeliac branch of the posterior vagus nerve*. Dissection is done from lesser curve side of the stomach. Lesser omentum over the proximal 3 cm of lesser curve (3 cm distal to OG junction) is incised; left index finger is passed directing towards the angle of His (cardia notch) obliquely with blunt gentle careful finger dissection. Oesophageal hiatus is located at left of the midline at T10 vertebral level. Hiatus is formed by pillars of the right crus and left crus. It is obliquely placed opening 1 cm behind the central tendon of the diaphragm. Oesophageal hiatus is separated from aorta by median arcuate ligament **(Fig. 19-11)**.



Fig. 19-9: Left side mediastinum – surgical anatomy.



Fig. 19-10: Accessory left hepatic artery when present should be preserved. It is arising from the left gastric artery.

Adequate exposure is important in oesophageal surgery. Proper retraction, adequate exposure and lighting, slow careful meticulous anatomical dissection is ideal. Both sharp and finger dissections are



Fig. 19-11: Hiatal dissection in oesophageal surgeries.

used. Bipolar cautery or harmonic scalpel are ideal energy sources in oesophageal surgery.

Anastomosis is done using 2 or 3 zero silk interrupted sutures. Two layers are commonly used. Taking bites from mucosa is very important. Traction tear or ischaemia due to holding on the wall of the oesophagus should be avoided. Gentle firm holding is important. Often horizontal mattress (box) may be used to prevent tear at suture bite. Inner layer often sutured with 2 zero vicryl; outer layer with 2 zero silk; both should be interrupted. Adequate vascularity should be maintained at the anastomotic site. Oesophageal end anastomosis should be always as **end to side, to the side** (anterior wall) of the stomach. *End to end oesophagogastric anastomosis is not preferred* as – disparity between lumens of oesophagus and stomach; technical difficulty in performing end to end anastomosis; lesser blood supply near the proximal cut open end of the gastric pouch; there is no protection from posterior leak from the anastomotic site; postoperative reflux is more. In end to side anastomosis, better blood supply is maintained in the stoma; buttressing effect of the stomach pouch behind prevents posterior leak; technically easier; lesser chance of postoperative reflux and hence it is preferred. Even stapler anastomosis (28 mm/31 mm) should be ideally end to side of the stomach. One should avoid using unnecessary clamp on the oesophageal side; if at all gentle soft occlusion clamp can be used to avoid crushing effect and compromise the viability. *No tension and accurate apposition are essential basis in oesophageal anastomosis.* Knots of inner layer should be inside to prevent the mucosal hernia and to achieve the mucosal inversion which prevents leak. Omental wrap around the anastomosis should be placed. Before starting the anterior inner layer (3rd layer) nasogastric tube should be positioned or ideally at least before placing final stitch of inner anterior layer. But many prefer to negotiate the tube after completion of the anastomosis in view of avoiding the contamination. Anterior cut edge of oesophagus should be 1 cm lengthier than posterior edge.

Kocherisation for duodenal mobilisation; mobilisation of stomach; retaining right gastroepiploic vessels (mainly) and right gastric artery; ligating left gastric and left gastroepiploic arteries; adequate widening of the hiatus (to prevent venous congestion of pulled up stomach/colon); absolute haemostasis are main technical needs in oesophageal surgeries.

Spillage of the gastric contents should be avoided to prevent sepsis as in oesophagectomy stomach is pulled upwards into the thorax; sepsis in thorax is really risky.

Three field lymhadenectomy is often added with clearing the abdominal, thoracic and neck lymph nodes (bilateral). Here anastomosis is done in the neck. McKeown approach may be suitable here.

Feeding jejunostomy is commonly used in oesophageal resection surgeries. Few advocate passage of nasogastric tube across the stoma and fix it to the nostril securely. It acts as a stent across the stoma; keeps the stoma patent; allows nasogastric feeding also even though there is no clear cut evidence for this.

Blood should be kept ready in case there is bleeding during thoracic dissection. Intraarterial catheter is required. CVP line is better to keep always.

SURGICAL TREATMENT FOR ACHALASIA CARDIA

Heller's cardiomyotomy is done for achalasia cardia. Extended myotomy is done when there is diffuse oesophageal spasm.

In 14th April 1013 Ernest Heller, a German surgeon did first cardiomyotomy based on Gottstein's idea through abdominal approach. He did myotomies at both anterior and posterior walls. It is an extramucosal oesophagomyotomy. Later many modifications were tried on this procedure. Original Heller's myotomy was double myotomies. In 1918 Groeneveldt from Holland modified it as only anterior myotomy which was popularised by Zaaiijer (1923). Myotomy facilitates gravity induced swallowing. Incidence of reflux and oesophagitis is very high (20%) and so partial or often total Nissen's fundoplication is added to prevent reflux. Pressure of the lower oesophageal sphincter (LES) is completely reduced but not eliminated by myotomy. Relief of dysphagia occurs *immediately after* recover from anaesthesia.

Vigorous achalasia and with severe suspected metaplasia confirmed by endoscopic biopsy needs resection of the lower oesophagus and oesophagogastric anastomosis. In megaoesophagus/sigmoid oesophagus results of myotomy is not good. Hence resection is better option **(Fig. 19-12)**.



Fig. 19-12: Achalasia cardia – diagram; endoscopic view; barium study view.

Preparation

Contrast oesophageal study, oesophagoscopy oesophageal manometry should be done. Manometry shows absence of peristalsis in lower oesophagus with incomplete relaxation of LES. Contrast CT scan is better option to see extent and dilatation. Chest X-ray to see the lungs for pneumonia, double mediastinal strip of oesophagus is also important. Barium swallow shows bird beak appearance. Fluoroscopy may be useful to see elongation, sigmoid oesophagus. Endoscopy shows dilated proximal oesophagus, closed puckered LES which will not open freely. Biopsy should be done to check mucosal changes and malignant transformation (adenocarcinoma).

Oesophagus is lavaged with normal saline on previous day and same day morning to prevent aspiration during induction of anaesthesia. Preoperative antibiotic is not necessary.

Nasogastric tube into the oesophagus is helpful especially while dissecting the lower oesophagus.

Approaches

Laparoscopy is an excellent approach for modified Heller's cardiomyotomy. *Toupet's posterior partial fundoplication* is added usually. It has become standard now. It is not useful in diffuse oesophageal spasm, vigorous achalasia and failure/recurrence.

Open thoracotomy through left sided thoracotomy approach is also better as it avoids laparotomy, retains integrity of the phrenooesophageal ligament thereby reducing the chances of reflux. Lengthy myotomy for diffuse oesophageal spasm is possible by thoracotomy approach. Disadvantages are morbidities of thoracotomy; if unidentified mucosal leak occurs it will cause empyema which is dangerous and needs drainage. Belsey Mark IV antireflux procedure can be done safely through this approach if needed. Thoracotomy is better in obese patients or in patients where adhesions at hiatus are anticipated through abdominal approach or failed abdominal myotomy. *Thoracoscopic approach* even though is practiced is not readily accepted.

Laparotomy – open abdominal approach (described by Ellis et al in 1958) – Heller's original approach was also abdominal. It is technically easier; general surgeons are more comfortable with laparotomy approach. But reflux is more common through this approach. Toupet's partial posterior fundoplication is done in this approach. Nissen's total fundoplication is also done but it may cause dysphagia and gas bloating syndrome and is obstructive wrap which is not ideal in myotomy. Anterior partial fundoplication is also useful and is nonobstructive wrap. Respiratory complications are less here. Transabdominal is preferred in patients with compromised cardiopulmonary function and in patients who need additional abdominal procedure and in patients who have already undergone prior thoracotomy.

Thoracoscopic approach is similar to thoracotomy technique. It has not become very popular due to technical difficulties in reaching and dissecting the hiatus. Right lateral decubitus with left thorax up is the position as per left thoracotomy. 1st port is in 3rd intercostal space 2 cm anterior to the posterior axillary line. 2nd 10 mm port is in 7th intercostal space 4 cm behind the posterior axillary line used for telescope; 3rd port is in 6th intercostal space in anterior axillary line; 4th port is in 7th intercostal space in midaxillary line; 5th port is 8th intercostal space in anterior axillary line. Inferior pulmonary ligament is cut; left lung is retracted. Oesophagus is identified in the groove between aorta and pericardium. Mediastinal pleura is incised; anterior vagus is dissected and kept aside; myotomy is done by cutting both longitudinal and circular muscle layers for 8 cm proximally. Distal myotomy across OG junction onto the stomach wall for 1 cm is done. This is the most difficult part of the procedure in thoracoscopy approach. Reflux is common in this approach as fundoplication is not possible. Belsey Mark IV procedure can be done to prevent reflux; but it is technically difficult. *Right sided thoracoscopic approach* is also used for myotomy in case laparoscopy is not possible or failure of previous laparoscopy.

Technique Through Thoracotomy

Procedure is done under general anaesthesia. Double lumen endotracheal tube may be beneficial. Position of the patient is for full left thoracotomy. After cleaning and draping, skin incision is made along left 7th intercostal space just above the 8th rib. Latissimus dorsi and serratus anterior are divided. Monopolar cautery is used. Pleura is opened after cutting the intercostal muscles. *Finochietto retractor* is placed and widened adequately. Occasionally rib resection may be needed if approach is inadequate. Inferior pulmonary ligament is divided. Left lung is retracted upwards. Mediastinal pleura overlying the lower oesophagus is incised longitudinally. Oesophagus gently dissected using finger at its lower part and is encircled using Penrose or latex drain or infant feeding tube. Presence of nasogastric tube facilitates the dissection. Vagi are identified and safeguarded.

Index finger is placed under the lower oesophagus. Narrow segment and dilated proximal part can be easily seen and felt. Longitudinal incision is made over left anterolateral aspect of the oesophageal wall away and anterior to left vagus using number 15 blade gently and carefully. Cranially incision is slowly extended for 7-8 cm until myotomy is extended into dilated segment also. Myotomy above should be extended into 2 cm over the proximal dilated segment. Distal extent of incision up to oesophagogastric junction may be maximum 10 mm over the stomach. But it is sufficient to make incision around 3 mm downwards over stomach. Lengthier incision over stomach should be avoided. Stomach wall is identified by presence of transverse small veins traversing it over the mucosa deep to muscular layer. Outlook of gastric muscle differs from oesophageal musculature. Edge of the cut musculature is held using dissecting forceps and using fine scissor it is raised from the deeper mucosal plane for half the circumference. It prevents from muscle reuniting again leading into stenosis. Raising of the muscle is done on both edges. Bulging of the mucosa onto the myotomy gap is clearly evident **(Fig. 19-13)**.

Anaesthetist is asked to infuse 200 ml of methylene blue into the oesophagus from above to see any leak from the mucosa. On table oesophagoscopy (flexible) is also often done. Saline infusion from above also can be done. If there is a leak mucosa is sutured using 3 or 4 zero silk or vicryl interrupted sutures.


Diaphragm
Mediastinal pleura opened
Oesophagus
Lung
Anterior vagus
Hiatus-look from thoracic side
Cardiomyotomy incision exposing mucosa
Muscle layer is separated to expose the mucosa widely. Care should be taken not to perforate
Vagus retracted towards left
After completion of adequate cardiomyotomy mediastinal pleura is sutured

Fig. 19-13: Cardiomyotomy through thoracotomy (left) approach.

Extended myotomy is done in diffuse oesophageal spasm. Extension is done proximally above adequately until entire spasmodic segment is released.

Intercostal tube (30 French no.) is placed. Lung is inflated. Thoracotomy wound is closed in layers.

Postoperative Care

Intravenous fluids and nasogastric aspiration is done. Nasogastric tube can be removed in 24-48 hours. Oral liquids started in 48 hours. Chest tube is removed in 4 days once drain reduces to minimum and chest X-ray confirms lung expansion.

Postoperative endoscopy and manometry may be done if needed to confirm the efficacy of the procedure.

Complications and Problems

Respiratory infection, empyema if there is leak postoperatively.

Recurrent dysphagia after initial symptomatic response or persistent dysphagia can occur. An *incomplete myotomy* that does not adequately lower the LES pressure will cause persistent or recurrent dysphagia. Here dilatation can be tried. Otherwise laparoscopic myotomy is done. Alternatively resection of lower oesophagus with oesophagogastric anastomosis is done.

Reflux oesophagitis is one of the complications even though it is less common and less severe in thoracotomy approach compared to abdominal approach. Antireflux procedure is needed. Few undertake modified Belsey Mark IV procedure while doing initial myotomy through thoracotomy approach itself. A nonobstructive wrap is always better.

Oesophageal perforation can occur but incidence is less.

Diaphragmatic hernia is another complication which can occur.

Technique Through Abdominal Approach

Incision – Upper midline incision extending down beside the left side of the umbilicus. Xiphoid process may require to be excised. Patient is in head up (reverse Trendelenburg) position.

A self-retaining retractor is placed. Sternal self-retaining chain retractor is better if available. Left lobe is mobilised by placing surgeon's left hand over the left lobe retracting it below and towards right. Left triangular ligament is divided using cautery and scissor. Thus left lobe is mobilised and retraced by folding it inwards to expose hiatus fairly adequately. Wet mop should be placed under the retractor to avoid injury to left lobe of liver during retraction. Stomach is displaced below by downward traction by first assistant using fingers or Babcocks. Peritoneal reflection over the OG junction is lifted using long dissecting forceps and using long curved scissor it is cut horizontally to push it upwards towards hiatus. Anterior left vagus should be safeguarded, gently dissected and kept aside using smooth sling. Entire abdominal oesophagus is mobilised using right index finger with blunt dissection. Dissection facilitates separation of the abdominal oesophagus from behind away from aorta. Mobilised lower oesophagus is hooked with right index finger and long gauze or tape or infant feeding tube or Penrose drain is passed around. Phrenooesophageal membrane is divided to allow the dissection into the peritoneum. Right pleura may get injured while dividing this membrane/ligament and so care should be taken to avoid it. Oesophagus is dissected by blunt and sharp dissection further upwards across the hiatus.

Oesophagus is held under tension by giving traction on the sling. Constriction part can be felt with this method. Using left index finger lower oesophagus is encircled; longitudinal incision is made on the anterior left lateral aspect of the oesophagus over the muscle; both longitudinal and circular muscles are cut; mucosa can be visualised. Both muscles are cut even though only circular muscle is hypertrophied and thickened due to the disease. Care should be taken not to injure it. Using right angles Mixter forceps dissection between mucosa and muscular layers is carried out upwards creating separation; separated muscle is cut using curved scissor; bipolar cautery can be used for small bleeder with care to avoid injury to mucosa. Energy sources like harmonic may be useful. Such *separation/adequate lifting/cutting of the muscle* are done sequentially with each time around 1 cm only. One should not take longer segment in a hurry as it will cause injury to mucosa by lifting of the mucosa. Cranially myotomy is done 8-10 cm. Often a metal clip is placed at this point for future identification of uppermost point of myotomy. Upper myotomy should go to the proximal 2 cm dilated segment of oesophagus. Myotomy is also done downwards over the stomach wall for less than 1 cm. It should never exceed more than 1 cm. Small veins traverse horizontally in submucosa of the stomach which are the identification markers of stomach wall. Edge of the cut musculature is held using dissecting forceps and using fine scissor it is raised from the deeper mucosal plane for half the circumference. It prevents from muscle reuniting again leading to stenosis. Raising of the muscle is done on both edges. Metal clip is also placed over the lowermost cut edge for identification. 200 ml methylene blue instillation is done to check for perforation **(Fig. 19-14)**.

It is usual to add on to Toupet's partial fundoplication along with closure of the oesophageal hiatus. Crural pillars/crura of the diaphragm behind are identified and approximated using interrupted 3-4 2 zero silk or polypropylene sutures. It should be only adequate apposition; should not be too tight; should able to pass finger through it. Gastric fundus is mobilised by dividing few gastric veins along the fundus. Cut muscle edges of the myotomy are sutured to the mobilised stomach which has wrapped from behind to complete the posterior partial fundoplication. Interrupted 3 zero polypropylene or silk sutures are used. Wound is closed without drain usually. Drain is kept if there is perforation or more bleeding **(Fig. 19-15)**.

Modifications

Often *anterior partial fundoplication* (*Dor's*) is also done instead of posterior fundoplication. In anterior fundoplication, after fundal mobilisation, it is placed back in normal position. Left sided cut edge of the myotomy is sutured to the medial aspect of the fundus from below upwards for about 4 cm as 3 zero silk or polypropylene continuous seromuscular suture; last bite is taken from the left crus of the diaphragm fixing it to the hiatus. Gastric fundus flap is rotated in front towards right medially on to the right cut edge of the myotomy **(Fig. 19-16)**.

After taking the bite from the right cut edge of the myotomy wound seromuscular bites are taken from the anterior stomach wall close to greater curvature from below upwards. Again upper most suture is taken from the right crus of the diaphragm. This keeps the cut edges of the muscle in separation preventing reunion and stenosis and it also protects exposed mucosa by covering it. But incidence of reflux is more with Dor's anterior wrap than Toupet's posterior wrap. So Toupet's posterior fundoplication is preferred commonly **(Fig. 19-17)**.


Left triangular ligament is cut
Left lobe liver is retracted with assistant's hand towards right and below
Stomach
A
Diaphragm
Oesophageal hiatus
Peritoneal reflection
Oesophagus
Left lobe of liver is retracted with Deaver's retractor
Incision over the peritoneum horizontally at OG junction to reflect the peritoneum above upto hiatus
Stomach is held and retracted downwards using 2 Babcocks or fingers with traction
B
Diaphragm
Oesophageal hiatus
Mobilised oesophagus
Left lobe liver is retracted with Deaver's retractor
Right index finger hooking the mobilised oesophagus
Anterior left vagus dissected and safeguarded
C
Diaphragm
Oesophageal hiatus
Mobilised oesophagus
Left lobe liver is retracted with Deaver's retractor
Right index finger hooking the mobilised oesophagus
Anterior left vagus dissected and safeguarded
D
Diaphragm
Oesophageal hiatus
Mobilised oesophagus
Retracted anterior vagus
Left index finger hooking the mobilised oesophagus
Sling around the OG junction to give traction downwards
E
Diaphragm
Oesophageal hiatus
Mobilised oesophagus
Using 15 no. blade longitudinal and circular muscle layers are incised
Left lobe of liver is retracted with Deaver's retractor
Retracted anterior vagus
Left index finger hooking the mobilised oesophagus
Sling around the OG junction to give traction downwards
F

Figs 19-14A to F


Diaphragm
Oesophageal hiatus
Mobilised oesophagus
Bulged oesophageal mucosa - care should be taken not to injure it
Retracted anterior vagus
Left index finger hooking the mobilised oesophagus
Sling around the OG junction to give traction downwards
G
Diaphragm
Oesophageal hiatus
Mobilised oesophagus
Bulged oesophageal mucosa - care should be taken not to injure it
Retracted anterior vagus
Sling around the OG junction to give traction downwards
H
Oesophageal hiatus
Mobilised oesophagus
Exposed mucosa of oesophagus for 8 cm
Anterior vagus
Forceps holding the edges of the cut muscles (Myotomy)
I
Oesophageal hiatus
Mobilised oesophagus
Exposed mucosa of oesophagus for 8 cm
8 cm
8 mm
Sling around OG junction
Anterior vagus
Forceps holding the edges of the cut muscles (Myotomy)
J
Oesophageal hiatus
Dissected edges of myotomy
Mobilised oesophagus
Exposed mucosa of oesophagus for 8 cm
8 cm
8 mm
Sling around OG junction
Stomach
Anterior vagus
Forceps holding the edges of the cut muscles (Myotomy)
K

Using right angled forceps (clamp) plane is created between muscle and mucosa gently.
- One should avoid tenting of mucosa.
- Slow, gentle sequential upward cutting of the muscle is done.
- Mucosa should not be cut.
- Only bipolar cautery or fine suture ligation is used

- Myotomy extended over stomach wall only for 3-8 mm (<10 mm).
- Small veins in submucosa are specific.

Muscle layer is separated from mucosa outward for ½ the circumference of the oesophagus carefully

Figs 19-14G to K

Figs 19-14A to K: Achalasia cardia – Modified Heller’s cardiomyotomy open method through abdominal approach.


A
Myotomy left cut edge
Fundus of stomach
Penrose sling/umbilical tape/infant feeding tube
220 degree partial wrap is modified Toupet's
B
Muscular layer cut
Mucosal bulge
C

Figs 19-15A to C: Heller's cardiomyotomy.


I row
II row
First row behind
Second row front, also to right crus

Fig. 19-16: Dor's anterior fundoplication.


Oesophageal hiatus
Exposed mucosa of oesophagus for 8 cm
Mobilisation of gastric fundus by ligating few short gastric vessels
8 cm
8 mm
Fundus
Spleen
Anterior vagus
Stomach
A
Oesophageal hiatus
Exposed mucosa of oesophagus for 8 cm
Inner / medial part of the fundus is sutured to left cut muscular edge of the myotomy as continuous seromuscular suture with last bite(s) should be taken from left crus of diaphragm
8 cm
8 mm
B
Oesophageal hiatus
Exposed mucosa of oesophagus for 8 cm
Right cut edge of the myotomy is sutured to the greater curvature (outer) part of the fundus using continuous seromuscular suture with uppermost bite is taken from right crus of diaphragm
C
Oesophageal hiatus
Completed anterior nonobstructive fundus wrap
D

Figs 19-17A to D: Anterior fundoplication (Dor's) for achalasia cardia.

Often initial myotomy is guided by passing a *balloon* which is inflated across. Anterior gastrotomy is done. Foley's catheter is inserted into the stomach and gently negotiated across the stenotic segment. Balloon is inflated slowly to stretch the muscle fibres which can be cut easily and mucosa can be identified easily. Later Foley's catheter is removed and gastrotomy is closed. Specialized balloon for the purpose is also can be used similarly **(Fig. 19-18)**.

Postoperative care

Nasogastric tube is removed in 24 hours. If there was perforation it is kept for 5 days. Drain if kept when indicated is removed in 5 days. Oral fluids started in 24 hours; later gradually semisolid and solid diet. Patient needs postoperative follow up with gastroscopy and manometry study in few months to confirm the adequacy of the cardiomyotomy.

Results and complications

Results of myotomy are very good. It is 90%.

Mucosal perforation, mediastinitis are rare complications. If there is mucosal perforation it is closed using interrupted sutures.

Rarely splenic injury may occur. Pleural effusion, pneumothorax or empyema are rare known complications.

Dysphagia and gas bloating syndrome is the problem, but it is less in partial fundoplication.

Laparoscopic Cardiomyotomy

Shimi and colleague (UK) in 1991 did first Heller's cardiomyotomy laparoscopically. Cuschieri described proper technique of laparoscopic cardiomyotomy.

Procedure is done under general anaesthesia. Nasogastric tube should be placed prior to surgery. Often orogastric tube is passed until procedure is over. Patient is in supine position with abducted and flexed legs with head up position 40° (reverse Trendelenburg). Surgeon stands in between legs. Camera surgeon on the right side of the patient;


Oesophageal hiatus
Abdominal mobilised oesophagus
Inflated balloon at the narrow segment
Anterior vagus retracted
Gastrotomy incision
Balloon catheter/ tube (Foley's) is passed
A
Myotomy done over inflated balloon
Exposed mucosa
Anterior vagus retracted
Gastrotomy incision
Balloon catheter/ tube (Foley's) is passed
B
Oesophageal hiatus
Myotomy muscular cut edges
Exposed oesophageal mucosa
Anterior vagus
Gastrotomy closed
C

Figs 19-18A to C: Cardiomyotomy balloon is often used.

assisting surgeon on the right side proximally; scrub nurse on the right side distally left of the left leg of the patient. Manometry and endoscopy needed should be kept in place to assess the completion and pressure before and after myotomy.

Supraumbilical incision in the epigastrium is made at 5 cm above the umbilicus (15 cm below the xiphoid). This 10 mm port site is used for 30° telescope with camera. Peritoneal access is done either by open method or by Veress needle. 10 mm trocar is passed. Other trocars at 5 mm left anterior axillary; 5 mm just below the xiphoid; 5 mm left midclavicular; 10 mm left midclavicular.

Left lobe of the liver is retracted through 5 mm subxiphoid port. Stomach is held with bowel holding forceps and retracted downwards and outwards by assistant through left anterior axillary 5 mm port. Gastrohepatic ligament is divided. After identifying right crus, behind the oesophagus dissection is done to create a window. Deep pillar of right crus and left crus are identified. Anteriorly phrenooesophageal ligament and peritoneum is divided transversely. Oesophagus is mobilised adequately proximally as well as at OG junction distally for 3 cm. Anterior left vagus is identified, dissected and safeguarded. Oesophagus is held with a tape or 0.62 cm width and 15 cm length Penrose drain and pulled down towards left lower abdomen. It facilitates further easy dissection.

Myotomy is done on the anterolateral surface of the oesophagus left of anterior vagus as longitudinal incision starting at cardia extending upwards for 6-8 cm. After dissecting longitudinal muscle circular muscle should be cut up to mucosa. Fine laparoscopic scissor is used. Harmonic scalpel is very useful. Monopolar cautery may injure mucosa and so better to be avoided. As bleeding is very less if at all needed bipolar is sufficient. In harmonic scalpel active blade should be kept anteriorly. Technique is splitting, elevating the longitudinal muscles and circular muscles; then to cut the circular muscle fibres as small segments sequentially up to the needed proximal length. Usual site is at 2 O'clock position left of the anterior vagus. But few advocates right of the anterior vagus at 11 O'clock position. Both are same until anterior vagus is safeguarded and adequate myotomy is done. Mucosa is whitish, smooth structure which is readily identifiable **(Fig. 19-19)**.

Adequate myotomy is important as incomplete myotomy is the common cause of failure. Myotomy should extend 3 cm proximal over the dilated proximal oesophagus. Distally it should extend across stomach only for less than 1 cm. Stomach wall is identified by its pattern of veins which is submucosal and transverse (*bridging veins*). Stomach wall is more vascular and difficult to dissect and chances of perforation are higher during this dissection. After myotomy cut edges are dissected for half the circumference of oesophagus (50%) to prevent reapproximation. Ideally gastroscopy is done. OG junction is identified by Z line and observed for patulous junction; it suggests adequate myotomy. Myotomy area is filled with normal saline and through gastroscopy air insufflation is done to confirm that there is no air leak bubble seen per abdomen over myotomy site. Often methylene blue is infused into the oesophagus to confirm leak. Manometry if kept in place just prior to surgery, pressure can be checked for adequacy and completion of myotomy by observing the drop in pressure.

Hiatal repair is done by approximating the crural pillar using nonabsorbable interrupted polypropylene sutures. Fundus of stomach is mobilised by dividing short gastric vessels using harmonic scalpel or bipolar cautery and scissor. Mobilised fundus is brought behind the OG junction round the hiatus to wrap it. *Toupet's partial posterior 220° (original Toupet is 180°; modified Toupet is 270°) fundoplication* is done. Mobilised and wrapped fundus is sutured to the right cut edge of the myotomy. This part of the wrapped fundus is


5 mm left lobe of liver retracting port just below the xiphoid
Laparoscopy monitor
Anaesthetist
First assistant
Scrub nurse
OT table
Surgeon in between legs of patient
Camera assistant
2nd monitor
Right midclavicular 5 mm working port (left hand working port)
Supraumbilical 10 mm camera port
Left midclavicular 10 mm working port (right hand working port)
Left axillary 5 mm stomach retracting port
Longitudinal muscle is cut / split to expose the thick circular muscle
Circular muscle is cut / split to expose the mucosa underneath
Anterior vagus nerve
Exposed oesophageal mucosa
Sling
Holding the cut edges of the cut muscle
Splitting ------ elevation ------ cutting ----> sequentially

Fig. 19-19: Technique of laparoscopic cardiomyotomy.

also sutured to the right crus in its upper part. Left cut edge is sutured to the left part of the mobilised fundus with interrupted sutures with its uppermost bite taken from the left crus. It prevents reflux and recurrent dysphagia by keeping the cut edges separate. *Dor's anterior partial fundoplication* is often advocated by many as it does not require posterior dissection and it covers the mucosa and may seal small injury which is unnoticed. But reflux incidence is more in anterior Dor's fundoplication. Left cut edge of the myotomy is sutured to the inner part of the fundus of the stomach with seromuscular sutures (2 zero silk/polypropylene). After that right cut edge of the myotomy is sutured on to the greater curvature (outer side) part of the stomach to pull and rollback the fundus over anterior surface of the myotomy area. Anterior fundoplication is used if there was mucosal injury (perforation) which is sutured on table; as it seals sutured site securely.

Intraoperative gastroscopy is very useful to identify the completion of the myotomy. Manometry on table is also very useful.
Robotic-assisted laparoscopic cardiomyotomy is very useful which reduces the hand tremors increasing the precision.

Postoperative care

Nasogastric tube/orogastric tube is removed after 24 hours. Oral fluids are started. Normal diet is started in 10 days. Straining is avoided for one month to prevent herniation of fundal wrap across the hiatus into the mediastinum.

Complications

Oesophageal perforation (4%) – once it is identified it should be sutured using 4 zero vicryl intracorporeal interrupted sutures. Closure is confirmed by methylene blue infusion.

Pleural injury and pneumothorax is the problem. It may occasionally need a chest tube insertion.

Postoperative dysphagia and recurrence of symptoms is usually due to incomplete myotomy (early). Late occurrence of dysphagia is due to reflux induced peptic stricture.

SURGICAL TREATMENT FOR REFLUX OESOPHAGITIS (FIG. 19-20)

Principles of antireflux surgeries

- Operation should restore the LES pressure twice the resting gastric pressure
- The adequate length of the intraabdominal oesophagus should be maintained
- Apposition of diaphragmatic crurae, reduction of hiatus hernia when present
- Repaired OG junction should relax during swallowing adequately
- Tension free fundoplication should be done.



Fig. 19-20: Types of hiatus hernia – sliding, rolling, combined.

Fundoplication

- *Nissen's posterior total fundoplication:* Here after narrowing the crus of diaphragm, mobilised *posterior part of the fundus* of the stomach is wrapped totally 360° around the area of OG junction.
  - *Rudolph Nissen* (1959) first did total fundoplication.
  - Opening the peritoneum over the oesophagus to mobilise the lower oesophagus.
  - Dissection of the diaphragmatic crura of the oesophagus.
  - Mobilisation of entire fundus by ligating short gastric vessels.
  - Vagi are preserved.
  - In Nissen's, 60 French bougie wrap is ideal; after complete mobilisation, only *posterior part of the fundus* is wrapped around after crural repair (otherwise fundoplication may displace into thorax causing paraoesophageal hernia); intraabdominal length of 2 cm oesophagus is created (not more); fundus of the stomach is known to relax in concert with oesophageal sphincter so only fundus should be used to buttress the sphincter; wrapping should be done only around sphincter of oesophagus not around the body of stomach; fundoplication should be kept in abdomen without under tension and without displacing into thorax. Nonabsorbable polypropylene sutures are used.
  - Crural repair is done using interrupted polypropylene sutures.
  - Fundoplication should prevent sphincter shortening/unfolding during gastric distension, should preserve normal swallowing ability, allow proper belching and allow vomiting whenever needed.
  - Bougie; on table and postoperative manometry to assess the pressure of new LOS; on table and postoperative gastroscopy – are commonly used in fundoplication.
  - Mortality of procedure is very less; other parts of the abdomen can be assessed and addressed like gall stones.
  - *Complications* are – *Gas bloat syndrome* (inability to belch); dysphagia; inability to vomit; slippage, proximal migration; paraoesophageal hernia, splenic injury. Floppy Nissen's fundoplication reduces the incidence of gas bloat syndrome.
  - *Laparoscopic Nissen's fundoplication* is ideal and equally successful.
  - *Transthoracic approach* is used for Nissen's fundoplication in patients who has had hiatus hernia repair earlier; who has had short oesophagus; in patients who has sliding hiatal hernia that does not reduce below the diaphragm, associated pulmonary disease, in obese, in patients who have narrow subcostal angle or barrel-shaped chest.
- *Toupet's partial 180° posterior fundoplication*: It is similar to Nissen's posterior fundoplication; it controls reflux alike Nissen's but gas bloat is very less. It is commonly done procedure now. Short



Fig. 19-21: Toupet's partial fundoplication.

gastric vessels are divided completely or partially. Modified 270° type is better placing sutures at 10 O'clock and 2 O'clock positions **(Fig. 19-21)**.

- *Dor anterior fundoplication*: Here right margin of the fundus is sutured to left margin of the oesophagus; front part of fundus is sutured to right margin of the oesophagus; 2nd row is also sutured to right crus. It is useful after Heller's cardiomyotomy if perforation of oesophagus has occurred. It will cover the sutured mucosal injury safely.
- *Rosetti Hell anterior fundoplication*: Here *anterior part of fundus* of stomach is used. Superomedial part of the fundus is brought around oesophagus to suture to anterior part of fundus. Here *short gastric vessels are not ligated* and much less fundus need to be mobilised.
- *Watson's anterolateral fundoplication*: 5 cm intraabdominal oesophagus is created with blunt transhiatal dissection. 120° anterolateral fundoplication augments the LOS function during stomach distension. Bougie insertion, division of short gastric vessels is not needed here.
- *Lind both anterior and posterior fundoplication* of 300° with 60° anteriorly uncovered area is not routinely practiced now.
- *Partial fundoplication with mesh wrap* around is also used. But complications of mesh like erosion, stricture and adhesions are so many.

Fundoplications

- Nissen's – total 360° posterior fundoplication
- Toupet's – partial 180° posterior fundal/posterolateral
- Rosette Hell – total anterior fundal
- Dor – anterior partial
- Watson's – anterolateral 120° partial
- Lind – posterior and anterior

Other Procedures

- *Hill's operation* (Dr Lucius Hill, USA, 1959):
  - Intraabdominal fixation of OG junction (cardia) into median arcuate ligament to augment the effect LOS, to enable the effective oesophageal peristalsis. Procedure is done through transabdominal approach which is assessed by intraoperative manometry. But it is technically difficult, may damage celiac plexus.
  - Oesophagogastric junction and crura of the diaphragm are dissected properly like in any other procedure in this location. Median arcuate ligament is condensed preaortic fascia arching over the anterior surface of the aorta just above the origin of coeliac artery. It joins the right crus and is attached to vertebral column also. Vertically it extends for about 3 cm along the aorta. Medial arcuate ligament is dissected off from coeliac artery and coeliac ganglion; right and left inferior phrenic arteries are also very close which should be carefully dissected. Nerve fibres of coeliac ganglion close to the ligament should be cut. In *Vasanth's method*, dissection at median arcuate ligament is done from upper margin; gently index finger is passed from above downwards underneath dense preaortic fascia to negotiate between aorta and median arcuate ligament. Inferior phrenic arteries and coeliac trunk and coeliac ganglion are there which should not be injured. Using no 1 zero polypropylene, suture bites are taken between pillars of right crus and left crus to repair the oesophageal hiatus **(Fig. 19-22)**.
  - Three suture bites are taken which are not tied but held with haemostats. Then either finger or flat instrument is placed underneath the median arcuate ligament to safeguard aorta and other structures; 1 zero polypropylene suture bites are taken; first from anterior phrenooesophageal bundle (near gastric fundus) from left towards right; next bite from lower oesophagus, posterior phrenooesophageal bundle with part of the lesser curve of the stomach; last bite is from the median arcuate ligament. Anterior phrenooesophageal bundle is left and lateral to anterior vagus at the base of the angle of His distal to oesophago fundic junction; posterior phrenooesophageal bundle is behind the OG junction towards tight right of posterior (right) vagus. Remaining two lower bites are also taken similarly. Haemostasis should be checked at this stage. Crural fibres are sutured to do hiatal repair; index finger should be able to pass through the sutured oesophageal hiatus. Then arcuate ligament repair sutures are tied to complete Hill's posterior gastropexy. Often Teflon pledgets are used into the arcuate ligament sutures but it is not mandatory. Antireflux adequacy is confirmed using saline.
- *Belsey Mark IV operation* (Ronald Belsey, Britain, 1967):
  - It is plication of oesophagus to the diaphragm through many interrupted mattress sutures so as to push the oesophagus downwards to make it intraabdominal with adequate length. It is done through left transthoracic approach. 240° fundoplication, creation of intraabdominal oesophagus, crural sling repair are the techniques. It corrects GERD and also maintains normal eructation and physiological reflux. But long hospital stay and respiratory complications are distressing problems **(Fig. 19-23)**.
  - Left posterolateral thoracotomy is done through 6th intercostal space. Oesophagus is mobilised from diaphragm to aortic arch. Left superior and inferior bronchial arteries are ligated. Direct oesophageal arteries are also ligated. Adequate mobilisation is essential. Vagi should be preserved carefully. Phrenooesophageal membrane is divided to enter into the peritoneal cavity. With the left hand fingers mobilising and retracting the OG junction and gastric fundus, with the right hand scissor dissection is done under vision. Short gastric vessels are divided. All attachments


Anerior phrenooesophageal bundle
Hiatal repair
Oesophagus
Median arcuate ligament repair
Median arcuate ligament
Aorta with coeliac trunk
Posterior phrenooesophageal bundle

Fig. 19-22: Hill's repair of hiatus hernia.

between stomach and hiatus are divided. Fundus and abdominal oesophagus are drawn into thoracic cavity by holding with Babcock's clamps.

- Hiatal repair sutures are placed using 1 zero polypropylene sutures from below upwards. All sutures are placed (3-4) first (tied together later only after completing the fundoplication).
- Gastric fundus is plicated around the anterior 2/3rd of the lower 4 cm of oesophagus. First row of sutures are 1.5 cm above the cardia. 3 zero or 2 zero polypropylene suture material is used. Left anterolateral position of the oesophagus used for plication as view over right side is inadequate. Bite taken from the gastric fundus (seromuscular) then from the muscular wall of the oesophagus horizontally then again on to the gastric fundus adjacent to first bite with a 5 mm gap. All first row plication sutures are placed; then they are tied to pull up the fundus **(Fig. 19-24)**.
- Second row of sutures are placed 2 cm above the first row using 2 zero or 3 zero polypropylene suture or silk. From gastric fundus as seromuscular to the oesophagus as muscular then back to the gastric fundus as seromuscular with a 5 mm gap. All sutures are placed and then tied; ends are not cut but held with haemostats. Now each free ends of the suture are passed through (after passing needles to each tails) the diaphragm from abdominal side towards thoracic side. Once all ends are passed like that; knotting is done securely. Fundus with the oesophagus is pushed down into the abdominal cavity.
- Hiatal sutures which were taken earlier (previously placed) are tied now securely to complete the hiatal repair.

- *Placement of Angelchik prosthesis*: Annular silicone gel filled angelchik prosthesis with a tape on either end. After insertion around OG junction ends are tied around.


Oesophagus
Fundus
Sutures to restore the angle
Diaphragm
Stomach
Anterior 2/3rd of fundal wrap
Plication of OG junction
Stomach
Stomach

Fig. 19-23: Belsey Mark IV operation.

- *Collis' vertical gastroplasty* is done using fundus stomach. A vertical cut along the line of oesophagus is made on the fundus which is sutured to create extra length of oesophagus and new lesser curvature. It is done whenever oesophagus cannot be mobilised due to oesophageal shortening by a stricture developed as a complication of GORD. Partial fundoplication is added to this usually. Previous gastrectomy is contraindication to this **(Fig. 19-25)**.
- *Transthoracic Collis – Nissen's gastroplasty –*
  - It is used in short oesophagus with stricture and recurrence after an earlier antireflux procedure. Open mind should be also kept for need of bowel (colon) interposition in such patients. New oesophagus is created by lengthening it. Then antireflux procedure is done. Entire procedure is done through thoracotomy **(Fig. 19-26)**.
  - Double lumen endotracheal lumen tube is placed. One lung anaesthesia is given. Nasogastric tube should be passed. Lateral left side up position is used for 6th intercostal space thoracotomy. Latissimus dorsi and serratus anterior muscles are cut. Incision posteriorly should extend up to the lateral margin of the spinal muscles. Pleura is opened. Often 7th rib excision posteriorly is needed to have a better access with ligation of intercostal vessels running under 7th rib at its lower margin. If needed conversion


Diaphragm
Gastric fundus pulled through hiatus above to thorax
Lung
Oesophagus mobilised (Thoracic)
Anterior vagus
Thoracic aorta
Oesophageal hiatus
A
Hiatal repair sutures placed (Not tied)
Anterior vagus (Retracted)
Aorta
Interrupted polypropylene sutures
B
First row of fundoplication between gastric fundus and 2 cm above the oesophageal wall
C
Knot tied of first row sutures of fundoplication
D

Figs 19-24A to D


These sutures are tied but tail ends are kept long initially; These ends are passed through the diaphragm after passing through a needle on each

2nd row of sutures taken from gastric fundus further away.
- First from fundus then from muscular part of oesophagus further 2 cm proximally; then again from gastric fundus with 5 mm gap
- Anterolateraly 3-4 such sutures are placed.

E
Diaphragm
Second row of suture bites
Gastric fundus
Oesophagus
First row of sutures-knot tied
F
Second row of sutures - knot tied over the diaphragm
G
Second row of sutures - knot tied over the diaphragm
Hiatal sutures earlier placed (during beginning) were tied to complete the hiatal repair
H

Figs 19-24E to H

Figs 19-24A to H: Technique of Belsey mark IV operation.

into thoracoabdominal by anterior extension of the thoracotomy should be done to facilitate the better dissection of the hiatus.

- Inferior pulmonary ligament and then mediastinal pleura has to be incised medial to the thoracic aorta. With blunt and sharp dissection and nasogastric tube as a guide, oesophagus with anterior vagus is encircled using sling (umbilical/Penrose drain). Proximally dissection is extended up to the inferior pulmonary vein. Lower part of the incision is extended in front along the pericardiophrenic sulcus to facilitate the hiatal dissection.
- Phrenooesophageal ligament and peritoneum is incised. Hiatus is dissected circumferentially. Hernial sac existing is identified. Hernial sac is dissected by holding the oesophagus with traction. A branch of inferior phrenic artery is ligated. Gastrohepatic ligament is incised and opened towards right with adequate traction. An accessory left hepatic artery is commonly seen in this ligament which should be ligated. Other attachments between hiatus and proximal stomach are divided using bipolar cautery or harmonic scalpel.
- Oesophageal stricture should be dilated using series of Maloney dilators. Peritoneum of the hernial sac is excised. Short gastric vessels along the greater curvature are ligated and divided or using harmonic scalpel for about 15 cm of greater curvature. Pad of fat around the OG junction is dissected and removed. 60 no. French Maloney dilator is passed across the hiatus. Lineal stapler is fired along the fundus left of the oesophagus to create a new fundus and neooesophagus of 7-8 cm (lengthened oesophagus). Stapled lines along the neooesophagus and gastric fundus are often inverted using continuous seromuscular sutures using 3 zero PDS or vicryl. Metal clip is applied at the junction of neooesophagus and stomach as a marker.
- New fundus is brought under the neooesophagus to create a wrap; it is sutured to the greater curvature with interrupted using

2 zero polypropylene sutures to complete the wrap. Usually 3 sutures for 3 cm length are placed. Bite also should be taken from the neooesophagus. Wrap should accommodate index finger to prove it as floppy. After that hiatal repair is done by apposing the right and left crura using interrupted polypropylene sutures. Mediastinal pleura may or may not be sutured. Intercostal tube is placed (36F). Thoracotomy wound is closed.

– Complications are – gastroplasty tube necrosis; recurrence; leak; empyema; obstruction.

- *Thal's patch procedure*: It is done for localised nondilatable stricture oesophagus. Stricture is incised full thickness longitudinally. Mobilised fundus of stomach is placed and sutured as a serosal patch technique over the defect **(Fig. 19-27)**.
- *Narbona's ligamentum teres cardiopexy* (commonly done in Spain): Ligamentum teres is mobilised from falciform ligament with its blood supply from left lobe of liver; it is detached from umbilicus and brought around the mobilised lower oesophagus with traction until LOS pressure becomes 15-20 mm Hg with manometry; flap end is sutured left of OG junction and anterior wall of stomach. It is more physiological and division of short gastric vessels is not required.
- *Boerema operation*: It is fixing OG junction in front into anterior abdominal wall. It is not practiced now.


Oesophagus
Diaphragm
Gastroplasty incision
Stomach

Fig. 19-25: Gastroplasty technique.


Incision can be extended down into the abdomen if upper abdominal aorta exposure is needed simultaneously
6th intercostal space approach
Serratus anterior muscle
Intercostal muscle
7th rib
Latissimus dorsi muscle (cut)
Serratus anterior muscle (cut)
Incision over intercostal muscle above the rib
Intercostal muscle (cut)
Pleura opened
7th rib is cut on its medial part near sternum
Intercostal vessels ligated

Fig. 19-26: Transthoracic Collis-Nissen's gastroplasty.



Fig. 19-27: Thal's patch.

- *Oesophagogastrectomy* is required whenever there is *failure of antireflux procedure*/*metaplasia* is present/*nondilatable stricture* is present. Lower end of oesophagus and proximal stomach is resected with oesophagogastric anastomosis is done through thoracoabdominal approach.
- *Transhiatal oesophagectomy* with anastomosis between cervical oesophagus and stomach in the neck is an alternate procedure which can be used in severe extensive disease and stricture.

Nissen's Fundoplication (Nissen–Rosetti)

It is done either through laparotomy/laparoscopy or through thoracotomy.

Preparation

Preoperative gastroscopy, pH studies, oesophageal manometry, contrast CT chest are needed as investigations. Nasogastric tube should be passed. Often oesophageal bougie or orogastric tube is also used as a guide for mobilisation.

Procedure

Patient is in reverse Trendelenburg position with head up (15-30°); general anaesthesia is used always. Upper midline incision from xiphoid process is done often extending left of the umbilicus below. Self retaining retractor is essential. After laparotomy, abdominal cavity is quickly explored **(Fig. 19-28)**.

Mobilisation - Stomach is held downward and left by assistant. This stretches the tissue around the oesophagus to facilitate dissection and also reduces the any hiatal hernial component. Left triangular ligament is cut to mobilise the left lobe of liver which is retracted down and towards right. Care should be taken not to injure left hepatic vein or IVC. Gastrohepatic ligament is divided. Accessory left hepatic artery may be present in the ligament which is usually saved. It is a branch of left gastric artery. It is now found that ligation of accessory hepatic artery is safer and so if needs can be ligated. Phrenooesophageal ligament and peritoneum is incised circumferentially in the hiatus to visualise the crura of diaphragm from behind. Mobilisation is done like mobilisation of the distal oesophagus described above. Blunt, peanut and sharp dissections are used. Energy sources can be used carefully. Three fingers should be passed easily, freely through post oesophageal window. Anterior and posterior vagi nerve trunks should be preserved dissected carefully and safeguarded. Penrose drain or sling is passed around the hiatus which is used as traction for further dissection.


30 degree head up tilt is ideal
for antireflux surgeries

Fig. 19-28: Operation table position in fundal wrap procedure with patient is in reverse Trendelenburg position with head up (15-30°).

Gastrophrenic ligament is identified and divided. Short gastric vessels are divided from the fundus to mobilise it adequately to create a wrap. Short gastric vessels are short, thin walled and stout. Tear of these vessels cause torrential haemorrhage. Often tear may extend into the splenic capsule creating further damage. Traction over the spleen should be gentle and minimal to prevent this; vessels should be ligated using 3 zero silk or vicryl and divided with bipolar cautery. Harmonic energy source is better. Sling over the hiatus is used for continuous traction over the fundus. Two Babcock clamps are passed underneath the oesophagus from right towards left to hold the mobilised fundus; fundus is brought underneath and the front of oesophagus. Babcock clamps are relaxed to check any tension on the mobilised fundus. Mobilised fundus should stay there comfortably without any tendency to return back to its original position. If it is not so, further mobilisation of fundus is needed.

Hiatal repair is a must to prevent fundoplication to slip into the thoracic cavity (mediastinum). Distal slippage of wrap does not occur as gastric trinity prevents that. Using zero polypropylene sutures, deep bites are taken from peritoneum right crus including tendinous portion then of left crus and peritoneum over it. From below upwards 3 interrupted sutures are placed. Sutures are tied sequentially from below upwards. It should not be too tight or too loose. Index finger should be able to pass through the repair and oesophagus comfortably **(Fig. 19-29)**.

Fundoplication - Adequate mobilisation of the hiatus, distal oesophagus (6-8 cm) and fundus is essential. *Wrap* can be done with vagi within or outside. Vagi are kept outside the wrap often. But many advocate wrap with keeping both vagi in position. Often *posterior vagus is kept outside the wrap and anterior vagus is within* the wrap. It does not make any difference until wrap is loose, free (*Floppy*) and suturing bites should not pass through the vagi. No. 2 zero polypropylene interrupted sutures are placed between wrapped part of the fundus through oesophageal muscle wall to the left part of the mobilised fundus to complete 360° plication. First three sutures each at 0.5-1.0 cm apart are placed from below upwards; then sutures are tied. First bite should be from mobilised fundus of the right of oesophagus of patient; through the lesser curve; then from the fundus at left of the oesophagus. Thickness of bite should be around 5 mm; but should not enter the lumen. Interrupted sutures are placed at 1 cm gap. Maximum 3 cm wrap is created not more than that. After completion of the wrap, two fingers should able to pass under the wrap to confirm that fundoplication is not too tight. Suture is also often placed from the wrapped fundus to the hiatal wall (right crus) to stabilise the fundoplication; but it is not necessary **(Figs 19-30 to 19-32)**.

Single suture 360° wrap with Teflon pledget buttress is also often done. Even though many advocate mesh usage for hiatal repair it is not advisable as mesh erosion into the oesophagus is threatening and dangerous.


Oesophagus
Peritoneum
Crus of diaphragm with deeper tendinous part
Peritoneum
Mobilised oesophagus
Interrupted zero polypropylene (thick) sutures
Crus with deeper tendinous part
Repair should not be too tight; should able to pass index finger freely across
Completed hiatal repair with 3 interrupted deep sutures

Mobilised OG junction with exposure of crura for hiatal repair

Commonly repair is done with retracting mobilised oesophagus towards left. Repair is done from right side

Often by few surgeons, repair is also done with retracting mobilised oesophagus towards right. Repair is done from left side

Fig. 19-29: Hiatal repair.


Anterior vagus
Oesophagus
Fundus wrap
Posterior vagus
Aorta
Anterior vagus
Oesophagus
Fundus wrap
Posterior vagus
Aorta
Anterior vagus
Oesophagus
Fundus wrap
Posterior vagus
Aorta

Both anterior and posterior vagi are within the wrap

Both anterior and posterior vagi are outside the wrap

Posterior vagus is outside the wrap; anterior vagus is inside the wrap

Fig. 19-30: During fundal wrap vagi are kept in different positions depending on the choice.


Crus of diaphragm
Mobilised oesophagus
4
3
2
1
Right limb of wrap (posterior part of mobilised fundus)
Left limb of wrap (anterior part of mobilised fundus)
Anterior vagus
Crus of diaphragm
<3 cm

Interrupted 2 zero polypropylene sutures maximum up to 2-3 cm wrap only (floppy wrap)

Completed Nissen's 360 degree total fundoplication
Vertical length of the wrap should be less than 3 cm

One should able to pass 1-2 fingers under the wrap freely - floopy wrap

Fig. 19-31: 360° wrapping of the fundus in NIssen's fundoplication.

Through nasogastric tube 400 ml of saline is infused into the stomach. Stomach is compressed with moderate pressure to trial expelling of the saline from stomach to oesophagus. If saline cannot be expelled means antireflux valve created is competent.

Postoperative care

Nasogastric tube is removed after 48 hours. Oral fluid is started. Oral contrast X-ray study is done to visualise progressively narrowing tapered OG junction which suggests the successful surgery. Absence of tapering suggests loose fundoplication.

Success rate for Nissen's fundoplication is 90%. Recurrence or failure rate is 10%.

Complications

Dysphagia is common after Nissen's fundoplication. It is usually temporary lasting for 3 weeks due to mucosal oedema. If dysphagia persists it is due to tight/wide (>3 cm width) wrap or too tight hiatal repair or missed other causes like achalasia, motility disorders. Indwelling bougie placement across the hiatus during surgery will prevent fundal wrap becoming too tight. Two fingers should be able to pass under the wrap.

Gas bloat syndrome is inability to belch causing tightness in the upper abdomen. It is due to too tight wrap. Floppy fundoplication prevents this.

Contd...



Fig. 19-32: Teflon pledget buttressing in fundoplication.

Contd...

Fundoplication can disrupt causing recurrence or failure. So it is ideal to use monofilament nonabsorbable 2 zero sutures. Polypropylene is commonly used. Vicryl or silk may get digested slowly eventually. Failure is due to disruption of wrap; loose wrap causing slipping of fundoplication; sliding hernia with wrap in abdomen; intrathoracic migration of fundoplication. Barium swallow confirms the diagnosis.

Fundoplication may slip downward causing hour glass stomach and obstruction.

Fundoplication wrap may get herniated into the thorax or paraoesophageal hernia may occur.

Gastric or oesophageal perforation can occur which needs proper suturing.

Injury to spleen (1-5%), vagi, pneumothorax, and subphrenic abscess are rare complications.

Laparoscopic Nissen's Fundoplication

Laparoscopic approach has become ***standard*** since 1992 for fundoplication. Preoperative preparation is same as open method. Contrast study; gastroscopy, 24 hour pH monitoring, oesophageal manometry, chest X-ray are needed. Severity of the reflux; presence of oesophagitis, Barrett's oesophagus, stricture, shortening are to be evaluated properly before planning the surgery. Patients who are intolerant or poorly responding to proton pump inhibitors; patients with large hiatal hernia; presence of complications are the indications for surgical intervention.

Technique - Under general anaesthesia, patient is with reverse Trendelenburg (30°)/head up with semilithotomy position. Surgeon stands in between legs. Three 10 mm trocars and two 5 mm trocars are placed. Supraumbilical port is 5 cm above towards left (to avoid falciform ligament) which is used for 30° laparoscope. Pneumoperitoneum is created. Camera assistant is on the right of the patient; assistant on the left; scrub nurse either right or left distally.

Hiatal mobilisation is done as like in Heller's cardiomyotomy. Gastrohepatic ligament (hepatogastric omentum) is incised. Hepatic branch of left gastric artery is divided; there may be aberrant left hepatic artery which may be the only branch supplying the left lobe of the liver (15%). It is safeguarded. Peritoneum is divided circumferentially all around. Right crus is identified and dissected; similarly left crus. Posterior vagus which is in the loose areolar tissue is also identified and dissected carefully for preservation. Phrenooesophageal ligament is divided all around.

Retrogastric window is created by incising the peritoneal attachment adjacent to gastric fundus near angle of His. Left inferior phrenic artery or few posterior short gastric vessels may be present here which should be fulgurated and divided. Umbilical tape or Penrose drain is used to sling around the OG junction and for traction. During left side mobilisation left pleura may get injured so care should be taken to avoid it.

Short gastric vessels are divided adequately using harmonic scalpel or bipolar cautery to mobilise the fundus. Splenic injury, short gastric vessel tear and gastric perforation are the complications which can occur, and should be avoided.

Hiatal repair is done by retracting the sling at OG junction towards left by approximating both pillars of right crus with left crus with their tendinous attachments using thick no. zero polypropylene interrupted sutures. Peritoneum overlying the crura should be included with the suture bites. Usually 3 sutures are placed 1 cm apart. It should not be too tight or too loose. Sling at OG junction when released oesophagus will retract and fill the hiatus without any constriction or without entering through the hiatus. Additional suture may be added if need arises.

Fundoplication - Grasper is passed from right side across the retroesophageal window towards left side of OG junction to hold the posterior wall of the mobilised fundus; it is pulled behind the oesophagus towards right side to form right limb of the fundic wrap. Anterior wall of the fundus forms the left limb of the wrap. By holding both limbs of the fundus/proposed wrap it is glided gently behind the oesophagus to position it properly (John Hunter's shoe shine technique). Colour of the wrap should be noted. If it becomes congested and bluish that means fundal mobilisation is inadequate compromising the vascularity. When traction pull on the right limb is released wrap should stay in place freely to confirm that wrap is adequately mobilised. 2 zero polypropylene suture is used for fundoplication. 60 French oesophageal bougie/dilator is passed per orally by anaesthetist to reach the OG junction which facilitates the floppy fundoplication. It is not necessary but optional. Bite (seromuscular) is taken from the right limb of the wrap (posterior wall of mobilised fundus); next bite is taken from the wall of the oesophagus left of the anterior vagus (muscular); last bite is from the left limb of the wrap (anterior wall of the fundus). Usually 3 sutures are placed but not more. Only 2-3 area should be covered by the wrap to make it floppy. Floppiness is checked by passing 5 m grasper freely under the wrap in front of the oesophagus. Wrap may be fixed to crura using nonabsorbable (polypropylene) suture to prevent wrap migration.

Modified Toupet's partial posterior fundoplication is also done to prevent gas bloat syndrome by suturing the right limb of the wrap to oesophageal muscular wall at 10 O'clock position using interrupted polypropylene sutures; left limb of the wrap is sutured to the left wall of the oesophagus similarly at 2 O'clock position to complete the 270° wrap.

Postoperative care

Nasogastric tube is removed in 24-48 hours. Oral sips are started. Gastroscopy is done during follow up period.

Complications

Wrap herniation (1%) which occurs in 48 hours; left sided pneumothorax; perforation; spleen injury; gas bloat syndrome; dysphagia are different complications.

OESOPHAGECTOMY

TRANSHIATAL OESOPHGECTOMY (ORRINGER AND ORRINGER, 1983)

It is commonly done procedure for carcinoma of oesophagus at lower third region. It is basically palliative procedure as nodal clearance not addressed. It is also logically a blind and blunt procedure as thoracic mobilisation of the oesophagus is not under vision. But it avoids the thoracotomy and its problems. Pulmonary complications are less and also duration of hospital stay compared to Ivor Lewis approach. It is also done for benign stricture of the oesophagus.

Procedure is done under general anaesthesia. Nasogastric tube should be in place. Blood should be kept ready in case there is bleeding during thoracic dissection. Intraarterial catheter is required. CVP line is better to keep always. Intravenous line on the left upper limb should be avoided. Position is supine with head end up (reverse Trendelenburg position). Head is turned towards opposite side. Neck is extended by placing a small blanket under upper thorax. Cleaning is done from chin to pubic symphysis. Draping is done **(Figs 19-33 and 19-34)**.

Abdominal dissection

Upper midline incision is placed. Often upper horizontal or bilateral subcostal may be used. Self-retaining retractor is placed. Abdomen is explored for secondaries in liver, peritoneum and coeliac lymph nodes. Left lobe of the liver is mobilised. Traction is given to stomach. Oesophagogastric junction is identified. Peritoneum and phrenooesophageal ligament is incised like mentioned above. Retrooesophageal window is created by sharp and blunt dissection. Accessory hepatic artery may be ligated. Short gastric vessels are ligated carefully without creating traction as vessels may get avulsed and can cause torrential bleeding. Splenic injury is a risk which should be avoided. Handling and traction over the spleen should be gentle with care. Left gastric vessels are doubly ligated securely. Energy sources like harmonic are very useful. But it is ideal to ligate left gastric artery. Vascular clips are other alternatives used. Left gastroepiploic vessels are ligated. Greater omentum is cut using harmonic or be sequential ligations to free greater curvature of the stomach. Retrogastric dissection is done by finger and scissor dissection. Right gastric and right gastroepiploic vessels should be retained. Both anterior and posterior vagi are cut **(Fig. 19-35)**.



Fig. 19-33: Midline laparotomy incision is commonly used. Often upper horizontal or bilateral subcostal may be used.



Fig. 19-34: Midline or bilateral subcostal incision can be used.

Duodenum is mobilised by Kocherisation. Pyloromyotomy or pyloroplasty is done. Usually *Heineke Mikulicz* pyloroplasty is done. Pyloroduodenum is cut longitudinally; it is sutured transversely to widen the pylorus. Two layered interrupted sutures are commonly used. Inner 2 zero vicryl full thickness; outer seromuscular 2 zero silk sutures. Pyloroplasty should be perfect and proper as after pull up it will stay in the thoracic cavity and any bile leak will enter the pleural cavity and is life threatening. Many prefer pyloromyotomy because while gastric conduit is pulled upwards pyloroplasty suture may give way due to traction. Metallic clips are placed at the edges of the pyloroplasty or pyloromyotomy as identification radiologic markers **(Fig. 19-36)**.


Gastroepiploic arterial arcade should be kept intact
Right gastroepiploic artery
Greater omentum

Fig. 19-35: Gastroepiploic arcade should be kept intact in gastric pull up procedures when stomach is used as conduit.



Fig. 19-36: Kocherisation is done; pylorus is widened usually by pyloromyotomy; often pyloroplasty is done.

Hiatus is gently dissected to free oesophagus; often a cut in the crus may be needed. Transverse phrenic vein which is present there needs ligation. This also facilitates the adequate accommodation of the pulled up stomach; if hiatus is not widened, congestion of the stomach can occur which is risky. Penrose drain or umbilical tape or any type of slings is passed around the OG junction, which helps in providing traction and further dissection. Hiatus should be widened about 3 fingers. Fingers are passed across the hiatus to feel the tumour and if it is adherent to aorta or vertebra transhiatal procedure is contraindicated. Pericardium can be gently reflected forward. Both side pleura are retracted laterally. Index and middle fingers are passed across the hiatus close to the oesophageal wall to dissect the perioesophageal loose areolar tissue. If fingers are kept adjacent to oesophageal wall it is less likely to injure the azygos veins even though there is small risk as procedure is blind. Fingers can be reached easily up to the carina of trachea. One should be very careful here as membranous trachea may be closer to oesophageal wall which may get injured. Injury to trachea membranacea is very difficult to manage and is near life threatening even though immediate right sided thoracotomy and suturing of the carina at its membrane is done but most of the time it is futile and patient succumbs. Dissection often still is possible to do under direct vision up to the arch of aorta; it is done with gentle traction, clipping of perioesophageal vessels and cutting the tissue; further traction and clipping like that sequentially. This is better facilitated by using a head lamp by the surgeon **(Fig. 19-37)**.

Dissection in the neck

Cervical oesophagus is approached usually through left side as in the neck oesophagus more towards left side. Surgeon stands on the left side of the patient. But if patient has undergone any surgery of the neck earlier then right side approach is used **(Fig. 19-38)**.

Incision is usually oblique vertical along the anterior border of the sternocleidomastoid muscle from sternal notch to mandibular level. Cosmetic low horizontal incision is also can be used. Sternocleidomastoid muscle is retracted laterally; *omohyoid* and often sternothyoid are divided. Carotid sheath with vessels is retracted laterally. Strap muscles are retracted medially to expose the thyroid and middle thyroid vein. Middle thyroid vein is ligated. Inferior thyroid artery is dissected and usually requires ligation but often preserved. Recurrent laryngeal nerve is identified and safeguarded. It is not always necessary to identify the recurrent laryngeal nerve. It is better to use *assistant's finger as retractor* on the medial aspect over trachea to prevent injury to recurrent laryngeal nerve by a metal retractor.

Oesophagus is visualised behind trachea as a vertical muscular tube. Lateral lobe of the thyroid is in front and lateral of it. Nasogastric


Oesophagus
Divided right crus
Peritoneum
Crus of diaphragm with deeper tendinous part
Right crus is divided using cautery to widen the hiatus

Fig. 19-37: To widen the hiatus right crus may be cut when needed.

tube can be felt easily by fingers. By careful blunt and sharp dissection retrooesophageal plane is created between oesophagus and vertebra. Care should be taken not to injure the oesophageal wall. Recurrent laryngeal nerves and tracheal posterior wall are also may get injured. Oesophagus is held using a Babcock clamp and gentle traction is exerted towards left side to complete the finger and sharp dissection around the oesophagus. A Penrose drain or sling is passed around the oesophagus. Oesophagus is further mobilised in the neck up to the sternum using finger. *Sponge on a stick* also can be used for posterior dissection of the oesophagus which is passed gently in front of the prevertebral fascia through neck wound.

Final mobilisation

With surgeon standing on the left side left hand fingers are passed through the oesophageal hiatus close to the oesophageal wall along the posterior mediastinum and right hand fingers are passed through the neck behind the trachea close to the oesophagus. Slight traction is needed to the oesophagus. Blunt gentle finger dissection is carried out circumferentially around the oesophagus. Fingers from below and fingers from above will meet each other to complete the dissection and mobilisation. Compression over the heart should be avoided; if there is any change in the arterial pressure fingers should be withdrawn temporarily and later dissection is completed again. Usually posterior dissection is carried out first; then anterior dissection. Upper part of the posterior dissection is done often from upper part using a *sponge on stick* **(Fig. 19-39)**.

Oesophagus is transected 5 cm distal to the cricopharyngeus between two occlusion clamps. Stay sutures are placed on to the proximal cut end of the oesophagus including the mucosa to prevent mucosal retraction. Linear stapler can also be used. A roller gauze or Penrose drain is tied around the distal cut of the oesophagus in the neck.

Oesophagus is pulled down into the abdomen across the posterior mediastinum and hiatus. Long Penrose drain or infant feeding tube is better as its free end is held with a haemostat in the neck; other end with the oesophagus and tumour is pulled down into the abdomen. Lengthy infant feeding tube or Penrose drain is released by cutting and is held with another haemostat; its other end is still in the neck being held by a haemostat. This allows the easy passage of the gastric conduit across the posterior mediastinum into the neck wound for further anastomosis. Tip of the gastric conduit should be pink, healthy and viable.



Figs 19-38A to C: Neck dissection to mobilise cervical oesophagus.



Fig. 19-39: Fundal mobilisation

Gastric conduit (Neooesophagus) creation

In the abdomen stomach is transected just distal to the OG junction using stapler. Stomach along the greater curvature is longitudinally transected distal to the OG junction for 6 cm. Stomach wall is sutured securely using 2 zero sutures in two layers. If stapler is used stapler line may be supported with seromuscular sutures. Entire oesophagus with tumour is removed. Gastric conduit is passed across the posterior mediastinum towards the neck wound. Often stay suture/s is/are placed on the wall/s of the gastric conduit to confirm that twist/rotation of stomach wall has not occurred. Often posterior part of the gastric conduit is fixed to the longus coli muscle in the neck with few serosal interrupted sutures. These *suspension sutures* are no longer said to be essential. Hiatus should be three finger width to prevent venous congestion over the pulled up gastric conduit. Extra width of the hiatus is narrowed by placing 2-3 interrupted silk sutures to the hiatus which prevents intestinal herniation. Often at the hiatus one or two interrupted sutures are placed between hiatus and anterior gastric wall (adjacent to hiatus). Pyloromyotomy/pyloroplasty usually stays 2-3 cm below the hiatus after gastric conduit pull through **(Fig. 19-40)**.

Anastomosis

Proximal cut end of the oesophagus is anastomosed to the anterior wall of the pulled up gastric conduit as end to side anastomosis. Adequate bleeding from the cut edges of both oesophagus and gastric conduit should be ensured. Oesophageal cut end should be made oblique (anterior flap/part of the oesophagus should be 1 cm longer than posterior flap). Anterior wall of the stomach is incised 3 cm lower to the tip of the gastric conduit. Usually vertical or transverse incision is made and is of 2.5 cm in size; often same sized elliptical piece of the stomach wall may be excised but it is not mandatory. Inner all layer full thickness/mucosa and submucosal layer 3 zero vicryl interrupted sutures are used; outer layer seromuscular/muscular 2 or 3 zero silk sutures are used to complete the anastomosis. Often posterior inner layer interrupted all sutures are placed first and held with different haemostats; knots are tied at the end one by one to achieve proper apposition and inversion. After posterior layer it is better to pass a nasogastric tube across the stoma into the gastric conduit and fix it. But many surgeons pass the nasogastric tube after the completion of the anastomosis by gentle milking of the tube tip. Anastomosis should stay above the level of the clavicle. It should be tension free also **(Fig. 19-41)**.

Suction drain is placed in the neck wound; drain is brought out through a separate wound and fixed to skin. Abdomen is inspected again for any blood trickling from the posterior mediastinum. Position of the gastric conduit gently felt and confirmed. Hiatus should able to accommodate three fingers. If it is more widened than 3 fingers then extra gap can be sutured with few interrupted sutures; this prevents bowel herniation across the hiatus. Feeding jejunostomy is done 15 cm distal to ligament of Treitz for postoperative care **(Figs 19-42 and 19-43)**.

Abdomen wound is closed in layers. Usually abdomen cavity is not drained; but oozing if expected tube drain is kept in the abdominal cavity. Neck is also closed in layers after placing a suction drain.

If pleural breach is suspected intercostal tube is placed in the thoracic cavity (in 75% of cases ICT is needed). Tube is removed in 72 hours once check chest X-ray shows adequate lung expansion and if there is no air leak or if pleural drain is less than 100 ml **(Fig. 19-44)**.

- Wide gastric conduit is important to preserve the submucosal collateral circulation.
- Adequate/extended Kocherisation is essential to avoid tension on the tip of the gastric conduit.
- Trauma should be avoided on the gastric conduit tip.
- Adequate (3 fingers) hiatal passage to prevent congestion of the gastric conduit.
- Twist/torsion/rotation of the gastric conduit should be avoided.
- Anastomosis should be above the level of clavicle (Cervical Oesophago Gastric Anastomosis; CEGA); it should be tension free; it should have good blood supply.
- Safe pyloromyotomy/pyloroplasty
- Preserve right gastroepiploic and right gastric arterial supply.


Stapler resection line 5 cm distal to the OG junction
Vagotomy (both)
Left pleura
Short gastric vessels (ligated)
Spleen
Carcinoma oesophagus
Splenic artery
Right pleura
Incised phrenooesophageal ligament
Widened hiatus
Gastric conduit
Left gastroepiploic artery (ligated)
Left gastric artery (ligated)
Crow's foot
Right gastric artery (preserved)
Right gastroepiploic artery (preserved)
Pyloromyotomy
Mobilised (Kocherised) duodenum

Fig. 19-40: Mobilisation and creation of conduit in transthoracic oesophagectomy.



Fig. 19-41: End to side oesophagogastric anastomosis.


Cervical oesophago gastric anastomosis (CEGA)
Trachea
Stomach is mobilised from the abdomen and pulled up into the thorax to replace as the oesophagus (Thoracic oesophagus is removed)
Clavicle
Thoracic aorta
Gastric conduit (pulled up)
Diaphragm
Hiatus
T10
Pyloromyotomy
Median arcuate ligament
Mobilised/Kocherised duodenum

Fig. 19-42: Final look of oesophagogastric anastomosis.



Fig. 19-43: Transhiatal oesophagectomy.

Postoperative care

Nasogastric tube is removed in 5-8 days once bowel sound is heard. Water soluble contrast study may be done after removal of the nasogastric tube (7th day) to confirm that - there is no anastomotic leak; stomach empties adequately; there is no obstruction. Oral sips are started initially later to switch over to semisolid and solid diet.

Complications and problems

Injury to azygos vein and tracheal membrane (less than 1%) at carina even though rare are most dangerous complications. It needs immediate thoracotomy. In case of azygos vein injury, immediate right sided thoracotomy is done; azygos vein is ligated at azgos arch where it enters to superior vena cava. Massive bleeding can occur from avulsion of oesophageal arterial branches from aorta. Whatever the reason, immediate packing through the hiatus and thoracotomy should be done to deal these problems under direct vision. Small linear tear in membranous trachea can be repaired; but avulsion of this part is life threatening. Mortality in transhiatal oesophagectomy is less than 1%.

Injury to spleen may warrant splenectomy (3%). Gastric wall oedema, congestion and necrosis may occur. In such situation if gastric viability is doubtful reexploration is done. Gastric conduit is resected. Colonic conduit is used for maintaining the continuity.

Bile leak, leak through the pleural cavity is again risky, and is difficult to manage. It needs reexploration through thoracotomy and suturing or conversion as colonic conduit. Mortality is very high if there is bile leak into the thoracic cavity. Leak may be from gastric conduit suture line or from pyloroplasty suture site.

Anastomotic leak from oesophagogastric anastomosis site (< 10%) is even though not uncommon is less risky as leak is into the neck. Further it is less usually partial and will heal spontaneously. It is better in such situation to keep the nasogastric tube in situ until leak subsides. Rarely it needs surgical reexploration at neck and resuturing.

Thoracic duct injury and lymph ooze can occur. Chylothorax (1%) is suspected when drain persists more than 800 ml/day after 4th postoperative day. Cream is infused through the jejunostomy to observe an opalescent colour in the intercostal tube drain. Thoracic duct injury needs reexploration and duct ligation.


Vertical midline or
upper horizontal or bilateral
subcostal incision
Stomach
Spleen
Accessory spleen
Mobilisation of greater omentum
Epiploic arcade retained
Pancreas
Right gastroepiploic artery (should be retained)
Colon
Epiploic arcade retained

Figs 19-44(1)


Short gastric vessels are ligated
Short gastric vessels are ligated
Short gastric vessels are ligated
Gastrohepatic ligament is dissected. Aberrant hepatic artery when present should be retained
Hiatal mobilisation
Epiploic arcade
Left gastroepiploic artery is ligated

Figs 19-44(2)


Hiatal dissection
Gastrohepatic dissection
Left gastric vessels ligation
Artery and vein (caudal-coronary)
are often individually ligated
Here mass ligation is done
Transfixation is better always
Dissected hiatus
Vagus nerve

Figs 19-44(3)


Pyloromyotomy/
pyloroplasty site
Pyloromyotomy is commonly done
Here pyloroplasty is done
Heineke Mikulicz pyloroplasty is done
Heineke Mikulicz pyloroplasty is done

Figs 19-44(4)



Heineke Mikulicz pyloroplasty is done

Stay suture on the gastric anterior wall as identification marker

Left sided oblique neck incision along the margin of sternocleidomastoid

Sternocleidomastoid muscle is retracted laterally with carotid sheath. Medially ideally finger retraction should be done. Here gentle instrument retraction is done

Trachea and groove is retraced to identify oesophagus

RLN should be safeguarded both sides. Inferior thyroid artery usually needs ligation

Oesophagus is held with Babcock's

Prevertebral space is dissected carefully; Care is taken not to injure RLN

Prevertebral space is dissected carefully; Care is taken not to injure RLN

Prevertebral space is dissected carefully; Care is taken not to injure RLN

Oesophagus is gently hooked

Sling is passed around the oesophagus

Figs 19-44(5)



Sling is passed around the oesophagus

Mobilisation of thoracic oesophagus by finger dissection from below and from above; traction should be given to sling

Usually oesophagus once mobilised is retrieved through laparotomy wound below. Here oesophagus with growth is brought out through the neck wound

Usually oesophagus once mobilised is retrieved through laparotomy wound below. Here oesophagus with growth is brought out through the neck wound

Figs 19-44(6)


Occlusion clamp is applied just below the OG junction
Stay sutures are placed; clamps applied to transect the oesophagus
Oesophagus is transected between clamps
Posterior interrupted sutures are placed between oesophagus and gastric fundus
Kocher's clamp applied on to oesophagus
Dividing the proximal oesophagus

Figs 19-44(7)


Gastric lumen
Cervical oesophageal lumen

Completion of the division

Posterior 2nd layer suturing

Posterior 2nd layer suturing full thickness interrupted sutures

Completion of posterior 2nd layer - full thickness

Nasogastric tube is negotiated across the stoma; it is often done after completion of the anastomosis by milking to keep the field sterile

Figs 19-44(8)



Anterior interrupted full thickness suturing is done

Anterior interrupted full thickness suturing is done

4th layer anterior outer interrupted sutures are placed to invaginate 3rd layer

Completed final outer anterior layer

Gently negotiating the stoma under the muscle

Figs 19-44(9)


Oesophageal specimen with growth
Closure of neck wound with a drain - optional - ideally tube drain
Laparotomy wound is closed after doing a jejunostomy

Figs 19-44(10)

Figs 19-44 (1 to 10): Technique of transthoracic blunt oesophagectomy with cervical oesophagogastric anastomosis.

Recurrent laryngeal nerve injury (5%) can occur while dissecting in the neck. Metallic retractor medially over the tracheooesophageal groove should be better avoided. Finger retraction is better.

Sepsis, empyema, mediastinitis, bronchopneumonia, ARDS are other complications.

Anastomotic stricture (3%) is not uncommon. It needs regular dilatation. Regurgitation, dumping, post-vagotomy diarrhoea are also common (17%). More frequent food of less quantity, sleeping in upright position, prokinetic drugs are beneficial.

Delayed gastric emptying may be due to pyloric obstruction, obstruction at hiatal level or redundant intrathoracic stomach (retort-shaped stomach into right thorax) lying in the posterior costophrenic gutter. Proper on table pyloromyotomy, 3 fingers hiatal width prevents this. Additionally prokinetic drugs and often dilatations are beneficial.

Survival rate for carcinoma after transhiatal oesophagectomy is 51% in 2 years and 29% in 5 years. It is comparable with the results of radical oesophagectomy and lymph node dissection.

IVOR LEWIS OPERATION (LEWIS-TANNER)

In 1946, Ivor Lewis (Tanner, 1947) described this procedure. Laparotomy is done. Tumour staging is done to mobilise stomach and stage the disease; right thoracotomy is done; tumour with part of oesophagus and stomach is resected; oesophagogastric anastomosis is done in the thorax. Technique involves coeliac node as well as adjacent thoracic node clearance. Original Ivor Lewis approach is initial laparotomy in supine position; repositioning into right thoracotomy position for thoracic dissection. Now commonly it is modified as synchronous combined abdominothoracic oesophagectomy without altering the position to approach abdomen and thorax. But finally it is surgeon's comfort and preference.

Patient is placed in semidecubitous position with right side upwards; it makes both abdominal and right posterolateral thoracotomy feasible without changing the position in the middle of the operation. Often midline incision is made in supine position; once initial abdominal part is over patient is positioned in right up position.

General anaesthesia with double lumen endotracheal tube is placed. Cleaning is done from neck along the right chest wall area up to pubic symphysis including entire abdomen. Draping is done. Head should be turned towards opposite side and right side neck should also be prepared so when need arises anastomosis can be done in the right side neck.

Once through upper midline incision exploration confirms the operability per abdomen thoracotomy is done in right posterolateral 4th intercostal space. Then abdominal mobilisation and thoracic mobilisation of the oesophagus is done **(Fig. 19-45)**.


Upper midline incision
Right 4th intercostal space posterolateral thoracotomy
Patient with semidecubitus position with hip rotated
Thyrocervical trunk
Subclavian artery
Internal mammary artery
1st
2nd
3rd
Right posterolateral thoracotomy
4th
5th
6th
Upper midline incision

Fig. 19-45: Incision for Ivor Lewis operation.

Abdominal Mobilisation

Self-retaining retractor is placed. Abdomen is explored for secondaries in liver and lymph nodes. Once operability is confirmed, left triangular ligament is divided to retract left lobe of the liver. Phrenooesophageal ligament and peritoneum is incised horizontally and OG junction is mobilised circumferentially with creation of retrooesophagus window. Gastrohepatic ligament is incised; accessory hepatic artery is ligated and divided. Left aberrant hepatic artery which originates from left gastric artery should be suspected if artery is wider than 5 mm and it may be supplying exclusively left lobe of the liver; if suspected it should be isolated, dissected and preserved. Greater omentum is divided. Short gastric vessels are ligated and divided. Energy sources are better for this. Left gastric artery is ligated at its origin to include the fat and lymph nodes. It is double securely ligated. Left gastric vein is also ligated separately (it is coronary vein and is caudal to artery). Right gastroepiploic and right gastric vessels should be preserved carefully. Bilateral truncal vagotomy is done. Dissection along the greater curvature should be done outside the gastroepiploic arcade and arcade should not get injured. Duodenum is mobilised up to its 3rd part by Kocherisation. Duodenal ligament between the posterior part of the duodenum to Gerota's fascia laterally is a ligamentous structure needs to be divided during Kocherisation. Care should be taken not to injure the superior mesenteric vein while mobilising the 3rd part of the duodenum as traction injury can occur. Heineke Mikulicz pyloroplasty or pyloromyotomy (circular muscle is cut using no. 15 blade) is done. Often stay suture is placed on the anterior part of the stomach to avoid rotation while pulling the stomach into the thorax. Hiatus may be widened by cutting it transversely using cautery.

Thoracic Mobilisation

Right posterolateral thoracotomy is done through 4th or 5th intercostal space. In females incision is made through inframammary crease. Pectoralis major and serratus anterior muscles are cut using cautery along the 4th space. Intercostal muscles are cut adjacent to upper border of 5th rib in the lower part of 4th space to avoid injury to intercostal vessels. Internal mammary artery near the sternal margin is identified, doubly ligated and divided. Pleura is opened. 4th rib near its sternal end is cut using bone cutter. Intercostal vessels at its lower margin is ligated and divided. Finochietto retractor is used to retract the ribs and so to expose the thoracic cavity. Usually wet mops are placed under the blades of the retractor. If further retraction is needed 5th rib can be cut like 4th rib. Incision if needed can be extended posteriorly up to the paraspinal muscles. Thoracic cavity is explored for secondaries in the lung and nodes. Mediastinal pleura is incised longitudinally on the surface of the oesophagus. Nasogastric tube facilitates identification of the oesophagus. Endoscopy on table may be useful to identify the oesophagus or to improve the dissection. At one point oesophagus is mobilised circumferentially with sharp and blunt dissection; it is encircled with a sling (or umbilical tape or infant feeding tube). Sling is used as a traction to proceed with further mobilisation of the oesophagus. Oesophagus is mobilised below up to the hiatus through which finger can be passed easily as hiatus below is already dissected. Upwards dissection is done behind the tracheal carina. Small arterial branches entering are divided between ligatures or haemoclips or harmonic scalpel can be used. Monopolar cautery is usually avoided; but bipolar cautery is quite useful. Azygos vein is visible on the right side which is arching above towards the superior vena cava. Azygos vein is doubly ligated (two on each side) at the beginning where it arches. Double ligation is needed. Care should be taken not to injure the superior vena cava. Vascular stapler can be used for the same. Often azygos vein is ligated at the level of hemiazygos vein (T8) especially if oesophageal transection is being done at lower level. It is better if possible to ligate the thoracic duct at this level to avoid its injury and leak. Fat, lymph nodes and adjacent tissues are dissected which should be included in the oesophageal specimen. Oesophagus is mobilized from thoracic aorta. All small vessels are ligated or fulgarated using bipolar or by harmonic scalpel. Proximal mobilisation should be 10 cm from the upper margin of the gross tumour. Mobilised stomach is passed through the widened hiatus into the thoracic cavity. Rotation of the stomach should be avoided by identifying the stay suture. Stomach just beyond the OG junction along the lesser curve is divided using stapler. Otherwise transection is done in between two occlusion clamps and stomach side is closed with two layer sutures (inner continuous 2 zero vicryl sutures; outer interrupted 2 zero silk sutures). 10 cm proximal to the tumour oesophagus is transected between clamps; specimen is removed. Proximal margin should be sent for frozen section biopsy.

Oesophagogastric Anastomosis

On the anterior wall of the mobilised stomach just distal to the sutured/stapled line 1.5 cm width circular stomach wall is excised; alternatively just 1.5 cm horizontal/vertical incision is also sufficient instead of circular tissue removal. It is said that circular piece of stomach wall removal prevents anastomotic stricture formation but that is not proved; so it is of surgeon's preference. Oesophageal cut end is made oblique for anastomosis. Outer layer suturing is done using interrupted 2 or 3 zero silk sutures taking bite from seromuscular layers of stomach and muscular layer of oesophagus (Once posterior outer layer suturing is over if stomach is not yet incised or circular piece is not removed, then an incision is made over the anterior wall of the stomach 2 cm below the transected part of the stomach). Inner all layer full thickness bite taken from the stomach wall; bite is taken from the mucosa and submucosa of the oesophagus (often muscular layer bite is also taken) using 2 or 3 zero silk or vicryl. Knots can be placed inside. Similarly anterior inner layer interrupted sutures are placed with knots inside. Sutures should be placed for every 3 mm width with bite point at 3 mm from the cut edge. After that anterior outer layer sutures are placed as interrupted seromuscular sutures. As oesophagus is cut obliquely with anterior edge lengthier (1 cm) than posterior edge, anastomosis becomes tension free **(Fig. 19-46)**.

In another method: OG junction is transected using stapler or between clamps and sutured. Stomach is pulled upwards into the right thoracic cavity across the widened hiatus. Mobilised oesophagus with tumour is held upwards; two stay sutures using 3 zero silk are placed between oesophagus 10 cm proximal to the upper margin of the tumour and 5-6 cm below uppermost part of the mobilised anterior wall of the stomach. Posterior interrupted sutures are placed between seromuscular stomach wall and muscular oesophageal wall. Posterior wall of the oesophagus is cut 5-6 mm distal to the sutured layer using 15 no. blade to identify nasogastric tube and mucosa. Incision (full thickness) over the stomach is made similarly distal to posterior layer; bleeding edges can be suture ligated or cauterised using bipolar cautery. Posterior mucosal layers of the oesophagus and stomach taking proper bites including submucosa at 3 mm intervals and 3 mm distant from the cut edges of stomach and oesophagus. Knots are tied inside the lumen. This layer is usually interrupted sutures but continuous


Tumour
OG junction transected with stapler
Pyloromyotomy
Proximal 10 cm margin
Interrupted outer silk sutures placed between stomach (seromuscular) and oesophagus (muscular)
5 cm distal to transected OG junction
Proximal 10 cm
Diaphragm
Incision is made on the oesophagus
Incision (horizontal) on stomach
Posterior inner interrupted mucosal sutures using 3 zero vicryl/PDS/silk with knots inside
Stay suture
Stay suture
Specimen with tumour and oesophagus cleared margins
Anterior inner mucosal interrupted sutures are placed using PDS/vicryl/silk 3 zero suture material
Posterior outer seromuscular of stomach and muscular of oesophagus interrupted sutures are placed using silk
Stay suture
Stay suture
Stay suture
Stay suture

Fig. 19-46: Oesophagogastric anastomosis in thorax in Ivor Lewis operation.

suture is also can be placed. Anterior wall of the oesophagus is cut 1 cm distal to the level of posterior wall to retrieve the specimen. Anterior mucosal layers are sutured similarly with knots tied inside the lumen. Anterior layers (seromuscular) of stomach and of oesophagus (muscular) are finally sutured with interrupted sutures.

Note: Anastomosis can also be done using stapler.

Stomach is fixed to prevertebral fascia with interrupted sutures to prevent tension over the anastomosis. Omentum may be tagged over the anastomotic site. Hiatus should be 3 fingers wide. Hiatus is fixed to the stomach using few interrupted silk sutures. Jejunostomy is done 15 cm from the ligament of Treitz.

Intercostal tube is placed into the thoracic cavity. Thoracotomy is closed in layers. Abdomen is also closed in layers with or without tube drain **(Fig. 19-47)**.

Postoperative Care

Nasogastric tube should be kept in situ for 5-7 days. Chest tube is removed once adequate lung expansion has occurred which is confirmed by chest X-ray and pleural drain is less than 100 ml/day.

Complications

Anastomotic leak is dangerous as anastomosis is in the thorax.
Bleeding can occur; but usually subsides.
Respiratory distress, pneumonia, cardiac arrhythmias, DVT are other problems.
Stenosis of the anastomosis can occur which often needs repeated oesophageal dilatation using bougies (Maloney's).
Subphrenic abscess can occur which is diagnosed by CT scan. Guided tube drainage or open drainage may be needed.



Fig. 19-47: Oesophagectomy specimen after resection.

Respiratory physiotherapy, prevention of deep vein thrombosis and sepsis control should be done. Oral sips started once nasogastric tube is removed. Normal diet is started in 10-14 days.

LEFT THORACOABDOMINAL APPROACH OESOPHAGOGASTRECTOMY (CHURCHILL AND SWEET, 1942)

It is done only if growth is in OG junction. Much proximal tumour is difficult approach through this as access is difficult. Phrenic nerve injury is a possible complication when diaphragm is cut radially and it may lead into diaphragmatic paralysis.

Double lumen endotracheal tube is used for general anaesthesia. Left side of the patient is upwards 60°-90° with right arm is straight in the arm board and left arm is suspended above towards head away from surgical field. Patient is supported with sandbags or supportive frames **(Figs 19-48 and 19-49)**.



Fig. 19-48: Incision for left thoracoabdominal approach.



Fig. 19-49: Abdominothoracic (left) approach for OG junction or lowermost oesophageal carcinoma.

Technique

Incision can be either upper midline incision which is extended over the thorax or oblique incision between xiphoid and umbilicus extending towards left into the thoracic cage. First abdomen is opened; explored for operability/secondaries/lymph node and peritoneal status. Once operable incision is extended across the 6th intercostal space upwards and posteriorly towards scapula and erector spinae. Latissimus dorsi and serratus anterior are cut. Scapula is retracted upwards. Intercostal muscles are cut on the upper part of 7th rib. Pleura is opened. Costal margins are divided using heavy scissor or bone cutter or 22 no. blade. Internal mammary artery may require to be ligated. Diaphragm should not be incised radially even though it is technically looks easier as phrenic nerve may get injured. It should be incised circumferentially (*Merendino and associates safe zones*, 1956). Incision is made in a line 3 cm from the rib margin parallel to it for 15 cm length **(Fig. 19-50)**.

Inferior pulmonary ligament is cut using long scissor or cautery; above up to inferior pulmonary vein. Mediastinal pleura is incised longitudinally from the thoracic descending aorta. Both vagi are cut



Fig. 19-50: Incision placed in diaphragm – safe zones (*Merendino and associates safe zones*)

high up below the level of lung hilum. Arterial branches entering the oesophagus are fulgarated using harmonic or bipolar cautery or ligated or occluded with haemoclips.

OG junction along the hiatus, lower oesophagus, stomach is mobilised through the abdominal wound same way like for other oesophagectomy (refer above). Gastroepiploic arcade should be retained along the greater curvature of the stomach while dividing the greater omentum; around 5 cm of redundant omentum should be attached to the stomach towards duodenal side. Right gastric and right gastroepiploic vessels are preserved. Kocherisation, hiatal dissection, ligation of left gastric vein (coronary vein – it is caudal to left gastric artery), left gastric artery, left gastroepiploic artery, accessory left hepatic artery are ligated securely to mobilise proximal stomach behind. Left gastric artery needs double ligation. Lymph nodes, fat should be cleared. Splenectomy may be done if needed. Pyloromyotomy is done. Oesophagus is transected using stapler 10 cm proximal to tumour; stomach is also transected 5 cm distal to the OG junction or the tumour (if tumour is extending into the stomach). Specimen is removed through the abdominal wound.

Crus of the diaphragm is cut if needed to widen the hiatus to prevent venous congestion of the pulled up mobilised stomach. Stomach is pulled across the hiatus up into the thoracic cavity. Anastomosis is done between the end of the oesophagus and anterior wall of the stomach as two layers. Posterior wall of the stomach may be fixed to the prevertebral fascia and hiatus using interrupted nonabsorbable sutures to stabilise the gastric pouch.

Abdomen is closed in layers. Intercostal tube is placed. Diaphragm is closed using interrupted horizontal mattress 1 zero polypropylene sutures. Second continuous suture layer may be added to this. Thoracotomy is also closed in layers.

Postoperative Care

Intercostal tube is removed once lung has expanded fully in 5-7 days. Respiratory physiotherapy, antibiotics, observation are done regularly. Nasogastric tube is removed in 7 days. Oral sips started later. Often contrast study is done to confirm the adequacy of the stoma.

Complications

Respiratory complications, anastomotic leak, infection, subphrenic abscess formation, stenosis of the stoma, paralysis of the diaphragm are the complications.

MCKEOWN THREE PHASE OESOPHAGECTOMY WITH LYMPHADENECTOMY (1972)

McKeown modified Ivor Lewis technique by mobilising the entire oesophagus through abdominal and right thoracotomy approach and with right cervical approach cervical oesophagogastric anastomosis is done in the right side neck.

Under double lumen endotracheal intubation general anaesthesia procedure is done. Original McKeown procedure was abdominal/thoracic one after another with change positions each time; then right sided neck approach for anastomosis. Now synchronized abdominal, thoracic and neck approaches are used even though technique is of three phases. Cleaning and draping is done exposing abdomen, thorax and right sided neck. In further modifications, often left side neck is used for cervical dissection of the oesophagus instead of original McKeown right sided approach.

First right anterolateral thoracotomy is done using submammary crease incision with 4th intercostal space approach. Many advocate first abdominal approach and the thoracic. It is essentially surgeon's choice. But operability can be initially well assessed through thoracotomy approach and then when tumour is above the lower 1/3rd oesophagus. After thoracotomy with rib resections and retraction, cavity is explored for metastases. Tumour is assessed for operability and nodal involvement. Incision is made on the mediastinal pleura. Oesophagus is mobilized with lymph nodes. Oesophageal branches are ligated or clipped and divided. Azgos vein is ligated at its arch level (four ligatures; divided between two ligatures each side). Different lymph nodes are carefully dissected and involved in the specimen. Bronchial artery is safeguarded.

Using upper midline incision laparotomy is done. Left triangular ligament is cut. Phrenooesophageal membrane is incised. Gastrohepatic ligament is divided. Retrooesophageal window is created. Short gastric vessels are ligated. Left gastroepiploic vessels are ligated and divided. Left gastric artery is ligated near its origin. Left gastric vein is ligated separately and divided which is caudal to artery (coronary vein). Nodes at this level are cleared. Right gastric and right gastroepiploic vessels are safeguarded. Gastroepiploic arcade is retained without traumatising it. Kocherisation is done to mobilize the duodenum. Pyloromyotomy is done. Oesophageal hiatus is widened adequately and hiatal dissection is done to communicate towards already dissected thoracic oesophagus.

Cervical dissection is carried out with oblique incision along the anterior border of the sternocleidomastoid muscle. Cosmetic horizontal incision also can be used. Deep fascia is incised. Carotid sheath is identified. Sternomastoid with carotid is retracted laterally. Omohyoid is divided using cautery. Thyroid with trachea is retracted medially using finger as retractor (assistant's finger). Inferior thyroid artery may require to be ligated. Oesophagus is identified by feeling the nasogastric tube inside. Oesophagus is dissected of from the prevertebral fascia using finger dissection. In front care should be taken not injure recurrent laryngeal nerves of both sides while hooking the oesophagus using finger. Oesophagus is slinged with infant feeding tube or umbilical tape or Penrose drain. Dissection is carried towards mediastinum with sharp and blunt methods to reach the thoracic dissection.

Oesophagus is transected 5 cm below the cricopharyngeus muscle using stapler. Specimen is removed through the thoracic cavity after stapling at 2 cm beyond the OG junction along the lesser curvature using stapler. Stapler line in the stomach is oversewn using continuous 3 zero vicryl sutures. Gastric conduit is gently pushed towards neck wound without causing any twist. Oesophageal proximal end is anastomosed to the anterior wall of the stomach with two layer interrupted anastomosis 3-5 cm distal to the tip of the gastric conduit.

Thoracotomy is closed after placing a chest tube. Abdomen is closed. Neck wound is closed with a suction drain.

Postoperative Care

It is same as in other oesophagectomies – chest tube care, nasogastric tube care, and observation for bleeding, leak and sepsis and respiratory problems. Chest tube, drain and nasogastric tubes are removed in 5-7 days.

Complications

Bleeding, leak, thoracic duct injury, gastric conduit problems, recurrent laryngeal injuries, tracheal injury, anastomotic stenosis – can occur.

EN BLOC RESECTION OF OESOPHAGUS (SKINNER, 1983)

It is en bloc resection of oesophageal carcinoma (radical oesophagectomy) with 10 cm proximal and distal clearance with removal of perioesophageal tissues, lymphatics, vessels of the oesophagus, azygos vein, bilateral pleural surfaces, pericardium anteriorly (partial removal), thoracic duct, cuff of the diaphragm, upper mediastinal and abdominal lymphadenectomy.

Laparotomy and right or left (for lower oesophagus) 6th intercostal space thoracotomy is done. Diaphragm is incised in safe area as phrenotomy. Abdominal oesophagus and coeliac nodal areas can be approached by large semilunar diaphragmatic division without doing laparotomy. All retroperitoneal tissues cephalad to pancreas including splenic and hepatic lymph nodes along with gastric nodes are dissected. OG junction is mobilised like usual oesophagectomy. Cuff of the diaphragmatic muscle is included in the oesophageal specimen. After en bloc resection, for lower oesophageal carcinoma, anastomosis is done above the aortic arch level. Thoracic duct is ligated just above the aortic hiatus through which it emerges from the abdomen.

In proximal (middle and upper) tumours, pleura is incised in superior mediastinum in front along the tracheooesophageal groove. Recurrent laryngeal nerves should be preserved. Oesophagus is dissected of the membranous trachea from thoracic inlet to carina. Azygos vein is ligated flush with the superior vena cava. Subcarinal lymph nodes are dissected. Posterior part of the pericardium is exposed. Pericardium is incised from superior pulmonary vein sleeve to inferior pulmonary vein sleeve. Pericardium is incised transversely to remove oval part of it. Bronchooesophageal arteries are ligated. Incision is extended in front of the aorta onto the left pleural cavity. Left pleura incised and included in the specimen.

In lower oesophageal tumour anastomosis is done in thoracic cavity in the pleural space or posterior mediastinum. In upper and middle tumours anastomosis is done in the right or left side of the neck. Approach and technique is similar as mentioned earlier. Neck nodes are cleared usually in en bloc dissection.

Patient often requires blood transfusions.

Postoperative care and complications

Respiratory care, intensive care is needed for 72 hours. Chest tube is removed once fluid quantity reduces less than 100 ml/day. Leak, pneumonia, mediastinitis lymph leak and cardiac arrhythmias are to be anticipated. Usual hospitalisation period is 14 days.

THREE FIELD LYMPHADENECTOMY FOR OESOPHAGEAL CARCINOMA

Forty per cent of upper 1/3rd tumours, 20% of lower 1/3rd tumours involve cervical nodes. Mucosal lesion has got 30% chances of nodal spread; submucosal has 50%; muscularis propria 60%; muscular and perioesophageal involvement has got 80% chances of nodal disease. Commonly nodes along the recurrent laryngeal nerves and behind the internal jugular vein are involved. Supraclavicular nodes when involved has got worse outcome. Its benefit over two field lymphadenectomy is controversial **(Fig. 19-51)**.



Usually only right 5th space thoracotomy with peripheral semilunar diaphragmatic phrenotomy and U shaped neck incision with manubrium split incision is used

Fig. 19-51: Incision for three field dissection.

Thorax and abdomen can be approached by right 6th space thoracotomy with large semilunar incision over the diaphragm. It is only optional not a mandatory to do laparotomy as once phrenotomy is done, abdomen can be approached comfortably through thorax.

First field - In the abdomen, coeliac, renal, superior mesenteric, hepatic, splenic, gastric nodes are dissected along with the mobilisation of the abdominal oesophagus, and ligation of left gastric and left gastroepiploic vessels retaining gastroepiploic arcade. Parahiatal nodes are also cleared. 2 cm distal to OG junction lesser curve is transected using stapler and stapler line is buried using continuous vicryl/silk seromuscular sutures. Kocherisation, pyloromyotomy is added. Gastric conduit is pushed into the thorax.

Second field - In the chest, posterior mediastinectomy is done to clear perioesophageal nodes, subcarinal nodes, nodes along the main bronchus, thoracic duct and azygos vein. Prevertebral and retrotracheal dissection is done to include further paratracheal nodes. Left recurrent laryngeal nerve is identified near its origin at the level of the aortic arch and dissected towards the neck; right recurrent laryngeal nerve is dissected at a place where it loops around the right subclavian artery with clearing the recurrent nodes adjacent to its superior mediastinal component (even though recurrent nodes are continuous chain nodes along the course recurrent laryngeal nerve in the mediastinum and neck, it is often classified as cervical and superior mediastinal components). Gastric conduit is pushed towards the thoracic inlet to reach neck for cervical oesophagogastric anastomosis.

Third field – U shaped neck incision is made with manubrium split to facilitate lower neck and superior mediastinal nodes properly. Brachiocephalic nodes, nodes lateral and posterior to carotid sheath, supraclavicular nodes and cervical recurrent nodes bilaterally are cleared with this approach **(Fig. 19-52)**.



Fig. 19-52: Configuration of neck nodes in 3 field neck node dissection.

Anastomosis is done in the neck. Diaphragm is sutured using nonabsorbable horizontal interrupted mattress sutures often with two layers. Thoracotomy is closed after placing bilateral chest tubes.

Problems

Delayed postoperative recovery, long hospital stay, sepsis, respiratory complications, recurrent laryngeal nerve palsy (10-50%), need for tracheostomy often, leak and lymph ooze are the problems. Mortality is 1-10%.

MINIMALLY INVASIVE SURGERY FOR CARCINOMA OF OESOPHAGUS (VIDEO ASSISTED APPROACHES)

In 1996 DePaula did laparoscopic transhiatal oesophagectomy and reported a series of 48 patients. Later Luketich and Cuschieri described thoracolaparoscopic oesophagectomy.

Procedure is done in different positions. Initially thoracoscopic procedure is done to mobilise the oesophagus and to complete lymphadenectomy in the mediastinum. This is done in lateral decubitus position or in prone position also. Infracarinal and supracarinal lymph nodes are included in the specimen as part of lymphadenectomy – paraoesophageal, bronchopulmonary, subcarinal, tracheobronchial, recurrent and paratracheal nodes are dissected carefully. Later in supine position, laparoscopic mobilisation of the stomach and abdominal oesophagus is done. Gastric conduit is created using endostapler. Gastric tube is pulled into the cervical incision after placing a nasogastric tube into the peritoneal cavity and fixing to gastric conduit through a minilaparotomy. Specimen is removed through the minilaparotomy; gastric conduit is pulled up. Cervical oesophagogastric anastomosis is done.

Laparoscopic and thoracoscopic intrathoracic oesophagogastric anastomosis also can be done in lower oesophageal carcinomas.

Problems and complications are similar to open surgery. *Advantages are* – better visualisation and dissection, avoiding thoracotomy, faster recovery. *Disadvantages are* – technical expertise, learning curve, availability, cost, prolonged anaesthesia.

COMPLICATIONS AFTER OESOPHAGEAL RESECTION

Complications after resection of the oesophagus for carcinoma (commonly) are intraoperative, early or delayed/late (after 30 days) postoperative. It can be major or minor complications.

Intraoperative	*Early*	*Delayed/Late*
Injury to lungs, pericardium Azygos vein bleeding Injury to spleen, coeliac artery Injury to thoracic duct Injury to tracheal membrane	Abdominal bleeding – intraabdominal Gastrointestinal bleeding Respiratory complications like ARDS, pneumonia, collapse of lung Chylothorax, haemothorax, empyema Mediastinitis Cardiac complications Bowel ischaemia, bowel obstruction Anastomotic leak Recurrent laryngeal nerve palsy Subphrenic/ intrathoracic abscess DVT, pulmonary embolism Wound infections	Anastomotic stricture Delayed gastric emptying Internal diaphragmatic herniation through the hiatus

Anastomotic leak

It is the most problematic complication. It is around 14%. Leak may be into the neck wound or into the thorax. Leak into neck wound is safer and is usually resolves by conservative therapy. Leak into the thoracic cavity is life threatening. It needs immediate thoracotomy. Small leak can be closed. Gastric conduit can be drained by placing a T tube. Large leak needs repositioning of the gastric conduit into the abdominal cavity. Temporary oesophageal diversion is done in the neck as oesophagostomy. Later if patient recovers from acute shock and its problems, elective diversion using colon can be done. Leak often may be from the staple line placed along the lesser curvature. It is usually into the thorax. Management is similar to anastomotic leak. Leak also can occur from pyloroplasty or pyloromyotomy. It is usually into the abdominal cavity. It needs redoing of the pyloroplasty through relaparotomy. Site of leak is confirmed by water contrast dye study. Contrast CT is also helpful.

Tracheal membrane tear

Tracheal membrane tear is another complication which is often very difficult to manage with high mortality. Small tear is sutured using nonabsorbable interrupted sutures (polypropylene). Large tear is difficult to tackle. It is managed by anterior mediastinal tracheostomy with resection of clavicle and manubrium and half of first rib (anterior breast plate resection). Supportive pectoralis major muscle flap or intercostal muscle flap is also needed around tracheostomy.

Major complications	*Minor complications*
Anastomotic leak	Atelectasis of lung
Tracheal membrane tear	Problems of feeding jejunostomy
Cardiac complications	Wound infection
Gastric conduit necrosis	Urinary retention
Recurrent laryngeal nerve injury	Paralytic ileus
Delayed gastric emptying	
Respiratory complications	
Chylothorax	
Pancreatitis, mediastinitis, septicaemia	
Intracavitary abscess formation	
Deep vein thrombosis	
Renal failure	

OESOPHAGEAL SUBSTITUTES

Oesophageal substitute is the one which is used as an interposed functioning bowel tube between the proximal normal oesophagus in the neck or thorax and stomach in the abdomen. It can be used after removal of thoracic oesophagus in its entirety or partly ***(oesophageal replacement***); in this type, oesophagus is placed in the same or similar place after oesophagectomy. Or often diseased oesophagus is retained as in advanced carcinoma oesophagus or in adherent multiple strictures which is difficult to dissect safely; in this type it is used as ***oesophageal bypass*** through different routes commonly retrosternal. Usually stomach, colon, jejunum are used. Occasionally local flaps (myocutaneous or free flaps) may be used for cervical oesophagus along with pharynx.

When oesophagus is excluded and gastric conduit is used as bypass, oesophagus should be drained to prevent abscess or mucocele formation or blow out of the distended oesophagus. It is done by doing oesophagojejunostomy or proximal end of the excluded oesophagus is brought out as tube oesophagostomy. If there is a broncho or tracheooesophageal fistula (in malignancy or other causes), then excluded oesophagus can be left alone as fistula drains into the respiratory tract functioning as pseudodiverticulum.

Transposition Routes

Transposition is done through posterior mediastinum (*shortest route*), right pleural space (transpleural), retrosternal or subcutaneous route.

Posterior mediastinal route is ideal if oesophagectomy has been done prior to transposition. Otherwise it is not useful as a bypass route for cancer cases with inoperable tumour or in strictured oesophagus. It has got shortest distant between neck and abdomen.

Transpleural route is easier; but can cause gastric or colonic distension due to negative thoracic pressure. It is often used after thoracic oesophagectomy. It is not ideal for bypass substitute as thoracotomy is required.

Retrosternal route is through anterior mediastinum behind the sternum across its entire length. Length of this route is longer than posterior mediastinal route; but gastric or colonic conduits can be bridged across without any tension in this route. This is commonly used bypass route when oesophagus is not removed. It is anatomically separated from the oesophageal tumour and so bypass conduit will not get involved by tumour. Oesophagus in the neck is mobilsed like other similar procedure. Anterior fibres of the diaphragm are detached from the xiphoid process to access the retrosternal plane. Tunnel is created by passing fingers from below and from above by blunt dissection. It is avascular plane and hence bleeding is not common. Conduit is pushed gently upwards using hand and fingers; instrument pull should

Approaches for Different Level Tumours

Post cricoid tumour (Squamous cell carcinoma):
Treated mainly by radiotherapy. Radical radiotherapy— 5000-6000 rads. Often pharyngolaryngectomy is done along with gastric or colonic transposition. But complications are more in this procedure. Free jejunal transfer is the other option.

Upper third growth (Squamous cell carcinoma):
It is treated mainly by radiotherapy. Commonly it is advanced with left recurrent laryngeal nerve palsy and bronchial invasion. If it is early and operable, *McKeown three phased oesophagectomy* and anastomosis is done in the neck. Initially thoracotomy through right 5th space is done and oesophagus is mobilised. Then laparotomy is done to mobilise the stomach. Through right side neck approach, oesophagus with growth is removed. Anastomosis between pharynx and stomach is done in the neck.

Split sternum approach oesophagectomy is also practiced.

*Middle third growth (Squamous cell carcinoma)***:**
Ivor Lewis operation (Lewis-Tanner two-phased oesophagectomy): After laparotomy stomach is mobilised. Pyloroplasty is done. Through right 5th space thoracotomy is done and growth with tumour is mobilised. Partial oesophagectomy and oesophagogastric anastomosis is done in the thorax. Intercostal tube drainage is placed during closure. Right gastroepiploic vessels/epiploic arcade should be retained safely (essential). Azygos vein should be ligated securely. Mediastinal nodes should be dissected. Thoracic duct should be ligated if needed just above the aortic hiatus where it enters the thorax. Feeding jejunostomy is better to maintain nutrition. If the growth is inoperable, palliative radiotherapy is given.

Lower third growth (Squamous cell carcinoma + adenocarcinoma):
Here through left thoracoabdominal approach, partial oesophagogastrectomy is done with oesophagogastric anastomosis. Often jejunal Roux-en-Y loop anastomosis is done. *Orringer approach*, i.e. *transhiatal blind/ blunt total oesophagectomy* with anastomosis in the left side of the neck. Through laparotomy, stomach and lower part of the oesophagus are mobilised. Through left sided neck approach, upper part of the oesophagus is mobilised using finger. Blind dissection is completed by meeting both fingers above and below in the thorax. Later oesophagus is pulled up out above through the neck wound and removed. Continuity is maintained in the neck. It is a *palliative* surgery.

Other Approaches
Thoracoscopic-laparoscopic oesophagectomy and lymphadenectomy is becoming popular, safer and effective.

Radical oesophagectomy with 3-field clearance of abdominal/ thoracic and cervical nodes is also practiced in many centers. 3-Field clearance (coeliac, thoracic and neck) is done for mainly squamous cell carcinoma as spread here is upwards. In adenocarcinoma 2-field clearance is sufficient (abdominal—coeliac and thoracic) as spread is downwards.

Skinner en bloc resection used to be of practice in olden days in which tumour with oesophagus is resected along with thoracic duct, azygos vein, intercostal vessels crossing the vertebral bodies, pericardium and mediastinal pleura. There is no survival benefit with this procedure.

Vagal sparing oesophagectomy with HSV is tried to preserve pylorus functioning avoiding pyloroplasty to reduce the chances of postprandial fullness. But it is technically tedious.

Lymphadenectomy in carcinoma oesophagus: *Standard*: Nodes removed are—paratracheal, parabronchial, carinal, paraoesophageal, posterior mediastinal, paracardial, left gastric, along lesser curve of stomach. *Extended/three field/ultraradical*: As like standard above, with bilateral cervical lymphadenectomy, removal of upper mediastinal, coeliac, retroperitoneal, subhepatic nodes is done.

be avoided as it will damage the conduit. Often head of the clavicle, first rib and part of the manubrium is removed to widen the thoracic inlet. This reduces the compression over the conduit and maintains its blood supply optimally.

Subcutaneous route is done when all other routes are not possible to utilise. If patient has undergone prior open cardiac surgery then retrosternal route is not possible and subcutaneous route is used. It is technically easier but lengthier conduit is needed. It is antesternal route. Anastomosis takes up well; but conduit is visible on the chest wall **(Fig. 19-53)**.

Stomach (Gastric Conduit)

It is preferred one and is based on right gastric and right gastroepiploic arteries. It is the most commonly used oesophageal substitute at present. It needs only one anastomosis and take up is well due to good vascularity. But it can cause postprandial fullness with bile or acid regurgitation (> 50%). It also needs a pyloromyotomy/pyloroplasty for gastric drainage as vagotomy is done to prevent delayed gastric emptying. Entire stomach or tubed part or reverse tubed part can be transposed. Stomach has got lengthier gastroepiploic arcade closer to greater curvature which straightens when stomach becomes straight; it does not kink when moved/transposed unlike colon or jejunum (here fan-shaped mesentery kinks and get tensed when transposed). Colon after years gets dilated and becomes redundant leading into stasis improper emptying. Prior gastrostomy is not a contraindication for using stomach as conduit; gastrostomy feeding more with fluid dilates the stomach significantly making it as a better conduit. Site of the gastrostomy even though is not very important but preferred to place towards lesser curve side. Presence of gastric outlet obstruction or gastric resection or previous gastrojejunostomy makes it a relative *contraindication* for preparing it as a suitable conduit.

For bypass in an advanced carcinoma entire stomach is used without making tubes. Here OG junction is transected and entire stomach is mobilised as usual with retaining the gastroepiploic arcade with its blood supply from right gastroepiploic artery. Kocherisation, pyloromyotomy, ligation of left gastric and left gastroepiploic pedicle and short gastric vessels are done. Mobilised stomach is pushed upwards towards neck for anastomosis with the cervical oesophagus. **(Fig. 19-54)**



Fig. 19-53: Subcutaneous route - colon transposition.

For replacement tubed stomach is commonly used. It may be reversed gastric tube based on left gastroepiploic artery or non–reversed gastric tube based on right gastroepiploic artery. Greater omentum is dissected of from the transverse colon and from both flexures. Middle colic artery should be safeguarded. Short gastric vessels are ligated and divided. Splenectomy is usually not necessary. Left gastric vessels are ligated. OG junction is mobilised.

In reversed gastric tube, right gastroepiploic artery is ligated 4 cm from the pylorus. Double row stapling along the greater curvature at this point is applied transversely for 2.5 cm. Proximal stapling row is held and few staples adjacent to greater curvature is removed and 40 French rubber catheter is passed through this proximally along the greater curvature up to the fundus. Multiple staplers are fired parallel to the tube towards the fundus to create reversed gastric tube. Staple line is oversewn using continuous 3 zero silk sutures to bury the staple line. Tube placed should be loosely accommodated there. Omentum is wrapped around the gastric tube. Tube based on the left gastroepiploic artery is tunneled through posterior mediastinum if oesophagectomy is undertaken; otherwise under the xiphoid through retrosternal space if oesophagus is not removed (as bypass, where entire stomach is used without tube usually) and anastomosed in the neck to cervical oesophagus **(Fig. 19-55)**.

In nonreversed gastric tube, right gastroepiploic artery is used as base; here left gastroepiploic vessels, short gastric vessels and left gastric vessels are ligated. Pyloromyotomy is done; extended Kocherisation is needed. Circular stapler is fired 4 cm proximal to the pylorus to facilitate the passage of the consecutive series of stapler lines until the outer aspect of the fundus to create 2.5 cm diameter vascularised tube based on right gastroepiploic artery. Staple line is inverted with continuous seromuscular sutures. Omentum is wrapped around the gastric tube **(Fig. 19-56)**.

Advantages of gastric conduit – adequate length is available; good blood supply; good anastomotic take up; easier to mobilise.

Disadvantages of gastric conduit – need for pyloromyotomy/pyloroplasty; gastric conduit tip necrosis; anastomotic stricture; delayed gastric emptying.

Colon

Technique is more with the need of three anastomoses. Right colon is used with middle colic artery based as antiperistaltic loop. Left colon is used with ascending branch of left colic artery as isoperistaltic loop. Postprandial problems are les in colonic conduit compared to stomach. Colon is used as right/left/transverse segment depending on need and vasculature and preference. It can be isoperistaltic or antiperistaltic. When a short segment of colon is used it is called as *short segment colon in interposition (probably used in as pridge gap in localised)* benign diseases); total or subtotal oesophageal replacement is called as *long segment colon interposition* (in multiple strictures, carcinoma oesophagus). Colon behaves more or less as a passive conduit **(Fig. 19-57)**.

Colon functions as a passive conduit and empties much slower than oesophagus. Motility of the colon is of three types – *right sided retrograde annular contractions* which helps in fluid and electrolyte absorption; *annular contractions* of the transverse and descending


Left gastric artery
Short gastric vessels
Celiac trunk
Right gastric artery
Aorta
Gastroduodenal artery
Right gastroepiploic artery
Left gastroepiploic artery
Splenic artery
Transected OG junction
Entire stomach is used for transposition based on right gastroepiploic artery

Fig. 19-54: Gastric conduit using entire stomach.


Stomach with blood Supply
Ligation of right gastroepiploic artery. Stapled transection 2.5 cm of greater curvature 4 cm from the pylorus
Passing a rubber tube/catheter through stapled part along greater curvature towards fundus
Serial stapling along and parallel to the tube and greater curvature to create reversed gastric tube as substitution based on left gastroepiploic artery
Mobilised reverse gastric tube ready for transposition towards neck

Fig. 19-55: Gastric conduit – reversed type.


Oesophagus
Right gastroepiploic artery
Circular stapled defect created adjacent to pylorus
Serial stapling along greater curvature to create 2.5 cm width nonreverse gastric tube
Created nonreverse gastric tube conduit based on right gastroepiploic artery. Left gastroepiploic artery is ligated here.

Fig. 19-56: Gastric conduit – nonreversed type.


Marginal artery of Drummond (Sudeck's)
Middle colic artery
SMA
Arc of Riolan
Intermediate LN
Principal LN
Epicolic LN
Right colic artery
Paracolic LN
Sudeck's critical point
Ileocolic artery
Superior rectal artery
Inferior mesenteric artery

Fig. 19-57: Blood supply of colon.

colon which slowly propels faeces into the rectum; *strong propulsive contractions* of the distal colon into the rectum. So right side can be used as antiperistaltic; left side can be used as isoperistaltic. Arterial supply of the colon and venous drainage makes it more proficient to use as conduit for oesophagus. Ileocolic, right colic, middle colic (branches of superior mesenteric artery) and left colic artery and sigmoid branches supply the colon. Marginal artery connects branches of superior mesenteric and inferior mesenteric arteries. Marginal artery may be absent in 2% of individuals. Right colic artery may be absent in 12%; middle colic in 4% cases. Right (8%) and middle colic arteries (6%) or both (0.5%) may be multiple often. Atherosclerosis of the inferior mesenteric artery makes marginal artery poorer and unsuitable for colonic conduit. There is no marginal vein on the right side colon and it is said that anastomotic leak in 25% of right sided colonic conduit substitute is due to venous congestion rather than arterial. More commonly preferred one is left side colon. *Reasons are* – smaller diameter of left colon matches relatively to oesophagus; constant and reliable blood supply of the left side colon; ability to propel solid content – make left colon is the first option. Right side colon is used as a reserve if left side colon is not available or cannot be used.

Indications – Colon is used when stomach is not available or not suitable for replacement. It can be used as bypass in advanced carcinoma oesophagus. It is useful in multiple oesophageal strictures, oesophageal atresia if stomach is not adequate for replacement. It is also used in patients for resurgery with failed gastric conduits of any reasons.

Contraindications – Primary colonic disease; inadequate blood supply to the colon; short/fibrosed colonic mesentery. Prior colonoscopy may be a need.

Technique – Adequate large bowel reparation is needed. For replacement it can be combined with the oesophagectomy and same upper midline incision is used. Colon is mobilised adequately. Both flexures, colonic mesentery are mobilised. Colonic arterial arcade is inspected by transillumination. Integrity of colonic mesentery and length of the colon is assessed. Marker stitches are placed at the proposed line of the colonic resection.

For left sided isoperistaltic colonic conduit, descending branch of left colonic artery which is communicating into the sigmoid arteries is ligated away from the main left colic trunk. Length of the colon needed for transposition is measured using umbilical tape. Atraumatic clamps are applied to the marginal artery right of the left branch of the middle colic artery and middle colic artery itself. If left side colon maintains adequate blood supply which is confirmed by fluorescein angiography and Wood's light examination, marginal branch at right of the left branch of middle colic artery and left branch of middle colic artery are ligated **(Fig. 19-58)**.

Now left side colon is exclusively supplied by the left colic artery. Colon is transected at proposed level with retaining the marginal arterial arcade and left colic artery. Right side part of the conduit is passed behind the colon and stomach; then across the thorax by suitable decided route to reach the neck. If only bypass is done without prior oesophagectomy, similar neck incision is done to reach the oesophagus. Oesophagus is transected and anastomosed to the colonic conduit at proximal right side colon. Proximal cut end of the oesophagus is anastomosed to side of the colon in the neck as end to side. Distal part of the left side end of the colonic conduit is anastomosed to the posterior surface of the stomach as end to side (end of the colon to side of posterior wall of the stomach). Posterior surface of the stomach acts as antireflux support. Anastomosis can also be done on the anterior surface of the stomach. Vertical gastrotomy is done for anastomosis. Colonic continuity is maintained by colocolic anastomosis. Feeding jejunostomy is usually done.

In right sided antiperistaltic colonic transposition, right colon is made to perfuse by middle colic artery. After deciding the line of and length of the needed right sided colon, atraumatic clamps are placed on to the marginal arteries, ileocolic, right colic, terminal ileal vessels to confirm the adequacy of perfusion of the proposed conduit through the middle colic artery. Once perfusion is confirmed, these vessels are ligated, middle colic artery is safely and carefully retained to maintain the perfusion. Isolated colon is transected distally terminal ileum 10 cm proximal to ileocaecal junction is transected proximally. Appendicectomy is done. Ileum with caecal end is transposed towards the neck with specified route. Length required is 4 cm more if route used other than posterior mediastinum especially retrosternal or subcutaneous **(Fig. 19-59)**.

Now many advocate transection at caecal level retaining the ileum. Ileotransverse anastomosis is done to maintain the bowel continuity. Oesophagoileal/colic anastomosis is done in the neck between the end of the oesophagus to side of the colon/ileum. Below colon is anastomosed behind or front of the stomach.

Problems with colon substitute

Preoperative preparation of colon is more complex and demanding. Multiple anastomoses (3) are required; it is more risky as far as colon is considered. Necrosis and leak is potentially life threatening in colon. Colon has got poor acid resistance unlike jejunum. Tendency to dilate gradually and causing redundancy is a problem. Extremely slow emptying time is another problem. Food is retained in the colon conduit for long time without emptying into the stomach.

Complications

Complications of colonic substitute depends on the length of the segment and indication for colonic substitute. Complications



Left branch of middle colic artery and marginal arteries beyond marker stitches are ligated and divided. Isoperistaltic left colon is based on left colic artery for transposition

Fig. 19-58: Left sided colon transposition.



Right colic, ileocolic, marginal arteries (beyond marker stitches) are ligated and divided.
Right sided antiperistaltic colon is based on middle colic artery.
Appendicectomy is done.
Transposition is done with ileum towards proximal neck to anastomose into cervical oesophagus.

Fig. 19-59: Right sided colon transposition.

may be mechanical or functional. It may be immediate, late and long term. Immediate complications are anastomotic disruption, leak, septicaemia, empyema, and mediastinitis. Late and long term complications are many. They are - transhiatal herniation, colocutaneous/colobronchial fistulas, stricture at oesohagogastric or oesophagocolic sites, pouching effects of the localised part or entire colonic conduit causing redundancy at cervical or thoracic inlet or supraaortic or supradiaphragmatic or infradiaphragmatic portions of the conduit leading into mechanical delay in emptying; cologastric adenocarcinoma; peptic ulceration of the redundant colon and bleeding. Many of these complications need revision surgeries but with poor results.

Jejunum

Isolated required length of pedicled jejunum is transposed. Jejunal free transfer is also tried; vessels are sutured to internal mammary vessels or to the vessels available in the neck (linguofacial trunk or superior thyroid artery). Pedicled jejunum is also *supercharged (boosting)* with microvascular anastomoses with internal mammary vessels. It is used as a last option even though it is ideal. Segment of the 2nd/3rd/4th loop of the jejunum (distal to ligament of Treitz) is harvested with its mesenteric arcade to transplant in the neck with microvascular anastomosis. Jejunum caliber approximates proximal oesophagus. Free jejunal transfer can be used as isolated reconstructive flap for pharyngooesophagus. Function of the remaining large part of the small bowel is not disturbed. Segment of the jejunum should be supplied by a single vascular arcade of adequate dimension. Anastomosis is done proximally to pharynx and distally to oesophagus with microvascular anastomosis. Jejunum retains its effective peristalsis when transposed. Jejunal mesentery limits pedicled transfer of the jejunum; it can reach only up to the inferior pulmonary vein. Free jejunal transfer is ideal and suitable. Pedicled jejunum can be transplanted for 20 cm length; can be increased by supercharging. Otherwise free transfer is the only possibility. Pyloromyotomy is required; gastrostomy is done in case of pedicled jejunal transfer to lower oesophagus. Approach for pedicled jejunal transfer to lower oesophagus is by left sided thoracoabdominal.

Recipient vessels are evaluated for diameter, patency, length, flow and associated vein by CT/MR angiogram. Linguofacial trunk or superior thyroid artery is used. Arterial anastomosis is done superficial to hypoglossal nerve. External jugular vein or tributary of internal jugular vein is used as recipient vein. Anastomosis is done using interrupted or continuous 9 zero polypropylene sutures using microscopy. Tension should be avoided in vascular anastomosis site.

Other Substitutes Used

Radial forearm free flap based at radial artery is used similarly using microvascular anastomosis. Lateral thigh free flap is also often used based on 3rd perforator of the profunda femoris artery along with the accompanied vein. These are mainly used to reconstruct pharyngooesophagus in the neck with microvascular anastomosis.

CRICOPHARYNGEAL MYOTOMY WITH PHARYNGEAL DIVERTICULECTOMY (REFER ALSO CHAPTER 14 - SURGERY OF FACE, HEAD AND NECK)

It is done in pharyngeal diverticulum. It is usually towards left side. If diverticulum is less than 3 cm, just myotomy is sufficient. If it is more than 3 cm then diverticulectomy is needed. *Belsey diverticulopexy* with fixing the most dependent portion of the diverticulum to the prevertebral fascia of upper cervical region with nonabsorbable interrupted sutures is often done; but not very acceptable. Anatomical upper sphincter cricopharyngeus muscle is 2.5 cm in length but physiologic upper oesophageal sphincter is 4 cm in length. So myotomy should be more than 4 cm extending beyond the anatomic cricopharyngeus proximally (2 cm) **(Figs 19-60 and 19-61)**.

Incision

Under general anaesthesia with nasogastric tube in place left lower horizontal or oblique incision along the inner margin of the sternocleidomastoid muscle is used **(Fig. 19-62)**.



Fig. 19-60: Anatomy of pharyngeal pouch.



Fig. 19-61: Contrast X-ray look of oesophagus in pharyngeal pouch.

Dissection

Skin, platysma, deep fascia is incised; sternocleidomastoid muscle is retracted; omohyoid muscle is divided; carotid sheath is retracted laterally; strap muscles are retracted medially along with thyroid gland. Middle thyroid vein is ligated. Inferior thyroid artery is ligated; recurrent laryngeal nerve is identified and safeguarded which is in front of the diverticulum. Diverticulum is identified between inferior constrictor of the pharynx (thyropharyngeus) and cricopharyngeus (Killian's dehiscence). Fundus of the diverticulum is held with Babcock's forceps and diverticulum is dissected from surrounding tissues using peanut blunt dissection and scissor and bipolar cautery. Care should be taken not to injure recurrent laryngeal nerve and oesophageal mucosa.



Fig. 19-62: Incision for excision of pharyngeal pouch.

Myotomy

Right angled haemostat/clamp is passed between the mucosa and transverse fibres of the cricopharyngeus without opening the mucosa. Instrument is elevated and fibres are incised for 5 cm below; later similarly upper fibres are also incised for few (2-3) cm **(Fig. 19-63)**.

Diverticulectomy

40 French Maloney's bougie is passed through the mouth into the oesophagus to identify the neck and opening of the diverticulum. Diverticulum is transected using 30 or 55 mm TA stapler. It also can be transected and hand suturing can be done using inner interrupted 3 zero vicryl and outer interrupted 3 zero silk sutures.

Drain is placed; wound is closed in layers. Maloney's bougie is removed. Nasogastric tube is kept for 48 hours and removed. Soft diet is started. Drain is removed in 4 days.

Complications

Leak from sutured site; infection; abscess formation; stricture formation. Complications like fistula formation, empyema, pneumonia and mediastinitis can occur whenever there is dense adhesion, sepsis, and large diverticulum extending into the thorax.

MANAGEMENT OF OESOPHAGEAL PERFORATION

Oesophageal perforation may be due to instrumentation or vomiting induced like Boerhaave's syndrome or postoperative leak. For cervical


Omohyoid muscle-cut
Thyroid gland
Middle thyroid vein ligated
Carotid artery
Internal jugular vein
Sternocleidomastoid muscle
Inferior thyroid artery ligated
Oesophagus
Pharyngeal diverticulum
Cricopharyngomyotomy
Sutured / stapled oesophageal mucosa
Transection of the diverticulum
Myotomy part

Fig. 19-63: Surgical technique for pharyngeal pouch.

oesophageal perforation lateral film with neck extension X-ray is taken. Contrast CT scan is diagnostic. Patient needs higher generation antibiotics, nasogastric tube at proximal part, intercostal tube, blood, CVP line, urinary cauterization.

Perforation may be bigger than what is thought of usually. Large perforation is difficult to close and in such situation, muscle or pleural or pericardial flap is needed to cover the defect. Resection and diversion to exclude the thoracic oesophagus are other options.

Right or left thoracotomy is done depending on the location of the perforation upper or lower part. Perforation may be clearly seen or may not be clear. In such situation, instillation of air or methylene blue per orally into the oesophagus by anaesthetist will help to identify the site of perforation. Often there will be necrotic material, sepsis, pus due to severe mediastinal infection.

In early cases (within 8 hours), perforation can be still closed in layers – inner mucosal interrupted 3 zero vicryl; outer muscular 3 zero silk sutures. Pleural flap from adjacent is elevated, covered over the suture line and sutured beyond using interrupted nonabsorbable sutures. Stapler closure can be tried but it is often difficult.

Perforation after 8 hours will have marked inflammatory oedema and is often difficult to close the defect with sutures. Here direct pleural flap or intercostal muscle flap is raised and covered over the defect directly. *Rectangular pleura flap* is dissected and raised from behind forward with base in front; elevated pleura is wrapped around the perforation fully and sutured to the oesophageal mucosa in depth using multiple interrupted 3 zero nonabsorbable sutures. *In intercostal muscle flap*, adjacent intercostal muscle is elevated from inside posteriorly adjacent to aorta with intact blood supply with its base at medial end; this vascularised flap is conveniently rotated forward encircling as a wrap around the perforated oesophagus and is sutured **(Figs 19-64 to 19-67)**.

Oesophagus is often *excluded/diverted* by doing cervical proximal oesophagostomy. *Cervical oesophagostomy* is done through left side neck incision along the anterior border of the sternomastoid. Mobilisation is done same as mentioned above. Sternocleidomastoid muscle is retracted outward after opening the deep fascia; omohyoid muscle is cut; carotid sheath is retraced laterally; thyroid and trachea is retracted medially using assistant's finger; recurrent laryngeal nerve is safeguarded (both sides). Middle thyroid vein and inferior thyroid artery if needed is ligated and divided. Prevertebral fascia is dissected to encircle the oesophagus by sharp and blunt dissection. Oesophagus is slinged using infant feeding tube or umbilical tape; significant length is mobilised both proximally and distally to prevent tension after doing oesophagostomy. Oesophagus with sling is brought out towards the middle of the wound. Sternocleidomastoid muscle and deep fascia are sutured using 3 zero vicryl. Platysma and skin is sutured in the wound leaving middle of about 4 cm length for oesophagostomy. Transverse incision on the half circumference of the brought out oesophagus is done; one should confirm that there is no tension. Partially opened up cervical oesophagus is sutured to skin using interrupted subcuticular 3 zero absorbable sutures.

Decortication of the lung with removal of both parietal and visceral pleura allows adequate lung expansion.

Two intercostal tubes are placed in the space on adjacent to the perforation site; other in the intercostal space itself.

Postoperatively patient needs ventilator support, antibiotics, total parenteral nutrition, jejunostomy feed and critical care management.


Oesophagus
Perforation
Diaphragm
Thoracic aorta deep to oesophagus under the mediastinal pleura
Rectangular pleural flap
Perforation closed with interrupted two layered nonabsorbable 3 zero sutures
Pleural flap to cover the sutured defect

Fig. 19-64: Primary closure of oesophageal perforation with pleural flap switch.


Thoracic aorta deep to mediastinal pleura
Diaphragm
Perforation in oesophagus
Elevated rectangular pleural flap which is rotated in front of aorta behind the perforated oesophagus to wrap around
Wrapped pleural flap around the perforated site. Perforation is not closed here. Wrapped pleura is fixed to oesophageal wall with many sutures

Fig. 19-65: Oesophageal perforation is not closed here; instead rectangular pleural flap is mobilised to cover the defect and suture on the oesophageal wall away from the perforation defect.


Oesophageal perforation
Thoracic aorta deep to oesophagus and mediastinal pleura
Ribs
Diaphragm
Intercostal muscle flap elevated from inside
Flap is brought in front of the aorta behind the oesophagus to wrap around the perforation. Proximal part of the wraps sutured to the outer margin of the perforation using 3 zero interrupted nonabsorbable sutures
Inner edge of the perforation is sutured to distal part adjacent to cut edge of the flap similarly

Fig. 19-66: Closure of the oesophageal perforation with intercostal muscle flap.


Sutured skin wound above and below
Incision for oesophagostomy
Sternocleidomastoid muscle
Sling around oesophagus
Oesophagus
Brought out oesophagus incised transversely partly on its anterior wall
Final oesophagostomy with suturing full thickness oesophagus to subcuticular skin as interrupted sutures. It is sited in the middle of the skin incision

Fig. 19-67: Cervical oesophagostomy for severe oesophageal perforation.

Condition has got high mortality. Other complications are empyema, mediastinitis, septicaemia, subphrenic abscess, respiratory failure and acute renal failure. Repeat CT chest, blood or blood product transfusions, monitoring by reassessing the patient with biochemical analysis is needed.

INTUBATION SURGERIES FOR ADVANCED CARCINOMA OF OESOPHAGUS

Intubation of oesophagus across the growth was practiced earlier as a palliative technique to relieve dysphagia is no longer commonly


5 cm length
14 mm lumen
20 cm length
9 mm lumen diameter
Celestin tube - 25 cm length with lumen
Pilot bougie of 60 cm length
Anchor stitch which is placed once pilot bougie is passed into the stomach through oesophagus. Pilot bougie with Celestin tube pulled down through laparotomy gastrotomy incision across the block in the oesophagus

Fig. 19-68: Celestin tube used for oesophageal intubation.

done. It is a surgical legacy. Atkinson tube, Celestin tube, Souttar tube, Mousseau-Barbin tube were used. Now endoscopic self-expanding metal stents (SEMS) are commonly used and ideal.

Celestin tube (armoured tube with a long tail) — It is a flexible polythene tube which is wider proximally with a barrel shaped funnel. It is 25 cm in length. It is 9 and 14 mm in diameter at luminal level. It is oval on cross section. There is a fine pilot bougie of 60 cm length made up of solid polythene. It is passed through endoscopy and laparotomy. Through an oesophagoscope pilot tube is passed across the growth into the stomach; oesophagoscope is removed; Celestin tube is anchored after plugging into the proximal end of the pilot bougie using a stitch through holes in both. Mini upper midline laparotomy is done. Anterior gastrotomy is done on the proximal part of the anterior wall of the stomach; end of the pilot bougie is identified and withdrawn through gastrotomy wound to pull down the anchored Celestin tube until proximal funnel impacts against the narrowed segment of the oesophagus. Excess end in the stomach is trimmed. Gastrotomy and laparotomy is closed. It is traction tube **(Fig. 19-68)**.

Souttar tube (coiled German silver wire)—Block is first dilated with bougies; tube is passed over small sized bougie and pushed across the block. It is mainly useful for lower oesophagus. Its introduction does not require laparotomy. It is a pulsion tube.

Mousseau-Barbin tube—Cheaper but needs laparotomy. After laparotomy anterior wall of the stomach is opened.

MB tube is passed from mouth with the help of anaesthetist by stitching its tip to nasogastric tube and pulled down into the stomach. Tip is cut near the cone part. It is sutured to anterior wall of the stomach. Gastrotomy is closed. It is a traction tube **(Fig. 19-69)**.


Oesophagus
Tube in place
Growth
Stomach

Fig. 19-69: *Mousseau-Barbin tube* – placement in advanced carcinoma of oesophagus. It is not used nowadays.

Chapter 20

Surgery of Stomach and Duodenum

SURGICAL ANATOMY OF STOMACH AND DUODENUM

The stomach lies obliquely in the upper left part of the abdomen occupying epigastric, umbilical and left hypochondriac regions. Most of it lies under left costal margin and ribs. Cardiac orifice on surface marking is located 2.5 cm left of the midline in the left 7th costal cartilage. Pyloric orifice is located in the transpyloric line 1.2 cm right of the midline. Fundus extends upwards from a line along the left of the cardiac orifice to a point up to the left 5th intercostal space just below the nipple. Stomach is J-shaped when empty; pyriform-shaped when distended. Stomach is 25 cm in length. It has got capacity of 30 mL at birth; 1 litre at puberty; 2 litres in adult.

The stomach contains four anatomic regions **(Fig. 20-1)**:

1. Fundus.
2. Cardia.
3. Body.
4. Pylorus – pyloric antrum and pyloric canal.

Angle of His is angle of entry of oesophagus into the stomach which is 30°-70°. In cadaver, it reduces to 20°. This oesophagogastric junction is often termed as cardia. Fundus is the segment of the stomach above an arbitrary horizontal line drawn from the angle of His. Fundus of the stomach is covered by the peritoneum anteriorly; posteriorly, it is covered in most parts except a crescent-shaped part along the upper right part of the fundus and posterior lesser curvature and this area is called as bare area of stomach. Occasionally, it is wide enough to cause difficulty in mobilizing the stomach. Behind fundus of the stomach is related to the diaphragm **(Fig. 20-2)**.

Stomach per se anatomically is a very mobile organ which is easier to understand. But while doing surgical procedures like gastrectomies, it is mandatory to mobilize the proximal or distal stomach and so stomach is often considered as *two gastric units* – proximal and distal **(Fig. 20-3)**.


Cardiac notch
Oesophagus
Fundus
Incisura angularis
1st part of the duodenum
Body
Pyloric antrum
Pyloric canal
Pyloric part of the stomach

Fig. 20-1: Parts of the stomach.


Angle of His
Fundus of the stomach

Fig. 20-2: Angle of His.


Proximal gastric unit
Distal gastric unit

Fig. 20-3: Stomach is considered as two units – proximal and distal. It is relevant while doing gastrectomies.

Proximal gastric unit contains proximal stomach with fundus, oesophagogastric junction, oesophageal hiatus and distal oesophagus. *Distal gastric unit* contains gastric antrum, pylorus and 1st part of the duodenum. It is related in front to the posterior surface of the left lobe of the liver; behind to right crus of the diaphragm, right side to caudate lobe of the liver, left side to the splenic inner surface. Antral mucosa is flat without rugae. It is often demarcated from outside from incisura angularis along the lesser curve, even though it is very much variable. Line is usually located 4 cm proximal to the '*crow's foot'* of the descending part of the anterior vagus nerve; 10 cm proximal to pylorus. Antrum ends at pyloric canal as pylorus. Pylorus ends to thin walled duodenum as pyloric ring (pylorus means *gate guard*). Pyloric ring is formed by a septum from submucosal connective tissue at pyloroduodenal junction; circular muscle proximal to this ring is thickened, acting as pyloric sphincter; distal to this forms thin circular muscle layer of the duodenum. First part of the duodenum is 2.5 cm in length. Pyloric orifice is located at the level of lower border of L1 vertebra in transpyloric plane. Pylorus on the surface feels like a circular groove/constriction due to pyloric sphincter. Pylorus feels like a firm nodule with prepyloric vein located in front of the pyloric constriction. Distal gastric unit is related behind to floor of the lesser sac, transverse mesocolon, head and neck of pancreas, aorta and celiac trunk with branches, gastroduodenal unit, common bile duct, portal vein and hepatic artery. In front, it is related to left and right lobes of the liver, transverse mesocolon, gallbladder with its neck often, anterior abdominal wall.

Oesophageal hiatus is formed by the two pillars of the right crus of the diaphragm. Phrenooesophageal membrane is present in front.

Stomach is often divided into two parts by a line drawn downwards and towards left from incisura angularis. Proximal part is called as cardia which is larger and is divided into fundus and body. Smaller distal pyloric part is again divided into pyloric antrum and pyloric canal. Fundus is above the line from angle of His, which is dome-shaped directed upwards which always normally contains gas. Body of the stomach is located between fundus and pyloric antrum and can distend enormously along the greater curvature. Lesser curve is very less distensible and at much posterior level than greater curvature. Lesser curve bears the maximum insult of the swallowed liquids. Body of stomach contains mucus cells, chief cells (peptic or zymogenic cells secrete digestive enzymes) and parietal cells (oxyntic cells secrete hydrochloric acid). Pyloric antrum is 7.5 cm in length which contains mainly mucous glands. Narrow tubular pyloric canal is 2.5 cm long **(Fig. 20-4)**.

Greater omentum is present along the greater curvature which extends downwards as a free apron on the abdomen; reflects back towards transverse colon where it is attached with avascular tissue. Within it exists the *omental bursa* which is of surgical importance, especially in radical gastrectomies. Omental bursa extends from the upper margin of the transverse colon along the superior leaf of the transverse mesocolon towards front of the pancreas, reflecting back in front to the greater omentum. Two layers of the greater omentum meet near the fundus in its upper part as gastrosplenic ligament.

Peritoneum on the posterior surface of the stomach near upper part reflects on the diaphragm as gastrophrenic ligament. Its upper part is avascular and through which a window can be created in vagotomy or during mobilization of the oesophageal hiatus. Its lower part contains short gastric vessels and lymph nodes.

Gastrocolic ligament is part of greater omentum extending from the greater curvature of the stomach and first part of the duodenum to the transverse colon. Mobilization of this ligament is essential in many gastric and pancreatic surgeries.

Fig. 20-4: Gastroscopy reveals the demarcation between the body and pyloric antrum. Antrum does not have rugosity.

Lesser omentum is much thinner and extends from lesser curvature towards the liver. Hepatogastric ligament is the proximal part of it extends from porta hepatis and lesser curvature of the stomach; above it extends as ventral mesentery of abdominal oesophagus. Hepatogastric ligament contains left gastric vessels, hepatic branch of anterior vagus, posterior gastric divisions of the vagus and lymph nodes. In 23% of individuals an aberrant left hepatic artery may be present in this ligament which may be exclusive supply of the left lobe of the liver.

Hepatoduodenal ligament is distal part of the lesser omentum extending from the liver to 1st 2.5 cm of the duodenum. Its free edge contains hepatic triad and lymph nodes **(Fig. 20-5)**.

Diaphragm separates the stomach from left pleura, pericardium and lower ribs (6th to 9th). Posteriorly stomach is related to diaphragm, left kidney, left adrenal gland, splenic flexure of colon, transverse mesocolon and splenic artery. Gastrosplenic ligament is spread between greater curvature of the stomach and spleen.



Fig. 20-5: Oesophagogastric junction and ligaments of stomach.

Arterial Supply of Stomach

Stomach is supplied by left gastric artery, a branch of coeliac artery (smallest branch of coeliac axis); right gastric artery, a branch of proper hepatic artery; right gastroepiploic artery, a branch of gastroduodenal artery (a largest branch of common hepatic artery); left gastroepiploic artery, a branch of splenic artery; short gastric arteries, branches of splenic artery; left inferior phrenic artery, a branch of aorta; posterior gastric artery, a branch of left gastric/splenic artery or from coeliac trunk which supplies distal oesophagus, fundus and OG junction. Gastroepiploic arteries are also called as gastroomental arteries. Vessels in the omentum form an arcade called as *arc of Barkow* **(Figs 20-6A and B)**.

Left gastric artery after originating from coeliac trunk (90%) runs retroperitoneally upwards and left giving oesophageal branches. Then it runs downwards to reach the proximal lesser curve to continue along lesser curvature of stomach to anastomose with the right gastric artery. When it enters the lesser curve, it gives cardiooesophageal branch, often called as ascending branch which runs upwards. Left gastric artery then runs downwards as descending branch which eventually gives into anterior and posterior branches. Numerous gastric branches enter the stomach to supply it. As a variation, left gastric artery may originate from common hepatic artery, splenic artery, aorta, superior mesenteric artery; or as gastrosplenic trunk or heptogastric trunk. Rarely can it originate directly from aorta. Aberrant left hepatic artery may arise (24%) from left gastric artery, and in such situation, artery will be much wider than usual.


Left gastric artery
Coeliac artery
Common hepatic artery
Hepatic artery proper
Right gastric artery
Gastroduodenal artery
Aorta
Short gastric arteries
Left gastroepiploic artery
Supraduodenal artery
Splenic artery
Right gastroepiploic artery
A
Superior panocreaticoduodenal artery
Stomach reflected upwards
Coeliac trunk
Liver
Left gastric artery
Short gastric arteries
Stomach
Inferior phrenic artery
Left gastroepiploic artery
Right gastric artery
Posterior gastric artery
Right gastroepiploic artery
Splenic artery
Gastrodeudenal artery
Pancreas
Aorta
Proper hepatic artery
Duodenum
SMA
Anterior pancreatico-duodenal artery
Common hepatic artery
Middle colic vein
SMV
Middle colic artery
Inferior pancreatico-duodenal artery
B

Figs 20-6A and B: Arterial supply of stomach. View also shown after reflecting the stomach upwards.

Right gastric artery commonly arises from proper hepatic artery (65%); but can arise from left hepatic artery (25%) or common hepatic artery (3%). It runs along the lesser curvature of stomach for 6 cm, 0.5 cm from lesser curve margin to join left gastric artery. Supraduodenal artery which usually arises from proper hepatic artery just proximal to right gastric artery can arise from right gastric artery (13%).

Common hepatic artery arises from coeliac trunk that runs behind the lesser sac towards right reaching the upper border of the duodenum. Here it gives large branch gastroduodenal artery which descends vertically downwards from 1st part of the duodenum behind to divide as *right gastroepiploic artery* and superior pancreaticoduodenal artery (which often divides into anterior and posterior branches running along the pancreaticoduodenal groove to communicate with inferior pancreaticoduodenal artery which is a branch of superior mesenteric artery). Common hepatic artery continues as proper hepatic artery which later gives supraduodenal artery and right gastric artery enters and runs along the free border of the lesser omentum in front of the portal vein and left of the common bile duct to reach porta hepatis. Here it divides into right and left branches.

Left gastroepiploic artery arises from the splenic artery distally close to greater curvature. Posterior gastric artery arises from splenic artery proximal to the origin of the left gastroepiploic artery. Often this is the only blood supply which is left in subtotal gastrectomy wherein left gastric artery is ligated at its origin and many short gastric vessels are also ligated.

Venous Drainage of Stomach (Fig. 20-7)

Right and left gastric veins drain into portal vein. Left gastric vein is caudal to left gastric artery and is also called as coronary vein. Left gastric vein receives tributaries from oesophageal hiatus and oesophagus; runs downwards and towards right to join commonly to portal vein (70%) or splenic vein near its junction to portal vein (30%). Left gastric vein communicates with azygos vein which will lead into the varices when there is portal hypertension. Left gastroepiploic and short gastric veins drain into splenic vein. Splenic vein block causes extensive varices in the proximal gastric unit. Right gastroepiploic vein drains into superior mesenteric vein. It receives anterior superior


Liver
Oesophageal tributaries
Short gastric vein
Right gastric vein
Splenic vein
Left gastric vein
Left gastroepiploic vein
Portal vein
Prepyloric vein of Mayo
Right gastroepiploic vein
Superior mesenteric vein

Fig. 20-7: Venous drainage of the stomach.

pancreaticoduodenal vein and middle colic vein in front of pancreatic head. Blockage of right gastroepiploic vein can cause duodenal varices. In portal hypertension, congestion of veins and varices can develop between right and left gastroepiploic vessels. Right gastric vein runs close to right gastric artery towards right along distal gastric unit to drain into the portal or superior mesenteric or splenic vein. Often *Henle's gastrocolic vein* may be present (70%) formed by right gastroomental vein and right colic vein; it is short run along the root of the transverse mesocolon and anterior surface of the head of the pancreas. Prepyloric vein of *Mayo* distinguishes pyloric canal from the first part of duodenum. It drains into the right gastric vein.

Nerve Supply of Stomach

Intrinsic innervation occurs through myenteric plexus of *Auerbach* and submucous plexus of *Meissner.*

Right vagus is posterior and left vagus is anterior. Right posterior vagus is away from oesophagus closer to aorta, unlike left vagus. Both right and left vagi are usually right of the midline in 80% of cases; but anterior vagus is more left compared to posterior vagus. Hence, it is better to name them as posterior and anterior even though right and left vagi are commonly used terminologies. Posterior vagus gives *criminal nerve of Grassi* (Professor Grassi, Rome), which supply lower oesophagus and fundus of stomach, which, if not cut properly during vagotomy, may lead to recurrent ulcer. It is a single nerve arising from posterior vagus that runs behind the cardia to supply part of fundus and proximal stomach. Vagus also gives splanchnic branches (*hepatic and coeliac branches),* ends as *nerve of Latarjet* (Latarjet – French surgeon, 1921) which supplies the antrum and maintains the antral pump. Each vagus gives divisions—splanchnic and gastric. Anterior gastric nerve from anterior trunk after running along the anterior surface of the lesser curvature ends as anterior nerve of Latarjet (greater anterior nerve of Mitchell) supplying the antral pump. Similarly posterior gastric nerve arises from posterior vagus. Anterior vagus gives hepatic branch (frequently multiple); posterior vagus gives a single stout coeliac branch to coeliac ganglion. Hepatic branch of the anterior vagus often gives a direct branch to the pylorus. Nerve of Latarjet arising from posterior trunk is much smaller and ends much proximal than that of anterior vagus. Parietal branches help in HCl secretion, which is an important concept in vagotomy that is done as a treatment in duodenal ulcer. *Truncal vagotomy* with posterior gastrojejunostomy is done for chronic duodenal ulcer with pyloric stenosis. Right vagus is thicker than left vagus; left vagus is embedded in the anterior oesophageal wall **(Fig. 20-8)**.

Among hepatic, anterior/posterior gastric and celiac divisions, coeliac division is the largest one. Coeliac division lies on the gastropancreatic peritoneal fold. It is a single trunk arising from the posterior vagus which supplies coeliac plexus.

Anterior vagus gives hepatic, gastric and antral branch. Hepatic branches originate as first branches of the anterior vagus below the diaphragm runs in the layers of the lesser omentum reaching liver; it gives the branches to liver and continues as plexus around hepatic artery giving branches to gall bladder, bile duct and pancreas. A pyloric branch begins here which runs along the right gastric artery downwards to supply pylorus and part of the stomach. One more branch runs along the gastroduodenal artery and right gastroepiploic artery to supply greater curvature of the stomach. About 5–10 gastric branches arise from anterior vagus supplying anterior portion of the proximal stomach and fundus. It runs closely associated with vessels of the lesser curvature entering the serosal layer of the stomach to run in the subserosal plane for 2 cm; then it enters the submucosal and mucosal planes. They supply parietal cells and smooth muscle cells of the body and fundus of the stomach. Often branch/branches may present at higher level at or beyond angle of His. Anterior nerve of Latarjet is the final continuation of the anterior vagus towards pylorus; near incisura angularis, it fans out many branches over the gastric antrum as 'crow's foot' (this word is coined by Goligher). Anterior and posterior nerves of Latarjet supply antropyloric mechanism. This nerve has to be preserved in highly selective vagotomy to retain antral pump function.


Anterior vagal trunk (left)
Anterior vagal trunk
Anterior gastric division (nerve of Latarjet anterior)
Hepatic division (branch)
Pyloric branch
Crow's foot
Gastric branches
Posterior vagal trunk (right)
Posterior vagal trunk
Criminal nerve of Grassi
Posterior gastric division (nerve of Latarjet posterior)
Coeliac trunk-single
Gastric branches
Crow's foot

Fig. 20-8: Distribution of vagal trunks in the abdomen.

Posterior vagus gives single coeliac branch which joins coeliac plexus. It often receives a communicating branch from anterior vagus. Around 5–6 gastric branches descend and enter the posterior wall of the stomach to supply similarly to gastric branches of the anterior vagus. Posterior vagus continues downwards as posterior nerve of Latarjet to supply antrum and pylorus. Posterior nerve of Latarjet ends at more proximal level than anterior nerve of Latarjet. Criminal nerve of Grassi arises from the posterior vagus running behind OG junction to supply fundus and proximal stomach.

Vagus in the distal 6–8 cm of oesophagus also supplies the stomach by different fibres through distal oesophageal plexus. So distal 8 cm of the oesophagus should be skeletonised to achieve optimum results of the vagotomy. Proximal most branch of 'crow's foot' is 7 cm from pyloroduodenal junction. Junction of antrum and body is 4 cm proximal to this. Antrum does not have parietal and chief cells. So in highly selective vagotomy, dissection is done proximal to 'crow's foot.' In the OG junction, vagal fibers are located within the peritoneal fold left of the oesophagus. So all loose areolar tissue should be dissected towards left of the oesophagus and angle of His to achieve complete vagotomy.

Highly selective vagotomy (*HSV)* is done in case of uncomplicated chronic duodenal ulcer (refractile ulcer) which is not responding to available medical line of treatment. In HSV, nerve of Latarjet is retained so as to retain antral pump and no drainage is required. Here only the fibres entering the stomach are ligated close to the lesser curve to reduce the acid secretion. Usually vessels accompanying nerves are also ligated together. In *selective vagotomy,* splanchnic branches are retained but it is presently not done. Gastroduodenal pain is sensed via sympathetic fibres (T5-T10). Term *extended proximal gastric vagotomy* means additional division of the recurrent branch of hepatic vagal branches distributed to greater curvature along gastroduodenal and right gastroepiploic arteries.

Histology

The fundus and body contain parietal (acid producing) and chief cells. *Parietal cells* secrete acid and intrinsic factor. *Chief cells* produce pepsinogen. There are two types of pepsinogen secreted by chief cells—I and II. Pepsinogen I is produced only in stomach. In gastric atrophy, pepsinogen I is decreased. In the antrum, *endocrine cells* produce *gastrin* (G cells) and somatostatin (D cells). 12% of epithelial cells of stomach are parietal (oxyntic) cells; 45% chief (zymogenic cells); 40% mucous cells; 3% endocrine cells. Submucosa is strongest, collagen rich layer of gastric mucosa. Gastric mucus is a mucosal barrier containing mucopolysaccharides which maintains the integrity of gastric mucosa. Muscles of the stomach wall are outer longitudinal; middle circular and inner oblique. Middle circular and innermost oblique muscles blend in angle of His forming collar of *Helvetius*.

Lymphatic Drainage of Stomach

Lymphatics of proximal half of stomach drain into left gastric, splenic, and superior pancreatic lymph nodes. From antrum, it drains into right gastric, right gastroepiploic and subpyloric lymph nodes. From pylorus, it drains into right gastric and subpyloric lymph nodes. Efferent lymphatics from suprapyloric region drain into para-aortic lymph nodes and so into left supraclavicular lymph nodes. Efferent lymphatics from subpyloric lymph nodes drain into superior mesenteric lymph nodes. Lymphatics near *oesophagogastric* (OG) junction communicate with oesophageal lymphatics. In carcinoma stomach if upper lymphatics are blocked, retrograde spread through lower lymphatics can occur. Presently in carcinoma stomach, different resections are classified as R0, R1, R2, R3, or D1, D2 (dissection) based on levels of lymph nodes in the abdomen in relation to the stomach. R0 is no residual disease; R1 is microscopic residual disease; R2 is macroscopic residual disease; R3 is inoperable **(Fig. 20-9)**.



Fig. 20-9: Lymphatic drainage of stomach.

Zones of lymphatic drainage in stomach: Four zones.

Zone 1-inferior gastric: It lies in gastrocolic omentum along the right gastroepiploic vessels, draining pyloric portion of the greater curve to pyloric, coeliac and aortic lymph nodes.

Zone 2-splenic: It lies in gastrocolic and gastrosplenic omentum along the left gastroepiploic vessels draining from upper half of greater curve to pancreaticosplenic and aortic lymph nodes.

Zone 3-superior gastric: There is drainage from proximal two thirds of the stomach and the upper lesser curve along the left gastric artery. Zone 3 drains into perioesophageal lymph nodes.

Zone 4-hepatic: It is from distal portion of lesser curve and pylorus along hepatic artery into para-aortic nodes.

Lymph node groups

Group I: Perigastric nodes
Group II: Along the root of major vessels
Group III: At the root of superior mesenteric artery and hepatoduodenal ligament
Group IV: Distant lymph nodes.

SURGERY FOR DUODENAL ULCER PERFORATION

It is an emergency surgery. Preoperatively X-ray abdomen in erect or lateral decubitus confirms the diagnosis. Additionally ultrasound abdomen may be useful. Electrolyte estimation, renal functions should be confirmed. Initial resuscitation with proper fluid therapy, antibiotics, CVP line, nasogastric aspiration and urinary catheterisation should be done **(Figs 20-10 to 20-12)**.

Occasionally when stomach is empty, perforation may get sealed-off automatically or may form localized abscess in the lesser sac, subphrenic space or paracolic gutter. Mikulicz (1887) and Dean (1894) did first successful closure of perforation by suturing edges of the perforation. Later Cellan Jones (1929) and Graham (1937) popularized the omental plugging and suturing the perforation which was originally thought by Bennett (1899).

Technique (Fig. 20-13)

Emergency laparotomy through upper midline incision is done. All infected fluid is sucked out. Perforation is identified. Usually duodenal



Fig. 20-10: Duodenal ulcer perforation. Here fluid from perforated site travels along the right paracolic gutter.



Figs 20-11A and B: X-ray chest and upper abdomen or lateral decubitus showing gas under diaphragm.


DU perforation
Omental patch
1
3
2
Sutures
1
3
2
Colon

Fig. 20-12: Closure of duodenal ulcer perforation using Graham's omental patch.


5 mm port
Midline incision
Perforation
5 mm
5 mm
10 mm (camera)

Fig. 20-13: Incision for closure of perforated duodenum for open and laparoscopic approach.

ulcer perforation is less than 1 cm in size. Giant ulcer is more than 2 cm in size. Omentum will be adherent to the site of perforation. It is gently separated. If duodenum is not perforated then stomach, posterior wall of stomach (lesser sac), small bowel and colon are thoroughly checked for possible sites.

Once perforation is identified, surrounding area is sucked out with suction. Liver, colon and proximal stomach are retracted. Suture material used for perforation is 3-0 vicryl or PDS or silk. As perforation edge is friable and oedematous, needle bites should be very gentle. Bite from each edge (5 mm from the edge) is taken separately. Each suture is kept away using haemostats on either side untied. Three stitches are taken at equal distances. Omental pedicle is held like patch. Viable segment should be used. Often it needs placing few ligatures to get adequate length of the omental pedicle. Omentum is placed on the perforation site to seal it. Knots are placed on it. Initially side sutures are tied on omentum; then center one to avoid tearing of the friable edge of perforated site. First suture towards the upper part i.e. apex of the omental pedicle is tied. All sutures should be interrupted horizontal one. Omental patch is placed *before suturing*—it is called as ***Graham Operation.*** Because of its *adhesion property,* it seals perforation; good vascularity and lymphatics promote the healing effectively **(Figs 20-14 to 20-16)**.


Needle bite from one edge of the perforated duodenal ulcer
Removing the needle from same edge through perforation
Taking the needle bite from opposite edge of the perforation
Completion of taking bites from both edges of the perforation
A
1
3
2
Perforation of duodenal ulcer with untied sutures
Greater omentum
Viable omental pedicle
Omental pedicle placed over the perforation ready to tie the knots
B

Figs 20-14A and B: Closure of duodenal perforation—technique.



In large (giant) peforated duodenal ulcer 4 seromuscular suture are placed 5 mm away from the edges of ulcer; Bites are not taken through the lumen of the duodenum

Viable omental patch is placed over it

Seromuscular sutures are tied over the omentum. Edge of the omentum is fixed to the adjacent duodenum with seromuscular sutures to make it watertight

Fig. 20-15: Perforated giant duodenal ulcer is closed by taking only seromuscular bites to hold omental patch; here bites are not taken through the mucosal layer across the lumen.


GB
DU perforation
Suction removal of pus and infected fluid
Interrupted silk 3 zero suture- kept untied on each and bite from each edge should be taken separately
Three interrupted sutures taken are held apart untied using haemostats
Greater omentum
Transverse colon
Viable omental pedicle harvested
Pedicle brought and placed over the perforated site and sutures
First knot is tied near the apex (uppermost) of the pedicle
Next lower most knot is tied; later middle knot is tied at last
Tying final middle knot
After completion of tying of three knots

Figs 20-16(1)


Final look of closure/
plication of perforation
Warm saline irrigation
of peritoneal cavity
Placing the tube drain- optional
Closure of the rectus sheath
using nonabsorbable ethylon
(polyethylene) continuous sutures
Final knot using Aberdeen method

Figs 20-16(2)

Figs 20-16(1 and 2): Closure of duodenal ulcer perforation.

Peritoneal wash (toilet) using 5–10 litres of warm saline is given. Drain is only optional. Drain is placed and abdomen is closed with modified Smead Jones technique (often if required using *tension sutures*. But tension/retention sutures are not recommended now, even though commonly practiced by significant number of surgeons). Drain is removed in 3–5 days. Nasogastric tube is removed in 5 days. Oral fluid is started once bowel sounds are heard adequately; patient passes flatus; no abdominal pain.

During discharge, patient is advised to avoid alcohol and to take H2 blockers or proton pump inhibitors for 6–12 weeks. After 12 weeks, *follow-up gastroscopy must be done.*

Complications

Subphrenic abscess formation: It is confirmed by CT abdomen. It can be treated conservatively or guided tube drainage or open drainage.

Reperforation rarely can occur which needs resection of distal stomach with perforated site and Billroth II anastomosis.

Duodenal obstruction is not uncommon. It causes gastric dilatation and persistent vomiting. With fluid therapy, nasogastric tube aspiration, it may subside. If not then oral contrast study of the gastroduodenum is needed. Relaparotomy and gastrojejunostomy is needed. Vagotomy to reduce the acid load is added depending on the general condition of the patient. HSV may be better option.

Duodenal fistula can occur occasionally. It may stop spontaneously. Occasionally it may require a diversion, serosal patch at the site.

Wound infection, burst abdomen can occur if patient's general condition is not good and nutritionally deprived.

Note:

Laparoscopy is beneficial for both diagnoses, as well as for therapy for perforation closure using omental patch. It is proposed and widely used for early duodenal perforation. It can be useful for most of the duodenal ulcer perforations except large or extensive one. If it is problematic, conversion options should always be kept in mind. Patient is in supine head up position (reverse Trendelenburg position); surgeon stands in between legs or on the left side. Monitor is on the head end right side. Cameraman is on the left of the surgeon. Trocar is placed as in the diagram. Technique is same as open method. Often omental patch integrity is tested by insufflation of stomach with air, and air bubble can be checked on the saline filled closed perforation site. Gastroscopy is also often used by many to confirm the same as well as to assure that sutures placed are not too deep. Mouret et al 1989 did first laparoscopic perforation closure. Nathanson et al later did laparoscopic closure of perforation. Intracorporeal knots are commonly used. Extracorporeal knots, fibrin glue fixation of omental patch, gelatin sponge sealing, stapled patch closure, placement of ligamentum teres into the perforation. *Advantages are*—better visualisation, less postoperative pain and early recovery. *Drawbacks* *are*—difficulty in suturing, and inadequate peritoneal toilet which takes long time. *Contraindications are*—elderly, cirrhotic, cardiac patients, obesity and coagulopathy.

Large perforated duodenal ulcer is often difficult to close. Here instead of taking bites directly through the edges of the perforated ulcer across the lumen, seromuscular bites are taken 5 mm away from the edges of the ulcer on either side. Usually 4 such interrupted sutures are placed and viable omental patch is placed over it to tie. After that omentum again is sutured to the duodenum on its margin as seromuscular stitches to make it watertight.

Once perforation is closed, either by open or laparoscopic method, after recovery, patient should be advised *anti-Helicobacter pylori* therapy (triple regime for 14 days) with PPI for 3 months. It reduces rate of reperforation and ulcer recurrence in duodenal ulcer.

In patients with severe peritonitis and critically ill, after perforation closure, it is better to insert a nasojejunal tube or feeding jejunostomy for nutrition in postoperative recovery period. Even if patient develops a temporary duodenal leak, this supports nutrition well until the leak stops.

Occasional *large perforated duodenal ulcer* with oedema which cannot be closed is managed by serosal patch/duodenal drainage and pyloric exclusion/gastrostomy, duodenostomy and jejunostomy/Roux-en-Y jejunal patch over the perforation. Vagotomy with pyloroplasty; vagotomy with antrectomy are all other options used with care.

Definitive procedure can be done or not is a matter of debate. But if contamination is less and ulcer is chronic, highly selective vagotomy can be added in selected patients.

Gastric Ulcer Perforation

It is difficult to manage gastric ulcer perforation as plication may not hold properly. Gastric ulcer perforation causes large amount of gas leak showing gas under both sides of the diaphragm in erect X-ray film. Partial gastrectomy and gastrojejunostomy or gastroduodenostomy is preferred one.

GASTROSTOMY

It is the communication of the anterior wall of the stomach to the abdominal wall skin mainly for feeding purpose whenever oral or nasogastric feeding is not possible or there is fear of reflux and pneumonia and oesophageal stricture due to long-term nasogastric feeding.

Indications

It is used in multiple strictures of oesophagus, in congenital oesophageal conditions as an initial stage of surgery during radiotherapy period, in head and neck cancers for feeding purpose. It improves the nutrition; medications can be given through this tube as well. It keeps the small bowel function active. It is also done in major trauma, sepsis, major surgeries, burns and severe malnutrition.

Types

Gastrostomy can be *temporary* wherein gastrostomy tube is removed later to allow the gastrostomy to close spontaneously; or *permanent* where gastrostomy is kept permanently for life-long for feeding purpose **(Fig. 20-17)**.

Gastrostomy can be serosa/*serous lined*; it is temporary and easier to do. It can be *mucus lined* which is permanent and is technically difficult. Stamm (1894), Kader–Senn (1896), Witzel (1891) are temporary types. Depage–Janeway (1913), Spivack, Beck Carrell–Jeau (1905, 1912), Tavel are permanent types **(Figs 20-18 to 20-22)**.

Gastrostomy can be done by *open* method; *endoscopic* [Percutaneous Endoscopic Gastrostomy (PEG)]; or *laparoscopic-assisted endoscopic* method. PEG has become more popular nowadays. Stamm and Janeway gastrostomies can be done laparoscopically also.



Fig. 20-17: Types of gastrostomies—serous-lined (temporary); mucus-lined (permanent).



Fig. 20-18: Beck Carrell Jean gastrostomy. It is a mucus lined permanent gastrostomy.



Fig. 20-19: Tavel permanent gastrostomy.



Fig. 20-20: Kader Senn temporary gastrostomy.



Fig. 20-21: Stamm gastrostomy is a temporary gastrostomy.



Fig. 20-22: Witzel's temporary gastrostomy.

Contraindications

Previous gastric surgeries, intestinal obstruction, gastric outlet obstruction, gastric diseases with impaired gastric emptying are contraindications.

Problems in gastrostomy

Leak—gastric fistula is very dangerous one. Gastrostomy is the commonest cause of gastric fistula. Infection can occur which can cause skin excoriation. Aspiration, pneumonia, diarrhoea is common—30%, bloating, abdominal cramps, displacement, blockage of the tube, trauma to other organs like colon.

Technique of Temporary (Stamm's) Gastrostomy

Commonly done type is Stamm's gastrostomy. It is serous-lined temporary gastrostomy. Upper midline incision is done. Stomach is held upwards towards wound using two Babcocks forceps applied at lesser and greater curvatures near middle of the stomach. In the midpoint of the stomach closure to greater curvature, marker stitch is placed. Purse string seromuscular suture is placed with a 2 cm diameter using 2-0 silk or vicryl. Using two Allis tissue holders, left edge of the cut linea alba is held apart; 2 cm vertical or horizontal incision is made on the skin over the middle of the rectus muscle; anterior rectus sheath is incised; rectus muscle is split; posterior rectus sheath and peritoneum is incised. Alternatively same can be achieved by a stab incision from skin towards the peritoneum under vision. Haemostat (medium sized or large) is passed from inside (peritoneum) out (towards skin) to grasp the selected gastrostomy tube (20 French Malecot/Foley's catheter/mushroom catheter) which is pulled into the peritoneal cavity. Incision is made within the purse string, suture placed (gastrotomy) using 15 number blade or cautery; tip of the gastrostomy tube is passed into the gastric lumen. Tip is usually directed downwards. If Foley's catheter is used, it is inflated with distilled water. Purse string suture is tied with knot to create inversion of serosa snugly on to the tube. It is supported by 2nd layer of purse string suture using 2-0 silk. This also ensures rapid closure of the stomach opening after removal of gastrostomy tube. Tube should be anchored to abdominal wall to prevent leak and spillage of the gastric contents. It is achieved by taking seromuscular bites from the stomach and to the peritoneal (or peritoneum with posterior rectus sheath) layer of the abdominal wall; 4 interrupted 2-0 silk or vicryl sutures are placed and kept untied initially. Once all four sutures are placed, they are tied and cut to anchor the tube to abdominal wall. Tube is fixed outside to the skin. Linea alba is sutured using polypropylene continuous sutures; skin is closed using stapler or nonabsorbable interrupted sutures **(Figs 20-23 and 20-24)**.

Temporary gastrostomy can be used for function in 48 hours. It should not be removed earlier than 3 weeks until proper sealing and track has formed.

Technique of Permanent (Depage Janeway) Gastrostomy

Permanent gastrostomy is mucus lined; it prevents regurgitation of gastric contents and avoids placing of a tube; it remains patent without any tendency to close. It is actually a permanent fistula **(Figs 20-25A and B)**.

Abdomen is opened forceps with upper midline incision. Stomach is held with two Babcock instruments adjacent to greater and lesser curvature. Occlusion clamps can be applied upper and lower part of the stomach to prevent spillage of the gastric content and bleeding from the cut edges. Flap from the gastric anterior wall is taken as rectangular. It can be horizontal with apex of flap towards lesser curve and base


Incision and
gastrostomy site
2-0 vicryl purse
string seromuscular
suture
Peritoneum
Abdominal wall
Umbilicus
Gastrostomy tube passed
into the peritoneal cavity
Anterior wall of stomach
is opened within purse string
Anchoring sutures
Anchoring
sutures
Gastrostomy tube is passed
into the gastric lumen.
2nd purse string is taken after
tying inner 1st purse string
2nd purse string is tied and 4-5 interrupted
sutures are taken from seromuscular layers
of stomach and peritoneum with posterior
rectus sheath
These anchoring sutures
are tied. Gastrostomy tube
is fixed. Abdomen is closed
in layers.

Fig. 20-23: Stamm temporary gastrostomy—technique.



Fig. 20-24: Technique of temporary gastrostomy.


Horizontal flap with base towards greater curvature
Vertical oblique flap adjacent to greater curvature with base towards pylorus
Vertical oblique flap adjacent to greater curvature with base towards fundus
A
Upper midline incision
Gastrostomy site
Horizontal gastric flap
Posterior wall gastric mucosa
Raised flap with base at greater curvature
Abdominal wall
Gastrostomy tube is placed along the flap into the gastric lumen
Anterior gastric wall and tube flap are sutured around the gastrostomy tube
End of the gastric tube flap is brought out through a separate wound and is sutured to the skin edge
B

Figs 20-25A and B: Janeway's permanent gastrostomy.

towards greater curve; or along the middle of the anterior wall of the stomach more towards the greater curvature as a rectangular flap with base directed either below or above. Flap should be adequately wide and lengthy as after flap harvesting, it shrinks significantly. Once flap is elevated adequately, 20 Foley's catheter is placed across the inner part of the flap into the stomach. Flap is sutured like a tube around the catheter using inner interrupted 2-or 3-zero vicryl and outer interrupted 3-0 silk sutures. Similar sutures are placed along the stomach wound from the base in two layers. Anterior wall is fixed to peritoneum using 2 or 3 interrupted sutures. Such permanent gastric tube can also be created using stapler device comfortably. A stab wound or layer by layer opening of the abdominal wound of 1.5 to 2.0 cm in length along the middle of the rectus muscle using a horizontal incision is used to bring the gastric tube outside as exteriorization and gastric mucosa is fixed to the skin (usually skin is incised horizontally; anterior rectus sheath is incised horizontally; rectus muscle is split; posterior rectus sheath and peritoneum are incised). Abdomen are closed in layers.

Fluid therapy can be started with catheter in situ in 48 hours. Catheter can be removed in 7 days. But tube (any tube of adequate size) should be reapplied and kept **(Fig. 20-26)**.

Technique of Percutaneous Endoscopic Gastrostomy (PEG)

It is done using gastroscope without doing laparotomy. It is useful in children and adult for feeding and decompression. Stomach should be amenable for distension through endoscope; transillumination should be visible across the abdominal wall to do PEG. Dr Jeffrey Ponsky developed this method in 1980.

Ascites, coagulopathy, gastric outlet obstruction, gastroparesis, previous abdominal surgeries, gastrectomies, obesity are contraindications for PEG **(Figs 20-27A and B)**.

Patient should be kept nil oral like for gastroscope. Sedation, intravenous line and fluid are started. Patient is placed in supine head up position. Local anesthetic spray or gargle is instilled to the throat (oropharynx). Gastroscope is passed. Stomach is distended by air insufflation sufficiently so as to make anterior wall of the stomach abut into the abdominal wall. Room is made dark by switching of the bright lights to make transillumination better visible along the upper abdomen. Position is confirmed by finger indentation in the upper midline abdominal wall which is seen in endoscope image. Local anaesthetic agent is infiltrated (xylocaine 2%) in the upper abdomen in the suitable place for about 2 cm area. One cm skin incision is made. 16 gauge IV cannula with needle is passed under endoscopic vision per abdomen across the skin incision into the anterior stomach wall. Safe tract method is used while passing the needle. Cannula needle is connected to syringe with xylocaine and passed forward progressively with suctioning in the syringe; when needle enters the lumen (confirmed by endoscopic view), air bubble can be seen; if air bubble is seen but needle has not entered the gastric lumen then it is presumed that bowel is interposed, and needle is immediately withdrawn. Needle is removed; cannula is kept in place; a long thick



Figs 20-26(1)



Figs 20-26(2)



Figs 20-26(3)

Figs 20-26(1 to 3): Janeway's permanent gastrostomy.



Figs 20-27A and B: Percutaneous endoscopic gastrostomy procedure.

(number 1) nylon or polyethylene or silk or guide wire is passed across the cannula into the stomach which is visualised through gastroscope. An endoscopic snare is passed through the working channel of the gastroscope into the stomach through which guide wire or nylon is held and pulled out along with endoscope. This causes guide wire or nylon to pass across the abdominal wall, stomach, oesophagus and mouth with one end in the abdominal wall and other end coming out through the mouth. Specialised PEG tube or de Pezzer catheter is tied to the guide wire or nylon at its oral end; nylon or guide wire at abdominal wall is pulled out with gentle traction until the PEG catheter or de Pezzer catheter comes and stays across the stomach and abdominal wall. Tube is fixed to the abdominal skin. Catheter position inside is confirmed by gastroscopy. An external bolster is kept on the tube to prevent migration. It is kept few mm away from the skin, usually by keeping sterile dressing pads or sponge underneath. Migration of PEG tube downwards may cause pylorus obstruction.

When one end of the guide wire/nylon brought out it is tied to the end of the PEG catheter and other end of the guide wire in the abdominal wall is pulled out to reach the PEG tube into the stomach and across the abdominal wall, it is called as "pull technique" which is the original method still popular. While pulling the tube, gastroscope is also passed from above to visualise the tube placement.

Instead of tying the guide wire end in the mouth to the PEG tube, PEG tube itself is pushed on to the guide wire across the mouth and is pushed by holding the guide wire ends at oral cavity, and at abdominal wall is held taut to reach the stomach and across the abdominal wall. Later gastroscopy is done to confirm the position, and guide wire is removed. It is called as "push technique".

Bowel interposition between stomach and abdominal wall is a real risk in PEG. Either small bowel or colon may get interposed. 'Safe tract' method (Foutch et al) can identify the bowel interposition. Here while passing the needle through the illuminated abdominal wall, skin incision continuous aspiration is created; if air gets aspirated before entering the endoscopically visible gastric lumen, it confirms the bowel interposition.

Feeding can be started in 48 hours. If needed catheter tube can be changed with a new one by railroad technique only after 4 weeks. Complications like skin infection, gastric wall necrosis, gastric leak, colon injury can occur occasionally.

Complications of PEG—Abdominal wall infection; migration of the gastrostomy tube; interposition of bowel (small or large) between stomach and abdominal wall while doing and getting injured is a real risk which may cause fatal peritonitis or external faecal fistula or gastrocolic fistula; separation of stomach wall from abdominal wall causing leak; inadvertent early pulling and extraction of the PEG tube which may settle spontaneously and only occasionally may need a laparotomy but observation of all such patients is a must.

Laparoscopic-assisted endoscopic gastrostomy is probably technically comfortable to a laparoscopic surgeon. Laparoscope is passed through an umbilical crease incision. With 15 mm Hg pneumoperitoneum, peritoneal cavity is inspected and proper site on anterior wall of the stomach is selected; pneumoperitoneum is reduced to 7 mm Hg. Four T fasteners are inserted into the peritoneal cavity to form a square pattern in the greater curvature and they are together held with traction to bring anterior wall of the stomach close to the abdominal wall; 16 gauge needle and guide wire or nylon is passed percutaneously through the abdominal wall into the stomach lumen. By doing gastroscopy, guide wire position may be confirmed and procedure may be continued by passing the PEG tube per orally across guide wire which has been brought to mouth through gastroscope into anterior abdominal wall. Alternatively through a J guide wire across the needle into the gastric lumen and dilatation, PEG tube can be directly facilitated into the gastric lumen across the abdominal wall.

GASTROJEJUNOSTOMY

Gastrojejunostomy can be anterior or posterior or Roux-en-Y types. It can be antecolic or retrocolic. In palliative procedures, gastrectomies and antecolic anterior gastrojejunostomy are done. In chronic duodenal ulcer with pyloric stenosis after truncal vagotomy, posterior retrocolic gastrojejunostomy is done. Roux-en-Y gastrojejunostomy is done after subtotal high gastrectomy or in recurrent diseases or whenever there are complications after initial drainage procedures **(Fig. 20-28)**.

Anterior Gastrojejunostomy

Only gastrojejunostomy is done perhaps as a palliative procedure in gastric outlet obstruction due to advanced distal gastric tumour when patient is presenting with vomiting (by Wolfer). It is often done in advanced unresectable carcinoma of pancreas or duodenum with obstruction. Gastrojejunostomy along with gastric resection for malignancy is usually of antecolic type as mesocolon may get involved by the tumour or might have already involved.

Patient is kept with nasogastric tube. Often stomach wash using normal saline may be needed. Stomach wash is better given using a gastric tube like Ewald's. Electrolyte estimation, anaemia should be assessed. Adequate hydration with normal saline should be done.

Procedure is done under general anaesthesia. Upper midline incision is done. Abdomen is explored for secondaries in liver, peritoneum and ascites. Primary tumour is assessed for resectability. Advanced carcinoma can be resectable as palliation even though it is not operable with lymph node clearance. In fact, when possible resection is better palliation than gastrojejunostomy. Usually anterior gastrojejunostomy is done as a palliation. Posterior gastrojejunostomy is not possible in advanced carcinoma of stomach as posterior surface is not accessible and also often fixed. As anterior gastrojejunostomy is nondependent and takes more time to start functioning, it is better to add on enteroenterostomy between afferent and efferent loops (jejunojejunostomy – Braun's) **(Fig. 20-29)**.

Stomach, proximal to the growth/obstruction is selected. It should be mobile and more towards greater curvature. Two Babcock's forceps are used to hold the part of the anterior wall of the stomach at greater curvature proximally and distally for about 8 cm in between; often lower end may be slightly deviated towards the lesser curvature, but it is not mandatory. It is better to separate the greater omentum adjacent to the proposed gastrojejunostomy anastomotic site by ligating the branches of the gastroepiploic arcade for 8 cm.

Ligament of Treitz is identified at duodenojejunal junction; inferior mesenteric vein that runs underneath very closely is also a marker to identify the duodenojejunal junction. This step is essential to avoid inadvertent selection of ileal loop leading to disastrous wrong gastroileostomy. After opening, mucosal pattern also confirms the jejunum (valvulae conniventes mucosal folds). Thirty cm length of the jejunum is brought towards the selected part of the stomach as antecolic.

Segment of the jejunum is held parallel to the part of the stomach held with Babcock's forceps. Antimesenteric part of the jejunum is used for anastomosis. Stay sutures are placed using 3-0 silk or vicryl at the corners of the selected parts of the stomach and jejunum taking seromuscular bites from both stomach and jejunal corners. Two occlusion clamps are placed proximal to the selected parts of the stomach and jejunum. Clamps prevent bleeding from the cut edges, prevent spillage of the bowel contents into the peritoneal cavity and also to steady the bowel. (Presently many surgeons feel that occlusion clamps are not necessary as when cautery is used bleeding will not occur; spillage can be controlled by using good suction device; this is more true probably while doing retrocolic gastrojejunostomy, as applying occlusion clamp towards gastric side is more cumbersome; however in olden days, occlusion clamps like Carwardine's or Lane's twin clamps were used for the same). Wet gauze is often placed in between two bowel segments as a sausage to absorb the spilled contents posteriorly; but one should remember to remove it at the end **(Figs 20-30A and B)**.

Presently, it is proved that single layer interrupted (both edges two layers) or continuous 2 or 3 zero vicryl all layer sutures are sufficient. However whenever gastric wall oedema is present and nutrition is inadequate, two layers (both edges four layers) anastomosis is done. Here again, outer layer may be placed as continuous or interrupted seromuscular (Lembert in interrupted) sutures.

In four layer anastomosis, posterior seromuscular suture is placed as continuous or interrupted using silk sutures. In continuous type, sutures are placed from one end to other end for about 5–6 cm length each bite is taken at 5 mm interval; from the jejunal side, it is of practice that to take bite 5 mm posterior to the antimesenteric border so that later incision on the jejunum will run on the antimesenteric line; once it reaches other end, suture material with needle is kept in wet gauze which is again used at a later period for anterior seromuscular layer. During continuous suturing, once or twice knots may be placed in between to prevent loosening. Posterior seromuscular layer ideally should involve submucosa also, even though depth assessment is blind. In interrupted posterior seromuscular suturing, 3 zero silk is used in same place as continuous suture line; ideally all sutures are placed first and kept long; knots for each is tied afterwards; ends of tied sutures are not cut immediately instead are held upwards to give traction so that gastrotomy and enterotomy is done easily. Once opening is done in the stomach and jejunum ends of these sutures are cut. Stomach is incised first; then jejunum is incised; jejunal opening should be smaller than gastric opening as jejunal wall stretches and enlarges significantly.

Anterior wall of the stomach is opened (gastrotomy) using number 15 blade or cautery for 5 cm; it runs 5 mm from the posterior seromuscular suture line. Ends of the cuts in gastric and jejunal side should be 1 cm shorter than posterior seromuscular suture line. It is often practiced to ligate small but definitive bleeders from the cut edges of the stomach using 4 zero vicryl (von Haberer submucosal sutures); however bipolar cauterization is more than sufficient for that. Gastric rugae mucosal pattern may be identified. Jejunum is opened using number 15 blade for corresponding length. First seromuscular layer is incised at full length; then mucosa is opened at one point; bile will exude out to confirm that lumen is exposed; nontoothed dissecting forceps placed into the lumen along the line of incision; using curved scissor rest of the jejunum part is incised. Jejunum also can be opened using cautery. Jejunal mucosa bulges out.

Second posterior all layer sutures are placed using 2-0 or 3-0 vicryl or silk. At the left angle, needle bites are taken from outside in of the gastric cut edge and inside out from jejunal cut edge which are tied with knots. Suture material is passed again into the lumen at the left angle; continuous sutures are taken as through and through all layers towards right side. Bites are taken at 2–5 mm intervals and 2–5 mm



Figs 20-28(1)



Figs 20-28(2)



Figs 20-28(3)

Figs 20-28(1 to 3): Gastrojejunostomy (GJ) technique. Note the isolation of the both gastric and jejunal parts; stay sutures; doing first gastrotomy and then jejunotomy; opening in the jejunum should be shorter than the gastric side; note the mucosal look and pattern of both gastric and jejunal wall; note the vessels in the cut edge of the gastric wall which can be ligated with 4 zero silk (von Haberer); note the posterior layer continuous suture and anterior inverting suture; clamps used are occlusion type ideally elliptical one; twin clamps can be used; stoma should be checked for patency; in posterior gastrojejunostomy, gastric wall should be fixed with interrupted seromuscular sutures to make stoma infracolic.



Fig. 20-29: Anterior gastrojejunostomy is done for advanced carcinoma of stomach.

from the edges. Care should be taken that all layers are included in the suture bites; less mucosa with more serosa is taken to avoid eversion but to create inversion. Once in 3-4 bites, locking of the suture is done to prevent purse string effect on the stoma. It is reached to the right edge.

Here needle bite is taken from inside-out of the jejunum at the angle and outside in of the stomach side to reach anterior wall and continue as anterior all layer (3rd layer) sutures. Continuous sutures of inside-out and outside-in can be taken. Connell stitch can be used here—with outside in of the stomach edge and inside out of the stomach edge


Slot
Screw
Carwardine's two clamps shown separately with slot and screw
A
Carwardine's twin clamps attached
B

Figs 20-30A and B: Carwardine's twin clamp and or Lane's gastrojejunostomy clamp used for gastrojejunostomy.

again; then looping across the wound edge towards jejunal side to pass again outside-in and inside-out at jejunal edge which is again looped across towards stomach edge of the wound. This 3rd layer passes from right towards left. Prior to completion of the 3rd layer, it is often advisable to pass the nasogastric tube across the efferent loop. Near the left angle during ending, the suturing continues as through and through sutures. Last bite should pass beyond the beginning bite to avoid gap as a possible site of leak. Suture is tied to the end of the first bite suture. Second layer is also can be placed as interrupted all layer vicryl sutures.

Final 4th anterior seromuscular layer is placed, using already kept silk suture in the wet gauze after completion of the 1st layer. Bites as seromuscular inverting sutures are taken towards left end and are tied to the original end.

Corner sutures additionally may be placed, if needed. Stoma should admit two fingers to confirm adequacy. Patency and integrity of the stoma should be checked. Omentum can be wrapped around the stoma.

Often afferent and efferent loops are communicated with short enteroenterostomy (jejunojejunostomy) to avoid alkali reflux. It is done usually 20 cm from the gastrojejunostomy site. Patency and integrity of the stoma should be checked. Jejunojejunostomy is also done using stapler **(Fig. 20-31)**.

Gastrojejunostomy can also be done using stapling device. Stay suture is placed on the right side ends of the selected stomach and jejunum. Stomach and jejunum loop are brought together. Small gastrotomy and enterotomy are done in the left side of gastric and jejunal side. One fork of the linear cutting stapler device is inserted into the stomach side and other onto the gastric wall side. Both walls are adjusted properly with proper placing of the antimesenteric border of the jejunum. Device is locked; interpositions of other tissues are avoided by careful look; stapler is fired and removed accordingly. Staple line is observed for bleeding; such specific points are reinforced with 3 zero or 4 zero vicryl sutures. Gastrotomy and enterotomy wounds are closed using 3 zero vicryl continuous sutures. These both openings can also be closed using 55 mm linear stapler. Abdomen is closed in layers without keeping drain.

Posterior Gastrojejunostomy

It is done in case of duodenal ulcer after truncal vagotomy as a drainage procedure, especially whenever there is scarring and stenosis with gastric outlet obstruction. It is posterior, retrocolic, short afferent loop (5-8 cm), oblique or vertical gastrojejunostomy (of Mayo) with completed anastomosis lying in infracolic compartment. It is not commonly advocated in malignancy as tumour invasion of mesocolon may obstruct the gastrojejunostomy loop.

Preparation

Stomach wash is required using saline in case of gastric outlet obstruction. Electrolyte estimation, daily preoperative intravenous normal saline infusion, correction of alkalosis, magnesium deficiency are needed. Nasogastric tube is passed.

Technique

Upper midline incision is placed. Once truncal vagotomy is done, mop is kept in the vagotomy site which should be removed at the end prior to closure. Gastrocolic omentum is opened, through lesser sac posterior surface of the stomach is exposed **(Fig. 20-32)**.

Transverse colon is held forward through the laparotomy wound to expose transverse mesocolon. Through transillumination, middle colic vessels are identified. Avascular plane usually towards left of middle colic (but can be on either side) is identified; held with haemostat and opened (for 6-8 cm) to reach the posterior surface of the stomach which is brought through this rent in the mesocolon. Posterior surface of the gastric wall is held with Babcock's forceps on two sides—one at greater curvature (towards right), another at lesser curvature (towards left). (Greater curvature towards greater surgeon; lesser curvature towards lesser surgeon). Many advocate fixing the mesocolon edge to the stomach wall with interrupted 3 zero silk sutures 2 cm from the proposed gastrojejunostomy site to keep it infracolic. But it is usual practice to do this once anastomosis is over which allows the placement of occlusion clamps comfortably on the gastric wall side. First loop of the jejunum is identified by recognising duodenojejunal junction using ligament of Treitz and inferior mesenteric vein. Afferent loop should be only around 8 cm, unlike in anterior antecolic type. Occlusion clamps are placed on gastric and jejunal side. Sausage gauze can be kept between stomach and jejunal segments. Stay sutures are placed from corners of the selected parts of the stomach and jejunal wall using seromuscular 3 zero silk suture; Babcock's forceps can be removed. Posterior seromuscular continuous or interrupted 3 zero silk sutures are placed with each bites at 5 mm interval. (In single layer anastomosis, this step is not necessary) Gastric wall is opened using cautery or no. 15 blade and curved scissor. Jejunum is opened on the antimesenteric margin similarly. Jejunal opening should be less than gastric opening. Posterior all layer anastomosis is done using continuous 3 zero or 2 zero vicryl sutures; in between, locking achieved haemostasis becomes secure and prevents purse string effect on the stoma. It is continued as anterior all layer suturing using Connell suture or continuous sutures; it is tied to the original end of the vicryl. Then anterior seromuscular suture is placed as continuous or interrupted silk sutures. Clamps are removed; any bleeding points are controlled by suture. Stoma should allow two fingers through it. Mesocolon is sutured to stomach wall 1-2 cm away from the suture line (both anteriorly and posteriorly). It is done to prevent herniation of the small bowel through mesocolon (Stammers).

Variations in Technique

Traditional method is outer seromuscular using silk continuous sutures and inner all layer vicryl sutures. Outer seromuscular layer can be interrupted sutures. Inner layer is usually continuous.

Single all layer sutures using interrupted or continuous silk or vicryl can also be used for gastrojejunostomy.

Roux-en-Y gastrojejunostomy can be done in case of complications after gastrojejunostomy.

Stapler gastrojejunostomy reduces the operating time.

Postoperative Care

Nasogastric tube aspiration is continued for 3-5 days. Once nasogastric tube aspiration reduces to minimum, it is removed. Oral sips are started.

Intravenous fluid is given for first 5 days. Antibiotics may be needed.

Complications

Anastomotic bleeding (1.5%) can occur which is confirmed by blood in the nasogastric tube. It usually subsides in 24 hours. Rarely it may require reopening and placing additional suture at the bleeding point. Leak from the site may occur which again may need reexploration.


Sausage
Occlusion clamps are applied
Jejunum is opened on its antimesenteric border
Stay suture
After posterior layer suturing anterior layer is sutured
Occlusion clamps are removed
After posterior layer suturing, anterior layer is sutured

Figs 20-31(1)



Figs 20-31(2)

Fig. 20-31: Jejunojejunostomy between afferent and efferent loop.

Initial delayed gastric emptying is due to stomal oedema or suture line haematoma which resolves spontaneously. Haematoma is more common in stapled anastomosis as stapler is not entirely haemostatic.

Efferent loop obstruction can cause persistent vomiting. Delayed gastric emptying in spite of adequate anatomical stomal opening is often difficult to manage.

Twist in the mesentery can cause afferent loop obstruction. Afferent limb syndrome can occur if the afferent limb becomes larger than needed; it is due to accumulation of large quantity of bile in the lengthy afferent limb making it as a reservoir which impairs its motility leading to poor afferent loop emptying. This false reservoir empties at time together into the stomach causing bilious vomiting in the morning time.

Antecolic gastroenterostomy shows poorer gastric emptying; causes afferent loop syndrome and volvulus compared to retrocolic type.

Jejunogastric intussusception is rare but definitive complication which occurs in loop (omega) gastrojejunostomy only; not in Roux-en-Y type. In 80% cases efferent limb intussusception occurs; 20% cases afferent; rarely both. It causes acute abdomen pain, haematemesis, tender mass left side of the umbilicus. Contrast X-ray shows coiled spring appearance; gastroscopy is diagnostic. Treatment is surgical resection, doing gastrectomy and Roux-en-Y anastomosis.

VAGOTOMY

Dragstedt in 1940–1942 started vagotomy through thoracic approach. He also later in 1951 postulated that just vagotomy is not sufficient; drainage procedure is essential and truncal vagotomy should be combined with either pyloroplasty or gastrojejunostomy. It used to be the standard surgical therapy for peptic ulcer disease for around 40–50 years. Later selective and highly selective vagotomies became popular. However presently because of the availability of good drugs, surgical therapy is specified mostly for refractory duodenal ulcers, and complications like bleeding and pyloric stenosis. Truncal vagotomy and posterior gastrojejunostomy is more suitable for pyloric stenosis (gastric outlet obstruction) due to chronic duodenal ulcer. Proximal gastric vagotomy/PGV (highly selective vagotomy) is the procedure of choice with refractory ulcers. Grinding, propulsive and retropulsive action of antral mill (antral motility) mainly depend on vagal nerves through their nerves of Latarjet. It is essential to empty the solid food by grinding food into chyme then propelling across the pylorus. Liquid emptying is basically by pressure in the body and fundus of the stomach. Antral mill is weakened permanently by truncal vagotomy. Pyloroplasty is probably done whenever there is bleeding.

H2 receptor antagonist like ranitidine, should be discontinued 24 hours prior to surgery; Proton pump inhibitors (PPIs) should be discontinued 7 days prior to surgery. It restores the acidity of the gastric lumen which reverses the bacterial colonization of the stomach which is important especially when drainage procedure is undertaken to prevent sepsis.

Truncal Vagotomy

General anaesthesia is used. Nasogastric tube should be placed. Patient is placed in supine head up (reverse Trendelenburg) position. Upper midline incision is placed; often it is necessary to extend 3 cm proximal to xiphoid process and across the umbilicus. Occasionally, excision of the xiphoid process may be needed. In olden days, surgeons were using left upper paramedian incision. Now it is not practiced. Routine exploration is done after laparotomy. Duodenal ulcer is identified with scarring, deformed duodenum and dilated stomach. Cayenne pepper look may be evident on the surface. Head of the pancreas should be examined for possible presence of the gastrinoma, of course it is often difficult to feel on table as lesion may be small. It is better if gastrinoma is suspected to do specific evaluation like serum gastrin estimation and multidetector CT (MDCT) abdomen.

Left triangular ligament is divided if needed, even though it is not necessary always. Inferior phrenic vein which is on the extreme right extent of the ligament should not be injured. Left lobe of the liver is folded towards right to expose the hiatus properly. Self retaining retractor is placed. Assistant is asked to hold the greater curvature of the stomach with wet mop to give traction downwards and towards left gently. This makes vagus taut to feel like string. Peritoneum on the front of the hiatus is incised and opened horizontally to expose the anterior surface of the oesophagus. Dissection begins on the left side of the hiatus. Index finger is passed gently from left side behind the oesophagus towards right side by breaking loose areolar tissue; any small vessels if encountered are fulgurated with bipolar cautery. Nasogastric tube inside oesophagus guides the dissection as well. Posteriorly aortic pulsation can be felt. Gently hepatogastric ligament is incised on the right side to allow index finger to pass and encircle the hiatus; with further blunt, sharp and cautery dissection hiatus is dissected properly. Infant feeding tube or Penrose drain is encircled around hiatus to facilitate the traction. With traction towards left and downwards, hiatus is further dissected posteriorly.

First anterior vagotomy is done. Anterior vagal trunk is felt like string while running finger in front of the oesophagus. Traction on stomach below is continued. Vagus is dissected of the oesophagus using right


Dilated stomach due to pyloric stenosis
due to chronic duodenal ulcer
Transverse mesocolon
Transverse colon
Middle colic vessels
Posterior surface of the stomach
Transverse
mesocolon
Middle
colic vessels
Transverse
colon
Transverse mesocolon opened
towards left of the middle colic vessels
Transverse mesocolon - opened
Stomach - posterior surface
is held with Babcocks
Stomach - posterior surface
is held with Babcocks
Duodenojejunal junction
is identified by ligament
of Treitz and by inferior
mesenteric vein location
First loop of jejunum is taken
~10 cm from DJ junction
for anastomosis
Posterior surface of the stomach
Jejunal loop is held with Babcocks
Colon
Stomach
Sausage
Jejunum
Both stomach and jejunum
are brought together
Occlusion clamps are applied
Occlusion clamps are applied
on both gastric and jejunal side

Figs 20-32(1)


Stay sutures are placed on the corners
Stay sutures are placed on the corners
Both sides are brought close together
Stay suture
Occlusion clamps
Gastric wall is opened first with No 15 blade or cautery
Gastric wall is opened first with No 15 blade or cautery
Mucosa ic cut with curved scissor
Cut gastric mucosa
Jejunal mucosa protruding
Jejunum is cut 5 mm behind the antimesenteric border using No 15 blade–jejunal cut should be shorter than gastric wall cut
Opened jejunal mucosa
Begining of single layer-posterior layer - vicryl suturing as continuous suture
Gastric mucosa
Jejunal mucosa
Suturing posterior layer - all layer continuous
Completion of posterior layer and begining of anterior layer as inverting suture; Connell suture also can be used for anterior layer
Posterior layer in - sutured with posterior layer of jejunum
Anterior layer in stomach
Anterior layer in jejunum
Inverting sutures of anterior layer

Figs 20-32(2)



Inverting sutures of anterior layer

Completion of anterior layer

Completion of anterior layer
- completion of GJ anastomosis

Completion of anterior layer
- completion of GJ anastomosis

Release of occlusion clamps
- observed for anastomotic site bleeding

Release of occlusion clamps
- observed for anastomotic site bleeding

Completion of gastrojejunostomy

Posterior, retrocolic, short loop
(afferent), oblique, isoperistaltic GJ

Additional sutures should be taken
if needed or cut edge is bleeding

Sausage is removed

Transverse mesocolon edge should be sutured
to stomach wall - as seromuscular interrupted
sutures - to make stoma infracolic

Transverse mesocolon edge should be sutured
to stomach wall - as seromuscular interrupted
sutures - to make stoma infracolic

Figs 20-32(3)



Figs 20-32(4)

Figs 20-32(1 to 4): Posterior gastrojejunostomy—technique.

angled forceps; any small bleeders should be fulgurated with bipolar forceps. Nerve hook may be used for dissection. About 2-3 cm length of the nerve is dissected. Two long curved haemostats are placed on the dissected nerve. Nerve segment (1cm) is excised between clamps. It should be placed in a bottle for biopsy with anterior vagus as label. Vagal ends are ligated with 2 zero silk suture. Long suture is needed to pass the ligature around. Additional anterior vagal trunks may be present in 40% of individuals and they should be dissected and cut. Small nerve fibres should also be divided. It is done by giving traction to the greater curvature **(Fig. 20-33)**.

Posterior vagotomy is done next. This nerve is more away from the oesophageal wall, unlike anterior trunk. Often it may be on the right crus of diaphragm. Oesophagus is held towards left; on the hiatus towards right, gentle dissection helps to identify it. It is thicker than anterior vagus. It is also similarly clamped, divided and excised (1 cm) and cut ends are ligated with silk. Posterior vagus often is associated with a significant sized vein which if get disrupted can cause bleeding. It is again sent for biopsy in separate bottle. Lower oesophagus for 7 cm is dissected meticulously and all nerve branches are identified and divided. Criminal nerve of Grassi is behind the hiatus; it also should be divided. Nerve fibres along the fundus and angle of His are also dissected and divided. Entire OG junction and lower oesophagus should be cleared of the nerve branches to avoid incomplete vagotomy and so recurrence of ulcer. Posterior vagus is commonly a single trunk unlike anterior vagus. Incidence of additional posterior vagal trunk is only 5%. Communicating trunk to anterior vagus is often present which should also be divided. Missing of posterior vagus is common and intact posterior vagus is one of the common causes of incomplete vagotomy. Posterior vagotomy is done often in different methods. First index finger is passed left of the hiatus behind the OG junction and with traction on the stomach, posterior vagus can be felt as a string like thick structure which is hooked with index finger from left to delineate left side and forward; it is clamped, 1 cm of it is excised and ligated by surgeon or assistant similarly. In another modification, entire hiatal dissection is not necessary. Only right side is dissected to identify the posterior vagus to complete the vagotomy. Coeliac branch is in a constant position as a constant single trunk which is identified close to the left gastric artery; if this branch is traced upwards, posterior vagal trunk is identified. This avoids extensive dissection and prevents complication. Truncal vagotomy should be completed with a drainage procedure like posterior gastrojejunostomy **(Figs 20-34 and 20-35)**.

Note:

Truncal vagotomy can be done through laparoscopy also. Vagotomy with antrectomy also can be done which reduces the ulcer forming area of the stomach and also reduces the gastrin release (gastrin is released from G cells of the antrum).

Proximal Gastric Vagotomy (PGV)

It is also called as parietal cell vagotomy (PCV) or highly selective vagotomy (HSV) or superselective vagotomy. It denervates the supply of cells in fundus and body specifically. Meantime, it preserves antropyloric gastric emptying function. PGV reduces both acid and pepsin secretion. PGV was first described by Amdrup and Johnston in 1969.

Indications

PGV is useful in refractory/intractable duodenal ulcer; repeated recurrences by drug therapy, perforated duodenal ulcer when presents within 24 hours; selected bleeding duodenal ulcers in females. PGV is not useful in gastric outlet obstruction due to duodenal ulcer.


Upper midline incision
Duodenal ulcer
GB
Transverse colon
Dilated stomach
Deaver retractor
Traction on the stomach towards left and below
With traction on the stomach anterior vagus is felt like a string while palpating with index finger
Peritoneum is incised in front of OG junction
Anterior vagus is dissected and 1 cm is excised
Suturing the cut end with silk
Opening the peritoneum all around

Figs 20-33(1)


Dissection of the oesophagus
Encircling the hiatus and oesophagus
Hooking the posterior vagus from left
Ligating the cut end of posterior vagus

Figs 20-33(2)

Figs 20-33(1 and 2): Technique of open truncal vagotomy.

Advantages

It is safer with less than 0.3% mortality. Dumping syndrome or diarrhoea is not known. Antral pump is retained and so drainage procedure is not needed. Basal acid secretion reduces to 80%; maximum acid response to stimuli (pentagastrin) is reduced to 60%. Developing anaemia, tuberculosis, osteoporosis, and carcinoma are not present.

Disadvantages

Lesser curve necrosis even though is rare but is a definitive complication. Ulcer recurrence rate is higher which is 10-15%. Dissection on the proximal part along the OG junction, angle of His and distal 7-8 cm of oesophagus is most crucial to prevent recurrence or to avoid failure due to incomplete vagotomy.

Technique

Preparation, position, incision are same as truncal vagotomy. Many surgeons suggest that hiatus should be dissected early with identification and dissection of vagal trunks first. It is probably not necessary or may be an option for individual surgeon. Oesophageal hiatus is mobilised using index finger and encircled with a Penrose or infant feeding tube. Anterior vagal trunk is carefully felt and identified; it is dissected gently and slinged using silk suture material or vascular slings. Similarly posterior vagus is dissected on the right side of the hiatus, and slinged. Greater curvature is mobilised; posterior surface of the stomach is also mobilised. Anterior PGV is done first. Crow's foot is identified. PGV begins from uppermost branch of the crow's foot; if crow's foot is not obvious then at a point of 6 cm from the prepyloric vein of Mayo (pylorus) dissection begins. A stay suture



Fig. 20-34: Barium meal X-ray showing gastric outlet obstruction due to pyloric stenosis due to chronic duodenal ulcer.

using 3 zero silk is placed at this point on the lesser curvature. Lesser omentum where it joins the lesser curve shows three distinct layers, if carefully dissected; first anterior layer gastric branches of anterior vagus; 3rd posterior layer gastric branches of posterior vagus; middle a loose areolar tissue. PGV begins always from distal to proximal. Gastric branches are very closely associated with vessels entering the stomach at lesser curvature, even though their directions are different (vessels are transverse; nerves are oblique). Using a fine haemostat, vessels are clamped, divided and tied using 3 zero silk individually very close to the gastric wall. It is often better to dissect the vessels for adequate length before passing a ligature towards lesser curve side followed by placing a haemostat on the lesser curve side to cut in between. This prevents bleeding and haematoma formation. It is continued up to the OG junction and later extends in front of the oesophagus towards left beyond the angle of His. Haemoclips and cautery should not be used. Haemoclip may slip causing bleeding and preventing further dissection properly. Cautery may transmit the energy along the nerve of Latarjet. Once anterior leaf is dissected and denerved properly, posterior vagotomy begins. Crow's foot in posterior vagus is not identified. Dissection begins 6-7 cm from the pylorus towards proximally along the posterior leaf of the lesser omentum very close to the lesser curvature of the stomach. Devascularisation with denervation is done similarly from below upwards towards OG junction; near OG junction criminal nerve of Grassi is identified which crosses behind the oesophagus. Often stomach is rotated to dissect the posterior part properly; but it is not necessary. One has to remember that stomach wall should not be included in ligatures.

Distal 8 cm oesophagus should be denerved properly and completely. Anterior vagus is gently retracted towards right and all nerve fibres are felt and divided carefully. Often fibres embedded in the oesophageal muscle are also divided; fibres along the angle of His are also divided. Posterior vagus is retracted towards right and OG junction towards left; distal 8 cm of posterior oesophagus is again cleared of all nerve fibres.



Figs 20-35A and B: Posterior, vertical, short loop, retrocolic gastrojejunostomy of Mayo. Vagotomy should be combined with gastrojejunostomy.

Entire lengths of both vagi are dissected completely and both nerves of Latarjet are visualised. Slings and Penrose rain are removed. Lesser curvature of the stomach is imbricated with 3-zero silk suture to prevent the devascularisation, perforation or lesser curve necrosis; it also prevents the nerve regeneration.

Gastroepiploic nerve along with the right gastric and epiploic artery when present should be divided. It is divided at the junction of the right and left gastroepiploic artery. Adding this, is called as extended proximal gastric vagotomy.

Ontable tests (intraoperative) are often used to confirm the completion of vagotomy. *Burge test*; ontable oesophagus and pylorus is closed to convert into a closed system; vagus nerve is electrically stimulated; intragastric pressure is recorded using a manometer; pressure rises in incomplete vagotomy. *Grassi test*; pentagastrin is injected intravenously during intraoperative period; gastrotomy is done; pH of the gastric mucosa is assessed before and after vagotomy; pH is less than 2.5 before, but more than 5.5 after vagotomy.

Complications of Vagotomy

Intraoperative

When left triangular ligament is mobilised more than usual, it may cause injury to the hepatic and phrenic veins causing bleeding.

Splenic injury even though rare can occur while retracting spleen towards left. It is more often seen in enlarged spleen. It can occur also during traction over the greater curvature of the stomach and whenever there are fibrous adhesions between spleen and greater curvature of the stomach.

Oesophageal laceration can occur when hiatus is mobilised from left side with index finger. Laceration usually occurs on the right posterolateral oesophageal wall. Tear should be exposed by rotating the oesophageal wall and is sutured with interrupted silk sutures. Often Nissen's fundoplication wrap may be useful. Nasogastric tube should be kept in situ for 7-10 days postoperatively. Injury is more while doing revagotomy or in patients with any previous upper abdominal surgery.

Other rare but known complications are—pneumothorax; oesophagogastric disruption; distal pancreatic injury; thoracic duct injury.

Early Complications

Gastric atony can occur due to altered gastric pacesetter potential, and normal propagation of peristalsis is altered. Ectopic pacemaker may appear which reduces the normal fundal pacemaker function leading into gastric atony. Atony leads into delayed emptying. Contrast (water soluble) study will show emptying of the gastric content but slowly. Endoscopy reveals widely opened stoma.

Transient dysphagia is seen in 10% of patients. It is due to temporary operative trauma; less commonly due to vagotomy.

Lesser curve necrosis (0.3%) occurs in 72 hours. They present with toxicity and features of perforation. It is initially thought due to devascularisation; but probably, it is due to gastric distension which causes compression on vascular network in already ligated vascular area. It requires reexploration, excision of the necrosed area, until it bleeds and resuturing. Jejunostomy may be required. Gastrectomy may also be needed.

Subphrenic abscess formation due to sepsis can occur. Occasionally infection may spread above to cause dreaded mediastinitis.

Long-term Complications

Twenty percent of truncal, 3% of selective, 1% of proximal gastric vagotomy will develop bowel disturbances like diarrhoea. It is episodic, with urgency of passage of mucus and flatus and stool. Truncal vagotomy can cause severe disabling diarrhoea in 1% of patients. Stasis, hypoacidity with bacterial overgrowth, changes in intestinal villi, altered biliary and pancreatic exocrine function, dysmotility of small bowel are the probable causes. It usually gets controlled with passage of time. Restriction of fluid, carbohydrate and milk products, neomycin, loperamide, codeine, cholestyramine are the treatments for vagotomy diarrhoea. Severe disabling persistent incapacitating diarrhoea (20 times a day stool with incontinence) needs surgical correction. Reverse jejunal interposition is the treatment.

Disruption of crural fibres due to dissection may cause reflux oesophagitis and later stricture formation.

Truncal vagotomy increases the incidence of gallstone formation. Because of hepatic divisions, gallbladder becomes hypotonic; decreased release of cholecystokinin from the duodenum is also the cause for gallstone formation.

PYLOROPLASTY

It is done in case of bleeding duodenal ulcer. Though this bleeding is controlled by various methods. It is also done as part of the procedure in creation of gastric reservoir for oesophageal substitution or bypass, if pyloromyotomy is not undertaken or not possible **(Fig. 20-36)**.



Fig. 20-36: Types of pyloroplasty.

Types of Pyloroplasty

Heineke–Mikulicz pyloroplasty

Upper midline incision is used for laparotomy. Duodenum is mobilised by Kocherisation. Peritoneum is held on the lateral part of the 2nd part of the duodenum and is incised along the margin of the duodenum. Finger dissection further facilitates the mobilisation. Avascular lateral duodenal ligament that runs between duodenum and retroperitoneum is also divided. Curved scissor and cautery can be used for the same. About 5 – 6 cm incision is made along the lower antrum, pylorus and 1st part of the duodenum longitudinally to its entire thickness. Bleeding points are cauterized using bipolar cautery. Opened pyloroduodenotomy wound is closed transversely as full thickness interrupted 3 zero vicryl or silk sutures **(Fig. 20-37)**.

First midpoint suture is placed; then sutures are placed on either side. Once midpoint suture is placed and is held long with a haemostat, remaining sutures are placed from one corner towards middle on either side. Second seromuscular suture is also placed often but it is difficult as it often tears. If there is no tear interrupted, seromuscular sutures can be placed, but it is not mandatory. Omentum is wrapped around it as a secure. Stapling closure also can be done easily using 55–4.8 mm linear stapler.

Emergency Surgical Management of Bleeding Duodenal Ulcer

Bleeding from duodenal ulcer is either from the small vessels in the wall of ulcer crater or due to erosion into the gastroduodenal artery. **Precipitating causes are—**alcohol, NSAIDs, steroids, excessive fibrosis and atherosclerotic disease.

Forrest classification of bleeding or bled ulcer

- Ia Spurting and bleeding
- Ib Nonspurting but active bleeding
- IIa Visible vessel with red or blue protrusion or pulsatile pseudoaneurysm
- IIb Nonbleeding ulcer with clot overlying
- IIc Ulcer with haematin base
- III Clean ulcer—no clot, no vessel

Usually posterior duodenal ulcer bleeds; bleeding from small vessels in the wall of ulcer is due to sloughing of the ulcer. It is less severe,


Kocherisation and pyloroduodenal longitudinal incision
Stay sutures are placed after making full thickness incision
Middle suture bite is taken and kept in haemostats as a marker
A
From the corners all layer silk interrupted sutures are placed towards middle marker suture
Completed single layer closure-interrupted
Note: Seromuscular layer is difficult to place; if needed only it is placed
Omental wrap on the suture line
B

Figs 20-37A and B: Heineke–Mikulicz pyloroplasty.


Coeliac artery
Left gastric artery
Right gastric artery
Ligation
Gastroduodenal artery
Bleeding DU
Underrunning
A
Gastroduodenal artery
Suture ligation
Ulcer
Stomach
Duodenum
B

Figs 20-38A and B: Bleeding duodenal ulcer is treated by underrunning the ulcer bed or ligating the gastroduodenal artery in two places.

gradual and often well-controlled by conservative treatment. Bleeding from erosion of gastroduodenal artery is severe, torrential and almost always needs early surgical intervention **(Fig. 20-38)**.

Indications for surgical treatment: In spite of conservative treatment, condition of patient deteriorates; bleeding from gastroduodenal artery; recurrent bleeding; elderly patient; if more than 4 units of blood required immediately.

Technique

After laparotomy, adequate Kocherisation is done. Pyloric channel and first part of the duodenum (gastroduodenum) are opened longitudinally, bleeder is identified. Underruning of the bleeding area with 2 zero silk or vicryl is done. Proximal and distal bleeding points are transfixed using 2 zero silk sutures. Deep transverse pancreatic artery which is a deep posterior branch of gastroduodenal artery should be occluded by placing a deep middle transfixing suture in the ulcer bed. If the bleed is from gastroduodenal artery, then it has to be ligated to stop the bleeding. It is done by dissecting above the duodenum where it originates from the common hepatic artery. Aneurysm needle may be used to pass a secure ligature around. Gastroduodenal artery also often needs to be ligated inferiorly to prevent backflow of blood; it is ligated below after defining and dissecting just above the origin of the right gastroepiploic artery. Keeping 5 mm distance from the origin, it is securely ligated with transfixation sutures using 2 zero silk. Opened gastroduodenum is closed by ***Finney's pyloroplasty.*** Truncal vagotomy may be done together, if only the general condition of the patient is good.

Finney's Pyloroplasty (1922)

It is done in bleeding duodenal ulcer and when wide pyloroplasty is needed.

Upper midline incision is used. Kocherisation is done adequately. Junction of the pylorus and first part of the duodenum is held at its upper margin with a Babcock's forceps or stay suture. Distal part of the greater curvature is brought closer to the pancreatic side of the 2nd part of the duodenum. Seromuscular sutures (3 zero silk) are placed between distal part of the greater curvature of the stomach and proximal inner part of the duodenum which are tied either after placing all sutures or individually after placing sutures one by one. A 'U'-shaped incision is made from greater curvature towards proximal duodenum which is deepened to have a full thickness gastroduodenotomy. Inner all layer suturing is done using 3 zero silk or vicryl from upper most apex part of the posterior layer towards downwards direction. Once lowermost part is reached, it is continued in front as anterior all layer continuous Connell sutures from below upwards. Anterior seromuscular interrupted 3 zero silk sutures are placed at the end. It is supported with omental patch. Truncal vagotomy may be added **(Figs 20-39A to D)**.

Complications

Bile leak due to anastomotic dehiscence is possible, especially when pyloroplasty is done in a scarred duodenum. Infection, subphrenic abscess formation, delayed gastric emptying are other complications.

Note:

Kennedy duodenoplasty is similar like pyloroplasty but distal to the pylorus on the proximal part of the first part of the duodenum;


Kocherisation
Placing distal greater curvature and inner duodenal wall closure
Seromuscular sutures are placed
A
Posterior seromuscular interrupted sutures
'U' incision
'U' opening of the pyloroduodenum
B
Posterior all layer continuous vicryl sutures
Same is continued as anterior all layer vicryl continuous sutures
Completion of anterior all layer continuous suture
C
Anterior seromuscular interrupted sutures- completed
D
Omentum placed on it

Figs 20-39A to D: Finney's pyloroplasty.


Longitudinal incision over the duodenum distal to pylorus
Closure of the full thickness wound horizontally

Fig. 20-40: Duodenoplasty is done distal to pylorus (Kennedy).

longitudinal full thickness incision is closed transversely **(Fig. 20-40)**. *Dudd pylorectomy*: Here ulcer crater is excised by a diamond-shaped incision along with pyloroplasty.

Antrectomy (hemigastrectomy): Here ulcer bearing area in the stomach is removed and pyloric antrum with either gastroduodenal or gastrojejunal anastomosis is done. It is done in case of recurrent ulcers or in Zollinger Ellison syndrome. It removes the gastrin secreting area (G cells). Antrectomy as a primary procedure is not routinely done for duodenal ulcer.

Gastric mucosal resection (Kirk, 1972): It is done in recurrent ulcers. Here antral mucosa is dissected and removed without ligating vessels externally. It is done after vagotomy. Anterior gastrotomy is done from pylorus 8 cm proximally and 3 cm distally to open entire distal stomach and duodenum. Using pH probe, proximal acid secreting mucosa and distal alkali secreting mucosa is marked at junction. Submucosal injection of 1 in 2,00,000 saline with adrenaline is injected around 300-500 ml. it distends and separates the mucosa and also prevents bleeding. Onto this mucosa, only circumferential incision is made at the pylorus junction and mucosa proximal is dissected off from the submucosa like tube for 8 cm. Proximal part is also transected circumferentially. Small bleeders are fulgurated using bipolar cautery. Mucosal edges proximal and distal are brought together using 3 zero vicryl sutures continuously taking bites deeply up to muscular layer.

GASTRECTOMY

Removal of the part or entire stomach surgically is called as gastrectomy. It can be antrectomy (hemigastrectomy), partial (65%), subtotal (80%), total or radical (nodal clearance) gastrectomy.

Gastrectomy reconstruction can be Billroth I or Bilroth II type. Billroth I is gastroduodenostomy; Billroth II is gastrojejunostomy.

Professor Hans Theodor Billroth did first gastrectomy with gastroduodenostomy in 1881 **(Figs 20-41 to 20-43)**.

Gastrectomy with Billroth I Methods of Anastomosis

Classical Bilroth I operation is partial gastrectomy with gastroduodenostomy with closure of lesser curve and anastomosis at greater curvature side. Horsley, von Haberer–Finney, von Haberer, Schoemaker, Kocher are different Billroth I modifications.


Billroth I anastomosis
Billroth II anastomosis

Fig. 20-41: Billroth I and II anastomosis after gastrectomy.


Subtotal gastrectomy (80% or above removed)
partial gastrectomy (65-75% removed)
Antrectomy (hemigastrectomy)
Total gastrectomy

Fig. 20-42: Anatomical meanings of hemigastrectomy, partial, subtotal and total gastrectomies.



Fig. 20-43: Technical meanings of distal, proximal and total gastrectomies. Proximal gastrectomy is done rarely now; probably done in OG junction growths only; even there, total gastrectomy is preferred by many.

Preparation

Gastroscopy and adequate biopsy are must; CT abdomen to detect additional pathology; adequate hydration; electrolyte management; evaluation of cardiac and respiratory systems are needed. Nasogastric tube and urinary catheter should be passed. Preoperative/perioperative antibiotics are a must as once stomach is opened, field gets contaminated.

Indications

Partial gastrectomy with Billroth I procedure is done in benign gastric ulcer (proved by endoscopic biopsy), benign tumour of the distal stomach, trauma to distal stomach, recurrent or bleeding duodenal ulcer, if pyloroplasty is not feasible. In carcinoma distal stomach, Billroth I anastomosis is usually not done as recurrence in bed when it occurs will cause obstruction due to encasement of the relapsed (local) tumour; whereas in Billroth II gastrojejunostomy, stoma recedes upwards and leaves away from the gastric bed and also omentum and colon interposes between gastric bed and stoma.

Technique

Patient is in supine head up position. General anaesthesia/epidural are given. Abdomen is approached through upper midline incision extending down towards left of the umbilicus. Abdomen is explored for any additional findings. Gastric ulcer area is felt for its location and adhesion. Self retaining retractor is placed. If initially benign gastric ulcer ontable is doubtfully malignant then a gastrotomy is done well away proximally and four quadrant biopsies are done and sent for frozen section biopsy and proceeded further accordingly.

For a benign condition, there is no need to remove the omentum. Kocherisation is done adequately. Gastrohepatic ligament (lesser omentum) is opened using index finger and gently posterior wall of the stomach is separated using finger dissection; if there are adhesions, these are released after release of greater omentum under direct vision. Greater omentum is clamped with two haemostats, divided and ligated sequentially between greater curvature and gastroepiploic arcade; alternatively bipolar cautery or ligaseal or harmonic scalpel (energy sources) can be used to free the greater omentum on the resecting part of the stomach (like in mobilisation of greater omentum in omentoplasty); alternatively, many advocate ligation of the greater omentum outer to the gastroepiploic arcade. Energy sources can be used for the same (harmonic). Right gastroepiploic artery is retained if arcade is retained. Once greater curvature is freed of the omentum, posterior surface of the stomach is easily seen by everting it; if any adhesions are present, these should be divided either with sharp dissection using scissor or cautery or harmonic scalpel. These adhesions if forced with finger for release will cause troublesome bleeding. Dissection close to the origin of the right gastroepiploic vessels should be done with care as small multiple veins may get torn causing bleeding. Middle colic vessels are very close and care should be taken not to injure them; especially middle colic artery if injured will cause transverse colon ischaemia. Middle colic vein joins right gastroepiploic vein which joins the portal vein or superior mesenteric vein. Middle colic vein may be ligated if need arises **(Fig. 20-44)**.

Left gastric vessels are ligated usually at midpoint of OG junction and pylorus along the lesser curvature. Left gastric vessels are clamped together; two haemostats (medium or large) proximally and one distally are applied; it is divided in between proximal and distal (keeping right angled forceps underneath) using number 15 blade or fine scissor. Proximal part is once transfixed with silk and another ligated. Distal part is also ligated using silk. One should confirm that there is bleeding or loosening of the ligature. Often alternatively, left gastric vessels are dissected using right angle forceps for 1.5 cm and ligature is passed and ligated both proximally (2 or 3) and distally (one) and divided in between; lengthy ligature ends are held traction during division. But it is now practiced that left gastric artery and vein are individually dissected, isolated and ligated separately, but it is technically difficult. Left gastric vein is caudal to artery. Few more


Benign lesion
Kocherisation
Lesser omentum is opened, Index finger is passed underneath behind posterior surface of the stomach to reach greater omentum
Left gastric artery
Right gastric artery
Right gastroepiploic artery
Left gastroepiploic artery
Arterial arcade and branches are identified
Alternatively greater omentum can be separated by ligating omentum outer to epiploic arcade with ligation of right gastroepiploic artery
Greater omentum is separated by ligating branches entering the stomach from epiploic arcade
Left gastric artery is ligated securely at lesser curvature
Line of resection
Separated omentum
A
B
C
Techique of ligating left gastric artery
Two clamps are applied on each lesser and greater curvatures at the line of resection
Gastric side stomach is transected using cautery or no. 15 blade; finger or instrument should be kept underneath as guard (protection)
Crushing clamps (Payr's) on specimen side occlusion clamps on gastric remnant side
Similarly clamps are applied on the duodenal side (pyloric end)
Specimen of gastrectomy
Deeper underneath through and through continuous suture
Over and over continuous suture on to deeper suture
Lesser curve is sutured by sewing machine technique

Figs 20-44(1)


Final gastroduodenal anastomosis
Crown/purse string stitch at 'angle of sorrow'

Figs 20-44(2)

Figs 20-44(1 and 2): Gastrectomy with Billroth I anastomosis—technique. It is usually done for benign lesions.

small vessels along the lesser curve at this point are also ligated and divided. Remaining gastric stump is supplied by the ascending branch of left gastric artery, left gastroepiploic and short gastric arteries. Similarly left gastroepiploic vessels (commonly two veins will be present at this level) are ligated along the greater curvature side at the point of resection of the stomach.

Nasogastric tube is palpated and pulled out proximally away from the line of applying clamps and line of division. One occlusion clamp is applied along the lesser curvature towards middle of the stomach directed downwards from lesser curve side; another applied horizontally from greater curvature side towards middle of the stomach. Large Payr's clamp is applied or (two Kocher's clamps or Parker Kerr crushing clamps) on the specimen side below. Stomach is transected in between, leaving clear margin on the proximal side; transection is done using number 15 blade from lesser curve towards greater curve with keeping finger or flat instrument behind as a guard to prevent inadvertent injury to deeper structures. Cautery can be used for the division. Antral mucosa should be completely removed.

Distal part is lifted upwards to visualise the posterior aspect. Small vessels between pancreas and stomach are cauterised or ligated and divided. Right gastric artery on the upper margin of the pylorus is dissected, ligated and divided. Other vessels in the lesser curve are also ligated and divided. Often instead of single right gastric artery, there will be leash of right gastric vessels which are ligated and divided. An occlusion clamp is applied on the 1st part of the duodenum after mobilizing duodenum for 1.5–2.0 cm. Duodenum is dissected gently using bipolar and finger. A Kocher's clamp is applied on the distal part of the specimen; duodenum is divided similarly using number 15 blade. Duodenal clamp is removed once to inspect its mucosa for completion of removal of entire antral mucosa; finger is passed inside to feel for orifice of duct of Santorini and ampulla of Vater (which is 7 cm from the pylorus). Care should be taken not to injure the bile duct. If duodenal division is done within gastroduodenal artery level (not beyond) then it is less likely that pancreatic ducts are injured. Bleeding from the cut edge of the duodenum should be adequate. If greater omentum is mobilised outer to the epiploic arcade by dividing fat and vessels of the greater omentum, then right gastroepiploic artery is to be ligated close to pancreas and where it enters the duodenal lower margin and greater curvature. There is rare chance of loss of omental viability by ligating both right and left gastroepiploic arteries; in such situation, omental excision can be added. Right gastroepiploic vessels can be ligated divided as a bulk (mass tie) between proximal two and distal one ligatures; but present practice is identifying vessels individually and dissecting and ligating.

Alternatively duodenal part of the dissection and ligating of right gastric artery and separation from the pancreas, clamping and dividing the duodenum can be done first, later lifting the specimen upwards, forwards and towards left. Left gastric and left gastroepiploic vessels are addressed. Stomach is similarly transected between clamps.

Lesser curve oblique clamp is held upwards; using 2 or 3 zero silk or vicryl, this part of the lesser curve is closed using sewing machine suturing technique. Here from the lesser curve end, needle bite is taken underneath the occlusion clamp and tied outside; tail end is held with a haemostat; continuous bites are taken underneath the clamp from lesser curve side towards the tip of the clamp as through and through running sutures; once this suture is reached up to the tip of the clamp, clamp is released; knot is tied to the last loop of the suture material; it is continued as over and over continuous suture towards the tail end of the suture material at lesser curve where it is tied with knot. Interrupted seromuscular layer suturing (Lembert) is also done on this layer.

During mobilisation and dissection of stomach, care should be taken to protect spleen, pancreas, duct of Santorini, common bile duct, middle colic artery. Duodenal mobilisation should not go beyond the gastroduodenal artery. Adhesion between pancreas and stomach distally is most crucial; care should be taken not to pull the stomach and do blunt dissection; instead sharp or bipolar cautery dissection should be done. Clamps used should be ellipsoidal and after applying compression should be uniform on the bowel. Clamp steadies the gut, prevents spillage, prevents oozing from the cut edges of the stomach and duodenum. Straight clamps even though commonly used are more damaging than ellipsoidal. These occlusion clamps when applied on your finger and after locking it, should not be painful.

Billroth I gastroduodenal anastomosis is done. Posterior interrupted silk stay sutures are placed; later tied after taking all bites. Posterior all layer through and through vicryl continuous suture is done from lesser curve end towards greater curve end; bites are taken at 3-5 minutes interval at 3-5 mm from the cut edges; locking is done once in 3 or 4 bites to prevent purse string and for haemostasis. Same is continued as anterior all layer through and through sutures towards lesser from greater curve. Connell sutures can be placed to invert the mucosa. In lesser curve, it is sutured tail end of the suture material. Anterior seromuscular interrupted silk sutures are placed afterwards. *Angle of sorrow* (***Jammerecke***) is angle where lesser curve end meets the sutured upper duodenal end. It should be reinforced with *crown stitch/ purse string stitch/ triple seromuscular stitch*. Bite (seromuscular) is taken from anterior gastric wall to posterior gastric wall and from posterior duodenal wall towards anterior duodenal end and tied with a knot. Often this stitch alternatively can be taken prior to completion of the suturing of the angle of sorrow which is kept untied and tied only at the end. Patency of lumen is confirmed by admitting the tip of the thumb. Usually nasogastric tube is negotiated across gastroduodenal stoma. Tube drain may be kept and is removed after 5-7 days.

Note:

Stapler can be used for closure of lesser curvature.
Present concept is gastroduodenostomy should be performed without clamps to avoid tension.
In olden days for suturing inner layer, *Moynihan atraumatic straight intestinal needle* were used (not now). They were used with hand for suturing.

Tanner's method: Twin gastroenterostomy clamps (Lane's) can be used for anastomosis by applying their blades on both duodenal and gastric sides.

Pauchet's operation/maneuver is used in high gastric ulcer with distal stomach lifted upwards to visualise the ulcer bearing area on the lesser curvature and tongue-like piece of lesser curve containing ulcer is excised and immediately sutured.

In a high lesser curve ulcer where access is difficult especially in obese individual, lesser curve can be created without application of the clamp. Here suturing begins from lower part of the proposed lesser curve, continuous sutures are applied upwards as '*open climbing*' technique until lesser curve end is reached. It is often guided by nasogastric or orogastric tube.

In von Haberer method, reefing and purse string is done to lower greater curvature part of the cut end of the stomach so that it is buried to avoid angle of sorrow.

In Schoemaker modification, entire lesser curve and antrum are removed; new lesser curve is created by hand suturing or stapling device.

In Horsley's modification, duodenum is anastomosed to lesser curve end of the stomach.

In von Haberer Finney's modification, opened entire cut end of the stomach is sutured to the side of the mobilised 2nd part of the duodenum with closure of the duodenal stump.


Angle of sorrow
Resection (partial)
Cut duodenal end is anastomosed to greater curvature of the stomach

Fig. 20-45: Gastrectomy with Billroth I anastomosis.


Cut duodenal end is anastomosed to lesser curvature of the stomach

Fig. 20-46: Gastrectomy with Horsley's modification of Billroth I anastomosis.

In Maingot's modification of von Haberer Finney's technique, duodenal stump is not closed; but its end is given a cut on its inner part (like a Cheatle's cut in small intestine) to widen the duodenal stoma which is anastomosed to the lower cut end of the stomach towards greater curvature after suturing lesser curvature.

Pylorus preserving Billroth I procedure and vagus preserving Billroth I procedures are advocated in Japan for early gastric cancers **(Figs 20-45 to 20-51)**.

Postoperative care

Nasogastric aspiration is done for 5 days. Then oral sips are started. Respiratory exercise, early mobilisation and Deep vein thrombosis (DVT) prophylaxis should be given. Antibiotic coverage, fluid and electrolyte management, observations are mandatory. Drain is removed in 5-7 days.

Complications

Stomal oedema, gastric paresis, stomal obstruction, anastomotic dehiscence and bile leak, sepsis, subphrenic abscess formations are known complications.

Gastrectomy with Billroth II Methods of Anastomosis

It is partial/subtotal gastrectomy with closure of the duodenal stump and achieving the continuity by doing gastrojejunostomy. Billroth first did this procedure on 1885 January 15. It was anterior antecolic gastrojejunostomy. So many modifications were done at a later period on this. Kronlein (1887); Von Eiselsberg (1889), Braun (1892); Roux


Closure of the entire gastric cut end and duodenal stump anastomosed to the posterior surface of the stomach

Fig. 20-47: Gastrectomy with Kocher's modification of Billroth I anastomosis.


Lesion
(Benign gastric ulcer)
After resection, duodenal inner wall is cut open to widen the stoma
Once new lesser curve is created, this duodenal stump is anastomosed to greater curvature

Fig. 20-48: Gastrectomy with Maingot's modification of Billroth I anastomosis.


Removal of entire lesser curvature and creation of new lesser curve with duodenal anastomosis to the greater curvature

Fig. 20-49: Gastrectomy with Schoemaker's modification of Billroth I anastomosis.


Extra length in greater curvature end is burried with a purse string suture
Cut end of duodenum is anastomosed with reefed cut end of the stomach with narrowed gastric stump by reefing/purse string

Fig. 20-50: Gastrectomy with von Haberer modification of Billroth I anastomosis.


Entire open end of the stomach is sutured to the side of the 2nd part of the duodenum with duodenal stump closure

Fig. 20-51: Gastrectomy with von Haberer Finney's modification of Billroth I anastomosis.

(1893); Reichel (1908; Polya (1911); Hofmeister–Finsterer (1914); Balfour (1917); Moynihan (1923) are different modifications.

Indications

Gastric ulcer where Billroth I is not possible; carcinoma pylorus and antrum as a radical or palliative procedure; recurrent ulcers; trauma to distal stomach and duodenum are different indications.

Preparation

Gastroscopy and biopsy are a must; CT abdomen to stage the tumour; adequate hydration; electrolyte management; evaluation of cardiac and respiratory systems are needed. Nasogastric tube and urinary catheter should be passed. Preoperative/perioperative antibiotics are a must as once stomach is opened, field gets contaminated.

Technique

After doing laparotomy through midline incision, thorough exploration of the abdomen is done for secondaries in liver, omentum, transverse colon, mesocolon, pancreas, primary tumour fixity, resectability, operability, nodal status etc are assessed. Operability means amenable for radical cure. Resectability means even though advanced, primary tumour which is not fixed posteriorly can be removed. Resection of growth (partial gastrectomy) is the best palliation even though it is advanced. In a fixed nonresectable tumour, palliative anterior gastrojejunostomy or Devine's exclusion procedure can be done to relieve vomiting due to gastric outlet obstruction by the tumour **(Fig. 20-52)**.

Kocherisation is usually not necessary for Billroth II anastomosis; if at all needed, only limited Kocherisation should suffice.

For benign lesions, technique of mobilisation is same as detailed above in Billroth methods. For confirmed carcinoma distal stomach, mobilisation is different. Greater omentum is separated from the colon along the avascular plane completely. Greater omentum is included in the specimen. Omental bursa is carefully separated from the transverse mesocolon and pancreatic bed. Care should be taken not to injure middle colic artery. Ligation and division of individual vessels using 3 zero silk or bipolar cautery or ligaseal or harmonic scalpel may be used as techniques to achieve this.

Right gastroepiploic vessels, right gastric artery, descending branch of left gastric artery (left gastric vascular pedicle) and left gastroepiploic vessels are ligated doubly and divided. Gastric remnant attains its blood supply through short gastric vessels and ascending branch of left gastric artery—which are sufficient enough. Retrogastric dissection is carried out carefully meticulously using bipolar cautery and sharp dissection (never blunt dissection). Duodenal part is mobilised from the pancreatic bed for 2 cm by rotating stomach upwards. Occlusion clamp is applied on the duodenal side at 1st part of the duodenum. Payr's crushing clamp is applied on the gastric side; duodenum is cut in between using no. 15 blade with right angled forceps or flat instrument behind. Good bleeding from the cut edge should be ensured from the duodenal stump, otherwise duodenal leak may occur at later period. If tissue is not healthy, edge is trimmed until it bleeds properly.


Stomach
Pyloric growth (advanced)
GJ stoma
Duodenum
Jejunum

Fig. 20-52: Devine's exclusion procedure.

Duodenal stump closure

Duodenal stump closure is an important step. It is done by different methods.

Using 2 zero or 3 zero vicryl or silk from superior to inferior part *sewing machine technique* closure is done; here continuous bites alternatively from right and left sides are taken underneath the occlusion clamp close to it to reach the inferior margin; then clamp is gently released, suture is looped and tightened; same suture material is again passed as over and over suture on the previous suture to reach the superior part and is tied to the tail end with secure knot. If needed, few additional interrupted sutures are placed. There is usually space, and length of the stump is not present to place interrupted Lembert sutures to bury/invert the duodenal stump. Often anterior part of the stump is buried on the prepancreatic fascia with interrupted vicryl sutures to secure the stump further **(Fig. 20-53)**.

Alternatively, clamp placed on the duodenal stump is gently lifted; loose over and over vicryl suture loops are placed from superior margin of the stump towards inferior margin under and over the clamp which is held loosely; clamp is loosened and gently removed by sliding and traction off the duodenal stump; suture is pulled tight. Then purse string thin small seromuscular suture is placed around the stump to invert it. A third layer purse string is placed to invaginate the stump completely (*Tanner's method*). Or Lembert seromuscular suture can also be placed using silk **(Fig. 20-54)**.

Open closure of the duodenal stump without applying the clamp using Connell suture is also practiced. Second layer of mattress silk suture is also required **(Fig. 20-55)**.



Suture material (vicryl or silk) is passed underneath the occlusion clamp alternatively on both sides without looping over the clamp from superior margin to inferior margin; clamp is released and suture is tightened and continued as over and over continuous suture on the stump to reach back to superior margin and is tied to the tail end to complete the closure of the stump

Fig. 20-53: Closure of duodenal stump using sewing machine technique.

Both inner and outer layers are closed using interrupted 3 zero or 2 zero silk sutures also considered safer.

Stapler closure of duodenal stump is safer and saves time with a good apposition. Usually there is no need to invaginate stapler line **(Fig. 20-56)**.

Catheter duodenostomy: It prevents build up of intraduodenal pressure and sutured stump will not distend. It is done in difficult duodenal stump and when doubt is there about the integrity of the stump. Usually lateral duodenostomy is done. Prior to closure of the duodenal stump, right angle clamp is passed into the lumen and 3 mm incision is made at lateral wall in 2nd part of duodenum on its tip; 14 Foley's catheter is passed into the duodenum. Duodenotomy around the catheter is closed by purse string vicryl/silk suture; and is also fixed to abdominal wall and brought out of abdominal wall through a stab incision and fixed to skin. It is usually kept for 10 days. Catheter is irrigated with 5-10 mL of warm normal saline. On 10th day catheter is partly withdrawn to the adjacent of the duodenum; if drainage after low suction becomes less than 100 mL it is gradually removed step by step in 2 days. In case if duodenal stump is impossible to close then catheter duodenostomy is done directly across the stump and is closed around it **(Fig. 20-57)**.

Nissen – Cooper technique: When there is fibrotic ulcer crater (benign) which could not be mobilised and removed, it is left in place on the surface of the pancreas and duodenum, if could not get adequate length, stump should be sutured to the ulcer crater itself in three layers. First layer is from anterior and anterolateral duodenal margin to the distal end of the fibrotic edge of the ulcer crater; 2nd layer is interrupted silk sutures between seromuscular duodenal wall to the proximal edge/lip of the ulcer crater; 3rd layer often is used to appose onto the thickened peripancreatic tissue. It is not done nowadays.

Bancroft Plenk operation: It is done when there is scarred duodenum which cannot be dissected or mobilised; 7.5 cm proximal to pyloric sphincter, circular seromuscular incision is made in the antrum. Muscular tube is dissected off from the mucosa circumferentially up to the pyloric sphincter; entire mucosa is made like tube; seromuscular purse string is placed at the pyloric sphincter excluding antral mucosal tube. Antral mucosa tube is cut and included in the gastrectomy specimen. Duodenal stump is further invaginated over seromuscular purse string suture. It is not done nowadays.

Lahey's method: Here in difficult distal stump, common bile duct is opened; Bake's dilator is passed to identify the duct during duodenal stump mobilisation and closure. Bile duct is closed with T tube.


The same suture material is continued as purse string suture to invaginate the stump
Removed clamp
Over and over through the clamp applied on the duodenal stump
Once it reaches from upper end to lower end, clamp is gently removed and suture is tightened

Fig. 20-54: Duodenal closure by Tanner's method.



Clamp is not applied to duodenal stump; stump corners are held with stay sutures; continuous or interrupted silk or vicryl sutures are placed. Final 2nd layer interrupted silk sutures are placed as seromuscular.

Clamp is not applied to duodenal stump; Babcock's forceps are applied to both edges of the stump together; stump corners are held with stay sutures; continuous or interrupted silk or vicryl sutures are placed; while sutures are on place adjacent Babcock's forceps are removed. Final 2nd layer interrupted silk sutures are placed as seromuscular.

FigS 20-55A and B: Technique of stump closure of duodenal stump without using occlusion/crushing (Payr's clamp).



Fig. 20-56: Stapler duodenal closure.

Completion of gastrectomy and Billroth II anastomosis

Distal end of the specimen (duodenal side) is held upwards and towards left to visualise anatomy posteriorly. Descending branch/left gastric artery is identified and ligated after proximal two secure ligatures. Left gastroepiploic vessels are ligated. Gastric remnant derives its blood supply from the oesophageal branches of inferior phrenic artery, short gastric arteries, proximal gastric branches of the left gastric artery (in 65% partial gastrectomy left gastric artery is ligated distally unlike in subtotal (75 - 80%/4/5th) gastrectomy wherein left gastric artery is ligated at its origin).

Stomach is fully drawn upwards on to the abdominal wound. Duodenojejunal junction is identified in similar way through ligament of Treitz and inferior mesenteric vein. First loop of the jejunum is taken making afferent loop of about 15-20 cm. Lengthy afferent or efferent loop may stand behind gastric remnant causing obstruction. Antecolic or retrocolic approach may be used; antecolic is preferred than retrocolic, as if stomal ulcer develops chances of penetration or formation of the gastrojejunocolic fistula is higher in retrocolic. However different surgeons prefer different approaches. If retrocolic then loop is brought through the transverse mesocolon left of the middle colic artery. Occlusion clamps applied on the lesser curve, on the greater curve and on the jejunal loop. Alternatively twin clamp can be applied. Posterior seromuscular sutures are placed using continuous or interrupted (seromuscular) silk sutures. This suture line runs through the entire length of the stomach curvature and selected loop of the jejunum from greater curvature towards lesser curve. Alternatively only greater curvature side of the stomach is sutured at the stomal length of around 4-5 cm. Crushing Payr's clamp is placed on the specimen side of the stomach. Specimen is cut between occlusion clamps and crushing clamp. Anterior flap of the gastric edge is kept longer than posterior flap. Lesser curve is closed using continuous 2 or 3 zero vicryl sutures as standard sewing machine technique or over and over two layer closure. Earlier placed continuous silk seromuscular suture is continued on the created lesser curve from edge of the lesser curve towards apex of the new lesser curve kept carefully for later continuation over the stoma. One should confirm that jejunum is properly placed with antimesenteric margin properly aligned otherwise oblique anastomosis can cause stomal obstruction at afferent or efferent level. Around 4 cm length of the jejunum is



Lateral catheter duodenostomy is commonly done. It is usually kept for 14 days.

End duodenostomy is done on to the duodenal stump. It is done only if duodenal stump can not be closed due to fibrosis.

Fig. 20-57: Catheter duodenostomy used to decompress the duodenal stump.

opened on the greater curvature (left) side. Posterior all layer through and through continuous sutures are placed using vicryl from greater curvature side towards lesser curve angle; it is continued as anterior layer all layer suture (using Connell suture) to reach greater curvature again and tied with a knot. Anterior seromuscular continuous suture is placed as a continuation of the already placed seromuscular suture on the new lesser curve, thus completing the anastomosis. Clamps are removed. Nasogastric tube should be passed across the stoma along the efferent limb. Any bleeders if present are secured with transfixation. Adequacy of the stoma is checked.

In order to prevent enterogastric bile reflux, jejunojejunostomy is done between afferent and efferent limbs—*Braun's enteroenterostomy*. This prevents bile reflux but diverts bile only partially unlike in *Roux-en-Y anastomosis which is more ulcerogenic.*

Ligatures at all four main vessel sites are observed for its security. Subphrenic spaces are sucked out and cleaned. Duodenal stump closure is observed. Abdomen is closed in layers after placing a tube drain.

Postoperative Care

Nasogastric tube aspiration; observation of vitals, drain site and urinary catheter; respiratory monitoring.

Nasogastric tube is removed in 5 days; oral sips started; drain removed in 7 days.

Note:

Antecolic is said to be better than retrocolic after gastrectomy and Billroth II anastomosis. However both are used all over equally.

Valve is found to be not helpful during anastomosis **(Fig. 20-58)**.

Single layer closure is universally accepted now as far as Billroth II anastomosis.

When placing afferent loop towards greater or lesser curv, it will not make much difference as far functioning of the stoma is considered. Moynihan's placing afferent loop towards greater curvature has gained popularity. Different modifications are shown in figures **(Figs 20-59 to 20-67)**.

Distal Gastrectomy with Roux-en-Y Anastomosis

Cesar Roux, Swiss surgeon from Lausanne described Roux-en-Y anastomosis in 1897. Jejunum is transected 20 cm from duodenojejunal junction; distal cut part of the jejunum is brought upwards towards gastric remnant and anastomosed; proximal cut end is anastomosed to distal cut part of the jejunum 45 cm from its cut margin to maintain the continuity.



Fig. 20-58: Valved gastrojejunostomy.



Fig. 20-59: Gastrectomy with classical Billroth II anastomosis.



Fig. 20-60: Gastrectomy Voneiselsberg modification of Billroth II anastomosis.



Fig. 20-61: Gastrectomy Kronlein modification of Billroth II anastomosis.



Fig. 20-62: Gastrectomy Braun modification of Billroth II anastomosis.



Fig. 20-65: Gastrectomy Finsterer Hofmeister modification of Billroth II anastomosis.



Fig. 20-63: Gastrectomy Balfour modification of Billroth II anastomosis.



Fig. 20-66: Gastrectomy Roux modification of Billroth II anastomosis.



Fig. 20-64: Gastrectomy Reichel and Polya modification of Billroth II anastomosis.



Fig. 20-67A: Gastrectomy Moynihan modification of Billroth II anastomosis.


Csendes procedure

Type IV gastric ulcer within 2 cm of OG junction. Gastrectomy is done with removal of entire lesser curve up to OG junction. Much of the greater curve is preserved; antecolic Roux en Y GJ is done to entire cut end of the stomach from OG junction to greater curve.

Fig. 20-67B: Csendes procedure – with gastrectomy, Roux en Y antecolic GJ to entire cut end of stomach

Indications

Early gastric cancer is a good option but with lymph node dissection. Gastrointestinal stromal tumour (GIST) and leiomyoma are other indications. It has been opined by many that Roux-n-Y anastomosis should be reserved to only subtotal gastrectomy with less gastric remnant. But presently proved that Roux-n-Y anastomosis is better; but Roux syndrome and gastric stasis are the major drawbacks.

Advantages

It shows very less enterogastric reflux and lower incidence of *H. pylori* infection. Gastritis and dumping is less in Roux-en-Y.

Disadvantages

Development of stomal ulcers; gallstone formation; technically additional anastomosis; endoscopic access to ampulla of Vater is lost or difficult; Roux stasis syndrome (25%, inadequate jejunal limb peristalsis).

Technique (Fig. 20-68)

Under general anaesthesia with head up position laparotomy is done with upper midline incision. Thorough exploration of the peritoneal cavity is done. Greater omentum is separated from the transverse


Early gastric cancer or
difficult benign lesions
75% gastrectomy is done
Duodenal stump is closed
Lesser curve is closed
Angle of sorrow
Crown suture
Proximal jejunal
segment is 20 cm
Middle
colic artery
Roux limb
40-45cm
2 cm pouch as
blind end

Through transillumination 20 cm from duodenojejunal junction vascular arcade is divided with ligature or using harmonic scalpel. Distal part is closed to bring up as Roux limb. Proximal part is kept open for end to side jejunojejunosotomy. Stapler dividing can also be done

- Roux loop brought retrocolic left of middle colic artery to do gastrojejunostomy
- Angle of sorrow should be addressed with crow/purse string / triple suture

End-to-side jejunojejunostomy is done.
If stapler is used, side-to-side can be done but without keeping blind end distally.
Roux is fixed to transverse mesocolon

Fig. 20-68: Roux-en-Y anastomosis after subtotal gastrectomy.

colon through avascular lane using scissor or cautery. Middle colic artery should be taken care of. While using cautery, care should be taken not to transmit heat to adjacent colon which may be dangerous. Lesser omentum is divided. Omental bursectomy is done by peeling of the omental layer from the superior part of the transverse mesocolon and in front of the pancreas. Line of proximal resection is marked; descending branch of left gastric artery and vein are ligated securely and divided; branch of left gastroepiploic artery along the arcade is ligated and divided. Stomach is transected using linear stapler device at two levels to create lesser curve and to achieve Roux-en-Y gastrojejunostomy. This can be done by applying pairs of clamps on each part and dividing in between using number 15 blade or cautery. Clamp distal to the resected line with the distal stomach is lifted upwards and towards right to expose posterior aspect of the stomach and duodenum in front of the pancreas. All adhesions between distal stomach and pancreas are divided with cautery or harmonic scalpel. Right gastroepiploic and right gastric arteries are ligated and divided. Right gastric artery may be like leashes of vessels often. Duodenum is mobilised up to the gastroduodenal artery level, not beyond. Small vessels entering the proximal duodenum should be tackled using bipolar cautery. Duodenum is transected using stapler. It can also be transected between two clamps and can be closed by hand suturing. Specimen is removed. Lymph node dissection is also carried out along with gastric mobilisation in case of distal gastric cancer.

Ligament of Treitz is identified; 20 cm from the duodenojejunal junction jejunal loop is selected for mobilisation. Through transillumination, vascular arcades are ligated along the mesentery to get adequate length of the distal jejunum. Jejunum is divided after ligating vascular arcade. It is better to ligate this arcade using 3 zero silk; but harmonic scalpel may be sufficient. About 40-45 cm of Roux limb is selected at distal part of the jejunum which is brought upwards towards gastric remnant. It can be brought retrocolic commonly or antecolic. It is passed through an opening in the transverse mesocolon towards left of the middle colic artery. Stapler line in the gastric remnant is removed partly for 4 cm on the greater curvature side; jejunum is opened on the antimesenteric border 2 cm proximal to the terminal end for 4 cm using cautery. Two layer anastomosis using outer continuous or interrupted silk and inner all layer vicryl sutures. Alternatively single layer continuous vicryl or silk can also be used. Angle of sorrow at the junction with the lesser curve also should be addressed with crown/triple suture. Stoma is confirmed using fingers. Continuity of gut below is maintained by end-to-side jejunojejunostomy after removing the stapler line (side-to-side also can be done wherein stapler line need not be removed). Roux jejunal loop is fixed to the transverse mesocolon with interrupted sutures to prevent herniation.

Nasogastric tube is gently negotiated across gastrojejunostomy stoma distally which acts as a stent. Pedicles, duodenal stump, anastomotic lines are checked again. Suction is done in surgical field. Mop counting is confirmed. Tube drain is placed. Abdomen is closed in layers **(Fig. 20-69)**.

Postoperative Care

Nasogastric tube is removed in 72 hours. Oral sips started and later solid food.

Drain is removed in 5 days.

Complications

- Gastroparesis.
- Dumping syndrome.
- Roux stasis syndrome.
- Afferent loop syndrome.
- Other complications.

Subtotal Gastrectomy with D2 Dissection

Subtotal gastrectomy is still an acceptable reasonable option as it is less morbid with better quality of life than total gastrectomy with equivalent survival rate. But when subtotal gastrectomy is not possible or microscopic margin clearance is doubtful then total gastrectomy is better option, especially when tumour is large occupying almost entire lesser curve or 75% of the stomach or tumour of the body of the stomach. Microscopic margin clearance is most important deciding factor, along with lymph node involvement which should be less than five. Even when there is microscopic clearance but if lymph nodes are positive in more than 5 nodes, then there is no benefit as far as prognosis is considered.

D2 gastrectomy includes—removal of stomach with growth, omental bursa, greater and lesser omentum, anterior layer of mesocolon, anterior pancreatic capsule, D2 lymphadenectomy. D2 dissection is better than D1 dissection of lymph nodes.

Presently newer staging for dissection is practiced in Japan—D1, D2, D3, D4, depending on levels of lymph nodes cleared ('D' for dissection). D1 or D2 dissections are commonly done.

D1 is done when nodes are N0. It is removal of nodes along the lesser and greater curves and pylorus (Group I: Stations 3-6).

D2 is done when nodes are N1. Here nodes like left gastric/common hepatic/splenic/retropancreatic are removed. Splenic nodes can be cleared with or without splenectomy along with removal of tail of pancreas. Here node stations 1-11 are removed. Stations 12-18 are not removed. Average 27 nodes are removed.

D3 is done when nodes are N2. Nodes removed for clearance are hepatoduodenal, nodes along mesentery, middle colic (1-16 stations). Average 43 nodes are removed.

D4 is *not commonly advocated*. It is removal of stations 1-18.

D1—involvement of group I lymph nodes.

D2—involvement of group I and II lymph nodes.

D3—involvement of group I, II and III lymph nodes.

D4—involvement of group I, II, III and para-aortic nodes.

Note:

All lymph nodes are numbered differently as 'stations' or 'echelons'. *D1 gastrectomy* is clearance of perigastric nodes; *D2 gastrectomy* is clearance of nodes along major vessel trunks—along coeliac and splenic arteries. D2 is always better than D1.

Lymph node stations in gastric carcinoma (Japan)—18 stations are there:

1. Right cardiac
2. Left cardiac
3. Nodes along the lesser curvature
4. Nodes along the greater curvature
    a. Along short gastric vessels—4sa
    b. Along left gastroepiploic vessels—4sb
    c. Along right gastroepiploic vessels—4sc
5. Suprapyloric nodes
6. Subpyloric nodes
7. Along left gastric artery
8. Along common hepatic artery
9. Along coeliac axis
10. At splenic hilum
11. Along splenic artery


Incision
Lesion in the lesser curve
Ometum is separated from epiploic arcade either outer to inner to the arcade
Middle colic artery is identified and safeguarded
Middle colic artery
Right gastroepiploic artery is ligated
Right gastric artery is ligated

Figs 20-69(1)



Linear stapler is used to close the duodenal stump

Stapler division and closure of duodenal stump

Caudal/descending branch of left gastric artery is doubly ligated

Occlusion clamp is placed

LINEAR CUTTER
LINEAR CUTTER 75
ETHICON

Figs 20-69(2)



Stomach divided between two clamps from lesser curve using cautery or 15 No blade

Middle colic artery is identified left of it meso colon is opened to pass Roux limb

Jejunal vessels are ligated and divided to create Roux limb

Figs 20-69(3)


Stapler division of jejunum to create Roux limb
Roux limb side close to end is opened
Roux limb is anastomosed to stomach cut end
Gastrojejunostomy
End (stapled) of Roux limb

Figs 20-69(4)





Figs 20-69(5)

Figs 20-69(1 to 5): Gastrectomy with Roux-en-Y gastrojejunostomy.

12. At hepatoduodenal ligament
13. Retroduodenal lymph nodes
14. At root of mesentery
15. Around middle colic artery
16. Para-aortic nodes
17. Around lower oesophagus
18. Supradiaphragmatic

TNM STAGING edition 7th 2010

Tumour – T
- Tx – tumour cannot be assessed
- T0 – no evidence of tumour
- Tis – carcinoma in situ, intraepithelial tumour without invasion
- T1a – invades lamina propria or muscularis mucosa
- T1b – invades submucosal
- T2 – invades muscularis propria
- T3 – invades subserosal connective tissue without invasion of visceral peritoneum or adjacent structures
- T4a – invades serosa/visceral peritoneum
- T4b – invades adjacent structures

Nodes – N
- Nx – cannot be assessed
- N0 – no nodal spread
- N1 – 1-2 regional nodes
- N2 – 3-6 regional nodes
- N3a – 7-15 regional nodes
- N3b – 16 or more nodes

Metastases – M
- M0 – no distant spread
- M1 – distant spread present

Contd...

First tier nodes: Nodes within 3 cm from primary tumour (stations 1-6)—N1 (old TNM).

Second tier nodes: Nodes in main and intermediate arterial trunk (stations 7-11)—N2 (old TNM).

Contd...

Staging
- 0 – Tis N0 M0
- IA – T1 N0 M0;
- IB – T1 N1 M0/T2 N0 M0
- IIA – T1 N2 M0; T2 N1 M0; T3 N0 M0
- IIB – T1 N3 M0; T2 N2 M0; T3 N1 M0; T4a N0 M0
- IIIA - T2 N3 M0; T3 N2 M0; T4a N1 M0
- IIIB - T3 N3 M0; T4a N2 M0; T4b N0-1 M0
- IIIC – T4a N3 M0; T4b N2-3 M0
- IV: Any T Any N M1

- Stage I, II,II: Locoregional disease
- Stage IV: Systemic disease

Japanese Classification of Gastric Carcinoma (JCGC)

It includes following principles:
- Basic rules for clinical, surgical, pathological, and final features
- Specific rules for histology
- Gastric biopsy specimen group classification
- Chemo RT response

Nodal spread as per JCGC:
- Nx – Nodes unknown/cannot be assessed
- N0 – No nodal spreads
- N1 – Group I nodes only involved
- N2 – Group II nodes are involved but not group III
- N3 – Group III nodes are involved

Birmingham staging

1 – Confined to mucosa/muscularis propria
2 – Muscularis/serosal involvement
3 – Nodal spread
4a – Residual disease; 4b – Metastatic disease

Third tier nodes: Nodes at stations 12-18 (para-aortic and above)—N3 (old TNM).

Note: 15 lymph nodes must be removed for adequate staging of nodes

Technique

Preparation is same as other gastrectomy. But CT scan and other modalities of evaluation in relation to secondaries and lymph node status should be done thoroughly.

Under general anaesthesia, laparotomy is done through lengthy upper midline incision which is extended below across the umbilicus. Head up position is preferred (reverse Trendelenburg).

Greater omentum is mobilised from the transverse colon through avascular plane. Anterior leaf of the peritoneum of the transverse mesocolon and peritoneum over the anterior surface of the pancreas is removed (omental bursectomy). Need for omental bursectomy is controversial. Omentum is dissected from splenic flexure of colon and inferior pole of the spleen to expose the tail and body of the pancreas. Left gastroepiploic vessels are divided at their origin from splenic vessels. Short gastric vessels are also ligated and divided. Energy sources like harmonic scalpel are of great use in such situation.

Right gastroepiploic vein is carefully dissected; bleeding is common here as many fragile tributaries are present. Right gastroepiploic vein after being joined by the middle colic vein forms gastrocolic vein which is short and joins the superior mesenteric vein. Right gastroepiploic vein is ligated at its joining junction. If tear and bleeding occur, gastrocolic trunk vein or middle colic vein can be ligated (middle colic artery should be safeguarded). Superior mesenteric vein is dissected in its front, medial and lateral aspects to clear lymph node stations. Right gastroepiploic artery is dissected at its origin from the gastroduodenal artery. Tissues with lymph nodes in front of the head of pancreas and behind the pylorus are cleared.

Gastrohepatic ligament is dissected. Aberrant hepatic artery if present should be preserved. Hepatoduodenal ligament is opened. Common hepatic artery, proper hepatic artery, right gastric artery, gastroduodenal arteries are identified and dissected to remove fat lymph nodes adjacent to it. Right gastric artery is ligated and divided at its origin. It usually arises from proper hepatic artery; but as variation, it can arise from gastroduodenal artery. Small vessels are common in this area which cause troublesome bleeding; so bipolar cautery or harmonic scalpel are better to be used. Kocherisation is needed for proper nodal clearance in relation to duodenum.

Duodenum is transected using stapler in similar way as mentioned earlier. Stapler is ideal; otherwise duodenum is cut between clamps and duodenal stump is closed by one of the suitable methods discussed earlier.

D2 lymphadenectomy is done. It begins by removing fat and lymph nodes lateral to the proper hepatic artery; tissues in front of the portal vein, superior border of the pancreas, in front and behind the common hepatic artery; left gastric vein (coronary vein) is ligated where it joins the portal vein which courses behind the lesser curvature; tissues along and above the splenic artery are also cleared. Coeliac axis is identified; nodes in front of it are cleared; left gastric artery is dissected, doubly ligated and divided and nodes along its origin are cleared. Lymph nodes along the right side of the OG junction along the crura of diaphragm and anterior surface of the abdominal oesophagus (lower 3 cm of abdominal oesophagus should be cleared). Dissection continues along the splenic artery and posterior surface of the stomach. Dissection is continued towards splenic hilum, if nodes are suspiciously involved. Splenectomy is not necessary **(Fig. 20-70)**.

Gastric division is done as *subtotal gastrectomy* (75-80%) by dividing the stomach 2 cm distal to OG junction along lesser curve and 5 cm distal along the greater curvature. Straight occlusion clamp is placed along the greater curvature towards remnant side and along lesser curve obliquely to create lesser curve. Crushing (Payr's) or Kocher's clamps are placed towards specimen side. Stomach is cut using no. 15 blade. Specimen is placed in orientation grid. Intraoperative frozen section biopsy is done to confirm the clearance at margins. Stapler device can be used to divide the stomach at two places. Usually lesser curvature part is transected with stapler. Stomal part is cut with knife between clamps.

Reconstruction is done by omega loop gastrojejunostomy with Braun jejunojejunostomy (ideally antecolic but retrocolic can be used) or Roux-en-Y gastrojejunostomy. Angle of sorrow/angle of death is addressed with crown/purse string/triple suture to stabilise the angle. Nasogastric tube is negotiated into efferent or Roux limb. Feeding jejunostomy may be required. Tube drain is placed. Even though gastric remnant is small, it maintains the OG junction function and remnant acts as small but significant reservoir.

TOTAL GASTRECTOMY

Removal of entire stomach (with cardia, distal oesophageal tube and cuff of duodenum) with nodal clearance may be the oncologically right surgery for carcinoma stomach. Palliative total gastrectomy, even though is done, often is doubtful about its advantages.

Connor did first total gastrectomy in 1884. Brigham, Richardson, Moynihan, Ravitch, etc started doing total gastrectomy.

Indications

Carcinoma involving most of the lesser curvature, carcinoma of body or proximal part of the stomach are probably the indications.
Preoperative preparations are same as subtotal gastrectomy.

Technique

Under general anaesthesia with double lumen, endotracheal tube is used. Patient is positioned supine with left chest upwards in case if extension is needed at a later period. Entire chest and abdomen are cleaned and draped. Upper midline incision with provision for extension into the thorax or bilateral subcostal incision or left upper oblique incision towards left chest wall or left thoracoabdominal incision is used. Lengthy incision is preferred to achieve good exposure **(Fig. 20-71)**.

Procedure is almost same as for subtotal gastrectomy. Mobilisation of the greater omentum from the transverse colon, infrapyloric dissection with ligation of right gastroepiploic vein and artery; suprapyloric dissection with ligation of right gastric artery at its origin and removing fat and lymph nodes along these vessels; duodenal transection; dissection along the cardia and lower oesophagus with clearance of all lymph nodes; ligation of left gastric artery at its origin; left gastric vein is ligated at its joining with the portal vein. Nodes along the splenic artery up to the hilum are cleared. Splenectomy is usually not indicated; but if inevitable arises then should be done. Lymph nodes along the crus of the diaphragm and coeliac artery are removed. Vascular clamp is applied at the line of resection of the lower


Subtotal gastrectomy with D2 lymphadenectomy
Billroth II anastomosis - antecolic, with
Braun enteroenterostomy
Subtotal gastrectomy with D2 lymphadenectomy
Roux-en-Y anastomosis

1. Mobilisation of greater omentum
2. Infrapyloric dissection with ligation of right gastroepiploic vein where it forms gastrocolic trunk; ligation of right gastroepiploic artery at its origin from gastroduodenal artery
3. Suprapyloric dissection with ligation of right gastric artery at its origin from proper hepatic artery; ligation of right and left gastric vein where they join the portal vein
4. Duodenal stump is closed — stapler or hand sewn
5. D2 lymphadenectomy clearing all nodes at proper hepatic artery level towards left at superior part of pancreas along splenic artery, along left gastric artery, along right side of cardia mainly; coeliac lymph node; nodes which originate along the splenic artery — may be removed, if possible
6. Occlusion clamp applying 2 cm distal to OG junction at lesser curve and 5 cm at greater curve
7. Completion of subtotal gastrectomy with D2 lymphadenectomy

Fig. 20-70: D2 lymphadenectomy with subtotal gastrectomy.

oesophagus 3 cm proximal to the OG junction. With crushing clamp on specimen side, specimen is removed.

Reconstruction is done by Roux-en-Y oesophagojejunostomy. Roux limb should be 40-45 cm. Oesophagojejunostomy should be end-to-side. Nasogastric tube should be passed across the oesophageal stoma. Distal jejunojejunostomy is done at 20 cm from the duodenojejunal junction. End-to-side anastomosis is done. If stapler resection of the loop was done earlier then side-to-side anastomosis is done.

COMPLICATIONS OF GASTRIC SURGERIES

Early Complications

Intragastric haemorrhage occurs usually from anastomotic site. It is identified by blood in the nasogastric tube. If it is mild, it can be left alone as it will subside in a day or two. If it is severe then patient develops shock with tachycardia and hypotension. Blood transfusion is required. If persists such patient needs relaparotomy, identification of bleeding point from the anastomotic site and secure suturing of the area using silk or vicryl. Occasionally bleeding can occur from the existing ulcer (duodenal ulcer) which usually subsides once acid level comes down and ulcer starts healing.

Extragastric haemorrhage occurs either from slipping of ligatures of left gastric/right gastric or epiploic arteries. Bleeding can occur from pancreatic bed, omental site or organs like spleen or liver. Nasogastric tube will not show the blood. Signs like shock, palor and low haemoglobin confirms the diagnosis, blood transfusion, relaparotomy and addressing the bleeding area accordingly is needed.

Duodenal blow out/duodenal stump leakage occurs in Billroth II anastomosis. It occurs in 5th-7th postoperative period commonly. Incidence is 3-5%. It is due to duodenal fibrosis, poor blood supply of the stump, pancreatitis, infection, raised intraduodenal pressure. It can also occur if there is obstruction at afferent limb of the loop Billroth II anastomosis without Braun enteroenterostomy. Leak causes sudden pain, tachycardia and initial sepsis; but gradually gets localised. Conservative treatment usually is sufficient. Additional feeding jejunostomy, creation of jejunojejunostomy between afferent and efferent loops usually is sufficient **(Fig. 20-72)**.

Leak from the Billroth I anastomosis is due to partial disruption of the anastomosis, probably few sutures have disrupted. Usually subsides gradually on its own. If it causes leak it is problematic.



Approaches: Lengthy midline; left thoracoabdominal (ideal); bilateral subcostal

1. Mobilisation of greater omentum
2. Infrapyloric dissection with ligation of right gastroepiploic vein where it forms gastrocolic trunk; ligation of right gastroepiploic artery at its origin from gastroduodenal artery
3. Suprapyloric dissection with ligation of right gastric artery at its origin from proper hepatic artery; ligation of right and left gastric vein where they join the portal vein
4. Duodenal stump is closed — stapler or hand sewn
5. D2 lymphadenectomy clearing all nodes at proper hepatic artery level towards left at superior part of pancreas along splenic artery, along gastric artery, along both sides or cardia mainly right side; coeliac lymph nodes; ligation of left gastric artery at its origin; ligation of the left gastroepiploic artery and posteror gastric artery which originates from splenic artery
6. Vascular clamp applying 3 cm proximal to OG junction to the oesophagus
7. Completion of total gastrectomy

Fig. 20-71: Total gastrectomy with oesophagojejunostomy—Roux-en-Y anastomosis.



Fig. 20-72: Duodenal blow out after gastrectomy with Billroth II anastomosis.

Gastrografin study provides a clue for leak. In such situation, relaparotomy is needed. Omental patch over the suture site with a drain placement is often sufficient. Occasionally needs conversion of Billroth I to Billroth II anastomosis. Feeding jejunostomy is needed.

Disruption of gastrojejunostomy is usually seen after Billroth II anastomosis; occasionally occurs after simple gastrojejunostomy also. It needs CT study/gastrografin study, reopening and omental patch if it is small. Often needs conversion to Roux-en-Y anastomosis. Disruption of pyloroplasty needs gastric resection.

Stomal obstruction: Stomal obstruction is due to stomal oedema; afferent loop obstruction; herniation of afferent or efferent limbs; kinking and adhesions at efferent loop level; afferent or efferent loop interposition behind the gastric remnant (herniation into lesser sac). Gastroduodenostomy obstruction if persists (Billroth I) for more than 10 days then it needs intervention by relaparotomy. It is not possible to dismantle the gastroduodenostomy stoma as it will cause leak. It is better to leave it like that and bring a gastrojejunostomy as antecolic in the gastric remnant. Stomal oedema usually subsides over the period of time. Thirty percent of stomal obstruction when persists need relaparotomy. Release of kinking and adhesions, correction of internal herniations of afferent or efferent or both limbs; conversion into alternate procedures like Billroth II or Roux-en-Y or adding one more gastrojejunostomy to gastric remnant are alternatives used.

Afferent loop obstruction: It is due to long afferent loop. Afferent loop is usually taken as 8-10 cm for posterior and 15 cm for anterior gastrojejunostomy. Roux-en-Y anastomosis eliminates afferent loop. Long afferent loop causes kinking of the loop at its junction with anastomosis which leads into duodenal obstruction. This leads into duodenal blow out in case of Billroth II anastomosis. Long afferent loop also can lead into twist, internal herniation, jejunogastric intussusception. All these lead into closed loop obstruction proximally in the duodenum raising intraduodenal pressure exceeding pancreatic duct pressure, abdominal pain, vague tender mass in the abdomen, raised total count and serum amylase mimicking acute pancreatitis. But in reality, there is enormous dilatation of the loop and duodenum which needs immediate laparotomy and surgical decompression or diversion. *Afferent loop obstruction cannot be diagnosed by endoscopy. Surgical treatment*: If loop is viable on laparotomy then creation of



Fig. 20-73: Afferent loop obstruction occurs due to long afferent loop which may herniate or twist or kink.

jejunojejunostomy between dilated afferent and normal efferent limb is suffice. Otherwise resection, dismantling the gastrojejunostomy and creation of Roux-en-Y anastomosis is needed **(Fig. 20-73)**.

Jejunal loop herniation after Billroth II anastomosis can occur as early complication or as late complication also. Herniation occurs in either afferent or efferent loop or both. If afferent loop is short, efferent loop will herniate; if afferent loop is long then afferent loop will herniate behind the gastrojejunostomy or efferent loop. Both loops if fixed to posterior parietal structures, it can be prevented. Relaparotomy is needed; hernia is reduced; mesentery is closed; if needed, afferent, loop is shortened and Roux-en-Y anastomosis is done.

Gastric remnant necrosis occurs in gastrectomies in which left gastric artery is ligated at its origin or splenectomy is also undertaken which compromises the blood supply of the gastric remnant. Gastric remnant after ligation of the left gastric artery maintains the viability through branch from left inferior phrenic artery. As a known variation, if inferior phrenic artery arises from left gastric artery which is already been ligated at its origin, gastric remnant necrosis is most likely to occur. Entire or part of the gastric remnant goes for necrosis leading to acute peritonitis features with coffee ground vomitus which needs immediate surgical intervention. Condition is diagnosed by MDCT abdomen. If part of the gastric remnant is necrosed then resection of that part and creating Roux-en-Y gastrojejunostomy is done; viability of remaining stomach should be adequate. If entire gastric remnant is involved which often may extend to distal oesophagus, then gangrenous part is resected with dismantling of the anastomosis; lower oesophagus is formed into a tube ostomy; cervical oesophagostomy is also done.

Intraabdominal abscess is not uncommon. It can be subphrenic abscess, pelvic abscess, interloop abscess; it can be single or multiloculated. CT abdomen is diagnostic. Higher generation antibiotics, percutaneous drainage or Open surgical drainage is needed **(Fig. 20-74)**.

Postoperative pancreatitis can occur (2-5%). It is usually not due to trauma but due to close proximity. But can occur while dissecting the pancreas in front, while removing the pancreatic capsule. It is treated conservatively. Postoperative jaundice is known to occur after gastric surgeries. It may be due to pancreatitis, anastomotic leak (bile gets absorbed from peritoneal cavity); haemolysis, sepsis, injury to bile duct, cholangitis, anaesthesia toxicity.

Common bile duct injury and injury at ampulla of Vater is uncommon but can occur. It is difficult to manage. Duodenum is opened; common bile duct is exposed; opened duodenum is sutured to head of the pancreas over the disrupted part as a coverage ostomy. T-tube drainage and stenting of ducts on table are other options. Isolated jejunal loop harvested from distal to existing anastomosis can be sutured to the head of the pancreas on to disrupted area. Second Roux loop can be taken to suture to the area **(Fig. 20-75)**.

Omental infarction, stress ulceration, inadvertent gastroileostomy are rare complications.

Late Complications

Alkaline reflux gastritis is commonest postgastrectomy late problem. Bile, pancreatic and duodenal juice is injurious to gastric mucosa. Reflux gastritis can occur in Billroth II (commonly), Billroth I, gastrojejunostomy alone when done and, pyloroplasty. Burning epigastric pain, bilious vomiting, anaemia, bleeding from the stomach are the features. Endoscopy with biopsy is diagnostic which shows oedema and friability of gastric mucosa. There will be acute and chronic inflammation with decrease in parietal cell mass but increase in mucus secreting cells. Prokinetic drugs may help. Measurement of bile acid in fasting gastric aspirate is useful. Surgical treatment is conversion to Roux-en-Y anastomosis; if patient has had pyloroplasty or gastrojejunostomy (after vagotomy) alone, then antrectomy and Roux-en-Y anastomosis to be done as Roux-en-Y perse is ulcerogenic. Many patients may have additionally reflux oesophagitis. Antireflux surgery may be needed in these patients.

Delayed gastric emptying can occur in any type of the gastric bypass. It is probably alteration in the gastric pacemaker activity. In these patients, endoscopy shows normal stoma **(Fig. 20-76)**.

Dumping syndrome can be early or late.

Early dumping syndrome is due to loss of pyloric sphincter mechanism allowing rapid passage of food across the duodenum or proximal jejunum causing vasomotor and gastrointestinal disturbances. It causes palpitation, sweating, increased bowel movements and borborygmi, colicky pain, tachycardia, hypotension, hypovolaemia, vomiting and diarrhoea. There is rapid passage of food. It is common (10%) and more severe type. It occurs in 30-60 minutes of eating. It is a primary disorder of carbohydrate metabolism. Initial transient hyperglycaemia prevents further absorption of glucose, which in turn draws fluid from the bowel wall by high osmolarity resulting in increased intestinal activity, resulting diarrhoea, and fall in blood pressure. Radionuclide studies show rapid emptying from


Left gastric artery ligated at its origin earlier
Coeliac trunk
Necrosis of the part of the gastric remnant
Cervical oesophagostomy
Distal tube oesophagotomy
Feeding jejunostomy

Gastric remnant resected
Roux-en-Y anastomosis is done

Entire gastric remnant and distal 1–2 cm of oesophagus will go for necrosis.

It needs resection of remaining entire gastric remnant; jejunojunostomy: cervical oesophagostomy; tube oesophagostomy of distal oesophagus; feeding jejunostomy.

Condition has got high mortality

Fig. 20-74: Gastric remnant necrosis. It is managed by resection of necrosis nonviable part and remaining part is anastomosed with jejunum as Roux-en-Y with feeding jejunostomy. If entire gastric remnant is disrupted then it is managed by cervical oesophagostomy, distal tube oesophagostomy and feeding jejunostomy. Later once patient recovers from shock and sepsis, after 3 months, colonic bypass is required.

the stomach; if patient is asked to drink 100 mL of 50% glucose in water, it will show the early symptoms. In late dumping syndrome, 3 hours after intake of 50% glucose in 100 ml of water will show drop in blood sugar below 50 mg% with concomitant raise in plasma insulin level. Treatment is small, that includes dry food, frequent food intake, avoiding carbohydrate diet, octreotide 100 microgram before food subcutaneously; surgical treatment may be required if patient looses weight, develops anaemia, symptoms persist. Surgical treatment is conversion into Roux-en-Y anastomosis or interposition of 25 cm of proximal jejunal segment as isoperistaltic (*Henley's loop*) between stomach and duodenum or jejunum itself. Vagotomy should be completed in these patients. Poth's double limb pouch is better and satisfactory than Henley's loop. Ulcer formation in the pouch/loop, stasis, obstruction are the problems. Triple limb pouches have also been tried. All these pouches have been tried along with Roux-en-Y anastomosis. Antrectomy is a must if Roux limb is planned. Ligidakis modification of Hunt Lawrence pouch has also been tried. Similar like Henley's loop interposition but loop is reversed during interposition gives better result. Ligidakis pouch is said to provide normal pouch motility, required delayed gastric emptying, without any pouch dilatation and stasis **(Figs 20-77 and 20-78)**.

Late dumping syndrome is of less severe type (5%). It is due to initial hyperglycaemia-induced insulin release which in turn causes hypoglycaemia 2-3 hours after meals. Diarrhoea and boborygmi are not present. Features of hypoglycaemia occur 2 hours afterwards with tremor, fatigue, nausea, sweating, and drowsiness. It is a reactive hypoglycaemia. Symptoms are relieved by glucose but aggravated by exercise. Treatment is reduced carbohydrate meal; increased protein diet; small intake of glucose between meals. Usually surgical correction is not needed for late dumping syndrome.

Dumping may be associated with postvagotomy diarrhoea. It is corrected by Roux-en-Y anastomosis and creating short jejunal reversal loop 100 cm distal to the ligament of Treitz. Dumping


T tube
drainage
T tube
drainage
Roux-en-Y
gastrojejunostomy
Isolated
jejunal
segment
Jejunojejunostomy
Jejunojejunostomy
Jejunojejunostomy
Gastrojejunostomy
Distal CBD
ligated
GB removed
Choledocho
jejunostomy
Duodenal stump
closed
Jejunopancreatic
anastomosis
Spatulation of duodenal stump is done
Disrupted pancreas
from duodenum

Additional Roux-en-Y loop has brought from distal jejunum on to the disrupted pancreas; T tube is placed to bile duct; Tube duodenostomy is also done Gall bladder is removed

Isolated jejunal loop has brought from distal jejunum on to the disrupted pancreas; T tube is placed to bile duct; tube duodenostomy is also done Gall bladder is removed;

Posterior wall of the spatulated duodenum is sutured to pancreatic capsule. Separate stents are passed across the bile duct and pancreatic ducts which are passed through the lumen of duodenum across its lateral wall to bring out of the abdominal wall

Anterior wall of the spatulated duodenum is closed with sutures

Fig. 20-75: Different procedures used for duodeno pancreatic disconnection.


60 cm
Roux limb
Reverse jejunal
loop of 10 cm
40 cm distal part

Reverse jejunal loop interposition with Roux-en-Y loop for severe reflux alkaline gastritis and vagotomy diarrhoea

Fig. 20-76: Reverse jejunal loop interposition with Roux-en-Y loop is done for severe alkaline gastritis and vagotomy diarrhoea.


Isoperistaltic single limb
jejunal pouch (non reversed)
interposition - Henley's pouch

Fig. 20-77: Henley's isoperistaltic jejunal loop interposition (non reversed). It does not give good results compared to reversed jejunal loop interposition.



Fig. 20-78: Reverse jejunal interposition is better than isoperistaltic.

may be associated with reflux gastritis. It is treated with Roux-en-Y anastomosis. Occasionally dumping, reflux gastritis and vagotomy diarrhoea may be associated together. It is treated by Roux-en-Y anastomosis, creation of short reversed jejunal segment distal to the 40 cm end-to-side anastomosis.

Recurrent ulcer: Recurrent ulcer after vagotomy with drainage procedure is treated with antral resection and completion vagotomy. Recurrent ulcers due to Zollinger Ellison syndrome is treated with total gastrectomy with Roux-en-Y anastomosis.

Small gastric remnant syndrome: It is due to reduced gastric reservoir. Patient develops abdominal discomfort by taking food and so restricts caloric diet. Gastric reservoir function is increased by doing different pouches using jejunum. Hunt Lawrence or Tanner Roux 19 pouches are often used **(Figs 20-79 to 20-84)**.

Malabsorption, gastric remnant bezoar formation, motility problems are also known to occur. Gastric remnant bezoar is common in Billroth I anastomosis and pyloroplasty. It is commonly phytobezoars (vegetable matter). Bezoar causes bleeding, perforation and malnutrition. It is treated by digestive agents like enterases, papase and other enzymes. Endoscopy removal may be required. Low fibre diet is required to prevent recurrence. Motility disorders can be treated by prokinetics, urecholine, coherin peptide, etc.



Fig. 20-79: Hunt Lawrence pouch as a reservoir for small gastric remnant.


Double back loop of jejunum with two separate jejunal anastomosis – Ligidakis pouch

Fig. 20-80: Ligidakis pouch. Ligidakis modification of Hunt Lawrence pouch is said to provide normal pouch motility, required delayed gastric emptying, without any pouch dilatation and stasis.



Fig. 20-81: Double limb jejunal pouch – Poth's.

Gastric remnant carcinoma: It is more common after Billroth I operation, can occur in other gastric surgeries also. Reflux with deconjugation of bile acids with hypoacidity; bacterial reduction of nitrates into nitrosamines, and vagotomy—are the causes. Incidence is 5%. It occurs 10 years after the gastrectomy. It carries poor prognosis.

Gastrojejunocolic fistula occurs in retrocolic gastrojejunostomy. It can occur after Billroth II anastomosis or simple gastrojejunostomy (retrocolic) also. Incidence is 5%. Initially marginal ulcer occurs on the anterior wall/rim of the stoma which gradually deepens/penetrates to erode into the anteriorly located colon to create gastrojejunocolic fistula. As marginal ulcer occurs on the anterior aspect of the stoma


Tanner Roux 9 loop for small gastric remnant syndrome

Fig. 20-82: Tanner roux 9 technique for small gastric remnant.


Reverse jejunal loop of 10 cm

Fig. 20-83: Terrence Kennedy reverse jejunum technique. Reverse jejunal loop is interposed in the Roux limb at gastrojejunostomy level.


Triple limb pouch

Fig. 20-84: Triple limb pouch across the Roux limb.


Stomach
Colon
Fistula
Jejunum

Fig. 20-85: Gastrojejunocolic fistula.

in antecolic gastrojejunostomy this ulcer erodes anteriorly into the abdominal wall and not into the colon. Faecal belching, vomiting, emaciation, anorexia, diarrhoea, gross weight loss—are the features **(Fig. 20-85)**.

Treatment is triple resection and maintaining the continuity with gastrojejunostomy, jejunojejunostomy, colocolic anastomosis. It is better to complete vagotomy and Roux-en-Y gastrojejunostomy if patient's general condition permits. In severely ill patient, initial ascending colostomy (*Phiffer*) proximal to colonic component of fistula is done to divert faecal matter so as to reduce the bacterial contamination in the fistula, then at a later stage, definitive triple resection is done. Alternatively often ileo sigmoidostomy (*Lahey*) is done between terminal ileum and sigmoid colon to divert the faecal content **(Fig. 20-86)**.

Roux stasis syndrome: It occurs after Roux-en-Y gastrojejunostomy. Its incidence is 10-30%. When Roux limb is longer, its incidence increases. Intolerance for solids is typical. Distressing bilious vomiting, loss of weight and recurrent pain are common. Gastroscopy shows patent stoma. Contrast study shows normal flow of dye. Radionuclide study reveals severe impairment of the gastric emptying. Roux limb in these patients acts as a barrier for gastric emptying. It shows severe gastric atony. It is common in females. Ectopic pacemaker in the Roux limb gets activated and delays the gastric emptying. There is uncoordinated peristalsis of Roux limb preventing progressive peristalsis. Uncoupled


Colon
GJC Fistula
Stomach
Colon
Duodenum
Jejunum
Jejunum
Fistula
Triple resection

Fig. 20-86: Triple resection for gastrojejunocolic fistula. Condition has got high mortality.

myoelectric complex, increased nonperistaltic and retrograde waves cause dysmotility of Roux limb. Prokinetic drugs will not benefit. Erythromycin may be beneficial. Treatment is conversion into Billroth I or II loop gastrojejunostomy.

Long-term Complications

Chronic afferent loop obstruction: It is due to long afferent loop design in Billroth II reconstruction. It causes recurrent twist or kink at gastrojejunostomy site. Internal herniation of afferent under efferent, stenosis of afferent at junction with stomach, volvulus of the redundant afferent loop, adhesions of afferent loop are common causes. It is recurrent repetitive obstruction. There is projectile vomiting; and vomitus contains bile. Upper abdominal pain develops after meals. Pain is relieved by vomiting. (In reflux gastritis, pain is constant; pain is not relieved by vomiting. Anaemia and bleeding are not uncommon in reflux gastritis). Treatments of chronic afferent loop obstruction are jejunojejunostomy, suspension of afferent loop, resection and shortening of the afferent loop, conversion into Roux-en-Y (ideal) or Billroth I anastomosis.

Chronic efferent loop obstruction is usually due to adhesions and kinking. It is usually intermittent; but often, it may be severe causing efferent loop gangrene. Treatment is surgical. Release of adhesions, conversion into Roux-en-Y anastomosis; require resection if there is gangrene.

Internal hernias after gastric surgery: It can occur as afferent or efferent loop hernias. It is seen in Billroth II anastomosis or simple gastrojejunostomy. It is common in antecolic anastomosis. Here afferent loop is taken larger and there is large space behind the stomach. Retrogastric hernia is more common in such situation. Ideally in antecolic anastomosis, jejunal loops should be fixed to abdominal wall parietes (*Gry and Morton method*) to prevent herniation. But it is not commonly practiced. When afferent loop is sutured to lesser curvature then hernia chances are higher. When anastomosis is done with afferent from greater curvature to lesser curvature side (left to right), herniation of afferent loop is less likely. It is treated by surgical correction.

Jejunogastric intussusception: It is the retrograde intussusception of efferent jejunal loop into the stomach or gastric remnant. It occurs only in loop gastrojejunostomy. It is rare but severe. In 80% cases, efferent limb is involved. Rarely afferent limb or both can be involved. Palpable tender mass on left of the umbilicus, haematemesis, pain on left side of umbilicus radiating towards back are typical. Contrast study shows coiled spring appearance. Laparotomy should be done. Intussusception is reduced; if it is viable, it is fixed to abdominal parietes. If it is gangrenous, resection is done; with Roux-en-Y anastomosis **(Fig. 20-87)**.



Fig. 20-87: Retrograde jejunogastric intussusception (*Courtesy:* Dr Arun kumar Mch GI surgeon).

RAMSTEDT'S PYLOROMYOTOMY FOR CONGENITAL HYPERTROPHIED PYLORIC STENOSIS

It is the manifestation of progressive hypertrophy of muscular wall of the pyloric sphincter muscle. Clinically non-bilious vomiting, palpable olive shaped pyloric mass in upper abdomen in a male infant of 3-4 weeks age; visible gastric peristalsis, with hypokalaemia and metabolic alkalosis sonologically pyloric channel > 3mm thickness and pyloric length > 2 cm is 100% diagnostic. *In 1912, Ramstedt* did pyloromyotomy but could not suture transversely as infant has become severely ill; but surprisingly infant recovered well, without a need for any further surgery.

Preparation

Initial electrolyte and fluid management is needed.

Technique

General anaesthesia is used. Infant is in supine position. Nasogastric tube (narrow/fine tube) is passed. Right upper quadrant transverse incision is used. External and internal oblique muscles are cut; transverse abdominis muscle is split. All layers muscle splitting incision also can be used. Peritoneum is opened. Body of the stomach is identified and held out of the wound. Pyloric hypertrophied mass should not be held as it will cause serosal tear and bleeding. If stomach is not clearly identifiable, then 30 mL of air is insufflated into the stomach to make it distend and visible. Greater curvature of the stomach is held and drawn towards left with traction. Mass extends distally up to the pyloric vein of Mayo. Middle of pylorus and mass on the anterior aspect is relatively avascular and is incised longitudinally for its entire length and thickness. Often muscle may invaginate into the duodenal bulb distally. Care should be taken not to injure the mucosa. If mucosal perforation occurs, mucosa is closed using 3 or 4 zero vicryl and omental patch is placed over it. Small venous ooze can occur due to venous congestion. Monopolar cautery should not be used; if needed, only bipolar cautery should be used. Benson pyloric spreader instrument is very useful to do proper pyloromyotomy. When superior and inferior margins of the cut pylorus move independently then pyloromyotomy is said to be complete.

If mucosal injury prevents further continuation of myotomy procedure, Graham patch of omentum is placed over it and sutured. Myotomy is done by rotating the pylorus to 180° **(Figs 20-88A and B)**.

Problems

Mucosal perforation, incomplete myotomy, postoperative vomiting and electrolyte imbalance, infection, pneumonia—are ontable and postoperative problems.


Thickened pyrloric muscle
Prepyloric vein of Mayo
Bulging mucosa
Muscular layer-cut
Incision for pyloromyotomy
Benson pyloric spreader
Mucosal layer exposed (not cut)
Bulging mucosa
A
Thickened pyrloric muscle
Incision over the pyloric mass
Identifying thick muscle and cutting
Bulging of the mucosa
B

Figs 20-88A and B: Ramstedt's pyloromyotomy technique.

Postoperative Care

Feeding is started in 12 hours with graded protocol. Pyloric muscle regresses to its normal thickness in 12 weeks. Final result and cure rate is excellent.

Laparoscopic pyloromyotomy is equally good and technique is similar but through laparoscopic instruments. Umbilical port is placed for camera. Two 5 mm working ports are placed. Arthroscopy knife is used to make incision over the pylorus. Laparoscopic spreader similar to Benson spreader is available to spread the incised pyloric muscle completely to allow protrusion of the mucosa outwards. One should avoid perforation. Two edges are held apart to confirm the completion of myotomy. Stomach is insufflated with air using orogastric or nasogastric tube to confirm the leak through laparoscopic vision **(Fig. 20-89)**.


Monitor
Anaesthetist
Infant for pyloromyotomy
5 mm
5 mm
Theatre table
10 mm
Camera surgeon
Scrub nurse
Surgeon

Fig. 20-89: Laparoscopic cardiomyotomy.

DUODENUM

Duodenum is derived from *dudekadaktulos* Latin–Greek word that means 12 fingers. It lies at the level of 1st, 2nd and 3rd lumbar vertebrae and at and above the level of the umbilicus in front. It is C-shaped with head of pancreas attached to its inner part. It is widest (2.5 cm), shortest, most fixed part of small intestine. The *duodenum* is 20-30 cm in length. It extends from pyloric sphincter to *ligament of Treitz*. It is divided into four parts. 90% of duodenal ulcer occurs in the 1st part of duodenum (duodenal bulb/cap). CBD and pancreatic duct merges to form *ampulla of Vater* and enter the 2nd part of duodenum. The 3rd part of duodenum is wedged between aorta and superior mesenteric artery.

Proximal part (2.5 cm) of the 1st part of the duodenum is intraabdominal and is mobile; its distal part (2.5 cm) is retroperitoneal.

First part behind is related to the common bile duct, portal vein, gastroduodenal artery and inferior vena cava. In front, it is related to caudate lobe of liver and gallbladder; above the epiploic foramen and below head and neck of the pancreas. At gastroduodenal junction, submucosal glands of Brunner appear which are not present in gastric mucosa. First part is 5 cm long. At superior duodenal flexure, it continues as 2nd part.

Second part is 7.5 cm long that begins at superior duodenal flexure runs downward; at the level of 3rd lumbar vertebra and at inferior duodenal flexure, it turns towards left to continue as 3rd part. Anteriorly is covered with peritoneum except in the middle where it is directly related to transverse colon. Other anterior relations are right lobe of the liver; transverse colon, root of transverse mesocolon, and small bowel. Posteriorly it is elated to right kidney, right renal vessels, inferior vena cava, right gonadal vein (joins the inferior vena cava behind 2nd part of the duodenum) and right psoas major. Medially it is related to head of pancreas and bile duct. Major duodenal papilla is located 10 cm distal to pylorus as an elevation. Accessory pancreatic duct opens at minor duodenal papilla, 6 cm from distal to pylorus.

Third part is 10 cm long that begins at inferior duodenal flexure at the level of the right margin of the lower border of the 3rd lumbar vertebra. It runs horizontally and upwards to continue as 4th part. In front it is related to superior mesenteric vessels and root of mesentery (vein is medial to artery); behind right ureter, right psoas major, right testicular or ovarian vessels; inferior vena cava; abdominal aorta with inferior mesenteric artery; above head of pancreas and uncinate process; below coils of jejunum.

Fourth part is 2.5 cm long; travels upwards left of the aorta up to superior margin of 2nd lumbar vertebra. Here it curves to form jejunum. Its terminal part is mobile. In front it is related to transverse colon, transverse mesocolon, lesser sac and stomach; behind left sympathetic chain, left psoas major, left renal vessels, left testicular vessels and inferior mesenteric vein; to the right upper part of the mesentery; to the left kidney (left) and ureter; above is body of the pancreas.

Suspensory ligament of Treitz is a fibromuscular band which arises from right crus of the diaphragm, passes downward behind the pancreas and splenic vein in front of the left renal vein. It is attached to the upper posterior surface of the duodenojejunal flexure and 3rd and 4th part of the duodenum. It may insert only duodenojejunal flexure or 3rd or 4th parts only or may have multiple attachments. Its proximal part is skeletal muscle; distal part is smooth muscle and in between elastic fibres **(Fig. 20-90)**.

Arterial supply of duodenum: Foregut part of the duodenum is supplied by superior pancreaticoduodenal artery (anterior and posterior), a branch of gastroduodenal artery; hindgut part is by inferior pancreaticoduodenal artery (anterior and posterior), a branch superior mesenteric artery. Other branches are supraduodenal artery of Wilkie, a branch of proper hepatic artery; retroduodenal artery of Edwards Michel, a branch of common hepatic artery. Inferior pancreaticoduodenal artery may arise from 1st jejunal branch of superior mesenteric artery or as a common trunk with 1st jejunal branch **(Fig. 20-91)**.


Ligament of Treitz
L1
L3
Duodenum

Fig. 20-90: Suspensory ligament of Treitz.


Proper hepatic artery
Common hepatic artery
Stomach (removed/reflected) outline
Left gastric artery
Right gastric artery
Coeliac trunk
Splenic artery
Dorsal pancreatic artery
Supraduodenal artery
Gastroduodenal artery
Superior pancreatico-duodenal artery
Anterior and posterior branches of superior pancreaticoduodenal artery
Anterior and posterior branches of inferior pancreaticoduodenal artery
Inferior pancreaticoduodenal artery
SMA
Transverse pancreatic artery
Duodenal branch of 1st jejunal artery

Fig. 20-91: Arterial supply of duodenum.


Stomach (reflected/removed) outline
Portal vein
Left gastric vein
Splenic vein
Anterior and posterior superior pancreaticoduodenal vein
Anterior pancreatico-duodenal venous arcade
Anterior and posterior inferior pancreaticoduodenal vein
SMV
Left gastroepiploic vein
Inferior pancreatic vein
Inferior mesenteric vein
Right gastroepiploic vein

Fig. 20-92: Venous drainage of the duodenum.

Venous drainage is mainly portal, superior mesenteric and splenic veins. Venous arcade is superficial to arterial arcade **(Fig. 20-92)**.

Lymphatic drainage is to pancreaticoduodenal nodes; to hepatic nodes; coeliac nodes; often to pyloric and aortic nodes.

Surgical Significance

Kocherisation is needed in many oesophageal, gastroduodenal and pancreatic surgeries to mobilise the duodenum. It is done by incising the right peritoneal reflection of the 2nd part of the duodenum and mobilising it towards left in front of inferior vena cava and right renal vein and aorta. It is mobilised along the head of the pancreas. Even though plane is avascular, care should be taken not to injure the vena cava and right gonadal vein.

Mobilisation of the hepatic flexure and transverse colon from the 2nd and 3rd parts of the duodenum to expose duodenum proximal to superior mesenteric vein is necessary in colectomy and pancreatic surgeries – *Cattell maneuver*.

Only 2 cm of 1st part of the duodenum can be skeletonised so that to retain the blood supply of the stomach.

Suspensory ligament of Treitz can be divided without any problem.

Duct of Santorini is close to gastroduodenal artery and may get injured in gastrectomy while mobilising the duodenum. Accessory pancreatic duct passes under the gastroduodenal artery (*water under the bridge*); while ligating the gastroduodenal artery (bleeding ulcer), one should avoid anterior medial duodenal wall to avoid injury to gastroduodenal artery. Duodenum should not be mobilised beyond the gastroduodenal artery.

One of the pancreaticoduodenal arteries should be retained ideally to keep head of pancreas viable, otherwise head may go for necrosis.

SURGICAL TREATMENT OF SUPERIOR MESENTERIC ARTERY SYNDROME (WILKIE'S/VASCULAR COMPRESSION OF THE DUODENUM)

It is the compression of the 3rd part of the duodenum between aorta and emerging of superior mesenteric artery which is in front of the duodenum. It is due to acute angulation between SMA and Aorta leading into compression. Bilious vomiting, distension, electrolyte imbalance are the features. Contrast imaging is diagnostic.

Treatment is release of suspensory ligament of Treitz and duodenojejunostomy between proximal dilated 2nd part of the duodenum and jejunum 10-15 cm from the duodenojejunal flexure. Side to side anastomosis is done. Gastrojejunostomy should not be done **(Fig. 20-93)**.

DUODENAL ATRESIA

It is the commonest site of intestinal atresia. It is usually a complete stenosis of the second part of duodenum at the level of ampulla of Vater. It is defective fusion of foregut and midgut with failure of recanalisation. Incidence is one in 10,000 live births.

Types (Fig. 20-94)

Type 1: Complete duodenal atresia: It is the commonest type (50%). It is usually complete separation with intact wall. In 25% cases, complete separation with wall also occurs. Type 2: Fibrous cord. Type 3: Incomplete or partial obstruction. It can be stenosis or web with an aperture. Duodenal diaphragm/web can present as complete; incomplete with a fenestra; incomplete diaphragm with central aperture which causes '*windsock' deformity* due to proximal dilatation. Here actual diaphragm will be proximal to the site of obstruction. Duodenal atresia may be *preampullary* (nonbilious vomiting) or *postampullary* (bilious vomiting). Postampullary is common (80-90%).

Associations

Duodenal stenosis is often associated with annular pancreas. It can be isolated with duodenal atresia or in association with Down's syndrome (30%)/incomplete rotation of gut (20%)/ congenital heart diseases (30%)/trisomy (30%)/anorectal malformations (10%), etc. It is commonly associated with maternal polyhydramnios (50%). Antenatal ultrasonography can confirm it. Fifty percent infants are premature.


Stomach
Duodenum 2nd part
Aorta
Superior mesenteric artery
A
Stomach
Dilated duodenum
Aorta
Narrow area
Duodeno-jejunostomy
SMA
B

Figs 20-93A and B: Vascular compression of the duodenum—Wilkie's syndrome.


Proximal dilated duodenum
Pancreas
Collapsed part
Complete atresia with separation
A
Fibrous cord atresia
B
Duodenal stenosis
C
Windsock deformity
D

Figs 20-94A to D: Types of duodenal atresia—(A) Complete; (B) Fibrous cord; (C) Duodenal stenosis and, (D) Windsock deformity.

Features

Jaundice, bilious/nonbilious vomiting immediately after birth, features of gastric outlet obstruction, dehydration, electrolyte changes are common, growth retardation of newborn due to deprived nutrition (by swallowed amniotic fluid in foetus).

Investigations

Plain X-ray shows classic *double-bubble sign with absence of air in the distal part*. In partial obstruction, air may be present in distal loop and so contrast study has to be done. Risk of aspiration in newborn infant should be remembered. Ultrasonography will show distended stomach and proximal duodenum, *rail road track* duodenum and features of associated anomalies. Maternal and foetal ultrasound in pregnancy may identify the pathology and also maternal polyhydramnios.

Treatment

Proper preoperative preparations like correction of fluid and electrolytes; gastric decompression; TPN; injection vitamin K; evaluation for associated anomalies.

Duodenoduodenostomy is done. Associated malrotation should be corrected in these patients (Ladd's operation).

Side-to-side duodenoduodenostomy may cause dilated duodenum (megaduodenum-30%); anastomotic dysfunction; and delayed transit of the content. *Kimura's diamond-shaped anastomosis* between transversely opened proximal pouch and longitudinally opened distal pouch reduces the problems of anastomosis. Presence of bile in the duodenum and proximal and distal patency should be confirmed by saline irrigation. Horizontal incision on the proximal dilated part; vertical incision in the lower collapsed part to create diamond-shaped gap which is sutured above with middle of the lower diamond-shaped edge will appose to corner of the proximal upper wound to create duodenoduodenostomy. Interrupted 4 zero or 5 zero vicryl or PDS is used for suturing. Transanastomotic nasojejunal or gastrostomy tube for feeding purpose is needed as prolonged postoperative ileus is the usual problem. *Tapering duodenoplasty* may be required if there is persistent duodenal dysmotility with a megaduodenum **(Fig. 20-95)**.

Duodenojejunostomy may cause blind loop problems. When gap and defect are long, retrocolic loop jejunojejunostomy is done. Gastrojejunostomy should not be done due to high incidence of marginal ulceration and bleeding.


Incision
Suturing
Kimura's anastomosis

Fig. 20-95: Duodenal atresia is treated by duodenoduodenostomy ideally. Kimura's duodenoduodenostomy gives good results.

Chapter 21

Surgeries of Small Bowel and Appendix

A. SMALL BOWEL

SURGICAL ANATOMY

The small intestine is 6 m in length. This includes upper fixed part (duodenum, 25 cm) and lower mobile part (proximal 2/5th is jejunum and distal 3/5th is ileum). At death intestine elongates as muscle tone is lost much faster in longitudinal muscle than circular muscle. Length of the small bowel mesentery is 15-25 cm. Mesentery attaches the small intestine to the posterior abdominal wall, contains blood vessels, lymphatics and fat. Line of attachment of the mesentery is an oblique line starting from a point 2.5 cm left of the midline and 1.0 cm below the transpyloric line extending downwards to the right iliac fossa. It extends from ligament of Treitz at the level of L2/L3 vertebra to right sacroiliac joint. Small bowel is 6 meters in length but mesentery is only 15-25 cm in length at its *root* **(Fig. 21-1)**.



Fig. 21-1: Surgical anatomy of small bowel.

Differences Between the Features of Jejunum and Ileum

Jejunum	*Ileum*
1. Long and few vasa rectae	Short and numerous vasa rectae
2. Long plicae	Small plicae
3. Thick wall	Thin wall
4. Mesentery transparent	Mesentery contains fat
5. Peyer's patches are scanty	Peyer's patches are abundant, located in the antimesenteric border
6. Villi, leaf like and more abundant	Villi, finger like and less abundant
7. Proximal 40% of small bowel	Distal 60%

Small bowel wall contains serosa, longitudinal and circular muscles, submucosa, mucosa with muscularis mucosa. Submucosa should be included to achieve optimum integrity in anastomosis **(Fig. 21-2)**.



Fig. 21-2: Arterial supply of the small bowel.

Nerve Supply

Sympathetic supply is from T9-T11 and parasympathetic supply is from vagus. Both pass through coeliac and superior mesenteric plexus. Bowel wall contains the myenteric plexus of Auerbach which lies between the circular and longitudinal muscle coats; and submucous plexus of Meissner. Sympathetic nerves are motor to sphincter, inhibitory to peristalsis; parasympathetic nerves are inhibitory to sphincter and stimulates peristalsis.

Normal GIT secretions

Saliva: 1000 mL
Gastric: 1500 mL
Intestinal: 4000 mL
Bile: 1000 mL
Pancreas: 1500 mL

Cell type function

Goblet cells: Mucous
Paneth cells: Lysozyme, tumour necrosis factor, cryptidins
Enterocytes: Absorption
Enteroendocrine cells: Different hormones

SURGICAL TREATMENT OF MECKEL'S DIVERTICULUM

It is a congenital diverticulum arising from the terminal ileum and is part of the unobliterated proximal portion of the vitellointestinal duct **(Fig. 21-3)**.



Fig. 21-3: Anatomy of Meckel's diverticulum.

It is 2% common; 2 feet from the ileocaecal valve; 2 inch in length; 2% of Meckel's diverticulum only will be symptomatic; 50% of symptomatic are below 2 years of age; 2:1 female preponderance is seen. It is congenital, results from incomplete closure of vitellointestinal duct. It is the most common congenital anomaly of small intestine. It arises from the antimesenteric border of the ileum, containing all three layers of the bowel with independent blood supply. In 20% of cases mucosa contains heterotopic epithelium like gastric (commonest—50%), colonic and pancreatic tissues (5%). It may be connected to or communicates with the umbilicus through a band or fistula. It may be associated with oesophageal atresia, exomphalos, and anorectal malformations **(Fig. 21-4)**.



Fig. 21-4: Meckel's diverticulum—laparoscopic view.

Presentations in Meckel's Diverticulum

It is asymptomatic in majority of the cases. Severe haemorrhage most common, seen in children aged 2 years or younger (*Maroon coloured blood)*. It can cause intestinal obstruction due to bands/adhesions/intussusception, perforation, volvulus of small bowel, peptic ulceration, diverticulitis (20%)—features mimic acute appendicitis. *Littre's hernia*—it is the presence of Meckel's diverticulum in hernial sac as content. It is observed in inguinal/femoral hernia. Silent Meckel's diverticulum may be found during laparotomy or laparoscopy or by radioisotope study. Carcinoid or GIST can occur in Meckel's diverticulum.

It is diagnosed by Technetium (Tc99) radioisotope scan which is very useful (90-95% accuracy). Ninety per cent of heterotrophic gastric mucosa can be identified in Meckel's diverticulum by radioisotope study. It can detect Meckel's diverticulum with minimal bleeding also (0.1 mL/minute). So it is very useful investigation in children presenting with bleeding. X-ray abdomen is taken to see complications like obstruction, perforation. *Laparoscopy is very useful way to confirm the diagnosis.* Enteroclysis/small bowel enema under fluoroscopy may show the Meckel's diverticulum. It is probably the most accurate investigation **(Fig. 21-5)**.



Fig. 21-5: Laparoscopic view of Meckel's diverticulum. Patient presented with features of acute appendicitis. On laparoscopy, Meckel's diverticulum which was adherent to umbilicus by a cord was found. Appendix was identified separately. Appendicectomy and Mecklian diverticulectomy was done.

Treatment

Asymptomatic Meckel's diverticulum can be left alone when identified during laparotomy.

Surgical treatment

Surgery is done whenever the base is narrow, in lengthy diverticulum, in presence of adhesions or band which may precipitate obstruction, intussusception or volvulus in symptomatic patients or presence of complications, when found in children below 2 years.

Resection of a short segment of ileum containing Meckel's diverticulum and end-to-end anastomosis is done.

Meckelian diverticulectomy with closure of enterotomy also can be done, but chances of retaining heterotopic tissues and stenosis are higher **(Figs 21-6 and 21-7)**.



Fig. 21-6: Meckel's diverticulum on table look. Patient underwent resection and anastomosis.


Colon
Meckel's diverticulum
Ileum
Meckel's diverticulum
Meckel's diverticulum
Ileum
Resected Meckel's diverticulum
End-to-end anastomosis
Resected Meckel's diverticulum with ileum
Meckelian diverticulectomy linear stapler can be used
Note:
Care of clearing heterotopic gastric epithelium should be taken. Should avoid stricture formation later.

Fig. 21-7: Meckel's diverticulum—surgical treatment. Meckelian diverticulectomy is done by obliquely clamping beyond the base of the Meckel's diverticulum. Care should be taken not to retain heterotopic gastric (or other) epithelium which can be felt like indurated area. Enough precaution should be taken so that stricture will not form later. When heterotopic tissues extend beyond the Meckel's diverticulum into the ileum, then resection of ileum with Meckel's and anastomosis is done. Clamping distal to the base of the Meckel's diverticulum like appendicectomy should not be done. It will cause stricture, leak or retaining heterotopic tissues in the part.

SMALL BOWEL RESECTION

It is one of the common surgeries done in the abdomen. It may be in emergency situation or elective one.

Indications: small bowel tumour, multiple perforation, trauma, bowel ischaemia, strangulation, Crohn's disease, intussusception **(Figs 21-8 and 21-9)**.



Fig. 21-8: Intussusception.


Gangrenous bowel
Occlusion clamp
Crushing clamp
Proximal dilated bowel
Distal collapsed bowel
Mesentery
Cheatle's cut
Resection
Lengthy midline incision
Anastomosis

Fig. 21-9: Bowel resection and anastomosis for gangrene in case of intestinal obstruction. Cheatle's cut on the antimesenteric margin of the collapsed distal segment is often needed to avoid discrepancy in luminal width. Single layer interrupted (silk/vicryl) or two layered continuous sutures can be used. Single layer is better in acute conditions.

Principles in Bowel Surgery

Antimesenteric border is having least blood supply and is so critical point in bowel anastomosis. So antimesenteric border should be cut obliquely while doing bowel anastomosis. Mesenteric arterial pulsation should be checked. Cut edge bleeding is very important. If surgeon is not satisfied about cut edge bleeding then one should trim the edge adequately. Blood supply is absolute deciding factor in bowel anastomosis.

Colour, peristalsis, pulsation in the arcade, bleeding suggests adequate blood supply. This is often confirmed by asking anaesthetist to give 100% oxygen for few minutes or by placing warm mop over the bowel or by on table Doppler study.

Serosal area should be *cleared off from fat* for 1 cm margin before doing bowel anastomosis. Fat will interfere with proper apposition of the cut edges. It also reduces the blood supply.

Luminal size of the anastomotic segments should be near equal to have proper serosal apposition. If it is not then narrower segment should be widened by incising antimesenteric border obliquely to widen the lumen *(Cheatle's cut*). Usually distal collapsed part will be narrower compared to proximal dilated segment; so commonly distal part needs Cheatle's cut.

Anastomotic edges should have free mobility; once anastomosis is done, stoma should not be under any tension. Release of adhesions, adequate mobilization by incising the peritoneal layer of the mesentery may be occasionally needed.

Knot should be tied with only optimum force. Excessive force will strangulate the cut edges. Loose knot will leave a gap causing inadequate apposition.

While suturing anterior layer one should be careful in avoiding inadvertent bites of the posterior layer which will block the lumen partially causing stricture and obstruction. Bites should be taken at 5 mm gap with 5 mm thickness of tissue from the cut edge.

Handling: Bowel should be handled carefully using nontoothed dissecting forceps or finger; one should not use toothed dissecting forceps or Allis forceps.

Clamps over the bowel should be placed at 30 degrees at antimesenteric border. Clamps should not extend far into the mesentery. Occlusion clamps are applied at viable part to prevent spillage of contents into peritoneal cavity, to prevent oozing from cut edges of the bowel and to stabilize the gut. Crushing clamps are placed after ligation of mesentery just prior to cutting the bowel; it is applied on the specimen side. One should take care about avoiding twisting of mesentery prior to anastomosis after resection.

Corners of the cut edge of the bowel should be held with seromuscular sutures or Babcock's forceps to allow posterior layer to drop behind and to facilitate proper bite taking of the cut edges.

Anastomosis can be done as continuous layer or interrupted sutures. In acute conditions as there is oedema interrupted one is better. Single layer interrupted sutures are safer and equally good. If two layer anastomosis is done outer interrupted silk sutures are used; inner continuous absorbable sutures like vicryl or PDS are used.

Posterior layer knots are placed inside the lumen; anterior layer knots are placed outside. Posterior layer knots can be placed outside also but it is technically tedious and it does not make any difference in outcome. In interrupted sutures bites should be taken as all layer through and through and kept long untied; once all bites are taken along one (posterior) layer, they are tied together. In the same way anterior layer is sutured. But it needs more suture material and becomes costly. It is possible to place suture and knot immediately and consecutively to complete the anastomosis of one layer in elective cases. Probably in acute conditions where there is oedema and inflammation in the cut edge of the bowel all layer tying together should be done.

In two layer anastomosis first posterior seromuscular interrupted sutures are taken which should include submucosa (which is strongest); then posterior 2nd layer of all layer through and through continuous sutures are taken at 5 mm gap with 5 mm tissue thickness bites. It is locked in between to prevent purse string effect on the stoma (*posterior continuous locking sutures*). Usually this suture begins at mesenteric end, runs towards antimesenteric end where it can be adjusted for size discrepancy; same suture material is continued as anterior layer towards again mesenteric end from antimesenteric end; anterior layer is sutured as outside in and inside out each from opposite side as inverting suture (anterior inverting sutures) or as outside in and inside out each from side looping over the cut edge towards opposite (*Connell suture*). Anterior layer is sutured afterwards as interrupted seromuscular silk sutures **(Figs 21-10 and 21-11)**.

Suture materials usually used are silk or polyglactic acid (vicryl) or polydioxazone suture (PDS). Usually 3 zero suture materials are used. In difficult situations 2 zero may be needed. In children 4 zero is used. Curved round body needle is used.

After completion of the anastomosis, additional sutures at corners may be added to prevent possible leak.

Mesenteric defect should be closed using interrupted or continuous sutures.

In emergency conditions tube drain may be required.


5 mm gap between each suture
5 mm thickness of tissue from cut edge

- Avoid tension
- Maintain blood supply
- Optimum strength while tying knot
- Do not strangulate
- Handle bowel carefully with nontoothed dissecting forceps or finger
- Do not use Allis forceps or toothed dissecting forceps
- Hold the corners with stay sutures on each side or Babcock's forceps
- Both two layers or single layer anastomosis are acceptable
- Continuous or interrupted sutures; interrupted sutures are preferred
- In acute condition like in gangrene interrupted single layer is ideal as due to oedema seromuscular layer suturing is difficult
- Knots in posterior layer can be inside the lumen in bowel; knot in anterior layer is placed outside; however, posterior layer outside knot placing can be done but it is technically tedious and there is no difference between two in relation to outcome

Fig. 21-10: Principles in taking bites in cut edges.


Outer seromuscular suture (Lembert)
Serosa
Muscular layer
Submucosa
Mucosa
Inner all layer through and through

Fig. 21-11: Two layer suturing of the bowel wall.

To check for viability of bowel, look for:

Peristalsis
Pulsations
Bleeding in mesentery and bowel wall
Friability—friable, flabby muscle is seen in ischaemia
Colour (black/pink)
Dull, lusterless, without shining serosa is seen in ischaemia

Different suturing used in bowel are:

Single layer seromucosal suture of bowel: It is now well practiced method of suturing of the bowel. Interrupted seromucosal sutures using three zero/two zero vicryl or PDS takes up well. Nonabsorbable silk or linen can also be used. *These nonabsorbable sutures are good old suture materials which are even now accepted well.* Only drawback presumed is formation of suture granuloma at the anastomotic site **(Fig. 21-12)**.

Gambee single layer full thickness (all layers) sutures using vicryl are also used in bowel anastomosis. It can also be used as continuous sutures especially during gastrojejunostomy. *Continuous suturing* is quicker; alternate bites should be locked to prevent purse string effect; anterior layer is closed with inverting sutures. *Interrupted suture* is more stable and stronger with less chances of anastomotic disruption. It also maintains the blood supply better than continuous sutures. Width of suture bite taken should be less over mucosal part than seromuscular part. Bites are taken 3 mm from the cut edge of the serosa; each bite is taken in a 5 mm gap **(Fig. 21-13)**.

Lembert suture: It is the commonly used seromuscular suture. Silk 3 zero or vicryl 3 zero is used. Deep seromuscular suture including submucosal layer is taken at a point 5 mm from the cut edge of the serosa; this bite emerges at same line (2 mm) from the cut closer edge of serosa; bite is taken on the opposite part of the bowel at 2 mm from the serosal cut edge as seromuscular which emerges at 5 mm point away in the same longitudinal line and knot is placed. It can be used as continuous suture also **(Fig. 21-14)**.

Cushing suture: It is similar to Lembert suture wherein seromuscular bites are taken parallel to the cut edge of the serosa (at 2 mm from the cut edge). Thickness of tissue taken is 5 mm. Both interrupted and continuous sutures can be taken **(Fig. 21-15)**.



Fig. 21-12: Single layer seromucosal suturing of the bowel.



Gambee suturing is all layer through and through suturing with knots tied inside the lumen in both posterior and anterior layers. Often on its inner aspect a mucosal loop bite is taken on each edge to achieve better mucosal inversion

Fig. 21-13: Gambee suture.



Fig. 21-14: Lembert suture.

Halsted suture: It is actually seromuscular horizontal mattress suture. Care must be taken to avoid excessive tension over the suture line as this may lead in to ischaemia of the anastomotic site **(Fig. 21-16)**.

Connell suture: Here suture material passes through all the layers of the intestine from serosa to mucosa; again brought out through all layers of the intestine on the same side from mucosa to serosa; passed over opposite segment of the bowel; passing from serosa



Fig. 21-15: Cushing suture.



Fig. 21-16: Halsted suture.

to lumen/mucosa and from mucosa to outside towards serosa; again coming towards same side to repeat the technique. It is very good technique to invert the mucosal part of the anterior layer. It is commonly used in double layer anastomosis but can be used in single layer anastomosis. Connell suture apposes well; achieves good mucosal inversion. But it is *not adequately haemostatic* and so bleeders on the cut edge of the bowel should be ligated or cauterized individually **(Fig. 21-17)**.



Fig. 21-17: Connell suture for bowel anastomosis.

Resection for gangrenous bowel should be done with division of mesentery very close to the bowel wall. In *small bowel tumour* mesentery is divided away at main branch vessel level with adjacent mesenteric lymph node clearance **(Figs 21-18 to 21-20)**.

Any serosal tear during small bowel surgery should be invaginated transversely using interrupted silk sutures. It prevents adhesion formation and possible chance of post-operative perforation from serosal tear site.

Technique

Nasogastric tube and urinary catheter is passed. Under general anaesthesia with patient in supine position, upper midline incision or middle midline incision running over left side of the umbilicus is made **(Fig. 21-21)**.

After laparotomy abdomen is explored routinely. In obstruction, junction of the proximal dilated segment and distal collapsed segment is identified. In tumour, site of tumour is recognized. Entire small and large bowel should be inspected and palpated for additional pathology. Mesenteric lymph nodes should be looked for. Bowel to be resected is clamped using occlusion clamps on either side at the line of resection. Clamps should not extend far into the mesentery. These clamps should be placed obliquely. Mesenteric vasculature is studied using transillumination. Once vascularity is identified, small windows are made in avascular area using artery forceps and is clamped with artery forceps, divided and ligated. If mesentery is bulky it is better to place two clamps proximally and two ligatures; often it is also necessary to transfix proximal sides of the windows with transfixation sutures to avoid slippage of ligature and bleeding. In resection of tumour, main branch vessel close to that particular loop is clamped, ligated and divided to achieve nodal clearance. Alternatively after creating two consecutive windows silk ligatures are passed and tied, two proximally and one distally and divided between proximal two ligatures and distal one; these tied ligatures should be cut only after dividing the pedicle/vessel. Instead of distal ligatures, artery forceps can be kept and left like that as it will come out with the specimen at the end which will avoid additional ligature passage but it is cumbersome because of so many instruments in the surgical field. In gangrene arcades are ligated close to bowel wall. All vessels entering the bowel are ligated and divided between two clamps. *Payr's* crushing clamp is applied on the specimen side; bowel is cut between occlusion clamp and crushing clamp. Division of bowel is done using no 15 blade or cautery from mesenteric side to antimesenteric side; it is advisable to keep mop or flat instrument underneath to prevent injuring the deeper structures. Clamps should be at 30° angle to the antimesenteric part of the bowel and specimen is removed with the crushing clamp. In tumour, mesentery is ligated proximal to the arcade level away from mesenteric margin of the bowel at main vessels (jejunal or ileal branches) to include adjacent lymph nodes in the specimen; bowel should be divided 5 cm away from the outer margin of the tumour on both sides. Superior mesenteric vessels will be much closer to dissecting area in such situation and so should be careful while applying clamps in such situation. Bulk clamping should be avoided. Large area of mesenteric clamping also can lead to mesenteric tear and causes difficulty in placing ligatures. Small mesenteric segments are clamped, ligated and divided consecutively till one reaches across towards clamp on other (opposite) side of the resecting segment **(Fig. 21-22)**.

Anastomosis is done by different methods—end to end anastomosis; side to side anastomosis; end to side anastomosis **(Fig. 21-23)**.


Gangrene bowel
Occlusion clamps are applied on, to bowel mesentery should not be clamped
Vessels are ligated and mesentery divided close to bowel wall between windows created after transillumination
Crushing clamps (Payr's/Kocher's on the specimen side
Cut ends of the bowel after resection ready for anastomosis
Resected specimen with Payr's clamps

Fig. 21-18: Resection of bowel in gangrene.


Tumour
Lymp nodes in the mesentry
Small bowel tumour
Occlusion clamp on the bowel 5 cm away from the tumour on each side
Vascular pedicle ligation away from the arcade on the main branches of jejunal or ileal — it includes adjacent draining lymph nodes in the mesentery also
Payr's/crushing clamp is applied on the specimen side on each end
Cut ends of bowel and mesenteric V defect after resection ready for anastomosis
Specimen after resection with tumour, with clearance bowel margin, lymph nodes and adjacent mesentery

Fig. 21-19: Resection of bowel in small bowel tumour.



Fig. 21-20: Serosal tear suturing should be done as interrupted seromuscular suture using silk—3 zero.

Commonly *end to end anastomosis* is used. First step is to place a seromuscular Lembert suture at mesenteric side 1 cm from the mucosal cut edge; often this stitch is taken as a through and through all layer single suture which acts as stay suture also which is held with a small haemostat. If there is discrepancy in size between two ends then *Cheatle's cut* is given to distal collapsed smaller sized bowel. Either single layer interrupted full thickness all layer sutures with 3 zero silk are placed or outer interrupted silk sutures with inner continuous vicryl sutures as two layers is used. After completion of the anastomosis stoma should be checked for patency and adequacy by placing fingers (two fingers); it is important to look whether sutured part is pink and healthy or dusky and unhealthy. If it is dusky then anastomosis is



Fig. 21-21: Incision for bowel resection.



Bowel should be cut obliquely towards antimesenteric border as blood supply at antimesenteric border is precarious



Bowel should be cut obliquely to ensure that critical antimesenteric margin will receive its blood supply optimally

Fig. 21-22: Correct and wrong methods of dividing bowel margin.

End-to-side anastomosis
is commonly done:
may need a Cheatle's cut
to achieve proper luminal size

Side-to-side anastomosis
- Commonly done when stapler is used
- Causes many suture lines—at ends and side
- Blind end should be less the 1–2 cm in length



End-to-side anastomosis (Roux-en-Y type)
— commonly used in gastrectomy, pancreatic
and biliary enteric anastomosis

Fig. 21-23: Different types of bowel anastomosis.

disconnected and edges are trimmed until it bleeds and anastomosis is redone. Supportive *crown stitch* is placed on the mesenteric side of the anastomotic site to avoid any possible leak. Tube drain is placed in difficult cases **(Figs 21-24 to 21-30)**.

In single layer interrupted anastomosis *Gambee stitch* with all layer through and through sutures from mucosa to serosa serosa and bowel wall and mucosa of opposite edge and knot is tied in the lumen. Often while taking bite from mucosa, loop can be done in the mucosa in Gambee stitch to achieve proper mucosal inversion. In single layer anastomosis often four quadrant (two on each side) seromuscular sutures are placed to relieve tension on inner layer.

Parker Kerr basting stitch previously was in use; after applying Parker Kerr clamps, basting Cushing's continuous suture bites are taken on the seromuscular layer over the clamp on each side circumferentially and then clamps are released.



Posterior seromuscular interrupted sutures are placed;
submucosal bite should be taken as it is strongest layer;
silk is commonly used for this layer — 3 zero silk

Fig. 21-24: Interrupted posterior outer seromuscular layer suture.



Stay sutures are placed at corners.
Elliptical occlusion clamps may be used and if so in place
All layer interrupted suture bites are taken with loops coming from within.
Once all sutures are placed, knots are tied one by one.

Fig. 21-25: Posterior all layer suturing is done as either interrupted full thicknes sutures (silk—3 zero); or continuous locking sutures using vicryl.



Anterior interrupted sutures are placed; all sutures are taken first and kept untied;
later knots are tied together one by one to complete the anterior layer.
Care should be taken not to take bite from the posterior layer which will
lead to partial obstruction.

Fig. 21-26: Anterior layer interrupted suture in bowel anastomosis.


Cheatle's cut
After resection bowel is ready for anastomosis
Anastomosis begins at mesenteric side of the bowel after placing a stay suture
Posterior continuous suture towards antimesenteric border and Cheatle's cut given on the collapsed distal part
Purse string suture
Complete end-to-end anastomosis
Purse string/figure of 8 suture on the mesenteric corner of the stomal site

Fig. 21-27: Technique of end-to-end anastomosis.

V shaped mesenteric defect is closed with interrupted silk sutures (ideal); often corresponding parts of the edges are held together with haemostats and ligature is tied around each pair to close the mesenteric defect (as here needle bite is not taken needle bite bleeding and haematoma of the mesentery will not occur). Continuous suturing even though mesenteric practiced causes troublesome tear at mesenteric edge and bleeding **(Figs 21-31 and 21-32)**.

Problems and Complications

Friable bowel wall with poor blood supply can lead into leak and enterocutaneous fistula. Ileostomy may be better in such situation rather than doing anastomosis.

Sepsis, subphrenic abscess and pelvic abscess can occur.

ENTEROLYSIS/ADHESIOLYSIS

Adhesions and bands are the most common causes of intestinal obstruction in Western countries. In India, hernia and then adhesions are the two common causes of intestinal obstruction **(Fig. 21-33)**.

Causes

Infection due to peritonitis; appendicitis; postlaparotomy; materials used during surgery can cause dense inflammatory reactions—suture materials like silk, thread, and foreign body, mop, and gauze, talc


Ischaemic segment
Occlusion clamps applied
Bowel segments are resected; cut ends are brought together
Posterior single layer interrupted silk sutures
Anterior single layer interrupted silk sutures
Mesenteric defect to be closed
Mesenteric defect to be closed
Mesenteric defect is closed

Fig. 21-28: Technique of resection and anastomosis.


Gangrene bowel
Normal bowel
Vascular block
Ligation of vascular pedicle in the mesentery and division
Nonviable cut edge of the bowel - with inadequate bleeding
Nonviable cut edge of the bowel - with inadequate bleeding
Nonviable cut edge of the bowel - with inadequate bleeding
Trimming of the devitalised cut edge till it bleeds properly is essential
Resected specimen

Figs 21-29(1)


Closure of mesenteric defect
Suturing the bowel ends using interrupted silk



Figs 21-29(2)

Figs 21-29(1 and 2): Resection of bowel in (massive resection) extensive gangrene due to mesenteric artery thrombosis.

powder; drugs like sulphonamides and penicillins; ischaemia of bowel due to poor blood supply; gynaecological conditions; bowel injury; radiation-induced enteritis, Crohn's disease and other inflammatory bowel diseases; specific conditions like tuberculosis, malignancy **(Figs 21-34 and 21-35)**.

Note:

- It is often called as *adhesive small bowel obstruction* (ASBO). 80% cases showed earlier laparotomies; 35% multiple laparotomy. In such patients 75% of surgeries are emergency ones.
- *Causes may be classified as—Congenital* adhesions; *Ischaemic*—Reduced blood supply of the bowel, *Traumatic*—Patients have undergone laparotomies for intraabdominal injuries; *Irritants*—Talc powder used for gloves, starch, antibiotics, nonabsorbable suture materials, gauze and cotton filaments, barium; *Inflammatory*—Appendicitis, cholecystitis, pelvic infection, Crohn's disease, tuberculosis; *Others*—Serosal denudation during surgery precipitates adhesions.
- Initial cause ischaemia/injury → inflammatory exudates → fibrinous adhesions → fibrous adhesion → fibrinolysis. Fibrinous adhesion is avascular. Often thick vascular adhesions develop. Adhesions can be localized or extensive.

Types

Type I—Fibrinous adhesions occur during 5th to 10th post-surgical period. It usually gets resolved completely. It is avascular and flimsy. *Type II—Fibrous* adhesions. Due to lack/poor blood supply, bowel gets attached to part of peritoneum or omentum or other parts of the bowel with dense vascular adhesions to maintain blood supply. It will persist and precipitate intestinal obstruction, often subacute and recurrent type.

Adhesions due to tuberculosis are severe, dense and difficult to separate.

Obstruction due to Bands

These are *dense fibrous strings* attached from one portion of the abdomen to another area or bowel causing entrapment of intestines leading into obstruction and often dangerous *strangulation.* Common causes are vitellointestinal duct, Ladd's band, omental band, postsurgical fibrous band, tuberculous band.

Clinical features are like that of intestinal obstruction. Management is release of the band either through laparoscopy or through laparotomy.

Features

Pain abdomen—colicky type and recurrent and episodic; distension, vomiting, constipation; reduced bowel sounds on auscultation; previous surgical scars commonly observed; dehydration, tachycardia, hypotension.

Commonest symptom in adhesions is ***pain*** which is sharp, sudden, recurrent, episodic and colicky. Colicky pain is more common in midlevel obstruction. *Gilroy Bevan triad* of adhesive pain is—(1) Pain may get aggravated or relieved on change of posture. (2) Pain in the region of old abdominal scar. (3) Tenderness is elicited by pressure over the scar.


Proximal small bowel tumour or obstruction patient
- will not show abdominal distension - scaphoid abdomen
CT picture showing intussusception of jejunum probably jejunal tumour
R
R
Laparotomy with retractor
Intussusception of
the jejunum
Reduction of the intussusception
of the jejunum
Jejunal tumour
Jejunal tumour
Occlusion clamps are placed > 5 cm
away from the tumour on either side
Ligating
the mesenteric
vessels
Ligating the mesenteric
vessels
After completion of mesenteric division,
Kocher's or Payr's clamp is placed
on specimen side
After completion of mesenteric
division, Kocher's or Payr's clamp
is placed on specimen side

Figs 21-30(1)



Occlusion clamp is readjusted obliquely with angulation. Note clamp should not extend far into the mesentery

Bowel is cut in between occlusion clamp and crushing clamp from mesenteric side to antimesenteric border

Bowel is cut in between occlusion clamp and crushing clamp from mesenteric side to antimesenteric border

Monopolar cautery may be used for cutting the bowel

Bowel is divided on either side to retrieve the specimen

Cut edges of jejunum bleeds adequately

V shaped mesenteric defect with cut edges

Cut edges of the bowel brought together which bleeds adequately

Anastomosis begins from mesenteric side towards antimesenteric side

Posterior full thickness continuous vicryl suture is completed

Begining of anterior inverting sutures

Anterior layer is completed

Figs 21-30(2)


Tied to tail end of same suture to complete the anterior layer
Note the position and angulation of occlusion clamps
Few interrupted full thickness all layer sutures are placed if needed
Occlusion clamps are removed
Checking the luminal size
Additional seromuscular suture can be placed as interrupted silk
Seromuscular layer is completed
Closure of mesenteric defect
Closure of mesenteric defect
Mesenteric end/angle of the stoma is supported by additional figure of 8 suture
Warm saline irrigation and suction
Rectus edges are held Allis forceps
Sergeant retractor
Closure begins - as single layer continuous suture with nonabsorbable suture material
Retrieved specimen of jejunal tumour

Figs 21-30(3)


Opened specimen
Completing the closure

Figs 21-30(2)

Figs 21-30(1 and 2): Resection of jejunal tumour and end-to-end anastomosis.


Resection line in bowel and mesentery
V shaped defect in the mesentery
Bowel anastomosis is done
Interrupted sutures from the edges of the mesentery
Haemostats are placed over the mesenteric edges at corresponding points on each side.
Simple ligature is passed around both corresponding haemostats together to place an apposition knot

Fig. 21-31: Closure of mesenteric defect using interrupted sutures.

Lower adhesions will have more distension compared to proximal adhesion.

Often it presents with features of obstruction initially, later features of strangulation (toxicity, fever, tachycardia, guarding, rigidity, rebound tenderness). Adhesions may be asymptomatic for many years but later become symptomatic.

Plain X-ray abdomen shows dilated bowel loops; oral contrast with CT scan is very useful; only in partial obstruction enteroclysis with water-soluble iodine dyes can be done.

Level of obstruction should be assessed probably by X-ray and CT scan; CT may show radiological features of strangulation—intramesenteric fluid; mesenteric oedema, congestion, bowel wall thickening more than 2 mm, reduced mural enhancement in strangulated bowel compared to adjacent bowel. Small bowel loop may go for volvulus showing *Whirl sign* in CT scan which is due to whirlpool mesentery of that part of the bowel. Electrolyte estimation, total count, serum creatinine, blood grouping—are needed **(Figs 21-36 and 21-37)**.



Fig. 21-32: Laparotomy wound closed after resection and anastomosis.



Fig. 21-33: Step ladder peristalsis in intestinal obstruction. Post-operative adhesions have become commonest cause of intestinal obstruction. Note the abdominal distension in a previous laparotomy patient and on table adhesions.



Fig. 21-34: Band with adhesions causing intestinal obstruction.



Fig. 21-35: A band causing stricture of small bowel.



Fig. 21-36: CT is ideal and diagnostic for intestinal obstruction.



Fig. 21-37: X-ray showing small bowel obstruction with multiple air fluid levels.

Treatment

Initial Treatment

IV fluids, nasogastric aspiration, antibiotics, often per anal flatus tube insertion, commonly patient responds in 4-5 days of therapy.

Later Treatment

Open surgical adhesiolysis using fingers gently.

Laparoscopic adhesiolysis is becoming popular, safer, and ideal with less recurrent adhesion rate and good results **(Fig. 21-38)**.

Noble's plication of intestines—wherein adjacent coils of small bowel are sutured to prevent going in for further recurrent adhesions.

Childs-Phillips mesenteric plication is a similar way of plication of intestinal mesentery, which will prevent crumpling of bowel and adhesion formation.

Passing long stiff tube from exterior through an opening in the proximal bowel up to the entry into the large bowel, which acts as intraluminal splinting **(Figs 21-39 and 21-40)**.

Intestinal intubation is technically difficult with chances of perforation and fistula formation. *Baker's tube* insertion through



Fig. 21-38: Laparoscopic view of dense adhesions—postoperative cause.



Fig. 21-39: Methods used to prevent recurrent adhesions and so to reduce the chances of intestinal obstruction. Noble's plication is plication of intestines.



Fig. 21-40: Childs-Phillips operation done to prevent adhesive obstruction by plicating mesentery.

jejunostomy site; *Stewardson insertion of Baker tube* through nasogastric route; In *Nelson and Nyhus* method, 2nd balloon to Baker tube 25 cm proximal to the first to facilitate easier insertion of the tube—are different tubes and techniques used **(Figs 21-41 and 21-42).**

Expandable PTFE membrane barriers or hyaluronic acid and carboxymethyl cellulose membrane barriers are also used.

Surgical Treatment for Adhesions—Enterolysis

Adhesions are common causes of intestinal obstruction. Usual treatment is adhesion release either through open or laparoscopic approach. Laparoscopic approach has become standard now. However principles of adhesiolysis are similar in both approaches.

Open Method

Usually it is diagnosed by recurrent pain, distension, vomiting. CT scan confirms the diagnosis. Approach is through same previous scar with extension on either ends. But peritoneum should be opened through normal part of the incision not through the old scar area. Once peritoneum is opened remaining part of the wound is opened under vision with release of any adherent omentum or bowel.



Fig. 21-41: Intestinal intubation via a gastrostomy tube used for adhesions.



Fig. 21-42: Intestinal intubation via a jejunostomy tube used for adhesions.

Sharp dissection is better if adhesions are fibrous and thick. In bowel adhesions to abdominal wall, dissection should be carried out very close to the abdominal wall; it is better to incise the abdominal wall peritoneum rather than creating a nonexisting plane between adherent bowel and abdominal wall; if it is tried it will surely create a rent in the bowel. While cutting adhesion finger is used underneath for guidance.

Flimsy thin fibrinous adhesions are dissected using index finger. *Gentle finger dissection* is carried out with care to avoid serosal or deeper tears in the bowel wall. *Oozing* while releasing adhesions usually subside after keeping a mop on the site.

Vascular adhesions need *bipolar cautery* to prevent bleeding. *Harmonic scalpel* can be used to release vascular adhesions. Monopolar cautery *should be avoided* as much as possible as bowel injury is likely to occur.

Release of omentum often needs ligature and division or harmonic scalpel. Adherent omentum pulls transverse colon along with it; colon will be often very close to crumpled adherent omentum; during dissection care should be taken not to injure colon inadvertently.

Adhesions very close to mesenteric vessels often will be thick and release should be careful to avoid injury to vessels.

Adhesions especially after hysterectomy and pelvic surgery will be mainly in the pelvis; such adhesions commonly involve terminal ileum and omentum. These adhesions are often stiff and difficult to release as they are deep in pelvis. Finger dissection may be helpful but has to be done with care. Undue traction to the bowel causes tear in the bowel.

Always adhesion release should begin from *easier area to difficult area*. Once all easier area is released, difficult area becomes easier to release.

Mesenteric peritoneal tear often occurs while releasing the bowel; placing a mop on the mesentery usually controls any ooze if occurs; definitive bleeding needs bipolar cautery fulguration or transfixation stitch using 3 zero silk or vicryl.

Entire small bowel from suspensory ligament of Treitz (duodenojejunal junction) to ileocaecal junction should be released.

Any small *serosal tear* is sutured using vicryl or silk seromuscular Lembert suture to invaginate the raw area. Lengthier tear should be sutured transversely using Lembert suture. Perforated bowel segment should be closed using interrupted 2 zero silk sutures. If certain part of the released bowel wall looks nonviable and dusky it should be resected and anastomosed without any doubt or debate. If bowel wall is oedematous and friable and difficult to undertake the resection and anastomosis then loop or end ileostomy is done; closure of ileostomy is done at a later stage after 3-6 months.

On table *Doppler evaluation* should be done if there is doubt about the viability of the bowel.

Some adhesive parts if it looks like to form adhesions again, such part can be *diverted* by doing enteroenterostomy or ileotransverse anastomosis. But it creates a blind pouch and may cause blind loop syndrome.

On table intestinal decompression is often needed if bowel is distended enormously. *Baker intestinal tube* (270 cm long with a 5 mL balloon) is passed by nasogastric route by anaesthetist or by operating surgeon through a gastrotomy incision creating a Stamm gastrostomy. Tube is gently negotiated across the pylorus into the duodenum gently and balloon is inflated partially to negotiate it into the entire length of small intestine by slow milking into the caecum across the ileocaecal valve. Balloon is fully inflated with 5 mL of saline. Suctioning of the tube should be done while negotiating it through the small bowel to decompress it. It can be kept for 3 weeks to create a *stitchless plication* of the small bowel. Tube is adjusted to make bowel as multiple 'S'. Tube is removed after 3 weeks. While removing it should be deflated completely otherwise it will create reverse intussusception of the small bowel **(Fig. 21-43)**.

Laparoscopic Method

Laparoscopy is better than open method. However, if bowel resection is needed open method is preferred or conversion has to be done. Camera port is placed away from previous scar. Usually it is placed in *left Palmar point* (left subcostal point) or right upper abdomen. Open method is ideal for placing first port. Visiport can be used safely. Stomach should be decompressed. Nasogastric tube and urinary catheter should be passed. Once main port is passed remaining ports (5 mm) are placed depending on the location of adhesions. One on each side and additional 5 mm on left side may be needed. First abdominal wall adhesions are released using scissor and bipolar cautery keeping scissor very close to abdominal wall. 30 degree telescope is ideal for this purpose. After releasing all abdominal wall adhesions bowel loop adhesions which are bands are released. Initially easier part is released with sharp scissor dissection. Later dense and difficult adhesions are released slowly, carefully and gently with patience. Entire small bowel is dissected off to complete the adhesiolysis. Serosal tear is sutured with intracorporeal Lembert suture using 3 zero vicryl. If perforation occurs it is better to convert into open method; however, if the surgeon is experienced and confident the perforation can be sutured laparoscopically using silk or vicryl by intracorporeal suture. But proper closure should be ensured otherwise peritonitis due to leak will occur **(Fig. 21-44)**.



Fig. 21-43: Releasing adhesions through open method.



Fig. 21-44: Adhesion seen through laparoscopy.

Problems and Complications

Serosal tear may be missed or overlooked and may leak at a later period causing peritonitis. Recurrent obstruction after adhesiolysis is 15%. Many patients undergo repeated laparoscopic or open surgeries to relieve the obstruction. Slow recovery, prolonged ileus requiring many days nasogastric tube placement, long time intravenous fluids and lengthy hospitalisation are the problems.

Prevention of Adhesions

Prevention is done by instilling drugs like hyaluronidase, steroids, dextrans, dextrins, polyvinyls, silicone, fibrinolysins, chondroitins, streptomycins; gentle handling of the bowel; prevention of spillage of contents like bile, faeces; ideal peritoneal wash using 8-10 liters of saline before closing the abdomen; careful placing of the drains; *Laparoscopic procedures has got lesser chance of adhesions than open method.*

STRICTUROPLASTY

It is commonly done for ileal stricture. Common cause is Crohn's disease. Strictures may be multiple in Crohn's disease. Even after resection disease or stricture may recur. Hence often, instead of resection stricturoplasty is done in these patients. It is useful in recurrence of stricture after previous resection of more than 100 cm; short fibrotic stricture.

Perforation, fistula due to Crohn's disease, haemorrhage are contraindications for stricturoplasty.

Types

Heineke Mikulicz stricturoplasty is similar to Heineke Mikulicz pyloroplasty, used in strictures less than 8 cm (short segment). It is longitudinal incision of stricture segment for its full thickness and transverse closure as a single layer with interrupted silk suture. Stricture is incised longitudinally 2 cm beyond the stricture on to the normal bowel on either side.

Finney's stricturoplasty is done for longer segment stricture. It is similar to Finney's pyloroplasty. Adjacent strictured bowel loops are brought together; U incision is made on the antimesenteric border of the bowel segments; anastomosis is done as in pyloroplasty with posterior seromuscular interrupted silk sutures, posterior all layer continuous or interrupted vicryl sutures, anterior all layer continuous or interrupted sutures and anterior seromuscular interrupted silk sutures **(Figs 21-45 and 21-46)**.

Problems and Complications

Recurrence, failure, re-obstruction at same segment, leak and peritonitis due to anastomotic dehiscence as anastomosis is on a scarred segment.

JEJUNOSTOMY

Jejunostomy for enteral nutrition is becoming more popular because of its comfort, easy to do, can be kept for long time, lesser complication than gastrostomy. *Indications* are same as gastrostomy.



Fig. 21-45: Heineke Mikulicz stricturoplasty.



Multiple strictures in the ileum → U shaped incision on the bowel loop → Stricturoplasty (Finney's) (Similar like Finney's pyloroplasty)

Fig. 21-46: Finney's stricturoplasty.

Types

Witzel jejunostomy: Site of placing jejunostomy is 20 cm from duodenojejunal junction. It is usually done after major abdominal surgeries. After finishing procedures like pancreatic surgery, a stab incision is made on the left side of the abdomen at the level or above the umbilicus. Catheter tip is passed from outside across the abdominal stab wound using a long artery forceps. Loop of jejunum 20-30 cm from the duodenojejunal junction is selected and held with Babcock's forceps. A small incision is made on the antimesenteric border of the selected jejunum of 5 mm in size; entire thickness of the bowel is opened using cautery; jejunostomy catheter (Foley's catheter 16 F or 18 F or feeding tube or nasogastric tube) is passed into the jejunum for adequate length beyond next loop. A purse string seromuscular suture using vicryl is placed around it and tightened securely around the catheter. A seromuscular tunnel of 5 cm length is created around the tube using 3 zero silk interrupted sutures. Serosa at proximal part of the tunnel may be fixed to parietal peritoneum at the abdominal wall. Tube outside is fixed to the skin **(Fig. 21-47)**.

Problems are: tube dislodgement, jejunal obstruction, intestinal juice leak, torsion of the bowel loop, catheter block, leak into the peritoneal cavity, diarrhoea, abdominal discomfort, abscess formation, metabolic problems. Problems may be mechanical, metabolic, gastrointestinal and infectious.

Jejunostomy can be done using gastroduodenoscopy (gastroscopy) similar like PEG. Gastroscopy is passed across the duodenum to jejunum; under visualization and guidance percutaneous needle is punctured into the jejunum and fine catheter through the needle is passed which is held using endoscopic snare and pulled out; jejunostomy catheter is tied.

Laparoscopic jejunostomy is done similar to needle jejunostomy under laparoscopic vision.

Needle catheter jejunostomy using catheter of small gauge can be done. Here percutaneous needle is passed across the abdominal wall into the abdominal cavity which is then inserted into the jejunum 20 cm from duodenojejunal junction. Fine catheter is passed through it; needle is removed. Purse string suture is placed. Jejunum is fixed to abdominal wall to prevent torsion. Tube is fixed to skin **(Fig. 21-48)**.

SMALL BOWEL PERFORATION

Perforation of small bowel can occur by various causes like trauma, typhoid ulcer, enteritis, roundworm infestation, bands causing initial



Jejunostomy tube is passed through the abdominal stab wound and then into the jejunal wound; tube is negotiated for adequate distance in the jejunal lumen

Purse string suture around the tube in the jejunal wound is placed
Tube is covered/burried with interrupted silk seromuscular suture for 5 cm along the jejunal wall to create Witzel tunnel.
Tube and jejunum is fixed to abdominal wall with interrupted sutures

Outside tube is fixed to abdominal wall

Fig. 21-47: Witzel jejunostomy.



Fig. 21-48: Needle catheter jejunostomy.

obstruction and later perforation. Patients present with features of peritonitis. Typhoid perforation which occurs on day 3rd after the infection, are usually multiple, along the antimesenteric border on the Peyer's patch. Guarding, rigidity which are definitive features of perforation may not be present in typhoid perforation. Traumatic perforation may be due to stab injury or blunt injury. Blunt injury causes traction at duodenojejunal junction leading to disruption of the bowel on the first loop of the jejunum; often it may be in ileocaecal region also for the same reason. Occasionally specific diseases like Crohn's or tuberculosis or malignancy or lymphoma of bowel can cause perforation **(Fig. 21-49)**.

Perforations should be treated surgically. After laparotomy entire small bowel should be inspected. Peritoneal cavity contains pus and intestinal juice. Pus should be collected for culture and sensitivity. Site should be held with Babcock's forceps. Peritoneal infected fluid is sucked out. Perforation edge is trimmed off. Perforation is closed transversely using interrupted 2 or 3 zero silk sutures. Often biopsy from the edge of the perforation should be taken especially when perforation at ileal site. Seromuscular Lembert interrupted suture may be placed; but it is often difficult in a friable oedematous bowel. Any mesenteric tear if present should be sutured. In multiple perforations resection of the ileum is necessary. If patient's general condition is not good and bowel is friable then loop ileostomy is preferred. Often after resection distal end may be closed and fixed at definitive point in the abdominal wall; and proximal part is brought out as end ileostomy. Ileostomy closure is done in 3-6 months.



Fig. 21-49: Multiple perforations in the ileum; could be due to typhoid.

Adequate peritoneal wash using *warm normal saline* is needed. Tube drain is put. Abdomen is closed as single layer. Smead Jones suture may be needed to avoid burst abdomen **(Figs 21-50 and 21-53)**.



Fig. 21-50: When bowel is viable in multiple perforations, it is nor resected but individual perforations are closed.



Fig. 21-51: When multiple perforations are present and bowel is ischaemic and nonviable, resection is done. Either primary anastomosis is done; or ileostomy is done (better when there is severe sepsis); or primary anastomosis with proximal diversion ileostomy may be done.



Fig. 21-52: Closure of ileal perforation.


London's sign
Large perforation
Self retaining retractor
Incision - midline left of umbilicus

Figs 21-53(1)


Site is held with Babcock's
Occlusion clamp is applied
Ragged edge of the peforation
Ragged edge of the peforation is trimmed with scissor
Interrupted all layer full thickness 2 (or 3 zero) zero silk sutures are placed
Interrupted all layer full thickness 2 (or 3 zero) zero silk sutures are placed

Figs 21-53(2)


Checking the patency of lumen
Interrupted seromuscular silk sutures are placed
Interrupted seromuscular silk sutures are placed
Peritoneal wash with 10 litres of warm saline with suctioning
Peritoneal wash with 10 litres of warm saline with suctioning
Placing the tube drain
Closure of rectus sheath - single layer
Checking the deeper abdominal wound for bowel interposition or bite

Figs 21-53(3)


Aberdeen knot
Burying the knot under rectus sheath

Figs 21-53(4)

Figs 21-53(1 to 4): Traumatic perforation of the small bowel due to blunt injury abdomen; London's sign with echymotic patch in the abdomen; X-ray showing gas under diaphragm; closure of perforation as shown.

Post-operative Care

Antibiotics, intravenous fluids, TPN, central line – CVP, urinary output measurement, monitoring and ICU care is needed. Nasogastric tube is kept in place. Prevention of DVT using low molecular heparin is better. Drain is removed in 5 days as well as nasogastric tube once bowel sounds appear. Observation for complications is very important.

Problems and Complications

Septicaemia, ARDS, DVT, DIC, acute renal failure, subphrenic abscess, pelvic or interloop abscess formation. Reperforation and peritonitis is a real threat. Burst abdomen, enterocutaneous fistula, are again a problem. Wound infection can occur.

INTESTINAL BYPASS PROCEDURE

Diverting a loop which is nonfunctioning or creating problem may be required as a surgical technique so as to relieve the obstruction or complication like leak. It is done in severe localized adhesions, malignancy, trauma, tuberculosis or Crohn's disease. However, formation of blind loop and its consequences like malabsorption, recurrent infection in blind loop are the problems and setback to this procedure. Small bowel bypass, ileo transverse anastomosis, ileosigmoid anastomosis are few bypass procedures usually advocated in selected patients. All these procedures are done as side to side anastomosis. It can be done as two layer anastomosis hand sewn or through stapler. In two layer anastomosis both layers are done as interrupted sutures using silk or inner vicryl and outer silk. While doing ileo transverse anastomosis transverse colon is opened longitudinally along its taenia **(Figs 21-54 and 21-55)**.


Incision over the taenia
Ileo transverse anastomosis
Taenia
Lesion/stricture of adhesions in terminal ileum or caecum

Fig. 21-54: Ileo transverse anastomosis.


Ligament of Treitz
Dense adhesions or stricture but bowel is viable
Enteroenteric anastomosis as bypass procedure is done

Fig. 21-55: Small bowel bypass.

ILEOSTOMY

There two types of ileostomy—end and loop. Usually end ileostomy is done as a permanent one after total proctocolectomy if ileal pouch to anal canal is not contemplated. Occasionally temporary end ileostomy is done; in such situation distal segment is closed and kept in right iliac fossa with a fixation stitch to abdominal wall. Temporary end ileostomy may be indicated in Crohn's disease, complex fistulas, ileocaecal trauma. While creating urinary diversion as ileal conduit ileostomy is needed.

Loop ileostomy is always temporary for diversion of small bowel content in any terminal ileal disease or proximal colonic disease.

Principles in Ileostomy

Stoma site should be marked in individual patient prior to surgery. It should be clearly discussed with patient. Stoma therapist and rehabilitation and counselling should be done.

Stoma site is right iliac fossa with infraumbilical mould of fat as summit. Incision should be marked at the surface on the rectus abdominis muscle. Stoma site should be away from scars, umbilicus, bony points, burn injury etc.

Stoma is marked as round line using a faceplate placed in proposed site.

Muscle should only be split not cut.

Creation of *spout* is important.

Types (Fig. 21-56)

End
Loop
Loop end

End Ileostomy

It is usually done after total proctocolectomy in ulcerative colitis, familial adenomatous polyp (here ileal pouch is contraindicated), multiple synchronous carcinomas, occasionally as temporary end ileostomy in Crohn's disease, ileocaecal trauma, right colonic obstruction.

Terminal ileum is brought out as ileostomy. Terminal ileum is mobilised from its mesentery keeping its arcade and blood supply intact. Terminal ileum is very important for absorption and so one should avoid unnecessary excision of terminal ileum.

Stoma site is in the right iliac fossa over the outer half of the right rectus extending downwards for 2 cm. *Skin is excised* for about a 2 cm circle. Subcutaneous fat is not excised **(Fig. 21-57)**.

Vertical (3-3.5 cm) or cruciate incision is made in the rectus sheath. Only vertical incision on the rectus sheath is sufficient; it is not mandatory to place the cruciate incision. With haemostat and finger dissection peritoneum is reached which is opened to enter the peritoneal cavity. Muscle should be *only split,* never cut. Through laparotomy wound a mop is firmly kept and pressed over the rectus muscle to prevent muscle getting slipped while splitting the rectus muscle. Vertical incision is made in the posterior rectus sheath and peritoneum. Peritoneal opening should be of *two finger size (index and middle)* snugly fitting; it should not be more as it will cause parastomal hernia. As laparotomy wound already exists through which access can be made easily. Injury to inferior epigastric vessels should be avoided. Terminal ileum is transected 2 cm from the ileocaecal valve in case if ileal pouch is being planned later; maximum up to 10 cm of terminal ileum can be removed but not beyond that in any type of ileostomy. *Stapler division* of the ileum is done to prevent the contamination. Stoma is fashioned by retaining the arcade; proximal to arcade few vessels are ligated. Incised rectus sheath is retracted. Babcock's forceps is passed across the ileostomy wound into the peritoneal cavity and cut end of the ileum is held and gently pulled out through the wound *for 6 cm* **(Fig. 21-58)**.



Fig. 21-56: Ileostomy types—end, loop, loop end.


Right rectus
2 cm circular skin is excised
Laparotomy incision
Vertical incision in the rectus sheath cruciate incision-optional

Fig. 21-57: Incision site for ileostomy.

Mesentery may be fixed to the lateral abdominal wall using interrupted 2 zero vicryl sutures. *Seromuscular interrupted stitches* are placed between the ileum and peritoneum as stabilization stitch. It is not done in case of Crohn's disease as fistula may form. This suture is placed through laparotomy wound from inside by everting the cut edge of laparotomy wound. Laparotomy wound is closed. Stapler line



After total protocolectomy during retrieval of specimen terminal ileum at 2–10 cm from ileocaecal valve is transected using stapler.
Stoma is fashioned by retaining the closure arcade to the stapled end.
Ensure that blood supply at the end is optimum.

After circular skin excision of 2 cm at stoma site vertical incision is made in the rectus sheath; muscle is only split; peritoneum with posterior rectus sheath is opened.
By passing Babcock's forceps stapled ileal end is brought out through ileostomy wound

Fig. 21-58: Ileostomy stoma fashioning.

is excised from the terminal end. Often another seromuscular bite is taken from ileum 1 cm from the ileal cut end and superficial fat layer (Camper); it prevents formation of the *parastomal gully*. Cut edge of the ileum (full thickness all layer interrupted) is apposed to subcuticular part of the skin (not full thickness skin) with initial four points then additional four sutures in between (*maturation*) **(Fig. 21-59)**.

After placing all sutures, knots are tied one by one. In a different method, alternate sutures are placed with an additional seromuscular stitch prior to passing through the skin subcuticular part. Through and through skin is better avoided otherwise there are chances of mucosal island implantation and early separation of stoma appliances.


– Staple line is divided using scissor-maturation
– 1 cm from cut end of ileum seromuscular bite is taken to again pass into the outer fat layer to prevent parastomal gully formation
– Mesentery is sutured to abdominal wall
– Stabilisation stich is placed from seromuscular suture of ileal wall to peritoneum; placed through the laparotomy wound
– Laparotomy is closed
8 interrupted sutures at 8 corners from full thickness ileal cut end to subcuticular part of the skin (not through the entire skin)

Fig. 21-59: Maturation of ileostomy.

Placement of two myotomies of the stoma before suturing to skin will also prevent the recession of the ileostomy to create needed *spouting*. While taking seromuscular suture, care should be taken not to enter mucosa to avoid stoma fistulas at the edge.

Often *spout is created* in such a way that stoma is made *to face downwards* which is ideal. It is done while placing seromuscular—outer fat suturing where in the proximal part this is taken shorter while in the caudal part it is longer and it is in between at sides. It can also be achieved while taking final bite between subcuticular and cut edge of ileum, additional seromuscular bites are taken at different levels **(Fig. 21-60)**.

Midline laparotomy → definitive procedure (proctocolectomy) → *marking the stoma site* on the right lower rectus → 2.5 cm *circular skin is excised* → fat is *not* removed → *vertical* 3.5 cm or cruciate incision in the *rectus sheath* → rectus muscle is *split* → mop with finger support through the laparotomy wound to prevent slipping of the rectus → posterior rectus sheath and peritoneum is incised vertically for *two finger breadth only* → *stapler transection* of the terminal ileum at 2-10 cm from ileocaecal valve → *stoma fashioning* is done with retaining the arcade → *Babcock's forceps* is passed from outside into the peritoneal cavity across the ileostomy wound → stapled ileum is held → brought out gently for *6 cm exteriorization* → mesentery may be obliterated by suturing it to abdominal wall → through laparotomy wound *stabilization interrupted stitches* are placed between seromuscular ileum and peritoneum all round → laparotomy wound is closed → ileostomy maturation is done by cutting stapled area → seromuscular stitch 1 cm away from the cut end of ileum is sutured to outer fatty layer to avoid parastomal gully by creating concertina effect → full thickness cut edge of the ileum is sutured to subcuticular part of the skin as interrupted sutures (8 sutures).


Disrupted ileoileal anastomosis
Distal part
Proximal part
Closure of distal part

Figs 21-60(1)


Closed distal part
Proximal part
Distal part is sutured to abdominal wall - as hitch stitch for future identification
Distal part is sutured to abdominal - as hitch stitch for future identification
Ileostomy incision in right iliac fossa
Rectus sheath is incised
Proximal ileum is brought out - end ileostomy
Closure of the abdominal wall
Ileostomy
Tension sutures
Closure of the abdominal wall

Figs 21-60(2)

Figs 21-60(1 and 2): End ileostomy done for critically disrupted earlier closed ileal perforation.

Loop Ileostomy

It is done to create diversion as temporary method. After ileal pouch with pouch anal canal anastomosis, covering diversion loop ileostomy is placed for 3-6 months. It is used in enterocutaneous fistula, ascending colon or caecal sepsis or gangrene, in radiation related severe pelvic problems, in multiple perforations of terminal ileum where severe sepsis prevents from doing primary anastomosis, diversion ileostomy is always better. Mesenteric vessels are not divided here. Loop ileostomy is done 15-20 cm proximally as ileum is not resected and later repositioned once its purpose is served **(Fig. 21-61)**.


Tape is passed around the terminal ileum 15–20 cm from ileocaecal valve
Coloured sutures to identify the proximal and distal parts
Loop is brought out through the ileostomy aperture
Proximal cephalad end
Tape is replaced by ileostomy rod or stiff plastic tube
Distal caudal end
Curved full thickness incision at caudal end
Mucosa opened; upper proximal end is reflected upwards to create spout
Proximal 5 sutures
Distal interrupted full thickness edge suture is taken to fix it to sub cuticular part of the skin
All interrupted
Distal 3 sutures
All sutures are placed at caudal and cephalad parts
First caudal sutures are tied; then cephalad proximal sutures are tied

Fig. 21-61: Technique of doing loop ileostomy.

Midline laparotomy is done for definitive condition. Once loop ileostomy is planned; stoma site is marked alike in end ileostomy on the right iliac fossa at lower rectus muscle area. Site in the ileum is identified and antimesenteric part is held with a Babcock's forceps. A small window is made in the small bowel mesentery and a tape is passed around it. Proximal and distal parts are tagged with stay stitches of different colours for identification purpose when it is brought out of the ileostomy aperture. Loop is brought out of the ileostomy wound. Rotation or twist or tear in the mesentery should not occur while pulling out. Proximal end is identified and oriented at cephalad direction; distal end is at caudal end. Tape is replaced with ileostomy rod; or stiff plastic tube can be placed. Laparotomy wound is closed. After proper identification of loops coloured stiches can be removed. Incision is made on the distal caudal end transversely using no 15 blade or cautery 0.5 cm from the distal skin margin. Incision extends 5 mm in front of the mesenteric attachment. Scissor is often better to the needed enterotomy. 3 zero vicryl interrupted sutures are placed from full thickness cut edges to the subcuticular part of the skin; caudally 3 sutures are needed; cephalad 5 sutures are needed. Sutures are kept long untied. Once all sutures are placed first caudal sutures are tied; then cephalad sutures are tied. Only proximal functioning part of the loop is everted, not distal non functioning part. *Spouting* is thus created to place a proper stoma appliance.

Complications of Ileostomy

Mucosal sloughing, pseudoobstruction, later cutaneous stenosis (Bishop's collar deformity), high output, electrolyte imbalance, parastomal infection by bacteria, *candida*, ileostomy fistula, paraileostomy ulceration, ileostomy obstruction, ileostomy recession, ileostomy prolapse and hernia. Many of these complications need revision ileostomy.

CLOSURE OF ILEOSTOMY

Closure of ileostomy is done after 3 months not prior to that. In closure of loop ileostomy distal part of the bowel should be assessed by doing colonoscopy and contrast X-ray. Bowel preparation may be needed with clear liquids for 24 hours prior to surgery. Nasogastric tube and urinary catheter is passed.

Under general anaesthesia in supine position after cleaning and draping, a circumferential incision is made close to mucocutaneous junction leaving 2 mm skin margin. Transverse or vertical extension if needed should be done. These extensions will help in proper adequate mobilization of bowel proximally and distally. Bowel wall is held with Allis forceps and traction is given to facilitate the dissection between bowel margin and abdominal wall to enter the peritoneal cavity. Usually sharp dissection using no 15 blade or scissor is used to cut through the planes. Cautery usage should be carefully done only to avoid the bowel injury. Counter traction on skin margin is achieved using retractor. Traction on the bowel edge with countertraction on the abdominal wall is essential to open the planes by sharp dissection. Once abdominal cavity is reached, adhesions are released by finger dissection keeping index finger close to the abdominal wall and with sweeping action. Once mobilized loop is brought out of the wound, proximally on both sides adequate mobilization should be done to avoid tension on the ileostomy closure. Adhesions on the part of the mesentery of that particular loop are also freed carefully without tearing the mesentery. This prevents kinking, angulation and tension on the bowel wall. Mucosal eversion is reversed. Cut edge of the bowel is trimmed to remove attachments of the skin and fat on to it. Adequate bleeding from the trimmed cut edge of the bowel is essential. Bowel wall serosa is also carefully dissected off from fat and adherent tissue. This facilitates the closure of anastomosis. Any tear in the bowel wall should be checked which might have occurred during dissection. It may be confirmed by infusing the normal saline into the lumen. Edge of the ileum should be cut properly using fine scissor. Defect in the bowel wall is closed transversely using 3 zero vicryl as interrupted sutures. Initially corner stitches are placed which are held up as stay stitches. Next middle stitch is placed to appose the defect. Further other stitches are placed at 3-5 mm gap. Usually full thickness suturing is done; but it is often advisable to place seromuscular sutures including proper bites on submucosa but mucosa is spared. This ensures accurate approximation. Often outer interrupted silk sutures are placed as additional seromuscular but it is not necessary **(Figs 21-62 and 21-63)**.

Bowel kept outside the wound is gently pushed inside without disruption. Drain (peritoneal) is usually not kept; but often is kept in practice by many. Rectus sheath is closed as interrupted single layer. Full thickness bites using nonabsorbable suture material (1 zero) is used. Skin is often kept open instead of primary suturing. Secondary suturing is done once wound granulates well after 3 weeks. Often wound heals by scarring without secondary suturing. Whenever primary skin closure is done using 1 zero polypropylene interrupted sutures, subcutaneous drain should be placed.

In difficult situation, abdominal wound is extended adequately transversely or vertically. Complete mobilization of the ileum and ascending colon is done. Resection and anastomosis is done. Anastomosis is either ileoileal or ileocolic type depending on bowel retained **(Figs 21-64 and 65)**.

Stapler closure of the loop ileostomy can be done. It is usually done as side to side.

Post-operative Care

Oral liquid is started after 48 hours. Low residue diet is used for 8 weeks. Antibiotics, heparin, urinary catheter is kept in place. Nasogastric tube is removed in 48 hours.

Complications

Anastomotic disruption and faecal fistula through the wound is the complication. Usually it settles down with conservative therapy. Occasionally it needs ileostomy again and later period resection and anastomosis.

Wound infection is common which settles with regular dressing and antibiotics.

SEROSAL PATCH TECHNIQUE

It is used in enterocutaneous fistula and intestinal perforations. In 1959 to 1963 Austin Jones and Kobald and Thal started this technique. This is useful in difficult cases. Serosa has got high ability to seal the perforations of any nature recent, chronic or with severe sepsis. But it is not routinely used; it is reserved for cases where nothing else is possible.

It is used when there is difficulty in closing duodenal stump, large perforations; enterocutaneous fistulas where in spite of proper conservative therapy patient is not responding.


Circumferential incision
Mobilisation of loop
Ileostomy cut edge is trimmed and refashioned for closure
Stay sutures placed at corners
Middle suture is placed
All interrupted sutures are placed and kept long untied
All sutures are tied one by one
Usually single layer interrupted sutures
Rectus sheath is sutured, skin sutured or can be kept open for healing

Fig. 21-62: Technique of ileostomy closure—loop type.


Old laparotomy scar
Ileostomy
Circular incision may be extended transversely
Ileostomy with adjacent rim of skin is dissected off the rectus sheath all round
Ileostomy with adjacent rim of skin is dissected off the rectus sheath all round
Extension medially
Release of adhesions in the abdomen
Release of adhesions in the abdomen
Distal closed loop is identified
Ileostomy loop as it is unhealthy is resected

Figs 21-63(1)


Ileostomy loop as it is unhealthy is resected
Distal closed end is not opened instead end to side anastomosis is done
Resected proximal end
End to side anastomosis between end of proximal and side of distal part
Completed anastomosis
Checking the lumen
Drain may be placed - optional; not always necessary
Closure of rectus sheath single layer interrupted
Skin wound can be left alone to granulate and heal; if sutured subcutaneous drain may be needed

Figs 21-63(2)

Figs 21-63(1 and 2): Closure of the ileostomy.


End ileostomy is mobilised after circular incision.
Distal cut end is identified and mobilised; Its stapled end is excised and end to end anastomosis is done.
Alternatively stapler anastomosis side to side can be done.

Fig. 21-64: Ileostomy closure—in loop end type.


Side to side stapler anastomosis is done; stapler device is passed through the open end
After side to side stapler firing end is closed with another stapler.

Fig. 21-65: Ileostomy closure using stapler.

It is used in leaking or difficult duodenal stump after Billroth II anastomosis; in duodenal perforation if closure is not possible or pyloroplasty is not possible; in disrupted already done pyloroplasty; in enterocutaneous fistula.

Procedure

Serosa of the small bowel (usually jejunum) is used. Loop (omega) or Roux loop is used. Serosal surface of the bowel is cleared of all fat by gentle dissection. Perforated site is debrided and edge is trimmed. If possible, if there is no tension perforated edge can be sutured; otherwise site is directly kept ready for serosal patch. Serosal patch is sutured 7 mm away from the edge of the defect/perforation. Interrupted seromuscular bites are taken both from the perforated bowel and the intestine which is being used for patching. 3 zero silk is used for suturing. Sutures are placed at 3 mm interval **(Figs 21-66 to 21-68)**.


Serosal patch bowel is sutured (without mucosal anastomosis) and without closing the defect.
– Patch is directly placed on the defect
7 mm
3 mm
Fistula leak/perforation in the bowel
– 7 mm away from margin of the defect serosal patch is sutured.
– Bowel used for patching is not incised.
– Seromuscular bites are taken from both bowel being patched and bowel used for patch.
– Every 3 mm interval interrupted sutures are placed.
– Fat on the serosal surface should be removed.
– Tension on the serosal patch should be avoided.
Serosal patch is sutured after closure of the defect/perforation with sutures

Fig. 21-66: Serosal patch technique.



Disrupted duodenal stump or difficult stump to close



Serosal bowel (jejunal) patch using Roux loop in the duodenal stump

Fig. 21-67: Serosal patch technique for duodenal stump problems after Billroth II anastomosis.

Problems

It is technically demanding. Recurrence of fistula and disruption may occur.


Disrupted pyloroplasty
Serosal patch on the disrupted pyloroplasty using Roux loop

Fig. 21-68: Serosal patch technique for disrupted Finney's pyloroplasty.

SMALL INTESTINE ATRESIA (INTESTINAL ATRESIA)

It is jejunoileal atresia. It is due to intrauterine mesenteric vascular accidents (occlusion) of the segments affected. V-shaped mesentery; presence of bile pigments in the distal segments suggesting earlier period of patency—are supportive for the above theory. It is often associated with malrotation, gastroschisis, volvulus—20%. Common site is proximal jejunum; next common is distal ileum. Maternal polyhydramnios occurs in 35% of jejunal atresia. Proximal bowel wall is dilated with hypertrophy but villi are normal. Distal bowel is collapsed but with hypertrophied villi. Narrow collapsed large intestine (microcolon) is seen in proximal atresia.

Griesfield Modification of Martin's Classification of Intestinal Atresia

Type I: Membranous/mucosal with normal mesentery— 20%.
Type II: The lumen is atretic—fibrous cord between proximal and distal parts of the segment involved (only one atretic segment) but mesentery is normal—40%.
Type III (a): Atresia with complete separation of proximal and distal ends and V-shaped defect of mesentery—35%.
Type III (b): Atresia with christmas tree-shaped defect in mesentery with distal bowel being supplied by single artery—right colic/ileocolic/superior mesenteric—*apple peel atresia*.
Type IV: Multiple atresias—5% **(Fig. 21-69)**.


Type I: Mucosal atresia
Type II: Fibrous atresia
SMA
Jejunum
Type IIIa: Complete single atresia–V shaped mesentery
Type IIIb: Complete jejunal atresia with coiled ileum — cristmas tree deformity
Type IV: Multiple atresias

Fig. 21-69: Intestinal atresia.

Treatment

Resection and anastomosis is the choice of therapy. Treatment of associated anomalies; tapering proximal jejunoplasty is done if extensive length of jejunum is involved. Prognosis depends on length of atretic bowel; multiple atresias; associated anomalies.

MALROTATION

It is interference in the process of normal rotation of midgut in fetus and its mesenteric fixation.

Stages of Normal Rotation of Midgut

Stage 1: In 4th-8th week of intrauterine period, midgut supplied by superior mesenteric artery (SMA) grows rapidly. As coelomic cavity cannot accommodate growing midgut during that period, it protrudes into the umbilical cord as *physiological hernia*.

Stage 2: In 10th-12th week, midgut migrates into coelomic cavity. First, small bowel returns towards the left side of the abdomen. Then caecocolic loop returns to left lower abdomen. It rapidly rotates 270° counterclockwise to reach right iliac fossa. Then duodenojejunal segment rotates 270° counterclockwise to reach left of SMA and behind the colon.

Stage 3: Fusion of different parts of mesentery and posterior peritoneum.

Different Errors of Rotation

Stage 1: Exomphalos major/minor or gastroschisis.

Stage 2: Errors of rotation in this stage is important and is usually considered under malrotation.

Nonrotation: Causing small bowel in right side; colon in left side; caecum in midline as suspension.

Incomplete rotation: It is the *most common type* of malrotation. Caecum is located in subhepatic right hypochondrium. *Ladd's peritoneal band* connects from caecocolic loop to posterior abdominal wall compressing the 2nd part of the duodenum. Entire midgut is hanging down along with SMA with a narrow based mesentery causing midgut volvulus.

Reverse rotation: Final 180° rotation occurs clockwise bringing colon posterior to duodenum and SMA.

Hyperrotation: Rotation up to 360° or 450° causing caecum on left side of the abdomen. Encapsulated small bowel occurs while fetal midgut returns into coelomic cavity.

Stage 3: Final defect in fixation causes mobile caecum and ascending colon leading into caecal volvulus **(Fig. 21-70)**.

Treatment

Resuscitation, antibiotics, fluid and electrolytes, blood transfusion as initial therapy **(Fig. 21-71)**.

Laparotomy through horizontal incision is done. Clockwise rotated midgut which is congested and cyanotic is identified. Untwisting of the midgut in counterclockwise direction is done. Viability of bowel is confirmed (colour, vessels in mesentery, peristalsis, on table Doppler). *Ladd's band* is divided, *large bowel is repositioned in left side.* The entire duodenum is *Kocherised* and the ligament of Treitz is divided so that *duodenum becomes straight towards right* iliac fossa. This achieves *wide root of the mesentery* and places the *small bowel in the right* side of the abdomen thus preventing further volvulus. A *complementary appendicectomy* is done—*Ladd's operation*. After laparotomy, if bowel is gangrenous, it is resected and remaining parts of the bowel are exteriorised as enterostomies. A second look operation is done to look for viability of remaining bowel and also to maintain the continuity. Often it will be extensive bowel resection leading to poor prognosis.



Fig. 21-70: Diagram showing incomplete gut rotation and small bowel volvulus.



Fig. 21-71: Ladd's operation for incomplete gut rotation. Ladd's band is released. Duodenum is straightened. Appendicectomy is done.

MECONIUM ILEUS

It is neonatal manifestation of fibrocystic disease of the pancreas wherein thick meconium, which is viscid and paste like, gets collected in the terminal ileum. Because of inspissation it forms a firm bolus leading to obstruction of the ileum. Neonates present with features of ileal obstruction as well as respiratory dysfunction, exocrine pancreatic insufficiency, and high salt in the sweat (Na^+ and Cl^- more than 90 mmol/L). Meconium ileus occurs in 15% of patients with cystic fibrosis. Cystic fibrosis is an autosomal recessive disease involving bronchioles, exocrine pancreas and sweat glands.

Condition is common in Caucasians. Exocrine pancreatic insufficiency and malabsorption is seen in 90% of patients with cystic fibrosis. There is hypertrophy and dilatation of the proximal ileum containing thick, viscid, tenacious dark green meconium. Distal ileum and colon are narrow and contracted having grayish meconium pellets. Meconium gets calcified very rapidly. Gangrene, perforation, volvulus can occur in 50% of cases. Intrauterine perforation causes fetal meconium peritonitis which leads to dense adhesions and calcification in peritoneum. Fetal meconium peritonitis is sterile. Plain X-ray shows calcified meconium pellets with multiple air fluid levels which appear as 'soap-bubbles' (*Neuhauser sign*). Vomitus of the patient which does not contain trypsin, when poured on the exposed X-ray film will not digest the gelatin of the film whereas the vomitus of individual with normal pancreas will digest the gelatin of X-ray film—*very useful test.* Pilocarpine, a cholinergic drug is injected into skin to stimulate the sweating and collected sweat (100 μg sweat) is analysed for sodium and chloride. Elevated albumin level in meconium, sodium level assay in nail clipping, serum immune active trypsin assay are other investigations **(Fig. 21-72)**.



Fig. 21-72: Pathology of meconium ileus. Note the meconium pellets in the distal ileum and colon; thick viscid meconium in proximal ileum.

Treatment

Nonoperative Measures

Dissolution through enema can be tried using *gastrografin* which is hyperosmolar and contains Tween 80 as dissolving agent. *Gastrografin* is diatrizoate meglamine with Tween 80 (polysorbate 80) as dissolving agent.

Acetyl choline (2-4%) also can be used for irrigation per-anally. Acetyl choline wash through nasogastric tube also can be used—5-10 ml 6th hourly. Treatment for cystic fibrosis is needed.

Operative Measures

When patient's condition is critical with obstruction, *Bishop-Koop operation* is done. Proximal dilated segment is resected and resected end is anastomosed to side of the distal collapsed ileum. End of the distal ileum is brought out as ileostomy. Through the ileostomy gastrografin or acetyl cystine wash is given regularly to dissolve meconium pellets. This ileostomy can be kept for long time. Continuity is maintained at later period **(Fig. 21-73)**.

Santulli operation is done where proximal ileum is brought as ileostomy for irrigation using a fine tube and distal ileum is sutured to proximal ileum as end to side anastomosis **(Fig. 21-74)**.

Resection and anastomosis is ideal if patient is fit and if proximal bowel is suitable for anastomosis.

SHORT BOWEL SYNDROME (SHORT GUT SYNDROME)

It is the symptom complex after massive small bowel resection, i.e. *resection more than 70% of the bowel*. Minimum bowel required is 1.2 meters. Proximal jejunal resection is better tolerated than distal ileal resection. Ileum is more adaptive and has got capacity to increase the absorption capacity more efficiently. So in massive resections, patients with retained ileum will do better. Adaptation is better if ileum and caecum is preserved.



Fig. 21-73: Bishop-Koop operation. Here distal ileum is brought as ileostomy and proximal part sutured to distal bowel.



Fig. 21-74: Santulli operation done for meconium ileus wherein proximal ileum is brought out as ileostomy. Distal ileum is sutured to proximal.

Causes

Massive small bowel resection as in superior mesenteric artery ischaemia; multiple sequential resections; recurrent Crohn's disease—common cause, necrotising enterocolitis in neonates and children, intestinal atresia, midgut volvulus, radiation enteritis.

Adaptive Changes in the Retained Small Bowel

Villous hypertrophy and hyperplasia, increased absorptive surface, increased capacity of small bowel, lower transit time of bowel content are different changes.

Factors Deciding the Outcome in Short Gut Syndrome

Age: Infants tolerate massive resection better. Retaining ileocaecal valve shows better outcome as ileocaecal resection interrupts the enterohepatic circulation of bile salts which in colon gets metabolised to secondary bile salts. Secondary bile salts block the absorption of water and electrolytes. Delayed clearance of gastrin causes hyperacidity and peptic ulcer. Adaptability of the small bowel—adaptation is better if ileum and caecum are preserved. Additional colectomy increases the morbidity. In such occasion retained jejunum will function as either of two ways.

'*Net absorbers*' have adequate absorption of water and sodium and usually will have more than 100 cm of retained jejunum. '*Net secretors*' have less than 100 cm of jejunum and lot of sodium and water are secreted into the lumen from plasma. These patients should avoid hypotonic solutions like water/tea; instead should take hypertonic saline with glucose containing 90 mmol sodium/L. WHO cholera fluid is ideal (contains 90 mmol sodium/L).

Clinical features: Diarrhoea, fluid and electrolyte deficiency, severe malnutrition, recurrent bacterial enteritis.

Outcome of Short Bowel Syndrome

Severe malabsorption, severe dehydration, gallstone formation due to altered bile metabolism, urinary calculi due to increased oxalate level, water and electrolyte imbalance, diarrhoea is common, recurrent bacterial enteritis, fulminant hepatic failure often can occur, osteomalacia, tetany, hypomagnesaemia, bleeding diathesis, peripheral neuropathy.

MASSIVE BOWEL RESECTION

Resection of *more than 200 cm* of small bowel is called as massive resection. *Metabolic sequelae* in massive resection depends on—extent and anatomical site of resection, functional capacity and adaptation of the small or large bowel, cause for the resection. It causes gastrin hypersecretion, increased parietal cell mass in stomach, peptic ulceration; increased endocrine pancreatic secretion; hypoalbuminaemia, oedema. *Resection of more than 100 cm of distal ileum* causes diarrhoea and steatorrhoea (steatorrhoea is faecal fat > 6 g/day), increases bile lithogenicity, causes deficiency of vitamins A, D, E, K; colonic bacteria converts unabsorbed fatty acids and conjugated bile salts into hydroxy fatty acids and deconjugated bile salts. *Ileum* maintains enterohepatic circulation of bile salts, absorption of vitamin B12 and vitamin D. Resection of middle part of small bowel is better tolerated. *Removal of ileocaecal valve* reduces the intestinal transit time; reduces absorption of vitamin B12, calcium, magnesium, zinc; increases diarrhoea and contamination of shortened small bowel by bacteria. In massive resection, *colonic bacteria* degrade fatty acids into lactate and short chain fatty acids; lactate reduces colonic pH which inhibits bacteroides; due to this acid resistant anaerobes will increase in colon which produces large amount of D lactate which is absorbed causing *D lactic acidosis* presenting with confusion, ataxia and nystagmus. *TPN* was introduced by Dudrick. It is very useful in short gut syndrome.

Treatment

Early Phase

Total parenteral nutrition.

Fat and fibre free but protein rich liquid diet with essential fatty acids; diarrhoea is controlled by loperamide/codeine phosphate; oral cholestyramine to bind bile salts is needed in massive resection which includes ileum; parenteral vitamin B12 injection regularly; H2 antagonists/PPIs/somatostatin (to reduce secretions from stomach, liver and pancreas); octreotide reduces the secretion and reduces GI motility; fluid and electrolyte management; control of diarrhoea.

Late Phase

Enteral nutrition is used to stimulate intestinal adaptation; TPN supplement—often permanently required; *lome parenteral nutrition* is universally used method in western countries. But in Asian countries it is not yet practicable. Hormones and glutamine administration are under trial.

Surgical techniques to delay the intestinal transit time or small bowel transplantation are under trial but with less success. *Reversal of 10 cm intestinal segment* to delay transit time can be useful. *Intestinal lengthening* to delay transit time and increase the absorption surface is done. *Small bowel transplantation*, ideal but graft rejection and failure is the problem. Antiperistaltic colonic interposition into the small bowel segment also tried. Regeneration of intestinal mucosa over denuded serosa is a new method. Longitudinal splitting of the intestine and closing of these as separate tubes which are anastomosed to each other to achieve lengthening—*Binachi's surgery*. Mucosal *stem cell transplantation using enterocytes* without lymphoid tissue. Seeded mucosal autografts in prosthetic tubes are other newer methods on trial.

APPENDIX

SURGICAL ANATOMY OF APPENDIX

It is a worm like diverticulum, located at the terminal end of the caecum where three taeniae join, about 2 cm below the ileocaecal orifice. Usually it is around 2-20 cm in size but can be variable (9/10 cm average). Size of its lumen is that of matchstick. Diameter of appendix is 3-8 mm; diameter of lumen is 1-3 mm (matchstick). It is longer in children. *Base of the appendix is located 2 cm below the junction of the transtubercular and right lateral planes. McBurney's point is only site of maximum tenderness in appendicitis* **(Figs 21-75 and 21-76)**.



Fig. 21-75: Base of the appendix is located 2 cm below the junction of the transtubercular and right lateral planes.

Mesoappendix is extension of the mesentery containing appendicular artery, a branch of ileocolic artery. Artery runs behind the terminal part of the ileum and enters the mesoappendix near base where it gives a recurrent anastomotic branch to posterior caecal artery. Artery ends in the wall of the appendix near tip. Often an accessory appendicular artery *(of Seshachalam)* may be present. Thrombosis of these vessels leads to gangrenous appendicitis **(Fig. 21-77)**.

Venous drainage is through appendicular, ileocolic, superior mesenteric and portal vein.

Nerve supply: T9 and T10 sympathetic nerves supply appendix through coeliac plexus.

Lymphatic drainage: mainly it is to ileocolic nodes. Often drainage may occur through appendicular nodes.

Mucosa of appendix is lined by columnar cells with crypts. Submucosa contains numerous lymphatic aggregations (follicles*)* *('Abdominal Tonsil')*. Opening of the appendix into caecum is guarded by *'valve of Geralch'* **(Fig. 21-78)**.



Fig. 21-76: Mc Burney's point is only site of maximum tenderness in appendicitis. It at the junction of lateral 1/3rd and medial 2/3rd of right spinoumbilical line.


Ileocolic artery
Superior mesenteric artery
Anterior caecal artery
Caecum
Ileum
Posterior caecal artery
Appendicular artery
Recurrent anastamotic branch
Appendix

Fig. 21-77: Appendicular artery.


Type A
Type B
Bird-beak appendix
Single caecum double appendix
Type C
Double caecum double appendix

Fig. 21-78: Wallbridge classification of duplication of appendix.

Duplication of appendix
(Wallbridge classification)
Type A: Partial duplication in a single caecum.
Type B: Two separate appendices in a single caecum.
Type C: Double caecum with each one having one appendix.

Different Positions are

Most common position *is retrocaecal (65-75%). Next common is pelvic (21-31%). Other sites are:* Preileal (anterior) —rare (1%); Postileal (splenic)—rarest (0.4%); Paracaecal; Subcaecal (2.2%); Subhepatic.

Often it may be in subserosal plane leading to difficult dissection during appendicectomy. In *situs inversus* appendix is on *the left side* **(Fig. 21-79)**.


Preileal
Retrocaecal
Postileal
Paracaecal
Pelvic
Subcaecal

Fig. 21-79: Different positions of the appendix.

APPENDICECTOMY

Reginald Fitz from Boston coined the term appendectomy in 1886. Chester McBurney started early surgery for acute appendicitis with muscle splitting incision (1884-1889).

Indications

- Acute appendicitis.
- Recurrent appendicitis.
- Appendicitis in pregnancy—done in 2nd trimester ideally.
- Appendicectomy as a part to give colonic lavage (Doodley's lavage). Appendicectomy along with other procedures—in correcting the malrotation of the gut (Ladd's procedure).
- Appendicectomy in carcinoid tumour involving the tip of appendix and tumour size less than 2 cm.
- Appendicectomy is done in *Munchausen syndrome*—a psychological condition.

Contraindications for Appendicectomy

- Appendicectomy is contraindicated in appendicular mass when formed after an attack of appendicitis. Here appendicectomy is done after 6 weeks as interval appendicectomy.
- Appendicectomy is not done in acute phase of Crohn's disease; however, it should be done if appendix and caecum is diseased.

Investigations

- Total leucocyte count is increased.
- U/S is done to rule out other conditions like ureteric stone, pancreatitis, ovarian cyst, ectopic pregnancy and also to confirm appendicular mass or abscess **(Fig. 21-80)**.

Sonographic Criterias for Appendicitis (85% specificity)
Noncompressible appendix of size > 6 mm AP diameter, hyperechoic thickened appendix wall > 2 mm—target sign.
Appendicolith.
Interruption of submucosal continuity.
Periappendicular fluid.
Caption: U/S showing dilated noncompressible appendix.



Fig. 21-80: Ultrasound of the appendix.

- Contrast CT scan is very much useful when diagnosis is difficult especially in old people. Dilated appendix; dilated lumen; thickened wall; nonfilling of the lumen by contrast or air; periappendicular fluid collection; presence of mass/abscess/associated pathology like carcinoma can be identified. It has 95% sensitivity and specificity with 95% accuracy. *Dirty fat thickened mesoappendix*, appendicular *phlegmon*, appendicular *faecolith* and thickened caecum funneling contrast into the orifice of the appendix as *arrowhead sign*—are all relevant features in CT scan.
- MRI is very useful in diagnosing appendicitis in *pregnancy*.
- *C-reactive protein,* even though nonspecific increases in acute phase. *99mTc HMPAO labeled leucocyte* imaging may give guidance in deciding the management.
- Laparoscopy is the most useful method **(Fig. 21-81)**.



Fig. 21-81: Calcified appendix/faecolith in plain X-ray.

Preparation

- Preoperative diagnosis by US abdomen; CT scan; total leucocyte count and by clinical features.
- Nil per orally for 6 hours prior to surgery.
- Preparation of skin of entire abdomen as possibility of extension of the incision should be kept in mind.
- Fitness for anaesthesia; blood sugar and serum creatinine estimation should be done.
- Urinary catheter is passed in laparoscopic appendicectomy or in difficult appendicectomy or in appendicitis with peritonitis where laparotomy is needed. In regular appendicectomies patient is asked to pass urine to empty the bladder before coming to operation theatre.
- Nasogastric tube is passed in peritonitis, burst appendicitis or with suppuration.
- Preoperative intravenous antibiotics should be started—amoxycillin, metronidazole or higher antibiotics depending on the need of individual case basis.

Types of Appendicectomy

- **Open appendicectomy**: Good old method. Here entire peritoneal cavity cannot be visualised. Often it may require extension of incision or converting into formal laparotomy **(Fig. 21-82)**.
- **Laparoscopic appendicectomy**: It is the gold standard approach for appendicectomy. Incision is small; entire peritoneal cavity can be seen which is important especially in females. Recovery is faster in this type.
- **Laparoscopic assisted appendicectomy:** Peritoneal cavity is visualised through laparoscope and appendix is delivered outside under vision through umbilical port or 10 mm working port. Mesoappendix and stump is dealt like in open appendicectomy. It is faster and meantime diagnosis is also confirmed. But it is often difficult to bring out the appendix with mesoappendix outside as mesoappendix may get torn.
- Appendicectomy can be done through **single incision laparoscopic surgery (SILS)**.
- **Interval appendicectomy** is done after initial conservative treatment for appendicitis or appendicular mass.
- **Incidental appendicectomy** is done along with some other abdominal procedures. Nowadays it is not practiced unless genuinely indicated.
- **Retrograde appendicectomy** is a type of dissection (not approach) done when tip is difficult to identify or to dissect. Here base of appendix is identified, dissected, mesoappendix adjacent to base is ligated or fulgurated using bipolar cautery. Base is crushed; transfixed using 2 zero vicryl and dissection is proceeded towards tip by repeated clamping and ligating tissue close to the appendix and ligating repeatedly until tip is dissected and appendix is freed entirely (serial clamping, division and ligation).
- **Elective appendicectomy** is nothing but interval appendicectomy done after recovering from an attack of acute appendicitis.
- **Emergency appendicectomy** is doing appendicectomy at the time of acute appendicitis.

Note:

- There is no role for prophylactic appendicectomy.
- But removal of normal appendix in an exploration for presumed appendicitis is accepted based on following reasons:



Fig. 21-82: Open appendicectomy.

- Early acute appendicitis (catarrhal/mucosal) on gross inspection is difficult to determine accurately; so grossly normal looking appendix still can have early appendicitis.
- It avoids future diagnostic dilemma in chronic pain in right iliac fossa. Pain may be due inflammatory bowel disease or gynaecologic conditions.
- A scar in right iliac fossa in any patient is assumed by surgeon that appendicectomy is done.
- Long kinked appendix or presence of faecolith may justify appendicectomy.

OPEN APPENDICECTOMY

Anaesthesia: However, even spinal anaesthesia is satisfactory general anaesthesia is ideal.

Incision

- *McBurney's incision* is used (McArthur; Gridiron). McBurney's point is junction of lateral 1/3rd and medial 2/3rd of right spinoumbilical line. At this point perpendicular to this line, incision of 5 cm in length is made 2.5 cm on each side. It is muscle splitting incision. Gridiron is a frame of cross beams to support a ship during repairs.
- *Lanz crease incision* is curved horizontal incision of 5 cm in length. Deeper dissection is same as McBurney's incision. It is cosmetically better as it is in the crease line.
- *Rutherford Morrison's muscle cutting incision:* It is usually modification done in an originally placed McBurney's incision as an extension to have better approach. Here internal oblique and transverse abdominis muscle are cut laterally. It is often done in higher or difficult or subhepatic appendix.
- *Fowler-Weir (Fowler-Davis; Rockey-davis) approac*h: Here extension of the original McBurney's incision is done medially and below by cutting lateral part of the rectus sheath. It is used in pelvic appendix or to feel the right ovary properly.
- *Right paramedian or lower midline incision:* It is used in case of peritonitis due to burst appendicitis **(Fig. 21-83)**.



Fig. 21-83: Different approaches for open appendicectomy.

Procedure

Skin is incised. Outer Camper fascia with subcutaneous fat is incised. Inner membranous scarpa's layer is also incised. Often superficial epigastric and superficial circumflex veins may require to be ligated. External oblique aponeurosis is visualized. It is incised laterally using blade. Medially it is cut along the line of incision using scissor or cautery. Cut edges are held using haemostats. Two Langebeck retractors are placed deep to the aponeurosis to visualize internal oblique muscle. Internal oblique muscle is split in the line of fibers using curved haemostat (curved medium sized artery forceps). Direction of the tip of the instrument should be laterally to prevent inadvertent opening of the rectus sheath and muscle and also to avoid injuring the inferior epigastric vessels. Similarly transversus abdominis muscle is split to reach the peritoneum. Often two fingers are passed deep into the wound and stretched away from the wound line to increase the space underneath. Often extraperitoneal fat may be present which needs careful blunt dissection with finger. Small vessel bleeding can occur which should be controlled using cautery. It confirmed that the bowel is not close under the peritoneum by filling peritoneum with two fingers. Peritoneum is opened by an oblique incision using blade or scissor; fluid if exudes should be collected for culture. Omentum at the site under the peritoneum suggests that appendix is inflamed. Peritoneum incision is extended along the line of skin incision (wound) to enter the peritoneal cavity.

Caecum is located in the right iliac fossa which is identified by the presence of 3 taeniae. Often summit of the sigmoid colon when it is redundant will be towards the right iliac fossa and may be mistaken for caecum and leads into futile search for appendix. Once taeniae of caecum is identified; caecum is held and gently pulled towards the wound without causing serosal tear. Caecum is held using Babcock's forceps. Base of the appendix will be identified. By putting the index finger inside the peritoneal cavity one can gently feel tubular structure which has got blind end and connects to caecum. But fallopian tube in females may be mistaken for that. Once the base of appendix is identified it is held with another Babcock's forceps. Gentle continuous traction with careful finger dissection makes entire appendix to be delivered through the wound outside. Whenever adhesions are present sharp dissection with scissor is better to prevent tear in the base of the appendix or in the caecum. Adhesions anywhere other than mesoappendix part are avascular and will not bleed much by sharp dissection. Careful judicious cautery dissection is allowed but one should not cause cautery injury to caecum or base which may lead to late necrosis, perforation and peritonitis which is life threatening. During dissection bowel should be held using non toothed forceps.

In females by passing right index finger, right ovary and fallopian tube should be palpated to confirm that they are normal. If there is fluid it should be collected. If there is blood one should suspect ectopic gestation and in such situation appendix will look grossly normal. It is also important to pull out terminal ileum for the presence of Meckel's diverticulum; and also to inspect and palpate ileal mesentery for enlarged lymph nodes.

Mesoappendix is often thick, oedematous and friable. Appendicular artery can be often seen through light transillumination which is dissected, clamped with haemostats, cut and ligated using 2 zero silk or vicryl (first ligation can be done by passing two ligatures and then can be cut). If it is difficult to identify appendicular artery which is a branch of ileocolic artery then mesoappendix clamped at several places up to the base and transfixed using silk or vicryl. Accessory appendicular artery when present should also be dealt similarly **(Figs 21-84A to D)**.

Appendix is held with Babcock's with proper visualization of the base of the appendix with adequate caecal wall. Base, 3-5 mm from the caecal junction is crushed using curved artery forceps (haemostat) and released and applied again 1 cm distally. Crushed part of the base of appendix is transfixed using figure of eight suture by 2 zero vicryl suture. Crushing the base was good old practice, which is done to appose the mucosal surface firmly. But now it is argued that crushing is not necessary and transfixation is done without crushing the base. Additional simple (not transfixation) ligature using vicryl or silk is done 2 mm proximal to this to have double ligation of the base. Appendix is cut between distally applied artery forceps and transfixation ligature using no 15 blade. Stump is cleaned with normal saline or povidone iodine solution. Two ligatures are safer to prevent giving way and it is practiced commonly; evidence suggests one strong proper ligature at the base is sufficient enough to hold **(Fig. 21-85)**.

Base of the appendix can be ligated with two firm ligatures using silk or vicryl without any transfixation also, like what is practiced in laparoscopic appendicectomy **(Fig. 21-86)**.

Invagination or Burial of the Appendix Stump

Burial of the stump can be done by various methods. Need for invagination or burial and its advantages are controversial. It was earlier thought that burial prevents the exposure of the stump to free



Figs 21-84A to D: Babcock's instrument is used to hold appendix and caecum during appendicectomy. Caecum should be held at taenia.


Umbilicus
McBurney's point
McBurney's (Gridiron) incision
Anterior superior iliac spine
Exposed external oblique aponeurosis
Subcutaneous fat and two layers of superficial fascia are cut
External oblique aponeurosis is cut
Internal oblique and tranversus abdominis are split in the line of fibers using curved haemostat or curved scissor

Figs 21-85(1)


Peritoneum
Peritoneum is held and lifted up using 2 haemostats and cut using scissor or blade
Babcock's forceps
Caecum
Inflamed appendix
Base
Mesoappendix

Figs 21-85(2)


Inflamed appendix
Base
Caecum
Mesoappendix
Mesoappendix with appendicular artery is ligated using silk
Mesoappendix with ligated and cut appendicular artery
Caecum
Base
Appendix near base (3-5 mm from base) is crushed using haemostat
Appendix held with Babcock's forceps
Base
Caecum
Crushed base (close to) of appendix
Haemostat is released and applied distally

Figs 21-85(3)


Appendix base is ligated; 2 ligatures - one with vicryl - transfixation and another one with simple ligature.

Appedix stump
Appendix specimen

Closure of peritoneum using vicryl

Figs 21-85(4)


Layer by layer
closure using vicryl
Closure of external oblique
using continuous 2 zero vicryl suture
Subcutaneous
absorbable sutures
Subcuticular skin suture with absorbable

Figs 21-85(4)

Figs 21-85(1 to 4): Technique of open appendicectomy.



Figs 21-86A and B: Ligation of the stump of the appendix.

peritoneal cavity which may lead into adhesion/band or sepsis. But present antisepsis, antibiotics use proved it is not so and there is no need to invaginate the stump. There is a debate that burial itself may precipitate abscess formation by creating closed cavity within the stump - serosa area. But again it is also controversial; however, present accepted trend/method is not to use invagination/burial; but place two ligatures with one of them may or may not be transfixation.

Burial when used is done by various methods—Simple 2-3 seromuscular Lembert interrupted sutures or purse string sutures. Purse string suture is taken using 2 zero silk or vicryl. Bites are taken circumferentially around the base starting from one point 5-10 mm away from the base on the caecal wall beginning from a taenia and ending (last bite) again at same taenia usually last bite passes beyond the first seromuscular caecal bite. Ends of the suture material are kept long with small haemostats. It is usual practice to take seromuscular invagination purse string circumferential sutures before transfixing the appendix but after freeing the appendix from mesoappendix. Many surgeons also practice taking seromuscular caecal purse string sutures after transfixation and cutting the appendix. Whatever the way it does not make much difference until burial/invagination is proper and adequate. Once appendix stump is cut purse string suture is gently tied towards the base; in the meantime, assistant will push the stump deep to serosa using a haemostat or non toothed forceps. Burial knot is placed.

Normal saline wash is given to the cavity and suction is done **(Fig. 21-87 to 21-89)**.

If appendix is perforated and there is pus around the appendix drain (tube/corrugated) is placed in the right iliac fossa. But its use is controversial and questioned **(Figs 21-90 to 21-92)**.

Wound is closed in layers: Peritoneum with continuous 2 zero vicryl. Transversus abdominis and internal oblique with 2 or 3 interrupted vicryl apposition sutures. Sutures should be loose and fascia covering the muscle should be included (not just muscle bundle). External oblique aponeurosis is closed using continuous vicryl suture. Skin is closed with interrupted nonabsorbable suture (polypropylene/polyethylene) suture or absorbable 3 zero subcuticular suture. Sutures are removed in 7 days. If there is infection skin wound can be left open until it granulates. When infection comes under control it is closed by secondary suturing.

COMPLICATIONS AFTER APPENDICECTOMY

- *Paralytic ileus* is due to sepsis and bowel handling. It usually subsides in 2-3 days.
- *Reactionary haemorrhage* due to slipping of ligature of the appendicular artery can be life threatening. Tachycardia, palor, dropping haemoglobin and PCV are the indicators. Emergency re-exploration with transfusion of blood is needed. Clots are removed. Bleeding artery is identified and ligated securely.


Crushing the base
Applying heamostat distally
Purse string suture-
3-5 mm away from the base
on the caecal seromuscular layer
Seromuscular purse string
is completed
Transfixation of base
of the appendix
Tansfixed base
of appendix
Caecum
Untied purse string suture
Cutting the appendix
with no 15 blade
15 no. blade
Appendix stump
Cleaning the stump
Appendix stump
Untied purse string
Tying the purse string
Burying the stump
using non toothed forceps
Burried stump with tied purse string

Fig. 21-87: Invagination of appendicular stump using purse string suture.



Fig. 21-88: Purse string suture is passed using vicryl or silk by taking bite from taenia then seromuscular bites 5 mm away from the base of appendix circumferentially to reach same taenia again; appendicectomy is done then purse string suture is tied to invaginate the stump of appendix.

- *Residual abscess* (pelvic, paracolic, local, subdiaphragmatic) can occur. Its severity depends on the virulence and load of the bacteria. It is initially treated with antibiotics. If it persists or progresses, CT scan is done to confirm it and later appropriately drainage is done depending on the location of the abscess.
- *Pylephlebitis (Portal pyaemia)* is nowadays rare due to availability of proper antibiotics. However, it can occur if there is immunosuppression. It presents with fever, chills, jaundice and tender, smooth, soft palpable liver. It is treated with adequate antibiotics.
- *Adhesions, kinking* and intestinal obstruction can cause recurrent spasmodic/colicky pain with vomiting. It is initially treated conservatively; but may require laparoscopic adhesiolysis later.
- *Right inguinal hernia (direct)*—due to injury to ilioinguinal nerve can occur.
- *Wound sepsis* 10%, faecal fistula can occur. Wound is laid open and later secondary suturing is done in case of wound sepsis. Faecal fistula usually subsides in few weeks. If there is distal obstruction or specific causes like tuberculosis or malignancy fistula will persist which should be dealt appropriately **(Fig. 21-93)**.
- *Respiratory problems*, DVT can occur.



Fig. 21-89: Invagination of stump of appendix using seromuscular Lembert suture.



Fig. 21-90: Suppurative appendicitis.



Fig. 21-92: Appendicectomy specimen.

FAECAL FISTULA AFTER APPENDICECTOMY

Causes

It can occur when appendicectomy is done in gangrenous/perforated/friable base appendix. It can occur after drainage of appendicular abscess. It can occur if appendicectomy is done/attempted in appendicular mass. If there is underlying additional pathology like Crohn's disease/carcinoma/ileocaecal tuberculosis/actinomycosis during appendicectomy, fistula can occur **(Fig. 21-94)**.



Fig. 21-91: Placing drain after appendicectomy. Ideally tube drain is placed.

Features

Faeculent, foul smelling discharge from either main wound or drain site.
Features of infection, with skin excoriation.
Features suggestive of cause.

Investigations

CT fistulogram to delineate the track.
CT scan abdomen to find out the other pathology.
Other relevant investigations, Hb%, albumin level, etc.

Treatment

Initially conservative—antibiotics, IV fluids, dressing, zinc oxide cream over the skin, observation.

Most of the time fistula subsides, provided there is no distal obstruction by adhesions or kinking or specific causes like carcinoma or tuberculosis. If persists even after 6 weeks, resection of ileocaecal segment and anastomosis is done.

TROUBLES IN APPENDICECTOMY

During surgery if appendix is found normal, other cause for symptoms should always be looked for like Meckel's diverticulum, Crohn's disease, ovarian/pelvic causes in females, malignancy, etc.

Appendicular tumour may be found. If it is in the tip, appendicectomy is sufficient. It could be carcinoid tumour. If it is in the base right hemicolectomy is done.

Absence of appendix—a rare occasion can occur. Caecum and taeniae should be traced properly before finalising it.

Appendicular abscess/pelvic abscess formation may create difficulty in managing the situation.

Malignancy in the caecum if identified on table—right hemicolectomy should be done.



Fig. 21-93: Wound infection after appendicectomy; secondary suturing is done at a later period.



Fig. 21-94: Faecal fistula after appendicectomy.

If Crohn's disease is identified during surgery, appendicectomy can be done with care, if base of the appendix is normal. But in rare occasion where appendix is involved by Crohn's disease, appendicectomy should not be done but treated only with antibiotics and steroids, otherwise fistula can develop.

Mortality rate of appendicectomy is less than 1%. Morbidity and complications are more after surgery for perforated appendicitis.

Surgical site infection is 5% in uncomplicated appendicitis; 20% in perforated appendix after surgery.

Small bowel obstruction postoperatively is 1% with simple appendicitis; 3-5% in perforated appendicitis after surgery.

More than 50% of obstruction occurs in first year of postoperative period. In children with appendicitis, there is poor localisation and so peritonitis is common. So conservative therapy should be avoided. Surgery is the only choice of treatment otherwise early peritonitis is the danger. Appendicular mass is initially treated with *Ochsner Sherren* regime. After 6 weeks, *interval appendicectomy* is done.

Children, old age, faecolith, laxative abuse, diabetes mellitus, immunosuppression and pelvic appendix are high-risk factors for perforation in appendicitis. In pelvic and retrocaecal appendicitis, adjacent ureteral inflammation can occur in which urine on analysis shows blood cells and pus cells. Incidence of removal of normal appendix is 30%. *Stump appendicitis* is inflammation and infection in the remaining portion of the appendix stump after appendicectomy. It is a rare entity. If on table during surgery normal appendix is found, it is called as '*Lily white appendix*'. Then other pathology like Meckel's deventicular, ileal/mesenteric lymph node/ovarian disease should to be looked for.

Appendicitis is the commonest acute abdominal condition found in pregnancy, their site of pain and features vary. They need appendicectomy by laparotomy. Laparoscopic appendicectomy is under trial in pregnancy. It is more common in 1st and 2nd trimester. Guarding and rebound tenderness will be absent. Risk of premature labour is 15%. Fetal death is 5%; but if appendix busts it raises to 29%. Maternal mortality raises to 10 times after 6 months **(Fig. 21-95)**.

SMALL INCISION OPEN APPENDICECTOMY

Often many surgeons do open appendicectomy using a very small incision of 1.5 to 2.0 cm in length. Even though cosmetically it is good, due to availability of laparoscopic appendicectomy this procedure should be avoided. And also it is a blind forcible procedure which is



Fig. 21-95: Appendicectomy in pregnancy—it is usually done through laparotomy.

against surgical principle as appendix is pulled out through the wound forcibly and mesoappendix also tied forcibly with traction. There are chances of tearing of the mesoappendix, and serosa of the caecum. Moreover, once mesoappendix and stump of the appendix are tied and pushed into the peritoneal cavity, it is impossible to visualize the stump for its security and integrity making the entire procedure as presumption and blind **(Fig. 21-96)**.

Procedure

Procedure is done under general anaesthesia; a small incision of 2 cm is made in MacBurney's point. Skin, superficial fascia, external oblique, internal oblique and transversus abdominis are separated accordingly. Peritoneum is identified and is held using haemostat. Once peritoneum is opened its edges are held securely with 4-6 artery forceps (haemostats). These arteries should never be removed until appendicectomy is complete and peritoneum is closed. Using Babcock's appendix is gently pulled out into the wound with traction. Caecum is also pulled out to identify the base of the appendix. Caecum is pushed back into the peritoneal cavity with base being held using Babcock's forceps. Mesoappendix is clamped and ligated up to the base. Base is transfixed using vicryl. Another simple ligature is also placed to the base. After cutting the appendix stump is pushed back into the peritoneal cavity. Peritoneum is closed using purse string vicryl suture. Muscles apposed using one or two vicryl sutures. External oblique is closed. Skin apposed using absorbable subcuticular suture.

LAPAROSCOPIC APPENDICECTOMY

History

In 1983, Semm from Germany did first incidental laparoscopic appendicectomy. In 1987 Schrieber reported laparoscopic appendicectomies in women in acute appendicitis.

Principles and Indications

Laparoscopic appendicectomy is a relatively controversial topic as most of the surgeons including those in the West still favor open appendicectomy in all cases. The main point of concern especially for cases that present late or those with burst appendix is the failure to give adequate peritoneal toileting and the formation of abscesses in the peritoneum. This fear can be alleviated by the use of thorough irrigation with antiseptic solution and insertion of drain through lateral port for evacuation of debris. It is still recommended that the beginner have a low threshold for conversion if he finds that the appendix is not visualized, is very friable, is perforated or the peritoneum is severely contaminated. Even though most experienced surgeons are capable of taking out the appendix via a very small incision there are situations where laparoscopic appendicectomy scores over open procedure. These are:

- Vague chronic abdominal pain where diagnostic laparoscopy culminates in an appendicectomy.



Fig. 21-96: Small incision open appendicectomy technique.

- Right iliac fossa pain in young women where the cause is of doubtful appendicular or ovarian/fallopian tube origin.
- Patients with atypical pain where there is chance of abnormal position of appendix such as subhepatic or in situs inversus.
- Obese individuals where a large incision may be required to access the abdomen.
- Diabetics where there is a chance of wound infection.
- Interval appendicectomy where recovery and discharge is faster in laparoscopic appendicectomy.

Note:

In spite of all these debate laparoscopic appendicectomy has become gold standard due to its added advantages compared to disadvantages.

Cases which should be taken up with caution (preferably by an experienced laparoscopic surgeon) are:

- Patients who are poor risk for general anesthesia.
- Patients whose abdominal scan shows formation of abdominal mass
- Patients with previous lower abdominal surgery
- Patients with stump appendicitis or burst appendix.

Ideal case for a beginner would be a young adult with pain of less than 48 hours of duration when you will find a turgid appendix which is still mobile in the peritoneal cavity without much of omental adhesion and pus formation. The routine work up of the patients is done as for open surgery. Consent is taken for laparoscopic surgery as well as for conversion in each case irrespective of the nature of the case. A nasogastric tube is not routinely placed if open access technique is used but it is used if surgeon uses Veress needle to create pneumoperitoneum. Catheterization is done to evacuate the bladder. It may be discontinued for routine cases when the surgeon has got enough experience to cut down the operating time. In these cases the patient is asked to void just before the procedure to keep the bladder empty.

Advantages of Laparoscopic Appendicectomy

- It allows thorough exploration of the contents of the peritoneal cavity especially in females. It also facilitates treatment for additional pathology identified like ovarian cyst in same sitting.
- It allows easier approach in subhepatic appendix and appendix in situs inversus.
- It allows lesser hospital stay (24 hours); can be done as day care surgery in uncomplicated cases.
- Pain in postoperative period is less with faster recovery period and also early return to work. Trauma of access is less.
- It reduces/prevents the incidence of wound complications.
- It is cosmetically better and avoids unnecessary laparotomy.

Disadvantages of Laparoscopic Appendicectomy

Technical difficulties in mobilizing the appendix; clearing the adhesions; cauterizing the mesoappendix; placing ligatures around appendix; extraction of the appendix.

One should always take prior consent for conversion into open appendicectomy.

Contraindications

It is relatively contraindicated in previous lower abdominal surgery, pregnancy with appendicitis, malignancy, palpable appendicular mass, immunosuppressed individual, comorbid status.

Instruments

1. Veress needle.
2. 10 mm port- 2 in no.
3. 5 mm port -1 in no.
4. 30° camera; xenon light source; 3 chip camera; monitor; CO_2 cylinder; CO_2 insufflator;
5. Maryland dissector.
6. Babcock dissector.
7. Bipolar forceps.
8. Scissors.
9. Suction irrigation.
10. Endoloops.
11. Endo bag.

Position of the Patient and Operating Room Setting

The patient is in supine position with Trendelenburg position to start with. Once the ports are in place and surgeon is ready to proceed with actual procedure the patient's right side it tilted up so as to clear right iliac fossa of small bowel. This can be done by tilting the table or placing a sand bag under the patient.

Monitor is kept on foot end towards right. Surgeon stands on left side facing downwards. Camera surgeon will stand on right side of the surgeon or diagonally opposite side (right side) depending on the convenience. Scrub nurse will stand on right side at distal end. Additional monitor may be placed on the left side, left of the surgeon to facilitate the proper view of the video images to people standing on the right side.

Laparoscopic appendicectomy is done under general anaesthesia **(Fig. 21-97)**.

Procedure

The first trocar (10 mm or 5 mm depending on the telescope being used) is inserted via a periumbilical incision. Access to the peritoneum can be gained by either insertion of Veress needle followed by trocar or direct insertion of trocar by open Hasson's method. After insertion of the first port, the telescope is inserted and entire abdominal cavity is inspected. 10 mm 30^0 camera is always better; but zero degree is sufficient to do usual appendicectomies. After this the attention is directed towards the right iliac fossa. Adequate tilt is required to clear the small bowel from the field. The secondary ports are inserted under direct vision so as to prevent injury to underlying bowel. The positions of the working trocars vary widely from person to person and from case to case. It is better for the surgeon to place the trocars according to the findings inside the abdomen. The position of the appendix can vary widely and also the amount of adhesions depends on factors such as number of previous attacks and duration of present attack.

The first port is inserted via an 11 mm infra umbilical incision either by open or closed technique. Subsequent two 5 mm ports are placed under vision. One port is commonly in the midline between umbilicus and pubic symphysis. The other is variable. Some surgeons prefer another port at the level of the umbilicus in the right almost in the anterior axillary line while others place it in right iliac fossa. Many other surgeons also in West like the working port to be placed in left iliac fossa. The point for consideration here is that the basic triangulation which is preferred in performing laparoscopy should be maintained. Any of the above mentioned port placement is correct as long as the surgeon is comfortable and performs a safe surgery. One



Fig. 21-97: Approaches for laparoscopic appendicectomy.

should not go in with a fixed idea for the ports as very often the surgical field demands alteration in the port placement. If endoloops are used as ligatures, left sided two additional working ports suffice (10 mm and 5 mm); if intracorporeal ligatures or transfixation are used then one port on midline below the umbilicus or in left iliac fossa and other on the right iliac fossa is a need to facilitate taking needle bites and putting ligature. Working ports are inserted always under vision. Additional 4th 5 mm working port can be used in difficult appendicectomies which will facilitate retraction of bowel or holding the appendix.

The left hand Babcock's forceps is used to hold the appendix and right hand Maryland dissector is used to trace the entire length of the appendix and reach the base of the appendix. Different energy source can be used to coagulate and divide the mesoappendix. For the basic set up and also most often bipolar coagulation forceps is adequate for the process.

Bipolar forceps is applied to the free edge of the mesoappendix and curved scissors is used to divide the same. This dissection is continued up to the base of the appendix. Harmonic scalpel may ease and quickens the job.

Use knot pusher to place three ties around the base of appendix. Grasping the appendix through the loop is an easy method to do this. Preformed endoloops can also be used. Many surgeons place intracorporeal ligatures using vicryl often with transfixation. Stump should have two ligatures in situ after appendicectomy. If faecolith is present it should be milked distally towards body using Maryland forceps **(Fig. 21-98)**.

After this the base of the appendix is secured with preformed endo loop or suture passed via the knot pusher. Three ties are placed. Between proximal most ligature and 2nd ligature gap should be less than 5 mm. The appendix is divided using curved sharp scissor between 2nd and 3rd ligatures. Intestinal stapling device can be used to cut and close the stump with two rows of staples. But stapling is not very popular and not cost effective. Specimen is removed through 10 mm working port using an extraction bag or finger of no 7.5 or 8 sterile gloves or using sterile condom **(Fig. 21-99)**.

If the appendix is friable or is badly infected then specimen retrieval bag should be used to prevent infection at port site. A thorough wash is given to the area using normal saline. A good look at the pelvis should be done before finishing the procedure. Choice of leaving a drain is dictated on case to case basis. It is recommended to close all fascial defects made by 10 mm ports as lot of subsequent hernias are been reported. Difficulty arises whenever there is a phlegmon or abscess or perforation. Subserosal appendix should be identified by incising the serosa carefully. Postileal, subhepatic and situs inversus appendix should be remembered **(Fig. 21-100)**.

A rapid recovery from ileus is noted in almost all patients when compared to open appendicectomy and early commencement of oral intake is not associated with higher complications. The patient is usually discharged within 48 hrs of surgery.

After putting telescope through umbilical port, if appendix mobilization looks easier and not a very turgid appendix, then both working ports can be 5 mm. In such occasions after cutting, appendix is extracted through the umbilical 10 mm port. 5 mm telescope is attached to the camera can be used to visualize extraction procedure.

Key steps

1. Camera port at umbilicus.
2. Two working ports one in midline and one in right flank.
3. Divide the mesoappendix after cauterizing with bipolar forceps.
4. Secure the appendix with endoloop.
5. Divide and retrieve appendix. Use endobag, if needed.
6. Wash the area.
7. Keep drain if needed.

Complications

- Injury to bowel, vessels while passing the ports.
- Complications of pneumoperitoneum.
- Accidental cautery injury to bowel, vessels and other vital structures.
- Bleeding, bowel perforation, peritonitis.
- Slipping of ligature, leak, peritonitis, fistula formation.

All complications need re-evaluation with US/CT abdomen; total count; liver function tests; platelet count. Higher generation antibiotics may be needed and one should not be hesitant to use it to control/prevent distressing septicaemia. Reopening if needed should be done at the earliest. Re laparoscopy can be ideal to observe what went wrong and amount of collection in the peritoneal cavity. Laparotomy with adequate midline incision should be done. Any pus collection should be drained. Perforation should be identified, is usually located in the caecum or ileum; it is closed using interrupted silk sutures. Adhesions, bands should be released. Thorough normal saline wash is given. Resection of the ileocaecal segment may be needed occasionally. Occasionally ileo transverse colon bypass anastomosis may be considered if caecal and appendicular stump area looks unhealthy. Proper assessment of the problem and proper



Fig. 21-98: Creating the Roeder's knot.



Fig. 21-99: Suturing of base in laparoscopic appendicectomy.

decision on table should be taken to achieve an optimum recovery as 3rd reopening after 2nd will be more troublesome and often may be disastrous. So all possible options should be kept in mind to achieve complete control of the problem.

Note:

It is ideally always better to use bipolar cautery while dissecting the mesoappendix. Additional precaution should be taken while cauterizing close to the caecum adjacent to base of the appendix.

When uncomfortable, conversion to open procedure should be done without hesitation; otherwise one should call and request another laparoscopic surgeon for help.

LAPAROSCOPY ASSISTED APPENDICECTOMY

This technique combines the advantage of visualization of internal anatomy and confirmation of appendicitis and also fast completion of the procedure by open method. The inflamed appendix is brought out to the exterior via a 10 mm trocar and the procedure of appendicectomy is carried out as in open surgery. The first trocar is placed around the umbilicus **(Fig. 21-101)**.

After inspection of the abdomen the nature of the appendix is assessed. Appendix which is around 6-8 mm, turgid, freely mobile in the peritoneal cavity and having minimal non purulent fluid collection in RIF are easily and ideally removed via this approach **(Fig. 21-102)**.

In these cases it is easy to apply some amount of traction on the appendix to deliver out these through the trocar wounds. It is important to assess how much traction the appendix can take (as a friable appendix can get cut when traction is applied). Such appendix which is very turgid and friable should be removed by division inside the peritoneal cavity as already described. The appendix is delivered through the umbilical port after mobilization or is brought out through a port placed in right iliac fossa. The position of the second trocar in right iliac fossa is variable and is dictated by the position of the base of the appendix which is seen on the inside. The tip of the appendix is grasped with a Babcock forceps on a reducer and delivered out of the wound. The gas flow to the abdomen is stopped


Bipolar cautery is safer
Reducer (10 m to 5 mm port)
5 mm instrument
(bipolar cautery here)
Inserting reducer through the 10 mm
port with 5 mm instrument
Appendix
Mesoappendix
fulgurated
Base
Caecum
Endoloop distal end
with chromic catgut loop
Endoloop is passed through the reducer which is
then negotiated into the peritoneal cavity
Endoloop proximal end with
breakable proximal handle with
which loop is manipulated
Reducer with endoloop is passed
into the 10 mm working port

Figs 21-100(1)


Irrigation part
Adjusting knob
Suction part


Irrigation saline is connected to suction instrument
Normal saline wash flow
Suction irrigation instrument tip
Two endoloop chromic catgut ligatures
Appendix stump
Caecum

Figs 21-100(2)

Figs 21-100(1 and 2): Laparoscopic appendicectomy.



Fig. 21-101: Laparoscopic assisted appendicectomy.

and the pneumoperitoneum is evacuated. This step is important to facilitate the delivery of the appendix through the wound. After this the procedure is same as for open appendicectomy. The mesoappendix is ligated and divided up to the base of the appendix and then appendicectomy is carried out. The stump is inspected for bleeding and caecum is pushed back into the abdomen. Pneumoperitoneum is recreated and the appendicular stump is again inspected to make sure that there is no bleeding. The pelvis can be washed with normal saline if a collection is seen. The right paracolic gutter is also inspected for any purulent collection and wash is given to the area. Keeping a drain is not a routine practice but the operating surgeon is the best judge to assess the same. Keeping a drain through the trocar site is simple and this can be removed after 24 hours. This is reassuring for surgeons performing initial few cases of laparoscopic appendicectomy.

Key steps

1. Camera port at umbilicus.
2. Second port over the base of the appendix.
3. Grasp the tip of the appendix with Babcock.
4. Evacuate pneumoperitoneum.
5. Deliver the appendix out via the working port.
6. Proceed with a routine appendicectomy.
7. Check the abdomen after procedure.

APPENDICULAR ABSCESS

It occurs due to suppuration in an acute appendicitis or suppuration in an already formed appendicular mass. Abscess commonly *occurs in retrocaecal* region but often can occur in subcaecal, preileal lumbar or postileal regions. *Pelvic abscess is also common after an attack of acute appendicitis* **(Fig. 21-103)**.

Features

High fever, features of toxicity with a soft, tender, swelling dull to percuss swelling in right iliac fossa which lies towards right lateral and lower side with clear upper margin but indistinct lower margin**.** U/S confirms the diagnosis.


Appendix is delivered
through 10 mm
umbilical port
Ligated
mesoappendix
Caecum
Transfixation at the base of the appendix
Additional proximal ligature
Cutting the appendix
distal to 2nd ligature
Stump with two ligatures
Mesoappendix
ligated
Caecum
Umbilical port wound

Fig. 21-102: Laparoscopic assisted appendicectomy - technique.



Fig. 21-103: Appendicular abscess.

Treatment

Antibiotics are started. US or CT guided catheter drainage initially followed by interval appendicectomy in 12 weeks is quiet useful.

If patient is not responding then under general anaesthesia, incision is made in the lower lateral aspect of the swelling above the inguinal ligament. Skin, external oblique muscle is cut. Abscess cavity is opened and pus is drained *extraperitoneally*, which is sent for culture and sensitivity. Wound is closed. A drain is placed through a separate incision. Antibiotics are continued. *Interval appendicectomy is done after 3 months.*

Recent study has confirmed that immediate appendicectomy in appendicular abscess showed higher rates of complication and hospital stay compared to initial percutaneous/open drainage followed by interval appendicectomy at 12 weeks.

Chapter 22

Surgeries of Liver and Biliary System

A. LIVER

- Surgical anatomy
- Liver resection
  - Principles and indications
  - Left hepatectomy
  - Right hepatectomy
  - Extended hepatectomy
  - Segmetectomies and non-anatomical resections
- Liver transplantation
- Surgical treatment of portal hypertension
- Surgical treatment of hydatid cyst

SURGICAL ANATOMY

The liver has always been noted to have the power of regeneration even from the time of Greek mythology where Prometheus was chained to a rock and an eagle would feast on his liver and it would regenerate each night in time for the eagle's return. It is a unique organ which can regenerate as well as be replaced with transplantation. Surgery of the liver is both easy and tough at the same time.

Grossly liver can be divided into right, left, quadrate and caudate lobes. It weighs around 1500 g. It is the largest gland of the body. It extends downwards from 5th intercostal space mainly on the right side partly on the left side. It is wedge-shaped like a pyramid of 4 sides. The falciform ligament divides the liver into right and left lobe on the diaphragmatic surface and ligamentum teres divides the same on the inferior surface. The quadrate lobe is situated between the gallbladder fossa and the porta hepatis. And the caudate lobe is situated between the inferior vena cava, the porta and fissure carrying ligamentum venosus. This division, however, does not represent the functional anatomy of the liver **(Fig. 22-1)**.

Different peritoneal attachments of the liver are called as ligaments of the liver which are important in initial mobilization of the liver. Anterior and posterior reflections of the liver are called as anterior and posterior coronary ligaments. Between these two lies the 'bare area' without peritoneal coverage and is directly related to the diaphragm. On right and left side two reflections join and form right and left triangular ligaments. Anteriorly it reflects on the superior surface of the liver and abdominal wall and forms falciform ligament; in between folds of falciform ligament, embryonic left umbilical vein forms round ligament/ligamentum teres; it also forms a fissure in the liver to separate liver into apparent right and left lobes **(Fig. 22-2)**.



Figs 22-1A and B: Anatomy of liver—surface and gross.

On the visceral surface, it extends as fissure for the ligamentum venosum. Between ligamentum venosum and gallbladder lies the quadrate lobe; between it and porta hepatis posteriorly lies the caudate lobe. At porta hepatis peritoneum extends as lesser omentum extending into the stomach and duodenum as hepatogastric and hepatoduodenal ligaments. Free right margin of the lesser omentum contains common bile duct, hepatic artery and portal vein with foramen Winslow communicating lesser sac into free peritoneal cavity **(Figs 22-3 and 22-4)**.


Falciform ligament
Lung
Lung
Bare area
Oesophagus
Left triangular ligament
Right triangular ligament
IVC
Posterior layer of coronary ligament
Anterior layer of coronary ligament

Fig. 22-2: Inferior surface of the diaphragm showing bare area; IVC position; coronary ligament; right and left triangular ligaments.


Gall bladder
Quadrate lobe
Falciform ligament
Common bile duct
Hepatic artery
Portal vein
Bare area
IVC
Caudate lobe

Fig. 22-3: Visceral surface of the liver.


Falciform ligament
Lung
Lung
Left triangular ligament
Coronary ligament
IVC
Gastrophrenic ligament
Right triangular ligament
Bare area
Splenorenal ligament
Spleen
Stomach
Hepatoduodenal ligament
Gastrosplenic ligament
Gastrohepatic ligament
Greater omentum

Fig. 22-4: Peritoneal reflections and ligaments of the liver.

True left lobe contains left lateral and medial segments; each is divided into superior and inferior subsegments. Right lobe is divided into anterior and posterior segments by invisible imaginary intersegmental fissure; each again is divided into superior and inferior subsegments **(Fig. 22-5)**.


Lateral segment
Posterior segment
Anterior segment
Medial segment
Right liver
Left liver

Fig. 22-5: Right lobe of liver (right liver) contains anterior and posterior segments; left lobe (left liver) contains medial and lateral segments.

Caudate lobe is indirect contact with IVC at its left side; it is often divided into right and left parts and caudate process. Caudate lobe derives its connections from bile duct, hepatic artery and portal veins of both right and left lobes. Caudate lobe is a separate region as such. It is segment 1, and is anatomically and functionally separate from right and left livers. It is behind the liver hilum and in front of retrohepatic IVC. Caudate lobe proper is called as *spigelian lobe*. In front, it is fused to segment 4; right side to segments 6 and 7. It is not draining into the hepatic veins; but drains directly into the retrohepatic IVC at its left front aspect. It derives its portal blood supply from three branches from main, right and left portal veins. Three branches arise from right and or left hepatic arteries. Ducts from caudate lobe run in front of the portal branch vein to drain into right or left hepatic duct or both.

Left lobe may be diminished in size as anomaly. Usually right lobe is 2/3rd of total liver mass. *Riedel's lobe* is an elongated tongue of liver extending from the right lobe to or below the umbilicus. It presents as an asymptomatic right upper abdomen unexplained mass in a middle-aged lady **(Fig. 22-6)**.

Grossly liver has got diaphragmatic and visceral surfaces. Diaphragmatic surface has got anterior, superior, posterior and right parts. Anterior part is related to diaphragm, costal margins, xiphoid process, and anterior abdominal wall; its inferior margin has got a deep notch for ligamentum teres and a wider notch for gallbladder. Superior part is related to diaphragm and is separated from right pleura and lung, pericardium, left pleura and lung. Posterior part is related to diaphragm and ribs; bare area and sulcus for IVC is located


Gallbladder
Riedel's lobe of liver

Fig. 22-6: Riedel's lobe of liver. It is common in females; presents as unexplained mass.

here. Right part is related to diaphragm, right pleura and lung, 7th to 11th ribs. Visceral surface is related to hepatic flexure and transverse colon in front; hepatorenal pouch (Morrison's) right kidney and right adrenal behind; gallbladder in gallbladder fossa of liver; 1st and 2nd part of the duodenum; oesophagus and stomach.

All the surgical techniques are based on the functional anatomy of the liver. The foundation of which was laid by J Cantlie in 1898 when he described *Cantlie's line* which passes to the left of the gallbladder fossa to the left of inferior vena cava. *Claude Couinaud* then divided into 8 functional units based on separate vascular and biliary pedicle (in clockwise direction). This has laid the foundation to all anatomical resection of liver. At the hilum, the right portal vein pursues a very short course (1–1.5 cm) before entering the liver. Once entering the hepatic parenchyma, the portal vein divides into a right anterior sectoral branch that arches vertical in the frontal plane of the liver, and a posterior sectoral branch that follows a more posterolateral course. The right portal vein supplies the anterior (or anteromedial) and posterior (or posterolateral) sectors of the right lobe. The branching pattern of these sectoral portal veins subdivides the right liver into 4 segments—segments V (anterior and inferior) and VIII (anterior and superior) form the anterior sector, and segments VI (posterior and inferior) and VII (posterior and superior) form the posterior sector. In contrast to the right portal vein, the left portal vein has a long extrahepatic length (3–4 cm) coursing beneath the inferior portion of the quadrate lobe (segment 4B) enveloped in a peritoneal sheath (the hilar plate.) Upon reaching the umbilical fissure, the left portal vein runs anteriorly and superiorly within the liver substances, and gives off horizontal branches to the quadrate lobe medially (segments IV A (superior) and B (inferior)) and to the left lateral segment (segments III (inferior) and II (superior)). The caudate lobe (segment I) is neither part of the left nor right lobes, though it lies mostly on the left side. To avoid confusion and bring uniformity in nomenclature of hepatic surgeries, the International Hepato–Pancreato–Biliary Association (IHPBA) which promotes understanding of causes, investigation and treatment of liver, pancreas and biliary tree disorders in 2000, during the recent World Congress of IHPBA in Brisbane presented their recommendations (for example, right hemiliver = right hepatectomy, right anterior section = right anterior sectionectomy, segments 1–9 = segmentectomy) **(Figs 22-7 to 22-9)**.

Blood Supply

Hepatic Artery

Hepatic artery supplies around 20% of total inflow to the liver. The anatomy of hepatic vasculature is standard only in about 60% of the patients. Several anomalous vessels supply segments of liver where they are termed as replaced hepatic arteries. The hepatic artery is one of the three branches of celiac trunk arising from the aorta at L1 vertebral level. The common hepatic artery typically passes forward for a short distance in the retroperitoneum where it then emerges at the superior border of the pancreas and left side of the common hepatic duct. After arising


Right hepatic vein
IVC
Middle hepatic vein
Left hepatic vein
Right portal vein
Left portal vein
Portal vein

Fig. 22-7: Cantlie's line and Couinaud's segments in liver. Caudate lobe is segment 1.


1. Common hepatic duct
1a - Rignt hepatic duct
1b - Left hepatic duct
2. Anterior branch
3. Posterior branch
4. Medial branch
5. Lateral branch
6. Anteroinferior
7. Posteroinferior
8. Posterosuperior
9. Anterosuperior
10. Caudate branch
11. Medial superior
12. Medial inferior
13. Lateral superior
14. Lateral inferior

Fig. 22-8: Distribution of biliary tree intrahepatically and portal plate.


Anterior sectoral duct
Posterior sectoral duct
Common hepatic duct
70%–normal pattern
Anomalous anterior sectoral duct
20%–anomalous right anterior duct
Anomalous posterior sectoral duct
5%–anomalous right posterior duct

Fig. 22-9: Usual pattern and anomalies which can occur in sectorial ducts in the liver.

from the celiac axis, the common hepatic artery turns upward and runs lateral and adjacent to the common bile duct. The gastroduodenal artery that supplies the proximal duodenum and pancreas is typically the first branch of the common hepatic artery. The right gastric artery takes off shortly thereafter and continues within the lesser omentum along the lesser curve of the stomach. At this point, the common hepatic artery is referred to as the proper hepatic artery. The proper hepatic artery courses towards the hilum, and soon divides into the right and left hepatic arteries. Prior to the bifurcation, a small cystic artery branches off to provide blood supply to the gallbladder **(Fig. 22-10)**.



1. Common hepatic duct
   1a - Rignt hepatic duct
   1b - Left hepatic duct
2. Anterior branch
3. Posterior branch
4. Medial branch
5. Lateral branch
6. Anteroinferior
7. Posteroinferior
8. Posterosuperior
9. Anterosuperior
10. Caudate branch
11. Medial superior
12. Medial inferior
13. Lateral superior
14. Lateral inferior

Fig. 22-10: Arterial supply of the liver—distribution of hepatic artery.

The proper hepatic artery bifurcates earlier than the common bile duct and portal vein. In 80% of cases, the right hepatic artery courses posterior to the common hepatic duct before entering the hepatic parenchyma. In 20% of cases, the right hepatic artery may lie anterior to the common hepatic duct. Upon reaching the hepatic parenchyma, the right hepatic artery branches into right anterior (segments V and VIII), and right posterior sectoral branches (segments VI and VII). The posterior sectoral branch initially runs horizontally through the hilar transverse fissure (of Gunz), normally present at the base of segment V and adjacent to the caudate process. The left hepatic artery runs vertically towards the umbilical fissure where it gives off a small branch (often called the middle hepatic artery, also often it arises from right hepatic artery) to segment IV, before continuing on to supply segments II and III. Additional small branches of the left hepatic artery supply the caudate lobe (segment I), although caudate arterial branches may also arise from the right hepatic artery.The most common hepatic arterial anomaly involving a replaced vessel is a replaced right hepatic artery (25%). In this situation, the replaced right hepatic artery usually arises from the superior mesenteric artery and runs lateral and posterior to the portal vein within the hepatoduodenal ligament. In rare instances, the entire common hepatic artery, or its individual branches may arise directly off the celiac trunk or aorta.

Middle hepatic artery is an extrahepatic arterial branch originates at liver hilum from right hepatic artery (45%) or left hepatic artery (25%) or when there is anomaly of either of right or left hepatic arteries then it arises from normal of the two branches. It is present in 70% of individuals and supply segment 4.

Hepatic arteries are not end arteries; translobar and subcapsular collateral circulation can exist. Right gastric and gastroduodenal may maintain hepatic blood flow. Hepatic artery ligation needs cholecystectomy.

Portal Venous System

The portal vein contributes about 80% of total inflow to the liver. The portal vein is formed by a union of the superior mesenteric vein (SMV) and splenic vein behind the neck and body of the pancreas. In up to one third of all individuals, the inferior mesenteric vein may also join this confluence. Venous tributaries from the pancreas may also drain directly into the portal vein, and generally correspond to the arterial supply. More precisely, there are anterior, posterior, superior and inferior pancreatic vessels. Access to the portal vein is typically obtained by identifying the superior mesenteric vein on the inferior surface of the pancreas. In some circumstances, it is necessary to first locate the middle colic vein within the transverse mesocolon and follow it inferiorly to the SMV **(Figs 22-11 and 22-12)**.

Right portal vein lies in front of the caudate lobe entering the right liver across the hilar plate divides into right anterior and posterior branches, right anterior branch runs vertically, divides into descending branch to segment 5 and ascending branch to segment 8. Right posterior branch runs horizontally and posterolaterally to supply segment 6 and 7. Right portal vein gives a branch to right side of caudate lobe. Left portal vein runs in portal plate for 3 cm and turns towards front and left in the umbilical fissure to join the round ligament anteriorly. It supplies segment 4 from its right side and segment 2 and 3 from its left side. Anatomical variations are common especially in right portal vein. Left portal vein is commonly extraparenchymal. Portal vein and hepatic artery branches to segment 4 can be isolated in the umbilical fissure outside the liver capsule. The left portal vein is narrower and longer compared to right portal vein. It divides into medial and lateral branches, each divides into superior, inferior branches; left portal vein gives a branch to left side of caudate lobe.

Reduction in portal blood flow increases the hepatic arterial flow but reduction in hepatic arterial flow will not increase the portal flow. Portal vein ligation can cause atrophy of liver.



1. Portal vein
   1a - Right portal vein
   1b - Left portal vein branch
2. Anterior branch
3. Posterior branch
4. Medial branch
5. Lateral branch
6. Anteroinferior
7. Posteroinferior
8. Posterosuperior
9. Anterosuperior
10. Caudate branch
11. Medial superior
12. Medial inferior
13. Lateral superior
14. Lateral inferior

Fig. 22-11: Portal venous system—intrahepatic course.



Fig. 22-12: Anatomical sites of porta systemic collaterals. 1. Lower end of oesophagus; 2. Around umbilicus; 3. Around anorectum.

Hepatic Veins (Outflow)

The three major hepatic veins (right, middle and left) comprise the main outflow tract for the liver, although additional veins (5–20) of varying size are always present as direct communications between the vena cava and the posterior surface of the right lobe. Uniquely, the caudate lobe (segment I) drains principally through direct communications with the retrohepatic vena cava. The right hepatic vein lies within the *right scissura* (or right segmental fissure) and divides the right lobe into a posterior (segments VI and VII) and anterior (segments V and VIII) sector. The middle hepatic vein lies within the *main hepatic scissura* separating the right anterior sector from the quadrate lobe. The middle hepatic vein occupies the plane separating true right and left lobes and does not follow the branches of the biliary tree. The middle hepatic vein drains from segments 5 and 6 (right anterior) and segment 4 (left medial section). The left hepatic vein lies within the *left scissura* in line with or just to the right of the falciform ligament. Left hepatic vein is formed by veins from segment 2 (transverse branch) and segment 3 (sagittal branch) **(Fig. 22-13)**.

The right hepatic vein drains directly into the suprahepatic vena cava, while the middle and left hepatic veins join to form a short common trunk of 1 cm in length prior to entry. Venous branches from segment 4 drains into middle hepatic vein but can drain left hepatic vein as a variation. Segment 4 vein is often called as umbilical vein but is misnomer. The umbilical vein represents an additional alternative site of venous efflux. It is located beneath the falciform ligament and eventually terminates in the left hepatic vein, or less commonly in the confluence of the middle and left hepatic veins. Large accessory right hepatic vein can often be present which drains to the vena cava directly. The caudate lobe has independent venous outflow directly draining into IVC. All three major hepatic veins (right, middle, left) drain into suprahepatic part of IVC. Suprahepatic IVC with junction of the three major hepatic and phrenic veins joining the IVC is enclosed with thick fibrous sheath extending from diaphragm. Division of this sheath is necessary to expose the major hepatic veins. In right hepatectomy, after mobilization of the liver, this sheath has to be identified and divided before parenchymal transection. There is also a fibrous band extending from the posterior part of retrohepatic IVC at the level of junction with right hepatic vein called as *Makuuchi IVC ligament* which courses from dorsal edge of left side of the caudate lobe and right liver. Left and middle hepatic veins in left hepatectomy are usually approached after parenchymal dissection. Ligation of one hepatic vein is not necessarily to proceed with hepatic resection.



Figs 22-13A and B: Distribution of hepatic veins—outflow/venous drainage of liver.

Hepatic Plate

It is fibrous sheath continuing from the Glisson's capsule, covering hepatic artery, portal vein and bile duct. Portal pedicle contains these three structures with lymphatics. Bile duct and hepatic artery are closely bounded together. Portal vein is separated by these two by separate loose areolar fascial sheath. Hilar plate is bounded above by segment 4 and right by cystic plate and left it continuous as umbilical plate. Umbilical plate contains left hepatic duct left hepatic artery and left sided portal vein. Middle hepatic artery is also located in umbilical plate.

Anatomical speciality

- Arterial anomalies occur up to 60% of times mostly with right hepatic artery but replaced left hepatic artery in lesser omentum (from left gastric) must also be looked for.
- Each segment is supplied by portal triad and drained by hepatic vein based on which segmentectomy can be performed.
- Glisson's capsule invests within hepatic parenchyma along with separate portal triad leading to Glissonian approach to resection.
- Vascular control is fundamental to safe liver resection.

Lymphatic Drainage of Liver

Superficial lymphatics lie on the surface of the liver deep to peritoneal coverings. Deep lymphatics drain into the right middle phrenic nodes; nodes of porta hepatis; these portal hepatis nodes in the transverse fissure are closer to portal vein and hepatic artery than bile duct.

LIVER RESECTION

In 1888, Langenbuch successfully removed solid left lobe tumour. Tiffany from America in 1890 removed a left lobe mass lesion. Keen removed a cystic lesion, angioma and a primary carcinoma of liver. In 1952, Lortat –Jacob and Robert designed thoracoabdominal approach and extrahepatic ligation of vascular pedicle to control bleeding prior to parenchymal dissection. In 1953, Quattelbaum described breaking of the liver tissue by finger fracture/digitoclasia. Finger or handle of knife is used for liver transection. In 1956, Finberg and associates started parenchymal dissection using back of scalpel. In 1958, Tien Yu Lin et al. started the technique of dividing the tissue between thumb and fingers; once resistant structures are felt (either vessel or ducts), they are ligated on both sides and divided.

Indications

Benign Neoplasms

- Hemangiomas
- Adenomas
- Focal nodular hyperplasia
- Cystadenoma

Malignant Tumours

- Primary
  - Hepatocellular carcinoma
  - Cholangiocarcinoma
- Metastatic tumours from
  - Colorectal cancers
  - Noncolorectal and neuroendocrine tumours
- Tumours directly invading liver
  - Adrenal, renal, gastric, colonic, retroperitoneal and IVC sarcoma
- Gallbladder carcinoma
- Hilar cholangiocarcinoma

Benign Conditions

- Intrahepatic biliary stricture/fistulae
- Intrahepatic biliary stones
- Recurrent pyogenic cholangitis
- Caroli disease
- Liver cysts/polycystic liver disease
- Parasitic cysts

Trauma

Liver Resection in Living Donors for Transplantation (Fig. 22-14)



Fig. 22-14: CT and operative picture of cholangiocarcinoma undergoing resection (By Dr Arunkumar Mch Gastro, Kochin).

General Considerations in Liver Resection

Case selection and perioperative management of patients with liver disease is as important as performing a safe surgery of liver. With advances in critical care management and surgical advances, it is now, however, possible to subject patients to liver resection in conditions like liver cirrhosis. Pre-operative assessment of patients must include good pre-operative imaging and volumetry (in case of major resection). High resolution triphasic CT scan should be obtained to delineate the portal anatomy, biliary anatomy and hepatic venous anatomy. Detailed discussion on hepatic imaging is beyond the scope of this book and only surgical aspect of liver resection is discussed. Major liver resection can be done only in patients who fall under CTP (Child-Turcotte-Pugh)—A class. Patients who are CTP B should be assessed carefully and additional ICG clearance may be needed to decide upon surgery. A minimum clearance of 10% is required for patients undergoing major resection. Patients who are CTP C class are generally not fit for any type of liver resection. A minimum of 30% of functional liver must be left behind (FLR—future liver remnant) for adequate recovery of the patient. This value can be higher than 40% in case of cirrhotics in whom the volume of liver does not co relate with functional liver. In cirrhotic patients, pre-operative portal vein embolization (2 weeks prior) is a good strategy to induce compensatory hypertrophy of remnant liver in order to increase the FLR.

Liver resection is classified as *anatomical and non-anatomical*. Anatomical is along the functional segmental anatomy of parenchyma with defined boundaries. When resection is done without taking into consideration of the segments is called as non-anatomical. Anatomical resections are termed as sectionectomy/segmentectomy; hepatectomy/hemihepatectomy. Hepatectomies are right and left. Sectionectomies are left lateral; left medial; right anterior; right posterior. Resection of three consecutive sections is called as trisectionectomy. Extended right hemihepatectomy includes middle hepatic vein with the part of segment 4. Extended left hemihepatectomy included middle hepatic vein with part segments 5 and 8.

Resection of three or more liver segments is called as *major* hepatic resection. Middle hepatic vein is the landmark between right and left liver. It begins in gallbladder fossa and ends in IVC either after joining left hepatic vein as common trunk or independently. It receives hepatic veins from segments 5 and 8 on right side and segment 4a and 4b from left side. Major resection is done when tumour is more than 5 cm or when tumour is close to liver hilum involving the portal pedicles. Major hepatic resection is often done in selected patients with en bloc removal of part of IVC or right adrenal gland or diaphragm or right kidney or duodenum.

In right hepatectomy when remnant liver in left lobe is inadequate then preoperative right portal vein embolization is done to induce the hypertrophy of left liver which is future remnant liver.

Evaluation in Liver Resection

Multidetector CT scan is ideal imaging method in terms of assessing the resectability and CT volumetry of the remnant liver. *Urata formula* is used to estimate the liver volume. It is important in cirrhotics. If liver volume is less than 40% in cirrhotics then major resection becomes high risk. Hepatic angiogram is not necessary unless MDCT shows vascular anomalies.

Assessment of liver and kidney function (LFT/RFT) is important. *Child–Pugh grading* is done to decide the selection of the patient for resection.

Indocyanine green (ICG) clearance test is more valuable than Child's grading or prothrombin time or platelet count. But high ICG retention rate can occur if there is partial compression of portal vein or bile duct.

Screening preoperatively for other comorbid diseases is also essential.

Vascular Control

The crux of good liver surgery lies in haemostasis. Liver vascular control has two components—*inflow control and outflow control.*

Pringle Manoeuvre

The inflow to the liver can be controlled using the *Pringle manoeuvre*. As described in anatomy, the whole hepatic pedicle including the artery lies in the free border of hepatoduodenal ligament. Here it can be encircled using an umbilical tape or vascular tape by making a window in the lesser omentum. The tape is threaded over a red rubber catheter and clamped. Tightening the clamp allows to stop inflow to the liver (Pringle's Manoeuvre (PM). The PM has relatively little general haemodynamic effect and no specific anaesthetic management is required. However, bleeding can still occur from the backflow from the hepatic veins and from the liver transection plane during unclamping.The other concern is the ischaemic-reperfusion injury to the liver parenchyma, especially in patients with underlying liver diseases. The Pringle's manoeuvre can be applied either continuously or intermittently. Continuous occlusion is safely applied for up to 60 minutes in healthy liver and for up to 30 minutes in diseased liver (fatty liver/cirrhosis). In intermittent Pringle's manoeuvre, the inflow is occluded for 15 minutes followed by 5 minutes of reperfusion. There is no difference in blood loss during surgery in both the manoeuvres however, there is more ischaemic injury to the liver in patients with pre-existing liver disease.

Hemihepatic clamping (half-Pringle manoeuvre) interrupts the arterial and portal inflow selectively to the right or left liver lobe that is to be resected. It can be performed with or without prior hilar dissection. It can also be combined with simultaneous occlusion of the ipsilateral major hepatic vein. The advantage of this technique is that it avoids ischaemia in the remnant liver, avoids visceral congestion and allows clear demarcation of the resection margin. The disadvantage is that bleeding from the parenchymal cut surface can occur from the non-occluded liver lobe. Segmental vascular clamping entails the occlusion of the ipsilateral hepatic artery branch and balloon occlusion of the portal branch of a particular segment.

It is often claimed that Pringle manoeuvre prepares the liver for eventual ischaemia—ischaemic preconditioning. Now newer gadgets like ultrasonic dissector allows liver transection without Pringle manoeuvre.

Total Vascular Exclusion (TVE)

Total vascular exclusion (TVE) combines total inflow and outflow vascular occlusion of the liver, isolating it completely from the systemic circulation. It is done with complete mobilization of the liver, encircling of the suprahepatic and infrahepatic IVC, application of the Pringle manoeuvre, and then clamping the infrahepatic IVC followed by clamping of the suprahepatic IVC. Occlusion of the IVC leads to marked reduction of venous return and cardiac output, with a compensatory 80% increase in systemic vascular resistance and 50% increase in heart rate and thus, not every patient can tolerate it. TVE can be applied to a normal liver for up to 60 minutes and for 30 minutes in a diseased liver. Lumbar veins will not be present in retrohepatic IVC. Right adrenal vein needs ligation.

Retrocaval ligament bridging the segments 6 and 7 should be completely divided to expose right hepatic vein. Hepatic veins should be exposed only after proper inflow control.

Parenchymal Transection

Maximum blood loss during liver surgery occurs during parenchymal transection. The toughest structure in the liver is the Glisson's capsule. The rest of the liver does not have much connective tissue and parenchyma is packed within lattice of biliary radicles and vascular structures. Even though the segments have independent vascular supply, there is still bleeding from adjacent side when inflow occlusion is not applied. Portal veins are less fragile than hepatic veins. The advance in surgical instrumentation has definitely made parenchymal transection easy. Though the simplest of techniques is sufficient energy sources may be needed in certain cases. The choice of device, however, remains personal and also depends on availability as many of these devices are expensive to procure and maintain **(Fig. 22-15)**.

The main modality of parenchymal transection are:

1. Kelly clamp and bipolar forceps
2. Water jet dissection—contact method
3. Cavitron Ultrasonic Surgical Aspirator (CUSA)—contact method
4. Ultrasonic dissection
5. Bipolar vessel sealer
6. Staplers
7. Finger fracture—compression method
8. Electrocautery and laser—thermal method
9. Suture ligation

Before starting parenchymal dissection, stay sutures are taken on either side of line of parenchymal transection. This aids greatly in applying traction especially in the initial dissection. Capsule of the liver is marked/scored along the line of planned resection with cautery. Parenchymal transection better begun at relatively thin liver at free edge.

Kelly Clamp and Bipolar Forceps

A small clamp (Kelly) is used to crush parenchyma between its blades in order to isolate vessels and bile ducts. Fine branches of Glisson's tree or tiny tributaries of hepatic veins (<3 mm) are coagulated using a bipolar forceps and are cut by scissors. Bipolar forceps cautery is equipped with a channel for water dripping, which prevents adhesion of debris to the cautery blades. Bigger identified vessels or bile ducts (>3 mm) are ligated or clipped on the remnant liver slice before cutting.

Water Jet Dissection

A jet of water (saline) is used for dissection of liver parenchyma. The saline is delivered on parenchyma at 30–50 atmospheric pressure which washes off soft tissue leaving behind more resilient biliary radicles and vessels. The device tip also hosts a suction device which clears the field for further dissection. The biliary radicles and vessels are either cauterized or ligated depending on their size as mentioned earlier. The device is held near but not in contact with liver parenchyma and dissection is done using gentle paintbrush-like strokes.

Cavitron Ultrasonic Surgical Aspirator (CUSA)

The device delivers ultrasonic shock to the tissue in contact with the vibrating tip and the tissue is then suctioned off the field by an inbuilt suction at the tip of the device. The ultrasonic probe divides parenchymal cells (because of their high water content) by the cavitational effect with less injury to structures with a high content of fibrous tissue, e.g. bile ducts and blood vessels. These structures are taken down using clips or suture ligation in the usual way. CUSA is more precise but slow. It acts as a mechanical disrupter and suction; it is useful in hilar area dissection. Ultrasonic dissector may damage hepatic veins when power is kept very high; so power should be set between 40–60% with short range amplitude **(Fig. 22-16)**.

Ultrasonic Cutting Devices

These devices have two blades at the tip of which one moves at high frequency (55 KHz) against the other producing sealing and cutting effect due to protein denaturation. Many companies now make these devices each one similar to the other. In practice, the device works partly like the Kelly crushing technique. When the Jaws of the device are approximated, they crush the parenchyma and then the small biliary radicles and vessels are sealed. Additional ties or bipolar may be required if the parenchyma is divided in fast cutting mode.

Bipolar Vessel Sealer

Bipolar vessel sealing device is also an excellent tool for parenchymal transection. The jaws initially act as a Kelly clamp in crushing liver tissue and then the biliary and small vascular channels are coagulated. The larger (10 mm) instrument has got an inbuilt blade which can then be used to divide the sealed tissue. The smaller (5mm) jaw blade does not have an inbuilt blade, and hence, tissue is divided by sharp dissection using scissors or electrocautery.

Stapling Devices

Vascular load of stapler (same as those used in GI surgery) can also be used for liver transection. These, however, are used mainly towards the posterior part of dissection where one encounters the hepatic veins. This helps to take the hepatic veins within the liver parenchyma which reduces the risk of vascular complications when compared to extrahepatic take of the hepatic veins. The jaws are approximated and stapler is fired across the tissue after making sure the field is clear and no inadvertent tissue is caught in the stapler.

Finger Fracture

It is pinching and compressing about 1 cm of parenchyma between thumb and forefinger. It disrupts the normal liver with preserving the vascular and ductal structures. Both surgeon and assistant do finger fracture together.

Suture Ligation

Any structure more than 2 mm in liver needs suture ligation or clipping. Circumferential and adequate length exposure is essential prior ligation. Fine silk, vicryl or metal clips can be used. All small portal


240
40
-160
Junior

Figs 22-15(1)



Figs 22-15(2)

Figs 22-15(1 and 2): Cholangiocarcinoma—arterial resection (By Dr Arunkumar Mch Gastro, Kochin).



Fig. 22-16: Cavitron ultrasonic surgical aspirator (CUSA).

and hepatic branches should be ligated on either side and divided in between. Avulsion of small hepatic veins can bleed significantly. Avulsed hepatic vein opening should be identified using suction and carefully sutured using 5 zero polypropylene suture material.

Argon Beam Coagulator

Argon beam coagulator can be used to control small bleeds on the surface. It is also used to stop bleeders on the surface of middle hepatic vein through tiny holes.

Preservation of Hepatic Ducts

It is very important to preserve the hepatic duct of the remnant; for that entire biliary tree until entering the liver parenchyma should be dissected especially in liver parenchyma. Branches are isolated; but ligation is done only after major part of parenchymal transection. Parenchyma around major duct is dissected using CUSA device. Choledochotomy and cannulation may safely identify the ductal anatomy.

Incisions used for Liver Resection

Patient is in supine position with both upper limbs on the side of the table or at least right side should be on the side of the table. Warming devices should be placed on the body. Perioperative antibiotics are given. Bilateral subcostal incision with an upper midline extension; thoracoabdominal incision; extension as sternotomy are different incisions used.

Mercedes Benz incision, Makuuchi J incision and bilateral roof top bucket handle incision—are different incisions used to expose field adequately **(Fig. 22-17)**.

Upper hand or Thomson retractor is used to elevate the rib cage; additional retractors are used in abdominal cavity. All perihepatic attachments are released – both triangular ligaments and falciform ligament. Mops are placed between diaphragm and liver to displace the liver downwards **(Figs 22-18 to 22-21)**.



Roof top incision with extension upwards (Mercedes benz)

Makuuchi J — incision — can extend towards left or downwards

Roof top bucket handle incision



Fig. 22-17: Incisions used to approach liver for resection and other procedures.

Nomenclature for liver resection

Segments	*Brisbane–2000*	*Couinaud–1957*	*Goldsmith and Woodburne–1957*
V-VIII	Right hemihepatectomy	Right hepatectomy	Right hepatic lobectomy
IV-VIII	Right trisectiontectomy	Right lobectomy	Extended right hepatic lobectomy
II-IV	Left hemihepatectomy	Left hepatectomy	Left hepatic lobectomy
II, III	Left lateral sectionectomy	Left lobectomy	Left lateral segmentectomy
II, III, IV, V, VIII	Left trisegmentectomy	Extended left hepatectomy	Extended left lobectomy

Starlz nomenclature—Entire right liver with complete resection of segment 4 is right trisegmentectomy; entire left liver with complete resection of segments 5 and 8 is left trisegmentectomy.

Indications	*Contraindications*
• Primary/secondary malignancy from gallbladder or colorectum or carcinoids • Benign tumours of liver • Parasitic/non-parasitic cysts—hydatid cysts/simple liver cysts • Refractory abscess/Caroli disease/RPC • LDLT • Klatskin's tumour • Trauma to liver	• Acute hepatitis–viral/alcoholic • Severe chronic hepatitis • Poor liver reserve • Severe portal hypertension • Severe coagulopathy • Severe thrombocytopenia—platelet count less than 30,000/-



Right liver/right hemiliver
Right hepatectomy +(–) segment 1
right hemihepatectomy

Left liver/left hemiliver
Left hepatectomy +(–) segment 1
left hemihepatectomy

Right anterior sectionectomy

Right posterior sectionectomy

Left medial sectionectomy
Resection of segment 4
segmentectomy

Left lateral sectionectomy
Bisegmentectomy

Segmentectomy 8 — It can be any segment, then named accordingly

Right anterior sectorectomy
Right paramedian sectorectomy

Right posterior sectorectomy
Right lateral sectorectomy

Any two consecutive segments — bisegmentectomy
– Here bisegmentectomy 7, 8

Left medial sectorectomy
Left paramedian sectorectomy
Bisegmentectomy 3,4

Left lateral sectorectomy
Left posterior sectorectomy
Segmentectomy 2

Right trisectionectomy
Right trisegmentectomy
Extended right hepatectomy
Extended right hemihepatectomy
Removal of segments 4,5,6,7,8 + or – segment 1

Left trisectionectomy
Left trisegmentectomy
Extended Left hepatectomy
Extended Left hemihepatectomy
Removal of segments 2, 3, 4,5, 8, + or – segment 1

Fig. 22-18: Different types of hepatic resections.



Figs 22-19(1)



Figs 22-19(2)



Figs 22-19(3)

Figs 22-19(1 to 3): Segmental liver resection—for secondaries (single) in liver from carcinoma of colon.



Fig. 22-20: Major hepatic resections.

Types of hepatectomy techniques

- Preliminary vascular section (Lortat-Jacob)
- Primary parenchymal transection (Ton That Tung in 1965)
- Selective clamping
- Total vascular exclusion
- Pedicular clamping (Pringles)
- Suprahilar clamping (Glissonian approach)
- Intrahepatic portal control

Technical principles

Inflow (portal vein, hepatic artery) control; outflow (hepatic veins) control; parenchymal transection; preservation of adequate sized liver remnant with intact inflow, biliary drainage and venous outflow; mobilisation of left and right triangular ligament; ligation of branches of portal vein and hepatic artery and resection of hepatic duct branch of the side; ligation of hepatic vein at a later period; proper haemostasis and ligation of individual biliary ductules. Retrohepatic caval dissection includes—dissection of right adrenal vein, inferior hepatic veins and IVC ligament. Preservation of the bile duct to the remnant liver is also equally important.

Vascular control
↓
Parenchymal dissection
↓
Precise anatomical identification
↓
Division of biliary tree (ducts/branches) with preservation of bile drainage of remnant liver

Resection along the main portal fissure (Cantlie's line) and removal on right side is *right hemihepatectomy* and removal on left side is *left hemihepatectomy*. Resection on right of the ligamentum teres is called as *right trisegmentectomy* (older—right lobectomy); and left of the ligamentum teres is called as *left lateral segmentectomy* segment II and III (older left lobectomy). Removal of single segment is called as *unisegmentectomy. Plurisegmentectomy* is removal of two or more segments. Segments IV and V are removed in carcinoma of gallbladder. Removal of small portion of liver either within the segment or traversing segments is called as *wedge resection* of the liver.



Figs 22-21(1)



Figs 22-21(2)



Figs 22-21(3)

Figs 22-21(1 to 3): Technique of liver resection—note the usage of waterjet for parenchymal transection (By Dr Ravishankar Mch Gastro, Bengaluru).

Techniques of parenchyma dissection

- Kelly clamp and bipolar forceps
- Water jet dissection
- Ultrasonic dissection
- Ultrasound cutting
- Dissecting sealer

How much to cut

- Remnant liver—≥30% of the original liver volume with complete venous drainage is safe

Intraoperative ultrasound

- Identifying tumour
- Recognizing the anatomy
- Unexpected contralateral tumour
- Intrahepatic selective vascular control using a balloon catheter
- Guided biopsy

After completion of resection

- Check for bile leak by injecting dye through cystic duct
- Check for absolute haemostasis
- Cholangiogram to confirm contra lateral biliary patency
- Fix the left lobe through falciform ligament

Complications

Bleeding, infection, septicaemia
Subphrenic abscess formation
Bile leak, haemobilia
Liver failure
Pleural effusion, empyema

Right Hepatectomy

The patient is positioned supine with a slight (15 degree) head up tilt. The abdomen is opened using a Mercedes Benz incision or Makuuchi J shaped incision. A Thompson type table mounted retractor is used for adequate and fixed retraction. The abdominal cavity is explored for any signs of extrahepatic spread. The falciform ligament is divided between ligatures. It is then taken down from the diaphragm till its posterior extent of suprahepatic vena cava. The hepatic veins are defined in this region by dividing the peritoneal reflection under vision. Applying downward traction on the liver opens up this space so as to carry out dissection under vision. The right triangular ligament is then divided which allows us to rotate the liver towards the left to expose the posterolateral side of the right liver. The right hepatic vein can be seen entering the IVC at the apex. The right subphrenic vein enters the IVC just above the insertion of the right hepatic vein. This needs to be divided between ligatures which allow safe encircling of the right hepatic vein. If the subphrenic vein is not divided, avulsion injury to it can cause troublesome bleeding.

The main portal pedicle is now encircled with a tape (*Pringle's manoeuvre*) but without clamping the same. Clamping can be done any time during the surgery if required. Cholecystectomy is performed and the cystic duct is cannulated with an infant feeding tube and secured. The portal plate is now lowered and the right hepatic artery and common hepatic duct are identified. Right hepatic artery is found between common hepatic duct and portal vein; it is confirmed by feeling the pulsation. Right hepatic artery is dissected close to the hilum of right liver to avoid injury to hepatic arterial branch to segment 4 which often may arise from right hepatic artery. Variations can occur which should be kept in mind while dissecting it. Right branch of portal vein is situated behind these structures and is also identified and looped. Arterial supply of hepatic duct is preserved while dissecting by staying away from it. A temporary vascular occlusion of right hepatic artery confirms the vascular anatomy in the patient. Initially bulldog clamp is applied to right hepatic artery; left hepatic artery pulsation should be checked now to confirm that inadvertent clamping of proper hepatic artery has not occurred. On table, Doppler study may be helpful for this purpose. The line of demarcation will appear along the Cantlie's line on arterial occlusion.

The right liver is now rotated to the left by the assistant so as to expose the retrohepatic IVC. The right hepatic artery is then divided between ligatures; two ligatures on either side should be placed before dividing. The right portal vein is now exposed. Atraumatic retractor is gently used to retract common hepatic duct while dissecting portal vein and its divisions. Small branches towards caudate lobe from right portal veins should be divided. Right portal vein is divided between vascular clamps and the edge over sewn with 6-0 polypropylene sutures. Alternately it can be divided with vascular stapler; or two ligatures are placed with more than 1 cm gap and two transfixation sutures are placed between two ligatures and divided in between. The right hepatic duct is not divided extrahepatically (at this juncture). It is divided during parenchymal division away from the hilar plate **(Fig. 22-22)**.

The attention is now given to separate the right lobe of the liver off the IVC. The right lobe is rotated towards midline by the assistant and short veins draining from the liver to the IVC are carefully isolated and divided between fine silk ligatures. The separation is continued cranially till the right hepatic vein is identified entering the IVC. Process and paracaval portion of the caudate lobe is divided from front and right side of the IVC. Inferior hepatic vein may be present if so should be carefully divided. Right adrenal gland will be visible and may interfere with the proper dissection; careful dissection is done between liver adrenal gland to expose the IVC; in a difficult situation, right adrenal gland may be removed. Right side of IVC ligament is carefully dissected and divided between clamps and sutured as it often contains a vein which may trouble with bleeding. The right hepatic vein is divided between curved vascular clamps. The cut edge on the hepatic vein is over sewn using 4-0 prolene running sutures. A vascular stapler fire across the right hepatic vein also achieves the same result. Thinner blade should be on the liver side as gap here is less but caution should be taken not to interpose liver tissue. Either method is acceptable although stapler is a more expensive choice over suture ligation.

Right liver is rotated within the abdominal wound; should not bring out of the wound to prevent ischaemia of left liver. After devascularising the right lobe, clear line of demarcation is seen on the liver surface which is scored using electrocautery. If demarcation is not there then right anterior hepatic artery or portal vein may be present. The parenchymal dissection is now carried out under low CVP (<5 mm Hg). Dissection is done along the middle hepatic vein plane rather than towards left. Transection plane is not vertical in relation to IVC but oblique in right hepatectomy. The choice of method for liver transection depends on the surgeon preference and the available gadgets at his disposal. In fibrotic cirrhotic liver, dissection along the middle hepatic vein is difficult and troublesome. The small biliary radicles and vascular branches are secured within liver parenchyma by bipolar coagulation or fine silk sutures if more than 3 mm in diameter. After parenchymal transection careful inspection of the cut surface is done to look for any bile leaks. It is usual to place a fresh piece of gauze on the cut surface and look for any biliary stains on the same after few minutes. Such points are then suture ligated using 4-0 vicryl sutures. At this point a saline leak test can be done using the already cannulated cystic duct stump. Saline is pushed from the cystic duct and any leak from the cut surface of the liver is looked for. Dilute methylene blue injection also can be used. Right hepatic duct is now dissected from the surrounding hilar plate and is divided with scissor and sutured with vicryl. It is usual to apply a pair of vascular clamps across the right hepatic duct and divide it; but care should be taken not to clamp part of the confluence; so after clamping, dye is injected into the cystic duct cannula to delineate the left hepatic duct properly under C arm image intensifier. Once again after inspecting the cut surface of the remnant


Ligation an division of right portal vein
Ligation + transfixation on both sides
6-0 polypropylene suturing of the stump on a vascular clamp
Division using vascular stapler
IVC ligament — should be divided between clamps and ligated
Right hepatic vein
Liver rotated towards left within the abdominal cavity
Diaphragm
IVC
IVC

Cholecystecomy is done. Cystic duct is cannulated with fine tube for eventual cholangiogram to delineate biliary system

Right hepatic artery is dissected after retracting the right hepatic duct. Soft vascular clamp or bulldog clamp is applied to right hepatic artery Presence of left hepatic artery pulsation should be confirmed Doppler on table will help to identify this and anomalies and also segments — 2,3,4 hepatic arterial branch and flow

Right hepatic vein should be transected ideally with stapler or using sutures When stapler is used, thinner blade should pass between liver and right hepatic vein

Scoring is done the superior and inferior surface along the Cantlie's line — while doing parenchymal dissection in this plane, middle hepatic vein terminal branches are identified and ligated, divided

After completion of parenchymal transection right hepatic duct is clamped carefully; cholangiogram through cystic duct cannula is done to confirm that left hepatic duct is patent

Right hepatic duct is divided and sutured with vicryl

Cystic duct cholangiogram is repeated or dilute methylene blue or saline is injected to identify possible bile leak from the surface of remnant liver; if present site is ligated with fine suture

Removed right hepatectomy specimen with gallbladder

Cystic duct cannula is removed and ligated securely

Falciform ligament should be fixed to the anterior abdominal wall to avoid falling of left lobe towards right and so torsion of remnant liver

Fig. 22-22: Technique of right hepatectomy.



Right hepatic artery, right hepatic duct and right portal vein are ligated (suture) and divided
Right hepatic vein is ligated and divided
Right sided segmental branches of middle hepatic vein are divided
Middle hepatic vein with its left branches are retained with left remnant liver

Fig. 22-23: Right hepatectomy—anterior approach.



Left hepatic duct, left hepatic artery and left portal vein are ligated; Middle hepatic vein is retained towards right liver

Fig. 22-24: Left hepatectomy—anterior approach.

liver dye is injected through cystic duct across the left hepatic duct to rule out bile leak. Any significant bile leak is suture ligated using fine polypropylene or vicryl. Argon beam coagulation is used to control fine bleeders on the surface.

Cystic duct cannula is removed and stump is ligated securely. The falciform ligament is now sutured back to the underside of the diaphragm. This is an important step to make sure the remnant left liver does not rotate to the right thus causing torsion. The cut surface of liver is then covered by a single sheet of surgical. A drain is placed in the subhepatic space and the abdomen is closed.

Anterior Approach Hepatectomy (Right or Left)

It is done in large tumour of right liver where it may be adherent to diaphragm, adrenal or mobilisation becomes tougher.

Prior standard liver mobilisation is not done to begin with. First hilar dissection is done. Cholecystectomy is done by ligating cystic artery and cystic duct; cystic duct is cannulated temporarily till the end of the procedure to identify left hepatic duct and bile leaks after resection in the remnant liver. Right hepatic artery, right portal vein and right hepatic duct is ligated after proper dissection. Liver is transected from anterior surface towards the liver hilum; initially scoring on both superior and inferior surface is done. Caudate lobe may be retained or excised depending on the need. Parenchymal dissection is done with ligation of segment 8 hepatic vein on the right side of middle hepatic vein. IVC is exposed in front on its entire length. Hepatic veins of segment 6 (inferior right) and 7 (middle right) and right hepatic vein is exposed. All three veins are dissected carefully, ligated and divided from front. IVC ligament is identified, ligated and divided. Right triangular ligament and right adrenal gland is dissected from the liver.

Problem with anterior approach is bleeding during parenchymal transection **(Figs 22-23 and 22-24)**.

Belghiti et al. Liver Hanging Manoeuvre

Belghiti et al. liver hanging manoeuvre when done very carefully will have control on bleeding during parenchymal dissection. Curved forceps is passed gently between liver tissue and anterior surface of liver to allow passage of a tape between suprahepatic IVC and infrahepatic IVC. It creates compression, guides the transection of liver and safeguards the IVC to some extent. But initial passage of forceps may injure the veins on the anterior surface of the IVC causing torrential haemorrhage.

Left Hepatectomy

The abdomen is opened by either a Mercedes Benz incision or J (Makuuchi) incision and preliminary exploration is done to make sure the lesion is operable. Any evidence of peritoneal involvement precludes resection. A table mounted abdominal retractor system is essential to relieve the assistants hands from retraction in a long procedure and it gives better and sustained exposure of the operative field especially at the hiatus and the suprahepatic IVC area. The falciform ligament is ligated and divided up to the suprahepatic IVC. Care must be taken during the posterior dissection near IVC. Then the left lobe of the liver is mobilized by dividing the left triangular ligament using scissors or electrocautery. A mop placed behind the left lobe prevents inadvertent injury to the stomach or spleen. Attention is now given to taking down the hilar plate (dividing the peritoneum along the inferior surface of the liver at the hilum) which exposes the hilar structures.

The left pedicle is easy to identify and control as it runs a long and more horizontal extrahepatic course. The hepatic artery is temporarily clamped to confirm the anatomy and to look for any aberrant left hepatic artery (if present from the left gastric artery, the liver parenchyma will appear perfused despite clamping of the normal left hepatic artery) and after confirming anatomy divided between double ligature of 1-0 silk. The left hepatic vein is then identified behind the artery and isolated. Tributaries draining the caudate lobe may drain close to the bifurcation and they can be preserved or divided between fine ligatures. The left portal vein is taken down around 5 mm distal to the bifurcation to avoid any stenosis of the right portal branch. The vein can be suture ligated with 1-0 silk or divided with vascular staplers or closed with running 5-0 prolene suture **(Fig. 22-25)**.

Cholecystectomy is performed and cystic duct can be cannulated and kept for performing a leak test at the end of the parenchymal transection. The biliary duct is often taken down higher up in the liver parenchyma during dissection to avoid any damage to the right bile duct. Bile duct is extremely prone to ischaemic injury and every precaution is taken to avoid it. Hence the ducts are always taken inside liver be it right or left hepatectomy. The left hepatic vein also runs a horizontal course and joins the middle hepatic vein within the liver on most of the occasions. The vein is usually divided at the end



Fig. 22-25: CT scan picture of left lobe HCC with resected left hepatectomy specimen and sutured incision.

of parenchymal transection. Once the left hepatic artery is divided, the plane of parenchymal transection is obvious on the surface of the liver. This is a good time for requesting a low central venous pressure from your anaesthetist colleague. CVP lower than 5 mm Hg decreases blood loss during parenchymal transection. The line of transection is scored using monopolar cautery. Stay sutures are taken on either side of line of demarcation which helps in applying traction during parenchymal dissection. The liver capsule is the toughest structure during transection and it needs to be divided using electrocautery. Further parenchymal transection is carried out in one of the methods as described above. Our preferred method of transection still remains Kelly clamp method as it is economical and fast. In cirrhotic patients, however, CUSA or water jet dissection is preferred. As the parenchymal transection is towards completion, Satinsky vascular clamp is applied to include the left hepatic vein. The left hepatic vein is then closed with running sutures using 5-0 prolene. Alternately, the left hepatic vein can be divided using a vascular stapler load. Meticulous haemostasis is achieved with bipolar coagulation. In some situations, a figure of eight suture using 4-0 prolene may be required to achieve haemostasis **(Fig. 22-26)**.

The cut surface of liver is observed carefully for any biliary leaks. A fresh piece of gauze is placed over the cut surface. Any yellowish discoloration should be looked into very carefully and identified biliary radicles should be ligated. A simple saline leak test can be performed at this stage as well. Saline is injected via the cannulated cystic duct and cut surface of liver is observed for any leaks. Various methods of managing the cut surface of liver have been described such as using argon beam coagulation, use of surface cauterisation using ball cautery and use of tissue glue on cut surface but none have been proved superior to one another. We cover the raw surface with single sheet of surgicel (oxidized cellulose). A single drain is placed in the subhepatic space and brought out via a separate stab incision in the right subcostal region. Abdomen is closed routinely after haemostasis. Patient is extubated as early as possible as this decreases the overall ICU stay of the patients and helps in early recovery of the patient. The patient is shifted out of high dependency unit by post-operative day 2 when his drain output has decreased and bowel sounds return. The drain is removed by post-operative day 5 or when the drain output is less than 50 mL over 24 hours. Patients liver function test, prothrombin time and INR are monitored and fresh frozen plasma is given for correcting any abnormality. Albumin infusion is given only if the plasma albumin falls below 3g/dL **(Fig. 22-27)**.

Postoperative Complications

Biliary leaks: Incidence of bile leak and biliary duct injury is more in left hepatectomy as confluence is towards left side; and right anterior and posterior hepatic duct may join left hepatic duct.

Liver failure: It is the failure of remnant liver may be due to less volume or sepsis or ischaemia. Renal failure develops as a after effect of the liver failure or sepsis.

Intra abdominal bleeding: Usual bleeding is 500 mL to 800 mL in hepatectomies;' but torrential bleeding can occur at any stage of the surgical dissection.

Delayed gastric emptying and intolerance to oral feeding is common after liver resection.

Ascites; portal vein thrombosis; other pulmonary complications; biliary strictures; biliomas are other complications which are addressed and evaluated accordingly.



Figs 22-26(1)



Figs 22-26(2)



Figs 22-26(3)



Figs 22-26(4)

Figs 22-26(1 to 4): Klatskin tumour—underwent left hepatectomy with resection of hepatic artery and portal vein with saphenous vein grafts to both (*Source:* Dr Arunkumar Mch Gastro, Kochin).



Figs 22-27(1)



Figs 22-27(2)

Figs 22-27(1 and 2): Hilar cholangiocarcinoma—left hepatectomy (By Dr Arunkumar MCh Gastro, Kochin).

Infection and intra abdominal abscess formation: Sepsis is due to liver failure or sepsis may precipitate liver failure. Bronchopneumonia is also common other than intra-abdominal sepsis.

Postoperative Care

Post-operatively patient is kept in critical care unit for 48 hours with monitoring urine output, liver function, hydration, blood pressure, body temperature, etc. High ammonia level, metabolic acidosis, respiratory distress, hypoglycaemia are indicators of inadequate remnant liver cell function. Dopamine or noradrenaline should be used to maintain blood pressure. Meantime fluid overload is also should be avoided. Parenteral nutrition with branched chain amino acids, phosphate and medium chained triglyceride emulsions and vitamin infusion is better. Phosphate is essential for liver regeneration and energy release. Intravenous potassium phosphate or oral sodium phosphate is given. Early enteral feeding promotes liver regeneration but tolerance for food especially medium chained triglycerides which is essential in post-operative period otherwise parenteral nutrition to be continued.

Extended Hemihepatectomy

Extended Right Hepatectomy

The extended right hepatectomy or right trisectionectomy includes liver segments 4 to 8 (segment 4 with right liver). It is usually done for resection of hilar cholangiocarcinomas or resection with carcinoma of gallbladder. Any extended hemihepatectomy is carried out after confirming that the remnant liver will be able to withstand the demand. In the classical approach, the segment 4b pedicle is secured before the parenchymal transection. The right pedicles are isolated and divided as for right hepatectomy (described earlier). The right hepatic vein is also taken down after mobilising the liver from the IVC posteriorly. For isolating the segment 4 pedicle, after lowering the hilar plate dissection is carried out to the right of portal pedicle going cranially. The pedicle is identified in the liver substance, isolated and divided between ligatures. The plane of parenchymal dissection is to the right of falciform ligament and is now identified by the ischaemic line. Parenchymal dissection is done in the usual fashion. As the right hepatic vein is already divided, the middle hepatic vein is the one major vessel to be encountered. It joins the left hepatic vein most of the times within the liver substance and hence, taking it needs careful attention. Care should be taken not to damage the left hepatic vein which joins it just within the liver. The falciform ligament is now sutured back to the underside of the liver. Drain is placed in the cavity. Rest of the procedure and post-operative care is the same as in major hepatic resection.

Extended Left Hepatectomy

This involves removal of liver segments 2, 3, 4, 5 and 8 (segment 5 and 8 with left liver). The residual liver 6 and 7 segment volume must be adequate to warrant a safe resection. In this case, the right hepatic vein needs to be preserved to provide drainage to the remnant segments. Portal vein embolisation with delayed hepatectomy (about 4 weeks) should be considered prior to resection, if the remnant liver is judged too small. The left portal pedicle is identified and tackled similar to left hepatectomy. The right anterior segmental pedicle is identified as it runs a horizontal course to the right after bifurcating from the posterior sectoral duct which runs deep into the liver cranially. After ligation of the pedicle, the transection line is demarcated on the liver surface and the parenchymal dissection is carried out in the usual fashion. The location of the right hepatic vein should be known at all the times and dissection should be to the left of the vein. At the end of parenchymal transection, the middle and the left hepatic vein are divided using a vascular stapler or suture ligated with continuous 4-0 prolene suture. Attention should be given to identify and points of biliary leaks from the cut surface of the liver. The abdominal cavity is drained and the post-operative monitoring done in routine fashion.

Right Anterior Sectionectomy

This is the resection of segments V and VIII which is supplied by anterior segment of the right portal pedicle. After performing cholecystectomy, the right main portal pedicle is identified and isolated. The anterior segmental pedicle is identified as going to the right and horizontally compared to the posterior pedicle which enters liver parenchyma cranially and posteriorly. The pedicle is isolated and clamped to produce the line of ischaemia which is seen on the liver surface. The parenchymal dissection is started and the anterior pedicle is ligated. The branches draining to the right hepatic vein are ligated intraparenchymally and at the end of parenchymal transection, the middle and the right hepatic vein are seen exposed in the field.

Left Lateral Sectionectomy

This procedure includes the removal of segments II and III of the left lobe of liver. These segments are situated to the left of the falciform ligament. The procedure is started with the mobilisation of the left liver by releasing the left triangular ligament and dividing the falciparum ligament. By pulling up the left liver via the round ligament, hepatic parenchymal transection is done along the left edge of the falciform ligament. The portal pedicle of the segment 3 is situated within 2 cms of liver transection and it is taken down intraparenchymally. The segment 2 pedicle is reached during more cranial dissection and it is usually thicker than the segment 3 pedicle. After dividing it, the left hepatic vein is reached. It is divided by using a vascular stapler or with help of a Satinsky clamp and cut edge is over sewn using 4-0 prolene.

Non-anatomical Wedge Resection

This is usually indicated in patients who have peripherally situated tumours which are easy to access on the surface. In patients who are not candidates for anatomical resections and in cirrhotic patients as well, these wedge resections are helpful. A resection margin of 1 cm is adequate in such situations. The line of resection is marked around the tumour and the depth is confirmed by an on table ultrasound. Parenchymal transection is begun without any vascular clamping whenever the lesion is large or significant bleeding is anticipated, the portal inflow can be taped (not clamped) and prepared should any inflow occlusion be needed. The biliary radicles and vessels are secured and divided as and when they cross the operative field **(Fig. 22-28)**.

Laparoscopic Liver Resection

There are three types of laparoscopic liver resections – pure laparoscopic (75%); hand-assisted laparoscopic resections; hybrid method.

Usually done procedures are—segmentectomy, left lateral sectionectomy, right and left hepatectomies, metastasectomy in colorectal malignancies.

It should have similar ***indications***, technical principles are same as of open procedure. Safety and outcome should be considered. Patient selection, size of tumour (<5 cm), location (in segments 2, 4, 5, 6), number of lesions, status of the liver, condition of patient, facilities available and skilled expertise are important.

Contraindications: Central tumours; right posterior lobe tumours; tumours at hilum/close to major vessels; not fit for laparoscopic procedures.

Technique: Right side of the patient is elevated with surgeon standing on the left side and first assistant on the right side. Surgeon can also stand between legs of the patient.



Fig. 22-28: Non-anatomical resection for secondaries in liver; primary is in colon.

A 12 mm port is introduced just above the umbilicus by open method. After laparoscopic exploration, additional 12 mm ports are placed in the right subcostal region. Laparoscopic ultrasound is essential. 5 mm ports are not used usually; but it is individual surgeon's choice. Parenchymal transection is done using ligaseal, harmonic or ultrasonic dissector or endovascular stapler. Cholecystectomy is done with fundus first method to reach Calot's. Blood vessels and bile duct branches are managed with endoclips or endostaplers. Raised pneumoperitoneum controls the oozing from the parenchymal surface. Portal inflow occlusion is usually not necessary. Hepatic veins are divided with cutting endovascular stapler. Intraoperative cholangiogram is done to identify biliary leak. Liver surface of the remnant liver may be covered with fibrin glue. Specimen is removed using a retrieval bag which is removed through a lengthened port incision. Drain is placed through the laparoscopic port. All other technical steps and principles are same as open procedure but through laparoscopy. Here tissue feel is not present; only magnified vision is present.

Conversion when needed—undue bleeding; difficulty in proceeding with dissection should be done without hesitation.

Complications are—pulmonary embolism; bleeding; biliary injuries; respiratory infections; bowel, diaphragm, pericardium, pleural injuries; air embolism and CO_2 embolism can occur. Air embolism is more risky.

Post-operative care—ICU management; electrolyte management; sepsis control; monitoring liver and renal functions; nutrition support; analgesia, prevention of DVT; daily biochemical assessment; when needed imaging evaluation.

LIVER TRANSPLANTATION

Introduction

Liver transplantation is the choice for end stage liver disease. Liver transplant is an accepted and effective treatment. Many tumours can be treated by transplantation. Cirrhosis, hepatitis, sclerosing cholangitis, biliary atresia, tumours are indications. In Budd-Chiari syndrome, if portacaval shunt has failed with progressive liver damage liver transplantation is indicated.

CTP (Child-Turcotte-Pugh) scoring system (ascites, encephalopathy, bilirubin, albumin, PT- INR), model for end stage liver disease (MELD score) consists of total bilirubin, INR, creatinine, paediatric end stage liver disease scoring (PELD) are different scorings used to assess the patients.

MELD Score $= 0.957 \times \text{Log}_e(\text{creatinine mg/dL}) + 0.378 \times \text{Log}_e(\text{bilirubin mg/dL}) + 1.120 \times \text{Log}_e(\text{INR}) + 0.643$

Transplantation of the liver is among the most technically demanding surgical procedures. TE Starzl performed the first human liver transplantation in 1963. Since then continuous improvements in surgical techniques, immunosuppressant's, prolongation of ischaemic tolerance and experience with indications/timing, liver transplantation has become a standard modality of treatment for chronic and acute end stage liver disease. The majority of liver transplantation is performed orthotopically. The shortage of organs has led to development of reduced size, split liver and living related (donor) liver transplantation techniques. Given the overall broad nature of the topic, the focus will be on deceased donor liver transplantation procedure along with a brief description of other techniques. For further reading, readers should refer to references at the end of the chapter.

Contraindications for Liver Transplantation

Active sepsis, SBP and HIV; extrahepatic malignancy; large hepatocellular carcinoma and cholangiocarcinoma; unfit for surgery—Severely advanced cardiopulmonary disease, active alcohol or substance abuse, inability to comply with immunosuppression protocols because of psychosocial situations—are the contraindications.

Donor Criteria

They are related to donor liver function, hepatitis screening, history of consumption of alcohol and toxic substances. Marginal donor and expanded donor criteria are in use in places due to very high demand for donor for transplantation. ABO compatibility is important. HLA matching is not necessary unlike in renal transplantation.

Deceased donor liver transplantation donor (DDLT)	*Living donor liver transplantation donor (LDLT)*
• 50 years or younger • No hepatobiliary disease • Haemodynamic and respiratory stability (systolic blood pressure >100 mm Hg, and central venous pressure >5 cm/H_2O); an acceptable PaO_2 and haemoglobin level • No severe abdominal trauma, systemic infection, or cancer • Normal kidneys—diuresis greater than 50 mL/h and normal creatinine; and finally, a dopamine requirement less than 10 µg/kg/min • Simple technically • Recipient complication is low (of bile duct) • Graft quality is average • Donor's complication—nil	• Young • Non-obese, tall • No infection and malignancy • No fatty liver • Enough liver to donate • Enough residual liver • Suitable anatomy • Technically complex procedure • Recipient complication is higher • Graft quality is good • Donor's complication—25% morbidity; 0.4% mortality

Back—Table Preparation of Liver Graft—Donor Operation

It is by a midline incision from suprasternal notch to pubic symphysis. Initially, dissection is done with a beating heart; but later with a cold preservation into aorta and portal vein and local ice application. UW solution extends cold ischaemic time for 24 hours but usually within 10 hours transplantation is done. IVC segment is removed with hepatic veins. Portal vein is transected. Celiac artery with branches along through hepatic artery is dissected and transected at celiac artery origin. Bile duct is transected.

Note: Remnant liver—≥30% of the original liver volume with complete venous drainage is safe for donor survival.

The donor liver is prepared on the back table for implantation. Bench preparation includes resection of the donor diaphragm and adrenal gland off of the bare area of the liver and vena cava. Meticulous ligation of tributaries from the vena cava (adrenal vein, phrenic vein, and lumbar branches) is performed. The artery is dissected free from the Carrel patch of the aorta up to the gastroduodenal artery. Dissection near the right or left hepatic arteries is avoided to prevent unnecessary injury. The portal vein is circumferentially dissected free.

The gallbladder may be removed at this stage or following reperfusion. Tissues surrounding the common bile duct are left intact to avoid injury of the blood supply.

Recipient Operation

Bowel preparation, prophylactic antibiotics, administrative immunosuppressive agents are needed before surgery. Bilateral subcostal incision is used with midline upward extension. Falciform ligament, left lateral ligaments, hepatogastric and hepatoduodenal ligaments are divided. Right and left branches of hepatic arteries are ligated. CBD and cystic ducts are divided with ligatures. Portal vein is dissected. Infra and suprahepatic vena cava are exposed. Portal vein and suprahepatic vena cava are clamped. Venovenous bypass between portal and femoral veins and internal jugular vein is created with a flow of blood through it more than 2.5 mL/minute. Warming circuits and ultrafiltration is needed. Suprahepatic vena caval cuff is created at the opening of the right, middle and left hepatic veins. Donor IVC is sutured to recipient IVC first above and then below as end to end. Recipient IVC can be preserved entirely and donor IVC is sutured to recipient IVC as end to side. Preservation solution is passed. Portal vein is sutured. Reperfusion injury can occur at this stage with hyperkalaemia and acidosis. Arterial reconstruction is done between donor celiac artery to recipient gastroduodenal artery. Bile ducts are sutured as end to end with or without T tube. Often choledochojejunostomy is also done.

Graft should be:
- 40% of the estimated standard liver volume.
- 0.8% to 1% of the body weight of the recipient is necessary for the recipient recovery.

Details of the Technique

The recipient's abdomen and bilateral groins are prepped and draped in a standard fashion. The most commonly used incisions are bilateral subcostal incision with a midline extension to the xiphoid process and reverse 'L'. The ligamentum teres is carefully divided between clamps and ligated because a large recannulised umbilical vein is often present in patients with severe portal hypertension. After dividing the falciform ligament with cautery, a mechanical retractor (Thompson) is used to retract the bilateral costal margins anteriorly and superiorly for excellent exposure of the upper abdomen. The abdominal cavity and liver are then inspected for any abnormalities including unsuspected malignancy. Following this, liver transplantation occurs in three stages:

a. Recipient hepatectomy
b. Anhepatic phase and implantation of donor liver
c. Post-revascularisation phase.

Recipient Hepatectomy

The liver is mobilised from its ligamentous attachments and the portahepatis is skeletonised. The peritoneum overlying the portal triad is divided with electrocautery near the liver edge. The right and left hepatic arteries are dissected free, ligated, and divided, leaving adequate length to form a branch patch for the arterial anastomosis. The proper hepatic artery is also dissected free to the level of the gastroduodenal artery allowing enough length for clamping during the anastomosis. A replaced or accessory right hepatic artery, which arises as a branch off the superior mesenteric artery travels in a posterior position to the common bile duct and lateral to the portal vein, can usually be palpated if present and can be ligated and divided. When the replaced right hepatic artery is relatively large and the proper hepatic artery is diminutive in size, the replaced right hepatic artery can be left long and used for arterial inflow for the donor liver.

The common bile duct and common hepatic duct should be dissected free with as much length as possible and without injuring the blood supply to the bile duct. Leaving the recipient bile duct as long as possible allows the length of the donor bile duct, which may have a tenuous blood supply, to be shorter and still avoids tension at the time of anastomosis. This is accomplished by first ligating and dividing the cystic duct. The common bile duct and common hepatic duct are then circumferentially dissected free, leaving the surrounding tissue to preserve the bile duct blood supply. The common hepatic duct is then ligated as close to the native liver as possible.

Once the bile duct and the hepatic artery are freed from surrounding tissues, the portal vein can be easily approached from its anterior, medial, and lateral aspects. In general, the portal vein is freed circumferentially from the edge of the duodenum up to its bifurcation of the right and left portal veins. Small branches may arise near the pancreas and excessive bleeding may arise if these are inadvertently injured. In situations where there is small bowel oedema, the portal vein should be left in continuity for as long as possible, particularly when the use of venovenous bypass is not intended.

The ligamentous attachments of the liver are then divided using electrocautery. Care must be taken to avoid injury to the phrenic or hepatic veins when freeing the suprahepatic inferior vena cava where it traverses the diaphragm. The liver is then dissected off of the anterior aspect of the inferior vena cava. Small venous branches from the inferior vena cava to the caudate lobe are ligated and divided. Division of the portal vein facilitates exposure for this dissection but is not required. The liver may be gradually retracted and dissected from either the right or left aspects until the right, middle, and left hepatic veins are reached. If a venacaval resection technique will be used, the vena cava can be circumferentially mobilised near the diaphragm above the hepatic veins as well as in an infrahepatic position. However, if a piggyback or cavocavostomy (side-to-side caval anastomosis) technique is intended, the dissection of the posterior aspect of the vena cava should be avoided to prevent bleeding from collaterals or lumbar vessels.

Anhepatic Phase and Implantation of the Donor Liver

At this point, the liver has been completely mobilised except for its attachments of the hepatic veins to the inferior vena cava and, in some cases, the portal vein. The decision should now be made whether to use venovenous bypass. Most patients will tolerate clamping of both the portal vein and the inferior vena cava without difficulty. At this point, communication with the anaesthesiologist is essential and the vena cava should be test clamped before division to make sure that adequate cardiac filling and blood pressure can be maintained. If the patient becomes hypotensive during test clamping, the clamp should be removed and additional volume or pressor support can be administered. Occasionally, patients will require venovenous bypass, but its use is no longer routine at most centres.

If necessary, venovenous bypass can be accomplished from both the portal vein and inferior vena cava simultaneously, or a single cannula in either the portal vein or the inferior vena cava may be used.

Inferior vena caval and mesenteric blood is delivered to the superior vena cava by a centrifugal pump. Flow rates of 1 to 2 L/min are usual.

Once venovenous bypass has been established or the decision to forego bypass has been made, the recipient hepatectomy is completed. If still intact, the portal vein is divided as high in the hilum as possible. Three methods are commonly used for orthotopic liver transplantation: (1) the segmental IVC resection (bicaval) technique, (2) the piggyback technique, and (3) cavocavostomy (side-to-side caval anastamosis) technique.

1. For the segmental IVC resection technique, the recipient liver is excised en bloc with the retrohepatic inferior vena cava after caval clamps have been placed in a suprahepatic and infrahepatic position. The hepatic veins are divided within the substance of the liver to allow the creation of a large suprahepatic cuff compromising the left, middle, and right hepatic veins. This technique has the disadvantages of (a) totally obstructing inferior vena cava flow, resulting in renal ischaemia and decreased cardiac filling with associated hypotension, possibly leading to the requirement of venovenous bypass; (b) requiring two vena caval anastomoses, prolonging the warm ischaemic time; and (c) requiring dissection posterior to the vena cava, possibly leading to bleeding. However, complete dissection of the caudate lobe off of the vena cava is not necessary, making the recipient hepatectomy phase somewhat easier and faster.
2. For the piggyback technique, a clamp is placed transversely, partially occluding the vena cava at the level of the hepatic veins. The vena cava is left in continuity and the hepatic veins are divided within the substance of the liver, allowing the creation of a common patch of the right, middle, and left hepatic veins for a wide anastomosis. This technique does have the advantage of only requiring a single vena caval anastomosis, helping to limit warm ischaemic time.
3. For the cavocavostomy technique, clamps can be placed on the right hepatic vein as well as the junction of the left and middle hepatic veins. The liver is excised and these venous branches are oversewn and the clamps are removed. Alternatively, the hepatic veins can be divided using an Endo GIA stapler. Advantages of the cavocavostomy anastomosis include (a) minimalisation of the time that the vena cava is clamped; (b) the vena caval clamp is placed longitudinally, only occluding the anterior third of the vena cava, leading to minimal or no changes in the recipient's hemodynamics; (c) a cavoplasty with long anastomosis over 6 cm is performed, limiting the likelihood of caval stenosis and minimising the risk for hepatic vein outflow complications; and (e) exposure during suturing of the anastomosis is considerably improved compared to the piggyback or bicaval technique.

After removal of the recipient liver, the right upper quadrant is carefully inspected and haemostasis is obtained. Complete haemostasis in the bare area is essential at this time because this region is easily visualised when the liver is absent but may be relatively inaccessible once the donor liver is implanted, especially if the donor liver is relatively large or the recipient is obese.

The donor liver is then brought onto the operative field. The vascular anastomoses are performed using a running monofilament polypropylene suture. If an IVC resection technique is planned, two caval anastomoses are required. For the piggyback technique, the donor infrahepatic vena cava is either oversewn or stapled and donor suprahepatic vena cava is then sewn in to the recipient hepatic vein cuff. For the side-to-side caval technique, a clamp is placed longitudinally on the anterior third of the recipient vena cava. A longitudinal venotomy is made on the anterior surface of the recipient vena cava. The donor suprahepatic and infrahepatic vena cava are either oversewn or stapled closed. A longitudinal posterior venotomy is then made matching the length of the recipient venotomy. The liver is then placed in the right upper quadrant and the left lateral segment is elevated. The two vena cava are then sutured in a side-to-side fashion.

During the caval anastomosis, the donor liver may be perfused with cold fluid via a cannula placed within the donor portal vein to wash out the preservation solution and helps to maintain the cold temperature of the liver. This step is not required but may be considered if the liver was preserved with a solution containing a high concentration of potassium or if a prolonged warm ischaemic time is anticipated.

Once the caval anastomosis or anastomoses are completed, the portal anastomosis, arterial anastomosis, or both can be performed prior to reperfusion. In theory, reperfusion with arterial blood would limit the extent of warm ischaemia to the biliary tree, which, unlike the remainder of the liver, receives its blood supply exclusively from the arterial blood and not along with portal venous blood. However, neither sequence has been clearly shown to be an advantage over the other, so the choice is made based on the surgeon's preference and the patient's anatomy. Most commonly, the portal venous anastomosis is completed and the liver is reperfused. The portal anastomosis is usually performed in an end-to-end fashion using a running technique. To avoid narrowing, an air knot (growth factor) is used when the suture is tied. For those patients with portal vein thrombosis, portal venous flow can be restored in most cases. Often, the thrombus can be evacuated with the use of forceps or by placing a Yankauer suction tip within the lumen of the portal vein. If the thrombus is more mature, an eversion endovenectomy may be necessary. If these manoeuvres are unsuccessful, the junction of the splenic vein and superior mesenteric vein may be patent. Dissection of the portal vein behind the pancreas to this junction can then be performed to allow for future anastomosis. In rare cases, all of these manoeuvres may be unsuccessful and a venous bypass graft using donor iliac vein from the superior mesenteric vein may be necessary. If the superior mesenteric vein is also occluded, either inferior vena cava (cavoportal hemitransposition) or left renal vein can be used for portal inflow.

At the time of revascularisation, flow is restored to the liver through the portal vein and/or the hepatic artery. Alternatively, the caval clamp can be "flashed" and the anastomosis inspected for bleeding and repaired if present. Portal blood should be restored gradually to minimise cardiac irritability, bradycardia, and hypotension. Close coordination between the surgeon and anaesthesiologist is necessary during this phase as hypotension and bradycardia are routinely encountered and cardiac arrest may rarely occur. If venovenous bypass has been used during the anhepatic phase, it can now be discontinued.

Once haemostasis is obtained and the patient has stabilised, attention can now be turned toward the arterial anastomosis if it has not already been performed. Hepatic artery (HA) anstamoses can be performed in variety of different ways due to variations in recipient and donor vascular anatomy, the need to optimise arterial inflow and surgeon's preference. At the end of HA reconstruction, one needs to avoid excessive looping, redundancy or twisting, especially so after release of retractors. For a donor HA with a standard anatomy either celiac axis with or without aortic carrel patch or shortened celiac artery near splenic artery origin with subsequent joining of celiac and splenic arterial orifice to form a patch, can be used. On recipient side, a patch created between the orifice of right and left hepatic arteries or between that of common hepatic and gastroduodenal arteries is used. Anastomosis is usually performed using a fine, non-absorbable, monofilament, running suture. Variations in donor arterial anatomy require back-table reconstruction. If the recipient arterial inflow is inadequate, an aortic conduit may be constructed. This is often performed using a graft consisting of the donor common and external (or internal) iliac artery. A partially occluding aortic clamp can either be placed in a supraceliac or infrarenal position and the common iliac artery is sutured in an end-to-side fashion to the recipient aorta. The donor Carrel patch can then be sutured in an end-to-end fashion to the external iliac artery of the conduit.

Post-revascularisation Phase

Following revascularisation, the liver should assume a normal colour and consistency within several minutes. Bile production should be seen while in the operating room and is among the first evidence for liver function. Inspection for surgical bleeding should be performed. If bleeding continues after all surgical bleeding has been resolved, attention should be directed toward correction of coagulopathy as described earlier.

Because of the relatively high complication rate associated with biliary reconstruction, it has been referred to as the "Achilles heel" of liver transplantation. There are several options for biliary reconstruction. The simplest and most common technique is currently an end-to-end choledochocholedochostomy from the donor to the recipient bile duct. If a size discrepancy exists, the narrower duct can be spatulated. Absorbable monofilament suture is most commonly used to avoid a nidus for future stone formation within the bile duct. While T-tubes were commonly used in the past to stent the anastomosis, evidence now suggests that more leaks or strictures develop as a result of the T-tube than are prevented. Alternative biliary reconstruction methods may be necessary for those with a bile duct of inadequate quality or size or in those whose primary disease is biliary pathology such as primary sclerosing cholangitis or biliary atresia. The most common option employed in these situations includes a standard Roux-en-Y choledochojejunostomy. Placement of drains is optional. Abdominal wall and skin closure is then performed in the standard fashion.

Reduced Size and Split Liver Transplantation

In the 1980s, the waiting list mortality for small, paediatric liver candidates was relatively high because the number of suitably sized small liver donors was inadequate. As a result, techniques to reduce the size of an adult liver, based on Couinaud's segmental anatomy were developed so that the left lobe, left lateral segment could be used for a recipient smaller by weight than the donor. During the early experience, the donor hepatectomy was performed in a standard fashion and the liver was brought back to the recipient hospital. The needed segments of the liver were cut down on the back table with the organ on ice, the vessels were left intact to the future transplant graft, and the remainder of the liver was discarded. Techniques have now developed so that both sides of the liver can be transplanted into two recipients, either a child and an adult or two adults. In addition, the liver may be split in situ at the donor hospital, allowing coagulation of the cut edge of the liver so that bleeding is minimised following reperfusion. Perfusion to both sides of the liver can be inspected prior to flushing, ensuring that blood flow to all segments of each future graft has been preserved. Split liver transplantation has been associated with a decreased survival rate and the potential for increased risk of complications, including primary non-function, hepatic artery thrombosis, and biliary complications. Because of this split, liver transplantation only accounts for a small proportion of transplants performed. In addition, only grafts from "ideal donors" are thought to be suitable for this form of transplantation. Current criteria for splitting include that the donor should be less than 40 years of age, to be on a single pressor or no pressors, have transaminases no greater than three times normal, and have a body mass index of 28 or less.

Segmental/Lobar/Split/Living Donor Liver Transplantation

Experience with deceased donor split liver transplantation as well as the success with living donor kidney transplantation led to the adoption of the techniques for split liver transplantation to living donor liver transplantation. The first living donor liver transplantation allowed an adult volunteer to donate the left lateral segment of the liver to a child. Based on the success of living donation in the paediatric population as well as the increased waiting list mortality rate for adults, these techniques have also been applied to adult recipients receiving either the right or left lobe from an adult volunteer. Living donor liver transplantation now accounts for approximately 5% of all liver transplants performed in the United States. In south East Asian countries including India, where deceased donor transplantation has developed more slowly because of cultural difficulties living donor transplant is the rule rather than the exception.

It is newer beginning but becoming preferred one. It is based on segmental anatomy and liver regeneration capacity. Minimum liver mass required is more than 1% of graft to body weight ratio. Right lobe is better. It is basically used in children; but useful in adults also. MELD score in donor should be less than 20 for living donor transplantation. Regeneration occurs very significantly in recipients in first 2 weeks reaching standard in 1 month. Regeneration is slow in living donor liver in 1 year. Graft to standard liver ratio should be more than 40%. Function of liver in living donor should be optimum. Proper imaging of the donor for entire anatomy including vasculature is important. Individual branches of portal vein, hepatic artery and bile duct are dissected and isolated. Liver is carefully separated from IVC; small branches of hepatic vein are ligated. Main hepatic vein is isolated; liver parenchyma is dissected with finger/Kelly fracture technique. After completion of parenchymal division, vessels are transected; dissected liver is perfused with cold preservation. Diseased liver of the recipient is removed completely. Graft is anastomosed in usual manner hepatic vein, portal vein, hepatic artery, bile duct. Living donor transplantation has got higher chances of morbidity, complications compared to cadaveric transplantation.

In many respects, transplantation of a graft from a living donor is similar to transplantation of a whole liver from a deceased donor. However, an IVC segmental resection technique is not possible given that the donor vena cava is not available for replacement of the recipient's retrohepatic inferior vena cava. Therefore, the recipient vena cava must be left intact. A direct hepatic vein to vena caval anastomosis is used. Establishing adequate outflow of hepatic venous blood is necessary to prevent oedema of inadequately drained segments of the liver possibly leading to small-for-size syndrome. Therefore, any accessory veins greater than 5 mm in diameter should be reconstructed either by direct anastomosis to the vena cava or by using an interposition graft. In addition, the lengths of the portal vein, hepatic artery, and bile duct on the donor graft are considerably shorter than those available from a deceased donor. Therefore, during the recipient hepatectomy, considerable care should be given to preserving the length of the recipient bile duct as well as the right and/or left hepatic artery and portal vein that are intended for future anastomosis.

Auxiliary/Heterotopic/Ectopic Liver Transplantation

Under selected circumstances, there is a good rationale for placing the donor allograft in heterotopic rather than orthotopic position, leaving the native liver in place. This procedure is known as auxiliary liver transplantation. Auxiliary liver transplantation has occasionally been used for cases in which liver transplantation is indicated for enzymatic deficiency but the native liver is otherwise normal in all other respects. It has also been used in cases of fulminant hepatic failure where the liver candidate is expected to die in the near future without transplant but if adequate time was allowed, the native liver may recover and return to normal. In this situation, immunosuppression can slowly be weaned, the transplanted liver will atrophy, and the recipient can be taken off of all immunosuppression. Another option, auxiliary partial orthotopic liver transplantation (APOLT), has been developed. For this technique, part of the native liver is resected, often the right trisegment, leaving only the left lateral segment intact. The donor liver is then transplanted in an orthotopic position. If the native left lateral segment recovers, immunosuppression can be weaned, leading to hypertrophy of the left lateral segment and involution of the allograft.

Post-operative Management

Antirejection drugs are given. Liver shows low immunogenicity and high regeneration capacity causing long-term outcome. Initially cyclosporine or tacrolimus with MMF or azathioprine with prednisolone is given. ICU care is needed.

Electrolyte and fluid management, sepsis management, prevention of encephalopathy, observation for complications are important.

Complications and Problems of Liver Transplantation

- Bleeding on table and post-operatively can occur especially when recipient liver is cirrhotic. FFP, platelet and blood are needed. Re-exploration is needed if bleeding persists post-operatively.
- Hepatic artery thrombosis is the common vascular complication leading into graft failure, CBD necrosis and anastomotic dehiscence.
- Immediate graft failure as primary non-functional graft can occur (5% liver grafts).
- Bile leak due to CBD ischaemia which can be identified by HIDA scan, ERCP, revision anastomosis is needed.
- Infection is common especially enterococci, staphylococci, Gram negative organisms, *Candida*, *Aspergillus,* etc. Antibiotic and antifungal therapy is needed.
- Acute rejection (30%) of T cell-mediated is seen within 10 days commonly but can occur up to 6 months. Liver biopsy confirms the rejection. Higher steroid therapy, polyclonal anti T cell antibodies are used.
- Chronic rejection is seen after 6 months; appears gradually with liver cell dysfunction and hyperbilirubinaemia. Liver biopsy shows less numbered biliary radicles—vanishing bile duct syndrome. It is due to humoral immunity. It is difficult to control; eventually needs retransplantation.
- Recurrent of the earlier disease to the transplanted liver like hepatitis, biliary sclerosis, sclerosing cholangitis. Hepatitis can be controlled by lamivudine (antiviral DNA polymerase for HBV), interferon α, ribavirin for HCV.
- Complications of immunosuppressive drugs like hypertension, hyperglycaemia, hyperlipidaemia, osteoporosis, malignancy, infection, bone marrow suppression, are often difficult to manage.

Survival

5 year survival is 70% in adults and 80% in children. It depends on age, general condition, earlier disease, associated problems, MELD scoring. The risk of rejection is highest (40%) during the first 3-6 months after transplantation and decreases significantly thereafter.

SURGICAL TREATMENT FOR PORTAL HYPERTENSION

Liver Transplant (Orthotopic)

Liver transplant is becoming popular for cirrhosis with varices. It is ideal, final and best. But donor availability and cost is the problem. If patient is for orthotopic liver transplantation (OLT), open shunt surgeries should not be done as liver hilum should be kept virgin for effective transplantation. TIPSS can be done as a bridge in such patients.

Shunt Surgery

Prophylactic shunt surgery should not be done. Shunt surgeries should not be done if the varices have not bled before.

Indications

Child's Grades A and B status with portal hypertension which has bled earlier at least once. Budd-Chiari syndrome with ascites is an indication. Familial heterozygous hypercholesterolaemia and glycogen storage disorders in olden days were indications for portacaval shunting. (Child's grading is used for selecting patients for surgery and predicting prognosis).

Surgery is contraindicated in Child C.

Non-selective Shunt Surgeries

Porta-caval shunt (end-side, side-to-side); Mesentericocaval shunt with or without graft; Mesenterico-renal shunt.

Proximal splenorenal shunt—Linton's shunt.

Non-selective shunts control and prevent further bleeding as well as reduce the ascites. But since it diverts the blood from liver, *there is high incidence of encephalopathy.*

Note: End-to-side porta caval shunt is called as ECK fistula (Eck, 1877).

Non-selective shunt surgeries are done in supine position with right side slightly elevated. Right subcostal incision extending on to left side is commonly used. Thoracoabdominal incision is used in patient with significant hepatomegaly or in obese patients. Liver is retracted upwards; duodenum is mobilized by Kocherisation; hepatoduodenal ligament is dissected.

Common bile duct is dissected and isolated. Kocherisation should be done. Posterior part of the portal vein is dissected first as front aspect is having mainly collateral which may cause torrential haemorrhage (it is often found that collaterals are so tortuous and friable and creates difficulty on dissecting the portal vein); these collaterals are more on the anterior aspect. Once portal vein is dissected all around an umbilical tape is passed around it. Adequate posterior dissection is essential to prevent angulation during anastomosis with IVC. Portal pressure should be measured through an omental vein.

Retroperitoneum is incised; IVC in front, lateral and medial aspect is dissected from a point where right renal vein joins the IVC to a point where IVC becomes retrohepatic. Vascular clamps are applied to portal vein proximally just above the pancreas and distally prior to bifurcation. ***In end-to-side portacaval shunt*** distally portal vein is divided and distal end is sutured using continuous 5-0 polypropylene suture. Two stay sutures are placed to proximal cut end of portal vein. Satinsky vascular clamp is applied to the anterior aspect of the IVC. IVC is incised. Often an ellipse of the wall in front of IVC may be excised. Incision in IVC should be at least 1½ *times the size of the portal vein. Posterior part of the portal vein is sutured to the medial part of the IVC using 5-0 continuous polypropylene sutures.* It is easier if many sutures are taken and then tightened to slide the portal vein into IVC. Anterior suturing is done between anterior aspect of the portal vein to lateral part of the IVC incision. This should be done always from upper part towards lower part. Continuous or interrupted sutures are used. End-to-side will decompress the splanchnic pressure but keeps sinusoids under high pressure; it will control the variceal bleeding; but will not relieve ascites. End-to-side is not done now. It is a total shunt. Hypertrophied caudate lobe creates problem in side-to-side anastomosis. Future liver transplantation may become difficult **(Fig. 22-29)**.



Fig. 22-29: End-to-side portacaval shunt.

Side-to-side shunt is also done similarly without transecting the portal vein. Longitudinal incisions in both portal vein and IVC are done. IVC incision should be 1½ times more than that of portal vein. Posterior continuous and anterior continuous or interrupted sutures are placed from above downwards. Shunt size should be minimum 10 mm. This shunt reduces the obstruction of sinusoids and so relieves ascites also along with control of variceal bleeding. It is a total shunt. *Total shunt* should have a shunt diameter not less than 10 mm.

Side-to-side shunt with an interposition graft (PTFE 8 mm size graft, 3 cm long) diverts blood causing reduction in portal pressure. Since its size of shunt is less than 10 mm, it controls the variceal bleeding well and also maintains the portal perfusion significantly reducing the incidence of the hepatic encephalopathy. It is a partial shunt. *Partial shunt* should have a shunt diameter not more than 8 mm; usually 8 mm **(Fig. 22-30)**.



Incision in IVC should be 11/2 times more than incision in portal vein; posterior continuous and anterior continuous or interrupted 5 zero polypropylene suture is used. suturing starts from above downwards.

Fig. 22-30: Side-to-side portacaval shunt surgery.

Mesocaval shunt can be side-to-end or side-to-side with a graft. In portal cavernoma in children side-to-side mesentericocaval shunt is used. In adult side to side with a graft is used. Midline laparotomy incision is used. When transverse colon is held and stretched upwards superior mesenteric vein can be seen; it is dissected and isolated. Ligament of Treitz is divided to mobilise small bowel forward and right **(Fig. 22-31)**.

Duodenum should be mobilised by Kocherisation. A 2 cm long SMV unobstructed segment is needed; large tributary vein on the left side of SMV should not be present; artery should not cross or override the SMV. Peritoneum in the right paracolic gutter is incised; entire ascending colon and proximal transverse colon is mobilised medially to identify IVC. IVC is dissected from iliac vein confluence to right renal vein level. Vascular clamps are applied across the IVC one


Spleen
Portal vein
Splenic vein
Kidney
Inferior mesenteric vein
Kidney
IVC
Mesentericocaval
SMV
CIV
CIV

Fig. 22-31: Side-to-end mesentericocaval shunt.

at close to its iliac confluence, another just below the renal vein level. IVC is transected just above the lower clamp; it is passed through the small mesentery through a created window between distal ileal vessel and ileocolic vessel. SMV is incised after applying a vascular clamp; incision is made on posterolateral part of it longitudinally proximal to right colic vein level. Anastomosis is done using 5 zero polypropylene continuous sutures.

Mesentericoocaval shunt with an *interposition graft* is side to side. Graft used is woven Dacron or PTFE. IVC is similarly dissected; side of IVC is incised after applying Satinsky clamp; IVC is anastomosed to graft as side to end with continuous 5-0 polypropylene suture. Other end of the graft is passed through the mesentery and is anastomosed to the side of mobilised SMV. Mesocaval shunt is preferred for isolated hepatic vein obstruction; technically easier; hilar dissection is not present **(Fig. 22-32)**.


Spleen
Portal vein
Splenic vein
Kidney
Inferior mesenteric vein
Kidney
Superior mesenteric vein
CIV
Mesentericocaval shunt (graft)

Fig. 22-32: Side-to-side mesenteric caval interposition graft to create a shunt.

Proximal (central) splenorenal shunt: Here blood flows high pressure portal system towards the low pressure systemic venous system through renal vein. It is presumed it allows part of blood to course through the liver to reduce the encephalopathy effects. Patient under general anaesthesia with left side up or oblique; left lengthy subcostal or left thoracoabdominal incision is made. Splenic flexure and transverse colon is mobilised to retract them downwards. Short gastric vessels are ligated and divided; splenophrenic and splenorenal ligaments are divided to reach the splenic hilum to identify splenic vessels. Splenic artery is ligated. Splenic vein is dissected proximally by ligating and dividing all branches entering into it so has to free it until it joins the superior mesenteric vein. Inferior mesenteric vein entering the splenic vein can be ligated and divided safely if needed. Vascular clamp is applied to the splenic vein; spleen is removed **(Fig. 22-33)**.


Inferior mesenteric vein
Spleen (removed)
Portal vein
Splenic vein
Kidney
Proximal splenorenal shunt
Kidney
CIV
Superior mesenteric vein
Satinsky clamp
Splenic vein
Spleen removed
Elliptical incision 1½ times of splenic vein diameter
Satinsky clamp
Left renal vein
Superior mesenteric vein
Left adrenal vein — ligated

Fig. 22-33: Proximal splenorenal shunt surgery. It is a non-selective shunt (Linton's).

The retroperitoneum is incised to identify the left renal vein just at lower margin of the pancreas. Left renal artery and renal vein is isolated with vascular tapes. Left adrenal vein needs often ligation and division for proper mobilisation of the left renal vein. Left renal vein is mobilised adequately. Left renal artery is often occluded with vascular bulldog clamp to reduce renal vein flow temporarily. A Satinsky clamp is placed obliquely across the renal vein; incision is made on the anterosuperior aspect of the left renal vein often to remove elliptical piece of it; incision should be 1½ times the diameter of the splenic vein end. End of splenic vein is anastomosed to the left renal vein using continuous 5-0 polypropylene sutures posteriorly and interrupted sutures anteriorly to complete the proximal/central splenorenal shunt. Tapes and clamps are removed from the left renal artery, renal vein and splenic vein.

Portacaval Shunt with Arterialisation

This is done in end-to-side portacaval shunt as there is abrupt stop of hepatic blood flow. So hepatic blood flow is maintained by interposition of the saphenous vein graft or synthetic PTFE graft between infrarenal aorta and hepatic stump of portal vein in end side shunt. Arterialisation is also can be achieved by turning splenic artery end to the portal vein to create as end-to-end anastomosis. As end-to-side portacaval shunt is not done now, arterialisation procedure has also no role at present **(Fig. 22-34)**.

Selective Shunts

Distal splenorenal shunt (DSRS)—Warren's shunt *(Warren, 1967)*. Size of the splenic vein should be 10 mm or more to do distal splenorenal shunt; if less, then shunt may develop thrombosis and shunt failure can occur. End of splenic vein is shunted to the side of the left renal vein. Splenic vein should be more than 10 mm in size (diameter). It selectively decompresses the portal bed near oesophagogastric area (so that it prevents bleeding). Liver is also perfused adequately and so possibility of encephalopathy is less. But it may augment incidence of ascites. Left subcostal or chevron incision is used with left side up position. Incision extends from left anterior axillary line extending across the right rectus up to the right margin of the right rectus muscle. Through gastrocolic ligament lesser sac is entered. Gastroepiploic arcade is divided to prevent later formation of collaterals (arcade is divided towards gastric side). Short gastric vessels should be retained (should never be interrupted; it is through this variceal bed is decompressed into splenic vein). Plane is created between 3rd part of the duodenum and pancreas by dividing peritoneum over it. When gland is reflected upwards, splenic vein is identified which is dissected carefully by ligating all branching vessels individually carefully and divided. A venous catheter is passed into the splenic vein to measure the splenic vein pressure. Inferior mesenteric vein is identified and, dissected, doubly ligated and divided. Splenic vein is mobilised up to its entry into the superior mesenteric vein. Vascular clamp is applied to the splenic vein. Splenic vein is divided at its junction with SMV. Small pancreatic branches entering the splenic vein are ligated and divided **(Fig. 22-35)**.

Left renal vein is dissected similarly; left adrenal vein is ligated but left gonadal vein is retained. Average length of the renal vein is 8 cm; 5 cm of it should be mobilised for proper shunt anastomosis. Portal side of the cut end is sutured with continuous polypropylene sutures. Left gastric (coronary) vein at its junction where it enters the portal or splenic vein is ligated and divided; all veins along the retroperitoneum above the pancreas, along splenocolic ligament, along greater and lesser omentum are interrupted effectively; right gastroepiploic vein is already ligated but should be confirmed. Efficacy in control of bleeding is 94%; with 90% preserved portal blood flow. Encephalopathy incidence is 15% or less.

Inokuchi shunt is a selective shunt between IVC and left gastric vein (using a graft).

Unconventional shunts

Modified Rex Shunt: It is done between left portal vein and SMV using autologous IJV graft.

Alternative splanchnic drainage is done route using inferior mesenteric or gastroepiploic veins; coronary vein to left portal vein.

Alternative systemic route: Mesogonadal or lienoadrenal shunts.

Unconventional shunts cause partial non-selective decompression; yield effective shunting; does not preclude liver transplantation. But need is good quality adequate length and caliber (>5 mm) vein.

Splenectomy

Left sided portal hypertension also called as s*egmental portal hypertension* (sinistral portal hypertension) is due to splenic vein thrombosis (If partial channels are present within it, it is called as *splenic vein cavernoma*). Here liver is normal and *splenectomy* alone will correct the condition. Banti in 1894 originally suggested splenectomy for portal hypertension.

Transjugular Intrahepatic Portosystemic Stenting/Shunt (TIPSS)

Size of stent must be 10 mm. It is a non-surgical, interventional radiological method, wherein, a stent is placed in the liver between hepatic venule and portal through a guidewire following dilatation. It



Here interposition graft is placed between infrarenal aorta and hepatic stump portal vein

Here splenic artery end is turned and rotated on to the hepatic stump of the portal vein

Arterialisation is done only in end-to-side portacaval shunt

Fig. 22-34: Portacaval shunt with arterialisation being done.



Fig. 22-35: Distal splenorenal shunt (DSRS)—Warren's shunt.

is a simple and easier method to reduce portal pressure. It can cause hepatic encephalopathy, bleeding, bile leak and infection.

It is contraindicated in encephalopathy, tumours and liver cysts. It is quite useful as a temporary measure to reduce portal bed pressure, before doing orthotopic liver transplantation in cirrhotic patients.

Problems with TIPSS

Post-stent encephalopathy—40%; stenosis (50%) and recurrent varices; bleeding; bile leak; sepsis **(Fig. 22-36)**.



Fig. 22-36: Transjugular Intrahepatic Portosystemic Stenting/Shunt (TIPSS).

Mesoatrial Shunt

When hepatic vein and IVC block are present, mesoatrial shunt or caval stenting and portacaval shunt or cavoatrial shunt with portacaval shunt is needed. Mesocaval shunt is indicated when there is IVC block that is not amenable for stenting; prerequisite is a pressure gradient of 15 mm Hg or more between IVC and right atrium. Shunt placement in low pressure system may precipitate shunt thrombosis.

Table 22-1: Child's grading of severity of liver disease

Clinical and biochemical measurement	*Points scored*		
	1	2	3
Serum bilirubin (mg/dL)	<2.0	2.0 to 3.0	>3.0
Serum albumin (gm/dL)	>3.5	3.0 to 3.5	<3.0
Ascites	None	Controlled	Uncontrolled
Mental status	Normal	Disoriented	Coma
Nutrition	Very good	Good	Poor
Total score	<6 Child's A	7-9 Child's B	10-19 Child's C
Pugh's modification			
Prothrombin time prolonged in secs	Increased up to 3	Between 3-6	> 6

Surgeries for portal hypertension
- Orthotopic liver transplant (OLT)
- Devascularisation surgeries
- Decompression surgeries

Surgeries for oesophageal varices and portal hypertension

Decompression procedures
- Non-selective shunts
  - End-to-side portacaval shunt (Eck fistula)
  - Side-to-side portacaval shunt
  - Mesentericocaval shunt
  - Mesentericocaval shunt with graft
  - Proximal splenorenal shunt—Linton's shunt
  - TIPSS

Selective shunts
- Distal splenorenal shunt—Warren's shunt
- Inokuchi shunt between left gastric vein and IVC through a graft

Devascularisation procedures
- Oesophageal stapler transection; Boerema Crile operation; Tanner's oesophageal gastric transection; Milnes Walker transection; Sugiura Futagawa/Hassab/Orozco and colleagues operations

Porta-azygos Disconnection/ Devascularising Procedures

They are inflow control that act effectively by devascularising the portal bed. It is useful in extensive portal and splenic vein thrombosis. Incidence of encephalopathy is very low here.

***Oesophageal stapler transection of Johnston*:** Through an anterior gastrotomy incision end-to-end stapler is passed across the oesophagogastric (OG) junction into the oesophagus and stapler is fired to transect, interrupt all varices, disconnect azygos and portal connection at oesophageal level and reanastomose automatically through the stapler. It is simple to do **(Fig. 22-37)**.



Fig. 22-37: Stapler transection—devascularisation procedure.

Boerema-Crile operation: It is a thoracic approach. Patient with right lateral position, thoracotomy is done through 8th rib; oesophagus is dissected and isolated; clamp is applied at cardia; oesophagus is opened longitudinally to hold edges with stay sutures. Varices columns are underrun using continuous vicryl sutures. Oesophageal incised muscle layer is resutured again. Usually hiatus is not opened across the diaphragm to abdominal cavity as if ascites is present, it may communicate into the pleural cavity.

Milnes-Walker thoracic oesophageal transection: It is done through left sided thoracic approach; vagi are safeguarded. Oesophageal muscle is incised longitudinally; mucosa and submucosa are dissected and isolated as like longitudinal tube which is resected to interrupt the mucosal and submucosal varices. This tubular structure is resutured and muscle incised is sutured back again. Below this, transected is done at the level of hiatus and resutured again.

Tanner's abdominal oesophagogastric transection: It is done through abdominal approach. All communications between the portal system and azygos systemic veins are interrupted after transecting the stomach 5 cm below the OG junction. After proper interruption reanastomosis is done between the cut ends of stomach.

***Sugiura-Futagawa operation* (1977, Japan):** Vagotomy, pyloroplasty, devascularisation, splenectomy. Laparotomy is done; can also use thoracoabdominal incision. Spleen is removed; devascularisation begins at lesser curvature of stomach; left gastric artery and vein (coronary vein) are ligated; greater curvature, posterior part of the stomach are devascularised. Paraoesophageal devascularisation is done by disconnecting all vessels passing between hemiazygos and azygos veins up to inferior pulmonary vein (in original Sugiura method, devascularisation was done up to arch of aorta) for at least 7 cm of lower oesophagus. Highly selective vagotomy is done (in original Sugiura truncal vagotomy and pyloroplasty is done). Oesophagus is transected using EEA stapler; anastomosis is covered with Nissen's fundoplication. Hassab from Egypt did similar devacularising procedure. Orozco and colleague from Mexico did similar devascularisation procedure without splenectomy with good results.



Fig. 22-38: Hydatid cyst CT scan—large cyst in liver.

SURGERIES FOR HYDATID CYST

Hydatid cyst is managed by chemotherapy; minimally invasive techniques (PAIR); open surgeries; laparoscopic procedures **(Figs 22-38 to 22-42)**.

Classifications

Hassen Gharbi's ultrasound-based classification of liver hydatid cysts (1981)

Type 1 – Pure fluid collection
Type 2 – Fluid collection with split wall
Type 3 – Fluid collection with septa
Type 4 – Heterogeneous appearance
Type 5 – Reflecting thick walls

WHO classification of liver hydatid cyst

Type – CL – Active; unilocular; no cyst wall; early stage; not fertile
Type – CE 1 – Active; cyst wall present; hydatid sand present; fertile
Type – CE 2 – Active; multivesicular rosette-like cyst wall; fertile
Type – CE 3 – Transitional; detaching laminated membrane; *water-lily* sign; beginning of degeneration
Type – CE 4 – Inactive; degenerative contents; no daughter cysts; not fertile
Type – CE 5 – Inactive; thick calcified wall; not fertile

Cyst is common in right lobe (65%); left lobe is (18%); both (16%). Segment 8 is commonly involved (30%); then segment 5 (22%).


10cm
R
30
mAs 100
IV CONTRAST
+C
kV 130
W 300 eff.mAs 100
10cm
IV CONTRAST
R
10cm
+C
kV 130
eff.mAs 100
IV CONTRAST
R
10cm
+C
kV 130
IV CONTRAST
IV CONTRAST
H
H

Fig. 22-39: Hydatid cyst—multiple in liver and extrahepatic region.



Fig. 22-40: Hydatid cyst—MRI is ideal and better than CT scan.



Omentum is mobilised with pedicle and placed on the cyst cavity; sutured with cyst wall rim to obliterate the cavity.

Fig. 22-41: Hydatid cyst—cavity obliteration by omentoplasty.

Drugs

Indications for drug therapy: 4 days prior to intervention and continue it for 1 month (albendazole) to 3 months (mebendazole) after the intervention; inoperable cysts; multiple or multiorgan cysts; recurrent hydatids; surgically unfit patients; cysts in lungs, bone, brain and eyes.

Contraindications: Large cysts; Honeycomb cysts (with septae); infected or calcified cysts; pregnancy.

Drugs used are: Albendazole 4 weeks cycles with 2 weeks drug free interval. It is ovicidal/larvicidal/vermicidal. Commonly used; praziquantel—60 mg/kg along with albendazole for 2 weeks; mebendazole—600 mg daily for 4 weeks.

Puncture–Aspiration–Injection–Reaspiration (PAIR)–Percutaneously Done (1980)

Aspiration of the cyst should not be done due to risk of anaphylaxis but presently Puncture-Aspiration-Injection-Reaspiration (PAIR) is done effectively.



Fig. 22-42: Simple cyst of liver; it is removed through laparoscopy easily. It is a differential diagnosis for hydatid cyst of liver.

Indications for PAIR	**Results and problems of PAIR**
• Inoperable patients • Patients who refuse surgery • CL, CE 1, CE 2 and CE 3 types/ Gharbi type 1 and 2 • Relapse cysts • Infected cysts • In pregnant women; children less than 3 years • Cysts more than 5 cm in different liver segments	• Complication rate—10-40 % • Mortality rate—0.9-2.5% • Fever—35%, disappears in 72 hours • Anaphylaxis—0.1-0.2%, Same as open surgery, but drugs should be kept ready for • Anaphylaxis • Infection—10% well-controlled by antibiotics • Local recurrences—4%, repeat PAIR can be done
Contraindications for PAIR • Inaccessible cysts • Cysts with multiple septae—honeycomb cysts • Hyperechogenic cysts • Communicating cysts to bile duct • Calcified cysts • Cysts in the lung	

Technique of PAIR

It is done under US/CT guidance; under local anaesthesia, cyst is punctured using a cholangiography 22-gauge needle through thickest route/part of cyst wall; Cyst is entered through non-dependent wall and 50 % of fluid is aspirated. All multiple/daughter cysts are aspirated. Radiopaque dye is injected to see if any communications are present. Scolicidal agents— 15-20% hypertonic saline is injected into the cyst. After 20 minutes reaspiration is done. A sclerosant—alcohol is injected. If cyst is 6 cm or more, a drainage catheter is placed for 24 hours for complete drainage and later alcohol sclerosant is injected. Double – puncture aspiration and injection (D-PAI) or modified PAIR/PEVAC (Percutaneous EVAcuation of Cyst) are other procedures done. PAIR has gained wide acceptance as it is safe, less invasive, and easier to do, with low morbidity and mortality. Complications and results are same as open surgery.

SURGERY

Surgery is the best treatment for hydatid disease as it removes the parasite, cystobiliary communications are addressed, less morbidity and mortality and low recurrence rate.

Procedures are Conservative and Radical.

- Surgery is still the choice and gold standard therapy for hydatid disease. The abdomen is opened, and the peritoneal cavity is packed with mops (black or colored mops are used to identify white scolices clearly so as to pick up all and prevent any spillage). Fluid from the cyst is aspirated and scolicidal agents (cetrimide, chlorohexidine, alcohol, hypertonic saline (15-20%), 10% povidone iodine or H_2O_2) are injected into the cyst cavity (formalin should not be used). Hypertonic saline should be left within the cavity for 15-20 minutes to have effective scolicidal effect.
- Detection of cystobiliary communications is very crucial as it may cause caustic sclerosing cholangitis when scolicidal agent like formalin is used. Communicating openings may be single or multiple. Cyst more than 10 cm is likely to have cystobiliary communications. Often clinically features of communications may not be present. Preoperatively there may be recurrent cholangitis; dilated bile duct. Factors important are—its size, number, site, involvement of hepatic/bile ducts and liver dysfunction.

Contd...

Contd...

Bile stained cyst on table during aspiration is highly suggestive of communication. White mops soaked with hypertonic saline are kept in the cyst cavity and gallbladder is gently squeezed to see for the bile staining of the mop in the cavity which confirms communication.
- Pericystectomy is ideal, but technically demanding.
- Laparoscopic pericystectomy is becoming more popular. Contraindications are deeply situated cyst, densely adherent cyst, and inaccessible cysts; more than 3 cysts; calcified cysts and cysts in other organs. Main problems with laparoscopic pericystectomy is spillage and difficulty in preventing it.
- Liver resection—only occasionally segmental or hemihepatectomy is done.

Scolicidal agents

- Cetrimide—can cause acidosis
- Alcohol 80%—can cause cholangitis
- Hypertonic saline—hypernatraemia
- Sodium hypochlorite—hypernatraemia
- Hydrogen peroxide

In cases with biliary communication, only hypertonic saline (15-20%) is used (not other agents)

Features of formed abscess are

Procedures used to correct the cystobiliary communications and to obliterate the cavity are:

- Suturing of the communication – simple suture using vicryl/PDS suture with T tube drain of bile duct.
- Pericystectomy (Pericystectomy is done by peeling off the cyst wall and abdomen is closed with or without a drain), marsupialization.
- Tube drainage of the cavity; capitonnage–spiral suturing of the bottom of the cavity upward from base of cavity to the edge of the cyst wall; introflexion–inverting the rim of the cyst edge without apposition; omentoplasty.
- Internal drainage procedures like choledochojejunostomy; transduodenal sphincteroplasty; Roux-en-Y cysto/intracystic hepatico jejunostomy; Roux-en-Y hepaticojejunostomy.
- In cystobiliary communication (fistula), cystobiliary disconnection is achieved anatomically between cyst and fistula and a multiperforated transparenchymal drain is placed into the fistula through the cyst and another multiperforated drain is placed into the cyst cavity. A T tube drain is placed into the bile duct (perdomo procedure) to achieve complete external drainage with facilitation of closure of the communication.
- Bipolar drainage: A drain is placed to cyst cavity and a T tube is placed into common bile duct. .
- Reconstructive procedure like pericystojejunostomy; bile duct repair.
- ERCP sphincterotomy.

Conservative Surgical Approach

It is technically easier; hepatic specialized surgeons are not necessary; safer; liver parenchyma is not entered; multiple bilateral cysts can be approached; cost-effective; tissue sparing; acceptable in relation to recurrence, morbidity and mortality.

Cyst should be exposed completely; cyst should be sterilised properly (scolicidal); should be evacuated completely; cystobiliary communications and cyst cavities are to be managed effectively.

Right subcostal with often extension towards left side is needed for adequate exposure. Liver should be released of all adhesions and made mobile.

Entire field surrounding the liver should be packed with hypertonic saline (20%) black/blue/green drapes/mops (to identify white scolices. Cyst wall is punctured carefully; often specialised cones are used for this purpose (Saidi Nazarian cryogenic cone (1971); Aaron's cone by Aaron's and Kune, Australia). Aaron's suction cone is better, safer and effective. But it is not necessary to use these devices. Stay sutures are placed on the cyst wall; cyst wall incised for 5 cm. Large sump suction is used to suck all fluid in the cavity. All laminated membranes are removed using forceps or hand or spoon.

Cyst roof which is redundant is excised. Cut edge of the cyst should be underrun with sutures (oversewing) to block small vessels and ducts in the cyst wall. Inside cyst cavity wall is gently scraped using hypertonic saline soaked gauze. All daughter cysts should be removed by this method with care, gentleness and patience. Cavity is washed with hypertonic saline repeatedly. Saline soaked packs are kept in the cavity for 10 minutes.

Different scolicidal agents are used. Different types have got different efficacy and exposure time. Hypertonic saline is safer with 30% solution having 10 minutes exposure time; lesser concentration needs more exposure time. Cetavlon has got shortest exposure time—5 minutes. Other scolicidal agents are—povidone-iodine, hydrogen peroxide, formalin (not used) with different exposure timings. Scolicidal agents can cause severe sclerosing cholangitis, methhaelmoglobinaemia, acute toxicity, hypernatraemia, air embolism, anaphylaxis, metabolic acidosis, may cause death rarely. Hypertonic saline is ideal. Partial pericystectomy is done usually in many situations; subtotal pericystecomy is also done occasionally. Pericyst adherent to biliary and vascular structures are left behind.

Cystobiliary communications (CBC) should be identified and managed properly. It may be single or multiple. Its management depends on the number, type, depth, site, size (minute or wider orifice), duct involved, and status of liver. On table bile-stained cyst suggests communication. In such situation, carefully with repeated saline wash staining site of bile can be identified. It is better to pass a needle into the CBD and inject saline or saline and air or dilute methylene blue to the bile duct to identify the site. Intraoperative cystic duct cholangiography is also done through cystic duct which needs cholecystectomy. It demonstrates the CBD scolices, site of leak. But it is not mandatory, often may not be sufficient. ERCP or intraoperative ultrasound (IOUS) is very useful in identifying the CBD scolices. Scolices in gallbladder are very rare.

Commonly such cystobiliary communications are of peripheral duct branches and small; just secure suturing of the minute orifice the using 4-0 vicryl or PDS is sufficient. In biliary tree, bile enters into scolices existing there and parasite dies and so CBD scolices are rare **(Fig. 22-43)**.

If cholangiogram or on table IOUS shows hydatid debris, then choledochotomy is done debris is removed; choledochoscope is done; T tube is placed while closing the CBD. T tube is also often placed when there are communications (which are sutured accordingly) to have assured decompression of the biliary tree so that sutures will not disrupt. Once T tube is placed per operative T tube, cholangiogram is done.

In case if suturing of the leaking orifice is impossible, then combined external drainage of the pericyst by placing a drain on pericyst and drainage of extrahepatic biliary apparatus is done (either external or internal). This method of draining both pericyst and biliary apparatus is called as bipolar drainage. External biliary apparatus drainage is achieved by placing a T tube into CBD. Often a multiperforated drain is passed through the orifice to drain fistula across the parenchyma; another such drain is placed into the cyst cavity; T tube is placed the CBD—*Perdomo procedure*.

Internal drainage of biliary tree can be achieved by *ERCP sphincterotomy* or transduodenal sphincteroplasty or bilioenteric anastomosis (Roux-en-Y choledochojejunostomy or duodenostomy). Bilioenteric drainage is done when there are many daughter cysts in CBD or dilated CBD or when there is cholangitis.

Cystobiliary communication into a major biliary ductal system if sutured may obliterate ductal drainage partially which is dangerous. Here Roux en Y cystojejunostomy or intracystic hepaticojejunostomy or intracystic bile duct repair is done. These procedures are often technically difficult and liver resection may be final answer in these patients.

Residual cavity of the cyst often needs obliteration by different methods. This cavity may be superficial or anterior or posterior or superior or inferior; it can have large opening with large capacity or small opening with large capacity. Residual cavity can be managed by—(1) Leaving cyst open; (2) With rim oversewn on the entire edge—marsupialization; (3) Small cyst can have simple closure; (4) Placing drainage tube into the cyst cavity as external drainage; (5) Introflexion by infolding edge of the cyst inward with taking bites from overlying liver tissue; (6) Capitonage—redundant pericyst is infolded from depth to outwards by consecutive interrupted layer of sutures or by continuous spiral suture bites taken from pericyst wall at alternative sides; This is difficult in large or calcified cysts; deep bites may injure liver parenchyma or hepatic veins underneath or stiff cyst wall may get avulsed off from the liver tissue causing severe haemorrhage; (7) Omentoplasty – Viable omental pedicle is placed into the cavity and fixed with absorbable sutures; drain is placed adjacent to the omental flap; omentum obliterates the cavity but will not prevent bile leak; omentoplasty can be combined with partly capitonage; (8) Roux-en-Y cystojejunostomy not commonly used; (9) Rectus abdominis and diaphragm myoplasty **(Figs 22-44 to 22-47)**.

Radical Surgical Procedures for Hydatid Liver Disease

It is done if conservative surgery is impossible; already done conservative surgery has failed; lobe involved is irreversibly damaged; adequate biliary drainage if cannot be achieved. Every patient with hydatid disease is not an indication for radical procedure. Closed pericystectomy; open pericystecomy; near total cystectomy; subadventitial cystectomy; non-anatomical liver resection and anatomical liver resections are different procedures done. In closed pericystectomy, cyst is not opened, instead entire pericyst is removed carefully and gently. In open pericystectomy also after opening, the cyst is entirely removed by similar methods. Near total pericystectomy is done when pericyst is adherent to IVC and major hepatic veins past of pericyst are left behind after sterilization with hypertonic saline but remaining part of the pericyst and scolices are completely removed. Pericyst is the outer most layer which is adherent to the liver tissue including vasculobiliary structures which may get damaged in during even careful dissection as adhesions are very strong often. Inner avascular granulomatous exocyst layer is separated from pericyst along the subadvential plane. If dissection is done little away from pericyst, it becomes non-anatomic liver resection. Hepatectomy is done only if entire right or left liver is involved.

Pericystectomy for Hydatid Liver Cyst

There is controversy regarding optimal treatment for this parasitic disease. Options of deroofing and content evacuation is considered suboptimal and pericystectomy may be too radicle a procedure for some cases. The main principle of the surgery is to eradicate the parasite and prevent intraoperative spillage of cyst contents avoiding peritoneal spread. Preoperatively 10-14 mg/kg/day of albendazole is administered orally for a period of 4 weeks. Deep seated cysts and



Enlarged palpable liver due to hydatid with positive hydatid thrill

Right subcostal incision

Liver is mobilised adequately

Coloured mop/towel should be kept around to identify white scolices (black)

Figs 22-43(1)


Black towels
should be used
Hypertonic saline 20-30%
soaked and kept for 10 minutes
Any cytobiliary communications
are sutured using 4-0 vicryl
One drains the cyst cavity other in the
peritoneal cavity is placed
Hypertrophied left lobe

Figs 22-43(2)


Closure of right subcostal incision
One drain the cyst cavity and the other is placed in the peritoneal cavity

Figs 22-43(3)

Figs 22-43(1 to 3): Hydatid cyst – conservative decompression—drainage procedure; it is commonly advocated, reasonably safe, simple and easier than radical surgeries for hydatid cyst of liver.



Hydatid cyst after conservative surgical drainage may have a large opening with large volume cavity

Hydatid cyst after conservative surgical drainage may have a small opening with large volume cavity

Fig. 22-44: Large and small opening of large volume/cavity hydatid cyst.


After conservative decompression surgery, cavity is marsupialised and drain is kept

Fig. 22-45: Hydatid cyst—marsupialisation of the cyst wall and cavity.



Interrupted sutures to infold cyst wall

Spiral sutures to infold the cyst wall

Capitonage is infolding of the cyst wall from depth by suturing the cyst wall with interrupted or continuous spiral sutures from deeper plane towards outside. It obliterates the cyst cavity

Fig. 22-46: Hydatid cyst—cavity obliteration by capitonage.



Ectocyst is infolded and sutured to liver capsule so as to obliterate the cavity

Fig. 22-47: Hydatid cyst—obliteration of cavity by introflexion.

those close to major veins may not be candidates for pericystectomy and formal hemihepatectomy may be indicated. Access to the abdomen is gained like for any major liver surgery. Abdomen is carefully explored for presence of any extrahepatic disease. Povidine-iodine soaked mops need to be kept ready in case of spillage of the cyst contents. Intraoperative ultrasound is helpful to determine the relation of the cyst to the hepatic veins and vena cava. The cyst on the surface are separated from the under surface of the diaphragm. The central venous pressure is kept under 5 mm Hg to decrease the intra operative blood loss. The portal inflow is taped and kept ready in case there is need for inflow occlusion due to bleeding. Stay sutures are placed in the liver parenchyma around the emerging part of the cyst to enable traction and better exposure during resection. The liver capsule is incised using diathermy. The identification of the right plane around the cyst capsule is important to decrease intraoperative blood loss. The parenchyma around the cyst is dissected out using Kelly clamp method or any available energy source. Attention must be paid to identify any biliary radicles communicating with the cyst. In case of difficulty, the procedure can be abandoned in favour of deroofing of the cyst and evacuation of the contents. After giving good wash inside a careful inspection is done to identify biliary communications if any and they are underrun. Omentum can be used to plug the cyst cavity.

Complications of Surgery

Biliary leak is the most important complication in large hydatid disease surgeries. Causes are—persistent cystobiliary communications; biliary tree injury; retained debris in CBD; calcified cyst. Conservative treatment with or without ERCP and sphincterotomy is usually sufficient.

Infection is one of the most common complications after hydatid cyst surgery; often patient develops septicaemia. Subphrenic abscess, liver abscess formation are not uncommon which should be addressed accordingly by antibiotics and guided external drainage using a tube.

Liver failure is the most dreaded complication especially very large cyst. Often patient succumbs to liver failure.

Respiratory problems like bronchopneumonia and ARDS can occur which should be addressed accordingly with ICU care.

Recurrences during long-term follow-up can also occur due to retained scolices or part of the germinative membrane. Progression of disease at different sites as secondary hydatids can occur which should be addressed depends on the site of the cyst. Recurrence rate is 1-30% in different studies. Initial surgical precision plays a major role in recurrence incidences.

B. GALLBLADDER WITH EXTRAHEPATIC BILIARY TREE

SURGICAL ANATOMY

Gallbladder

It is a pear-shaped (size is 5-12 cm) reservoir, located in a fossa on the inferior surface of the liver. Four parts of gallbladder are fundus, body, infundibulum and neck. *Hartmann's pouch* is pathological one located in the infundibular region created by gallstones. The hepatic surface is attached to liver by connective tissue of liver capsule; non-hepatic surface and fundus is covered by peritoneum. Body of the gallbladder is covered by peritoneum on the non-hepatic surface and is related to transverse colon, and 1st and 2nd portions of the duodenum. In 4% of individuals body has got its own mesentery. Such gallbladder is called as *floating/roving gallbladder* and is prone for torsion and gangrene. Body of the gallbladder is related to transverse colon and 1st and 2nd part of the duodenum.

Gallbladder drains through cystic duct into common hepatic duct to form common bile duct. It is supplied by cystic artery, a branch of right hepatic artery. *Calot's triangle* is (Calot, 1891; cholecystohepatic triangle) formed by common hepatic duct to the left, cystic duct and gallbladder below, and inferior surface of liver above. Cystic artery originating from right hepatic artery passes behind the common hepatic duct enters the Calot's triangle to reach the gallbladder. It contains lymph node of '*Lund' (Fred Bates Lund)*.Often cystic artery, hepatic artery, cystic duct have anomalous positions and anomalous origins. Both gallbladder neck and cystic duct contain mucosal fold called *valves of Heister.* Gallbladder is pear-shaped with 50 mL capacity. *Fundus* is in the summit like a dome and is covered fully by peritoneum; it projects beyond the liver margin. It contains smooth muscle. This part is anastomosed to small bowel while doing cholecystojejunostomy. *Body* contains mainly elastic tissue which is a storage part; it is in deeper plane is attached to liver and outer part is attached to peritoneal cavity. Body tapers into *neck* like a funnel lying on the free border of hepatoduodenal ligament; its distended convexity is called as *infundibulum*/Hartmann's pouch (pathological). *Lining* of the gallbladder is by columnar epithelium which contains cholesterol and fat globules. The *mucus* secreted into the gallbladder originates in the tubuloalveolar glands globular cells lining the mucosa of infundibulum and neck **(Fig. 22-48)**.



Fig. 22-48: Anatomy of gallbladder and Calot's triangle.

Extrahepatic Biliary Tree

The left hepatic duct is formed by the ducts draining II, III, IV segments of the liver. The right hepatic duct is formed by the ducts draining V, VI, VII, VIII segments of the liver. Both join to form the *common hepatic duct (CBD)*, which joins with the cystic duct to form the *common bile duct*. Junction of right and left hepatic ducts to form common hepatic duct is 0.25-2.5 cm from the surface of the liver. Left duct is longer about 1.7 cm than right hepatic duct which is 0.9 cm. occasionally this junction may be intrahepatic due to enlargement of the liver. Common hepatic duct is variable in length from 1.5 cm to 3.5 cm. When cystic duct joins the junction of the right and left hepatic ducts then common hepatic duct is considered as absent. Cystohepatic junction may be angular, parallel and spiral.

Cystic duct is 3 mm in diameter and 2-4 cm in length. Variations are common. During these variations should be remembered to avoid inadvertent injury to common bile duct.

Common bile duct is normally 5-12 cm in length and 6-8 mm in diameter. Length depends on the position where cystic duct joins. It has got 4 parts – (1) *Supraduodenal* with a length of 2 cm; (2*) Retroduodenal* part with a length of 1.5 cm; (3) *Pancreatic part* with a length of 3.0 cm; (4) *Intramural/intraduodenal* part with a length of 1.1 cm. Length of each part is variable. Supraduodenal portion lies in the two leaves of the hepatoduodenal ligament, in front of the portal vein to the right of the proper hepatic artery. Retroduodenal part runs from the superior margin of the 1st part of the duodenum to upper margin of the head of the pancreas. Gastroduodenal artery is left of the duct; posterior superior pancreaticoduodenal artery crosses the duct first in front of the duct later behind it just it joins the duodenum. Common bile duct may be covered partly by pancreas (44%) or fully (embedded in the pancreas—30%) or not covered by pancreas (16%) or covered by two leaves. It joins the major pancreatic duct in the wall of the 2nd part of duodenum to form the *ampulla of Vater*. Intraduodenal part of common bile duct (CBD) is surrounded by smooth muscle fibres called as *sphincter of Oddi.* CBD if more than 8 mm diameter is pathological. Pancreatic CBD is palpable from behind after Kocher's duodenal mobilisation. Intraduodenal part is oblique in the duodenal wall running for 1.5 cm. Here CBD diameter reduces from 5.5 to 3.5 mm. Pancreatic and bile duct initially separated by a septum with a common adventitia for 5-10 mm eventually forms a confluence of ducts **(Figs 22-49 and 22-50)**.


Right hepatic duct
GB
Left hepatic duct
Common hepatic duct
CBD (supraduodenal part)
CBD (retroduodenal part)
CBD (retropancreatic part)
CBD (intraduodenal part)
Pancreatic duct
Sphincter of Oddi

Fig. 22-49: Parts of common bile duct.



Fig. 22-50: Sphincter of Oddi—surgical anatomy.

Blood Supply

Arterial Supply

Gall bladder receives its blood supply from cystic artery which is a branch of right hepatic artery or aberrant hepatic artery. Right hepatic artery runs behind the common hepatic duct (87%), often it may be in front of common hepatic duct (13%). Incidence of aberrant right hepatic artery is 15 -20%; cystic artery arises from this (in 80% cases) when it is present.

Aberrant right hepatic artery may replace right hepatic artery (12-16%) or may be accessory to existing right hepatic artery (4-5%). Aberrant/accessory right hepatic artery arises from superior mesenteric artery.

Left hepatic artery anomaly is important. Left hepatic artery may originate from left gastric artery in 5% of cases. In such patients during gastrectomy, while dissecting and ligating this, *aberrant left hepatic artery* may get ligated causing devascularisation of the left lobe of the liver. Often normal left hepatic artery is present originating from common (proper) hepatic artery as usual; but additionally an *accessory left hepatic artery* arising from left gastric artery may also be present (5%).

Cystic artery after its origin, runs towards the neck of the gallbladder where it divides into superficial (anterior) and deep (posterior) branches. Cystic artery as *variation* may arise from left hepatic or proper hepatic or common hepatic or gastroduodenal arteries.

Bile and hepatic ducts are supplied by gastroduodenal, retroduodenal, right and left hepatic and posterosuperior pancreaticoduodenal arteries. One should not devascularise more than 3 cm of the surface of the common bile duct. Supraduodenal bile duct derives its blood supply from retroduodenal artery (60% from below and 38% from above) through right hepatic artery. Bile duct ischaemia should be avoided while doing choledochojejunostomy or choledochoduodenostomy. Two arteries run parallel in the common bile duct at 3 and 9 o'clock position. Interruption of these two arteries lead into bile duct stricture.

Afferent arteries supply the bile duct. Bile duct is not supplied by portal venous system unlike liver. Afferent arteries are gastroduodenal, retroduodenal, right and left hepatic and posterosuperior pancreaticoduodenal arteries. Afferent arteries empty into the marginal arteries which run at 3 and 9 o'clock positions longitudinally along the common bile duct and common hepatic duct. Hilar marginal artery is located at the upper angle of the confluence of right and left hepatic ducts. These marginal arteries form fine network of epicholedochal plexus on the surface of the bile duct, common, right and left hepatic ducts. At the right and left hepatic ducts confluence it forms hilar plexus. These plexus will not extend above beyond the fibrous sheath of the hilar plate. So dissection above hilar plate should be done with the sheath itself, not between sheath and hepatic ducts **(Fig. 22-51)**.


Hilar marginal artery
1
1
3
1
2
3
1
2
1. Afferent vessels
2. Marginal arteries (3 and 9 O'clock positions, longitudinal)
3. Epicholedochal plexus
Afferent vessels from posterior superior pancreaticoduodenal arteries, hepatic arteries
Marginal arteries usually two, occasionally 3rd may be present at 12 O'clock position
Epicholedochal arterial plexus

Fig. 22-51: Pattern of blood vessels in extrahepatic biliary apparatus.

Transection of the bile duct at superior most part makes lower cut edge ischaemic; transection at inferior part close to duodenum makes upper cut edge ischaemic. So in bile duct transection (traumatic/iatrogenic), primary anastomosis (choledochocholedochal) is not safer and is not practiced.

As extrahepatic biliary tree is supplied by hepatic arterial system (no portal venous supply) unlike dual supply of liver, blockage of hepatic artery may cause bile duct necrosis. Right hepatic artery may get injured in laparoscopic cholecystectomy along with bile duct injury. It may cause ischaemia of bile duct also. During surgery bile duct should be divided sharply; it should not be dissected from surrounding tissue to main epicholedochal plexus.

Venous Drainage

Deep cholecystic veins in the gallbladder bed drains into the liver. Superficial cholecystic veins drain into upwards to liver and downwards to portal vein. Usually these veins are less prominent and will not cause significant bleeding after division. But in portal biliopathy gallbladder and choledochal varices will develop which may cause torrential bleeding on dissection **(Fig. 22-52)**.



Fig. 22-52: Veins in biliary system—extrahepatic.

Lymphatic Drainage

Gall bladder drains into the cystic node at the junction of the cystic and common hepatic ducts (lymph node of *Lund*); from here to the '*node of the hiatus'* and posterior pancreaticoduodenal nodes. The *pericholedochal nodes* get their afferent lymphatics from extrahepatic bile duct and right lobe of the liver (**Fig. 22-53**).


Cystic node of Lund
Node of the hiatus
Superior pancreaticoduodenal nodes
Posterior pancreaticoduodenal nodes

Fig. 22-53: Lymphatics of biliary system.

Bile

Daily up to 1000 mL of bile is secreted from the liver which contains water (98%), bile salts, bile pigments, fatty acids, lecithin, cholesterol, and electrolytes (sodium, potassium, chloride, bicarbonate, calcium, magnesium) with a pH more than 7.0. Main function of gallbladder is to concentrate and store the bile. Capacity of gallbladder is 40-50 mL. Bile salts form micelle which makes cholesterol soluble. Bile salts (i.e. salts of cholic and chenodeoxycholic acids) with formed deoxycholic acid (in the bowel) enter the enterohepatic circulation to get resecreted in the bile. Bilirubin conjugated in the liver is secreted into the bile, which in the bowel is converted into urobilinogen by bacteria. Urobilinogen gets absorbed in the bowel, enters the liver for resecretion again and part of it is excreted in the urine. Absence of urobilinogen in the urine signifies obstructive jaundice. In the absence of gallstones or any other disease, bile is sterile. Symptomatic gallstone disease shows positive culture for bacteria, commonest being *E. coli* and *Klebsiella*.

Congenital Anomalies of Gallbladder and Extrahepatic Biliary Tree

Anomalies of gallbladder may be in number; form; position.

Absence of gallbladder—rare.

Phrygian cap: A cap-like projection and bend over the fundus of the gallbladder (*Phrygia* is an ancient Asian country—Mongolia) (Liberte cap of French revolution). It is identified in cholecystogram. It is 6% common.

Double/triple gallbladder: Additional one may be intrahepatic. Cystic ducts may join to form a common cystic duct which joins the CBD, or cystic duct of each gallbladder may join separately into the CBD.

Mobile/floating/mesenteric gallbladder: Gallbladder has a long mesentery attached. It may cause torsion. It can cause recurrent abdominal pain. It is also called as gallbladder ptosis. Its incidence is 5%. There are three types of floating gallbladder. (1). Gallbladder is completely invested by peritoneum without mesentery and only attachment between liver and gallbladder is cystic duct and artery. (2). Gallbladder is having complete mesentery. (3). Cystic duct and neck of the gallbladder have mesentery with fundus and body are free hanging and ptosed. Such a ptosed gallbladder can position in iliac fossa, lumbar or pelvic region. Torsion is common in elderly, thin people. Its removal is easier through laparoscopic or open method **(Fig. 22-54)**.

Long cystic duct with low insertion of the cystic duct into CBD near the ampulla is possible. This is important in all pancreatic/biliary/laparoscopic biliary surgeries.

Absence of cystic duct with gallbladder directly entering the CBD through a wide opening near infundibulum.

Accessory cholecystohepatic duct (*duct of Luschka*) may be present (10%) which if not identified and ligated during cholecystectomy will cause biliary fistula/ peritonitis due to continuous leak.

Cystic artery may originate anteriorly (15%) from right hepatic artery/from common hepatic artery.

Very tortuous hepatic artery in front of the origin of the cystic duct is called as *Moynihan's caterpillar hump*. It is important cause of bleeding in cholecystectomy.

There may be *double cystic duct* or cystic duct may insert high into the common hepatic duct or right hepatic duct.

Aberrant hepatic duct is a normal segmental duct that joins the biliary tract just outside the liver instead of just within. It drains normal portion of the liver but travels hepatocystic triangle and may get injured during cholecystectomy **(Figs 22-55 to 22-78)**.



Figs 22-54A and B: (A) Laparoscopic view of gallbladder mesentery; (B) diagrammatic look.



Here cystic duct joins separately down into the duodenum directly without any communication to the CBD. This situation is called as 'absence CBD'.

Fig. 22-55: Absence common bile duct; here cystic duct joins duodenum separately.



Fig. 22-56: Absence common hepatic duct; here right and hepatic ducts join at the confluence where cystic duct joins the bile duct.



Fig. 22-57: Cystic duct is absent with wide communication into CBD. There is higher chance of CBD injury here.



Fig. 22-58: Absent gallbladder.



Fig. 22-59: Accessory cholecystohepatic duct (Duct of Luschka—10%). It may cause bile leak post-operatively if it is not ligated during cholecystectomy.



Fig. 22-60: Double cystic ducts from the gallbladder joining the CBD.



Fig. 22-61: Long cystic duct joining the CBD very low.



Fig. 22-62: Cystic duct joining the right hepatic duct—a variation.



Fig. 22-63: Cystic duct with wide opening into CBD.

PREOPERATIVE PREPARATION AND ASSESSMENT

Outcome in hepatobiliary surgery depends on many factors. (1) *Hepatobiliary function*—Low pressure biliary system with obstruction to all functions of liver cells (synthetic, metabolic, secretory) will be affected. Secretion gets reduced due to increased pressure. If bilirubin is less than 1.5 mg%, mortality is less than 3%; if it becomes more than 20 mg% mortality raises up to or more than 30%. Metabolisms of many drugs are also affected. Bile acid serum level raises and inhibits cytochrome 450 enzymes reducing the oxidation. Albumin, coagulation factors and immunoglobulin synthesis is affected. (2) 50% of obstructive patients have *higher endotoxin level* in blood; it is due to reduced bile salts in intestinal lumen which normally prevents absorption of endotoxins from intestine and bile salts and also inhibit anaerobic bacterial growth. So reduced bile salt causes sepsis and endotoxaemia. That also causes acute tubular necrosis, and *renal failure*. Sludging of bile salts in the renal tubules reduces the tubular function by blockage and aggravates the



Angular cystohepatic junction

Parallel cystohepatic junction

Spiral cystohepatic junction

Spiral cystohepatic junction

Fig. 22-64: Possible different types of cystohepatic junction.



Fig. 22-65: Phrygian (cap) gallbladder.



Fig. 22-66: Gallbladder diverticulum.



Double gallbladder with one gallbladder in right side, normal position and other is on the left side draining into left hepatic duct

Fig. 22-67: Double gallbladder. One may be intrahepatic. It may have separate cystic ducts joining CBD or two cystic ducts join to form single duct to join the CBD. One gallbladder may be on right side, other one on left side.



Fig. 22-68: High position gallbladder.



Fig. 22-70: gallbladder is present only on left side joining left hepatic duct.



Fig. 22-69: Intrahepatic gallbladder.

problem. Mannitol probably and also proper hydration prevents this problem in tubules. (3) *Bleeding tendencies*—Vitamin K absorption from the intestine is reduced due to reduced luminal bile acids in the lumen. It prolongs the prothrombin time. This can be corrected by giving IM or IV vitamin K. Endotoxin absorption is increased due to reduced bile acids in the gut which causes recurrent mild disseminated intravascular coagulation (DIC) and raise in fibrin degradation products. It causes tendency for bleeding during surgery and postoperative period. Additionally defective coagulation factor synthesis, hypersplenism (if there is cirrhosis) and fibrinolysins in circulation aggravates the thrombocytopaenia. (4) *Nutritional deficiencies*—Obstructive jaundice causes severe malnutrition with anorexia and weight loss. Pancreatic head or periampullary pathology causes duodenal obstruction and also poor exocrine and endocrine function of the pancreas. (5) *Altered body resistance and immunity with sepsis*—Obstructive jaundice causes defect in T cell proliferation, phagocytosis, delayed hypersensitivity reaction. It reduces the defensive function of the Kupffer cell to phagocytose and neutralize endotoxins. (6) *Gut endotoxins* are increased due to reduced gut bile acids (bile acids emulsify endotoxins); there will be increased bacterial translocation across the gut; this overall increase the sepsis rate in obstructive jaundice patient. (7) Obstructive jaundice reduces the *activity of propylhydroxylase enzyme* in the skin (enzyme


CBD entering into
pylorus or cardia

Partial duplication
of the CBD

Complete duplication
of the CBD
Here pancreatic duct
and CBD enter the
duodenum separately

Duplication of CBD with one of
the divisions begins from cystic
duct with a communication to
hepatic duct confluence

Duplication with right
and left hepatic ducts
joining separately

Fig. 22-71: Duplications of common bile duct.



Fig. 22-72: Right and left hepatic duct junction is intrahepatic deep to hepatic plate/hilum.



Accessory hepatic duct joining the junction of right and left hepatic ducts

Accessory hepatic duct joining the common hepatic duct near cystic duct junction



Accessory hepatic duct joining the cystic duct

Accessory hepatic duct joining the neck of the gallbladder

Fig. 22-73: Different types of multiple hepatic ducts.

helps proline attachment to collagen) and so diminishes the effective collagen formation and its strength. So burst abdomen and incisional hernia is common. (8) *Cardiac problems*—Obstructive jaundice causes decreased contractility; poor response to drugs; decreased peripheral vascular resistance; hypovolaemia; raised serum bile acids cause diuresis and natriuresis.



Fig. 22-74: Cystic artery originates from right hepatic artery which is anterior to common bile duct.



Fig. 22-75: Moynihan's caterpillar turn/hump is bending of right hepatic artery in front of/close to cystic duct. It may get injured during cholecystectomy causing torrential haemorrhage.

ASSESSMENT

Clinical Assessment

Jaundice (**Fig. 22-79**), fever, chills, urine output, weight loss, mass abdomen to be looked for.

Biochemical and Blood Tests

Liver function tests; serum amylase, lipase; renal function tests; coagulation profile (V, VII, IX, X, prothrombin, fibrinogen); prothrombin time (INR); platelet count; urine-bilirubin, urobilinogen, bile salts; reticulocyte count, osmotic fragility test, Coomb's test. In obstruction—direct bilirubin and serum alkaline phosphatase (very sensitive indicator of obstruction) is raised. But serum alkaline phosphatase is raised in bone diseases also; 5′-nucleotidase and serum


Right hepatic
artery
Cystic artery
Accessory
cystic artery
Accessory right hepatic artery
(arising from superior
mesenteric artery)
Left hepatic artery
Proper hepatic artery
Common hepatic artery
Gastroduodenal artery
Right gastric artery
SMA
A
Right hepatic
artery
Cystic artery
Cystic artery
Accessory/aberrant right hepatic artery
(arising from superior mesenteric artery)
(Replacing normal right hepatic artery
15 — 20%)
Left hepatic artery
Proper hepatic artery
Common hepatic
artery
Gastroduodenal
artery
Right gastric
artery
SMA
B

Here normal right hepatic artery will be present so double right hepatic artery supplies right lobe of liver — 5%

Figs 22-76A and B: Accessory right hepatic artery originates from superior mesenteric artery additional to normally located right hepatic artery; aberrant right hepatic artery arising similarly from superior mesenteric artery but replacing the normal right hepatic artery.



Normal pattern cystic artery

Right hepatic artery is anterior to CBD and cystic artery arises from that

Cystic artery arises from gastroduodenal artery

Cystic artery arises from left hepatic artery



Cystic artery arises from hepatic artery proper

Cystic artery arises from common hepatic artery

Right hepatic artery runs behind the CBD and at upper border of cystic duct near neck of gallbladder giving cystic branch. Right hepatic artery which is >3mm in size and so while ligating or clipping cystic artery one should be careful if cystic artery is wider.

Fig. 22-77: Variations in cystic artery – different from normal.

γ–glutamyl transferase level raise are specific for hepatocytes as they are not found in bone. Serum alanine aminotransferase (ALT; it is predominantly found inside hepatocytes), raise suggests liver injury; degree of liver injury is assessed by serum albumin and prothrombin time. High direct bilirubin more than 20 mg% may suggest malignant obstruction.

Imaging

Plain X-ray abdomen is of less use in identifying the gall stones (10%). It is useful to diagnose biliary fistula, emphysematous cholecystitis.

Ultrasound is good investigation to detect gall stones, and biliary dilatation. Normal size of the CBD is 8 mm; more than 10 mm suggests


Aberrant left hepatic artery
Left gastric artery
Celiac trunk
Aorta
Normal left hepatic artery
Aberrant left hepatic artery
Left gastric artery
Celiac trunk
Aorta

Accessory left hepatic artery arising from left gastric artery; here normal left hepatic artery will be present originating from proper hepatic artery

Aberrant left hepatic artery exclusively arises from left gastric artery; here normal left hepatic artery is absent. This artery should be retained while doing gastrectomy during ligating the left gastric artery

Fig. 22-78: Anomalies of left hepatic artery.



Fig. 22-79: Typical obstructive jaundice.



Fig. 22-80: Ultrasound abdomen showing gallbladder stone and normal sized CBD.

dilatation. However, its accuracy rate is only 80%. Stones in CBD and hepatic ducts are difficult to identify by ultrasound. Ultrasound cannot pick up malignancy which is a differential diagnosis for obstructive jaundice **(Fig. 22-80)**.

CT scan is effective in identifying non-dilated ducts and stones in that. Anatomy is better seen with 90% accuracy. CT is better to rule out malignancy in head of pancreas or periampullary region **(Fig. 22-81)**.

MRI and **MRCP** are better to identify the biliary tree. It gives idea about venous anatomy and parenchymal status **(Fig. 22-82)** .

Endoscopic retrograde cholangiopancreatography (ERCP): Through a side viewing gastroduodenoscope, sphincter of Oddi is cannulated, and dye is injected. Biliary and pancreatic trees are visualised. It is done under C-ARM guidance and sedation like midazolam or propofol anaesthesia. Patient is placed in prone position with the head turned towards right. After passing gastroduodenoscope, sphincter is identified and cannulated. Under visualisation 3 mL of water soluble iodine contrast is injected into the bile duct and pancreatic duct. When cannula goes upwards beside vertebra, it signifies that it is in bile duct; and if cannula goes across the vertebra, it is in



Fig. 22-81: (A) CT scan showing dilated CBD. (B) CT scan showing choledochal cyst.



Fig. 22-82: MRI is a useful method to assess biliary anatomy.

pancreatic duct. ***Indications:*** Malignancy—irregular filling defect; chronic pancreatitis—*'chain-of-lakes'* appearance; congenital anomalies; stones; stricture of biliary tree; choledochal cyst; for sampling of biliary and pancreatic juices for analysis and cytology; brush biopsy from tumour site. ***Therapeutic uses:*** Extraction of stone from biliary duct; Nasobiliary drainage; Stenting of tumour in the CBD or in the pancreas; Dilatation of the biliary stricture; endoscopic papillotomy (**Fig. 22-83**).

Complications: Pancreatitis; Duodenal injury, perforation; cholangitis; bleeding from pancreaticoduodenal artery; sphincter stenosis. ***Relative Contraindications:*** Acute pancreatitis; previous gastrectomy.

Percutaneous transhepatic cholangiography (PTC): It is done in case of severe obstructive jaundice under cover of antibiotics and after control of any bleeding tendency—by giving injection vitamin K or FFP transfusion. ***Indications:*** Failure of ERCP; high biliary strictures; Klatskin tumour; high blocks when external caternal catheter drainage is needed; stenting in high tumours with the help of fluoroscopy (C-ARM)/US/CT guided, *Chiba* or *Okuda needle* which is long, flexible, thin, blunt, without a bevelled end (15 cm long and 0.7 mm in diameter) is passed into the liver through right 8th intercostal space in midaxillary line. Once needle is in the dilated biliary radicle, bile is aspirated (sent for culture, cytology, analysis) and then water soluble iodine dye is injected into the same so as to visualise the dilated biliary radicles, also the site and extent of the obstruction, i.e. tumour, stricture. Procedure can be used for therapeutic stenting across the biliary tree through the obstruction either in the hepatic ducts or in the CBD into the duodenum. It is used whenever ERCP fails, in high strictures (in CHD), in Klatskin tumour, in catheter drainage (external) in high blocks, in stenting high tumours. ***Prerequisites for PTC:*** It should have normal prothrombin time (or should be made normal by injection vitamin K or FFP); should be a last and final inevitable method for evaluation; or therapy; blood for transfusion in case of bleed, consent for intervention in need, antibiotic prophylaxis—are a must prior to PTC. ***Complications*:** Bleeding, biliary leak and biliary peritonitis and septicaemia. PTC has got 95% accuracy rate. It confirms the diagnosis; site and cause of obstruction is determined; specific anatomy is identified.

Note: Chiba is a university in Japan. Okuda is the name of person.

PTBD is percutaneous transhepatic biliary drainage. It can be *external or internal*. It is done through PTC.

Preoperative cholangiogram: It is done during CBD exploration for stricture, residual CBD stones, atresia, choledochal cyst, cholangitis. Fine polythene catheter is passed into the CBD through cystic



Fig. 22-83: Endoscopic retrograde cholangiopancreatography (ERCP).

duct and dye is injected. *Under C-ARM image-intensifier*, any block or stricture can be identified and completion of the procedure can be confirmed. ***Complications:*** Infection; bile leak. ***Precaution:*** Air should not be present in the syringe, as it may mimic stones **(Fig. 22-84)**.



Fig. 22-84: Preoperative cholangiogram. Fine catheter is passed through cystic duct into the CBD. Care should be taken to avoid air getting into the CBD (it will mimic stone). Dye is injected under C-ARM guidance.

Post-operative T-tube cholangiogram: After choledochotomy, *Kehr's T-tube* is *placed in CBD for 14 days* and then water soluble dye is injected into the tube and X-ray is taken. Complete free flow of dye into the duodenum indicates that there is no blockage. T-tube can then be removed safely. Block indicates residual CBD stones. **Residual CBD stones are removed by:** Dormia basket; Fogarty's catheter; Choledochoscope; ERCP.

Biliary scintigraphy: Technetium 99m labeled iminodiacetic acid is (HIDA/PIPIDA) injected IV; it is secreted in bile to give functional nature. It is used in neonatal jaundice, biliary fistulas, acute cholecystitis. It assesses the patency of bile flow like in biliary enteric anastomosis.

Celiac and superior mesenteric angiography: It is useful in bleeding varices in cirrhosis. It is done prior to porta systemic shunt surgery; therapeutic vasopressin injection; diagnosis of hemobilia; during selective embolisation in haemobilia and hepatic artery pseudoaneurysm (postoperative). It can access the resectability of biliary cholangiocarcinomas. It also detects the vascularity and encasement of the major vessels like mesenteric vein and portal vein.

Endoscopic ultrasound (EUS): It detects tumour, its infiltration, lymph node status. Normal lymph node is hyperechoic and indistinct; metastatic lymph nodes are hypoechoic and well-defined. Needle aspiration cytology of lymph node can be done through the EUS.

Laparoscopy

Laparoscopy and laparoscopic ultrasound is very useful in staging the cancer on table and determine the encasement, operability, vessel invasion, peritoneal deposits.

Risk Factors in Obstructive Jaundice

Age >60 years; temperature; haematocrit <30%; leukocytosis; hypoalbuminaemia; raised serum bilirubin, alkaline phosphatase, blood urea nitrogen, serum creatinine, malignant obstruction. Sepsis, renal status, nutrition are most important factors.

Little's mortality index

Mortality score = (0.0016 × serum creatinine in μ mol/L) – (0.0227 × albumin g/L) + (0.0641 × cholangitis score) + 0.6935.

Cholangitis score: 0 – afebrile; 1 – temperature < 37.5°C; 2- > 37.5°C without rigors; 3 - > 37.5°C with rigors and right upper quadrant pain; 4 – fever with shock and or mental changes.

Note: An index of 0.5 or more is associated with high risk for death

PREOPERATIVE PREPARATION

Preoperative hyperalimentation is required if serum albumin is less than 3 gram%; 20% of weight loss; serum transferrin level less than 200 mg%. Adequate hydration either orally or intravenously using normal saline is a must.

Prolonged prothrombin time is common; it is corrected by injecting vitamin K 10 mg IV or IM once a day daily for 5 days; prothrombin time is repeated after 5 days; often fresh frozen plasma is needed to correct the prothrombin time. Platelet infusion is also required often if DIC is anticipated. Epsilon Amino Caproic Acid (EACA) may be useful with shortened clot lysis time and hypofibrinogenaemia.

Renal function should be maintained properly in obstructive jaundice patients by adequate hydration; mannitol therapy; oral bile salts may reduce endotoxin absorption from gut and so its toxic effects on kidney.

Sepsis with cholangitis is a real threat in obstructive jaundice. Such patient (toxic cholangitis—with mental changes and hypotension) requires higher generation antibiotics and emergency decompression of biliary system by ERCP and stenting; otherwise it is life-threatening. Normally bile and biliary systems are sterile. Stasis, obstruction, enteric anastomosis, foreign body precipitates biliary sepsis. *E coli*, *Klebsiella*, *Enterococcus* and *Bacteriodes fragilis* are common organisms found in biliary tree with sepsis. Bile culture, ability of antibiotics to excrete in bile, concentrations in liver and blood; toxic effects are the parameters to decide type of antibiotics chosen. Piperacillin and tazobactum is quiet effective. Prophylactic antibiotics should be given if patient is undergoing surgery or ERCP or otherwise.

Preoperative biliary drainage through transhepatic route in obstructive jaundice routinely is not necessary but in selected patients with severe obstructive jaundice, it may be beneficial.

Cardiac and respiratory problems can occur; detailed cardiac and respiratory evaluations are needed with respiratory physiotherapy.

CHOLECYSTECTOMY

In 1743, Jean Louis Petit did first cholecystostomy for gall stones. Until 1882, cholecystostomy was the procedure used to be practiced for gall stones. In 1882, Carl von Langenbeck did first cholecystectomy. In 1985, Prof Erich Muhe of Boblingen from Germany did first laparoscopic cholecystectomy which he presented in congress of

German surgical society. In 1987, Mouret of Lyon, France reported first laparoscopic cholecystectomy. Jacques Perissat (France) presented first paper on laparoscopic cholecystectomy.

Indications

Gallstones—symptomatic; cholecystitis—acute, chronic; acalculous cholecystitis; empyema gallbladder; mucocoele of gallbladder.

Prophylactic cholecystectomy is done in diabetic patients; congenital haemolytic anaemia; patients who has underwent bariatric surgery; while giving intraarterial chemotherapy through hepatic artery.

Approaches

Open method

Different incisions are—Right subcostal incision (Kocher's); Kehr hockey stick modification (medial end is extended upwards towards xiphisternum); upper midline incision; right paramedian; horizontal incision; Mayo-Robson incision. Right subcostal incision is commonly used.

Open approach is done when laparoscopic approach is not possible; or during laparoscopy difficulty arises and so conversion has been done to open method (failed laparoscopy); or if patient is not fit for general anaesthesia or for pneumoperitoneum **(Figs 22-85 and 22-86)**.

Laparoscopic Approach

Laparoscopic cholecystectomy has become standard and ideal **(Fig. 22-87)**.

Preoperative Preparation

Evaluation by liver function tests, prothrombin time, diabetes, ultrasound (CBD should be assessed properly including its diameter); CT scan when needed to assess the biliary tree, pancreas; gastroduodenoscopy if hiatus hernia, oesophageal varices (portal hypertension) is suspected. If CBD stone is present, ERCP and stenting should be done prior to laparoscopic cholecystectomy. If open cholecystectomy is planned then CBD exploration should be planned in these patients. Preoperative antibiotics are also necessary in cholecystectomy. Cardiac and respiratory assessment is required in these patients. Heparin as a prophylaxis for deep vein thrombosis may be a need.



Fig. 22-85: Gangrene of gallbladder is probably a sure indication of open cholecystectomy. But presently even such gallbladders can be removed laparoscopically by an experienced skilled laparoscopic surgeon only. Learner should convert such gallbladder into open method rather than inviting trouble.



Fig. 22-86: Technique of open cholecystectomy.

TECHNIQUE OF OPEN CHOLECYSTECTOMY

General anaesthesia or epidural anaesthesia is used. Nasogastric tube and urinary catheterisation is passed. Patient is in supine position. C-arm image intensifier/fluoroscopy should be kept in place or cassette changer top should be placed underneath the patient at the level of surgical field. Preoperative antibiotics are given – tazobactum or amoxicillin as common organisms are *Escherichia Coli* and *Streptococcus faecalis*. Heparin should be injected subcutaneously to prevent formation of deep venous thrombosis. Cleaning of entire abdomen is done; draping is done in the incision area. Surgeon stands on the right side; two assistants on left side; during retraction of right costal margin, if needed, one assistant may have to come to right side towards left of the operating surgeon.

Incision: Right subcostal incision is used – 2 cm below the right costal margin. Skin, subcutaneous tissue, external oblique, internal oblique and transverse abdominis muscles are cut (transverse abdominis is often thin and can be split also). Medially rectus sheath is incised up to the midline; a haemostat is passed underneath the rectus muscle and is cut using monopolar cautery. 9th intercostal nerve is divided where it emerges lateral to the rectus muscle border. It causes only slight skin hypoesthesia but not muscle weakness (if possible it can be retained). Vessels underneath should be fulgurated. Rectus muscle after dividing will not retract in upper abdomen due to presence of tendinous intersections. Peritoneum is opened. Peritoneal cavity is explored. Oesophageal hiatus, gallbladder, pancreas, duodenum should also be palpated **(Fig. 22-88)**.

Retraction: Right hand is placed between liver and diaphragm to retract liver downward and allow air to enter above the liver causing


1
2
3
4
5
6
Commonest incision used for open — Kocher's
5 mm
10 mm
5 mm
Additional 5 mm port if needed
10 mm
North American approach
1. Kocher's subcostal incision
2. Kehr's hockey stick incision
3. Horizontal incision
4. Right paramedian incision
5. Mayo Robson incision
6. Upper midline incision
Open method incisions
10 mm
5 mm
5 mm
10 mm
French/European approach — semilithotomy
Laparoscopic approach — Port positions

Fig. 22-87: Incisions for open and laparoscopic cholecystectomy.



Fig. 22-88: Kocher's right subcostal incision for cholecystectomy.

downward displacement of liver to make gallbladder more visible. Often colon and duodenum may be adherent to the gallbladder, they should be dissected by sharp and finger dissection. Colon is pushed downwards; duodenum and stomach medially. Care should be taken not to injure the colon or duodenum. Moist mops are kept on the colon and it is retracted downwards using a Deaver's retractor; another moist mop is kept on the stomach and duodenum and is retracted medially towards left using another Deaver's retractor. Right costal margin is retracted upwards using an abdominal wall Morris retractor with a moist mop underneath. Liver is often retracted upwards from left of the falciform ligament or medial to the gallbladder using another Deaver's retractor **(Fig. 22-89)**.

Often gallbladder is very tense due to mucus or pus or bile which needs aspiration so that gallbladder is made easier to hold and handle **(Fig. 22-90)**.

Two Methods Used for Cholecystectomy

Duct—first method (Calot's first method): Here *Calot's triangle* is dissected. Cystic artery is identified and ligated. Cystic duct is ligated close to the gallbladder. Gallbladder is separated from gallbladder fossa and removed. Haemostasis is maintained. Usually Calot's first method is used.


Retraction of upper wound — rib cage
Retraction of liver left of the gallbladder if need arises
Medial retraction of the stomach and duodenum
Fundus is held upwards and right;Hartmann's pouch is held downward and right
A
Retraction of the colon downwards
B
Acute cholecystitis
Retraction for cholecystectomy
C

Figs 22-89A to C: (A) Method of retraction in open cholecystectomy and CBD exploration—below to the colon; (B) Medially to stomach and duodenum; (C) Above towards left of gallbladder on liver.



Fig. 22-90: Aspiration of the gallbladder is done if gallbladder is tense.

Fundus—first method: It is done in difficult gallbladder due to dense adhesions. Fundus is separated from the liver bed. Dissection is carried proximally until cystic duct and cystic artery are identified, which are then ligated.

Calot's First (Conventional; Below Upward) Method

Fundus of the gallbladder is held with Babcock's or sponge holding forceps or gallbladder holding forceps. Traction is given to fundus upwards and towards right (outwards). Hartmann's pouch is held with another Babcock's or sponge holding forceps and traction is given downwards and outwards.

In the Calot's triangle, peritoneum is incised using long curved scissor to expose the cystic duct and artery. With fine dissection using peanut (pledget in haemostat), haemostat and right angle clamp Calot's triangle is dissected to identify the cystic artery, cystic duct, and junction where cystic duct joining the common bile duct. Cystic duct lymph node of Lund will be seen in Calot's triangle lying on the top of cystic artery.

Two silk or vicryl ligatures are passed around the cystic duct. Any stones in the cystic duct are felt and milked proximally into the gallbladder. Entire length of the cystic duct is dissected using sharp and finger dissection. Ligature close to the Hartmann's pouch is ligated (**Fig. 22-91**).

Technique of cystic duct cholangiography—Distal ligature is not ligated instead is held apart with stretching. Cystic duct is incised near its beginning close to the gallbladder just distal to the tied ligature. A fine plastic tube (or infant feeding tube no 5-8 or ureteric catheter) or



Cystic artery and duct are dissected meticulously. Anomalies should be kept in mind. Cystohepatic junction should be identified. Cystic artery is ligated first (proximally double)





Intraoperative (on table) cystic duct cholangiogram is done
- Avoid air bubble
- 1:1 sodium diatrizoate with warm saline 50 ml
- Avoid concentrated dye
- Assure that entire biliary tree is filled with dye
- If sphincter spasm is present NTG or glucagon can be injected



Cystic duct is doubly ligated. Care should be taken to avoid inadvertent placing of the ligature on to the CBD due to traction or kink


Double ligatures
Transfixation
Simple ligature

Both cystic artery and cystic duct are doubly ligated
- Cystic duct is often transfixed towards stump side; proximally simple ligature is applied



Neck of the gallbladder is held laterally
Gallbladder is dissected off from the liver bed using cautery, scissor and finger dissection
One should avoid opening the liver parenchyma
Bipolar cautery may be used


Cystic duct and artery — stumps
Gallbladder bed

Gallbladder bed after removal of gallbladder is inspected for bleeding; small bleeders are fulgurated; often surgical, if needed, may be placed on the bed. Safety of CBD is again confirmed. Mops are removed with proper count. Tube drain may be placed if indicated. Wound closed in layers using no. 1 vicryl


Retraction of liver upwards and left
Retraction of stomach and duodenum medially
CBD
Cystic duct stump
Retraction of colon below

Fig. 22-91: Calot's first method of open cholecystectomy.

cholangiogram catheter (which has got a bead at the tip) of 2 meter length with 50 mL syringe filled with dilute sodium diatrizoate (1:1 with normal saline; 25 mL saline + 25 mL dye). Entire syringe and plastic tube should be devoid of air bubble—very important. Plastic tube negotiated across the cystic duct for 5 mm close to bile duct. Narrow lumen or valve of Heister in the cystic duct may cause difficulty in negotiating the tube. Distal ligature is tied on the catheter with cystic duct. Bile should not be aspirated into the tube to prevent air bubble formation; if surgeon wants to confirm that tip is inside the lumen gently small quantity can be aspirated with care. Left side of the theatre table is tilted upwards for 10 cm to avoid superimposition of the bile duct image with vertebrae. If C-arm is available, dye is injected and under fluoroscopy guidance; bile duct is visualised and also flow into the duodenum. A radiolucent area is identified as common bile duct stone. Often dye will not enter the duodenum due to sphincter spasm; in such situations small dose of nitroglycerin or 1 mg of glucagon intravenously will relieve the spasm to allow the dye to pass into the duodenum. Even with this, dye has not entered the duodenum, then bile duct exploration is indicated. *Findings* to be observed in the cholangiogram are—diameter of the bile duct, any radiolucent area in the biliary tree, status of hepatic ducts, smooth tapering at ampulla of Vater and free flow of dye into the duodenum. Cystic duct cholangiogram ensures and confirms ductal anatomy, may aid in limiting the ductal injury (even though it may not prevent) and decides need for common bile duct exploration.

If C-arm image intensifier is not available, initially 4 mL of dye is injected to take first X-ray film; 2nd X-ray film is taken after injecting remaining part of the dye.

Intraoperative cholangiogram

- Cystic duct cholangiogram—commonly used
  - Real time fluoroscopy—ideal
  - Static film technique—two films should be taken
  - Needle technique in laparoscopic cholecystectomy percutaneous needle is used
- Gallbladder cholangiography
- Infundibular approach (Kumar's)

Precautions while doing cystic duct cholangiography are—avoiding injecting more quantity and more concentrated contrast material as this will cause missing of small calculi and duodenum will be flooded with dye; air bubble should be avoided compulsorily; entire biliary system should be visualised including hepatic ducts; correction of sphincter spasm by drugs while doing the study if needed.

Cystic artery is doubly ligated using silk and divided. Usually cystic artery is above the level of cystic duct and in slight posterior plane than the cystic duct. Cystic artery is in close proximity to liver. Cystic artery should be adequately dissected for about 1 cm using right-angled Mixter instrument; often its branches may need to be ligated independently. Any variations, if possible, should be kept in mind. In adhesions, dissection of artery may take time; as far as possible artery should be dissected and ligated. Occasionally, in dense adhesions where dissection is not possible, then mass ligation may be done if it seems mandatory; but it carries higher chance of ligating or injuring right hepatic artery or hepatic duct. While dissecting the cystic artery, artery may get torn inadvertently; then blind clamping the area with haemostat should be avoided; instead a mop is kept in the place with pressure and after proper retraction and lighting, mop is gently removed to identify the bleeding proximal end of cystic artery which is held with right angle and carefully ligated. Often in such situation, bipolar cautery fulguration helps in controlling the bleeding. If identification of cut end of cystic artery is still difficult, the incision should be extended medially or upward medially towards xiphisternum to get adequate exposure. Too large a cystic artery, if present, it is unlikely to be; rather it could be right hepatic artery (3 mm or more in diameter). *Cystic artery should be ligated first* to allow subsequent Calot's dissection easier; to make cystic duct straight by eliminating the convolutions; to avoid its tearing due to traction on the gallbladder. Accessory cystic artery may be present in anomalous position.

Bile duct should not be extensively dissected unnecessarily; but cystohepatic junction should be delineated properly. Monopolar cautery should be avoided close to bile duct; bipolar cautery is suitable.

Once bile duct exploration is not under strategy, then *cystic duct is doubly ligated* proximally after removing cholangiogram catheter. Simple ligature is placed using vicryl or silk close to cystohepatic junction; just distal to its transfixation suture is placed. Cystic duct is divided. It is *ideal* to place ligatures and then divide the cystic duct rather than clamping, dividing and then ligating the duct. Many feel that cystic duct ligation is done only after complete mobilisation of the gallbladder from liver bed. However, if dissection is adequate in Calot's and assured then cystic duct can be ligated safely prior to dissection of gallbladder from liver bed.

Dissection of the gallbladder from the liver bed: Usually it is easier to dissect the gallbladder from the liver by giving traction to fundus and Hartmann's pouch. Cystic duct stump is held with a haemostat to give outward traction to make peritoneal fold between gallbladder and liver stretched and fold is incised to proceed with the dissection. Dissection should be close to the gallbladder wall without injuring the liver tissue. Dissection begins from Calot's area towards fundus. Dissection is done using scissor or monopolar cautery or using peanut. Plane of dissection is deep to mucosa of the gallbladder. All small bleeders from the liver surface should be fulgurated. Care is taken to look for direct entry of accessory duct from liver to gallbladder; if present, should be ligated securely to prevent bile leak. After removal of gallbladder, mop is kept in place for few minutes. Often gelfoam or surgical may be kept to prevent oozing from the liver bed. Occasionally *under running of the bleeding point* using 4-0 vicryl may be useful. Catching with a haemostat and ligating should not be attempted in liver bed.

Complete haemostasis is achieved. Common bile duct is again palpated for confirmation that stones not missed. It is done by palpating supraduodenal portion of the common bile duct and also pancreatic portion by placing fingers behind the second part of the duodenum. Mops are removed; counts should be checked **(Figs 22-92 and 22-93)**.

Tube or Jackson Pratt closed suction drain is placed when there is acute cholecystitis or in difficult gallbladder surgery. Abdominal wall is closed as single or two layers using vicryl. Skin can be approximated using stapler or nylon.

Fundus First Method (Above Downward)

Here after opening the abdomen and exposure with proper retraction instead of dissecting the Calot's, fundus of the gallbladder is held with sponge holding forceps. Using sharp scissor or monopolar cautery, fundus and body of gallbladder is dissected from its liver bed from fundus, to begin with, towards neck and Calot's triangle. Blunt dissection using peanut or suction apparatus is very useful. One should avoid entering the parenchyma of liver. It is done in difficult cases wherein Calot's is difficult to dissect to begin with. Fundus first method



Cleaning and draping

Incision

Cutting rectus muscle

Exploration

Pulling down the liver to allow air to enter over liver

Exposing the gallbladder area with proper retraction of liver (left side), colon below, duodenum and stomach medially

Holding the gallbladder fundus with sponge holding forceps

Figs 22-92(1)


Holding Hartmann's pouch
to retract down and right
Calot's dissection
Bipolar and suction
dissection at Calot's
CBD
Hartmann's with stone
Bipolar and suction dissection
Separating the GB from liver
bed using monopolar cautery
GB
Cystic artery
CBD
Cystic duct
Hartmann's pouch
GB
Cystic
artery
CBD
Cystic duct

Figs 22-92(2)


Ligating the cystic artery
Division of cystic artery
CBD
Feeding cystic duct
Feeding the cystic duct with vicryl suture
Cystic duct
Ligating the cystic duct
Cystic duct is ligated with silk/vicryl
One more ligature is placed distally

Figs 22-92(3)



Transfixation of cystic duct using vicryl which is often also done after dividing cystic duct — becomes easier

Two proximal ligatures; one distal ligature

Cutting cystic duct with blade or scissor

Dissecting GB from its liver bed from Calot's to fundus

Stone at Hartmann's

Duct cholangiogram is not done in this patient as already choledochotomy is decided as confirmed CBD stones with failed ERCP

Dissecting GB from its liver bed from Calot's to fundus

Figs 22-92(4)


Cystic artery
CBD
Cystic duct
Closure of Kocher's incision
Closed right subcostal incision
Tube drain-optional
Gallbladder with multiple stones

Figs 22-92(5)

Figs 22-92(1 to 5): Open cholecystectomy—steps. In one patient after difficult Calot's dissection, gallbladder is separated from liver bed from fundus towards Calot's then cystic duct is ligated. In another patient, Calot's is addressed with ligation of cystic artery and duct, and gallbladder is separated from Calot's towards fundus (from its liver bed).

ensures that common bile duct and hepatic ducts will not be injured. But oozing from the liver bed makes further dissection cumbersome. Once Calot's is reached, cystic artery is ligated and divided. Cystic duct is ligated doubly after doing cystic duct cholangiography by similar method.

Postoperative Care

Nasogastric tube is removed within 24 hours unless there is paralytic ileus. In infected gallbladder, antibiotics are continued. Drain when kept is removed in 4 days.



Fig. 22-93: Specimen of gallbladder with cholesterol stone.

Precautions

Size of the common bile duct should not be overestimated; often it is small enough to mimic the cystic duct and inadvertent ligation by mistake is known to occur. Kinking at cystohepatic junction due to traction can cause clamping the junction with bile duct partially and completely.

Anomalies of cystic duct (short or long; may enter right hepatic duct), of right hepatic duct; presence of accessory ducts should be remembered.

Cystic artery while ligating care should be taken of variations of right hepatic artery and chances of ligating the right hepatic artery. Any artery if more than 3 mm in size, one should suspect it as right hepatic artery.

Cystohepatic junction should be identified and dissected prior to ligation of the cystic duct. Caterpillar hump of right hepatic artery is known to exist and easily gets injured while dissecting.

Dissection of gallbladder from liver bed often may be troublesome and is also should be meticulous. It is often observed that surgeon relaxes while dissecting the gallbladder from its bed once Calot's is addressed properly.

Blind clamping and ligation should not be undertaken.

If needed, incision should be *extended* accordingly.

Cystic duct cholangiogram ideally should be done in all cases even though it is not practiced by many surgeons routinely.

Cholecystitis in pregnancy: Ideally if possible cholecystectomy should be postponed and is done 3 months after delivery. If there is secondary choledocholithiasis or if it becomes inevitable then ideal timing to do surgery is 2nd trimester. Cholecystectomy is safer. But if bile duct exploration is needed cholangiogram whether to be done or not is a debate. It is said that X-ray is safer after 1st trimester. Even then uterus shield should be used if cholangiogram is done. Bile duct stone after choledochotomy can be removed using choledochoscope. CT imaging should be avoided in pregnancy. Ultrasound is the main imaging modality in pregnancy. MRI is safer. Laparoscopic cholecystectomy is becoming an accepted method in 2nd trimester but needs expertise; open trocar placement; low pressure surgery and keeping PCO_2 less than 40 mm Hg are the essential measures to be taken. Fetal monitoring during surgery, obstetrician help and follow up fetal monitor in immediate post-operative period is needed.

Cholecystectomy in cirrhotic patients*:* In cirrhotics, selection of the patient is important. Liver will be nodular. All adhesions are vascular and often bleed profusely. Dissection of the gallbladder from the liver bed may create technical problems. Preoperative preparation should be adequate like—injection vitamin K; fresh frozen plasma transfusion, platelet transfusions, antibiotic therapy. Even then *laparoscopic cholecystectomy is better than open approach in cirrhotics.* Fundus first method should be used in cirrhotics; harmonic scalpel or other energy sources should be used. Doing partial cholecystectomy by ligating at the of Hartmann's pouch is much safer than dissecting Calot's. Often conversion is needed; still often limiting the procedure towards cholecystostomy may be a compulsion due to technical hurdles. In cirrhotics, one should avoid placing T tube as localisation and track formation is poorer and chances of biliary peritonitis are higher. If at all. T-tube is placed then critical postoperative care is needed. T tube should be removed only after 4 weeks. Profuse bleeding from the liver bed in cirrhotics is a real matter of concern. Often it is difficult to achieve adequate required haemostasis and keeping a pack/mop in the bed to achieve compression for 24-48 hours is the only choice; such packs should be removed in 48 hours under anaesthesia gently with all precautions. Posterior part of the gallbladder can be left alone like that removing only remaining parts. Mucosa of such left out difficult gallbladder is ablated using ideally argon laser or bipolar cautery. Opening of the cystic duct is invaginated using absorbable 3-0 suture material like vicryl.

In patients with coagulative disorders, cholecystectomy should be done by keeping ready adequate number of units of frozen plasma or platelets or factor VIII depends on the type of coagulopathy patient harbours.

Complications

Injury to colon, duodenum and mesentery can occur whenever there are adhesions.

Bile leak: It is the most distressing complication surgeon faces. Small bile leak through the drain is probably due to either cystic duct stump disruption or accessory duct leak. Usually it is 100-200 mL/day. It usually subsides in 7-10 days. If leak persists ERCP and stenting is needed; it also identifies the bile duct and hepatic duct status. If bile leak is more than 400 mL/day it means probably it is bile duct or hepatic duct injury. It needs proper evaluation with CT scan/MRCP. It is addressed only at a later period once inflammation subsides after 3 months. Nutrition during this period should be maintained adequately. It needs expertise work and needed proper identification, dissection of biliary tree and hepaticojejunostomy **(Figs 22-94 and 22-95)**.



Inadvertent clamping of the bile duct below and hepatic duct above during cystic duct ligation is possible

Fig. 22-94: Injury to bile duct can occur if inadvertent clamping has occurred.



Fig. 22-95: Bile leak after open cholecystectomy.

Post-cholecystectomy jaundice may be due to cholangitis, missed bile duct stones, bile duct stricture due to trauma or ligation of bile duct or hepatic duct. ERCP, liver function tests proper imaging to identify the problem are needed to plan the eventual surgical correction.

Post-operative bleeding is not common. But can occur if cystic artery ligature is slipped or if there is sepsis at the gallbladder bed. Occasionally it could be due to anomalous right hepatic artery which is injured due to inability to identify the vascular anomaly. Infection may cause hepatic artery pseudoaneurysm which may often be life-threatening. It needs CT angiogram and intervention radiology to address the feeding artery of the pseudoaneurysm by glue or other embolisation devices. However, inadvertent embolisation or gluing of the right hepatic artery may cause acute fulminant hepatic necrosis of the liver and may kill the patient. Hogarth Pringle's manoeuvre is ideal to control bleeding on table by applying pressure using thumb and fingers over the Foramen Winslow.

Sepsis: Subphrenic, pelvic, hepatic abscess can occur occasionally when there is cholangitis, immunosuppression or if surgery done in a badly infected gallbladder. Blood culture, blood count, clinical assessment is a must. Higher generation antibiotics should be started to prevent them going for septicaemia. Abscess can be addressed usually by image guided catheter drainage or aspiration. Open drainage is needed only rarely.

Biliary stricture can occur as late sequelae after cholecystectomy due to bile duct injury. 80% of biliary strictures are post-operative. After cholecystectomy [open or laparoscopic, more common following laparoscopic (0.8%) than open method (0.35%)]. ***Clinical features are*****:** Obstructive jaundice; pain abdomen; features of ascending cholangitis; profuse persistent bile leak.

Waltmann Walter syndrome – It is compression of IVC due to collection of fluid in gallbladder fossa and subphrenic space after cholecystectomy; it mimics coronary artery thrombosis.

Bismuth classification of biliary stricture (Fig. 22-96)

- I. Low CBD stricture with stump (proximal to stricture) >2 cm
- II. Middle CBD stricture with proximal stump <2 cm
- III. Hilar. Confluence of right and left hepatic ducts is intact
- IV. Separated right and left hepatic ducts
- V. Stricture involving intrahepatic ducts

Causes of post-operative stricture

- Too much traction to the GB during ' Fundus first cholecystectomy'
- Blind application of artery forceps in Calot's to control bleeding
- Anomalies of biliary tree
- Inflammatory adhesions at Calot's triangle
- Injury during other surgery like gastrectomy

Management

LFT, prothrombin time, ERCP, CT, MRCP; choledochoduodenostomy or choledochojejunostomy.

Minilaparotomy Cholecystectomy

Here incision of 5 cm length is made lateral to the right rectus in subcostal region. It is done in olden days in thin individuals where



Fig. 22-96: Bismuth classification of biliary stricture.

easy retraction makes Calot's dissection possible. In present era of laparoscopic surgery, minilaparotomy cholecystectomy or any other surgeries should not be done. When open surgery is done, adequate incision with adequate exposure of the dissecting surgical field should be the approach. Hence minilaparotomy has become a surgical legacy.

Partial Cholecystectomy

It is done in severely adherent Calot's triangle difficult for dissections and biliary tree cannot be delineated. It is also useful in cirrhosis with portal hypertension. Here gallbladder is removed distal to the Calot's triangle at Hartmann's pouch level. When there is dense adhesion in the Calot's and dissection is impossible, it is better to do partial cholecystectomy than injuring the bile duct or hepatic artery to lead into dreaded complications. Fundus first dissection is done carefully. When reaching towards the Calot's, care should be taken not to meddle and create complications. Hartmann's pouch is held with Babcock's forceps. Tissue just behind the Hartmann's is ligated and divided. Hartmann's pouch is divided. Gallbladder is removed. Any stones in the Hartmann's are removed; warm saline wash is given. Usually in such situations, cystic duct already sealed without communicating into the bile duct. Mucosa of the retained part of the Hartmann's pouch is fulgurated using bipolar cautery or argon laser. Hartmann's pouch on the cystic duct side is transfixed and ligated using vicryl **(Fig. 22-97)**.

Subtotal cholecystectomy is a similar procedure but it is divided still further away from the Hartmann's pouch at the beginning of the body of the gallbladder. Technically there is hardly any difference.

CHOLECYSTOSTOMY

It is the drainage of the gallbladder exteriorly. It is only a life-saving procedure; not a definitive procedure.

Indications

It is done during process of surgical cholecystitis if cholecystectomy seems not possible with acute cholecystitis or empyema gallbladder or on table anaesthetic problem causes compulsion to terminate the definitive procedure. After cholecystostomy, once patient recovers, definitive procedure of cholecystectomy should be done.



Fig. 22-97: Partial cholecystectomy.

Cholecystostomy is done only in critical ill patients who are on severe sepsis and renal failure **(Fig. 22-98)**.

In olden days, in periampullary carcinoma or carcinoma head of the pancreas with severe obstructive jaundice with bilirubin as high as 30 mg% and general condition is really poor and eventual definitive resectable procedure like Whipple's is feasible, cholecystostomy as initial decompression procedure is done. Nowadays, in carcinoma pancreas as if operable, Whipple's operation is done otherwise bypass is done and because of the availability of ERCP, cholecystostomy is rarely done nowadays.

Technique

If cholecystostomy is not decided on table during laparotomy, then right subcostal incision of 5 cm length is made under general or local anaesthesia abdomen is opened; liver is pushed down by placing hand over the liver; gallbladder is identified and felt; it is held with Babcock's forceps. If gallbladder is tense it should be aspirated; otherwise using trocar and cannula contents are decompressed. Fluid should be collected for culture.

Two stay sutures are placed on the fundus of the gallbladder. Gallbladder is incised for about 1 cm in between stay sutures. Contents are aspirated after collecting for culture. All stones are removed using stone removal instruments (Randall stone removal forceps). Warm saline ash is given properly into the gallbladder. Finger is passed into the gallbladder to milk out all stones and contents. Foley's or Malecot's or de Pezzer catheter 22-24 sized is passed into the gallbladder. Purse string suture is passed around the tube by taking bites through the fundus of the gallbladder around the gallbladder. Additional interrupted sutures if needed should be placed. Tube can be brought out through the omentum or omentum may be wrapped around it to reduce the chance of leak. Through a separate stab wound tube is brought out of the abdominal wall. Often tube is also fixed to abdominal wall from inside by placing interrupted sutures between parietal peritoneum and fundus of the gallbladder. Tube is fixed outside using skin suture.



Fig. 22-98: A Foley's or Malecot's catheter is placed in severely ill patients with acute cholecystitis to drain pus initially, and later elective cholecystectomy is done. Procedure is done in elderly, severely ill, empyema GB, emphysematous GB, perforation of GB (cholecystostomy).

Problems

If there is necrosis or gangrene of the gallbladder then cholecystostomy is contraindicated as necrosed part will disrupt and cause biliary peritonitis.

It is totally contraindicated in acute cholangitis where, when there is obstruction ERCP is a must.

Perse cholecystostomy is not done nowadays as in these patients alternatively percutaneous drainage under guidance serves same purpose.

If cystic duct is already blocked by fibrosis cholecystostomy will not function as a bile drainage system. But sepsis will come under control to lead into eventual definitive cholecystectomy.

LAPAROSCOPIC CHOLECYSTECTOMY

Laparoscopic cholecystectomy is the standard technique for removal of gallbladder.

Indications

- Symptomatic gall stone diseases – pain, mucocoele, cholecystitis acute or chronic.
- Acalculous cholecystitis.
- Asymptomatic gall stones—when patient is undergoing bariatric surgery, diabetics, renal transplantation, haemolytic diseases, in children.
- Complications of the gall stones like gall stone ileus, empyema, and perforation also can undergo laparoscopic cholecystectomy; but conversion rate may be more. If during laparoscopic procedure, when dissection becomes difficult surgeon should not be hesitant to convert into open cholecystectomy to avoid serious complications.
- Gall stone dyspepsia where biliary pain is present without the presence of gall stones. Here patient may get relieved of the symptoms by laparoscopic cholecystectomy. Biliary dyskinesia may be an indication.
- Gall bladder polyps—if polyps are multiple, if they are increasing in size, if size is more than 1 cm then laparoscopic cholecystectomy is indicated.

Contraindications

There is a debate about absolute contraindication for laparoscopic cholecystectomy. Patients who are unfit for general anaesthesia are contraindications. In patients with portal hypertension and coagulopathy laparoscopic cholecystectomy still be better than open but adequate precautions should be taken including correction of coagulopathy, need for plasma or platelet transfusions. Proven gallbladder cancer is a sure contraindication for laparoscopic cholecystectomy. Multiple earlier laparotomies, severe dense adhesions in cholecystitis, acute pancreatitis, anomalies in the biliary system, cirrhosis, pregnancy, obesity are the real challenging situations while doing laparoscopic cholecystectomy. Need for a conversion and non-hesitant to convert at right time prior to creation of critical problem are to be kept in mind by surgeons.

Technique

Patient is placed in 15º head up anti-Trendelenburg position with 15º right upward tilt. Probably this is done after insertion of the first camera port in supine position. Nasogastric tube should be passed to decompress the stomach. Urinary catheter is placed otherwise bladder should be emptied before patient is brought into the operation theatre table. It is required in difficult cases or complications are suspected or when prolonged anaesthesia is needed.

After clearing and draping, monitor is kept in the right up facing towards the table; surgeon stands on the left side; camera assistant on the left of the surgeon; scrub nurse on the right side near foot end of the patient. Ideally two monitors on right and left sides should be kept. What is commonly practiced is North American approach with the position explained above. Radiolucent table is essential to do fluoroscopy whenever needed like on table cholangiogram.

Instruments (Fig. 22-99)

1. Veress needle
2. 10 mm port—2 in no.
3. 5 mm port—2 in no.
4. Maryland forceps.
5. Atraumatic (Universal) grasper.
6. Toothed grasper 5 mm.
7. Gallbladder extracting forceps 10 mm.
8. Clip applicator.
9. Suction irrigation.
10. Scissors.
11. Hook/spatula dissector.
12. Endo bag.

Alternatively patient may be kept in semilithotomy position with anti-Trendelenburg tilt; thighs should be kept parallel to ground. Surgeon stands in between legs. Port placements are almost similar but right hand working port is placed in the left hypochondrium to achieve triangulation. This position is called as French or European position.

Camera port (10 mm) is placed at upper umbilical crease line. But it can be placed at changed positions depending on a obesity, previous surgery. Open or closed method can be used. A 10 mm working port is placed in the epigastrium just below the xiphoid process in the subcostal region. After initially puncturing the rectus sheath, it is directed towards right to avoid entering through the falciform ligament. If it passes through the falciform ligament then bleeding may occur as falciform ligament is vascular; falciform ligament may act as a flap to interrupt proper functioning of the port. Third (5 mm) port is placed in the same level at midclavicular line; 4th lateral 5 mm port is placed at anterior axillary or still lateral depending on need.

Abdomen is inspected all round. Gallbladder is identified; presence of adhesions by omentum, colon, stomach and duodenum over the gallbladder is identified. Through lateral 5 mm port toothed instrument is passed and fundus of the gallbladder is held firmly and is pushed upwards towards diaphragm; this allows the opening and visualisation of the Calot's area. If gallbladder is found tense then it is decompressed by aspirating the content using long needle passed directly through abdominal wall into the gallbladder under vision. Fine trocar and cannula also can be used but usually needle aspiration is sufficient.

Release of adhesions is important. Through epigastrium port Maryland instrument is passed using a reducer. Through midclavicular port 5 mm non-toothed atraumatic grasper is passed. Omentum is pulled down from the gallbladder by holding the edge using Maryland very close to the gallbladder. Cautery and blunt traction separates the omentum. Similarly colon, stomach and duodenum are released from the field. Monopolar cautery may injure these structures due to heat generated and so should only be used judiciously. Once adhesions



Fig. 22-99: Laparoscopic cholecystectomy instruments and Calot's triangle dissection and X-ray view of the clips placed.

are released, infundibulum is held using the midclavicular port instrument. Infundibulum is held downwards and towards right.

Calot's triangle is dissected using Maryland forceps. In infundibular technique, cystic duct is dissected carefully both in front and behind and traced towards infundibulum to visualise typical flare when cystic duct joins the infundibulum and with a funnel shape. Cystic duct is further dissected from infundibulum towards the cystohepatic junction; i.e. from safety zone to danger zone. Bipolar cautery should be used rather than monopolar cautery. Entire Calot's should be dissected including cystic artery. It should be made sure that only two structures enter the gland. Lymph node of Lund is a good marker to dissect cystic artery; node is anterior to the artery. Calot's dissection should not extend posterior to a constant landmark on the inferior surface of the liver—Rouvier sulcus **(Fig. 22-100)**. This oblique sulcus usually is present in the liver; dissection should be in front of it; never extend posterior level of this landmark.

Another technique is '*critical view of safety*' in which entire Calot's triangle including Hartmann's pouch is dissected off from the liver bed to identify the cystic duct and artery.

Cystic artery is dissected using Maryland forceps; isolated. Any anomalies should be identified. Lymph node of Lund is a good marker to identify which is in front of the artery. Often anterior/superficial and posterior/deep branches are identified. After dissection of entire Calot's and to confirm that only two structures are entering the gallbladder cystic artery is clipped on both sides and divided with curved scissor. Harmonic scalpel can also be used to divide the cystic artery. Cystic artery is divided prior to cystic duct usually.

Then cystic duct is clipped using 10 mm clip applicator through epigastric port. Two clips are applied proximally and one clip distally and divided in between. Blind application of clip should be avoided; clip applied should be away from bile duct. Undue traction during clipping should be avoided. Before clipping gallbladder stone is milked into the gallbladder from the cystic duct if any stones are present.

Gallbladder is detached from the gallbladder using various instruments. Spatula with monopolar cautery is commonly used and safer. Hook is also used; its bend is commonly used; to cut peritoneal edge sharp tip is hooked and fulgurated. Harmonic scalpel is an excellent tool for this. Hartmann's pouch is held using the 5 mm grasper (dolphin nosed) and alternatively changes its position according to its need. Undue deeper fulguration may open up the liver tissue. It is safer to keep the instrument closer to the gallbladder than liver bed. When small peritoneal fold attachment is left near the fundus, bed is retracted to inspect the Calot's and gallbladder bed properly for the clip placement and oozing. Often gallbladder may get opened to spill the stones and bile. Bile should be sucked out properly and stones should be extracted or kept in an extracting bag kept in the peritoneal cavity.

Gallbladder is extracted through the epigastric port; 10 mm stout gallbladder holding instrument (claw-shaped) is used to hold at neck of the removed gallbladder; instrument with 10 mm port is removed with the gallbladder. Often port site rectus sheath and skin incision may need to be widened by few mm. Gallbladder neck once comes out of the wound can be opened and suck out all bile. Stones in the gallbladder can be removed using an artery forceps to make its



Fig. 22-100: Laparoscopic view of Rouvier sulcus.


Crepe bandages to both legs
General anaesthesia
Laparoscopic instruments
Head up-right up position with nasogastric tube in place
Monitor on right up
Cleaning and draping
Camera and 30 degree telescope
30 degree telescope
White balance ok
Open method

Figs 22-101(1)


Dipping the telescope in hot saline/water

Figs 22-101(2)


Toothed grasper to hold the fundus of gall bladder
11 no. blade is used to make incision in the abdomen
Maryland dissector is used with reducer through 10 mm working port

Figs 22-101(3)


5 mm non-toothed grasper is used to hold and retract the Hartmann's pouch - down and right
5 mm working port retracting fundus of GB
5 mm working port retracting Hartmann's pouch
Camera port
10 mm working port with reducer
Scrub nurse
Cameraman
Surgeon
Releasing the adhesions

Figs 22-101(4)


Cystic artery
Cystic duct
Irrigation and suction

Figs 22-101(5)


Suctioning is done lateral
side under liver and paracolic gutter
Bipolar cautery is better in
dissecting the Calot's
Rouvier sulcus
Suction device
10mm clip applicator
with clip

Figs 22-101(6)


Curved scissor
Clip to the cystic artery
First artery should be clipped
Cystic duct isolated
Milking of cystic duct

Figs 22-101(7)


3 clips to cystic duct-two proximal one distal-duct is cut between this
Cystic duct stump
Spatula dissector — monopolar cautery is used
Spatula dissector — monopolar cautery is used

Figs 22-101(8)



Monopolar hook can be used for dissection in GB bed

Monopolar hook can be used for dissection in GB bed

Monopolar hook can be used for dissection in GB bed either on its bend or on its hook

Change of position of Hartmann's will facilitate dissecting of GB

Inspection, irrigation of GB bed should be done just prior to completion of the dissection

Final separation of GB from its bed

Figs 22-101(9)


Removed GB is kept on the liver surface for retrieval
GB retrieval 10 mm jaw forceps
Retrieval endo bag can be used to avoid spillage and contamination of the port site
14 no. nasogastric tube as drain through lateral 5 mm port — optional or when indicated
Rectus sheath in deeper plane should be sutured in all 10 mm and above ports

Figs 22-101(10)

Figs 22-101(1 to 10): Technique of laparoscopic cholecystectomy in detail.

removal easier. Gallbladder can be held by passing curved Kocher's clamp through the epigastric port site wound after removing the port temporarily. Retrieval bag can be used to remove the gallbladder and is probably ideal.

Once gallbladder is removed, gallbladder is checked for its opening and contents. Port is placed again. Gallbladder bed and Calot's triangle is checked again. Bed is irrigated and inspected for the final closure.

Usually closure is not necessary. When there is difficulty in dissection or if sepsis is present, then drain is kept. A 14 French nasogastric tube is passed through the lateral 5 mm port is placed in gallbladder bed **(Fig. 22-101)**.

Key steps

1. Place four standard ports.
2. Right up and head up position.
3. Maintain adequate traction on the gallbladder at all times.
4. Posterior dissection at Calot's triangle.
5. Cystic artery and duct are identified dissected properly from safe distal zone (infundibular) to danger proximal zone (CBD level)
6. Clip application after confirming anatomy.
7. Clip artery first then only duct.
8. Dissect gallbladder close to the wall.
9. Inspect gallbladder fossa.
10. Drain the gallbladder bed.
11. Fascial sheaths of all 10 mm port sites should be closed securely.

Trocars are removed, rectus sheaths are closed in 10 mm ports. Skin is sutured or sealed with cyancrylate glue **(Figs 22-102 to 22-104)**.

The drain is removed after 24 hours and oral is started. The patient is mobilised as early as possible and discharged after 48 hours.

Difficult Gallbladder

The safest thing to do when the anatomy of the Calot's triangle is not defined is to convert to open surgery. Conversion should not be taken as a failure but as a wise decision in the interest of the patient. At times, the Calot's triangle is adherent and all planes are lost. In such cases, the suction irrigation device can be used as a blunt dissector and dissection can be done using jet of saline through the channel. One should always be aware of the position of the duodenum and the CBD as they are likely to be damaged. Using a gauze piece to keep the field clean can be done provided utmost care is given and the same is retrieved at the end of the procedure. It is easy to lose track of the small piece and later struggle to find it. Retrograde dissection can be done provided the surgeon is experienced but for the majority of us it may be safe to convert into an open surgery. Subtotal cholecystectomy is an alternative which can be undertaken. Additional instrument using additional port can be tried like fan liver retractor.



Fig. 22-102: Gallbladder specimens removed in different patients – through laparoscopy.



Fig. 22-103: Different gall stone—types.



Fig. 22-104: Gallbladder specimens with different pathological look.

Trouble Shooting

1. Difficulty in visualising the Calot's triangle	Reposition the patient. Apply the traction cranially. Clear the viscera away from the operative field. Aspirate the Ryle's tube to deflate the stomach. Apply lateral traction to the Hartmann's pouch.
2. Bleeding at Calot's triangle	Try to perform posterior dissection. Apply compression using gauze piece and wait for 5 minutes. Do not dissect the area blindly which you cannot visualise.
3. Short cystic duct	Confirm the anatomy. Apply intra corporeal knots using silk or vicryl
4. Bleeding from liver bed	Take the gallbladder on the spot and apply pressure keeping the gallbladder on it. Wait for 5 minutes. Stay close to the gallbladder while dissecting.

Complications of Laparoscopic Cholecystectomy

Haemorrhage: It can be from liver bed, slippage of cystic artery ligation or after formation of hepatic artery pseudoaneurysm **(Fig. 22-105)**. Trocar site bleeding can also cause significant difficulty in controlling.

Spillage of stones: They should be extracted carefully. Often it is left behind as stone gets migrated and it is difficult to pick up every stone. Such unidentified stone may cause real problem occasionally. It can cause abscess in subphrenic space or intra-abdominal region; can cause sinus formation, granuloma formation. It can erode various vital structures in the peritoneal cavity causing colocutaneous fistula, duodenal fistula, intestinal obstruction, major vessel thrombosis (middle colic artery), haematuria, and septicaemia.

Biliary tree injuries are due to missed anatomy, over traction on the CBD, anomalies, adhesions, etc. If biliary tree (bile duct or hepatic duct) injury occurs conversion should be done. Type of injury is identified and classified. ERCP stenting may be tried on table. Otherwise choledochojejunostomy should be done. It is unwise to repair a completely transected common bile duct as stricture will develop eventually **(Fig. 22-106)**.

Injury to colon, stomach, and duodenum can occur. Complications specific to laparoscopy should be kept in mind.

Wound infection, incisional hernia can occur.

Pancreatitis, retained stones, biliary stricture are other complications.

SINGLE INCISION LAPAROSCOPIC SURGERY (SILS) IN CHOLECYSTECTOMY (FIG. 22-107)

SILS is an advanced minimally invasive surgical procedure wherein surgeon operates exclusively through a single umbilical entry port. It is also called as single port access surgery (SPA), one port umbilical surgery (OPUS), and single port incision less conventional equipment utilising surgery (SPICES), natural orifice transumbilical surgery (NOTUS).

Whales did tubal ligation in 1969 through single incision; Pelosi did SIL appendicectomy in 1992; Navarra et al, did SIL cholecystectomy in 1997; Pishkun et al. did SIL cholecystectomy in 1999.



Fig. 22-105: Hepatic artery pseudoaneurysm after laparoscopic cholecystectomy; it is treated successfully by injection of glue and coils through intervention radiology.



Different ways where bile duct and hepatic duct can get injured during laparoscopic surgery-during clipping of the cystic duct

Fig. 22-106: Possible ways by which common bile duct and right hepatic duct can get injured while doing laparoscopic cholecystectomy.

It needs general anaesthesia, specialized umbilical large trocars which accommodates working instruments also, flexible laparoscope, rotatable instruments, articulating handles and harmonic scalpel.

Here through a large 2.5 cm umbilical vertical incision dissection is done by open method to reach peritoneal cavity. Specialised port in which one can pass 10 mm telescope and two 5 mm instruments for work. Instruments are angled and flexible to meet the ergonomic principles to certain extent. Dissection of gallbladder is done in similar fashion like four port technique. Specimen is easily retrieved through umbilical port as it is wider enough. If difficulty arises any time one can add additional ports as required.

Advantages

There is no visible scar like a traditional multiport, faster recovery time, early return to work and cosmetically better.

Disadvantages

Expensive trocars and instruments, skilled work, learning curve, dissection against normal surgical ergonomics. Coaxial orientation of optics and instruments, loss of triangulation – 'Azimuth angle', sword fighting of instruments inside; nutcracking outside—are real problems.

Complications

Umbilical wound pain, infection, umbilical hernia, time consuming because of limited visibility during learning curve complications of cholecystectomy and conversion rate may be more, selection of case is very important.

COMMON BILE DUCT EXPLORATION

It is done to remove the CBD stones after open cholecystectomy. Present era of ERCP with laparoscopic cholecystectomy its indications are not that common unlike in olden days. However, failed ERCP patients needs open choledochotomy and extraction of the biliary tree stones. In olden days, it is indicated if intraoperative duct cholangiography shows stones in CBD; recent history of jaundice; palpable stones in the CBD; CBD diameter more than 10 mm; if ultrasound shows stones in CBD; when in doubt. Many times even if ultrasound is normal with altered liver function in blood parameters should suspect the presence of CBD stones; CT abdomen or MRI is ideal in such situation. One has to remember without confirming the presence or absence of CBD stones, if cholecystectomy is done either by open or laparoscopic approach without a plan to do on table cholangiogram will definitely trouble the surgeon in post-operative period.



Fig. 22-107: Single incision laparoscopic surgery (SILS) for cholecystectomy.

It is now usual in specified center that by a skilled authentic laparoscopic surgeon, duct cholangiogram and CBD exploration can be done through laparoscopy without opening.

If ERCP has failed or on table during open approach mandatory duct cholangiogram shows stones in the CBD, then CBD exploration is indicated **(Fig. 22-108)**.



Fig. 22-108: Placement of T-tube in CBD after choledocholithotomy. Note the separate drain placed in the cholecystectomy bed to drain fluid, blood and bile.

Technique

Incision is same as Kocher's incision but may require upwards extension towards xiphisternum or towards left side as partly bucket handle. After exploring the abdomen, cholecystectomy is done in usual manner with on table duct cholangiogram. Kocherisation of the duodenum is a must. Peritoneum on the anterior part of the CBD is incised to expose the CBD for 2-3 cm; small bleeders are cauterised using bipolar cautery; monopolar cautery should not be used. Two stay sutures are placed on the CBD using 3-0 vicryl; one just above the duodenum; another just below the level of the joining of cystic duct. Stay sutures are placed on the anteromedial surface of the CBD. Needle with syringe is passed into the CBD to aspirate bile which is collected for cytology and culture **(Fig. 22-109)**.

Incision is made vertically in the CBD on its anteromedial surface between stay sutures for 1.5-2 cm using no. 15 blade **(Fig. 22-110)**; incision begins at its upper hepatic side downwards towards duodenum just up to above the duodenum; care should be taken not to pass across the posterior wall and so into the portal vein even though it is very rare; suctioning of bile is done (Incision should not be done on the lateral right side of CBD as cystic duct and CBD may have a common channel for 2 cm).

Mobilized 2nd part of the duodenum is held with thumb and fingers of one hand. Any stones if felt is carefully milked upwards towards choledochotomy wound. Stones are removed by different means—pituitary scoop of proper size; Randall's stone forceps; Fogarty catheter; Dormia basket; *choledochoscope (ideal)*; Desjardin's choledocholithotomy forceps; Bake's CBD dilator (malleable no. 3). One should not force the stiff instrument downwards towards the ampulla as it may perforate the pancreatic part of the CBD causing fatal pancreatitis or bleeding or sepsis. 10 F catheter or infant feeding tube can be gently passed through the ampulla and if it is so that means ampulla is adequately patent without obstruction. Repeated warm saline irrigation both below through the CBD and above through the hepatic ducts should be done. First retrograde exploration is done; then downwards. It is easier to negotiate the tube and flush left hepatic duct. One should be careful in passing tube into right hepatic duct as it may get injured causing haemobilia **(Figs 22-111 to 22-114)**.



Fig. 22-109: Needle aspiration of common bile duct is done to aspirate bile which often may be infected.



Fig. 22-110: Pott's scissor is better to cut and extend the incision in the common bile duct after making incision using no 15 blade.

Fogarty catheter when used is negotiated into the duodenum and confirmed by feeling the duodenum. It is only partially inflated and allowed just to pass through the ampulla proximally; then it is fully inflated to gently pull upwards towards choledochotomy to retrieve the stone along with that.

Ideally choledochoscope is best to visualise and retrieve the stones. Both rigid and flexible choldochoscopes are available. Both are sterilized by ethylene oxide for repeated uses. Flexible scope has got poorer quality of image, costly, damageable, less life-span than rigid one even though



Fig. 22-111: Bakes dilator no. 3 F is used; one should be gentle while using it as forcible push may damage pancreas due to bile duct perforation.



Fig. 22-112: Desjardin's choledocholithotomy forceps to retrieve gallbladder stones.



Fig. 22-113: Dormia basket to retrieve stones from CBD.

it is safer easily negotiable into the CBD and hepatic ducts to retrieve the stones. Rigid scope is commonly used; 4 cm and 6 cm rigid scopes are available with 5 (outer) × 3 (inner) mm diameter. If CBD size in less than this which is unlikely is a contraindication for choledochoscope. Warm saline irrigation is done through the choledochoscope (rigid choledochoscope needs continuous saline irrigation like cystoscope of urologists otherwise mucosa cannot be seen). Choledochoscope is used with surgeon standing on the left side of the patient. Scope can be carefully negotiated proximally up to often tertiary ducts. Distally choledochscope is passed with guidance of other hand under Kocherised duodenum. If stones are visualised in distal CBD they are removed using different flexible instruments passed beside the choledochoscope for direct visualisation of the stone for retrieval.

If by all these means, stones are still retained due to impaction in distal CBD, then duodenotomy in 2nd part of the duodenum followed by sphincterotomy is done at 11 o'clock position for 1 cm to retrieve the stone; later sphincteroplasty is done. T-tube should be placed; it has got vertical and horizontal part with a soft flexible junction which makes its removal safer. 16 French size is used (diameter 5 mm). As this size facilitates passage of choledochscope later through the track formed after 21 days in case if there are retained stones **(Fig. 22-115)**.

T-tube (Kehr's T tube) comes in different sizes; 16 F size is usually used. Horizontal limb is cut shorter; each horizontal limb should be 1 cm; lengthy tube inside CBD may precipitate pancreatitis or may traumatise during its removal after 14-21 days. T-tube should be



Fig. 22-114: Fogarty catheter often used to retrieve the CBD stones.



After duct cholangiogram and cholecystectomy, Kocherisation is done; peritoneum on the anterior aspect of the CBD is incised

Using syringe with needle CBD aspirated for bile which is sent for culture

Two 3-0 vicryl stay suture are placed on the anteromedial surface of the CBD

Using no. 15 blade, vertical incision of 2 cm is done on the anteromedial surface between stay sutures from above downwards



Through choledochotomy CBD stones are removed; first from above then from below.. Desjardin's forceps; Fogarty catheter; Dormia basket; pituitary scoop; choledochoscope are used for stone retrieval

Warm saline irrigation is done both proximally and diatally; Kehr's T-tube is placed after cutting the horizontal limbs for 1 cm only; tube is brought through lower most part of the choledochotomy

CBD is closed with interrupted 4 zero vicryl sutures above the T-tube which is 4-0 brought out through a separate wound

Fig. 22-115: Technique of common bile duct exploration and placement of T tube.

brought out at the lower most part of the choledochotomy incision to avoid the disruption of the suture line while removal. T-tube should be ideally made up of latex rubber, not of plastic or polyvinyl. Latex causes extensive reaction to create a track and so as to prevent bile leak into peritoneal cavity and so biliary peritonitis. Different modifications are available. Maingot's split type is also available with a slit on the opposite side of the junction. CBD is closed above the T-tube keeping T-tube at the lower most part of the CBD. Interrupted 3-0 vicryl or 4-0 PDS is used. Patency of the tube should be checked by saline infusion.

Completion on table T-tube cholangiogram is a must. T-tube is brought out of the abdomen through a separate stab incision at anterior axillary line. Tube drain is placed at gallbladder bed **(Fig. 22-116)**.

Postoperative Care

Antibiotics are continued. Nasogastric tube can be removed in 48 hours. Drain is removed in 5-7 days. Post-operative T-tube cholangiogram is done in 1-14 days. In doubtful cases T-tube should be kept in place for 21 days more. Prior to removal, one should confirm that there are no residual stones. Often T-tube is clamped for 24 hours; if patient develops pain, vomiting, pain abdomen, bile leak from side of T-tube, it is probable that there are retained stones.

Problems and Complications

Haemorrhage during surgery may be due to oozing from gallbladder bed, hepatic artery injury, portal vein injury even though it is rare.

Post-operative pancreatitis due to CBD perforation by forcible negotiation of the tube across the ampulla into the duodenum.

Bile leak and bile peritonitis is equally dangerous and life-threatening.

Haemobilia may be due to intrahepatic injury while retrieving the stones from hepatic ducts. Plasma, vitamin K injection is usual treatment. Hepatic angiography confirms the diagnosis. Therapeutic embolization may be required.

Septicaemia, subphrenic abscess can develop mainly in diabetic and old aged.

Residual bile duct stones: It is confirmed by T-tube cholangiogram. Its incidence is 3%; but less if choledochoscope is used. Small stones less than 1 cm is retrieved by saline (1 litre) in heparin (5000 units) infusion into the T-tube. In 5 days often, stone reduces in size. Patient is discharged with T-tube with an advice of daily infusion of 50 mL of saline into the T-tube. Patient is asked to come after 8 weeks for further management of retained stones. During this period track, has formed well. It is managed by Burhenne (radiologist, Canada) method. Under fluoroscopic guidance after removal of T-tube, flexible catheter is passed into the track to reach the duodenum across the stone; Dormia basket is passed through the flexible catheter; gently it is manipulated to trap the stones into the basket under guidance to retrieve the stones; repeated attempts clears all the stones. It has got 90% success rate. Flexible choledochoscopy can be passed (not rigid) through the track to visualise and retrieve the stone. Repeat ERCP, sphincteroplasty, re exploration, choledochoduodenostomy or choledochojejunostomy are other methods in these patients.


Choledochotomy with T-tube insertion
Choledochotomy with T-tube insertion
Vertical limb is brought out through the lowermost part of the choledochotomy
Interrupted sutures 3-0 vicryl proximal to T-tube of choledochotomy
Interrupted sutures 3-0 vicryl proximal to T-tube of choledochotomy
Note the position of the T-tube
T-tube brought out of the abdominal wound at anterior axillary line
T tube brought out of the abdominal wound at anterior axillary line
Tube drain is placed
Tube drain
T-tube
T-tube in place
Cholangiogram AP
T-tube cholangiogram

Fig. 22-116: Placement of T-tube after CBD exploration and removal of the CBD stone. It is done in secondary CBD stone where stones have slipped from the gallbladder into the CBD.

CHOLEDOCHODUODENOSTOMY

Riedel in 1881 did first choledochoduodenostomy.

Indications

Stones still remained with CBD after CBD exploration for multiple CBD calculi. It could be with primary CBD stones or secondary stones. But commonly such stones are primary one. Retained stones in the hepatic ducts are also indication.

Papillary stenosis: It is often known to occur. It is diagnosed by failure of the dye reaching the duodenum during operative cholangiography and inability to pass 3 mm dilator across CBD into the duodenum.

Impacted distal CBD stone wherein removal is impossible.

Intrahepatic calculi, residual stones after removal of T-tube in earlier operation, diverticula in the duodenum causing CBD obstruction and cholangitis, benign stricture of the distal CBD.

Prerequisite

CBD should be more than 1.5 cm to do choledochoduodenostomy.

Contraindications: CBD if not dilated significantly, sclerosing cholangitis, chronic pancreatitis which needs surgical decompression, malignant obstruction, duodenal oedema.

Technique (Fig. 22-117)

Preparation anaesthesia and position is same as cholecystectomy. Cholecystectomy is done. Kocherisation should be done adequately. Longitudinal choledochotomy is made on the CBD of 2.5 cm in length. Duodenum is incised on its first part longitudinally around 2.2 cm (3 mm lesser than CBD incision). Through the opening ampulla is again palpated to avoid missing malignancy; often choledochoscope can be done to confirm that. Distal end of the choledochotomy is brought to the middle of the lower leaf of the duodenotomy. Middle points of the edges of the choledochotomy is brought towards the ends of the duodenotomy incision; stay sutures are placed using 3-0 vicryl. Further 3-0 vicryl interrupted sutures are placed initially to complete the posterior layer (knots should be outside ideally); then anterior layer. Finally funnel-shaped choledochoduodenostomy anastomosis is completed. Stoma should be at least 2.5 cm. Abdomen is closed with a tube drain.

Problems

- ***Sump syndrome:*** it is due to creation of blind segment/pouch at distal CBD causing stasis and cholangitis. This pouch contains infected bile, food, calculi (Fig. 22-118).
- Bile leak due to anastomotic disruption can occur.
- Recurrent cholangitis is another problem.

TRANSDUODENAL SPHINCTEROPLASTY

Indications are same as choledochoduodenostomy.

Technique (Fig. 22-119)

After cholecystectomy through Kocher's incision, Kocher's manoeuvre is done; common bile duct is explored. No. 3 Bake's dilator is passed into the CBD but not across the ampulla of Vater. Tip of the dilator is palpated through the anterior duodenal wall which allows the proper placement of the sphincterotomy incision.

Duodenotomy of 4 cm length is made in the 2nd part of the duodenum centring at the level of the ampulla. Retractors are placed into the cut edges of the duodenotomy to expose the ampulla adequately. It is better to place four stay sutures to retract edges at four corners.

Incision is made at 11 o'clock position. It keeps incision away from pancreatic duct entry and also is relatively avascular. Using no. 15 blade or Pott's scissor, tip of the Bake's dilator as a guide incision is made along the orifice. After cutting partially, 4-0 vicryl sutures are placed on either sides of the opened ampulla and held apart to give traction. Pancreatic duct orifice is identified at 5 o'clock position on the posterior aspect. Incision is further extended for 3 mm and


Vertical incision in the CBD of 2.5 cm; longitudinal incision of 2.2 cm is done in the duodenum
Middle of the edges of the choledochotomy is sutured to ends of the duodenotomy
It creates funnelling and keeps stoma patent
After cholecystectomy and CBD exploration, Kocherisation should be done; CBD diameter should be 1.5 cm or more
Posterior sutures using 3-0 interrupted vicryl is placed with knots outside preferrably
Anterior layer is closed using interrupted sutures to complete the choledochoduodenostomy

Fig. 22-117: Choledochoduodenostomy—technique.


Liver
CBD
Stomach
Choledocho-duodenostomy
1st part duodenum
Site of sump syndrome
Duodenum

Fig. 22-118: Technique of choledochoduodenostomy for CBD stones. Note the site of possible occurrence of sump syndrome.

additional stay sutures are placed. Pancreatic ductal orifice may be better visualised by injecting secretin one unit/kg IV which stimulates the pancreatic juice flow across the orifice. Incision is continued sequentially every time for 3 mm with a pair of vicryl stay sutures. Sphincterotomy of entire sphincter of Oddi needs 2 cm length of incision along the ampulla. Otherwise length of the sphincterotomy should be length of the CBD diameter. At the apex, figure of eight suture should be placed.

If there is associated chronic pancreatitis and stenosis of the pancreatic duct, if no. 3 Bake's dilator is not negotiable, then pancreatic ductoplasty also should be done. Probe is passed into duct. Duct is incised at its anterior wall for 10 mm using Pott's scissor at 5 o'clock position; technique is as similar as sphincteroplasty of sphincter of Oddi; i.e. every 3 mm incision paired 4-0 vicryl stay sutures; sequentially until adequate ductoplasty (of Wirsung) is achieved.

Choledochotomy is closed with a T-tube; duodenotomy is closed; tube drain is placed. Abdomen closed in layers **(Fig. 22-120)**.

Post-operatively antibiotics are given; nasogastric tube is removed in 48 hours and oral feeding is started. Liver function, serum amylase levels are estimated during feeding post-operative period. Tube drain is removed in 5 days. T-tube is removed in 2 weeks.

Complications

Duodenal fistula, sepsis, subphrenic abscess formation, and pancreatitis are complications.

CHOLEDOCHOJEJUNOSTOMY/ BILIARY ENTERIC ANASTOMOSIS/ HEPATICOJEJUNOSTOMY

Indications

Major ductal injury, inoperable tumour (palliative bypass), chronic pancreatitis; biliary stricture are indications.

Side-to-side or side-to-end choledochojejunostomy can be done. Unless CBD is completely transected and distally ligated in definitive resections like Whipple's operation, end-to-side type is usually not necessary **(Fig. 22-121)**.


After cholecystectomy, Kocherisation is done; choledochotomy is done; duodenotomy of 4 cm in 2nd part is done
4 stay sutures are placed into the duodenotomy edges
Ampulla is identified; no. 3 Bake's dilator is placed in the distal CBD; but passed across the ampulla
With Bake's tip as guidance using Pott's scissor sphincter is cut at 11 o'clock position
Interrupted 4-0 vicryl sutures are placed on both cut edges
Bake's dilator is negotiated into the duodenal lumen
Sphincter is cut every 3 mm further sequentially towards along the bile duct with placement of 4-0 vicryl sutures until apex; in the apex a figure of 8 sutures is placed
Completed bile duct sphincteroplasty
If there is pancreatic duct stenosis then ductoplasty of duct of Wirsung is done
Warm saline wash is given along the choledochotomy incision both above and below; T-tube is placed across-the choledochotomy; choledochotomy and duodenotomy is closed using interrupted vicryl sutures; tube drain is placed into the peritoneal cavity in the subhepatic space

Fig. 22-119: Technique and steps of transduodenal sphincteroplasty.


Duodenotomy at 2nd part
Duodenotomy at 2nd part
Stay sutures at angles
Closure after sphincteroplasty longitudinally; transverse closure is also done

Fig. 22-120: Duodenotomy in transduodenal sphincteroplasty and closure of duodenum ideally transverse; here longitudinal closure was done which is also accepted.



Fig. 22-121: Primary biliary stones in common bile duct and hepatic ducts. It needs choledochojejunostomy.

Technique

After doing cholecystectomy (it facilitates the approach and visualisation and avoids later development of cholecystitis) and choledochotomy or incision on the common hepatic duct, Roux limb is prepared. Technique of dissection and choledochotomy is same as for bile duct exploration. Choledochotomy should be around 2-2.5 cm in length.

Duodenojejunal junction is identified by ligament of Treitz and inferior mesenteric vein. After 2nd arcade of the blood supply in the mesentery, through transillumination arcades are identified and divided using small haemostats. Bipolar or harmonic scalpel can be used. 20 cm from the duodenojejunal junction is the site taken for Roux limb. Jejunum is cut with no. 15 blade between occlusion clamps; or stapler transection can be done. Roux limb is passed across the transverse mesocolon through a rent at right of the middle colic artery to reach the CBD area. Antecolic placement loop can be done if there are lot of adhesions and if there are infiltrations in case of malignancy at mesocolon level. Blood supply of the Roux limb is assessed by its colour and pulsation at its mesentery (**Figs 22-122 and 22-123**).

In *side-to-side anastomosis*, 4-0 vicryl sutures are used. Jejunum is incised over its antimesenteric border 1 cm proximal to the stapled end. Lengthy distal part distal to the proposed anastomosis should not be kept as it may cause blind loop and recurrent infection. Jejunotomy incision should be 2 cm in length (3 mm lesser than choledochotomy incision. Usually 4 interrupted sutures are placed between jejunum (posterior cut edge) and right margin of the CBD with 3-4 mm apart. Jejunal bites should be adequate. Ideally from CBD outside in, then from jejunum inside out bites are taken so that knots are placed outside; but posterior knots can be placed inside by taking bites from inside out and outside if technical difficulty arises. All sutures are placed and kept long with haemostats; only after placing all posterior sutures jejunum is pushed gently into the choledochotomy and knots are tied; all threads are kept long and cut at the end. Anterior sutures are taken similarly with knot placement outside. After taking all bites, knots are tied sequentially at the end. It is logically better to take bite from the middle of the choledochotomy cut edge on both sides to the ends of the jejunostomy so that stoma will be kept patent; however, both ways are adequate enough to maintain the stomal patency **(Figs 22-124 and 22-125)**.

It is often practice that both posterior and anterior suture bites are taken together and kept aside using haemostats. With *parachute technique* (railroading, *Voyles-Blumgart technique*, 1982) jejunum is pushed and posterior and anterior knots are placed sequentially. However, it is often technically difficult especially to identify the corresponding sutures to put knots and may create problem while knotting. If surgeon is not well-practiced with this technique, he should avoid it to prevent problems thereafter.


CBD
Roux limb of jejunum

Fig. 22-122: Creation of Roux jejunal loop.


Choledochojejunostomy
45-60 cm
Roux limb
Longitudinal
choledochotomy of
2-2.5 cm distal to
cystic duct level
20 cm
Middle
colic
vessels
Jejunojejunostomy

Roux-en-Y loop was created 20 cm from duodenojejunal junction
Roux loop is brought through T_n mesocolon right of middle colic vessels; jejunotomy is done 1 cm proximal to the closed end: side-to-side interrupted 4-0 vicryl sutures are placed to complete cholodochojejunostomy

Stay sutures are placed
Choledochotomy is done
Jejunotomy is done at antimesenteric border-1 cm proximal to the end
Centre of the edges of the choledochotomy is sutured to ends of the jejunotomy

Posterior layer knots are placed with knots placing outside

Anterior layer interrupted 4-0 vicryl sutures are placed

Fig. 22-123: Choledochojejunostomy technique.



Kocherisation of duodenum

Feeling the distal CBD by holding the Kocherised duodenum

Aspirating the CBD to confirm bile: bile is collected for culture

Stay sutures using vicryl

Opening the CBD in between stay sutures using no. 15 blade

Opening the CBD to retrieve the stone

Stone retrieval from CBD

Saline wash and stone retrieval from proximal part (hepatic)

Saline wash and stone retrieval from distal part-(CBD)

Figs 22-124(1)


ERCP stent removed
Doing scopy to visualise distal CBD using no 4 or 5 f rigid scope (Rigid choledochoscopy)
Scope inside the CBD
CBD
Choledochoscope is done from left side
Identifying the DJ junction
Opening the T_n mesocolon right of the middle colic vessels
Transillumination test to check the jejunal vascular arcade
Arcade is carefully ligated 20 cm from DJ jn
Stapler for transection of the jejunum
Cartridge placement
Placing and locking the cartridge across the jejunum
Firing the cartridge

Figs 22-124(2)


Stapled transection ends of jejunum
Distal cut end is passing through the rent in the T_n mesocolon as Roux limb towards choledochotomy
Distal cut end is passing through the rent in the T_n mesocolon as Roux limb towards choledochotomy
Jejunotomy 1 cm proximal to end at antimesenteric border: should be lesser in length than choledochotomy
Posterior layer interrupted bites using 4-0 vicryl from outside-in; then inside out- to keep knots outside
Posterior layer interrupted sutures in place
Anterior layer sutures are placed after tying posterior layer knots
Completed anterior layer of choledochojejunostomy
Jejunum is anchored to T_n mesocolon
Side-to-side jejunojejunostomy

Figs 22-124(3)


Side-to-side jejunojejunostomy
Side-to-side jejunojejunostomy
Side-to-side jejunojejunostomy
Side-to-side jejunojejunostomy
Closing mesenteric rent
Saline irrigation if needed is given
Placing the tube drain
Closure of Kocher's incision
Aberdeen knot
GB specimen
GB and CBD stones

Figs 22-124(4)

Figs 22-124(1 to 4): Choledochotomy, choledochoscopy, Roux-en-Y side to side choledochojejunostomy with side-to-side enteroenterostomy. Here stapler is used initially to transect the jejunum.


CBD
Staple Roux limb end
Choledochojejunostomy under progress
Choledochojejunostomy-side to side

Fig. 22-125: Roux-en-Y side-to-side choledochojejunostomy.

End-to-end anastomosis can be done if CBD diameter is wider. It is done in malignancy with obstruction either after resection or as palliative procedure. Technique is similar like end-to-end anastomosis. Knots are placed outside. Interrupted vicryl sutures are placed.

Side-to-end anastomosis is also can be done between side of bile duct to end of Roux limb provided bile duct is sufficiently dilated **(Fig. 22-126)**.

Stenting of the choledochojejunostomy or hepaticojejunostomy is done often by many but is not mandatory. When it is done, it is brought out through the Roux jejunal limb outside and then through a stab wound through abdomen. T-tube may be passed which is brought out through bile duct proximally. It is usually not necessary. Stenting across the stoma through as biliary radicle across the liver to bring out through the abdominal wall is also practiced but may damage biliary tree and may cause bleeding or haemobilia.

Enteroenterostomy is done 60 cm distal to the stoma to complete the Roux-en-Y anastomosis. This is usually end-to-side either hand sewn or stapler. If initial transection was stapler one; then without dismantling original one, a side to side enteroenterostomy can be done **(Figs 22-127 and 22-128)**.

There is usually not necessary to keep a stent through the choledochojejunostomy. If needed no 8 French tube can be passed across the stoma to reach the efferent loop and is brought out through


Roux-en-Y choledochojejunostomy
End-to-side jejunojejunostomy
Jejunojejunostomy
Side-to-side jejunojejunostomy -done when jejunum is transected using stapler

Fig. 22-127: Types of jejunojejunostomy done in Roux-en-Y anastomosis—side-it-side or end-to-side.


Choledochojejunostomy - side to end type; it is done when CBD is dilated very much so that end of the jejunum can be directly anastomosed

Fig. 22-126: Choledochojejunostomy side-to-end.


Side-to-side JJ

Fig. 22-128: Side-to-side jejunojejunostomy.

a small stab incision in the antimesenteric border which is fixed to parietal wall. Finally tube is brought out through a separate stab wound on the abdominal wall. But displacement, falling of the tube is common.

Hepaticojejunostomy after resection is usually end-to-side of Roux loop **(Fig. 22-129)**. It is also often used in trauma. Here biliary enteric anastomosis is achieved by anastomosing into the right and left hepatic ducts. Often confluence of the right and left hepatic ducts to form common hepatic duct is intrahepatic; it is approached at the base of the segment four by cutting the bridging liver tissue between umbilical fissure and segment 4 liver lobe (quadrate). Through same approach left hepatic duct is approached. Technique of anastomosis is similar – interrupted 4-0 vicryl or PDS posterior layer knots will come outside; as well as anterior layer knots. It is always better to keep the knots outside rather than inside even though many contemplate that inside knots are safer. Approaching left hepatic duct is called as Hepp-Couinaud technique **(Fig. 22-130)**.

If there is duodenal obstruction, gastrojejunostomy also should be done to prevent gastric outlet obstruction which may call for 2nd surgery at a later period. Duodenal obstruction occurs especially when there is associated pancreatitis **(Fig. 22-131)**.

Access loop: Often access loop is used to reach the biliary system. It is done by keeping more length of the distal blind end of the Roux limb to bring close to the abdominal wall and fix it; whenever needed this can be opened and stoma and biliary system can be reached through endoscope. Alternatively Roux blind end can be anastomosed to pylorus near lesser curve which can be used as access to biliary system through endoscope **(Fig. 22-132)**.

Loop choledochojejunostomy with enteroenterostomy (Braun) is not commonly advocated. It is technically easier; there is no transection of the jejunum and dissection of mesenteric arcade. It was the common procedure in olden days. Often when it is done few plication sutures are placed to afferent limb to prevent food getting entered into biliary system (to avoid cholangitis)—Kenneth Warren stitch. Loop anastomosis is done nowadays to gallbladder while doing cholecystojejunostomy in advanced malignancies with dilated patent gallbladder **(Fig. 22-133)**.


Hepaticojejunostomy is done
between common hepatic duct and jejunum

Fig. 22-129: Hepaticojejunostomy Roux-en-Y anastomosis.

RADICAL/EXTENDED CHOLECYSTECTOMY

It is done in operable cases of carcinoma of gallbladder.

Cholecystectomy with resection of liver segments IV and V—*extended cholecystectomy with perihepatic nodal clearance*. At least 2 cm margin in the liver from the gallbladder bed should be cleared. All pericholedochal lymph nodes should be removed. Frozen section biopsy from cystic duct stump should be done to identify for the existence of microscopic tumour. If present, CBD resection and hepaticojejunostomy is done. *Open approach* rather than laparoscopic is ideal for carcinoma gallbladder. Hemihepatectomy with cholecystectomy with nodal clearance.

If patient has undergone laparoscopic cholecystectomy and histology confirmed carcinoma, then staging should be done. All port areas should be reexcised to prevent *port site recurrence*. Often extended resection of segment IV and lymph nodes may be needed. Spillage of bile during laparoscopic cholecystectomy is common (30% in non-malignant GB, 50% in carcinoma GB).

Incision is Kocher's incision with extension upwards on its medial aspect or towards opposite side. Initial exploration is done for tumour extent, nodal status, and liver secondaries. Once it is felt that operable extended cholecystectomy is done. Here approach is totally different from traditional approach of cholecystectomy. Liver at gallbladder bed 2 cm away from the bed is marked on the surface; stay sutures are placed on this line and away correspondingly on the liver side. Liver is dissected between these two parallel stay sutures with classic methods—finger reaction, bipolar, ligating or clipping the biliary ductules. Ductules are ligated using 4-0 polypropylene sutures. It is deepened towards the neck of the gallbladder and Calot's triangle. One should not injure posterior sectional/sectorial duct which may come on its way. All lymph nodes are cleared at Calot's, perihepatic and on the bile duct. Cystic artery and duct is ligated close to right hepatic artery and bile duct. Duct margin is sent for frozen section biopsy. If negative wound is closed with a tube drain. If positive then common bile duct is excised (resection of CBD) along with hepaticojejunostomy **(Fig. 22-134)**.

TREATMENT OF BILE DUCT CARCINOMA/ CHOLANGIOCARCINOMA

When operable (only 5%), portal region clearance with hemihepatectomy can be done. *Intrahepatic type* is treated with hemihepatectomy. *Perihilar* is treated with hemihepatectomy or extensive bile duct resection, nodal clearance, caudate lobe removal, cholecystectomy. Distal tumour is treated with Whipple's pancreaticoduodenectomy.

Staging laparoscopy with a laparoscopic ultrasound is done. Laparotomy is done if operable with bilateral subcostal with xiphisternum extension (Mercedes Benz incision); on table ultrasound and Doppler is needed to rule out liver metastases and vascularity of the tumour. Celiac axis and hepatoduodenal lymph node dissection is done; CBD is resected distally and frozen section of the distal margin is done; if positive then pancreaticoduodenectomy is added. Hemihepatectomy is often added. Hepatic artery or portal vein involvement needs its resection and vascular grafts for reconstruction with saphenous or external iliac vein. Remnant hepatic duct is sutured to jejunum as Roux-en-Y hepaticojejunostomy using 7-0 PDS.

Most often it is inoperable. Stenting can be done to relieve jaundice, through PTC or ERCP or on table. Chemotherapy—5 FU; gemcitabine,



Figs 22-130(1)



Figs 22-130(2)

Figs 22-130(1 and 2): Redoing of hepaticojejunostomy for retained stones in the hepatic ducts and intrahepatic biliary system (By Dr Arunkumar, Mch GI surgeon).


GB
CBD
Cystic duct
Duodenum
Cutting with no.15 blade from inside outward
Cutting with monopolar cautery
Window creation in T_n mesocolon right of middle colic vessels
Opening of CBD using no. 3 knife and no. 15 blade with stay sutures in place

Figs 22-131(1)


Jejunotomy in Roux limb 1 cm proximal to end
Jejunotomy in Roux limb 1 cm proximal to end
Choledochojejunostomy
Jejunojenunostomy to complete Roux-en-Y
End-to-side Jejunostomy
Stomach
Colon
Jejunum
Doing antecolic GJ as there is duodenal obstruction

Figs 22-131(1)

Figs 22-131(1 and 2): Choledochojenunostomy (Roux-en-Y) with gastrojejunostomy (GJ) for duodenal obstruction.

cis platin; chemotherapy with external beam radiotherapy (ERBT) are other options.

Klatskin Tumour

It is cholangiocarcinoma at the confluence of the hepatic ducts and common hepatic duct above the level of the cystic duct (20% of cholangiocarcinomas). *It causes obstructive jaundice with hydrohepatosis without enlargement of gallbladder.* Management is like cholangiocarcinoma. Hilar resection with hepaticojejunostomy; segment III left hepaticojejunostomy—Blumgart's; Longmire's left hepaticojejunostomy after left liver lobe resection; Cattell's hepaticojejunostomy; Smith's mucosal graft hepaticojejunostomy; Palliative PTC with stenting/ERCP stenting, intraoperative stenting. Metal stents show long period of patency (12 months) than polyethylene stents (4 months) **(Fig. 22-135)**.

BILE DUCT INJURIES

Causes

Cholecystectomy—open or laparoscopic; trauma; instrumentation—ERCP, baby endoscope, choledochoscope; other surgeries—pancreatic, duodenal, gastric; anomalous biliary system increases the risk of injury.


Hepaticojejunostomy
Access loop
Hepaticojejunostomy
Radio-opaque
marker clips
Access loop

End of the Roux limb is sutured to pylorus through which hepaticojejunostomy can be accessed endoscopically

Access loop placed in the subparietal place fixed to fascia and marked with radio-opaque clips loop can be accessed when needed under guidance per abdominally

Fig. 22-132: Hepaticojejunostomy access loop – two approaches.


Choledochojejunostomy
Omega
loop
Kenneth - Warren stitch
Jejunojejunostomy

Loop choledochojejunostomy is not done nowadays
To loose plication sutures are placed in the afferent limb
to prevent food entering the biliary system — Kenneth-Warren stitch
Here transection of the jejunum is not done
Jejunojejunostomy is done between afferent and efferent limbs
This procedure is a surgical legacy

Fig. 22-133: Loop choledochojejunostomy with enteroenterostomy. It is not advocated commonly now.


Thickened GB
Cleared liver margin
Gall stones
Tumour
Lymph nodes removed

Fig. 22-134: Extended cholecystectomy for gallbladder carcinoma. (By Dr Arunkumar, Mch GI surgeon).


A
B
Liver
Klatskin tumor
Common hepatic duct
CBD

Figs 22-135A and B: Klatskin tumour; its location (A), and resected specimen (B).

Classifications

Strasberg classification

- Class A: Bile leak from the cystic duct or an accessory duct showing continuity with the common bile duct.
- Class B: Section/injury of an accessory duct/sectorial ducts/aberrant right hepatic duct with no continuity with the common bile duct with occlusion.
- Class C: Leak/open drainage from a sectorial duct/aberrant right hepatic duct with no continuity with the common bile duct.
- Class D: Partial section/lateral injury of an extrahepatic duct/bile duct with no complete loss of continuity with the rest of the bile duct system.
- Class E: Complete section/circumferential injury of the bile duct with subtypes according to the length of the stump at various levels.
  - E1–Stricture/injury at more than 2 cm distal to bifurcation.
  - E2–Stricture/injury less than 2 cm distal to bifurcation.
  - E3–Stricture/injury at bifurcation.
  - E4–Stricture/injury involving right and left hepatic ducts.
  - E5–Complete obstruction of entire bile duct.

Note: Only right and left partial injuries are not included in this classification

Stewart-Way classification

This classification involves four strata based on the mechanism and anatomy of injury.

- Class I: It refers to the incomplete section of bile duct with no loss of tissue. It has a prevalence rate of 8%.
- Class II: It is a lateral injury of the common hepatic duct that leads to stenosis or bile leak. It is the consequence of thermal damage and clamping the duct with surgical staples. It has a prevalence of 2% with a concomitant hepatic artery injury in 20% of cases. T-tube related injuries are included within this class.
- Class III: It is the most common (60%) represents the complete section of the common hepatic duct. It is subdivided in to type IIIa, remnant common hepatic duct; type IIIb, section at the confluence; type IIIc, loss of confluence; and type IIId, injuries higher than confluence with section of secondary bile ducts. Associated injury of right hepatic artery occurs in 25% of cases.
- Class IV: It is right (65%) and accessory right (25%) hepatic duct injuries with associated injury of the right hepatic artery (60%). Occasionally, it includes the common hepatic duct injury at the confluence (5%) besides the accessory right hepatic duct lesion (prevalence of 10%).

Hannover classification (2007)

It classifies injuries in relationship to the confluence and also includes vascular injuries.

- Type A: It refers to cystic and/or gallbladder bed leaks.
- Type B is a complete or incomplete stenosis caused by a surgical staple.
- Type C represents lateral tangential injuries.
- Type D refers to complete section of the common bile duct emphasizing their distance to the confluence as well as the hepatic artery and portal vein concomitant injuries.
- Type E is late bile duct stenosis at different lengths to the confluence.

Note: *Bismuth classification* (for open surgery/prelaparoscopic era) is discussed in biliary stricture topic earlier.

Presentations

Fever, pain, bile stasis features like cholangitis, jaundice; 10% of laparoscopic bile duct injuries are identified on table; 30% with bile leak; 25% with obstructive jaundice; 30% with cholangitis. Patients with bile leak present early; with formed biliary stricture presents with jaundice and cholangitis months or years later.

Problems

Biliary fistula with electrolyte imbalance; biliary peritonitis, septicaemia; subphrenic abscess formation; *Biloma* formation; severe malnutrition, deficiencies; late - biliary cirrhosis, portal hypertension.

Investigations

LFT, coagulation profile; US abdomen, fistulogram; Dynamic CT scan will delineate the anatomy of injury; ERCP is useful if injury is only partial where stenting can also be done. PTC is the *investigation of choice* to identify site, nature, extent of stricture. It also facilitates drainage and stenting. Hepatobiliary scintigraphy may be useful. MRCP may be useful to identify ductal anatomy. CT arteriography is useful to identify associated hepatic artery or portal vein injury which is 20% in association with CBD injury.

Management

General: Antibiotics, nutrition, TPN.
Conservative: Small partial injury to CBD may resolve spontaneously or with the help of ERCP, sphincterotomy and stenting.

Management of biliary duct injury on table (during ***laparoscopic cholecystectomy***/open): Conversion into open with a lengthy subcostal/bucket handle incision. Intraoperative cholangiogram should be done. Partial injury of CBD less than 30% of circumference is treated with primary repair with a T-tube in place. Extensive injury more than 30% of the circumference or cautery injury or complete CBD transection should be treated with Roux-en-Y choledochojejunostomy. Isolated hepatic duct injury less than 3 mm in size should be ligated. More than 3 mm in size should be reimplanted or Roux-en-Y hepaticojejunostomy should be done. If facility for surgical repair is available, patient should be sent to a higher centre after placing a drain with abdomen closure.

Management of bile duct injury identified at a later period: In such situation it is better to wait for 6 weeks to subside inflammation which facilitates easier proximal CBD identification. After proper assessment of injury, Roux-en-Y choledochjojejunostomy or *Roux en Y hepaticojejunostomy* is done.

Hepp–Couinaud approach: Here hilar plate is meticulously dissected; left hepatic duct is anastomosed to Roux jejunal loop to create hepaticojejunostomy often with creation of proximal 'access loop' for future endoscopic approach. Complications are—recurrent cholangitis, bile leak from stoma, haemobilia, stenosis of biliary enteric anastomotic site (10%; occurs often after many years).

CHOLECYSTOJEJUNOSTOMY

It is not commonly advocated now. It is indicated in advanced pancreatic malignancy as a bypass as life expectancy in these patients is short. It is often combined with gastrojejunostomy whenever there is duodenal obstruction. It is a palliative procedure in obstructive jaundice due to advanced malignancy in head of pancreas or periampullary carcinoma. It is not done in benign disease and in conditions where long-term results are anticipated. It is possible to do only if there is patency of cystic duct and the common bile duct so that obstructive jaundice is relieved through patent cystic duct into jejunum. Additional enteroenterostomy is also done (Braun) **(Fig. 22-136)**.


Midline laparotomy
Liver secondaries with obst jaundice with gastric outlet obstruction
Stomach
Jejunum
Colon
Posterior layer GJ
Anterior antecolic GJ is completed
GB
Jejunal loop
Beginning of cholecystojejunostomy
GB
Jejunum
Stay sutures are placed
Gall bladder is opened at fundus
Jejunum is opened

Figs 22-136(1)


Posterior layer vicryl suturing is done
Anterior layer suturing
Anterior layer suturing completed
Cholecystojejunostomy
Optional 2nd layer -seromuscular
CCJ
Jejunojejunostomy (Loope — Braun)
Jejunojejunostomy (Loope — Braun)

Figs 22-136(2)

Figs 22-136(1 and 2): Technique of palliative gastrojejunostomy and loop cholecystojejunostomy with jejunojejunostomy (Braun) as a palliative procedure. Patient has got liver metastasis.

Technique: Midline laparotomy is sufficient. First antecolic gastrojejunostomy is done to anterior wall of the stomach. Then next jejunal loop is selected for anastomosing into the fundus of the gallbladder. Gallbladder is aspirated to confirm presence of bile. Preoperative CT may be useful to assess cystic duct patency. It also can be confirmed by on table dye study. Stay sutures are placed between fundus of gallbladder and jejunal loop. Fundus is opened horizontally; jejunum is opened on its antimesenteric border little lesser size than that of fundus of gallbladder. Usually single layer is sufficient. However, if two layer anastomosis is planned, posterior seromuscular layer is placed using interrupted silk or vicryl sutures. Full thickness posterior seromucosal 2nd layer is sutured using continuous or interrupted 3-0 vicryl. Third layer full thickness anterior seromucosal layer is placed similarly; finally anterior seromuscular interrupted sutures are placed. Between afferent and efferent limb of the anastomosis enteroenterostomy is done using single layer continuous vicryl suture. Abdomen is closed in layers without drain. Nasogastric tube is removed after 72 hours. Jaundice will reduce in 10 days; patient can eat food as palliation.

Complications*:* Cystic duct may get blocked and jaundice will reappear. Severe cholangitis may develop.

TREATMENT OF CHOLEDOCHAL CYST

Types of choledochal cysts (Todani modification of Alonso-Lej classification) **(Fig. 22-137)**.
Type I: Dilatation of extrahepatic biliary tree (60%).
Type Ia—Cystic.
Type Ib—Focal segmental (saccular).
Type Ic—Fusiform.
Type II: Diverticulum of extrahepatic biliary tree (5%).
Type III: Choledochocoele—cystic dilatation of intraduodenal part of CBD (5%).
Type IV: Dilatation of extra- and intrahepatic or multiple parts of extrahepatic biliary tree (30%).
Type IVa: Dilatation of extrahepatic and intrahepatic biliary tree. It is 2nd most common.
Type IVb: Dilatation of multiple sections of the extrahepatic bile duct.
Type V: Dilatation of the only intrahepatic biliary tree (*Caroli's disease*) **(Figs 22-138 and 22-139)**.

Treatment

Choledochal cyst should be treated to avoid possible late complications of the cyst—cirrhosis, portal hypertension, abscess formation, malignant changes (cholangiocarcinoma).

Resection of extrahepatic biliary tree with removal of choledochal cyst along with cholecystectomy and Roux-en-Y hepaticojejunostomy is the ideal treatment for choledochal cyst especially types I, II and IVb. In Type I—excision of cyst with its mucosa and reconstruction by Roux-en-Y hepaticojejunostomy is done. In Type II—excision of the diverticulum and suturing of the CBD wall is done. In type III—endoscopic sphincterotomy is done. Excision is also often needed. Intrahepatic dilatation is difficult to treat. If it is localised, hepatectomy is sufficient, but if it is diffuse, liver transplantation may be required. In type IV if cyst is adherent to portal vein posteriorly, that part of the cyst wall over the portal vein is left behind. But mucosa of the part should be removed (*Lily's operation*). Liver resection is often necessary



Fig. 22-137: Different types of choledochal cysts—(1) Fusiform type, (2) Saccular type, (3) Choledochocoele, (4) Fusiform + Intrahepatic type, (5) Intrahepatic type.



Fig. 22-138: Pancreaticobiliary maljunction. Here pancreatic duct joins CBD more proximally than normal causing reflux of pancreatic enzymes into the CBD. It leads into weakening, dilatation and choledochal cyst.


Choledochal cyst-MRI

Fig. 22-139: MRI of choledochal cyst.

in type IV. Frozen section biopsy of the choledochal cyst should be done for possible chances of existing cholangiocarcinoma; if biopsy becomes positive then hepatic resection along with bile duct resection is needed. Caroli's disease needs liver transplantation.

When CBD excision with cholecystectomy is done; distal CBD is washed using cystoscope to remove all stones, debris. Level I excision will retain cyst mucosa; level II will be adequate; level III is likely to damage the pancreatic duct as there will be biliopancreatic malposition with pancreatic duct joining he bile duct much more proximally than normal **(Figs 22-140 and 22-141)**.

Note: Cystoenterostomy should not be done for choledochal cyst.

Complications of Surgery

Ascending cholangitis; formation of intrahepatic biliary stones; pancreatic stones formation; malignancy—cholangiocarcinoma; pancreatitis; liver disease and failure.

BILIARY ATRESIA—TREATMENT

Classification

Correctable—10%; Noncorrectable—90%.

Biliary Atresia

Type I: Atretic CBD—10%
Type II: Atretic CBD and common hepatic duct
Type III: Atretic CBD, common hepatic duct and right and left hepatic ducts—88% **(Fig. 22-142)**

Biliary atresia can be:

Perinatal acquired (70%) type is not associated with congenital anomalies. *Fetal/embryonic* (30%) is associated with congenital anomalies. It may be associated with other congenital anomalies (20%) of the GIT—(malrotation, annular pancreas duodenal atresia) and congenital heart diseases, polysplenia, situs inversus, absent vena cava, preduodenal portal vein.

Treatment

In correctable cases: Roux-en-Y jejunal anastomosis is done; In noncorrectable cases, hepaticoportojejunostomy (*Kasai's operation*). Liver transplantation is becoming more popular in biliary atresia—ideal.

Presently *Kasai (1974) hepatoportoenterostomy* (Kasai and Susuki, 1959) is done (in 8 weeks) as a preliminary procedure followed by liver transplantation eventually. After opening the abdomen, gallbladder is cannulated and on table cholangiogram is done to confirm atretic segment. Liver biopsy should also be done at the same time **(Fig. 22-143)**.

If biliary patency is found procedure is abandoned. In atretic biliary tree, gallbladder is dissected off the liver and by applying traction to it; fibrotic atretic biliary tree is felt and dissected up to intrahepatic segment (up to the segmental branches of portal vein). Atretic extrahepatic tissue is removed to open up the microscopic ductules. Portal plate (edge of the dissected fibrous mass in portal plate)/hepatic hilum is anastomosed to Roux-en-Y part of the small bowel. Postoperatively, antibiotics, intravenous corticosteroids initially, later orally (for 6-12 weeks), ursodeoxycholic acid (for 1year), nutrition, medium chain and essential fatty acids, essential elements supplementation is given. Success of procedure depends on age of the patient; presence of cholangitis; ductule size (more than 200 µm is better); bridging fibrosis; type of atresia; bilirubin level. Eventually cholangitis, portal hypertension, variceal bleeding will develop.


Removal at level I
Removal at level II
Removal at level III
Choledochal cyst
- Resection CBD-supraduodenal portion
- Removal of stones from distal part
- Warm saline irrigation of distal part
- If needed mucosectomy of distal part
- Frozen section biopsy may be needed to rule out cholangiocarcinoma
- Always cyst is removed along with gallbladder
- Cystoscopic view for irrigation of the distal part is better
Roux-en-Y hepaticojejunostomy is done
Removal at level I - Incomplete
Removal at level II - Ideal - adequate
Removal at level III - Dangerous - can damage pancreatic duct

Fig. 22-140: Surgical technique for choledochal cyst.


Cor > sag -7
C cyst
GB
View from behind
Cor > sag -1
C cyst
View from front
C cyst
C cyst
C cyst
Clamping lower margin of cyst
Cutting lower margin
Lower cut end is closed after irrigating distal CBD
Proximal — cut end hepatic duct
Creation of Roux loop
Completed end-to-side choledochojejunostomy
Resected cyst with gallbladder
Jejunojejunostomy to complete Roux-en-Y anastomosis

Fig. 22-141: Operative technique of choledochal cyst excision.


Liver
10%
Type I
Liver
2%
Type II
Liver
88%
Type III

Fig. 22-142: Biliary atresia—types.


Type III- most common type of biliary atresia
Roux-en-Y anastomosis is done to the edge of the dissected fibrous mass of tissue in the portal plate

Fig. 22-143: Kasai hepatoportoenterostomy.

Chapter 23

Surgeries of Pancreas and Spleen

THE PANCREAS

SURGICAL ANATOMY

It was Rufus of Ephesus who named the organ 'pancreas', which in Greek means Pan—all; Kreas—flesh/meat. Homer used the word 'sweetbread' to describe it as animal flesh; but the fact is that it becomes bitter to the surgeons and not sweet when it develops major disease like pancreatitis. Moynihan described pancreas as an 'abdominal tiger'. The pancreas is a gland located deep in the abdomen between the stomach and the spine (2nd and 3rd lumbar vertebrae). The liver, intestine and other organs surround the pancreas. It extends on the right side from duodenum towards spleen on the left side.

The pancreas lies in the retroperitoneum within the anterior pararenal space. The head is the portion of the gland lying within the C-loop curve of the duodenum. The head is prolonged inferiorly and medially to extend behind the superior mesenteric vein. The uncinate process usually stops short at the level of the right renal hilum inferiorly.

The neck of the gland is the constricted segment of the gland lying anterior to the superior mesenteric vessels. The body is a horizontal segment of the gland lying behind the lesser sac and stomach. Dorsal to the body runs the splenic vein. The tail of pancreas may be inclined slightly cephalic to the level of the head. It follows the splenic vessels into the splenic hilum **(Fig. 23-1)**.



Fig. 23-1: Ductal parts of the pancreas.

The pancreas is about 15 cm long, 3 cm broad and 1.5 cm thick and is flat pear/retort shaped. It weighs around 100 g. The widest part of the pancreas is the head, the middle section is the body, and the thinnest part is the tail. Pancreas is a fixed organ. Omental bursa is above; transverse mesocolon is in front; greater sac is below the pancreas. Above it is related to 1st part of the duodenum, pylorus, stomach, liver and spleen. Below it is related to 3rd part of the duodenum, jejunum, transverse colon and spleen. Inner part of the 1st, 2nd and 3rd parts of the duodenum is closely adherent to the corresponding parts of pancreas and duodenum here is not having peritoneal coverage and is called as bare area of duodenum. Posteriorly pancreas extends from hilum of kidney to hilum of spleen. It is related behind to hilum of kidney, IVC, superior mesenteric vein and portal vein, aorta, left kidney and hilum of spleen **(Fig. 23-2)**.



Fig. 23-2: Parts of the pancreas.

Head lies to the right of the superior mesenteric vessels. It is adherent to the inner part of the C-loop of the duodenum. Posteriorly it is related to the hilum and adjacent right kidney, right renal vessels, IVC, left renal vein entering IVC, right crus of the diaphragm, posterior pancreaticoduodenal arcade, right gonadal vein and distal CBD.

Neck is 1.5 cm in length; lies between celiac trunk above and superior mesenteric vessels below. Its junction with the head is at an imaginary line from the portal vein to the superior mesenteric vessels below. Anterior superior pancraticoduodenal artery originates from the gastroduodenal artery near the upper part of the neck of the pancreas at this junction. Behind the superior mesenteric vein joins the splenic vein to form portal vein. Small veins may enter the portal vein and the superior mesenteric vein directly from the neck of the pancreas. Short and often stout lateral veins may enter it from its lateral part to portal vein; left gastric, splenic and rarely inferior mesenteric vein may enter the portal vein from the left side.

Lower posterior part of the head of the pancreas extends behind the superior mesenteric vessels and in front of IVC and aorta is known as ***uncinate process***. It gets blood supply from the superior mesenteric vessels through very short vessels. One should ligate these vessels carefully while dissecting the uncinate process, otherwise tear of these vessels may lead into torrential bleeding. Occasionally this process may be absent or encircle superior mesenteric vessels completely. Left renal vein is above it; duodenum is below it. An anomalous right hepatic artery may pass through the uncinate process after originating from the superior mesenteric artery.

Pancreas lying towards the left of the neck/superior mesenteric vein is known as ***body of pancreas***. It is related to the 4th part of the duodenum, suspensory ligament of Treitz, first part of jejunum, left side transverse colon. Superior mesenteric vein and artery run between head and uncinate process to run in front of the duodenum. Vein is towards the right of the artery. Above body of the pancreas is related to celiac axis, common hepatic artery and splenic vessels from right to left. In front, it is covered by posterior wall of the omental bursa which has got two layers of the peritoneum. Stomach covers in front of it. Transverse colon with its two leaves is also in front of it. Middle colic vessels are connected here. Middle colic artery after originating from superior mesenteric artery runs between two leaves of mesocolon. Inferior mesenteric vein runs close to inferior border of the distal part of the body of pancreas to join splenic vein. Posteriorly it is devoid of peritoneum and is related to aorta, origin of superior mesenteric artery, left crus of diaphragm, left suprarenal gland, left kidney, left renal vessels and splenic vein **(Fig. 23-3)**.



Fig. 23-3: Posterior relations of the pancreas.

Tail of the pancreas is the distal most part of the pancreas; its tip is related to spleen; it is enveloped within two layers of splenorenal ligament along with the splenic vessels. Tail of the pancreas may be mobile.

Pancreas is long, flat and irregularly prismatic in shape; its right extremity, being broad, is called the head, and is connected to the main portion of the organ, or body, by a slight constriction, the neck; while its left extremity gradually tapers to form the tail. It is situated transversely across the posterior wall of the abdomen, at the back of the epigastric and left hypochondriac regions. Conventionally it shows two segments; cephalocervical right segment is supplied by gastroduodenal and superior mesenteric arteries. Left-sided corporocaudate segment is supplied by splenic and dorsal pancreatic arteries. Junction of two segments is relatively avascular.

The main pancreatic duct (duct of Wirsung) opens at the major duodenal papilla, measuring 3-4 mm in diameter in adults. It enlarges slightly with advancing age. The diameter of the duct tapers to 1-2 mm toward the tail. A slight narrowing at the head and body of the pancreas is a normal variation. The accessory pancreatic duct (duct of Santorini) opens at the minor duodenal papilla, proximal to the major duodenal papilla. Both bile and pancreatic ducts open into the duodenum in 60% of individuals; in 30%, duct of Santorini ends blindly and duct of Wirsung carries the secretion; in 10%, duct of Wirsung may be small or absent and duct of Santorini secretes entirely.

On cross-sectional images, the measurements of normal pancreas diameters generally are as follows: head of the pancreas, 3 cm; neck and body of the pancreas, 2.5 cm; and tail, as long as 2 cm.

The position, size and shape of the pancreas vary among patients. The pancreas gradually diminishes with advancing age, sometimes becoming more marked beyond the seventh decade. The surface of the pancreas is smooth in 80% of patients and lobulated in approximately 20%. Ampulla of Vater is situated on the posteromedial wall of the 2nd part of the duodenum; right of 2nd and 3rd lumbar vertebrae (commonly at the level of spine of 2nd lumbar vertebra). Muscular sphincteric complex (Sphincter of Oddi, 1887; sphincter of Boyden) is obliquely placed of 6-30 mm in length, contains four separate sphincters—superior bile duct sphincter, inferior submucosal bile duct sphincter, pancreatic sphincter and ampullary sphincter. Papilla is found in the mucosa (on endoscopy) where longitudinal mucosal fold meets the transverse fold like a 'T'. Papilla is nipple-like projection of duodenal mucosa; major duodenal papilla is located on the posteromedial wall of the 2nd part of the duodenum 10 cm from pylorus (but may vary); minor duodenal papilla is located 2 cm proximal to major papilla **(Figs 23-4 and 23-5)**.


Opening of ampulla of Vater is at the junction of transverse mucosal fold and longitudinal mucosal fold

Fig. 23-4: Orifice of ampulla of Vater in the duodenal mucosa.



Fig. 23-5: Sphincter complex of Ampulla of Vater.

Ampulla (ampulla of Vater; Abraham Vater, 1684) is slightly widened common pancreaticobiliary channel beyond the septum. Ampulla will not be obvious if septum between bile duct and pancreatic duct extends up to the orifice. Variations are—I: The pancreatic duct joins bile duct at a variable distance; II: The pancreatic and bile ducts open separately on the major duodenal papilla (5%); and III: Both ducts open into the duodenum at separate points (10%) **(Figs 23-6A to C)**.

The pancreas produces insulin and other hormones—exocrine and endocrine both. The pancreas also produces pancreatic enzymes that help to digest food. The pancreas releases the juices into a system of ducts leading to the common bile duct. The common bile duct empties into the second part of the duodenum through the ampulla of Vater.

Blood Supply

Arterial Supply

The gastroduodenal artery is the descending branch of common hepatic artery which courses in front of the portal vein. The first branch of this artery is the superior posterior pancreaticoduodenal artery which descends posteriorly along the common hepatic duct to anastamose with posterior branch of inferior pancreaticoduodenal artery forming the posterior arch. The superior anterior pancreaticoduodenal artery runs in the curve of the duodenum down to anastomose with anterior branch of inferior pancreaticoduodenal artery to form the anterior arch. The inferior pancreaticoduodenal artery begins behind the uncinate process of the pancreas as the first right branch of the **superior mesenteric artery** and divides after a short distance into an anterior and a posterior branch. Arteria pancreatica magna takes off from the splenic artery and joins into the glandular parenchyma at the level of the passage from the middle part to the left third of the tail of the pancreas. The artery of the tail of the pancreas is represented by four arterial trunks which surround the pancreatic tail. They originate from the left gastroepiploic artery or from the so-called main inferior trunk of the splenic artery. Dorsal pancreatic artery arises from splenic artery at the neck of the pancreas close to its origin from celiac trunk. Right branch of dorsal pancreatic artery supplies head of pancreas after joining posterior superior pancreatic arcade; its left branch runs in a groove on the inferior margin of the pancreas known as transverse or inferior pancreatic artery which supplies body and tail of the pancreas. Dorsal pancreatic artery may arise from the celiac trunk or common hepatic artery. Major arteries of pancreas lie posterior to pancreatic duct. Splenic artery runs tortuously towards left along the upper and posterior surface of the body and tail of the pancreas. Splenic artery gives branches which communicate with inferior pancreatic artery. Arteria pancreatica magna is also known as great pancreatic artery after originating from splenic artery anastomoses with inferior pancreatic artery **(Figs 23-7A to C)**.

Caudal pancreatic artery is often present; originating from splenic artery or left gastroepiploic artery (is a branch of splenic artery); it communicates with transverse pancreatic artery and arteria pancreatica magna. It also supplies accessory spleen when present. Anomalous right hepatic artery is a common variation observed which arises from SMA which runs behind the CBD or portal vein; it may be accessory to normally existing right hepatic artery (a branch of common hepatic artery) or replacing the right hepatic artery, in which case it is the only supply to the right liver. Occasionally aberrant left hepatic artery may arise from SMA or gastroduodenal artery. These variations are important while doing Whipple's pancreaticoduodenectomy or total pancreatectomy. Middle colic artery may arise from dorsal pancreatic or inferior pancreaticoduodenal arteries instead of SMA. Middle colic artery is usually close to uncinate process but it may pass through the head of pancreas or run close to the 2nd part of the duodenum as variation in pathway. Body and tail of pancreas usually derive their arterial supply from branches of both splenic artery and dorsal pancreatic artery (50%); but dorsal pancreatic artery may be entirely absent and body and tail of pancreas are exclusively supplied by splenic artery (25%); or there may not be any branches from the splenic artery to the body and tail of the pancreas and blood supply is exclusively from the dorsal pancreatic artery (25%).



Normal pattern
Both pancreatic ducts
open into the duodenum

Accessory Santorini duct
ends blindly

Duct of Wirsung is smaller than Santorini
and both are not connected

Figs 23-6A to C: Different duct patterns in pancreas.


Hepatic artery
Coeliac artery
Splenic artery
Gastro-duodenal artery
Superior pancreatico-duodenal artery
Superior mesenteric artery
Arteria pancreatica magna
A
Inferior pancreaticoduodenal artery
Proper hepatic artery
Common hepatic artery
Stomach (removed/reflected) outline
Right gastric artery
Left gastric artery
Celiac trunk
Supraduodenal artery
Dorsal pancreatic artery
Gastroduodenal artery
Splenic artery
Superior pancreatico-duodenal artery
Anterior and posterior branches of superior pancreaticoduodenal artery
Transverse pancreatic artery
Anterior and posterior branches of inferior pancreaticoduodenal artery
Duodenal branch of 1st jejunal artery
SMA
Inferior pancreatico-duodenal artery
B
Splenic artery
Right gastroepiploic artery
Gastroduodenal artery
Common hepatic artery
Superior pancreaticoduodenal artery
Inferior pancreaticoduodenal artery
SMV
SMA
C

Figs 23-7A to C: Arterial supply of the pancreas.

Ampulla is supplied by posterosuperior pancreaticoduodenal artery through epicholedochal plexus. Anterosuperior pancreaticoduodenal artery may get injured in pancreaticojejunostomy as drainage procedure for chronic pancreatitis.

Venous Drainage

The venous drainage from the head of the pancreas drains into the portal vein via pancreaticoduodenal veins and several small veins which drain directly into the portal vein in the medial and inferior aspect. The inferior pancreatic vein courses along the inferior margin of the pancreas and receives different small veins. It flows into the inferior or the superior mesenteric vein. Veins are superficial to arteries; both arteries and veins are deep to the pancreatic duct system. Duct → veins → arteries—is the pattern from front to back. Anterior superior pancreaticoduodenal vein and/or right gastroepiploic vein may join with a colic vein to form a common short gastrocolic trunk which joins the SMV on its right side. This trunk should be ligated in pancreatic resections. Posterior superior pancreaticoduodenal vein joins portal vein on the upper margin of the pancreas **(Fig. 23-8)**.

Posterior inferior pancreaticoduodenal vein joins SMV. Small branches enter the right side of the SMV and portal vein from head of the pancreas which should be ligated in Whipple's operation. Usually there are no branches in front of the SMV and portal vein underneath the neck of the pancreas, but as a variation, veins can be present. SMV joins splenic vein behind the neck of the pancreas to form portal vein. Inferior mesenteric vein usually joins splenic vein but may join portal vein or SMV directly. CBD is on the right side of the portal vein; common hepatic artery on the left side and IVC behind it. Right gastric vein joins portal vein above the joining of the left gastric (coronary vein); left gastric vein may join portal or splenic vein.

Lymphatic Drainage

The lymphatic ducts which drain the pancreas course towards the lymph nodes situated near the gland following the artery. The first tier of lymph nodes are situated on the surface of the pancreas and the second tier of lymph nodes are situated along the gastroduodenal and hepatic vessels near the head and along the splenic artery in the region of the body and tail of the pancreas. Drainage is centrifugal.


Superior pancreatico-duodenal vein
Portal vein
Splenic vein
Inferior mesenteric vein
Superior mesenteric vein
Inferior pancreatico-duodenal vein
A
Stomach (reflected/removed outline
Portal vein
Left gastric vein
Splenic vein
Left gastroepiploic vein
Anterior and posterior superior pancreaticoduodenal vein
Anterior pancreatico-duodenal venous arcade
Anterior and posterior inferior pancreaticoduodenal vein
SMV
Inferior pancreatic vein
Inferior mesenteric vein
Right gastroepiploic vein
B

Figs 23-8A and B: Venous drainage of pancreas.

Cubilla et al. classified lymphatic drainage nodes into 5 groups—superior, anterior and posterior part of superior part of head, body, gastric → superior nodes drain into the suprapancreatic lymph nodes along the upper border of the pancreas; *inferior*—anterior and posterior parts of inferior part of head, body → inferior nodes drain into the inferior pancreatic group of lymph nodes which drain into the superior mesenteric nodes, left lateral aortic lymph nodes and may reach lumbar lymphatic trunk through a collecting duct; *anterior*—anterior pancreaticoduodenal, pyloric and mesenteric—drains anterior part of both superior and inferior portions of the head of pancreas—anterior nodes → 2 collecting ducts → infrapyloric and anterior pancreaticoduodenal nodes → nodes in the root of the mesentery; *posterior*—posterior pancreaticoduodenal, along common bile duct—drains from posterior surface of the superior and inferior parts of the head of the pancreas → reaches right lateral aortic nodes and nodes at origin of the superior mesenteric artery and lymphatics from bile duct and ampulla reaches to posterior pancreaticoduodenal lymph nodes; *splenic*—along its hilum and tail of the pancreas. Lymph flow is from pancreas to duodenum **(Fig. 23-9)**.


Superior pancreatic nodes
Left gastric nodes
Pyloric nodes
Splenic nodes
Pancreatico-duodenal nodes
Superior mesenteric nodes
Inferior pancreatic nodes
Aortic nodes
Nodes in the root of the mesentery

Fig. 23-9: Lymphatic drainage of pancreas.

There are no lymphatic communications between pancreatic nodes and gastric nodes. So, omentectomy is not necessary in pancreatic resections for malignancies. Lymphatics from head of the pancreas may reach hepatic nodes along the bile duct and common hepatic artery. Lymphatics of the head finally drain into nodes right of the celiac and superior mesenteric arteries. Lymphatics from the body and tail drain to the nodes left of the celiac and superior mesenteric arteries. Lymphatics from the head usually will not travel towards the body and tail. All drain finally towards the aortic nodes. Proper Whipple's pancreaticoduodenectomy should include removal of 35 nodes; total pancreatectomy should include 70 nodes. For adequate staging of pancreatic cancer, 15 nodes are needed.

Nerve Supply

Preganglionic sympathetic supply is derived from preganglionic efferent fibers of 5th to 9th thoracic segments to form greater splanchnic nerve. Fibers from 10th and 11th segments form lesser splanchnic nerve. Occasionally some fibers form the least splanchnic nerves. These nerves pass across the crura of diaphragm to supply celiac and superior mesenteric ganglia. Postganglionic branches from these ganglia reach the pancreas through its arterial branches. Cell bodies of efferent fibers are interconnected with the cell bodies of the dorsal root ganglia of spinal nerve of the same level; hence pancreatic pain refers to the abdominal wall. Parasympathetic supply is by celiac division of the posterior vagus. Efferent fibers from the brain reach celiac ganglion and then reach ganglion cells in the pancreas; their postganglionic fibers supply islet of Langerhan cells. Surgical significance of celiac ganglion is for managing the pancreatic pain by celiac plexus block, splanchnicectomy, and guided celiac injection, etc. Pain in chronic and relapsing pancreatitis is due to raised intraductal pressure (ductal hypertension), fibrosis of pancreas, multiple strictures, pancreatic ischaemia, multiple pseudocysts and pancreatic neuropathy. Pancreatic neuropathy is due to neural and perineural inflammation of intrapancreatic nerves with infiltration of immune cells. In carcinoma pancreas, initially tumour is painless but once perineural invasion by tumour cells occurs, then typical pain develops.

GENERAL PRINCIPLES IN PANCREATIC SURGERIES

Pancreas is an organ located deep in the retroperitoneum extending from right to left side. Its clear anatomy, vasculature and relations are to be known while doing pancreatic surgery. Variations and major vessels should be tackled carefully. 60% of the gland is in the body and tail of the pancreas. Only 40% of the gland will be removed in Whipple's operation.

Preservation of duodenum in surgeries of pancreatic head is difficult due to strong attachment of pancreas and vascular arcade. Preoperative imaging is essential. Helical CT scan with contrast to arterial and portal venous phase is needed. ERCP, endoultrasound (EUS), MRI may be needed in selected patients. Liver function tests, prothrombin time, coagulation profile, adequate hydration is needed preoperatively. Laparoscopic assessment prior to opening the abdomen is better to assess the final operability **(Fig. 23-10)**.

Pancreas is reached by dividing gastrocolic ligament (greater omentum). It can be reached through hepatogastric ligament (lesser omentum) also. Vagus is usually preserved.

Hepatic flexure is better to be mobilised to reach and expose the head of pancreas adequately—**Cattell-Braasch** manoeuvre; ***Kocherisation of the duodenum*** is a must in all pancreatic surgeries in relation to head. In Whipple's operation and total pancreatectomy, extended Kocherisation is needed wherein 2nd part of the duodenum is mobilized beyond the left, margin of the aorta. Peritoneum lateral to the 2nd part of the duodenum is incised above and below; posteriorly IVC with its fascial covering is seen; plane is loose areolar and is relatively avascular; left index and middle fingers are placed behind the duodenum through the incision; left thumb is placed in front; it allows proper palpation of head of the pancreas to assess the size and possible operability. But this will not clearly indicate the portal vein invasion.

Left hand index finger is passed from above underneath the neck gently downwards in front of the portal vein; right hand index finger is passed similarly in front of SMV from below upwards to reach the opposite finger. Care should be taken to keep the fingers strictly in front which is usually avascular (laterally draining veins enter SMV and portal vein and so finger should not pass laterally). Even though it is crude it reasonably confirms the operability. But better is always preoperative dynamic imaging with arterial phase to confirm the operability. Gastrocolic omentum and splenic flexure should be mobilised downwards adequately to expose the body and tail of the pancreas.

It is the invasion or encasement of the SMA or celiac trunk precludes the resection in malignancy. Portal vein / SMV invasion is not considered as unresectable. It is still resectable with resection of segment of vein with placement of patch graft over it. These invasions can be assessed properly by endoultrasound, MRI, arteriogram or venous and arterial phase in CT.

Once operability is confirmed in Whipple's operation, then only superior and inferior pancreaticoduodenal arteries should be ligated; as their ligation causes duodenal and pancreatic head necrosis.

In pancreaticoduodenectomy, bile duct is usually resected above the level of cystic duct, and cystic duct and hepatic duct margins should be sent for frozen section biopsy **(Fig. 23-11)**.

Presently pylorus preserving pancreaticoduodenectomy is favoured. Duodenum is transected just distal to the pylorus. But cut margin should be sent for frozen section biopsy prior to proceeding with the further steps of pylorus preserving pancreaticoduodenectomy **(Figs 23-12 and 23-13)**.

In distal pancreatectomy, ligation of splenic artery and vein leads into splenectomy. If short gastric vessels are preserved, spleen can be salvaged even though splenic vessels are ligated; it is called as ***Warshaw procedure***; but late development of splenic congestion and gastric varices can occur.

Portal vein anomaly and right hepatic artery anomalies should be remembered while doing pancreatic resection.

Secure anastomosis, patience and postoperative care are needed in all patients. Sepsis, bile and pancreatic leak, pancreatic pseudoaneurysm, renal failure, liver failure, disseminated intravascular coagulation, postoperative haemorrhages are the possible different complications which can occur in pancreatic surgeries. Daily monitoring, clinically, biochemically, often imaging are needed during postoperative care **(Fig. 23-14)**.



Fig. 23-10: Insulinoma in the body of pancreas. Enucleation can be done; but if multiple in the body and tail of the pancreas, distal pancreatectomy is needed.



Fig. 23-11: Partial pancreatectomies—types—95% subtotal; 85% subtotal; Whipple's; distal.



Fig. 23-12: Exposure of the pancreas. It needs mobilisation of the right flexure of colon and transverse colon, often leaves flexure also.



Fig. 23-13: In pancreaticoduodenectomy, whether portal vein and SMV are free of tumour (not adherent to portal vein) is assessed by placing left index finger between neck of pancreas and portal vein; right index finger between neck and SMV; both fingertips if felt easily and freely to be in contact with each other, then portal invasion/adhesion is not present.

SURGICAL TREATMENT FOR CHRONIC PANCREATITIS

Indications for Surgery

Persisting pain is the main indication; severe malabsorption; suspicion of malignant transformation; multiple relapses; complications like pseudocyst, segmental portal hypertension; biliary obstruction (*Wadsworth syndrome*); pseudocyst; pancreatic ductal dilatation > 5 mm; pancreatic ascites/fistula; pancreatic ductal stenosis.

Objectives of Surgery

Pain relief when endotherapy has failed; management of complications; procedure is selected which shows less morbidity and mortality; Quality of life (QOL) should be preserved.

Problems and Limitations of Surgery

Disease is irreversible parenchymal and ductal damage and so surgery *cannot cure* or reverse completely. Disease progression cannot be prevented or arrested by surgery. Risk of development of cancer continues. Complications of surgery are a drawback.

Benefits of Surgery in Relation to Pain Relief and Obstruction

It relieves intraductal, interstitial, intracellular hypertension through drainage procedures. Entrapped nerves are released and reduction in pancreatic enzyme reduces nerve irritation—resectional methods. *Pacemaker*—head of pancreas is removed in head-coring procedure (Frey's) to relieve pain. It is less morbid and acceptable method. Resection is better than the drainage procedure but technically demanding and has got higher mortality.

Principles of Surgery

Pancreatic duct decompression (*drainage*) reduces the pain and retains the existing exocrine and endocrine functions. But chances of malignant transformation are still high. In significant number of patients, recurrence of symptoms (50% recurrence of pain in 5 years) and progression of the disease pathology occur and it does not give a complete cure. Normal diameter of pancreatic duct is 4 mm in head; 3 mm in body; 2 mm in tail of the pancreas. *Pancreatic duct diameter more than 5-7 mm is an indication for surgery (pancreaticojejunostomy)*. *Pancreatic resection* (total pancreatectomy) is the actually ideal technique which relieves pain, removes entire diseased tissue. But technical difficulty; high surgical mortality (21%); and severe exocrine and endocrine deficiency (brittle diabetes) are the drawbacks. Head of pancreas is considered as pacemaker and origin of the pancreatitis disease and so pancreaticoduodenectomy (*Whipple's*) is the other option to give adequate relief. It is preferred in patients who are having relatively normal body and tail of the pancreas. Occasionally when the disease is limited to tail and body, then *distal pancreatectomy* with or without splenectomy often with distal pancreaticojejunostomy may be done. But it is not beneficial if disease is extensive and diffuse. Resection is the main method of treatment if ductal dilatation is not adequate. *Combined resection and drainage procedures* are also done. Head is decored at various levels and decompressed duct is anastomosed to jejunum.

Patient should completely stop alcohol and smoking after surgery. Nutrition should be reasonably adequate; serum albumin should



Figs 23-14(1)



Figs 23-14(2)

Figs 23-14(1 and 2): Pancreatic pseudoaneurysm—patient underwent removal of pseudoaneurysm and distal pancreatectomy. Intervention radiology is ideal; but when it fails surgery is the option.

be more than 3g %. Otherwise surgery is done after improvement of nutrition. Proper preoperative evaluation is a must.

Proper preoperative evaluation, assessment of variations in portal vein and arterial pattern, frozen section biopsy are important in all pancreatic surgeries.

Exposure of pancreas needs mobilisation of the right flexure of colon (Cattell-Braasch) transverse colon and often left flexure also; extended Kocherisation (duodenal mobilization), separation of stomach from anterior part of the pancreas, separation of spleen and tail of the pancreas from left adrenal gland, left kidney and left renal vessels.

Meticulous dissection, control of bleeding and using bipolar cautery or other energy sources minimise the bleeding and improve and hasten the dissection.

Anastomosis in pancreatic surgery should be careful, skilled and meticulous as leak from pancreas will be disastrous **(Figs 23-15 to 23-17)**.



Fig. 23-15: CT scan of chronic pancreatitis.



Fig. 23-16: ERCP showing pancreatic duct pathology with strictures.



Fig. 23-17: X-ray showing multiple pancreatic stones.

Surgeries

1. *Puestow's operation* [*Puestow-Gilesby* (1958)]: As the duct is dilated more than 7-8 mm, duct can easily be opened longitudinally. After removing all stones from the duct, it is anastomosed to the jejunum as *Roux-en-Y anastomosis.* In Puestow's operation, spleen is removed **(Fig. 23-18)**.
2. *Partington-Rochelle operation/Modified Puestow's Operation (1960)*: Here longitudinal pancreaticojejunostomy is done using almost entire laid open pancreatic duct. Spleen is retained in this procedure. This is now a commonly done procedure **(Fig. 23-19)**.


Oesophagus
Puestow's operation
Stomach
Spleen removed
Pancreas
Duct
Duodenum
Jejunum
Jejunal loop is telescoped into the entirely mobilised body and tail of pancreas and fixed

Fig. 23-18: Puestow's pancreaticojejunostomy. Here spleen is removed. Entire length of dilated duct is opened. Distal pancreas is mobilised up to the superior mesenteric vessels. Pancreas with opened duct is telescoped into the Roux loop of jejunum and anastomosed.


Oesophagus
Spleen retained
Stomach
Pancreas
Duct
Duodenum
Jejunum

Fig. 23-19: Partington-Rochelle operation. Here spleen is retained and longitudinal pancreaticojejunostomy is done to the opened duct from the front.

3. Duodenal preserving with resection of head of pancreas in front of portal vein with jejunal loop anastomosis to the transected neck of pancreas—*Beger procedure (Hans Beger from Ulm, Germany, 1980).* Here extensive resection of head (than Frey's) is done. It addresses the inflammatory mass present in the head of pancreas by resecting it but preserving the blood supply of duodenum and bile duct. Here two anastomoses are present; one proximal over the extensive decored area; another on to the distal pancreas to its ductal system. Sleeve of pancreas is left behind with duodenum to preserve the blood supply. It is less radical resection; but it needs transection of the neck of the pancreas and double separate anastomoses; one at the decored transected part of the head; another at distal cut end of the body with laid open duct. Pancreaticojejunostomy is done at two sites of the Roux limb. It is also known as *duodenal preserving pancreatic head resection (DPPHR)*. Pain relief is 94%; insulin secretory capacity and glucose tolerance improve in this **(Figs 23-20 and 23-21)**.
4. *Berne modification of Beger procedure :* This modification spares the dissection of the pancreatic body from the portal vein. After the resection of pancreatic head, a single cavity results which can be anastomosed end to side with a Roux-en–Y jejunal loop. If stenosis of the intrapancreatic part of the common bile duct cannot be resolved by decompression and resection of the surrounding pancreatic tissue, or if the intrapancreatic portion of the common bile duct is opened accidentally during pancreatic head resection, the wall of the opened bile duct is fixed with single stitches to the surrounding tissues and is included in the same anastomosis. Complete transection of the neck is not done here.
5. *Longitudinal pancreaticojejunostomy* after excision of peripancreatic duct tissue: Here superficial part of the head of pancreas is removed to achieve improved drainage—*Frey procedure (Frey and Smith, 1987).* It is done when ductal dilatation is not adequate; head is more than 4 cm thick. Head coring is done with retaining 5 mm thick tissue in front of veins, close to duodenum. It shows 75% pain relief in 3 years. Here procedure is similar but decoring is done up to duct of Wirsung and Santorini and single longitudinal pancreaticojejunostomy is done **(Fig. 23-22)**.


Oesophagus
Spleen retained
Stomach
Liver
Pancreas
SV
PV
SMV
Jejunum
Duodenum
Beger procedure
Decoring up to portal vein, neck transected to anastomose

Fig. 23-20(1)


Portal vein
SMV
Exposure of the entire pancreas and pancreatic duct opening at the head and neck region
Decoring and removal of head retaining a sleeve close to the duodenal rim and transecting the neck of the pancreas
Pancreaticojejunostomy at two sites of Roux limb, one at the head and another at the body of the pancreas

Figs 23-20(2)

Figs 23-20(1 and 2): Beger procedure. Here head is decorated up to the visible portal vein. Neck is transected. Distal end of the pancreas with retained part is anastomosed to Roux loop of jejunum.


Pancreatic duct and head decored widely

Fig. 23-21: Decoring of the pancreatic duct and head in Beger technique.

6. Resection of tail of pancreas with retrograde Roux-en-Y pancreaticojejunostomy is known as—*Duval procedure (1954)*. It was not very successful in long-term as multiple strictures especially in proximal part are not laid open and addressed. Decompression of the main pancreatic duct is achieved by resection of the pancreatic tail and retrograde drainage of the pancreatic duct via a termino-lateral pancreaticojejunostomy. It may be useful if there is single stricture, which is unlikely **(Fig. 23-23)**.
7. If disease mainly involves head of the pancreas, then pancreaticoduodenectomy can be done—*Whipple's procedure.*
8. *Subtotal pancreatic resection:* Here spleen, body and tail of the pancreas are removed entirely, retaining the head of pancreas.
9. 95% *subtotal pancreatectomy is ideal but technically not feasible and demanding—Child's operation.* It is never recommended and advocated.
10. *Total pancreatectomy* is indicated when the entire gland is diseased. It relieves the pain and also prevents the diseased pancreas from turning into malignancy. Patient has to take insulin and oral pancreatic enzymes permanently (*brittle diabetes*).
11. The cause is treated like cholecystectomy for gallstones. Therapeutic ERCP is useful in removal of stones in dilated duct.
12. When duodenal, biliary and pancreatic obstruction is present—choledochojejunal, pancreaticojejunal and gastrojejunal anastomosis may be needed—*triple anastomosis.*

13. Only biliary stricture which cannot be managed by ERCP needs choledochojejunostomy.

Figs 14.31A and B: *Choledochojejunostomy*. It is Roux-en-Y anastomosis. It is done whenever there is complication of biliary stricture after pancreatitis. Often triple anastomosis may be required—pancreaticojejunostomy, choledochojejunostomy and gastrojejunostomy. It is done whenever there is duodenal obstruction, biliary block and pancreatic duct dilatation (drainage procedure) **(Figs 23-24 and 23-25)**.



Fig. 23-22: Frey's procedure. Here head of pancreas is decorated and opened duct with decored head is anastomosed to Roux loop of jejunum.



Fig. 23-23: Retrograde pancreaticojejunostomy after resection of the tail of the pancreas (Duval).



Fig. 23-24: Dilated pancreatic duct is laid open; multiple stones are removed and duct is ready for longitudinal pancreaticojejunostomy (LPJ). (By Dr Arunkumar, MCh, Gastro, Kochin).



Fig. 23-25: Pancreatic duct stones—removed during pancreaticojejunostomy.

Technique of Longitudinal Pancreaticojejunostomy—(Partington-Rochelle Operation—LPJ)

Longitudinal pancreaticojejunostomy is commonly done as drainage procedure as it is technically easier with reasonable good results with minimum morbidity and mortality. Preoperative CT scan to assess the ductal pattern diameter and splenic vein status is important. Duct dilatation more than 5-7 mm is better for pancreaticojejunostomy to drain the pancreas; it is also now done in non-dilated or less dilated duct system as it acts like a permanent fasciotomy on the pancreas which allows significant decompression. Splenic vein thrombosis when present, patient will have varices which are tortuous and dilated and so during surgery may cause troublesome bleeding. ERCP is a must to assess ductal anatomy, strictures ('chain of lakes' appearance), and stones. Pancreatic malignancy and chronic pancreatitis are difficult to differentiate grossly and on table biopsy is a must. Chronic pancreatitis itself predisposes malignancy **(Fig. 23-26).**



Multiple stones in pancreatic duct with dilated duct

Gastrocolic omentum is opened by ligating and dividing the omentum Stomach is separated from the anterior part of the pancreas and is retracted upwards using two Deaver's retractors

Pancreas surface is palpated for duct or stones or induration; syringe with lengthy needle is passed into the propsed site of the pancreatic duct; clear fluid is aspiratted, collected for cytolgy and culture

Needle is kept in place and using no 11 blade duct is incised longitudinally

Incision is extended towards head and tail end adequately; it should not go beyond gastroduodenal artery and arterial arcade All stones in the duct are removed;

Stones removed from the duct

Pancreatic duct is laid open adequately; stones are removed fully

A window is made on the transverse mesocolon right of the middle colic artery; first loop of the jejunum 20 cm from the DJ junction is transected after ligating arcade branches at that point; Division is done either by no 15 blade or using stapler; Distal Roux loop is brought through the window towards the laid opened pancreatic duct

Jejunum is opened little lesser length than that of ductal opening

Posterior interrupted 3 zero silk sutures are placed; all tied together; then similarly anterior layer is sutured with knots outside Roux-en-Y length is kept about 45–50 cm Jejunojejunostomy is done—end to side or side to side (Stapler)

Fig. 23-26: Technique of longitudinal pancreaticojejunostomy.

Under general anaesthesia, patient is in supine position, lengthy midline incision is placed. In obese patients, bilateral subcostal or upper transverse incision may be needed. After thorough exploration, self-retaining retractor is placed. Usually Kocherisation is not essential but to feel head of pancreas and if decoring is planned, then Kocherisation is done. It is better to release transverse colon on right side and hepatic flexure downwards to expose field adequately.

If gall bladder is not yet removed earlier by laparoscopy or open method, then cholecystectomy should be done.

Gastrocolic ligament is opened and transversely divided to expose the anterior surface of the pancreas. Omentum is held in between clamps, divided and ligated; alternatively harmonic scalpel or ligaseal can be used here to hasten the technique. Stomach is retracted upwards using a wide Deaver retractor. All adhesions between the posterior surface of the stomach and pancreas should be released over the head, uncinate process, body and tail of the pancreas **(Fig. 23-27)**.

Transverse colon and small bowel are retracted downwards. Peritoneal attachment on the front of the pancreas may be incised but not necessary. Entire gland from head to tail is carefully palpated for location of duct, stones and possible site of malignancy.

A 21-gauge needle with syringe is taken; suspected site of the duct usually in lower part of the gland is pricked; by trial and error usually which is dilated duct can be reached; clear pancreatic fluid is aspirated; fluid is collected for culture, analysis and cytology. With the needle in place no. 11 blade is passed adjacent to the needle to enter into the duct. It can be done using a cautery also **(Fig. 23-28)**.

Once duct is visualized, a Bake's dilator or any probe or infant feeding tube is passed to locate the duct direction and stones. If identification of the duct system has failed by repeated needle punctures which is not uncommon, then on table ultrasound is very useful to identify the duct. If it is not available, then carefully millimeter by millimeter pancreatic tissue is cut near the neck of the pancreas towards body side until duct is reached. In olden days tail used to be transected often with splenectomy to identify the duct and proceeded with standard old Puestow Gilesby technique—but nowadays it is not necessary to change to Puestow. Any bleeders in the cut edge of the duct are controlled using bipolar cautery. Duct is incised towards head up to the gastroduodenal artery not beyond; distally it is opened up to the end of the duct as much as possible. All stricture parts should be laid open; all stones should be removed. Minimum 8 cm duct length should be opened. Venous plane is deeper to ductal system. Deep incision across the posterior wall of the duct may injure the splenic vein. In the head, there are chances of injuring anterior pancreaticoduodenal vessels; one should be careful to preserve them. After passing the needle, intraductal pressure can be measured; or another fine needle can be inserted into the parenchyma to measure interstitial pressure of the pancreas. Entire duct of Wirsung, duct of Santorini and duct of uncinate process should be laid open; but should limit within the anterior pancreaticoduodenal arcade **(Fig. 23-29)**.

If Frey's procedure is undertaken, entire pancreatic tissue in front of these ducts should be excised and laid open. It is done by placing series of consecutive stay sutures using silk or vicryl and cutting the pancreatic tissue using tough curved scissor (Pott's scissor or another one). Bleeders are addressed with suture ligation using 3 zero silk or vicryl. Monopolar cautery should not be used. Bipolar cautery is safer.

Roux limb is prepared 20 cm from the ligament of Treitz. Jejunal vessels are ligated. Small bowel is transected between two occlusion clamps; proximal end is left like that to do later end-to-side jejunojejunostomy. Alternatively stapler transection of the jejunum can be done. A window is created in the transverse mesocolon to the right of the middle colic artery. Distal Roux limb is brought through it to reach supracolic compartment. Loop is brought towards the tail end of the pancreas so that anastomosis becomes isoperistaltic in relation to the ductal drainage. If loop end is brought towards the head part of the pancreas it will become antiperistaltic, still can drain the duct adequately. Usually 45-50 cm Roux loop is sufficient **(Fig. 23-30)**.



Fig. 23-27: Stomach is retracted upwards.



Fig. 23-28: Pancreatic duct is opened for adequate length from head to tail, minimum of 8 cm.

Entire pancreatomy on the duct is anastomosed to the jejunum. Jejunotomy/enterotomy is done on the antimesenteric border of the jejunum just 1 cm proximal from the distal end of the Roux loop. Enterotomy should be 5 mm lesser than the ductal opening. Side-to-side pancreaticojejunostomy is done. Posterior layer is sutured first. Interrupted 3 zero silk or vicryl sutures are used. All suture bites should be taken first. While taking bites from pancreatic side full thickness bite including fibrous peripancreatic tissue should be taken. Few advocate that mucosal bite should be avoided. But usually it does not the cause any problem. Continuous suturing should be avoided as it will block endings of the small ducts into the main pancreatic duct. After taking all bites, posterior layer knots are placed one after other. Ties on either side (one on each end) are kept long. Knots are placed inside. It is also


Bucket handle bilateral subcostal incision
Gastrocolic ligament is opened colon is reflected downwards stomach is upwards
Colon is reflected downwards Omentum is divided adequately
GB
IVC
Kocherisation is being done
Mobilised duodenum
Kocherisation of the duodenum and feeling the head of the pancreas is always better
Stomach is reflected upwards colon and small bowel downwards
Stomach is reflected upwards colon and small bowel downwards
Aspiration of the pancreatic duct for identification

Figs 23-29(1)


Duct is incised no 11 blade
Gall bladder needs removal
Cholecystectomy
Cystic duct stump
GB removed
Indentification of duodenojejunal junction
Window in transverse colon

Figs 23-29(2)

Figs 23-29(1 and 2): Initial steps in longitudinal pancreaticojejunostomy.



Figs 23-30(1)



Figs 23-30(2)



Figs 23-30(3)



Figs 23-30(4)

Figs 23-30(1 to 4): Longitudinal pancreaticojejunostomy procedure.

often practised that knots are placed outside in posterior layer; if it is so, bites should be taken from outside to inside of the duct and then inside to outside of the jejunum to place the knots at end. Placing knots inside the pancreaticojejunostomy is very well accepted. Anterior layer anastomosis is done by taking series of interrupted bites from anterior edge of the duct opening to anterior edge of the jejunal incision. Here also all bites are taken, tied one by one later and then ends are cut. Knots are placed outside in anterior layer. Single layer is sufficient in pancreaticojejunostomy even though few practice double-layer anastomosis which is technically difficult and not essential as such. Roux limb may be fixed to anterior pancreatic tissue to prevent kinking proximal to lengthy anastomosis **(Fig. 23-31)**.

End-to-side jejunojejunostomy is done to maintain the bowel continuity (45–50 cm from pancreaticojejunostomy site). If stapler transection is done, side-to-side anastomosis can be undertaken. Single layer continuous or interrupted 3 zero vicryl sutures are used for the same. Second layer 3 zero silk interrupted seromuscular sutures can be added **(Fig. 23-32)**.


Posterior interrupted sutures using silk or vicryl sutures are placed
Pancreatic duct laid open
Completed anterior layer single layer interrupted

Fig. 23-31: Longitudinal pancreaticojejunostomy.


Roux en Y jejunojejunostomy after pancreaticojejunostomy
Completion of JJ
LPJ (Supracolic)
End of Roux loop
Colon
JJ (Infracolic)

Fig. 23-32: Jejunojejunostomy in Roux-en-Y pancreaticojejunostomy.

If celiac ganglion block is needed, it can be given on table by direct palpation of aorta. 20 ml of 50% ethanol is injected along each side of the aorta using 21-gauge spinal needle.

Jejunum is fixed to the mesocolon by few interrupted silk sutures to prevent herniation. Jejunostomy, if needed, is done. Drain is placed. Abdomen is closed in layers.

Problem with this procedure (LPJ) is failure to identify the portal hypertension and dilated veins in the pancreas, and possible occult carcinoma of the pancreas.

Complications of Surgery

Pancreatic leak/fistula (10%); infection; bleeding; recurrence; brittle diabetes in total pancreatectomy.

Pain/relief in chronic pancreatitis is achieved by drugs; decompression/drainage surgeries, resection surgeries, epidural analgesia, coeliac ganglion block, operative chemical splanchnicectomy, extra/intraperitoneal right and left splanchnicectomy, transhiatal bilateral splanchnicectomy, thoracoscopic splanchnicectomy. 5-year pain-free period in decompression surgery is 70%.

A. Drainage procedure

- *Partial*: draining the duct partially
  - a. Sphincterotomy and sphincteroplasty
  - b. Duval procedure
  - c. Puestow-Gillesby procedure
  - d. Leger's procedure—Here splenectomy; opening of the duct; retrograde loop pancreaticojejunostomy is done instead of Roux-en-Y.
  - e. Marcadier procedure—Only duct in the body is drained through a side-to-side loop pancreaticojejunostomy.
- *Complete*: draining the main duct completely
  - I. Pancreaticojejunostomy
    - a. Partington-Rochelle procedure
    - b. Bapat's (India, 1997) modification of Partington's procedure—Here end of Roux loop is not closed but fish mouth is created by giving a cut at antimesenteric border and entire part is anastomosed to side of the duct.
    - c. Moreno Gonzales procedure—Pancreatic and bile duct drainage is established into an isolated vascularised loop of jejunum which is then anastomosed to the duodenum.
  - II. Pancreaticogastrostomy

    It is technically found easier; however, it is not practised usually. Patients developed steatorrhoea because of the inactivation of the pancreatic enzymes by gastric acid.

B. Resectional procedures

- a. Whipple's operation.
- b. Traverso-Longmire procedure: Pylorus preserving pancreaticoduodenectomy, 1978.
- c. Beger's procedure: Decoring of head with transection of the neck and two anastomoses are done—one at head and another at cut end of the body of pancreas to a single Roux loop. In Berne's modification, head is decored but neck is not transected and a single cavity created is anastomosed to a Roux jejunal loop; CBD when opened here, its edge is also involved in stitches so that bile is also made to drain into the Roux loop.
- d. Denervated pancreatic flap: Warrens denervated pancreatic flap: The pancreas is divided over the portal superior mesenteric vein after ligation of the splenic artery and vein. The pancreatic head is excised leaving a thin rim. The remaining pancreas is not drained. Ligation of splenic vein and artery is probably denervate the gland.

  Shires' denervated splenopancreatic flap: Complete mobilization of the pancreas from the retroperitoneum, resection of the head and the uncinate process leaving a thin rim of pancreas adjacent to the duodenum, division of the splenic vein at its junction with the SMV and drainage of the distal pancreatic remnant into a Roux-en-Y limb of jejunum.
- e. Subtotal pancreatic resection: Body and tail of pancreas is removed. Disease in the body and the tail is often secondary to disease in the head of the pancreas, thereby limiting its role. This procedure is still indicated when the disease is confined to body and tail, e.g. pseudocyst, failed pancreaticojejunostomy, nondilated duct, pseudoaneurysm and when there is disease beyond the neck of pancreas, and the pancreatic duct is oversewn. A concomitant splenectomy is unavoidable in the majority of patients because of dense fibrosis precluding the isolation of the splenic vessels.
- f. Child's procedure: 95% distal pancreatectomy. The spleen, the tail, body and uncinate processes are completely removed. The small cuff of the head that is preserved protects the vascularity and common bile duct during surgery. This procedure is performed when lesser procedures have failed or when the entire pancreas is severely diseased.
- g. Total pancreatectomy: With duodenal preservation (Russel, 1987); without duodenal preservation.

C. Extended drainage procedure

- a. Rumpf's extended drainage (1983): This is a combination of Partington's procedure with a transduodenal pancreatic sphincteroplasty. It is indicated when there is a prepapillary obstruction to the drainage of pancreatic duct due to stones or stricture.

D. Resection with extended drainage

- a. Extended Beger procedure—In addition to the duodenum preserving head resection, a side-to-side lateral pancreaticojejunostomy is performed after slitting open the main pancreatic duct.
- b. Frey's procedure.
- c. Izbicki V-shaped ventral pancreatic excision. In this procedure, a long V-shaped excision of ventral aspect of the pancreas is done with a lateral pancreaticojejunostomy by a mucosa to capsule anastomosis. This procedure drains the main as well as the second and third order ducts. This is an ideal procedure for small duct disease with a maximum diameter of the Wirsung's duct less than 3 mm.

E. Pancreatic denervation alone

- a. Left splanchnicectomy with celiac ganglionectomy: Mallet Guy (1983) advocated an extraperitoneal approach through the 12th rib for left splanchnicectomy with celiac ganglionectomy. This is done after correcting the extrapancreatic pathology.
- b. Left splanchnicectomy, celiac ganglionectomy with bilateral vagotomy.
- c. Complete pancreatic denervation: Hirokawa described a more extensive denervation procedure, which includes freeing the pancreas from the posterior abdominal wall and resection of all postganglionic pancreatic nerve plexus including those surrounding the common hepatic and splenic arteries (1986).
- d. Transthoracic/videothoracoscopic pancreatic denervation: The greater splanchnic nerves are responsible for pain in supramesenteric viscera and the nerve trunks lie above the level of the 10th thoracic vertebra and descend along the spine to end in the celiac plexus, similarly the lesser splanchnic plexus. Transthoracic division of the splanchnic nerves with bilateral vagotomy performed through a left thoracotomy. Procedure can be performed using a videothoracoscopic technique (Makarewicz W et al, 2003).

F. Pancreatic autotransplantation

- a. Islet cell transplantation
- b. Segmental pancreatic transplantation.

Postoperative Care

Nutrition—TPN/jejunostomy feed; fluid and electrolyte management; prevention/control of sepsis; proper monitoring; Octreotide on table and postoperatively—regular intervals or slow infusion—5 days. Nasogastric tube is removed in 48 hours. Oral fluid is started in 4-5 days. Drain is removed in 5-7 days.

Surgery for Chronic Pancreatitis

Drainage: Technically easier; Less mortality < 2-5%; Adequate pain relief; Recurrence of pain in 5 years—50%. But diseased tissue is left behind; Disease progression and fear of existing occult carcinoma (17%) or later onset.

Resection: Technically demanding; Mortality is 8-21%—very high; Used when carcinoma is suspected or localised disease. Head is the pacemaker of the disease. Whipple's is preferred. Total pancreatectomy causes high mortality, brittle diabetes; though ideal, it is not done commonly.

Islet Cell Auto-transplantation

The Mirkowitch technique: Partially purified islet produce a fairly large volume of minced digested islet cell tissue which is then injected into a portal vein very slowly. But portal pressure is markedly raised several fold. *Let preparation technique (Hinshaw et al)*—5 ml tissue pellet is produced containing 500,000-2000,000 islets for transplantation, portal pressure remained essentially unchanged. Total pancreatectomy and islet autotransplantation are done for chronic pancreatitis with intractable pain when other treatment measures have failed, allowing insulin secretory capacity to be preserved, minimising or preventing diabetes, while at the same time removing the root cause of the pain. Pain relief is obtained in most patients, and insulin independence preserved long-term in about a third, with another third having sufficient beta-cell function so that the surgical diabetes is mild. Islet autotransplantation has been done with partial or total pancreatectomy for benign and premalignant conditions. Islet autotransplantation should be used more widely to preserve beta-cell mass in major pancreatic resections [Blondet JJ, et al. (2007)].

Segmental Pancreatic Transplantation

Auto-transplantation of the resected body and tail of the pancreas is done into the thigh following near total pancreatectomy. The splenic vessels are anastomosed to the femoral vessels. The divided end of the pancreas is closed and the duct is ligated or injected with synthetic polymers (e.g. prolamine or neoprene). Duct obliteration is thought to cause rapid and permanent atrophy of the exocrine pancreas but preserves endocrine function. Still it is found that duct obliteration does not prevent relapse or progression of chronic pancreatitis in the preserved pancreatic segment. Internal drainage of the duct into a Roux-en-Y limb of jejunum has also been reported.

Laparoscopic Pancreatic Resection

Laparoscopic resection of the pancreas is technically quite demanding. It is technically feasible. The benefit of the laparoscopic approach may not be as apparent as that of a less complex laparoscopic procedure. The use of laparoscopy for distal pancreatic resection with splenic preservation is beneficial. Optimal closure of the cut edge of the pancreas and preservation of the spleen and its main vessels are the most important aspects of this operation. Laparoscopic longitudinal pancreaticojejunostomy and laparoscopic Whipple's procedures are done now in specified centers by skilled laparoscopic surgeons with same principles and technique as open surgery.

SURGICAL TREATMENT FOR PSEUDOCYST OF PANCREAS

It is a localized collection of sequestered pancreatic fluid, usually 3 weeks after an attack of acute pancreatitis. It can occur after trauma and recurrent chronic pancreatitis. Collection usually occurs in the lesser sac in relation to stomach, but can occur in relation with duodenum, jejunum, colon and splenic hilum. About 50% of acute pancreatitis leads to pseudocyst formation, but among that 20-40% will resolve spontaneously. **Sites—**Lesser sac—commonest, i.e. between colon and stomach; can occur in relation to duodenum, jejunum, colon and splenic hilum. **Types—**Depending on whether it communicates with pancreatic duct or not is classified as: 1. *Communicating pseudocyst. and* 2. *Noncommunicating pseudocyst. Pseudocyst can also be Acute pseudocyst or Chronic pseudocyst.*

Initially, cyst wall is thin *(unformed),* but later it gets fibrosed and thickened *(formed)* (matured). It is lined by fibrin layer but no endothelium, hence known as pseudocyst. It contains typically brownish fluid with sludge-like necrotic material. It can get infected to form *infected pseudocyst* or *pancreatic abscess.* Amylase level in the cyst fluid is very high (> 5000 units/ml).

Complications of pseudocyst—Rupture—3%—into bowel or peritoneum; bleeding from the splenic vessels—7%; cholangitis; duodenal obstruction; portal/splenic vein thrombosis and segmental portal hypertension; cholestasis due to CBD block.

D'Egidio's classification of pseudocyst

Type I: After an attack of acute pancreatitis; Normal duct anatomy; no fistula/communication.

Type II: After an attack of acute on chronic pancreatitis; Abnormal duct anatomy without stricture; 50% chances of fistula.

Type III: After an attack of chronic pancreatitis, abnormal anatomy with stricture; always communicating. It appears like retention cyst.

Investigations

U/S abdomen (commonly done procedure), U/S reveals the size and thickness of the pseudocyst. Size less than 6 cm indicates that one can wait for spontaneous resolution. US also shows the presence of gall stones. Endosonography (EUS) is very useful. CT scan is ideal and study of choice. It is two times more sensitive than U/S. It demonstrates size, shape, number, wall thickness, contents, pancreatic duct size, and extent of necrosis in pancreas, calcification and atrophy in chronic pancreatitis, regional vessels, pseudoaneurysm, and splenic/portal vein thrombosis. Splenic artery CT angiography is very relevant in suspected cases of pseudoaneurysm. MRCP delineates the ductal anatomy and its abnormality. ERCP can be done to find out the communication **(Fig. 23-33)**.



Fig. 23-33: CT scan of pseudocyst of pancreas.

Indications for Surgery/Intervention

Size more than 6 cm; formed pseudocyst; infected pseudocyst; cyst persisting after 6 weeks/progressive cyst; multiple cysts/cyst due to trauma; communicating cysts/cyst with severe pain; thick-walled pseudocyst.

Cystogastrostomy

Procedure is done under general anaesthesia. Preoperative antibiotics are given. Nasogastric tube is passed. Cyst should be firmly attached to the wall of the stomach to do cystogastrostomy. Cyst wall should be thick to do cystogastrostomy otherwise only external drainage is possible **(Figs 23-34 and 23-35)**.

At laparotomy, cyst is palpated. Any undue pulsation more than usual should indicate a suspicion of pseudoaneurysm. Anterior wall of the stomach is easily exposed. Gastrotomy on the anterior wall of the stomach is made—6-8 cm on its most prominent part. Posterior wall of the stomach is opened after again confirming that cyst wall is adherent to the stomach. Anterior wall is retracted by placing two Deaver's retractors inside anterior wall; or 4 stay sutures can be placed on 4 points. Long needle with syringe is passed into the cyst; brownish coloured fluid is aspirated. If blood is aspirated, pseudoaneurysm is suspected. Fluid is sent for cytology and biochemical assessment (amylase level). Aspiration is often done prior to gastrotomy but usually done after gastrotomy. Posterior wall of the stomach with an elliptical incision is excised along with similar sized anterior cyst wall. This cyst wall is sent for histology. The thick capsule of pseudocyst is opened. All fluid with necrotic material is sucked. Fluid should be sent for cytology, culture and sensitivity and amylase estimation. Cyst wall always should be biopsied—ideally frozen section biopsy. Cyst cavity should be washed with warm normal saline after breaking septae. Cut edge of the stomach is anastomosed to the cut edge of the cyst wall using continuous or interrupted vicryl sutures. This pseudocapsule which is anastomosed to posterior wall of the stomach is known as *Jurasz operation.* Anterior wall gastrotomy is closed with continuous single layer vicryl sutures. Stapler closure also can be done. Usually peritoneal drainage is not necessary. Nasogastric tube is kept for 48 hours. Oral started in 72 hours **(Fig. 23-36)**.



Figs 23-34: Cystogastrostomy.



Fig. 23-35: Opened pseudocyst wall. Always collect fluid for amylase which will be very high; and also for CEA; take frozen section biopsy from the edge.


Cyst fluid — note the brownish black colour
Anterior gastrotomy
Posterior wall of stomach with bulging cyst
Posterior wall of stomach and cyst wall are opened
Suturing cyst wall to opened posterior wall of the stomach with continuous vicryl sutures

Fig. 23-36: Pseudocyst with cystogastrostomy.

If stomach is not adherent to cyst wall, then cystojejunostomy is done; if cyst wall is not thick on table, then only external drainage should be done.

If cyst contains pseudoaneurysm, then on table ultrasound should be done; here it is better to do distal pancreatectomy with the removal of cyst and ligation of splenic artery **(Figs 23-37 and 23-38A and B)**.

Note: Feel for pulsation to rule out pseudoaneurysm and needed adhesion between stomach and cyst; aspirate to rule out blood and to confirm brownish black fluid of cyst; do always frozen section biopsy of cyst wall to rule out cystadenocarcinoma. Cyst fluid is sent for amylase and CEA.

Other Procedures

1. ***Cystoduodenostomy:*** It is similar to stomach technically; but duodenum is opened and anastomosis is done. It is commonly not used as duodenum healing is not as good as cystogastrostomy and leak may occur.
2. ***Cystojejunostomy:*** It is done in large cyst and recurrent cyst. Roux-en-Y cystojejunostomy is better with lesser recurrence rate than cystogastrostomy. Upper midline incision is used; laparotomy exploration is done. Cholecystectomy, if needed, is done. Anterior wall of the cyst is exposed by releasing the omental adhesions using sharp and bipolar cautery dissection. Cyst is aspirated in similar way and collected for culture, cytology and biochemical analysis. 4 cm cyst wall is excised elliptically; tissue is sent for frozen section biopsy. Jejunum is transected 20 cm from the ligament of Treitz; distal Roux limb is brought upwards through a created window in the transverse mesocolon. End of the Roux loop is anastomosed to the cyst wall as end-to-end using interrupted 3 zero vicryl or silk sutures. Rent in the mesocolon is sutured to the jejunum. Divided proximal cut end of the jejunum is anastomosed to the antimesenteric side of the Roux limb 50 cm from the cystojejunostomy site. Defect in the jejunal mesentery is closed with interrupted sutures **(Figs 23-39 and 23-40)**.
3. If infected, cystogastrostomy with external drainage is done using Malecot's catheter (*Smith operation*) **(Fig. 23-41)**.
4. ***Laparoscopic cystogastrostomy*** is becoming popular, effective and less invasive.



Fig. 23-37: Aspiration of the cyst.

5. ***Distal pancreatectomy*** with pseudocyst removal if cyst is in distal part or if there is a pseudoaneurysm **(Fig. 23-42)**.



Figs 23-38A and B: Aspiration of pseudocyst of the pancreas.



Fig. 23-39: Cystojejunostomy is better. If cyst is not adherent to stomach with thick cyst wall, cystojejunostomy is done.

PANCREATICODUODENECTOMY (WHIPPLE'S OPERATION/PARTIAL PANCREATICODUODENECTOMY)

The standard surgical treatment for pancreatic cancer remains the pancreaticoduodenectomy, first described by Whipple (Allen Oldfather Whipple) in 1935. Initially he did two staged procedure and in 1942 he modified into one stage procedure. High operative morbidity and mortality rates led to technical modifications of the operation which, combined with improvement in anesthesia and critical care, have resulted in current perioperative mortality rate of 2% or less **(Fig. 23-43)**.

Indications

Periampullary carcinoma, carcinoma of 2nd part of the duodenum, ampulla, distal CBD are traditional indications. Chronic pancreatitis with disease involving mainly head of pancreas with severe pain is also an indication **(Fig. 23-44)**.



Aspiration of cyst to confirm

Dissection and isolation of the cyst

Opening of the thick walled cyst and suctioning the content

Fluid should be sent for culture, amylase and CEA; Edge should be biopsied — ideally frozen section

Creation of Roux limb for cystojejunostomy

Figs 23-40(1)


Roux limb is brought towards the opened cyst
Cystojejunostomy — usually interrupted sutures are used; here continuous suturing is done

Figs 23-40(2)


Jejunojejunostomy to maintain continuity
Completed cystojejunostomy
Completed cystojejunostomy

Figs 23-40(3)

Figs 23-40(1 to 3): Technique of cystojejunostomy for pseudocyst of pancreas.



Fig. 23-41: When infected pseudocyst should be drained externally along with internal drainage (Smith).

Fig. 23-42: Laparoscopic cystogastrostomy is a safe and effective method; technique and principles are the same. Intracorporeal suturing is needed.



Fig. 23-43: Configuration of Whipple's operation.



Fig. 23-44: Periampullary carcinoma with dilated CBD and gall bladder.

Contraindications

Liver and peritoneal secondaries; celiac lymph node involvement; involvement of the SMA or root of the mesentery. Significant deep infiltration of portal vein precludes the resection, even though resection of portal vein with graft is done.

Preoperative staging and evaluation with CT, MRI, ERCP, EUS, liver function tests, prothrombin time, and coagulation profile are needed. Adequate hydration in preoperative period is needed. Preoperative antibiotic may be needed if cholangitis is suspected. Malignant obstructive cholangitis, if present, is a high risk, may require an initial decompression by ERCP and then proceed with pancreaticoduodenectomy. However, routine preoperative decompression is not practised nowadays **(Fig. 23-45)**.



Fig. 23-45: Endoscopic view of periampullary carcinoma.

Risks are—intraoperative bleeding; anomalies of vessels; pancreatic and biliary leak; infection; acute pancreatitis; postoperative bleeding.

Technique of Whipple's Operation

The current practised technique utilizes a *bilateral subcostal incision (Chevron incision)*. The liver and peritoneal surface is carefully examined to exclude the presence of metastatic disease, and intraoperative ultrasonography of liver and pancreas is performed. Random lymph node sampling is not done however; suspicious lymph nodes found during the operation are subjected to frozen section analysis.

In an operable case, it is often practised to go ahead with pancreaticoduodenectomy without biopsy. Ideally on table FNAC of the tumour directly or transduodenal needle tissue biopsy or choledochotomy with choledochoscopic biopsy in case of CBD tumour is preferable; however preoperative endoscopic biopsy of periampullary carcinoma or ERCP biopsy is also commonly advocated.

Adequate exposure is essential for proper Whipple's operation. Good retraction with self-retaining retractor makes assistant's hands free to help the surgeon during surgical procedure. Bipolar cautery, ligaseal, harmonic scalpel are of benefits including staplers to divide stomach and duodenum. Initial mobilization is done by reflecting the hepatic flexure and transverse colon downwards; then extended Kocherisation is done by lateral duodenal ligament which exposes SMV, IVC and aorta partly. Invasion or encasement of these vessels will prevent from proceeding with resection; just essential bypass will be sufficient. Middle colic vein when traced will help in identifying the SMV **(Figs 23-46 and 23-47)**.



Fig. 23-46: Kocher's manoeuvre and Cattell-Braasch manoeuvre to mobilise the duodenum and right-sided colon.



Fig. 23-47: Mobilisation of duodenum and colon in Whiple's operation.

Dissection in this area should be careful and gentle as venous tear causes torrential bleeding and becomes time consuming to control bleeding. Duodenum is freed above up to foramen Winslow. Gastrohepatic ligament is dissected to identify proper hepatic artery after incising the peritoneum over it. Any lymph nodes identified are brought down towards the specimen. Gastroduodenal artery is identified which is a branch of common hepatic artery. It runs downwards under the 1st part of the duodenum on the surface of the head of the pancreas to divide into right gastroepiploic artery and superior pancreaticoduodenal artery. Gastroduodenal artery is divided between double silk ligatures. Once dissection proceeds medially, anterior surface of the portal vein is identified; anterior surface usually being avascular is dissected gently between it and neck of the pancreas downwards; similarly another index finger is passed from below between SMV and neck of the pancreas upwards to feel the other finger from above. But this is not sufficient to confirm the invasion; finger has to be passed under the 2nd part of the Kocherised duodenum with thumb in front to feel for invasion of the uncinate process and posterior wall of the portal vein and superior mesenteric vessels. Right gastric artery is also divided which is much smaller than the gastroduodenal artery. Incision of the peritoneum over the CBD allows clearing the lymph nodes in the porta hepatis. Hepatic artery and CBD should be visualised properly after this part of the dissection. Cholecystectomy is performed. Common hepatic duct (CHD) is transected just above the joining of the cystic duct. CHD is temporarily occluded with a soft camp. It is a routine to do frozen section biopsy of the edge of the CHD and cystic duct in all patients whenever facilities are available. Antrectomy (with vagotomy if desired) is done now **(Figs 23-48 to 23-51)**.

Division of the pancreas can be done now or after the mobilisation of the duodenojejunal loop and bringing the loop towards right underneath the superior mesenteric vessels. Pancreas is carefully mobilised towards the left of the portal vein and SMV at least for 3 cm. Small vessels entering the splenic vein should be carefully divided after ligation. Splenic vein located on undersurface of the distal pancreas should not be injured but should be separated for adequate length so that safe anastomosis of pancreas into the jejunum can be undertaken. Ligation of the superior and inferior pancreatic artery in the pancreas is needed prior to transecting the pancreas. Stapler transection of the



Fig. 23-48: Cholecystectomy is done during portal dissection in Whipple's operation.



Fig. 23-49: Transection of bile duct and ligation of the gastroduodenal artery in Whipple's operation.



Fig. 23-50: Portal dissection in Whipple's operation.



Fig. 23-51: Antrum is transected. Transection can be done using stapler device.

neck of pancreas can be done left of the SMV level; pancreas need to be divided again left of the stapler line to keep the cut distal end open for later anastomosis. Cut margin from left side should be sent for frozen section biopsy. Stapled part will come towards the specimen. Alternatively two stay sutures using 3-zero vicryl is placed on the superior and inferior parts of the neck of the pancreas towards left and held apart and forward; often stay sutures are placed—2 front and 2 behind; flat instrument like scalpel knife is placed underneath to guard the portal vein; neck is transected using no. 15 blade under vision from below upwards; finger guidance underneath is also useful. Duct distally when dilated will be visible and is stented with a fine plastic tube temporarily to prevent it getting entangled with sutures **(Fig. 23-52)**.

Proximal 6 cm of the jejunum is dissected by separating it from jejunal vessels extending proximally along the ligament of Treitz towards the superior mesenteric vessels on the right side; SMV (right) and SMA (left) pass in front of the 3rd part of the duodenum; duodenojejunum is freed by serial clamping, ligating and dividing the vessels of this part; ligaseal or harmonic scalpel saves time if used here. Jejunum is transected with stapler; otherwise divided between clamps and proximal end is closed using 3-zero continuous or interrupted single layer or double layer sutures. 1st jejunal branch arising from the SMA should be ligated prior to sliding the duodenojejunum underneath the superior mesenteric vessels to bring towards right.

Entire specimen with duodenojejunum has come towards right of the portal system. Uncinate process is carefully dissected off from the SMA and SMV. Arterial branches often arise from SMA deep to the SMV to reach head and uncinate process which is carefully dissected, ligated and divided. Uncinate process and pancreas extending behind the portal vein and SMV are serially ligated and divided. Care should be taken not to injure the SMV and portal vein while giving traction to the specimen. Often it is a better practice that a surgeon holds the specimen with his left hand and with his hand, he dissects, allowing the assistant to pass a polypropylene or silk ligature through a right-angled Mixter forceps and ligate it towards left side; opposite specimen side can be divided without ligature as surgeon is holding it firmly. All veins draining from the pancreas towards the right margin of the SMV and portal vein are ligated similarly and divided. Dividing without ligation will end with unnecessary bleeding and as such delays the procedure rather than hastening it. SMV should be retracted using gentle curved vein retractor towards left to visualise the SMA under which uncinate process ends. This dissection is carried out from below upwards. It is again better to do frozen section biopsy of the uncinate process to confirm the adequacy of resection as far as clearance is considered **(Fig. 23-53)**.

Anastomoses Parts

First pancreaticojejunal anastomosis is done usually as end to side; *then* hepaticojejunostomy is done; *later* antecolic gastrojejunostomy is done.

Distal transected jejunal loop is brought through the transverse mesocolon window towards pancreatic region. *Pancreati-*



Fig. 23-52: Transection of the neck of pancreas in Whipple's operation.

cojejunostomy is done by different methods—(1) When pancreatic duct is dilated duct to mucosa anastomosis is done; 3-5 cm distal to the stapled line along the antimesenteric border, jejunum is opened slightly lengthier than the diameter of the opened pancreatic duct; prior to enterotomy interrupted sutures are placed between the posterior capsule of the pancreas and the seromuscular layer of the posterior part of the proposed enterotomy site on the jejunum (posterior to enterotomy) using 4-zero polypropylene suture material. 5-6 such sutures are needed. Pancreatic duct is sutured to the full thickness jejunum as interrupted sutures using 5 or 6-zero polypropylene or PDS suture material posterior layer. Fine no. 8 infant feeding tube can be passed across the duct; proximal end is brought out through a stab wound 10 cm distal to the anastomotic site and also brought out of the abdominal wall; anterior layer duct mucosa full thickness jejunum anastomosis is done similarly; magnifying lens may be useful for ductal anastomosis. Duct may be fixed to pancreas and jejunal edge by a single 6-zero vicryl. Anterior pancreatic capsules to seromuscular jejunal interrupted sutures are placed. Stenting ductal tube which was brought out is fixed to jejunum with 5-zero vicryl sutures and this jejunal point is fixed to the parietal abdominal wall with 4-zero silk sutures. This stent also can be brought out through the proximal cut end of the jejunal stump through a separate stab incision similarly. End-to-side pancreaticojejunostomy is completed. This method can be used only for end-to-side anastomosis. (2) If duct is not dilated or pancreatic tissue is friable to take suture bites, then entire 2 cm distal cut pancreatic stump is invaginated into the cut end of the jejunal limb. Telescopic sutures are passed from outer part of jejunum 2 cm from the cut edge into its lumen, then from inside to outside of the pancreatic tissue; returning back from outside inside of pancreas and inside out of the jejunum stump. Two such telescopic sutures are placed on both sides. If pancreatic stump is too bulky, injection glucagon 1 mg IV helps to relax and accommodate the stump adequately. Otherwise stump is invaginated to the lateral part of the jejunum 3-5 cm proximal to the jejunal end which is closed; corresponding sized incision is made to accommodate the pancreatic stump. Before telescoping no. 8 infant feeding tube can be placed in the duct if duct is properly identified and brought out in similar way 10 cm proximally. If duct is too small, it is not mandatory to stent or suture the duct as proper telescoping of the pancreas with two layers interrupted, suturing both posteriorly and anteriorly, is sufficient without any problem. When these telescopic sutures are pulled in, pancreatic stump gets invaginated automatically into the jejunum; these telescoping sutures are not tied. Cut edge of the pancreas telescoped inside is sutured again to the bowel wall at 2 cm distance with interrupted polypropylene 4-zero sutures—circumferentially. All sutures round are placed then later tied together. Telescoping sutures are tied now. Next layer of the anastomosis is done between the cut edge of the jejunum as full thickness and the pancreatic capsule as interrupted sutures. This method is used for either side or end of the jejunal limb. (3) Another method is to place the posterior seromuscular layer of the jejunum to the pancreatic capsule 2 cm away from the cut margin; then 2nd posterior full thickness jejunum to the pancreatic cut edge with or without including the posterior edge of the duct; 3rd layer is anterior full thickness bowel wall to the cut edge of the pancreatic stump with or without taking bites from anterior part of the duct; 4th layer is seromuscular bite from the bowel 2 cm from the earlier layer and from the pancreatic capsule at corresponding distance. This method is used for either side or end of the jejunal limb **(Fig. 23-54)**.

Hepaticojejunal anastomosis is done as end-to-side of the jejunal loop on to its antimesenteric border. Jejunum is opened at antimesenteric border 15 cm from the pancreaticojejunostomy site; incision should be slightly lesser than or equal to that of hepatic duct. Anastomosis is done using interrupted 4-zero vicryl sutures; posterior layer sutures are placed first with knots outside; first all posterior suture bites are taken and then knots are tied at the end. Anterior layer is sutured with knots outside. Every 3 mm gap sutures should be placed. If surgeon wants stenting of the hepaticojejunostomy, then prior to placing sutures, longitudinal/vertical limb of no. 14 F 'T' tube is passed through cut end of the hepatic duct proximally and is brought out through a small incision through the hepatic duct outside and of the abdominal wall through a separate stab wound. This drains bile outside and also promotes healing of the pancreaticojejunostomy **(Figs 23-55 and 23-56)**.

Gastrojejunostomy is done 20 cm distal to the hepaticojejunostomy as an antecolic anastomosis. As already stomach is transected with stapler earlier during procedure, gastrojejunostomy is done using linear stapler device just proximal and posterior to the stapled line. Single layer 3-zero vicryl hand sewn anastomosis also can be done after doing gastrotomy and corresponding jejunotomy **(Fig. 23-57)**.


Bilateral subcostal incision
Exploration
Kocherisation
IVC
2nd part duodenum
Gastrocolic ligament division
and Cattell-Braasch method
of mobilising right colon below
Dissection at porta with cholecystectomy
Cholecystectomy is done
Clockwise dissection
Gastroduodenal artery
dissection and ligation
Divided gastroduodenal artery

Figs 23-53(1)


Dilated CBD dissection after cholecystectomy
Transection is done above cystic duct ligation
Frozen section of cut margins of
cystic duct and CHD is sent
CBD
Finger underneath the neck
of the pancreas in front of the portal vein
Neck
CBD
Neck
Transection of the stomach at antrum
Transection of the stomach at antrum
Neck of pancreas isolated
Transection of the stomach at antrum
Stay sutures to pancreas at 2–4
superior and inferior

Figs 23-53(2)


Transecting the neck of pancreas
Identification of DJ junction by Inf Mes vein and ligament of Treitz
Dissection of the DJ, proximal jejunum, 3rd and distal parts of the duodenum
Transection of the proximal jejunum
Dissection under the 3rd parts of the duodenum

Figs 23-53(3)


Energy source is used for the dissection
Transecting the jejunum
Part for anastomosis
Transecting the jejunum
Part to be removed with specimen
Proximal part is tied with a tape and is slid underneath the SMA and SMV towards right side
Duodenum is brought out towards right side
Uncinate dissection

Figs 23-53(4)


Dissection of pancreas head from mesenteric vessels and portal vein from below upwards
Pancreas head specimen
CHD
Pancreas distal stump
Transected antrum
Liver
CHD
Pancreas stump
Transected antrum
CHD
Pancreas stump
Liver
Portal vein

Figs 23-53(5)


Closure of distal jejunal end
Bringing the jejunum through Tr mesocolon towards portal bed
Two layered pancreaticojejunostomy using 3 zero silk or polypropylene
Placing finger under the P-J stoma
P-J completed
Doing hepaticojejunostomy
CHD
Jejunotomy
Interrupted posterior layer is completed 4-5 sutures
P-J
Posterior layer of hepaticojejunostomy
Hepaticojejunostomy completed
P-J
Hepaticojejunostomy
Liver
P-J

Figs 23-53(6)


Completed antecolic GJ
Transected antrum
GB
Head of pancreas with tumour
Duodenum
Stenting of the stoma may be done
GJ can be done using stapler
Often stenting of pancreatic duct as well as CHD is done
Stenting
Specimen of Whipple's of another patient with duodenal carcinoma
Stapler transection of antrum and also jejunum can be done

Figs 23-53(7)

Figs 23-53(1 to 7): Technique of Pancreaticoduodenectomy—steps.



Fig. 23-54: Pancreaticojejunostomy in Whipple's operation.

Jejunostomy is done for feeding purpose at the end and is brought out through left side of the abdomen. Suction tube drain is placed and abdomen is closed in layers.

On table intraoperative octreotide is injected 100 micrograms intravenously usually at the beginning of the pancreatic resection.

If portal vein is involved, vascular resection can be done with internal jugular vein *(IJV) interposition graft*; usually from left side. Technique is often called as ***extended Whipple's operation or Fortner's regional pancreatectomy***.

Postoperative Care

Nasogastric tube is removed in 5-7 days; jejunostomy feeding is started in 5-7 days along with oral fluid. T-tube and pancreatic tube are kept for 21 days. Antibiotics are given. TPN may be needed. Daily monitoring with liver function, renal function, haemogram (with platelet count) and prothrombin time is needed. CVP line is better for all these purposes, immediate postoperative period despite less bleeding on table, hypotension is common, which is due to lot of fluid loss in 3rd space. So patient needs adequate fluid therapy to combat this. Intravenous octreotide is given daily either as infusion or at regular intervals for 5 days to reduce pancreatic secretions. Pancreatic leak can be identified by clear fluid leak from the drain. It may subside spontaneously; but often needs 1-2 litres saline wash daily. If it persists and patient deteriorates, then relaparotomy done and remaining pancreas including spleen has to be removed to save the life **(Figs 23-58 and 23-59)**.

The Surgical Resection is Divided into the following Six Clearly Defined Steps

1. ***A Cattell-Braasch* manoeuvre** is performed by mobilising the right colon and incising the visceral peritoneum to the ligament of Treitz. When complete, this manoeuvre allows retraction of right colon and small bowel downward and towards right exposing the third and fourth parts of duodenum. The omental bursa is entered by taking the greater omentum from the transverse colon. The middle colic vein is identified, ligated and divided before its junction with the


(Free finger apposition along the front of portal vein and SMV behind the neck of pancreas)
4. Transect stomach
3. Portal dissection
5. Transect jejunum and dissect ligament of Treitz, rotating duodenum under mesenteric vessels
Clockwise dissection in Whipple's
2. Extended Kocher manoeuvre (Assess operability by feeling uncinate and SMA and celiac axis)
6. Transect pancreas and complete retroperitoneal dissection by removing specimen from SMA
1. Cattell-Braasch manoeuvre exposing SMV

SMV. This allows greater exposure of the infrapancreatic SMV and prevents iatrogenic injury during dissection of the middle colic vein—MV junction.

2. ***The Kocher's manoeuvre*** is begun at the junction of the ureter and the right gonadal vein. The right gonadal vein is ligated and divided, and all fibro fatty and lymphatic structures overlying the medial aspect of the right kidney and inferior vena cava is removed with the specimen. The Kocher's manoeuvre is continued to the lateral edge of the aorta (extended Kocher manoeuvre), carefully identifying the left renal vein. Traditionally, the relation of the tumour to the SMA is assessed by manual palpation following a complete Kocher manoeuvre.
3. ***The portal dissection*** is initiated by exposing the common hepatic artery proximal and distal to the gastroduodenal artery. The gastroduodenal artery is then ligated and divided. Two large lymph nodes are commonly encountered during portal dissection, removal of this en-block with the specimen is necessary to adequately mobilise the hepatic artery and portal vein. The gallbladder is dissected out of the liver bed and the common bile duct transected just cephalad to its junction with the cystic duct. The anterior wall of the portal vein is easily exposed following division of common hepatic duct and medial retraction of the common hepatic artery. Bleeding caused by injury to posterior superior pancreaticoduodenal vein may be difficult to control at this time in the operation. Portal vein should be mobilised after stomach and pancreas have been divided as in step 6. The portal dissection is made more difficult in the presence of anomalous hepatic arterial circulation, particularly in reoperative cases when preoperative arteriography is of help.
4. The stomach is transected at the level of third or fourth transverse vein on the lesser curvature and at the confluence of the gastroepiploic veins on the greater curvature. The omentum is divided at the level of the greater curvature transection.
5. The jejunum is transected approximately 10 cm distal to the ligament of Treitz, and its mesentery is sequentially ligated and divided. The duodenal mesentery is similarly divided to the level of the aorta, and the duodenum and jejunum are then reflected beneath mesenteric vessels.
6. After traction sutures are placed on the superior and inferior borders of the pancreas using 2-0 silk (this is important to reduce bleeding from marginal vessels during transection), the pancreas is transected with an electrocautery at the level of portal vein. If there is an evidence of tumour adherence to the portal vein or the SMV, the pancreas can be resected at a more distant location in preparation for segmental venous resection. The specimen is cleared from SMV and often SMA depending on its posterior extension by ligating and dividing small venous tributaries to the uncinate process and pancreatic head. Complete resection of the uncinate process along with medial retraction of the superior mesenteric-portal vein confluence facilitates exposure of the SMA, which is then dissected out to its origin at the aorta. Frozen section analysis of the pancreatic and common hepatic duct transection margin is obtained. Positive resection margins mandate further resection until clear margins are achieved.

Pancreatic, Biliary and Gastrointestinal Reconstruction

Reconstruction proceeds in the counterclockwise direction and again in a stepwise and orderly fashion.


2. End-to-side choledochojejunostomy
1. End-to-side pancreaticojejunostomy
Counterclockwise reconstruction
3. End-to-side gastrojejunostomy (antecolic)
4. Jejunostomy tube drains

1. ***Pancreaticojejunal anastomosis***

   The pancreatic remnant is mobilised from retroperitoneum and splenic vein for a distance of 2 to 3 cm. The transected jejunum is brought through a small incision in the transverse mesocolon to the right or left of middle colic vessels. A two-layered, end-to-side, duct-to-mucosa pancreaticojejunostomy is performed. If the pancreatic duct is small (<4mm), a small silastic internal stent can be left behind under the anastomosis. Following completion of posterior row of interrupted 3-0 seromuscular sutures, a small full thickness opening is made. The anastomosis between the pancreatic duct and the small bowel mucosa is completed with 4-0 or 5-0 monofilament sutures either vicryl or prolene depending on the centre preference. The anastomosis is completed with placement of anterior row of 3-0 seromuscular sutures.

   Pancreaticogastric anastomosis

   The advantage claimed in this type of anastomosis is that there are less chances of pancreatic fistulae formation due to the good blood supply of the stomach and the presence of acidic environment that prevents activation of pancreatic enzymes causing less autodigestion at anastomosis site. The anastomosis is technically simple because the stomach is right in front of the cut remnant of the pancreas. The remnant is mobilised off the bed for 2-3 cms and brought into the stomach through an opening in the posterior wall of stomach. The pancreas is anastomosed using single layer of suture running from the pancreatic capsule to the gastric serosa using prolene 3-0 suture. Internal stent can be left in situ if the pancreatic duct is very small.
2. A single-layer biliary enteric (***hepaticojejunostomy***) anastomosis using interrupted, 4-0 absorbable monofilament sutures (PDS). It is important to align jejunum with the bile duct to avoid tension on the pancreatic and biliary anastomosis. A stent is rarely used in the construction of the hepaticojejunostomy.



Fig. 23-55: Hepaticojejunostomy in Whipple's operation.



Fig. 23-56: T-tube may be placed in the CHD and across the hepaticojejunostomy if needed; but it is not mandatory.

3. An antecolic, and end-to-side ***gastrojejunostomy*** is constructed in two layers. A posterior row of silk sutures is followed by a running, monofilament, full-thickness inner layer; the anterior row of silk sutures completes the anastomosis. The distance between the biliary and gastric anastomosis should allow the jejunum to assume its antecolic position (for the G-J) without tension. There is no harm in making a long (25-30 cm) afferent limb.
4. ***Feeding jejunostomy*** tubes are placed using the Witzel technique, and then two closed suction drains are placed. Enteral feeding via a jejunostomy tube avoids a delay in the hospital discharge due to poor oral intake.

Complications of Whipple's Operation

Pancreatic fistula, biliary fistula, sepsis, subphrenic abscess, respiratory complications, cholangitis and hepatic failure, renal failure, anastomotic dehiscence of any stomas, bleeding, postoperative acute pancreatitis, marginal ulcer, SMA or SMV thrombosis, portal vein thrombosis, gastric bezoar formation.

Pylorus Preservation Partial Pancreaticoduodenectomy (Traverso Longmire)

Preservation of the antropyloroduodenal segment in combination with pancreaticoduodenectomy was first described by Traverso and colleagues in 1978 (Traverso Longmire). Proponents of the technique argue that preservation of the antropyloric pump mechanism results in long-term upper gastrointestinal tract function with associated salutary nutritional squeal. Published data to date involve a retrospective comparison that has yielded mixed results.

Nevertheless, most pancreatic surgeons agree that pylorus preservation should not be performed for patients with bulky tumours



Fig. 23-57: Gastrojejunostomy in Whipple's operation. It can be hand-sewn or by using stapler on the posterior surface of the earlier transected part of the stomach.



Fig. 23-58: Pancreaticogastrostomy in Whipple's operation. Pancreatic secretion is neutralized in gastric acid pH.



Fig. 23-59: Periampullary carcinoma of pancreas—gross look in two different patients.

of the pancreatic head, duodenal tumours involving first or second part of the duodenum, or lesions in which pyloric and peripyloric lymph nodes are grossly positive.

The steps in pylorus preserving pancreaticoduodenectomy are identical to that of standard pancreaticoduodenectomy, except in the approach to the antrum, pylorus and the duodenum. Preservation of sufficient blood supply to the proximal duodenum and preservation of vagal innervation to the antrum and pylorus are critical. Therefore, appropriate caution must be exercised during the portal dissection to avoid unnecessary division of the right gastric artery or injury to the nerves of Latarjet. This is the fundamental technical difference in the pylorus-preserving procedure and is essential to facilitate a well-vascularised duodenojejunostomy and to avoid postoperative gastroparesis **(Fig. 23-60)**.



Fig. 23-60: Pylorus preserving pancreaticoduodenectomy.

The duodenum is divided approximately 2 to 3 cms beyond the pylorus. The blood supply to the first portion of the duodenum arises from the proximal branches of the gastroduodenal artery and the supraduodenal artery, both of which arise from the hepatic artery. When possible, the supraduodenal artery should be preserved. The duodenojejunostomy is performed in an end-to-side fashion using a single-layer technique with monofilament absorbable sutures.

TOTAL PANCREATECTOMY (TOTAL PANCREATICODUODENECTOMY)

Total pancreatectomy is rarely required for adenocarcinoma of pancreas. It can be performed for carcinoma of the body and tail that present early or are incidentally picked up on ultrasound. Total pancreatectomy is performed by modifying step 1 in the six-step pancreaticoduodenectomy. Following the completion of the Cattell-Braasch manoeuvre and identification of the infrapancreatic SMV, the greater omentum is separated from the left side of transverse colon and the splenic flexure is mobilised. The peritoneum lateral to the spleen is then incised in the cephalad direction to the gastroesophageal junction. The short gastric vessels are ligated and divided, allowing medial and cephalad retraction of the stomach. Mobilisation of the spleen and the pancreas from their retroperitoneal attachments to the kidney and the adrenals is completed. The inferior mesenteric vein is divided and the mesenteric root divided from the lateral border of the SMV to the lateral border of the aorta, staying anterior to the SMA. Division of the splenic artery and vein is delayed until steps 2 through 5 are completed. Then, in preparation for completion of the retroperitoneal dissection, the spleen and the distal pancreas are again reflected medially, exposing the origin of the splenic artery and the splenic vein—SMV junction. The splenic artery and vein are then ligated and divided. Hepaticojejunostomy and gastrojejunostomy are done similarly **(Fig. 23-61)**.



Fig. 23-61: Total pancreatectomy—specimen.

DISTAL PANCREATECTOMY

Any tumour in the body and tail of the pancreas; endocrine tumours when cannot be excised locally; trauma to the tail of the pancreas; in selected patients when chronic pancreatitis is localised to the tail of the pancreas with or without pseudocyst in the tail **(Fig. 23-62)**.



Fig. 23-62: Distal pancreatectomy specimen.

Usually distal pancreatectomy is done with splenectomy. Splenic preservation is often tried. Open and laparoscopic approaches are used for distal pancreatectomy. Invasion of the junction of splenic vein and portal vein by the tumour is an inoperable sign of the tumour. Any attempt of resection in such situation makes disastrous portal vein laceration **(Figs 23-63A and B)**.



Figs 23-63A and B: Cystadenocarcinoma of pancreas. CT picture of same patient.

Technique

Under general anaesthesia, patient is placed in supine position with left side upwards slightly. Lengthy upper midline incision or left subcostal incision is used. Abdomen is explored for operability and metastases.

Greater omentum is divided between ligatures and detached completely from the transverse colon. Splenic flexure is mobilised downwards and separated completely. Peritoneal layer is incised at the lower part of the pancreas to expose the lower margin. Care should be taken at this stage not to injure inferior mesenteric vein which will be ligated at a later period. Peritoneum along the superior margin is also incised with care as tortuous splenic artery is on the upper margin of the pancreas. Splenic artery near the neck of the pancreas is identified by feeling its pulsation. One should not get confused with the common hepatic artery. Splenic artery is dissected, isolated and ligated but divided only at later period **(Fig. 23-64)**.

Spleen is mobilised towards right of the patient by dividing splenorenal ligament. Posteriorly kidney, renal vessels and adrenal gland will be present from which tail of the pancreas is gently separated by blunt and sharp dissection as usually the plane is avascular. But if tumour is close to the tail of pancreas, there may be adhesions due to desmoblastic reaction or invasion of the tumour to these structures. Adrenal vein may close to the dissecting area which should be safeguarded. If tumour invasion occurs into the renal vessels (which are very well identified preoperatively by proper imaging), left side nephrectomy is to be done provided opposite kidney is functioning well. Spleen with tail, body of the pancreas is lifted upwards into the wound. Left gastroepiploic vessels and short gastric vessels are carefully ligated. Further dissection and elevation of the body of the pancreas will visualise the inferior mesenteric vein joining the splenic vein. Inferior mesenteric vein is doubly ligated with silk and divided. Further dissection posteriorly with finger or peanut will show the splenic vein joining the SMV to form portal vein. 2 cm away from this junction splenic vein is gently dissected from the tissues around as often it is embedded in the pancreatic tissue. Splenic vein is encircled with a right angle and doubly ligated and divided. Previously ligated splenic artery is divided with double ligation **(Figs 23-65 and 23-66)**.

Peripancreatic tissues are dissected to bare the neck of the pancreas. Neck is divided using stapler. Specimen is retrieved. Usually stapler transected proximal cut end of pancreas does not require any additional sutures. If stapler is not used then transected pancreas is closed using interrupted mattress sutures by 3-zero nonabsorbable suture—polypropylene or silk. Pancreatic duct needs a separate transfixation using 3-zero polypropylene suture. Cavity is inspected for any bleeding. Sutured pancreatic stump is again inspected. Tube suction drain is placed in the left subphrenic space. Abdomen is closed in layers.

Post-operative Care

Fluid therapy is continued; nasogastric tube is removed in 72 hours; drain is kept for 5-7 days. Antibiotics may be needed as sepsis can occur. Serum amylase and lipase estimation may require to be done during post-operative period.

Complications

Pancreatic fistula can occur which usually subsides spontaneously by conservative therapy.

Subphrenic abscess formation, acute pancreatitis, left-sided pleural effusion, complications of splenectomy like OPSI, injury to left kidney, left renal vessels, diaphragm and colon can occur.

RADICAL ANTEGRADE MODULAR PANCREATOSPLENECTOMY (RAMPS)

Here distal pancreatectomy with splenectomy is done from right towards left instead of standard left to right technique. This gives early control of splenic vessels and also achieves optimum tumour clearance. It is done for tumours of body and tail of the pancreas. Nodal clearance is also important in this technique. Greater omentum is freed from colon. Short gastric vessels are ligated and divided. Right colon is mobilized, SMV is identified; portal dissection is done; gastroduodenal artery is not divided; all lymph nodes are removed and reflected towards left on the body of the pancreas. Kocherisation should be done. Portal vein and SMV are separated from the neck of the pancreas like in Whipple's operation. Neck towards left of portal vein is transected after placing 4 stay sutures. Stump towards head of the pancreas is sutured securely using nonabsorbable sutures (polypropylene). Posterior peritoneum is opened; fat and lymph nodes are cleared from crus of the diaphragm, in front of the common hepatic artery; nodes adjacent to left gastric artery are dissected; left gastric vein (coronary vein) is dissected, ligated and divided. Splenic artery originating from the celiac trunk is identified, ligated with transfixation at its origin. Spleen and tail of the pancreas is dissected off. Dissection can be done anterior to adrenal gland (anterior RAMPS) or posterior to adrenal gland if tumour has invaded adrenal gland (posterior RAMPS). Inferior mesenteric vein is ligated here where it joins the splenic vein. But renal vessels and kidney are kept away from dissection. Once final mobilisation is done, splenic vein is doubly ligated and divided. Neck is transected using stapler or hand suturing of the cut head end of the pancreas is done using 3 zero polypropylene interrupted sutures after transection. Duct may be separately sutured.

Modified Appley's (Canadian surgeon, 1954) technique is RAMPS with resection of the celiac or common hepatic artery. Here blood supply to liver, duodenum and pancreas is achieved through inferior pancreaticoduodenal artery arising from SMA. Often an arterial (PTFE) graft from the aorta to proper hepatic artery is also done.

CHOLCECYSTOJEJUNOSTOMY

Cholecystojejunostomy is occasionally done as a palliation in carcinoma of pancreas. Even though choledochojejunostomy is better and ideal for palliation and also to relieve obstruction, in advanced malignancy with involvement of mesocolon and extensive nodes, simpler surgery like cholecystojejunostomy still carries a role because of its simplicity in doing it in selected patients. However, it is useful only if cystic duct remains patent. Technique is detailed in the chapter on gallbladder **(Fig. 23-67)**.


Large mass abdomen
left upper part
Incision — subcostal — bilateral
Mass from the
tail of the pancreas
Spleen
Mass from the
tail of the pancreas
Stomach
Dissecting and dividing
ligaments of spleen
Splenic artery

Figs 23-64(1)


Feeling splenic vessels in the pedicle
Splenic vessels

Figs 23-64(2)


Splenic vessels are individually dissected and doubly ligated
Splenic artery is ligated
Splenic artery is ligated
Ligated splenic artery
Splenic vein is doubly ligated

Figs 23-64(3)


Resected specimen in
distal pancreatectomy
Pancreatic proximal
stump
Left subphrenic space
after retrieval of the tumour
Cut specimen
Drain in left
subhepatic space

Figs 23-64(4)

Figs 23-64(1 to 4): Distal pancreatectomy for pancreatic tail tumour/mass.



Fig. 23-65: Mucinous cystadenocarcinoma of pancreas.



Fig. 23-66: Mucinous cystadenoma of pancreas [*Courtesy:* Dr Arunkumar MCh (Gastro) Kochin].



Fig. 23-67: Cholecystojejunostomy as a palliation in advanced carcinoma of pancreas is done occasionally. Gastrojejunostomy is added for possible duodenal obstruction.

SPLEEN

SURGICAL ANATOMY

Spleen is derived from the word *splen* in Greek; and *lien* from Latin. It is a wedge-shaped organ lying mainly in left hypochondrium, along the long axis of 10th rib. It is obliquely placed along the 10th rib downwards, forwards and laterally. It is wedged between fundus of stomach and diaphragm. Hilum of spleen transmits splenic vessels and nerves. Spleen has got anterior and posterior ends; two surfaces (parietal and visceral); three borders (superior is notched in front; inferior; intermediate) **(Fig. 23-68)**.

It is vascular purple-coloured soft organ. It is 12 cm in length; 7-8 cm in width; 2-3 cm in thickness. Normally spleen is not palpable. Its weight is 200 grams.

It is posteriorly related to left side diaphragm, diaphragmatic recess and left 9th, 10th, and 11th ribs. It is being related to left lung and pleura above these structures.

Its parietal surface is related to diaphragm; the visceral surface is related to stomach, splenic flexure of colon, pancreas and kidney. Upper pole is close to stomach and often may be fixed to stomach having short gastric vessels there. Lower pole is 4-7 cm away from the stomach **(Figs 23-69 and 23-70)**.

Ligaments of Spleen

Spleen is suspended by two ligaments *(a) lienorenal ligament, (b) gastrosplenic ligament.* These two are main/chief splenic ligaments


Neck
Body
Tail
Spleen
Head
Uncinate process
SMV
SMA
Neck
Body
Tail
Spleen
Head
Uncinate process
Left kidney
Splenic flexure
Left adrenal gland
SMV
SMA
Gastrosplenic ligament
Stomach
Spleen
Lienorenal ligament
Kidney

Fig. 23-68: Anatomy of spleen. Note the different relations of spleen which are surgically important during splenectomy.

which form splenic pedicle. Lienorenal ligament transmits blood vessels to spleen. The tail of pancreas lies in this ligament, which can be damaged during splenectomy. Outer layer of lienorenal/splenorenal ligament forms posterior layer of gastrosplenic ligament. The gastrosplenic ligament contains short gastric vessels which supply the left half of greater curvature of stomach. Gastrosplenic ligament also contains left gastroepiploic vessels below. Presplenic fold may be present in front of this gastrosplenic ligament which during traction may get torn and can cause bleeding from the left gastrosplenic ligament **(Fig. 23-71)**.



Fig. 23-69: Parietal surface of the spleen.



Fig. 23-70: Visceral surface of the spleen.


Phrenosplenic ligament
Pleura
Gastrosplenic ligament
Lung
Body
Diaphragm
Neck
Tail
Spleen
Head
Pancreaticosplenic ligament
Phrenocolic ligament
Uncinate process
Left adrenal
Splenocolic ligament
Left kidney
SMV
SMA
Pancreaticocolic ligament
Colon

Fig. 23-71: Ligaments and relations of the spleen.

Phrenicocolic ligament comes in contact with lower pole of spleen, which may be damaged during mobilisation of splenic flexure of colon. It extends below from the lateral margin of the splenic flexure of the colon reflecting upwards laterally touching to the lower pole of the spleen to reach diaphragm; it is closely related to the spleen as spleen stays on its surface forming splenic floor. It is not attached to the spleen.

Splenophrenic ligament reflects between upper pole of spleen and stomach towards inferior surface of the diaphragm. Even though it is avascular, it may cause bleeding while dividing and so bipolar cautery or other energy sources should be utilised, otherwise ligation may be required **(Fig. 23-72)**.


Gastrosplenic ligament
Splenic pedicle
Spleen
Lienorenal ligament
Kidney
Stomach
Liver

Fig. 23-72: Splenic pedicle contains lienorenal (splenorenal) and gastrosplenic ligaments; they are main/chief ligaments of the spleen (view from above).

Pancreaticocolic ligament runs between tail of pancreas and splenic flexure. Splenocolic ligament reflects from splenic flexure of the colon towards lower pole of the spleen medial to phrenocolic ligament.

Spleen is palpated under left costal margin during inspiration. It has to enlarge 2-3 times its normal size to become palpable.

Blood Supply

Arterial Supply

Splenic artery is the largest branch of coeliac artery but may arise from aorta or superior mesenteric artery, blood flow is 300 ml/min. Often it may arise from a common gastrosplenic trunk (left gastric artery and splenic artery) or common hepatosplenic trunk (common hepatic artery and splenic artery). Artery is 0.6 – 1.3 cm in diameter with 7-30 cm in length. It is tortuous. It runs in the upper margin of the pancreas. It initially crosses the left border of the aorta, then runs on the front of the tail of the pancreas and upper pole of kidney before reaching the splenic hilum. Tortuosity of the artery allows free movement of the spleen. Branches are dorsal pancreatic artery, posterior gastric artery, left gastroepiploic artery and arteria pancreatica magna. Artery passes through the lienorenal ligament to reach the splenic hilum where it divides into 5 or more branches. Short gastric arteries may arise from splenic artery or left gastroepiploic artery **(Fig. 23-73)**.

Splenic artery shows one of the two patterns of branches towards spleen. (1) *Magistral type* where there is long main splenic artery with short terminal branches as—superior terminal artery gives superior polar artery and often short gastric arteries. Inferior terminal artery gives penultimate and an ultimate branch and other branches inside the spleen. Inferior polar artery runs downwards towards inferior pole of the spleen. (2*) Distributive type*—Here superior polar artery directly originates from the splenic artery having an anastomotic branch with inferior terminate branch.

Venous Drainage

Splenic vein joins the superior mesenteric vein at right angle behind the neck of pancreas to form the portal vein. Often 2 or more splenic vein tributaries join and form splenic vein. Its other tributaries are left gastroepiploic vein, short gastric vein and pancreatic veins. Commonly inferior mesenteric vein joins splenic vein just before it joins the portal vein; but inferior mesenteric vein may join SMV or directly into the portal vein **(Fig. 23-74)**.

Splenic parenchyma contains *white pulp* and *red pulp*. *White pulp* lies in centre surrounding the central artery, which is a branch of trabecular artery. It is made up of lymphatic nodules with germinal centres and periarterial lymphatic sheaths with a network containing lymphocytes and macrophages. White pulp is surrounded by marginal zone which contains end arteries from central and peripheral peniciliary arteries **(Fig. 23-75)**.

Marginal zone contains marginal sinus which filters the materials from the white pulp. Immunoglobulins secreted by white pulp enter marginal zone and into main bloodstream. *Red pulp* is located outer to marginal zone. Red pulp contains cords and sinuses. Central artery gives reticular branches which open into these sinuses and cords wherein particles are phagocytosed. Commonly central artery eventually ends in these cords and sinuses. Few end branches of the central artery directly enter the pulp vein. Cords and sinuses eventually drain into pulp vein. Blood circulation through these cords and sinuses is known as '*open*' circulation (90%). Blood circulation through white pulp but not entering these cords and sinuses is known as '*closed*' circulation (10%).

Removal of non-deformable intracellular substances from deformable cells is known as "*pitting*". *Heinz bodies/Howell-Jolly bodies, Pappenheimer siderotic bodies* are removed by this method from RBCs. Post-splenectomy patients will show these bodies in


Short gastric arteries
Celiac trunk
Neck
Head
Uncinate process
Aorta
Superior polar artery
Superior terminal artery
Ultimate branch
Penultimate branch
Spleen
Inferior terminal artery
Inferior polar artery
Splenic artery
SMV
SMA
A
Short gastric arteries
Superior polar artery
Neck
Head
Uncinate process
Aorta
Penultimate branch
Ultimate branch
Superior terminal artery
Inferior terminal artery
Inferior polar artery
Spleen
Splenic artery
Left gastroepiploic artery
SMV
SMA
B

Magistral-bundled type of splenic artery pattern

Distributed type of splenic artery pattern

Figs 23-73A and B: Arterial distribution of the spleen (Splenic artery).



Splenic artery is in front of the splenic vein

Splenic artery is both in front and behind the splenic vein — coiled

Splenic vein is in front of the splenic artery

Fig. 23-74: Splenic vein tributaries and different patterns of its course.



Fig. 23-75: Splenic architecture. Architecture of spleen showing red pulp (peripheral); white pulp (central); open and closed circulation; marginal zone and sinuses and trabecular artery and vein.

the RBCs in peripheral smear. In splenunculi, these bodies will be absent even after splenectomy. Removal of aged/abnormal red cells is done by the process of "*culling*". RBCs which lose osmotic balance and membrane integrity are known as non-deformable and they are removed by this method. Half life of platelets is 10 days. In splenomegaly, 80% of platelets may be sequestered in spleen causing thrombocytopenia. Normally spleen is reservoir for platelets. 1/3rd of total platelet mass is present in spleen. In pathological status like immune diseases phagocytosis of platelets in spleen is accelerated by many folds. Splenomegaly and hypersplenism can cause neutropenia. Half life of Neutrophil is 6 hours. Bacterial clearance also occurs in spleen by phagocytosis. After splenectomy, patients are more prone to OPSI, *immunologic functions* like synthesis of antibody IgM; formation of lymphocytes; production of tuftsin, opsonins, properdin and interferons.

Lymphatic Drainage

It is to supra- and infrapancreatic nodes and splenic nodes.

Splenic Segments

Usually spleen has got two segments—superior and inferior. 15% of individuals may have three segments—superior, middle and inferior.

SPLENUNCULI (30%) (FIG. 23-76)

30% of individuals can have accessory spleen. These are single (60%), or two (20%) or multiple accessory spleens. Size of these accessory spleens varies from 0.5 cm to 10 cm.

Sites—Hilum of spleen (50%); near splenic vessels; tail of the pancreas (30%); splenic ligaments—gastrosplenic/splenorenal; mesocolon; greater omentum. After splenectomy, they undergo hyperplasia and lead to recurrence of the disorder for which spleen was removed. Blood peripheral smear in these patients with splenunculi *will not show* Howell-Jolly bodies, Pappenheimer siderotic bodies. Accessory spleen can also be occasionally present adjacent to left ovary or adjacent to left testis.

PRINCIPLES IN SPLEEN SURGERY

Initial immunisation for pneumococci, meningococci, haemophillus influenza by appropriate vaccines is necessary. Vaccine should be given 2 weeks prior to surgery.

Proper pre-operative evaluation depending on the condition to which patient undergoes splenectomy is important. CT, peripheral smear, platelet count, osmotic fragility test, prothrombin time, coagulation profile and bone marrow aspiration, when needed, have to be done.

Splenic surgery needs proper exposure of surrounding ligaments and structures, proper dissection of the splenic vessels, avoiding trauma to pancreas, stomach, colon and left kidney.

Laparoscopic splenectomy is ideal unless spleen is massively enlarged.

Accessory splenic tissue should be identified and removed. It is difficult to identify often these splenunculi but becomes mandatory when dealing with hereditary spherocytosis or idiopathic thrombocytopenic purpura.

Spillage of spleen during dissection or retrieval should be avoided. It will be troublesome in conditions like ITP.

Post-splenectomy sepsis is a life time risk to the patient. OPSI is more troublesome in splenectomy for trauma. Partial splenectomy, splenorrhaphy, mesh splenorrhaphy, splenic autotransplantation are other options that should be kept in mind. Splenic preservation in trauma is preferred unless patient is haemodynamically unstable or life-threatening haemorrhage sets in. On table Argon beam laser often helps to control bleeding from the splenic surface. Splenic salvage in



Fig. 23-76: On table photo of splenunculi with splenomegaly. Splenunculi should be removed, otherwise disease will recur.

splenic trauma could be non-operative and operative. Hilar injury, large splenic haematoma with a contrast splenic blush in CT are the contraindications for conservative/salvage approaches.

Post-operative sepsis like subphrenic abscess, pancreatitis, OPSI, pancreatic fistula, injury to adjacent organs, post-operative deep vein thrombosis are to be taken care of.

Before splenectomy, pre-operative splenic artery embolisation is occasionally done only in very large spleen to reduce the size of the spleen; but splenectomy should be done in specified period of 7-10 days, otherwise splenic necrosis, sepsis can occur.

Laparoscopic splenectomy is ideal for elective splenectomy unless spleen is very large in size. It is ideal for ITP as spleen would not be enlarged enormously here.

Adequate exposure should be achieved through a large incision. Small incision does not have a role in open splenectomy. Thoracoabdominal incision may be needed when spleen is adherent to diaphragm or usual abdominal incision may require to be extended as thoracoabdominal if there is difficulty in dissecting the spleen.

Splenic ligaments are usually vascular; they cause troublesome oozing and so need careful dissection, ideally using bipolar cautery. Perisplenic adhesions are also vascular and need ligation prior to division. Splenic vessels at the hilum are prone to tear as they are fragile.

Proximal control of the splenic artery at its origin is better in large spleen. Anatomical variation like coiling of splenic vein on the splenic artery may get injured causing torrential bleeding. In ITP splenic artery should be ligated first and platelets should be transfused only later. Even if splenic artery is ligated proximally, it should be ligated again distally at the hilum during final stage of the dissection.

Short gastric vessels should be carefully ligated and divided. Harmonic scalpel or transfixation sutures are better.

Proximal greater curvature should be invaginated using sero-muscular continuous or interrupted silk sutures to avoid greater curve necrosis.

In portal hypertension and myelofibrosis and in massive spleen normal avascular splenic ligaments will be very much vascular and can cause torrential bleeding.

Blood products like fresh frozen plasma, platelets are often needed while doing splenectomy in massively enlarged spleen.

Absolute haemostasis after removal of spleen is essential; bleeding from tail of the pancreas should be suture ligated with fine polypropylene transfixation. In other areas, bipolar cautery or ligation of the bleeders should be done.

Pancreatic injury should be avoided as pancreatic fistula or pancreatitis can occur. Gastric trauma, if it occurs, can result in gastric fistula which is very difficult to manage.

SPLENECTOMY

Indications for splenectomy:

1. Trauma.
2. In distal pancreatectomy, total pancreatectomy, rarely radical gastrectomy—removed *"en bloc"* with stomach.
3. Staging laparotomy in case of Hodgkin's lymphoma.
4. Hereditary spherocytosis and other haemolytic anaemias.
5. Idiopathic thrombocytopaenic purpura (ITP).
6. Portal hypertension with variceal bleeding—mainly gastric varices with splenic vein thrombosis.
7. Tuberculosis of spleen.
8. Others:
   Gaucher's disease.
   Chronic myeloid leukaemia, myelofibrosis.
   Felty's syndrome.
   Carcinoma of tail of the pancreas during distal pancreatectomy.
   Schistosomiasis.
   Splenic artery aneurysm.
   Splenic infarction.
   Cystic disease of spleen.
   Splenic tumours.

Elective Splenectomy

Pre-operative vaccine; haemogram; Adequate blood is kept ready if need arises, antibiotics, nasogastric tube, urinary catheterisation are needed preoperatively.

Incision—Left subcostal incision is commonly used; it can be extended towards right side or upwards as Kehr's incision. Lengthy midline incision is also used but not a preferred one. In trauma lengthy midline incision is the preferred one always to explore and address other parts of the abdomen. Midline incision may be preferred when spleen extends massively towards right iliac fossa. Occasionally, thoracoabdominal incision may be a need **(Figs 23-77 and 23-78)**.

There are two approaches for splenectomy—*anterior approach* wherein through lesser or greater omentum, splenic artery is isolated for ligation first, then dissected in front to later mobilise spleen medially to complete the splenectomy; *posterior approach* is first used in mobilising the spleen from lateral side medially, then dissection is done in the hilum of the spleen. In elective cases, anterior approach is ideal; in trauma and emergency situation, posterior approach is the preferred one **(Fig. 23-79)**.

Anterior Approach

Lesser omentum is opened to identify superior border of the pancreas. Splenic artery is identified. Peritoneum over it is opened. Splenic artery at the level of the body of the pancreas is dissected, isolated and ligated. Instead of ligating it, an umbilical tape or vascular clamps can be applied to it to have a good control. Alternatively, splenic artery can be approached after opening the gastrocolic ligament (greater omentum, left gastroepiploic vessels are ligated; superior margin of the body of the pancreas is dissected to identify the splenic artery which is ligated doubly using silk sutures. Short gastric vessels are ligated from below upwards along the gastrosplenic ligament; energy source like harmonic scalpel or ligaseal will be very helpful here **(Fig. 23-80)**.


1
2
3
4
5
1. Left subcostal incision
2. Lengthy midline incision
3. Kehr's incision
4. Bilateral subcostal incision
5. Thoracoabdominal incision

Fig. 23-77: Incisions used for splenectomy.



Fig. 23-78: Kehr's incision splenectomy.



Fig. 23-79: Splenectomy.

Splenophrenic and splenorenal ligament is gently divided as it is usually avascular but ligation and division are better or by using energy sources. Spleen is dissected off from the Gerota's fascia. Plane is created between tail of the pancreas at its lower border and posterior abdominal wall and with finger dissection, finger can be encircled around.

Splenocolic ligament is divided and left flexure of the colon is released downwards. Remaining short gastric vessels and other peritoneal attachments are released using bipolar cautery and scissor or by ligation and division. Phrenicocolic ligament is also divided properly.

Spleen is elevated forward and medially to reach the splenic hilum and tail of the pancreas from behind. Splenic artery above and splenic vein below is identified and gently separated from tail of the pancreas. Splenic artery is dissected, isolated and ligated doubly using silk and divided. Branches of the splenic vein are divided after prior ligation. Splenic vein needs two or three proximal ligations; splenic vein is ligated at the end but care should be taken not to tear the vein by undue traction on the spleen towards front and medially. Splenic hilum with splenic vein is divided to get the splenic specimen out.

In elective cases for haemolytic diseases, meticulous search for accessory spleen is made out and should be removed properly. Spillage of the spleen should be avoided absolutely.

Seromuscular sutures should be placed on the greater curvature of the stomach towards fundal half side to prevent gastric necrosis or bleeding or leak. Either continuous or interrupted 2-zero silk sutures should be placed **(Figs 23-81 and 23-82)**.

Absolute meticulous haemostasis on the surface near the tail of pancreas and in relation to different ligaments is essential. Transfixation ligatures or bipolar cautery should be used to achieve that.

Suction tube drain is placed. Abdomen is closed in layers.

Posterior Approach

Spleen is held medially towards right. Splenocolic and phrenocolic ligaments are divided to make splenic flexure of the colon descend downwards. Splenophrenic ligament is released. Splenorenal ligament is identified from behind which is incised carefully to expose the splenic vessels. In trauma where there will be continuous bleeding, assistant is made to put his thumb and index finger between the


General anaesthesia
Nasogastric tube
Catheter in place
Sand bag under left side abdomen
Bilateral subcostal incision

Figs 23-80(1)



Figs 23-80(2)





Figs 23-80(3)

Figs 23-80(1 to 3): Splenectomy in a large spleen through open bilateral subcostal incision.


Greater curvature is invaginated using 2-zero vicryl
or silk — seromuscular continuous or interrupted sutures
Spleen removed
Splenic
pedicle ligated

Fig. 23-81: Greater curvature of the stomach near fundus and proximal body should be invaginated using seromuscular sutures. It prevents greater curve necrosis.

pedicle, otherwise an atraumatic occlusion clamp can be placed across the tail of the pancreas including the hilum to control the bleeding temporarily. Splenic artery is doubly ligated; branches of vein are ligated. Splenic vein is ligated doubly. Spleen is removed. Occlusion clamp is released. Any bleeding points in the pedicle are again transfixed using vicryl or silk and ligated. Tube drain is placed. Abdomen is closed in layers.

Postoperative Care

It is usual to keep a nasogastric tube in place for 24-48 hours; urinary catheter may be needed. Often antibiotics are needed in post-operative period. Coagulation profile monitor, observation for sepsis, left-sided atelectasis and pleural effusion are a must. Low molecular weight heparin, leg exercises and respiratory physiotherapy are always given.

MANAGEMENT OF SPLENIC TRAUMA

Splenic trauma is the *most common* blunt injury in the abdomen. Injury can be simple avulsion to hilar transection. It may be associated with injuries to left lobe liver, diaphragm, left lung, splenic flexure, small bowel or pancreas **(Figs 23-83 to 23-91)**.

Splenic organ injury scale (1994)

Grade I	Non-expanding subcapsular haematoma < 10% surface area. Non-bleeding capsular laceration with < 1 cm depth
Grade II	Non-expanding subcapsular haematoma, 10-50% surface area. Non-expanding intraparenchymal haematoma < 5 cm in diameter Laceration—capsular tear 1-3 cm in depth, which does not involve trabecular vessel
Grade III	Expanding subcapsular or > 50% surface area or ruptured bleeding subcapsular haematoma/intraparenchymal haematoma. Intraparenchymal haematoma > 5 cm or parenchymal laceration > 3 cm depth involving trabecular vessels
Grade IV	Laceration involving segmental or hilar vessels with > 25% devascularisation
Grade V	Shattered or avulsed spleen; hilar devascularsation with entire spleen devascularisation

Non-operative Management

Splenic trauma can be managed in majority of patients (65%) by non-operative management by observation, haemodynamic monitoring, output chart and abdominal girth measurement. Initial CT scan is a must to assess the grading of injury. Daily ultrasound monitoring and haematocrit are also important. Absolute bed rest for initial 7-10 days is needed until clot gets localised and organised. Antibiotics, blood and plasma transfusions and fluid management are needed. If any time the surgeon feels that non-operative management is not suitable, then one should go ahead for surgical intervention.



Figs 23-82(1)



Figs 23-82(2)



Figs 23-82(3)



Figs 23-82(4)



Figs 23-82(5)



Figs 23-82(6)

Figs 23-82(1 to 6): Splenectomy in a massive spleen—subcostal incision extending towards right.

Splenic trauma may be avulsion of the capsule, superficial tears, partial transverse tears, complete transverse tears, longitudinal tears, stellate tears, subcapsular haematoma and hilar injuries.

Note:

- If patient shows features of haemodynamic instability—blood pressure below 90 mm Hg, pulse rate above 120/minute, if patient does not show any positive response after 2 litres of crystalloid solution infusion, then non-operative management should be abandoned.
- Non-operative approach prevents possibility of OPSI, thrombocytosis causing possible DVT
- 80% of children (due to more elastin in spleen and complete coverage with ribs in childhood) and 50% of adult with splenic injury are treated with nonoperative method.
- Failure rate in nonoperative management up to grade II is 15-20% which is gradually reducing to 5% in many centres. It is more in patients with age more than 55 years.
- Delayed splenic rupture and formation of splenic pseudoaneurysm are problems in non-operative approach.
- Normal activity of the patient can be resumed only after 3 weeks following non-operative treatment in grade I and II injuries; after 8 weeks in grade III or beyond usually with a confirmation by CT scan.



Fig. 23-83: Types of splenic injury: (A) Subcapsular hematoma; (B) Incised wound; (C) Lacerated wound; and (D) Hilar injury.



Fig. 23-84: Reconstructed CT image of left lower rib fracture. It is often associated with splenic injury and left lung and diaphragmatic injuries.



Fig. 23-85: Splenic subcapsular haematoma.



Fig. 23-86: Deep transverse splenic lacerations.

Surgical Intervention

Splenectomy

Type of intervention needed is decided based on CT finding as well as on table operative findings. If there are extensive lacerations, large progressive splenic laceration with haematoma or perisplenic haematoma extending on both poles of the spleen, then splenectomy may be the only option. Splenectomy for trauma is done through posterior approach for quick reach and control. An occlusion clamp or vascular clamp is placed across the pedicle close to the tail of the pancreas initially by placing index finger underneath the pancreas. Lacerated spleen is held medially and towards right **(Fig. 23-92)**.

Splenophrenic, splenocolic and phrenocolic ligaments are divided to reach the splenic hilum along the lienorenal ligament. Splenic artery is identified, dissected and ligated doubly using silk. Splenic vein will b e at lower part of the spleen is also ligated and divided. Rest of the attachments are also better ligated and divided. If surgeon is holding the spleen, then through right-angled Mixter instrument, dissection is done to pass ligatures and assistant will tie the knots; otherwise assistant should hold the spleen gently but firmly towards right and surgeon himself can place the ligatures. Spleen is removed. Rest of the abdomen is observed for additional injuries like that of diaphragm, liver, kidney, colon, small bowel and pancreas. Blood transfusion is done as commonly it is indicated. If there are no bowel and liver injuries, then autotransfusion of collected blood of haemoperitoneum can be done in theatre after proper filtering.



Fig. 23-87: Large splenic haematoma—splenectomy was done.



Fig. 23-90: Subcapsular haematoma. It can rupture late and can cause shock in the hospital or after discharge. Straining may precipitate rupture of the haematoma. Haematoma resolution should be confirmed by imaging prior to when the patient starts heavy straining works.



Fig. 23-88: Hilar injury—needs splenectomy.



Fig. 23-91: Stellate tear in the spleen.



Fig. 23-89: Multiple tears often need splenectomy. If it is on to one segment, then partial splenectomy can be tried.

Splenic Preservation Surgeries

Small injuries like superficial lacerations which are often observed as iatrogenic injury during gastrectomy, pancreatic surgeries can be controlled by pressure, packing, haemostatic agents, surgical, haemoclips, omental pedicle patch, suturing, etc. Argon beam laser is useful for surface oozing. These are superficial avulsions of capsule of the spleen. *Surgicel* is oxidized cellulose. Initially a gauze is placed gently but continuous firm pressure is applied for 10 minutes. Then gauze is removed; two layers of surgicel are applied again and another gauze over it; pressure is applied for 10 minutes. Gently apply pressure and outer gauze is removed to retain the surgicel at place. Avitene is another alternative to control the capillary ooze. Using forceps avitene is applied on the raw area for about 4 mm thickness; gentle pressure is applied using dry gauze for 5 minutes. Gauze is removed.

Transverse tears: Partial transverse tears can be sutured using 2-zero vicryl interrupted sutures. Initially haemostasis is required. Complete transverse tear needs partial splenectomy. Segment which is blue and



Fig. 23-92: Splenectomy in a trauma patient; lengthy midline incision is used; posterior approach is better. Soft vascular or occlusion clamp can be applied to begin with on the pedicle near the tail of the pancreas to control bleeding.

dusky is removed retaining opposite one, either superior or inferior, depending on the involvement **(Figs 23-93 and 23-94)**.

Longitudinal tears: As they cross across the segments, it is often difficult to manage and conserve. However, conservation is possible if one could be able to achieve proper haemostasis. Once it is so, omental pedicle is wrapped on the lacerated defect of the spleen and sutured over it. Further bleeding warrants splenectomy **(Fig. 23-95)**.

Splenorrhaphy

Splenorrhaphy is one of the methods of splenic conservation practised. Here spleen should be carefully mobilized from the lateral aspect of the spleen and omentum. Posterior part of the spleen is packed with a mop. Assistant can gently place the thumb on the splenic artery to control bleeding. Clot on the left subphrenic area and on the lacerated wound is gently removed; care should be taken not to extend the laceration during this step. Small bleeders inside the wound are ligated using 4-zero vicryl. Wound is sutured with mattress sutures using 2-zero vicryl by taking bites from the capsule. Surgicel and Teflon pledgets can be used during capsular suturing. Just simple sutures will not hold the wound **(Fig. 23-96)**.

Splenorrhaphy by suturing is usually done for a transverse tear, usually single or often two. Longitudinal tear is difficult to appose by suturing. Multiple tears are difficult to manage. In such a situation, absorbable mesh is placed around the spleen by completely wrapping



Figs 23-93A and B: Transverse tear may be superficial or deep. Superficial tear is sutured—mattress interrupted one. Deep tear needs omental buttress or mesh wrapping; observation and repeat imaging are essential. If general condition deteriorates, partial or complete splenectomy should be done.



Fig. 23-94: Superficial avulsion or simple tear can be sutured by interrupted mattress vicryl 2-0 sutures.



All bleeders are carefully suture-ligated; omental pedicle is placed over the defect and sutured to splenic capsule using interrupted 2-zero sutures

Fig. 23-95: Longitudinal tear needs omental buttressing on the wound.



Fig. 23-96: Splenorrhaphy—diagrammatic look.

it around; a loose purse string is placed on the mesh on the inner aspect round the hilum. 2-3 plication sutures are placed on the outer surface to fix it (*mesh wrapping*).

In especially clean incised wound, spleen can be salvaged by suturing the wound carefully with placement of gel foam, topical thrombin, absorbable mesh wrap over the wound. Suture repair, oxidised cellulose and debridement of lacerated spleen—are other methods used. Temporary occlusion of splenic artery is often needed during splenorrhaphy. 10% of splenic injuries undergo splenorrhaphy. Its application is getting reduced due to non-operative approach in such patients. But in class IV or V injuries, splenorrhaphy is not possible.

Advantages of Splenorrhaphy: It avoids OPSI; avoids dead space and so prevents potential space for subphrenic abscess; cellular components of blood are better maintained.

Partial Splenectomy (Hemi)

If deep injury to one of the segments of the spleen has occurred and if it is not possible to suture it by Splenorrhaphy, then partial splenectomy can be tried. Splenic artery is isolated proximally after initial lateral mobilisation of the spleen gently. Its branches—superior polar and inferior polar vessels are identified. Artery of the injured segment is dissected and ligated very close to the spleen in the hilum. On the other hand, without dividing the polar artery at the hilum, partial splenectomy can also be done; here splenic artery is isolated and silastic tape is placed around to control the bleeding; all bleeders on the hilum towards injured side are ligated and divided; injured spleen part is divided. Small bleeders are ligated on the surface with 4-zero vicryl. Sling on the splenic artery is released; surface is observed for any bleeding if it is so controlled with sutures. Cut edge of the partial splenectomy is sutured with mattress sutures with or without Teflon pledgets on both sides **(Figs 23-97 and 23-98)**.

Suction tube drain is placed; wound is closed in layers. Even though the patient is undergoing conservative surgery, vaccine should be given; children should receive penicillin prophylaxis.

LAPAROSCOPIC SPLENECTOMY

First laparoscopic splenectomy was done in 1991 by Delaitre et al. He also started hanging spleen approach in 1995. Richardson adapted leaning spleen approach later.

Indications

Haematological diseases like ITP, Felty's syndrome, thrombotic thrombocytopenic purpura, Thalassaemia and pancytopenia. ITP is the commonest indication.

Hypersplenism, mobile spleen causing recurrent torsion, splenic cysts.

Splenic artery aneurysm.

Benign tumours of the spleen.

Staging in Hodgkin's lymphoma.

Contraindications

Massively enlarged spleen, splenic injury, splenectomy in portal hypertension, splenic vein thrombosis, pregnancy, previous upper abdominal surgery and splenic abscess are contraindications. However, these indications may be relative. In certain situations, laparoscopic splenectomy can be tried if experts are doing it. Obesity, spleen more than 30 cm and approximately of 3 kg weight is contraindicated.



Fig. 23-97: Partial splenectomy.


Deep tera on the upper part of the spleen
Splenic superior polar artery is ligated; spleen is carefully removed at its upper part
Mattress sutures are placed using 2-zero vicryl sutures
Teflon pledget support can be used in front and behind

Fig. 23-98: Partial splenectomy—technique.

Preoperative Preparation

Evaluation is same as for open method. 2 weeks prior to the surgery immunisation against pneumococcal, meningococcal and haemophillus bacteria should be given.

Approaches

Anterior approach shows easier exploration for accessory spleen, splenic artery, easier rapid conversion into open midline incision, when need arises **(Fig. 23-99)**.



Fig. 23-99: Port positions and patient position for laparoscopic splenectomy.

Lateral approach allows easier retraction of stomach and colon; easier dissection of tail of pancreas and lower pole; splenic pedicle can be assessed and addressed easily; trocar positions are easier; operative ergonomics are better; easier control of short gastric vessels and minimum manipulation of the spleen which prevent splenic trauma and spillage.

Rotating operative table is ideal for this procedure. Right up position with surgeon standing on the right side; cameraman on the left of the surgeon on the right side of the patient. 30-degree telescope and harmonic scalpel are better and ideal.

10 mm port is umbilical for camera; 5 mm left hand working port is between epigastrium and camera; 10 mm right hand working port is at left midclavicuar line, if endovascular stapler is being used this port should be 12 mm; 5 mm epigastric port for retraction of the stomach; left anterior axillary line 5 mm port when needed to retract spleen.

Technique—Spleen is retracted using an instrument through the anterior axillary line port; stomach is retracted through the epigastrium port.

Dissection starts with identifying the splenic artery. Two-hand technique, traction and counter-traction are needed for easy dissection. After dividing gastrosplenic ligament by dividing the short gastric vessels using harmonic scalpel or clips or bipolar cautery, stomach is mobilised and retracted medially and in front.

Peritoneum on the splenic artery adjacent to the upper border of the pancreas is incised to identify it. Splenic artery is gently dissected circumferentially to place a silk ligature. Ligature is tied but artery is not divided now; artery is divided only at a later period (ligation in continuity).

Splenic flexure of the colon is mobilised by dividing splenocolic, phrenocolic and other attachments; inferior pole of the spleen and lower part of the splenic hilum are visualised. Splenophrenic ligament is divided using harmonic scalpel to expose the splenorenal and retrosplenic ligaments. These ligaments are also divided to expose the hilar contents/vessels properly. Now spleen is hanging by its diaphragmatic attachment above. Splenic vein is seen in the lower part of the opened splenorenal ligament; often its wide tributaries also may be present. Ideal way to tackle these vein/veins is to pass a ligature around it using silk. Bipolar, harmonic clipping may not be adequate for this. Endostapler also sometimes may not hold. Splenic artery is doubly ligated again and divided. Splenic artery can be divided using harmonic scalpel as already once it is ligated proximally.

Once hilar vessels are divided, remaining parts of the attachment are released using harmonic scalpel. Separate upper pole vessel may be present which needs ligation, if harmonic scalpel is used.

Spleen is placed into a plastic impermeable retrieval bag; bag opening is brought through the left 10 mm port but may require lengthening of the port incision to retrieve the bag. Otherwise through bag opening, morcellator is passed to crush the spleen and retrieve the bag with specimen.

Laparoscopic splenectomy is also a good alternative in many splenectomies when splenomegaly is not massive. It is not useful in massive spleens and trauma.

Problems in laparoscopic splenectomy

Large spleen finds it difficult to manipulate and visualise; splenic artery can be approached through the lesser sac like often which is done in open method after opening the lesser omentum.

Adhesions between spleen and diaphragm often may be vascular and difficult to release through laparoscopy.

Venous tear and bleeding is often difficult to control; such bleeding needs real pressure and packing and that is difficult to achieve.

Spillage during dissection and retrieval of specimen may be hazardous in conditions like ITP; splenunculi might get missed, leading into failure in outcome.

Pre-operative splenic artery embolisation in a large/massive spleen, splenic artery aneurysm, portal hypertension reduces the size of the spleen which makes dissection and surgery much easier; but it is not done always. But it may induce severe perisplenitis creating troublesome dissection itself.

Capsular disruption during manipulation should be avoided to prevent splenosis from developing.

COMPLICATIONS OF SPLENECTOMY

Complications

1. Haemorrhage and shock
2. Haematemesis
3. Pancreatitis
4. Pancreatic fistula
5. Gastric dilatation
6. Left-sided pleural effusion
7. Left-sided colonic injury
8. Severe sepsis
9. Changes in cellular component of blood
10. DIC

Haemorrhage—mainly from short gastric vessels. Re-exploration and control of bleeding are needed.

Acute gastric dilatation—needs nasogastric tube aspiration.

Haematemesis due to mucosal congestion following ligation of short gastric vessels.

Left-sided pleural effusion and left basal atelectasis (left lobe atelectasis is the commonest complication) (30%).

Left subphrenic abscess.

Pancreatitis following damage to tail of the pancreas and pancreatic fistula (3%).

Haematologic changes: Rise in WBC and platelet count, rise in abnormal RBCs and RBC bodies.

Gastric fistulas—it is better to invaginate the greater curvature using seromuscular silk or vicryl interrupted sutures.

Left-sided colonic injury.

Infection—Post-splenectomy septicaemia, OPSI—most dangerous.

Portal vein thrombosis can occur.

DVT as late sequelae after splenectomy is often dangerous. Risk is 4 times more than non-splenectomised people and also pulmonary embolism. It is better to put them on long-term small dose of *aspirin* to reduce the incidence of thromboembolism.

Overwhelming Post-splenectomy Infection (OPSI)

As there is reduced IgM, tuftin, properdin and other antibodies, phagocytosis of encapsulated bacteria is defective. So, the post-splenectomised patient is more prone for *Pneumococcal septicaemia* (commonest), *N. meningitides, H. influenzae and Babesia microti* infections. Risk is more in patients on chemotherapy, radiotherapy and haemolytic diseases. Incidence is 4% or less. It is common in first two years after splenectomy. But it can occur any time. Risk persists for lifetime. Features—Prodromal phase—fever, chills, sore throat; hypotension, shock; DIC; respiratory distress, coma, death. Mortality for fully developed OPSI—50-70%.

Prevention

Pneumococcal vaccine should be given to all splenectomised patients. Polyvalent pneumo-vac is given 2-3 weeks prior to surgery and soon after recovery from surgery and it is repeated once in 5 years (given to patients older than 2 years). Other vaccines advised are meningococcal vaccine (only to those who travel with high risk), *H. influenzae* 'B' vaccine (to all, whatever the age, once in 10 years). In malaria endemic areas, antimalarial prophylaxis is given for patients after splenectomy.

Treatment of OPSI—Antibiotics like Cefoperazone, Ceftazidime, Amikacin; Ventilatory support—ICU care; blood transfusion; immunoglobulin transfusion; nutrition (TPN) and maintaining of urine output.

Prevention of OPSI—Lifelong prophylaxis using benzathine penicillin 12-24 lakh units controversial in adults (mainly it is given to children; changing concepts say it is selective in adults); pneumococcal vaccine given 2-3 weeks prior to splenectomy—gives 70% protection. *H. influenzae* B-type vaccine and meningococcal vaccine are given only to high-risk groups, as its effects are for short-term. So, it is not routinely given.

Note: Protection by vaccine is not completely guaranteed **(Fig. 23-100)**.

Note:

- OPSI is more common when splenectomy is done for malignancy or haematological diseases or done in young individuals.
- Usage of prophylactic penicillin (benzathine) is controversial in adults even though it is beneficial in children up to 16 years.
- OPSI can occur at any time after splenectomy. Drugs like erythromycin, amoxicillin are also used as prophylactic agents.
- Mortality in fully developed OPSI (hypotension, DIC, MODS) is 60%—very high.
- Patients who survived after OPSI with therapy may develop residual problems like—gangrene of limbs, deafness, meningitis, mastoid osteomyelitis, heart valve destruction.
- 7% of OPSI cases have S pneumonia sepsis. Others are – N meningitidis, H influenzae, Capnocytophaga canimorus after dog bite.
- PPV 23 is the commonest vaccine used. Revaccination is done once in 5 years; decline in pneumococcal antibody level may be the criteria for revaccination.
- Preservation of 25% of spleen is sufficient to protect against pneumococcal infection. So, partial splenectomy is definitely helpful.
- Splenic autotransplantation into the omental pouch is under trial at present to reduce chances of OPSI.



Fig. 23-100: Splenic aneurysm. It is the commonest site of aneurysm in the abdomen after aorta. Most common in women, due to atherosclerosis. Congenital splenic artery aneurysm can occur. Splenic artery pseudoaneurysm (10%) can occur after an attack of acute pancreatitis which may cause life-threatening rupture.

MESH SPLENOPEXY

It is also known as splenic mesh wrap. It is done for trauma. Electively it is often used in wandering/mobile spleen (*Splenoptosis*).

In open method in trauma, absorbable mesh is wrapped around completely. It is partly haemostatic and creates tamponade also.

Different methods are there to place the mesh as a wrap. Mesh may be wrapped around completely and at the hilar level it is bunched loosely using purse string suture. As per another method, a large absorbable mesh is taken. At its centre, a circular gap is made through which poles of the spleen are slid and mesh is wrapped from hilum outwards; mesh margins are sutured on the parietal surface of the spleen.

In wandering spleen, spleen is rotated to correct the torsion; after mobilisation, spleen is placed over one large mesh, which is fixed above and lateral to the lateral abdominal wall. Another similar mesh is placed on the front aspect of the spleen, which is also fixed to the lateral abdominal wall above and mesocolon below.

Procedure can be done in open or laparoscopic method also.

Chapter 24

Colonic Surgeries

SURGICAL ANATOMY

Colon extends from ileocaecal valve to rectum. It is 135-150 cms in length. Right colon is caecum, ascending colon and hepatic flexure; left colon is sigmoid colon, descending colon and splenic flexure. Transverse colon which is freely mobile joining part of right and left surgical units.

Caecum is below the ileocaecal valve, usually of 6 cm long and 7.5 cm in width. It is situated in the lateral part of the right iliac fossa. Posteromedially there is appendix. Posteriorly caecum is related to right iliopsoas, genitofemoral, femoral and lateral cutaneous nerve of thigh, genital vessels and external iliac artery. Retrocaecal appendix will be behind it. Caecum may be of different types depending on its development (caecum develops from postarterial segment of the midgut loop as caecal bud). Usual *ampullary* type is 80% common where right caecal pouch is larger and appendix arises at its medial side. *Conical* type has appendix at its tip (12%); *intermediate* has right and left parts of the pouch of equal size with appendix coming out from its depression. Caecum gets its arterial supply from caecal branch of ileocolic artery; venous drainage into SMV. Its nerve supply is of midgut—T11; L1, parasympathetic is vagus. Ileocaecal valve opens on its posteromedial part of caecocolic junction. Ileocaecal valve has got two lips (upper lip is horizontal at ileocolic junction and lower lip is concave, is at ileocaecal junction) and two frenulae (anterior left is rounded; posterior right is narrow and pointed). When caecum distends valve closes preventing reflux of caecal contents **(Figs 24-1A and B)**.

Caecum is fixed to posterior abdominal wall. In 25% of individuals, caecum is mobile. Mobility may precipitate volvulus or intussusception. Ileocolic / superior ileocaecal fossa, which opens towards left, is formed by fold of the peritoneum formed by anterior caecal artery. It is related to ileum and its mesentery, ascending colon and ileocaecal vessels in front. Inferior ileocaecal fossa is formed by bloodless fold of Treves extending from the terminal ileum and caecum in appendicular mesentery. It is below the ileum and its mesentery, in front of the mesentery of the appendix. Retrocaecal fossa is located behind the caecum, left of the right paracolic gutter, right of the mesentery **(Fig. 24-2)**.



Figs 24-1A and B: Anatomy of ileocaecal valve.

Ascending colon is usually *fixed posteriorly* but can be mobile with a mesentery in 11-35% of individuals. In such situation, caecum will also be mobile along with ascending colon; it may lead into caecal volvulus along with ascending colon. Often there will be an abnormal connective tissue band running across the ascending colon called as *Jackson's veil*; it may often be vascularised. From the right sided


Superior ileocaecal fossa
Anterior caecal artery
Inferior ileocaecal fossa
Retrocaecal fossa

Fig. 24-2: Fossae in relation to caecum.

posterior abdominal wall it extends downwards and inwards getting attached to the anterior longitudinal ligament of ascending colon; often this veil may extend into caecum also. Ascending colon is 12 cm in length extending from caecum to hepatic flexure up to the inferior surface of the right lobe of liver. Behind it is related to iliacus, iliolumbar ligament, quadratus lumborum, transversus abdominis, lateral cutaneous, ilioinguinal and iliohypogastric nerves, iliolumbar vessels, 4th lumbar artery and right kidney **(Fig. 24-3)**.

Right colic (hepatic) flexure: Ascending colon forms right colic / hepatic flexure; hepatic flexure bends forwards, downwards and left to continue as transverse colon. Hepatic flexure is related to lower part of the right kidney and inferior surface of the right lobe of the liver.

Transverse colon is 50 cm in length extending from right flexure to left flexure. It hangs in the middle downwards like a suspension. It is suspended by transverse mesocolon, which is attached to anterior border of the pancreas and so creates wide range of mobility. In front it is related to greater omentum; behind it is related to 2nd part of the duodenum, head of the pancreas. Transverse mesocolon is double fold of peritoneum, which begins from the anterior border of the pancreas; middle colic artery runs in it. Middle colic artery may get damaged during gastrectomy due to adhereons during division of the greater omentum due to adhesions.

Left colic (splenic) flexure: It extends from the junction of the transverse colon to descending colon; it bends backwards and downwards towards descending colon. It is related behind to left kidney and diaphragm below to anterior end of the spleen. *Phrenocolic ligament* extends as peritoneal fold from the splenic flexure to the 11th rib at midaxillary line; it also supports the spleen forming bed for it. It forms the upper limit of the left paracolic gutter. Splenocolic ligament is located between spleen and splenic flexure **(Figs 24-4A and B)**.

Descending colon is 25 cm long and extends from the left colic flexure to the sigmoid colon, vertically running up to iliac crest and medially on the iliopsoas muscle; in the pelvic brim it continues as sigmoid colon. Descending colon is retroperitoneal; it is rare to have a mesocolon. Behind it is related to transverse abdominis, quadratus lumborum, iliopsoas, iliohypogastric, ilioinguinal, lateral cutaneous, femoral and genitofemoral nerves, iliac branches of the iliolumbar vessels and testicular and external iliac vessels.

Sigmoid (pelvic) colon: It is about 35 cm in length extending from pelvic brim to 3rd piece of sacrum to continue as rectum. It is suspended with sigmoid mesocolon. Iliac part of the sigmoid is fixed one; pelvic part is mobile one with sigmoid mesentery. Left ureter passes


Jackson's veil

Fig. 24-3: Jackson veil/membrane extending from lateral abdominal wall on the anterior surface of the ascending colon.


Phrenosplenic ligament
Pleura
Gastrosplenic ligament
Lung
Body
Diaphragm
Neck
Tail
Spleen
Head
Pancreaticosplenic ligament
Phrenocolic ligament
Uncinate process
Left adrenal
Splenocolic ligament
SMV
SMA
Left kidney
Pancreaticocolic ligament
Colon
A
Stomach
Spleen
Gastro colic ligament (greater omentum) divided
Left kidney
Pancreaticocolic ligament
Splenocolic ligament
Renocolic ligament
Splenic flexure
B

Figs 24-4A and B: Splenic ligaments and relations of the splenic flexure of the colon. These relations are important in left sided colectomy.

through the sigmoid colon through intersigmoid recess. Summit of the sigmoid is towards right iliac fossa. Pelvic mesocolon is inverted 'V' shaped; it has got two limbs—left limb is attached to brim of the left side pelvis; right limb is attached from apex to 3rd piece of the sacrum. Pelvic mesocolon carries superior rectal vessels; its apex is related to left ureter **(Figs 24-5A to C)**.

Rectosigmoid junction is actually not a precise point as it is variable; it is marked by a distinct flexure. If the lesion is below the promontory it is called as rectal; rectosigmoid is 15 cm above the anal verge on sigmoidoscopy.

Colon does not have mucosal villi; its longitudinal muscularis externa has three discrete bands (taeniae). Appendices epiploicae are fat appendages attached to the surface of the colon; it is the site of infarction, torsion and site for diverticulae formation. While removing these appendages they should not be pulled out to avoid injury to the vessel underneath.

Blood Supply

Arterial Supply

Ileocolic, right colic, and middle colic arteries which are branches of superior mesenteric artery supply the colon from caecum to splenic flexure. Left colic, sigmoid, superior rectal arteries which are branches of inferior mesenteric artery supply the descending and sigmoid colon. The anastomotic arcade formed between the branches of superior and inferior mesenteric arteries is called '*arc of Riolan*.'

Ileocolic, right colic, middle colic (branches of superior mesenteric artery) and left colic artery and sigmoid branches supply the colon. Marginal artery connects branches of superior mesenteric and inferior mesenteric arteries. Marginal artery may be absent in 2% of individuals. Right colic artery may be absent in 12%; middle colic in 4% cases. Right (8%) and middle colic arteries (6%) or both (0.5%) may be often multiple. Atherosclerosis of the inferior mesenteric artery makes marginal artery poorer and unsuitable for colonic conduit. There is no marginal vein on the right side colon and it is said that anastomotic leak in 25% of right sided colonic conduit substitute is due to venous congestion rather than arterial.

Superior mesenteric artery (SMA) (artery of midgut) arises from the front of the abdominal aorta behind the body of pancreas at L1 vertebral level 1 cm below the coeliac trunk; it runs in front of the uncinate process crossing the 3rd part of the duodenum entering the mesentery to run in between its two layers. It ends at right iliac fossa by anastomosing with branch of ileocolic artery. Posteriorly above the root of the mesentery it is related to aorta, left renal vein, uncinate process and 3rd part of the duodenum; in the root of the mesentery it crosses the IVC, right ureter, right psoas muscle. SMV is at its right side; it is surrounded by superior mesenteric plexus of nerves. *Towards right side* it gives inferior pancreaticoduodenal, middle colic, right colic and ileocolic arterial branches. Middle colic artery arises just below the pancreas running downwards and forwards in the transverse mesocolon; its right branch communicates with right colic artery and its left branch with left colic artery. Right colic artery arises from SMA or as a common trunk with either middle colic or ileocolic arteries. It runs towards the upper part of the ascending colon; its descending branch anastomose with ileocolic artery and its ascending branch with middle colic artery. Ileocolic artery arises from SMA running downwards and towards right dividing into superior branch which anastomose with right colic artery and inferior branch which anastomose with terminal branch of the SMA. Inferior branch gives ascending colic branch, anterior and posterior coecal branches, appendicular artery and an ileal branch (terminal part of the ileum). Jejunal and ileal branches of SMA arise from its left side (fifteen in number) runs between two layers of the mesentery supplying the jejunum and ileum except terminal part of the ileum which is supplied by the ileal branch of the ileocolic artery. Jejunal vasa recta are longer and less numerous; ileal vasa recta are shorter and more in number.

The marginal artery of the colon, also known as the *marginal artery of Drummond* (Sir David Drummond (1852-1932) an English physician), is an anastomotic branch connects the IMA and SMA. It is sometimes absent as an anatomical variant. The Marginal Artery of Drummond runs in the mesentery close to the bowel as part of the vascular arcade that connects the SMA and IMA. This artery is almost always present and its absence should be considered a variant.

The Arc of Riolan (Riolan's arcade, Haller's anastomosis, 1803), also known as the 'meandering mesenteric artery' or central anastomotic mesenteric artery, is another inconstant vascular arcade present in the colonic mesentery that connects the proximal middle colic artery with a branch of the left colic artery. This artery is found low in the mesentery, near the root. Rarely, it can arise from SMA **(Figs 24-6A to C)**.

Inferior mesenteric artery (artery of hindgut) (IMA) supplies colorectoanal region from left 1/3rd of the transverse colon to anal canal above the dentate line. IMA arises from front of the aorta 4 cm above the bifurcation of the aorta behind the 3rd part of the duodenum at L3



Measurements of sigmoid mesentery

Figs 24-5A to C: Relations and features of the sigmoid colon.


A
Marginal artery of Drummond's (Sudeck's)
Middle colic artery
SMA
Arc of Riolan
Principal LN
Intermediate LN
Epicolic LN
Right colic artery
Paracolic LN
Ileocolic artery
Sudeck's critical point
Superior rectal artery
Inferior mesenteric artery
B
Superior mesenteric artery
Inferior mesenteric artery
Colon
Griffith critical point
Middle colic artery
Marginal artery
Marginal artery of Drummond/ Sudeck
Right colic artery
Arc of Riolan (Haller)
Ileocolic artery
Left colic artery
Appendicular artery
Sigmoid artery
Ileal branches
Sudeck's critical point
Terminal ileum
C
SMA
Inferior branch
Ileocolic artery
Ascending colic branch
Anterior caecal branch
Posterior caecal branch
Ileal branch (for terminal ileum)
Appendicular artery

Figs 24-6A to C: Blood supply and lymphatics of the colon.

vertebral level. It descends downwards and left crossing the common iliac artery medial to the left ureter; in the sigmoid mesocolon it continues as superior rectal artery. *Left colic artery* is the 1st branch of IMA, runs upwards and left ends by dividing into ascending and descending branch. The ascending branch enters the transverse mesocolon and anastomoses with branch of middle colic artery. Descending branch anastomoses with 1st sigmoid artery. Left colic artery may be absent in 6% of cases. Sigmoid branches are 2-4 in number forms lowermost part of the marginal artery. Lowermost branch anastomose with superior rectal artery. *Sudeck's critical point* at the rectosigmoid junction is described as the point of origin of the last sigmoid arterial branch, originating from the inferior mesenteric artery (IMA). The Sudeck's critical point refers to a specific location in the arterial supply of the rectosigmoid junction, namely the origin of the last sigmoid arterial branch from the IMA. This arterial branch usually forms an anastomosis with a branch of the superior rectal artery. The anastomosis is small and often only singular. Sudeck's point has particular relevance in colorectal surgery and also forms a site of watershed susceptible to ischaemia. Superior rectal artery is the continuation of the IMA beyond the root of the sigmoid mesocolon. Opposite 3rd sacral vertebra it divides into right and left branches; each pierces the muscular coat of the rectum to supply rectum and anal canal communicating with middle and inferior rectal arteries. Right branch divides into anterior and posterior branches. Often a branch from proximal part of the left colic artery joins a branch from proximal middle colic artery to form arc of Riolan. IMA can be ligated and blood supply can be maintained through marginal artery (via SMA and through branches from internal iliac arteries). Marginal artery is weaker and less consistent in the splenic flexure and often absent in splenic flexure level and this point in splenic flexure is called as *Griffith critical point*.

Venous Drainage

Venous drainage occurs into superior mesenteric vein (which joins the splenic vein to form the portal vein) and inferior mesenteric vein (drains into the splenic vein). Venous drainage is similar to arterial supply. Marginal vein is often absent on the right side; but on left side marginal vein will be always present. So venous congestion can occur in right sided colon after surgery which may lead into venous infarction.

LYMPHATIC DRAINAGE

Mucosa contains no lymph channels, so mucosal cancers rarely metastasize. Nodes are *epicolic* (located in the colonic wall), *paracolic* (located along the inner margin), *intermediate* (located near the mesenteric vessels), *and principal* (located near main mesenteric vessels). Nodes situated along the main blood vessels like SMA, middle colic, right colic, ileocolic, IMA, left colic, sigmoid, superior rectal are called as proximal nodes; nodes along the next level branches are called as intermediate nodes, nodes in the colonic wall and its inner margin are called as distal nodes.

NERVE SUPPLY

Colonic motility is under control of autonomic nervous system; parasympathetic via vagi and pelvic nerves, sympathetic via superior and inferior mesenteric ganglia. The effect of meal on colonic activity is termed as *gastrocolic reflex*.

PRINCIPLES IN COLONIC SURGERY

Colonoscopy is essential in all colonic diseases prior to surgical intervention unless it is a surgical emergency. Proper preoperative staging using CT scan of abdomen and chest, endosonography is needed for staging. Carcinoembryonic antigen (CEA) is of no use for diagnosis; however, it is done to get a base line level so as to be utilised during follow up for comparison.

*Preoperative preparation (of the bowel)—Principle behind bowel preparation***—**Colon contains large amount of bacteria up to 10^9 /mL of faeces. Commonest anaerobe is bacteroides; commonest aerobe is *E Coli*; *Pseudomonas*, *Enterococcus*, *Proteus*, *Klebsiella*, *Streptococcus* are other organisms. Bowel preparation is done to clear this bacterial load to reduce postoperative complications. ***Methods used are****—Mechanical bowel preparation* using PEG or sodium phosphate**.** *Polyethylene glycol (PEG)* is a non-absorbed sodium sulphate solution, 2-3 litres of which is asked to drink by the patient along with plenty of additional fluids orally. It cleans the bowel by passing loose stool for 10-15 times in 12 hours. It acts by its hygroscopic action. *Side effects* are—nausea, vomiting, and abdominal cramps. Antiemetics are often needed. It is ideal in renal failure, ascites, cirrhosis, CCF. *Sodium phosphate* is an alternative to PEG as smaller volume is sufficient to take. But it causes electrolyte imbalance. Its efficacy is similar to PEG. But patient compliance and cost is better acceptable. It can cause hyponatraemia, hypokalaemia, hypocalcaemia and hypophosphataemia in case of renal dysfunction. In such patients, it is contraindicated. *Other methods*—(A) *Total gut irrigation* daily using 200 mL of *oral mannitol* or through nasogastric tube for 3 days prior to surgery; (B) *Bowel wash* daily for 3 days prior to surgery using 2 litres of normal saline (not water as it will cause water intoxication); it cleans entire large bowel; (C) Senna, castor oil, bisacodyl; (D) Repeated enemas. *PEG or sodium phosphate has taken over all this methods. Contraindications* for mechanical bowel preparation: Complete bowel obstruction and perforation. *Antibiotics parenteral and as bowel antiseptics, oral neomycin* (gentamycin, streptomycins were used in olden days) 1 gram, *erythromycin* 1 gram, is used 3 days prior to surgery. Alternatively *ciprofloxacin and metronidazole* are used. IV fluids should be given in addition to these patients to maintain hydration adequately. *IV antibiotics* given *4 hours before* making incision, reduces the incidence of sepsis (no clear evidence). Usually cephalosporins are given. ***Controversies—***There is doubt about the advantages of preoperative mechanical bowel preparation even though it practiced universally. Oral antibiotics used to reduce the bacterial load in the colon are also controversial. However, preoperative single dose parenteral antibiotic improves the result and reduces the sepsis.

Turnball no touch technique with ligation of pedicle at its origin prior to mobilising the colon and tumour reduces the chances of tumour spread. Avoiding breaching the colonic wall, negative proximal, distal and radial margins are absolute need. Intraoperative frozen section biopsy of resected margin should be taken. Lymphovascular clearance is a must in colectomies for carcinomas.

Controversies still exist about the duration of nasogastric tube and beginning of oral feeding. Proponents of late oral feeding after 7 days believe that colonic stomal tensile strength and ability to withstand disruptive force takes 7 days and so oral feeding started after 7 days. Initially oral liquid then gradually solid food is started. Proponents of early feeding believe once bowel sounds is heard and patient has passed flatus without abdominal distension, feeding can be started; it is also believed that by them that gradual feeding from oral liquid to solid is not necessary.

In colectomy for benign diseases initially colon is mobilized by opening the peritoneum along the paracolic gutter, and then vessels are ligated close to the bowel wall at its inner margin. There is no need to ligate vessels at its origin and no need to do lymphovascular clearance.

In *colonic perforation*—resection, creation of proximal stoma, closure of distal colon or creation of mucus fistula is better. Diversion may be loop ileostomy if perforation is in the right colon or proximal (right sided) colostomy if perforation is in left colon.

In colonic obstruction as general condition of the patient will not be good it is better to do resection and diversion.

Intestinal decompression can be done by doing a colotomy at the proximal site. On table colonic lavage as antegrade irrigation cleans the colon mechanically facilitating the one stage resection and primary anastomosis without diversion.

Meticulous anastomotic technique is important to avoid anastomotic dehiscence. Pulsatile arterial blood flow at the cut edge of the mesentery adjacent to the cut edge of the bowel is the deciding factor along with the bleeding from bowel cut edge and pink, soft and pliable bowel. Haematoma in the bowel wall, haematoma in the mesentery may reduce the blood supply. Single layer interrupted sutures using 3-0 silk is adequate. At every 3-5 mm sutures should be placed. Posterior layer knots are kept inside; anterior layer knots are placed outside. Two layers can be done with inner full thickness continuous or interrupted 3-0 vicryl sutures; outer interrupted seromuscular silk sutures. *Submucosa is strongest* layer and so bites should be taken through it during seromuscular sutures.

Different methods of anastomosis are used. ***Open method*** is commonly advocated. It can be single layer interrupted anastomosis or two layered anastomosis. ***Single layer*** has the advantages as it is easier, it maintains blood supply at the cut edges and prevents necrosis of the cut edges. Single layer bites can be *simple seromucosal full thickness sutures* or *mattress full thickness seromucosal* or *simple serosubmucosal sutures (mucosal bite is not taken here)* depending on the surgeons convenience and need of the patient. Whenever ***two layer anastomosis*** is done, inner continuous or interrupted full thickness sutures with outer seromuscular interrupted silk sutures are used. Usually 3-0 suture material is sufficient. Cut ends should be made of equal size by Cheatle's cut; occlusion clamps should be in place; initially bites are taken from mesenteric corner, antimesenteric corner and later bites are taken on either side. All suture bites should be ideally taken first and knots are tied later. Knots are placed inside in posterior layer and outside in anterior layer **(Figs 24-7 to 24-9)**.

In closed method crushing clamps are placed on each side of the bowel; *serosubmucosal interrupted bites* are taken posteriorly; once all posterior bites are taken knots are tied outside. Then anterior serosubmucosal bites are taken and knots are tied outside. Once all knots are tied then only crushing clamps are released. With thumb and finger crushed inner parts of the cut ends of the bowel are separated properly (which are inside the lumen) and surgeon should confirm that lumen is made patent. Closed method prevents contamination; it is not commonly practiced. Still there are surgeons who advocate this method.

At least 1 cm of the bowel cuff is cleared of the fat, mesentery and epiploic appendices. Leak commonly occurs on the mesenteric side of the stoma. Mesenteric defect should be closed using interrupted or continuous sutures by absorbable (vicryl) or nonabsorbable (silk) sutures. Tension free anastomosis should be achieved. Flexures whenever needed should be adequately mobilised to achieve free mobility of the stoma. Contamination should be avoided by using occlusion clamps, irrigation, and decompression. Fluid collection like blood, serous fluid should be avoided. Possible distal obstruction should be identified. It should be corrected otherwise it will cause anastomotic dehiscence. Patient who had radiotherapy earlier or if patient who is on steroids for long time needs special attention as stomal dehiscence and leak is very common. Omental wrap may be used around the anastomotic stoma.


Cut edge should be oblique devoid of fat (fat should be removed using scissor) for 1 cm from the cut edge
Cheatle's cut if needed should be given on the antimesenteric border
Pulsatile mesentery with bleeding cut edge is the most important factor
Occlusion clamps should be placed to avoid contamination
Final anastomosis — interrupted silk sutures

Fig. 24-7: Technique of colonic anastomosis.


Middle bite
Antimesenteric suture bite
A
Cut ends of the bowel ready for anastomosis
Full thickness seromucosal simple interrupted sutures — knots inside
Full thickness seromucosal mattress interrupted sutures — knots inside
Serosubmucosal simple interrupted sutures — knots inside
Open method single layer suturing technique different ways
B

Figs 24-8A and B: Suturing of the colon—different methods.



Fig. 24-9: Doyen's occlusion clamp is used during anastomosis as it is least traumatic.

Stapling is commonly used in colorectal surgery (Fig. 24-10)

Stoma (colostomy/enterostomy) when planned should be sited properly. End ileostomy should protrude 1.5 cm from the abdominal wall; end colostomy should protrude 1.0 cm from abdominal wall. Stoma care should be meticulously followed. Stoma closure in temporary stomas should be done only after 3 months not earlier; adequate time is needed to achieve stoma stability and develop proper nutritional and biochemical optimum in the body. In loop ileostomy, site should be 10 cm proximal to the ileocaecal valve so that closure will be easier later. Nowadays end ileostomy is also commonly used as temporary one as it is easier to construct and easier to close at a later period. In permanent ileostomy Kock's continent type is often done with a nipple valve which facilitates collection of ileal excretions. It needs a tube insertion into the continent pouch at regular intervals by patient himself to evacuate the content. Kock's continent avoids usage of the stoma appliances. But problem herein it needs re-surgery in up to 30% cases and complications are common. Permanent end ileostomy is needed in severe Crohn's disease where pouch is contraindicated or in ulcerative colitis wherein pouch has failed.


Stapled ends of the bowels are brought together
On the anti mesenteric border small area of stapled line is removed
Side-to-side stapling is done
Side-to-side stapling is completed
Opening in the ends are closed using one more stapling

Fig. 24-10: Stapling is also used for colonic anastomosis. For anterior resection circular stapler is used.

Ureter is very important structure which should be safeguarded on both sides. Stenting prior to surgery may be needed if obstruction is suspected or observed in imaging. On right side duodenum, SMV are also important.

Bowel wall oedema may trouble proper approximation. Interrupted sutures, stapler usage are helpful. Otherwise diversion should be done instead of forcing the sutures.

Laparoscopic colectomy has become popular and safer on both right and left. In left colectomy circular stapler makes anastomosis easier and precise.

CAECOPEXY

It is rarely done nowadays. It is used whenever caecum and ascending colon is mobile with higher chances of precipitating volvulus. It is done by fixing the caecum and ascending colon to the lateral abdominal wall. Bites should be taken from the taeniae of the caecum **(Fig. 24-11)**.

CAECOSTOMY

Caecostomy is often done in acute colonic conditions as diversion procedure after surgery distally like perforation closure and resection. It is useful in pseudo-obstruction. But it is not as popular as colostomy because it may not function adequately, may get displaced or blocked. But it is technically easier and usually done by doing appendicectomy and passing Malecot's tube through appendicular stump. Removal is easier without any surgical intervention. Foley's catheter no. 30 F can be used. Purse string suture is placed around the tube by taking seromuscular bites with 3-0 vicryl or silk suture. It is also fixed by 2-3 interrupted sutures taken between seromuscular part of the caecum very close to the tube and parietal peritoneum (abdominal wall).

It is often done along with other procedure during laparotomy. When only caecostomy is planned it is done through a oblique incision in right iliac fossa above the groin crease similar to Mc Burney's incision. Distended caecum is identified; an occlusion clamp is placed across the caecum; appendix removed with a purse string suture on the taeniae circumferentially. Appendix stump is not ligated; instead suction apparatus passed into that to suck the content to prevent spillage. No. 30 Foley's catheter is passed onto the caecum; purse string suture is ligated. Second purse string suture is placed. Appendicectomy should be performed even if caecostomy is done on the anterior part of the caecum through taenia.

Tip of the tube is directed toward hepatic flexure. Nonfunctioning, blockage, slippage, leak are the complications **(Figs 24-12A to D)**.


Taenia coli
Interrupted 2-0 or 3-0 silk or vicryl sutures
Abdominal wall
Lateral abdominal wall peritoneum

Fig. 24-11: Caecopexy technique.

COLOSTOMY

It is an artificial opening made in the colon to the exterior (skin) to divert faeces and flatus.

Types

1. ***Temporary:*** Is done in conditions wherein diversion is required to facilitate healing distally in the rectum or distal colon. And this is closed once the purpose is over. Site of temporary colostomy is usually right hypochondrium and left iliac fossa.
2. ***Permanent*** colostomy is always *end/terminal colostomy* placed in left iliac fossa, 6 cm above and medial to the anterior superior iliac spine.

Colostomy Can be

Diversion colostomy: It is done when there is breach in bowel wall, trauma, destruction, sphincter injuries, Crohn's, carcinoma rectosigmoid. It is usually brought out as an end colostomy with a mucus fistula or with a Hartmann's resection. It can be at sigmoid, descending and transverse colon. ***Decompression colostomy:*** It is done for obstructive lesions in rectosigmoid, toxic megacolon. Types—(1) *Blow hole* procedure is done as a single or multiple small stomas onto the skin to decompress colon in acutely ill patients with massively dilated or impending perforation of colon. Problems



Only caecostomy can be done through a separate incision in the RIF; appendicectomy is done; double purse string suture are placed; Foley's catheter no. 30 is passed; fixed to the abdominal wall

Fixing the tube to the abdominal wall

Caecostomy can be done through a separate stab incision in the caecum; here appendicectomy stump is suture ligated or it can be done through appendicectomy stump also

Figs 24-12A to D: Caecostomy technique.

are—remaining possible ischaemic parts of the colon is not identified risking perforation; peristomal skin complications and mucosal prolapse is common. (2) *Tube caecostomy*—It is technically easier without much complications; but tube getting blocked limits its use regularly. (3) *Loop transverse colostomy*—It serves as decompressing and diverting long stoma without getting blocked. It is done only in mobile colon. *Irrigation colostomy:* It avoids need for appliance wear; reduces the passage of uncontrolled gas with less leak of stools. But it is time consuming with chance of water intoxication due to excess water absorption during irrigation.

Colostomy Can be

Loop colostomy *or double barrelled colostomy or* ***Devine's divided double-barrel colostomy*** (wherein there is a gap of skin between the two openings of colostomy which prevents spillage into the distal loop).

Loop colostomy is done temporarily to divert the stool. It is presently done to defunction distal anastomosis or in high fistulas or perianal traumas. It can be done at sigmoid colon at the junction of the sigmoid and descending colon as descending colon is fixed it, prevents colostomy prolapse. It can also be done more proximally at transverse colon in right hypochondrium. It is easier to construct. But prolapse is much more with colostomy than ileostomy; marginal artery may get damaged causing problematic eventual closure. Double barrel colostomy was done in olden days in sigmoid volvulus as Paul Mikulicz operation wherein a spur was created between two limbs at antimesenteric border.

Indications

Temporary: Congenital megacolon. ***Permanent:*** AP-Resection; anorectal malformations; carcinoma anal canal; sigmoid volvulus after Hartmann's operation; perforation of left sided colon; left sided colonic growth; high anal fistula; trauma to left sided growth **(Figs 24-13 to 24-15)**.

Technique

Loop colostomy

It is ideally done under general anaesthesia; but can be done under spinal or local anaesthesia. It is done along with laparotomy for



Figs 24-13A to D: Types of Colostomy. (A) Temporary colostomy, (B) Loop colostomy, (C) Devine's double barrel colostomy, (D) Permanent colostomy.



Fig. 24-14: Different types of stomas used in colostomy.



Fig. 24-15: Midline incision is used for resection. Incision in the right hypochondrium is used for loop colostomy (temporary). Permanent end colostomy is done after abdominoperineal resection (APR); here colostomy is sited at left iliac fossa.

definitive procedure or only loop colostomy at time and definitive procedure is done at a later period **(Fig. 24-16)**.

Incision is in the right hypochondrium midway between umbilicus and right costal margin, horizontally placed of about 6 cm in length, over the right rectus muscle with its right end ends just lateral to the lateral margin of right rectus abdominis muscle. Skin, two layers of superficial fascia and anterior rectus sheath is incised in the line of the skin incision. Rectus muscle is split vertically or horizontally cut; posterior rectus sheath and peritoneum are opened. Transverse colon is pulled out; omentum is detached from the colon for sufficient length—6 cm. Transverse mesocolon very close to the colonic wall is opened (window is created) in avascular plane and glass rod or stiff silastic tube/drain tube of 18 French size is passed across (which is usually removed in 8-10 days). Glass rod prevents retraction keeping colocutaneous suture line intact. But it is not mandatory to place a rod like this always; it is useful in obese patients. Glass rod often is brought out on either side by a separate stab incision which facilitated proper placement of sutures between colonic edge and skin. Colon is traditionally opened longitudinally along the taenia extending to both limbs of the loop. It is also practiced to open the colon horizontally which causes less damage to blood vessels. Both ways are accepted. After opening it is often practiced that few interrupted 2 zero vicryl sutures are placed between rectus sheath and seromuscular part of the colon away from the cut edge site. Usually 6 such sutures are placed. But it is again not mandatory to place such sutures in temporary colostomy. Interrupted sutures are placed between skin, subcutaneous and full thickness colonic cut edge. Many people use only subcuticular part of the skin for suturing instead of entire skin. Colostomy is ready for function. Stoma appliance is placed. Stoma should protrude outward at least 1-3 cm beyond skin margin **(Fig. 24-17)**.

Prasad end loop colostomy is often done along with laparotomy resection. Colostomy site is transected using stapler; proximal part is brought out through already created colostomy opening and is matured by releasing the stapler line; distal stapled colon is brought out adjacent to proximal loop. Proximal cut edge is sutured to skin using interrupted skin sutures. Distal loop stapled line is removed; it is partly sutured to skin; its inner part which is adjacent to proximal loop is anastomosed to it as side to side to create a modified loop colostomy.

End or Terminal Colostomy

End or terminal colostomy is done after abdominoperineal resection. It is permanent one. End colostomy site should be marked properly and a circular disc of skin is removed. Many do skin excision by holding the skin with a toothed forceps or Allis forceps and excising an elliptical skin but it is actually inadequate but accepted. Similarly same sized superficial fascia and rectus sheath is excised at corresponding level. Rectus muscle is split and peritoneum is incised. Two fingers should be passed through the wound without any difficulties. End of the cut colon is brought out by passing a Babcock's forceps inside through the opening for about 5 cm outside. If possible when colon is intraperitoneal lateral space between mesocolon and abdominal wall is closed using interrupted silk sutures. It prevents herniation. Otherwise colon end itself can be made extraperitoneal and brought out. One should ensure that there is no tension and good blood supply at the end of the colon. Few interrupted vicryl sutures may be placed between rectus sheath and seromuscular colon 1 cm proximal to the colon end. Interrupted skin sutures are placed between colonic full thickness edge and skin with subcutaneous fat. Many people take bites from seromuscular part of the colon avoiding the mucosa but it is practically not necessary. Even fixing to the rectus sheath is not mandatory even though commonly practiced.

When stapler is used for resection of the colon, stapler end is brought out and then later stapler line is excised. Other option is maturation is done at a later period postoperatively. But nowadays preferred one is doing maturation in the operation table only after closure of the main laparotomy wound.



Right hypochondrium horizontal incision 6 cm length over rectus muscle upper 2/3rd to middle1/3rd supraumbilical area or middle of the line between umbilicus to right costal margin

incision can be along with a laparotomy procedure incision — midline

Skin, superficial fascia are incised anterior rectus sheath is exposed

Horizontal incision on the anterior rectus sheath

Rectus muscle is exposed using retractors on both sides

Rectus muscle is either split vertically or cut horizontally and retracted

Transverse colon is brought out of the wound with visible taenia and mesocolon

Window opening on the mesocolon

Glass rod or silastic tube of 18 F size is passed under the mesocolon; it is not mandatory but usually done

Glass rod or tube/drain tube can be brought out through two separate skin stab wounds on both sides

Longitudinal incision on the taenia of 6 cm length is made

Transverse incision on the summit of the loop can also be made

Fascial suturing between rectus sheath and proximal colonic can be taken

Final interrupted silk sutures between colon edge to skin including subcutaneous fat

Fig. 24-16: Technique of loop colostomy.


Loop colostomy site
at right hypochondrium
A window is created in the tr
mesocolon through which tube
is passed
Taeniae
Taenia at transverse colon is
opened longitudinally to expose
both proximal and distal lumens
adequately
Protruded posterior wall
of the transverse colon
Both lumens proximal and distal are felt
Edge of the colon is sutured to skin
as full thickness interrupted skin sutures

Fig. 24-17: Loop colostomy is usually done in right hypochondrium. It is a temporary colostomy.

Complications of Colostomy

Prolapse of mucosa (prolapse of distal loop mucosa is common)—commonest complication; retraction; necrosis; stenosis; herniation; bleeding; diarrhoea; enteritis; skin excoriation. Necrosis of stoma can be just mucosal or full thickness.

Mucosal necrosis is treated conservatively. Full thickness necrosis needs reexploration and creation of new stoma.

Colostomy prolapse is common in loop than in end. It is initially treated conservatively; if troublesome then conversion into end colostomy and mucus fistula is safer. Mucus fistula is created at a separate opening.

Parastomal hernia is common in end colostomy. It is herniation of intestine on the side of bowel stoma—ileostomy/colostomy/other stomas. Incidence is 8%. *Classification (Devlin's)*: (1) Subcutaneous—Intestine herniates along the side of stoma to reach subcutaneous plane—commonest. (2) Interstitial—along the side of stoma intestine herniates into intermuscular plane. (3) Intrastomal – Bowel herniates between emerging and everted parts of the stoma. (4) Parastomal—Herniation occurs between the layers of the prolapsed stoma. Parastomal hernia can cause obstruction and strangulation. *Features:* Pain, features of obstruction, stomal malfunction, swelling which is tender, toxicity. If it is distressing it should be treated. Local repair with or without mesh can be done; otherwise closure of the stomal site with hernial repair using a mesh and redoing the colostomy at different location is the only choice. Mesh may be placed intraperitoneally or extraperitoneally. Rectus sheath which is closed often is supported with a local large Leslie skin flap.

Infection (enteritis / colitis), colostomy separation, skin excoriation, social problems, appliance problems are often difficult to manage **(Fig. 24-18)**.

Colostomy Care

It is similar to stoma care. Initially stoma bag should be transparent as content is liquid stool but later it can be opaque. Regular consultation with stoma therapist; care of the skin; training for managing colostomy, its care to prevent leak, odour, and discomfort. Educating the patient regarding the proper usage of colostomy bags and proper care of the colostomy is very essential.



Fig. 24-18: Colostomy site recurrence of the carcinoma who has earlier undergone abdominoperineal resection.

CLOSURE OF COLOSTOMY

Criteria for temporary colostomy closure:

Integrity of distal colon should be normal and adequate; anorectal sphincter should be normal. Cause for construction of colostomy is cured completely without any suspicion of recurrence of same disease distally. When temporary colostomy is done, it is closed usually after 3 months. Closure of colostomy is done after proper bowel preparation, ideally under general anaesthesia. Colonoscopy is a must just prior to colostomy closure to confirm that distal colon is normal and without any obstruction and devoid of any disease.

Types of Colostomy Closure

Two types of closure are present - Extraperitoneal and intraperitoneal type. *Now intraperitoneal closure is done.*

Earlier extraperitoneal closure was done in loop colostomy by placing a spur in between and closing the antimesenteric part of the colon. It prevents the peritoneal contamination. But inadequate closure, leak, adhesions are the problems.

Intraperitoneal closure—commonly advocated technique now. It is done by placing series of 6-8 silk sutures around the skin margin to give traction while dissecting, separating and mobilising the colon using circumferential incision over the margin with 2 mm skin edge. Incision is deepened to enter the peritoneum and pull out the colostomy stoma. Adequate mobilisation is essential to prevent tension over the anastomotic site. Part adjacent to the skin is resected and anastomosed using silk/vicryl. Two layer anastomosis using interrupted sutures is usually practiced. If there is an unhealthy edge then it is better to mobilise the hepatic flexure completely and do a small colonic segment resection and anastomosis. Sutured bowel is placed into the peritoneal cavity. Drain is placed into the peritoneal cavity. Abdomen closed in layers.

Proper postoperative care is important. Patient should perform anal sphincter exercises to prevent sphincter atrophy and to maintain sphincter tone.

Complications of Colostomy Closure

Breakdown of anastomotic site and faecal fistula is the commonest complication; but it usually subsides unless there is distal obstruction. Distal anastomotic abscess formation, wound infection, wound dehiscence and later incisional hernia can develop.

TREATMENT FOR DIVERTICULAR DISEASE OF SIGMOID/COLON

Medical Treatment

High fibre diet; antibiotics; bulk purgatives; avoid constipation; regular follow-up of the progress of disease and onset of complications.

Abscess can be drained by CT guided aspiration or percutaneous drainage tube. *Guided aspiration* of the abscess is sufficient if abscess is small. Proper antibiotics are needed.

In acute stages, conservative treatment like bowel rest, antispasmodics, antibiotics are advised **(Fig. 24-19)**.


Serosa
Muscle layer
Mucosa
Acquired diverticula
-Common
-Sigmoid colon
-Only mucosal protrusion
Diverticula
Serosa
Muscle layer
Mucosa
Muscle layer
Serosa
Congenital diverticula
-All layers with muscle layer
-Caecum/ascending colon
-Rare

Fig. 24-19: Colonic diverticula – diagram.

Indications for Surgery

Recurrent diverticulitis; diverticulitis with complications.

Surgery required is—*Resection of sigmoid colon and anastomosis (colorectal). Laparoscopic sigmoid resection can also be done* **(Fig. 24-20)**.

If colon is loaded with faecal matter, initially a transverse colostomy is done. Then resection and anastomosis; later colostomy closure is done as a staged procedure **(Fig. 24-21)**.

In case of perforation, proximal colostomy and exteriorization of the affected bowel with later resection and anastomosis is done as it has high mortality **(Fig. 24-22)**.


Resection and primary anastomosis
Part resected

Fig. 24-20: Resection and primary anastomosis can be done in sigmoid diverticula after proper bowel preparation electively.

Occasionally, Hartmann's procedure (combination of sigmoidectomy, end colostomy and closure of rectal stump) is better and life saving **(Fig. 24-23)**.

Fistulas are treated by resection of the diseased bowel and closure of the fistula along with diversion procedures like colostomy, cystostomy, ureterostomy.


Diversion loop colostomy
Resection and primary anastomosis
Part resected

Fig. 24-21: Resection of sigmoid colon for sigmoid diverticula with primary anastomosis and defunctioning diversion colostomy.


Resection
End colostomy
Mucus fistula
Part resected

Fig. 24-22: Resection and formation of end colostomy and mucus fistula for acute sigmoid diverticulitis.



Fig. 24-23: Hartmanns operation for acute diverticulitis with sepsis/perforation/peritonitis. Here, after resection proximal colon is exteriorised as end colostomy. Distal rectal stump is closed.

In certain cases of diverticulosis, a longitudinal incision through the taenia and muscular layer without opening the mucosa is sufficient (like Heller's/Ramstedt's myotomy)— *Reilly's sigmoid myotomy*.

Note: It is basically **a benign condition**, therefore the prognosis is good. High fibre diet is advised. Complications like *perforations, fistulas are dangerous and life-threatening*. Right sided diverticulum in the caecum and ascending colon is usually solitary and congenital.

Myotomy

- Heller's myotomy—achalasia cardia
- Ramstedt's myotomy—congenital pyloric stenosis
- Reilly's myotomy—diverticulosis

TREATMENT FOR ULCERATIVE COLITIS

General: Correction of anaemia; fluid and electrolyte supplementation; nutrition (high protein, carbohydrate, vitamin, but low fat diet), TPN; sedatives and tranquillisers; psychological counselling.

Drugs: In active disease, drugs are used to *induce remission*. Later drugs also should be given for *maintenance* of remission and to prevent relapses. Salazopyrine/sulphasalazine splits into 5 amino-salicylic acid and sulphapyridine in colon. It is used as *first line therapy*. Its dose is 2-4 gm/day. It is mainly used to induce remission. It suppresses PGE1 and PGE2 to reduce the inflammation, inhibits proteolytic enzymes and also causes immunosuppression. 5 ASA is the most active ingredient. Side effects are skin rashes, bone marrow suppression, folic acid deficiency, haemolysis in glucose-6-phosphate dehydrogenase deficiency patients, temporary fertility problems in men. 5 ASA (Mesalamine) is also used in active disease as *first line therapy*. It is used with an azo bond to prevent its absorption in small bowel. Its induction of remission is same as sulphasalazine. Idiosyncrasy and temporary infertility is not present in mesalamine. Its *oral* dose is 2-4 gm/day. It is also used as *retention enema* which is better than steroid enema in left sided ulcerative colitis/proctitis. But mesalamine enema (4 gm in 100 ml saline) is costly. Enema is combined with oral mesalamine or oral steroid in acute cases. Mesalamine 500 mg s*uppository* is also used in BID doses. Daily oral (1.6 gm) and topical 4 gm enema, twice weekly is often used for maintenance therapy. Headache, dyspepsia and myocarditis are the complications. Steroids are used in cases where salazopyrine fail to induce remission. It is a drug for *refractory cases*. Oral prednisolone 60 mg/day tapering in 4 weeks is the dose. Intravenous hydrocortisone 100 mg 8th hourly is used in acute cases. 100 mg hydrocortisone enema/40 mg methylprednisolone enema (steroid retention enema) are used for 2 weeks in acute active diseases. Most patients with moderate to severe disease need steroid therapy. *Budesonide* is a newer steroid hydrocortisone analogue is also equally effective with lesser side effects and less adrenal suppression. Immunomodulators are used often to induce remission and for maintenance. Azathioprine and 6-mercaptopurine are used. They act at DNA level (purine ribonucleotide) and inhibit lymphocyte function (of T cells). But this action is slow. Cyclosporin is used in refractory, fulminant severe ulcerative colitis as a reserve drug. Dose is 4 mg/kg/day IV. Mebeverine HCl and Tegaserod (6 mg) are the other drugs used in ulcerative colitis. Other measures are using sucralfate, short chain fatty acids, probiotics, anti-diarrhoeal drugs (diphenoxylate, loperamide, codeine), avoiding milk products, fibre, fruits. Anti-tumour necrosis factor alpha – *Infliximab* is also used selectively (in some studies). It is given intravenously at interval of 6 weeks. It shows 70% remission in ulcerative colitis. Newer drugs with a targeted delivery into the colon is used nowadays. *For example* Olsalazine (azobond); Balsalazine (4 aminobenzoyl carrier).

Indications for Surgery—30% Cases

Intractability—commonest indication; toxic dilatation; perforation; haemorrhage; risk of malignant transformation, dysplasia (DALM); onset at early age; chronic invalidism; progressive disease with stricture, abscess, fistulae; steroid dependency, persistent active disease; malignancy; severe extraintestinal manifestations; growth retardation in children.

Toxic megacolon: It is 1.5% in incidence; common in transverse colon; colon more than 6.5 cm in diametre in transverse colon and more than 10 cm in caecum is likely to be toxic; colon is like wet blotting paper; commonly seen in ulcerative colitis; can occur in bacterial colitis, pseudomembranous colitis, fulminant amoebic colitis; may be precipitated by antidiarrhoeal drugs. It is treated by—IV fluids, blood transfusion, antibiotics, steroids; it can be life threatening; plain X-ray abdomen is very useful; emergency surgery, colectomy, colostomy/ileostomy may be required. In olden days *blow hole procedure* was advocated for toxic megacolon, may be still useful in severe cases. Skin level transverse colostomy, sigmoid colostomy and a loop ileostomy is done to decompress entire small and large bowel. After many months (6-8 months) once patient recovers from acute illness, total proctocolectomy with ileal pouch anal anastomosis is done.

Surgeries

Total proctocolectomy with ileo-anal anastomosis with pouches as reservoir ("J', 'S', or "W' pouches). It is called as *restorative proctocolectomy with ileal pouch anal anastomosis (IPAA)*. It is *ideal curative procedure* for ulcerative colitis. Anal sphincter complex is preserved. An 30 cm ileal pouch is created either hand sewn or with stapler. Created ileal pouch reservoir is anastomosed just above the anal canal using end-to-end stapler. Diametre of the pouch should be twice the diametre of the ileum. Obstruction (25%), diarrhoea, *pouchitis (25%)*, leak, sepsis, incontinence are the complications.

Total proctocolectomy with ileostomy (permanent, continent Kock's ileostomy, with one way valve is done). It is used at present only *in revision surgery* when needed after restorative proctocolectomy.

Total proctocolectomy with end non-continent ileostomy was the earliest operation done for ulcerative colitis. It is now *reserved only* for ulcerative colitis complicated with carcinoma of rectum. *Ileostomy site* should be marked in standing and sitting position. Stoma should be within the right rectus abdominis muscle at the summit of infraumbilical fat, away from midline incision, bony prominences and umbilicus.

Total colectomy with ileorectal anastomosis can be done. Proper follow up at regular intervals by regular sigmoidoscopic evaluation should be done as rectum is also diseased and vulnerable for complications. It is *not commonly* practiced now.

Total colectomy with rectal mucosectomy and anastomosis above the dentate line on posterior aspect is also occasionally used.

TREATMENT CONCEPT IN CARCINOMA COLON

Mainly Surgical

Right Sided Early Growth

Right radical hemicolectomy with ileo transverse anastomosis is done. Structures removed are terminal 6 -15 cm of ileum, caecum and appendix, ascending colon, 1/3rd of transverse colon, lymph nodes (epicolic, paracolic, intermediate, principal).

In inoperable right sided growth, *ileo-transverse anastomosis*is done as a by-pass procedure.

In transverse colon and hepatic flexure growth—*An extended right hemicolectomy* is the procedure done for transverse colon growth which includes division of right colic, middle colic arteries at their origin, with removal of terminal 6 cm ileum, ascending and transverse colon; anastomosing terminal ileum and proximal part of the descending colon—*ileocolic*. Alternatively, in mid transverse colon growth only transverse colon with both flexures can be removed; anastomosing cut ends of ascending and descending colon—*colocolic*.

Left Sided Early Growth

Left radical hemicolectomy is done, where in left ½ of transverse colon and descending colon is removed along with lymph nodes.

Left sided stenosing type of growth can present with acute intestinal obstruction, in which case initially colostomy is done. Later, after 3-6 weeks, following proper preparation, required formal procedure is done, followed by colostomy closure after 8 weeks (*3 stage operation*). Presently it is done only in critically ill patient; otherwise it is proved that it is not necessary to do 3 stage procedures; instead primarily resection and anastomosis with a proximal diversion colostomy is an effective procedure.

Often growth in the transverse or left sided colon, which is stenosing or obstructive type, can cause *closed loop obstruction* because of the competent ileocaecal valve. As a result, pressure increases in the caecum eventually leading to its perforation. Perforation can also occur occasionally at the site of tumour. They need *emergency intervention*—caecostomy or colostomy, or ileostomy with resection and anastomosis. If severe peritonitis sets in, it may be life-threatening.

Left sided colon growth *with obstruction* can be treated with resection of tumour, saline lavage and cleaning the rest of the colon by passing a catheter through the appendix into the caecum followed by primary anastomosis thus avoiding colostomy.

Severely *obstructed sigmoid growths* are often treated alternatively by tumour resection with removal of entire proximal colon and continuity is maintained with ileo sigmoid/ileo rectal anastomosis. It also avoids diversion.

During exploration, presence of any synchronous growths has to be looked for. Now it is found that carcinoma colon can be *associated with tuberculosis or lymphoma of colon*. So this association is also looked for.

In acute left sided growths, *trans anal self-expanding metal stents* can be used instead of defunctioning colostomy.

Turnball's 'No touch technique': Here the vessels are ligated at its origin, at the beginning, in order to prevent the tumour spread—due to tumour handling. This medial to lateral oncological approach could be ideal in carcinomas. In laparoscopic colectomies, this medial to lateral approach is better as colon will be fixed laterally makeing dissection medially easier.

Abdominal total colectomy with ileorectal anastomosis is done if there are multiple primary tumours or in HNPCC. Significant chronic diarrhoea is the problem due to defective water absorption.

In Liver Secondaries

*In solitary liver secondary, s*egmental hepatic resection is useful.

In case of multiple secondaries confined to one lobe of the liver, hemihepatectomy can be tried.

Metastasectomy—it is done in one secondary/one lobe secondaries/less than 3 metastases in both lobes/without any extrahepatic spread.

A 'Second Look Operation'

It is most often helpful in carcinoma of colon, to resect the residual or recurrent tumours (*Owen Wangensteen's Second look surgery). Relaparotomy is done after a stipulated period at regular intervals once colectomy is done for carcinoma.*

Synchronous Growths

If there are synchronous growths or growth with other area having multiple potential polyps, then total *colectomy with colorectal* anastomosis is done.

Recurrent Tumour

Recurrent tumour should be treated by re-exploration and resection with adjuvant chemotherapy of different regime.

Laparoscopic Approach

Laparoscopic evaluation and resection is becoming popular. Laparoscopic assisted colonic resection is also done [*Hand assisted laparoscopic surgery (HALS)*].

Note

- Caecum and ascending colon—right radical hemicolectomy (terminal ileum to mid-transverse colon); hepatic flexure and transverse colon—extended right radical hemicolectomy (terminal ileum to proximal descending colon); splenic flexure extended left radical hemicolectomy (hepatic flexure to rectosigmoid); descending colon and sigmoid—left radical hemicolectomy (splenic flexure to rectosigmoid).
- Minimum 5 cm margin clearance at colonic side/sides is needed; 6 cm terminal ileum clearance is sufficient in case of right sided growth.
- Duodenum, ureter, IVC, superior mesenteric vein should be taken care of during dissection in right hemicolectomy; spleen, stomach, tail of the pancreas should be taken care of in left hemicolectomy.
- It is ideal to mobilize both flexures adequately in all colonic surgeries to reduce the anastomotic tension.
- Bleeding at edges of anastomotic site should be adequate; in emergency obstructive situation, better to do temporary covering colostomy or ileostomy to prevent anastomotic leak whenever necessary.
- On table and postoperative hypoxia and hypotension should be prevented to minimize anastomotic leak.
- Preoperative mechanical bowel preparation is important in elective colonic resection using polyethylene glycol / mannitol, oral bowel antiseptics like neomycin and metronidaziole.
- Infiltration into adjacent local structures is not a contraindication for surgical resection.
- At least 12 nodes should be examined during histology after resection.
- Blood transfusion before or during surgery for colonic cancer may alter the immunological aspect of the colonic cancer and may increase the recurrence rate and so may alter the prognosis. It is presently not very well-proved. Reason thought is—Blood transfusion raises the level of suppressor T cells leading into immunosuppression. So autologous blood transfusion is better when in needed.
- Proper preoperative bowel preparation by mannitol/polyethylene glycolhypertonic saline/bowel wash/ bowel antiseptics (neomycin or gentamycin or streptomycin and metronidazole orally).
- Antibiotic prophylaxis; DVT prophylaxis by crepe bandage or stockings bandage, heparin or low molecular weight heparin; pulmonary function tests and pulmonary exercise preoperatively as well as postoperatively; urinary catheterisation, nasogastric tube placement—are always needed.
- Postoperative proper care with fluid, electrolyte, drain care, early mobilization, monitoring.
- Complications of surgery are leak (fecal fistula), bleeding, infection like intraperitoneal/pelvic abscess, respiratory problems, DVT, wound infection, burst abdomen.

RESECTION OF THE COLON

Colonic resection is a common condition surgeons will come across. It may be for benign diseases, acute conditions like obstruction, volvulus or perforation or diseases like severe ulcerative colitis, polyps of different type and cause, carcinoma at different levels. Technically even though colon resection is easier than biliopancreatic surgeries, to achieve an optimum result with least complications proper preoperative, operative and postoperative care should be undertaken.

Principles

Prior evaluation of the disease, extent, type of resection needed, and comorbid status should be evaluated by imaging, colonoscopy, biochemical and nutritional assessment, cardiac and respiratory evaluation. CT imaging is essential.

Need for diversion in obstruction and other acute conditions should be thought of. Diversion may be colostomy or ileostomy depending on the location of the pathology. Stoma appliances, stoma care should be planned.

Tumour may be closer to ureter or invading it; such situation warrants for ureteric stenting prior to surgery. Stent may be removed within 3 months.

Bowel preparation is routinely done with methods which surgeons are familiar. Bowel antiseptics, perioperative antibiotics are used. Nasogastric tube and urinary catheterization is needed.

Epidural with General Anaesthesia is Commonly Used

Different types of colectomies are performed depending on the need; these terminologies are used based on the extent of the colon resected. In benign conditions vascular ligations are done very close the colonic wall and conventional colectomies are done with colon being mobilized first from paracolic gutter inwards then vessel ligation followed by anastomosis. In carcinomas, resection begins with vascular ligation at its origin to achieve lymphovascular clearance. After ligation of the branch vessels at its origin then only colon mobilization is done from paracolic gutter to complete the resection – this is termed as radical resection of the colon. Hence usually *conventional colectomies* done for benign conditions with colonic mobilisation first; whereas in radical colectomies done for malignancies involves lymphovascular ligation first at the origin of the branch vessels. But one should remember that radical colectomies can be achieved through conventional approach after colon is mobilised vessels are ligated at its origin to clear nodes. Ligation of vessels at its origin is not done in colectomies for benign diseases.

Different types of colectomies are shown in the diagram—they are—ileocaecal resection; segmental ascending colon resection; right hemicolectomy; extended right hemicolectomy, transverse colectomy, left sided hemicolectomy; extended left sided hemicolectomy; sigmoid colectomy; subtotal colectomy; total colectomy; total proctocolectomy **(Figs 24-24 to 24-29)**.

RIGHT COLECTOMY

Conventional Right Hemicolectomy

Lengthy midline incision is used. Proper exploration is done – gall bladder, liver, pancreas, remaining parts of the bowel, pelvis, nodes should be assessed. Usually conventional right hemicolectomy is done for benign lesions. So lymph node clearance is not needed. But it is very well accepted that conventional colectomy can be used for malignancies but vessels should be ligated at its origin and lymphovascular clearance should be adequate and also gentle dissection and handling of the colon and tumour is needed. Self retaining retractor is placed. Surgeon can stand either on right side or on left side. Many prefer to stand on left side. Caecum, terminal ileum and ascending colon are gently retracted anteromedially. Posterolateral peritoneum (*Toldt's line*) gets stretched and is incised using cautery or scissor. As plane is natural and avascular gentle finger dissection using index finger will create a space underneath the peritoneum up to the hepatic flexure and peritoneum is incised to expose the psoas major muscle. If surgeon is holding the bowel assistant can incise the peritoneum otherwise assistant is made to hold the bowel. Ureter, gonadal vessels are identified and safeguarded. Near hepatic flexure duodenum is identified which is dissected and left in the retroperitoneum. Posteriorly Gerota's fascia with kidney will be separated; Gerota's fascia is separated by dividing renocolic ligament. Gerota's should not be opened. Junction of the ascending colon and hepatic flexure is adherent to the gallbladder and should be released using scissor and finger dissection (division of *hepatocolic ligament*). Greater omentum is ligated and divided to achieve further mobilisation. In benign lesions omentum can be divided close to the colon at avascular plane. While mobilising hepatic flexure and right half of the transverse colon, mesocolon is related to SMV, middle colic vessels. Veins are friable here and gentle careful dissection under vision is needed to avoid unnecessary troublesome bleeding. If bleeding occurs it is better to keep a mop for a while and the bleeder is identified and caught with a haemostat and transfixation ligation is done using 3-0 vicryl or polypropylene. Firm pressure for few minutes controls most of the bleeding here. SMV is identified and care should be taken not



Ileocaecal local resection for benign condition

Hepatic flexure needs mobilisation

Resection of ascending colon
– local / segmental resection
– for benign condition

Hepatic flexure needs mobilisation

Right hemicolectomy
Splenic flexure needs mobilisation

Extended right hemicolectomy
Splenic flexure needs mobilisation

Transverse colectomy

Left hemicolectmy
– Here lower extent of resection is either proximal or distal to sigmoid arteries

Needs hepatic flexure mobilisation

Extended left hemicolectmy
– Here lower extent of resection is either proximal or distal to sigmoid arteries
– Proximal extent is proximal to the left branch of the middle colic artery

Needs hepatic flexure mobilisation

Sigmoid colectomy
– Local sigmoid resection
– Done for benign diseases like sigmoid diverticulae

Subtotal colectomy

Total colectomy

Total proctocolectomy

Fig. 24-24: Different types of colectomies with extents of resection.



Fig. 24-25: Extended right hemicolectomy.



Fig. 24-26: Finochette retractor gives good exposure of the field keeping assistant's hands free for assisting.

to injure it. Peritoneum incision on the mesentery of the terminal 15 cm ileum is completed and that part of the ileum is also mobilised. Occlusion clamps are placed at the line of resection. Clamps are placed on the ileum obliquely; clamps should not extend onto the mesentery (only bowel part should be clamped). Another occlusion clamp is placed on the right 1/3rd to ½ of the transverse colon. Once right colon unit is completely mobilised, vessels are ligated. In benign diseases vessels are ligated very close to the bowel without intervening the main branch vessels. Often there will be fat in the mesentery which obviates the proper ligation; it is better to take short width of the mesentery of 1 cm for ligation; proximal double ligation or transfixation is needed and is safer. Vessels are identified through transillumination. In malignancy main vessels are ligated at its origin. Prior to ligation of the vessels one should confirm that ureter, gonadals, duodenum are kept away from the site of resection. Once mesenteric ligation is done within the area between the occlusion clamps; crushing or Kocher's clamps are applied on the specimen side. Ileum is cut using no. 15 blade from inside mesenteric point to outside antimesenteric part; similarly colon is cut between clamps to retrieve the specimen. Occlusion clamps should be placed oblique outwards to maintain the blood supply of the colon at its antimesenteric part. In practice occlusion clamps are placed 10 mm from the cut edges of the ileum and transverse colon; but ideally clamps should be placed 10 cm from the cut edges even though it is not practiced by most of the surgeons. Bleeding from the cut edge should be confirmed as well as pulsatile mesenteric edge. Fat should be removed from the colon for 1 cm from the cut edges to prevent fat interposition during anastomosis. For anastomosis, single layer interrupted full thickness 3-0 silk sutures or two layered interrupted full thickness vicryl sutures and outer interrupted seromuscular 3-0 silk sutures can be used. Cheatle's cut may be needed on the antimesenteric border of the ileum. Mesenteric rent is closed using continuous or interrupted 3-0 vicryl or silk sutures.

Conventional right hemicolectomy

Midline laparotomy
↓
Exploration
↓
Mobilisation of the colon from paracolic gutter through avascular plane of *Toldt*
↓
Safeguarding the ureter, gonadals
↓
Ascending colon and hepatic flexure is released from gall bladder by dividing hepatocolic ligament
↓
Mobilisation from the duodenum and Gerota's fascia
↓
Greater omentum is separated by ligation and division
↓
Care should be taken about SMV and its branches and bleeding
↓
Ligation of the vessels close to the colon in case of benign conditions; ligation of their branches at their origin from middle colic vessels to ileocolic vessels in case of malignancy to clear nodes
↓
Division of the terminal ileum and transverse colon between clamps
↓
Constructing a safe ileocolic anastomosis
↓
Closure of the mesenteric defect
↓
Suction tube drain and closure of the abdomen



Incision over the lateral paracolic gutter along the line of Toldt

Mobilisation at the hepatic flexure gall bladder, hepatocolic ligament, renocolic ligament, from duodenum and head of the pancreas and division of the gastrocolic ligament

Relation behind the ileocaecal region-right ureter is crossing the common iliac artery division and gonadals

Fig. 24-27: Relations, structures which will come across while doing right hemicolectomy.

Radical Right Hemicolectomy

It is done commonly from medial to lateral with vessels ligated at its origin to clear the lymphovascular area. It clears the drainage lymph nodes properly in carcinomas. It also prevents spillage, avoids manipulation of the tumour area prior to vascular ligation—based on '*Turnball's no touch technique*'. Advantages of this medial to lateral technique are—it facilitates the early ligation of the main branches of the SMA and SMV and so prevents possible eventual trauma of superior mesenteric vessels while mobilising the colon; field will be clean and so anatomical variations are better identified. Early lymphovascular dissection achieves more precise dissection and clearance. Even though it is oncologically not very much proved, technically it is more precise. But surgeon should remember that radical hemicolectomy can also be done through conventional approach wherein after complete mobilisation of the colon, vessels are ligated at its origin to clear lymphovascular area.

Through transillumination vascular arcade is studied; site of division is decided in the ileum and transverse colon. After creating a small window at the mesenteric sides of these two points umbilical tapes or fine infant feeding tubes or two wet roller gauzes are passed one on each point (at terminal ileal and transverse colon sides) and tied firmly. Omentum (in malignancy) is detached from the stomach by ligation and divisions or harmonic scalpel can be used. First right branch of the middle colic artery is ligated at its origin (in carcinoma caecum and ascending colon); usually double ligation is needed proximally. In extended right radical hemicolectomy (carcinoma hepatic flexure and transverse colon), middle colic artery is ligated at its origin (at the level of the lower border of the pancreas) as colon division is far away at splenic flexure and remaining descending colon has its blood supply from left colic artery. Both middle colic artery and vein are ligated; inferior pancreaticoduodenal vein is very close and during dissection of the middle colic vessels this vein may get torn by avulsion causing torrential haemorrhage. Transverse colon is lifted upwards; right mesocolon is already opened while ligating the middle colic vessels; index finger is passed underneath to do gentle finger dissection; pulsation of the ileocolic trunk is felt. It is dissected from



Line of resection

In hemicolectomy for benign lesions vessels are ligated close to the colonic wall

Fig. 24-28: In benign lesions, while doing hemicolectomy lateral to medial (conventional) approach is used with ligating the vessels close to the colonic wall without any lymphovascular clearance.



In hemicolectomy for malignant lesions (radical right hemicolectomy) vessels are ligated at their origin from the main branch or SMA

Fig. 24-29: In malignancy, medial to lateral approach (oncological) is used with proper lymphovascular clearance. Here vessels are ligated at their origin.

surrounding areolar tissue; ileocolic vein is also located adjacent to the artery which should not be injured. SMA pulsation is also felt and is identified. SMA pulsation should not be mistaken for ileocolic arterial pulsation. Ileocolic artery and vein are individually ligated doubly using silk 1 cm distal to the SMA. Ileocolic vessels are divided. Ileal mesentery is divided for 10-15 cm (length of ileum removed depends on the location of the primary tumour). It is divided between ligatures.

Now right paracolic gutter is incised at avascular plane of Toldt from terminal ileum to hepatic flexure level using blunt finger and sharp scissor dissection. Ureter, gonadals, Gerota's fascia, duodenum is dissected using bipolar cautery and sharp scissor dissection. Blunt dissection here may injure these structures or can cause bleeding. Gerota's fascia is separated by dividing renocolic ligament. Omentum is separated from the greater curvature of the stomach (partial omentectomy) up to the level of transection of the transverse colon. Ureter is easily identified by its tubular shining nature with good peristalsis. Ureter crosses common iliac artery where bifurcates into external and internal iliac arteries. Reflected peritoneum may be having attached ureter and so should be inspected and felt carefully in the peritoneum.

Ileum and colon is divided similarly like mentioned earlier in conventional method above. Anastomosis is done. Stapler transection can be done at both ends; later completion with side-to-side stapler anastomosis **(Fig. 24-30)**.

Radical right hemicolectomy – medial to lateral vessel first hemicolectomy (Turnball no touch method)

Midline incision, exploration, self-retaining retractor

↓

Umbilical tape or fine infant feeding tube or wet roller gauze is tied around the ileum and transverse colon at their line of resection

↓

Transverse colon is lifted up

↓

Middle colic vessels are identified

↓

In right radical hemicolectomy, right branch of the middle colic vessel at its origin is ligated (in caecal and ascending colon growth). Origin of the middle colic vessels at the lower border of the pancreas is dissected and double ligated in hepatic flexure and right side transverse colon growth (extended). Double ligation should be ligated.

↓

Right colic vessels are ligated (may be absent also)

↓

Larger ileocolic artery is identified, dissected and doubly ligated (should not get confused for SMA)

↓

Terminal ileal vessels (terminal 10-15 cm) are ligated

↓

Now colonic mobilisation is done along the paracolic gutter through the line of *Toldt*

↓

Ureter, gonadals, duodenum, Gerota's fascia are identified and dissected away from right colon

↓

Ascending colon and hepatic flexure is mobilized by separating from gall bladder, duodenum and by cutting the renocolic ligament using scissor and gentle finger dissection; partial omentectomy is done by dividing the omentum adjacent to greater curvature of the stomach

↓

Once complete mobilization is over; specimen is divided between clamps on both sides. Fat at the colonic cut edges is freed for 1 cm;

↓

End to end hand sewn or side to side stapler ileo colic anastomosis is done

↓

Mesenteric defect is closed; suction tube drain is placed; abdomen is closed in layers

Stapler anastomosis can be done as side to side. Few stapler area in the antimesenteric borders of each ends which are brought together are removed just sufficient enough to pass the arms of the stapler. Arms are passed through this across the antimesenteric border and stapler is fired to create the anastomosis as side to side. Now stapled ends of the each part are having a defect at heir antimesenteric border which is closed by another linear stapling device.

Postoperative Care

Nasogastric tube is removed once bowel sounds appears; patient passes flatus; no distension in the abdomen. Drain is removed in 5 days. Oral fluid started in 3-5 days. Antibiotics are given. Fluid and electrolyte management is done judiciously.

Complications

Infection, subphrenic and pelvic abscess formation can occur. It is identified by CT imaging; initially can be treated with antibiotics conservatively but if persists or progress then US/CT guided pigtail catheter drainage or occasionally open drainage is done.

*Anastomotic disru*ption is dangerous complication. It causes leak from drain site or main abdominal wound. If leak is significant then re-exploration and re-anastomosis are done; commonly re-anastomosis is difficult due to friable inflamed oedematous bowel; ileostomy for diversion is best in such situation. If leak is less and patient is passing stool per anally then conservative treatment settles the leak. TPN, antibiotics, control of sepsis and observation, repeated imaging is the needed management.

Abdominal dehiscence is not uncommon; it needs resuturing of the rectus sheath, control of infection.

Injury to right ureter, duodenum can occur. Duodenal injury is sutured if it is small otherwise duodenostomy through a T tube should be done. Ureter injury on table when identified is sutured using interrupted 3-0 vicryl sutures. J stent should be placed in the ureter which is removed in 6-12 weeks.

LEFT COLECTOMY

Left hemicolectomy is done for both benign and malignant diseases. Principles are almost similar as right hemicolectomy. But no touch technique is difficult to apply to left-sided colectomy. Marginal artery should be retained in all these patients especially in malignancies to maintain the blood supply retained to colon and anastomotic site. Left branch of the middle colic artery when retained is adequate enough to maintain the blood supply. Inferior mesenteric artery is ligated and divided at its origin from the aorta and inferior mesenteric vein is divided at lower border of the pancreas. Even most of the sigmoid if needs resection, blood supply of the anastomotic site can be achieved from middle rectal and inferior rectal arteries along with marginal artery. In benign diseases vessels are not ligated at their origin but close to the colonic wall as lymphovascular clearance is not needed.

In no touch technique, inferior mesenteric vessels are ligated first with lymphovascular clearance (for carcinoma left side colon) then left colon mobilisation is done. In benign diseases first mobilisation of the left colon is done then vessels are ligated close the colonic wall.

Splenic injury can occur while mobilizing the splenic flexure; alternatively spleen may get infiltrated by the splenic flexure growth which needs splenectomy. Gonadal vessels can be ligated if needed; but left ureter should be taken care of.



Figs 24-30(1)


Ligation of vascular pedicles at their origin
Ligation of vascular pedicles at their origin
Gastrocolic omentum division

Figs 24-30(2)



Figs 24-30(3)



Figs 24-30(4)



Figs 24-30(5)



Figs 24-30(6)


Mesenteric defect
Anastomotic site

Figs 24-30(7)



Figs 24-30(8)

Figs 24-30(1 to 8): Right radical hemicolectomy with lymphovascular clearance with medial to lateral approach. Vessels are ligated near their origin.

Technique

Epidural and general anaesthesia are given. Nasogastric tube and urinary catheter are passed. After cleaning and draping lengthy midline incision is made. Head down position is better. If in sigmoid resection, when EEA stapler is used then low lithotomy position is better. Self retaining retractor like Finochette is used. Surgeon usually stands on the left side.

Sigmoid and descending colon is held towards right using a mop; peritoneum on the paracolic gutter is incised adjacent to sigmoid; left ureter and left gonadals are identified and safeguarded; incision is extended proximally towards splenic flexure; greater omentum attached to that part of the transverse colon close to the splenic flexure is divided between ligatures. Undue traction and blunt dissection should be avoided which may cause troublesome oozing. *Renocolic ligament* between capsule of left kidney and posterior part of the mesocolon is divided. *Lienocolic (splenocolic) ligament* is divided; *pancreaticocolic ligament* is divided to free the splenic flexure downwards. Appendices epiploicae of transverse colon may come across during dissection which when divided may cause bleeding; it needs proper ligation. While mobilising the splenic flexure adequate exposure is essential; undue traction on the colon may cause the avulsion on the omentum and bleeding; recognising the right plane and dissecting along that is needed; sharp scissor dissection with careful bipolar cautery fulguration is ideal rather than blunt dissection in splenic flexure mobilisation.

Duodenum 3rd and 4th part will be visualised here. Mesocolon on the medial aspect is incised from splenic flexure downwards towards the sacral promontory level. Inferior mesenteric artery is identified emerging from the aorta; its origin is visualised; 1-2 cm distal to its origin artery is double ligated and divided. This allows safe preservation of the hypogastric nerve plexus which are in front of the aorta. Preaortic areolar tissue with lymph nodes is swept medially to clear all lymphovascular tissues. Preaortic sympathetic plexus should not be injured to prevent development of sexual dysfunction. Inferior mesenteric vein is identified which runs upwards behind the duodenojejunal junction behind the pancreas to join splenic vein **(Fig. 24-31)**.

Rest of the mesocolon is divided down towards the sigmoid colon; here marginal artery is divided to complete the mesocolon and vascular dissection and mobilisation. If dissection is carried out downwards up to the rectosigmoid junction; proximal rectum


IMV is ligated at lower border of the body of the pancreas
IMA is ligated 1.5 cm from its origin from aorta
Aorta
Sites of ligations of inferior mesenteric vessels

Fig. 24-31: Ligation of inferior mesenteric vessels in radical left colectomy.

which is covered by peritoneum is dissected for 3 cm above the sacral promontory by ligating and dividing the vascular pararectal tissues. Autonomic nerve plexus lying on the posterior pelvic brim is preserved. Fat around the rectum for 1 cm should be cleared meticulously to achieve optimum anastomosis. Occlusion clamp is applied to the transverse colon proximal to the mobilised splenic flexure; crushing clamp is applied towards specimen side and divided in between using cautery or ideally no. 15 blade. Proximal cut edge should bleed adequately for safe anastomosis. Distally proximal to the mobilised and dissected proximal rectum another curved crushing / Kocher's clamp is applied (towards specimen side); usually clamp is not placed on the rectal stump side; however a soft occlusion clamp can be used if necessity arises. Bleeders in cut edge of the rectum are ligated using fine 4-0 vicryl or bipolar cauterisation is done. Fat should be cleared from the cut both ends for 1 cm; bleeding cut edge should be confirmed. Proximal cut end of the transverse colon easily reaches the rectal stump at sacral promontory level. If tension is present then the hepatic flexure should be mobilised to make transverse colon tension free.

While anastomosing, the cut edges transverse mesocolon should come towards the right side of the rectum. Usually two layered anastomosis is done; but single layer interrupted silk sutures are sufficient. Surgeon should stand on the left side while doing anastomosis. Initially two posterior seromuscular 3 zero silk sutures are placed on the medial and lateral aspects; knots are not tied now and these sutures act as marker / stay sutures to identify the medial and lateral edges of the rectal end. Then remaining 4-6 seromuscular sutures are placed at 5 mm gap; once all sutures are placed they are tied; leaving medial and lateral tied stay sutures long remaining sutures are cut. 2nd posterior full thickness interrupted 3 zero vicryl sutures are placed at 5 mm gap; once all sutures are placed they are tied together. 3rd layer anterior full thickness interrupted 3 zero vicryl sutures are placed and tied together. Lastly anterior seromuscular interrupted 3 zero silk sutures are placed. Site is checked for tension free anastomosis with adequate lumen inside **(Fig. 24-32)**.

Many use continuous 3 zero vicryl sutures for 2nd and 3rd layer. It is also practiced that if apposing area can be rotated for 180° then anterior layer seromuscular sutures are placed first; rotated fully to visualize the posterior layer through which anterior full thickness, posterior full thickness and posterior seromuscular sutures are placed and colon is derotated back to its original position. *End to end (EEA)* stapler can be used to achieve proper anastomosis. *Linear stapling device* can be used to transect at transverse colon level as well as rectal level.

It is often used to pass a wide Foley's catheter (no. 22 F) per anally and gently to negotiate across the anastomotic site to keep it there for 48 hours. After insertion of the Foley's catheter before negotiating across, anastomotic field is filled with normal saline and air is pushed across the Foley's catheter to check air bubbles in the field; if air bubbles are present then few more interrupted silk sutures may be placed at the site of the leak. Again even though it is not mandatory many do anal sphincter dilatation presuming that it will prevent distal obstruction and so reducing the chances of anastomotic leak. Tube drain is placed in the pelvis. Abdomen is closed in layers.

Postoperative Care

Nasogastric tube is removed in 72 hours; oral liquid is started. Drain is removed in 7 days. Skin sutures are removed in 10 days.

Complications

Intraoperative – injury to left ureter; spleen, haemorrhage—adequate exposure and careful dissection will prevent this.


Colon
Mesocolon
Rectum
Mesocolon should be on right side of the patient
Two stay sutures are placed on medial and lateral part
All seromuscular 3-0 silk sutures are placed — interrupted
All seromuscular 3-0 silk sutures are placed — interrupted

Fig. 24-32: Placing seromuscular sutures in colorectal anastomosis.

Postoperative—anastomotic leak can occur; it is usually partial leak and subsides gradually. If significant high fistula persists then covering diversion proximal colostomy or ileostomy should be done. Often peritonitis may develop in such situation, anastomotic site is detached and proximal colonic part of anastomosis is brought out as colostomy; distal rectal stump is closed (Hartmann's) which is sutured to sacral promontory by 2-3 silk sutures to prevent it from getting retracted; once patient recovers from sepsis, only after 3 months resurgery should be done to maintain the continuity. Pelvic abscess, left sided subphrenic abscess are other complications which can occur.

LAPAROSCOPIC COLECTOMY

Laparoscopy for colectomy right or left is now well-accepted approach. There is lack of tactile sensation; dissection in more than one quadrant needs to change the camera in different ports during dissection. Contamination, bleeding, spillage of the content, port site recurrence, conversion, long time, cost are different problems. Still colectomy either totally laparoscopic or hand assisted are accepted universally. Principles and technique are same as open surgery. Identification and localization of the pathology, mobilisation of the needed part of the colon, devascularisation, restoration of the bowel continuity are essential steps of the colectomy. Different ports of different sizes, specialised instruments like bowel grasper and endostaplers are needed. Endostapler needs 12 mm port.

Different types of laparoscopic colectomies are practiced. In dissection facilitated laparoscopic colectomy, mobilisation of the colon is done through laparoscopy; and then through a small laparotomy incision, resection and anastomosis is done. In resection facilitated laparoscopic colectomy, dissection and resection is done through laparoscopy; specimen retrieval and anastomosis is done extracorporeally. In near total laparoscopic colectomy, dissection, resection and anastomosis is performed through laparoscopy; specimen retrieval and anvil of the circular stapler is passed through a small incision. In totally laparoscopic colectomy, dissection, resection, retrieval of the specimen and anastomosis are done through laparoscopy only; it is technically very demanding and time consuming.

Indications: Colonic malignancy, colonic tuberculosis, ileocolic Crohn's disease; diverticulitis, polyps which cannot be removed through the colonoscopy.

Contraindications: Faecal peritonitis, cirrhosis of liver, large abdominal aneurysm, pregnancy, cardiopulmonary problems, previous abdominal surgeries, blood dyscrasias.

Laparoscopic Right Hemicolectomy

Conventional lateral to medial approach and oncological medial to lateral approach are the two approaches. Former one is used in benign lesions and technically easier; latter one is used in malignancy wherein first vascular control is obtained prior to mobilisation. Nasogastric tube and urinary catheterisation are done. Under general anaesthesia, in supine position, cleaning and draping are done. Monitor is kept on the right side; surgeon stands on the left side; cameraman on the left of the surgeon; then scrub nurse.

Port positions: 10 mm umbilical port is created as open method (or closed Veress needle method can be used) which is used as right hand working port initially then later as camera port; suprapubic 10 mm port is used as camera port for mobilisation and later is used for retraction; left hand 5 mm working port is on the right iliac fossa; 10 mm epigastric port initially is used for retraction during hepatic flexure mobilization and later as right hand working port **(Fig. 24-33)**.

Medial to lateral oncological approach: Here during initial dissection of lymphovascular tissue, lateral peritoneal attachment of the ascending colon, which is yet to be divided acts as a natural retractor facilitating the vascular dissection easily. Camera telescope is passed through the suprapubic 10 mm port; terminal ileum is held upwards; peritoneum is opened behind the terminal ileum and caecum; retroperitoneal tunneling is created; right ureter and right gonadals are identified in this avascular plane; cranial dissection is done in front of the right ureter and right gonadals till 2nd part of the duodenum is visualised; Gerota's fascia is seen during this dissection which is not opened. Duodenum, head of the pancreas and IVC is visualised. Stretching of the mesentery facilitates the identification of the ileocolic and right colic vessels from below upwards. Ileo colic vessels are dissected close to their origin to SMV and SMA; fat and lymphatics are cleared off from its surface; ileocolic artery and vein are individually clipped or ligated and divided. Right colic vessels are also divided; often right colic vessels may be absent. Mesentery is divided using harmonic scalpel. Mesentery division continues on the transverse mesocolon until the right branch of the middle colic vessels are identified which are individually clipped and divided. Patient's position is changed to head-up position (reverse Trendelenburg). Right flexure of the colon is retracted downwards and medially; now umbilical port is used as camera port; epigastric port is used for right hand working. Lesser sac is entered by dividing the greater omentum between transverse colon and stomach. Dissection continues laterally by dividing the peritoneum between duodenum and pancreas and transverse colon. Hepatocolic ligament is divided to release the hepatic flexure. Middle colic vessels can be ligated at this juncture as proximal as towards its origin. This completes the devascularisation of the entire right colon; mesentery of the terminal ileum is divided using harmonic scalpel. At the end lateral attachment of the colon is divided using harmonic scalpel to complete the dissection and devascularisation. Intracorporeal resection is done using endo stapler; specimen is retrieved through a small subumbilical incision and anastomosis is done extracorporeally. Alternatively after dissection and mobilisation, mobilised part is exteriorised through a small subumbilical incision; resection is done; anastomosis is done using hand sewn or lineal stapler.



Fig. 24-33: Ports used for right laparoscopic colectomy.

Lateral to medial approach: It is conventional one wherein lateral peritoneal attachment (along the white line of Toldt) of caecum and ascending colon is incised and colon is mobilised; similarly hepatic flexure and transverse colon is mobilised using harmonic scalpel. Right ureter, vas deferens, gonadals and duodenum are identified. Gastrocolic ligament is divided. Subumbilical midline incision is done for 5 cm; mobilised colon is brought out; ileocolic, right colic and middle colic vessels are ligated and divided extracorporeally; in benign conditions vessels are ligated close to the colonic wall as there is no need to divide branch vessels at their origin. Resection and anastomosis is done extracorporeally; mesenteric defect is closed; anastomotic parts is placed back into the peritoneal cavity; minilaparotomy is closed in layers; again pneumoperitoneum is created; peritoneal cavity and anastomotic site is inspected; port area are closed in layers.

Laparoscopic Left Hemicolectomy

Patient is placed supine with semilithotomy position with thighs placed in semiflexed and hips flexed to only limited 15^0. Rotating table is a must to tilt the table as needed. Nasogastric tube insertion and urinary catheterisation is done. Monitor is placed on the left foot side. Wide area cleaning and draping is done; camera port (10 mm) is placed in supraumbilical position or right of the midline; 10 mm right hand working port is in the right iliac fossa; 5 mm left hand working port is in the right lumbar region; 10 mm colon retracting port is in the left lumbar area. Additional trocars may be added depending on need. Surgeon initially stands on the right side but changes the position to between legs for dissection of the splenic flexure and transverse colon on the left side. Head down with left upwards is the usual table tilt done to make small bowel to fall away from the pelvis.

Peritoneal cavity is explored including liver for initial assessment. Sacral promontory is identified; over the medial aspect of the mesosigmoid an incision is made; through the left lumbar midclavicular port sigmoid is grasped and retracted laterally. Avascular plane is reached by deepening the plane. Plane in front of the ureter, gonadals and inferior mesenteric vessels is dissected carefully. Ureter is safeguarded. Inferior mesenteric vessels are dissected and, ligated and divided individually using silk (intracorporeal sutures). Dissection in this plane is continued upwards towards the splenic flexure. Gerota's fascia is visualised and kept undisturbed.

Now sigmoid colon is gently retracted medially and lateral colonic peritoneal attachment is incised along the white line of Toldt. Surgeon should stand in between legs incision; monitor is shifted towards head end; table may be tilted according to need. Dissection over the lateral peritoneum is carried out upwards. Renocolic, splenocolic attachments are released; gastrocolic omentum is divided between stomach and transverse colon. Pancreaticocolic ligament is dissected to release the splenic flexure adequately downwards **(Fig. 24-34)**.

Surgeon returns back to right side position; monitor is shifted back to foot end. Rectal dissection is done through avascular plane between the layers of the pelvic fascia; mesorectum is divided up to the line of resection using harmonic scalpel. Colon can be transected using endostapler; otherwise through subumbilical incision colon is exteriorized; mobilized colon is resected; and end to end or stapler anastomosis is done. Sterile barrier (plastic) should be used while retrieving the specimen to avoid port site complications. Alternatively after resection using stapler; anvil of the EEA stapler is sutured to proximal end using nonabsorbable purse string suture; both ends are dropped into the peritoneal cavity. EEA stapler is gently negotiated per anally towards peritoneal cavity; its sharp point is made to perforate away from stapler line; it is connected to the anvil already present in the peritoneal cavity along with the proximal cut end of the bowel with purse string and locked. Stapler is fired to complete the anastomosis. Device is removed; doughnut is observed.

Complications and Problems with Laparoscopic Colectomy

Difficulty in dissection and mobilisation; injury to vital structures; multiquadrant dissection; problems related to laparoscopy itself; inability to feel the tumour; problems with the retrieval of the specimen; port site problems; increased operating time; anaesthesia complications; availability of the instruments; cost are different problems.

Complications specific to technique are—anastomotic leak; abscess formation (pelvic/subphrenic); anastomotic stenosis. In such situation proximal diversion or colostomy with mucus fistula formation or Hartmann's procedure may be required. Inadequate clearance in case of tumours, port site recurrences are other complications.

Laparoscopic Subtotal/Total Colectomy

It is demanding technique as it needs mobilisation of the colon in different quadrants as well as in pelvis. Tilting table is a must as position has to be changed depending on the site of mobilisation. With steep head-down (Trendelenburg) position (similar like for left colectomy) after placing adequate proper ports dissection begins at rectosigmoid. Dissection here is same as for left colectomy mentioned above. Inferior mesenteric vessel ligation; splenic flexure mobilisation remains the same. Transverse colon mobilisation is carried out as continuation of the splenic flexure mobilisation; gastrocolic omentum is divided using harmonic scalpel; transverse mesocolon is dissected to identify the middle colic artery which is ligated and divided. SMA should be identified and safeguarded without injuring it.

Right colon mobilisation is done with surgeon standing on the left side similar to right colectomy. It is done from medial to lateral approach. Retroperitoneal tunneling is created; right ureter, gonadals are identified; plane in front is dissected upwards; ileocolic vessels are ligated; then right colic artery. Once vascular divisions are complete, lateral peritoneal attachment is incised and divided along the Toldt's line. Terminal ileal vessels are divided using harmonic scalpel.

Rectum is further mobilised depending on the level of resection; injury to sympathetic nerves should be avoided to prevent sexual dysfunction. Injury to sacral plexus vessels will cause torrential haemorrhage; it is difficult to cauterise them as they retract into the sacral foramina.

Rectosigmoid is divided using lineal stapler; minilaparotomy is done with a Pfannenstiel incision; protective plastic sheath is placed across the edge of the laparotomy; specimen is brought out; proximal part (terminal ileum) is transected. Ileo rectal continuity is achieved by intracorporeal suturing or if rectal end can be brought out to the wound it can be done using hand sewn technique; otherwise circular EEA stapler can be used to achieve continuity. Lower level resection decides the procedure as either subtotal or total colectomy.



Figs 24-34(1)



Figs 24-34(2)



Figs 24-34(3)



Figs 24-34(4)



Figs 24-34(5)


ILS 29
12 mm
100 mm
XCEL
Bladeless Trocar
echelon60
echelon60

Figs 24-34(6)

Figs 24-34(1 to 6): Laparoscopic left colectomy. Note the angulated stapler used for transection. It needs 12 mm port. Note the patient position; port positions; steps; specimen retrieval; barrier plastic to the subumbilical minilaparotomy; anvil; placing purse string suture; circular stapler; firing the stapler; and other steps of dissection. Dissection here is done from medial to lateral. Main vessels (left colic) are clipped and divided using harmonic.

LOCALLY ADVANCED TUMOUR (INOPERABLE)

It is managed by colonoscopic decoring and stenting as a palliation. But it needs repetitive procedure. Alternatively bypass can be done either as ileo transverse anastomosis in case of hepatic *flexure* growth or colocolic anastomosis between transverse colon and descending colon in case of the left side advanced growth near or at splenic flexure **(Fig. 24-35)**.

Bowel proximal and distal are brought together confirming that there is no tension; if tension is there bowel mobilisation may be needed. Antimesenteric border of the ileum of 6 cm and antimesenteric border of the colon are incised at taenia at corresponding parts after placing occlusion clamps. Interrupted two layer anastomosis is done with inner full thickness and outer seromuscular sutures using 3 zero silk. Greater omentum may be wrapped around; clamps are removed. Usually drain is not required for bypass procedures unless there is contamination **(Fig. 24-36)**.


Ileo-transverse bypass anastomosis in inoperable right side growth
Colocolic bypass anastomosis in inoperable left side growth

Fig. 24-35: Bypass colonic procedures in advanced malignancies.

SURGICAL MANAGEMENT IN LARGE BOWEL OBSTRUCTION

Large bowel obstruction faces problems with sepsis, dehydration, contamination during surgery, electrolyte imbalance and nutritional deficiency.

Presently resection and primary anastomosis is done as a possibility. However, surgeon should finally decide about the factors like patient's general condition to obtain optimum recovery. Decision should be individualised rather than generalised. If needed after resection and anastomosis for right sided obstruction, covering loop ileostomy should be done which is closed after 3 months.

In left sided obstruction commonly due to growth, resection and anastomosis with right side diversion colostomy is the choice. It is often preferable to do on table colonic lavage to reduce the contamination and sepsis. It is done by passing a catheter through appendicectomy opening or a separate ileal stab opening which is secured by a purse string suture. Left sided growth/obstruction is identified; colon is transected between clamps above the obstruction; proximal end of the bowel is directed outside the surgical field to empty the content or connected to a lengthy tube (Savaage's decompressor). Warm normal saline is run through the proximal catheter distally across the colon towards distal end to empty; around 10 litres of fluid is needed to clean the bowel adequately **(Fig. 24-37)**.

Treatment of Sigmoid Volvulus

Initial treatment—nasogastric tube aspiration; IV fluids; catheterisation; antibiotics; *A flatus tube or sigmoidoscope* is passed in operation theatre (proper care is taken otherwise it leads to perforation). If it derotates, patient will pass flatus and faeces; and distension reduces **(Fig. 24-38)**.

If derotation does not occur, laparotomy through midline incision should be done. Dilated sigmoid colon is derotated manually and checked for viability. If viable, it can be fixed to the lateral wall of abdomen or pelvis—***Sigmoidopexy***.

If sigmoid colon is gangrenous, it is resected and proximal cut end is brought out as colostomy and distal end is brought out as mucus fistula, from the rectum *(Paul-Mikulicz Operation)*. Later after 6 weeks, continuity is maintained after proper preparation.

Resection of the gangrenous sigmoid done; proximal cut is brought out as end colostomy: distal end closed – *Hartmann's operation*. Later in 6-12 weeks colorectal anastomosis is maintained.

Primary resection and anastomosis is not advisable because of the contamination and anastomotic leak.

Mortality in sigmoid volvulus is due to *perforation, peritonitis and septicaemia* **(Fig. 24-39)**.

TREATMENT FOR HIRSCHSPRUNG'S DISEASE

Initially, colostomy is done either transverse or transitional, so to have normal bowel function, and nutritional supplementation. Once the child attains 10 kg of weight, definitive procedure is done, i.e. a. Excision of aganglionic segment (spasmodic segment); b. Maintenance of continuity by doing coloanal anastomosis; c. Closure of colostomy later.

Common procedures done are

Modified Duhamel operation: Resection of upper part of the rectum and a part of colon; anastomosis of colon to posterior part of the lower rectum and crushing the spurs to create the rectal pouch. It is *technically easier and a retro-rectal pull through*. New pouch is created by anterior part of the aganglionic rectum and by ganglionic proximal pulled down colon. Biopsy should be taken from proximal pulled down colon to look for evidence of ganglions. Pulled down proximal colon is sutured to full thickness posterior anal canal just above the dentate line. Spur between these two segments is crushed by Kocher's forceps or specialised instrument to create a single pouch **(Fig. 24-40)**.

Soave's mucosectomy and pull through operation: Through laparotomy approach rectum is mobilised deeply into the pelvis; circular myotomy is made on the rectal wall; submucosal plane is created up to the dentate line; denuded mucosa is excised; normal colon is brought down through this tube and coloanal anastomosis is done. In original Soave's technique, after telescoping the normal proximal colon through the rectal tube outside anus it is made to protrude outside for few cms which is not sutured and left like that to allow distal part to slough off to achieve continuity naturally.

Total proctocolectomy with ileo-anal anastomosis in case of total colonic Hirschsprung's disease.


Ileum
Taeniae
Transverse colon
Stay sutures
Opening colon and ileum using cautery
Colon
Ileum
Posterior layer suturing
Posterior layer suturing
Anterior layer suturing
Completed anastomosis
- single layer interrupted
silk or vicryl sutures

Fig. 24-36: Ileo-transverse anastomosis is done in a patient with obstruction at ileocaecal region. It is done here as patient had abdominal tuberculosis involving peritoneum and omentum; hence resection is not done with less aggressive bypass was done. Single layer interrupted sutures are placed—silk suture material.


Obstructive pathology
Appendix is removed catheter is passed; purse string fixation is done
Bowl
Colon proximal to obstruction is transected proximal colon is connected to a bowl away from surgical field
Or colon can be connected through a decompressor device Warms saline is continuously irrigated from proximally placed catheter across the colon to bring out at distal part
Alternatively proximal irrigating catheter can be passed through the terminal ileum also

Fig. 24-37: Technique of colonic decompression.


Band
Long sigmoid colon
Long mesentery
Narrow root

Fig. 24-38: Precipitating factors for sigmoid volvulus.

Swenson's operation: Through abdomino-anal approach, aganglionic segment of the rectum is mobilised including proximal normal bowel. Rectum above the pathological level is transected; lower segment is everted through the anus; normal proximal colon is brought out through the everted rectum; everted diseased rectum is resected just above the dentate line, anastomosis is done between brought out colon and cut end of the rectum just above the dentate line. Anastomotic site is repositioned back by gentle push.

Anorectal myectomy is found to be very useful for ultrashort segment and short-segment Hirschsprung's disease. Mucosa is incised horizontally 1 cm proximal to mucocutaneous junction. A strip of muscularis with part of internal sphincter is excised with both muscle layers of the rectum for about 6–10 cm length. Mucosa is sutured back. Complications are abscess formation and failure.

Complications of Surgeries

Severe colitis often distressing; faecal fistula due to disruption of the anastomotic site; stenosis at anastomotic site; stunted growth of the child due to deficiencies.



Fig. 24-39: Sigmoid volvulus: Note distended tympanic abdomen; X-ray showing typical sigmoid volvulus; on table gangrenous sigmoid volvulus; underwent resection with colostomy and mucus fistula (exteriorisation).


Proximal colon
Aganglionic rectum
UB
Sacrum
Proximal colon
Aganglionic rectum
UB
Sacrum
Spur crushed

Fig. 24.40: Modified Duhamel operation. Normal colon is brought behind the aganglionic rectum and anastomosed just above the dentate line.

Chapter

25

Anorectal Surgeries

SURGICAL ANATOMY

Rectum

Rectum is connecting part between sigmoid colon above and anal canal. It is a misnomer as it is not straight; it has got curvatures anteroposteriorly and side to side. It is located in the posterior part of the lesser pelvis in front of the three sacral pieces and coccyx. It begins at 3rd sacral vertebra and ends at anorectal ring 2 cm in front and below the tip of coccyx at the apex of the prostate in males. It is 12 cm in length; proximally it has got same diameter as sigmoid colon; below it dilates to form rectal ampulla. Initially, it runs backwards and downwards then it runs forwards and downwards. In the sacrum and coccyx, it is concave in front; it bends backwards at the anorectal junction. It has got three lateral curves—upper lateral with convex towards right; middle lateral with convex towards left; lower lateral with convex towards right **(Fig. 25-1)**.



Fig. 25-1: Curvatures of the rectum.

The three cardinal features of large intestine (*sacculation, appendices epiploicae and taeniae*) are *absent* in the rectum.

Rectosigmoid junction implies a segment of bowel comprising the last seven centimeter of sigmoid colon and upper five centimeter of rectum. On sigmoidoscopic examination, it is taken as a point 15 cm from the anal verge. Taeniae of the sigmoid blends for about 8 cm to become longitudinal muscle coat of the rectum.

Relations of the Rectum

Upper 1/3rd is covered with peritoneum in front and sides; middle 1/3rd is covered by the peritoneum only in front; lower 1/3rd is not related to peritoneum but is dilated to form ampulla. Lower 1/3rd lies below the rectovesical pouch in males (pouch is 7.5 cm from the anus); below the rectouterine pouch (5.5 cm from the anus) in females. Upper 2/3rd in front in males is related to rectovesical pouch, intestines and sigmoid colon; in females rectouterine pouch, intestines and sigmoid. Lower 1/3rd in front in males it is related to base of the urinary bladder, ends of the ureters, seminal vesicles, vas deferens and prostate; in females it is related in front to lower part of the vagina **(Fig. 25-2)**.



Fig. 25-2: Relations of the rectum.

Posteriorly rectum is related to lower three sacral pieces and coccyx, anococcygeal ligament, pyriformis muscle, coccygeus and levator ani, median sacral, superior rectal and lower lateral sacral vessels, sympathetic chain and ganglion impar, anterior primary rami of S3,4,5 and coccyx 1 nerves, pelvic splanchnic nerves, lymph nodes, lymphatics and fat.

Upper rectum contains 3 folds—left superior (12 cm from anal verge); right middle (10 cm from anal verge); left inferior (7 cm from the anal verge). These folds are called as valves of Houston.

Arterial Supply of the Rectum

Superior rectal artery, terminal branch of inferior mesenteric artery is the main artery of the rectum. It runs medial to left ureter at pelvic brim; opposite 3rd sacral vertebra it divides into right and left branches.

Each branch divides into smaller branches to pierce the muscle wall of the rectum to run in the anal columns up to anal valves to form anastomoses.

Middle rectal artery arises from anterior division of the internal iliac artery runs in the lateral ligament supplies muscles of the lower rectum.

Median sacral artery arises from the back of the lower most part of the aorta descending in the median plane supplying the posterior part of the anorectum **(Fig. 25-3)**.



Fig. 25-3: Arterial supply of anorectum.

Venous Drainage

Superior rectal vein: Internal anal plexus forms about six tributaries which run upwards in the rectal submucosa; pierces the rectal muscular coat about 7.5 cm above the anus; join together to form superior rectal vein which eventually continues as inferior mesenteric vein.

Middle rectal veins drain from muscle coat of the rectum to end in internal iliac vein.

Submucous venous plexus drains into the venous plexus around the rectum, which communicates with the venous plexus in the base of the broad ligament in female and vesical plexus in male.

Lymphatic Drainage

Upper half of rectum drains along the superior rectal vessels drain into the inferior mesenteric nodes; from the lower half of the rectum drain along the middle rectal vessels into the internal iliac nodes.

Nerve Supply

Superior rectal, inferior mesenteric and inferior hypogastric plexus supply both sympathetic (L1,2) and parasympathetic (S2,3,4) components. Sympathetic nerve is vasoconstrictor, inhibits the rectal muscle, and constricts the internal sphincter. Parasympathetic nerve contracts the rectal muscle but inhibits the internal sphincter.

Supports of Rectum

Pelvic floor: It is formed by levator ani muscles.

Fascia of Waldeyer: It is the condensation of pelvic fascia behind rectum, contains superior rectal vessels and lymphatics. It attaches the lower part of the rectal ampulla to the sacrum. It is strong thick layer of parietal pelvic fascia adherent to sacrum and coccyx. Below it fuses with the rectum at anorectal junction. It is seen as a thick white fascial layer above the anococcygeal ligament. This Waldeyer fascia has to be divided to gain access to the retrorectal space; inadvertent dissection posterior to this fascia will injure sacral veins causing torrential haemorrhage.

Lateral ligaments of rectum: It is the condensation of pelvic fascia, attaches rectum to the postero-lateral wall of lesser pelvis. They enclose the middle rectal vessels and branches of the pelvic plexus. It is also called as rectal stalk, is a dense fibrous tissue running from the 3rd piece of sacrum to the rectal wall. It contains nervi erigentes. These ligaments have to be divided during abdominoperineal resection.

Denonvillier's fascia: It is the fascial condensation which separates rectum from prostate and seminal vesicles in males and vagina in females. It is densely adherent visceral pelvic fascia in front of extraperitoneal portion of the rectum extending above from upper peritoneal reflection below to urogenital diaphragm; laterally it continues with lateral ligaments. This fascia remains adherent to the posterior aspect of the prostate gland.

ANAL CANAL

Anal canal is 3.8 cm long extending from the anorectal ring to the anus directed downwards and backwards; it is situated below the level of pelvic brim; lying in the perineal anal triangle between right and left ischiorectal fossae. These fossae facilitate expansion of the anal canal during defaecation. Anal canal is surrounded by inner involuntary and outer voluntary sphincters. They keep the anal canal closed as an anteroposterior slit.

Anorectal junction is the junction where rectal ampulla narrows and pierces the pelvic diaphragm. It corresponds to the apex of the prostate. Anorectal junction is located 2 cm in front and just below the tip of the coccyx.

The anus is surface opening of the anal canal situated 4 cm below and in front of the tip of the coccyx. This has radial folds of the skin with pigmentation containing apocrine glands.

Relations: Anteriorly, it is related to perineal body; in males, membranous urethra and bulb of penis; in females, lower end of the vagina. Posteriorly, it is related to the anococcygeal ligament and coccyx. Laterally, it is related to the ischiorectal fossae. Sphincter muscles are around the anal canal.

Spaces Related to the Anal Canal

Ischiorectal fossa (pyramidal shape 5 cm depth and 2 cm width) lies between anal skin and levator ani. Right and left communicates with each other. Laterally, it is related to fascia covering obturator internus and ischial tuberosity; medially to levator ani and external sphincter; posteriorly sacrotuberous ligament and gluteus maximus; anteriorly urogenital diaphragm; below, the floor by skin. Above, it is related to lunate fascia and pudendal neurovascular bundle in pudendal canal

(*Alcock's canal*). There is no deep fascia under the skin in ischiorectal fossa. *Fascia lunata* (semilunar shaped hence the name) covers fascia on the levator ani medially, covers fascia on the obturator internus laterally (pudendal canal is located between obturator fascia and fascia lunata transmitting internal pudendal vessels and nerves); in front it fuses with urogenital diaphragm; above fascia is arched as tegmentum creating suprategmental space above **(Fig. 25-4)**.


Obturator internus
Levator ani
Alcock's canal (pudendal)
External sphincter
Lunate fascia
Ischiorectal fossa

Fig. 25-4: Surgical anatomy of ischiorectal fossa.

The perianal space surrounds the anal canal below the white line. It contains subcutaneous external sphincter, external rectal venous plexus and the terminal branches of the inferior rectal vessels and nerves. Pus here spreads to white line or perianal skin but not into the ischiorectal space.

Submucous space lies above the white line between mucous membrane and internal sphincter, which contains internal venous plexus and lymphatics. Abscess here (submucous abscess) is not visible from outside; on rectal examination, it is felt as boggy tender swelling. It needs drainage under general anaesthesia.

Parts of the Anal Canal

Interior of the anal canal is divided into three parts **(Fig. 25-5)**.


Ano-rectal junction
Upper part – 15 mm
Anal column
Anal valve
Pectinate line (Dentate line)
Pecten
Middle part – 15 mm
White line of Hilton
Lower part – 8 mm

Fig. 25-5: Parts of the anal canal.

Upper part is 15 mm in length; lined by mucous membrane; endodermal origin. 6–10 vertical folds here are called as *anal columns of Morgagni*; lower ends of these columns joint together by transverse folds called as *anal valves*; depression above each valve is called as *anal sinus/anal crypt*. Anal glands about 5–10 in number opens into the anal crypts. Transverse line along the anal valves all around is called as *pectinate/dentate* line. Epithelial projections of the anal valve are called as anal papillae. Dentate line is situated opposite the middle of the internal sphincter.

Middle part of the anal canal is called as pectin or transition zone; is 15 mm in length; dense submucosal venous plexus makes it appear bluish; this part mucosa is less mobile. Lower portion of middle part is whitish and is called as white line of Hilton, which defines the gap between subcutaneous part of the external sphincter and lower border of the internal anal sphincter. Middle part is thin, pale, glossy and is lined by stratified squamous epithelium without sweat glands.

Lower part of the anal canal is 8 mm in length and is lined by sweat and sebaceous glands like a true skin.

Muscles of the Anal Canal

Internal anal sphincter is formed by thickened circular smooth muscle which is involuntary; extends and surrounds proximal 3 cm of the anal canal; below it ends at white line of Hilton. It is controlled by autonomic nervous system. Internal sphincter is light chicken meat coloured, firm structure which is well exposed during haemorrhoidectomy; its lower fibres are divided during sphincterotomy for fissure in ano. Under anaesthesia when anus is stretched, lower end of the internal sphincter is at a lower level than the lower end of the external sphincter **(Fig. 25-6)**.


Circular muscle
Puborectalis
Longitudinal muscle
Internal anal sphincter
Deep part
Ischiorectal fossa
Submucosal venous plexus
Superficial part
External sphincter
Subcutaneous part
Fibro-elastic septa
White line
Perianal fascia
Skin

Fig. 25-6: Sphincters of the anal canal.

External anal sphincter is striated voluntary muscle which surrounds the entire length of the anal canal and has three parts—deep, superficial and subcutaneous. *Subcutaneous part* is below the level of the internal sphincter; it is flat band of 15 mm size, which does not have bony attachments. *Elliptical superficial part* arises from terminal coccygeal segment and anococcygeal ligament or raphe which after surrounding the lower part of the internal sphincter gets inserted into the perineal body. *Deep part* also does not have bony attachment;

it surrounds the upper part of the internal sphincter to fuse with puborectalis above. External sphincter is supplied by the inferior rectal nerve and branch of the 4th sacral nerve **(Fig. 25-7)**.



Fig. 25-7: External sphincter and puborectalis muscle. Deep part of the external sphincter fuses with the puborectalis above.

Conjoint longitudinal muscle coat is formed at the anorectal junction by the fusion of the puborectalis and longitudinal muscle coat of the rectum lying between external and internal sphincters. Below it forms fibroelastic band, which at the level of white line divides into many fibroelastic septa piercing the subcutaneous part of the external sphincter getting attached to the skin around anus. Lateral most septum is perianal fascia; anal intermuscular septum is most medial one.

Anorectal muscular ring is formed at the anorectal junction by the fusion of the puborectalis, deep external sphincter and internal sphincter. Ring is less prominent anteriorly as puborectalis fibres are absent anteriorly. Anorectal ring is palpable on digital examination of the rectum.

Arterial Supply of the Anal Canal

Part above the pectinate line is supplied by the superior rectal artery; part below is supplied by the inferior rectal artery.

Venous Drainage of Anal Canal

Internal rectal/haemorrhoidal venous plexus lies in the submucosa of the anal canal draining into the superior rectal vein and so inferior mesenteric vein; communicates freely with external venous plexus which drains into the middle (to internal iliac vein)and inferior rectal (to internal pudendal vein) veins—creating a porta systemic communication.

Lymphatic Drainage of Anal Canal

Lymphatics above the dentate line drains into internal iliac nodes; below the line drains into medial group of superficial inguinal nodes.

Nerve Supply of Anal Canal

Above the dentate line sympathetic by inferior hypogastric plexus L1,2 and parasympathetic by pelvic splanchnic nerve, S2,3,4; below the dentate line somatic inferior rectal nerve S2,3,4.

Internal sphincter contracts by sympathetic action; relaxes by parasympathetic action. External sphincter is supplied by the inferior rectal nerve and branch of 4th sacral nerve.

Muscles Related to the Anorectum

Levator ani: It is important muscle in the pelvic diaphragm. It has got two parts. **Pubococcygeus part**—*Anterior fibres* of the puborectalis originates from the medial surface of the pelvic surface of the body of the pubis which surrounds prostate in males as levator prostatae; in females surrounds the vagina as sphincter vaginae. *Middle fibres* arise from the lateral parts of the pelvic surface of the body of pubis as puborectalis which encroache the anorectum. The *posterior fibres* of the pubococcygeus originate from the anterior half of the white line of the obturator fascia getting attached posteriorly to anococcygeal ligament and tip of the coccyx. ***Iliococcygeus part*** arises from the posterior half of the white line of obturator fascia and pelvic surface of the ischial spine; inserted medially and behind to anococcygeal ligament and side of the last two pieces of coccyx. Levator ani is supplied by a branch from 4th sacral nerve and a branch from inferior rectal nerve or perineal division of the pudendal nerve **(Figs 25-8 and 25-9)**.

Coccygeus: It is triangular in shape which is partly muscle and partly tendinous; originates from pelvic surface of the ischial spine and sacrospinous ligament to insert into the side of the coccyx and 5th sacral vertebra. Coccygeus is supplied by a branch from 4th and 5th sacral nerves.

Pyriformis muscle: It originates from pelvic surface of 2nd, 3rd, 4th pieces of the sacrum, upper margin of the greater sciatic notch, adjoining sacroiliac joint and sacrotuberous ligament; inserted into the apex of the greater trochanter of the femur. It is supplied by ventral S1, 2 rami.

Obturator internus: It originates from pelvic surface of the obturator membrane, body of the ischium, ischial tuberosity, ischiopubic rami, ilium below the pelvic brim; it is inserted into the medial surface of the greater trochanter of the femur after passing through the lesser sciatic foramen running laterally. It is supplied by nerve to obturator internus—L5, S1, 2.

Vessels of the Pelvis

Internal iliac artery (IIA) begins as smaller terminal branch of common iliac artery which is 3.75 cm in length. IIA in fetus transmits blood to the placenta through the umbilical artery. CIA → IIA → umbilical artery → placenta in fetus. After birth, only proximal part of the umbilical artery persists as 1st part of the superior vesical artery;



Fig. 25-8: Levator ani muscle.


Pubic symphysis
Sacrum
Puborectalis
Anal canal
Pubic symphysis
Puborectalis
Anal canal

Fig. 25-9: Puborectalis sling.

remaining part of the umbilical artery obliterates as medial umbilical ligament. IIA begins in front of the sacroiliac joint at the level of disc between L5 and sacrum. It runs medial to psoas major downwards and backwards ending at the upper margin of the greater sciatic notch by dividing into *anterior and posterior divisions*. IIA is related in front to ureter, ovary and Fallopian tube in females; behind to internal iliac vein, lumbosacral trunk and sacroiliac joint; laterally to external iliac vein and obturator nerve; medially to peritoneum and small tributaries of IIV. IIA supplies all pelvic organs except those supplied by the superior rectal, ovarian and median sacral arteries; the perineum; greater part of the gluteal region; iliac fossa. *Branches* of anterior division are—superior vesical; obturator; middle rectal; inferior vesical; inferior gluteal (largest branch of anterior division) and internal pudendal. (In females, inferior vesical artery is replaced by vaginal artery; also uterine artery as an additional branch). *Posterior division branches are*—iliolumbar, two lateral sacral, superior gluteal arteries (runs above the 1st sacral nerve and enters the gluteal region by passing through the greater sciatic foramen above the pyriformis). Inferior gluteal and internal pudendal are terminal branches; in males there are six branches; in females seven branches (uterine artery is extra). Artery of vas arises from superior vesical artery **(Fig. 25-10)**.

Obturator artery runs in obturator fascia in between obturator vein (below) and nerve (above) enters the obturator foramen. It passes through the obturator foramen. It is crossed by ureter and vas deferens. It gives iliac, vesical branches and a pubic branch, which communicates with pubic branch of the inferior epigastric artery and with pubic branch of opposite side obturator artery.

Middle rectal artery originates with the inferior vesical artery; it supplies prostate, seminal vesicle and a little to muscle of the rectum; it may be absent in females.

Inferior gluteal artery is the largest branch of IIA running downwards in front of the sacral plexus and pyriformis and runs between pyriformis and coccygeus to enter lower part of the greater sciatic foramen to reach gluteal region. It gives muscular, fascial and vesical branches in the pelvis.

Internal pudendal artery is the main artery of the perineum and external genitalia. It is the smaller terminal branch of the anterior division of the IIA. In the pelvis, it runs on the pyriformis, sacral plexus, inferior gluteal artery enters the gluteal region by passing through the greater sciatic foramen; it runs for a short course in gluteal region; again through lesser sciatic foramen enters the pudendal canal. In the canal it is related to dorsal nerve and perineal nerve; gives inferior rectal artery posteriorly and perineal artery anteriorly; artery enters the deep perineal space as artery of penis or artery of clitoris. Artery of the penis divides just behind the arcuate pubic ligament as deep and dorsal arteries of the penis. Branches of the internal pudendal arteries are—*inferior rectal artery* that supplies skin and muscles of


Aorta
Median sacral artery
Posterior division
Anterior division
Superior vesical artery
Obliterated umbilical artery
Obturator artery
Obturator fascia
Inferior vesical artery
Common iliac artery
Iliolumbar artery
Superior gluteal artery
Internal iliac artery
External iliac artery
Pyriformis muscle
Sacral arteries
Middle rectal artery
Ischial spine
Ischial tuberosity
Internal pudendal artery
Inferior gluteal artery

Fig. 25-10: Internal iliac artery and its branches in the pelvis.

the anal region. Perineal artery pierces the base of the perineal membrane to reach the superficial perineal space dividing into transverse perineal and posterior scrotal arteries. Artery of the penis runs in the deep perineal space gives artery of the bulb (supplies the bulb of penis and posterior urethra); urethral artery (supplies anterior urethra and corpus spongiosum); deep artery of the penis supplies the crus and corpus cavernosum; dorsal artery of the penis supplies the skin, fascia of the body of the penis and glans.

Internal iliac vein lies posteromedial to the IIA joins the external iliac vein to form common iliac vein at the pelvic brim, in front of the lower part of the pelvic brim.

Lymph Nodes of the Pelvis

Internal iliac nodes receive lymphatics from all pelvic organs, deeper parts of the perineum, muscles of the buttock and back of thigh; efferents enter the common iliac nodes. Sacral and obturator nodes drain to these nodes.

External iliac nodes receive lymphatics from inguinal nodes of infraumbilical deeper parts of the abdominal wall, membranous urethra, prostate, base of the urinary bladder, cervix of the uterus, part of the vagina. Inferior epigastric nodes and circumflex iliac nodes drain to these nodes.

Common iliac nodes are 4–6 in number receive lymphatics from external and internal iliac nodes; their efferents enter the lateral aortic nodes.

Nerves Related to Anorectum

During dissection of the rectum, hypogastric nerves should be retained. So proper anatomical knowledge of nervous system in the pelvis is essential to a surgeon.

Autonomic Nervous System of Abdomen

Sympathetic nerves are derived from coeliac plexus formed by splanchnic from thorax supplies all abdominal organs and gonads; the lumbar sympathetic trunk has got somatic branches to lower abdominal wall and lower limb; visceral branches supply pelvic organs. Coeliac ganglion is the largest ganglion in the body situated one on each side of the coeliac trunk. Coeliac/solar plexus is located in relation to coeliac ganglion on the aorta around coeliac trunk and root of SMA. Coeliac plexus extends above to crura of diaphragm; overlapped by IVC and pancreas. Its preganglionic fibres come from greater and lesser splanchnic nerves; preganglionic vagal fibres from right vagus mainly. Its branches are – plexuses of phrenic, hepatic, left gastric, suprarenal, renal, testicular/ovarian. Superior mesenteric plexus contains superior mesenteric ganglion. Abdominal aortic plexus is intermesenteric plexus formed by coeliac plexus and fibres from 1st and 2nd lumbar splanchnic nerves. Plexus is situated on the sides and in front of the aorta, between the origins of the superior and inferior mesenteric arteries with 6–12 intermesenteric nerves which are connected to each other. Above it is connected with coeliac plexus; below it continues as superior hypogastric plexus. Branches of this aortic plexus are—testicular, inferior mesenteric, iliac and superior hypogastric plexus.

Lumbar sympathetic chain: It is situated on both sides of the body of vertebrae. There are four ganglia as 1st and 2nd are usually fused together. It runs downwards closely related to psoas major and lumbar vessels; on right side it is covered by IVC; on left side by lateral aortic nodes. First ganglion is very closely related to crus of diaphragm. Lumbar sympathetic chain continuous below behind the common iliac vessels as sacral part of the sympathetic chain. Anterior primary rami of corresponding lumbar nerves send white rami communicans to corresponding ganglion. Lumbar nerves receive grey rami communicans from corresponding ganglia as their lateral branches. Their upper two medial branches join coeliac and aortic plexus; lower two join the superior hypogastric plexus.

Superior hypogastric plexus often is called as presacral nerve; is located in front of the abdominal aorta, left common iliac vein, median sacral vessels, body of 5th lumbar vertebra, sacral promontory, and between two common iliac arteries. Plexus is located more towards left side. It is having commonly multiple fibres. Plexus is formed by descending fibres of aortic plexus and 3rd and 4th lumbar splanchnic nerves. Above it gives branches to ureter, testis/ovary, and common iliac plexus branch; below it divides into right and left hypogastric nerves which on reaching the pelvis form inferior hypogastric plexus **(Fig. 25-11)**.



Fig. 25-11: Autonomic nervous system of the posterior abdominal wall and pelvis.

Inferior hypogastric plexuses are two—right and left. It is located in the pelvis extraperitoneally; lying on the side of rectum, seminal vesicle, prostate, posterior part of the urinary bladder in males; in females it lies on side of rectum, cervix and fornix and posterior part of the urinary bladder. In males, adjacent to prostate and seminal vesicle, in front of the Denonvillier's fascia nervi erigentes from pelvic splanchnic nerves join sympathetic branches to form a neurovascular bundle of Walsh. Inferior hypogastric plexus gives sympathetic and parasympathetic branches.

Parasympathetic nerves are derived from vagus, which joins coeliac ganglion; pelvic splanchnic nerves join inferior hypogastric plexus. Pelvic splanchnic nerves (nervi erigentes) are sacral outflow of parasympathetic system. Nerves arise from ventral rami of S2,3,4. They pass through the sacral foramina and join the inferior hypogastric plexus to supply the pelvis; few fibres run upwards along with hypogastric nerves to join superior hypogastric plexus.

Pelvic sympathetic chain runs medially over the body of the sacrum along the medial margins of the foramina, one on each side, two chains join in front of the coccyx as ganglion impar.

PRINCIPLES IN ANORECTAL SURGERIES

Lithotomy position is essential in most of the anorectal surgeries. Low lithotomy with legs at low position is better **(Fig. 25-12)**.

Entire abdomen, perineum should be cleaned and separately draped. Nasogastric tube and urinary catheterisation is needed in rectal surgeries and in selected anal surgeries. Head low position (reverse Trendelenburg/Fowler's) is also useful to keep small bowel upwards out of surgical field in the pelvis. Anatomical dissection in the rectum is difficult as it is a narrow compact area. Injury to sphincters will lead into incontinence. Buttocks should be abducted properly to facilitate the perineal dissection in abdominoperineal resection and also in anterior resection to negotiate the circular stapler across the anal canal.

Invasion of the tumor into the presacral nerves and prostate makes rectal cancer inoperable. Adherence to sacrum due to desmoplastic reaction is common and is not a contraindication for resection. In some patients with local invasion initial neoadjuvant chemotherapy or chemoradiation and later resection (APR) can be done probably after 3 cycles of chemotherapy.

Anastomotic leak can occur in rectal anastomosis. There is no serosa in the lower rectum and so barrier is not clear.

Nerves in the posterior plane may get injured which will cause impotence. Safeguarding the nerve is very important. Preaortic sympathetic nerves of the superior hypogastric plexus contribute to inferior pelvic hypogastric plexus; this plexus at sacral promontory forms two hypogastric nerves often each with many strands descends in the posterolateral wall of the pelvis close to IIA (hypogastric artery); injury to this will cause failure of ejaculation in males.

In carcinoma, achieving clearance circumferentially (CRM, circumferential resected margin) is important. Total mesorectal excision is ideal (TME) but technically it is demanding.

Disparity between diameter of rectal ampulla (6 cm) and colon needs correction. Otherwise anastomotic dehiscence can occur. Side to end anastomosis between the colon and rectum will correct this problem. Tension free anastomosis is very important. Mobilisation of the splenic flexure is a must in all rectal cancer surgeries.

Oozing in the presacral space during dissection is common; it is often difficult to reach the instruments into deep pelvis for control of haemorrhage and dissection especially in open approach. Laparoscopic approach facilitates the instruments into the place and visual dissection. Haematoma is common in this space which will lead into sepsis, disruption of the anastomosis. It is better to place a suction drain in the presacral space. Dissection in presacral space very close to the periosteum will injure the veins draining through the sacral foramina which get retracted into the foramina. It is impossible to control such haemorrhage. Packing or placing surgicel on the presacral foramina or placing thumbtack on the foramina (Nivatvongs and Fang, 1986) or bone wax are the only options. If nothing helps then pack/mop kept in place firmly controls the bleeding almost always. Presacral bleeding can be avoided by doing sharp dissection rather than blunt dissection. Laparoscopic dissection is very helpful for presacral dissection. Dissection should be in front of the endopelvic fascia, which covers the presacral veins. If presacral dissection is bloodless then it means it is in proper plane.

Most of the bleeding in rectal surgeries are venous and careful bipolar cautery fulguration controls the bleeding often also with suture ligation.



Fig. 25-12: Lithotomy position is commonly used for anorectal surgeries. Prone jackknife position is also used often.

Waldeyer fascia in the lower part behind the rectum is strong and tough and it should be dissected with sharp scissor or harmonic scalpel or using cautery. Care should be taken not to injure the rectal wall during this dissection.

Peritoneum in the pelvic floor after colorectal anastomosis should not be sutured as it will create a dead space around the anastomotic site. But it may be sutured after APR. It is to be sutured or not is a debate in patients who receive RT to avoid small bowel getting radiation enteritis and so adherent to pelvis.

Adequate blood supply is an absolute need in colorectal anastomosis. Inadequate blood supply means inadequate healing of the anastomotic site. It is better to ligate vessel after the branching of the left colic artery instead of ligating the inferior mesenteric artery at its origin.

Both ureters should be identified and safeguarded in rectal surgeries. It is important to have a fair knowledge of the surgical anatomy of the ureter, rectum and pelvis while doing rectal surgeries. Blind surgeries, surgeries without anatomical knowledge in the anorectum will lead into the complications. There cannot be presumption in surgical dissection and technique. Proper anatomical knowledge and safe dissection is the absolute need in rectal surgeries. Ureter crosses the common iliac artery at its bifurcation; it is identified on table by its colour, vascular network on its surface, by eliciting the peristalsis by gentle pinching or touching. Ureter should be traced beyond the lateral ligaments of the rectum.

For most of the rectal cancers, sigmoid is removed with the rectal specimen and continuity is achieved by anastomosing the descending colon to the rectal stump after complete mobilisation of the splenic flexure.

Stapled (circular) anastomosis is better in low resections. In resection suturing anastomosis can be done 10 cm above the anal verge. Below that level suturing is difficult. Angulated stapler is used to divide and close the rectal stump from above; then circular stapler is passed from below to complete the stapled anastomosis. This avoids the difficult purse string suturing of the rectal stump.

Difficult low anastomosis should be complemented with proximal diversion colostomy of transverse colon at right hypochondrium.

Anastomotic site is often passed with a tube 28–30 French Foley's catheter across and can be kept in place for 4–5 days. Through this, air can be injected on table to observe the possible air bubble in a saline filled anastomotic site to identify the leak (leak test). Leak test is commonly done in anterior resection even though many surgeons do not keep catheter in place for long time (4–5 days). In olden days, it is practice to do sphincter dilatation in presumption of preventing distal obstruction and fair anastomotic take up. It is not proved as such and so is not mandatory.

In anorectal surgeries like for fissure in ano, haemorrhoids, Sitz bath is given. Patient sits in a warm water bowl dipping the anal canal region for 25–30 minutes two to three times a day; it reduces the oedema, promotes the healing and relieves the pain significantly. Local heat increases blood flow to the area, promoting healing. A plastic tub that can be fit over the toilet commode to which few centimetres depth warm water is added. Small quantities of Eusol, povidone iodine or salt can be added to that. Delayed wound healing is common after excision of anal papilloma or similar lesions. Stricture is also common due to wound contraction and fibrosis **(Fig. 25-13)**.

Sphincter injury, stricture in anorectal surgery is common which should be avoided by careful dissection at anatomical plane.

All patients with colorectal surgery needs DVT prophylaxis using low molecular weight heparin. Stoma therapist should give advice in relation to stoma care prior to surgery if patient needs colostomy or ileostomy.



Fig. 25-13: Anal papilloma.

TREATMENT PLAN FOR CARCINOMA RECTUM

Surgical Principles

Surgery is the main method of treatment. Preoperative chemoradiotherapy is often used if growth is invading into adjacent tissues (T4). Adjuvant chemotherapy and radiotherapy is a must. Genetic, morphologic, biologic features of rectal cancers are similar to colonic cancers. But *anatomical factors* make it more complex than colonic cancers, like its location deep in the pelvis, relation to important structures like ureters, bladder, genital, autonomic nerves and anal sphincters. So surgical approach is very difficult. *Avascular endoplelvic fascial plane (holy plane of Heald)* is important during dissection to avoid injury laterally to autonomic nerves (will cause impotence in men and bladder dysfunction in both sexes); more medial dissection leads into incomplete clearance and high local recurrence. *Abdomino perineal resection (APR)* is the gold standard. But if tumour is well-differentiated and if there is adequate margin above the anal canal, a sphincter saving *anterior resection (AR)* can be done. *Low anterior resection (LAR)* is possible if EEA stapler is used for anastomosis. But anterior resection should not be done by compromising the adequacy of tumour clearance. Tumour clearance is still the priority in rectal cancer as it decides the eventual outcome. *Total mesorectal excision (TME) should be the goal* in all procedures as mesorectum contains nodes and lymphatics, clearance of which gives better result. It is a *sharp dissection* (not blunt) in avascular areolar plane between fascia of rectum which encroach the mesorectum and parietal pelvic wall fascia. Mesorectum should not be breached. Absolute haemostasis, *preservation of autonomic nerves* and dissection under vision are the essential principles. Both layers of membranous anterior Denonvillier's fascia should be dissected off the prostate and seminal vesicles in male to have proper clearance. In TME for middle and lower rectum, entire mesorectum should be removed. For upper rectal tumours, TME is done 5–6 cm below the lower margin of the tumour. *TME improves the quality of life in relation to impotence, retrograde ejaculation and urinary incontinence. These complications are around 50% or more in APR whereas in TME it is less than 20%.* Recommended *distal rectal margin clearance is 5 cm*, however, 1–2 cm distal margin is an *acceptable* clearance. *Circumferential resected margin—CRM* (*radial margin,> 2 mm*) is more important than proximal and distal margin. A 5-cm clearance of mesorectum from the primary tumour is essential as tumour implants can occur only for up to 4 cm from primary tumour margin.

Principles to be followed—adequate lymphatic and vascular clearance; en bloc resection of primary tumour; no/less touch technique; avoiding spillage; adequate radical surgery. *Ultra low anterior resection or intersphincteric* resection can be considered in low rectal tumours. After resection (on table) *irrigation of rectal bed* with cetrimide or hypertonic solution like distilled water is often practiced as they are tumouricidal. Selection of the procedure, AR or APR is decided by proper staging using TRUS and MRI. Neoadjuvant chemotherapy or neoadjuvant chemoradiotherapy is often used in T3 lesions, which also may avoid APR; and AR may be sufficient. Local wide excision approaches are often used when tumour is < 4 cm; < 40% circumference involved.

T1 N0/T2 N0 tumour: *transanal approach* is used in small tumours that is 3–5 cm above the dentate line but within 10 cm from the anal verge: *transcoccygeal Kraske's approach* for posterior wall rectal tumours (dangerous posterior faecal fistula can occur); *Transanal endoscopic microsurgery* (Buess) using operating microscope and videoscope can also be done. This *endosurgical device* is 4 cm in diameter, specialised sealed proctoscope with ports for CO_2 insufflation, water irrigation, and suction and for monitoring intrarectal pressure. CO_2 insufflation distends the rectum and local excision is done with proper positioning of the device.

In females, partial vaginectomy with or without hysterectomy and bilateral oophorectomy may be needed in T4 lesions to achieve surgical resection. Removal of uterus and ovaries prevents patient from developing possible associated cancers of these organs. Carcinoma rectum also spreads to ovaries commonly, which can be prevented by oophorectomy. Often resection of liver secondaries can be undertaken in selected patients when one lobe is involved or solitary secondaries are present.

Laparoscopic APR/AR is becoming popular. *Features are*: Dissection will be more meticulous. Less blood loss, less post-operative pain; early bowel function; clearance is same as open method in relation to primary tumour and nodes.

Short hospital stay, mortality and morbidity are similar to open method. Port site recurrence chances are 0.5-2% (Earlier it was higher; now it has reduced due to proper technique, careful handling of the specimen, specimen isolation prior to extraction, trocar site irrigation with cytotoxic agents and povidone iodine).

For carcinoma rectum presenting with obstruction, an initial proximal colostomy is done. Neoadjuvant chemoradiation is given. Patient is reassessed for operability. Then APR is done with permanent colostomy.

Incidence *of local recurrent rectal cancer* is 30%. About 80% of local recurrence occur within 2 years of surgery. Common site of recurrence is in the pelvic wall. It also can occur at distal anastomotic margin. Intractable pelvic pain, urinary symptoms, sepsis, bleeding, perineal sinus, swelling and induration, bowel disturbances are the features. It is evaluated by CEA, biopsy, CT abdomen, MRI of pelvis and PET scan. It is often difficult to manage **(Figs 25-14 and 25-15)**.

Incidence of recurrence will come down to 5% in proper TME. Palliative chemoradiation, end colostomy, ureteral stenting are the palliation. RT controls pain and bleeding. Extensive radical surgery like removal of tumour with pelvic structures can be undertaken with diversions but with a high mortality rate and failure rate.

Proper *preoperative bowel preparation* is a must in all rectal cancers, which reduces the post-operative problems like sepsis, leak and increases the early chance of recovery. Bowel preparation by polyethylene glycol; electrolytes *orally*; bowel wash *per anally*; bowel antiseptics like neomycin 1 gm tid previous day/erythromycin 1 gm tid/metronidazole tid *orally*. Systemic antibiotics like cefazolin, metronidazole, gentamicin; prophylactic heparin or low molecular weight heparin; Foley's catheterisation and nasogastric tube—are other preparations. Preoperative adequate hydration using IV fluids; blood grouping and crossmatching and required bottles of blood should be reserved if needed to transfuse during the procedure.

Different Surgeries for Carcinoma Rectum

1. **Abdominoperineal resection** (A-P resection) (APR) wherein sigmoid, descending colon and upper rectum is mobilised per abdominally. Anal canal with perianal and perirectal tissues are dissected per anally. Retained colon is brought out as *end colostomy* in *left iliac fossa*.



Fig. 25-14: CT scan showing extent of carcinoma rectum. CT is useful to assess nodal status.



Fig. 25-15: MRI of rectum is useful to assess local infiltration.

APR—types
Miles—abdomen first, perineum later
Gabriel—perineum first, abdomen later
Lloyd-Davies—synchronised (together), (combined)

APR is done through lower midline incision in lithotomy position. Left-sided colon and entire rectum is mobilised from above. Rectum is mobilised posteriorly in avascular plane in front of nerve plane (hypogastric nerve) between mesorectum and sacrum. Inferior mesenteric artery is ligated high proximal (as lymphovascular ligation) at its origin or just beyond its first branch. Colon is transected and proximal cut end is fashioned for end colostomy in *left iliac fossa*. Through perineum, a purse string suture is placed around anal margin. Circumferential incision is placed around the anus. Dissection is deepened using scissor and cautery into the perineal body, coccyx, ischial tuberosity, ischiorectal fossa. First posterior and lateral dissections are undertaken until it reaches above. Lastly, anterior dissection is done to reach above and specimen is removed through perineal wound. Perineal wound is closed in layers often with a drain. Abdomen drain is placed. Colostomy is created by suturing skin to mucosa using silk. Colostomy done in left iliac fossa after APR. Colostomy care is important.

Complications of APR: Bleeding; infection of perineal wound; complications of colostomy like prolapse, stenosis, and infection; injury to urinary system, ureter, impotence, urinary incontinence. Operative mortality is less than 2%. *APR is the treatment of choice when mesorectum is involved or when it is poorly differentiated tumour or when nodes are involved.* It gives adequate clearance.

Sphincter saving APR with coloanal anastomosis: It is done in operable distal rectal tumour in young individual wherein within oncological principle anal sphincter need not be sacrificed but adequate oncological tumour clearance can be achieved. Here a permanent colostomy stoma is avoided. Approach is both abdominal and perineal. Initial dissection of rectal mobilisation is done from above; dissection of rectal mucosa from the anal sphincter at the level of dentate line and complete dissection of distal rectum is done through anal canal. Entire rectosigmoid is removed retaining only the anal sphincter. Colonic J pouch or coloplasty reservoir is created in the mobilised descending colon; coloanal anastomosis is done per anally using hand sutures under direct visualisation.

APR with neosphincter reconstruction is also occasionally sought; but technically difficult with complications.

Perineal colostomy is done with gracilis muscle wrap which is made to produce sphincter like muscle twitch using an implanted pacemaker.

2. **Anterior resection** (Abdominal radical restorative operation) is done in growths located in the mid and upper part of the rectum, which is well-differentiated, small-sized and with a clear adequate length for anastomosis after resection. *Anterior resection* is also called as *anterior proctosigmoidectomy* through *abdominal* approach wherein rectum *above* the peritoneal *reflection* is resected with colorectal anastomosis. *Low anterior resection (LAR)* is resection of rectum *below the peritoneal reflection* along with the sigmoid colon (as sigmoid should be removed due its precarious blood supply after dissection), with total mesorectal excision (TME) *through abdominal approach* (laparotomy) followed by *colorectal anastomosis* using *circular* stapler device (EEA stapler). Stoma should be inspected using proctoscope for integrity and when in doubt a covering temporary proximal colostomy should be done. LAR often leads to frequent small bowel movements causing more frequent stools called as *low anterior resection syndrome (LAR syndrome)/clustering*. It can be avoided by creating reservoir either by doing *colonic J pouch* or by doing *coloplasty* 6 cm from proximal divided end of colon (longitudinal colotomy between taeniae of 10 cm which is sutured horizontally).

Criteria for anterior resection—(Low anterior resection, LAR) are - Upper and middle third rectal growth; growth above the peritoneal reflection; well-differentiated tumour; < 4 cm size tumour; in females, growth 7 cm above the anal verge; T1 N0/T2 N0 tumour; Tumour without lymphatic or venous spread.

Advantages: It avoids permanent colostomy; sphincter is retained and so patient's acceptance is high **(Fig. 25-16)**.

Disadvantages: Uncertainty of clearance which is very important in cancer surgeries and so chances of local recurrence is high; anastomotic leak, infection; stenosis.

3. **Hartmann's operation (Henri Hartmann, 1923)** is an excellent palliative procedure—

It is done in elderly people who are not fit for major surgery like AP resection and also in locally advanced tumours. It is also done often in sigmoid diverticula with complications like abscess formation and sepsis. Here rectal growth is resected along with sigmoid colon and cut end of the rectum (rectal stump) is closed completely. Proximal colon is brought out as *end colostomy*. It is done as an emergency procedure wherein it is unsafe to perform a primary anastomosis and also due to insufficient length of the distal retained rectum it is also difficult to do mucus fistula. Midline laparotomy is done; sigmoid is mobilised similarly; ureter is safeguarded; vessels are ligated below the level of the left colic artery branch. Mesentery of sigmoid is divided. Distal dissection of the rectum is done just below the level of the peritoneal reflection. Rectum is resected using TA 55 linear stapler. Sigmoid is resected at its junction with descending colon; specimen is removed. Descending colon is mobilised to get adequate length for colostomy; extraperitoneal tunneling of the descending colon is not necessary as it is only temporary end colostomy. Drain is kept in the pelvis after thorough warm saline wash. Abdomen is closed. Complications are—burst abdomen; sepsis (pelvic abscess); rectal stump leakage; complications related to colostomy; haemorrhage; severe colitis; intestinal obstruction. As it is an emergency procedure



Fig. 25-16: Anterior resection for carcinoma upper rectum using stapler device.

got high mortality of 10-20%. Restoration of the continuity is done only after 3-6 months for benign conditions **(Figs 25-17A to C)**.

4. **Pelvic evisceration (Brunschwig's operation):** It is removal of rectum with the tumour, all the lymph nodes, urinary bladder, fat, fascia, uterus, vagina, with colostomy and urinary diversion. It is neither favourable nor popular.
5. **Palliative colostomy** is done in advanced unresectable growth which presents with intestinal obstruction.

ANTERIOR RESECTION/ABDOMINAL RADICAL RESTORATIVE OPERATION/ ANTERIOR PROCTOSIGMOIDECTOMY (OPEN METHOD)

It is called as anterior resection as dissection is done from above in front through laparotomy. It is done in rectal carcinoma wherein tumour is above, 6–14 cm from the anal verge; i.e. middle and upper thirds of the rectum. Anterior resection is done as sphincter saving procedure otherwise patient might have undergone abdominoperineal resection with a permanent end colostomy.

Presently anterior resection of the rectum has widened definition than the earlier one due to availability of the modern laparoscopic set up. Anterior resection may be ***high*** (anastomosis above the peritoneal reflection); ***low*** (anastomosis below the peritoneal reflection; ***ultra low*** (anastomosis within 2 cm of the dentate line with sphincter preservation). *Coloanal anastomosis as sphincter saving procedure* is done by anastomosing the colon to the dentate line or below it. Ultralow and coloanal types need laparoscopy for dissection and stapler for anastomosis. ***Low anterior resection (LAR)*** is commonly advocated either by open or through laparoscopy.


Growth
A
Carcinoma rectum (lower)
After A-P resection
B
Carcinoma upper rectum—anterior resection
Resected
C
Advanced carcinoma rectum—Hartmann's resection

Figs 25-17A to C: Surgeries for carcinoma rectum (A) A-P resection, (B) Anterior resection, (C) Hartmann's resection.

Preoperative evaluation and preparations are same—colonoscopy and biopsy; CEA; CT abdomen and pelvis to check nodal status and secondaries in liver; MRI pelvis to identify local infiltration; EUS is also very useful. Bowel preparation is done as similar for colonic diseases (please read in previous Chapter 24).

Technique

Position

Patient is kept in modified lithotomy position with steep head down at 40°. Surgeon stands on left side. One assistant stands on right side; another in between legs of the patient.

Incision

Lengthy midline incision is placed; abdominal cavity is explored for secondaries; self retaining retractor is placed.

Sigmoid Dissection

Small bowel is pushed upwards and kept away from the pelvis. Distal sigmoid may be occluded using a tape. Sigmoid colon is retracted medially. Peritoneum on the left lateral paracolic gutter is exposed; held between two haemostats and incised using scissor. Adhesions in this lower pat are common which are released carefully. Peritoneal incision on the lateral paracolic gutter is extended towards the splenic flexure. Left ureter, left gonadals are identified. Left ureter is dissected carefully and plastic loop is passed around it. Ureter is dissected carefully downwards using scissor and bipolar cautery down into the pelvis. Left hypogastric nerve in front of the internal iliac artery is identified and safeguarded. Sigmoid colon is retracted medially; incision is made on the right side of the sigmoid mesocolon. Dissection is done from bifurcation of the aorta downwards into the pelvis. Right ureter is also identified as it crosses the bifurcation of the common iliac artery in front of it. Right hypogastric nerve is identified now. Incision is made on the rectovesical or rectouterine pouch to mobilise the rectum from front. This also can be done at later period during rectal mobilisation.

Vascular Ligation

Colon is mobilised and held upwards and left with traction. Gonadal vein is separated. Inferior mesenteric artery originating from the front of the aorta is identified; fat and lymphatics (lymphovascular bundle) are swept towards the specimen colorectum; inferior mesenteric artery is divided 1.5 cm from its origin; it is also ligated and divided after it gives off left colic branch to maintain the adequate blood supply in the eventual anastomotic site which is essential. Preaortic sympathetic nerve should be retained.

Presacral Dissection

Sigmoid is retracted upwards and towards left to identify a tissue band between posterior aspect of the rectum. It should be divided using cautery as it contains branches of the middle sacral artery. Loose avascular areolar tissues on both sides of this band are identified. Dissection is continued in this avascular holy plane (*avascular plane of Heald)* using scissor; blunt dissection as it is tempted for will open the posterior endopelvic fascia to expose presacral veins which if get injured cause torrential haemorrhage. Slow gentle meticulous sharp dissection is better. Posterior presacral dissection is done down into the pelvis up to the coccyx. Ureter and hypogastric nerves are visualised again for safety. Laterally lateral ligaments are identified by stretching the rectum towards opposite side. Lateral ligament is dissected and divided using cautery with right angle forceps underneath. Once both lateral ligaments are divided, tough Waldeyer's fascia is seen extending from the coccyx to the posterior rectal wall which is divided with sharp dissection. If difficulty in ureter dissection is anticipated by imaging study then prior stenting of the ureter is better. If on table ureter is injured then it can be closed primarily with 4 zero vicryl interrupted sutures with a J stent inside or by ureteric reimplantation into the bladder or ureteroureterostomy to opposite ureter. If hypogastric nerve is infiltrated by tumour one nerve can be sacrificed.

Anterior Dissection of the Rectum

Anteriorly peritoneum in rectovesical/rectouterine fold is incised. Dissection is carried out downwards behind the prostate and seminal vesicles along the Denonvillier's fascia. Initially sharp dissection, then blunt and sharp dissection helps to separate this fascia and rectum from prostate and seminal vesicle. Rectal wall and tumour should not be breached to avoid tumour spillage and contamination of the field. Dissection in woman is between the uterus and rectum and posterior wall of the vagina and rectum. Bilateral salpingo-oophorectomy is often done by few surgeons in anticipation of spread of tumour from rectum to ovaries. It is not mandatory.

In low and ultralow anterior resection, Waldeyer fascia should be divided completely; Denonvillier's fascia in front should be dissected adequately beyond the apex of the prostate up to the urethra; laterally beyond the lateral ligaments down to the puborectalis, pubococcygeus proper and iliococcygeus (parts of levator ani). Dissection should not go beyond the puborectalis. All fat and lymphatics should be cleared up to this point. Distal tumour clearance in such patients will be only 1 cm which is oncologically sufficient.

In females, anterior dissection is done between vagina and rectal wall and Denonovilier's fascia is less developed in females; posterior to cervix and posterior fornix this fascia is vascular due to venous plexus. Cuff of the vagina may require to be excised to include with the specimen. Often, if tumour is infiltrating the cervix hysterectomy is done along with the procedure like in APR. Nervi erigentes curves anteriorly from sacral foramina to converge and join the presacral nerves and form *neurovascular bundle of Walsh* at 2 and 10 o'clock positions in the Denonvillier's fascia just behind the lateral edges of the seminal vesicles. This bundle controls both potency and bladder function.

If seminal vesicles are involved by tumour infiltration in rare occasion only they are also excised along with the specimen; in such situation, it is difficult to preserve nerves in Denonsvillier's fascia.

Extended anterior resection may be advocated. It means removal of the involved internal iliac nodes and lateral pelvic wall. Plane of dissection here is lateral to the anterior division of internal iliac vessels; so these vessels are ligated at their origin/joining.

Haemostasis

Presacral haemostasis is a must. It is usually venous bleeding which stops by pressure. Presacral venous tear may be torrential; it is controlled by gel foam, surgicel, bone wax, pressure, titanium thumbtack—titanium preloaded haemorrhage occlude pin with applicator, muscle fragment welding (rectus abdominis muscle piece is harvested and placed on the bleeding vein in the foramina and held with forceps and high coagulation current is passed to the muscle through the forceps), silastic tissue expander tamponade. Occasionally, need may arise to pack the presacral area with mops which are removed in 48 hours once control of haemorrhage is obtained.

Splenic Flexure Mobilisation

Adequate mobilisation of the splenic flexure is done to avoid tension at anastomotic site. Renocolic, splenocolic, pancreaticocolic and gastrocolic ligaments are divided to mobilise the splenic flexure; mobilisation should be done under vision and so adequate exposure through lengthy incision is ideal always. Colon is divided above the sigmoid level using an occlusion clamp; bleeding from the cut edges should be ensured; fat and appendices epliploicae are cleared off for 1 cm from the cut edge. Colonic wash with warm distilled water is also often used; it will be beneficial.

Division of the Rectum

After complete mobilisation of the rectum, mesorectal pedicle which runs on the posterior aspect of the rectal wall containing few blood vessels is ligated securely distal to the line of the division. Distal rectal stump is dissected to remove all fat and perirectal tissues so as to expose the longitudinal muscles. Rectum is divided 3 cm distal to the rectal tumour after applying curved crushing clamp proximal to line of division. Distally soft curved occlusion clamp may or may not be needed; often even if clamp is applied it tends to slip. Distal rectal stump is irrigated with warm ½ to 1 litre of sterile warm water or warm dilute povidone iodine solution. There should be adequate bleeding from the cut edge of the rectum. Specimen is retrieved. Specimen and lymph nodes should be marked. Line of resection distally taken as 3 cm is sufficient; even 1-3 cm is adequate enough as it is proved that microscopic mural spread beyond the palpable lower edge of the tumour is very rare.

In low and ultralow anterior resection (open method), resection at lower end of the tumour on the rectal stump is difficult. Strong right angle clamp is placed 1-2 cm dial to the tumour after thorough irrigation of the rectum per anally using warm distilled water. Small incision is made distal to the clamp on the anterior surface of the rectum; polypropylene 1 zero continuous suture bites are taken from the distal cut edge with 5 mm gap with 5 mm thickness; sequentially rectum is cut part by part and suturing is continued as *whip stitch* until entire rectum is transected beyond the clamp to retrieve the specimen. Frozen section biopsy from distal end should be done ideally. One should remember that it is not possible to take circumferential stitches around the stump after transection of the rectum in open method. Stapler should be used for anastomosis. J pouch may be done if surgeon is well versed with technique in ultralow resections.

Anastomosis

It is achieved usually as end to end two layer or one layer anastomosis. 3 zero or 2 zero silk or vicryl is used. In single layer anastomosis interrupted silk sutures are used. In two layer, outer silk and inner vicryl or silk interrupted sutures are used. Full thickness horizontal mattress sutures also can be placed. If there is discrepancy between colonic end and rectal stump (rectal ampulla is wider often 6 cm or more) then side to end anastomosis can be done to correct the discrepancy (Baker). Circular stapling anastomosis can also be done. Rectal stump can be transected using linear stapler and also the proximal colonic resection site. Anvil is passed to the proximal colonic end and fixed using polypropylene purse string sutures; circular stapler is passed per anally across the distal rectal stump; if linear stapler is not used then circular stapling end is fixed to rectal stump using similar purse string sutures. Anvil is connected to the circular stapler and is fired. Stapler with anvil is removed with completion of the colorectal anastomosis. Doughnut should be observed for adequacy. Fat should be cleared for 1.5 cm in both ends prior to stapler anastomosis as fat interposition can cause disruption and leak. Blood vessels adjacent to bowel wall near cut edge should be ligated or fulgurated properly otherwise after stapling troublesome bleeding can occur.

Closure

Pelvic peritoneum should not be closed. Large Foley's catheter is passed per anally towards the anastomotic site; pelvis is filled with warm distilled water; air is infused through the Foley's catheter to check the leak from the anastomotic site by seeing the air bubbles; if present additional silk sutures may be needed. Suction tube drain is placed into the pelvis and abdomen is closed in layers. Usually covering proximal colostomy is not needed as bowel is already been prepared as an elective surgery. If there is lot of contamination in the field or if it is very low anterior resection, then diversion colostomy should be done.

Post-operative Care

Nasogastric tube is removed in 5 days; drain is removed in 5-7 days. Foley's catheter from the urinary bladder is removed in 7 days. Oral fluid is started in 5 days. Observation for leak, sepsis, should be done.

Complications

Injury to ureter: If it occurs it should be sutured on table using 4 zero vicryl interrupted sutures with a J stent within. Ureteric reimplantation to the urinary bladder or ureteroureterostomy are other options.

Haemorrhage from pelvic presacral veins can be dangerous; surgicel, bone wax, packing are the options. Blood transfusions are required.

Pelvis abscess formation or pelvic infection or pelvic irritation is common. Fever with chills, lower abdomen pain, tenesmus, tenderness on gentle rectal examination, raised total count are the features. US may show abscess. CT is confirmative. CT guided percutaneous drainage, posterior colpotomy and drainage may be needed. If still persists then open drainage with diversion colostomy is needed. As already there is a anastomotic site per rectal drainage is impossible.

Sexual dysfunction in males if nerves in the pelvis are injured. Use of excessive monopolar cautery in posterior dissection may cause nerve injury; so judicious use of monopolar cautery or use of bipolar cautery or harmonic scalpel (open, focus) is better.

Bladder dysfunction is common in males which is usually mild and subsides gradually.

Anastomotic leak due to disruption can occur. It needs diversion proximal colostomy.

Stenosis at anastomotic site is not uncommon. Sigmoidoscopy confirms it. It should be differentiated from recurrence and so needs biopsy in suspected cases. Dilatation is sufficient usually; occasionally resurgery is required.

Abdominal wound infection, wound dehiscence and incisional hernia also can occur.

ABDOMINOPERINEAL RESECTION (APR)

Abdominoperineal resection (APR) is based on the concept that lymphatics spread from the rectum occure upwards, laterally and downwards and so entire field is removed. In 1908, *West Ernest Miles* did first APR. Presently APR is done if LAR (Low Anterior Resection) is not possible or in invasive rectal cancers **(Fig. 25-18)**.

Abdominal Part

Initial evaluation, abdominal phase of surgery are same as in anterior resection described above. Urinary catheter, nasogastric tube, steep head down low wide lithotomy position under epidural/general anaesthesia - are the preliminary steps. Incision is midline with umbilical curve towards left/colostomy site is in left iliac fossa **(Fig. 25-19)**.



Fig. 25-18: Extent of resection and citation of colostomy in APR.


APR - incision - midline with umbilical curve towards right
Marked colostomy site
Closed anal canal
with purse string suture using no.1 silk

Fig. 25-19: Midline incision with umbilical curve towards right side; colostomy site should be marked. Anal canal should be closed using no 1 silk with purse string suture.

Extent of resection is above the sigmoid below the left colic artery level. Peritoneum in the left paracolic gutter is incised and extended proximally across the sigmoid mesentery; below it is extended into the pelvis; left ureter is identified. Peritoneum on the right side is incised and sigmoid is retracted towards left; upward it is dissected up to the sacral promontory and aortic bifurcation. Right ureter is identified and preserved. Inferior mesenteric vessels are ligated and divided. IMA is ligated after the origin of the left colic artery. Sigmoid mesentery is dissected up to the colon margin. Presacral dissection is done in similar fashion like low anterior resection. Lateral ligaments are divided. Anterior dissection is done by incising the rectovesical peritoneal fold. It is extended downwards behind the prostate and seminal vesicle up to the membranous urethra in males and up to posterior fornix in females. In females, vaginal cuff may be removed; or hysterectomy can be done if needed. Further, dissection to complete the division of the entire lateral ligaments downwards facilitates to achieve the mobility of entire rectal tube. Levator ani muscle on both sides should be visualised to complete the abdominal part. Colon is resected after deciding the line of resection. Distal part is tied with an umbilical tape or roller gauze if stapler transection is not done. Proximal part is left for colostomy with an occlusion clamp.

Perineal Part of the Surgery

Purse string suture is placed using no 1 silk suture using cutting needle around the anus so as to close the aperture. Elliptical incision is made beginning 3 cm in front of the anus extending posteriorly towards the coccyx. Incised skin is held with Allis' forceps with purse string silk suture; dissection is carried out in the posterior plane in front of the coccyx. Coccyx can be excised if needed. Inferior haemorrhoidal arteries are identified, ligated and divided. Anococcygeal ligament is visualised and divided using cautery or scissor. Waldeyer's dense condensed fascia extending between the lower rectum and the lower presacral and precoccygeal region is divided using cautery. Often this fascia is divided from above through abdominal approach. Levator ani muscle is divided on either side to reach the abdominal pelvic area after incising the peritoneum there. Lateral dissection is done upwards by giving traction on the specimen towards the opposite side.

Lastly, anterior perineal dissection is done; lower edge of the transverse peronei muscle is identified; plane below it is dissected which is a natural plane separating rectum and urinary system. Incision on the anterior aspect is deepened to reach the apex of the prostate. Plane behind the prostate is dissected; rectourethralis muscle is transected to reach the peritoneal cavity behind the urinary bladder. As dissection is completed, all around specimen is removed. In females, dissection between vagina and rectum is done; if tumour is closer then cuff of the vagina adjacent to tumour is also removed. If vaginal cuff is not removed then during dissection blood supply to vagina should be retained otherwise it will cause perineo vaginal fistula which may persist for long time.

Closure of the perineal wound—all bleeders are cauterized. Wound is washed with warm distilled water and warm saline. Two suction drains one on each side is placed; deeper vicryl sutures are placed. In case wound is contaminated with faecal matter thorough wash is given; deeper vicryl sutures are placed and external wound is kept open. This wound is dressed regularly and allowed to granulate and heal on its own.

Many surgeons use prone jackknife position for perineal surgery, which is said to be better, but not popular. Here once abdominal part is entirely completed with closure and creation of colostomy, patient's position is changed to prone position for perineal part of the dissection **(Fig. 25-20)**.



Fig. 25-20: Specimen of carcinoma rectum after APR.

Creation of Colostomy

Colostomy is created as end one in the left iliac fossa on the rectus muscle. A circular piece of skin is excised. Anterior rectus sheath is excised; muscle is split; peritoneum is opened to bring the end of the colon outwards. It can be brought out extraperitoneally to prevent herniation. Seromuscular suture bites are taken from the colon 5 cm proximal to cut margin which is also passed through the peritoneum and rectus sheath; interrupted vicryl sutures are placed. After closure of the abdominal wound, maturation of the colostomy is done by trimming the end if there is stapler line and suturing the full thickness edge of the colon to the skin using interrupted silk sutures.

Closure

Pelvic peritoneum is irrigated. Pelvic peritoneum can be closed in APR if it is amenable for closure. Usually, there is no need to place the drain into the peritoneal cavity. If pelvic cavity is not sutured and kept open (can be kept open without suturing also) then abdominal drain may be needed. Omentum is brought out lateral to the colostomy part of the colon towards the pelvis to fill the free space. It also absorbs fluid, prevents sepsis and supports urinary bladder. Alternatively if omentum is not adequate then absorbable mesh of large size can be sutured to posterior and lateral abdominal wall without injuring the ureters. In females uterus if not removed will fall retroverted and fill the pelvic cavity. Few surgeons do the caecal mobilisation so as to allow it to drop into the pelvic cavity to fill the space. Abdomen is closed in layers. Pelvis is already drained from below.

Colostomy care: Immediate care is given by doing irrigation daily with one litre warm saline to the proximal colon through colostomy. It is to distend the proximal colon so as to produce reflex peristalsis to empty the entire colon; so patient should feel colicky pain after saline infusion. Infusion is done through a tube, which should be gentle otherwise perforation may occur.

Postoperative Care

Nasogastric tube can be removed in 24 hours. Usually, colostomy starts functioning early. Oral feeding can be started in 48 hours. Perineal drain is removed in 7 days. Urinary catheter is removed in 7-10 days.

Colostomy bag is placed and colostomy care should be given. Colostomy site should be observed for mucosal necrosis; hence, initially transparent bags are used to visualise the mucosa easily. Perineal suture is removed in 14 days. *Sitz bath* to the perineal wound helps in faster healing of the wound.

Complications

Bleeding during abdominal dissection due to presacral vein or dissection; bleeding from perineal wound can occur from inferior haemorrhoidal vessels and branches of the internal iliac vessels.

Injury to ureter during abdominal and presacral dissection can occur. Urethral injury can occur while dissecting the rectum in front either from above or from below.

Small bowel adhesions can occur onto the pelvic suture line; or herniation of the small bowel across the pelvis leading into *intestinal obstruction* can occur. Colostomy in such situation will not function. Contrast CT is useful to confirm the obstruction. Initially it is treated conservatively; if patient is not responding then laparotomy may be needed.

Infection—wound infection, pelvic infection, septicaemia and urinary infection can develop after abdominoperineal resection **(Fig. 25-21)**.



Fig. 25-21: Wound infection after APR.

Bladder dysfunction is very common due to lack of pelvic support to urinary bladder. *Sexual impotence* is common after APR due to nerve damage (>50%).

Colostomy complications can develop—necrosis, retraction, prolapsed, parastomal hernia.

Problem in healing of the perineal wound—wound may partially heal by forming a chronic sinus. Wound healing may be delayed often. Persistent discharging sinus can occur; it will last for years often; it needs exploration of the sinus, excision of the sinus with coccyx; once it granulates well split skin graft is placed on the raw area.

LAPAROSCOPIC ABDOMINOPERINEAL RESECTION

First laparoscopic APR was done by Sackier in 1991. Laparoscopic abdominoperineal resection with formation of the colostomy is commonly done. Here abdominal part dissection is easier under direct vision; perineal dissection is same as in open. It is technically easier compared to laparoscopic anterior resection as anastomosis is not done **(Fig. 25-22)**.



Fig. 25-22: Laparoscopic APR. Colostomy is in left iliac fossa.

Present indication for laparoscopic APR—tumours within one cm of the anal verge; invasive rectal cancers.

Contraindications—perforated or obstructed tumours; severe obesity; previous pelvic surgeries. Tumours invading the bladder, pelvic wall, uterus needs open approach.

Patient position, trocar placements are same as described in laparoscopic low anterior resection. But here dissection is done much more distally beyond the levator ani posteriorly and up to proximal urethra beyond the apex of prostate anteriorly.

Laparoscopic USG is better to confirm the operability and to rule out any possible metastases in liver, nodes and retroperitoneum.

Abdominal part of the technique is same as laparoscopic anterior resection. Perineal part is same as perineal part of the open APR.

Steps in Laparoscopic APR

Proper positioning—lithotomy with steep head down; proper port placement

↓

Release of adhesions; in women elevation of uterus towards abdominal wall using silk sutures

↓

Holding the sigmoid up and left

↓

Opening the mesocolon adjacent to sacral promontory and dissecting upwards

↓

Identification of left ureter and gonadals; dissection should not be too anterior and too posterior

↓

Ligation of inferior mesenteric artery after dissection beyond the origin of the left colic artery.

↓

Division of IMA is done using ligatures, endovascular stapler, clipping, ligasure.

↓

Division of the inferior mesenteric vein at the lower border of the pancreas.

↓

Splenic flexure mobilisation is not necessary but paracolic gutter along the line of Toldt needs to be incised.

↓

Medial to lateral dissection of the sigmoid mesocolon up to the colon margin.

↓

Ureter, gonadals on both sides are preserved.

↓

Posterior presacral dissection along the avascular holy plane of the Heald which is identified by loose areolar tissue; in front endopelvic fascia is present enveloping the mesorectum; behind presacral pelvic (parietal) fascia will be present which should not be breached to avoid injury to presacral veins and hypogastric nerves (one on each side).

↓

Sharp dissection is done with division of Waldeyer fascia to identify the levator ani.

↓

Lateral ligaments are divided between mesorectum and the autonomic nerves using harmonic scalpel; mesorectum should not be breached and autonomic nerves should not be injured.

↓

Mobilisation in front between the anterior rectal wall mesorectum and prostate and seminal vesicles along and in front of the Denonvillier's fascia beyond the prostate apex to urethra up to the pelvic floor; in females anterior dissection is done between vagina and rectal wall and Denonvilier's fascia is less developed in females; posterior to cervix and posterior fornix this fascia is vascular due to venous plexus. Cuff of the vagina may require to be excised to include with the specimen. Often, if tumour is infiltrating the cervix hysterectomy is done along with APR (like in open). Nervi erigentes curves anteriorly from sacral foramina to converge and join the presacral nerves and form *neurovascular bundle of Walsh* at 2 and 10 o'clock positions in the Denonvillier's fascia just behind the lateral edges of the seminal vesicles. This bundle controls both potency and bladder function.

↓

Sigmoid is divided along the proposed line of resection using linear stapler.

↓

Perineal procedure—elliptical skin incision; dissection in front of coccyx; division of anococcygeal ligament; division of levator ani on both sides; division of superficial transverse muscles in front; then puborectalis and rectourethralis muscles.

↓

Retrieval of specimen through perineal wound.

↓

Suction tube drains are placed on both sides of the perineal wound; levator on both sides are approximated using vicryl in front of the coccyx; skin is closed using interrupted sutures.

↓

Pneumoperitoneum is recreated; proximal cut end of the colon is observed to rule out any twist and kept ready for colostomy; pelvic floor is visualised for any bleeding; omentum is brought into the pelvic cavity which minimises the fluid collection and so sepsis; it supports the urinary bladder in front in males so as to reduce residual urine; it prevents the small bowel adhesions also.

↓

Creation of the terminal permanent colostomy.

LAPAROSCOPIC LOW ANTERIOR RESECTION (LAR)

Indication: Rectosigmoid and rectal growth 4 cm proximal to the dentate line. In LAR resection is done 2 cm above the dentate line. Presently high, low, ultralow anterior resections can be done through laparoscopy with expertise.

Advantages: Magnification, better visualisation, better dissection, preservation of the nerves, easier dissection through the avascular holy plane of Heald; better haemostasis, faster recovery.

Problems: Learning curve, need for modern equipments and cost, time consuming, inability to feel the tumour.

Preparation: Colonoscopic confirmation with biopsy is done. CT abdomen and pelvis is done to see nodal status, liver secondaries and local invasion. Carcino embryonic antigen (CEA) is done as a base line level for later follow up. Patient is prepared using polyethylene glycol or sodium phytate solutions 12 hours prior to surgery. Oral aminoglycoside and metronidazole may be given as bowel antiseptic.

Anaesthesia: General anaesthesia is used. Perineal scrub cleaning is done properly.

Position: Low lithotomy position with steep head down like for laparoscopic hysterectomy to make small bowel to settle in proximal abdomen. Cleaning and draping is done. Left side of the patient is raised to allow small bowel to fall out of the pelvis.

Surgeon stands on right side. Camera surgeon stands on left side of the surgeon; scrub nurse in between legs; first assistant on the left side of the patient near left shoulder to hold the colon using bowel grasper. Monitor is placed on the left side near foot end.

A 10-mm umbilical port is used for 30° telescope. *5 mm port is placed in midclavicular line on right side*. 10 mm port is placed at right iliac fossa 2.5 cm medial and above the anterior superior iliac spine. This port later requires to be converted to 12 mm port to pass *articulating endo stapler* to staple the low rectum. Additional 5 mm port is later required in midline just above the symphysis while mobilising the splenic flexure.

After pneumoperitoneum, with assistant holding and pulling sigmoid upwards and towards left (through left upper 5 mm port); surgeon does dissection through two working ports—right 5 mm upper port and right 10 mm lower port; medial side of the mesocolon is incised from below upwards from left rectovesical/rectovaginal peritoneal reflection extending proximally across the sacral promontory upwards towards inferior mesenteric artery (IMA) origin. Left ureter and left gonadal vessels are identified and dissected off the posterior peritoneum. Sympathetic nerve at the level of the sacral promontory is preserved. IMA near its origin (usually after it gives left colic branch in case of carcinoma rectum) is clipped/ligated and divided using ligaseal or harmonic scalpel. Dissection further towards left visualises Gerota's fascia covering the left kidney.

Colour of Gerota's fascia is more deep yellow than the surrounding fat. Incision is further extended upwards towards the duodenojejunal flexure. Inferior mesenteric vein is identified close to the ascending branch of left colic artery at the lower border of the pancreas which is double clipped and divided. Accessory left colic artery when present should be preserved carefully.

Now it is better if surgeon shifts his position in between legs of the patient to do mobilisation of the splenic flexure of the colon. Right lower and suprapubic ports are used for splenic flexure mobilisation. Dissection begins at the left paracolic gutter extending upwards towards splenic flexure; renocolic, splenocolic, gastrocolic and pancreaticocolic ligaments are incised. Splenic flexure is mobilised from left kidney, spleen and pancreas. It can be done from left side towards right or from middle level of transverse colon by dividing gastrocolic omentum towards left using harmonic scalpel.

Once splenic flexure is mobilised, surgeon again shifts his position towards right with working ports on right upper and lower area.

A 30° camera is placed on the right 10 mm port to visualise the pelvis for pelvic dissection. Plane of dissection is in a potential space between parietal and viscera pelvic fascia, which is avascular. Incised peritoneum on the sacral promontory is extended downwards on the right side of the rectum towards pelvis. Superior hypogastric plexus and two hypogastric nerves are identified and preserved. Peritoneum is incised on the left side and in front like U on the rectovesical or rectouterine fold. Dissection is continued in this *avascular holy plane of Heald* down towards the levator in front of the parietal pelvic fascia to clear the mesorectum. Levators are clearly seen now; midline raphe and Waldeyer fascia, which is strong and condensed is divided using harmonic scalpel. Mesorectum should be removed up to the levator ani.

Lateral mobilisation is done by dividing the lateral ligaments on both sides close to the rectum. It contains middle rectal vessels. Medial part of the autonomic plexus and branches passes through the lateral ligament. These nerves should be preserved.

Anterior mobilisation is done along the Denonvillier's fascia behind the prostatic capsule up to the apex of the prostate. Mesorectum also should be cleared.

At the end circumferential dissection is done to achieve fully mobilised rectal tube. Fat and fascia of the rectal tube is removed to achieve complete denudation and muscularisation. This is essential step prior to stapler application. Cautery should not be used as it may injure the rectal wall; sharp dissection should be done; mucosa should not be breached. Rectal examination and proctoscopy can be done to assess the completion of the mobilisation.

Using *roticulating stapler* rectum is transected. Per anally warm distilled water wash is given to the rectum. This needs conversion of 10 mm port into 12 mm port (of suprapubic port). If this is not available then small Pfannenstiel incision (5 cm) made through which conventional linear stapler is used to divide the rectum. Tumour distal margin is felt for clearance. Bowel is brought out of the wound and specimen is removed after placing a sterile plastic sheath in the abdominal wound to prevent contamination and tumour spillage on the abdominal wound **(Fig. 25-23)**.



Fig. 25-23: Roticulating stapler is used to transect the rectum.

Transected proximal colon is prepared for anvil of the circular cartridge placement. After positioning the anvil, using 2 zero polypropylene purse string suture is placed around it through the cut edge of the colon. Colon with anvil is dropped into the peritoneum carefully without allowing the rotation. Circular stapler cartridge is passed through the anus carefully gently towards rectal stump and is perforated just adjacent to the stapler line in the middle; cartridge is locked to the anvil using two instruments. While locking the instrument care should be taken not to interpose other structures. It is done by counter clockwise movement of the shaft of the stapler. Stapler is fired through circular anastomosis. One minute after firing stapler is released by clockwise movement with careful rotation.

Pelvis is filled with warm distilled water and Foley's catheter is passed per anally; air is infused to check the air bubble leak in the pelvis. After completion, tension in the anastomotic site is assessed. Tube drain is placed through one of the 10 mm ports. Diversion colostomy is done if needed.

TOTAL PROCTOCOLECTOMY WITH ILEOANAL POUCH

It is removal of entire colon and rectum with creation of ileal distal pouch and doing ileoanal anastomosis.

Indications

Ulcerative colitis; indeterminate colitis; familial adenomatous polyposis, multiple sessile polyps, synchronous multicentric carcinomas.

Contraindications

Crohn's disease is a contraindication as terminal ileum is involved now or later ileum may get involved after anastomosis leading into failure of the treatment.

Preoperative Preparation

Preoperative planning is essential. Colonoscopy, biopsy, marking of stoma, mechanical bowel preparation, nasogastric tube and urethral catheter placement and rectal washes with normal saline is done.

Total Colectomy

Lithotomy with head down with lengthy midline incision is used under general anaesthesia. Mobilisation is same as combinations of right and left colectomies with proctectomy. Right paracolic gutter is incised and right colon is mobilised from lateral to medial approach unless malignancy is confirmed or suspected wherein dissection is done from medial to lateral. Right ureter, gonadals, duodenum, SMA, SMV are carefully preserved after dissection. *Vessels are ligated either close to colon wall.* Once ileocolic artery is ligated terminal ileum is supplied by jejunal branches of SMA; arcade should be kept intact. Left side is mobilised from sigmoid towards the splenic flexure. Splenic flexure including transverse colon is mobilised fully. Sigmoid is mobilised; vessels are ligated securely using ligatures; clips can be used.

Proctectomy

Proctectomy (Excision of the entire rectum) is done in same way as abdominal part of APR. Both ureters and hypogastric nerves with autonomic plexus are retained carefully. Presacral dissection is done in avascular holy plane of Heald which is identified by loose areolar tissue. One should not open posterior presacral fascia to avoid injury to presacral veins and nervi erigentes. Waldeyer fascia is divided. Lateral dissection is done by dividing the lateral ligaments; autonomic nerve plexus are close to it; one should avoid injuring it. Anterior dissection is done behind the Denonvillier's fascial plane; behind prostate and seminal vesicles. Neurovascular bundle of Walsh at 2 and 10 O'clock positions. Posterior dissection is done up to levator ani muscles. Entire rectal tube is mobilised. Distal small length of the mucosa if retained needs anorectal mucosectomy prior to doing hand sewn ileoanal anastomosis. Distal rectum is transected. Entire colorectum is removed after transecting the ileum very close to the caecum between soft occlusion clamps retaining its blood supply.

Mobilisation of the Small Bowel for Adequate Length

Small bowel mesentery is mobilised up to the 3rd part of the duodenum and inferior border of the pancreas. If still mobilisation is needed, then all peritoneal tissues are cleared from right of the superior mesenteric vessels. Using transillumination, superior mesenteric vessels and arcade should be identified for preservation. Small tiny 1 cm transverse incisions are made carefully on the peritoneum overlying the superior mesenteric vessels and also Kocherisation of the duodenum will also be helpful.

Construction of Ileal Pouch

Different pouches are used. J, S, W, H are different types. S pouch is easier to reach to the anal canal (more than 3-4 cm better than J pouch). J pouch is easier to construct. Possibility to tension free pouch should be confirmed prior to construction of the pouch. Pouch plan is done; proposed apex is held with Babcock's forceps which is pushed down towards the anal canal; finger is placed in the anal canal to feel the Babcock's tip easily without tension confirming that pouch is tension free. A point in the ileum 20 cm from the cut end if brought down 6 cm beyond the pubic symphysis, it is said that tension free pouch is possible. Pouch is created either by hand sewn or by stapler. Interrupted or continuous inner full thickness vicryl sutures and outer seromuscular interrupted silk sutures are used to create the pouch after doing enterotomy on the antimesenteric border. Stapler can be used to create pouch. 15 cm each limb (total of 30 cm of terminal ileum) J pouch is created. Pouch should be checked for leak proof by infusing saline into the pouch. Apex of the pouch is opened; saline filled syringe is passed through this enterotomy and pushed to check for leak. Syringe is removed. Anvil of the circular stapler is passed into the pouch through the enterotomy and purse string suture is placed using 2 zero polypropylene sutures **(Fig. 25-24)**.



Fig. 25-24: Different pouches are used – J, S, W,H.

Ileal Pouch Anal Anastomosis

When stapler is used, anastomosis is achieved at anorectal ring at the top of the anal column; here anal sensory epithelium is retained and anastomosis is tension free as it is higher level than hand sewn. Stapled anastomosis at further lower level is not possible as it will damage the internal sphincter. Stapled type is easy to do; less infective complications, functionally better. But there is potential malignant transformation in transitional zone (4-5%). So, whenever biopsy report shows dysplasia then mucosectomy with hand sewn anastomosis should be done. Cartridge is passed into the anal canal; rectal stump is already stapled during transection; cartridge is punctured through rectal stump and is locked with anvil of the pouch; stapler is fired to achieve the anastomosis. Stapler is removed; doughnut is checked. Sphincter should not be included in the stapler; posterior vaginal wall should not be included to avoid formation of pouch-vaginal fistula. Apex of the J pouch or end of the S pouch is used.

When *mucosectomy* is needed in patients with dysplasia, rectum is transected just above the levator ani; mucosa is stripped off the muscular layer of the rectum from dentate line up to the anorectal ring/levator ani. Ferguson anal retractor is needed for this purpose. 10-20 mL of 1 in 2,00,000 units of adrenaline solution is used to raise the mucosa from the muscle layer. Every parts of the mucosa should be removed carefully and gently. Frozen section biopsy of the excised mucosa is a must to rule out carcinoma and Crohn's disease. Cautery is used to control bleeding. CUSA can be used to do mucosectomy. Mucosectomy is better achieved in prone Jackknife position. Sullivan and Garnjobst in 1982 started to do mucosectomy prior to abdominal procedure in prone position. Mucosectomy is done from dentate line upwards for 4-6 cm in a tubular fashion **(Fig. 25-25)**.

Pouch is brought down towards anal canal and is anastomosed to anal canal. Hand sewn anastomosis is technically difficult and demanding. Ileal pouch end is brought down into the anus after mucosectomy. Bivalved Park's retractor is of great help for this. Two Gelpi retractors one at right angles to each other are also very useful. 4 zero vicryl interrupted sutures are taken. Bites should take few fibres of underlying internal sphincter muscle

Covering Diversion Loop Ileostomy

Covering diversion loop ileostomy is done 20 cm proximal to the pouch which should not have any tension. Routinely diversion should be done as usually patients are on high dose of steroid, malnourished, toxic, anaemic. In selected patients restorative proctocolectomy with



Fig. 25-25: Construction of ileal pouch and placing anvil in the pouch.

ileal pouch anal anastomosis is done without any diversion ileostomy. Transanal pouch (32 French) catheter is placed often for 5 days.

Posto-perative Care

Ileostomy created is usually of high output that drains about 1 to 2 litres of liquid causing severe dehydration and electrolyte imbalance. One should avoid hot weather, exercise, high fibre diet; plenty of oral fluids should be taken. Loperamide orally is useful to reduce the pouch output. Steroid if patient is on; it should be tapered gradually under observation. Antibiotics, correction of nutrition and anaemia are needed depending on the individual patients.

Complications

Usual complications are anastomotic leak, stricture, recurrent pain, diarrhoea, perianal ulceration, perianal infection, pelvic abscess formation, irritable pouch syndrome.

Pouchitis is a specified complication in ileal pouch surgeries. In pouchitis patient presents with acute diarrhoea, urgency, rectal bleed, suprapubic pain. Pouchitis disease activity index is often used to assess the severity of the pouchitis—by features, endoscopy and biopsy. Local steroid, mesalamine are useful. If persists then pouch excision and permanent ileostomy should be done.

Cuffitis, cuff abscess if inadequate mucosectomy is done.

Technical complications like injury to ureter, bleeding, impotence, sepsis, intestinal obstruction can occur.

Faecal incontinence is another distressing problem.

TREATMENT FOR RECTAL PROLAPSE

Treatment for Partial Prolapse

The nutrition of the child is improved and digital repositioning is tried. *Correction of constipation* is important **(Fig. 25-26)**.

Submucosal injections of 10 mL of 5% phenol in almond oil or ethanolamine oleate is given into the apex of the prolapse under general anaesthesia so as to create an aseptic inflammation leading to tethering of mucosa to the underlying muscular coat. Injection can also be given at the base or both at the apex and base. Alternatively, 30 mL of tetracycline or oxytetracycline or hypertonic saline injection can also be used. Initial injection is supported by



Fig. 25-26: Partial rectal prolapse.

Thiersch wiring using (temporary) chromic catgut until adhesion occurs between the mucosa and muscular layer (in 3 weeks). In adults, injection therapy is tried for partial prolapse, results are not as good as in children.

Thiersch wiring alone is tried with good success rate in children.

Goodsall's operation is excision of the prolapsed mucosa at its base, usually in three positions. Stapled transanal rectal resection surgery *(STARR)* is also often used **(Fig. 25-27)**.



Fig. 25-27: Goodsall's ligature for partial prolapse. Prolapsed mucosa is ligated at different positions using nonabsorbable suture material often with double needled. Usually, it is done for one side in three portions.

Treatment for Complete Prolapse

Principles

Surgery is done to *control* the prolapse; to *restore* continence; to *prevent* constipation **(Fig. 25-28)**.



Fig. 25-28: Complete rectal prolapse.

In young males, abdominal repair should be avoided as it injures pelvic nerves leading to sexual impotency. So perineal approach is better.

Rectopexy is fixing the rectum to sacrum by sutures or mesh after complete mobilisation of the rectum. Laparoscopic rectopexy using polypropylene mesh and sutures gives good result and has become very popular.

Delorme's operation is better option in young individual with complete prolapse. In elderly perineal proctectomy with anterior and posterior reefing of the sphincter muscle is the accepted method now. It is similar to Altemeier technique (It is perineal rectosigmoidectomy). Here entire prolapsed rectum and redundant sigmoid is resected through perineum prior to reefing of the sphincter. Anal encircling surgeries using synthetic wires/mesh/suture materials are limited to extremely ill patients and elderly who will not withstand perineal proctectomy. *Choice of procedure* depends on age, sex, operative risk, pelvic floor defect, degree of incontinence, history of constipation.

Colonoscopy, defaecating proctography, bowel preparation, nasogastric tube, urinary catheterisation and perioperative antibiotics are needed in preoperative preparation.

Procedures for repair of rectal prolapse

Perineal Operations	*Abdominal Operations: Open/ Laparoscopic*
• Mucosal sleeve resection (Delorme) • Perineal rectosigmoidectomy (Altemeier) • Posterior fixation of the rectum of Lockhart-Mummery • Wyatt operation • Mickulicz Miles perineal transanal rectosigmoidectomy/amputation of prolapse • Anal encircling (Thiersch)	• Suture rectopexy – Goligher, Lahaut, Devadhar, Rosoe Graham • Prosthetic or mesh rectopexy – Anterior/posterior – Ripstein, Well's • Resection rectopexy – Muir's • Anterior resection • Lahaut's operation

Surgery—Types

Abdominal Procedures

Laparoscopic Rectopexy

It is ideal and good approach to fix the rectum to sacrum. *Laparoscopic posterior mesh rectopexy (**LPMR**)* is the procedure done. Prior colonoscopy and bowel preparation is needed using exelyte or Peglec. Head down, low lithotomy position is needed. Ports placement is same as for anterior resection or APR. 10 mm umbilical camera port; 10 right lower pararectus right hand working port; 5 mm left lower pararectus left hand working port; 5 mm left lumbar port for traction to the sigmoid colon; another extra 5 mm suprapubic port in female patients to fix the uterus **(Fig. 25-29)**.

Sigmoid colon is held with left sided port. Surgeon does dissection from right side. Peritoneum on the right of the rectum is opened from sacral promontory downwards to reach avascular holy plane of Heald which is identified by typical presence of loose areolar tissue. Care should be taken to avoid injury to autonomic nerves, ureters. Dissection is extended down as posterior mobilisation into the pelvis with adequate mobilisation of the rectum. Lateral peritoneal reflection on left side is incised and is dissected to connect on both sides of the mesorectum. Left ureter is preserved. Presacral mobilisation is done below up to levator ani muscle. Lateral ligaments are either divided



Fig. 25-29: Ports placement for laparoscopic rectal prolapse.

or left alone. It is divided usually in elderly; it is preserved in young individuals unless there is a need to correct undue redundancy of the rectum. *Anterior mobilisation* is also important. Anterior mobilisation along the Denonvillier's fascia is done 5 cm below the peritoneal reflection. 15 × 10 cm polypropylene mesh is placed in the presacral space deep to rectum, which is fixed to presacral fascia along the sacrum and sacral promontory. Mesh is also sutured to rectal wall on both sides using interrupted polypropylene sutures to create a mesh wrap around the mobilised rectum. Only partial wrapping of mesh is done. This partial wrap corrects the prolapse completely without incontinence and constipation. Partial wrap may be ½ or 2/3rd or 3/4th one. Peritoneum is closed using vicryl to extraperitonealise the mesh. Many advocate laparoscopic mobilisation and fixation of mobilised rectum to sacral promontory using polypropylene sutures without mesh.

Laparoscopic sigmoid resection and rectopexy (Laparoscopic resection rectopexy, LRR) is done when there is rectal prolapse with constipation, with excess redundant sigmoid colon with kinking. Here complete resection of the sigmoid colon is done with colorectal stapled anastomosis. Suture rectoplexy is done by suturing the rectal wall to the mesorectum and the presacral fascia below the level of the sacral promontory. Usually three interrupted sutures are placed. Often fixation between lateral ligaments and sacral promontory is also done. Sigmoidoscopy is done to check the anastomosis. In LRR mesh should not be used as field may be contaminated during resection.

Well's (Britain, 1959) Operation

Polyvinyl alcohol sponge is wrapped around the mobilised rectum posteriorly (from behind) and is fixed to sacrum. Infection, fistula formation is high. Polypropylene mesh is used as a modification now instead of polyvinyl sponge; wrapping is only partially done to reduce the incidence of constipation. But this Ivalon sponge is not approved in USA FDA. Teflon (poly carbon fluoride) and polypropylene mesh are commonly used now. Patient under general or epidural anaesthesia is placed supine head down position. After midline laparotomy, small bowel is pushed and packed upwards. Peritoneum on both sides of the rectosigmoid is incised 5 cm above the pelvic brim one after the other. Both ureters are identified and protected. At the sacral promontory posterior peritoneum is incised; avascular presacral holy plane of Heald is identified by the presence of loose areolar tissue. Dissection is done in this plane. Anteriorly mesorectum should not be disturbed and posteriorly presacral fascia should not be breached to avoid injuring the presacral veins and nerves. Dissection is done using cautery and scissor up to the coccyx. Tougher Waldeyer fascia behind the lower rectum and coccyx is also divided. Anterior dissection is done carefully up to distal part of the seminal vesicles. Care should be taken not to injure the neurovascular bundle of Walsh at 2 and 10 o'clock positions. Lateral ligament if needed should be divided to avoid the redundancy. Full mobilisation is essential to avoid redundancy and so recurrence. Proper haemostasis is achieved. Ivalon sponge used is 22 × 10 cm size × 3 mm thickness, which is fixed to presacral fascia using three interrupted 2 zero polypropylene sutures posteriorly. All three sutures are taken first then sutures are moved deep down into the pelvis to tie knots. 3/4th circumference of the rectum is encircled by the sponge and is fixed on both sides to the rectal wall using three interrupted 3 zero polypropylene sutures. Pelvic peritoneum is closed using continuous vicryl sutures to extraperitonealise the sponge. Now polypropylene mesh (6 × 4) is used **(Fig. 25-30)**.

Ripstein Operation (Charles Benjamin Ripstein, Canada, 1965)

After mobilisation of the rectum, 5 cm width Teflon mesh sling is passed around the rectum from front to fix it behind to fascia 5 cm below and in front of the sacral promontory. Sling is also fixed in front and laterally to rectum. As anterior fixation is dangerous, this procedure is not advocated now **(Fig. 25-31)**.

Suture Rectopexy

Rectum is mobilised fully; rectum is secured to sacral fascia or bone using interrupted nonabsorbable sutures. It is simple, easy to undertake with high success rate; but causes evacuation disturbances, constipation and obstruction **(Fig. 25-32)**.

Goligher's Operation

Rectum is entirely mobilised up to anorectal ring and its posterior muscular layer is fixed to presacral fascia using interrupted polypropylene sutures.

Devadhar Rectal Plication

Through abdominal approach, junction between thicker lower part and thinner upper part of the intussusception is identified. A purse



Fig. 25-30: Well's Ivalon sponge repair—posterior repair.


Mobilised rectum
Sacrum
Anterior Teflon mesh sling (Marlex / Goretex) fixed to sacrum

Fig. 25-31: Ripstein repair—anterior repair.



Fig. 25-32: Suture rectopexy.

string suture using silk is placed in front and laterally; further 3-4 interrupted submucosal Lembert sutures are placed to create reverse intussusception.

Lahaut's Operation

Rectosigmoid is mobilised fully; mobilised loop of rectosigmoid is passed in front through posterior rectus sheath behind the rectus muscle; extraperitonealisation is done to pull the rectus forward to prevent descent.

Rosoe Graham Operation

After mobilisation of the rectum, levator muscles are exposed and sutured in front of the rectum along with removal of pouch of Douglas.

Dumphy Operation

It is done through combined abdominoperineal approach with perineal rectosigmoidectomy. Both procedures control prolapse well but not incontinence.

Muir Low Anterior Resection

In a redundant rectosigmoid with prolapse, rectosigmoid resection is done; excision of redundant pouch of Douglas is done; rectum is fixed to sacrum behind.

Nigro Teflon Halter Operation

It is suspension of the rectum through intra-abdominal sling approach from pubis around the mobilised rectum using 4 × 20 cm mesh sling middle part of the mesh is sutured to rectal wall using interrupted sutures. Pubic rami are dissected in space of Retzius. Each end of the mesh is sutured to pubic ramus on each side to suspend the rectum.

Orr (1947) Fascia Lata Sling Suspension

Fascia lata sling is taken from lateral part of the thigh; it is sutured to wall of the rectums and sacrum with interrupted sutures on both sides after complete mobilisation of the rectum. Nylon is used by many instead of fascia lata for similar suspension.

Complications of Abdominal Procedures

Intraoperative—presacral bleeding, nerve plexus injury, injury to ureter.

Post-operative—Intestinal obstruction, adhesions, faecal impaction, fistula formation, mesh erosion, recurrence, stricture formation. Constipation rate is more if lateral ligaments are divided; if slings are placed anteriorly also along with posterior slings. Pelvic abscess is common especially in Well's operation which can be prevented by proper bowel preparation prior to surgery. Once abscess forms, Ivalon sponge or mesh has to be removed. Preoperative antibiotics are used to prevent this complication.

Perineal Procedures

Delorme's operation (Mucosal sleeve resection and rectal muscle plication, Edmond Delorme, French surgeon, 1900;)

After prior bowel preparation, under spinal anaesthesia, in lithotomy position, completely prolapsed rectum is held with Babcock's forceps. 1 in 2,00,000 adrenaline solution is injected into the submucosal plane of the rectum to cause haemostasis. Rectum is pulled down to create complete prolapse and held using Babcock's forceps at the apex. A circumferential incision is made 1-2 cm away from dentate line; often additional longitudinal incisions may be needed in oedematous friable mucosa. Dissection is done with sharp scissor and cautery; mucosa is stripped off from the deeper muscular layer from 1-2 cm below the anal margin (1-2 cm proximal to dentate line in nonprolapsed position) to the apex of the prolapsed rectum. This 1-2 cm gap is needed to preserve the anorectal sensation. Tubular mucosa is held down with traction; this stripped sleeve can be resected at apex now or later placing plication sutures on the muscular layer; it is better to keep if it is not friable as it helps in giving traction to the rectum while placing plication sutures. Muscular layer of rectum is plicated using absorbable vicryl 2 zero interrupted sutures all around; approximately 12-15 plication stitches are needed. These sutures are tied after finishing the passage of all sutures. Cut end of the mucosa of the apex is sutured to anal margin using interrupted vicryl sutures. It is technically easier **(Fig. 25-33)**.



Figs 25-33(1)



Fig. 25-33(2)



Fig. 25-33(3)



Fig. 25-33(4)



Fig. 25-33(5)



Fig. 25-33(6)



Figs 25-33(7)

Figs 25-33(1 to 7): Delorme's procedure for rectal prolapse.

Complications: It causes alteration in rectoanal inhibitory reflex, complete loss of rectal reservoir function, incontinence may persist and recurrence chance is high. Abscess in plicated segment can occur. Occasionally stricture can develop.

Perineal Posterior Fixation of the Rectum of Lockhart-Mummery

Retrorectal space is dissected through perineal approach and posterior rectal wall is sutured to sacrum and coccyx, additionally placing a retrorectal gauze pack to stimulate adhesions.

Wyatt Operation

Through perineal post-anal approach, dissected retrorectal space is placed with a Marlex/mersilene mesh which is sutured high to the sacral promontory and rectal wall laterally.

Mickulicz Miles Perineal Transanal Rectosigmoidectomy/ Amputation of Prolapse

Prolapsed rectum is excised and sigmoid is sutured to the anal margin.

Altemeier's Perineal Rectosigmoidectomy (1952)

After rectosigmoidectomy, colonic anastomosis and pelvic floor is supported by suturing puborectalis muscle in front of the rectum using nonabsorbable sutures.

Rectum is fully prolapsed and held with Babcock's forceps. 1:2,00,000 adrenaline is injected to the submucosal plane. Circumferential incision is made 1.5 cm away from the dentate line; first on the posterior surface then on the anterior surface. All the layers of the rectal wall is incised to its full thickness. Perirectal fat is identified between two outer and inner rectal tubes. Inner rectal wall is not incised. Mesorectum between two tubes is identified. Mesorectum is carefully ligated using two ligatures proximally sequentially at proximal level. Peritoneal cul de sac of sliding hernia is identified and opened. Bowel contents inside peritoneal cavity is pushed upwards; further ligation, division and mobilisation of the mesorectum and mesosigmoid is done. Hernial sac is closed with absorbable vicryl sutures. Levator ani is sutured posteriorly using 2-3 interrupted 2 zero polypropylene sutures to achieve levatorplasty; often anterior levatorplasty is also done. Sigmoid on its anterior part is cut and is sutured to the anal canal above the level of pectinate line to preserve columns of Morgagni; preservation of columns of Morgagni retains the fine anal continence and reduces the chances of anal stricture formation after surgery. Once anterior part of sigmoid colon is cut and sutured (using 3 zero vicryl) only then posterior part of the sigmoid colon is cut and sutured to anal canal. This avoids retraction of the cut part of the sigmoid proximally. Anastomosis can also be done using circular stapler.

Complications are—bleeding, anastomotic dehiscence, sepsis, anal stenosis, which may require regular dilatation.

Gant-Miwa Operation (1920, Japan)

Placement of 30-40 absorbable interrupted sutures incorporate the mucosa and submucosa from the apex of the prolapse 1 cm above the dentate line with each at 5 mm apart; with anal encirclement. It has got 15% recurrence rate.

Anal Encircling

In 1891, Thiersch did anal encircling using silver wire to provoke inflammatory fibrosis as well as to give mechanical support to the anal orifice—*Thiersch wiring*. It is done under local anaesthesia. Two small incisions are made at lateral parts or anterior and posterior parts of the anal canal. Submucosal tunnel is created using a curved haemostat. Silver wire is passed around deeper to these incisions and tied after placing the *index finger* into the anal canal. Wire can be removed after 12 months. Polypropylene, nylon are the other materials that can be used. Ribbon shaped prosthetic mesh also can be used. Procedure leads into partial closure and narrowing of the anal canal. *Temporary wiring* along with Goodsall's ligature or injection sclerotherapy using thick catgut are often advocated. *Complications*: Pain due to wire erosion, infection, faecal impaction, incarceration, rectal prolapse, recurrence (80%).

Supralevator high encirclement of anal orifice (of Notaras) is done above the level of levator muscles by placing Teflon or nylon ribbons through anterior and posterior incisions. It gives better support and will not cut through. *Thoralsksen* modified this by placing plastic/mersilene tape around the bowel high up.

Complications of rectal prolapse surgery

- Injury to hypogastric nerve causing impotence.
- Bladder dysfunction.
- Bleeding from presacral venous plexus.
- Injury to rectum and colon causing faecal fistula.
- Constipation after rectopexy is a known complication.
- Recurrence of prolapse.
- Incontinence persists in 50% of cases post-operatively.
- Infection—proctitis/pelvic abscess.

TREATMENT OF PILONIDAL SINUS

Pilonidal sinus may consists of primary and secondary sinuses. It is common in hairy people. Tuft of hairs in the track is common presentation **(Figs 25-34 and 25-35)**.

In Acute Phase Initially

Drainage of the abscess is done and antibiotics are given; later definitive treatment is undertaken.





Fig. 25-34: Primary and secondary pilonidal sinus tracks.



Fig. 25-35: Tuft of hairs in pilonidal sinus track.

Definitive Treatment

Excision

In prone position (*jackknife* position, i.e. prone with buttocks elevated) excision and primary closure is done under general anaesthesia or local anaesthesia. All sinus tracks, unhealthy granulation tissues with hairs are removed completely. Methylene blue is injected to demonstrate the multiple tracks properly. Excision and skin grafting—has got high recurrence rate **(Figs 25-36 and 25-37)**.

Excision with Z Plasty

It shows good result. Excision with multiple Z plasty is said to be better but technically difficult **(Figs 25-38 and 25-39)**.

Karydakis Excision

It is done through a semilateral incision and lateralised suturing of the wound away from the midline, gives good result. In prone position with buttocks strapped outwards, paramedian vertically elliptical incision of 5 cm length 2 cm from the midline is placed; edges of the ellipse should be symmetrical; elliptical skin, fat and deep fascia is excised. Medial part of the ellipse will cross the midline to include all midline primary sinuses. Medial flap of the incision is raised for 2 cm further towards midline and opposite side and all fat and deep fascia under the entire length of the medial flap is excised. Haemostasis is maintained. Suction drain is placed. Buttock straps should be released prior to wound closure. Pressure dressing is placed. Subcutaneous tissue and skin are closed. Sutured wound will lie away from newly formed midline **(Fig. 25-40)**.

Rhomboid Flap

Excision with closure using *Limberg (Rhomboid) buttock flap* (single or double rhomboid flaps)—good result. Under general or local anaesthesia, in prone position with buttocks strapped outwards to table using wide plaster after cleaning and draping, rectangular (rhomboid) tissue of full thickness skin and subcutaneous fat is excised including the midline with its long axis in the midline. Angles of rhomboid should be 60º and 120º. Angles are adjusted meticulously as shown in the pictures; flaps are elevated, rotated and


Sinus
Strp
Strapping in pilonidal sinus surgery is essential
Strapping is released after dissection prior to suturing
Methylene blue injection to the sinus track

Fig. 25-36: Pilonidal sinus—operative jackknife position; making incision for the same.



Fig. 25-37: Excision and primary suturing of the pilonidal sinus. It has got high recurrence rate as scar formed here is in the midline.


Defect
'Z' plasty

Fig. 25-38: Incision and mobilisation for Z plasty.

sutured using 3 zero polypropylene or polyethylene. While elevating the flap monopolar cautery should be avoided or used only with care; bipolar cautery is better. No. 15 blade or fine scissor is always better to retain the blood supply of the flap. Suction drain is placed underneath. Buttock straps should be released before suturing. Subcutaneous absorbable sutures are placed. First sutures should be placed over the angles other sutures. Pressure dressing is placed **(Figs 25-41 to 25-43)**.

Bascom Technique

It is the excision of the pilonidal sinus through lateral approach—is a good method. Through a lateral incision or multiple small lateral


Position of the patient
Prone - Jackknife position
Incision for excision and Z plasty
Anus
Pilonidal sinus

Figs 25-39(1)


Pilonidal sinus track excision
Suction drain tube
Stay suture
Stay suture

Figs 25-39(2)



Figs 25-39(3)

Figs 25-39(1 to 3): Technique (Steps) in 'Z' plasty—done for pilonidal sinus. It gives good result. Multiple Z plasties are also used.


Strapping should be removed
while suturing after excision
Strap using wide plaster
Strap using wide plaster

Fig. 25-40: Karydakis excision.


Strap using wide plaster
Strapping should be removed while suturing

Fig. 25-41: Limberg-rhomboid flap used for pilonidal sinus.



Figs 25-42(1)





Figs 25-42(2)

Figs 25-42(1 and 2): Rhomboid flap for pilonidal sinus.



Fig. 25-43: Rhomboid flap after healing—scar will not be in midline.

incisions 2-4 mm sized sinus is approached and pus is drained; hairs are removed with only minimal excision of sinus. Cavity walls are not excised. Lateral small wounds are either sutured or left open for spontaneous healing. Procedure is done under general/local anaesthesia in prone Jackknife position. After cleaning and draping, small pits in the midline primary site are approached through tiny 3 mm diamond incisions and skin is excised. A probe is passed through one of these opened pits to identify the side towards which sinus tracks. A vertical 3 cm incision is made in the paramedian area deep enough to reach the sinus cavity. All unhealthy tissues including track and hairs are removed. Thorough wash is given. Fibrofatty flap is rotated towards midline. In modified Bascom technique this rotation is not done. Tiny diamond midline wounds are closed with subcuticular non-absorbable sutures. Lateral wound is left open to granulate on its own **(Fig. 25-44)**.

V-Y Gluteal Advancement Flap

V-Y gluteal advancement flap is useful in recurrent and wide area involvement.

Lahey and Cattell's Method

Lahey and Cattell's relaxing skin incisions on one buttock is done to relieve tension on main wound sutures with later closure of secondary wounds by sutures or advancement.



Fig. 25-44: Bascom technique.

Davies and Starr Buttock Skin Flap Rotation

Davies and Starr buttock skin flap rotation into the defect and secondary defect is closed at a later period.

After complete excision of entire sinus, wound is left open to granulate and heal by epithelialisation with regular dressings.

Buie's Marsupialisation

Buie's marsupialisation of the sinus track, 1944—after making incision on the sinus track, edge of the laid opened area is sutured to the skin edge all round using silk or vicryl. This reduces healing time and promotes healing.

Lord and Millar's Limited Excision

Lord and Millar's limited excision of primary track for 0.5 cm depth with removal of tuft of hairs, debris and unhealthy granulation tissue using tiny brush and nylon bristle.

Excision with Primary Suturing

Excision with primary suturing is done only when disease is confined to midline; but creating a midline scar increases the chances of recurrence as hairs can penetrate midline scar easily.

Excision of all Granulation Tissues

Excision of all granulation and unhealthy tissues from both primary and secondary sinuses with *deroofing* and allowing it granulate and heal by secondary intention. It is better than primary closure. Problem is healing takes 6-8 weeks and creates wide scar which can breakdown. Present principle is to avoid any midline scar in pilonidal sinus surgery.

Injection of Phenol to the Track

Injection of phenol to the track destroys the epithelium after removal of the tufted hairs. Phenol is allowed to be in contact with epithelium for 3 minutes to create a blanch in the track orifice.

Nonoperative Treatment/Prevention of Recurrence after Surgery

Regular shaving of natal cleft to have meticulous hair control and proper perineal hygiene is essential. *Laser, depilatory cream, electrolysis* are other methods used.



Fig. 25-45 (1)



Fig. 25-45: Parts of piles—internal and external.

Causes for High Recurrence Rate

Improper removal (technical); overlooking of existing diverticulum; entry of new tuft of hairs; breakage of scar. *Note*: Condition has got high recurrence rate (20%).

TREATMENT OF HAEMORRHOIDS

Parts of piles—pedicle (internal) and external component **(Fig. 25-45)**.

Preventive Therapeutic/Curative

Preventive	*Parasurgical*
Diet – more fibre/liquid Laxatives	• Sclerotherapy • Banding • Cryotherapy • Infrared coagulation (IRC) • Laser therapy • Doppler Guided Haemorrhoidal Artery Ligation (DGHAL)
Medical	*Surgical*
Local applications; Sitz bath, diet, laxatives, drugs – analgesics	• Open haemorrhoidectomy • Closed haemorrhoidectomy • Stapled haemorrhoidopexy • Anal stretching – Recamier, Lord's

Non-operative

Sitz bath—means the patient has to sit in warm water with the anal region dipped in water for 20 minutes, 2-3 times a day. This reduces the oedema, pain and promotes healing. Specialised toilet trays are available which can be placed over the commode on which patient can sit for Sitz bath **(Fig. 25-46)**.



Fig. 25-46: Sitz bath.

Local applications to reduce pain, itching and oedema can be used. Antibiotics, laxatives, anti-inflammatory drugs are beneficial. Other different methods are—Fibre diet 35 gram/day, plenty of water; *Fibre alternatives* can be used to supplement a high-fibre diet; squatting position may reduce the incidence of piles; plenty of liquid intake; l*axatives* such as lactulose solution which soften bowel motions and relieve the constipation (bulk-forming agents, e.g. ispaghula husk, sterculia, methylcellulose); bulk laxatives such as psyllium mucilloid, Konsyl or polycarbophil may be necessary.

In Case of Inflamed, Permanently Prolapsed, Oedematous Piles

Initially, manual stretching of the anal canal sphincter is tried. In 1968, Lord proposed that increased anal pressure contributes the formation of the haemorrhoids; so dilatation of the anal reduces the anal pressure thereby controls the haemorrhoids. A constriction to the outlet is present in 3rd and 4th degree haemorrhoids which is relieved by gentle firm stretching of the lower rectum and anal canal until constriction disappears. Eight fingers are passed as high as possible to achieve this. This prevents congestion of anal cushions and relaxes the anal sphincter, as a result of which the prolapsed piles gets reduced—*Lord's dilatation (8 fingers)*. Once oedema subsides, in 1-2 weeks, formal procedure is done. **Complications of anal dilatation—** Incontinence—rectal—usually temporary; infection; haemorrhage/haematoma; prolapse rectum **(Fig. 25-47)**.

Note: Lord's dilatation is presently not accepted.



Fig. 25-47: Lord's dilatation – it is 8 finger dilatation of the anal canal; it may cause anal incontinence.

Injection-Sclerosant Therapy

It is done in first degree and early second degree piles (internal)—outpatient procedure. Using proctoscope and Gabriel syringe, 3-5 mL of 5% phenol in almond oil is injected into the submucosal plane just above the anorectal ring to the pedicle. All three piles can be injected separately—3-5 mL to each site in single sitting. Technique can be repeated after 6 weeks. This technique is not done in the presence of sepsis or prolapse. The drug causes fibrosis in the submucosal region (sclerosis leading to mucosal fixation on to deeper planes and occlusion of lakes) and thereby fixation of the anal cushions which do not prolapse, causes strengthening of the vessel wall and obliteration of the vessel lumen. It is quick and painless; gives 95% cure rate in first degree piles; done on OP basis. *Contraindications are*—thrombosed/prolapsed piles, presence of proctitis/fissure/fistula-in-ano, pregnancy and diabetes mellitus. Sclerotherapy has not gained popularity, oily solution is difficult to handle and inject. *Complications*—recurrence (15%), hypochondriac pain due to entry of drug into the portal system, tenesmus, mucosal sloughing/ulceration, submucosal abscess, anal canal pain, anal stricture.

Inadvertent deep injection can precipitate pelvic abscess, prostatitis, impotence, rectovaginal fistula **(Fig. 25-48)**.

Rubber Band Ligation/Banding

It is done for second degree piles. It causes ischaemic necrosis and piles fall off. At one time only two piles can be banded. Repeat banding can be done only after 3 weeks. Band should be placed 2 cm above the dentate line. Usually 2 bands are used for pile mass to take care of breakage. Tissue sloughs off in 1-2 weeks leaving an ulcer which heals by scarring. Equipment is inexpensive, simple to perform; done without anaesthesia on OP basis; results are consistent, stops bleeding and tackles the prolapsing anal cushion. Different Band ligators are available now. Barron's (1962), McGivney ligator, McGown one hand ligator, etc. **(Fig. 25-49)**.

It is contraindicated in fissure/fistula/proctitis.

Complications: If applied low into skin it causes severe pain; discomfort; secondary haemorrhage; ulceration; thrombosis; slippage; sepsis.



Fig. 25-48: Gabriel syringe—It is used for injection sclerotherapy for internal piles using 5% phenol in almond/olive oil (almond/vegetable oil acts as a vehicle which holds phenol for long period of action). It is a stainless steel syringe with two metallic finger brims near the proximal end. One more metallic finger brim is present on the proximal end of the piston to place thumb while injecting.



Fig. 25-49: Rubber band ligation instrument for first and early second degree piles.

Note:

Suction banding is used presently—Lurz Goltner suction ligator; O'Regan disposable suction banding system. Suction is used to suck the internal pile into the banding gun.

Cryosurgery

Using nitrous oxide (–98°) or liquid nitrogen (–196°), extreme cold temperature is used to coagulate and cause necrosis of piles which gets separated and falls off subsequently. It is relatively painless and can be done on OP basis. All masses can be tackled at one sitting. This is carried out with the help of a *cryoprobe*. Nitrous oxide is preferred since it produces adequate freezing. Nitrous oxide delivery system/cryoprobe does not require special rewarming circuit. Liquid nitrogen produces quick destruction and damage of sphincter muscle; also needs special rewarming circuit for its release and is costlier. Under lithotomy position, cryoprobe is applied in the longitudinal axis of internal pile above the dentate line; the pressure must be maintained above 700 lb continuously; rapid adhesion with freezing (white area formation on piles) occurs; traction and slight rotation in both directions is done to draw entire pile mass to come in contact with the probe; after entire tissue is frozen in 20-30 seconds, the probe is detached after warming (defrosting/thawing). Procedure is repeated on other pile masses **(Figs 25-50 and 25-51)**.



Fig. 25-50: Cryosurgery instrument set up for cryohaemorrhoidectomy.


Grooved proctoscope

Fig. 25-51: Cryosurgery for piles.

Advantages: It is reasonably painless, simple, safe, can be done on OP basis, with less bleeding.

Disadvantages: It causes *profuse watery discharge*, itching,pain if skin is frozen; marked oedema of adjacent skin, incontinence occasionally.

Infrared Coagulation

Here heat is used to burn the piles so as to allow it to fall off. Pulses of infrared radiation are applied through a handheld applicator. The specific infrared wavelengths produce chemical changes that cause blood coagulation within the haemorrhoid itself, which causes the haemorrhoid to seal, shrivel, shrink or slough off. Source of infrared rays of 14 volt Wolfram halogen lamp with a gold plated reflector rays are transmitted from fibre optic cable, which terminates in a probe or pistol for coagulation. In left lateral position, the probe is applied at the base of pedicle above the dentate line and bursts are given in clover leaf fashion. Timer is set at 2 secs giving a depth of 2 mm; total time taken is 2-5 minutes. It is done in first, second and third degree piles. It produces a discrete area of necrosis (coagulates tissue proteins and evaporates water from the cells), which heals to form a scar; reduces or eliminates blood flow through the haemorrhoid thereby shrinking it and mucosa becomes fixed to the underlying tissue. Often 3 or 4 sittings are needed at 1 month intervals. It does not cause noncontact coagulation; does not cause interference with electromagnetic devices such as pacemakers. It is *contraindicated* in external pile, proctitis. Long-term results are not good. Equipment is expensive; multiple sessions are needed.

Laser Therapy for Piles

It is used for third degree piles. Nd-YAG, diode and carbon dioxide lasers can be used but are expensive and tedious. The intense beam of light interacts with tissue and can be used to cut, coagulate or ablate the tissue, seal off nerves and tiny blood vessels. By sealing superficial nerve endings patients have minimum post-operative discomfort. Laser is used for dissecting and excising pile masses. It is done for internal haemorrhoids.

Advantages—less operative time; less intraoperative and post-operative bleed and pain; rapid healing; quick recovery; done under LA/SA; less complications; minimal pain, constipation and urinary retention.

Disadvantages—needs skill; sphincter should be taken care of; non-contact burning can occur; secondary haemorrhage can occur due to heat tissue destruction; and also injury to sphincter can occur **(Fig. 25-52)**.

Doppler Guided Haemorrhoidal Artery Ligation (DGHAL, Morinaga, 1995)

The DGHAL is an advanced instrument that works under Doppler guided ultrasound. It is painless, 20-minute procedure that cures all degrees of haemorrhoids. It causes choking and blocking of the blood supply of piles. It is done using proctoscope with an incorporated Doppler probe (modified proctoscope with built in ultrasound transducer, light and special window echo sounder). This proctoscope is inserted and used to locate the haemorrhoidal arteries by an audible signal. Once located, a needle holder is inserted into the lumen of the proctoscope and the artery ligated with a 'figure of eight' absorbable suture into the submucosa. The procedure is repeated until no more Doppler signals are identified. It is the transanal dearterialisation technique.

Advantages: Anaesthesia is not needed; blood loss, pain, residual problems are minimal; done as day care surgery; early return for work; may be safe in diabetic, cardiac, old age patients, and in pregnancy. It is under trial and too early to confirm the efficacy.

Ultroid

It is monopolar, low voltage device having a generator unit, an attachable handle, single use sterile probes, a grounding pad, nonconductive anoscope. Device acts by production of sodium hydroxide at the negative electrode. Probe tip is placed at the apex of the pile mass above the dentate line and amperage of 6-16 mA is passed. Probe is kept in position for 10 minutes until sound ceases. Only one pile mass is treated during one sitting. Technique is not popular.

Stapled Haemorrhoidopexy (Antonio Longo, 1998)

It is circumferential excision of the mucosa and sub-mucosa 4 cm above the dentate line using circular haemorrhoidal stapler passed per anally (MIPH—minimally invasive procedure for haemorrhoids; PPH—Procedure for Prolapse and Haemorrhoids). It is not called as stapled haemorrhoidectomy as neither anal mucosa nor haemorrhoidal tissues are removed.

Advantages are—it is less painful; less blood loss; faster recovery; short hospital stay and equally efficacious. It is done only for prolapsed piles **(Fig. 25-53)**.

This procedure avoids wound in the sensitive perianal skin thereby reducing the post-operative pain. Under spinal or general anaesthesia, circular anal dilator is passed (CAD 33) into the anal canal; it is anchored to skin; circular purse string suture anoscope is passed into the anal canal. It can be rotated so the purse string suture can be placed 4 cm above dentate line on the rectal mucosa. Small bites which are close together are taken from mucosa and submucosa; muscle layer should not be included in the bites. There should not be any gaps or dog ears in the purse string suture. Fully opened stapler head is inserted into the anal canal and through the purse string beyond it; purse string is tied with one throw knot; two tiles of the suture is passed through the lateral channels in the head of the anvil with the suture threader. External knotting of the suture tails is done. Stapler is closed completely and fired with continuous downwards traction on the purse string suture. Using stapling gun, a unique circular stapler which reduces the degree of prolapsed piles by excising a circumferential strip of mucosa from the proximal anal canal. The strip of mucosa and submucosa is excised circumferentially above the dentate line. The veins leading to the haemorrhoids are thus incorporated in this excision. Activation of the gun also simultaneously recovers the cut mucosa and submucosa by stapling the edges together.

Disadvantages: Need for experience, as it is advanced surgical skill; costlier; may cause a full-thickness excision of the rectal wall; may injure the anal sphincter. *Improper purse string* can cause incomplete doughnut leading to severe haemorrhage.

Contraindication: Associated anorectal disease like fissure, fistula in ano; full thickness complete rectal prolapse; anal stenosis; gangrene and abscess, acute thrombosis.



Fig. 25-52: Laser surgery for piles.

***Note*:**

Doughnut should be *sent for histology* for muscular layer; proper doughnut should not contain muscular layer.

Open Operative Methods: Still Gold Standard

Indications

Third degree piles; failure of nonoperative methods; fibrosed piles.

Haemorrhoidectomy is the best treatment for haemorrhoids. The haemorrhoidectomy is performed using an open or closed technique. The open technique is commonly used in UK and is known as *Milligan-Morgan operation*. The *closed technique (Hill Ferguson)* is more popular in USA. Both involve ligation and excision of the haemorrhoid, but in the open technique the anal mucosa and skin are left open to heal by second intention, and in the close technique, the wound is sutured. Efficacy of surgery is 95% with 2-5% recurrence rate **(Figs 25-54 and 25-55)**.

Methods

Ligation and excision of piles—commonly done procedures *(Milligan-Morgan) (Open method).*

Under anaesthesia, in lithotomy position (Few advocate initially sphincter dilatation/stretching to reduce the post-operative pain. But it is not necessary). Skin (V shaped), adjacent anal mucosal strip



Fig. 25-53: Stapled haemorrhoidopexy. It is minimally invasive procedure for haemorrhoids. It is high mucosal rim excision including vascular pedicles using circular (single use) staplers. It is done for prolapsed piles.



Fig. 25-54: Holding pile mass for haemorrhoidectomy.





Fig. 25-55: Holding the pile and incising the skin – 'V' cut.

with haemorrhoidal plexus underneath (i.e. entire haemorrhoidal complex) is excised. Preliminary proctoscopy is a must and sigmoidoscopy should be done when in doubt. Later skin is held with Allis or artery forceps forceps, internal pile (mucosal component) is held with artery forceps **(Fig. 25-56)**.

Skin is cut in "V' shaped manner using curved scissor or diathermy (cutting monopolar); entire skin edge has to be incised across the anoderm up to the anal mucosa; incision is deepened; bleeding is common while dissecting in the deeper plane which usually stops on its own but often may require bipolar cautery and internal sphincter is separated and pushed up. Pedicle is dissected from the internal



Fig. 25-56: Transfixation of the pile mass.

sphincter so the only haemorrhoidal plexus with mucosa is present in the pedicle base. Pedicle is transfixed with vicryl or catgut and distal part is excised. All the three piles can be dealt in a single sitting. Instead of transfixing the haemorrhoidal pedicle base it is divided after proper fulguration using cautery **(Figs 25-57 and 25-58)**.

Wound is not sutured but left open. Adequate bridges of the skin, anoderm and mucosa are retained; it prevents anal stenosis. Pack is placed (pack can be avoided if bleeding is controlled using bipolar cautery). Here haemorrhoid is excised radially. Dressing and 'T' bandage is applied. Post-operatively**,** *Sitz bath*, antibiotics, laxatives, analgesics, local applications are given. Pack should be removed in 12 hours. Often few finger dilatation of the anal canal is required to prevent stenosis. In the Hill – Ferguson method – procedure is similar but after completion, skin edges of the each pile mass is sutured using absorbable sutures (3 zero vicryl).

Submucosal Haemorrhoidectomy of 'Parks'

Approach here is above the skin through submucosal plane. Radial incision is made along the haemorrhoidal complex proximally along



Fig. 25-57: Cautery can be used carefully for fulgurating pedicle and also to make skin incision.


Lithotomy position
Cleaning and draping
Digital examination
V shaped incision

Figs 25-58(1)


Internal sphincter
Pedicle

Figs 25-58(2)


Vicryl transfixation

Figs 25-58(3)


Packing is not always necessary
Pack should be removed in 8–12 hours
'T' bandage

Figs 25-58(4)

Figs 25-58(1 to 4): During haemorrhoidectomy, skin part is held with Allis forceps; internal pedicle is held with artery forceps. A 'V' cut is placed over the outer skin up to mucocutaneous junction. Dissection is deepened to visualise the internal sphincter. Once pedicle is dissected, it is transfixed using vicryl suture material. Distal tissue is excised. Technique is repeated on other sites also.

the anoderm and anal mucosa; dissection is deepened to separate internal sphincter; pedicle is transfixed and ligated using 2 zero vicryl. Incision edges are partially sutured back using 3 zero vicryl. There is no tissue loss and so stricture will not occur; but external component and redundant mucosa is not addressed and so this procedure has not become popular **(Fig. 25-59)**.

Hill-Ferguson Closed Method

Here patient in prone position, under general/caudal anaesthesia, retraction is done using Hill-Ferguson retractor. Incision is made around pile mass, pedicle is dissected to its proximal base; it is ligated with transfixation using 2 zero vicryl or silk; mucosa and anal skin is sutured using 3 zero vicryl/dexon after proper haemostasis using cautery.

Whitehead (Whitehead, England, 1882) Haemorrhoidectomy

Here mucosa is sutured to the anal canal above the pectinate line through a circumferential incision. It is technically difficult, causes mucosal ectropion (wet anus, Whitehead deformity). Procedure is rarely done now.

Management of Strangulated/Thrombosed/ Gangrenous Piles

Here initially conservative treatment is done using warm water Sitz bath; antibiotics; elevation; bed rest; saline compression dressing; analgesics. This reduces the oedema and piles shrink. Later in 15-20 days haemorrhoidectomy is done. Doing haemorrhoidectomy immediately may precipitate portal pyaemia, bleeding and also increases risk of developing anal stricture **(Fig. 25-60)**.

Newer Methods

Using ultrasound or controlled electric energy (Harmonic scalpel or ligasure or laser), haemorrhoidectomy can be done with less post-operative pain. But tissue charring may precipitate secondary haemorrhage. Sentinel pile often requires excision under local anaesthesia **(Figs 25-61 and 25-62)**.

Post-procedure Complications

Pain—due to spasm, nerve irritation, muscle injury; retention of urine—commonest—50%.

Reactionary or secondary haemorrhage—secondary haemorrhage is more problematic as infected friable granulation tissues will bleed torrentially and it is not possible to cauterize or ligate the bed; blood transfusions is often required; antibiotics, inflating the balloon of a 30 French Foley's catheter inside the canal is tried.

Anal stricture is not uncommon; needs regular dilatation by patient himself; usually done two times a day for 6-8 weeks will stretch the anal canal correcting the stricture. Severe cases need stretching under general anaesthesia or anoplasty to rectify the problem **(Fig. 25-63)**.

Anal fissure due to breakdown of the anoderm.

Recurrence is not very high—2-5%.

Anal discharge for sometime which usually subsides in 2 weeks.

Incontinence for faeces or gas is common; but subsides in 4-6 weeks.

Ectropion (Whitehead deformity) of the anal mucosa; it commonly regresses once healing occurs as mucosa will be drawn upwards towards the muscle.

TREATMENT OF ANAL FISSURE

General Measures for Anal Fissure

Adequate fluid intake (6-8 glasses of liquids); fibre rich diet (vegetables, fruits, brown rice); bulk forming agents (psyllium husk, bran); stool softeners (lactulose); local anaesthetic agents (lignocaine 5%); Sitz bath; avoid constipation; once recovers, regular anal dilatation **(Fig. 25-64)**.

In an Acute Case

Lord's Dilatation

It is done under general anaesthesia to relax the sphincter. It is the *manual dilatation* (Lord, 1968-1969) of the anus under general anaesthesia with relaxation using *four fingers of each hand* (*8 fingers*) to cause vigorous stretching of the anal canal to break the circular constricting band in the wall of the anorectum. It is found that it causes tear of levator ani reducing its tone and so it is not universally accepted even though it gives early pain relief; but incidence of symptomatic incontinence is surprisingly not very much. Later, use of laxatives, xylocaine surface anaesthetic application, and anal dilatation with finger can be carried out for certain period**.** Bed rest; 2% nifedepine ointment.



Radial Park's incision

Submucosal dissection with elevating the mucosa; transfixation ligation of the pile mass using 2 zero vicryl

Partial closure of the mucosal parts

Fig. 25-59: Parks submucosal haemorrhoidectomy.



Fig. 25-60: Prolapsed thrombosed pile. It needs initial conservative treatment and later definitive treatment. Anal sphincter stretching may be useful.



Fig. 25-61: Ligasure is often used in haemorrhoidectomy; it avoids suture ligation of the pedicle.

Stretching of the anal sphincter (Recamier, 1829) using *two fingers of each hand* (*4 fingers*) under anaesthesia is also an alternative one. It is better than Lord's dilatation as complications are less. Fingers are passed into the anal canal one by one up to 4 fingers; gradual persistent stretching is done. In males stretching is done anteroposteriorly and in females transversely **(Fig. 25-65)**.

For Chronic Fissure (Fig. 25-66)

Lateral anal sphincterotomy (Subcutaneous lateral internal sphincterotomy): Here internal sphincter is divided partially away from the fissure either in right or left lateral positions (also gives a good result). Here *closed or open methods* are used. Sphincterotomy is done below the dentate line. Brodie did first anal sphincterotomy in 1839. In 1863, Hilton popularized it; but was not sure which structure is torn. Miles later said pectin band is divided. In 1951, Eisenhammer understood that it is internal sphincter, which is truly divided partially in this procedure. In olden days, posterior midline sphincterotomy was in practice; but it was causing keyhole deformity with flatus incontinence (34%) and faecal soiling. In 1969, Eisenhammer again modified the technique into lateral sphincterotomy.

In *closed method* (Notaras, 1969), bivalved retractor is passed first to stretch the sphincter gently so as to make it taut which facilitated its cutting easier*;* no 11 blade is inserted into the intersphincteric



Fig. 25-62: Sentinel pile often requires excision under local anaesthesia.



Fig. 25-63: Anal dilator. Many anorectal surgeries require regular anal dilatation post-operatively. Note how to hold the dilator to pass into the anus after applying lubricant.


Rectum
Anal valve
Anal canal
Fissure-in-ano
Anal valves
Hypertrophied
anal papilla
chronic fisssure
Sentinel pile

Fig. 25-64: Fissure in ano and its surgical anatomy.



Fig. 25-65: Stretching of the anal canal is done using four fingers (two fingers of each hand). Instrument stretching can be done.



Fig. 25-66: Chronic fissure in ano and its parts.

groove to pass upwards. Blade is moved medially to cut lower 1/3 or 1/2 of the internal sphincter. Cataract surgery knife (Beaver cataract blade, 25.5 × 2.2 mm) is better instrument (Notaras). Hook knife is also used. External sentinel pile and inner fibroepithelial polyp on the inner end is excised. Closed method is simple but effective method. It can very well be done under local anaesthesia with 1:2,00,000 adrenaline as office or day care surgery. Lateral, prone jackknife or lithotomy positions are used. Right lateral 9 O'clock position is the preferred site/point/area than left (In left side 3 O'clock position left haemeorrhoidal vessels are located. So, chances of haematoma are more); but right hand surgeon finds difficult to give a backhand cut on the sphincter than left hand surgeon; so many right hand surgeons prefer to do on left side. Digital examination of the rectum is done; intersphincteric groove is identified; retractor can be placed gently if needed; after sphincterotomy residual sphincter fibres can be broken using finger. Reintroduction of blade should be avoided **(Fig. 25-67)**.



Fig. 25-67: Closed method of lateral sphincterotomy.

In *open method,* skin is incised laterally circumferentially for 2 cm at 9 O'clock position (radial incision also can be used); free edge of the internal sphincter is dissected external to anal verge. Hypertrophied band of lower part of internal sphincter (free lower edge) is dissected and divided. If wound has to be closed absorbable 4 zero vicryl should be used. Wound may be left open to allow it to granulate. Haematoma, ecchymosis, perianal abscess, bruising, fistula, incontinence are the complications of lateral sphincterotomy. Flatus incontinence is more common in women. Recurrence rate of sphincterotomy is 2-4%. Complications are little less in closed approach but recurrence rates are same in both.

Dorsal fissurectomy with sphincterotomy is done under anaesthesia. Specimen should be sent for biopsy to rule out carcinoma, tuberculosis, Crohn's disease, etc. Here, transverse lower fibres of internal sphincter are divided in the floor of the fissure. Keyhole deformity is a troublesome effect of fissurectomy. But for *chronic fibrotic anal fissure, fissurectomy has to be the treatment* along with sphincterotomy. Sphincterotomy can be done in the fissure floor after excision or lateral sphincterotomy can be added.

Topical nitroglycerine 0.2% can also be used to relax the sphincter. It causes severe headache. Botulinum toxin 25 units injected into the internal sphincter. It causes temporary denervation of the internal sphincter; reducing its tone, improving the blood supply and controlling ischaemia. It causes temporary incontinence for flatus (10%). Diltiazem (2%), and L arginine are the other agents that can be used. Regular anal dilatation is also important to prevent recurrence.

ANORECTAL ABSCESS

Most common causative organism is *E. coli (60%).* Others are *Staphylococcus, Bacteroides, Streptococcus, B. proteus.* Commonly occurs due to infection of anal gland in perianal region. 95% of anorectal abscesses are due to infection of anal glands in relation to crypts—*cryptoglandular* disease. Common in diabetics and immunosuppressed **(Fig. 25-68)**.



Fig. 25-68: Anatomy of anorectal abscess.

Other Causes

Injury to anorectum; cutaneous infection (e.g. Boil); blood borne infections; many anorectal abscesses are associated with anal fistulas; fissure-in-ano; perianal haematoma; post-anorectal surgery; Crohn's disease; tuberculosis **(Fig. 25-69)**.

Differential diagnosis of anorectal abscess: Periurethral abscess; Bartholin abscess; tuberculous abscess.



Fig. 25-69: Perianal haematoma and its drainage. It can be done under local anaesthesia.

Investigations

MRI is the *investigation* of *choice* for anorectal abscess; *perineal and anal US* is also very useful; investigations relevant to specific cause may be done; proctosigmoidoscopy is needed to identify secondary cause in anorectum.

Classification

1. Perianal.
2. Ischiorectal.
3. Submucous.
4. Pelvirectal.
5. *Fissure abscess* (in relation to fissure-in-ano).

Perianal Abscess (60%)

This usually results due to suppuration of anal gland or suppuration of thrombosed external pile or any infected perianal condition. It lies in the region of subcutaneous portion of external sphincter. After drainage under general anaesthesia, pus should be sent for culture. Patient should be re-examined in 2 weeks with proctosigmoidoscopy. If patient develops abscess later which should be warned to the patient before hand then fistulotomy or fistulectomy should be done at a later period. Anal fistula is not recognised at the time of drainage of the fistula; so usually fistulotomy is delayed until fistula manifests **(Fig. 25-70)**.

Ischiorectal Abscess (30%)

Ischiorectal fossa (pyramidal shape 5 cm depth and 2 cm width) lies between anal skin and levator ani. Right and left communicates with each other. Laterally, it is related to fascia covering obturator internus; medially to levator ani and external sphincter; posteriorly sacrotuberous ligament and gluteus maximus; anteriorly urogenital diaphragm; below, the floor by skin. Above, it is related to lunate fascia and pudendal neurovascular bundle in pudendal canal (Alcock's canal). Commonly, it is due to extension of low intermuscular anal abscess, laterally through external sphincter. But often it can be blood or lymphatic borne. Fat in the fossa is more prone for infection because it is least vascularised. Fossa communicates with that of opposite side through post-sphincteric space and so *horse-shoe like* abscess can occur. When swelling is pressed just prior to making incision, if pus exudes per anal canal it means there is an internal opening and patient is likely to develop a trans-sphincteric fistula. Abscess presents with tender, indurated, brawny swelling in the skin over the ischiorectal fossa with high fever. *Swelling is not well-localised and fluctuation is absent in ischiorectal abscess.*

Treatment

Under general anaesthesia in lithotomy position, through a cruciate incision a portion of skin is excised (de roofing) and pus is drained. Cruciate incision should be placed close to the anal verge as subsequent fistula if formed will be having short track. Pus is sent for C/S and presence of any internal opening to rectum should be looked for (for possibility of an existing fistula). Presently, there is a debate whether cruciate incision is needed or not **(Figs 25-71 and 25-72)**.

Submucous Abscess (5%)

It occurs above the dentate line, which can be drained with sinus forceps, through a proctoscope; aching pain in the anorectum with



Figs 25-70(1)



Figs 25-70(2)

Figs 25-70(1 and 2): Drainage of perianal abscess.



Fig. 25-71: Cruciate incision is used for drainage of ischiorectal abscess.

significant perineal discomfort. On digital examination (P/R), tender, soft, smooth swelling in the lower rectum and anal canal. It may be missed clinically as there is no obvious swelling externally. It is called as deep post-anal abscess if it originates from posterior crypt above the external sphincter in front of and below the coccyx. *Treatment* is proper antibiotics; incision and drainage under general anaesthesia. Drainage of deep post-anal abscess requires division of the external sphincter by passing a probe the invariably existing primary opening in the posterior midline (Hanley).

Intersphincteric Abscess (2%)

It begins in a cryptogland in the intersphincteric plane, which burrows cephalad to present as a mass in the lower rectum. Abscess differs from submucous abscess as it is not in the submucosa plane but it is in the intersphincteric plane. Features are anorectal pain which is exacerbated during defaecation; rectal examination reveals a tender mass. It requires admission and hospital treatment under general anaesthesia. Abscess wall should be marsupialised along with excision of the part of the internal sphincter with crypt. Abscess cavity is allowed to drain into the lumen.

Pelvirectal Abscess

It is situated between the upper surface of levator ani and pelvic peritoneum. It is almost like a pelvic abscess; develops secondary to appendicitis, salpingitis, diverticulitis, Crohn's. Ultrasonography of abdomen is done to rule out the above factors. Treated accordingly, after thorough investigations for diabetes, Crohn's and other conditions. Occasionally, it can develop as in continuity cephalad extension of a trans-sphincteric or retrosphincteric abscess. US abdomen and pelvis or CT scan is must. MRI may be needed if there is intersphincteric pathology. Usually, it is treated like a pelvic abscess drained under general anaesthesia either per rectally in males or per vaginally (posterior fornix) in females. Malecot or Foley's catheter is placed. External drainage is rarely done; it is done only in few occasions' like Crohn's disease with abscess where long term drainage is needed. Through intersphincteric space after placing an incision close to the anal canal, abscess is reached and Malecot's catheter is placed.

Problems with anorectal abscess: Recurrent abscess formation; fistula formation is common. Other than this in diabetic patients anorectal abscess may cause necrotizing fasciitis or Fournier's gangrene. Perianal abscess may be often associated with leukaemia, neutropenia (neutrophil count less than 500/mm^3).

FISTULA-IN-ANO

It is a track lined by granulation tissue which connects perianal skin superficially to anal canal; anorectum or rectum deeply. It usually occurs in a pre-existing anorectal abscess which rupture spontaneously **(Fig. 25-73)**.

Fistula-in-ano

Cryptoglandular or Non-cryptoglandular

Non-cryptoglandular (other causes)—10%—Tuberculosis, carcinoma, Crohn's disease, ulcerative colitis, lymphogranuloma venereum, hydradenitis suppurative, traumatic.



Fig. 25-72: Drainage of ischiorectal abscess. Cruciate incision can be used; but its need is a debate. Packing the cavity to drain is a must.



Fig. 25-73: Anatomy of fistula in ano.

Cryptoglandular Hypothesis (90%)

The intersphincteric space is the surgical plane between the internal and external sphincters and is found between the longitudinal muscle and external sphincter, where it exists as a sheet of fat containing loose areolar tissue. The fat-filled ischioanal fossa lies lateral to the sphincter complex and is traversed by a network of fibroelastic connective tissue. Proximal half of the anal canal is characterised by longitudinal mucosal folds, the anal columns of Morgagni. The distal aspect of each column is linked to its neighbour by a small semilunar fold (the anal valves), which in turn forms small pockets (the anal sinuses, or *crypts of Morgagni*). The distal undulating limit of these valves is the dentate (pectinate) line, which also marks the most distal aspect of the anal transitional zone, a histologic junction between anal squamous and rectal columnar epithelium. The dentate line lies 2 cm proximal to the anal verge and is important landmark in fistula in ano because the anal glands empty into the crypts that lie proximal to the valves. These glands secrete mucus to lubricate anus, and are the source of infection. These glands present in the subepithelium, internal sphincter, and two-thirds of these glands are located within the intersphincteric space. The infection of these intersphincteric glands initiates the fistula in ano, known as the "*cryptoglandular hypothesis*".

These glandular infection leads into an intersphincteric abscess due to blockage of the draining duct by infected debris. This abscess may resolve by spontaneous drainage into the anal canal or may progress to an acute anorectal abscess. Treatment of this abscess is incision and drainage; but source of infection in the intersphincteric space persists, leading into development of a fistula in ano. Acute anorectal abscess and fistula in ano are believed to be acute and chronic manifestations, respectively of the same disease.

While most fistulas start as a *simple single primary tract*, recurrent infection eventually causes formation of *extensions (secondary tracts)*. Extensions may be intersphincteric, ischioanal, or supralevator (pararectal). The ischioanal fossa is the commonest site for an extension. Extensions also can occur in the horizontal plane known as "horseshoe" if there is ramification each side of the internal opening **(Fig. 25-74)**.

Classification (Figs 25-75 to 25-77)

Standard (Milligan Morgan, 1934; Goligher 1975)	*Park`s classification (1976)*
• Subcuntaneous—commonest • Low anal—common • Submucous • High anal • Pelvirectal	• Intersphincteric—commonest 70% • Trans-sphincteric 25% • Supralevator/suprasphincteric 4% • Extrasphincteric 1%

Fistula can be:

1. ***Low level fistulas—****these open into the anal canal below the internal ring.*
2. ***High level fistulas****—these open into the anal canal at or above the internal ring.*

Fistula can be

- *Simple fistula* without extensions.
- *Complex fistula* with extensions **(Figs 25-78 and 25-79)**.

Fistula can be with

Single external opening.

Multiple external openings which are often seen in tuberculosis, ulcerative colitis, Crohn's disease, LGV, hidradenitis suppurativa, actinomycosis **(Fig. 25-81)**.



Fig. 25-74: Anatomy of anal glands (Cryptoglands of Morgagni).



Fig. 25-75: Standard classification of fistula in ano.



Fig. 25-76: Intersphincteric fistula is the commonest type.

Low-level Fistulas

It has a prevalence of 0.01% and is common in young adult males (2:1, male to female). It presents with seropurulent discharge (65%), along with skin irritation and one or more external opening may be present with induration of the surrounding skin. Often it may heal superficially but pus may collect beneath forming an abscess, which again discharges through same or new opening.

Ischiorectal fossa on each side, most often communicates with each other behind the anus causing *horseshoe* fistula.

Goodsall's (England, 1900) Rule

Fistulas with an external opening in relation to the anterior half of the anus is of *direct type.* Fistulas with external openings in relation to posterior half of the anus, has a curved track may be of horse-shoe type, opens in the midline posteriorly and may present with multiple external opening all connected to a single internal opening **(Fig. 25-82)**. *P/R examination shows indurated internal opening usually in the midline posteriorly***.** Most of the fistulas are on posterior half of anus.


Trans-sphincteric fistula
Supralevator fistula
Extrasphincteric fistula

Fig. 25-77: Trans-sphincteric, supralevator, extrasphincteric types of fistulas.



Fig. 25-78: Simple fistula in ano.

Investigations

Chest X-ray, ESR and barium enema X-ray; *if required fistulogram is done only under anaesthesia*. MRI/MR fistulogram ideal. Endorectal US (US perineum) is useful to assess deeper plane. Discharge study, methylene blue dye study, biopsy. Colonoscopy often when ulcerative colitis/Crohn's is suspected. Specific blood tests and colonoscopy if needed should be done **(Figs 25-83 to 25-85)**.



Fig. 25-79: Complex fistula in ano.



Fig. 25-80: Multiple fistula in ano.



Fig. 25-81: Probing of fistula should be done in operation theatre prior to surgery.



Fig. 25-82: Goodsall's rule.

Note: *Probing and fistulogram in the ward* before surgery using *Lipiodol* is not advisable as it may cause recrudescence of inflammation. It can be with adequate precaution in the operation theatre under general anaesthesia otherwise it can *create extensions*.

Differential diagnosis for fistula-in-ano: Urethral fistula in male; chronically infected Bartholin's gland; pilonidal sinus; hidradenitis suppurative; carcinoma; Crohn's disease; tuberculosis, ulcerative colitis.

Treatment of Fistula in Ano

Principles in management	*Procedures*
• Identify the cause – cryptoglandular or other • Delineate exactly the fistula in ano by – MRI/EUS • Identify relation of fistula to anal sphincter • Drain all sites of infection • Eradicate track and secondary extensions • Preserve anal continence of function The *primary objectives* are to eradicate the tract and drain all associated sites of infection while simultaneously preserving anal continence.	• Laying open of fistula – fistulotomy with curetting • Fistulectomy • Gluing of fistula – not much useful • Mucosal flap procedure • Fistulectomy with primary repair • Fistulectomy with primary repair with episiorectopexy • Fistulectomy with secondary repair • Anal Fistula Plug repair (AFP) • LIFT Technique (Ligation of Intersphincteric Fistula Track) • Seton technique (Latin – seta – a bristle) • Colostomy- lay open, fistulectomy, later closure of colostomy – for high type • VAAFT procedure (Video Assisted Anal Fistula Track ligation)

Principles in management

- Delineate exactly the fistula anatomy—MRI/EUS
- Identify the cause—cryptoglandular or other
- Methylene blue injection on table
- Fine ureteric catheter may be placed into the track
- Drain all sites of infection
- Eradicate track and secondary extensions
- Preserve anal continence function
- Fistula surgery should be done in a dry field
- Careful use of cautery is ideal



Fig. 25-83: Methylene blue injection study in fistula in ano. It is usually done on table prior to surgery to identify track.



Fig. 25-84: Fistulogram for fistula in ano.



Fig. 25-85: MR fistulogram.

One should remember that

- It is not easy to treat fistula
- Needs proper assessment and planning
- Right method to right type
- High, complex fistula—a risky one
- MR fistulogram with EUS may be ideal to delineate track
- Beware of high recurrence rate and specific causes

Fistulotomy

It is done in low anal fistula. It is technically easier. Methylene blue solution may be injected to the external opening. Track is identified. After passing the probe through the entire fistulous track, incision is made over the probe to cut and lay open the fistulous track. It is allowed to granulate and heal from the floor/surface. Technique is safe, easy and can be done on outpatient basis. Only outer part of the track is excised for histology purpose. External opening part is widened as skin part will heal more rapidly than mucosal part. Anal opening (only, not mucosal) is sutured to the internal sphincter for haemostasis as an optional technique. Dressing is done. Post-operative pain is very less. There is not much difference in outcome between fistulotomy and fistulectomy. Fistulotomy wound heals faster **(Figs 25-86 and 25-87)**.

Advancement Flaps

They are used occasionally to get better result—mucosal flap procedure. Procedure is done per anally under spinal anaesthesia. Lithotomy position is used. Flap of mucosa with underlying internal sphincter with its blood supply is mobilised to cover the internal opening of the fistula properly and securely. Advancement can be done from above or from below. Problems are—it is technically demanding; flap failure; incontinence; it needs expertise to do.

Gluing of the Fistula Track

It is tried but success rate is not good. Fibrin glue is a multicomponent system containing mainly human plasma fibrinogen and thrombin. Once prepared, it is injected into the fistula track, which hardens in few minutes and fills the entire track. Success rate is 70%.

Anal Fistula Plug (AFP) Repair

Surgisis anal fistula plug (*porcine small intestine submucosa, SIS*) is used with 85% success rate in simple fistula. It contains naturally derived extracellular matrix which acts as scaffolding, ingrowth of tissue, remodeling **(Fig. 25-88)**.

LIFT Technique (Ligation of Intersphincteric Fistula Track):

It is high ligation of the fistula track with lateral approach. Here fistula tract is securely close to the internal sphincter, which probably avoids the reinfection of the intersphincteric space. Further resection of the intersphincteric tract and curettage of the remaining outer tract eliminates the diseased cryptoglandular tissue; distal tract when closed prevents its re-infection. Under anaesthesia in lithotomy position, methylene blue is injected into the track; fine ureteric catheter is passed gently through the fistula track from the external opening; intersphincteric space is reached through a 2-cm transverse incision in the intersphincteric groove adjacent to the fistula site. Fistula running across is identified and is clamped on the inner side with a haemostat; part of the fistula track in the groove is excised and sent for histology. Clamped fistula track on the inner side is suture ligated very close to the internal sphincter using 3 zero vicryl securely. External opening and the fistula track up to the intersphincteric space is gently curetted to clear all infected granulation tissue **(Fig. 25-89)**.

Track opening in the intersphincteric space towards the external sphincter is sutured using 3 zero vicryl. Dissected external sphincter and transverse incision in the intersphincteric groove is also sutured



Fig. 25-86: Fistulotomy—laying open of the fistula track is the commonly done procedure.



Fig. 25-87: Fistulotomy set needed for fistulotomy.



Fig. 25-88: Anal fistula plug.


Longitudinal muscle
Rectum
Anal columns
Intersphincteric space
Levator ani
Puborectalis
Internal anal sphincter
Anal gland
External anal sphincter
Dentate line
Longitudinal muscle
Rectum
Anal columns
Intersphincteric space
Levator ani
Puborectalis
Internal anal sphincter
Anal gland
External anal sphincter
Incision
Dentate line
Longitudinal muscle
Rectum
Anal columns
Intersphincteric space
Levator ani
Puborectalis
Internal anal sphincter
Anal gland
Dentate line
External anal sphincter
Malleable retractor
Longitudinal muscle
Rectum
Anal columns
Intersphincteric space
Levator ani
Puborectalis
Internal anal sphincter
Anal gland
Dentate line
External anal sphincter
Longitudinal muscle
Rectum
Anal columns
Intersphincteric space
Levator ani
Puborectalis
Internal anal sphincter
Anal gland
Dentate line
External anal sphincter
Longitudinal muscle
Rectum
Anal columns
Intersphincteric space
Levator ani
Puborectalis
Internal anal sphincter
Anal gland
Dentate line
External anal sphincter

Trans-sphincteric fistula

2 cm transverse incision along the intersphincteric groove

Methylene blue is injected to the track ureteric catheter is passed

Excision of the fistula track in the intersphincteric groove — track close to the internal sphincter is ligated using 3 zero vicryl

▭ **Specimen of the fistula**

Outer part of the track is scraped/curetted and then track is sutured from inside

Wound is closed in layers

Fig. 25-89: Ligation of intersphincteric fistula track (LIFT).

using interrupted 3 zero vicryl sutures. LIFT avoids incontinence as it is sphincter saving technique. (This procedure was developed by Thai colorectal surgeon, Arun Rojanasakul, Colorectal Division Department of Surgery, Chulalongkorn University in Bangkok, Thailand, 2005). Initially in 1993, Matos et al described this intersphincteric approach to excise the infected gland.

VAAFT procedure (Video Assisted Anal Fistula Track ligation): Fine specialized endoscope is passed through the external opening into the fistula track; with continuous irrigation fistula track is cleaned and wall is cauterized. Inner opening is ligated through vicryl from luminal side.

Treatment of Horseshoe Fistula

It is commonly trans-sphincteric but can be intersphincteric also. It has got multiple external openings with a subcutaneous communication in U or horseshoe shape with arms anteriorly and internal opening in posterior midline. All openings should be excised in horseshoe fistula and laid open widely. It is allowed to granulate and heal by secondary intention. Most important part in the horseshoe fistula is excision of the internal opening; if internal opening is removed then external openings will close (Hanley). It requires unfolding of the posterior midline to drain the deep post-anal space adequately. External openings and their tracks in such situation are individually approached, curetted and packed. Laid open deep post-anal space is also packed **(Fig. 25-90)**.

Fistulectomy

Under general or spinal anaesthesia, probe is passed through external opening up to the internal opening, which is felt as an induration. Fistula is opened along the probe using a knife. Fibrous track along with unhealthy granulation tissue and additional external openings are excised. Specimen is always sent for histopathology. *Fistulectomy for low level fistulas do not cause rectal incontinence.* Proper curetting of the infected anal gland area is essential. It is done in recurrent, chronic fibrotic fistulas **(Fig. 25-91)**.


Horseshoe fistula
with internal opening
in posterior midline
Entire fistula track
including inner opening
is laid open — usual technique
Dressing pack
Interanl opening is laid open widely along deep post - anal space and is packed;
each external opening and track is curetted and packed — Hanley's method

Fig. 25-90: Management of horseshoe fistula in ano. Both sides are laid open including the internal opening. When there are multiple external openings, they are individually curetted; internal opening is laid open properly.

Multiple Fistulae in Ano

It means usually multiple external openings; but occasionally can have more than one internal opening. All external and internal openings should be laid open. Sphincter should be taken care of. Non-cryptoglandular causes should be thought of like tuberculosis, Crohn's, ulcerative colitis, HIV infection **(Fig. 25-92)**.

Seton Technique

A silk or linen or braided nylon ligature is passed across the fistula and left in place with a tie. *Striated muscle* superficial to fistula track is encircled with Seton material and tied securely and left in situ to create ischaemic necrosis, dividing the muscle slowly without allowing it to spring apart avoiding gutter deformity. Even though internal sphincter is divided, causing adequate laying open of entire fistula track, the sphincter function and pressure will be well preserved. This allows the fistula to granulate and heal from above and to close completely. Usually takes longer duration to heal. It is done for intermediate and intersphincteric fistula. It is used prior to definitive procedures like fistulectomy or advancement flap.

Seton can be kept for 3 months. It can be regularly replaced by new silk or any material by rail road technique without anaesthesia **(Fig. 25-93)**.

Two types of setons are present. Loose setons are used mainly to drain for long period in recurrent/post-operative fistulas and due to specific causes like Crohn's. There is no tension in seton. Soft braided nylon is used.

Cutting setons are used when enclosed muscle is needed to cut (cheese wiring through ice effect). It is placed tight. It is used as a definitive treatment. It divides the sphincters slowly and track progressively becomes lower until seton falls out on its own. So, sphincter is divided part by part so that time is given for healing to the divided part prior to the next portion of the sphincter is divided. It is said to retain the sphincter function and so continence.

Other Methods

There are still many more methods for treating fistula. As recurrence rate is higher and is common disease, more and more procedures will evolutes – like laser, etc. Their real advantages over standard technique is not sure **(Figs 25-94)**.

Postoperative Care

Sitz bath, antibiotics, analgesics, laxatives are given. Regular dressing is done. Wound usually granulates well and seals.

Complications

Fistula surgery is demanding and needs meticulous approach otherwise complications will occur. Incontinence for flatus and often faeces are the main complications. Infection, discharge, delayed healing, spread of infection are other complications.



Fig. 25-91: Fistulectomy technique for fistula in ano. Entire track is removed and bed is curetted and left open; healing is slower in fistulectomy compared to fistulotomy.



Fig. 25-92: In managing multiple fisutlae, all external and internal openings including extensions should be laid open and curetted.


Rectum
Anal valves
Anal canal
Fistula-in-ano
Seton

Fig. 25-93: Seton technique.


biolitec
Continuous Mode
LASER READY

Fig. 25-94: Laser in fistula surgery. It controls bleeding well.

Chapter

26

Retroperitoneal Surgeries

SURGICAL ANATOMY

This is the space between the peritoneal cavity and posterior abdominal wall. It is bounded anteriorly by posterior parietal peritoneum and contents of the peritoneal cavity; posteriorly by vertebral column, psoas, iliacus, quadratus lumborum muscles, and tendinous portion of transversus abdominis muscles; superiorly by diaphragm; inferiorly by pelvic levator muscles (by Ackerman). It is real potential space **(Fig. 26-1)**.

Three spaces are defined in the retroperitoneum. *Anterior paranephric space* is located between the parietal peritoneum and Gerota's fascia. *Middle perinephric space* is bounded in front by Gerota'a fascia and behind by Zuckerkandl's fascia; it contains kidney, adrenal, renal pelvis and proximal ureter and renal vessels. *Posterior paranephric space* is located between Zuckerkandl's fascia and transversalis fascia.

Retroperitoneum contains vessels (aorta, IVC, portal veins); kidney and ureters; pancreas, duodenum, parts of colon, rectosigmoid; lymphatics, cisterna chyli and thoracic duct; celiac, superior and inferior hypogastric, sacral sympathetic chains; ilioinguinal, iliohypogastric, lateral cutaneous, femoral, genitofemoral, obturator, sciatic and pudendal.

Retroperitoneal tumours, secondaries, aneurysms, retroperitoneal haematoma, abscess, retroperitoneal fibrosis (Ormond's) are different conditions which can occur in this space. It is an extensive space. Dissection in this space is tedious, bleeds from major or small vessels torrentially **(Fig. 26-2)**.

APPROACHES FOR RETROPERITONEUM

Transperitoneal lengthy midline incision is very useful approach for both sides of the retroperitoneum.

Loin incision extraperitoneally like approaches to kidney and ureter **(Fig. 26-3)**.


12th dorsal nerve
Iliohypogastric nerve
Ilioinguinal nerve
Lateral femoral cutaneous nerve

Fig. 26-1: Retroperitoneal anatomy.


Kidney
Retroperitoneal tumour
Laterally deviated ureter
IVC
12th dorsal nerve
Iliohypogastric nerve
Ilioinguinal nerve
Lateral femoral cutaneous nerve

Fig. 26-2: Retroperitoneal tumour.


Loin incision
Oblique lumbar incision

Fig. 26-3: Approaches for retroperitoneum—lengthy midline; oblique loin or loin incision in lateral position.


Approach incision for suprarenal aorta
IVC
Aorta
17
18
16
1
2
3c
2
3
11
3b
3a
13
20a
5
12
19
14
20b
20c
20d
Kocherisation of duodenum
6
4
7
8
6
10
10
9
15
15
Approach incision in retroperitoneum for infrarenal aorta
1. Inferior phrenic artery
2. Middle suprarenal artery
3. Coeliac trunk
3-a. Hepatic artery
3-b. Splenic artery
3-c. Left gastric artery
4. Superior mesenteric artery
5. Renal artery
6. Gonadal artery
7. Lumbar artery
8. Inferior mesenteric artery
9. Median sacral artery
10. Common iliac artery
11. IVC
12. Left renal vein
13. Left adrenal vein
14. Left gonadal vein
15. Common iliac vein
16. Liver
17. Diaphragm
18. Oesophagus
19. Right kidney
20. Duodenum: 20a- 1st part; 20b- 2nd part; 20c- 3rd part; 20d- 4th part.
Surgical anatomy and exposure of abdominal aorta

Fig. 26-4: Retroperitoneal approaches for aorta and lymph nodes.

Laparoscopic approach is very good to do retroperitoneal lymph node dissection.

Robotic assisted laparoscopic RPLND.

Structures approached through retroperitoneum (other than kidneys and ureters) are (Fig. 26-4):

- Aorta and its major branches.
- Retroperitoneal lymph nodes.
- Retroperitoneal tumour.
- Inferior vena cava and portal veins.
- Lumbar sympathetic chains.

RETROPERITONEAL LYMPH NODE DISSSECTION (RPLND)

RPLND is specifically commonly done for testicular and ovarian tumours. It is often also done in other malignancies also like carcinoma cervix, endometrium, rectum, etc. Nonseminomatous germ cell tumour of stage I and IIa shows good benefit. RPLND is used for staging as well as for therapy.

Both open and laparoscopic approaches are used. Laparoscopic approach is better as magnification and dissection is better. Nerve sparing is better.

Right-sided RPLND includes complete dissection above the inferior mesenteric artery up to renal vessels; laterally up to both ureters; below along the bifurcation of the common iliac vessels on same side (right). *Left-sided RPLND* includes complete dissection above the inferior mesenteric artery up to renal vessels; laterally on left side up to left ureter; towards right up to the right margin of the IVC; below along the aortic bifurcation/bifurcation of common iliac vessels on same side. In certain conditions bilateral RPLND is also done.

Preoperative Preparation

Patient should undergo complete metastatic work up as if there is blood spread or peritoneal spread RPLND is contraindicated. Peritoneal infection also temporarily preludes the surgery. Blood should be kept ready. Mechanical bowel preparation is needed. Nasogastric tube and Foley's catheter is passed.

Principles

Principles in RPLND are adequate exposure; meticulous dissection; haemostasis; use of bipolar cautery, proper retraction, safeguarding the bowel.

Technique

Right-sided RPLND—Right peritoneal fold (Toldt's line) is incised from hepatic flexure to medial umbilical ligament; colon is retracted medially by sharp dissection; colorenal and hepatorenal ligaments are divided by sharp dissection. Kocher's duodenal mobilization is done. Great vessels are exposed. Right spermatic cord and internal inguinal ring is identified. Vas deferens crossing ureter and iliac vessels is dissected, clipped and transected. External, iliac vessels should be safeguarded. Gonadal vein is dissected up to its joining to IVC; gonadal artery is dissected up to a point where it crosses and joins aorta. Gonadal vein is clipped and divided at its joining to IVC. Adventitia overlying the IVC is dissected carefully from renal vein level above and common iliac vessels level below. Right ureter is gently retracted laterally and lymphatics are dissected and retracted laterally. Ureter is dissected distally up to the point where it crosses the iliac vessels. Lymphatics with nodes are dissected and swept upwards. Sympathetic chain is identified and lymph nodes are dissected from behind without injuring the lymphatic chain. Inferior mesenteric artery and left renal artery is identified. Lumbar veins are identified and clipped before division. Intercavoaortic nodes should be cleared. Accessory renal artery and retroaortic renal vein may get confused and ligated inadvertently; this should be avoided. IVC is retracted gently in front and tissues are dissected and brought towards specimen. Dissection up to the left ureter should be done right RPLND **(Fig. 26-5)**.

Left-sided RPLND—Dissection here is above up to left renal vein; left ureter laterally; bifurcation of left common iliac veins below; right margin of IVC towards right side. Left paracolic gutter peritoneum is incised. Left colon is mobilized including splenic flexure by dividing left renocolic, phrenocolic, splenocolic, gastrocolic and pancreaticocolic ligaments; left renal vein is identified and dissected. Below up to the bifurcation of the common iliac vessels dissection is done. Colon, spleen above mobilized medially; left internal inguinal ring and left vas deferens is identified; left vas deferens is divided after clipping. Left gonadal vein is dissected up to its joining into the left renal vein. Aorta and left ureter is identified and dissected to clear paraaortic lymph nodes. Dissection from aorta above towards iliac vessels downwards along the origin of inferior mesenteric artery is carried out to clear all lymph nodes. Lymphatics along the intercavoaortic region from renal vein level to IMA level are cleared. IVC is dissected and retracted towards right to identify lumbar veins which are ligated and all tissues are swept towards left specimen side **(Fig. 26-6)**.



Fig. 26-5: Template for RPLND right-side.





Fig. 26-6: Template for RPLND left-side.

Complications

Haemorrhage occurs while dissecting and mobilising the IVC especially from its tributaries. Clipping the vessels is better way to prevent the haemorrhage.

Injury to ureter, stricture ureter (5%), and hydronephrosis due to surgical trauma can occur.

Lymphocele, chylous ascites due to lymphatic dissection is likely to develop often (3%).

Retrograde ejaculation due to sympathetic nerve damage can occur (5%). Nerve sparing surgery, avoiding monopolar cautery close to the sympathetic chain prevents this.

Contd...

Contd...

Paralytic ileus is common due to retroperitoneal dissection. If it persists long time one should suspect haematoma, pancreatitis, urinary extravasation.

Sepsis is not uncommon – retroperitoneal or intraabdominal abscess formation can occur. It is diagnosed by CT scan, usually responds with higher generation antibiotics; may require guided catheter drainage; occasionally only needs open drainage.

Chapter 27

Urologic Surgeries

SURGICAL ANATOMY OF KIDNEY

They are a pair of excretory organs situated retroperitoneally, on the posterior abdominal wall; one on each side of vertebral column. Vertically it extends from the upper border of T12 vertebra to the centre of the body of L3 vertebra. The right kidney is slightly lower than the left, left kidney is slightly nearer to the median plane. Each kidney is about 11 cm long, 6 cm broad, and 3 cm thick; 150 gram in weight; reddish brown in colour. Lateral border is convex. Medial border is concave with a hilum. Structures seen in the hilum are (from anterior to posterior)—(1) renal vein, (2) renal artery, (3) renal pelvis. Upper pole is related to suprarenal gland; lower pole lies 1 inch above the iliac crest. Capacity of renal pelvis is 10 ml. The angle between the 12th rib and the outer border of the sacrospinalis is the kidney/renal angle. Fetal kidney has got 12 lobules which fuse after birth to become smooth. Hepatorenal pouch (Morrison's kidney pouch) is a peritoneum lined deep recess, related to the upper pole of kidney. It is the lowest site when the body is in horizontal position, excluding the pelvis. Collection of extravasated fluid is likely to occur in this pouch following surgeries to liver and biliary tract.

Kidney occupies lumbar, epigastric, hypochondriac, umbilical region. It extends vertically from upper border of 12th thoracic vertebrae to the centre of the body of 3rd lumbar vertebra. Right is lower than left; left is more medial than right. Upper pole is more medial than lower as long axis is directed downwards and laterally. Transpyloric plane passes through the upper part of the right renal hilum and lower part of left renal hilum. Hilum lies opposite the lower border of the 1st lumbar spine; right hilum is lower **(Fig. 27-1)**.

Morris parallelogram is surface marking drawn from behind; two horizontal lines are drawn one at the level of the 11th thoracic spine, other at the level of 3rd lumbar spine; two vertical lines are drawn one 2.5 cm and other 9 cm from the midline. From front on the right side hilum lies 5 cm from the median plane below on the left side above the transpyloric plane; medial to the tip of the 9th costal cartilage. Upper pole lies midway between xiphisternum and transpyloric plane 5 cm from midline; lower pole 7 cm from midline at umbilical plane on the right side and at subcostal plane (little above) on the left side. Lower pole is 2.5 cm above the iliac crest.



Fig. 27-1: Location of both kidneys and configuration. Right kidney is lower than left. Left renal vein is longer and runs in front of the aorta and behind the SMA.

Relations of Kidney

Posterior relations—Diaphragm, medial and lateral arcuate ligaments; psoas major muscle; quadratus lumborum; transversus abdominis; subcostal vessels; subcostal, iliohypogastric, and ilioinguinal nerves. Right kidney is related 12th rib; left one to 11th and 12th ribs **(Fig. 27-2)**.

Anterior relations—Right-Right adrenal gland; 2nd part of the duodenum; right flexure of the colon; small bowel; partly covered by peritoneum at hepatic and bowel parts. *Left*-Left adrenal gland; spleen; stomach; pancreas; splenic vessels; left colonic flexure; descending colon; jejunum. Gastric, splenic and jejunal surfaces are covered by peritoneum.

Capsules of Kidney

Proper fibrous capsule—It is fibrous membrane which can easily be stripped off from the organ. This is a thin membrane which closely invests the kidney and lines the renal pelvis.


Pleura
11th rib
Diaphragm
Adrenal gland
12th rib
Renal fascia - anterior layer
Kidney
Subcostal nerve and vessels
Iliohypogastric nerve
Ilioinguinal nerve
Renal fascia - posterior layer
Posterior abdominal wall
Aorta
Ribs
Left adrenal gland
Left kidney
Left renal artery
Right adrenal gland
Right kidney
Right renal artery
View from behind
Posterior relations of the kidney
Lateral arcuate ligament
Medial arcuate ligament
Subcostal nerve and artery
Related to-
Psoas major
Quadratus lumborum
Iliohypogastric nerve
Transversus abdominis
Ilioinguinal nerve
Posterior relations of the kidney
Splenic flexure
Pancreas
Duodenum
Liver
SMA
SMV
Hepatic fexure
Transverse abdominis
Aorta
Internal oblique
Spleen
IVC
External oblique
Renal vessels
Renal pelvic
Kidney
Kidney
Renal fascia
Thoracolumbar fascia
Serratus posterior inferior
Anterior layer
Middle layer
Posterior layer
Spine
Erector spinae
Psoas major
Quadratus lumborum
Latissimus dorsi
View from above

Fig. 27-2: Relations of kidney.

Perirenal/perinephric fat is in the space of Gerota – it is the layer of fat outside the fibrous capsule.

Renal fascia of Gerota— It is fibroareolar sheath which covers the kidney and perinephric fat. It has got anterior layer *(Fascia of Toldt)* and posterior layer *(Fascia of Zuckerkandl)*. Many trabeculae runs in this plane from fibrous capsule to the renal fascia. Above two layers of renal fascia encloses the adrenal gland as a separate compartment and fuse each other; continuing with fascia under the diaphragm. Below two layers are separate enclosing the ureter; anterior layer merges with the connective tissue of the iliac fossa; posterior layer blends with the fascia iliaca. Laterally two layers fuse to continue as fascia transversalis. Medially anterior layer passes in front of the renal vessels and merges with the connective tissue around the aorta and IVC. The posterior layer gets fused with the fascia covering the quadratus lumborum and psoas major; to the vertebra and intervertebral disc. Medially it forms a septum to get pierced by renal vessels preventing perirenal fluid to cross to opposite side.

Pararenal/paranephric body of fat is fat lying outside the renal fascia more on backside and lower pole filling paravertebral gutter to create a cushion for kidney.

Structure of Kidney

Gross

Coronal section shows outer brownish cortex, inner pale medulla, and renal sinus. Renal sinus is a space that extends into the kidney from hilum. It contains (1) branches of renal artery, (2) branches of renal vein, (3) renal pelvis.

The pelvis divides into 2-3 major calyces which in turn divide into 7-13 minor calyces.

Histology

Each kidney is composed of 1-3 millions of uriniferous tubules; each of which has a collecting part *(collecting tubules)* and secretory part *(nephron)*.

Blood Supply

Arterial Supply

It is from renal artery, which arises from the aorta at right angles, at the level of intervertebral discs between L1 and L2 vertebrae just below the



Fig. 27-3: Segments of kidney.

level of the origin of the SMA. Right renal artery passes laterally behind the IVC and head of the pancreas to reach the right renal hilum. Left renal artery runs behind the left renal vein, splenic vein, body of the pancreas and duodenojejunal flexure. Each renal artery gives inferior adrenal artery and ureteral branches. About 95% of abdominal aortic aneurysm arises below the level of origin of renal artery **(Fig. 27-3)**.

The kidney is divided into anatomic segments based on blood supply. In the hilum, the main artery, divides into anterior and posterior divisions. The anterior division supplies the apical, upper, middle and lower segments; posterior segment is supplied by the posterior division. The knowledge of this is important in the operation of anatrophic nephrolithotomy, where a functionally *avascular plane* (*Brodel*) between the posterior segment and the upper and middle segments exist on the posterior half of the kidney, about two-thirds of the way from the hilum to the lateral margin of the kidney. There is no collateral circulation between segments of the kidney but veins will communicate freely between segments.

Main renal artery → division → segmental artery → lobar artery to each pyramid → 2 interlobar arteries run on each side of the pyramid → 2 arcuate arteries interlobular arteries run radially to cortex → afferent arteriole to glomeruli and also branches to renal capsule which forms capsular plexus. Afferent glomerular arteriole → glomerulus → efferent glomerular arteriole → peritubular glomerular plexus. Renal medulla derives its blood supply from efferent arterioles. Free circulation in the cortex is glomerular; restricted circulation in the medulla bypasses cortical glomeruli which is more rapid **(Fig. 27-4)**.

Accessory renal artery (30%) may arise from aorta running parallel to renal artery entering the kidney either at poles or at hilum.

Venous Drainage

Peritubular capillary plexus → interlobular veins → arcuate veins → interlobar veins → renal vein at renal sinus → join IVC just below the transpyloric plane. Left renal vein is longer than right one. Renal vein lies in front of the renal artery. Right renal vein lies behind the second part of the duodenum. Left renal vein crosses in front of the aorta lying behind the pancreas and splenic vein. Tributaries of left renal vein are left adrenal and left gonadal veins.

Nerve Supply

T10,11,12 through the lesser and lower splanchnic nerves.



Fig. 27-4: Arterial segments and their distribution in the kidney.

Lymphatics

They are drained into para-aortic (lateral aortic) nodes. Perinephric fat is removed during nephrectomy (for malignancies), as intrarenal lymphatics freely communicates with the plexus in the perinephric fat.

SURGICAL ANATOMY OF THE URETER

Each ureter is 25-30 cm long. It begins within the renal sinus as a funnel-shaped dilatation called renal pelvis. It enters the bladder wall obliquely to open at the lateral angle of the trigone. It lies in the retroperitoneal space not attached to any fixed structures, so can be displaced or obstructed by retroperitoneal masses like tumours or aneurysms. Abdominal portion of ureter lies on the medial portion of psoas major muscle near the tips of transverse processes of lumbar vertebra (which is very well seen in IVP). The ureter enters the pelvis crossing the end of common iliac or beginning of external iliac artery. In females, uterine artery crosses the ureter from lateral to medial side, about 2 cm lateral to the cervix (this has to be remembered while ligating the uterine arteries in hysterectomy).

Ureter is marked by a line running downwards and medially from the tip of the 9th costal cartilage to the pubic tubercle; behind it is marked by a line running vertically downwards from the 2nd lumbar spine till the posterior superior iliac spine.

Ureter runs downwards and medially on the psoas major muscle and enters the pelvis by crossing the common iliac artery in front near its bifurcation. In the true pelvis ureter runs downwards, backwards and laterally along the anterior margin of the greater sciatic notch; opposite the ischial spine it runs forwards and medially to reach the base of the urinary bladder. It enters the bladder obliquely to open at trigone.

Normal sites of constrictions: (1) PUJ, (2) At the brim of lesser pelvis, (3) Along its passage through the bladder wall.

Abdominal Part of Ureter

Right Side

It is related to 3rd part of the duodenum; right colic, ileocolic, right gonadal vessels; root of the mesentery; terminal part of the ileum. Right ureter is related medially to IVC.

Left Side

Left ureter is related to gonadal artery (not gonadal vein but it is adjacent and medial to left ureter), left colic vessels, sigmoid colon, sigmoid mesocolon. Posteriorly the ureter lies on psoas major, tips of transverse processes of lumbar vertebrae; genitofemoral nerve. Left ureter is related to left gonadal vein medially.

Pelvic Part of Ureter

Initial Part

Initially it runs forward. Here it is related behind to internal iliac artery, origin of its anterior trunk, internal iliac vein, lumbosacral trunk, sacroiliac joint. It is related laterally to superior vesical artery, obturator nerve, obturator artery and vein, inferior vesical vein, middle rectal artery, in females it is posterior boundary of the ovarian fossa.

Later Part

Later it runs forward. In males – vas deferens crosses the ureter above from lateral to medial side, the seminal vesicle lies below and behind the ureter, vesical veins surround its terminal part. In females it lies in the lower medial part of the broad ligament of the uterus. Uterine artery lies initially above and in front, later it crosses the ureter from lateral to medial side "water under the bridge", ureter lies 2 cm lateral to the supravaginal portion of the cervix, then above the lateral fornix of the vagina and end lies in front of the vagina. Interureteric distance of the ureters inside the bladder is 5 cm in full bladder and 2.5 cm in empty bladder.

Arterial Supply

Upper segment of ureter receives blood supply from branches of renal, gonadal and adrenal arteries; the middle portion from the aorta and branches of arteries of posterior abdominal wall; the pelvic portion from the branches of internal iliac arteries. Vessels reach the abdominal portion of ureter on the medial side; whereas the pelvic portion receives on the lateral side (This has to be remembered while mobilising the ureter). The vessels form an anastomotic plexus in the adventitia of the ureter, which is found to be deficient in 10-15% of individuals leading to necrosis of cut ends of ureter following extensive mobilisation. Arteries divide into ascending and descending branches which first form a plexus on the surface of ureter.

Nerve Supply of Ureter

Sympathetic comes from T10-L1 segments and parasympathetic from S2-S4 nerves. It arises from renal, aortic and hypogastric plexuses.

ANATOMY OF URINARY BLADDER

It is a muscular reservoir of urine situated in the pelvis, posterior to the pubic bone from which it is separated by the retropubic space. The size, shape, position of bladder depends on the amount of urine it contains. In females, the peritoneum is reflected from the superior surface of the bladder onto the anterior wall of the uterus close to the junction of the body of uterus and cervix. In males, the peritoneum is reflected from the superior surface of the bladder over the superior surface of the ductus deferens and seminal vesicles. The neck of the bladder is the most fixed part, lies 3-4 cm behind the pubic symphysis. In males it lies on the prostate and in females it rests on the anterior vaginal wall which is also supported by the levator ani muscle **(Fig. 27-5)**.

Structure of the Bladder

The bladder wall consists of interlacing fibres of smooth muscle. The urothelium consists of transitional epithelium which is loosely



Fig. 27-5: Anatomy of urinary bladder—posterior aspect and interior part.

attached and easily separated from the bladder wall except over the *trigone*. *Trigone* is a triangular area over the lower part of the base of the bladder. The ureters open into the posterolateral angles of the trigone. The internal urethral orifice opens at the inferior angle of trigone.

Sphincters

Internal sphincter: Smooth muscle, situated at the neck of the bladder, micturition follows its relaxation. It is innervated by autonomic nervous system.

External sphincter: It consists of striated muscle, innervated by the perineal branch of pudendal nerve (S2,S3).

ANATOMY OF PROSTATE

It is an accessory gland of male reproductive system. It is composed of glandular tissue embedded in fibromuscular stroma. It surrounds the first 3 cm of the urethra.

Lobes

It is composed of 5 lobes—anterior, posterior, 2 lateral, 1 middle/median lobe. Primary carcinoma is said to begin in posterior lobe. Middle lobe produces an elevation in the lower part of the trigone of bladder *(uvula vesicae)*. Adenoma is more common here due to more amount of glandular tissue **(Fig. 27-6)**.

Capsules

1. *True capsule*: Formed by the condensation of the peripheral part of the gland; continues with the stroma of the gland.
2. *False capsule*: Derived from the pelvic fascia. On each side prostatic venous plexus are embedded in it.

McNeal Divided Prostate into Three Zones

1. *Peripheral zone*—prone for carcinoma.
2. *Periurethral transition zone* where BPH arises.
3. *Central zone.*

Note: Prostate carcinoma develops in prostatic gland proper; BPH develops in submucosal glands.

Blood Supply

Superior and inferior vesical arteries, branches of anterior division internal iliac artery, obturator and inferior gluteal arteries supply the bladder. In females uterine and vaginal arteries supply the bladder instead of inferior vesical artery.

Venous drainage is by the vesical plexus of veins, which drains into the internal iliac veins. These veins connect directly to veins of hip bones, the heads of femoral and vertebral bodies. This accounts for the site of occurrence of bony metastasis in carcinoma of the bladder and prostate.

ANATOMY OF URETHRA

Male Urethra

Male urethra is 20 cm long and is S-shaped. It extends from internal urethral orifice (neck of the bladder) to external urinary meatus (tip of penis).

Posterior urethra:
- Prostatic urethra.
- Membranous urethra.

Anterior urethra:
- Bulbar urethra.
- Penile urethra.

Prostatic urethra is 3 cm in length runs vertically downwards from internal urethral orifice through the anterior part of the prostate. It is widest part of the male urethra (mainly in its middle). It is most dilatable also. It joins membranous urethra. Its orifice is star-shaped; posterior mucosa contains median longitudinal mucosal ridge as urethral crest/verumontanum; in the middle of this crest an elevation called as colliculus seminalis is present. Prostatic utricle opens into the urethra into a slit like orifice on this elevation. Prostatic utricle is a blind sac of 6 mm length in the prostate directing upwards and behind between median and posterior lobes. Opening of ejaculatory ducts are present on both sides of this slit. Two vertical grooves one on each side of this crest are called as prostatic sinuses. Around 30 prostatic glands open into these sinuses.

Membranous urethra is 2 cm in length runs downwards and forward through the deep perineal space; pierces the perineal membrane



Fig. 27-6: Anatomy of prostate.

about 2.5 cm below the pubic symphysis. It is the narrowest part of the urethra in males. It is surrounded by external urethral sphincter. Many urethral glands open into this urethra. *Cowper's bulbourethral glands* are located one on each side of this urethra. Their ducts travel down and open into the spongy part of the urethra after piercing the perineal membrane.

Penile/spongy urethra is 15 cm in length has got *proximal bulbar urethra* running forward and upward in the bulb of penis; later it bends downwards in front of the lower part of the pubic symphysis to run in the corpus spongiosum of penis. Diameter of penile urethra is 6 mm in diameter and is narrow; in its beginning beyond the membranous urethra it is dilated to form intrabulbar fossa which bulges into the floor on each side; terminal navicular fossa in the glans bulges into the roof on each side. External meatus 6 mm sagittal slit bounded by tiny labium on each side. Cowper's bulbourethral gland ducts open into penile urethra one on each side. Plenty of urethral glands of Littre open into penile urethra with their openings facing forward. Many small lacunae of Morgagni open obliquely forwards; biggest lacuna on the roof of the navicular fossa is called as sinus of Guerin **(Fig. 27-7)**.

Internal urethral involuntary sphincter contains smooth muscles, elastic and collagen fibers which is supplied by sympathetic nerves (supply above the level of the ejaculatory duct).

External voluntary urethral sphincter controls the membranous urethra and is supplied by the perineal branch of the pudendal nerve (S2,3,4).

Female Urethra

Female urethra is 4 cm long and 6 mm in diameter. It corresponds to the prostatic urethra of male above the level of prostatic utricle. It starts at internal urethral orifice 5 cm behind the pubic symphysis running downwards and forwards embedded in the anterior wall of the vagina crosses the urogenital diaphragm ending at the external urethral orifice in the vestibule. Proximally it is crescentic; middle it is star-shaped; transverse distally. External meatus is sagittal. Skene's paraurethral glands are collection of mucous glands on each side in the proximal part corresponds to prostate in males.


Prostate
Prostatic urethra
Verumontanum
Membranous urethra
Bulbar urethra
Penile urethra
Fossa navicularis

Fig. 27-7: Anatomy of male urethra.

APPROACHES TO KIDNEY

Approaches may be posterior (loin) or anterior (per abdomen) or thoracoabdominal **(Figs 27-8 and 27-9)**.

Loin approach is the standard approach. It is retroperitoneal approach. It is posterior subcostal with oblique lumbar incision. It is useful for pyeloplasty, nephrectomy for benign conditions like pyonephrosis with nonfunctioning kidney, tuberculous kidney, nephron sparing nephrectomies. Loin approach is in lateral position; with raised kidney bridge (or sand bags under the loin); with one knee flexed; large flat pillow between two legs; Mayo's table to keep instrument; arm is abducted and placed on an arm rest; with proper cotton padding to all pressure areas. Patient should be fixed to the table with tying belt and side supports. 12th rib excision is often required. 11th rib excision approach is done whenever 12th rib is rudimentary or absent.

11th rib with the 12th excision achieving extensive loin approach is called as *Nagamatsu approach* is used for large renal tumours.


Subcostal incision
- below 12th rib
Transcostal incision
- 12th rib approach
Supracostal incision
just above 12th rib
11th rib excision approach
Note: All these incisions are
loin posterior approaches
12th rib
11th rib
Posterior
lumbotomy incision
Nagamatsu
approach
12th rib
11th rib

Fig. 27-8: Different approaches to kidney.



1. Subcostal approach - below the 12th rib
2. Transcostal approach - through 12th rib resection
3. Supracostal approach - just above the 12th rib
4. 11th rib excision approach

Note: All these incisions are loin posterior approaches

Fig. 27-9: Posterior loin approaches as viewed from front of the patient.

Transperitoneal abdominal approach (anterior approach) is useful in renal malignancies.

Thoracoabdominal approach may be needed in large upper pole tumours. Patient is placed in supine position with two sandbags one under the shoulder and another under the buttock of the side of the surgery. Incision runs along the 10th or 9th rib extending from posterior axillary line to the midline and continuing downwards as midline incision. Hyperextension is provided by breaking the table. Posteriorly latissimus dorsi, serratus posterior inferior are incised using diathermy; 10th rib is resected (instead intercostal muscles may be cut above the rib); external oblique, internal oblique and rectus muscles are cut; costovertebral ligament behind and costal cartilage in front are cut. Pleura is identified and opened along the line of incision. Lung is retracted upwards; diaphragm is cut in the line of incision. Rectus sheath and peritoneum is opened up to the lower end of the incision. Large self retaining retractors are used to retract wound edges to expose the field. While closing the wound, peritoneum is closed first; diaphragm is sutured using polypropylene or vicryl (no. 1); ribs are approximated using no. 1 polypropylene; pleura and intercostal muscles are sutured after placing a intercostal tube to the pleural cavity through the 6th intercostal space in the midaxillary line. Loin muscles are sutured – latissimus dorsi, serratus posterior inferior and external oblique are sutured. Other layers of the abdomen are closed. Skin is apposed using skin staplers **(Fig. 27-10)**.



Fig. 27-10: Thoracoabdominal approach for kidney is done for large tumours.



Fig. 27-11: Laparoscopy is very well accepted for most of the urologic surgeries; becoming standard also. But technique and principles are same as open method.

Anterior supine paramedian vertical extraperitoneal approach is also popular for approaching while managing the benign conditions.

Laparoscopic approach is said to be ideal for many diseases including nephrectomy **(Fig. 27-11)**.

Retroperitoneoscopic approach is often used; but laparoscopic approach gives more space to work on it.

Posterior lumbotomy approach in prone position is no longer advocated.

Loin Incision (Posterior Approach; Morris Incision, Sir Henry Morris London)

Loin position is usual position used for renal surgeries. It can be subcostal (classical Morris incision is subcostal type); transcostal (12th rib); supracostal (above the 12th rib in the intercostal space). Subcostal is used for the benign diseases and lower pole diseases. Transcostal, supracostal and 11th rib excision approach is for difficult cases and upper pole tumours.

Patient is placed in loin position. It is usually transcostal 12th rib excision loin approach. Full lateral position with kidney bridge raise (to break the table 40° to horizontal) with flexion of the knee of the leg which is on the theatre table is done (lower side leg - 90°). Flat wide pillow should be kept between legs. Arm facing upwards is positioned towards head end with a support (cradle support). Patient is strapped firmly to table to prevent tilting or changing of the position during surgery. Back support is often needed. Mayo's table is placed on the leg side which facilitates to keep instruments safely after draping **(Fig. 27-12)**. Anaesthetist should observe blood pressure as it may drop after raising the kidney bridge by compression on the IVC.

After cleaning and draping, incision begins posteriorly behind the posterior axillary line in posterior subcostal line extending forward towards the outer margin of the rectus muscle. It usually marks angle of the 12th rib posteriorly to 15 cm beyond the tip of 12th rib. Rectus is usually not cut. Skin, subcutaneous tissue and superficial fascia are cut. Posteriorly latissimus dorsi, serratus posterior inferior and quadratus lumborum are cut; anteriorly external and internal oblique muscles are cut. Usually 12th or 11th is cut. Rib is identified. Incision is made over its periosteum. Periosteum is reflected using periosteal elevator and rib raspatory. Care should be taken to avoid injury



Fig. 27-12: Position of the patient for loin incision to approach kidney.

to vessels underneath which often need proper ligation. Rib after mobilisation, is cut using bone cutter. Cut end is often smoothened using bone file. Pleura is very close to the rib which should not be opened. If openes pneumothorax develops; which is usually managed by placing vicryl sutures to pleura while anaesthetist keeps ventilating the lung with adequate expansion. Usually intercostal tube is not necessary. Postoperative check X-ray is needed for the evidence of pneumothorax. Transverse abdominis muscle is usually split from posterior to anterior. Peritoneum is adherent to the abdominal wall in front. So care should be taken not to tear on the anterior aspect. Peritoneum is swept forward to reach the Gerota's fascia **(Figs 27-13 and 27-14)**.

Nagamatsu approach gives excellent exposure of the kidney and its pedicle. It is done in same lateral loin position. Incision extends initially vertically from above at its angle inferiorly to the angle of the 12th rib and then running obliquely forward along the 12th rib towards umbilicus just lateral to the rectus muscle. Periosteum of the both 11th and 12th ribs are removed and ribs are excised.

Note: In supracostal and transcostal approaches, diaphragmatic and pleural attachments are released; pleura is pushed upwards carefully without opening it. Costo vertebral ligament should be divided. Iliohypogastric nerve should be mobilised below; subcostal nerve superiorly. Due to lateral position with raise of kidney bridge or breaking of the table venous return to heart decreases as due to IVC compression. One should inform anaesthetist while positioning the patient **(Fig. 27-15)**.

For many procedures of the kidney like nephron sparing nephrectomy, anatrophic pyelolithotomy ice packs are placed on the kidney surface for 20 minutes to increase the cold ischaemic time **(Fig. 27-16)**.



Fig. 27-13: Muscle and fascial layers which come across during posterior approach to kidney.


Kidney bridge of the table is elevated
Incision
External oblique
Incision over the 12th rib
Periosteal elevator

Figs 27-14(1)


12th rib dissected
Peritoneum is reflected medially

Figs 27-14(2)



Figs 27-14(3)

Figs 27-14(1 to 3): Transcostal approach to kidney.



Fig. 27-15: Position of the patient usually used for loin approach for all common procedures including laparoscopic surgeries.

Closure of the Loin Wound

It is done in two layers. Transversus abdominis and internal oblique muscles are closed using continuous vicryl suture as inner layer. External oblique is closed using nonabsorbable or delayed absorbable continuous suture as outer layer. Covering fascia should be included in the bite which is stronger than muscle itself. Drain when needed should be kept below the lower margin of the wound and on the anterior aspect in front of the level of the anterior superior iliac spine; through a separate stab incision.

Incision can be extended into the thorax or into the peritoneal cavity as needed.

High 11th rib excision approach (both 12th and 11ribs are excised subperiosteally) is called as *Nagamatsu approach* which is used in approaching upper pole renal cell carcinoma (RCC).

Problems with Loin Incision

It is more painful, time consuming to open and close. Pleural and peritoneal opining is problematic in this approach. However, it is the most commonly used open approach for surgical interventions of the kidney.

Lumbotomy Incision (Gil-Vernet)

It is done in prone position for both sides; lateral position is possible for unilateral lumbotomy incision, two separate incisions can be placed on both sides in bilateral approach. It is used in bilateral partial nephrectomies, bilateral adrenalectomies. Unilateral lumbotomy incision can be placed in loin position; but it is more painful and retraction is difficult.

It is vertical posterior incision from 12 rib level to lilac crest. Incision is along the lateral border of the sacrospinalis. It extends from the upper border of 12th rib at lateral side of erector spinae downwards and forwards to the level of iliac crest for about 10 cm. It is deepened through latissimus dorsi, serratus posterior inferior, lumbosacral fascia, quadratus lumborum. Subcostal neurovascular bundle and 11th intercostal nerve should be mobilised and preserved. Gerota's fascia is visible; kidney is approached. If needed 12th rib or 12th and 11th ribs need to be excised to have better access. Pleura should not be injured.

Anterior Approaches

Anterior transperitoneal approach—It is done by lengthy midline or paramedian incision. Once laparotomy is done abdomen is explored;



Fig. 27-16: Ice crystals placement on the kidney.

paracolic gutter is incised; colon is mobilised medially; Gerota's fascia is identified; ureter is identified by its location, peristalsis (elicited by tapping), feel, vascular pattern. Pelviureteric junction (PUJ) is identified; gonadal vessels are identified which crosses the ureter from front. IVC is identified and exposed for its full length while doing nephrectomy and vascular ligations.

Anterior extraperitoneal approach may be used—Here paramedian incision is placed; anterior rectus sheath is incised vertically; rectus muscle is retracted laterally; posterior rectus sheath is incised vertically without opening the peritoneum; peritoneum is reflected by finger dissection medially to reach the retroperitoneum renal area.

Thoracoabdominal approach is also anterior approach.

DISSECTION OF THE KIDNEY

It is always better to identify and dissect the vessels to have vascular control prior to dissecting the kidney. In benign diseases Gerota's fascia is opened to reach the kidney, pelvis and upper 1/3rd ureter. In malignancy Gerota's fascia is not opened except in nephron sparing surgeries. It is always better to keep Satisnky vascular clamp ready in the theatre table during nephrectomy.

Right Sided Kidney Dissection

Right side faces challenges due to presence of the IVC, liver and right adrenal vein. Peritoneum is swept by blunt finger dissection medially; right colon will be located deeper to the peritoneum; after mobilisng it medially Gerota's will be exposed fully. Below ureter is identified by finger and cautery dissection. It is slinged using fine polythene tube or infant feeding tube. Gonadals crossing the right ureter is identified. Right gonadal vein joins the IVC behind the duodenum; right gonadal artery crosses the ureter and arises from aorta above the origin of the inferior mesenteric artery at the lateral margin of the aorta. Ureter below crosses the junction of common iliac artery and its branches in front of it. IVC is dissected fully from common iliac vein junction to the duodenum level. Duodenum is mobilised medially. Renal vessels are identified; right renal vein variations are common in its location, and branches. Sometimes double right renal veins may be present. Renal vein is carefully dissected using right angle instrument. It is not ligated but gently kept aside; right renal artery which is deeper and above is identified by its pulsation, isolated and doubly ligated using vicryl no. 1 or divided after transfixation. Aberrant renal artery is identified, dissected and ligated if present. Renal vein is ligated doubly using vicryl no. 1 and divided. Prior division between clamps followed by ligation should not be done because if clamp slips torrential haemorrhage can occur. It is always better to keep the Satinsky vascular clamp ready in case needed. Often tumour extends close to the IVC and it is difficult to dissect in such situation; right renal artery is identified between aorta and IVC, as after its origin it runs behind the IVC to reach the right kidney and is ligated and divided at this juncture.

Tumour thrombus may extend across the renal vein into the IVC. If such thrombus is of short length in the IVC then after applying oblique Satinsky vascular clamps IVC is opened vertically to remove all tumour thrombus, and later venotomy in the IVC is sutured using

3 zero polypropylene continuous suture. If thrombus extends still more proximally extensively then veno cardiac bypass has to be done to achieve complete clearance of the tumour thrombus.

Often tear can occur in the IVC causing torrential haemorrhage (*Pack; Patience; Plan; Proceed* whenever there is bleed); tear should be occluded with thumb and Satinsky clamp should be applied obliquely and IVC is sutured with continuous 4 zero polypropylene sutures.

Left Side Kidney Dissection

Approach is left loin posterior one. All layers are opened to reach the kidney. Peritoneum is usually not breached. Descending colon and splenic flexure is separated by dividing splenocolic ligament and mobilised fully medially to expose the entire left side Gerota's fascia and also left renal pedicle. This also requires dividing the lienorenal ligament. Renal pedicle is dissected; renal vein is in front of the renal artery. Renal vein is carefully dissected and kept aside. Often initially there will be more than one tributaries of the renal vein, in such situation each is isolated and kept aside. By palpating with the finger for pulsation, left renal artery is identified, dissected and doubly ligated. Clips, haemoclips, vascular staplers can be used. Left adrenal vein joins the left renal vein vertically from above; it often needs ligation otherwise torrential haemorrhage can occur. Left inferior phrenic vein joins left adrenal vein which is also should be taken care off. Tail of the pancreas and splenic vein are very close to the upper part of the left kidney and its hilum; they are in front of the kidney. Care should be taken not to injure them which are separated by gentle finger dissection. Once left kidney is dissected fully medially with proper vascular control then only lateral dissection should be done in carcinoma kidney. In benign conditions like pyeloplasty pedicle dissection is not needed; Gerota's fascia is opened to reach the kidney and renal pelvis.

Different types of nephrectomies

Nephroureterectomy – It is done in transitional cell carcinoma of kidney pelvis wherein entire kidney with Gerota's fascia is removed along with entire length of the ureter up to the ureteric orifice.

Nephrectomy – It is done in benign conditions with kidney not functioning – non functioning hydronephrotic kidney (DTPA scan shows function less than 20%).

Radical nephrectomy – It is removing the entire kidney, Gerota's fascia, fat, adrenal gland, lymph nodes, and entire ureter. Presently adrenal gland is removed only if it is invaded by RCC. Lymph node clearance is done only if imaging shows lymph nodes or on table lymph nodes are found.

Subcapsular nephrectomy – It is done in nonfunctioning benign/infective kidney like pyonephrosis wherein kidney is removed at subcapsular plane. As dissection outside capsule is impossible due to dense inflammatory adhesions; if attempted likely to injure the major vessels like IVC to land in disaster.

Heminephrectomy – It is done in duplex kidney wherein one part is totally separate from other anatomically and functionally even though they are covered by a single capsule. Non functioning part is removed after pedicle dissection to identify the specific vessels of that particular part/moiety; those vessels are ligated securely. Dissection through the parenchyma after vascular ligation is very easy as plane is entirely avascular.

Nephron sparing nephrectomy – It is becoming more popular and acceptable method of treatment to surface RCC which is small and well localised wherein kidney is salvaged. Only diseased part with clearance margin is removed and frozen section biopsy is done to confirm the clearance.

Partial nephrectomy – It is removal of one of the poles of the kidney retaining the other pole. It is done when disease is limited to that particular pole only.

Donor nephrectomy – It is done in renal transplantation. Usually left kidney is used as left renal vein is longer.

APPROACHES TO URETER

Oblique Iliac Incision (Abbernethy's/Modified Gibson's)

It is used for *extraperitoneal approach* for ureteric stone, urinary bladder, lumbar sympathectomy. It is muscle cutting incision. It can be used as transperitoneal also.

Position is partial or complete lateral one depending on the side the surgery is needed. Incision is placed from mid-axillary line at the level of the umbilicus directing downwards and forwards towards pubic symphysis up to the lateral margin of the rectus muscle. Skin, subcutaneous fat, superficial fascia, external oblique muscle and aponeurosis below are incised layer by layer in the line of incision. Internal oblique and transverse abdominis muscles are also cut in the line of incision. Under transversalis fascia extraperitoneal fat and peritoneum is visualized. In extraperitoneal approach, peritoneum is swept forward from behind by blunt finger dissection. Psoas major muscle, genitofemoral nerve and inferior vena cava are identified. Ureter with its typical look and peristalsis (*vermiculations*) is also identified. Depending on the type of surgery further procedure is undertaken. Muscle is retracted using self retaining retractor. Peritoneum if inadvertently opened, it can be sutured using 2 zero vicryl **(Fig. 27-17)**.

Paramedian extraperitoneal approach also can be used.

Transperitoneal approach is used when additional abdominal procedures are also warranted.

Laparoscopic and retroperitoneoscopic approaches are good other alternatives.

TREATMENT OF RENAL TUBERCULOSIS

Antitubercular therapy is started. INH, rifampicin, ethambutol and pyrazinamide. Duration of treatment is *one year* **(Fig. 27-18)**.

Surgeries

After 6-12 weeks of drug therapy, surgical treatment is planned. Kidney is exposed. Pyocalyx is drained. Cut edge of the capsule is sutured—*Hanley's renal cavernostomy.*



Fig. 27-17: Oblique iliac incision (Modified Gibson's).



Fig. 27-18: Renal tuberculosis.

Hydronephrosis—*Anderson Hynes* operation or nephrostomy or stenting ("J" stent) of ureter is done.

Renal tuberculous abscess not resolving for 2 weeks should be drained.

Ureteral stricture—stenting/reimplantation of the ureter into the bladder/psoas hitch/Boari's flap/ileal conduit (*Koch's ileal conduit*).

Thimble bladder—hydraulic dilatation/ileocystoplasty/caecocystoplasty/sigmoid colocystoplasty is done.

In unilateral lesion, with gross impairment of renal function—*nephroureterectomy* is done. Indications for nephroureterectomy are - Nonfunctioning kidney; disease extensively involving the kidney; disease causing hypertension and severe obstruction; tuberculous pyonephrosis; coexisting renal cell carcinoma.

TREATMENT FOR HYDRONEPHROSIS

Always conservative surgeries which are aimed at conserving the kidneys are done. Nephrectomy is not done unless indicated **(Figs 27-19 to 27-21)**.

The cause is treated: Stone, congenital anomaly, aberrant renal vessels, stricture urethra (dilatation, urethrotomy, urethroplasty); phimosis (circumcision); BPH (TURP); posterior urethral valve (cystoscopic fulguration of valve).

Pyeloplasty may be dismembered or nondismembered; open or laparoscopic approach. In bilateral cases side which is functioning well should be operated first; after 6 weeks opposite side is operated.

Anderson-Hyne's Operation (Dismembered Pyeloplasty)

This procedure was first done in 1847 for retrocaval ureter. In congenital PUJ obstruction, the spasmodic segment and redundant pelvis are excised. A new pelvis is created and the cut end of pelvis is anastomosed to the ureter in the *dependent* position. Vascular, funnel shaped, dependent, tension free anastomosis should be done. Open approach is usually through loin in lateral position. Once peritoneum is pushed medially; colon is also pushed medially adequately. Ureter in the middle is identified; stent if present in the ureter will guide the identification easier; otherwise it can be identified by its look, peristalsis, location. Peristalsis can be elicited on it. Ureter is dissected and slinged. Proximally dissection is continued towards renal pelvis. PUJ with pelvis and lower pole kidney is identified and dissected properly. Small bleeders in the junction are cauterized using bipolar



Fig. 27-19: Specimen of kidney showing hydronephrosis.



Fig. 27-20: CT scan showing unilateral and bilateral hydronephrosis in differant patients.


Left kidney
Left background
Right background
Summed function image
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
Right kidney BS curve
Left kidney BS curve
Counts/min
28000
24000
20000
16000
12000
8000
4000
0
6x Adn.
0
2
4
6
8
10
12
14
16
18
20
22
Minutes
Renogram analysis curves

	Left kidney	Right kidney
Uptake % (2-3 min.)	61.95	38.15
Time to peak (min.)	2.88	18.88
Time to ½ (min.)	15.03	0.00
Peak count rate (C/min.)	21,044.00	21,690.18

Renogram analysis results

Fig. 27-21: Isotope scan showing hydronephrosis on the right side.


PUJ
Dilated pelvis
Kidney
Stay suture

Fig. 27-22: Stay sutures placed for pyeloplasty.

cautery. Stay sutures are placed one at the upper part of the pelvis laterally; another at lateral lower part of the pelvis medially; one more at the upper end of the ureter **(Fig. 27-22)**.

Pelvis which is redundant is excised within the stay suture area including the diseased PUJ. Specimen is sent for histology. Fish mouth cut is given to the ureter. Lower angle of the ureter is sutured to the lower angle of the cut end of the pelvis. J stent is passed across the ureter and pelvis. Further sutures are placed either continuous or interrupted using 3 zero vicryl sutures to complete the anastomosis. Further left open cut end of the renal pelvis is sutured. Anastomosis should be tension free, dependent. Adequate mobilisation of the lower ureter is often required. Tube drain is placed; wound is closed in layers. Drain is removed in 7 days; J stent is removed in 3-6 weeks **(Figs 27-23 and 24)**.


Pelvis
Congenital PUJ
HN kidney
Ureter

Fig. 27-23: Principles of Anderson-Hyne's operation. Excision of PUJ and redundant pelvis; anastomosis of the ureter with vascularised, tension free, funnel-shaped, dependent stoma.


Kidney
PUJ
Pelvis

Figs 27-24(1)



Figs 27-24(2)

Figs 27-24(1 and 2): Anderson-Hyne's operation—pyeloplasty in an adult.

Complications are – urine leak; infection; inadequate functioning of the kidney; stricture formation at anastomotic site **(Fig. 27-25)**.

Non-dismembered pyeloplasties: Here PUJ is not transected. Reconstruction is done without PUJ transection by different methods, e.g. Foley's Y-V plasty.

Davis T-tube ureterostomy: Placement of T tube in the ureter by making longitudinal incision.

In bilateral HN, without renal failure, *kidney which is functioning better should be operated first.* Three months later, otherside kidney is dealt with. In bilateral HN with renal failure, *bilateral nephrostomy and haemodialysis* support is required initially. After 3-6 weeks IVU is done and the functions of both kidneys are looked for. If they function, then are treated accordingly by Anderson-Hyne's operation. *If kidneys are still not functioning (renal function <20% on isotope study) then nephrectomy and renal transplantation* is the only option left.

Laparoscopic or *retroperitoneoscopic pyeloplasty* is becoming popular but is expensive and time consuming. It gives good result as well **(Fig. 27-26)**.

Endoscopic pyelolysis, even though technically easier results are not assured.

Aberrant renal artery or *vein* in the lower pole of kidney can compress the PUJ causing HN. Renal angiogram confirms the diagnosis. *Treatment of aberrant renal vessels*—If it is a vein it can be ligated safely. But if it is an artery, it exclusively supplies the lower pole


Renal pelvis
Stay sutures
Spatulating the
ureter-fish mouth

Fig. 27-25: Anderson-Hyne's operation – pyeloplasty in a child.


Position of the patient
Monitor
Position of surgeon
Open approach incision
Anterior rectus sheath is incised
Anterior rectus sheath is incised
Rectus muscle is split
to reach the posterior rectus sheath
Rectus sheath sutures are taken
in both sides of the port using vicryl

Figs 27-26(1)


Colon mobilisation
Ureter
Ureter
Pelvis
Cutting the pelvis

Figs 27-26(2)



Figs 27-26(2)

Figs 27-26(1 and 2): Laparoscopic pyeloplasty is standard now. Initially cystoscopy is done to pass a ureteric catheter or J stent. Loin position (lateral) is used. Camera port is at the level of the umbilicus through the rectus muscle. Horizontal 1.5 cm incision is made; anterior rectus sheath is incised horizontally; rectus muscle is split; posterior rectus sheath and peritoneum is opened. 10 mm port is passed; two vicryl sutures on two diagonally opposite sides of posterior rectus sheath is taken and kept long for tying at the end of the procedure. Pneumoperitoneum is created. One 10 mm and another 5 mm ports on either side and laterally are passed under vision as working ports. Additional 5 mm working port can be added if need arises. Lateral paracolic gutter is incised along the Toldt's line; colon is mobilised fully medially from the Gerota's fascia; i.e. right side hepatic flexure and left side splenic flexure. Ureter is identified; gonadal vein is crossing the ureter on right side; on left side gonadal vein lies adjacent to ureter on its medial aspects without crossing it. Ureter is identified by its tubular nature, colour, peristalsis, vascular network. IVC is identified on the right side. Ureter is dissected upwards towards the renal pelvis which is mobilised all around. PUJ is identified and dissected. Renal pelvis is incised and cut in V-shaped manner. PUJ is also excised along with that. Spatulation of ureter (fish mouth) is done on its lateral side from its cut end using scissor. J stent is passed if not passed earlier; it is pushed towards the renal pelvis. Bite with 3 zero vicryl is taken from its apex of the spatulation from outside to inside then it is passed to the lower cut end of the pelvis from inside to outside. Knot is placed outside. One should not place knots inside in the urothelium anywhere. Continuous sutures are taken, first posterior layer is done between ureteric cut part and pelvis cut part; Once posterior layer is finished knot is tied. Using new 3 zero vicryl anterior layer sutures are taken similarly. Proximal part of the renal pelvis is again separately sutured and closed. Secure dependent vascular funnel-shaped tension free anastomosis is achieved. Tube drain is placed; port sites are closed.

of the kidney and so cannot be ligated. So kidney is mobilised; upper and lower poles are approximated together so that artery is made to slip away from the site of compression—*Hamilton Stewart operation*. Nowadays this operation is not done. Vessels are dissected carefully and kept aside (preserved) and PUJ is transected and anastomosed in front of the vessels **(Fig. 27-27)**.

TREATMENT OF PYONEPHROSIS

After starting antibiotics, pus is immediately drained from the kidney through a loin incision and *nephrostomy* tube (Cabot's nephrostomy) (Malecot's catheter) is placed. If kidney is totally destroyed, *subcapsular nephrectomy* is done. This also prevents other kidney from getting infected through perirenal lymphatic connections. Approach is though loin. Adhesions are common. It is often difficult to identify the major vessels and renal pedicle. Injury to renal vein, IVC is known to occur. Often mass clamping at the pedicle with transfixation ligatures using polypropylene sutures are better rather than individually identifying and ligation the vessels. If IVC tear is suspected the incision is extended, peritoneum is opened; duodenum and posterior abdominal wall is dissected to identify the IVC completely. Tear is identified with placement of vascular clamps. Tear is sutured. In bilateral pyonephrosis, *bilateral nephrostomy* is the only choice. *'J' stenting* is done often to keep the ureters patent.





Fig. 27-27: Aberrant renal vessels.

TREATMENT OF RENAL STONES

PCNL (Percutaneous Nephrolithotomy)

Indications are - Stones more than 2.5 cm in size; multiple stones; Stones not responding for ESWL.

Procedure: Initially cystoscopy is done and ureteric stent/catheter is placed and renal pelvicalyceal system is identified under C-arm guidance. Under the guidance of C-arm or U/S, needle puncture is made in the loin percutaneously. Through kidney, calyx and pelvis are approached. Guide wire is passed. Graduated dilators are passed and so track is widened. Then through that, a nephroscope is passed. After fragmentation, stone is removed using different methods [Laser (Holmium), pneumatic, ultrasonic or electrohydraulic] **(Fig. 27-28)**.

Complications of PCNL: Haemorrhage; perforation of collecting duct causing extravasation of irrigation fluid; *injury to colon or pleura* while creating initial track for nephroscope.



Fig. 27-28: PCNL—technique. It is commonly done procedure now for renal stone.

ESWL (Extracorporeal Shock Wave Lithotripsy) (Fig. 27-29)

Piezo-Ceramic or *Electromagnetic* shock waves are passed to the stone through water bath or water cushion which acts as a media. Shocks are produced at 2/sec. 1000-4000 shocks are required for each stone. *Dornier Lithotripter* is used for fragmenting stones. Stone is located and observed through fluoroscope (C-arm) or ultrasound. Shock waves are triggered to create *compressive waves* over the stone, to fragment it. These fragments are flushed out later.

Advantages—No anaesthesia is required. Can be done as an OP procedure, less than 2.5 cm sized stones are well fragmented, hard stones, oxalate stones are better eliminated by ESWL, ESWL can be done repeatedly in different sittings, if it is not successful one can switch over to PCNL.



Fig. 27-29: ESWL table and machine used for renal stones. It needs C-arm to guide the exact point of stone to be fragmented.

Complications—Renal haematoma; Severe haematuria; injury to adjacent structures; fragmented stone retains in the ureter.

Contraindications—Pregnancy; bleeding disorders; patients with abdominal aneurysms; sepsis and renal failure (Serum creatinine more than 3 mg%).

Surgeries (Fig. 27-30)

Pyelolithotomy: It is suitable for stones in extrarenal pelvis. By loin (posterior subcostal) incision, kidney is approached. Renal pelvis is opened, the stone is removed and the pelvis is closed using 3 zero vicryl. A drain is placed and wound is closed **(Figs 27-31 and 27-32)**.

Extended pyelolithotomy (Gil-Vernet): In case of intrarenal pelvis, incision is done on the hilum between the pelvis and kidney over the renal sinus, dissection is carried out so as to remove the stones from pelvis as well as calyces.

Nephrolithotomy: By placing incision just behind the most convex surface (Brodel's line), stone is removed.

Nephropyelolithotomy: By making incisions both over the kidney and pelvis, stone/stones are removed. It is often done in *staghorn calculus* **(Fig. 27-33)**.

Partial nephrectomy: Done when there are multiple stones occupying a pole, usually lower pole of the kidney or when there is damage to the calyx, if not removed may encourage further stone formation.

Bench surgery: Kidney is removed out temporarily, cooled by ice packs or inosine or liquid nitrogen. Stones are searched and removed completely. Later kidney is replaced in right iliac fossa.

Coagulum pyelolithotomy: Coagulum solution which contains fibrinogen is poured into the renal pelvis. It is activated so that it solidifies,



Fig. 27-30: Bilateral renal stones (large) with right ureteric stone.



Figs 27-31(1)



Figs 27-31(2)



Figs 27-31(3)

Figs 27-31(1 to 3): Very large renal pelvic stone of more than 8 cm in size weighing 610 grams. It is one of the largest renal stone extracted (*Courtesy:* Dr Ashok Pandit, MCh, Urologist, Mangala hospital, Mangalore).

meanwhile entangling the stones in renal pelvis. This entangled mass is removed en masse.

Anatrophic pyelolithotomy: After exposing the kidney, it is cooled with ice packs for 20 minutes and posterior branch of the renal artery is clamped temporarily using bull-dog clamp. The most avascular plane behind the Brodel's line is thus visualised properly. Kidney is opened through this line and stone/stones are removed (anatrophic means "to prevent atrophy") **(Fig. 27-34)**.

REMOVAL OF URETERIC STONE

Problems with ureteric stones – Obstruction, hydronephrosis; infection, impaction, ureteric stricture **(Fig. 27-35)**.

Surgical Intervention for Ureteric Stones

Indications - Size of the stone more than 5 to 8 mm. IVU showing deterioration of function. Co-existing infection. If stone is impacted in the ureter with persistent symptoms **(Fig. 27-36)**.

Upper third stone: ESWL is used for stone in upper third ureter. The stone is pushed into the renal pelvis and then PCNL is done.

URS—*Ureterorenoscopic stone removal*. Through ureteroscope, stone is visualised and often fragmented using pneumatic bombarder. It is then extracted by ureteroscope. Complications are perforation of ureter and extraperitoneal leakage of urine, bleeding. Open *ureterolithotomy is done* through loin incision **(Fig. 27-37)**.

Stone in middle third ureter: URS; open ureterolithotomy; laparoscopic stone removal.

Stone in lower third ureter: URS; *Dormia basketing* **(Fig. 27-38)**.

Indications for Dormia basketing - Stone in lower third ureter, stone below pelvic brim, stone less than 10 mm size, single stone, basket is passed into the proximal ureter beyond the stone and opened. The stone is then pulled out.

Complications of Dormia basket - Stone dislodgement, urethral injury, avulsion of ureter, stricture ureter, open ureterolithotomy.

Using cystoscope under general anaesthesia, *uretericmeatotomy* is done for stones impacted at the ureteric orifice. It is released by cutting the orifice at upper and lateral aspects.

Note: All ureteric stones can also be removed through laparoscopy or retroperitoneoscopy.

Open Ureterolithotomy

Nowadays open approach is not commonly done; however surgeon should be familiar with the technique. On the day of surgery, plain X-ray KUB should be taken to confirm the location of the stone or ultrasound should be done. Large impacted stone which is not amenable to remove by any endourology technique is removed by open method. Oblique loin incision (*Modified Gibson's*) extending down towards the hypogastric region suprapubically – is used. It is an extraperitoneal approach. Skin, superficial fascia, external oblique, internal oblique are cut in the line of incision; transversus abdominis is split from behind forward as its posterior aspect not adherent to the peritoneum compared to anterior aspect; this avoids inadvertent opening of the peritoneum. Peritoneum is swept forward and medially by blunt finger dissection and this plane is avascular. Care should be taken not to enter behind the psoas major; if it


Mayo's table
Scrub nurse
Surgeon
Assistant
Left sided kidney aproach
Incision
Latissimus dorsi
serratus posterior inferior
12th rib
Cutting the 12th rib

Figs 27-32(1)


External oblique
Internal oblique
Transversus abdominis
Peritoneum
Kidney is exposed
ureter dissection
Pelvis
PUJ
Ureter-slinged
Peanut dissection

Figs 27-32(2)


Stay suture
Stay suture
Pelvis
Kidney
Ureter
Incising the pelvis with 15 no blade
Stone extraction from the renal pelvis

Figs 27-32(3)


Small nephrotomy to remove other calyceal stones
Giving warm saline wash to pelvis, calyces and ureter
Pyelotomy wound to be sutured after placing J stent
Guide wire
Stent

Figs 27-32(4)


Passing J stent below along the ureter
J stent other end is pushed into the renal pelvis
Closure of the pyelotomy wound

Figs 27-32(5)


No 11 blade is used to create a stab wound for tube drain
Tube drain is placed
Wound closure in two layers using vicryl

Figs 27-32(6)

Figs 27-32(1 to 6): Technique pyelolithotomy – open method. Now usually stones are removed through PCNL, ESWL or laparoscopic approach.



Figs 27-33A to F: Surgeries for renal stones. (A) Pyelolithotomy, (B) Extended pyelolithotomy, (C) Nephropyelolithotomy, (D) Nephrolithotomy, (E) Partial nephrectomy, (F) Coagulum pyelolithotomy.


Sterile ice crystals
Vascular control using Satinsky clamp

Figs 27-34(1)


Nephrotomy adjacent
Brödel's line
Stone extraction
Closure of nephrotomy
using vicryl

Figs 27-34(2)



Figs 27-34(3)

Figs 27-34(1 to 3): Anatrophic nephropyelolithotomy. Vascular clamp is applied to the pedicle. Ice packs are kept over the kidney for 20 minutes; nephrotomy is done adjacent to Brodel's line to remove all stones. Nephrotomy wound is closed using vicryl. Nephrostomy (optional) and J stent (always) is kept in place. Vascular clamp is removed. Tube drain is placed; wound is closed in layers.


PUJ
Crossing of iliac artery
Crossing of vas deferens
Bladder musculature
Ureteric meatus

Fig. 27-35: Sites where a stone can get impacted in the ureter—narrow parts of the ureter.


Upper third
• Flush
• ESWL
• PCNL
• URS
• Open ureterolithotomy
Middle third
• Flush
• URS
• Open ureterolithotomy
Lower third
• Flush
• URS
• Dormia basket
• Ureteric meatotomy
• Open ureterolithotomy

Fig. 27-36: Approaches for ureteric stones at different levels.



Fig. 27-37: J stent is commonly used for all urologic surgeries whether open or laparoscopic.

happens plane will be lost and unnecessary troublesome bleeding can develop. Genitofemoral nerve is identified; ureter is identified by its peristalsis; it is dissected and sling is passed around it. Gently ureter is palpated towards the distal narrower part from proximal dilated part (due to impacted stone). Stone is palpated without giving room for its slippage; carefully ureter distally is also dissected and held with a tape/sling. Both slings held taut to prevent the slippage of the stone in both directions. Two 3 zero vicryl stay sutures are placed; stone is steadied between fingers; longitudinal incision is made directly on the stone from below upwards; grating sensation will be felt while making the incision; stone is retrieved; using fine polythene tube warm saline irrigation is flushed both proximally and distally to clear small particles of the stone. An infant feeding tube is passed distally to confirm that there is no obstruction. J stent is passed across the ureter which is removed after 6 weeks. Ureter incision is closed with 3 zero interrupted vicryl sutures taking bites only from the muscular layer. If wall of the ureter is odematous and friable it is not necessary to suture the ureter; J stent placement is sufficient. Tube drain is placed into the cavity. Wound is closed in layers.

TREATMENT OF STAGHORN CALCULUS

Antibiotic is started. *Unilateral stone* is removed by *nephropyelolithotomy*. Multiple incisions are made over the Brodel's line (avascular plane) and assisted by pelvic incision. Stone is removed. Blood transfusion may be necessary as bleeding can occur. After that, nephrotomy and pyelotomy incisions are sutured with 3 zero vicryl **(Fig. 27-39)**.



Fig. 27-38: Dormia basket is used to remove the stone in the lower ureter. Single stone less than 1 cm can be removed.



Fig. 27-39: (A) X-ray showing staghorn calculus. (B) Large staghorn calculus removed from another patient.



Fig. 27-40: Nephropyelolithotomy. *Note* the incisions placed.

In *bilateral cases* IVU is very essential. The kidney which is functioning better should be treated first. After 3 months, the other side kidney should be operated upon. If there are *bilateral staghorn calculi with pyonephrosis,* then initially bilateral nephrostomy is done using Malecot's catheter *(Cabot's nephrostomy*). IVU is done later to see the renal function. If function is present, then both kidneys are operated one after the other in a gap of 3 months. They often need *haemodialysis.* Sometimes in case of severe infection *nephrectomy* is required. *Presently, PCNL is becoming a popular procedure for unilateral or bilateral staghorn calculi.* But when required, *conversion to open nephropyelolithotomy* should be considered **(Fig. 27-40)**.

Complications of staghorn calculus – Pyelonephritis, pyonephrosis, perinephric abscess, renal failure.

TREATMENT OF RENAL CELL CARCINOMA

Surgery is the treatment of choice. Initial CT imaging and proper evaluation is a must **(Fig. 27-41 and 27-42)**.



Fig. 27-41: CT scan of renal cell carcinoma.

Radical nephroureterectomy: *Structures removed are* entire kidney along with tumour; perinephric tissue; ipsilateral adrenal gland (adrenal gland can be spared); proximal 2/3rd ureter/as low as possible; lymph nodes from crus of diaphragm to aorta bifurcation with renal



Fig. 27-42: Large upper pole renal cell carcinoma.

hilar nodes. Transperitoneal approach is often used. Retroperitoneal/ Nagamatsu (resection of 11th ribs) approach/thoracoabdominal approach/posterior vertical are other approaches used. Patient will be in lateral position. After laparotomy, colon is mobilised medially. Vessels are identified and dissected and ligated securely (transfixation and three ligatures proximally using nonabsorbable silk/ polypropylene sutures). Preoperative renal artery embolisation can be done to decrease vascularity and to facilitate the removal of entire tumour. Always renal vein is ligated early so as to prevent tumour dislodgement (But early ligation of renal vein may cause congestion and torrential bleeding and so renal artery is ligated first commonly in practice). But usually renal artery which is posterior is dissected and clamped or ligated in continuity; then renal vein is ligated and divided; later ligated renal artery is divided. In case of IVC extension of tumour thrombus (8%), after applying an oblique vascular clamp, IVC is opened, tumour thrombus is removed and IVC is sutured. In supradiaphragmatic vena caval extension of thrombus, cardiopulmonary bypass is necessary. First renal vessels (artery and vein) should be ligated to prevent tumour dissemination and bleeding. Lymphadenectomy is not necessarily undertaken routinely; it is only done when imaging shows significant nodal enlargement or on table enlarged nodes are seen.

Even in large fixed tumour, palliative nephrectomy or debulking is advised as it may cause regression of secondaries.

Nephron sparing surgeries are done in bilateral RCC (bilateral partial nephrectomy). Renal artery is temporarily occluded using vascular clamps and kidney is cooled to have proper control of bleeding and adequate visualisation of the line of resection. Partially resected specimen is assessed by frozen section biopsy. Retained partial capsule is sutured after haemostasis. Renal arterial clamp is released. It is presently done for unilateral localized tumours also. After isolation of the renal artery with placing icepacks to control the ischaemic time, artery or its branch is clamped using vascular clamp. Icepacks are already in place. Tumour with clearance margin of 5 mm to 10 mm is excised; sent for immediate frozen section biopsy. Bleeding is controlled using continuous 3 zero vicryl sutures. Methylene blue is injected from below across the ureteric catheter; if renal excised wound stains blue that means there is disruption of the calyces and it should be sutured. Arterial clamp is released. Any bleeding points if present are sutured. Surgicel is placed on the raw area. Drain is placed. Loin wound is closed. Warm ischaemic time for kidney is 30 minutes; cold ischaemic time is up to 4 hours **(Fig. 27-43 to 27-44)**.

Partial nephrectomy (Carl Boye Semb, university of Oslo)– It is done when disease is limited to one of the poles usually lower (T1a, T1b). Polar vessels are ligated and polar segment of the kidney is resected. Cut raw area is sutured with continuous 3 zero vicryl sutures. Tube drain is placed. Procedure is done through loin incision **(Fig. 27-45)**.

Complications

Intraoperative

Bleeding can occur from IVC, renal vein or branches. Vascular clamps should be used to control the bleeding. Vessel wall is sutured using continuous polypropylene 4 zero or 3 zero sutures.

Bowel injuries can occur especially to colon which is close to Gerota's fascia. If injury occurs then temporary colostomy or ileostomy is needed for 3 months after which it is closed. Sharp dissection injuries or cautery injuries can occur.

Injuries to liver, gall bladder, spleen (on left side) can occur during dissection due to avulsion. Pancreatic injury on left side can also occur. Injury to pleura, diaphragm are not uncommon **(Fig. 27-46)**.

Postoperative

Delayed bleeding, pseudoaneurysm formation, arteriovenous fistula can occur in nephron sparing nephrectomy. It is usually treated by therapeutic angioembolisation.

Infection, abscess formation, septicaemia can occur after any type of nephrectomy. Lymphocele can develop after lymphadenectomy.

Raised creatinine level in postoperative period in many nephrectomies.

TREATMENT OF POLYCYSTIC DISEASE OF KIDNEY

Initially wait and watch policy. If one of the cysts overdistends causing pain, haemorrhage, infection, then surgical intervention is required. *Rovsing operation*: The kidney is exposed. The cyst is opened. The fluid is evacuated. The cut edge is marsupialised. Presently U/S guided aspiration is done as a simpler approach. Laparoscopic/retroperitoneoscopic aspiration/de-roofing of the renal cyst is also commonly done. Once renal failure sets in, then initial haemodialysis followed by bilateral nephrectomy, is done and later renal transplantation should be planned for.

TREATMENT OF SOLITARY RENAL CYST

Kidney is exposed. The cyst is aspirated and a portion of the cyst wall is removed (*Kirwin's operation*) and cavity is filled with perinephric fat. Occasionally if the cyst is in one of the pole, partial nephrectomy is done. Laparoscopic approach is ideal.


28.2mm
28.1mm
10 cm
P

Figs 27-43(1)



Figs 25-43(2)



Figs 27-43(3)

Figs 27-43(1 to 3): Nephron sparing nephrectomy.

TREATMENT OF BLADDER STONE (FIG. 25-47)

Cystoscopic litholapaxy - Under general anaesthesia, cystoscope is passed and the stone is visualised. It is fragmented by pneumatic, laser, electromagnetic waves or mechanohydraulic lithotripsy. The bladder is flushed using an irrigator (Freyer's evacuator or irrigator or Ellik's evacuator).

Contraindications are - Too large stone; too small stone, too soft stone, too many stones, stone in bladder diverticula, bladder tumour, contracted bladder, patient's age below 10 years. When patients general condition is poor, as the procedure takes a longer duration it is avoided and open removal is advised. However presently most of the stones can be removed through cystoscopy except very large and hard stone **(Fig. 27-48)**.

Suprapubic open cystolithotomy - Through Pfannenstiel incision, bladder is approached extraperitoneally. Bladder is identified by its detrusor muscle pattern, which has criss-cross pattern and also its venous pattern. Bladder is opened near the fundus vertically between stay sutures; incision should avoid venous plexus and stone is removed. Bladder is closed with 2 zero vicryl continuous single layer or two layers sutures. Often SPC is added using Malecot's/Foley's catheter but is not mandatory. Foley's catheter is passed per urethera which is removed after 3 weeks. Wound is closed in layers with a drain in retropubic space **(Figs 27-49 and 27-50)**.

Suprapubic percutaneous litholapaxy - This procedure is becoming popular. When cystoscope cannot be passed per urethra, bladder is approached suprapubically. Through a needle, guide wire and dilators, a track is created through which a nephroscope is passed to remove the stone after fragmenting. The cause is treated **(Fig. 27-51)**.

TREATMENT OF BLADDER TUMOURS

Noninvasive Tumour

Endoscopic resection of tumour is ideal. *Intravesical chemotherapy* using BCG (Dose: 120 mg in 150 ml of normal saline weekly for six weeks), mitomycin C, epirubicin, adriamycin, thiotepa, methotrexate can be given especially for carcinoma *in situ*. BCG is very useful. Very rarely *BCG provocation* can occur. Fever, joint pain, granulomatous prostatitis, sinus formation, disseminated tuberculosis are the features. Dysuria, frequency and urinary irritation can occur. BCG is *live attenuated vaccine*; its advertent IV entry can be *life threatening* and so if there is haematuria its infusion should be postponed. Mitomycin C causes skin desquamation and rash. *Systemic chemotherapy*: Using cisplatin, 5-FU, adriamycin, mitomycin.

Helmstein balloon degeneration for large papillary tumour. Balloon is passed into the bladder and inflated so as to cause pressure necrosis of the summit of the tumour. Later remaining part of the tumour can be resected easily through cystoscopy.

Invasive Bladder Tumour

Curative interstitial radiotherapy using implantation of radioactive gold grains (Au 198) (half life is two and half days), or radioactive tantalum wires (Ta 182) (half life is 4 months).

Radical deep external beam radiotherapy (45 Gy) using cobalt 60 is useful, as bladder is retained normal act of micturition and potency can be maintained. Complication is that it may eventually lead to formation of thimble bladder **(Fig. 27-52)**.


Tumour
Loin incision/approach
Vascular control (renal artery sling)
Tumour / RCC
Tumour excision with clearance - 1 cm

Figs 27-44(1)


Adjacent Gerota
Tumour specimen
Vicryl suturing of the bed to control bleeding
Bipolar cauterisation
Injection of methylene blue through ureteric catheter
Methylene blue leak - calyceal opening which should be sutured

Figs 27-44(2)



Figs 27-44(3)

Figs 27-44(1 to 3): Nephron sparing nephrectomy in a different patient with vascular control using a bull dog clamp.



Fig. 27-45: Partial nephrectomy. Procedure is done through loin posterior approach. It is done for lower pole tumour. Segmental/polar vessels are ligated and kidney is divided; surface is sutured; surgicel is placed; J stent should be placed; wound is closed with a tube drain.


Pleural injury should be sutured using vicryl continuous sutures

Fig. 27-46: Pleural injury can occur while approaching kidney. It should be sutured with vicryl continuous sutures. Anaesthetist should inflate the lung fully while taking the last bite from the pleura to inflate the lung properly.



Fig. 27-47: X-ray showing bladder stone.

Surgery

Indications for surgery - Multiple bladder tumours, sessile tumours, recurrent tumours, poorly differentiated tumours, *in situ* carcinomas, squamous cell carcinoma, adenocarcinomas.

Partial cystectomy done when tumour is confined to fundus of the bladder and is single, with a margin of clearance of 2.5 cm. External beam RT and chemotherapy should be given. Partial cystectomy can be done through laparoscopy easily. Through cystoscopic guidance



Fig. 27-48: Doing cystoscope as diagnosis and to remove bladder stone by fragmentation.



Fig. 27-49: Large oxalate stone removed from the urinary bladder.



Fig. 27-50: X-ray showing SPC with Malecot catheter.



Fig. 27-51: Asepto syringe used for bladder wash in patients with urinary catheter which has been blocked; or when haematuria is noticed in the catheter. It is also used to fill the bladder with saline.



Fig. 27-52: CT picture showing bladder tumour. Specimen showing transitional cell carcinoma of bladder.

and laparoscopy tumour margin is marked on the bladder surface; resection is done through the laparoscopy; bladder wall is sutured by intracorporeal continuous vicryl sutures. Position and port sites are almost similar to laparoscopic hysterectomy. Partial cystectomy is also done often along with sigmoid resection, ileal resection or with hysterectomy whenever disease processes like diverticulitis, Crohn's disease or malignancy invades the bladder partially. Along with the resection of the primary tumour and organ, disc of urinary bladder attached to the colon or ileum is removed; primary suturing of the bladder wall is done using 2 zero vicryl sutures.

Radical cystectomy: CT scan is a must before doing radical cystectomy to see the pelvis and lymph node status. Here urinary bladder, urethra, paravesical tissues, lymph nodes (pelvic) are removed. In females hysterectomy with removal of part of the vagina is done. After surgery urinary diversion is done either by doing continent ileal conduit, or ureterosigmoidostomy or by creating rectal urinary pouch.

Intravesical chemotherapy by BCG, mitomycin C, adriamycin and interferons are used later.

Systemic chemotherapy by cisplatin, adriamycin, mitomycin, vinblastine—adjuvant therapy. Neoadjuvant cisplatin based chemotherapy is beneficial improving survival by 7%. MVAC regime is methotrexate; vinblastine; adriamycin and cisplatin.

Prognosis

Depends on type, differentiation, location, stage, invasion, number, lymph node status, pelvis involvement and response to treatment. TCC alone—85%; TCC with SCC or adenocarcinoma—6%; SCC/adenocarcinoma alone—3%; spindle cell carcinoma— 2%.

RADICAL CYSTECTOMY

It is done as a curative surgery for bladder carcinoma. Staging, cystoscopic biopsy, preliminary preparation for anaesthesia should be done.

Procedure is done under general anaesthesia in supine head down position. Head down (reverse Trendelenburg) position helps in keeping the bowel in the proximal abdomen away from the surgical field.

Technique

Lengthy midline incision is placed to open the abdomen. Incision extended above the umbilicus should be towards left side of the umbilicus. Abdomen is explored for liver, nodes and metastases in other areas. Median umbilical ligament is divided at umbilical level; it is dissected towards the dome of the urinary bladder. Lateral bladder dissection is done; vas deferens is identified, dissected, ligated and divided. Medial umbilical ligament is similarly dissected and divided between ligatures. Superior vesical artery (vessels) is ligated and divided. Posterior dissection is done in rectovesical plane after opening the peritoneum in rectovesical pouch. Fascia of Denonvillier's is dissected downwards. Dissection is done between rectum and urinary system. Neurological bundle of Walsh can be scarified in radical surgeries. Seminal vesicles, prostate is identified; dissection is reached towards the apex of the prostate identifying the membranous urethra. With bipolar cautery harmonic scalpel ligation, vessels are dealt. Venous plexus in the lateral aspect is divided between secure ligatures. Dissection in the retropubic area in the space of Retzius is undertaken by blunt finger and sharp scissor dissection. Many vessels in this area should be ligated otherwise troublesome bleeding can occur. Dissection is done beyond the prostate. Both ureters are divided close to the trigone; cut end pieces of ureters are sent for frozen section biopsy. Lymph nodes are cleared from common iliac artery downwards along the iliac vessels up to Cloquet (Rosenmuller) lymph node which is cleared; posteriorly nodes are cleared up to obturator nerve. Lymph nodes on both sides are cleared according to template. Iliac and obturator lymph nodes are cleared completely.

Urethra distal to prostate is transected. 24 no. French sized Foley's catheter is passed per urethra from below and is inflated, pulled with traction; it gives compression to prostatic bed to prevent bleeding and also acts as drainage.

Reconstruction is planned. It is creation of neobladder and achieve drainage either by suturing the neobladder pouch to the cut end of urethra as orthotopic drainage; or neobladder is exteriorized after ureteral reimplantation into the created pouch.

Creation of Pouch

Two types of pouches is used. One pouch is ileal W pouch with creation of continent at its summit; summit is brought out with valve mechanism created in it through the right iliac fossa. Other pouch is caecal and ascending colon pouch with terminal ileum as a passage with intussuscepted ileum towards the caecum as valve mechanism. Here 15 cm of terminal ileum is selected; additional further proximal 5 cm is also taken to create intussusception. Right colon is mobilized from right paracolic gutter, hepatic flexure, and right half of the transverse colon. Colonic mesentery is not ligated; right branch of the middle colic artery is ligated; left colic artery should be retained and also arcade of the terminal ileum. Ileum is transected either by stapler or with knife and cautery; right half of the transverse colon is transected; ileo transverse colon anastomosis is done. Mesenteric defect is closed. Harvested ileocolic segment is mobilised carefully towards right side without interrupting its blood supply; it is achieved by mobilising the mesentery up to the 3rd part of the duodenum. Ascending colon, part of the transverse colon in the harvested part is opened using scissor or cautery along the taenia. Ileocaecal valve is identified. Distal part of the harvested ileum is skeletonised for 5 cm which is intussuscepted towards ileocaecal valve; it is achieved by passing a long Babcock's clamp through the lumen and holding the ileal wall from inside at 5 cm from the ileocaecal junction and pulling it distally towards the caecum. Once it is intussuscepted its terminal mucosa is denuded for 2-3 cm and sutured again to prevent it retracting backwards; it functions like a valve. Foley's catheter 20 sized is passed from the cut end of the harvested ileum to confirm the patency and is placed in the caecum with inflation. Two ureteric catheters are passed through it towards caecum and kept. One of which is labeled or marked with tie to identify the side. Right side ureter is mobilized proximally for adequate length. Left side ureter is also mobilised adequately and is passed behind the mesentery from left towards right. Both ureters are reimplanted into posterior part of the caecum/ascending colon at around 1-2 cm gap. Small stab incision of 8-10 mm length is made in the right half of the caecum or proximal ascending colon; ureter is transected near its cut margin obliquely (fish mouth). Stent marked right is passed through right ureter into the pelvis. It is anastomosed to the caecal wall using interrupted 3 zero vicryl sutures with knots outside. Similarly left ureter is implanted into the caecum posteriorly on its left side. Opened ascending colon is closed horizontally to create a colonic pouch. An independent Foley's catheter is passed through the separate wound in front of the caecum to bring it as ostomy from the pouch to drain it. Length of the ileum is assessed to have adequate shortest distance from the pouch to reach right iliac fossa, the site of ostomy (stoma) which is permanent. Circular piece of the skin is excised in the spinoumbilical line in front of the rectus muscle. Either cruciate incision is made in the anterior rectus sheath or similar disc of the sheath is removed. Rectus muscle is split; peritoneum is opened; assistant will give counter pressure through a mop covered finger from inside while creating stomal opening. Care should be taken not to injure the inferior epigastric vessels. Cut ileal end of the harvested segment is brought out using a Babcock's clamp. 2 cm proximal from the cut end of the ileum seromuscular interrupted sutures are placed between the bowel and anterior rectus sheath using 3 zero vicryl. Even though it is not mandatory it is often practiced to fix the bowel to the peritoneum by interrupted vicryl sutured adjacent to stomal opening. Skin is sutured to the cut edge of the ileum; while initially taking seromuscular bites away from the cut edge then from the mucosa at the edge, then from the full thickness skin it is taken so as to create protrusion of the mucosa of stoma outwards – *Brooke's method of maturation of the urinary conduit.*

Gastrostomy may be done for feeding and aspiration purpose. Suction tube drains are placed one in the pelvis another in the right side abdomen. Abdomen is closed in layers.

***Note*:** There are many methods of creating pouches – Mainz pouch (Ileo colic); Indiana pouch; orthotopic pouches like studer neobladder of ileum; Hautmann neobladder of ileum; Monti and spiral Monti types.)



Fig. 27-53: Ureterosigmoidostomy.

URETEROSIGMOIDOSTOMY (Henri Chaput, 1894, French Surgeon)

It is a procedure done for urinary diversion after radical cystectomy or as a permanent diversion for many other causes, e.g. bladder dystrophy. Left ureter is implanted to the sigmoid colon, right one to the upper rectum or rectosigmoid junction. Collecting system is not necessary here; but exposure of urinary tract to faecal infection is the real problem.

Different types of ureterocolic anastomosis are present. Fish like incision on the sigmoid by incising the seromuscular layer lengthier and mucosa is opened on the end of this incision to anastomose cut end of ureter on it. Coffey, Grey Turner, Nesbit, Cohen's, Cordonnier type; Leadbetter are different types. In Leadbetter (Boston, USA) type submucosal tunneling is done to prevent reflux.

Complications

Because the pressure in sigmoid colon is more, it causes *pyelonephritis* and recurrent upper urinary tract infection. Due to diarrhoea *hypokalaemia occurs.* Because of reabsorption of chloride, *hyperchloraemic acidosis* occurs. *Treatment of complications* - IV sodium bicarbonate (8.4%) with slow IV potassium; IV antibiotics; Patient is advised to take potassium citrate and sodium bicarbonate and to avoid salt; in many cases conversion to *ileal conduit* may be required.

Stricture formation is common in ureterosigmoidostomy. Mucosa to mucosa anastomosis may prevent this **(Fig. 27-53)**

URINARY DIVERSION

It is diversion of urine temporarily or permanently, proximal to the site of obstruction. Temporary type is done in benign conditions and distal obstructions, to promote healing. Permanent type is done in advanced malignancies which block the urine flow distally, after radical cystectomy, after radiotherapy with frozen pelvis, etc **(Fig. 27-54 and 27-55)**.



Fig. 27-54: Types of urinary diversions.



Fig. 27-55: Ileal conduit as urinary diversion.

Temporary Diversions

Suprapubic cystostomy (SPC); vesicostomy in children in ectopiae vesicae, epispadias, urethral anomalies; urethrostomies; nephrostomies in pyonephrosis and high obstructive uropathies; pyelostomies are other procedures; ureteral J stent is a method of internal temporary diversion which is kept maximum for 3 months.

Permanent Diversions

External Diversions

Noncontinent ileal conduit

Here 20 cm of vascularised distal ileum (30 cm from IC valve) is prepared. Ureters are re-implanted over the ileum. Other end of ileum is brought out as a 3 cm stoma in right iliac fossa. Patient has to wear a bag over it. Ileal pouch can be created as a reservoir – J, S, W, etc.

Continent ileal conduit

It is similar conduit with creation of specialised valve (Koch's continent) within, using ileal mucosa or appendix. Patient has to empty the conduit by passing self catheters once in 6 hours. Instead of appendix, intussusception of distal 5 cm ileum into the caecum across the ileocaecal valve and denudation and suturing of the mucosa can create a continent conduit.

Mitrofanoff continent stoma of appendix

It is done in children with spina bifida with neurogenic bladder. Mesentery of appendix is retained (undisturbed). It is dissected at its base from caecum which closed with 2 zero vicryl. Base is mobilised without disturbing its blood supply and implanted into the bladder using 3 zero vicryl sutures. Tip is transected to get the needed lumen; warm saline wash is given into the lumen gently. Transected opened lumen is brought out through a stab incision into the skin in right iliac fossa and its mucosa (full thickness appendix wall) is sutured to skin to create a stoma; often local skin flaps are used to support the appendix and to achieve continence. Urine is drained from the urinary bladder by catheterisation across the appendix stoma. It is a continent cystostomy using pedicled appendix.


Ureteric anastomosis
Posterior
Anterior
Rectal bladder
External sphincter
Sigmoid colon opening into the perineum in front
Anal canal with urinary catheter into rectal bladder
Transected sigmoid colon is brought in front of the anal canal through perineum to achive defecation function with sphincter

Fig. 27-56: Lowsley's rectal bladder.

Lowsley's (urologist, New York) rectal bladder

Left side colon is mobilsed fully; rectosigmoid junction is transected; rectal stump is closed either hand sewn or stapler. Distal cut end of the sigmoid is brought down through the perineum in front of the rectum and anal canal to anastomose to incised skin in front of the original anal canal. This new anal canal created acts as defecating organ. Rectal bladder behind acts as urinary reservoir and normal anal canal acts as urination device. It is kept catheterised for few weeks **(Fig. 27-56)**.

Cutaneous ureterostomy/cutaneous ring ureterostomy are other options.

Internal Diversions

Ureterosigmoidostomy (Leadbetter-Palitano); rectal bladder creation; ileocystoplasty; caecocystoplasty/sigmoidocystoplasty; creation of neobladder (orthotopic) using ileum/caecum/sigmoid colon which is sutured to urethra.

Types of Urinary Diversions

Nephrostomy; pyelostomy; cutaneous ureterostomy; cutaneous ring ureterostomy; suprapubic cystostomy; vesicostomy in children; urethrostomy; ureterosigmoidostomy; rectal bladder; urinary ileal conduit (Koch's conduit).

Complications of Diversions

Urine leak, faecal leak, intestinal obstruction, sepsis; Hyperchloraemic hypokalaemic metabolic acidosis; pyelonephritis; Osteomalacia, growth retardation; Calculi formation—4%; Continent failure, blockage of diversion stoma (stenosis); Reflux of urine; Vitamin B_{12} and folate deficiency due to absence of ileum; Complications of stoma; Renal failure; Metaplasia and adenocarcinoma especially at uretero sigmoidostomy junction.

URETERIC REIMPLANTATION

Ureter may often need to be reimplanted into the urinary bladder. In stricture distal ureter, ureteral tuberculosis, trauma to ureter may be iatrogenic reimplantation is needed.

Usually oblique Gibson's loin incision extending to suprapubic area is ideal; Pfannenstiel incision is also can be used.

Ureter is fully mobilised keeping its blood supply intact. Diseased part is excised. Urinary bladder is mobilised fully both in front, behind, and on opposite side to get adequate tension free length for anastomosis. Cut distal end is reimplanted into the urinary bladder. Ureter can be reimplanted directly or through tunneling depending on need and surgeons' choice. Mucosa to mucosal anastomosis is better.

Psoas hitch - Mobilised urinary bladder is fixed to psoas major muscle on its medial side adjacent to genitofemoral nerve without injuring it; 2 zero interrupted vicryl sutures are placed between muscular layer of bladder and psoas major muscle. Usually three sutures are placed; this psoas hitch prevents urinary bladder getting retracted back into the pelvis and so keeps ureteric anastomosis tension free.

Boari flap - If psoas hitch seems inadequate to achieve tension free anastomosis, then superolateral part of the urinary bladder is elevated after incision as flap; it is tubularised to achieve extra needed length. Cut end of the ureter is sutured into that. This procedure is usually sufficient.

Isolated segmental ileal interposition is done whenever entire length of the ureter is lost. Isolated pedicled 30 cm ileum is harvested; bowel continuity is maintained by doing bowel anastomosis. Ileal harvested segment is washed thoroughly using warm normal saline. Proximal end is closed; just distal to this closed proximal end over the antimesenteric border 8-10 mm sized opening is made in the bowel; renal pelvis or proximal ureter is anastomosed to this ileal segment using 4-6 interrupted 3 zero vicryl sutures with knots placed on outside. Distal part of the isolated segment is sutured to the bladder using 2 zero vicryl as interrupted end to end anastomosis. Knots should be outside the lumen. Nephrostomy, J stent, cystostomy, nasogastric tube, peritoneal cavity tube drain and urinary catheterisation are also needed while finishing the surgery.

MANAGEMENT OF BENIGN PROSTATIC HYPERPLASIA (BPH)

Patient with *acute retention* of urine requires *urethralcatheterisation*. If urethral catheterisation fails, then *suprapubic cystostomy (SPC)* is done. Trocar SPC is available which is technically easier to do and minimally invasive; but bladder should be full and is confirmed clinically by dullness in suprapubic region and by ultrasound. If bladder is not full chances of intraabdominal injury is high. If patient presents with *uraemia*, then urethral catheterisation is a must. That allows the kidney to function adequately and further obstructive damage is prevented. Serum electrolytes should be corrected properly in these patients **(Fig. 27-57)**.

Indications for Surgery

Prostatism (frequency, dysuria, urgency); acute retention of urine; chronic retention of urine with residual urine more than 200 ml; complications like hydroureter, hydronephrosis, stone formation, recurrent infection, bladder changes; haematuria.

Surgeries

Transurethral Resection of Prostate (TURP)

Using cystoscope with fluid like glycine irrigating continuously, enlarged prostate is identified and resected using a loop with a hand control. Resection is done using high frequency diathermy current, above the level of verumontanum. After surgery, continuous bladder irrigation using normal saline is done using three way Foley's catheter. Antibiotics should be given. Catheter is removed in 72 hours. ***Postoperative complications are:*** Water intoxication with congestive cardiac failure—TURP syndrome; hyponatraemia; haemorrhage; infection; incontinence; perforation of the bladder or prostatic capsule; stricture urethra; retrograde ejaculation and impotence; recurrence **(Figs 27-58 and 27-59)**.



Fig. 25-57: Diagram showing normal prostate pattern and post prostatic pouch with residual urine.

TURP

- No suprapubic incision
- Most common and popular method
- Done using resectoscope
- Recurrence may occur in large prostate
- TURP syndrome can develop
- Continuous postoperative irrigation using glycine solution is needed for 72 hours
- Faster recovery and early discharge is possible.

Freyer's Suprapubic Transvesical Prostatectomy

Before TURP, it was a popular and was the procedure of choice for enlarged prostate. Under spinal anaesthesia, through Pfannenstiel incision, rectus sheath is opened horizontally; recti are split; peritoneum is not opened; it is pushed upwards beyond the dome of the bladder. Urinary bladder is identified by its muscle pattern and lateral vesical

Fig. 27-58: TURP is done using cystoscope and resectoscope.



Fig. 27-59: Asepto syringe for bladder irrigation.

venous plexus. Bladder is confirmed by aspirating urine. Stay sutures are placed one at the dome another at the lower part of the bladder. Urinary bladder is opened vertically; urine is sucked out. Deaver retractor is placed on the dome of the bladder. Prostate is felt by index finger. With finger dissection anterior plane is created by opening the prostatic urethra anteriorly. Lateral lobes and median lobe are removed by finger dissection. Posterior lobe is not removed. Warm pack is kept on the prostate bed to control bleeding. Vicryl sutures are placed on either sides of the raw area to control bleeding. Often anterior and posterior wedge at the vesicourethral junction need to be excised to prevent later urinary obstruction. 24-30 F 3 way Foley's catheter is passed from urethra into the bladder; balloon is inflated adequately; traction is given to the catheter so that balloon creates tamponade and control of the haemorrhage. Malecot's catheter is placed through the bladder at a separate stab incision which is brought out through a separate stab wound at the abdominal wall. Bladder wall is closed using 2 zero vicryl sutures. Another tube drain is placed in the Retzius space. Recti are sutured; rectus sheath is closed; skin is closed. Complications are haemorrhage, infection, stricture urethra, incontinence, impotence, bladder neck contracture.

Millin's Retropubic Prostatectomy

Here urinary bladder is not opened; retropubic space is dissected to identify the prostate which is enucleated. Urethra is sutured; drain is placed and wound is closed. 3 way Foley's catheter should be placed in the bladder across the urethra. It is done without opening the bladder. Cystoscopy should be done before doing retropubic prostatectomy as bladder is not opened during surgery. Pfannenstiel extraperitoneal approach is used under spinal anaesthesia. Self retaining retractor is placed. Supine head down position is used. Fat on the surface of prostate behind the pubis is gently cleared off. Bipolar or unipolar diathermy should be used area is vascular. Puboprostatic ligament is ligated and divided. Prostatic capsule is incised 1 cm below the bladder neck transversely. Stay sutures using 2 zero vicryl should be placed on both sides. Once prostate with adenoma is exposed, anterior commissure of the prostatic lobes are opened to enter the prostatic urethra. With finger dissection prostate is separated from the capsule entirely first on one side then on opposite side. Mop is placed over the area to control bleeding. Middle lobe is again excised using finger. Prostatic urethra may need to be divided above the level of verumontanum. 24 F Foley's 3 way catheter is passed per urethrally into the bladder; traction to that will control the bleeding. Capsule is sutured using 2 zero vicryl. Drain is placed in the retropubic space. Wound is closed in layers. Complications are – haemorrhage, infection, extravasation, urethral stricture, incontinence.

Young's perineal prostatectomy through perineal approach.

Other Methods

Microwave hyperthermia treatment with temperature of 45–50 degree; laser treatment is becoming popular, using holmium laser; high energy electromagnetic treatment; placement of intraurethral stents at prostatic urethra; placement of extraurethral stents which are inert; transurethral balloon dilatation of the prostate; if patient presents with acute retention of urine, initial urethral catheterisation is done. If not possible then *suprapubic trocal cystostomy* ideally or formal open SPC is done. Once patient's obstructive uropathy is under control, TURP is done after 7-14 days after evaluation.

Specific Problems after Surgical Intervention of Prostate

Retrograde ejaculation—65%; Erectile dysfunction—5%; Failure, recurrence of symptoms and enlargement—10%; Need for re TURP/surgery in 10 years—15%; Severe sepsis—6%; Recurrent late urinary infection—20%; Postoperative haematuria—3% needs transfusion; Mortality in TURP is 0.5%.

Other methods used for BPH

- Transurethral incision of prostate—TUIP
- Laser ablation
- Transurethral microwave therapy—TUMT
- Transurethral needle ablation using high frequency radiowaves—TUNA
- High intensity US energy
- Water induced thermotherapy—through a balloon placed in prostatic urethra
- Prosthetic stents
- Balloon dilatation

PROSTATIC ABSCESS

It is infection, suppuration and pus formation in the prostate gland. Presentation is fever, rigors, perineal pain, urinary disturbances, and tender soft fluctuant swelling in the prostate on rectal examination. Often presentation may be retention of urine. Total count will be increased. Urine microscopic examination will show pus cells. US is diagnostic. Ultrasound is often done over perineum also. Treatment is antibiotics; US guided aspiration transperineally in lithotomy position or transperineal incision and drainage. Suprapubic cystostomy is better in case of retention of urine. After drainage antibiotics are needed for longer period of weeks to prevent recurrent infection.

RADICAL PROSTATECTOMY

Radical retropubic prostatectomy is the treatment of choice in early carcinoma of prostate. Procedure can be done through laparoscopy or robotic assisted. Adenocarcinoma occurs in peripheral zone; not in central zone. Urethra passes through central zone.

Technique

Under spinal or general anaesthesia and patient is placed in supine with head down position. 30 F Foley's catheter is passed per urethrally and inflated with 30 cc distilled water. Lower midline incision is made. Anterior rectus sheath is incised; recti are retracted; space of Retizus is reached. Peritoneum is not opened. Blunt dissection is used to reflect the peritoneum above both sides to expose iliac vessels, obturator fossae and ductus deferens. Obturator and iliac lymph nodes are cleared from the bifurcation of the common iliac vessels above up to obturator nerve behind; below up to the pubic bone and along the obturator fossae on both sides. Bladder is retracted above with a retractor and by pulling up of the balloon of the Foley's catheter passed; endopelvic fascia is incised and puboprostatic ligament is divided. Superficial dorsal vein is divided. Bipolar cautery is used carefully. Deep dorsal vein is identified and securely ligated using no 1 vicryl by transfixation at two places to avoid injuring neurovascular bundle of Walsh (when nerve sparing dissection is planned). It is divided in between. Dorsal venous complex may extend posteriorly which is tackled better using harmonic scalpel. But care should be taken not to injure the nerve bundles and urethral sphincters by these energy sources. Judicious use of these instruments is needed. Ligation even though technically difficult and time consuming if often seems better. Once these veins are divided apex of the prostate and membranous urethra are exposed. Urethral wall is divided after placing four stay sutures at four angles (anchor sutures) on its wall which facilitates anastomosis later between bladder and urethra. Foley's catheter is divided after applying clamp on its balloon end side which prevents balloon getting deflated which is used for bladder traction later. Posterior wall is divided and rectourethralis. Denonvillier's fascia is identified which is divided in midline distal to apex of the prostate. In nerve sparing radical prostatectomy, dissection should be careful to preserve neurovascular bundle. Retrograde dissection once completed, ureteric orifices are identified by injecting the indigocarmine intravenously. Bladder neck posteriorly is dissected from the seminal vesicles to reach the isolated bladder neck which is transected. Bladder neck preservation by preserving the circular muscles will compromise the clearance of the tumour. Vas deferens, seminal vesicles are removed enbloc with the prostate.

Haemostasis is achieved by underruning the prostate bed using 3 zero vicryl sutures. Vesicourethral anastomosis is done using 3 zero vicryl or monocryl as water tight around 22 F Foley's catheter. Suction drain in the retropubic space is needed. Wound is closed in layers.

Complications

Bleeding, infection, septiacaemia, pelvic abscess formation, stricture or incontinence are complications.

TREATMENT OF STRICTURE URETHRA (FIG. 27-60)

Intermittent Dilatation

Gradual dilatation, initially with thin dilators, later with thicker dilators of increasing size. Dilatation should be done in operation theatre under aseptic precaution. One should avoid forcible dilatation or over dilatation. Dilatation is done "*Once a week for one month, once a month for one year, and later once a year.*



Fig. 27-60: Ascending urethrograms showing single and multiple strictures in two patients.



Fig. 27-61: Filiform bougies are used to dilate narrow stricture urethra. One of the bougies will be passed into the urethra (Faggot).

Dilators used: Lister's dilator [has got olive tip (blister)]; Clutton's dilator; Filiform bougies **(Fig. 27-61)**.

Complications of dilatation are - Infection and bleeding due to trauma; false passage; fistula formation.

Visual Internal Cystoscopic Urethrotomy or Stricturotomy

Here using cystoscope, stricture is visualised and is cut at 12 o'clock position, until it bleeds (fibrous tissue is cut completely). After that Foley's catheter is passed and kept in position for 48 hours **(Fig. 27-62)**.

External Urethrotomy

It is done by open method. Presently it is not commonly done as cystoscopic urethrotomy is more popular. It is presently done as an initial stage surgery for urethroplasty *(Wheelhouse's operation*).

Urethroplasty

Stricture is excised and urethra is reconstructed using *prepuceal skin* or scrotal skin *(Johanson's urethroplasty).*

Problems in urethroplasty are - Staged procedure and so prolonged hospitalisation; infection; necrosis of skin flap; leak and fistula formation; restenosis.

Complications of stricture urethra

- Retention of urine
- Urethral fistula
- Infection—urethritis, cystitis, pyelonephritis
- Urethral diverticula
- Periurethral abscess
- Bilateral hydronephrosis
- Stone formation
- Renal failure
- Due to straining—hernia, haemorrhoids, rectal prolapse

TREATMENT OF HYPOSPADIAS

Staged Procedure (Fig. 25-63)

I. At the age of one and half years, surgical correction of the chordee is done.
II. At the age of 5-7 years, reconstruction of urethra is done using *prepucial skin* (ideal) or scrotal skin if the patient has been circumcised. Best is prepucial skin. *Perineal urethrostomy is done for diversion*. Perineal urethrostomy should be there until reconstruction of urethra takes up well *(Denis-Browne procedure).*



Fig. 27-62: Cystoscopic view of the stricture urethra which needs internal urethrotomy.



Fig. 27-63: Hypospadias which needs staged repair.

Magpi repair: Meatal advancement glandular repair—for glandular hypospadias.

In hypospadias, circumcision is contraindicated as prepucial skin is required for future urethroplasty.

TREATMENT OF POSTERIOR URETHRAL VALVE

Micturating cystourethrography (MCU) is diagnostic. It shows dilated proximal urethra. U/S abdomen shows cricket ball bladder. Blood urea and serum creatinine should be done. IVU may be needed. Antenatal US shows fetal urinary tract dilatation.

Differential diagnosis - *Marion's disease:* Bladder neck obstruction due to hypertrophied interureteric bar. MCU differentiates it from posterior urethral valve. Treatment is Y-V plasty *(Bonin's Y-V Plasty)*. Neurogenic bladder also mimics same.

Treatment

Initial SPC and later cystoscopic resection of the posterior urethral valve is done usually after several weeks.

TREATMENT URETHRAL STONES

If it is impacted in the external meatus or fossa navicularis, meatotomy and extraction of the stone is done (Meatotomy is cutting and widening of external meatus so as to have an easy stone extraction). If it is impacted in other parts of the urethra, urethroscopy and removal of stone from urethra is done or through a cystoscope the stone is pushed into the bladder and then extracted. In case of retention of urine, initial suprapubic cystostomy is required before removal of the stone. Diverticulum and stricture urethra should be treated accordingly.

Complications of urethral stones: Bleeding, stricture urethra and infection.

Chapter

28

Obesity and Morbid Obesity

OBESITY AND MORBID OBESITY

Obesity is weight more than 20% above the normal. Body mass index (BMI) is weight in kilogram divided by height in meters squared [wt in kg/(Ht in meters)^2].

Morbid obesity is a condition wherein BMI is more than 40 kg/m^2. It is often also defined as weight 100 lbs or more; or 100% over ideal body weight.

Weight more than double the expected weight to that age and height of the individual is also often called as *morbid obesity*. If body weight exceeding BMI 50 kg/m^2 is called as *superobesity*.

Causes of Obesity

- Familial, hyperinsulinism, hyperadrenocorticism, hyogonadism.
- Abnormal eating behaviour—Hormones which control eating are– ghrelin from stomach; insulin from pancreas; leptin from fat; PYY 3-36 from colon. Hypothalamus is the center in CNS which controls eating.

Nutritional status	*BMI (kg/m^2)*
• Underweight	• < 18.5
• Normal	• 18.5-24.9
• Overweight (Preobesity)	• 25.0-29.9
• Obesity	• > 30
– Class I	– 30.0-34.9
– Class II (Moderate)	– 35.0-39.9
– Class III (Severe/Morbid)	– 40.0
• Superobesity	• > 50
• Super superobesity	• > 60

Complications of obesity	*Obesity and surgery*	*Treatment for obesity*
General: Difficulty in work, fatigue, depression, back pain, arthritis and gout *Cardiovascular*: Hypertension, stroke, thrombophlebitis, pulmonary embolism *Pulmonary*: Hypoventilation, poor respiratory effort *GIT*: Hiatus hernia with reflux, changes in liver, pancreatitis, gall stones *Endocrine*: Diabetes mellitus	• Hernia and gall stones are more common in obese individual. • Burst abdomen, incisional hernia are more common in obesity • Delay in recovering from anaesthesia • Infertility is more common	*General*: Dieting, exercise *Drugs*: Orlistat, Sibutramine *Surgeries*: • *Restrictive* – Vertical banded gastroplasty – Laparoscopic adjustable gastric banding (LAGB) – Jaw wiring • *Malabsorptive* – Biliopancreatic diversion (BPD) – Biliopancreatic diversion with duodenal switch (BPD – DS) – Jejunoileal bypass • *Combined* • Roux-en-Y gastric bypass (RYGB) open or laparoscopic

Contd...

Contd...

Obesity is more common in young women. Child of a normal weight parents has 10% chance of become obese. If both parents are obese then child has got 80% chances to develop obesity.

Problems with Morbid Obesity

Obstructive sleep apnoea, degenerative joint disease, back pain, hypertension, GERD, gall stones, type II diabetes, hyperlipidaemia, arrhythmias, venous diseases, DVT, skin diseases, urine incontinence, infertility, ventral hernias, obesity hypoventilation syndrome, polycystic ovarian disease, hirsutism, gynaecomastia, steatohepatosis, malignancies—are common problems. All these conditions are called as *comorbidities.*

Infertility is common in married morbid obese women due to improper ovulation, polycystic ovary disease. Urinary incontinence is common in morbid obese women (stress incontinence and detrusor instability). Pregnancy in morbid obese patient is considered as high risk pregnancy. Gestational diabetes, hypertension, are common. It is better these women to undergo bariatric surgery prior to pregnancy which definitely reduces the complications during pregnancy. Such individual after bariatric surgery needs more iron and vitamin supplements.

Evaluation of the patient – cardiac, respiratory assessment, lipid profile, blood glucose, renal and liver status assessment, anaesthesia risk assessment.

Medical Management

- *General:* Diet, life style changes, exercise.
- *Drugs*: (1) Orlistat is a selective inhibitor of gastric and pancreatic lipases that reduces the absorption of lipids from intestine. (2) Sibutramine is a noradrenaline and 5 HT reuptake inhibitor which act as appetite suppressor.

Surgical Treatment (Bariatric Surgery)

Bariatric surgery causes long term durable weight loss. Patient's eating behaviour is reduced to slow ingestion of small boluses of food and or also reducing the absorptive surfaces.

Types of Bariatric Surgery

1. *Restrictive* wherein caloric intake is reduced. Purely gastric restrictive procedures are vertical banded gastroplasty (VBG) and laparoscopic adjustable gastric banding (LAGB).
2. *Malabsorptive* wherein absorption of calories and nutrients from food is reduced. Biliopancreatic diversion (BPD) and biliopancreatic diversion with duodenal switch (BPD–DS) are malabsorptive procedures.
3. *Combined* wherein both methods are used. Roux-en-Y gastric bypass (RYGB) is both restrictive and malabsorptive types. Gastric bypass reduces GI polypeptide ghrelin level secreted from fundus of stomach and duodenum. Ghrelin acts on specific receptor in CNS – hypothalamus to initiate appetite. This stimulation is reduced to decrease appetite. In restrictive only procedure ghrelin level raises and so appetite stimulation is not controlled.

Indications for Bariatric Surgery

BMI more than 40 kg/m^2 or BMI more than 35 kg/m^2 with comorbidity is indication for bariatric surgery. American Association of Bariatric Surgery (ASBS) published indications and approved surgeries.

Contraindications

Patients who are unfit for general anaesthesia (cardiac/renal/respiratory/hepatic) or who are unable to adjust postoperative life styles or psychiatric patients are contraindications for bariatric surgery.

Preoperative preparations and evaluations are:

- Complete cardiac, respiratory/renal/hepatic evaluation.
- Lipid profile and blood glucose assessment.
- Obstructive sleep apnoea in obese patient should be assessed using polysomnography and be treated.
- Risk assessment for DVT should be done.
- If GERD symptoms are present gastroscopy should be done.
- USG abdomen to identify gallstones should be done; if gallstones are present it is of usual practice to do cholecystectomy along with bariatric procedure.
- Nutritional evaluation and dietician advice for preoperative and postoperative diet management.
- Psychological screening is needed to all patients to counsel their postoperative care and diet.
- Separate theatre table is needed for morbid obese patient. Equipments should be long and flexible. In laparoscopic surgery, special ports and instruments are needed.

DIFFERENT SURGERIES

Vertical Banded Gastroplasty (VBG); Mason (1982)

It is a purely restrictive type with creation of a calibrated stoma in the lesser curvature which is reinforced by an encircled mesh with a proximal gastric pouch. After laparotomy Ewald's stomach tube is passed per orally to place against lesser curve. A 2.5 cm circular window is created in the body of stomach near lesser curvature 8 cm below the *angle of His*. After this, four lines of linear vertical stapling are done from circular opening towards angle of His. This staple line ideally should be divided using another cutting linear stapler to reduce chances of dehiscence. This creates a 50 ml proximal gastric pouch. A 1.5 × 7 cm polypropylene mesh is placed around the lesser curve through circular opening and sutured to create a 5 cm collar stoma **(Fig. 28-1)**.

VBG causes only medium term weight loss; its efficacy is less compared to other procedures. *Complications of VBG are* – stricture at stoma (20%), vomiting (30%), reflux (20%), staple line dehiscence (40%), conversion into other procedures. Mortality is 0.3%.

VBG is technically easier to do; it has got very less chances of long term metabolic and nutritional deficiencies.

Laparoscopic Adjustable Gastric Banding (LAGB)

It is also a restrictive type (1992, Guy Bernard) to create a narrow stoma just below the OG junction. It is used in adolescents and elderly. It is contraindicated in hiatal and paraoesophageal hernias. It is done using *laparoscopy.*


Angle of His
Proximal gastric pouch
Wrapped mesh
Stomach ready for VBG
7 X 1.5 cm polypropylene mesh
Circular window made in stomach using circular stapler
Vertical 4 line staples form window towards angle of His
Ideally middle of staple line is divided using cutting linear stapler
7 X 1.5 cm polypropylene mesh is wrapped around the window to create a narrow stoma

Fig. 28-1: Vertical banded gastroplasty (VBG).

Under general anaesthesia, with patient in reverse trendelenburg position six laparoscopic ports are placed. Using pars flaccida method, retrogastric tunnel is created; a silicone band is passed through the tunnel to encircle the cardia just below the OG junction; tail of the band is buckled and locked. Stoma diameter is determined by inserting a calibration tube. Stomach over the band is imbricated using interrupted sutures except the buckle area. Silicone tube end is brought out through the abdominal wall to connect access port. It is used for band volume adjustment by injecting or withdrawing the saline.

Gastrograffin study is done on 1st postoperative day to assess band position and lumen patency. Patient is advised to have liquid diet for one month. Band adjustment is done under fluoroscopic guidance in 2 months. Adjustment is done to achieve weight loss at a rate of 2 kg/week. Efficacy of LABG is 55% **(Fig. 28-2)**.

Complications of LABG are – spleen/stomach injury; bleeding; band slippage (10%); band erosion (7.5%); tube related complications; vomiting; pouch dilatation; reflux. Conversion rate is 3%; mortality is less than 0.5%.

Jejunoileal Bypass

It was the first malabsorptive procedure done for obesity. Now this technique is not done due to high incidences of complications.

Proximal jejunum is divided and proximal cut end is anastomosed to distal ileum just proximal to ileocaecal valve to reduce the absorptive surface area of small bowel **(Fig. 28-3)**.

Complication rates were higher and so procedure is not practiced. Colon in these patients absorbs high level of oxalate causing nephrocalcinosis. Bypassed bowel promotes bacterial growth causing endotoxin induced liver injury, cirrhosis, liver failure. Complications like protein, vtamin K, vitamin B_{12} deficiencies; gallstone formation; enteritis and diarrhea; arthritis, osteoporosis are common.

Roux-en-Y Gastric Bypass

It is commonly done combined procedure. It can be done by open or laparoscopic method. Proximal stomach is dissected between 1st and 2nd branches of left gastric artery. Vagii nerves and *nerves of Latarjet* are retained carefully. Stomach is transected at this proximal site to create a proximal gastric pouch (15 ml if BMI is > 50; 30 ml if BMI is 40-50). It is usually carried out through linear stapler. Jejunum is transected 45 cm from *ligament of Treitz*. A side to side jejunojejunal anastomosis is done using stapler 75 cm distal to the distal cut end. Proximal Roux part of the distal jejunal cut part (75-150 cm, based on patient's preoperative weight) is brought out through the transverse mesocolon towards the created proximal gastric pouch and gastrojejunostomy is done to this proximal gastric pouch. Mesenteric defect is closed. Stomal integrity is checked on table by air distension and methylene blue infusion. Gastrograffin study is done in 24 hours to assess pouch size, stomal patency and distal obstruction. Oral food is started in 24 hours and patient is discharged in 4 days **(Fig. 28-4)**.

RYBG is more useful in weight loss compared to purely restrictive types. 5 year weight loss is 60-75%. It also prevents progression of non insulin dependent diabetes mellitus, controls hypertension, sleep apnoea, hyperlipidaemia, asthma, arthritis, GERD.

Complications are – Roux obstruction, anastomotic leak, acute distal gastric dilatation, stomal stenosis, marginal ulcer, dumping syndrome, internal hernias, vitamin B_{12} deficiency, iron deficiency anaemia. Distal gastric dilatation needs emergency intervention which is usually due to jejunojejunal obstruction.

Laparoscopic RYGB (1994, Wittgrove, Clark, Trembly)

Technique is similar to open RYGB. Anastomoses are done using endoscopic stapler. GJ between gastric pouch and Roux jejunum is done either using linear stapler through laparoscopic port after making a gastrotomy in the pouch which is later sutured after staple firing; or by using circular stapler anastomosis is done wherein anvil is initially passed transorally often under endoscopic guidance across the pouch into the Roux jejunum; or by using hand sewing with absorbable sutures. Omentum is released from the colon and is covered over the GJ. Mesenteric defect and *Patterson Brown defect* are closed. A *Brolin antiobstructive stitch* is placed between Roux and biliopancreatic limbs. Integrity of anastomosis is checked using insufflation of air, methylene blue. *Complications are* similar to open RYBG. Conversion rate is 9%. *Advantages* of LRYBG to open RYBG are—faster recovery, less postoperative pain, less wound related complications, less morbid one. *Disadvantage* of LRYBG is availability of facility, technical expertise, and steep learning curve.

Now technique is modified to antegastric, antecolic one which has become popular (Gagner).

Biliopancreatic diversion (BPD) (Nicola Scopinaro, Italy)

It is done in patients who had failed restrictive procedure or who are superobese.


Pars flaccida method used to create retrograde tunnel
Silicone band wrapped around with buckle
Gastric pouch
Calibration tube should be brought out through access port

Fig. 28-2: Laparoscopic adjustable gastric banding (LAGB).


Jejunum
Ileum
Proximal jejunum is anastomosed to distal ileum to bypass small bowel absorptive surface
Jejunum
Ileum

Fig. 28-3: Jejunoileal bypass procedure (JIB).


Creation of proximal gastric pouch of 15–30 ml
45 cm
Staple transection of jejunum at 45 cm from DJ junction
GJ with Roux loop
75–150 cm
Roux limb of 75–150 cm passed through Tn mesocolon
Jejunojejunostomy

Fig. 28-4: Roux-en-Y Gastric bypass procedure (RYBG).

Distal subtotal gastrectomy is done with formation of proximal gastric pouch (of 400 ml in BMI 40-50; 200 ml in BMI >50). Ileum is transected 250 cm proximal to ileocaecal valve; distal ileal segment is brought up to anastomose into the proximal gastric pouch. Proximal biliopancreatic jejunoileal limb is anastomosed into distal ileal segment 50 cm proximal to ileocaecal valve as end to side stoma. Additionally cholecystectomy should be done **(Fig. 28-5)**.

Modification of BPD with duodenal switch (BPD–DS) has become more popular. Here sleeve gastrectomy along the greater curvature is done to create gastric reservoir (200 ml) along lesser curve. Duodenum just distal to first part is divided using stapler; proximal cut end is sutured to proximal upward pulled end of the distal ileal segment of earlier transected ileum, 250 cm from ileocaecal valve. Biliopancreatico duodenal with proximal jejunoileal segment is later stapled to distal ileum 50 cm proximal to ileocaecal valve. Duodenal switch reduces the marginal ulcer rate and dumping syndrome.

Results of BPD/BPD-DS are excellent for weight reduction compared to restrictive procedures. But they need lifelong supplement of vitamins, fat soluble vitamins, calcium, and iron. Technically BPD is easier to do when compared to BPD–DS **(Fig. 28-6)**.

Complications of BPD/BPD-DS are—anemia (30%); protein deficiency (20%); dumping syndrome; marginal ulcer (in BPD 10%; in BPD-DS it is 1%); osteoporosis; night blindness; biliopancreatic limb obstruction; staple line leak; staple line bleed; DVT; subphrenic abscess. Vitamin B_{12} deficiency is specific.

Cholecystolithiasis after Bariatric Surgery

Gall stone formation is common after bariatric surgery (50%). It is due to rapid weight loss. If gall stones are present at the time of bariatric surgery it is essential to do laparoscopic cholecystectomy during bariatric procedure. It is controversial about doing prophylactic cholecystectomy during bariatric surgery even though it is practiced in many places. Advantages are – it prevents future gall stone formation after bariatric surgery (loss of access); it prevents difficulties in approaching CBD in case needed endoscopically due to surgery. Disadvantage is cholecystectomy adds additional 1 hour time for bariatric surgery increasing the risk of immediate complications. Patients who are not having gall stones after bariatric surgery should receive ursodeoxycholic acid 300 mg twice daily for 6-12 months post bariatric surgery period. Often stomach is anchored to abdominal wall as access part to biliary system for future need.

Note: Many of these patients require abdominal contour plastic surgery (panniculectomy, abdominoplasty) after weight reduction due to bariatric surgery.


Subtotal gastrectomy with proximal pouch
Long biliopancreatic limb
200 cm long GI tract limb
50 cm

Fig. 28-5: Biliopancreatic diversion procedure (BPD).


Gastric sleeve resected stomach
GI tract limb
50 cm common channel

Fig. 28-6: Biliopancreatic diversion with duodenal switch procedure (BPD–DS).

Bariatric Surgery

Only effective therapy for severe obesity is bariatric surgery.

80% of bariatric surgeries are gastric bypasses specifically laparoscopic approach.

Original gastric pouch was of 150 ml volume with loop gastrojejunostomy which is later changed to a pouch of < 20 ml volume with Roux-en-Y gastrojejunostomy.

Indications are – BMI more than 40 Kg/m^2 or BMI more than 35 Kg/m^2 with comorbidity (diabetes, hypertension), sleep apnoea, obesity hypoventilation syndrome.

Management needs – bariatric surgeon, nutritionist, physician, pulmonologist, cardiologist, endocrinologist, psychiatrist, psychologist and anaesthesiologist.

Principle – bypassing the gastroduodenum blocking the neurohumoral effect; rapid delivery of food to hindgut; early satiety; malabsorption. Usually 75 cm Roux limb is used; longer limb of 150 cm Roux limb is used for BMI more than 50 Kg/m^2.

Technique –

Access - Supine position; operating surgeon stands on the right side; 5 mm optical viewing trocar; left upper quadrant Veress needle and trocar; 5 mm liver retractor, is placed and anchored to the bed with a self-retaining device; wider trocar for endostapler (12 mm).

The Roux limb creation - The transverse colon and omentum are placed towards the upper abdomen; ligament of Treitz is identified; proximal jejunum is oriented as proximal and distal parts by C configuration; jejunum is divided 50 cm distal to the ligament of Treitz using linear cutting stapler; the mesentery of the jejunum divided using two stapler firings; sufficient length of mesentery is created to achieve adequate tension-free passage Roux limb; the Roux limb is marked. Roux limb is measured distally for 75 cm from the marker; bowel should be straightened (not stretched) while marking; side to side jejunojejunostomy anastomosis is done after doing jejunotomies using harmonic scalpel between the biliopancreatic and the Roux limb using linear stapler; jejunotomy ends are closed using another lineal stapler firing. Reinforcing sutures may be placed using 3-0 silk. One reinforcing stitch is placed between the stapled end of the biliopancreatic and the Roux limb - *Brolin stitch*. One more is placed proximally at the crotch between the biliopancreatic and Roux limb. The mesenteric defect (*Patterson Brown defect*) between the biliopancreatic and Roux limb is then closed with a continuous vicryl or silk 3 zero suture.

Greater omentum is divided at the level of the midtransverse colon using the harmonic scalpel. The Roux limb is passed upward between the leaves of the divided omentum to the gastric pouch in the *antecolic* and *antegastric* approach.

Creation of gastric pouch - The patient is placed in the steep reverse Trendelenburg position; window is created in the gastrohepatic ligament with the harmonic scalpel. Linear stapler is fired toward the gastric lesser curvature to divide the lesser omentum and descending branch of the left gastric artery but the main left gastric arterial trunk should be preserved which is the main blood supply of the gastric pouch. Gastric pouch of 15-20 ml is created by sequential firing using lineal staplers from lesser curve towards the angle of His. Gastric pouch is dissected off from left crus to achieve pouch mobility and to reduce tension while creating GJ; pouch is also properly separated from gastric remnant below to avoid gastrogastric fistula.

Creation of GJ – Linear: posterior suture line between gastric pouch and Roux limb → gastrotomy and jejunotomy creation using harmonic scalpel → GJ is done using lineal stapler → stapler entry common opening is sutured using 3 zero silk with endoscope in place → GJ is checked for leak and bleeding (*bleed and leak test* by insufflation using endoscope). *Transoral circular stapler method* - Gastroscope is passed into the pouch → snare is pushed through a small gastrotomy → guidewire is passed through a laparoscopic port which is grasped by the snare to pull out through the mouth → anvil of the stapler is attached to the guidewire and pulled antegrade into the gastric pouch → the circular stapler is passed in the open end of the Roux limb → the stapler and anvil are connected → the stapler is fired to create a circular stapled GJ anastomosis → the open Roux limb is closed with a linear stapler. *Circular transabdominal and hand sewn* are other methods. Jackson Pratt *drain* is placed behind the pouch; omentum is placed and sutured on the GJ as Schauer cap. Roux limb may be stitched (one stitch) to the gastric remnant to avoid its twist.

Leak test – It is done by initially occluding the Roux distal limb with a clamp and by submerging the GJ with warm normal saline and pouch is insufflated with air through endoscope.

At the end *cholecystectomy* is done; if not patient is put on ursodeoxycholic acid for 6-12 months. Additional core needle biopsy performance is a controversial.

Postoperative management - Pain control; antiemetics; essential preoperative medications are continued as IV until the patient is started on liquids; incentive spirometry use; nil orally on the night of surgery; Gastrografin swallow study on 1st postoperative day (must); if the swallow study does not show any leak or obstruction, then oral clear fluid is started; monitoring; cardiac evaluation; psychiatrist counseling; drain removal on 7th day.

Complications – gastric leak (1-5%), sepsis, pulmonary embolism (1%) are major complications. Fever, tachycardia, tachypnea are probable features of leak. Acute dilation of the gastric remnant is less than 1% in incidence but life threatening; it is due to obstruction of the biliopancreatic limb; presents as severe epigastric pain with gastric distension; plain X-ray is useful; CT scan is diagnostic; it is treated with emergency decompression by percutaneous gastrostomy; the biliopancreatic limb obstruction is managed surgically only once the patient has stabilised. Wound infection rate is 10%. Infections of laparoscopic trocar sites can occur.

Late complications are - Marginal ulceration at GJ site (10%) is due to ischemia, smoking, gastrogastric fistula, large pouch size, retained anastomotic suture, NSAID; *Helicobacter pylori* infection. Late bowel obstruction can occur which is due to an internal hernia 1-10%; if episodic abdominal pain or recurrent partial small bowel obstruction, laparoscopic exploration is performed; often obstruction is due to intermittent bowel herniation through a mesenteric defect. Anastomotic stricture at GJ can occur due to tension on the Roux limb or pouch ischaemia or chronic marginal ulcer, usage of circular stapler; strictures occur 1 to 3 months after surgery; Present with dysphagia, vomiting; treated with endoscopic balloon dilations in 2-3 times. Nutritional deficiencies like deficiency of iron (30%); folate (35%); vitamin B$_{12}$ (25%); anemia (up to 54%) can occur. Very late long term complications like severe protein calorie malnutrition requires revision surgery to lengthen the common channel.

Chapter 29

Adrenal Gland Surgeries

ADRENAL GLAND SURGERIES

Adrenalectomy is the standard treatment for adrenal tumours, bilateral adrenal diseases like primary adrenal hyperplasia, incidentalomas more than 5 cm in size, and often metastases in adrenal gland.

Surgical Anatomy of Adrenal Glands

The adrenal glands are named in relation to the kidneys. The term "adrenal" comes from Latin – *ad* means "near"; and *renes* means "kidney". Suprarenal is derived from Latin – *supra* means "above" and *renes* means "kidney". Adrenal glands are essential endocrine glands.

Two suprarenal endocrine adrenal glands are located in the retroperitoneum along the upper pole and medial part of the kidneys in front of the crus of diaphragm opposite 12th rib and vertebral end of 11th intercostal space. Each adrenal gland is 5 × 3 × 1 cm in dimensions weighing 5 grams. Adrenal gland is within renal fascia but separated by a fascial septum from kidney. Right gland is *triangular* in shape (top hat); left one is *semilunar* (cocked hat). Gland is yellow or mahogany (reddish-brown) or *golden-orange* in colour. Right adrenal is relatively higher than left adrenal (right kidney is lower level than left kidney). Between two adrenal glands structures present are – crura, the aorta and coeliac arteries, coeliac plexus and inferior vena cava. Kidney may be ectopic or ptotic but adrenal will be in the original position. But fusion of kidney like horse shoe kidney may have fusion of adrenal glands also (**Figs 29-1 and 29-2**).

Right Adrenal Gland

It has got a base, an apex, anterior and posterior surfaces, anterior, medial and lateral borders. Anterior surface is related to inferior vena cava medially, bare area of the liver laterally, duodenum below. It is devoid of peritoneum. Posterior surface is related to right crus of diaphragm above and right kidney below. Hilum of right adrenal is near upper end. Apex is related to bare area; base is related to upper pole of right kidney. Three arteries supplying the right adrenal gland course behind the IVC. Right adrenal vein arises near upper part of the hilum. Right adrenal gland is not very close to right kidney (unlike left adrenal gland which is very closely attached to left kidney).

Left Adrenal Gland

It has got narrow upper end and round lower end. Upper end is related to posterior end of spleen; hilum of left adrenal gland is near lower end through which left adrenal vein exits. Anterior surface is related to cardiac end of stomach, splenic artery and pancreas. Gastric related part only is covered with peritoneum/omental bursa. Posterior surface is related to left kidney laterally, left crus of diaphragm medially. Medial convex border is related to left celiac ganglion, left inferior phrenic artery, left gastric artery. Lateral concave border is related to the stomach.


Diaphragmatic attachment
Adrenal gland
Septum
Renal fascia
Kidney
Triangular right adrenal
Semilunar left adrenal

Cut section of adrenal gland

Location of right and left adrenals


Inferior phrenic artery
Right
Left
Middle adrenal artery
Superior adrenal artery
Right adrenal gland
Right adrenal vein
Superior adrenal artery
Left adrenal gland
Left inferior phrenic vein
Inferior adrenal artery
Inferior adrenal artery
Left adrenal vein
Right renal vein
Left renal vein
Right kidney
Left kidney
Left gonadal vein
Aorta
IVC

Fig. 29-1: (1)


Aorta
Left adrenal gland
Ribs
Left renal artery
Left kidney
Right adrenal gland
Right renal artery
Right kidney
View from behind
IVC
Aorta
Liver
GB
Right adrenal gland
Right kidney
Superior mesenteric vessels
Left adrenal gland
Splenic artery
Spleen
Left kidney

Fig. 29-1: Surgical anatomy of adrenal gland.


Related to liver in front
Related to IVC in front
Related to pancreas in front
Related to stomach in front
Front view
Right adrenal gland
Left adrenal gland
Posterior view
Left adrenal gland
Right adrenal gland

Fig. 29-2: Anterior and posterior views of adrenal glands.

Arterial Supply

Adrenal gland is one of the most vascular organ (gram of tissue) like thyroid (so metastases are common). It is supplied by – superior adrenal artery, a branch of inferior phrenic artery; middle adrenal artery, a branch of aorta; and inferior adrenal artery, a branch of renal artery. Main supply to right gland is superior adrenal artery; to left gland is middle adrenal artery. Inferior phrenic artery often gives group of 6-8 arteries separately instead of one superior adrenal artery. Middle adrenal artery arises from aorta at the level of origin of superior mesenteric artery; it may be single/multiple/often absent or supply perirenal fat. Left side it is more commonly constant and predominant. Inferior adrenal artery is usually single but can be multiple arises from renal artery or from accessory renal artery or superior polar artery of kidney.

Venous Drainage

Venous drainage is not accompanied by adrenal arteries. Adrenal gland is drained by one single vein which begins at the adrenal hilum. *Right adrenal vein* is short < 1 cm and stout drains from the anteromedial part of the gland from upper part of its hilum into inferior vena cava on its posterolateral aspect directed above downwards obliquely. Occasionally an *accessory right adrenal vein* may be present draining into IVC or hepatic veins above the level of right adrenal vein. Right adrenal vein may drain into right hepatic vein or right renal artery instead of IVC. *Left adrenal vein* is long and is directed downwards perpendicular to the renal vein and medially to drain into left renal vein after crossing the left renal artery in front. It is on the anterior surface of the gland. Left inferior phrenic vein joins left adrenal vein on its medial aspect at a point 1.5 cm above the junction of left renal vein and left adrenal vein. Variations like double adrenal veins may be present. Tearing or avulsion of adrenal vein from IVC or left renal vein can occur during dissection causing torrential haemorrhage.

Lymphatics

Adrenal gland is drained into lumbar and lateral aortic nodes. Lymphatic plexus are present under the capsule and in medulla. Subcapsular plexus drains with the arteries; medullary plexus drains with the veins. Right adrenal drains into paraaortic nodes, right renal nodes and nodes at right crus of diaphragm. Left drains into nodes adjacent to left renal artery and paraaortic nodes. Lymph may also drain into the posterior mediastinum through lymphatics along the inferior phrenic artery. Lymphatics from the upper pole of right adrenal gland may communicate with lymphatics of the liver.

Nerve Supply

Adrenal medulla has got myelinated preganglionic sympathetic fibers. Coeliac and renal plexus give branches to adrenals.

Structure

Adrenal gland has got outer thick cortex and inner thin medulla. Two are independent in development, structure and function. Cortex has got *outer* zona glomerulosa secreting mineralocorticoids; *middle* zona fasciculata screting glucocorticoids; *inner* zona reticularis secreting sex hormones. Adrenal medulla contains chromaffin cells in groups, autonomic ganglion cells with capillaries.

Embryology

Adrenal cortex develops from *intermediate mesoderm* of coelomic epithelium; medulla is from *neural crest* cells. Fetal adrenal gland is 20 times larger in relation to body weight than adult adrenal gland. In fetus at 4 months of gestation, adrenal gland is 4 times larger than kidney size of that age. During birth adrenal gland becomes 1/3rd of the kidney size.

ADRENALECTOMY

Indications for Adrenalectomy

Unilateral

- Cushing's syndrome – cortisol secreting adenoma.
- Unilateral pheochromocytoma.
- Virilizing tumours.
- Unilateral nonfunctioning tumour > 4 cm in size.
- Adrenocortical carcinoma.
- Solitary adrenal metastasis (should be confirmed by PET scan to rule out other metastatic areas).

Bilateral Adrenalectomy

- Bilateral pheochromocytoma (10%).
- Bilateral nodular adrenal hyperplasia.
- Ectopic ACTH producing tumour.
- Cushing's disease (pituitary related).

Adrenal incidentalomas (4%) are identified on US/CT/MRI which are otherwise asymptomatic clinically. It can be functioning or nonfunctioning. Biochemical evaluation is a must to find out its functional nature if it is so. Incidentaloma more than 4 cm in size, progressive increase in size on repeated imaging, functioning tumour, suspicious of malignancy should be operated. Nonfunctioning cortical adenoma is the commonest type of adrenal incidentaloma.

Preoperative Preparation

CT imaging is the ideal one for diagnosis, to assess extent, involvement, nodal status. MRI is also used often. CT chest is done to check metastases.

In Functioning Tumours:

Relevant investigations like 24 hour urinary catecholamines and metanephrines and plasma metanephrine, VMA; for aldosteronoma ratio of plasma aldosterone concentration (PAC) to plasma renin activity (PRA) is greater than 20:25 with an absolute PAC more than 15 ng/dl, raised 24 hour urine aldosterone level >12 μg on a high sodium diet, raised urinary potassium excretion rate >30 mEq/24 hour; for Cushing's syndrome with cortical adenoma 24 hour urine free cortisol level estimation, dexamethasone test (1 mg dexamethasone is injected at 23.00 hours, morning 8 o'clock plasma cortisol level is assessed, in normal individual plasma cortisol level will be suppressed below 3μg/dl whereas in Cushing's syndrome suppression will not be there, plasma ACTH level (if ACTH is raised MRI head for pituitary disease with inferior petrosal sinus blood sampling is done); for adrenocortical carcinoma 24 hour urine free cortisol and plasma DHEA (dehydroepiandrosterone) level estimation is done. Correction hypokalaemia and hypertension is important.

In Conn's syndrome correction of electrolytes and blood pressure is important. Oral potassium supplementation and spironolactone (200-400 mg daily for 3 weeks) are useful in aldosteronoma.

Hypertension in pheochromocytoma is corrected using α-blocker with phenoxybenzamine 10 mg twice daily up to a total dose of 60 mg/day and increased if needed later. *Plenty of liquid (adequate hydration)* intakes are essential while patient is in the hospital often with hospitalisation. Beta-blocker if at all is given only once patient is fully alpha blocked for 4 weeks and usually given one week prior to surgery to control tachycardia and arrhythmias.

Preoperative intravenous steroid is needed in case of adrenalectomy for Cushing's syndrome. Contralateral gland may be *suppressed or atrophied* in Cushing's syndrome.

CVP line, arterial line, cardiac monitor, urinary catheterisation, nasogastric intubation are required.

Approaches for Adrenalectomy

Laparoscopic Approach

It is ideal for all unilateral adrenal tumours which are benign, less than 6 cm in size. It is the gold standard as access and dissection will be more precise in the depth. Gagner's transabdominal lateral approach is commonly (1962) is used. This gives a wider working space with better visualisation of abdominal contents. It is the preferred method. Anterior transabdominal laparoscopic approach is also used. Retroperitoneoscopic approach is direct approach to adrenal gland but working space is less. Retroperitoneoscopic approach allows lesser respiratory and haemodynamic complications.

Open Approach

It is advocated in tumours larger than 6 cm, previous upper abdominal surgery, malignant adrenal tumour, bilateral adrenal tumours.

Lateral Flank Open Approach:

It is used to reach the adrenal bed. It is like approaching the kidney and is more familiar to surgeons and urologists. Proper padding at different pressure points is important to reduce the chances of rhabdomyolysis and hyperextension neuropraxia **(Fig. 29-3)**.

Open Anterior Transabdominal Approach:

It is used in malignant tumours which are more than 8 cm, with extraadrenal extension, with nodal spread and in case of previous upper abdominal surgery where bowel adhesions are common. Bilateral subcostal incision allows removal of both adrenal glands. This is commonly used approach for bilateral adrenalectomy **(Fig. 29.4)**.

Open Posterior Retroperitoneal (Lumbodorsal) Approach:

It is used in small tumours less than 6 cm which are not approachable through laparoscopy. This approach has become rare as most of these tumours when benign can be approached through laparoscopy. Only tumour less than 6 cm which is malignant but not invaded is approached retroperitoneally. Patient is placed in prone position. Incision is placed along the 11th or 12th rib. 11th or 12th rib is resected. Two incisions on both sides allow bilateral adrenalectomy. Peritoneal opening is avoided in this approach. Postoperative ileus, infection wound dehiscence are less in this approach. Both sides can be approached in same prone position. But abdominal contents cannot be assessed for any pathology.



Fig. 29-3: Positions for lateral approach for left and right adrenalectomy.



Fig. 29.4: Open abdominal approaches – Chevron incision for bilateral adrenalectomies; midline incision; right paramedian incision.

Hockey stick incision is another incision used for posterior approach which is placed from 10th rib extending downwards and then laterally towards iliac crest. Vertical incision is also can be used. The latissimus dorsi muscle is divided with 12th rib resection subplerally. Serratus posterior muscle is divided. Intercostal nerves (12th) are retained. Paraspinal muscles are retracted medially. Pleura is gently dissected from the diaphragm above; diaphragm is incised to reach Gerota's fascia. Gerota's fascia is incised; kidney is dissected downwards to expose the adrenal gland. Adrenal vein is identified carefully dissected and doubly ligated. Adrenal arteries are also ligated to dissect the gland completely. Pleura if injured can be sutured with a small red rubber tube inside the pleural cavity which is removed after adequate inflation of lung during closure of the wound; otherwise intercostal tube drainage. Diaphragm is closed with sutures. Wound is closed in layers. Postoperative musculoskeletal pain, pleural injury and less access to adrenal vessels are the problems **(Fig. 29-5)**.

Thoracoabdominal Approach:

It is used when there is major vascular invasion like inferior vena cava or extensive upward dissection is needed. Patient is in semilateral position. Midline incision extending into the thorax through 9th or 10th rib to achieve thracoabdominal exposure is used. Incision can also be used at the angle of the 9th to 10th ribs extending across the midline to the midpoint of the contralateral rectus muscle just above the umbilicus. Diaphragm is incised by taking care not to injure phrenic nerve. Liver, IVC and hepatic veins are exposed well. Dissection is carried out as usual **(Fig. 29-6)**.



Fig. 29-5: Posterior approach for adrenal gland. It is rarely used now. It is useful in bilateral adrenalectomy.



Fig. 29-6: Incision for thoracoabdominal approach.

TECHNIQUE OF OPEN ADRENALECTOMY

Open approach is done through lengthy subcostal incision. Bilateral subcostal incision is used to approach both adrenal glands. Anterior rectus sheath, rectus muscle medially and external and internal oblique and transversus abdominis muscles are divided to enter the peritoneal cavity.

Right Adrenalectomy

Hepatic flexure of the colon is mobilised medially and inferiorly. Triangular ligament of the liver is divided to retract liver medially to exposed right adrenal area. Kocherisation of the duodenum medially adequately is important to expose the IVC properly. Right adrenal gland will be deeper to inferior vena cava at its medial part and in front of the upper pole of right kidney below. Downward traction to right kidney improves the exposure. Resectability of the large tumour should be assessed. Encasement of IVC and liver metastases are contraindications for resection of the tumour. Lymph nodes should be assessed in malignancy and may require removal for radical clearance. Fascia between the right adrenal gland and IVC is incised carefully and dissected away from adrenal gland. While gentle lateral displacement of adrenal gland is done, right adrenal vein which is short and stout entering into the IVC identified. It is doubly ligated carefully or using clips. Right adrenal vein is divided. Often in large tumour right adrenal vein stretches over the tumour; in such situation right adrenal vein is ligated or stapled with appropriate device at its IVC junction. Rarely accessory right adrenal vein may be existing above the level of right adrenal vein which needs careful dissection and ligation or clipping. Arterial branches enter the gland on the medial side from deeper aspect of the IVC, which should be ligated or cauterised using bipolar cautery. Ultrasonic energy device can also be used. Laterally dissection is done between liver and adrenal gland and between kidney and adrenal gland. Right renal vein is safeguarded. Superior polar artery of right kidney will be often very close to the adrenal gland and should not be injured. If tumour involves adjacent structures then enblock removal of adrenal tumour with kidney, hepatic flexure of colon and part of the liver segment can be done. Partial infiltration of the IVC at one place may allow tumour resection by removing the small part of the wall of the IVC which will be repaired using 3 or 4 zero polypropylene suture material. One should not hold the adrenal gland/tumour as tumour spillage can occur. Only *periadrenal fat and thin fascia* should be held to facilitate the dissection. Dissection between adrenal gland and kidney is done last as if it is done earlier, adrenal gland will retract upwards and accessibility becomes difficult. Tumour spillage should be absolutely avoided. After tumour removal haemostasis is maintained. Distilled water irrigation is used on the adrenal bed. Drain is placed to the dissected area **(Fig. 29-7)**.

Left Adrenalectomy

Splenorenal ligament is divided; splenic flexure of the colon is mobilised adequately to retract it downwards. Peritoneum in left paracolic gutter (*Toldt's line*) is incised in its full length; incision is carried upwards through splenic flexure then towards left along the transverse colon in its upper part towards right up to ½ or 2/3rd of its length. Peritoneum in the lower border of the tail of the pancreas is incised. Spleen with tail of the pancreas is mobilised medially and upwards. Renal fascia is incised and superior pole of kidney is dissected. Adrenal gland is exposed. Often large left sided adrenal tumour may be adherent to the tail of pancreas and spleen and in such situation dissection of tail of pancreas and spleen is done through lesser sac by anterior approach. Left adrenal vein joins left renal vein vertically from above downwards after crossing the left renal artery in front. Left inferior phrenic vein joins left adrenal vein. Entire left renal vein should be dissected to have a proper visualisation in large tumour. Left adrenal vein is double ligated securely. It is better to ligate left inferior phrenic vein separately which joins left adrenal vein. Inferior mesenteric vein and splenic vein will be closer in large tumours which should not be injured. Newer energy sources like ultrasonic seal may be useful. Left renal artery runs horizontally just above and behind the left renal vein. Left inferior adrenal artery which arises from left renal artery is identified and ligated. Adrenal vein should be ligated first in functioning pheochromocytoma to prevent the release of catecholamines into the circulation. Periaortic lymph nodes with retroperitoneal fat and adjacent Gerota's fascia are removed along with the tumour in case of adrenal malignancies. Often enblock removal of left kidney, splenic flexure of colon and spleen with tail of the pancreas is done in large aggressive tumours. Occasionally inferior mesenteric vein may require to be ligated in large left adrenal tumour **(Fig. 29-8)**.

In primary hyperaldosteronism and pheochromocytoma, gland is hypervascular and friable. So gland should be held gently over periadrenal fascia using fine forceps. All small vessels should be clipped or haemostasis is achieved using bipolar forceps to prevent haematoma formation which will interfere with further dissection **(Fig. 29-9)**.

Postoperative Care

Respiratory physiotherapy, observation, pain control, prevention of sepsis, observation for bleeding are important. Acute adrenal insufficiency can occur in case of bilateral adrenalectomy which presents as sudden haemodynamic instability and circulatory failure. Prompt adequate steroid supplement is essential in these patients.

In adrenalectomy for pheochromocytoma, because patient is on phenoxybenzamine, more intravenous fluids are required after resection to maintain circulatory volume. During surgery sodium nitroprusside infusion (10 μg/kg/minute) is required. Circulating catecholamine/metanephrine/VMA level estimation and 24 hour urinary catecholamines estimation is needed postoperatively and later on yearly. *Hypertensive exacerbations* and tachycardia are likely to occur during induction of anaesthesia and during direct tumour handling. Intraoperative hypovolaemia, postoperative hypotension should be managed well. Central venous line with CVP monitoring and arterial line for monitor is a must.

In bilateral adrenalectomy postoperatively patient requires oral *steroid and mineralocorticoid* (fludrocortisone 100 μg/day) for lifelong. Even in Cushing's syndrome due to unilateral functioning cortical adenoma, after unilateral adrenalectomy oral steroid supplement is required for 2 years until hypothalamic pituitary adrenal axis which was suppressed earlier recovers to allow contralateral adrenal gland to function.

In adrenalectomy for aldosteronoma, postoperative hypotension, hyperkalaemia and acidosis can occur. It is corrected by intravenous normal saline infusion rapidly and intramuscular injection of deoxycorticosterone acetate (DOCA, 10 mg twice daily).

Regular blood sugar estimation is needed after adrenalectomy for functioning pheochromocytoma as sudden reduction in circulating catecholamine can cause hyperinsulinism and hypoglycaemia **(Fig. 29-10)**.


Rib resection approach
Adrenal tumour - right
Liver
Kidney
IVC

Figs 29-7(1)



Figs 29-7(2)



Figs 29-7(3)

Figs 29-7(1 to 3): Right sided adrenal tumour; removed along with kidney while doing adrenalectomy.

Complications of Adrenalectomy

Bleeding which may life threatening can occur from adrenal vein, inferior vena cava, renal vein, liver, spleen, pancreas and kidney tissue injury. Proper ligation of adrenal vein, reconstruction of the inferior vena cava or renal vein, suturing of the liver or kidney injuries is needed. Satinsky clamp is needed for proper suturing of the IVC. Central line, blood transfusion may be required. Haemorrhage is the most common complication after adrenalectomy.

Injury to pleura (pneumothorax) may warrant intercostal tube placement. On table chest X-ray may be needed after closure of the wound. Postoperative pulmonary collapse, pneumonia, ARDS can occur.

Injury to colon, pancreas and spleen can occur. Bowel injury may cause peritonitis, septicaemia. Injury may due to cautery or energy source or during scissor dissection.

Acute adrenal insufficiency may be fatal if steroid supplement is not started adequately.

Hypovolaemia on table and postoperative hypotension is common after resection of pheochromocytoma. Careful monitoring in critical are unit is needed. *Postoperative hypotension* is common after adrenalectomy for functioning pheochromocytoma due to loss of α receptor mediated sympathetic tone which needs large quantity of intravenous fluids.

Rebound hyperinsulinism due to reduced inhibitory effect on insulin secretion by sudden reduction in circulating catecholamines (catecholamines inhibit insulin secretion thereby causing hyperglycaemia) leading into *hypoglycaemia*. Regular blood sugar estimation postoperatively is important in patients who underwent adrenalectomy for functioning pheochromocytoma. Weekly urinary catecholamine estimation initially and later yearly is important.

Other complications—Wound infection, sinus formation and postoperative wound pain are other problems.

Pheochromocytoma *in pregnancy* has got 50% maternal mortality; vaginal delivery is contraindicated in pheochromocytoma.

LAPAROSCOPIC ADRENALECTOMY

Gagner in 1992 started first laparoscopic transabdominal lateral flank approach which is commonly used. Transperitoneal anterior approach and retroperitoneal posterior approach ((Mercan, et al) are other approaches used.

Laparoscopic adrenalectomy is the safe, effective '*gold standard'* operation for benign adrenal tumour of less than 6 cm in size. Approach, dissection, haemostasis, recovery, morbidity status, pain, hospitalisation are all factors in favour of laparoscopic adrenalectomy. Bilateral tumours are also better amenable through laparoscopy.


Spleen
Pancreas
Incision along the paracolic gutter is essential
Colon
Incision to medialise the spleen
Liver
Spleen
Left adrenal gland
Splenic vessels
Pancreas
Incision to separate from spleen
Incision along the lower border of the pancreas
Kidney
Splenocolic ligament
Colon
Incision along the paracolic gutter
Medialised spleen with tail of pancreas
Left adrenal gland
Pancreas
Left kidney
Colon
Incision is extended along the posterior aspect of the spleen tail of the pancreas and medial to kidney to expose left adrenal completely

Fig. 29-8: Technique of left adrenalectomy.

Indications	*Contraindications*
Cortisol producing adenoma, aldosteronoma Primary adrenal hyperplasia Pheochromocytoma Non functioning cortical adenoma, incidentaloma Adrenal cyst, ganglioneuroma, myolipoma	Adrenal cortical tumour more than 5-6 cm; > 100 grams weight Malignant pheochromocytoma Adrenocortical carcinoma Any adrenal mass more than 8-10 cm Extensive previous upper abdominal surgery

Tumour more than 6 cm makes laparoscopic dissection difficult especially adrenal veins; causing higher chances of tear in IVC or left renal vein. Larger tumour is more likely to be adrenocortical carcinoma which is an indication for open surgery.

Approaches

Lateral flank transperitoneal approach—This position allows retraction of the adjacent organs by gravity to facilitate the exposure of the adrenal glands; adequate access to retroperitoneum as well as abdominal cavity; gives proper working space and triangulation; other organs in the abdominal cavity can be assessed properly. Additional procedures like gall bladder removal are possible. *Disadvantages*: postoperative ileus and mobilisation of colon is required. Opposite adrenal cannot be approached; if needed needs repositioning of the patient.

Transperitoneal anterior approach—It is done in supine position which allows access to both adrenal glands. But it is technically demanding with longer operative period. Mobilisation of viscera like colon, spleen, tail of pancreas, liver is needed. Usually left side adrenalectomy is done first; then right side. Reason is once left side is over which is easier, if conversion is required for right side which will be addressed with conversion right side open approach.

Posterior retroperitoneal approach—It gives direct access to adrenal gland without opening the peritoneal cavity and without a need for mobilisation of other organs. It is also useful for bilateral adrenalectomy wherein change of position is not required in Cushing's syndrome, bilateral pheochromocytoma. But it gives less working space and minimum triangulation; orientation of anatomy from behind becomes difficult; on table inadvertent formation of pneumoperitoneum due to peritoneal tear limits the working space further; pleural injury may occur.

Patient is placed in prone/prone jackknife position. By open method through a small incision just below the tip of 12th rib with splitting the muscle layers retroperitoneum is reached. Through balloon or finger dissection space is widened. CO_2 insufflation can also be done using Veress needle under fluoroscopic guidance also but it is difficult. Additional ports are placed as needed. Second port is in the loin at the level of inferior pole of the kidney just above the iliac crest 5 cm laterally below the 11th rib; 3rd port is at the level of midpoint of kidney just lateral to sacrospinalis; 4th port is 2 cm lateral to that. Further ports if needed may be placed. Retro-pneumoperitoneum pressure should be 20-25 mm Hg which creates more working space and reduces the oozing. 30° telescope is used. Dissection is from lateral to medial first ligating the arteries and branches or sealing using harmonic. In right side, on deeper medial dissection IVC is identified; right adrenal vein is carefully dissected and clipped. Left side inferomedially left renal vein with left adrenal vein entering the left renal vein is identified; left adrenal vein after careful dissection is



Figs 29-9(1)



Figs 29-9(2)

Figs 29-9(1 and 2): Left sided adrenalectomy in a child—neuroblastoma.

clipped and divided. Remaining dissection is done using harmonic device. Haemodynamic and respiratory complications are less here.

Lateral retroperitoneal approach – Here retroperitoneum is approached in lateral position. Initial access port is placed in midaxillary line 3 cm above the iliac crest between latissimus dorsi and external oblique muscles. By open method retroperitoneum is reached; using finger or balloon space is created and widened. Additional ports are placed along the same line. Remaining dissection is same as posterior approach. Advantage here is conversion can be done when needed easily as transperitoneal approach.

Laparoscopic Right Adrenalectomy

Procedure is done under general anaesthesia with lateral decubitus position with right side upward (left lateral decubitus). Reverse Trendelenburg position (head up) is needed. Nasogastric tube and urinary catheterisation is used usually. Central venous line is needed. Right side up with knee adjacent to table is flexed. Safety straps with padding on all pressure pints and compression stockings to both legs. Usually surgeon stands on the right side with camera operator on opposite side leg end or on the right side of the surgeon and assistant is opposite to surgeon. Position can be varied depends on the surgeon's choice and comfort **(Fig. 29-11)**.

Thirty degree telescope with high definition imaging system and medical monitor is needed. Energy source like harmonic sealer is also useful. Basic laparoscopic instruments, suction irrigation device, right angled instrument are all essential. A laparoscopic ultrasound may be useful often. Through Veress needle initial access is achieved at a point two fingerbreadth below the right costal margin medial to right anterior axillary line; through it one 10 mm port is passed for camera. Another 10 mm port is placed in the midaxillary line behind the first port. Two additional 5 mm ports are placed with a 5 cm gap between along the subcostal line in front. 15 mm pressure pneumoperitoneum is needed.

Right triangular ligament is divided using hook or harmonic energy device from IVC to diaphragm. Liver is rotated medially and superiorly. Liver is kept in retracted position using fixed retractor. Retroperitoneum is exposed. Subhepatic IVC, upper pole of the kidney and adrenal gland will be visualised by further careful dissection. Hepatic flexure if required may be reflected downwards by incising its peritoneal attachment. Duodenum is identified medially and in front to IVC. Duodenum is reflected in front and medially to expose IVC further. Peritoneum between adrenal gland and IVC is incised. Dissection between IVC and medial border of the adrenal gland is done for entire length carefully and meticulously. Adrenal gland is reflected away from IVC. *Right adrenal vein* is identified running into the IVC to join. It is less than 1 cm in length and stout. Adrenal gland



Figs 29-10(1)





Figs 29-10(2)

Figs 29-10(1 and 2): Open left sided adrenalectomy for left sided adrenocortical carcinoma—non functioning.



Fig. 29-11: Positions for laparoscopic right adrenalectomy.

is held carefully through its *periadrenal fat* and *thin fascia* and never on the gland substance as it may bleed and breach capsule causing tumour spillage. Right angled dissector is used to isolate, separate and dissect the adrenal vein carefully. Endoclips are placed 2 on the IVC side and one gland side. Right adrenal vein is cut to mobilise the gland from IVC. Endosutures or endovascular stapler can also be used. Arterial branches are divided using clips or harmonic device. Anatomical *variation* of right adrenal vein which may drain at right hepatic or right renal vein instead of IVC should be remembered. Additional *right accessory adrenal vein* may exist above the level of right adrenal vein draining into right hepatic vein. *Arterial branches* are at lower level than adrenal vein and so often it is necessary to divide arterial branches first to facilitate the easier isolation of the right adrenal vein. But *in pheochromocytoma* adrenal vein should be ligated first to prevent early catecholamine release into the circulation. Adrenal gland is elevated off the IVC; posterior border is dissected off the diaphragm then lateral border. Adrenal gland is placed in impermeable pack to retrieve (retrievable bag). Adequate irrigation of adrenal bed using normal saline and also proper haemostasis is essential. Drain if needed is placed. Port sites are closed using vicryl in layers.

Laparoscopic Left Adrenalectomy

Lateral decubitus with left side upward position (right lateral decubitus) is used. Port position is similar counterpart of the right adrenalectomy. Often different port positions are advocated by many. Surgeon stands on the right side of the patient near hip region/abdomen side; camera operator left of the surgeon near left (lower) arm; assisting surgeon near head end above the left arm; staff nurse is extreme right near leg end. Camera operator can stand on the right side of the surgeon also if it seems convenient **(Fig. 29-12)**.



Fig. 29-12: Laparoscopic left adrenalectomy position, port placements.

Splenic flexure of colon is mobilised fully using hook or harmonic device with division of splenocolic attachment. Incision is needed along the entire length of the paracolic gutter along the *line of Toldt* and also along the upper left ½ to 2/3rd of transverse colon. Colon is reflected downwards and towards right. Splenorenal ligament is divided from lower pole of the spleen; splenic attachment to the diaphragm is divided to rotate the spleen and tail of the pancreas medially (rotated off the kidney and left adrenal gland –*open book method*). Short gastric vessels often require to be divided. Left side retroperitoneum is approached. Gerota's fascia is opened to reach the superior pole of the kidney which is dissected free of left adrenal gland.

Adrenal gland is identified between spleen and upper pole of kidney by its *golden orange colour* and fine granular texture. It is often difficult to differentiate adrenal gland (*golden orange*) from tail of the pancreas (*salmon coloured).* Laparoscopic ultrasound is useful to differentiate tail of the pancreas from adrenal gland. Adrenal gland is identified by gentle dissection. Inferomedial border of the gland is dissected first by principle. Inferior phrenic vein joins the left adrenal vein 1.5 cm above the level of the left renal vein. If dissection here finds difficult then gland is mobilissed in its upper, lateral and medial borders of the adrenal gland first and later inferomedial border is addressed. *Left adrenal vein* is dissected using right angle instrument and doubly ligated or clips are applied. Renal vessels should be identified and safeguarded. Left renal artery is above and behind the left renal vein. Left adrenal vein joins left renal vein from above crossing the left renal artery vertically in front. Left inferior adrenal artery arises from left renal artery also to be clipped or ligated. Injury can occur to colon, diaphragm, spleen, tail of the pancreas and diaphragm. Drain is often placed after irrigation and haemostasis of the adrenal bed. Ports are closed in layers.

Conversion Rate

Cause for conversion is bleeding from adrenal vein during dissection. 5-10% is the conversion rate. Learning curve raises the conversion rate. When needed conversion should be postponed to minimize the further complications.

Role of Laparoscopic Ultrasound

It is very useful in identifying small tumours especially in left side and in obese patients. It is also useful in assessing the adjacent structures like renal vessels, IVC. Adrenal vein is difficult to identify through laparoscopic ultrasound. It is useful in identifying associated pathology in other organs and also while doing partial adrenalectomy.

Laparoscopic Partial Adrenalectomy/Cortex Sparing Adrenalectomy

It is done *only selectively* in a small peripherally located bilateral benign tumours or unilateral tumour (peripheral aldosteronoma) wherein opposite side adrenalectomy is already done. Tumour should not be lying close to or over the adrenal vein. Tumour is excised with a 0.5 cm margin of normal adrenal gland. Dissection is done using harmonic scalpel. Haemostasis is achieved using ligaseal or bipolar cautery. Adrenal vein can be preserved in this technique. *Problems* are – tumour spillage and recurrence of tumour even in benign lesion.

Complications and Problems of Laparoscopic Adrenalectomy

Haemorrhage is the main complication of laparoscopic adrenalectomy mainly during dissection of adrenal vein causing tear in IVC or left renal vein. Immediate conversion into open and control of haemorrhage is needed. Suring of tear in IVC or left renal vein after applying vascular clamp is the need.

Injury to various organs like liver, spleen, pancreas, kidney, colon, pleura, diaphragm, etc. can occur which should be dealt with accordingly appropriately.

Pancreatitis and pancreatic fistula may develop which is usually managed conservatively.

Respiratory problems like pneumonia, atelectasis, pneumothorax which is managed with antibiotic, intercostal tube drainage, antibiotics. Pneumothorax due to pleural injury and entry of CO_2 into thoracic cavity is specific problem related to laparoscopic adrenalectomy. In such situation patient if maintains the adequate saturation, laparoscopic procedure can be continued; otherwise conversion is needed.

Deep venous thrombosis, pulmonary embolism needs proper heparin prophylaxis.

Postoperative ileus, port site infection, port site hernia should be treated with antibiotics, conservative treatment and hernia repair.

Acute adrenal insufficiency may be fatal which should be treated with hydrocortisone of adequate dose.

Other complications are – nerve compression, compartment syndrome, renovascular hypertension, lymphocele, tumour recurrence, arrhythmias.

Variation in adrenal vein anatomy on the right side may confuse with right renal vein. Any vein which is not amenable to endoclip comfortably should be cautioned and differentiated from right renal vein.

On left side tail of the pancreas may be mistaken for adrenal gland. Often it may require laparoscopic ultrasound to differentiate. Adrenal gland is bright variegated dark yellow with fine granularity whereas pancreas is greyish white in colour. Upper pole segmental renal artery may be mistaken for adrenal artery. If adrenal artery is more than 0.5 mm in diameter then it is better to reconfirm its identity.

During retraction, liver or spleen may get lacerated during laparoscopy. Cautery injury to adjacent organs can also occur.

In *obese patients*, dissection of adrenal may be difficult due to large quantity of fat covering the adrenal gland. Laparoscopic ultrasound may be useful in such situation.

In *potentially curable adrenal malignancy*, laparoscopic approach is not advised until now.

Remember

- Careful selection of patient for laparoscopic adrenalectomy or open method is important.
- Laparoscopic adrenalectomy is the gold standard for benign adrenal tumours, tumours less than 6 cm sized.
- Malignant adrenal tumours, tumour more than 6-8 cm, previous upper abdominal surgery needs open adrenalectomy.
- Hormonal assessment is a must in all adrenal tumours to identify whether they are functioning or nonfunctioning tumours.
- In pheochromocytoma, on table hypertensive exacerbations are observed. After surgery, hypotension can occur which should be controlled. Postoperative hypoglycaemia is another complication after surgical extirpation.
- Adrenal vein should be ligated first ideally. Ligation of the adrenal vein is crucial step in adrenalectomy.
- Right adrenal vein is short and stout joins IVC posterolaterally. Right adrenal vein begins at the superior part of the hilum of the right adrenal gland. Right adrenal arteries runs from their origin behind the IVC to enter the right adrenal gland.
- Right adrenal gland is little more away and above than right renal vessels compared to left adrenal gland which is close to left renal vessels.
- During dissection adrenal capsule should not be breached to prevent tumour spill over. Gland should be held only over periadrenal fat and fascia using fine forceps.
- Ideally gland after removal should not be morcellated instead it should be retrieved using a retrieval impermeable bag.

Chapter

30

Surgeries in Hernia

Surgical Anatomy of Inguinal Canal

Superficial inguinal ring is a triangular opening in the external oblique aponeurosis and is 1.25 cm above the pubic tubercle. The ring is bound by a superomedial and inferolateral crus. Normally the ring does not admit the tip of little finger.

Deep inguinal ring is a U-shaped (or *Lambda* shaped) condensation of the transversalis fascia, lies 1.25 cm above the inguinal ligament midway between the symphysis pubis and the anterior superior iliac spine (mid inguinal point).

Inguinal canal: In infants both superficial and deep rings are superimposed without any obliquity of the inguinal canal. In adults it is 3.75 cm long, directed downwards and medially from the deep to superficial ring.

In males inguinal canal transmits the spermatic cord, ilio-inguinal nerve (outside the cord within the inguinal canal) and genital branch of the genito-femoral nerve (within the cord). Cord is covered by cremaster muscle which is a continuation of internal oblique muscle, internal spermatic fascia which is a continuation of transversalis fascia. Cord contains testicular artery, artery of vas (a branch of superior vesical artery which is derived from the anterior division of internal iliac artery), cremasteric artery, pampiniform plexus of veins, genital branch of genitofemoral nerve, sympathetic plexus and lymphatics. In females, inguinal canal contains round ligament, indistinct sparse cremaster, cremasteric vessels, ilioinguinal nerve, and genital branch of genitofemoral nerve. Inguinal canal in female is called as *canal of Nuck*. Round ligament (in females) is much more intimately adherent to peritoneum than spermatic cord (in males) **(Figs 30-1 and 30-2)**.

Boundaries of Inguinal Canal

In front: External oblique aponeurosis and conjoined muscle laterally.

Behind: Inferior epigastric artery, fascia transversalis and conjoined tendon medially.

Above: Conjoined muscle (arched fibres of internal oblique).

Below: Inguinal ligament (*Poupart's*) and lacunar ligament (*Gimbernat*).

External ring is a triangular opening in the external oblique aponeurosis lying 1.25 cm above the pubic tubercle. Its superomedial crus is formed by external oblique aponeurosis and inferolateral crus by inguinal ligament.


Inferior epigastric artery
Anterior superior iliac spine
Conjoined tendon
Rectus muscle
Deep inguinal ring
Mid inguinal point
Superficial inguinal ring
Pubic tubercle

Fig. 30-1: Surgical anatomy of inguinal canal.


Pampiniform plexus of veins
Ilioinguinal nerve
Internal spermatic fascia
Artery to cremaster
Testicular artery
Cremasteric fascia with muscle
Genital branch of genitofemoral nerve
Lymph vessels
Artery of ductus deferens
Vas deferens

Fig. 30-2: Contents of spermatic cord.

Internal ring is a normal opening in the transversalis fascia and transverses aponeurosis which is U shaped or lambda (λ) shaped; it is 1.25 cm above the mid inguinal point (between anterior superior iliac spine to pubic symphysis).

An indirect inguinal hernia (hernia though deep ring) travels down the canal on the lateral and anterior aspect of the spermatic cord; whereas the direct hernia pops out directly forward through the posterior wall of the inguinal canal. Neck of the indirect sac is lateral to inferior epigastric vessels but direct sac emerges medial to the inferior epigastric vessels with a wide neck. Saddle-bag or pantaloon hernial sac has got both medial and lateral component. Inguinal hernia is above and medial to the pubic tubercle. Femoral hernia is below and lateral to pubic tubercle **(Figs 30-3 and 30-4)**.

Direct hernia occurs through *Hesselbach's* (1814) triangle which is bound by inferior epigastric artery laterally, lateral border of rectus muscle medially, inguinal ligament below. It is divided into medial and lateral halves by obliterated umbilical artery (medial umbilical ligament). So direct hernia is classified as *medial or lateral depending on which part of the Hesselbach's triangle, it is arising from.* Lateral umbilical ligament is formed by inferior epigastric arteries. Medial type actually is called as *external supravesical hernia* and this fossa is called as *external supravesical fossa* **(Fig. 30-5)**.


Inferior epigastric artery
Indirect sac
Direct sac
Anterior superior iliac spine
Inferior epigastric artery
Deep inguinal ring
Inguinal ligament
Superficial inguinal ring
Sac
Anterior superior iliac spine
Inferior epigastric artery
Deep inguinal ring
SAC
Inguinal ligament
ER
Pubic bone
Cord

Fig. 30-3: Surgical anatomy of direct and indirect inguinal hernia sac.


Ant superior iliac spine
Inguinal ligament
Femoral hernia
Direct inguinal hernia
Indirect inguinal hernia
Pubic tubercle
Inguinal ligament
Lacunar ligament
Conjoined tendon
FN
FA
FV
Inguinal hernia
Femoral hernia
Cooper's ligament
Obturator hernia

Fig. 30-4: Anatomical relations and locations of the inguinal, femoral and obturator hernias.


Anterior superior iliac spine
Inferior epigastric artery
Conjoined tendon
Rectus muscle
Pubic bone
Inguinal ligament
Medial umbilical ligament

Fig. 30-5: Surgical anatomy of Hesselbach's triangle.

Inguinal Defense Mechanisms

Obliquity of inguinal canal creates flap valve mechanism by approximating anterior and posterior walls of the canal. Cooper described external oblique aponeurosis as outer barrier of the inguinal canal causing step down effect for the spermatic cord.

Shutter mechanism of internal oblique forms anterior, roof and posterior wall of the inguinal canal. Roof apposes to floor like a shutter.

External ring is *guarded* by conjoined tendon behind and reflected part of inguinal ligament in front. Internal ring is *guarded* by fleshy internal oblique. Contraction of external oblique aponeurosis causes *pinch cock/slit valve* effect by approximation of two crura of external ring.

Cremaster muscle on contraction helps cord to plug the external ring—*ball valve mechanism*.

Hormones also play a role to maintain inguinal muscles.

Anatomy of Abdominal Wall

Anterior Abdominal Wall

The anterior abdominal wall is a musculofascial dynamic structure which maintains intraabdominal pressure for various physiological functions. It has got three paired flat muscles, two recti abdominis muscles and linea alba in midline. These are anteriorly related to skin, subcutaneous tissue and superficial fascia; posteriorly related to transversalis fascia and peritoneum. *External oblique fascia* (external layer of the fascia of external oblique muscle is also called as *innominate fascia of Gallaudet*) is thin fascial covering of external oblique muscle and fascia which forms intercrural fibers of the superficial inguinal ring; and it extends below into the scrotum as external spermatic fascia.

External oblique muscle arises from middle of body of lower eight ribs running below, front and medially inserting into xiphoid process, linea alba, pubic symphysis, pubic crest, pectineal line of pubis and anterior 2/3rd of outer lip of the iliac crest. It is supplied by lower six thoracic nerves. Lower free border of the external oblique aponeurosis forms inguinal ligament. Triangular opening in its aponeurosis above the pubic crest is called as superficial inguinal ring **(Fig. 30-6)**.

Internal oblique muscle arises from lateral 2/3rd of inguinal ligament, anterior 2/3rd of intermediate part of iliac crest, thoracolumbar fascia; runs upwards, forwards and medially to insert into lower four ribs and cartilages, xiphoid process, pubic crest, pectineal line of pubis. It is supplied by lower six thoracic nerves, 1st lumbar nerve. Aponeurosis below the level of umbilicus remains as a single layer forming the anterior rectus sheath and linea alba. Above aponeurosis splits into anterior lamina which passes medially in front of rectus abdominis and posterior lamina which passes behind rectus abdominis which ends below midway between umbilicus and pubic symphysis as linea *semicircularis of Douglas* (arcuate line). *Semilunar line of Spieghel* lies in lateral border of the rectus sheath from pubic tubercle to the tip of the costal cartilage of 9th rib **(Fig. 30-7)**.

Transverse abdominis muscle originates from lateral 1/3rd of inguinal ligament, anterior 2/3rd of inner lip of iliac crest, thoracolumbar fascia, lower six cartilages with fibers running horizontally forwards inserting into an aponeurosis extending from xiphoid process, linea alba, pubic crest, pectineal line of pubis. Lowest fibers fuse with lowest fibers of internal oblique to form conjoined/conjoint tendon. It is supplied by lower six thoracic and first lumbar nerves. Neurovascular plane of abdomen lies between internal oblique and transverse abdominis muscles **(Fig. 30-8)**.

Rectus abdominis muscle arises from lateral part of pubic crest (lateral head) and anterior pubic ligament (medial head) running vertically upwards to insert into xiphoid process and 7th, 6th and 5th costal


ORIGIN
Linea alba
External oblique muscle
External oblique aponeurosis
Posterior free border
Iliac crest
Inguinal ligament (lower free border)
INSERTION
Superficial inguinal ring

Fig. 30-6: External oblique muscle.


Xiphoid
INSERTION
Linea alba
Aponeurosis
Internal oblique muscle
Thoracolumbar fascia
Arcuate line
ORIGIN
Conjoint tendon
Inguinal ligament

Fig. 30-7: Internal oblique muscle.


Xiphoid
Linea alba
7th rib
Aponeurotic posterior rectus sheath
Transversus abdominis muscle
INSERTION
INSERTION
ORIGIN
12th rib
ORIGIN
Thoracolumbar fascia
Inguinal ligament
Arcuate line
Conjoint tendon

Fig. 30-8: Transverse abdominis muscle.

cartilages. It is supplied by lower six thoracic nerves. There are three tendinous intersections; one at xiphoid, one at umbilicus, one between two which are adherent to anterior half of muscle and anterior wall of rectus sheath. They are due to embryologic segmental origin of muscle which adds to the power of muscle **(Figs 30-9 and 30.10)**.

Inguinal ligament is formed by thickened posteriorly folded lower border of the external oblique aponeurosis extending from anterior superior iliac spine to pubic tubercle; lateral ½ is oblique and rounded and medial ½ is horizontal and grooved. The pectineal part of the inguinal ligament (lacunar) (triangular) is related in front to medial end of the inguinal ligament behind to pectin pubis; apex is attached to pubic tubercle; base directing laterally forms medial wall of femoral ring. Cooper's pectineal ligament is thickened pectineal fascia which is attached to the pectin pubis lateral to the base of the lacunar ligament. Aponeurotic fibers from the inferior crus of the external ring passing superomedially to linea alba is called as *Colles' reflected part of the inguinal ligament.*


INSERTION
Xiphoid process
Tendinous intersections
Rectus abdominis muscle
Inguinal ligament
Origin (Two heads)

Fig. 30-9: Rectus abdominis muscle.


Superior epigastric artery
Nerves piercing posterior rectus sheath
Posterior rectus sheath
Inferior epigastric artery
Linea semicircularis
Inguinal ligament
Nerves entering rectus muscle
Rectus muscle (Retracted)

Fig. 30-10: Abdominal wall anatomy behind the rectus muscle.

Cremaster muscle is muscle fascicule embedded in cremaster fascia *(Scarpa's sheath)* which are attached to inguinal ligament laterally, internal oblique, transverse abdominis and conjoint tendon, pubic tubercle and pubic crest medially. It is seen properly only in males; sparse in females. It is supplied by genital branch of genitofemoral nerve (L1). It suspends the testis in elevated position. It closes during raise in intraabdominal pressure; it protects nerves of the inguinal canal. During hernioplasty if cremaster is excised, testis may hang like clapper bell due to loss of suspensory and retractile function of the cremaster. So if cremaster is excised, medial cut end should be sutured to inguinal ligament or pubic tubercle. Stroking medial aspect upper thigh will cause reflex contraction of cremaster with elevation and retraction of testis—*cremasteric reflex* which is absent in upper motor neuron disease. Reflex is through femoral branch (stroking of medial thigh) of genitofemoral nerve to genital branch of genitofemoral nerve (cremaster muscle) through spinal cord.

Pyramidalis is a small triangular rudimentary muscle arising from anterior surface of body of pubis running upwards and medially in front of the rectus abdominis to insert into linea alba; which is supplied by T12 subcostal nerve which is tensor of linea alba **(Fig. 30-11)**.

Deep Nerves of the Abdominal Wall

Lower five intercostal and subcostal (lower six thoracic) nerves and iliohypogastric and ilioinguinal nerves supply the anterior abdominal wall. *Lower five intercostal nerves* pass through the slips of origin of transversus abdominis muscles; runs between transversus abdominis and internal oblique; pierces the posterior lamina of internal oblique aponeurosis to reach rectus sheath; then passes behind the rectus sheath in front of the epigastric vessels, pierces the rectus muscle to continue as anterior cutaneous nerve. Before piercing it supplies the anterior rectus sheath transversus abdominis, internal oblique, external oblique and rectus abdominis. During its course it also gives lateral cutaneous nerve of the abdominal wall through flat abdominal muscles. *Battle's incision* which is pararectal incision will injure these nerves causing weakening of the rectus muscle and so is avoided.

Subcostal nerve, anterior primary ramus of 12th thoracic nerve after travelling behind the diaphragmatic lateral arcuate ligament, passes in front of the quadratus lumborum and then pierces the transversus abdominis to run like other intercostal nerves. It supplies pyramidalis muscle and gluteal region as lateral cutaneous branch.

Iliohypogastric nerve arises from the anterior division of L1 nerve runs away from lateral margin of psoas major muscle in front of quadratus


Rectus muscle
Conjoint tendon
Pyarmidalis
Deep ring
Inguinal ligament
External ring
Cremaster muscle
Cremaster fascia
Scrotum

Fig. 30-11: Anatomy of pyramidalis and cremaster.

lumborum behind kidney and colon to pierce transversus abdominis just above the iliac crest; runs between transversus abdominis and internal oblique; pierces the internal oblique 2.5 cm above the anterior superior iliac spine, run between internal oblique and external oblique to reach 2.5 cm above the superficial inguinal ring where it pierces the external oblique aponeurosis to supply skin around the area.

Ilioinguinal nerve also arises from anterior division of L1 nerve runs over the quadratus lumborum, iliac crest pierces the transversus abdominis 3.5 cm medial to anterior superior iliac spine; runs between transversus abdominis and internal oblique for a short distance to pierce internal oblique just below and medial to iliohypogastric nerve lateral to deep inguinal ring; runs in inguinal canal outside the cord is males or round ligament (in females), passes through superficial inguinal ring; runs in front of the scrotum to supply anterior part of the scrotum.

The genitofemoral nerve arises from ventral divisions of L1, L2 nerves; passes through the medial part of the psoas major muscle running below in front of the muscle; just above the deep ring it divides into medial genital and lateral femoral branches. Genital branch after piercing the psoas sheath runs in front of the external iliac artery and passes through deep ring to enter the inguinal canal within the spermatic cord in males or round ligament in females. It supplies cremaster muscle, runs in the cord to reach anterolateral aspect of the scrotum and supplies that part. In females it gives sensory branches to round ligament and labium majus. Femoral branch passes along with the femoral artery to supply skin over the femoral triangle.

Lateral cutaneous nerve of thigh (lateral femoral cutaneous nerve) arises from dorsal divisions of L2, L3 of lumbar plexus comes out at lateral border of the psoas major muscle passing on the inner lower short part of the quadratus lumborum to run on the main bulk of the iliacus muscle downwards and laterally; pierces the transversus abdominis, internal oblique and external oblique through and through (without travelling in between these muscles); passes behind the lateral part of the inguinal ligament 2-2.5 cm medial to anterior superior iliac spine. It supplies the skin over upper lateral part of the thigh and anterior part of the gluteal region after dividing into anterior and posterior branches **(Fig. 30-12 to 30-14)**.

Femoral nerve arises from dorsal divisions of L2, L3, L4 nerves of lumbar plexus, runs in the lower lateral border of the psoas major muscle in a groove between psoas major and iliacus muscles to reach the thigh along the lateral most compartment of the femoral canal. It supplies the iliacus muscle.



Fig. 30-12: Nerves in the groin. Ilioinguinal, iliohypogastric and genital branch of genitofemoral nerves are important three nerves which surgeon will come across during the open inguinal hernia surgery.

Obturator nerve arises from ventral divisions of L1, L2, L3 nerves of lumbar plexus runs on the medial aspect of the psoas major muscle; passes forwards and below into the pelvic brim where it is crossed by internal iliac artery and ureter to enter the obturator canal. In the canal it divides into anterior and posterior divisions. Anterior division supplies pectineus, adductor longus, gracilis and often adductor brevis muscles and hip joint. Posterior division supplies obturator externus, adductor magnus and often adductor brevis muscles, through genicular branch which runs in adductor canal, popliteal fossa, and oblique popliteal ligament supplies the knee joint. This genicular branch often gets compressed in obturator hernia to cause referred pain in knee joint (*Howship Romberg sign*).

Muscles of the Posterior Abdominal Wall

They are psoas major, psoas minor, quadratus lumborum and iliacus. *Psoas major* arises from body and transverse processes of all lumbar vertebrae to insert into the tip and medial part of the lesser trochanter of the femur after passing behind the inguinal ligament along with the iliacus tendon (lateral part of the lesser trochanter). It is supplied by L2, L3, L4 spinal nerves. *Psoas minor* is small muscle in front of the psoas major arises from bodies of T12 and L1 vertebrae to insert into the pectin pubis and iliopubic eminence. It is supplied by L1. *Iliacus* arises from upper 2/3rd of inner aspect of fossa of ilium, upper lateral part of the sacrum to insert into lateral part of the lesser trochanter along with psoas major. It is supplied by femoral nerve. *Quadratus lumborum* arises from transverse process of L5 vertebra and inner lip of iliac crest to insert into medial part of the anterior surface of 12th rib and transverse processes of upper four lumbar vertebrae. It is supplied by spinal nerves T12 to L4.

Fascia Transversalis (Cooper's Fascia)

It is the fascia that lines the inner surface of the transversus abdominis muscle separated from the peritoneum by extraperitoneal connective tissue. In front it is adherent to linea alba above the umbilicus; behind merges with anterior layer of thoracolumbar fascia and renal fascia; above with diaphragmatic fascia; below it is attached to inner lip of iliac crest, inguinal ligament; medially it is attached to pubic tubercle, pubic crest and pectineal line which prolongs down as anterior layer of femoral sheath. It also forms internal spermatic fascia around the cord. Deep inguinal ring is U/lambda/oval shaped opening 1.25 cm above the mid inguinal point (between pubic symphysis and anterior superior iliac spine) which is lateral to inferior epigastric artery, transmits spermatic cord in males and round ligament in females. In the inguinal area transversalis fascia is *bilaminar* enclosing the inferior epigastric vessels. *Space of Bogros* is extension of the retropubic *space of Retzius* which is located beneath the posterior lamina of transversalis fascia and in front of the peritoneum. Inlay preperitoneal mesh repair is done by placing mesh in this space. Thickening of the transversalis fascia at medial side of the internal ring and in front of the inferior epigastric vessels is called as *interfoveolar Hesselbach's ligament*.

Endoabdominal Fascia

Endoabdominal fascia is connective tissue that lines inner aspect of the entire abdominal musculature. Part in relation to transversus abdominis is called as fascia transversalis. It forms iliac, diaphragmatic and renal fascia.


Iliohypogastric nerve
Ilioinguinal nerve
Ilioinguinal nerve
Ilioinguinal nerve
Iliohypogastric nerve

Fig. 30-13: Ilioinguinal nerve and iliohypogastric nerves.


Quadratus lumborum
Iliohypogastric nerve
Ilioinguinal nerve
Lateral femoral cutaneous nerve
Femoral branch of genitofemoral nerve
Genitofemoral nerve
Psoas major muscle
Genital branch of genitofemoral nerve
Ilioinguinal nerve
Iliohypogastric nerve

Fig. 30-14: Anatomy of different nerves in relation to groin hernia.

Iliopubic Tract (Bandelette of Thomson)

Iliopubic tract is confused with inguinal ligament. It is an aponeurotic band extending from iliopectineal arch (thickened medial part of the iliopsoas fascia) and anterior superior iliac spine to superior ramus of the pubis forming deep musculoaponeurotic layer with transversus abdominis muscle, aponeurosis and transversalis fascia; it runs medially along inferior margin of the deep ring, anterior margin of the external iliac vessels, femoral sheath to attach to the pectineal ligament of Cooper **(Fig. 30-15)**.

Blood Supply of Abdominal Wall

It is divided into superficial and deep vessels. ***Superficial vessels*** are superficial epigastric, superficial circumflex iliac and superficial external pudendal arteries—are branches of femoral artery. They travel towards umbilicus in subcutaneous plane. Superficial epigastric artery communicates with opposite superficial epigastric artery and all three communicate with deep arteries.


External supravesical hernia site
Median umbilical ligament (urachus)
Medial umbilical ligament (bliterated umbilical artery)
Direct inguinal hernia site
Lateral umbilical ligament (Inferior epigastric vessels)
Indirect inguinal hernia site
Deep ring
Gonadal vessels
Urinary bladder
External iliac vessels
Vas deferens

Fig. 30-15: Ligaments related to groin and hernia surgery.

Deep arteries are posterior intercostal arteries (10, 11), anterior branches of four lumbar and subcostal arteries and deep circumflex iliac artery. Deep arteries travel between transversus abdominis and internal oblique muscles. Recti are supplied by superior and inferior epigastric arteries. *Superior epigastric artery* is one of the two terminal branches of the internal thoracic/mammary artery. It originates at 6th intercostal space enters the abdomen between costal and xiphoid origin of the diaphragm, enters the rectus sheath from above, behind the 7th costal cartilage. It descends downwards communicating with inferior epigastric artery behind the rectus muscle. Branches are muscular, cutaneous, hepatic along the falciform ligament and anastomotic to opposite side artery.

Inferior epigastric artery (IEA) originates from external iliac artery just above the inguinal ligament, runs upwards and medially in the extraperitoneal connective tissue between peritoneum and posterior lamina of transversalis fascia initially medial to internal ring; pierces the transversalis fascia at the lateral border of the rectus muscle; runs in front of the arcuate line supplying the rectus and ends by anastomosing with superior epigastric artery. Branches are—muscular, cremasteric, pubic, and cutaneous. *Cremasteric branch* after travelling laterally towards deep ring supplies cremaster and runs along the spermatic cord. Pubic branch runs medially along the pubic bone to communicate with pubic branch of anterior division of obturator artery. Often obturator artery may be replaced by this pubic branch of inferior epigastric artery as abnormal/aberrant obturator artery. This pubic branch crosses over femoral ring and Cooper's ligament. This may be injured during fixation of mesh in TEP repair or femoral hernia repair causing torrential bleeding from both cut ends. As medial cut end retracts deep into the obturator fat and fascia it is difficult to control bleeding. This area is often called as *circle of death*. Inferior epigastric vein is medial to IEA **(Fig. 30-16)**.

Deep circumflex iliac artery arises from lateral side of the external iliac artery behind the inguinal ligament which after piercing the transversalis fascia runs along the iliac crest; at its middle it again pierces the transversus abdominis and internal oblique to reach adjacent to anterior superior iliac spine where it anastomoses with superior gluteal, superficial circumflex iliac, lateral circumflex femoral arteries. Here it also gives ascending branch which runs in abdominal wall which may be injured in TEP causing large haematoma.

Bendavid circle: It is the circle where venous network is situated in *space of Bogros* formed by branches of inferior epigastric, iliopubic, suprapubic, and retropubic veins. They communicate with aberrant obturator vein which is commonly existing (70%). During laparoscopy (TEP/TAPP) due to high insufflation pressure veins will collapse and will not bleed during dissection but bleeds later in postoperative period.

Triangle of doom is observed in laparoscopic hernia procedure. It is a triangle formed medially by vas deferens, laterally by testicular vessels and peritoneal reflection below with the apex at internal ring. External iliac vessels lie in this triangle and so extreme care should be taken while dissecting the hernia sac in this triangle.

Preperitoneal Space of Nyhus

It is the space between transversalis fascia and peritoneum. Medially, it is in front of the urinary bladder and behind pubic bone as retropubic space of Retzius (1858). Laterally it continues as space of Bogros (1823). Below it is limited at iliopubic tract; laterally to anterior superior iliac spine and iliopsoas fascia. Iliopubic tract is analogue of the inguinal ligament, extends from Cooper's ligament to anterior superior iliac spine which divides endoscopic view of pre-peritoneal space into *superior compartment* (contains inferior epigastric artery, Hesselbach's triangle, cord structures and is site of inguinal hernia) and *inferior compartment* (contains femoral canal, iliac vessels (vein medially and artery laterally) iliopsoas muscle, genitofemoral nerve, lateral femoral cutaneous nerve). External iliac vessels lie in a triangle formed by gonadal vessels laterally, vas deferens medially and peritoneal reflection inferiorly (*triangle of doom*). Aberrant obturator artery which is an occasional branch of inferior epigastric artery replacing its pubic branch travels across Cooper's ligament, which during fixation of mesh can cause torrential haemorrhage—*circle of death*. *Triangle of pain* is formed by gonadal vessels medially, iliopubic tract laterally and peritoneal reflection below. Genitofemoral nerve and lateral cutaneous nerve of thigh traverse this triangle. Injury to these nerves either by dissection or by tacks causes severe post operative pain. Tacks/staplers should not be placed in this triangle.



Fig. 30-16: Inferior epigastric vessels—on table look.

Endoscopic hernia repair needs dissection and exposure of the entire myopectineal orifice from midline to anterior superior iliac spine

Fruchaud's (French Surgeon) Myopectineal Orifice (MPO)

It is an osseo-myo-aponeurotic tunnel. *It is through this tunnel that all groin hernias occur.* It is bound medially by lateral border of rectus sheath; above by the arched fibres of internal oblique and transverse abdominis muscle; laterally by the iliopsoas muscle; below by the pectin pubis and fascia covering it.



Fig. 30-16A: Myopectineal orifice of Fruchaud's.

Fossae of the Anterior Abdominal Wall

There are three fossae on the inner surface of the anterior abdominal wall above the ligament and below the umbilicus. *Lateral fossa* is lateral to lateral umbilical ligament (which contains inferior epigastric artery) which is the site of indirect inguinal hernia. Lateral fossa contains deep inguinal ring. *Medial fossa* is between lateral and medial umbilical ligament (obliterated umbilical artery). Here direct hernia develops. *Supravesical fossa* is between medial and median (obliterated urachus) umbilical ligament which is the site of external supravesical hernia. Internal supravesical hernia develops in relation to urinary bladder directly, as anterior prevesical, posterior retrovesical and lateral paravesical.

NEWER CLASSIFICATIONS OF GROIN HERNIA

Gilbert Classification

***Type I*:** Hernia has got snug internal ring through which a peritoneal sac passes out as indirect sac.

Type II: Hernia has a moderately enlarged internal ring which admits one finger but is lesser than two fingerbreadth. Once reduced it protrude during coughing or straining.

Type III : Hernia has got large internal ring with defect more than two fingerbreadth. Hernia descends into the scrotum or with sliding hernia. Once reduced it immediately protrudes out without any straining.

Type IV: It is direct hernia with large full blow out of the posterior wall of the inguinal canal. The internal ring is intact.

Type V: It is a direct hernia protruding out through punched out hole/defect in the transversalis fascia. The internal ring is intact.

Type VI: Pantaloon/double hernia.

Type VII: Femoral hernia.

TYPE VI and VII are Robbin's modifications **(Figs 30-17A and B)**.

NYHUS Classification

It is based on size of the internal ring and posterior wall weakness.

Type I: Indirect hernia with normal deep ring.
Type II: Indirect hernia with dilated/widened deep ring.
Type III: Posterior wall defect.
  a. Direct.
  b. Pantaloon hernia: Indirect with posterior wall weakness.
  c. Femoral hernia.
Type IV: Recurrent hernia.

BENDAVID Classification

Type I: Antero-lateral defect (indirect).
Type II: Antero medial. (direct).
Type III: Postero-medial (femoral).
Type IV: Posterior-prevascular hernia.
Type V: Antero-posterior defect: Inguino-femoral hernia.

INDIRECT (OBLIQUE) INGUINAL HERNIA (FIG. 30-18)

This is the most common type of hernia. It is more common in younger age group as compared to direct inguinal hernia which is more common in elderly. It is more common on right side in 1st decade but in 2nd decade the incidence is equal on both sides. Hernia is bilateral in 30% of cases. Sac is thin in indirect type. Neck is narrow and, lies lateral to inferior epigastric vessels **(Fig. 30-19)**.

Types: (1) *Bubonocele*, where the hernia is limited to inguinal canal; (2) *Funicular where p*rocessus vaginalis is closed just above the epididymis. Contents of the sac can be felt separately from testis, which lies below the hernia. (3) *Complete (Scrotal*) where testis appears to lie within the lower part of hernia. It can occur in any age group. It occurs in a congenital preformed sac (*processus vaginalis*). More commonly contents descend into the pre-existing sac only when there are precipitating causes which force the content down **(Fig. 30-20 to 30-22)**.

SURGERIES FOR INGUINAL HERNIA

History of Hernia Surgery

Original Eduardo Bassini (Padua, 1889) repair is though an anterior approach. He opened posterior wall of inguinal canal and did a sutured three layered repair. In modified Bassini repair transverse arch is sutured to the shelving edge of inguinal ligament as single layered interrupted sutures.

De Chauliac differentiated inguinal from femoral hernias (1363). Kaspar Stromayr differentiated direct and indirect hernias in 1559. Ambroise Pare (1550) used trusses in hernia. John Hunter, Astley Paston Cooper (1841) Franz Hesselbach, Antonio Scarpa (1832), Pieter Camper, Jules Germain Cloquet (1883), Bogros, Retzius contributed in understanding anatomy of the groin.



Figs 30-17A and B: Bilateral direct hernia.



Fig. 30-18: Complete indirect hernia

La Roque, GL Cheatle, JP Hoguet, AK, Henry, McVay, McEvedy, Lotheissen, McArthur (used strips of external oblique aponeurosis to approximate conjoined tendon to inguinal ligament), Kirschner (used thigh fascial grafts), Gallie (used strips of fascia lata for repair using his specialized needle *Gallie's needle*), Handley (used silk with staylace darning), Meick (used first multifilament Nylon), Haxton (used monofilament Nylon), Moloney (Nylon darn procedure, 1948) are the others who contributed to hernia surgery.

Halsted (John Hopkins Baltimore) did four layered repair shifting cord anterior to the external oblique aponeurosis thus bringing superficial and deep ring directly very close causing higher chances of recurrence.

EE Shouldice (1945) of Toronto did repair of transversalis fascia under local anaesthesia as a tension free 4/6 layered tissue repair.

Usher from Texas in 1958 first used Marlex mesh in posterior wall for repair as tension eliminating.

Lichtenstein (1970) did rolled plug mesh repair of femoral hernia. Newman (New Jersey) did tension free inguinal hernia onlay mesh repair. Lichtenstein and Amid made this technique popular worldwide with certain modifications.

Nyhus from Chicago and Condon from Milwaukee popularized open posterior repair from higher approach. Their technique probably became basis for TEP/TAPP.

Stoppa and Rives (France) evoluted giant reinforcement of the visceral sac by blocking Fruchaud's myopectineal orifice (MPO) bilaterally.

EH Phillips and JB McKeran started TEP in 1990. Arregui started TAPP in 1992 **(Fig. 30-23)**.

Anaesthesia Used for Inguinal Hernia Repair

General/spinal/epidural or local anaesthesia can be used to do inguinal hernia repair.

Local anesthesia is becoming popular; for open approach. General anesthesia is needed in children, for TAPP and TEP procedures.

Technique of Local Anesthesia

Around 50-60 mL of xylocaine 0.5% is used. Plain xylocaine 0.5% or xylocaine 0.5% with adrenaline can be used. Plain xylocaine—dose is 2 mg/kg body weight. Xylocaine with adrenaline—dose is 7 mg/kg body weight **(Fig. 30-24)**.

Two Methods are Used

1. *Nerve block method (Point block*)
   10 mL of xylocaine is infiltrated 2 cm above and medial to anterior superior iliac spine to block the iliohypogastric nerve. Midinguinal point is infiltrated with 10 mL xylocaine. Area around the pubic tubercle place is infiltrated with 10 mL xylocaine. 10 mL of xylocaine is infiltrated just below the inguinal ligament lateral to femoral artery to block the genital branch of genitofemoral artery. Line of skin incision is infiltrated with 10 mL of xylocaine. Later neck of the hernial sac is infiltrated with 10 mL of xylocaine.
2. *Field block method (Shouldice method*)
   Skin of around 4 cm wide area is infiltrated including the subcutaneous plane as first layer from anterior superior iliac spine to pubic symphysis. Skin, subcutaneous and two layers of superficial fascia (Camper and Scarpa's) are incised. Area deep to external oblique aponeurosis is infiltrated with 10 mL of xylocaine. External oblique aponeurosis is incised. Exposed inguinal canal and hernial sac is infiltrated with 10 mL of xylocaine to continue with the dissection.

Different Surgeries (Fig. 30-25)

Herniotomy in Infants

In infants, whether it is hernia or hydrocele, *only herniotomy* is done through inguinal approach (*Michaelis plank operation)*. High ligation is the procedure of choice. Few advocated bilateral inguinal herniotomy in all children with unilateral/bilateral inguinal hernias. Hernia here is due to patent processus vaginalis and always indirect.



Fig. 30-19: Surgical anatomy of indirect hernia and types of indirect inguinal hernia.



Fig. 30-20: Bubonocele.



Fig. 30-21: Enterocele in a hernial sac.

It is common in boys (9:1); common on right side; 15% bilateral. Often presentation is like hydrocele. It is often associated with undescended testis. Incarceration of bowel is very high in male infants with inguinal hernia. It is near 30% in premature or child less than 1 year. From 1 year to 18 years age group incarceration is around 15%. In girls, ovary and fallopian tubes are common content; strangulation of ovary is common. Conservative treatment should not be done in childhood inguinal hernia **(Fig. 30-26 to 30-28)**.

Inguinal canal approach: Technique is same as in adults but more care and meticulous technique is needed. Superficial inguinal ring should not be opened to avoid the scarring of the superficial inguinal ring. Vas deferens should not be held with haemostat or forceps. Fine non toothed Adson's forceps can be used if only needed. Whenever sac is complete distal part is left alone after transecting the sac; proximal part is ligated high above the level of the deep ring. Before ligating one should ensure that contents are pushed properly into the peritoneal cavity. Usually hydrocele is due to infantile hernial sac and so there is no need to do a separate incision for hydrocele; instead distal part of the sac is opened for an adequate length, followed by removal of fluid content and later sac is left open like that. Separate hydrocele or encysted hydrocele if present, should be dealt through same incision. Repair is not needed along the floor of the inguinal canal; and it will disturb the shutter mechanism if repair is done. Transversalis fascia should not be injured. *Very rarely* when direct sac is present posterior wall may be repaired by suturing conjoined tendon to inguinal ligament using 3 interrupted polypropylene sutures. But a surgeon should remember that *in children there is no repair in inguinal hernia*. Wound is closed in layers. Contralateral exploration is often advocated by many as a routine practice.



Fig. 30-22: Indirect hernial sac



Fig. 30-23: Mesh plasty has become standard now.

Inguinal incision without opening the inguinal canal approach: In infants variation in approach can be undertaken but with difficulty. Here medial inguinal incision is made. Cord structures coming



Fig. 30-24: Open inguinal surgery is commonly done under local anaesthesia.



Fig. 30-25: Large hernia needs catheterization before surgery.

out of the superficial inguinal ring is identified without opening the superficial inguinal ring and external oblique aponeurosis. Inguinal canal in infant is very short with superficial and deep rings lying at same level. Sac once identified by careful meticulous dissection and traction, can be reached up to deep ring. Proximal sac is ligated with transfixation. Distal sac is left open. One should avoid injuring vas, testicular veins in the cord as they are very fine in infants. Use of bipolar cautery (not monopolar) is essential. Wound is closed in layers.

Suprainguinal preperitoneal open approach is also used. External oblique, internal oblique and transverse abdominis are split after skin and subcutaneous layer incision. Transversalis fascia is incised. Preperitoneal space is entered to identify the indirect sac which is dissected. Proximal part of the sac is ligated and distal part is cut and left open to retract below.

Transperitoneal laparoscopic approach is present alternative where the hernial sac is ligated proximal to deep ring by placing polypropylene purse string sutures on both sides.

In incarcerated hernia if strangulation is found even after release of the constriction band, then laparotomy approach is better and safer (lower abdomen horizontal incision) to do resection and anastomosis of the bowel.

Complications: Recurrence (< 1%), haematoma, seroma, injury to vas, post herniotomy hydrocele, testicular atrophy. Recurrence is due to injury to transversalis fascia (leads into direct hernia later), missed sac, improper ligation of the sac, sepsis, connective tissue disorders. As vas deferens and testicular vessels are very fine structures in infants and children injury may occur which should be avoided. If injury to vas occurs it should be repaired using 8 zero polypropylene sutures using microscope.

In Adults

It includes *herniotomy i.e.* excision of hernial sac and ***herniorrhaphy or hernioplasty*** (strengthening of the posterior wall of inguinal canal either by repair or mesh).

Herniotomy

Anaesthesia: Spinal or G/A or local anaesthesia.

Procedure

After cleaning and draping, skin is incised 1.25 cm above and parallel to the medial two third of inguinal ligament. Two layers of superficial fascia (outer Camper's fascia and inner Scarpa's fascia) are incised. Superficial pudendal and superficial epigastric vessels are ligated with catgut or cauterized. Self retaining mastoid or similar retractor is placed to retract the skin edges. External oblique aponeurosis is incised along its long axis parallel to the line of skin incision. Incision is extended on either ends of the incision; medially it is extended to cut the margins of the superficial ring. Upper leaf is reflected above and held with haemostat; using peanut dissection upper leaf is raised adequately to visualize conjoined tendon and lateral rectus sheath. Lower leaf is reflected downwards to visualize and expose the inguinal ligament. Entire inguinal ligament is dissected medially and exposed with its shelving edge and iliopubic tract. Ilioinguinal nerve is safeguarded. Cremasteric muscle (box) with its fascia is opened longitudinally as medial and lateral flaps. Cremaster vessel is ligated and cremaster muscle is excised after ligating proximally and distally. Cremasterectomy is not essential. Even though it exposes cord and posterior inguinal wall well; it causes hanging testis without support (*clapper in bell*). Many advocate stitching the distal sutured part to pubic tubercle after cremasterectomy, so that it will give support to testis partially. It is not mandatory to excise entire cremaster. If there is a lipoma of the cord *it should be* excised; but normal fat in the cord should not be removed. If removed it may cause testicular oedema and hydrocele. Cord structures are dissected. Sac lying anterior and lateral to cord is identified and is pearly white in color. Dissection is usually started from the fundus and extended towards the neck which is identified by the extra peritoneal fat. The neck is narrow and is lateral to inferior epigastric artery. *High dissection beyond the deep ring* is done. Sac is opened at the fundus. Finger is passed to release any adhesions. Sac is twisted so as to prevent the content from coming back. It is transfixed using absorbable suture material (chromic catgut 2-0 or vicryl) and is excised (redundant sac) distally **(Figs 30-29 to 30-33)**.


4
4
4
4
5
3
1
2
1. Inguinal canal approach
2. Inguinal incision outside the external ring approach
3. Suprainguinal preperitoneal approach
4. Laparoscopic approach
5. Laparotomy - lower transverse approach

Note: – Superficial ring should never be cut
– Inguinal repair should never be done
– Distal part of the sac should not be ligated
– Separate exploration of hydrocele is not needed

Fig. 30-26: Different approaches for herniotomy in infants and children.



Fig. 30-27: Right sided inguinal hernia in a child.



Fig. 30-28: Incision for right sided inguinal hernia in a child.



Fig. 30-29: High dissection above the internal ring is required in indirect sac.



Fig. 30-30: Lipoma of the cord is a common entity; when present it should be excised.

Hernia Repair

Repair may be
- *Pure tissue repair:* Shouldice, Mac Vay (still very useful repair) and modified Bassini
- *Prosthetic repair:* Lichtenstein, Rives, Gilbert, Stoppa, TEP, TAPP



Fig. 30-31: Vas deferens should be identified and safeguarded especially in children.



Fig. 30-32: Indirect sac after opening at the fundus is twisted to avoid contents getting entangled prior to transfixation.

It means repair or strengthening of the posterior wall of the inguinal canal. By principle defective first layer which is transversalis fascia should be used in repair. Strengthening can be done by tissue or prosthetic repair. Strengthening by tissue repair has got various approaches where transversalis fascia or tendinous fascio-aponeurotic upper part is approximated to iliopubic tract or Cooper's ligament or shelved edge of the inguinal ligament. Upper leaf taken for repair should be tendinous fascioaponeurotic layer not fleshy red muscle. Non absorbable monofilament sutures like polypropylene should be used ideally. In few centers delayed absorbable sutures are used but it is not considered to be ideal. Prosthetic repair is done by placing mesh or prosthesis by onlay/inlay/sublay/sublay intraperitoneal method. Tissue prosthesis like tensor fascia lata or temporal fascia are not used now. Polypropylene mesh is commonly used with different modifications. Approach for repair may be ***anterior*** through inguinal canal (for tissue repair and mesh repair either onlay or sublay) or ***posterior*** through high suprainguinal preperitoneal.

Modified Bassini's Herniorrhaphy

Conjoined tendon and inguinal ligament are approximated using interrupted non absorbable monofilament sutures (polypropylene); medial most stitch is taken from the periosteum of pubic tubercle (*called as key or Bassini's stitch)*; external oblique is closed and other layers are closed. Bassini originally used silk suture for the repair (1887). He also used triple layer of upper leaf which contains transversalis fascia, transversus abdominis and internal oblique muscles in this repair. Care should be taken not to injure iliac vessels (mainly vein) while taking bite from inguinal ligament. It is often practiced to take bites in inguinal ligament at different levels to prevent tearing of the fibers of inguinal ligament. Laterally repair is done beyond the line of internal ring. Few advocate horizontal mattress sutures starting from conjoined tendon to inguinal ligament and from inguinal ligament to conjoined tendon **(Figs 30-34 to 30-36)**.

Complications of Herniorrhaphy
- Haemorrhage.
- Haematoma.
- Infection (5%).
- Haematocele.
- Post herniorrhaphy hydrocele, lymphocele.
- Hyperaesthesia over the medial side of inguinal canal due to injury to ilioinguinal or iliohypogastric nerve.
- Recurrence.
- Osteitis pubis.
- Injury to urinary bladder/bowel.
- Testicular atrophy, penile oedema rarely can occur.



Fig. 30-33: Technique of transfixation of the sac.


Bassini's repair using
interrupted monofilament sutures
Approximation of inguinal ligament and
conjoined tendon — Bassini's tissue repair
Few advocate horizontal
mattress sutures
Polypropylene
suture
Conjoint
tendon
Inguinal
ligament

Fig. 30-34: Bassini's tissue repair. It is not commonly used now; it is useful in strangulated inguinal hernia or when there is infection where mesh is contraindicated.

Lytle`s Repair (William James Lytle)

Often internal ring is narrowed by placing interrupted sutures over the medial side of the ring to the transversalis fascia using either silk or polypropylene (to narrow the ring and push the cord laterally) **(Fig. 30-37)**.

Halsted (USA) – Tanner (London) Slide Operation

To reduce the tension in the repair area, relaxing incision is placed over the lower rectus sheath so that conjoined tendon is allowed to slide downwards **(Fig. 30-38)**.

Abrahamson Nylon Darning

Continuous intervening network of non absorbable sutures are placed between conjoined tendon and inguinal ligament to give good support to posterior inguinal wall.

Koontz`operation (Koontz AR – New York, 1963)

In old people after taking consent, orchidectomy is done along with removal of full cord, testis and total closure of posterior inguinal wall by repair so as to reduce the recurrence.

Removal of Cord in the Inguinal Canal

Cord is removed from the inguinal canal by ligating both at external and internal ring. But testis is retained (for psychological reason) and closure of inguinal canal by repair is done.

Mc Vay Operation – 1940 - (Cooper's Ligament Repair)

It is repaired by placing interrupted sutures between the edge of transversus abdominis to Copper's ligament starting from pubic tubercle medially towards femoral sheath and later continued as suture repair between transversus abdominis and iliopubic tract laterally up to the entrance of cord. It is a pure tissue repair. It requires relaxing vertical/curvilinear oblique incision at the lateral border of the anterior rectus sheath from pubic tubercle to a point superiorly for 4 cm. It covers all three groin defects (myopectineal orifice)—indirect, direct and femoral.

Nyhus (Original) Iliopubic Repair

To have a suprainguinal approach, a transverse incision is made two fingerbreadths above the pubic symphysis to expose the rectus sheath. Left index finger is passed into the external ring; level of internal ring is confirmed. Anterior rectus sheath is incised horizontally above the level of the deep ring; lateral part of lower end of the rectus is retracted. Posterior rectus sheath is opened. External oblique, internal oblique and transversus abdominis muscles are cut along the length of the incision. Transversalis fascia is cut to reach the preperitoneal space. If it is direct sac it is dissected without opening and isolated. Sac is inverted using absorbable purse string suture. If it is an indirect sac, it is dissected proximally high up, opened and ligated. Transaponeurotic arch (transverse abdominis muscle and transversalis fascia) is sutured below to Copper's ligament and iliopubic tract. Nyhus mesh repair is done similarly through this approach by placing mesh and suturing to Cooper's ligament **(Fig. 30-40)**.

Andrew's Operation

It is overlapping of the external oblique aponeurosis.

Condon Procedure

It is anterior iliopubic tract repair by suturing the transversus abdominis to iliopubic tract from pubic tubercle to deep ring; then extending lateral to the cord. In direct sac relaxing incision is made on the lower rectus before tying all placed sutures.

Shouldice Repair

Even though transversalis fascia is thin, it is a tough layer and so double breasting of this fascia using continuous sutures (with non absorbable material) strengthens the posterior wall of the inguinal canal.

It is a multilayered repair. Continuous sutures provide *even distribution of tension* throughout the repair. It was originated at *Shouldice hernia clinic in Toronto* by Shouldice (EE Shouldice 1930) where it was usually done under local anaesthesia. Often cremasteric resection is done in Shouldice in order to have proper revelation of the posterior inguinal wall. Cremasteric vessels (located at lateral part of the cord along with genital branch of genitofemoral nerve) need ligation during cremasterectomy. After doing herniotomy as in any other inguinal hernia, transversalis fascia is incised along the line of the


Interrupted sutures are placed
Knotting the sutures
Knotting the sutures
External oblique aponeurosis
Conjoint tendon
Inguinal ligament
Cord retracted
Complete Bassini (modified) tissue repair
Repair area
External oblique aponeurosis
Conjoint tendon
Inguinal ligament
Cord

Fig. 30-35: Bassini's repair. It is a type of tissue repair.

wound from deep ring to pubic tubercle. Upper medial flap is elevated without elevating lower lateral flap. If there is redundant part of the transversalis fascia it should be excised to leave adequate amount of clean cut edges. Superior pubic vein is located on the deeper surface of the iliopubic tract which should not be injured while operating. Cribriform fascia of thigh is incised deep to the inguinal ligament to free the lateral flap of external oblique aponeurosis and also to visualize femoral opening.

First suture line: Lower lateral flap of fascia is sutured to posterior deep part of the elevated upper flap using continuous sutures from pubic tubercle to internal ring which is tied at deep ring without cutting / ending.

Second suture line: Using same suture which is not cut, free margin of upper flap is sutured to the shelving edge of the inguinal ligament from deep ring towards pubic tubercle. It causes double-breasting of the transversalis fascia. Knot is placed at the end over the pubic tubercle. First and second line sutures are done using a single suture material.

Third suture line: The conjoined tendon and anterior to the shelving part of the inguinal ligament is sutured from internal ring to pubic tubercle continuously and tied without cutting.

Fourth suture line: Same uncut suture is again sutured back continuously between conjoined tendon and anterior fibers of the inguinal ligament to reach internal ring (**Fig. 30-41**).


Internal ring
Conjoint tendon
Inguinal ligament
External oblique aponeurosis
Sutures (interrupted)
Cord
Testes

Fig. 30-36: Modified bassini repair.


Lytle's repair
Cord
Conjoint tendon
Internal ring
External oblique
Testes

Fig. 30-37: Lytle's repair is narrowing the internal ring.


Tanner's slide
Cord
Conjoint tendon
Bassini's repair
External oblique

Fig. 30-38: Tanner slide operation.


Internal ring
External oblique
Conjoint tendon
Cord
Testes

Fig. 30-39: Darning in inguinal hernia.

External oblique aponeurosis is sutured in two layers (5th and 6th suture lines; double-breasting) in front of the cord in original Shouldice repair. Hence this original Shouldice repair is 6 layered procedure.


Incision is horizontal above the level of the deep ring
- Anterior rectus sheath is cut to retract rectus muscle medially
- Posterior rectus sheath is cut
- External and internal oblique and transversus abdomins muscles are cut in the line of incision
- Transversalis fascia is cut to reach preperitoneal space
- Direct sac is only dissected and inverted
- Indirect sac is dissected, opened and ligated
- Illiopubic tract repair is done

Fig. 30-40: Nyhus iliopubic tissue repair. Same plane after similar dissection mesh can be placed.

First two layers of transversalis fascia, next two layers of conjoined tendon and last two layers of external oblique aponeurosis. Suture material used here is 34 gauge fine steel wire (in original Shouldice repair) or polypropylene or polyethylene. Nowadays external oblique is sutured as a single layer. Often it is difficult to close external oblique aponeurosis. Medial part of the cut end of the cremaster is sutured to pubic bone or inguinal ligament to prevent drooping of the testis. Recurrence rate in Shouldice repair is 1 %.

Berliner modified Shouldice repair: It involves double-breasting of the transversalis fascia like in Shouldice repair and single layer closure of the external oblique aponeurosis without any additional two-layered repair of conjoined tendon to inguinal ligament.

Repair of Sliding Hernia

In *LaRoque repair* deep ring is incised above and below; reefing of the sigmoid colon mesentery is done which forms the posterior wall of the inguinal canal so that entire sigmoid is replaced into the peritoneal cavity. Posterior wall of the sac should not be separated from large bowel or bladder. If tried it may lead to faecal or urinary fistulas. Often sac can be excised partially; this partially excised sac can be pushed into peritoneal cavity. Right sided sliding hernia will have caecum and appendix in its posterior wall; caecum should not be separated from posterior wall of the sac which may otherwise create faecal fistula. Appendix should not be removed as it may precipitate sepsis. Appendices epiploicae from sigmoid colon should not be removed as there are chances that they may contain small colonic diverticula which may get opened to contaminate the field. Bladder will be present on medial side of the sac and sac should not be separated; if bladder injury occurs it should be sutured in two layers of vicryl. Inside out purse string suture on the opened sac is applied and the sac with its posterior wall is pushed into the abdominal cavity. Urinary catheterization is a must **(Fig. 30-42)**.



A: Exposing the transversalis fascia properly

B: Incising the transversalis fascia using scissor or cautery from IE vessels to pubic tubercle

C: **First suture line**
Narrow superomedial flap and wider inferolateral flaps are created; only superomedial flap is elevated

D: Deep part of the elevated medial flap is sutured to free edge of inferior flap using continuous polypropylene sutures

E: First suture line is completed from pubic tubercle to deep ring and knot is placed but needle end of the suture is not cut

F: Second suture line is started from same suture material between free edge of the superomedial flap to shelving edge of inguinal ligament as continuous suture form deep ring towards pubic tubercle

G: **Second suture line**
Completed second line of suture by knotting at pubic tubercle

H: Third line of suture begins from deep ring towards pubic tubercle between deeper part of conjoined tendon to inguinal ligament anterior part as continuous suture

I: **Third suture line**
Completed third line of suture by knotting at pubic tubercle but keeping needle end suture long for further 4th line suture to place

J: **Fourth line of suture**
It is done between anterior part of conjoined tendon to further anterior part of the inguinal ligament from pubic tubercle to deep ring

Figs 30-41A to J: Technique of Shouldice repair.



Figs 30-42A and B: Sliding hernia is common in left side; exclusively seen in males. Posterior wall of the sac should not be separated in sliding hernia; if done will injure the colon or urinary bladder. Insertion of urinary catheter is a must prior to surgery. It is usually indirect type; huge hernia which is often irreducible is typical. Posterior wall is formed by sigmoid colon or urinary bladder. Contents are small bowel and omentum.

Hernioplasty (Figs 30-43 and 30-44)

Approach to preperitoneal space

Anterior trans inguinal approach (Anandale)

- Condon approach
- Rive's repair

Posterior approach

- Supra inguinal (Nyhus)
- Grid Iron: (Kugel's)
- Midline: Cheatle-Henry's-Stoppa's GPRVS
- McEvedy's: oblique incision (rectus sheath)
- Laparoscopic: TEP (Dulucq); TAPP (Arrigue/Dion and Morin)

Advantages of preperitoneal approach are: L**ess chance of** damage to nerves and spermatic cord and testicular atrophy. It is most tension free approach. Entire MPO in Bogros space is covered with prosthesis beyond the pubic symphysis (beyond 2.5 cm) and anterior superior iliac spine (2.5 cm). Coverage should be 2/3rd over anterior abdominal wall; 1/3rd beyond and below Cooper's ligament.

Disadvantages are: It involves more extensive dissection of preperitoneal space; requires larger mesh reinforcement; it makes future entry for surgical approach difficult (especially for uro/vascular surgeries). Risk of damage to major vessel (iliac vein), bowel and bladder, extraperitoneal hematoma are high.

Selection for posterior approach: All recurrences after anterior/onlay repairs; all Nyhus type 3 and 4 hernias; incarceration; TEPP to open conversion. It is *avoided* in patients who are unfit for regional anesthesia, bleeding tendency, concurrently with TURP/bladder surgery, known malignancy.

Technical tips and requirements are: Good visibility and retraction, regional/ideally general anesthesia, exact full knowledge of preperitoneal anatomy (both for operating surgeon and camera man/assistant). Larger mesh (15 x 15/15 x 10 cm) is needed; two point fixation to Cooper's ligament.

Complications are: Haematoma (avoid in patients taking aspirin/clopidogrel); seroma—in inguinal/scrotal space—aspiration is done.

Recurrences are due to: Inadequate creation of space, inadequate mesh overlap, mesh migration—(fixation to Cooper's ligament is needed mainly in direct defect).



Fig. 30-43: Giant inguinal hernia. It requires open hernioplasty.

Lichtenstein's Inguinal Hernia Mesh Repair Under Local Anaesthesia

20 mL of xylocaine 2% mixed with 10 mL of bupivacaine 0.5%, 50 mL of normal saline, 1 mL of 1:1000 adrenaline solution with hyalase solution is used for local anaesthesia. Different combinations are in use. 50:50 of xylocaine 1% with 0.5% bupivacaine with 1 in 2,00,000 epinephrine in normal saline is also used. 45-50 mL of this prepared solution is sufficient. Propofol sedation with intravenous drip may be added. Anaesthetic agent is injected layer by layer. 5ml is injected into subdermal plane along the line of incision using 25 G long needle; 3 mL is injected intradermally; 10 – 20 mL is injected deep subcutaneously. After skin and subcutaneous incision, subaponeurotic injection of anaesthetic agent is done (10 mL) first at lateral end of the incision to anaesthetize all three nerves of the inguinal canal; then along the line of the incision up to the pubic tubercle.



Fig. 30-44: Different approaches for preperitoneal inguinal hernia (groin hernia) surgeries.

Procedure

After cleaning and draping, line of skin incision is marked using marking pen at 1.25 cm above and parallel to the medial 2/3rd of inguinal ligament. Using 24G or 26G long spinal needle, prepared anaesthetic agent is injected into the skin underneath along the marked line of incision and in subcutaneous plane below and above. Skin is incised. Using cautery or scalpel blade skin incision is deepened. Two layers of superficial fascia, outer Camper and inner Scarpa's fascia are incised. Often these superficial epigastric, superficial circumflex, superficial external pudendal veins are ligated using fine absorbable sutures (3 zero vicryl/catgut). External oblique aponeurosis is identified by its shining fibers. It is exposed above, below up to inguinal ligament and medially up to pubic tubercle and midline. Around 20 mL of local anaesthetic solution is injected underneath the external oblique aponeurosis medially and laterally. External oblique aponeurosis is incised using no 15 scalpel blade or cautery. Cut edges of the aponeurosis are held with artery forceps. Aponeurosis is incised medially and laterally along the line of the incision. Medially it is extended often up to the external ring to open it. Two leaves of the aponeurosis are elevated above to visualize the conjoined tendon and below to visualize the shining inguinal ligament (Poupart's). Self retaining mastoid retractor can be used to expose the canal clearly. Iliohypogastric nerve is identified above and medially which after piercing the internal oblique enters the external oblique. In the inguinal canal cord is covered by cremasteric muscle and internal spermatic fascia; external spermatic fascia covers the cord below the level of the superficial inguinal ring. Ilioinguinal nerve is in the inguinal canal outside the cord which enters the canal through a gap between external and internal oblique muscles, passes through superficial inguinal ring. Genital branch of genitofemoral nerve passes through the cord structures. Both nerves supply the (L1) anterior 1/3rd



Figs 30-45A and B: Cord holding forceps.



Fig. 30-46: In case of direct sac, always one should dissect the cord and look for indirect sac (pantaloon hernia); otherwise if present and missed recurrence can occur.

of the scrotum and penis. Posterior 2/3rd of the scrotum is supplied by the posterior scrotal nerves and perineal branch of the posterior cutaneous nerve of the thigh (S3). Ilioinguinal nerve is safeguarded after careful dissection. Partial injury or entrapment of this nerve can cause persistent pain in the medial aspect of the thigh and the scrotum. Injury to iliohypogastric nerve causes pain in the inguinal region on medial aspect and in lower abdomen near midline. This *inguinodynia* may be due to entrapment by suture or mesh or due to partial injury of these nerves. Complete transection of the nerve can cause anaesthesia of skin of this region **(Figs 30-45 and 30-46)**.

Cremaster muscle (cremaster box) is opened. Many advocate excision of cremaster to achieve good repair but it causes loss of support to cord and testis causing flapper in bell like problem due to hanging testis. Chances of inguinodynia are increased as the protection to genital nerve and paravasal nerves is removed. Even though it is not proved it is thought that one of the causes of distressing dysejaculation could be due to cremaster dysfunction after cremasterectomy. Medial dissection is done beyond the pubic tubercle. Hernial sac is identified. Sac is pearly white in colour which is anterolateral in position with respect to cord in case of indirect sac. Fundus, body and neck of the sac are dissected using scissor or cautery. Cord is held using hernia ring (Collingwood Stewart) or thin gauze or penrose drain and kept aside (usually below the inguinal ligament). Cord is dissected 2 cm beyond the pubic tubercle. Neck of the sac is identified by its narrow area, being lateral to inferior epigastric vessels and by presence of extraperitoneal pad of fat. Sac is dissected *high up above* the level of the internal ring ***(high dissection***); sac is opened on the summit of the fundus; held with two artery forceps; finger is passed into the sac to confirm that all contents are reduced; if not, by finger dissection adhesions are released and contents are reduced completely; sac is twisted adequately so that no contents will return back to the sac during ligation; sac is transfixed high above the internal ring using 3 zero vicryl or monocryl and ligated. Presently it is thought that high dissection is more important than high ligation; but usually it is common to advocate high ligation of the sac. Redundant sac is excised to complete the herniotomy. There is presently a debate on ligation of sac as ligation of sac increases the chances of postoperative pain due to mechanical pressure, ischaemia and irritation of somatic peritoneal nerve. It is also found that without ligation of indirect sac will not increase the chances of recurrence **(Fig. 30-47)**.

If sac is extending into the scrotum as complete type and if there is difficulty in dissecting such sac from scrotum, then distal part of the sac is left in situ open after transecting at superficial ring level. Important aspect here is distal part of the sac should not be ligated *(Wantz technique*) and if ligated it will lead into hydrocele. In direct hernia, sac is medial to inferior epigastric vessels and is usually not opened unless there is obstruction. Direct sac is pushed underneath. Transversalis fascia is identified and cut along the line of incision obliquely as medial lower and lateral upper flaps. It is common to do plication of this fascia even though it is not mandatory (using continuous non absorbable monofilament polypropylene sutures) **(Figs 30-48 and 30-49)**.

Inguinal canal is exposed well using Langenbeck retractor above and Czerny's retractor below and medially. Cord is kept away below. Polypropylene mesh is used for repair (10 × 6 cm size); size is decided based on the width of the defect; adequate sized mesh covering 2.5 cm above and medially should be used. Often mesh of required size is cut. Mesh is sutured below to the inguinal ligament; medial most suture is taken from a point very close to the pubic tubercle. One should be sure that mesh covers well medial to the pubic tubercle (2 cm beyond). Size of the mesh used is usually 15 × 8 cm. Size should accommodate defect well beyond pubic tubercle (2 cm), superior margin (4 cm) and deep ring (6 cm) laterally. Presently it is thought that light weight large pore combined absorbable and non absorbable mesh is better than only nonabsorbable mesh. As part of the mesh gets absorbed in 120 days; support by mesh well achieved with very less incidence of distressing mesh inguinodynia (due to ilioinguinal and iliohypogastric nerves getting adherent to the mesh). Suturing of mesh is done using interrupted non absorbable monofilament polypropylene or polyethylene sutures below to inguinal ligament. Continuous sutures


Cleaning and draping
Anterior superior iliac spine
Incision above and parallel to inguinal ligament
Pubic tubercle
SC tissue and two layer of superficial fascia (Camper and Scarpa) are incised
External oblique aponeurosis is incised
Edges of the external oblique aponeurosis are held with two haemostats
Edges of the external oblique aponeurosis is cut up to external ring and laterally beyond deep ring level
Ilioinguinal nerve
External oblique aponeurosis
Conjoint tendon
Inguinal ligament below

Figs 30-47(1)


Ilioinguinal nerve
External oblique aponeurosis
Conjoint tendon
Inguinal ligament
Direct sac
Cord
Deep ring
Inf epigastric artery - lateral
Inf epigastric vein - medial
Direct sac
Inguinal ligament
Indirect sac should be looked for by dissecting the cord
Transversalis facia is opened
Sac deep to transversalis fascia is separated and pushed in. Direct sac is not opened
Transversalis fascia
Transversalis fascia is sutured using polypropylene
Preparation of polypropylene mesh for Lstein repair
Taking first medial fixation bite 2 cm from the mesh margin
Placing interrupted sutures between mesh and inguinal ligament
Taking bite from medial part of the inguinal ligament close to pubic tubercle
First knot fixation medially -Mesh should overlap beyond 2 cm of pubic tubercle

Figs 30-47(2)


Placing interrupted sutures between mesh and inguinal ligament
Alternatively - Continuous suture between mesh and inguinal ligament
Lateral cut part of the mesh (upperr 2/3rd and lower 1/3rd) is rounded around cord and ilioinguinal nerve
Mesh is pushed laterally upto anterior superior iliac spine
Leaflets of the mesh encircled around the Cord is sutured to keep it in position
Air lock sutures placed between mesh and conjoint tendon above as interrupted one
One should be careful not to take bites from iliohypogastric nerve
Mesh is often fixed medially also
Suture below onto inguinal ligament
External oblique aponeurosis
Cord
Sutures above to conjoint tendon

Figs 30-47(3)


Closure of external oblique aponeurosis
Interrupted inverting absorbable subcutaneous sutures
Subcuticular absorbable sutures

Figs 30-47(4)

Figs 30-47(1 to 4): Lichtenstein hernioplasty—mesh repair.



Figs 30-48A to C: Direct sac—inguinal hernia.

also can be used while suturing lower flap of mesh to inguinal ligament. Mesh is sutured below to inguinal ligament up to the level of deep ring not beyond (if so femoral nerve may occasionally get injured). It is important to keep needle facing forward to avoid taking inadvertent bite of femoral/iliac vessels (mainly vein) especially in thin individuals. Even though it happens rarely, in such situation without get panicked on seeing the sudden torrential bleed from the site of needle bite, one should gently pull out the suture without allowing further tear of the bitten tissue and sufficient pressure should be applied using a mop to stop the bleeding. Practicing knot tying in such situation would not be correct as tying may further tear the vessel. Occasionally, further exposure of the major vessel may be a needed to control the bleeding using 4 zero vascular continuous suture. Laterally mesh is partially cut horizontally (3 cm upper flap × 2 cm lower flap) so as to enclose the cord and ilioinguinal nerve; lower flap of the cut part is narrower than upper flap. Often few surgeons excise a circular piece of mesh to accommodate cord and remaining tails of the mesh is crossed laterally and sutured. It is important to place lateral tails beyond the incision area (6 cm from deep ring) under the external oblique up to the level of anterior superior iliac spine. Lastly upper end of the mesh is sutured



Fig. 30-49: Distal part of the sac should not be ligated; it is left open probably by giving slit on its wall. If ligated, distal part forms a cavity where fluid may collect forming hydrocele.

to the conjoined tendon in front with loose sutures (*air lock sutures*) just to keep mesh in place. It is often of practice to use absorbable sutures in these upper part so that nerve entrapment in case if occurs (iliohypogastric nerve) will get corrected or may not cause much problem; for same reason only loose sutures are used just to keep mesh in place (air lock). It is also allowed to place continuous sutures below to inguinal ligament. But it is not ideal to place continuous sutures above. Mesh should be sutured with relaxation to bear the forward protrusion pressure of the transversalis fascia during standing. Pressure difference between intraabdominal area and abdominal wall in lying down position is 8 cm of water; which rises to 80 cm in standing position. Mesh placed should bear this pressure change effectively to prevent recurrence of hernia **(Figs 30-50A and C)**.

Cord and ilioinguinal nerve is placed back in the inguinal canal. External oblique is sutured using absorbable vicryl sutures. Subcutaneous interrupted sutures are placed. Skin is closed with continuous subcuticular monocryl 3 zero sutures or monofilament 3 zero interrupted sutures. Waterproof dressing is placed.

Postoperatively patient is asked to take normal diet. Intraoperative intravenous antibiotic is given. Patient is asked to take analgesics and oral antibiotics for 3-5 days.

Procedure can be done as a day care surgery unless the patient is old, with cardiac or respiratory problems. Dressing is changed and wound is observed in 5-7 days. Sutures if non absorbable are removed in 7 days.

Different Types of Hernioplasty

Onlay mesh repair is placing mesh in front: It is sutured above to conjoined tendon and below to inguinal ligament using monofilament non absorbable suture material.

Inlay mesh repair is done by placing mesh deep to conjoined tendon at par with muscular or aponeurotic plane (*bridging)*.

Lichtenstein tension free onlay mesh repair (1984) where the cord is encircled with mesh which is often done under local anaesthesia. Suturing of mesh is done similar to onlay mesh repair. It has got less recurrence rate.

Nyhus preperitoneal mesh repair (sublay)

It is done through *suprainguinal* horizontal incision (*posterior approach)* above the pubic symphysis and internal ring. Preperitoneum is approached through lateral border of the lower part of rectus muscle by making an opening in the posterior rectus sheath. Mesh is placed in the preperitoneal space deep to the cord, conjoined tendon, and transversalis fascia. Below, it is folded deep to the iliopectineal ligament of Cooper and sutured to it using two or three interrupted non-absorbable sutures. It is sutured to transverse abdominis above and transversalis fascia from deep.

Modified Rives preperitoneal mesh repair (Read – Rives - sublay)

It is preperitoneal mesh repair through *transinguinal approach (anterior approach)*. Direct sac is inverted with sutures. For indirect sac a *high dissection and ligation* is done. Here mesh is placed in preperitoneal space, folded and sutured below to iliopectineal ligament, above to the transverse abdominis in deeper plane. Often transversalis fascia opened earlier is sutured back using non-absorbable suture material in front of the placed mesh (**Figs 30-51 and 30-52)**.

Stoppa's (Rene S Stoppa) giant prosthesis reinforcement of visceral sac (GPRVS- sublay)

It is done in large hernias, hernias in elderly, bilateral hernias, recurrent and re-recurrent hernias, hernia with very lax abdomen, obesity and hernia with collagen diseases like Marfan's syndrome. Horizontal length (size) of the mesh is 2 cm less than distance between two anterior superior iliac spines and vertical length (size) is distance between the umbilicus and pubic symphysis (26 × 15 cm). Dacron polyester mesh is better than polypropylene mesh which is supple, lightly adherent but rapidly fixing. Large mesh is placed between peritoneum and lateral, inferior, anterior abdominal wall


Prolene mesh is trimmed
as in the figure and also
two tails are created by cutting
the mesh laterally with 3 cm
upper part and 2 cm lower part
Tail are crossed across the
cord and ilioinguinal nerve to
create a new pseudointernal
ring
A
B
C
Mesh
Internal ring
External oblique
Cord
Testes
Conjoint tendon

Figs 30-50A to C: Lichtenstein mesh repair—polypropylene is used; often mesh is trimmed.


External oblique aponeurosis
External oblique aponeurosis
is incised in the line of incision
External ring
is cut
Ilioinguinal nerve
Careful dissection of the cord structures
Iliopubic
tract
Inguinal
ligament
Cord
Transversalis fascia
Opening of the
transversalis fascia
Reaching the
preperitoneal space
Opening of the
transversalis fascia

Figs 30-51(1)


Preperitoneal space dissection alround using finger and gauze
Identification of inferior epigastric vessels
Space dissection deep to pubic bone and Cooper's ligament
Polypropylene mesh of 15 x 15 cm size
Mesh is held in folding position like an umbrella to push deep into the preperitoneal space
Placing mesh underneath the pubic bone
Pubic bone
Mesh in place
Transversalis fascia
Fixing mesh to Cooper's ligament below using polypropylene suture
Suture knot between mesh and Cooper's ligament
Pubic bone
Cord
Transversalis fascia
Mesh
Mesh fixation

Figs 30-51(2)


Inguinal ligament
Closure of transversalis fascia using polypropylene suture
Closed transversalis fascia

Figs 30-51(3)

Figs 30-51(1 to 3): Rives trans inguinal preperitoneal mesh repair.

which stretches in the lower abdomen and pelvis. It is contraindicated in sepsis, iliac vein thrombosis, when GA or spinal anaesthesia cannot be given to the patient. It is done through lower midline subumbilical incision as a posterior preperitoneal approach across space of Retzius medially and space of Bogros laterally. Procedure is done under GA/spinal/epidural anaesthesia. Local anaesthesia is not used. Patient is placed in supine head down position. Subumbilical midline incision is placed across skin, subcutaneous fascia rectus sheath. Peritoneum is not opened. Space of Retzius in front of the bladder is dissected using finger and peanut swab. Dissection is continued towards *opposite side* of the surgeon first along the space of Bogros. Hernial sac/sacs whether indirect/direct or femoral sac are dissected off from their place. Indirect sac when large can be cut and proximal part is ligated and distal end is left open. Dissection is done further using finger along external iliac vessels, iliopsoas muscle. Funicular elements of sac along the vas deferens and testicular vessels are released so as to make complete parietalisation of the cord. Usual size of the mesh is 26 × 15 cm. Polyester mesh is preferred. Prosthesis mesh is made chevron shaped. It is placed and spread along the myopectineal orifice, on lateral part and towards midline. Mesh should be placed unfolded. Surgeon changes his position by moving on to opposite side to carry on with similar dissection on side where he was standing earlier. Usually such large mesh is placed without any anchorage. Often one vicryl stitch is placed between upper medial end of mesh and lower margin of midline of *umbilical fascia (Richet's*). Suction drains are placed. Mesh envelops the endoabdominal fascia widely preventing the recurrence below at groin or at lower midline wound. Drains are removed in 2 days. *In Rignault's modification*, procedure is done through Pfannensteil incision (nerve injury and bleeding chances are high in this incision). Unilateral half cut GPRVS is called as *Wantz procedure,* done under local anaesthesia. Migration of mesh into the bladder is the only rare but severe complication which may occur.

Gilbert mesh repair (patch and plug)

After herniotomy, internal ring is plugged by cone shaped (umbrella plug) piece of prolene mesh. Later onlay/inlay mesh repair of posterior wall of the inguinal canal is done.

Gilbert's PHS (Prolene Hernia System) repair (onlay and sublay)

It is an open *transinguinal approach* to place a specially devised mesh in both preperitoneal as inlay and in front as onlay mesh repair. This mesh has got a rounded deeper part which is placed in preperitoneal space and a modified quadrangular part which is placed as onlay. Both parts are connected through a connecting stiff rounded part in between which steadies the mesh in place preventing the displacement. Procedure is usually done under local anaesthesia. Direct sac when present is opened. Transversalis fascia over the sac is cut circumferentially and extra part of the fascia is excised. Preperitoneal space is reached using gauze and finger dissection to place the round part of the mesh; lower part of this rounded mesh should be below and deep to the pubic bone to cover entire myopectineal orifice. Outer part is folded perpendicularly using a sponge holding/flat forceps to visualize the inner part and gently pushed into the preperitoneal space using finger. Using index finger it is spread gently in the preperitoneal space. On either side of connector of the mesh, transversalis fascia is sutured using one each polypropylene sutures to fix the connector. Outer quadrangular part is placed in front horizontally. Medially it should cover 2 cm beyond pubic tubercle like onlay mesh repair **(Fig. 30-53)**.

Using polypropylene interrupted suture below it is sutured to inguinal ligament, above to conjoined tendon by one suture, medially to soft tissue adjacent to pubic tubercle. Cord structure with ilioinguinal nerve is passed through the mesh by making a vertical cut on the wide portion of the anterior part of the mesh near its upper margin adjacent to internal ring and once cord is encircled, mesh is secured around the cord by single suture with crossing over the leaves


Pubic tubercle
Anterior superior iliac spine
Inguinal canal is exposed
Inguinal ligament
Lower leaf of external oblique aponeurosis
Conjoint tendon
Cremaster covered over cord
External oblique aponeurosis
Inguinal ligament
Conjoint tendon
Ilioinguinal nerve

Supine position cleaning is done right sided direct hernia

Incision: inguinal - 1.25 cm above the inguinal ligament

Two layers of superifical fascia — outer Camper's and inner Scarpa's are incised

External oblique aponeurosis is exposed

External oblique aponeurosis is incised using blade and later cut using scissor-care should be taken not to injure the ilioinguinal nerve which is very close Cautery can be used but carefully

Dissection in the inguinal canal

Superficial inguinal ring is identified by passing finger underneath and is cut

Dissection of cord is done using scissor or cautery

Figs 30-52(1)


Cord separated is held with finger or cord holding forceps
Direct sac
Cord
Conjoint tendon
Cord is kept aside below the lower leaf of external oblique aponeurosis
Inferior epigastric vein and artery
Dissection of the cord to rule of existence of indirect sac (pantaloon)
Vas deferens
Cord dissection
Opening transversalis fascia
Cord
Preperitoneal space
Direct sac (usually not opened)
Transversalis fascia opened
Cooper's ligament and pubic bone

Figs 30-52(2)


Inferior epigastric vessels
Polypropylene mesh
Mesh is pushed and placed in the preperitoneal space
Mesh in preperitoneal space
Cord
Mesh
Transversalis fascia
Cooper's ligament
Nonabsorbable suture material needle bite between mesh and Cooper's ligament
Mesh is fixed to Cooper's ligament using polyethylene nonabsorbable suture material
Cord
Inguinal ligament
Mesh
Transversalis fascia
Fixation stich to Cooper's ligament
Closure of transversalis fascia using nonabsorbable continuous suture
While closing care should be taken not to take bite along through the ilioinguinal nerve
Cord is kept in place External oblique edges are held

Figs 30-52(3)



Figs 30-52(4)

Figs 30-52(1 to 4): Rives preperitoneal mesh repair—trans inguinal approach.

of the cut part of the mesh. Slit can also be made on the lateral margin to accommodate the cord structure. Connecting cord (connector) or rounded part should not be cut or cord should not be passed through this. In indirect sac preperitoneal space can also be created through posterior wall of the inguinal canal like in direct sac or through the internal ring space is created by blunt dissection by passing index finger. Pulsation of iliac artery can be felt lateral to the index finger. This dissection can be achieved using a sponge held in an instrument or by index finger. Dissection is between preperitoneal space and transversalis fascia. Inferior epigastric vessels are usually left in place between the two lamina of fascia transversalis but can be securely ligated if difficulty arises. Space of 6 cm radius is created all around centering deep ring. Connector is made to remain either on internal ring or on the direct defect of the posterior wall of inguinal canal. Wound is closed in layers. Skin is closed with subcuticular absorbable suture or N butyl cyanacrylate bond. Patient can be discharged within 24 hours. Wound inspection is done in 7 days. Mild discolouration and oedema may last as long as for 6 weeks. Complications are haematoma, swelling, seroma, infection.

Kugel (Rober D Kugel) groin hernia mesh repair (sublay)

It is done through *posterior preperitoneal* approach with tension free less invasive sutureless repair. *Indications* are indirect, direct or femoral hernias; recurrent hernias after anterior approach (onlay); in young individuals. It can be done in bilateral hernias also. It can be done in post radiation patient with hernia or recurrence after TEP or TAPP. Kugel patch contains two overlapping layers of knitted polypropylene mesh which are attached to each other ultrasonically. Near the outer edge of the mesh it has got a polyester spring which stiffens the mesh to unfold. 1 cm of mesh extends outer to the spring which also has radial slits to have easy maneuverability. Anterior layer of the mesh has got single transverse slit to facilitate the insertion. Multiple 3 mm holes through both layers of the mesh are present that allow tissue contact in better way to prevent mesh displacement. Small V shaped triangular cuts on the anterior layer adjacent to these multiple holes act as sutureless anchors. Small 8 × 12 cm and large 11 × 14 cm sizes are available, former is used in indirect sac, latter in direct sac. Incision is above the deep ring and lateral to inferior epigastric vessels. Midpoint of the inguinal ligament is marked. *Oblique incision* line just superior to this point; with 1/3rd lateral and 2/3rd medial to this point is made **(Figs 30-54A and B)**.

Skin, subcutaneous tissue, external oblique aponeurosis is cut; internal oblique and transversus abdominis muscles are split to reach deeper space. Ilioinguinal and iliohypogastric nerves will not come into the field. Transversalis fascia often which is two layered is split vertically to avoid injury to inferior epigastric vessels. Inferior epigastric vessels are retracted medially. Preperitoneal space is created first superiorly then laterally. Indirect sac is dissected off the deep ring from above; if dissection is difficult, sac can be cut with distal part left open and proximal part being ligated using absorbable 3 zero vicryl. Direct sac is dissected off the defect without opening; its pseudosac which is modified transversalis fascia is dissected off entirely from the peritoneum behind. Often it is needed to make a small incision on the pseudosac to prevent seroma formation as this cut allows dissipation of fluid or blood into the tissue in the inguinal canal in front. As approach is small, proper malleable retractors are necessary. Dissection is carried out down under the pubic bone across Cooper's ligament. Care should be taken not to injure vessels at this place either small veins or aberrant obturator artery. Kugel's mesh patch is placed properly without allowing any tissue bands folding it. Transversalis fascia is sutured with one absorbable suture. Transversus abdominis and internal oblique muscles are not sutured. External oblique aponeurosis is sutured; then subcutaneous tissue and skin. Bilateral hernias are dealt with two separate incisions.

Transabdominal preperitoneal mesh repair (TAPP-sublay) using laparoscope (Arregui – 1991)

This is used in large indirect hernia or irreducible inguinal hernia. 10 mm umbilical port is used for laparoscope. 5 mm ports on pararectal point at the or above the level of the umbilicus one on each side are used so as to achieve adequate triangulation. Contents of the hernia are reduced. Hernial sac is dissected in preperitoneal plane after


Part placed in preperitoneal spaceas sublay
Connector
Part placed in front as onlay
PHS extended

Figs 30-53(1)

making curved horizontal incision at the upper part of the opening of sac. Incision over the peritoneum is made from lateral to medial. From a point around 3-4 cm lateral to lateral umbilical ligament (inferior epigastric vessels) horizontal incision is made across internal ring on its upper part medially up to medial umbilical ligament. Preperitoneal space is dissected to identify pubic bone, Cooper's ligament, vas, gonadal vessels, and inferior epigastric vessels. Once sac is dissected and excised, a prolene/vipro/ultrapro mesh of 15 × 10 cm sized is placed in preperitoneal pace. It is fixed to pubic bone/ Cooper's ligament using tacks. Peritoneum is closed with continuous



Figs 30-53(2)

Figs 30-53(1 and 2): Prolene hernia system—surgical technique (PHS).


A
Incision lateral 1/3rd and medial 2/3rd
ASIS
Deep ring
Mid point of the inguinal ligament
Pubic tubercle
Transversalis fascia
Linea sermicircularis
B
Inferior epigastric vessels

Incision is made at a point in the vertical line on mid point of the inguinal ligament just above the level of deep ring as transverse or slight oblique with lateral 1/3rd and medial 2/3rd at this point.

Ext oblique aponeurosis/muscle is cut; internal oblique and transversus abdominis muscles are split; inferior epigastric vessels are retracted medially. Transversalis fascia is cut vertically to reach preperitoneal space. All dissections for approach are above the deep ring

Figs 30-54A and B: Kugel's procedure for inguinal hernia. It is suprainguinal posterior approach.

prolene sutures from lateral to medial. It is mainly used in irreducible and large hernias. Thus reperitonealisation should be done properly. TAPP without reperitonealisation **(TAPPWR)** can be done if dual mesh with ePTFE on inner visceral side can be placed after complete dissection in retroperitoneal space without suturing/apposing the peritoneum. ePTFE prevents viscera from getting adherent and eroded by mesh. Neoperitoneum develops on the ePTFE mesh in 10 days. Complications of TAPP are similar to TEP. Additional problems of bowel injury by trocars, problems of pneumoperitoneum can occur. Advantage of TAPP is larger working space **(Figs 30-55 to 30-58)**.


(TAPP)
10 mm port
-5 mm (TAPP)
-5 mm (TAPP)
-10 mm (TEP)
-5 mm (TEP)
-5 mm (TEP)
A
B

Figs 30-55A and B: Ports used for TEP (red color) and for TAPP (yellow color).


Rectus muscle
Skin
Abdominal muscles (external/internal/transverse)
Preperitoneal space
Transversalis fascia
Peritoneum
Intestines
Normal anatomy of abdominal wall
Rectus muscle
Skin
Abdominal muscles (external/internal/transverse)
Preperitoneal space
Transversalis fascia
Peritoneum
Intestines
Preperitoneal approach (for TEP)
Rectus muscle
Skin
Abdominal muscles (external/internal/transverse)
Preperitoneal space
Transversalis fascia
Peritoneum
Intestines
Transabdominal preperitoneal approach (TAPP)

Fig. 30-56: Diagrammatic representations of TEP and TAPP.



Fig. 30-57: Indirect hernia sac as seen in TAPP.

Totally Extra Peritoneal Repair (TEP Repair) Using Laparoscope (First done by McKernon, EH Phillips and Laws 1990, 1993)

This technique is gaining more popularity than TAPP. It does not breach the peritoneal cavity. It is useful for bilateral and recurrent hernias. It is contraindicated in previous midline surgical scar, previous caesarean, previous pelvic surgery or pelvic radiation.

Patient is ideally *catheterized*. Surgeon should stand opposite to the side of the hernia. Camera man stands on the same side proximal to the surgeon. Scrub nurse stands on the opposite side. Monitor is kept near the foot end side on the side of the hernia. Through sub umbilical vertical/horizontal incision (10 mm) extra peritoneal space is reached. Often special type of balloon is used to create the same. *Cobweb space* is avascular and easily identifiable. It is better to use zero degree telescopes initially to reach the pubic bone. Touching of the telescope over the hard pubic bone can be felt during dissection. Further dissection allows visualization of the bone as *light house sign*. Immediate laterally Cooper's ligament can be identified. After CO_2 insufflation, another 5 mm port is inserted 4 cm below the first port in the midline. It is often better to put a hypodermic needle (needle of a syringe) into the space from midline to identify the site of the further ports. Third 5 mm port is inserted in the same line 4 cm below or in the right iliac fossa. Dissection is carried out downwards carefully, then medially up to the pubic tubercle, ilio-pectineal ligament, laterally to iliac vessels, and inferior epigastric vessels. At this stage 30° telescope is used. Direct sac when present is immediately visualised. It is dissected proximally by traction and countertraction over the white pseudosac (attenuated transversalis fascia) in front. After complete separation many practice to pull this pseudosac proximally to fix it to anterior abdominal wall to prevent the formation of seroma. Entire sac should be dissected down and behind to visualize wide direct defect medial to inferior epigastric vessels. One should remember that inferior epigastric vessels are properly seen only after dissection



Fig. 30-58: Mesh placement in TAPP procedure.


Triangle of pain
Inferolateral margin iliopubic tract
Lateral femoral cutaneous nerve of thigh
Internal ring
Lateral margin peritoneal reflection
EIV
Deep circumflex iliac vessels
EIA
Anterior femoral cutaneous nerve of thigh
Medial margin vas deferens
Femoral branch of genitofemoral nerve
Femoral nerve
Posterior proximal margin Peritoneal reflection
Gonadal branch of genitofemoral nerve
Superomedial margin of triangle of pain Testicular vessels
Lateral margin of triangle of doom, Testicular vessels
Triangle of doom

Fig. 30-59: Triangle of doom and triangle of pain.



Figs 30-60(1)



Figs 30-60(2)



Figs 30-60(3)

Figs 30-60(1 to 3): Technical aspects of TEP

of the sac in case of direct one. Whereas in indirect sac, first inferior epigastric vessels are seen; then peritoneal sac is seen lateral to it running upwards, medially and proximally in the anterior abdominal wall. Hernial sac descends downwards into the internal ring. Sac is dissected from the deep ring. Usually entire sac can be dissected proximally. It is usual to place an endoloop into the sac but not always necessary. Large complete sac is transected at internal ring with placing an endoloop on proximal part of the sac; distal part of cut sac is left open without ligation.

Triangle of doom should be identified and care should be taken while dissecting in this area. Laterally dissection is done up to anterior superior iliac spine adequately along the iliopsoas to create needed space to place large mesh. *Triangle of pain* should be kept in mind as not to injure lateral femoral cutaneous nerve and femoral branch of genitofemoral nerve **(Fig. 30-59)**.

One should avoid opening peritoneum as it reduces the extraperitoneal space to undertake further part of the procedure. If it happens, then it is better to place a Verres needle into the peritoneal cavity to deflate it and to increase the CO_2 flow rate. If bleeding occurs through injury of inferior epigastric vessels, it is tackled by placing clips or using bipolar cautery. Iliac vessels injury is catastrophic which needs immediate conversion to open procedure for proper vascular repair.

Mesh is passed through 10 mm port using a reducer after removing the telescope. If difficulty arises in passing mesh then port knob is removed and mesh is directly pushed into the space through the port. Once adequate space is dissected 15 × 15 cm sized mesh is placed and spread. Care should be taken not to have any folding in the mesh. Mesh may be sutured to ilio-pectineal ligament. Tackers should not be placed laterally and adjacent to vessels. Displacement of mesh is not common. Other side also can be done together. Deflation of gas is done at the end to keep the mesh in place. Port sites are sutured. 10 mm port site needs deeper vicryl suture **(Fig. 30-60)**.

Different port approaches and port placements are used for TEP

1. *Duluq approach:* Veress needle is passed just above the midline across the linea alba into the *space of Retzius* in preperitoneal area. CO_2 is insufflated into the preperitoneal space at a rate of 1 litre/

minute with needle tip manipulating at various directions to inflate preperitoneal space adequately. Through a vertical subumbilical incision, 10 mm trocar is passed into the space directing obliquely towards the pubis initially, later at 60° angle. Zero degree telescope is passed to visualize the space and for further dissection using telescope along the cobweb areolar tissue. Further 5 mm trocars are passed as usual.

2. *McKernan's method:* Anterior rectus sheath is exposed through infraumbilical 2 cm vertical incision which is incised vertically to expose the rectus muscle; rectus muscle is retracted laterally to reach posterior rectus sheath; through this route Hassan's cannula is passed to proceed with creation of space and further two 5 mm ports below midline are inserted. 12.5 × 7.5 cm mesh with slit for passage of cord is used.
3. *Phillips TEP using initial peritoneoscopy:* After creating pneumoperitoneum through subumbilical 1 cm incision 10 mm trocars and port is passed into the peritoneal cavity. Under laparoscopic vision additional two 10 mm ports are passed on either side after making skin incision into the preperitoneal space without entering the peritoneal cavity along the lateral borders of the both rectus muscles. Laparoscope with the trocars is slowly withdrawn until preperitoneal space is reached where it is advanced into the preperitoneal space to proceed with the further dissection as usual.

Anatomical Considerations

Preperitoneal space is a potential space in front of the peritoneum, behind the transversalis fascia and anterior rectus muscle. Below in front of the urinary bladder, it is called as *space of Retzius* (medially), laterally it is called as *space of Bogros*. Median umbilical fold is formed by urachus in the midline. Medial umbilical ligament is formed by obliterated umbilical arteries, lateral umbilical fold by inferior epigastric vessels. Three fossae are lying in relation to these folds—supravesical and medial fossae are medial to lateral umbilical fold which are sites of direct hernia whereas lateral fossa is lateral to lateral umbilical fold and is site of indirect hernia.

In 1956 *Fruchaud* described his *myopectineal orifice* bounded medially by the lateral border of rectus abdominis, laterally by iliopsoas, superiorly by conjoined tendon and inferiorly by pectin pubis. This area is the site of groin hernia which should be covered by mesh of adequate size to strengthen the defect and to prevent the recurrence. Iliopubic tract is analogue of the inguinal ligament, extends from Cooper's ligament to anterior superior iliac spine which divides endoscopic view of preperitoneal space into *superior compartment* (contains inferior epigastric artery, Hesselbach's triangle, cord structures and is site of inguinal hernia) and *inferior compartment* (contains femoral canal, iliac vessels (vein medially; artery laterally), iliopsoas muscle, genitofemoral nerve, lateral femoral cutaneous nerve). External iliac vessels lie in a triangle formed by gonadal vessels laterally, vas deferens medially and peritoneal reflection inferiorly (*triangle of doom*).

Aberrant obturator artery which is an occasional branch of inferior epigastric artery replacing its pubic branch travels across Cooper's ligament, which during fixation of mesh can cause torrential haemorrhage—*circle of death*. *Triangle of pain* is formed by gonadal vessels medially, iliopubic tract laterally and peritoneal reflection below. Genitofemoral nerve and lateral cutaneous nerve of thigh traverse this triangle. Injury to these nerves either by dissection or by tacks cause post-operative pain. Tacks/staplers should not be placed in this triangle **(Figs 30-61 to 30-66)**.



Fig. 30-61: Circle of death.



Fig. 30-62: Port incisions in TEP.



Fig. 30-63: TEP after dissection prior to placement of mesh. Direct defect, inferior epigastric artery, pubic symphysis and Cooper's ligament are clearly seen.



Fig. 30-64: TEP after dissection showing indirect sac, inferior epigastric vessels, Cooper's ligament.



Fig. 30-65: TEP mesh placement in preperitoneal space.



Fig. 30-66: Seroma in groin is common after TEP which can be aspirated safely.

Indications for TEP	*Contraindications for TEP*
• Recurrent hernia • Bilateral hernia • Indirect/direct/femoral hernia	• Obstructed/strangulated inguinal hernias • Ascites • Bleeding disorders
Landmarks to be identified in TEP	*Principles in TEP*
• Pubic bone midline • Inferior epigastric artery • Cooper's ligament • Iliopubic tract • Cord and vas deferens • Psoas muscle and nerves in relation	• Supine or head-down supine position • Surgeon standing opposite side of hernia • Camera person placed on opposite side of hernia • Monitor at foot end • Catheterize/empty the bladder properly prior to TEP • Adequate wide space creation • Careful dissection of cord and sac • Ligate indirect sac • Mesh should not be fixed laterally • Size of mesh is 15 × 15 cm • Two point fixation—one at pubic bone other at Cooper's ligament by tacks/staplers

Difficulties and complications in TEP repair

Difficulty in dissecting indirect sac. Cord/vas injury
Inadvertent opening of the sac/peritoneum and creation of pneumoperitoneum.
Injuries to major structures like iliac vessels: 0.5-1.0%
Displacement of mesh or erosion into the structures like urinary bladder—rarely may occur.
Nerve injury: lateral cutaneous nerve of thigh and femoral branch of genitofemoral nerve
Formation of seroma/haematoma
Infection
Recurrence
Prolapsed of the mesh into the direct hernial defect

Advantages of TEP repair

Approach is totally extraperitoneal
Small incision
Proper placement of mesh in right space that is preperitoneal space
Peritoneal cavity is intact and not opened

STRANGULATED INGUINAL HERNIA

Irreducibility, obstruction and strangulation are the complications of the inguinal hernia. First irreducibility occurs which leads into obstruction and strangulation **(Figs 30-67 to 30-71)**.

Features of strangulated hernia	*Causes of strangulation*
• Tense, tender, irreducible	• Narrow neck
• No impulse on coughing	• Adhesions
• Shock, toxicity	• Irreducibility
• Features of obstruction when there is enterocele	• Long-time, large hernia with adhesions
• Abdominal distension, vomiting	
• Rebound tenderness	

Patient with strangulated inguinal hernia presents with irreducibility, pain and tenderness, distension of abdomen, vomiting, and toxic features. Initial resuscitation is done with nasogastric aspiration, fluid and electrolyte therapy, antibiotics, urinary catheterization. Erect X ray abdomen may show multiple air fluid levels. *Emergency surgery* is needed under general anaesthesia. Inguinal incision extending into the groin is placed. Incision is deepened to reach the external oblique aponeurosis which is cut across the superficial inguinal ring **(Fig. 30-72)**.

Incision is extended and deepened downwards along the root of the scrotum. Sac is identified and held. One should also hold the contents in the sac so has to prevent contents getting reduced and also toxic fluid spilling into the peritoneal cavity. Sac is opened carefully; all toxic fluid in the sac is sucked out thoroughly. Content, either bowel or omentum is held with Babcock's forceps. Viability of the bowel is checked by its colour, texture, peristalsis, mesenteric pulsation or when in doubt by giving 100% oxygen to the patient or after covering the bowel wall using hot mops. If bowel is not viable resection and anastomosis is done. For this, incision may be adequately extended laterally along the lateral abdominal wall. Closing this wound and separate laparotomy incision is not mandatory. Anastomosis is done using interrupted single layer silk or vicryl sutures. *Strangulated omentum* is not uncommon which is treated by omentectomy. *Drains* are placed into the peritoneal cavity as well as into the inguinal wound **(Fig. 30-73)**.


Irreducible herinia
Incision extends into the scrotum
External oblique aponeurosis is opened
Hernial sac
Vas deferens with cord
Sac is opened
Sac is opened
Omentocele
Omentocele

Figs 30-67(1)


Reducing the content into peritoneal cavity
Sac is excised and sutured - transfixation
Mesh placed
Final closure of the wound

Figs 30-67(2)

Figs 30-67(1 and 2): Large irreducible omentocele in a hernia.



Fig. 30-67(A): Irreducible hernia-typical look.

Inguinal canal is strengthened by *modified Bassini's repair* using interrupted monofilament polypropylene sutures. Prosthetic mesh is not used as field is contaminated. In later period if hernia recurs then prosthetic mesh is used for repair. Biological mesh can be used during the surgery for strangulated hernia **(Fig. 30-74)**.

Problems in strangulated hernia are: sepsis, leak and fistula formation, ileus, wound infection, peritonitis, intraabdominal abscess formation like pelvic or subphrenic, electrolyte imbalance, respiratory complications like pneumonia and ARDS, DIC.

INGUINAL HERNIA IN FEMALES

Commonest groin hernia in females is inguinal hernia. Often it may contain Fallopian tube or ovary. Round ligament is attached to labia. Sac is in close relation with round ligament. Sac is adherent and is often difficult to dissect. It is invariably indirect sac. Direct hernia is rare in females. Surgery is the treatment. Laparoscopic or open approach can be used. Round ligament is excised and inguinal canal is entirely closed. Mesh is placed in preperitoneal plane. That also prevents femoral hernia to develop. Incision and technique are same. Bilateral inguinal hernia can be treated surgically in same sitting **(Fig. 30-75)**.

VENTRAL HERNIA

Any protrusion through abdominal wall with the exception of hernia through the inguinofemoral region is defined as *ventral hernia*. Incisional hernia (80%) and primary defects in abdominal fascia which can cause umbilical hernia, epigastric hernia, paraumbilical hernia or Spigelian hernia are grouped under ventral hernia. *Ventral hernia can be*—reducible, irreducible, obstructed, strangulated, single, multiple small defects (*Swiss cheese hernia*) **(Figs 30-76 to 30-83)**.


Incision for irreducible hernia
Czerney's hernia retractor

Fig. 30-68: Irreducible enterocele.



Fig. 30-69: Forced reduction of inguinal hernia will get reduced with the sac with persistent obstruction and strangulation within the peritoneal cavity.



Fig. 30-70: Gangrenous omentum.



Fig. 30-71: Garry's stricture occurs in long standing obstructed hernia. Stricture develops where bowel developed obstruction at the ring.

Factors responsible for development of incisional hernia

- Vertical incision has got higher chances of incisional hernia than horizontal incision
- Layered closure of the abdomen has got higher chance than single layer
- Continuous closure has got higher chances than interrupted closure
- Using absorbable suture material has got higher chances of hernia than nonabsorbable sutures
- Emergency surgical wound has higher chances than elective surgical wound
- Laparotomy for peritonitis, acute abdomen, and trauma can commonly cause incisional hernia
- Drainage through the main laparotomy wound may precipitate formation of incisional hernia
- Chronic cough, smoking, obstructive uropathy, constipation can precipitate incisional hernia
- Diabetes, old age, malnutrition, malignancy, anaemia, hypoproteinaemia, jaundice, ascites, liver disease, uraemia, steroid therapy, immunosuppressive diseases are other precipitating factors

Type of defects in incisional hernia

- Small defect
- Large and wide defect
- Very large defect
- Massive/diffuse
- Multiple defects

Incisional hernia may be vertical midline above or below the umbilicus; vertical midline including umbilicus; vertical paramedian; transverse above or below the umbilicus; transverse which crosses the midline; oblique above or below the umbilicus or combined.

It may be less than 5 cm defect; between 5-10 cm; more than 10 cm.

Note: Size of the defect is important to decide the type of surgical closure in incisional hernia.

Pre-operative Preparations for Incisional Hernia Surgery

- Reduction in weight and control of obesity; nutrition, control of anaemia; treatment for diabetes, hypertension, cardiac diseases, respiratory problems; treating the precipitating causes; chest X-ray, U/S abdomen to be done. Cessation of smoking, respiratory physiotherapy is important.
- Massive incisional hernia after reduction may cause IVC compression, paralytic ileus and diaphragmatic elevation with respiratory embarrassment (*abdominal compartment syndrome*). It is prevented by prior increasing the capacity of peritoneal cavity by creating pneumoperitoneum using CO_2 so as to increase the intraperitoneal pressure by 12-15 cm of H_2O, daily for 3-6 weeks. Later definitive surgery is done.

Treatment Strategy for Incisional Hernia

It can be non prosthetic tissue repair or prosthetic repair. *Non prosthetic repair has become a surgical legacy*. ***Prosthetic repair is the present standard***.

Non Prosthetic Repair

Non prosthetic repair has got only historical value as recurrence rate is very high (as high as 55%).


Incision
Hernia sac
Content
A
Abdominal wall
Ring blocking the content
Inguinal canal
Inguinal ligament
Thigh
Peritoneum
Gangrenous bowel
Toxic fluid
Sac of hernia
B

Figs 30-72A and B: Incision for strangulated inguinal hernia.


Strangulated hernia
Omentum
Sac
Gangrene bowel
Sac
Gangrene bowel
Viable bowel
Ring
Sac
Gangrene bowel

Fig. 30-73: Strangulated hernia—approach. Note the incision placed for strangulated hernia. Only tissue is done Modified Bassini's. Mesh is not used.


Strangulated segment
Sac
Content
Toxic fluid

Fig. 30-74: Strangulated hernia with 'W' type bowel content (Maydl's hernia). Inner loop gets strangulated.

Cattell's operation: When the defect is less than 3 cm, and if the patient is having adequate abdominal muscle tone, *layer-by-layer anatomical repair* is done using monofilament non-absorbable suture material like *polypropylene/polyethylene,* ideally with interrupted sutures. Sac should be dissected, ligated and excised prior to repair. Peritoneum and posterior rectus sheath is apposed as first layer and anterior rectus sheath as second layer.

Double breasting of the rectus sheath using interrupted nonabsorbable sutures using monofilament suture material. It is overlapping the rectus sheath in two layers with two rows of sutures.

Keel operation is done in large defect. Scar is excised and sac is dissected beyond the margin of the defect. Sac is never opened unless there is obstruction of the content. Sac in inverted using continuous/interrupted inverting nonabsorbable sutures, layer by layer until the defect margins are apposed together which is then again sutured with interrupted sutures. (*Keel is inverted beam of the ship running along its bottom*).



Figs 30-75(1)



Figs 30-75(2)

Figs 30-75(1 and 2): Inguinal hernia repair in female.



Fig. 30-76: Large ventral hernias. It needs proper mesh repair. Causes—Congenital defect, obesity, smoking, chronic cough.



Fig. 30-77: Port placement for laparoscopic ventral hernia repair. Left subcostal point is Palmer point.



Fig. 30-78: Laparoscopic view of ventral hernia with omentum as irreducible content. Content is released and dual or four layered mesh is fixed with tackers or sutures.

Nuttall's operation is done for lower midline incisional hernia. Recti attachments are detached from the pubic bones and are crossed over to fix to opposite pubic bones so as to create a firm abdominal wall support by crossed recti muscles **(Fig. 30-84)**.

Prosthetic Repair of Incisional Hernia

It is the Present Standard

It is now universally accepted that prosthetic repair is gold standard for all incisional hernia. Prosthesis used are polypropylene mesh, e-PTFE, Dacron, dual intraperitoneal mesh, biologic grafts.

Open Mesh Repair of the Incisional Hernia

It is always better and ideal with less chances of recurrence. Adequate sized mesh is placed at different planes onlay/overlay or inlay or retrorectus or preperitoneal. Mesh onlay is placing mesh in front of the defect and muscle layer usually after doing simple repair. It has got high recurrence rate (25%) with wound infection. So it is not practiced commonly. Inlay is bridging the defect using prosthetic mesh by suturing mesh to the surrounding myoaponeurotic defect. Repeated contractions of abdominal wall muscles, mesh shrinkage, separation forces of recti lead into high recurrence rate in this (20%). So again it is not commonly accepted method. *Rive's Stoppa's mesh placement* for incisional hernia is placing mesh between posterior rectus sheath and rectus muscle. It is *sublay retrorectus mesh* placement. Midline or transverse incision is done. If needed panniculectomy incision may also be used. Hernial sac is dissected using fine scissor and cautery. Bowel may be adherent to sac and so care should be taken not to injure the bowel. Usually peritoneal sac is opened; all adhesions are released. Retrorectal plane is entered by incising the posterior rectus sheath; 5 cm area beyond the defect is dissected. Usually it will be within the rectus muscle area; if dissection is needed beyond that then it is done through intermuscular plane between internal oblique and transverse abdominis or through preperitoneal plane up to the plane of psoas major muscle. Dissection is done using blunt, sharp scissor and cautery. Peritoneum, posterior rectus sheath and transversalis fascia are sutured. Polyester or lightweight polypropylene mesh is ideal **(Fig. 30-85)**.

Mesh is fixed using polypropylene interrupted sutures to the abdominal wall muscles in its full thickness. 'U' stitches are placed using Reverdin needle. Sutures are placed on one side of the wound from mesh to abdominal wall; once all sutures are placed on one side of the wound, they are tied. Then mesh is fixed similarly on the other side of the wound. Usually around 10 sutures are needed on one side. Absorbable sutures may be used to reduce the chances of chronic abdominal pain. Sutures keep the mesh in place and prevent bulging of the mesh. Often these sutures are brought out through separate stab incisions in the abdominal wall and knots are tied which are buried in the subcutaneous plane. Deeper blind bites on to the peritoneum should not be taken. Linea alba or anterior rectus sheath should be closed to keep the abdominal contour and function normal and also to prevent infection. Commonly polypropylene mesh is used. Other materials used are polyester, Dacron, polytetrafluroethylene (PTFE) mesh, polyglycolic acid mesh (vicryl mesh) or combined polypropylene and polyglycolic acid mesh (vypro mesh). Suction drain should be placed in front of the mesh and in subcutaneous plane as



Figs 30-79A and B: On table look of ventral hernia sac and its mesh repair (in retrorectus plane).



Fig. 30-80: CT scan finding of the ventral hernia.



Fig. 30-81: Incisional hernia through right subcostal incision scar.



Fig. 30-82: Incisional hernia—large.

well. Subcutaneous tissue and skin are closed with interrupted sutures. When subcutaneous drain is placed, suturing of subcutaneous fat is not done as strangulation/necrosis of fat can occur by suturing. Mesh repair is ideal approach for incisional hernia. Prevention of infection/ haemostasis and drainage are important. Recurrence rate in this type is less than 5% **(Fig. 30-86)**.

Open Intraperitoneal Mesh Repair for Incisional Hernia

It is done whenever peritoneum is not enough to close. Dissection is done similarly. ePTFE mesh is used to place the mesh directly outer to viscera intraperitoneally. Mesh is first fixed to abdominal wall at 12 and 6 O'clock positions to prevent displacement. Continuous mesh fixation suture is placed from 12 o'clock position to 6 o'clock position; later from 6 o'clock to 12 o'clock position. Rectus sheath is sutured in front after placing a suction drain.



Fig. 30-83: Incisional hernia while coughing; while relaxing it is getting reduced showing thin lax skin.



Fig. 30-84: (A) Keel and (B) Nuttall's operation for incisional hernia. It is not used nowadays.

Component Separation Technique with Mesh Placement (Autologenous Repair by Vascularised Innervated Muscle Flaps) (Ramirez, 1990)

It is release of the external oblique aponeurosis and separation of the lateral abdominal wall muscles to achieve advancement of the abdominal wall to cause medialisation of the rectus muscle up to 10 cm to achieve reformation of dynamic abdominal wall with midline linea alba closure. Originally it was designed as a nonprosthetic repair but eventually it became popular with additional mesh placement in retrorectus or intraperitoneal area. Vertical incision is made along the hernial sac usually in midline. Sac is identified, dissected, opened and ligated. Flap in front of anterior rectus sheath is raised to identify the external oblique aponeurosis 2-5 cm lateral to the lateral margin of the rectus sheath. Longitudinal incision is made in the external oblique aponeurosis below and beyond the hernial defect usually up to the inguinal ligament; above up to 5 cm above the costal margin. External oblique muscle is then dissected off from the internal oblique in an avascular plane between these two muscles up to posterior axillary line to medialise the rectus muscle along its full length. Additional 4 cm of medialisation can be achieved if needed by incising the posterior rectus sheath longitudinally on its medial aspect. Large prosthetic mesh is now placed after creating plane in retrorectus area or intraperitoneal dual mesh can also be placed. Biologic graft can be used in infected contaminated area. Drain is placed over the mesh. Linea alba is closed. Multiple drains are placed in subcutaneous plane. By this separation technique rectus is advanced for 5 cm in upper abdomen; 7-10 cm in middle and 3 cm in lower abdomen.

It is often of practice that skin fat is first dissected off the anterior rectus sheath for 5 cm beyond the rectus; incision is made in posterior rectus sheath and muscle is separated from the posterior rectus sheath; lastly aponeurosis is incised to separate external oblique from internal oblique to achieve adequate medialisation to close the defect and linea alba.

Separation of component can also be achieved *endoscopically*. 10 mm incision is made adjacent to the tip of 11th rib. External oblique aponeurosis is identified and incised along the line of incision 1 cm to reach an avascular plane between external oblique aponeurosis and internal oblique muscle. Inguinal hernia balloon dissector is placed, directed towards pubic tubercle and is inflated to create adequate space to place a 10 mm port to achieve up to 12 mm Hg pressure with CO_2 insufflation. One 5 mm port is placed in posterior axillary line through which aponeurosis is cut caudally using scissor or cautery. Another 5 mm port is placed medially through which cranial part of the aponeurosis is cut. *Complications of component separation technique are*—seroma/haematoma formation; lateral bulging of the muscle if internal oblique muscle is cut; mesh related complications; paralytic ileus; wound infection; abdominal wall nerve injury and its consequences. Recurrence rate is less than 5%.

Laparoscopic Mesh Repair for Incisional/ Ventral Hernia (1992—LeBlanch and Booth)

It is placing a mesh under the defect laparoscopically in intraperitoneal plane. The only problem of this underlay placement is chances of adhesion and GI fistula formation but it is found to be safer. Laparoscopic preperitoneal mesh placement is also done for smaller defects. Now dual mesh (PTFE) or four layered mesh are available. Presently only these meshes are recommended for use. Here mesh is placed under the peritoneum deep to the defect after reducing the contents. Mesh is fixed with sutures and tacks. In four layer mesh, deepest 1st layer is absorbable cellulose which allows new peritoneum to creep underneath. 2nd layer is PDS/PTFE mesh 3rd layer is polypropylene mesh last 4th layer is again PDS/PTFE mesh. It is ideal but costly.

Exact defect is marked using skin marking pen after cleaning and draping under general anaesthesia. Catheterization is always better done especially in lower abdominal hernias. After creating pneumoperitoneum ports are placed. Table can be tilted accordingly depending on location of the hernial site. Procedure is done in supine position. Surgeon and cameraman are standing on left side of the patient. Monitor is placed on right side towards leg end. Left Palmar point below the left subcostal margin is used for 10 mm port for 10 mm end or side viewing telescope. 5 mm port with 5 mm telescope can be used if available. Usually open method is used. Hasson cannula is better in this situation. Visiport usage makes creation of this first port site better. Further two 5 mm ports are placed also in the left side along the anterior axillary line. If needed additional port may be used on the opposite side. Hernial contents are reduced with careful dissection.


Ventral hernia
Incision
Hernial sac
Margin of the defect
Dissection should be deeper to rectus muscle
Multiple Swiss cheese defects
Omental content which are adherent is released and omentum is excised
Retrorectal dissection to place mesh as retrorectus sublay
Closure of the peritoneum using vicryl
Retrorectus sublay space ready to place mesh
Polypropylene mesh (PPM)
Mesh placed in retrorectus plane
Mesh is fixed to abdominal wall anteriorly with interrupted sutures often by 'U' stitch
Placing suction drain
Anterior rectus sheath is closed with interrupted sutures
Suction drain is fixed
Compression dressing

Fig. 30-85: Technique of open ventral hernia repair by placing mesh in retrorectus plane.


Incisional hernia
Incision elliptical with scar excision
Excision of adherent omentum and opening of the sac
Creation of retrorectus - sublay plane
Closure of the peritoneum using vicryl
Sublay retrorectus space ready for mesh placement
Polypropylene mesh
Fixation of mesh to abdominal wall on either sides
Polypropylene mesh placement into retrorectus space

Figs 30-86(1)



Figs 30-86(2)

Figs 30-86(1 and 2): Incisional hernia repair and retrorectus mesh placement. This is the standard technique in open repair. Suction drain should be placed always.

Dissection is done either with bipolar cautery or ideally sharp scissor. Adhesiolysis is done by keeping scissor close to abdominal wall to reduce the chances of bowel perforation. Entire abdominal contents are inspected. Hernial defect is assessed by placing a flexible ruler intraabdominally through a port under standard insufflation pressure of 12 mm Hg. Dual or four layer mesh with nonadhesive surface facing towards abdominal contents is placed. It is folded carefully and passed inside through 10 mm port. All four corners are sutured using transfascial fixation sutures. It is fixed properly using tackers (helical tacks) or sutures. It is better to place sutures using specialized needle or by intracorporeal suturing and knotting technique. Helical tacks are placed all round at every 5 mm gap. Patient is discharged in 24 hours with abdominal binder for 6 weeks advicing not to lift weight for 6 weeks. *Advantages of laparoscopic ventral hernia repair* are—proper visualization of entire abdomen; avoidance of unnecessary dissection; identification of multiple/Swiss cheese defects; less recurrence rate; short hospital stay; less morbid surgery; faster recovery; better in obese patients. *Disadvantages, problems and complications* are—seroma formation (20%), cautery or dissection injury to bowel (5%), costly mesh, need for general anaesthesia, mesh folding, displacement, bowel interposition between mesh and peritoneum if mesh is not properly placed, mesh infection, wound infection, recurrence, port site bleeding, port site hernia, inadvertent fall of tackers into the peritoneal cavity and its possible complications like erosion into major vessels and vital structures, paralytic ileus, retention of urine postoperatively after removal of the catheter, abdominal wall neuralgia due to injury to abdominal wall nerves by sutures or tackers, conversion into open method. Complications are classified as intraoperative, early, late.

Different types of Mesh Repair for Incisional Hernia

- *Rive's Stoppa's method* of placing mesh between posterior rectus sheath and rectus muscle widely—retrorectus approach is better.
- *Under the peritoneum, directly over the content (intraperitoneal):* Now it is accepted but there are chances of adhesions/fistula formation. It is used in laparoscopic repair. Dual mesh/four layered mesh is used.
- *Overlay* mesh placed outer to musculoaponeurotic layer *is not ideal* due to high recurrence rate.
- *Combined inlay and overlay* with two layers of mesh—practiced in few centers.
- *Bridging at myoaponeurotic level outer to peritoneum (inlay):* Adequate sized mesh is placed in the defect level bridging the gap to cover preperitoneum. It is better by principle but still shows high recurrence **(Fig. 30-87)**.

Postoperative Care

Postoperative management is crucial in these patients. Prevention of sepsis, DVT, ileus, mobilisation are important. Heparin should be started to prevent DVT. Early ambulation, fluid and electrolyte management, catheterization, care of drain (drain should be kept until drainage becomes minimal), abdominal binder is used to support abdominal wall during recovery period.

Additional Problems in Large Incisional Hernia

- While reducing the bulky contents like bowel and omentum, inadequate intraabdominal capacity leads to increased intra-abdominal pressure causing IVC compression, mesenteric oedema following stasis of splanchnic bed, paralytic ileus, diaphragmatic elevation and respiratory distress (*abdominal compartment syndrome*), urinary and bowel disturbances. Abdominal capacity can be raised by creating regular pneumoperitoneum over the period of 3-6 weeks.
- Lordosis and back pain may be presenting feature.
- Sac and contents may get adherent to the thin skin over the summit of the hernia leading to skin ulceration and occasionally fistula formation.
- Often might need resection of the adherent bowel segment. In such a situation only biologic grafts may be possible. Otherwise primary tissue has to be done which has got high recurrence rate.


Mesh
Inlay mesh repair
- At the level of the rectus
- Bridging
Retrorectus - Underlay
mesh repair
Onlay/overlay mesh repair
- In front of the rectus sheath
- Not ideal
Underlay mesh repair
In front of transversalis fascia
Linea alba
Skin and
subcutaneous tissue
External oblique
Internal oblique
Tn abdominis
Rectus muscle
Mesh
Transversalis fascia
Peritoneum
Peritoneal cavity
Preperitoneal type of underlay
mesh repair

Fig. 30-87: Different levels where mesh can be placed in ventral/incisional hernia—sublay/retrorectus is ideal anatomical plane.

- Large mesh placement is required.
- Additional lipectomy (panniculectomy) may be done in case of pendulous abdomen.

UMBILICAL HERNIA REPAIR

Anatomy of Umbilical Region

Umbilical ring is a complex structure which is related to linea alba, falciform ligament, obliterated urachus (median umbilical ligament) and umbilical fascia (*Richet's fascia*). It is located at the level of L4 and L5 vertebral disc. It is lower position in infants. It is water shed area for venous and lymphatic drainage—above umbilicus it drains to axillary vein or lymphatics; below to inguinal area. Umbilical skin is supplied by T10 spinal cord. It is the meeting point of four folds of embryonic plate and three systems—GI (vitellointestinal), urinary (urachus), and vascular (umbilical vessels). Umbilical hernia develops due to either absence of umbilical fascia or incomplete closure of umbilical defect. Weakest part in the umbilical cicatrix is upper part where hernia begins **(Figs 30-88A and B)**.

Primary Closure of the Defect

An infraumbilical incision is made encircling its lower half. Sac is dissected circumferentially and is released off from the umbilicus and subcutaneous tissue. Sac is opened; contents are reduced; excess part is excised up to the umbilical ring. Defect is closed with interrupted nonabsorbable polypropylene sutures. Often layer by layer closure of the layers of the peritoneum is also advocated. Anterior rectus sheath can be sutured either horizontally (ideally) or vertically. Umbilicoplasty is done by creating umbilical dimpling. Center of the umbilical flap is inverted by using finger or instrument; from the summit of the inverted umbilical skin absorbable vicryl – 3 zero suture bite is taken which is sutured firmly to the sutured rectus sheath defect. Skin is closed often with a suction drain underneath **(Fig. 30-89)**.

Mayo's Operation

Here horizontally opened rectus sheath is approximated as double breasting with upper flap overlapping lower flap in front. Interrupted



Figs 30-88A and B: Umbilical hernia in a child and in an adult. Both need surgical intervention. In children primary repair or Mayo's repair is done; in adult mesh repair is done placing mesh retrorectus plane.


Defect in the umbilical hernia
Interrupted mattress
sutures
Closure with simple
interrupted sutures

Fig. 30-89: Primary closure of umbilical hernia is done when defect is small. Mayo's repair or mesh repair is better.

nonabsorbable polypropylene 2 zero sutures are used. Suture bite begins from outer surface of upper flap about 2 cm from cut margin; passes deeper to upper flap reaches the outer surface of the lower flap about 1 cm from the cut margin of the lower flap where the horizontal bite of 5-8 mm width is taken; again bite comes out of the outer surface of the lower flap which later pierces upper flap from deeper aspect to outer aspect to complete the suture. Similar sutures are taken at 5 mm distance. All suture ends are held using small haemostats which are tied together after completion of taking all suture bites. Cut margin of the upper flap which is overhanging on to the lower surface of the lower flap is sutured to the lower flap with continuous or interrupted sutures using polypropylene. It is ideal to place a suction drain underneath the main suture line before tying all knots. Skin is closed using interrupted sutures. Pressure dressing is placed. Procedure is also done for paraumbilical hernia. It is '*vest over pant'* autogenous repair **(Fig. 30-90)**.

Sublay Mesh Repair

In a large umbilical hernia with a degenerated skin on its surface it is often difficult to retain the umbilicus. When umbilicus is tried to be saved, infraumbilical incision should extend laterally about 2 cm on each side at 3 and 9 o'clock positions. Sac is dissected similarly. Sac is excised after excision of redundant sac. Presently it is standard to use polypropylene mesh as sublay or in retrorectus position and then rectus sheath is closed. Mesh placement is better to prevent recurrence in large umbilical hernia. Keeping a suction drain is the usual practice. Umbilical dimpling can be created by placing single vicryl/polypropylene interrupted suture under the center of skin flap to sutured rectus defect. Skin is closed ideally with interrupted sutures even though many practice absorbable subcuticular suture **(Fig. 30-91)**.

Umbilectomy

Unhealthy thin skin over the large umbilical hernia is a real problem. It is better to do umbilectomy in these patients (excision of umbilical cicatrix). A horizontal elliptical incision is made to encircle the umbilicus. Undermining of skin should not be done. Incision is deepened up to aponeurosis. Umbilical margin is dissected using cautery or scissor; sac is opened and excised. Often content is adherent to sac. Sac is carefully dissected off the contents. Adherent omentum needs omentectomy. Often defect may require to be widened to replace the content into the peritoneal cavity. It is achieved by incising the defect laterally (horizontally). Falciform ligament attached to umbilicus is ligated and divided to complete the excision of the umbilicus. Sac is closed using vicryl. Preperitoneal space is created deep to rectus muscle. A polypropylene mesh of adequate size is placed in preperitoneal/retrorectus plane. It is sutured at the margin at different places to abdominal wall in front. It should never be sutured to peritoneum posteriorly. Suction drain is placed in front of the mesh. Rectus sheath is closed using interrupted polypropylene sutures. Subcutaneous drain is often helpful. Skin is closed with interrupted sutures **(Fig. 30-92)**.

Open dual PTFE and polypropylene mesh placement: Umbilical hernia is dissected similarly through subumbilical incision. Redundant sac is excised. Peritoneum is not closed. A special composite mesh containing wider PTFE on the inner side with little smaller polypropylene mesh on the outer aspect is used. It has also got two additional straps of the mesh attached to the outer part of the main composite mesh which are used to hold and later to fix into the defect anteriorly. 4.3 cm and 6.4 cm diameter sized meshes are available. Holding straps folded mesh with PTFE part facing the visceral surface is placed intraperitoneally abutting into the peritoneal surface. Care


Defect with upper and lower flaps including the peritoneum
First suture bite 2 cm away from upper flap margin; then into the outer surface of the lower flap as 2nd bite is taken; then from deeper to outside of upper flap
All interrupted such sutures are taken; later knots are placed together
Knots are placed on the surface of upper flap
Edge of upper flap is sutured to the lower part of lower flap
Drain should be placed underneath the first row of sutures

Fig. 30-90: Mayo repair (vest over pant) for umbilical hernia—steps.



(A) Incision for umbilical hernia Infraumbilical semicircle

(B) In large hernia lateral extensions for 2 cm at 3 and 9 O'clock positions are needed.

Incision
Incision
Raised skin flap
Sac
Sac adherent to umbilical skin
Dissecting the sac up to umbilical ring
Sac is opened excised and Sutured
Defect
Dissection of sac from the umbilical skin

Figs 30-91(1)


Mesh is used
to place in
preperitoneal space
Placed mesh
in position
Suction drain is
placed
Rectus sheath is sutured horizontally
with monofilament nonabsorbable sutures
Haemostasis
is achieved
Creation of
umbilical dimpling
Skin suturing
Pressure dressing
Interrupted sutures

Figs 30-91(2)

Figs 30-91(1 and 2): Technique of umbilical hernia repair with sublay mesh placement.


Elliptical incision for umbilectomy
A
B

Figs 30-92A and B: Umbilectomy is needed for large hernia through elliptical incision.

should be taken to avoid interposition of the bowel between mesh and peritoneal surface. Outer polypropylene part of the mesh is fixed to anterior myoaponeurosis 4 cm away from the margin of the defect using 'U' stitch with knot on the outer surface. First at 3 and 9 o'clock positions sutures are placed; then straps are tugged under the defect in front of the round polypropylene part of the mesh and these straps are fixed using similar 'U' stitches at 6 and 12 o'clock positions. Anterior rectus sheath is approximated horizontally using interrupted sutures. Skin is closed with interrupted sutures after absolute haemostasis. This has got excellent results with low recurrence rate.

Laparoscopic umbilical hernia repair: It is similar like any ventral hernia repair through laparoscopy which is done under general anaesthesia.

Complications

infection, haematoma/seroma formation, ileus, recurrence. Recurrence rate with primary repairs is very high—40% if defect is more than 1 cm. So mesh repair is ideal in adult umbilical hernia repair.

EPIGASTRIC HERNIA (FATTY HERNIA OF LINEA ALBA)

It is common (10%); common in males; 20% of epigastric hernias are multiple—Swiss *cheese like*. It occurs usually through a defect in the decussation of the fibres of linea alba, anywhere between xiphoid process and umbilicus. Extraperitoneal fat protrudes through the defect as fatty hernia of the linea alba presenting like a swelling in the upper midline with an impulse on coughing. *It is sacless hernia*. Later protrusion enlarges and drags a pouch of peritoneum, presenting as a *true epigastric hernia*. If the defect is less than 1.5 cm, lateral margin of the defect is formed by only anterior and posterior lamina of the rectus sheath; if the defect is > 1.5 cm, then lateral margin is also formed by rectus muscle. Content of true epigastric hernia is usually omentum, sometimes it may be small bowel. It is common in muscular men; manual labourers **(Figs 30-94 and 30-95)**.

Treatment

Through a vertical incision, sac is dealt with. Defect is closed with nonabsorbable interrupted sutures. Large defect is supported with


PTFE
Two layered inner PTFE and outer polypropylene mesh with two straps outwards
Polypropylene
Mesh is placed intraperitoneally as underlay with PTFE part on the visceral side
Outer part is fixed securely anteriorly to rectus sheath at four corners.
Straps are used initially to hold but later to fix in one direction
A
B

Fig. 30-93A and B: Umbilical hernia repair using open dual PTFE and polypropylene mesh placement.



Fig. 30-94: Epigastric hernia.



Fig. 30-95: Epigastric hernia with Swiss cheese defects.


Hernia with sac
Deep dissection across defect in preperitoneal area ready to place mesh
Linea alba margin (defect)

Fig. 30-95A: Epigastric hernia on table look.

preperitoneal mesh—ideal and better. Complete reconstruction of linea alba is needed from xiphisternum to umbilicus especially in *Swiss cheese* type using different methods like—interrupted primary closure using polypropylene sutures; *modified shoelace technique* is used after removing strip of medial margins of the linea alba; double breasting of the linea alba **(Figs 30-96 and 30-97)**.

FEMORAL HERNIA REPAIR

Surgical Anatomy of Femoral Canal Fig. 30-98 and 30-99

It is the medial most compartment of the femoral sheath which extends from femoral ring above to saphenous opening below. It contains fat, lymphatics, lymph node of Cloquet. It is 1.25 cm long and 1.25 cm wide at the base. Below it is closed by cribriform fascia.

Femoral ring is bounded anteriorly by inguinal ligament and iliopubic tract; posteriorly by ilio pectineal ligament of Cooper, pubic bone and pectineal fascia covering the pectineus muscle; medially by concave, sharp lacunar (Gimbernat's) ligament; laterally by a thin septum separating from femoral vein **(Fig. 30-100 and 30-101).**

Pathology in Femoral Hernia

Through femoral canal, hernial sac descends down vertically up to saphenous opening and then escapes out into the loose areolar tissue to expand out like a ***retort***. Because of its irregular pathway and narrow neck, it is more prone for obstruction and strangulation. During surgery, precaution should be taken about the femoral vein and pubic branch of obturator artery (or abnormal obturator artery) which often may get injured leading to torrential haemorrhage.

Hydrocele of femoral hernia occurs when adherent omentum is the content which secretes fluid into the sac. *Herniation* through a gap in the lacunar ligament (medial) is always strangulated and is called as *Laugier`s femoral hernia.* In congenital dislocation of hip, femoral hernia occurs *behind* the femoral vessels—*Narath`s femoral hernia.* If sac lies under the pectineal fascia, it is called as *Cloquet`s hernia. Strangulation and Richter`s hernia are common in femoral hernia.* Often on medial side, a portion of bladder forms the wall of the femoral hernial sac— *sliding femoral hernia.*

Surgical Approaches Fig. 30-102

Lockwood (London)—Low Operation

Here sac is approached below the inguinal ligament through groin crease incision so that fundus of sac is dissected by direct vision and repair is done from below. Incision is made 1 cm below the inguinal ligament on its medial portion. Skin and subcutaneous tissue is incised to visualize the swelling with sac. Blunt dissection will reveal the margin of the sac. Commonly sac content is irreducible. Sac is opened; fluid invariably present in the sac is collected for culture and sucked out. Bowel/omentum are held using Babcock's forceps. Viability of bowel or omentum is checked by colour, peristalsis, and blood supply. If content is viable, it is pushed into the peritoneal cavity. If reduction of the content is difficult then constriction at femoral ring should be released. It is done by cutting the inguinal ligament in front. One should not cut the lacunar ligament to release the ring while approaching from below as superior invisible part of the lacunar ligament may be closely related to aberrant obturator artery or pubic branch of obturator artery which communicates with pubic branch of inferior epigastric artery. If this artery is cut both


Epigastric hernia
Defect in the alba
Dissecting deep to defect into retrorectus plane
Entering the retrorectus plane
Sac
Omentum as content
Defect
Excising the omentum which is adherent and sac
Defect
Closure of the sac
Defect
Defect
Retrorectus plane
Defect
Mesh
Retrorectus plane

Figs 30-96(1)


Placing the mesh into retrorectus plane
Placing the mesh into retrorectus plane
Mesh in retrorectus plane
Mesh
Defect
Fixation suture to mesh - Mesh should be fixed anteriorly to rectus sheath
Closure of the rectus sheath
Subcutaneous closure
Subcuticular skin

Figs 30-96(2)

Figs 30-96(1 and 2): Epigastric hernia dissection, defect and retrorectus mesh repair.


Incision for
epigastric hernia
A
Hernia with sac
Linea alba
margin (defect)
B

Figs 30-97A and B: Surgical treatment of epigastric hernia and plane of placing the mesh.


Anterior superior iliac spine
Inguinal ligament
F
N
F
A
F
V
Lacunar ligament
Sac
Femoral hernia
Pubic
bone

Fig. 30-98: Femoral hernia – surgical anatomy.


Anterior superior iliac spine
FN
FA
FV
Adductor longus
Lateral cutaneous
nerve of thigh
PT
Profunda
femoris artery
Sartorius

Fig. 30-99: Femoral triangle and its boundaries.



Figs 30-100A and B: Femoral hernia is common in females.


Inguinal hernia
Inguinal hernia
Femoral hernia

Fig. 30-101: Femoral and direct inguinal hernia in a male patient.


Mc'Evedy-high approach
Inguinal ligament
Lotheissen-inguinal approach
6
Lockwood-low approach
4 3 2 1 5
1. Femoral hernia
2. Femoral vein
3. Femoral artery
4. Femoral nerve
5. Lacunar ligament
6. Cooper's ligament

Fig. 30-102: Surgical approaches for femoral hernia repair.


Lacunar ligament
Inguinal ligament
Repair
FN
FA
FV
Cooper's ligament

Fig. 30-103: Repair of femoral hernia.


A
Intestinal lumen
Gangrenous area
B

Figs 30-104A and B: Femoral hernia Richter's type—perforated. Only part of circumference of the bowel is involved (gangrene or ischaemia) in Richter's hernia.

cut ends of the artery will bleed profusely and also medial cut end may retract into obturator fossa which will be difficult to identify for secure ligation. Inguinal ligament is sutured to Cooper's ligament or pectineal fascia using interrupted polypropylene sutures. Femoral vein that is located laterally should be guarded using finger to prevent taking of inadvertent bite. Usually three sutures are sufficient. First all three sutures are placed and then tied together to prevent tearing of the inguinal ligament. One should ensure that constriction of the femoral vein will not occur. J shaped needle if available should be ideal to take suture bites.

If bowel is gangrenous it is better to do resection by formal laparotomy incision. Other option is extending the incision vertically across into the lower abdomen to complete the resection and anastomosis. In uncontaminated hernia mesh plug is placed which is often sutured into the inguinal ligament and Cooper's ligament **(Figs 30-103 and 30-104).**

Mc'Evedy (Manchester) High Operation

An incision is made over the femoral canal extending vertically above the inguinal ligament. Sac is dissected from below, neck from above and repair is done from above. It gives a very good exposure of neck, fundus of sac and repair is also easier. It is done in strangulated femoral hernia.

Lotheissen's (Vienna) Operation

It is through inguinal canal approach (like for inguinal hernia). Transversalis fascia is opened and neck of the sac is identified in the femoral ring. Sac is dissected from above, neck is ligated and repair is done. If release of constriction ring is necessary then cut can be given to lacunar ligament under direct visualization; one should not injure vessels which is (abnormal obturator artery or pubic branch of inferior epigastric artery) in close proximity to it. If difficulty arises then it is better to cut medial most part of the inguinal ligament to release the neck of the sac.

Lotheissen's repair: After herniotomy, conjoined tendon is sutured to ilio-pectineal line (ligament) by interrupted sutures (2 or 3), using nonabsorbable monofilament sutures. Care should be taken to avoid injury to femoral vein, pubic branch of obturator artery, bladder.

A.K.Henry's approach: Repair of bilateral femoral hernia through lower midline abdominal incision with extraperitoneal approach.

Laparoscopic approach: It is similar to inguinal hernia either through TEP or TAPP or with placement of mesh to cover the Fruchaud's myopectineal orifice.



Fig. 30-105: Surgical anatomy of Spigelian hernia.



Fig. 30-106: Spigelian hernia and placing mesh after dissection.

Complications

Bleeding; haematoma, abscess formation.

SPIGELIAN HERNIA

It was first described by Flemish anatomist Adriaan van den Spiegel. It is lateral ventral hernia through *Spigelian fascia* at any point along its line. *Semilunar line of Spiegel* is a line from pubic tubercle to tip of 9th costal cartilage. It marks the lateral margin of the rectus sheath. Semicircular arcuate line (fold) of Douglas is lower end of posterior lamina of rectus sheath below the umbilicus and above the pubis. Spigelian fascia is area between lateral border of the rectus muscle and external and internal oblique and transversus abdominis muscle. Spigelian hernia belt extends from line Monro (interspinous line) for 6 cm above where spigelian hernia is very common **(Figs 30-105 and 30-106).**

Spigelian hernia can occur above (10%) or below (90%) the umbilicus. Below the umbilicus it occurs at the junction of the linea semilunaris and linea semicircularis. In Spigelian hernia, defect is formed by internal oblique and transversus abdominis muscle. External oblique is outer to the hernial sac. A vertical or transverse incision is made. External oblique is cut vertically or transversely. Sac can be visualized deep to it. Ring often requires a release by cutting the rectus muscle medially. Sac is opened; contents are reduced; sac is ligated using 3 zero vicryl. In earlier days, defect containing internal oblique and transversus abdominis was closed with interrupted monofilament polypropylene sutures. Now retrorectus mesh placement is done prior to closing the defect.

BIOMATERIALS USED IN SURGERIES OF HERNIA

There are many biomaterials used in hernia and vascular surgeries. Its efficacy is based on its tissue response.

Response to Prosthetic Material

Inflammatory response occurs in 4 phases. They are: (1) Acute inflammation that occurs within 2-3 days and climaxes after 14 to 21 days. (2) Chronic inflammatory response seals the foreign body. (3) Foreign body reaction with mediators like PDGF, TGF-β, ILGF, EGF recruiting more inflammatory cells, fibroblasts and smooth muscle cells to promote tissue ingrowths. (4) Fibrosis—collagen rich scar tissue forms and builds a three dimensional frame work around and through the mesh.

Prosthesis

Bursting and ultimate effective strength of the prosthetic material depends on: (1) Pore size, (2) Structural configuration and (3) Filament properties—diameter, type of polymer, monofilament or multi-filament.

Classification of pore size - Type I: Pore size >75 μm, e.g. Prolene lighter mesh which allows macrophages, fibroblasts, blood vessels and collagen to adhere significantly to the material thereby increases its tensile strength. Type II: Pore size less than 10 μm, e.g. ePTFE attract more histiocytes than fibroblasts, causes formation of immature, loose granulation tissue around the mesh. Type III: Macroporous material with multifilamentous or microporous component, e.g. PTFE mesh, Dacron mesh, braided polypropylene mesh. Type IV: Submicronic pore size e.g. silastic sheeting.

Maximum tensile strength required to maintain abdominal closure is 16N/cm with normal intra abdominal pressure being 20kPa. Conventional prosthetic materials have greater than 32N/cm e.g. prolene may rupture at 131kPa. So, true failure of prosthesis is rare. Recurrence, usually at suture line is due to weakness of prosthesis-tissue interface. Mesh of small pore size causes rigid nonelastic scar plate in tissue. Mesh of large pore size causes elastic flexible soft scar mesh which is always better.

Earlier in olden days of surgical practice, prosthetic materials made of stainless steel and tantalums were used. Usher in 1958 first used inert strong polyethylene Marlex mesh; but it was difficult to sterilize. In 1962 polypropylene which can be sterilized by autoclave was introduced. Presently meshes made of—polypropylene, polyester and polytetrafluoroethylene (PTFE) with combinations of these as composite mesh are available. All these meshes are designed to bear 4 times more than the bursting pressure of the abdominal wall.

Meshes can be *heavyweight (80 g/m^2), medium weight or lightweight (<30 g/m^2)*. Compliance of abdominal wall (abdominal wall movement) is studied using stereography technique in all these different weight mesh groups to prove that restriction of movement of the abdominal wall is highest in heavyweight mesh and is less with lightweight mesh. Compliance, pain and abdominal wall discomfort depends on the formation of strong scar around the mesh with shrinkage of mesh, stiffness and discomfort. Heavyweight mesh shows shrinkage up to 40%. Lightweight mesh or combination of lightweight mesh with an absorbable component (vypro [LWM with vicryl], ultrapro [LWM with monocryl]) showed less shrinkage. These meshes cannot be placed over viscera directly as it may cause bowel ingrowth into the mesh and fistula formation. Interceed antiadhesive barrier dual mesh is used to place the mesh intraperitoneally. There is theoretical possibility of carcinogenicity of heavyweight mesh which is not identified in humans until now even though it is observed in experimental studies in rats.

Meshes can be: (1) *Nonabsorbable* like polypropylene or polyester or ePTFE; (2) *Absorbable* like polyglactin (vicryl); (3) *Composite* absorbable and nonabsorbable like vypro with polypropylene and vicryl, ultrapro with polypropylene and absorbable poliglecaprone 25 (glycolide + e-caprolactone). ePTFE (1972) is a common material used as vascular graft. It is now used as intraperitoneal prosthesis as visceral ingrowth into the mesh is not seen. Dual Goretex ePTFE mesh is also used. Polyester meshes (mersilene by Ethicon, Dacron by Bard) are commonly used for Rives and Stoppa procedures. Polyester is softer and supple and does not stiffen and harden as much as heavyweight polypropylene. Only absorbable vicryl mesh is used in splenic and renal trauma which has got 0.5 mm pore size with 0.17 mm thickness. It is inert, nonantigenic which supports well for 60 days. It is placed over the organs using sutures. Absorbable mesh cannot be used for hernia repair **(Fig. 30-107)**.

Lightweight mesh was started by professor Schumpelick, Germany to have strength enough to bear the abdominal wall pressure and stress but flexible and elastic to move with abdominal wall and also being thin with less mass to handle easily. Composite absorbable and nonabsorbable mesh is widely used now. *Vypro mesh* contains equal parts of absorbable polyglactin and nonabsorbable polypropylene components. Filaments of both are twisted together and knitted to form vypro mesh to make it more elastic with stretching capacity in all directions. Polyglactin component of the mesh loses its tensile strength gradually by hydrolysis in 70-90 days. Due to large pore size of 5 mm tissue ingrowth is better thus preventing non elastic rigid scar plate formation but to form an *elastic flexible stretchable* (30% stretchable as compared to only 8% stretch of polypropylene mesh) strong biophysical anatomical reinforcement of the defect and abdominal wall with less abdominal wall discomfort. It forms less foreign body mass. It cannot be used in contaminated field. A modified version of vypro mesh with rhombically placed violet polyglactin and polypropylene thread is often used for inguinal hernia repair. Rhomboid part keeps the mesh rigid making intraoperative manipulation easier. Similarly *Ultrapro mesh* contains equal parts of polypropylene and poliglecaprone 25 which like vypro mesh achieves flexible stable scar tissue. It is ideal for tension free repair, TAPP and TEP. Ultrapro mesh contains dyed and undyed parts **(Fig. 30-108)**.



Fig. 30-107: Poylopropylene synthetic mesh.



Fig. 30-108: Light weight mesh used in laparoscopic hernia surgery.

Multilayered mesh has developed to place intraperitoneally to prevent adhesion of bowel/viscera with fistula formation. Sterile multilayered thin flexible mesh contains oxidized regenerated cellulose (ORC) as 1st and innermost layer; polydioxanone (PDS) 2nd deeper layer; soft nonabsorbable polypropylene mesh as 3rd deeper layer; again a layer of PDS as deepest 4th layer. First ORC layer prevents adhesions and peritoneum develops on it in 4 weeks. PDS is nonantigenic and gets absorbed in 6 months. This mesh is easier to handle, unroll, less infective, stays intact, creates flexible scar, and incorporates strongly to tissues and abdominal wall. This mesh is used in intraperitoneal placement in all incisional and ventral hernias either through open or laparoscopic methods. It is contraindicated in contaminated areas. *Dual mesh* of different types with cellulose or ePTFE as inner layer and polypropylene part as outer layer is also available for same use. These meshes should be fixed properly to abdominal wall using sutures at regular intervals of 1 cm to prevent gap between mesh and abdominal wall which may be a site of dangerous visceral interposition. Sutures are ideal although tacks are practiced by many.

Biological meshes are available for use in contaminated fields. Cellular parts of the human or animal (porcine or bovine) tissue are removed to prevent allergic reactions and protein structure is stabilized to act like a collagen implant to scaffold the tissues by allowing natural fibroblast to proliferate. They act as extracellular matrix for ingrowth of new vessels and collagen to create bioscaffolding which controls the bacteria by presence of macrophages and antibiotics when needed in these tissues adequately. Many materials used are—porcine gut submucosa (*surgisis*), cadaver dermis, porcine dermis, bovine pericardium, fetal bovine pericardium. These disappear over the time from the host completely replacing natural collagen tissue.

Surgical technique of placing mesh are: Onlay on the myoaponeurotic fascia (like in Lichtenstein in inguinal hernia; not used in ventral hernia); Inlay is bridging of the myoaponeurotic fascia; Sublay/underlay is either preperitoneal (preferred placement) or intraperitoneal (only dual or similar mesh) placement of the mesh. Mesh should be fixed with permanent sutures preferably of the same material. It should be overlapped for 4-6 cm with normal fascia in order to obtain a solid prosthesis tissue interphase and also taking into account the shrinkage of tissue which occurs eg prolene mesh can shrink up to 40% in the body.

Complications of mesh are: infection, reaction, extrusion, nerve entrapment, abdominal wall discomfort, visceral erosion and fistula formation, inguinodynia in inguinal hernia repair, seroma formation (5% to 16%) may be due potential space, lymphatic disruption, reaction to mesh.

COMPLICATIONS OF HERNIA SURGERY

Complications of hernia surgery are important as often complications may become more problematic than hernia itself. 20 years back where tissue repair was popular recurrence was the most worried complication. Now since recurrence rates have come down due to standard usage of mesh, mesh related complications have become more common than recurrence. Inguinodynia, mesh extrusion, mesh infection, mesh erosion are the worried problems **(Fig. 30-109)**.

• Complications of open hernia surgery • Complications of TEP/TAPP • Complications of other hernia surgery—ventral/femoral	• Early • Delayed • Late • Life threatening

Complications of open hernia surgery	*Complications of TEP/TAPP*
• Infection • Neural: Groin pain; ostetitis pubis • Ischaemic orchitis—due thrombosis of pampiniform venous plexus (0.5%) • Injury to vas • Injury to viscera • Recurrence • Hydrocele formation • Seroma, haematoma • Inguinodynia • Dysejaculation: painful, burning sensation just before/during/after ejaculation due to cremaster dysfunction or vas stricture (0.25%)	• SC emphysema • Pneumothorax, hypercarbia • Vascular • Neural • Visceral • Infection, ileus • Conversion • Recurrence

Immediate	*Late/delayed*
• Vascular: Injury to iliac vessels/IE vessels • Visceral injury—bowel/bladder • Vas injury • Anaesthetic complications	• Seroma/haematoma • Neural complications • Intestinal obstruction • Bowel adhesion/fistula • Testicular atrophy • Mesh related complications • Recurrence

Inguinodynia

It is chronic inguinal pain seen in post hernia surgery patients (30%)—whether tissue or mesh repair. *Causes are*—traction, cautery, transection, entrapment. Even though it can occur in both tissue and mesh repair, it is more observed in mesh repair especially in onlay mesh repair. It is due to entrapment of nerve in the suture or in the mesh itself or nerve gets adherent to the mesh during fibrosis (perineural fibrosis) (*Mesh inguinodynia*). It may be transient or



Fig. 30-109: TEP causing haematoma in the groin which is aspirated.

persistent. Nerves involved are—Iliohypogastric, ilioinguinal, genital branch of genitofemoral nerve, paravasal nerves. *Features are*—Distressing pain in the groin which often radiates to thigh, scrotum and loin. Arch and twist mobility of pelvis reproduce the pain. Bupivacaine injection relieves the pain. Imaging/nerve conduction studies are of no use. Open method has higher (32-38%) incidence of inguinodynia than TAPP/TEP. In open hernia surgery inguinodynia has replaced recurrence as a primary complication. It is distressing discomfort to both patient and surgeon. Incidence is less in posterior or laparoscopic approach.

It is treated with analgesics/nerve block (Injection of steroid, local anaesthetic agents, phenol, and alcohol)/transcutaneous stimulation/cryotherapy/radiofrequency therapy/neurectomy. Neurectomy is done via groin or suprainguinal or laparoscopic or laparotomy approach. Commonly groin approach is used. Ilioinguinal, iliohypogastric and genitofemoral nerves are carefully dissected. Nerve which is causing the problem is transected at a point where it comes out of the internal oblique muscle and proximal end should be ligated, otherwise end neuroma may form to cause recurrence of the pain. This ligated stump is buried in the internal oblique muscle. Just neurolysis may be sufficient but chances of readhesion are higher with recurrence of symptoms. In difficult cases nerve may be transected through laparotomy/laparoscopy approach **(Fig. 30-110)**.

Ischaemic Orchitis

It is due to thrombosis of pampiniform plexus veins in the cord leading to venous congestion and eventual testicular atrophy (0.5%). It is commonly observed while managing the recurrent hernia through anterior approach. In such situation it is advisable to use posterior approach. It can occur in laparoscopic hernia repair also.

Wound Infection

It may be surface infection of skin or subcutaneous tissue. It may be deeper infection involving the mesh. Surface infection is controlled by using specific antibiotics. There is risk of mesh extrusion in deeper infection and may require surgical removal of the mesh. Parenteral antibiotics are needed. Prophylactic antibiotic is given at perioperative period 30 minutes prior to skin incision. Focus of infection especially in the skin should be identified prior to surgery and treated properly **(Fig. 30-111)**.

Recurrence

Recurrence after hernia surgery is reduced significantly in last 15 years. It is different for different procedures. Now overall incidence is 1-3%. Bassini's repair—10%; Shouldice repair—1%; hernioplasty—1 to 3%; other methods—1 to 5%.

Tissue repair has got higher recurrence than prosthetic repair. *Causes* may be—persisting precipitating etiologies, smoking, more tension in the wound, infection, mesh displacement, missed indirect sac, patulous internal ring **(Figs 30-112 to 30-114)**.

Recurrence may be *medial or lateral* recurrence. Medial recurrence is common and is due to the fact that greatest tension in hernia repair occurs adjacent to the pubic tubercle.

Recurrence also often may be classified as *true or false* recurrences. If hernia occurs in inguinal region after inguinal hernia repair it is called as true recurrence. If other groin hernia occurs after inguinal hernia repair like femoral hernia or obturator or other rare types, it is called as false recurrence. But presently hernia is classified grossly as groin hernias and so all recurrences are true recurrences.

Dysejaculation (0.25%)

It is burning or painful sensation just before, during or after ejaculation. It may be due to obstruction to the ejaculate flow caused by stricture in vas deferens or due to cremaster dysfunction.

Hydrocele

Post herniorrhaphy hydrocele occasionally can occur due to lymphatic obstruction. Deep and superficial rings should not be constrictive while suturing.



Fig. 30-110: Ilioinguinal nerve entrapment.



Fig. 30-111: Infection of the hernia surgery wound may increase the chance of recurrence.



Fig. 30.112: Left sided recurrent hernia.



Fig. 30.113: Sac in a recurrent hernia.



Fig. 30.114: Large recurrent hernia.

Haematoma or Seroma Formation

It is common. It often requires needle aspiration. Open evacuation is usually not required unless haematoma is significantly large. Often haematocele can occur. In TEP bleeding can occur from small vessels, inferior epigastric vessels, or port site. It is dealt with bipolar cautery, clipping or ligaseal **(Fig. 30.115)**.

Infection

Minor infection on the subcutaneous tissue subsides with dressing and antibiotics. Deeper infection may cause trouble to the mesh. Infected mesh may get extruded or may form a sinus. Such mesh has to be removed under general anaesthesia. Defect may get fibrosed or later may require a repair **(Figs 30-116 and 30-117)**.

Major Complications

Injury to iliac vessels, inferior epigastric vessels, pubic branch of inferior epigastric artery or abnormal obturator artery can cause severe torrential haemorrhage. It needs surgical exploration and corrective procedures like repair of injured iliac vessel or ligation of inferior epigastric vessels. Bowel or urinary bladder injury can cause fistula formation. Bowel fistula needs proper evaluation with CT fistulogram and later surgical exploration and resection of the involved segment. Injury to urinary bladder causing urinary fistula can be treated by catheterization for 3-6 weeks. Once fistula subsides catheter can be removed safely without any problem later. If fistula persists then bladder exploration and excision of fistula tract with suturing and repair of bladder wall is done. Anaesthetic complications like pneumonia, ARDS can be occasionally life threatening.

GUIDELINES AND RECOMMENDATIONS FOR GROIN HERNIA

References—European Hernia Society guidelines on the treatment of inguinal hernia in adult patients. Hernia 2009 Aug;13(4):343-403.



Fig. 30.115: Port site bleeding is a cumbersome problem in TEP surgery. It should be carefully controlled using bipolar cautery. If inferior epigastric vessel is the cause then it may require clipping after changing one of the 5 mm ports into 10 mm.



Fig. 30-116: Mesh infection forming fistula after laparoscopic ventral hernia repair.



Fig. 30-117: Infection of the mesh after open inguinal hernia surgery.

doi: 10.1007/s10029-009-0529-7. Epub 2009 Jul 28. Danish Hernia Database recommendations for the management of inguinal and femoral hernia in adults - This guideline has been approved by the Danish Surgical Society December 12th, 2010. Dan Med Bull 2011;58:(2):C4243.

Diagnosis

The diagnosis is mainly based on **clinical examination;** ultrasonography, CT or MRI are rarely needed (with some associations/precipitating factors), while herniography is not recommended. In patients with indicative symptoms of hernia, but no detectable hernia, diagnostic laparoscopy may be an option.

Indication

Hernia repair is recommended in the presence of symptoms affecting daily life.

In Male Patients

With minimal or absent symptoms watchful waiting is recommended; with primary unilateral or bilateral groin hernia the preferred method is mesh repair, either at open surgery (Lichtenstein) or laparoscopically, irrespective of age.

In Females

Repair is recommended not only in symptomatic but also in all asymptomatic patients (due to increased risk of strangulation in females). Laparoscopic approach is recommended whether inguinal or femoral; unilateral or bilateral. Risk of recurrence in women is higher when performing an open repair compared with a laparoscopic repair for a primary hernia.

Due to excellent exposure of the myopectineal orifice including the femoral canal during the laparoscopic dissection it is recommended that all women with a groin hernia (inguinal or femoral) should be offered a laparoscopic repair.

In Young Age

Since young age may be a risk factor for chronic pain, after inguinal hernia repair the use of mesh repair in young male patients (e.g. 18-30 years) is controversial but so far data does not support any disadvantages but rather the contrary. The use of a mesh is, therefore, recommended in all adult patients (>18 years) with indication of inguinal hernia repair.

In Recurrent Hernia

In patients with recurrent hernia with a previous open repair laparoscopic repair is preferred. Patients with recurrence after laparoscopic repair should undergo open mesh repair.

Type of Surgery

Compared to the Lichtenstein operation, laparoscopic repair is associated with less acute pain and faster recovery.

Furthermore, available data suggest less chronic long-term pain after laparoscopic repair.

Conventional tension-producing methods like Bassini, McVay or Shouldice are no longer recommended in a routine elective setting.

Use of a plug mesh for an inguinal hernia is not recommended.

Tissue repair is done in strangulated hernia or with sepsis.

TEP and TAPP are equally safe and effective in skilled hands.

In case of severe comorbidity, previous extensive pelvic surgery or radiation therapy it may be advisable to perform the operation as an open procedure.

In Bilateral Groin Hernia

Laparoscopic approach is preferred but different data show different conclusions in comparison to open versus laparoscopic.

Large Inguinoscrotal Hernia

Large inguinoscrotal or incarcerated hernia may preferably be treated by open repair, although international expert centers have shown good results after laparoscopic repair.

In Direct Hernia

Asymptomatic small direct hernias can be left to be watched carefully; large and symptomatic direct hernia should be operated. Laparoscopic or open Lichtenstein repair is used.

Both sides are operated in single sitting in open method.

Design of Mesh Used

Mesh in Open Repair

14 × 7 cm mesh with 2 cm medial overlap—Lichtenstein repair is used; below continuous sutures non absorbable; above always interrupted sutures; folding of the mesh should be avoided; three nerves should be safeguarded.

Mesh in Laparoscopic Repair

Minimum 15 × 10 cm sized mesh should be used; larger hernia defects (direct > 4 cm; indirect > 4 cm)—17 × 12 cm sized mesh may be a need.

Type of Mesh

Recent data suggest that light weight meshes may be followed by less complaint after surgery although the risk of recurrence may be slightly elevated. Slitting the mesh for the passage of cord can be used in open method.

However, it is in general recommended *not to cut a slit* in the mesh in laparoscopic inguinal hernia repair.

Fixation of Mesh

It has been agreed in the database at different national meetings to use nonabsorbable monofilament suture material for mesh fixation.

Fixation in Laparoscopy

Mesh fixation in laparoscopic inguinal hernia repair is controversial.

Current evidence suggests that fixation of the mesh with tacks may be followed by increased risk of acute and chronic pain and recent reports have suggested that laparoscopic repair can be performed without fixation or with glue fixation without increased risk of recurrence.

However, because of the limited amount of data, the recommendation is mesh fixation during laparoscopic repair, and this can be performed by *nonabsorbable tacks*, absorbable tacks or by glue fixation. There is not yet sufficient data to support one method for another.

Anaesthesia in Hernia Surgery

Elective surgery for groin hernia should be performed in an out-patient setting, using cost-effective local anaesthesia for open mesh repair. General anaesthesia can also be used for open.

General anaesthesia is used and recommended for laparoscopic repair.

Note: Spinal anaesthesia is not recommended.

Antibiotic Need in Hernia Surgery

Routine prophylactic antibiotics are not indicated.

In patients with increased risk of infections antibiotics may be indicated, although the evidence for this is lacking.

Antithrombotic Prophylaxis in Groin Hernia Surgery

In open hernia repair

There are no guidelines available for open inguinal hernia repair, and for this operation, routine prophylaxis is not recommended.

In laparoscopic hernia repair

LMWH is recommended if > 2 of following criteria is present—Duration of surgery > 1 hour; History of venous thromboembolism, congestive heart failure; Age >40 years; Previous myocardial infarction, Immobility, HRT, varicose veins, OCP use, multiparity, peripartum; Cancer, Chronic renal failure, Inflammatory bowel disease; Obesity. *Regime*—Single perioperative dose of LMWH.

Hospital Stay

Inguinal hernia surgery as day surgery is as safe and effective as inpatient treatment and more cost effective. This applies for all patients including selected elderly and ASA-III-patients, but may depend on local factors such as social backup etc. It is therefore recommended that inguinal hernia repair is performed in an outpatient setting unless argued otherwise from specific factors.

Convalescence and Restrictions

It depends on post operative pain and operative approach – open/ laparoscopic. There is no evidence supporting prolonged convalescence periods to avoid recurrence, and patients can therefore be active immediately after surgery when pain is not a hindrance.

Treatment of Chronic Pain (3 Months After Repair)

Surgical treatment is recommended only after 12 months. Neurectomy or mesh removal may be the need.

Chapter

31

Surgeries of Penis, Scrotum and Testis

SURGICAL ANATOMY OF PENIS

Penis has got two parts—root and body.

Root of the Penis

Root of the penis is located in superficial perineal pouch containing two crura and one bulb. Each crus is attached to pubic arch and is covered by ischiocavernosus. Bulb is attached to perineal membrane in between crura and is covered by bulbospongiosus. Urethra pierces its deep surface traversing bulbospongiosus. Ischiocavernosus becomes corpus cavernosum (two in number one on each side); bulbospongiosus forms corpus spongiosum **(Fig. 31-1).**

Body of Penis

It is covered by thin dark coloured skin, begins at pubic symphysis; contains two corpora cavernosa which are extensions of ischiocavernosa of both sides from the root and corpus spongiosum which is continuation of the bulbospongiosus located in the median plane. Corpora cavernosa does not reach the end of the penis; each ends under cover of the glans. Tunica albuginea, a strong fibrous cover surrounds the corpora cavernosa of the penis; it has got superficial part which is longitudinal and covers both corpora; deep part which is circular surrounds each corpus separately with a median septum in between. Corpus spongiosum forms glans penis. Projecting margin at the base of glans is called as corona glandis with groove just proximal to it, which is neck of the penis. Dilated portion of the urethra within the root of the glans is called as navicular fossa **(Fig. 31-2)**.


Prepuce
Glans penis
Body of the penis
Corpus spongiosum
Corpus cavernosum
Urethra
Deep artery of the penis
Crus of the penis
Urethra
Root of the penis
Ischiocavenosus
Bulbospongiosus covering the bulb of penis

Fig. 31-1: Parts of the penis—root and body.

Skin over the Penis

Skin over the glans continues as prepuce; it is foreskin which is freely mobile over the glans and has got two layers. On the ventral surface of the glans skin forms a fold called as frenulum. Preputial sac is a potential space between foreskin and glans. Numerous preputial sebaceous glands on the corona glandis and neck secrete smegma sebaceous material which collects in the sac.

Fascia of the Penis

Inner Scarpa's membranous part of the superficial layer of the abdomen continues below over the penis as superficial fascia of penis which contains only areolar tissue and few muscle fibres without any fat (fat is totally absent). This superficial fascia contains superficial


Superficial dorsal vein of penis
Deep dorsal vein of penis
Skin
Dorsal artery of penis
Superfical fascia
Dorsal nerve of the penis
Deep fascia (Buck's fascia)
Tunica albuginea
Corpus cavernosum
Superficial longitudinal part of the tunica albuginea
Deep artery of penis
Deep circular part of the tunica albuginea
Corpus spongiosum
Urethra
Median septum
Artery of the bulb of penis

Fig. 31-2: Coverings and anatomy of penis (cross section).

dorsal vein of the penis. Deep fascia of penis is actual fascia of penis called as Buck's fascia. Buck's fascia covers both cavernosa and spongiosum; it does not extend into the glans. Deep dorsal vein, dorsal arteries, dorsal nerves are deep to Buck's fascia. Only proximally, it is covered with Dartos.

Ligaments of the Penis

Linea alba extends downwards as fundiform ligament of penis which splits to cover the penis. Deep to the fundiform ligament lies the suspensory ligament of penis, which extends from pubic symphysis and blends with deep fascia of the penis.

Arterial Supply of Penis

Internal pudendal artery supplies penis, which is a smaller terminal branch of anterior division of internal iliac artery. It runs downwards in front of the pyriformis, sacral plexus and inferior gluteal artery; pierces the pelvic fascia passing through the greater sciatic foramen below the pyriformis; from the gluteal region it enters the pudendal canal across the ischial spine. It gives three branches to penis. *Artery of the bulb* of penis supplies bulb and proximal half of the corpus spongiosum. *Deep artery of the penis* runs in the corpus cavernosum forming helicine arteries. *Dorsal artery of the penis* runs deep to deep fascia on the dorsum supplying distal part of the corpus spongiosum, glans penis, prepuce and frenulum. Skin and superficial fascia of the skin is supplied by the superficial external pudendal artery, a branch of femoral artery **(Fig. 31-3)**.

Venous Drainage of Penis

Single superficial dorsal vein lies in the superficial fascia; later divides into right and left branches draining into superficial external pudendal vein on each side. Deep dorsal vein is deep to deep fascia runs proximally between pubic symphysis and perineal membrane to drain into the prostatic plexus of veins. Dorsal vein, deep cavernosus vein, vein of the bulb drain to the internal pudendal vein.

Nerve Supply of the Penis

Sensory supply is from dorsal nerve of the penis and ilioinguinal nerve. Motor (to muscles) supply is by perineal branch of the pudendal nerve. Autonomic supply is from pelvic plexus through prostatic plexus (S2,3,4).

Pudendal Canal

It is the fascial tunnel just above the sacrotuberous ligament which travels forward on the lateral wall of the ischiorectal fossa 4 cm above the ischial tuberosity, leading from the lesser sciatic foramen posteriorly to the perineal membrane anteriorly. It contains internal pudendal vessels and pudendal nerve. It is formed by splitting of the fascia lunata with obturator fascia laterally and perineal fascia medially.

Pudendal nerve is derived from ventral divisions of S2, 3, 4 nerve roots leaving the pelvis (between pyriformis and coccygeus) to enter gluteal region medial to internal pudendal vessels and sciatic nerve through the greater sciatic foramen; crosses ischial spine again enters the pelvis through lesser sciatic foramen to run at the lateral wall of the ischiorectal fossa. It is the main nerve of the perineum and external genitalia. Branches—Inferior rectal nerve supplies the external sphincter, levator ani, skin of the anal canal and anus. Anus also gets its nerve supply from perineal branch of 4th sacral nerve, perforating cutaneous branches of the 2nd and 3rd sacral nerves and gluteal branches of posterior cutaneous nerve of the thigh. Perineal branch (larger terminal branch) gives medial and lateral posterior scrotal / labial branches and supplies urogenital diaphragm. Dorsal nerve of the penis or clitoris is purely sensory. It supplies skin of the body of penis and glans or clitoris **(Fig. 31-4)**.

Pudendal nerve block is done by blocking the nerve with local anaesthetic agent where it crosses the ischial spine. Ischial spine is palpated per vaginally. Sensory branches of the perineal skin are also derived from ilio-inguinal nerve, perineal branch of posterior cutaneous nerve of the thigh and genital branch of genitofemoral nerve.

Pudendal artery is branch of internal iliac artery. From its origin it follows same path as the pudendal nerve on its medial side to supply perineum. It gives inferior rectal artery, perineal artery and artery of penis or clitoris. In females it is much smaller.

TREATMENT OF CHORDEE

Chordee due to hypospadias is corrected by staged procedure. In chordee following circumcision, initially stilbestrol 6 mg daily is given.


Artery of the penis
Dorsal nerve of the penis
Dorsal artery of the penis
Perineal membrane
Deep artery of the penis
Urethral artery
Artery of the bulb
Pudendal nerve
Pudendal canal
Internal pudendal vessels
Inferior rectal vessels and nerve
Perineal vessel and nerve
Transverse perineal vessels
Posterior scrotal vessels and nerve

Fig. 31-3: Blood and nerve supply of penis.



Fig. 31-4: Anatomy of pudendal nerve.

Later chordee is corrected surgically by excising fibrous tissue followed by skin grafting. More often they require surgical intervention.

TREATMENT PEYRONIE'S DISEASE (INDURATIO-PENIS PLASTICA)

Some cases resolve spontaneously. Drugs—steroids; vitamin E; potassium aminobenzoate 12 mg/day; tamoxifen 20 mg daily; terfenadine and fexafenadine; colchicine therapy; intralesional injection of verapamil 10 mg once in 2 weeks—12 injections.

Surgery is needed in many cases. Excision and plication to opposite side is done—*Fitzpatrick operation*. Multiple incisions over the fibrous plaque and temporal fascia bridging gives often good success—*Gelhard's operation*. Excision of fibrous plaque and corporotomy is covered with overlay flap like tunica vaginalis flap (*Lockhart's*) / dermal flap (*Devine and Horton's*). Intracorporeal penile prosthesis placement is often needed.

TREATMENT OF CARCINOMA OF PENIS

Sentinel lymph node biopsy: ***Cabana sentinel node*** is located above and medial to the junction of saphenous and femoral vein. It is the first node to get involved in carcinoma penis. So this sentinel lymph node biopsy (SLNB) after isosulphan blue dye injection into the primary is done to decide for the necessity for ilioinguinal block dissection. In operable cases surgery is the prime and initial method of treatment.

In case of carcinoma in situ, T_1 lesion of glans penis or well differentiated tumour in young individual, circumcision and curative radiotherapy to the penis can be given using radioactive tantalum wire implantation (6000 cGy in 7 days) or by wearing radium penile mould continuously or intermittently (6000 cGy in 7 days) or by linear accelerator external beam radiotherapy (6000 cGy in 5 weeks). Involvement of nodes in these patients is less than 10%. Postoperative radiotherapy to inguinal region is often given.

In advanced fixed inguinal nodes palliative external radiotherapy is given. It is to palliate pain, fungation and anticipated erosion into femoral vessels.

Role of radiotherapy in carcinoma penis: Carcinoma in situ; small lesion less than 2 cm; lesion confined to glans; small lesion in young individual; advanced inoperable disease; palliation to inoperable inguinal nodes in groin; postoperative RT.

Staging of carcinoma of penis

Jackson's staging of carcinoma penis:
Stage I – Tumour involving only 90% five-year glans/prepuce/both survival
Stage II – Tumour extending into 70% body of penis
Stage III – Tumour having mobile 50% inguinal nodes
Stage IV – Tumour spreading to 5% adjacent structures/fixed nodes
TNM staging:
T_0 – No primary tumour
Tis – Carcinoma in situ
T_1 – Tumour < 2 cm without deep invasion
T_2 – Tumour between 2-5 cm with minimal deep invasion
T_3 – Tumour > 5 cm with deep invasion/urethral spread
T_4 – Tumour spread to adjacent tissues
N_0 – No nodal spread
N_1 – Mobile regional nodes—unilateral
N_2 – Mobile regional nodes—bilateral
N_3 – Fixed regional nodes
M_0 – No distant spread
M_1 – Distant spread present

Topical 5 FU cream or Nd:YAG laser photoirradiation is useful in carcinoma in situ.

Chemotherapy: 5 FU; methotrexate, bleomycin, cisplatin and vincristine are useful. MBP/VBM combinations are used. Bleomycin is a radiosensitiser and so beneficial if RT is planned later.

Partial Amputation of the Penis

If growth involves the glans or prepuce without extending into the proximal part of shaft of the penis, then *partial amputation of the penis* is done. In olden days if growth is extending to the body then partial amputation was not done; instead total amputation was done. A length of 2.5 cm stump is retained. Clearance of 2 cm from the proximal extended part of the tumor is needed. Advantage is proper streaming of the urine is possible.

Under spinal anaesthesia, in supine position cleaning and draping is done including both groins. Red rubber catheter is passed per urethrally which facilitates the easier identification and dissection of the urethra in the corpus spongiosum. A rubber tourniquet to the base of the penis may be used. Incision is by flap method. Two flaps are used. Dorsal/superior flap is 2.5 cm from the root of the penis; ventral or inferior flap is longer by 1 cm so that urethra is brought out through this flap in its centre and closed wound will come on the end of the dorsal part. Inferior flap is incised through skin, subcutaneous tissue up to the fascial sheath and is initially elevated up to the level of the superior dorsal flap which is more proximal. Incision is deepened through skin and subcutaneous tissue to the fascial sheath of the corpora cavernosa and corpus spongiosum all round along the both flaps. These flaps are elevated using scissor proximally up to the base of the penis to expose the entire corpora cavernosa and corpus spongiosum. Monopolar cautery is better avoided as retained proximal part of the body may undergo necrosis. Corpora cavernosa are divided at the level of the beginning of the superior dorsal flap; as it bleeds profusely (as it is very vascular) proximal corpora cavernosa needs suture transfixation on each side using no. 1 vicryl in cutting needle. Alternatively, a pair of Kocher's clamps can be placed on the each corpus cavernosum and divided distally; transfixation are done deep to the Kocher's clamps which is released after transfixation. Corpus spongiosum with urethra is dissected, isolated carefully (prior passed red rubber catheter facilitates the easier dissection). Red rubber catheter is removed. Urethra with corpus spongiosum is divided 1.5 cm distally. Tourniquet if placed at the root of the penis should be removed now. Site of urethral passage through the ventral inferior flap is marked; stab incision is made; cut end of the urethra is passed through it. Emerged cut end of the urethra is split vertically for 1 cm; each side of the split urethra is sutured not to the edge of the stab wound of the skin but skin just beyond it to facilitate protrusion of the urethral mucosa so as to reduce the chances of stricture formation. Foley's catheter 18 F sized is passed and is kept in situ for 7 days. If stricture develops then regular dilatation of the urethra is needed.



Fig. 31-5A and B



Figs 31-5A to C: Partial amputation of penis with catheter in situ.

Partial amputation of penis with bilateral ilioinguinal lymph node block dissection is called as *Young's operation* **(Figs 31-5A to C)**.

Total Amputation of Penis

If tumour involves the proximal part of the body of penis or if it is anaplastic/poorly differentiated tumour *total amputation of penis* is done with *perineal urethrostomy*. It is done when body of the penis involved and when there is impossible to do partial amputation of the penis. It is done under spinal anaesthesia **(Figs 31-6A and B)**.

Lithotomy – Trendelenburg position is used. Red rubber catheter is passed per urethra or a metal bougie or male metal catheter can also be used for this purpose. Penile growth is covered with a sterile glove and sterile band or tie is used to fix it the body of the penis. A racquet shaped incision is made covering the penis; it begins as a vertical midline from the pubis downwards encircling the root of the penis again joining on the ventral aspect and extending downwards in the midline scrotal raphe and towards the perineum 3 cm in front of the anus. Scrotum is split into two halves; retracted laterally. Anteriorly fundiform and suspensory ligaments of the penis are split. Dorsal vessels are dissected and ligated. With blunt and sharp dissection and also using cautery perineal incision is deepened. Both crura and bulb are exposed; dissected. Bulb is separated from the perineal membrane; crura are detached from the pubic arch. Urethra is dissected from the muscular component of the bulb; red rubber catheter is removed. Urethra is transected 5 cm distal to the perineal membrane through which it passes out. No. 18 Foley's catheter is passed and inflated. Haemostasis is achieved using cautery **(Fig. 31-7)**.



Figs 31-6A and B: Diagram showing total amputation of penis.


Carcinoma penis
Cleaning and draping
Lithotomy position
Red rubber catheter is placed in the urethra for identification and easier dissection of urethra
Growth is covered with sterile glove
Incision for perineal urethrostomy
Identification of the bulbar urethra
Dissection and encircling the urethra
Opening urethra vertically using no 15 blade
Opened bulbar urethra

Figs 31-7(1)



Foley's catheter is passed per urethrally into the bladder

Suturing urethral mucosa to skin using 3 zero vicryl; bite from skin is taken little away from the edge

Dividing bulbospongiosum completely to complete the perineal urethrostomy

Figs 31-7(2)


Racquet incision around the root of penis
Suspensory ligament of penis

Figs 31-7(3)


Clamping the crura using kocher's clamps both sides
Transfixation using thick vicryl using a tough cutting needle
Dividing with cautery
Transected crura of penis
Specimen – distally

Figs 31-7(4)


Drain is placed
Perineal urethrostomy

Figs 31-7(5)



Figs 31-7(6)

Figs 31-7(1 to 6): Technique of total amputation of penis.

Often if detachment of the crura from the pubic arch is difficult then a Kocher's clamp is applied one on each side of the corpora and is transfixed each side using thick no. 1 vicryl with cutting needle. It is impossible to transfix the corpora using round body needle. Drain is placed on the anterior part of the wound. Skin is closed vertically leaving space posteriorly for perineal urethrostomy. Urethral stump is split longitudinally for 5 mm both in front and behind (this prevents stricture formation) and is sutured to the skin little beyond the cut margin of the skin using 3 zero interrupted vicryl sutures.

Alternatively perineal urethrostomy is done first in lithotomy position. Urethra distally is transected. Racquet incision is placed around the root of the penis. And total amputation of the penis is done in same way.

Problems with perineal urethrostomy are scrotal ammoniacal dermatitis and stricture at urethrostomy site. Dermatitis is prevented by asking the patient to urinate in sitting position lifting the scrotum upwards. Stricture needs dilatation. Stricture of the urethra is not uncommon. It needs regular urethral dilatation **(Fig. 31-8)**.

Total scrotectomy with orchidectomy is done along with total amputation of the penis with perineal urethrostomy —*Sir Piersey Gold operation*. This avoids ammoniacal dermatitis and lymphoedema of the scrotum, a sequelae which may occur after inguinal node dissection. It also reduces the sexual desire.

INGUINAL BLOCK DISSECTION – RADICAL GROIN DISSECTION

Principles

It is clearing the inguinal nodes with fat and fascia en bloc from the groin. It is done in carcinoma penis, skin carcinomas of the limb including melanoma and squamous cell carcinoma, carcinoma anal canal or drainage areas like scrotum/vagina etc. Dissection is done between adductor longus, sartorius, base of femoral triangle and inguinal ligament; with clearing fat and fascia 5 cm above the inguinal ligament in front of the external oblique aponeurosis. Long saphenous vein is ligated and divided 10 cm below the saphenofemoral junction. It covers the *Dresslers quadrangle*.

Presence of metastatic inguinal node even though is a more important prognostic factor than tumour grade. Even the 50-55% of patients present with palpable inguinal nodes in carcinoma penis only 50% of these patients will have histologically positive nodes. But 25% of patients without clinically palpable nodes will have positive metastatic nodes. When lymph nodes are involved on one side, contralateral nodes are involved in 50% of cases and iliac nodes are involved in 30% of cases. When lymph nodes are involved and are mobile, *bilateral ilioinguinal nodal dissection* is done. *Primary inguinal block* is doing block dissection within 4 weeks of surgery for primary tumour. *Secondary inguinal block* is doing block dissection after 4 weeks of surgery for primary disease. Only 50% of palpable



Fig. 31-8: Perineal urethrostomy with stricture in the created urethra.

inguinal nodes are involved by metastatic spread. So often a course of antibiotic is given and waited for 6 weeks. Complications of ilioinguinal block dissection are *flap necrosis*, lymphoedema of lower limb, femoral blow out, infection, lymphorrhoea and haemorrhage.

If primary tumour is poorly differentiated (high grade), and if tumour is T2 or above, chances of inguinal nodal spread is more than 50% and so a prophylactic inguinal nodal dissection is done even though nodes are not involved clinically. 5 year survival improves by 50% in these patients by prophylactic lymphadenectomy.

Often, involvement of inguinal nodes may be due to infection. So a trial of antibiotic therapy is given for 6 weeks to reduce the size of the inguinal node.

Removal of iliac nodes (pelvic lymphadenectomy) does not alter the outcome. It is done to confirm the spread, so that further therapy can be planned and prognosis can be predicted.

Elective prophylactic inguinal block is done in high-risk group—invasive carcinoma; T2 and T3 tumours; with vascular invasion. *Therapeutic inguinal block* is done whenever FNAC of node shows positive tumour.

Superficial lymph node block is dissected superficially to fascia lata in N0 disease. It should undergo frozen section biopsy. If nodes are positive, then formal block dissection should be done.
Standard inguinal lymphadenectomy—is classical block dissection.

Modified inguinal block dissection (Catalona): Small incision, limited dissection, preservation of saphenous vein—this reduces the morbidity and lymphoedema of the limb. However, there is not much evidence to confirm its advantages.

Surgical Anatomy of Femoral Region

It is a triangle in front of the upper 1/3rd of thigh immediately below the inguinal ligament; it is bounded laterally by the medial border of the sartorius medially by the medial border of the adductor longus, base is by inguinal ligament apex is below at a point of joining of sartorius and adductor longus. Roof is formed by skin, superficial fascia, superficial inguinal nodes, femoral branch of the genitofemoral nerve, branches of the ilioinguinal nerve, superficial branches of the femoral artery and associated veins, upper part of long saphenous vein, deep fascia, saphenous opening and cribriform fascia. Floor is formed by adductor longus, pectineus, iliacus and psoas major from medial to lateral. *Contents are*—femoral artery and branches (superficial external pudendal, superficial epigastric, superficial circumflex iliac; deep branches are profunda femoris, deep external pudendal and muscular); medial and lateral circumflex branches of the profunda femoris artery; femoral vein and its tributaries (vein is medial and posteromedial to artery); femoral sheath extends 4 cm along the femoral vessels; femoral nerve is lateral to artery in the iliopsoas groove; nerve to pectineus, femoral branch of genitofemoral nerve, lateral cutaneous nerve of thigh and deep inguinal lymph nodes. *Tributaries of the femoral vein are*—great saphenous vein; veins along the profunda, deep external and muscular branches of the femoral artery; medial and lateral circumflex femoral veins; descending genicular vein. Branches at saphenofemoral junction are—lateral and medial circumflex femoral, external pudendal, superficial and deep circumflex iliac, superficial epigastric veins **(Fig. 31-9)**.

Femoral nerve is about 2 cm in length. It divides into anterior and posterior divisions. Anterior division supplies sartorius and gives medial and intermediate cutaneous nerves of the thigh; posterior division supplies rectus femoris, three vasti and gives saphenous nerve branch the only cutaneous one. Nerve also gives articular and vascular branches **(Fig. 31-10)**.

Superficial external pudendal artery pierces the cribriform fascia travelling medially in front of the spermatic cord supplying the external genitalia; superficial external pudendal vein lies below and medial to artery. Superficial epigastric artery pierces the cribriform fascia travels upwards towards umbilicus to supply anterior abdominal wall. Superficial epigastric vein is medial to artery. Superficial circumflex iliac artery pierces the fascia lata lateral to the saphenous opening travelling upwards below the inguinal ligament anastomosis with branches of the deep circumflex iliac, superior gluteal, lateral circumflex femoral arteries at the level of the anterior superior iliac spine. Superficial circumflex iliac vein is below and lateral to the artery.

Dresslers quadrangle—upper border is formed by line joining anterior superior iliac spine and pubic tubercle; laterally line joining anterosuperior iliac spine and a point 20 cm below it; medially pubic tubercle and a point 15 cm below it. Nodal block dissection for carcinoma penis should cover this area adequately **(Fig. 31-11)**.

Deep fascia of thigh is also called as fascia lata; is attached anteriorly to inguinal ligament, laterally to iliac crest, behind through gluteal fascia to sacrum, coccyx and sacrotuberous ligament, medially to the pubis, pubic arch and ischial tuberosity. Below it is attached to bone and knee joint and continues as popliteal fascia posteriorly. Lateral thickened 5 cm wide band like iliotibial tract above splits into superficial lamina which is attached to iliac crest tubercle and deep lamina to capsule of the hip joint. Below it is attached to the anterior part of the lateral condyle of tibia. Tract stabilises the knee joint and has got insertions of gluteus maximus and tensor fascia latae in its upper part.

Saphenous oval opening in the fascia lata is 4 cm below and lateral to pubic tubercle; it is vertically 2.5 cm and transversely 2.0 cm (vertically oval); it is directed down and lateral. Its lateral crescentic sharp margin lies in front of the femoral sheath; its medial margin is deeper and is formed by pectineal fascia.

Funnel shaped femoral sheath encloses upper 4 cm of femoral vessels; its anterior wall is formed by downward extension of transversalis fascia; its posterior wall is formed by the fascia iliaca. Sheath is asymmetrical with vertical lateral wall and oblique medial wall directed below and laterally. Sheath is divided into lateral arterial, intermediate venous and medial lymphatic compartments by two septa. Medial one is called as femoral canal 1.5 × 1.5 cm at base above (femoral ring) and narrow below. Femoral ring is bounded by fascia over pectineus behind, lacunar ligament medially, septum laterally and inguinal ligament in front **(Fig. 31-12)**.

Femoral canal contains lymph node of Cloquet (one of the deep inguinal nodes); femoral hernia can occur through it; abnormal obturator artery arising from the inferior epigastric artery or pubic branch of obturator artery may communicate with the pubic branch of inferior epigastric artery. Any of these may run on the lacunar ligament on the medial wall of the femoral canal injury of which during surgery may cause torrential haemorrhage.

Inguinal Lymph Nodes

Superficial lymph nodes drain from skin and fascia of the lower limb, perineum and trunk below the watershed umbilical line. It is classified as lower vertical; upper lateral and upper medial. Upper medial and lateral group is often called as horizontal group. *Lower vertical group*


Femoral nerve
Femoral artery
Femoral vein
Superficial circumflex iliac artery
Iliopsoas
Pectineus
Iliacus
Psoas tendon
Sartorius
Sartorius
Great saphenous vein
Adductor longus
Superficial epigastric vessels
Femoral branch of genitofemoral nerve
Superficial circumflex iliac vessels
Ilioinguinal nerve
Horizontal group
Vertical group
Superficial inguinal lymph nodes
Saphenous opening
Vas deferens
Great saphenous vein
Lateral cutaneous nerve of thigh
Medial cutaneous nerve of thigh
Intermediate cutaneous nerve of thigh
Superficial external pudendal vessels

Fig. 31-9: Surgical anatomy of femoral triangle—boundaries; floor, relations; contents; inguinal lymph nodes.


Nerve to iliacus
Femoral nerve
Nerve to pectineus
Anterior division
Posterior division
Nerve to rectus femoris
Nerve to sartorius
Nerve to vastus lateralis
Nerve to vastus intermedius
Nerve to vastus medialis
Medial cutaneous nerve of thigh
Intermediate cutaneous nerve of thigh
Saphenous nerve

Fig. 31-10: Anatomy of femoral nerve in the thigh.



Fig. 31-11: Dressler's quadrangle.



Fig. 31-12: Femoral sheath – anatomy.

(4-5) is located along the both sides of the saphenofemoral junction which drain from the lower limb except buttock. 2-3 upper lateral nodes are located below the lateral part of the inguinal ligament draining skin and fascia of lateral thigh, buttock, flank and back below the umbilical line. *2-4 upper medial nodes* are located below and medial part of the inguinal ligament; few nodes lie above the inguinal ligament along the superficial epigastric vessels. They drain the anterior abdominal wall below the umbilical level; perineum with anal canal below the pectinate line, vagina below the hymen, with external genitalia except glans, penile part of the male urethra superolateral angle of the uterus through round ligament. Efferents from superficial nodes drain into the deep inguinal nodes after piercing cribriform fascia; few drain directly into external iliac nodes.

Deep inguinal nodes (4-5) are located medial to the upper part of the femoral vein. They receive afferent from superficial inguinal nodes, popliteal nodes, glans penis/clitoris and deep lymphatics of the lower limb. Efferent from deep nodes reach external iliac nodes. Proximal most deep node is called as *Cloquet/Rosenmuller* node which is located in the femoral canal.

Technique of Inguinal Block Dissection

It is properly called *as inguinofemoral lymphadenectomy*. If pelvic lymphadenectomy is added then it is called as *ilioinguinal lymphadenectomy* (Ilioinguinal block dissection).

Preoperative antibiotics are given (1 hour before surgery); heparin prophylaxis is also recommended.

It is done under spinal anaesthesia. Supine, with hip slightly abducted and knee flexed, position is used. Lower abdomen, groin, entire thigh is prepared and draped.

Different incisions are used—S; two incisions one vertical and one horizontal; two parallel incisions suprainguinal and infrainguinal; vertical L; oblique with elliptical excision (3 cm wide) of skin over the femorals **(Fig. 31-13)**.

Flap is elevated with retaining some amount of fat in the skin otherwise necrosis of skin flap will occur. 5 cm above the inguinal ligament fat and fascia is dissected towards the inguinal ligament. Flap is elevated laterally over the sartorius; medially above over the pubic tubercle to expose the cord structures and external ring; medially and below over the adductor magnus below up to the apex of the femoral triangle. Great saphenous vein is identified at the apex and ligated. Fascia over the sartorius adductor magnus and pectineus can be removed along the specimen. Fascia over the sartorius is incised and swept medially; near the apex once long/great saphenous vein is ligated. Dissection begins from lateral aspect towards medially; all branches of the femoral vessels are ligated, divided or clipped or fulgurated. Bipolar cautery is better otherwise femoral nerve branches may be injured especially motor nerves (if monopolar is used). Scissor dissection offers good mobilisation of the tissues. Femoral sheath covering the femoral vessels is incised to expose the both femoral vein and artery; femoral vein is posteromedial to artery. Care should be taken not to injure the vein. Small direct branches of the vessels are ligated securely after meticulous dissection. Above femoral canal is identified and Cloquet's lymph node is dissected and removed. When saphenofemoral junction is reached, great saphenous vein is again ligated with transfixation. Cloquet node is bridging node between inguinal and pelvic nodes; if on frozen section Cloquet node is positive then pelvic lymphadenectomy is done to clear iliac nodes. All nodes in front of the femoral vessels should be cleared. It


S shaped incision
Two incisions — One parallel and above the inguinal ligament another vertical incision intersecting first one
In the thigh part of the incision elliptical skin piece is excised and skin grafting is done at the end as primary graft
Two parallel incision
L shaped incision

Fig. 31-13: Different incisions which can be used for inguinal block dissection.

is better to place a retractor under the inguinal ligament and remove uppermost lymph nodes of the groin. Distilled water wash is given to the wound. Femoral canal is closed with interrupted nonabsorbable sutures between lacunar ligament and inguinal ligament **(Fig. 31-14)**.

Deep Ilio-obturator (Pelvic) Lymphadenectomy

It is done by extending the groin incision upwards and laterally. Inguinal ligament is divided after placing a flat instrument or finger over the femoral vessels. Skin, superficial fascia and external and internal oblique muscles are incised; transversus abdominis is split. Peritoneum is swept medially towards midline with blunt finger dissection to expose the common iliac vessels and pelvis. Peritoneum should not be opened. Peritoneum with its contents is retracted using broad Deaver retractor. Alternatively self-retaining retractor may be used. Pelvic lymph node dissection begins from common iliac vessels downwards; laterally from genitofemoral nerve towards medially. All nodes along the common iliac vessels are cleared; nodes in front and in between the external iliac vessels (between external iliac artery and vein) should be properly dissected and removed. Dissection in proceeds downwards and medially along the internal iliac vessels (hypogastric vessels) by clearing all nodes. Obturator nerve (thick nerve) is identified in the triangle formed by external and internal iliac vessels. Branches of the internal iliac arteries may be identified. All fat, tissues and lymph nodes are cleared from the endopelvic fascia preserving obturator nerve and important branch vessels from bladder medially, obturator foramen below, up towards the external iliac vessels and inguinal ligament. Haemostasis is achieved by bipolar cautery. Drain may be placed into the pelvis.

Closure

Internal oblique and external oblique muscles are closed using 2 zero vicryl. Femoral canal is closed with interrupted nonabsorbable sutures. Often it is necessary to place a mesh between the groin and retroperitoneum to prevent hernia formation. Lateral attachment of the sartorius in the anterior superior iliac spine is divided and is rotated over the femoral vessels keeping its blood supply intact. Mobilised/transposed sartorius is sutured to inguinal ligament above and adductor magnus muscle medially using interrupted 2 zero vicryl sutures (*Sartorius muscle transposition, its blood supply is segmental*). It covers the femoral vessels and so gives protection to them; also it seals the large defect under the groin thus preventing herniation of the abdominal content. Alternatively, if sartorius is not adequate or is removed for clearance purpose then *rectus abdominis flap or tensor fascia lata flap* will be very useful. Skin grafting may be needed over the possible necrosed area which is excised **(Fig. 31-15)**.

Closed suction drain should be placed until drain fluid becomes less than 50 ml/day; usually in 3 weeks.

Complications of Inguinal Block Dissection

Early Complications

Haemorrhage, infection, flap necrosis—common. Infection is common in the wound. It may be skin infection, cellulitis, abscess formation. Sutures are removed if there is collection inside. Thorough irrigation with normal saline is done. Discharge is sent for culture and sensitivity. Antibiotics and drainage under anaesthesia is often required in such situation. Usually wound will granulate and heal in 6 weeks. Once it granulates well occasionally skin grafting may be required. Postoperative DVT is not uncommon. Venous Doppler will confirm the diagnosis. LMWH should be started immediately. Lymphorrhoea is lymph ooze from the wound; usually occurs in 6 weeks, often persists for long time. It is due to disruption of lymphatic drainage.

Late Complications

Lymphoedema is a distressing complication. It is more common in obesity, old age, after additional adjuvant RT, deeper node clearance and saphenous vein ligation (not proved). Limb elevation, manual massaging, stockings, avoiding injury, prevention of recurrent infection are the therapeutic methods used.

SURGICAL ANATOMY OF SCROTUM

It is a cutaneous bag containing the right and left testis, epididymis and lower part of spermatic cord. It is divided into right and left half by a raphe which is continued in front along the penis and backwards along the perineum towards anus. Left hemiscrotum is lower than right. In cold environment scrotum is contracted, short and corrugated due to contraction of dartos muscle. In warm environment, it is flaccid and elongated due to dartos relaxation.

Layers of the Scrotum (From without Inwards)

1. Skin
2. Dartos muscle
3. External spermatic fascia
4. Cremasteric fascia
5. Internal spermatic fascia

Blood Supply

From external pudendal, deep external pudendal scrotal branches of internal pudendal and cremasteric branch of inferior epigastric arteries.

Nerve Supply

Anterior 1/3rd portion is supplied by (segment L1 of spinal cord) ilioinguinal nerve and genital branch of genitofemoral nerve. Posterior 2/3rd portion is supplied by (S3) posterior scrotal branch of pudendal nerve and perineal branch of posterior cutaneous nerve of thigh. Dartos is supplied by sympathetic nerve.

TREATMENT FOR HYDROCOELE (FIGS 31-16 AND 31-17)

Surgeries

Sub-total excision
Partial excision and eversion (Jabouley's operation)
Evacuation and eversion
Lord's plication
Sharma and Jhawer's technique



Figs 31-14(1)



Figs 31-14(2)



Figs 31-14(3)



Figs 31-14(4)



Figs 31-14(5)


Sartorius rotation to cover femorals
Two suction drains are placed
Skin is sutured
Two suction drains are placed

Figs 31-14(6)

Figs 31-14(1 to 6): Technique of ilioinguinal block dissection done for carcinoma penis. 'S' incision is used here. 5 cm above the inguinal ligament is cleared. Pelvic lymphadenectomy (ileo-obturator/iliac) is also done; sartorius rotation is done; two drains are placed.

Procedure

Under G/A or spinal or local anaesthesia (cord block) , after cleaning and draping, vertical incision of about 6-8 cm in length is made over the scrotum, anteriorly 1 cm lateral to the median raphe. Skin, dartos, external spermatic fascia, internal spermatic fascia are incised. *Bluish hydrocoele sac is identified*, i.e. parietal layer of tunica vaginalis of testis (it is bluish due to congested venous network over the stretched sac). Fluid is evacuated using trocar and cannula. Sac is opened. Monopolar cautery should be used carefully otherwise testicular artery goes for spasm causing testicular atrophy. It is better to use bipolar cautery or fine ligatures for these bleeders **(Fig. 31-18)**.



Fig. 31-15: Split skin graft is often placed on the centre of the wound with excision of the skin over the femoral area around 3 cm with which avoids flap necrosis.


Internal ring
External ring
Vaginal hydrocoele
T
Internal ring
External ring
Congenital hydrocoele
T
Internal ring
External ring
Infantile hydrocoele
T
Internal ring
External ring
Encysted hydrocoele
T
Internal ring
External ring
Bilocular hydrocoele
T
Internal ring
External ring
Hydrocoele of the hernial sac
T

Fig. 31-16: Different types of hydrocoele.



Fig. 31-17: Bluish coloured sac of the large hydrocoele.



Fig. 31-18: Trocar and cannula used to evacuate the hydrocoele fluid.

If the sac is small, thin and contains clear fluid, Lord's plication can be done, i.e. tunica is bunched into a "ruff" by placing series of multiple interrupted chromic catgut/vicryl sutures so as to make the sac to form fibrous tissue (It is relatively avascular and so haematoma will not occur).

Evacuation and eversion of the sac behind the testis also can be done if sac is thin and fluid is not infected. After eversion, everted sac is sutured with chromic catgut/3-0 vicryl by continuous sutures **(Fig. 31-19)**.

If the sac is thick, in large hydrocoele and chylocoele, subtotal excision of the sac is done (as tunica vaginalis is reflected on to the cord structures and epididymis posteriorly, total excision leads to orchidectomy with division of cord). It is also called as *radical cure or hydrocoelectomy*. It is ideal procedure for hydrocoele with least complications and recurrence **(Figs 31-20 and 31-21)**.

Alternatively, the sac is excised partially and then eversion is done and everted edges are sutured together, which is called as *Jabouley's* operation.

After evacuation, the sac with the testis can be placed in a newly created pocket between the fascial layers of the scrotum—*Sharma and Jhawer's technique.*

A drain is placed near the root of the scrotum on the lateral aspect because it becomes the most dependent portion, when scrotal support is given. Scrotal support is given to reduce the scrotal oedema.



Figs 31-19(1)



Figs 31-19(2)



Figs 31-19(3)

Figs 31-19(1 to 3): Technique of evacuation and eversion for hydrocoele surgery.



Fig. 31-20: chylocele.

Routinely, it may not be necessary but in large hydrocoele, infected hydrocoele it is better to keep a drain. Corrugated drain is commonly kept.

Wound is closed in layers, inner dartos with absorbable; outer skin with interrupted nonabsorbable sutures. *Presently* skin with dartos is closed as single layer with interrupted nonabsorbable monofilament sutures. Scrotal support is given to elevate the scrotum so that oedema of the scrotum will reduce and so also pain. Drain is removed in 48 hours **(Fig. 31-22)**.

In bilateral hydrocoeles, each side is dealt separately by two incisions on each hemiscrotum and two drains are kept. In small bilateral hydrocoele through median raphe approach both sides can be treated with evacuation, excision and eversion the sac (*single layer procedure*). However, in bilateral large hydrocoeles median raphe approach is not advisable.

Note

Aspiration must be avoided as much as possible as it is only a temporary measure (recurrence occurs very early) and chances of haematocele, infection are higher.

Encysted hydrocoele of the cord—It is located in the root of the scrotum. It is brilliantly transilluminant; traction test is positive; mimics epididymal cyst. It is treated by excision of the encysted hydrocoele through scrotal approach. Normal tunica vaginalis is also usually opened and everted **(Fig. 31-23)**.

Multiloculated hydrocoele is known to occur. If found each loculi should be opened and their sacs are removed **(Fig. 31-24)**.

Complications of Surgery

Reactionary haemorrhage is common. It causes haematoma formation with swelling, pain, distress. Small haematoma can be left alone, as it will resolve spontaneously. If haematoma is large it is evacuated after re-exploration, bleeders are ligated using vicryl. Wound is closed with a drain.

Infection is not uncommon. It may lead into wound disruption, sinus formation, and orchitis. Suitable antibiotics control this problem.

Pyocele can occur due to severe infection especially in diabetics. It is treated by proper drainage under general anaesthesia with warm saline irrigation and suitable antibiotics. On table Doppler can be used to check the viability of the testis. Orchidectomy can be postponed at a later period if needed during reinspection of the wound and testis under general anaesthesia.

Sinus formation—persistent sinus may be due to suture material reaction, or focus of infection or retaining the thick diseased sac. So, it is always better to excise the sac if it is thick, infected and diseased. Rarely need may arise to re-explore the sinus for complete excision. Specific disease like tuberculosis of the epididymis has to be thought of. Sinus track excised should be sent for histology.

Recurrent hydrocoele is due to retained sac, formation of another sac or loculated sacs if present. It should be treated by resurgery again.

Conditions Where Orchidectomy is Done in Hydrocele

Pyocele with testicular destruction; Clotted haematocele with testicular destruction. Doppler study is a must before doing orchidectomy. Consent has to be taken. Doppler study of the opposite side also should be done. Low orchidectomy is done **(Fig. 31-25)**.

TREATMENT OF HAEMATOCELE

Acute haematocele is treated by incision and drainage under general anaesthesia. Chronic clotted organised haematocele is treated with low orchidectomy **(Fig. 31-26)**.



Figs 31-21(1)



Figs 31-21(2)

Figs 31-21(1 and 2): Radical cure/hydrocoelectomy/subtotal excision of the sac for large hydrocoele.



Fig. 31-22: Scrotal support is used in all scrotal surgeries to reduce oedema and pain.



Fig. 31-23: Encysted hydrocoele of the cord.



Fig. 31-24: Multiloculated hydrocoele.



Fig. 31-25: Pyocoele with nonviable testis is an indication for low orchidectomy.

TREATMENT OF PYOCELE

Antibiotics are started. Under general anaesthesia, scrotum is explored immediately and pus is evacuated. Viability of the testis is checked. On table Doppler study is ideal. If viable, pus is evacuated and sent for culture, wound is loosely closed with a drain or *ideally* left open and at a later date examination is done under anaesthesia to check for viability and secondary suturing is done with a drain if testis is viable. If the testis is not viable, then *orchidectomy* is done (after taking consent). When in doubt, always testis is left in place and observed. Often, testis will show signs of viability. If not, then low orchidectomy is done at a later stage.

VARICOCELE

It is dilatation and tortuosity of the pampiniform plexus of veins and so also the testicular veins. Normally, there will be numerous plexus of veins (pampiniform) in the scrotum, which all join together to form about 4-8 veins in the inguinal canal. Above, in the abdominal cavity, in the posterior abdominal wall all join to form a single testicular vein. On left side, it drains the left renal vein; on the right side it drains the inferior vena cava.

Varicocele is common in *tall, thin young men*. More common on the *left side*, but often can be bilateral **(Fig. 31-27)**.

Commonly, it is idiopathic in origin, may be due to absence or incompetent valve at the junction of left testicular vein and left renal vein causing inefficient drainage of blood. Other reason is, due to perpendicular (right angle) entry of the left testicular vein into the left renal vein. In left sided renal cell carcinoma, tumour proliferates into the left renal vein and blocks the entry of left testicular vein causing varicocele on left side which is *irreducible*. Varicocele causes increased temperature in the scrotum which depresses the spermatogenesis and so causes *infertility* (correctable infertility) **(Fig. 31-28)**.

Types of Varicocele

Primary/idiopathic—95%: No cause is found. There is incompetence of valves of the testicular vein. It is common on left side because left testicular vein joins left renal vein perpendicularly and left side vein is longer and liable to get compressed by loaded sigmoid colon. Left renal vein is often compressed between aorta and SMA.

Secondary—due to specific cause like left-sided renal cell carcinoma with a tumour thrombus in left renal vein causing obstruction to venous



Figs 31-26(1)



Figs 31-26(2)



Figs 31-26(3)



Figs 31-26(4)

Figs 31-26(1 to 4): For chronic haematocele low orchidectomy is done through scrotal approach. Cord is divided between clamps and ligated by transfixation using 1 zero vicryl (absorbable) suture.


IVC
Kidney
Right testicular vein
Left testicular vein
Pampiniform vein
Testis

Fig. 31-27: Anatomy of testicular veins. Left testicular vein joins into left renal vein in perpendicular fashion. Right vein joins IVC directly.



Fig. 31-28: Varicocele—It is common on left side—'*bag of worms*' look. Note the on table look of dilated veins.

flow of left testicular vein. *Subfertility/infertility* are observed even in unilateral varicocele. It is a debate whether it really causes subfertility. Possible causes are: Altered heat exchange mechanism of the scrotum due to varicocele; hyperthermia; inhibition of spermatogenesis; increased blood flow; increased temperature in the testes; increases the metabolic activity using glycogen storage; depletion of glycogen → injury of parenchyma of testes; oligospermia; hypoxia of testes; same cause leads into Leydig cell dysfunction, decreasing testosterone levels. Final effect is maturation arrest and poor spermatogenesis.

Features

Swelling in the root of the scrotum; dragging pain in the groin and scrotum; *"Bag of worms"* feeling; impulse on coughing; on lying down it gets reduced (except in renal cell carcinoma); *Bow sign*: After holding the varicocele between thumb and fingers, patient is asked to bow. Varicocele gets reduced in size. Bowing reduces the blood flow of testicular vein and pampiniform plexus causing reduction in size.

Grading of varicocele—I. Small; II. Moderate; III. Large; IV. Severely tortuous.

Investigations—Venous Doppler of the scrotum and groin; U/S abdomen to look for kidney tumour; Semen analysis.

Treatment

Indications for surgery

Pain; Oligospermia—usually in 6-12 weeks oligospermia improves very well and also the conception rate.

Surgeries

Palomo's operation: Suprainguinal extraperitoneal ligation of testicular vein. Under spinal anaesthesia, above the inguinal canal in the line of anterior superior iliac spine lateral to the rectus muscle, horizontal incision is made; skin superficial fascia, external oblique are incised; internal oblique and transversus abdominis is split to reach extraperitoneal space. Careful blunt dissection identifies the testicular vein which runs upwards towards IVC on right side and towards left renal vein on left side. Testicular vein is dissected using right angle instrument, ligated and divided.

Inguinal approach (Inavissevich approach): Easier and safer. It is same as approaching for inguinal hernia in open method. After opening the external oblique, cord is mobilised and cremaster is opened; pampiniform veins are observed; dilated veins are individually dissected and ligated securely using silk or vicryl. There is no indication to do any repair of the posterior inguinal canal in this procedure.

Subinguinal approach *(Marc-Goldstein)*: It is subinguinal approach at superficial inguinal ring outside the external oblique aponeurosis without opening the external oblique aponeurosis. Here cord is easily identified through a small incision. Under local anaesthesia, pubic tubercle is marked. Cord after exiting though the external ring passes in front of the pubic tubercle before entering into the root of the scrotum. A small horizontally oblique incision is made directly on the pubic tubercle. Gentle careful dissection directly visualises the cord. Cord is dissected all around for a short distance. Ilioinguinal nerve is outside the cord very closely which should not be injured. Fine haemostat is passed underneath the cord structure to stabilise the cord. Cord is dissected by opening the overlying cremaster; dilated veins are individually dissected and ligated securely. One should not allow tear of the vein, if it happens upper part will retract and bleed which is difficult to identify and ligate. Skin is closed using absorbable sutures (subcuticular / interrupted). It is technically easier; inguinal canal is not opened **(Figs 31-29 to 31-30)**.

Scrotal approach: In case of grade IV, veins have to be excised through this approach. Vertical paramedian incision is made in the scrotum, cord is identified and dilated veins are dissected and securely ligated with vicryl. Often tunica vaginalis sac is opened and everted to prevent possible chance of developing hydrocoele due to lymphatic disruption.

Laparoscopic approach: Earlier it became very popular as technically, it was very easy. Under general anaesthesia, with head down position, after creation pneumoperitoneum, laparoscope is passed through umbilical port. Additional 5 mm or 10 mm ports are placed. Testicular veins are identified on both sides which run retroperitoneally upwards and medially. Peritoneum is incised; vein is dissected and clipped; alternatively bipolar fulguration or intracorporeal ligation can also be done. Once a enthusiastic procedure due to high recurrence rate its efficacy and acceptance is slowly going way.

Complications of varicocele surgery

Haemorrhage and scrotal haematoma; infection, pyocele; injury to testicular artery; injury to ilioinguinal nerve and pain; recurrence—5-10%.

TREATMENT OF CYST OF EPIDIDYMIS

It is due to the cystic degeneration of: Paradidymis (organ of Geraldes)—is the most common cause; appendix of the epididymis; appendix of the testis; the vas aberrans of Haller. Eventhough it is of congenital origin, it occurs in middle age. It is tensely cystic, contains clear fluid; often bilateral. They are aggregation of number of small cysts and so *multiloculated.* They feel like *'bunch of tiny grapes'* situated behind the body of the testis. Because of numerous septae they are finely tessellated and so are brilliantly transilluminant, appear like *'chinese lantern pattern'* **(Figs 31-31A and B)**.

Avoid excision as much as possible as it results in infertility in young individual as it may block the sperm transfer. In old age, excision can be done. Approach (scrotal) and technique is similar like for hydrocoele. Cyst is excised and scrotal wound is closed.

TREATMENT OF SPERMATOCELE

It is a *unilocular, acquired retention cyst* derived from blockage of some portion of the sperm conducting mechanism of the epididymis. It is situated in the head of the epididymis, above and behind the body of the testis. Swelling contains *barley water like fluid,* which contains spermatozoa. It is soft, cystic and transilluminant. It is often considered by the patient as having an additional testis. Aspiration cytology confirms the diagnosis. *Treatment:* It can be left alone. If it is large, excision is done through scrotal approach **(Fig. 31-32)**.

SURGICAL ANATOMY OF TESTIS

It is the male gonad**.** It is suspended in the scrotum by the spermatic cord. It lies obliquely such that its upper pole is tilted forwards and



Figs 31-29(1)



Figs 31-29(2)

Figs 31-29(1 and 2): Technique of subinguinal varicocele repair.

laterally. It is 4 cm long, 2.5 cm broad, 1.8 cm thick with a weight 15 grams (adult). Epididymis lies along the lateral part of the posterior border **(Fig. 31-33)**.

Descent of Testis

Testis develops from mesonephros at T10,11,12 segments. Both side they descend downwards towards scrotum. It appears in 2nd month of intrauterine life; reaches iliac fossa in 3rd intrauterine month; between 4th to 7th month rests in deep inguinal ring; 8th month reaches external ring; at 9th month before delivery reaches to bottom of the scrotum. Factors are hormones, gonadotrophins, differential growth of body wall; action of gubernaculum; intra-abdominal pressure and temperature **(Fig. 31-34)**.



Fig. 31-30: Subinguinal incision both sides for bilateral varicocele ligation of veins.


Testis
Epididymal cyst
Septa
A
B

Figs 31-31A and B: Epididymal cyst.


Spermatocele
Testis

Fig. 31-32: Diagram showing position of spermatocele.


Ductus deferens
Paradidymis
Appendix of epididymis
Globus major (head)
Appendix of testis
Body of epididymis
Tail of epididymis

Fig. 31-33: Anatomy of the testis.


Kidney
Urinary bladder
1
2
3
4
5

Fig. 31-34: Stages of testicular descent.

Coverings of the Testis

1. Tunica vaginalis—lower persistent portion of processus vaginalis.
2. Tunica albuginea—dense, white fibrous coat covering the testis; the posterior border of which is thickened to form the mediastinum testis. Numerous septa extend from it into the inner surface to create around 300 lobules.
3. Tunica vascularis is innermost vascular layer lining the lobules.

Structure of Testis

Testis contains 200-300 lobules, each containing 2-3 seminiferous tubules. Each tubule is 60 cm in length but heavily coiled. Diametre of the tubule is 0.2 mm. Lining of tubule contain cells of different stages of spermatogenesis. These seminiferous tubules join together to form around 30 straight tubules; they enter mediastinum of testis; after joining each other to form rete testis which contains network of tubules. Rete testis gives 30 efferent ductules which comes out at the superior pole of the testis and enters the epididymis with a coiled ductules to form head of the epididymis. A single duct is formed in the body and tail of the epididymis to continue as vas deferens at the lower pole of the testis.

Arterial Supply

Testicular artery, a branch of abdominal aorta arises at the level of 12th vertebra a little below the origin of renal arteries; runs downwards and laterally on the psoas major in the posterior abdominal wall crosses the IVC, ureter and genitofemoral nerve on the right side. On right side, it is deep to the ileum (small bowel, terminal ileum). On the left side, artery crosses the left ureter, left genitofemoral nerve running on the left psoas major lying deep to colon. It travels downwards to enter the internal inguinal ring and inguinal canal. It runs in the spermatic cord (within the cord anterior to the vas deferens) to reach the posterior border of the upper pole of the testis. It divides into smaller and larger branches. Medial and lateral branches pierce the tunica albuginea to reach tunica vasculosa.

Venous Drainage

It is by forming pampiniform (*like a vine)* plexus of veins which ultimately fuse to form single vein, which drains into IVC on right side, left renal vein on left side. In the scrotum, its anterior part is around the testicular artery; middle part is around vas deferens and testicular artery; posterior part is isolated. It forms four veins at external ring; two veins at internal ring; single vein at retroperitoneum.

Lymphatic Drainage

It is into para-aortic and pre-aortic group of lymph nodes at the level of L_2 vertebra.

UNDESCENDED TESTIS

Complications of Undescended Testis

Sterility; trauma and pain; an associated indirect inguinal hernia (70%); torsion testis; epididymo-orchitis (as the pain will be high up it mimics acute appendicitis); testicular atrophy; *malignant transformation in undescended testis is 20 times more common* than normally descended testis. It is higher in abdominal than in inguinally located testis. *Seminoma* is the most common malignancy in undescended testis. The testis which has normally descended on other side (in case of unilateral undescended testis), is also more prone for malignant transformation than normal individual.

Investigations

Abdominal ultrasound (U/S) is done but intra-abdominal testis is difficult to detect in U/S. Assessment of FSH, hCG. If FSH is high in a young boy, that means there is bilateral anorchia. CT scan can be done probably to locate the abdominal testis; gonadal venogram; laparoscopy—quiet useful and therapeutic also; blind ending *vas deferens* in laparoscopy is called as *vanishing testis*. It means testis has completely atrophied **(Figs 31-35 and 31-36)**.



Fig. 31-36: Laparoscopic view of undescended testis adjacent and deep to internal ring.



Fig. 31-35: Undescended testis; on table finding.

Treatment

Treatment is always surgery. Surgery is done between two and four years of age.

Principles

Mobilisation of cord to achieve adequate length is important. Repair of associated inguinal hernia is essential as it is a very common association. Finally needs adequate scrotal fixation without tension which will keep the testis in place and prevents its retraction into the groin during healing.

Mobilisation of Spermatic Cord

Under general anaesthesia in children, spinal in adult after cleaning and draping, inguinal canal is opened with lengthy incision like for inguinal hernia. Hernial sac is identified; often cord will be less developed and testis will be smaller than normal. Unless sac or tunica vaginalis is opened it is often difficult to identify the undescended testis. Herniotomy is done. Inferior epigastric vessels are ligated to lengthen the cord. If length is still required, vas and testicular vessels are mobilised retroperitoneally. If further length is required then a soft clamp is applied to the testicular artery and the viability of testis is checked. If it is viable that means it is also receiving blood supply from the artery of vas or cremaster vessels. Then testicular artery can be ligated safely so that adequate length can be achieved to bring down the testis to the scrotum—*Stephen-Fowler's technique.*

Fixation of the Testis

Proper scrotal pouch is created by finger dissection. Fixation of the testis into the scrotum is done using nonabsorbable interrupted sutures (polypropylene). A small scrotal incision is made at the bottom of the scrotum. Long haemostat is passed through the scrotal wound across the scrotum to inguinal wound; stay suture placed at the gubernaculum is held with haemostat and pulled gently out towards the scrotal wound. Interrupted bites are taken between tunica albuginea and scrotal wall; usually three bites are taken from below upwards using 3 zero polypropylene suture. Knots are tied at the end. Scrotal wound is sutured. Inguinal wound is closed in layers.

In bilateral cases, testis is passed into the opposite scrotum through an opening in the scrotal septum —*Ombredanne's operation* **(Fig. 31-37).**

If the testis is totally atrophied, *orchidectomy* should be done after taking consent, because even though this is a nonfunctioning testis, it is highly prone for malignant transformation. Removed testis should be sent for histology.

Laparoscopic orchidopexy: Laparoscopic mobilisation of the testis is very useful. Under general anaesthesia, head down position, ports are placed on both sides at the level of the umbilicus. Gonadal vein is identified and traced downwards to reach the testis. Usually it will be very close to the internal ring. Peritoneum is incised close to the cord and the testis and mobilised. Hernial sac is dissected like in laparoscopic hernia repair. Once adequate mobilisation is done like in open method small scrotal incision is made and through a long haemostat mobilised testis is pulled down to scrotum to fix it similarly. Inferior epigastric vessels can be clipped and divided through laparoscopy safely which will add on to the extra length of the cord.

Role of hormone therapy: Not much. Only indications are cryptorchidism associated with hypogenitalism and obesity and doubtful retractile testis. It should be given at or after the age of eight. hCG (Chorionic gonadotrophin) 1000 I/U—twice weekly for maximum of ten weeks (not more than 10 weeks). It stimulates Leydig cells to produce testosterone. GnRH—1.2 mg/day as nasal spray for one month.

Note: In bilateral case surgery is done with an interval of 6 months.

Ladd and Gross procedure: After placing the testis in the scrotal pouch, it is fixed by a polypropylene suture into tunica albuginea, across scrotal skin and into the thigh skin outside. This suture is removed in 14 days.

Keetley-Torrek procedure: Testis is mobilised and is brought into the scrotal pouch first. Then it is brought out through scrotal skin. A pouch is created on the medial aspect of the thigh outer to fascia lata, deep to thigh skin after making skin incision. Testis delivered from scrotal pouch is placed into the thigh pouch. Scrotal and thigh incisions are sutured around the cord inside. After 6 months scrotal sac with cord and testis is separated and placed in the scrotal pouch.

Laparoscopic approach: Orchidopexy has become popular and accepted method.

Orchidopexy may not alter the chances/risk of developing carcinoma of testis. But it makes easy observation and evaluation by ultrasound to detect the possible changes early.

Orchidectomy is considered if there is atrophy; torsion; inability to bring down abdominal testis.

Testicular biopsy in infertility to study spermatogenesis is sent in *Bouin's fluid*—picric acid (75%); acetic acid (25%). It should not be sent in usual formalin.

Surgeries in undescended testis

External anchorage—Ladd and Gross
Ombredanne's procedure
Denis-Brownes operation—narrowing of the neck and external anchorage
Keetley-Torrek procedure into the thigh
Dartos pouch creation and placing the testes
Stephen-Fowler's technique
Silbar procedure—autotransplantation with microvascular anastomoses into inferior epigastric vessels

ECTOPIC TESTIS

Lockwood theory: Even though there are multiple gubernaculum, scrotal tail normally gets activated better and so testis is brought down to the scrotum. In ectopic testis, scrotal tail weakens or ruptures and so one of the other accessory tails will act and pulls the testis in direction according to its site.

Different Sites

Superficial inguinal pouch; perineum; root of the penis; femoral triangle (thigh) **(Fig. 31-38)**.

Testis, here functions normally and is of normal in size. It is more prone for trauma and can cause psychological problem.

Superficial inguinal pouch is a space between external oblique and Scarpa'a fascia. On raising the legs, ectopic testis in superficial inguinal pouch becomes more prominent but not in case of undescended testis located in inguinal canal.



Figs 31-37(1)



Figs 31-37(2)

Figs 31-37(1 and 2): Orchidopexy—technique in undescended testis.

Treatment

Mobilisation and creation of a new scrotal pouch to place and fix the testis to scrotal pouch using polypropylene interrupted sutures.

TREATMENT OF TORSION TESTIS

Emergency exploration of the scrotum and untwisting of the torsion testis is done. Then viability of testis is checked. Arterial Doppler of both sides is must. Twisted testis will be viable only for 6 hours—critical period/golden period so urgent correction twist and fixation is essential **(Figs 31-39 to 31-41)**.

Once viability is confirmed, the testis is fixed to the scrotal sac using three interrupted nonabsorbable sutures (3-0 polypropylene). Fixation should be done using only nonabsorbable sutures, never absorbable sutures. If surgery is done within 6-12 hours, viability of the testis may be retained. If delayed, testis becomes gangrenous and *orchidectomy* is done after taking informed consent. *When in doubt, testis is retained and orchidectomy can be postponed to later period* so as to give a chance to have a viable testis. Here *early exploration is an important aspect.* When diagnosis is in doubt, exploration is advised.

Postoperatively, a repeat Doppler study helps to confirm the viability. As often the condition is *bilateral, other side testis should also be fixed to prevent the torsion.* Approach to other side should



Fig. 31-38: Tails of Lockwood and ectopic testes.



Fig. 31-39: Direction of torsion of testis is always outwards.

be different through other side hemiscrotum. It is better to avoid approaching other side through same ipsilateral incision.

TESTICULAR BIOPSY

It is done in infertility with low sperm count. It is usually done under local anaesthesia. Only one side is done. After injecting local anaesthesia xylocaine without adrenaline (plain), skin, dartos, spermatic fasciae are incised. Tunica vaginalis is incised. Testis is exposed. With no. 15 blade small incision is made on the tunica albuginea. Protruding seminiferous tubules less than 5 mm size is excised. Tunica albuginea is sutured using 3 zero vicryl or monocryl continuous sutures. Tissue is placed in *Bouin's fluid*—picric acid (75%); acetic acid (25%). It is sent for spermatogenesis assessment. Skin is closed **(Fig. 31-42)**.

TREATMENT OF TESTICULAR TUMOUR

Spread of Testicular Tumour

Local

To epididymis, cord, tunica albuginea, scrotum and so inguinal nodes.

Lymphatic Spread

Lymphatics drainage of testis is through its mediastinum along the gonadal vessels to para-aortic and retroperitoneal nodes. Through the lymphatics along the medial side of testis may run with the artery of vas draining into the common iliac nodes at the bifurcation of common iliac artery. Spread mainly occurs to ***para-aortic***; often to retroperitoneal and common iliac nodes. Malignancy spreads to inguinal nodes, only if scrotal skin is involved.

Right testicular tumour spreads to interaortocaval nodes immediately below the renal vessels as *primary landing zone* (L2 level), then to para-aortic nodes. Paracaval, preaortic, common iliac nodes can be involved.

Left testicular tumour spreads to true para-aortic nodes to begin with just below the renal vessels; then to preaortic and common iliac nodes.

From retroperitoneal and para-aortic nodes spread occurs to left supraclavicular nodes and posterior mediastinal nodes. Seminoma mainly spreads through lymphatics than teratoma.

Extranodal Spread

It occurs to lungs, liver, brain, bone, kidney, adrenals in order of frequency.

Investigations

No FNAC; No scrotal approach; No incision biopsy.
Through inguinal approach, cord and testis are exposed. A soft clamp is applied to the cord at or above the level of the deep ring so has to prevent dissemination through blood. Frozen section biopsy is done from the suspected area. If tumour is positive, *high orchidectomy is done (Chevassou maneuver).*

Measurement of tumour markers (HCG, AFP, LDH) are important. AFP and hCG are elevated in nonseminomatous germ cell tumours (teratomas)—65%. Raised AFP always indicates teratomatous tumour. *AFP level increase is not seen in pure seminomas.* hCG may be elevated in *advanced* cases of seminomas (10%). LDH level depends on growth rate/cellular proliferation/tumour burden. LDH is increased in 80% of advanced seminomas and 60% of nonseminomatous germ cell tumour. hCG is never found in normal individual. It is secreted by syncytiotrophoblasts. Half life is 18-36 hours. It is increased in choriocarcinoma (100%); embryonal carcinoma (65%); teratoma testis; recurrent or residual disease in testicular tumour after therapy. Placental alkaline phosphatase (PLAP) is increased in seminoma.

Chest X-ray is done to look for lung secondaries. HRCT scan is ideal. *Ultrasound abdomen* is done to see nodal status like para-aortic nodes and liver secondaries. *Ultrasound scrotum to see* echogenicity of testis and tumour within is essential.

CT scan abdomen and pelvis is to look for secondaries, iliac and para-aortic nodes. CT chest is needed to confirm lung secondaries.

Based on presence of AFP; hCG; LDH; nonpulmonary visceral secondaries (bone/liver/brain), germ cell tumour risk group classification is done to both seminomatous germ cell tumour (SGCT) and also to nonseminomatous germ cell tumour (NSGCT).

Good risk and intermediate risk group for SGCT.

Good risk; intermediate risk and poor risk for NSGCT **(Fig. 31-43)**.



Fig. 31-40: Torsion testis – early intervention shows viable testis. It should be fixed to scrotal wall; opposite testis is also fixed using nonabsorbable interrupted sutures.



Fig. 31-41: Testicular torsion with gangrene testis. This testis is not viable; so needs orchidectomy.

Staging of testicular tumours

I. Lesion confined to testis
II. Nodes involved below the diaphragm
III. Nodes involved above the diaphragm
IV. Distant (blood) spread

TNM staging

T_0 – No evidence of tumour
Tis – Carcinoma in situ
T_1 – Tumour limited to testis and epididymis. Vascular/lymphatic invasion not present. Tumour may invade tunica albuginea but not tunica vaginalis
T_2 – Tumour limited to testis and epididymis with vascular/ lymphatic invasion. Or tumour extends through the tunica albuginea with involvement of tunica vaginalis
T_3 – Tumour invades to spermatic cord with or without vascular/ lymphatic invasion
T_4 – Tumour invades to scrotum with or without vascular/ lymphatic invasion
N_0 – Regional lodes not involved
N_1 – Single/multiple nodes—not more than 2 cm in size
N_2 – Regional nodes—between 2-5 cm
N_3 – Regional nodes > 5 cm

Contd...

Contd...

M_0 – Distant spread not present
M_1 – Distant spread present
M_{1a} – Distant spread to nonregional nodes or to lungs
M_{1b} – Distant spread to other than nonregional nodes or lungs

Serum tumour markers (S)

S_x – Marker study not done
S_0 – Normal marker study
S_1 – LDH < 1.5 × N (upper limit of normal) and hCG < 5000 mIU/ml and AFP < 1000 ng / ml
S_2 – LDH 1.5-10 × N or hCG 5000-50000 mIU/ml or AFP 1000-10000 ng/ml
S_3 – LDH > 10 × N or hCG > 50000 mIU/ml or AFP > 10000 ng/ml

Treatment

Initially high orchidectomy is done in all patients through inguinal approach by ligating and dividing the cord at internal ring level **(Fig. 31-44)**.

Seminomas are radiosensitive. So after high orchidectomy, *radiotherapy* is given to increase the cure rate and also to reduce relapse. It is


Bouin's solution

Figs 31-42(1)



Figs 31-42(2)

Fig. 31-42: Testicular biopsy is done to study stages of spermatogenesis in infertility with low sperm count. Bouin's fluid is used. Only one side is done.



Fig. 31-43: Staging of testicular tumours.

the treatment of choice in stage I seminomas. Opposite testis should be shielded during radiotherapy. Seminomas with high levels of tumour marker are treated as nonseminomatous tumours.

Chemotherapy is also effective. *Cisplatin* is very useful drug in seminoma. *In teratoma, retroperitoneal radical lymph node Dissection (RPLND)* is beneficial after high orchidectomy. Even in stage I disease, chances of existing retroperitoneal spread is 30%. So RPLND (infrahilar) has a major role especially in teratomas which are relatively radioresistant. It involves removal of precaval, retrocaval, paracaval, interaortocaval, retroaortic, para-aortic, common iliac nodes along with removal of gonadal vein and adjacent fibrofatty tissues from internal ring level to its insertion into renal vein on left side and inferior vena cava on right side. Commonly bilateral RPLND is done as contralateral nodes also can be involved. Mortality in RPLND is only 1%. RPLND may cause ejaculatory problems. Nerve sparing RPLND is ideal if technically possible. Nerve sparing dissection is done on opposite side of the tumour. Laparoscopic RPLND is also advocated safely.

Note:
Please refer chapter 26 retroperitoneal surgeries for description of RPLND.

Modified RPLND is same side lymph node dissection both above and below the inferior mesenteric artery (IMA); opposite side dissection is limited to above the level of IMA so that sympathetic chain on opposite side is preserved to retain ejaculation.

Complications of RPLND: Haemorrhage; injury to main structures like major vessels/ureter/bowel; chylous ascites; lymphocele; retrograde ejaculation.



Figs 31-44(1)



Figs 31-44(2)



Figs 31-44(3)

Figs 31-44(1 to 3): High orchidectomy is done for testicular tumour through inguinal approach. Not through scrotal incision. Cord is ligated at the level of the internal ring.

Chemotherapeutic drugs for teratoma are *cisplatin, bleomycin,* vinblastine, *etoposide,* ifosfamide, mesna, paclitaxel. BEP regime is commonly used (Bleomycin, etoposide, cisplatin).

ORCHIDECTOMY

Testis is removed for variety of reasons. However, formal written consent should be taken before doing orchidectomy. It is done in pyocele, chronic haematocele, testicular tumour, undescended testis where testis is atrophied. Bilateral orchidectomy is done in carcinoma prostate to achieve hormone control.

Types

- Low orchidectomy.
- High orchidectomy.
- Subcapsular orchidectomy.

Low Orchidectomy

It is done in pyocele, old clotted chronic haematocele. Arterial Doppler is a must to confirm the nonviability of testis. In case of pyocele, on table Doppler is ideal to confirm nonviability and also to document for legal purpose.

Under spinal or general anaesthesia after cleaning and draping incision is made on the scrotum lateral to the median raphe. Skin, dartos, spermatic fascia is incised. Nonfunctioning testis is mobilised up to the root of the scrotum by blunt finger dissection. Cord is mobilised for adequate length. At the root of the scrotum cord is clamped using three strong clamps or Kocher's forceps. Distally one more haemostat is applied **(Fig. 31-45)**.

Cord is divided and testis is removed and sent for histology. Transfixation suture is placed using 1 zero vicryl or chromic catgut.



Fig. 31-45: Site of clamping for low orchidectomy.

Nonabsorbable suture material like polypropylene is not used as it may cut through the tissues. It is also not possible to dissect the cord structures to isolate the vessels and ligate independently. Clamps should not slip as if it happens vessels retract proximally into the groin causing torrential bleeding and it is difficult to identify the bleeder from the retracted vessel. Alternatively after mobilisation of the cord, first transfixation is done proximally using vicryl and clamps are applied to divide the cord which prevents retraction and possible bleeding of the vessel.

Corrugated or suction drain is placed which is removed in 48 hours. Skin with layers is sutured with interrupted sutures. Sutures are removed 7-10 days **(Fig. 31-46)**.



Figs 31-46(1)



Figs 31-46(2)

Figs 31-46(1 and 2): Low orchidectomy is done for pyocele; haematocele. In this old aged patient while doing hydrocoele surgery, firm lesion was found in the testis and so through scrotal approach only low orchidectomy was done. Biopsy report was inflammatory mass. Ideally scrotal wound should have been closed; new separate inguinal incision should have been made through which testis with cord is delivered into the groin high up to deep ring and cord is ligated at deep ring to achieve high orchidectomy. On table ultrasound will be very useful.



Fig. 31-47: Site of ligation in high orchidectomy (Chevassou maneuver).

High Orchidectomy

It is done classically for testicular tumour. It is also done in undescended testis. Lengthy inguinal incision is placed. Inguinal canal is opened. Testis with cord is dissected, mobilised fully up to or proximal to the internal ring. A soft occlusion clamp is placed over the cord at internal ring level. Testis is palpated for confirmation of the tumour. Often it is transected partially and seen; biopsy is done from the suspected area and confirmation is done by frozen section. If biopsy is negative then testis capsule is sutured back and testis is placed in the scrotum **(Fig. 31-47)**.

Once frozen section confirms the malignancy, clamp is not released; transfixation of the cord is done just proximal to the clamp using silk or vicryl and distally cord is divided to complete the orchidectomy. Double ligation of proximal cord stump is needed. Wound is closed with a suction drain. Testis specimen should be sent for histology. Often it is practice to place prosthesis in the scrotum in young individual. It is also often practiced to do biopsy of opposite side as malignancy can be bilateral. But nowadays due to good imaging (ultrasound) this technique it is not practiced.



Fig. 31-48: Technique of subcapsular orchidectomy.

Subcapsular Orchidectomy

It is done in carcinoma prostate to achieve hormonal control. So it is done always bilateral. It is done under spinal anaesthesia or local anaesthesia. Single midline median raphe incision is sufficient. If surgeon is not comfortable then two separate vertical incisions one in each hemiscrotum may be placed **(Fig. 31-48)**.

Testis is reached; tunica albuginea is incised longitudinally using no 15 blade or cautery. All seminiferous tubules are removed using finger and scoop. Small bleeders in the inner wall of the testis are fulgurated using bipolar cautery. Tunica albuginea is sutured using 3 zero vicryl. Procedure is repeated on the other side. Skin wound is closed using nonabsorbable interrupted sutures. Presently urologists prefer to do low orchidectomy rather than subcapsular one.

Chapter

32

Basic Surgeries in Obstetrics and Gynaecology

General surgeons frequently encounter with gynaecological problems in females. Previously before the advent of ultrasound and CT scan there would be lots of confusion with diagnosis and the surgeon would be surprised with a gynaecological condition on table as the clinical features of some surgical conditions overlap with those of gynaecological conditions. Current investigative methods have reduced the surprises for the surgeons. But still it is wise for a surgeon to know common gynaecological conditions and their operative treatments.

SURGICAL ANATOMY OF FEMALE GENITALIA

Female genitalia are broadly classified into *external* and *internal genitalia*.

External Genitalia

It is also termed as *vulva* or *pudendum*. It is an ill-defined area bounded by *mons veneris* anteriorly, *labia majora* laterally and *perineum* posteriorly.

Mons veneris is a pad of subcutaneous adipose tissue over the pubis, covered by hair in adult females.

Labia majora consists of folds of skin with underlying subcutaneous fat extending on either side from mons in front to end in skin of perineum posteriorly. It is prominent in reproductive age group, covered with hair on outer aspect, whereas the inner aspect is hairless, moist and pinker than outer surface. Labia majora is covered with stratified squamous epithelium, contains hair follicles, sweat glands, sebaceous glands and a specialised sweat glands called apocrine glands whose secretions give the characteristic aroma. So presence of all these structures makes labia majora prone for folliculitis, boils, and sebaceous cysts. Labia majora are homologous with scrotum in males.

Labia minora are two thin folds of skin devoid of fat lying on either side within the labia majora, which divide anteriorly to enclose the clitoris forming *prepuce* on upper surface and *frenulum* on under surface; posteriorly unite together to form a fold of skin in midline called *fourchette*. It is devoid of hair follicle but contains erectile muscle fibres, numerous sebaceous glands, vessels and nerve endings.

Clitoris is cylindrical erectile body consists of a glans, covered by prepuce, analogue to the penis in male but here it is entirely separate from urethra, attached to the undersurface of symphysis pubis by suspensory ligament. It is extremely sensitive with numerous nerve endings, plays considerable part during sexual intercourse in inducing orgasm in females.

Bartholin glands are a pair of pea-sized glands situated on either side at the junction of middle and posterior thirds of labia majora deep to bulbospongiosus muscle. They are compound racemose type of glands, secrete abundant lubricating mucus during sexual excitement. Duct is 2 cm long, opens below the level of hymen at the junction of anterior 2/3 and posterior 1/3. It is lined by columnar epithelium but by stratified squamous epithelium near the opening. Gland which is otherwise not palpable becomes enlarged by inflammation. Pus can be expressed through the duct opening on applying pressure on the gland when infected in acute gonorrhoea.

The space between the anterior and inner aspect of the labia minora is the *vestibule* which is bounded posteriorly by the vaginal introitus. *Urethral meatus* lies in the midline just below the clitoris. *Vaginal orifice* lies posterior to the urethral meatus, bounded by a thin membrane called *hymen* in virgins, which contains an eccentrically placed opening. Hymen gets ruptured by coitus which may sometimes cause brisk haemorrhage. It is lined on either side by stratified squamous epithelium.

Vestibular bulb are bilateral elongated masses of erectile tissue that lies beneath the mucous membrane of the vestibule, on either sides of the vaginal orifice in front of the Bartholian gland, which may get injured during child birth resulting in brisk haemorrhage.

Arterial supply of external genitalia is by branches of internal pudendal arteries and femoral arteries. *Venous plexus* formed drain into internal pudendal vein, vesical venous plexus and long saphenous vein. Varicosities that occur in these venous plexus during pregnancy may spontaneously rupture or cause haematoma formation. *Nerve supply* is by cutaneous branches of ilioinguinal and genital branches of genitofemoral nerve and pudendal branches of posterior cutaneous nerve of the thigh. *Lymphatics* drain bilaterally into superficial inguinal lymph nodes, lymph node of Cloquet and external and internal iliac nodes.

Internal Genitalia

It includes vagina, uterus, fallopian tubes and ovaries.

Vagina is the channel that communicates uterus with the exterior at vulva. The canal is directed upwards and backwards making an angle of 45° with the horizontal in erect posture. Though, it is distensible its diameter is wider at its upper part, narrow at its lower part. It is attached to the cervix slightly at a higher level on the posterior aspect making the posterior fornix deepest of the all. This part of the vagina is in direct contact with the peritoneum of the pelvic floor and is the thinnest area in whole of the peritoneal cavity. Pointing pelvic abscess can be drained through the posterior fornix. Herniation of coils of intestine or *enterocele* can occur through this fornix. Ureter lies 12 mm anterolateral to the lateral fornix. Vagina is related to base of the bladder and urethra in front, ampulla of rectum and *pouch of Douglas* behind. Vaginal secretion is derived from cervix and from transudation across the epithelium. Its acidic nature (pH is 4.5) is due to the presence of lactic acid formed by the bacterial (*Doderlein*) activity on the glycogen of the epithelial cells which is also estrogen dependent. This acidic nature is protective and inhibits the growth of pathogenic organisms and also explains the growth of mixed organisms before puberty and in menopausal age group where the influence of estrogen is low. It is supplied by the cervicovaginal branch of uterine artery, branches of internal iliac artery, and middle rectal with internal pudendal artery. Vaginal veins form plexus that drain into internal iliac vein. Lymphatics from lower 1/3rd vagina drain along with external genitalia into superficial and deep inguinal lymph nodes; middle 1/3rd into internal iliac nodes upper 1/3rd into external iliac nodes.

Uterus is a pyriform shaped muscular organ that lies in the pelvis between bladder in front and rectum behind. It measures 8.5-9 cm in length 6.5 cm in breadth and 3.5 cm in thickness, flattened anteroposteriorly, lies in anteverted, anteflexed position, slightly deviated to right. It is divided functionally and anatomically into body and cervix with isthmus being the line of demarcation. It is at this level the peritoneum gets reflected from the bladder onto the body of the uterus and this loose peritoneal fold is called the *utero-vesical* fold of peritoneum. Uterine artery, at this level changes its horizontal course into vertical, along the lateral surface of the body. Uterus consists of corpus or the body and cervix. *Fundus* is that part of the body above the attachment of fallopian tubes. *Cornu* is the junction of attachment of tubes to the uterus. *Isthmus* is the constricted portion that lies between the body and the cervix that forms the lower uterine segment during pregnancy. *Cervix* is the cylindrical lower part of the uterus that opens into the vagina. The endocervical canal is 2-3 cm in length that continues with the endometrial cavity at the isthmus. The exocervix is lined by stratified squamous epithelium whereas the endocervix by mucus secreting columnar epithelium, their junction of transformation is the squamocolumnar junction which is the site of initiation of dysplasia.

Peritoneum covers most part of the uterus except over the anterior aspect of the cervix, and laterally at the sites of attachment of tubes, round ligament and ovarian ligament. Posteriorly the peritoneum covers whole of the uterus, supravaginal cervix, upper part of the vagina and then reflects onto the anterior surface of the rectum thus forming the *pouch of Douglas* that consists of coils of intestine. The two sheets of peritoneum form the *broad ligament* on either side of the uterus which extends to lateral pelvic wall. Fallopian tubes lies in the medial 3/4th of the superior free border, where the lateral 1/4th forms the *infundibulopelvic* ligament which contains the ovarian vessels. *Mesovarium* is a fold of peritoneum that attaches ovary to the posterior layer of broad ligament. *Round ligament* is attached to the uterine cornu reaches the internal abdominal ring. The *ovarian ligament* attaches inner poles of the ovaries to the uterine cornu below the fallopian tubes.

Fallopian tubes are a pair of hollow muscular tubes, 10 cm long, attached to uterine cornu at one end and opens into the abdominal cavity on the other end, the opening of which is surrounded by radiating fimbria, *ovarian fimbria* being the longest is attached to ovaries. Interstitial portion is the narrowest portion of the tube, ampullary is the widest.

Ovaries are paired gonadal structures measuring 5 × 3 × 3 cm, that is suspended in the pelvis by the infundibulopelvic ligament laterally and ovarian ligament medially; mesovarium attaches the hilar surface of the ovary to the posterior surface of the broad ligament. It receives blood supply mainly from branches of ovarian artery and also branches of uterine artery.

Uterine artery, the branch of anterior division of internal iliac artery, supplies chiefly the uterus, tubes, and vagina. Once it reaches the parametrium, it runs medially to reach the internal os, where after giving a vaginal branch it turns upwards along the lateral border of the uterus, running a tortuous course ends near the cornu after anastomosing with ovarian artery. Uterine artery during its course towards internal os crosses over the ureter where it pierces the Mackenrodt's ligament. The vaginal branch of the uterine artery reaches the lateral fornix traversing the parametrium, has to be separately ligated during hysterectomy, which otherwise may lead into severe postoperative haemorrhage.

Ovarian artery arises from the abdominal aorta below the renal vessels; enter the infundibulopelvic ligament, ends by anastomosing with the uterine artery after giving branches to tubes, ovary, broad ligament and uterus. Veins form plexus which lie between layers of broad ligament that drain into renal vein on the left side, into inferior vena cava on the right side.

Lymphatics from the fundus and adjoining uterine corpus drain into para-aortic nodes along the ovarian vessels, from the cornu along the round ligament into superficial inguinal lymph nodes, from the lower part of the corpus into external iliac nodes; lymphatics from the cervix drain into external and internal iliac group, obturator group, paracervical and sacral group of nodes. Lymphatics from these entire groups ultimately drain into para-aortic group of lymph nodes. The lymphatic vessels of the ovary drain in three directions. The main group accompanies the ovarian vessels in the infundibulopelvic ligament, eventually reaches the periaortic nodes near the kidney. Other lymphatic channels communicate with channels of the opposite ovary by crossing the fundus of the uterus through the ovarian ligament. Some channels drain through the ovarian and round ligaments into the superficial inguinal lymph nodes in the groin.

Anatomy of Pelvic Floor

Pelvic floor consists of all structures from the skin of perineum below to the facial covering of the levator ani muscle above. It is pierced from before backwards by the urethra, vagina, and anal canal. Pelvic floor not only supports these canals but also the pelvic organs. Normal physiological function of the pelvic organs depends on the anatomic integrity of this pelvic support. Pelvic organ prolapse, urinary and anal incontinence sexual voiding and defecatory dysfunction can result defect in pelvic support. A proper knowledge of the pelvic support helps to treat pelvic floor dysfunction.

Pelvic Floor Supports

1. Levator ani muscle support
2. Perineal membrane
3. Perineal body
4. Pelvic connective tissue

Levator ani is a paired muscle that forms the main muscular component of the pelvic floor. It is also called as *pelvic diaphragm* and is composed of 3 components—iliococcygeus, ischio-coccygeus, pubococcygeus. Normally levators maintain a constant state of contraction, thus an active floor is provided that supports the weight of the abdominopelvic organs against the forces of intraabdominal pressure. This helps to prevent excessive strain over the ligaments. Type1 muscle (slow twitch) fibres are predominant in these levators which bring about this normal resting contraction of these levators. This helps to keep the urogenital hiatus closed and draw the distal urethra, vagina and rectum towards pubis. The reflux contraction of these muscle elicited by the sudden increase in the intraabdominal pressure is brought about by the type 2 muscle fibres. Relaxation of the levators occurs for a brief intermittent period at the time of voiding, defecation and parturition. Other muscles which form the important component of pelvic floor are bulbospongiosus and ischiocavernosus, superficial transverse perineal muscle of superficial perineal pouch, sphincter urethrae and deep transverse perineal muscle of deep perineal pouch, and external anal sphincter. Levators receive efferents from S_2—S_5 nerve roots; the urethral and external anal sphincters by pudendal nerve.

Mass of dense connective tissue between the distal third of the posterior vaginal wall and the anus below the pelvic floor formed primarily by the connection between the halves of the perineal membrane in the midline forms the *perineal body*. It supports the distal vagina and rectum.

Uterus is supported in its position of anteversion and anteflexion in the pelvis by uterine ligaments, pelvic floor and pelvic cellular tissues. *Endopelvic fascia* is the connective tissue covering of the vagina, supravaginal cervix, uterus, bladder, urethra and rectum. *Pelvic cellular tissue* is the loose areolar tissue that acts as a packing material filling the space between the pelvic peritoneum and the fascia covering the pelvic floor. It condenses into bands that radiate from these organs to lateral pelvic wall laterally, sacrum posteriorly and pubic bones anteriorly. The anterior band which is attached to the anterolateral aspect of cervix, anterior vaginal vault and back of pubic bone is the *pubo vesico cervical ligament*. The lateral band called the *Mackenrodt's ligament* or *cardinal ligament* extends from the supravaginal cervix and upper part of the vagina to the lateral pelvic wall, consists of ureteric canal 1 cm lateral to cervix through which passes the ureter, supports the uterus preventing it to be dragged through the vagina when there is increased intra-abdominal pressure. The posterior band is the *uterosacral ligament* that extends from the uterine isthmus to the level of junction of 2nd and 3rd sacral vertebra, lateral to rectosigmoid, below the fold of peritoneum, acts as support of the uterus, maintaining it in its anteverted position. Mackenrodt's and uterosacrals constitute an important support (*level 1*) to the cervix and upper vagina, whose defects leads to post hysterectomy vault prolapse. The lateral walls of the midvagina are attached on each side to the pelvic walls. The anterior wall of the vagina is attached on its lateral aspect to arcus tendinosus and to the medial aspects of levator ani muscle (*level 2 support*). Clinical manifestation of defects in these support results in prolapse of anterior and posterior vaginal wall and stress urinary incontinence. The distal third of the vagina is attached to the urethra anteriorly, pubovaginalis muscle and perineal membrane laterally, to the perineal body posteriorly (*level 3 support*). Defect in these support results in distal rectocele or perineal descent. While treating genital prolapse it is very important to know and understand the integrity of these supports.

As pelvic cellular tissue extends into the gluteal region through sacrosciatic foramen, obturator region through obturator foramen, femoral triangle through femoral canal, perirenal region along the ureter, labia majus along round ligament, any inflammatory processes in pelvis can spread to any of these regions.

Anatomy of Pelvic Part of Urinary Apparatus in Females

It is important to know the *course of ureter* in pelvis as its course is altered in large broad ligament tumours or myomas. It needs to be dissected during Wertheim's operation. It crosses the bifurcation of common iliac artery beneath the peritoneum, to enter the pelvic brim where it is crossed by the ovarian vessels; and on left side also by mesosigmoid. It forms the posterior boundary of ovarian fossa, lies medial to the structures on the lateral pelvic wall along the anterior margin of greater sciatic foramen. It further progresses downwards, and at the level of ischial spine turns medially and forwards to enter into the ureteric canal in Mackenrodt's ligament, where it is crossed from above by the uterine vessels. After its exit from the canal it progresses forwards and medially to reach the bladder, where it lies from the cervix at a distance of 1-2 cm. Pelvic ureter is supplied from its lateral aspect by branches of internal iliac artery, vaginal artery, vesical and middle rectal arteries which form plexus on its outer fibrous sheath.

Urinary bladder is a hollow muscular organ, which when empty lies in the pelvis in front of vagina and uterus. When filled and gets distended rises above the pelvic brim to become palpable per abdomen. Uterovesical fold peritoneum lies above the bladder base at the level of internal os. Bladder is firmly attached to supravaginal portion of cervix at its base above and to the middle of the anterior vaginal wall at its neck below, but bladder base is separated from the upper part of anterior vaginal wall by a loose areolar tissue that forms the plane of cleavage between the two. It is through this plane where the bladder is separated off the cervix and anterior vaginal wall during hysterectomy and caesarean section. Bladder is supplied by superior and inferior vesical branches of internal iliac arteries. Veins form plexus around bladder neck that drain into internal iliac veins.

Urethra from the base of the bladder passes downwards and forwards behind the symphysis pubis, measures 3.5 cm in length, opens out at the *external urinary meatus* below the clitoris. There is pair of *paraurethral gland of Skene* along the floor of the urethra, the duct of which opens near the external meatus, can get infected to form an abscess or cyst.

SURGERIES IN FEMALE GENITAL TRACT

Preoperative Preparation

Minor surgical procedures of vulva and vagina, dilatation and curettage, cervical biopsy which are done under local anaesthesia can be done as outpatient procedures. Major surgeries of vagina, abdominal operations, needs admission one or two days prior to the procedures.

Patient is assessed by taking detailed history pertaining to her menstruation, pregnancy and postpartum period, other medical illness like hypertension, diabetes, bronchial asthma and epilepsy, tuberculosis, and any surgeries done in the past.

In detail, medical examination is done before major surgeries to rule out hypertension, diabetes and ischaemic heart disease. Chest X-ray is taken in case of chronic cough to rule out emphysema, tuberculosis. ECG and ECHO are done to assess the cardiac status.

Antihypertensives are started for hypertension, insulin for diabetics, antibiotics sometimes with bronchodilators for chest infections. Bleeding tendencies are ruled out by doing bleeding time, clotting and prothrombin time. Blood grouping is done and required amount of blood is kept ready for transfusion. Anaemia with HB% <10 gms needs preoperative transfusion of blood or packed cells in emergency. Urine routine examination is done to rule out urinary tract infection which has to be actively treated prior to surgery. Renal functions are assessed by doing blood urea and serum creatinine levels. Caries tooth and gum sepsis must be managed.

Preparation of the part—The operating site over the abdomen, vulva and perineum must be shaved for all major surgical procedures. Shaving is done with a sharp disinfected razor blade using soap or cream to prevent any injuries to the skin. Vaginal douche must be given for few days prior to abdominal surgeries and vaginal surgeries. For minor surgeries, no vaginal preparation or shaving is required.

Preparation of the bowel is essential for all major abdominal and vaginal surgeries. Bowel wash or enema may be given on the previous day evening. Minor vaginal procedures require no enema. Patient kept fasting for 8 hours for all major surgeries done, with light food intake on the previous day.

Premedications like inj Pethidine 50 mg inj. Phenergan 25 mg with inj. atropine or any other drug is given 1 hour prior to the surgery as per anaesthetists instructions. Preoperative antibiotics are given 1 hour prior to surgery.

Patient is made to empty the bladder prior to minor surgeries. But for major abdominal surgeries catheter is inserted and left *in situ*. For vaginal procedures bladder is initially catheterised and later left *in situ* after the surgery.

Informed consent of the patient is taken for all major and minor procedures explaining the nature of the procedures, its after effects and care.

Patient is placed in Trendelenburg position for abdominal surgeries and in lithotomy position for vaginal surgeries.

For abdominal surgeries vagina is initially cleaned with iodine preparation and later abdomen is painted with iodine preparation and spirit from mid chest to mid thighs. For vaginal surgeries whole of perineum, thighs and lower abdomen is painted with antiseptic solution. Later vulva is initially swabbed followed by vagina. Later the painted area is draped with sterile linen, except the area to be operated is exposed.

Routine bimanual examination under anaesthesia is very beneficial in all vaginal and abdominal surgeries.

DILATATION AND CURETTAGE (D & C)

It is done for diagnostic purpose:

- As a part of investigation and treatment of menstrual disorders
- As a part of initial workup in infertility
- In postmenopausal bleeding.

As a part of treatment in:

- Dysfunctional uterine bleeding
- To remove retained products of conception
- To remove retained IUCD
- To remove endometrial polyps.

Only cervical dilatation done in:

- Cervical amputation
- For intrauterine radium insertion
- For insertion of LNG-IUCD
- For drainage of pyometra
- For cervical cautery.

This procedure is deferred in the presence of active infections of vagina, cervix, fallopian tubes and endometrium.

D&C is done as an outpatient procedure with the patient instructed to fast for 4-6 hours. It can done under general anaesthesia, but doing under local paracervical block and IV sedation (petidine/diazepam and fortwin along with atropine) would be ideal. Prior to the procedure preparing the local area by shaving is not an absolute necessity. Patient is asked to void urine just before the procedure. Patient is placed in the lithotomy position with buttocks protruding slightly beyond the edge of the table. Vulva, vagina and perineum is cleaned with suitable antiseptic lotion (savlon). Bimanual examination is done to assess the position of the uterus, size of the uterus, its mobility, and to assess any other pelvic pathology. Labia is gently drawn apart and *vaginal speculum* (Sim's or Auvard's) of appropriate size is inserted into the vagina. Anterior lip of cervix is held with *volsellum*. If there is difficulty in visualising the cervix, one can use *anterior vaginal wall retractor* to lift up the bladder. The cervix that is held is drawn towards introitus by gentle traction. By doing this the endocervical canal is straightened thereby allowing easy passage of instrument into the uterine cavity. *Uterine sound* held lightly between thumb and fingers is passed gently through the cervix to note the utero-cervical length and also to confirm the position of the uterus whether retroflexed or anteflexed. This has to be done very carefully as any forceful introduction of sound will cause false passages in the endocervical canal.

Dilatation of Cervix

Cervix is now gradually dilated using *graduated metal dilators* (Hegar's or Hawkin's-Amblar's) starting from lowest size close to that of the sound. It is gently pushed into the cervical canal with steady pressure, the tip of which should go well beyond the internal os. The distance to which the dilator is pushed should not be beyond that of the utero-cervical length determined by the uterine sound. And the pressure to be used on the dilator comes by repeated practise. Uterine perforations are more common with smaller dilators than larger ones. The degree dilatation depends on the type of procedure to be done. For simple curettage it is sufficient to dilate up till 7 mm so to allow the passage of a *curratte,* whereas for suction in termination of pregnancy it can be dilated maximum up to 10 mm. Overdoing in nulliparous will cause damage to cervix leading to incompetence.

Curettage of Endometrium

A small sharp curette of 7 mm width is inserted into the uterine cavity. Holding its sharp concave edge firmly against anterior uterine wall curetting is started from 12 o'clock position in ante-clockwise direction with stroke done from fundus to the cervix. Pressure used should be optimum enough to scrape off the endometrium but not too excess to cause uterine perforation. This gauging of pressure comes only by practice. All the anterior wall, posterior wall, cornual ends and fundus must be optimally scraped and are collected on sterile gauze. Endometrial curettings that is scraped off is collected in a bottle containing 10% formalin saline and is sent for histopathological study. In *fractional* curettage, the samples collected from anterior wall, posterior wall, cornual ends and endocervix are separately collected and sent in separate bottles with proper labelling. The sample has to be sent in normal saline to rule out endometrial tuberculosis.

The speculum is removed off the vagina after ensuring the haemostasis. After the patient recovers from anaesthesia she is discharged with a course of antibiotics and analgesics.

Complications

Cervical tear—common at the time of dilatation during earlier days. But now with the use of prostaglandins (vaginal misoprostol 400 mcg 3-4 hours prior to procedure) which aids in softening the cervix and help in favourable dilatation. If cervical tear has occurred it has to be sutured without fail. Sometimes the tear may extend upwards involving the descending cervical arteries causing profuse haemorrhage. This can be controlled by a deep lateral stitch on the cervix. It may sometimes necessitate opening the abdomen if there is a tear of the cervix involving the uterine artery above which needs to be ligated.

Uterine perforation—this can be produced by uterine sound, dilators or curette. Sudden loss of resistance while sounding the uterus, dilating the cervix or curetting the uterus should one suspect perforation. The procedure is abandoned at this point and laparoscopy is done to confirm the perforation. The perforation may be simple involving only the uterus or may injure the bladder, omentum, vessels and intestines. If it is simple uterine perforation without involving adjacent viscera, patient is admitted and observed for 24 hrs with antibiotics, monitoring pulse, temperature and respiration. If she is stable she may be discharged. Laparotomy is required when there is visceral injury, big uterine perforation, vessel injury and peritonitis. Uterine rent is sutured, bleeding vessel is ligated. Hysterectomy is done when there is extensive uterine injury with haemorrhage or broad ligament haematoma. Bowel is inspected from jejunum to rectum including omentem. Simple bowel perforation can be sutured in 2 layers using vicryl sutures. Bowel resection with end to end anastomosis is required in case of multiple perforations along with avulsion of mesentery. Bladder injury if present should be identified and sutured with 2 layers of 2-0 vicryl sutures and catheter should be left *in situ* for 7-10 days.

Infection—may be immediate or late; may be localised to pelvis and uterus or may extend to the general peritoneal cavity causing peritonitis. Local pelvic infection is treated conservatively with higher antibiotics. Generalised peritonitis require proper management of fluid and electrolytes, higher antibiotics, laparotomy, pus drainage, hysterectomy if necessary.

Remote complications are secondary amenorrhoea, infertility due to secondary sepsis.

MEDICAL TERMINATION OF PREGNANCY

Induced abortions in India are been liberalised and was brought under *Medical Termination of Pregnancy Act* passed by the parliament which came into force on April 1, 1971. The law specifies—

1. The condition under which pregnancy can be terminated.
   a. *Medical grounds* where the continuation of pregnancy (i) may endanger the life of pregnant woman ii) cause grave injury to the physical and mental health of the woman as in cardiac diseases (severe grade III and grade IV types, pulmonary hypertension, cardiac enlargement, left ventricular hypertrophy, ECG changes showing myocardial ischemia) renal diseases (CRF),uncontrolled hypertension and diabetes, ongoing psychiatric diseases (like schizophrenia, severe depression), malignancies of cervix or breast, severe degree of hyperemesis not responding to any conservative management.
   b. *Eugenic grounds* where there would be a risk of physical and mental disability in fetus when the mother has been exposed to teratogenic drugs, radiation, viral infections (rubella) , at the time of organogenesis (First 8 weeks of gestation); risk of chromosomal abnormalities (trisomy 21, 18) and inborn errors of metabolism in fetus picked up by amniocentesis done after 14 weeks, sonar study done at 18-20th week revealing neural tubal defects (spina bifida, anencephaly) in fetus.
   c. *Social grounds* to prevent grave injury to the physical and mental health of the pregnant woman, where the woman has to undergo an unplanned pregnancy resulted from contraceptive failure or rape.
2. The abortion procedure can be performed by:
   a. Registered Medical Practitioner who has assisted at least 25 MTP's in an authorised centre and having a certificate.
   b. One who had 6 months house surgeon training in obstetrics and gynaecology.
   c. MD/diploma holder in obstetrics and gynaecology.
3. This procedures can be done at government hospitals or places maintained by the government or at places approved by the government.

Written consent of only the patient is sufficient; in case of minor or lunatic consent of the parent or the legal guardian can be taken.

Termination is legally permitted up to 20 weeks, beyond 12 weeks opinion of two medical practitioners is necessary.

Methods of Termination

Prior to termination it is essential to assess Hb%, blood grouping and Rh typing, urine analysis and blood sugar estimation. If patient is Rh negative blood group it is essential to give inj. Anti-D 50 µg within 72 hours of the procedure. USG to confirm period of gestation.

First Trimester (up to 12 weeks)

Medical method

Mifepristone (RU486) and misoprostol—Mifepristone an analog of natural progesterone blocks its effect and misoprostol (PGE_1) helps in expulsion of conceptus by bringing about powerful uterine contraction. Recommended dose of 600 mg of mifepristone orally on day 1 followed by 400 mcg of misoprostol orally on day 3 is effective when used within 50 days of gestation. 200 mg of mifepristone orally with 800 mcg of misoprostol vaginally is also equally effective.

Problems:

- Incomplete expulsion (2-3%), confirmed by USG done after 2 weeks, needs surgical evacuation.
- Non-responders (1%), where the above protocol has failed to bring about abortion, requires surgical evacuation.

Other regimens:

- Methotrexate 50mg/m^2 IM followed by misoprostol 800 mcg vaginally after 7 days.
- Tamoxifen 20 mg orally for 4 days followed by 800 mcg of misoprostol vaginally.

Surgical Method

- Menstrual regulation
- Dilatation and suction evacuation
- Dilatation and curettage.
  - *Menstrual regulation:* This involves aspiration of uterine cavity within 2 weeks of last missed period without confirming the pregnancy. The contents of uterine cavity is aspirated using a special plastic syringe of 60 ml capacity with a non-return valve attached to a flexible plastic cannula (Karman) of 6-12 mm diameter. The syringe can be used 65-75 times and the cannula for 10-12 times.The vacuum created in the syringe is similar to that in an electrical apparatus, upto 660 mm of mercury. The procedure can be done as an out-patient procedure without anaesthesia but may sometimes require paracervical block.

    Under aseptic precaution, speculum is inserted into the vagina, cervix is visualised and held with Allis forceps or small-sized vulsellum. The cervix is dilated up to the required size. The cannula is inserted into the cavity. It is attached to the syringe. The valve of the syringe is closed and the piston is pulled back to create a vacuum before attaching it to the cannula. Once the cannula is inserted into the uterine cavity the valve is released. The cannula is moved to and fro gently until whole of the endometrial contents are aspirated or the syringe gets completely filled with contents. The cannula is detached from the syringe and the aspirated contents are inspected by pouring it over basin filled with water. The procedure may be repeated until no contents fill the syringe, or you see air bubbles in the syringe or when you feel the gripping sensation of the uterus and uterine cavity feels empty. The vacuum must be repeatedly created as mentioned above before attaching it to the cannula. *Problems*: The procedure may be inadequate in pregnancies beyond 7 weeks. There is risk of continuation of pregnancy (5%) and also a possibility of missing ectopic pregnancy. Other risks are uterine perforation (05%) though rare do can occur. Incomplete abortion, haemorrhage due to retained products of conception, cervical tear and perforations are the other problems that can be encountered.
  - *Dilatation and suction evacuation***:** This procedure involves sucking of products of conception with the help of a cannula attached to a suction apparatus.

    This method is useful in termination of pregnancy less than 12 weeks, in incomplete abortion, inevitable abortion, and molar pregnancy. It can be done as a outpatient procedure under paracervical block and IV sedation (inj diazepam 10mg and atropine 0.6 mg). General anaesthesia may be required in apprehensive patients.

    Prior to the procedure a gentle vaginal examination is done to note the size, position of the uterus with patient in lithotomy position, perineum is cleaned with any antiseptic solution. Draping is done. Posterior vaginal speculum of appropriate size is inserted. Cervix is visualised and held with vulsellum or Allis's forceps. Paracervical block given Uterine sound is inserted into the uterine cavity to know the uterocervical length and the direction of the uterine cavity. The cervix is dilated with the help of dilators as mentioned in the previous topic to a size less than the size of the cannula which has to be used. The dilatation can be made easy by the use of vaginal misoprostol 400 mcg 3 hours prior to the procedure or parenteral carboprost (15 methyl $PGF_{2\alpha}$). Once the dilatation is done cannula is inserted into the uterine cavity. Noting the uterocervical length it should not move beyond that length. With a help of rubber tubing or plastic tubing it is connected to a suction apparatus. The pressure of the suction apparatus is maintained at 400-600 Hg. Injection methergin 0.2 mg is given intravenous. By to and fro movements of the cannula the contents of the uterine cavity are aspirated which gets collected in the bottle of the suction apparatus. The suction can be regulated by placing a finger over the hole at the base of the cannula. The suction is said to be complete when no contents are aspirated from the uterine cavity, air bubbles are seen in the cannula, when one feels the gripping sensation over the cannula by the contracting uterus, and the typical grating sensation .The vacuum has to be broken by detaching the tubing before the cannula is removed. The cavity is gently curetted with a curette. The cannula may be re-inserted to aspirate any leftover contents. At the end of the procedure cervical os is examined for any bleeding. A sterile vulval pad is placed.
  - Problems:
    - » Cervical injury and laceration (already discussed in dilatation and curettage).
    - » Perforation (already discussed in dilatation and curettage). Can be minimised with the use of plastic cannula.
    - » Infection can be reduced and/controlled with the use of proper antibiotics before and after the procedure.
  - Drawbacks: Not beneficial in gestation beyond 10 weeks as the products are big to be sucked into the cannula.
  - *Dilatation and curattage:* The steps are similar as described before. But as the products of conception has to be removed the cervix needs to be dilated to 10-12 mm even for 8 weeks gestation,14-15 mm for 11-12 weeks gestation.The cervix needs to be softened prior to the procedure by vaginal misoprostol (inseted 3 hours before) or intramuscular carboprost (given 2 hours before). Dilatation must be carried out gently and smoothly to avoid cervical tear.

    As the pregnant uterus will be soft intravenous methargin 0.2 mg has to be given once the dilatation is complete and curettage is begun in order to contract the uterus and make it hard. Alternatively oxytocin 5U can be given intravenously as methergin causes undesirable vomiting.

    Uterine sound is passed to know the uterocervical length. Sponge holding forceps or ovum forceps of appropriate size is inserted through the dilated cervix and advanced towards fundus. The sac is ruptured allowing the fluid to flow out. The blades of the forceps is opened and the products are held with the blades and gently pulled out through the cervix. The procedure is repeated until all products are pulled out. Undue traction should be avoided while pulling out the products. If resistance is felt then the products are pulled in small bits until the cavity is felt empty. A blunt curette can now be inserted into the cavity and curettage is done to loosen the tissues. The ovum forceps is re-inserted to remove any more bits left especially from the cornual ends. Cavity can be curetted gently until you feel the grating sensation of endometrium and no blood trickles through the cervical os ensuring the completeness of the procedure. Antibiotics are always given for 5 days to prevent any infection.

Second Trimester Termination

- *Surgical evacuation:* Dilatation and evacuation, aspirotomy
  It is suitable up to 13-15 weeks of pregnancy.
- Intra-amniotic instillation of drugs: Hypertonic saline, urea, prostaglandins.
- Extra-amniotic instillation of drugs: Ethacridine lactate, prostaglandins and hypertonic saline.
- Hysterotomy.

Combining the use of oxyrocic drugs augments the myometrial activity and thereby help to shorten the induction-abortion interval. Vaginal misoprostol 400 mg can be used prior to the above procedure which will help in cervical softening and dilatation thereby preventing cervical tears.

Dilatation and evacuation: Patient is in lithotomy position. Vulva is cleaned with antiseptic solution and draped with sterile clothes. Posterior vagina is depressed with Sim's speculum. Cervix is visualised and held with sponge holding forceps or vulsellum. Paracervical block given. Cervix is dilated as described before up to no.12. Sac is ruptured and the liquor amnii is aspirated with a large-bore suction cannula. A special forceps called the aspirotomy forceps which has long blades, strong jaws measuring 7-12 mm across and no ratchet is inserted into the cavity. The fetal parts are crushed with it and extracted out through the cervix. Injection methergin 0.2 mg IV is given at the time of evacuation to contract the uterus so as to make it hard to avoid perforation and also to minimise the bleeding. Placental parts are also removed with the forceps. Cavity is curetted with blunt curette.

With expert hands this method helps to evacuate the uterus with minimal bleeding and no hospitalisation.

Intra-amniotic instillation of drugs: This method is employed beyond 16 weeks up to 20 weeks. It requires hospitalisation. Drugs instilled into the amniotic cavity may be $PGF_{2\alpha}$ alone or combination of PGE_2 and hypertonic urea solution or hypertonic saline solution. USG is necessary to confirm the placental site. Coagulation profile, cardiac and renal status, are checked.

The prostaglandin solution to be injected is freshly prepared before use by diluting 40 mg of $PGF_{2\alpha}$ in 20 ml syringe containing physiological saline. Combination of hypertonic urea solution and PGE_2 is prepared by dissolving 80 g of 40% urea in 150 ml of physiological saline and mixing it with 10 mg of PGE_2 in 50 ml syringe. 2 mg of 15 methyl $PGF_{2\alpha}$ (carboprost) can also be used with urea solution. Amount of hypertonic saline required is 10 ml per weeks of gestation.

Patient is placed in dorsal position after emptying the bladder. 5ml 1% lignocaine is used to infiltrate the skin over the chosen site far away from placenta. 19-gauge needle is used to inject the local anaesthetic agent into the rectus muscle and peritoneum. An 18-gauge spinal needle or Tuhey needle is inserted into the uterus with the tip in a clear pocket of amniotic fluid. About 20 ml of fluid is withdrawn to ensure the correct placement. If blood comes out of the needle, then probably the needle placement may be incorrect or it may have pierced some blood vessel. The needle is withdrawn and reinserted in another site till clear amniotic fluid is aspirated.

The drugs to be instilled are injected slowly through this needle. As the volume injected may lead to over distension of uterus causing discomfort to the patient, sufficient amount of amniotic fluid (at least 50 ml) must be aspirated prior to instillation. When hypertonic saline is used it is safer to infuse by means of drip set taking at least 5-10 minutes to infuse it. Vital signs should be recorded immediately after the procedure. Patient should be under close observation at least for 2 hours. Antibiotic coverage is given.

The patient may feel severe pain if the drug is injected into the myometrium or into the peritoneal cavity at when the procedure may be abandoned. When hypertonic saline is used as the instillating agent the patient may experience severe thirst, headache, flushing hypertension, chest pain, bradycardia, apnoea, tingling of fingers and severe pain, if the solution is accidently injected into the blood vessel. The procedure should be immediately abandoned and 1000 ml of dextrose solution should be rapidly infused with intravenous diuretics. This may sometimes also cause anuria, cerebral oedema.

Uterine contraction usually commences within 2-6 hours. If at all no satisfactory contraction is seen then the dose of prostaglandins can be repeated without urea solution. One should withhold the use of syntocin infusion to avoid uterine hyperstimulation, cervical laceration and rupture uterus and fluid overload.

Induction-abortion interval is 36-48 hours in 95% of cases when hypertonic saline is used; whereas it is 13-16 hours in 90% of cases when the combination of urea and prostaglandins are used.

Complications

- Nausea, vomiting, diarrhoea (more when PG's are used).
- Intense abdominal pain due to hyperstimulation of uterus.
- Cervical tear and laceration leading to profuse haemorrhage.
- Incomplete expulsion with retained products of conception which might require exploration and evacuation under anaesthesia.
- Intrauterine infection leading to severe sepsis which can be checked with proper usage of higher antibiotics.
- Hypernatraemia due to accidental infusion of hypertonic saline into a blood vessel.
- Uterine necrosis, rupture, pulmonary and cerebral oedema, consumption coagulopathy, and renal failure are hazards more common with hypertonic saline infusion.
- Accidental infusion of saline into bladder wall or myometrium or peritoneal cavity or ovaries can cause severe irritation and tissue necrosis.

Contraindication:

- Hypertonic saline is better avoided in pre-existing cardiovascular disease, hypertension, sickle cell anaemia, renal disease and severe anaemia (as hypernatremia can cause haemolysis).
- PG's are better avoided in patients with known history of bronchial asthma.

Late sequelae: Menstrual disturbances due to chronic endometritis, secondary infertility due to cervical incompetence and tubal block, chronic pelvic inflammatory disease, ectopic pregnancy.

Exta-amniotic instillation of drugs: Drugs used—0.1% ethacrydine lactate (10 ml per week but maximum is 150 mL) $PGF_{2\alpha}$ 200-500 µg or PGE_2 200 µg.

Patient is placed in lithotomy position after emptying the bladder. After cleaning with antiseptic lotion, perineum is draped. Vagina is cleaned with antiseptic solution, cervix is visualised with the help of Sim's speculum and held with tenaculum. A no. 16 Foley's catheter is pushed through the cervix well beyond the internal os up to 10 cm between uterine wall and membranes. The balloon of Foley's is inflated with 10 ml saline or distilled water. This will fit at the internal os there by preventing the fall of the catheter.

Now the drug either ethacrydine lactate or prostaglandins is injected to the extraamniotic space through this catheter. The required dose of prostaglandin is taken and dissolved in physiological saline to make 100 ml solution. This solution is injected through the catheter to the extraamniotic space. The dose of prostaglandins can be repeated every 2 hrs or can be be given as a continuous infusion through the catheter. Usually contraction starts within 1-2 hours and induction – abortion interval is around 16-18 hours in 90% cases. Patient should be monitored continuously for vital signs, uterine contraction and cervical dilatation. The catheter gets expelled with dilatation of cervix followed by expulsion of the fetus. Placenta is frequently retained which needs to be evacuated under anaesthesia.

Complications

- Infection due to indwelling catheter. So some prefer to remove the catheter within 4 hours. Antibiotics coverage should be started at the earliest.
- Intolerance to prostaglandins—fever, severe nausea, vomiting, diarrhoea, uterine hyperstimulation.
- Cervical tear and laceration leading to profuse bleeding.
- Expulsion of live fetus giving a uncomfortable feeling.
- Retention of placenta needing evacuation under anaesthesia.
- Menstrual disturbances due to chronic endometritis, secondary infertility due to cervical incompetence and tubal block, chronic pelvic inflammatory disease are the late sequelae.

Hysterotomy

This is not routinely done for medical termination of pregnancy. It is done if all the other methods for midtrimester abortion fails and is usually combined with tubal sterilisation whenever necessary. The procedure is usually done through abdominal route but can also be done vaginally.

The patient is prepared as for any abdominal surgery. The procedure can be done under general or spinal or epidural anaesthesia. The abdomen is painted with antiseptic lotion, draped with sterile drapes. Abdomen is opened by Pfannenstiel incision. After opening the peritoneum uterus is drawn out of the incision and the abdomen is packed with sterile mops to prevent the spillage of uterine contents into the peritoneal cavity (to prevent scar endometriosis). The loose uterovesical fold of peritoneum is opened and bladder is pushed down. A vertical incision of 5 cm is made on the myometrium as low as possible, deepened until the membranes are visible. As the isthmus is narrow in early pregnancy, transverse incision may cause injury to uterine vessels. Inj. Methergin 0.2 mg is given intravenously. The products of conception are gently removed from the uterine cavity. Cavity is cleaned with a gauze gently.The uterine incision is closed by apposing the muscle in 2 layers by continuous sutures, with 1-0 chromic catgut in round bodied needle.

Alternatively, uterus can be opened in the upper segment without opening the UV fold of peritoneum, but the incision is made as low as possible. This approach is usually followed by tubal ligation to prevent rupture uterus in future pregnancy.

Abdominal packs are removed. Abdomen is closed in layers after a peritoneal wash with saline.

Patient is kept nil oral till the bowel movements are heard. Hydration is maintained with IV fluids. Sepsis is prevented with proper antibiotics. Patients is watched for vaginal bleeding, and sepsis. Patient is discharged on 5th day from the hospital.

Complications

Sepsis peritonitis, uterine bleeding, anaesthetic hazards are the immediate complications. Menstrual irregularities, scar endometriosis, rupture of hysterotomy scar in future pregnancy are the delayed complications.

Vaginal Hysterotomy

Patient is placed in lithotomy position. Cervix is exposed with Sim's speculum and anterior wall retractor. It is held with vulsellum. Anterior vaginal skin above the cervix is infiltrated with 10 ml 1:200000 adrenaline to reduce the bleeding. A horizontal incision is made on the vaginal epithelium at its junction with the cervix. Bladder is identified and pushed up with finger and guaze to expose the cervix and the lower segment. Uterine wall is incised 3 cm on the lower segment; products of conception are removed with ovum forceps. Later the uterine wall is closed followed by the closure of the vaginal epithelium.

This procedure avoids all the hazards of abdominal procedure.

BARTHOLIN CYST AND ABSCESS

Bartholin's cyst is a rounded swelling on the inner aspect of labium majus at the junction of anterior 2/3rd and posterior 1/3rd due to blockage of duct orifice following chronic inflammation. Cyst is asymptomatic but may cause slight vulvar discomfort, dyspareunia.

Cyst may sometimes rupture spontaneously which then may require sitz bath and a course of antibiotics. Persistent cyst needs excision which can be done under general anaesthesia with the patient placed in lithotomy position. Vulva and perineum is painted with antiseptic lotion and draped. A vertical incision is made over the outer aspect of the cyst not extending upwards too much as it may cause damage to vestibular bulb containing venous plexus. A plane of cleavage is dissected between the cyst wall and the vaginal mucosa and skin. As the cyst is thin walled and the tissues around the cyst wall are thickened and vascular, the cyst is likely to rupture during the dissection. Sharp dissection helps to enucleate the cyst completely. Duct also should be removed along with the cyst. Bleeding vessels has to be cauterized or ligated. Cavity is obliterated with interrupted sutures. A silastic drain can be kept in the cavity if there is excess oozing. The skin is trimmed and closed with interrupted sutures. Drain may be removed on the 2nd day. Patient is discharged with a course of antibiotics **(Fig. 32-1)**.

Acute inflammation of the Bartholin gland leads to bartholinitis and abscess formation. Abscess is very painful causing the patient difficult to sit, and walk. Incision and drainage of the abscess is done under general anaesthesia. A vertical incision is done on the outer aspect of the abscess. Pus drained is sent for culture and sensitivity. Finger is inserted into the cavity and explored. Gauze plug soaked with betadine solution is kept in the cavity. Daily dressing is done till cavity heels. Antibiotics are given. Alternatively *marsupialisation* can also be done for bartholin abscess. Under general anaesthesia a vertical incision 2.5 cm is made over the vaginal aspect of the labium. The skin is separated from the underlying abscess. The abscess cavity is opened with scalpel. Pus drained is collected and sent for culture and sensitivity. The edges of abscess cavity and skin is trimmed and apposed with 3-0 interrupted catgut sutures. No drain is required. Even though it is practiced to suture the skin if infection is severe, pack can be kept and dressing can be done. As if it is severely infected area, it will not granulate if sutured. Non suturing may lead into wide scar. When healing occurs a small permanent opening will remain **(Fig. 32-2)**.

ECTOPIC PREGNANCY

It is an abnormal pregnancy where the fertilised ovum implants and develops outside the normal uterine cavity.

Sites of Ectopic Pregnancy

Fallopian tubes—98% (ampullary portion commonest)
Ovaries—0.15%
Abdominal cavity—1%
Cervix

Clinical Features

Patient with ectopic pregnancy presents with variable degrees of abdominal pain (may be severe, acute or dull aching type); short


Cyst
Incision
Cyst wall
Cyst ruptures
Cyst cavity
Skin is sutured using 3 zero chromic catgut
Cyst wall

Fig. 32-1: Bartholin cyst excision—technique.

period of amenorrhoea (may or may not be present, may have on and off spotting); fainting episodes (typical of ectopic), feeling of nausea and vomiting with pain. Some patient may present with profound shock with a characteristic pallor out of proportion to visible vaginal bleeding. Tenderness in lower abdomen and the typical tender uterine movement, raised serum β-HCG, ultrasound abdomen and pelvis may show free fluid in pelvic cavity along with absence of intrauterine gestation with presence of gestational sac outside the uterine cavity—all help in coming to a diagnosis. In doubtful cases laparoscopy can be done to diagnose and proceed with ectopic gestation.



Fig. 32-2: Bartholin abscess drainage.

Surgical Aspects in Ectopic Pregnancy

Once the diagnosis is confirmed patient is immediately taken up for surgery. Patient in shock is initially resuscitated with IV fluids. Minimum 2 points of blood is arranged as there may be significant intra-peritoneal haemorrhage. IV antibiotics are given.

Abdomen is opened by a large incision either by Pfannenstiel or lower midline so as to have adequate access to ectopic site and also there may be adhesions which may have to deal with. Blood in the peritoneal cavity is cleared off with suction. Ectopic site is identified.

In tubal ectopic gestation, *salpingectomy* is done when future fertility is of no concern, when there is rupture with major intra-peritoneal haemorrhage, or when the tube is extensively damaged. One pair of long haemostatic clamps (Kocher's long and straight clamp) are placed on the medial end of the fallopian tube including the mesosalpinx close to the tube so as to conserve the ovarian vasculature. Second pair is placed on the lateral aspect on the mesosalpinx. The tips of the clamps should be approximated. If the adjacent ovary need to be removed the second pair of clamp is placed over the infundibulopelvic ligament. The divided pedicles are transfixed and ligated with 1/0 vicryl sutures before releasing the clamps. The excised tubes are sent for histopathological examination.

Partial salpingectomy/segmental resection is done when one wants to conserve the tube for fertility. Only that part of the tube damaged by ectopic pregnancy is removed, leaving behind considerable amount of tube for reanastomosis in later period. Clamps are applied on either side of the ectopic. Before applying clamps it is essential to note vessel free area in the mesosalpinx which appears transilluminant. The tips of the clamps should be placed close to each other. This will avoid bleeding from any blood vessels when sutures are applied. The pedicles include the cut end of the tubes and mesosalpinx. If the patient does not wish for future fertility tubal ligation (by *Pomeroy's method*) is done on the other tube.

Conservative Surgery in Ectopic Pregnancy

Salpingostomy/Salpingotomy: In case of un-ruptured ectopic pregnancy, this procedure can be done to conserve the tube. The tube is held on either side of the ectopic gestation with Babcock's forceps. A linear incision on the antimesenteric border, running parallel to the tube is done with knife/needle tip cautery/laser, at the site of ectopic gestation for about 2/3rd of the length of the swollen part. Prior to the incision over the tube, inj. vasopressin may be given to the tube so as to reduce bleeding. Products of conception are flushed out with suction irrigator or removed with non-toothed dissecting forceps. Bleeding points are ligated with fine sutures or cauterized. Lavage of the tube with Hartmann's solution may help in identifying the bleeding points. If the tube is not very healthy with fimbria partly occluded, it is left open (*salpingostomy*) without suturing to heel by itself, which usually occurs in 3-6 weeks. The incision may be closed in one layer with fine 6/0 prolene if the tubes look healthy (*salpingotomy*).

The success of conservative surgery depends on—

- One should not use catgut as it may cause inflammatory reaction in the tube leading to decreased fertility.
- Tubes are to be handled gently using atraumatic instruments and sutures.
- Peritoneal cavity must be cleared off blood clots so to reduce the adhesion formation. Proper haemostasis should be ensured.

Laparoscopic surgeries for ectopic pregnancy is done in haemodynamically stable patient, is now becoming immensely popular as the healing time is quicker with minimal adhesions. Salpingectomy, salpingostomy or segmental resection can be done laparoscopically. In salpingectomy, the tubal segment to be removed is coagulated with bipolar forceps. The meso-ovarium is coagulated and cut close to the tube. The specimen can be retrieved by a small suprapubic stab incision. Haemostasis can be obtained with diathermy.

Chronic Ectopic

Here the patient has passed the acute phase of the ectopic presentation. Due to continuous slow bleed from the ectopic site haematoma is formed which organises to form a mass in the lower abdomen with significant adhesions with the adjacent bowel, omentum and bladder.

Ovarian Pregnancy

Ectopic pregnancy in ovaries is diagnosed when the gestation occupies the region of ovary and that side tube is normal. As rupture is an inevitable phenomenon *oophorectomy* is done. Presently many have advocated cystectomy as the procedure of the choice. Only the portion of the ovary involved by ectopic is removed either by laparotomy/laparoscopy.

Cervical Pregnancy

When the implantation occurs in cervix it leads to cervical pregnancy. It mimics inevitable abortion. But here the uterine size is smaller for the gestational age with internal os closed. Uterine curettage shows no placental tissue. When suction curettage is done to evacuate the pregnancy, one may encounter with mild to severe haemorrhage. This can be dealt with either by uterine packing or by placing lateral cervical suture to ligate the lateral cervical vessel. Cervical encirclage or applying tamponade with Foley's catheter or angiographic embolisation are other methods tried to control bleeding. In severe cases one may need hysterectomy.

Abdominal Pregnancy

It can be *primary* (when the implantation of the fertilised ovum exclusively occurs in the peritoneal cavity) or *secondary* (when the fertilized ovum escapes into the peritoneal cavity either following tubal abortion or through utero-peritoneal fistula). Amniotic sac with the fetus is found within the peritoneal cavity. Placenta may be attached to any of the organs receiving blood supply from it. Empty uterine cavity with abnormal position of the fetus on ultrasound will help one to come to a diagnosis. Laparotomy is done immediately once the diagnosis is made. Fetus is removed out after clamping and cutting the cord close to the placenta. Placenta can be removed if its vascular supply can be identified and ligated. But severe bleeding can occur wherein case sterile packs are kept for 24-48 hours and closed. Angiographic embolisation can be tried to stop the bleeding. Alternatively or in case the vascular supply cannot be identified or the placenta is stuck to a vital organ, it is left *in situ* and abdomen is closed. Higher antibiotics are given to prevent infection. Follow-up with serial ultrasound and serum β-hCG is done to look for the shrinkage of the placenta which can occur by aseptic autolysis. Bowel obstruction, sepsis and fistula formation are the likely complications.

CAESAREAN SECTION

It is an important operative procedure where in fetus after 28 completed gestational week is removed from the uterine cavity by an incision over the abdominal and uterine walls.

When it is done for the first time it is called as *primary caesarian section*, when done on subsequent pregnancies it is called *repeat caesarian section*.

Types

Classical caesarean section—Where the incision made over the uterus is in the upper segment.

Lower segment caesarean section—Where the incision made over the uterus is in the lower segment.

Although caesarian section started as the 'classical type' it is now been totally replaced by 'lower segment caesarean section,' as postoperative complications like adhesions, peritonitis and sepsis are more with classical type and also because of the poor integrity of the scar in classical type giving high chances of rupture uterus. Now classical type is totally out of practice.

Emergency caesarean section—When an unforeseen complication arises either during pregnancy or during labor that may endanger mother's or baby's condition, an emergency section is resorted to.

Elective caesarean section (Planned C-section)—The caesarean is planned and done on a specific date during pregnancy (patient not in labor) chosen by the patient and the doctor after assessing the maturity of the baby.

Indications

Elective indication:

- Previous caesarian section done for a recurring cause like contracted pelvis, CPD
- Previous 2 caesarian section
- Malpresentations
- Severe degrees of placenta previa
- Severe diabetes mellitus, severe hypertension, severe degrees PIH, cardiac disease not fit for induction of labour
- Bad obstetric history
- Elderly primigravida
- Fetal macrosomia with birth weight >4 kg
- Advanced carcinoma cervix
- Pelvic tumours, impacted ovarian cysts not allowing a vaginal delivery
- Previously repaired VVF
- HPV infection in mother
- Maternal request.

Emergency indication*:*

- Complications of labor—prolonged labour or a failure to progress (dystocia)
- Fetal distress
- Cord prolapse
- Uterine rupture
- Increased maternal blood pressure after amniotic membrane rupture
- Maternal or fetal tachycardia after amniotic membrane rupture
- Placental problems (placenta praevia, placental abruption or placenta accreta)
- Failed labour induction
- Failed instrumental delivery (by forceps or ventouse)
- Umbilical cord abnormalities (vasa previa, multilobate including bilobate and succenturiate-lobed placentas, velamentous insertion).

Preoperative Preparation

For elective caesarian section it is advisable to keep the patient fasting for 6 hours. But if the patient is in labour as for emergency C section, it is not possible to keep the patient fasting. To prevent acid aspiration injection ranitidine 150 mg, antiemetic metoclopramide is injected an hour before the surgery. Abdomen and perineum up to mid-thigh is shaved. Inj. atropine 0.6 mg is administered IV. Bladder is catheterised. Before giving anaesthesia it is always advisable to hear the fetal heart sound and do a pelvic examination (especially in patients who were in labour). Some indications like placenta previa, placenta accreta, previous caesarian section, twin pregnancy, rupture uterus require cross-matched blood to be kept ready. Pediatrician should be called for to attend the baby soon after extraction.

Anaesthesia

It may be general/spinal/epidural. It depends on the indication and the experience of the anaesthetist. Most of the elective C section is preferably done under epidural/spinal. General anaesthesia is given when spinal anaesthesia is contraindicated or not possible.

Positioning of the Patient

Patient is positioned in dorsal position with left lateral tilt of 15° to avoid *supine hypotension syndrome*. Under anaesthesia due to direct pressure of the gravid uterus over the inferior vena cava, there would be fall in cardiac output and uterine perfusion which can be prevented by giving a 15° tilt on the lateral aspect with a sandbag or firm pillow.

Antiseptic cleansing with iodine or savlon solution is done followed by draping of the abdomen.

Incision

Before putting an incision over the abdominal wall the lie, presentation of the fetus is confirmed.

The incision may be midline or paramedian or *Pfannenstiel*. *Midline incision* extends from upper border of the pubes to 2 cms below the umbilicus. But its extent depends on the fetal size or configuration of the abdomen. The incision is deepened through the rectus sheath. Peritoneum is opened in the upper third so as to avoid injury to the bladder. Alternatively *Pfannenstiel* incision is used which is now very popular and in wide use, as the wound healing is better and postoperative discomfort, wound disruption is less with this incision. This transverse skin incision is approximately 12 cm long, placed 2-3 cm (2 fingers breadth) above the symphysis pubes. *Joel-Cohen* incision is another transverse incision that could be alternatively used, placed slightly higher, 3 cm below the line joining the anterior superior iliac spine. The incision is deepened through the subcutaneous tissues, haemostasis is obtained with diathermy. Rectus sheath is incised in midline and the incision is extended laterally with scissors. Rectus sheath held with Allis forceps or Lane's tissue holding forceps and dissected upwards. Bleeders are secured with diathermy. The parietal peritoneum is identified, held with two artery forceps and opened with knife or scissors after confirming that there is no structure in the underlying the peritoneum. The peritoneal incision is extended upwards; downward extension must be done carefully due to the presence of bladder which may have displaced unexpectedly high.

The lateral recesses of the wound may be packed with taped abdominal packs to prevent the soiling of the peritoneal cavity with liquor or meconium. Free packs should be avoided as they may get lost in the abdominal cavity leading to medicolegal issues and other complications.

Any rotation (*dextrorotation* commonly) in the long axis of the uterus is noted by the position of the round ligament. This is very important, as if not corrected now; when the uterine incision is done there will be unnecessary lateral extension into the uterine vessels causing bleeding.

Exposing the Lower Uterine Segment

A Doyen's retractor is inserted on the pubic side of the incision. Lower segment is identified. This may not be well formed if is preterm gestation. The loose utero-vesical fold of peritoneum is identified. It is held with non-toothed forceps and opened with scissors. It is extended transversely all along the fold. And the bladder is pushed down away gently by fingers from the site of uterine incision. Fingers are kept towards uterine side rather than bladder. In case of previous caesarian section where there is adhesion of bladder to the lower segment one may have to do sharp dissection with scissors or else it may result in bladder injury. The retractor is advanced further to retract the bladder away from the lower segment.

Uterine Incision

A small transverse incision is made over the lower segment, deepened carefully till one sees the amniotic membrane. The level of the incision depends on the level of the head, such that its widest diameter can be easily brought out. It is usually put 2-3 cm above the bladder base. In unengaged floating head, when the lower segment has not formed and thick as in preterm pregnancy it is better to put the incision slightly higher or else it may extend laterally into the base of the broad ligament involving the vessels. Alternatively low midline, ⊥ shaped or J shaped incision is used. When caesarian section done in advanced stages of labour where the lower segment is stretched incision is placed slightly higher or else the incision may extend into the bladder or into the vagina. It is also better to put a stay stitch in the midline so that the lower uterine flap will not get lost behind the bladder and will help to identify during subsequent suturing.

If the amniotic membrane is not ruptured during uterine incision, it is done and the gushed out fluid is sucked out with the suction. The incision is widened on either side by stretching it with forefingers. This may give ragged edges thereby suturing the uterine edges may give poor quality scar. So, some prefer to widen the uterine incision using scissors, keeping the index and middle fingers underneath the incision for guiding and protection.

Extraction of the Fetus

Four fingers of the hand are inserted below the presenting part. In cephalic presentation the head is gripped with the fingers. The Doyen's retractor is removed. The head is delivered out through the incision which is assisted by the pressure applied over the fundus by the assistant. If the head is deeply jammed in the pelvis, it has to be pushed up by an assistant with sterile gloved hand inserted into the vagina. Once the head is out the secretions in the mouth and nostrils are cleared with hand suction. Shoulders are delivered by insinuating fingers in the axilla; meanwhile the assistant has to retract the upper uterine flap. Once the shoulders are freed the baby will come out freely. The cord is clamped with two artery forceps and cut between the two. Baby is handed over to the pediatrician. Meanwhile inj. Methergin 0.2 mg is given to the mother either IV or IM at the time of delivery of the shoulders to prevent postpartum haemorrhage. Alternatively 5 units of oxytocin may be used in the infusion fluid to prevent bleeding.

In case of high floating head where the delivery of the head through the incision is difficult, one can use outlet forceps or ventouse to extract the head.

In case of breech presentation, the breech is first extracted first through the incision later followed by shoulders and head.

Removal of Placenta

Once the baby is delivered out, the lateral angles of the uterine incision is secured with Green-Armytage clamps. The uterine incision is observed for any bleeding sinuses which are secured with the clamps. Identifying the lower margin of the incision is important as most of the time it gets retracted below and behind the bladder, getting hidden by the pool of blood. It is traced from its lateral angle and held up with Green-Armytage clamps. The stay sutures applied before uterine incision will now come into role to identify the lower margin.

It is always better to wait for placental separation rather than forceful extraction. Once the placenta is found to have separated it is extracted by controlled cord traction, meanwhile applying pressure over the fundus in upward direction. Along with the placenta the membranes are to be carefully stripped off, even from the lower uterine segment. This may require the clamps applied to the margins and the angle to be removed and reapplied.

Complete removal of placenta is ensured by observing for the cotyledons. The uterine cavity may be cleaned gently with sterile gauze. If the patient was not in labor the cervical canal may need to be widened with finger for the outflow of uterine discharge **(Fig. 32-3)**.

Closure of the Uterine Incision

Uterus is closed with atraumatic round bodied needle using 1/0 chromic or 1/0 vicryl needle.

Uterine wound is well visualized. Doyen's retractor is re-inserted to retract the bladder. The suturing is started from the angle far from the operator. The first stitch is taken slightly beyond the angle so as to secure the vessels near the angle. This stitch is very important as sometime the incision may extend laterally tearing the uterine vessels. The suturing is continued taking full thickness of uterine muscle excluding the decidua. Continuous locking suture are used to secure haemostasis. Need of second layer suturing has become a controversy. Some prefer to put a second layer of continuous suture to invert and strengthen the first layer. If haemostasis is well maintained with one layer suturing, then some prefer to avoid second layer suturing. The uterus is palpated to see whether it has contracted or not. Sometimes it may require continuous massage to make it contract and become hard as a cricket ball. UV fold of peritoneum is usually left as such as spontaneous healing is known to occur. Any major bleeding from the bladder base is identified, may need securing with sutures. Ovaries and tubes on both sides are visualised for any abnormalities. The



Figs 32-3(1)



Figs 32-3(2)



Figs 32-3(3)



Figs 32-3(4)



Figs 32-3(5)

Figs 32-3(1 to 5): Lower segment caesarean section – technique.

abdominal packs if kept prior to the procedure are removed. The paracolic gutters are cleared off clots, and meconium. Irrigation with saline may be used if needed.

Closure of the Abdomen

Once haemostasis is ensured, instruments and mop count are cleared from the theatre nurse; the abdomen is closed in layers. Initially peritoneum with continuous 1/0 vicryl sutures, followed by the rectus sheath with continuous 1/0 vicryl sutures. The subcutaneous fat if thick may need to be sutured with 2/0 plain catgut or 3/0 vicryl. The skin is closed with subcuticular sutures with 3/0 monocryl or 2/0 ethylon or with clips.

- Vagina is cleaned off clots.
- Catheter is placed *in situ* for 24 hours.
- Patient is kept nil oral for 18-24 hours.
- Breastfeeding of the baby is started as soon as possible when the mother is able to hold it against the breast.
- Parenteral antibiotics given for 24-48 hours followed by oral preparation.

Complications of Caesarean Section

Maternal Complication

a. *Haemorrhage:* It is common in emergency caesarean section done in patient who was in labour for long hours, multiple pregnancy, and placenta previa, placental abnormalities (increta, percreta, and accreta).

It may be primary or secondary. Primary haemorrhage is due to bleeding from placental bed, uterine sinuses, uterine vessels, or atonic PPH. Bleeding from lacerated uterine vessels and sinuses can be controlled by taking appropriate stitches. Bleeding from placental bed is controlled by giving bimanual uterine compression with warm mops. Occasionally may require figure of eight sutures. When caesarean section is done for placenta previa, where the placental attachment is over the lower segment whose retraction is not sufficient to control the bleeding, careful application of simple or box stitches or figure of eight sutures over the bleeding sinuses will control the bleeding. Compression sutures of lower anterior and posterior segment can be tried. Alternatively lower segment can be packed with a sterile pack; the end of it should be passed through the cervix into the vagina so that it can be pulled out after 18-24 hours. In *atonic PPH* intramyometrial injection of prostaglandin can be tried after parenteral uterotonics. Continuous bimanual compression is tried. If by bimanual compression the bleeding gets controlled then this patient will benefit with B-Lynch sutures.

Technique of B-Lynch suture: With vicryl no.1 or monocryl mounted on 70 mm round bodied needle the uterus is punctured 3 cm below the right lower edge of uterine incision 3 cm from right lateral border. The suture is brought out from within the uterus puncturing at a point 3 cm above the right upper edge of the incision, 4 cm from the right lateral margin. The suture is now passed above the fundus 3-4 cm from right corneal border. Sutures can be fixed here so as to prevent the slippage of the sutures. The suture is pulled back posterior under moderate tension. It is now brought into the uterine cavity piercing the posterior uterine wall at the same surface points as that of anterior. The suture is then brought back to the posterior aspect of the uterus piercing the posterior wall 4 cm from its left lateral margin. It is passed round the fundus 4 cm from the corneal end. The suture is brought near the left side of the uterine incision in similar fashion as on the right side. With the assistant giving bimanual compression of the uterus the sutures are tightened. One has to confirm that the vaginal bleeding has stopped. Once it is confirmed that bleeding has stopped the uterine incision is closed as explained before.

This procedure will save the uterus from unnecessary hysterectomy. But this procedure will help only if bleeding reduces by bi-manual compression. This procedure can also be done in atonic PPH following vaginal delivery, but the uterus need to be opened as in lower segment caesarean section.

Uterine artery ligation: Ligation of uterine artery on both side will reduce the bleeding by 90%. Uterus is grasped and held to expose the vessels in the broad ligament. With vicryl 1/0 on a round bodied needle uterus is pierced 2 cm below the lateral end of the incision. The needle should pass though the full thickness of myometrium so that both uterine artery and vein should be included in the ligation. Then the needle is passed from behind through an avascular portion of broad ligament and tied anteriorly. Effective ligation will result in blanching of the uterus.

Uterine artery embolisation may be tried to occlude the uterine vessels. Meanwhile blood test for coagulation profile is done. Replacement of blood volume with packed cells and FFP is done.

b. *Injury to bladder, ureter, intestines:* Bladder wall may get opened while opening the peritoneum due to upward pull of the bladder as seen in prolonged labour or obstructed labour or previous history of caesarean section. It may also get injured while pushing the bladder away from the lower segment. When caesarean section is done in 2nd stage of labour, bladder is likely to be injured during extraction of the foetus. The damaged area is identified and sutured with vicryl 2/0 in two layers. Catheter is kept for 7-10 days.

Ureters are likely to get injured or ligated while suturing the uterine incision. This occurs quite commonly when the pelvic architecture is distorted as in previous surgeries. Complete ligation is rare. Ureter may get kinked due to placement of suture into the paraureteral tissue or partially ligated if the suture passes though its wall partially. When the ureters are kinked due to placement of suture in paraureteral tissue, ureterolysis is done; but one has to be assured that one stays out of the adventitia. If the ureters are partially or totally ligated, the ligatures are removed. Viability of the ureters is checked by looking for peristalsis, absence of blanching and discolouration. In case of doubt on viability, that particular segment is resected and re-anastomosed with 3/0 vicryl sutures. J-stent has to be kept *in situ* which is removed after 6-12 weeks through cystoscopy.

Intestine injuries are rare during caesarean section but do can occur. The caecum on right side and sigmoid colon on left may get injured. If injury is small it is sutured with 3/0 silk or vicryl with a drain in the peritoneal cavity. If the injury is large it requires diversion colostomy for sigmoidal injuries, ileostomy for caecal injuries. Though, these injuries are rare, prompt recognition and early treatment is very essential to prevent sepsis, fistula formation, renal failure and so on.

c. *Sepsis:* Infection in the urinary tract, lungs, abdominal wound, uterus, and peritoneum is known to occur. Usage of appropriate prophylactic antibiotics have reduced their incidence. Postoperative atelectasis (partial lung collapse) can sometime occur in CS. Postoperative peritonitis, wound dehiscence, burst abdomen is quite common, often associated with premature rupture of membrane, severe anaemia, poor nutritional status. The incidence of wound infection in caesarean section is high (2.5%—16%) which needs active management.

d. *Amniotic fluid embolism:* Though extremely rare, is known to occur which has 60—80% mortality. The amniotic fluid, foetal cells, hair enter maternal circulation through placental bed trigger an allergic reaction in the mother resulting in cardiorespiratory collapse and DIC.
e. *Anaesthetic hazards:* As most of the time when patient is taken up for emergency caesarean section, she is unlikely fasting for 6 hours.This can lead to aspiration of stomach contents especially when under general anaesthesia leading to atelectasis, aspiration pneumonitis.
f. *Thromboembolism:* Thrombus is more likely to occur in lower limb and pelvic veins. Common in obese patients. If gets dislodged and can precipitate pulmonary embolism. Therefore, proper hydration in postoperative period, and early ambulation is necessary.
g. *Shock:* Due to haemorrhage, amniotic fluid embolism or sepsis.
h. *Paralytic ileus* –Control of sepsis, maintenance of electrolyte balance is necessary.
i. *Intestinal obstruction—due to adhesions.*
j. *Poor healing of the uterine scar leading to scar dehiscence and rupture in future pregnancy or delivery.*
k. *Increased risk of placenta previa, placenta accreta, placenta increta, placenta percreta in future pregnancy necessitating hysterectomy.*

Fetal Complication

Respiratory distress, prematurity, birth injury while extraction are some of the common problems seen in the babies born by caesarian section.

CAESARIAN HYSTERECTOMY

It is the removal of uterus at the time of caesarian section.

Indication

- Abnormal placentation—placenta increta, placenta percreta, placenta accreta.
- Atonic PPH—when all other methods (both medical and surgical) of arresting the bleeding have failed.
- Rupture uterus—where the damage to the uterus is beyond repair.
- Carcinoma cervix diagnosed during pregnancy.

It can be called as *postpartum hysterectomy* if done immediately after vaginal delivery.

After caesarian section, once hysterectomy is decided, the surgeon has to inform the anesthetist and the patient's relatives. Patient's consent should be taken in planned hysterectomy. In emergency situation when the patient is not in a position to give consent, the consent of the patient's husband or the close relative is taken.

Precaution

Pelvic architecture is altered in pregnancy. So it may not be as easy as in non-pregnant uterus. Blood vessels are engorged and tortuous and tissues are edematous. So, careful clamping and ligating the pedicles is necessary. The vessels may otherwise retract leading to severe bleeding which may be difficult to control. The pelvic anatomy may get distorted in conditions like rupture uterus. Proper identification of the structures followed by their repair, and control of bleeding is very essential.

Incision

If it is a planned hysterectomy, midline vertical is ideal as it gives good exposure and also helps to access the upper abdomen. But most of the caesarian section is started with *Pfannenstiel incision* where most of the time the exposure is not adequate enough for hysterectomy. One may need to put a vertical incision converting it into an inverted T-shaped incision which gives a cosmetically bad scar and more postoperative pain. A transverse incision can be converted into a *Cherney incision* by transecting the rectus muscle at its insertion which can provide adequate exposure. An alternative approach is division of the rectus muscle converting a standard Pfannenstiel to a modified *Maylard incision.*

Procedure

The fundus of the uterus is grasped, removed from the pelvis and placed on the abdominal wall. The uterus should be kept under upward traction so as to diminish blood loss by constricting the uterine vasculature.

The uterine incision may be closed with single continuous sutures before proceeding to hysterectomy as this will reduce the bleeding. In atonic PPH uterus may be packed with sterile gauze so as to prevent continuous bleeding from placental site till the hysterectomy is complete. In abnormal placental attachment like placenta accreta, percreta, severe bleeding will occur by forceful removal of placenta. So cord is cut short and tied and proceeded with hysterectomy without removing the placenta. When the uterus need to be saved placenta may be left back with cord cut short covering with higher antibiotics and methotrexate. Placenta is known to disintegrate by autolysis.

Standard hysterectomy procedure is started with identification of round ligament. A self-retaining retractor may be placed to improve visualisation. Round ligaments are clamped with Kocher's clamps, ligated and cut on both sides. Care is taken to see that tips of the clamps lies on an avascular plane of broad ligament so as to avoid unnecessary bleeding. With electrocautery the anterior leaf of broad ligament is opened and proceeded medially to the point where the vesicouterine peritoneum was dissected off the lower uterine segment to create the bladder flap. In postpartum hysterectomy the vesicouterine peritoneum is opened along with the anterior leaf of broad ligament and the bladder is then pushed away and down from the lower uterine segment. Posteriorly, the broad ligament is incised laterally and parallel to the infundibulopelvic ligament to expose the retroperitoneum. The loose areolar tissue is carefully dissected parallel to the course of the ureter so as to allow proper visualisation of the retroperitoneal space and the course of the ureter.

An avascular area is identified in the posterior leaf of the broad ligament and perforated with electrocautery. Straight Kocher's clamp is placed on the cornu of the uterus, the utero ovarian ligament which attaches the adnexa (tubes and ovary) to the uterus are included in this clamp. A second clamp is placed lateral to this clamp, avoiding ovarian tissue. The tissue between the medial and lateral clamps is divided, and the pedicles are ligated by a transfixing suture using 1/0 vicryl or chromic catgut. Double ligation may be done to reinforce the first ligature. The lateral clamp is then removed. The clamp on the uterine cornu is left in place for traction and to control back bleeding. This procedure is repeated on the other side also.

Next, the uterine arteries are identified and ligated. The uterine arteries are palpable, grossly enlarged due to the pregnancy. The parametrial tissue surrounding the uterine vessels is delicately "skeletonised" anteriorly until the uterine arteries are identified. Curved clamps (Heaney or Kocher's) are placed such that the curved end is perpendicular to the vessels at the level of internal os. Care should be taken to see that the uterine artery is clamped properly and entirely. Some prefer to use two clamps but it is always better to use one to reduce the chances of ureteral injury. A straight clamp (Kocher's) may be applied on the medial aspect of the above clamp close to the uterus to prevent the back flow of blood from uterines when they are cut. The uterine artery is cut and ligated (double often) with 1/0 vicryl sutures. The suture is passed beyond the tips of the clamp and tied behind the clamp. A portion of the leaves of broad ligament is incorporated with the pedicle so as to prevent the retraction of the vessel. Alternatively, Haeney's ligature can be used to secure the pedicle. The curved clamp on the lateral aspect is removed. The procedure is repeated on the other side.

A second clamp may need to be placed medial to the previous pedicle moving down the parametrial tissue and hugging the cervix, which will allow ligation of any branches of the uterine artery not ligated with the first clamp.

Now decision is to be made whether to do a supracervical/subtotal hysterectomy or total hysterectomy. In emergency condition where the patient has bled a lot, further prolonging the surgical procedure is not suitable for her general condition; supracervical/subtotal hysterectomy is commonly done as a life-saving procedure. The uterus is amputated with a scalpel or cautery, cutting superiorly to the ligated uterine arteries proceeding medially and downward, thus allowing removal of an inverted cone of the cervix, which will facilitate approximation of the edges of the cervical stump regardless of the degree of dilation. Once amputated, the cervical stump can be approximated in an anterior-to-posterior fashion using interrupted figure-of-eight ligatures. Special care should be taken to avoid the bladder injury.

If the patient's conditions are favorable and when it is a planned procedure then total hysterectomy is done. But the problem here is identification of cervix. If the patient was in late stages of labour with cervix fully dilated and effaced it becomes difficult to identify it from vagina. Some surgeons prefer to "mark" the cervix, either by placing a ring forceps on the anterior lip of the cervix or placing a suture on the cervix. If total hysterectomy is decided then bladder has to be pushed further down. Extreme care should be taken as the bladder wall is extremely soft and friable and likely to get damaged. When the cervix is not dilated its level can be felt through the vaginal wall. The clamps are applied to the cardinal ligaments, cut and ligated. Sometimes, the uterosacral ligaments are quite prominent and may need to be individually clamped and ligated. Clamps need to be reapplied medial to the previous pedicle, and thus proceed downwards till the surgeon reaches the external os. Suture line approximating the uterine incision may be released now and the cervix can be palpated from within the uterus. Now the vagina is opened and cervix is amputated with curved scissors. Allis forceps can be used to maintain traction on the anterior, posterior, and lateral angles of the vaginal wall. The vaginal epithelium is very friable and must be handled gently.

Closure of vaginal cuff begins with supporting angle sutures that incorporate the lateral vaginal angles, the lower cardinal ligament pedicles, and the uterosacral pedicles. The vaginal cuff may be closed with continuous locking or interrupted sutures. Or the cuff may be left open putting continuous nonlocking suture to the anterior and posterior cuff edges to secure hemostasis which allows drainage of any discharge until spontaneous reperitonealisation occurs.

Pelvis is irrigated with warm saline. All pedicles are inspected for any bleeding. Vaginal cuff must be inspected for any bleeding. In supracervical hystectomy, amputated cervical stump is inspected for any bleeding. Cystourthroscope can be done per operatively to exclude any bladder or ureteric injury. Indigocarmine dye can be injected intravenously to the patient. Both ureteric orifices are visualised. Gush of blue dye through the ureteric orifices confirm ureteral patency. Also staining of the operative site indicates bladder injury which needs to be identified and closed with 2/0 or 3/0 vicryl in two layers. Continuous bladder catheterisation is done for 7-10 days. In case of placenta percreta there may be placental intrusion into the bladder wall. In such cases excision of that portion of the bladder wall with bladder wall reconstruction should be done by an urologist.

Abdomen is later closed after taking the count of instrument and mops.

Complications

a. Sepsis: Quite common. It can be in the pelvis, urinary tract, abdomen, or in the wound. Seroma, wound infection, cuff hematoma and cellulites, pelvic haematoma and abscess are often seen. It is due to excessive handling of the genital tract as it occurs in PPH, bleeding. Higher antibiotics have to be started before hand as the patient may quietly slip into septicemia.
b. DIC: It is mainly due to excessive bleeding that has lead to hysterectomy or due to sepsis. Transfusion of blood, platelets, FFP, and cryoprecipitate is done.
c. Deep venous thrombosis: Thrombosis in pelvic veins and leg veins are likely to occur with the risk of pulmonary embolism. Early mobilisation, use of compression stockings will reduce the risk of thrombosis.
d. Bladder injury/ureteric injury: If not identified and repaired can lead to vesicovaginal fistula and ureterovaginal fistula.
e. Psychological impact of hysterectomy in young women has to be dealt by proper counseling and support.
f. Prolonged hospital stay:

TUBAL STERILIZATION PROCEDURES

It is the procedure where the fallopian tubes are occluded so that the woman will not be able to conceive and become pregnant in the future. It is a permanent method of contraception normally done in women who feel that they have completed their family.

Approach: It can be done by minilaparotomy or along with caesarian section or by laparoscopic approach.

Timing: It can be done along with caesarian section as mentioned before or abortion (*concurrent*) or within 24-48 hours of normal delivery (*puerperal*) or any time after 3 months of delivery or abortion (*interval*). It is commonly done in the immediate postmenstual period.

Anaesthesia: It can be done under general or spinal anaesthesia or local anaesthesia (1% lignocaine infiteration) with IV sedation (Inj. Pethedine 50 mg + inj. Phenergan 25 mg).

Informed consent of the couple is taken after proper counseling regarding the irreversibility of the procedure and also informing about the chances of failure (due to tubal recanalization).

Procedure

Minilaparotomy

Patient is kept fasting for 6-8 hours. Abdomen is shaved. There is no compulsory bladder catheterisation. Patient is made to void urine just before the procedure.

Incision—When done in immediate postpartum period where the uterus is palpable below the umbilicus, the incision of ½”-¾” is made two fingers breadth below the fundal height; whereas in interval period it is done two fingers breadth above the symphysis pubis. It can be midline, paramedian or transverse incision.

The abdomen is opened in layers as usual. Once the peritoneum is opened small specialised retractors are used to retract the incision while delivering the tube out.

The surgeon now introduces his index finger into the abdomen, goes behind the uterus, feels for the tubes and delivers it out hooking it with fingers. An instrument inserted through the vagina to lift the uterus would be useful especially in interval sterilisation to draw the tubes towards the incision. It is identified by the fimbrial end of the tube. It is held with Babcock’s forceps at the junction of proximal and middle third portion **(Fig. 32-4)**.

Methods of tubal occlusion

- *Pomeroy tubal ligation*—Here part of the tube is elevated to create a loop or knuckle. An absorbable ligature (1/0 chromic catgut) is tied around the base of the elevated segment tightly, and the tubal segment (approx 1 cm) is cut out. The cut ends of the fallopian tube separate as the ligature dissolves. Within a few days, the peritoneum grows over and covers the cut ends of the tubal segments. It is the most commonly used method.
- *Madlener procedure*—Similar to the above procedure but here a loop of tube is elevated and crushed before ligation.
- *Parkland tubal ligation*—Involves tying two non-absorbable ligatures around the fallopian tube in its proximal to middle segment and then cutting out the tubal segment between the ligatures. The end result is similar to the Pomeroy method of tubal ligation.
- *Irving’s tubal ligation*—Two ligatures are placed around the fallopian tube in its proximal to mid-segment and the tubal segment between the two ligatures is removed. Using blunt dissection, a tunnel is made within the substance of the uterine myometrium on its posterior aspect and the proximal tubal segment is pulled into this tunnel and sutured. And the distal tied end is buried in the substance of the broad ligament.
- *Fimbriectomy*—A portion of the fallopian tube closest to the ovary is removed, thereby eliminating the tubal ability to capture eggs and transfer them to the uterus.
- *Bipolar coagulation*—This method uses electrical current to cauterise sections of the fallopian tube, commonly used in laparoscopic female sterilisation.
- *Tubal clip*—Involves application of permanent clip to the tube (*Filshie Clip or Hulka Clip*) thereby blocking the transference of eggs from the ovary.
- *Tubal ring*—Involves application of a silastic band to the fallopian tubes.

The last three procedures are used in laparoscopic tubal ligation.

Tubal ligation is done on both sides. The resected tubal segment is sent for biopsy. The peritoneum is closed by purse string suture. The abdomen is closed in layers. The patient can be discharged in 24-48 hours.

Complications

- Preoperative—Bladder injury, bowel injury, broad ligament haematoma, uterine perforation.
- Postoperative—Sepsis, wound infection, haematoma, peritonitis.

Laparoscopic tubal ligation: Usually done as an outpatient procedure.

Anaesthesia: General anaesthesia or local (done in camp).

Position: Patient is placed in lithotomy position, with 15° Trendelenburg tilt. Both abdomen and vagina is cleaned with antiseptic solution. Uterine sound can be inserted to manipulate the uterus **(Fig. 32-5)**.

Procedure: Through a small skin incision of ½”below the umbilicus, Verres needle is inserted into the abdominal cavity at a 45° angulation, tip directed towards the pelvis. The abdomen is inflated with gas (carbon dioxide). The needle is removed and trocar with cannula is introduced through the incision by twisting movement. Laparoscope is introduced through the cannula. The pelvic organs are visualised. Through another small incision laterally placed either on left or right side another trocar with cannula is inserted. Through this cannula either bipolar forceps or *ring applicator* loaded with silastic ring is introduced. Ring applicator needs no sized 7 trocar as ring applicator is 7 number sized. The tube is grasped 2-3 cm from uterotubal junction. It is either cauterised with the bipolar till 1 cm of the tube blanches or the silastic ring is slipped to the base of the loop of tube that was picked up and drawn into the cylinder of applicator. The procedure is repeated on the other side. The tubes have to be visualised to see that the rings are placed properly and there is no bleeding. After confirming haemostasis laparoscope is removed. Abdomen is deflated and skin incisions are sutured.

Complications

- Bowel and bladder perforation
- Vessel injury
- Cardiorespiratory embarrassment

SURGERIES FOR OVARIAN PATHOLOGY

Many ovarian tumours are cystic, but some cysts are not tumours and some tumours are not cysts.

Their simplified classification:

- *Benign:*
  - Functional cysts of the follicles and corpus luteum.
  - Benign serous or mucinous cystadenomas.
  - Dermoid cysts (teratomas)
  - Endometriotic cyst (chocolate cyst)
  - Unclassified benign cysts (simple paraovarian cysts).
- *Malignant*:
  - Malignant serous or mucinous cystadenocarcinomas.
  - Metastatic carcinomas (from the gut, or breast)
  - Burkitt's lymphoma
  - Other rarer tumours.



Figs 32-4(1)



Figs 32-4(2)

Figs 32-4(1 and 2): Tubectomy is done during caesarean section after taking consent.

Pseudocysts are postinflammatory collections of fluid between adhesions in the pelvis, and are not true ovarian cysts; but the distinction is not always easy, even at operation.

The *uterine adnexa* consist of the ovaries, the fallopian tubes, and the uterine ligaments and any pathology arising from these structures are referred to as *adnexal pathology*.

An adnexal mass may be noted in cases of acute abdomen and the differential diagnosis should include adnexal torsion, ruptured hemorrhagic cyst, degenerating leiomyomata, ectopic pregnancy, unruptured tuboovarian abscess.

Some of the surgeries performed in the ovaries are ovarian cystectomy, oophorectomy, ovarian drilling, salpingo-oophorectomy.

Ovarian Cystectomy

It is done in benign conditions where the cyst *only* is removed leaving behind the functional ovary in place. She needs its endocrine function, regardless of possible fertility. Of the benign cyst functional cyst, dermoid cyst and endometriotic cyst are commonly encountered in clinical practice.

Indication

Symptomatic cysts, cysts > 6 cm size in premenopausal women/>3 cm size in postmenopausal women not showing resolution in 2-3 months of close observation or failed to resolve with 2-3 cycles of oral contraceptive pills, cysts with ultrasonic features deviating from being functional cyst, and bilateral cysts are removed by cystectomy.

However cystectomy is not advisable in postmenopausal women with large cysts >10 cm size, complex cyst with multiloculation, thick septa and solid components, and cysts with elevated CA-125 levels.


Port positions for laparoscopic tubectomy - 10 mm camera; tuberectomy port
Ring applicator - tip with rings in position ready for firing
Ring applicator - tip with rings in position ready for firing
Fallopian tube
Rings applied on right side
Rings applied on left side
Port site closure

Fig. 32-5: Laparoscopic tubectomy/sterilisation.

Anaesthesia

General or spinal for laparotomy with cystectomy, general anaesthesia for laparoscopic cystectomy.

Position

Dorsal lithotomy for laparoscopic cystectomy as it allows the use of uterine manipulator; supine position for laparotomy.

The abdomen, perineum, and vagina are surgically prepared.

Technique of Cystectomy by Laparotomy

In postmenopausal age or above it should be an infraumbilical midline incision for adnexal masses as the incidence of malignant disease is high in this age group and lower midline incision will give adequate access and exposure than the low transverse though it is cosmetically poor. Adequate exploration of the abdomen for a malignant ovarian process through a Pfannenstiel or transverse incision is difficult. A transverse incision or Pfannenstiel incision is adequate for younger patients in whom the chance of a malignant disease is quite low. If a malignant disease is encountered in this younger age group, the transverse or Pfannenstiel incision may be converted into inverted T incision.

After opening the peritoneum the abdomen is thoroughly explored. Any suspicious tissue in the upper abdomen (under surface of the diaphragm and surface of the liver) or along the aortic lymph nodes should be sent for a frozen section analysis. Ascites or any peritoneal deposits or papillary excrescences on ovarian surface are noted. In the presence of any of these features cystecomy is abandoned.

Uterus is pulled up towards the incision. Ovaries are indentified. Most ovarian cysts have few adhesions and can be easily drawn towards the incision. If adhesions are seen then it may be due to previous PID, malignant cyst in which the growth has already spread into the peritoneum, endometriotic/chocolate cyst, a cyst which has previously undergone torsion.

Cul-de-sac is packed with moist pack to prevent the pelvic contamination if there is a spill. The ovary is held with Babcock clamps placing on the ovarian ligament. An elliptical incision is made with a scalpel through the thin ovarian cortex of a benign cyst the end of the knife handle can be inserted and develop a plane between the cyst wall and the ovarian cortex. Alternatively, fine-needle electrocautery or small Metzenbaum scissors can be used to separate the cyst wall from the ovarian cortex. After the cyst wall has been completely separated from its adherent attachments to the thin ovarian cortex, it can be shelled out without rupture. If proper plane is got, shelling out the cyst will be without difficult except near the base which needs to be cut with cautery or scissors. However, because of the friability of the cyst wall, rupture can occur even with the gentlest technique. So instead of having accidental rupture which will uncontrollably soil the peritoneal cavity, it is better to aspirate the cyst before shelling out its capsule. Aspiration of cyst will also facilitate the removal of large cysts through small incision and also it eases to release the paraovarian adhesion before cystectomy **(Fig. 32-6)**.

After the cyst has been removed, the dead space can be obliterated with fine 5/0 nonreactive vertical mattress sutures or figure-of-eight sutures. The ovarian surface is then re-approximated with 5/0 fine subcortical running suture. Interrupted sutures may be placed if cortex is friable. Alternatively the redundant cortex can be removed and the dead space is obliterated with an internal closure taking care that suture material does not penetrate the ovarian cortex. This prevents ischemia and adhesion formation. Some authors advocate leaving the ovary open after cystectomy.

Difficulties Encountered in Cystectomies

Extensive adhesions may be encountered in endometriotic cyst, post inflammatory cyst where the ovary cannot be freely moved above the pelvis. Forceful attempt to pull the ovary may injure the bladder, rectum, ureter and lacerate the veins. Adhesions have to be released slowly with both sharp dissections with scissors or gently with hands. In endometriotic cyst the thick chocolate coloured fluid is aspirated and sucked out, the friable cyst wall is removed as much as possible. Haemostasis is achieved with diathermy. Post inflammatory cyst is just aspirated and abdomen is closed giving her antibiotics. It is safer to leave a little cyst wall on her gut or the bladder, than to remove a little gut or bladder with the cyst wall.

Before closing the abdomen it is always good to give a thorough peritoneal cavity wash with saline so as to wash out the spilled cyst content. Abdomen is closed in layer. Usually no drain is required **(Fig. 32-7)**.

Complications

- Removal of large cyst may cause cardiorespiratory failure in immediate postoperative period.
- Supine hypotension syndrome while removal of large cyst due to its pressure over the veins, this can be prevented by giving lateral tilt during the surgery.
- Injury to bladder, ureter, bowel in presence of dense adhesions.
- Infertility due to adhesion.



Fig. 32-6: Bilateral large ovarian cysts are removed through laparotomy.



Fig. 32-7: Specimen of simple cyst of the ovary.

Laparoscopic Cystectomy

This is becoming very popular now as adhesions are less, so fertility will not be affected much. Postoperative recovery is faster. Endometriotic cysts are better tackled with laparoscopy than laparotomy.

Port site—periumbilical for telescope and camera. Two lateral port in the lower abdomen, one 5 mm another 10 mm. Additional ports can be used based on the requirement.

The ovarian capsule is incised with scissors or monopolar hook. The ovary is stabilised with a contralateral grasping forceps holding the suspensory ligament. The ovarian capsule is dissected/teased away from the cyst wall either by hydrodissection or a probe. Cyst is thus completely freed from the ovary. Bleeding points on the ovarian cortex is cauterised with bipolar forceps. The cyst sometimes ruptures while dissecting away from the ovarian capsule. The fluid can be aspirated and thorough wash to the pelvis is given later **(Figs 32-8 and 32-9)**.

Alternatively in case of large cyst, it has to be aspirated by passing a 18 guage needle through a trocar. Fluid is aspirated with 20 cc syringe or aspiration system. Fluid is sent for analysis. Pelvic wash is given. After draining the fluid, hole is made in the capsule of the ovary. The cyst wall is pulled away from the ovarian capsule. Contralateral traction is given with 5 mm grasping forceps. Complete capsule can be removed if the right plane is achieved. There may be some adhesions near the base which needs to be separated with monopolar hook or scissors. Resected area is thoroughly irrigated. Any bleeding points are coagulated with bipolar forceps. If stripping of the capsule cannot be achieved completely as in endometriosis, the residual part must be destroyed with laser or electrocautery. Suture of the margins are reserved for large cysts or when more than incision is done. This will restore the shape of the ovary thereby reducing adhesion **(Fig. 32-10)**.

The resected cyst wall is removed through 10 mm trocar. If the cyst is intact without rupture, a plastic bag may be inserted into the peritoneal cavity so that the cyst may be passed into it and retrieved though a small suprapubic incision or through an incision over the pouch of Douglas. Alternatively the cyst when inside the bag can be aspirated and the size reduced so that it can be brought through the 10 mm trocar **(Fig. 32-11)**.

Oophorectomy

Oophorectomy is the surgical removal of an ovary or ovaries. Some call it also as *ovariectomy*, but this term has been traditionally used in basic science research describing the surgical removal of ovaries in laboratory animals.



Fig. 32-8: Laparoscopic removal of simple cyst of the ovary.



Fig. 32-9: Laparoscopic chocolate cyst removal.

Indication:

- Ovarian diseases—ovarian cyst, cancer
- Endometriosis
- As prophylaxis to reduce the chances of developing ovarian cancer or breast cancer
- In conjunction with removal of the uterus **(Fig. 32-12)**

Procedure:

Informed consent of the patient is a must before the ovary is removed.

Anaesthesia, exposure, positioning as in ovarian cystectomy.

The pedicle consists of the infundibulopelvic ligament and ovarian vessels, the ovarian ligament, and portion of the broad ligament. If the pedicle is wide clamp it with several clamps, taking bite not more than 2.5 cm in each of them. It will be less likely to slip if the pedicle is cut at some distance from each clamp. The pedicle in each clamp is transfixed with 1/0 vicryl sutures, taking care to avoid the plexus of veins when the needle is inserted. The stump is checked for any bleeding before cutting the ligatures short. Ovary thus removed is sent for biopsy. It is sometimes done on both sides **(Fig. 32-13)**.

Laparoscopic Oophorectomy

The ovary is stabilised with a grasping forceps over the ovarian ligament from contralateral port. The infundibulopelvic ligament is cauterised with bipolar forceps and cut with scissors. Alternatively harmonic scalpel or seal can be used. The ovarian ligament is cauterised and cut. The ovary can be retrieved using a plastic bag through 10 mm portal site.


Uterus
Gangrene ovary due to torision
Derotation of twisted pedicle

Fig. 32-10: Gangrene ovary due to torsion of ovarian cyst; it is removed through laparoscopy.



Fig. 32-11: Twisted ovarian cyst showing the twisted torsion pedicle.

Complications

- Greater risk of cardiovascular disease
- Increased risk of osteoporosis and bone fractures
- Significantly impairs sexual well-being
- Libido loss, difficulty with sexual arousal, and vaginal dryness
- Parkinsonism
- Decline in psychological well-being.

Salpingo-oophorectomy

It is removal of tube with along the ovary. It may be a unilateral procedure or bilateral which is often combined with hysterectomy.

Indication:

- Benign adnexal mass
- Adnexal torsion
- Tubo-ovarian abscess and pelvic inflammatory disease.
- Ectopic pregnancy
- Endometriosis
- Removal of normal appearing ovaries and tubes at the time of hysterectomy for benign disease, to decrease the risk of development of ovarian pathology in future and so the need for any procedures.


Twisted ovary
Pedicle clamping
(Kocher's)

Fig. 32-12: Gangrene ovary with torsion of the cyst.



Fig. 32-13: Ovarian pedicle after removal of ovary.

- Malignancy—Ovarian cancer, uterine cancer, or metastases to ovaries from a distant primary malignancy (gastrointestinal, breast, lung carcinoma)
- Removal of ovaries and tubes in women genetically susceptible to ovarian cancer.

Sometime there may be extensive adhesions between tubes and ovary that it necessitates its removal with the ovary.

Procedure:

Approaching from below and behind, any adhesions between the ovary and broad ligament is carefully divided. Tube and ovary are raised and the infundibulopelvic ligament is identified. Ureter has to be identified before clamping the infundibulopelvic ligament so as to avoid injury to it. The IP ligament is clamped with 2 curved Kocher's clamp. It is cut between the two clamps. The pedicle is transfixed and ligated with 1/0 or 2 zero vicryl suture. Next ovarian ligament and uterine end of the tube is together clamped, cut and ligated **(Figs 32-14 and 32-15)**.

Complications

- Injury to ureter especially when there is severe adhesion as in endometriosis, PID.
- Injury to colon on left side while ligating the IP ligament.

MYOMECTOMY

Myomectomy is removal of myomas from the uterine wall. It may be intramural, subendometrial or subserosal. It causes infertility. Myomectomy is part of the treatment for infertility often.

Myoma can be removed either by open or laparoscopic method. Laparoscopic myomectomy needs more skill than laparoscopic hysterectomy.

Open Myomectomy

Bladder catheterisation is done. Patient with head down position is better to displace the bowel from the pelvis. It is done through Pfannenstiel incision. Site and size of the myomas should be assessed by preoperative imaging. Uterus is delivered/brought out of the abdominal wound. Often vasopressin injection into the uterus may be injected to reduce the bleeding; but its complications should be taken care of. Incision is made on the surface of the uterus directly on the myoma site. Myometrium is carefully separated using monopolar cautery or using no. 15 blade. Bleeding should be controlled. Well capsulated whitish yellow coloured myoma can be identified. Myoma screw is passed into the myoma which is manipulated to pull out the myoma off the uterine wound. Cautery, ligasure will also help from separating it from deeper plane. Once myoma is removed, bleeding points are fulgurated using bipolar cautery. Finger is inserted to confirm that endometrium is injured or not. If endometrium is injured it is sutured with 2 zero vicryl sutures. Myometrium is also sutured using 2 zero sutures. Parametrium is sutured similarly **(Fig. 32-16)**.

Laparoscopic Myomectomy

Bladder catheterisation should be done. It is done under general anaesthesia with head down and lithotomy position. 10 mm supra-umbilical camera port is placed; 10 mm working port on one side in the iliac fossa; another 5 mm on the opposite iliac fossa; one more 5 mm port on the right side above the earlier 5 mm port which is used for myoma 5 mm screw to pass. Incision is made on the uterus on the myoma site using monopolar cautery. Once glistening avascular myoma capsule is identified, laparoscopic myoma screw is inserted into the myoma. Using the screw myoma is manipulated gently, gradually and progressively to retrieve it from myoma bed in the uterine wall. Bleeders should be addressed using ligasure or harmonic scalpel or bipolar cautery. Uterine wall is sutured with intracorporeal suturing. Difficulty is identifying the endometrial tear and suturing it. If difficulty arises conversion should be done. Absolute haemostasis should be achieved.

HYSTERECTOMY

It is operative removal of the uterus. It is the most common gynecological surgical procedure.

Indications

Benign condition	*Malignant condition*
• Dysfunctional uterine bleeding	• Cervical intraepithelial neoplasia
• Fibroid and adenomyosis	• Cancer of endometrium, ovary, fallopian tube
• Bilateral ovarian cyst	• Gestational trophoblastic disease.
• Post menopausal bleeding	
• Endometriosis	
• Pelvic inflammatory disease	
• Pelvic organ prolapse	
• Obstetric causes like postpartum haemorrhage, rupture uterus, abnormal placentation	


Cleaning
Draping
Pfannenstiel incision
Anterior rectus sheath
Anterior rectus sheath is opened horizontally
Rectus muscle
Upper leaf of the rectus sheath is reflected upwards
Lower leaf of the rectus sheath is reflected downwards
Recti are retracted laterally from midline to expose the peritoneum
Peritoneum is opened from above downwards

Figs 32-14(1)


Ovarian cyst
Cyst pedicle
Pedicle is partially twisted
Derotated pedicle
Ovarian cyst/neoplasm
Dissecting the pedicle
Infundibulopelvic ligament
is clamped using Kocher's clamp
Tranfixation ligation using 2 zero vicryl
Applying Kocher's clamps on the
Fallopian tube on the uterine side
Uterus
Pedicle divided

Figs 32-14(2)


Tube ligation on the uterine side
Peritoneal closure-
continuous vicryl suture
Seargeant retractor
Closed peritoneum - from above downwards
Closure of the rectus muscle
Closure of rectus sheath using
monofilament nonabsorbable suture

Figs 32-14(3)


Subcutaneous tissue closure
Subcuticular skin closure using monocryl
Specimen - dermoid cyst of ovary - other side ovary is normal histology - benign dermoid cyst

Figs 32-14(4)

Figs 32-14(1 to 4): Salpingo-oophorectomy for benign dermoid cyst of the ovary—technique.



Fig. 32-15: Krukenberg tumour of the ovary.

Types

Total hysterectomy—uterine corpus with cervix removed.

Subtotal hysterectomy—only uterine corpus removed retaining the cervix.

Panhysterectomy—uterine corpus, cervix along with bilateral tubes and ovaries removed.

Radical hysterectomy—total hysterectomy, bilateral salpingo-oophorectomy, along with removal of parametrium, upper 1/3rd vagina and pelvic lymph nodes.

Routes of Removal

Uterus can be removed via abdominal, vaginal, or laparoscopic route.



Fig. 32-16: Myomectomy – specimen – large and multiple.

Choice of this route depends on the uterine size, presence of pelvic pathology, uterine descent. Uterus up to 12-14 weeks size, with slight descent, with absence of any pelvic pathology like endometriosis, PID, pelvic adhesions due to previous surgeries, with absence of cervical hypertrophy/fibroid can be safely and effectively removed by vaginal route. Vaginal hysterectomy is less morbid and cost effective than abdominal hysterectomy. A diagnostic laparoscopy will clarify the situation and may allow the procedure to be converted to a laparoscopically assisted vaginal hysterectomy (LAVH).

Need of Oophorectomy During Hysterectomy

It is decided on the age of the patient, and gross structure of the ovary. *Prophylactic oophorectomy* is the term used for removing clinically normal ovaries, often done in postmenopausal women or in women aged > 45 years to prevent the development of any ovarian pathology in future. Young women < 45 years with normal looking ovaries can be left behind.

Disadvantages of oophorectomy:

- Menopausal symptoms which may be so severe that may require HRT.
- Risk of osteoporosis, atherosclerosis, coronary thrombosis increases.

Advantages: Risks of developing ovarian cancer, cysts are reduced.

Anaesthesia

Can be done under general/spinal anaesthesia. However spinal anaesthesia is preferable for vaginal hysterectomy.

Abdominal Hysterectomy

Technique: The patient is placed in supine or modified lithotomy position with legs supported by the Allen universal stirrups. The latter position favours access to vagina. The vagina and perineum are cleaned with antiseptic solutions. Indwelling Foley catheter is inserted. A pelvic examination is routinely performed under anaesthesia. This examination helps to delineate the existing pathology and also in selection of the type of incision. The abdomen is then cleaned from the anterior thighs to the xiphoid with antiseptic solutions. Sterile drapes are applied.

Incision: Abdomen is opened either by a low transverse, Pfannenstiel (mostly preferred), or infraumbilical-midline/paramedian (when good exposure is required) incision.

Once inside the peritoneal cavity, the abdomen is explored and pelvic pathology is carefully evaluated. The surgeon should examine the appendix for any pathology. The upper abdominal organs, including liver, gallbladder, stomach, under surface diaphragm, and omentum should be palpated for any pathology. The retroperitoneal nodes in the pelvic and paraaortic area should be palpated. Mild Trendelenburg position will help in keeping the bowel out of the operative field **(Figs 32-17 and 32-18)**.

A self-retaining retractor may be used to retract the lateral abdominal flaps. The bowel packed superiorly with warm wet packs to afford good exposure of the pelvis. Any adhesions of the small bowel or rectosigmoid may need to be divided at this time so that the bowel can be mobilised out of the operative field. The uterus is elevated out of the pelvis with pair of Kocher's clamp applied on the uterine cornual end on each side which grasps the isthmic portion of fallopian tubes and mesosalpinx. Bilateral clamps in this position will allow for elevation, traction, and rotation of the uterus. Uterine mobility is restricted in cases of extensive inflammatory disease, endometriosis, malignancy, or very large fibroids, but uterine mobility is satisfactory in most benign conditions. Bilateral tubes and ovaries are carefully examined for any pathology **(Fig. 32-19)**.



Fig. 32-17: Tissue forceps commonly used to hold the rectus sheath while raising the flap upwards.



Fig. 32-18: Doyen's retractor is often used in pelvic surgeries.

If the ovaries and tubes are healthy then *total hysterectomy* is done. The uterus is pulled to one side so that the opposite ovary and tubes are stretched and exposed. The round ligament is clamped midway with a pair of Kocher's clamp, divided and the clamps are removed after ligating with 1/0 vicryl sutures. This opens the retroperitoneal space, which is almost always a free space for blunt dissection, even in the patient with extensive tumor, inflammatory disease, or endometriosis. The loose areolar tissue of the retroperitoneum is divided with the index finger and the tip of the suction or the back of a tissue forceps. The external iliac artery on the medial surface of the psoas muscle is identified. Blunt dissection is done to expose superiorly to the level of the bifurcation of the common iliac artery. At this junction the ureter always crosses the pelvic brim and is identified easily. The internal iliac or hypogastric artery entering the pelvis at this location, parallel to the ureter is also identified. Identification of ureter and its course will prevent its injury during clamping and ligating of pedicles. This is especially important when pelvic anatomy is distorted as in pelvic inflammatory disease, endometriosis and malignancy. A window is made by sharp or blunt



Figs 32-19(1)



Figs 32-19(2)



Figs 32-19(3)

Figs 32-19(1 to 3): Technique of open hysterectomy.

way in the peritoneum beneath the fallopian tube between the uterus and ovary. A Kocher's clamp is used to clamp the tube and utero-ovarian ligament, its tip should lie in the window created in the peritoneum. The clamp that was initially placed at the corneal end of the uterus acts as a back clamp. The tube and utero-ovarian ligament are divided between the clamps and the pedicle is ligated twice. The procedure is repeated on the other side.

In *panhysterectomy* where the ovaries and tubes are to be removed, a hole in the peritoneum between the ureter and the ovarian vessels is made under direct vision. The ovarian vessels in the infundibulopelvic ligament are clamped with Kocher's clamp. A second back clamp is placed distally and the ovarian vessels are divided between the two clamps. Dissection done in the retroperitoneum will avoid the injury to ureter at this junction. The pedicles are transfixed and ligated with 1/0 vicryl sutures. The procedure is repeated on the other side also.

The uterus is now pulled upwards and backwards. Utero-vesical fold of peritoneum is exposed and is divided with sharp scissors just inferior (5 to 10 mm) to its attachment to the lower uterine segment. At this junction peritoneum is usually mobile, and this peritoneal division is carried from one side round ligament to the other. An avascular plane of loose areolar tissue can be identified between the posterior bladder wall and the anterior cervix. By giving constant upwards traction on the uterus and peritoneal fold of the bladder, the bladder is dissected away from the cervix either by sharp dissection with scissors or by blunt dissection with a gauze held with an Allis forceps. Care should be taken to see that scissors should rest lightly on the fascia overlying the cervix and this dissection should take place over the cervix avoiding to go far laterally as one may encounter bleeding due to injury to uterine vessels. With the thumb of one hand in front and fingers of the other behind the uterus the extent of this bladder dissection below the cervix is determined. As the bladder is advanced below the cervix, the thumb in front and the fingers behind come into closer opposition as they now have only the vaginal wall between them. Posteriorly, it is not necessary to dissect the rectum off the posterior cul-de-sac; but if adherent and prevents good exposure, it should be dissected free slightly by blunt dissection after the uterine vessels have been divided. The posterior peritoneum between the uterosacral ligament beneath the cervix is incised. By blunt dissection with fingers in the avascular plane which exists between the rectum and posterior cervix/vagina, will push the rectum backwards away from the operative field.

Next step is a crucial step of hysterectomy which is the ligation of uterine vessels. Any improper ligation or slipping of ligatures will cause the vessels to retract and result in torrential bleeding. Blind catching of the vessels with a hemostat in an attempt to stop bleeding will likely to damage the ureter that traverse close by. Uterus is pulled sharply to one side, and the loose fatty tissue adjacent to the lateral lower uterine segment on the opposite side is dissected. The uterine artery is usually found immediately adjacent to the uterus at the level of the internal cervical os. Skeletonising the uterine artery and vein allows them to be clamped more accurately. Less adjacent tissue means a smaller vascular pedicle, which allows more precise and more secure ligation. However excessive attempts to isolate the vessels may produce unnecessary bleeding. The exposed vessels are clamped with Heaney or Kocher's clamp adjacent to the uterus. The clamp must be applied at right angles to the vessels. A second clamp can be placed above the first for added safety. If the uterus is small, no back clamp is required. The uterine vessels are cut with scissors or a knife and the pedicle are doubly ligated with 1/0 vicryl sutures. The procedure is repeated on the opposite side.

It is once again made sure that the bladder anteriorly and the rectum posteriorly have been freed from the cervix. Giving upward traction on the uterus, the deeper portions of the broad ligament is exposed. By using a retractor bladder is retracted away and downwards and thereby pull the lower uterine segment away from the ureter. A straight Heaney or Kocher's clamp is now applied over the remaining portion of the broad ligament/parametrium close to the lateral portion of the cervix. Giving traction on the uterus towards opposite side, the cervix is freed from the parametrium with scissors. By staying close to the cervix the risk of damaging the ureter is minimised. The clamps are removed after transfixing and ligating the pedicles with 1/0 absorbable sutures. Procedure is repeated on the opposite side. Maintaining good exposure, one or two pedicles are tied on each side, and then the procedure is repeated on the opposite side until the level of the cervico-vaginal junction has been reached. Once again, the bladder and rectum are checked and advanced if necessary to be sure that they are well clear off and the anterior and posterior vaginal walls are exposed. Haeney's clamps are then applied across the vagina below the cervix from either side, which should include the base of the cardinal ligaments laterally, the uterosacral ligament posteriorly, and anterior and posterior vaginal wall. With a knife or heavy, sharply angled scissors the vagina is divided above these clamps and below the cervix. This is closed technique of removing the cervix from the upper vagina which decreases the chance of spillage of vaginal contents into the abdomen. This technique decreases the risk of infection and the formation of symptomatic granulation tissue at the vaginal apex. Alternatively vagina may be opened by a stab incision with a knife below the cervix over the anterior vaginal wall and is cut circumferentially under direct vision. Full thickness vaginal edge is held with Allis forceps. Uterus thus removed is placed in a tray. Gauze may be introduced into the vagina from above and the vagina is cleared of clots. The lateral clamps are removed after transfixing and ligating the pedicles. Inclusion of the uterosacral and cardinal ligament in this pedicle provides excellent support of the vaginal apex. The vagina is closed with interrupted sutures or continuous locking 1/0 vicryl sutures.

Pelvis is irrigated with warm saline; the pedicles are inspected carefully to be sure that haemostasis is achieved. Cautery or excessive suturing at the bladder base should be avoided as it may predispose fistula formation because of necrosis. Any bleeding areas at the uterine vessels or cardinal ligament should be grasped with an Allis clamp and resutured within the suture line. The pelvis is not reperitonealised. New mesothelium arises from the subperitoneal connective tissue cells and occurs simultaneously in all exposed areas independent of the size of the defect. Attempts to cover areas of peritoneal injury may lead to increased adhesion formation at the sites of reperitonealisation by preventing autolysis of early fibrinous attachment and introducing reactive responses to suture material. The packs and retractor are removed. The anterior peritoneum is closed with delayed absorbable suture to prevent the development of future incisional hernia. The abdomen is closed in the usual way.

Difficult Hysterectomy

Difficulties are encountered in severe pelvic endometriosis, PID, malignancies large myomas where the pelvic anatomy is distorted. Dense adhesions cause great restriction in uterine mobility. By sharp dissection with scissors and blunt dissection with hand the adhesions are to be released and proceeded. In large cervical myomas the bladder may be pushed upwards into the abdomen which is likely to get injured while opening the peritoneal cavity. Often ureter may lie close to the myomas due to distortion of the anatomy. In cases of pelvic endometriosis or previous caesarian section it may be difficult to separate and advance the bladder from the cervix. In some cases adhesions are so extensive that an attempt to remove the cervix may cause trauma to bladder, rectum and ureter. In such cases one may have to resort to *subtotal hysterectomy* **(Fig. 32-20)**.

The *technique of subtotal or supracervical abdominal hysterectomy* is similar to abdominal hysterectomy until the ligation and clamping of uterine vessels. Care should be taken to see that the bladder and rectum have been advanced far enough so that the cervix can be clearly visualised both anteriorly and posteriorly. Upward traction is given to the uterine fundus and with electrocautery the cervix is cut anteriorly just above the level of uterine artery ligation. A shallow V-shaped incision is made on both anterior and posterior aspect until the uterine fundus is excised. Figure-of-eight sutures are used to close the upper endocervix in a hemostatic fashion. The top of the cervix is checked for any bleeding, and this cervical stump may be covered by the bladder peritoneum to minimise the risk of adhesions **(Fig. 32-21)**.

Postoperative Care

Foley's catheter inserted for bladder drainage is removed after 24 hours. Patient is hydrated with IV fluids for 24-48 hours. Once the normal bowel movements gets resumed oral diet is started. Parenteral antibiotics given for 48 hours, later switched over to oral preparation. Analgesics to control pain, initially inj.pethidine (50 mg) + phenargan (25 mg) later tramadol and paracetamol. Patient is motivated for early ambulation and respiratory exercise to avoid pneumonia and deep vein thrombosis. Skin suture are removed anywhere between 7th-10th postoperative day. If bilateral ovaries are removed in a young patient she may require hormone replacement therapy for certain period. Normal activities can be resumed in 2-3 weeks. Patient is advised to avoid lifting heavy weights and intercourse for 4-6 weeks. Driving and travelling can be resumed once the pain has completely reduced. Patient should consult the physician if there is any vaginal bleeding, fever, persistent nausea /vomiting, increase pain out of proportion to the postoperative period.

Complications of Hysterectomy

Intraoperative Complication

Ureteric injury: Common sites of ureteral injury during abdominal hysterectomy include the infundibulopelvic ligament where the ovarian vessels are ligated; the area of the uterine artery ligation and at the bladder base. It is wise to expose the ureter in the retroperitoneal space so that its injuries can be avoided. Despite proper precaution if there is a doubt of ureteric injury, *indigocarmine* dye is injected intravenously. Its spill through the ureteric orifices is seen either through cystoscopy or by making an incision over the dome of the bladder.

Bladder injury: Bladder may be unusually drawn up into the abdomen by large pelvic tumors, adhesions due to previous surgery leading to its injury while opening the peritoneum. Bladder may sometime be unusually adherent to the cervix due to previous caesarian section or pelvic endometriosis. So while advancing the bladder off the cervix or upper vagina its muscle fibres may get torn up. Apart from trigonal injuries bladder injury is repaired by 2 layer closure of continuous 3/0 vicryl sutures. Trigonal injuries are dealt by the urologist. Continuous bladder drainage by indwelling Foley's catheter for 7 days is done.

Haemorrhage: Often bleeding occurs from the slipping/loosening of ligatures from ovarian or uterine pedicles. Bleeding is also encountered near the bladder base. Blind application of haemostat should be avoided. Firm pressure is applied with a warm wet mop. By slowly releasing the pressure the bleeding vessel is identified,


Even though pfannensteil incision is ideal for open hystrectomy, in very large uterus midline incision is preferred which gives adequate exposure
Urinary catheter should be in place
Fallopian tube is divided, here ligasure is used otherwise suture ligation using vicryl is done
Infundibulopelvic ligament is divided-ligasure or transfixation ligatures (doubly)
Utero-ovarin ligament is divided-ligasure or double transfixation. Here opposite side ovary was retained.
Uterus
Tube
Ovary
Fimbria
Kocher's clamp is used

Figs 32-20(1)



Ligasure division of the utero ovarian ligament

Dealing uterine artery pedicle-ligasure or double transfixation

Urinary bladder is pushed and dissected downwards to expose proximal anterior vaginal wall

Dealing M'cenrodt ligament using ligasure or tranfixation by 2 zero vicryl

Transfixation of the uterine pedicle additionally

Opening the vault anteriorly using no 11 blade suctioning should be done

Bleeders are ligated

Figs 32-20(2)



Ligated pedicles
Vaginal opening above
Completed vault closure
Completed vault closure

Vault is closed using continuous locking sutures by 2 zero vicryl suture

Gelfoam may be placed on the vault if needed.
Usually peritonealisation is not required

Figs 32-20(3)

Figs 32-20(1 to 3): Hysterectomy for a large uterine tumour through midline incision.



Fig. 32-21: Endometrial carcinoma specimen after hysterectomy.

clamped and ligated with suture. Bleeding from small vessels can be cauterised with electrocautery. Bleeding from denuded surface can be controlled by pressure, or application of topical agents like thrombin/collagen.

Bowel injury: Bowel injuries do can occur when there are extensive adhesions in the pelvis due to endometriosis, malignancy, pelvic inflammatory disease. When the defects are small not involving the mucosa in small bowel, it is closed with single layer of continuous/interrupted 3/0 silk sutures in direction perpendicular to the intestinal lumen. If the defect is large than resection and anastomoses is done. In rectum and sigmoidal injuries, if the defect is small not involving the mucosa it can be closed in similar fashion to small bowel. Large defect involving the mucosa requires diversion colostomy along with primary repair.

Postoperative Complication

a. *Hemorrhage*—It is a serious postoperative complication. It may present with vaginal bleeding or change in vital signs like, tachycardia, pallor, tachypnoea, hypotension some with a palpable mass over the abdomen. Fluids are transfused. Blood transfusion should be done. When vitals are stable then the patient is shifted to operation theatre and examined for any bleeding from the vaginal vault. If it is from the raw vaginal edges one or two re-enforcing stitches over the vault will stop the bleeding. In the absence of any vaginal bleeding and the patient's vitals are not satisfactory, and then exploratory laparotomy is done keeping enough points of blood ready for transfusion. The bleeding vessel is identified and ligated. Sometimes there may not be a intraperitoneal bleeding but from torn and retracted inferior epigastric vessels of the abdominal wall.

b. *Sepsis*—infection may be at the wound site, intraperitoneal, urinary tract, vaginal vault, lungs. *Wound infection* is the most common form of sepsis. Anaemia, poor nutrition, preoperative sepsis, malignancy, ineffective haemostasis leading to haematoma are some of the predisposing factors. Infection may be superficial to the rectus sheath or may be deep to it involving all the layers. It may involve full length of incision or restricted to a small segment. When all the layers are involved the wound may disrupt suddenly leading to burst abdomen which needs to be treated as an emergency. Under anaesthesia resuturing is done. In case of superficial infection it may lead to many discharging sinuses. The wound needs exploration under cover of higher antibiotics. Secondary suturing with deep mattress sutures using ethylon 2/0 is done which is removed only after 2 weeks. Mild superficial infection can be treated conservatively with antibiotics and regular dressing though it gives a bad scar.

   Fever in postoperative period can be due to urinary sepsis, pneumonia, bacteraemia, thrombophlebitis. Blood, urine are sent for culture. Chest X-ray is taken. Postoperative ultrasound will help to know any fluid collection in pelvis and abdominal cavity. Antibiotics are changed suitably. Sometimes the collection may localise in pelvis forming a pelvic abscess which may need to be drained vaginally. By thrusting an artery forceps followed by finger through the vault will help to drain the pus from the pelvis.

   Peritonitis though rare, do can occur following bowel injury or due to retained foreign body like gauze/mops. Ultrasound abdomen or CT scan is done. Some patient may require relaparotomy if bowel injury or retained foreign body is suspected.

   Pneumonia—quite common in elderly, obese ladies and those with history of chronic bronchitis. Postoperative respiratory exercises will help to prevent this.

c. *Oliguria/anuria*—in the presence of normal blood pressure, one should suspect ureteric ligation. Postoperative ultrasound will help to confirm this. Emergency nephrostomy may be done later, followed by exploration and reimplantation of the ureter.

d. *Paralytic ileus, intestinal obstruction*—electrolyte imbalance, sepsis are known to cause paralytic ileus. Proper hydration, higher antibiotics, nasogastric aspiration with Ryles tube will help to restore the bowel function normally. Persistent vomiting with colicky pain should one be suspicious of intestinal obstruction. Occasionally a loop of small bowel may get adherent to the vault. Laparotomy is done. Resection and end-to-end anastomosis is done.

e. *Thrombophlebitis and deep vein thrombosis*

f. *Pulmonary embolism*

g. *Early menopause*—Women who have undergone hysterectomy may experience menopause earlier than the average age of menopause (age 51). This may be due to an interruption in blood flow to the ovaries. Removal of ovaries also induces menopausal symptoms in the immediate postoperative period. Unless hormones replacement not started patient may develop severe symptoms that may affect the mental status.

Vaginal Hysterectomy

Indications: Common indications include abnormal or dysfunctional uterine bleeding, complex endometrial hyperplasia, leiomyoma (12-14 weeks size), adenomyosis, pelvic organ prolapse **(Fig. 32-22)**.



Fig. 32-22: Uterine prolapse.

Prerequisites for vaginal hysterectomy*:*

- Good uterine mobility that can be demonstrated with Valsalva manoeuvre
- Absence of adenexal pathology
- Pubic arch of 90° or greater with adequate vaginal canal, deep and wide posterior vaginal fornix will make the vaginal surgery easier to perform.

Proper selection of the patient is very important in vaginal hysterectomy.

Contraindication*:*

- Restricted uterine mobility
- Previous pelvic surgeries and caesarean section
- Severe endometriosis and pelvic inflammatory disease where there may be extensive pelvic adhesions
- Adenexal pathology—ovarian cysts and tumours, tumours of fallopian tubes
- Uterus enlarged beyond 12-14 weeks.
- Nulliparity
- Narrow pubic arch and narrow vaginal canal.

However vaginal hysterectomy can be successfully done in nulliparous women and women who have undergone caesarean as long as adequate access for division of the uterosacral and cardinal ligaments is obtained by the surgeon and the uterus can be sufficiently mobilised to allow vaginal extraction. Even when the uterus is enlarged beyond 12-14 weeks vaginal hysterectomy can still be accomplished safely by means of morcellation, uterine bisection, wedge debulking, or intramyometrial coring techniques.

Benefits of vaginal hysterectomy over the abdominal: Morbidity of abdominal procedure like, wound infection and disruption, blood loss, intestinal obstruction, paralytic ileus, adhesions, deep vein thrombosis is less in vaginal hysterectomy. Postoperative pain and discomfort is less in vaginal hysterectomy, so need of less analgesia and early ambulation is possible. Duration of hospital stay is less. So more cost effective than the abdominal procedure.

Prior to vaginal procedure adnexa can be tackled by laparoscopy, thereby converting the hysterectomy into a vaginal procedure which would otherwise be an abdominal (LAVH).

Preoperative Preparation

For better postoperative healing of the vaginal vault it is always advisable to give vaginal douche a day before and on the day of the surgery. This will help to clean the vaginal epithelium from any infection. The rectum is evacuated with an electrolyte purgative or fleet enema on the evening before surgery. Bowel cleansing evacuates solid stool from the rectum, reduces the bacterial load at the perineum, and reduces the incidence of postoperative ileus and constipation. Patient is kept fasting for 6-8 hours. Informed consent is taken.

Prophylactic broad-spectrum antibiotics are started before the surgery. The risk of postoperative infection can be reduced if antibiotics are given just before the surgery such that to be effective, the antibiotic must be in the tissue at the time of surgery.

Technique

Anaesthesia—It can be done under general, spinal or epidural anaesthesia. It depends on the condition and choice of the patient.

Positioning—The patient is positioned in the dorsal lithotomy position with the buttocks just over/well off the edge of the table. Type of stirrup used should take care to protect the vulnerable vascular, bony, and neurologic points of the lower limb. Use of adequate leg padding, avoiding marked flexion of the thigh, and avoiding pressure points, particularly laterally, where the peroneal nerve encircles the head of the fibula will prevent these injuries due to wrong positioning. In addition to this mild Trendelenburg (10–15°) positioning will help the surgeon to comfortably operate. Assistants need to stand inside the stirrups to see the operative field.

The vagina and perineum is cleansed with betadine or savlon lotion. In addition lavage of the vagina with saline will also help to reduce the postoperative infection. Bladder is drained with a metal catheter. The patient is then draped.

An examination under anesthesia is now performed, in dorsal lithotomy position, to assess descent of the pelvic organs, respective defects, mobility, and uterine size. The final decision is made at this time as to whether the procedure can be done vaginally or abdominally.

A heavy speculum is placed into the posterior vagina. With a right-angle retractor anterior vagina is retracted and the cervix is visualised. The anterior and posterior lips of the cervix are grasped with a single- or double-toothed tenaculum/vulsellum forceps. Sounding the uterus now will help to confirm the suspected size and contour of the uterus.

Gentle traction over the cervix with the vulsellum is given in all directions so that the surgeon can visualise the cervico-vaginal junction, the area where the initial incision has to be made. 0.5% lidocaine with 1:200,000 or a dilute solution of vasopressin may be injected into the paracervical tissue, the area around the uterosacral ligaments, the lower portion of the cardinal ligament, and the bladder pillars. This will help to decrease peroperative blood loss, and also to delineate the surgical planes. But the use of vasoconstrictive infiltration is not always necessary.

With adequate traction on the anterior and posterior lips of the cervix, a circumferential incision is made through the full thickness of vaginal epithelium at the cervico-vaginal junction. Anteriorly the junction is at where the vaginal rugae begin and the smooth cervical epithelium ends. As the incision is laid circumferentially, adequate counter-traction against the respective lateral vaginal wall will prove to be helpful. The full-thickness posterior vaginal mucosa is incised to meet the anterior incision. If this initial incision is made below the level of cervico-vaginal junction close to the external os, a greater amount of dissection is needed to displace the vaginal mucosa and usually an increased amount of bleeding is encountered. And depth of the incision also should be adequate enough to involve only the full thickness of the vaginal mucosa, otherwise the dissection extends into the cervix leading to increased blood loss and technical difficulty. Now the vagina is dissected from the underlying tissue sharply with scissors or bluntly with the surgeon's sponge-covered finger. The bladder is dissected off the anterior lower uterine segment all the way up to the vesicouterine peritoneal fold. This step is frequently insufficiently performed for fear of entering the bladder. Entry into the anterior cul-de-sac is difficult if this dissection is not sufficiently carried up to the vesicouterine peritoneal fold. The bladder is elevated with a right-angle retractor placed under the vaginal mucosa and bladder. Strong downward traction is applied on the cervix held by vulsellum. This maneuver aids in identifying the vesicouterine peritoneal fold which appears as a white transverse line across the lower uterine segment. It is grasped with forceps and incised with sharp curved scissors. The edge of this incision is held with artery forceps and a finger is inserted to explore the area so as to be sure that one is in the peritoneal cavity and not the bladder and also to identify any unsuspected pathologic condition that was not identified before. A right-angle retractor is placed into the peritoneal cavity underneath the finger. If the patient had a previous caesarean section, the scar of this procedure can be readily visualised and identified separately from the bladder. Sometimes it is possible to dissect beneath the caesarean section scar to gain entry into the superior part of the vesicouterine space to identify the vesicouterine peritoneal fold.

With steep upward traction on the cervix, the cul-de-sac is exposed. Posterior vaginal cuff is retracted with forceps placing the peritoneum of the cul-de-sac on tension. The peritoneum of the cul-de-sac is incised with curved scissors. Care should be taken not to place this incision closer to the cervix in an attempt to prevent injury to the rectum, which results in retroperitoneal dissection ultimately pushing the peritoneum superiorly and posteriorly, thereby obscuring the identification of the peritoneum. Once the cul-de-sac is opened a finger inserted into the cul-de-sac and the area is explored for any unsuspected pathology. A right-angle retractor or weighted speculum is placed into the posterior cul-de-sac which will help to keep the rectum away from the operative site during the operation.

With the upward and lateral traction on cervix, a curved Heaney clamp is placed in the posterior cul-de-sac with one blade underneath the uterosacral ligament and the other over the uterosacral ligament, immediately lateral to the uterine cervix so that some carvical tissue is also included in this clamp. This prevents the possible ureteric damage during clamping of the uterosacral ligament. The uterosacral ligament is cut with curved scissors so that approximately 0.5 cm of tissue is distal to the clamp. A transfixion suture with 1/0 vicryl is placed at the tip of the clamp and tied. The procedure is repeated on the other side also. Next, the cardinal ligaments on both sides are identified, clamped, cut, and suture-ligated with 1/0 vicryl sutures in a manner similar to that previously described for the uterosacral ligaments.

Next the remaining portion of the broad ligament attached to the lower uterine segment containing the uterine artery is clamped, cut and suture ligated with 1/0 vicryl on both sides adjacent to the cervix. Use of a single clamp in the vaginal hysterectomy reduces the chance of ureteric damage.

The uterine fundus is now delivered out posteriorly by giving traction on the uterine fundus on the posterior aspect with tenaculum. By inserting fingers the utero-ovarian ligament is identified. Along with remaining portion of broad ligament and round ligament it is clamped and cut. The pedicles are double-ligated, first with a suture tie and then with a suture ligature medial to the first tie. The fallopian tubes and ovaries are now inspected by drawing them into the operative field. If adnexa are to be removed, then the round ligaments should be clamped, cut and ligated separately. By applying traction on the utero-ovarian pedicle the ovary is drawn into the operative field with a Babcock clamp. A Heaney clamp is placed across the infundibulopelvic ligament, and the ovary and tube are excised. Even this pedicle is double ligated with a suture tie and a transfixation suture ligature.

When uterus size is big following techniques may be employed to facilitate the removal of the uterus—morcellation, intramyometrial coring, uterine bisection, and wedge debulking. Morcellation can be used in enlarged uterus, fixed uterus or when there is limited vaginal exposure. It should not be performed if the uterine arteries cannot be ligated or when malignancy is suspected. Intramyometrial coring is done by circumferentially incising the outer myometrium beneath the uterine serosa with a scalpel while placing the cervix on traction. The enlarged uterus is delivered as an elongated mass inverting the uterine fundus. Uterine bisection is performed by cutting the uterus from cervix to the uterine fundus in the sagittal plane.

The entire broad ligament with the pedicles from the tubo-ovarian round ligament anteriorly to the uetrosacral ligament posteriorly are exposed. Wet mop is placed in the peritoneal cavity to allow the surgeon to visualise the pedicles on both side and confirm the adequacy of haemostasis. If any bleeding points are present, it is ligated under direct vision.

Peritonealisation is done using a delayed absorbable suture beginning from anterior peritoneal edge. A continuous purse-string suture is applied beginning from 12 o'clock position proceeding in clockwise direction to incorporate the distal portion of the left upper pedicle and then the left uterosacral and cardinal ligaments. The suture then incorporates the posterior peritoneum as high as possible. The suture is then carried through the uterosacral and cardinal ligament on the patient's right side, and then through the right upper pedicle. This type of high peritoneal closure will help to prevent future enterocele formation.

The vaginal mucosa can be approximated either in a vertical or horizontal fashion, using either interrupted or continuous sutures. These sutures should involve the entire thickness of the vaginal epithelium, taking care not to take bite into the bladder anteriorly.

Vagina is packed with sterile gauze pack soaked with iodine solution. Bladder is catheterised for 24 hours. Both this pack and catheter is removed after 24 hours.

Postoperative care:

- Patient is kept nil oral for 12-24 hours as the intestinal mobility is sluggish.
- Hydration is maintained by IV fluids.
- Pareteral antibiotics for 24 hours followed by oral preparation. Analgesics may be required as there may be pelvic discomfort during the first 24-48 hours.
- Early ambulation will help to prevent DVT.

Complications

a. *Haemorrhage*—Bleeding may be from the vaginal cuff margin or from above from one of the pedicles. It may present as vaginal bleeding in the immediate postoperative period or retroperitoneal bleeding which may present with deterioration of vital signs with little amount of vaginal bleeding.

Resuscitative measures should be undertaken. Haematocrit in the immediate postoperative period will give an idea of amount of blood loss. Ultrasound may sometimes be helpful if retroperitoneal/intraabdominal bleed is suspected. Blood transfusion is arranged. Patient is shifted to the theatre. Under anaesthesia vagina is inspected with proper light. If it seems to come from the cuff margins one or two re-enforcing stitches will stop the bleeding. If it appears to come from above, the vault stitches are opened and the bleeding pedicle is identified and ligated. Sometimes the bleeding vessel may get retracted and cannot be controlled from below. In that cases laparotomy is done, bleeding vessel is identified if possible. If not then uni/bilateral anterior division of interneal iliac artery ligation is done. Many retroperitoneal bleed stops on its own by tamponade effect forming a haematoma which eventually gets absorbed. Higher cover of antibiotics is put to prevent the infection of this haematoma.

b. *Sepsis*—

In the form of pelvic infection is known to occur quite commonly after vaginal hysterectomy. Patient presents with fever, pain in lower abdomen and pelvis, tenderness in the vaginal cuff. Infection ranging from vaginal cuff cellulitis, pelvic cellulitis, pelvic abscess, infected pelvic haematoma, and adnexal abscess is known to occur. Usually pelvic cellulitis or vaginal cuff cellulitis gets controlled with combination of parenteral higher antibiotics. Pelvic abscess should be suspected when in spite of higher antibiotics the fever fails to come under control. Ultrasound helps in diagnosis. Vaginal cuff may need to be opened with an artery forceps and drain out the purulent material. Infected haematoma if present is drained. Once this is drained usually the sepsis gets controlled. Parenteral antibiotics are continued for another 24-48 hours after the temperature has come to normal **(Figs 32-23 and 32-24)**.



Figs 32-23(1)



Figs 32-23(2)



Figs 32-23(3)



Figs 32-23(4)



Figs 32-23(5)


Rectocele repair

Figs 32-23(6)



Figs 32-23(7)

Figs 32-23(1 to 7): Vaginal hysterectomy for uterine prolapse is technically demanding, skilled time consuming procedure. It is done under spinal anaesthesia in lithotomy position. After cleaning and draping, bladder is emptied using metal catheter. Cervix is held with vulsellum forceps. Anterior vaginal wall is incised like inverting 'T'. Anterior vaginal wall is separated carefully by blunt gauze and sharp scissor dissection to push the adherent bladder underneath upwards up to the urethral opening. Laterally is dissected adequately so as to make feasible to place Kocher's clamp. Peritoneum is opened both at uterovesical fold in front and uterovaginal fold behind. Fundus of the uterus is delivered out. Mackenrodt ligament, uterine pedicle and ovarian ligaments are serially ligated with transfixation carefully after applying Kocher's clamp and divided these structures. Usually 1 or 2 zero vicryl is used for transfixation ligatures. Uterus is removed. Peritoneum is closed with vicryl purse string sutures. Bladder is invaginated using purse string 2 zero vicryl sutures. Often polypropylene mesh may be placed to prevent recurrence of cystocele. Tied sutures of both Mackenrodt ligaments on both sides which were already kept long are passed through a needle and passed across the vaginal wall to continue with perineorrhaphy. Extra vault is carefully excised vertically. Vault (anterior vaginal wall) is sutured with 1 zero vicryl from above downwards as continuous locking sutures till the lower end. Suture passed across from the both side Mackenrodt ligaments are tied firmly on the vaginal wall. If rectocele is present, it is repaired. Horizontal incision is made on the posterior vaginal wall just above the skin margin; posterior vaginal wall is raised off the anterior rectal wall; care should be taken not to injure rectum; once this flap is elevated. Rectocele is repaired by placing interrupted sutures over pararectal tissues. 2/3 interrupted sutures are placed over the levator ani and tissues of perineal body; Rectum is pushed backwards when sutures are applied; posterior vaginal wall is excised adequately; remaining cut margin is resutured vertically using continuous vicryl suture to complete the rectocele repair. Foley's catheter is passed and kept in place for 5 days. Vagina is packed with betadine soaked pack which is removed within 24 hours.

Laparoscopic Hysterectomy

Laparoscopic hysterectomy is not an alternative to vaginal hysterectomy but for abdominal. Its main aim is to reduce the abdominal procedure which has higher morbidity in terms of intestinal adhesions, infection, blood loss, hospital stay, and postoperative pain.

Drawbacks

- Need of trained surgeons, and hospital staff.
- Equipments which are costly and difficult to maintain.
- Cost factor—not all patients can afford the procedure.

Types of Laparoscopic Surgery

- Laparoscopic assisted vaginal hysterectomy (LAVH)
- Laparoscopic subtotal hysterectomy (LSH)
- Total laparoscopic hysterectomy (TLH)

Though laparoscopic supracervical hysterectomy (LSH) has been associated with a shorter operating time, decreased chances of visceral trauma, and less technical difficulty, however, some patients continue to have cyclical bleeding until menopause, and there is a small risk of developing cervical cancer in the retained cervix.

Preoperative Preparation

Routine tests including chest X-ray, ECG, ECHO is done. Patient kept fasting for 6-8 hours. Bowel is evacuated on the previous evening by enema. Prophylactic antibiotics are given. Informed consent taken. The chances of conversion to laparotomy is explained.

Preparation and Positioning

Patient is placed in a dorsal lithotomy position with pneumoboots. The arms are tucked by the sides and a foam mattress under the patient prevents the sliding during steep Trendelenburg position. Or the patient needs to be tied to the table to prevent from sliding. The table is kept in a lowest position. Monitor is placed directly facing the surgeon. Bladder is catheterised. Uterine manipulator is inserted after cleaning the perineum and vagina.

Instruments

- 10 mm telescope 0°/30°
- Video camera
- Light source—xenon source best



Figs 32-24(1)


GPSL
GYNECARE
GYNEMESH* PS
GYNECARE
GYNEMESH* PS
GYNECARE
GYNEMESH* PS
GYNECARE
GYNEMESH* PS
GYNECARE
GYNEMESH* PS
GYNECARE
GYNEMESH* PS
Manufactured by:
GYNECARE
WORLDWIDE
+H206GPSL1S

Figs 32-24(2)



Figs 32-24(3)

Figs 32-24(1 to 3): Cystocele repair done by placing specialised polypropylene mesh under the anterior vaginal wall. After opening the anterior vaginal wall, urinary bladder is separated from the anterior vaginal wall laterally upto the pubic ramus. Mesh is placed snuggly over the bladder, the sides of which is anchored to the vaginal flaps near the pubic ramus. Vaginal flaps are trimmed. Excess trimming is avoided. Anterior vaginal flaps is closed with continuous locking sutures using n0.1 chromic catgut.

- Trocar—two 5 mm , three 10 mm
- 5 mm grasping forceps—toothed/plain
- Scissors
- Unipolar electrode
- Bipolar forceps and the electrical cable
- Suturing forceps
- Suction and irrigation system
- Optional—harmonic scalpel, ligasure, morcellator.

Technique

Primary trocar is inserted just below the umbilicus or above if the uterine size is big. It is inserted either by closed method with help of verres needle or by open method by making a small incision near the umbilical margin and opening the peritoneum under vision. CO_2 gas is insufflated into the peritoneal cavity. 0° telescope is inserted through this trocar. Whole of the abdomen and pelvic anatomy is visualised. Any visceral injury during trocar insertion is looked for. Liver, under surface of the diaphragm, paracolic gutters, appendix are visualised for any additional pathology. Now the number of working ports and their site is decided by the individual surgeon and the pelvic pathology. Two lateral ports for 5 mm trocar are inserted under vision 2 cm above and medial to anterior superior iliac spine. Care is taken to avoid injury to inferior epigastric vessel. One 10 mm port lateral to the rectus at the level of umbilicus is put on left side (surgeon side). Additional ports may be put depending on requirement of the surgeon.

Round ligament on both sides is coagulated first with bipolar forceps and cut with scissors, 3 cm from the uterus. This can also be done with ligasure/harmonic scalpel. Elevation and traction to the opposite side with uterine manipulator will give proper exposure of the pedicles to be coagulated. If the ovary is to be removed, ureter is identified at the pelvic brim which is usually easy on the right side, but may be more difficult on the left due to sigmoid colon. The ovary or fallopian tube is grasped from the contralateral side for proper exposure of the infundibulopelvic ligament. Infundibulopelvic ligament is coagulated with bipolar forceps/ligasure under vision and sectioned. It is better to coagulate the pedicle with bipolar before using harmonic scalpel. While coagulating care is taken to see that ureter and iliac vessels are far away from the coagulating instrument. The coagulation and ligation is then proceeded anteriorly to join the previously sectioned area of the round ligament. The procedure is repeated on the opposite side.If the ovaries are to be preserved then the utero-ovarian ligaments are coagulated close to the ovaries and sectioned. Special care is taken to desiccate the parametrial veins that run between the ovary and the round ligament as these can be quite tortuous and tend to bleed if left unattended.

The procedure can now be carried from vaginal route (LAVH). Vaginal route can also be proceeded after opening the uterovaginal pouch and pushing the bladder down.

At the junction where round ligament is sectioned, the leaves of the broad ligament is sparated with a Maryland grasper. The anterior leaf of broad ligament is opened downwards and forwards towards the bladder on either side with monopolar hook. Utero-vesical junction is identified, grasped and elevated with forceps, cut with scissors or monopolar hook. The blader pillars are identified, cut with scissors thereby freeing and pushing the bladder off the lower uterine segment and cervix with a blunt suction probe. In patients with history of prior cesarean delivery, this area may be scarred and is important to stay relatively high on the uterus during the dissection. A re-evaluation of the route of dissection is advised if fat is encountered because the fat belongs to the bladder indicating that the dissection is moving too close to the bladder.

Due to variation in anatomy and the course of the uterine vessels it is initially helpful to skeletonise them. With the uterine manipulator uterus is pushed cephalad and to opposite side which helps to move the uterine vessels away from the ureter. The ascending uterine vessels are coagulated with the bipolar forceps at the level of internal cervical os, staying above the rim of the cervical cup. When the bubbles stop coming from the vessel it means that the vessel is desiccated completely and is safe to transect with the scissors or harmonic scalpel. Uterine artery can also be coagulatd and cut with ligasure. Uterosacral ligaments are desiccated and cut.

Disposable silicone tube of diameter of 45 mm or 35 mm is inserted into the vagina and is pushed upwards and forwards. This tube helps to stretch the cervicovaginal junction and helps in identifying the vaginal fornices. The outer end of the tube is covered with a cap thus helping to maintain the pneumoperitoneum. The uterine movements can be controlled with help of myoma screw inserted through 5 mm trocar. Colpotomy is done along the indentation of the vaginal tube, first anteriorly with monopolar hook or harmonic scalpel and extended laterally. The lateral angle of the vault may need to be coagulated with bipolar or ligasure as vaginal branches of uterine arteries are frequently encountered. Colpotomy is continued on posterior aspect. Thus uterus with cervix is separated. It can be drawn out through the vagina. If uterus is large it can be broken down with morcellator. Vaginal vault can be sutured laparoscopically or from the vagina. If vault suturing is done laparoscopically then pneumoperitoneum has to be maintained either by a wet mop placed in the vagina or placing the uterus drawn from the pelvis in the vagina. Vault is closed laparoscopically by 1/0 vicryl continuous sutures using needle holder forceps. With training and practice suturing by laparoscope would not be a difficult job **(Fig. 32-25)**.

Once the suturing is done mop from the vagina is removed. Pelvis is irrigated with saline. All pedicles are seen for any sign of bleeding. Once haemostasis is confirmed CO_2 gas insufflation is stopped. Trocars are removed under vision. Telescope is removed. Trocar site is closed with 2/o vicryl sutures/Dermabond.

Patient is kept nil oral for 24 hours. Catheter can be removed in 24 hours. Antibiotics are continued for 5 days. Patient can be discharged from the hospital in 3-4 days.

Complications

a. *Injury to bladder*—Endometriosis, previous surgery, inexperience of surgeon, over distended bladder, and pelvic adhesions are proposed risk factors for bladder injury. Bladder injury can occur during insertion of trocar, especially in the suprapubic site piercing dome of the bladder; in base while separating the bladder off the cervix especially in patient who had previous caesarean section where adhesion are present between the bladder wall and cervix; or as the result of thermal energy. Fistula may result due to thermal injury. In suspected cases, the bladder is filled with methylene blue dye and observed for leakage of dye. Unrecognised cases present with abdominal discomfort and oliguria as cardinal sign. According to type, size, and localisation of injury, surgical management is planned via laparoscopy, laparotomy, or vaginal approach. Bladder can be repaired successfully by laparoscope or by laparotomy with 2 layer of 2/0 vicryl sutures.

b. *Ureteral injury*—Electrocautery (unipolar or bipolar) is the leading cause of laparoscopic iatrogenic ureteral injury. Injuries with loop suturing, trocars, laser devices, staples, and sharp dissection are also known. The 3 following locations carry the risk for ureteral injury during laparoscopic surgeries: at the pelvic brim, where the ureters lie beneath the insertions of the infundibulopelvic ligaments; deep ovarian fossa where the ureter passes; and the ureteral canal. Ureters are often injured while coagulating the uterine arteries, 4-5 cm above the uterovesical junction. Lack of precise recognition of the cervicovaginal margin and dissection too far down the vagina can injure the ureter 2 cm to 3 cm from the ureterovesical junction. Injuries may include transection, ligation, avulsion, crush injury, devascularisation, resection, fulguration, and perforation.

   Intraoperative methods for identifying ureteral injury—

   - 5 mL to 10 mL intravenous indigo carmine injection
   - Intraoperative ureteral catheterisation
   - Intravenous excretory urography
   - Dissection of the ureter.

   Intraperitoneal urine leak cannot be demonstrated in a coagulated or ligated ureter when tested intraoperatively. Absence of ureteral jet on cystoscopic examination reveals the problem clearly in such a case.

   Depending on the type of injury, patients may present in the early postoperative period or the presentation of thermal or laceration injuries may be delayed by several days or weeks. Postoperative presentation is variable and nonspecific, such as acute pelvic pain,


Uterine manipulator is used pervaginally
Lithotomy, head down position. Uterine manipulator from below.
Ligaseal/ligasure is used
L3
34
40
Monitor
Perineal part draping
Vaginal tube is used during bladder separation
Working ports in abdomen.
Perineal part vaginal tube

Figs 32-25:(1)


Extraction of the uterus
Suturing of the vault can be done
from above or below like shown here
Vault closed using 2 zero vicryl
Skin apposition using glue
STERILE UNI PACK
ISO AMYL 2-CYANOACRYLATE
Marvilyte

Figs 32-25:(2)

Figs 32-25(1 and 2): External part of the laparoscopic hysterectomy—position, ports, vaginal tube and uterine manipulator.

nausea, vomiting, malaise, and leakage of fluid though the trocar sites, abdominal distension, costovertebral angle tenderness, ileus, fever, peritonitis. X-ray of the abdomen may reveal a ground-glass appearance indicating fluid collection; CT scan reveals the presence of urine in the peritoneal cavity after intravenous injection of contrast medium.

Repair by laparoscope can be done if recognised intraoperatively. If recognised in the early postoperative period passing double J-shaped stent allows spontaneous healing of focal ureteral injuries. But delayed recognition, and extensive damage may require laparotomy to perform an end-to-end anastomosis or ureteral re-implantation.

c. *Intestinal injury*—Nearly half of bowel injuries occur during trocar insertion and the rest occur during the operation. Entry-related bowel injuries are mostly lacerations common in patients with previous laparotomies. Most of the intraoperative bowel injuries are thermal and is not diagnosed during surgery leading to delayed intervention which may be life-threatening. If intraoperatively unrecognised, patients present with nonspecific complaints not exactly pointing to peritonitis, such as mild abdominal pain, fever, diarrhoea, and abdominal distension, further delaying the diagnosis. Late consequences may be generalised peritonitis, abscess formation, and septic shock. Intestinal obstruction though rare can occur when obstructive small-bowel adhesions develop to the vaginal apex.

d. *Haemorrhage*—Present as vaginal haemorrhage, retroperitoneal haemorrhage, and intraabdominal haemorrhage. Intraabdominal haemorrhage can be due to inadequate coagulation or excessive coagulation leading to charring and break off of the adjacent vessel wall. Bleeding can also occur due to trauma to abdominal wall vessels while trocar insertion. Injury to inferior epigastric vessel and less commonly muscular arteries are known to occur. They may present as continuous dripping of blood from the port during surgery or massive intraperitoneal bleed in postoperative period or abdominal wall haematoma which may get infected. Bleeding is controlled by tamponade or suturing. Sometimes may require exploration of the portal site to visualise the bleeding vessel and ligate it under vision. It is good practice to inspect all the trocar sites for any active bleeding before the laparoscope is finally withdrawn. Retroperitoneal major vascular injuries are related to the Veress needle, trocar, or energy source. It is trauma to aorta, vena cava, or, more commonly, the common iliac vessel. Major vascular injuries rarely remain unrecognised intraoperatively. Immediate laparotomy is done by midline incision and the vessel repair is done.

e. *Sepsis*—May present with wound infection especially of umbilical site, vault granuloma, pelvic cellulitis.

f. *Hernia*—It can occur at the trocar site. It is common in the extraumbilical port of ≥10 mm size not adequately repaired. Bowel, omentum may get sucked into the portal site leading to intestinal obstruction. Laparotomy is needed for this. To minimise the risk of herniation, secondary trocars should be removed under supervision before the primary one, valves should be kept closed to prevent a sucking effect, 5 mm trocars should be preferred as much as possible and the trocar site should be correctly closed.

g. *Others problems related to pneumoperitoneum*—Subcutaneous emphysema, pneumomediastinum, and pneumothorax, gas embolism. All discussed in detail in the previous chapters.

Radical Hysterectomy

Indications: Radical hysterectomy is performed as a primary therapy for—

- Stage IB or IIA cancer of the cervix.
- Selected patients with stage IIb adenocarcinoma of endometrium (with gross cervical invasion)
- Upper vaginal carcinoma, uterine or cervical sarcomas, and other rare malignancies confined to the area of the cervix, uterus, and/or upper vagina.
- As a potential salvage therapy for women with cervical cancer who have been treated with irradiation and subsequently develop a small central pelvic recurrence or have a small central area of persistent disease.

Types of radical hysterectomy:

- *Type 1 hysterectomy is extrafascial, or simple hysterectomy* which involves removal of the cervix along with the uterine corpus, but does not require ureteral mobilisation or removal of a significant amount of the parametria. It is used as primary treatment for stage IA1 disease and after concurrent chemotherapy and radiation therapy for stage IB2 and bulky stage IIA cervical carcinoma
- *Type 2 (modified) radical hysterectomy, or Wertheim operation*, involves more extensive dissection than the extrafascial hysterectomy where the central portion of the parametrial tissues is removed while minimising disruption of the ureteral and vesical vasculature. It involves removal of medial half of the uterosacral ligaments and the cardinal ligaments, ligation of the uterine artery just medial to the point where it crosses the ureter, removal of a 1–2 cm portion of the upper vagina along with pelvic and para-aortic lymphadenectomy. Here it does not involve dissection of the ureter from the vesicouterine ligament. It is done in stage IA2 cervical carcinoma.
- *Type 3 radical hysterectomy*, originally described by *Meigs*, aims at removal of parametrial tissue as much as possible. It involves transaction of the uterosacral ligaments near their origin from the sacrum, excision of the cardinal ligaments as widely as possible after the uterine artery is ligated at its origin where it branches off from the hypogastric artery, removal of a 2-3 cm portion of the upper vagina along with pelvic and para-aortic lymphadenectomy. Care is taken to preserve the superior vesical artery.
- *Type 4 hysterectomy* is seldom done, represents an extended radical hysterectomy. It involves complete dissection of the ureter from the vesicouterine ligament along with sacrifice of the superior vesical artery. 3/4th of the vagina along with the uterus and parametria are removed along with complete lymphadenectomy.
- *Type 5 hysterectomy* also has limited application. This procedure involves resection of involved portions of the bladder, distal ureter, rectum along with the uterus, parametria, adnexa, and pelvic lymph nodes. Subsequent ureteral reimplantation is done.

Preoperative preparations:

- Abdominal and pelvic CT scan/MRI helps to evaluate the pelvic disease, ureter and lymph nodes.
- Along with routine blood investigations patients should have a thorough evaluation to insure that there are no other major medical contraindications to surgery. ECG, ECHO, chest X-ray are done to rule out cardiac complications.
- As there is potential for blood loss in these patients, central venous access should be done by an anaesthetist and required amount of properly typed and cross-matched blood should be kept ready. Anaemic patients should receive preoperative blood transfusion.
- Prophylactic antibiotic, usually a first generation cephalosporin is started.
- Patients are asked to start liquid diet 24 hours before surgery. Bowel preparation is done with Peglec/exelyte.
- For thromboembolic prophylaxis subcutaneous injection of low molecular weight heparin is started prior to surgery and continued in the postoperative period.
- Sequential compression devices (SCDs) are placed on both lower limb immediately prior to surgery, and are left in place until the patient becomes ambulant.

Technique

The patient is placed in the modified dorsal supine lithotomy position (15° Trendelenburg). The urethral orifice, vaginal introitus, and anal orifice are all available for instrumentation in this position and a second assistant can stand at the foot of the table between the patient's legs. The thighs are elevated 15 to 20° relative to the abdomen as there will be less strain on the patient's lumbosacral spine in this position. Care is taken to avoid pressure on the peroneal nerves in the legs by giving cushions. The abdomen from the rib margin to the midthigh, perineum, and vagina are surgically prepared. The bladder is emptied with a Foley catheter. A thorough bimanual examination is always performed. This can be followed by cystoscopy or proctosigmoidoscopy.

An abdominal incision is made in the midline, extending around and 2-3 cm above the umbilicus and inferiorly up to the pubic symphysis. Self-retaining retractors are used to retract the muscle. Moist pack is placed beneath each arm of the self-retaining retractor to avoid excessive compression of the epigastric vessels that course beneath the rectus muscles and it is advisable to release the mechanical retractors at periodic intervals to improve circulation through the abdominal musculature.

Before starting the dissection in the pelvis, the entire abdominal cavity is carefully evaluated for evidence of metastatic disease. This includes superior and inferior surfaces of the liver and under surface of diaphragm, the celiac plexus, omentum, serosal surface of small and large bowel as well as the mesentery. The kidneys and the retroperitoneal space along the aorta and vena cava is palpated because these are the major sites of extrapelvic spread of cervical cancer. Pelvic and para-aortic/para-caval lymph nodes are palpated, and any enlarged or suspicious nodes are removed and sent for histopathology. If there is histopathologic evidence of unsuspected, metastatic tumor in a para-aortic lymph node, radical hysterectomy operation is abandoned. These patients are treated with concurrent chemotherapy and extended-field radiation therapy.

Intestines are packed in upper abdomen with moist packs. Uterus is held by Kelly Clamps applied at its corneal ends. The round ligament is clamped, cut, and ligated near the lateral pelvic wall. The anterior leaf of the broad ligament is incised inferiorly along the lateral pelvic wall for a distance of approximately 3 cm. The posterior leaf of the broad ligament is incised superiorly along the lateral pelvic wall to the level of the infundibulopelvic ligament. The infundibulopelvic ligament is clamped, cut, and doubly ligated at the lateral pelvic wall. Next the utero-ovarian ligament is clamped, cut, and ligated, and the tube and ovary are removed. The procedure is repeated on the other side.

The retroperitoneal space is approached along the lateral pelvic wall. The common iliac, external iliac, and internal iliac arteries and associated lymph nodal tissue are exposed. The ureter is identified. By placing two silk sutures in the adjacent medial peritoneum the ureter is pulled medially away from the iliac vessels. The base of the aorta is exposed. The lymph nodal tissue surrounding the common iliac, external iliac, and internal iliac arteries are all removed by sharp dissection from the bifurcation of the aorta to the inguinal ligament at the femoral canal. Care is taken to avoid bleeding from the middle sacral vessels as well as from the proximal part of the left external iliac vein, which courses through this retroperitoneal space. Only the loose areolar tissue and fascial sheath from the iliac vessels; should be removed avoiding trauma to the intima or wall of the vessels particularly the veins.The external iliac and common iliac arteries are retracted laterally, and lymph nodal tissue surrounding the common iliac, external iliac, and internal iliac veins are removed by sharp dissection. The genitofemoral nerve lying lateral to the external iliac vessels, should be preserved because damage to this nerve produces postoperative discomfort in the groin and medial aspect of the thigh. Lymph nodes from each of the major anatomic sites (i.e., common iliac, external iliac, internal iliac) is placed in separate containers, labeled accordingly and sent for histologic analysis. The external iliac artery and vein are retracted laterally by a vein retractor. All lymphatic tissues are removed from behind these vessels and from the obturator fossa by sharp dissection. Particular care is taken to avoid trauma to the obturator nerve and vessels. They are also labeled separately and sent for histology. The obturator nerve is identified and preserved. The uterine artery is identified as it comes off the anterior division of the internal iliac artery and is ligated and tied with 2-0 suture. All these procedure is repeated on the opposite side.

By blunt dissection the pararectal space and paravesical spaces are exposed on both sides with the intervening web, which is the lateral extent of the cardinal ligament.

The paravesical space composed of loose connective tissue and fat is bounded by—

- Medially by the bladder and the retropubic space
- Laterally by the pelvic sidewall and obturator internus muscle
- Posteriorly by the cardinal ligament
- Anteriorly by the pubic symphysis
- Floor by the levator muscle
- Roof by the anterior leaf of the broad ligament that blends with the bladder peritoneum medially and the parietal peritoneum laterally.

The pararectal space is bounded by—

- Medially by the rectum
- Laterally by the hypogastric artery (the internal iliac artery)
- Posteriorly by the sacrum
- Anteriorly by the cardinal ligament.

The lateral aspect of the cardinal ligament containing the vascular web is clamped, cut, and ligated on both sides with 2-0 silk ties.

The distal stump of the transected uterine artery is traced entering the tunnel and it is related to the ureter within the tunnel where it crosses the ureter from lateral to medial side. The ureter is seen as it enters the tunnel. Two horizontal curved clamps are inserted beneath the roof of the tunnel over the ureter. The tissue in the roof of the tunnel which also consist the uterine artery and vein, is clamped, cut, and ligated. This dissection is undertaken on both sides. The ureter on both sides are rolled laterally out of the tunnel and dissected free from surrounding tissue lysing the flimsy adhesions between it and floor of the tunnel until its entrance into the bladder.

The bladder is dissected from the anterior vagina by sharp dissection. The uterus is retracted upward.The cul-de-sac peritoneum between the uterus and the rectum is incised. Retracting the uterus upwards, finger is inserted between the uterosacral ligaments, and the posterior wall of the vagina is dissected off the anterior rectal wall. Keeping the uterus under upward traction the upper portion of the uterosacral ligaments is clamped, cut and ligated on both sides. The lower portion of the uterosacral ligaments, containing the parasympathetic nerves to the bladder, is retained.

The anterior, posterior, and lateral attachments of the uterus and parametria have now been ligated. The paravaginal tissue on either side is clamped with Haeney's clamp, cut, and ligated with 1/0 vicryl sutures. The vagina should be transected approximately 3 cm below the cervix and the isolated bleeding sites on the vaginal cuff are ligated using 2-0 vicryl sutures. The vagina is closed with continuous interlocking 1/0 vicryl suture.

Abdomen is closed in layers after placing a closed suction drains in both retroperitoneal spaces. These drains are brought out through the anterior abdominal wall in each lower quadrant and are sutured to the skin.

Postoperative Complications

a. *Infectious and febrile morbidity*—It is the most common postoperative complication. Prophylactic use of broad-spectrum antibiotics reduces the frequency of this complication.
b. *Postoperative bleeding*—Most often they are self-limited and can be treated conservatively with close observation for haemodynamic instability and blood transfusions but sometimes may require re-exploration.
c. *Bladder dysfunction*—Due to interruption in the autonomic nerve supply to the bladder resulting from bilateral stripping of sacral nerves, excision of large portion of paracervical and paravaginal webs of retroperitoneal tissue and bilateral pelvic node dissection will damage the sympathetic fibres of the bladder. This results in transient hypertonia, gradually being replaced by hypotonia. Most patients get back the ability to void within 2–3 weeks; however, it may persist in approximately 5% of patients. In addition, a substantial number of patients develop persistent urinary incontinence postoperatively.
d. *Lymphocyst formation*—Results from interruption of efferent pelvic lymphatics leading to lymphedema, pelvic discomfort, and infection and also increase the frequency of deep venous thrombosis and pulmonary embolism. Lymphedema develops insidiously over time, occurs more frequently when pelvic lymphadenectomy is followed by radiation or groin node dissection. Similarly, lymphocyst formation can occur as a result of extensive pelvic lymphadenectomy. Lymphocyst may cause ureteral obstruction or presents as a pelvic mass. Percutaneous drainage under ultrasound guidance or surgery with marsupialisation may be necessary.
e. *Sexual dysfunction and surgical menopause*—Reduces the quality of life, can impose psychological problems.
f. *Vesicovaginal and ureterovaginal fistula*—Most dreaded and troublesome complication, results from ligation of the superior vesical artery and disruption of blood supply to the distal ureter. The need for postoperative radiotherapy will worsen this problem. Patient presents with fever, continuous dribbling of urine per vagina, sometimes with enlarged pelvic mass. To determine whether it is a vesicovaginal or ureterovaginal fistula, intravesical instillation of methylene blue followed by intravenous injection of indigo carmine is done and colour change in the swab placed in the vagina at high, mid, and low level is noted (*three swab test*). Alternatively, an intravenous pyelogram or computed tomography may help to locate the fistula. Most often uretero-vaginal fistula is located in the distal 1/3rd of ureter. Small vesicovaginal fistulas may heal spontaneously with prolonged bladder catheterisation; however, larger defects that fail to heal with conservative management needs surgical repair. Stenting is required for uretero-vaginal fistulas. If retrograde stent cannot be passed, then percutaneous nephrostomy with anterograde stenting is done. Repair of uretero-vaginal fistula is done after 3-6 months.
g. *Ureteric stricture*—can also occur after radical hysterectomy.

REPAIR OF GENITOURINARY FISTULAS

Types of Genital Fistulas

a. *Ureters*—ureterovaginal, ureterocervical, ureterouterine
b. *Bladder*—vesicovaginal (high, mid, low), vesicocervical, vesico-uterine
c. *Urethra*—urethro-vaginal

Investigation

Per speculum examination: Most fistula can be easily seen by perspeculum examination after instilling the bladder with dilute methylene blue especially VVF. Continuous trickling of urine from the vagina is seen. Vaginitis and vulvitis may be present due to constant dribbling of urine.

Fluid creatinine estimation and simultaneous comparison with serum creatinine is done. If the fluid creatinine is many times more than the serum creatinine, then the fluid is nothing else but urine because only the kidney has the capacity to concentrate creatinine to a high level.

Moir's three swab test—Three swabs are placed in the vagina at three levels. Bladder is filled with dilute methylene blue. Patient is made to walk for 10-15 minutes. If the lower most swabs get wet and stained blue it is incontinence per urethra. If the middle swab gets wet and stained blue it is due to VVF. If the uppermost swabs get wet but not stained blue it is uretero-vaginal fistula.

Cystoscopy—Helps to identify the level of fistula, its relation to the ureter, number of fistula. It is of limited use in large fistula as it is difficult to distend the bladder. In these cases the bladder can be distended with air/CO_2.

Intravenous urogram—helps to identify the level of fistula. If this fails then retrograde pyelography is done.

Spiral CT scan—reveals renal and ureteric anatomy, abscess, fluid collection.

Uretero-Vaginal Fistula

Invariably the distal 1/3rd ureter is involved.

Sites of ureteral injuries:

- At or just below the pelvic brim, dorsal to the infundibulopelvic ligament.
- Along the course of the ureter in lateral pelvic wall above the uterosacral ligament.
- At the base of the broad ligament where the uterine artery crosses the ureter from lateral to medial side.
- As the ureter passes in the tunnel in Mackenrodt's ligament
- In the intramural portion of the bladder.

Nature of injury:

- Trauma to the vascular sheath leading to ischaemia—damage to the adventitia should be avoided as much as possible during dissection of ureter.
- Ligature incorporation.
- Segmental resection.
- Thermal injury—though the mean distance of thermal damage with most of the instruments is approximately 2 mm, it may be as much as 5 mm.
- Injury by staplers in laparoscopic surgery.

Though abdominal hysterectomy for conditions like endometriosis, pelvic inflammatory disease, ovarian tumors is the commonest cause it is known to occur in radical hysterectomy, caesarian hysterectomy. The best way to prevent ureteric fistula is its identification in the retroperitoneal space and trace its course from pelvic brim to the bladder. Blind application of clamps over the bleeding uterine vessels should be avoided. Judicial usage of thermal current near the ureter will help to avoid thermal injury. As the pelvic part of ureter receives blood supply from lateral aspect, dissection and mobilisation is carried out from medial aspect so as to avoid devascularisation injury.

Repair

In the immediate postoperative period, repair is not attempted. Ureteric stenting with J stent is done. Indwelling catheter is placed. Only when there is infected urinoma or in generalised sepsis measures are taken to divert the urine from the kidney like percutaneous nephrostomy so to protect the kidney function. Small fistula often heals spontaneously. If fails to heal then after 3-6 months once the tissue oedema subsides ureteral resection and re-implantation is done. The ureter is transected above the healthy site and re-implanted in to the posterior aspect of the bladder. If the ureter cannot be reached to the bladder without tension then *psoas hitch* is done. The entire ventral surface of the bladder is freed from its areolar attachment in the retropubic space. On the anterior wall of the bladder a curved incision is put. This incision is put at 90° to the direction desired to elongate the bladder. Two fingers are inserted into the postero-superior portion of the bladder. A pliable bladder can be extended to reach the psoas tendon across the iliac vessels to reach the transected proximal end of ureter. The posterior surface of the bladder is anchored to the psoas tendon by interrupted absorbable sutures. These sutures are attached to the bladder wall without entering the bladder lumen. The transected ureter is implanted into the posterior aspect of the bladder dome, some distance from the trigone so as to minimise any potential stenosis or injury to the contralateral ureteral orifice. The ureter is stented, and the bladder is closed in two layers at right angles to the way it was opened. A drain is placed near the ureteroneocystostomy which is to removed in the 2 to 3 days once it is certain that there is no leak. The bladder is drained for 10 days and ureteral stent is removed after 6 weeks.

Vesicovaginal Fistula

Bladder trauma commonly occurs during hysterectomy and caesarian section while dissecting the bladder off the cervix and vagina. Failure to identify the bladder injury, thermal injury, suture placement through the bladder and vaginal wall while closing the vaginal cuff, ichaemic necrosis of the bladder wall due to prolonged pressure of the fetal head in 2nd stage of labour, forceps delivery of the baby are the common cause of vesicovaginal fistula.

Treatment

Once the fistula has occurred it is wise to wait for 3-6 months. Indwelling catheter antibiotics are put to subside the infection and edema. Small fistulas <3 mm may heal spontaneously during this waiting period. Meanwhile local condition is improved with vaginal estrogen cream; zinc oxide cream for ammoniacal dermatitis. Small fistulas can be tried to close with fibrin sealants.

a. *Vaginal repair*

Patient is placed in lithotomy position. Fistula is exposed properly. This may demand an extended episiotomy especially for high fistulas near the vault. Foleys is passed across the fistula. Bulb inflated and the fistula is given mild traction below.

- *Flap-splitting technique*—In this technique, the vaginal epithelium is incised circumferentially around the fistula and widely dissected from the underlying endopelvic fascia for a distance of about 2 cm. the tract is left unresected, the bladder is closed, tension-free, in 2 layers with 3 or 4/0 vicryl–first layer includes the full thickness of vaginal skin previously left intact at the fistula tract, along with the partial thickness of the bladder wall, and second layer involves closure in the muscularis placed perpendicular to the prior suture line. Martius bulbocavernosus flap can be advanced near the fistula for vasularisation.The surgery is completed with the vaginal closure over the bladder defect.
- *The Latzko procedure*—It is an excellent procedure for correcting small posthysterectomy fistulae at the vaginal apex with adequate vaginal length. A circumferential incision is made around the fistula. Vaginal epithelium is stripped from the anterior and posterior fascia at least 2.5 cm in all directions around the fistula tract. The fistula is not excised. The vesical edges of the fistula are not denuded. The pubovesical fascia is closed in two layers, and vaginal epithelium is closed using interrupted sutures. The walls have a natural tendency to fall together and are easily approximated without tension. The vaginal wall in contact with the bladder becomes the posterior vesical wall and which eventually gets re-epithelialised with transitional epithelium. Indwelling catheter is placed to prevent undue filling of bladder and tension over the stitches.

b. *O'conor's abdominal repair*

Indication for abdominal approach—

- The need for concomitant abdominal surgery, such as augmentation cystoplasty and ureteral reimplantation
- Adequate vaginal exposure of the fistula not possible
- VVF involving the ureters, bowel, or other intra-abdominal structures
- Involvement of the VVF with ureteric orifices.

By midline/Pfannenstiel incision laparotomy is done. After entering the peritoneal cavity the posterior wall of the bladder is dissected free as much as possible. Incision made on the posterior wall of the bladder is extended down to the level of the fistula. Stay sutures may be placed along the incision for every few centimeters to permit traction so as to aid in exposure and dissection. Location of fistula and its relation to the ureteric orifice is identified. If necessary ureteral catheters may be placed. The fistula tract, scarred and necrotic tissue are resected. The posterior wall of the bladder is dissected from the underlying endopelvic fascia and vagina. The bladder and vagina are closed separately. The bladder is closed in 2 layers of 3/0 vicryl suture in continuous fashion beginning from the apex. First layer includes the mucosa and full thickness bladder wall, second layer involves the seromuscular layer inverting the first. Bladder is drained by a suprapubic catheter removed after 2-3 weeks and transurethral catheter removed after 4-5 days.

c. *Bladder mucosal autologous grafts*

By laparotomy, cystotomy is done and bladder mucosa is denuded circumferentially near the fistula site for a distance of 1 cm. The fistula tract and vaginal wall are left undisturbed. At the edge of the anterior cystotomy margin a free bladder mucosal graft is dissected sharply from underlying muscularis layer. This mucosal graft is then secured with interrupted 4-0 vicryl sutures over the fistulous tract. These sutures are placed into the superficial muscularis at a distance of 2-3 cm. The bladder is closed in 2 layers. A transurethral catheter is used for 4-5 days. A suprapubic Malecot catheter is placed for 2-3 weeks.

Rectovaginal Fistula Repair

It is the abnormal communication between rectum and anal canal. Though obstetric trauma is the commonest cause, carcinoma cervix invading the posterior vaginal wall tuberculosis, radiotherapy induced are other causes.

Foul smelling discharge or faeces though the vagina is the presentation. Fistula may *below* just above the anal sphincter or *high* up near the vault.

Investigation

- *Contrast study*—using a contrast material a vaginogram or a barium enema is done to identify a fistula located in the upper rectum.
- *Computerised tomography (CT) scan*—of abdomen and pelvis helps to locate a fistula and determine its cause.
- *Magnetic resonance imaging (MRI)*—can show the location of a fistula, as well as involvement of pelvic organs or the presence of a tumor. MR fistulogram can be more useful.

Preparation

Complete mechanical bowel preparation is essential for the repair of rectovaginal fistula (RVF). Diversion colostomy is essential in high fistula, radiation induced fistulas and in recurrent/failed repair of RVF. Vagina is prepared with antiseptic solution. Preoperative higher antibiotics are started.

Technique

Patient is put in lithotomy position. Vaginal mucosa is incised circumferentially round the fistula. The vaginal flap is raised all round the fistula. Extreme care is taken to see that the bowel mucosa is adequately mobilised and the devitalised, scarred, or avascular portions of the mucosa is been excised. After adequate mobilisation of the intestinal mucosa, its edges are sutured in an inverting fashion with interrupted 3-0 vicryl sutures. A second layer of closure involving the perirectal fascia and sometimes even levator ani muscle is done. To improve the vascularity of the area bulbocavernosus flap may be drawn into the area. A longitudinal incision down the labia majora is done through the pad of fat until the bulbocavernosus muscle is exposed. After its dissection it is transected above its insertion into the perineal body, leaving its blood supply from the pudendal artery intact. A tunnel approximately 3 cm wide is created from inside the vaginal canal and the bulbocavernosus muscle is drawn through this tunnel underneath the labia minora. It is placed over the repaired area and is sutured over the perirectal fascia with interrupted 3-0 vicryl sutures. The vaginal mucosa and the labial skin are sutured with 2/0 vicryl sutures. Stool softeners are given for 3-6 months.

However higher fistulas cannot be dealt satisfactorily through vagina and may require open abdominal approach. After dissecting the rectovaginal septum, the fistula is divided, and the rectum and vagina are closed primarily without bowel resection. Omentum may be interposed in between to separate the suture lines. This is useful when the fistula is not large and the tissues available for closure are healthy. But when tissues are unhealthy because of irradiation, inflammation, or neoplasm, unless the abnormal tissues are resected this type of repair is likely to fail. Functional anal sphincters are preserved whenever possible by use of a low anterior resection, and coloanal anastomosis.

TRANSOBTURATOR TAPE (TOT) FOR STRESS URINARY INCONTINENCE

Under spinal anaesthesia, in lithotomy position, Foley's catheterisation is done. A point is marked on the outer aspect of the labia majora which is a point of intersection of an imaginary horizontal line passing to the clitoris and vertical line passing through the adductor longus tendon. Suburethral anterior vaginal wall flap is raised for 2 cm by making a vertical incision. Dissection upwards and laterally is carried out as far near the pubic ramus. A stab incision is made on the marked point on the outer aspect of the labia majora (vertical incision). Through this small incision specialised curved stout trocar which is having an opening (helical trocar) is inserted under guidance over the pubic bone and then to pass under and around the pubic bone across the obturator membrane so as to enter its tip into the anterior vagina adjacent and under the flap created; through the eye at its tip polypropylene tape (strip of lengthy mesh) is fed and gradually withdrawn to bring the tape out through the incision on the skin. Helical trocars are different for right and left side. Similar procedure is repeated on the opposite side to pass another end of the tape (mesh strip) to the opposite side labia majora incision. One should confirm that tape should fit only snugly neither too tight nor too loose. Ends of the mesh tape are buried under the skin (both sides) and skin is closed on both sides. Anterior vaginal wall incision is closed using chromic catgut. Urinary catheter is kept for 2 days.

Problems

Injury to bladder, obturator vessels, mesh displacement, failure of the procedure, it is a blind procedure. It is considered to be safe in spite of the fact that it is blind **(Fig. 32-26)**.



Figs 32-26(1)


Mesh
Right side instrument-mesh retriever
Mesh
Right side instrument
Eye to pass the mesh strip
Left side instrument

Figs 32-26(2)

Figs 32-26(1 and 2): Technique of transobturator tape (TOT) placement for stress urinary incontinence.

Chapter

33

Other Procedures

ROBOTIC SURGERY

Word—*Robota (Czech)* means for compulsory labour. First robot was deviced by Leonard da Vinci. Surgical robot is powered computer-controlled manipulator with artificial sensing that can be reprogrammed to move and position tools to carry out a range of surgical works. Initially da Vinci robot is developed from defense advanced research project agency (DARPA) for military research of remote battlefield surgery. Cholecystectomy was performed remotely via telesurgery from 300 miles away. Intuitive surgery created in 1999 after acquiring military patent rights from military. First robotic prostatectomy was performed in 2001 **(Fig. 33-1)**.

There are three parts in robotic system:

- Surgeon's console
- Patient's cart
- Optical cart.

As the surgeon manipulates the remote control unit, movements of the surgeon is translated to robotic arms. Each robotic arm contains multiple appendages connected by joints. The 'hand' of the robot holds interchangeable surgical instruments that can be moved in a manner similar to wrist of human. Scaled, filtered, translated movements are achieved without hand dominance. In laparoscopy, it is surgeon's hand, team work and proper instruments, tremor at the working end is always present; camera is controlled by camera surgeon not operator whereas in robotic surgery camera is controlled by operator. Endowrist moves 360° at all angles, makes dissection and suturing perfect **(Fig. 33-2)**.

Special features are: Binocular stereoscopic 3D vision with stability of camera; increased dexterity because of endoinstrumentation; high density camera with 15X magnification; easy dissection; quick intracorporeal suturing and knotting; precise technique; surgeon sits comfortably and operate with arms rested; adequate ergonomics with equal tremor less movements of right and left arms; multitasking instrumentations; harmonic robotic arm; three arms with 3D HD robotic camera arm with 4th arm robot for retraction; patient friendly as well as surgeon friendly.

Advantages: It is less painful; less blood loss; fast recovery; needs short hospital stay; small incision; cosmetically accepted; better outcome. Robot facilitates the performance of most complex procedures with minimally invasive high standard techniques.



Fig. 33-1: Robotic surgical device set.



Fig. 33-2: Robotic endowrist which moves in all angles—360°.

Procedure done: All procedures done through laparoscopy can be done through robotic surgery. Nephrectomy, prostatectomy, hysterectomy, oesophageal surgeries; thyroid surgeries; oropharyngeal surgeries.

Learning curve: Surgical simulator to learn the robotic surgery is available—as red dragon/blue dragon. This skill simulator can teach endowrist manipulation, cameras and clutching; 4th arm integration; system settings; needle control and driving; energy use and dissection **(Fig. 33-3)**.

Limitations: Absence of tactile feedback, fixed patient position; increased cost to patient.

Future: Present set has got following features – monopolar/bipolar/advanced bipolar energy; harmonic; advanced grasper; laser.



Fig-33-3: Robotic skill simulator.

Future set will have linear cutter, seal, suction irrigation, drill, etc. Endowrist one vessel single use 8 mm diameter sealer with compact snake wrist is designed to seal and cut up to 7 mm diameter vessels. Image guidance fluorescence, lymph node mapping are newer one. Firefly fluorescence imaging of da Vinci identified real time anatomy using near infrared guidance which enhances visualisation of the critical vasculature like of mesentery, permits real time perfusion of the bowel prior to resection mainly in colon.

Advanced single port robotic set is the future. Single port very flexible robotic arm with snake like robots are possible in coming days **(Figs 33-4 to 33-6)**.

Robotic scrub nurse as a helper robot in changing instruments like a scrub nurse.

LIPOSUCTION

Liposuction, also known as *lipoplasty* ("fat modelling"), *liposculpture suction lipectomy* ("suction-assisted fat removal") is a cosmetic surgery operation that removes fat from many different sites on the human body. Areas affected can range from the abdomen, thighs and buttocks, to the neck, backs of the arms.

Several factors limit the amount of fat that can be safely removed in one session. Finally, the operating surgeon and the patient make the decision. There are negative aspects to removing too much fat. Unusual "lumpiness" and/or "dents" in the skin can be seen in those patients "over-suctioned". The more fat removed, the higher the surgical risk.

Liposuction may be performed under general, regional ("tumescent"), or local anaesthesia. The safety depends on the amount



Fig. 33-4: Robotic flexible system.



Fig. 33-5: Robotic SILS port.

of tissue removed, the choice of anaesthetic and the patient's general condition. Fit patient, patients who have stopped smoking for many months are ideal candidates for this contour correction surgery.

Technique was first performed by a French surgeon, Charles Dujarier. In 1926, a French model underwent contour surgery of leg by Charles Dujarier to later develop gangrene of the leg was a tragic story. This was the oldest history about contour surgery. In 1960, curettage surgery was proposed with variable results and morbidity. Again a French surgeon, Dr Yves-Gerard Illouz, in 1982 originated a method of suction-assisted lipolysis after infusing fluid into tissues using blunt cannulas and high-vacuum suction—Illouz method. In 1985, Klein and Lillis described the "tumescent anaesthesia", a regional technique which with high volumes of fluid containing local anaesthetic with intravenous sedation. High volume of fluid and potential toxicity of xylocaine tumescent technique later changed to low volume "super wet" tumescence. In the late 1990s, ultrasound was introduced to facilitate the fat removal by first liquefying the fat using ultrasonic energy. But it showed more complications. Laser thermal lipolysis is modern technology. Whatever the type is used, it is the surgeon's skill finally matters for adequate liposuction to create normal contour without complications.



Fig. 33-6: Robotic snake instrument.

Diabetes, cardiac illness is the relative risks for liposuction.

Principles: To remove the right amount of fat; to cause the least disturbance of other tissue, such as blood vessels; to keep the person's fluid balance normal.

Sites where liposuction is done: Abdomen; hips; outer and or inner thigh; flanks; back; inner knee; upper arm; submental/chin; gynecomastia in males.

Preparation

Anticoagulants should be avoided for 2 weeks. Pre-operative antibiotics are needed. Cardiac evaluation, respirator exercises are given.

Technique

Power-assisted liposuction cannula is often used nowadays.

Fat is removed through a cannula and a suction device. Liposuction technique depends on the amount of fluid injection and the mechanism by which the cannula functions. The surgeon creates forwards and backwards motion, carefully through the fat layer, breaking up the fat cells and drawing them out of the body by suction. The patient will feel only a scraping or rasping sensation from the cannula movement. During liposuction, multiple small puncture wounds are made for inserting the cannula that can vary in size depending on the technique **(Fig. 33-7)**.

Ultrasound-assisted liposuction is useful for working on more fibrous areas, like the upper back or male breast area. It takes longer time; but with less blood loss.

Water-assisted liposuction is done by using a thin fan-shaped water beam, which loosens the structure of the fat tissue, so that it can be removed by a special cannula. During the liposuction, the water is continually added and almost immediately aspirated via the same cannula. It utilizes less infiltration solution and oedema is less in this.

Postoperative Management

A compression garment which can easily be removed by the patient is worn for four weeks, this garment must have elasticity. Analgesics may be needed. Patient can go for work in 1-2 weeks.

Side-effects

Bruising which is painful; swelling; scars; pain in the abdominal wall; numbness in the abdomen which will subside in few weeks; post-operative weight gain; restricted mobility due to abdominal binder; pain, inflammation.



Fig. 33-7: Liposuction technique and device.

Complications

Allergic reaction to medications or material used during surgery. Infection: any time the body is incised or punctured, bacteria can get in and cause an infection. Damage to the skin: most surgeons work on the deeper levels of fat, so as to avoid wounding the skin any more than they must for the insertion of the cannula. Sometimes the cannula can damage tissue beneath the skin. Skin necrosis can occur rarely; and adjacent skin falls off in the necrotic area. Injury to internal organ during puncture of the abdominal wall can occur; such as the intestines during abdominal liposuction. Contour irregularities can occur. Thromboembolism and fat embolisation can develop occasionally. Burns due to friction of the cannula can occur. xylocaine toxicity presenting as tingling and numbness and eventually seizures, followed by unconsciousness and respiratory or cardiac arrest. Fluid imbalance as fat contains a lot of fluid and is removed in liposuction, and also the surgeon injects fluid for the procedure, a very large amount for tumescent liposuction, fluid imbalance can set in. This could happen afterwards, after the patient is at home. If too much fluid remains in the body, the heart, lungs and kidneys could be badly affected.

DRESSINGS

They are the materials used to cover wounds, ulcers to provide support and to encourage healing.

Advantages

It covers the wound and so prevents further contamination. It gives comfort to the patient.

Disadvantages

It may get soaked. It may delay the epithelial layer formation.

Types

Dry dressings: It is used in clean, sutured operated wound. It is not changed at regular intervals.

Wet dressings: It is used in ulcers and wounds. Dressings are made wet by using jelly or Sofra-Tulle sheets.

Components of Dressing

Inner contact layer: It is non-absorbent and only allows secretion to pass into the absorbent layer. It does not allow penetration of granulation tissue. It is usually kept wet. Either mesh gauze or Sofra-Tulle is used.

Intermediate absorbent layer made up of cotton which absorbs the secretions.

Outer layer as supportive is made up of gauze.

Dressings are fixed to the place by—Bandages; Plasters; dynoplast; crepe bandages; depending on the condition and amount of discharge from the wound/ulcer, it is changed as required—twice a day/once a day/once in two days. Small dressings are done without anaesthesia. Large areas like burn wounds or dressing in children require general anaesthesia.

BANDAGES

Technique of bandaging is called as ***dysmergia***.

Indications

To reduce the swelling like in lymphoedema; to keep dressings in position; to support splint; to stop bleeding/oozing.

Types of Bandages

Roller bandages: It is a continuous roll of material, which is rolled over the part to cover the area. It is used in limbs.

It is available in different lengths and widths—1 inch, 2 inches, 4 inches or 6 inches. It is used in different ways.

- ***Circular turns:*** Continuous rolls placed over the same place.
- ***Spiral turns:*** After the initial turn of the bandage, it ascends proximally overlapping the distal 2/3rd of the previous turn.
- ***Reverse spiral turn****:* Here each spiral turn is reversed in opposite direction so as to attain uniform pressure. It is used in limbs and areas which end as cones.
- ***Figure eight turn:*** It is used in knee, elbow, wrist, ankle and for clavicle.
- ***Recurrent turn:*** It is used in head and amputation stump. Here initially circular rolls are made and over that half turns are made to cover other parts of the area required.
- ***Spica bandage:*** It has got ascending and descending turns, with each turn overlap and cross each other. It is used in hip, groin, shoulder, breast or thumb. *Spica means eye of a bean.*

'T' bandages: It is used in perineum and groin.

Tailed bandages**:** It may be four tailed bandages or many tailed bandages. It is used to support dressings on a wide area like in burns dressing, over abdomen or chest wall.

Tubular bandages: These are stockings which are unrolled over the limb to give pressure effects. It is used in lymphoedema, varicose veins and in the post-operative period following surgeries of the limb.

Triangular bandage: These are used for supporting the elbow or forearm. Here a wide gauze is used to cover the arm, forearm and elbow, which again winds around the neck.

Cravat bandages: It is a folded type of triangular bandage, which is used as sling around the neck, when elbow requires to be rested.

Principles of Bandaging

Bandage is applied to the part from distal to proximal end. Proper positioning of the limb is a must before bandaging. After initial few circular turns, the required type of bandaging is then done. Bandage is unrolled outwards. During bandaging, latter turn should overlap 2/3rd of earlier turn. Firm, adequate pressure should be used during bandaging. After completing the procedure, the knot should not lie over the area or over the bony points or over the back. It should not cause venous or arterial compression. Digits should be left open and circulation in the digits should be observed for.

Size of bandages used at different places are: Finger/toe—One inch; Arm—Two and half inches; Leg—Four inches; Thigh—Six inches; Trunk—Six inches; Head—Four inches.

Index

A

Abbe flap 434
Abbernethy's incision 535, 1061
Abdominal aortic aneurysm 308
Abdominal compartment syndrome 223
Abdominal diagnostic paracentesis 207
Abdominal incisions 522
Abdominal oesophagus 580
Abdominal retractors 540
Abdominal tonsil 732
Abdominal trauma 206
Aberdeen knot 53, 524
Aberrant renal artery/vein 1065
Aberrant right hepatic artery 801
Above knee amputation 259
Abrahamson nylon darning 1134
Abscess in axilla 245
Abscess neck 245
Accessory appendicular artery of Seshachalam 732
Accessory auricle 414
Accessory pancreatic duct 694
Accessory thyroid arteries 442
Acellular dermal matrix graft 506
Achilles heel 786
Ackerman 1045
Acriflavine 12
Acron head stripper 355
Acute abdominal compartment syndrome 23
Acute adrenal insufficiency 29
Acute compartment syndrome 315
Acute limb ischaemia 316
Acute lung injury 19
Acute renal failure 22
  non-oliguric 22
  oliguric 22
Acute suppurative tenosynovitis 230
Acute wound failure 28
Adair Hadfield operation 478
Adductor canal 298
Adrenal incidentalomas 1108
Adson's fine suction tip 94
Adson's toothed forceps 38
Advanced trauma life support 203
Advancement flap 178
Air plethysmography 345
AIS scoring 198
Albucasis 3
Alcock's canal 981
Aldrete scoring system 69
Alexis Carrel 6, 273
Alfred Blalock 5
Ali Javan 124
Allen Oldfather Whipple 4
Allen's test 226
Alligator forceps 93
Allison's lung retractor 85
Allis' tissue holding forceps 77
Allograft 168
Altemeier's perineal rectosigmoidectomy 1007
Ambroise Pare 3, 1128
Ambu bag 118
Ambulatory phlebectomy 369
Ambulatory selective varices ablation 362
Amdrup Johnston 660
Ampulla of Vater 692
Amputation of index finger 266
Anal columns of Morgagni 981
Anal crypt 981
Anal encircling 1008
Anal fistula plug repair 1038
Anal sinus 981
Anastomotic false aneurysm 288
Anastomotic leak 24
Anatrophic pyelolithotomy 1074
Anderson Hynes operation 1062
Andreas Vesalius 2
Andrew's operation 1134
Aneurysm needle 90
Angelchick prosthesis 596
Angle of His 582, 634
Angle of sorrow 669
Ankle block 196
Anorectal junction 980
Anorectal myectomy 977
Anterior abdominal wall 518
Anterior accessory great saphenous vein 347
Anterior epistaxis 30
Anterior extraserous approach 237
Anterior jugular vein 388
Anterior tibial artery exposure 307
Anterior transposition of ulnar nerve 380
Anterior triangle of neck 388
Anterior vagus 637
Anterolateral neck dissection 405
Antisepsis 11
Antonio Scarpa 1128
Antrectomy 666
Aortic clamping 209
Aorto-vena caval fistula 313
Aortoduodenal fistula 310
Aortoenteric fistula 310
Aortofemoral bypass graft 288
Aortoiliac bypass graft 296
Aortoiliac thromboendarterectomy 282
APACHE 32
Apical subungual infection 226
Appendices epiploicae 940
Appendicular abscess 752
APS 32
Arc of Riolan 940
Arcuate line 519
ARDS 19
Areola sparing mastectomy 493
Argon beam coagulator 127, 764
Argon laser 125
Arterial allograft 285
Arterial autografts 285
Arterial ligation 276
Arterial xenograft 285
Arteriography 208
Arteriotomy 275
Arteriovenous fistula 332
Art of surgery 1
ASA grading 11, 69
Ascending venography 346
Asepsis 11
Asepto syringe/Dakin's syringe 113
Aspiration 19
Astley Paston Cooper 1128
Atelectasis 18
Atraumatic needle 87
Auchincloss operation 483
Austin Jones 725
Autoclave 11
Autograft 168
Autotransfusion 208
Auxiliary partial orthotopic liver transplantation 787
Avascular endopelvic fascial plane 986
Axial pattern flaps 175

Axillary abscess 134
Axillary reverse mapping 471
Axillary sampling 480
Axillary tail of Spence 470
Axillofemoral graft 305
Axonotmesis 379

B

B-Lynch suture 1258
Babcock's forceps 77
Backhand manoeuvre 1
Backhaus' towel clip 72
Baid test 133
Baker's tube 712
Bake's dilator 93, 844
Balance's sign 213
Balfour's self-retaining retractor 83
Ball tipped needle 303
Ball valve mechanism 1123
Bancroft Plenk operation 672
Bandelette of Thomson 1126
Bapat's procedure 887
Bard-Parker's handle 88
Bare area of stomach 634
Bartholin cyst 245, 1247
Bascom technique 1010
Bassini's stitch 1133
Baton round injury 199
Battle's incision 520, 527, 1124
Beck Carrell 642
Bectin Dickenson syringe 113
Beger procedure 875
Beley's mark IV antireflux procedure 586
Belghiti liver hanging manoeuvre 774
Below knee amputation 255
Belsey diverticulopexy 629
Bench surgery 1071
Bendavid circle 1127
Bennett 638
Benson pyloric spreader 691
Berger's anterior approach 269
Bernard von Langenbeck 4
Berne modification 875
Berry's ligament 454
Besley's mark IV operation 595
BHEARS triangle 444
Bickford's bronchial clamp 86
Bier's block 196
Bilateral neck dissection 412
Bile leak 24
Biliary atresia 864
Billroth 666
Billroth I operation 666
Bipolar cautery 65, 122
Birmingham staging 683
Bishop-Koop operation 731
Bivalved Park's retractor 996
Bladder neck retractor 84
Bladder sound 105
Blandy second approach 223
Blanket sutures 46
Blow hole procedure 944
Boari flap 1096
Boari's flap 1062
Boerema-Crile operation 792
Boerema operation 599
Bogros 1128
Boiling 11
Bolus grafting 170
Bone cutting forceps 115
Bone elevator/bone lever 115
Bone marrow aspiration 157
Bone nibbler 116
Bonney Reverdin needle 88
Bonney's blue 173
Boomerang needle 105
Bouin's fluid 1226
Bouin's solution 157
Bowie-Dick test 11
Boyd's perforator 348
Boyd's amputation 253
Brachial endarterectomy 317
Brachial plexus injury 379
Brachiobasilic AV fistula 334
Brachiocephalic AV fistula 334
Braided 112
Braithwaite skin grafting knife 115
Branchial cyst 395
Branchial fistula 395
Braun's enteroenterostomy 674
Braun's jejunojejunostomy 650
Breast abscess 134
Breast conservative surgery 480, 488
Breast reconstruction 494
Brigham 683
Brodel avascular plane 1051
Brodel's line 1071
Brodie's abscess 245
Bronchoaortic constriction 580
Bronchoscopy 162
  flexible 162
  rigid 162
Brooke's method of maturation of urinary conduit 1094
Brunschwig's operation 989
Buck's fascia 1191
Buie's marsupialisation 1015
Bulldog clamp 75
Burgess amputation 256
Burge test 663
Burhenne method 842
Burst abdomen 28, 521
B'jork flap 141

C

Cabana sentinel node 1192
Cabot's nephrostomy 1070
Cadiopulmonary resuscitation 21
Caecopexy 944
Caecostomy 944
Calf thrombosis 374
Calot's first method 813
Calot's triangle 800
Canal of Nuck 1121
Cantlie's line 756
Capacitive coupling injury 569
Carbon dioxide laser 125
Cardiac arrest 20
Cardiac injury 206
Cardiac orifice 634
Carl von Langenbeck 811
Carotid blow out 411
Carotid body tumour 401
Carotid endarterectomy 281
Carotid triangle 389
Carpal tunnel syndrome 380
Carrel and Guthrie 285
Carrel patch 783
Carrel's triangulation technique 189, 276
Carrier 176
Carwardine 650
Carwardine's clamp 653
Carwardine's twin intestinal occlusion clamp 92
Catalona inguinal block dissection 1200
Catgut 110
Catheter directed sclerotherapy 371
Catheter duodenostomy 672
Cattell manoeuvre 694
Cattell's operation 1164
Cattle-Braasch manoeuvre 871
Caudal anaesthesia 197
Caudal maxillectomy 432
Caudate lobe 754, 755
Cauliflower ear 414
Cautery dissection 40
Cavitron ultrasonic surgical aspirator 129, 761
Cavocavostomy technique 785
Cayenne pepper look 656
CEAP classification 346
Celestin tube 633
Celioscopy 7
Cellan Jones 638
Central maxillectomy 432
Central venous pressure 31
Cervical constriction 580
Cervical lymph node biopsy 403
Cervical oesophagostomy 631
Cervical oesophagus 579
Cervicothoracic sympathectomy 384
Cesar Roux 674
Cetrimide 12
Chain-of-lakes 810
Chao 464
Charaka oath 7
Charged coupled device 548
Charles Dujarier 1307
Charles Hill 68
Charles Huggins 6
Charriere unit 132
Cheatle's cut 699
Cheatle's forceps 71
Cheatle's gallstone scoop with or without hook 93
Cheek retractor 84
Cheif cells 401, 638
Chemical sympathectomy 384
Chemosurgery 150
Cherney's incision 531, 1259
Chester B McVay 3
Chevassou manoeuvre 1229
Chevron incision 535, 895
Chiba or Okuda needle 810
Child-Pugh grading 760
Childs-Phillips mesenteric plication 712
Child Turcote Pugh scoring system 783
Child's operation 876
Chisel 116
CHIVA 362
Chlorhexidine 12
Chloroxylenol 12
Cholecystectomy 811
Chongquing's sharpened curved mosquito clamp 163
Chopart's amputation 252

Chorda tympani 502
Christian Bernard 6
Chronic adrenal insufficiency 29
  primary type 29
  secondary type 29
Chronic afferent loop obstruction 691
Chronic efferent loop obstruction 691
Chronic wound 27
Churchill and Sweet 621
Chvostek's sign 461
Cimino-Brescia AV fistula 333
Cinacalcet 466
Circular open amputation 248
Circular staplers/EEA staplers 163, 167
Circulating nurse 13
Circumareolar incision Webster 474
Circumcision 144
Clarimount approach 237
Classification 26
Classification of arterial substitutes 285
Claude Couinaud 756
Cleft lip and palate 414
Clitoris 1240
Cloquet's hernia 1178
Closed amputation 248
Closed siphon drains 99
Closed suction drains 99
Clostridium difficile 24
Clutton's dilator 105, 1099
Cobra head 204
Cockett perforator 348
Codman's stripper 355
Cohen's law of meningitis 158
Cold abscess 138
Cold laparoscope 547
Cole tube 97
Colles' reflected part of inguinal ligament 1124
Collingwood Stewart's ring bladed hernia forceps 107
Collis' vertical gastroplasty 597
Colonic ischaemia 310
Colonic preparation 10
Commando operation 429
Commisure reconstruction 439
Common hepatic artery 636
Common iliac nodes 984
Common peroneal nerve injury 379
Communicating vein of Giacomini-Cruveilhier 347
Compartment excision 154
Compartment syndrome 376
Complications of mastectomy 488
Complications of TPN 33
Compound palmar ganglion 233
Computer assisted designing 271
Condon procedure 1134
Conley's point 504
Connell stitch 653
Connell suture 699, 700
Connor 683
Conn's syndrome 1108
Consent 8
  extension doctrine 8
  implied 8
  substituted 8
  valid 8
Consumer Protection Act 7
Continuous locking sutures 46
Continuous mass closure 46
Continuous over and over simple suture 43
Continuous over and over suture 46
Cooley 288
Cooper's fascia 520, 1125
Cooper's glands 1054
Coopting sutures 211
Cornu 1241
Coronary vein 636
Corpora cavernosa 1190
Corpus spongiosum 1190
Corrugated rubber drain 98
Cotton 111
Counter incision 478
Courvoisier 2
Cravat bandages 1309
Cremasteric reflex 1124
Cresol 12
Cricoid hook 96
Criminal nerve of Grassi 637
Crimping textile grafts 287
Criteria for weaning ventilator 19
Critical view of safety 826
Cross leg flap 183
Crown stitch 669, 703
Crow's foot 635
Crushing Payr's clamp 673
Cryotherapy 129
Cryptoglandular disease 1030
Crypts of Morgagni 1034
C shaped teractor—Roux 82
Culling 919
Curling's ulcer 22
Cushing suture 49, 700
Cushing's ulcer 22
Cutaneous flap 175
Cutaneous staplers 163
Cutting needles 43
Cystoduodenostomy 891
Cystogastrostomy 889
Cystojejunostomy 891
Cystoscope 118
Cystoscopic litholapaxy 1088
Czerny's retractor 81

D

3 D laparoscope 561
Dacron 286
Damage control surgery 203
D Arsonal 121
Davies and Starr buttock flap 1015
Davis T-tube ureterostomy 1065
Dean 638
Deaver's retractor 82
De Bakey's vascular clamp 75
Decannulation of tracheostomy 143
De Chauliac 1128
Deep artery of penis 1191
Deep inferior epigastric perforator flap 495
Deep inguinal ring 1121
Defibrillation technique 22
De Humani Coporis Fabrica Libri 2
Delayed exposed graft 172
Delayed primary closure 202
Delorme's operation 1000
Delorme's procedure 998
Delphian nodes 442
Deltopectoral flap/Bakamjian flap 178
Denervated pancreatic flap 887
Denis-Browne procedure 1099
Denonvillier's fascia 980
Depage-Janeway 642
Depage-Janeway gastrostomy 643
DePaula 624
De Pezzer catheter 103, 649
De Quarvain's stenosing tenosynovitis 377
Dermabrasion 190
Descending venogram 346
Desjardin's choledocholithotomy forceps 92
Desjardin's forceps 840
Dettol 12
Devadhar rectal plication 999
Devine and Horton's flap 1192
Devine's double-barrel colostomy 945
Devlin's classification 949
Diagnostic laparoscopy 208
Diagnostic peritoneal lavage 207
Diaphragmatic constriction 580
Diaphragmatic injury 206
Diathermy 64, 568
Digastric flap 506
Digastric triangle 389
Digital nerve block 196
Dinner knife position 36, 89
Disinfection 11, 573
Disobliteration 278
Distal arterial bypass 307
Distal gastric unit 635
Distal pancreatectomy 910
Distal splenorenal shunt 790
Distant flap 176
Diversion colostomy 944
Diverticulectomy 630
Dobutamine 32
Documenting 7
Dodd perforator 348
Doderlein 1241
Dog ear 61
Dohlman's operation 395
Dolphin nose needle 87
Donor criteria 783
Doodley's lavage 733
Dopamine 32
Dornier lithotripter 1071
Dorsal artery of penis 1191
Dorsal fissurectomy 1030
Dorsalis pedis artery exposure 307
Dor's anterior partial fundoplication 587
Dos Santos 282, 285
Double/triple gallbladder 802
Doyen's intestinal occlusion clamp 92
Doyen's mouth gag 114
Doyen's retractor 83, 1252
Doyen's rib rasparatory 85
Doyen's towel clip 72
Dragstedt 656
Drapanas and McDonald 207
Dr Belding H Scribner 332
Dresslers quadrangle 1199
Dr Frederic E Mohs 150
Dr Nilis Alwall 332
Dr RM Waters 68
Dr Wayne Quinton 332
Dr Willem Kolff 332
Dr Yves-Gerard Illouz 1307

Dudd pylorectomy 666
Duluq approach 1157
Dumphy operation 1000
Duncan slip knot 59
Dundee Ski needle 53
Dunhill pillow 448
Duodenal atresia 694
Duodenal blow out 684
Duodenal fistula 641
Duodenal injury grading 216
Duodenal obstruction 641
Duodenal stump leakage 684
Duplex scan 345
Dupuytren's enterotome 110
Duval procedure 876
Duval's lung holding forceps 86
Dye laser 125
Dynamic lines of Kraisl 481
Dysejaculation 1186
Dysphagia lusoria 322

E

EACA 67
Early dumping syndrome 686
ECK fistula 787
Ectopic salivary gland 513
Ectopic thyroid tissue 440
Ectropion 413
Edoardo Bassini 4
EE Shouldice 1129
Ejection fraction 345
Elbow disarticulation 267
Elective amputation 247
Elective laparotomy 515
Electrical dermatome 115
Electrocautery 121
Electrodessication 369
Electrosurgery 568
Ellick's evacuator 1088
Emergency amputation 248
Emergency laparotomy 515
Emergency splenectomy 214
EMLA 196
Enaz Moniz 285
Endarterectomy 278
Endoabdominal fascia 520
Endoaneurysmography 4
Endocrine cells 638
Endoleak 315
Endoloops 59
Endopelvic fascia 1242
Endoscopic parathyroidectomy 466
Endostapler 163
Endostaplers 67, 571
Endotrol tube 97
Endovascular aneurysm repair 313
Endovenous laser ablation 126
Endovenous laser ablation treatment 364
Energy sources 566
Enteroenterostomy 852
Entropion 413
Enucleation 154, 413
Epi-perineurorrhaphy 378
Epidural anaesthesia 197
Epineurorrhaphy 378
Equal flap 247
Erb's point 408
ERCP 809
Ernest Heller 585
Ethylene oxide sterilisation 12, 577
EUSOL 12
Eversion carotid endarterectomy 282
  type 1 282
  type 2 282
Evisceration 413
Ewald's gastric tube 650
Excimer laser 125
Expanded polytetrafluoroethylene graft 288
Expert witness 7
Exposed graft 172
Exposure of abdominal aorta 328
Exposure of ascending aorta and arch of aorta 326
Exposure of axillary artery 323
Exposure of brachial artery 324
Exposure of carotid artery 319
Exposure of descending thoracic aorta 327
Exposure of femoral artery 330
Exposure of iliac arteries 329
Exposure of radial and ulnar arteries 325
Exposure of subclavian artery 322
Exposure of vertebral artery 321
Extended Beger's procedure 887
Extended left hepatectomy 781
Extended proximal gastric vagotomy 638
Extended radical mastectomy 493
Extended right hepatectomy 781
Extended supraomohyoid neck dissection 405
Extended total mastectomy 488
External anal sphincter 981
External iliac nodes 984
External jugular vein 389
External laryngeal nerve 443
External oblique fascia 518
External oblique muscle 518
External supravesical fossa 1122
External supravesical hernia 1122
Extra-anatomical graft 305
Extracorporeal knotting 54
Extracorporeal ligature 567
Extracorporeal shock wave lithotripsy 128
Extragastric haemorrhage 684

F

Face lift incision 504
Facial nerve 502
Facial nerve injury 379, 508
Falciform ligament 754
Faraboeuf's rasparatory 86
Fascial dehiscence 521
Fascia lunata 981
Fascia of Waldeyer 980
Fascia of Zuckerkandl 1050
Fascia transversalis 520
Fasciocutaneous flap 175
Fat embolism 19
Father of geology 500
Father of laparoscopy 7
Father of modern surgery 3
Features of ideal graft 285
Fegan's sclerotherapy 369
Felon 227
Female metal catheter 104
Femoral embolectomy 317
Femoral nerve 1125
Femorofemoral crossover graft 305
Femoropopliteal bypass graft 297
Fergusson's bone holding forceps/lions forceps 116
Fibreoptic laryngoscope 459
Fiddle-bow position 89
Field block 196, 1129
Figure of eight 376
Filiform bougies 105
Filshie clip 1261
Fine lengthy straight and bayonet forceps 118
Finger dissection 38, 39
Finney's pyloroplasty 665
Finney's strictureoplasty 714
Finochietto retractor 586
Fisch nerve hook 81
Fistula-in-ano 1033
Fistula bistoury 109
Fistulectomy 1041
Fistulotomy 1038
Fitzpatric operation 1192
Flap-splitting technique 1301
Flap necrosis 248
Flatus tube 107
Floating gallbladder 800
Foam sclerotherapy by Tessari 370
Fogarty vascular clamp 274
Foley's catheter 100
Foot drop 378
Foramen caecum 428
Foramen of Langer 470
Forehand suturing 1
Forequarter amputation 269
Formaldehyde 12
Forrest classification 664
Fortner's regional pancreatectomy 906
Fourestier 7
Four quadrant tap 208
Fowler-Davis approach 735
Fowler-Weir approach 735
Fowler's position 985
Francis D Moore 6
Franke 4
Franz Hesselbach 1128
Fred Bates Lund 800
Free flaps 175
Free reversed saphenous vein graft 303
Frenulum linguae 399
Freyer's evacuator 1088
Freyer's suprapubic transvesical prostatectomy 1096
Frey's procedure 872, 875
Frey's syndrome 510
Friedrich's lung holding forceps 86
Frie's modified Bernard facial flap 436
Fruchaud's myopectineal orifice 1127
Fuller's biflanged tracheostomy tube 20
Fuller's bivalved tracheostomy tube 95, 140
Fundiform ligament of penis 1191
Fundus first method 814

G

Gabriel syringe 113, 1017
Gagner 466
Gagner's transabdominal lateral approach 1108
Gaillard Thomas incision 474
Gallie cup 117
Gallie's needle 88, 1129
Gambee single layer full thickness 49

Gambee single layer suture 700
Gant-Miwa operation 1008
Gas bloat syndrome 602
Gas gangrene 202
Gasless laparoscopy 563
Gas plasma sterilisation 577
Gastric conduit 607
Gastric mucosal resection 666
Gastric preparation 10
Gastric remnant carcinoma 689
Gastric remnant necrosis 686
Gastrocnemius muscle flap 181
Gastrocolic ligament 635
Gastrohepatic ligament 582
Gastrojejunocolic fistula 689
Gastrosplenic ligament 582, 635, 917
Gastrostomy 642
Gelatin sponge 67
Gelhard's operation 1192
Genitofemoral nerve 1125
Genu 502
George Kelling 7
Germain Cloquet 1128
Gerota's fascia 1045, 1050
Giant ulcer 639
GIA staplers 163
Gibbon's catheter 103
Gigli's saw 117
Gilbert classification 1127
Gilbert mesh repair 1147
Gillies fan flap 437
Gillies flap 434
Gillie's amputation 252
Gilroy Bevan triad 706
Gilvernet incision 537, 1059
Gimbernat ligament 1121
Gladu 7
Glasgow coma scale 199
Glove drain 99
Glover's clamp 309
Gluck Sorenson incision 390
Glutaraldehyde 12, 575
Golden hour 203
Goldner method 377
Goligher's operation 999
Goodsall's operation 998
Goodsall's rule 1035
Goose foot 500
Gordon Gould 124
Graft failure 288
Graft infection 288
Graham 638
Graham operation 639
Granny knot 61
Grasping position 36, 89
Grassi test 663
Greater anterior nerve of Mitchell 637
Greater petrosal nerve 502
Great saphenous vein 347
Griesfield modification of Martin's
  classification 729
Griffith critical point 941
Gritti-Stokes amputation 259
Groeneveldt 585
Groin flap 179
Gry and Morton method 691
Guillotine amputation 248
Gunz fissure 757

H

Hach perforator 348
Haematoma 26
Haematoma of ear 413
Haemostasis 62
Haemostatic figure of eight suture 43
Haemothorax 205
Haeney's clamps 1278
Hagedron reverse flattened point fish hook
  needle 88
Haimovici triad 315
Half-Pringle manoeuvre 760
Halogens 12
Halsted-Tanner slide operation 1134
Halsted 1129
Halsted mosquito forceps 74
Halsted nodes 471
Halsted radical mastectomy 488
Halsted suture 49, 700
Hamburger-Brennan-Mahorner self-retaining
  retractor 448
Hamilton-Bailey technique 504
Hamilton Stewart operation 1070
Hand amputations 265
Hanley's renal cavernostomy 1061
Hans Christian 7
Harmonic ace 569
Harmonic scalpel 128, 569
Harris Benedict equation 33
Hartley-Dunhill operation 447
Hartmann's operation 975
Hartmann's pouch 800
Hartmann's procedure 988
Harvey Cushing 5
Hasson's open method 554
Hasson's trochar and cannula 550
Hawkin's-Amblar's dilator 1243
Heath suture cutting scissor 91
Hegar's dilator 1243
Heimlich valve 161
Heineke-Mikulicz pyloroplasty 604, 664
Heineke-Mikulicz stricturoplasty 714
Heinz bodies 918
Helium-neon laser 125
Heller's cardiomyotomy 585
Helmstein balloon degeneration 1088
Hemimandibulectomy 417
Hemimaxillectomy 432
Hemithyroidectomy 446
Henle gastrocolic vein 637
Henry Gray's cholecystectomy forceps 93
Hepaticojejunal anastomosis 898
Hepatoduodenal ligament 635
Hepatogastric ligament 635
Hepatorenal syndrome 10
Hepp-Couinaud approach 860
Hernia bistoury 107
Hernia director 108
Herniotomy 1129
Hesselbach's triangle 1122
Hexachlorophane 12
Hi-low jet three-lumen tracheal tube 97
Hiatal repair 600
Hibitane 12
Highly selective vagotomy 637
Hill Ferguson technique 1020
Hill's operation 595
Hilton's method 134
Hind quarter amputation 261
Hip disarticulation 260
Hippocrates 2
Hippocratic oath 7
Hockey stick incision 1109
Hollister Bell cap technique 144
Holmium laser 125
Holy plane of Heald 986
Homer 866
Hopkins 547
Horizontal mattress suture 43
Horseshoe fistula 1041
Horsley 666
Horsley's modification 670
House-Brackmann score 509
Howship Romberg sign 1125
Hudson brace with perforator and burr 110
Hulka clip 1261
Humby's knife 115
Hungry bone syndrome 461
Hunter's adductor canal perforator 348
Hydrogen peroxide 12
Hymen 1240
Hyperhidrosis 384
Hypertensive crisis 20
Hyperthyroid crisis 29
Hypogastric flap 179
Hypoparathyroidism 460
Hypothyroidism 29, 462
Hysterotomy 1247

I

Ideal stump 248
Ileofemoral cross over graft 297
Ileofemoral graft 296
Ileostomy closure 724
Iliohypogastric nerve 1124
Ilioinguinal nerve 1125
Iliopubic tract 1126
Inavissevich approach 1221
Incineration 11
Incentive spirometer 17
Incisional hernia 521
Incision of indecision 515
Indigocarmine 1278
Indocyanine green clearance test 760
Inferior epigastric artery 521
Inferior gluteal artery 983
Inferior hypogastric plexus 984
Inferior phrenic vein 656
Inferior rectal artery 983
Inferior thyroid artery 442
Inferior thyroid vein 442
Infiltration block 196
Infrahyoid muscles 440
Inguinal canal 1121
Inguinodynia 1185
Injection sclerotherapy for varicose veins 369
Injury severity score 198
Inlay method of suturing 276
Innominate fascia of Gallaudet 518, 1123
Inokuchi shunt 790
In situ saphenous vein graft 299
Intercostal muscle flap 631
Intercostal block 196
Intercostobrachial nerve 472
Interfoveolar Hesselbach's ligament 520, 1125
Internal anal sphincter 981

Internal iliac artery 982
Internal iliac nodes 984
Internal oblique muscle 518
Internal pudendal artery 983
Interscapulothoracic amputation 269
Intersphincteric abscess 1033
Intestinal atresia 729
Intestinal intubation 712
Intra-abdominal abscess 235
Intracorporeal suture 568
Intracorporeal suturing and knotting 53
Intracranial abscess 245
Intragastric haemorrhage 684
Intraosseous fluid therapy 194
Intraperitoneal rupture 312
Investing layer of deep fascia 389
Iodophors 12
Ionising type radiation 11
Irving's tubal ligation 1261
Ischiorectal abscess 134, 1031
Ischiorectal fossa 980
Island flap 175, 178
Isograft 168
Isthmectomy 447
IVC filters 375
Ivor Lewis operation 618
Izbicki V shaped ventral pancreatic excision 887

J

Jackson Pratt drain 543
Jackson's staging of carcinoma penis 1192
Jackson's tracheostomy tube 95, 140
Jackson's veil 938
Jacobsen intratympanic parasympathetic neurectomy 510
Jacques Perissat 812
James Nicoll 68
Jammerecke 669
Jamming slip knot 53
Janos Verres 7
Jean Louis Petit 811
Jeau 642
Jejunogastric intussusceptions 691
Jening's mouth gag 114
Jenkin's rule 46
Joel Cohen's straight transverse incision 531
Johansen stepladder procedure 439
Johanson's urethroplasty 1099
John Collins Warren 3
John H Gibbon 5
John Hunter 3, 1128
Joll's thyroid retractor 84, 448
Joll's triangle 444
Jonathan Rhoads 6
Joseph E Murray 2
Joseph Lister 3
Juan Parody 313
Juergen-Breunner needle 87
Julio Palmaz 313
Jurasz operation 889

K

Kader-Senn 642
Kalk 7
Kanavel signs 233
Karapandzic flap 434, 437
Karydaki's excision 1009
Kasai's operation 864
Kaspar Stromayr 1128
Keel operation 1164
Keetley-Torrek procedure 1226
Kehr hockey stick modification 812
Kehr's sign 213
Kehr's T tube 93
Kelly's proctoscope 108
Kennedy duodenoplasty 665
Kessler method 377
Keyland's retractor 82
Kidney biopsy 157
Kidney hilum retractor 85
Kidney tray 117
Killian's dehiscence 579
Kimura's diamond shaped anastomosis 695
Kirwin's operation 1085
Klatskin tumour 857
Knee joint disarticulation 256
Knitted graft 287
Knots types 112
Kobald 725
Kocher 666
Kocherisation 5, 584, 694, 871
Kocher's 4th throid vein 442
Kocher's approach 416
Kocher's forceps 5, 76
Kocher's gland holding forceps 78
Kocher's incision 5, 812
Kocher's method 5
Kocher's occlusion clamp 92
Kocher's subcostal incision 522, 533
Kocher's test 5
Kocher's thyroid dissector 79
Kocher's thyroid incision 5
Kocher's thyroid retractor 84
Kocher's vein 5
Koch's ileal conduit 1062
Koontz operation 1134
Kous Netzof aluminium needle 88, 211
Kraske's approach 987
Krukenberg amputation 267
Krypton laser 125
KTP laser 125
Kunlin suture 277
Kuntz nerve 384
Kurt Semm 7
Kustner's incision 531

L

Labia majora 1240
Labia minora 1240
Ladd and Gross procedure 1226
Ladd's band 730
Ladd's operation 730
Lahaut's operation 1000
Lahey and Cattell's incisions 1015
Lahey's method 672
Laimer's triangle 579
Lane twin clamps 650
Lane's gastrojejunostomy clamp 653
Lane's needle 88
Lane's paired gastrojejunostomy clamp 92
Lane's tissue holding forceps 77
Langenbeck's retractor 81
Langenbuch 759
Langer's line 481
Lanz crease incision 735
Laparolift 563
Laparoscope 547
Laparoscopic instruments 118
Laparoscopic Nissen's fundoplication 603
Laparoscopic posterior mesh rectopexy 998
Laparoscopic pyloromyotomy 692
Laparoscopic retroperitoneal lumbar sympathectomy 384
Laparoscopic ultrasound 561
Laparotomy circuit 521
Large bowel injury 219
La Roque repair 1136
Laser assisted vascular anastomosis 126
Laser endarterectomy 125
Laser shield endotracheal tube 97
Late dumping syndrome 687
Latent period of Bandet 213
Lateral anal sphincterotomy 1028
Lateral approach thyroidectomy 458
Lateral cutaneous nerve of thigh 1125
Lateral ligaments of rectum 980
Lateral pectoral nerve 472
Lateral pterygoid muscle 421
Lateral segmentectomy 768
Latissimus dorsi 472
Latissimus dorsi flap 179
Latissimus dorsi muscle/myocutaneous flap 495
Latissimus dorsi myocutaneous flap 494
Latzko procedure 1301
Laugier's femoral hernia 1178
Lawson-Tait choledocholithotomy forceps 93
Lee de Forest 121
Left anterior extraserous approach 237
Left gastric artery 636
Left gastroepiploic artery 636
Left hemihepatectomy 768
Left hepatectomy 774
Left lateral sectionectomy 781
Left palmer point 559
Left subcostal incision 534
Left thoracoabdominal approach oesophagogastrectomy 621
Left triangular ligament 656
Leger's procedure 887
LE Hughes double near and far suture 49, 521, 537
Leksell gamma knife perfexion 131
Le Maitre's valvulotome 299
Lembert 4
Lembert suture 49, 700
Lester Dragstedt 4
Let preparation technique 888
Levator ani 982, 1241
Levator glandulae thyroideae 440
Lewis-Tanner 618
Lichtenstein 1129
LIFT technique 1038
Ligament of Cooper 470
Ligament of Treitz 650, 693
Ligamentum teres 754
Ligamentum venosum 754
Ligasure/ligaseal/ultrasonic shears/laser/harmonic scalpel 65
Ligasure 129, 570
Ligidakis modification of Hunt Lawrence pouch 687
Lily's operation 863
Limberg flap 183, 1009

Lind both anterior and posterior
fundoplication 595
Lindholm tube 97
Linear staplers 163, 164
Linea semilunaris of Douglas 519
Linen 111
Line of Toldt 1119
Lingual frenulum 428
Linton's shunt 787
Linton's vertical approach 360
Lipoma 148
Liposuction 1306
Lisfranc's amputation 252
Listerism 3
Lister's bandage/dressing cutting scissor 91
Lister's dilator 1099
Lister's sinus forceps 79
Lister's urethral dilator 104
Little wood posterior approach 269
Liver abscess 239
Liver biopsy 155
Liver injury grades 210
Local rotation flaps 175
Lockhart's flap 1192
Lockwood-Law operation 1178
Lockwood theory 1226
Loin incisions 536
London's sign 206, 217, 720
Long posterior flap 247
Long thoracic nerve 472
Loop transverse colostomy 945
Lord and Millar's excision 1015
Lord's dilatation 1016
Lotheissen's operation 1183
Low and high frequency sound wave energy 127
Lowsley's rectal bladder 1095
Ludwig's angina 138, 393
Lumbar puncture 158
Lumbar sympathectomy 381
Lumbotomy incision 537
Lung abscess 245
Lurz Goltner suction ligator 1017
Lymph node of Lund 800
Lymph node station of gastric carcinoma 677
Lyre sign 401
Lysol 12
Lytle's repair 1134

M

MacIntosh blade 97
Madlener procedure 1261
Magill's forceps 32, 98
Magpi repair 1100
Maingot's modification 670
Maingot's pedicle clamp 76
Mainz pouch 1094
Makuuchi incision 764
Makuuchi IVC ligament 758
Malecot's catheter 102
Male metal catheter 104
Malignant hyperthermia 25
Mallet 117
Manchester operation 1182
Marc-Goldstein approach 1221
Marcadier procedure 887
Marginal artery of Drummond 940
Marion's disease 1100
Mark Whiteley 369
Martin's thrombectomy forceps 279
Maryfield introducer 101
Maryland dissectors 552
Mass casualities 203
Masseter 420
Matas aneurysmorrhaphy 278
Maxillectomy 431
May-Hunsi operation 373
Maylard's incision 531, 1259
Mayo-Robson incision 527, 812
Mayo needle 88
May or Kuster perforator 348
Mayo's operation 1173
Mayo's pedicle clamp 76
Mayo's scissors 91
Mayo's table 117
Mayo's towel clip 72
McArthur 1129
McBurney's incision 735
McEvedy high operation 1182
McGregor and Nakajima flap 438
McGregor flap 434
Mc Indoe scissor 91
McKeown three phase oesophagectomy with
lymphadenectomy 622
McKernan's method 1158
McNeal 1053
Mc Vay operation 1134
Meckelian diverticulectomy 698
Meckel's diverticulum 697
Medial pectoral nerve 472
Medial pterygoid muscle 420
Median and ulnar nerve block 196
Median nerve injury 379
Median phrenicotomy 583
Median sacral artery 980
Medical anti-shock trouser 200
Medical ethics 7
Medical negligence 7
Meier wire 315
Meigster's/Lahey's right angle forceps 74
MELD score 783
Melon seed bodies 234
Melzer knot 59
Memory 53
Mendelson's syndrome 19
Menghini needle 156
Meralgia paraesthetica 380
Mercedes Benz incision 535, 764
Mesenteric abscess 245
Mesentericocaval shunt 789
Mesenteric tear 209
Mesh graft 169
Mesh hepatorrhaphy 211
Mesoatrial shunt 791
Mesocaval shunt 788
Mesovarium 1241
Metzenbaum scissor 38, 91, 1265
Mexican hat incision 481
Meyer's ligament 401
Miami Vein Clinic 371
Microdochectomy 478
Microfibrillar collagen powder 67
Micropoint needle 87
Microwave ablation 130
Middle finger amputation 266
Middle rectal artery 980, 983
Middle rectal vein 980
Middle thyroid vein 442
Midline incision 523
  lower 524
  upper 523
Midpalmar space infection 227
Midtarsal amputation 252
Miegster clamp 64
Mifepristone 1244
Mikulicz 638
Millard cleft repair 414
Millard criteria 414
Miller's blade 98
Milligan-Morgan technique 1020
Millin's retropubic prostatectomy 1097
Millin's self-retaining retractor 83
Milnes-Walker thoracic oesophageal
transection 792
Minimally invasive video-assisted
thyroidectomy 464
Minimum touch technique 1
Minor's starch iodine test 510
Mirkowitch technique 888
Misoprostol 1244
Missouri swan neck catheter 338
Mitchel first approach 223
Mitchel's clip applicator 113
Mitchel's clip extractor 113
Mitchel's clip magazine 113
Mitchel's metal clip 113
Mixter clamp 64
Modified Appley's technique 911
Modified Bassini's herniorrhaphy 1133
Modified Blair incision/Lazy S/Sistrunk
incision 503
Modified Duhamel operation 975
Modified Fisherman's knot 61
Modified Gibson's incision 535, 1061
Modified radical mastectomy 483, 488
Modified Rex shunt 790
Modified Smead-Jones closure 49, 537
Modified Smead-Jones suture 521
Modified Syme's amputation 255
Modified Toupet's partial posterior
fundoplication 604
Mohs surgery 150
Moir's three swab test 1300
Mollison's mastoid retractor 84
Monk's localising zones 217
Monofilament 112
Monopolar cautery 65, 121
Mons veneris 1240
Montgomery tubercles 470
Moreno Gonzales procedure 887
Morrant-Baker's appendix holding forceps 77
Morris incision 1055
Morris kidney retractor 85
Morrison's kidney pouch 1049
Morrison's pouch 756
Morris parallelogram 1049
Morris' retractor 82
Mounted tie 63
Mouret 641
Mouret of Lyon 812
Mouret P 7
Mousseau-Barbin tube 633
Moynihan 683, 866

Moynihan atraumatic straight intestinal needle 669
Moynihan's caterpillar hump 802
Moynihan's cholecystectomy forceps 93
Moynihan's gastrojejunostomy clamp 92
Moynihan's glass tube 110
Moynihan's occlusion clamp 92
Moynihan's tetra towel clip 72
Moynihan's tissue forceps 78
Muir low anterior resection 1000
Multifilament 112
Multiple casualities 203
Multiple phlebectomies 360
Munchausen syndrome 733
Muscle flap 175
Myer's stripper 355
Myer's vein stripper 115
Myocardial infarction 20
Myocutaneous flap 175

N

Nagamatsu approach 1054
Narath's femoral hernia 1178
Narbona's ligamentum teres cardiopexy 599
Nathanson 641
Near total thyroidectomy 447
Neck injuries 204
Negative pressure drains 542
Negus artery forceps 74
Nelson and Nyhus method 713
Neodymium-yttrium aluminum garnet laser 125
Neon laser 125
Nephrocalcinosis 465
Nerve of Latarjet 637, 909
Nerve release 380
Nerve repair 378
Nerve to serratus anterior 472
Nervi erigentes 984
Net absorbers 731
Net secretors 731
Neuhauser sign 730
Neuropraxia 379
Neurotmesis 379
Neurovascular bundle of Walsh 990
Newman-Seabrock operation 510
Niels Stenson 500
Nigro Teflon Halter operation 1000
Nipple sparing mastectomy 493
Nissen-Cooper technique 672
Nissen's fundoplication 600
Nissen's posterior total fundoplication 594
Noble's plication 712
Node of hiatus 802
Non-anatomical wedge resection 781
Non-ionising radiation 11
No reflow phenomenon 315
NOTUS 837
Nuttall's operation 1167
Nyhus classification 1127
Nyhus iliopubic repair 1134
Nylon 111

O

Ober's and Barr's procedure 378
Oblique iliac incision 535
Obturator artery 983
Obturator internus 982
Obturator nerve 1125
Oesch pin stripping 358
Oesophageal injuries 206
Oesophageal transection of Johnston 791
Oesophageal triangle 583
Oesophagogastric junction 638
Office surgery 68
Ombredanne's operation 1226
Omental bursa 635
Omental bursectomy 677
Omental flap 175
Omentoplasty 338
On-table colonic lavage 10
Open amputation with inverted skin flaps 248
Open drainage 237
Open drains 99
OPSI 937
Orbitectomy 432
Orchidectomy 1235
Organ space infection 26
Ormond's disease 1045
Orr fascia lata sling suspension 1000
Orringer and Orringer 604
Osteomyocutaneous flap 175
Osteotome 116
Out patient surgery 68
Ovarian fimbria 1241
Owen H Wangensteen 5
Oxford endotracheal tube 97
Oxidized cellulose 67
O'Conor abdominal repair 1301
O'Regan suction banding 1017

P

PAIR 794
Palma operation 372
Palmer point 714
Palomo's operation 1221
Pancreatic abscess 245
Pancreatic injury grading 215
Pancreaticojejunostomy 898
Panhysterectomy 1277
Pantaloon hernia 1122
Pappenheimer siderotic bodies 918
Para Achillean Bassi 348
Parachute technique 276, 846
Paralytic ileus 522
Paramedian incision 527
Parapharyngeal abscess 393
Pararectal space 1299
Parastomal gully 722
Paraurethral gland of Skene 1242
Paravesical space 1299
Parietal cells 638
Parietal cell vagotomy 660
Parker-Kerr 669
Parker-Kerrs crushing clamp 92
Parker Kerr basting 703
Parkland tubal ligation 1261
Park's submucosal haemorrhoidectomy 1022
Paronychia 227
Parotid abscess 134
Parotid abscess drainage 510
Partial cholecystectomy 824
Partial maxillectomy 432
Partial splenectomy 214
Partial thyroidectomy Thomas 447
Partington-Rochelle operation 875
Passive drains 542
Patellar tendon bearing prosthesis 271
Patey's fasciovenous plane 500
Patey's operation 483
Patey's parotidectomy 503
Patient controlled analgesia 18
Patterson approach 416
Patterson Brown defect 1103
Pauchet's operation 669
Paul-Mikulicz operation 975
Paul Brand's operation 378
Paul's drainage tube 100
Payr's crushing clamp 92
Payr's gastric occlusion clamp 92
Peanut dissection 39
Pectoralis major 472
Pectoralis major myocutaneous flap 179
Pectoralis minor 472
Pedicled flap 178
Peg-leg amputation 256
Pelvic abscess 240
Pelvirectal abscess 1033
Pen holding/writing position 89
Pen holding position 36
Penrose drain 542
Percutaneous catheter drainage 236
Percutaneous transhepatic cholangiography 810
Percutanous endoscopic gastrostomy 645
Perdomo procedure 796
Perianal space 981
Pericardial tap/pericardiocentesis 159
Pericholedochal nodes 802
Pericystectomy 796
Perineal posterior fixation of rectum of Lockhardt-Mummery 1007
Perinephric abscess 242
Peritoneal dialysis access 338
Peritonealisation 1284
Peritoneal tap 160
Peroneal artery exposure 307
Perry 207
Pes anserinus 500
Peyronie's disease 1192
Pfannenstiel incision 531
Phantom limb 248, 249
Pharyngeal pouch 395
Phenol 12
Phillips TEP 1158
Photodynamic therapy 131
Photofrin 131
Phrenicocolic ligament 917
Phrenooesophageal ligament 582
Phrygian cap 802
Physiological hernia 729
Pierre Robin syndrome 414
Pieter Camper 1128
Piggyback technique 785
Pinch cock effect 1122
Pirogoff's amputation 255
Pittaluga technique 362
Platysma 388
Platz and Wepner method 438
Pleura flap 631
Pleural tap/pleurocentesis 158
Plexus of Auerbach 637
Plexus of Meissner 637
Plurisegmentectomy 768
Pneumothorax 205
Point block 1129

Polyamide 111
Polybutester-Novafil 111
Polydek 111
Poly dioxanone 111
Polyester 111
Polygalactic acid 111
Polyglecaprone/monocryl 111
Polyglycolic acid/dexon/synthetic polymer of glycolic acid 111
Polyglyconate/maxon 111
Polypropylene mesh 107
Pomeroy tubal ligation 1261
Poole's multiperforated suction tip 95
Porta-caval shunt 787
Portal venous system 757
Port closure needle 87
Post-thrombotic syndrome 375
Posterior epistaxis 30
Posterior extraserous approach 237
Posterior gastrojejunostomy 654
Posterior tibial artery exposure 307
Posterior vagus 637
Posterolateral neck dissection 405
Postoperative gastrointestinal bleeding 23
Postoperative hypertension 20
Postoperative ileus 23
Postoperative parotitis 30
Postoperative pneumonia 19
Postoperative psychosis 25
Postoperative sinusitis 30
Pott's scissors 278
Pott's sutures 298
Pouchitis 997
Pouch of Douglas 1241
Poupart's ligament 1121
Pre-formed slip knots 59
Pre-hospital trauma life support 203
Premaxillectomy 432
Premedication 11
Prepyloric vein of Mayo 637
Pretied loops 567
Prevention of infection 15
Prevertebral fascia 389
Primary closure 202
Primary contracture 172
Primary hyperparathyroidism 464
Principles in making incision 37
Pringle manoeuvre 66, 211
Pringle manoeuvre 760
Problems with cautery 123
Proflavine 12
Prosthetic grafts 286
Proximal gastric unit 635
Proximal gastric vagotomy 660
Proximal splenorenal shunt 789
Psoas abscess 243
Psoas hitch 1096
Psoas major 520
Psoas minor 520
Psoas spasm 243
Pudendal canal 1191
Pudendal nerve 1191
Puestow's operation 875
Pulmonary capillary wedge pressure 31
Pulmonary contusion 205
Pulmonary embolism 20
Pulmonary injury 205
Pulmonary oedema 19
Pulsed laser 125
Pulse oximeter 16, 32
Push technique 649
PVC tracheostomy tube 95, 140
Pylephlebitis 743
Pyloric orifice 634
Pyonephrosis 242
Pyramidalis 1124
Pyriformis muscle 982

Q

Quadrantectomy 481
Quadrate lobe 754
Quadratus lumborum 520
QUART therapy 482
Queckenstedt's test 158
Queen of face 502
Quilted grafting 170
Quincke spinal needle 197

R

Radial forearm flap 182
Radial nerve injury 379
Radical cholecystectomy 853
Radical excision/radical block dissection 154
Radical neck dissection 404
Radical parotidectomy 503
Radiocephalic AV fistula 333
Radiofrequency ablation 129
Radiofrequency ablation method 362
Radiosurgery 130
Rae preformed tracheal tube 97
Railroad technique 223
Rail road track duodenum 695
Rampley's sponge holding forceps 71
RAMPS 911
Randall's forceps 840
Random pattern flaps 175
Ravitch 683
Ray amputation 252
Reboring 278
Rebound hyperinsulinism 1113
Recipient hepatectomy 784
Recipient operation 784
Record syringes 113
Rectal ampulla 979
Rectal injuries 220
Rectopexy 998
Rectosigmoid junction 979
Rectus abdominis muscle 519
Rectus sheath 519
Recurrent laryngeal nerve 443
Recurrent laryngeal nerve injury 379
Recurrent thyrotoxicosis 463
Recurrent ulcer 689
Red-rubber tracheostomy tube 95
Red rubber tracheostomy tube 140
Reef knot 61
Reflux oesophagitis 587
Regional flap 176
Registrar's incision 515
Reilly's sigmoid myotomy 951
Remedial parathyroidectomy 466
Renal injury grading 221
Renal revascularisation 318
Reperforation 641
Reperfusion injury 315
Residual venous fraction 345
Res ipsa loquitur 7
Respiratory complications 18
Respiratory failure 19
  type I 19
  type II 19
  type III 19
Retention of urine 22
Retention of urine causes 132
Retention sutures 46, 538
Retrograde ejaculation 1048
Retromammary bursa 470
Retroperitoneal radical lymph node dissection 1232
Retroperitoneal rupture 312
Retropharyngeal abscess 392
Retzius 1128
Reverse cutting needle 87
Revised trauma scale 198
Rhomboid flap 1009
Rib approximator 86
Rib fractures 205
Rib retractor 85
Rib shear 86
Richardson 683
Richet's fascia 1147
Riedel's lobe 755
Riegner 401
Right angle retractor 81
Right anterior sectionectomy 781
Right gastric artery 636
Right gastroepiploic artery 636
Right gastroepiploic vein 637
Right trisegmentectomy 768
Rignault's modification 1147
Ring finger amputation 266
Ripstein operation 999
Robert's pedicle clamp 76
Rockey-Davis approach 735
Roeder's knot 54
Rooftop incision 535
Roos 400
Rosenberg 285
Rosetti Hell anterior fundoplication 595
Rosoe Graham operation 1000
Rotter's node 484
Round body needle 43, 87
Roux stasis syndrome 690
Rovsing operation 1085
Rudolph Matas 4
Rule of 2 in thyroid 444
Rumpf's extended drainage 887
Rupture bladder 224
Ruptured aortic aneurysm 312
Russian forceps 79
Rutherford Morrison's incision 735
Ryle's tube 106

S

Sacless hernia 1177
Saddle block 197
Saddle embolus 318
Saegesser's tender point 213
Safer zone for anaesthesia 10
Safe tract 649
Saint Mark's anal dilator 109
Salpingectomy 1250
Salpingostomy 1250
Salpingotomy 1250

Saltatory flap 176
Salutary effect 215
Santulli operation 731
Saphenous neuralgia 358
Saphenous vein graft 298
Sartorius muscle transposition 1203
Satinsky vascular clamp 75, 274
Savaage's decompressor 975
Savlon 12
Scalene triangle 400
Scalpel dissection 39
Scandinavian technique 554
Scanlon operation 483
Scapula retractor 85
Scarpa's sheath 1124
Schlatter 4
Schoemaker 666
Schoemaker modification 670
Schuchardt flap 434
Schuchardt technique 439
Scissor dissection 39
Sclerosants 370
Scolicidal agents 796
Scribner shunt 332
Scrub nurse 13
Seatbelt injuries 225
Seattle Artificial Kidney Centre 332
Sebaceous cyst 148
Secondary contracture 172
Secondary hyperparathyroidism 464
Secondary late closure 202
Seddon's classification 379
Segmental portal hypertension 790
Selective vagotomy 637
Self righting needle holder 53
Semicircularis of Douglas 1123
Semicircular line of Spieghel 1123
Semiclosed endarterectomy 279
Semilunar line of Speighel 519
Semm 7, 545
Semon's law 460
Senior nurse 13
Senn 4
Sentinel lymph node biopsy 478
Sequestrectomy forceps/sequestrum holding forceps 116
Sergeant instrument 48
Seroma 25
Serosal patch technique 725
Serratus anterior 472
Seton technique 1041
Sewing machine technique 672
Shamblin classification 401
Sharma's and Jhawer's technique 1210
Sherman perforator 348
Shiley's fenestrated tube 140
Shimi 591
Short gut syndrome 731
Short saphenous vein 347
Shoulder amputation 268
Shoulder disarticulation 268
Shouldice repair 1134
Shunt surgery 787
Shutter mechanism 1122
Sigmoidopexy 975
Signaloc 11
Silk 111
Simple everting suture 43
Simple interrupted fascial suture 43
Single hand technique 52
Single hook retractor 81
Single incision laparoscopic surgery 561
Single layer seromucosal closure 49
Sir Astley Cooper 2
Sistrunk operation 445
Skeletonisation of vessel 63
Skew flap 256
Ski needle 53, 87
Skin hook 81
Skinner's en bloc resection of oesophagus 623
Skin sparing mastectomy 482, 488
Skin staplers 46
Sliding femoral hernia 1178
Slit valve effect 1122
Small gastric remnant syndrome 689
SMART tool 374
Smead-Jones sutures 46
Smead-Jones technique 641
Smith operation 891
Soave's mucosectomy and pull through operation 975
Solid ankle cushion heel 271
Souttar tube 633
Soyer 288
SPA 837
Space of Bogros 520, 1125
Space of Parona infection 229
Space of Reeves 450
Space of Retzius 520, 1127
Spatulated side cutting needle 87
Spencer-Wells pedicle clamp 76
Sphincter of Oddi 800, 867
Spica bandage 1309
SPICES 837
Spigelian hernia 1183
Spigelian lobe 755
Spigot 110
Spiral embedded/armored/reinforced tube 97
Spivack 642
Splauding classification 573
Splenectomy 920
Splenic injury grading 213
Splenic organ injury 924
Splenic vein cavernoma 790
Splenophrenic ligament 918
Splenorrhaphy 214, 934
Splenunculi 919
Split skin graft 168
S shaped retractor 82
Stab position 36, 89
Stages of imbibitions 172
  inosculation 172
  neovascularisation 172
Stamm 642
Stamm's gastrostomy 643
Stamp graft 169
Stapled haemorrhoidopexy 1019
Steele's scissor 91
Stephen-Fowler technique 1226
Stepladder excision 395
Sterilisation 11, 571
Stewart incision 483
Stewart vertical mattress suture 43
Stomal complications 24
Stoppa's repair 1144
Stump neuroma 248
Stump pain 249
Stye Bunnell's operation 378
Stylomastoid foramen 502
Subadventitial plane 403
Subcostal nerve 520, 1124
Subcutaneous mastectomy 474
Subcuticular suture 46
Subfacial endoscopic perforator surgery 360
Subfascial ligation 360
Sublay mesh repair 1174
Submental triangle 388
Submucous abscess 1031
Subphrenic abscess 236, 641
Subtotal hysterectomy 1278
Subtotal parathyroidectomy 466
Subtotal thyroidectomy 446
Sudeck's critical point 941
Sugiura-Futagawa operation 792
Sump suction drain 99
Sump syndrome 844
Sunderland's classification 380
Superficial inguinal ring 1121
Superior epigastric artery 521
Superior hypogastric plexus 984
Superior rectal artery 979
Superior rectal vein 980
Superior thyroid artery 441
Superior thyroid vein 442
Supraduodenal artery 636
Suprafacial parotidectomy 503
Suprahyoid muscles 440
Supraomohyoid neck dissection 405
Surgeon's knot 61
Surgical complications 18
Surgical site infection 26
Sushruta 2
Sussmane-Raszynski needle 194
Sustentacular cells 401
Suture rectopexy 999
Suture removal 62
Suturing types 112
Swan Ganz triple channel pulmonary artery balloon catheter 31
Sweat test 226
Swenson's operation 977
Syme's amputation 252
Syndrome of inappropriate ADH secretion 29
Szabo and Berci needle holder 53

T

Tanner's abdominal oesophagogastric transection 792
Tanner's method 669, 672
Taper cutting needle 87
Tapering duodenoplasty 695
TAPP repair 1151
Tarsorrhaphy 413
Tavel 642
Tayside knot 59
Teflon 286
Teflon tubes 332
Temporalis muscle 423
Tenckhoff neck catheter 338
Tendon graft 378
Tendon lengthening 378

Tendon release 377
Tendon repair 377
Tendon transfer 378
Tenoma 377
Tension sutures 46
Tentomy knife 90
TEP repair 1154
TE Udwadia 545
Texas Endosurgery Institute knot 59
Thal 725
Thal's patch procedure 599
Thenar space infection 229
Theodor Billroth 4
Theodore Maiman 124
Theodor Kocher 5
Therapeutic intervention scoring system 32
Thiersch graft 168
Thiersch wiring 998
Thiersch's skin grafting knife 115
Thimble bladder 1062
Third tier nodes 683
Thompson-Walker's suprapubic cystolithotomy forceps 105
Thomson retractor 764
Thoracic oesophagus 579
Thoracic outlet syndrome 399
Thoracic trauma 204
Thoracoabdominal aneurysm 318
Thoracodorsal nerve 472
Thoracoscopic sympathectomy 387
Thoracostomy 205
Thoralsksen 1008
Three field lymphadenectomy 584, 623
Three point suture 46
Thyroglossal cyst 440
Thyroidea ima artery 442
Thyroidectomy 445
Thyroid primodium 440
Thyrotoxic storm 462
Tibial nerve injury 379
Tiemann catheter 103
Tiffany 759
Tinel's sign 380
Toe amputation 251
Toe nail excision 190
Toggle mode 552
Toilet mastectomy 493
Toldt's line 953, 1047, 1110
Tongue depressor 114
Tongue tie 399
Toomy syringe 114
Total conservative parotidectomy 503
Total gut irrigation 10
Total mastectomy 488
Total mesorectal excision 986
Total thyroidectomy 447
Total vascular exclusion 760
Toupet's posterior partial fundoplication 585
Tourniquets 65
Tracheal hook 96
Tracheal pars membranacea 581
Tracheobronchial tree injury 205
Tracheostomy 139
Tracheostomy care 143
Tracheostomy complications 143
Transcondylar amputation 259
Transfacial lip split incision 417
Transfacial Patterson operation 417
Transfixation ligature 63
Transhiatal oesophagectomy 604
Transilluminated phlebectomy 369
Transillumination microsclerotherapy 371
Transjugular intrahepatic portosystemic stenting 790
Transmetatarsal amputation 252
Transoral approach 417
Transperitoneal approach 239
Transposition flap 178
Transposition routes 625
Transthoracic Collis-Nissen's gastroplasty 597
Transverse abdominis muscle 519
Transverse abdominis myocutaneous flap 494
Transverse rectus abdominis muscle flap 181
Trasnscarpal amputation 267
Trauma and injury severity score 198
Traumatic needle 88
Traverso-Longmire 908
Traverso-Longmire procedure 887
Trendelenburg operation 351
Triage 203
Triangle of doom 1127
Triangle of pain 1127
Triangle of Truesdale 583
Trigone 1053
Triple anastomosis 876
Triple modified reef knot 61
Trivex method 369
Trocar and cannula 107
Trocar point needle 87
Trousseau's tracheal dilator 95
Truncal vagotomy 637
Tru taper needle 87
Tube caecostomy 945
Tube drain 99
Tumescent anaesthesia 364, 1307
Tunica adventitia 273
Tunica intima 273
Tunica media 273
Tunneling 289
Turnball's no touch technique 952
Turner-Warwick's incision 533
Twisted 112
Two hands technique 52
Two point discrimination test 226
Two stage Syme's amputation 253
Types of neck dissection 406

U

Ullmann 6
Ulnar nerve injury 379
Ultrasonic cutting devices 761
Ultroid 1019
Umbilectomy 1174
Underrunning of tissue 64
Under water seal drain 99
Unna boot 372
Upper hand retractor 764
Ureterovaginal fistula 1300
Urethral injury 223
Urinary catheterisation 132
Urothelium 1052
Usher 1129
Uvula vesicae 1053

V

VAAFT procedure 1041
Vagotomy 656
Valleylab 570
Valmiere 7
Valve cutter method 299
Valves of Geralch 732
Valves of Heister 800
Valves of Houston 979
Valvulae conniventes 650
Valvulotomy 299
Vasectomy 162
Velour surface graft 287
Venepuncture 191
Venesection 191
Venography/phlebography 346
Venous allograft 286
Venous autograft 285
Venous clinical severity scoring 346
Venous Doppler 345
Venous filling index 345
Veress needle 549, 1116
Vermilion reconstruction 439
Vertical banded gastroplasty 1102
Vertical RAM flap 495
Verumontanum 1053
Vesicovaginal fistula 1301
Vestibule 1240
Vicryl 111
Video-assisted parathyroidectomy 466
Vienna operation 1183
Vim-Silverman needle 156
Vinyon 286
Visiblack needle 87
Visiport 555
Visor flap approach 416, 429
VNUS closure method 362
Volkmann's retractor/cat's paw 81
Volkmann's scoop 118
Volsellum 1243
Von Haberer-Finney 666
Von Haberer 666
Von Haberer method 670
Von Haberer submucosal sutures 650
Von Haller 401
Voorhees 286
Voyles-Blumgart technique 846
Vsanth's method 595

W

Wadsworth syndrome 872
Wagner-Grossman hypothesis 460
Wagner's method 253
Wallbridge classification 733
Waltmann Walter syndrome 823
Waltzing 176
Wangensteen's second look surgery 952
Wardill-Kilner push back operation 415
Warren's shunt 790
Warshaw procedure 871
Water jet dissection 761
Watson's anterolateral fundoplication 595
Watson's skin grafting knife 115
Web space infection 227
Well's arterial clamp 75
Well's criteria for DVT 374
Well's operation 999

Wendell 4
Wertheim's operation 1242
West Ernest Miles 991
W flap 437
Whales 837
Wharton's duct 511
Wheelhouse's operation 1099
Whipple's operation 887
Whip stitch 990
Whirl sign 710
Whitehead haemorrhoidectomy 1027
White line of Hilton 981
Wick drain 99
Wide excision of basal cell carcinoma 148
Wide excision of squamous cell carcinoma 149
Wiley's eversion endarterectomy 279
Wilhelm Conrad Roentgen 4
Wilkie's vascular compression 694
William S Halsted 4
William TG Morton 3
Winging of scapula 472
Winnie's block 196
Witzel 642
Witzel jejunostomy 715
Wolfe graft 172
Wolfer 650
Woven type 286
Wrap herniation 604
Wrist disarticulation 267
Writing position 36
WT Bovie 121
Wyatt operation 1007

X

Xenograft 168

Y

Yankauer suction tip 94
Yeoman's punch biopsy forceps 109
Young's gland holding forceps 78
Young's operation 1193
Young's perineal prostatectomy 1097

Z

Zaaiijer 585
Zadik's excision 190
Zisser technique 438
Zollikofer 7
Zona fasciculata 1107
Zona glomerulosa 1107
Zona reticularis 1107
Zones of lymphatic drainage in stomach 638
Z plasty 175, 178
Zuckerkandl's fascia 1045



SRB's
Manual of
Surgery

MANUAL OF SURGERY



Fourth Edition

SRB's Manual of Surgery

Sriram Bhat M MS (General Surgery)
Professor
Department of Surgery
Kasturba Medical College
Mangalore, Karnataka, India

Honorary Surgeon
Government Wenlock Hospital
Mangalore, Dakshina Kannada, Karnataka, India
e-mail: meera_sriram2003@yahoo.com

Foreword
Prakash Rao

JAYPEE BROTHERS MEDICAL PUBLISHERS (P) LTD
New Delhi • Panama City • London • Philadelphia (USA)

Jaypee Brothers Medical Publishers (P) Ltd

Headquarters

Jaypee Brothers Medical Publishers (P) Ltd
4838/24, Ansari Road, Daryaganj
New Delhi 110002, India
Phone: +91-11-43574357
Fax: +91-11-43574314
Email: jaypee@jaypeebrothers.com

Overseas Offices

J.P. Medical Ltd
83, Victoria Street, London
SW1H 0HW (UK)
Phone: +44-2031708910
Fax: +02-03-0086180
Email: info@jpmedpub.com

Jaypee-Highlights Medical Publishers Inc
City of Knowledge, Bld. 237, Clayton
Panama City, Panama
Phone: +507-301-0496
Fax: +507-301-0499
Email: cservice@jphmedical.com

Jaypee Brothers Medical Publishers (P) Ltd
17/1-B Babar Road, Block-B, Shaymali
Mohammadpur, Dhaka-1207
Bangladesh
Mobile: +08801912003485
Email: jaypeedhaka@gmail.com

Jaypee Brothers Medical Publishers (P) Ltd
Shorakhute, Kathmandu
Nepal
Phone: +00977-9841528578
Email: jaypee.nepal@gmail.com

Website: www.jaypeebrothers.com
Website: www.jaypeedigital.com

© 2013, Jaypee Brothers Medical Publishers

All rights reserved. No part of this book may be reproduced in any form or by any means without the prior permission of the publisher.

Inquiries for bulk sales may be solicited at: jaypee@jaypeebrothers.com

This book has been published in good faith that the contents provided by the author contained herein are original, and is intended for educational purposes only. While every effort is made to ensure accuracy of information, the publisher and the author specifically disclaim any damage, liability, or loss incurred, directly or indirectly, from the use or application of any of the contents of this work. If not specifically stated, all figures and tables are courtesy of the author. Where appropriate, the readers should consult with a specialist or contact the manufacturer of the drug or device.

SRB's Manual of Surgery

First Edition : 2004
Second Edition : 2007
Third Edition : 2009
Reprint : 2010
Fourth Edition : **2013**

ISBN 978-93-5025-944-3

Printed at

God could not be everywhere all the time,
so, He created Mothers

This book is in the memory of my mother
Late Mrs Devaki Krishna Bhat
who continues to inspire and guide me

Foreword

> *A true surgeon is never fearless; he fears for his patients, he fears for his shortcomings, his own mistakes, but never fears for himself or his professional reputation.*
>
> **—Samule J Mixter**

The manual is written for the students in this firing line for their MBBS degree. Common conditions seen on a day-to-day basis have been dealt with a little more detail. The uncommon and rare conditions have been dealt briefly. The mode of clinical presentation and the physical signs are mentioned vividly so as to register in the mind of the reader. There is a brief mention of necessary investigations in each of the surgical conditions. The accepted mode of recent advances in investigation and treatment has been included. This manual is meant for Final MBBS degree examination and not a consolidated textbook. Certain chapters are included at the end of the book for the more enthusiastic students and for those interested in participating in quiz programmes.

The clinical photographs are of very good quality, which are self-explanatory of the conditions. The clinching physical signs have been highlighted in box forms with different shades of colour. This mode of presentation emphasises the point to be conveyed to the students which they can recollect when required either while arriving at a diagnosis in their examination or while in practice after obtaining the degree. This book gives a good foundation in surgery for those who wish to pursue surgery as a career.

What does the surgeon ought to be?

The conditions necessary for the surgeon are four—*first*, he should be learned; *second*, he should be an expert; *third*, he must be ingenious; and the *fourth*, he should be able to adapt himself.

Foremost, it is required that the surgeon should know not only the principles of surgery, but also those of medicine in theory and practice; second, he should have seen others operate; third, he should be ingenious, of good judgement and memory to recognise conditions; and the fourth, he should be adaptable and able to accommodate himself to circumstances.

> *Let the surgeon be bold in all sure things, and fearful in dangerous things, let him avoid all faulty treatments and practices. He ought to be gracious to the sick, considerate to his associates, cautious in his prognostications. Let him be modest, dignified, gentle, pitiful, merciful; neither covetous nor an extortionist of money; but rather let his reward be according to his work, to the means of the patient, to the quality of the issue, and to his own dignity.*
>
> **—Ars Chirurgica**

I thank Sriram Bhat M for giving me this privilege of writing a foreword to his excellent manual.

Prakash Rao MS
Retd. Professor of Surgery
Kasturba Medical College
Mangalore, Karnataka, India

Preface to the Fourth Edition

It is my pleasure to release the *fourth edition* in four years after the release of third edition of *SRB's Manual of Surgery*. Earlier editions were well-accepted by undergraduates and postgraduates. I felt that I should bring out the fourth edition in the intention of making it much more updated with texts and illustrations. I have done extensive corrections in this edition. I added many new topics, text details, and additional topics in different chapters. Morbid obesity, gastrointestinal fistulas, and surgical audit are the newer topics added. Malignancies have been discussed in much more detail with new concept of staging and with present oncological trends. Mistakes are corrected and insufficient topics are upgraded. I have referred many books, journals and taken the help of my colleagues in surgery and other departments. I have retained all chapters with some rearrangements of few chapters and topics. Self-assessment questions at the end of each chapter are removed which allowed me to add much more text material in the same space.

I sincerely express my thanks to everybody who have helped me to bring out this edition, and also to the publishers who are the backbone of this upgraded edition. I hope this new book will be well-accepted by the teachers, undergraduates and postgraduates of surgery department. I sincerely welcome all criticisms.

Sriram Bhat M

Preface to the First Edition

This book is born out of a desire to provide a complete, authoritative, current textbook on Surgery. For the past fifteen years of my teaching profession, watching students hurriedly jotting down notes during classes, an urge was born within me to put my thoughts in print. I am fortunate to have been guided by my teachers and supported by my students towards this goal.

An attempt has been made to make this book simple and reader-friendly while not compromising on the aspect of providing students with necessary information and a better clinical understanding of surgery. Recent advances in surgery till date have been included to the best of my knowledge. Text has been presented in a simple and lucid language so as to help students understand and recapitulate the subject better. Since a picture is worth than thousand words, over 500 photographs, X-rays and illustrations have been incorporated in this work to make surgery more interesting and understandable. Inspirational quotes have been interspersed to motivate students to go the extra mile.

Discussion on Instruments and Operative Procedures has been dealt with in necessary detail separately. A chapter containing a list of interesting new developments in surgery and uniquely new topics like Fascinating Signs, Misnomers, Triads and other interesting chapters have been included.

While this book has been compiled with undergraduates in mind, I am confident that it will serve as a useful reference for postgraduates and practitioners.

In compiling this book I have consulted many authoritative books and publications and I sincerely express my appreciation and gratitude to all of them.

Suggestions and constructive criticisms towards improving this book in subsequent editions are always welcome.

Sriram Bhat M

Acknowledgements

I am happy to bring out one more edition (fourth) of the book *SRB's Manual of Surgery*. This is due to constant help and support of many.

I thank our Chancellor, Dr Ramdas M Pai; Pro Chancellor, Dr H S Ballal; Vice Chancellor of Manipal Academy of Higher Education (MAHE), Professor K Ramnarayan; beloved Dean, Professor Venkatraya Prabhu; our associated Deans, Professor Anand Kini and Professor Vivian D'Souza for their academic support.

I thank Dr Alfred Augustine, Professor and Head, Department of Surgery, Kasturba Medical College (KMC), Mangalore, Karnataka, India, for his constant encouragement in academic work and progress.

I always remember my senior teachers, Professor CR Ballal and Professor Suresh Kamath, Professor K Prakash Rao, Professor Subramanya Bhat, Professor Bhaskar Shetty and Professor Ramachandra Pai for their constant help.

Professor Prakash Rao is a guide and encourager to everybody who will be remembered as a special person by me always.

My special thanks to Dr Jayaram Shenoy and Dr Jayaprakash Rao for their affection and support.

Surgical unit heads in our college Dr BM Nayak, Dr Thangam Verghese, Dr Harish Rao, Dr Shivaprasad Rai, Dr Yogishkumar, and Dr Shivananda Prabhu are always supportive for my work and are worth to be remembered always.

I am grateful to all my teachers and colleagues in surgery department who directly or indirectly helped me to bring out this fourth edition.

I appreciate District Medical Officer and Resident Medical Officer of Government Wenlock Hospital, Mangalore, Dakshina Kannada, Karnataka, India, for their kind help.

I will never forget my close associates, Dr Ganapathy, MD, Mangala Hospital, Kadri, Mangalore, Karnataka, India, and Dr Ashok Pandith, MCh, Urologist, for their affectionate help and encouragement in all my endeavours. They always stood with me in my difficulties.

I thank very much the Faculty, Department of Surgery and Paediatric Surgery, JJM Medical College (JJMMC), Davangere, Karnataka, India for providing the needed photographs.

I sincerely thank Professor Navinchandra Shetty, Senior Radiologist, Mangalore, Karnataka, India, and also other radiologists for their help in providing and guiding me in X-rays, CT scans and imaging methods.

I acknowledge Professor Kishore Chandra Prasad, Senior ENT Surgeon, for his help, guidance and encouragement in bringing out this book.

I thank Dr Manohar Pai, Dr Ashfaque Mohammed, Dr Kalpana Sridhar, Dr Ramesh, Dr K Akbar, Dr Keshava Prasad, Dr Kishore Reddy, Dr Achaleshwar Dayal, Dr Raghav Pandey, Dr Rupen Shah, Dr Ashwini Mallya, Dr Praveen, Dr Shibu Mohan, Dr Poornachandra, Dr Rahul Bhat, Dr Ranjith Rao, Dr Irshad, Dr Amar, Dr Rajesh, Dr Suyog, Dr Chandini, Dr Adithya, Dr Ashok Hegde, Dr Rajesh Ballal, Dr Devidas Shetty, Dr Venkatesh Sanjeeva, Dr Sunilkumar Shetty, Dr Shanbogh, Dr Harish Nayak, Dr Subraya Kamath, Dr Venkatesh Shanbogh, Dr Tantri, Dr Sandeep Gopal, Dr Ganesh and Dr Sampath, for their help in various aspects.

My sincere thanks to well-known in our state and country, Senior Professor Narayanaswamy Srinivasan, MS, FRCS who earlier worked as—Head, Department of General Surgery, Bangalore Medical College; Director of Sanjay Gandhi Accident Hospital and Research Institute, Byrasandra, Bengaluru; Dean and Director of Bangalore Medical College and Research Institute, Bengaluru; Joint Director of Medical Education, Government of Karnataka, India, for his affectionate encouragement.

I sincerely appreciate Dr Raghavendra Bhat and Dr Ravichandra, Consultants, Department of Radiology, Yenepoya Medical College, Mangalore, Karnataka, India, for their contribution and affectionate help.

I thank Dr Ganesh Pai, MCh (Paediatric Surgeon), Dr Suresh Pai, MCh; Dr Ashok Shetty (Cardiothoracic Surgeon); Dr Muralidhar Pai, MCh (Neurosurgeon); Dr Vivekanand Prabhu (Paediatric Surgeon); Dr Sadashiva Rao (Paediatric Surgeon); Dr Narayana Bhat (Paediatric Surgeon); and Dr Prashanth Mallya (Anaesthetist), for their help and contributions.

I thank my friend Dr Jagadish, MDS, for his contributions to X-ray and opinion on dental and faciomaxillary topics.

My special thanks to Dr Harikiran Chekuri, Hyderabad, for his help in correcting the mistakes.

My wife, Dr Meera Karanth, helped me day and night in revising this edition and without her help this could not have been possible. My beloved daughter, Ananya, helped me in drawing new diagrams artistically. I enjoy her love and affection towards me.

I remember my students, Dr Ravi CR, Dr Ashwini Polnaya, Dr Ishwara Keerthi, Dr Sudesh, Dr Narasimha Murthy, Dr Nithin, Dr Ashish Singh and Dr Aromal, for their special contributions.

I thank all my students especially postgraduates of surgery department who were helping regularly in bringing out this edition.

Words are not sufficient to remember all my patients who are the main material for the book. I pray for their good health always.

I appreciate Shri Jitendar P Vij Sir (Group Chairman), Mr Ankit Vij (Managing Director), Mr Tarun Duneja (Director-Publishing) and all staff of M/s Jaypee Brothers Medical Publishers (P) Ltd, New Delhi, India, for doing appreciable work in their respective field of printing and publishing. Also, my appreciation to working team in the Branches of Jaypee Brothers Medical Publishers at Bengaluru and Mangalore, for their timely help.

My sincere thanks to editing team members—Ms Sunita Katla (Publishing Manager); Mr KK Raman (Production Manager); Ms Seema Dogra (Cover Designer); Ms Geeta Srivastava and Mr Laxmidhar Padhiary (Proofreaders); Mr Kapil Dev Sharma and Mr Kulwant Singh (DTP Operators), and Mr Sumit Kumar and Mr Ram Murti (Graphic Designers) of M/s Jaypee Brothers Medical Publishers (P) Ltd, New Delhi, India, for their dedicated and affectionate work in bringing out the fourth edition of the title.

Contents

1. General Surgery 1

A. Wounds and Wound Healing 1

Wounds 1; Classification of Wounds 1; Wound Healing 5; Compartment Syndrome 8; Crush Injury 9; Crush Syndrome 10; Degloving Injuries 10; Keloid 11; Hypertrophic Scar 12; Problems with Wound Healing 13

B. Ulcer 14

Ulcer 14; Granulation Tissue 17; Investigations for an Ulcer 19; Traumatic Ulcer 20; Trophic Ulcer (Pressure Sore/Decubitus Ulcer) 21; Ulcer due to Chilblains 23; Ulcer due to Frostbite 23; Martorell’s Ulcer 23; Arterial/Ischaemic Ulcer 23; Bairnsdale Ulcer 23; Carcinomatous Ulcer (Epithelioma, Squamous Cell Carcinoma) 24; Marjolin's Ulcer 24; Rodent Ulcer 24; Melanotic Ulcer 24; Diabetic Ulcer 25; Meleney’s Ulcer (Postoperative Synergistic Gangrene) 26; Lupus Vulgaris (‘Lupus’—Wolf) 26; Tuberculous Ulcer 27; Bazin’s Disease (Erythrocyanosis Frigida/Erythema Induratum) 27; Tropical Ulcer 27; Venous Ulcer (Gravitational Ulcer) 28; Syphilitic Ulcer 28; Soft Chancre/Soft Sore/ Ducrey’s Ulcer/Chancroid/Bubo 28; Climatic Bubo/Tropical Bubo 29; Clinical Examination of an Ulcer 29

C. Sinus and Fistula 30

Sinus 30; Fistula 30; Median Mental Sinus 33; Sequestrum 34; Preauricular Sinus 35

D. Infectious Diseases 36

Surgical Infection 36; Cellulitis 37; Erysipelas 38; Erysipeloid Disease 39; Lymphangitis 39; Abscess 40; Bacteraemia 45; Septicaemia 45; Pyaemia 45; Metastatic and Pyaemic Abscess 46; Boil (Furuncle) 46; Hidradenitis Suppurativa 46; Carbuncle 47; Pott’s Puffy Tumour 48; Pyogenic Granuloma (Granuloma Pyogenicum) 49; Impetigo 49; Scrum Pox 49; Tetanus 49; Gas Gangrene 52; Tuberculosis 54; Leprosy 55; Syphilis (Great Pox) (French Disease) 56; Actinomycosis 56; Madura Foot (Mycetoma Pedis) 57; Rabies (Hydrophobia) 58; Rabies in Dogs 60; Anthrax 61; Nosocomial and Opportunistic Infections 61; HIV Infection and AIDS (Acquired Immunodeficiency Syndrome) 62; Necrotising Fasciitis 65; Acute Pyomyositis 67; Surgical Site Infection (SSI) 67

E. Swellings 71

Lipoma 71; Cysts 74; Dermoids 75; Sebaceous Cyst (Wen, Epidermoid Cyst) 79; Glomus Tumour 82; Papilloma 83; Warts 84; Fibroma 84; Bursae 85; Semimembranosus Bursa 86; Morrant Baker’s Cyst 87; Lymph Cyst (Lymphatic Cyst) 88; Lymphangioma 88; Calcinosis Cutis 89; Neuroma 89; Neurofibroma 90; Neurilemmoma (Schwannoma) 92; Ganglion 93; Chordoma 93; Epignathus 93

F. Electrolyte and Nutrition 95

Normal Physiology 95; Water Loss (Volume Loss) 95; Water Excess (ECF Volume Excess) 95; ECF Loss 96; ECF Excess 96; Hyponatraemia 96; Hypernatraemia 97; Hypokalaemia 97; Hyperkalaemia 98; Hypermagnesaemia 98; Hypomagnesaemia 98; Acid-Base Balance 98; Metabolic Alkalosis 99; Respiratory Alkalosis 99; Metabolic Acidosis 99; Respiratory Acidosis 100; Anion Gap 100; Fluid Therapy 100; Nutrition 101; Gastrostomy 103; Jejunostomy 104; Total Parenteral Nutrition (TPN) 104; Refeeding Syndrome 106; Obesity and Morbid Obesity 106; Different Surgeries 107

G. Shock 111

Shock 111; Stages of Shock 112; Effects of Shock 112; Clinical Features of Shock 115; Investigations in Shock 115; Central Venous Pressure (CVP) 116; Pulmonary Capillary Wedge Pressure (PCWP) 116; Systemic Inflammatory Response Syndrome (SIRS) 117; Multiple Organ Dysfunction Syndrome (MODS) 117; Oxygen Therapy 118; Topical O_2-Therapy 118; Cardiac Arrest 118

H. Haemorrhage and Blood Transfusion 121

Haemorrhage 121; Blood Transfusion 124; Blood Substitutes 126; Massive Blood Transfusion 126; Autologous Blood Transfusion 127; Artificial Blood 127; Erythropoietin 127; Tourniquets 127; Disseminated Intravascular Coagulation (DIC) 128; Mechanism of Blood Coagulation (Haemostasis) 129

I. Burns 130

Burns 130; Management of Burns 134; Eschar 136; Contracture in Burn Wound 137; Electrical Burns 139; Inhalation Injury 141; Chemical Burns 141

J. Trauma 143

Triage 143; Spinal Injury 145; Neck Injuries 146; Bullet Injuries 146; Blast Injuries 147; Penetrating Injuries 148; Abdominal Trauma 148; Blunt Trauma of Abdomen 150; Duodenal Injury 152; Pancreatic Injury 153; Small Bowel Injury 153; Colonic Injury 154; Liver Injury 154; Splenic Injury 154; Renal Injury 154; Urinary Bladder Injury 154; Abdominal Compartment Syndrome 154; Seatbelt Injuries 155

K. Hand and Foot 156

Hand 156; Hand Infections 157; Acute Paronychia 160; Chronic Paronychia 161; Apical Subungual Infection 161; Terminal Pulp Space Infection (Felon) 161; Infection of Web Spaces 162; Deep Palmar Space Infection 162; Space of Parona Infection 164; Acute Suppurative Tenosynovitis 164; Compound Palmar Ganglion 165; Orf 166; Milker's Nodes 166; Hand Injuries 166; Dupuytren's Contracture 168; Volkmann's Ischaemic Contracture 168; Syndactyly 169; Mallet Finger (Base Ball Finger) 170; Heberden's Nodes 170; Spina Ventosa 170; Foot 170; Callosity 170; Corn 171; Plantar Fasciitis (Policeman's Heel) 172; Ingrowing Toe Nail 172; Onychogryphosis 172; Onychomycosis 172; Athlete's Foot 172; Hallux Valgus 173

L. Arterial Diseases 174

Surgical Anatomy of Thoracic Outlet 174; Arteries of Upper Limb 175; Arteries of Lower Limb 175; Arterial Diseases 175; Intermittent Claudication 175; Rest Pain 176; Limb Ischaemia 176; Pregangrene 177; Gangrene 177; Different Levels of Arterial Obstruction 178; Other Features of Poor Circulation 178; Investigations for Arterial Diseases 179; Diseases of the Arteries 182; Atherosclerosis 182; Thromboangiitis Obliterans (TAO) Syn. Buerger's Disease 184; Takayasu's Pulseless Arteritis 188; Raynaud's Phenomenon 188; Temporal Arteritis 190; Treatment of Arterial Diseases 190; Subclavian Steal Syndrome 196; Acute Arterial Occlusion 196; Traumatic Acute Arterial Occlusion 197; Embolism 197; Reperfusion Injury 199; Saddle Embolus 200; Embolectomy 200; Fat Embolism 201; Air Embolism 201; Therapeutic Embolisation 201; Caisson's Disease or Decompression Disease 202; Aneurysm 202; Mycotic Aneurysm 203; Abdominal Aneurysm 203; Abdominal Aortic Aneurysm 204; Peripheral Aneurysm 208; Carotid Artery Aneurysm (Extracranial) 209; Dissecting Aneurysm 209; Erythromelalgia/Erythralgia 210; Livedo Reticularis 210; Polyarteritis Nodosa 210; Scleroderma/Systemic Sclerosis 211; Acrocyanosis (Crurum Puellarum Frigidum) 211; Gangrene 211; Diabetic Foot and Diabetic Gangrene 213; Trophic Ulcer 214; Bedsores (Decubitus Ulcer) (Pressure Sores) 214; Frostbite 215; Ainhum 215; Endovascular Surgeries 215; Upper Limb Ischaemia 216; Arterial Substitutes 220

M. Vascular Lesions and Hamartoma 221

Vascular Anomalies 221; Haemangioma 221; Vascular Malformations 225; Cirsoid Aneurysm 225; Arteriovenous Fistula (AVF) 225; Campbell de Morgan Spots 229; Parry-Romberg Disease 229; Hamartomata 229

N. Venous Diseases 230

Anatomy of Veins of Lower Limb 230; Physiology of Venous Blood Flow in Lower Limb 231; Deep Vein Thrombosis (DVT) 231; Varicose Veins 235; Venous Ulcer (Gravitational Ulcer) 249; Compression Therapy for Varicose Veins 251; Thrombophlebitis 251; Klippel-Trenauny Syndrome 252; Anticoagulants 252; Heparin 252; Low Molecular Weight Heparin (LMWH) 252; Oral Anticoagulants 253; Warfarin 253; Direct Thrombin Inhibitors 253; Antiplatelet Drugs 253; Pulmonary Embolism 254

O. Lymphatics 255

Surgical Anatomy 255; Lymphangiography 257; Isotope Lymphoscintigraphy 257; Lymphoedema 257; Lymphomas 264; Hodgkin's Lymphoma (HL) 265; Non-Hodgkin's Lymphoma (NHL) 269; Malt Lymphoma (Maltoma) 270; Burkitt's Lymphoma (Malignant Lymphoma of Africa) 270; Cutaneous T Cell Lymphoma 270; Chylous Ascites 271; Chylothorax 271; Chyluria 271; Sarcoidosis 272

P. Peripheral Nerves 273

Peripheral Nerve Injuries 273; Tinel's Sign 275; Brachial Plexus Injuries 275; Causalgia 275; Median Nerve Injury 276; Carpal Tunnel Syndrome 276; Ulnar Nerve Injury 278; Claw Hand 278; Radial Nerve Injury 279; Common Peroneal Nerve Injury 280; Foot Drop 280; Medial Popliteal Nerve Injury 281; Axillary Nerve Injury 281; Long Thoracic Nerve Injury (Nerve of Bell) 281; Meralgia Paraesthetica 281

Q. Neoplasm 282

Definition 282; Dysplasia 283; Carcinoma In Situ 284; Aetiologic Factors 284; Spread of Malignant Tumours 284; Grading of Tumour 285; Staging of the Tumour 285; Paraneoplastic Syndromes 286; Investigations for Neoplasm 286; Management Strategy for Cancers 291

R. Skin Tumours 293

Anatomy 293; Classification of Skin Tumours 293; Skin Adnexal Tumours 294; Dermatofibroma (Sclerosing Angioma or Subepithelial Benign Nodular Fibrosis) 296; Dermatofibrosarcoma Protuberans 296; Keratoacanthoma (Molluscum Sebaceum) 296; Rhinophyma (Potato Nose) (Bottle Nose) 297; Seborrhoeic Keratosis (Seborrhoeic Wart, Basal Cell Papilloma) 298; Squamous Cell Carcinoma (Epithelioma) (Khangri Cancer) (Chimney Cancer) 299; Marjolin's Ulcer 302; Basal Cell Carcinoma (Rodent Ulcer) 303; Turban Tumour 306; Naevi 306; Melanoma 308

S. Sarcomas **318**

Sarcoma **318**; Liposarcoma **325**; Fibrosarcoma **326**; Malignant Fibrous Histiocytoma (MFH) **326**; Leiomyosarcoma **327**; Rhabdomyosarcoma **327**; Chondrosarcoma **327**; Haemangiosarcoma **328**; Lymphangiosarcoma **328**; Synovial Sarcoma **328**; Malignant Peripheral Nerve Sheath Tumour (MPNST) **328**; Kaposi's Sarcoma **328**

T. Amputations **330**

Amputation **330**; Complications of Amputations **337**; Prosthesis **339**

U. Reconstruction **340**

Graft **340**; Skin Grafts **340**; Flaps **344**; Tendon **351**; Tendon Repair **351**; Tendon Transfer **352**; Tendon Graft **352**

V. Transplantation **353**

Preoperative Evaluation **353**; Organ Procurement **354**; Renal Transplantation **354**; Immunosuppressive Agents **355**; Liver Transplantation **357**; Bone Marrow Transplantation **359**; Pancreatic Transplantation **359**; Small Bowel Transplantation **359**; Dialysis **359**; Cimino Fistula (Cimino-Brescia) **360**

W. Stings and Bites **362**

Snake Bite **362**; Spider Bite **362**; Bee Bite **363**; Mammalian Bite **363**

X. Pain **364**

Gate Control Theory **364**

2. Faciomaxillary Diseases 367

Diseases of the Palate **367**; Orthopantomogram (OPG) **367**; Cleft Lip and Cleft Palate **368**; Maxillofacial Injuries **372**; Primary Care (Early Care) in Maxillofacial Injuries **374**; Fracture Middle Third Area **375**; Zygomatic Complex Fracture **376**; Fracture of the Mandible **378**; Dislocation of the Mandible **380**; Preauricular Sinus **380**; Jaw Tumours **381**; Epulis (Greek—Means Upon Gum) **382**; Ameloblastoma (Adamantinoma, Eve's Disease, Multilocular Cystic Disease of the Jaw) **383**; Dentigerous Cyst (Follicular Odontome) **384**; Dental Cyst (Radicular Cyst, Periapical Cyst) **385**; Osteomyelitis of Jaw **385**; Alveolar Abscess (Dental Abscess) **386**; Fibrous Dysplasia of Bone/Jaw **386**; Cherubism (Cherub—Angelic Being) **388**

3. Oral Cavity 389

Ranula **389**; Sublingual Dermoids **390**; Stomatitis **390**; Cancrum Oris (Noma) **391**; Syphilitic Lesions of Oral Cavity **392**; Leukoplakia **392**; Erythroplakia **393**; Oral Submucosal Fibrosis **393**; Premalignant Conditions of Oral Cavity **394**; Oral and Upper Aerodigestive Cancers **394**; Cheek **396**; Carcinoma Cheek/Buccal Mucosa **396**; Lip **408**; Neoplasm of Lip **410**; Carcinoma Lip **410**; Tongue **414**; Tongue Ulcers **415**; Benign Tumours of Tongue **416**; Tongue Fissure **416**; Glossitis **416**; Tongue Tie **417**; Carcinoma Tongue **417**; Carcinoma of Posterior One-Third/Base of the Tongue **422**; Nasopharyngeal Carcinoma **423**; Maxillary Tumours **424**; Malignant Tumours of Tonsil **426**; Carcinoma Hard Palate **427**; Laryngeal Tumours **427**; Malignant Tumours of Larynx **427**; Trismus **430**

4. Salivary Glands 431

Anatomy **431**; Saliva **434**; Sialography **434**; Salivary Calculus and Sialadenitis **435**; Sialosis **437**; Sialectasis **437**; Recurrent Childhood Parotitis **438**; Parotid Abscess (Suppurative Parotitis) **438**; Parotid Fistula **438**; Sjögren's Syndrome **439**; Mikulicz Disease **440**; Salivary Neoplasms **440**; Pleomorphic Adenoma (Mixed Salivary Tumour) **441**; Adenolymphoma (Warthin's Tumour, Papillary Cystadenolymphomatosum) **444**; Oncocytoma (Oxyphil Adenoma) **445**; Basal Cell Adenoma **445**; Mucoepidermoid Tumour **445**; Adenoid Cystic Carcinoma (**10**% of Salivary Tumours) **446**; Acinic Cell Tumour **446**; Malignant Mixed Tumour (MMT) **446**; Adenocarcinoma of Salivary Glands **446**; Squamous Cell Carcinoma of Salivary Glands **447**; Submandibular Salivary Gland Tumours **447**; Management of Malignant Salivary Tumours **447**; Minor Salivary Gland Tumours **450**; Parotid Lymphoma **451**; Parotidectomy **451**; Frey's Syndrome (Auriculotemporal Syndrome, Gustatory Sweating); (Lucie Frey—Polish Surgeon—1932) **452**; Facial Nerve Injury (Lower Motor Nerve Lesion, Surgically Related) **453**

5. Neck 455

Anatomy of Lymphatics of Head and Neck **455**; Thoracic Outlet Syndrome (TOS) **456**; Cervical Rib **457**; Branchial Cyst **459**; Branchial Fistula **460**; Pharyngeal Pouch **462**; Laryngocele **463**; Cystic Hygroma (Cavernous Lymphangioma) **464**; Ludwig's Angina **465**; Parapharyngeal Abscess **466**; Retropharyngeal Abscess **466**; Subhyoid Bursitis **467**; Carotid Body Tumour (Potato Tumour, Chemodectoma, Nonchromaffin Paraganglioma) **468**; Torticollis (Wry Neck) **469**; Sternomastoid Tumour **469**; Tuberculous Lymphadenitis **470**; Cold Abscess **474**; Secondaries in Neck Lymph Nodes **475**; Chemotherapy for Head and Neck Cancers **482**

6. Thyroid 484

Development **484**; Anatomy **484**; Physiology **486**; Congenital Anomalies **486**; Thyroid Function Tests **489**; FNAC of Thyroid **489**; Classification of Goitre **490**; Diffuse Hyperplastic Goitre **491**; Multinodular Goitre (MNG) **491**; Discrete Thyroid Nodule **494**; Solitary Thyroid Nodule **494**; Retrosternal Goitre **497**; Thyrotoxicosis and Hyperthyroidism **499**; Radioactive

Iodine **508**; Thyroid Neoplasms **509**; Differentiated Thyroid Carcinoma (DTC) **509**; Papillary Carcinoma of Thyroid (PCT) **510**; Follicular Carcinoma of Thyroid (FCT) **512**; Anaplastic Carcinoma of Thyroid **515**; Medullary Carcinoma of Thyroid (MCT) **518**; Malignant Lymphoma **519**; Hashimoto's Thyroiditis (Struma Lymphomatosa) **519**; De-Quervain's Subacute Granulomatous Thyroiditis **519**; Riedel's Thyroiditis (0.5% Common) **520**; Thyroid Incidentaloma **520**; Thyroidectomy **521**; Emil Theodor Kocher **526**; Kocher's Test **526**; Hypothyroidism **526**; Recurrent Laryngeal Nerve Palsy **527**

7. Parathyroids and Adrenals **531**

Anatomy **531**; Calcium **531**; Hyperparathyroidism (HPT) **532**; Parathyroidectomy **534**; MEN Syndrome (MEA Syndrome) **536**; Apudomas **536**; Hypoparathyroidism **537**; Tetany **537**; Adrenals **538**; Adrenal Cortical Tumours **538**; Adrenocortical Carcinoma **539**; Cushing's Syndrome **539**; Conn's Syndrome **540**; Virilising Syndrome or Adrenogenital Syndrome **540**; Neuroblastoma **540**; Pheochromocytoma **542**

8. Breast **544**

Anatomy **544**; Mammography **547**; Aberration of Normal Development and Involution (ANDI) of the Breast **548**; Fibroadenoma **548**; Fibrocystadenosis (Fibrocystic Disease of the Breast/Mammary Dysplasia/Cyclical Mastalgia with Nodularity) **551**; Sclerosing Adenosis **552**; Phyllodes Tumour (Cystosarcoma Phyllodes/Serocystic Disease of Brodie) **552**; Mastalgia ("Pain in the Breast") **553**; Traumatic Fat Necrosis **554**; Galactocele **554**; Mastitis **555**; Antibioma **558**; Duct Ectasia **558**; Mondor's Disease **558**; Tuberculosis of the Breast **559**; Breast Cysts **559**; Galactorrhoea **560**; Gynaecomastia (Greek—Women Breast) **560**; Duct Papilloma **562**; Zuska-Atkins Disease **563**; Mammary Fistula of Atkins **563**; Carcinoma Breast **563**; Management of Early Carcinoma Breast **586**; Advanced Carcinoma Breast **590**; Prognostic Factors in Carcinoma Breast **592**; Prophylactic Mastectomy **593**; Carcinoma of Male Breast **593**; Breast Reconstruction **594**; Breast Implants **596**; Nipple Retraction **597**

9. Peritoneum **599**

Anatomy **599**; Physiology **599**; Acute Peritonitis **600**; Primary Peritonitis **600**; Secondary Peritonitis **600**; Tertiary Peritonitis **600**; Spontaneous Bacterial Peritonitis (SBP) **605**; Sclerosing Peritonitis **606**; Biliary Peritonitis **606**; Postoperative Peritonitis **606**; Other Forms of Peritonitis **607**; Pelvic Abscess **607**; Subphrenic Spaces and Subphrenic Abscess **608**; Mesenteric Cysts **611**; Mesenteric Panniculitis **612**; Acute Mesenteric Lymphadenitis **612**; Mesenteric Malignancy **612**; Mesenteric Trauma **613**; Peritoneal Malignancy **613**; Omental Cyst **614**; Omental Torsion **614**; Omental Tumour **614**

10. Abdominal Tuberculosis **615**

Abdominal Tuberculosis **615**; Ileocaecal Tuberculosis **616**; Ileal Tuberculosis **621**; Peritoneal Tuberculosis **621**; Tuberculous Mesenteric Lymphadenitis **624**; Ano-Recto-Sigmoidal Tuberculosis **626**; Tuberculosis of the Omentum **626**

11. Liver **627**

Surgical Anatomy of Liver **627**; Liver Function Tests (LFT) **628**; Alfa-Feto Protein (AFP) **628**; Liver Biopsy **629**; Liver Injury **629**; Infections of Liver **631**; Liver Tumours **642**; Liver Cysts **649**; Portal Hypertension **651**; Oesophageal Varices **654**; Portal Hypertensive Gastropathy **661**; Ascites **661**; Ascites in Portal Hypertension **663**; Budd-Chiari's Syndrome **664**; Hepatic Failure **664**; Hepatic Encephalopathy **665**; Hepatorenal Syndrome **665**; Hepatic Resection **665**; Portal Biliopathy **668**

12. Gallbladder **669**

Surgical Anatomy **669**; Oral Cholecystogram (OCG; Graham-Cole Test) **670**; IV Cholangiogram **671**; Endoscopic Retrograde Cholangio-pancreatography (ERCP) **671**; Percutaneous Transhepatic Cholangiography (PTC) **672**; Magnetic Resonance Cholangio-pancreatography (MRCP) **673**; Radioisotope Scan Study **673**; Peroperative Cholangiogram **673**; Postoperative T-Tube Cholangiogram **673**; Congenital Anomalies of Gallbladder **673**; Choledochal Cysts **675**; Caroli's Disease **677**; Biliary Atresia **677**; Gallstones **679**; Acute Cholecystitis **684**; Acute Acalculous Cholecystitis **686**; Empyema Gallbladder **687**; Mucocele of the Gallbladder **688**; Chronic Cholecystitis **688**; Cholecystoses **689**; Dissolution Therapy for Gallstones **690**; Choledocholithiasis **690**; Sump Syndrome **694**; Courvoisier's Law **694**; Surgical Jaundice (Obstructive Jaundice) **695**; CBD Strictures (Biliary Strictures) **697**; Sclerosing Cholangitis **699**; Gallbladder Polyp **699**; Benign Biliary Papilloma **699**; Carcinoma Gallbladder **699**; Cholangiocarcinoma (Bile Duct Carcinoma) **702**; Klatskin Tumour **702**; Biliary Fistulas **703**; Gallstone Ileus **703**; Hemobilia **704**; White Bile **705**; Cholecystectomy **705**; Laparoscopic Cholecystectomy **706**; Single Incision Laparoscopic Surgery (SILS) in Cholecystectomy **708**; Bile Duct Injuries **708**; Post-cholecystectomy Syndrome **709**; Biliary Dyskinesia **710**

13. Spleen **711**

Surgical Anatomy **711**; Functions of the Spleen **711**; Splenunculi **712**; Splenic Injury (Rupture Spleen) **712**; Splenomegaly **716**; Hereditary Spherocytosis **716**; Immune Haemolytic Anaemia **717**; Thalassaemia (Mediterranean Anaemia/Cooley's Anaemia/Erythroblastic Target Cell Anaemia) **718**; Sickle Cell Disease **718**; Idiopathic (Immune) Thrombocytopenic Purpura (ITP) **718**; Thrombotic Thrombocytopenic Purpura (TTP) **720**; Splenectomy **720**; Overwhelming Postsplenectomy Infection (OPSI) **722**; Splenic Artery Aneurysm **722**; Splenic Abscess **723**; Hypersplenism **723**; Splenic Cyst **724**

14. Pancreas 725

Anatomy **725**; Serum Amylase **726**; Magnetic Resonance Cholangio-pancreatography (MRCP) **727**; Pancreatitis **727**; Acute Pancreatitis **727**; Complications of Acute Pancreatitis **732**; Pseudocyst of Pancreas **734**; Chronic Pancreatitis **738**; Pancreatic Tumours **746**; Exocrine Pancreatic Tumours **746**; Carcinoma Pancreas **747**; Endocrine Pancreatic Tumours **755**; Insulinomas **756**; Gastrinomas **757**; Glucagonomas **758**; Zollinger-Ellison Syndrome **758**; Cystic Fibrosis **758**; Annular Pancreas **759**; Ectopic (Accessory) Pancreatic Tissue **759**; Pancreatic Divisum **759**; Pancreatic Calculus **760**; Pancreatic Ascites **760**; Pancreatic Fistulae **760**; Pancreatic Abscess **761**; Pancreatic Necrosis **761**; Pancreatic Trauma **762**; Cystic Lesions of Pancreas **763**; Exocrine Pancreatic Disease **763**

15. Retroperitoneal Space 764

Anatomy of Retroperitoneum **764**; Retroperitoneal Fibrosis **764**; Retroperitoneal Swellings **765**; Retroperitoneal Tumours **766**; Psoas Abscess **769**

16. Differential Diagnosis of Mass Abdomen 771

Mass in the Right Hypochondrium **773**; Mass in the Epigastrium **775**; Mass in the Left Hypochondrium **778**; Mass in the Lumbar Region **778**; Mass in the Umbilical Region **780**; Mass in the Right Iliac Fossa **780**; Mass in the Left Iliac Fossa **781**; Mass in the Hypogastrium **781**

17. Abdominal Wall and Umbilicus 784

Diseases of the Umbilicus **784**; Omphalitis **784**; Umbilical Granuloma **786**; Anomalies of Vitellointestinal Duct **786**; Umbilical Sinus **787**; Umbilical Adenoma (Raspberry Tumour) **787**; Umbilical Fistula **788**; Patent Urachus **788**; Burst Abdomen (Abdominal Dehiscence) (Acute Wound Failure) **788**; Abdominal Wall Tumours **791**; Desmoid Tumour **791**; Exomphalos (Omphalocele) **792**; Gastroschisis (Belly Cleft) **793**; Rectus Sheath Haematoma **794**; Abdominal Wall Abscess **794**; Meleney's Progressive Synergistic Bacterial Gangrene of Abdominal Wall **795**; Divercation of Recti (Diastasis Recti) **796**

18. Hernia 797

Hernia **797**; Aetiology **797**; Parts of Hernia **798**; Classification of Hernia **799**; Inguinal Hernia **800**; Surgical Anatomy of Inguinal Canal **800**; Classification of Inguinal Hernia (Earlier) **802**; Newer Classification of Hernia **803**; Indirect (Oblique) Inguinal Hernia **803**; Direct Hernia **811**; Malgaigne Bulging **817**; Incarcerated Hernia **817**; Strangulated Hernia **817**; Sliding Hernia (Hernia-En-Glissade) **820**; Pantaloon Hernia (Double Hernia, Saddle Hernia, Romberg Hernia) **821**; Infantile Hernia **821**; Femoral Hernia **822**; Ventral Hernia **824**; Incisional Hernia **825**; Umbilical Hernia **829**; Paraumbilical Hernia (Supra- and Infraumbilical Hernia) **831**; Epigastric Hernia (Fatty Hernia of Linea Alba) **831**; Spigelian Hernia **833**; Obturator Hernia **834**; Richter's Hernia **834**; Lumbar Hernia **835**; Phantom Hernia **835**; Sciatic Hernia **836**; Complications of Hernia Surgery **836**; Parastomal Hernia **836**; Different Types of Hernia **837**

19. Oesophagus 838

Anatomy **838**; Lower Oesophageal Sphincter (LOS) **839**; Dysphagia **840**; Contrast Study of Oesophagus **841**; Oesophagoscopy **842**; Oesophageal Endosonography **842**; Gastro-oesophageal Reflux Disease (GORD/GERD) **842**; Hiatus Hernia **847**; Rolling Hernia (Paraoesophageal Hernia) **848**; Reflux Oesophagitis **848**; Barrett's Oesophagus (Norman Barrett, British, 1950) **849**; Barrett's Ulcer **849**; Oesophageal Motility Disorders **849**; Achalasia Cardia (Cardiospasm) **850**; Plummer-Vinson Syndrome (Paterson-Kelly Syndrome) **853**; Corrosive Stricture of Oesophagus **854**; Schatzki's Rings **856**; Boerhaave's Syndrome **856**; Mallory-Weiss Syndrome **856**; Tracheo-oesophageal Fistula **857**; Oesophageal Diverticulum **857**; Carcinoma Oesophagus **858**; Benign Tumours of the Oesophagus **866**; Oesophageal Perforation **867**; Foreign Body Oesophagus **867**

20. Stomach 869

Anatomy **869**; Blood Supply of Stomach **870**; Nerve Supply of Stomach **870**; Histology **870**; Lymphatic Drainage of Stomach **871**; Duodenum **871**; Gastric Physiology **871**; Gastric Function Tests **872**; Gastrin **873**; Barium Meal Study **873**; Gastroscopy **874**; Helicobacter Pylori **875**; Congenital Hypertrophic Pyloric Stenosis **876**; Gastritis **877**; Acute Peptic Ulcer (Duodenal or Gastric Ulcer) **878**; Gastric Ulcer **879**; Duodenal Ulcer **882**; Pyloric Stenosis due to Chronic Duodenal Ulcer **885**; Perforated Peptic Ulcer **887**; Bleeding Peptic Ulcer **891**; Haematemesis **893**; Complications of Gastric Surgery **894**; Trichobezoar (Rapunzel Syndrome) **898**; Chronic Duodenal Ileus (Wilkie's Syndrome) **898**; Durban's Syndrome **899**; Acute Gastric Dilatation **900**; Gastric Volvulus **900**; Gastric Polyp **901**; Menetrier's Disease **901**; Duodenal Diverticula **902**; Carcinoma Stomach **902**; Gastric Lymphoma **915**; Gastric Sarcomas **916**; Gastrointestinal Stromal Tumours (Gist) **917**; Pyloroplasty **918**; Gastrostomy **918**; Gastrectomy **919**; Gastrojejunostomy (GJ) **920**; Retrograde Jejunogastric Intussusception **920**; Vagotomy **920**

21. Small Intestine 922

Anatomy **922**; Meckel's Diverticulum **923**; Regional Enteritis (Crohn's Disease) **925**; Surgical Complications of Typhoid **928**; Surgical Complications of Roundworm (Ascaris Lumbricoides) **929**; Pneumatosis Cystoides Intestinalis **931**; Mesenteric Vessel Ischaemia **931**; Necrotising Enterocolitis **934**; Small Bowel Tumours **935**; Benign Tumours of Small Bowel **936**; Malignant Tumours of Small Bowel **937**; Carcinoid Tumour **939**; Short Bowel Syndrome (Short Gut Syndrome) **941**; Massive Bowel Resection **941**; Small Bowel Enema (Enteroclysis) **942**; Capsule Endoscopy **942**; Small Bowel Enteroscopy **943**; Enteric/Gastrointestinal Fistula **943**

22. Large Intestine 948

Anatomy **948**; Hirschsprung's Disease (Congenital Megacolon) **949**; Diverticular Disease of the Colon **951**; Ulcerative Colitis **954**; Ischaemic Colitis **959**; Pseudomembranous Colitis **960**; Surgical Complications of Intestinal Amoebiasis **960**; Tumours of Colon **961**; Benign Tumours/Polyp of the Colon **961**; Juvenile Polyps **961**; Metaplastic/Hyperplastic Polyp **961**; Peutz-Jegher's Polyp **962**; Adenoma of Colon **962**; Familial Adenomatous Polyp (FAP) **963**; Gardner's Syndrome **964**; Carcinoma Colon **964**; Angiodysplasia of Colon **974**; Ogilvie's Syndrome **974**; Colostomy **975**; Stoma Care **977**; Stoma Appliances **978**; Faecal Fistula **979**; Preparation of Large Bowel for Surgery **980**; Surgical Pouches **980**; Barium Enema **981**

23. Intestinal Obstruction 983

Intestinal Obstruction: Types **983**; Dynamic Obstruction **984**; Duodenal Atresia **989**; Small Intestine Atresia (Intestinal Atresia) **990**; Malrotation **991**; Meconium Ileus **992**; Intussusception (ISS) **994**; Volvulus **997**; Sigmoid Volvulus (Volvulus of Pelvic Colon) **997**; Paralytic Ileus (Adynamic Intestinal Obstruction) **1000**; Adhesions and Bands **1000**; Internal Hernias **1003**

24. Appendix 1005

Surgical Anatomy **1005**; Duplication of Appendix (Wallbridge Classification) **1005**; Acute Appendicitis **1006**; Incidental Appendicectomy **1013**; Appendicular Mass (Periappendicular Phlegmon) **1014**; Appendicular Abscess **1015**; Faecal Fistula After Appendicectomy **1016**; Mucocele of Appendix **1016**; Neoplasms of the Appendix **1017**; Laparoscopic Appendicectomy **1017**

25. Rectum and Anal Canal 1020

Anatomy **1020**; Per-rectal Examination (Digital Examination of the Rectum) **1021**; Proctoscopy (Kelly's) **1022**; Sigmoidoscopy **1022**; Colonoscopy **1022**; Carcinoma Rectum **1023**; Solitary Ulcer Syndrome **1029**; Rectal Prolapse **1030**; Anorectal Malformations (ARM) **1034**; Pilonidal Sinus/Disease (Jeep Bottom; Driver's Bottom) **1036**; Piles/Haemorrhoids **1038**; Anal Fissure (Fissure-In-Ano) **1046**; Anorectal Abscess **1049**; Fistula-In-Ano **1051**; Anorectal Strictures **1056**; Condyloma Acuminata **1057**; Anal Intraepithelial Neoplasia (AIN) **1057**; Malignant Tumours of Anal Area **1057**; Anal Margin Tumours **1058**; Sacrococcygeal Teratoma **1058**; Anal Incontinence **1059**; Descending Perineal Syndrome **1059**; Proctitis **1060**; Proctalgia Fugax **1060**; Hidradenitis Suppurativa of Anal Region **1060**; Pruritus Ani **1060**; Gastrointestinal Haemorrhage (GI Bleed) **1061**

26. Urology 1065

A. Kidney 1065

Anatomy of Kidney and Ureter **1065**; Kidney—Anatomy **1065**; Ureter—Anatomy **1066**; Plain X-ray—Kidney, Ureter and Bladder (KUB) **1066**; Intravenous Urogram (IVU) **1067**; Retrograde Pyelography (RGP) **1068**; Renal Angiogram **1069**; Micturating Cystourethrography (MCU) **1069**; Ascending Urethrogram **1069**; Isotope Renography **1070**; Cystoscopy **1071**; Catheters **1071**; Foley's Catheter (Fredrick Eugene Basil Foley—American Urologist) **1072**; Malecot's Catheter **1073**; Red Rubber Catheter **1073**; Nephrostomy **1074**; Suprapubic Cystostomy (SPC) **1074**; Haematuria **1075**; Horseshoe Kidney **1076**; Cystic Diseases of the Kidney **1076**; Polycystic Kidney Disease (PCKD) **1077**; Duplication of Renal Pelvis and Ureter **1078**; Retrocaval Ureter **1079**; Ureterocele **1080**; Injuries to Kidney **1080**; Renal Tuberculosis **1081**; Hydronephrosis (HN) **1084**; Pyonephrosis **1088**; Carbuncle of Kidney (Renal Carbuncle) **1088**; Perinephric Abscess **1089**; Renal Calculus **1089**; Ureteric Calculi **1094**; Staghorn Calculus **1097**; Benign Tumours of Kidney **1098**; Wilm's Tumour (Nephroblastoma) **1099**; Renal Cell Carcinoma (RCC) **1100**; Approaches to Kidney (Surgical) **1104**

B. Urinary Bladder 1105

Anatomy **1105**; Ectopia Vesicae (Extrophy of the Bladder) **1106**; Urachal Anomalies **1106**; Vesical Calculus **1106**; Cystitis **1110**; Recurrent Cystitis **1110**; Interstitial Cystitis (Hunner's Ulcer, Elusive Ulcer) **1110**; Schistosoma Haematobium (Endemic Haematuria, Urinary Bilharziasis) (Swimmer's Itch) **1111**; Thimble or Systolic Bladder **1111**; Bladder Tumours **1112**; Transitional Cell Carcinoma (TCC) **1112**; Ureterosigmoidostomy **1115**; Rupture Bladder (Bladder Injury) **1115**; Residual Urine **1116**; Malakoplakia **1116**; Neurogenic Bladder **1117**; Vesicoureteric Reflux **1117**; Bladder Diverticula **1118**; Urinary Diversion **1119**; Urinary Fistulas **1120**

C. Prostate 1121

Anatomy 1121; Acid Phosphatase 1121; Prostate Specific Antigen (PSA) 1121; Benign Prostatic Hyperplasia (BPH) 1122; Prostatitis 1125; Bladder Outlet Obstruction (BOO) 1125; Carcinoma Prostate 1126

D. Urethra 1129

Anatomy 1129; Urethral Injury 1129; Rupture of Membranous Urethra and/or Prostatic Urethra (Posterior Urethra) 1129; Rupture of Bulbous Urethra (Anterior Urethra) 1130; Stricture Urethra 1131; Hypospadias 1132; Epispadias 1133; Posterior Urethral Valve 1133; Urethral Calculi 1134; Urethritis 1135; Extravasation of Urine 1135; Retention of Urine 1136

E. Penis 1138

Phimosis 1138; Paraphimosis 1139; Circumcision 1140; Balanoposthitis 1141; Chordee (Cordee) 1141; Priapism 1141; Peyronie's Disease (Induratio-Penis Plastica) 1141; Ram's Horn Penis 1142; Carcinoma Penis 1142; Buschke-Lowenstein's Tumour 1147

F. Scrotum 1148

Anatomy 1148; Fournier's Gangrene 1148; Hydrocele 1149; Primary Vaginal Hydrocele 1150; Secondary Hydrocele 1151; Haematocele 1154; Pyocele 1155; Cyst of Epididymis 1155; Spermatocele 1156; Varicocele 1157

G. Testis 1160

Anatomy 1160; Undescended Testis 1161; Ectopic Testis 1163; Retractile Testis 1164; Torsion of the Testis 1164; Testicular Tumours 1165; Paratesticular Tumours 1170; Orchitis 1170; Epididymitis 1171

27. Neurosurgery 1172

Head Injuries 1172; Extradural Haematoma 1177; Subdural Haematoma 1178; Subarachnoid Haemorrhage (SAH) 1179; Depressed Skull Fracture 1180; Hydrocephalus 1181; Intracranial Abscess 1182; Intracranial Aneurysms 1182; Intracranial Tumours 1183; Pituitary Tumours 1186; Craniopharyngiomas 1187; Spinal Dysraphism 1187; Meningocele 1188; Spina Bifida 1188; Intervertebral Disc Prolapse (IVDP) 1189; Tuberculosis of Spine (Caries Spine) 1190; Spinal Tumours 1193

28. Thorax 1194

Chest Injuries 1194; Fracture Ribs 1195; Flail Chest and Stove in Chest 1196; Pneumothorax 1197; Tension Pneumothorax 1197; Haemothorax 1198; Pleural Tap 1198; Bronchoscopy 1199; Empyema Thoracis 1199; Empyema Necessitans 1200; Lung Abscess 1201; Intercostal Tube Drainage 1202; Shock Lung (Stiff Lung) 1203; Pulmonary Embolism (PE) 1203; Surgical Emphysema 1204; Lung Cysts 1204; Mediastinal Tumours 1205; Thymomas 1207; Pancoast Tumours (Superior Sulcus Tumour) 1208; Chest Wall Tumours 1208; Pericarditis 1209; Acute Pericarditis 1209; Chronic Constrictive Pericarditis (Pick's Disease) 1210; Pericardial Tap 1210; Cardiac Tamponade 1210; Diaphragmatic Hernia 1211; Pulmonary Complications during Postoperative Period 1213; Surgical Management of Pulmonary Tuberculosis 1214; Video Assisted Thoracoscopic Surgery (VATS) 1214

Cardiac Surgery 1215

Anatomy 1215; Preoperative Assessment and Preparation of the Cardiac Patient 1216; Cardiopulmonary Bypass 1217; Congenital Heart Diseases 1217; Patent Ductus Arteriosus (PDA)—10% 1217; Coarctation of Aorta—5% 1218; Atrial Septal Defect (ASD)—7% 1218; Ventricular Septal Defect (VSD)—15% 1219; Pulmonary Stenosis 1219; Transposition of Great Vessels 1219; Tetralogy of Fallot 1220; Acquired Heart Disease 1220; Mitral Regurgitation 1221; Aortic Stenosis 1221; Aortic Regurgitation 1221; Valve Replacement Surgery 1222; Ischaemic Heart Disease (IHD) 1222; Cardiac Pacemakers 1223; Postoperative Care 1223

29. Adjuvant Therapy 1224

Radiotherapy 1224; Chemotherapy 1227; Cell Cycle 1227; Antimalignancy Drugs 1227; Hormone Therapy in Cancer 1227; Immunosuppression 1229; Immunotherapy 1229; Hybridoma 1229; Gene Therapy 1230

30. Anaesthesia 1231

Preoperative Assessment 1231; General Anaesthesia 1232; Anaesthetic Agents 1232; Oxygen 1232; Muscle Relaxants 1232; Reversal Agents 1232; Instruments in Anaesthesia 1232; Complications of General Anaesthesia 1234; Postoperative Care 1234; Monitoring the Postoperative Patient 1234; Regional Anaesthesia 1235; Topical Anaesthesia 1235; Infiltration Block 1235; Field Block 1235; Nerve Block 1235; Intravenous Regional Anaesthesia (Bier's Block) 1235; Spinal Anaesthesia 1235; Saddle Block 1236; Epidural Anaesthesia 1236; Caudal Anaesthesia 1237

31. Advanced Imaging Methods 1238

Ultrasound 1238; Doppler 1240; CT Scan 1240; Magnetic Resonance Imaging (MRI) 1242; Radionuclide Imaging 1243; Positron-Emission Tomography (PET Scan) 1243

32. Operative Surgery 1244

A. Asepsis and Sterilisation 1244

Sterilisation **1244**; Disinfection **1244**; Antisepsis **1244**; Asepsis **1244**; Different Methods of Disinfection/Sterilisation **1244**

B. Instruments 1247

Cheatle's Forceps **1247**; Sponge Holding Forceps (Rampley's) **1247**; Mayo's Towel Clip **1247**; Artery Forceps (Haemostat) **1247**; Right Angle Forceps **1248**; Kocher's Forceps **1248**; Allis' Tissue Holding Forceps **1248**; Babcock's Forceps **1248**; Lane's Tissue Holding Forceps **1249**; Morant-Baker's Appendix Holding Forceps **1249**; Volkmann's Retractor **1249**; Langenbeck's Retractor **1249**; Czerny's Retractor (Hernia Retractor) **1249**; Morris' Retractor **1249**; Deaver's Retractor **1249**; Doyen's Retractor **1250**; Self-retaining Retractor **1250**; Single Hook Retractor **1250**; Plain Non-toothed Dissecting Forceps **1250**; Toothed Dissecting Forceps **1250**; Surgical Needles **1250**; Needle Holder **1251**; Joll's Thyroid Retractor **1251**; Moynihan's Occlusion Clamp **1251**; Payr's Crushing Clamp (Gastric) **1251**; Desjardin's Choledocholithotomy Forceps **1251**; Bake's Dilator **1251**; Sinus Forceps (Lister's) **1252**; Scissors **1252**; Volkmann's Scoop **1252**; Tracheostomy Tube **1252**; Drains **1252**; Foley's Catheter **1254**; Malecot's Catheter **1254**; Simple Red Rubber Catheter **1254**; Lister's Urethral Dilator **1254**; Ryle's Tube **1254**; Infant Feeding Tube **1255**; Kehr's 'T' Tube **1255**; Proctoscope **1255**; Flatus Tube **1255**

C. Suture Materials 1256

Classification I **1256**; Classification II **1257**; Classification III **1257**; Classification IV **1257**; Classification V **1257**

D. Diathermy (Electrocautery) 1258

Types **1258**

E. Operative Procedure 1259

Abdominal Incisions **1259**; Vasectomy **1260**; Circumcision **1260**; Hydrocele **1261**; Inguinal Hernia **1261**; Appendicectomy **1262**; Thyroidectomy **1262**; Tracheostomy **1263**; Cryosurgery **1264**; Lasers in Surgery (Light Amplification Stimulated Emission of Radiation) **1265**; Staplers in Surgery **1265**; Nasojejunal Tube Feeding **1266**; Gossypiboma (Gossypium—Cotton Based in Latin) **1266**

F. Laparoscopic Surgery 1267

Advantages of Laparoscopic Surgery **1267**; Laparoscopic Cholecystectomy **1268**; Laparoscopic Appendicectomy **1269**; Advanced Laparoscopic Surgeries **1269**; Diagnostic Laparoscopy **1270**; Retroperitoneoscopy **1270**; Natural Orifice Transluminal Endoscopic Surgery (NOTES) **1270**

G. Dressings and Bandages 1272

Dressings **1272**; Bandages **1272**

H. Day Care Surgery 1274

Day Care Surgery **1274**; Surgical Audit **1275**; Surgeon and Law **1276**

33. Miscellaneous 1277

A. Fascinating Signs in Surgery 1277

B. Triads in Surgery 1287

C. Misnomers in Surgery 1288

D. Triangles in Surgery 1289

E. Drugs at a Glance 1291

Antibacterials **1291**; Sulfonamides **1291**; Quinolones **1291**; Penicillin **1292**; Ampicillin/Amoxycillin/Talampicillin/Pivampicillin **1292**; Methicillin **1292**; Cloxacillin/Dicloxacillin/Flucloxacillin **1292**; Carbenicillin/Ticarcillin **1292**; Piperacillin/Azocillin/Mezlocillin **1292**; Clavulanic Acid **1292**; Sulbactum **1292**; Tazobactum **1292**; Carbapenem/Imipenem/Meropenem **1292**; Lincomycin/Clindamycin **1292**; Vancomycin/Teicoplanin **1293**; Cephalosporins **1293**; Macrolides **1293**; Aminoglycosides **1293**; Tetracyclines **1294**; Chloramphenicol / Thiamphenicol **1294**; Drugs For Tuberculosis **1294**; Antiamoebic Drugs **1295**; Important Antihelminthics **1295**; Anticoagulants **1296**; Other Drugs **1296**

Appendix *1299*

Further Reading *1303*

Index *1305*

Chapter 1 General Surgery

A. Wounds and Wound Healing

> *One having a wound in his eyebrow. An ailment which I will treat. Treatment [of a wound in the eyebrow]: Now after thou hast stitched it, [thou shouldst bind] fresh meat upon [it] the first day. If thou findest that the stitching of this wound is loose, thou shouldst draw it together for him with two strips (of plaster), and thou shouldst treat it with grease and honey every day until he recovers.*
>
> **—[Anonymous],** circa 2500 BC

CHAPTER OUTLINE

- Wounds
- Classification of Wounds
- Wound Healing
- Compartment Syndrome
- Crush Injury
- Crush Syndrome
- Degloving Injuries
- Keloid
- Hypertrophic Scar
- Problems with Wound Healing

WOUNDS

Wound Definition

A wound is a break in the integrity of the skin or tissues often, which may be associated with disruption of the *structure and function.*

Wound is simply a disruption of any tissues—soft tissue or bone or internal organs. Ulcer is disruption or break in the continuity of any lining—may be skin, mucous membrane or others. Ulcer is one of the types of wounds.

CLASSIFICATION OF WOUNDS

I. Rank and Wakefield Classification

a. **Tidy wounds**
  - They are wounds like surgical incisions and wounds caused by sharp objects.
  - It is incised, clean, healthy wound without any tissue loss.
  - Usually primary suturing is done. Healing is by primary intention.

b. **Untidy wounds**
  - They are due to:
    - Crushing.
    - Tearing.
    - Avulsion.
    - Devitalised injury.
    - Vascular injury.
    - Multiple irregular wounds.
    - Burns.
  - Fracture of the underlying bone may be present.

  Wound dehiscence, infection, delayed healing are common.
  - Liberal excision of devitalised tissue and allowing to heal by secondary intention is the management.
  - Secondary suturing, skin graft or flap may be needed.

II. Classification based on Type of Wound

a. ***Clean incised wound*** is a clean cut wound with linear edge.

b. ***Lacerated wounds*** have ragged edges with devitalisation of some part of tissues. Wound excision and primary suturing is done.

c. ***Bruising and contusion***: Minor soft tissue injury with discoloration and haematoma formation without skin break.

I dressed him and God healed him.— **Ambroise Pares**



Figs 1.1A and B: A. Tidy wound; B. Untidy wound.

d. ***Haematoma***: It may be subcutaneous/intramuscular/subfascial/intra-articular. Small haematoma will get absorbed. Large haematoma once get infected forms an abscess and so it should be drained under general/regional anaesthesia adequately. Often haematoma contains only reddish plasmatic fluid which can be aspirated with wide bore needle.

e. Closed blunt injury.

f. Puncture wounds and bites.

g. ***Abrasion***: It is superficial and is due to shearing of skin where the surface is rubbed off. It heals by epithelialisation. It is only epidermal injury exposing dermis and dermal nerves.

h. Traction and avulsion injury.

i. ***Crush injury:*** It is caused by war wounds, road traffic accidents, tourniquet. It leads to:
   - Compartment syndrome.
   - Muscle ischaemia.
   - Gangrene, loss of tissue.

j. War wounds and gunshot injuries.

k. Injuries to ***bones and joints, may be open or closed.***



Fig. 1.3: Haematoma in the groin being aspirated. Haematoma may get infected or can compress adjacent structures.



Fig. 1.2: Lacerated wound in the scalp.



Fig. 1.4: Traumatic haematoma in the leg with abrasion over its surface.



Fig. 1.5: Subungual haematoma. Often nail may need to be removed to evacuate the blood clot.

l. Injuries to ***nerves, either clean cut or crush.***
m. Injuries to ***arteries and veins*** (major vessels).
n. Injury to internal organs, may be of penetrating or nonpenetrating (blunt) types.
o. ***Penetrating wounds***—commonly due to stab injuries. Common example is stab injury abdomen. Stab wound may be small on body surface but damage to the deeper organs like liver, spleen, major vessels like inferior vena cava/mesenteric vessels or intestines may be extensive and life-threatening. Patients with stab injury over abdomen should be admitted and evaluated by ultrasound or CT scan abdomen and observed. Often wound exploration is needed under general anaesthesia in operation theatre.



Fig. 1.6: Typical look of abrasion in face.



Fig. 1.7: Multiple abrasions



Fig. 1.8: Penetrating wound of the abdomen.

III. Classification based on Thickness of the Wound

- ***Superficial wound*** involving only epidermis and dermal papillae.
- ***Partial thickness*** wound with skin loss up to deep dermis with only deepest part of the dermis, hair follicle shafts and sweat glands are left behind.
- ***Full thickness*** wound with loss of entire skin and subcutaneous tissue causing spacing out of the skin edges.
- ***Deep wounds*** are the one extending deeper, across deep fascia into muscles or deeper structures.
- ***Complicated wounds*** are one associated with injury to vessels or nerves.
- ***Penetrating wound*** is one which penetrates into either natural cavities or organs.

IV. Classification based on Involvement of Structures

- ***Simple wounds*** are one involving only one organ or tissue.
- ***Combined wounds*** are one involving mixed tissues.

V. Classification based on the Time Elapsed

- ***Acute wound*** is up to 8 hours of trauma.
- ***Chronic wound*** is after 8 hours of trauma.

VI. Classification of Surgical Wounds

a. Clean wound
  - Herniorrhaphy.
  - Excisions.
  - Surgeries of the brain, joints, heart, transplant.
  - Infective rate is less than *2%.*

b. Clean contaminated wound
  - Appendicectomy.
  - Bowel surgeries.
  - Gallbladder, biliary and pancreatic surgeries.
  - Infective rate is 10%.

c. Contaminated wound
  - Acute abdominal conditions.
  - Open fresh accidental wounds.
  - Infective rate is 15-30%.



Fig. 1.9: Clean wound of thyroidectomy surgery.



Fig. 1.10: Hernia surgery with hernia sac. It is a clean wound.



Fig. 1.11: Appendicectomy wound, which is a clean contaminated wound.

d. Dirty infected wound

- Abscess drainage.
- Pyocele.
- Empyema gallbladder.
- Faecal peritonitis.
- Infective rate is 40-70%.



Fig. 1.12: Contaminated wound—burst appendicitis.



Figs 1.13A and B: Acute peritonitis with frank pus in peritoneal cavity due to bowel perforation is a dirty wound.

Wound classifications

• *Simple wounds:* Only skin is involved.	• Tidy wounds
• *Complex wounds:* Vessels, nerves, tendons or bones are involved.	• Untidy wounds
• *Closed wounds:*	• Clean wound
– Contusion	• Clean contaminated wound
– Abrasion	• Contaminated wound
– Haematoma	• Dirty wound
• *Open wounds:*	
– Incised wounds	
– Lacerated wounds	
– Crush injuries	
– Penetrating wounds	



Fig. 1.14: Degloving injury in the leg.



Fig. 1.15: Wound causing extensive skin loss and necrosis.



Fig. 1.16A



Fig. 1.16B

Figs 1.16A and B: Wound with tension sutures after surgeries for acute abdomen/peritonitis. It is a contaminated wound. Both vertical and horizontal tension sutures are shown.

WOUND HEALING

> *A scab is a beautiful thing—a coin the body has minted, with an invisible motto: In God We Trust. Our body loves us, and, even while the spirit drifts dreaming, works at mending the damage that we do.*
>
> **—John Updike,** 1984

Wound healing is complex method to achieve anatomical and functional integrity of disrupted tissue by various components like neutrophils, macrophages, lymphocytes, fibroblasts, collagen; in an organised staged pathways—haemostasis → inflammation → proliferation → matrix synthesis (collagen and proteoglycan ground substance) → maturation → remodelling → epithelialisation → wound contraction (by myofibroblasts).

Types of Wound Healing

Primary Healing (First Intention)

- It occurs in a clean incised wound or surgical wound. Wound edges are approximated with sutures. There is more epithelial regeneration than fibrosis. Wound heals rapidly with complete closure. Scar will be linear, smooth, and supple.

Secondary Healing (Second Intention)

- It occurs in a wound with extensive soft tissue loss like in major trauma, burns and wound with sepsis. It heals slowly with fibrosis. It leads into a wide scar, often hypertrophied and contracted. It may lead into disability.
- Re-epithelialisation occurs from remaining dermal elements or wound margins.

Start by doing what's necessary, then do what's possible and suddenly you are doing the impossible.



Fig. 1.17: Wound in the abdomen healing with second intention which requires secondary suturing once it granulates well. Secondary suturing is done after 10-14 days, once wound granulates well with proper control of infection. Scar in such type is prone to form incisional hernia.

Healing by Third Intention (Tertiary Wound Healing or Delayed Primary Closure)

After wound debridement and control of local infection, wound is closed with sutures or covered using skin graft. Primary contaminated or mixed tissue wounds heal by tertiary intention.

Stages of Wound Healing

- Stage of inflammation.
- Stage of granulation tissue formation and organisation. Here due to fibroblastic activity synthesisation of collagen and ground substance occurs.
- Stage of epithelialisation.
- Stage of scar formation and resorption.
- Stage of maturation.

Phases of Wound Healing

Inflammatory Phase (Lag or Substrate or Exudative Phase)

- It begins immediately after wound healing. It lasts for 4-6 days.
- Features of inflammation are rubor, calor, tumour, dolor and loss of function.
- Macrophages secrete fibroblastic growth factor which enhances angiogenesis.
- Polymorphonuclear leukocytes (PMN leukocytes) appear after 48 hours which secrete inflammatory mediators and bactericidal oxygen derived free radicals.
- These cells also remove clots, foreign bodies and bacteria.
- Chemical factors involved in wound healing are:
    - Growth factor—platelet derived, epidermal, transforming.
    - Interleukin.
    - Tumour necrosis factor.
    - Prostaglandins.
    - Collagenase.
    - Elastase.

Here *haemostasis, coagulation and* chemotaxis occurs. Coagulation begins in wound haematoma → formation of platelet fibrin thrombus → release of cytokines, PDFG (platelet derived growth factor), transforming growth factor β (TGF-β), platelet activating factor, fibrin, serotonin. Chemotaxis causes neutrophil migration first, and then activation of macrophages, lymphocytes leading into phagocytosis, wound debridement, matrix activation, angiogenesis. Chemotaxis factors are complement factors, interleukin-1, TNF-α (tumour necrosis factor-α) TGF-β and platelet factor. Activated macrophages produce free radicals and nitric oxide; release cytokine to activate lymphocytes which release interferon and interleukin (called as lymphokines). These actions are reduced in diabetes mellitus, Cushing's syndrome and immunosuppression increasing the rate of sepsis.



Figs 1.18A and B: Healing ulcer with healthy granulation tissue which is ready for skin grafting.

Proliferative Phase (Collagen/Fibroblastic Phase)

- Collagen and glycosamines are produced by fibroblasts.
- It begins in 7 days and lasts for 6 weeks.
- Hydroxyproline and hydroxylysine are synthesised by specific enzymes using iron, alpha ketoglutarate and vitamin C.
- Tropocollagen is produced which aggregates to form collagen fibrils.
- 80–90% of their final strength (in postoperative wounds) is achieved in 30 days.

Here proliferation of venular endothelial cell with fibroblast at wound margin and bed occurs by the action of cytokines and released growth factors. This *angiogenesis and fibroplasia* causes formation of granulation tissue which contains fibroblasts, neocapillaries, collagen, fibronectin and hyaluronic acid. Later neutrophils lead into apoptosis and die which are phagocytosed by macrophages; later macrophages go for apoptosis which are cleared by lymphocytes into draining lymph nodes.

Remodelling Phase (Maturation Phase)

- It begins at 6 weeks and lasts for 2 years.
- There is maturation of collagen by cross-linking which is responsible for tensile strength of the scar.
- Collagen production is not present after 42 days of wound healing.

Initially fibrin, fibronectin, proteoglycan deposition occurs; later collagen protein develops to form scar. Normal dermal skin contains 80% type I (20% type III) collagen; granulation tissue contains mainly type III collagen; scar contains both type I and III collagen equally. Basic essential components of collagen are proline and lysine. Hydroxylation of lysine and later glycosylation of this hydroxylysine decides the collagen molecule type. Hydroxylation of both proline and lysine as essential step needs adequate concentration of vitamin C, iron and α-ketogluteric acid. Collagen deposition in the wound is assessed by quantity of hydroxyproline excreted in urine. There is a balanced activity of collagen production and degradation of collagen (collagenolysis). Collagen is broken down by collagenase and *MMPs (matrix metallo prpteins)*. Procollagen through procollagenase → collagen fibril → cross-linking → collagen fiber → deposition. Deposited collagen → through collagenase → degradation and collagenolysis.

Scar strength is 3% in 1 week; 20% in 3 weeks; 80% in 12 weeks.

Phases of wound healing

Vascular response → blood coagulation/thrombosis → inflammation → new tissue formation → epithelialisation → wound contraction → remodelling.

Factors Affecting Wound Healing

Local factors

- Infection
- Presence of necrotic tissue and foreign body
- Poor blood supply
- Venous or lymph stasis
- Tissue tension
- Haematoma
- Large defect or poor apposition
- Recurrent trauma
- X-ray irradiated area
- Site of wound, e.g. wound over the joints and back has poor healing
- Underlying diseases like osteomyelitis and malignancy
- Mechanism and type of wound—incised/lacerated/crush/avulsion
- Tissue hypoxia locally reduces macrophage and fibroblast activity

General Factors

- Age, obesity, smoking
- Malnutrition, zinc, copper, manganese
- Vitamin deficiency (Vit C, Vit A)
- Anaemia
- Malignancy
- Uraemia
- Jaundice
- Diabetes, metabolic diseases
- HIV and immunosuppressive diseases
- Steroids and cytotoxic drugs
- Neuropathies of different causes

Management of Wounds

a. Wound is inspected and classified as per the type of wounds.

b. If it is in the vital area, then:
   - The airway should be maintained.
   - The bleeding, if present, should be controlled.
   - Intravenous fluids are started.
   - Oxygen, if required, may be given.
   - Deeper communicating injuries and fractures, etc. should be looked for.

c. If it is an incised wound then *primary suturing* is done after thorough cleaning.

d. If it is a lacerated wound then the *wound is excised* and primary suturing is done.

e. If it is a crushed or devitalised wound there will be oedema and tension in the wound. So after wound debridement or wound excision by excising all devitalised tissue, the oedema is allowed to subside for 2-6 days. Then *delayed primary suturing* is done.

f. If it is a deep devitalised wound, after wound debridement it is allowed to granulate completely. Later, if the wound is small *secondary suturing* is done. If the wound is large a split skin graft (Thiersch graft) is used to cover the defect.

g. In a wound with tension, *fasciotomy* is done so as to prevent the development of compartment syndrome.

h. Vascular or nerve injuries are dealt with accordingly. Vessels are sutured with 6-zero polypropylene nonabsorbable suture material. If the nerves are having clean cut wounds it can be sutured primarily with polypropylene 6-zero or 7-zero suture material. If there is difficulty in identifying the nerve ends or if there are crushed cut ends of nerves then marker stitches are placed using silk at the site and later secondary repair of the nerve is done.

i. Internal injuries (intracranial by craniotomy, intrathoracic by intercostal tube drainage, intra-abdominal by laparotomy) has to be dealt with accordingly. Fractured bone is also identified and properly dealt with.

j. Antibiotics, fluid and electrolyte balance, blood transfusion, tetanus toxoid (0.5 ml intramuscular to deltoid muscle), or antitetanus globulin (ATG) injection.

Wound debridement (wound toilet, or wound excision) is liberal excision of all devitalised tissue at regular intervals

> *Clinical diagnosis is an art, and the mastery of an art has no end: you can always be a better diagnostician*
>
> **—Logan Clendening**

(of 48-72 hours) until healthy, bleeding, vascular tidy wound is created.



Fig. 1.19: Lacerated wound over the eyebrow. Eyebrow should not be shaved during suturing.

Primary suturing means suturing the wound immediately within 6 hours. It is done in clean incised wounds.

Delayed primary suturing means suturing the wound in 48 hours to 10 days. It is done in lacerated wounds. This time is allowed for the oedema to subside.



Figs 1.20A and B: Delayed primary suturing is done once oedema over the wound subsides. It is done as single layer interrupted deep sutures using monofilament polypropylene or polyethylene.

Secondary suturing means suturing the wound in 10-14 days or later. It is done in infected wounds. After the control of infection, once healthy granulation tissue appears, secondary suturing is done.

Principles of wound suturing

- Primary suturing should not be done if there is oedema/infection/devitalised tissues/haematoma
- Always associated injuries to deeper structures like vessels/nerves or tendons should be looked for before closure of the wound
- Wound should be widened by extending the incision whenever needed to have proper evaluation of the deeper structures—*proper exploration*
- Proper cleaning, asepsis, wound excision/debridement
- Any foreign body in the wound should be removed
- Skin closure if it is possible without tension
- Skin cover by graft/flap—immediate or delayed
- Untidy wound should be made tidy and clean before suturing
- Proper aseptic precautions should be undertaken
- Antibiotics/analgesics are needed
- Sutured wound should be inspected in 48 hours
- Sutures are removed after 7 days

Remember

- *Wound toilet* is washing the wound thoroughly using normal saline—ideal
- *Wound debridement* (french-letting loose) is allowing content to come out by release incisions or faciotomies. But commonly debridement is used for wound excision
- *Wound excision* is actually correct terminology for excision of devitalised tissues once or serially
- *Radical wound excision* is (pseudotumour approach) is excising entire devitalised tissues leaving tissues with visible bleeding from all layers

COMPARTMENT SYNDROME

Compartment syndrome is a special entity; common in leg, forearm, thigh and arm; is a syndrome due to increased intracompartmental pressure within a limited space area.

Causes are—narrowed space due to tight dressings/plaster cast, lying on one limb in comatous patient; increased content within the compartment due to trauma like fractures, oedema, ischaemic injury, haematoma, positioning after trauma, burn injury, etc.; high pressure injection injuries like gun injury, oil based material injury, extravasation of chemotherapeutic drugs; snake bite.

It compromises circulation and function mainly of muscles and nerves. It often maintains the normal colour and temperature of the fingers and distal pulses may not be obliterated in spite of severe muscle ischaemia. Muscle ischaemia *more than 4 hours* causes muscle death and myoglobinuria. Irreversible nerve damage develops if ischaemia persists for 8 hours. Progressive, persistent severe pain which is aggravated by passive muscle stretching is the diagnostic sign. Tense tender regional lymph node is typical. Pulse will be usually normally felt in compartment syndrome; but may become absent if there is associated arterial injury. Compartment pressure more than 30 mmHg is an indication for *fasciotomy*.



Fig. 1.21: Necrotizing fasciitis with extensive skin involvement which requires adequate wound excision and eventual skin coverage.



Fig. 1.22: Fasciotomy for compartment syndrome should be longitudinal, deep and lengthy and should decompress the compartment to expose the underlying muscle. It should be done early.

It is common in calf and forearm. Closed injuries cause haematoma leading to increased pressure. It is often associated with fracture of the underlying bone which in turn compresses the major vessel further aggravating the ischaemia causing ***pallor, pulselessness, pain, paraesthesia, diffuse swelling*** and ***cold limb***.

If allowed to progress it may eventually lead to ***gangrene*** or ***chronic ischaemic contracture*** with deformed, disabled limb.

Problems with the compartment syndrome

- Infection, septicaemia and abscess formation
- Renal failure
- Gangrene of the limb
- Chronic ischaemic contracture
- Disabled limb, Volkmann's ischaemic contracture

Muscle necrosis releases myoglobulin which is excreted in the urine, damages the kidneys leading into renal failure.

Note:
Affected muscle when passively stretched worsens the pain—the most reliable clinical sign.

Treatment

- Compartment pressure will be persistently more than 30 mm Hg. It can be measured by placing a fine catheter in the compartment and using a pressure monitor. This is an indication for *fasciotomy*. Adequate lengthy incision involving skin, fat and deep fascia should be done until underneath muscle bulges out properly. Multiple incisions should be made if needed. Separate incision in each compartment should be done.

Fasciotomy done in forearm anterior compartment is a specific method. Carpal tunnel *should be released by cutting flexor retinaculum.* Incision begins at the junction of the thenar and hypothenar area; extends proximally initially transverse across flexion crease of the wrist at the ulnar border; then across forearm towards radial side of forearm; then in proximal forearm towards medial side creating convex flap towards lateral side. In the elbow it crosses along the medial border to reach the arm where it runs in arm along the medial part of the anterior arm. Injury to major nerves, palmar cutaneous branch of median nerve should be avoided while placing the incision. Incision should be deepened by cutting the deep fascia along the entire length of the incision. *Dorsal fasciotomy* should be added by placing longitudinal lengthy incision in the midline. Two longitudinal incisions on the dorsum of the hand also should be made.



Fig. 1.23: Incision for fasciotomy in upper limb begins at flexor retinaculum extending into the forearm with a convex flap towards radial side eventually leading towards medial epicondyle of the elbow joint.

- Antibiotics.
- Catheterisation.
- Mannitol or diuretics to cause diuresis, so as to flush the kidney.
- Fresh blood transfusion.
- Hyperbaric oxygen.

CRUSH INJURY

Crush injury is one where a part of the body is being squeezed/compressed between two high force or pressure systems. It causes extensive lacerations, bruising, compartment syndrome, crush syndrome, fractures, haemorrhage, etc. with extensive tissue destruction and devitalisation. Renal failure, hypovolaemic shock and sepsis are the most dreaded problems in crush injuries.



Fig. 1.24A



Fig. 1.24B

Figs 1.24A and B: Traumatic crush injury pelvis exposing testis and iliac vessels. Patient underwent hemipelvectomy.

CRUSH SYNDROME

It is due to crushing of muscles causing extravasation of blood and release of myohaemoglobin into the circulation leading to *acute tubular necrosis* and *acute renal failure*.

Causes

- Earthquakes.
- Mining and industrial accidents.
- Air crash.
- Tourniquet.

Initially tension increases in the ***muscle compartment*** commonly in the limb, which itself impedes the circulation and increases the ***ischaemic damage***. In 3 days, urine becomes discoloured and scanty, patient becomes restless, apathy and delirious with onset of ***uraemia***. Crush syndrome is often life-threatening. *Injury* is much worser than initial look.

Effects of crush syndrome

- Renal failure
- Toxaemia
- Septicaemia
- Disability with extensive tissue loss
- Gas gangrene

Treatment

- Tension in the muscle compartment is relieved by placing *multiple parallel deep incisions* in the limb so as to prevent further damage.
- Rheomacrodex, or mannitol is given to improve the urine output by improving the renal function.
- Alkalisation of urine is done by giving sodium citrate or sodium bicarbonate. It increases the solubility of acid haematin in the urine and so promotes its excretion. Urinary pH should be above 6.5 until urine does not show any myoglobin. Mannitol-alkaline diuresis should be 8 litre/day.
- Initial aggressive volume load using saline about 1-1.5 litres/hour is ideal in these patients.
- Haemodialysis is done sometimes as a life-saving procedure.
- Other measures:
  - Catheterization.
  - Oxygen therapy.
  - Antibiotics.
  - Blood transfusion.
  - Correction of severe hyperkalaemia.

Note:

Doing fasciotomy several days after crush injury may not be safe as it may lead to sudden release of myoglobulin causing myoglobulinuria and renal failure.

DEGLOVING INJURIES

- It occurs due to shearing force between tissue planes as traction—avulsion injury. It usually occurs between subcutaneous tissue and deep fascia or between muscle and bone. It can be localised or circumferential.



Fig. 1.25: Degloved injury.



Fig. 1.26: Degloving injury wherein skin often with soft tissues gets avulsed off the deeper plane to create extensive raw area which may bleed/get infected.

- It can be in one plane or multiple planes.
- It is commonly observed in machinery injuries or major road traffic accidents. It is much more extensive than of on initial presentation.
- Under anaesthesia fluoroscein is injected intravenously and viable skin is visible as fluorescent yellowish—green colour under ultraviolet light. As injection of fluoroscein is not fully safer, serial excision is better to look for dermal punctate bleeding.
- It needs examination under general anaesthesia, wound excision/radical excision, flap coverage, microflap surgeries,

skin grafting, with proper asepsis, and blood transfusion as there is significant blood loss in these injuries.

KELOID: *'Like a claw'*

- Keloid is common in blacks. Common in females.
- Genetically predisposed. Often familial. Very rare in Caucasians.
- There is defect in maturation and stabilization of collagen fibrils. Normal collagen bundles are absent.
- Keloid continues to grow even after 6 months, may be for many years. It extends into adjacent normal skin. It is brownish black/pinkish black (due to vascularity) in colour, painful, tender and sometimes hyperaesthetic; spreads and causes itching.
- Keloid may be associated with Ehlers-Danlos syndrome or scleroderma.
- When keloid occurs following an unnoticed trauma without scar formation is called as *spontaneous keloid*, commonly seen in Negroes.
- Some keloids occasionally become nonprogressive after initial growth.
- Pathologically keloid contains proliferating immature fibroblasts, proliferating immature blood vessels and type III thick collagen stroma.

Site: Common over the sternum. Other sites are upper arm, chest wall, lower neck in front.

Differential diagnosis: Hypertrophic scar.

Treatment: Controversial.



Figs 1.27A and B: Keloid in chest below the sternum and upper part of arm near shoulder—common sites of occurrence.



Figs 1.28A and B: Keloid over sternum (Butterfly shaped). Note the typical common site.



Fig. 1.29: Keloid in the upper part of the scar. It is the previous parotidectomy scar.

a. Steroid injection—***intrakeloidal triamcinolone***, is injected at regular intervals, may be once in 7-10 days, of 6-8 injections.
b. Steroid injection—excision—steroid injection.
c. Methotrexate and vitamin A therapy into the keloid.
d. Silicone gel sheeting; topical retinoids.
e. Laser therapy.
f. Vitamin E/palm oil massage.
g. *Intralesional excision* retaining the scar margin may prevent recurrence. *It is ideal and better than just excision.*



Figs 1.30A and B: Keloid in the chest wall due to burn wound.

h. Excision and irradiation or irradiation alone.
i. Excision and skin grafting may be done.

***Note*:**

Excision and primary suturing has got high recurrence rate; hence it is not usually practiced.

Recurrence rate is very high—more than 50%.

HYPERTROPHIC SCAR

- Occurs anywhere in the body.
- Not genetically predisposed. Not familial.
- Growth usually limits up to 6 months.
- It is limited to the scar tissue only. It will not extend to normal skin.


Epidermis
Linear scar in clean wound
Dermis
Scar (linear)
Subcutaneous tissue
Hypertrophic scar in infected wound limits to scar
Scar (hypertrophic)
Keloid in genetically predisposed extends to normal skin
Scar (keloid)

Fig. 1.31: Diagrammatic representation of linear, hypertrophic and keloid scar.

Differences between keloid and hypertrophic scar

		Keloid	*Hypertrophic scar*
a.	Genetic predisposition	Yes	No
b.	Site of occurrence	Chest wall, upper arm, lower neck, ear	Anywhere in the body, common in flexor surfaces
c.	Growth	Continues to grow without time limit	Growth limits for 6 months
		Extends to normal skin	Limited to scar tissue only
d.	Treatment	Poor response	Good response to steroids
e.	Recurrence	Very high	Is uncommon
f.	Collagen synthesis	20 times more than normal skin (Type III thick)	6 times more than normal skin (Type III fine collagen)
g.	Relation of size of injury and lesion	No relation. Small healed scar can form large keloid	Related to size of injury and duration of healing
h.	Age	Adolescents, middle age	Children
i.	Sex	Common in females	Equal in both
j.	Race	More in blacks (15 times)	No racial relation
k.	Structure	Thick collagen with increased epidermal hyaluronic acid	Fine collagen with increased alpha actin
l.	Features	Vascular, tender, itching	Not vascular, nontender, no itching
m.	Natural history	Progressive	Shows regression
n.	Problems	Hyperaesthesia, ulceration	Not much

- It is pale brown in colour, not painful, nontender.
- Often self-limiting also. It responds very well for **steroid** injection.
- Recurrence is uncommon.
- It is common in wounds crossing tension lines, deep dermal burns, wounds healed by secondary intention.



Figs 1.32A and B: Different contractures in hypertrophic scars over forearm, finger and neck.

Complications

- Often this scar breaks repeatedly and causes infection, pain.
- After repeated breakdown it may turn into ***Marjolin's ulcer***.



Fig. 1.33: 'Z' plasty is very useful method to release small contractures.

Treatment

It is controlled by ***pressure garments*** or often revision excision of scar and closure, if required with skin graft.

PROBLEMS WITH WOUND HEALING

- Wound infection is common in devitalized deep difficult wounds. Diabetes, immunosuppression, cytotoxic drugs, anaemia, malnutrition, malignancy increases the chances of wound infection.
- Wound dehiscence is common in all above said adverse factors. Wound suddenly gives away with pain causing copious serosanguineous discharge. After laparotomy when done specially as an emergency in trauma, acute abdomen and also in malignancy, abdominal closed wound may burst in 5-7 days. Usually all layers of abdomen give away causing discharge, occasionally bowel will extrude out. It needs emergency closure of the abdominal wound using specialized sutures or retention sutures.
- Hypertrophic scar or keloid formation due to altered collagen synthesis in the wound healing process. Collagen synthesis is increased *3 times* in hypertrophic scar and *20 times* in keloid.
- Deeper wound will cause specified problems like paraesthesia, ischaemia, paralysis, etc.

B. Ulcer

CHAPTER OUTLINE

- Ulcer
- Granulation Tissue
- Investigations for an Ulcer
- Traumatic Ulcer
- Trophic Ulcer
- Ulcer due to Chilblains
- Ulcer due to Frostbite
- Martorell's Ulcer
- Arterial/Ischaemic Ulcer
- Bairnsdale Ulcer
- Carcinomatous Ulcer
- Marjolin's Ulcer
- Rodent Ulcer
- Melanotic Ulcer
- Diabetic Ulcer
- Meleney's Ulcer
- Lupus Vulgaris
- Tuberculous Ulcer
- Bazin's Disease
- Tropical Ulcer
- Venous Ulcer
- Syphilitic Ulcer
- Soft Chancre/Soft Sore/Ducrey's Ulcer/Chancroid/Bubo
- Climatic Bubo/Tropical Bubo
- Clinical Examination of an Ulcer

ULCER

Definition

An ulcer is a break in the continuity of the covering epithelium, either skin or mucous membrane due to molecular death.

Parts of an Ulcer

a. *Margin*: It may be regular or irregular. It may be rounded or oval.

b. *Edge:* Edge is the one which connects floor of the ulcer to the margin. *Different edges are:*

Sloping edge. It is seen in a healing ulcer.

Its inner part is *red* because of red, healthy granulation tissue.

Its outer part is *white* due to scar/fibrous tissue.

Its middle part is *blue* due to epithelial proliferation.

Undermined edge is seen in a tuberculous ulcer. Disease process advances in deeper plane (in subcutaneous tissue) whereas (skin) epidermis proliferates inwards.

Punched out edge is seen in a gummatous (syphilitic) ulcer and trophic ulcer. It is due to endarteritis.

Raised and beaded edge (pearly white) is seen in a rodent ulcer (BCC). Beads are due to proliferating active cells.

Everted edge (rolled out edge): It is seen in a carcinomatous ulcer due to spill of the proliferating malignant tissues over the normal skin.

c. *Floor:* It is the one which is seen. Floor may contain discharge, granulation tissue or slough.



Fig. 1.34: Parts of an ulcer.

d. *Base:* Base is the one on which ulcer rests. It may be bone or soft tissue.



Fig. 1.35A



Fig. 1.35B

Figs 1.35A and B: Maggots on the ulcer bed in two different ulcers. Maggots eat only dead tissue/slough.

Induration of an Ulcer

Induration is a clinical palpatory sign which means a specific type of hardness in the diseased tissue. It is obvious in well-differentiated carcinomas. It is better felt in squamous cell carcinoma. It is also observed in long standing ulcer with underlying fibrosis. It is absent or less in poorly differentiated carcinomas and malignant melanoma. Less indurated carcinoma is more aggressive. Specific types of indurations are observed in venous diseases and chronic deep venous thrombosis. Brawny induration is a feature of an abscess. Induration is felt at edge, base and surrounding area of an ulcer. Induration at surrounding area signifies the extent of disease (tumour). Outermost part of the indurated area is taken as the point from where clearance of wide excision is planned.

Classification I (Clinical)

a. *Spreading ulcer:* Here edge is inflamed and oedematous.



Figs 1.36A and B: Callous ulcer without any sign of healing, without any granulation tissue. *It is due to callous attitude of the patient.*



Fig. 1.37: Ulcer edges.



Figs 1.38A and B: Tuberculous ulcer in chest wall and ankle in two separate patients. Note the undermined edge. Discharge study, biopsy and later antituberculous drugs are the treatment. They are *usually painful*.

b. *Healing ulcer:* Edge is sloping with healthy pink/red granulation tissue with serous discharge.

c. *Callous ulcer*: Floor contains pale unhealthy granulation tissue with indurated edge/base. It lasts for many months to years. *Ulcer does not show any tendency to heal.* It is due to callous attitude of the patient.

Classification II (Pathological)

a. *Specific ulcers:*
- Tuberculous ulcer.
- Syphilitic ulcer: It is punched out, deep, with "wash-leather" slough in the floor and with indurated base.
- Actinomycosis.
- Meleney's ulcer.

b. *Malignant ulcers:*
- Carcinomatous ulcer (Figs 1.40 and 1.41)
- Rodent ulcer (Fig. 1.39).
- Melanotic ulcer.

c. *Nonspecific ulcers:*
- *Traumatic ulcer*: It may be mechanical, physical, chemical—common.
- *Arterial ulcer:* Atherosclerosis, TAO (Fig. 1.42)
- *Venous ulcer:* Gravitational ulcer, post-phlebitic ulcer (Fig. 1.43).
- *Trophic ulcer/Pressure sore.*
- *Infective ulcers*: Pyogenic ulcer (See Fig. 1.44).
- *Tropical ulcers*: It occurs in tropical countries. It is callous type of ulcer, e.g. Vincent's ulcer.
- *Ulcers* due to chilblains and frostbite (*cryopathic ulcer*).
- *Martorell's hypertensive ulcer.*
- *Bazin's ulcer.*
- *Diabetic ulcer.*
- *Ulcers* due to leukaemia, polycythemia, jaundice, collagen diseases, lymphoedema.
- *Cortisol ulcers* are due to long time application of cortisol (steroid) creams to certain skin diseases. These ulcers are callous ulcers last for long time and require excision and skin grafting.



Fig. 1.39: Basal cell carcinoma of face (rodent ulcer). Ulcer edge is raised and beaded in appearance.



Fig. 1.40: Squamous cell carcinoma scalp. Note the ulcero-proliferative lesion with everted edge.



Fig. 1.41: Squamous cell carcinoma in the arm with secondaries in the axillary lymph node. Friable tumour tissues in the floor cause bleeding after trauma. Secondaries are fixed with ulceration. It is advanced disease.



Fig. 1.42: Ischaemic ulcer foot. Middle three toes are already amputated because of gangrene.



Fig. 1.43: Venous ulcers in both feet. Site is around ankle (Gaiter's zone). There are healthy granulation tissues. It needs skin grafting and definitive procedure for varicose veins after evaluation.



Fig. 1.44: Infective ulcer in the foot. Note the quantity of slough, exposed tendon and gangrenous toes. Patient requires below or above knee amputation.

Wagner's Grading/Classification of Ulcer

Grade 0 – Preulcerative lesion/healed ulcer
Grade 1 – Superficial ulcer
Grade 2 – Ulcer deeper to subcutaneous tissue exposing soft tissues or bone
Grade 3 – Abscess formation underneath/osteomyelitis
Grade 4 – Gangrene of part of the tissues/limb/foot
Grade 5 – Gangrene of entire one area/foot

GRANULATION TISSUE

It is proliferation of new capillaries and fibroblasts intermingled with red blood cells and white blood cells with thin fibrin cover over it (See Figs 1.51 and 1.52)



Fig. 1.45: Nonhealing ulcer with pale unhealthy granulation tissue.



Figs 1.46A and B: Ulcer in the foot, initially with slough; later after slough excision and regular dressings. Area requires skin grafting.



Figs 1.47A to C: Ulcer leg with exposed bone. Patient underwent local rotation flap to cover. Area from where flap is rotated is covered with split skin graft. When the bone is exposed, skin grafting is not possible.



Fig. 1.48: Large ulcer in the foot and leg with exposed tendon.



Figs 1.49A and B: Ulcers with healthy granulation tissue. Ulcer is ready for split skin grafting.



Fig. 1.50: Nonhealing ulcer foot in a diabetic patient with *Pseudomonas* infection. Note the greenish discharge in the wound. *Pseudomonas* infection is commonly hospital acquired.

Different discharges in an ulcer (as well as from a sinus)

a. *Serous:* In healing ulcer
b. *Purulent:* In infected ulcer
    Staphylococci: Yellowish and creamy
    Streptococci: Bloody and opalescent
    Pseudomonas: Greenish colour due to pseudocyanin
c. *Bloody:* Malignant ulcer, healing ulcer from healthy granulation tissue
d. *Seropurulent*
e. *Serosanguinous:* Serous and blood
f. *Serous with sulphur granules:* Actinomycosis
g. *Yellowish:* Tuberculous ulcer

Types

- ***Healthy granulation tissue***: It occurs in a healing ulcer. It has got sloping edge. It bleeds on touch. It has got serous discharge. 5 Ps of granulation tissue—*Pink, Punctate haemorrhages, Pulseful, Painless, Pin head granulation.* Skin grafting takes up well with healthy granulation tissue. Streptococci growth in culture should be less than 10^5/gram of tissue before skin grafting.



Fig. 1.51: Healing ulcer with healthy granulation tissue. Note the sloping edge.



Fig. 1.52: Exuberant granulation tissue (proud flesh) in an ulcer. It should be scooped out using Volkmann's scoop prior to skin grafting.



Fig. 1.53: Pyogenic granuloma.

- ***Unhealthy granulation tissue:*** It is pale with purulent discharge. Its floor is covered with slough. Its edge is inflamed and oedematous. It is a spreading ulcer.
- ***Unhealthy, pale, flat granulation tissue***: It is seen in chronic nonhealing ulcer (callous ulcer).
- ***Exuberant granulation tissue (Proud flesh)***: It occurs in a sinus or ulcer wherein granulation tissue protrudes out of the sinus opening or ulcer bed like a proliferating mass. It is commonly associated with a retained foreign body in the sinus cavity.
- Sprouting granulation tissue of sinus.
- ***Pyogenic granuloma***: It is a type of exuberant granulation tissue. Here granulation tissue from an infected wound or ulcer bed protrudes out, presenting as a well-localised, red swelling which bleeds on touching.
  Differential diagnosis: PapillomXa, skin adnexal tumours.
  Treatment: Antibiotics, excision and sent for biopsy.

INVESTIGATIONS FOR AN ULCER

- *Study of discharge*: Culture and sensitivity, AFB study, cytology.



Fig. 1.54: Typical greenish coloured ulcer due to *Pseudomonas* infection.



Fig. 1.55: X-ray showing osteomyelitis with sequestrum inside. Osteomyelitis prevents ulcer healing. Bone thickening on clinical examination is typical.

- *Edge biopsy*: Biopsy is taken from the edge because edge contains multiplying cells. Usually two biopsies are taken. Biopsy taken from the centre may be inadequate because of central necrosis.
- X-ray of the part to look for periostitis/osteomyelitis.
- FNAC of the lymph node.
- Chest X-ray, Mantoux test in suspected case of tuberculous ulcer.

Note:
Ulcer will not granulate if haemoglobin is less than 10 gm% and serum albumin is < 3 gm%.

Assessment of an Ulcer

- Cause of an ulcer should be found—diabetes/venous/arterial/infective.
- Clinical type should be assessed.
- Assessment of wound is important—anatomical site; size and depth of the wound; edge of the wound; mobility; fixity; induration; surrounding area; local blood supply. *Wound perimeter* may be useful in assessing this.
- *Wound imaging* is done by tracing it on a transparent acetate sheet at regular intervals.
- Presence of systemic features; regional nodal status; function of the limb/part; joint movements; distal pulses; sensations should be assessed.
- Severity of infection should be assessed—culture of discharge.
- Specific investigations like edge biopsy; X-ray of part; blood sugar; arterial/venous Doppler; angiogram.

Management of an ulcer

- Cause should be found and treated
- Correct the deficiencies like anaemia, protein and vitamins deficiencies
- Transfuse blood if required
- Control the pain
- Investigate properly
- Control the infection and give rest to the part
- Care of the ulcer by ***debridement, ulcer cleaning and dressing is done***
- Remove the exuberant granulation tissue
- Topical antibiotics for infected ulcers only like framycetin, silver sulphadiazine, mupirocin
- Antibiotics are not required once healthy granulation tissues are formed
- Once granulates, defect is closed with secondary suturing, skin graft, flaps

Ulcer cleaning is done using dilute povidone iodine and normal saline (*better and ideal*). It should be done daily or two times a day depending on the severity.

Conflict is the primary engine of creativity and innovation.—**Ranold Heifetz**



Fig. 1.56: Ulcer after wound debridement. Adequate wound excision is essential whenever there is slough and necrosis to allow granulation tissue to develop.



Figs 1.57A and B: Solutions commonly used for ulcer dressing—povidone iodine (brownish); EUSOL (colourless); hydrogen peroxide and normal saline. Note the EUSOL bath. Dilute EUSOL solution in a basin is used wherein ulcer foot is dipped and kept in place for 20-30 minutes. EUSOL removes the slough and cleans the ulcer bed. Hydrogen peroxide releases nascent oxygen and helps in removing necrotic material.

Debridement of an ulcer

- It is removal of devitalised tissue
- Small ulcers are debrided in ward
- Large ulcers are debrided in operation theatre under general anaesthesia
- All dead, devitalised, necrotic tissues are removed
- Slough should be separated adequately before debridement
- Often devitalised tissue separates on its own by autolysis
- Enzymes like collagenase are used for debridement
- Hydrotherapy and dressings are mechanical nonselective method of debridement

Dressing of an ulcer is done

- To keep ulcer moist
- To keep surrounding skin dry
- To reduce pain
- To soothen the tissue
- To protect the wound
- As an absorbent for the discharge

Note:

Debridement can be surgical, mechanical, autolytic or enzymatic.

Ulcer dressings

- *Cotton dressing*—cheap but traumatic
- *Paraffin dressing*
- *Polyurethane dressings* used in clean wounds
- *Alginates (seaweed) dressing* used when there are heavy exudates
- *Type 1 collagen dressings* cause haemostasis, proliferation of fibroblasts and improve the blood supply
- *Foam dressings* are highly absorbent, decrease the wound maceration, and reduce the frequency of dressing—hydrophilic polyurethane foam
- *Hydrocolloid dressings* help in separation of slough and autolysis of dead tissues
- *Transparent film dressings* are waterproof, permit oxygen and water vapour across and prevent contamination
- *Hydrogel dressings* used for clean wounds

Causes of formation of chronic ulcers in the skin

- Recurrent infection
- Trauma
- Absence of rest
- Poor blood supply
- Hypoxia
- Oedema of area
- Loss of sensation
- Malignancy
- Specific cause like tuberculosis
- Fibrosis
- Periostitis or osteomyelitis of the underlying bone

TRAUMATIC ULCER

- Such ulcer occurs after trauma. It may be *mechanical*—dental ulcer along the margin of the tongue due to tooth injury; *physical* like by electrical burn; *chemical* like by alkali injury.

- Such ulcer is acute, superficial, painful and tender. Secondary infection or poor blood supply of the area make it chronic and deep.
- *Footballer's ulcer* is a traumatic ulcer occurring over the shin of males due to direct knocks on the shin. It is staphylococcal infection with a chronic and deep ulcer.
- Traumatic ulcers can occur anywhere in the body due to trauma.



Fig. 1.58: Traumatic ulcers in the upper limb.



Fig. 1.59: Degloving ulcer with devitalised exposed tendons on the dorsum of the hand.

- Trauma causes infection, necrosis, fasciitis, crush injury, endarteritis of the skin leading into formation of large/deep nonhealing ulcer.
- Treatment depends on size and extent of ulcer. Regular dressing, later skin grafting is done.

TROPHIC ULCER (PRESSURE SORE/ DECUBITUS ULCER)

Pressure sore is tissue necrosis and ulceration due to prolonged pressure. Blood flow to the skin stops once external pressure becomes more than 30 mmHg (more than capillary occlusive pressure) and this causes tissue hypoxia, necrosis and ulceration. It is more prominent between bony prominence and an external surface.

It is due to:

- Impaired nutrition.
- Defective blood supply.
- Neurological deficit.

Sites

- Over the ischial tuberosity.
- Sacrum.
- In the heel.
- In relation to heads of metatarsals.
- Buttocks.
- Over the shoulder.
- Occiput.

Due to the presence of neurological deficit, trophic ulcer is also called as *neurogenic ulcer/neuropathic ulcer.* Initially it begins as callosity due to repeated trauma and pressure, under which suppuration occurs and gives way through a central hole which extends down into the deeper plane up to the underlying bone as *perforating ulcer (penetrating ulcer*).

Bedsores are trophic ulcers.

Factors causing pressure sore

- Normal stimulus to relieve the pressure is absent in anaesthetised patient
- Nutritional deficiencies worsens the necrosis
- Inadequate padding over the bony prominences in malnourished patients
- Urinary incontinence in paraplegia patient causes skin soiling-maceration-infection-necrosis



Fig. 1.60: Trophic ulcer—heel. It is deep punched out ulcer. It often requires rotation flap/transposition flap.



Figs 1.61A and B



Fig. 1.61C

Figs 1.61A to C: Bedsore (decubitus ulcer) over the greater trochanter, ischium and sacrum. Bedsore is a trophic ulcer. It is usually with punched out edge.

Clinical Features

- Occurs in 5% of all hospitalised patients.
- Painless ulcer which is punched out.
- Ulcer is nonmobile with base formed by bone.

Neurological causes

- Diabetic neuropathy
- Peripheral neuritis
- Tabes dorsalis
- Spina bifida
- Leprosy
- Spinal injury
- Paraplegia
- Peripheral nerve injury
- Syringomyelia



Fig. 1.62: Bedsore over the sacrum with thick black slough on the surface.

Staging of pressure sore

- Nonblanching erythema—early superficial ulcer
- Partial thickness skin loss—late superficial ulcer
- Full thickness skin loss extending into subcutaneous tissue but not through fascia—early deep ulcer
- Full thickness skin loss with fascia and underlying structures like muscle/tendon/bone, etc—late deep ulcer

Investigations

Study of discharge, blood sugar, biopsy from the edge, X-ray of the part, X-ray spine.

Treatment

- Cause should be treated.
- Nutritional supplementation.
- Rest, antibiotics, slough excision, regular dressings.
- *Vacuum assisted closure (VAC):* It is the creation of intermittent negative pressure of minus 125 mmHg to promote formation of healthy granulation tissue. Negative pressure reduces tissue oedema, clears the interstitial fluid and improves the perfusion, increases the cell proliferation and so promotes the healing. A perforated drain is kept over the foam dressing covered over the pressure sore. It is sealed with a transparent adhesive sheet. Drain is connected to required vacuum apparatus.



Fig. 1.63: Vacuum assisted closure of an ulcer.

- Once ulcer granulates well, flap cover or skin grafting is done.
- Excision of the ulcer and skin grafting.
- Flaps—local rotation or other flaps (transposition flaps).
- Cultured muscle interposition.
- *Proper care:* Change in position once in 2 hours; lifting the limb upwards for 10 seconds once in 10 minutes; nutrition; use of water bed/air bed/air-fluid floatation bed and pressure dispersion cushions to the affected area; urinary and faecal care; hygiene; psychological counselling. Regular skin observation; keeping skin clean and dry (using regular use of talcum powder); oil massaging of the skin and soft tissues using clean, absorbent porous clothing; control and prevention of sepsis helps in the management.

ULCER DUE TO CHILBLAINS

- It is due to exposure to intense cold causing blisters and ulcerations in the feet.
- These ulcers are ***superficial.***
- It is due to excessive cutaneous arteriolar constriction.
- The condition is also called as ***perniosis.***

ULCER DUE TO FROSTBITE

- It is due to exposure of a part to wet cold below the freezing point (cold wind).
- There is arteriolar spasm, denaturation of proteins and cell destruction.
- It leads to gangrene of the part.
- Ulcers here are always ***deep.***

MARTORELL'S ULCER (1945)

- It is seen in *hypertensive* patients often with atherosclerosis.
- It is seen in *calf*. Often it is *bilateral* and *painful*.
- Necrosis of calf skin occurs with sloughing away and formation of deep, punched out ulcers extending into the deep fascia.
- There is sudden obliteration of the arterioles of the calf skin.
- All *peripheral pulses* are present.
- *It takes months to heal.*

  Treatment: Once ulcer granulates well, skin grafting with lumbar sympathectomy is done.



Fig. 1.64: Typical Martorell's ulcer.

ARTERIAL/ISCHAEMIC ULCER

- It is common in toes, feet or legs; often can occur in upper limb digits. It is due to poor blood supply following blockage of the digital or medium sized arteries.
- Atherosclerosis and TAO (Thromboangiitis obliterans) are common causes in lower limb.
- Cervical rib, Raynaud's phenomenon and vasculitis are common causes in upper limb.
- Ulcer initially occurs after trauma, soon becomes nonhealing, spreading with scanty granulation tissue.
- Ulcer is very painful, tender and often hyperaesthetic. Digits may often be gangrenous. Intermittent claudication, rest pain are common. Other features of ischaemia are obvious in the adjacent areas. They are—pallor, dry skin, brittle nail, patchy ulcerations, and loss of hair.
- Ulcer is usually deep, destructs the deep fascia, exposing tendons, muscles and underlying bone. Dead tendons look pale/greenish with pus over it.
- **Management:** Specific investigations like arterial Doppler, angiogram, lipid profile, and blood sugar are done. *Treatment* is done accordingly—drugs like vasodilators; arterial surgeries may be needed.



Fig. 1.65: Ischaemic ulcer foot. This ulcer is likely to lead into gangrene and eventual amputation.



Fig. 1.66: Ischaemic ulcer foot with gangrene of toes without evidence of any bleeding with exposed tendons

BAIRNSDALE ULCER

- It is a chronic, irregular, undermined ulcer due to *Mycobacterium ulcerans* infection.
- Deep severe form, with extensive dermal necrosis is called as ***'Buruli ulcer.'***
- Discharge study will show acid-fast bacilli.
- Antituberculous drugs resolve the ulcer usually. Skin grafting may be required later.

A man without purpose is like a ship without rudder.

CARCINOMATOUS ULCER (EPITHELIOMA, SQUAMOUS CELL CARCINOMA)

- It arises from prickle cell layer of skin. It may initially begin as a nodule or ulcer; but later forms an ulcerative lesion with rolled out/everted edge. Floor contains necrotic content, unhealthy (tumour) granulation tissue and blood.
- Ulcer bleeds on touch and is vascular and friable. Induration is felt at the base and edge. It is usually circular or irregular in shape. Initially ulcer is mobile but becomes nonmobile once it infiltrates into deeper tissues. The typical foul smell is due to necrotic material, infection and release of polyamides from the tumour cells.
- Hard, discrete regional lymph nodes are often palpable, initially mobile but later become fixed. Lymph nodes can fungate eventually. Ulcer and lymph nodes are initially painless; but becomes painful and tender once there is deeper infiltration or secondary infection. Systemic spread is rare. It is a *locoregional malignant* disease.
- *Verrucous carcinoma* is exophytic, locally malignant well differentiated squamous cell carcinoma without lymphatic spread.
- **Management:** Edge biopsy; FNAC of regional lymph nodes are the investigations. Treated with wide local excision with skin grafting and regional lymph node block dissection.



Fig. 1.67: Squamous cell carcinoma heel. It is proliferative ulcer. Note the raised and everted edge.



Fig. 1.68: Proliferative squamous cell carcinoma in the amputation stump. Patient has undergone amputation earlier for distal carcinomatous ulcer. This is recurrence at the stump site. SCC can be proliferative, ulceroproliferative or proliferative ulcer on clinical look.

MARJOLIN'S ULCER (Rene Marjolin,1828, Paris)

- It is *slow* growing *locally* malignant lesion—a very well differentiated squamous cell carcinoma occurring in an *unstable scar of long duration*.
- It is commonly seen in chronic venous ulcer scar. Often it is observed in burns scar and scar of previous snake bite. Lesion is ulcerative/proliferative.
- Edge may be everted or may not be. It is painless as scar does not contain nerve fibrils. It does not spread into lymphatics as scar is devoid of lymphatics. Induration is felt at the edge and base. There is marked fibrosis also.
- Once lesion spreads into adjacent normal skin, it can spread into regional lymph nodes behaving like squamous cell carcinoma.
- *Managed by* edge biopsy and wide local excision and grafting.



Fig. 1.69: Marjolin's ulcer in a chronic unstable scar (of long duration) in the leg. It does not spread through lymphatics.

RODENT ULCER

- It is ulcerative form of basal cell carcinoma which is common in face.
- Ulcer shows central area of dry scab with peripheral raised active and *beaded (pearly white)* edge. Often floor is pigmented. It erodes into deeper plane like soft tissues, cartilages and bones hence the name—*rodent ulcer*.
- As lymphatics are blocked early in the disease by large tumour cells, it does not spread to regional lymph nodes. Blood spread is absent. It is only *locally malignant.*
- It is common in face; rarely can it occur over tibia, external genitalia, mucocutaneous junction. It does not occur in mucosa.
- **Management:** Edge biopsy, CT scan of the part to see the depth, wide excision

MELANOTIC ULCER

- It is ulcerative form of melanoma. It can occur in skin as *de novo* or in a pre-existing mole. Ulcer is pigmented often with a halo around.
- Ulcer is rapidly growing, often with satellite nodules and '*in-transit*' lesions. It is very aggressive skin tumour arising from melanocytes.

- It spreads rapidly to regional lymph nodes which are pigmented. Blood spread to liver, lungs, brain, and bones is common. It can occur in mucosa, genitalia, and eye. It is a systemic malignant disease.
- **Management:** Excision biopsy (usually *incision biopsy is not done*), FNAC lymph node, US abdomen. *Treatment* is wide local excision, regional node block dissection, chemotherapy.



Figs 1.70A and B: Melanotic ulcer in the foot with enlarged inguinal lymph nodes.

DIABETIC ULCER

Causes

- Increased glucose in the tissue precipitates infection.



Fig. 1.71: Diabetic ulcer foot.

- Diabetic microangiopathy which affects microcirculation.
- Increased glycosylated haemoglobin decreases the oxygen dissociation.
- Increased glycosylated tissue protein decreases the oxygen utilization.
- Diabetic neuropathy involving all sensory, motor and autonomous components.
- Associated atherosclerosis.



Figs 1.72A and B: Foot is the most common area for diabetic infective problems. It can cause abscess, ulcer, osteomyelitis, gangrene, septicaemia. Initially patient undergoes toe amputation but later eventually land with below knee or above knee amputation.

Sites

- Foot-plantar aspect—is the most common site.
- Leg.
- Upper limb, back, scrotum, perineum.
- Diabetic ulcer may be associated with ischaemia.
- Ulcer is usually spreading and deep.

Investigations

- Blood sugar both random and fasting.
- Urine ketone bodies.
- Discharge for culture and sensitivity.
- X-ray of the part to see osteomyelitis.
- Arterial Doppler of the limb; glycosylated haemoglobin estimation.

When you cease to dream, you cease to live.

Problems with diabetic ulcer

- Neuropathy, in foot—clawing of toes, hammer toe (due to intrinsic muscle paralysis)
- Multiple deeper abscesses; osteomyelitis of deeper bones are common
- Reduced leukocyte function; resistant infection; spreading cellulitis
- Arterial insufficiency
- Septicaemia; diabetic ketoacidosis
- Associated cardiac diseases like ischaemic heart disease

Treatment

- Control of diabetes using insulin.
- Antibiotics.
- Nutritional supplements.
- Regular cleaning, debridement, dressing.
- Once granulates, the ulcer is covered with skin graft or flap.
- Toe/foot/leg amputation.
- Microcellular rubber (MCR) shoes to prevent injuries; care of foot.

MELENEY'S ULCER (POSTOPERATIVE SYNERGISTIC GANGRENE)

- It is commonly seen in *postoperative wounds* in abdomen and chest wall like empyema drainage or after surgery for peritonitis.
- It is an acute rapidly spreading ulcer with destruction and deep burrowing of subcutaneous tissues.



Fig. 1.73: Meleney's ulcer.

- Occasional symbiotic infection may develop in leg or hand. This can be as *de novo* association of ulcerative colitis or on a pre-existing venous ulcer.

Aetiology

- It is common in old age and immunosuppressed individuals and after surgery for infected cases.
- It is caused by microaerophillic streptococci, *Staphylococcus aureus* and anaerobes.

Sites

- It is common in abdomen and thorax. It begins in wound margin and spreads rapidly. It can also occur in other areas of skin.
- Infection is severe, often with endarteritis of the skin leading to ulcer and destruction.

Clinical Features

- Features of toxaemia.
- Spreading painful ulcer with discharge.
- Abundant granulation tissue with purple and red zones.

Management

- Random blood sugar is checked, if diabetic it has to be controlled.
- Antibiotics.
- Blood transfusion, critical care.
- Adequate excision of dead tissues until it bleeds.
- Once healthy granulation tissue is formed skin grafting is done.

LUPUS VULGARIS ('Lupus'—Wolf)

- It is *cutaneous tuberculosis* which occurs in young age group.
- Commonly seen on face, hand and forearm; starts as *typical **apple-jelly nodule*** with congestion of skin around. Eventually a superficial ulcer with *undermined edge* is formed.
- Glass slide pressed firmly on the diseased area to eliminate the surrounding hyperaemia causes clinically obvious *apple-jelly* appearence.



Figs 1.74A and B: Lupus vulgaris in forearm and thumb. Biopsy confirmed tuberculosis. Patient needs antituberculous drugs (*Courtesy:* Dr Ashfaque, DNB, Surgeon, KMC, Mangalore).

- The ulcer is active and destruction occurs at the periphery with healing takes place at the centre.
- Often lesion extends into nose and oral cavity involving the mucosa.
- Due to lymphatic obstruction facial oedema can occur.
- Long-standing lupus vulgaris can turn into *squamous cell carcinoma.*

Investigation

ESR, discharge study, biopsy, chest X-ray.

Treatment

a. Antituberculous drugs.
b. If complete healing does not occur, then ***excision and skin grafting*** is required.

TUBERCULOUS ULCER

It is due to *Mycobacterium tuberculosis*. It is usually due to cold abscess later forming ulcer in the neck, chest wall, axilla and groin. It can also be primary tuberculosis of the skin (commonly in face). Ulcer can be single or multiple; oval or rounded; with undermined edge (due to progression of disease outwards underneath and healing inwards by skin), painful and tender with caseating material on the floor. Ulcer is usually not deep. Regional lymph nodes may be enlarged matted, firm, and nontender.



Fig. 1.75: Tuberculous ulcer is typically undermined.

Management: Discharge study for epithelioid cells (modified histiocytes), AFB; edge biopsy, antituberculous drugs.

BAZIN'S DISEASE (ERYTHROCYANOSIS FRIGIDA/ERYTHEMA INDURATUM)

(Pierre Bazin, 1850, Paris)

- It is localised area of fat necrosis with chronic ischaemia of ankle skin affecting exclusively adolescent girls. It may be due to tuberculosis. It is observed in girls with more / thick subcutaneous fat around ankle.
- Bluish pink leg which becomes bluish mottling in extreme cold season. On warming, skin turns bright red and painful which is typical due to hyperaemia. In these patients perforating arteries perfusing the skin around the ankle are small/ poor/not existing causing ischaemia of skin around ankle which becomes hyperaesthetic and sensitive for temperature alteration.
- Symmetrical, purple nodules develop in ankles and lower leg which later break down forming multiple, small, painful, superficial ulcers often with ankle oedema and pigment scars.
- Treatment is antitubercular drugs and lumbar sympathectomy.

TROPICAL ULCER

- It is endemic in monsoon hit humid tropics with repeated epidemics but sporadic in subtropics. Trauma or insect bite leads into infection exclusively in the lower part of the leg and foot.
- It is an acute ulcerative lesion of the skin observed in tropical regions like Africa, India and South America. It is associated with lower socioeconomic group, anaemia, and malnutrition and vitamin deficiency.
- It is commonly caused by *Fusobacterium fusiformis* (Vincent's organisms) and *Borrelia vincentii*.
- There are abrasions, redness, papule and pustule formation, acute regional lymphadenitis and severe pain.
- Pustule bursts in 3 days along with necrobiosis and phagedena causing a spreading painful ulcer with an undermined edge, brownish floor and serosanguineous discharge. Spreading stops in few weeks with ulcer persisting for many months to years. Eventually a chronic, large nonhealing/callous ulcer forms with persistent pain, profuse serosanguineous discharge, extremely unpleasant odour, long existing firmly adherent slough in the floor without any obvious constitutional symptoms. During healing it causes a slight pigmented, parchment like round scar.
- Often destruction is progressive without cessation (*phagedena*) to extend into entire soft tissues of foot and leg inviting amputation. ***Phagedena*** (Greek—to eat) is also seen in chancroid and cancrum oris.
- Occasionally squamous cell carcinoma can develop in it.
- **Treatment:** Improvement in nutrition, penicillin, metronidazole, Eusol dressing, skin grafting at a later date.

Happiness is never found until we have the grace to stop looking for it.

VENOUS ULCER (GRAVITATIONAL ULCER)

- It is common around ankle (*gaiter's zone*) due to chronic venous hypertension. It is due to *varicose veins* (long saphenous vein/short saphenous vein/perforators) or *post-phlebitic* limb.
- Post-phlebitic limb consists of veins that is been partially recanalised following deep venous thrombosis which causes increased venous pressure around ankle through perforators.
- Varicose veins are common in *females*. 50% of venous ulcer is due to varicose veins; 50% are due to post-phlebitic limb (previous DVT). Pain, discomfort, pigmentation, dermatitis, lipodermatosclerosis, ulceration, periostitis, ankle joint ankylosis, talipes equinovarus deformity and Marjolin's ulcer are the problems of varicose veins and later of venous ulcer.



Fig. 1.76: Venous ulcer around ankle with skin changes over surrounding area. It is the most common site of venous ulcer.

- Ulcer is initially painful; but once chronicity develops it becomes painless. Ulcer is often vertically *oval*; commonly located on the *medial side*; occasionally on lateral side; often on both sides of the ankle; but *never* above the middle third of the leg. Floor is covered with pale or often without any granulation tissue. When well-granulated, edge is sloping. Induration and tenderness is seen often at the base of an ulcer.
- Inguinal lymph nodes (*vertical group*) are often enlarged. Ulcer often attains very large size which is nonhealing, indolent and callous.
- Ulcer heals on rest and treatment; but reforms again. Scarring is common due to repeated healing and recurrent ulcer formation. This *unstable scar* of long duration may lead into squamous cell carcinoma (*Marjolin's ulcer*).
- **Management**: Venous Doppler, regular dressing, skin grafting, specific treatment for varicose veins.

SYPHILITIC ULCER

- Nowadays it is a rare entity. It is caused by *Treponema pallidum* bacterium. It is a sexually transmitted disease. It is named as '*Syphilis*' after a shepherd named *Syphilus* who acquired the disease as was written in a poem by Francastorius of Verona. Many clinical lesions are observed in different stages of syphilis.
- *John Hunter* inoculated himself with syphilis organism to study the clinical features and effects. After 24 years of inoculation, he died from rupture of syphilitic aortic aneurysm at the age of 65.
- Genital chancre (*Hard chancre, Hunterian chanre*) is painless, hard, button like, indurated, nonbleeding ulcer; usually seen in corona or frenum of penis, often on lips, breasts and anal region; appears 4 weeks after initial infection in ***first stage*** of the disease (***primary syphilis***). Shotty, painless, firm, discrete groin lymph nodes may get enlarged along with genital chancre. Suppuration in these nodes will not occur. Extragenital chancres in lips and breasts show enlarged neck/axillary nodes which are inflamed, painful and also often may be matted.
- During ***second stage*** (***secondary syphilis***) white, thickened *mucous patches* appear commonly in the mouth like small, circular, superficial *snail track* ulcers. Also there appears raised, flat, hypertrophied, and warty like epithelium at mucocutaneous junctions (mouth, genitalia) called as *condyloma lata*. Generalised, shotty, hard, discrete, painless lymph nodes are palpable, epitrochlear and suboccipital nodes in particular are enlarged. *Epitrochlear nodes* are felt 1-2 cm above the medial epicondyle (It is also enlarged in non-Hodgkin's lymphoma/NHL). Iritis, arthritis, hepatitis (massive liver in syphilis is called as *hepar lobatum*), meningitis, syphilitic osteitis with *'ivory' sequestrum*, *coppery red skin rash*, *moth-eaten alopecia* are other features of second syphilis.
- ***In tertiary/late stage syphilis*** *gummatous ulcer* develops. It is deep, punched out, painless, nontender ulcer with *wash leather slough* in the floor, with *'silvery tissue paper'* like scar around and occurs over the subcutaneous bones like tibia, sternum, skull, palate or other area. It also can occur over the tongue, anterior aspect of the scrotum. It is due to delayed hypersensitivity reaction with endarteritis obliterans and vasculitis. Perforation of nasal septum/palate can occur. *Clutton's joint* and *Sabre tibia* are often seen. Lymph nodes are not affected in tertiary syphilis. Neurosyphilis (*tabes dorsalis*), *aneurysm of arch of aorta* are other features of tertiary syphilis.
- Tabes dorsalis presenting as generalized paralysis of insane is often called as ***late tertiary or quaternary*** syphilis.
- Long quiescent asymptomatic period from secondary to tertiary is called as ***latent syphilis***.
- Secondary syphilitic stage shows plenty of circulating *Treponema spirochaetes* in blood where as in tertiary stage spirochaetes are less or absent.

SOFT CHANCRE/SOFT SORE/DUCREY'S ULCER/CHANCROID/BUBO

- These multiple irregular genital ulcers appear 3 days after infection with *Haemophillus ducreyi* as a venereal disease.
- They are acute painful, tender, nonindurated ulcers. Floor shows yellowish slough with purulent discharge. Edge is oedematous and inflamed. Acute regional lymphadenitis with suppuration presenting as tender, soft or firm swelling is common. Such soft fluctuant inguinal swelling is termed as ***bubo***.
- *Treatment* is by drugs like co-trimoxazole, erythromycin, ciprofloxacillin, ceftriaxone; aspiration of bubo.

CLIMATIC BUBO/TROPICAL BUBO

- It is due to *lymphogranuloma inguinale*, a *venereal* spreading organism (LGV, *Chlamydia* type L1, 2, 3).
- In LGV, lesion of *primary genital stage* is small, painless and commonly unnoticed.
- Lesion *of secondary stage* develops in 2 weeks. In males inguinal lymph nodes; in females intrapelvic and pararectal nodes are involved. Suppuration of inguinal nodes eventually occurs leading into discharging sinuses. *Frei intradermal test* becomes positive in 6 weeks and remains positive for life time.
- *In tertiary stage,* eye, joint, meninges may get involved after many years. Repeated chronic inflammation, lymphatic blockage, scarring can cause rectal stricture and vulval elephantiasis (*esthiomene*) in females.
- *Treatment* is tetracycline for 3 weeks.

OTHER ULCERS

- Ulcers can occur, in various parts like over shin, legs, feet, face, chest wall, in various diseases like anaemia, polycythaemia, sickle cell disease, hereditary spherocytosis, leukemia, vasculitis, autoimmune diseases like rheumatoid arthritis, Paget's disease of bone (deep, nonmobile, fixed to bone; common in tibia), ulcerative colitis, etc.
- *Treponema pertenue* causing *Yaws* (Frambesia) can have multiple painless ulcers in leg and feet due to walking with bare foot (organism enters through abrasion) which heals spontaneously leaving a *tissue paper like scar*.
- Poor hygiene and dressings can cause multiple, small, red often scabbed *Staphylococcus aureus ulcers* on the skin over the leg and feet which is often recurrent and disturbing.

CLINICAL EXAMINATION OF AN ULCER

History

- Mode of onset
- Duration
- Pain—its time of onset, progress, severity
- Discharge from ulcer
- History suggestive of associated disease/treatment history

Local examination of an ulcer

Inspection

- Site of ulcer—arterial ulcer over the digits; venous ulcer over the malleoli; trophic ulcer over heel/pressure points
- Size of ulcer
- Shape of ulcer
- Number
- Margin whether regular/irregular/well-defined/ill-defined
- Edge of ulcer
- Floor of the ulcer—floor is the one what is seen. It rests on the base (Base is not seen; it is only felt). Red color in floor—healing ulcer; slough with pale/purulent discharge—nonhealing ulcer or tubercular; wash leather slough—syphilitic ulcer/proliferative and nodular floor—squamous cell carcinoma; pigmented—melanoma, pigmented basal cell carcinoma
- Discharge from ulcer bed—serous, serosanguinous, bloody, purulent; color of discharge—greenish in *Pseudomonas* infection
- Surrounding area to be examined for inflammation, oedema, eczema, scarring, pigmentation
- Inspection of the entire part/limb

Palpation

- Tenderness over edge, base and surrounding area
- Warmness over surrounding area
- Edge palpation for induration
- Palpation of base for induration/fixity
- Depth of ulcer—trophic ulcer is deep with bone as its base—often it is measured gently in mm
- Bleeding on palpation and touching
- Palpation for deeper structures and its relation to ulcer
- Surrounding skin and tibia/calcaneum/other related bones for thickening
- Examination of adjacent joint for mobility
- Examination of regional lymph nodes is essential—tenderness (acute infection), mobility, consistency may be hard (carcinoma metastasis)/ firm/soft and nontender (inflammatory); fixity (malignancy); ulceration or fungation (malignancy); sinus (nonspecific, tuberculosis or carcinoma)

Specific systems

- Examination of arterial pulse, peripherally in relation to ulcer and cardiovascular system for murmur
- Examination for varicose veins in standing position
- Examination of the abdomen for splenomegaly (sickle cell disease); hepatomegaly
- Examination of spine (gibbus, paraspinal spasm, movements) and neurological system like sensation and muscle power

C. Sinus and Fistula

CHAPTER OUTLINE

- Sinus
- Fistula
- Median Mental Sinus
- Sequestrum
- Preauricular Sinus

SINUS

It is a blind track lined by granulation tissue leading from an epithelial surface into the surrounding tissues.

Sinus means ***"hollow"*** or ***"a bay" (Latin)***.



Fig. 1.77: Sinus.

Causes

Congenital: Preauricular sinus.
Acquired: Actinomycosis, tuberculosis, pilonidal sinus, chronic osteomyelitis, median mental sinus.



Fig. 1.78: Typical sinus in the thigh due to osteomyelitis of the greater trochanter.

FISTULA

It is an abnormal communication between the lumen of one viscus to another or the body surface or between the vessels. Fistula means "***flute"*** or ***"a pipe** or **tube***."



Fig. 1.79: Fistula.

Causes

Congenital:

- Branchial fistula.
- Tracheo-oesophageal fistula.
- Congenital AV fistula.
- Umbilical fistula (patent vitello-intestinal duct).

Acquired:

a. Traumatic:
    - Following surgery—intestinal fistulas (biliary, pancreatic, faecal).
    - Following instrumental delivery or difficult labour (vesicovaginal fistula, rectovaginal fistula, ureterovaginal fistula).
b. Inflammatory—intestinal actinomycosis, tuberculosis.
c. Malignancy—when the growth of one organ penetrates into the nearby organ (Rectovesical fistulas as in carcinoma rectum, vesicouterine fistulas as in uterine cancer).

External fistula	***Internal fistula***
Orocutaneous	Tracheo-oesophageal fistula
Branchial fistula	Cholecystoduodenal fistula
Thyroglossal fistula	Colovesical fistula
Enterocutaneous fistula	Rectovesical fistula
Appendicular fistula	



Figs 1.80A and B: Faecal fistula through laparotomy wounds. One is through main wound; other is through drain site. It often occurs after surgery for severe peritonitis, tuberculosis, malignancy.

Clinical Features

- Discharge from the opening of sinus.
- No floor.
- Raised indurated edge, indurated base, nonmobile.
- Often *sprouting granulation tissue over the sinus opening.*
- Bone thickening in osteomyelitis.
- Surrounding skin may be *erythematous* in inflammatory; *bluish* in tuberculosis; *excoriated* in faecal fistula; *pigmented* in chronic sinuses/fistulas.
- Discharge typical of the cause will be evident which will be obvious after *applying pressure* over surrounding area.
- Induration is a feature of all chronic fistulas *except* tuberculosis.



Fig. 1.81: Multiple discharging sinus foot. It is commonly due to mycetoma (Madura foot). It could also be due to tuberculosis, chronic pyogenic osteomyelitis or malignancy.

- *Thickening of the bone underneath* on palpation if sinus is adherent to bone or if there is osteomyelitis.
- Enlargement of *regional lymph nodes* will be evident.
- Sinus may be single or multiple.

Causes of persistence of a sinus or fistula

- A foreign body or necrotic tissue underneath, e.g. suture, sequestrum
- Insufficient or nondependent drainage
- Persistent obstruction in the lumen, e.g. in faecal fistula, biliary fistula (distal obstruction)
- Lack of rest, persistent infection
- Wall become lined with epithelium or endothelium
- Dense fibrosis prevents contraction and healing
- Specific infections: Tuberculosis, actinomycosis
- Presence of malignant disease, post-irradiation

***Note*:**

The most common cause of sinus in neck is tuberculosis. Commonly it is tuberculous lymphadenitis. It shows *yellowish cheesy* discharge with bluish margin. Usually tuberculous sinus/ulcer do not show any induration.



Fig. 1.82: Discharging abdominal faecal fistula showing extensive skin excoriation.



Fig. 1.83: Abdominal faecal fistula in a patient who underwent surgery for acute intestinal obstruction due to tuberculosis.

When a man looses his health he begins to take care of it. **— John Billings**



Figs 1.84A and B: Secondaries in neck causing discharging sinus. (A) and (B) in two different patients.



Fig. 1.85: Mandibular sinus. It is usually due to infected tooth causing osteomyelitis of mandible. It also could be due to tumour, trauma, actinomycosis and radiation. X-ray (orthopantomogram), study of discharge and biopsy are relevant investigations. Such fistula should be excised with extraction of the causative tooth.



Fig. 1.86: Discharging sinus in the neck due to tuberculosis of lymph nodes with a cold abscess underneath.



Fig. 1.87: Sinus opening in the thigh. Note there is no floor.



Fig. 1.88: Pilonidal sinus showing primary and secondary sinus.



Fig. 1.89: Fistula in ano both sides.



Fig. 1.90: Postoperative gastrointestinal fistula. Note the skin excoriation. It can be controlled by using zinc oxide cream local application.

Different discharges in a sinus/fistula

- *Purulent*—bacterial infection
- *Caseous*—tuberculous
- *Sulphur granules*—actinomycosis
- *Mucus*—branchial fistula
- *Saliva*—parotid fistula
- *Faeces*—faecal fistula
- *Bile*—biliary, duodenal fistula
- *Bone*—osteomyelitis sinus
- *Urine*—urinary fistula

Note:

- Streptococcal pus is *watery* with blood stain.
- Staphylococcal pus is *yellow* and creamy.
- Green or *greenish blue* pus is due to *Pseudomonas aeruginosa* infection.
- *Anchovy sauce pus* is seen amoebic liver abscess.
- Gas gangrene produces *sickly sweet odour—decayed apple* like.
- *E. coli* pus is usually *odourless.*
- Anaerobic bacteria and proteus vulgaris cause typical odour due to proteolysis. Bacteroids cause typical *over ripe Camembert cheese* like odour.
- Faecal fistula causes *foul smelling discharge with gas bubble* in it.
- Tuberculous sinus discharges *caseating cheesy* material.

Investigations

a. Fistulogram/sinusogram using ultrafluid lipiodol or water soluble iodine dye (Lipiodol is poppy seed oil containing 40% iodine).
b. Discharge for C/S, AFB, cytology, staining.
c. Biopsy from the edge for tuberculosis and malignancy.
d. Chest X-ray; X-ray of the part; MRI (most reliable) of the part.
e. ESR.
f. CT sinusogram.
g. Probing gently with care.
h. Digital examination of the rectum and proctoscopy in fistula in ano.

Treatment

- Treat the cause.
- ***Excision*** of sinus or fistulas. Always specimen should be sent for histology.
- Antibiotics, antitubercular drugs, rest, adequate drainage.

MEDIAN MENTAL SINUS

It is a chronic infective acquired condition wherein there is infection of roots of one or both lower incisor teeth forming root abscess which eventually tracks down between two halves of lower jaw in the midline presenting as discharging sinus on the point of chin at midline.



Fig. 1.91: Median mental sinus. Note the origin of the sinus from the root/roots of the lower incisor/incisors.



Fig. 1.92: Median mental sinus.

Clinical Features

- Usually painless discharging sinus in the midline on the point of chin.
- Often incisor infection may be revealed (in many patients clinically tooth looks normal even though root is infected invariably).
- It is often mistaken for infected sebaceous cyst.
- Osteomyelitis of the mandible is the possible complication.

Differential Diagnosis

- Infected sebaceous cyst.
- Tuberculous sinus.
- Osteomyelitis.

Investigations

- Dental X-ray is diagnostic (Plain X-ray mandible may not reveal the disease).
- Discharge study—C/S, cytology, AFB.

Be strong enough to face the world each day.
Be weak enough to know you cannot do everything.—**Nabil Mourad**

Treatment

- Antibiotics, after doing discharge study (C/S).
- Lay opening and excision of the sinus track with *extraction of incisor tooth/teeth*.

SEQUESTRUM

- Sequestrum is dead bone *in situ*.
- It can be pyogenic, tubercular (feathery), *Salmonella* (granular), syphilitic (ivory), tubular and ring (in amputation stump).
- It can be *unformed*—means separation between sequestrum and adjacent normal bone has not occurred or *formed*—means there is proper adequate separation between normal bone and sequestrum by forming granulation tissue. Radiologically formed sequestrum shows clear lucent area/zone of demarcation.
- Sequestrum is denser because of the absence of decalcification in the dead bone as there is no blood supply (*dead bone is dense bone*).
- Sequestrum should be *formed* prior to surgical intervention—sequestrectomy and saucerisation.



Figs 1.93 A and B: Diagram and X-ray showing osteomyelitis with sequestrum and sinus. Sequestrum is dead bone *in situ*.



Figs 1.94A to C: Osteomyelitis patient with scar. Also showing on table photo of sequestrectomy and saucerisation.



Figs 1.95A and B: X-ray pictures showing features of osteomyelitis with sequestrum, sinus, cavity.



Fig. 1.96: X-ray of foot showing osteomyelitis of metatarsal bones. Metatarsal osteomyelitis is commonly seen in diabetes mellitus and trauma.

PREAURICULAR SINUS

It is a *congenital entity* occurring due to imperfect fusion of the six tubercles which form ear cartilage. Sinus opening may be seen at the root of the helix or on the tragus. Track is quiet deep running backwards, slightly upwards towards the helix. It usually ends *blindly*. Outer opening of the sinus often closed causing formation of a cystic swelling which contains fluid which is often infected. Preauricular sinus in *no instance* will communicate with the external auditory meatus. Bursting of this swelling leads into formation of ulcer like lesion. It can be unilateral or bilateral. *Occasionally* multiple sinuses are seen. Opening of the sinus occurs in a *small triangular area* in front of the ear at the level of the tragus. *Scarring* is common around the opening due to repeated infection.

Features

- It is seen since childhood.
- Often swelling appears and apparently disappears repeatedly.
- Pain and discharge is common.
- It causes a cosmetic problem in young individual.
- Differential diagnosis is tuberculosis.
- Discharge study, ESR, sinusogram to assess the track is needed. MR sinusogram is beneficial.

Treatment

Excision under general anaesthesia with removal of entire track is essential. If track is not removed properly recurrence will occur.

D. Infectious Diseases

> *But however secure and well-regulated civilized life may become, bacteria, protozoa, viruses, infected fleas, lice, ticks, mosquitoes, and bedbugs will always lurk in the shadows ready to pounce when neglect, poverty, famine, or war lets down the defenses.*
>
> **—Hans Zinsser,** 1934

CHAPTER OUTLINE

- Surgical Infection
- Cellulitis
- Erysipelas
- Lymphangitis
- Abscess
- Bacteraemia
- Septicaemia
- Pyaemia
- Metastatic and Pyaemic Abscess
- Boil
- Hidradenitis Suppurativa
- Carbuncle
- Pott's Puffy Tumour
- Pyogenic Granuloma
- Impetigo
- Scrum Pox
- Tetanus
- Gas Gangrene
- Tuberculosis
- Leprosy
- Syphilis
- Actinomycosis
- Madura Foot
- Rabies
- Anthrax
- Nosocomial and Opportunistic Infections
- HIV Infection and AIDS
- Necrotising Fasciitis
- Acute Pyomyositis
- Surgical Site Infection

SURGICAL INFECTION

- Surgical infection is major problem in surgical practice. Asepsis (prevention of entry of organisms) and antisepsis (killing of the bacteria in the skin or tissues) has made a difference in surgical practice. Epithelial surfaces act as mechanical barrier and phagocytes, antibodies; complements, macrophages, leukocytes, opsonins, etc. act as protective mechanisms.
- Malnutrition, diabetes mellitus, obesity, uraemia, jaundice, malignancy, immunosuppression, radiotherapy, chemotherapy, HIV, ischaemia, foreign body, haematoma are the risk factors for surgical infections. Virulence of organisms, blood supply, body immunity and support of antibiotics are the decisive factors in proper response to control infection.
- Surgical infection can be *superficial surgical site infection* in the wound or *deep surgical site infection* in deeper fasciomuscular layers or *organ space infection* like abdomen/thoracic cavity, etc.
- Health care associated infection occurs after hospital admission in intensive unit/postoperative ward, etc.
- *Southampton wound grading system for healing and infection:*
    - Grade 0 is normal healing;
    - Grade 1 is with bruising/mild erythema;
    - Grade 2 is severe erythema with other features of inflammation at or around wound;
    - Grade 3 is serous or bloody discharge;
    - Grade 4 is presence of pus or deep infection or tissue breakdown or significant haematoma.

ASEPSIS wound score system is used to assess the wound infection.

ASEPSIS wound scoring

Parameters	*Score*
• **A**dditional treatment	
1. Antibiotics	10
2. Pus drainage	05
3. Wound debridement	10
• **S**erous discharge—for 5 days of first 7 days of wound infection	0-5 daily
• **E**rythema—for 5 days of first 7 days of wound infection	0-5 daily
• **P**urulent fluid—for 5 days of first 7 days of wound infection	0-10 daily
• **S**eparation of deep tissues—for 5 days of first 7 days of wound infection	0-10 daily
• **I**solation of bacteria	10
• **S**tay in the hospital (in-patient) more than 14 days due to infection	05

CELLULITIS

- It is ***spreading inflammation*** *of subcutaneous and fascial planes.*
- Infection may follow a small scratch or wound or incision or insect/snake/scorpion bite.

Causative Agents

- Commonly due to *Streptococcus pyogenes* and other Gram +ve organisms. Release of streptokinase and hyaluronidase cause spread of infection.
- Often Gram –ve organisms like *Klebsiella, Pseudomonas, E. coli* are also involved (usually Gram –ve organisms cause secondary infection).
- It can be superficial or deep. More common superficial type is easier to diagnose.
- It is common in diabetics, immunosuppressed people and old age.
- It is common in face, lower limb, upper limb and scrotum.
- Cellulitis occurring in children is never primary but secondary to an underlying bone infection—*Morison's aphorism* (James Morison, 1939—Surgeon, Durham, Newcastle).

Sequelae

- Infection can get localised to form ***pyogenic abscess***.
- Infection can spread to cause ***bacteraemia, septicaemia, pyaemia***.
- Often infection can lead to ***local gangrene.***
- Extensive necrosis of skin and subcutaneous tissue—*necrotizing fasciitis*.

Clinical Features

- Fever, toxicity (tachycardia, hypotension).
- Swelling is diffuse and spreading in nature.
- Pain and tenderness, red, shiny area with stretched warm skin.
- Cellulitis will progress rapidly in diabetic and immunosuppressed individuals.
- Tender regional lymph nodes may be palpable which signify severity of the infection.
- No edge; no pus; no fluctuation; no limit.

Management

- Elevation of limb or part to reduce oedema so as to increase the circulation
- Antibiotics—penicillins, cephalosporins.
- Dressing (often glycerine dressing is used as it reduces the oedema because of its hygroscopic action glycerine magnesium sulphate dressing).
- Bandaging.

Cellulitis in Special Areas

Orbital Cellulitis

Cellulitis in orbit causes *proptosis,* leading to impairment of ocular movements and blindness. It can spread through ophthalmic veins into cavernous sinus causing *cavernous sinus thrombosis.* It requires admission and immediate aggressive treatment with higher generation antibiotics (Penicillins, cephalosporins).



Fig. 1.97: Cellulitis face. Note the oedema of the face and eyelids.



Figs 1.98A and B

*Oedema gives rise to soft pitting, while if pus present, induration can always be felt.***—Allan B Kanavel**



Figs 1.98C to E

Figs 1.98A to E: Note the cellulitis in different patients. It is common in lower limbs. There is no edge without any formed pus. It should never be incised with certain exceptions like Ludwig's angina. It is treated by antibiotics. It can cause bacteraemia/septicaemia.



Fig. 1.99: Severe cellulitis face involving nose, eyelids and facial skin. It can cause septicaemia, cavernous sinus thrombosis or intracranial spread of infection. This area is called as *dangerous zone* in face. It needs hospitalisation for treatment.

Ludwig's Angina

It is cellulitis of upper part of the neck involving submandibular region and floor of the mouth along the fascial planes It may be precipitated by tooth extraction, oral cancer, submandibular gland infection, diabetes mellitus, chemotherapy, etc.



Fig. 1.100: Dangerous area of face—area of upper lip and lower part of nose. Infection from this area spreads through deep facial vein → pterygoid plexus → communicating vein → cavernous sinus causing its life-threatening thrombosis.

Clinical Features

- Diffuse swelling, redness, tenderness and induration in the floor of the mouth and submandibular region.
- Difficulty in opening of the mouth (***Trismus***).
- Toxic features like fever, tachycardia and tachypnoea.
- ***Severe laryngeal oedema*** (presents with respiratory distress, stridor and cyanosis).
- Dysphagia and *putrid halitosis*.

Complications

- ***Septicaemia.***
- Spread of infection into the parapharyngeal space leads to ***thrombosis*** of internal jugular vein which may extend above into the sigmoid sinus which may be fatal.

Treatment

- Antibiotics—intravenous.
- Early surgical intervention (decompression) is required. Under GA, horizontal incision is placed in submandibular region extending on both sides, deepened to include deep fascia. ***Mylohyoid*** muscles on both sides are cut. It releases the tension, preventing laryngeal oedema and so further spread of infection is prevented. Antibiotics should be continued.
- Incised wound is closed by ***secondary suturing*** once infection is controlled completely (not earlier).

ERYSIPELAS

It is a **spreading inflammation** of the skin and subcutaneous tissues due to infection caused by *Streptococcus pyogenes*. There will be always cutaneous lymphangitis with development of ***rose pink rash*** with cutaneous lymphatic oedema. Vesicles which form eventually will rupture to cause serous discharge.

Sites

- *Orbit, face and ear lobule*—most common.
- Hands and scrotum.
- Umbilicus in infants.
- Decubitus ulcer of lower limb occasionally.

Clinical Features

- ***Toxaemia*** is always a feature.
- ***Rash*** is fast spreading and blanches on pressure.
- ***Rash*** *is raised with sharp margin.*
- Redness becomes brown and later yellow with vesicles.
- ***Discharge*** *is serous (In cellulitis discharge is purulent).*
- In the face and orbit it causes severe oedema.
- ***Milian's ear sign*** is a clinical sign used to differentiate erysipelas from cellulitis wherein ear lobule is spared. Skin of ear lobule is adherent to the subcutaneus tissue and so cellulitis cannot occur. Erysipelas being a cutaneous condition can spread into the ear lobule (Gaston Milian—dermatologist Paris, 1945).
- Disease is common in poorly hygienic debilitated individuals.
- Septicaemia, localised cutaneous and subcutaneous gangrene are the dangerous problems.
- Lymphoedema of face and eyelids can occur later due to lymphatic fibrosis.

Treatment is with ***penicillins.***

ERYSIPELOID DISEASE

- Also called as *'Fish handler's disease.*
- Occurs following any cuts or scratches.
- It has features of both erysipelas and cellulitis.
- It is self-limiting with relatively mild symptoms.

LYMPHANGITIS

- It is an acute *nonsuppurative* infection and *spreading* inflammation of lymphatics of skin and subcutaneous tissues due to *beta haemolytic streptococci*, staphylococci, clostridial organisms. It is commonly associated with cellulitis. Erysipelas is a type of lymphangitis.
- In endemic areas, filariasis is the most common cause (coastal India). It is caused by *Wuchereria bancrofti*. It is transmitted through bites of Culex mosquito. Microfilaria reaches the lymph node forming adult worm which blocks the lymph node causing obstruction, fibrosis and lymphangitis.
- Usually infection occurs following a small trauma in bacterial cause. Rapidly fever and redness at the area develops.

Features

- Streaky redness which is spreading is typical. On pressure area *blanches*; on release redness *reappears*.
- Oedema of the part, palpable tender *regional lymph nodes* are obvious.
- Fever, tachycardia, features of toxaemia.
- Groin lymph nodes are enlarged and tender in *lower limb* lymphangitis. In *upper limb,* as lymphatics are mainly located on the dorsum of hand, oedema and redness develops on the dorsum. Infection in thumb and index finger causes palpable tender axillary nodes; in little and ring finger causes first tender palpable epitrochlear nodes to appear; infection in middle finger causes first deltopectoral nodes to enlarge.
- Regional lymph nodes (only) may eventually suppurate to form an *abscess*.
- *Toxaemia, septicaemia* may occur. Rapidity may be more in diabetics and immunosuppressed.
- *Chronic lymphangitis* occurs due to repeated attacks of acute recurrent lymphangitis leading into acquired *lymphoedema*.

Management

- Antibiotics like penicillin, cloxacillin.
- Elevation, rest, glycerine magnesium sulpha dressing.
- Management of toxaemia or septicaemia with critical care.



Figs 1.101A and B



Figs 1.101C

Figs 1.101 A to C: (A) Lymphangitis of lower limb showing redness. (B1) Lymphangitis of upper limb; (B2) Blanching is seen immediately after pressure; (C) Typical red streaks in an upper limb lymphangitis.



Fig. 1.102: Lymphangitis of one leg. Note the typical streaky redness compare to normal side.

ABSCESS

> *If you examine a swelling of pus in any limb of a man and you find it (with) its head raised and it is enclosed and it is rounded, you shall say concerning it: "a swelling of pus, an illness which will be treated by me with the knife treatment. There is something in it like mucus. Something comes forth like wax. It makes a pocket. If anything (remains) in its pocket, it recurs."*
>
> —**(Anonymous),** circa 1500 BC

Types

- Pyogenic abscess
- Pyaemic abscess
- Metastatic abscess
- Cold abscess due to chronic infection like tuberculosis

Pyogenic Abscess

It is a ***localised collection*** of pus in a cavity lined by granulation tissue, covered by pyogenic membrane. It contains pus in loculi. Pus contains dead WBC's, multiplying bacteria, toxins and necrotic material.

- Protein exudation causes fibrin deposition and formation of pyogenic membrane.
- Macrophages and polymorphs release lysosomal enzymes which cause liquefaction of tissues leading into pus formation.
- Toxins and enzymes released causes tissue destruction and pus formation.



Fig. 1.103: Pyogenic abscess—parts.

Mode of Infection

- Direct
- Haematogenous
- Lymphatics
- Extension from adjacent tissues

Bacteria Causing Abscess

- *Staphylococcus aureus.*
- *Streptococcus pyogenes.*
- Gram-negative bacteria (*E. coli*, *Pseudomonas, Klebsiella*).
- Anaerobes.



Fig. 1.104: Abscess forehead. Patient is diabetic and has had trauma to the site.



Fig. 1.105: Abscess in the face. Note the localisation and redness.



Fig. 1.106: Abscess in the nape of the neck—suboccipital region. Note the redness and visible pus.

Factors precipitating abscess formation

- General condition of the patient: Nutrition, anaemia, age of the patient
- Associated diseases: Diabetes, HIV, immunosuppression
- Type and virulence of the organisms
- Trauma, haematoma, road traffic accidents

Clinical Features

- Fever often with chills and rigors.
- Localised swelling which is smooth, soft and fluctuant.
- Visible (pointing) pus.
- Throbbing pain and pointing tenderness.
- Brawny induration around.
- Redness and warmth with restricted movement around a joint.
- *Rubor* (redness); *dolor* (pain); *calor* (warmness); *tumour* (swelling) and *functiolaesa* (loss of localised and adjacent tissue/joint function) are quiet obvious.

(Commonly cellulitis occurs first which eventually gets localised to form an abscess.)



Fig. 1.107A



Figs 1.107B and C

Figs 1.107A to C: Pyogenic abscess in different locations in chest wall; in plantar aspect of the foot and in the thigh. Note the redness and visible pus.

Visible (pointing) pus, tenderness, fluctuation are the features of formed abscess.

Cellulitis	*Pyogenic abscess*
Diffused—no edge	Well-localised with clear edge
Pus not formed—non-suppurative initially	Formed pus
Not fluctuant	Fluctuant
Spreading—SIRS can occur	
Blood culture may be negative	Culture of pus is usually positive
Never incise; if done danger of bacteraemia, antibiotics, elevation, dressing—are treatment	Drainage is essential

Sites of Abscess

a. *External Sites*

- Fingers and hand.
- Neck.
- Axilla.
- Breast.
- Foot, thigh—here it is deeply situated with brawny induration.
- Ischiorectal and perianal region.
- Abdominal wall.
- Dental abscess, tonsillar abscess and other abscesses in the oral cavity.

Happy is he who has no serious consequences of his erroneous diagnosis to regret.—**Fredrick H Marsh**



Fig. 1.108: Perineal abscess.

b. *Internal Abscess*

- Abdominal: Subphrenic, pelvic, paracolic, amoebic liver abscess, pyogenic abscess of liver, splenic abscess, pancreatic abscess.
- Perinephric abscess.
- Retroperitoneal abscess.
- Lung abscess.
- Brain abscess.
- Retropharyngeal abscess.

Investigations

- Total count is increased.
- Urine sugar and blood sugar is done to rule out diabetes.
- USG of the part or abdomen or other region is done when required.
- Chest X-ray in case of lung abscess.
- Gallium isotope scan is *very useful*.
- CT scan or MRI is done in cases of brain and thoracic abscess.
- Investigations, relevant to specific types: Liver function tests, PO_2 and PCO_2 estimation, blood culture.



Fig. 1.109: Abscess in plantar aspect of foot. Note the visible pus.

Complications of an Abscess

- Bacteraemia, septicaemia, and pyaemia.
- Multiple abscess formation.
- Metastatic abscess.
- Destruction of tissues.
- *Antibioma formation* (common in breast abscess). Once abscess forms, thick fibrous tissue develops around abscess cavity because of antibiotics. Cavity contains sterile pus as thick flaques. It is nontender, localised, smooth, hard swelling which may mimic carcinoma (in breast—carcinoma breast). It should be differentiated clinically from carcinoma (it is not progressive whereas carcinoma is progressively increasing). FNAC is essential to differentiate. Antibioma should be excised.
- Sinus and fistula formation.
- Large abscess may erode into adjacent vessels and can cause life-threatening torrential haemorrhage, e.g. as in pancreatic abscess.
- Abscess in head and neck region can cause laryngeal oedema, stridor and dysphagia.
- Specific complications of internal abscess:
  - Brain abscess can cause intracranial hypertension, epilepsy, neurological deficit.
  - Liver abscess can cause hepatic failure, rupture, jaundice.
  - Lung abscess can lead to bronchopleural fistula or septicaemia or respiratory failure or ARDS.



Fig. 1.110: Abdominal wall abscess being aspirated. Note the aspirated pus in the syringe. Abscess should be aspirated prior to drainage.



Fig. 1.111: Multiple abscesses in neck, chin, face. It is common in HIV, diabetes and immunosuppressed.

Treatment of an abscess

Abscess should be formed before draining. Exceptions for this rule are:

- Parotid abscess
- Breast abscess
- Axillary abscess
- Thigh abscess
- Ischiorectal abscess

Features of a formed abscess

- Visible pus
- Pointing tenderness
- Fluctuation
- Excruciating pain

Note:
Pus anywhere will come to surface; pus anywhere should be drained.



Fig. 1.112: Scrotal abscess, which is well-localised and ready for drainage. Patient has undergone surgery for hernia earlier.

Procedure

Hilton's *method* of draining an abscess.

- Initially broad spectrum antibiotics are started (depending on severity, extent and site of the abscess).
- Under general anaesthesia or regional block anaesthesia,* after cleaning and draping, abscess is aspirated and presence of pus is confirmed.
- Skin is incised *adequately*, in the line parallel to the neurovascular bundle in the most dependent position.
- Next, pyogenic membrane is opened using ***Sinus forceps***** and all loculi are broken up. Abscess cavity is cleared of pus and washed with saline.
- A **drain** (either gauze drain or corrugated rubber drain) is placed.
- Wound is ***not closed***. Wound is allowed to granulate and heal. Sometimes *secondary suturing* or *skin grafting* is required.
- Pus is sent for ***culture and sensitivity***.
- Biopsy should be done in suspected tuberculosis or malignancy.
- Antibiotics are continued.
- Treating the ***cause*** is important.

Counter-incision is placed in breast abscess which is placed in upper quadrant.

Incision should be deeper while draining pus in radial and ulnar bursae, palmar spaces and tenosynovitis.

Problems in drainage

- Improper drainage
- Bleeding
- Residual abscess or sinus formation



Figs 1.113A and B

---

* As the pus is acidic local anaesthetic agent will not act and hence it is not used.

** Sinus forceps do not have lock and has got serrations in the tip. It is called as sinus forceps because it was initially designed and used to pack sinuses.

Joseph Lister is father of modern surgery and started antiseptic surgery in 1912.



Figs 1.113C to F

Figs 1.113 A to F: Technique of incision and drainage of a pyogenic abscess. Abscess should be aspirated first to get pus; No. 11 blade is used to incise; using sinus forceps pyogenic membrane is opened; pus is collected for culture; loculi are broken using sinus forceps and little finger; cavity is irrigated with *normal saline (ideal)* and povidone iodine; cavity is packed with roller gauze; wound is not sutured.

Differential Diagnosis

- ***Aneurysm:*** Especially in popliteal, femoral and axillary regions. So before draining the abscess, presence of pus is confirmed by aspirating with a needle. It should be remembered that thrombosed aneurysm may not be pulsatile but can be warm, soft and tender.
- ***Soft tissue tumours:*** Sarcomas may be smooth, soft and warmer.
- Haematoma.



Fig. 1.114: Incision for draining an abscess by Hilton's method. Note the longitudinal incision.



Fig. 1.115: Abscess with loculi and breaking of loculi using finger for drainage.



Fig. 1.116: Typical cold abscess and tuberculous sinus in the neck. It does not show signs of acute inflammation. It should be drained (under cover of antituberculous drugs) through *nondependent incision* and incision should be closed without placing a drain.

Differences between pyogenic abscess and cold abscess

Pyogenic abscess	*Cold abscess*
a. Red, warm, tender, with signs of acute inflammation	a. No signs of acute inflammation
b. Pyogenic bacteria are nonspecific organisms (*Streptococcus, Staphylococcus*)	b. Tuberculous bacteria
c. For drainage, dependent incision is used	c. Nondependent incision is used
d. Suturing of the wound is not done	d. Wound is sutured
e. Drain is placed	e. Drain is not placed (otherwise sinus will form which is difficult to treat)

BACTERAEMIA

Presence of bacteria in blood.

SEPTICAEMIA

Presence of overwhelming and multiplying bacteria in blood with toxins causing SIRS (Systemic inflammatory response syndrome) or MODS (Multiorgan dysfunction syndrome).

Types

a. ***Gram +ve septicaemia*** is due to staphylococci, streptococci, pneumococci, etc. It is common in children, old age, diabetics and after splenectomy. After splenectomy, overwhelming post-splenectomy sepsis (OPSI) is not uncommon. Common origin is skin, respiratory infection.
b. ***Gram –ve septicaemia*** is common in acute abdomen like peritonitis, abscess, urinary infections, biliary infections, postoperative sepsis. It is commonly seen in malnutrition, old age, diabetics, immunosuppressed people. Common bacteria are *E. coli, Klebsiella, Pseudomonas, Proteus.* Condition is also called endotoxic shock. Common focus of Gram-negative sepsis are urinary infection, abscess or infected wounds, biliary sepsis, postoperative wounds.

Stages of Gram-negative Septicaemia

a. ***Warm stage*** is *reversible stage*. Here existing fever is due to pyrogenic response. Patient is toxic with fever, chills and rigors.
b. ***Cold stage*** is *irreversible stage*. Here fever is not present due to absence of pyrogenic response. Patient is having renal failure, ARDS, liver failure and multiorgan failure.

Investigations

- Urine/pus/discharge culture.
- Blood culture.
- Haematocrit.
- Electrolyte assessment.
- PO_2 and PCO_2 analysis.
- Blood urea, serum creatinine, liver function tests.

Treatment

- Antibiotics like cefoperazone, ceftazidime, cefotaxime, amikacin, tobramycin, metronidazole.
- Fresh blood transfusion.
- Adequate hydration.
- Oxygen supplementation.
- Ventilatory support.
- Electrolyte management.
- Parenteral nutrition (TPN).
- CVP line for monitoring and perfusion.
- FFP or platelets in case of DIC.

Complications of septicaemia

- Disseminated intravascular coagulation (DIC)
- ARDS
- Liver dysfunction
- Renal failure
- Bone marrow suppression—thrombocytopaenia
- Multiorgan failure

PYAEMIA

Presence of multiplying bacteria in blood as emboli which spread and lodge in different organs in the body like liver, lungs, kidneys, spleen, brain causing ***pyaemic abscess.*** This may lead to ***multiorgan dysfunction syndrome (MODS***). It may endanger life if not treated properly.

Clinical features

- Fever with chills and rigors
- Jaundice, oliguria, drowsiness
- Hypotension, peripheral circulatory collapse and later coma with MODS

Common Causes

- Urinary infection *(most common)*.
- Biliary tract infection.
- Lower respiratory tract infection.
- Abdominal sepsis of any cause.
- Sepsis in diabetics and immunosuppressed individuals like HIV, steroid therapy.

> *In tuberculus arthritis, starting pain at night is very important, as it attracts more attention than occasional discomfort during the day.*
> **— Royal Whitmann**

Investigations

- Total leucocyte count.
- Pus culture.
- Blood culture.
- Urine culture.
- Blood urea and serum creatinine.
- LFT.

Treatment

- Monitoring of vital parameters.
- Antibiotics (ceftazidime, cefoperazone, ceftriaxone sodium).
- IV fluids, maintenance of urine output.
- Hydrocortisone.
- Blood and plasma transfusion.
- Nasal oxygen, ventilator support, monitoring of pulmonary function.

METASTATIC AND PYAEMIC ABSCESS

Metastatic abscess

- It is an abscess which occurs as a spread from other abscess. For example, lung abscess causing metastatic abscess in the brain (common example).
- Presentation here is of features of focus abscess and of metastatic abscess (localised features).

Pyaemic abscess

- It is from any infective focus which need not be always from an abscess (from cellulitis or skin infections, etc.) causing pyaemic emboli leading into multiple abscess in different places like brain, kidneys, liver, etc.
- Presentation here, is mainly of systemic features involving multiple organs with toxicity.
- These emboli contain bulk of multiplying organisms often derived from infective thrombus or vegetations. Focus may be an abscess, cellulitis, skin infection, acute osteomyelitis, and acute bacterial endocarditis. Acute appendicitis with severe sepsis can cause infective pyaemia in liver called as *pyelphlebitis or portal pyaemia*.
- Pyaemic abscess are multiple, deeper, beneath the fascia or in the internal organs. When it is on the surface, it is less tender without any clear signs of inflammation.
- **Management:** Evaluation for focus of infection, pus for culture, blood culture (three samples), antibiotics, critical care, systemic therapy, drainage of surface abscesses.
- Pyaemic abscess carries high mortality with SIRS and MODS.

BOIL (Furuncle)

It is an acute staphylococcal infection of a hair follicle with perifolliculitis which usually proceeds to suppuration and central necrosis.

- Often boil opens on its own and subsides (*S. aureus* infection).
- Furuncle in external auditary canal is very painful because of rich cutaneous nerves. Here skin is adherent to perichondrium.
- Boil often heals spontaneously; suppuration will not occur in such boil; it is often called as *blind healed dull boil.*
- Boil is *common* over back, neck, thigh, and forearm even though it can occur anywhere. Boil in eyelash follicle is called as *stye*. Boil can occur in perianal region which can lead into abscess and fistula. Boil can lead into *hidradenitis, common in axilla and pubic region*. Boil can cause *cellulitis* of local area. Overlying skin undergoes necrosis. But during healing re-epithelialisation occurs.
- Boil commonly *subsides* spontaneously often with the support of suitable antibiotics; occasionally it requires incision and drainage. Regional enlarged tender lymph nodes may be palpable due to secondary infection.
- Systemic features are *not common* unless it is multiple/recurrent/severe or in diabetics and immunosuppressed.
- Multiple/recurrent boils are *common* in diabetics.



Fig. 1.117: Furuncle/boil are infection of hair follicle with perifolliculitis due to *Staphylococcus aureus.*

Treatment

- Antibiotics given if boil is not resolving spontaneously—*cloxacillin*/amoxycillin.
- Rarely drainage of boil is needed in severe persistent form.

Complications

- Cellulitis.
- Lymphadenitis.
- Hidradenitis (*Infection of group of hair follicles*).
- Boil in dangerous zone can cause cavernous sinus thrombosis.

HIDRADENITIS SUPPURATIVA

It is a chronic infective and fibrous disease of the skin bearing *apocrine* sweat glands. Apocrine sweat glands are coiled glands which open into the hair follicles.

Sites of apocrine sweat glands

- Axilla
- Groin
- Areola
- Umbilicus
- Scalp, chest
- Perineum

Aetiology

- Obesity, smoking.
- Poor hygiene.



Figs 1.118A and B: Hidradenitis suppurativa. It is chronic infection of apocrine sweat glands of the skin. It is common in axilla (*Courtesy*: Dr Achaleshwar Dayal, MS, Itarsi, MP).

- Diabetes mellitus.
- Steroids.

Common bacteria involved are staphylococci, streptococci, *Staphylococcus aureus*, *Propionibacterium acnes*.

Pathogenesis

Obstruction of duct of apocrine sweat gland by keratin
↓
Dilatation of the duct of gland
↓
Infection and abscess formation
↓
Involvement of subcutaneous tissue and adjacent apocrine glands
↓
Fibrosis, scarring, sinus formation
↓
Spread to surrounding tissues

Clinical Features

- Common in females 4 : 1.
- The most common site is axilla. Often it is bilateral.
- Multiple discharging sinuses, with nodules in the skin which is tender.
- Induration due to fibrosis.

Investigation

- Discharge study—culture/sensitivity and AFB.
- Biopsy to rule out tuberculosis or malignancy.

Differential Diagnosis

- Tuberculous sinus.
- Malignancy (squamous cell carcinoma of skin).
- Lymph node mass in the region which are in *deeper plane*.

Treatment

- Antibiotics—cephalosporins, long acting penicillin.
- Excision of the involved area widely followed by skin grafting or flaps.
- Excision of the involved area widely followed by skin grafting or flaps (radical wound excision).
- Antiandrogen drugs.

CARBUNCLE

Word meaning of carbuncle is ***charcoal.***

- It is *an infective gangrene of skin and subcutaneous tissue*.
- ***Staphylococcus aureus*** is the main culprit.
- Common site of occurrence is ***nape of the neck and back.*** *Skin* in this area is thick. Condition also can occur in shoulder, cheek, hand, forearm.
- It is common in ***diabetics*** and after forty years of age**.**
- It is common in males.

Infection
↓
Development of small vesicles
↓
Sieve like pattern
↓
Red indurated skin with discharging pus
↓
Many fuse together to form a central necrotic ulcer (*ash-grey slough*) with peripheral fresh vesicle looking like a "***rosette***" (cribriform)
↓
Skin becomes black due to blockage of cutaneous vessels
↓
Disease spreads to adjacent skin rapidly

Patient is ***toxic*** and in diabetics they are ***ketotic***

Investigations

- Urine sugar and urine ketone bodies.
- Blood sugar.
- Discharge for C/S.

> *An external sore may be obvious on external genitalia—hot and tender in gonorrhea and chancroid, painless and indolent in syphilis.*
> **— Angus E.W. McLachlam**



Fig. 1.119: Carbuncle in the buttock. Note the vesicles and typical colour.



Fig. 1.120: Carbuncle in the nape of the neck—typical site. Note the wide area of involvement and dark area—charcoal like. *Ash-grey slough* is specific.

Treatment

- Control of diabetes is essential using insulin.
- Antibiotics like penicillins, cephalosporins or depending on C/S is given.
- Drainage is done by a cruciate incision and debridement of all dead tissues is done. Excision is done later.
- Once wound granulates well, ***skin grafting*** may be required.

Renal Carbuncle is an entity which occurs in kidney due to infection, forming localized infective mass lesion.

POTT'S PUFFY TUMOUR

- It is a misnomer. It is not a tumour.
- It is formation of diffuse external swelling in the scalp due to **subperiosteal pus** formation and **scalp oedema**.
- It originates commonly in frontal region and may extend into other regions.
- Often there is acute osteomyelitis of frontal bone.



Fig. 1.121: Pott's Puffy tumour. Note the swelling over the frontal region and eyelid.

Causes

- Chronic frontal sinusitis which eventually suppurates and extends into subperiosteal region.
- Trauma—subperiosteal haematoma.
- Chronic suppurative otitis media.

Clinical Features

- Pain and boggy swelling in frontal region which is warm, tender.
- Toxicity and drowsiness.
- Pitting scalp oedema is typical.

Complications

- *Osteomyelitis* of frontal bone.
- Spread of infection into intracranial cavity leads to *intracranial abscess* (Extradural or subdural abscess) (*dumb-bell* abscess). So may present with features of raised intracranial tension like headache, coning and convulsions.

Investigations

- Total leucocyte count—increased. ESR—raised.
- X-ray skull. CT scan.

Differential Diagnosis

Secondaries in the skull or brain.

Treatment

- Antibiotics and drainage under general anaesthesia before it spreads into cranial cavity.
- Once it extends into cranial cavity, it is treated accordingly by formal neurosurgical decompression (often using ***Dandy's brain cannula***).
- Osteomyelitis of skull bones requires radical removal with reconstruction of skull defect.

PYOGENIC GRANULOMA (GRANULOMA PYOGENICUM)

- It is a common condition which occurs on the face, scalp, fingers and toes.
- It may be due to minor trauma or minor infection.
- Infection leads to formation of unhealthy granulation tissue which protrudes through the wound.
  It is also called as acquired lobular capillary haemangioma.

Clinical Features

- Usually single, well localised, red, firm, nodule, which bleeds on touch.
- May or may not be tender.

Sites

- Face
- Scalp
- Fingers
- Toes

Differential Diagnosis

- Haemangioma.
- Papilloma.
- Skin adnexal tumours.
- In recurrent cases, haemangioendothelioma and melanoma.



Figs 1.122A and B: Pyogenic granuloma finger.

Treatment

- Excision, laser surgery.
- Tissue to be sent for histopathological study.

IMPETIGO

- It is highly infectious superficial skin infection caused by staphylococci/streptococci organisms.
- Usually seen in children, with formation of multiple blisters that rupture and coalesce, to cover as *honey-coloured* crust.
- Treatment is oral antibiotics and topical antiseptics.

SCRUM POX

It is a type of impetigo seen in Rugby players (Staphylococcal infection).



Figs 1.123A to C: Pyogenic granuloma (A) adjacent to nose; (B) in the—scalp post-auricular region and (C) lower lip.

TETANUS

> *It is painful for him to open his mouth. His heart beats too slowly (or weakly) for speech. You observe his saliva falling from his lips, but not falling completely.... He suffers stiffness in his neck. He does not find he can look at his two shoulders and his breast.*
>
> **—(Anonymous),** Circa 1500 BC

It is an infective condition caused by *Clostridium tetani* organisms leading to reflex muscle spasm, often associated with tonic clonic convulsions.

Predisposing Factors for Tetanus

- Absence of prior tetanus toxoid immunisation.
- Trauma with lacerations, deep wounds, crush devitalised wounds, presence of foreign body, wounds with anaerobic environment in the tissues.
- Chronic suppurative otitis media with perforation, caries teeth.
- Improper sterilisation in the ward, labour (septic abortion) and operation theatre.
- Tattooing, rusted nails (there is a myth that only rusted instrument will cause tetanus; this is not true), ear lobe prick, colloquial perianal therapies,

Note:
Tetanus is *not communicable* from person to person.

Even if you're on the right track, you'll get runover if you just sit there. **— Arthur Godfrey**

Organism

- ***Clostridium tetani*** is a *Gram-positive, anaerobic, motile, noncapsulated,* organism with *peritrichous flagella*, and ***terminal spores*** *(Drum stick appearance*).
- Spore is the infective agent. They are found in soil, manure, dust.
- Spore can gain entry through any wound, pricks, injuries resulting from road traffic accidents, penetrating injuries.

Toxins

- Exotoxins released by *Clostridium tetani* are *tetanospasmin* and *tetanolysin* (Exotoxin is the one which is released from bacteria without their destruction/death. *Endotoxin* is the one which is released with death of the bacteria). Tetanus bacteria release only exotoxins.
- Tetanospasmin, the *common exotoxin* released by the multiplying bacteria once spore germinates travels along the *perineural* sheath, *lymphatics* along the nerve, and through blood to cause various effects.

Pathogenesis


Spore
Enters the wound
It germinates in anaerobic media releasing bacteria, which multiply
Release of ***Exotoxins***
Tetanospasmin
Tetanolysin
Through lymphatics
Through the perineural sheath
Circulation
Haemolysis
Enters the central nervous system
Blocks cholinesterase enzymes at anterior horn cells
Toxaemia (through blood)
Blocks the NMJ (neuro-muscular junction)
by acting on cholinesterase enzyme
Causing hyperexcitability and reflex spasm of muscles
often with ***tonic, clonic convulsions***
Aggravates the muscle spasm
Once toxin is fixed in nerve tissue,
it can no longer be neutralised by antitoxin

Clinical Features

Symptoms

- *Trismus* is the most common symptom
- Jaw stiffness, pain and stiffness in the neck and back muscles
- Anxiousness, sweating
- Headache, delirium, sleeplessness
- Dysphagia
- Dyspnoea

Signs

- ***Trismus,*** due to spasm of masseter and pterygoids.
- ***Risus sardonicus*** (smiling facies), due to spasm of the facial muscle—zygomaticus major. Looks as if patient is smiling.
- Neck rigidity.
- Spasm and rigidity of all muscles.
- Hyperreflexia.
- Respiratory changes—due to laryngeal muscle spasm, infection, aspiration.
- ***Tonic clonic convulsions.***
- Abdominal wall rigidity often with haematoma formation.
- Severe convulsion may often lead to fractures, joint dislocations and tendon ruptures.
- Fever and tachycardia.
- Retention of urine (due to spasm of urinary sphincter), constipation (due to rectal spasm).
- Rarely features of ***carditis*** are seen due to involvement of the cardiac muscle, which is dangerous, as it often leads to cardiac arrest and death. Here ***steroids*** are very useful. It presents with refractory *bradycardia.*
- Symptoms will be aggravated by stimuli like light, noise.

Incubation Period

- Time between the ***entry of spore and appearance of first symptom***.
- Usually 7-10 days.
- Shorter the incubation period worser the prognosis and more severe the course of disease. If it is less than 3 days it is commonly fatal.

Period of Onset

- *Time between appearence of first symptom and appearance of first sign.*
- Shorter the period of onset worser the prognosis and vice versa. If it is less than 2 days it is commonly fatal.

Effects on Respiratory System

Diaphragm and other muscles of respiration undergo spasm causing tachypnoea, respiratory distress, respiratory infections, aspiration, cyanosis, respiratory failure with altered PO_2 and PCO_2 levels.

Types of Tetanus

- ***Early tetanus*****:** It is a severe form with a short incubation period and poor prognosis.
- ***Latent tetanus*****:** Wound is healed and forgotten. After a long incubation period, may be years later, under favourable environment, spores release bacteria and cause tetanus. It carries better prognosis. Latent tetanus is often called as *delayed tetanus*.
- ***Late tetanus*****:** Disease develops many months after injury.
- ***Ascending tetanus:*** Symptoms and signs progress from below upwards.
- ***Descending tetanus*****:** Symptoms and signs progress from above downwards.
- ***Cephalic tetanus:*** Facial muscles are involved first (3rd, 4th, 6th and 7th cranial nerves can get involved). Facial nerve is commonly involved in this type. Oculomotor nerve—3rd nerve (*ophthalmoplegia*), hypoglossal nerve—12th nerve (*spasm of tongue*) are other cranial nerves involved.
- ***Localised tetanus.*** Here muscles adjacent to the wound or muscles of one segment or one area develop spasm. It is due

to less virulent toxin or released toxins are of less concentration or only one or few segments of anterior horn cells of the spinal cord are affected.

- ***Bulbar tetanus*:** When muscles of deglutition and respiration are involved. Highly fatal.
- ***Tetanus neonatorum*** (7th day tetanus): Tetanus occurring in neonates. Spread is through umbilical cord. It carries very high, nearly 100% mortality.
- ***Urban tetanus***. Due to repeated injections in IV drug abusers.
- ***Postoperative tetanus*** due to improper sterilisation.
- Even though it is classified as *acute tetanus* (tetanus develops within 10 days) or *chronic tetanus* (tetanus develops from 10 days to 3 months) it is only of outcome value as therapy will be same in both. *Post-abortion or puerperal tetanus* develops due to practice of improper sterilisation during abortion or delivery. If patient is not given tetanus toxoid during the first attack, he can develop second attack of tetanus at a later period called as *recurrent tetanus* as patient who had once tetanus is not immune for development of second attack of tetanus. In children and adolescents chronic suppurative otitis media (CSOM) with perforation of tympanic membrane can cause tetanus—*otitis tetanus.*

Different Postures in Tetanus



Fig. 1.124: Different types of postures seen in tetanus.

- ***Opisthotonus**:* Posterior muscles are acting more, so *backward bending.*
- ***Orthotonus***: *Straight posture*. Both front and back muscles are acting equally.
- ***Emprosthotonus:*** *Forward bending* as front muscles are acting more.
- ***Pleurosthotonus***: *Lateral bending* as lateral muscles act more.

Complications of tetanus

- Fracture bones
- Haematoma
- Aspiration pneumonia, respiratory failure, ARDS
- Carditis, arrhythmias—life-threatening
- DVT, pulmonary embolism
- Toxaemia
- Secondary infection—septicaemia
- Bedsore. Malnutrition, stress gastric ulcers
- Mortality used to be very high in earlier days up to or more than 50%. It is reduced to 15-20% at present; but it is still higher in children and elderly
- Repeated uncontrollable convulsions can lead into coma and death.

Staging of Tetanus

- ***Mildly ill**:* Rigidity, spasm, trismus and different postures.
- ***Seriously ill***: Spasm, rigidity, severe respiratory infections, dysphagia.
- ***Dangerously ill**:* Cyanosis with ***respiratory failure*** and tonic-clonic convulsions, cyanosis.

Differential Diagnosis

- Strychnine poisoning (here patient is normal in between).
- Trismus due to other causes like—dental, oral, tonsillar sepsis, oral malignancy, temporomandibular joint dysfunction.
- Meningitis.
- *Hydrophobia.*
- Convulsive disorders.

Culture media for *Clostridium tetani* are RCM (Robertson's cooked meat) media and nutrient agar.

Cause of death in tetanus

- Respiratory failure with aspiration pneumonia and ARDS
- Severe carditis—an ominous sign
- Mortality is 45-50%—becoming less now in will equipped centers (15%)

Treatment

- Patient is admitted and isolated in a dark, quiet room.
- Antitetanus globulin (ATG), 3,000 units IM single dose is given. Test dose is not required (It is a human Ig). It is 100 times more effective than ATS. Anaphylaxis is not observed. Once toxin is *fixed to nerve* tissue it *cannot* be neutralised; but *circulating toxins* are *very well* neutralised.
- Antitetanus serum (ATS): When ATG is not available or when patient cannot afford, after ***IV test dose*** (1,000 units of ATS), full dose is given, i.e. 1,00,000 units, half of it is given IM and half of it is given IV. It is a horse serum, so possibility of anaphylactic reactions should be borne in mind.
- Wound debridement, drainage of pus, injection of ATG 250-500 units locally to reduce the toxin effect.
- Ryle's tube has to be passed, initially to decompress, so as to prevent aspiration, but later for feeding purpose.
- Catheterisation.
- IV fluids and electrolyte balance has to be maintained. TPN is also required.

- ***Tetanus toxoid*** should be given as disease will not give immunity against further infections. To start—first dose, second dose after one month, third dose after six months. *Aluminium phosphate adsorbed tetanus toxoid* 0.5 ml is injected into the deltoid muscle (IM). Booster dose should be given every 4 years or after any significant trauma. In patients who have not been immunised earlier, it needs 30 days to develop antibody after tetanus toxoid injection.
- IV *diazepam* 20 mg 4th or 6th hourly. Dose is adjusted depending on severity and convulsions.
- IV *phenobarbitone* 30 mg 6th hourly.
- IV *chlorpromazine* 25 mg 6th hourly.
- Injection crystalline penicillin 20 lacs 6th hourly and injection. gentamicin and metronidazole to prevent secondary infection.
- Regular suction and clearance of respiratory tract.
- Nasal oxygen.
- In ***severe cases***, patient is ***curarised*** and placed in ***ventilator (IPPR).***
- ***Endotracheal intubation*** or ***tracheostomy*** are often ***life-saving procedures.***
- ***Good nursing care***—Change of position, prevention of bedsores, prevention of DVT (which is common in tetanus and often requires heparin injection).
- Chest (respiratory) physiotherapy during recovery period.
- ***Steroids*** are given when carditis is suspected.
- *Cardiac pacemaker* may be useful in refractory bradycardia and arrhythmias.

Following treatment patient often gets spasm of different muscles (**tics**) for a long period which can be prevented by giving methocarbamol for 6 months to one year.

General measures

- Isolation
- Avoid noise and light
- ATG 3,000 units IM
- ATS-50,000 IM and 50,000 IV—after test dose
- Antibiotics like inj penicillin 20 lacs 6th hourly
- Inj tetanus toxoid 0.5 ml IM—to deltoid muscle
- IV fluids with TPN
- Urinary catheterisation
- Nasogastric tube is passed to prevent aspiration initially, later for feeding
- Regular suction of throat
- Nasal oxygen when required
- Prevention of bedsore formation
- Prevention of DVT by low molecular weight heparin
- Good nursing care.

Specific measures

- IV diazepam 20 mg 6th hourly
- IV phenobarbitone 30 mg 6th hourly
- IV chorpromazine 25 mg 6th hourly
- Endotracheal intubation and ventilator support
- Tracheostomy if there is severe respiratory secretions
- Steroids
- Bronchodilators like deriphylline
- Wound care—debridement, drainage, and local injection of ATG

Prophylaxis against tetanus

- In adults, fresh immunisation to start—second in one month, next in 6 months period. Tetanus toxoid 0.5 ml IM. Booster dose should be given once in every 4 years or after any significant trauma
- In infants—triple antigen (DPT)—6 weeks, 10 weeks, 14 weeks, 18 months, and 5 years
- To pregnant mother tetanus toxoid injections are given in 4th and 6th months of pregnancy
- Additional booster dose given in major injuries or high-risk injuries
- ATG 500-1000 units IM given as a prophylaxis in road accidents, severe burns, crush injuries, war wounds, penetrating wounds and wounds of head and face. Here tetanus toxoid also should be given separately at separate site IM

Monitoring during Therapy

PCO_2, PO_2, haemotocrit, blood urea, serum electrolytes, chest X-ray, ECG are done at regular intervals.

GAS GANGRENE

It is an *infective gangrene* caused by clostridial organisms involving mainly skeletal muscle as *oedematous myonecrosis*. Earlier it was called as ***malignant oedema***.

Source and Predisposing Factors

- Contaminated, manured or cultivated soil, intestines are the sources. Faecal flora commonly contains clostridial organisms enters the wound; in presence of calcium from blood clot or silica (silicic acid) of soil, it causes infection.
- It is common in crush wounds, following road traffic accidents, after amputations, ischaemic limb, gunshot wounds, war wounds. Injury or ischaemia or necrosis of the muscle due to trauma predisposes infection.
- Anaerobic environments in the wound—initial infection with aerobic organism utilises existing oxygen in tissues creating anaerobic environment to cause clostridial sepsis.

Organisms

- *Clostridium welchii* (perfringens): Gram-positive, central spore bearing, nonmotile, capsulated organisms, most common—60%.
- *Clostridium oedematiens.*
- *Clostridium septicum.*
- *Clostridium histolyticum.*

***Clostridium welchii* produce toxins**

- Alpha (most common)
- Beta
- Epsilon
- Iota
- *Phi toxin*—myocardial depressant
- *Kappa toxin*—destruction of connective tissue and blood vessels
- **Bursting factor** and circulating factor

Various *strains* include—A, B, C, D, E.
'A' strain is most common.

***Note*:**
Nonclostridial gas producing organisms like coliforms can also cause gas gangrene.

Exotoxins

- ***Lecithinase*** is important toxin which is haemolytic, membranolytic and necrotic causing ***extensive myositis.*** It splits lecithin into phosphocholine.
- ***Haemolysin*** causes extensive haemolysis.
- ***Hyaluronidase*** helps in rapid spread of gas gangrene.
- ***Proteinase*** causes breaking down of proteins in an infected tissue.

Spores enter through the devitalised tissues commonly
in road traffic accidents, crush injury
↓
Spores germinate
↓
Released bacteria will multiply
↓
Exotoxins are released
cause their effects

Effects

- Extensive necrosis of muscle with production of gas (hydrogen sulphide; nitrogen; carbon dioxide) which stains the muscle brown or black *anaerobic myositis/myonecrosis*.
- Usually muscle is involved from origin to insertion.
- Often may extend into thoracic and abdominal muscles.
- When it affects the liver it causes necrosis with frothy blood—***foaming liver***, is characteristic.
- Rapidly spreading infection which is also often fatal.
- Limbs are commonly involved; but organs like liver can also be affected.
- Muscle glycogen is broken down into lactic acid, CO_2 and hydrogen. Proteinase released by organism forms amino acids which further releases ammonia and hydrogen sulphide. Acid released earlier is neutralised by ammonia and calcium to progress further multiplication of organisms.

Clinical Features

Incubation period is 1-2 days.

- Features of toxaemia, fever, tachycardia (*out of proportion* to fever) pallor.
- Wound is under tension with foul smelling discharge (sickly sweety/*decaying apple* odour).
- Khaki brown coloured skin due to haemolysis.
- ***Crepitus*** can be felt.
- Jaundice may be *ominous sign* and also oliguria *signifies renal failure.*
- *Frequent sites* are adductor region of the lower limb and buttocks and subscapular region in upper limb.

Clostridium welchii can infect limbs, abdominal wall, appendix, gallbladder, common bile duct, intestine, uterus (during septic abortion).

Clinical Types

- ***Fulminant type*** causes rapid progress and often death due to toxaemia, renal failure or liver failure or MODS or ARDS.
- ***Massive type*** involving whole of one limb containing fully dark coloured gas filled areas.
- ***Group type:*** Infection of one group of muscles, extensors of thigh, flexors of leg.
- ***Single muscle type*** affecting one single muscle.
- ***Subcutaneous type*** of gas gangrene involves only subcutaneous tissue (i.e. superficial involvement). It is mainly of *anaerobic cellulitis type* without muscle involvement usually caused by less virulent clostridial organisms other than clostridial welchii. It is usually superficial but may spread and involve fascial planes. It causes necrosis with foul smelling seropurulent discharge.



Fig. 1.125: Gas gangrene in upper limb. It is after effect of an assault using an axe by a drunken husband.



Fig. 1.126: Gas gangrene involving entire leg extensively. Note the black/khaki coloured area. Patient died of toxaemia.

Complications of Gas Gangrene

- Septicaemia, toxaemia.
- Renal failure, liver failure.
- Circulatory failure, DIC, secondary infection.
- Death occurs in critically ill patients.

Investigations

- X-ray shows gas in muscle plane or under the skin.
- Liver function tests, blood urea, serum creatinine, total count, PO_2, PCO_2.
- CT scan of the part may be useful especially in chest or abdominal wounds.
- *Gram's stain shows* Gram-positive bacilli.
- *Robertson's cooked meat media* is used which causes meat to turn pink with sour smell and acid reaction.

Right is right even if everyone is against it, and wrong is wrong even if everyone is for it.

- *Clostridium welchii* is grown in culture media containing 20% human serum in a plate. Antitoxin is placed in one-half of the bacteria grown plate sparing the other half. Zone of opacity will be seen in that half of the plate where there is no antitoxin. In the other half part of the plate where there is antitoxin there is no opacity—*Nagler reaction.*

Prevention of gas gangrene

- Proper debridement of devitalised crushed wounds
- Devitalised wounds should not be sutured
- Adequate cleaning of the wounds with H_2O_2 and normal saline
- Penicillin as prophylactic antibiotic.

Treatment

- Injection benzyl penicillin 20 lacs 4th hourly + Injection metronidazole 500 mg 8th hourly + Injection aminoglycosides (if blood urea is normal) or third generation cephalosporins or metronidazole.
- ***Fresh blood transfusion***.
- ***Polyvalent antiserum*** 25,000 units given intravenously after a test dose and repeated after 6 hours (Welchii 10,000 IU, oedematiens 10,000 IU, and septicum 5,000 IU).
- ***Hyperbaric oxygen*** is very useful.
- Liberal incisions are given. All dead tissues are ***excised*** and **debridement** is done until healthy tissue bleeds.
- Rehydration and maintaining optimum urine output (30 ml/hour) (0.5 ml/kg/hour).
- Electrolyte management.
- In severe cases ***amputation*** has to be done as a ***life-saving procedure***—stump should never be closed *(Guillotine amputation)*.
- Often ventilator support is required.
- *Once a ward or operation theatre is used for a patient with gas gangrene, it should be fumigated for 24-48 hours properly to prevent the risk of spread of infection to other patients especially with open wounds.*
- Hypotension in gas gangrene is treated with whole blood transfusion.
- Therapy should be concentrated in managing dehydration, hypotension, infection, toxaemia by hydration, fresh whole blood transfusion, passive immunisation, antibiotics, and hyperbaric oxygen, doing radical wound excision with removal of all dead tissues with foreign body or amputation with critical care.

TUBERCULOSIS

> *Whilst meagre Pthisis gives a silent bow, her strokes are sure, but her advances slow. No loud alarms, nor fierce assaults are shown: She starves the fortress first, then takes the town.*
>
> **—Samuel Garth**, 1699



Fig. 1.127: Tuberculous lymphadenitis and tuberculous ulcer.

- It is commonly caused by *Mycobacterium tuberculosis;* occasionally by *Mycobacterium bovis, M. kansasii, M. fortuitum, M. marinum, M. ulcerans.*
- *M. tuberculosis* is ***gram neutral, acid fast, alcohol fast*** straight or slightly curved rods.
- It is prevalent in most of the developing countries and has made its resurgence in the developed countries with the advent of AIDS.

Pathogenesis

- The characteristic lesion here is *'tubercle',* which is an avascular granuloma composed of a central zone containing giant cells, with or without caseation necrosis, surrounded by a rim of epithelioid cells, lymphocytes and fibroblasts.
- It can occur in almost all organs in the body. Presentation may vary depending on the individual sites.

General Features

- Low grade fever with evening rise of temperature.
- Loss of appetite.
- Decreased weight.

Investigations

- ESR is often raised; peripheral smear—lymphocytosis.
- AFB (Acid fast bacillus) staining using Ziehl-Neelsen stain.
- Chest X-ray is done to rule out pulmonary tuberculosis.
- Culture of the organism in Lowenstein Jenson media.
- Mantoux skin test—read after 48 hours of inoculation.
- Guinea-pig inoculation.
- Relevant investigations depending on the site of the tuberculosis.

Treatment

- Antituberculous drugs are given for 6 months to one year.
- Specific treatment is given depending on the site of the tuberculosis.

(Please refer individual chapters for details about tuberculosis at different locations and also chapter drugs for Antituberculous Therapy.)

LEPROSY

- It is caused by *Mycobacterium leprae.* It is a Gram-positive, acid fast bacillus.
- It mainly involves skin, nasal mucosa and peripheral neural tissues.



Figs 1.128A to D: A leprosy patient with the typical face (leonine); skin patches; hand deformities and trophic changes; trophic ulcer in heel.

- It involves only the cooler parts of the body (So axilla, gluteal region are not involved). Testicular involvement is seen but not the ovary. It does not involve the vital organs. Though not acutely fatal, the disease leaves the victim severely deformed and crippled for life.

Types

a. *Multibacillary Types*

- ***Lepromatous leprosy***: It denotes little or no host resistance. Bacilli are seen in large numbers in the superficial nodular lesions and the patient is highly infective.
- ***Borderline lepromatous.***
- ***Borderline.***

b. *Paucibacillary Types*

- ***Borderline tuberculoid.***
- ***Tuberculoid leprosy***: Here strong host resistance is observed. The disease is more localised, but it causes more deformities due to early involvement of nerves. Bacilli are scanty in the lesion and so infectivity is minimal.

Investigations

- Regular checking of sensation of the suspected area.
- Split skin smear, nerve biopsy.

Treatment

- Dapsone 100 mg daily.
- Rifampicin 600 mg once a month.
- Clofazimine 50 mg daily + 300 mg once a month.

For paucibacillary types, treatment is for 6 months.
For multibacillary types, treatment is for 2 years or more.

Surgical Complications in Leprosy

a. *Primary Deformities*

- Leonine facies.
- Collapsed nasal bridge.
- Upper branch facial nerve palsy (causes lagophthalmos).
- Keratitis and blindness.
- Claw hand either ulnar or combined ulnar and median nerves.
- Radial nerve palsy—wrist drop (1%).
- Clawing of toes due to involvement of posterior tibial nerve.
- Foot drop due to involvement of lateral popliteal nerve. (Medial popliteal nerve which supplies the tibialis posterior is never involved.)

b. *Secondary Deformities*

- Anaesthesia of the part makes it prone to trauma, infection, infective gangrene, destruction, autoamputation and functionless parts.
- Trophic ulcers in the foot are common.

Life is like a mirror. If you smile at it, it also smiles at you.

Treatment

- Reconstructive surgeries.
- Release of contractures.
- Tendon transfers.
- Arthrodesis.
- Ulcer management.
- Physiotherapy and rehabilitation.

SYPHILIS (GREAT POX) (FRENCH DISEASE)

> *It is concluded…that this disease which amongst the Italians is called Gallicus, that is to say, the French disease, should now be named PaturSa, …a disease filthie and Saturnall. It is a filthie disease, because it maketh women to be esteemed unchast and irreligious…. There is a twofold kinde of causes…. The first is the only influence or corruption of the aire, from whence we must charitably thinke, that it infected those which were religious. The second is conversation, as by kissing and sucking, as appeareth in children, or by carnall copulation.*
>
> —**Juan Almenor,** 1502

It is a venereal infection caused by *Treponema pallidum.*

Early syphilis: It lasts for 2 years and the patient is infective during this period.

Primary syphilis: It presents as a *Hunterian chancre* (Hard chancre). It is a shallow, painless, indurated, nonbleeding ulcer usually seen in the genitalia and often on the lips, breasts and anal region. It occurs in 3-4 weeks after the infection. It is confirmed by dark field microscopic study of the discharge for the organism.

Secondary syphilis: It occurs in 6-12 weeks.

It presents as:

- Cutaneous coppery rashes.
- Snail-track oral ulcers.
- Condyloma lata: Raised, flat, white lesions seen at the mucocutaneous junctions (mouth, anus vulva).
- Painless, shotty lymphadenopathy—epitrochlear suboccipital.
- Moth-eaten alopecia.
- Hepatitis, arthritis, iritis, meningitis. Massive, enlarged liver in syphilis is called as *hepar lobatum.*
- Syphilitic osteitis with "ivory" sequestrum.

Latent syphilis: It lasts between 2 years to lifetime. Serum tests are positive.

Late (tertiary) syphilis:

- Painless, punched out, *gummatous ulcers* are seen with *"wash leather base" and silvery tissue paper scar.*
- It is seen over the tibia, sternum, ulna, skull, scrotum.
- It is a hypersensitivity reaction occurs as a result vasculitis and obliterative endarteritis.
- *Neurosyphilis.*
- *Cardiovascular syphilis*—aneurysm of arch of aorta.

Investigations

- VDRL test; Kahn test.
- *Treponema pallidum* haemagglutination test (TPHA).
- *Treponema pallidum* immobilisation test (TPI).

Treatment

Penicillin for 15 days is the drug of choice.

Doxycycline 100 mg can be given thrice daily for 15 days. Others: Erythromycin, tetracycline, cephalosporins.

Jarisch-Herxheimer reaction is commonly seen after penicillin, which often requires steroid therapy.

Congenital Syphilis

Here the infection is transmitted from the mother to foetus through placenta.

Early congenital syphilis: It is seen in newborn.

- *Features are:*
  - Rash, syphilitic snuffles
  - Nasal discharge, weight loss
  - Periostitis, meningitis, hepatosplenomegaly
  - Pneumonia alba

Late congenital syphilis:

- *Hutchinson's triad:*
  - *Interstitial keratitis*
  - *8th nerve deafness*
  - *Hutchinson's teeth: Peg shaped upper incisors*
    Moon's molar, molars with cusps
- Congenital neurosyphilis
- Cutaneous, skeletal or visceral gummas
- Saddle nose
- Sabre tibia, Clutton's joint
- Perforated palate

Congenital syphilis is treated with penicillins.



Fig. 1.129: Saddle nose.

ACTINOMYCOSIS

- It is caused by ***Actinomyces israelii***.
- It is an anaerobic Gram-positive ***fungal like bacterium***, which is a branching filamentous organism. It is called as ***"Ray fungus"*** because of ***sun-ray*** appearance.

Clinical Types

- **Facio-cervical**: It is the most common type. Infection spreads either from tonsil or from adjacent infected tooth. Initially an induration develops. Nodules form with involvement of skin of face and neck. It softens and bursts through the skin as ***sinuses*** which discharge *pus which contains sulphur granules* (60%).

- **Thorax**: Lungs and pleura get infected by direct spread from pharynx or by aspiration. Empyema develops. Later chest wall nodules appear leading to sinuses with discharge (20%).
- **In right iliac fossa:** It presents as a ***mass abdomen*** with discharging sinus.
- **Liver** is infected through portal vein (*Honey comb liver*).
- **Pelvic:** Pelvic actinomycosis can occur due to intra uterine devices.

Pathogenesis

Organism enters through deeper plane of the tissue, causes subacute inflammation with induration and nodule formation. Eventually discharging sinus forms at the surface. Pus collected in a swab or sterile tube will show *sulphur granules*.

Clinical Features

- ***Discharging sinus*** with induration and nodules.
- ***No lymph nodal involvement***.
- Through blood spread it may cause pyaemia and endanger life.

Investigations

- Pus under microscopy shows branching filaments.
- ***Gram's staining*** shows ***Gram-positive mycelia*** in centre with ***Gram-negative radiating peripheral filaments***. These clubs are due to host reaction which are lipoid material (antigen-antibody complex).
- Cultured in brain heart infusion agar and thioglycolate media.

Differential Diagnosis

- Chronic pyogenic osteomyelitis.
- Carcinomas at the site.
- Tuberculous disease.

Treatment

- Penicillins for longer period (6-12 weeks).
- Tetracyclines, lincomycin, streptomycin.
- Dapsone and iodides may be useful.
- Antifungals are often given because it is fungal like bacterium.
- Surgical debridement is occasionally required.

MADURA FOOT (MYCETOMA PEDIS)

- It is a chronic granulomatous condition of the foot involving subcutaneous and often deeper tissues causing multiple discharging sinuses.
- It was first identified in ***Madurai, Tamil Nadu (India)*** *by* ***Gill*** (1842, Madura mycosis).
- It is common in India and Africa.
- It is common in Tamil Nadu.
- It can be *fungal* (*more common*) or *bacterial origin. Bacterial* can be *Actinomyces* or *Nocardia*. Among bacterial *Nocardia madurae* is most common.
- *Fungal eumycotic mycetoma* is caused by *Madurella mycetomi* or *Madurella grisa*. Fungal mycetoma causes black granules, crushed smear of which shows thick stout filaments (5 µm). *Bacterial mycetomas* are by *Actinomyces* (*A. israelii* or *A. bovis*) or by *Nocardia* or *Actinomadura* (red granules). Occasionally it can be due to pyogenic bacteria like *Staphylococcus aureus* (*Botryomycosis*). Bacterial mycetoma shows white/yellow/red granules which on smear delineates thin filaments (1 µm). *Nocardia asteroids* can primarily involve lungs later spreading to brain, kidney and other organs as metastatic infection.

Organisms

- ***Nocardia madurae*** (most common)
- *Nocardia brasiliensis*
- *Nocardia asteroides*
- *Actinomyces israelii*

Pathogenesis

Organism enters through a prick in the foot usually who walks barefoot
↓
Reaches deeper plane in the foot
↓
Evokes chronic granulomatous inflammation
↓
Causes pale, painless, firm nodule
↓
Formation of vesicles
↓
Burst to form a discharging sinuses.

- Discharging granules may be *Black, Red, Yellow.*
- In black type of Madura foot, infection is mainly subcutaneous.
- In red and yellow types, it burrows into the deeper plane including bone causing bone necrosis (osteomyelitis). Eventually gross swelling of the limb with multiple discharging sinuses with disability will occur.
- Muscles and bones are involved.
- Tendons and nerves are affected.
- **Regional lymph nodes are not involved.**
- Condition will deteriorate by secondary bacterial infection.

Clinical Features

- Painless diffuse swelling in the foot of long duration.
- Later multiple discharging sinuses develop on the skin.
- Lymph node involvement will not occur unless secondary bacterial infection is present.
- Significant limb disability is common.

Differential diagnosis

- Chronic osteomyelitis
- Tuberculous osteomyelitis
- Carcinoma

The best rose bush is not the one with the fewest thorns, but that which bears the finest roses.— **Jerry Van Dyke**

Investigations

- Discharge study will show branching filamentous appearance of the organism.
- Culture in Sabouroud's dextrose agar medium.
- Gram stain for actinomycosis will show sun-ray appearance with Gram +ve centre and Gram –ve clubs.
- X-ray of the foot is done to look for osteomyelitis.



Fig. 1.130: Madura foot. Note the multiple sinuses.



Figs 1.131A and B: Mycetoma thigh and foot in two different patients. Note the discharging sinuses.

Treatment

- Antifungal drugs—amphotericin.
- Long-term penicillins.
- Dapsone, iodides.
- In severe cases amputation may be required.
  If infection occurs in the hand it is called as ***Madura hand***.

RABIES (HYDROPHOBIA)

It is an *acute fatal encephalomyelitis* caused by a single stranded RNA virus *Lyssa virus type 1*.

- It is a zoonotic disease transmitted to humans by bite/lick/scratch of infected animals (*commonly dogs*).
- It is an ancient disease mentioned even in Vedas. Rabies word is derived from Sanskrit word *'Rabhas'* means 'to do violence'.
- *Celsus* found relation of saliva of infected dog to human disease in 1st century AD. *Louis Pasteur* developed 1st vaccine against Rabies in 1885.
- Rabies is uncommon in developed countries. It is mainly seen in Indian subcontinent (80%) and Africa. In India it is not seen in Lakshadweep, Andaman and Nicobar islands. If disease is not seen for 2 years in humans and animals then that area is termed as *rabies free*. Maldives country does not have human or animal rabies.

Pathogenesis

- There is no predilection for age or sex even though it is observed more in children and adult males.
- 95% of rabies develops due to *bite of rabid dog* occasionally cat (**Urban rabies**). Other animals that can transmit rabies are monkey, horse, fox, cows and buffaloes, donkey, pig, sheep, camel, elephant, mongoose, jackal, bear (**Wild life/sylvatic rabies**). In India transmission is not observed through bats, rodents and birds. **Bat rabies** (vampire bat) is seen in parts of USA and Latin American countries.
- Asymptomatic carrier stage occurs only in animals but they are unlikely to be infective. Only symptomatic animals are considered to be infective.
- Rabies virus is bullet shaped envelop virus (75 nm × 180 nm) with numerous glycoprotein spikes to help in attachment of virus and also to induce antibodies. Natural occurring rabies virus is called as **street virus** which shows long incubation period of 20-60 days. Serial passage of this virus to brain of rabbits creates **fixed virus** which has got short incubation period of 4-6 days which does not show Negri bodies. This fixed virus which cannot multiply in extraneural tissues is inactivated to prepare vaccine.
- *Infection* commonly occurs by animal ***bite***, often by ***licks***, ***scratches***. Licks on *abraded skin* and licks on *abraded or unabraded* mucosa can cause infection. Licks are often *ignored* dangerously. Severity of infection depends on *viral load in the animal saliva* and class of wound. ***Aerosol*** transmission is found in bats or in lab workers. ***Person to person*** transmission can occur even though it is rare. Rabies may get transmitted through organ/corneal transplantation.
- Virus multiplies at the site of infection and passes (*ascends*) through the peripheral nerves into the CNS to develop **Negri bodies** in the brain leading into *fatal encephalomyelitis*.

From the brain virus *descends* into different tissues like *salivary glands*, muscles, heart, adrenals and skin. It also involves salivary glands to get secreted in the saliva to cause infection.

Clinical Features

- Incubation period is 3-6 weeks; but rarely can be up to many years.
- Prodromal symptoms like fever, headache.
- Pain, tingling sensation at the site of bite.
- Hyperexcitability and irritability; increased muscle reflexes and spasms.
- Increased salivation, sweating, lacrimation.
- Hydrophobia (fear of water) and **aerophobia** (fear of air) is **pathognomonic.**
- Mental instability, dilatation of pupils.
- Symptoms are aggravated by swallowing water or blowing air on them.
- Once disease starts, patient die in 72 hours.

Fear of water is seen only in affected human beings, not in animals.

Classification of Wounds

Class I**:** Touching or feeding the diseased animal, lick over intact skin or scratches without oozing of blood.

Class II**:** Licks on broken skin, scratches with blood ooze, and all bites except over head, face, palms and fingers. Minor wounds less than five in number.

Class III: All bites over head, face, palms and fingers, lacerated wounds, wounds more than five in number, wild animal bites, *and contamination of mucous membrane* with saliva.

Indications for Antirabies Vaccination

- All rabid animal bites.
- If animal is killed or dies during 10 days of observation period.
- Bite by an unidentified animal.
- If lab tests in animal show positive for rabies.
- All wild animal bites.

Vaccines for Rabies

1. Nervous Tissue Vaccine

(a) BPL inactivated vaccine: It is nervous tissue vaccine. It is 5% emulsion of the infected brain of the sheep containing the inactivated fixed virus. It is *Semple vaccine*.

Dosage of semple vaccine (as recommended by Pasteur Institute, Coonoor)

	Adult	*Children*	*Duration*
Class I	2 ml	1 ml	7 days
Class II	3 ml	3 ml	10 days
Class III	5 ml	3 ml	10 days

Mode of administration: Subcutaneously into the abdominal wall using long needle. Joseph Meister received first anti-rabies vaccine (ARV) in 1885. In Olden days, it was given for 15-21 days.

Antibody develops in 7-30 days. Protection lasts only for 6 months. Booster doses are given if needed.

Side effects

- Headache, palpitation, allergic reactions.
- Redness, tenderness and swelling at the site of the vaccination.
- *Post-vaccinal neuroparalysis*—a dangerous life-threatening complication.
- During therapy patient *should avoid alcohol and steroids*.

(b) Nervous tissue vaccine derived from suckling mouse (less than 9 days old) brain *(Fuezalida vaccine)* is used to reduce neuroparalytic complications as suckling mouse has low myelin neuron. It is given for 10 daily doses then on 20th and 30th day.

2. Avian Vaccines—Duck Embryo Vaccine (DEV)

It has got less neuroparalytic side effects. It can cause egg protein allergy. Purified duck embryo vaccine (PDEV-1 ml) is available in India.

3. Cell Culture Vaccines

They are more potent and safer.

- **Human Diploid Cell Vaccine (HDCV-1 ml):** Safest vaccine. It is prepared using fixed virus in human diploid fibroblast cells. But it is costly. It is available in India.
- *Second generation tissue culture vaccines*: They are potent and cost-effective. They are derived from nonhuman base sources. Examples are chick embryo fibroblast **(Purified Chick Embryo Cell Culture Vaccines—PCECV-1 ml)**, foetal bovine kidney, hamster kidney cells, vero cells **(Purified Vero cell Rabies Vaccine—PVRV-0.5 ml).**

Dosage: 2.5 IU in one ml. One ml is given IM into the deltoid on 0, 3, 7, 14, 28 and 90 (optional) days.

Side effects: Headache, redness at the site, fever. No other serious side effects.

Second generation tissue culture vaccine can be given intradermally also. Intradermal dose is one fifth of the intramuscular dose (0.1 ml).

Wound Treatment

- *Proper local wound care* reduces the chances of rabies infection by 80%. Immediate cleaning and washing of the wound with running water for 15 minutes is essential to reduce the viral load at the wound site. If soap is available soap water is also used. It is better to wash with warm water if available.
- Wound should be *cleaned with virucidal agents* like alcohol, tincture, povidone iodine. Savlon or carbolic acid or nitric acid should not be used.

- Wounds *should not be closed*. ARS should be injected locally. In deep wounds it may be closed only after 48 hours with loose sutures after thorough washing.
- ARS (horse or human) *should be injected* to all wounds locally.
- One *should not* scrub the wound.
- One *should not touch* the wound with *bare hands*. One should wear gloves to touch the wound.

Passive Immunity

It is used in all severe exposures, class II and class III and in all wild animal exposure. Present recommendation is injection of ARS with vaccine in all exposed patient irrespective of the class.

Types of Antirabies Serum (ARS)

Horse antirabies serum (horse/equine ARS): It is given on first day with a dose of 40 IU/ kg body weight (maximum up to 3000/units). Half is given into the wound and another half given into the gluteal muscle (IM)—single dose. It prevents the multiplication of the virus at the wound site. It also prolongs the incubation period. Passive immunity should always be combined with vaccine therapy. ARS needs test dose prior to injection of full dose. *Side effects*: Serum sickness, anaphylaxis. **Human rabies immunoglobulin (**HRIG). Dose is 20 units/kg body weight. Part is injected into the wound remaining part into the gluteal muscle (IM)—single dose. Patient should be immunised actively along with serum with additional booster doses. Side effects are rare here.

Post-exposure Prophylaxis

Cell culture and purified duck embryo vaccines are used as they are safe and efficacious.

All vaccines should be given to deltoid region (never to gluteal region as due to high fat content vaccine won't get absorbed into circulation rapidly and so immune response may not be optimum). Vaccines should be stored at 4-8°C after reconstitution and should be used immediately.

Mode of Injection

a. Intramuscular into deltoid region—**Essen regimen.** It is commonly used and technically easier but higher dose is required compared to intradermal. It is injected at a schedule of 0, 3, 7, 14, and 28 days and booster at 90 days. *First dose should be combined with ARS preferably HRIG.* Multisite IM regime is often used as follows—first dose on day 0 two doses of IM vaccine is injected one on each side deltoid. Later single doses on 7 and 21 days (as 0 {2}, 7 {1}, 21 {1}).
b. *Intradermal route*: (1) *Two site intradermal method* is used. 1/5th of the IM dose of selected vaccine is used. Two sites on the day 0, 3, 7 and one site on the days 28 and 90 . PVRV 0.1 ml; PCECV 0.2 ml; PDEV 0.2 ml. (2) *Eight site intradermal method* is used. On day 0, eight sites intradermal injections at both deltoids, both suprascapular, both thighs, both lower quadrants of abdomen are given. On day 7, on 4 sites—both deltoids, both thighs intradermal injections are given. On days 28 and 90 one dose on each day intradermal vaccine is injected at one site. HDCV 0.2 ml is used. It is like 0 (8); 7 (4); 28 (1); 90 (1). In whatever type, on first day (0) rabies immunoglobulin should be injected locally as well as IM.

Postexposure vaccination if individual *has been vaccinated earlier*: Doses on days 0, 3, and 7 are given. But ideally assessed by serum antibody level (should be more than 0.5 IU/ml. Passive immunity is not given in individuals who had vaccination earlier.

Pre-exposure Prophylaxis

It is given to veterinarians, animal handlers. Dose: I ml of cell culture vaccine IM or 0.1 ml intradermally on days 0, 7, 28. Serum titre for antibodies should be assessed after 1 month. If it is less than 0.5 IU/ml then one booster dose is injected. Booster doses are given once in every 2 years.

RABIES IN DOGS

Incubation period: 10 days to 8 weeks.

Types

a. ***Furious type***: Here dogs are aggressive like a mad dog. Dog changes its behaviour with loss of fear of human beings; bites objects, eat, mud, etc. Running amok, voice change, inability to bark properly, excessive salivation and foaming, paralysis and death.
b. ***Dumb type***: Dog is paralytic and sleepy. There is no aggressiveness at all. Dog sleeps for 3 days and dies.

Once symptoms of rabies develop in a dog *it rarely survives more than a week.*

Dog brain is sent for study in 50% glycerol-saline solution.

Lab Tests to Confirm Rabies in Dogs/Animals

- *Fluorescent antibody test (FRA test)*: It is reliable test. If FRA test is negative in brain of animal then even if dog is rabid its saliva does not contain virus. FRA test is positive at any stage of the disease.
- *Microscopic* examination of the brain of the infected dead animal to look for NEGRI bodies. It is seen in 90% of dead rabid dogs.
- *Mouse inoculation test* is very sensitive test. 10% brain tissue emulsion in saline is centrifuged at 2000 rpm for 10 minutes; 0.03 ml top fluid is injected intracerebrally into the suckling mouse to demonstrate rabies in 8 days in mouse.
- Corneal test is simpler but negative result does not rule out the infection possibility.

Immunisation in Animals

a. *BPL inactivated nervous tissue vaccine* (20% infected sheep brain suspension): Single dose 5 ml to dogs; 3 ml to cats. Second dose after 6 months. Then once a year regularly.
b. *Modified live virus vaccine* (33% infected chick embryo suspension): Dose—3 ml single dose which is repeated once in 3 years.
c. *Oral vaccines* are used successfully to control wild foxes in Canada by placing vaccine in food through baits.

Remember about rabies

- Control of stray dogs and immunisation of all dogs will reduce the incidence of rabies
- Prevention is the only way in rabies. Established rabies cannot be treated—100% mortality
- HDCV and PCECV dose is 1 ml; PVRV is 0.5 ml—IM into deltoid or anterolateral aspect of thigh in children (NEVER GLUTEAL region)
- Day 0 is the day of first date of vaccination not day of bite
- Interchanging of vaccines is even though acceptable but not well recommended and ideally should be avoided
- Vaccine dose is same in all age groups
- Reconstituted vaccine should be used immediately
- Vaccine dose may be doubled in first dose if ARS is not used in bites of face, head, hands and genitals, in malnourished patients, in patients who are on steroids, antimalignancy drugs, antimalarials; in pregnancy, lactation, infants, elderly, HIV and immunosuppressed individuals
- Consumption of unboiled milk of a rabid cattle amounts for class III bite and needs prophylaxis vaccine
- Pet dog should be examined periodically by veterinary doctor. Usual vaccination method used in dog is—at 3rd month of age, 1 month later, and later yearly booster doses. 0, 6 months and then yearly is also used. Pet dog should be prevented from coming into contact with stray dogs
- Dietary or alcohol restriction is not needed during vaccination as it will not alter immune response
- Concomitant other vaccine injection along with rabies vaccine can be done but at different injection site as there is no interference with immune response
- There is no contraindication for rabies vaccine as it is life-saving method
- All cases of dog bite should receive initial vaccine and ARS immediately. If the dog remains healthy even after 10 days of observation period vaccine is discontinued. Virus can be present in saliva 3 days before onset; once symptom begins dog cannot live for more than 4 days. Safe period of 3 days is added and so total 10 days is observed
- Virus can present in semen of a rabid man. So if he had contact with his wife within 5 days prior to symptoms then wife should be vaccinated as class III with HRIG
- If by mistake vaccine is given to gluteal region, fresh full course of vaccine to deltoid region should be started
- There are no single shot vaccines available. It is a myth
- Antiviral drugs are of no use
- Modern CCVs are very safe and efficacious
- Intradermal route of 0.1/0.2 ml is the best route
- Equinus ARS is cheaper and equally effective; but test dose should be given to prevent reaction
- Rabid dog *will never* have hydrophobia. Rabid dogs can swim through water or can even drink water. Aerophobia and photophobia are present in rabid dog. Hydrophobia is observed *only in* human rabies
- Bite by cats and cows also should be vaccinated
- Steroids and antimalarials should be avoided during vaccination as it may alter the immune response

ANTHRAX

- It is caused by *Bacillus anthracis*, which is a *Gram-positive*, aerobic, spore forming, capsulated, nonmotile, nonacid-fast bacillus and is *resistant to heat and antiseptics*.
- Disease is common in cattle and seen in people who handle carcasses, wool, hairs.
- It is often used in *biological war.*

Types

a. Cutaneous type (*Hide porter's disease*)

  - It is the most common type and occurs within 3-4 days after infection.
  - Indurated papule with black slough surrounded by vesicles—***malignant pustule.*** Itching is common in papule—black colour eschar (Anthrax means *charcoal*).
  - Regional lymph nodes are involved.
  - ***Toxaemia*** is common.

b. Respiratory type (*Wool Sorter's disease*) is due to inhalation of spores, causing ***haemorrhagic pneumonia***. It is more dangerous and life-threatening.

c. Alimentary type due to ingestion of spores.

  - Fatal *septicaemia and* meningitis can occur in any type.

Diagnosis

- Culture of fluid will show ***Medusa head appearance.***
- It shows positive M'Fadyean's reaction and positive Ascoli's thermoprecipitation test.

Treatment

- *Ciprofloxacillin, doxycycline*, penicillins.
- Alum precipitated Anthrax toxoid is used in humans.
- Scalvo's serum prepared by active immunisation of asses are used.

NOSOCOMIAL AND OPPORTUNISTIC INFECTIONS

Nosocomial Infection (Hospital Acquired Infection)

It is an infection acquired because of *hospital stay.*

Sources

- Contaminated infected wounds.
- Urinary tract infections.
- Respiratory tract infections.
- Opportunistic infections.
- Abdominal wounds with severe sepsis.

Spread can occur from one patient to another, through nurses or hospital staff who fail to practice strict asepsis.

Live your life as an exclamation not an explanation.

It is more common in:

- Diabetics
- Immunosuppressed individuals
- Patients on steroid therapy and life-supporting machines
- Instrumentations (indwelling catheter, IV cannula, tracheostomy tube)
- Patients with artificial prosthesis

Organisms

- *Staphylococcus aureus* is the most common organism causing hospital acquired wound infection. Others are *Pseudomonas, Klebsiella, E. coli, Proteus.*
- *Streptococcus pneumoniae, Haemophilus*, Herpes, *Varicella, Aspergillus, Pneumocystis carinii* are the most common pathogens involved in hospital acquired respiratory tract infection which spreads through droplets.
- *Klebsiella* is the most common pathogen involved in hospital acquired UTI which is highly resistant to drugs.

Management

Most of the time, organisms involved are *multidrug resistant, virulent* and hence, cause *severe sepsis*.

- Antibiotics.
- Isolation.
- Blood, urine, pus for culture and sensitivity to isolate the organisms.
- Blood transfusion, plasma or albumin therapy.
- Ventilator support.
- Maintaining optimum urine output.
- Nutritional support.

Prevention

- Isolation of patients with badly infected open wounds, severe RTI/UTI.
- Following strict aseptic measures in OT and in ward by hospital attendants.
- Proper cleaning and use of disinfectant lotions and sprays for bedpans, toilets and floor.
- The precipitating causes has to be treated, along with caring for proper nutrition and improving the anaemic status by blood transfusion.

Opportunistic Infections

They are normally of *low pathogenicity,* occur through therapeutic invasive procedures and are common in immune deficiency status.

Immune deficiency may be due to:

- Diabetes
- HIV
- Steroid therapy
- Radiotherapy
- Immunosuppressive therapy in transplantation
- Cytotoxic chemotherapy
- Starvation and old age

Therapeutic invasive procedures may be in the form of IV cannula, bladder catheter, tracheostomy and other minor surgical procedures which permit the skin organisms like *Staphylococcus epidermidis* to penetrate the skin and invade the deeper tissues.

Organisms

Bacteria: *Gram-negative: E. coli, Pseudomonas, Klebsiella, Proteus, Serratia.*
Gram-positive: *Staphylococcus epidermidis, Streptococcus pneumoniae.*
Viruses: *Herpes, CMV, Varicella zoster*, may cause fatal pneumonia.
Fungal: *Candida, Aspergillus,* yeast.
Protozoal: *Cryptosporidia* (causes diarrhoea), *Pneumocystis carinii.*

Because of the poor defence mechanism, infection is severe and often life-threatening.

Investigations

- Swab culture, blood culture, pus culture.

Treatment

- These infections are difficult to treat as they are often *multi-drug resistant.*
- Combination of broad spectrum antibiotics—cephalosporins, aminoglycosides, metronidazole are given.
- Depending on culture and sensitivity appropriate antibiotics are given.
- Often ventilatory support and critical care are necessary.

HIV INFECTION AND AIDS (Acquired Immunodeficiency Syndrome)

> *Even if I'd made no money, even if it was the pariah of specialties by virtue of its lack of procedures, an unexpected fringe benefit had become evident with the appearance of AIDS: In those early days, dealing with AIDS made us an elite group, an unexpectedly glamourous group. Even the cardiac surgeons could not approach our kind of heroism. Yes, they dealt with death every day. But it was somebody else's death they had to worry about. Never their own.*
>
> —**Abraham Verghese,** 1994

History

- 1983: Discovery of the virus
- First case of AIDS detected in UK
- 1984: Development of an antibody test

Definition of AIDS

Confirmed HIV infection with CD_4 T lymphocyte count < 0.2 × 10^6/L with symptoms.

Human Immunodeficiency Virus

It was discovered by *Barre-Sinoussi and Montagnier in 1983.*

Types

It is classified under HTLV Type III. HIV is subdivided into Type 1 and Type 2.

They are *retroviruses*.

Clinical classification of HIV Infection

- Acute infection
- Asymptomatic but positive HIV
- Persistent generalised lymphadenopathy
- AIDS (HIV related diseases)
  - Constitutional diseases like weight loss, fever, diarrhoea
  - Neurological diseases, dementia, neuropathy, myelopathy
  - Opportunistic infections
  - Malignancies. Kaposi's sarcoma, non-Hodgkin's lymphomas, primary cerebral lymphomas
  - Other diseases attributable to HIV infection

Mode of Transmission

- Sexual intercourse—vaginal or anal.
- Needle pricks—using unsterilised needles for injections, in IV drug abusers, careless handling.
- Mother to child—during birth through vaginal secretion, transplacental, through breast milk.
- Blood transfusions, organ transplantations.

Disease is common in Africa and Asian countries.

HIV mainly harbours in semen, genital secretions, blood, pus, sputum, saliva and other body fluids.

Anti-HIV antibody

- It appears about 3 weeks to 3 months after exposure
- It always indicates infection
- It has got weak neutralising capacity
- It persists throughout the HIV infection

Tests for HIV

1. ELISA test (**screening test**).
2. Western blot test (**diagnostic test**).
3. Polymerase Chain Reaction (PCR).
4. Anti-HIV antibody detection.
5. *Viraemia quantification*—to start treatment and to see the response of antiviral drugs (useful if it is within 0.5 log 10).
6. *CD_{4+} count*
   - Normal value > 500/mm^3.
   - Values between 200-500/mm^3 is seen in Kaposi sarcoma, *Candida* infection, *Mycobacterium tuberculosis.*
   - Values between 50-200/mm^3 is seen in *Pneumocystis carinii* and *Toxoplasma* infections.
   - Values < 50/mm^3 is seen in atypical mycobacteria, cytomegalovirus, lymphomas.

After HIV infection, there is a time gap for the patient to become reactive to tests. This time gap is called as *"Window period"*. This period is variable. But during this period, the individual is infective.

Pathogenesis

Envelope glycoprotein of HIV binds with the surface molecule CD_4 of 'T' lymphocytes, monocytes, macrophages, cutaneous Langerhan's cells, dendritic cells of all tissues.



Fig. 1.132: HIV patient presented with tuberculous cold abscess with discharging sinus.



Figs 1.133A and B: Picture showing HIV kit and wearing of the HIV kit as a precaution while doing surgery for HIV infected individuals.



Fig. 1.134: Severe infection of ear cartilage in a HIV infected patient.

CD_4 of lymphocytes—T helper cells induce and control the normal immune response.

HIV suppresses immune response completely directly by suppressing 'T' cell, indirectly by suppressing 'B' cell. Finally it dismantles and destroys the immune system making the individual prone to opportunistic infections.



After HIV infection, antibodies develop to virus envelope and core proteins which persists throughout life.

General Features in HIV

- Weight loss more than 10%.
- Fever more than 1 month.
- Diarrhoea more than 1 month.
- Neuralgia, arthralgia, headache.
- Lymphadenopathy.
- Cutaneous rashes, dermatitis, fungal (*Candida*), bacterial, viral (herpes simplex 1 and 2) infection.
- Dental infection, gingivitis, candidiasis of oral cavity and oesophagus.
- Varicella zoster infection.
- Opportunistic infections.
- Poor healing after surgery, trauma, infection with more complications.

Tumours in HIV Infection

- Kaposi's sarcoma—40% common.
- Lymphomas (NHL common) (3-4%).
- Cervical cancer.
- CNS lymphomas.
- Ano-genital squamous cell carcinoma.
- Testicular tumours (Germ cell types).
- Lung cancer.
- GIT lymphomas and adenocarcinomas.
- Squamous cell carcinoma of anal canal and cervix.

Pulmonary Problems in HIV Infection

- Pneumonia.
- Tuberculosis.
- Fungal infections.
- *Pneumocystis carinii pneumonia.*
- Cytomegalovirus pneumonia.

GIT Problems in HIV Infection

- GIT infections—bacterial, protozoal, viral.
- Kaposi's sarcoma, lymphomas, adenocarcinomas.
- Hepatitis ('C' virus), cholestasis.
- Anorectal diseases.
- Abdominal tuberculosis.



Fig. 1.135: Kaposi's sarcoma.

Neurological Problems in HIV Infection

- Encephalitis, aseptic meningitis, myelitis.
- Neuropathies with demyelination.
- Opportunistic infections like *Toxoplasma, Cryptococcus* causing severe meningitis.
- Primary CNS lymphomas.
- CNS tuberculosis (Tuberculomas).
- Visual problems.

Management

Investigations

- Tests for HIV.
- Tests for specific and opportunistic infections.
- Tests relevant for associated tumours.

Treatment

1. Antiviral therapy:
    - *Nucleoside reverse transcriptase inhibitor (NRTI):* Zidovudine, didanosine, abacavir, lamivudine, stavudine.
    - *Non-nucleoside reverse transcriptase inhibitor (NNRTI)*: Nevirapine, delavirdine.
    - *Protease inhibitors*: Ritonavir, indinavir, amprenavir.
2. Treatment of **opportunistic infections**.
3. Treatment of **tumours.**
4. Immunotherapy:
    - Alpha and gamma interferons.
    - Interleukins.
5. Bone marrow transplantation.
6. Anti-CD_3 or IL-2 after **HAART** (**H**ighly **A**ctive **A**nti-**R**etroviral **T**herapy).
7. ***Psychotherapy***.
8. Counselling of HIV patients and their families.
9. Life-expectancy after initial HIV infection is 8-10 years.

Prevention

Continues to be our best weapon in combating the menace of HIV infection.

- Safe sex. Condom usage reduces the risk of transmission.
- Health education.
- Use of disposable needles to prevent infections.

Universal precautions against HIV

- Care in handling sharp objects like needles, blades
- All cuts and abrasions in an HIV patient should be covered with a waterproof dressing
- Minimal parenteral injections
- Equipments and areas which are contaminated with secretions should be wiped with sodium hypochlorite solution or 2% glutaraldehyde
- Contaminated gloves, cottons should be incinerated
- Equipments should be disinfected with glutaraldehyde
- Disposable equipments (drapes, scalpels, etc.) should be used whenever possible
- Walls and floor should be cleaned properly with soap water
- Separate operation theatre and staff to do surgeries to HIV patients is justifiable
- Avoid shaving whenever possible before surgery in HIV patients
- All people inside the theatre should wear disposable gowns, plastic aprons, goggles, overshoes and gloves
- Surgeons, assistants and scrub nurse should wear in addition double gloves
- Suction bottle should be half-filled with freshly prepared glutaraldehyde solution
- Spilled body fluids should be diluted with glutaraldehyde
- Accidental puncture area in surgeon or scrub nurse should be immediately washed with soap and water thoroughly
- Theatre should be fumigated after surgery to HIV patient

HIV, hospital and surgeon

- Isolation per se of HIV patient is not required.
- Proper care should be taken to prevent transmission of the virus.
- Open wounds, disposal of excreta, fluids, discharge, pus and other infective materials should be taken care of properly.
- Risk of HIV infection through needle prick is very less (0.03%).

Following measures should be taken while managing HIV patients:

- Wearing double gloves.
- Wearing proper spectacles (as HIV can get transmitted through eyes directly).
- Wearing proper head mask, theatre shoes, apron.
- Measures to prevent spread of infection from patient to patient in the hospital.
- Disposal of needles through a sharp disposing container.

Disinfection

- Autoclave is ideal.
- Boiling.
- Sodium hypochlorite solution.
- 2% glutaraldehyde solution.

NECROTISING FASCIITIS

- It is spreading inflammation of the skin, deep fascia and soft tissues with extensive destruction, toxaemia commonly due to *Streptococcus pyogenes* infection, but often due to mixed infections like anaerobes, coliforms, Gram-negative organisms.
- It is common in old age, smoking, diabetics, immunosuppressed, malnourished, obesity, steroid therapy and HIV patients. Trauma is a common precipitating factor/cause—80%.
- It can occur in limbs, lower abdomen (Meleney‘s infection), groin, perineum. There is acute inflammatory response, oedema, extensive necrosis and cutaneous microvasculature thrombosis.
- Muscle is usually *not involved* in necrotising fasciitis.



Figs 1.136A to C: Necrotising fasciitis of skin, deep fascia and soft tissues without involvement of muscle.

A successful team beats with one heart.



Fig. 1.137: Fournier's gangrene. Note the destruction of skin over penis, scrotum and lower abdominal wall.

Types

Type I—It is due to mixed infection.

Type II—It is due to *Streptococcus pyogenes*, usually due to minor trauma like abrasions.

Clinical Features

- Sudden swelling and pain in the part with oedema, discoloration, necrotic areas, ulceration.
- Foul smelled discharge.
- Features of toxaemia with high-grade fever and chills, hypotension.
- Oliguria often with acute renal failure due to acute tubular necrosis.
- Jaundice.
- Rapid spread in short period (in few hours).
- Features of SIRS, MODS with drowsy, ill-patient.
- Condition if not treated properly may be life-threatening.

Management

- IV fluids, fresh blood transfusion.
- Antibiotics depend on C/S or broad-spectrum antibiotics. High dose penicillins are very effective. Clindamycin, third generation cephalosporins, aminoglycosides are also often needed.
- Catheterisation and monitoring of hourly urine output.
- Haematocrit, serum creatinine assessment.
- Pus culture, blood culture.
- Electrolyte management and monitoring.
- Control of diabetes, if patient is diabetic.
- Oxygen, ventilator support, dopamine, dobutamine supplements whenever required.
- Radical wound excision of gangrenous skin and necrosed tissues at repeated intervals.



Figs 1.138A and B: Necrotising fasciitis over chest wall and neck in two different patients.



Figs 1.139A to C: The typical necrotising fasciitis showing gangrenous skin. In second photo, arm is extensively involved. Also note the granulating area after extensive wound excision of the necrotic skin (debridement).

Necrotising fasciitis

- 80% are polymicrobial—*streptococci, staphylococci, E. coli, Pseudomonas, Proteus, Clostridium*
- It is a surgical emergency condition as it is very rapidly progressive
- Lower limb is the most common site—60%
- Oedema beyond erythema, woody hard texture on palpation
- Crepitus with subcutaneous emphysema, skin vesicles, dish water pus with grayish discharge are common
- Lymphangitis is usually absent
- Pink/orange skin stain and later focal skin gangrene
- Shock, multiorgan failure
- Resuscitation, wound excision, antibiotics, critical care (oxygen, intubation, ventilator) is needed
- Hyperbaric oxygen given in high pressure chamber with 100% oxygen in 2-3 atmospheric pressure reduces the mortality to 10-20%. It is bactericidal and promotes the neutrophil function
- In spite of adequate therapy mortality is 30-50% or more

- Vacuum assisted dressing is better.
- Once patient recovers and healthy granulation tissue appears, spilt skin grafting is done. As it commonly involves large area, mesh graft (meshing of SSG) is needed.

ACUTE PYOMYOSITIS

- It is infection and suppuration with destruction of the skeletal muscle, commonly due to *Staphylococcus aureus* (90%) and *Streptococcus pyogenes*, occasionally due to Gram-negative organisms.
- It is common in muscles of thigh, gluteal region, shoulder and arm.
- Precipitating factors are similar to necrotising fasciitis—trauma, malnutrition, anaemia, and immunosuppression.
- Pain, oedema, tenderness over the site with apparently normal overlying skin.
- Induration and muscle spasm is typical.
- Fever, jaundice, uraemia (*acute renal failure*) are common.



Fig. 1.140: Pyomyositis of thigh muscle.

Management

- *Creatine phosphokinase* will be very high and signifies acute phase (more than 50,000 units); due to *rhabdomyolysis*.
- MRI is useful. US guided pus aspiration is also done.
- *Treatment* is antibiotics, radical wound excision with removal of pus and all necrosed muscle and compartment release. *Haemodialysis* is needed until recovery if there is renal failure. Later secondary suturing or skin grafting is needed.

SURGICAL SITE INFECTION (SSI)

Surgical site infection is the second most common complication following surgical procedures (*first being postoperative pneumonia*) due to virulent bacterial entry, altered wound microenvironment, and changed host defense. Prevention of SSI can be achieved by better preoperative preparation; proper infection control during surgery; adherence to principles of preventive antibiotic therapy; better surgical techniques to reduce hematoma, tissue injury and foreign bodies within the surgical site; prevention of tissue hypoxia with enhanced oxygen support.

Common Sources of Infection

- Surgical wards, wounds, ulcers, catheters, drains, sputum, urine, faeces, open wounds.
- Operation room without proper ventilation, nurses, surgeons. Operation methods, sterilisation of instruments.

Organisms Causing SSI

- Commonly *Staphylococcus aureus*. Any organisms like clostridia, Gram-negative bacteria can cause SSI.
- Bacteria present in a wound with no signs or symptoms of systemic inflammation is called as *colonization,* usually less than 10^5cfu/ml. Transient exposure of a wound to bacteria (usually less than 6 hours) is called as *contamination* with varying concentration.

Sequence of Events (in Surgical Wounds)

- *Activation* of inflammation occurs by cuts, incisions, abrasions, burns. This initiates *inflammation* by protein coagulation, platelet aggregation, mast cell activity, release of complements and bradykinin. *Phase I of inflammation* begins with vasodilatation, increased bulk flow, increased vascularity. Later *Phase II of inflammation* proceeds with phagocytic infiltration and bacterial phagocytosis, removal of dead tissue with release of proinflammatory cytokines. Here tissue injury from incision mobilizes phagocytes before bacterial contamination leading into prior preparation against infection. If contamination is controlled monocytes activate to *regulate wound healing* using myofibrocytes and collagen.
- If bacterial *contamination is not controlled*, proinflammatory cells release TNF-α to stimulate neutrophils for phagocytosis. It also causes release of reactive oxygen and acid hydrolases from lysosomal vacuoles to result in lipid peroxidation, release of interleukins, evoking acute inflammatory response with creation of space containing pus which contains necrotic tissue, neutrophils, bacteria and proteinaceous fluid with *all signs of inflammation*—rubor, dolor, calor, tumour. It is *typical surgical site infection* (SSI).

The drops of rain make a hole in the stone not by violence, but by oft falling.

Factors Related to SSI

- *Bacterial entry* (inoculum) into the wound occurs through air in operation room, through instruments, through surgeons and theatre staffs, patient's endogenous bacteria like perineum, urine, etc.
- *Bacterial virulence* plays major role in causing SSI.
- *Microenvironment in the wound* like haemoglobin level at surgical site; presence of necrosis which interferes with phagocytosis; presence of dead space and or foreign body in the wound.
- *Host defenses* both natural (Innate) and acquired, when altered SSI occurs. Acquired causes are—shock, hypoxia, chronic illness, hypoalbuminemia, malnutrition, hypothermia, hyperglycemia, corticosteroids, HIV infection, malignancy and certain drugs.

Classification of Surgical Wounds

- *Clean wounds*—operative procedure does not enter into normally colonised viscus.
- *Clean-contaminated*—operation enters into a colonised viscus but under elective controlled circumstances.
- *Contaminated wounds*—gross contamination is present at the surgical site in the absence of obvious infection.
- *Dirty wounds*—surgical procedures performed when active infection is present.

Risk Classification and Identification System

It is based on three categories of variables—(1) Those that estimate intrinsic degree of microbial contamination at the surgical site. (2) Those that measure the duration of operation. (3) Host susceptibility markers.

Variables that Influence SSI

Variables that influence SSI	Point
1. An abdominal operation.	1
2. Operation lasting more than 2 hours.	1
3. Surgical site classified as contaminated or dirty/ infected.	1
4. Operation performed on a patient with more than three discharge diagnosis.	1
Total index	**4**
All variables have equal significance. This index twice better at predicting SSI than wound classification. Disadvantage is that it is not operation specific and variables collected at discharge.	

The National Nosocomial Infections Surveillance (NNIS) System as Basic SSI Risk Index

NNIS system	Point
Operation classified as contaminated or dirty.	1
The patient has an ASA (American Society of Anaesthesiology) preoperative assessment score of 3, 4, or 5.	1
Duration exceeds 75th percentile of 'T' point. 'T' point defined as length of time in hours that represents 75th percentile of procedures in NNIS survey.	1

Note:
T point for common surgical procedures are—Coronary artery bypass graft—5; Bile duct, liver or pancreatic surgery, craniotomy, head and neck surgery—4; Colonic surgery, joint prosthesis surgery, vascular surgery—3; Abdominal or vaginal hysterectomy, ventricular shunt, herniorrhaphy—2; Appendicectomy, limb amputation, caesarean section—1.

Physical Status classification

Class I: A patient in normal health.

Class II: A patient with mild systemic disease resulting in no functional limitations.

Class III: A patient with severe systemic disease that limits activity, but is not incapacitating.

Class IV: A patient with severe systemic disease that is a constant threat to life.

Class V: A moribund patient not likely to survive 24 hours.

Classification of Surgical Site Infection (SSI)

A. According to the Depth of the Wound Infection

1. Superficial incisional SSI

It occurs within 30 days of operation; involves only skin and subcutaneous tissue; and one of following:

Purulent drainage (culture documentation not required), organisms isolated from fluid/tissue of superficial incision, at least 1 sign of inflammation, wound is deliberately opened by the surgeon, surgeon or attending physician declares that the wound is infected.

A wound not considered a superficial site infection—if stitch abscess is present; if infection is at episiotomy site; burn wound, SSI extends into the fascia or muscle.

2. Deep incisional SSI

It occurs within 30 days of operation or 1 year if an implant is present; involves deep soft tissues of the incision; and at least one of the following—purulent drainage from the deep incision site without organ/space involvement, fascial dehiscence or deliberate separation by surgeon, deep abscess, identified by—reoperation/histopathology/radiology, surgeon or attending physician declares deep infection present.

3. Organ space infection

It occurs within 30 days or 1 year if an implant is present; involves anatomic structures not opened or manipulated during surgery; and one of the following—pus from a drain placed into organ/space, organism isolated by culture, identification of abscess by direct examination, reoperation, histopathology, radiology, diagnosis by surgeon or attending physician.

B. Classification of Wound Infection According to the Aetiology

a. *Primary infection* where the wound is the primary site of infection.

b. *Secondary infection* arises following a complication that is not directly related to the wound.



Fig. 1.141: Surgical site infection classification as—superficial incisional, deep incisional, organ space.



Figs 1.142A and C: Surgical site infection (SSI) types: (A) Superficial incisional SSI. (B) Deep incisional SSI. (C) Organ space SSI.

C. Classification of Wound Infections According to the Time

a. An *early infection* presents within 30 days of a surgical procedure.
b. An *intermediate infection* occurs between 1-3 months afterwards.
c. *Late infection* occurs in more than three months after surgery.

D. Classification of Wound Infections According to the Severity

a. *Minor* wound infection if there is discharge without cellulitis or deep tissue destruction.
b. *Major* if the discharge of pus is associated with tissue breakdown, partial or total dehiscence of the deep fascial layers of the wound, or if systemic illness is present.

Note:
Please refer first page of this Chapter for Southampton wound grading system and Asepsis wound score system.

Prevention of SSI

1. Preoperative

- Preoperative cleaning and antiseptic scrub of surgical site. Skin is colonised by various bacteria mainly *Staphylococcus aureus* (50%). Preoperative skin wash using chlorhexidine decreases bacterial colonisation by 80% and so wound contamination.
- Surgical site to be shaved or clipped in the operation theatre. Shaving should be done in the theatre itself or within 2 hours of beginning of the surgery otherwise infection rate may raise. Clean wound infection after shaving is 2.3%; after clipping it is 1.7%; without shaving or clipping it is 0.9%. However, selective shaving is definitely needed in area like scalp, axilla, groin, and perineum.
- Surgery should be avoided or postponed if fingers or hand of surgeon has open wounds or infection.
- Obvious infection in patient if exists should be treated.
- Prolonged preoperative admission should be avoided for an elective surgery.

2. Care in the Operation Theatre

- One should ensure that sterile caps, masks, gowns and sterile gloves are used.
- Proper skin cleaning is needed on table after anaesthesia using antiseptics like povidone iodine. One should ensure that all drapes are dry throughout the procedure and all instruments are thoroughly sterilised.
- Unimpregnated plastic drapes are avoided as it is found that it does not have any advantage.

- Gentle tissue handling, absolute haemostasis, holding tissues using instruments as much as possible, using appropriate suture materials, avoiding dead space during closure are certain essential on table tips to reduce SSI.
- One should consider leaving wounds open if it is severely contaminated.

3. *Preventive Antibiotic Therapy*

- It is used whenever high-risk of infection is associated with the procedure and consequences of infection if possibly severe and if patient has a high NNIS risk index.
- Antibiotics should be administered as close to the incision time as possible, before induction of anaesthesia.
- Selected antibiotic should have activity against likely pathogens.
- Postoperative systemic antibiotics for 24 hours (beyond 24 hours not shown to reduce SSI).
- Benefit of preoperative antibiotics in NNIS risk 0 index is difficult to assess and quantify.
- Proper techniques and wound microenvironment are more important than antibiotics.
- Preventive systemic antibiotics not to be used to prevent nosocomial infections.
- Oral antibiotic bowel preparation with appropriate mechanical bowel preparation.
- If systemic antibiotics are to be used antibiotics of longer half-life are to be chosen.
- Very long procedures should have a redosing strategy during the procedure.

4. *Enhancement of Host Defences*

- Increased oxygen delivery facilitates phagocytic eradication of microbes.
- Optimising core body temperature is important as warmer patients resist bacteria better.
- Blood glucose control is essential even to nondiabetics as well.

Management of SSI

- SSI is managed depending on the type of SSI—superficial, deep or organ space.
- All infected material and pus should be removed from the wound site—*debridement*.
- Sutures are removed to allow *free drainage* of infected material.
- Infected fluid is sent for culture and sensitivity and suitable antibiotics are started.
- Once wound shows signs of healing by healthy granulation tissue, secondary suturing is done. Often it is allowed to heal by scarring.

E. Swellings

CHAPTER OUTLINE

- Lipoma
- Cysts
- Dermoids
- Sebaceous cyst
- Glomus Tumour
- Papilloma
- Warts
- Fibroma
- Bursae
- Semimembranosus Bursa
- Morrant Baker's Cyst
- Lymph Cyst
- Lymphangioma
- Calcinosis Cutis
- Neuroma
- Neurofibroma
- Neurilemmoma
- Ganglion
- Chordoma
- Epignathus

LIPOMA

- It is a benign tumour arising from yellow fat.
- Tumour arising from brown fat is called as ***hibernoma (reddish brown).***
- It is called as ***universal tumour*** (ubiquitous tumour) as it can occur anywhere in the body (except in brain).
- It is the ***most common benign tumour (Karyotype 12q change)***.
- It can be ***diffused*** or ***localised***.
- *Diffuse lipomas* are not encapsulated, not well localised. Common in palm, sole, head and neck region, difficult to be removed. It is seen in subcutaneous and intermuscular tissues (*pseudolipoma*).
- It can be *single or multiple (5%)*. Multiple lipomas often associated with many syndromes like ***MEN syndrome*** *(Multiple endocrine neoplasia syndrome)*.

Types

- Painful lipomas are called as ***neurolipomas.***
- ***Dercum's disease*** is tender deposition of fat especially on the trunk, is also called as ***adiposis dolorosa***. *It is basically multiple neurolipomatosis.*
- *Fibrolipoma:* Lipoma with fibrous component.
- *Naevolipoma:* Lipoma with telangiectasis.
- *Lipoma arborigens* is pedunculated lipoma.
- Lipomas attain large size in thigh, shoulder, retroperitoneum, back and often may turn into sarcoma.

Sites

- Subcutaneous.
- Subfascial.
- Intramuscular.



Figs 1.143A and B: Large lipoma in the nape of neck.

Eyes that look are common; eyes that see are rare.—**J. Oswald Sanders**

- Intermuscular in anterior abdominal wall.
- Parosteal.
- Subserosal.
- Submucosal (GI tract).
- Extradural (not intradural).
- Intra-articular.
- Subsynovial.
- Subperiosteal.
- Intraglandular—breast, pancreas, kidney

Clinical Features

- Localised swelling, which is lobular (surface), nontender.
- Semifluctuant (because fat in body temperature remains in semiliquid condition). It is usually *nontransilluminant*.
- Mobile, with edges slipping between the palpating fingers (slip sign).
- Skin is free.
- Lipomas may be pedunculated at times.
- It is *rare* in children.
- *Pain* in lipoma may be due to neural element or compression to nerves or adjacent structures. *Angiolipomas* being highly vascular is commonly *tender*.
- *Trunk* is the most common site; nape of neck and limbs are next common.
- Clinically lipoma can be single, multiple or diffuse.



Figs 1.144A and B: Diffuse lipoma on the plantar aspect of foot and back.



Fig. 1.145: Slip sign of lipoma.



Fig. 1.146: Large lipoma in the back over scapula.



Fig. 1.147A



Figs 1.147B and C

Figs 1.147A to C: Pedunculated lipoma. It is common in axillary region. Lobular surface with narrow pedicle is typical. Often ulceration can occur in the surface due to repeated friction. It often mimics papilloma.

Differential Diagnosis

- Neurofibroma,
- Cystic swellings.

Note:
FNAC/incision biopsy in suspected cases and CT /MRI scan in cases of deeply located/intracavitary lipomas/large lipomas is done.

- Application of ice over the swelling hardens lipoma but not neurofibroma.

Complications

- Myxomatous changes—occurs in *retroperitoneal* lipoma.
- Saponification.



Figs 1.148A and B: Large lipoma in buttock region.



Fig. 1.149: Lipoma in lateral chest wall near posterior axillary fold.

There can be no substitute for detailed appraisal of the history of clinical signs.— **Harold Ellis**

- Calcification.
- Submucosal lipoma can cause intussusception and so intestinal obstruction.
- Sarcomatous changes—liposarcoma (most common type of sarcoma).

***Note**:*

It is now considered that all sarcomas are of *de novo* in origin to begin with at mitochondrial level; so benign soft tissue tumour turning into sarcoma is under debate or rare or not existing; but in *clinical practice* such an entity is still considered *by few*.

Liposarcoma

- Common in retroperitoneum, thigh and back
- Rapid growth
- Warm and vascular
- Dilated veins over the surface
- Infiltration in to deeper plane with restriction of the mobility
- Skin fixation and fungation
- Blood spread to lungs

Treatment



Fig. 1.150: Submuscular lipoma under gastrocnemius muscle.

- Excision.
- Small lipoma is excised under local anaesthesia and larger one under general anaesthesia.
- If it is liposarcoma, CT chest should be done to see secondaries in lungs. Later wide excision is done alongwith adjuvant chemotherapy and radiotherapy.



Fig. 1.151: Gross feature of specimen of lipoma.

***Note**:*

Lipoblastoma, a benign tumour is seen in infant boys in extremity subcutaneous tissue.

CYSTS

Cyst is a collection of fluid in a sac lined by epithelium or endothelium. **Word meaning of cyst is** "*bladder*" **(Greek)** **(**Greek word '*KUSTIS*' means bladder**).**

True Cyst

- Cyst wall is lined by epithelium or endothelium.
- If infection occurs, cyst wall also will be lined by granulation tissue.
- Fluid is usually serous or mucoid derived from the secretion of the lining.

False Cyst

- It does not have epithelial lining.
- Fluid collection occurs as a result of exudation or degeneration.

Example:

a. Pseudocyst of pancreas.
b. Wall of cystic swelling in tuberculous peritonitis.
c. Cystic degeneration of tumour.
d. After haemorrhage, in a haematoma, RBC's are lysed, gets absorbed and fluid remains as a false cyst.

"Apoplectic cyst" is formed in brain as a result of ischaemia, causing collection of fluid.

Classification

a. *Congenital cyst*
    - *Dermoids:* Sequestration dermoid.
    - *Tubulodermoids:* Thyroglossal cyst, postanal dermoid, ependymal cyst, urachal cyst.
    - *Cysts of embryonic remnants:* Cysts from paramesonephric duct and mesonephric duct, cysts of urachus and vitellointestinal duct.

b. *Acquired cysts*
    - *Retention cysts*: They are accumulation of secretions of a gland due to obstruction of the duct, e.g. sebaceous cyst, Bartholin's cyst, cyst of parotid, breast, epididymis.
    - *Distention cyst:* Lymph cyst, ovarian cyst, colloid goitre.
    - *Exudation cyst:* Bursa, hydrocoele, pancreatic pseudocyst.

c. *Cystic tumours*: Dermoid cyst of ovary, cystadenomas.
d. *Traumatic cyst*: Due to trauma, haematoma occurs usually in thigh, loin, shin. It eventually gets lined by endothelium containing brown coloured fluid with cholesterol crystals.
e. *Degenerative cyst*: Due to cystic degeneration of a solid tumour (due to necrosis of tumour).
f. *Parasitic cyst*: Hydatid cyst, trichiniasis, cysticercosis.

Clinical Features of a Cyst

- Hemispherical swelling which is smooth, fluctuant, nontender, well-localised.
- Some cysts are transilluminant.
- Presentation varies depending on its anatomical location and pathology.
- Cyst can be single or multiple. Sebaceous cysts are often multiple.



Figs 1.152A to C: Traumatic cyst thigh with false cyst wall with clot inside.

Effects of a Cyst

- Compression of adjacent structures (CBD): Choledochal cyst compressing over the CBD.
- Infection.
- Sinus formation.
- Haemorrhage.
- Torsion, e.g. ovarian cyst.
- Calcification, e.g. hydatid cyst, cysticercosis.
- Cachexia: In malignant ovarian cyst patient goes for severe cachexia.

Swellings which are brilliantly transilluminant

- Ranula
- Cystic hygroma and lymph cyst
- Hydrocoele
- Epididymal cyst (*Chinese-lantern* pattern)
- Meningocoele



Figs 1.153A and B: Brilliantly transilluminant swellings—possibly lymph cyst.

DERMOIDS

Types

1. *Sequestration Dermoids*

- It occurs at the line of embryonic fusion, due to inclusion of epithelium beneath the surface which later gets sequestered forming a cystic swelling in the deeper plane.
- It is congenital type.

Common sites are:

a. Forehead, neck, postauricular dermoid.
b. External angular dermoid.
c. Root of nose.
d. Sublingual dermoid.
e. Anywhere in midline or in the line of fusion.
    - Dermoids occurring in the skull may extend into the cranial cavity.
    - When it occurs as an external angular dermoid, it extends into the orbital cavity, or it can extend into any cavity in relation to its anatomical location (e.g. thorax, abdomen).

Types of angular dermoid

a. ***External angular dermoid:*** It is a sequestration dermoid situated over the external angular process of the frontal bone. Outer extremity of the eyebrow extends over some part of the swelling. This typical feature differentiates it from the swelling arising from the lacrimal gland. It may extend into the orbital cavity also (Frontozygomatic suture).

b. ***Internal angular dermoid:*** It is a sequestration dermoid cyst in central position near the root of the nose. It occurs in frontonasal suture line. It is rare. It mimics swelling from *lacrimal sac* or mucocele of frontal sinus. *Mucocele of frontal sinus* is due to blockage of frontonasal duct.

- Dermoid cyst contains putty like desquamated material, hair follicle, sebaceous and sweat glands. It is lined by both dermal and epidermal components.
- Dermoid cyst in skull region has different anatomical types as it often may extend into cranial cavity.

Count your blessing not your problems.

- Cyst which is located entirely outside the skull bone over suture line but without bone indentation.
- Cyst located outside the skull bone but with a bone defect underneath. Bone defect may be either on outer table of skull or through both tables of skull with attachment to dura.
- Cyst lyeing partly outside and partly inside the skull with a connecting stalk between the two like a *dumb bell*.
- Cyst is entirely within the skull bone between skull and dura. It is very rare but known.



Figs 1.154A and B: Types of angular dermoid. (A) External angular dermoid. (B) Internal angular dermoid (midline).

Clinical features

- Painless swelling in the line of embryonic fusion.
- Presents in the second or third decade onwards.
- Smooth, soft, nontender, fluctuant (*Paget's test positive* i.e. swelling is fixed with two fingers and summit is indented to get yielding sensation due to fluid).
- Nontransilluminating.
- Free skin, often adherent into the deeper plane.
- There will be ***resorption and indentation*** of the bone beneath.
- Impulse on coughing may be present only if there is intracranial extension.



Figs 1.155A to C: Postauricular dermoid in different patients.



Figs 1.156A and B: Dermoid in the midline—suprasternal space of burns/sternum. It may extend into deeper plane and so it needs CT chest and evaluation.



Fig. 1.157: Lipoma forehead. It looks like a dermoid.



Fig. 1.158: External angular dermoid, right sided.


1.
1. Cyst outside skull bone
2.
2a.
2b.
2a. Cyst with bone indentation
2b. With dura attachment
3.
3. Cyst connecting inside skull with a stalk
4.
4. Entire cyst is intracranial — very rare

Fig. 1.159: Sequestration dermoid in skull—anatomical types.

Differential diagnosis

- Sebaceous cyst.
- Lipoma.

Investigations

- X-ray—skull or part.
- CT scan head or part.

Complication of sequestration dermoid

- Infection
- Haemorrhage, rupture
- Surface ulceration
- Pressure effects if there is intracavitary extension like into cranial cavity or thoracic cavity, etc.
- Calcification

Treatment

- Excision is done under *general anaesthesia.* Often formal neurosurgical approach is required by raising cranial osteocutaneous flaps.



Fig. 1.160: Dermoid in the ear. It arises due to sequestration at the fusion line of the one of the six developmental ear tubercles (Each ear develops from SIX ear tubercles).

The most valuable diagnostic instrument is passage of time. — **Henry George Miller**

Submental dermoid

- It is a congenital sequestration dermoid occurs during fusion of 1st and 2nd branchial arches. It is deep to deep fascia of neck.
- It presents as soft, cystic, fluctuant, nontransilluminating, swelling in midline in submental region which does not move with deglutition nor moves while protruding the tongue out.
- It should be differentiated from thyroglossal cyst, cold abscess from submental lymph nodes or sebaceous cyst.
- It is excised under general anaesthesia with a curvilinear submental incision.

2. *Tubulodermoids*

It arises from the embryonic tubular structures.
Examples include:

- Thyroglossal cyst.
- Ependymal cyst.
- Postanal dermoid.
- Urachal cyst.

3. *Implantation Dermoid (Figs 1.161 and 1.162)*

- Due to minor pricks or trauma, epidermis gets buried into the deeper subcutaneous tissue which causes reaction and cyst formation (trauma is *forgotten often*). It is an *acquired* cyst.
- It is common in fingers (common in tailors, gardeners), toes and feet.

Clinical features

- Swelling is painless, observed after minor trauma, slowly progressing in fingers or toes.
- It is smooth, soft, mobile, tensely cystic, nontransilluminating and is often adherent to skin.
- It contains only squamous epithelium, without hair follicle/sweat or sebaceous glands.
- Complications are infection, rupture and pressure effect over digital nerves.

Differential diagnosis

- Lipoma, Bursa.

Treatment

- Excision—under local anaesthesia.

4. *Teratomatous Dermoid*

- It arises from all germinal layers ecto, meso and endoderms.
- It occurs in ovary, testis, retroperitoneum, mediastinum.
- It contains hair, teeth, cartilage, sebum and muscle.
- It can be benign or malignant.



Figs 1.161A and B: Implantation dermoid finger and thumb—classical site.



Figs 1.162A and B: Implantation dermoids in the hand and foot.



Fig. 1.163: Dermoid cyst ovary right sided.



Fig. 1.164: Cut section of dermoid cyst ovary showing sebum.



Fig. 1.165: Twisted gangrenous cyst ovary.

SEBACEOUS CYST (WEN, EPIDERMOID CYST)

- It is a *retention cyst.* It is due to blockage of the duct of sebaceous gland, causing a cystic swelling. Sebaceous glands are situated in dermis which secretes sebum through sebaceous duct which opens either directly to skin surface or in to a hair follicle.
- It is common in face, scalp, scrotum.
- *It is not seen in palms and soles* as there are no sebaceous glands.
- Sebaceous cyst contains yellowish white cheesy material with fat and epithelium. It has putty like consistency, with a parasite in the wall of the sebaceous cyst—***Demodex folliculorum***. It is lined by only epidermal layer of squamous epithelium.

Clinical Features

- Painless swelling which is *smooth, soft, nontender, freely mobile, adherent to skin especially over the summit, fluctuant (positive Paget's test), nontransilluminating with punctum over the summit.*
- It moulds on finger indentation.



Figs 1.166A and B: Small sebaceous cysts in face and back with typical punctum over the summit.

The worth of your lives comes neither in what we do nor whom we know but by whom we are.



Figs 1.167A and B: Large sebaceous cyst in the face and scalp. Note the hair loss on the surface.



Fig. 1.168: Infected sebaceous cyst face.



Figs 1.169A and B: Sebaceous cyst showing moulding sign.



Fig. 1.170: *Strawberry scrotum*—multiple sebaceous cysts on the scrotum.

- ***Punctum*** is present over the summit in 70% of cases because here sebaceous duct opens directly into the skin which gets blocked. Punctum is depressed black coloured spot over the summit of the sebaceous cyst. Because of the denuded squamous epithelium (keratin) it is black in colour. In 30% cases sebaceous duct opens into the hair follicle and so punctum is not seen.
  (**Fordyce's disease** is heterotopic sebaceous glands in mucosa of the lip and oral cavity).
- Hair loss over the surface is common due to constant pressure over the roots of the hair follicles.
- Unpleasant odour of sebum content is typical.

Complications

- Infection and abscess formation.
- Surface gets ulcerated leading to formation of a painful, fungating mass with discharge called as—***Cock's peculiar tumour***—often resembles epithelioma. It is a misnomer as it is not a tumour. It is a chronic granuloma on an ulcerated surface of a sebaceous cyst.
- ***Sebaceous horn*** results from hardening of slowly discharged sebum through the punctum. Horn is one which has greater length than its base diameter. Cutaneous horn is keratin deposition.



Figs 1.171A and B: Multiple sebaceous cysts in the scrotum. Occasionally partial scrotectomy is done in these patients.



Fig. 1.172: Sebaceous horn scalp.



Fig. 1.173: Sebaceous horn—nape of the neck.



Fig. 1.174: Multiple sebaceous cysts back.

*If we are to grow good cor n, we must help our neighbours grow good corn.***—Steve Goodier.**

Note:

- Multiple sebaceous cysts may be associated with syndromes like Gardner's syndrome.
- Sebaceous cyst in the scrotum is usually multiple, firm and often calcified without any punctum. It is often treated by partial or total scrotectomy. Scrotum with multiple sebaceous cysts is *strawberry* scrotum.



Figs 1.175A and B: Cock's peculiar tumour over scalp and ear.



Fig. 1.176: Incision for sebaceous cyst is elliptical which includes punctum.



Figs 1.177A and B: Elliptical incision and removal of sebaceous cyst.

Treatment

- Excision including skin adjacent to punctum using elliptical incision—*dissection method*.
- Incision and avulsion of cyst wall.
- If abscess is formed, then drainage initially and later excision is done.
- If capsule is not removed properly the cyst will recur.

GLOMUS TUMOUR

- It is also called as ***glomangioma***.



Fig. 1.178: Glomus tumour in finger tip—subungual region.

- It arises from the cutaneous glomus composed of a tortuous arteriole which communicates directly into the venule (*Sucquet-Hoyer* canal) and these vessels being surrounded by network of small nerves making this lesion very painful. This communication is called as *Sucquet-Hoyer canal*.
- Tumour consists of a mixture of blood spaces, nonmedullated nerve tissue, muscle fibres derived from the wall of the arteriole, with large cuboidal glomus cells—***angiomyoneuroma***.
- They are often seen in limbs and common in nail-beds near the finger tips, as purple red swelling.
- It is 2-3 mm in size.
- It does not turn into malignancy.

Clinical Features

- *Severe burning sensation and pain, out of proportionate to the size. The most common site is nail-bed.*
- Even the slightest pressure will give rise to severe pain. Dilated vessels compress over nerves.
- **It is compressible and pain is more when the limb is exposed to sudden changes in temperature (cold stimulus).**
- On increasing the pressure in the arm above systolic, pain disappears.
- It looks like a *reddish blue spot* which does not blanch on percussion.
- *Subungual* type may not be visible but only to cause episodic digital severe pain.
- It is usually single, but *rarely* multiplicity is observed as familial.

Sequestration dermoid	*Sebaceous cyst*
• Occurs in the line of fusion	• Occurs anywhere except palm and sole
• Skin is not adherent (free)	• Skin is adherent over summit
• Extends often into deeper plane or cavities through suture line	• Subcutaneous plane—do not extend to deeper plane
• Punctum is absent	• Punctum is present—70% cases
• Bone resorption and indentation is common	• Freely mobile without bone resorption
• With restricted mobility	• Superficial swelling, mobile
• Needs proper evaluation with X-ray/CT scan	
• Excision is done under general anaesthesia	• Excision is done under local anaesthesia

Differential Diagnosis

- Pyogenic granuloma—bleeds on touch.
- Subungual melanoma—painless pigmented lesion.

Treatment

- Excision cures the condition.

PAPILLOMA

- It is warty swelling from the skin or often from the mucous membrane.
- It has got a central axis of connective tissue, blood vessels and lymphatics.



Figs 1.179A and B: Pedunculated papilloma. Note the incision for the same.



Fig. 1.180: Pedunculated papilloma with its pedicle.

True Papilloma

- It is a benign tumour with localised overgrowth of *all* layers of the skin. It is commonly pedunculated but rarely can be sessile.
- It contains sweat glands, sebaceous glands and hair follicles.
- Pedunculated papilloma is villous with a central axis of connective tissues, blood vessels and lymphatics.
- Papilloma can be *cutaneous or mucosal*. Cutaneous can be *squamous or basal* cell type. Squamous cell papilloma can be soft which is seen in eyelids in elderly; or can be *congenital* which can be sessile or pedunculated; single or multiple. Squamous papilloma also occurs in oral cavity. *Basal cell papilloma* is oily semitransparent brownish raised seborrhoeic keratotic lesion in skin around trunk of elderly.

Infective Papilloma

Infective papilloma is a warty lesion due to infection, e.g. condyloma acuminata.

Papilloma may be	single. multiple.
Papilloma may be	pigmented. nonpigmented.



Fig. 1.181: Papilloma right waist. Note the warty surface.

> *Look well to this day, for yesterday is but a dream and tomorrow is but a vision. But today, well lived, makes every yesterday a dream of happiness and every tomorrow a vision of hope.* **—Kalidasa**



Fig. 1.182: Papilloma tongue. Note: Papilloma can occur in mucous membrane also like in oral cavity, urinary bladder, gallbladder and rectum.

- True papilloma may turn into squamous cell carcinoma occasionally. There will be sudden increase in size, bleeding or ulceration.
- Papilloma can occur in the breast called as *duct papilloma* which is the most common cause of bloody discharge from the nipple.
- Papilloma can occur in mucous membrane like in *oral cavity, urinary bladder* (transitional papilloma), in the *rectum* (columnar), in the *larynx,* in the *gallbladder* (cuboidal).

Differential Diagnosis

Amelanotic melanoma, pedunculated lipoma, carcinoma.

Treatment

- *True papilloma* is excised with its base along with surrounding 1 cm skin margin.
- *Infective warts* can be treated by excision or CO_2 snow or diathermy coagulation.

Complications of papilloma

- Bleeding
- Malignant transformation
- Ulceration
- Mechanical disability like voice change when it occurs in vocal cord

Fibroepithelial papilloma also called as *skin tags/achrochordon* is very common benign skin lesion of usually 5 mm diameter in size; common in adults; common in neck, axilla, thigh and groin. It is a vascularised keratinised squamous epithelium, can cause local irritation and insignificant bleeding. If it causes cosmetic problem it is removed by laser/cautery or excision.

WARTS

- They are usually multiple hyperkeratotic skin patches with finger like projections, common in children and adolescents.
- They are common in finger tips, face, axilla and sole of the feet. It may be familial but often stimulated by virus.
- They are dry, overgrown projections from the skin of finger often painful, tender and disfiguring. Repeated rubbing may cause infection. It can spread to other fingers and other parts of the body. Kiss lesions can occur.
- Warts attain their size in few weeks and then persist for many months to years. They may regress spontaneously also.
- **Plantar wart (*Verruca plantaris*)** is wart in the sole. Speciality of this is it gets pushed into the sole of the foot due to walking. It is common in ball and heel of the foot. It is pearly white in color with brownish haemorrhagic flecks. It is often covered by apparently normal skin because wart is buried into the skin. It looks like a circular pit. It is grey white finger/filiform like strands in the center of the lesion and is soft. Plantar warts can be multiple. It is painful and very tender on pressing (more than callosity or corns). A defined clear lump may not be felt.
- *Butcher's wart/pathologist's wart/verrucas necrogenica* is due to entry of *Mycobacterium tuberculosis* through broken skin which are common in *milkmaids*. It presents as bluish red warty lesion from which fluid oozes out on pressure between projections. It is common over *dorsum of hand*. Lesion is surrounded by pustules.
- *Senile* warts and *venereal* warts are other types. Venereal warts are same as infective papilloma.
- *Differential diagnoses* are true papilloma, callosities, neurofibromas.
- *Treatment* is excision. Salicylic acid, podophyllin cream applicatins are also used. Laser ablation of warts is commonly advocated.

FIBROMA

It is a benign tumour arising from fibrous tissue. It is capsulated.

Classification of True Fibroma

1. *Soft fibroma*—contains immature fibrous tissue. Common in face, presents as soft brown swelling.
2. *Hard fibroma*—contains well-formed fibrous tissue.

Note:

True fibroma is rare and cannot be diagnosed clinically. It is mostly combined with mesodermal tissues like nerve sheath (neurofibroma), fat (fibrolipoma), muscle (fibromyoma).

Treatment

Treatment of true fibroma is excision.

An entity called ***aggressive fibromatosis*** is known to occur as unencapsulated proliferation of fibrous tissue, common in abdominal and chest wall. It is considered presently *as locally malignant*. It does not spread through lymphatics or through blood. *But recurrence is common.*

Desmoid tumour is a variant of aggressive fibromatosis, seen in females, often associated with Gardner's syndrome (Desmos = tendon, eidos = appearance). *Refer chapter Abdominal Wall and Umbilicus*.

Recurrent fibroid of Paget's is a rare type of fibrosarcoma occurring in a scar tissue after many years.

BURSAE

Bursa is a sac like cavity containing fluid within, which in normal location prevents friction between tendon and bone.

- Minor injuries and pressure leads into bursitis, which will present as a swelling at the site.
- Inflammation of this bursa due to friction causes ***bursitis***, which commonly presents as swelling, pain, and restricted movements.
- Bursa secretes *synovia like clear fluid* in a cavity lined by flat endothelium. It reduces the friction at the site between tendon and bone. Normally fluid content is little to cause a swelling. Minor trauma or infection causes sudden increase in fluid secretion of the bursa making it to enlarge and clinically palpable as pathological bursitis. Bursa is common around knee, elbow, heel and hip.
- Long-standing bursitis leads into thickening of its wall often with calcification making it feel hard with indurated surface. Lining of bursa may become rough or fluid may contain loose fibrinous particles to create *grating sensation* (*crepitus*) on the surface.
- Often overlying skin becomes thick, cracked and horny due to repeated friction and inflammation.
- Bursa may get adherent to deeper tissue as well as overlying skin to make it immobile. Bursa is usually well-localised, smooth, fluctuant, nontender swelling. Often it can be bilateral—in knee or elbow.
- Joint related should be examined. Bursa *may be* communicating with the adjacent joint.
- Gout or rheumatoid arthritis can cause bursa. For example, olecranon bursa can develop in gout patient.
- Bursa should be differentiated from cold abscess, soft tissue tumour, aneurysm, synovial tumour (sarcoma) at different locations.

Complications of Bursa

- Infection of bursa can occur due to trauma to overlying skin or through blood.
- Mechanical disturbances and discomfort.

Management

- US of the anatomical site, X-ray of the part or MRI are very useful.
- Avoiding friction and other aggravating factors may control many bursae.
- Aspiration and steroid injection may be useful.
- Bursa which is felt indurated with thick wall or calcified or infected or attained large size or which interferes with joint movement or daily activities needs surgical excision. Subcutaneous bursa can be excised under local anaesthesia; large or deeper bursa requires general anaesthesia for excision.

Different Types

It can be ***anatomical or adventitious***.

Anatomical

- *Anatomical bursae* are located normally in a particular anatomical site with a purpose of reducing friction. They are commonly deep and adjacent to a bone or joint.
- They become *pathological* and clinically significant when it presents with *bursitis*.
- They are soft, cystic, well localised, nontransilluminating swelling at known anatomical site.
- *Subhyoid bursa*: An horizontally oval swelling situated below the hyoid bone and in front of the thyrohyoid membrane.
- *Subacromial bursa*: In front and lateral to humeral head in relation to supraspinatus tendon between acromion and greater tuberosity of humerus.
- *Bicipito radial bursa.*
- *Olecranon bursa* (*Student's elbow*, *Miner's elbow*): It is subcutaneous bursa in relation to olecranon which becomes distended due to prolonged periods of leaning over elbow. Gout may involve this bursa.
- *Psoas bursa*: A tensely cystic swelling situated beneath and below the inguinal ligament, in the lateral aspect of the femoral triangle. But it will not extend above the inguinal ligament in to the iliac region (unlike in psoas abscess which extends above and is *cross fluctuant*). Psoas bursa lies between the psoas tendon and lesser trochanter. When it is enlarged, it causes diffuse swelling over outer part of femoral triangle lateral to femoral vessels. When hip is moved swelling becomes painful. It also should be differentiated from femoral hernia.
- *Prepatellar bursa* (*Housemaid's knee/miner's beat knee*)*:* It lies subcutaneously in front of lower half of patella and upper half of patellar tendon (upper part) undergoes inflammation in people who do much kneeling. Joint is normal here.
- *Subcutaneous infrapatellar bursa* occurs between skin and lower part of the tibial tuberosity and ligamentum patellae. It is called as *Clergyman's knee*. 'Clergyman' is Christian priest who kneels down during prayer.
- Suprapatellar bursitis is deep to patella and vastus intermedius, in front of lower end of femur. It communicates with knee joint.



Fig. 1.183: Bursa near elbow joint.



Fig. 1.184: Prepatellar (*Housemaid's knee*) and infrapatellar bursae (*Clergyman's knee*).

- *Brodie's bursa* lies deep to medial head of gastrocnemius.
- *Semimembranosus bursa*
- *Bursa anserina*—under the tendons of Guy ropes (sartorius, gracilis and semitendinosus tendons—*Goose's foot*).
- *Retrocalcaneum bursa*—between calcaneum and tendo-Achilis.

Adventitious Bursa

- Adventitious bursa occurs in an *unusual place/site* due to friction/pressure between two layers of tissue. Once it becomes chronic it may get adherent to overlying skin or tissue underneath.
- It may get infected, wall gets calcified, and fluid may become thick. It is well-localised, cystic usually nontender swelling. It becomes painful and tender if infected.
- Lining of bursa may become rough or fluid may contain loose fibrinous particles to create grating sensation/crepitus on the surface.



Fig. 1.185: Location of olecranon bursa (*Student's elbow*).



Fig. 1.186: Adventitious bursa over lateral aspect of foot—a common site.



Fig. 1.187: Common site of adventitious bursa (*Bunion*).

- **Examples**
  - *Bunion* is adventitious bursa in patient with hallux valgus occurring between head of first metatarsal and skin.
  - *Tailor's bursa* occurs between lateral malleolus and skin.
  - *Porter's bursa* occurs between skin over shoulder and clavicle.
  - *Weaver's bursa* occurs between gluteus maximus, ischial tuberosity and skin.
  - *RetroAchillis bursitis* occurs between skin and Achilles tendon.
  - *Subcalcaneal bursitis* occurs between calcaneum and heel in long distance runners.
  - *Billing gate hump* appears over 7th cervical spine deep to overlying skin in people carrying weight over it. Billing gate is a large *fish market* in London.
- Condition should be *differentiated* from soft tissue tumour, sebaceous cyst, ganglion (depending on the location of bursa).
- **Management**: X-ray of the part and FNAC of swelling should be done. Later it is excised usually under local anaesthesia.

SEMIMEMBRANOSUS BURSA

It is a cystic swelling in the *upper medial* aspect of the popilteal fossa under the semimembranosus tendon. It is said to be due to friction under the tendon causing bursitis.

Features

- It is located between semimembranosus tendon and femoral condyle *above* the knee joint line.
- It is *common* in young adult; in *both* sexes. It is *most common* swelling of the popliteal fossa.
- It is nontender, cystic/tensely cystic (firm) swelling located above and on medial aspect of the popliteal fossa, fluctuant, noncompressible, often transilluminating, often with a fluid thrill. When it enlarges it comes out of semimembranosus tendon to become subcutaneous.
- Content of bursa *does not* communicate with knee joint. So fluid cannot be reduced into the joint cavity; but often appears *flaccid* on flexion of knee or by firm pressure probably due to displacement of fluid into deeper recesses of the bursa. The swelling becomes *tense* when knee is extended.
- Knee joint is *normal.*



Fig. 1.188: Semimembranosus bursa typical location.



Figs 1.189A and B: Semimembranosus bursa—typical location. On flexion it only becomes flaccid but *does not disappear.*



Fig. 1.190: Semimembranosus bursa on table look.

Differential Diagnosis

- Baker's cyst, popliteal aneurysm.

Treatment

- Ultrasound of popilteal fossa shows the cystic swelling under semimembranosus tendon.
- X-ray knee joint is normal.
- Excision is done under general anaesthesia using tourniquet. Complete excision of the sac is needed to prevent recurrence.

MORRANT BAKER'S CYST

It is a cystic swelling containing gel like fluid in the *lower midline* of the popliteal fossa. It occurs due to herniation of the synovial membrane of the knee joint as a result of chronic arthritis.

- It is *pulsion/pressure diverticulum* of the synovial membrane towards surface under the gastrocnemius through an opening in the joint capsule. It is *below* the joint line.

Clinical Features

- It is common in middle-aged individuals.
- It is smooth, soft and cystic, nontransilluminant, often tender swelling located below (the joint line) and in midline of the popilteal fossa.



Fig. 1.191: Morrant Baker's cyst—typical location.

- On flexion swelling *disappears* and on extension swelling *increases* in size.
- Pain and tenderness are present in knee joint with effusion showing positive patellar tap.
- The knee joint movements are painful and restricted.
- Baker's cyst may *rupture* sometimes causing severe sudden pain and swelling in the calf mimicking *deep vein thrombosis.*

The mother's heart is child's schoolroom.—**Henry Ward Beecher.**



Figs 1.192A and B: Baker's cyst. It is below the joint line.

Differential Diagnosis for Baker's Cyst

- Semimembranosus bursa.
- Thrombosed popliteal aneurysm (often bilateral).

Management

- X-ray of joint shows arthritic changes.
- MRI may be needed occasionally.
- Arthritis is treated and Baker's cyst is excised under *general anaesthesia in prone* position.

LYMPH CYST (LYMPHATIC CYST)

- It is an *acquired type* of *distension cyst* wherein lymphatics form a localised swelling with a capsule around it.
- It usually occurs in subcutaneous plane, which is smooth, soft, nontender, mobile, and brilliantly transilluminant. It is usually not adherent to the skin.
- **Common sites** are neck and limbs.
- It can get infected and form an abscess.



Fig. 1.193: Lymph cyst, which is transilluminant. It is an acquired condition.

Differential Diagnosis

- Cold abscess, dermoid cyst.

Treatment

- Excision.

LYMPHANGIOMA

It is congenital localised clusters of dilated lymph sacs in the skin and subcutaneous tissue that has failed to join the normal lymph system during development period.

Types

Capillary Lymphangioma

- It is simple type which can be present at birth but noticeable skin vesicles often develop in few years.
- It is common at the junction of body to limbs-like near shoulder, axilla, groin or buttock.
- Skin vesicles contain clear watery or yellow fluid. Bleeding within the vesicle may turn it into brown or black. Its features includes multiple, indistinct white/brown/black coloured vesicles of 0.5 to 4 mm size at typical locations in children involving around 5-20 cm area of skin in the particular location.
- If it is less than 5 cm in size it is called *as lymphangioma circumscriptum*.
- If it is more than 5 cm in size it is called as *lymphangioma diffusum*.
- If it is with reticulated ridges, it is called as *lymphoedema ab igne*.
- Area is soft, spongy, often fluctuant with fluid thrill and translucency. It is not compressible. Vesicles will not fade on pressure.
- Often lesion may get infected to make it painful and tender.
- Condition will not block the lymph drainage in normal lymphatics and skin oedema is absent.
- Regional lymph nodes are not enlarged.



Fig. 1.194: Lymphangioma circumscripta (*Courtesy*: Balasaraswathy, MD, Consultant Dermatologist, Mangalore)

Cavernous Lymphangioma

- It is soft, lobulated, fluctuant, *brilliantly transilluminant* larger lymphatic swelling with often multiple communicating lymphatic cysts.
- It often extends into deeper plane like muscle. It is common in face, mouth, lips *(macrocheilia*), tongue *(macroglossia*).

Cystic Hygroma

It is collection of clustered sequestered lymph sacs (occurring during developmental period *in utero*) presenting in newborn as large swelling which is soft, smooth, fluctuant, brilliantly transilluminant, and *compressible* (For detail refer chapter 5, Neck).

CALCINOSIS CUTIS

- It is a type of calcification (*dystrophic*) in or under the skin. Usually presents as a circumscribed lesion in the skin.
- Commonly seen in females. Common site is in the waist (Fig. 1.195)
- Usually bilateral.
- It is said to be due to friction causing degeneration of skin and immediate deeper structure with increased local alkalinity of the tissue causes precipitation of the calcium leading to solid, hard, swelling in the skin. Cut section shows hard, yellowish material.
- It may mimic calcified lipoma or neurofibroma.
- **Treatment** is excision and closure of defect often with local flaps.



Fig. 1.195: Calcinosis cutis near waist is a common site. It is common in females.

NEUROMA

Two types of neuromas are found.

- **False neuroma.**
- **True neuroma.**

False Neuroma

- It occurs due to injury to the nerve either after trauma or amputation which presents as a tender swelling.
- It arises from the connective tissue of nerve sheath.
- It contains fibrous tissue with coiled nerve fibres.
- It can be ***end neuroma,*** commonly seen in amputation stump as a tender localised firm swelling often adherent to the stump scar. It can cause neuralgia in the stump. It prevents the proper usage of prosthesis. So during amputation, nerve should be pulled down and cut so as to make cut end to retract more proximally, which prevents the formation of neuroma.
- It can be ***lateral (side) neuroma*** which is observed after partial nerve injury, usually after trauma. It presents as a tender, firm swelling along the line of the peripheral nerve.



Figs 1.196A and B: Types of false neuromas: (A) End neuromas: (B) Lateral neuromas.

True Neuroma

- It is a rare tumour.
- It occurs in connection with sympathetic system.

Types

Ganglioneuroma

- It contains ganglion cells and nerve fibres.
- It occurs in connection with sympathetic chain. So it is observed in neck (parapharyngeal mass), thorax, retroperitoneum, adrenal medulla.
- It is relatively benign and symptomless and often attains a large size.
- Early complete excision can give a cure.

Neuroblastoma

- It is poorly differentiated, aggressive, embryonic type of tumour.
- It is seen in infants and children.
- It spreads through blood but can go for spontaneous remission occasionally.

Myelinic Neuroma

- It contains only nerve fibres.
- Ganglion cells are absent.
- It occurs in spinal cord or pia mater.

Move to the rhythm of soul and you'll never miss a beat.—**Vicki Virk**

NEUROFIBROMA

- **It is a benign tumour arising from connective tissue of the nerve containing ectodermal neural and mesodermal connective tissue components.**
- It can be single or multiple. Neurofibromas may be associated with pheochromocytomas, hypertension and few syndromes.



Figs 1.197A and B: Multiple neurofibroma.



Figs 1.198A and B: Patient with multiple neurofibromatosis underwent laparotomy showing serosal neurofibroma.



Figs 1.199A and B: Plexiform neurofibroma in the (A) Face and neck; and (B) Buttock.



Fig. 1.200: Plexiform neurofibromatosis involving trigeminal (5th cranial) nerve.



Fig. 1.201: Plexiform neurofibroma involving ophthalmic division of trigeminal nerve.

Sites

- Cranial.
- Spinal. Neurofibroma is the most common intradural extramedullary spinal tumour.
- Peripheral.

Types

- ***Nodular neurofibroma:***
  - It presents as single smooth, firm, tender (often) swelling which moves horizontally or perpendicular to the direction of the nerve, not in the direction of the nerve.
  - There is pain and hyperaesthesia in the distribution of the nerve.
- ***Plexiform neurofibroma:***
  - It commonly occurs along the distribution of 5th cranial nerve in the skin of face. It often occurs in the cutaneous distribution of the peripheral nerve.
  - It attains enormous size with thickening of the skin which hangs downwards. It causes erosion into the bone, orbit and deeper structure.
  - It may also undergo myxomatous degeneration. It causes cosmetic problem.
  - Paraesthesia along the distribution of the trigeminal nerve (commonly ophthalmic division) is common.
  - **Pachy dermatocele**—a variant of plexiform neurofibroma where neck is involved. There is thickening and oedema of skin, pigmentation, thromobosed veins with enormous proliferation of subcutaneous nerve fibers causing *folded pendulous hanging thickened skin* with tissues. It is *common* along trigeminal (5th cranial) nerve; rarely is it seen in limbs and scalp skin.



Fig. 1.202A



Fig. 1.202B

Figs 1.202A and B: Multiple neurofibromatosis with café-au-lait spots in the skin.

- ***Generalised neurofibromatosis (von Recklinghausen's disease*)**: (1:4000 births)
  - It is an inherited autosomal dominant disease wherein there will be multiple neurofibromas in the body—chromosome 17. It is called as type 1 in which more than 50% will be familial. *Type 1*, more commonly, called as *von Recklinghausen's* disease. Type 2 is *acoustic neurofibromatosis* (mutation of chromosome 22). All layers of nerve with Schwann cells and fibroblasts show tumour proliferation.
  - It may be cranial, spinal or peripheral.
  - It is associated with pigmented spots (coffee coloured) in the skin, commonly seen on the back, abdomen, thigh ***(café au lait spots)***. More than 5 in number, with each 1.5 cm or more in size is significant. *Café-au-lait* signifies common neuroectodermal origin of nerve sheath cells and melanocytes.
  - *Axillary/groin freckles and Lisch nodules,* pigmented iris, hamartoma may be present.
  - Neurological disturbance is uncommon.
  - It may be associated with MEN type IIb (Multiple neurofibromas of eyelids, lips, and face; medullary carcinoma of thyroid; pheochromocytoma, hyperparathyroidism), primary brain tumours and bone cysts.
- ***Elephantiatic neurofibromatosis***:
  - It is of congenital origin. It involves limbs.
  - Skin of the limb is greatly thickened, dry and coarse.
- ***Cutaneous neurofibromatosis*:**
  - They are small, multiple, firm/hard nodules arising from terminal ends of dermal nerves. Overlying skin is normal without any changes. It commonly occurs all over the body. It can be pedunculated or sessile. It can occur in scalp to result in a *turban tumour.*

Clinical Features

- Mild pain or painless swelling usually in subcutaneous or cutaneous plane with tingling, numbness and paraesthesia along the distribution of nerve.

- Round/oval/fusiform swelling along the peripheral/cutaneous nerves which moves perpendicular to the direction of the nerve but not along the longitudinal direction of nerve fibre with smooth surface and firm consistency. It is nontender or mild tenderness may be present. Skin is free unless it is of cutaneous type. Cutaneous type is often soft.

Complications

- Cystic degeneration.
- Haemorrhage into the tissues.
- Spinal and cranial neurofibromas can cause neurological deficits.
- Erosion into deeper planes, bone, orbit.
- Muscle atrophy.
- Spinal dumbbell tumour can cause compression of spinal cord and paralysis of the limb.
- *Sarcomatous changes*: Common in generalised type (5%). When it occurs it shows rapid enlargement, warmness, more vascularity with dilated veins. Secondaries in lungs can occur through blood spread.

Note:

- *The most common* spinal tumour is neurofibroma.
- von Recklinghausen disease of *primary hyperparathyroidism* is different as it is due to raised PTH level causing *osteitis fibrosa cystica*.
- Familial type of neurofibroma may be associated with *scoliosis*.
- Café-au-lait spots is also seen in *McCune Albright* syndrome.

Treatment

- Excision.

Indications

- Symptomatic neurofibroma—pain and pressure symptoms
- Cosmetically problematic lesion
- Recent increase in size
- Malignant transformation 5%

Remember about neurofibroma

- Neurofibroma is fusiform swelling which has got horizontal mobility but not longitudinal mobility (neurilemmoma has got free mobility in all directions)
- Café au lait spots signify common neuroectodermal origin of nerve sheath and melanocytes
- Kyphoscoliosis may be an association in familial variety
- Phaeochromocytoma with hypertension may be an association (20%)
- *Plexiform neurofibromatosis* commonly involves trigeminal cranial nerve mainly ophthalmic division causing paraesthesia, can obstruct the vision when it is large, have grossly thickened pendulous skin hanging down to various levels
- Calcification, saponification, myxomatous changes, sarcomatous transformation (fungation, rapid recent increase in size, warmness, dilated surface veins, redness with increased vascularity, fixity, persistent severe pain, immobility, lung spread) and cosmetic problem are the complications
- Intestinal neurofibroma may precipitate intussusception

NEURILEMMOMA (SCHWANNOMA)

It is arising from Schwann (neurilemmal cells) cells. They are lobulated, encapsulated, soft, whitish grey in appearance. They displace the nerve from which they arise and can be removed. They are common in acoustic nerve (cerebellopontine angle) but also can occur in a peripheral nerve. Occasionally they are multiple. Calcification is common. It is *ectodermal* in origin.



Fig. 1.203: Lingual schwannoma (*Courtesy:* Dr Harish Rao, Professor in Surgery, KMC, Mangalore).



Fig. 1.204: Schwannoma in the forearm.



Figs 1.205A and B: Neurilemmoma—gross look and cut section.

Two types:

Anthony A—Two rows of spindle cells with central acellular area (Verocay bodies).

Anthony B—Acellular myloid areas.

Presentation is pain along the distribution of the nerve, hyperaesthesia and tenderness and as, soft or firm, lobulated, well localised mobile swelling.

Treatment

- Excision—easier without causing neurological damage.

Recurrent schwannoma could be malignant.

GANGLION

It is a cystic swelling occurring in relation to tendon sheath or synovial sheath or joint capsule. It contains clear gel like fluid.



Figs 1.206A and B: Ganglion over the dorsum of the wrist—typical location. It can occur over the flexor aspect also. It can be transilluminant also.



Fig. 1.207: Ganglion over the wrist.

Common sites

- Dorsum of wrist (Near scaphoid-lunate articulation)
- Flexor aspect of wrist
- Around ankle joint—occasionally

Pathogenesis

- Cystic degeneration of the tendon sheath.
- Leakage of synovial fluid through joint capsule.
- There are small islets of microspaces in synovial sheath which often fuse together or one of them gets enlarged to form ganglion.

Clinical Features

- Well-localised swelling which is smooth, soft, cystic, or tensely cystic, (Paget's test is +ve), nontender, transilluminant. It is mobile but mobility is restricted when tendon is contracted against resistance.
- Occasionally it is communicating with joint capsule.
- Often pain, tenderness and restricted joint movement may be the presentation (but rare).

Differential Diagnosis

- Lipoma.
- Lymph cyst.
- Sebaceous cyst.
- Small ganglion often mistaken for sesamoid bone or exostoses.
- Bursa.

Treatment

- Asymptomatic ganglion is better left alone because of high recurrence rate.
- **Excision.** Usually done under local anaesthesia (lignocaine plain 2%). Patient should be explained of **high recurrence** rate (30%). After excision always it should be sent for histopathology. Firm crepe bandage application for 4 weeks is better in these patients.
- Aspiration and sclerosant injection may be useful.

(In olden days people used to rupture the ganglion using bible book).

CHORDOMA

Tumour arising from the remnants of notochord.
It is seen in:
  - Sacrococcygeal region.
  - Sphenoid sinus region.
  - Around the foramen magnum.

- It invades into the surrounding structure like nerves.
- Resection is difficult.
- Radioresistant.

EPIGNATHUS

This is a type of growth anomaly seen in neonates wherein growth from the base of skull protrudes through the mouth.

We seldom think of what we have, but always of what we lack.



Fig. 1.208: Epignathus.

Note:

- *Enucleation* is removal of the swelling within the tissue of origin with normal part of tissue of origin is being retained, e.g. enucleation of prostate in benign prostatic hyperplasia (BPH).
- *Excision* is removal of tissue/tumour entirely with its capsule.
- *Wide excision* is removal of tumour with surrounding tissue margin adequately for clearance.
- *Compartment excision* is removal of tumour/diseased tissue with all adjacent soft tissues in one compartment except neurovascular bundle. It is done in limbs for soft tissue sarcoma as a curative but limb saving procedure.
- *Radical excision/radical block dissection* is removal of tumour widely with adjacent soft tissues with lymph node dissection.


Elliptical incision partially occupying the swelling – includes the punctum in this
Straight incision over swelling
Elliptical incision occupying the entire swelling (circumferential)

Fig. 1.209: Different incisions used in surgical approaches to remove swelling.

Swellings which are cross fluctuant

- Psoas abscess
- Bilocular hydrocoele
- Ranula (plunging)
- Compound palmar ganglion

F. Electrolyte and Nutrition

CHAPTER OUTLINE

- Normal Physiology
- Water Loss
- Water Excess
- ECF Loss
- ECF Excess
- Hyponatraemia
- Hypernatraemia
- Hypokalaemia
- Hyperkalaemia
- Hypermagnesaemia
- Hypomagnesaemia
- Acid-Base Balance
- Metabolic Alkalosis
- Respiratory Alkalosis
- Metabolic Acidosis
- Respiratory Acidosis
- Anion Gap
- Fluid Therapy
- Nutrition
- Gastrostomy
- Jejunostomy
- Total Parenteral Nutrition
- Refeeding Syndrome
- Obesity and Morbid Obesity

NORMAL PHYSIOLOGY

Total body water is 60% of body weight in males, 50% of body weight in females, i.e. 30 litres.

- Intracellular water—20 litres (2/3).
- Extracellular water—10 litres (1/3).
  - Plasma (1/4) (2.5 litres).
  - Interstitial fluid (7.5 litres).

Ion	*ICF*	*ECF and plasma*
Sodium	10 mmol/L	140 mmol/L
Potassium	150 mmol/L	4.5 mmol/L
Chloride	Trace only	105 mmol/L

ECF volume and osmolality regulation is controlled by three hormones. Aldosterone, ADH, atrial natriuretic hormone.

WATER LOSS (VOLUME LOSS)

It is decrease in the whole body fluid volume which includes both ECF and ICF. It is usually ECF loss which is more important and assessed. It can be *isotonic volume depletion* with both salt and water loss leading into *hypovolaemia*, or *only water loss* with only minimal loss of electrolytes leading into *dehydration*.

Causes and Features

- *Isotonic volume depletion* occurs due to diarrhoea, vomiting, and excess diuresis. Here normal or decreased sodium is observed. Fluid loss is only of ECF and so early intravascular volume reduction occurs. This causes hypotension and decreased tissue perfusion. Features are—dry tongue, rapid pulse, cold clammy extremities, sunken eyes, hypotension, oliguria, raised blood urea, decreased urinary sodium. Hypovolaemia can be mild (< 2l fluid loss); moderate (2-3 L fluid loss); severe (>3 L fluid loss).
- *Only pure water* loss occurs due to poor fluid intake and diabetes insipidus. It causes dehydration with proportionate decrease in total body water (2/3rd ICF, 1/3rd ECF). As ECF including intravascular fluid loss is less, hypotension is less. Features here are—severe thirst, confusion and convulsions due to hypernatraemia; blood pressure is relatively normal. Dehydration can be mild (weight loss 5%); moderate (10%); severe (15%).

Management

- Evaluation is done by doing serum sodium, urinary sodium, and blood urea.
- Isotonic volume depletion is corrected by 0.9% normal saline.
- Pure water depletion is corrected by more water intake/intravenous 5% dextrose.
- Monitoring fluid therapy by skin and tongue examination, weight gain, pulse, blood pressure, CVP, PCWP.

WATER EXCESS (ECF VOLUME EXCESS)

It can be divided into *water and salt excess* or *predominantly water excess* called as *water intoxication*.

Water and salt excess occurs in CCF, cirrhosis, nephrotic syndrome, hypoproteinaemia, renal failure, excessive saline infusion.

Water intoxication occurs in TURP, excess infusion of 5% dextrose only, SIADH secretion, psychogenic polydypsia. It is managed by stopping fluid infusion or procedure (TURP); fluid restriction, and treating the cause.

You cannot harm a bandaged wound.— **Croatian Proverb**

Causes

- Excessive amount of intravenous dextrose (5%).
- During colorectal bowel wash for preparation of large bowel for surgery, if water is used instead of saline, especially in children.
- In TURP (Transurethral resection of prostate) when excess irrigating fluid water or glycine is used (commonly used).
- In syndrome of inappropriate antidiuretic hormone (SIADH) which is commonly associated with lobar pneumonia, empyema, oat cell carcinoma and head injury.

Clinical features

- Drowsiness, weakness
- Convulsions and coma
- Nausea, vomiting
- Passage of dilute urine
- Distended neck veins
- Pedal oedema
- *Gain in body weight*—most sensitive and consistent sign
- Circulatory overload—tachycardia, pulmonary oedema, hypertension
- Bilateral basal crepitations, ascites
- Raised CVP, PCWP

Investigations

- Haematocrit and sodium level (will show fall in level).
- Low potassium. Low blood urea.

Treatment

- Water and salt restriction and observation.
- Monitoring in ICU.
- Management of fluid and electrolyte balance.
- Infusion of hypotonic sodium chloride.

Administration of diuretics and hypertonic saline should be avoided, as it may cause rapid changes in serum sodium and water level which will lead to neuronal demyelination and *fatal outcome.*

ECF LOSS

- Here only ECF loss is present with normal ICF.
- It is seen in vomiting, diarrhoea, intestinal obstruction.
- Treatment is infusion of normal saline.

ECF EXCESS

- Only ECF excess without an ICF excess.
- Excessive infusion of saline with impaired excretion.
- Raised JVP (earliest and best clinical sign), cardiac failure and peripheral oedema.
- Treatment is fluid restriction and diuretics like frusemide.

HYPONATRAEMIA

Sodium level less than 130 mEq/litre. Hyponatraemia is said to be *severe* if serum sodium becomes lesser than 100 mEq/L in acute type; and lesser than 115 mEq/L in chronic type.

It can be due to water overload (dilutional) or sodium loss.

Types of Hyponatraemia

- Acute—presents as neurological manifestations
- Chronic—causes pontine myelinolysis. It presents as behavioural changes, progressive weakness, and cranial nerve palsies.

Types also may be:

- *Hypervolaemic hyponatraemia* wherein rapid absorption of fluid occurs into intravascular compartment leading into pulmonary and cerebral oedema. It is due to decreased osmolality causing movement of ECF into the cells. Serum sodium level lesser than 100 mmol/L is called as severe hyponatraemia, causes convulsions. Here urinary sodium will be less than 15 mmol/L. Acute hyponatraemia is corrected by fluid restriction, hypertonic saline, loop diuretics like frusemide. Monitoring the serum sodium level of the patient is essential. Sodium should be corrected up to above the level of 125 mmol/L. Correction should be slow and gradual at a rate of 2 mEq/L/hour with up to 20 mEq/L correction in 24 hours with 4th hourly assessment of serum sodium. Overcorrection of sodium should not be done. Rapid correction can lead into *irreversible myelin lysis of pontine*.
- *Hypovolaemic hyponatraemia:* It is due to hypovolaemia by diarrhoea, vomiting, wherein urine sodium level is less than 20 mmol/L; due to diuresis or renal causes wherein urine sodium level is more than 20 mmol/L or it may be due to correction of hypovolaemia using hypotonic fluid like 5% dextrose. Condition can be treated well using isotonic normal saline.
- *Normovolaemic hyponatraemia:* It may be due to renal failure or syndrome of inappropriate ADH secretion (SIADH). In mild asymptomatic patients it is corrected by fluid restriction (1 litre/day will raise the serum Na). Vasopressin antagonist *demeclocycline* which increases the diluting ability of kidney is used in severe cases.
- *Pseudohyponatraemia:* Plasma osmolality is mainly achieved by serum sodium; but small proportion, i.e. 25% of osmolality is due to other solutes like glucose, lipids, plasma proteins, urea which will not move easily between intracellular and extracellular spaces. When concentration of these molecules raise due to some pathology, proportionately relative concentration of sodium will drop causing pseudohyponatraemia. Here condition causing related to specific solutes mentioned above is treated, than hyponatraemia.

Causes

- Intestinal obstruction.
- Intestinal fistulas—biliary, duodenal, gastric, pancreatic.
- Gastric outlet obstruction with severe vomiting.
- Ryle's tube aspiration.
- Severe diarrhoea due to viral cause, in colitis, colorectal polyps.
- Syndrome of inappropriate antidiuretic hormone (SIADH).
- Immediately after surgery and trauma, sodium depletion occurs.
- Stroke.

Clinical features

- *Dry coated tongue*
- *Sunken eyes*
- *Dry wrinkled skin*
- *Hypotension*
- *Dark scanty urine*
- *Irritability, disorientation and neurological manifestations*
- *Convulsions*
- *In chronic hyponatraemia—hypothermia, reduced tendon reflexes, pseudobulbar pasly*

Investigations

- Serum electrolytes. Urinary sodium is low.
- Sodium *deficit* is calculated by: (125 – present serum sodium) × body weight in kg × 0.6.

Treatment

- Intravenous infusion of normal saline as a slow and gradual correction at a rate of 2 mEq/L/hour in acute cases and < 1 mEq/L/hour in chronic cases. Correction should not exceed more than 20 mEq/L/day in acute cases and more than 10 mEq/L/day in chronic cases. Hypertonic saline of 1.6% or 3% also can be used in severe cases. 0.9% normal saline contains 154 mEq of NaCl; 3% saline contains 500 mEq of NaCl.
- The cause is treated.

HYPERNATRAEMIA

Serum sodium level > 150 mEq/L. Excess infusion of normal saline causes overload in circulating salt and water. It is usually due to water deficit.

Causes

- Renal dysfunction.
- Cardiac failure.
- Drug induced like NSAID, corticosteroids.

It may be either primary sodium excess or primary potassium excess or primary water deficit.

Types of Hypernatraemia

- *Euvolemic* (pure water loss): It is due to failure of water intake like in comatous patients, bedridden people, postoperative patients and in patients with high fever leading into extrarenal loss of water. It can occur in diabetes insipidus or chronic renal failure as renal loss of water.
- *Hypovolaemic* (among loss of water and sodium, more water is lost than sodium): It is due to vomiting, diarrhoea, more undue sweating (extrarenal); osmotic diuresis by glucose/mannitol (renal).
- *Hypervolaemic* (both sodium and water gain but sodium gain is more than water gain) as seen in more salt intake, excess steroids, sodium bicarbonate/hypertonic saline infusion (salt gain).

Clinical Features

- Pitting oedema.
- Puffiness of face.
- Increased urination.
- Often dilated jugular veins.
- Features of pulmonary oedema.

Investigation

- Serum electrolytes, plasma and urine osmolality, renal function tests, haematocrit.

Management

- Restriction of saline and sodium. Treatment of pulmonary oedema.
- *Hypernatraemia should be corrected slowly as follows:*
  - Initial infusion of normal saline, then infusion of half strength saline (0.45%) and later with 5% dextrose, i.e. gradual controlled correction is done. Otherwise cerebral oedema and hyperglycaemia can develop.
  - Oral and nasogastric administration of water/fluids.

HYPOKALAEMIA

Sudden Hypokalaemia

Serum potassium level less than 3.5 mEq/L.

It occurs in patients in diabetic coma treated by insulin and saline infusion.

Gradual Hypokalaemia

Causes

- Diarrhoea of any causes, villous tumour of the rectum, ulcerative colitis.
- After trauma or surgery.
- Pyloric stenosis with gastric outlet obstruction.
- Duodenal fistula, ileostomy.
- After ureterosigmoidostomy.
- Insulin therapy.
- Poisoning.
- Drugs like beta agonists.
- Familial periodic paralysis.

Clinical Features

- Slurred speech.
- Muscular hypotonia—physical sign.
- Depressed reflexes.
- Paralytic ileus.
- Weakness of respiratory muscles.
- Cardiac arrhythmias.
- Inability to produce concentrated urine and so causes nocturia and polyuria.

ECG shows prolonged QT interval, depression of the ST segment and inversion of T wave, prominent U wave.

Often hypokalaemia is associated with *alkalosis.*

Serum potassium will be decreased.

Treatment

- Oral potassium 2 g 6th hourly, 15 ml potassium chloride syrup (20 mmol of K).
- IV KCl 40 mmol/litre given in 5% dextrose or normal saline *slowly*, often under ECG monitoring [Total dose is 40 mmol (0.2 mmol /kg/hour). Maximum dose per hour is 20 mmol].
- *Hypokalaemic alkalosis which occurs in pyloric stenosis* should be treated carefully by IV potassium as there will be severe potassium loss.

HYPERKALAEMIA

Normal range of potassium is 4.0 to 4.5 mEq/litre.

Hyperkalaemia manifests when potassium ***exceeds 6 mEq/litre.***

Causes

- Renal failure.
- Rapid infusion of potassium.
- Transfusion of stored blood.
- Diabetic ketoacidosis.
- Adrenal insufficiency.
- Potassium sparing diuretics, cyclosporine, beta blockers.
- Metabolic acidosis.
- Insulin deficiency.
- Tissue destruction, burns, trauma, tumour necrosis, crush injury.
- *In vitro* haemolysis, thrombocytosis, tourniquet application, exercise—pseudohyperkalaemia.
- Familial hyperkalaemic periodic paralysis.

Potassium excess is a dangerous condition which can cause sudden cardiac arrest.

Investigations

High serum potassium level. Peak 'T' wave in an ECG.

Treatment

- IV administration of 50 ml of 50% glucose with 10 units of soluble insulin, slowly.
- Infusion of 10% calcium gluconate (as cardioprotection) intravenously.
- Calcium chloride is given in severe cases as calcium in this form is released immediately without hepatic metabolism.
- Diuresis using frusemide injection.
- Haemodialysis when required—very useful.
- Continuous ECG monitoring is a must.
- Polyesterene sulphonate ion exchange resin 30 g/hour in 50 ml of 70% sorbitol as an enema.
- Salbutamol nebulisation or intravenously 0.5 mg in 4 ml of saline/Albuterol nebulisation.
- IV sodium bicarbonate—shifts potassium in to cells. 7.5%, with 50-100 ml intravenously in 10 minutes.

HYPERMAGNESAEMIA

It is rare. Serum magnesium > 2.5 mEq/litre.

Normal *serum magnesium* is 1.5-2.5 mEq/L and intracellular magnesium which is more (2nd higher) is 26 mEq/L. Magnesium is mainly deposited in bone (60%). It is a cofactor for many enzymes necessary in phosphorylation of glucose in the cell and ATP utilisation in muscle fiber. Daily required dietary intake of magnesium is 0.4 gram. It is reabsorbed well in proximal renal tubule.

Causes

- Advanced renal failure treated with magnesium containing antacids, diabetic ketoacidosis.
- Intentionally produced hypermagnesaemia while treating pre-eclampsia.

Clinical Features

- Loss of tendon reflexes (most common).
- Neuromuscular depression.
- Flaccid quadriplegia.
- Respiratory paralysis.
- Somnolence.
- Hypotension.

HYPOMAGNESAEMIA

- Serum magnesium < 1.5 mEq/litre.

Causes

- Malnutrition, alcohol.
- Large GI fluid loss.
- Patients on total parenteral nutrition.

Clinical Features

- Hyperreflexia.
- Muscle spasm.
- Paraesthesia.
- Tetany.
- It mimics hypocalcaemia. It is often associated with hypokalaemia and hypocalcaemia.

Treatment

Two gram (16 mEq) of magnesium sulphate slow intravenously, in 10 minutes. Later maintenance dose of 1 mEq/kg/day as slow continuous infusion is given/oral magnesium is needed.

ACID-BASE BALANCE

Normal pH (– log 10 of H^+) is 7.36-7.44.

Factors which control the pH

- *Buffer system*
  - Bicarbonate buffer
  - Protein buffer
  - Phosphate buffer
- *Renal control of pH*
- *Respiratory control of pH*

Note:
When H^+ increases pH decreases.

An *acid* is a substance that dissociates water to release hydrogen ion. A *base* is a substance that takes hydrogen ion. A *buffer* is a combination of weak acid and conjugate base. These buffers maintain the H^+ concentration in blood within fine limits. Natural buffers are *extracellular or intracellular*. Bicarbonate/carbonic acid buffer, phosphate buffer and plasma proteins are *extracellular* natural buffers. Haemoglobin and other proteins are *intracellular* buffers. Bicarbonate/carbonic acid buffer is most important as carbonic acid levels are regulated by lungs which eliminates excess of it as CO_2. Bicarbonate part is separately controlled by kidney.

Acidosis is pH of blood less than 7.35. Alkalosis is pH more than 7.45.

Henderson Equation (Used to Assess Hydrogen Ion Concentration)

$$H^+ \text{ (nmol/L)} = \mathbf{K} \times \frac{H_2CO_3 \text{ mmol/L}}{HCO_3^- \text{ mmol/L}}$$

$$\text{OR} \quad \mathbf{K} \times \frac{\alpha\ PCO_2}{HCO_3^- \text{ mmol/L}}$$

Here constant **K** is 800 (for H_2CO_3 / HCO_3 buffer).

Carbonic acid (H_2CO_3) is solubility coefficient of CO_2 in blood (α) multiplied by partial pressure of CO_2 (PCO_2). α is 0.03 ml/mmHg/100 ml of blood; PCO_2 is 40 mmHg. $H_2CO_3 = \alpha PCO_2 = 0.03 \times 40 = 1.2$ ml. Normal blood bicarbonate/ HCO_3 level is 24 mmol/L. so $\mathbf{H^+}$ is 800 × 1.2 divided by 24 = 40 mmol/L.

Henderson-Hasselbalch Equation (Used to Assess pH)

It is used to find out pH of the blood using logarithm. Negative logarithm of constant K (800 for carbonic buffer) is called as pKa. It is 6.1 for H_2CO_3 / HCO_3 buffer system.

$\mathbf{pH} = \text{pKa} + \log \frac{HCO_3^-}{H_2CO_3}$ means 6.1 + log 24 divided by 1.2 = 6.1 + log 20 = 6.1 + 1.3 = 7.4

METABOLIC ALKALOSIS

Primary base excess, i.e. HCO_3. *A standard bicarbonate above 27 mmol/litre.*

Causes

- Repeated vomiting due to any cause. Commonly seen in cases of pyloric stenosis. Here ***hypokalaemic alkalosis*** occurs which is an important aspect for managing the patient.
- Excess alkali ingestion, e.g. antacids.
- Cortisol excess either due to over administration or Cushing's syndrome.

Clinical Features

- Cheyne stokes breathing with period of apnoea of 5-30 seconds.
- ***Tetany*** due to alkalosis. More often *latent tetany* which is revealed by *Trousseau's sign.*

Investigations

Serum electrolytes, arterial blood gas analysis.

Treatment

- Normal saline or double strength normal saline IV infusion, with slow IV potassium chloride 40 mmol/litre in saline, slowly under ECG monitoring.
- pH more than 7.7 causes life-threatening alkalosis which requires rapid correction by infusing dilute hydrochloric acid or ammonium chloride, however, with care and monitoring.

RESPIRATORY ALKALOSIS

Arterial PCO_2 is below normal.

Causes

- Hyperventilation during anaesthesia, due to head injury/ severe pain.
- High altitude.
- Hyperpyrexia.
- Encephalitis, hypothalamic tumours, drugs like salicylates, due to cirrhosis of liver.
- Hysteria.

Features and Management

- Headache, tingling, circumoral anaesthesia, tightness in chest, tetany, arrhythmias are the features.
- Low $PaCO_2$, low HCO_3, high alkaline pH are typical. Serum HCO_3 will not fall below 15 mEq/L.
- It can be acute or chronic.
- It is managed by oxygen therapy, treating the cause, *acetazolamide* in high altitude.
- Respiratory suppression due to alkalosis is treated by CO_2.

METABOLIC ACIDOSIS

It is an excess acid or base deficit. **A standard bicarbonate below 21 mmol/litre.**

Causes

Increase in fixed acid:

- Diabetic ketoacidosis.
- Starvation.
- Hypoxia.
- Renal insufficiency.
- Cardiac arrest.
- Excessive exercise.
- Intestinal strangulation. Here anion gap is increased.

Less you eat, you are malnourished. More you eat, more you are diseased.

Loss of base:

- Diarrhoea.
- Ulcerative colitis.
- Gastrocolic fistula.
- Intestinal fistula.
- Ureterosigmoidostomy causes hyperchloraemic hypokalaemic acidosis. Here anion gap is normal.

Features

- Rapid, deep, noisy breathing (air-hunger)—*Kussmaul's* breathing.
- Cold clammy skin, tachycardia, right heart strain, altered level of consciousness.
- Cardiac arrhythmias, hypotension.
- Anorexia, muscle weakness, vomiting.
- pH below 7.2 is dangerous and life-threatening.
- Capillary stasis.
- Urine is strongly acidic.
- Low standard HCO_3 level.
- Base deficit.
- It is evaluated by doing arterial blood gas analysis (ABG) which shows low HCO_3, low pH; anion gap; urinary anion gap (UAG). Normal UAG is zero or positive. In metabolic acidosis due to GI cause, UAG becomes negative due to increased NH_4Cl excretion; if it is due to renal cause, UAG will be positive.

Treatment

- Correction of hypoxia.
- **50 mmol of 8.4% sodium bicarbonate infusion IV.**

Sodium bicarbonate required in mEq/L = Body weight in kg × Base deficit × 0.3.

- Correction of electrolytes.
- Specific treatment for lactic acidosis (*type A* [shock / respiratory/CO/cyanide/anaemia]; *type B* [diabetes/hepatic/toxins/drugs])—only careful use of $NaHCO_3$ in severe cases, *dichloracetate* which stimulates pyruate dehydrogenase to reduce lactate.
- Specific therapies for diabetic ketoacidosis, alcoholic acidosis, aspirin poisoning, renal causes.

Astrup formula

Total base excess or deficit = Base excess/base deficit × body weight in kg × 0.3

RESPIRATORY ACIDOSIS

It is a feature of respiratory failure with high arterial PCO_2 causing fall in pH.

Causes

- During and after anaesthesia.
- Chronic bronchitis.
- Emphysema.
- Thoracic diseases.
- Upper abdominal surgeries and diseases.
- Respiratory airway obstruction.
- Myasthenia gravis.
- Poliomyelitis.
- Stroke, infection, obesity, hypoventilation.

Features and Treatment

- Features of hypercapnia like dyspnoea, confusion, psychosis, hallucinations, sleep disturbances, tremor, jerks, and personality changes. CNS manifestations are more severe in respiratory acidosis than in metabolic acidosis as lipid soluble CO_2 crosses blood-brain barrier easily than HCO_3.
- Acute respiratory acidosis is managed by oxygen therapy, ventilator support. Oxygen therapy should not be used in chronic hypercapnoea unless it is really indicated as hypoxia stimulated respiration may be suppressed. Alkali therapy also is not usually used unless acidosis is very severe (below 7.15) or there is severe bronchospasm.

ANION GAP

- It is calculated estimation of the undetermined or unmeasured anions in the blood.
- It is $(Na^+ + K^+) — (HCO_3^- + Cl^-)$.
- Normal anion gap is 10-16 mmol/litre.
- Anion gap is charge difference between unmeasured anion and cation. Important unmeasured anions are anionic protein, phosphate, sulphate, organic acids. Unmeasured cations are calcium and magnesium. Albumin is the main component of anion gap. When albumin decreases by one gram/dl then anion gap decreases by 2 mEq/L.

Increased anion gap is seen in	*Normal anion gap is seen in*
• Metabolic acidosis due to ketoacidosis	• Diarrhoea
• Lactic acidosis	• GIT fistulae
• Poisoning	• Hyperchloraemic acidosis
• Renal failure	

FLUID THERAPY

Osmolality of a solution is assessed by the amount of solute dissolved in a solvent like water measured in weight (kg).

Osmolarity of a solution is assessed by the amount of solute dissolved in a solvent like water measured in volume (litre).

Normal plasma Osmolality is 285 mOsm/kg (275-295).

Osmolality is calculated by two methods

a. *Osmolality of plasma* = $\frac{0.54}{1.86} \times 10^3$ mOsm/kg

It is based on the fact that solution of 1 mOsmol/kg freezes at – 1.86°C; whereas normal plasma freezes at – 0.54°C.

b. *Osmolality of plasma* = $2 \times (Na) + \frac{(\text{Glucose mg\%})}{18} + \frac{(\text{Blood urea mg\%})}{6}$

It is based on the concentrations of major solutes in plasma. So sodium concentration contributes mainly to the osmolality.

Colloidal osmotic pressure is difference in plasma osmotic pressure and interstitial fluid pressure which is normally 25 mm Hg, which is mainly by plasma albumin concentration. Plasma proteins do not go out of capillary wall into the interstitium.

Principles of Fluid Therapy

Indications

- For rapid restoration of fluid and electrolytes in dehydration due to vomiting, diarrhoea, shock due to haemorrhage or sepsis or burns.
- Total parenteral nutrition.
- Anaphylaxis, cardiac arrest, hypoxia.
- Post-gastrointestinal surgeries.
- For maintenance, replacement of loss or as a special fluid.

Advantage

Controlled, accurate and adjustable, rapid and predictable.

Problems in Fluid Therapy

- Needs hospitalisation; costly; needs asepsis.
- Fluid overload; pulmonary oedema and cardiac failure; infection.
- Thrombophlebitis; haematoma; cellulitis in local area.
- Pyrogenic reaction; air embolism; bacteraemia.
- Discomfort; poor patient acceptance.

Daily requirement of sodium is 100 mEq; potassium is 60 mEq; calcium is 5 mEq; magnesium 1 mEq.

One litre of normal isotonic saline contains 154 mEq of sodium.

Ringer's lactate is the most physiological fluid (*crystalloid*) containing sodium—130 mEq/lt; potassium—4 mEq/lt; chloride—109 mEq/lt; lactate (bicarbonate)—28 mEq/lt; and calcium—3 mEq/lt. It should be avoided in liver failure patients. As it does not contain glucose it can be used in diabetics.

Other *crystalloid* fluids—normal saline, dextrose saline, 5% dextrose, isolyte P, isolyte G, isolyte M.

Colloids are of large molecules which shift the fluid from interstitial compartment to intravascular compartment and are used as plasma expanders. Haemaccel, hetastarch, pentastarch, dextran 40/70 are colloids.

Special purpose fluids are sodium bicarbonate 7.5% and 8.4% used in metabolic acidosis, forced diuresis, hyperkalaemia; mannitol 10/20% used as an osmotic diuretic agent; hypertonic saline 1.6%, 3%, 5% and 7.5% used in hyponatraemia of different severity; albumin 4.5% as plasma expander; albumin 20% in severe hypoalbuminaemia.

Calculation of Drop Rate of IV Fluids

1 ml =16 drops in usual drip set. For microdrip set one ml = 60 drops.

a. Quantity of fluid required in liters per day × 10 = Drop rate/minute. 2.5 litres is usually used quantity of fluid/day. So 2.5 × 10 = 25 drops/minute.
b. Fluid volume in ml to be infused in one hour divided by four = Number of drops/minute. Example: 100 ml/hour means 25 drops/minute.
c. Number of microdrop/minute = Volume in ml/hour (50 microdrop/minute = 50 ml/hour)

Note:

- Weight loss more than 10% of individual's weight in 6 months is called as significant weight loss.
- Body Mass Index (BMI) is body weight in kilograms divided by height in meters squared. BMI less than 18.5 signifies nutritional impairment and below 15 signifies severe malnutrition.
- Daily fluid loss from kidneys is 1500 ml; from lungs is 400 ml; from skin is 800 ml; from stool is 60-150 ml.
- Energy requirement per day is 20-30 kcal/kg, i.e. around 2000 kcal/day total.
- Glucose requirement is 200 g per day; fat requirement is 200 g per week; nitrogen (protein) requirement is 0.15 g/kg per day. Nitrogen need increases to 0.25 g/kg/day in hyper catabolic status.
- Transit time is rapid in jejunum; three times slower in ileum; still slower in colon.
- Fluid absorption capacity is 40% in jejunum; 70% in ileum; 90% in colon.
- Electrolyte and vitamin B_{12} absorption and enterohepatic circulation occurs in ileum and so ileum is more important than jejunum.

NUTRITION

> *We (now) devote more attention to the patient's diet and habits, and more often send him away with good advice than with hastily-written prescriptions.*
>
> **—Robert Hall Babcock,** 1901

Principles of Nutrition

- Avoiding of malnutrition is the basic goal in nutrition therapy as malnutrition increases the morbidity and mortality of the disease process and prevents or delays the recovery. Malnutrition increases the chance of sepsis, prevents wound healing, increases the respiratory complications, and decreases the efficacy and tolerance to radiotherapy or chemotherapy.
- Whenever possible enteral route of nutrition should be used ideally. If that is not possible then parenteral nutrition is used.
- Overfeeding should be avoided as it leads into hyperglycaemia, hepatic steatosis, raised BUN, and excess CO_2 production.
- Timing and type of nutrition is also important.
- Nutrition therapy reduces protein wasting.
- Immunomodulators like glutamine, arginine and omega 3 fatty acids are also very useful. *Glutamine* is a nonessential amino acid synthesized in skeletal muscle. It is essential for cell proliferation during tissue repair. Glutamine helps GI mucosal cell proliferation, maintains mucosal integrity, improves immune function and prevents translocation of bacteria. It is useful in inflammatory bowel disease, short gut syndrome, burns, major trauma, and sepsis. Glutamine

is used commonly by enteral route even though IV preparations are now available (but it is very unstable in solutions).

Caloric requirement:

- Neonatal 100 kcal/kg/day.
- Adult 40 kcal/kg/day.
- Adult with catabolism 60 kcal/kg/day.

It is given as:

- Carbohydrates 50%.
- Fat 30-40%.
- Protein 10-15%.

Caloric values:

- Carbohydrate 4 kcal/g.
- Protein 4 kcal/g.
- Fat 9 kcal/g.

Indications for Nutritional Support

a. Preoperative nutritional depletion.
b. Postoperative complications: Sepsis, ileus, fistula.
c. Intestinal fistula: High type wherein output is more than 500 ml/day. It may be duodenal, biliary, pancreatic, intestinal.
d. Pancreatitis, malabsorption, ulcerative colitis, pyloric stenosis.
e. Anorexia nervosa and intractable vomiting.
f. Trauma—multiple fractures, fasciomaxillary injuries, head and neck injuries.
g. Burns.
h. Malignant disease.
i. Renal and liver failure.
j. Massive bowel resection causing short bowel syndrome.

Assessment

- Body weight
- Mid-arm circumference
- Triceps skin fold thickness
- Serum albumin
- Lymphocyte count

Nutritional requirements: Carbohydrates, fat, proteins, vitamins (includes fat soluble vitamins also), minerals, trace elements.

Methods of Feeding

Enteral:

a. *Gastrointestinal tract is the best route to provide nutrition.*
b. *Enteral feeding can be delivered by bolus, by gravity or using mechanical pump.*
    - *By mouth:* Requires:
        - Common sense,
        - Cleanliness,
        - Compassion.
    - *By nasogastric tube:* Confirmation of the tube in the stomach is made by injecting 5 ml of air down the tube and listening through a stethoscope for its bubbling entry into the stomach. Feeding rate is 30-50 ml/hours. 5 hours night time gap is given to allow gastric pH to return to normal.

Problems with tube feeding are:

- Blockage
- Nausea and vomiting, aspiration
- Hyperosmolarity
- Diarrhoea
- Tube discomfort
- Cholestasis

c. *By enterostomy:*
    - Gastrostomy.
    - Jejunostomy.



Fig. 1.210: Nasogastric tube passed should be confirmed in place using stethoscope. Tube is used for feeding purpose.



Fig. 1.211: Gastrostomy tube in place for enteral feeding.

Different preparations and formulas are available for enteral feeding. Soluble fibre containing diets along with nutrients are better to prevent diarrhoea.

Complications of enteral feeding

- Aspiration
- Wound infection and leak
- Diarrhoea due to rapid feeding or hyperosmolarity
- Hyperglycaemia
- Hypokalaemia
- Refeeding syndrome due to severe hypokalaemia and hypophosphataemia


Oesophagus
Gastroscope
Abdominal wall
Guide wire
Stomach
Trocar
Gastrostomy catheter
Oesophagus
Guide wire
Stomach
A
Oesophagus
Guide wire
Abdominal wall
Gastrostomy catheter (tube)
Stomach
Oesophagus
Abdominal wall
Gastrostomy catheter (tube)
Stomach
B

Figs 1.212A and B: Percutaneous endoscopic gastrostomy (PEG). Guide wire passed through a trocar in the abdominal wall into the stomach is pulled out across the oesophagus and mouth under visualisation using gastroscope. Gastrostomy catheter (tube) is passed along the guide wire and pushed downwards across mouth and oesophagus to reach the stomach. It is further pushed along the abdominal wall through the trocar. Gastrostomy tube is pulled out through abdominal wall and fixed. Trocar is removed. Placement of tip of gastrostomy tube can be confirmed by doing gastroscope.

Advantages of Enteral Nutrition

- Enteral nutrition preserves mucosal protein, digestive enzymes, IgA secretion; prevents mucosal atrophy and bacterial translocation.
- It is more physiological as nutrients pass through liver, the first filter to process and store. Gallstone formation is prevented (unlike long-term TPN) by stimulating gallbladder motility.
- It has got less serious complications. It is cost-effective.
- It supplies glutamine and short chained fatty acids to gut.

Contraindications of Enteral Nutrition

- Intestinal obstruction, GI bleed, paralytic ileus, severe diarrhoea, high output fistula.
- Low cardiac output, haemodynamically unstable patient.
- If safe access to enteral feeding is not present.
- Anticipated complications if thought to be present should be avoided.

GASTROSTOMY

It is done if feeding is required for more than *one month.*

Indications

- Severe malnutrition
- Major surgeries
- Severe sepsis
- Trauma
- Head and neck surgeries

Types

Based on duration of use:

- Temporary.
- Permanent.

Based on lining:

- Mucus lined (permanent).
- Serosal lined (temporary).

Based on technique:

a. ***Stamm temporary gastrostomy:*** After opening the abdomen, anterior wall of the stomach is opened. Feeding tube (Malecot's catheter) is placed in position. Two layers of purse string sutures are put around the tube. Wound is closed.
b. ***Kader-Senn temporary gastrostomy***.
c. ***Percutaneous endoscopic gastrostomy*** (popular)—now becoming common method.
d. ***Janeway's mucus lined permanent gastrostomy*** by creating tunnel in stomach wall.

Problems in gastrostomy

- Leak—gastric fistula
- Infection
- Aspiration and pneumonia
- Diarrhoea is common—30%
- Bloating, abdominal cramps
- Displacement, blockage of the tube

Contraindications

- Previous gastric surgeries.
- Intestinal obstruction.
- Gastric outlet obstruction.

JEJUNOSTOMY

Jejunostomy for enteral nutrition is becoming more popular because of:

- Its comfort,
- Easy to do,
- Can be kept for long time,
- Lesser complication than gastrostomy.

Indications are same as gastrostomy.

Types

a. *Witzel jejunostomy:* Site of placing jejunostomy is 30 cm from duodenojejunal junction.
b. *Needle jejunostomy* using catheter of small gauge.



Fig. 1.213: Needle jejunostomy.

TOTAL PARENTERAL NUTRITION (TPN)

All nutritional requirements are given only through intravenous route, not through gastrointestinal tract. It can be through a central catheter through the subclavian/internal jugular vein where the tip of venous catheter is at distal part of superior vena cava.

It can also be a peripheral (Peripheral Parenteral Nutrition/PPN) through a peripherally inserted central venous catheter (PICC) or through a formal peripheral venous line.

Indications

- Failure or contraindication for any enteral nutrition for 7-10 days
- High output abdominal fistulas, duodenal, biliary, pancreatic fistulas
- Major abdominal surgeries of liver, pancreas, biliary, colonic
- Septicaemia
- Multiple trauma
- Short bowel syndrome
- Severe pancreatitis, bowel ischaemia, peritonitis, ileus
- Massive GI bleeding, unstable haemodynamically
- High-risk of aspiration
- Hyperemesis gravidarum
- Multiorgan failure, head injury, severe burns

About 5% of hospital admissions require TPN.

Technique

- Using a needle and guide wire a *Subclavian vein catheter* is passed just below the clavicle and fixed securely to the skin.
- TPN is given through *central vein* and not through a peripheral vein.
- Peripherally inserted central catheter (PICC) is also commonly used (PPN).

Goals, Factors and Assessment in TPN

- To decrease adverse effects of catabolism; to increase protein synthesis, to reduce protein breakdown, to prevent weight loss.
- To support ongoing metabolism.
- To improve immune function, cardiac and respiratory function.
- To maintain glycogen reserve in cardiac and respiratory muscles.
- To maintain acid, base and electrolyte metabolism.
- Age, premorbid state, muscle mass, weight, serum albumin should be assessed.
- Underlying disease, its severity, therapies for the disease, GI function should be assessed.
- *Fluid requirement* is assessed by—1500 ml for 20 kg weight + 20 ml/kg for additional weight.
- *Energy needed* is calculated by calculating resting energy expenditure (REE). (1) By *simple calculation*: REE in kcal/day = 25 × weight in kg. (2) *Harris Benedict equation*: REE in men = 66 + (13.7×weight in kg) + (5 × ht in cm) – (6.7 × age in years). In women = 655 + (9.6 × weight) + (1.8 × ht) – (4.7 × age). Activity/disease/thermal factors are also

added. (3) *Indirect calorimetry*: It is more accurate method done using special instrument. REE: = ($3.9 \times VO_2$) + ($1.1 \times VCO_2$) – 61.

Components used in TPN

- Carbohydrates
- Fat and amino acids
- Vitamins and trace elements, electrolytes, minerals

Components Used in TPN/PPN

Carbohydrates: Dextrose is less costly (1 gram dextrose 3.4 kcal); can be used in 50-70% concentration during PN. It supplies calories, stimulates insulin release and glucose oxidation, prevents muscle protein breakdown, has got nitrogen sparing ability. *Problems* of carbohydrate/dextrose are—low calorie value compared to fat, requires large fluid volume to infuse, hyperglycaemia, causes more CO_2 production, because of high osmolality it causes thrombophlebitis in 10% or above concentration. Rate of administration of dextrose is 5 mg/kg/min.

Fat: Fat gives high calorie (1 gram—9 kcal), essential fatty acids. It is given as emulsion containing long chain triglycerides. It contains soyabean/sunflower oil with egg yolk phospholipids (emulsifying factor), glycerin (isotonic). Fat has got low osmolality (260 mosm/L); it is available as 10%, 20%, 30% emulsions. *Advantages of fat* in PN are—high calorie, prevents hyperglycaemia, glucose and nitrogen sparing, less CO_2 production, less insulin production; it prevents essential fatty acid deficiency (for this purpose 3 days a week dose is given), reduces thrombophlebitis. *Problems of lipids in* PN are—hypertriglyceridaemia, sepsis, fat embolism, fat overload, hepatic dysfunction, pancreatitis, delayed gastric emptying. Lipid emulsions are avoided in hyperlipidaemia, anaemia, acidosis, obesity. Lipid emulsion is good culture media for bacteria and fungi; so care should be taken to prevent sepsis. Triglyceride level should be monitored weekly; if more than 400 mg%, infusion is discontinued. Mixture of long and medium chain fatty acids is better tolerated and efficient.

Amino acids: They are source of proteins. Calorie value of amino acid is 4 kcal/gram. 6.25 gram protein has 1 gram nitrogen. In PN 20% of energy comes from amino acids; rest from dextrose and fat. Daily protein need is 0.8-1.5 gram/kg. Protein supplement should be less in patients with CRF and hepatic encephalopathy. Its need is more in burns, trauma, enteropathy, sepsis. Protein supplement should not exceed 1.7 gram/kg/day; if so will cause raised urea production. *Uses of* amino acids in PN—in protein anabolism; prevents scatabolism. Proper monitoring by doing BUN or ammonia level is essential during amino acid therapy.

***Vitamins, electrolytes, trace elements and minerals*:** Electrolytes like sodium, potassium, magnesium, phosphate, calcium; fat soluble vitamins like A, D, E, K; water soluble vitamins; trace elements like chromium, copper, iodine, iron, manganese, selenium, zinc are all used in PN.

Monitoring the patient

- By body weight, fluid balance, blood glucose, electrolytes, blood urea, LFT, serum calcium, magnesium, phosphate should be done at regular intervals.
- A weight gain more than one kg/day signifies fluid overload.

Complications

Technical

a. Air embolism.
b. Pneumothorax.
c. Bleeding.
d. Catheter displacement, sepsis, blockage.
e. Infection, thrombosis.

Biochemical

a. Electrolyte imbalance: Hyponatraemia, hypokalaemia, hypophosphataemia.
b. Hyperosmolarity.
c. Hyperglycaemia—common.
d. Dehydration.
e. Altered immunological and reticuloendothelial function.
f. Azotaemia.

Others

a. Dermatitis.
b. Anaemia and increased capillary permeability.
c. Cholestatic jaundice: It is common.
d. Severe hepatic steatosis.
e. Metabolic acidosis.
f. Candida infection (candidiasis), staphylococcal infection (10-15%).

Contraindications

- Cardiac failure
- Blood dyscrasias
- Altered fat metabolism

Anabolic steroid durabolin 25 mg IM weekly is given to improve nitrogen balance.

Home parenteral nutrition

- It is becoming popular
- It is commonly used in western countries
- It is indicated in short bowel syndrome or any other conditions wherein enteral feeding is not possible but patient can be sent home with provision for home parenteral nutrition
- Patient himself uses the TPN fluids as advised at home. He will be with TPN catheter
- Patient should attend TPN clinic weekly for follow-up or immediately whenever complications arise
- Patient will be comfortable psychologically and often can attend his job also

REFEEDING SYNDROME

- Refeeding syndrome is occurrence of severe fluid and electrolyte imbalance in severely malnourished individual while starting the proper feeding enteral or parenteral nutrition. It is more common in TPN.
- It causes hypomagnesaemia, hypocalcaemia and hypophosphataemia leading into myocardial dysfunction, respiratory changes, altered liver functions, altered level of consciousness, convulsions and often death.
- Gradual feeding and correction of magnesium, phosphate and calcium and other electrolytes is important.
- Condition is common in chronic starvation, severe anorexia and alcoholic patients.

OBESITY AND MORBID OBESITY

Obesity is weight more than 20% above the normal. Body mass index (BMI) is weight in kilogram divided by height in meters squared [wt in kg / (Ht in meters)^2].

Morbid obesity is a condition wherein BMI is more than 40 kg/m^2. It is often also defined as weight 100 lbs or more; or 100% over ideal body weight.

Weight more than double the expected weight to that age and height of the individual is also often called as morbid obesity. Body weight exceeding BMI 50 kg/m^2 is called as *superobesity*.

Causes of Obesity

- Familial, hyperinsulinism, hyperadrenocorticism, hyogonadism.
- Abnormal eating behaviour: Hormones which control eating are—ghrelin from stomach; insulin from pancreas; leptin from fat; PYY 3-36 from colon. Hypothalamus is the center in CNS which controls eating.

Nutritional status	***BMI (kg/m^2)***
• Underweight	• < 18.5
• Normal	• 18.5-24.9
• Overweight (Preobesity)	• 25.0-29.9
• Obesity	• > 30
– Class I	– 30.0-34.9
– Class II (Moderate)	– 35.0-39.9
– Class III (Severe / Morbid)	– 40.0
• Superobesity	• > 50
• Super superobesity	• > 60

Obesity is more common in young women. Child of a normal weight parents has 10% chance to become obese. If both parents are obese then child has got 80% chances to develop obesity.

Problems with Morbid Obesity

Obstructive sleep apnoea, degenerative joint disease, back pain, hypertension, GERD, gallstones, type II diabetes, hyperlipidaemia, arrhythmias, venous diseases, DVT, skin diseases, urine incontinence, infertility, ventral hernias, obesity hypoventilation syndrome, polycystic ovarian disease, hirsutism, gynaecomastia, steatohepatosis, malignancies—are common problems. All these conditions are called as ***comorbidities.***

Infertility is common in married morbid obese women due to improper ovulation, polycystic ovary disease. Urinary incontinence is common in morbid obese women (stress incontinence and detrusor instability). Pregnancy in morbid obese patient is considered as high-risk pregnancy. Gestational diabetes, hypertension, are common. It is better these women to undergo bariatric surgery prior to pregnancy which definitely reduces the complications during pregnancy. Such individual after bariatric surgery needs more iron and vitamin supplements.

Complications of obesity	***Obesity and surgery***	***Treatment for obesity***
• *General:* Difficulty in work, fatigue, depression, back pain, arthritis and gout • *Cardiovascular:* Hypertension, stroke, thrombophlebitis, pulmonary embolism • *Pulmonary:* Hypoventilation, poor respiratory effort • *GIT:* Hiatus hernia with reflux, changes in liver, pancreatitis, gallstones • *Endocrine:* Diabetes mellitus	• Hernia and gallstones are more common in obese individual • Burst abdomen, incisional hernia are more common in obesity • Delay in recovering from anaesthesia • Infertility is more common	• *General:* Dieting, exercise • Drugs: Orlistat, Sibutramine • Surgeries: – *Restrictive* ◆ Vertical banded gastroplasty ◆ Laparoscopic adjustable gastric banding (LAGB) ◆ Jaw wiring – *Malabsorptive* ◆ Biliopancreatic diversion (BPD) ◆ Biliopancreatic diversion with duodenal switch (BPD-DS) ◆ Jejunoileal bypass – *Combined* – Roux-en-Y gastric bypass (RYGB) open or laparoscopic

Evaluation of the patient—cardiac and respiratory assessment; lipid profile; blood glucose; renal and liver status assessment; anaesthesia risk assessment.

Medical Management

- General: Diet, life style changes, exercise.
- *Drugs*: (1) Orlistat is a selective inhibitor of gastric and pancreatic lipases that reduces the absorption of lipids from intestine. (2) Sibutramine is a noradrenaline and 5 HT reuptake inhibitor which act as appetite suppressor.

Surgical Treatment (Bariatric Surgery)

Bariatric surgery causes long-term durable weight loss. Patient's eating behaviour is reduced to slow ingestion of small boluses of food and or also reducing the absorptive surfaces.

Types of Bariatric Surgery

a. *Restrictive* wherein caloric intake is reduced. Purely gastric restrictive procedures are vertical banded gastroplasty (VBG) and laparoscopic adjustable gastric banding (LAGB).
b. *Malabsorptive* wherein absorption of calories and nutrients from food is reduced. Biliopancreatic diversion (BPD) and biliopancreatic diversion with duodenal switch (BPD-DS) are malabsorptive procedures.
c. *Combined* wherein both methods are used. Roux-en-Y gastric bypass (RYGB) is both restrictive and malabsorptive types. Gastric bypass reduces GI polypeptide ghrelin level secreted from fundus of stomach and duodenum. Ghrelin acts on specific receptor in CNS—hypothalamus to initiate appetite. This stimulation is reduced to decrease appetite. In restrictive only procedure ghrelin level raises and so appetite stimulation is not controlled.

Indications for Bariatric Surgery

BMI more than 40 kg/m^2 or BMI more than 35 kg/m^2 with comorbidity is indication for bariatric surgery. American Association of Bariatric Surgery (ASBS) published indications and approved surgeries.

Contraindications

Patients who are unfit for general anaesthesia (cardiac/renal/respiratory/hepatic causes) or who are unable to adjust postoperative life styles or psychiatric patients are contraindications for bariatric surgery.

Preoperative Preparations and Evaluation

- Complete cardiac, respiratory/renal/hepatic evaluation.
- Lipid profile and blood glucose assessment.
- Obstructive sleep apnoea in obese patient should be assessed using polysomnography and be treated.
- Risk assessment for DVT should be done.
- If GERD symptoms are present gastroscopy should be done.
- USG abdomen to identify gallstones should be done; if gallstones present it is of usual practice to do cholecystectomy along with bariatric procedure.
- Nutritional evaluation and dietician advice for preoperative and postoperative diet management.
- Psychological screening is needed to all patients to counsel their postoperative care and diet.
- Separate theatre table is needed for morbid obese patient. Equipments should be long and flexible. In laparoscopic surgery, special ports and instruments are needed.

DIFFERENT SURGERIES

Vertical Banded Gastroplasty (VBG); Mason (1982)

It is a purely restrictive type with creation of a calibrated stoma in the lesser curvature which is reinforced by an encircled mesh with a proximal gastric pouch. After laparotomy Ewald's stomach tube is passed per orally to place against lesser curve. A 2.5 cm circular window is created in the body of stomach near lesser curvature 8 cm below the *angle of His*. After this, four lines of linear vertical stapling are done from circular opening towards angle of His. This staple line ideally should be divided using another cutting linear stapler to reduce chances of dehiscence. This creates a 50 ml proximal gastric pouch. A 1.5 × 7 cm polypropylene mesh is placed around the lesser curve through circular opening and sutured to create a 5 cm collar stoma.


Angle of His
8 cm
Proximal gastric pouch
Wrapped mesh
Stomach ready for VBG
Circular window made in stomach using circular stapler
Vertical 4 line staples from window towards angle of His
Ideally middle of staple line is divided using cutting linear stapler
7 X 1.5 cm polypropylene mesh is wrapped around the window to create a narrow stoma
7 X 1.5 cm polypropylene mesh

Fig. 1.214: Vertical banded gastroplasty (VBG).

The fool is never satisfied while the wise man finds wealth in contentment

VBG causes only medium term weight loss; its efficacy is less compared to other procedures. *Complications of VBG are*—stricture at stoma (20%), vomiting (30%), reflux (20%), staple line dehiscence (40%), conversion into other procedures. Mortality is 0.3%.

VBG is technically easier to do; it has got very less chances of long-term metabolic and nutritional deficiencies.

Laparoscopic Adjustable Gastric Banding (LAGB)

It is also a restrictive type (1992, Guy Bernard) to create a narrow stoma just below the OG junction. It is used in adolescents and elderly. It is contraindicated in hiatal and paraoesophageal hernias. It is done using *laparoscopy.*

Under general anaesthesia, with patient in reverse Trendelenburg position six laparoscopic ports are placed. Using pars flaccida method, retrogastric tunnel is created; a silicone band is passed through the tunnel to encircle the cardia just below the OG junction; tail of the band is buckled and locked. Stoma diameter is determined by inserting a calibration tube. Stomach over the band is imbricated using interrupted sutures except the buckle area. Silicone tube end is brought out through the abdominal wall to connect access port. It is used for band volume adjustment by injecting or withdrawing the saline.

Gastrograffin study is done on 1st postoperative day to assess band position and lumen patency. Patient is advised to have liquid diet for one month. Band adjustment is done under fluoroscopic guidance in 2 months. Adjustment is done to achieve weight loss at a rate of 2 kg/week. Efficacy of LAGB is 55%.

Complications of LAGB are—spleen/stomach injury; bleeding; band slippage (10%); band erosion (7.5%); tube related complications; vomiting; pouch dilatation; reflux. Conversion rate is 3%; mortality is less than 0.5%.

Jejunoileal Bypass

It was the first malabsorptive procedure done for obesity. Now this technique is not done due to high incidences of complications.

Proximal jejunum is divided and proximal cut end is anastomosed to distal ileum just proximal to ileocaecal valve to reduce the absorptive surface area of small bowel.

Complication rates were higher and so procedure is not practiced. Colon in these patients absorbs high level of oxalate causing nephrocalcinosis. Bypassed bowel promotes bacterial growth causing endotoxic induced liver injury, cirrhosis, liver failure. Complications like protein, vtamin K, vtamin B_{12} deficiencies; gallstone formation; enteritis and diarrhoea; arthritis, osteoporosis are common.

Roux-en-Y Gastric Bypass

It is commonly done combined procedure. It can be done by open or laparoscopic method. Proximal stomach is dissected between 1st and 2nd branches of left gastric branches. Vagii nerves and *nerves of Latarjet* are retained carefully. Stomach is transected at this proximal site to create a proximal gastric pouch (15 ml if BMI is > 50; 30 ml if BMI is 40-50). It is usually carried out through linear stapler. Jejunum is transected 45 cm from *ligament of Treitz*. A side to side jejunojejunal anastomosis is done using stapler 75 cm distal to the distal cut end. Proximal Roux part of the distal jejunal cut part (75-150 cm, based on patient's preoperative weight) is brought out through the transverse mesocolon towards the created proximal gastric pouch and gastrojejunostomy is done to this proximal gastric pouch. Mesenteric defect is closed. Stomal integrity is checked on table by air distension and methylene blue infusion. Gastrograffin study is done in 24 hours to assess pouch size, stomal patency and distal obstruction. Oral food is started in 24 hours and patient is discharged in 4 days.

RYGB is more useful in weight loss compared to purely restrictive types. 5 years weight loss is 60-75%. It also prevents progression of noninsulin dependent diabetes mellitus, controls hypertension, sleep apnoea, hyperlipidaemia, asthma, arthritis, GERD.

Complications are—Roux obstruction, anastomotic leak, acute distal gastric dilatation, stomal stenosis, marginal ulcer, dumping syndrome, internal hernias, vitamin B_{12} deficiency, iron



Fig. 1.215: Laparoscopic adjustable gastric banding (LAGB).


Jejunum
Ileum
Proximal jejunum is anastomosed to distal ileum to bypass small bowel absorptive surface
Jejunum
Ileum

Fig. 1.216: Jejunoileal bypass procedure (JIB).


Creation of proximal gastric pouch of 15-30 ml
45 cm
Staple transection of jejunum at 45 cm from DJ junction
GJ with Roux loop
75-150 cm
Roux limb of 75-150 cm passed thru Tn mesocolon
Jejunojejunostomy

Fig. 1.217: Roux-en-Y gastric bypass procedure (RYBG).

deficiency anaemia. Distal gastric dilatation needs emergency intervention which is usually due to jejunojejunal obstruction.

Laparoscopic RYGB (1994, Wittgrove, Clark, Trembly)

Technique is similar to open RYGB. Anastomoses are done using endoscopic stapler. GJ between gastric pouch and Roux jejunum is done either using linear stapler through laparoscopic port after making a gastrotomy in the pouch which is later sutured after staple firing; or using circular stapler anastomosis is done wherein anvil is initially passed transorally often under endoscopic guidance across the pouch into the Roux jejunum; or using hand sewing with absorbable sutures. Omentum is released from the colon and is covered over the GJ. Mesenteric defect and *Patterson Brown defect* are closed. A *Bronlin antiobstructive stitch* is placed between Roux and biliopancreatic limbs. Integrity of anastomosis is checked using insufflation of air, methylene blue. *Complications ar*e similar to open RYBG. Conversion rate is 9%. *Advantages* of LRYBG to open RYBG are—faster recovery, less postoperative pain, less wound related complications, less morbid one. *Disadvantage* of LRYBG is availability of facility, technical expertise, and steep learning curve.

Now technique is modified to antegastric, antecolic one which has become popular (Gagner).

The lazy man is always occupied with his laziness.

Biliopancreatic Diversion (BPD) (Nicola Scopinaro, Italy)

It is done in patients who had failed restrictive procedure or who are superobese.

Distal subtotal gastrectomy is done with formation of proximal gastric pouch (of 400 ml in BMI 40-50; 200 ml in BMI > 50). Ileum is transected 250 cm proximal to ileocaecal valve; distal ileal segment is brought up to anastomose into the proximal gastric pouch. Proximal biliopancreatic jejunoileal limb is anastomosed into distal ileal segment 50 cm proximal to ileocaecal valve as end to side stoma. Additionally cholecystectomy should be done.

Modification of BPD with duodenal switch (BPD-DS) has become more popular. Here sleeve gastrectomy along the greater curvature is done to create gastric reservoir (200 ml) along lesser curve. Duodenum just distal to first part is divided using stapler; proximal cut end is sutured to proximal upward pulled end of the distal ileal segment of earlier transected ileum, 250 cm from ileocaecal valve. Biliopancreaticoduodenal with proximal jejunoileal segment is later stapled to distal ileum 50 cm proximal to ileocaecal valve. Duodenal switch reduces the rate of marginal ulcer and dumping syndrome.


Subtotal gastrectomy with proximal pouch
Long biliopancreatic limb
200 cm long GI tract limb
50 cm

Fig. 1.218: Biliopancreatic diversion procedure (BPD).



Fig. 1.219: Biliopancreatic diversion with duodenal switch procedure (BPD-DS).

Results of BPD/BPD-DS are—excellent for weight reduction compared to restrictive procedures. But they need lifelong supplement of vitamins, fat soluble vitamins, calcium, and iron. Technically BPD is easier to do when compared to BPD-DS.

Complications of BPD/BPD-DS are—anemia (30%); protein deficiency (20%); dumping syndrome; marginal ulcer (in BPD 10%; in BPD-DS it is 1%); osteoporosis; night blindness; biliopancreatic limb obstruction; staple line leak; staple line bleed; DVT; subphrenic abscess. Vitamin B_{12} deficiency is specific.

Ileal Interposition with Sleeve Gastrectomy

It is done *mainly in type II diabetes*. Often they are associated with obesity, dyslipidaemia, hypertension, nephropathy and neuropathy. Two types of ileal interposition with sleeve gastrectomy are done.

Type 1: Sleeve gastrectomy is done. 170 cm of ileum with mesentery is isolated 30 cm from ileocaecal junction. Jejunum is transected 50 cm from duodenojejunal flexure. Isolated 170 cm ileal segment is interposed 50 cm distal to DJ junction with end to end anastomosis on both ends.

Type 2: After doing sleeve gastrectomy, gastroduodenal junction is transected; cut proximal end of duodenum is closed. 170 cm ileal segment with mesentry is isolated and interposed between cut end of stomach and side of jejunum 50 cm distal to DJ flexure.

Cholecystolithiasis After Bariatric Surgery

Gallstone formation is common after bariatric surgery (50%). It is due to rapid weight loss. If gallstones are present at the time of bariatric surgery it is essential to do laparoscopic cholecystectomy during bariatric procedure. It is controversial about doing prophylactic cholecystectomy during bariatric surgery even though it is practiced in many places. Advantages are—it prevents future gallstone formation at the time of bariatric surgery (loss of access); it prevents difficulties in approaching CBD in case needed endoscopically due to surgery. Disadvantage is cholecystectomy adds additional 1 hour time for bariatric surgery increasing the risk of immediate complications. Patients who are not having gallstones at the time of bariatric surgery, should receive ursodeoxycholic acid 300 mg twice daily for 6-12 months of post-bariatric surgery period. Often stomach is anchored to abdominal wall as access part to biliary system for future need.

Note:

Many of these patients after bariatric surgery require plastic surgery for abdominal contour (panniculectomy, abdominoplasty) after weight reduction due to bariatric surgery.

G. Shock

> *The first noteworthy characteristic of the blood in shock is a high capillary red count…. When haemorrhage as a complicating factor tending to reduce the blood count is considered, these high counts are striking. They indicate that in shock a concentration of the blood occurs, at least in the superficial capillaries.*
>
> —**Walter Bradford Cannon, J Fraser, AN Hooper,** 1918

CHAPTER OUTLINE

- Shock
- Stages of Shock
- Effects of Shock
- Clinical Features of Shock
- Investigations in Shock
- Central Venous Pressure
- Pulmonary Capillary Wedge Pressure
- Systemic Inflammatory Response Syndrome
- Multiple Organ Dysfunction Syndrome
- Oxygen Therapy
- Topical O_2-Therapy
- Cardiac Arrest

SHOCK

Shock is a state of poor perfusion with impaired cellular metabolism manifesting with severe pathophysiological abnormalities. It is due to circulatory collapse and tissue hypoxia. Normal *aerobic metabolism* is not maintained due to hypoperfusion. Shock is meant by '*inadequate perfusion*' to maintain normal organ function.

At *cellular level* hypoxia causes change of normal aerobic to anaerobic metabolism causing lactic acidosis. Intracellular potassium is released into circulation. Lysosomes from cells get released into blood causing cell lysis. *Hypoxia and acidosis* through complements release free oxygen radicals and cytokines which damage capillary endothelium. Eventually cardiovascular, respiratory, renal, endocrine and GIT will be affected presenting as *systemic* features.

Causes of shock

1. **Hypovolaemic shock**—due to reduction in total blood volume.
   It may be due to:
   a. *Haemorrhage*
      – External from wounds, open fractures
      – Internal from injury to spleen, liver, mesentery or pelvis
   b. *Severe burns*, which results in loss of plasma
   c. Peritonitis, intestinal obstruction
   d. Vomiting and diarrhoea of any cause
2. **Cardiac causes**
   a. Acute myocardial infarction, acute carditis
   b. Acute pulmonary embolism wherein embolus blocks the pulmonary artery at bifurcation or one of the major branches
   c. Drug induced
   d. Toxaemia of any causes
   e. Cardiac surgical conditions like valvular diseases, congenital heart diseases
   f. Cardiac compression causes
      i. Cardiac tamponade due to collection of blood, pus, fluid in the pericardial space which prevents the heart to expand leading to shock.
      ii. Trauma to heart
3. **Septic shock**—is due to bacterial infections which release toxins leading to shock
4. **Neurogenic shock**—due to sudden anxious or painful stimuli causing severe splanchnic vessel vasodilatation. Here, patient either goes for cardiac arrest and dies or recovers fully spontaneously—spinal cord injury/anaesthesia can cause neurogenic shock
5. **Anaphylactic shock**—is due to Type 1 hypersensitivity reaction
6. **Respiratory causes**
   a. Atelectasis (collapse) of lung
   b. Thoracic injuries
   c. Tension pneumothorax
   d. Anaesthetic complications
7. **Other causes**
   a. Acute adrenal insufficiency (Addison's disease)
   b. Myxoedema

Shock may be *hypovolaemic, cardiogenic, obstructive, distributive or of endocrine* variety.

Pathophysiology of Shock

Any cause of shock

↓

Low cardiac output

↓

Vasoconstriction occurs as a compensation to perfuse vital organs like brain, heart, muscle, kidneys, liver

↓

Because of vasoconstriction and tachycardia

↓

Dynamic circulation increases

↓

Tachypnoea occurs to increase the oxygen saturation

↓

Peripheral veins (capacitance vessels) constrict diverting blood from splanchnic system towards essential vital organs

↓

Decreased renal blood flow reduces the GFR and thereby the urine output

↓

Renin angiotensin mechanism gets activated causing further vasoconstriction and aldosterone release

↓

Causes salt and water retention

↓

ADH is released

↓

Further concentration of urine occurs

When shock persists cardiac output falls further

↓

Hypotension and tachycardia occurs leading to poor perfusion of coronaries

↓

*Hypoxia—**metabolic acidosis***

↓

Release of cardiac depressants

↓

Cardiac (pump) failure

Hypoxia

↓

Anaerobic metabolism

↓

Lactic acidosis

↓

Cell wall damage

↓

Sodium and calcium enter the cell

↓

Potassium leaks out of the cell

↓

Causes hyperkalaemia, *hyponatraemia and hypocalcaemia*

↓

Intracellular lysosomes break down releasing powerful enzymes which destroy own cell

↓

SICK CELL SYNDROME

Platelets are activated forming small clots in many places

↓

Disseminated intravascular coagulation (DIC) (Consumption coagulopathy)

↓

Further bleeding.

STAGES OF SHOCK

Factors like infection, trauma, burns, haemorrhage, hypovolaemia

↓

Hypoxia and its effects.

↓

SIRS *(Systemic inflammatory response syndrome*) is due to vasodilatation, increased endothelial permeability, thrombosis, leukocyte migration and activation.

↓

All these lead to altered cytokines level, abnormal **NO (nitric oxide)** synthesis, abnormal arachidonic acid metabolism, neutrophil activation, free radical production, altered complement activation, failure to have a localisation of inflammation. It is severe type of ***reversible shock.***

↓

Which will lead to established microvascular occlusion, cellular dysfunction, sick cell syndrome, DIC and PUMP failure.

↓

MODS (*Multiorgan dysfunction syndrome)* ***(Irreversible shock*)**—of lungs, kidneys, liver, clotting system and brain.

Note:

- *Distributive shock* is one in which there is vasodilatation, decreased vascular resistance, hypotension, altered microvascular perfusion with arteriovenous shunting, altered cellular oxygen metabolism. It is seen in septic shock, spinal trauma, adrenal crisis and anaphylaxis.
- *Obstructive shock* occurs due to mechanical impediment of circulation due to pulmonary embolism, tension pneumothorax or cardiac *tamponade*.

EFFECTS OF SHOCK

Heart: Low perfusion → low venous return → decreased cardiac output → hypotension → tachycardia. Persistent shock causes hypoxia and release of myocardial depressants leading to further cardiac damage.

Lung: Interstitial oedema → decreased gaseous exchange → pulmonary arteriovenous shunting → tachypnoea → *Adult/Acute respiratory distress syndrome (ARDS)* and pulmonary oedema.

Metabolic: Shock leads to hypoxia, which activates anaerobic metabolism leading to lactic acidosis. Antidiuretic hormone (ADH) is released which increases the reabsorption of water from renal tubules. Other hormones released are ACTH, prostaglandins, histamine, bradykinin, and serotonin to compensate the effects of shock to increase the perfusion of vital organs like heart, brain and lungs.

Cellular changes occur in persistent shock due to release of lysosomal enzymes, which alters the cell membrane permeability causing cell death—*sick cell syndrome*.

Sympathetic overactivity alters the microcirculation leading to capillary dysfunction.

Brain perfusion, when decreases the patient becomes drowsy. *Brain is the last organ to get underperfused in shock.*

Kidneys: GFR decreases and tubular reabsorption of salt and water increases for compensatory response. But in severe cases tubular necrosis sets in leading into irreversible damage.

Blood*:* Alteration in cellular components including platelets leads to *Disseminated intravascular coagulation (DIC)*. It causes bleeding from all organs.

Gastrointestinal tract: Mucosal ischaemia develops causing bleeding from GIT with haematemesis and malaena. It is aggravated by DIC. Hepatic ischaemia leads into increased enzyme levels.

Types of Hypovolaemia

a. *Covert compensated hypovolaemia:* When blood volume is reduced by 10-15% , there will not be significant change in heart rate, cardiac output and splanchnic blood compensates for the same.

b. *Overt compensated hypovolaemia*: Here patient has cold periphery, tachycardia, a wide arterial pressure, tachypnoea, confusion, hyponatraemia, metabolic acidosis, but systolic pressure is well-maintained.

c. *Decompensated hypovolaemia:* Here all features of hypovolaemia are present like hypotension, tachycardia, sweating, tachypnoea, oliguria, drowsiness, eventually features of SIRS is seen and often if not treated on time leads to MODS, i.e. irreversible shock.

Types of Shock

1. *Vasovagal Shock*

It is sudden dilatation of peripheral and splanchnic vessels causing reduced cardiac output and shock. Often it may be life-threatening due to hypoxia.

2. *Neurogenic Shock*

- It is usually due to spinal cord injury, which causes dilatation of splanchnic vessels.
  - This type can safely be treated with vasoconstrictor drugs to bring up the blood pressure. There will be bradycardia, hypotension, arrhythmias, and decreased cardiac output. Blood pressure control, oxygen delivery, maintenance of haemodynamics, airway, fluid therapy, intravenous methylprednisolone therapy should be done. Dopamine and or phenylephrine (α agonist) can be used.

3. *Hypovolaemic Shock—Most Common Type*

- Haemorrhage, may be due to injury to the liver, spleen, bone fractures, haemothorax, vascular injury, severe bleeding on table during surgeries of thyroid, liver, portal vein or major vessels.
- Vomiting, diarrhoea due to any cause.
- Burns.

4. *Cardiogenic Shock*

Cardiogenic shock is defined as circulatory failure causing diminished forward flow leading into tissue hypoxia in the setting of adequate intravascular volume with systolic blood pressure < 90 mmHg for 30 minutes; cardiac index < 2.2 L/minute / sq meter; raised PCWP (pulmonary capillary wedge pressure) > 15 mmHg. It is commonly seen in acute MI with a mortality > 50%. Cardiogenic shock develops within 24 hours of MI. it occurs when 50% of left ventricular wall is damaged by infarction. It leads to pulmonary oedema and severe hypoxia. Ischemic necrosis of left ventricular wall causes failure of pump thereby decreasing stroke volume.

Diagnosis is established by *ECG*, echocardiography, arterial blood gas analysis, *cardiac enzymes, PCWP* and electrolyte estimation (hypokalaemia and hypomagnesaemia are common) are the essential investigations.

Management

- Proper oxygenation with intubation, ventilator support, cardioversion, pacing, antiarrhythmic drugs, correction of electrolytes, avoiding fluid overload, prevention of pulmonary oedema as immediate measures.
- Dobutamine (β1 receptor agonist) is used to raise cardiac output provided there is adequate preload and intravascular volume (it is peripheral vasodilator and reduces BP). Dopamine is preferred in patients with hypotension. But it may increase peripheral resistance and heart rate worsening cardiac ischaemia. Often both dopamine and dobutamine combination may be required.
- Careful judicial use of epinephrine, norepinephrine, phosphodiesterase inhibitors (amrinone, milrinone) are often needed. Anticoagulants and aspirin are given. Thrombolytics can be used. β blockers, nitrates (nitroglycerine causes coronary arterial dilatation), ACE inhibitors are also used.
- *Intra-aortic balloon pump (IABP)* may need to be introduced transfemorally as a mechanical circulatory support to raise cardiac output and coronary blood flow.
- Relief of pain, preserving of remaining myocardium and its function, maintaining adequate preload, oxygenation, minimizing sympathetic stimulation, correction of electrolytes should be the priorities.

Tears shed for self are tears of weakness, but tears shed for others is a sign of strength.

- Percutaneous transluminal coronary angioplasty *(PTCA)* and coronary artery bypass graft *(CABG)* are the final choices.

5. *Cardiac Compression Shock*

- It is probably due to pericardial tamponade of any cause or kinking of great vessels, massive pulmonary embolism, tension pneumothorax, air embolism causes obstructive shock with reduced preload to heart.
- Acute massive pulmonary embolism from a thrombus or an air embolism (***50 ml of air***), obstructing more than 50% of pulmonary vasculature leads to severe shock and sudden death.
- Tachycardia, hypotension, pulmonary oedema, raised JVP, gallop rhythm are the features.

6. *Septic Shock*

Septic shock may be due to gram-positive organisms, gram negative organisms, fungi, viruses or protozoal origin.

Gram-negative septicaemia/gram-negative septic shock is called as *endotoxic shock*. It occurs due to gram-negative bacterial infections, commonly seen in strangulated intestines, peritonitis, gastrointestinal fistulas, biliary and urinary infections, pancreatitis, major surgical wounds, diabetic wounds and crush injuries.

Gram-positive septic shock	*Gram-negative septic shock*
• Due to exotoxin by gram +ve bacteraemia like *Clostridium tetani/welchii*, staphylococci, streptococci pneumococci • Fluid loss, hypotension is common; with normal cardiac output	Gram negative bacteria cause endotoxaemia and its effects. Urinary/gastrointestinal/ biliary and respiratory foci are common

Pathophysiology of septic shock

Toxins/endotoxins from organisms like *E. Coli*, *Klebsiella*, *Pseudomonas*, and *Proteus*

↓

Inflammation, cellular activation of macrophages, neutrophils, monocytes

↓

Release of cytokines, free radicals

↓

Chemotaxis of cells, endothelial injury, altered coagulation cascade—SIRS

↓

Reversible hyperdynamic warm stage of septic shock with fever, tachycardia, tachypnoea

↓

Severe circulatory failure with MODS (failure of lungs, kidneys, liver, heart) with DIC

↓

Hypodynamic, irreversible cold stage of septic shock.

Septic shock is typically a *vasodilatory shock* wherein there is peripheral vasodilatation causing hypotension which is resistant to vasopressors. This is due to toxin induced release of isoform of nitric oxide synthetase from the vessel wall which causes sustained prolonged release of high levels of nitric oxide. Magnitude of infection is quantified as (1) *Sepsis* which shows fever, tachycardia, leukocytosis. (2) *Severe sepsis* which shows low tissue perfusion with organ dysfunction (lactic acidosis, dysfunction of liver, kidney, lungs). (3) *Septic shock* with systemic hypotension (BP < 90 mm Hg in spite adequate fluid therapy), severe organ dysfunction (acute lung, kidney, liver injury), maldistribution of blood flow, shunting in microcirculation.

Stages of septic shock

a. *Hyperdynamic (warm) shock*: This stage is *reversible stage***.** Patient is still having inflammatory response and so presents with fever, tachycardia, and tachypnoea. Pyrogenic response is still intact. Patient should be treated properly at this stage. Based on blood culture, urine culture (depending on the focus of infection), higher antibiotics like third generation cephalosporins, aminoglycosides, metronidazole are started. The underlying cause is treated like draining the pus, laparotomy for peritonitis, etc. Ventilatory support with ICU monitoring may prevent the patient going for the next *cold stage of sepsis*.
b. *Hypodynamic hypovolaemic septic shock (cold septic shock)***:** Here pyrogenic response is lost. Patient is in decompensated shock. It is an irreversible stage along with MODS (Multi-organ dysfunction syndrome) with anuria, respiratory failure (cyanosis), jaundice (liver failure), cardiac depression, pulmonary oedema, hypoxia, drowsiness, eventually coma and death occurs (*Irreversible stage).*

Treatment of septic shock

- Correction of fluid and electrolyte by crystalloids, blood transfusion. *Perfusion* is very/most important.
- Appropriate antibiotics—third generation cephalosporins/ aminoglycosides.
- Treat the cause or focus—drainage of an abscess; laparotomy for peritonitis; resection of gangrenous bowel; wound excision.
- Pus/urine/discharge/bile/blood culture and sensitivity for antibiotics.
- Critical care, oxygen, ventilator support, dobutamine/ dopamine/noradrenaline to maintain blood pressure and urine output.
- Activated C protein prevents the release of inflammatory mediators and blocks the effects of these mediators on cellular function.
- Monitoring the patient by pulse oximetry, cardiac status, urine output, arterial blood gas analysis.
- *Short-term (one or two doses) high dose steroid therapy* to control and protect cells from effects of endotoxaemia. It improves cardiac, renal and lung functions. Single dose of methylprednisolone or dexamethasone which often may be repeated again after 4 hours is said to be effective in endotoxic shock.

Septic shock

- Common causes are biliary, urinary, GIT sepsis (peritonitis, strangulation), respiratory (pneumonia)
- Common bacteria are *E.coli, Klebsiella, Pseudomonas*
- Common pathophysiologies are release of toxins, neutrophil activation, cytokine release, and sick cell syndrome, SIRS, MODS
- Clinical stages are hyperdynamic amd hypodynamic
- Find out the source of the infection by U/S, CT scan
- Do pus/blood/urine culture
- Start antibiotics of high generations like ceftazidime, amikacin, cefoperazone
- Dopamine/dobutamine infusion (slow)
- Monitoring by pulse, BP, respiration, urine output, level of consciousness
- Ventilator support, ICU management
- Treat the causes like peritonitis, abscess

7. Anaphylactic Shock

Injections—penicillins, anaesthetics, stings, venom, shellfish may be having antigens which will combine with IgE of mast cells and basophils, releasing histamine and large amount of SRS-A (Slow releasing substance of anaphylaxis). They cause bronchospasm, laryngeal oedema, respiratory distress, hypotension and shock. Mortality is 10%.

Rashes all over the body are commonly observed.

Anaphylactic shock

- Sudden onset
- Distributive shock
- Bronchospasm, laryngeal oedema
- Generalised rashes and oedema
- Hypotension, feeble pulse
- Mortality 10%
- To start adrenaline 100 ug IV, steroids, IV fluids, oxygen with foot end elevation
- Ventilator in severe cases
- Cardiac massage, defibrillation

CLINICAL FEATURES OF SHOCK

- In early stage—tachycardia, sweating, cold periphery, hypotension, restlessness, air hunger, tachypnoea, oliguria, collapsed veins.
- In late stage—cyanosis, anuria, jaundice, drowsiness.

Clinically shock may be:

- *Compensated* with mild tachycardia, normal blood pressure, urine output, normal respiration and mild lactic acidosis.
- *Mild* shock with mild lactic acidosis, tachycardia, tachypnoea and anxiousness.
- *Moderate* shock with significant lactic acidosis, decreased urine, tachycardia, tachypnoea, drowsiness, and mild hypotension.
- *Severe* shock with severe lactic acidosis, anuria, tachypnoea with gasping, severe tachycardia, profound hypotension and unconsciousness.

Shock index is ratio of pulse rate to blood pressure. Normal is < 1. In shock, it reverses.

INVESTIGATIONS IN SHOCK

- Regular monitoring of BP, pulse.
- Heart rate. But in young patients and patients on beta blockers, tachycardia may be masked.
- Respiratory rate.
- CVP line (Central venous pressure).
- PCWP (Pulmonary capillary wedge pressure).
- Pus, urine, blood culture in case of septic shock.
- U/S, CT, X-ray depending on location of pathology or septic focus.
- Measurement of urine output.
- Arterial PO_2 and PCO_2 analysis.
- Electrolyte estimation.
- Blood CBC, pH assessment, pulse oximetry. *Serum lactate estimation* is an important prognostic indicator. Level on admission, high level reach, and level becoming normal should be assessed.

Treatment

Guidelines

- *To treat the cause*
- *To improve cardiac function*
- *To improve tissue perfusion*

Treatment of shock

- First stabilize the patient with initial resuscitation
- Next evaluate the patient for cause and severity
- Lastly treat the specific cause to achieve cure

- Treat the cause, e.g. arrest haemorrhage, drain pus.
- **Fluid replacement:** Plasma, normal saline, dextrose, Ringer's lactate, plasma expander (haemaccel) (maximum 1 litre can be given in 24 hours).

  Initially *crystalloids* then colloids are given. Blood transfusion is done whenever required.

  Fluid therapy is ideally done with crystalloids like normal saline, Ringer's lactate, Hartmann's solution. Blood loss should be corrected by blood transfusion only. Crystalloids and colloids do not have O_2 carrying capacity. Hypotonic solutions like dextrose are poor volume expanders and so should not be used in shock. *Dynamic fluid response* is studied by infusing 500 ml of fluid rapidly in 10 minutes.

  Responders show improvement; *transient responders* show improvement temporarily but revert back to original status probably due to still existing fluid/blood loss or still existing fluid shift from intravascular space; *nonresponders* will not respond as fluid loss is severe and persistently ongoing.

- *Inotropic agents*: Dopamine, dobutamine, adrenaline infusions—mainly in distributive shock like septic shock.

Note:

- Dopamine improves renal and splanchnic blood
- Dobutamine improves the cardiac output
- Adrenaline/Levarterenol IV in anaphylaxis
- Amrinone and milrinone are newer inotropic drugs



Fig. 1.220: Trendelenburg position—head down position, used in patient in shock.

- Correction of acid-base balance. Acidosis is corrected by using 8.4% sodium bicarbonate intravenously.
- *Steroid* is often life-saving. 500-1000 mg of hydrocortisone can be given. It improves the perfusion, reduces the capillary leakage and systemic inflammatory effects.
- Antibiotics in patients with sepsis; proper control of blood sugar and ketosis in diabetic patients.
- Catheterisation to measure urine output (30-50 ml/hour or > 0.5 ml/kg/hour should be maintained).
- Nasal oxygen to improve oxygenation or ventilator support with intensive care unit monitoring has to be done.
- CVP line to perfuse adequately and to monitor fluid balance. TPN is given when required.
- PCWP to monitor very critical patient.
- Haemodialysis may be necessary when kidneys are not functioning.
- Control pain-using morphine (4 mg IV).
- Ventilator and ICU/critical care management.
- Injection ranitidine IV or omeprazole IV or pantoprazole IV.
- *Activated C protein* even though costly is beneficial as it prevents the release and action of inflammatory response.
- *MAST (military antishock trouser): Provides circumferential external pressure of 40 mmHg. It is wrapped around lower limbs and abdomen, and inflated with required pressure. It redistributes the existing blood and fluid towards centre. It should be deflated carefully and gradually.*

Remember

- Response to dynamic fluid therapy can be checked in patient in shock by perfusing 500 ml of fluid rapidly in 10 minutes and patient is checked as nonresponder/transient only initial responder or proper responder.
- Vasopressor like dobutamine is used only in distributive shock like due to sepsis (not in hypovolaemic, haemorrhagic shock where there is low preload).
- Intubation and ventilator may be needed in shock.
- The patient is monitored with ECG, pulse oximetry, blood pressure/invasive blood pressure, CVP/ PCWP, urine output, pupillary reaction (dilated or not), serum electrolytes, arterial PO_2 and PCO_2 analysis.

CENTRAL VENOUS PRESSURE (CVP)

It is a method to measure the right atrial pressure by placing a venous catheter (20 cm) into the SVC (superior vena cava). Commonly for CVP monitoring, a venous catheter is passed through internal jugular vein or infraclavicular subclavian vein to the SVC (used for TPN purpose). Occasionally a long catheter (60 cm) can be passed through basilic vein (not commonly done). Under radiological guidance, initially a needle is passed 3 cm above the medial end of the clavicle, in the hollow between the two heads of sternomastoid muscles, directing towards the suprasternal notch into the right internal jugular vein. Then through a guide wire, a venous catheter is passed into the SVC through right internal jugular vein, which can also be confirmed by changes in flow during inspiration and expiration.

Catheter is connected to saline manometer, taking manubriosternal angle (angle of Louis) as zero point.

Normal value is 2-10 cm of saline.

If less than 2 cm, more fluid is infused.

If more than 10 cm, fluid infusion should be restricted.



Fig. 1.221: CVP cannula. Note the location of tip of CVP line in the SVC (or can be in the right atrium).

Complications of CVP

- Pneumothorax
- Haemothorax
- Injury to brachial plexus and vessels
- Bleeding
- Sepsis
- Catheter displacement

PULMONARY CAPILLARY WEDGE PRESSURE (PCWP)

It is a better indicator of circulating blood volume and left ventricular function.

Catheter used is *Swan Ganz* triple channel pulmonary artery balloon catheter.



Fig. 1.222: CVP line for monitoring and perfusing the patient in shock.

It is used to:

- Differentiate right and left ventricular failure, pulmonary embolus, septic shock
- To measure and monitor cardiac output during the use of inotropic agents, vasodilators and fluid therapy

Procedure

Under strict aseptic precaution, using cannula and guide wire, catheter is passed through internal jugular vein, into the right atrium. Balloon is inflated by 1.5 ml of air and then negotiated into pulmonary artery, until it reaches a small branch and wedges it. Pressure at this point is called as *pulmonary capillary wedge pressure.*

PCWP normally is 8-12 mmHg, considering mid axillary point as zero reference point.

After that, balloon is deflated to get pulmonary artery pressure which is normally 25 mmHg systolic and 10 mmHg diastolic.

PCWP catheter can be kept *in situ* only for 72 hours.

Complications

- Arrhythmias
- Pulmonary artery rupture
- Balloon rupture
- Pulmonary infarction
- Pneumothorax
- Haemothorax
- Bleeding, sepsis, thrombosis

SYSTEMIC INFLAMMATORY RESPONSE SYNDROME (SIRS)

- *SIRS* is systemic manifestations of inflammation due to variety of causes like infection, pancreatitis, polytrauma, burns, transfusion reaction, and malignancy. So it is often categorised as *infectious cause SIRS or noninfectious cause SIRS*. It causes either hyperthermia (>38°C) or hypothermia (< 36°C); tachycardia (pulse > 90/minute); tachypnoea (> 20/minute); total white cell count > 12,000/cu mm, or count < 4000/cumm.



Fig. 1.223: Pulmonary capillary wedge pressure. Note the wedged balloon in the tip of the venous catheter in the pulmonary arteriole.

- It is final common pathway in shock due to any cause (trauma, sepsis, endotoxaemia, burns) where there is failure of inflammatory localisation with vasodilatation, increased endothelial permeability with damage, thrombosis, leucocyte migration and activation.
- It is associated with release of free radicals, abnormal arachidonic acid release, cytokine release, neutrophil sequestration, abnormal NO synthesis, complement activation, DIC.
- It is a part of severely decompensated *reversible shock* which eventually leads to MODS (Multiorgan dysfunction syndrome), a state of *irreversible shock* wherein patient is anuric, drowsy, cold and terminally ill.
- SIRS carries poor prognosis.

Distributive shock is sudden change in vascular capacity leading to shock like in anaphylaxis and adrenal crisis.

MULTIPLE ORGAN DYSFUNCTION SYNDROME (MODS)

- It is progressively becoming irreversible injury of all tissues like *kidney, lungs, liver, GIT*. Lungs and liver are commonly involved (70%). Next organs to be involved are kidney and GIT. Order of involvement of organs in MODS is—lungs → right ventricular failure → liver → kidney. But mortality is higher if kidney and lungs are involved.
- It occurs in critically ill patient after severe trauma, burns, acute pancreatitis, bleeding and sepsis.
- It is more common in elderly, diabetic, smokers, alcoholics, cirrhosis, malnutrition, patients under steroids and cytotoxic drugs, and uraemia.

Hope puts a smile on our face when the heart cannot manage.

- Multiple features related to multiple organ dysfunctions are typical. Oliguria, jaundice, hypotension, drowsiness, respiratory distress are common.
- Platelet microaggregation, acute pulmonary hypertension, ARDS, DIC, circulatory failure with reduced total oxygen utilization in spite of adequate oxygen supply, impaired defense mechanism are the pathogenetic features.
- Respiratory, renal, hepatic, circulatory, coagulative and cardiac failure occurs as an end stage MODS.
- *Primary MODS* is due to a well defined cause like pulmonary contusion, rhabdomyolysis, multiple transfusions.
- *Secondary MODS* occurs as result of host response in SIRS.
- *Management* of MODS is critical care in ICU with ventilator support, haemodialysis, transfusions, antibiotics, proper nutrition in the form of TPN or enteral. MODS stage has got high mortality.

OXYGEN THERAPY

Indications

1. Chest injuries, any severe haemorrhage.
2. Gas gangrene with toxic haemolysis.
3. Coal gas poisoning.
4. Over morphinisation.
5. Pulmonary embolism and fat embolism.
6. Spontaneous pneumothorax, pulmonary oedema, cardiac infarction, pneumonia, cor pulmonale.
7. Cardiogenic shock and acute bronchitis.

27% oxygen is delivered through ventimask (disposable polythene mask) at a rate of 4-6 litres per minute. Oxygen is also given along with positive pressure ventilation.

HYPERBARIC OXYGEN

It is administration of oxygen 1 or 2 atmospheres above the atmospheric pressure in a compression chamber. It increases the arterial oxygen saturation so that oxygen perfusion of tissues will be increased.

Indications

1. Carbon monoxide poisoning.
2. Tetanus, gas gangrene infections.
3. Bedsores, frostbites, necrotising fasciitis.
4. Drenching in paralytic ileus to reduce the nitrogen gas in distended bowel.
5. As a radiosensitizer in the treatment of cancer.

Complications

- Cerebral gas embolism.
- Rupture of tympanic membrane.
- Visual defects.
- O_2 toxicity.
- CO_2 narcosis.
- Respiratory depression.

Contraindication

- Asthma/emphysema.
- High fever.
- Chronic sinusitis.
- Viral infection.
- Pregnancy.

TOPICAL O_2-THERAPY

H_2O_2 to release nascent oxygen in ulcers and abscess.

CARDIAC ARREST

*It is the cessation of the heart. Heart stops contracting***.**

Causes: All causes for shock.

Differences between CVP and PCWP

	CVP		*PCWP*
1.	Technically easier	1.	Requires skilled experts
2.	Normal pressure is 2-10 cm of saline	2.	8-12 mmHg
3.	Gives gross idea about fluid balance	3.	Better and specific
4.	Left ventricular function is not assessed	4.	Left ventricular function is very well-assessed
5.	Not used to differentiate between right and left ventricular function	5.	Very well-differentiated
6.	Can be kept *in situ* as long as desired	6.	Cannot be kept *in situ* for more than 72 hours
7.	Catheter tip is in SVC	7.	Catheter tip is in pulmonary capillary with wedging
8.	Plain tip catheter	8.	1.5 ml air filled balloon tip
9.	Can be used for TPN, fluid infusion, etc.	9.	Can not be used for TPN, or fluid infusion
10.	Complications are easy to tackle	10.	Often difficult to tackle
11.	Not as sensitive and specific as PCWP	11.	Sensitive and specific

Features of cardiac arrest

- No palpable pulse
- Heart sounds not heard
- Cessation of respiration—cyanosis occurs
- Development of unconsciousness
- Pupils start dilating

Critical Period

Once heart and lungs stop, *brain death occurs in 3 minutes*.

Immediate measures

- **A**irway
- **B**reathing
- **C**ardiac compression
- **D**rugs and **D**efibrillator
- **E**CG, **E**ndotracheal tube and **M**onitor

a. **External cardiac compression (massage)**: Patient is laid flat on a *hard surface (never on soft surface)*. Manual compression is exerted over the lower sternum using both hands one over other without bending the elbow at a rate of 60 to 70 per minute. Rib cage damage during procedure can be very well ignored (Heel of right hand is placed over the sternum 8 cm above xiphoid process and left hand is placed over it).

b. Another person at the same time should give *mouth to mouth breathing* at a rate of 20 to 30 per minute after clearing the airway by removing froth and dentures. A bag with mask can be used to ventilate using air or oxygen.

c. Endotracheal intubation and ventilator support.

d. Injection of 1:10,000 adrenaline and 10% calcium chloride intravenously.

e. Sodium bicarbonate 8.4% injection, hydrocortisone injection.

f. Defibrillator, if there is ventricular fibrillation.

g. Analysis of blood gas (PCO_2 and PO_2), and serum electrolytes assessment at repeated intervals.

h. Urinary catheterization, Ryle‘s tube insertion.

i. Monitoring the patient with BP, pulse, respiration, and temperature chart.

Observations to be made are:

- Groin pulse
- Respiration and breath sounds
- Blood pressure
- Pupillary reaction
- ECG activity



Fig. 1.224: Technique of external cardiac massage.



Fig. 1.225: Technique of mouth-to-mouth respiration. Note patient’s nose should be held closed with right hand of the doctor/assistant and with left hand lower jaw should be pushed forward.

Once patient recovers, the cause and sequelae has to be managed properly.

Sequelae are due to hypoxia and circulatory collapse

- Cerebral oedema and permanent brain damage
- ARDS (Adult respiratory distress syndrome)
- Renal failure

Internal Open Cardiac Massage

This method is used when cardiac arrest occurs in the operation theatre during surgery, acute tamponade, and acute bilateral pneumothorax.

Left side thorax is opened through a lengthy incision along 4th or 5th intercostal space. Initially heart with intact pericardium is rhythmically compressed and relaxed using left hand against sternum. Mean while costal cartilages above and below are cut with a knife to have a better exposure. Pericardium is opened in front of the phrenic nerve. Direct cardiac massage is undertaken until heart regains its function and later shifted to ventilatory support and critical care.



Fig. 1.226: Left thoracotomy for open internal cardiac massage.

Defibrillation Technique (Cardioversion)

Apply gelly to the site of electrodes. One electrode at the base of heart to the right of the sternum other over the estimated area of the apex of the heart. ***Ensure that nobody is in contact with the patient***. Activate the defibrillator. Resume ventilation and ECG monitor immediately. After that, monitor continuously, correct the acidosis, catheterise and observe urine output. Arrange for ICU care.



Fig. 1.227: Defibrillator used in case of cardiac arrest.

H. Haemorrhage and Blood Transfusion

> *There are canals (or vessels) in it (the heart) to (every) member. Now if the priests of Sekhmet or any physician put his hands (or) his fingers (upon the head, upon the back of the) head, upon the two hands, upon the pulse, upon the two feet, (he) measures the heart, because its vessels are in the back of the head and in the pulse; and because its (pulsation is in) every vessel of every member.*
>
> —**(Anonymous),** Circa 2500 BC

CHAPTER OUTLINE

- Haemorrhage
- Blood Transfusion
- Blood Substitutes
- Massive Blood Transfusion
- Autologous Blood Transfusion
- Artificial Blood
- Erythropoietin
- Tourniquets
- Disseminated Intravascular Coagulation
- Mechanism of Blood Coagulation

HAEMORRHAGE

Classification

I. Based on the source of bleeding:

a. ***Arterial*** is bright red in colour, spurting like jet along with pulse of the patient.

b. ***Venous*** is dark red, steady and continuous flow. Blood loss may be severe and rapid when bleeding is from femoral vein, jugular vein, other major veins, varicose veins, portal vein, oesophageal varices.

Pulmonary arterial blood is dark red in colour and pulmonary venous blood is bright red in colour.

c. ***Capillary:*** Here bleeding is rapid and bright red. It is often torrential due to continuous ooze.

II. Based on the time of onset of bleeding in relation to any operative procedure:

1. ***Primary:*** Occurs at the time of injury or operation.
2. ***Reactionary:*** It occurs within 24 hours after surgery or after injury (commonly in 4-6 hours).

Precipitating factors	*Common causes*
Coughing	Thyroid surgery
Vomiting	Cholecystectomy
Straining	Major abdominal surgeries
Rise of blood pressure	Circumcision
Restlessness	Hydrocele surgery
Venous refilling during recovery from anaesthesia	Tonsillectomy
Slipping of ligature	
Clot dislodgement	

3. ***Secondary:*** It usually occurs in 14 days after surgery.

Factors	*Common causes*
Infection	Erosion of carotid artery by cancer (secondaries in the neck)
Pressure by drain or bone	Haemorrhoidectomy
Malignancy	Inguinal block dissection

III. Based on the type of haemorrhage:

Revealed haemorrhage	*Concealed haemorrhage*	*Initially concealed but later revealed*
It is visible	It constitutes	Haematuria
external	internal haemorrhage	Haematemesis
haemorrhage	• Liver injury	Melaena
	• Spleen injury	
	• Fracture femur	
	• Ruptured ectopic gestation	
	• Cerebral haemorrhage	
	• Haemothorax	

IV. Based on the duration of haemorrhage:

1. ***Acute haemorrhage:*** It is sudden, severe haemorrhage after trauma, surgery.
2. ***Chronic haemorrhage:*** It is chronic repeated bleeding for a long period like in haemorrhoids, bleeding peptic ulcer, carcinoma caecum, etc. They present with chronic

No problem is too large for God's intervention and no person is too small for God's attention anaemia with hyperdynamic cardiac failure. They are in a state of chronic hypoxia. It is corrected by *packed cell transfusion* not by whole blood itself. Cause has to be treated accordingly.

3. ***Acute on chronic haemorrage:*** It is more dangerous as the bleeding occurs in individuals who are already hypoxic, which may get worsened faster.

V. Based on the possible intervention:

1. *Surgical haemorrhage*—can be corrected by surgical intervention.
2. *Nonsurgical haemorrhage*—is diffuse ooze due to coagulation abnormalities and DIC.

Pathophysiology of Haemorrhage

Bleeding
↓
Hypovolaemia
↓
Low cardiac output
↓
Tachycardia and shunting of blood from splanchnic vessels by venoconstriction so as to maintain perfusion of vital organs like brain, heart, lungs, kidneys
↓
Hypoxia
↓
Activation of cardiac depressants
↓
Anaerobic metabolism and altered cell membrane function causing influx of more sodium and calcium inside the cell and potassium comes out of the cell
↓
Hyponatraemic, hyperkalaemic, hypocalcaemic metabolic acidosis
↓
Lysosomes of cell get lysed releasing powerful enzymes which is lethal to cell itself
↓
SICK CELL SYNDROME

Platelets and coagulants are activated leading to formation of small clots DIC and further bleeding.
↓
Progressive haemodilution leading to ***total circulatory failure.***

Initially there is compensatory hypovolaemic shock and later there is decompensatory hypovolaemic shock which will lead to MODS and death.

DIC, acidosis and hypothermia are the major factors in worsening the situation in haemorrhage.

Clinical Features of Haemorrhage

- Pallor, thirsty, cyanosis.
- Tachycardia, tachypnoea.
- Air hunger.
- Cold clammy skin due to vasoconstriction.
- Dry face, dry mouth and goose skin appearance (due to contraction of arrector pilorum).
- Rapid thready pulse, hypotension.
- Oliguria.
- Features related to specific causes.

Signs of significant blood loss

- Pulse > 100/minute
- Systolic BP< 100 mmHg
- Diastolic BP drop on sitting or standing > 10 mmHg
- Pallor/ sweating
- Shock index (ratio of pulse rate to blood pressure) > 1 (cardiac index)

Measurement of Blood Loss

- Clot size of a clenched fist is 500 ml.
- Blood loss in a closed tibial fracture is 500-1500 ml; in a fracture femur is 500-2000 ml.
- Weighing the swab before and after use is an important method of on-table assessment of blood loss.



Fig. 1.228: Mops used during major surgery should be kept in a rack so that quantity of bleeding during surgery can be assessed approximately.

Classification of haemorrhagic shock (circulatory failure)

Class	*Blood loss*	*Features*
I	Up to 15% (< 750 ml)	Normal
II	Blood loss 15-30% (750-1500 ml)	Palor, thirsty, tachycardia
III	Blood loss 30-40% (1500-2000 ml)	Hypotension, tachycardia, oliguria, confusion
IV	Blood loss > 40% (> 2000 ml)	Rapid pulse, low BP, anuria, unconsciousness, MODS

Rains Factor

Total amount of blood loss =	Total difference in swab weight × 1.5 or Total difference in swab weight × 2 (For larger wounds and larger operations)

- Hb% and PCV estimation.
- Blood volume estimation using radioiodine technique or micro-haematocrit method.
- Measurement of CVP or PCWP.
- Investigations specific for cause: U/S abdomen, Doppler and often angiogram in vascular injury, chest X-ray in haemothorax, CT scan in major injuries, CT scan head in head injuries.

Effects of haemorrhage

- Acute renal shut down
- Liver cell dysfunction
- Cardiac depression
- Hypoxic effect
- Metabolic acidosis
- GIT mucosal ischaemia
- Sepsis
- Interstitial oedema, AV shunting in lung—ARDS
- Hypovolaemic shock—MODS

Treatment

- Restoration of blood loss: By blood transfusion, albumin 4.5%, SAG-M blood, saline, Haemaccel (Gelatin), dextran, plasma infusions.
  Note: One unit of blood should raise 1 gm% of haemoglobin.
- Catheterisation, foot end elevation, monitoring.
- Oxygen support/intubation/ventilator and critical care.
- Pressure, packing and *head down (Trendelenburg)* position to restore BP and blood supply of brain.
- Wound exploration and proceeding, i.e. ligation of the small vessel, suturing the wound part, vessel suturing (anastomosis), excision of the tissues.
- Absolute rest, analgesics, morphine 10-20 mg IM/IV to relieve pain, sedation.
- ICT placing for haemothorax.
- Laparotomy for liver or spleen or mesentery or bowel injuries, suturing, splenectomy.
- Topical applications for local ooze—Oxycel, gauze soaked with adrenaline, bone wax for oozing from bone and other local haemostatic agents (collagen, thrombin).
- In venous haemorrhage, elevation, ligation of vein or in case of large vein suturing of venous wall, pressure bandaging, packing will be helpful.
- Tourniquet are often used in operation theatre for control of haemorrhage in limbs. But it is not advisable as a first aid measure.
- TPN, CVP monitoring, electrolyte management are all equally important.
- Steroid injection, antibiotics, ventilator support are often required.

Management concepts

- Confirm shock, hypovolaemia and haemorrhage by clinical assessment
- Immediate resuscitation by blood, oxygen, fluid
- Identify site of haemorrhage—ultrasound, endoscopy, CT scan, diagnostic peritoneal lavage (DPL), blood tools
- Control of haemorrhage—surgery, endoscopic control, therapeutic embolisation
- Definitive treatment if any
- Sepsis control
- Prevention of coagulopathy by FFP, platelet concentrate, fresh blood
- Critical care management
- End point resuscitation, fluid and electrolyte management, prevention of organ failure

Local haemostatic agents

- Gelatin sponge (Gel foam)
- Oxidised cellulose (Surgicel)
- Collagen sponge (Helistat)
- Microfibrillar collagen powder (Avitene)
- Topical thrombin
- Bone wax (derived from bees wax + almond oil)
- Gelatin matrices (Floseal)
- Topical EACA, topical cryoprecipitate

Ab Gel®
ABSORBABLE GELATINE SPONGE USP
Size :80MM X 50mm X 10mm Approx.
Sterile, Haemostatic, Absorbable Gelatine Base Foam Specially Prepared For SURGICAL USE
Mfg. Lic. No. 130
WARNING : The Sterility of the product cannot be guaranteed if the package bears evidence of damage, or if the package has been previously opened, or wet
Manufactured by
Sri Gopal Krishna Labs. Pvt. Ltd.
SRI GOPAL KRISHNA LABS. PVT. LTD.
CUT HERE
A
B

Figs 229A and B

Every obstacle introduces a person to himself.



Fig. 229C

Figs 1.229A to C: Gel foam (gelatin sponge) is a good haemostatic agent on oozing surface like gallbladder bed after cholecystectomy.



Fig. 1.230: Oxidised regenerated cellulose is very good local haemostatic agent; but it is much costlier than gelatin sopnge.

BLOOD TRANSFUSION

> *This noon I met with Mr (Robert) Hooke, and he tells me the dog which was filled with another dog's blood at the (Gresham) College the other day, is very well, and like to be so as ever. And doubts not its (i.e. blood transfusion) found being of great use to men.*
>
> —**Samuel Pepys,** 1666

Indications

- Acute blood loss following trauma, ≥15% of total body volume in otherwise healthy individuals (liver, spleen, kidney, GIT injuries, fractures, haemothorax, perineal injuries).
- During major surgeries—abdominoperineal surgery, thoracic surgery, hepatobiliary surgery.
- Following burns.
- In septicaemia.
- As a prophylactic measure prior to surgery.
- Whole blood is given in acute blood loss.
- Packed cells are given in chronic anaemia.
- Blood fractions are given in ITP, haemophilias.

Donor Criteria

- Donor should be fit without any serious diseases like HIV1 and HIV2 and hepatitis infections and malaria.
- Weight of donor should be more than 45 kg.

Collection of Blood

Blood is collected in a sac containing 75 ml of CPD (Citrate phosphate dextrose) solution and stored in special refrigerators at 4 degree celcius. CPD blood lasts for 3 weeks.

In stored blood

- RBC's last for 3 weeks
- WBC's are destroyed rapidly
- Platelets also get reduced in 24 hours
- Clotting factors are labile and so their levels fall quickly

Blood Fractions

1. ***Packed cells***
   - It is obtained by centrifuging whole blood at 2000-2300 g for 15-20 minutes.
   - It is used in chronic anaemias, in old age, in children.
   - It minimises the cardiac overload due to transfusion.
   - It can be stored for 35 days at 1°-6°C.
2. ***Plasma:***
   - This is obtained in the same way as packed cells by centrifugation.
   - It is indicated in *burns, hypoalbuminaemia, severe protein loss.*
   - It can be fractionalised into different fragments:
     a. ***Human albumin 4.5%*** is obtained after repeated fractionations and can be stored for several months in liquid form at 4°C**.**
     b. ***Fresh frozen plasma (FFP)*****:** Fresh plasma obtained, is rapidly frozen and stored at –40°C. It contains all coagulant factors. 1 unit of FFP increases the clotting factors levels by 3%. It can be stored for 2 year. Rhesus D positive FFP can be transfused to Rhesus D negative female.

     Uses:
     - Severe liver disease with abnormal coagulation function.
     - Congenital clotting factor deficiency.
     - Deficiency following warfarin therapy, DIC, massive transfusion.
     - To maintain prothrombin time at normal level. Dose of FFP is 15 ml/kg.

c. ***Cryoprecipitate*:** When fresh frozen plasma is allowed to thaw at 4°C, visible white supernatant layer develops and is called as cryoprecipitate which is rich in Factor VIII and fibrinogen. It is stored at minus 40°C and can be kept for 2 year. Cryoprecipitate is used to raise fibrinogen level at a dose to make plasma fibrinogen level 150 mg/dl. It is also used in inherited deficiency of Factor VIII, fibrinogen, Factor XIII, von Willebrand's disease.


IMMUNATE(TM) 250 I.U.
Purified Freeze-Dried Human Coagulation Factor VIII, Virus inactivated – EP
Freeze-dried substance to be reconstituted with 5 ml of Sterilised Water for Injectio
Prior to use see instructions in the package insert.
Immediately after reconstitution administer by the intravenous route (max. 2 ml/mi
Contains no preservative.
Manufactured by:
Baxter AG, Vienna, Austria
Imported & Marketed in India by:
Baxter (India) Pvt. Ltd
Enkay Towers, V Floor
Udyog Vihar, Phase V
Gurgaon, Haryana-122016
Import Licence Number BP-4-79
Retail Price Not to Exceed Rs. 3472/- L.T. Extra
FREE
GOVERNMENT OF KARNATAKA
HEALTH DEPARTMENT
NOT FOR SALE

Fig. 1.231: Purified freeze dried human coagulation factor VIII is available for use in haemophilia patients

d. ***Fibrinogen*** is obtained by organic liquid fractionation of plasma and is stored in dried form. It is very useful in DIC and afibrinogenaemia. It has risk of transmitting hepatitis.

e ***Factor VIII and IX concentrate**:* They are freeze dried part from a large pooled plasma used in haemoplhilia and von Willebrand's disease.

3. ***Platelet rich plasma***: It is obtained by centrifugation of freshly donated blood at 150-200 g for 15-20 minutes.Platelet rich plasma contains 5.5 × 10^9/L platelets in 50 ml plasma. It can be random donor platelet or single donor platelet. Single donor platelet is prepared by plateletapheresis containing 3 × 10^9/L platelets in 200 ml of plasma. One single donor platelet is equal to 8 units of random donor platelet.
4. ***Platelet concentrate:*** It is prepared by centrifugation of platelet rich plasma at 1200-1500 g for 15-20 minutes. Used in thrombocytopenia and drug (aspirin, clopidogrel) induced haemorrhage. Platelet is transfused at a dose of 0.1 unit/kg, when platelet drops below 50,000 with episodes of bleeding.
5. ***Prothrombin complex concentrate (PCC)*** are derived from pooled plasma which contains factors II, IX and X; used in emergency reversal of warfarin therapy in uncontrolled haemorrhage.

SAG-M Blood

A proportion of donations will have plasma removed and will be replaced by crystalloid solution of SAG-M.

S — Sodium chloride.
A — Adenine.
G — Glucose anhydrate.
M — Mannitol.

Advantages

- This allows good viability of cells
- But it is devoid of any protein
- It is very useful in anaemias

Precautions

- For every four units of SAG-M blood, one whole blood has to be given.
- Later for every two units of SAG-M blood, one unit (400 ml) of 4.5% human albumin has to be given.
- Coagulation status and platelet count should be checked regularly.

After grouping and cross-matching, 540 ml of blood is transfused in 4 hours (40 drops per minute), using a filtered drip set.

One litre of blood contains 350 mg of iron. Normal excretion of iron is 1 mg/day. Iron overload can occur after many transfusions. Iron excretion can be increased by desferrioxamine infusion.

Complications of Blood Transfusions (Please also See Table for Entire List)

Febrile reactions: It is the most common complication due to impurities like pyrogens in the blood or in infusion set. Headaches, fever, chills and rigors, tachycardia, nausea are the features. Transfusion is temporarily stopped or the flow is slowed down with administration of antipyretic drug to reduce fever. Often transfusion of that unit needs to be discontinued.

Allergic reaction (3%): Utricaria and allergy to specific proteins in the donor's plasma can occur. Usually it is mild and is treated with steroid and antihistaminics. In severe utricaria that unit of blood is discarded; new washed RBC's and platelets are used.

Acute haemolytic reactions: It is the most dangerous complication. It is due to ABO incompatibility. Usually it is *nonfatal* but occasionally can be *fatal*. It is commonly due to technical error at different levels. It amounts for criminal negligence in court of law. Intravascular destruction causes haemoglobinemia, haemoglobinuria, acute renal failure and DIC. Dyspnoea, chest pain, sweating, fever with chills, tachycardia, hypotension, and cardiac arrest occurs in fatal type. *Jaundice is a common* feature in nonfatal type. Free haemoglobin level in blood will be above 5 mg/dl. Condition is treated as an emergency in critical care unit/ICU. Transfusion is stopped immediately; blood sample of recipient and transfusing blood is sent immediately for two laboratories for rechecking. *Smoky urine* of the patient is typical. Injection hydrocortisone/dexamethasone IV is given immediately. *Fluid therapy*, *alkalization of blood* is done using sodium lactate and sodium bicarbonate. Mannitol 20 gram in 100 ml is infused in 5 minutes; furosemide 120 mg is injected intravenously. Haemodialysis is needed if there is renal failure. Often ventilator support, defibrillator if cardiac arrest occurrs is needed. Correction of acidosis, electrolytes is needed.

Transfusion related acute lung injury: It is due to donor plasma antibody against HLA and leukocyte specific antigens of recipient. Occasionally it is due to recipient's antibody against donor's leukocytes. Features are—breathlessness, saturation drop, fever, hypotension which is observed 4 hours after transfusion. Chest X-ray shows bilateral diffuse infiltrate. They need ventilator support for short period with eventual rapid and complete recovery.

Transfusion related graft versus host disease (TGVH): This *very serious*, very rare complication occurs due to recognition and reaction against host tissues by infused donor lymphocytes. It is common in immunosuppressed, lymphoma, leukaemic patients. Any type of blood products including leukocyte reduced blood can cause the condition. Features are—pancytopaenia, toxic epidermal necrosis, liver dysfunction with *more than 90%* mortality. It is difficult to treat.

Congestive cardiac failure (CCF): It occurs if especially large quantities of whole blood are transfused in chronic severe anaemia, pregnancy, elderly patients, in patients who have cardiac problems.

Complications of blood transfusion

- Congestive cardiac failure
- Transfusion reactions HBV, HCV
  - Incompatibility. Major and minor reactions with fever, rigors, pain, hypotension
  - Pyrexial reactions due to pyrogenic ingredients in the blood
  - Allergic reactions
  - Sensitisation to leukocytes and platelets
  - Immunological sensitisation
- Infections
  - Serum hepatitis
  - HIV infection
  - Bacterial infection
  - Malaria transmission
  - Epstein-Barr virus infection
  - Cytomegalovirus infection
  - Syphilis, Yersinia
  - *Babesia microti* infection
  - *Trypanosoma cruzi* infection
- Air embolism
- Thrombophlebitis
- Coagulation failure
  - Dilution of clotting factors
  - DIC
  - Dilutional thrombocytopenia occurs in patients with massive blood transfusion
- Circulatory overload causing heart failure
- Haemochromatosis in patients with CRF receiving repeated blood transfusions
- Citrate intoxication causes bradycardia and hypocalcaemia. For every four units of blood 10 ml of 10% calcium chloride or gluconate should be infused intravenously
- Iron overload

BLOOD SUBSTITUTES

- ***Human albumin* 4.5%**

  There is no risk of transmitting hepatitis.

  Plasma *fractionation* is done using organic liquids and heat to extract *albumin* which is stored at 4°C for many months. It can be used in patients with cirrhosis, burns, nephrotic syndrome, ovarian hyperstimulation syndrome (occurring after ovarian stimulation with gonadotrophin injections during *in vitro* fertilization (IVF) therapy). One gram of albumin binds with 14 ml of water so it increases the blood volume also. Albumin is infused daily as needed until good response is observed. Albumin is expensive.

- ***Dextrans*** are useful to improve plasma volume. They are polysaccharides of varying molecular weights.

  This is derived from *leuconostoc mesenteroides* bacteria after adding yeast. One gram of dextran binds with 20 ml of water to raise the plasma volume.

  a. *Low molecular weight dextran* (40,000 mol wt) (*Dextran 40, Rheomacrodex*).

     Dextran 40 is very effective in restoring blood volume immediately. But small molecules are readily excreted in kidney and so effect is transitory. It may be useful in prevention of sludging in kidney and hence renal shut down.

  b. *High molecular weight dextran* (*Dextran 110 and Dextran 70*).

  Less effective but long acting and so useful to have prolonged effect.

  Precautions

  1. Blood samples for blood group and cross-matching should be taken before giving dextrans as it interferes with Rouleaux formation of red cells.
  2. Dextrans also interfere with platelet function and so may precipitate abnormal bleeding.
  3. Total volume of dextrans should not exceed 1000 ml.

- ***Gelatin,*** in a degraded form of mol. wt. 30,000S, is used as a plasma expander. Up to 1000 ml of 3.4-4% solution containing anions and cations is given intravenously—***Haemaccel***. But it is less effective than dextran and after 4 hours of its infusion, only 30% remains intravascular.

- ***Hydroxyethystarch:*** It contains starch, sodium hydroxide, ethylene oxide. It is a good plasma volume expander but lasts only for 6 hours.

MASSIVE BLOOD TRANSFUSION

- It is defined as *replacement or transfusion of blood equivalent to patient's blood volume in < 24 hours corresponding to that particular age (In adult it is 5-6 litres, in infants it is 85 ml/kg body weight.)* Or single transfusion of blood more than 2,500 ml continuously
- Massive transfusion is used in severe trauma associated with liver, vessel, cardiac, pulmonary, pelvic injuries. Often it is required during surgical bleeding (primary haemorrhage on table) of major surgeries

- Adverse effects of massive transfusion
  - a. Severe electrolyte imbalance (hypocalcaemia, hyperkalaemia, acidosis)
  - b. Coagulopathy—altered platelet and coagulation factors.
    - – Dilutional thrombocytopenia
  - c. Citrate toxicity
  - d. Hypothermia
  - e. Poor oxygen delivery—due to reduced 2,3 DPG
  - f. Infections
  - g. Incompatibility and transfusion reactions
  - h. ARDS, DIC

AUTOLOGOUS BLOOD TRANSFUSION

An healthy individual with no infection and haematocrit of $\geq$ 30% can predonate blood few weeks prior to any elective surgeries which in turn can be used at the time of surgery.

Autologous blood is used in orthopaedic, gynaecologic and urologic surgeries. Patient donates one unit of blood weekly; last one if at all being 72 hours before the date of surgery.

Recycled Blood

In major surgeries if there is significant blood loss, then patient's bled blood is carefully sucked out through a sterile system and is filtered and reused again to the patient. This will reduce the number of transfusions.

ARTIFICIAL BLOOD

1. *Perfluorocarbon (Fluosoleda)*—abiotic substitute as synthetic oxygen carrier. Its half life is 7 days. It is RBC substitute.
   - It has got high affinity for O_2.
   - It is inert, colourless, odourless, dense, poorly soluble liquid.
   - It is biocompatible.
   - It is emulsified with albumin or lipids before infusion. Its emulsion alone injection can cause pulmonary embolism.
   - It can bind and release oxygen. But as it reduces the PPO_2 quickly, it is a disadvantage. Patient ideally to be kept in hyperbaric place.
2. *Stroma free haemoglobin*—biomimetic haemoglobin based substitute.
3. *Chelates which reverse bound O_2*.
   - Intraoperative—salvage of blood: On table blood is collected, washed, filtered and transfused. Used in trauma.

ERYTHROPOIETIN

- Injection 1000-3500 units preoperatively also used to increase the RBC count.
- It is used in CRF patients who are on haemodialysis. It is given twice weekly but it is costly.

TOURNIQUETS

Tourner means to turn (Greek). A tourniquet is used to cut off the blood supply to a limb temporarily so that a bloodless field is created while performing the surgery. Limb should be exsanguinated before applying/inflating the cuff of the tourniquet. It is done using a bandage or pressurized Rhys-Davis exsanguinator. A tourniquet is applied in mid-thigh above the knee joint in lower limb and in mid-biceps level above the elbow in upper limb. It should not be closer to joints. It is not applied over the forearm or leg. It is applied over layers of gauze or cotton, not over a bare skin. Pressure used in upper limb is 250 mmHg; lower limb is 300 mmHg (In children, it is 150 and 250 mmHg for upper and lower limbs respectively).



Fig. 1.232: Esmarch rubber tourniquet.



Fig. 1.233: Automatic gauged pressure tourniquet.

Uses

- To attain bloodless field in limb surgeries—upper and lower limbs, orthopaedic surgeries, soft tissue tumours, amputations.
- It is used (rubber tourniquet) to access veins for IV injections and IV sampling.
- Tourniquet is used in diagnostic tests for varicose veins, purpura (ITP), carpal tunnel syndrome, tetany.
- It is used as a first aid in bleeding conditions of limbs, snake bite (it is controversial).

- Tourniquets are often used for small procedures in fingers and toes.

Types

- **Rubber tourniquet:** Simple red rubber catheter is used for drawing blood, to have access to veins.
- Martin's tourniquet made up of India rubber.
- **Pneumatic tourniquet:** Used in limbs, will give the arterial pressure and also acts as a tourniquet (Sphygmomanometer cuff is simpler and easily available type).
- Esmarch rubber **elastic bandage tourniquet.**
- Conn pneumatic tourniquet is manually operated tourniquet where air is pumped up to the required pressure.
- Specialised sophisticated tourniquets are available which gauge pressure and time accurately—automatic tourniquet.

Tourniquet time for upper limb is one hour and for lower limb is two hours.

Contraindications

- In all peripheral vascular diseases and atherosclerosis.
- Infection.
- Deep venous thrombosis.
- Crush injuries.
- Sickle cell disease.

Complications

- Crushing effect on muscles in thigh occurs leading to crush syndrome.
- Tourniquet palsy in upper limb (radial nerve involvement)—neuropraxia.
- Infection.
- Improper application of tourniquet leads to more bleeding.
- Forgetting the removal of tourniquet or taking more time to release may compromise the blood supply of the limb leading to severe ischaemia and gangrene.
- Skin blistering and necrosis.

DISSEMINATED INTRAVASCULAR COAGULATION (DIC)

DIC is a manifestation due to wide spread intravascular coagulation resulting in microthrombi formation, consumption of platelets and clotting factors and production of breakdown products eventually leading into severe bleeding and tissue ischaemia.

Causes

- Major trauma causes DIC due to release of tissue thromboplastin. Burns, major surgery can also cause DIC.
- Sepsis is the most common cause of DIC. Common sepsis causing DIC are gram-negative, meningococcal, malarial, histoplasmosis, aspergillosis, etc.
- Acute pancreatitis can cause DIC by releasing proteolytic enzymes which activate prothrombin and factor X.
- Septic abortion, abruption, retained dead foetus, amniotic fluid embolism are obstetric causes of DIC.
- Carcinoma of pancreas, prostate, acute promyelocytic leukaemia often cause DIC.
- Haemolysis, snake bite, liver dysfunction are other causes.

Types of DIC

- *Acute DIC* presents with bleeding in gums, GIT, venepuncture site, haematuria, petechiae, oozing from surgical or traumatic wounds. Massive bleeding also can occur.
- *Chronic DIC* is a low grade type with thrombotic features.

Investigations

- In DIC—bleeding time, platelet counts are reduced. Thrombin time (TT), prothrombin time (PT) and activated partial thromboplastin time (APTT) are prolonged. Fibrinogen degradation product (FDP), D-dimer test are raised.
- Complete haematocrit, investigations relevant to cause, renal function tests, LFT, electrolyte estimation, blood/discharge/pus/urine culture.

Coagulation cascade system:



Treatment of DIC

- *Treatment of specific cause* as per protocol. Correction of haemodynamic instability by fluid therapy, transfusion of packed cells or whole blood. Dopamine/dobutamine therapy.
- *Factor replacement—specific therapy* for DIC—FFP, cryoprecipitate, platelet concentrate transfusions are essential. FFP is given at a dose of 15 ml/kg. Cryoprecipitate is used to raise fibrinogen level at a dose to make plasma fibrinogen level 150 mg/dl. Platelet is transfused at a dose of 0.1 unit/kg, when platelet drops below 50,000 with episodes of bleeding.
- Heparin use is often controversial. It is used *mainly* in chronic DIC, DIC with purpura, DIC of obstetric cause, cancer induced DIC, DIC due to acute antiphospholipid antibody syndrome.
- EACA, tranexamic acid can be used but with questionable benefits.

MECHANISM OF BLOOD COAGULATION (HAEMOSTASIS)

Haemostasis is the spontaneous arrest of bleeding. When an injury occurs ***platelet adhesion*** occurs to injured vessel/capillary wall which activate the release of ADP (Adenosine diphosphate) which makes more platelet to aggregate (***platelet aggregation***). These activated platelets release thromboxane A_2 which further increases the adhesion and aggregation of platelets. Circulating fibrinogen binds to an activated platelet receptors glycoprotein IIb and IIIa and fibrinogen gets converted into fibrin.

Clotting factors are proteins synthesized by the liver which with a series of cascade reaction activates clotting factors and achieves blood coagulation by a complex mechanism. Factor II, VII, IX and X are vitamin K dependent for their synthesis in liver (carboxylation of glutamic acid). In the process of coagulation each factor gets activated to an enzyme by partial proteolysis which in turn activates other needed coagulation factors. Eventually fibrinogen gets converted into soluble fibrin and later into insoluble ***fibrin.***

Two types coagulation system are there:

- *Intrinsic pathway*
- *Extrinsic pathway*

In vitro coagulation occurs by intrinsic coagulation system. Cascade gets activated by vessel wall injury, shear stress of vessel or other factors. It activates the cascade to get final result.

Coagulation Cascade System

Blood clotting factors

Factor No.	***Common name***
I	Fibrinogen
II	Prothrombin
III	Thromboplastin
IV	Ionic calcium
V	Hereditary labile factor, activator (AC) globulin, proaccelerin
VI	Accelerin,supposed to be active form of Factor V
VII	Proconvertin; serum prothrombin—conversion accelerator (SPCA)
VIII	Antihemophilic factor (AHF)
IX	Plasma thromboplastin component (PTC; Christmas factor)
X	Stuart-Prower factor
XI	Plasma thromboplastin antecedent (PTA)
XII	Hageman factor
XIII	Fibrin stabilizing factor, fibrinase
XIV	Prekallikrein
XV	Kallikrein
XVI	Platelet factor

Hemophilia and *von Willebrand's disease* are the two most common inherited bleeding disorders due to deficiency of factor VIII.

Factor VIII has two components; smaller one—factor VIII C is needed for activation of factor X in intrinsic coagulation pathway; its deficiency leads to *classic hemophilia*. It is inherited as an X-linked recessive trait, thus it occurs in males and homozygous females. The larger component of factor VIII called *von Willebrand's factor,* facilitates the adhesion of platelets to subendothelial collagen, hence crucial for hemostasis, its absence leads to *von Willebrand's disease.*

Classic haemophilia is called haemophilia A is caused by deficiency of factor *VIII C* with X linked *recessive* trait. It occurs in males or homozygous females. Recurrent haemarthroses is a common presentation. Petechiae and echymoses are absent. Bleeding time is normal but coagulation time is prolonged. Treatment is replacement of factor VIII haemophilic factor. If not known patient may go for a life-threatening bleeding even after dental extraction.

Von Willebrand's disease is deficiency of larger component (99%) of the factor VIII-vWF. It is an autosomal *dominant* disease with normal bleeding time and normal platelet count. Common presentations are spontaneous bleeding from mucous membrane, excessive bleeding from wounds and severe menorrhagia. Haemarthroses is not common in von Willebrand's disease. Treatment is replacement of specific factors.

Haemophilia B also called as *Christmas disease* is due to factor IX deficiency is inherited as X linked autosomal recessive trait.

Action, to be effective, must be directed to clearly conceived ends.

I. Burns

> *The infusion of large quantities of fluid, mainly a salt solution, as many as 3-4 litres daily, has proved satisfactory. Sometimes a life is saved if not more than one-quarter of the body surface has received a third-degree burn…. I have given blood transfusions to two patients with severe burns, with recovery in one case and postponement of death in the other.*
>
> **—Gustav Riehl,** 1925

CHAPTER OUTLINE

- Burns
- Management of Burns
- Eschar
- Contracture in Burn Wound
- Electrical Burns
- Inhalation Injury
- Chemical Burns

BURNS

Types of burns

- Thermal injury
  - Scald—spillage of hot liquids
  - Flame burns
  - Flash burns due to exposure of natural gas, alcohol, combustible liquids
  - Contact burns—contact with hot metals/objects/materials
- Electrical injury
- Chemical burns—acid/alkali
- Cold injury—frost bite
- Ionising radiation
- Sun burns

Classification of Burns

Depending on the Percentage of Burns

Mild (Minor):

- Partial thickness burns < 15% in adult or <10% in children.
- Full thickness burns less than 2%.
- Can be treated on outpatient basis.

Moderate:

- Second degree of 15-25% burns (10-20% in children).
- Third degree between 2-10% burns.
- Burns which are not involving eyes, ears, face, hand, feet, perineum.

Major (severe):

- Second degree burns more than 25% in adults, in children more than 20%.
- All third degree burns of 10% or more.
- Burns involving eyes, ears, feet, hands, perineum.
- All inhalation and electrical burns.
- Burns with fractures or major mechanical trauma.

I. Depending on thickness of skin involved

a. ***First degree***: Here the epidermis looks red and painful, no blisters, heals rapidly in 5-7 days by epithelialization without scarring.

Rule of Nine (Wallace's rule of "9")

	Adults	***Children***	***Infants***
Head and neck	9%	18%	20%
Front of chest and abdominal wall	9 × 2 = 18%	18%	10 × 2 = 20%
Back of chest and abdominal wall	9 × 2 = 18%	18%	10 × 2 = 20%
Lower limb	18 × 2 = 36%	13.5 × 2 = 27%	10 × 2 = 20%
Upper limb	9 × 2 = 18%	18%	10 × 2 = 20%
Perineum	01%	01%	
	100%	**100%**	**100%**

Note: It is head and lower limb percentage which differ in adults and children.


9
9+9
9
9
9+9
1
9
+
9
9
+
9
Adult
A
18
9+9
9
9
9+9
1
13.5
13.5
Child
B

Figs 1.234A and B: Percentage of burns in (A) Adults; (B) Children



Fig. 1.235: First degree burn.



Fig. 1.236: Second degree burns with blisters.



Fig. 1.237: Extensive third degree burns with eschar.



Fig. 1.238: Extensive burns more than 50%.


First-degree
Superficial partial-thickness
Deep partial-thickness
Full-thickness

Fig. 1.239: Degrees of burns.

b. ***Second degree***: The affected area is mottled, red, painful, with blisters, heals by epithelialisation in 14-21 days.
  - Superficial second degree burn heals, causing pigmentation.
  - Deep second degree burn heals, causing scarring, and pigmentation.

c. ***Third degree***: The affected area is charred, parchment like, painless and insensitive, with thrombosis of superficial vessels. It requires grafting. Charred, denatured, insensitive, contracted full thickness burn is called as **eschar.** These wound must heal by re-epithelialisation from wound edge.

d. ***Fourth degree***: Involves the underlying tissues—muscles, bones.

Success lies not in achieving what you aim at, but in aiming at what you ought to achieve.

II. Depending on thickness of skin involved

a. ***Partial thickness burns:*** It is either first or second degree burn which is red and painful, often with blisters.
b. ***Full thickness burns:*** It is third degree burns which is charred, insensitive, deep involving all layers of the skin.

Assessment of Burns

- Wallace's rule of nine is used for early assessment—refer figure.
- *Using the Lund and Browder chart* is better method for assessing the burns wound. Here each part of the body is individually assessed for involvement of burns.
- Patient's *entire hand area* is 1%. Clean piece of paper is cut to the size of hand and through that percentage of burns is assessed.

44°C temperature takes 6 hours to cause deep burns. 65°C takes 45-60 seconds to cause deep full thickness burn.

Clinical Features

- History of burn.
- Pain, burning, anxious status, tachycardia, tachypnoea, fluid loss.
- In severe degrees features of shock.

Tolerable temperature to human skin is 40°C for brief period.



Fig. 1.240: 3rd degree burns with charred skin, with thrombosed veins and eschar.



Fig. 1.241: Face burns in an adult—severe 3rd degree.

Pathophysiology

Heat causes coagulation necrosis of skin and subcutaneous tissue
↓
Release of vasoactive peptides
↓
Altered capillary permeability
↓
Loss of fluid → **Severe hypovolaemia**
↓
Decreased cardiac output → Decreased myocardial function
↓
Decreased renal blood flow (Renal failure) → Oliguria
↓
Altered pulmonary resistance causing pulmonary oedema
↓
Infection
↓
Systemic inflammatory response syndrome (SIRS)
↓
Multiorgan dysfunction syndrome (MODS).

There is increased capillary permeability, decreased plasma oncotic pressure causing loss of protein and fluid from intravascular space. Vasoconstriction occurs due to raised capillary hydrostatic pressure leading into cellular aggregation. Blockage of lymphatics causes poor clearance of fluid and proteins from interstitial spaces. Cell membrane function is impaired causing intracellular fluid accumulation. Activation and release of various complement factors, histamine, and prostaglandins results in myocardial dysfunction, oedema of tissues, reduced immunoglobulin synthesis. Catecholamine levels are raised drastically in patient with burn. There will be lipolysis, proteolysis, increased release of glutamine and alanine from skeletal muscles. Urea production is increased due to more proteolysis.

Massive oedema in the body is due to altered pressure gradient because of the injury to basement membrane.

Cardiac dysfunction is due to:

- Hypovolaemia.
- Release of cardiac depressants.
- Hormonal causes like catecholamines, vasopressin, angiotensins.



Fig. 1.242: Burn zones (Jackson's).

Renal changes are due to:

- Release of ADH from posterior pituitary to cause maximum water reabsorption.
- Release of aldosterone from adrenals to cause maximum sodium reabsorption.
- Toxins released from the wound along with sepsis causes acute tubular necrosis.
- Myoglobin released from muscles (in case of electric injury or often from eschar) is most injurious to kidneys.

Pulmonary changes are due to:

- Altered ventilation-perfusion ratio.
- Pulmonary oedema due to burn injury, fluid overload, inhalation injury.
- ARDS.
- Aspiration.
- Septicaemia.

Assessment of airway injury is important in burns

- Occurs in burns around face and neck, or trapped in burning room
- Presents with hoarseness or stridor
- Inhaled burning gases can cause upper airway burns and laryngeal oedema
- Smoke inhalation can cause chemical alveolitis, pulmonary oedema, ARDS and respiratory failure
- Steam inhalation can cause damage to respiratory epithelium and subglottic oedema
- Carbon monoxide inhalation more than 10% is dangerous as it forms carboxyhaemoglobin (CO has got 240 times more affinity to haemoglobin than oxygen) which blocks oxygen transport completely causing respiratory arrest, hypoxia and metabolic acidosis
- Chest wall burn causes mechanical block of ventilation—needs escharotomy in chest wall and procedure is painless
- Airway burn may require early elective intubation or tracheostomy or emergency cricothyroidotomy as a life-saving method

GIT changes are due to:

- *Acute gastric dilatation* which occurs in 2-4 days.
- Paralytic ileus.
- Curling's ulcer.
- Cholestasis and hepatic damage.
- Acute acalculous cholecystitis, acute pancreatitis can occur.

Metabolic Changes

- Hypermetabolic rate (BMR).
- Negative nitrogen balance.
- Electrolyte imbalance.
- Deficiencies of vitamins and essential elements.
- Metabolic acidosis due to hypoxia and lactic acid.

Sepsis in Burn Patient

- Focus may be at the burn site, catheter site, cannula/CVP line site, or respiratory infection.
- Low immunity, loss of proteins and immunoglobulins, loss of barrier causes sepsis. Opportunistic infection is also common.
- Associated conditions like diabetes, HIV infection, old age, respiratory diseases worsen the sepsis in burn injury.
- It may be *local infection commonly* by *Staphylococcus aureus* in early period, *Pseudomonas*, *Candida*, *Aspergillus*, herpes simplex virus in partial thickness nasolabial burns. It may be suppurative thrombophlebitis also.
- *Systemic infection* like pneumonia, bacteraemia, septicaemia can occur.
- Burns itself *creates* immunosuppression.
- Sepsis is identified by fever, lethargy, *leukocytosis, thrombocytopenia*.

Infections are commonly due to:

- Streptococci (Beta haemolytic—most common)
- *Pseudomonas*
- *Staphylococci*
- Other gram-negative organisms
- *Candida albicans*



Fig. 1.243: Burns over chest wall with eschar. Note the extent of involvement.



Fig. 1.244: Deep burns face with eyelid involvement.

Life's disappointments are opportunity's hidden appointment.



Fig. 1.245: Second degree burns in the leg with blebs.

Effects of Burn Injury

- Shock due to hypovolaemia.
- Renal failure.
- Pulmonary oedema, respiratory infection, adult respiratory distress syndrome (ARDS), respiratory failure.
- Infection by *Staphylococcus aureus*, beta haemolytic *Streptococcus, Pseudomonas, Klebsiella* leads to bacteraemia, septicaemia. Fungal and viral infections of dangerous types can also occur.
- GIT: Hypovolaemia, ischaemia of mucosa, erosive gastritis—**Curling's ulcer (seen in burns > 35%).**
- Fluid and electrolyte imbalance.
- Postburn immunosuppression predisposes to severe opportunistic infection.
- Eschar formation and its problems like defective circulation, ischaemia when it is circumferential.
- Electrical injuries often cause fractures, major internal organ injury, convulsions.
- Development of contracture is a late problem. It leads to ectropion, microstomia, disability of different joints, defective hand functions, growth retardation causing shortening.
- Inhalation burn causes pulmonary oedema, respiratory arrest, ARDS.
- Chemical injury causes severe GIT disturbances like erosions, perforation, stricture oesophagus (**alkali**), pyloric stenosis (**acid**), mediastinal injury.
- Other problems commonly seen are DVT, pulmonary embolism, urinary infection, bed-sores, severe malnutrition with catabolic status, respiratory infection.
- Complications of burns contracture itself like hypertrophic scar, keloid formation.
- **Toxic shock syndrome:** It is a life-threatening exotoxin mediated disease caused by *Staphylococcus aureus*. It is common in children, presents with rashes, myalgia, diarrhoea, vomiting, and multiorgan failure with high mortality.

Causes of death in burns

- Hypovolaemia (refractory and uncontrolled) and shock
- Renal failure
- Pulmonary oedema and ARDS
- Septicaemia
- Multiorgan failure
- Acute airway block in head and neck burns



Figs 1.246A and B: Burns hand both palmar and dorsal aspect.



Fig. 1.247: Deep burn in the scalp involving extensively.

MANAGEMENT OF BURNS

First Aid

- Stop the burning process and keep the patient away from the burning area.
- Cool the area with tap water by continuous irrigation for 20 minutes (not cold water as it can cause hypothermia).

Indications for admission in burns

- Any moderate and severe burns
- Airway burns of any type
- Burns in extremes of age
- All electrical/deep chemical burns

Initial management

- Clothing should be removed
- Cooling of the part by running water for 20 minutes
- Cleaning the part to remove dust, mud, etc
- Chemoprophylaxis—tetanus toxoid; antibiotics; local antiseptics
- Covering with dressings by different methods
- Comforting with sedation and pain killer

Definitive Treatment

- Admit the patient.
- Maintain airway, breathing, circulation.
- Assess the percentage, degree, and type of burn.
- Keep the patient in a clean environment.
- Sedation and proper analgesia.
- Patient should be in ***burns unit*** (ideally air-conditioned) with barrier nursing, sterile clothes, bed sheets with all aseptic methods.

Fluid Resuscitation

Formulas to calculate the fluid replacement:

a. **Parkland regime: Commonly used:**
   4 ml/% burn/kg body weight/24 hours.
   Maximum percentage considered is 50%.
   Half the volume is given in first 8 hours, rest given in 16 hours.

b. **Muir and Burclay regime:**

$$\frac{\%\text{ Burns} \times \text{Body weight in kg}}{2} = 1\text{ Ration}$$

   3 Rations given in first 12 hours.
   2 Rations in second 12 hours.
   1 Ration in third 12 hours.

c. **Galveston regime (pediatric):**
   5000 ml/m^2 burned + 1500 ml/m^2 total

d. **Modified Brooke formula:**
   First 24 hours:
   RL: 4 ml/kg/% burns in 24 hours
   (first half in first 8 hours)
   Colloid—none.
   Second 24 hours:
   Crystalloids—to maintain urine output
   Colloids—0.3 ml to 0.5 ml/kg/burns in 24 hours.
   (Albumin in RL solution) (Albumin alone should be given with care if really indicated only).

e. **Evan's formula:**
   In first 24 hours:
   Normal saline 1 ml/kg/% burns
   Colloids 1 ml/kg/% burns
   5 % dextrose in water, 2000 ml in adult.
   In second 24 hours:
   Half of the volume used in first 24 hours.

Fluids used are normal saline, ringer lactate, Hartmann fluid, plasma. Ringer lactate is the fluid of choice. Blood is transfused in later period (after 48 hours).

First 24 hours only *crystalloids* should be given (Crystalloids are one which can pass through capillary wall like saline either hypo, iso or hypertonic, dextrose saline, Ringer lactate).

Sodium is assessed by formula: 0.52 mmol × kg body weight × % body burns, given at a rate of 4.0 to 4.4 ml/kg/hour.

After 24 hours up to 30-48 hours, *colloids* should be given to compensate plasma loss (colloids are one which are retained in intravascular compartment). Plasma, haemaccel (gelatin), dextrans, hetastarch are used. Usually at a rate of 0.35-0.5 ml/kg/% burns is used in 24 hours.

- Urinary catheterization to monitor output; 30-50 ml/hour should be the urine output.
- Tetanus toxoid.
- Monitoring the patient: Hourly pulse, BP, PO_2, PCO_2, electrolyte analysis, blood urea, nasal oxygen, often intubation is required.
- IV ranitidine 50 mg 8th hourly.
- **Ryle's tube insertion initially for aspiration purpose later for feeding** *(Enteral feeding).*
- Antibiotics: Penicillins, aminoglycosides, cephalosporins, metronidazole.
- Culture of the discharge; total white cell count and platelet count at regular intervals are essential to identify the sepsis along with fever, tachycardia and tachypnoea.
- In burns of oral cavity tracheostomy may be required to maintain the airway.
- **Total parenteral nutrition (TPN)** is required for faster recovery, using carbohydrates, lipids, vitamins ***(through a CVP line).***
- Tracheostomy/intubation tube may be required in impending respiratory failure or upper airway block.
- Intensive nursing care.

Local Management

- Dressing at regular intervals under general anaesthesia using paraffin gauze, hydrocolloids, plastic films, vaseline impregnated gauze or fenestrated silicone sheet or biological dressings like amniotic membrane or synthetic biobrane.
- **Open method** with application of silver sulfadiazine without any dressings, used commonly in burns of face, head and neck.
- **Closed method** is with dressings done to soothen and to protect the wound, to reduce the pain, as an absorbent.
- **Tangential excision** of burn wound with skin grafting can be done within 48 hours in patients with less than 25% burns. It is usually done in deep dermal burn wherein dead dermis is removed layer by layer until fresh bleeding occurs. Later skin grafting is done.
  Advantages of tangential excision: *It reduces*—the chance of secondary infection, the hospital stay, and formation of hypertrophic scar or contracture, the cost.
- In burns of head and neck region, exposure treatment is advised.
- Slough excision is done regularly.
- **After cleaning with povidone iodine solution silver sulfadiazine** ointment is used. It is an antiseptic and soothening agent. It causes neutropenia.

If anything is sacred, the human body is sacred.— **Walt Whitman**

Topical agent	*Advantages*	*Problems*
Silver sulfadiazine (1%)	• Antiseptic (G +ve and G –ve)	• Neutropenia, pseudoeschar • It diffuses poorly through the eschar
	• Soothening, good penetration, • Hydration and softening of eschar occurs	• Causes hypertrophic granulation and so not used once wound is clean and eschar is separated
	• It does not cause pain	• Causes wound maceration
		• It should be avoided in pregnancy, nursing mother and infants below 2 years of age
Sulfamylon (5%/11%)	• Antipseudomonal, anticlostridial	• Very irritant, painful
(Mafenide acetate)	• Penetrates very well in to tissues • It is water soluble • It is good antipseudomonal agent	• Causes acidosis, by inhibiting the carbonic anhydrase
Silver nitrate (0.5%)	• Antiseptic	• Stains burnt area
Povidone iodine (5%)	• Antiseptic 0 (G +ve, G –ve)	• Irritant and painful
	• Used on granulation tissue after eschar separation	• Not used in partial burns
	• Used in perineum and buttocks to prevent maceration	
Silver sulphadiazine and cerium nitrate	• Boosts cell mediated immunity and forms sterile eschar	

Other agents used are *Sulfamylon* (***Mafenide acetate***) and *Silver nitrate*.

- ***Sulfamylon*** is antipseudomonal and anticlostridial agent. It penetrates well into the tissues but it is very irritant. It causes acidosis.
- ***Silver nitrate*** causes staining of burnt area.
- 0.025% sodium hypochlorite (Dakin's solution) is effective against Gram +ve organisms; 0.25% acetic acid is effective against Gram – ve organisms, but both mildly inhibit epithelialisation.

Regular culture and sensitivity for bacteria is required, to see for streptococcal growth which should be less than *1,00,000 (10^5) per gram of tissues.*

Wound Coverage

- Once the area granulates well, in 3 weeks usually, split skin grafting is done (SSG, Thiersch graft).
- For wider area MESH split skin graft is used.
- If there is eschar, *escharotomy* is required to prevent compression of vessels.
- In certain areas like face and ear, full thickness graft (Wolfe graft) or flap is required.
- **Cultured skin:** Full thickness skin biopsy of patient's skin is done immediately after admission. By specialized culture technology sheets of skin can be manufactured in 3 weeks as cultured epithelial grafts. It can cover skin of almost entire body. It is usually useful in burns of > 80%. Take up of cultured graft is 60-75%. *Limitations are*—time taken to develop cultured graft; more vulnerability for mechanical trauma; costly; time taken to manufacture; scarring.

Synthetic dressings in burn wound

- Vaseline impregnated gauze dressing prevents stiffness of eschar.
- Hydrocolloid dressing (*duoderm*) helps moist environment, proper epithelialisation. It is useful in mixed deep burns. It is changed once in 3 days.
- *Opsite* is less expensive, with less pain, creates moist barrier. But it does not have antimicrobial effect and it causes accumulation of exudates.
- *Biobrane* is collagen coated silicone sheet which gets adherent to wound acting as barrier without any pain. But it does not have antimicrobial effect and it causes accumulation of exudates. It is used for 2nd degree burns.
- *Transcyte* has similar features of biobrane. It contains growth factor derived from cultured fibroblasts which promotes wound healing.
- *Integra* contains deeper collagen matrix as dermal substitute; outer silicone sheet as epidermal substitute. Inner collagen matrix acts as dermis whereas outer silicone sheet is removed 2 weeks after dressing and additional autograft should be placed. It provides complete wound cover. Scarring after healing is reduced significantly.

Biologic dressings for burn wound

It is used to cover the wound temporarily as a barrier and also to have some immunologic function. Eventually graft will slough. Later wound is covered with auto-skin graft. It is used for massive burn injuries more than 50%. Possible problem is transmission of viral diseases.

Xenograft is of pig skin. *Allograft* is of cadaver skin (homograft)—it gives all existing normal skin function for temporary period. It may leave a dermal equivalent in the wound later.

ESCHAR

- It is charred, denatured, full thickness, deep burns with contracted dermis.

- It is insensitive, with thrombosed superficial veins.
- **Circumferential eschar** in the upper limb, lower limb, neck, thorax can cause more oedema which initially causes venous compression and later arterial compression causing ischaemia, gangrene of the distal part. So distal area should be monitored for circulation.
- If required deep longitudinal full thickness incisions are made in different areas so as to prevent collection of oedema fluid and also to prevent compression over the vessels. This is called as **escharotomy**. Escharotomy causes large quantity of blood loss and so blood transfusion is needed while doing escharotomy. Incision should be of adequate length and depth during escharotomy. It should be placed in such a way so as to avoid injury to major neurovascular system. Release of muscle compartment is needed often in these patients.
- Multiple incisions or incisions over the joints may be needed.
- Early rapid separation of eschar indicates severe sepsis underneath.
- Eventually eschar should be excised and the area is allowed to granulate and skin grafting should be done.
- **Pseudoeschar** is thickened burnt skin due to repeated silver sulphadiazine application.

CONTRACTURE IN BURN WOUND

Contracture in burns can occur anywhere. It is more common wherein flexibility and mobility is present like along the joint, eyelids, cheeks, lips, neck, elbow, knee, etc. Contracture can be *intrinsic* by loss of tissue or *extrinsic* by pull during healing phase contraction. Contracture proceeds towards position of comfort until it meets or closely reaches opposite surface. There is clearly wound shortening. Disorganised over formation of compact collagen (3 times normal) causes hypertrophic scar leading further contracture.

Deficit of neck extension is graded, normal > 110°; E_1 95-110°; E_2 is 85-95°; E_3 is < 85° with mentosternal synechia.

Classification of Burns Contracture in the Neck (BM Achauer)

- Mild (less than 1/3rd)—inability to see ceiling.
- Moderate (1/3rd to 2/3rd)—flexion is possible but not extension.
- Severe (more than 2/3rd)—fully contracted in flexed position with pull on lower lip.
- Extensive—contraction is extensive with mentosternal adhesions.

Ifeanyichukwu has classified neck contracture into: Type 1—mild anterior with narrow contracting band less than fingerbreadth (1a) or broad band (1b); *type 2*—moderate anterior with narrow band (2a) or broad band (2b); *type 3*—severe anterior mentosternal adhesion with supple neck skin (3a) or without supple skin (3b); *type 4*—posterior with narrow band (4a) or multiple or broad band (4b).

Reconstruction territories in neck in burn contracture based on functional benefits are—central above; central below; central above and below; lateral.

Complications of Burns Contracture

- Ectropion of eyelid causing keratitis and corneal ulcer.
- Disfigurement in face.
- Narrowing of mouth **microstomia.**
- Contracture in the neck causing restricted neck movements.
- Disability and nonfunctioning of joints due to contracture.
- Hypertrophic scar and keloid formation.
- Repeated breaking of scar and infection, ulcer, cellulitis.
- Pain and tenderness in the scar contracture.
- ***Marjolin's ulcer:*** It is a very well-differentiated squamous cell carcinoma occurring in a scar ulcer due to repeated breakdown *(unstable scar of long duration).*
  - It is locally malignant.
  - As there are no lymphatics in the scar, so there is no spread to lymph nodes.
  - As there are no nerves in the scar it is painless.
  - It has raised and everted edge with induration.
  - Biopsy confirms the diagnosis.

Treatment: *Radiotherapy is not given* for Marjolin's ulcer. Treatment is either *wide excision* or *amputation. It is curable.*

Once it spreads out of the scar tissue it behaves like any other squamous cell carcinoma and so can spread to regional lymph nodes.

Treatment for Contracture

- Release of contracture surgically and use of skin graft or "Z" plasty or different flaps. *Different flaps* used are—transposition flaps, vertical or transverse; laterally based flap; bilobed flap; bipedicled flap; advancement flap; regional flap; random cutaneous flap (*Epaulette flap, Charretera flap*); fasciocutaneous/myocutaneous flap; tube flap; expanded skin flap; combined skin graft and flap; microvascular free flap.
- Proper physiotherapy and rehabilitation is essential.
- Pressure garments to prevent hypertrophic scars.
- Management of itching in the scar using aloe vera, antihistamines and moisturizing creams.

Problems in Managing Burn Contracture

- Giving proper anaesthesia is challenging.



Fig. 1.248: Ectropion of upper eyelid due to burns.

> *Complete and lasting freedom from disease is but a dream remembered from imaginings of garden of Eden.*
> **— Reni Jules Dubos**



Figs 1.249A to C: Contracture at different parts of the body—chest, face and neck.



Fig. 1.250: Marjolin's ulcer developed over burns scar.



Fig. 1.251: Severe contracture at knee joint causing deformity.



Fig. 1.252: Same patient with knee contracture undergoing release surgery.



Fig. 1.253: Burn contractures over neck and chest wall causing cosmetic problem.



Fig. 1.254: Infant had burns in head and neck region causing severe contracture.



Fig. 1.255: Hypertrophic burn scar with contracture neck in a female.

- Scar excision can cause significant bleeding.
- Identifying major structures in the area and safeguarding vascular and others is often worrisome.



Figs 1.256A and B: Elbow contracture due to burns.



Fig. 1.257: Keloid in the hand after burn injury.

- Need for repeated surgeries as staged one.
- Maintaining the position with skeletal traction, fixation, collar, POP cast, etc.
- Psychological problems and needs counseling.
- Prolonged hospital stay, cost factors.

Prevention of development of contracture

- Joint exercise in full range during recovery period of burns
- Pressure garments for a long period
- Topical silicon sheeting
- Saline expanders for scars

ELECTRICAL BURNS

Types of Electrical Injury

- *Low tension injury:* Less than 1000 volts.
- *High tension injury*: More than 1000 volts—may be due to current itself causing intense damage on the tissues up to 2000°C; flash injury due to electrical arc up to 4000°C; flame injury by catching of fire to the clothing and body; traumatic injury like fractures and internal organ injuries.
- It is always a deep burn (***always a major burn***).
- There is a *wound of entry and wound of exit*.

There is no right way to do something wrong.



Figs 1.258A and B: High voltage electric burn wound of entry in the hand with extensive destruction. Some patient showing wound of exit in the buttock which is extensive and deep.



Fig. 1.259: Wound of entry in an electric burn.

- Patient may also have major internal organ injuries. GIT, thoracic injuries.
- Often convulsions can develop.
- Death may occur due to cardiac arrhythmias (***instant death due to ventricular fibrillation***).
- ***Gas gangrene*** is common after electric injury.
- Release of myoglobin can cause renal tubular damage and ***renal failure***.
- Acidosis is common and so often bicarbonate infusion is needed.
- Patient should *always be admitted* and should be assessed by ECG, cardiac monitor, U/S abdomen, chest X-ray, sometimes even CT scan head, cardiac enzyme analysis.
- Depending on the injury it is managed accordingly.
- Fractures and dislocations are common in electrical injuries which is treated accordingly.
- *Mafenide acetate* is better agent as it penetrates well and it is useful against clostridial infection.
- *Mannitol* is used to prevent myoglobin induced renal failure.

Electrical burns

Types	***Treatment***	***Complications***	***Monitoring and prevention***
High voltage—can cause ventricular fibrillation, cardiac arrest, death. Extensive organ and surface injuries with fractures. *Low voltage*—deep burn at the site of wound of entry.	Emergency resuscitation Assessment of burn Prevention of renal failure by hydration, dialysis, alkalization of urine to clear myoglobin, mannitol therapy, IV sodium bicarbonate. Extensive fasciotomy, debridement. Infection control. Reconstruction.	• Neurological like epilepsy, haemiplegia, aphasia, memory loss, headache. • Cardiac—arrhythmias. • Vascular injuries—major vessels, bleeding. • Compartment syndromes. • Ischaemia, gangrene of limbs. • Contracture development. • Bronchopneumonia, pleural effusion. • Abdominal—ileus, erosive gastritis, Curling ulcer, injury to liver, pancreas, spleen, GIT. • Bone and joint injuries. • Cataract can occur in high voltage burn. • Severe potassium deficiency is common.	**Monitoring:** ECG, echocardiography Relevant investigations like X-ray, ultrasound, CT, electrolytes, urine analysis, LFT, renal function tests. **Prevention:** Care during electrical work and with electrical system. Unused outlets should be sealed with plastic. Electrical system should be away from water source.

- Wound excision, amputation, surgery for internal organ injury, cardiac monitoring are essential part of the surgical management.

INHALATION INJURY

It occurs after major fire burns.
It is due to:

- Inhalation of heat.
- Noxious gases and incomplete products of combustion.
- At the site of fire, oxygen concentration is less than 2% which can cause death in 45 seconds due to hypoxia.
- Inhaled carbon monoxide binds with Hb immediately to form carboxyhaemoglobin causing severe anoxia and death.
- CO has got 240 times more affinity for haemoglobin than oxygen. Carboxyhaemoglobin in blood more than 10% is dangerous; more than 60% is life-threatening.
- Symptoms of carbon monoxide intoxication—headache, disorientation, visual changes, fatigue, vomiting, hallucinations, shock and cardiac arrest.
- Smoke contains hydrocyanide which causes tissue hypoxia and profound acidosis.
- Laryngeal oedema and laryngospasm.
- Bronchial oedema and bronchospasm.
- Formation of *bronchial cast* is typical which is due to oedema, lymph exudation, separation of ciliated epithelial cells from basement membrane. Inhaled gas causes supraglottic airway burn, laryngeal oedema, loss of respiratory epithelium, ARDS, CO poisoning, mechanical restriction of chest wall movement.

Later Problems

- ARDS, pneumonia.
- Atelectasis, pulmonary embolism.
- Pulmonary oedema, pneumothorax.

Clinical Features

- They have low oxygen saturation.
- Charring of mouth, oropharynx with facial burns.
- Carbon sputum.
- Change in the voice, singed facial and nasal hair.
- Decreased level of consciousness with stridor or dyspnoea.
- Acute pulmonary insufficiency with asphyxia, CO poisoning, upper airway obstruction. After 3 to 5 days, ARDS and hypoxia develops. Bronchopneumonia with septicaemia occurs after 5 days.

Management

- Replacing the patient from the site earliest.
- Ventilator support for several weeks.
- Antibiotics.
- Bronchoscopy, at regular intervals to remove bronchial cast.
- Tracheostomy whenever required.
- Hyperbaric oxygen.
- IV heparin to reduce bronchial cast. Heparin nebulisation (10,000 units in 3 ml saline 4th hourly) is also useful. N-acetylcysteine nebulisation—20% in 3 ml saline 4th hourly, bronchodilators like albuterol 2nd hourly is very useful. Hypertonic saline inhalation induces the effective coughing to remove casts. Racemic epinephrine is used to reduce mucosal oedema.

Note:
Steroids are not beneficial in inhalation burns.

- Monitoring the patient with arterial blood gas analysis regularly.

CHEMICAL BURNS

- In chemical burns, tissue destruction is more and progressive. It is always a deep burn.
- **Acid** burn occurs in skin, soft tissues and GIT. In GIT, it is common in **stomach** either due to nitric acid or sulphuric acid which may lead to severe gastritis or pyloric stenosis. Other acids are formic acid, hydrofluoric acid. They cause metabolic acidosis, renal failure, ARDS, haemolysis. Acidaemia should be corrected by IV sodium bicarbonate.
- *Hydrofluoric acid* is commonly used in industrial areas. It is strongest inorganic acid that can produce corrosion and dehydration. It chelates blood calcium causing hypocalcaemia and arrhythmias. It is managed with water irrigation, application of 2.5% calcium gluconate gel at 15 minutes interval, local intradermal and intra-arterial injection of 10% calcium gluconate. Continuous cardiac monitoring, IV calcium gluconate or calcium chloride administration is needed.
- **Alkali** burns occur in oral cavity and **oesophagus** which leads to multiple oesophageal strictures. Sodium hydroxide, lime, potassium hydroxide and bleach are common alkalis involved. They cause saponification of fat, fluid loss, release of alkali proteinates and hydroxide ions which are toxic.
- ***External chemical burns*** are always deep and cause extensive disfigurement with cosmetic problems.
- *Initial treatment* is dilution with water (***Hydrotherapy).*** It is done using 15-20 litres of running tap water.
- *Neutralisation with antidote should never be done at initial phase* of treatment as it creates exothermic reaction which aggravates the tissue damage. Late neutralisation is done, if required by 0.2% acetic acid in alkali burns, sodium bicarbonate, calcium gluconate 10% gel, topical ziphrin solution in acid burns.
- Treatment should always be with hospitalisation.
- Mannitol diuresis, haemodialysis, calcium gluconate IV, pain relief, serum electrolyte management, TPN, ventilator support are systemic management required.
- Late treatment is reconstruction of the face.
- Oesophageal dilatation or colonic transposition is done for oesophageal stricture due to alkali burn.
- Gastrojejunostomy is done for acid induced pyloric stenosis.
- *Tar burns* are treated additionally with neosprin which contains Tween-80 emulsifier of tar.

- *Cement* is calcium oxide alkali. Its burn is due to hydroxyl ion which is often deep. Treatment is removal of cloth, irrigation with water, keeping pH below 8. Often it may form eschar.

Medicolegal and ethical aspects in burns

- Police should be informed whenever a female, pregnant patient arrives with burns
- Consent for high-risk should be taken especially in burns > 30%
- Burns should be assessed whether it is accidental or homicidal
- Relatives should be informed about the duration of stay, problems, repeated surgeries
- In patients with severe burns who is likely to die, when suspected, dying declaration should be arranged
- Cost of therapy, long duration of stay and cosmetic problems should be informed to the relatives

J. Trauma

CHAPTER OUTLINE

- Triage
- Spinal Injury
- Neck Injuries
- Bullet Injuries
- Blast Injuries
- Penetrating Injuries
- Abdominal Trauma
- Blunt Trauma of Abdomen
- Duodenal Injury
- Pancreatic Injury
- Small Bowel Injury
- Colonic Injury
- Liver Injury
- Splenic Injury
- Renal Injury
- Urinary Bladder Injury
- Abdominal Compartment Syndrome
- Seatbelt Injuries

Trauma is the major public health problem in all countries.



Fig. 1.260: Trauma causing large tissue defect exposing the bone.

TRIAGE

Triage means *"To sort"* in French.

Triage is a system to attend trauma patients, formulated by *Committee of Trauma of the American College of Surgeons.*

Advanced trauma life support (ATLS) is essential for first hour care of an injured patient.

Pre-hospital trauma life support (PHTLS) is to prevent deaths while injured patients are transported to the hospital.

Types of Triage System

- *Multiple casualties:* Staff and facilities are sufficient but priority is given to life-threatening injuries.
- *Mass casualties*: Staff and facilities are not sufficient to manage. Here those who are likely to have highest chance of survival are given priority.

Assessment of four components

i. Physiologic response
ii. Anatomical injury
iii. Biomechanical injury
iv. Comorbid factors

Triage algorithm

Step One (Assess physiological impact)

Measure vital signs and level of consciousness

- By Glasgow coma scale
- Systolic blood pressure
- Respiratory rate
- Revised trauma score. It is based on airway, laryngeal injury, spine injury, maxillofacial injury

Step Two (Assess anatomical impact)

All penetrating injuries to head, neck, thorax, major burns, fracture bones, pelvic fractures, paralysis

Step Three (Assess mechanism)

Automobile accidents, crash or blast injuries, high energy injuries, fall from more than 20 feet. Bullet injury

Step Four (Assess history)

- Patient's age below 5 years or age more than 55 years
- Cardiac diseases, respiratory and metabolic diseases
- Pregnancy
- Patients with bleeding disorders
- Immunosuppressed individuals

BASED ON THESE STEPS CONSIDER TO SHIFT THE PATIENT TO TRAUMA CENTER and TRAUMA TEAM SHOULD BE KEPT ALERT.
It is important in multiple and mass casualities (fire, blasts, automobile accidents, train accidents).

Management

- Initial evaluation of the patient.
- Physiologic stabilisation.
- Control of haemorrhage.
- Management of thoracic and abdominal injury.
- Management of cranial injury.

I. *Primary Management*

- **A**irway management (blocked by food, vomitus, clot, fallen tongue).

> *During an injury, unsuspected lesions of the spinal cord may cause the most excruciating abdominal pain.*
> **—Theodore Schrire**

- **B**reathing.
- **C**irculation.
- **D**isability and level of consciousness assessment by Glasgow coma scale.
- **E**xposure of the patient from head to toe for final assessment.
- **F**ingers and tubes: Finger evaluation, Foley's catheterisation.

Goals

- Identify life-threatening conditions.
- Decide and implement appropriate treatment to the area of trauma.
- First think to salvage the life, then think to salvage the limb.
- Rapid assessment, rapid resuscitation, rapid stabilisation.
- Optimum, complete care.
- Transport efficiently to higher trauma centre.

Categorise the patient

I: Deceased
II: Walking wounded
III: Immobile wounded
IV: Trapped wounded

Tag the patient accordingly

Red colour : Immediate treatment is required
Yellow colour : Urgent treatment is required
Green colour : Delayed treatment is required
Blue colour : Expectant treatment is required
Black colour : Deceased

AIRWAY
Chin lift
Jaw thrust
Nasal airway
Oral airway
Endotracheal intubation
Tracheostomy
(assess airway patency)

BREATHING
100% oxygen
Assess bilateral chest raise
Assess breath sounds
Use pulse oximetry
Treat flail chest, pneumothorax
Intercostal tube drainage

CIRCULATION
Monitor vitals
Heart sounds
ECG
IV fluids blood transfusion
Treatment of shock
Control of external bleed
Use two IV lines—14G/16G

DISABILITY EVALUATION
Neurological examination
Glasgow coma scale
Pupillary reaction

EXPOSE THE PATIENT FULLY
Undress the patient
Hypothermia assessment
Assess injuries
Examine joints, bones, abdomen, other systems
Look for identification marks

FINGERS AND TUBES
Examine all orifices like P/R, P/V, etc.
Use required tubes like catheter, Ryle's tube

II. Investigations

- X-ray spine, chest, pelvis, extremities.
- CT scan.
- Blood group and cross-matching.
- Arterial blood gas analysis.
- Serum electrolytes.
- U/S abdomen.



Fig. 1.261: Crush injury leg due to road traffic accident.



Fig. 1.262: Ankle injury with open wound.



Fig. 1.263: Degloving injury involving entire left lower limb, perineum, and left groin. Patient has lost scrotum and both testes. There were no internal injuries and vessels and nerves were intact. Patient underwent wound excision extensively and colostomy was done to promote healing of perineal wound and prevent contamination.

III. Secondary Survey

Re-evaluate the patient completely again.

IV. Definitive Care

(All discussed under individual topics.)

Mechanism of Trauma

- Blunt trauma—direct or indirect blunt injury can occur. Seat belt reduces the blunt injury in vehicles.
- Penetrating injury—severity depends on the extent of deeper injury.
- Blast injury.
- Crush injury—earthquake, industrial accidents, and train accidents—causes crush syndrome; compartment syndrome.
- Burn injury.
- Injury in alcohol patients.



Fig. 1.264: Class III dog bite on face in a boy.



Fig. 1.265: Degloving of scalp with bone periosteum exposing the skull bone. Outer table was actually dead and required bone removal and graft after healthy granulation tissue was formed.

Concepts in Trauma Management

- Concept of '*golden hour*' to treat the trauma patient is important.
- Multidisciplinary approach.
- Planning, setting up, organizing, team work.
- Assess respiratory system; circulation; bleeding areas—as priority.
- Assess also whether patient is haemodynamically stable or unstable.
- Arrange fluids, blood, catheters, ventilator, etc.
- Further definitive therapy depending on severity and site of injury.

Damage Control Surgery

- Resuscitation and early therapy in operation theatre itself.
- Minimum but essential surgery to control bleeding and prevent contamination.
- Secondary definitive surgery at a later period to have final control.

SPINAL INJURY

- Assess the type, extent and severity of the injury.
- Careful first aid and transfer to prevent further damage to the spinal cord.



Fig. 1.266: Hand injury involving all fingers.



Fig. 1.267A

Remember what you do not know. It differs you from others.



Fig. 1.267B

Figs 1.267A and B: A person has bitten this patient during a fight and removed the central part of lower lip. It is repaired primarily by Y repair. ***Remember human bites are most dangerous***.

- Assess the sensory loss or motor loss properly.
- Assess fractures clinically, by X-ray and MRI.
- *Central cord syndrome* is common and is due to hyperflexion or hyperextension of the neck in an injured patient causing ischaemia of spinal column due to interfering of spinal artery blood flow.
- *Brown-sequard syndrome:* It is due to partial transection of the cord causing ipsilateral motor function loss and contralateral sensory function loss.
- High dose of steroid is very useful to prevent further damage.
- Rest, traction to neck.
- Decompression of spinal canal surgically by removing bone, disc, haematoma is useful.
- Spinal stabilisation.

NECK INJURIES

Neck is divided into zones for managing neck injuries
- *Zone I*: From clavicle to cricoid cartilage
- *Zone II*: From cricoid cartilage to angle of the mandible
- *Zone III:* Above the angle of the mandible

Indications for Neck Exploration in Injuries

- Expanding haematoma.
- Uncontrolled external haemorrhage.
- Decreased carotid pulse.
- Stridor, hoarseness, dysphonia, haemoptysis.
- Severe dysphagia, odynophagia.
- Blood in oropharynx.

Treatment

- The neck is explored with adequate incision under general anaesthesia.
- The injured structure like vessels, oesophagus, trachea, muscles are sutured.
- Antibiotics.



Fig. 1.268: Degloving scalp trauma and exposed bone is granulating well.



Fig. 1.269: Neck trauma zones.

- Blood transfusion is given as required.
- Ryle's tube for 5-7 days.

Other injuries like head, thorax, abdomen, maxillofacial area are discussed in respective chapters.

BULLET INJURIES

Bullet injury has *wound of entry* and *wound of exit*. Extent of damage is not related to the external wounds. It is related to the travel of bullet inside and extent of blast or cavitation effect inside caused by the bullet. It causes burn damage.

It can damage vessels, organs like liver, spleen, kidneys, bowel, lungs, heart, cranial structures, soft tissues, bones and joints.

Management

- The wounds are explored properly under general anaesthesia.
- All dead tissues and dead muscles are excised.
- Skin is generously and adequately incised.
- Injured nerves are cleaned and silk marker stitches are placed to identify for later secondary suturing (Nerve should not be sutured primarily in bullet injury).
- All foreign bodies are removed.



Fig. 1.270: Multiple pellets over elbow region after gunshot.

- Tendon repair should not be done primarily.
- Wound should not be closed. It should be left open.
- Adequate blood transfusion and antibiotics coverage should be given.
- Major artery or vein are sutured. Vein graft can be used. But *synthetic graft should never be used.*
- Thorough inspection, irrigation and debridement of injured joints is done.
- Immobilisation is done.
- Tetanus toxoid, antitetanus globulin (3000 units IM), antigas gangrene serum is given.
- Second look surgeries at a later period is done once patient has been stabilised.
- Delayed primary closure in 4-7 days or secondary closure in 14 days is done.
- Depending on extent of defect, skin grafting or flaps are used.
- Laparotomy, thoracotomy, craniotomy are done depending on the site of the injury.

BLAST INJURIES

Here extent of damage is much more than bullet injuries.

It creates ***complex blast wave*** which contains ***blast pressure wave*** and ***mass movement of air.***

This explosion pressure wave is more than 1000 pounds per square inch. This pressure wave has got incident pressure and reflected pressure. Both will cause severe damage.

Factors causing the damage

- High pressure wave
- Mechanical injury
- Chemical injury
- Thermal injury
- Inhalation of toxic gases and smoke

Organs Affected

- Ear drums, lungs.
- GIT, brain.
- Skeletal system.

Individual becomes ***deaf*** after blast and so rescue work may be delayed.

Management

- Critical trauma care.
- Management of shock and triage primary manage-ment.
- Urgent surgeries like laparotomy, thoracotomy, craniotomy.
- Massive blood transfusion.



Fig. 1.271: Degloving injury buttock. It needs colostomy to protect the wound from sepsis. Later once skin coverage is done colostomy is closed.



Figs 1.272A and B: Crush injury foot with retained skin from plantar aspect was rotated forward *(Courtesy*: Dr Mayur Rai, Orthopaedician, KMC, Mangalore).



Fig. 1.273: Penetrating injury. Pole missed all the major vessels. Miraculously the patient survived, after a Marathon surgery to tell her tale to her children.

- Antibiotics.
- Ventilator support.
- Management of specific organs like eye, ear.

PENETRATING INJURIES

- It can occur in abdomen, thorax, cranial cavity.
- It causes haemorrhage, damage to internal organs like liver, bowel vessels, lung, pericardium and heart, brain.



Fig. 1.274: Stab wound on the back communicating into the thoracic cavity. Wound was explored and sutured, with an ICT inserted into the thoracic cavity.

- It is life-threatening and immediate surgical intervention is the only treatment. Patient requires adequate amount of blood transfusion, antibiotics, shock management.

ABDOMINAL TRAUMA

It can be:
- Blunt trauma
- Stab injury
- Abdominal wall injury

Abdominal trauma is a major surgical emergency which most surgeons face. It is often associated with head injuries, chest, pelvic and bone injuries. Often patient is unconscious causing difficulty in diagnosing the condition. Often more importance is given to other system injuries like of head, thorax and bones whereas abdominal injury is not addressed properly causing life-threatening consequences. When patient is conscious, history related abdominal trauma is useful. Abrasion over the abdominal skin suggests the possibility of internal injury *(London's sign)*. Distension, tenderness, rebound tenderness, fullness and dullness in the flank when present one should presume internal injury. Tachycardia, hypotension, shock may be evident when there is significant haemoperitoneum. Injuries may be organ injury like of liver, spleen, kidney, pancreas, etc. or bowel injury or retroperitoneal injury which is often under diagnosed or missed. Major vessel injury like of inferior vena cava, mesenteric vessels can cause real threat to life unless it is identified and managed early. 25% of entire trauma patients need surgical exploration of the abdomen.



Fig. 1.275: Traumatic haemoperitoneum.

Abdominal trauma can be *blunt or stab/penetrating or abdominal wall injuries*. Spleen is the most common organ involved in *blunt trauma*. Often in blunt trauma first part of the jejunum or ileocaecal junction gives way (*blow out effect*) due to traction often causing complete transection of bowel horizontally close to the junction. It is due to force of the mobile part of the bowel over the fixed part. Liver is the most common organ involved in *penetrating injuries*.

Injuries of the abdomen may be *closed injuries, compression injuries and penetrating injuries*. Penetrating injuries may be *low velocity injury* like stab injuries or *high velocity injury* like gunshot injuries. Penetration of blunt weapon causes less deep trauma than sharp weapon (sickle, knife). In sickle injury tip and sharp edge moves in curved pattern and so it is often difficult to predict the depth, track and organs injured.

Routinely followed indications for exploration in abdominal trauma are—hypotension without any other cause; bleeding through wound; continuous bleeding in nasogastric tube; evisceration of abdominal content through the open wound except in case of protruded omentum without any hypotension and features of peritoneal irritation; air under diaphragm in blunt abdominal injury (not in penetrating injury as external air gets sucked into the peritoneal cavity through the wound).

Types

- Liver injury.
- Spleen injury.
- Gastric/small bowel/colonic injuries.

- Duodenal injuries.
- Pancreatic injuries.
- Injuries to kidney/bladder/urethra.
- Mesenteric injury.
- Vascular injuries.
- Associated injuries like of diaphragm, lungs.
- Abdominal compartment syndrome.
- Gunshot or blast injuries.



Figs 1.276A to C: Stab injury to LIF by an angry husband to his wife causing left common iliac artery transection injury with aortic partial injury. In spite saphenous vein graft reconstruction patient could not survive (*Courtesy*: Professor Yogishkumar, MS, KMC, Mangalore).

General Clinical Features

- Features of shock—pallor, tachycardia, hypotension, cold periphery, sweating, oliguria.
- Abdominal distension.
- Pain, tenderness, rebound tenderness, guarding and rigidity, dullness in the flank on percussion.
- Respiratory distress, cyanosis depending on the amount of blood loss.
- Bruising over the skin of the abdominal wall.
- Features specific of individual organ injuries.

Investigations

1. Ultrasound abdomen. FAST is *Focused Abdominal Sonar Trauma*: It is rapid, noninvasive, portable bedside method of investigation focusing on pericardium, splenic, hepatic and pelvic areas. Blood more than 100 ml in cavities can be identified. It is not reliable for bowel or penetrating injuries. It often needs to be repeated.
2. **Diagnostic peritoneal lavage (DPL):** It is done in case of blunt injury abdomen. Through a subumbilical lavage catheter one litre of normal saline/Ringer's lactate is infused into the peritoneal cavity. Patient is changed to different positions and side-to-side. Fluid content is aspirated from the abdomen for assessment.
   It has got 98% accuracy rate.

One of the criterias signifies positive lavage

- 10 ml or more of gross blood
- RBC count more than 1,00,000/cumm
- WBC count more than 500/cumm
- Amylase level in the fluid more than 175 IU/dl
- Presence of bile, bacteria, food particles or foreign body

It is the procedure of choice in physiologically unstable patient with blunt abdominal injury (like with spinal injury, unconscious patient).

Contraindications for DPL

- When laparotomy is definitely indicated
- Previous laparotomy
- Pregnancy
- Obesity

3. CT scan is indicated in assessing retroperitoneum, solid organ injuries. It is noninvasive and highly specific.
4. Diagnostic laparoscopy (DL) is valuable method in stable abdominal trauma patient.

Treatment

Emergency laparotomy.

Only bed of thorns can give crown of roses.


Normal saline infusion
Subumbilical incision
Urinary catheter
Peritoneal dialysis catheter
Saline infusion
Siphoned return fluid collection
Return fluid (Red/pink/ clear)
A
B

Figs 1.277A and B: *Diagnostic peritoneal lavage*—incision and technique. 10 French polyvinyl catheter is used. Urinary bladder is emptied by passing a catheter. After injecting xylocaine local anaesthesia into subumbilical region, 2-3 cm vertical subumbilical midline incision is made. Skin, linea alba is incised. Local anaesthesia is infiltrated into the peritoneum again. Peritoneum is held with two haemostats and a purse string suture is placed using polyglactic acid absorbable suture material. Peritoneum is incised for 3 mm length. Catheter (standard peritoneal dialysis catheter) is introduced into the peritoneal cavity. If blood enters the catheter immediately, it means early laparotomy is needed and carried out without continuing the peritoneal lavage. Otherwise, one litre of normal saline is infused into the peritoneal cavity rapidly in few minutes through the catheter using a drip set with elevation of the fluid bottle/bag. Patient is moved well to mix the fluid in all four quadrants. Now bag is lowered below so that fluid from the peritoneal cavity reenters/siphoned into the bag. Collected fluid is analysed for red cells, leukocytes, etc. DPL may not be useful in bowel injury, retroperitoneal injury, diaphragmatic injury, organ haematoma (subcapsular splenic haematoma). If patient is decided for observation catheter can be left *in situ* for repeat DPL after 6 hours. One has to remember that DPL is not a substitute for clinical assessment and monitoring. In *Lazarus-Nelson* approach Teflon catheter with a guide wire is used.



Fig. 1.278: Blunt injury abdomen. Note the bruising over abdominal skin—*London's sign*.

Indications for laparotomy

- ❖ Frank haemoperitoneum
- ❖ Significant diagnostic peritoneal lavage
- ❖ Haemodynamically unstable patient
- ❖ U/S or CT scan shows significant intra-abdominal injuries

BLUNT TRAUMA OF ABDOMEN

It is common in accidents. It is often missed or lately diagnosed. Ultrasound/CT abdomen or diagnostic peritoneal lavage (DPL) is useful. In many cases on clinical grounds direct exploratory laparotomy is done. Plain X-ray abdomen may show gas under diaphragm.

Difficulty arises in *deciding about the need for laparotomy* in abdominal trauma in *unconscious* patients. If severity of external injury is out of proportion to the existing severe shock then exploratory laparotomy is indicated in an unconscious patient. It is also often difficult to diagnose bowel injury in such patients. If it is suspected laparotomy should be undertaken in such patients. Associated spinal injury masks the abdominal findings.

Injuries may be of liver, spleen, GIT, pancreas, mesentery, vascular or diaphragm. Associated chest, pelvis, skeletal and head injuries should be remembered.

Features of Blunt Trauma

- ♦ Features of profound shock, progressive distension of abdomen, pain, tenderness, guarding, rigidity, rebound tenderness, dull flank.
- ♦ Features specific of individual organ injury like obliteration liver dullness in bowel injury.
- ♦ Bruising of skin over the abdomen—*London's sign*.
- ♦ Respiratory distress, cyanosis.
- ♦ Repeated clinical examination is a must in blunt trauma.

Evaluation

Ultrasound Abdomen

- ♦ It is very useful, simpler, noninvasive method of evaluating the abdomen. Negative ultrasound means no immediate further intervention is needed and also conservative treatment can be undertaken.
- ♦ *Advantages of ultrasound:* There is no danger of radiation; it can be done bedside; it can be repeated many times; it

is cost-effective. Its sensitivity is 90%; specificity is 98%. Focused abdominal sonar (ultrasound) for trauma *(FAST)* is very useful method.

- *Disadvantages:* It is less useful in obesity, with interposition of gas, when fluid is less than 500 ml; retroperitoneal injuries and bowel injuries.
- *Focused abdominal sonar trauma (FAST)*: It is rapid, noninvasive, portable bedside method of investigation focusing on pericardium, splenic, hepatic and pelvic areas. Blood more than 100 ml in cavities can be identified. It is not reliable for bowel or penetrating injuries. It often needs to be repeated.

Diagnostic Peritoneal Lavage (DPL) (by Perry)

It is useful in *blunt injury* abdomen. It is not very useful in penetrating injury, bowel injury, retroperitoneal and pelvic injuries.

CT Scan of Abdomen

It is most commonly used and better investigation for abdominal trauma. It is useful in blunt/penetrating trauma, suspected pancreas, spleen, liver, duodenal, retroperitoneal injuries. Smaller injuries, early haemoperitoneum are better detected. It is noninvasive, highly specific, highly accurate (96%), with low false-positive/low false-negative, noninvasive.

Other Investigations

a. *Abdominal diagnostic paracentesis* (Drapanas and McDonald): Here 18 G short bevel spinal needle is inserted into the peritoneal cavity after injecting local anaesthetic agent into the abdominal wall. With continuous suctioning through syringe, needle is passed at various sites. Positive tap means return of minimum of 0.1 ml of nonclotted blood. False-positive result occasionally can occur due to needle puncture of abdominal wall vessels. Needle should not be inserted close to previous abdominal scar as bowel may be adherent underneath the scar. Change of direction of needle is done by withdrawing the needle tip outer to peritoneum and again puncturing the peritoneum. Puncture by 18 G needle of nondistended bowel will seal without any leakage. Peritoneal tap should be avoided if bowel is distended. *Bilateral flank tap/four quadrant tap* is also done with similar result. Rectus sheath haematoma and false-negative results are the problems.

b. *Diagnostic laparoscopy* is very useful. It can be done under local anaesthesia. Haemoperitoneum, solid organ and diaphragmatic injuries are well assessed. But bowel and retroperitoneal injuries are more likely to be missed.

c. *Arteriography* through Seldinger technique is useful in suspected cases of renal arterial injury (thrombosis/spasm); intimal tears, traumatic aneurysm and aortic occlusion (after seat belt injury) are well diagnosed with arteriography. Often it can be therapeutic also. Pelvic bleed extending into retroperitoneum is not uncommon which can be assessed by arteriography and also the bleeding vessel can be identified. But venous bleed cannot be assessed by this.

d. *Doppler assessment of major vessels* may be beneficial especially for IVC, aorta, iliac vessels, and portal system; but with haemoperitoneum visualisation window may be poor and vessels can be better identified by contrast CT scan.

Management Concepts in Abdominal Trauma

- *Evaluation* of extent of the injury; number of organs injured and severity of injury; haematocrit assessment (haemoglobin drop up to 6 gm% is tolerated well with adequate tissue oxygenation. Rapid drop of hemoglobin needs adequate number of blood to be kept ready for transfusion, like 5/10/bottles or more); central line for volume replacement; urinary catheterisation; administration of systemic antibiotics.
- *Autotransfusion of blood* is very useful as a life-saving procedure in such situation. Blood from the cavity is sucked out into a sterile bottle which contains 150 ml of 3.8% sodium citrate dextrose solution. This blood is strained/filtered through gauze and re-transfused. If there is colonic and small bowel injuries auto transfusion is not possible for fear of sepsis due to contamination.
- *Upper midline incision* extending down across the left of the umbilicus is the preferred incision. But surgeon should not be hesitant to extend the incision into the thorax or do horizontal T or extend as needed depending on the internal organ injury.
- *First priority* after opening the abdomen *is immediate control of profuse bleeding using finger compression or mop* or pressure. Later once the field is clean; area is assessed for the extent of injury without releasing the compressed finger on the bleeding site. A vascular clamp or bulldog clamp is helpful in such situation. Once it is applied over the site of bleeding, compressing finger can be removed. Vascular suturing using 4 zero or 6 zero polypropylene/resection of the tissue; reconstruction of the area; persistent pressure mop *in situ* with closure of the abdominal wall with an option of second look surgery in 48 hours are the different options. Individual organs are assessed and graded for injuries and managed accordingly.
- During laparotomy entire abdomen should be inspected/palpated carefully for any additional missed injuries. Lesser sac, retroperitoneum, duodenum, pancreas and diaphragm should be checked. Often peritoneum on the margin of the duodenum and right side colon is incised, duodenum and colon is reflected medially to visualise the retroperitoneum. Pelvic structures need special attention. Rectum, urinary bladder injuries are likely to be missed if proper attention is not given. On catheterization, if urine is clear it means urinary system is normal. Portal venous system should be assessed.
- *Resection or repair* should be decided later once haemostasis is maintained. Whether the injury is to the bowel or organs

(liver/spleen/kidney, etc.) resection or repair approach is decided depending on the severity of individual organ injury (based on scale or grade).

- *Mesenteric tear* may be the cause for haemoperitoneum. Tear may be perpendicular or parallel to the bowel. If it is perpendicular, haemostasis and approximation of the mesentery is sufficient; if it is parallel tear, then blood supply to corresponding bowel may be compromised and resection of that part of the bowel is indicated. Mesenteric haematoma is left alone if small and nonprogressive. Whether there is any colour changes in the adjacent bowel should be observed. If haematoma is large; if it is progressive; if it causes compromised blood supply to the adjacent bowel, then it should be gently evacuated. Mesenteric leaf is opened using curved scissor; clot is evacuated using gentle finger dissection; bleeder is identified and ligated. If there is compromised bowel function, it should be resected. Bleeding from the major vein like superior mesenteric vein is disastrous as tear may not be localised but may be extensive; and even gentle dissection may cause more tear. It is carefully mobilised; vascular clamps are applied and repaired using 5 zero polypropylene sutures.
- **Aortic clamping**: Catastrophic bleeding found after opening the abdomen which cannot be controlled and bleeding with profound hypotension are the indications for aortic clamping. Profuse intraperitoneal bleed comes under control temporarily by tamponade effect of tense abdominal wall and it itself temporarily helps the patient. The moment abdomen is opened; tamponade effect is released causing further rapid bleed leading into critical catastrophe. If such event is expected prior to opening the abdomen very quick rapid thoracotomy (*prelaparotomy thoracotomy*) through left 5th intercostal space is done; left lung is deflated and displaced; pleura over the thoracic aorta is incised; aorta is dissected using finger; vascular clamp or soft intestinal occlusion clamp is applied to occlude the thoracic aorta. Later laparotomy is performed to go ahead with management of the bleeding. If profound bleeding is observed after laparotomy necessitating the aortic clamping, it is done by applying the clamp in infradiaphragmatic part of the aorta. Peritoneum is incised on the right of the abdominal oesophagus in infradiaphragmatic area; aorta is dissected using finger high up close to diaphragm to avoid injury to celiac plexus; clamp is applied across (infradiaphragmatic aortic occlusion).
- *Usually drainage* using tube drains on either side of the abdomen is used even though it is controversial. ICT should be placed if thoracotomy is also undertaken.
- *Jejunostomy* for enteral nutrition is ideal in all major abdominal injuries. Often gastrostomy is also done along with jejunostomy in case of duodenal and pancreatic injuries.
- *Management of individual organs* after grading its severity of the injury—duodenum, pancreas, liver, spleen, bowel, kidney, etc. ***(Please refer individual chapters for detail—highlights of individual organ injury is given below).***
- Management as critical care (ICU with intensivist); multiple blood transfusions; management of sepsis, maintenance of respiration, management of electrolyte changes, treatment of renal failure, provision of nutrition, prevention of DVT, management of DIC are very essential part of postoperative treatment.



Figs 1.279A to C: Traumatic blunt injury abdomen causing small bowel injury which is sutured using interrupted horizontal silk sutures.

DUODENAL INJURY

- Its severity depends on the type and extent of the injury.
- It can be haematoma or lacerations.
- Lacerations can cause duodenal disruption, may be < 50% or > 50% or 75% or more.
- Laceration may extend into the ampulla, distal CBD, pancreas or with duodenal devascularisation.

Grading of duodenal injury

Grade I – Haematoma – Laceration	Involving single portion of the duodenum. Partial thickness injury without perforation.
Grade II – Haematoma – Laceration	Involving more than one portion. Disruption less than 50% circumference.
Grade III – Laceration	Disruption of 50-75% of the circumference of 2nd part of the duodenum; disruption 50-100% of the 1st, 3rd or 4th part of the duodenum.
Grade IV – Laceration	Disruption more than 75% of 2nd part of the duodenum and involving the ampulla or distal common bile duct.
Grade V – Laceration – Vascular	Severe disruption of duodenopancreatic complex. Duodenal devascularisation.

Management

- CT scan is more relevant investigation.
- Associated other injuries should be managed accordingly.
- Haematoma without extension is managed conservatively with nasogastric aspiration, antibiotics and IV fluids.
- Lacerations are sutured surgically with a stenting or often with bypass like gastrojejunostomy.
- ERCP stenting or CBD bypass is also often required.

Complications

- Infection, duodenal leak.
- Peritonitis, haemorrhage.

PANCREATIC INJURY

- It can be in the head or body and tail of the pancreas.
- It may be associated with injury to duodenum or portal or superior mesenteric veins.
- It can be contusion or severe lacerations.

Management

- High resolution CT scan is diagnostic.
- Distal pancreatectomy for injuries distally.
- Conservative treatment is useful with antibiotics, IV fluids.
- Whipple's operation or total pancreatectomy is done as a last resort.
- Drainage of the pancreatic bed is simple and often useful method.

Complications

- Pancreatitis, septicaemia.
- Pancreatic fistula, pancreatic abscess formation.
  Pancreatic injury has got high mortality (> 45%).

SMALL BOWEL INJURY

- It can be blunt injury or stab injury.
- Blunt injury causes disruption of either duodenojejunal region or at ileocaecal region.
- Presentation is like haemoperitoneum or features of peritonitis.
- *Monks localising zones* in the abdomen signify the location of the small bowel injury.
- Presence of pattern bruising over the abdominal wall signifies the small bowel injury and its site. It is called as *London's sign.*

Management

- Plain X-ray abdomen shows gas under abdomen with ground-glass appearance.
- U/S abdomen is useful.
- Laparotomy and closure of the perforation if it is small.
- In presence of extensive bowel injury or multiple injuries, resection and anastomosis is done.
- Any associated injuries should be dealt with accordingly.



Figs 1.280A and B: Assault causing stab injury abdomen. On opening the abdomen, multiple perforations were found in the small bowel and was sutured. Patient recovered well.

COLONIC INJURY

- Left sided injury is treated with proximal colostomy with closure of the wound if it is small, or resection and anastomosis if it is wider area. Closure of colostomy is done at later stages after 3-6 months.
- Small wound over right sided colon can be sutured primarily.
- Ileostomy alone or ileostomy with ileo-transverse anastomosis or right hemicolectomy with ileostomy is indicated in following situations:
  - Extensive peritoneal contamination.
  - Colonic vascular injuries.
  - Haemodynamically unstable patients.
  - Long-term hypotension after trauma.

LIVER INJURY

It can be subcapsular haematoma, lacerations, deeper injuries, lacerations with disruption of hepatic lobes or segments or liver injury with vascular injuries like of inferior vena cava or hepatic veins.

Present with features of haemorrhagic shock, distension of the abdomen, tenderness, rebound tenderness, guarding, rigidity.

- CT is diagnostic tool
- Liver injury is graded depending on involvement of hepatic veins, portal system, biliary system and duodenum
- Often high grade liver injury also can be managed nonoperatively
- *Push* (direct compression); *Pringle* (occluding portal triad at foramen Winslow with fingers temporarily); *plug* by embolisation; *pack* the liver bed; repair of vena cava or portal vein; stenting of biliary tree and hemihepatectomy—are the treatment strategies

Management

- Small tear is sutured.

  For larger tears:
  - Deep sutures.
  - Packing.
  - Debridement.
  - Haemocoagulants.
- Liver resection is not done (not advisable) usually for injuries.
- ***Pringle manoeuvre***—by compressing the porta near foramen Winslow—to control bleeding (not more than 30 minutes).
- Blood transfusions.
- Treatment of associated injuries like of diaphragm, lung, duodenum, colon.
- Antibiotics.

Complications of Liver Injury

- Haemorrhage, septicaemia, bile leak.
- Liver failure, haemobilia.
- Subphrenic abscess, CBD stricture.

SPLENIC INJURY

It can be subcapsular haematoma, laceration or hilar injury.

It can be associated with other organ injuries like left kidney, left lobe of the liver, splenic flexure of the colon or pancreas.

It can cause torrential haemorrhage and shock.

It is the most common organ injured in blunt injury abdomen.

Management

- U/S abdomen, diagnostic peritoneal lavage are the investigations.
- Blood transfusions.
- Splenorrhaphy is done in selected patients so as to save the spleen.
- Splenectomy.
- Management of associated injuries.

Complications of Splenectomy

- Left lung atelactasis.
- Overwhelming postsplenectomy infection (OPSI).
- Pancreatitis and pancreatic fistula.
- Gastric bleeding.
- Subphrenic abscess.

RENAL INJURY

- It is commonly managed conservatively.
- IVU is the investigation of choice in renal injury.
- Surgery is indicated when there is hilar injury, progressive bleeding, failure of conservative treatment or perinephric abscess formation.

URINARY BLADDER INJURY

Intraperitoneal bladder injury occurs in distended bladder. It is treated always by surgical exploration through transabdominal approach. Bladder tear is sutured with keeping a suprapubic cystostomy using Malecot's catheter.

Extraperitoneal injury can be treated conservatively by placing a Foley's catheter for 2-3 weeks.

ABDOMINAL COMPARTMENT SYNDROME

- Normal intra-abdominal pressure is 2-12 mmHg. Abdominal compartment syndrome is increased intra-abdominal pressure *more than 12 mmHg*. It is often sudden, rapidly progressive decreasing the venous return to heart.
- It is common in *multiple traumas*. Ileus, bowel oedema are the factors causing it. It is also seen in retroperitoneal haemorrhage, pancreatitis, long-standing hernia after reduction into the peritoneal cavity.
- Upward displacement of the diaphragm, increased peak inspiratory pressure, peripheral resistance, intrapleural pressure, CVP and PCWP; hypoxia, hypercapnia, acidosis; compression of IVC, decreased venous return to heart, cardiac output and right atrial pressure, decreased visceral and renal blood flow and glomerular filtration; mesenteric venous hypertension; bowel wall oedema and ischaemia—are the effects. Oliguria, respiratory failure, cardiac arrest ensures if abdomen is not decompressed.

Abdominal compartment syndrome (ACS)

Causes	*Features*	*Management*
Multiple trauma and ICU patients—common	Hypoxia, hypercarbia	Bladder pressure assessment
Postoperative ileus	Decreased urine output	Ryle's tube aspiration
Acute abdomen	Hypotension	Resuscitation
Acute gastric dilatation	Tense abdomen—distended	ICU care
Laparoscopic procedures	Decreased venous return	Surgical decompression
Intestinal obstruction	Bowel ischaemia	
	Cardiac arrest	

- Intra-abdominal pressure is measured using a *urinary catheter in the urinary bladder*. Pressure is graded *(Busch)* as I—10-15 cm of H_2O; II—16-25 cm of H_2O; III—26-35 cm H_2O; IV—more than 36 cm H_2O.
- Beyond grade III immediate decompression is needed. Initial *volume preload is essential* otherwise sudden decompression may cause cardiac arrest in asystole due to reduced preload, sudden influx of high potassium, acid and other metabolic by products into the heart.
- Condition is a *surgical emergency*.

Intra-abdominal pressure grading (Busch) in cm of water

I—10-15 cm of H_2O
II—15-25 cm of H_2O
III—25-35 cm of H_2O
IV—more than 35

SEATBELT INJURIES

- In an individual with seatbelt, during impact *violent deceleration* of human body occurs. Seatbelt impinges heavily on its point of contact with trunk and viscera continue to move forward. It leads into severe contusion of abdominal contents; *detachment of bowel from its mesentery* due to free forward rapid mobility of the bowel over a relatively fixed mesentery. Solid organ injury occurs only occasionally.
- *Two point anchorages* causes' solid organ injuries like of liver/spleen. *Lap-belt* causes contusion and bowel injury commonly.
- It is often difficult to identify the injuries due to presence of more obvious other injuries. CT chest and abdomen diagnostic peritoneal lavage (DPL) are very useful.
- Petechiae around iliac crest or costal margin are signs wherein one can suspect seatbelt injuries.
- Distraction fracture of lumbar spine (*chance fracture*) with hyperaesthesia of T12 and L1 level is often associated. 10% of such fractures are associated with intra-abdominal injuries.
- *Treatment* is immediate laparotomy and proceed—bowel suturing/resection/suturing of the organ injuries/splenorrhaphy/splenectomy.

K. Hand and Foot

CHAPTER OUTLINE

- Hand
- Hand Infections
- Acute Paronychia
- Chronic Paronychia
- Apical Subungual Infection
- Terminal Pulp Space Infection
- Infection of Web Spaces
- Deep Palmar Space Infection
- Space of Parona Infection
- Acute Suppurative Tenosynovitis
- Compound Palmar Ganglion
- Orf
- Milker's Nodes
- Hand Injuries
- Dupuytren's Contracture
- Volkmann's Ischaemic Contracture
- Syndactyly
- Mallet Finger
- Heberden's Nodes
- Spina Ventosa
- Foot
- Callosity
- Corn
- Plantar Fasciitis
- Ingrowing Toe Nail
- Onychographosis
- Onychomycosis
- Athlete's Foot
- Hallux Valgus

HAND

Surgical Anatomy of the Hand

Flexor Retinaculum

- It extends medially from pisiform and hook of hamate, laterally to scaphoid tubercle and trapezium crest as a strong fibrous band so as to bridge carpus to create a carpal tunnel.
- Ulnar nerve and vessels, palmar cutaneous branches of median and ulnar nerves, palmaris longus muscle are superficial to the carpal tunnel.
- Median nerve, tendons of flexor digitorum superficialis, profundus and pollicis longus, radial and ulnar bursa are deep to flexor retinaculum.

Palmar Aponeurosis

It is a thickened, modified deep fascia in the palm with its apex pointing proximally (as continuation of palmaris longus) and base distally which in turn gets divided into four parts. They extend over deep transverse ligament into lumbrical tunnel.

Blood Supply of the Hand

- Superficial palmar arch is mainly formed by ulnar artery and completed by superficial palmar branch of radial artery. It gives four digital branches to medial three fingers.
- Deep palmar arch is formed by radial artery and is completed by deep branch of ulnar artery. It gives three palmar metacarpal arteries which communicate with superficial palmar arch. It also gives communicating, perforating branches to dorsal metacarpal arteries.

Muscles of the Hand

- ***Thenar muscles***: Abductor pollicis brevis, flexor pollicis brevis, opponens pollicis and adductor pollicis.
- ***Hypothenar muscles***: Palmaris brevis, abductor digiti minimi, flexor digiti minimi and opponens digiti minimi.
- ***Lumbricals*** are four in number—named from lateral to medial.
- Four ***palmar interossei***.
- Four ***dorsal interossei.***

Nerve Supply

- Abductor pollicis brevis, flexor pollicis brevis, opponens pollicis and 1st and 2nd lumbricals are supplied by median nerve (5 muscles).
- Rest of the muscles in hand are supplied by ulnar nerve (15 muscles).

Modified Verdan Zone System in the Hand (Tendon Zones)

Zone I

From the fingertip up to the attachment of flexor digitorum superficialis (middle of middle phalanx). It contains tendon of flexor digitorum profundus.

Zone II

It begins proximal to metacarpophalangeal joint at distal palmar crease and extends up to the attachment of flexor digitorum superficialis at the middle of the middle phalanx. It is called as "***No-Man's-Land.***" Here flexors are tightly enclosed within a fibro-osseous tunnel. It is the ***most dangerous zone*** in hand injuries (***critical zone***).

Zone III

It begins at the distal end of flexor retinaculum (base of the palm) and ends at the transverse crease of the palm. It contains lumbricals attached to flexor digitorum profundus.

Zone IV

It begins at the proximal end of the flexor retinaculum and ends at its distal end.



Fig. 1.281: Anatomy of flexor retinaculum and palmar aponeurosis.



Fig. 1.282: Modified Verdan zone system in the hand.

Zone V

It extends from the proximal end of flexor retinaculum up to distal third of the forearm.

HAND INFECTIONS

Hand is a compact actively functioning unit. It contains neurovascular bundles, muscles, bones and ligaments.

Infection may be due to minor injuries or blood borne.



Fig. 1.283: Infection of finger at middle phalanx level. Note the oedema and position of the finger.

Precipitating causes

- Diabetes
- Immunosuppression
- Trauma
- HIV infection
- Steroid therapy
- Vascular diseases

Common organisms

- *Staphylococcus aureus—most common*
- *Streptococcus*
- Gram-negative organisms like *E. coli, Klebsiella, Pseudomonas*
- Occasionally fungal infection causing chronic paronychia, Madura hand due to Nocardia group of fungi, viral infection like *orf* can occur

General Features of Hand Infection

- Infection spreads faster in all areas.
- Causes oedema over the dorsum of hand due to lax skin and more lymphatic network even though infection per se is more over the volar aspect. It looks like ***frog hand.***
- Restricted movements of fingers and hand. The hand functions like ***hook***, ***pinch***, ***grip***, ***grasp*** are lost.
- Severe pain and tenderness, with fever.
- Tender palpable axillary lymph nodes are often present.

Different Types of Hand Infections

- Acute paronychia.
- Chronic paronychia.
- Terminal pulp space infection ***(felon)***.
- Subungual infection.

- Web space infection.
- Mid-palmar space infection.
- Thenar space infection.
- Deep palmar abscess.
- Acute suppurative tenosynovitis.
- Chronic tenosynovitis of flexor tendon sheath of palm and forearm—compound palmar ganglion.
- Lymphangitis of the hand.
- Arthritis of hand joints.
- Subcuticular abscess

Hand infection can be superficial or deep; it can be localised or spreading.



Figs 1.284A to F: Different types of hand infections. Note the oedema of hand even on dorsal aspect. Small infective focus can aggravate rapidly and so early proper drainage from deeper plane is important in managing the hand infections. Often it may cause extensive destruction exposing the tendons.

Investigations

- Pus for culture and sensitivity.
- Blood sugar.
- Urine sugar and ketone bodies.
- X-ray of the part.
- Arterial Doppler of the hand if needed.



Fig. 1.285: Hand positions.



Figs 1.286A and B: Hand positions in immobilisation and function.



Fig. 1.287: Hand infection. Infection of ring finger extending into the palm.



Fig. 1.288: Infection of little finger with dorsal oedema.



Fig. 1.289: Hypertrophic scar and keloid in hand and forearm after burn contracture.

General Principles of Managing Hand Infections

- Antibiotic therapy.
- **Position of rest** with wrist slightly abducted and extended, thumb and index fingers away (glass-holding position). *Position of function* is in which thumb and index fingers are pinching firmly with wrist extension.
- Elevation of hand reduces the oedema, increases perfusion, promotes healing.
- Early recognition of localised **pus.** Once localised, **Incision** and **Drainage** is done ideally under general anaesthesia or regional block **(not local anaesthesia).** Draining incision should not cross the palmar crease. Incision should have adequate length and adequate depth (deep to palmar fascia, otherwise evacuation of pus is inadequate). Care should be taken not to injure neurovascular bundles. Pus should be sent for culture and sensitivity. **Slough,** if present should be excised thoroughly. Gauze drain is placed. Regular dressings are done with continuation of antibiotics. Communications into other areas of hand should also be drained.
- **Bloodless field** (using tourniquet) is better to drain pus from hand.
- Proper measures must be taken after treatment. Initial rest, elevation of hand and later proper physiotherapy and regular exercise of hand and fingers are encouraged to restore normal function.

> *Early signs of Volkmann's contracture are pain, pallor, puffiness, pulselessness and paralysis.*
> **—David L Griffiths**

Complications of hand infections

- Stiffness of digits and hand (ankylosis)
- Deformity and disability
- Bacteraemia and septicaemia
- Osteomyelitis of bones depending on the location of abscess like metacarpal bones, terminal phalanx
- Suppurative arthritis of joints
- Paralysis of median nerve

Remember

- Hand should be flexible and strong; sensitive and pain free and coordinated to show all fine and powerful functions
- *Pinch* (picking a small object); *power grip* (holding a hammer); *key grip* (holding a key); *chuck grip* (holding a pen); *hook grip* (carrying a bag)—are the functions of hand
- Hand should be properly examined clinically for tendon functions; neurological problems—sensations (sweat test, two point discrimination test); for circulation (Allen's test); joint movements; examination of entire upper limb; opposite hand; axillary lymph nodes and other relevant systemic examinations
- Nerve conduction studies; electrophysiology; MRI hand; radioisotope bone scan; selective angiograms; X-ray hand are the relevant investigations other than systemic investigations
- Principles of treatment—elevation to reduce oedema; splintage to prevent contracture; early movements once inflammation subsides; early exploration of wound or surgical drainage of infective area; regional anaesthesia; usage of tourniquet; incisions when done across the flexor creases, should be at 45° angle

ACUTE PARONYCHIA

- It is the most common hand infection.
- It occurs in subcuticular area under the **eponychium**.
- Minor injury to finger is the common cause.
- Suppuration occurs very rapidly.
- It tracks around the skin margin and spreads under the nail causing **hang nail** or **floating nail**.
- Organisms are *Staphylococcus aureus* and *Streptococcus pyogenes*.
- Quantity of pus is very less around 0.5 ml but it should be drained to relieve sympotoms.

Clinical Features

Severe throbbing pain and tenderness (dependent throbbing) with visible pus under the nail root. Nail on touch is very tender (paronychia means "**Run around"**).

Treatment

- Pus is sent for culture and sensitivity.
- Antibiotics like cloxacillin, amoxycillin.
- Analgesics.
- The pus is drained by making an incision over the eponychium. Digital block using xylocaine 2% plain (*without adrenaline* as end artery supply to digits can develop arterospasm) is given as anaesthesia.
- If there is a floating nail, then the nail is dead and it has to be removed.
- Recovery is fast.



Figs 1.290A and B: Pointing pus in acute paronychia. Quantity of pus is very less usually around 0.5 ml.



Figs 1.291A and B: Paronychia showing pointing pus in one picture and sloughed area granulating in another picture.

CHRONIC PARONYCHIA

It is commonly due to fungal infection—due to candida infection commonly.

Clinical Features

- It is common in females.
- Nail is diseased with ridges and pigmentation.
- Itching in the nail bed.
- Recurrent pain, discharge
- Secondary bacterial infection may supervene.

Investigation

Culture of scrapings for fungus and other causative agents.

Treatment

- Long-term antifungal therapy—local and systemic.
- Antibiotics for secondary infection.
- In severe cases removal of nail is required.

APICAL SUBUNGUAL INFECTION

- It is infection of the space between subungual epithelium and the periosteum.
- It occurs after minor trauma or rarely after formation of subungual haematoma.
- Beneath the free edge of the nail, pus comes to the surface.
- Excruciating tenderness with small visible pus under the tip (summit) of the nail is the feature.
- Drainage with 'V' incision over the summit is the treatment along with antibiotics.
- Osteomyelitis is not common.

TERMINAL PULP SPACE INFECTION (FELON)

- It is the second most common hand infection (25%).
- Index and thumb are commonly affected.
- Usually by a minor injury like finger prick.



Fig. 1.292: Apical subungual infection and pus formation. Note the 'V' shaped incision to drain the same.

Surgical Anatomy

- Terminal pulp space contains fat and is partitioned by septae which is attached from periosteum of terminal phalanx to skin.
- Proximally deep fascia is attached to the periosteum distal to the base of terminal phalanx, i.e. distal to the attachment of flexor tendon.
- So, terminal space is a closed compartment, as the result of which pressure increases when there is infection, compressing terminal artery leading to thrombosis, resulting in osteomyelitis of terminal phalanx.

Bacteria

- *Staphylococcus*—most common.
- *Streptococcus,* Gram-negative organisms.

Clinical Features

- Pain, tenderness, swelling in the terminal phalanx.
- Fever.
- Tender axillary lymph nodes.

Often suppuration is severe, forming **collar stud abscess** which eventually may burst.



Fig. 1.293: Anatomy of the terminal pulp space.



Fig. 1.294: Pulp space infection.



Fig. 1.295: Incision for pulp space drainage.

Dupuytren's contracture typically affects the ring finger and years later the little finger becomes implicated. In 30% cases little finger is primarily affected.
—Peter F Early

Causes of collar-stud abscess

- Tuberculous cold abscess
- Terminal pulp space infection (Felon)
- Deep palmar space infection

Investigations

- X-ray of the part is required often to rule out osteomyelitis of terminal phalanx.
- Pus for culture and sensitivity.

Treatment

- Antibiotics and analgesics.
- **Drainage** of terminal pulp space by an oblique deep incision.
- If there is osteomyelitis of the terminal phalanx, it has to be amputated.

Complications

- **Osteomyelitis** of the terminal phalanx.
- **Pyogenic arthritis** of distal interphalangeal joint and tenosynovitis of flexor sheath.
- **Septicaemia**—in immunosuppressed individuals.

INFECTION OF WEB SPACES

Surgical Anatomy

There are three triangular web spaces filled with fat between the dorsal and volar skin. When the space is filled with pus it straddles the deep transverse ligament. Even though pus is volar, it points out dorsally.

It originates from:

- Abrasion.
- Infection of proximal volar space of finger.
- Callosities.
- Infection of proximal spaces.
- Trauma.
- Spread from other palmar spaces and from flexor sheaths through lumbrical canal.

Bacteria

- *Staphylococcus.*
- *Streptococcus.*
- Gram-negative organisms.

Clinical Features

- Fever.
- Pain and tenderness.
- Oedema of dorsum of hand.
- **Maximum tenderness** is on the volar aspect.
- **'V' sign—**separation of fingers.
- If untreated, infection may spread into other web spaces and hand spaces.

Treatment

- Elevation of hand.
- Antibiotics and analgesics.
- **Drainage** under regional or general anaesthesia. A **horizontal** incision is placed on volar skin of the web and deepened to reach the space by dividing fibres of palmar fascia. Pus is drained and sent for culture and sensitivity. If other web spaces are involved they should be drained through a separate incision. Edges of the wound are cut to leave a *diamond shaped* opening in front. Often counter-incision over dorsal skin of web is needed.



Fig. 1.296: Incision for web space drainage.

DEEP PALMAR SPACE INFECTION

Surgical Anatomy

Two deep palmar spaces are present

- **Midpalmar space.**
- **Thenar space.**

Midpalmar space is bound in front by palmar aponeurosis, behind by medial three metacarpals, laterally by a vertical line from lateral margin of the middle finger. It contains flexor tendons, neurovascular bundles and lumbricals. It is the common site of the infection.

Thenar space is located anterior to lateral two metacarpals. Infection here is usually due to extension from midpalmar space.

Midpalmar Space Infection

Causes

- Trauma.
- Spread from infection of finger spaces and web spaces.
- Haematogenous spread.
- Spread from tenosynovitis.

Clinical Features

- Pain and tenderness in the palm.
- Oedema of dorsum of hand **(frog hand).**
- Loss of concavity of palm.
- Painful movement of metacarpophalangeal joint (but interphalangeal joint movements are normal and painfree).
- Fever.


Palmar aponeurosis
Superficial palmar arch
Septum
Digital nerves
Thenar muscles
Flexor pollicis longus tendon
Hypothenar muscles
Flexor tendons of index finger
Flexor digitorum superficialis tendons
Thenar space
Flexor digitorum profundus tendons
Dorsal subcutaneous space
Dorsal subaponeurotic space
Midpalmar space
A
Thenar space
Flexor retina-culum
Space of Parona
Midpalmar space
B
First lumbrical canal
Lumbrical canals–2nd, 3rd, 4th
Thenar space
Midpalmar space
Flexor retinaculum
Incisions to drain pus from space of Parona
Space of Parona
C

Figs 1.297A to C: Anatomy of palmar spaces of the hand and forearm. Midpalmar space is on the medial aspect; thenar space is on the lateral aspect. *Space of Parona* is on the lower forearm.

- Palpable tender axillary lymph nodes.
- Eventually pus may come out of palmar aponeurosis forming collar stud abscess and later sinus formation.
  X-ray of the part is required.

Treatment

- Elevation of the affected limb.
- Antibiotics and analgesics.
- **Drainage:** It is *drained* under regional/general anaesthesia by placing horizontal/oblique incision parallel to the palmar crease. One should avoid crossing the crease line as much as possible. Palmar aponeurosis is carefully incised vertically to avoid injury of the neurovascular bundles. Alternatively one of the *interdigital web spaces* is incised horizontally*; lumbrical canal* (3rd or 4th) is opened to reach the deep palmar space. Pus is drained and sent for culture and sensitivity. Thorough saline irrigation is very essential. Drain is placed through the wound.

Complications

- Osteomyelitis of metacarpals
- Stiffness of hand
- Suppurative arthritis
- Extension of infection into other spaces

Thenar Space Infection

Thenar space (triangular shape) is located anterior to the lateral two metacarpals and fascia over transverse head of adductor pollicis; behind the short muscles of thumb, flexor tendons of index finger and 1st and 2nd lumbricals. Thenar muscles and flexor pollicis longus are lateral to it; fibrous vertical septum from palmar aponeurosis to 3rd metacarpal bone is medial to it. It is on the outer half of the hollow of the palm. Proximally it extends from flexor retinaculum; distally it extends to transverse palmar crease. It communicates to fascial sheath of 1st lumbrical. It is often associated with midpalmar space infection.

When a hand is seriously inflamed it takes up the position of greatest ease, which is, in fact, the position of rest.
— Frederic Wood Jone

It is *drained* similarly by placing incision on the lateral aspect of the palm or through the first web space incision is done along the *first lumbrical canal* on the radial side of the index finger. Often incision is made parallel to cleft between index and thumb on the posterior aspect.



- Skin incision parallel to crease line
- Never cross the crease line
- Palmar aponeurosis is opened vertically
- Space can be approached through lumbrical canal through horizontal web space incision

Fig. 1.298: Incisions to drain midpalmar space infection.


Incision through first web space – radial side of index finger – through first lumbrical
Incision

Fig. 1.299: Incision and drainage of thenar space abscess.

SPACE OF PARONA INFECTION

Forearm space of Parona is a rectangular space situated in the lower part of the forearm above the wrist, in front of pronator quadrates and deep to long flexor tendons. Above it extends up to oblique origin of flexor digitorum superficialis, below up to flexor retinaculum communicating with midpalmar space. Flexor tendon sheath proximally extends into this space. Pus in this space is drained through lateral incisions in the lower part of the forearm.

ACUTE SUPPURATIVE TENOSYNOVITIS

It is the bacterial infection of flexor tendon sheaths.

Surgical Anatomy

- **Radial bursa** is synovial sheath of flexor tendon of thumb which extends to the digit.
- **Ulnar bursa** is synovial sheaths of medial four flexor tendons of hand which extends into the digit of the fifth (little) finger.



Fig. 1.300: Bursae hand.

- Extensor tendons are devoid of sheaths.
- Radial and ulnar bursa communicate with each other in 80% of cases.

Common bacteria: Staphylococcus aureus, Streptococcus pyogenes.

Clinical Features

- Symmetrical swelling of entire finger.
- Flexion of finger—**Hook sign**.
- Severe pain on extension.
- Tenderness over the sheath.
- Oedema of whole hand, both palm and dorsum (due to lymphatic spread).
- As ulnar bursa extends into the little finger its infection results in pain and tenderness extending up to little finger but not much to other fingers.

Kanavel signs

- Swollen finger held in flexion
- Exquisite pain on passive extension
- Tenderness precisely over the tendon sheath
- *Area of greatest tenderness over the part of ulnar bursa lying between transverse palmar creases*

- In infection of radial bursa thumb is swollen with pain and tenderness over the sheath of the flexor pollicis longus and there is inextensibility of interphalangeal joint.
- Swelling just above the flexor retinaculum is common.

Treatment

- Elevation of the affected limb.
- Antibiotics and analgesics.
- Position of rest.
- **Drainage** under general anaesthesia. Incisions are placed over the site of maximum tenderness and flexor sheath should be opened up. Many a times multiple incisions are required.

It is *drained through two incisions*—one over the proximal part of the sheath; other over the distal part of the sheath in the digit—along the crease lines. A fine catheter is passed into the sheath from proximal incision and irrigated with normal saline through this catheter. This catheter is left *in situ* for further regular irrigations, splinting of hand is necessary with boxing glove dressing.

Complications

- Spread of infection proximally into forearm—to *space of Parona*
- Stiffness of fingers and hand
- Suppurative arthritis
- Osteomyelitis
- Median nerve palsy
- Bacteraemia and septicaemia

COMPOUND PALMAR GANGLION

- It is chronic tenosynovitis of flexor tendon sheaths due to tuberculosis (tuberculous tenosynovitis) or rheumatoid arthritis.
- It can be unilateral or bilateral.

Pathology

- Flexor tendon sheath on either side of the wrist is involved, i.e. both in the volar surface of palm and lower forearm.
- Swelling contains fluid with typical ***melon seed bodies***.
- Condition is often bilateral in case of rheumatoid arthritis.

Clinical Features

- Swelling in the palm and lower forearm which is smooth, soft, nontender, fluctuant and also *cross-fluctuant* across flexor retinaculum, nontransilluminating.
- Wasting of hand and forearm muscles are seen.
- Matted axillary lymph nodes may be palpable.
- Primary focus may be present in lungs.

Investigations

- ESR, chest X-ray.
- FNAC of axillary lymph node and swelling itself.


Incisions for digital synovial sheath drainage
Incision for radial bursa
Incision for ulnar bursa
A
Digital incision
Irrigation polythene catheter
Syringe with saline for wash
Exposed tendon
Synovial sheath (infected)
Incision in the palm
Synovial sheath exposed in the digit
Syringe with saline for wash
B

Figs 1.301A and B: Suppurative tenosynovitis is drained through incision at proximal part and another at digital sheath. Often by placing fine polythene catheter into the sheath, saline wash is given into the area.

Disease is the fate of poor, but also punishment of rich.— **Ivo Andrick**

Treatment

- Start antituberculous drugs: INH, rifampicin, ethambutol and pyrazinamide for 9 months.
- Excision of flexor tendon sheath is done along with scraping of caseating material, tubercles, melon seed bodies.
- Care should be taken not to injure median and ulnar nerves.

ORF

It is contagious pustular dermatitis of the hand due to a parapox virus infection.

MILKER'S NODES

It is similar viral infection of the hand seen in cow handlers.

HAND INJURIES

Classification

- ***Tidy injuries***: They are clean incised wounds and are usually treated by primary suturing but depends on the tissues involved like nerves, tendons and muscles.
- ***Untidy injuries***: They are lacerated wounds. Treated by debridement and later by delayed primary or secondary suturing.
- ***Compartment injuries.***
- ***Degloving injuries***
- ***Indetermined injuries*** which could not be assessed.

Assessment of Injury

It should include: Number, extent, depth, deformity and disability, neurovascular injuries, tendon injuries, muscle injuries bone and joint injuries.

Principles of Treatment

- Haemostasis.
- Use of tourniquet.
- Wound debridement and cleaning.
- Antibiotics and antitetanus treatment (toxoid and antitetanus globulin).
- Primary suturing if it is a incised wound or delayed primary suturing if there is odema.
- Skin grafting or flaps for skin loss.
- Tendon suturing or tendon graft for tendon injuries.
- Rest and elevation of the affected parts.
- Management of fractures by splint, wiring.
- Nerve repair for nerve injuries.
- Immobilisation up to 21 days.
- Later physiotherapy with warm, exercise, was bath active movements.
- Microsurgical restoration of digits. Reimplantation of the digits.



Figs 1.302A and B: Indeterminate and untidy hand injuries.

In hand	
Do's	***Don'ts***
Do examine hand carefully	Do not incise every infected digit
Do think of other diagnosis	Do not make puncture incisions or over pads
Do wait for abscess to localise	Do not injure the digital nerves or vessels
Do place adequate length and depth of incisions	Do not place incisions crossing the crease line
Do immobilise, elevate the hand	Do not close human bites or lacerated wounds
Do give antibiotics and proper dressings	Do not forget to send pus for culture and sensitivity



Fig. 1.303: Hand injury exposing tendons. Note the marker stitch in the tendon. It needs local transposition flap or groin flap to cover. Skin grafting is not possible over tendons.

- Amputation of digits or metacarpals only when inevitable.

Primary repair of tendons and nerves are of lesser priority in untidy injuries. Priority is wound debridement/ wound excision and early skin cover. Cut ends of nerves and tendons are tagged with coloured stitches for future identification purpose.

Complications and morbidity of hand injuries

- Infection
- Osteomyelitis
- Arthritis of joints
- Stiffness
- Loss of function due to disability



Fig. 1.304: Stuck finger by a ring. It is removed by applying soap, fat, and wax. String method is winding and unwinding a thread under and across the stuck finger. Sawing is done only when every method fails.



Fig. 1.306: Hand injury which is healing but with severe deformity of fingers.



Fig. 1.305: Avulsion injury of thumb causing raw area. This needs proper skin cover to get the function adequately.



Fig. 1.307: Typical deformity of finger which needs correction for proper function.

"Impossible" is a word found only in the dictionary of fools.—Napoleon

DUPUYTREN'S CONTRACTURE

> *Individuals pre-disposed to the affection we are describing, observe that it is more difficult to extend the fingers of the affected hand… The first (interphalangeal joint) is flexed at nearly a right angle…the most powerful efforts are insufficient to extend it…. Hence, it was natural to conclude, that the commencement of the disease was in the unusual tension of the palmar aponeurosis.*
>
> —**Guillaume Dupuytren,** 1833

It refers to localised thickening of palmar aponeurosis and later formation of nodules with severe permanent changes in metacarpophalangeal and proximal interphalangeal joints. Terminal interphalangeal joint is *not involved* as palmar aponeurosis does not extend to terminal phalanx. It is common in *males* (10:1).

- It starts in ring and little fingers, with flexion of ring and little fingers. Later involving all fingers.
- There is thickening and nodule formation in the palm with adherent skin.
- It is often familial and bilateral 45%.
- Pads (of fat) develop in knuckles and are called as ***Garrod's pads*** (in proximal IP joints).



Figs 1.308A and B: Dupuytren's contracture in the hands. Note the involvement of the ring finger. Note the fibrous band on the other hand as early finding.

Conditions often associated with:

- Plantar fasciitis 5%—Ledderhose's disease
- Mediastinal and retroperitoneal fibrosis
- Peyronie's disease of penis 3%
- Nodules in the face and ear
- Pellegrini-Stieda's disease

Aetiology

- Repeated minor trauma, use of vibrating tools.
- Cirrhosis, alcoholism, smoking,
- Epileptics on treatment with phenytoin sodium.
- Diabetics, pulmonary tuberculosis, AIDS.
- Other metabolic conditions.
- Familial—autosomal dominant.

Galezia triad

- Dupuytren's contracture
- Retroperitoneal fibrosis
- Peyronie's disease of penis

Complications

- Restriction of hand function and so disability.
- Arthritis of MCP and proximal IP joints.

Treatment



Fig. 1.309: Z plasty done for Dupuytren's contracture.

- Fasciotomy of palmar aponeurosis and later physiotherapy, Z plasty.
- In severe cases fasciectomy partial or complete.
- Treatment of the cause.

Recurrence can occur in 5-50% cases.

VOLKMANN'S ISCHAEMIC CONTRACTURE

It is a vascular injury leading to muscular infarction and subsequent contracture.

Causes

- Supracondylar fracture of the humerus.
- IV chemotherapy.
- Burns.
- Closed forearm crush injuries.
- Tight plaster after reduction of fracture.

Pathogenesis

Injury of brachial artery (tear, contusion, spasm, compression)

↙ ↘

Results in infarction of forearm flexor muscle — Injury to median nerve (mainly) and ulnar nerve both by ischaemia and infarction

↓

Aseptic muscle necrosis

↓

Fibrosis of flexor muscle of forearm

↓

Contracture

Clinical Features

Acute phase:
- Pain (persistent pain in forearm, hand, fingers—ominous symptom).
- Pallor.
- Puffiness (due to oedema).
- Pulseless (absence of radial pulse; but its presence does not rule out the onset of impending contracture).
- Paresis.

Late phase: Deformity

Deformity (due to injury to median nerve):

- Wrist joint extended.
- Extended metacarpophalangeal joints.
- Flexed interphalangeal joints.

Volkmann's sign:

In early stage, the fingers can be extended at the interphalangeal joints, only when the wrist is flexed fully. The fingers tend to flex if any attempt to extend the wrist is made.

Treatment

***In acute phase*:**
- Removal of plastic cast applied after fracture reduction.
- Correction of fracture.
- Exposure of brachial artery and application of 2.5% papaverine sulphate to relieve the spasm if any.
- Suture of arterial tear if present, often with placement of arterial graft.
- Lateral incision over the deep fascia of forearm is placed to decompress the oedema.

***In late phase (once deformity occurs)*:**
- Physiotherapy
- Dynamic splints.
- ***Max-Page operation***: Release of flexor muscles (forearm muscles) from their origins from the bone and allowing it slide down until full extension.
- Excision of fibrous tissue and damaged muscles along with tendon transfer.
- Arthrodesis.

SYNDACTYLY

It is *webbing* or *fusion* of fingers.

Causes

- Congenital and hereditary—common.
- Traumatic like burns.

Types

- Cutaneous—simple.
- Fibrous.
- Bony—complex.
- It can be unilateral or bilateral.
- Often all four limbs may be involved with webbing of toes.
- It may be associated with polydactyly or visceral anomalies.
- If bony type is suspected, X-ray of the part should be taken.



Fig. 1.310: Syndactyly.



Fig. 1.311: Syndactyly and polydactyly of both hands and both feet.

You become successful by helping others to become successful.

Treatment

- If cutaneous, release of web is done as a staged procedure along with "Z" plasty or skin grafting.
- If fibrous, release can be done.
- If bony type, release is difficult because blood supply may be compromised which leads to gangrene of the digit.

MALLET FINGER (Base Ball Finger)

The terminal phalanx can not be extended because of tear at insertion of extensor tendon or avulsion fracture of the base of the terminal phalanx.

HEBERDEN'S NODES

These are seen in osteoarthritis, occurring behind the distal interphalangeal joints of ***index,*** middle, little and ring fingers.



Fig. 1.312: Arthritis of joints of hands.

SPINA VENTOSA

Refers to phalangeal tuberculosis (***Tuberculous dactylitis***). It is called as spina ventosa because of its appearance as "air filled balloon".



Fig. 1.313: Spina ventosa.



Fig. 1.314: Localised gigantism of index finger, thumb and part of the medial aspect of the hand.

FOOT

Foot contains 7 tarsal bones, 5 metatarsals, 14 phalanges (total 26 bones). Two sesamoid bones of 1st metatarsal bone are common. There are 4 layers of muscles in foot. Ligaments, muscles, joints, maintain the stability of foot complex. Blood supply is by anterior tibial, posterior tibial and peroneal arteries. Nerve supply is by saphenous, sural, posterior tibial, superficial and deep peroneal nerves.

CALLOSITY

- It is a hard, thickened skin occurs as a protective measure seen in wider area usually over heel and heads of metatarsals.



Fig. 1.315: Callosity in the foot.

- A callosity protrudes outwards from the skin.
- It is greyish-brown, raised, *protruded outwards*, thickened, hypertrophic skin occurs due to occupation and skeletal structure. It is *painless*. It is *wider* lesion. Paring the top layer exposes the shiny translucent dead skin beneath.
- It is grayish brown hypertrophic raised thick protective phenomenon which occurs commonly in areas of wear and tear like hands and feet. Top roughened layer when peeled off, shiny, translucent, homogenous dead skin can be exposed beneath.
- It is painless; it can get rubbed easily to create a sore.
- As it is a protective phenomenon it is best left alone.

CORN

Types

- Hard corn.
- Soft corn.

Hard Corn

- It is localised area of thickening over a bony projections like heads of metatarsals.
- Histologically it differs from callosity by having severe keratoses with a central core of degenerated cells and cholesterol.
- It presses over the adjacent nerves causing pain. It can get infected causing severe pain and tenderness with inability to walk.
- It is *smaller* lesion which is *pushed deep into* the skin forming a *localised* palpable *painful/tender* nodule with a *central yellow-white core* of dead cornified skin.
- Corn is common if there is deformity or by wearing tight fitting shoes/foot wears.
- Corn is narrow, deep and painful/tender.
- It is common in females.
- Corn is usually white/gray/yellow coloured, deep seated lesion.
- Infection, abscess formation and ulceration can occur especially if patient is diabetic.
- Corn may be associated with bursae causing bursitis.
- Corn often recurs after excision.

Treatment

- Excision.
- Local application of salicylic acid preparations or mixture of salicylic acid/lactic acid/collodion may be helpful. Skin softening agents are also tried.
- Eliminating the pressure is very important to prevent recurrence.
- Avoid excision of corn unnecessarily in diabetic (especially with neuropathy) and in ischaemic foot.

Soft Corn

It usually occurs between 4th and 5th toes due to friction of bases of adjacent proximal phalanges (See Fig. 1.318).



Fig. 1.317: Diagram showing differences between corn and callosity.



Fig. 1.318: Corns in the plantar aspect of the foot.



Fig. 1.316: Corn under great toe.



Fig. 1.319: Subcuticular abscess over great toe.

A positive attitude is like a magnet for positive results.

PLANTAR FASCIITIS (Policeman's Heel)

It occurs due to friction or tear of the ossified posterior insertion of the plantar fascia which is common in people who stand or walk for long-time.

Treatment

Analgesics, rest, steroid injections to the site.

INGROWING TOE NAIL (Onychocryptosis)

- It is also called as embedded toe nail.
- It is due to curling of the side of nail inwards, causing it to form a lateral spike resulting in repeated irritation and infection of overhanging tissues in the nail fold.

Causes

- Tight shoes.
- Improper cutting of nails (very short and convex).

Clinical Features

- It is common in ***great toe*** and is often ***bilateral***.
- Both medial and lateral sides of the toe can be involved.
- Recurrent attacks of acute and subacute paronychia occurs.
- Pain, tenderness, swelling of margins of the toe, often along with granulation tissue and foul smelling discharge.

Treatment

- Regular dressing and packing.
- Antibiotics. Discharge is sent for culture and sensitivity.
- Nails should be cut concavely or straight without leaving lateral spikes towards soft tissues.
- ***Zadik's*** or ***Fowler's operation***: Skin in lateral margin and root is incised so as to expose the lateral spike and germinal matrix. ***Infected tissues with pus and germinal matrix of ingrown part of the nail is excised or often entire nail with its root and germinal matrix is excised.***


Eponychium
Root of nail
Germinal matrix
Lunula
Hyponychium (Subungual space)
Anatomy of the nail
Zadik's procedure
Hypertrophied infected tissue
Incision for ingrowing toe nail

Fig. 1.320: Zadik's or Fowler's operation.



Figs 1.321A and B: Ingrowing toe nail. Note the granuloma caused by repeated infection and inflammation.


Incision
Nail
Germinal matrix

Fig. 1.322: Incision for nail excision. Note the germinal matrix. Removal of nail, entire or partial with adjacent germinal matrix is called as radical nail excision.

ONYCHOGRYPHOSIS

- It is curving of nail upwards (***Ram's Horn Nail***).
- It occurs due to repeated trauma or fungal infection.

ONYCHOMYCOSIS

It is fungal infection of the nail.

ATHLETE'S FOOT

- It is the fungal infection of the skin between the toes—*Tinea pedis.*

- Fungi enter through cracks; survive due to moisture in between toes.
- Skin is swollen, red, with sticky fluid, macerated with blisters.
- Itching, deep cracks, pain and discharge are common.

Treatment

- Part should be kept dry. Cotton, clean socks should be worn.
- Oral antifungals, antihistaminics and topical antifungals are used.
- Condition is contagious.

HALLUX VALGUS

- Here great toe is deviated laterally at first metatarsophalangeal joint. There is outward deviation of great toe with medial deviation of first metatarsal head.
- It may be due to persistent lateral force or occasionally hereditary.
- Condition is often *bilateral.*
- It is common in *females.*
- Thick walled bursa *(bunion)* over medial aspect of the head of the first metatarsal bone is common.
- Undue prominence of head of first metatarsal bone is typical often forming an *exostosis* at this point. *Osteoarthritis* of 1st metatarsophalangeal joint can occur.
- Lateral deviation of proximal phalanx over 2nd toe causing *crowding* of the toes.
- Initially it is painless; but eventually pain and tenderness develops with infection of bunion and *splaying* of forefoot.
- X ray shoes deviation with often osteoarthritis of the metatarsophalangeal joint.



Figs 1.323A and B: Hallux valgus deformity.

Treatment

Keller's operation: Proximal 1/3rd of the proximal phalanx of great toe and medial part of head of 1st metatarsal bone is excised through medial curved incision. Soft tissue interposition is done.

Mayo's procedure: Medial part of base of the proximal phalanx of great toe and head of 1st metatarsal bone is excised – opposite of Keller's.

Simmond's procedure: Varus osteotomy at the base of 1st metatarsal bone with reinsertion of adductor hallucis tendon is done.

McBride procedure: Transfer of adductor hallucis tendon and lateral head of flexor hallucis brevis from proximal phalanx of great toe to the lateral part of head of 1st metatarsal bone.

Arthrodesis of metatarsophalangeal joint is done to relieve pain.

Excision of bunion, deformity correction, osteotomy, muscle transfers are also done as a **combined approach.**



Fig. 1.324: Hallux varus deformity. It is opposite of hallux valgus deformigy.

Today well lived makes every yesterday, a dream of happiness and tomorrow, a vision of hope.

L. Arterial Diseases

CHAPTER OUTLINE

- Surgical Anatomy of Thoracic Outlet
- Arteries of Upper Limb
- Arteries of Lower Limb
- Arterial Diseases
- Intermittent Claudication
- Rest Pain
- Limb Ischaemia
- Pregangrene
- Gangrene
- Different Levels of Arterial Obstruction
- Other Features of Poor Circulation
- Investigations for Arterial Diseases
- Diseases of the Arteries
- Atherosclerosis
- Thromboangiitis Obliterans
- Takayasu's Pulseless Arteritis
- Raynaud's Phenomenon
- Temporal Arteritis
- Treatment of Arterial Diseases
- Subclavian Steal Syndrome
- Acute Arterial Occlusion
- Traumatic Acute Arterial Occlusion
- Embolism
- Reperfusion Injury
- Saddle Embolus
- Embolectomy
- Fat Embolism
- Air Embolism
- Therapeutic Embolisation
- Caisson's Disease or Decompression Disease
- Aneurysm
- Mycotic Aneurysm
- Abdominal Aneurysm
- Abdominal Aortic Aneurysm
- Peripheral Aneurysm
- Carotid Artery Aneurysm
- Dissecting Aneurysm
- Erythromelalgia/Erythralgia
- Livedo Reticularis
- Polyarteritis Nodosa
- Scleroderma/Systemic Sclerosis
- Acrocyanosis
- Gangrene
- Diabetic Foot and Diabetic Gangrene
- Trophic Ulcer
- Bedsores
- Frostbite
- Ainhum
- Endovascular Surgeries
- Upper Limb Ischaemia
- Arterial Substitutes

SURGICAL ANATOMY OF THORACIC OUTLET

Thoracic outlet is bounded by manubrium sternum in front, spine posteriorly, and the first rib laterally. At the superior aperture of thorax subclavian vessels, brachial plexus traverse the cervicoaxillary canal to reach the upper limb.

Cervicoaxillary canal is divided into proximal *Costoclavicular space* and *distal axilla (*divided by first rib).

Costoclavicular space is bounded superiorly by clavicle, inferiorly by first rib, anteromedially by the costoclavicular ligament, and posterolaterally by scalenus medius muscle along with long thoracic nerve.

Scalenus anticus muscle divides the costoclavicular space into two compartments, the anterior one containing subclavian vein and the posterior one containing subclavian artery and brachial plexus.

This posterior compartment is called as *Scalene triangle* bounded by scalenus anticus anteriorly, scalenus medius posteriorly, and the first rib inferiorly.

Cervical rib narrows this triangle and causes compressive features of the C_8, T_1 nerve roots and subclavian artery. Anything that narrows costoclavicular space causes *Thoracic outlet syndrome*.

Causes of thoracic outlet syndrome

- Cervical rib
- Long C_7 transverse process
- Anomalous insertion of scalene muscles
- Scalene muscle hypertrophy
- Scalene minimus
- Abnormal bands and ligaments
- Fracture clavicle or first rib
- Exostosis
- Tumours in the region

Differential diagnosis for thoracic outlet syndrome

- Carpal tunnel syndrome
- Cervical spondylosis
- Spinal canal tumours
- Shoulder myositis
- Angina
- Raynaud's disease
- Spinal stenosis
- Ulnar nerve compression

ARTERIES OF UPPER LIMB

Right subclavian artery begins from brachiocephalic trunk (innominate artery) whereas left subclavian artery arises directly from the arch of aorta. From underneath the sternoclavicular joint artery arches over the pleura and apex of lung about 2.5 cm above the clavicle and then reaches the lateral border of first rib to continue as axillary artery.

Subclavian artery is divided into three parts by scalenus anterior muscle.

Axillary artery is divided into three parts by pectoralis minor muscle.

At the lower border of teres major muscle it enters the arm and continues as brachial artery.

About 2.5 cm below the crease of the elbow joint, it bifurcates into radial and ulnar arteries which run in the forearm.

Ulnar artery forms the superficial palmar arch which is completed by superficial palmar branch of radial artery.

Radial artery after passing through the anatomical snuff box enters the dorsum of hand and first intermetacarpal space to form deep palmar arch. It is completed by deep palmar branch of ulnar artery and is 1 cm proximal to superficial palmar arch.

ARTERIES OF LOWER LIMB

Abdominal aorta bifurcates at the level of fourth lumbar vertebra (corresponds to the level of the umbilicus in anterior abdominal wall) into two common iliac arteries.

Common iliac artery is about 5 cm in length passes downward and laterally; and at the level of lumbosacral intervertebral disc, anterior to sacroiliac joint, it divides into external and internal iliac arteries. Internal iliac artery supplies pelvic organs.

External iliac artery continues as common femoral artery at the level of inguinal ligament.

About 5 cm below the inguinal ligament common femoral divides into superficial femoral and deep femoral (Profunda femoris) arteries.

Deep femoral provides collateral circulation around the knee joint and also communicates above with gluteal vessels to maintain collateral circulation around the gluteal region.

Superficial femoral artery at the hiatus in the adductor magnus, continues as popliteal artery up to the inferior angle of the popliteal fossa where it divides into anterior and posterior tibial arteries.

Anterior tibial artery supplies anterior compartment of leg and ankle, continues as dorsalis pedis artery which forms dorsal arterial arch of the foot.

Posterior tibial artery supplies posterior compartment of leg and ends as medial and lateral plantar arteries which forms plantar arterial arch of the foot.

Posterior tibial artery gives peroneal artery which runs close to fibula supplying calf muscles.



Figs 1.325A and B: CT angiogram of aortoiliac segment showing aortoiliac block due to atherosclerosis. Collaterals are also well-developed.

ARTERIAL DISEASES

- **Stenosis** due to trauma, atherosclerosis, emboli. It may be:
  - In the brain causing transient ischaemic attacks.
  - In the limbs causing claudication and rest pain.
  - In the abdomen causing pain, bloody stool.
  - In the kidney causing haematuria.
- **Dilatations are aneurysms.**
- **Arteritis**.
- **Small vessel abnormalities.**

INTERMITTENT CLAUDICATION

Claudio means *"I limp"* a Latin word. It is a crampy pain in the muscle seen in the limbs. Due to arterial occlusion, metabolites like lactic acid and substance P accumulate in the muscle and cause pain.

The site of pain depends on site of arterial occlusion.

- The most common site is calf muscles.
- Pain in foot is due to block in lower tibial and plantar vessels.
- Pain in the calf is due to block in femoropopliteal segment.
- Pain in the thigh is due to block in the superficial femoral artery.
- Pain in the buttock is due to block in the common iliac or aortoiliac segment, often associated with impotence and is called as **Leriche's syndrome.**

Pain commonly develops when the muscles are exercising. Cause for pain is accumulation of substance P and metabolites. During exercise increased perfusion and increased opening of collaterals wash the metabolites.

Boyd's classification of claudication

- Grade I: Patient complains of pain after walking, and distance in which pain develops is called as 'claudication distance'. If patient continues to walk, due to increased blood flow in muscle and opening of collaterals metabolites causing pain are washed away and pain subsides
- Grade II: Pain still persists on continuing walk; but can walk with effort
- Grade III: Patient has to take rest to relieve the pain

Claudication

- *Arterial*—typically develops after walking for certain distance and resolves rapidly within 5 minutes once walking is stopped
- *Neurogenic*—pain develops in standing or walking and disappears immediately after stopping walk; normal feeling pulses without ischaemic changes are present. It is usually due to narrow lumbar canal (spinal canal stenosis)
- *Venous*—it is rare but definitely occurs. It is observed in chronic pelvic venous obstruction as a mechanical high venous pressure. It is usually due to iliac vein thrombosis. Peripheral pulses are normal

Note:

- Beta blockers may aggravate claudication.
- Claudication is not that common in upper limb but can occur during writing or any upper limb exercise.

REST PAIN

- It is continuous aching in calf or feet and toes or in the region even at rest depending on site of obstruction.



Fig. 1.326: Rest pain in a patient suffering from TAO. Holding the foot reduces the pain slightly.

- It is '*cry of dying nerves*' due to ischaemia of the somatic nerves. It signifies severe decompensated ischaemia. Pain gets aggravated by elevation and is relieved in dependent position of the limb.
- Pain is more in the distal part like toes and feet. It gets aggravated with movements and pressure.
- Hyperaesthesia is common association with rest pain.
- Rest pain is increased in lying down and elevation of foot; it may be reduced on hanging the foot down.
- Rest pain is worst at night and so patient is sleepless at night.
- Rest pain is apparently reduced by holding the foot with hand, probably due to suppression of transmission of pain sensation.

Features of arterial stenosis/block in limbs

- Intermittent claudication
- Rest pain
- Cold periphery, numbness, paraesthesia
- Color changes, ulceration, gangrene
- Altered sensation and decreased function/movements
- Diminished/absent arterial pulsation
- Thrill/bruit over the stenosed artery
- Altered venous filling—normally it is in few seconds; it is delayed in arterial stenosis; it is rapid AV fistula

LIMB ISCHAEMIA

Causes

- Atherosclerosis.
- Embolism (acute).
- Arteriopathies—Buerger's disease, Raynaud's disease, Takayasu's disease.
- Diabetes.
- Scleroderma.
- Physical agents—trauma, tourniquet, radiation injury.

Classification of Limb Ischaemia

Fontaine classification of limb ischaemia

- Stage 1: No clinical symptoms
- Stage 2: Intermittent claudication
  - 2a: Well compensated—can walk > 200 metres
  - 2b: Poorly compensated—walk only < 200 metres
- Stage 3: Rest pain
- Stage 4: Gangrene, ischaemic ulcer

Rutherford classification

Grade	*Clinical feature*
0	Asymptomatic
1	Mild claudication
2	Moderate claudication
3	Severe claudication
4	Ischaemic rest pain
5	Minor tissue loss
6	Major tissue loss

Limb ischaemia is also classified as

- *Functional* ischaemia.
- *Critical* ischaemia.

Functional Limb Ischaemia

Here flow of blood is normal when limbs are at rest; but will not be increased during exercise. It presents as claudication. It is defined as *"Muscle discomfort in the limb reproducibly produced by exercise and relieved by rest within 10 minutes."*

Critical Limb Ischaemia

It is persistently recurring ischaemic rest pain for 2 weeks, which requires regular analgesics for > 2 weeks or ulceration or gangrene of the foot or toes with an ankle systolic pressure < 50 mmHg or toe systolic pressure < 30 mmHg. Ankle brachial pressure index (ABPI) *will be less than 0.3*.

One should check blood pressure in all 4 limbs. ABPI is checked in supine position; systolic blood pressure in upper and lower extremities (two upper and two lower) is checked and higher value of each extremities is taken; ABPI is calculated.

Results—>**0.90 is normal; 0.70-0.89 is mild disease; 0.50-0.69 is moderate; <0.50 is severe.**

Note:
Calcification can alter the ABPI.

PREGANGRENE

It is the changes in tissue which indicates that blood supply is inadequate to keep the tissues alive and presents with rest pain, colour changes, oedema, *hyperaesthesia* with or without ischaemic ulceration.

GANGRENE

It is macroscopic death of tissue *in situ* with or without putrefaction.
(For detail see page no. 211, 212 and 213).



Fig. 1.327: Gangrene of great and little toes in a patient with vascular compromise.

Dry Gangrene

It is dry, desiccated, mummified tissue caused by gradual slowing of bloodstream. There *is a line of demarcation* and is localised.

Wet Gangrene

It is due to both arterial and venous block along with superadded infection and putrefaction. It spreads proximally and there is *no line of demarcation*. It spreads faster.

Organs in which gangrene can develop—appendix, bowel, gallbladder, testis, pancreas.

Necrosis*:* It is microscopic cell death.

Sequestrum is dead bone *in situ.*

Slough is dead soft tissue.



Fig. 1.328: Gangrene of little toe with line of demarcation.



Fig. 1.329: Ischaemic ulcer foot in a diabetic patient.

Severely diseased distal aorta in atherosclerosis on arteriography is called as "shaggy aorta".



Fig. 1.330: Ischaemic right leg. Note the wasting and hair loss.



Figs 1.331A and B: Gangrene of all toes at their distal phalanges. All ischaemic features are obvious.



Fig. 1.332: Ischaemic changes in the right leg. Third and fourth toes are gangrenous with line of demarcation. Great and little toes are partly gangrenous. There are ischaemic features in the right foot and leg like hair loss/skin changes/wasting.

Line of Demarcation

- It is a line between viable and dying tissue indicated by a band of hyperaemia. It also indicates that disease is getting localised.
- *Final separation* between healthy and gangrenous tissue occurs by development of a layer of granulation tissue in between.
- It is hyperaesthetic due to *exposed nerve endings.*

Types of Separation

- Separation by *aseptic* ulceration is seen in dry gangrene.
- Separation by *septic* ulceration is seen in infected condition and *wet* gangrene.

Features of ischaemia

- Marked pallor, purple blue cyanosed appearance
- Thinning of skin
- Diminished hair
- Loss of subcutaneous fat
- Brittle nails, with transverse ridges
- Ulceration in digits
- Wasting of muscles
- Tenderness and temperature (cold)

DIFFERENT LEVELS OF ARTERIAL OBSTRUCTION

- *Aortoiliac block* causes claudication in both buttocks, thighs, and calves; absence of femoral and distal pulses bruit over aortoiliac region. *Impotence* occurs due to defective perfusion through internal iliac arteries and so into the penis causing erectile dysfunction (*Leriche's syndrome*)**.**
- *Iliac artery obstruction* causes claudication in thigh and calf; bruit over iliacs with absence of femoral and distal pulses.
- *Femoropopliteal obstruction* causes claudication in calf with absence of distal pulses but with palpable femoral.
- *Distal obstruction* shows absence of ankle pulses with palpable femoral and popliteal pulses.
  - *Paraesthesia* over the skin of the foot is due to shunting of blood from the skin to muscles in deeper plane.
  - *Sensation* in gangrenous area is absent. But, at the line of demarcation, skin is *hyperaesthetic*.

OTHER FEATURES OF POOR CIRCULATION

- The affected part is *cold* with *numbness*, *paraesthesia* and *colour changes*. Observing for *colour change* is important as, if it is not present one may have to think that numbness could be of neurological origin. On elevation the part blanches, on dependency part becomes purple. *Temperature sensation* on the ischaemic limb is lost apart from its coldness.
- *Ulceration, gangrene, decreased sensation and movements* are the features to be checked.
- **Delayed capillary filling**: Blanched nails or pulp of fingers, on pressure, will show delay in refilling (to turn pink) after release of pressure.
- **Delayed venous refilling**: Two fingers are placed over the vein. Finger nearest to heart is moved away so as to empty the vein. Distal finger is released to observe the venous refilling. Delay in filling is called *Harvey's sign*, signifies ischaemia. Venous filling is increased in AV fistulas.
- **Crossed leg test (*Fuchsig's test*):** Patient is asked to sit with the legs crossed one over the other so that the popliteal fossa of one leg will lie against the knee of other leg. Oscillatory movements of foot can be observed synchronous with the popliteal artery pulsation. This movement is absent with blockage of popliteal artery.
- **Disappearing pulse syndrome:** Exercise the limb after feeling the pulse. Pulse disappears once patient develops claudication. It is due to vasodilatation and increased vascular space occurring as the result of exercise wherein arterial tension can not be kept adequately and so pulse will disappear (*unmasking the arterial obstruction*).

- ***Buerger's postural test:*** Patient lying down on his back is asked to raise the leg above. In normal individuals, limb (plantar aspect of foot) remains pink even after raising above 90°. Ischaemic limb, when elevated shows marked pallor and empty veins. The angle in which pallor develops is called as *Buerger's angle of vascular insufficiency.* If this angle is < 30°, it indicates severe ischaemia.
- **Systolic bruit** may be heard over stenosed artery like subclavian artery, femoral artery, carotid artery, iliacs, renal artery.
- ***Adson's test (Scalene manoeuvre):*** In a patient sitting on a stool, the radial pulse is felt. The patient is then asked to take a deep breath (to allow the rib cage to move upwards so as to narrow the cervicoaxillary channel) and turn the face to same side (to contract scalenus anterior muscle so as to narrow the scalene triangle). If the radial pulse disappears or become feeble it signifies cervical rib or scalenus anticus syndrome.
- **Elevated arm stress test (EAST), or *modified Roos test*:** With both the arms kept in 90° abduction and external rotation position, patient is asked to make a fist and release repeatedly for 5 minutes. In normal side, patient will continue to do the manoeuvre whereas in diseased (Thoracic outlet syndrome) side patient gets pain and paraesthesia with difficulty in continuing the manoeuvre. Patient drops the arm down to relieve the symptoms.
- **Costoclavicular compression manoeuvre (*Falconer test*):** Radial pulse becomes absent when patient draws his shoulders backwards and downwards in excessive military position. This is because at this position, subclavian artery is compressed between first rib and clavicle, leading to feeble or absent radial pulse. *Halstead manoeuvre another similar text*.
- **Hyperabduction manoeuvre (*Wright test*):** When affected arm is hyperabducted, radial pulse becomes absent or feeble due to compression of artery by pectoralis minor tendon.
- ***Allen's test:*** It is done to find out the patency of radial and ulnar arteries. Both the arteries are compressed near the wrist and allowed to blanch completely in one minute (In the mean time patient closes and opens the fist several times for further venous outflow). Palm appears pale and white. One of the arteries is released and colour of hand is noted. Normally hand will become pink and flushed in no time; whereas in obstruction, the area will still remain pale. Other artery is also released and looked for changes in hand. Often test has to be repeated to get proper information.
- Abdomen should be examined for the presence of abdominal *aortic aneurysms*. It presents as pulsatile mass above the umbilicus, vertically placed, smooth, soft, nonmobile, not moving with respiration, resonant on percussion. Expansile pulsation is confirmed by placing the patient in knee-elbow position.
- Auscultation for *arterial bruit* over femoral artery, abdominal aorta, subclavian and carotid arteries is done.

Palpation of Blood Vessels

- *Dorsalis pedis artery* is felt just lateral to the extensor hallucis longus tendon at the proximal end of first web space, felt against the navicular and middle cuneiform bones. It is absent in 10% cases.
- *Posterior tibial artery* is felt against the calcaneum just behind the medial malleolus midway between it and tendon Achilles.
- *Anterior tibial artery* is felt anteriorly in the midway between the two malleoli against the lower end of tibia just above the ankle joint, lateral to extensor hallucis longus tendon.
- *Popliteal artery* is difficult to feel. It is palpated better in prone position with knee flexed about 40-50°, to relax the popliteal fascia. It is felt in the lower part of the fossa over the flat posterior surface of upper end of tibia. In upper end of the fossa, artery is not felt as there is no bony area in intercondylar region.
- *Femoral artery* in the groin is felt just below the inguinal ligament midway between anterosuperior iliac spine and pubic symphysis. Often hip has to be flexed for about 10-15° to feel it properly.
- *Radial artery* is felt at the wrist on the lateral aspect against lower end of the front of radius.
- *Ulnar artery* is felt at the wrist on the medial aspect against lower end of the front of ulna.
- *Brachial artery* is felt in front of the elbow just medial to biceps brachii tendon.
- *Axillary artery* is felt in apex of the axilla against shaft of the humerus.
- *Subclavian artery* is felt against first rib just above the middle of the clavicle.
- *Facial artery* is felt against body of mandible at the insertion of masseter.
- *Common carotid artery* is felt medial to sternomastoid muscle at the level of thyroid cartilage against carotid tubercle (*Chassaigne tubercle*) of transverse process of 6th cervical vertebra (in carotid triangle).
- *Superficial temporal artery* is felt just in front of the tragus of the ear against zygomatic bone.

INVESTIGATIONS FOR ARTERIAL DISEASES

- ***Segmental pressure measurements:*** Segmental BP is measured at multiple levels (upper and lower thigh, upper calf and ankle); pressure reductions between levels help to localise the occlusion; normally pressures increase as one moves further down the leg (>20 mmHg gradient abnormal); test is inaccurate in calcified artery walls.
- Blood tests: Hb%, blood sugar, lipid profile, peripheral smear, platelet count.
- ***Doppler*** to find out the site of block—hand held Doppler can be used (**Doppler**: *Christian Johann Doppler*, Austrian physicist).
    - *Duplex scan:* It is combination of B mode ultrasound and Doppler study. Difference in transmitted beam of the ultrasound and reflected beam is called as *Doppler shift* which is assessed and converted into audible signals. It is used to study the site, extent, severity of block, and also about collaterals. Audible sound is heard with normal flow, and sound is important. Turbulence is heard when there is stenosed partially blocked artery. Audible sound will be absent if there is complete block. Using Doppler probe blood pressure at various levels can be assessed. Pulse wave tracing along the artery is also important.

Half of us are blind, few of us feel and we are all deaf.—**William Osler**



Fig. 1.333: Hand held Doppler is simpler way to identify and assess the artery.

- Arterial diameter, blood flow rate, velocity of flowing blood, assessment of stenosed segment is properly done using Doppler.

- ***Treadmill test/ECG/echocradiography*** to assess cardiac/coronary status.
- ***Ultrasound abdomen*** to see aneurysm/aorta and its anatomical changes/other vessels in the abdomen/other organs.
- ***Plethysmography:*** It measures the blood flow in limbs. Water filled volume recorder; air filled volume recorder; mercury in silastic gauze is used after occluding the venous outflow. It is a noninvasive method. Segmental plethysmography using occlusion cuffs of 65 mmHg pressure is placed at thigh, calf and ankle levels and then quantitative measure of pulsation is done.
- ***Ankle-brachial pressure index***: Normally it is 1. If it is less than 0.9, it means ischaemia is present. If it reaches 0.3 or below then it signifies severe ischaemia with gangrene.
- ***Angiography:***
  - *Angiography* is *the appropriate* investigation for arterial diseases.



Fig. 1.334: Seldinger angiogram—retrograde femoral approach. (*Courtesy:* Dr Vasudeva Rao, Vascular Surgeon, Manipal Hospital, Bengaluru).

  - *Retrograde transfemoral Seldinger* (Sweden) *angiography*:
    - It is commonly done angiogram. It is done only when femorals are felt. If femoral pulsation is not felt then angiogram is done either *transbrachially (left brachial artery),* or *transaortic.*

Indications for angiogram

- TAO
- Atherosclerosis
- Raynaud's phenomenon
- AV fistulas
- Haemangiomas
- Thoracic outlet syndrome (e.g. cervical rib)
- Aneurysms
- Neoplastic conditions

    - Other angiograms are carotid angiogram, coeliac angiogram, superior mesenteric angiogram, coronary angiogram.

Seldinger technique (Steps)

- Arterial cannula is passed into the artery, e.g. femoral artery
- Needle is removed and guidewire is passed through the cannula
- Cannula is removed
- Dilator is passed over the guidewire
- Dilator is removed and arterial catheter (5 French sized) is passed over the guidewire
- Guidewire is removed

    - Femoral artery is used because it can be easily felt and cannulated to pass an arterial catheter.
    - Water soluble iodine dye (Sodium diatrizoate) is injected. X-rays are taken to see the block, its extent in the affected limb.
    - In TAO *cork screw* appearance is characteristic**.** *Distal run off* through collaterals is also important.
    - If catheter is passed still proximally angiogram of opposite side is possible.
    - Seldinger technique can also be used (to study) to do renal angiogram to detect renal artery stenosis, renal carcinomas, renal anomalies (vascular). But a *caution* should be remembered that angiogram in limb may precipitate further rapid thrombus formation, worsening ischaemia and precipitating gangrene.

Complications of retrograde angiogram

- Bleeding, hypotension
- Dissection of the vessel wall, pseudoaneurysm
- Haematoma formation
- Embolic blue toe syndrome
- Thrombosis, AV fistula
- Infection, osmolarity discomfort
- Anaphylaxis—4%

  - ***Direct aortic angiogram***, practiced earlier, is discouraged at present because of the risk of *aortic dissection* and paraplegia due to blockage/spasm of anterior spinal artery.
  - ***Digital subtraction angiography (DSA)***
    - Here vessel (artery) is delineated in a better way by eliminating other tissues through computer system. AV fistulas, haemangiomas, lesion in circle of Willis, vascular tumours, other vascular anomalies are well made out.



Fig. 1.335: DSA showing total block of right common iliac artery due to thrombosis.



Fig. 1.336: CT angiogram showing abdominal aorta, branches and renal vessels.

- Dye is injected either to an artery or vein. Injecting into a vein is technically easier but larger dose of dye is required. Injecting into an artery is technically difficult but small dose of dye is sufficient.
- *Advantages:* Only vascular system is visualised; other systems are eliminated by computer subtraction. Small lesion, its location and details are better observed with greater clarity.
- *Disadvantages:* Cost factor and availability**.**
- *Complications:* Anaphylaxis, bleeding, thrombosis.

♦ ***CT angiogram/MR angiogram.***

♦ ***Brown's vasomotor index:*** Specific nerve of the ischaemic limb is anaesthetised like posterior tibial nerve or ulnar nerve (local anaesthetia or spinal anaesthesia is given to anaesthetise entire limb). If the ischaemic disease is at vasospasm stage (like in TAO), nerve block will relieve the sympathetic vasospasm and skin temperature rises. It is compared to mouth temperature of the patient.



Figs 1.337A and B: Aortic and aortoiliac CT angiogram.

It is to assess the degree of vasospasm which is used as a predictor of the efficacy of sympathectomy.

(Rise in skin temperature—rise in mouth temperature) divided by rise in mouth temperature is called as *Brown's vasomotor index*. If it is more than 3.5, it is due to vasospasm, and can be relieved by sympathectomy. If less than 3.5, sympathectomy is not beneficial.

♦ ***Transcutaneous oximetry:*** By placing polarographic electrodes over the skin over thigh, leg and foot of oxygen tension (tcPO_2) can be measured which is reflection of underlying tissue perfusion. Normal tcPO_2 in the foot is

*The peroneal artery replaces the anterior tibial artery in 5% of cases.***—Solly M Cohen**

50-60 mmHg. Level less than 40 mmHg shows inadequate wound healing. Level below 10 mmHg suggests critical ischaemia with complete failure of wound healing.

- ***Other tests***
  - *Xenon 133 isotope method* is used to study muscle blood flow. Xenon 133 after mixing with normal saline is injected IM to study its clearance.
  - Two electromagnetic electrodes are placed in contact with arterial wall in opposite directions which pick up moving blood force to feed into electronic amplifier. But it is invasive as artery has to be dissected to place electrodes.

Treatment Plan for Arterial Diseases

- Stopping smoking; supervised exercises; regular controlled walk, diet (carbohydrate and lipid free diet); care of limbs.
- Control of hypertension, diabetes; antilipid drugs like atorvastatin 10 mg or pravastatin 40 mg; low dose aspirin 75 mg; clopidogrel 75 mg; vasodilators; ticlopidine; dipyridamole; cilostazole 100 mg are different drugs used.
- Percutaneous transluminal balloon angioplasty (PTA) done mainly to iliac arteries, subclavian arteries, renal artery, carotid and occasionally leg arteries and mesenteric or gastrointestinal arteries. PTA with stenting using expandable stents to the arteries is also often done to get a better result.
- Bypass graft surgeries—aortofemoral; femorofemoral; iliofemoral, etc. Dacron, human umbilical vein (3 mm), saphenous vein; PTFE (Polytetraflouoro ethylene)—are different grafts used.
- Endarterectomy, atherectomy, thrombectomy, profundaplasty, etc.

DISEASES OF THE ARTERIES

- Atherosclerosis.
- Thromboangiitis obliterans (TAO) (Buerger's disease).
- Raynaud's disease.
- Conditions causing Raynaud's phenomenon: Like scleroderma, rheumatoid arthritis, SLE, granulomatosis, vasculitis of other causes.
- Embolus.
- Aneurysms.
- Other causes: Fibromuscular dysplasia, radiation, Takayasu's arteritis.

ATHEROSCLEROSIS

It is a chronic, complex inflammatory condition of elastic and muscular arteries, involving as systemic and segmental. It begins in childhood as fatty streaks.

Risk factors
Definitive
• Hypercholesterolaemia, and hyperlipidaemia (cholesterol > 200 mg%; high LDL (>100 mg%); low HDL (< 35 mg%).
• Cigarette smoking
• Hypertension
• Diabetes mellitus
Relative
• Age—elderly
• Common in males
• Hypertriglyceridaemia
• Sedentary life, obesity
• Family history



Fig. 1.338: Angiogram showing atherosclerosis.

Pathogenesis

- All risk factors cause initial endothelial injury, both mechanical as well as toxic. This reduces significantly *normal atheroprotective features* of endothelium (*barrier function; antiadhesive effect; antiproliferative effect* on smooth muscles of arterial wall). Progressive atheromatous plaque formation, thrombosis, migration and proliferation of vascular smooth muscle cell occur. *Migrated smooth muscle cells* into intima act as neointima and this migration is stimulated by PDGF (*platelet derived growth factor* released by endothelial smooth muscles, platelets); which (this migrated smooth muscle) newly becomes secretory to produce large quantity of matrix of the plaque. Lipid (LDL) gets oxidised to release factors which promote inflammation and coagulation and factors which prevent production of *protective nitric oxide*. Macrophages stabilise the plaque.
- *Pathology* constitutes of atherosclerotic plaque which contains smooth muscle cells, connective tissue matrix, macrophages and lipid (the feature of atherosclerosis). Ulceration and calcification occurs in these plaques. *Ulcerated plaque* is highly thrombogenic causing thrombosis and further critical block of the vessel leading to tissue ischaemia and infarction distally.
- Plaques are more at the *dividing junctions* of the artery where stress and shear force of the blood flow is more. Plaques are dynamic in nature with progression and regression phases.
- Plaque progression has got a unique ability of *adaptation* so that as the plaque progresses, lumen caliber is been tried

to be preserved until critical stage occurs. Stenosis more *than 40%* is said to be *critical*. Beyond this, compensatory mechanism fails causing rapid progression and further stenosis of lumina. Stenosis more than 40% causes *atrophy of tunica media* making arterial wall mechanically unstable leading into dilatation and aneurysm.

- ***Common arteries involved are***—infrarenal part of abdominal aorta, coronary arteries, iliofemoral vessels, carotid bifurcation, popliteal arteries. It is less common in upper limb arteries, common carotid, renal and mesenteric arteries.

Features and Evaluation

- It is common after 50 years, but can occur at earlier age group.
- It occurs in males and females. Family history is common.
- Smoking, hypertension, diabetes, raised cholesterol are common causes.
- Veins are not diseased. Arterial wall is thickened on palpation.
- Thrill and bruit over femoral, renal, carotid arteries may be felt/heard. It suggests localised stenosis with turbulence of blood flow.
- Features of ischaemia in the affected limb seen. Absence/feeble pulses including of main arteries of the limb—femorals. Abdomen should be examined for aortic aneurysm.
- Transient ischaemic attacks, chest pain, eye problems, mesenteric ischaemia, altered renal function may be associated.
- Blood sugar, fasting lipid profile, Doppler, angiogram (CT / DSA), US abdomen, ECG, echocardiography are essential investigations. Angiogram shows typical narrowed artery, site, extent, percentage of stenosis, and collaterals.

Management

- *Risk factor modification*: Avoid smoking; control of hypertension, diabetes, hypercholesterolaemia; weight reduction by diet, and exercise.
- *Drugs*: Antiplatelet agents (aspirin 75 mg, clopidogrel 75 mg); cilostazol 50 mg bd; atorvastatin to reduce cholesterol; pentoxiphylline.
- *Percutaneous transluminal angioplasty (PTA)* is very useful for iliac blocks and lower limb blocks.
- *Surgeries:*
  - Thrombectomy, endarterectomy, profundaplasty.
  - Reverse/saphenous vein graft.
  - By pass grafts—iliofemoral, aortofemoral, iliopopliteal, femorofemoral grafts.
  - Amputations if limb is gangrenous—toe/below knee, above knee. Forefoot and Syme's amputations are not feasible in vascular conditions.

Note:

Lumbar sympathectomy and omentoplasty are not much useful in atherosclerotic limb. Omental vessels as such are often poorly perfused in atherosclerotic patients due to involvement of coeliac trunk.

Aortoiliac Occlusive Disease

Common site of symptomatic atherosclerotic occlusive arterial disease of lower limb is infrarenal abdominal aorta and iliac arteries. Aortic bifurcation is the most common site of occlusion. Often disease may also extend into infrainguinal level.

Types of Aortoiliac Occlusive Disease

Type I: Disease localised to distal abdominal aorta and common iliac arteries.
Type II: Wide spread aortic and iliac disease.
Type III: Multiple level diseases along with infrainguinal diseases.



Distal aorta and common iliac arteries

Widespread abdominal aorta and iliac arteries

Multiple level disease–abdominal, iliac, infrainguinal arteries

Fig. 1.339: Types of aortoiliac occlusive disease.

Features

- Common in 5th and 6th decades. Common in males.
- Claudication in buttock, Leriche syndrome with impotence, distal ischaemia are the features.
- Femoral artery pulsations below are absent. Systolic bruit over aorta and iliac arteries may be heard suggesting stenosis.
- Atheromatous plaque may dislodge and may cause embolus causing acute presentation.
- Aortic angiogram is diagnostic.

Management

- Treatment for diabetes, hyperlipidaemia, etc.
- Surgical treatment is the mainstay.
  - Direct *anatomical* reconstruction
    - *Aortoiliac endarterectomy* is reboring/disobliteration procedure useful for type I disease. Diseased intima, plaque with thrombus is removed by arteriotomy along the entire length which is closed later using 4 zero/5 zero polypropylene continuous sutures (open endarterectomy). In lengthy disease, after making two small arteriotomies at proximal and distal diseased parts, endarterectomy loop is passed to remove the intima with diseased plaque (*semi-closed endarterectomy*). *Advantages:* It avoids prosthetic graft and its complications. *Problem* is—reocclusion and restenosis.

Dacron is polyethylene terephthalate.

- *Aortofemoral bypass* graft is the gold-standard surgical procedure for type I and II disease. Long-term patency rate is 70-80%. Woven Dacron graft is used. *Complications are*—bleeding, thrombosis, embolisation, graft blockage, graft failure, graft infection, graft leak, aortovenacaval/aortoduodenal fistula, mesenteric ischaemia (colonic), impotence.

- Indirect *extra anatomical* bypass

  It is quicker and technically easier and is suitable to patients who cannot tolerate anatomical bypass. Axillo-bifemoral graft is used, only in such occasional situation.

- Nonoperative *catheter based* endovascular procedure

  If stenosis is less than 5 cm *percutaneous transluminal angioplasty* (PTA) with or without intravascular stents can be done. It is useful for single or multiple short focal stenoses. It is now proved that long-term patency of PTA is equal to surgical intervention.



Figs 1.340A and B: Aortofemoral bypass graft.

Infrainguinal Arterial Occlusive Disease

It is either part of type III aortoiliac disease (aortoiliac femoral) or femoropopliteal tibial disease. Superficial femoral artery is most commonly involved. Involvement of long segment of the artery is common. Occasionally a short stenotic segment may be present.

Management

- If the popliteal artery below knee is patent *femoropopliteal bypass* is the ideal procedure used. Otherwise one of the patent branches is used for bypass. *In situ saphenous vein graft* is ideal; reverse saphenous vein graft or synthetic femoropopliteal graft can also be used.
- *Profundaplasty* may be done to improve the collateral circulation through profunda femoris (deep femoral).

Note:

PTA in infrainguinal blocks is occasionally useful, only when stenosis is short and well-localised; otherwise it is *not a good* option. Angioplasty with laser drilling is often tried.

THROMBOANGIITIS OBLITERANS (TAO)
Syn. Buerger's Disease

> *The disease (occurs) in young adults between the ages of twenty and thirty-five or forty years.... Upon examination we see that one or both feet are markedly blanched, almost cadaveric in appearance, cold to the touch, and that neither the dorsalis pedis nor the posterior tibial artery pulsates.... After months... trophic disturbances make their appearance.... Even before the gangrene, at the ulcerative stage, amputation may become imperative because of the intensity of the pain.*
>
> —**Leo Buerger**
> 1908 (Professor of Urology, 1879 to 1943)

- It is a disease exclusively seen in males of young age group (Not usually seen in females due to genetic reason). Seen only in smokers and tobacco users.
- Almost always starts in lower limb, may start on one side and later on the other side. Upper limb involvement occurs only after lower limb is diseased. Only upper limb involvemnt can occur (not uncommon) but it is *rare.*
- It is nonatherosclerotic inflammatory disorder involving medium sized and distal vessels with cell mediated sensitivity to type I and type III collagen.
- It is common in Jewish people; it is rare even in female smokers.
- Hormonal influence, familial nature, hypersensitivity to cigarette, altered autonomic functions are probable different causes.
- Lower socioeconomic group, recurrent minor feet injuries, poor hygiene are other factors.
- It is segmental, progressive, occlusive, inflammatory disease of small and medium sized vessels with superficial thrombophlebitis often may present as Raynaud's phenomenon with microabscesses, along with neutrophil and giant cell infiltration, with skip lesions.



Fig. 1.341: Ischaemic features in upper and lower limbs (four limbs).

Pathogenesis

Smoke contains *carbon monoxide* and *nicotinic acid*

↓ ← Carboxyhaemoglobin

Causes initially vasospasm and hyperplasia of intima

↓

Thrombosis and so obliteration of vessels occur, commonly medium sized vessels are involved.

↓

Panarteritis is common

Usually involvement is *segmental*

↓

Eventually artery, vein and nerve are together involved

↓

Nerve involvement causes rest pain

↓

Patient presents with features of ischaemia in the limb

↓

Once blockage occurs, plenty of collaterals open up depending on the site of blockage either around knee joint or around buttock

Once collaterals open up, through these collaterals, blood supply is maintained to the ischaemic area

↓

It is called as *compensatory peripheral vascular disease*.

↓

If patient continues to smoke, disease progresses into the collaterals, blocking them eventually, leading to severe ischaemia and is called as *decompensatory peripheral vascular disease*. It is presently called as ***critical limb ischaemia.*** It causes rest pain, ulceration, gangrene.

***Note*:**
There is vasospasm → intimal hyperplasia → thrombosis → panarteritis → obliteration; tender, cord like veins with *superficial migratory thrombophlebitis* (30%); with nerve involvement due to vasa nervorum block/spasm. Arterial lumen is *blocked* but not thickened like atherosclerosis.

Smoking index (SI) =

$$\left[\text{Number of cigarettes smoked per day}\right] \times \left[\text{Number of years of smoking}\right]$$

SI > 300 is a risk factor

Pack Years Index (PYI) =

$$\left[\text{Number of years of smoking}\right] \times \left[\text{Number of } \textit{packets of cigarettes} \text{ per day}\right]$$

PYI > 40 is a risk factor

Shianoya's criteria for Buerger's disease

- Tobacco use. Only in males
- Disease starts before 45 years
- Distal extremity involved first without embolic or atherosclerotic features
- Absence of diabetes mellitus or hyperlipidaemia
- With or without thrombophlebitis

Classification of TAO

Type I: Upper limb TAO—rare.

Type II: Involving leg/s and feet—crural/infrapopliteal.

Type III: Femoropopliteal.

Type IV: Aortoiliofemoral.

Type V: Generalised.

Clinical Features

- Common in male smokers between the 20-40 years of age group. It is a *smoker's disease*.



Fig. 1.342: Gangrene of leg and foot.



Fig. 1.343: Ischaemic ulceration in the foot.

The art of seeing invisible things is called as 'clinical vision'.



Fig. 1.344: Gangrene of mid-toes—distal part.



Fig. 1.345: Dry gangrene of leg. Patient needed above knee amputation.



Fig. 1.346: Ischaemic ulcer foot. Note the poor blood supply and unhealthy granulation tissue.

- Intermittent claudication in foot and calf progressing to rest pain, ulceration, gangrene.
- Recurrent migratory superficial thrombophlebitis.
- Absence/feeble pulses distal to proximal; dorsalis pedis, *posterior tibial,* popliteal, femoral arteries.
- May present as Raynaud's phenomenon.



Fig. 1.347: Bilateral TAO in a young male with large ischaemic ulcers. Patient underwent amputation of both limbs (Below-knee).



Fig. 1.348: Great toe gangrene. Note the clear line of demarcation.



Fig. 1.349: Gangrene foot.

Investigations

- Hb%. Blood sugar.
- Arterial Doppler and Duplex scan (Doppler + B mode U/S).
- ***Transfemoral retrograde angiogram*** through Seldinger technique:
  - Shows blockage—sites, extent, and severity.
  - *Cork screw* appearance of the vessel due to dilatation of vasa vasorum.
  - Inverted tree/spider leg collaterals.
  - *Severe vasospasm causing corrugated/rippled artery.*
  - *Distal run off* is amount of dye filling in the main vessel distal to the obstruction through collaterals. If distal run off is good then ischaemia is compensated. If distal run off is poor then ischaemia is decompensated.



Fig. 1.350: Skip ischaemic ulcers are common in vascular diseases. It suggests severe ischaemia up to most proximal ulcer level.

- ***Transbrachial angiogram*:** If femorals are not felt, then transbrachial angiogram (through left side brachial artery—left subclavian artery—and so to descending aorta) should be done.
- Ultrasound abdomen to see abdominal aorta for block/aneurysm.
- Vein, artery, nerve biopsy.



Fig. 1.351: CT angiogram of lower limb (leg area) showing segmental block.



Fig. 1.352: Angiogram showing block in main vessel with opened up collaterals and adequate distal run off.



Fig. 1.353: Angiogram showing adequate collaterals.

Treatment

Stop smoking. "Opt for either cigarette or limb, but not both."

Drugs

- Vasodilators, e.g. nifedepine.
- Pentoxiphylline increases the flexibility of RBC's and helps them reach the microcirculation in a better way so as to increase the oxygenation. Its efficacy is more in *venous ulcer* than arterial diseases (now).
- Low dose of aspirin 75 mg once a day—antithrombin activity.

Learn to see, learn to hear, learn to feel, learn to smell—that is clinical method.

- Prostacyclins, ticlopidine, praxilene.
- Clopidogrel 75 mg; atorvastatin 10 mg; parvostatin 40 mg; *cilostazole* 100 mg bid—is a phosphodiesterase inhibitor which improves circulation (ideal drug).

All drugs act *at the collateral level* than on the diseased vessel.

- Analgesics, often sedatives, antilipid drugs like atorvastatin may be needed. Complamina retard (*xanthine nicotinate*) tablet which was used daily once earlier, is presently not in use. However, graded injection of xanthine nocotinate 3000 mg from day 1 to 9000 mg on day 5 is often practiced to promote ulcer healing, helps to increase claudication distance as a temporary basis. Low molecular dextran may be also used.

Care of the Limbs

- *Buerger's position and exercise*—regular graded exercises up to the point of claudication improves the collateral circulation.
  In *Buerger's position*, head end of bed is raised; foot end of bed is lowered to improve circulation. In *Buerger's exercise* leg is elevated and lowered alternatively, each for 2 minutes for several times at time.
- *Care of feet (Chiropady):* Exposure of feet to more cold and warm temperature should be avoided; trauma even minor like nail paring or pressure at pressure points in feet should be avoided. Dryness of feet and legs should be avoided by applying oil to the feet and legs. *Footwea*r should be selected carefully. It is better to wear socks with footwear. *Heel raise* by raising the heels of shoes by 2 cm decreases the calf muscle work to improve claudication.

Chemical Sympathectomy

- Sympathetic chain is blocked to achieve *vasodilatation* by injecting local anaesthetic agent (xylocaine 1%) paravertebrally beside bodies of L 2, 3 and 4 vertebrae in front of lumbar fascia, to achieve temporary benefit. Long time efficacy can be achieved by using *5 ml phenol* in water. It is done under C-Arm guidance. Feet will become *warm immediately* after injection. *Problems* are—possible risk of injecting phenol into IVC/aorta, spinal cord ischaemia.

Surgery

- *Omentoplasty* to revascularise the affected limb.
- *Profundaplasty* is done for blockage in profunda femoris artery so as to open more collaterals across the knee joint (It often makes better perfusion to the knee joint and flap of below-knee amputation).
- *Lumbar sympathectomy* to increase the cutaneous perfusion so as to promote ulcer healing. But it may divert blood from muscles towards skin causing muscle more ischaemic.
- *Amputations* are done at different levels depending on site, severity and extent of vessel occlusion. Usually either below-knee or above-knee amputations are done.
- *Ilzarov method* of bone lengthening helps in improving the rest pain and claudication by creating neo-osteogenesis and improving the overall blood supply to the limb.

Gene Therapy

- Intramuscular injection of vascular endothelial growth factor (VEGF) which is an endothelial cell mitogen that promotes angiogenesis.

TAKAYASU'S PULSELESS ARTERITIS (Takayashu, 1938—Ophthalmologist, Japan)

- It is progressive, initially symptomless panarteritis involving aortic arch and branches of aorta of unknown etiology, probably immunological.
- It is common in young females (85%); common in Japan; commonly subclavian artery is involved (85%); involves all layers of arteries of upper limb and neck; often bilateral. It remains unnoticed for long time.

Features

- Fever, myalgia, arthralgia, upper limb claudication.
- Absence pulses in upper limb/limbs, neck; hypertension.
- Fainting on turning the neck or change in position; atrophy of face.
- Thrill/bruit along major arteries of upper limb and neck are the features.
- Optic nerve atrophy without papilloedema.
- Weakness and paraesthesia of upper limb.
- Cerebral softening, convulsions, hemiplegia can occur.
- Occasionally it can be life-threatening. Myocardial infarction; embolism, ischaemia are other *complications.*
- DSA; MR angiography and Doppler are the *investigations.*

Treatment

- To suppress immunity prednisolone 50 mg/day and cyclophosphamide daily is given.
- Vascular reconstruction.

RAYNAUD'S PHENOMENON

> *Under the influence of a very moderate cold, and even at the height of summer, she (case 1) sees her fingers become ex-sanguine, completely insensible, and of a whitish yellow colour.... One might indeed have suspected that the local asphyxia was connected with a spasmodic state of the vessels,... a functional trouble localised to the arterioles immediately contiguous to the capillaries.*
>
> —**Maurice Raynaud,** 1862 (French Surgeon)

It is an episodic vasospasm, i.e. arteriolar spasm. It leads to sequence of clinical features called as Raynaud's syndrome.

Raynaud's syndrome

Sequence of clinical features due to arteriolar spasm.

- *Local syncope:* It is due to vasospasm, causing white cold palm and digits along with tingling and numbness
- *Local asphyxia*: It is due to accumulation of deoxygenated blood as the result of vasospasm causing bluish discolouration of palm and digits with burning sensation (due to accumulated metabolites)

- *Local recovery:* It is due to relief of spasm in the arteriole, leading to return of blood to the circulation causing flushing and pain in digits and palm (pain is due to increased tissue tension)
- *Local gangrene*: If spasm persists more than ischaemic time (more than one hour in upper limb), then digits go for ulceration and gangrene. Does not occur regularly but is an occasional phenomenon in the cycle

Coffman criteria for Raynaud's syndrome—"episodic attacks of well-demarcated reversible self-limiting colour changes for 1-20 minutes on exposure to cold/emotional stimuli and is symmetrical/bilateral lasting for 2 years".

Causes for Raynaud's Phenomenon

- ***Raynaud's disease***:
  - It is seen in females, usually bilateral.
  - It occurs in upper limb with normal peripheral pulses.
  - It is due to upper limb (hand) arteriolar spasm as a result of abnormal sensitivity to cold. Patient develops blanching, cyanosis and later flushing as in Raynaud's syndrome. Occasionally if spasm persists it results in gangrene.
  - Symptoms can be precipitated and observed by placing hands in cold water.
- Working with ***vibrating tools***: Like pneumatic road drills, chain saws, wood cutting, fishermen travelling in machine boats—*vibration white finger*.



Fig. 1.354: Vasculitis can cause arterial insufficiency.

- ***Collagen vascular diseases***: Like scleroderma, rheumatoid diseases causing vasculitis (all autoimmune diseases).
- ***Other causes***: Cervical rib, Buerger's disease, Scalene syndrome.

It is often associated with CREST syndrome (**C**alcinosis cutis**,** **R**aynaud's phenomenon, **E**sophageal defects, **S**clerodactyly, **T**elangiectasia).

Types of Raynaud's phenomenon

- Vasospastic
- Obliterative

Raynaud's can be:

- *Primary Raynaud's* is an idiopathic vasospastic disorder without underlying identifiable causes. Usually there is no significant pain in primary type. Primary is probably due to increased sensitivity of alpha 2 receptors to nonepinephrine; decreased nitric oxide and endothelin 1 in endothelial cells; increased serotonin and thromboxane. It is common in females and younger age group. Usually it is bilateral involving all digits.
- *Secondary Raynaud's* is vasospasm due to some underlying cause. Significant pain will be present especially during rewarming stage. There are positive autoantibodies; equal in both sexes; occurs at any age group; need not be bilateral.

Features

- Commonly *bilateral.*
- Common in young *females*.
- Raynaud's disease is common in *w*estern *w*hite *w*omen.
- Usually medial *four digits* and palm are involved. Thumb is *spared*.
- Features of pallor/*blanching* (syncope), *dusky cyanosis* (asphyxia), rubor/painful *red engorgement* (recovery) are the presentation. Occasionally if vasospasm becomes longer, gangrene or ischaemic ulceration supervenes along the tips of the fingers.
- Peripheral pulses (radial/ulnar) are *normally* felt. These pulses will be absent in upper limb TAO.
- Repeated *attacks* are common.

Investigations

- Type is identified by angiogram of hand (DSA/MR angiogram), arterial Doppler/Duplex scan.
- Other investigations required are X-ray of the part, antinuclear antibody (ANA assay) tests specific for different conditions
- Assessment of segmental blood pressure gradient from brachial-forearm-wrist-fingers; finger tip thermography; *cold recovery time* (normal is less than 10 minute, but in Raynaud's it is more, often up to 30 minutes); *reactive hyperaemia time* (pneumatic cuff is inflated and kept for 5 minutes and released to observe hyperaemia); nail fold capillary microscopy; Laser Doppler flux to assess microvascular perfusion of finger skin—are *special methods* of evaluations.
- Other routine investigations for arterial diseases like blood sugar/lipid profile/hypercoagulability status.

Treatment

- Treat the cause.
- Avoid precipitating factors—protect from cold/proper dress/hand warmer electrical or chemical/hand gloves. Avoid smoking even though it is not direct etiological cause (other than upper limb TAO), but it may possibly aggravate the disease. Avoid vibrating tools.

- Vasodilators/pentoxiphylline/low dose aspirin (75-100 mg per day). Calcium antagonist (nifedipine 20 mg) is useful. Steroids may be useful in case of secondary Raynaud's.
- ACE inhibitors, nitrates, endothelin inhibitors (bosentan), epoprostenol—prostaglandin a potent vasodilator and antiplatelet drug (continuous intravenous infusion can be given), iloprost—prostacycline analogue, PG E1, misoprostol (oral PG E 1)—are all tried at different stages of the disease.
- Cervical sympathectomy—is used for nonhealing digital ulceration. Not very beneficial to Raynaud's syndrome.

TEMPORAL ARTERITIS

- There is localised inflammatory giant cell infiltration of arterial wall (*giant cell arteritis*) involving superficial temporal, facial, retinal, upper limb, coronary and vertebral arteries.
- It is common after 50 years. Common in females (2:1).
- Claudication of facial muscles, ischaemic severe headache, tender, thrombosed superficial temporal artery and its branches are the features.
- Retinal ischaemia leading into irreversible blindness is dangerous feature. Involvement of coronary artery may cause myocardial infarction.
- Temporal artery biopsy is diagnostic – shows giant cell granuloma with CD4+ T lymphocytes.
- High dose long-term *prednisolone 80 mg* / day is needed. In involvement of retinal artery IV hydrocortisone / *methylprednisolone* may be needed initially.

TREATMENT OF ARTERIAL DISEASES

a. Medical

General Measures

- Stop smoking, reduction of weight, exercise.
- Change in life style, care of feet.
- Control of diabetes and hypertension.
- Buerger's position and exercise.

Drugs

- Nifedipine, praxilene, pentoxiphylline, low dose aspirin, prostacycline, dipyridamole, ticlopidine.
- Clopidogrel (75 mg).
- Cilostazol (type III phosphodiesterase inhibitor) 100 mg BD—inhibits platelet aggregation.
- Oral anticoagulants are used *only* if there is history of embolism or atrial fibrillation.
- Prostaglandins, growth factors, vascular endothelial growth factor (VEGF), E_2Fdecoy (blocks intimal and smooth muscle cell proliferation), mesoglycan (breaks blood clot), testosterone, herbals like garlic (reduces viscosity of blood) are other newer drugs under use and trial.
- B vitamins and folic acid reduces homocysteine level (which is a risk factor).
- Inositol, L-carnitine (1500 mg), magnesium 500 mg (not in renal failure or with diarrhea), vitamin E and C are other agents often used to improve walking distance.
- Heparin is used *only* in acute phase or embolism.

b. Surgery

- ***Percutaneous transluminal balloon angioplasty (PTA):*** Through transfemoral Seldinger approach, initially angiogram is done. Then under guidance (fluoroscopic) stenosed area is approached. First guidewire is introduced through which balloon catheter is passed. Balloon of the angioplasty catheter is inflated at stenosed area *for one minute* and repeated if required. Plaques should rupture. Catheter is withdrawn. It is useful in cases of localised stenosed areas.

Note:

- Often *nonexpandable or self-expandable stents* are used if stenosed segment is not dilated adequately through balloon—PTA with stenting.
- PTA for carotid artery stenosis is risky and not ideal as there will be possible release of microemboli during dilatation procedure which can precipitate stroke. Specialised balloon catheters with umbrella tip which can trap the microemboli may be used in these places.

Types

- Conventional: Here balloon is inflated along the lumen to break the plaque circumferentially.
- Subintimal: Here balloon is inflated after passing subintimal plane to break the plaque.

Complications

- Thrombosis, bleeding, sepsis.
- Embolism, dissection, retroperitoneal haematoma.
- Pseuodoaneurysm formation.

Advantages

- It is done under local anaesthesia.
- Procedure can be repeated if needed.
- Stent can be placed at a later stage if needed.
- It is done when stenosis is *less than* 5 cm. In ideal indications its efficacy is equal to surgery.

Disadvantages

- It is less useful for lengthy blocks or stenosis more than 5 cm.



Fig. 1.355: Conventional and subintimal types of PTA.



Fig. 1.356: Percutaneous transluminal balloon angioplasty (PTA). Note the inflated balloons on both side iliac arteries.



Figs 1.357A and B: DSA showing left sided aortoiliac block and correction after doing PTA.

- It is dangerous to do in stenosis of carotid artery where endarterectomy is ideal.

♦ ***Atherectomy:***

It is removal of atheroma either through open surgery or by percutaneous route from the wall of the vessels.

♦ ***Thrombectomy:***

It is removal of thrombus through an arteriotomy of larger vessels. Done in aortoiliac, femoropopliteal region.

♦ ***Endarterectomy:***

- It is removal of thrombus along with diseased intima through an arteriotomy. Endothelium of the vessel is removed, hence the name.



Figs 1.358A and B: DSA showing superior mesenteric artery stenosis. It is corrected by PTA.

- It is done in *carotid,* aortoiliac and occasionally aortofemoral blocks. It is also called as *disobliteration/ reboring*. There are three methods—(1) *Open method*—Arteriotomy is done along the entire diseased segment; endarterectomy is done by removing thrombus, diseased intima with plaque along the plane of media. Arteriotomy is closed using 5 zero polypropylene suture and patient is heparinised. (2) *Semiclosed method*—Here two arteriotomies are done on either ends of the level of obstruction; loop endarterectomy stripper is passed from one end to complete the endarterectomy; two arteriotomies are closed. (3) *Wiley's eversion endarterectomy*—Here artery is cut transversely at the junction of diseased and normal nondiseased segment; diseased intima with plaque is circumferentially dissected; artery is everted out to extract the diseased intima like a tube; everted artery is reduced and sutured to normal end of the artery. *Advantages are*—it avoids prosthetic graft and its complications. *Problem* is—reocclusion and restenosis.

♦ Placement of ***intraluminal stent for localised stenosis***.

♦ ***Profundaplasty:***

- It is done when there is localised block in opening of profunda femoris (deep femoral). Profunda femoris is opened, thrombus if present, is removed. Opening is widened using either venous or synthetic (Dacron or PTFE) grafts. This procedure allows collaterals across the knee joint to open through profunda femoris and so gives good blood supply below-knee level and may prevent patient going in for above-knee amputation.

*Absolute diagnosis are unsafe and are made at the expense of the conscience.***—William Osler**



Fig. 1.359: Thrombectomy.

(May be able to save knee joint with below-knee amputation with better prosthesis.)

- Lateral angiogram view is needed to identify the orifice of profunda femoris. Disease involves *invariably only at the orifice* without extending distally towards 1st perforator branch. Endarterectomy at the junction and closure with a venous patch widens the opening adequately.

◆ ***Reverse saphenous vein graft:***
In case of femoropopliteal block, saphenous vein is dissected out, reversed and sutured above to the femoral artery and below to popliteal segment so as to bypass the blood through reverse saphenous vein graft. Saphenous vein is reversed to nullify the action of valves so as to allow easy flow of blood.


Atheroma
Artery
Artery
Arteriotomy
Atheroma intima removed
Ring stripper

Fig. 1.360: Endarterectomy technique. Both thrombus and diseased intima are removed through an arteriotomy. Often ring stripper is used to remove the atheromatous plaque.

◆ ***In situ saphenous vein graft:***
It is arterialisation of saphenous vein. Saphenous vein intact in same position is sutured above and below the blocked femoropopliteal region to bypass the blood across. Venous valves are removed through valvulotomy instrument so as to allow the blood to pass. Here nutrient supply of vein is left intact with proximal part of the vein sutured to wider part of the femoral artery, narrow distal part is sutured to narrow part of the artery.


Common iliac artery
Internal iliac artery
External iliac artery
Inguinal ligament
Common femoral artery
(Deep femoral artery) profunda femoris artery
Superficial femoral artery (blocked)
Dacron graft

Fig. 1.361: Profundaplasty for deep femoral block.

◆ ***Arterial/venous grafts:***

Synthetic:
- ❖ Dacron woven graft
- ❖ Dacron knitted graft
- ❖ PTFE—polytetrafluoroethylene graft

Natural:
- ❖ Internal mammary artery (ideal one)
- ❖ Long saphenous vein either reverse or *in situ*
- ❖ Umbilical vein graft (cryopreserved)—3 mm vein is the minimum diameter required
  Grafts of different length and size are available

Different procedures

- Aortofemoral bypass graft (end to side)—5% mortality.
- Ileofemoral bypass graft.
- Femorofemoral bypass graft
- Femoropopliteal graft.
- Femorodistal graft.
- Axillofemoral graft.

Problems with grafts: Leak, infection, thrombosis, cost factor, availability, reblock.

Note:
Angioscope is used to visualise the valves in saphenous vein or to visualise the completion of the by pass grafts like femorodistal graft.


Bypass graft
Occluded vessel

Fig. 1.362: Bypass graft (Aortoiliac).


Inguinal ligament
CIA
IIA
EIA
Femoral artery
Profunda femoris
Block
Graft

Fig. 1.363: Femoropopliteal bypass graft.

- ***Cervicothoracic preganglionic sympathectomy:*** It is removal of 2nd and 3rd thoracic ganglia which contains cells of postganglionic fibres supplying the upper limb. Preganglionic white rami communicantes fibres from 2nd and 3rd sympathetic nerves enter thoracic T1 ganglion and supplies head and neck region through upper part of the stellate ganglion. Preganglionic sympathetic nerve entering the 2nd and 3rd ganglia from below, supplies sympathetic fibres for upper limb through the lower part of the stellate ganglion. In cervical sympathectomy for upper limb ischaemia, lower part of stellate ganglion with Kuntz nerve is divided. For head and neck hyperhidrosis entire stellate ganglion should be removed which leads to development of Horner's syndrome. For hyperhidrosis of axillary area, along with stellate ganglion upper four thoracic ganglia has to be removed.


Arota
Arterial graft
EIA
EIA
CIA
IIA
Inguinal ligament
Femoral artery
Inguinal ligament
Deep femoral artery

Fig. 1.364: Aortofemoral bypass graft (End to side).



Fig. 1.365: On table picture of aortofemoral arterial graft.

Indications

- Cervical rib with vascular manifestations—useful
- Raynaud's phenomenon—useful
- Hyperhidrosis—very useful
- Upper limb vasospasm due to other causes—useful
- Acrocyanosis—useful
- Causalgia—very useful
- Sudeck's osteodystrophy

Approaches

- *Supraclavicular approach:*
  Through a supraclavicular incision sternomastoid, (omohyoid is retracted or divided) scalenus anterior

Einstein died of ruptured aortic aneurysm. Nissen did cellphone wrapping of the aneurysm in Einstein muscles, are divided. Phrenic nerve is displaced medially; subclavian artery is pushed downwards; thyrocervical trunk is identified and ligated securely, suprapleural membrane is depressed, stellate ganglion is identified in the neck of the first rib. All rami communicantes from second and third ganglia are divided. Grey ramus from second ganglion to first thoracic nerve called as *Kuntz nerve,* is also divided.

Complications

- Bleeding
- Injury to subclavian artery and nerves
- Pneumothorax and haemopneumothorax
- Horner's syndrome with ptosis, miosis, anhydrosis, enophthalmos
- Chylous fistula, chylocele
- Post-sympathetic neuralgia

- *Transthoracic/axillary approach (Hedley atkins)*: This gives better visibility and easier removal of rami, lower down compared to supraclavicular approach. Patient is placed in lateral position; transverse incision is made just below the hair bearing line; intercostobrachial nerve is preserved. Thorax is opened at 2nd space. Sympathetic chain is identified at the neck of 1st rib.
- *Thoracoscopic sympathectomy* is the choice, and popular approach at present.

  Advantages are better visibility with magnification, less trauma of access (wound), faster recovery, and precise.



Fig. 1.366: Cervical sympathectomy scar in the neck and patient has developed Horner's syndrome. Healed ulcer over tip of index finger on left side is seen. Patient is asymptomatic after sympathectomy.

- ***Lumbar sympathectomy***:

Indications:

- Peripheral vascular disease like TAO.
- To promote healing of cutaneous ulcers.
- To change level of amputation and to make flaps to heal better after amputation.
- Causalgia of lower limb (it is common in upper limb).
- Hyperhidrosis of lower limb is rare.



Fig. 1.367: Ptosis of right eye in Horner's syndrome.

Principle:

- It increases the cutaneous blood supply thereby promoting healing of ulcer and skin flaps in amputation. It is a preganglionic sympathectomy. Ganglion L2 and L3 supplies legs below knee level. L1 supplies upper part of thigh and buttock region. L1 lies under the crus of diaphragm. L4 lies under the common iliac vessels below.
- It increases the blood flow for 2-4 weeks by abolishing constriction of arterioles and precapillary sphincters (basal and reflux). It produces transient small increase in distal perfusion; increases the nutritive perfusion to *promote ulcer healing*; alters the pain perception and pain impulse transmission temporarily.

Procedure:

Under general or spinal anaesthesia, ganglia are approached through a transverse incision in the loin at the level of umbilicus, through extraperitoneal approach, by dividing external oblique, and internal oblique, and splitting transverse abdominis muscles. Inferior vena cava on right side, aorta on left side are identified. Sympathetic chain is identified by its rami, over transverse processes of lumbar spines. L_2, L_3, L_4, L_5 ganglia are removed. L_2 is identified by its size (**Larger**) and more number of rami. L_1 is retained on one side in bilateral cases. If both are removed it will lead to failure of ejaculation and so sterility *(Dry ejaculation).*

Complications

- Injury to IVC or aorta
- Bleeding lumbar veins
- Spinal vessel spasm and so ischaemia of spinal cord and paraplegia, dry ejaculation
- Injury to bowel and ureter
- Wound infection and abscess formation
- Post-sympathetic neuralgia
- Paradoxical gangrene of opposite leg and foot

- Its effects are only temporary (3-4 weeks). Long-term results are doubtful. It can be combined with omentoplasty.
- It can also be done along with below-knee amputation to increase the blood supply of skin flap so as to have better healing.

- Limb will become warmer immediately after sympathectomy.



Fig. 1.368: Lumbar sympathectomy scar with ischaemic ulcer foot showing healing sign.

***Note*:**
Lumbar sympathetic chain may be mistaken for lymph nodes, fat, tendon of psoas muscle, genitofemoral nerve.

- ***Chemical sympathectomy*:**
  - It is done in lateral position using a long spinal needle under local anaesthesia. Position is confirmed by injecting dye under fluoroscopy. Later 5 ml of *phenol* in water or absolute alcohol is injected lateral to the vertebral bodies of fourth and second lumbar vertebrae. Care should be taken to see that the needle does not enter IVC or aorta.
  - Procedure is contraindicated in patients with *bleeding disorders* and in patients who are on *anticoagulants.*
- ***Omentoplasty:***

Indications

- Peripheral vascular disease—to improve circulation
- For lymphoedema, it helps by providing lymphatics and so to drain lymph from the limb
- It is also tried for revascularisation of pharynx, cranial cavity



Fig. 1.369A



Figs 1.369B and C

Figs 1.369A to C: Omentoplasty procedure for revascularisation of the ischaemic limb.

Omentum is supplied by omental vessels


Coeliac artery
Gastroduodenal artery (through common hepatic artery)
Splenic artery
Right gastroepiploic artery
Left gastroepiploic artery
Omental vessels

Four layers of omentum has got omental arcades of vessels. Omentum is also rich in lymphatics. It has got adhesive property. By retaining one of the pedicles, omentum can be mobilised so as to reach the limb to maintain the circulation. It can also be mobilised up to the ankle. It promotes ulcer healing, reduces the pain and controls the features of ischaemia. It can also be used in upper limb ischaemia. But, if patient continues to smoke, disease spreads to these omental vessels also. Often it can be mobilised to both lower limbs in bilateral diseases.



Fig. 1.370: Incisions for omentoplasty in the abdomen (upper midline) and in lower limb.

> *In early painful stage the ischemic foot (gangrene threatened) is nearly always pink, the skin being atrophied as though it were stretched tightly over underlying structure*
> **—Wilfrid G Oakley**

Complications of omentoplasty:

- Abdominal sepsis.
- Incisional hernia, where omental pedicle is tunneled into the limb from the abdomen.
- Adhesions and intestinal obstruction.

Procedure: Under general anaesthesia, abdomen is opened with upper midline incision. Omental vessels are identified. Omentum with its blood supply is carefully mobilised to get an adequate length. Lengthened, mobilised omentum is brought into the subcutaneous plane through abdominal wall, lateral to the lower part of rectus muscle. Later this pedicle is mobilised in the subcutaneous tunnel across the leg, burried in the deep fascia.

- ***Other treatment methods*:**
  - *Amputations* are done at different levels depending on extent of gangrene, site of block, amount of collaterals.



Fig. 1.371: Below knee amputation stump which is also ischaemic. Patient underwent below knee amputation for gangrene foot. But patient might need above knee amputation.

SUBCLAVIAN STEAL SYNDROME

Following obstruction of the first part of subclavian artery, vertebral artery provides collateral circulation to the arm by reversing its blood flow. This causes *cerebral ischaemia with syncopal attacks,* visual disturbances, diminished blood pressure in the affected limb.



Fig. 1.372: Subclavian steal syndrome.

- It is more common on left side.
- Vertebrobasilar symptoms like dizziness, syncope, visual disturbances, vertigo can occur.
- Pain, heaviness, paraesthesia and fatigue in the arm which is aggravated by exercise.
- Radial pulses on both sides are asymmetrical.
- Blood pressure on the diseased side will be 20 mmHg less compared to normal side.
- *Javid test:* Here compression of carotid artery makes ipsilateral radial pulse feeble.

Investigations

Duplex scan and angiogram. DSA is useful.

Treatment

- Transluminal balloon angioplasty.
- Endarterectomy or bypass graft.
  (Common carotid—subclavian graft).

ACUTE ARTERIAL OCCLUSION

It is a condition of acute lack of tissue perfusion due to sudden cessation of circulation. Main axial artery of the limb is blocked presenting within minutes to hour after occlusion.

It is *common* in lower limb, upper limb; but can occur in mesenteric, cerebral, coronary arteries.

Causes

- *Embolism is the most common* cause in developing country.
- *Trauma*.
- *Thrombosis* of an artery: Normal artery can develop sudden acute thrombosis in certain special situations with hypercoagulable status like malignancy, leukaemia, antiphosholipid antibody syndrome, protein C/protein S/antithrombin deficiency; polycythaemia rubra vera, thrombocytosis. It is commonly observed in external iliac artery, profunda femoris artery and popliteal artery.
- *Thrombosis of a bypass graft* is common cause in western countries which occurs at the site of anastomosis.

Pathophysiology

Distal ischaemia begins immediately after acute obstruction. Most sensitive peripheral nerves are first involved, and then muscles, subcutaneous tissue and skin are affected in order. Irreversible ischaemia occurs in 6 hours. Golden period is 1-6 hours. Ischaemia may get aggravated by—propagation of thrombus below and above the block occluding the orifices of collaterals, fragmentation of embolus, associated thrombosis, acute compartment syndrome.

Acute ischaemia causes endothelial injury of capillaries, arterioles and venules with luminal obliteration. Raised capillary permeability causes fluid leakage into extravascular space forming massive tissue oedema deep to deep fascia which by raising the intracompartmental pressure further reduces the perfusion leading into *acute compartment syndrome*.

Features

- *Pain* which is continuous, severe, steady, bursting.
- *Pallor* of the distal part with extreme cold limb.
- *Pulselessness*—sudden loss of earlier palpable pulse.
- *Paraesthesia*—sensory disturbances like tingling, numbness or complete loss of sensation.
- *Paresis*—damage to motor nerve and muscle leading into paralysis as a late grave feature.
- *Poikilothermia*.

Pain, paraesthesia, paresis are due to ischaemia of peripheral nerves which are sensitive to hypoxia.

TRAUMATIC ACUTE ARTERIAL OCCLUSION

Causes

- Thrombus due to trauma.
- Subintimal haematoma.
- Acute compartment syndrome.
- During femoral or brachial arterial catheterisation for either diagnostic or therapeutic procedures.

Clinical Features

History of trauma, *pain, swelling at the site, pallor, pulselessness, cold limb.*

Investigation

Duplex scan, angiogram.

Treatment

- Wound is explored and tear in the artery is identified. It is sutured using nonabsorbable monofilament material, *polypropylene 6-0*. Often venous or dacron graft is required for interposition.
- Proper antibiotics and heparin are required to prevent thrombosis of the vessel. Later patient is advised to take oral warfarin for maintenance.
- ***Compartment syndrome*** is common in anterior compartment of leg and in front of forearm. Here because of the closed compartment, pressure increases following fracture, haematoma which compresses over the vessel. It leads to blockade of vessel causing acute ischaemia of the limb presenting with severe pain, pallor, pulselessness.
  - *Treatment: Immediate decompression by longitudinal fasciotomy*, is the treatment of choice, wherein deep fascia is cut adequately to relieve the compression. Otherwise limb may go for severe ischaemia, gangrene and may land in amputation.
- Associated fractures, haematoma, vessel tear has to be managed accordingly.

EMBOLISM

('Embolus' means in *Greek*—peg; first this term was used by Virchow in 1854)

It is due to a solid, liquid or gaseous, material which is floating and travelling in the bloodstream, eventually blocking the vessel on its pathway.

- ***Arterial emboli*:**

Sources

- *Cardiac source* (80%):
  - Due to mural thrombus following mitral stenosis and atrial fibrillation (50%); myocardial infarction (25%); others (5%) like prosthetic valves, endocarditis, intracardiac tumours (atrial myxoma)
- *Noncardiac (10%)*:
  - Aneurysms (5%); atheromatous plaque in proximal artery, paradoxical (1%)
- *Idiopathic* is 10%
- Others (4%) like:
  - Cervical rib causing poststenotic dilatation of subclavian artery can cause emboli
- *Cryptogenic*—an unknown source (5%)—after investigations source is not found

- ***Venous emboli*** are due to DVT causing pulmonary embolism.
- ***Venous-arterial paradoxical emboli:*** Seen in intra-cardiac shunt (ASD) or intrapulmonary shunts (A-V malformations) *(Osler-Weber-Rendau syndrome)*
- ***Fat embolism***.
- ***Air embolism***.

Effects of Arterial Embolism

- *Brain:* Blockage at *middle cerebral artery* causes hemiplegia, transient ischaemic attacks (TIA), visual disturbances
- Blockage at *central retinal artery* causes amaurosis fugax or permanent blindness
- Blockage at *mesenteric vessels* causes intestinal gangrene
- Blockage at *renal artery* leads to haematuria, loin pain
- Blockage at *limb vessels* causes pain, pallor, pulseless, paraesthesia, paresis, ulceration, gangrene
- Most common site of arterial emboli is *common femoral artery*

Sites of Lodging of Emboli

The most common site is lower limbs (75%). 10% brain; 10% upper limb; 5% superior mesenteric and renal arteries.

In the lower limb the most common site is at the bifurcation of common femoral artery (40%); popliteal artery (15%); common iliac artery (12%); aortic bifurcation (10%).

Unless you try to do something beyond what you have already mastered, you will never grow.

Features of Embolism

- Earlier history of claudication is absent but history suggestive of disease for source of emboli will be present.
- Sudden, dramatic, rapid development of pain with numbness.
- Limb becomes rapidly cold and mottled with blebs.
- Loss of sensation and movements.
- Absence of distal pulses but forcible, expansile, prominent proximal pulse. For example—prominent femoral artery pulsation with embolic bock at popliteal level.
- Toxic features.
- Collapsed veins, cold limb distal to the level of block, oedema and presence of blebs distally.
- Muscle which is soft normally while palpating will feel doughy initially but later becomes stiff. Once stiffness of muscle is found embolectomy benefit is bleak.

Differences between embolism and thrombosis

Features	*Embolism*	*Thrombosis*
Source	Present	Not present
Pulse	Proximal and contralateral pulses normal	Same and opposite side pulses may be absent
Temperature	Severely cold	Cold or normal
Angiography	Sharp cut off sign	Diffuse tapered disease
Collaterals	Very few—not well-developed	Well-developed



Fig. 1.373: Right leg showing features of acute embolism.

Investigations for Arterial Embolism

- Emergency Doppler angiogram, ECG and echocardiography. Angiogram is *gold standard* in all acute limb ischaemia. It differentiates between embolism and thrombosis; status of vessel proximally and distally. Angiography should ideally be done from contralateral limb or through left brachial.
- Relevant tests for origin of emboli. Prothrombin time, APTT, BT, CT, platelet count should be done.

Note:
Once embolism occurs irreversible changes occur distally in 6 hours, so ideal period for intervention is within 6 hours.

Classification of Severity of Acute Limb Ischaemia

Class I: Viable—no pain; no neurological deficit; Doppler shows audible signal. Venous flow present.
Class IIa: Marginally threatened—no pain; numbness/paraesthesia; no audible Doppler signal. Venous flow present.
Class IIb: Immediately threatened—persistent pain; sensory and motor loss; no Doppler signal. Venous flow present.
Class III: Irreversible—paralysis and anaesthesia. No venous flow.

Ischaemia up to class IIb with normal venous flow is called as **Early**; ischaemia which is class III, with muscle rigor, marbled skin and without any venous flow is **Late**. This late ischaemia is more likely to land with amputations even though revascularization can be tried.

Treatment

Treatment of Embolism and Thrombosis of Acute Limb Ischaemia

Immediate infusion of 5000-10,000 units of IV heparin and relief of pain are needed first.

Surgical

- *Embolectomy* (*surgical exploration and removal of clot*) is the choice for embolus. It is done either by interventional balloon 5 French (Fogarty, 1963) embolectomy or open method. It is the standard treatment for arterial embolism. It can be repeated several times until adequate bleeding occurs.
- For acute thrombosis causing acute limb ischaemia, open thrombectomy with or without bypass may be the surgical treatment; but it is not the standard treatment for acute thrombosis (Standard is thrombolysis, Dotter and co, 1974).

Endovascular therapy

- Intrarterial thrombolysis using *urokinase*.
- Percutaneous mechanical thrombectomy—it is done either by suctioning clot via catheter or dissolution of thrombus by pulverization and aspiration by high speed motors or fluid jets.
- Ultrasound accelerated thrombolysis using catheter based or transdermal using acoustic cavitation to ablate thrombus.

Embolectomy

- It is done as early as possible as an emergency operation.
- Under fluoroscopic guidance, *Fogarty catheter* (interventional radiology) is passed beyond the embolus and balloon is inflated. Catheter is withdrawn out gently with embolus. Procedure has to be repeated until embolectomy is completed and good back bleeding occurs. Angiogram is repeated to confirm the free flow.
- Postoperatively initially heparin and later oral anticoagulants are used. Procedure is done under general anaesthesia or local anaesthesia.
- *Open arteriotomy and embolectomy* can be done by *direct approach* and later the arteriotomy has to be sutured. Postoperatively anticoagulants and antibiotics are given.

Intra-arterial thrombolysis using fibrinolysins: After passing arterial catheter, angiogram is done and agents are injected intraarterially through the arterial catheter.

Drugs used are:

- Streptokinase (here lysis occurs in 48 hours).
- Urokinase. It is commonly used for thrombolysis. It converts plasminogen to plasmin which breaks fibrin clots. Initial bolus of 2,50,000 IU is given followed by an infusion of 4,000 IU/min for 4 hours, later continuous infusion of 2,000 IU/min to complete the lysis. Even though controversial, it is of usual practice to infuse 1000 IU/hour of heparin to prevent new thrombus formation. Check angiography should be done during therapy. Multiholed catheter (5 French) is used for infusion.
- Tissue plasminogen activator (TPA)—Alteplase, Reteplase—here lysis occurs in 24 hours. TPA is *better and ideal*; but it is costly. It has very less side effects.
- TPA pulse-spray method—here lysis occurs in 6 hours.

Contraindications for thrombolysis

- Recent stroke
- Recent major surgery or major bleed like of varices
- Recent eye surgery
- History suggestive of or confirmed active duodenal/gastric ulcers
- Pregnancy
- Uncontrolled hypertension or coagulation disorders

Note:
Heparin should not be used concomitantly with fibrinolytics.

Anticoagulant therapy to prevent recurrent emboli.

Immediate infusion of heparin 5000 units intravenously to prevent further extension of thrombus is needed.

Advantages of thrombolysis	*Disadvantages of thrombolysis*
• Gentle angiographic clot removal	• Useful only for class I and IIa acute ischaemia
• Survival and limb salvage is equal	• Bleeding at the site and elsewhere is possible
• It is mainly useful for acute thrombus	• 25% rate of failure
• For embolus it is used often as an adjunct along with embolectomy	
• It avoids surgery	

Complications of Revascularisation in Acutely Ischaemic Limb

- *Reperfusion* injury
- *'No reflow' phenomenon*: It is due to severe capillary oedema causing poor peripheral tissue hypoperfusion in spite of major vessel revascularisation.
- *Acute compartment syndrome* can occur due to massive ischaemic oedema especially of skeletal muscles deep to deep fascia which compress on venules exceeding tissue interstitial pressure causing further compromise in tissue perfusion. Compartment pressure when measured using transducer needles will be more than 40 mmHg or > 30 mmHg for 3 hours or above the mean arterial pressure. Presents with muscle weakness, sensory changes, leg pain which is aggravated by dorsiflexion of toes.
- Other complications are—sepsis, reblock, bleeding and catheter related complications.

REPERFUSION INJURY

- It occurs after reestablishment of arterial flow to an ischemic tissue bed which further leads to tissue death causing specifically *peripheral muscle infarction*. It is due to sudden release of oxygen free radicals which blocks the microcirculation, with release of high levels of potassium (hyperkalaemia) and myoglobin (myoglobinaemia and myoglobinuria). Haemodynamically patient becomes unstable with lactic acidosis, intracellular changes, interstitial oedema and cardiac dysfunction. It is often life-threatening.
- *Haimovici triad* of revascularisation injury (1960)—(1) Muscle infarction; (2) Myoglobinuria; (3) Acute renal failure.
- Severe ischaemia causes oedema in the muscular compartment with raise in compartment pressure more than the essential capillary perfusion pressure causing *acute compartment syndrome*. It is common in the anterior compartment of the leg. It is basically in the skeletal muscles deep to deep fascia. Compartment pressure when measured using transducer needles will be more than 40 mmHg or > 30 mmHg for 3 hours or above the mean arterial pressure. Muscle weakness, sensory changes, leg pain which is aggravated by dorsiflexion of toes.
- *'No re-flow' phenomenon* due to tissue oedema causes capillary perfusion block. Even though compartment syndrome and 'no reflow' phenomemenon are separate entities they are always seen together along with reperfusion injury.
- Metabolic acidosis, acute tubular necrosis causing acute renal failure and cardiac arrhythmias may set in and become life-threatening.
- **Features are**—toxaemia; oliguria; persistent pain and oedema in the leg with muscular tenderness; raised blood urea and serum creatinine with features of acute ischaemia in the limb. Raised creatinine level (renal failure), creatine kinase (muscle lysis) are typical.
- Treatment:
  - Mannitol to prevent renal failure; fluid therapy.
  - *Fasciotomy* to reduce raised compartment pressure. All four compartments of lower limb should be decompressed surgically. Long vertical lateral deep fasciotomy incision in the calf behind the fibula along the deep fascia and its fibular attachments is a must. Bleeding is common after fasciotomy as patient is heparinised. Infection of the wound can occur. Later, once the patient is stabilised and oedema subsides with healthy wound, secondary

suturing or skin grafting is done. If after fasciotomy, patient survives then it is with eventual development of *Volkmann's ischaemic contracture*.

- Antibiotics and supportive therapy.

SADDLE EMBOLUS

It is an embolus blocking at *bifurcation of aorta.*

Causes

- Mural thrombus after myocardial infarction.
- Mitral stenosis with atrial fibrillation.
- Aortic aneurysm.



Fig. 1.374: Saddle embolus blocking the bifurcation of abdominal aorta. It causes severe, rapid, dramatic symptoms.

The embolus which blocks at aortic bifurcation is usually large.

Clinical Features

- Features of sudden, rapidly progressive ischaemia in both lower limbs.

Note:
In aortic bifurcation thrombus, there is earlier history of claudication in the buttock often with *Leriche's syndrome*. Symptoms are slow and gradual but not dramatic. Collaterals between aorta and iliac arteries have well-formed and so sudden, rapid development of gangrene will not occur.

- Gangrene of both lower limbs.
- Features of associated infection.

Investigations

- Arterial Doppler, aortic angiogram.
- U/S abdomen.

Treatment

- Initially, heparin is injected intravenously—10,000 units and later 5,000 units subcutaneously 8th hourly.
- Embolectomy can be done using Fogarty's catheter.
- Open arteriotomy and embolectomy can also be tried.
- Antibiotic prophylaxis is given to prevent infection.

EMBOLECTOMY

Indications

- Acute embolic blockade of artery commonly seen in common femoral, cranial vessels, mesenteric vessels.
- It should be done within 6 hours as after 6 hours irreversible changes occur.
- It is usually done under local anaesthesia under C arm guidance with anaesthetist monitoring the patient. It can be done under spinal or general anaesthesia.



Fig. 1.375: Embolectomy technique.

Methods

- *Interventional method* is usually employed using Fogarty's catheter. Good back bleed signifies completeness of embolectomy.
- *Open arteriotomy method* is done directly over the artery followed by suturing the artery.

Note:

- *Intraoperative arteriogram* is a must to confirm the adequacy of blood flow and completion.
- *Intraoperative thrombolysis* as an adjunct to save the limb using urokinase 2,50,000 IU for minutes into distal artery may be beneficial.
- *Prophylactic fasciotomy* is needed in delayed cases to prevent reperfusion injury.
- *Postoperative systemic heparin* and later oral anticoagulant is given.
- *Treatment* for atrial fibrillation, atherosclerotic stenosis and other causes is needed.

Complications

- Bleeding
- Sepsis
- Thrombosis
- Narrowing
- Incomplete removal



Figs 1.376A and B: Fogarty's catheter. It is 80 cm in length with 4 to 7 French size. It is used for embolectomy. Note the inflated balloon at the tip.

After Embolectomy

Patient is placed in ICU care.
Monitoring with—PTT, thromboplastin time.

FAT EMBOLISM

It is commonly seen after *fracture femur, tibia,* or *multiple fractures* and occasionally following electroconvulsive therapy, usually occurs in 72 hours.

It is due to aggregation of chylomicrons, derived from bone marrow, causing fat embolism.

It is often a fatal condition.

Clinical Features

- *Cerebral*: Drowsy, restlessness, disoriented, constricted pupils, pyrexia, coma.
- *Pulmonary:* Cyanosis, tachypnoea, right heart failure, froth in mouth and nostrils, fat droplets in sputum, eventually respiratory failure.
- *Cutaneous*: Petechial haemorrhages in the skin.
- *Retinal artery emboli* is the earliest sign to appear, causing *striae haemorrhages, fluffy exudates* confirmed on fundoscopic examination.
- *Kidney*: Blockage in renal arterioles results in fat droplets in urine.

Treatment

- Oxygen.
- Heparinisation.
- Low molecular weight dextran.
- Ventilator support and ICU management.

AIR EMBOLISM

Causes

- Through venous access like IV cannula, most common cause.
- During artificial pneumothorax.
- During surgeries of neck and axilla.
- Traumatic opening of major veins sucking air inside, causing embolism.
- During fallopian tube insufflation.
- During illegal abortion.
    - Amount of air required to cause air embolism is 15 ml.
    - When the air enters the right atrium, it gets churned up forming a foam which enters the right ventricle and blocks the pulmonary artery.
    - ***Mill-Wheel murmur*** heard over the precordium through a stethoscope is diagnostic.
    - During open heart surgery/therapeutic pneumothorax, by accidental pulmonary vein puncture or in atrial septal defect (ASD) air may enter left side of the heart (*paradoxical air embolism*) causing coronary block or cerebral air embolism.
    - Through paravertebral veins also air embolism to brain can occur.

Treatment

Patient is placed in Trendelenburg left side up position. By passing a needle, the air has to be aspirated from the right ventricle. Often requires life-saving open thoracotomy to aspirate the excess air causing the block.

THERAPEUTIC EMBOLISATION

Indications

- Haemangiomas.
- AV fistulas.
- Malignancies like renal cell carcinoma, hepatoma.
- Cerebrovascular problems.
- To arrest haemorrhage from GIT, urinary and respiratory tract.
    - In bleeding duodenal ulcer or gastric ulcer, embolisation is done to occlude gastroduodenal artery or left gastric artery respectively.
    - It is also useful in bleeding oesophageal varices, secondaries in liver (mainly due to carcinoids), hepatoma.

When you cease to dream, you cease to live.

Materials used for therapeutic embolisation

- Blood clot
- Gel foam
- Balloons
- Quick setting plastics
- Stainless steel coils
- Human dura
- Plastic microspheres
- Ethyl alcohol
- Wool

CAISSON'S DISEASE OR DECOMPRESSION DISEASE

It occurs due to rapid decompression from high altitude, aircraft, compressed air chambers, deep sea divers causing bubbling of nitrogen which blocks the small vessels.

- In joints and muscles it causes excruciating pain *(bends).*
- Spinal cord ischaemia causing neurological deficits.
- Lungs may be affected causing choking with chest pain, tightness and dry cough.

Treatment

- Oxygen therapy.
- Recompression and gradual decompression in special chamber.

ANEURYSM

> *There is no disease more conducive to clinical humility than aneurysm of the aorta.*
>
> —**William Osler,** Circa 1900

It is an abnormal permanent dilatation of localised segment of arterial system. Diameter will be *50% more* than expected normal diameter of that artery in aneurysm. Atherosclerosis which is the most common (90%) facilitating cause of aneurysm is due to destruction and *loss of stability* of tunica media.

True aneurysm contains all three layers of artery.

False aneurysm contains single layer of fibrous tissue as wall of the sac and it usually occurs after trauma.

Types

- *Fusiform*—uniform dilatation of entire circumference of arterial wall
- *Saccular*—dilatation of part of circumference of the arterial wall
- *Dissecting*—through a tear in the intima blood dissects between inner and outer part of tunica media of the artery



Fig. 1.377: True and false aneurysms. In true type, all layers are intact. In false type all layers breached with haematoma having a false capsule.



Fig. 1.378: Fusiform and saccular types of aneurysms.



Fig. 1.379: Thoracic aortic aneurysm.

Causes

- ***Acquired:***
  - *Degenerative:* Atherosclerosis (*most common cause*); mucoid degeneration of intima and media (in South African young Negroes).
  - *Traumatic*: Direct; indirect like in post-stenotic dilatation by cervical rib; traumatic AV aneurysmal sac; aneurysm due to irradiation (due to dryness and destruction of vasa vasorum causing weakening).
  - *Infective*: Syphilis; mycotic; tuberculosis (in lung); arteritis; acute sepsis.
  - *Collagen diseases* like Marfan's syndrome, polyarteritis nodosa, Ehler-Danos syndrome.
- ***Congenital:***
  - Berry aneurysm; cirsoid aneurysm; congenital AV fistula**.**

Sites

- Aorta.
- Femoral.
- Popliteal.
- Subclavian.
- Cerebral, mesenteric, renal, splenic arteries.

The most common is *true, fusiform, atherosclerotic, aortic aneurysms.*

Berry aneurysms are multiple aneurysms occurring in circle of Willis.

Effects and complications of aneurysm

- Thrombosis and distal ischaemia
- Release of emboli causing acute arterial occlusion
- Pressure effects on bone (erosion); skin; veins (oedema); nerves (pain, paraesthesia); stomach (erosion—haematemesis); oesophagus (dysphagia)
- Rupture
- Infection of aneurysm

Clinical Features of Aneurysms

- Swelling at the site which is *pulsatile (expansile*), smooth, soft, warm, compressible, with thrill on palpation and bruit on auscultation. Swelling reduces in size when pressed proximally.
- Distal oedema due to venous compression.
- Altered sensation due to compression of nerves.
- Erosion into bones, joints, trachea or oesophagus.
- Aneurysm with thrombosis can throw an embolus causing gangrene of toes, digits, extending often proximally also.

Differential Diagnosis

- Pyogenic abscess: Abscess has to be always confirmed by aspiration; especially in axilla, popliteal region, groin.
- Vascular tumours.
- Pulsating tumours: Sarcomas, pulsating secondaries.
- Pseudocyst of pancreas mimics aortic aneurysm.
- AV fistula.

Investigations

- Doppler study, duplex scan, angiogram, DSA.
- Tests relevant for the cause, like blood sugar, lipid profile, echocardiography.

Treatment



Matas aneurysmorrhaphy for saccular aneurysm

Excision and graft in fusiform aneurysm (dacron graft)



Ligation and exclusion using autologous vein by-pass graft

Excision of aneurysm and by-pass using autologous vein graft

Figs 1.380A to D: Different methods of aneurysm repair. (A) Matas aneurysmorrhaphy for saccular aneurysm. (B) Excision and Dacron grafting. (C) Ligation and exclusion of the aneurysm using autologous vein graft. (D) Excision of aneurysm and bypass using autologous vein graft.

- Reconstruction of artery using arterial grafts.
- Arterial endoaneurysmorrhaphy—MATAS. It is done usually for peripheral saccular aneurysm. Matas aneurysmorrhaphy may be restorative or endo-obliterative or reconstructive.
- Therapeutic embolisation.
- Clipping the vessel under guidance (e.g. cranial aneurysms).
- Older methods which are now not used but popular earlier were—wiring of the aneurysmal sac/wrapping of the aneurysmal sac/ligatures at different levels (ligation just proximal to aneurysmal sac—*Anel's;* ligation proximally proximal to an arterial branch—*Hunter's;* ligation just distal to aneurysmal sac—*Brasdor's*; ligation distally distal to an arterial branch—*Wardrop's*; ligature one proximal and another distal to aneurysmal sac—*Antylus'*).

MYCOTIC ANEURYSM

- It is a ***misnomer***.
- It is not due to fungus but due to bacterial infection.
- Common bacteria are gram-positive organisms *like Staphylococcus aureus (most common)* and *Streptococcus.*
- Common aetiology is bacterial *endocarditis* but could be any infective site.
- Common vessels involved are aorta, visceral, head and neck and intracranial.
- Commonly it is saccular, multilobed, with a narrow neck.
- Patient presents with fever, toxaemia and tender pulsatile mass if it is in the periphery.

Investigations

- Leucocytosis. Positive blood culture, MR or CT angiogram are relevant.

Treatment

- Broad spectrum antibiotics
- Resection of aneurysm; debridement and drainage of the infected aneurysm with adequate blood transfusions.
- Extra-anatomic bypass through uninfected tissue planes to avoid contamination of the graft.
- Long-term antibiotic therapy is necessary.
- It has got 25% mortality.

Note:

Microbial arteritis with aneurysm is a different entity is due to bacteraemia occurring in an atherosclerotic vessel due to *Salmonella* infection).

ABDOMINAL ANEURYSM

- Abdominal aortic aneurysm is the *most common* aortic aneurysm.
- Splenic artery aneurysm is the *2nd most common* type.
- Incidence is 2%. It is more common in males.
- Transverse diameter of aorta in an aneurysm should be 3 cm or more.

Today's impossibilities are tomorrow's miracle.

- Common in elderly; common in males (4:1); chance of getting aneurysm in genetically related first degree relatives is 10 times more.
- Common in smokers (8:1with nonsmokers); in 55% of patients *Chlamydia pneumoniae* is identified.

***Note*:**
Smoking is an important factor.

ABDOMINAL AORTIC ANEURYSM



Figs 1.381A and B: Abdominal aortic aneurysm (A). Thrombosis of the aneurysm (B).

Causes

- *Atherosclerosis* (as degenerative process) is the *most common facilitating* cause (95%)—aortic wall contains smooth muscle cell matrix, elastin, collagen; *elastin* (in tunica media) is the main load bearing part with *collagen* (in adventitia) as safe net in the wall to provide tensile strength preventing aneurysm formation. *Elastin in medial layer* of aorta is *degraded* and reduced significantly in infrarenal aorta in relation to collagen, absence or less vasa vasorum in infrarenal aorta and atherosclerotic unstability of the medial wall of aorta cause infrarenal aorta more prone to develop aneurysm. Increased proteolytic activity of aortic medial wall due to increased *matrix metallo proteinases* (MMP) (derived from aortic smooth muscle cells and macrophages) cause elastin and collagen degradation and increase in diameter of aneurysm. *Collagen degradation in adventitia* causes rupture.
- *Familial* aortic aneurysm (associated with 25% of AAA) is more prevalent in females to reduce male to female ratio to 2:1. It is related to decrease in type III collagen, α1 antitrypsin and lysyl oxidase. Marfan's, Ehler Danlos syndromes are related genetically.
- Others: Syphilis, dissection, trauma, collagen diseases, infection, arteritis, cystic medial necrosis, association with *Chlamydia pneumoniae* (55%).

Classification I

- Infrarenal—most common 95%.
- Suprarenal—5%. Isolated suprarenal type is rare; it is usually associated with thoracic and or infrarenal types.

Classification II

- Asymptomatic.
- Symptomatic.
- Symptomatic ruptured.

Asymptomatic Type

- It is found incidentally either on clinical examination or on angiography or on ultrasound.
- Repair is required if diameter is over 5.5 cm on ultra sound.
- It is identified during routine abdominal palpation or while assessing or operating for some other abdominal conditions.

Symptomatic without Rupture **(Clinical features/ presentations)**

- It presents as *back pain, abdominal pain, mass abdomen* which is smooth, soft, nonmobile, not moving with respiration, vertically placed above the umbilical level, pulsatile both in supine as well as knee-elbow position with same intensity, resonant on percussion.
- Common in males (4:1); common in smokers.
- GIT, urinary, venous symptoms can also occur.
- Hypertension, diabetes, cardiac problems should be looked for and dealt with.
- In infrarenal type upper border is clearly felt.
- Lower limb ischaemia and embolic episodes can occur.
- 5% present as *inflammatory aneurysm* adherent to ureters, left renal vein, inferior vena cava and duodenum. Expanding aneurysm blocks lymphatics causing inflammation and fibrosis; or it may be due to infection and fibrosis of earlier localised ruptured abdominal aortic aneurysm. Such chronically inflamed aneurysm will not rupture further; but it is always symptomatic with fever and severe pain in abdomen and back. It needs surgical repair through retroperitoneal approach.



Fig. 1.382: CT scan picture showing right arch aorta (anomaly) with thrombosed aneurysm.



Fig. 1.383: Chest X-ray showing aortic aneurysm.

- *Aortocaval fistula,* presents as high output cardiac failure with continuous bruit in abdomen and severe lower limb ischaemia (*steal phenomenon*).
- *Aortoenteric fistula* is due to erosion of aneurysm into 4th part of duodenum presenting as GI bleed, malaena, shock. It is treated by duodenal closure, aortic ligation, aneurysmal exclusion with extra-anatomic bypass graft with gastrojejunostomy. Contamination is the major threat here.
- Being a retroperitoneal mass *back pain is common*—may be due to retroperitoneal stretching, nerve irritation or vertebral erosion.
- Aneurysm in a patient with horseshoe kidney which is anterior to aorta is difficult to manage. Left retroperitoneal approach is needed. EVAR is not possible.

Investigations

- Blood urea, serum creatinine.
- U/S (*most widely used* noninvasive test; but neck of the aneurysm, dimensions and relation to renal arteries are difficult to assess), aortogram, DSA, CT scan (*most precise*). *U/S is an effective screening tool*. Screening is done in cardiovascular patients in men (60-85 years), in women (60-85 years); men and women above 50 years with family history; annually in asymptomatic AAA with 4.0-4.5 cm size, with size > 4.5 cm once in every 6 months.
- CT angiogram, MR angiogram.
- Blood sugar, lipid profile, other relevant investigations like ECG, echocardiography, cardiac and pulmonary assessment.

Note:
X-ray will show *eggshell* calcification. CT scan is *more reliable and precise* investigation of choice—gives better information regarding extent on sides/neck, size, dimensions, size and site of the thrombus, calcification, relation of renal arteries, inflammation and fibrosis and adjacent tissues. MRI may be better only in renal failure patients.

Complications of abdominal aortic aneurysm

- Rupture, infection
- Thrombosis, embolism
- Distal ischaemia/gangrene
- Aortocaval fistula formation
- Aortoenteric fistula
- Erosion of vertebra
- Spinal cord ischaemia when thrombosis develops

Differential Diagnosis

- Retroperitoneal mass, pseudocyst of pancreas, retroperitoneal cyst mimic abdominal aortic aneurysm especially when it is thrombosed.
- Mesenteric ischaemia, acute pancreatitis, perforated duodenal ulcer may mimic ruptured aneurysm.
- Other conditions causing back pain like disc prolapse, sciatica.

Treatment

Conservative/Medical Treatment

- It is done in *low-risk* abdominal aortic aneurysm (age below 70 years; active physically without cardiac, respiratory, renal impairment and noninflammatory aneurysm); if aneurysm size is < 5 cm; if growth rate is < 0.5 cm/year.
- It includes risk factor modifications; stopping smoking; control of blood pressure (propranolol), cholesterol; usage of drugs—alpha blockers, elastase inhibitors (NSAID—indomethacin), matrix metalloproteinases (MMP) inhibitor (doxycycline).

- Periodic size measurement of an aneurysm using ultrasound once in 6 months to find out growth rate is essential during conservative treatment.

Surgical Treatment

- ***Indications for surgery***
  - Asymptomatic aneurysm more than 5.5 cm.
  - Growth rate more than 0.5 cm/year.
  - Painful, tender aneurysm.
  - Thrombosed aneurysm, aneurysm with distal emboli.

Low-risk abdominal aortic aneurysm—age below 70 years; active physically without cardiac, respiratory, renal impairment and noninflammatory aneurysm. Here surgical mortality is < 3%.

Intermediate risk—sedentary; stable coronary disease; mild COPD; creatinine 2-3 mg%; inflammatory/suprarenal aneurysm. Here surgical mortality is 3-7%.

High-risk—restricted daily works; significant coronary disease; dyspneic COPD; creatinine > 3 mg%; liver failure status. Here surgical mortality is > 10%.

- ***Open surgical repair***
  - It is called as *endo-aneurysmorrhaphy with intraluminal graft placement* (Crawford, 1960). It is done under GA with epidural support. Major challenges during anaesthesia are—blood loss, haemodynamic control, problems during clamping and declamping of aorta, temperature control, renal hypoperfusion, left ventricular strain.
  - Incision is commonly lengthy midline *transperitoneal* or supraumbilical transverse. *Retroperitoneal appro*ach is used in horseshoe kidney, abdominal wall stoma, inflammatory aneurysm, suprarenal extension, peritoneal dialysis, hostile abdomen. Retroperitoneal approach favors rapid control of proximal aorta but prevents visualisation of abdomen.
  - After laparotomy, duodenum and small bowel are retracted laterally and above; left renal vein which is in front of aorta is dissected and retracted; occasionally it may require to be ligated and it is safer provided left gonadal and left suprarenal veins are intact. Distal arterial clamps are applied first along common or external and internal iliac arteries on both sides. Proximal aortic clamp is applied at infrarenal level. Aorta is opened longitudinally midline towards right to avoid injury to orifice of inferior mesenteric artery. Atheroma, thrombus is removed until adequate backbleeding occurs. Lumbar vessels are ligated from the luminal side. Knitted Dacron graft after preclotting or woven Dacron graft or ePTFE tube graft is used. Graft is anastomosed above and below using polypropylene sutures (4 zero). Inferior mesenteric artery can be reimplanted. Clamps are released first below. Colonic and limb perfusion is checked for adequacy. Graft is covered with aneurysmal sac.
  - *Minimal incision aortic surgery (MIAS)* is done in thin individual with midline abdominal incision 12 cm in length with its 9 cm part above the umbilicus. Specialised retractors and vascular clamps are used for this. Advantages are less postoperative pain, ileus and incisional hernia.



Aorto bifemoral dacron graft (Woven) with right femoral exposed



Graft in place in retroperitoneum

Figs 1.384A to C: Abdominal aortic aneurysm with aortofemoral graft placement (Courtesy: Dr Ashok Shetty, mch, Cardiothoracic Surgeon, Mangalore).

- ***Endovascular aneurysm repair (EVAR)***
  - In 1991 Juan *Parodi* and Julio Palmaz first did EVAR. It is less invasive, less morbid with less mortality rate and shorter hospital stay. It is basically aneurysm exclusion method. It is useful in old age and patients who are not fit for surgery. EVAR is basically a prophylactic procedure. EVAR is indicated if aneurysm is less than 5.5 cm in men and less than 5.0 cm in women. It is usually done in patients after 65 years.

- It is endoluminal stent graft placement into the aneurysmal segment of aorta using interventional radiology with Seldinger's technique approach through femoral artery.
- Dacron or ePTFE with integral metallic stent for support and firm attachment is used as stent/endovascular prosthesis.
- One aortic and iliac (of one/same side) stent is commonly used together which is passed through same side common femoral. Other iliac is maintained with a separate stent approached through opposite common femoral.
- Procedure can cause endoleak, thrombosis, embolism, malposition/displacement of stent, sigmoid ischaemia, renal failure, failure of stent function causing recurrence and infection.

Symptomatic Ruptured Aortic Aneurysm

- Risk of rupture is 1%, if diameter is within 5.5 cm in size. Risk increases to 20% once the diameter = 7 cm.

It may be *anterior rupture* (20%) into the free peritoneal cavity causing severe shock and *death* very early; or *posterior rupture* (80%) with formation of *retroperitoneal haematoma* of large size causing severe back pain, hypotension, shock, absence of femoral pulses and with a palpable mass in the abdomen.

- **Management of Ruptured Aortic Aneurysm**
  - Immediate diagnosis by ultrasound.
  - Resuscitation.
  - Massive blood transfusions (10-15 bottles).
  - Emergency surgery is the only life-saving procedure in these cases.

Patient has to be shifted to the operation theatre. Abdomen is opened. *Vascular clamps* or *bull dog* clamps are applied to the aorta above and below the aneurysm. Adventitia is opened and the clot is removed. Aneurysm is excised and the *arterial graft* either *PTFE (Polytetrafluoroethylene), knitted dacron graft,* or *woven dacron graft* is placed. The graft is sutured to the vessel above and below using monofilament, nonabsorbable suture material, polypropylene 5-zero.

Complications of surgery

- *MI* is the most common cardiac complication in perioperative and in first 2 days of postoperative period
- Haemorrhage and haemodynamic complications
- Renal failure—is most common noncardiac complication
- Colonic ischaemia—10% due to poor IMA circulation
- Sexual dysfunction
- Aortoduodenal fistula
- Aortovenacaval fistula
- Spinal cord ischaemia—paraplegia
- Paralytic ileus
- Distal thromboembolism—blue toe syndrome
- DVT
- Graft leak, graft thrombosis, graft failure
- Anastomotic disruption, pseudoaneurysm formation
- Prosthetic infection/migration



- Ipsilateral aortic and iliac single unit modulus is passed through same side CFA.
- Opposite side (contralateral side) branch CIA graft is deployed through superstiff guide wire.
- Through opposite CFA.

Completion of procedure with graft in place. Arteriotomy is closed and skin incision is closed.

Figs 1.385A and B: Endovascular aneurysm repair (EVAR). Aortic and one side iliac stent is used as one unit modulus which is passed through same side common femoral artery; opposite side iliac part is inserted as separate modulus through opposite CFA.



Fig. 1.386: *Infrarenal aortic aneurysm repair*. It is the most common site of aortic aneurysm. Adventitia of aorta is opened; aneurysm is excised; graft is sutured above and below; adventitia is wrapped around.

Remember

- Pulsation of an aneurysm is expansile. Pulsation may be absent if it is thrombosed
- Abdominal aneurysm of any size which is painful or tender should be operated
- Abdominal aortic aneurysm of any size causing embolus should be operated
- Abdominal aortic aneurysm more than 5.5 cm should be operated
- In ruptured abdominal aortic aneurysm emergency surgery is the only choice operation with rapid resuscitation; immediate opening and repair using graft. Systolic pressure in this patient should be just adequate to maintain the cardiac function but should not be more than 100 mmHg as it will cause more bleeding
- Anterior rupture is more dangerous than posterior rupture
- Endoluminal stenting is becoming popular

PERIPHERAL ANEURYSM

- *Peripheral aneurysms* are less common compared to aneurysms in the cavity. Such surface aneurysms are easily visible and better amenable for clinical examination. But same time it may be mistaken for abscess and inadvertent wrong attempt of incision and drainage can occur leading to disastrous consequences.
- Popliteal type is the *most common* one. Brachial, radial, femoral and axillary are other rarer sites. *Expansile pulsation* which is confirmed using two finger placement with thrill and bruit is typical. Infection, thrombosis make it less pulsatile mimicking an abscess.
- Erosion into adjacent bone and skin, rupture are known to occur. Distal emboli may lead into digital gangrene.
- Pressure on the affected artery proximally reduces the size, and eliminates the thrill/bruit; pressure distal to aneurysm increases the prominence of the aneurysm swelling with bounding pulsation.
- X ray, arterial Doppler, angiogram, echocardiogram are needed.
- *Treatment* is open repair using arterial graft or endovascular stenting.

Popliteal Aneurysm

- Is most common (70%).
- 65% are bilateral.
- 25% cases are associated with abdominal aortic aneurysm.
- 75% cause complications in 5 years.



Fig. 1.387: Femoral artery aneurysm with impending rupture—needs emergency surgical intervention. It is rare type.



Fig. 1.388: Popliteal aneurysm about to rupture. It is the most common peripheral aneurysm.



Fig. 1.389: Radial artery aneurysm.

Presentations

- Swelling in popliteal region which is smooth, soft, pulsatile, well-localised, warm, compressible, often with thrill and bruit. *It may mimic a pyogenic abscess*.
- Thrombosis and emboli from popliteal aneurysm can cause distal gangrene which may spread proximally and may lead to amputation.
- Rupture may cause torrential haemorrhage.

Investigations

- Duplex scan, Angiogram.
- CT scan, MRI.

Treatment

- Aneurysmorrhaphy.
- Repair with arterial graft using PTFE, Dacron.
- Endoluminal stenting.

CAROTID ARTERY ANEURYSM (EXTRACRANIAL)

Incidence is less than 4% of peripheral aneurysms.
Most common site: Common carotid artery bulb, often extends into the internal carotid artery.



Fig. 1.390: Carotid aneurysm.

Causes

- Atherosclerosis, trauma.
- Syphilis, Marfan's syndrome.
- Ehler-Danlos syndrome.
- Congenital.

Clinical Features

- 10% bilateral.
- Swelling in the neck at the level of the thyroid cartilage, below the angle of mandible.
- Pulsatile (expansile pulsation).
- Smooth, soft, nontender, horizontally mobile.
- Bruit felt.
- Neurological features due to embolic episodes (50%).
- Hoarseness of voice.
- Horner's syndrome.
- Dysphagia.
- Swelling extending into the tonsillar bed.



Figs 1.391A and B: Basilar artery aneurysm—angiogram (*Courtesty:* Dr Muralidhar Pai, MCh, Mangalore).

Differential Diagnosis

- Carotid body tumour.
- Neurofibroma arising from the vagus.
- Abscess in neck.

Complications

- Rupture.
- Thrombosis.
- Hemiplegia.

Investigations

- Doppler of neck, carotid angiogram.
- DSA, CT scan.

Treatment

- Reconstruction of the artery using vascular graft.
- Ligation of the bulb as a life-saving procedure, but results in hemiplegia.
- Intravascular stents.

DISSECTING ANEURYSM

It is a misnomer. It is not an aneurysm, only an aortic dissection.

It is the dissection of media of the aorta after splitting through intima creating a channel in the *media* of the vessel wall.

Causes

- Hypertension (It is associated in 80% of dissecting aneurysms).
- Cystic medial necrosis.
- Marfan's syndrome and collagen diseases.
- Trauma.
- Weakening of the elastic layers of the media due to shear forces.

Today well lived makes every yesterday, a dream of happiness and tomorrow, a vision of hope.

Features

- It is always seen in thoracic aorta, common in ascending aorta (70%).
- It is uncommon in other parts of aorta or other vessels.
- It can occur in aortic arch or thoracic descending aorta.
- This dissected aortic channel gets lined by endothelium, often reopens distally into the aorta causing *double-barrelled aorta* which, in fact, prevents complications.
- It is commonly associated with aortic insufficiency. Atherosclerosis is *not a usual cause* for dissecting aneurysm.

I. Classification (DeBakey's)

- *Type I:* Dissection begins in ascending aorta extends into descending thoracic aorta (70%)
- *Type II:* Dissection originates in ascending aorta and extends only up to the origin of the major vessels. It is safer type with less complications
- *Type III*: Dissection begins in the descending thoracic aorta beyond the origin of the left subclavian artery

II. Stanford classification

- Proximal—includes DeBakey's Type I and II
- Distal—includes DeBakey's Type III

III. Dissecting aneurysm can be:

- Acute
- Chronic
- Healed dissecting aneurysm which communicates distally again to aorta as double barrelled aorta



Fig. 1.392: Dissecting aneurysm.

Complications

- *Acute:* Rupture into the pericardium or pleura—*dangerous* type
- *Chronic:* Blockage of coronary vessels and major vessels like carotid and subclavian arteries with aortic insufficiency

Clinical Features

- Pain in the chest, back which is excruciating.
- Features of ischaemia due to blockage of different vessels.

Investigations

- Chest X-ray shows mediastinal widening
- Arterial Doppler
- Angiogram

Treatment

Antihypertensives.

Surgery: Using Dacron graft reconstruction of aorta has to be done with cardiopulmonary bypass.

Indications for surgery

- Progressive disease
- Significant ischaemia
- Impending rupture
- Type A aortic dissection

ERYTHROMELALGIA/ERYTHRALGIA

- It is severe burning pain and redness in the feet. Sensation of heat is so severe that patient keeps the feet in cold water to reduce it.
- It presents as episodic attack.
- There will be flushing in feet; prominent veins; warmness in the skin; severe hyperaesthesia is typical; even touching can be painful.
- It can be primary or secondary. *Secondary* is which is not uncommon is observed in arterial obliterative conditions, erythrocyanosis frigida, polycythaemia, gout and frostbite. *Primary* is due to unknown etiology; it is very rare.
- Vasodilators and sympathectomy may be beneficial.

LIVEDO RETICULARIS

It is a condition often associated with Systemic lupus erythematosus presenting as features of *arteriolar spasm and dilatation of venules* which is worsened by cold.

POLYARTERITIS NODOSA

- It is a necrotising inflammatory reaction with commonly microscopic polyarteritis and nodule formation, often of small and medium sized arteries (not capillaries), causing ischaemia of lower and upper limb.
- Visceral arterial (mesenteric) involvement (70%) can cause abdominal pain, GI bleed; mucosal ulceration and perforation of small bowel. Massive hepatic infarction, cholecystitis can develop.
- Renal artery can cause loin pain, haematuria, and renal hypertension.
- Coronary artery also can get involved causing myocardial infarction.
- Disease is common at bifurcation of medium/small sized arteries leading to localised aneurysms.
- It is common in males (3:1); fever, weakness, myalgia, arthralgia are early features.
- Presents with localised small aneurysms, like multiple 5-10 mm nodules, palpable along the course of the artery.
- In late stage presents with myocardial infarction, renal failure, sepsis, GI bled.
- HBsAg is positive in 40% patients of polyarteritis nodosa.

- Angiogram of renal, mesenteric, peripheral arteries will show aneurysms at branching points.
- Biopsy of tender nodule, tender muscle is useful for diagnosis.
- Treatment is prednisolone 60 mg daily with cytotoxic drugs.
- Prognosis is poor with rapid death in early years.

SCLERODERMA/SYSTEMIC SCLEROSIS

- It is *a progressive* disease causing fibrosis of skin, GI tract, lungs, heart and kidney.
- It is common in females (4:1) at 4th/5th decade.
- It is considered as vasculitis even though earlier considered as collagen disease.
- Pathology consists of cytotoxic endothelial injury causing interstitial oedema, severe fibroblast proliferation causing fibrosis of affected vessels, and dilatation and proliferation of remaining capillaries as telangiectasis.
- Thin epidermis, thick dermis with more collagen with absence of appendages and rete pegs are typical.
- Lower 2/3rd oesophagus is sclerosed (50%) with increased collagen in submucosa with atrophied mucosa and muscularis. Dysphagia is common.
- Diffuse interstitial fibrosis, thickening of alveolar membrane and pulmonary hypertension occurs.
- Synovial thickening causes arthritis; fibrosis of skeletal muscles; interstitial myocardial fibrosis causes bundle branch block, pericardial effusion.
- Glomerulosclerosis in kidney is common (50%). Renal failure is common.
- Fibrosis of thyroid, periodontal membrane can occur. Malabsorption syndrome is common due to small bowel involvement.
- Involvement of digital arteries present as Raynaud's phenomenon.
- Calcinosis, Raynaud's, oesophageal hypomotility, sclerodactyly, and telangiectasia are the presentation of CREST syndrome.
- ***Investigations***—anaemia, raised ESR, elevated IgG, presence of antinuclear antibodies and anticentromere antibodies (in CREST)—are different laboratory findings. Skin and peripheral arterial biopsy is confirmative.
- ***Treatment***—is difficult. Drugs like D pencillamine, colchicines, p amino benzoic acid, vitamin E, dimethyl sulfoxide, ranitidine are tried at various levels. Vasodilators, warming and massaging skin, avoiding detergent soaps, oil and hydrophilic ointment application are used.
  Steroids, oxygen therapy for irreversible pulmonary fibrosis; haemodialysis for renal failure; digitalis and other drugs for cardiac failure are needed later.
- Death is due to cardiac/pulmonary/renal failure.

ACROCYANOSIS (CRURUM PUELLARUM FRIGIDUM)

- It is persistent, painless cyanosis seen in fingers and often in legs with paraesthesia and chilblains affecting young females.
- It is chronic persistent arteriolar constriction with slow rate of blood flow.
- Trophic changes and ulcerations are not seen.
- Cyanosis *which is persisting* may aggravate on exposure to cold.
- It may be associated with endocrine dysfunction.

Treatment

- Vasodilators.
- Cervical sympathectomy (effective).

Raynaud's phenomenon	*Acrocyanosis*
• Episodic	• Persistent
• Painful	• Painless
• Acute arteriolar spasm	• Chronic constriction
• Ischaemic changes are common	• Ischaemic changes are not seen

GANGRENE

> *If the tips of (the patient's) fingers are falling off and are black, he will die.*
>
> —**(Anonymous),** circa 2000 BC

It is *macroscopic death* of tissue *in situ* (in continuity with adjacent viable tissue) with or without putrefaction.

It can occur in sites like:

- Limbs
- Appendix
- Bowel
- Testes
- Gallbladder

Causes

- Secondary to arterial occlusion like atherosclerosis, emboli, diabetes, TAO, Raynaud's disease, ergots.
- Infective: Boil, carbuncle, gas gangrene, Fournier's gangrene, cancrum oris.
- Traumatic: Direct, indirect.
- Physical: Burns, scalds, frostbite, chemicals, irradiation, electrical.
- Venous gangrene.

Clinical Features

- *Colour changes*: Pallor, greyish, purple, brownish black due to disintegration of haemoglobin to sulphide.
- *Absence of pulse*, loss of sensation, loss of function.
- *Line of demarcation* between viable and dead tissue by a band of hyperaemia and hyperaesthesia along with development of a layer of granulation tissue.

Differences between dry gangrene and wet gangrene

Dry gangrene	*Wet gangrene (Moist)*
Clear line of demarcation is seen	Line of demarcation is vague
Dry, shriveled, mummified	Oedmatous, putrified, discoloured (H_2S)
Slow, gradual loss of blood supply	Sudden loss of blood supply
Separation is by aseptic ulceration	Septic ulceration causes separation
Limits to the demarcation	Can extend proximally rapidly
Causes are atherosclerosis, TAO	Emboli, trauma are the causes
Limited amputation is sufficient	Major higher amputation is often needed



Figs 1.393A and B: Gangrene of foot and leg. Note the line of demarcation. But skip lesion proximally shown signifies more proximal spread of gangrene which may need above knee amputation.



Figs 1.394A and B: Gangrene of lower and upper limbs in two different patients.

In *dry gangrene* the separation occurs by aseptic ulceration with minimum infection and the gangrene is dry and mummified**.**

In *wet gangrene,* separation takes place by septic ulceration. Often demarcation is vague with *skip lesions* more proximally and so landing with higher level of amputations. Even after amputation skin flap may show *die back* process, leading to failure of taking up of flap of amputation and so requiring still higher level of amputation.

- *Proximal ischaemic features* may be present with rest pain, colour changes, hyperaesthesia—pregangrene.

Types of gangrene

- *Dry gangrene* is due to slow, gradual loss of blood supply to the part causing dry, desiccated, wrinkled, mummified part with proper line of demarcation from the viable adjacent tissues
- *Wet gangrene* is due to infection with putrefaction, causing oedematous, swollen, discoloured part, spreading proximally, with vague line of demarcation from the adjacent viable tissues

Investigations

- Hb%, blood sugar.
- Arterial Doppler, angiogram (Seldinger technique).
- U/S abdomen to find out the status of aorta.

Treatment

***Limb saving methods*:**

- Drugs: Antibiotics, vasodilators, pentoxiphylline, praxilene, dipyridamole, small dose of aspirin, ticlopidine.
- Care of feet and toes:
  - The part has to be kept dry.
  - Any injury has to be avoided.
  - Proper footwear is advised (Microcellular rubber footwear, MCR).
  - Measures for pain relief is taken.
  - Nutrition supplementation is done.
  - The limb should not be warmed.
  - Pressure areas has to be protected.
  - Localised pus has to be drained.
- Cause is treated.
- Diabetes is controlled.

- Surgeries to improve the limb perfusion: Lumbar sympathectomy, omentoplasty.

Profundaplasty, femoropopliteal thrombectomy or endarterectomy, arterial graft bypass are done according to the need.

Life-saving procedures: *Amputations may have to be done occasionally.*

Level of amputation is decided on skin changes, temperature, line of demarcation, Doppler study.

- *Below-knee amputation* is a better option as *BK prosthesis* can be fitted better and also the movements of knee joint are retained. There is no need of external support and limp is absent.
- In *above-knee amputation* range of movements are less, limp is present, and often requires third (stick) support to walk.

Different amputations done are *Ray amputation*, below-knee amputation *(Buerger's amputation)*, *Gritti-Stokes transgenial amputation*, above-knee amputation.

Lisfranc's, Chopart's, Symes', Modified Symes' amputations are not commonly used in ischaemic limb as flaps will not survive.

DIABETIC FOOT AND DIABETIC GANGRENE

Foot is a complex structure with many layers of muscles, ligaments, joints, arches, fat, thick plantar fascia, vascular arches, neurological system which maintains weight-bearing, gravity, normal walk, stability and gait (swing and stance phases).

Problems in diabetic foot

- Callosities, ulceration
- Abscess and cellulitis of foot
- Osteomyelitis of different bones of foot like metatarsals, cuneiforms, calcaneum
- Diabetic gangrene
- Arthritis of the joints

Meggitt's classification of diabetic foot

- Grade 0: Foot symptoms like pain, only
- Grade 1: Superficial ulcers
- Grade 2: Deep ulcers
- Grade 3: Ulcer with bone involvement
- Grade 4: Forefoot gangrene
- Grade 5: Full foot gangrene

Pathogenesis of Diabetic Foot/Gangrene

- High glucose level in tissues is a good culture media for bacteria. So infection is common.
- *Diabetic microangiopathy* causes blockade of microcirculation leading to hypoxia.
- *Diabetic neuropathy*: Due to sensory neuropathy, minor injuries are not noticed and so infection occurs. Due to motor neuropathy, dysfunction of muscles, arches of foot and joints occurs. And loss of reflexes of foot occurs causing more prone for trauma and abscess. Due to autonomic neuropathy, skin will be dry, causing defective skin barrier and so more prone for infection.



Fig. 1.395: Diabetic with extensive sepsis and gangrene. It requires amputation.

- *Diabetic atherosclerosis* itself reduces the blood supply and causes gangrene. Thrombosis can be precipitated by infection causing infective gangrene. Blockage occurs at plantar, tibial, and dorsalis pedis vessels.
- *Increased glycosylated haemoglobin* in blood causes defective oxygen dissociation leading to more hypoxia. At tissue level there will be increased glycosylated tissue proteins, which prevents proper oxygen utilisation and so aggravates hypoxia.

Clinical Features

- Pain in the foot.
- Ulceration.
- Absence of sensation.
- Absence of pulsations in the foot (Posterior tibial and dorsalis pedis arteries).
- Loss of joint movements.
- Abscess formation.
- Change in temperature and colour when gangrene sets in.
- Patient may succumb to *keto acidosis, septicaemia or myocardial infarction*.

Investigations

- Blood sugar, urine ketone bodies.
- Blood urea and serum creatinine.
- X-ray of part to look for osteomyelitis.
- Pus for culture and sensitivity.
- Doppler study of lower limb to assess arterial patency.
- Angiogram to look for proximal blockage.
- Ultrasound of abdomen to see the status of abdominal aorta.
- Glycosylated haemoglobin estimation.

Treatment

- ***Foot can be saved only if there is good blood supply.***
  - Antibiotics—decided by *pus C/S*.
  - Regular dressing.
  - *Drugs:* Vasodilators, pentoxiphylline, dipyridamole, low dose aspirin.
  - Diabetes is controlled by *insulin only*.
  - Diet control, control of obesity.
  - Surgical debridement of wound.

He who attempts the absurd can achieve the impossible.



Figs 1.396A to C: Diabetic foot with ischaemic ulceration and gangrene. Note in one of the photos distal part of foot is gangrenous and proximal part is pregangrenous. This patient underwent above knee amputation.



Fig. 1.397: Gangrene of 3rd and 5th toes in a diabetic. Patient already underwent amputation of 4 the toe earlier for gangrene.

- Amputations of the gangrenous area. Level of amputation has to be decided by skin changes and temperature changes or Doppler study.
- Care of feet in diabetic:
  - Any injury has to be avoided.
  - MCR footwears must be used (Microcellular rubber).
  - Feet has to be kept clean and dry, especially the toes and clefts.
  - Hyperkeratosis has to be avoided.

TROPHIC ULCER

Aetiology

Diabetic neuropathy, spinal injury and diseases, other neuropathies.

Causes

- Pressure
- Anaemia
- Malnutrition
- Injury
- Moisture

Common Sites

Heel, heads of metatarsals, sacrum, ischium, occipital region. *Bedsore is a trophic ulcer*.

Clinical Features

They are deep, punched out, nonmobile ulcers, with bone as its base.

Investigations

X-ray spine, nerve conduction studies, blood sugar, Hb%.

Treatment

- Nutrition is improved.
- Anaemia is treated.
- Diabetes is controlled.
- Regular dressing is done.
- Pressure and injuries has to be avoided.

BEDSORES (Decubitus Ulcer) (Pressure Sores)

Bedsore is a *trophic ulcer* with bone as the base.
It is nonmobile, deep, punched out ulcer.

It is common in		
Old age Bedridden	Tetanus	Patients with orthopaedic
Diabetic Paraplegic	Comatose	and head injuries

Sites of bedsore are occiput, heel, sacrum, ischium, scapula.

Factors: Malnutrition, pressure, anaemia, sensory loss, moisture.

Treatment

- Change of positions is always encouraged.
- Use of water bed, ripple bed is advised.
- Moisture has to be avoided.
- Soaking by urine, sweat, pus, and faeces has to be taken care off.
- Good nursing, regular dressing, good nutrition are necessary.
- Antibiotics, blood transfusions are very essential.
- Excision of dead tissue followed by skin grafting or local rotation flaps may have to be done.
- Rehabilitation.

FROSTBITE

- It is due to exposure to cold wind or high altitude.
- It is common in old age during cold spells.
- Damage to vessel wall occurs causing oedema, blistering, gangrene formation.
- Part is painless and waxy.
- Cells get frozen at – 5°C. Initially redness and oedema (1st degree); blister formation (2nd degree); skin necrosis (3rd degree); gangrene (4th degree develops gradually.



Figs 1.398A and B: Large bedsore over the sacrum in a abedridden patient. Note the size and slough on the surface.

Treatment

- *Gradual warming is done*. Part should be wrapped with cottonwool and rested. Warming is gradually done with 44°C in 30 minutes with warm water. Limb elevation is done to reduce oedema. Intra-arterial vasodilators may help.
- Warm drinks, analgesics, paravertebral injections to sympathetic chain, *hyperbaric oxygen* are effective.
- If gangrene develops, amputation is needed.

AINHUM

- Commonly affects males (can also occur in females).
- Common in blacks, in Negroes.
- History of running barefoot in childhood is common.
- *Fifth toe* is commonly affected.
- A fissure develops at the interphalangeal joint which becomes a fibrous band, that encircles the digit causing necrosis (Gangrene of little toe).
- Often it can be bilateral.

Treatment: It is early "Z" plasty. Amputation is often required later. Most often autoamputation occurs.

***Note*:**
Yoruba people of Nigeria named *ainhum*.



Figs 1.399A and B: Typical Ainhum. Note it is bilateral. Note the constriction ring in the little toe.

ENDOVASCULAR SURGERIES

It is mainly used in peripheral vessels like femoropopliteal, renal, coronary, cerebral vessels.

Types

- *Balloon angioplasty:* It is useful in short segment stenosis in large vesles like renal vessels, iliofemoral, coronary vessels. It is less effective compared to open surgery.
- *Intravascular stenting:* Balloon expandable and self-expanding stents are used at stenosed area.
- *Endovascular grafts* (PTFE, DACRON).
- Endovascular atherectomy.
- *Angioscopy:* Flexible, small, fibreoptic scopes to visualise vessel wall with sufficient irrigation to avoid opacification by blood.
- *Intravascular ultrasound:* To evaluate the vessel wall morphology.

Indications

- Aneurysm for stenting and grafting
- Aortoiliac constrictive disease
- Renal artery stenosis
- Carotid occlusive disease
- AV fistulas
- Management of pseudoaneurysm

Complications

- Thrombosis.
- Rupture.
- Sepsis.
- Fluid overload.
- Air embolism.

UPPER LIMB ISCHAEMIA

It is a rare uncommon entity compared to lower limb ischaemia but important because of its difficulty in managing. *Higher-level amputations are rare in upper limb ischaemia.*

Its incidence is rare (5%) due to abundant collateral supply, infrequency of atherosclerosis, decreased metabolic demand and smaller muscle mass.

It mostly affects distal small arteries (90%).

Symptoms are usually delayed.

Types of Upper Limb Ischaemia

- Acute.
- Chronic.

Acute type

Causes:

- **Embolism—common.** 30% of the peripheral emboli lodge in upper extremity. The most common site is at the bifurcation of brachial artery (40%); next common is at axillary artery (12%). Embolism is due to:
    - Cardiac origin (70%)—valvular lesions (atrial fibrillation, endocarditis), IHD, paradoxical.
    - Others—aneurysms, *thoracic outlet syndrome*, plaque.
- **Trauma—most common.** Brachial artery injury is seen in 30% of civilian trauma with arterial injuries, blunt injuries, fractures and dislocations, penetrating injuries.
- Iatrogenic.
- Post AV fistula ‘Steal syndrome’.
- Aortic dissection.

Symptoms of acute ischaemia:

- Pain, pallor, poikilothermia, paraesthesia, paralysis.



Fig. 1.400: Upper limb ischaemia with gangrene extending proximally towards elbow joint.

Chronic Type

Causes:

- Arteritis—aortoarteritis, Takayasu arteritis, giant cell arteritis, connective tissue disease/vasculitis—scleroderma, SLE, RA, PAN, etc.
- Atherosclerosis—most common cause in USA.
- TAO of upper limb.
- Others—fibromuscular dysplasia; postirradiation—lung, breast; occupational injuries; vibration injury, hypothenar hammer syndrome; hypercoagulable states; APLA, polycythemia, cold agglutinins.

Symptoms of chronic ischaemia:

- Upper limb ‘Claudication’.
- Weakness and wasting.
- Digital ischaemia—ulcer, gangrene in finger tips.
- Raynaud’s phenomenon.

Signs of chronic ischaemia:

- Wasting of arm, forearm and hand muscles.
- Ischaemic changes in skin; tapering of finger tips.
- Drop in systolic pressure >20 mmHg.
- Proximal thrill or bruit.
- Mass in the neck, thrill and bruit in the neck in supraclavicular region.
- Adson test, hyperabduction (Halsted) test, Roos test, Allen`s tests are important.

Raynaud’s Phenomenon

- It is *episodic vasospasm*. It is common in upper limb.
- *Raynaud’s disease*: It is *primary* Raynaud’s phenomenon—no cause could be demonstrated (Idiopathic).
- *Raynaud’s syndrome*: It is *secondary* Raynaud’s phenomenon—secondary to a demonstrable lesion like SLE, scleroderma, TAO or atherosclerosis.
- *Symptoms*: Pain, discolouration, sensation of cold and numbness, pronounced on exposure to cold, and under stress.



Fig. 1.401: Left upper limb ischaemia with gangrene of three fingers and ischaemic changes in hand, forearm and arm.



Fig. 1.402: Gangrene of left index finger. Patient has undergone cervical sympathectomy.

- *Signs*: Cyclical colour changes—*Pallor*, *Cyanosis* and *Rubor* with swelling; seen in fingers, toes, nose, ear lobes and lips.
- *Pathology of Raynaud's phenomenon*: Exaggerated vasomotor response to stress; more common in females; no structural changes in the vessels, except in late stages; recurrent attacks can lead to atrophy of skin, subcutaneous tissue and muscles, ischaemic ulcers and gangrene.

Investigations in Upper Limb Ischaemia

- Lab tests for vasculitis, hypercoagulable states, and atherosclerotic risk factors.
- X-rays—for cervical rib; clavicular and first rib fractures; fractures and dislocations in extremity; pulmonary lesions of connective tissue disorders.
- Arterial Doppler study.
- Angiogram (Subclavian angiogram)—CT/MR; conventional.
- CT scan neck and thorax.
- Blood sugar, lipid profile, cardiac evaluation.



Fig. 1.403: Upper limb angiogram showing blocks in subclavian artery.

Management of Upper Limb Ischaemia

- Treatment of the cause.

Treatment of Embolus

- Time since the first symptom is very important.
- Clinical assessment of extent of ischaemia, immediate anticoagulation with heparin, Doppler study and angiogram of the arterial system, evaluation for the source of embolus—are the protocols.
- Embolectomy
  - *Brachial embolectomy*: Local/regional/general anaesthesia is used. Longitudinal incision in the arm is used for proximal embolus; Lazy S-shaped incision across the elbow is done for embolus extending into the bifurcation and to expose the branches.

Treatment in Trauma

- General evaluation and resuscitation.

We always have time enough, if we will use it in a right way.

- Control of bleeding in open wound: Pressure bandage/ manual compression (DO NOT USE TOURNIQUET).
- Time since the event and clinical assessment of limb perfusion.
- Stabilisation of fractures and dislocations
- Doppler study of arterial system, angiogram if required.
- Arterial repair; bypass graft either venous or synthetic.

Treatment of Chronic Ischaemia

- Medical management
  - Risk modification—diabetes, hypertension, dyslipidemia, smoking, homocystinaemia, exercise training.
  - Antiplatelets—aspirin/ticlopidine/clopidogrel.
  - Anticoagulants—heparin/warfarin.
  - Xanthines/pentoxiphylline/cilostazol.

  Cilostazol—suppresses cAMP phosphodiesterase III rise in cAMP levels with antiplatelet, antithrombotic effects; induces vasodilatation; increases plasma HDL cholesterol; decreases plasma triglycerides.
- Catheter based interventions
  - Atherectomy.
  - Angioplasty ± stenting by conventional or subintimal approach.
  - Stent grafts.
  - Cryoplasty.
- Surgery
  - Endarterectomy.
  - Bypass surgery.
  - Sympathectomy, extraperiosteal resection of the cervical rib.

Bypass Surgeries in Upper Limb Ischaemia

- Conventional bypass
  - Aorto-subclavian/axillary bypass.
  - Subclavian: Axillary/brachial bypass.
  - Brachiodistal bypass.
- Extra anatomical bypass
  - ***Carotid: Subclavian/Axillary bypass.***



Figs 1.404A to D



Fig. 1.404E

Figs 1.404A to E: Brachial embolectomy (upper limb)—open method.

- Subclavian: Subclavian bypass.
- Axillary: Axillary bypass.

- Subclavian Carotid transposition.

Treatment of Raynaud's Phenomenon

- Avoiding triggering agents
- Drugs (vasodilators)—calcium channel blockers, angiotensin II receptor blockers, alpha-1 adrenergic blockers, Sildenafil, prostaglandin E1.
- Surgery—sympathectomy.

Note:
Individual topics about causes of upper limb ischaemia are discussed in different places.

Upper limb ischaemia

- Trauma/cervical rib are the common causes
- Opposite limb, lower limbs should be examined
- Cardiovascular system should be examined
- Neck should be examined
- Wasting/girth should be checked
- All relevant clinical methods are equally significant
- Auscultation over neck/axilla/carotids for bruit are important
- Doppler; angiogram; nerve conduction studies; CT neck and thorax are essential investigations
- Arterial repair; therapy for cervical rib; scalenotomy; cervical sympathectomy are the different modalities of treatment
- Digital amputation may be required



Fig. 1.405: Carotid subclavian bypass.



Fig. 1.406: Subclavian carotid transposition.

You my say you KNOW, but by your actions it is KNOWN.

ARTERIAL SUBSTITUTES

Ideal arterial substitute is not yet developed. Ideal arterial substitute should be strong, durable for patient's life, biocompatible, nonthrombogenic, should be resistant for infection, easily available, should have a long-term patency rate, and should have elastic property of normal artery.

Features of ideal graft	
Strong	Should be leak proof on restoration of blood flow
Durable for patient's life	Should not chemically or physically degenerate
Non thrombogenic	Should not cause any abnormal reaction to surrounding tissues
Biocompatible	Should not occlude when flexed
Resistant to infection	Should not damage blood contents
Flexible	
Should maintain long-term patency	
Should have elastic property of normal artery	

Carrel and Guthrie first did venous autograft into arteries of dogs. They did extensive histological study of viable and nonviable grafts. Lexer in 1907 used saphenous vein for axillary artery repair. Murray started to use intraoperative heparin. Enaz Moniz and dos Santos originated technique of arteriography. Gross and his colleagues in 1948 started to use viable arterial allografts. Later it was found that, as of graft is considered tissue viability is not essential for success of graft uptake.

Classification of Arterial Substitutes

- Arterial allograft—not used.
- Arterial autograft—internal mammary artery (common), internal iliac artery.
- Arterial xenograft—bovine carotid artery graft—not used.
- Venous autograft—long saphenous vein (common), small saphenous vein, basilic vein, cephalic vein.
- Venous allograft—umbilical vein graft.
- Prosthetic grafts
  - Textile grafts
    - Dacron graft—knitted or woven or crimping or velour types.
    - Teflon graft—knitted or woven crimping or velour types.
  - Non textile semi-inert polymer graft:
    - ePTFE graft—expanded polytetrafluoroethylene graft.

Preclotting the ***noncoated knitted*** or woven Dacron graft is done to seal the graft and to prevent leak, and to create a smooth lining at graft—blood interface. This step is not necessary for PTFE or newer grafts.

Complications of Graft

- *Neointimal fibrous hyperplasia* at suture lines of the graft is due to surgical trauma, PDFG, arterial smooth muscle proliferation.
- *Graft infection*—incidence is 2%. It is more in lower limb graft than abdominal graft. Peroperative cephalosporin administration reduces the rate of graft infection. If infection occurs graft should be removed and revascularisation is achieved using a saphenous vein graft.
- *Graft failure* is rare but can occur. It is due to fiber degeneration, manufacturing defect, diffuse dilatation of graft (is due to expansion of the knit in knitted Dacron).
- *Anastomotic false aneurysm* (3%) occurs just adjacent to suture line towards host artery. It is tearing of the artery adjacent to suture line due to mismatched graft artery compliance, improper suture placement, and arterial degeneration. There will be partial or total separation of the graft from the host with blood collection in a covering of fibrous capsule. Eventually it will rupture/may cause thrombosis and embolism. Treatment is graft—artery reanastomosis with insertion of additional piece of graft.

M. Vascular Lesions and Hamartoma

CHAPTER OUTLINE

- Vascular Anomalies
- Haemangioma
- Vascular Malformations
- Cirsoid Aneurysm
- Arteriovenous Fistula
- Campbell De Morgan Spots
- Parry-Romberg Disease
- Hamartomata

VASCULAR ANOMALIES

- It is *a collective term* used for haemangioma and vascular malformations.
- *Haemangioma* is a benign tumour containing hyperplastic endothelium with cellular proliferation with increased mast cells. Growth in tissue culture is observed. It is absent at birth, seen by 1 month in 30%. It usually shows biphasic growth phase with slow involution. 95% of cases achieve spontaneous involution. Fast growing type can cause platelet trapping and thrombocytopenia. Associated skeletal changes are not common but can occur. But bone erosion by the lesion can occur. It is common in girls (3:1).
- *Vascular malformations* are single layer endothelium lined spaces derived from arterial, capillary, venous or lymphatic system. There is no growth in tissue culture. Raise in mast cells is not seen. 90% cases are seen at birth; only few at later period. It is equal in both sexes (1:1). Quiescent endothelium with vessels showing progressive ectasia is the feature. Intravascular coagulation and mild thrombocytopenia can develop. Skeletal changes and overgrowth are common. Spontaneous involution is not common.
- Disfigurement, tissue destruction, deformity, dysfunction, telangiectasia, skin scarring are common.
- *Szilagyi classification*—(1) Cavernous haemangioma; (2) Microfistulous AV communications; (3) Macrofistulous communications; (4) Anomalous mature vascular channels.
- *Humburg classification*—(1) Predominantly arterial/venous/lymphatic defects with aplasia or obstructive dilatation which is limited or infiltrative; (2) Predominantly AV shunting defects with deep/superficial limited or infiltrating lesions; (3) combined vascular defects—arterial, venous and haemolymphatic which may be limited or infiltrating.
- *Diagnosis* is made clinically and by radiological imaging—coloured Doppler, DSA, MRI. *MRI* is *better* than CT to identify the flow (MR angiogram is ideal). Haemangiomas show intense parenchymal staining; vascular malformations show ecstatic vessels without much parenchyma; AVM shows rapid venous shunting.

HAEMANGIOMA

- It is the most common tumour in children (in 10% of term deliveries).
- It shows cellular endothelial hyperplasia with increased mast cells.
- Onset is few weeks after birth with biphasic growth showing initial rapid growth with gradual involution over 5-7 years.
- It is benign vascular endothelial tumour, common in girls (3 : 1).
- It is commonly seen in skin and subcutaneous tissue but can occur anywhere in the body like in liver, brain, lungs or other organs.


Vascular anomalies
Haemangiomas
Multilayered
Mast cells
Vascular malformations
Single layer
No mast cells


Vascular anomalies
Arterial/venous proliferation/ lymphatic ectasia
AV shunting defects
Combined vascular defects
Aplasia/dilatation
Limited/infiltrative
Superficial/deep
Limited/infiltrative
Arterial + venous + lymphatic
Limited/infiltrative

You may be disappointed if you fail, you are doomed if you don't try.

- It grows rapidly in first year and 70% involutes in 7 years.
- Early proliferative lesion is bright red, irregular; deep lesion is bluish coloured. Involution causes colour fading, softness, shrinkage leaving crepe paper like area.
- Commonly it is central; common in head and neck region (60%).
- Often large haemangiomas may be associated with visceral anomalies. Head and neck haemangioma is associated with ocular and intracranial anomalies; sacral with spinal dysraphism. Multiple cutaneous haemangiomas may be associated with haemangioma of liver causing hepatomegaly, cardiac failure (CCF), anaemia.
- Ulceration, bleeding, airway block and visual disturbances are common complications.
- A definitive even though rare, but important life-threatening complication is platelet trapping and severe thrombocytopenia presenting as ecchymosis, petechiae, intracranial haemorrhage massive GI bleed.
- Raised angiogenic (fibroblastic) growth factor which is secreted in patient's urine is useful lab investigation to differentiate it from vascular malformations.

Classification

- *Capillary*
  - Salmon patch (stork bite)
  - Strawberry haemangioma
  - Port-wine stain (naevus flammeus)
- *Cavernous*

Capillary Haemangioma

- ***Salmon patch (stork bite):***
  - It presents at birth. It commonly occurs in nape of the neck (50%), face, scalp and limbs. It usually involves wide area of skin. It is caused by an area of persistent fetal dermal circulation. With age, it goes for spontaneous regression and disappears completely (usually in one year). Hence masterly inactivity is the treatment.
- ***Strawberry haemangioma:***
  - It may start at birth or child is normal at birth; between one to three weeks it appears as red mark which rapidly increases in size in 3 months to form strawberry/raspberry haemangioma. It contains immature vasoformative tissues. There will be eventually intravascular thrombosis, fibrosis and mast cell infiltration.



Fig. 1.407: Salmon patch.



Fig. 1.408: Strawberry haemangioma.

  - It is a *true capillary* haemangioma.
  - It is 20 times more common than port wine stain.
  - It is common in *white girls*. Male to female ratio is 1 : 3.
  - It is common in head and neck region.
  - It is clinically *compressible,* warm with bluish surface.
  - Bleeding can occur after minor trauma and also ulceration.
  - It involves skin, subcutaneous tissues and often muscles also.
  - After one year of age, it slowly begins to disappear, and *completely* in 7-8 years (70% in 7 years).
  - It is the most common haemangioma.

- Haemangioma in periorbital region obstructs the vision in newborn with amblyopia and if it persists for 7 days causes permanent visual damage. Astigmatism also can occur
- Haemangioma in nasal area in newborn may obstruct nasal airway seriously (as newborn cannot breathe through mouth—obligatory nasal breathing)
- Skin ulceration may cause haemorrhage
- Infection can occur which may lead into sepsis, necrosis or rarely septicaemia
- Systemic steroid for 3 weeks induces involution
- Usually there is no role for surgery. Surgery is done only for retained tissue after involution

- ***Port-wine stain (Naevus flammeus)***:
  - It presents at birth and persists throughout life without any change. Spontaneous regression will not occur. It presents as smooth, flat, reddish blue/intensely purple area; common in head, neck and face; often with maxillary and mandibular dermatomes of 5th cranial nerve. Eventually surface becomes nodular and keratotic.
  - It persists throughout life.
  - It is actually a *capillary malformation* even though considered under haemangioma. It results from defect



Fig. 1.409: Port-wine stain (Naevus flammeus).

in maturation of sympathetic innervation of skin causing localised vasodilatation of intradermal capillaries.

- It is often associated with Sturge-Weber syndrome, Klippel-Trenaunay-Weber syndrome and Proteus syndrome.
- It needs treatment—laser (pulsed dye/diode); excision and grafting; cosmetic coverage. Expected result by treatment is not possible many times.

Indications for surgery or intervention

- Uncontrolled growth
- Functional impairment like vision or hearing
- Accidental haemorrhage

Treatment

- They are treated by *wait and watch policy* commonly—allowed for *spontaneous regression*.
- Pulsed dye laser (diode laser), surgical excision and reconstruction. *Feeding vessels* may need to be ligated after wide exposure before achieving complete extirpation. Sclerotherapy/cryotherapy/CO_2 snow therapy cause *unpleasant scarring*.
- *Preoperative embolisation* facilitates surgical excision and reduces the operative blood loss. When once embolisation done, surgery should be done *as early as possible* otherwise recurrence occurs and much more worried formation of enlarged collaterals can occur.
- Materials used are—foam, plastic spheres, stainless/platinum steel coils, ethanol, polyvinyl alcohol foam of 1000 μ meters size, and rapidly polymerizing acrylic. Problems are tissue necrosis, reaction, normal tissue embolisation. Procedure is done with interventional radiology under C-Arm guidance.
- *Rapidly growing* haemangioma may need systemic/oral and intralesional *steroid* therapy.
- Antiangiogenic *interferon 2a* may be useful.
- Life-threatening *platelet trapping* may be controlled by *cyclophosphamide* chemotherapy.
- Haemangioma with *drug resistant CCF* can be treated with *radiotherapy*.

Associated syndromes

- ***Klippel-Trenaunay-Weber syndrome:*** Naevus flammeus + osteohypertrophy of extremities (soft tissue and bone hypertrophy) + varicose veins of lower limbs. If there is an association of arteriovenous fistula (AV fistula), it is called as ***Parkes-Weber syndrome***
- ***Kasabach Merritt syndrome:*** Capillary haemangioma + DIC (Disseminated intravascular coagulation) with thrombocytopenia
- ***Sturge-Weber syndrome:*** Haemangiomas (Naevus flammeus) + hemiplegia and Jacksonian epilepsy (calcified vascular cerebral and meningeal deposits) + glaucoma
- ***Maffucci syndrome:*** Cavernous haemangioma + dyschondroplasia
- ***Proteus syndrome:*** Naevus flammeus + regional gigantism with lymphaticovenous malformation (asymmetrical hypertrophy)
- ***Osler-Rendu-Weber syndrome:*** Haemangioma of skin and lip with gastrointestinal tract haemangioma (hereditary haemorrhagic telangiectasia), (autosomal dominant)

Cavernous Haemangioma

- It is present at birth and consists of a multiple venous channels.
- Its size increases gradually and may cause problems.
- It often contains feeding vessels which is of surgical importance.
- *Sites*: Head, neck, face, limbs, tongue, liver and other internal organs.
- Large or multiple cavernous haemangiomas can cause *congestive heart failure* (hyperdynamic) due to shunting of large quantity of blood.
- Cavernous haemangioma with dyschondroplasia is called as Maffucci syndrome.



Figs 1.410A and B: Cavernous haemangioma in (A) tongue and (B) knee.

> *When I was young, I observed that nine out of ten things I did were failures. So I did ten times more work.*
> **—George Bernard Shaw**

- Cavernous haemangioma is often mixed with lymphatic component also (mixed vascular and lymphatic).

Clinical Features

- It is smooth, soft, well-localised, warm, fluctuant, compressible, nonpulsatile swelling with bluish surface occurring in skin and subcutaneous tissue (often in mucosa like oral cavity) without any transillumination.
- *Compressibility and bluish surface* is diagnostic. When swelling is pressed it reduces partially/often completely but when pressure is released it slowly attains its original size and shape. Vascular and lymphatic malformations are compressible.
- It is usually nontender unless it gets infected or undergoes thrombosis or causes haemorrhage.



Figs 1.411A and B: Cavernous haemangioma in the cheek near angle of the mouth and in the tip of the tongue. Haemangioma tongue is one of the causes of macroglossia.



Fig. 1.412: Laparoscopic view of cavernous haemangioma of liver. It is the most common benign tumour of the liver.

Differential Diagnosis

- Lymphangioma: It is brilliantly transilluminant unless it is infected or fibrosed.
- Lipoma, cold abscess, lymph cyst—clinically it is easier to differentiate.

Complications

- Haemorrhage.
- DIC.
- Thrombosis.
- Infection, ulceration and septicaemia.
- Erosion into the adjacent bone.
- High output cardiac failure.

Investigations

- Ultrasound, Doppler.
- Angiogram to find out feeding vessel.
- Platelet count.
- MRI/MR angiogram to see feeding vessels and deeper extension.

Treatment

- Sclerosant therapy: It is the initial first line of therapy. It causes aseptic thrombosis and fibrosis of the cavernous haemangioma with less vascularity and smaller size. It is directly injected into the lesion. Sodium tetradecyl sulphate/hypertonic saline are used. Often multiple injections are needed to achieve complete required effect. Later excision of the lesion is done.
- Ligation of feeding artery and often at later stage excision is done once haemangioma shrinks.
- Therapeutic embolisation.
- If small and located in accessible area, excision is the initial therapy.

- Laser ablation—diode pulsed laser is becoming popular because of good control of bleeding. CO_2/Nd:YAG laser is also equally effective.

VASCULAR MALFORMATIONS

- Secondary to defect in development of vascular components, in 8th week of intrauterine period.
- Single layer endothelium lined spaces derived from arterial, capillary, venous or lymphatic system showing ectasia.
- There is no growth in tissue culture. Raise in mast cells is not seen.
- Associated with many syndromes.
- Can be located in skin or in deeper planes.
- Present at birth and grows in proportion to child's growth. Pale skin which later darkens over the age or faint blue mass is the presentation.
- Spontaneous involution is not common.
- Capillary malformation (CM) type is due to lack of sympathetic control.
- Venous malformation (VM) type is *most common* vascular malformation which shows hypoplasia, hyperplasia or aplasia of superficial or deeper system. It is seen in subcutaneous plane as faint blue compressible mass with morning pain and stiffness of the area.
- Lymphatic malformation (LM) type can be microcystic (lymphangioma) or macrocystic (cystic hygroma). It can cause lymphoedema, soft tissue and bony hypertrophy, asymmetry (face), macrochelia, macroglossia, macrotia, cellulitis.
- *Low/slow flow* malformations can cause skeletal hypoplasia; *high/fast flow* malformations can cause hypertrophy. AVM is high flow type.
- Consumption coagulopathy (DIC) can occur.
- It is equal in both sexes (1:1).
- Doppler is commonly used investigation; but MRI (*MR angiogram is ideal*) with contrast is ideal to identify and to differentiate low and high flow types.
- *Treatment*—conservative with compression garments and sclerotherapy. Laser photocoagulation is the choice for superficial malformations; multiple sittings may be needed; complete clearance may not be achieved. Surgical excision can be done. Preoperative embolisation may be needed.

Vin rose patch:

It is a congenital intradermal pale pink vascular malformation with dilatation of vessels in subpapillary dermal plexus. It may be associated with haemangiomas; AV malformations in limbs; congenital lymphoedema.

CIRSOID ANEURYSM

- It is a rare variant of capillary haemangioma occurring in skin, beneath which abnormal artery communicates with the distended veins.
- Commonly seen in **superficial temporal artery** and its branches.
- Often the underlying bone gets thinned out due to pressure.
- Occasionally extends into the cranial cavity.
- Ulceration is the eventual problem which will lead to uncontrollable haemorrhage.

Clinical Features

Pulsatile swelling in relation to superficial temporal artery, which is warm, compressible, with arterialisation of adjacent veins and with *bone thinning* (due to erosion). It feels like a *'pulsating bag of worms'*.

Investigations

- Doppler study, CT scan.
- Angiogram, X-ray of the part.

Treatment

- Ligation of feeding artery and excision of lesion, often requires preliminary ligation of external carotid artery.
- Intracranial extension requires formal neurosurgical approach.

ARTERIOVENOUS FISTULA (AVF)

It is an abnormal communication between an artery and vein.

Types

- Congenital—is arteriovenous malformation.
- Acquired (Trauma is common cause).

Congenital Arteriovenous Malformation (Fistula)—AVM (AVF)

During developmental period AV communications occur.

It is high flow type of vascular malformation. It is 30% of all vascular malformation. 90% of AVM contains both arterial and venous components. Shuting of blood with thrill and bruit with hyperdynamic circulation is common.

Sites

- Limbs, either part or whole of the limb is involved. It may be localised to toes or fingers.
- Lungs.
- Brain—in circle of Willis.
- Other organs like bowel, liver.

Clinical Features

Structural changes in the limb:

- Limb is **lengthened** due to increase in blood flow since developmental period.
- Limb **girth** is also increased.
- Limb is **warm.**

> *When stethoscope is applied aneurysm is either silent or a systolic bruit can be heard, but an arteriovenous fistula emits a continuous murmer throughout the systole and diastole.*
> **—Charle G Rob**



Fig. 1.413: MR angiogram of AV malformation in cranial cavity.



Fig. 1.414: MRI picture of AV malformation.

- **Continuous thrill and continuous machinery murmur** all over the lesion.
- **Dilated arterialised varicose veins** are seen due to increased blood flow and also due to valvular incompetence.
- Often there is **bone erosion** or extension of AVF into the bone as such.



Figs 1.415A and B: Hypertrophic changes due to AV malformation.

Physiological changes

Because of the hyperdynamic circulation, there is **increased cardiac output** and so often **congestive cardiac failure**.

Complications

- Haemorrhage
- Thrombosis
- Cardiac failure (CCF)

Investigations

- Angiogram—MR angiogram is ideal.
- Doppler study.
- X-ray of the part.
- ECG, echocardiography.

Treatment

- *Conservative*—sclerotherapy, compression, avoiding injury.
- **Indications for intervention**
  - *Absolute*: Haemorrhage, ischaemia, CCF.
  - *Relative*: Pain, functional disability, cosmesis, limb asymmetry.
  - *Emergency*: Torrential bleeding usually after trauma (example—road traffic accidents).

Interventions

- Surgical ligation of *feeding vessels* and complete excision of the lesion. Often if lesion is extending into deeper planes it is technically difficult; but with *usage of tourniquet*, careful meticulous dissection and ligation of all vessels will lead into successful excision of entire lesion.
- Therapeutic *embolisation*/preoperative embolisation hasten the proper surgical excision.
- In *emergency bleeding*, adequate transfusion of blood , tourniquet usage, intraoperative embolisation and then excision of entire lesion is done. Occasionally when extensive AVM is present often involving the entire limb, amputation is the final option left as a life-saving procedure.



Figs 1.416A to E: Congenital arteriovenous malformation involving right upper limb, axillary region and part of right half of neck and face. Note the limb lengthening and widened girth. Limb is warmer. Limb should be measured at each level. Auscultation reveals continuous bruit over the limb. Note the dilated tortuous veins due to hyperdynamic circulation.

Acquired Arteriovenous Fistula (AVF)



Fig. 1.417: AV fistula.

Causes

- Trauma in (most common cause):
    - Femoral region.
    - Popliteal region.
    - Brachial region.
    - Wrist.
    - Aorta—vena caval.
    - Abdomen.

  It may be following road traffic accidents, penetrating wounds, cock-fight injury (common in South India).
- After surgical intervention of major vessels.
- Therapeutic: For renal dialysis, AVF is created (**Cimino fistula**) to achieve arterialisation of veins and also to have hyperdynamic circulation. It is done to have easy and adequate venous access for long time **haemodialysis.** Common sites are **wrist, brachial, and femoral** region.

Pathophysiology

- *Physiological changes: Cardiac failure due to hyperdynamic circulation*.
- *Structural changes:*

Changes at the Level of Fistula

Blood flows from high pressure artery to low pressure vein causing diversion of most of the blood. Between the artery and vein, at the site of fistula, dilatation develops with formation of fibrous sac called as **aneurysmal sac.** This presents as warm, pulsatile, smooth, soft, compressible swelling at the site with **continuous thrill and continuous machinery murmur**.

Changes Below the Level of the Fistula

Because of diversion of arterial blood **distal part becomes ischaemic**. Because of high pressure arterialisation of veins and valvular incompetence occurs causing **varicose veins**.

Changes Proximal to the Fistula

Hyperdynamic circulation causes cardiac failure.

If pressure is applied to the artery proximal to the fistula, swelling will reduce in size, thrill and bruit will disappear, pulse rate and pulse pressure becomes normal. This is called as **Nicoladoni's sign** or **Branham's sign.**

Cardiac failure may be very severe in traumatic AVF (often resistant to drug therapy).

Investigations

- Doppler, angiogram.
- ECG, echocardiography.

Treatment

- **Excision** of fistula and **reconstruction** of artery and vein with graft.



Figs 1.418A and B: Acquired arteriovenous fistula in the wrist over radial vessels. It should be palpated for compressibility and thrill. It should be auscultated for bruit.



Fig. 1.419: AV fistula created for treating chronic renal failure has formed an aneurysm. It may rupture to cause severe haemorrhage. Thrombosis or sepsis also can occur in this.



Fig. 1.420: Quadruple ligation of AV fistula.



Fig. 1.421: Reconstruction of AV fistula using graft.

Done in early stages—larger vessels. Venous or Dacron graft is used.

- In emergency situation, **quadruple ligation**, i.e. both artery and vein above and below are ligated without



Fig. 1.422: Hunter's ligation is ligation of artery proximal to AV fistula. It should not be done as it causes diversion of all blood from periphery leading to gangrene of distal part.

touching the fistula and sac. Patient recovers well from cardiac failure.

- Therapeutic embolisation may be tried.

Hunter's ligation should be avoided. It is used as life-saving measure because it invariably causes limb ischaemia and gangrene even though patient recovers from cardiac failure. It is ligation of both artery and vein proximally so as to make cardiac function normal. But it invariably steals the blood from the limb leading to gangrene.

CAMPBELL DE MORGAN SPOTS

- It is usually smaller (0.2 to 6 mm) in size, circular, elevated and bright red swelling.
- It is common in trunk. Common in elderly.
- Also called as *cherry angiomas.*
- Usually it does not require treatment.
- When needed, excision or electrodesiccation or laser removal is done.

PARRY-ROMBERG DISEASE

- It is hemifacial atrophy of skin, soft tissue and bone.
- Common in females.
- It usually begins at twenties.
- Atrophy of skin, fat, muscle, cartilage and bone causing *coupe de sabre* deformity.
- It is a self-limiting disease.
- Aesthetic reconstruction is offered when severe deformity develops.

HAMARTOMATA

Hamartano means *'I miss' (Greek).* Or 'fault' or 'misfire' or 'error'—(missing the mark in spear throwing).

Note:

Presently this terminology is not very much in use.

- It is a benign lesion with aberrant differentiation producing a mass of disorganised but mature specialised cells or tissue indigenous to the particular site.
- It is tumour like overgrowth of tissue or tissues proper to that part.
- It may be single lesion or multiple lesions.
- Haemangiomas, lymphangiomas, AV malformations, neural malformations are the examples.

Problems with hamartomas

- Pressure symptoms locally
- Bleeding
- Infection
- Gigantism
- Cosmetic problem

Treatment

- Depends on site, type, extent.
- Cryotherapy, ligation of feeding vessels, sclerotherapy, excision or laser therapy.

N. Venous Diseases

CHAPTER OUTLINE

- Anatomy of Veins of Lower Limb
- Physiology of Venous Blood Flow in Lower Limb
- Deep Vein Thrombosis
- Varicose Veins
- Venous Ulcer
- Compression Therapy for Varicose Veins
- Thrombophlebitis
- Klippel-Trenauny Syndrome
- Anticoagulants
- Heparin
- Oral Anticoagulants
- Direct Thrombin Inhibitors
- Antiplatelet Drugs
- Pulmonary Embolism

ANATOMY OF VEINS OF LOWER LIMB


Perforators
Short saphenous system
Long saphenous system

Fig. 1.423: Anatomy of lower limb veins.

Deep Veins

- Tibial, popliteal, femoral veins are called as *"veins of conduits"* which drain blood into iliac veins and then to IVC.
- *Pumping veins*: They are venous sinuses existing in the calf muscles which pump blood towards major veins. They are better termed as *musculovenous pumps*. They are also called as the *peripheral heart*.

Superficial Veins

- *Long/great saphenous vein*: It is a subcutaneous vein over the inner aspect of the leg and thigh, joins into femoral vein at fossa ovalis. Tributaries of long saphenous vein are posterior arch vein, anterior vein of leg, anterolateral vein, posteromedial vein and sometimes accessory saphenous vein.
- *Short/small saphenous vein*: It is over the lateral and posterior aspect of the leg enters the deep fascia in the upper calf region and later joins popliteal vein at variable distance.
- Posterior arch vein of '*Leonardo*' (from medial ankle to the long sephanous vien below the knee).
- Anterior arch vein to peroneal veins.



Fig. 1.424: Bilateral varicosity of great saphenous veins.


Superficial circumflex iliac
Superficial epigastric
Superficial external pudendal
LSV
Anterior vein
Posterior vein
Perforators

Fig. 1.425: Long saphenous vein anatomy and its tributaries.



Figs 1.426A and B: Short saphenous vein varicosity.

Superficial veins have got multiple valves which facilitates blood flow towards heart. Superficial veins usually drain about 10% of lower limb blood, i.e. from skin and subcutaneous tissues.

Perforator Veins

They are the veins which connect superficial to deep veins at various levels. They travel from superficial fascia through an opening in the deep fascia before entering the deep veins. The direction of blood flow here is from superficial to deep veins. These perforators are also guarded by valves so that the blood flow is unidirectional, i.e. towards deep veins. Reversal of flow occurs due to incompetence of perforators which will lead to *varicose veins*.

Types

- Ankle perforators (May or Kuster)
- Lower leg perforators: I, II, III (of Cockett)
- Gastrocnemius perforators (of Boyd)—below knee
- Mid-thigh perforators (Dodd)
- Hunter's perforator in the thigh

There are no valves for IVC and iliac veins. Long saphenous vein has got 10-14 valves; whereas short saphenous vein has usually one valve. Veins can accommodate large quantity of blood and hence called as *capacitance* vessels.

PHYSIOLOGY OF VENOUS BLOOD FLOW IN LOWER LIMB

Veins are thin-walled vessels with collapsible walls, that assume an elliptical configuration in collapsed state and circular configuration in the filled state.

Venous valves are abundant in the distal lower extremity and the number of valves decreases proximally, with no valves in superior and inferior vena cava.

Venous Return

- Arterial pressure across the capillary increases the pumping action of vein.
- *Calf musculovenous pump*: During contraction phase of walking, pressure in the calf muscles increases to 200-300 mmHg. This pumps the blood towards the heart. During relaxation phase of walking, pressure in the calf falls and so it allows blood to flow from superficial to deep veins through perforators. Normally while walking, pressure in the superficial system at the level of ankle is 20 mmHg.
- During walking, foot pump mechanism propels blood from plantar veins into the leg.
- Gravity.

***Note*:**

Pressure in *arteriolar end of the capillary* is 32 mmHg; *venular end of capillary* is 12 mmHg.

Factors responsible for venous return

- Negative pressure in thorax
- Peripheral pump—calf muscles
- Vis-a-tergo of adjoining muscles
- Nonrefluxing valves in course of veins

DEEP VEIN THROMBOSIS (DVT)

It is called as *phlebothrombosis*. It is *semisolid clot* in the vein which has got high tendency to develop pulmonary embolism and sudden death. Common site of beginning of thrombus is soleal veins which later propagate proximally, often getting detached to cause acute massive pulmonary embolism or moderate sized emboli can cause pyramidal/wedge shaped pulmonary infarcts.

Aetiology: Factors

Virchow's triad

- Stasis
- Hypercoagulability
- Vein wall injury

Causes

- Following childbirth.
- Trauma—to leg, ankle, thigh, pelvis.
- Muscular violence.
- Immobility: Bed ridden patients, individuals on long duration air or bus travel ***(Traveller's thrombosis*).**
- Debilitating illness, obesity, immobility, bed rest, pregnancy, puerperium, oral contraceptives, estrogens.
- Postoperative thrombosis *(Most common cause)*: Common after the age of 40 years. Incidence following surgeries is 30%. In 30% of cases both legs are affected. Usually seen after prostate surgery, hip surgery, major abdominal surgeries, gynaecological surgeries, cancer surgeries. Bedridden for more than 3 days in the postoperative period increases the risk of DVT.

You may be disappointed if you fail, you are doomed if you don't try.

- *Spontaneous thrombosis* is common in visceral neoplasm like carcinoma pancreas or carcinoma stomach. It is often migrating type.
- Thrombus may start in a venous tributary which eventually may extend into the main vein causing DVT.
- ***Axillary vein thrombosis***
  - It can occur spontaneously, following compression by cervical rib, by various causes of thoracic inlet syndrome, or arm being in the hyperabduction state for prolonged period (e.g. painting the ceiling), after axillary lymph node block dissection, after radiotherapy to axilla, occasionally as a complication of venous cannulation.
  - Upper limb DVT is rare compared to lower limb DVT (5% of all DVT). It may be axillary or subclavian vein or both.
  - But 30% of upper limb DVT can cause pulmonary embolism.
  - Primary upper limb DVT is *Paget-Schroetter syndrome,* is due to subclavian vein compression that occurs in thoracic outlet syndrome. It may be precipitated by exertion of arms, swimming, exercise, etc.
  - Idiopathic upper limb DVT is rare. Occult underlying malignancy should be thought of.
  - Secondary upper limb DVT is due to CVP line, pacemaker thrombocytosis, malignancy, surgeries, radiotherapy, etc.
  - Unilateral arm, forearm swelling with bluish discolouration, pain, pitting oedema, often with skin blebs are the features.
  - Investigations are—Duplex scan, MR venography (as clavicle obscures proper duplex evaluation), BT, CT, PT, APTT, platelet count estimation.
  - *Treatment* is similar, with heparin/LMWH/warfarin, thrombolysis using tissue plasminogen activator, elevation of the arm, using compression stockings.
- Polycythaemia vera, thrombocytosis.
- Deficiencies of antithrombin III, protein C, protein S, factor V of Leiden, thrombophilia.
- Recent myocardial infarction, heart failure, nephrotic syndrome.
- Thrombosis can occur in individuals who sit with computers for long time—'***ethrombosis'.***

Sites

a. Pelvic veins—not uncommon; involves internal iliac veins. It is more common in PID (pelvic inflammatory disease) in females. In males prostatic veins may be the site of origin. It is difficult to identify clinically even though rectal or vaginal examination may help.

b. Leg veins—very common in veins of soleus muscle in calf; femoral vein/iliofemoral vein thrombosis can occur along with calf veins or independently without calf vein thrombosis which shows adductor canal tenderness. Iliofemoral vein thrombosis is common on left side due to its lengthy course/compression by right iliac artery/often due to presence of web at its entry into IVC. Incidence of bilateral leg DVT is 30% which should be differentiated from bilateral pedal oedema due to other causes like hypoproteinaemia, renal failure and cardiac causes.

c. Upper limb veins—not uncommon (Axillary vein thrombosis).



Fig. 1.427: Deep vein thrombosis (DVT) in both legs. 30% cases of DVT are bilateral.



Fig. 1.428: Unilateral left leg DVT. Note the oedema and colour changes.

Phlegmasia Alba Dolens

It is DVT of *femoral vein* (deep femoral vein commonly) causing painful congestion and oedema of leg, with lymphangitis, which further increases the oedema and worsens the situation (*white leg*).

Phlegmasia Caerulea Dolens

It is extensive DVT of *iliac and pelvic veins* causing *blue leg* with either venous gangrene or areas of infarction.



Fig. 1.429: Right leg venous gangrene. Note the discolouration, blebs and oedema.

Features of DVT

- Commonly it is asymptomatic—60%
- Fever—most common
- Tense, tender, warm, pale/bluish, shiny swelling calf
- Positive Homan's, Mose's or Neuhof's signs
- Inverted champagne bottle sign
- Features of pulmonary embolism

Clinical Features

- Fever—earliest symptom.
- Pain and swelling in the calf and thigh (often). Pain is often so severe that the patient finds it difficult to flex (or move) the leg.
- Leg is tense, tender, warm, pale or bluish with stretched and shiny skin.
- *Positive Homan's sign*: Passive forceful dorsiflexion of the foot with extended knee will cause tenderness in the calf.
- *Mose's sign*: Gentle squeezing of lower part of the calf from side-to-side is painful. Gentleness is very important otherwise it may dislodge a thrombus to form an embolus.
- *Neuhof's sign*: Thickening and deep tenderness elicited while palpating deep in calf muscles.
- Most often, DVT is *asymptomatic* and presents suddenly with features of *pulmonary embolism* like *chest pain, breathlessness* and *haemoptysis.*
- After applying tourniquet at saphenofemoral junction, patient is made to walk and without removing the tourniquet, limb is elevated—persisting prominent superficial veins will be observed in DVT—*Linton's test.*

Differential diagnosis for DVT

- Ruptured Baker's cyst
- Ruptured plantaris tendon
- Calf muscle haematoma
- Cellulitis leg
- Superficial thrombophlebitis

Investigations

- Venous Doppler.
- ***Duplex scanning:*** It shows noncompressible vein which is wider than normal. On compression over calf muscles, it does not show any augmentation of flow. Normal venous sound at the area of femoral vein which disappears during inspiration is conspicuously absent in DVT.
- ***Venogram:*** Contrast material is injected into venous system to get detailed idea of the veins after applying tourniquet into superficial system. Occlusive and nonocclusive thrombus can be differentiated by this. But as it is invasive one, it is not commonly done at present. MR venogram is under trial at present. Impedance plethysmography is used to measure the rate of venous emptying. Vein occlusion is done using cuff around upper thigh which is confirmed by flat electrical wave pattern. When cuff is released rapid flow of wave is observed in normal; sluggish flow of wave is seen in DVT.
- ***Radioactive I^{125} fibrinogen study:*** Sodium iodide 100 mg orally is given to the patient 24 hours before the test to block the thyroid activity. I^{125} labelled fibrinogen 100 µ curies is injected intravenously. First radioactivity of heart is measured by placing the scintillation counter over the precordium. Reading obtained by this is adjusted as 100%. After that legs are elevated using adjustable stands and to prevent venous pooling, scintillation counter is placed over the calf. Counting in the leg is done from below upwards at 5 cm intervals. Procedure is done in preoperative period; on 1st, 3rd and 6th postoperative days. A 20% or more raise in percentage value suggests deep vein thrombosis in leg. I^{125} labelled fibrinogen is used (earlier I^{131} labelled fibrinogen was used) because it has got softer radioaction; its detectability is with much lighter and mobile apparatus.
- Haemogram with platelet count; *D-dimer test*/analysis of fibrin degradation products (FDP) are relevant tests used. D-dimer test is measurement of cross-linked degradation products which interprets the plasmin activity on fibrin. Negative D-dimer test is of more value.
- Ventilation—perfusion scanning with mismatched defects; pulmonary artery CT scan with filling defect; pulmonary angiography are the investigations to confirm the pulmonary embolism.

Treatment

- Rest, elevation of limb, bandaging the entire limb with crepe bandage.
- Anticoagulants: Heparin/low molecular weight heparin, warfarin, phenindione.
- ***For fixed thrombus:***
    - Initially high dose of heparin of 25,000 units/day for 7 days is given. Then later patient is advised to continue warfarin for 3-6 months. Dose is controlled by assessing *Activated Partial Thromboplastin Time (APTT).* Duration of heparin treatment is usually for 7-10 days. *Dose*

Oral contraceptives increases the risk of DVT by 3-5 times.



Fig. 1.430: Doppler study showing DVT.



Fig. 1.431: U/S showing thrombosis of the IVC.

of heparin is often calculated as— 80 units/kg bolus of heparin followed by 15 units/kg of infusion.

- Low molecular weight heparin is preferred to heparin.
- Warfarin should be started as early as possible (*same day* of heparin therapy). Day one and day two—10 mg each day; day three—5 mg. On day three prothrombin time should be done. Warfarin is given for 3-6 months with regular monitoring, depending on the cause, risk group, and severity of DVT. INR should be maintained between 2.0 to 3.0.
- Oral anticoagulants being teratogenic *cannot be used* during pregnancy. LMWH is the *drug* of *choice* used during pregnancy and postpartum period.

- ***For free thrombus*:**

Free thrombus

- Fibrinolysins
- Thrombectomy using Fogarty's catheter
- IVC filter

- *Fibrinolysins*: Streptokinase, 6 lakhs to start with and later one lakh hourly. It is commonly infused directly into the affected vein through a venous catheter. Urokinase or tissue plasminogen activator may also be used to dissolve thrombus (it should not be given when patient is on heparin).

Fibrinolysins

- Tissue plasminogen activator—directly into the thrombus through popliteal/femoral vein
- Urokinase—1,20,000 to 2,50,000 units/hour; derived from human urine
- Reptilase—0.5-1 unit/hour
- Streptokinase—6 lakh to start with later one lakh hourly; derived from streptococci

- Venous thrombectomy is done using Fogarty venous balloon catheter.
- Thrombotic emboli is prevented from reaching the heart by filtering it at IVC level using intracaval filters—Kim ray Greenfield filter, suture sieve plication, stapler plication, vena caval ligation, Mobin Uddin umbrella filter.
- Special thrombectomy device of 7-9 French sheath is passed through the thrombosed segment to have partial mechanical thrombectomy and through that thrombolytics (tissue plasminogen activator) are infused. Thrombus can be removed nowadays through balloon angioplasty tube. Open venotomy and thrombectomy also can be done.

- *Palma operation*: In iliofemoral thrombosis, common femoral vein below the block is communicated to opposite femoral vein through opposite long saphenous vein.
- *May-Husni operation*: When blockage is in popliteal vein, popliteal vein below the block is anastomosed to long saphenous vein (end-to-end) so as to bypass the blood across the popliteal block.



Fig. 1.432: Palma operation for iliofemoral block. Using opposite saphenous vein femoral vein is connected to other femoral vein.



Fig. 1.433: Crepe bandages applied to both legs in bilateral varicose veins and DVT.

Prevention of DVT

- Categorise the patient as low/moderate and high risk. *Low-risk*—young patients undergoing surgery for less than 30 minutes. *Moderate-risk*—patients above 40 years of age undergoing major surgery. *High-risk*—one who had existing cardiac diseases, stroke, previous history of DVT, suffering from malignancy
- Mechanical methods—elastic compression bandage; elevation; external pneumatic bandage
- Pharmacological—low molecular weight heparin—once a day

- Care has to be taken to see for proper positioning of legs with no pressure on the calf muscles.
- Pressure bandage to the legs has to be applied during major surgeries, laparoscopic surgeries. During postoperative period, elevation, massaging, pressure bandage, early ambulation, maintaining hydration are essential measures.
- Low dose heparin is given in suspected cases, in major surgeries and continued during postoperative period till the patient is ambulated. 5,000 units is given subcutaneously 2 hours before surgery. Low molecular weight heparin is preferred drug than heparin as it can be used once a day; it does not require monitoring; it does not cause thrombocytopenia (like heparin); and there is lesser risk of bleeding.
- Various measures like graduated static compression, elastic stockings, electrical stimulation of calf muscles, pneumatic compression are used to prevent sluggish flow of blood.
- Dextran 70, intravenously 500 ml during surgery and another 500 ml postoperatively in 24 hours can also be used to prevent DVT.
- Smoking increases the viscosity of blood and so should be stopped.
- Patients on oral contraceptives or oestrogens should stop the drug 6-8 weeks prior to any elective surgery.

Effects and sequelae of DVT

- Pulmonary *embolism*—15%
- Infection; venous gangrene
- Partial recanalisation, chronic venous hypertension around the ankle region causing venous ulcers—*chronic venous insufficiency*—CVI
- Recurrent DVT—30%
- Propagation of thrombus proximally—20-30%

VARICOSE VEINS

They are dilated, tortuous, elongated veins in the leg. There is reversal of blood flow through its faulty valves.

It is *permanently* elongated, dilated vein/veins with tortuous path causing *pathological* circulation. *Risk factors* being heredity; female sex; occupation that demands prolonged standing; immobility; raised intra-abdominal pressure like in sports, tight clothing, pregnancy, raised progesterone level and altered estrogen-progesterone ratio, chronic constipation, high heels. *Prevalence* of varicose veins is 35%; severe varicose veins is 10%; chronic venous insufficiency (CVI) is 8%; ulcer is 2%.

Classification I

- Long/great saphenous vein varicosity.
- Short/small saphenous vein varicosity.
- Varicose veins due to perforator incompetence.

Classification II

- *Thread veins* (or dermal flares/telangiectasis/spider veins/ Hypen veins are 0.5-1 mm in size): Are small varices in the skin usually around ankle which look like dilated, red or purple network of veins (*Venulectasia*). Spider naevi/*venous flares* are common in females.
- *Reticular varices* (1-4 mm in size): Are slightly larger varices than thread veins located in subcutaneous/subdermal region.
- *Varicose veins*. Dilated palpable subcutaneous veins more than 4 mm in diameter (specifically located in saphenous compartment).
- *Combination of any of the above.*

Small varicose vein is < 4 mm in diameter. Large varicose vein is > 4 mm in diameter.

Corona phlebectatica are blue telangiectasias on the medial aspect of the *foot below the malleolus* around ankle level. More than 5 such lesions are the best independent predictor of the skin changes.



Fig. 1.434: Varicose veins in lower limbs.

Pulsatile varicose veins in lower limb is seen in Klippel Trenauny syndrome.



Figs 1.435A to C: (A) Great saphenous vein varicosity. (B) Small saphenous vein varicosity. (C) Perforator incompetence (*blow outs*).



Fig. 1.436: Thread veins are up to 1 mm diameter; reticular veins are 1-4 mm in diameter.

Classification III

CEAP Classification of Lower Limb Varicose Veins (2004)

CEAP classification

C—*Clinical* signs (grade 0-6); (A) for asymptomatic or (S) for symptomatic presentation

E—*Etiological* classification: Congenital (Ec), Primary (Ep), Secondary (Es), No venous etiology (En)

A—*Anatomic* distribution: Superficial (As), Deep (Ad) or Perforator (Ap), No venous location identified (An)

P—*Pathophysiologic* dysfunction: Reflux (Pr), Obstructive (Po), Both, or No pathophysiology identified (Pn)

Grading of clinical signs (C)

0—No visible or palpable signs of venous diseases
1—Telangiectases, reticular veins or malleolar flare
2—Varicose veins
3—Oedema without skin changes
4—Skin changes due to venous diseases like pigmentation, eczema or lipodermatosclerosis 4a—pigmentation; 4b—lipodermatosis, atrophia blanche
5—Skin changes as above with healed ulceration
6—Skin changes as above with active ulceration

Anatomical distribution (A)

As—superficial system:
1–Telangiectases, reticular veins
2–Great saphenous vein above the knee—ostial and preterminal
3–Great saphenous vein below the knee
4–Small saphnous vein
5–Nonsaphenous—43%

Ad—deep system:
From 6 to 15

Ap—perforator system:
17–Perforator vein (PV) of the thigh
18–Perforator (PV) of the calf and leg

An—no anatomical lesion identified

Pathogenesis

Two theories

- Fibrin cuff theory
- White cell trapping theory

Incompetence of venous valves
↓
Stasis of blood
↓
Chronic ambulatory venous hypertension
↓
Defective microcirculation
↓
RBC diffuses into tissue planes
↓
Lysis of RBC's
↓
Release of haemosiderin
↓
Pigmentation
↓
Dermatitis
↓
Capillary endothelial damage
↓
Prevention of diffusion and exchange of nutrients
↓
Severe *anoxia*
↓
Chronic venous ulceration ***(Fibrin cuff theory*).**

- Inappropriate activation of trapped leucocytes release proteolytic enzymes which cause cell destruction and ulceration—***White cell trapping theory***. Fibrin deposition, tissue death, scarring occurs together, called as *lipodermatosclerosis***.**
- *Secondary valvular failure* → venous reflux → venous wall dilatation → effects. Weakening of the venous endothelial wall and valves occur due to raised venous wall tension by—(1) Shearing stress pressures of blood flow, (2) Increased matrix metalloproteinases (MMPs) activity on endothelium and smooth muscle cells reducing structural integrity of

venous wall with decreased elastin content in the media of the vein, (3) Changes in normal venous constriction and relaxation properties, (4) Recurrent inflammation.

- *Venous system* in the lower limb is maintained by—(1) *Valvular competence,* (2) *Venous patency,* (3) *Calf muscle pump* which is venous channel/plexus within the soleus muscle. Any change in any of these systems can cause venous insufficiency.
- *Chronic venous insufficiency (CVI)* is a syndrome resulting from continuous chronic venous hypertension/ambulatory venous hypertension [AVP] (> 80 mmHg venous pressure at ankle) in the erect posture either on standing or exercise (in normal people venous pressure in superficial system falls during calf contraction). CVI consists of postural discomfort, varicose veins, oedema, pigmentation, induration, dermatitis, lipodermatosclerosis and ulceration. CVI patients may be having superficial vein incompetence (30%) with or without perforator incompetence or deep vein incompetence (30%) or having previous DVT with complete obliteration or partial recanalisation with incompetence called as *post-thrombotic syndrome* (30%).
- Varicose vein is a condition of *progressive deterioration* even often with interventions.



Figs 1.437A and B: Lipodermatosclerosis is pigmentation, thickening, and induration of the skin due to venous diseases.

Aetiology of Varicose Veins

Varicosities are more common in lower limb because of erect posture and long column of blood has to be supported which can lead to weakness and incompetency of valves. Incidence is 5% of adult population.

- *Primary varicosities* due to:
  - Congenital incompetence or absence of valves.
  - Weakness or wasting of muscles—defective connective tissue and smooth muscle in the venous wall.
  - Stretching of deep fascia.
  - Inheritance (family history) with FOXC2 gene.
  - Klippel-Trenaunay syndrome, avalvulia, Parkes-Weber syndrome. Here varices are of atypical distribution.
- *Secondary varicosities*:
  - Recurrent thrombophlebitis.
  - Occupational—standing for long hours (traffic police, guards, sportsman).



Fig. 1.438: Bilateral varicose veins with pigmentation, ulcer and lipodermatosclerosis.



Fig. 1.439: Long saphenous vein varicosity.



Fig. 1.440: Long saphenous vein varicosity on the medial aspect.

Venous claudication is acute bursting pain on ambulation due to chronic venous insufficiency.



Fig. 1.441: Ankle flare seen around ankle, which eventually leads into complications of varicose veins.

- Obstruction to venous return like abdominal tumour, retroperitoneal fibrosis, lymphadenopathy, ascites.
- Pregnancy (due to progesterone hormone), obesity, chronic constipation.
- AV malformations—congenital or acquired.
- Iliac vein thrombosis.
- Tricuspid valve incompetence.

Sites where varicosities can occur

- Lower limb
- Pampiniform plexus of veins
- Vulva, perineum
- Sites of portosystemic anastomosis

Predisposing factors for varicose veins are—age, sex, race, obesity, height, left > right, occupation, family history, erect posture.



Fig. 1.442: Typical site of venous ulcer. Note the pigmentation and chronicity.

Clinical Features

Symptoms in varicose veins

- Dragging pain, postural discomfort
- Heaviness in the legs
- Night time cramps—usually late night
- Oedema feet, itching (feature of CVI)
- Discolouration/ulceration in the feet/painful walk

Causes of pain/cramps in varicose veins/venous diseases

- Increased venous wall tension—chronic venous hypertension
- Hypoxia of tunica media of the venous wall due to altered function of vasa vasorum
- Increased capillary pressure
- Hyperviscosity of red cells—haemorrheological disorders
- Platelet hyperaggregation
- Reduction in capillary permeability causing *capillary functional disorder*
- Altered cutaneous microcirculation due to leukocyte adhesion and accumulation into the venous wall; release of free radicals cause *microvascular lesional disease*

Oedema in venous diseases

- Can be localised or generalised
- Localised oedema is due to ankle flare or dilatation of medial marginal vein
- Cellulitis and lymphangitis association causes oedema
- Scarring and thickening of dermal and subdermal tissues—*lipodermatosclerosis* (brawny induration)
- Ankle becomes narrower due to contraction of skin and subcutaneous tissues but calf remains prominent—*champagne bottle appearance*
- Pale atrophic skin with white patches surrounded by dilated capillaries and pigmentation—*atrophic blanche*

It is more common in females (10 : 1). Often it is familial. *Familial varicose veins* begin in younger age group, seen bilaterally, involves all veins including deep veins.

Signs

- Visible dilated veins in the leg with pain, distress, nocturnal cramps, feeling of heaviness, pruritus.
- Pedal oedema, pigmentation, dermatitis, ulceration, tenderness, restricted ankle joint movement.
- Bleeding, thickening of tibia occurs due to periostitis.
- Positive cough impulse at the saphenofemoral junction.
- *Saphena varix*—a large varicosity in the groin, which becomes visible and prominent on coughing.
- **Brodie-Trendelenburg test**: Vein is emptied by elevating the limb and a tourniquet is tied just below the saphenofemoral junction (or using thumb, saphenofemoral junction is occluded). Patient is asked to stand quickly. When



Fig. 1.443: Site of saphena varix—in the lower part of groin just below the inguinal ligament.



Fig. 1.444: Brodie-Trendelenburg test. Note the reversal of blood flow while releasing the tourniquet.



Figs 1.445A and B: Tourniquet tests for long saphenous vein and short saphenous vein.

tourniquet or thumb is released, rapid filling from above signifies saphenoemoral incompetence. *This is Trendelenburg test I.*

In *Trendelenburg test II*, after standing tourniquet is not released. Filling of blood from below upwards rapidly can be observed within 30-60 seconds. It signifies perforator incompetence.

- ***Perthe's test:*** The affected lower limb is wrapped with elastic bandage and the patient is asked to walk around and exercise. Development of severe cramp like pain in the calf signifies DVT.
- ***Modified Perthe's test***: Tourniquet is tied just below the saphenofemoral junction without emptying the vein. Patient is allowed to have a *brisk walk* which precipitates *bursting pain* in the calf and also makes superficial veins more prominent. It signifies DVT.

  DVT is contraindicated for any surgical intervention of superficial varicose veins. It is also contraindicated for sclerosant therapy.
- ***Three tourniquet test***: To find out the site of incompetent perforator, three tourniquets are tied after emptying the vein.
  - At saphenofemoral junction.
  - Above knee level.
  - Another below knee level.

  Patient is asked to stand and looked for filling of veins and site of filling. Then tourniquets are released from below upwards, again to see for incompetent perforators.
- ***Schwartz test:*** In standing position, when lower part of the long saphenous vein in leg is tapped, impulse is felt at the saphenous junction or at the upper end of the visible part of the vein. It signifies continuous column of blood due to valvular incompetence.
- ***Pratt's test***: Esmarch bandage is applied to the leg from below upwards followed by a tourniquet at saphenofemoral junction. After that the bandage is released keeping the tourniquet in the same position to see the "*blow outs*" as perforators.
- ***Morrissey's cough impulse test:*** The varicose veins are emptied. The leg is elevated and then the patient is asked to cough. If there is saphenofemoral incompetence, expansile impulse is felt at saphenous opening. It is a venous thrill due to vibration caused by turbulent backflow.
- ***Fegan's test***: On standing, the site where the perforators enter the deep fascia bulges and this is marked. Then on lying down, button like depression (crescent like) in the deep fascia is felt at the marked out points which confirms the perforator site.
- ***Ian-Aird test***: On standing, proximal segment of long saphenous vein is emptied with two fingers. Pressure from proximal finger is released to see the rapid filling from above which confirms saphenofemoral incompetence.
- Examination of the abdomen has to be done to look for pelvic tumours, lymph nodes, which may compress over the veins to cause varicosity

Everybody is in favour of progress. It is the change they don't like.



Fig. 1.446: Bilateral varicose veins. Note the tortuous long saphenous vein.

Venous disability scoring system

Score 0	Asymptomatic
Score 1	Symptomatic but able to carry out activities without any therapy
Score 2	Symptomatic—can do activities only with compression/limb elevation
Score 3	Symptomatic—unable to do daily activities even with compression or limb elevation

Venous segmental disease score (venous clinical scoring system) is done based on different symptoms/signs/ulcer activity/compression therapy with 10 parameters with each having 3 scores as mild/moderate/severe.

Complications of Varicose Veins

- *Haemorrhage:* Venous haemorrhage can occur from the ruptured varicose veins or sloughed varicose veins, often torrential, but can be controlled very well by elevation and pressure bandage.
- *Pigmentation, eczema and dermatitis.*
- *Periostitis* causing thickening of periosteum. It delays healing of ulcer due to poor perfusion of ulcer bed.
- *Venous ulcer.*
- *Marjolin`s ulcer*—due to *unstable scar of long duration*—very well differentiated squamous cell carcinoma.
- *Lipodermatosclerosis.*
- *Ankylosis* of the ankle joint is due to fibrosis of soft tissues around ankle joint—fibrous ankylosis.
- *Talipes equinovarus*, wherein patient walks on the tip of toes like horse.
- *Deep venous thrombosis* per se due to varicose vein is rare but can occur if there is associated deep vein disease or recurrent thrombophlebitis.
- *Calcification of the wall* of varicose veins or of sclerosed soft tissue.
- *Recurrent thrombophlebitis*, clot formation on the superficial system often at perforator level which often get infected causing fever and tenderness over the spot.

Investigations

- ***Venous Doppler:***
  - With the patient standing, the doppler probe is placed at saphenofemoral junction and later wherever required. Basically by hearing the changes in sound, venous flow, venous patency, venous reflux can be very well-identified.
  - *Doppler test:* When a *hand held Doppler* (continuous wave 8 MHz flow detector) is kept at SFJ, typical

Fig. 1.447: Doppler machine to assess venous system and its problems.



Fig. 1.448: Venous haemodynamic mapping (VHM) of the lower limb.

audible, '*whoosh signal'* > 0.5 sec while performing Valsalva manoeuvre is the sign of reflux at SFJ. It is also used at SPJ and at perforators. *Note:* All clinical/phlebological tests mentioned above have been superseded by Doppler test. *Doppler test is considered to be a clinical method.*

- ***Duplex scan:***
  - It is a highly reliable U/S Doppler imaging technique (here high resolution B mode ultrasound imaging and Doppler ultrasound is used) which along with direct visualisation of veins, gives the functional and anatomical information, and also colour map. Examination is done in standing, lying down position and also with Valsalva manoeuvre. *Hand-held Doppler* probe is placed over the site and visualised for any block and reversal of flow. DVT is very well-identified by this method.
  - *Venous haemodynamic mapping/*VHM/Cartography is essential prior to surgery.

***Note*:**
Proper *venous haemodynamic mapping (VHM)* is essential.

Venous Doppler in varicose veins

- To find out DVT—very important
- To find out saphenofemoral, saphenopopliteal incompetence
- To find out perforator incompetence
- Uniphasic signals signify flow in one direction—normal
- Biphasic flow signifies reversal flow with incompetence



Figs 1.449A and B: Duplex scan for venous diseases of lower limb should also be done in standing position.

  - **Digitally coded free flow (B flow) USG** (Professor Feder Lurie of Hawaii) allows simultaneous visualisation of flowing blood/blood cells and surrounding stationary structures to give proper *haemodynamic imaging* with functioning mechanism of venous valves, valve leaflets and flow across leaflets. This may be the *ideal* tool of investigation in future.

- ***Venography:***
  - *Ascending venography* was very common investigation done before Doppler period.

    A tourniquet is applied above the malleoli and vein of dorsal venous arch of foot is cannulated. Water soluble dye injected, flows into the deep veins (because of the applied tourniquet). X-rays are taken below and above knee level. Any block in deep veins, its extent, perforator status can be made out by this.

    It is a good reliable investigation for DVT.

    If DVT is present, surgery or sclerotherapy are contraindicated.
  - *Descending venogram* is done when ascending venogram is not possible and also to visualise incompetent veins. Here contrast material is injected into the femoral vein through a cannula in standing position. X-ray pictures are taken to visualise deep veins and incompetent veins.

Phlebography

- Ascending phlebography defines obstruction
- Descending phlebography identifies valvular incompetence
- Regularly not required to be done

- ***Plethysmography*:**
  - It is a noninvasive method which measures volume changes in the leg. It gives *functional* information on venous volume changes and *calf muscle pump* insufficiency.
  - ***Photoplethysmography***: Using probe transmission of light through the skin, venous filling of the surface venules which reflects the superficial venous pressure is measured. Initially patient performs dorsiflexion at ankle for 10 times to empty the venules and pressure tracing falls in photoplethysmography. Patient takes rest and refilling occurs. In normal people, it occurs through

arterial inflow in 20-30 seconds. In venous incompetence filling also occurs by venous reflux and so refilling time is faster than normal.

Disadvantage: Site of reflux cannot be localised by this method.

- ***Air plethysmography***: Patient is initially in supine position with veins emptied by elevation of leg. Air filled plastic pressure bladder (inflatable polyurethane cuff filled with air) is placed on calf to detect volume changes. Minimum volume is recorded. Patient is turned to upright position and venous volume is assessed. Maximum venous volume divided by time required to achieve maximum venous volume gives the *venous filling index (VFI)*. VFI is a measure of reflux. *Ejection fraction* is volume change measured prior and after single tiptoe manoeuvre which is a measure of calf pump action. *Residual venous fraction* is an index of overall venous function which is venous volume in the leg after ten toetip manoeuvres divided by venous volume prior to manoeuvre. *Increased VFT and diminished ejection fraction in a patient will benefit from surgery.*

- ***Ambulatory venous pressure (AVP):***
  It is an invasive method. Needle inserted into dorsal vein of foot is connected to transducer to get its pressure which is equivalent to pressure in the deep veins of the calf. Ten tiptoe manoeuvres are done by the patient. With initial rise in pressure, pressure decreases and eventually stabilises with a balance. Pressure now is called as *ambulatory venous pressure (AVP)*. After stopping exercise, veins are allowed to refill with return of pressure to baseline. Time required for pressure to return to 90% of baseline is called as *venous refilling time (VRT).* Raise in AVP signifies venous hypertension. Patients with AVP more than 80 mmHg has got 80% chances of venous ulcer formation.
- ***Arm-foot venous pressure:***
  Foot pressure is not more than 4 mmHg above the arm pressure.
- ***U/S abdomen***, peripheral smear, platelet count, other relevant investigations are done depending on the cause of the varicose veins.
- If venous ulcer is present, then the discharge is collected for culture and sensitivity, biopsy from ulcer edge is taken to rule out Marjolin's ulcer.
- Plain X-ray of the part is taken to look for periostitis.
- ***Varicography***:
  Here nonionic, iso-osmolar, nonthrombogenic contrast is injected directly into the variceal vein to get a detailed anatomical mapping of the varicose veins. It is used in recurrent varicose veins.

Differential diagnosis

- Lymphoedema
- AV malformation
- Orthostatic oedema
- Renal and cardiac disease
- Hepatic causes
- Vasculitis
- Metabolic diseases like gout, myxoedema, and morbid obesity
- Chronic infections like tuberculosis, syphilis

Treatment

- ***Conservative treatment:***
  - *Elastic crepe bandage application* from below upwards or use of pressure stockings to the limb—pressure gradiant of 30-40 mmHg is provided.
  - *Diosmin therapy* which increases the venous tone.
  - *Elevation of the limb*—relieves oedema. Two short times, during day and full night, elevation of foot with feet above the level of heart and toes above the level of nose is the method.
  - *Unna boots*—provide nonelastic compression therapy. It comprises a gauze compression dressings that contain zinc oxide, calamine, and glycerine that helps to prevent further skin break down. It is changed once a week.
  - *Pneumatic compression method*—provide dynamic sequential compression.
  - These methods *reduce the AVP*, reduce transcapillary fluid leakage by increasing SC pressure and improve cutaneous microcirculation.
- ***Drugs used for varicose veins:***
  - Calcium dobesilate—500 mg BD. Calcium dobesilate improves lymph flow; improves macrophage mediated proteolysis; and reduces oedema.
  - Diosmin—450 mg BD.
  - Diosmin 450 mg + Hesperidin 50 mg (DAFLON 500 mg). Mainly used in relieving night cramps but not to improve healing of ulcers.
  - Toxerutin 500 mg BD, TID. Antierythrocyte aggregation agent which improves capillary dynamics.
  - Diosmin is micronized purified flavanoid fraction. It protects venous wall and valve, and it is anti-inflammatory, profibrinolytic, anti-oedema, lymphotropic.
  - Benzopyrones, saponins, plant extracts, Ruscus (venular α 1 adrenergic receptor partial agonist) coumarins are different drugs used.

  Benefits of all these drugs are doubtful.
- ***Injection—sclerotherapy:***
  - *Fegan's technique:* By injecting sclerosants into the vein, complete sclerosis of the venous walls can be achieved.

  Indications
  - Uncomplicated perforator incompetence.
  - In the management of smaller varices—reticular veins, thread veins (telangiectasis).
  - Recurrent varices.
  - Isolated varicosities.
  - Aged/unfit patients.

Sclerosants used are:

- Sodium tetradecyl sulphate 3% (STDS)—commonly used
- Sodium morrhuate
- Ethanolamine oleate
- Polidocanol

Mechanisms of action

- Causes aseptic inflammation
- Causes perivenous fibrosis leading to block
- Causes approximation of intima leading to obliteration by endothelial damage
- Alters intravascular pH/osmolality
- Changes surface tension of plasma membrane

- A 23 gauge needle is inserted into the vein (3-8 mm sized) and vein is emptied. 0.5-1 ml of sclerosant is injected into the vein and immediately compression is applied on the vein (prevent the entry of blood which may cause thrombosis, which later gets recanalised, further worsening the condition) so as to allow the development of sclerosis and to have proper endothelial apposition.
- Usually injection is started at the ankle region and then proceeded upwards along the length of the veins at different points. Later pressure bandage is applied for six weeks. Often injections may have to be repeated at 2-4 weeks intervals for 2-4 sessions. Technique is called as *macrosclerotherapy.*
- Entrapped blood may require to be evacuated after 14 days which is often essential to prevent recanalisation.

- ***Microsclerotherapy:***

  Very dilute solution of sclerosing agent like STDS, (0.1% of 0.1 ml—dilute) Polidocanol is injected into the thread veins and reticular veins followed by application of compression bandage (30 G needle). Dermal flare will disappear well by this method.
- ***Transillumination microsclerotherapy*** *(vein—lite):* It is better imaging of the veins using light generated by halogen bulb with high quality fibre illumination over the skin uniformly and passing 30 gauge needle for microsclerotherapy.
- ***Foam sclerotherapy by Tessari:***
  - STDS taken in a syringe is passed rapidly into another syringe which contains air to result in formation of foam. 1 ml of STD is mixed with 4 ml of air to make 5 ml of foam which is injected to vein. Total 6 ml maximum of STDs with 30 ml foam can be used. This foam in much larger quantity is injected into the superficial vein. Air get absorbed between foam and endothelial lining is destroyed. Foam minimises thrombosis by pushing the blood out of the site of the vessel where action is needed. Polidocanol/STDs is used for foam sclerotherapy.
  - *Advantages:* Cheap, technically easy, easily available, OPD procedure, can be repeated many times, anaesthesia is not needed, can be used along with other procedures for varicose veins.
  - *Complications:* Headache, transient blindness, stroke, air embolism, thrombophlebitis, pain over injected site, pigmentation.
  - *Contraindications:* Peripheral arterial disease, DVT.
- ***Echosclerotherapy:***

  Sclerotherapy is done under duplex ultrasound image guidance.
- ***Catheter directed sclerotherapy:***

  It is devised at Miami vein clinic with specific catheter for sclerotherapy. This catheter has got side holes all around the specific length for uniform contact of venous wall with the foam. It also has got a balloon at the tip



Figs 1.450A to C: Technique making foam and injecting into the vein. 4 ml air with 1 ml STD is mixed vigorously using 3 way stopcock and two 5 ml syringes. Created foam is injected into the vein immediately. Total of 6 ml STD (30 ml foam) can be injected.

INR (International Normalised Ratio): Ratio of measured PT to a mean lab control PT corrected for the sensitivity of thromboplastin



Fig. 1.451: Catheter directed sclerotherapy.

which after inflation blocks the SFJ thus preventing embolization of foam. It has got three external ports one for balloon inflation; one for bladder valve port; one for injection. This technique is under trial.

Contraindications for sclerotherapy

- Saphenofemoral incompetence
- Deep venous thrombosis
- Huge varicosities—may precipitate DVT
- Peripheral arterial diseases
- Hypersensitivity/immobility
- Venous ulcer—relative contraindication

Advantages of sclerotherapy

- It can be done as an outpatient procedure.
- It does not require anaesthesia.

Disadvantages of sclerotherapy

- Inadvertent subcutaneous injection can cause skin necrosis or abscess formation.
- Anaphylaxis, vasovagal shock, allergy.
- Hyperpigmentation.
- Thrombophlebitis.
- Deep venous thrombosis can occur.
- Inadvertent intra-arterial injection—serious complication.
- Intravenous haematoma.
- Temporary ocular disturbances.
- Skin staining, injection ulcers, persistent local pain.

Remember about sclerotherapy

- Current place of sclerotherapy is mainly for recurrent varicosities and thread/telangiectatic veins
- Sodium tetradecyl sulphate (STDS) is most commonly used sclerosant
- Hyperpigmentation is common after STDS
- Anaphylaxis is common after sodium morrhuate
- Anaphylaxis is least with polidocanol
- Extravasation (presence of pain/irritation/burning) should be avoided as it will cause skin necrosis
- Postsclerotherapy walking immediately after injection for 30 minutes with elastic bandage in place prevents/minimises the chances of DVT
- Compression bandage should be worn for minimum period of 6 weeks
- Sclerotherapy can be—macrosclerotherapy; microsclerotherapy; echo (ultrasound guided) sclerotherapy; foam sclerotherapy; transilluminated sclerotherapy

Indications for interventional procedures: *To relieve* **Complaints** which are relevant like pain, discomfort; to reverse **Complications** like skin changes, ulcers, bleeding, superficial thrombophlebitis, lipodermatosclerosis; **Cosmesis; prophylaxis** (not well accepted)**.**



Fig. 1.452: Veins should be marked just prior to surgery using marking ink.

- ***Surgery:***
  - ***Trendelenburg operation (Crossectomy)***
    It is juxtafemoral flush ligation of long saphenous vein (i.e. flush with femoral vein), after ligating named (superficial circumflex, superficial external pudendal, superficial epigastric vein), deep external pudendal vein and unnamed tributaries. All tributaries should be ligated, otherwise recurrence will occur. Double saphenous vein is the most common anomaly occurring near saphenovenous junction.
  - **Stripping of vein**
    - Using *Myer's stripper* vein is stripped off. Stripping from below upwards is technically easier. Immediate application of crepe bandage reduces the chance of bleeding and haematoma formation. Stripping avulses the vein as well as obliterates the tributaries. Babcock's stripper and rigid metal pin stripper can also be used.
    - ***Two methods of stripping*** are used: (1) *Extraluminal collision technique* using Myer's stripper (Acorn head stripper, 73 cm long) is practiced since long time; but it damages the adjacent tissue, causes infection, postoperative pain, discomfort and haematoma along the stripped tract with possibility of revascularisation of the tract haematoma. (2) *Invagination technique* is better with less damage to adjacent tissue. *Codman's stripper* is used for invagination technique.
    - Stripping of the short saphenous vein is done from ankle below upwards after passing stripper from above downwards. It obliterates the mid calf perforator vein which is the common reason for recurrences.
    - ***Complications of stripping:*** *Saphenous neuralgia* (1%) due to saphenous nerve injury/avulsion; numbness and tingling along femoral nerve distribution; haematoma; infection; ulceration; *recurrence of the*



Fig. 1.453: Linton's vertical approach for subfascial perforator ligation in the leg.


A
Olive tips (knobs)
Handle
Detachable tip
Stripper
B

Figs 1.454A and B: Photo of Myer's stripper with Olive tips and also diagrammatic look of the same.

disease is common (30%) which is not due to any technical default but due to progression of disease itself by *neo-angiogenesis and re-vascularisation*.

- *Stripping is not usually done for the veins in the lower part of the leg in LSV*.
- *Stripping of the vein is more effective than just ligation at the junction.*


Inguinal ligament
Antero-
superior
iliac spine
Incision
LSV

Fig. 1.455: Incision for juxtafemoral flush ligation of long saphenous vein (Trendelenburg operation).


Tributaries
Saphenofemoral junction
LSV
A
All tributaries
ligated
LSV
Saphenofemoral junction
B

Figs 1.456A and B

A man without purpose is like a ship without rudder.



Fig. 1.456C

Figs 1.456A to C: Saphenofemoral junction and its ligation. Tributaries are well seen.



Fig. 1.457: Stripper knob on the distal part of the vein before stripping of the vein.



Figs 1.458A and B





Figs 1.458C and D

Figs 1.458A to D: Long saphenous vein stripping. Note the stripped vein. Stripping is better than just ligation at the junction.

  - ***'Inverting or invaginating stripping'*** using rigid *Oesch pin stripper* is better as postoperative pain and haematoma is less common and also tissue damage. Vein should be very firmly fixed to the end of the stripper and pulled out to cause the inverting of the vein.
  - *Stripping of short saphenous vein is more beneficial than just ligation at saphenopopliteal junction*. It is done from above downwards using a rigid stripper to avoid injury to sural nerve.
- ***Subfascial ligation of Cockett and Dodd*:**
  - Perforators are marked out by Fegan's method. Perforators are ligated deep to the deep fascia through incisions in anteromedial side of the leg.



Fig. 1.459: Typical perforator ligation.



Fig. 1.460: Cockett and Dodd subfascial ligation of perforators using multiple small horizontal incisions.

- ***Ligation of short saphenous vein*** at saphenopopliteal junction. It is done in prone position with horizontal incision. Variations in SP junction are common. But stripping is better.
- ***Linton's vertical approach***—subfascial ligation of perforators.
- ***Stab avulsion of varicose vein and perforators (Fig. 1.461):*** Avulsion is done using mosquito forceps or avulsion hooks—*hook phlebectomy*. It is popular method, also used along with other minimal invasive techniques like EVLA, RFA. Multiple incisions are made and veins are carefully and gently avulsed/teased to clear it. Postoperative compression bandage is a must.

♦ **Minimally invasive methods:**

a. Subfascial endoscopic perforator ligation surgery (SEPS)

- A special telescope is introduced deep to deep fascia through a single small vertical incision at proximal leg selecting healthy skin. Potential space between muscle and deep fascia with loose areolar tissue is easy to dissect using endoscope. Technique is done under tourniquet 300 mmHg pressure. Endoscope is advanced down along the medial border of the tibia. Perforators travelling in subfascial plane are identified and fulgurated using bipolar cautery or clips can be applied into the perforators. It is recommended in chronic venous insufficiency (CVI). But its limitation is difficulty in getting 'lift off' skin in cases with severe lipodermatosclerosis to identify the perforators.



Fig. 1.461: Avulsion of the perforator using hook or mosquito forceps through a small skin incision.


Through working channel clip applicator or diathermy instrument is passed
Visual side may be connected to a monitor
Incision for SEPS
Perforators

Fig. 1.462: Subfascial endoscopic perforator ligation surgery (SEPS).

b. Radiofrequency ablation (RFA) method (VNUS closure method) (VNUS medical technologies Inc; Sunnyvale, CA, USA) (by Goldman 2000):

This procedure is done under general or regional anaesthesia. A RFA catheter is passed into long/ short saphenous vein near saphenofemoral or sapheno-popliteal junction under guidance. 85°C temperature is used for longer period of time to cause endothelial damage, collagen denaturation and venous constriction. Phlebectomy is done while withdrawing the catheter. Wall of the vein is destroyed through its full thickness. Vein forms a cord, which gets dissolved by macrophages and immune cells.

c. ***Trivex method*:**
Under subcutaneous illumination and local anaesthesia, a large quantity of fluid is injected percutaneously to identify the superficial veins under. Tumescent anaesthesia created causes hydrodissection. Trivex resector and illuminator are placed under the skin. Resector gently extracts veins by suction and morcellation. Further stages of tumescence flushes all blood and delivers vasoconstriction solutions. Solution is passed through 18 gauze needle to clear all blood underneath. Method is cosmetically acceptable; removes all sized veins; achieves good pain relief; with minimal complications like bruising, induration which gets resorbed eventually; and can be used when there are venous ulcers.

d. ***Endovenous laser ablation (EVLA):***
It is done as an outpatient procedure or as day-care surgery. Patient lies supine with diseased leg flexed, hip externally rotated and knee flexed. With aseptic precaution, under U/S guidance LSV is cannulated above the knee and a guide wire is passed beyond SFJ and 5- French catheter is passed over guide wire and tip is placed 1 cm distal to the junction. 200 ml of 0.1 % lignocaine (crystalloid with local anaesthetic) is infiltrated along the length of the LSV. Laser fibre is inserted up to the tip of the catheter and catheter is withdrawn for 2 cm and laser fibre protrudes for 2 cm. Laser fibre is fired step by step using diode laser (810-1470 nm diode laser energy), one mm withdrawal in 2 seconds. Once procedure is over catheter is removed and pressure bandage is applied for 2 weeks. Heat produced (729-1000°C at tip) by the laser produces steam bubbles with thermal damage of endothelium leading into occlusion of the vein. Laser energy acts on the blood within the vein rather directly through the wall and heats the blood and in turn heats the vein wall. *Drawback of laser* therapy is inability to create flush occlusion allowing tributaries to open up to cause possible recurrence.
Complications of EVLA: Pain; ecchymosis, haematoma, skin burns, difficulty in cannulating the unsuitable vein if selected; DVT; sensory disturbances, infection.

Note:
EVLA has got 95% efficacy. *Tumescent anaesthesia* is prepared by mixing 5000 ml of normal saline, 30 ml of xylocaine 1% with adrenaline, 30 ml of 8.4% sodium bicarbonate. It is injected using long needle along the length adjacent to vein to cause tamponade and to prevent heat burn on the surface.

e. ***Other methods:***
- *Transilluminated phlebectomy* is done by passing transilluminating light under the skin and passing a rotating blade through another small incision. Veins are grasped and removed by rotating movements.
- *Ambulatory phlebectomy* is done through tiny small incisions using special phlebectomy instruments.
- *Electrodessication* using weak electric current through a fine needle directly into the spider veins (telangiectasis) is also used.



Figs 1.463A to D: Endovenous laser ablation (EVLA) for varicose veins.

Problems in varicose vein surgery

- Infection—10%
- Haematoma formation
- DVT—0.01%
- Saphenous neuralgia, sural nerve injury
- Recurrence

***Note*:**
Contraindication for surgery is deep vein thrombosis (DVT).

VENOUS ULCER (Gravitational Ulcer)

It is the complication of varicose veins or deep vein thrombosis.

Pathogenesis of Venous Ulcer

Varicose veins or DVT which are recanalised, eventually causes *chronic venous hypertension* around ankle

↓

Causes haemosiderin deposition in the subcutaneous plane from lysed RBC's

↓

Eczema

↓

Dermatitis

↓

Lipodermatosclerosis

↓

Fibrosis

↓

Anoxia

↓

Ulceration

Ambulatory venous hypertension is the *prime cause* of venous ulcer formation. Venous hypertension may be *gravitational* which is due to hydrostatic pressure by weight of blood column from the right atrium (*hydrostatic reflux*) which is maximum at foot and ankle **OR** *dynamic* which is due to muscular contraction across the incompetent perforator with a high pressure up to 200 mmHg (*hydrodynamic reflux*). There is a peculiar recycling of blood from deep veins → femoral vein → spillage of blood across incompetent SFJ into LSV / GSV → passage of same blood across perforators into the deep veins to reach femoral vein → again to enter the LSV as spillage.



Fig. 1.464: Venous ulcers in the lower limb.

White cell trapping' theory and 'fibrin cuff' theory; release of free radicals; increased matrix metalloproteinases (MMPs); abnormal fibroblast activity; inhibition of growth factors; are other causes of venous ulcer formation.

- *Area where venous ulcer commonly develop, is around and above the medial malleoli* because of presence of large number of perforators which transmit pressure changes directly into superficial system. This area is called as *Gaiter's zone*. It can also be on both malleoli.
- Ulcer is often large, nonhealing, tender, recurrent with secondary infection. Vertical group of inguinal lymph nodes are usually enlarged and tender.



Fig. 1.465: Gaiter's zone. It is handbreadth area around malleoli where complications of venous disease occurs. *Word gaiter* (French) is a leather/cloth covering for lower leg and ankle.



Fig. 1.466: *Champagne bottle sign/inverted beer bottle sign* is seen in lipodermatosclerosis due to prominent calf with narrow ankle contracted skin and subcutaneous tissue. Sign is often observed in DVT also.

Everything has its beauty but not everyone sees it.

- Often it leads to scarring, ankylosis, Marjolin's ulcer formation. Slough from the ulcer bed may give way causing venous haemorrhage.
- *Periostitis is common* which also prevents ulcer from healing.
- Most of the venous ulcers have surrounding lipodermatosclerosis. *Lipodermatosclerosis is pigmentation, thickening, chronic inflammation and induration of the skin in calf and around ankle.*
- Due to regular walking on toes so as to relieve the pain causes contraction and extra-articular fibrosis of achilles tendon. Proper exercise is the remedy for—*talipes equinovarus.*

Note:
70-80% of leg ulcers are venous ulcers.

Differential Diagnosis

- Ischaemic ulcer, diabetic ulcer.
- Rheumatoid ulcer.
- Traumatic ulcer.
- Neuropathic ulcer.
- Neoplastic ulcer.

Investigations

- Discharge from the ulcer for culture and sensitivity.
- X-ray of the area to look for periostitis.
- Biopsy from the ulcer edge to rule out Marjolin's ulcer.
- Investigations to rule out other causes of leg ulcers like arterial; neurological; diabetes; sickle cell disease and other haemolytic diseases.
- Erythrocyte sedimentation rate; C-reactive protein, peripheral smear; red cell counts.
- Doppler—venous and often arterial.

Treatment

- ***Bisgaard method*** of treating venous ulcer:
  - Measures to reduce oedema, increase venous drainage, so as to promote ulcer healing.
    - Elevation.
    - Massage of the indurated area and whole calf.
    - Passive and active exercise.
  - Care of ulcer by regular cleaning with povidone iodine, H_2O_2.
  - Dressing with EUSOL.
  - Four layer bandage (45 mmHg pressure) technique to achieve high compression pressure. It is changed once a week.
  - Antibiotics depending on culture and sensitivity of the discharge.

Different bandages used are:

- *Charing*—Cross (hospital London) elastic multilayered compression bandage, once a week
- Low compression bandaging
- Graduated elastic compression stockings with a leak proof absorbent dressing beneath
- Unna boots
- Crepe bandage/stockings

- Once ulcer bed granulates well, split skin graft (SSG) is placed *(Thiersch Graft),* or pinch graft.
- ***Specific treatment for varicose veins*** should be undertaken—Trendelenburg operation, stripping of veins, perforator ligation.
- Fifty percent of venous ulcer occurs as a result of recanalisation of DVT, and the leg is commonly called as ***postphlebitic limb (leg).*** It presents with all complications of venous diseases like eczema, ulceration, lipodermatosclerosis and venous ulcers. Here surgery for superficial varicose veins are contraindicated. Venous valve repair ***(Kistner's valvuloplasty)*** or *valve transplantation* or drugs like ***Stanazolol,*** which reduces the fibrous tissue thereby increasing the oxygenation are beneficial.



Fig. 1.467: Patient should wear stockings regularly in postoperative period for 3-6 months. It will reduce the recurrence rate and symptoms.



Fig. 1.468: Skin grafting over a venous ulcer after formation of healthy granulation tissue.

Complications of venous ulcers

- Haemorrhage
- Marjolin's ulcer (in unstable scar of long duration)
- Infection
- Talipes equinovarus
- Periostitis is common over the tibia
- Disability
- Calcification

(**EUSOL** is Edinburgh University solution of lime containing *boric acid, sodium hypochlorite, calcium hydroxide.)*

***Note*:**
- Present concept is to treat the ulcer first by compression bandage; regular dressing; skin grafting. Once ulcer has healed definitive procedure for varicose veins is done. Studies show that rapidity of healing of ulcer perse is not dependent on the surgery for varicose veins.
- Recurrence rate of venous ulcer after proper therapy is 30%. Reulcer formation is more in post-phlebitic/ thrombotic limb.

COMPRESSION THERAPY FOR VARICOSE VEINS

- Compression reduces the venous wall tension; prevents reflux; controls the venous over-distension.
- Compression diverts the blood towards deep veins through perforating veins; prevents the outward flow of blood in perforator incompetence; improves the efficacy of calf muscle pump. Compression reduces the oedema and improves the venous and lymphatic drainage; improves venous elasticity; improves the microcirculation and more important is it prevents further damage of the venous wall.
- Compression may be elastic/inelastic/combination of elastic and inelastic (*Unna boot*)/multilayered (four layered) compression system which can provide sustained high compression for several days—usually up to a week/intermittent pneumatic compression. *Unna boot* is three-layered paste gauze compression dressing containing calamine, zinc oxide, glycerin, sorbitol, gelatin and aluminium silicate which has mainly inelastic inner component with partly elastic outer layer wrap.
- Recommended pressure in mild varicose veins, pregnancy and postoperative period is 20 mmHg; in symptomatic varicose veins and after sclerotherapy is 30 mmHg; in venous ulcer and post-phlebitic leg it is 40-45 mmHg; in phlebolymphoedema (venous oedema with lymphatic oedema which is more dangerous) it is more than 45 mmHg.
- Skin maceration, excoriation, dryness, infection, ulceration and failure are the complications of compression therapy.

Fig. 1.469: Compression stockings should be worn in varicose vein disease even after intervention to reduce the chances of recurrence.

Remember

- Compression improves ulcer healing rate
- Supplementation of phlebotonic drugs in conjunction with compression therapy is accepted
- Inelastic compression causes more improvement (reduction) in venous filling index (VFI) than elastic compression. But elastic compression is more commonly used because it is better accepted
- Multilayered bandage system is most effective
- Ankle-arm pressure index less than 0.6 is contraindication for compression therapy as it may precipitate ischaemic ulcer formation
- Exercise may improve the muscle—pump action

Compression garments standard

British standard
- Class I: 14-17 mmHg
- Class II: 17-24 mmHg
- Class III: 24-35 mmHg

International (European) standard
- Class I: 20-30 mmHg
- Class II: 30-40 mmHg
- Class III: 40-50 mmHg
- Class IV: 50-60 mmHg

Compression Bandages

- *Type I*: Light weight confirming stretch bandages. These comprise light weight elastomer with high elasticity but little power. It is used to retain dressings.
- *Type II* (short stop): Light support bandages. Minimal stretch. Exhibit limited elasticity but tends to lock out on minimal extension. In ambulant patient CVI they form an essentially inelastic covering to the leg which will exert pressure during calf systole but not during diastole. They are unsuitable for control of oedema.
- *Type III* (Long stop): These are extensible elastic and powerful to a varying degree.

THROMBOPHLEBITIS

It is the inflammation of veins, usually superficial veins due to different causes. It is actually superficial vein thrombosis with inflammation (slight).



Fig. 1.470: Superficial thrombophlebitis with clot and infection.

Types

a. *Acute***:** Due to IV cannulation, trauma, minor infections, hypercoagulability.
b. Recurrent.
c. *Spontaneous:* Polycythaemia vera, polyarteritis, Buerger's disease.
d. *Thrombophlebitis migrans (Trousseau's sign, 1876*): It is spontaneous migrating thrombophlebitis seen in visceral malignancy like pancreas, stomach.
e. Mondor's disease.

Clinical Features

- Pain, redness, tenderness, cord like thickening of veins, fever.
- It can be seen either in upper limb or lower limb.

Complications

- Destruction of venous valves resulting in varicose veins.
- DVT, embolism, infection.

Treatment

- Elevation.
- Anti-inflammatory drugs, antibiotics.
- Application of crepe bandage.

KLIPPEL-TRENAUNY SYNDROME

It is a nonfamilial mesodermal anomaly with skin naevus, varicose veins, soft tissue and bone hypertrophy. Deep veins are often aplastic. It is usually managed with compression bandages. If patient is undergoing surgery for some other condition, then LMWH should be started. Condition itself occasionally can be treated with EVLA for varicose veins if only deep veins are normal; bone length discrepancy correction of leg is done.

Parkes Weber syndrome is a differential diagnosis. PW syndrome presents with varicose veins, multiple AV fistulas, chronic venous hypertension, high output cardiac failure and ulceration.

ANTICOAGULANTS

These are the agents used to prevent and treat thrombosis and thromboembolic events.

HEPARIN

- It is a natural anticoagulant, a mucopolysaccharide.
- It prevents clotting of blood both *in vivo* and *in vitro* by acting on all three stages of coagulation. It *prolongs clotting time* and *activated thromboplastin time* in specific (by 1.5-2.0 times the control).
- Heparin also causes hyperkalaemia, thrombocytopenia.
- Commercial heparin is derived from lung and intestinal mucosa of pigs and cattle.
- The onset of action is immediate after administration, lasting for 4 hours.
- It is metabolised in the liver by heparinase.
- It does not cross placental barrier and is not secreted in breast milk.

Indications

- As prophylaxis in major surgeries, postoperative period, puerperium.
- As therapy in DVT.

Dose

- For prophylaxis: 5,000 units/subcutaneously 8th hourly.
- For therapy: 10,000 units/IV 6th or 8th hourly. Later changed to subcutaneous dose.
- In severe cases, 5,000 units to 20,000 units is given daily through IV infusion at a rate of 1,000 units per hour. Daily dose should not exceed 25,000 units.

Heparin should not be given intramuscularly and should not be combined with streptokinase or urokinase. Heparin is not given orally.

Heparin administration should always be monitored with APTT.

Complications

Allergy, bleeding, thrombocytopenia.

Danaparoid is an antifactor Xa, heparinoid, is an anticoagulant used in patients where heparin is contraindicated.

LOW MOLECULAR WEIGHT HEPARIN (LMWH)

It is a commercially prepared heparin with a molecular weight of 4,000 to 6,500.

- Enoxaparin.
- Dalteparin.
- Parnaparin.
- Reviparin.
- Fraxiparin.

Advantages

- Have a longer duration of action—once a day
- Have a better anticoagulant effect
- Less interaction with platelets
- Less antigenic
- Usage is easier and more acceptable
- Monitoring is not necessary

Disadvantages

They are expensive.

Presently LMWH are becoming very popular.

Heparin antagonist: 50 mg of 1% protamine sulphate solution is given slow intravenous. 1 gm reverses 100 units of heparin. It is given only after doing activated thromboplastin time. Overdosing or infusion without indication may itself precipitate bleeding.

ORAL ANTICOAGULANTS

They are given orally and are slow acting.

Types

- *Coumarin derivatives*: Bishydroxycoumarin (Dicoumarol): First coumarin drug derived from sweet clover.
  Warfarin sodium: Most common oral anticoagulant used.
- *Indandione derivative*: Phenindione, anisindione.

Mode of Action of Oral Anticoagulant Therapy

- By suppressing synthesis of prothrombin, factors VII, IX and X.
- By inhibiting vitamin K mediated carboxylation of glutamic acid.
- Oral anticoagulant does not have *in vitro* action.
- They are slow acting, and long acting.
- Control of oral anticoagulant therapy is by *monitoring prothrombin time*.
- PT comes to normal only 7 days after cessation of the drug.
- *They cross placental barrier and are known to cause teratogenicity when given in 1st trimester.*
- *They are secreted in breast milk.*

Indications

- In DVT after cessation of heparin for maintenance therapy.
- After valve replacement surgery.

To achieve adequate anticoagulant effect and to prevent thromboembolic episodes the *INR* has to be maintained within 2-3.

Side Effects

- Bleeding—it may require blood transfusion/FFP or vitamin K injection intramuscular or oral to control.
- Cutaneous gangrene.
- Fetal haemorrhage and teratogenicity.
- Alopecia, urticaria, dermatitis.
- Drug interactions: with NSAIDS, cimetidine, omeprazole, metronidazole, cotrimoxazole, erythromycins, barbiturates, rifampicin, griseofulvin.

WARFARIN

WARFARIN (**W**iskonian **A**lumini **R**esearch **F**oundation + coum**ARIN** derivative) *SODIUM* is the most common drug used. It has got lesser side effects. It has got cumulative action and so given in tapering dose.

Dose is 5 mg, once a day.

It should be discontinued 7 days before any surgery like tooth extraction and prothrombin time should return to normal level. During surgery, if excess bleeding occurs, fresh frozen plasma may be given.

The effects of warfarin sodium is reversed by injection vitamin K; the dose depends on INR and emergency of reversal (takes 24 times to reverse).

IN VITRO ANTICOAGULANTS: Oxalates, citrates, EDTA (Ethylene diamine tetra-acetic acid).

Thrombolytic agents

- ❖ Streptokinase
- ❖ Urokinase
- ❖ Anistreplase
- ❖ Alteplase

Differences between oral anticoagulants and heparin

	Oral anticoagulant	***Heparin***
	Slow acting	Immediate
	Long acting	Short acting
	Only *in vivo* action	Both *in vitro* and *in vivo* action
Monitored by:	Prothrombin time	Partial thromboplastin time
	Crosses the placental barrier	Does not cross the placenta
	Secreted in milk	Not secreted in milk
Administration:	Orally	Intravenously/ subcutaneously

Contraindications for anticoagulant therapy

- ❖ Ongoing bleeding
- ❖ Recent surgery/invasive procedure
- ❖ Severe trauma
- ❖ Bleeding tendency (clotting factor deficiency)
- ❖ Intracranial haemorrhage
- ❖ Pericarditis/pericardial effusion
- ❖ Patient prone to fall

DIRECT THROMBIN INHIBITORS

a. Recombinant hirudin and hirudin analogues—derived from leeches, are direct inhibitors of thrombin.
b. Argatroban—synthetic direct thrombin inhibitor.

ANTIPLATELET DRUGS

- Small dose aspirin—inhibits platelet synthesis of thromboxane A2.
- Ticlopidine (125 mg BD)—alters platelet membrane, thereby platelet aggregation.
- Clopidogrel—action similar to ticlopidine.

If you have the best products, you won't need much advertising.

- Dextran—decreases platelet aggregation.
- Abciximab—glycoprotein IIb/IIIa inhibitors, block platelet aggregation, and platelet adhesion to fibrin.
- Dipyridamole—xanthine oxidase inhibitor.

PULMONARY EMBOLISM

- It is commonly due to lower limb DVT (15% of lower limb DVT). It can also occur after pelvic vein DVT or upper limb DVT (30% of upper limb DVT).
- Chest pain, cough, haemoptysis, dyspnoea are the features.
- Often site of DVT may be asymptomatic. When symptomatic, fever, pain, tense, tender calf, with positive Homan's sign may be evident.
- Massive embolism causes sudden cardiac arrest and death due to pulmonary artery block. Moderate embolism causes *pyramidal wedge shaped* infarcts in lungs.
- Duplex scan of limb, CT angiogram of thorax, pulmonary angiogram (gold standard), X-ray chest, ventilation perfusion scan, ECG, echocardiography are useful investigations.
- *Treatment* is thrombolysis, heparin/LMWH, compression bandage.
- Occasionally surgical removal of clot from pulmonary artery is done if possible.
- *IVC filter* placement is essential in recurrent DVT with anticoagulation, DVT with contraindication for anticoagulation, pulmonary hypertension. *Greenfield IVC filter* is ideal with 95% patency rate. *Complications* are—bleeding, haematoma, migration of filter into pulmonary artery, thrombosis at filter level, IVC perforation.
- *Retrievable IVC filters* are newer method used to prevent long-term filter complications. It is used in young patients who are at risk of DVT and embolism, for short specified period only like—high-risk trauma with orthopaedic injuries, extensive iliofemoral thrombosis, during thrombolytic therapy. *Recovery filter, Gunthur-Tulip filter, OptEase filters* are used. They are deployed through IJV or femoral vein under angiographic or intravascular US guidance. Recovery and Gunthur-Tulip types are recovered through right IJV. OptEase is recovered from right femoral vein. *Complications* are same as nonretrievable IVC filters. Retrieval failure, retrieval site thrombosis and embolism are specific complications.
- DVT prophylaxis is a must in all these patients.

O. Lymphatics

CHAPTER OUTLINE

- Surgical Anatomy
- Lymphangiography
- Isotope Lymphoscintigraphy
- Lymphoedema
- Lymphomas
  - Hodgkin's Lymphoma
  - Non-Hodgkin's Lymphoma
- MALT Lymphomas
- Burkitt's Lymphoma
- Cutaneous T Cell Lymphoma
- Chylous Ascites
- Chylothorax
- Chyluria
- Sarcoidosis

SURGICAL ANATOMY

Primordial lymphatic system begins to develop during 6th week of development adjacent to jugular vein as lymph sacs. Peripheral lymphatic systems develop from these primordial lymph sacs. Lymphatic system has three components. *Terminal lymphatic capillaries,* which have high porosity absorb lymph, macromolecules, cells and microbes from tissues into the system*; lymphatic vessels* which collect and transport lymph; *lymph nodes* which are interposed in the lymphatic pathway filter lymph and maintain immunity of the body. Lymphatic vessels run adjacent to main blood vessels reaching the major lymphatic channels. *Cisterna chyli* is formed in the abdomen, continues as thoracic duct (formed at 9th week of gestation) in the thorax which has got initial main course towards right side of the mediastinum; but later towards left side entering the internal jugular vein at its joining point of the subclavian vein. In the periphery there is hardly any lymphovenous communications. Lymphovenous communications occur at lymph node level; iliac, subclavian and jugular levels. Lymphatics are absent in epidermis, cornea, CNS, cartilage, tendon and muscle.

Great lymph ducts are—the thoracic duct—single; right lymph duct—single; subclavian, bronchomediastinal and jugular trunks on both sides. These ducts contain valves to prevent backflow.

Cisterna chyli is formed by joining of right and left lumbar lymphatic trunks and intestinal lymphatic duct. Lumbar trunks are short lymph vessels arising from para-aortic lymph glands. It receives lymph from lower limb, pelvis and pelvic viscera, kidney, adrenal and deep lymphatics of abdominal wall. Left lumbar trunk is behind the aorta. Intestinal lymph duct arises from preaortic nodes. It joins the cisterna chyli from front. It receives lymph from stomach, intestines, liver (except most convex surface which drains into right lymph duct), spleen and pancreas. Cisterna chyli is a lymph sac lying in front of the L_1 and L_2 vertebrae between aorta and crus of the diaphragm. From its upper end it continues as thoracic duct. *Thoracic duct* passes through the aortic orifice of the diaphragm, runs medial to azygos vein and right of the aorta in posterior mediastinum. In front it is related to oesophagus, diaphragm and pericardium; behind right intercostal arteries, hemiazygos and accessory hemiazygos vein. At the level of 7th thoracic vertebra it crosses towards left side behind the oesophagus obliquely reaching left side at 5th thoracic vertebral level. It runs upwards between left margin of oesophagus, medial part of left pleura, and behind left subclavian artery. In the neck it passes in front of vertebral system (vertebral vessels and sympathetic chain) and behind carotid system (Common carotid artery, internal jugular vein, vagus nerve), crossing scalenus anterior, phrenic nerve, transverse cervical and suprascapular arteries ending as a single vessel at the junction of internal jugular vein and subclavian vein with a valve. *Tributaries of thoracic duct* are—trunk from lateral intercostal nodes from lower six spaces; efferents from posterior mediastinal nodes, lateral intercostal nodes of upper six spaces, left jugular lymph trunk from head and neck region, left subclavian lymph trunk from left upper limb, left bronchomediastinal trunk from left side of the thorax. Single termination of duct is common (77%); but double/triple/quadruple terminations are known to occur. Occasionally it may end in left subclavian vein, left vertebral vein, right internal jugular vein, right subclavian vein. Thoracic duct is 45 cm in length and 5 mm wide (wider at both ends; narrow in the middle).

Right lymph duct is 2.5 cm in length, formed by right jugular, right subclavian and right bronchomediastinal trunks; runs on the scalenus anterior joining the junction of right internal jugular vein and subclavian vein.

There are about total 450-600 lymph nodes in the body. Around 200 in the neck; around 100 in the thorax; around 50-60 in the axilla; around 250 in the abdomen and pelvis; around 50 in the groin area.

Lymphatic Watersheds of Skin

Lymph from the dermis and appendages drain into a plexus in deep fascia which in turn drains into respective lymph nodes. *There are six watershed areas in the body for lymphatic drainage*. One vertical midline divides into right and left. Two horizontal lines on each side divide the area into three zones. First lies above the line of clavicle; second between line of clavicle and line at umbilical level; third below the level of umbilical line. First drains into head and neck lymph nodes; second drains into axillary nodes; third drains into inguinal/

In very early oedema, during pinching, there is a resistance that is not present on normal site, owing to thickening of dermis and subcutaneous tissue.

—Sidney S Rose


C7
Left CCA
Left IJV
Left subclavian vein
Valve
Thoracic duct
Oesophagus
T5
T6
T7
Accessory hemiazygos vein–T8
Azygos vein
Hemiazygos vein–T9
Descending thoracic aorta
Crus of the diaphragm
L1
L2
Cisterna chyli
Left lumbar lymph trunk
Intestinal lymph trunk
Right lumbar lymph trunk
Para-aortic nodes
Pre-aortic nodes
IVC
Abdominal aorta

Fig. 1.471: Thoracic duct anatomy; cisterna chyli; tributaries of thoracic duct.


Vertical sagittal line
Right lymphatic duct
Clavicular watershed line (Above this line drains into neck nodes)
Between clavicular and umbilical lines drainage occurs to axillary nodes
Umbilical level watershed line
Entire lower limb and one side of the perineum up to umbilical line drains into groin lymph nodes
Cervical nodes
Thoracic duct
Mediastinal nodes
Axillary nodes
Cysterna chyli
Pre and para-aortic nodes
Epitrochlear nodes
Iliac nodes
Groin nodes (Inguinal)
Popliteal nodes

Fig. 1.472: *Watershed zones/areas of lymphatic drainage*. Vertical sagittal midline; clavicular horizontal line; umbilical line—are used to divide areas into three zones on each side. Above clavicular line drainage occurs to cervical nodes; between clavicular line and umbilical line drainage occurs into axillary nodes; below umbilical line drainage occurs to inguinal lymph nodes. At the level of (lines) drainage can occur to lymph nodes on either side.

groin nodes. Malignancy drains into their respective nodes depending on the location. Lesion on the line can spread to both territory lymph nodes. In skin and appendageal cancers, deep fascia also should be cleared.

Microanatomy of Lymph Node

Lymph node contains three regions—*cortex; paracortex and medulla*. Cortex contains mainly follicles. It may be rounded lymphocytic aggregations of primary follicles or lymphocytic aggregation with germinal centres of secondary follicles due to antigenic stimulation. It contains B lymphocytes, macrophages, dendritic reticulum cells. Germinal centre is surrounded by small B lymphocytes. Both cortex and medulla are associated with humoral immunity. Proliferation of germinal centres suggests active humoral immunity with antibody production. Central medulla contains mainly lymphatic sinuses, arteries and veins, plasma cell and B lymphocytes. Paracortex is located in a zone between cortex and medulla. It contains T lymphocytes, related to cell mediated immunity. Post-capillary venules with high endothelial cells and lymphocytes in the wall are typical. In cell mediated immunity, paracotex expansion occurs. Afferent lymph vessels enter the node through the capsule. It enters the marginal sinus, communicates with intranodal sinus, merging as efferent lymph vessels which enter the hilum. Intranodal sinus lining is highly phagocytic containing littoral cells and sinus lining histiocytes. Main artery and veins pass through the hilum to enter the medulla, paracortex and inner part of cortex. Superficial cortex is supplied by direct capsular vessels.

Function of Lymphatics

Most of the *intravascular proteins are daily filtered through lymphatics* and returned to the circulation again. Macromolecules (albumin, globulin and fibrinogen) and microbes are also filtered at the nodal level as first immune system. From GIT fat is absorbed directly through lymphatics. Lymph shows centripetal flow. Cholesterol, long chain fatty acids, fat soluble vitamins are transferred through lymphatics into cistern chyli directly from GIT bypassing the liver. Transport is mainly due *to intrinsic contractility of the lymphatic vessels* which contain valves for effective forward flow. To a lesser extent other factors like muscle contraction, arterial pressure, thoracic pressure, respiratory movements play role. *8 litres of lymph is produced daily; once it reaches to lymph nodes it is concentrated to 4 litres which* enters the venous circulation. *Protein concentration in lymph is very high (25 grams/litre)*.



Fig. 1.473: Acute lymphangitis leg. Usually regional lymph nodes are enlarged and tender.

LYMPHANGIOGRAPHY

Indications

- Congenital lymphoedema like aplasia, hypoplasia, hyperplasia.
- Lymphomas show *reticular* pattern. It is also useful to assess the response to treatment.
- Secondaries in lymph nodes, especially iliac and para-aortic lymph nodes.

Technique

Patent blue dye or 1 ml isosulphan blue is injected subcutaneously between toes. Dye is taken up by lymphatics which will be visualised clearly. After making incision, one of the lymphatic vessels is dissected and 30 G needle is passed. Ultra-fluid lipiodol which is an oily contrast medium is injected slowly using pressure pump at a rate of 1 ml in 8 minutes (total quantity is 7 ml). Slowly in 24 hours, it passes through the lymphatics and reaches the iliac and para-aortic lymph nodes. Radiographs taken will help to visualise both lymphatic vessels as well as lymph nodes.

Secondaries in lymph nodes causes filling defects. Lymphomas shows enlarged nodes which have foamy or reticular appearance.

Disadvantages

- Technically difficult.
- Extravasation of dye can occur.
- Dye may not reach the required area.
- Time consuming and invasive procedure.

Lymphangiographic classification of lymphoedema **(Browse classification):** (Norman Browse)

- *Congenital hyperplasia (10%):* Congenital; common in males; entire leg is involved; one or both sides; with often family history; progressive; involves increased number of lymphatics and lymph nodes associated with chylous ascites, chylothorax and protein losing enteropathy
- *Distal obliteration (80%):* Common in females; starts at puberty; calf and ankle are involved; often bilateral; with often family history; slow progression; aplasia/hypoplasia of lymphatics
- *Proximal obliteration (10%):* Occurs at any age; equal in both sexes; leg and thigh involved; unilateral; rapid progression; proximal aortoiliac nodal block

ISOTOPE LYMPHOSCINTIGRAPHY

- Radioactive technetium labelled sulphide colloid particles, or radioiodinated human albumin are injected into the web space using fine needle. These particles are specifically taken up by lymphatics.
- Using gamma camera, limb and inguinal region is exposed to visualise the lymphatics and inguinal lymph nodes.
- Radioactivity in inguinal nodes is measured at 30 and 60 minutes. Normal uptake is 0.6-1.6%; if it is < 0.3% in 30 minutes it is diagnostic of lymphoedema. If it is > 2% it suggests rapid abnormal clearance due to oedema as the result of venous disease.
- In 3 hours, it reaches the para-aortic lymph nodes, other abdominal lymph nodes and liver.
- Later thoracic duct also can be visualised. It can be compared to the take up on the other limb.

Advantages

- It is more sensitive.
- Technically easier and faster compared to lymphangiography.
- Thoracic duct, other lymph nodes and liver can be visualised.
- It is the test of choice. It is simple and safe.
- It has 90% sensitivity; 100% specificity.

LYMPHOEDEMA

It is accumulation of fluid (lymph) in extracellular and extravascular fluid compartment, commonly in subcutaneous tissue. It is primarily due to defective lymphatic drainage.

It is *increased* protein rich interstitial fluid.

Classification

Kinmonth classified lymphoedema as:

- Primary without any identifiable lymphatic disease.
- Secondary is acquired due to definitive cause. ***Most common form.***

Primary type

It affects commonly females.

- It is common in lower limb and left side.

It can be:

- Familial
- Syndromic (Turner's / Klinefelter's / Down's / Klipple Trenauny Weber)

It can be:

- Lymphoedema congenital (10%) — Present at birth—< 2 years — Familial type is called as ***Nonne-Milroy's disease.*** It is type I familial, autosomal dominant—chromosome 5 related; bilateral upper and lower limbs, genitalia and face may be involved. Incidence is 1:6000 of live births.
- Lymphoedema praecox — Present at puberty—up to 2-35 years (80%). — Familial type is called as ***Letessier-Meige's syndrome.*** It is type II familial. It occurs between puberty and middle age.
- Lymphoedema tarda — Present in adult life—after 35 years

It can be radiologically (lymphangiography):

- Hypoplasia 70%
- Aplasia 15%
- Hyperplasia (varicose lymphatics) 15%

Pathophysiology of Lymphoedema

Decreased lymphatic contractility, lymphatic valvular insufficiency, lymphatic obliteration by infection, tumour or surgery causes all effects and pathology of lymphoedema. This leads to lymphatic hypertension and dilatation causing lymph stasis, accumulation of proteins, glycosamines, growth factors, and bacteria. There is more collagen formation, deposition of proteins, fibroblasts, ground substance causing fibrosis in subcutaneous and outside deep fascia. Muscles are normal *without* any oedema but may get *hypertrophied*.


Fig. 1.474: Right side congenital limphoedema in a girl.


Fig. 1.475: Early lymphoedema left side—pitting type.


Fig. 1.476: Late lymphoedema—grade 2.


Fig. 1.477: Lymphoedema leg extending into the thigh with lymphangitis.



Figs 1.478A to D: Lymphoedema foot in different patients—severe with vesicles/oedema/skin changes/fissures.

Causes of secondary lymphoedema

- Trauma
- Surgery—inguinal block or axillary block dissection/post-mastectomy with axillary clearance
- Filarial lymphoedema due to *Wuchereria bancrofti*—common cause in coastal region
- Tuberculosis
- Syphilis
- Fungal infection
- Advanced malignancy—hard, fixed lymph nodes in axilla or in inguinal region
- Postradiotherapy lymphoedema
- Bacterial infection
- Rare causes: Rheumatoid arthritis, snake and insect bites, DVT, chronic venous insufficiency

Note:
Secondary lymphoedema develops rapidly.

Filariasis

It is caused by a parasite *Wuchereria (Brazil) bancrofti (Australia*). It was also called as Malabar leg in 1709, by Clarke, Cochin. Female adult worm is longer 7-10 cm than male worm (4 cm). *Microfilaria* is colourless, translucent, 300 µ length and 10 µ thick. It has head, body and tail. Microfilaria circulates in blood. In India, Asian countries and China they show nocturnal periodicity (from 10 PM to 4 AM). It is related to night biting habits of the vector, *Culex fatigans* mosquito and sleeping habits of the host.

Man is the definitive host; animal or reservoir host is not known. *Female mosquito* is intermediate host (in India and China—Culex fatigans). Development or multiplication of microfilaria will never occur in human blood. Life span of microfilaria in human blood is 3 months. Microfilaria is infective to female mosquito. A density of 15 microfilaria/drop of blood are needed to make it infective.

Life Cycle

Microfilaria from carrier human blood → enters the stomach of female Culex mosquito when it bites human carrying the parasite in blood → ex-sheathing of microfilaria in stomach of mosquito in 6 hours → penetrate the stomach wall → migrate to thoracic muscles of mosquito in 12 hours → metamorphosis into sausage shaped first stage larva in 48 hours → second stage larva in one week → elongated actively motile *third stage infective larva* in one more week (one microfilaria forms one infective larva; microfilaria never multiplies in mosquito nor in human) → enters the proboscis of mosquito to become infective to human during the mosquito bite; it takes 20 days for microfilaria to develop into infective 3rd stage larva in mosquito [*extrinsic incubation period*]→ enters human skin while biting → many larvae get destroyed in human skin by immunity, few enters lymphatics → enters regional lymph nodes in inguinal or axillary or abdominal nodes → develop into adult worm in lymph nodes → mating of female and male worms takes place → gravid female worm releases up to 50,000 microfilariae/day into lymph circulation → thoracic duct → subclavian vein → microfilaria in human circulation → infective to female mosquito. Time from 3rd stage infective larva entering human skin and forming adult worm and later releasing microfilaria into blood is called as *biological incubation period* (12 months); time from 3rd stage infective larva entering human skin to appearance of first clinical feature is called as *clinical incubation period* (16 months).

Effects of Wuchereria Bancrofti Infection

- *Carrier stage* having circulating microfilaria but *asymptomatic.*
- *Immune and allergic reactions* by adult worm causing macrophage and lymphocyte infiltration, endothelial hyperplasia, lymphatic vessel wall thickening, lymph stasis, dilatation, further reaction, fibrosis, further blockage, calcification, recurrent streptococcal infection, filarial lymphoedema.
- *Filarial fever, utricaria, pruritus, epididymo-orchitis as acute* presentation.
- *Occult filariasis* where microfilaria is not demonstrable in blood but identified in lungs (by biopsy confirmation) causing eosinophilia, bronchospasm, nocturnal cough, fever, wheeze, weight loss, arthritis, thrombophlebitis, tenosynovitis.
- *Lymphadenitis, lymphangitis*.
- *Lymphangiovarix, lymphorrhagia, lymph scrotum, lymphocele,* chyluria, chylous diarrhoea, retroperitoneal lymphangitis, chylous ascites, chylothorax.
- *Blood smear—night time (thick and thin)*, lymph node biopsy, skin test, eosinophilia, serological tests, DEC provocation test (by giving 100 mg DEC) *are different investigations*.

Pathology *(Commonly in Filarial Lymphoedema)*

Recurrent lymphangitis causes obliteration of lymph vessels
↓
Dermal lymphatic backflow
↓
Retrograde obliteration (or die back of lymphatics)
↓
Oedema, initially pitting but later nonpitting
↓
Recurrent cellulitis—thickening of skin
↓
Accumulation of proteins, growth factor, glycosaminoglycans
↓
Activation of collagens and keratinocytes
↓
Protein rich lymphoedematous tissue formation
↓
Deposition of ground substance, subdermal fibrosis
↓
Dermal thickening and dermal proliferation, Fissuring → Cracks—Ulceration—Abscess formation
↓
Stout leg with unbearable weight
↓
Elephantiasis.

Rarely it causes protein losing diarrhoea, chylous ascites, chylothorax, chyluria, lymphorrhoea. Recurrent lymphadenitis occurs in the region which aggravate the condition.

Disease in the limb is confined to skin and subcutaneous tissue, i.e. often, only superficial lymphatics are involved by the disease, deep lymphatics are not. *Superficial and deep lymphatics are not communicating* with each other (Unlike the veins in the limb where superficial and deep veins are freely communicating with each other).

Sites of lymphoedema

- Lower limb—most common
- Upper limb
- Scrotum, penis (Ram's horn penis)
- Breast—requires reduction mammoplasty
- Labia
- Eyelid
- Localised lymphoedema

Clinical Features

- Swelling in the foot, extending progressively in the leg—*tree trunk* pattern leg.
- Loss of normal perimalleolar shape—*tree trunk pattern* leg.
- *Buffalo hump* in the dorsum of the foot.
- Squaring of toes.
- Skin over the dorsum of foot cannot be pinched because of subcutaneous fibrosis—*Stemmer's sign.*
- Initially pitting oedema occurs, which later becomes nonpitting.
- Dull ache/severe pain/burning/bursting/cramps; 50% patients will have pain.
- Debility/immobility/obesity/muscle wasting.
- Athlete's foot with joint pain and disability.
- Eczema, fissuring, papillae formation, ulceration, lymph ooze, elephantiasis are other features.
- Fever, malaise, headache.
- Recurrent abscess formation.
- Psychological and social discomfort causing severe morbidity.
- *Endemic elephantiasis/podoconiosis* is common in Africa; seen in barefoot workers; due to destruction of lymphatics by silica derived from soil containing alkaline volcanic rocks.



Fig. 1.479: Ram's horn penis.



Fig. 1.480: Typical elephantiasis leg with late lymphoedema.

Brunner's grading of lymphoedema

Latent—subclinical: No clinically apparent lymphoedema.	
Grade I	Pitting oedema which more or less disappears on elevation of the limb—is due to excess deposition of interstitial fluid
Grade II	Nonpitting oedema occurs which does not reduce on elevation
Grade III	Oedema with irreversible skin changes like fibrosis, papillae, fissuring

Lymphoedema can be:

- *Mild* lymphoedema—< 20% of excess limb volume.
- *Moderate* lymphoedema—20-40%.
- *Severe* lymphoedema—> 40%.

Differential Diagnosis

- Cardiac causes, hypoproteinaemia, malnutrition, nephrotic syndrome, liver failure.
- Myxoedema.
- Trauma.
- Venous diseases like DVT.
- Lipodystrophy and lipoidosis (lipoedema). Lipoedema occurs exclusively in females; begins in puberty; bilateral and symmetrical; trunk may be involved; feet are not involved; not pitting; not related to elevation/compression; MRI shows only fat without fluid.
- Arterial diseases including AV malformations.
- Gigantism.
- Drug induced—steroids, estrogens, nifedipine.
- External compression of veins as caused by abdominal tumours.

Investigations

- For the cause.
- ESR, peripheral smear.
- Lymphangiography.
- Isotope-lymphoscintigraphy.
- MRI, CT scan to identify the cause.



Figs 1.481A to C: Different lymphoedema pictures. Note the oedema, fissuring, cracks. All these make it more vulnerable for infection.



Fig. 1.482: Lymphoedema of lower limb developed after ilioinguinal block dissection for nodal secondaries from melanoma.



Fig. 1.483: Recurrent filarial leg with nodules and ulceration.



Fig. 1.484: Extensive scrotal lymphoedema of filarial origin. Patient underwent scrotal reduction.



Figs 1.485: Lymphoedema right arm and forearm. Common causes for upper limb lymphoedema are filarial and post-mastectomy with axillary nodal clearance.

Indecisive people are like a blind man looking in a dark room for a black cat that isn't there.



Figs 1.486A and B: Lymphoedema of penis. It needs reduction and reconstruction otherwise it may cause urinary problem and sexual dysfunction.

Complications

- Skin thickening, abscess and maggot's formation.
- Recurrent cellulitis, nonhealing ulcers, septicaemia.



Fig. 1.487: Severe lymphoedema foot with vesicles and thickening.

- Lymphangiosarcoma; *Stewart Treves syndrome* (0.5%, occurs after 10 years), which presents as multiple bluish satellite nodules in the skin of the limb often with ulceration and haemorrhage. Skin/nodule biopsy is confirmative. Chemotherapy, radiotherapy, later even though radical amputation is the treatment, it carries very poor prognosis. This syndrome is usually seen in *upper limb after mastectomy*.
- Recurrent streptococcal infection.

Treatment

Conservative

a. Elevation of the limb, exercise, weight reduction.
b. Static isometric activities like prolonged standing or carrying weights should be avoided; rhythmic isotonic movements like swimming/massaging should be encouraged.
c. Diuretics to reduce the oedema is controversial. It more often causes eletrolyte imbalance than being beneficial.
d. Benzopyrones are protienolytic agents/*lympedim.* They are coumarin (I, 2 benzopyrones) derivatives with no anticoagulant effect but increase the lymphatic peristalsis and pumping mechanism along with proteolysis.
e. Daily wearing of below knee stockings.
f. Avoid trauma and infection.
g. Intermittent pneumatic compression devices (Pressure > 50 mmHg); multilayered lymphoedema bandaging (MLLB)—nonelastic type is preferred method; graded stockings.
h. Antibiotics—flucloxacillin, erythromycin, long acting penicillins.
i. Topical antifungal 1% clotrimazole and systemic griseofulvin 250-1000 mg.
j. Regular washing and keeping the limb clean is very important.
k. Diethyl carbamazine citrate (DEC) 100 mg TID for 3 weeks.
l. Pain relief—by suitable means.
m. Skin care:
    - Keratolytics like salicylic acid 5%; bland emollient; soft/liquid paraffin.
    - Avoidance of skin sensitisers like some soaps.
    - Topical steroids.
    - Control of allergy.
    - Control of fungal infection by drugs like fluconazole.
    - 3% benzoic acid ointment to prevent Athlete's foot.
    - Control of lymphorrhoea.
    - Prevention/control of skin infections.
n. **Complex decongestive therapy** is a comprehensive two phase program of elevation, exercise, massaging, and compression wraps. First phase is *intensive therapy* and second phase is *maintenance therapy*.

    Compression wraps may be high stretch wraps or low stretch wraps. Low stretch wraps are better accepted. It should be worn initially for 24 hours. Compression wraps are used in initial intensive phase of therapy. *Graduated elastic compression garments* are used in maintenance phase which provides maximum pressure of 50 mmHg at the distal part with gradual reduction of pressure in proximal portion.

    Manual lymphatic drainage is a specialised technique to stimulate the contractility of lymph collecting vessels and enhance fluid and protein transport by gentle, light, superficial massaging of the skin so as to open up new lymphatic vessels. Technique is done first on the opposite normal side; then trunk, same side trunk; same side proximal; same side distal and later same side distal to proximal fashion, so as to redirect the lymph towards functioning lymphatic territories.

Surgery

Surgeries for lymphoedema has been classified as:

a. *Excisional*
  - Charle's operation.
  - Homan's operation.

b. *Physiological*
  - Omentoplasty.
  - Nodovenous shunt (Neibulowitz).
  - Lymphovenous shunt (O'Brien's).
  - Ileal mucosal patch.

  Here either communication between superficial and deep lymphatics are created or new lymphatic channels are mobilised to the site.

  Omentoplasty (Omental pedicle): As omentum contains plenty of lymphatics, omental transfer with pedicle will facilitate lymph drainage.

c. *Combined:* Both excision + creation of communication between superficial and deep lymphatics.
  - Sistrunk operation.



Before Charle's operation After Charle's operation

Fig. 1.488: *Charle's excisional surgery*. Here after excising lymphoedematous tissue, area is covered with skin graft.



Fig. 1.489: *Thompson's Swiss-roll operation*. Here after removal of lymphoedematous tissue, deep fascia is opened to expose the muscle. Epidermis abraded using skin graft knife. This shaved dermis is buried into the muscle to get communication into the deeper lymphatics.

  - Thompson's operation.
  - Kondolean's operation.

d. *Bypass procedure*:
  - *Handley's* (1908) silk threads/nylon threads/perforated polyethylene tubes placement as burial from ankle to mid-abdominal level, kept for one year. Procedure is only of historical interest.
  - Skin bridge across the thigh and abdomen (Gillies).
  - Nodovenous shunt.
  - Lymphovenous shunt using microscope.
  - Ileal mucosal patch (Kinmonth). Segment of ileum with pedicle is isolated and opened to expose the mucosa; mucosa is denuded and this mucosa is placed in the thigh as burial to communicate with lymphatics to drain into abdominal lymphatics across ileum.
  - Baumeister lymphatic grafting.
  - Autotransplantation of free lymphatic flap from opposite side—done in post-mastectomy lymphoedema (Trevidic and Cormier).

e. *Limb reduction surgeries*:
  - ***Sistrunk operation:*** Along with excision of lymphoedematous tissue, window cuts in deep fascia is done, so as to allow communication into normal deep lymphatics.
  - ***Homan's operation:*** Excision of lymphoedematous tissue is done after raising skin flaps. Later skin flaps are trimmed to required size and sutured primarily. Medial and lateral sides of the limb are done at separate sittings with 6 months interval.
  - ***Thompson's operation:*** Lymphoedematous tissue is excised under the skin flaps. Epidermis and part of



Fig. 1.490: Diagram showing right side groin nodovenous shunt between iguinal lymph node and long saphenous vein. Left side showing lymphovenous shunts between dilated lymphatics and long saphenous vein. At least 4 lymphatics should be anastomosed using 7 zero/11 zero prolene—using operative microscope.



Figs 1.491A and B: *Believe it or not!* Severe scrotal lymphoedema reaching almost up to feet; after surgical excision it weighed 40 kg; postoperatively patient went home with – 40 kg weight (*Courtesy:* Professor Shivananda Prabhu, MS, KMC, Mangalore).

the dermis of one of the skin flaps is shaved off using Humby's knife. It is buried under opposite flap, deep to the deep fascia like a *swiss roll (Swiss roll operation* or *buried dermal flap operation).*

Problems here are formation of epidermal cysts and sinus.

- ***Kondolean's operation:*** Along with excision of lymphoedematous tissue, vertical strips of deep fascia is removed so as to open the deep lymphatics which creates communication between superficial and deep lymphatics.
- ***Macey's operation:*** Here skin and subcutaneous tissue are peeled back with deep fascia and split skin grafting is done over the denuded area. Overlying pad of tissue is sutured back temporarily and after 10 days, it is trimmed away.
- ***Miller's procedure*:** It is excision of subcutaneous tissues under the skin flap with deep fascia in two stages. First stage is done over the medial aspect of the limb; second stage done after two months over lateral aspect of the limb.
- ***Charle's (1912) operation*:** Done in severe lymphoedema with elephantiasis. Along with excision of lymphoedematous tissue, skin grafting is done. It reduces the size and weight of the limb. Patient becomes ambulatory. Wound sepsis, graft failure, dermatitis, hyperkeratosis are the complications.
- Reduction surgeries are done for lymphoedema of scrotum, penis, labia and eyelid.

In severe type, occasionally amputation may be required.

LYMPHOMAS

They are progressive neoplastic condition of lymphoreticular system arising from stem cells.

Lymphomas are the 3rd most common malignancy among children comprising 15% of paediatric cancers.

Aetiology

- Genetic predisposition.
- Sjogren's syndrome—30 fold increase of NHL.
- HIV infection.
- Wiskott—Aldrich syndrome.
- Ataxia—telangiectasia.
- Bloom's syndrome.
- Virus etiology—Epstein-Barr virus.
- Celiac sprue—intestinal T cell lymphoma.
- *H. pylori* may be associated with MALT lymphoma.
- Occupation causes—hair dye workers; herbicide exposure.
- Ionising radiation.
- Smoking; alcohol consumption; tobacco usage.
- Lymphomas are more common in western countries than in Asia.

Types

- *Hodgkin's lymphoma (HL).*
- *Non-Hodgkin's lymphoma (NHL).*



Fig. 1.492: Enlarged, B/L, rubbery neck LNs of lymphoma. Note the involvement of lacrimal sac.



Figs 1.493A and B: Stage IV lymphoma with neck nodes/sternal swelling/axillary nodes which has ulcerated (ulceration is not common in lymphoma).

WHO modified **REAL** classification (**R**evised **E**uropean **A**merican **L**ymphoma) of lymphoma:

- B-cell neoplasms
  - Precursor B cell neoplasm—ALL, LBL.
  - Peripheral B cell neoplasm—it includes all B cell related non-Hodgkin's lymphomas
- T-cell and putative NK cell neoplasms
  - Precursor T cell neoplasms—ALL and LBL T cell related
  - Peripheral T cell and NK cell neoplasm—it includes all T cell related non-Hodgkin's lymphomas
- Hodgkin's lymphoma
  - Predominant HL—nodular lymphocyte type
  - Classical HL
    - Nodular sclerosis
    - Lymphocyte rich
    - Mixed cellularity
    - Lymphocyte depletion

Note: ALL is acute lymphoblastic leukaemia. LBL is lymphoblastic lymphoma.

Older Classifications (Not practiced now)

- Jackson and Parker (1944): Paragranuloma; granuloma; sarcoma.
- Lukes and Butler (1966): Lymphocytic and histiocytic nodular; lymphocytic and histiocytic diffuse; nodular sclerosis; mixed cellularity; diffuse fibrosis; reticular.

HODGKIN'S LYMPHOMA (HL)

> *(The lymph glands of the neck) exhibited a firm cartilaginous structure of a light colour and very feeble vascularity, but with no appearance of softening or suppuration. Glands similarly affected accompanied the vessels into the chest, where the bronchial and mediastinal glands were in the same state and greatly enlarged…. The spleen was enlarged to at least four times its natural size… presenting the same structure as the enlarged glands.*
>
> —**Thomas Hodgkin,** 1832

- It is the most common type of lymphoma.
- Infectious mononucleosis, Epstein-Barr virus, HIV infection and genetic monoclonal B cell disorder (90%) may be the aetiologies.
- Grossly lymph nodes are fleshy, pinkish grey, and rubbery in consistency.
- Microscopically contains cellular infiltration with lymphocytes, reticulum cells, histiocytes, fibrous tissue and ***Reed-Sternberg*** cells: (Reed-Sternberg cells are *giant cells with two large mirror image nuclei)*.

Rye's classification

- Lymphocytic predominance. Has got *good prognosis*
- Mixed cellularity
- Nodular sclerosis
- Lymphocytic depletion. Has got *poor prognosis*

(Reed-Sternberg cells are also seen occasionally in certain other conditions like glandular fever).

Clinical Features

- It is more common in males.
- It has got bimodal presentation. It is seen in young and adolescents (20-30 years) as well as in elderly (> 50 years).
- Painless progressive enlargement of lymph nodes. They are smooth, firm, nontender, typically *India rubber* consistency.

Site

- Cervical lymph nodes most common—82% (lower deep cervical group and in posterior triangle).
- Others include axillary, mediastinal, inguinal, abdominal.

Specific Features

- Nodular sclerosis is most common type.
- Consecutive group of lymph nodes are involved.
- *Splenomegaly* is very common (45%).
- Hepatomegaly with jaundice—jaundice is due to haemolysis or due to diffuse liver involvement.

The difference between ordinary and extraordinary is that little extra.—**Zig Ziglar**



Figs 1.494A and B: Lymphoma in a boy and in an adolescent with neck nodes. Note the diffuse nature. Nodes are usually *India rubber* consistency.

- *Para-aortic lymph nodes* may be enlarged and often palpable as vertically placed mass at or just left of the midline, which does not move with respiration, does not fall forward, nonmobile, resonant, smooth, firm mass often with transmitted pulsation from aorta (secondaries are hard, nodular usually primary from GI, melanoma, testis). Ascites is not a common feature.
- Rarely alcohol may induce pain in enlarged node; classical *Pel Ebstein fever* described early is also seen in other infections like brucellosis.
- *Constitutional symptoms like fever, pruritus, weight loss may be present which signifies stage "B", which has got poor prognosis. Stage "A" is absence of these symptoms which signifies better prognosis.*

Stage 'B' Symptoms

- Weight loss, more than 10% in 6 months.
- Fever, earlier called as *Pel Ebstein fever* is actually is due to brucellosis.



Fig. 1.495: Hodgkin's lymphoma in neck region.



Figs 1.496A and B: Fungating lymphoma in both axilla of a patient.

- Pruritus—25%. It may be the only presenting symptom. It is usually seen in nodular sclerosis type.
- Anaemia.
- Bone pain.

- Mediastinal lymph node involvement may cause compression features like SVC obstruction. Mediastinal lymphoma is the most common mediastinal malignancy which usually occurs in *anterior* mediastinum. Occasionally presentation may be difficulty in breathing, chest pain, dysphagia and SVC obstruction (*Pemberton's sign may be positive*). It may be asymptomatic also. If ratio between maximum transverse diameter of mediastinal mass to maximum transverse intrathoracic diameter *(MMR)* is more than 0.33 in chest X-ray or more than 0.35 in CT chest, then it carries worst prognosis.
- Occasionally bone like vertebrae may get involved.
- Anaemia, pancytopaenia.

Ann-Arbor clinical staging

Stage 1: Confined to one group of lymph node
Stage 2: More than one group of lymph nodes on one side of the diaphragm
Stage 3: Nodes involved on both sides of the diaphragm
Stage 4: Extranodal involvement like liver, bone marrow
Suffix 'S'—Spleen involved
Suffix 'B'—Presence of constitutional symptoms
Suffix 'A'—Absence of constitutional symptoms

Note: In modification, following additions are there

- Single extralymphoid site is I E
- An extralymphoid site with one or more lymph nodes same side of diaphragm is II E
- An extralymphoid site with lymph nodes on both sides of diaphragm III E.
- An extralymphoid site with spleen and lymph nodes on both sides of diaphragm III SE.
- Spleen with lymph nodes on both sides of diaphragm is III S.

N—Nodes H—Liver S—Spleen L—Lung
M—Marrow P—Pleura O—Bone D—Skin
Stage III (1) is nodes above renal vein level and
Stage III (2) is below it.

Differential Diagnosis

- Tuberculosis.
- NHL.
- HIV.
- Chronic lymphatic leukaemia.
- Nonspecific lymphadenitis.
- Sarcoidosis.
- Secondaries in lymph nodes.



Fig. 1.497: Secondaries in neck lymph nodes. It is hard, large probably fixed and nonmobile making it advanced and inoperable.

Investigations

- *Blood:* Hb%, ESR, peripheral smear, blood urea, serum creatinine. Serum alkaline phosphatase and calcium may elevated.
- *FNAC of lymph nodes*.
- *Excision biopsy of lymph nodes*. Full lymph node is excised to retain the architecture of the lymph node. It is important to grade the tumour. It is better to have *immunohistochemistry* of tumour tissue. As cell mediated immunity is decreased, CD4/CD 8 ratio will be decreased.
- *Chest X-ray*—to look for mediastinal lymph nodes, pleural effusion.
- *U/S abdomen*—to look for the involvement of liver, spleen, abdominal lymph nodes.
- *CT scan of mediastinum/chest*, abdomen and pelvis is better, ideal and essential. *CT is* used ideally *to stage* the disease.
- *Chamberlain's mediastinoscopy* and biopsy of mediastinal lymph node is done if peripheral nodes are not available for biopsy. *Laparoscopy* and biopsy of different abdominal lymph nodes is also a good option.
- *Lower limb lymphangiography* to look for the pelvic and retroperitoneal lymph nodes. It shows reticular pattern in node; it can be used to assess the therapeutic response and prognosis. Lymphoscintigraphy is better and acceptable. It is prognostic tool also.
- *Bone marrow biopsy* to stage and also to see the response to treatment.
- *Staging laparotomy*:
  - The abdomen is opened. Splenectomy is done mainly to remove the tumour bulk, as spleen is commonly involved and also to avoid irradiation to splenic area which often causes unpleasant pulmonary fibrosis. Biopsies are taken from both lobes of the liver (needle biopsy) from para-aortic, celiac mesenteric, iliac nodes. In females ovaries are fixed behind the uterus to prevent radiation oophoritis *(oopheropexy/ovarian translocation).*
  - Staging laparotomy is not routinely done now. It is done only if it benefits the patient to have better plan of treatment or better result.
  - It is done in stage I/IIA lymphoma (HL) in selected patients.

***Note*:**
Staging laparotomy, splenectomy (requires for immune function), lymphangiogram, IVU are no longer/very rarely done now for HL.

Problems in HL

- Pleural effusion—respiratory discomfort.
- SVC obstruction.
- Spine if involved—not very common but can occur.
- Opportunistic infection—mycobacteria, cytomegalovirus, herpes zoster.
- Bronchopneumonia, septicaemia.
- Immunosuppression and its effects.
- Risk for other malignancies in later life.



Fig. 1.498: Staging laparotomy for Hodgkin's lymphoma. Needle and wedge biopsies from liver/nodal biopsies from para-aortic, celiac, mesenteric, iliac nodes/splenectomy/ovarian translocation/iliac crest biopsy are the components of staging laparotomy. This can be very well-achieved through laparoscopy also now. Staging laparotomy is not commonly done now.

Treatment for HL

Treatment strategy for HL

- Early favourable stage—extended field radiation only
- Early unfavourable stage—extended radiation plus chemotherapy
- Advanced stage—extensive chemotherapy often with local radiation

Unfavourable signs in early HL

- Large mediastinal mass
- Extranodal disease
- Elevated ESR
- Four or more involved regions
- Presence of B symptoms
- Anaemia < 10 gram % low serum albumin level < 4 gram %
- Age more than 50
- Male gender

Note: First five parameters are most important.

- Stage I and II:
  - Mainly ***radiotherapy***—external high cobalt RT.
    - Above the diaphragm—"*Y" field therapy*, covering cervical, axillary, mediastinal lymph nodes. It may cause carcinoma of breast.
    - Below the diaphragm, *mantle* or *inverted "Y" field therapy*, covering para-aortic and iliac nodes. It may cause infertility.
  - Chemotherapy is also given.
- Stage III and IV: Mainly ***chemotherapy***.



Figs 1.499A and B: Mediastinal nodes involved in lymphoma as seen in chest X-ray and chest CT scan.

Differences between HL and NHL

	HL (more common)	***NHL***
Age:	Young and elderly	Middle age and elderly
Pattern of involvement:	Symmetrical and consecutive	Asymmetrical
Cervical lymph node:	Commonly involved	Any group can be involved
Splenomegaly:	Common	Not common
Peripheral lymph node involvement (e.g. epitrochlear nodes)	Not common	Common
Treatment:	Mainly radiotherapy Chemotherapy (MOPP regime)	Mainly chemotherapy
Prognosis:	Better	Poor

Drugs used include:

❖ Mustine.	**M.** (Mechloroethamine). 6 mg/sq meter on 1st and 8th day.
❖ Oncovine.	**O.** (Vinca alkaloids). 1.4 mg/sq meter on 1st and 10th day.
❖ Procarbazine.	**P.** 100 mg orally daily for 10 days.
❖ Prednisolone.	**P.** 45 mg orally daily for 10 days.

Other regimens available—MVPP, ABVD

ABVD is becoming more popular and commonly used now. Adriamycin—30 mg/sq meter (cardiotoxic); Bleomycin—10 mg/sq meter (pulmonary fibrosis); vinblastine—6 mg/sq meter (bone marrow suppression); DTIC/Dacarbazine 350 mg/sq meter.

Treatment for Relapses

- Autologous stem cell transplantation.
- High dose chemotherapy.
- High dose chemotherapy with autologous stem cell transplantation.
- MOPP/ABV hybrid regime.
- Single dose vinorelbine (new vinca alkaloid); gemcitabine; immunotherapy; tumour vaccination; gene therapy.

Prognosis

- Stage I and II—80%.
- Stage II IA—70%.
- Stage III B and stage IV—< 40%.

Prognostic factors

- Stage I and II has got better prognosis
- Lymphocytic predominance has got better prognosis
- Stage "A" without constitutional symptoms has got better prognosis
- Anaemia < 10 g %; hypoalbuminaemia < 4 g %; lymphocyte count < 600/mm^3; WBC count > 15,000/ mm^3; age > 50 years; involvement of bone and liver are other poor prognostic factors

NON-HODGKIN'S LYMPHOMA (NHL)

- It occurs in middle aged and elderly. It is more aggressive than HL.
- It involves asymmetrical group of lymph nodes.
- General condition is poor.
- Inner Waldeyer ring, epitrochlear lymph nodes, peripheral lymph nodes are commonly involved.
- Spleen is not commonly involved.
- Hepatomegaly is common.
- Vertebral involvement is common; paraplegia can occur. (40%).
- Secondary infection, cachexia and immunosuppression is more common.
- Inner Waldeyer ring and oropharynx lymphoma (NHL-B cell) may be associated with MALT lymphoma of stomach; so gastroscopy is indicated in these patients.
- Pyoderma gangrenosum may the presentation.
- *Small bowel lymphomas* are usually NHL type. *Western type* is annular, ulcerative multiple B cell type, presents as obstruction, bleeding, weight and appetite loss, perforation. *Celiac disease related lymphoma* is usually primary T cell type presents with severe unresponsive diarrhoea, PUO, obstructive features. *Mediterranean* lymphoma of small bowel is seen in North America and Middle East which is associated with alpha chain disease.
- Sarcoma, carcinomas/secondaries are the differential diagnosis for NHL.

Types

- Nodular (Follicular)
- Diffuse lymphocytic
- Undifferentiated
- Histiocytic type

Rappaport classification	*Working classification*
• Nodular	• Low grade
• Diffuse	• Intermediate grade
	• High grade

Pathological Classification

- *B cell type*—small lymphocytic, follicular, Burkitt's lymphoma.
- *T cell type*—cutaneous, mycosis fungoides, Sezzary syndrome, lymphoblastic lymphoma.

Note:
Many different classifications are there for NHL. Students have to refer pathology book when needed.

Histochemistry and tumour markers are very sensitive and essential tools other than biopsy; CT chest, abdomen, pelvis; MRI spine, peripheral smear and bone marrow biopsy. **Serum LDH,** calcium, CD5, CD23 counts are very useful prognostic indicators. Raised LDH carries poor prognosis and also patients require aggressive chemotherapy.

Treatment

Mainly **chemotherapy**
Various regimens available include:

- ChOPP—Chlorambucil, Oncovin, Procarbazine, Prednisolone.
- ABVD—Adriamycin, Bleomycin, Vincristine, Dacarbazine.
- ABVP—Adriamycin, Bleomycin, Vincristine, Prednisolone.
- Combinations of above.
- *Rituximab* may be used with chemotherapy regimes.
- *Role of radiotherapy* in NHL: When vertebra is involved.
- Prognosis is poor compared to HL.

MALT LYMPHOMA (MALToma)

- It is lymphoma arising from mucosa associated lymphoid tissue. It is usually primary GI lymphoma (4% of gastric lymphoma); of Non-Hodgkin's B cell type.
- The most common site is stomach. *Helicobacter pylori* infection is the causative agent commonly.
- It can be low grade or high grade.
- *Low grade* occurs in patient with chronic gastritis due to *Helicobacter* infection. Diffuse mucosal thickening with ulceration is seen. Antihelicobacter therapy is very useful in this type.
- *High grade* is aggressive one. It presents with features similar to gastric carcinoma often with smooth, firm gastric mass in epigastric region.
- Systemic features like fever, night sweats, and weight loss can occur in 50% cases. Bleeding with haematemesis with obstruction is not uncommon. Locoregional lymph nodes (only) may get involved.
- Endoscopic biopsy is essential to diagnose. Endosonography, bone marrow biopsy, CT scan of chest, abdomen and pelvis is a must to confirm primary GI/gastric lymphoma and to identify or to rule out extragastric lymph node NHL.
- *Radical subtotal gastrectomy with adjuvant chemotherapy* is the treatment along with treatment for *Helicobacter* infection. Primary chemotherapy and RT is also useful. Palliative gastrectomy is needed in case of bleeding and obstruction.

BURKITT'S LYMPHOMA (Malignant Lymphoma of Africa)

> *Thirty-eight cases of a sarcoma involving the jaws of African children are described. This is a syndrome which has not previously been fully recognised. It is by far the most common malignant tumour of childhood seen at Mulago Hospital.*
>
> —**Denis Parsons Burkitt,** 1958

- It is common in South Africa and New Guinea.
- *Epstien-Barr virus* may be the etiological agent. It is common in children.
- It is associated with infectious mononucleosis.
- It is common in malaria endemic area.
- The tumour is multifocal, rapidly growing, painless.
- Different groups of lymph nodes can also be affected.

Microscopy

Primitive lymphoid cells with large clear histiocytes—*starry night (starry sky)* pattern.

Sites

- It is common in jaw—either lower or upper.
- Abdominal presentation and renal involvement is common (75%).
- Renal involvement often may be bilateral.
- In females, ovaries are commonly affected.

Types

a. Endemic (African)—commonly occurs in jaw.
b. Nonendemic (sporadic)—commonly occurs in abdomen.
c. Aggressive lymphoma—occurring in HIV patients.

Investigation

- FNAC and biopsy confirms the diagnosis.
- Jaw X-ray shows osteolytic lesions.
- U/S abdomen is done to look for involvement of kidneys.
- Blood urea and serum creatinine estimation is done.

Treatment

- Radiotherapy.
- Chemotherapy: Cyclophosphamide, methotrexate, orthomelphalan.
- Surgery is usually not indicated unless it is localised or in case of involvement of ovaries.

Prognosis is good.

CUTANEOUS T CELL LYMPHOMA

- Cutaneous T cell lymphoma comprises mycosis fungoides, Sezzary syndrome, reticulum cell sarcoma of skin and other cutaneous lymphocytic dysplasias. Mycosis fungoides is the most common among them.
- Cutaneous T cell lymphoma can be indolent (commonly mycosis fungoides); aggressive (Sezzary syndrome); provisional (granulomatous/panninculitis like T cell lymphoma).
- Initial macular patch/plaque phase slowly changes into tumour phase with painful, pruritic erythroderma often with visceral spread. Alopecia mucinosa and follicular mucinosis are common in mycosis fungoides. Lymph nodes may get involved. Tumour cells in peripheral smear are also important in deciding therapy and prognosis.
- Multiple skin biopsies/peripheral smear/node biopsy/immunohistochemistry/pheo or genotyping are important investigations
- Prognosis depends on extent of skin involvement (more the 10% body surface area carries poor prognosis)/nodal spread/blood spread.
- *Treatment:* Localised external beam radiotherapy; topical chemotherapy (bexarotene gel/carmustine ointment); phototherapy; total skin electron beam therapy; extracorporeal photochemotherapy. Bexarotene is a type of retinoid.
- ***Sezzary syndrome*** is a type of cutaneous T cell lymphoma with skin lesions with special Sezzary cells having cribriform nucleus. It is often associated with leukaemias. It is treated like any other cutaneous T cell lymphoma.



Fig. 1.500: Cutaneous T cell lymphoma.

CHYLOUS ASCITES

It is collection of lymph in the peritoneal cavity. It is due to obstruction of intestinal lymphatics and subsequent leak.

Causes

- *Most common cause* is—*congenital* lymphatic abnormality in children (*megalymphatics* with lymphoedema) and in adults lymph node malignancy, either primary or secondary.
- Filarial lymphoedema causing obstruction.
- Malignancy either nodal secondaries or nodal primary causing obstruction.
- Tuberculosis causing blockage of lymph drainage and rupture and leak into the peritoneal cavity.
- Post-surgical cause.

Features

- Ascites, often massive.
- Severe malnutrition and protein deficiency.
- Features specific to the cause.
- Triglycerides > 110 mg/dl in ascitic fluid is diagnostic.
- Ascitic fluid aspiration is chalky white in colour and it shows chylomicrons. It should be studied for fat globules, proteins, AFB and malignant cells.
- Laparoscopy and biopsy is necessary when lymphoma/secondaries are suspected.
- CT scan and CT guided biopsy may be needed.
- Lymphangiography to find out the site of leak.

Treatment

- Control of infection.
- Antituberculous and antifilarial drugs.
- Fat free, protein rich diet.
- Nutritional support—TPN/enteral.
- Medium chain triglycerides can be given as it directly gets absorbed into the blood rather into the lymphatics.
- Repeated tapping, peritoneovenous shunts are often required.
- Surgical ligation of leaking lymphatic duct.

CHYLOTHORAX

It is accumulation of lymph in the pleural cavity.

It is *common on right side* because of long course of thoracic duct towards right side.

Causes

- Injury due to trauma/surgeries in neck or chest. Surgical trauma is the *most common cause*—may be oesophageal surgeries, pneumonectomy, cervical sympathectomy, neck dissections or aortic surgeries.
- Tuberculosis, lymphoma or secondaries in the mediastinum.
- Carcinoma lung or oesophagus.

Features

- Chest pain, dyspnoea, pleural effusion.
- Protein loss and malnutrition
- Pleural tap will show chalky white fluid rich in chylomicrons. Triglycerides more than 110 mg/dl in the pleural fluid.
- Chest X-ray, CT chest are needed.

Treatment

- ICT placement.
- Fat free protein rich diet.
- Antibiotics therapy for the cause.
- Often pleurodesis using bleomycin, talc, tetracycline or pleural stripping is needed.
- Thoracic duct ligation is beneficial in traumatic/iatrogenic cases.
- Through thoracoscopic approach, ligation of the thoracic duct is done if leak persists *beyond one week*. If oral cream is given to the patient 6 hours before surgery, leaking site will be better identified. Thoracic duct is ligated *above and below* the leak either through thoracoscopy or thoracotomy.
- ICT drainage, oral diet of medium chain triglycerides which is absorbed directly into blood not through lymphatics; with TPN, is the usual earlier way of management.

CHYLURIA

- It is passage of milky white chylous urine, which is aggravated after fatty meal.
- It may be due to obstruction of intestinal lymphatic vessels leading to high lymphatic pressure causing diversion of lymph into renal lymphatics or it often may be due to rupture

of intestinal lymphatics into renal pelvis or ureter leading into a lymphourinary fistula.

- *The most common cause is filarial* (2% of filarial cases): Other causes are tumour, tuberculosis, malaria and ascariasis infestation.
- Urinary infection, protein loss is common.
- It mimics bacterial/tuberculous pyuria or phosphaturia.
- Clot colic due to *lymph clot* in urinary system may be the presentation.
- Urine study, culture, IVU, lymphangiography, U/S abdomen is needed.
- Treatment is low fat, protein rich diet, antibiotics, DEC, plenty of oral fluid intake, ligation of dilated lymphatics through laparotomy or sclerosing the lymph vessels.
- Condition causes severe psychological and nutritional problem.

SARCOIDOSIS

It is a differential diagnosis for lymph node mass. It is basically a granulomatous condition of unknown cause with bilateral hilar lymphadenopathy; with involvement of lungs, liver, spleen, lymph nodes, lacrimal glands, parotid glands, CNS, hypercalciuria, acute onset of erythema nodosum in the skin. Fever and loss of weight are not common. It shows noncaseating epithelioid granuloma with positive Kveim-Siltzbach skin test (80%); high levels of serum angiotensin converting enzyme (SAGE). Investigations needed are—CT chest; mediastinoscopy; nodal biopsy; slit lamp examination of eye; often abnormal immunoglobulins in the circulation. It is treated by corticosteroids with good response. It should be differentiated from other causes of lymphadenopathy especially Hodgkin's lymphoma.

Note:

For topics tuberculous lymphadenitis and lymph node secondaries please refer chapter 'Neck'.



Figs 1.501A and B: Gross feature of sarcoidosis of spleen (*Courtesy:* Dr Arunkumar, MCh, Gastroenterologist).

P. Peripheral Nerves

> *The power of moving in every part of the body by means of the muscles which obey the will, or by means of others the actions of which are involuntary; the various perceptions by the five external senses; and lastly those mental powers named memory, imagination, attention, and judgement, together with the passions of the mind; all these seem to be exercised by the ministry of the nerves; and are impaired, disturbed, or destroyed, in proportion to any injury done to the brain, the spinal marrow, and nerves, not only by their peculiar diseases, of which we know little, but by contusions, wounds, ulcers, and distortions, and by many poisons of the intoxicating kind.*
>
> **—William Heberden,** *1802*

CHAPTER OUTLINE

- Peripheral Nerve Injuries
- Tinel's Sign
- Brachial Plexus Injuries
- Causalgia
- Median Nerve Injury
- Carpal Tunnel Syndrome
- Ulnar Nerve Injury
- Claw Hand
- Radial Nerve Injury
- Common Peroneal Nerve Injury
- Foot Drop
- Medial Popliteal Nerve Injury
- Axillary Nerve Injury
- Long Thoracic Nerve Injury
- Meralgia Paraesthetica

PERIPHERAL NERVE INJURIES



Fig. 1.502: Cross-section of a nerve.

Classification

Seddon's Classification

- *Neuropraxia:* It is temporary physiological paralysis of nerve conduction. Here recovery is complete. There is no reaction of degeneration.
- *Axonotmesis:* It is division of nerve fibres or axons with intact nerve sheath. There is reaction of degeneration distally with near complete recovery. Patient can present with sensory loss, paralysis of muscles or causalgia.



Fig. 1.503: Dermatomes.

- *Neurotmesis:* Here complete division of nerve fibres with sheath occurs. Degeneration occurs proximally up to the first node of Ranvier as well as distal to the injury. Recovery is incomplete even after nerve suturing. There is complete loss of motor and sensory functions with loss of reflexes. If the nerve is mixed type other than pure motor or sensory recovery is still poorer.

Injuries may be incised or lacerated or crushed one.

Cut end of the nerve forms proximally *neuroma* and distally *glioma.*

Neuromas may be:

- True neuroma or false neuroma.
- End neuroma or side neuroma.

Sunderland's classification

I: Conduction block—temporary neuronal block
II: Axonotmesis but endoneurium is preserved
III: Axonotmesis with disruption of endoneurium, but perineurium is preserved
IV: Here disruption of endo and perineurium has occurred but epineurium is intact
V: Neurotmesis with disruption of endo, peri and epineurium has occurred

Clinical Features

- Loss of sensory, motor, autonomous and reflex functions.
- Secondary changes in the skin and joint.

Primary nerve suturing is done if it is a clean incised wound.

Secondary nerve suturing is done after 3 weeks if it is a crushed wound.

Management

- Associated injuries like fracture, vessel injury, injuries in other systems should be looked for.
- Assessment of nerve injury is done by checking sensation, muscle power, reflexes.
- Nerve conduction studies.
- Investigations relevant for associated injuries.
- Exploration of the wound.

Debridement of the area is done. If injury is incised one, then nerve is sutured with 8-0 to 10-0 nonabsorbable interrupted sutures (polypropylene).

Types of Nerve Suturing

Usually microscope or loup is used for nerve suturing.

i. *Epineurorrhaphy*: Only epineurium is sutured using interrupted sutures.
ii. *Epi-perineurorrhaphy*: Initially perineural sheath and then epineurium is sutured.

Nerve suturing can be:

- ***Primary repair*:** It is done immediately after injury. Nerve ends are minimally trimmed very close using a blade. All fascicles of the nerve are oriented correctly. Two stay sutures are placed to keep the orientation properly. Usually epineural suturing is done using 8 zero polypropylene interrupted sutures. It needs magnification. 6-8 sutures are placed for large peripheral nerve like median or ulnar nerve. For small nerve like digital nerve, only 2-3 sutures are placed.
- ***Secondary repair*:** It is done at a later period. It is done in a preexisting scar tissue. Here first nerve ends, both proximal and distal are identified, carefully dissected adequately. Proximal neuroma and distal glioma are trimmed for 1 cm to expose the normal fascicles of the nerve ends. Often guide sutures of silk may be present which were placed earlier during exploration of the trauma. Once nerve ends are clean, it is sutured alike primary suturing with stay sutures, with proper alignment of fascicles, followed by epineural suturing. Here as epineurium is thicker, suturing is easier.

If nerve is lacerated, then *marker stitches (using silk)* are placed at the cut end site to identify the nerve for suturing at a later period.

If nerve suturing fails or if could not be done, then tendon transfer is done at a later period after 4-6 months.

Incomplete injury usually does not require any suturing.

Easier suturing is achieved by following methods:

- Relaxing incisions.
- Transpositioning of the nerve.
- Shortening of the bone.
- Nerve graft—usually sural nerve is used for nerve graft.
- Positioning of the limb.
- Initially *neurolysis* (release of the scar tissue adjacent to injury) is done in case of secondary suturing.

Prognostic factors in healing of the nerve injury:

- Higher the lesion worser the prognosis.
- More the gap between the cut ends worser the prognosis.


Severed nerve ends are trimmed just close to the ends. Guide/stay stitches are placed on both sides of each ends.
Orientation of fascicles are done in both cut ends. Epineural sutures are placed with knots on outside. Polypropylene interrupted sutures are used.
Completed epineurorrhaphy.

Fig. 1.504: Primary nerve repair.


If cut ends are without any undue tension (tension free), then ends are sutured with orientation of fascicles.
Neuroma/glioma formation at the cut ends of nerve.
Neuromas are trimmed for 1-2 cm to get normal fascicles at the nerve ends.
If there is tension then nerve graft is necessary using sural nerve.

Fig. 1.505: Secondary nerve repair.

- ♦ Associated injuries alter the prognosis.
- ♦ Children do better with nerve injury.
- ♦ Type of the injury also decides the prognosis.

The rate of growth of nerves after peripheral nerve suturing is 1 mm/day.

TINEL'S SIGN

It is the clinical sign (prognostic indicator) used to assess the level of regeneration. It is elicited 3 weeks after the nerve injury (Regeneration begins after the completion of nerve degeneration).

Tapping over the course of the nerve is done *from distal to proximal* to elicit a sensation of "*pins and needles"* or *hyperaesthesia.*

If sensation is felt at the site as well as distally along the distribution of the nerve, that means good recovery can be expected. If sensation is felt only at the site of tapping, then result is equivocal. If no sensation is felt it means no recovery.

Causes of peripheral nerve lesions

- ❖ Traumatic: Either closed or open injury
- ❖ Inflammatory: Leprosy, herpes zoster, diphtheria
- ❖ Compression neuropathies
- ❖ Lead poisoning
- ❖ Arsenical poisoning
- ❖ Alcoholism
- ❖ Diabetes mellitus
- ❖ Vitamin B_1 deficiency
- ❖ Porphyria
- ❖ Neurofibroma and other neural tumours
- ❖ Idiopathic

BRACHIAL PLEXUS INJURIES

It can be:

♦ Supraclavicular injury	65%
♦ Infraclavicular injury	25%
♦ Combined	10%

It can also be:

- ♦ Upper plexus injury.
- ♦ Lower plexus injury.



Fig. 1.506: Brachial plexus anatomy.

It can be:

Pre-ganglionic injury	Post-ganglionic injury
Avulsion injury	Usually less severe
More dangerous	Better recovery
Extends into the spinal cord	

Investigations

- ❖ Nerve conduction studies.
- ❖ CT/MRI.
- ❖ Electromyogram.
- ❖ X-ray cervical spine and part.

Treatment

- ♦ Conservative, nerve repair.
- ♦ Tendon transfer, physiotherapy.

Osteotomy of coracoid process proximal to the attachment of pectoralis minor, short head of biceps and coracobrachialis is done to improve abduction—*Sever's operation.*

CAUSALGIA

It is severe burning pain and hyperaesthesia in the distribution of a peripheral nerve due to *incomplete injury* to the nerve.

Features of upper and lower plexus injuries

	Upper plexus injury (Erb-Duchenne paralysis)		***Lower plexus injury (Klumpke's paralysis)***
1.	It is due to depression of shoulder by trauma	1.	Forcible hyperabduction of shoulder causes this injury
2.	After difficult labour in newborn	2.	In newborn it result due to difficult breech delivery
3.	Here C_5 and C_6 roots are injured	3.	Here C_8 and T_1 are injured
4.	Muscles affected are deltoid, biceps brachioradialis and supinator	4.	Intrinsic muscles of the hand are involved
5.	*Effects are:*	5.	*Effects are:*
	a. Elbow will be extended, pronated and upper limb is internally rotated (*Policeman receiving tip)*		a. Combined median and ulnar claw hand
	b. Sensory deficit over the lateral aspect of arm and upper part of the lateral forearm		b. Horner's syndrome
			c. Sensory deficit over the medial aspect of forearm, hand, and medial 1½ finger

In lesions of S_1 there is no dropped big toe.—**Gosta Norlen**

Sites

Common in upper limb.

Commonly seen in median nerve, also often in brachial plexus injuries. In the lower limb it is seen in sciatic nerve or tibial nerve injuries.

Pathology

Incomplete nerve injury produces abnormal impulse towards sensory nerve ending causing vasomotor instability and pain.

Clinical Features

- Hyperaesthesia with severe disabling and burning pain.
- Skin becomes red, shiny and glossy which sweats profusely—*Weir-Mitchell's skin.*
- Eventually skin becomes atrophic, cyanotic, cold and blotchy.
- Skin is less sensitive to heat, cold, and pin prick, but hypersensitive to touch and tender to pressure.
- Nails are rigid, brittle with change in colour.

Investigation

Nerve conduction studies.

Treatment

- Anti-inflammatory drugs, steroids, physiotherapy.
- IV guanethidine regionally.
- If not improved, sympathectomy—cervical for upper limb, lumbar for lower limb.

MEDIAN NERVE INJURY

- Median nerve arises from lateral ($C_{5,6,7}$) and medial cord (C_8 and T_1) of the brachial plexus. It is initially lateral to the axillary artery and becomes medial in the lower part of the arm and in the cubital fossa. It passes through the pronator teres, descends in relation to flexor muscles and enters the palm through the carpal tunnel at the wrist.
- It supplies pronator teres, flexor carpi radialis, palmaris longus and flexor digitorum superficialis. Anterior interosseous branch of the median nerve supplies pronator teres, lateral half of the flexor digitorum profundus, flexor pollicis longus and pronator quadratus.
- In the wrist, it supplies abductor pollicis brevis, flexor pollicis and opponens pollicis of thenar eminence and lateral two lumbricals. It gives sensory supply to lateral three and half fingers of the hand.

Median nerve is affected in:

- Injuries
  - Supracondylar fracture of the elbow
  - Fracture—dislocation of the elbow
  - Direct cut injuries
- Leprosy
- Carpal tunnel syndrome
- As a part of brachial plexus injury

Clinical Features of Median Nerve Palsy

In high median nerve palsy

- Wasting of the thenar eminence. Loss of sensation on lateral three and half fingers.
- Ochsner's clasping test shows pointing index because of the inactivity of lateral two divisions of the profundus.
- "*Ape or Simian thumb deformity*" is due to overaction of the adductor pollicis which is supplied by the deep branch of ulnar nerve. As all other thenar muscles are paralysed, thumb comes in the same plane of the metacarpals.
- "*Pen test*": In median nerve injury, pen held in front of the hand cannot be touched by thumb as abduction is not possible due to paralysis of the abductor pollicis brevis.

In low median nerve palsy profundus is not paralysed and so *pointing index* is not seen.

Investigations

- Nerve conduction studies.
- X-ray of the part in case of fracture.
- Electromyogram.

Treatment

- Nerve suturing or nerve graft.
- Tendon transfer.
- Treat the cause like carpal tunnel syndrome.

CARPAL TUNNEL SYNDROME

- It is the compression neuropathy of median nerve in the carpus, deep to flexor retinaculum.
- Flexor retinaculum (transverse carpal ligament) maintains the concavity of wrist and extends laterally from trapezium and scaphoid to pisiform and hook of the hamate medially.

Carpal tunnel is formed by carpal bones behind and flexor retinaculum in front. It contains median nerve and long flexor tendons of fingers and thumb. Ulnar nerve lies superficially, not in the carpal tunnel.

Median nerve gets compressed if space of the carpal tunnel gets reduced.

Causes

- Lunate dislocation, malunited Colle's fracture.
- Radiocarpal arthritis, flexor tendon tenosynovitis.
- Myxoedema, acromegaly, pregnancy.

Clinical Features

- Common in females.
- Tingling, numbness, paraesthesia and burning sensation in the lateral three and half fingers supplied by median nerve. Burning sensation gets aggravated at night.
- Ape thumb deformity, wasting of thenar muscles, weakness of opponens pollicis and abductor pollicis brevis, i.e. features of low median nerve palsy.
- When BP cuff is inflated patient feels the typical pain in the fingers.


Flexor retinaculum
Hook of Hamate
Pisiform bone
Ulnar nerve
Trapezium crest
Scaphoid tubercle
Radial styloid process
A
Palmar cut branch of ulnar nerve
Palmaris longus
Palmar cut branch of median nerve
Hypothenar muscles
Thenar muscles
Pisiform bone
Ulnar nerve and artery
Triquetral
Scaphoid tubercle
Scaphoid
FDS muscle
FDP muscle
Lunate
Palmar aponeurosis
B
Flexor retinaculum

Figs 1.507A and B: Anatomy of the carpal tunnel and flexor retinaculum.

- Tapping the median nerve at the distal end of forearm with the wrist held in extension aggravates the symptoms.
- Condition is often bilateral.

Phalen’s Test (Wrist Flexion Test)

Flexion of the wrist causes exacerbation of the symptoms within 1 minute and the symptoms will disappear as the wrist is straightened.

Differential Diagnosis

- Cervical spondylosis.
- Cervical rib syndrome.

Diagnosis

Nerve conduction studies.

Treatment

- Surgical decompression of median nerve by cutting both superficial and deep part of flexor retinaculum completely, by ’S’ shaped incision.
- Surgery is usually done under *local anaesthesia*. General or brachial block can be used. Tourniquet is commonly used. *Vertical crease incision* is made in the proximal part of the palm with convexity of the incision towards the ulnar side.
- Skin incision is deepened. Palmar cutaneous branch of the median nerve should be preserved. Incision is deepened to identify the flexor retinaculum. *Entire length, both superficial and deep parts* should be cut properly. It is cut towards ulnar side of the wound. *Only skin* is sutured using interrupted nonabsorbable 3 zero polypropylene or polyethylene sutures.
- *Complications* are incomplete fasciotomy and recurrence, nerve injury.

To know how to laugh whole heartedly, you have to know how to weep also.



Fig. 1.508: Incision for carpal tunnel syndrome.

- Using small proximal incision, endoscopy can be passed to visualise and cut the entire flexor retinaculum—*minimal access surgery.*
- Postoperatively **good physiotherapy** is required.
- Condition is permanently curable.

ULNAR NERVE INJURY

- After arising from the medial cord of the brachial plexus (C$_8$ and T$_1$), it runs on the medial aspect of the axillary artery up to middle of the arm. Then it enters the posterior compartment in relation to triceps muscle. After passing behind the medial epicondyle and through two heads of flexor carpi ulnaris, it runs in front of the flexor digitorum profundus (FDP) in the forearm. It reaches the hand in front of the flexor retinaculum through *"Guyon's canal"*. Here it divides into superficial and deep branches.
- Ulnar nerve supplies flexor carpi ulnaris, medial half of flexor digitorum profundus, all muscles of the hypothenar eminence (palmaris brevis, abductor digiti minimi, opponens digiti minimi, flexor digiti minimi), adductor pollicis of the thenar eminence and all interossei of the hand. It also gives sensory supply to medial part of the hand, medial one and half fingers.

Ulnar nerve is affected in:

- Supracondylar fracture
- Injury to the medial epicondyle
- Tardy ulnar palsy
- Leprosy
- Cubitus valgus deformity

Clinical Features

- *Claw hand* deformity.
- Weakness of all the muscles supplied by the ulnar nerve.
- "*Card test*": A card is placed between the two fingers of the patient to grasp. As the palmar interossei are weak, patient cannot grasp [palmar interossei are adductors of the fingers (*PAD*)].
- Abduction of fingers are checked [dorsal interossei are abductors (*DAB*)].
- *Froment's sign*: A book is placed to grasp between fingers and thumb of the patient. Normally thumb will be straight because of the action of adductor pollicis muscle. As it is paralysed in ulnar palsy, grasp is achieved by the action of flexor pollicis longus and there will be flexed thumb.
- Loss of sensation over medial one and half fingers and hand.

Investigations

- Nerve conduction studies.
- Electromyogram.

Treatment

- Nerve suturing or nerve grafting.
- Tendon transfer.

Intrinsic minus deformity: It is due to loss of intrinsic muscle power, i.e claw hand.

Intrinsic plus deformity: It is due to muscle contracture and fibrosis.

Ulnar paradox: In ulnar palsy, higher the lesion, lesser the deformity, lower the lesion more the deformity. In higher lesion, FDP is also paralysed. In lower lesion FDP is intact and so FDP causes more flexion (overaction) and so aggravates the claw hand.

CLAW HAND

- It is the hyperextension of the metacarpophalangeal joint with flexion of the interphalangeal joints of the hand.
- Extension of MCP joint is due to unopposed action of extensor digitorum.
- Flexion of MCP joint and extension of interphalangeal joints are by extensor hood of interossei and lumbricals. So extensor hood is functioning mainly by ulnar nerve and also by median nerve. In ulnar or median nerve palsies, these actions are paralysed and so patient develops claw hand.
- It is actually *intrinsic minus deformity.*

Causes

- Leprosy
- Trauma
- Entrapment neuropathies
- Tardy ulnar palsy
- Klumpke's palsy

Clinical Features

- Typical claw hand.
- Loss of sensation along the distribution of the nerve.
- Inability to grasp card between the fingers.
- While holding the book between the thumb and fingers, thumb will be flexed in ulnar claw hand (*positive Froment's test*).

Types

- ***Ulnar claw hand****:* Only medial two fingers are involved.
  - *Low ulnar palsy*: Here lesion is in the wrist (at Guyon's canal). Here deformity is more because of the overaction of the FDP.



Figs 1.509A and B: *Ulnar claw hand* with hyperextension of metacarpophalangeal joints and flexion of proximal and distal interphalangeal joints in medial two fingers due to ulnar nerve palsy.



Figs 1.510A and B: *Combined claw hand* involving all fingers due to both ulnar and median nerve injuries.

  - *High ulnar palsy*: Here FDP is also paralysed and overaction is not there. So lesser deformity occurs.

    ***Ulnar paradox*: Higher the lesion lesser the deformity, lower the lesion more the deformity.**

- ***Median claw hand*:** Only lateral two fingers are involved. It is less common.
- ***Combined median and ulnar claw hand*:** Here all four fingers of the hand are involved.

Investigations

- Electromyogram.
- Nerve conduction studies.

Treatment

- ***Paul Brand's operation*:** Extensor carpi radialis longus or brevis (ERCB) is transferred with a graft to the extensor hood through the lumbrical canal. Graft is taken from palmaris longus or plantaris muscle.
- ***Stye-Bunnell's operation*:** Flexor digitorum superficialis of index finger is used (only in ulnar claw hand) to transfer to extensor hood.
- *Fowler's operation*: Extensor digitorum is used to transfer to extensor hood.
- *Riordan operation*: Flexor carpi radialis is used for tendon transfer.
- *Anterior transpositioning* of the ulnar nerve in case of tardy ulnar palsy.

RADIAL NERVE INJURY

- Radial nerve is derived from the posterior cord of the brachial plexus ($C_{5, 6, 7, 8}$ and T_1). It descends behind the axillary artery in front of the subscapularis, latissimus dorsi and teres major. It passes through the medial and lateral heads of the triceps muscle, winds round the humerus through the radial groove and enters the forearm in front of the lateral epicondyle in relation to brachioradialis, brachialis and extensor carpi radialis longus muscles.
- In the arm it supplies triceps, anconeus, brachioradialis, extensor carpi radialis longus and part of brachialis. It gives posterior and lower lateral cutaneous nerves of the arm and posterior cutaneous nerve of the forearm.
- *Superficial branch* of the radial nerve from the elbow runs in the forearm in relation to supinator and brachioradialis and ends by forming five digital nerves which gives sensory supply to lateral three and half fingers on the dorsal aspect—except skin over the distal phalanges.
- *Deep branch also* called as posterior interosseous nerve winds round the radius supplying supinator and extensor carpi radialis brevis. It gives 3 short branches to extensor digitorum, extensor digiti minimi and extensor carpi ulnaris. It also gives two long branches—one to abductor pollicis longus and extensor pollicis brevis; another to extensor pollicis longus and extensor indicis.

Open confession is good for the soul.

Conditions where radial nerve is affected

In the ***axilla***

- *Crutch palsy.* It is neuropraxia
- Fracture upper end of the humerus
- Bony or soft tissue growth

In the ***radial groove***

- Pressure on the arm from the edge of the operating table
- *Saturday night palsy*—an individual with excessive alcohol consumption compresses his arm over the chair or by fall. It is neuropraxia
- Prolonged tourniquet application—*tourniquet palsy*
- Fracture of the shaft of the humerus
- *Rarely* intramuscular injection of drugs can cause radial nerve palsy

In the ***elbow***

- Dislocation or fracture neck of the radius

Clinical Features

- *Wrist drop* because of inability of extending the wrist.
- Inability to extend metacarpophalangeal joint, but extensions of the interphalangeal joints are normal.
- Inability to extend the forearm.
- Inability to extend the thumb.
- Flexion of the elbow against resistance with forearm in mid-prone position is difficult because of the weakness of the brachioradialis muscle.
- Loss of sensation in back of the arm, forearm, hand and lateral three and half fingers.

Posterior interosseous nerve is purely motor and so sensation is intact when it gets injured. *It causes only dropped fingers.*

Investigations

- X-ray of the part.
- Nerve conduction studies.

Treatment

- Nerve suturing or nerve graft.
- Tendon transfer.



Fig. 1.511: *Wrist drop*—due to radial nerve palsy.

COMMON PERONEAL NERVE INJURY

This nerve supplies the extensor and peroneal group of muscles and sensory supply to the skin over the front and lateral aspect of the leg and dorsum of the foot.

Common peroneal nerve is affected in:

- Fracture neck of the fibula
- Leprosy
- Lead poisoning
- Iatrogenic

Clinical Features

- Foot drop with high stepping gait.
- Talipes equinovarus deformity.
- Loss of sensation on the lateral side of the leg and dorsum of the foot.

Management

- Treating the foot drop.
- MCR chappals.

FOOT DROP

Inability to dorsiflex and evert the foot due to paralysis of the peroneal and extensor group of muscles, as a result of common peroneal nerve injury.

Causes

- Fracture neck of the fibula
- Leprosy
- Lead poisoning
- Iatrogenic
- Direct incised wound



Fig. 1.512: *Foot drop* with claw toes. It is due to peroneal nerve injury (Lateral popliteal nerve).

Clinical Features

- High stepping gait.
- Loss of sensation over lateral and dorsum of the foot.

Treatment

Tendon transfer using tibialis posterior muscle. Tendon of the muscle is detached from its navicular insertion and with a tendon graft (from plantaris) it is transferred to cuboid and cuneiform bones to get dorsiflexion and eversion.

a. Ober's procedure.
b. Barr's procedure.

MEDIAL POPLITEAL NERVE INJURY

It supplies the soleus, gastrocnemius, popliteus, plantaris, tibialis posterior, flexor digitorum longus and flexor hallucis longus.

Medial popliteal nerve is rarely involved by any disease process. Trauma can cause medial popliteal nerve palsy.

Clinical features

- Inability to plantar flex the foot
- Claw toes
- Sensory loss in the sole of the foot

AXILLARY NERVE INJURY

Axillary nerve supplies the deltoid and teres minor muscle and also sensory supply to the skin over the upper lateral aspect of the arm.

Axillary nerve is affected in:

- Fracture neck of the humerus.
- Dislocation of humeral head.
- Following IM injection into the deltoid.

Clinically there will be loss of abduction of the shoulder and anaesthesia of the skin over the lateral part of the arm.

LONG THORACIC NERVE INJURY (NERVE OF BELL)

It supplies serratus anterior muscle. It arises from $C_{5, 6, 7}$ cervical roots.

The nerve is injured commonly in malignancy, during breast, axillary or chest wall surgeries.

Clinically, when outstretched (elbow extended) arm is pushed against the wall, the inferior angle of the scapula will become prominent (*Winging of the scapula*).

MERALGIA PARAESTHETICA

(Meralgia – Greek – thigh)



Fig. 1.513: Lumbar plexus showing origin of lateral cutaneous nerve of thigh.

- It is *entrapment neuropathy* of lateral cutaneous nerve of thigh. Nerve gets *compressed* while passing through the inguinal ligament. It arises from posterior divisions of lumbar plexus ($L_{2, 3}$); runs over the quadrates lumborum and iliacus muscles; emerges behind the lateral part of the inguinal ligament; divides into anterior and posterior branches, supplying skin over anterolateral part of the thigh and anterior part of the gluteal region.
- It causes hyperaesthesia, tingling over upper lateral aspect of the thigh along the distribution of the nerve. Symptoms get worsened on standing or walking; it is relived by sitting.
- It *mimics* disc prolapse or Hansen's disease or neuropathies.
- It is *treated* by reassurance; carbamazepine; steroids. Often *release* of inguinal ligament fibres that are compressing the nerve is needed.

Q. Neoplasm

CHAPTER OUTLINE

- Definition
- Dysplasia
- Carcinoma *In Situ*
- Aetiologic Factors
- Spread of Malignant Tumours
- Grading of Tumour
- Staging of the Tumour
- Paraneoplastic Syndromes
- Investigations for Neoplasm
- Management Strategy for Cancers

DEFINITION

Willis defined neoplasm as "*it is an abnormal mass of tissue, the growth of which exceeds and is uncoordinated with that of the normal tissues and persists in the same excessive manner even after cessation of the stimuli.*"

Neoplasia is:

- **P**rogressive
- **P**urposeless
- **P**erverted
- **P**ersistent
- **P**ervasive
- **P**roliferative mass of tissue.

Classifications

Benign	***Malignant***
Well-differentiated	Lack of differentiation
Structures are typical of tissue/cell of origin	Atypical structure with anaplasia
Smooth, slow, progressive rate of growth	Erratic, rapid growth
Normal mitotic figures	Abnormal mitotic activity
Well localised and capsulated	Not localised. Not capsulated
Do not infiltrate surrounding normal tissues	Infiltrate the surrounding tissues
No metastasis	Metastasise through lymphatics or blood
Curable	May not be completely curable
Few benign tumours after a long time may turn into malignancy	
Treatment is simple	Treatment is complex and complicated
No recurrence	Recurrence can occur

Sarcoma	***Carcinoma***
Arising from mesenchymal tissues	Arising from epithelial cells derived from any of the three germ layers
'Sar' means flesh (Greek), *Oma* means tumour	*Carc* means crab like
Smooth, firm or hard swelling	Hard, proliferative, with everted edge
Warm and vascular with dilated veins over the surface	
Spreads mainly through blood commonly to lungs, e.g. liposarcoma, fibrosarcoma,	Spreads through lymphatics as well as blood, e.g. squamous cell carcinoma, renal cell carcinoma, adenocarcinoma

- **Neoplasms which are only locally malignant**: No blood spread. No lymph node spread—Marjolin's ulcer, Rodent ulcer, Verrucous carcinoma, Adamantinoma.
- **Neoplasms which are loco-regionally malignant**: Spread only to regional lymph nodes is observed—Squamous cell carcinoma, Papillary carcinoma thyroid.
- **Neoplasms which are systemic** and spreads through blood and often also to lymph nodes.
- Melanoma, carcinoma breast.

Components

Parenchyma: It contains proliferating neoplastic cells.
Stroma: It contains supporting connective tissues and blood vessels.

Features of anaplasia

- Lack of cellular differentiation
- Pleomorphism—variation in size and shape
- Hyperchromatism—dark staining nuclei
- Anisocytosis
- Anisonucleosis
- Abnormal mitotic activity



Fig. 1.514: Soft tissue sarcoma thigh. Note the dilated vassels on the surface.



Fig. 1.515: Carcinoma heel region. Note the everted edge with proliferative cauliflower like look.



Fig. 1.516: Squamous cell carcinoma scalp. Note the everted edge. It is ulceroproliferative lesion.



Fig. 1.517: Soft tissue sarcoma thigh.

Features of malignant tissues

- Altered differentiation, anaplasia
- Rapid rate of growth
- Local invasion—locally, lymphatic, vascular and perineural
- Metastasis
- Not capsulated
- Increased vascularity
- *Microscopic changes*—necrosis, numerous atypical mitotic activities, nuclear changes like pleomorphism/enlargement/hyperchromatism/clumping of chromatin/enlargement and multiplication of nucleoli

DYSPLASIA

It means "disorderd growth." There is loss in the uniformity of the cells with pleomorphism and hyperchromatism, as well as loss in their architectural orientation.



Fig. 1.518: Melanoma lip. Note the extension.

The creation of a thousand forests is in one corn.—**Ralph Waldo Emerson**

CARCINOMA *IN SITU*

Here dysplasia involves the entire thickness of the epithelium, and is preinvasive. Basement membrane is intact in carcinoma *in situ.*

AETIOLOGIC FACTORS

Age

It is more common in elderly. But it is variable.

Heredity

- Familial: Familial polyposis of colon
- MEN syndrome
- Neurofibromatosis
- von-Hippel-Lindau syndrome
- Familial breast and ovarian cancers

Genetic

- Xeroderma pigmentosa
- Ataxia telangiectasia
- Fanconi anaemia, Bloom syndrome

Tumour suppressor gene p53 plays important role in prevention of the cancers. Its function is prevention of replication of damaged DNA. If damaged DNA replicates there is high chances of abnormal mitotic activity and cancer transformation of the tissue. *Loss or reduction of ability/function of p53 suppressor gene* can lead into cancers. Common cancers associated with p53 loss are cancers of breast, colorectum, retina, bone, brain, soft tissues, blood and familial related type.

Acquired causes

- Chronic atrophic gastritis
- Solar keratosis
- Leukoplakia of oral cavity
- Ulcerative colitis

Chemical carcinogens

- Alkylating agents
- Hydrocarbons
- Smoking—lung, aerodigestive system, bladder cancer
- Asbestos—lung cancer
- Alcohol—liver cancer
- Amides, Azo dyes—bladder cancer
- Aflatoxin B_1
- Arecoline, collagenases and tannins (present in Betel nuts)
- Nitrosoamines, vinyl chloride, insecticides

Geographical variation

Japan—Carcinoma stomach
China, France—Carcinoma oesophagus
Hongkong—Nasopharyngeal carcinoma
Australia—Melanoma
India—Carcinoma oral cavity, gallbladder carcinoma
Newzealand—Small bowel tumours

Radiation carcinogens

- UV rays, ionising radiation.

Microbial carcinogens

- Human papilloma virus—carcinoma cervix
- Epstein-Barr virus—Burkitt's lymphoma, nasopharyngeal carcinoma
- Hepatitis 'B' virus—liver cancer
- Human T cell leukaemia virus Type I
- *Helicobacter pylori* can cause carcinoma of stomach and is associated with lymphomas [Mucosa Associated with Lymphoid Tissue (MALT)]

SPREAD OF MALIGNANT TUMOURS

1. **Local spread**: Into adjacent structures like soft tissues, vessels, bone.
2. **Lymphatic spread**
   - ***By permeation*:** Here malignant cells proliferate through lymphatic vessels up to lymph node level. For example, in carcinoma breast malignant cells permeate into axillary lymph nodes.
   - ***By embolisation:*** Here cells get dislodged from lymphatic vessels and freely travel to spread into further level of lymph nodes. In carcinoma breast by embolisation, spread occurs from axillary lymph node to supraclavicular lymph node.
   - ***Retrograde lymphatic spread*** occurs once lymph vessel get blocked by malignant infiltration. In carcinoma breast retrograde spread occurs to opposite breast, opposite axilla, or to mediastinum. In melanoma, through dermal lymphatics and retrograde spread '***in transit nodules***' occur in the skin.
3. **Blood spread**

   Occurs through veins, as veins are thin-walled and infiltration is easier (Arteries contain elastic fibres in their wall, which resist malignant infiltration).

   Both by ***permeation*** (e.g. in renal cell carcinoma permeation through renal vein is common) and by ***embolisation*** (in other malignancies).

   Blood spread is commonly to lungs, bone (upper end of femur and humerus, ribs, skull), liver, brain, adrenals and other organs.

   In carcinoma prostate, due to increased pressure and venous blockade, retrograde venous spread occurs through vertebral venous plexus which causes **osteoblastic secondaries** in pelvic bones and vertebrae.
4. **Seedling:** For example
   - From lower lip cancer to upper lip as **kiss cancer.**

Kiss cancer

- Lip
- Bladder
- Cervix
- Vocal cord
- Vulva

   - Recurrence in the scar after surgery for malignancy, e.g. deposition of malignancy in the scar of SPC from bladder tumour.
   - Seedling in the peritoneal cavity from abdominal malignancy is common causing intractable ascites.



Fig. 1.519: Secondaries in neck. FNAC is the investigation to diagnose.



Fig. 1.520: Carcinoma ovary specimen. It was malignant teratomas of ovary. Other ovary was normal. So chemotherapy is used as an adjuvant. Patient was 23 years young female.



Fig. 1.521: Ethmoidal sinus tumour. Biopsy and CT scan is needed to confirm and assess the extent.

5. **Transcoelomic spread:** Spillage or dislodge of malignant cells occurs from primary site resulting in seedling on other organ, e.g. in carcinoma stomach secondaries in ovary (***Krukenberg tumour***) occurs due to transcoelomic spread. Here cells get deposited on the raw surface of ovary during ovulation (So it occurs in menstruating age group only).

GRADING OF TUMOUR

It signifies aggressiveness of tumour.

It is based on differentiation of tumour cells and mitotic activity.

Broder's grading of squamous cell carcinoma: Based on keratin/ epithelial pearls
Grade I: Well differentiated—>75% epithelial pearls
Grade II: Moderately differentiated—50-75% epithelial pearls
Grade III: Poorly differentiated—25-50% epithelial pearls
Grade IV: < 25% epithelial pearls

Special Features of Malignant Cells

- Independent and autonomous nature without any control or check.
- Normal telomeric shortening is altered. Normal cell divides for 40-60 times. Later telomere gets shortened and cell division stops. It is altered in malignancy with infinite cell division.
- Reduced cellular apoptosis. Normal cell has capacity to die once its function is over. It is normal programmed death of a cell. It is activated by tumour suppressor gene p53. If this gene loses its function, tumour will form.
- Tumour has got capacity to create and construct blood supply called as *angiogenic* capacity.
- Malignant cells invade through the basement membrane and spread through blood and lymphatics. It is through secretion of special enzymes, increased interstitial pressure, capacity to have motility, release of collagenases/proteases/integrins.
- Spread occurs by proliferation and permeation as well as embolisation.
- Creation of instability and alteration of existing tissue function (not obeying normal tissue function of that particular site).
- *Gompertzian growth*—rapid growth of a tumour occurs prior to its clinically detectable stage. Once it becomes clinically detectable which needs thirty generation of cell divisions (1 mm tumour is 10^9 cells), its growth slows down later. This late slow growth is due to decreased oxygen to tumour/by competition between host cells and tumour cells and also between tumour cells themselves.
- Tumour mutation occurs at different generation of divisions stabilising the tumour further.

STAGING OF THE TUMOUR

It is based on the size of the primary tumour, nodal spread and blood spread.

It is called as ‘TNM’ staging.

‘TNM’ staging is more relevant than grading in managing and predicting prognosis.

PARANEOPLASTIC SYNDROMES

Certain symptom complexes which are not specifically explained by the tumour, but are relevant, often problematic and life-threatening are called as paraneoplastic syndromes.



Fig. 1.522: Carcinoma tongue is more common in lateral margin. Incision biopsy from the margin is done here.

Incidence: Seen in 10% of patients.

INVESTIGATIONS FOR NEOPLASM

I. *BIOPSY*

‘Bio’ means life or tissue. *Opsis* means vision or microscopy.

Biopsy means study of tissues using microscopy.

OR *life by vision*

OR *vision for life* (to save life).



Fig. 1.523: Typical *malignant cachexia* observed in GIT malignancies. It is totally malnourished incapacitated situation.

Paraneoplastic syndromes

Syndrome	***Cause***	***Type of tumour***
Cushing’s syndrome ACTH	or ACTH like substance	Small cell carcinoma lung Neural tumour Pancreatic tumour
Syndrome of inappropriate	ADH	Small cell carcinoma lung
ADH secretion		Brain tumour
Carcinoid syndrome	Serotonin, bradykinin	Bronchial adenoma
		Gastric and pancreatic carcinoma
Hypoglycaemia	Insulin	Fibrosarcoma
	Insulin like substance	Hepatoma
Hypercalcaemia	PTH related peptide	Renal cell carcinoma Carcinoma breast, SCC lung Ovarian carcinoma, leukaemia
Polycythaemia	Erythropoietin	Renal cell carcinoma, hepatoma Cerebellar haemangioma
Myasthenia	Immunologic	Lung cancer
Acanthosis nigricans	Epidermal growth factor	Lung cancer, uterine cancer, gastric carcinoma
Dermatomyositis	Immunologic	Lung carcinoma, breast carcinoma
Clubbing and hypertrophic		Ca lung
Osteoarthropathy of fingers		
Migrating thrombophlebitis	Tumour product mucin	Ca pancreas, lung
(Trousseau phenomenon)	It activates clotting	



Figs 1.524A and B: Carcinoma cheek—advanced. It needs incision biopsy/orthopantomogram X-ray/CT of the part.



Fig. 1.525: Secondaries in skull—solitary.



Fig. 1.526: Carcinoma breast. Note the dilated veins on the surface. FNAC should be done to confirm the diagnosis.



Fig. 1.527: Soft tissue tumour of buttock. It could be sarcoma.



Fig. 1.528: CT picture of brain tumour—astrocytoma.

The pathological fracture is a transverse one, and although it unites readily, refracture is not unusual.

—Max E Lake



Fig. 1.529: Contrast MRI of spinal column showing extradural schwannoma.



Fig. 1.530: CT scan picture of retroperitoneal leiomyosarcoma.

Fig. 1.531: Alopecia (hair loss) is common after chemotherapy for cancers.

Types of biopsies

- Incision biopsy
- Excision biopsy
- Trucut biopsy
- Pap smear
- FNAC
- Frozen section biopsy
- Punch biopsy
- U/S guided biopsy
- Laparoscopic biopsy
- CT guided biopsy
- Thoracoscopic biopsy
- Endoscopic biopsy (gastroscopic or colonoscopic or through ERCP or through cystoscopy)
- Proctoscopic biopsy
- Open biopsy either laparotomy or thoracotomy or craniotomy using Dandy's brain cannula

- Biopsy is sent in 10% formaldehyde solution. In special occasions like, to assess receptors/to do histochemistry, biopsy is sent in low temperature; in normal saline or in specialised ingredients. Tissues are kept in formalin for 24 hours and then taken for 'cut up' by pathologists. Sections are done after making tissue blocks using microtome up to 5 microns thickness. These sections are placed on a slide for staining with haematoxylin and eosin. This is studied under microscopy by pathologist to give the report. Detailed history, findings, markings of the specimen should be done by the surgeon prior to sending the specimen. Bone specimens are decalcified in hydrochloric acid for 7-21 days before sectioning and staining. So its report will be delayed usually.
- Inadequate sampling and improper reports may be due to—limited tissue sent; tissues are nonviable; too superficial biopsy done; cautery use on the tissues; crushing effect on the tissues (gentle meticulous biopsy is important without rough handling and without over use of cautery on the required tissues).
- Specimens are kept for 6 weeks. Blocks are kept for 30 years. Slides are kept for 10 years.
- Risk of false positivity in malignancy should be remembered. It is probably due to contamination, interchanged specimens, wrong interpretation, ulceration, etc. Re-biopsy/reinterpretation/repeat sectioning may be needed in such situations.
- Often additional methods like deeper sections; extra blocks; special stains are needed. Special stains are PAS (Periodic Acid Schiff) for glycogen, mucin and fungi; D (diastase) PAS for mucin; Perls Prussian blue for iron in haemochromatosis; reticulin for fibrous tissue; elastin stains for fibrosis; congo red for amyloid; Ziehl-Neelsen for mycobacteria; Grocott for fungi; Giemsa stain for protozoa; Warthin-Starry stain for spirochaetes.

Incision Biopsy

- It is taken from the edge of the lesion as in ulcer, not from the centre as there is necrosis.
- Usually *two biopsies* are taken in ulcerative lesion from the edge—edge/wedge biopsy (edge is a line which limits

two parts; wedge is an area at two meeting parts like thick to thin, etc.

- Incision biopsy is contraindicated in a case of melanoma where excision biopsy is preferred.
- In secondaries in lymph nodes, FNAC is preferred. If it fails to give information, incision biopsy is done.

Note:

Biopsy taken from the centre of the lesion is only in post-radiation ulcer and syphilitic gumma. Because of irradiation there is no blood supply in the margin and tumour proliferates in the centre of the lesion.

Excision Biopsy

In small lesions excision biopsy is done, e.g. lymph node biopsy is done in case of lymphoma.

Trucut Biopsy

It is done using a specialised device wherein gun with trucut tip is inserted into the surface tissue/organ and gun is fired to close the punching tip of the needle to catch and cut adequate tissue. It is done in prostate, breast and surface tumours. It cannot be done to deeper tissues or tissues which are close to major vessels/structures.



Fig. 1.532: Trucut biopsy gun used for trucut biopsy. It gives histological diagnosis; it is also helpful to assess histochemistry.

FNAC (Fine Needle Aspiration Cytology)

It is cytological study of tumour cells to find out the disease and also to confirm whether it is malignant or not.

Procedure: It is done using ***23*** or ***24*** gauge needle fixed to specialised syringes which creates negative pressure for aspiration and contents are smeared on the slides. Dry slides as well as slides fixed with 100% methanol are used for study.

- It is done in parotid, thyroid, lymph node, breast and all other surface lesions.
- In follicular carcinoma of thyroid it is not very useful, as angioinvasion and capsular invasion which are specific cannot be detected.
- In lymph nodes it is useful for detecting secondaries and tuberculosis.
- U/S guided or CT guided FNAC are popular at present—especially when it is done from liver, lungs, kidneys, etc. (from deeper structures/organs).



Fig. 1.533: Fine needle aspiration cytology (FNAC) of thyroid. It is also done in breast, lymph node and other swellings. It is not done for testicular tumour.



Fig. 1.534: FNAC vacuum creator with loaded syringe [FNAC gun; *Cameco syringe* (Sweden) holder]. (*Courtesy:* Dr Krishna Upadhya, MD, Nandikoor Laboratory, Mangalore)

It is absolutely contraindicated in testicular tumour. Because tough tunica albugenia usually prevents tumour spread and once it get disrupted by FNAC, spread can occur.

Cytological study is done after Papanicolaou stain; Giemsa staining or Romanowsky staining.

Note:

- In 1934, Martin and Ellis did **FNAC** using 18 G needle with syringe with local anaesthesia use.
- Kline and Neal in 1973 did syringe needle aspiration using 18 G needle making dry smears.
- In 1982, A John Webb detailed standard FNAC using 21 G needle. Needle is passed obliquely into the lesion; constant suction is applied using ***Comeco syringe or braced thumb method***. With suction persisting needle is moved in 4 directions. Suction is gently released and needle is withdrawn. Needle is detached from syringe to draw air which is reattached to withdrawn needle to blow the content over a dry slide.
- In 1987, A Zajdello et al fine needle sampling of the tissue in question *without aspiration*. 25 G needle is used without a syringe. Needle is moved in various directions to detach the cells by sharp end of the needle; by capillary force, cells are conducted into the needle lumen. Air filled syringe is attached to needle to express cells into a glass slide. Trauma to tissue is said to be less; and feel of tissue consistency is better through held needle. It is called as Fine Needle Sampling Without Aspiration / Fine

Needle Non-aspirating Cytology (*FNNAC*)/Fine Needle Capillary Sampling (*FNCS;* as capillary action causes conduction of cells into needle).
- US guided/MRI guided/CT guided/Mammographic guided FNAC are available now which are more precise versions of localization of lesions to be aspirated.
- Ether with alcohol in equal proportion is used for wet fixation to stain Papanicolaou or H & E stains. Grace in 1994 used modified ultra Pap stain 3 changes – by rehydration of air dried smears using normal saline to cause RMBC haemolysis to restore cell transparency; by using mixture of 4% formaldehyde and 65% ethanol to reduce fixation time from minutes to few seconds; by using Richard Allen Haematoxylin 2 and cyto stain. Total time of staining in this modification is 90 minutes.

Advantages

- Very sensitive.
- Done on OP basis.
- Least invasive, safer, fast and cheaper.
- Anaesthesia is not required.
- Tumour dissemination through the track is not present (except in testicular tumour where it is not done).
- Presently DNA study of the cell can detect very early malignancy.

Disadvantages

- Negative result cannot rule out malignancy.
- Tissue study is not possible.
- Further studies not amenable.

***Note*:**
FNNAC—Fine Needle Non-aspirating Cytology is done in some tissues (in some centres). Here needle is passed into the tissue and material collected from the needle (without any aspiration) is studied for cytological analysis.

Frozen Section Biopsy

Frozen section is done whenever biopsy report is needed at the earliest. It is usually done in a pathology set up existing adjacent to the operation theatre. An unfixed fresh tissue is frozen (using CO_2) in a metal and sections are made and stained. It is technically difficult; processing and staining is of inferior quality and often it is difficult to give accurate results. But advantage is it is quick and surgeon can decide the further steps of procedure in same sitting like nodal clearance/type of resection to be done, etc.
- It is done in carcinoma breast or in follicular carcinoma of thyroid when FNAC fails.
- During surgery after resection of the tumour to look for (on table) the clearance in the margin and depth and also to study the lymph nodes for their positivity.

II. *IMMUNOHISTOCHEMISTRY*

It is detection of specific antigen using an antibody. Antibody labelled with a dye, binds to antigen in a section of tissue causing specific colours like brown, and determines its presence and distribution in the tissues. It is safe, specific and quick.
It is used in:
- *Neoplasia*
  - To confirm, to find differentiation, to detect metastases; to plan type of therapy.
  - To categorise leukaemias or lymphomas; either of ‘T’ cell or of ‘B’ cell type.
  - To find out site of origin of metastatic tumours, e.g. by doing prostate specific antigen in prostate cancer or doing thyroglobulin in thyroid carcinomas or clear cells in the lung in metastatic renal cell carcinoma.
  - Detection of receptors or molecules, e.g. estrogen receptors [ER] in breast cancer. ER positive has got better prognosis. Presence of onco-protein product c—erbB2 in breast cancer signifies poor prognosis.
  - Gastrointestinal stromal tumour (GIST) can be treated with imatinib if it shows CD 117 expression.
  - Endocrine tumours are assessed on ki67 proliferative index.
  - Cytokeratin marker for epithelial tumors like carcinoma; S100 and actin for glandular malignancy; S100 for melanoma; CD31 and CD34 for vascular malignancy; CA 125 for ovarian tumours; PSA for carcinoma prostate; CD3 and CD20 for lymphoma.
- *Infections*
  - Detection of specific antibodies to the antigens of certain specific infective agents like Epstein-Barr virus, cytomegalovirus, human herpes virus 8, herpes simplex virus, etc.
- *To identify abnormal accumulation* of various proteins like ά-1-antitrypsin; deposition of amyloid.
- *Assessment of immunoglobulins*.
- *Screening for mutations*.

III. *TUMOUR MARKERS*

- Tumour markers are biochemical indicators of presence of a tumour. They are not used for primary pathological diagnosis.
- They are of prognostic value.
- Presence of tumour marker signifies recurrence or residual tumour.

IV. *OTHER METHODS*

Electron Microscopy

- It is visualisation of tissue in very high magnification of 1000 × 500 000 in difficult deciding cases. But it is time consuming and expensive.

In Situ Hybridisation

- It is determination of presence or absence of a specific gene and its location in a fresh/fixed tissue sections using an oligonucleotide probe, targeting at specific DNA or RNA sequence.

Polymerase Chain Reaction (PCR)

DNA is amplified using this special method and detected by technique like electrophoresis. PCR can be done on blood or nontissue samples. It is highly sensitive, fast and safe. Disadvantages are—expensive and risk of DNA contamination.

Uses

- Detection of mutations in congenital conditions like von Hippel-Lindau disease (vHL gene); haemochromatosis (HFE gene); colorectal carcinoma (APC gene).

Tumour markers	
Category 1	
***Hormonal*:**	
Human chorionic gonadotrophin (HCG)	— Trophoblastic tumour, nonseminomatous testicular tumour
Calcitonin	— Medullary carcinoma of thyroid
Catecholamines and VMA	— Pheochromocytoma
Ectopic hormones	— In tumours of paraneoplastic syndromes
Category 2	
Isoenzymes:	
Prostatic acid phosphatase	— Carcinoma prostate
Neuron specific enolase	— Small cell carcinoma lung, neuroblastoma
Category 3	
Oncofetal antigens:	
Alpha fetoprotein	— Liver cancer, nonseminomatous germ cell tumour
Carcinoembryonic antigen (CEA)	— Carcinoma colon (common). Carcinoma pancreas, lung, stomach and breast
Category 4	
Mucin and other proteins:	
CA—125 (Carbohydrate antigen)	— Ovarian cancer
CA—15-3	— Breast cancer
CA—19-9	— Pancreatic and colon cancer

- Gene rearrangements in different conditions like lymphoma or other diseases can be detected by PCR (clonality).
- Assessment of loss of heterozygosity in tumours like oligodendroglioma (1p, 16q).
- PCR study for infections like tuberculosis.
- Fluorescence *in situ* hybridisation (FISH)
- It is a type of cytogenetics (study of chromosomes) that can be done in fixed or fresh tissues; used in haematological malignancies or trisomy 23. It is safe and quick.

MANAGEMENT STRATEGY FOR CANCERS

- *Diagnosis* is confirmed by biopsy from primary usually.
- *Evaluations* for staging—metastatic work up.
- *Approaches for primary*—surgery/radiotherapy/chemotherapy.
- *Approaches for secondary.*
- *Palliation* in advanced stage—palliation of *distressing* symptoms.

Treatment of tumours

- Surgery—wide excision/radical
- Radiotherapy—curative/palliative
- Chemotherapy
- Immunotherapy
- Gene therapy



Fig. 1.535: Advanced aggressive malignancy face may be carcinoma or sarcoma.

Have, goals, they give direction, purpose and meaning to life.



Fig. 1. 536: Advanced fungating carcinoma of breast.



Fig. 1.537: Recurrent secondaries in neck after radical neck dissection.



Fig. 1.538: Anal canal carcinoma (SCC).



Fig. 1.539: Secondaries in ovaries—Krukenberg tumour.



Fig. 1.540: Malignant primary nerve sheath tumour (MPNST).

Malignancies which are curable

- Basal cell carcinoma
- Adamantinoma
- Verrucous carcinoma
- Marjolin's ulcer
- Papillary carcinoma of thyroid
- Carcinoma colon

Sarcomas which spread to lymph nodes

- Synovial sarcoma
- Ewing’s sarcoma
- Lymphosarcoma
- Kasposi’s sarcoma
- Rhabdomyosarcoma
- Angiosarcoma

R. Skin Tumours

CHAPTER OUTLINE

- Anatomy
- Classification of Skin Tumours
- Skin Adnexal Tumours
- Dermatofibroma
- Dermatofibrosarcoma Protuberans
- Keratoacanthoma
- Rhinophyma
- Seborrhoeic Keratosis
- Squamous Cell Carcinoma
- Marjolin's Ulcer (1828)
- Basal Cell Carcinoma
- Turban Tumour
- Naevi
- Melanoma

ANATOMY

Epidermis: Layers

- Stratum corneum—1/3 of epidermis
- Stratum granulosum—1-3 layers of cells
- Stratum spinosum—3-5 layers of cells
- Stratum basale—columnar cells
- Stratum lucidum is seen in palms and sole.

Melanocytes—one melanocyte is seen for every 10 basal cells
Langerhan's cell—a clear cell in stratum spinosum.
Basement membrane is seen at dermo-epidermoid junction.

Epidermis is avascular.

Epidermis is 5% of the total skin. It is thickest (0.5-1 mm) in palm, sole, back and buttocks. It is thinnest in eyelids (0.05-0.09 mm).

Dermis—contains collagen fibres, elastic fibres, capillaries, venules, arterioles, lymphatics, nerves, erector pilorum muscle, sweat glands (eccrine, apocrine), sebaceous glands. Merkel cells, Meissner and Pacinian corpuscles are receptors in dermis. Dermis constitutes 95% of the skin. Dermis is 15-40 times thicker than epidermis.



Fig. 1.541: Skin anatomy.



Fig. 1.542: Extensive infective destruction of the eyelids, face exposing bone and deeper structures. Maggots are seen on the surface. It mimics carcinoma but it was of infective origin. *Phagedena* is infective destruction without proliferation. It often mimics malignancy.

CLASSIFICATION OF SKIN TUMOURS

Benign

Epidermal

- Seborrhoeic keratosis.
- Trichilemmal tumour.
- Sebaceous adenoma.
- Sebaceous epithelioma.
- Hydrocystoma, syringoma, spiradenoma.

Probability is the rule of life, especially under the skin. Never make a positive diagnosis.—**William Osler**

Dermal tumour

- Neurofibroma.
- Dermatofibroma.

Malignant

- Squamous cell carcinoma.
- Basal cell carcinoma.
- Melanoma.
- Malignant skin adnexal tumour.
- Secondaries in the skin. Sister Joseph nodules around umbilicus.

Classification of skin tumours

Epidermal

Benign—papilloma, seborrhoeic keratosis

Malignant—BCC, SCC

Melanocytic

Benign—all types of naevi

Malignant melanoma

Skin adnexal tumour

Benign—syringoma, hidradenoma, sebaceous adenoma, trichofolliculoma, trichilemmoma

Malignant—hidradenocarcinoma, sebaceous carcinoma

Dermal tumours

Neurofibroma, dermatofibroma, dermatofibrosarcoma protuberans

- *Skin cancers* (SC) *are also classified as melanotic (MSC) or nonmelanotic (NMSC)*. NMSC are *commonest*. Patient who had BCC/SCC has higher risk to develop 2nd new skin cancer (35% in 3 years; 50% in 5 years). *NMSC can be low risk or high risk groups*. Lesion more than 2 cm in trunk and limbs; more than 1 cm in forehead and neck; more than 6 mm in central face; poorly defined margin; recurrent type; moderate or poor differentiation; perineural/vascular invasion; presence of immunosuppression; previous RT – are *high risk* lesions.

Note:

- Multiple sebaceous adenomas with visceral malignancy are called as *Torre-Muir syndrome*.
- Secondaries in skin can occur like ***Sister Joseph nodules*** around the umbilicus.



Fig. 1.543: Abdominal wall cutaneous secondaries; primary is from carcinoma stomach.



Fig. 1.544: Sister Joseph secondary nodule in umbilicus.

SKIN ADNEXAL TUMOURS

Classification

- *Eccrine gland tumours*: Syringoma, hidradenoma, syringocystadenoma.
- *Hair tumours*: Trichoepithelioma, tricholemmoma.

Features

- They are tumours arising from accessory skin structures like sebaceous glands, sweat glands, hair follicles.
- It is not uncommon. It may be **benign** or **malignant**.
- It presents as protruding well-localised swelling in the skin.
- *Trichoepithelioma* is usually seen in nasolabial fold; mimics BCC; presents as small cutaneous nodule.
- *Tricholemmoma* is also called as *naevus sebaceous of Jadassohn*. It is a hamartoma from hair follicle which can turn into BCC in 10% of cases.



Fig. 1.545: Skin adnexal tumour (benign) in the face.



Fig. 1.546: Skin adnexal tumour (malignant) turned out to be of hair follicle origin.



Fig. 1.548: Skin adnexal tumour. Vascularity is increased and it is malignant.



Fig. 1.547: Skin adnexal tumour—preauricular region.

- *Adenoma sebaceum* is seen in tuberous sclerosis as red papules in face which appears below 10 years. It is often called as *Bourneville's disease*.
- *Calcifying epithelioma of Malherbe/pilomatrixoma* is benign hair matrix cell tumour seen below the age of 10 years, containing basaloid and eosinophilic ghost cells with calcification.
- *Malignant skin adnexal tumour* forms a nodular, hard, indurated swelling in the skin, often with involvement of regional **lymph nodes** which are hard and nodular**.**
- It mimics **squamous cell carcinoma of skin.**

Differential Diagnosis

- Squamous cell carcinoma of skin.
- Dermatofibrosarcoma protuberans.

Diagnosis

- Biopsy—excision or incision type.
- FNAC of lymph node.

Treatment

- Benign tumour—excision.
- For malignant tumour—wide excision and regional lymph node block dissection when required.

Prognosis is good. It is better than squamous cell carcinoma.

Note:

- **Merkel cell carcinoma** is aggressive malignant condition arising from neuroendocrine receptor cells of the skin (dermis) which mimics histologically oat cell carcinoma. It is common in white elderly females (4 : 1) may be due to UV rays. Treatment is wide excision with radiotherapy.
- **Adenocarcinoma arising from the apocrine glands** of skin is called as *extramammary Paget's* disease of skin (intraepidermal adenocarcinoma) commonly observed in perianal region.
  - It can occur in genitalia or in axilla (more apocrine glands). In 25% of cases, the condition is associated with an *underlying in situ* or invasive carcinoma. *Presentation* is like red plaque/white/depigmented areas/crusts/scales mimicking dermatitis, eczema, fungal infections. Condition is often associated with GI or urinary malignancies (40%). Biopsy of lesion, CT evaluation for other malignancies, wide local excision and radiotherapy—are the management principles.

It's when the fish opens his mouth that he gets caught.

DERMATOFIBROMA (Sclerosing Angioma or Subepithelial Benign Nodular Fibrosis)

- It is a benign tumour arising from skin from dermal dendritic cells.
- It is formation of firm, single or multiple nodules occurring commonly in extremities (limbs).
- It can be red, brownish yellow (due to lipid), or bluish black (due to haemosiderin).

  Histologically, spindle cells are arranged in 'mat like' or 'cart-wheel' pattern.
- It is also called as ***dermal histiocytoma.***

Differential Diagnosis

- Squamous cell carcinoma of skin.
- Melanoma.
- Basal cell carcinoma.
- Skin adnexal tumour.

Treatment

- Excision.

DERMATOFIBROSARCOMA PROTUBERANS

- It is a low grade fibrosarcoma which grows slowly but persistently. It arises from *dermal fibroblasts*.
- Occurs in head and neck, limbs, abdominal wall and back–Trunk is commonest site (50%).
- It is not a rare entity, often attains a large size with multiple, nodular, hard, swelling with often involvement of lymph nodes. Malignant spindle cells are seen histologically.
- Rarely it spreads into lungs through blood.
- It mimics squamous cell carcinoma of skin and skin adnexal tumour.
- Positive for CD34 and ring chromosome.
- With melanin pigmentation it is called as *Bednar's tumour*.

Diagnosis

- Biopsy of the lesion.
- Chest X-ray, CT Scan.
- FNAC of the lymph node.

Treatment

- Wide excision and follow up.
- Recurrence is common—50%.
- Prognosis is good.

KERATOACANTHOMA (MOLLUSCUM SEBACEUM)

- It is an overgrowth and subsequent spontaneous regression of ***pilosebaceous glands*** with proliferation of squamous cells protruding out of the duct which are common in adult males (3:1) and places where more sebaceous glands are found.
- Cause is unknown. It may be self limiting, benign neoplasm of viral origin (papilloma virus).



Figs 1.550A and B: Dermatofibrosarcoma.



Fig. 1.549: Dermatofibroma in leg.



Fig. 1.551: Malignant skin tumour with ulceration of the skin over chest wall. Axillary nodes were enlarged in this patient.

- It presents as a rapidly growing, painless, single swelling in the skin with central brown area.
- It grows usually for 4 weeks and later shows spontaneous regression in 4 months. It is a pseudomalignancy.
- During regression phase, central area separates from the lesion leaving a deeply seated scar.

Clinical Features

- Mobile, hard, painless, nontender, lump with a *central brownish volcano* like area. It is common in face. It can be recurrent in lips and fingers.
- Lymph nodes are not enlarged.
- *It is totally benign.*

Differential Diagnosis

- Squamous cell carcinoma.

Treatment

- Excision. The tissue is sent for histopathological study.

RHINOPHYMA (Potato Nose) (Bottle Nose)

- It is a **glandular form of acne rosacea** causing immense thickening of **distal part of skin of nose** with visible openings of sebaceous follicles. Nose is bluish red in colour with dilated capillaries.
- It is due to hypertrophy and adenomatous changes in sebaceous glands.
- Male to female ratio is 12:1. 3% cases may have occult BCC in it. But rhinophyma itself will not cause BCC.

Treatment

- Excision of excess tissue and reconstruction.



Fig. 1.552: Dermatofibrosarcoma protuberans.



Figs 1.553A and B: Typical keratoacanthoma with central brownish area. It is self-limiting disease. It never turns into malignancy but looks like SCC.



Figs 1.554A and B: Rhinophyma. Typical look and site.

SEBORRHOEIC KERATOSIS (Seborrhoeic Wart, Basal Cell Papilloma)

It is a benign overgrowth of the basal layer of epidermis with excess of small darkly stained basal ce1lls, which protrudes from the surface of the epidermis to give oily appearance.



Figs 1.555A to C: Seborrhoeic keratosis in face, ear and in periumbilical region. It is not a premalignant condition.

Features

- It is common in elderly. Common sites are the back, face, neck.
- It grows slowly with widening in area without altering in thickness.
- It often gets infected but uncommon to bleed on touch.
- It is pigmented due to melanin and so mimics naevus or melanoma.
- It is common Caucasians. It is familial—autosomal dominant gene related.
- Often when it falls off, it leaves a pale pink patch on the skin with visible small surface capillaries.
- It is not a premalignant condition (Note: Solar keratosis is a premalignant condition).
- It is hard and stiffer than normal skin.
- Lymph nodes are not involved.
- It does not occur in palms and soles.
- It can be picked off from the skin.
- *'Stuck on' appearance is characteristic.*

Differential Diagnosis

- Melanoma, Pigmented BCC, Naevus,

Treatment

- Excision cures the condition.
- Shave excision or curettage can be done.

PREMALIGNANT CONDITIONS OF THE SKIN

- *Bowen's disease* of skin: It is an intradermal precancerous condition. It presents as brownish induration with a well-defined edge. Microscopically it contains large clear cells. Eventually, it will turn into carcinoma (10%). Entire epidermis is disorganised and irregular. It shows parakeratosis, acanthosis, hyperkeratosis. Chronic solar exposure; arsenic; human papilloma virus 16 are the aetiologies. Topical 5 fluorouracil or imiquimod; 4 mm margin surgical excision; MOHS; laser are the therapeutic options

  Erythroplasia of Queyrat is Bowen's disease occurring over glans penis
- *Paget's disease* of nipple
- Leukoderma
- *Senile* or *solar keratosis:* It is multiple, dry, hard, scaly, lesions on the face and back of hands due to exposure to sunlight, occurs after middle age. This is sunray induced hyperkeratosis with irregular, firm, raised or flat patch. Squamous cell carcinoma develops later after 10 years. Lesion in such situation becomes non-healing, indurated with central crust with everted edge; hard enlarged regional lymph nodes may be palpable
- *Radiodermatitis,* arsenic dermatitis
- *Chronic scars* develop into Marjolin's ulcer
- Albinism
- *Xeroderma pigmentosa* wherein there is defective DNA excision repair mechanism. It turns into malignant melanoma, BCC, SCC
- *Chronic lupus vulgaris*
- *Prolonged irritation of skin* by various chemicals like dyes, tar, soot

SQUAMOUS CELL CARCINOMA (Epithelioma) (Khangri Cancer) (Chimney Cancer)

- It occurs in premalignant conditions like Bowen's disease, Paget's disease, leukoplakia, chronic scars, chemically induced chronic irritation, radiodermatitis, senile keratosis, e.g. Khangri cancer in Kashmir, Chimney scrotal cancer, Kang cancer of Tibetans.
- It arises from squamous layer of the skin. Usually it occurs in a pre-existing predisposing lesion; occasionally can develop in *de novo* skin.
- It can be grossly proliferative/ulcerative/ ulceroproliferative/ red plaque like. Proliferative type is cauliflower like.
- It expresses cytokeratins one and ten.
- It is the 2nd (20%) most common skin cancer.
- It is common in males.
- *Exposure to UV B rays* (ultraviolet rays are A,B,C types) causes SCC by direct carcinogenic effects on keratinocytes, unrepaired mutations, decreased immune surveillance response, inhibition of tumour rejection, mutation of p53 suppressor gene (seen in 90% SCC).



Fig. 1.556: Squamous cell carcinoma eyelid. Note the involvement.



Fig. 1.557: Squamous cell carcinoma on the labia.

Aetiology of SCC

- Bowen's disease. Exposure to UV B rays
- Chronic scars and sinuses (burns; osteomyelitis; venous ulcer)
- Lupus vulgaris
- Solar keratosis—20% chances of SCC
- Senile keratosis
- Xeroderma pigmentosa
- Tobacco use
- Viral cause—human papilloma virus (HPV) five and sixteen
- Chemically induced chronic irritation
- Radiodermatitis
- ***Kangri cancer***—it is due to constant placing of the hot charcoal pot (kangri) over the abdominal wall to control cold. Seen in Kashmir
- ***Kang cancer*** is seen in buttocks and heel of Tibetans due to sleeping over oven bed to control cold
- ***Chimney sweep cancer*** is observed in scrotum due to constant irritation by tar
- *SCC is more common in immunosuppressed individuals*, immunosuppressive drugs like azathioprine, cyclosporine, prednisolone; risk becomes 10% in 10 years of intake of these drugs and 40% in 20 years.

Common Sites are:

- Dorsum of hand, limbs, face, and skin of abdominal wall SCC can occur in external genitalia, mucocutaneous junction, oral cavity, respiratory system, oesophagus, gallbladder, in urinary bladder as metaplasia from transitional cell lining.



Figs 1.558A and B: Squamous cell carcinoma in the forearm and foot. It is proliferative cauliflower like lesion.

Finding fault is easier. Finding remedy is the one which is more difficult.

Clinical Features

- An ulcerative or ulceroproliferative lesion.
- **Raised** and **everted edge**.
- **Indurated** base and edge.
- Bloody discharge from the lesion.
- Regional lymph nodes are commonly involved, which are hard, nodular, initially mobile but eventually fixed to underlying structures.
- Usually blood spread does not occur.

Variants

- *Marjolin's ulcer* which occurs in chronic scar is a type of squamous cell carcinoma without lymph node spread.
- *Verrucous carcinoma* is a squamous cell carcinoma, commonly occurring in mucous membrane or mucocutaneous junction without lymph node spread. It is dry, exophytic, warty, indurated growth. It has good prognosis. It is a curable malignancy.
- A rare multiple self healing SCC is observed usually in face as familial autosomal dominant (Ch 9q) disease in Western Scotland-*Ferguson-Smith syndrome.*

Histology

- Malignant whorls of squamous cells with epithelial or **keratin pearls** are characteristic feature.
- Spindle cells, invasion, deep and peripheral margin clearance.

Broder's classification

I: Well differentiated: 75% or more keratin pearls
II: Moderately differentiated: 50-75% keratin pearls
III: Poorly differentiated: 25-50% keratin pearls
IV: Undifferentiated/anaplastic: <25% keratin pearls. It is seen in 20% of SCCs.

Differential Diagnosis

- BCC.
- Melanoma.
- Keratoacanthoma.
- Skin adnexal tumours.
- Actinic keratosis.
- Pyogenic granuloma.

Investigations

- Edge biopsy.
- FNAC from lymph node.



Fig. 1.559: Squamous cell carcinoma foot—ulceroproliferative lesion with fungating inguinal node secondaries. It is an advanced disease. Opposite inguinal nodes are also significantly enlarged.



Fig. 1.560: Squamous cell carcinoma and BCC in face of a patient.

TNM staging for skin cancer other than melanoma

Tumour	***Node***	***Metastasis***
T 0 no tumour found	N 0–No nodes	M 0–No distant spread
T is Tumour *in situ*	N 1–Regional nodes ++	M 1–Distant spread ++
T 1 Tumour < 2 cm		
T 2 Tumour 2-5 cm	G1 – Low grade	
T 3 Tumour > 5 cm	G2 – Moderate grade	
T 4 Spread to cartilage, muscle or bone.	G3 – High grade	



Figs 1.561A and B: Recurrent SCC in amputated stump. Note the enlarged significant lymph nodes in the groin.

Treatment

- **Radiotherapy** using radiation needles, moulds, etc. is given.
- **Wide excision**, *2 cm* clearance followed by skin grafting or flaps**.**
  (Presently for tumour less than 2 cm, 4 mm clearance and for tumour more than 2 cm, 1 cm clearance is sufficient). Wide excision should show *clearance* both at margin as well as in the depth. If muscle, fascia, cartilage are involved, it should be cleared. Reconstruction is usually done by primary split skin grafting (*SSG/Thiersch*). Delayed skin grafting also can be done once wound granulates well. Often flaps of different types may be needed depending on the site of lesion.
- **Amputation** with one joint above.
- For lymph nodes, block dissection of the regional lymph nodes is done.
- Curative radiotherapy (RT) is also useful in tumours which are not adherent to deeper planes or cartilage as SCC is radiosensitive. It is also useful in recurrent SCC and in patients who are not fit for surgery. A dose of 6000 cGy units over 6 weeks; 200 units/day is used. Recurrence after RT is treated by surgical wide excision.
- In advanced cases with fixed lymph nodes, **palliative external radiotherapy** is given to palliate pain, fungation and bleeding.
- **Chemotherapy** is given using methotrexate, vincristine, bleomycin.
- Field therapy using cryo probe or topical fluorouracil or electrodessication.

Prognostic factors in SCC

- Tumour size > 2 cm is worse
- Tumour border—ill-defined border is worse
- Associated immunosuppression is worse
- Differentiation—poorly differentiated is worse
- Perineural involvement has worse prognosis
- Invasion; depth < 2 mm has got better prognosis; depth more than 16 mm has got worst prognosis
- Local recurrence rate is 20%. Recurrence period is 5 years, not beyond

Verrucous Carcinoma (Fig. 1.563)

- Dry, exophytic, warty growth.
- No lymph node spread.
- No blood spread.
- Surgery is the treatment—wide excision.
- No radiotherapy.
- Examples:
  - Giant condyloma acuminatum (Buschke-Lowenstein tumour, Verrucous carcinoma of genitalia).



Fig. 1.562A

Moles must never be cauterised or curetted.



Fig. 1.562B

Figs 1.562A and B: *Carcinoma cunniculatum*—in heel and under great toe which is a low grade verrucous type of SCC.

- Oral florid verrucous carcinoma.
- Verrucous carcinoma of foot (plantar aspect)—***carcinoma cuniculatum.***

MARJOLIN'S ULCER (1828)

- It is a well-differentiated squamous cell carcinoma which occurs in chronic scars like burn scar, scar of venous ulcer.
- As it develops in a scar due to chronic irritation and there are **no lymphatics** in scar tissue, **it will not spread to lymph nodes**.
- As scar is relatively avascular it grows slowly. As scar does not contain nerves, it is painless.
- Once it reaches the normal skin it may behave like any other squamous cell carcinoma, i.e. it will spread to lymph nodes. It occurs in *unstable scar of long duration*.

Clinical Features

- History of pre-existing venous ulcer or burn scar.
- Indurated, painless, nontender, ulcer with raised and everted edge.
- Biopsy from the edge **confirms the diagnosis.**

Treatment

- **Wide excision**.
- In case of large ulcer, **amputation** is required.
- ***Radiotherapy should not be given*** as it may turn into poorly differentiated squamous cell carcinoma.
  It is a curable malignancy.



Fig. 1.563: Verrucous carcinoma of penis. It is an exophytic, dry, warty, locally malignant lesion (Squamous cell carcinoma).



Fig. 1.564: Marjolin's ulcer in a burn scar.



Fig. 1.565: Marjolin's ulcer foot in a pre-existing burns scar. It is a well-differentiated squamous cell carcinoma occurring in an unstable scar of long duration.



Figs 1.566A and B: Marjolin ulcers over elbow and over foot. First one occurred over elbow in a pre-existing snakebite scar. Second one occurred in a long-standing venous ulcer.

BASAL CELL CARCINOMA (Rodent Ulcer)

It is a low grade, locally invasive, carcinoma arising from basal layer of skin (or adnexal basal layer of hair follicle) or muco-cutaneous junction. ***It does not arise from mucosa.***

- It is the commonest (70%) malignant skin tumour.
- It is more common in white-skinned people than blacks.
- Common in places where exposure to *UV light* is more (***Australia).***
- Other causes are—arsenics, coal tar, aromatic hydrocarbons, skin tumour syndromes.
- It is common in males, common in middle-aged and *elderly*.
- Common site is ***face***—above the line drawn between angle of mouth and ear lobule (90%)—*Onghren's line*.
- It is called as ***tear cancer*** because it is commonly seen in area where tears roll down.
- Often it can occur in muco-cutaneous junctions.
- *Basal cell naevus syndrome* (Gorlin syndrome) with BCC; medulloblastoma; bifid ribs.
- ***It is only locally malignant***. It does not spread through lymphatics nor through the blood. But it erodes deeply into local tissues including cartilages, bones causing extensive local destruction. Hence the name **"*rodent ulcer*".**

Types

1. Nodular.
2. Cystic/nodulocystic.
3. Ulcerative.
4. Multiple, often associated with syndromes and other malignancies.
5. Pigmented BCC—mimics melanoma.
6. Geographical or field fire or forest fire BCC is wide area involvement with central scabbing and peripheral active proliferating edge.
7. **Basisquamous**—behaves like squamous cell carcinoma which spread into lymph nodes. BCC which has not been treated for long time can turn into Basisquamous carcinoma.

Note:
Nodulocystic and noduloulcerative is the commonest form (70-90%).



Fig. 1.567: Basal cell carcinoma.



Fig. 1.568: Rodent ulcer lateral aspect of the eyebrow. Note the typical beaded edge.

Adversity reveals genius, prosperity conceals it.



Fig. 1.569: BCC in perianal region. It is nodular type. Wide excision is required.



Figs 1.570A and B: BCC in different places—below the ear and in the inner angle of the eye.



Fig. 1.571: Note the common site of BCC—in the face above the line drawn between angle of mouth and ear lobule—*Onghren's* line.



Figs 1.572A and B: Nodular BCC in the nose.



Fig. 1.573: *Sebaceous epidermal naevus*. It is common in females, often extensive, begins in childhood. It needs surgical excision and skin grafting. It has got 10% chances of turning into BCC.



Figs 1.574A to C: Basal cell carcinoma in different locations. Note the nodularity and ulceration. Note the beaded edge.

Clinicopathological Types

a. *Superficial type*—small buds of tumour masses.
b. *Morpheic type*—dense stroma with basal cells and type IV collagen; spreads rapidly.
c. *Fibroepithelioma type* of Pinkus shows elongated cords of basaloid cells with mesh work.

It contains outer palisading columnar cells with central polyhedral cells but no *prickle cells* or *keratinisation*.

Clinical Features

- Ulcer on the face in a middle-aged man which is nontender, dry, slowly growing, nonmobile, with raised and beaded edge with central scab, often with central depression or umbilication.
- Site of beading signifies the area of active proliferating cells. In between beaded areas dormant nonactive cells are present.
- No lymph node or blood spread occurs. Due to large sized tumour cells/tumour cluster, it does not spread through lymphatics.

High-risk BCC

- BCC can be low risk or high-risk
- Size > 2 cm
- Near the eye/nose/ear
- Ill-defined margins
- Recurrent tumours
- Immunosuppressed individuals

Differential Diagnosis

1. Squamous cell carcinoma.
2. Melanoma.
3. Keratoacanthoma.
4. Seborrhoeic keratosis.

Investigations

Edge biopsy, X-ray of the part, CT scan.



Fig. 1.575: BCC lesions in different places (multiple).

Treatment

- It is ***radiosensitive***. If lesion is away from vital structure (like away from eyes), then curative radiotherapy can be given. **Radiotherapy is not given, once it erodes cartilage or bone.** RT is *not given* to BCC of ear and close to lacrimal canaliculi.



Figs 1.576A to C: Surgical wide excision in BCC.

- *Surgery:*
  - Wide excision (1 cm clearance) with skin grafting, primary suturing or flap (Z plasty, rhomboid flap, rotation flap) is the procedure of choice.
  - Laser surgery.
  - Cryosurgery.
  - **MOHS** (*Microscopically Oriented Histographic Surgery*) (Federic E Mohs, American Surgeon) is useful to get a clearance margin and in conditions like BCC close to eyes, nose or ear, to preserve more tissues. MOHS is becoming popular in BCC/dermatofibrosarcoma protuberans/melanoma. Procedure is done by dermatological surgeon along with a histotechnician/histologist. Under local anaesthesia, a saucerised excision of the primary tumour is done and quadrants of the specimen are mapped with different colours. Specimen is sectioned by histotechnician from margin and depth, and it is stained using eosin and haematoxylin. It is studied by MOHS surgeon or histologist. Residual tumour from relevant mapped area is excised and procedure is repeated until clear margin and clear depth are achieved. Clearance must be complete and proper in BCC otherwise there will be very high chance of recurrence (70%).

Indications for surgery

- Rodent ulcer eroding into cartilage or bone
- BCC close to the eye
- Recurrent BCC

TURBAN TUMOUR

It is a descriptive term wherein entire scalp looks like a turban because of multiple scalp swellings. It can be due to *multiple cylindroma; multiple hidradenomas; subcutaneous neurofibromas; nodular multiple basal cell carcinoma.*

- *Multiple cylindroma* is usually considered disease under this term. Cylindroma is a variant of eccrine spiradenoma (skin adnexal tumor). Multiple firm pinkish nodules in the scalp are the presentation in multiple cylindroma. They are rare, often locally malignant, grows slowly over the span of many years to cover entire scalp with reddish lobulated lesion.
- Hidradenoma is a rare benign sweat gland tumour. Multiple tumours commonly look like a turban in the scalp. They are painless, disfiguring, cosmetically problematic, soft, boggy, non-fluctuant, non-compressible cutaneous swellings; commonly observed in middle age group.
- Multiple sebaceous cysts over the scalp mimic the same.
- *Management* is initial biopsy to find out the cause; then wide excision with skin grafting.

NAEVI

- It is a *hamartomata* of melanocytes due to excessive stimulation.
- It may present during birth or appear later in life.



Fig. 1.577: Different types of naevi.

Types

1. ***Hairy mole*** is a mole with a hair growing on its surface.
2. ***Nonhairy mole.***
3. ***Blue naevus.*** It is seen in children. It is located deep in the dermis, hence appears blue. It is common in buttock (Mongolian spot), hand, feet.
4. ***Junctional naevus***. It lies centred in the junctional layer (basal layer) of the epidermis as clusters. It is immature, unstable and premalignant. Microscopically there is proliferation of melanocytes at the epidermal junction. Features of malignant transformation are—change in the size, colour, bleeding, ulceration, crusting, satellite spots.
5. ***Compound naevus***. It is combination of intradermal and junctional naevus. Intradermal part is inactive but functional part is potentially malignant.
6. ***Juvenile melanoma (Spitz naevus)*** (It is a misnomer). It appears as junctional like mole before puberty. It is seen in children on face. They present as brownish red nodular lesion which needs always excision.
7. ***Hutchinson's freckle***. It is seen in elderly with large area of dark pigmentation. In the macular stage it is smooth and brown. In the tumour stage it is dark and irregular. It can turn into melanoma commonly.
8. ***Halo naevus*****:** Halo of depigmentation around the pigmented naevus. This halo is due to antibody response to melanocytes. Halo naevus is often seen along with vitiligo. Similar halo may develop around a malignant melanoma lesion.
9. ***Intradermal naevus:*** Cluster of dermal melanocytes is seen without junctional component. Common in face.
10. ***Spindle cell naevus*****:** It is dense, black pigmented lesion containing spindle cells and atypical melanocytes at dermo-epidermal junction; seen in females on high with malignant potential.
11. ***Naevus spilus***: It is hyperpigmented speckles throughout, also called as *speckled lentiginous naevus*. Malignant potential is rare.
12. ***Naevus of Ota*** is dermal melanocytic hamartoma seen in distribution area of trigeminal nerve (ophthalmic /maxillary). It is seen in oriental and African race adolescent females (thigh) with a hormonal influence.
13. ***Naevus of Ito*** is similar lesion occurring in shoulder region.
14. ***Dysplastic naevus*** is proliferation of atypical melanocytes from epidermal basal layer having variegated irregular look; it is usually > 5 mm in size; can be familial; 10% cases may turn into superficial spreading melanoma.



Fig. 1.578: Hairy naevus.



Fig. 1.579: Congenital naevus.



Fig. 1.580: Compound naevus.



Fig. 1.581: Junctional naevus.



Fig. 1.582: Intradermal naevus.

Treatment

Excision. Always should be sent for histopathology.

Note:

- *Giant naevus* is naevus more than 1% of body surface area or more than 20 cm in size. Giant congenital pigmented naevus (GCPN) often shows dermatomal distribution. Pigment cells spread from epidermis to fat and muscle often. It may turn into melanoma (5% risk). Such melanomas are usually axial; is usually associated with retroperitoneal / intracranial melanosis. Curettage, dermabrasion, laser, excision and SSG are the treatment options.
- *Mongolian spot* is a blue brown/grey pigmented macular area which is seen in sacral region during birth and after initial intense pigmentation regresses fully in 7 years.
- Normal number of melanocytes releasing abnormally higher number of melanin granules is called as *freckle*/ephilis.

MELANOMA

- It is a malignant tumour arising from epidermal melanocyte which is *most aggressive* cutaneous malignant tumour.
- It is of *neural crest* (ectodermal) origin.
- It is 20 times more commonly seen in *whites* than blacks.



Figs 1.583A and B: Giant congenital pigmented naevus (*Courtesy:* Dr Murali Keshav, MD, Paediatrician, KMC, Mangalore).

- *Melanoblast*: Primitive cell derived from the neural crest.
- *Melanocyte*: The cell which synthesises melanin is located in the basal layer (melanocyte : basal cell : : 1 : 10).
- *Melanophores* are pigment melanin carriers through dendrites into the epidermis.
- *Melanophages* are macrophages having melanin pigment.
- Melanoblasts and melanocytes contain DOPA oxidase enzyme and synthesise melanin. They show +ve DOPA reaction.
- Melanophores and melanophages show –ve DOPA reaction.
- Melanin synthesis is controlled by melanocyte stimulating hormone, ACTH and sex hormones.

DOPA reaction:

$$\text{Tyrosine} \xrightarrow[\text{Tyrosinase}]{} \text{DOPA} \xrightarrow[\text{Oxidase}]{} \text{Melanin}$$



Fig. 1.584: Xeroderma pigmentosa with BCC in the nose. Such patients are prone for other skin malignancy like melanoma also. There is defective DNA excision repair.



Fig. 1.585: Clark's level.

- Its incidence is equal in both sexes.
- Its incidence is increasing over the years.
- 5 % of skin cancers are melanomas.
- It is most common in Queensland, Australia. Auckland, New Zealand.

Sites

Sites of melanoma

- Head and neck—25%
- Trunk—25%
- Lower limb—25%
- Upper limb—11%
- Other sites—14%

- In females, *leg* is the commonest site.
- In males, the *front* or *back* of the trunk.
- In the Bantu tribe, *sole* is the commonest site.

Other sites:

Eyes (iris, ciliary body, choroids), mucocutaneous junction (anorectal region, genitalia), head and neck (meninges, oropharynx, nasopharynx, paranasal sinuses).

Risk Factors

- Exposure to sunlight (exposure to UV light; more common in white-skinned—20 times).
- Ethnic factors, socioeconomic status (high society), lifestyle, climate.
- Albinism.
- *Xeroderma pigmentosa* – RR is 1000 (By Kaposi in 1874): It is an autosomal recessive (Ch 9q) disease with defect in DNA excision repair mechanism causing formation of aberrant nucleotide causing ultraviolet rays' intolerance, erythema, pigmentation, photophobia, premature skin ageing, multiple malignancies with 60% mortality at the age of 20.
- Junctional naevus.
- Familial dysplastic naevus syndrome.
- Sporadic dysplastic naevi. 10% risk.
- Large congenital naevi (larger than 20 cm).
- Family history of melanoma (10% through chromosomes 1p, 6q, 7 and 9). They often present with multiple primary melanomas; associated with dysplastic naevus.
- History of earlier skin cancers other than melanoma.
- Patients who are on immunosuppressive drugs or after renal transplantation or NHL (RR - 30).

Malignancies which spread from mother to foetus

- Melanoma
- Lymphosarcoma

Classifications

Breslow's classification (1970): Based on thickness of invasion measured by optical micrometer—most important prognostic indicator until nodal spread

I: Less than 0.75 mm
II: Between 0.76 to 1.5 mm
III: 1.51 mm to 4 mm
IV: more than 4 mm

Relation of Tumour Thickness to Nodal Spread—Based on AJCC Classification

Lesion	*Tumour thickness*	*Nodal spread*
Thin	< 1 mm	< 10%
Intermediate	1-4 mm	20-25%
Thick	> 4 mm	60%

You will soon break the bow if you keep it always stretched.

Clark's levels (Fig. 1.585)

Level 1: Only in epidermis
Level 2: Extension into papillary dermis
Level 3: Filling of papillary dermis completely
Level 4: Extension into reticular dermis
Level 5: Extension into subcutaneous tissue

Differential diagnosis for melanoma (other pigmented lesions of the skin)

- Seborrhoeic keratosis, dermatofibroma
- Pigmented BCC, pigmented SCC
- Naevus, sebaceous epidermal naevus
- Kaposi's sarcoma, mycosis fungoides
- Cutaneous haemangioma
- Certain skin adnexal tumours
- Solar keratosis
- Pyogenic granuloma
- Cutaneous angiosarcoma



Fig. 1.586: Extensive pigmented lesion of the skin.

Types

- Cutaneous melanoma
- Extra cutaneous—10% (ocular is common site)
- Occult (Unknown primary)—2-7%

Clinical Types

1. ***Superficial spreading:***
    - **Most common**. 64-70%. Occurs in any part of the body with variegated irregular look. It has more radial growth and better prognosis. It commonly arises from a pre-existing naevus.
2. ***Nodular melanoma:*** 12-25%.
    - **More aggressive**. It is common in younger age group, occurring in any part of the body. It has more vertical growth. Common in mucosa and mucocutaneous junc-



Fig. 1.587: Superficial spreading melanoma (70%).



Fig. 1.588: Nodular malignant melanoma.



Fig. 1.589: Melanoma in the sole. Often such pigmentation may be unnoticed.



Fig. 1.590: Large melanotic lesion in the heel.



Figs 1.591A and B: Primary melanoma with lymph node secondaries in two different individuals. Note the pigmented ulcerated secondaries in one.



Fig. 1.592: Melanoma in tongue.

tion; uniform; nodular; more vertical growth; nodal spread is common; has got poor prognosis. It usually appears as *de novo*. Common in men; common in trunk, head and neck.

3. ***Lentigo maligna melanoma:***
   - 7-15%. **Less common, least malignant**. Occurs in old age and common in face (**Hutchinson's melanotic freckle**). It is slow growing, variegated, brown macule/lentigo; common in face/neck/hands; common in elderly women. Lentigo maligna is *in situ* type.



Figs 1.593A to C: Melanoma in vagina—in mucocutaneous junction. On table and excised specimen of melanoma.

Creativity begins with thinking different and progress with acting different, thus giving unique results.



Fig. 1.594: 'In-transit' nodules in melanoma. They are secondary depositions in dermal lymphatics.



Fig. 1.595: Satellite nodule in melanoma occurs within 2 cm of primary. Note the primary in the heel and satellite nodule adjacent to it.

4. ***Acral lentiginous melanoma:***
    - 5%. Occurs in palms, soles and subungual region. Common in **Japan**. It has got a **poor prognosis**. It is **least common**. Usually attains large size; nodular type with more vertical growth phase. It is common in Africa and Asia. It is less common in whites. It is often flat, irregular macule. It mimics fungal infection/pyogenic granuloma.
5. ***Amelanotic melanoma:***
    - This is the **worst type.** Because of the undifferentiation, tumour cells loose their capacity to synthesise melanin. It presents as rapidly progressive pinkish fleshy tumour. It may mimic soft tissue sarcoma. It needs markers like S100, HMB45 for diagnosis.
6. ***Desmoplastic melanoma*** has high affinity for perineural invasion; is common in head and neck with higher recurrence rate. It is *amelanotic melanoma with thicker lesion* carrying poor prognosis due to neural invasion.

Note:

Subungual melanoma which was earlier thought of acral lentiginous type is now considered as superficial spreading type. It is involvement of *nail fold matrix* (not nail plate). Triangular, macular, progressively widening pigmentation of nail fold with nail dystrophy is typical—*Hutchinson's sign*. It should be differentiated from benign racial melanonychia which are dark streaks under the nail. Biopsy of *nail matrix* should be done here.

Ocular melanoma: It is the commonest malignancy arising in eye. It may arise from retina, iris, ciliary body, choroid. It rarely metastasize or only at late stage as it is devoid of lymphatics. Ocular melanoma commonly shows its distant spread to liver. Massive hepatomegaly is typical and is often seen many years after the treatment of primary ocular lesion. Condition is treated with enucleation, radiation, photocoagulation.

Clark's concept—Two phases of growth: Initial radial growth phase occurs horizontally, later vertical growth phase occurs with invasion.

Melanoma

- 5% of all skin cancers—incidence
- 20 times more common in whites than blacks
- Mucosal melanoma has got poor prognosis
- Can spread from mother to foetus
- Multiple melanomas are 1% common
- Melanoma in choroid will not cause lymph node involvement, as it has no lymphatic drainage. But late massive liver secondaries even after 10-20 years is known to occur
- 10% of melanomas are familial—in whites
- Satellite nodules are secondary skin nodules within 2 cm of primary
- In transit' nodules are secondary skin nodules beyond 2 cm of primary any where up to lymph node region
- Melanoma may present as secondary (in liver, lungs, bone, brain) with occult primary when primary is situated in anus, genitalia, eye, external auditory canal, adrenal gland, nail bed and scalp—7%
- Pigmentation is not *mandatory* to diagnose melanoma even though it is commonly present.

Clinical Features

- It can stat in a pre-existing **naevus** (commonly junctional naevus)—50-60% or as **de novo** in a normal skin—40-50%.
- Melanoma is **unknown before puberty.**
- ***No induration is seen in melanoma***.
- Pigmentation with irregular surface and margin with rapid growth.
- **Ulceration, bleeding, itching, change in the colour.**

Note:

When a mole turns malignant, following changes should be observed (*Glasgow* criteria:

- ***Major signs*:** Change in *size* (diameter more than 6 mm), *shape* and *colour*
- ***Other changes***:
    - Inflammation, crusting, bleeding, itching
    - Nodularity, ulceration, halo around a mole
    - Satellite lesions
    - Doppler positive pigmented lesions using hand held Doppler (> 1 mm thick lesion)

Five most important features of melanoma

- **A**symmetry
- **B**order irregularity
- **C**olour variation
- **D**iameter > 6 mm
- **E**levation

Spread

- **Through lymphatics** it spreads to regional lymph nodes either by permeation or by embolisation.
- **In-transit nodules or satellite nodules** are seen in the skin between the primary lesion and regional lymph node area, and is due to retrograde spread to dermal lymphatics.
- **Through blood**: To lungs, liver (huge liver), brain, skin, bones. Secondaries are typically black.

Blood spread in melanoma

- *Brain*—convulsions, localising features and raised intracranial pressure
- Lung—cannon ball secondaries, pleural effusion-haemoptysis, chest pain and cough
- Liver (massive liver), ascites
- Skin—cutaneous nodules often pigmented
- Bones—bone pain, pathological fracture. Paraplegia/neurological deficits in spine metastasis

Extensive visceral involvement causes ***melanuria***

- Melanoma **in choroid** has got better prognosis, because as there are no lymphatics, spread is delayed.
- Sometimes primary is very small and unnoticed (in anus, subungual region). They present with features of secondaries only.

***Note*:**

Infiltration into deep fascia by melanoma is rare in initial stages as deep fascia acts as a strong barrier.

Staging of Malignant Melanoma (It is older staging system)

IA: Thickness less than 0.75 mm.
IB: Thickness between 0.76 to 1.5 mm.
IIA: Thickness between 1.51 to 4.0 mm.
IIB: Thickness more than 4.0 mm.
IIIA: Any of the above + nodes less than 3 cm.
IIIB: Any of the above + nodes more than 3 cm.
IV: Any of the above + any node + M1 (distant spread).

Occult melanomas (primary unknown) are common in

— Anus
— Scalp
— External auditory canal
— Nail bed
— Genitalia
— Eye
— Adrenal medulla

Tumour markers for melanoma

- MELAN-A
- S 100
- HMB 45 (Hydroxy Methyl Bromide)
- LDH

Investigations

- **No incision biopsy.** It can cause early blood spread.
- Excision biopsy of primary. It is done with 2 mm margin with deeper fatty tissue. One should avoid using cautery

Newer TNM staging (2002) for melanoma

Tumour	***Node***
T 0 No tumour	N 0 No nodes
T is *In situ* tumour	N 1 a—one node micrometastasis
T 1a < 1 mm level II, level III no ulceration	N 1 b—one node macrometastasis
T 1 b < 1 mm, level IV with ulceration	N 2 a—2 or 3 nodes micrometastasis
T 2 a 1-2 mm no ulceration	N 2 b—2 or 3 nodes macrometastasis
T 2 b 1-2 mm with ulceration	N 2 c—no nodes but satellite or in transit lesions
T 3 a 2-4 mm no ulceration	N 3-4 or more nodes; nodes with satellite or in transits
T 3 b 2-4 mm with ulceration	Stage 0 – TisN0M0
T 4 a > 4 mm no ulceration	Stage IA – T1aN0M0; IB – T1b/T2aN0M0
T 4 b > 4 mm with ulceration	Stage IIA – T2b/T3aN0M0; IIB – T3b/T4aN0M0; IIC – T4bN0M0
M—Metastasis	Stage IIIA – T1-4aN1a/N2aM0; IIIB – T1-4bN1a/N2aM0, T1-4aN1bN2bM0, T1-4a/bN2cM0; IIIC – T1-4bN1b/N2bM0, any TN3M0
M 0—no blood spread	Stage IV – Any T, Any N, M0
M 1 a—Skin, subcutaneous tissue, distant node	
M 1 b—Lung spread	
M 1 c—Other viscera or distant spread and increase in LDH	

There is no service than doing something for someone who will never find it out!

and avoid crushing the tissues as much as possible. Instead of excision biopsy, punch biopsy is done in case of large primary tumour very close to pinna, eye, nose. Punch biopsy assesses the depth/thickness of the lesion. Punch should be done at the most elevated part of the lesion to get proper depth.

- FNAC of lymph node.
- U/S abdomen to look for liver secondaries (usually huge hepatomegaly occurs).
- Chest X-ray to look for secondaries in lung ("cannon ball" appearance). HRCT of chest is ideal.
- Relevant other methods depending on site and spread, e.g. CT scan of head, chest, abdomen, pelvis.
- Urine for melanuria signifies advanced disease.
- Sentinel lymph node biopsy (**SLNB).**

Treatment

Surgery is the main treatment.

For Primary:

a. Handley's ***wide local excision (WLE)*** is wide excision with clearance of margin as well as depth. Clearance margin used in olden days is 3-5 cm.

Present recommendation is— *in situ* melanoma needs 0.5 cm clearance; melanoma < 1 mm thickness needs 1.0 cm clearance; 1-2 mm thickness needs 1-2 (1.5) cm clearance; 2 cm/3 cm clearance is sufficient for > 2.0 mm thickness. Procedure can be done under regional or local anaesthesia. Evidence says that more than 2 cm clearance will not show any additional advantage in treating primary tumour.

Primary closure or SSG or local flaps are used to cover the defect.

b. If primary area is wide, then amputation with one joint above is done.

c. In fingers and toes, disarticulation is required.



Fig. 1.596: Wide excision of melanoma from the heel. Note the clearance margin and depth of dissection.



Fig. 1.597: Wide excision and skin grafting done for melanoma.



Figs 1.598A and B: Widely excised melanoma specimen from heel. Cut section of widely excised specimen of melanoma from heel shows the depth of the tumour.



Figs 1.599A and B: Secondaries in inguinal lymph nodes from primary melanoma sole-on table finding. Specimen of ilioinguinal block is also shown. Pigmented nodes are observed.



Fig. 1.600: Disarticulation of lateral two toes for interdigital melanoma.



Figs 1.601A and B: Melanoma secondaries in groin nodes after block dissection. Black lesions are observed in cut section.

d. Melanoma in anal canal may require abdominoperineal resection.
e. Enucleation in case of melanoma in eye.
f. *Melanoma in pregnancy* is treated with termination of pregnancy and specific therapy for melanoma. Pregnancy should be postponed for 2 years.

For lymph node secondaries:

1. In a clinically palpable lymph node, FNAC of lymph node is done. In case of spread, then regional block dissection, i.e. ilioinguinal or axillary or neck is done. Once FNAC shows positive lymph node 5-year survival rate reduces to 50%.
2. In a fixed lymph node, only chemotherapy is the treatment because it is inoperable.
3. *Lymphatic mapping and sentinel node biopsy* (Dr Donald Morton, 1970): Radioactive colloid is injected around primary site and lymphoscintigraphy is done using hand held gamma camera to visualise the micrometastasis in the nodal field. If there are micrometastasis, then regional block dissection (therapeutic LND) is done.

   SLN (Sentinel lymph node) can be identified in 95% or more of groin and axillary nodes and in 85% cases of head and neck melanomas. Often both blue dye and technetium sulfur colloid is used together to identify the SLN. SLNB is useful for melanoma with thickness more than 1 mm depth. Less than 1 mm thickness is considered as *low-risk* for metastases; between 1-4 mm thickness is considered as *intermediate-risk* for metastases mainly of nodal spread; more than 4 mm thickness will be considered as *high-risk* for both nodal as well as blood spread. SLNB is the investigation of choice for staging in intermediate thickness melanoma.
4. Prophylactic regional block dissection which was previously advocated is now controversial. But still used in many centres. Elective lymph node dissection (ELND) is done when tumour thickness is 1-4 mm.
5. *Management in unknown primary* (2%) presenting as nodal secondaries is by nodal radical dissection at the region with adjuvant chemotherapy. They have better prognosis

than with known primary. Patient should be monitored and evaluated to identify the primary site during every follow up. Once primary is identified it is treated accordingly depending on its location.

For Loco Regional Recurrent Melanoma:

- *Local recurrence* is one which recurs within 5 cm radius of the primary tumour in skin or subcutaneous tissues. Risk of local recurrence is 0.2% if primary tumour is less than 0.75 mm; 2% if it is between 0.75-1.5 mm; 6% if it is 1.5-4 mm; 12% if it is more than 4 mm.
  - *Isolated limb perfusion* (Creech et al, New Orleans, 1958) using cytotoxic agents like Melphalan (M for M), interleukin 2, tumour necrosis factor (TNF). Concentration used here is 15-25 times more than that is used for systemic therapy. Melphalan dose is 10 mg / l perfusion solution in leg (13 mg/L in arm).

    Melphalan is injected at high temperature of 41°C with a pump and oxygenator through cannulas in femoral artery and vein with a proximal tourniquet *in situ.* Hyperthermia and oxygenation increase the metabolic activity of tumour cells to make it more vulnerable to melphalan. Procedure controls the local disease well with preserving the functioning limb. *Complications* like DVT, bleeding, sepsis can occur. It is used in local recurrence or 'In-transit' deposits.

    It shows 80% response rate with 15% complete response; but only of short period.
  - Laser ablation of multiple small cutaneous lesions.
  - *Isolated limb infusion* (Thompson, 1993): Vascular catheters are passed and placed across femoral artery and vein through opposite femoral vessels or through arm vessels. The limb is warmed; patient is anaesthetized 2 hours later and also heparinized; papaverine is injected into arterial catheter and tourniquet is applied in the thigh/arm. Melphalan 7.5 mg/L, actinomycin D 75 µg/L in 400 ml saline (10 mg and 100 µg/L in 300 ml NS in upper limb) is infused into the isolated limb for 6 minutes which is pumped around the limb repeatedly for 30 minutes with a hypoxia in limb; drugs are washed out using a Hartmann's solution; tourniquet is removed and normal circulation is regained with removal of vascular catheters. Protamine is given to reverse heparin action.

For Distant Spread:

- Brain, *lung and liver* are the *most common* sites; skin, bone, GI are less common sites. But melanoma is one of the commonest tumours to spread to *intramural GIT* to present as intussusception.
- Distant spread when found or suspected, CT scan of head, chest, abdomen and pelvis are needed. PET scan and tumour markers are very useful.
  - Chemotherapy and immunotherapy is the main treatment.
  - Isolated lung or liver metastasis can be resected.
  - Radiotherapy is useful for bone and brain secondaries. Stereotactic program using gamma knife is better for brain secondaries.

Chemotherapy for Melanoma

Indications:

a. Secondaries in lungs, liver, bones.
b. After surgery for melanoma. Usually it is given intravenously.

Drugs are:

a. DTIC: Diethyl Triamine Imino Carboxamide.
b. *Melphalan* (Phenyl alanine mustard) (Melphalan for melanoma).
c. Carboplatin, vindesine.
d. *CVD regime*—is cisplatin, vinblastine and dacarbazine.

Immunotherapy/Biological Therapy

- It is done using specific tumour antibodies, BCG, levamisole, *Corynebacterium parvum*, alpha interferon, interleukins and tumour vaccines is tried with some success rate up to 40% in advanced melanomas.
- *Biochemotherapy* is combination of CVD with interferon α and interleukin 2.
- Interferon α is a cytokine which is antiangiogenic and stimulator of natural killer NK cells. Dose is 20 mU/m^2 IV 3 times a week for 4 weeks then maintenance dose of 10 mU/m^2 subcutaneously 3 times a week for one year. Severe myelodepression and fulminant liver necrosis are the toxicity and so often dose is reduced to 3 mU/m^2 three times weekly for 2 years.
- GM2 ganglioside based vaccine (stimulates production of IgM antibodies), Melacine (contains melanoma cell lysates) and cancerVax are three vaccines under trial at present.

Endolymphatic Therapy

- It can be done to control disease in the nodes using radioactive I_{131} or P_{32} with ultrafluid lipiodol along with lymphangiography.

***Note*:**

- There is not much role for radiotherapy.
- Radiotherapy is beneficial only in secondaries in brain and bones.

Prognosis for Melanoma

- It is not good since it is a very aggressive tumour.
- Old age has worse prognosis.
- Females show better prognosis.
- Extremity melanoma has better prognosis than head and neck.



Figs 1.602A and B: Melanoma involving face extensively with destruction. Note the maggots over the surface of tumour. Melanoma is *most aggressive* cutaneous malignancy.

Prognostic factors—overall poor	***Staging as prognostic factor***
• **Tumour thickness**—very important factor	Stage I: > 90% prognosis Stage II: 70%
• Nodal spread—once regional nodes are positive, 85% of patients will have occult distant spread. Number of positive nodes is also important.	Stage III: 35% Stage IV: < 2%
• Ulceration—poor	
• Angiogenesis, vascular invasion—poor	
• In-transit nodules—poor	
• Vertical growth—poor prognosis	
• Metastatic disease—poor	
• Staging	
• Mitotic activity	

Follow-up After Therapy in Melanoma

- In stage I and II disease after treatment, follow up is done at 6 months interval for 3 years. It is done by clinical examination, LDH assay, USG abdomen and chest X-ray.
- In stage III disease, PET scan CT of head, chest and abdomen are indicated.

Sentinel node biopsy

a. Carcinoma breast
b. Melanoma
c. Carcinoma penis

Note: Melanoma also can occur in fishes, dogs and horses.

S. Sarcomas

CHAPTER OUTLINE

- Sarcoma
- Liposarcoma
- Fibrosarcoma
- Malignant Fibrous Histiocytoma
- Leiomyosarcoma
- Rhabdomyosarcoma
- Chondrosarcoma
- Haemangiosarcoma
- Lymphangiosarcoma
- Synovial Sarcoma
- Malignant Peripheral Nerve Sheath Tumour
- Kaposi's Sarcoma

SARCOMA

Sarcomas can arise from bone or soft tissue. *Osteosarcoma* is the commonest of all sarcomas. *Soft tissue sarcoma* (STS) which is arising from mesenchyma is the one which will be discussed in this chapter. STS are aggressive tumours which needs multimodality therapeutic approach.

Sarcoma occurs in younger age group compared to carcinoma with fish fleshy gross look with haemorrhage and necrosis. It shows rapid growth, with tendency to show early blood spread. Lymphatic spread is rare even though few sarcomas can spread through lymphatics along with blood spread. Blood spread commonly occurs to lung but liver, skin, brain can also get involved.

Soft tissue is tissue that connect, surround and support the skeletal system which is non-epithelial, extra skeletal tissue excluding reticuloendothelial system, glial tissue but it also includes peripheral nervous tissue by convention. Embryologically it is mainly from mesoderm but few from neuroectoderm.

STS are named based on their tissue which it resembles. Liposarcoma—fat; fibrosaroma—fibroblast; malignant fibrous histiocytoma—mesenchyma/histiocytes; leiomyosarcoma—smooth muscle; rhabdomyosarcoma—skeletal muscle; chondrosarcoma—chondroblast; angiosarcoma—blood vessels.

Features

- Sarcomas are much lesser in incidence compared to carcinomas.
- It occurs in younger age group compared to carcinomas.
- They can arise from bone (osteosarcoma) or from any soft tissues (soft tissue sarcomas) (Mesenchymal tissue).
- They are much more aggressive compared to carcinomas.
- They are rapidly growing tumours with fleshy appearance.
- They are not encapsulated but often are having pseudocapsule.
- They spread through blood especially to lungs often also to other organs.
- Lymphatic spread is not common with certain exceptions.
- Main method of treatment is surgery, i.e. wide excision, amputation.
- In inoperable cases debulking is the accepted method of treatment.
- Chemotherapy is the adjuvant therapy.

Important features of sarcoma

- More aggressive
- Rapidly spreading
- Not very much radiosensitive
- Blood spread
- Painless soft tissue mass is the presentation
- Very vascular

Soft tissue sarcoma

- 1% of adult malignancy
- 15% of paediatric malignancies
- Incidence:
  - 35% occurs in lower limb (commonest site)
  - 15% upper limb, 15% retroperitoneum
  - 10% trunk, 15% viscera, 10% other areas
- **Soft tissue sarcoma (STS)** arises from pluripotent mesenchymal stem cell without in situ changes. Transformation from benign lesion to sarcoma is not observed/disproved now except MPNST (Malignant peripheral nerve sheath tumour)
- Ratio of soft tissue sarcoma to bone sarcoma is 3:1
- Soft tissue sarcoma is more common in males (4:1)
- Ratio of benign soft tissue tumour to malignant soft tissue tumour is 100:1. Most of the sarcomas arise as *de novo*. Per se benign will not turn into malignancy, as it is now found that cell of origin to begin with multiples with anisocytosis in soft tissue sarcoma. In olden days it was accepted to consider benign (precursor tumour) turning into malignancy like lipoma turning into liposarcoma which is disproved now. But this argument does not hold good for nerve sheath tumour and probably lymphoedema turning into lymphangiosarcoma (post mastectomy)
- 50% of STS occurs in extremities called as extremity STS; 35% lower and 15% upper limb
- 3% of sarcoma spreads to lymph nodes
- Soft tissue tumour > 5 cm should be biopsied in suspicious of sarcoma

- Commonest sarcoma of bone is *osteosarcoma* (Note: commonest malignancy of bone is secondaries).
- Commonest soft tissue sarcoma is *liposarcoma / malignant fibrous histiocytoma* (MFH – 25%) overall; in the extremities both *MFH and liposarcoma*; in the retroperitoneum it is *liposarcoma*.
- Commonest visceral (GIT) sarcoma is leiomyosarcoma.
- In genitourinary system leiomyosarcoma is commonest in adults and rhabdomyosarcoma in *paediatric age group*; in uterus leiomyosarcoma; in myocardium angiosarcoma; in hand and foot synovial sarcoma; in skin Kaposi's sarcoma; in head and neck region angiosarcoma.

Note:

- Many liposarcomas arise at sites devoid of adipose tissue. Most rhabdomyosarcomas arise in locations that lack voluntary muscle.
- 40% of soft tissue sarcomas are more than 10 cm in size at the time of presentation; 30% are 5-10 cm and 30% are less than 5 cm.

Incidence of STS

In adults

- MFH and liposarcoma—35-45%.
- Rhabdomyosarcoma—10%.
- Leiomyosarcoma—9-15%.
- Synovial sarcoma—7%.



Fig. 1.603: Soft tissue sarcoma foot. Note the vascularity.



Fig. 1.604: Osteosarcoma of the upper end of humerus in an adolescent boy.



Fig. 1.605: Osteosarcoma upper tibia. Note the size of the tumour and ulceration. It is very vascular.



Figs 1.606A and B: X-ray pictures of osteosarcoma in tibia and femur.

- Malignant peripheral nerve sheath tumour (MPNST)—6%.
- Fibrosarcoma—5%.

In children

- Rhabdomyosarcoma, neuroblastoma are common tumors.

Aetiology

- *Genetic*
  - von Recklinghausen disease
  - Gardner's syndrome
  - Tuberous sclerosis
  - Basal cell naevus syndrome
  - Li-Fraumeni syndrome
- *Chemicals*—PVC, tetrachlorodibenzodioxin, arsenic
- *Viral*—HIV in Kaposi's sarcoma, cytomegalovirus
- *Ionising radiation*—malignant fibrous histiocytoma (p53)
- Lymphangiosarcoma in post-mastectomy lymphoedema—*Stewart—Treves syndrome.*
- Osteogenic sarcoma in Paget's disease of bone/exposure to radium
- Retinoblastoma associated sarcoma
- Gorlin's syndrome
- Thorotrast, vinyl chloride, arsenic, pesticides

Clinical Features of Soft Tissue Sarcoma

- Painless swelling of short duration with progressive increase in size—*soft tissue mass*. 30% of patients may present as *pain* during first evaluation.
- Compression of adjacent structures
- Smooth, firm/hard, warm and vascular
- Features of secondaries in lung—cough, haemoptysis and chest pain. *Lung* is the commonest site of secondary.
- Secondaries in *liver* as a principal site especially in visceral STS.
- There are no reliable findings to distinguish benign from malignant swellings.
- One has to maintain a high index of suspicion in any soft tissue mass deep to deep fascia, any soft tissue mass > 5 cm, any new enlarging or symptomatic soft tissue mass.

Investigations

Preoperative evaluation of STS is done:

- To determine the "exact extent" of the tumour.
- To obtain a tissue diagnosis.
- To evaluate metastatic disease.

Tissue Diagnosis

- ***Incision biopsy*** is the *most reliable method* of diagnosis. It provides adequate tissue sample.
- *Trucut biopsy*/core needle biopsy is an *acceptable first diagnostic* step as it is technically easier, not costly, with fewer complications. But it is not useful in visceral STS. Again if it is inadequate one should not be hesitant to go for incision biopsy at the earliest. It is done using 14 gauge needle; often US / CT guide is used.
- Excision biopsy is done *only* if the tumor size is < 3 cm which is cutaneous or subcutaneous wherein wide local re-excision is possible. Otherwise excision biopsy *should be avoided* as it may contaminate the tumour bed and restricts the therapeutic options.



Figs 1.607A and B: Soft tissue sarcoma upper chest wall. Note the vascularity and extent.

***Note*:**

FNAC is of *less value* in STS. It is significant only if it positive. It is useful in local or distant recurrences in documented sarcoma patients, or to evaluate nodal status if enlarged. CT guided FNAC is useful for retroperitoneal/intra-abdominal sarcomas.

Assessment of the Extent of Tumour

Imaging in STS provides a 3–dimensional extent of the tumour and helps in accurate planning of surgical procedure. But it does **not** reliably distinguish between a benign and malignant process. It assesses macroscopic and **not** microscopic extent of the disease. Imaging is essential for metastatic work up.

- *MRI is the investigation of choice* as it determines the vascularity, relation to vessel and fascial planes (extent and invasion). *Advantages of MRI* are—imaging of choice in STS, excellent soft tissue delineation, without radiation, multiplanar imaging possible. Images of skip metastases are possible. *Disadvantages of MRI* are—cost, bone involvement is poorly delineated, claustrophobia, not possible in presence of metal implants and pacemakers.

- CT scan also can be used to see the extent and invasion but not equivalent to MRI. CT scan helps in identifying presence and extent of the soft tissue mass, status of the adjacent structures, with mandatory contrast enhancement isodense masses, vasculature are better delineated. SPECT—3 dimensional reconstruction feasible. *Advantages of CT* are—easy availability, relatively cost effective, best to demonstrate bony involvement, useful for guided biopsies. *Disadvantages of CT* are—cross-sectional imaging, ionizing radiation, inferior soft tissue detail.
- *US is less sensitive* investigation. It is useful in extremity lesions to assess vascular system. It is initial/first investigation done in GI leiomyosarcoma/retroperitoneal sarcoma. It is useful for serial studies, guided trucut biopsy.
- X ray of part is not necessary; it is only used in initial phases to differentiate STS from bony lesion.
- *Angiogram* is traditionally used to delineate adjacent vasculature. It is upstaged by CECT/MRA. It is not necessary to do regularly in all cases but when there is a need for accurate assessment of vasculature it is ideal. It is used in intra-arterial chemotherapy for unresectable tumours.
- CT abdomen is *better* in GI/retroperitoneal sarcomas.

Evaluation of Metastatic Disease

- Chest X-ray is done to look for secondaries.
- CT chest is ideal to see early lung secondaries. It is done in all deep seated, high grade and tumour more than 5 cm in size.
- US abdomen is sufficient to check liver secondaries. But CT abdomen may be better choice. Often CT pelvis is also added.

Other Investigations

- Radionuclide scintigraphy (Gallium-67).
- -p-MRS (p-Magnetic Resonance Spectroscopy) and FDG (Fluor-2-Deoxy Glucose) PET are done to assess the metabolic activity of tumour.



Fig. 1.608: MRI of STS leg.

- Immunohistochemistry and *FISH* (fluorescence *in situ* hybridization).
- Tumour markers.
- Haematocrit, peripheral smear, ESR, serum alkaline phosphatase, serum creatinine.

Incision biopsy for soft tissue sarcoma

- It is the ***ideal tool*** to conclude sarcoma histologically
- Incision should be placed in such a way that it can be included in wide tumor excision at a later period—as biopsy track is always contaminated
- One should achieve absolute / adequate haemostasis to avoid haematomas as tumours are vascular
- Proper site of incision biopsy should be decided
- One should use shortest possible route to tumour while taking incision biopsy; should not violate more than one compartment; should avoid neurovascular bundle. (Injury to vessels and nerves should be avoided)
- Smallest longitudinal incision is used to provide adequate specimen (Incision should be longitudinal in limbs)
- Transverse incision is *contraindicated* in the limbs except over the flexures
- Minimal tissue disturbance and avoiding raising of flaps are crucial (Flaps should not be undermined)
- It is better to use cold knife
- One should avoid crushing/distorting the specimen
- Frozen section/Imprint specimen can be used to avoid sampling error.
- Drains are *not used* routinely in incision biopsy. If used exit *near*/close to the wound and not away/distant from the incision biopsy wound.
- Excise the biopsy tract and drain site *enbloc* during the definitive procedure.
- Immunohistochemistry and cytogenetics are possible



Fig. 1.609: Incision for biopsy in STS should be longitudinal so that it can be included in future surgical wide excision. Never place transverse incision for biopsy.



Fig. 1.610: MRI picture of the soft tissue tumour thigh encasing vessels partially and eroding the bone. Patient needed high level, above knee amputation.



Fig. 1.611: CT picture of retroperitoneal leiomyosarcoma.

Staging

Staging of the soft tissue tumour is done depending on the tumour size, nodal status, metastasis and histological grading of the tumour **(GTNM staging).**

TNM staging of soft tissue sarcoma

Grade (G)	*Tumour (T)*
Gx Cannot be assessed	Tx Cannot be assessed
G1 Well-differentiated	T0 No primary
G2 Moderately differentiated	T1 Size < 5 cm or 5 cm (maximum dimension)
G3 Poorly differentiated	T1a: Superficial
	T1b: Deep tumour
G4 Undifferentiated	T2 Size > 5 cm
	T2a: Superficial
	T2b: Deep tumour
Regional lymph nodes (N)	*Distant spread (M)*
Nx Nodes cannot be assessed	Mx Cannot be assessed
N0 No nodes	M0 No distant spread
N1 Nodes present	M1 Distant spread present

Note: Superficial tumour is outside the superficial fascia. Deep tumour is deep to superficial fascia or any tumour invading the superficial fascia.

Stage I – G1, 2; T1a, 1b, 2a, 2b; N0; M0.
Stage II – G3, 4; T1a, 1b, 2a; N0; M0.
Stage III – G3, 4; T2b; N0; M0.
Stage IV – Any G; any T; N1; M0. OR Any G; Any T; N0; M1.

Grading of sarcomas

Low	Desmoid, dermatofibrosarcoma, liposarcoma. Here < 15% chances of metastases
High	Synovial, Rhabdomyosarcoma, Angiosarcoma Malignant fibrous histiocytoma, Extraosseous chondrosarcoma. Here > 50% chances of metastases
Undetermined	fibrosarcoma, Leiomyosarcoma

Note:

- STS is an aggressive, invasive, destructive growth with high recurrence and distant metastases rate. Tumour shows *fish flesh* cut appearance.
- *Basis used for classification of STS*—STS being highly heterogeneous group of tumour is classified based on adult tissue it resembles; i.e the *type of tissue formed* rather than from the type of origin.
- ***Grade*** is the single most important factor in staging. It denotes the "biological aggressiveness" of the sarcoma. It predicts the likelihood of metastases.
- Nodal metastases are rare in STS (3%). It has the same prognosis as M1 disease hence staged as Stage IV.
- M1 is – Distant metastases.

Differential diagnosis for soft tissue sarcoma

- Haematoma
- Abscess
- Aneurysm
- Myositis

Treatment

Principles of Treatment

- ***Surgery*** is the *main treatment* modality. Amputation rate for STS has come down drastically from 50% in 1960 to 5% at present. It is also because of proper ***adjuvant radiotherapy*** following function/limb sparing complete excision, application of microvascular surgeries. Neoadjuvant chemotherapy, perioperative/postoperative RT also play a major role.
- In *low grade tumour* without any spread—functional/limb sparing complete wide excision is sufficient without any adjuvant therapy. If microscopic margin is positive for tumour then postoperative External Beam RT (EBRT) is given.
- In *high grade tumour < 5 cm* size, function sparing wide excision with more than 1 cm clearance margin is sufficient. If clearance margin is less than 1 cm or shows microscopic

positive margin, then perioperative brachytherapy OR postoperative EBRT is given.

- In *high grade tumour which is between 5-10 cm* size, function/limb sparing complete wide excision with perioperative brachytherapy OR postoperative EBRT is given.
- In *high grade tumour more than 10 cm* in size, initially neoadjuvant chemotherapy; then functional/limb sparing complete wide excision with postoperative brachytherapy and EBRT should be given.
- All limbs should be *conserved* if possible but with curative intent.

Surgery

Enneking classification of surgical procedures

- *Intralesional excision*—done inside pseudocapsule very high recurrence 100%—not used.
- *Marginal excision*—en bloc resections through the reactive zone-high recurrence rate 70%
- *Wide excision* means en bloc resection done through normal tissues beyond the reactive zone; it means if the margin is less than 5 cm; tumour is never visualised during surgery; it has local recurrence rate of 30%. Wide margin is classified as adequate if margin is at least beyond 1cm outside the reactive zone or inadequate if margin is within 1 cm.
- *Radical excision*—if the margin is more than 5 cm outside the reactive zone. It is like compartment excision with very low recurrence rate.

Other procedures

- Compartmental excision; function/limb sparing.
- Vascular resections with vascular reconstruction.
- Amputation.



1. Tumour mass.
2. Reactive zone.
3. Intralesional excision.
4. Marginal excision.
5. Wide excision–clearance up to 5 cm.
6. Radical excision–clearance > 5 cm.
7. Compartment excision.

Fig. 1.612: Different surgical approaches for STS.

A thin barrier is considered to be a 2 cm thickness of normal tissue; a thick barrier is 3 cm thickness; and joint cartilage is said to be equivalent to a 5 cm thickness margin. A surgical margin that is outside a barrier, with normal tissue between the barrier and the reactive zone of the tumour, is considered to be curative.



Figs 1.613A to C



Figs 1.613D and E

Figs 1.613A to E: Surgical approach to a deep seated sarcoma in leg—deep to gastrocnemius and soleus.

- **Wide local excision** with clearance of 2 cm (minimum need is 1 cm) or more with preservation of function is needed. Depth clearance is also important. 3-5 cm clearance even though was practiced in olden days, is not necessary.
- **Compartment resection** is a radical limb saving procedure. Here muscle group of one compartment (anterior, posterior or medial) is resected entirely from its origin to insertion with the tumour. It is done only when tumour is intracompartmental. It is not suitable when tumour is extracompartmental or many compartments are involved or encased to major neurovascular bundle.
  Basis for compartmental excision is—STS rarely penetrate anatomical barriers unless it is very advanced.
- Amputation is done in large tumours of upper or lower limbs.

Indications for amputations in soft tissue sarcoma

- Major neurovascular encasement
- Bone involvement
- Multiple compartment involvement
- Limb itself is diseased like lymphoedema
- Recurrence with multicentricity

  - *Radical amputation* is done as disease has not spread systemically which should be confirmed by CT chest, abdomen and pelvis. In metastatic disease there is no need to do amputation as long term survival is not possible except if primary is fungating and distressing.



Figs 1.614A and B: Recurrent chest wall tumour, could be secondaries, as patient was earlier amputated for soft tissue tumour hand (forearm amputation). X-ray of the same patient shows large tumour mass.

Tumor site	***Level of amputation***
Foot	Below knee
Leg	Above knee
Thigh-middle and lower third	Hip disarticulation
Thigh proximal third	Hemipelvectomy
Buttock	Hemipelvectomy
Hand and wrist	Below elbow
Forearm	Above elbow
Distal arm and elbow	Shoulder disarticulation
Axilla and shoulder girdle	Forequarter amputation

- Debulking surgery is useful in large advanced tumours like retroperitoneal sarcomas.

Radiotherapy

- ***Preoperative radiotherapy*** followed by wide excision—neoadjuvant RT.
- ***Postoperative radiotherapy*** is commonly used because of less tumour burden and less wound problems. Titanium clips are placed during surgery at high risk areas to identify the site to concentrate proper RT.
  - *Brachytherapy* is very effective in local control of the tumour. Initially precise mapping of the area is done in the

operation theatre. Loading catheters are placed in surgical field peroperatively. Later these catheters are loaded with iridium 192. Dose is 45 Gy to tunbour bed for 6 days.

- Permanent radioactive sources can also be placed to the area.
- *Postoperative external beam radiotherapy* (EBRT)—it is quiet effective and used in high grade tumour more than 5 cm often with brachytherapy. Dose is 70 Gy-25 fractions.

- Palliative external radiotherapy can be given to prevent bleeding, fungation and to reduce pain in advanced cases. It is also used in secondaries in brain, bone.
- *Primary radiotherapy* alone (radical) is of less beneficial in soft tissue sarcoma, but now it is used with more favorable results.

Radiotherapy in soft tissue sarcoma

- Brachytherapy is given in high grade tumour
- External beam radiotherapy is used in low grade tumour
- All tumours more than 5 cm need adjuvant radiotherapy (external beam)
- Preoperative radiotherapy is also beneficial
- Deep seated tumour; high grade; size more than 5 cm needs chemoradiation

Chemotherapy

- Chemotherapy drugs—*VAC (Vincristine, Adriamycin, Cyclophosphamide*) are commonly used. Other drugs *ifosfamide*, *dacarbazine* are used in combination with above drugs. *Mesna* is used as a protection for haemorrhagic cystitis. Chemotherapy is used when tumour is more than 5 cm or high grade. Usually *postoperative chemotherapy* is given. MAID regime is used especially in recurrent STS. Mesna, Adriamycin, Ifosfamide, Dacarbazine drugs are used. Its response rate is 50%. But survival benefit is controversial.
- *Neoadjuvant chemotherapy* is used to make the primary tumour better operable. It makes eventual surgery better; provides early treatment for micrometastasis; gives idea about the response for chemotherapy. Drugs used are adriamycin and ifosfamide.
- *Isolated limb perfusion using cytotoxic drugs and tumour necrosis factor* with hyperthermia is also often used.
- Chemoradiation is a good alternate adjuvant therapy used.

Distant Spread

- *Pulmonary metastasis* can be treated with wedge resection, segmentectomy, lobectomy, pneumonectomy. Surgery is done only when primary is well-controlled. Radiotherapy and chemotherapy are also tried. More than three number metastases in lung signify poor prognosis.

Prognostic factors in STS

- Size > 5 cm—important factor
- High grade
- More than one compartment involvement
- Deep tumours and multicentric
- Neurovascular invasion
- Lung secondaries
- Clearance margin


Recurrent STS; note the old scar
A
Recurrent STS forearm; note the old scar
B

Figs 1.615A and B: Recurrent soft tissue sarcoma over scapular region and forearm in two different patients. Old surgical scar is seen.

LIPOSARCOMA

- It is the ***commonest type*** of soft tissue sarcoma arising from the fat cells (of primitive mesenchymal cells).
- Lipoma as a precursor tumour for liposarcoma which was thought earlier is *disproved*/not accepted now.
- It is 20% of all soft tissue sarcomas.

Common Sites

1. Thigh—commonest site.
2. Retroperitoneum.
3. Back.
4. Shoulder.

Small minds are first to condemn great ideas.

Types

1. *Well-differentiated*—common between 50-70 years age group; common in extremities (75%); metastasis is rare.
2. *Dedifferentiated*—common between 50-70 years age group; common in retroperitoneum (75%); metastasis is high.
3. *Myxoid*—common at 25- 45 years age; common in extremities (75%); high rate of metastasis.
4. *Round cell type*—common at 25- 45 years age; common in extremities (75%); high rate of metastasis.
5. *Pleomorphic* (5%)—poor prognosis.

Microscopically, it contains lipoblasts with 'signet ring' malignant cells. It is low grade type.

Spread is to lungs.

Treatment is wide excision or radiotherapy with surgical debulking in places where complete removal of tumour is not possible like in retroperitoneal liposarcoma.

FIBROSARCOMA

- It can arise from ***the bone*** or from ***soft tissues.***
- It is common between 30-55 years; common in deep soft tissues of lower extremities with intact overlying skin.
- It is arising from fibroblasts. Intramuscular and intermuscular fibrous tissue, fascial envelops, aponeurosis and tendons are common origin.
- Commonest site is thigh.
- Spindle fibroblasts with *'herring bone'* pattern are typical on microscopy.



Fig. 1.616: Recurrent dermatofibrosarcoma protuberans.

Types

1. *Well-differentiated.*
2. *Poorly differentiated.*
3. *Dermatofibrosarcoma protuberans*. It is common in trunk. *DFSP* is an intermediate grade fibrohistiocytic tumor with nodular cutaneous mass; common in adult male; common in trunk and proximal extremities having slow growth without deep muscle invasion. Skin is taut, nodular and commonly ulcerated.
4. *Aggressive fibromatoses* are variant of fibrosarcoma which are locally malignant in which desmoid tumour is also included.

Fibrosarcoma is slow growing tumour which attains large size.



Fig. 1.617: Malignant dermatofibrosarcoma left side of the chest wall.

Clinically it is smooth, hard, warm, localised tumour.

It compresses or infiltrates the adjacent structures like neurovascular bundle.

MALIGNANT FIBROUS HISTIOCYTOMA (MFH)

- It is group of malignant soft tissue tumours with a fibrohistiocytic appearance.
- MFH is one of the most common STS in adult.
- 70% occur in skeletal muscles.
- Lower extremity is the common site.
- It presents as solitary, multilobular lesion.
- It spreads along the fascial planes or between muscle fibres which is the probable reason for local recurrence.
- Myxoid/giant cell/inflammatory/angiomatoid/pleomorphic are the types. It is common in adults and elderly.



Fig. 1.618: Dermatofibrosarcoma.

LEIOMYOSARCOMA

- It arises from smooth muscle. Cut section shows whorled appearance.
- It constitutes 10% of STS; common after 60 years.
- Two third occurs in women.
- It is undetermined grade—aggressive.
- It is common in retroperitoneum and viscera, but can occur in limbs and skin. Uterus is also common site.
- Recurrence is common. It has got poor prognosis.
- It can occur in the piloerector muscle of skin; inferior vena cava; pulmonary artery.
- Desmin and actin are the most common immunohistochemical stains.



Fig. 1.619: Large soft tissue tumour over gluteal region with ulceration and vascularity. It was confirmed as malignant fibrous histiocytoma. Patient was successfully operated.

RHABDOMYOSARCOMA

- It arises from striated muscle.
- It is common in *head and neck*, upper thigh and arm.
- *It is commonest sarcoma in children.*
- It can occur in retroperitoneum, pelvis and genitourinary tract.
- It is common in males.



Fig. 1.620: Recurrent soft tissue tumour thigh. Note the scar of old surgery.

Types

1. *Pleomorphic*—msot common type of rhabdomyosarcoma. It is common in adult, aggressive with poor prognosis.
2. *Embryonal*—common in infants and children—*is seen in viscera like urinary bladder.*
3. *Botryoidal*—slow growing polypoidal—respond well to chemotherapy and radiotherapy.
4. *Alveolar*—chromosomal translocation is common.

It is more aggressive tumour with poorer prognosis (High grade).

It also metastasises to lymph nodes.

CHONDROSARCOMA

- It arises from chondroblasts.
- It attains large size with slow growing nature.
- Common sites are ribs, flat bones.



Figs 1.621A and B: Chondrosarcoma leg lateral aspect. X-ray shows calcified tumour. It was successfully removed as limb salvage procedure.

HAEMANGIOSARCOMA

It originates from blood vessel endothelium.

Types

Malignant haemangioendothelioma.
Malignant haemangiopericytoma.



Fig. 1.622: Aggressive haemangiosarcoma of the scalp.

LYMPHANGIOSARCOMA

- It arises from lymph vessel endothelium.
- It commonly occurs after radical lymph node dissection *Stewart-Treves syndrome*.

SYNOVIAL SARCOMA

- It is the 4th commonest type. It occurs 15-40 years of age.
- Origin need not be from synovium.



Fig. 1.623: Synovial sarcoma.

- 85-90% occurs in lower limb; head, neck and shoulder are the next common site.
- It is common in thigh, leg, shoulder, hand and foot.
- Occasionally it can occur in the abdominal wall and retroperitoneum.
- It is common in young individuals.
- It occurs adjacent to joint but uncommon to involve the synovial sheath of the joint.
- It spreads both through blood as well as through ***lymph nodes (20%).***
- It is very aggressive soft tissue sarcoma (High grade).
- Calcification with or without ossification is common—10%.
- Synovial sarcoma may be biphasic or monophasic.
- It possess specific chromosomal translocation (96-100%) – t(X; 18)(p11.2; q11.2).

MALIGNANT PERIPHERAL NERVE SHEATH TUMOUR (MPNST)

- It arises from peripheral nerves.
- It shows differentiation along nerve elements.
- MPNST replaced olden terms—malignant schwannoma, neurofibrosarcoma, neurogenic sarcoma, malignant neurilemmoma.
- 20-50% arises from neurofibromatosis type 1 (latent period 15-20 years). MPNST is an exception to sarcoma will not arise from benign precursor.
- Common sites are major/proximal nerve trunks.

KAPOSI'S SARCOMA

- It is malignant blood vessel tumour of multicentric origin arising from vascular smooth muscle or pericytes.
- It is seen commonly in HIV patients due to immunosuppression.
- Primary tumour commonly occurs in skin, mucous membrane, lymph nodes or viscera.
- It is linked with Human Herpes Virus 8(HHV8) as causative agent.

Types

1. *European Kaposi's sarcoma*: It is common in old age. It is first described by Kaposi in 1862. It mainly involves skin especially lower extremity. Visceral involvement is rare.
2. *African Kaposi's sarcoma*: It occurs commonly in children and young individual. It involves skin and lymph nodes commonly. It resembles lymphoma.
3. *Transplant associated Kaposi's sarcoma*: It is due to drug induced immunosuppression. It involves mainly skin and often regresses once immunosuppression is discontinued.
4. *AIDS associated Kaposi's sarcoma*: It occurs in 30-40% of AIDS patients. It is common in homosexuals. It has got wide, disseminated involvement with metastases. It is very aggressive. It is often associated with lymphoma and other malignancies.

Note:
Kaposi's sarcoma is not found in transfusion related AIDS.

Clinical Features

- Multiple reddish-blue nodules in the skin with ulceration over the nodule.
- Lymph node enlargement.
- Koebner phenomenon is common in areas of trauma.

Differential Diagnosis

- Lymphomas.
- Cutaneous angiomatoses.
- Mycobacterial infection of skin.

Investigations

- Biopsy from the skin lesion.
- Tests for HIV infection.

Sarcomas which also spread to lymph nodes

1. Synovial sarcoma
2. Lymphangiosarcoma
3. Rhabdomyosarcoma—alveolar type
4. Ewing's sarcoma
5. Angiosarcoma
6. Epithelioid sarcoma
7. Carcinosarcoma of uterus

Treatment

- Irradiation.
- Chemotherapy. Drugs used are adriamycin, bleomycin and vinblastine.
- Antiretroviral therapy.
- Interferons.

T. Amputations

> *"Amputation is one of the meanest yet one of the greatest operations in surgery, i.e. mean—when resorted to where better may be done. Great—as the only step to give comfort and prolong life."*
>
> **—Sir William Ferguson**

CHAPTER OUTLINE

- Amputation
- Complications of Amputations
- Prosthesis

AMPUTATION

Indications

- Gangrene due to atherosclerosis, embolism, TAO, diabetes, ergots.
- Trauma: To save life in crush injuries.
- Neoplasms: Osteosarcomas, Marjolin's ulcer, melanomas.
- Gas gangrene.
- Severe sepsis.
- Occasionally severe elephantiasis, madura foot, when all other methods have failed to help.
- **Dead, dying, devitalised tissues.**
- Severe deformity congenital or acquired.

Types

It can be:
- *Non-end bearing/side bearing*—Weight is taken up by the joint.
- *End bearing/cone bearing*—Weight is taken up by the body.

It can be:
- Weight bearing.
- Non-weight bearing.

It can be:
- *Provisional* amputation with flap – later final formal amputation my be required.
- *Guillotine* amputation which always requires revision formal amputation.
- *Formal* amputation – is definitive one.

Types of Flaps

- *Long posterior flap* in below-knee amputation.
- *Equal flaps* in above-knee amputation.

Ideal Stump

- Should heal adequately by 1st intention.
- Should have rounded, gentle contour, with adequate muscle padding.
- Should have sufficient length to bear prosthesis.
  - For B-K 7.5 (minimum) to 12.5 cm from tibial tuberosity
  - For above and below elbow 20 cm stump.
  - For A-K 23 cm from greater trochanter.



Figs 1.624A and B: Different levels of amputation in upper limb and lower limb.



Fig. 1.625: Little toe amputation for gangrene. Wound has healed well.



Fig. 1.626: Forefoot amputation.



Fig. 1.627: Above-knee amputation done for osteosarcoma of the upper end of the tibia. Here equal flaps are used.

- Should have thin scar which does not interfere with prosthetic function.
- Should have adequate adjacent joint movement.
- Should have adequate blood supply.
- Scar should be in a place where it is not exposed to pressure.
- Scar should be freely mobile over underlying tissues. Skin and scar should be freely mobile over the underlying bone. It is achieved only if deep fascia is closed properly. Scar and skin should be free to achieve free movement of the prosthesis. Socket of prosthesis with mobile skin creates a piston to bone to move like a joint.
- Skin should not be infolded.
- Redundant soft tissue should not be there.
- Stump should be free from tenderness and conical.

Conical bearing

- Here healing is by primary intention
- Bone should not be projecting
- Myoplastic
- No neuroma
- Scar should not be tender
- Proximal joint should be supple

Evaluation of the Patients who need Amputation

- Haematocrit, control of anaemia by transfusing blood/packed cells.
- Control of infection using antibiotics.
- Decision of level of amputation by skin temperature, arterial Doppler.
- Informed consent should be taken.
- Plan for prosthesis and rehabilitation by physiotherapist and rehabilitation team.

Different incisions for amputation

- *Circular incision amputation*—skin and muscles are divided circularly at a lower level than that of bone
- *Elliptical/oval incision* amputation
- *Racquet incision amputation*—for digital disarticulation
- *Amputation using flaps*—it may be of equal flap (above knee amputation) or with long posterior single flap (below knee amputation). Total length of single flap or combined length of two flaps should be equal to 11/2 times the diameter of the limb at the line of amputation. Flap should be semicircular to get a conical stump, not rectangular

Principles in Amputation

- Adequate blood supply of the flap should be maintained.
- Proper marking of the skin incision is essential.
- Tourniquet *should not be used* if amputation is done for vascular diseases.
- Proximal part of the flap contains muscle component but distal part should contain only skin and deep fascia.
- Flap length should be adequate; not short. It should be ideally semicircular not rectangular to get a conical stump.
- Nerve should be pulled down and cut using a sharp knife and allowed to retract into the soft tissue otherwise neuromas may develop.
- In crush injury/entrapment injury/sepsis—guillotine amputation is done. Later skin is pulled down by using skin traction, eventually to have better skin coverage.
- Bone should be cut with beveling and all sharp margins should be rounded.
- Postoperatively regular dressings are done. Patient is mobilised using axillary crutches. After 3 months, once scar has matured and stump has become supple, proper prosthesis is fit. *Berlamont* first started immediate postoperative fitting

Asking for help is strength, not weakness.


Bones
Plaster of Paris
BK amputated limb
Walking component

Fig. 1.628: Pylon is plaster cast with walking component used for immediate mobilisation after below-knee amputation.

of prosthesis to leg for early mobilisation. *Plaster pylon* is applied to the stump and a prosthetic extension is fit to facilitate partial weight bearing immediately after surgery. It has got more stump complications and so it has not become popular.

- Stumps can be side bearing (sutures are on the side); end bearing/conical (sutures are on the end) or cylindrical.
- Postoperatively active exercise should be given to the proximal joint so that prosthesis can be fit to it properly.
- If there is sepsis especially in gangrene limb, flaps should be left open or loosely sutured otherwise flap necrosis occurs.
- Proper anatomy of muscles and neurovascular bundle around should be known in all amputations.

Different Amputations

- ***Ray amputation***
  Amputation of toe with head of metatarsal or metacarpals.


8
7
Gritti-Stokes
6
5
4
3
2
1
1. Ray's
2. Transmetatarsal (Gillies)
3. Tarsometatarsal (Lisfranc's)
4. Midtarsal (Chopart's)
5. Syme's
6. Below-knee (Burgess)
7. Transcondylar
8. Above-knee

Fig. 1.629: Different levels of amputation in lower limb.


Incision for ray amputation

Fig. 1.630: Ray amputation for toes—racquet incision.



Fig. 1.631: Ray's amputation done for gangrene of great toe. It is usually not sutured.



Fig. 1.632: Forefoot amputation.

- ***Transmetatarsal amputation (Gillies')***
  Here amputation is done proximal to the neck of the metatarsals, distal to the base.
- ***Lisfranc's amputation* (*Tarsometatarsal amputation*)**

Here tarsometatarsal joint is disarticulated with a long volar flap. It needs a surgical boot. But there is inevitable development of equinovarus deformity. So stabilisation of midtarsal and ankle joints is needed. In Hey's modification, 2nd metatarsal is cut at base instead of disarticulation.

- ***Chopart's amputation (Midtarsal amputation)***
  Here talonavicular joint and calcaneo cuboid joints are disarticulated. Tibialis anterior muscle is sutured to drilled talus bone. A long volar flap is used and immobilised for 6 weeks after surgery.
- ***Syme's amputation***
  - It is removal of the foot with calcaneum and cutting of tibia and fibula just above the ankle joint with retaining heel flap (dividing both malleoli). Heel flap is supplied by medial and lateral calcaneal vessels (branches of posterior tibial artery). *Elephant boot* is used for the limb after Syme's which is inexpensive. Many patients walk well with Syme's stump without difficulty. It is presently mainly used in trauma (crush injury) and malignancies in distal part of the foot. In vascular diseases, calcaneal vessels may not be adequate to maintain the viability of the flap. While raising the flap, knife should be very close to the calcaneum so as to avoid injury to calcaneal vessels and to maintain the viability of the flap.
  - In *Wagner's method* deep fascia of heel is sutured to drill holes made on the anterior edge of tibia and fibula. *Above knee cast* is essential.
  - *Advantages are*—it is an end bearing stump having good proprioception. Patient can walk without prosthesis. Low energy consumption ambulation is possible.
  - *Disadvantages*—posterior displacement of heel pad; poor cosmesis.
  - *Boyd's amputation*—anterior part of the calcaneum is excised (osteotomy) just distal to the peroneal tuberosity and calcaneotibial arthrodesis is created. It is done to prevent posterior migration of heel pad.



Fig. 1.634: Incision for Syme's amputation.



Fig. 1.635: Elephant boot used after Syme's amputation.

- ***Modified Syme's amputation***
  Here heel flap is elliptical. Tibia and fibula are divided slightly higher. But variation here is the elliptical flap.



Fig. 1.633: Syme's incision and level of amputation.



Fig. 1.636: Modified Syme's incision is elliptical one.

Imagination is the highest kite one can fly.

Pirogoff‘s amputation

It is like Syme’s amputation except posterior part of the calcaneum is retained along with heel flap. It provides longer stump than Syme’s amputation.



Fig. 1.637: Pirogoff’s amputation.



Fig. 1.638: Below-knee amputation technique—incision, flap and levels of cutting bones.



Fig. 1.639: Below-knee amputation—long posterior flap. Note the placing of the drain.



Fig. 1.640: Below-knee amputation flap necrosis has occurred which eventually granulated with repeated dressings. Area is ready for skin grafting.



Fig. 1.641: Bilateral below knee amputations done for vascular causes with diabetes.

Below-knee amputation

Here we use a long posterior flap with scar placed over anterior aspect is used. Prosthesis placement is better here with greater range of movements without limp and without support. It is also called as *Burgess amputation*. Fibula should be divided first, higher than the proposed site of cut of tibia otherwise its sharp end will press on the skin flap. Tibial stump should be beveled anteriorly. Posterior muscles are sutured across the bone end, to the periosteum in front. In more proximal type of below knee amputation, fibula often is removed to allow the proper use of flap. Length of the flap should be 11/2 times the circumference of the site (around 12 cm). Stump length is 14-17 cm from knee joint. Minimum length required for prosthesis is 8 cm. If need to extend more proximally, it is better to do above knee amputation. Modern artificial limbs like *suction socket prosthesis* are used now.

- ***'Peg-leg' amputation***
  - It is amputation 5 cm below the knee level – proximal most below knee amputation. It is *not practiced* nowadays. Here anterior flap is rotated posteriorly like a hood and patient kneels and bears weight which is well-accustomed to pressure. It is done whenever prosthesis cannot be used probably due to economic causes (in developing countries).



Fig. 1.642: 'Peg-leg' amputation is below-knee amputation done close to the knee joint (5 cm stump) with folding flap and metallic support down. It is not used now.

- ***Transcondylar-Gritti-Stokes amputation*** with long posterior flap.
  - Femur is divided just above the articular surface and patella is anchored to the divided femur. There is risk of nonunion between patella and femur. This procedure is *no longer performed.*
- ***Above-knee amputation***
  - Usually equal anterior and posterior flaps are used. Lower third and middle third level amputations are done. Ideally the required length of the femur as stump is 25 cm from the tip of the trochanter. Femur length lesser than 10 cm is not possible and here one needs to do hip disarticulation. In children as growing epiphysis of femur is in lower end, it is essential to preserve as much length of femur as possible. It is done in ischaemia, trauma, sepsis, gangrene which is spreading above. Often patient might earlier have undergone below knee amputation but now as indicated need above knee amputation. It is usually contraindicated in children (done only in undue definitive indication) or if stump is less than 7.5 cm.
  - *Advantages* are technically easy, healing chances are better and faster. *Disadvantages* are cosmetically poor, rehabilitation is difficult, and fitting of prosthesis is not proper, patient needs a third support for walk with often a limp.



Fig. 1.643: Above-knee amputation, incision and approach.



Fig. 1.644: Above-knee amputation wound which is infected in a diabetic patient.

- ***Hip disarticulation***
  It is done whenever it is not possible to save the minimum 10 cm length of the femur. Incision used is either single posterior flap—Solcum's approach (better) or anterior racquet incision—Boyd's approach.
- ***Hind quarter amputation***
  Inter innominate abdominal amputation (*Sir Gordon Taylor's* amputation): Removal of one side pelvis with innominate bone, pubis, muscles and vessels. Original ligation of common iliac artery is modified to individual ligations of external and internal iliac vessels. Internal iliac artery is ligated beyond the origin of the superior gluteal artery to keep the large posterior flap viable. *Now hind quarter name*

The most popular Jaipur foot was designed by PK Sethi.

is replaced by hemipelvectomy. It may be *standard hemipelvectomy* with classic gluteal flap; *extended hemipelvectomy* with removal of posterior part of the sacrum; *conservative hemipelvectomy* with retaining part of the pubis, ilium bones on that side. *Internal hemipelvectomy* is new method wherein *hemipelvectomy* is done with preserving the limb.



Fig. 1.645: Hindquarter amputation done for run over of vehicle over pelvis, right thigh. Patient also underwent colostomy. Patient survived with severe morbidity.

- ***Krukenberg's amputation***
  Done in upper limb following any trauma. Here forearm amputation is done in such a way that it creates a gap between radius and ulna like a claw to have a hold or grip.
- ***Interscapulothoracic amputation*** *(Forequarter amputation)* (*Littlewood's* posterior approach or Berger's anterior approach):



Fig. 1.646A



Fig. 1.646B

Figs 1.646A and B: Forequarter amputation done for electric burn which caused extensive damage to upper limb.

It is removal of entire upper limb with scapula and lateral 2/3rd of the clavicle and muscles attached to it. It is done in malignancies involving scapula, upper part of humerus and near shoulder joint.

- In emergency conditions like severe sepsis, gas gangrene and machinery entrapment, ***Guillotine amputation*** is done without suturing. Suturing is done at later period. All tissues are divided at same level.

Postoperative Period

- Physiotherapy is advised.
- Regular dressings are done.
- Crutch is used initially, after 3 months prosthesis is placed.
- Rehabilitation is important.



Fig. 1.647: Upper limb *Guillotine amputation*—above elbow done for trauma induced gas gangrene.



Fig. 1.648: Forequarter amputation done for sarcoma proximal to shoulder joint.



Fig. 1.651: Ulcer in the below-knee amputated stump.



Fig. 1.649: Above-knee amputation stump having small sinus.



Fig. 1.652: Ulcer after great toe amputation done for vascular gangrene.



Figs 1.650A and B: (A) Below-knee amputation stump infected. (B) Tibia is exposed.

COMPLICATIONS OF AMPUTATIONS

Early

Haemorrhage, haematoma, infection.

Late

Pain, ulceration of stump, ring sequestrum formation, flap necrosis, painful scar, *Phantom limb*—feeling of amputated part in toto or partially with pain over it.

Haematoma

It is identified by pain, swelling over the stump underneath the flap. It is aspirated using a wide bore needle. Haematoma may delay healing; may precipitate infection or flap necrosis due to pressure. After aspiration, pressure dressing is needed. If haematoma reforms after 2-3 aspirations, it should be drained by opening the wound on one corner and inserting haemostat into the wound.

Infection of the Stump

It may cause abscess formation, delay in wound healing, flap necrosis, giving way of the wound. Removing few or all sutures to relieve pressure and draining the pus underneath is needed. Infection may also lead into poor scar, adherent scar which causes difficulty in placing the prosthesis.

Flap Necrosis

It is a *common* complication. Main causes for flap necrosis are poor blood supply, infection, haematoma underneath, inadequate length of the flap causing stretching of flap. Small area of necrosis can be excised. Wider area needs laying opening of the wound or revision of the stump or higher level amputation. Anaemia, poor nutrition, nutritional deficiencies, diabetes mellitus, immunosuppression, smoking, old age are other factors causing flap necrosis.

Stump Neuroma

It can occur due to proliferation of the nerve fibrils beyond the point of nerve division and is usually due to failure of cutting of the nerve more proximal to the level of division of the bone. It causes pain and tenderness over the stump. It is usually relieved by analgesics, reassurance and prosthesis. Occasionally it may require reexploration of the wound, excision of end neuroma and also cutting nerve more proximally.

Stump Pain after Amputation

It is *a common problem*. Causes are—infection, poor blood supply, causalgia, stump neuroma, phantom pain/limb, deep vein thrombosis, adherent scar, formation of spurs and osteophytes at amputated bone end. Scar adhesion to bone is prevented by keeping adequate length of deep fascia underneath intact. Spurs and osteophytes are confirmed by X-ray and needs removal using bone nibbler after appropriate skin incision.

Phantom Limb

It is *typical* awareness of sensation that as if amputated part is still present *partly or in toto*; often such part may be painful or disturbing or hyperaesthetic. Exact cause is not known; but it is probably due to presence of severe pain at the amputated part just prior to amputation making brain area for that part in alert situation causing phantom limb. Reassurance, prosthesis, analgesics help to control the condition. It is said that it can be prevented by proper pain control for 24 hours prior to amputation; but it is often difficult. It is common in upper limb.



Fig. 1.653: Patient with axillary crutches.

Ulceration Over the Stump

It is *not uncommon*. It is due to necrosis, infection, lengthy bone stump pressing on the summit of the flap, prosthesis, nutritional deficiencies, diabetes mellitus, ischaemia. Ulcer may be small/large; superficial/deep. Callous chronic ulcer at the end of the stump is called as *Douglas ulcer*. Small ulcer is later treated by regular dressings and suturing. Large ulcer needs flap to cover the defect. *Osteomyelitis of the stump* should be ruled out in chronic stump ulcer. *Ring sequestrum* may be typical in such situation. Revision amputation is needed for the stump.

Contracture of the Joint

Contracture of the joint proximal to the amputated stump is *common.* It is mainly due improper positioning after amputation due to pain, poor exercise and occasionally due to inflammation of surrounding soft tissues. Contracture interferes with proper fitting and functioning of the prosthesis and delays rehabilitation. Proper positioning, passive stretching and exercises, strengthening exercises with help to correct it. Rarely needs surgical release of the contracture.

Other Complications

- Scar hypertrophy, skin thickening, hyperkeratosis, papilloma, eczema,lymphoedema, boils, bursae over bony point can occur which are treated accordingly.
- Spur, osteophyte formation, causalgia, jactitation of the stump, stump aneurysm, stump fracture— are other complications.

PROSTHESIS

It is the substitution to a part of the body to achieve its optimum function.

(Orthroses are supplement for limb function.)

In Lower Limb

- *Syme's amputation*: Elephant boot, Canadian Syme's prosthesis.
- *Below-knee amputation*: Patellar tendon bearing (PTB) prosthesis and solid ankle cushion heel (SACH).
- *Above-knee amputation:* Suction type prosthesis. It is placed above the stump. It is better and well-tolerated.
- *Nonsuction type prosthesis*: It is placed at the ends. It requires additional support.
- *Hind-quarter amputation:* Tilting table prosthesis (TTP) or Canadian prosthesis is used here.
- *Patellar tendon bearing prosthesis (PTB prosthesis)*: Here all the weight bearing is done below knee; movement is controlled by his own knee joint. Patellar tendon is the main key weight bearing area within the socket; stump posteriorly up to the popliteal fossa is also important to provide counter pressure so that patellar tendon is kept in place. Medial and lateral paratibial areas and medial condylar flare also bear significant weight. Head of the fibula, tibial tubercle, cut ends of tibia and fibula are pressure intolerant areas. Socket should have proper relief areas to these intolerant parts.
- *Computer-assisted designing and computer-assisted manufacturing (CAD – CAM) socket* is an automated processing method which fulfills all above criteria accurately with modifications. It is more comfortable and is made up of thermoplastic or laminated plastic with closed cell polyethylene foam.
- Suspension for below knee amputation prosthesis is leather cuff strap above femoral condyles. Exo or endoskeleton is used. For athletics endo skeleton is preferable.
- *SACH (Solid Ankle Cushion Heel) foot* is used. It is multiaxial, optimizes gait, and facilitates walking on rough ground. It needs minimal maintenance. It is preferred in old people. Energy storing foot is often used wherein ankle joint is replaced by a plastic spring.

In Upper Limb

1. Above elbow prosthesis is a high technology prosthesis. It is sophisticated device with harness, socket, elbow joint unit, control cable, forearm and wrist device.
2. Below elbow prosthesis.
   Krukenberg's amputation does not require any prosthesis.

Advantages of Prosthesis

- Cosmetic.
- Function of the part relatively can be got.
- Ambulation in lower limb prosthesis.

Disadvantages

- Infection.
- Pressure ulcers.
- Joint disability.

Prosthesis Types

- Exoskeletal prosthesis.
- Endoskeletal prosthesis with modular system.

Internal prostheses are one used inside. They are placed by open surgery. They are nonreactive, long durable materials, e.g. hip prosthesis in total hip replacement.



Figs 1.654A to C: Below-knee amputee with prosthesis. It gives good range of movements, normal walk and comfort.

U. Reconstruction

CHAPTER OUTLINE

- Graft
- Skin Grafts
- Flaps
- Tendon
- Tendon Repair
- Tendon Transfer
- Tendon Graft

GRAFT

Graft: It is transfer of tissue from one area to other without its blood supply or nerve supply.

Autograft: It is tissue transferred from one location to another on the same patient.

Isograft: It is tissue transfer between two genetically identical individuals, i.e. between two identical twins.

Allograft: It is tissue transfer between two genetically different members, e.g. kidney transplantation (Human to human) (Homograft).

Xenograft: It is tissue transfer from a donor of one species to a recipient of another species (Heterograft).

SKIN GRAFTS

> *We bring back, refashion, and restore to wholeness the features which nature gave but chance destroyed, not that they may charm the eye but that they may be an advantage to the living soul, not as a mean artifice but as an alleviation of illness, not as becomes charlatans but as becomes good physicians and followers of the great Hippocrates. For although the original beauty of the face is indeed restored, yet this is only accidental, and the end for which the physician is working is that the features should fulfill their offices according to nature's decree.*
>
> —**Gaspare Tagliacozzi,** 1597

Skin Grafting: It is transfer of skin from one area (donor area) to the required defective area (recipient area). It is an autograft.

Types

1. PARTIAL THICKNESS GRAFT (Split-thickness skin graft—SSG)

Also called as *Thiersch graft*, is removal of full epidermis + part of the dermis from the donor area.

It may be

- *Thin SSG.*
- *Intermediate SSG*, all depends on the amount of thickness of dermis taken.
- *Thick SSG.*

Indications

1. Well granulated ulcer
2. Clean wound or defect which can not be apposed
3. After surgery to cover and close the defect created.
   For example:
   After wide excision in malignancy
   After mastectomy
   After wide excision in squamous cell carcinoma
   Graft can survive over periosteum or paratenon or perichondrium

Prerequisite

1. Healthy granulation area
2. β-haemolytic streptococci load less than 10^5 per gram of tissue, otherwise graft failure will occur

Contraindications

SSG can not be done over bone, tendon, cartilage, joint.

Technique

Donor area: Commonly *thigh,* occasionally arm, leg, forearm.

- Knife used is *Humby's Knife.*
- Blade is *Eschmann blade, Down's blade.*
- Using Humby's knife graft is taken, punctate bleeding is observed which says that proper graft has been obtained.

Different instruments used to harvest the skin graft

- Humby's knife
- Watson modification of Humby's knife
- Power dermatome is also used (Brown)
- Sterilised razor blade can be used with a specialised device to harvest small grafts under local anaesthesia



Figs 1.655A and B: Split skin grafting knife and set; and harvesting.



Fig. 1.657: Commonest donor area for spilt skin grafting is thigh.



Fig. 1.656: Miniature SSG knife to take stamp sized small grafts. Sterile razor blade is used in this.

Donor area is dressed and dressing is opened *after 10 days*, not earlier.

Recipient area is scraped well and the graft is placed after making window cuts in the graft to prevent the development of seroma. Graft is fixed and *tie-over* dressing is placed. If graft is placed near the joint, then the part is immobilised to prevent friction which may separate the graft. On *5th day,* dressing is opened and observed for graft take up. *Mercuro chrome* is applied over the recipient margin to promote epithelialisation.



Figs 1.658A and B



Figs 1.658C to E

Figs 1.658A to E: Technique of split skin grafting.



Fig. 1.659: Skin stapler can be used to fix the SSG to the margin of the recipient bed.

Stages of Graft Intake

1. *Stage of plasmatic imbibition*: Thin, uniform, layer of plasma forms between recipient bed and graft.
2. *Stage of inosculation*: Linking of host and graft which is temporary.
3. *Stage of neovascularisation*: New capillaries proliferate into graft from the recipient bed which attains circulation later.

***Note*:**

Graft is stored at low temperature of 4°C for not more than 21 days.



Fig. 1.660: Humby's knife with Eschmann blade.



Fig. 1.661: Harvesting a skin graft.



Figs 1.662A and B: Donor area of split skin graft in the thigh and graft placed over raw area in the leg.

Disadvantages of SSG

1. Contracture of graft. Two types:
   A. *Primary contracture* means SSG contracts significantly once graft is taken from donor area (20-30%). Thicker the graft more the primary contracture.
   B. *Secondary contracture* occurs after graft has taken upto recipient bed during healing period, due to fibrosis. Thinner the graft more the secondary contracture.
2. Seroma and haematoma formation will prevent graft take up.
3. Infection.
4. Loss of hair growth, blunting of sensation.
5. Dry, scaling of skin due to nonfunctioning of sebaceous glands. So after healing, oil (coconut oil) should be applied over the area.
6. Graft failure.



Figs 1.663A and B: Mercurochrome is often used to apply on the SSG recipient bed margin to promote epithelialisation. It is applied once a day.



Fig. 1.664A:



Figs 1.664B and C

Figs 1.664A to C: Mesher used in split skin grafting to increase its surface area to cover wider area like burns wound. A large defect can be covered by this. It can cause expansion of skin upto six times.

Advantages

1. Technically easier.
2. Wide area of recipient can be covered. To cover large area like burns wound, graft size is increased by passing the graft through a ***Mesher*** which gives multiple openings to the graft, which can be stretched on the wider area like a net. It can cause expansion upto 6 times.
3. Graft take up is better.
4. Donor area heals on its own.

5. Mercurochrome/merbromin is used as a local applicant to the edge of the grafted area (SSG) and small raw areas to promote epithelialisation. It is applied once a day.

2. FULL THICKNESS GRAFT (Wolfe Graft)

- It includes both epidermis + full dermis.
- It is used over the face, eyelid, hands, fingers and over the joints.
- It is removed using scalpel blade. Underlying fat should be cleared off properly. Deeper raw donor area is closed by primary suturing. If large area of graft is taken, then that donor area has to be covered with SSG which is a disadvantage in full thickness graft.



Figs 1.665A to C: Mesh graft placed over donor area and photo of it, once it takes up.

Common sites of donor area

1. Post-auricular area
2. Supraclavicular area
3. Groin crease area

Advantages

1. Colour match is good. Especially for face.
2. No contracture (unlike in SSG).
3. Sensation, functions of sebaceous glands, hair follicles are retained better compared to SSG.
4. Functional and cosmetic results are better.

Disadvantages

1. It can be used only for small areas.
2. Wider donor area has to be covered with SSG to close the defect.
3. Can not be used to cover ulcers.

Other Grafts

1. Composite graft which includes skin + fat + other tissues like cartilage.
2. Tendon graft.
3. Bone graft.
4. Nerve graft.
5. Venous graft.
6. Corneal graft.
7. Combined graft (allograft + autograft).

FLAPS

It is transfer of donor tissue with its blood supply to the recipient area.

Parts of Flaps

Base, pedicle, tip of flap. Vasculature is usually through the pedicle in the centre of the flap. Tip is the place where often flap goes for necrosis.

Indications

- To cover the wider, deeper defects
- To cover over bone, tendon, cartilage
- If skin graft repeatedly fails

Types

1. *Random pattern flaps*: Here vascular basis is subdermal plexus of blood vessels. No known blood vessel is supplying it. Rectangular flap with length to width ratios 1 : 1 or less than 1.5 : 1.



Fig. 1.666: Hand held Doppler to hear audible signal of perforator to do rotation flap in the leg.



Fig. 1.667: Traumatic exposure of the bone. Flap is needed to cover this defect. It could be cross leg flap or rotation flap. Skin grafting is not possible in this situation.


Dermal-Subdermal plexus
Segmental artery
Musculocutaneous and perforator arteries

Fig. 1.668: Anatomy and blood supply of a skin flap.



Fig. 1.669: Flap which has taken up well-placed over the defect on the bone with osteomyelitis.



Fig. 1.670: Different methods of immobilisation is needed for flap and SSG. Fixation is often used in limbs.

2. *Axial pattern flaps*: Here superficial vascular pedicles pass along their long axes, e.g. forehead flap, deltopectoral flap, groin flap. Anatomically a known blood vessel is supplying it. It is long lengthy flap.

Anatomical types depending on the types of tissue in the flap:

1. *Cutaneous flap*: Forehead flap, deltopectoral flap.
2. *Fasciocutaneous flap*: Radial forearm flap, scapular flap, lateral arm flap.


A
B
Inguinal ligament
Anterosuperior iliac spine
Groin flap
Superficial circumflex iliac artery
Femoral artery

Figs 1.671A and B: Groin flap is based on superficial circumflex iliac artery. It can be used in defects in hand and forearm. It is a cutaneous flap.


Thoraco-acromial artery
PM muscle

Fig. 1.672: Pectoralis major myocutaneous flap.


SSG
A
Lesion excised
Flap raised
Flap rotated (transposed)
B

Figs 1.673A and B: Transposition flap.

3. *Muscle flap*: Gluteus maximus muscle flap, gracilis flap, tensor fascia lata muscle flap.
4. *Myocutaneous flap*: Pectoralis major myocutaneous flap, latissimus dorsi flap - composite flap.
5. *Osteomyocutaneous flaps*: Radius with brachioradialis and skin, rib with intercostal muscles and skin—composite flap.
6. *Local rotation flaps*, *transposition flaps*: When the flap moves laterally it is called as transposition flap. When the flap rotates laterally towards defect it is called as rotation flap. Transposition flap is squarely designed which moves laterally to close the defect creating a larger area on its original place which has to be covered with split skin graft.
7. '*Z' plasty*: It is a procedure which involves transposition of two inter-digitating triangular flaps. There is change in



Fig. 1.674: Technique of 'Z' plasty. It is used in contracture release. Dupuytren's contracture and pilonidal sinus.


Lesion/defect
Flap
Flap

Fig. 1.675: Rhomboid flap


V-Y plasty
Y-V plasty

Fig. 1.676: Technique of V-Y plasty and Y-V plasty.


Defect with flap

Fig. 1.677: Bilobed flap is used in lesions of the nose commonly.



Fig. 1.678: Advancement flaps, used in distal defects.

direction as well as gain in length of the common limb of Z. Angle size and length of the limb are the most important factors. It is used in managing contracted scars, facial scars, Dupuytren's contracture and to cover the excised defects like pilonidal sinus (example). There should be transverse skin slack available equal to the length between the axes of Z. It can be single or multiple Z plasty. Complications are flap necrosis near the angle tip, infection, failure.



Fig. 1.679: On table marking of glabellar flap to place after excising a lesion in the root of the nose.

8. *Free flaps*: Vascular pedicle of the flap, both artery and vein are anastomosed to recipient vessels using operating binocular microscopes.
9. Omental flaps.
10. *Island flap*: Localised flap is swung around a stalk from the donor area to the recipient area often with the pedicle buried underneath the skin bridge in between. Pedicled flap is also an island flap.

Areas where flaps are commonly used: Oral cavity, neck, breast, limbs (leg), buttock, bedsores.

Flaps mobilised from donor area with its pedicle is placed and sutured to recipient area. Once flap takes up usually in 3-6 weeks, base of the flap is cut and sutured to recipient area.

Saltatory flap is mobilising the flaps in stages from distant donor area towards recipient area. It requires many staged surgeries and long term hospitalisation.

Waltzing is a technique wherein flap is moved from donor area and attached adjacent to the recipient defect area. Later in 2nd stage, it is moved towards the defect formally. It reduces the tension on the flap and increases the success rate.

Advantages of Flaps

1. Good blood supply, good take up.
2. Gives bulk, texture, colour to the area.
3. Allows required movements in the recipient area. For example, jaw movements after pectoralis major flap after wide excision with hemimandibulectomy for carcinoma cheek.
4. Cosmetically better.

Disadvantages of Flaps

1. Long-term hospitalisation.
2. Infection.
3. Kinking, rotation and flap necrosis.
4. Staged procedure.

Positioning of the patient for long time is important to have a good flap take up which is a real discomfort to the patient.



Fig. 1.680: Waltzing of flap.

Note:

Delaying of the flap after mobilisation is done to reorient its blood supply so as to decrease flap necrosis and increase flap survival. Delaying period is 10-14 days. Flap is raised properly as required and resutured to same place so as to allow the formation of reorientation of vasculature near the tip of the flap. This delayed flap is raised again in 10-14 days to place in required area.

Different Flaps Used are:

Forehead Flap

It is fasciocutaneous flap from forehead based on *anterior branch of superficial temporal artery.* Superficial temporal artery is terminal smaller branch of external carotid artery. It begins under the parotid behind the neck of mandible, runs vertically upwards, crossing the root of zygoma at preauricular point; 5 cm above the zygoma it divides into anterior and posterior branches. Anterior branch anastomoses with supraorbital and supratrochlear branches of ophthalmic artery. Artery supplies scalp of temple region and side, parotid, ear, facial muscles. Superficial temporal artery gives transverse facial artery which runs from anterior margin of parotid, and middle temporal artery which runs deep to temporalis muscle.



Fig. 1.681: *Saltatory flap*. Flap raised from the abdomen is reached to the cheek in stages—from abdomen to wrist; from wrist to cheek.



Forehead flap through anterior branch of superficial temporal artery

Bipedicle forehead flap through both anterior and posterior branches of superficial temporal artery



Figs 1.682A and B: Forehead flap based on superficial temporal artery. It is fasciocutaneous flap.

It is used for defects in cheek (carcinoma, cancrum oris) and nasal reconstruction.

Standard forehead flap is taken from forehead above the level of eyebrow starting from the opposite side of the midline with base just above the zygoma. Width of the flap is usually about 3-4 cm. Flap is dissected from the distal end of the marked area going deep up to epicranium, raising the flaps using scissor dissection. Flap is held up using skin hooks. Flap is rotated towards the defect area in the cheek. Inner area of the flap is covered with split skin graft. Donor flap area is covered with another split skin graft. After 3 weeks, base of the flap is disconnected; remaining proximal part of the flap can be replaced into forehead donor area. SSG over donor flap area takes up well. This flap often can be rotated under (deep to) the zygoma also.

A lined forehead flap can be used. After flap elevation, under surface of the flap is lined by split skin graft prior to rotation. This grafted lined flap is resutured into the donor area for 2 weeks until undersurface of graft takes up well; after 2 weeks flap is rotated towards the defect area (cheek).

Delaying of the flap is often done in forehead flap. Flap after elevation, is replaced into the original position to have optimum vascular reorientation; after 2 weeks it is again rotated towards defect. Delayed flap reduces the flap necrosis chances.

Often bipedicled forehead flap (*Narayanan's flap*) is used taking both from anterior and posterior branches of the superficial temporal artery. This flap is moved to defect in cheek with anterior branch part staying outside and posterior part will line the mucosal area.

A different type—*middle forehead flap* is used for nasal reconstruction.

Problems—Poor color match, contraction of flap and donor area is cosmetically nonacceptable.

Deltopectoral flap (Bakamjian flap)

It is based on first three perforating branches of the internal mammary artery (mainly 2nd perforator). Flap runs horizontally across the chest wall anteriorly towards shoulder tip from its base over the sternal border. Its upper border is along the line of the clavicle; its lower border is along the line of anterior axillary fold line. Raw area often requires a spilt skin grafting. It is usually rotated upwards often with waltzing. It is tubed and attached above. Tube is drained to prevent any collection to occur. Rotation angle is important to prevent any kinking in the pedicle. It is usually used to cover the defects in cheek, chin, mastoid and parotid region. Often flap is delayed to get adequate length.



Fig. 1.683: Deltopectoral cutaneous flap.

Groin flap (Fig. 1.684)

It is based on superficial circumflex iliac artery which is 2-3 cm below and parallel to the inguinal ligament. Artery originates from femoral artery over medial border of the sartorius and ends at anterior superior iliac spine. 1:1 rectangular flap with deep fascia is used. Secondary defect can usually be closed with sutures. It is used mainly for defects in wrist/forearm where positioning is easier.

Latissimus dorsi muscle/myocutaneous flap

It is based on thoracodorsal artery, a branch of subscapular artery. Skin over the upper and anterior border of Latissimus dorsi is used for transfer. It is commonly used to cover the defect after mastectomy. But it does not give the bulk. It is technically easier. It can be used as muscle flap also. It helps as skin cover. Prosthesis is needed to place underneath to provide bulk in post-mastectomy defect.



Fig. 1.684A



Fig. 1.684B

Fig. 1.684A and B: Groin flap used for burns defect in the hand.

Pectoralis major myocutaneous flap

It is based on the pectoral branches of thoracoacromial artery. Usually skin below and medial to nipple over the muscle is used. Muscle pedicle is made as broad as skin. It used to cover the defect over the cheek/neck/pharynx/intraoral lesions after wide excision with removal of skin over the tumour. Vessel marking is 2 cm medial to coracoid process, obliquely below the clavicle at the junction between middle third and outer third. Skin with muscle is dissected from the deeper structures like ribs, intercostal muscles and pectoralis minor. Flap is raised upwards up to the coracoid. Lateral pectoral vessels if possible are retained, otherwise can be sacrificed. Defect



Figs 1.685A and B: Pectoralis major myocutaneous flap used for carcinoma cheek.

below is usually closed primarily with sutures. Often it needs spilt skin grafting. Pectoralis major flap can be used along with deltopectoral flap with proper planning.

Gastrocnemius muscle flap

It is either medial or lateral and is commonly used to cover the upper part of the tibia and knee joint. It is technically easier and functional deficit occurring at donor area is insignificant. It is rarely used as myocutaneous flap.

Transverse rectus abdominis muscle flap (TRAM flap)

It is either superior pedicle based on the superior epigastric vessels or inferior pedicle based on the inferior epigastric vessels. Superior pedicle based flap is used to cover postmastectomy area or chest wall defect. To cover post mastectomy area opposite side superior pedicle is used to reduce the arc through which flap has to rotate (but rotating from opposite side is technically difficult). Inferior pedicle flap is used to cover the defects in groin and thigh. Proper marking of the flap is essential. Skin incision is made like an ellipse. Anterior rectus sheath is cut in the line of incision and is raised upwards carefully of the rectus muscle up to the xiphisternum. Muscle is gently separated of the posterior rectus sheath with care not to injure the epigastric vessels. Once dissection is complete lower part of the muscle is cut in superior pedicle to rotate upwards carefully. In the upper part again anterior rectus sheath is opened to pass the flap towards the defect in subcutaneous plane. TRAM flap gives bulk and contour to the defect. But it is technically difficult. Usually opposite side of the defect is taken as flap as it is easier to rotate from opposite side. Defect in the abdomen usually needs mesh to support and close. It is not possible to do this flap in obese individuals and if patient has undergone laparotomy earlier (with a lengthy scar). Inferior cut end of the inferior epigastric artery in superior pedicle flap can be anastomosed to a vessel in recipient bed to improve the perfusion *(supercharging)*. Inferior epigastric artery in inferior pedicle can be additionally perfused using opposite inferior epigastric artery (*recharging*).

Radial forearm flap

It is perfused from the radial vessels and raised on the flexor aspect of the forearm. Perforating branches of these vessels supply deep fascia and skin over it. Flap can be fasciocutaneous or osteofasciocutaneous/osteomyofasciocutaneous if radial bone is also used as part of the flap. Radial forearm free flap is commonly used for mandible defects. It is technically easier and safer. Flap is raised along with skin, segment of the radius along its intermuscular septum through which vessels pass and brachioradialis as components. Care is taken in dissecting vessels of the bed and not to injure the radial nerve. In free flap artery is sutured to the recipient artery like facial artery using microscope. Other similar flaps are—ulnar forearm flap, scapular flaps, and vascularised fibular transfer.

Limberg flap

It is a type of rhomboid flap used in pilonidal sinus with base at gluteal skin.

Cross leg flap

It is commonly used to cover the defect in the foot/leg from opposite leg.



Figs 1.686A to C: Rhomboid flap used to cover the defect after excising a lesion in the arm.



Figs 1.687A and B: Cross leg flap.



Fig. 1.688: Rotation flap. It is commonly used in gluteal region in managing bedsores.

TENDON

- Tendon is the continuity of the muscle to have its action at the site especially in hand, foot and digits.
- It is covered by synovial sheath with a thin layer of fluid in between which allows smooth gliding of the tendon.

Tendon after injury heals by:

1. **Intrinsic healing method** occurs through synovial fluid when tendon is not under stress.
2. **Extrinsic healing method** occurs through proliferation of fibroblasts across epitenon. It occurs when tendon is under stress. It forms a mass of fibrous tissue at the site called as "*tenoma*". It may interfere with the proper gliding of the tendon.

Stages of tendon healing

- By 21 days, weak healing occurs and contraction of muscle is possible
- By 6 weeks, mild traction can be applied to the tendon
- By 3 months, moderate stress can be used
- By 8 months, full tensile strength is recovered

Tendon injuries may be cut wound, lacerations, injury associated with nerve or vessel injury.

TENDON REPAIR

1. ***Primary repair*** is done within 24 hours.
2. ***Delayed repair*** within a week after 24 hours.
3. ***Secondary repair*** anytime after one week.

Types of Suturing the Tendon

1. ***Kessler method***. Here knot comes in the cut part of the tendon.
2. ***Goldner method***. Here knot comes away from the cut ends of the tendon.

Suture material used is monofilament nonabsorbable suture material (polypropylene, 3 or 4 zero).

- Continuous sutures are used for suturing.
- Epitenon can be later apposed with interrupted sutures.
- Postoperative immobilisation is advised for 3-4 weeks.
- Later passive and active exercise is done with the help of a physiotherapist.

Complications of tendon suturing are infection, adhesion, stiffness and failure.



Fig. 1.689: Types of tendon suturing

TENDON TRANSFER

- It is the transfer of one tendon from its existing site to another site where its function is required to have a function required at the newer site.
- Function of the transferred tendon should be maintained by other tendons.
- Tendon should be able to acquire the function at the newer site properly.
- For example, in ulnar claw hand, the tendon of flexor digitorum superficialis (FDS) (of index finger) is transferred to lumbrical canal of the digits to have flexion at MCP joint and extension of proximal IP joint.

TENDON GRAFT

- When tendon suturing or transfer is not possible because of inadequate length, tendon of a muscle which is not of much help functionally, is taken as a graft to obtain required length.
  Common grafts used are:
  - Palmaris tendon in forearm.
  - Plantaris tendon in leg.
  - For example, extensor carpi radialis brevis (ECRB) is lengthened using tendon graft to transfer to lumbrical canals in claw hand.

Problems in tendon graft: Infection, adhesions, graft failure, stiffness of the part.

V. Transplantation

CHAPTER OUTLINE

- Preoperative Evaluation
- Organ Procurement
- Renal Transplantation
- Immunosuppressive Agents
- Liver Transplantation
- Bone Marrow Transplantation
- Pancreatic Transplantation
- Small Bowel Transplantation
- Dialysis
- Cimino Fistula

PREOPERATIVE EVALUATION

- General evaluation: Pulmonary, cardiac, GIT, renal status and cancer screening.
- Immunologic evaluation: Serology for hepatitis, HIV, cytomegalovirus.
- Placing the organ in the same position is called as orthotopic transplantation, e.g. liver.
- Placing the organ in new position is called as heterotopic transplantation.

Donor Criteria

a. *Cadaver donor*

- Individuals with severe brain injury resulting in brain death.

  Brain death is defined as "complete irreversible cessation of all brain functions".

Criteria for brain death

- Absence of spontaneous respiration
- Absence of cranial reflexes
- Absence of response to stimuli
- Irreversible causes
- Absence of cerebral blood flow
- Isoelectric EEG
- Sustained apnoea with elevated CO_2

Other criteria for cadaver donor:

- Normothermic patient.
- No respiratory effort by the patient.
- Brain—dead donor.
- The heart is still beating.
- No depressant drugs intake should be there while evaluating the patient.
- Individual should not have any sepsis, cancer (except brain tumour).
- Not a HIV or hepatitis individual.

b. *Living donor*

- Living unrelated donor.
- Living related donor.
- Individual should have normal health.

Requirements

- ABO typing.
- Serology tests.
- Angiogram.
- Intravenous urography.
- HLA typing.

Human Leucocyte Antigens (HLA)

They are cell surface molecules which are highly antigenic. They play main role in graft rejection and hence called as *major histocompatibility complex/antigens* MHC) (Dausset, 1958). *Class I* are located in nucleated cells. *Class II* are located in dendritic cells/macrophages/B cells, etc.

Major histocompatibility complex (MHC)

- MHC is located in chromosome number 6
- Individual will have two HLA (*Human Leucocyte Antigens*) genes inherited from each parents, which together called as HLA types
- Class I— HLA is HLA-A, HLA-B and HLA-C. Intracellular antigens
- Class II—HLA is HLA-DP, HLA-DQ and HLA- DR. Extracellular antigens
- HLA-DR is most important in kidney transplantation

Principles of donor organ retrieval

- Adequate exposure is needed
- Control of the vessels above and below the organs to be removed is done
- Initiation of preservation *in situ*
- Removal of the organs, and separation.
- Completion of preservation
- Removal of iliac vessels for vascular reconstruction of pancreas and liver grafts
- Organ packaging

The winner always has a programme; the loser always has an excuse.

ORGAN PROCUREMENT

Principles of Organ Procurement

- Once brain death has been confirmed in cadaver donor, after giving inotropic support drugs (T3 and argipressin) various organs are surgically removed carefully with preservation of their vessels. After removal, organs are flushed with chilled preservative solution (in specific organ procurement like of kidney, *in situ* perfusion of organs (kidneys) is done by placing double balloon catheter into the abdominal aorta and a balloon catheter into the femoral vein) and placed in sterile bags containing saline and organ preservative solutions which are then immersed in 0-4°C box containing ice. Donor specimens are transported to the site of the recipient centre. *Wisconsin and Euro-Collins solutions* are commonly used.
- *Non-heart beating donors (NHBD)*—here organs are procured from individuals who are just dead on arrival to the hospital or who have died in the hospital in spite of resuscitation. *Category I*—Dead on arrival; *Category II*—Unsuccessful resuscitation; *Category III*—'Awaiting cardiac arrest' after support withdrawal; *Category IV*—Cardiac arrest with brain death.
- *University of Wisconsin solution* contains—potassium lactobionate; sodium phosphate; magnesium sulphate; adenosine; allopurinol; glutathione; raffi-nose; hydroxyethyl starch; insulin; dexamethasone; potassium; sodium; with 320 mosmol/l osmolality and pH of 7.4.
- *Living donor's organs* are used commonly in kidney transplantation from genetically related individuals. It can be used from genetically unrelated donors after proper MHC match. Donor nephrectomy is done through loin incision (commonly from left side). Laparoscopic donor nephrectomy has become popular and safe.

Technique of Organ Procurement

Positioning the donor on the operating table: Supine position, with arms abducted on boards and legs laid flat and uncrossed. The neck is extended by placing a sandbag under the shoulders (as during thyroidectomy).

Midline sternotomy incision is used extending up to the pubic symphysis with a supraumbilical horizontal part. Abdomen and thorax are exposed properly. Retroperitoneal right sided mobilisation is done (*Cattel-Braasch manoeuvre*). Cannulation of inferior mesenteric vein is done. Aortic cannulation is done. Perfusion of preservative solution is done.

Sequence of the thoracic organ procurement: First the heart (care must be taken to leave enough supradiaphragmatic IVC for both organs such as the liver and the heart); then the lungs separately or together are procured. Cooling of the abdominal organ has to be continued until the last thoracic organ is procured.

Sequence of abdominal organ procurement: The small bowel is the most sensitive organ for ischemia; therefore, it is retrieved first. The second organ to be procured is the pancreas followed by the liver. Liver and the pancreas could also be retrieved *en block* and split on the back table. Finally, the kidneys are the last organs to be procured.



Fig. 1.690: Incision for organ procurement.

The most popular tool kit comprises the iliac vessels, which consists of common, external and internal artery and the vein.

Organ Packing in Steps (Eurotransplant or National Transplant Organisation)

The first bag is filled with a cold preservative solution. The procured organ must be completely covered by the preservative solution, and the bag must be closed (well tied) without any air. The second bag or a wax-impregnated fibre container is filled with cooled saline or Ringer lactate solution. The first tied bag must be completely covered in one of the solutions and closed (well tied) without air. Third bag dry, without air, well tied and sometimes covered with a sterile drape is also used. Finally the organ is placed in an icebox and well covered with nonsterile melting ice, the box is firmly closed to make the organ ready for transportation.

RENAL TRANSPLANTATION

> *An animal which has undergone a double nephrectomy and grafting of both kidneys from another animal can secrete almost normal urine with his new organs, and live in good health for at least a few weeks.*

The Criteria for an Ideal Deceased Kidney Donor

- Normal renal function.
- Without hypertension requiring treatment; without diabetes mellitus.
- No malignancy other than a primary brain tumor or treated superficial skin cancer.
- No generalised viral or bacterial infection.
- Acceptable urinalysis; age between 6 and 50 years.
- Negative assays for syphilis, hepatitis, HIV, and human T-lymphoproliferative virus.



Fig. 1.691: Renal transplantation.

Three types of donors:

1. Living related donors.
2. Living nonrelated donors.
3. Cadaver donors.

Highest chances of success in any transplant (renal) is seen when the donor is the identical twin.

Compatibility should be checked by tissue typing, i.e. ABO blood group system and major histocompatibility complex.

Evaluation of living donor:

- Tissue typing, ABO, MHC typing.
- Renal function—blood urea, serum creatinine.
- IVP.
- Selective renal angiogram. Single vessel is better.
- HIV/hepatitis evaluation.

Usually *left kidney* is taken for *transplantation* because of *long left renal vein.* It is placed in right iliac fossa with ureter connected to the urinary bladder; renal artery to internal iliac artery (end-to-end); renal vein to external iliac vein (end-to-side). Renal artery (end) to external iliac artery (side) through Carrel stitch is also used for arterial continuity.



Fig. 1.692: Another method of getting arterial perfusion of the transplanted kidney by suturing (*Carrel stitch*) external iliac artery to renal artery side-to-end.

Technique

Before the removal of kidney, the donor receives IV mannitol to prevent kidney ischaemia, diuretics and IV heparin. After removal of donor kidney, protamine sulphate is given to the donor. Removed donor kidney is perfused with cold perfusion fluid at 4°C and cold intravascular electrolytes. Solutions used to preserve the donor kidney are *Euro-Collins* solution or *University of Wisconsin (UW)* (both contains inert sugar which prevents swelling of cells). First renal vein, then renal artery and at the end ureter is anastomosed.

Azathioprine, cyclosporine and prednisolone should be started 3 days prior to surgery. Diuretics and mannitol should be continued as required.

Bilateral nephrectomy in recipient is required only in:

- Polycystic kidney disease.
- Haematuria.
- Severe hypertension.

Kidney will stand cold ischaemia for 72 hours.

Note: Overall survival is 90% in one year and 80% in five years.

Postoperative Management

- Immunosuppression: By cyclosporine, azathioprine, prednisolone, antithymocytic globulin and antilymphocytic serum.
- Proper fluid balance has to be taken care of.

Complications

- Acute tubular necrosis.
- Rejection (Rejection is identified by radioisotope study and percutaneous kidney biopsy). Chronic rejection is the common cause of graft failure.
- Obstruction of the collecting system.
- Infection.
- Urine leakage—5%.
- Secondary haemorrhage.
- Renal infarction.
- Hazards of immunosuppression:
  - Infection by unusual organisms like cytomegalovirus, herpes, *Pneumocystis carinii*, varicella and other bacterial infections, candidial infection.
  - Changes in the cellular component of blood.
  - Uncommon malignancies of CNS, skin.
  - Nephrotoxicity, GIT bleeding and perforation.
  - Hirsutism, delayed wound healing, cataract formation.
  - Renal artery stenosis—10%.
  - Renal vein thrombosis—5%.
  - Lymphocele.

IMMUNOSUPPRESSIVE AGENTS

Induction Therapy

- It is used *immediately* after transplantation (up to 3 weeks).
- *Antilymphocytic globulin (ALG)*—human lymphocytes are injected into rabbit/horse to develop antisera—ALG. It acts

If there were no obstacles, there would have been no achievements.

against T cells. It inhibits cell mediated immunity, allograft rejection, graft versus host reaction. It is used in transplantation of kidney, pancreas, heart, small bowel. Anaphylaxis, anaemia, thrombocytopenia, allergy (*serum sickness*) are the reactions. Rabbit serum is better than horse serum in terms of preventing the graft rejection (acute). Rabbit serum has antibodies against CD2,3,48,11a,18,25; HLADR, HLA class I.

- *Monoclonal antibody*—OKT3 (*1975 by Kohler, Milstein – got Nobel prize*) is developed by hybridoma technique, is a monoclonal antibody which acts / blocks at TCR complex (T cell receptor complex CD3) affecting the function of native T cell and cell mediated immunity. Within 60 minutes of IV injection of OKT3 it blocks T cell function removing the circulating T cells. Problem with OKT3 is its immune reactions. So often it is combined with steroid or indomethacin. It can cause acute *cytokine release syndrome*.
- *Interleukin 2 receptor (IL2 R) inhibitors*—α chain of IL 2 R is related to activated T cells. Basiliximab (chimeric) and daclizumab (human) are two anti-CD25 monoclonal antibodies which bind with α chain of IL 2R. These drugs are well tolerated through a peripheral IV line; stops acute rejection; with less risk of infection and malignancy. It does not cause serum sickness or cytokine release syndrome. But all alone its effects are inadequate and so it should be used only in concomitant with other immunosuppressants.
- *Rituximab* is an anti-CD20 monoclonal antibody as a depleting agent on B cell. It is used to control humoral mediated rejections. It is used in heart transplantation.
- *Alemtuzumab*—an anti-CD52 human monoclonal antibody which is expressed in B cell, T cell, monocyte, macrophage. It causes prolonged lymphocyte depletion for 6 months. It is used along with tacrolimus in kidney transplantation. Steroid can be spared while using his. This drug is also used in lymphoma, multiple sclerosis and rheumatoid arthritis.
- *IVIG* (intravenous immunoglobulin) derived from pooled plasma neutralises the circulating autoantibodies, blocks the T cell cytokines, lymphocyte proliferation and apoptosis.

Maintenance Therapy

All transplant patients require maintenance therapy for prolonged period. Different drugs are used. Steroid and azathioprine are old drugs commonly used.

- ***Prednisolone:*** It inhibits cytokines, binding of IL 2 to receptors, blocks macrophage migration, and inhibits delayed hypersensitivity reaction. But it causes Cushing's syndrome, hypertension, peptic ulcer, cataract, diabetes, osteoporosis, muscle wasting. Often methyprednisolone may be used.
- **Antiproliferating agents:** They inhibit differentiation and division of lymphocytes by blocking the purine, pyrimidine and folic acid metabolism as a structural analogue.
  - *Azathioprine* is a purine analogue containing 6 mercaptopurine with a labile sulfhydryl chain. Conversion of inosine nucleotide to adenosine and guanosine is blocked. Drug inhibits both humoral and cell mediated immunity. Toxic effects are—bone marrow suppression, hepatotoxicity.
  - *Mycophenolate mofetil* (MMF): It inhibits inosine monophosphate dehydrogenase of purine metabolism blocking lymphocyte proliferation. Dose is 2 grams/day. It is now more commonly used than azathioprine. Diarrhoea and bone marrow suppression are the side effects.
  - *Leflunomide*: It blocks pyrimidine synthesis in lymphocytes by inhibiting dihydroorotate enzyme. This drug is used in rheumatoid arthritis. FK 778 is its analogue which is under trial in renal transplant.
- **T cell directed immunosuppressants:**
  - *Cyclosporine* (Borel, 1972) is extracted from fungus *Tolypocladium inflatum*. It is selective inhibitor of TCR mediated activation suppressing T cells. It inhibits formation of mature CD4 and CD8 T cells in thymus. It contains 11 amino acids with molecular weight 1202. It is a very good immunosuppressant. But it *does not* cause myelosuppression. It is metabolised in the liver by cytochrome P-450. *Side/toxic effects* are—*nephrotoxicity*, hypertension, hirsuitism, gingival hyperplasia, hyperkalaemia, neurotoxicity, tremor, hepatotoxicity, risk if infection (CMV, *candida*, *Pneumocystis carinii*, secondary infections) and malignancy (lymphoma, skin and CNS). IV dose given initially is 4 mg/kg in 500 ml of saline; later changed to oral therapy as 12 mg/kg daily; after few weeks dose is tapered to 5 mg/kg/day. Regular serum cyclosporine estimation twice weekly with estimation of haematocrit, blood urea and serum creatinine is needed.
  - *Tacrolimus* (FK 506, 1984, Japan) is derived from fungus *Streptomyces tsukubaensis*. It is macrocyclic lactone (MW 822) causes similar effect like cyclosporine. Drug binds with intracellular binding protein immunophilin forming complexes which block the phosphatase activity of calcineurium so that inhibits IL 2 production. It is used in liver transplant, in acute rejection of kidney. Side effects are similar as cyclosporine but will not cause hirsuitism and gingival hypertrophy. It causes alopecia and diabetes.
  - *Sirolimus* (rapamycin) is a macrolide antibiotic which inhibits signal transduction from IL2 R to nucleus. It inhibits allograft rejection. It is used along with other immunosuppressants like cyclosporine. It causes anaemia, thrombocytopenia and proteinuria. Nephrotoxicity is less with sirolimus.
- **Costimulation blockage agent** like *belatacept* which is a fusion protein of extracellular part of CTLA4. It s a good immunosuppressant used monthly or bimonthly.

Risks Related to Immunosuppression

They are mainly infection and malignancy. *Individual drug related toxicity* also can occur.

Infection

- Opportunistic infections are common with immunosuppression. Cytomegalovirus (CMV) infection is common causing pneumonia, hepatitis, pancreatitis, GI problems. *Pneumocystis carinii* infection is also common.

- Trimethoprim, sulfamethoxazole, acyclocvir, ganciclovir, valganciclovir, clotrimazole, pneumococcal vaccine, hepatitis B vaccine, pentamidine nebulizer are different drugs used to prevent sepsis.
- BK virus associated nephropathy is controlled by cidofovir, IV immunoglobulin.

Malignancy

- Malignancy potentiality increases by 10 times.
- Skin cancers and carcinoma cervix are common.
- Virus mediated tumours like carcinoma cervix (HPV); hepatoma (Hepatitis B and C); Kaposi's sarcoma (herpes virus 8); lymphoma (EBV) are common. EBV related lymphoma is post-transplant lymphoproliferative disorder (PTLDs). Rituximab, anti-CD20 monoclonal antibody reduces B cells is effective in these patients. Hyper CMS IG is used as prophylaxis in high-risk groups.

LIVER TRANSPLANTATION

> *An ideal treatment for several kinds of liver disease would be removal of the diseased organ and orthotopic replacement with a hepatic homograft.*
>
> —**TE Starzl, TL Marchioro, KN von Kaulla,** et al, 1963

Indications

- Primary biliary atresia, metabolic liver disease.
- Cirrhosis.
- Malignant disease of the liver.

Children respond better for liver transplantation. Tissue typing and cross-matching are not that necessary and do not influence the results.

If the transplantation is done at the same site after doing hepatectomy, it is called as ***orthotopic liver transplantation***. If it is placed in a different site it is called as ***ectopic*** or ***heterotopic liver transplantation***. Success rate in liver transplantation is better.

Liver transplantation is the choice for end stage liver disease. Liver transplant is an accepted and effective treatment. Many tumours can be treated by transplantation. Cirrhosis, hepatitis, sclerosing cholangitis, biliary atresia, tumours are indications.

CTP (Child Turcote Pugh) scoring system (ascites, encephalopathy, bilirubin, albumin, PT- INR); *Model for end stage liver disease (MELD score)* consists of total bilirubin, INR, creatinine; *Paediatric end stage liver disease scoring* (PELD); are different scorings used to assess the patients.

- *MELD Score* $= 0.957 \times \text{Log}_e(\text{creatinine mg/dL}) + 0.\ 378 \times \text{Log}_e(\text{bilirubin mg/dL}) + 1.120 \times \text{Log}_e\ (\text{INR}) + 0.643$

Contraindications for liver transplantation

- Active sepsis, SBP and HIV.
- Extrahepatic malignancies.
- Large hepatocellular carcinoma and cholangiocarcinoma.
- Unfit for surgery - severely advanced cardiopulmonary disease.
- Active alcohol or substance abuse.
- Inability to comply with immunosuppression protocols because of psychosocial situations.

Donor criteria

They are related to donor liver function, hepatitis screening, history of consumption of alcohol and toxic substances. Marginal donor and expanded donor criteria are in use in places due to very high demand for donor for transplantation. ABO compatibility is important. HLA matching is not necessary unlike in renal transplantation.

Donor operation

It is by a midline incision from suprasternal notch to pubic symphysis. Initially dissection is done with a beating heart; but later with a cold preservation into aorta and portal vein and local ice application. UW solution extends cold ischaemic time for 24 hours but usually within 10 hours transplantation is

DDLT (deceased donor liver transplantation) donor	***LDLT (living donor liver transplantation) donor***
• 50 years or younger	• Young, Non-obese, tall
• No hepatobiliary disease	• No infection, malignancy, No fatty liver
• Hemodynamic and respiratory stability (systolic blood pressure >100 mmHg, and central venous pressure >5 cm/H_2O); an acceptable PaO_2 and haemoglobin level	• Enough liver to donate
• No severe abdominal trauma, systemic infection, or cancer	• Enough residual liver
• Normal kidneys—diuresis greater than 50 mL/h and normal creatinine;and finally, a dopamine requirement less than 10 µg/kg/min	• Suitable anatomy of liver
• Simple technically	• Technically complex procedure
• Recipient complication is low (of bile duct)	• Recipient complication is higher
• Graft quality is average	• Graft quality is good
• Donor's complication—nil	• Donor's complication—25% morbidity; 0.4% mortality

Success is never final and failure is never fatal; its courage that counts.

done. IVC segment is removed with hepatic veins. Portal vein is transected. Celiac artery with branches along with hepatic artery is dissected and transected at celiac artery origin. Bile duct is transected.

- Remnant liver—≥30% of the original liver volume with complete venous drainage is safe for donor survival.

Recipient Operation

Bowel preparation, prophylactic antibiotics, administrative immunosuppressive agents are needed before surgery. Bilateral subcostal incision is used with midline upward extension. Falciform ligament, left lateral ligaments, hepatogastric and hepatoduodenal ligaments are divided. Right and left branches of hepatic arteries are ligated. CBD and cystic ducts are divided with ligatures. Portal vein is dissected. Infra and suprahepatic vena cava are exposed. Portal vein and suprahepatic vena cava are clamped. Venovenous bypass between portal and femoral veins and internal jugular vein is created with a flow of blood through it more than 2.5 ml/minute. Warming circuits and ultrafiltration is needed. Suprahepatic vena caval cuff is created at the opening of the right, middle and left hepatic veins. Donor IVC is sutured to recipient IVC first above and then below as end-to-end. Recipient IVC can be preserved entirely and donor IVC is sutured to recipient IVC as end-to-side. Preservative solution is passed. Portal vein is sutured. Reperfusion injury can occur at this stage with hyperkalaemia and acidosis. Arterial reconstruction is done between donor celiac artery to recipient gastroduodenal artery. Bile ducts are sutured as end-to-end with or without T tube. Often choledochojejunostomy is also done.

Graft should be:

- 40% of the estimated standard liver volume.
- 0.8 to 1% of the body weight of the recipient is necessary for the recipient recovery.

Segmental/Lobar/Split/Living Donor Liver Transplantation

It is newer beginning but becoming preferred one. It is based on segmental anatomy and liver regeneration capacity. Minimum liver mass required is more than 1% of graft to body weight ratio. Right lobe is better. It is basically used in children; but useful in adults also. MELD score in donor should be less than 20 for living donor transplantation. Regeneration occurs very significantly in recipients in first 2 weeks reaching standard in 1 month. Regeneration is slow in living donor liver in 1 year. Graft to standard liver ratio should be more than 40%. Function of liver in living donor should be optimum. Proper imaging of the donor for entire anatomy including vasculature is important. Individual branches of portal vein, hepatic artery and bile duct are dissected and isolated. Liver is carefully separated from IVC; small branches of hepatic vein are ligated. Main hepatic vein is isolated; liver parenchyma is dissected with finger/Kelly fracture technique. After completion of parenchymal division, vessels are transected; dissected liver is perfused with cold preservative solution. Diseased liver of the recipient is removed completely. Graft is anastomosed in usual manner hepatic vein, portal vein, hepatic artery, bile duct. Living donor transplantation has got higher chances of morbidity, complications compared to cadaveric transplantation.

Postoperative Management

- Antirejection drugs to be given.
- Liver shows low immunogenicity and high regeneration capacity causing long-term outcome. Initially cyclosporine or tacrolimus with MMF or azathioprine with prednisolone is given. ICU care is needed.
- Electrolyte and fluid management, sepsis management, prevention of encephalopathy, observation for complications are important.

Complications and Problems of Liver Transplantation

- *Bleeding* on table and postoperatively can occur especially when recipient liver is cirrhotic. FFP, platelet and blood are needed. Reexploration is needed if bleeding persists postoperatively.
- *Hepatic artery thrombosis* is the common vascular complication leading into graft failure, CBD necrosis and anastomotic dehiscence.
- *Immediate graft failure* as primary nonfunctional graft can occur (5% of liver grafts).
- *Bile leak* due to CBD ischaemia which can be identified by HIDA scan, ERCP, revision anastomosis is needed.
- *Infection* is common especially enterococci, staphylococci, gram negative organisms, candida, aspergillus, etc. Antibiotic and antifungal therapy is needed.
- *Acute rejection* (30%) of T cell mediated is seen within 10 days commonly but can occur up to 6 months. Liver biopsy confirms the rejection. Higher steroid therapy, polyclonal anti-T cell antibodies are used.
- *Chronic rejection* is seen after 6 months; appears gradually with liver cell dysfunction and hyperbilirubinaemia. Liver biopsy shows very few numbered biliary radicles—*vanishing bile duct syndrome*. It is due to humoral immunity. It is difficult to control; eventually needs retransplantation.
- *Recurrence* of the earlier disease to the transplanted liver like hepatitis, biliary sclerosis, sclerosing cholangitis. Hepatitis can be controlled by lamivudine (antiviral DNA polymerase for HBV), interferon α, ribavirin for HCV.
- *Complications of immunosuppressive drugs* like hypertension, hyperglycaemia, hyperlipidaemia, osteoporosis, malignancy, infection, bone marrow suppression are often difficult to manage.

Survival

- 5-year survival is 70% in adults and 80% in children.
- It depends on age, general condition, earlier disease, associated problems, MELD scoring.
- The risk of rejection is highest (40%) during the first 3-6 months after transplantation and decreases significantly thereafter.

BONE MARROW TRANSPLANTATION

Indications

- Leukaemias.
- Aplastic anaemias.
- Immune deficiencies, etc.

Recipients are initially treated with total body irradiation. As bone marrow is an active immune system, *proper tissue typing* is essential. *Infant bone marrow* is better marrow as a *donor*. Marrow aspirated from donor's bone is transplanted by *intravenous injection* to the recipient.

Immunosuppression with cyclosporin-A is always needed. It will take few weeks to show the response.

Problems

1. Graft rejection.
2. *Graft-Versus-Host* disease (GVH) is more dangerous.

PANCREATIC TRANSPLANTATION

- It is used in diabetic patients, taken from cadaver donor to replace insulin.
- It can be combined with kidney transplantation to patients who have diabetes with end stage kidney disease.
- Donor criteria are individuals without pancreatitis.
- Entire pancreas with duodenum (Lillehei) or part of the pancreas (body and tail of the pancreas) can be transplanted.
- It is placed in the ***right iliac fossa*** with anastomosis done between portal vein and iliac vein, duodenum fixed to bladder.
- Graft take up is 60-70%.

Complications

Graft pancreatitis, pancreatic leak, bleeding, urinary infections like cystitis, failure.



Fig. 1.693: Pancreatic transplantation with duodenum and small bowel to achieve adequate exocrine function. Exocrine function is achieved immediately; endocrine (insulin) function is achieved after few days.



Fig. 1.694: Pancreatic transplantation.

Isolated Pancreatic Islet Transplantation

Islets of Langerhans are obtained by mechanical disruption of pancreas by injecting collagenase into the pancreatic duct. Tissue disrupted is collected and purified by density gradient centrifugation. These islet cells are injected into the liver through portal vein. Islet cell rejection is prevented by covering them with semipermeable membrane which prevents antibodies reaching islet cells but allowing insulin to get secreted. By this method animal pancreatic islet cells transplantation is also under trial.

SMALL BOWEL TRANSPLANTATION

- Indication is short bowel syndrome following massive resection, atresia, necrotising enteritis, Crohn's disease.
- Bowel anastomosis with a stoma (ileostomy) is usual method.
- As small bowel is rich in lymphoid tissue, graft versus host reaction is a major problem. So graft take up is poor.
- It is an immunological challenge even though technically easier.

Graft rejection

- **Hyperacute** rejection is due to antibody reaction which occurs within minutes of vascularisation of the graft
- **Acute** rejection results due to cell mediated immunity, occurring in a few days to first 3 months of transplant. It responds well to steroids and immunosuppressants
- **Chronic rejection** occurs in 12 months after transplant, is not very common. It is due to late vasculitis. When it occurs, responds very poorly to steroids or other drugs. It is common type

DIALYSIS

It is technique for the removal of waste product of metabolism, normalisation of plasma electrolytes and removal of plasma water.

Types

- Peritoneal dialysis.
- Haemodialysis.

Peritoneal Dialysis

Indications

- Acute renal failure until renal function recovers.
- Chronic renal failure until long term dialysis is instituted.

Contraindications

- Abdominal surgery.
- Hypercatabolic states.
- Infection.
- Pre-existing malignancy.

Insertion of catheter

A rigid plastic catheter is inserted through the abdominal wall into the peritoneal cavity using a trocar through a small cut made in the skin under L/A. Catheter is bound to abdomen.

Dialysis is done using sterile dialysate solution instilled into and drained out of abdomen.

Complications

- Leakage
- Pain—short lasting, mild
- Peritonitis
- Membrane failure
- Hernia

Continuous ambulatory peritoneal dialysis (CAPD) is the preferred method of dialysis in some centre.

Haemodialysis

Indications

- Acute renal failure.
- Chronic renal failure.
- Acidosis.
- Electrolyte disturbance.
- Intoxication.
- Uraemia (pericarditis and polyneuropathy due to uraemia are absolute indications).

Haemodialysis requires access to circulation which is achieved by creating a fistula between the radial artery and the cephalic vein at the wrist *(Cimino fistula).* Here dialysis occurs in a dialysing machine across a semipermeable membrane (usually cellulose membrane).

Complications

- Access site—arterial and venous stenosis, thrombosis, infection.
- Hypotension.
- Dyspnoea.
- Bleeding (due to dysfunctional platelets due to uraemia and due to heparin use).
- Disequilibrium syndrome.

Even though repeated dialysis (in CRF, at least twice a week is needed) helps, patient needs repeated blood transfusions, which will lead into haemochromatosis/iron overload. Patient should be given erythropoietin injection 3,000 units twice weekly to prevent repeated blood transfusions. But it is expensive. Transplantation is the best answer eventually, in all these individuals.



Fig. 1.695: Patient with CRF undergoing haemodialysis using a dialysis unit.



Figs 1.696A and B: Arteriovenous fistula between radial artery and cephalic vein at wrist is done to attain increased venous engorgement and arterialisation so as to achieve rapid blood flow which is necessary for haemodialysis. Patient with chronic renal failure who requires regular haemodialysis needs this.

CIMINO FISTULA (CIMINO-BRESCIA)

It is an arteriovenous fistula created for *haemodialysis.* Usually at wrist, radial artery is anastomosed to cephalic vein side-to-side and a created good fistula shows continuous thrill and bruit, with increased venous engorgement along with hyperdynamic circulation. At the ankle, often fistula is created between posterior tibial artery and saphenous vein; in the thigh between femoral artery and long saphenous vein. Distal gangrene is not common.

Complications

Infection, bleeding, hyperdynamic circulation.



Figs 1.697A to E: Creation of Cimino AV fistula using radial artery and cephalic vein (magnifying operating loupe is used during anastomosis using 6 zero polypropylene) (*Courtesy:* Ashok Pandit, MCh, Urologist).

I am a great believer in luck and I find the harder I work, the more I have of it.

W. Stings and Bites

CHAPTER OUTLINE

- Snake Bite
- Spider Bite
- Bee Bite
- Mammalian Bite

SNAKE BITE

Snakes belong to Crotalidae, Elapidae and Viperidae family. Common poisonous snakes are cobra, krait and viper.

Common snakes are cobra, Russell's viper, saw scaled viper, pit viper, krait.

It causes renal failure, pulmonary oedema, cardiac complications and neurological problems.

Clinical Features

Local

- Burning pain, oedema and erythema.
- Swelling, echymoses and haemorrhagic bullae.
- Tissue necrosis, ulceration and gangrene.

Systemic

- Weakness, perioral paraesthesia, muscle twitching.
- Shock.
- Pulmonary oedema.
- Renal failure.
- Neurological manifestations.
- Bleeding tendency.

Vipers affect multiple organs and soft tissues. Cobra and coral snakes are neurotoxic.

Investigations

- Blood count.
- Coagulation studies like bleeding time, clotting time and prothrombin time.
- Blood urea and serum creatinine.
- Serum electrolytes.
- Creatine phosphokinase [CPK].
- Urine analyis for RBCs, albumin, myoglobin.
- PO_2 and PCO_2 assessment.

Management

First Aid

- Reassurance.
- Immobilisation.
- The site has to be incised and cleaned.
- Tourniquet to *occlude lymphatics* only but not venous or arterial circulation.
- The snake has to be identified.
- The patient must be transferred to proper medical centre as early as possible.
- The bite wound is identified and assessed.
- It is thoroughly cleaned with debridement.
- *Polyvalent antisnake venom* (against cobra, krait, vipers) should be given. It should be given earliest within 4-24 hours. Dose is 20-150 ml depending on the type, severity and age of the individual. It is dissolved in normal saline and given as IV infusion in 500 ml saline with 20 drops/minute as flow rate. If the snake has been identified monovalent serum is better and more potent.
- Tetanus toxoid.
- IV fluids, blood transfusion and plasma.
- Antibiotics.
- Urine output measurement.
- Monitoring by regular checking of blood urea, serum creatinine and bleeding and clotting time.
- In cobra bite, there is neuromuscular blockade and paralysis occurs. So *neostigmine* should be given 0.5 mg IV every half hourly and later repeated as required. It is given along with 0.6 mg of atropine.
- In viper bite DIC is common. So heparin is given as 10,000 to 15,000 units loading dose and later 5,000 units as maintenance dose 8th hourly.
- Human fibrinogen, whenever required.

Complications of Snake Bite

- Cellulitis and gangrene of the part.
- Deep venous thrombosis [DVT].
- Pancytopenia.
- DIC and haemorrhage.
- Neurological complications.
- Septicaemia.
- Renal failure.
- Marjolin's ulcer.

SPIDER BITE

Types

1. *Black Widow Spider Bite*
    - It causes neurotoxicity.
    - It causes muscle spasms, pain and abdominal cramp and rigidity.
    - Hypertension, tachycardia and diaphoresis are the other features.
    - Its effects last for 2-3 days.


Snake venom secreted from saliva of the snake parotid
Peptides
Enzymes
Other chemicals
Damage endothelium of the vessel
Protease 1-amino acid Oxidases
Hyaluronidase
Phospholipase A_2
Alters coagulation, platelet function, fibrinolysis, vascular integrity changes, DIC
Oedema and hypovolaemic shock
Tissue necrosis
Spread of venom through tissues
Damage RBCs and muscle cells *(Myotoxic)*
Haemorrhagic episodes

- Cleaning the wound, antibiotics, antihistamines, specific antivenins are the line of treatment.

2. *Brown Spider Bite*
   - It releases sphingomyelinase-D which causes necrosis of the skin and haemolysis.
   - Local effects include skin rash, blister formation, necrosis of the skin and extensive ulceration.
   - Systemic effects are anaphylaxis, arthralgia, thrombocytopenia, haemolysis and renal failure.
   - Often it can be life-threatening especially in children and elderly.
   - The effects last for 2-3 weeks.
   - Wound debridement, antibiotics, antihistamines, steroid therapy, antivenins and management of systemic complication.

BEE BITE

Honey bee has got barbed stinger with two lancets. These lancets get attached to human skin to release the venom. Bee dies after bite.

Wasps: Yellow jacket wasps are more aggressive.

Bee venom contains dopamine, histamine, neurotoxin and toxic peptides.

Clinical Features and Management

- Allergic reactions.
- Anaphylaxis.
- Pain in the local region, oedema, pruritus, flushing.
- Hypotension, laryngeal oedema, bronchospasm.
- Muscle spasm, convulsions.
- Renal failure in severe cases.
- Soda bicarbonate is used to neutralise the bee venom.
- Antibiotics and antihistamines.

MAMMALIAN BITE

- It includes human bites also.
- Infection rate is more in mammalian bites.
- Proper wound toileting is very important.
- Within 12 hours, incised wound is closed primarily.
- All lacerated wounds and wound which is seen after 12 hours is left open. Wound is closed secondarily.
- Antibiotics are must in all mammalian bites.
- Human bite is very dangerous bite.

Awareness of change in important and equally acceptance of it also.

X. Pain

CHAPTER OUTLINE

- Gate Control Theory

Pain is a subjective one and is difficult to assess and quantify. Pain perception varies from person-to-person and from time-to-time.

- It can be physical or mental
- It can be localised or diffused
- It can be acute or chronic
- It can be intermittent or persistent
- It can be mild or severe

Pain Pathway

Pain receptors in the skin
↓
Neurotransmitters of pain like substance P or peptides are activated
↓
Sensory nerves
↓
Posterior horn of spinal cord
↓
Spinothalamic tract
↓
Thalamus
↓
Cerebrum
↓
Pain perception

GATE CONTROL THEORY

Gate control system is located at the junction of first and second neuron. Large diameter 'A' fibre is stimulated by temperature and touch. Fine 'C ' fibre is stimulated by pain. If 'A' fibre once gets stimulated, blocks the gate mechanism, then pain from 'C' fibre cannot pass through the gate to reach the brain for perception.

Pain modulators like endorphins and opioid peptides in brain and spinal cord inhibit the release of substance 'P'.

Causes of Pain

- Inflammatory causes due to any infection or infestations.
- Hypoxia due to poor blood supply like in myocardial infarction, peripheral vascular disease.
- Trauma.
- Obstruction like intestinal obstruction.
- Colicky pain like ureteric, biliary, intestinal.
- Compression over nerve roots like in inter vertebral disc prolapse.
- Advanced malignancies cause severe distressing pain, which requires proper pain control.
- Ulcers, perforation, peritonitis, abscess formation are all other causes.

Clinical Assessment of Pain

- Its severity, nature, cause should be assessed.
- Cause should be thoroughly analysed by doing all investigations like haematocrit, sinology, CT scan, culture of the fluid like pus, blood.

Pain is a most common symptom which patient complains to a clinician. Latin word *'poena'* means penalty/punishment. Pain is the one patient feels; tenderness (sign) is one surgeon/clinician elicits.

Specific Points in History in Relation to Pain to be Asked are:

- ***Original site of pain*** is very important. In acute appendicitis original site of pain is in umbilicus; but later it is referred to right iliac fossa. Shift of pain towards other site.
- ***Time and mode of onset of pain***—it is sudden onset and rapidly progressive in acute appendicitis; it is of insidious onset and of long duration with episodic nature in chronic peptic ulcer.
- ***Type/nature of pain***—superficial/deep; dull ache or sharp severe/pricking/bursting/vague aching (continuous mild pain), throbbing, scalding (burning sensation particularly felt during urination in cystitis, pyelonephritis, urethritis), pins and needles pricking sensation in peripheral nerve injury or irritation, shooting pain (seen in intervertebral disc prolapse and sciatica—pain shoots along the course of nerve), stabbing (sudden, severe, sharp, episodic—seen in perforated duodenal ulcer), distension pain (a feeling of restricted or distended like in paralytic ileus or intestinal obstruction), colicky pain is due to muscular contraction in a hollow tube in an attempt to obviate the obstruction by forcing the content out—gripping, episodic pain with vomiting and sweating (seen in intestinal colic, ureteric colic of stone, biliary colic of stone), twisting pain of bowel volvulus/twisted ovarian cyst/torsion testis, constricting pain around the chest by angina, etc.

- ***Severity of the pain:*** In acute conditions like peritonitis and abscess pain will be severe compared to chronic one.
- ***Progression of pain:*** It may be persistent and progressive; or initially mild gradually increases, later gradually subsides; fluctuation in intensity whether increases and decreases in intensity at regular intervals; quickly reaches maximum and remains like that.
- Duration of Pain
- ***Periodicity of pain:*** Pain appears, persists for few weeks and then disappears for few weeks; again reappear. Such periodicity is often observed in chronic peptic ulcer; trigeminal neuralgia.
- ***Precipitating/aggravating factors:*** Abdominal pain may get worsened by taking food like in gastric ulcer. Pain due to appendicitis, ureteric stone aggravates by change of position, walking, jolting. Pain of urinary bladder stone aggravates in standing position. In reflux oesophagitis pain increases while scooping. Pain in pancreatitis increases while lying down. Pain in intervertebral disc prolapse aggravates by lifting the weight.
- ***Relieving factors of pain:*** Pain reduce by certain methods and patient uses that method to relieve the pain. Hunger pain of early morning in duodenal ulcer is relieved by taking food. Pain of pancreatitis is relieved in sitting and bending forward. Propped up position relieves pain of reflux oesophagitis. In acute peritonitis, pain reduces temporarily by lying still.
- ***Associated symptoms***: Acute pain may be associated with pallor, sweating and vomiting. Migraine pain with vomiting and visual disturbances; intestinal/ureteric colic with sweating, vomiting and cold periphery; acute pyelonephritis and urinary infections with chills/rigors and fever; ureteric colic with haematuria; biliary colic with jaundice and pale stool are other examples of such association.
- ***Time of occurrence of pain*** is often important in diagnosing the condition. In duodenal ulcer, hunger pain occurring in early morning or later evening is typical. Migraine occurs in early morning; frontal sinusitis induced headache occurs a few hours after getting up.
- ***Pain may move from one place to other:*** *Radiation of pain* It is extension of pain from original site to another site with persisting of pain at original site. This radiating pain is of same character of original site. Penetration of duodenal ulcer posteriorly causes pain both in epigastrium and back—is an example. Pain of pancreatitis radiates to back. *Referred pain:* Pain is not felt at the site of the disease but felt at distant site. Diaphragmatic irritation causes referred pain at the tip of shoulder through same segmental supply of diaphragm (phrenic nerve C4, C5) and shoulder (cutaneous supply C4, C5). Hip joint pathology may cause referred pain in knee joint—through articular branches of femoral, obturator and sciatic nerves. Other *examples*—referred ear pain from carcinoma tongue through lingual and auriculotemporal nerve; referred pain in the epigastrium from the heart; referred pain in the abdomen from pleura; referred pain over the testis from the ureter. *Shifting/migration of pain:* Origin of pain is one site; later pain shifts to another site and pain at original site disappears. Pain when begins in viscera, it is felt at the same somatic segmental area in the body; but once parietal layer is involved by inflammation/pathology pain is felt at the anatomical site. Example is pain of acute appendicitis where original visceral pain is at the umbilicus (T9 and T10 segments supply both umbilicus and appendix) shifts later to right iliac fossa when once the parietal peritoneum of that area is inflamed.

Types of pain:

- *Superficial pain*: It is sharp usually localised pain, due to irritation of peripheral nerve endings in superficial tissue by chemical/mechanical/thermal/electrical injury. *Segmental pain:* It occurs due to irritation of particular nerve trunk/root; located in particular dermatome of the body supplied by the sensory nerve trunk or root.
- *Deep pain:* It is due to irritation of deeper structures like muscles/tendons/bones/joints/viscera. It is vague and diffuse when compared to superficial pain. It is often referred to common segmental areas of representation. Often spasm of skeletal muscle of same spinal cord segment can occur.
- *Psychogenic pain:* It may be functional/emotional/hysterical.
- *Other pain:* like due to thalamic/spinothalamic diseases/ *causalgia* (intense burning pain along the distribution of the partially.

Grading of pain is done using pain scale. It is compared to a 10 cm line numbered 0 to 10. This is called as *visual analogue scale* (VAS). Minimum is 0 means no pain. 10 is the worst excruciating pain. 2 is mild; 4 is discomforting; 6 is distressing; 8 is intense.

Reasons to control postoperative pain/acute pain

- Uncontrolled pain causes tachycardia, hypertension and vasoconstriction
- Abdominal (upper abdominal mainly) and thoracic wound pain restricts the respiration causing tachypnoea, altered respiration, coughing, chest infection, pneumonia
- Persisting pain causes restricted movements, deep venous thrombosis and its problems, bed sores
- Pain delays the recovery and also causes psychological trauma to the patient

Management of Pain

- Correct the cause like removal of renal stone, cholecystectomy for gallstones.
- Analgesics.
- Surgical removal of tumour.
- Injection of phenol or alcohol.
- Electric stimulation, massaging, infrared therapy, wax bath.
- Proper physiotherapy.
- Hormone therapy.
- Injection to ganglion like in trigeminal neuralgia.

Acute pain	*Drugs/opioids/epidural anaesthesia/drug infusion*
Chronic pain due to malignancy	First level—simple analgesics (aspirin, paracetamol, NSAIDs, tricyclic antidepressants)
	Second level—intermediate opioids codeine, tramadol, dextropropoxyphene
	Third level—strong opioids like oral morphine, intravenous morphine, subcutaneous diamorphine, epidural diamorphine. Analgesic infusion is also useful. Neurolytics are used whenever there is limited life-expectancy. Other methods are - Subcostal phenol injection for rib secondaries/celiac plexus block using alcohol/intrathecal hyperbaric phenol/percutaneous anterolateral cordotomy/pituitary ablation/hormone ablation/ palliative radiotherapy/steroids/flecainide therapy
Chronic pain in benign disease	Local anaesthetics/steroid injections/nerve stimulation like acupuncture/nerve decompression/pain due to sympathetic overactivity is corrected by—IV pentolamine (alpha adrenergic block), stellate ganglion block, block using guanethidine, percutaneous chemical lumbar sympathectomy using phenol. Other methods for chronic pain are—paracetamol/NSAIDs/antidepressants/opioids/carbamazepine/ neuroablative surgeries

- Chemotherapy for malignancies.
- Radiotherapy.
- Sympathectomy for vascular diseases, causalgia.
- Cordotomy for severe pain in case of advanced tumours.
- Mental relaxation.
- Attending pain clinic.
- Continuous epidural anaesthesia/analgesia using opioids.
- *Patient controlled analgesia* (PCA) is injecting opioids through epidural route or intravenous route by patient himself after training him.
- Intravenous infusions of the analgesia.

Pain may be:

- Acute pain.
- Chronic pain due to malignancy.
- Chronic pain due to benign disease.

Drugs for Pain

Drugs can be given orally, intramuscularly, few intravenously, intrathecally, per rectally as suppositories, sublingually.

Narcotic Analgesics

- Morphine 10-15 mg. Very useful in intractable pain. It can cause nausea, constipation, and respiratory depression. Its action is neutralised by naloxone.
- Pethidine 50-100 mg IM.
- Diamorphine 5-10 mg. It is used only in intractable pain.
- Pentazocine 30-60 mg.
- Dihydrocodeine.
- Codeine phosphate is commonly used after intra-cranial surgery. It should not be given intravenously as it may precipitate severe hypotension. Codeine also causes constipation.
- Bupremorphine.

Non-narcotic Drugs

- Aspirin.
- Ibuprofen.
- Naproxen.
- All these NSAIDs cause gastric irritation and may risk the gastric bleeding. NSAIDs are non-specific cyclooxygenase inhibitors. So gastric protection and platelet function are lost. Rectal diclofenac as suppository is good analgesic.
- Paracetamol is effective analgesic and antipyretic agent. It is relatively less common to cause gastric bleeding.

***Note*:**
Specific COX2 inhibitors are contraindicated in ischaemic heart disease.

Other Drugs

- Anticonvulsants.
- Antidepressants, anxiolytics.
- Carbamazepine for neuralgia.

Chapter 2 Faciomaxillary Diseases

CHAPTER OUTLINE

- Diseases of the Palate
- Orthopantomogram
- Cleft Lip and Cleft Palate
- Maxillofacial Injuries
- Primary Care (Early Care) in Maxillofacial Injuries
- Fracture Middle Third Area
- Zygomatic Complex Fracture
- Fracture of the Mandible
- Dislocation of the Mandible
- Preauricular Sinus
- Jaw Tumours
- Epulis
- Ameloblastoma
- Dentigerous Cyst
- Dental Cyst
- Osteomyelitis of Jaw
- Alveolar Abscess
- Fibrous Dysplasia of Bone/Jaw
- Cherubism

DISEASES OF THE PALATE

- Cleft palate.
- *Torus palatinus*—a bony hard swelling in the centre of the hard palate.
- Nasopalatine cysts.
- *Epstein's pearls*—at the junction of soft and hard palates, in the midline, in infants due to retained developmental cell rests.
- Apical cyst or abscess.
- Minor salivary gland tumour—commonest site is palate.
- Maxillary tumour extending into the palate.
- Squamous cell carcinoma of the palate.
- Gummatous perforation in the middle of the palate seen in congenital syphilis.
- Perforation of the palate anywhere in carcinoma palate.

ORTHOPANTOMOGRAM (OPG)

It is a plain X-ray of the mandible which shows the entire mandible in a single plane. It is better than X-ray mandible lateral view as it highlights proper dentition, inner and outer plates of mandible and joints. It is like a rotational tomogram.

Indications

a. Jaw tumours—Adamantinoma, dental cyst, dentigerous cyst, osteoclastoma.
b. Osteomyelitis of the mandible.
c. Fracture mandible.
d. Carcinoma oral cavity to check *infiltration* into the mandible.



Figs 2.1A and B: Orthopantomogram is being taken and also picture showing OPG X-ray.



Fig. 2.2: OPG showing jaw tumour probably adamantinoma.

CLEFT LIP AND CLEFT PALATE

Development of Face

Face develops from median nasal process, lateral nasal process, maxillary process, mandibular arch, globular arch, olfactory pit and eye. Any change in the development or fusion of these arches leads to formation of different types of cleft lip or cleft palate.

Aetiology

- Familial—more common in cleft lip or combined cleft lip and palate (Risk is 1:25 live births).
- Protein and vitamin deficiency.
- Rubella infection.
- Radiation.
- Chromosomal abnormalities.
- Maternal epilepsy and drug intake during pregnancy (steroids/eptoin/diazepam).

Classification

I. *Cleft lip alone*: Unilateral.
Bilateral.
Median.
II. *Cleft of primary palate (in front of incisive foramen) only:*
  a. Complete—means absence of pre-maxilla.
  b. Incomplete—means rudimentary pre-maxilla.
    i. Unilateral.
    ii. Bilateral.
    iii. Median.
III. *Cleft of secondary palate (behind the incisive foramen) only:*
  a. Complete—nasal septum and vomer are separated from palatine process.
  b. Incomplete.
  c. Submucous.
  It can be - Cleft with soft palate involvement.
  - Cleft without soft palate involvement.
IV. *Cleft of both primary and secondary palates.*
V. *Cleft lip and cleft palate together.*

Defect is often associated with other congenital anomalies of cardiac, gastrointestinal, neurological system, *Pierre-Robin syndrome* (most commonly associated syndrome with features of isolated cleft palate, retrognathia, posteriorly displaced tongue), *Klippel-Feil syndrome*, *Stickler's syndrome* (eye, skeletal, muscular, cleft disorder), *Shprintzen's syndrome* (cardiac and cleft disorder), *Down's syndrome, Treacher-Collin's syndrome, Apert's syndrome* and trisomy.

Cleft lip

- *Central*—rare. In upper lip. Between two median nasal processes. (*Hare lip)*
- *Lateral*—maxillary and median nasal process, *commonest*; can be unilateral or bilateral
- *Incomplete* cleft lip does not extend into nose
- *Complete* cleft lip extends into nasal floor
- *Simple* cleft lip is only cleft in the lip
- *Compound* cleft lip is cleft lip with cleft of alveolus

LAHS classification of cleft disorders

- 'L' for lip, 'A' for alveolus, 'H' for hard palate, 'S' for soft palate
- *Capital* 'LAHS' for 'complete' type
- *Small letters* 'lahs' for 'incomplete type'
- *Asterisks* 'lahs' for microclefts
- 'LAHSHAL' for bilateral clefts

Incidence

- Common in Caucasians.
- In 75% of cases it is unilateral. Commonly occurs on the left side (60%).
- In 50% of cases it is combined cleft lip and palate. Incidence is 1:600 live births. Common in boys.
- In 15-25% of cases it is cleft lip alone.
- In 25-40% of cases it is cleft palate alone. Incidence is 1:1000 live births. More common in girls.

Problems in Cleft Disorders

- Difficulty in sucking and swallowing. This is commonly observed in cleft palate than in cleft lip.



Fig. 2.3: Central cleft lip (Hare lip, Type I cleft lip—It is rare).



Fig. 2.4: Lateral type of cleft lip (Type II variety—it is commonest). It is due to imperfect fusion of maxillary process and median nasal process. It can be unilateral or bilateral.



Fig. 2.5: Wide cleft palate and lip—complete type in a child.



Fig. 2.6: Bilateral cleft lip.



Fig. 2.7: Unilateral cleft lip, lateral type which is commonest.

- Speech is defective especially in cleft palate, mainly to phonate B, D, K, P, T and G.
- Altered dentition or supernumerary teeth.
- Recurrent upper respiratory tract infection.
- Respiratory obstruction (in *Pierre Robin syndrome*)
- Chronic otitis media, middle ear problems.
- Cosmetic problems.
- Hypoplasia of the maxilla.
- Problems due to other associated disorders.

Treatment for Cleft Lip

Millard criteria is used to undertake surgery for cleft lip.

Millard criteria (Rule of '10')

- 10 pound in weight
- 10 weeks old
- 10 gm % haemoglobin



Fig. 2.8: Bilateral cleft lip involving palate.

Bleeding gums in uraemia are not so spongy as in scurvy: in fact they may look nearly normal.—**Frederic J Wright**



Figs 2.9A and B: Cleft lip and cleft palate in an adult.

a. *Millard cleft lip repair* by rotating the local nasolabial flaps.
b. Management of associated primary or secondary cleft palate deformity.
c. Proper postoperative management like control of infection, training for sucking, swallowing and speech.
d. Tenninson's 'Z' plasty (*Tenninson-Randall triangular flap*).

Note: *Delaire timing of the cleft surgery* – Unilateral/ bilateral cleft lip alone, in one stage operation done in 4-6 months. For cleft palate alone involving only soft palate, in one stage surgery is done in 6 months. For cleft palate alone but involving both soft and hard palates – soft palate in 6 months; hard palate in 18 months. In combined cleft lip and palate, unilateral or bilateral, in two stages – cleft lip and soft palate in 6 months; hard palate in 18 months.

Cleft Palate

- It is due to failure of fusion of the two palatine processes.
- Defect in fusion of lines between premaxilla (developed from median nasal process) and palatine processes of maxilla one on each side.



Figs 2.10A and B: Cleft palate only. Lip is normal. Pre-maxilla is not involved.



Fig. 2.11: Steps of cleft lip repair.

Principles of cleft lip repair

- "Rule of 10' should be fulfilled
- Before 6 months it should be operated
- Infection should not be present
- *Millard* advancement flap is commonly used for unilateral cleft lip repair
- Bilateral cleft lip repair can be done either in single or two stages (with 6 months gap between each stage)

- One stage bilateral cleft lip repair is done using *Veau III method/Millard's single stage/Black* method
- Proper markings are made prior to surgery and incision should be over full thickness lip
- Often 1 : 2,00,000 adrenaline injection is used to achieve haemostasis
- Three layer lip repair should be done (mucosa, muscle and skin)
- Cupid's bow should be horizontal
- Continuity of white line should be maintained
- Vermilion notching should not be there

- When premaxilla and both palatine processes do not fuse, it leads into complete cleft palate (Type I cleft palate).



Fig. 2.12: Cleft palate with cleft lip in a child. Child also is suffering from congenital cardiac defects.



Fig. 2.13: Complete cleft palate Type I.

- Incomplete fusion of these three components can cause incomplete cleft palate beginning from uvula towards posteriorly at various lengths. So it could be Type II a–bifid uvula, Type II b–bifid soft palate (entire length) or Type II c –bifid soft palate and posterior part of hard palate (but anterior part of hard palate is normal).



Fig. 2.14: Cleft palate Type II a—bifid uvula.



Fig. 2.15: Cleft palate Type II b—bifid soft palate (entire soft palate).

- Small maxilla with crowded teeth, absent/poorly developed upper lateral incisors.


Cleft palate II c—bifid soft palate
and cleft posterior hard palate

Fig. 2.16: Cleft palate Type II c—bifid soft palate entire length with cleft of posterior hard palate (anterior palate is normal).

Preauricular ulcer is a late stage of an abscess due to a congenital preauricular sinus. It refuses to heal for infection is maintained from the sinus.
— Francis AR Stammers



Fig. 2.17: Bilateral congenital craniofacial cleft (*Courtesy*: Dr Sathish Bhat, Plastic Surgeon, Mangalore).

- Bacterial contamination of upper respiratory tract with recurrent infection is common.
- Chronic otitis media with deafness may occur.
- Swallowing difficulties to certain extent and speech problems can occur.
- Cosmetic problems can occur.

Treatment for Cleft Palate

Criteria for surgery

- 10 kg weight
- 10 months of age (10-18 months)
- 10 gm % haemoglobin

- Cleft palate is usually repaired in 12-18 months. Early repair causes retarded maxillary growth (probably due to trauma to growth center and periosteum of the maxilla during surgery if done early). Late repair causes speech defect.
- Both soft and hard palates are repaired.
- Abnormal insertion of tensor palati is released. *Mucoperiosteal flaps* are raised in the palate which is sewed together. If maxillary hypoplasia is present, then *osteotomy of the maxilla* is done. With *orthodontic help teeth extraction and alignment* of dentition is done.
- Regular examination of ear, nose and throat during follow up period.
- Postoperative speech therapy.
- Whenever complicated problems are present, staged surgical procedure is done.
- *Wardill- Kilner push back operation*—by raising mucoperiosteum flaps based on greater palatine vessels.
- *Secondary management:*
    - Hearing support is given using hearing aids if defect is present; control of otitis media.
    - Speech problems occur due to velopharyngeal incompetence; articulation problems also can occur – speech therapy is given. It is corrected by pharyngoplasty, veloplasty, speech devices.
    - Dental problems like uneruption, unalignments are common. They should be corrected by proper dentist opinion, and reconstructive surgery.
    - Orthodontic management with alveolar bone graft, maxillary osteotomy – done in 8-11 years of age.
    - Veloplasty, dental implants, rhinoplasty, orthognathic surgeries, etc.

Principles of palatoplasty

- Timing is between 10-18 months
- Mucoperiosteum flap is raised
- Palatal defect is closed using 3 layers—nasal, muscle and oral layers
- Hook of pterygoid hamulus is fractured to relax tensor palate muscle to relieve tension on suture line


Cleft palate with palatine artery
Cleft palate repair V-Y palatoplasty

Fig. 2.18: V-Y palatoplasty.

MAXILLOFACIAL INJURIES

It may be due to road traffic accidents, assaults, bullet injuries or sport injuries.

Classification

Fracture in maxillofacial region can be grouped as:

- Fracture lower third that comprises mandible.
- Fracture middle third that comprises maxilla, zygoma and nose.
- Fracture upper third of the face involving part of the orbit, frontal bones.

Maxillofacial fracture also can be grouped as:

- Fractures of the face which do not involve the dental occlusion—fractures of zygoma and nose.
- Fracture which involves the dental occlusion – fracture mandible and maxilla.



Fig. 2.19: Relation between middle third and cranium in 45° plane.



Fig. 2.20: Posterior gagging of occlusion due to backward displacement of fracture segment in middle third fracture.

Soft Tissue Injuries

- Lacerations, contusions, cut wounds, etc.
- Eyelid injuries with black eyes.
- *Facial nerve injury*: Primary repair is required.
- *Parotid duct injury*: Here primary anastomosis of the injured duct is done, with a fine polythene cannula is kept as a stent inside the duct which will be removed in 14 days.
- *Lacrimal apparatus injury*: Here the duct is sutured with a fine nylon thread in the canaliculus which is kept for 3 months.

Injuries to the Facial Bones

- *Fracture nose*: Nasal bones are most commonly injured bones in face. Patient presents with pain and swelling in the nose with deviation and displacement. Here reduction of the fractured nasal bones and nasal septum under general anaesthesia is done. Later position is maintained by nasal packs from inside (which is removed in 7 days) and by a nasal plaster from outside (which will be kept for 14 days). Procedure is done using Walsham's and Asch's forceps.
- Injuries to the *maxilla.*
- *Zygomatic* bone injuries.
- *Mandibular* bone fracture and mandibular dislocation.
- *Orbital bone fracture*: Presents with diplopia, enophthalmous, sensory loss in the area of infraorbital nerve.
- Infraorbital ecchymosis of the orbit is called as *Panda sign*.



Fig. 2.21: Soft tissue injury face involving upper lip.

Clinical Features

- Localised swelling due to haematoma.
- Facial oedema.
- Bleeding with open wounds.
- Asymmetry which is clinically confirmed by observing supraorbital ridges, nasal bridge.
- Localised tenderness.
- Step deformity.
- Trismus.
- Diplopia.
- Features of associated injuries like intracranial, abdominal or thoracic injuries.

Investigations

- X-ray face.
- CT scan of head and jaw.

General treatment for faciomaxillary injuries

- Suturing of soft tissues
- Airway maintenance
- Control of bleeding
- Pain relief
- Control of infection
- Treating the individual fractures

Ankylosis of mandible joint causes receding of chin giving a characteristic shrew mouse profile.

—Leon Dufourmentel

PRIMARY CARE (EARLY CARE) IN MAXILLOFACIAL INJURIES

Injury can be isolated single bone fracture or multiple bone fractures. Real primary care is usually not required except when there is mechanical respiratory block causing airway obstruction.

Respiratory Obstruction

Causes

- Oronasal airway block can occur by blood, clot, vomitus, foreign body, dentures, teeth, saliva, bone pieces, etc.
- Backward falling of tongue can cause obstruction of the nasopharynx and oropharynx. It is common in bilateral mandibular fracture.
- Occlusion of the nasopharynx and oropharynx can occur in fracture maxilla with posterior and inferior displacement.
- Haematoma in floor of the mouth or posterior oral cavity can cause airway block.
- Oedema of larynx/tongue/posterior third of oral cavity/pharynx.
- Surgical emphysema.

Treatment

- Cleaning of the oral and nasal cavities to remove obstructing agents like clot, dentures, teeth or bone. Gauze swabbing and suction.
- Fallen tongue should be placed forward using finger and often temporary alignment of the occlusion may be needed.
- Maxillary disimpaction is done when needed in fracture maxilla.
- Positioning of the patient is important. Prone/semiprone position with head towards one side is the safest position. If this is not possible, then patient may be placed in sitting position which also improves the breathing. Placing the patient flat on his back in supine position should be avoided as much as possible.
- Tracheostomy should be done when needed without delay as it will be life saving by facilitating the easy airway and breathing.

Control of Pain

Analgesics like NSAIDs are used to control pain. Morphine and analogues are not used as they may suppress the respiration. They may mask the pain of alarming severe injury in chest, abdomen or other areas, or they may interfere with pupillary reaction and neurological signs in the presence of intracranial injuries.

Control of Infection

Antibiotics are needed. Tetanus toxoid and often antitetanus globulin (ATG 3000 units IM) are required.

Haemorrhage in Maxillofacial Injuries

Haemorrhage in maxillofacial injuries is usually not life threatening. But it should be identified and controlled properly. In association with other internal injury, such haemorrhage may be important to cause the circulatory failure.

Haemorrhage may be due to:

- Soft tissue bleeding.
- Bleeding from inferior alveolar artery, palatine vessels.
- Nasal bleeding.

Control of Bleeding

- Blood transfusion, IV fluids, resuscitation.
- Nasal packs.
- Fracture correction.
- Ligation of the bleeder.
- Cauterisation.
- Packing the area.
- Under running the bleeding field.
- Embolisation.
- External carotid artery ligation above the level of the origin of the superior thyroid artery.

Fractures not involving occlusion	***Fracture involving occlusion***
Central	***Dentoalveolar***
• Fracture nasal bones and/or nasal septum	*Subzygomatic* • Le Fort-I-low level either unilateral or bilateral • Le Fort II-pyramidal either unilateral or bilateral
• Fracture of frontal process of maxilla	
• Fractures of above two extending into ethmoid-nasoethmoid	
• Fractures above three which extends into frontal bone – fronto-orbito-nasal dislocation	*Suprazygomatic* • Le Fort III – high level • Craniofacial disjunction–unilateral or bilateral
Lateral	
• Fractures involving zygomatic bone, arch and maxilla excluding the dentoalveolar component	

Le Fort classification

(*Rene Le Fort*—French surgeon classified these fractures by dropping rocks on the face of the cadavers and later dissected the area for study and research and published paper in 1911)

Types	***Features***
Le Fort I (Guerin's fracture-low level) (floating fracture, horizontal fracture of maxilla)	• Bleeding from nose • Posterior gagging of occlusion • Upper lip swelling • Palatal ecchymosis • Occlusion derangement • Floating maxilla
• It runs horizontally above the floor of the nasal cavity involving lower third septum, palate, alveolar process of maxilla and lower third of pterygoid plates of maxilla	

Le Fort II (pyramidal fracture) • From the nasal bones at top-most, fracture runs laterally towards lacrimal bones, medial wall of orbit, infraorbital margin, through ormedial to infraorbital foramen and backwards below the zygomatico maxillary area through lateral wall of maxillary sinus and pterygoid plates. Zygoma is intact with skull base	• Oedema of middle third face • Both sides circumorbital and subconjunctival ecchymoses • Nasal bleeding/ obstruction/deformity • Deformity of face (dish face), diplopia • Retroposition of maxilla with posterior gagging • Limitation of ocular movements, CSF rhinorrhoea • Tenderness and separation of infraorbital margin
Le Fort III (craniofacial disjunction, high level) • Here fracture runs parallel to skull base. It passes through the nasal bone, lacrimal bone, ethmoid bone, optic foramen, inferior orbital fissure, pterygomaxillary fissure and lateral orbital wall with frontozygomatic suture with zygomatic arch	• Lengthening of face • Enophthalmos, ocular level depression • Hooding of eyes, occlusal plane tilting • Entire facial skeleton moves as a single block • Tenderness and separation of suture line • Diplopia • Trismus, teeth malalignment *Guerin sign*: Haematoma at greater palatine foramen



Figs 2.22A to D: Le Fort classification–different types and also dentoalveolar fracture (*Refer table for details*).

Associated Injuries

All associated injuries should be assessed properly and individually. On priority basis it should be treated.

- Soft tissue injuries.
- Cranial injuries.
- Orbital injuries.
- Intra-abdominal/thoracic/pelvic injuries.

FRACTURE MIDDLE THIRD AREA

It includes-

- Maxillae, zygomatic bones, palatine bones, nasal bones, lacrimal bones, inferior conchae (one on each side).
- The vomer, ethmoid and its attached conchae, pterygoid plates of sphenoid.

Fracture middle third includes fracture maxilla, zygoma and nasal bones.



Fig. 2.23: Fixation of the splint to skull. It is often used with gunning splints to fix it to skull.

Clinical Features

- Oedema face, subconjunctival haemorrhage, ocular ecchymosis.
- Bleeding from the nose.
- Diplopia due to trapping of the extra-ocular muscles in the fracture segments.
- Anaesthesia of the cheek.
- Trismus and malalignment of teeth.
- *Guerin's sign*: Haematoma at greater palatine foramen.
- Always patient should be examined and observed for CSF leak and intracranial injuries.

The first two letters of goals are go.....



Fig. 2.24: Photo showing bilateral maxillary fracture.

Investigations

- CT scan head.
- X-ray skull.

Treatment

- It should be managed in a center for maxillofacial injuries.
- Antibiotics.
- Tracheostomy.
- Associated zygoma and nasal fractures are reduced first.
- Direct wire suturing of the zygomaticofrontal region.
- Fixation of teeth in occlusion using eyelet wires, bars or cap splints.
- Once reduced, fracture bones are immobilised using extra-oral rods called as *Mount Vernon box frame.*
- Initially intravenous fluids and blood transfusions are required. Later Ryle's tube feeding is done.
- Proper ophthalmic consultation is necessary when there are orbital injuries.

ZYGOMATIC COMPLEX FRACTURE

Classification

- *Simple fracture which is stable and undisplaced*— here fracture line passes across the infraorbital foramen downwards over anterior wall of the antrum.
- *Simple fracture which is displaced medially*. It may be associated with rotation / tilt in vertical axis, either medial tilt or lateral tilt. Infraorbital nerve may get compressed or branches of superior dental nerve may get torn.
- *Unstable fracture with rotation around horizontal axis* with medial tilt or lateral tilt.
- *Comminuted fracture* extending into the floor of the orbit.
- *Fracture of the zygomatic arch* causes a localised depression of the arch which displaces medially and tends to impinge on the coronoid process of the mandible.
- '*Blow-out' fracture* of the orbit is due to direct blunt trauma on the eyeball causing depressed comminuted fracture of the orbital floor with herniation of the orbital fat into the antrum (Fig. 2.23C).
- *Enbloc dislocation of zygomatic bone* medially/ inferiorly/ posterolaterally.

Clinical Features

- Swelling and bruising in the cheek with subconjunctival haemorrhage.
- Flattening of the cheek prominence.
- Step in the margin of the bony orbit at the infraorbital foramen.
- Sensory loss over the supply of the branches of the superior orbital nerve— teeth on the affected area are anaesthetic on percussion.
- Sensory loss over the supply of the infraorbital nerve usually over infraorbital region, upper lip and alar region of the nose—common.
- Enophthalmos is due to herniation of the orbital fat across the fracture floor of the orbit into the antrum
- Diplopia is due to entrapment of the inferior rectus muscle preventing upward rotation of the eyeball while looking up.
- Trismus with marked restriction of the lateral movements.
- Epistaxis, lowering of pupil level.
- Infraorbital ecchymosis of the orbit is called as *Panda sign.*


Fracture site (undisplaced)
Fracture site (displaced medially)
A
B
Eyeball
Blow
Orbital floor
Blow
Zygoma fracture
Maxillary sinus
C

Figs 2.25A to C: (A and B) Diagrams showing different types of zygomatic fractures, (C) Blow-out fracture.

Investigations

- 30° occipitomental X-ray is used commonly but often obliquity of X-ray may be increased to 60°. In X-ray, findings observed are:
    - Fracture line near infraorbital foramen, zygomatic arch and lateral wall of the antrum.
    - Orbital floor line for fracture.
    - Opacity in the antrum due to blood.
- CT scan is done to see orbital depression and herniation of orbital fat.

Treatment

- *Every patient with zygoma fracture need not require surgical correction.*
- Need for surgery is decided based on clinical features.

Indications for surgery are:

- Infraorbital anaesthesia, trismus
- Diplopia, enophthalmos
- Flattening of the cheek
- Undisplaced fracture with infraorbital anaesthesia

Surgical Approaches

1. *Closed reduction of the zygomatic arch through Gillies temporal approach*:



Fig. 2.26: Technique showing method of temporal reduction using disimpaction forceps.

An oblique skin incision of 2 cm length temporal is made between the two branches of the superficial temporal artery. Care is taken to avoid injury to artery. Whitish glistening temporal fascia is identified and incised. Zygoma elevator is introduced beneath the zygoma and fracture fragments are manipulated and elevated into proper position. An audible snap is heard when fracture gets reduced into position. Reduced, disimpacted fracture is always stable. Additional corrections in other parts can be done by different leverage actions of the elevator. Orbital rim, zygomatic arch are palpated for completion of correction. Skin wound is closed with sutures.

Elevators used are Bristow's periosteal elevator, Rowe's zygomatic elevator.



Figs 2.27A and B: Disimpaction of maxilla using Rowe's disimpaction forceps by downward leverage action.

2. *Internal fixation by open reduction and fixation is needed*

- When fracture is unstable or
- Comminuted or
- Zygoma fracture with middle third fractures.

By proper incisions infraorbital and zygomaticofrontal fracture sites are exposed; after open reduction they are fixed using wires/plates and screws.

3. *Exploration of the orbital floor is necessary whenever there is*

- Comminuted fracture in orbital floor.
- Orbital fat herniation.
- Diplopia with entrapment of the inferior rectus muscle.



Fig. 2.28: Fracture zygoma showing open reduction and fixation using wires directly. Two types of incisions are shown depending on the site of the fracture.

FRACTURE OF THE MANDIBLE

Types

I. At the *neck of the condyle* (35%), as it is the weakest point. The condyle is displaced in front and medially often with dislocation. Painful jaw movement is the clinical features. It may be unilateral or bilateral.

II. At the *angle of the mandible*: If fracture is upwards and inwards, it is impacted and undisplaced. So it is a favourable fracture. If fracture is downwards and outwards, it gets displaced and so it is an unfavourable fracture. It needs open reduction using wires.

III. Fracture *near the mental foramen through the canine fossa*. This fracture causes displacement. Such bilateral fractures can cause pull on digastric and geniohyoid muscles precipitating fall of *tongue backwards which will block the airway.*



Fig. 2.29: Types of mandibular fractures.

Other Classifications

Classification of the fracture mandible

Depends on the type	*Depending on the anatomical site*
• Simple	• Dentoalveolar fracture
• Compound	• Condylar fracture
• Comminuted	• Coronoid fracture
• Pathological	• Fracture ramus of the mandible
• Green stick fracture in children	• Fracture angle of the mandible
	• Fracture in the body of the mandible
	• Symphyseal region fracture

Guardsman fracture is direct fracture of symphysis and indirect fractures of both the condyles of the mandible. In olden days guards of the queen who are in attention position used to faint and fall forward to get these fractures.

Dentoalveolar fracture

Features	*Management*
• Horizontal fracture below the alveolar margin	• Look for other injuries in face
• Dentoalveolar segment will be freely mobile	• X-ray face to see injuries
• Tooth may get split vertically/horizontally	• Dentoalveolar segment reduction and placing jaws in central occlusion position
• Derangement in occlusion and alignment	• Stabilisation using inter-dental wires or arch bars
• Gingival laceration	• Liquid diet for 3-4 weeks
• Bleeding	
• Infection and late osteo-myelitis of mandible	

Clinical Features

- Pain and tenderness in the lower jaw with bruising over the surface.
- Haematoma in the floor of the mouth is called as *Coleman's sign.*
- Difficulty in opening the mouth, speech and swallowing.
- Anaesthesia of the lower lip due to compression of inferior dental nerve.
- Deranged dental occlusion.
- Step deformity.

Investigations

- X-ray of the mandible.
- Orthopantomogram (OPG).

Treatment

- Antibiotics to prevent formation of osteomyelitis of the mandible.
- Open fixation of the fracture segments using silver wires for 4-6 weeks.
- Fixation by:
    - Interdental wiring.
    - Using arch bars.
    - Silver alloy or plastic caps.
- Only fluid diet for 6 weeks.
- Irrigation wash to the oral cavity to maintain the hygiene.

Complications of fracture mandible

- Obstruction of the airway
- Osteomyelitis of the mandible
- Trismus
- Speech disturbances


Temporalis
Medial pterygoid
Masseter
Mylohyoid
Digastric
Fracture site
Fracture site

Fig. 2.30: Muscle actions in mandible fracture causing different displacements.


Fracture unreduced
Fracture reduced
Teeth not occluded
Teeth well occluded

Fig. 2.31: Unreduced and reduced fracture mandible.


Fracture coronoid
Dentoalveolar fracture
Condyle fracture
Ramus fracture
Symphyseal fracture
Body fracture
Angle fracture

Fig. 2.32: Different sites of fracture mandible.


Simple Arch Bar Fixation
Cleats
Erich arch bar fixation with cleats

Fig. 2.33: Arch bar wiring. Figure shows both simple and Erich arch bar wiring with cleats to pass wire.



Fig. 2.34: Circummandibular wiring used in gunning splints.



Fig. 2.35: Interdental wiring. It is commonly used and accepted method of wiring.

Rudeness is a weak imitation of strength.


Upper border wiring
Fracture site
Lower border wiring
Fracture site

Fig. 2.36: Upper and lower border wiring. It is used to fix the mandibular fractures and is often done together with other fracture fixations in the face.


Compression plate
Fracture site
Alverolar compression
Fracture mandible
Compression plate fixed
Axial compression

Fig. 2.37: Compression plating of a mandibular fracture. Note the different methods.

DISLOCATION OF THE MANDIBLE

- It occurs at *temporomandibular joint.*
- Unilateral dislocation after trauma is common.
- Bilateral dislocation occurs during yawning and it is recurrent.

Clinical features are difficulty in opening the mouth with pain and tenderness over the joint.

Treatment

- Reduction of dislocation under general anaesthesia.
- If there is associated fracture mandible it should be dealt accordingly.

PREAURICULAR SINUS

- It is due to failure of fusion of anterior tubercles of the auricle creating a sinus.
- Often sinus opening gets sealed forming a preauricular cyst which gets infected forming an abscess.
- Sinus can get infected repeatedly, discharging pus through its opening.
- It is often multiple.

Investigations

- Sinusogram.
- Discharge study.

Differential Diagnosis

- Cold abscess.
- Sebaceous cyst.



Fig. 2.38: Preauricular sinus. During excision, methylene blue is injected into the track initially and later it is excised using elliptical incision.



Fig. 2.39: Microtia which is corrected later (*Courtesy*: Dr Sathish Bhat, Plastic Surgeon, Mangalore).



Figs 2.40A and B: Retruded chin is corrected by plastic reconstruction (*Courtesy:* Dr Sathish Bhat, Plastic Surgeon, Mangalore).

Treatment

Complete excision of the sinus with entire track.

Treacher-collins syndrome

- Mandibulofacial dysostosis
- Hypoplasia of the zygomatic bone and mandible
- Antimangoloid slant to the palpebral fissure
- Coloboma of lower eyelid
- Low ear lobule with deficient middle ears
- Familial—3rd arch syndrome (Mandibulofacial dysostosis)

JAW TUMOURS



Fig. 2.41: Jaw tumour (Right sided).



Fig. 2.42: Upper jaw tumour (Left sided).

Classification

I. ***Swelling arising from the gums*** (*Epulis*):
  - Congenital epulis.
  - Fibrous epulis.
  - Pregnancy epulis.
  - Giant cell epulis.
  - Myelomatous epulis.
  - Sarcomatous epulis.
  - Carcinomatous epulis.

II. ***Swelling arising from the dental epithelium*** (*Odontomes*):
  - Ameloblastoma.
  - Compound odontome.
  - Enameloma.
  - Cementoma.
  - Dentinoma.
  - Odontogenic fibroma and myxoma.
  - Radicular odontome.
  - Composite odontome.

Cysts arising in relation to dental epithelium:
- Dental cyst.
- Dentigerous cyst.

III. ***Swelling arising from the mandible or maxilla:***
  - Osteoma and osteoblastoma.
  - Torus palatinus and mandibularis.
  - Fibrous dysplasia.
  - Osteoclastoma (Common in mandible).
  - Osteosarcoma.
  - Secondaries.
  - Giant cell reparative granuloma.

IV. ***Surface tumours:***
  - Tumours from the surface which extend into the jaw.
  - Ossifying fibroma.
  - Osteofibrosis of maxilla.
  - Ivory osteoma of jaw.
  - Leontiasis ossea (diffuse osteitis).
  - Carcinoma extending into the jaw.

EPULIS (Greek—means upon gum)

Swelling arising from the mucoperiosteum of gums.



Fig. 2.43: Epulis.

Congenital Epulis

- It is a benign condition seen in a *newborn* arising from gum pads.
- It is a variant of granular cell myoblastoma originating from gums.
- It is more common in *girls.* It is more common in *upper jaw*, common in canine or premolar area.
- It is not a malignant condition.

Clinical Feature

Well localised swelling from the gum which is firm and bleeds on touch.

Treatment

Excision.

Fibrous Epulis

- It is a benign condition, can occur in any individual.
- It is red, firm/hard, sessile/pedunculated.
- It is commonest type.
- It is fibroma arising from periodontal membrane.

Clinical Features

Painless, well localised, hard, non-tender, grey pink swelling in the gum which bleeds on touch.

Differential Diagnosis

Squamous cell carcinoma from the gum.

Investigations

- X-ray jaw.
- Orthopantomogram
- Biopsy from the lesion.

Treatment

Excision with extraction of the adjacent tooth. Recurrence can if root is not removed properly.

Pregnancy Epulis

- It occurs in *pregnant women* due to *inflammatory gingivitis.*
- Usually during 3rd month of pregnancy.
- *Clinically* it resembles fibrous epulis or pyogenic granuloma.
- It usually resolves after delivery. Otherwise it should be excised.

Myelomatous Epulis

- It is seen in *leukaemic* patients.

Investigated for leukaemia by peripheral smear, bone marrow biopsy.

Treatment: For leukaemia.

Granulomatous Epulis

It is a mass of granulation tissue in the gum around a caries tooth. It forms a localised soft/firm/fleshy mass in the gum which bleeds on touch.

Giant Cell Epulis

Osteoclastoma causing ulceration and haemorrhage of gum.

Carcinomatous Epulis

Squamous cell carcinoma of the alveolus and gum presenting as localised, hard, indurated swelling with ulceration.

Fibrosarcomatous Epulis

Fibrosarcoma arising from fibrous tissue of the gum.

Epulis

- Congenital
- Fibrous-commonest
- Granulomatous
- Pregnancy
- Carcinomatous
- Myelomatous
- Fibrosarcomatous

Odontogenic tumours

Epithelial tumours
- Ameloblastoma
- Calcifying odontogenic tumour
- Odontogenic adenomatoid tumour
- Composite odontoma, which may be either complex or compound. It is odontogenic hamartoma contains all 4 layers, dentin, enamel, cementum and pulp

Mesodermal tumours
- Odontogenic fibroma, myxoma
- Cementoma, dentinoma

Malignant odontogenic tumours
- Malignant ameloblastoma
- Fibrosarcoma

AMELOBLASTOMA (Adamantinoma, Eve's Disease, Multilocular Cystic Disease of the Jaw)

- It arises from the dental epithelium probably from the *enamel/dental* lamina.
- It occurs commonly in *mandible* or maxilla.
- Occasionally it is seen in the base of the skull in relation to Rathke's pouch or in tibia.
- Histologically it is a variant of *basal cell carcinoma*.
- It is a *locally malignant tumour.*
- It neither spreads through lymph node nor through blood. Hence it is *curable.*



Fig. 2.44: Large jaw tumour—could be adamantinoma/ osteoclastoma.



Fig. 2.45: Orthopantomogram (OPG) X-ray showing unilocular odontogenic tumour in lower jaw.

- It is usually unilateral.
- It can occur in a pre-existing dentigerous cyst.
- It is usually multilocular cystic spaces but can be unilocular also.
- Histologically cords of odontogenic epithelium, connective tissue, stellate reticulum like cells with columnar ameloblast like cells.

Clinical Features

- Swelling in the jaw usually in the mandible near the angle which attains a large size, extending to vertical ramus—*Eggshell crackling.*
- It is a gradually progressive, painless swelling which is smooth and hard with intact inner table (enlarges externally).
- Lymph nodes are not enlarged.
- Outer table expansion.
- It is common in males, common in 4th to 5th decades.

Attitudes are more important than facts.

Differential Diagnosis

- Osteoclastoma of the mandible: Here inner table is not intact.
- Dentigerous cyst.
- Dental abscess.
- *Giant cell reparative granuloma (Jaffe's tumour)* – It is a swelling which occurs due to haemorrhage within the bone marrow. It contains vascular stroma, collagen and connective tissue cells. It is common in women. It causes painless enlargement of jaw. It can be treated by calcitonin (100 units/0.5 mg subcutaneously daily for 12 months) or surgical curettage.

Investigations

- Orthopantomogram (OPG) shows multiloculated lesion—*Honeycomb* appearance.
- Biopsy from the swelling.
- CT scan of the region.



Figs 2.46A and B: X-ray (two different X-rays) showing typical honeycomb/multiloculated features of adamantinoma (*Courtesy:* Dr Veena Jagadish, MDS).

Treatment

- Segmental resection of the mandible. OR
- *Hemimandibulectomy with reconstruction of the mandible.*

Note:

Curettage and bone grafting should not be done. It is a curable condition.

Recurrent adamantinoma can spread through blood into lungs.

DENTIGEROUS CYST (Follicular Odontome)

- It is a unilocular cystic swelling arising in relation to the dental epithelium from an unerupted tooth.
- Common in lower jaw, but can also occur in upper jaw.
- It occurs over the crown of unerupted tooth. Commonly seen in relation to premolars or molars.
- It causes expansion of outer table of the mandible.

Clinical Feature

Painless swelling in the jaw which is smooth and hard.

Differential Diagnosis

- Adamantinoma.
- Dental cyst.
- Osteoclastoma.



Fig. 2.47: Dentigerous cyst.

Complication

It can turn into *adamantinoma.*

Investigation

Orthopantomogram. Tooth within the cyst, which is well-defined.



Fig. 2.48: Orthopantomogram showing dentigerous cyst.

Treatment

- If it is small, excision of the cyst is done.
- If it is large, initial marsupialisation and later excision is done.
- *Unerupted tooth should be extracted.*

DENTAL CYST (Radicular Cyst, Periapical Cyst)

- It occurs under the root of the chronically infected dead erupted tooth.
- It is lined by squamous epithelium derived from epithelial debris of *Mallassez.*

Clinical Feature

As a smooth, tender swelling in the jaw in relation to caries tooth which causes expansion of the jaw bone.



Fig. 2.49: Dental cyst.

Complication

It can cause osteomyelitis of the jaw.

Differential Diagnosis

Dentigerous cyst.

Investigation

Orthopantomogram.

Treatment

- Antibiotics.
- Drainage or excision of the cyst with extraction of the infected tooth is done.

Differences between dental cyst and dentigerous cyst

	Dental cyst	*Dentigerous cyst*
a. Site of occurrence	Erupted tooth under the root	Over the crown of an unerupted tooth
b. Infection	Common	Not common
c. Complication	Osteomyelitis	Adamantinoma
d. Treatment	Excision and extraction of tooth	Marsupialisation, excision and then extraction of tooth

Curable malignancies

- Adamantinoma
- Basal cell carcinoma
- Verrucous carcinoma
- Papillary carcinoma thyroid
- Marjolin's ulcer
- Carcinoma colon

OSTEOMYELITIS OF JAW

It is an inflammatory process in jaw; acute or chronic. It can be in the maxilla or mandible.

Causes

- Alveolar abscess leading into osteomyelitis.
- Recurrent dental infection.
- Trauma.
- After dental extraction; surgeries of the jaw.
- Postradiotherapy osteomyelitis (osteoradionecrosis).

Types

- *Acute* is common in children; maxilla or mandible may get involved; swelling, redness, fullness is the features; pus may trickle through nostril if it is in maxilla.



Fig. 2.50: Osteomyelitis of the mandible. Discharging sinus is obvious.

- *Subacute* type is the commonest type; common in adult; apical sepsis, endarteritis, bone necrosis is the pathology; common in mandible; rare in maxilla due to existing network vasculature which prevents endarteritis. Compression over inferior dental nerve causes numbness in chin in area of distribution of mental nerve. Pain, swelling, tenderness, irregularity, bone thickening are typical.

- *Chronic type* is also common in mandible; apical abscess, alveolar abscess, trauma, radiation, chemicals like phosphorus, tuberculosis, syphilis, actinomycosis are the causes. Pain, bone thickening, irregularity, discharging sinus, sequestrum in the discharge, discomfort are the features. Infection from lower incisor causes median mental sinus. X-ray shows features of osteomyelitis with new bone formation and sequestrum.

Management

- X-ray jaw; CT scan of jaw; discharge study; ESR are essential investigations. Biopsy from the sinus is needed often.
- It is often difficult to treat. In acute phase, antibiotic coverage, treatment of cause is done. In chronic type, sequestrectomy, mandibulectomy is needed.

Actinomycosis of Jaw

Faciocervical is the commonest type; lower jaw is commonly involved; infection begins at carious tooth; indurated gums → nodules → abscess → multiple sinuses → discharging sulphur granules with normal X-ray (*Ray fungus*). *Actinomycosis israelii* is the causative agent. It is treated by penicillins.

ALVEOLAR ABSCESS (Dental Abscess)

It is due to spread of infection from root of the tooth into the periapical tissue. Initially, it forms periapical abscess which later spreads through the cortical part of the bone into the soft tissues around forming an alveolar abscess.



Fig. 2.51: Tooth infection causing large dental abscess. It needs antibiotics, proper drainage and tooth extraction. Patient may develop trismus/retropharyngeal infection/chronic osteomyelitis of the mandible.

Disease begins in the pulp of tooth → pulpitis → spread to root → localized osteitis → abscess formation → spread into soft tissues outside in cheek → initially diffused later localised swelling in the jaw with redness and oedema of gum. Initial dull continuous pain later becomes severe excruciating pain.

Bacteria: Staphylococci, streptococci, anaerobic-bacteria and gram-negative organisms.

Clinical Features

- Deep, throbbing pain in the jaw and adjacent oral cavity with diffuse swelling over the cheek.
- Tender soft tissue swelling in the jaw which eventually bursts spontaneously leading to sinus formation.
- Oedema, pain and tenderness in the floor of the mouth.
- Trismus and dysphagia.
- Fever and features of toxaemia.
- Tender palpable lymph nodes in the neck.

Investigations

- X-ray of the mandible or maxilla.
- Discharging pus for culture study.

Complications

- Septicaemia.
- Spread of infection into other spaces like parapharyngeal spaces; sublingual and submandibular spaces causing Ludwig's angina; oedema of epiglottis and respiratory distress; spread to pterygoid space and along pterygoid muscles through emissary vein → cavernous sinus thrombosis; upper canine tooth abscess → medial corner of eye → angular vein thrombophlebitis → cavernous sinus thrombosis; submasseteric abscess.
- Lower incisor abscess can cause abscess in the chin and later median mental sinus; chronic osteomyelitis of the jaw with discharging sinuses. Osteomyelitis is common in mandible – *horizontal process near the mentum*, presenting with pain, swelling, discharging sinuses, bone thickening, loose tooth, and trismus. Sequestrum is commonly seen. It is treated by antibiotics, sequestrectomy, mandibulectomy.

Treatment: Antibiotics, sequestrectomy, mandibulectomy.

Treatment

- Antibiotics.
- Drainage of the abscess under general anaesthesia.
- Extraction of the tooth at a later period.
- Excision of the sinus whenever required.

FIBROUS DYSPLASIA OF BONE/JAW

It is benign self limiting non-capsulated lesion of bone wherein normal bony architecture is replaced by collagen, fibroblasts, osteoid and calcified tissue. It is often classified as benign tumour with localized developmental arrest, with bone being not differentiated into a mature bone tissue.

It is seen in childhood and adolescents.

Types

It may be *polyostotic or monostotic*. Condition can occur in long bones, ribs and jaw bones, either mandible or maxilla. Disease is either metaphyseal or in the shaft, never in epiphysis.

1. Monostotic (70%)

- It is equal in both sexes. It occurs in children and adolescents; stops once growth plate is closed.
- Femur is the commonest bone involved; tibia, ribs, jaw bones, skull and humerus can get involved.
- It can present as asymptomatic diffuse hard bony swelling or can be painful due to fracture. Discrepancies of the part with asymmetry are common.
- Monostotic will not turn into polyostotic type.
- Monostotic will not turn into sarcoma.

2. Polyostotic Fibrous Dysplasia (27%) without Endocrine Dysfunction

- It begins in earlier age group than monostotic.
- It is common in femur, skull, tibia, humerus, ribs, fibula, radius, ulna, mandible and vertebrae. Craniofacial bones are involved in more than 50% of patients.
- It may continue to grow in adulthood (progressive).
- There is no evidence of hyperparathyroidism. It should be differentiated from primary hyperparathyroidism of bone.
- Involvement of shoulder and pelvis causes severe deformity.
- Severe involvement of femur causes '*shepherd crook'* deformity.
- Recurrent spontaneous fractures are common.
- Polyostotic occasionally turns into sarcoma.

3. Polyostotic Fibrous Dysplasia with Endocrinopathies (3%)

- *Polyostotic fibrous dysplasia with skin pigmentation* (*Café au lait*, on same side of the disease in neck, chest, back, shoulder, pelvis, larger) with sexual precocity in females (McCune Albright's syndrome); often with hyperthyroidism, growth hormone secreting pituitary adenoma and primary adrenal hyperplasia is 3% common.
- It is due to mutation of guanyl nucleotide binding protein gene (GNAS gene).

- Fibrous dysplasia is most common in *femur—shepherd crook deformity; metaphyseal*
- In the jaw, mandible is the common site, vertical ramus, outer table expansion
- Monostotic is more common
- Polyostotic is more problematic—discrepancies, pathological fracture, sarcoma changes
- Monostotic ceases with cessation of growth
- Surgery should never be done during growing period

Fibrous Dysplasia of Jaw

- In the jaw, it can occur in maxilla or mandible; but mandible is more common site.
- It presents with diffuse swelling of vertical ramus of the mandible or maxilla. Gritty white, hard cartilages with cysts are the pathology. Diffuse hard, painless swelling which causes asymmetry is the usual presentation. It progresses with the growth of the bone.
- It is commonly monostotic but can be polyostotic. Monostotic ceases once bone develops completely. Polyostotic may continue to grow.
- Teeth are normal.
- Expansion is towards outer cortex of the mandible.
- Polyostotic occasionally turns into sarcoma (but not monostotic).

Complications of Fibrous Dysplasia

- Deformity and cosmetic problems.
- Pathological fractures.
- Sarcomatous transformation in polyostotic type only.

Differential Diagnosis

- Osteoclastoma, adamantinoma.
- Osteitis fibrosa cystica of primary hyperparathyroidism.

Investigations

- X-ray is diagnostic showing ground glass/smoke screen appearance.
- Serum alkaline phosphatase may be slightly elevated.
- Biopsy may be needed to confirm the condition and to rule out other conditions.
- Parathormone assay, serum calcium estimation in suspected parathyroid pathology.

Treatment

It should not be operated during growing period as if intervened there may be chances that it may turn into osteosar-



Fibrous dysplasia mandible

Fig. 2.52A



Fibrous dysplasia maxilla
Fig. 2.52B

Figs 2.52A and B: Fibrous dysplasia of mandible and maxilla in two different patients. Mandible is common site in jaw. Overall femur is the commonest site.

coma. As it is a self limiting disease it can be left alone once the growth stops or can be corrected by restorative excision to maintain facial contour. Thorough curettage with grafting of cancellous bone may be done. Bisphosphonates are often used to relieve pain.

CHERUBISM (Cherub—Angelic Being)

It is an autosomal dominant condition that occurs in first year of life.

Pathology

- Giant cell granuloma with fibrous tissues in the jaw.
- It is commonly *bilateral.*
- Commonly seen in the *angles of the mandible* and also in maxilla.
- It is familial fibrous dysplasia of jaw commonly involving both halves of the mandible with bulging outwards near the angle of the jaw causing '*winged face*' appearance of angelic babies.

Clinical Features

- Diffuse enlargement of maxilla and both sides of the mandible.
- Bulging of the cheek causes pull of the lower eyelid. Hence, child appears like, as if looking upwards.
- Interference with the development and eruption of the teeth.

Treatment

It is a self-limiting disease. Often requires dental care and treatment for proper dentition.

Pierre-Robin syndrome

- Congenital condition
- Cleft palate alone
- Mandibular hypoplasia
- Cyanotic episodes
- Deficiency in transforming growth factor
- Defective sucking and tongue falling backwards in infants
- Cryptorchidism



Fig. 2.53: Earlobe infection.

Chapter 3 Oral Cavity

CHAPTER OUTLINE

- Ranula
- Sublingual Dermoids
- Stomatitis
- Cancrum Oris
- Syphilitic Lesions of Oral Cavity
- Leukoplakia
- Erythroplakia
- Oral Submucosal Fibrosis
- Premalignant Conditions of Oral Cavity
- Oral and Upper Aerodigestive Cancers
- Cheek
- Carcinoma Cheek
- Lip
- Neoplasm of Lip
- Carcinoma Lip
- Tongue
- Tongue Ulcers
- Benign Tumours of Tongue
- Tongue Fissure
- Glossitis
- Tongue Tie
- Carcinoma Tongue
- Carcinoma of Posterior One-Third/Base of the Tongue
- Nasopharyngeal Carcinoma
- Maxillary Tumours
- Malignant Tumours of Tonsil
- Carcinoma Hard Palate
- Laryngeal Tumours
- Malignant Tumours of Larynx
- Trismus

RANULA

(*Rana* = *Frog*, Ranula looks like belly of frog, hence the name—Latin).

- Ranula is an *extravasation cyst arising from sublingual gland* or *mucous glands of Nuhn* or *glands of Blandin* in the floor of the mouth. Occasionally it can occur in submandibular salivary gland also.
- Initially there is blockage of the duct (of sublingual gland) causing retention cyst, which causes rupture of the acini due to increased pressure leading into extravasation cyst.

Clinical Features

- Presents as a bluish smooth, soft, fluctuant, brilliantly transilluminant swelling in the lateral aspect of the floor of the mouth.
- It often extends into the submandibular region through the deeper part of the posterior margin of mylohyoid muscle and is called as *plunging ranula*. It is intraoral ranula with cervical extension. It is cross fluctuant across mylohyoid. It can arise from both submandibular and sublingual salivary glands as a mucus retention cyst initially, which reaches neck by passing across the mylohyoid muscle presenting as soft, fluctuant, nontender, dumbbell shaped swelling in the submandibular region. It is bidigitally palpable. US and/or MRI is diagnostic. It is treated by surgical excision through neck approach along with excision of submandibular and sublingual salivary glands. Small plunging ranula is often excised per orally along with excision of sublingual salivary gland.
- Ranula has a delicate fibrous capsule and is lined by a layer of macrophages. It contains clear fluid.
- It may damage the Wharton's duct.
- It may rupture; it may get infected.
- It may interfere with speech and swallowing occasionally.

Clinical features of ranula

- Bluish swelling in the floor of the mouth
- Laterally placed
- Nontender
- Fluctuant and cross fluctuant (plunging ranula)
- Brilliantly transilluminant

Differential Diagnosis

Lymph cyst.
Sublingual dermoid.

> *Leukoplakia tongue looks as though it has been covered with white paint that had hardened, dried and cracked.*
> **—Sir Henry T Buutlin**



Figs 3.1A to C: Ranula. Note the bluish discolouration, brilliantly transilluminant and the location.

Treatment

- *Marsupialisation* can be done initially, and later once the wall of the ranula is thickened it is excised (*Marsupial* means pouch where baby is kept, carried and sucked on the mother's belly, like in Kangaroo).
- If ranula is small it can be excised without marsupialisation.
- Excision of sublingual salivary gland is often needed. In plunging ranula submandibular salivary gland needs to be excised.

SUBLINGUAL DERMOIDS

They are *sequestration dermoids* lined by squamous epithelium containing keratin.

It is smooth, soft, fluctuant, nontransilluminant bidigitally palpable swelling.

Types

1. ***Median sublingual dermoid:*** It is derived from epithelial cell rests at the level of fusion of *two mandibular arches*. It may be supramylohyoid or inframylohyoid. It is located between two genial muscles, in relation to mylohyoid muscle. It is a midline swelling which is smooth, soft, cystic, nontender, nontransilluminant.
   Treatment is excision through oral approach.
   Complication is abscess formation.
2. ***Lateral sublingual dermoid:*** It develops in relation to submandibular duct, lingual nerve and stylohyoid ligament. It is derived from *first branchial arch*. It forms a swelling in the lateral aspect of the floor of the mouth.
   Treatment: Small one is removed per orally. Larger one, through submandibular incision.

STOMATITIS

- It is inflammation of oral mucosa by trauma, radiotherapy, chemicals, nutritional deficiency or infection.
- *Traumatic stomatitis* may be due to dentures, teeth bite, and brushing of teeth harshly which presents as painful thin covering of furr with increased salivation. Proper mouth wash will cure the condition.
- *Aphthous stomatitis* is seen in malnutrition, debility, steroid usage. Present as multiple hyperaemic painful vesicles later forming deep round painful ulcers. It is treated with mouth wash and if needed by antibiotics. Recurrent aphthous stomatitis with ulcers is often familial, more common in women, common in lip, cheek, tongue which are very painful with more salivation. It heals spontaneously. But during active period, it interferes with speech, swallowing distressfully. It is treated by many drugs like levamisole, antibiotics, vitamin B and C, local applications of anaesthetics (xylocaine)/choline salicylate/benzalkonium chloride.
- *Candida stomatitis* (Monilial thrush) is due to fungal infection, *Candida albicans* which is seen in diabetics, individuals on steroid therapy, long-term antibiotics, patients who are bedridden, on prolonged ICU care, in infants, and debilitated patients. Initially multiple red spots which are painful appear in the tongue and buccal area which later turn into curdy white patches. Often it extends into pharynx and oesophagus causing dysphagia. It is treated with antifungal drugs like clotrimazole or flucanazole. *Rhagades* occur at corners of mouth in congenital syphilis leaving radiating scar and furrow.
- *Vincent's ulcerative stomatitis* (*Vincent's angina/trench mouth)* is due to infection by Gram –ve anaerobic bacteria *Borrelia vincentii and Fusiformis fusiformis*. It is common in adolescents and young adults below the age of 35 years. Presents with fever, excessive salivation, red swollen gums with painful ulcers covered with yellow slough (*pseudomembrane*) which can be removed like *membrane – ulcerative gingivitis*. From the gums it spreads to cheek, palate, and pharynx. Tongue involvement is uncommon. Tender neck lymph nodes are palpable. *Musty foetor oris* is typical. Edentulous patients will not develop this infection. Infection in tonsillar crypts is called as *Vincent's angina*. It is confirmed by swab culture. It is treated by antibiotics (penicillin group); peeling of membrane, mouth wash, supportive measures, vitamin B and C.
- *Nutritional stomatitis* is due to—(1) vitamin B deficiency like nicotinic acid (pellagra), riboflavin deficiency. It is



Figs 3.2A and B: Sublingual dermoid. It is usually midline. It is not transilluminant. Note the extension into the neck in submental region. Excised specimen is also shown.

common in tongue presenting as red area with atrophy of papillae. (2) Vitamin C deficiency is commonly seen as bleeding gums and loosening of teeth. (3) Iron deficiency anaemia causes superficial glossitis mainly in females.

- *Angular stomatitis* is superficial lengthy red brown fissures/ulcers in and around the angle of the mouth with cracks. Candida and streptococci infections are common. It is often called as *cheilosis/perleche*. It is treated with vitamin B, C, iron and protein supplements with adequate oral hygiene. Perleche is seen in children who suck their finger.

CANCRUM ORIS (NOMA)

- ‘*Noma*’ means—‘to devour’ in Greek—‘eat greedily’ or ‘consume destructively’.
- It is an infective gangrene, a severe form of Vincent‘s acute ulcerative gingivitis and stomatitis.
- Seen in poorly nourished, ill-child due to *Borrelia vincentii* and Fusiformis bacteria.



Fig. 3.3: Severe infection of lip.

> *In the case of malignancy of upper jaw, depression of the angle of the mouth on the affected side is also a typical sign.*
> **—Charles P Wilson**

- It starts in lips later extends to gums, spreads into cheek, bone, soft tissues and skin causing extensive tissue loss with severe toxaemia.
- Extensive necrosis of the mucus membrane of the oral cavity with destruction of deeper soft tissue and often bone.
- In children it may follow after an attack of measles, gastroenteritis, typhoid, bronchopneumonia. Malnutrition is a predisposing factor.
- Excessive salivation, fetid odour with destruction, discharge and toxic features.
- *Borrelia vincentii* can be cultured.
- X-ray part shows bone destruction.
- Condition has got high mortality.
- Secondary infections may also coexist.

***Note*:**
Phagedena is a destructive ulceration with gangrene seen in cancrum oris, chancroid.
(Phagedena is destruction without proliferation but malignancy is destruction with proliferation).

Treatment

1. Systemic antibiotics, high dose penicillins, metronidazole,
2. High protein and vitamin rich diet, through nasogastric tube.
3. Wound irrigation and liberal excision of the dead tissue.
4. Blood transfusion, TPN.
5. Later patient requires flaps to cover the defect.

SYPHILITIC LESIONS OF ORAL CAVITY

Chancre in lip: It is highly contagious primary chancre, presents as painless macule later forming painful superficial ulcer. Ulcer eventually heals with a scar. It can be on both upper and lower lip—*primary syphilis*.

Mucous patches which are greyish white contagious patches seen on lip, cheek and fauces. Mucous patches fuse together to form *linear snail track ulcers* in fauces, pillars—*secondary syphilis*. *Hutchinson's contagious condyloma* in midline tongue can occur.

Gummatous painless ulcer is seen in anterior 2/3rd of tongue, palate and nasal septum (causes perforation and collapse of nasal bridge).

Syphilitic chronic glossitis is seen in *tertiary syphilis* which is a precancerous condition.

LEUKOPLAKIA

It is a white patch in the mucosa of the oral cavity that cannot be characterised clinically or pathologically to any other disease. It is a premalignant condition.

Types

1. *Homogenous*.
2. *Nodular*—more potentially malignant.
3. *Speckled*—more potentially malignant–highest.

Clinically the lesion appears as white or greyish coloured, well-localised patch in the cheek, tongue, palate or other areas of the oral cavity.

Hairy leukoplakia is dense pigmented friable lesion seen in tongue; it is more common in patients with AIDS. There are no hairs (misnomer).

Common causes

- Smoking
- Spirit
- Sepsis
- Superficial glossitis
- Syphilis
- Spices
- Sharp tooth
- Susceptibility
- Pan chewing using areca, tobacco, slaked lime
- Chronic hypertrophic candidiasis (long-standing candida infection)

- ***Incidence of*** leukoplakia in those who smoke or chew pan is 20%, whereas incidence in non-smokers is 1%.
- ***Incidence of*** its turning into malignancy is 2-4%. It increases with age, duration of the pan chewing, smoking.



Fig. 3.4: Leukoplakia right cheek.

- Buccal mucosa and oral commissures are most common sites. Common in males (3:1).
- Leukoplakia of long duration; leukoplakia in elderly; leukoplakia in younger females; leukoplakia in floor of the mouth and tongue; leukoplakia with induration, cracks and fissures are more likely to turn into malignancy.
- ***Histology:*** *Parakeratosis with widening of rete pegs.*

Histological staging

- Acanthosis—elongation of rete pegs—smooth, white, dry patch
- Parakeratosis
- Widening of rete pegs
- Dyskeratosis—keratin cell layer formation deep to epidermis
- Dysplasia
- Carcinoma *in situ*

- Biopsy confirms the diagnosis as well as rules out the carcinoma.



Fig. 3.5: Leukoplakia cheek.

Treatment

- Pan chewing and smoking has to be stopped.
- Excision, if required skin grafting has to be done.
- Regular follow-up is necessary.
- Isoretinoin is helpful. Beta-carotene, tocoferol are also used.
- CO_2 laser excision.

ERYTHROPLAKIA

- It is red velvety appearance of the mucosa which cannot characterise any recognised condition.
- It is 17-20 times more potentially malignant than leukoplakia.
- Histologically *parakeratosis with severe epithelial dysplasia* is the typical feature.



Fig. 3.6: Erythroplakia of cheek.

- Red color is due to decreased keratin causing shining and prominence of submucosal red vascularised connective tissue.
- It is equal in both sexes.
- It is common in lower alveolar mucosa, gingivobuccal sulcus and floor of the mouth.
- It can be homogenous/speckled/granular or erythroplakia interspersed with leukoplakia.
- Diagnosis is done by biopsy.
- *Treatment*: Biopsy and surgical excision.

ORAL SUBMUCOSAL FIBROSIS

- It is a progressive fibrosis deep to the mucosa of the oral cavity which causes *trismus* and *ankyloglossia*.
- The mucosa of cheek, gingivae, palate and tongue shows *a mottled/marbled pallor*.
- It is common among Asians and Indians.
- *Aetiology*: Hypersensitivity to chilli, betelnut, tobacco and vitamin deficiencies probably alter the collagen metabolism leading to juxtaepithelial fibrosis, epithelial atrophy and dysplasia.
- 4.5-7.6% of oral submucosal fibrosis turns into malignancy (Paymaster—1956 study shows 30-33% incidence—very high).
- *Treatment*: Precipitating factors has to be avoided.
- Surgical excision when required, followed by skin grafting, has to be done.



Fig. 3.7: Submucosal fibrosis of right cheek. Note the stiff fibrotic bands and scarring.

Submucosal fibrosis

- Due to:
    - Prolonged local irritation by chilies, tobacco (pan/quid), areca due to arecoline
    - Dietary causes—deficiencies of vitamin A, B complex (riboflavin) and iron
    - Localised collagen disorder
- Racial: It is common among Indians / Asians and people of Indian origin
- Prevalence in India is 5 per 1000
- Incidence is 4-7 %
- Common in middle age; equal in both sexes

- Soreness and burning in mouth which is more during meals; vesicular eruptions; trismus; difficulty in protruding the tongue. Initial red area turns into superficial ulcers which later forms *stiff, fibrotic bands* and scarring.
- Common in soft palate, faucial pillars; buccal mucosa
- Disease is progressive, even after cessation of causative factor like areca use/smoking
- It shows epithelial atrophy, hyperplasia, dysplasia and fibrosis
- *Treatment*—local injection of dexamethasone (4 mg) with hyalase (1500 units) biweekly for 10 weeks; avoidance of irritants; vitamin supplements; correction of anaemia; surgical wide excision and skin grafting

PREMALIGNANT CONDITIONS OF ORAL CAVITY

High risks—lesions with definite risk of malignant change

- Leukoplakia.
- Erythroplakia.
- Chronic hyperplastic candidiasis: It is common in commissures of the mouth and tongue. Dense plaque of leukoplakia is common with curdy white patches due to *Candida albicans* infection. It often may not respond to drugs, surgery or laser. Immunodeficiency is often associated with this. It is treated by topical or systemic antifungal drugs/surgical excision or laser therapy.

Medium risks—premalignant but not associated with higher incidence of carcinoma

- Oral submucosal fibrosis.
- Syphilitic glossitis.
- *Sideropenic dysphagia* (*Sideropenia* is iron deficiency without anaemia); or Plummer-Vinson syndrome. Sideropenia is common in Scandinavian females. It causes atrophy of epithelium and becomes potentially malignant. Proper iron therapy controls the disease and reduces the risk.



Fig. 3.8: Carcinoma cheek with candida (curdy white dots) infection.

Equivocal risk lesions

- Oral lichen planus.
- Dyskeratosis congenital—reticular atrophy, nail dystrophy, leukoplakia in oral cavity.
- Discoid lupus erythematosus.

***Note*:**

- Oropharyngeal cancer is the most common cancer—40% in Indian subcontinent. In western countries, it accounts for 4% only.
- *Risk factors*—tobacco and related products; alcohol; areca nut; human papilloma virus; Epstein Barr virus; *Paterson Kelly syndrome*; nutritional deficiency.
- Patient may develop a second primary (15%) in the oropharynx in different site at same time or within 6 months of the existing primary (*synchronous*—4% prevalence; 20% of second primaries) or after 6 months of first primary (*metachronous*—80% of second primaries). Metachronous second primary is more common than synchronous second primary and it usually occurs in 2 years.



Fig. 3.9: Synchronous oral carcinoma with leukoplakia.

Premalignant conditions of oral cavity

- Leukoplakia
- Erythroplakia
- Chronic hyperplastic candidiasis
- Oral submucosal fibrosis
- Syphilitic glossitis
- Sideropenic dysphagia
- Oral lichen planus
- Discoid lupus erythematosus
- Dyskeratosis congenita

ORAL AND UPPER AERODIGESTIVE CANCERS

- It is one of the commonest cancer in Asian countries and India (40%).
- All 'S' mentioned probably are the causative agents. Smoking, quid of chewing pan are important causes. Tobacco, betel nut, alcohol, human papilloma virus (present in 80% of oral cancers; present in 40% normal individuals), EB virus, vitamin A deficiency, Plummer-Vinson syndrome,

bad dental hygiene, denture irritation—are etiologies. Risk is 8 times in tobacco chewers; 10 times with quid users; 30 times with night quid users.

- Alcohol increases the solubility of carcinogens and suppresses the DNA repair.
- Incidence of oral cancer in India is 28 per 1, 00,000 population. Commonest oral cancer in India is of buccal mucosa (more than 70%).
- In oral cavity, in West, it is common in tongue (50%), buccal mucosa (25%), floor (15%), gums and others (10%).
- Leukoplakia (*commonest*), erythroplakia, chronic hyperplastic candidiasis are *precancerous lesions*; submucosal fibrosis, syphilitic glossitis, sideropenic dysphagia are *precancerous conditions*. Oral lichen planus, discoid lupus, dyskeratosis congenita are doubtful associated lesions. Precancerous lesion is one where cancer is more likely to occur; precancerous condition is one where there is increased risk of cancer.
- Upper aerodigestive cancers include that of oral cavity, larynx and pharynx. Depending on anatomical location they present with different features other than common features—trismus, ear pain, hoarseness of voice, dysphagia, ankyloglossia.
- Usually they are locoregional disease with high affinity to involve regional lymph nodes. Distant spread is rare except in nasopharyngeal carcinoma. Tongue has highest incidence of nodal spread, then floor of the mouth, lower alveolus, cheek, upper alveolus, palate.
- Multiple synchronous (at same time, 10%) de novo sites and or metachronous (at different periods, 15%) multiple sites
- Cancers in posterior third of tongue and floor of the mouth is often missed on clinical examination—*coffin corner or sump area*.
- Primary may be very small to be detected clinically in places like fossa of Rosenmuller, pyriform fossa, nasopharynx, posterior third tongue but present clinically as hard lymph node secondaries in neck called as *secondaries with unknown primary*. Hard secondaries in neck confirmed by FNAC but all investigations including blind biopsies, CT head and neck region and endoscopies could not identify primary lesion creates a situation called as secondaries in neck nodes with an *occult primary (30%)*.
- *Trismus* (pterygoid muscle involvement), *ear pain* due to auriculotemporal nerve involvement, *eye pain* in nasopharyngeal carcinoma, *dysphagia* due to tongue involvement mainly the posterior third, *hearing loss* due to spread to eustachian tube can occur.
- Bronchopneumonia, aspiration are common problems.
- Biopsy, endoscopy, CT neck, MRI, chest X-ray are different investigations needed depending on anatomical location of lesion.
- Staging will help to plan the treatment and predict prognosis.
- *Surgical wide excision and radiotherapy are main modalities of treatment. Chemotherapy is used as an adjuvant*. Curative treatment in early growth with preservation of functions like swallowing, speech, cosmesis; but with adequate oncological clearance is the principle of surgical approach. Radiotherapy is also used as curative therapy.
- Palliative chemotherapy, radiotherapy and surgery can be done depending on location of the lesion.
- Involvement of mandible, neck nodes—number, size and fixity alters the prognosis and treatment schedule.
- Outcome also depends on the anatomical location of the malignancy. Lip carries better prognosis; tongue has poor prognosis.
- General principles used in approaching oral cancers are as follows (however it depends on grading and staging of the tumour):
    - If only primary is present which is mucosal with size less than 2 cm without nodal spread, then wide local excision with supraomohyoid block dissection of same side is done (N0); primary may also be treated with curative brachytherapy or external beam teletherapy. If nodes are histologically positive then radical neck dissection is done.
    - Larger mucosal primary with similar features are also treated similarly; but postoperative RT or/and chemotherapy is added depending on grading of the tumour.
    - In all these types of lesions, if there are positive mobile neck nodes which is confirmed by FNAC, then radical neck dissection should be done.
    - If primary lesion extends into adjacent soft tissue with mandibular involvement then mandibular resection (marginal mandibular/segmental/partial/hemimandibulectomy) is needed. Part is reconstructed using plates or bone graft taken from iliac crest or opposite 11th rib. 2.4 mm reconstruction plate with PMMF or non-vascularised bone graft (iliac crest cancellous chips) or vascularised bone graft from fibula/iliac crest/scapula are the present recommendations. Skin covering is done by split skin graft inside to mucosa or by appropriate flaps depending on the need and feasibility of donor area (PMMF/DP flap/forehead flap). Neck is addressed similarly. Postoperative EBRT and chemotherapy is needed either concurrent or sequential.
    - If primary is advanced then chemotherapy with EBRT is used. If lesion reduces in size and becomes operable it is then operated accordingly.
    - In fixed primary or secondary, RT with chemotherapy is used for palliation to relieve pain, fungation, sepsis.
- In advanced stage terminal events may be severe malnutrition, bleeding, sepsis, and bronchopneumonia.
- Posterior lesions has got poor prognosis than anterior lesions. Lip carries best. Prognosis depends on anatomical location, grading, lymph node status, soft tissue involvement and response of therapy.

Carcinoma of Gingivobuccal Complex

- It is cancer (SCC) involving *buccal mucosa and gingiva* etiology of which is keeping tobacco quid in gingivobuccal sulcus.

- It is often called as *Indian oral cancer* as it is most commonly seen in India.
- Buccal mucosa extends from upper to lower alveolus; from commissure in front to retromolar region behind.
- Features, management are same. Marginal mandibulectomy/segmental resection is commonly needed.
- Adjuvant RT and chemotherapy is useful.

CHEEK

Anatomy of Cheek

- They are fleshy flaps on either side of the face. The demarcation between the lips and cheek is nasolabial fold.
- It is composed of skin, superficial fascia with parotid duct, buccinator muscle, submucosa with buccal glands and mucous membrane.
- Lymphatics: Submandibular and pre-auricular nodes.



Fig. 3.10: Haemangioma cheek.

Retromolar Trigone

- It is the mucosa on the anterior surface of the ascending ramus of the mandible. It is triangular in shape with the base being superior and apex inferiorly behind the third molar tooth.
  - Malignancy in this area commonly invades the ascending ramus of the mandible, often to soft palate and tonsillar fossa. It is also said that lymphatics here communicates with pharyngeal lymphatics in this region. Lip split or mandibulotomy approach is needed in these patients.

CARCINOMA CHEEK/BUCCAL MUCOSA

Squamous cell carcinoma is the most common type of carcinoma of the cheek.



Fig. 3.11: Carcinoma buccal mucosa. It is the most common oral cancer in India.

- Occasionally it can be adenocarcinoma arising from the minor salivary glands or mucous glands. Rarely it can also be melanoma.

Malignancies of the oral cavity

- *Squamous cell carcinoma—commonest*
- Minor salivary gland tumours
- Melanomas
- Adenocarcinomas—rare
- Sarcomas—rare (Sarcomatoid)
- Basaloid SCC

Sites of carcinoma in oral cavity in order

In India	*In Western countries*
Cheek—commonest	Tongue
Tongue	Floor of the mouth
Floor of the mouth	Lip
Palate	Cheek
Lips	

Precipitating Factors

All 'S'—Smoking, spirit, syphilis, sharp tooth, sepsis, spices.

Incidence of oral cancer is six times more in smokers than nonsmokers.

Premalignant lesions and conditions

- Leukoplakia
- Erythroplakia
- Chronic hyperplastic candidiasis
- Oral submucosal fibrosis
- Sideropenic dysphagia
- Syphilitic glossitis



Figs 3.12A to D: Carcinoma cheek in different patients. Note the usage of tongue depressor for proper visualisation of the lesion.



Fig. 3.13: Trismus in a patient with advanced carcinoma cheek (T4 lesion). Patient is on chemotherapy and so developed alopecia.

Betel nut chewing (*Pan*, with *pan quid* kept in cheek pouch for a long time) is an important causative factor of carcinoma cheek.

Betel/areca nut, betel leaf, slaked lime, and tobacco (often with catechu and condiments) wrapped in betel leaf is repeatedly chewed after putting into the mouth; and the *quid* formed is kept for long duration in gingivolabial sulcus; which is said to be highly carcinogenic. Tobacco is the main carcinogenic component, followed by arecoline (stimulate collagen synthesis and fibroblast proliferation) and tannin (stabilizes collagen) alkaloids of areca.

Types

- Ulcerative
- Proliferative (exophytic)
- Verrucous



Figs 3.14A and B: Betels commonly used to prepare quid which is kept in gingivoalveolar groove. It is common cause for carcinoma oral cavity.

Verrucous Carcinoma

- It occurs as a superficial proliferative exophytic lesion with minimal deep invasion, often multiple.
- Lesion has white, dry, velvety or warty, keratinised surface. It is common in females.
- It is of low grade, very well-differentiated squamous cell carcinoma, which is locally malignant without any lymphatic spread.
- It is a curable malignancy.
- After biopsy treatment is *wide excision. Radiotherapy* is not given as it may lead to poorly differentiated carcinoma.



Fig. 3.15: Verrucous carcinoma of oral cavity at gingiobuccal sulcus with leukoplakia.

Biological Behaviour of Carcinoma Cheek

- Carcinoma is common in posterior half of cheek than anterior.
- It spreads into the deeper plane to involve buccinator, pterygoids; into the retromolar trigone, base of the skull, pharynx.
- It spreads outwards to involve the skin causing fungation, ulceration, orocutaneous fistula formation.
- Mandible is commonly involved either by direct extension or through subperiosteal lymphatic plexus which communicates freely with oral lymphatics.
- Lymph nodes commonly involved are submental, submandibular, deep cervical and often lateral pharyngeal groups. Nodal spread is seen in 50% of cases.
- Infection of the tumour area and soft tissues around is common, causing fever, foul smelling ulcer, halitosis.
- Respiratory infection is common in these patients.
- Once tumour extends into the retromolar region, soft palate and pharynx, dysphagia will occur.
- Lesion will later spread to involve alveolus.



Fig. 3.16: Recurrent carcinoma cheek in an operated case.

Clinical Features

- *Ulcer* in the cheek which gradually increases in size in a patient with history of chewing pan and smoking is the commonest presentation and initially it is painless.
- *Pain* occurs when it involves the skin, bone or if secondarily infected. Referred pain to the ear signifies involvement of lingual nerve. Lingual and auriculotemporal nerves arise from mandibular division of trigeminal nerve.
- *Halitosis* which is bad odour breath is common in many oral cancers. It is due to necrosis of tumour, release *of mercaptan*, butyric acid and ammonia.
- *Involvement of retromolar trigone* indicates that it is an advanced disease, as the lymphatics here communicate freely with the pharyngeal lymphatics.
- *Everted edge, induration* are the typical features of the ulcer.
- Mandible is examined bidigitally, for thickening, tenderness, irregularity and sites of fracture. Mandible may get involved by direct extension, through mandibular canal, or through periodontal membrane. Loss of central part of mandible due to destruction by tumour will cause pouting of lower lip with drooling of saliva—*Andy Gump* deformity. Mandibular canal is close to occlusive alveolar surface in *elderly and edentulous* patients to cause early mandibular spread in carcinoma.
- *Trismus and dysphagia* signify involvement of pterygoids or posterior extension.
- Occasionally it may extend into the *upper alveolus and to the maxilla* causing swelling, pain and tenderness.
- Once involvement of soft tissue occurs, it may come out through skin as fungating lesion often with orocutaneous fistulas with saliva dribbling through fistula.
- Submandibular lymph nodes and upper deep cervical lymph nodes are involved which are hard and nodular; initially mobile and later get fixed to each other and then to deeper structure.
  - Once lymph nodes get fixed it may infiltrate into hypoglossal nerve (tongue will deviate towards the same side), spinal accessory nerve (defective shrugging of shoulder) and cervical sympathetic chain (*Horner's syndrome*).
  - Compression over external carotid artery leads to absence of superficial temporal artery pulsation.
  - Eventually it causes fungation and bleeding from major vessels—*-**carotid blow out.***

***Note*:**
Node involvement may be due to infection. So often trial antibiotic is given initially.



Figs 3.17A and B: Advanced carcinoma cheek presenting as swelling outside. There is an ulcer inside over the mucosa.

Staging (for all oral cancers)

TNM Staging

T_0	No evidence of primary tumour
Tis	Carcinoma in situ
T_1	Tumour size < 2 cm—greatest dimension
T_2	Tumour size 2-4 cm
T_3	Tumour > 4 cm
T_4	Tumour is of any size involving bone, soft tissues, muscles
Nx	Nodes cannot be assessed
N_0	No lymph node spread
N_1	Lymph node size < 3 cm, same side
N_2	Lymph node size 3-6 cm and single (*N2a*); multiple lymph nodes 3-6 cm size on same side (*N2b*); bilateral or opposite side nodes up to 6 cm size (*N2c*)
N_3	Lymph node spread, more than 6 cm size

Stages

Stage I – T1,N0,M0.
Stage II – T2,N0,M0.
Stage III – T3,N0,M0; T1-3,N1,M0.
Stage IV – T4,N0,M0; T1,N2-3,M0; T0,N0,M1.

Fissuring of tongue due to ariboflavinosis is longitudinal and the bottom of fissure is beefy red.

—Dimitri Afonsky



Figs 3.18A to C: Carcinoma cheek fungating outside extensively. Note the pigmentation in one of the pictures.



Figs 3.19A and B: Advanced carcinoma cheek with fungation and orocutaneous fistula.



Fig. 3.20: Oral cavity carcinoma with mandibular involvement, with T4 lesion.

Features of advanced carcinoma cheek

- Involvement of retromolar trigone
- Extension into the base of skull and pharynx
- Fixed neck lymph nodes
- Extension to the opposite side

Problems with oral carcinomas

- Upper airway obstruction and bronchopneumonia
- Feeding difficulties and severe malnutrition
- Immunosuppression
- Secondary sepsis, uncontrollable bleeding
- Fixity of secondaries, fungation and disability
- Psychological trauma
- When once trismus develops, patient is unable to take adequate food and eventually leads into cancer cachexia. Trismus may develop by tumour infiltration or after RT.
- Orocutaneous fistula causes salivary dribbling which is distressing.

Investigations

1. *Edge biopsy*, usually taken from two sites. Biopsy has to be taken from the edge as it contains active cells; not from the centre as it is the area of necrosis. *Malignant squamous cells with epithelial pearls (Keratin pearls)* are the histological features.

***Note*:**
Biopsy from the centre is taken only from postradiotherapy ulcer and ulcerated minor salivary gland tumours.

Broder's histological grading

a. Well-differentiated: > 75% epithelial pearls
b. Moderately differentiated: 50-75% epithelial pearls
c. Poorly differentiated: 25-50% epithelial pearls
d. Very poorly differentiated: < 25% epithelial pearls

2 FNAC from lymph nodes.
3. CT scan is used to assess the extent of tumour into mandible, pterygoid region, in patient with trismus, with neck lymph nodes, with carotid involvement by lymph nodes.
   MRI is very useful in assessing the soft tissues, base of skull, and perineural spread.



Fig. 3.21: Normal orthopantomogram. OPG is a must in all oral carcinomas to stage the disease and to plan the treatment.



Fig. 3.22: Orthopantomogram showing secondaries in mandible.

4. Orthopantomogram to look for the involvement of mandible—destruction and fracture sites. Symphysis menti and lingual plate are not clearly appreciated. So often OPG may be supported with dental occlusion and intraoral X-rays.
5. Opinion and help of dentist is taken for teeth extraction, dental care, for prosthesis preparation especially for palate, alveolus, dentures.

***Note*:**
Open biopsy should be avoided in case of secondaries in lymph nodes as it may aggravate the spread to further level of lymph nodes.

Treatment

Treatment may be ***curative*** or ***palliative***.

Treatment Strategy

- ***Surgery***. Wide excision, hemimandibulectomy, neck lymph nodes block dissection.
- ***Radiotherapy:*** Curative or palliative; external or brachytherapy.
- ***Chemotherapy:*** Intraarterial, IV or orally.

a. ***Early growth without bone involvement:***
   1. *Curative radiotherapy* using ^{137}Caesium needles or ^{192}Iridium wires, i.e. brachytherapy.
      Advantages:
         i. Surgery is avoided.
         ii. No surgical mutilation.

Indications for surgery	*Advantages*	*Disadvantages*
• Early tumour • Tumour spreading to mandible bone/ alveolus • Fungation, haemorrhage due to erosion • Recurrence of tumour after RT • Multiple sites • Soft tissue spread • Locally advanced but amenable to surgical resection	• Pain is controlled • Often curative • Fungation, ulceration, bleeding is prevented	• Mortality (5%) • Morbidity, sepsis, flap necrosis, fibrosis • Cosmetic problem • Loss of anatomy and its function



Fig. 3.23: Patient who has undergone hemimandibulectomy with primary closure. Note the defect.



Fig. 3.24: Hemimandibulectomy, resected specimen (*Courtesy:* Dr. Jagadish Chandra, MDS).



Fig. 3.25: *Patterson incision* to approach carcinoma cheek by raising skin flaps from lower part of face adjacent to lower margin of the mandible.

iii. Parts are retained.

iv. As it is a squamous cell carcinoma, primary is radiosensitive—90% cure rate.

2. Other option is *wide excision with 1-2 cm clearance*. Often, the approach to the tumour is by raising the cheek flap (outside). After the wide excision, the flap is placed back ***(Patterson operation)***.
3. Presently advanced technology in radiotherapy, facilitates the use of external radiotherapy also. The incidence of dreaded complication like *osteoradionecrosis of mandible* has been reduced due to better RT methods.

b. ***Growth with mandible involvement:***
Here along with wide excision of the primary tumour, hemimandibulectomy or segmental resection of the mandible or marginal mandibulectomy (using rotary electric saw) is done.

c. ***Operable growth with mandible involvement and mobile lymph nodes on the same side*** (confirmed by FNAC):
Along with wide excision of the primary, hemimandibulectomy and radical neck lymph node dissection is done (like commondo operation).
Wide excision of primary lesion, hemimandibulectomy with radical neck node dissection is called as *composite resection*.

d. ***Operable growth with mandible involvement; mobile lymph nodes on same side and opposite side:***
Along with wide excision of the tumour, hemimandibulectomy, radical neck lymph node dissection on same side and functional block dissection on opposite side are done, retaining the internal jugular vein, sternomastoid, spinal accessory nerve.

e. ***Operable primary tumour with mobile lymph nodes on same side but without mandibular involvement:***
Wide excision of primary tumour and radical neck lymph node dissection on same side are done. Mandible is not removed.



Figs 3.26A to C: Lip-split incision approach for carcinoma cheek. It gives adequate exposure of the cheek. Lower extension is for neck block dissection.



Fig. 3.27: Defect in the cheek after wide excision for carcinoma cheek. Defect needs coverage using PMMF with skin graft inside (*Courtesy*: Professor Kishore Chandra Prasad, ENT Surgeon and Head of the Department and Dr Sampath, ENT Surgeon, KMC, Mangalore).



Fig. 3.28: Specimen showing primary tumour in cheek with mandible (hemimandibulectomy) and block dissection nodes.

f. ***Fixed primary tumour or advanced neck lymph node secondaries:***
Only palliative *external radiotherapy* is given to palliate pain, fungation and to prevent anticipated torrential haemorrhage.

g. ***Preoperative radiotherapy is often used in fixed lymph nodes to downstage*** the disease so as to make it operable.

Halitosis is better breath than no breath at all !!!



Fig. 3.29: Segmental resection of the mandible (angle of mandible to mental foramen).



Fig. 3.30: Hemimandibulectomy.



Fig. 3.31: *Visor approach* for oral malignancy. Visor approach for anterior mandible, floor of the mouth and tongue. Here skin over the anterior curved margin of the mandible is incised to approach the floor of the mouth for needed procedure.



Fig. 3.32: Partial mandibulectomy is removal of mandible one side from mental foramen to line of coronoid process including coronoid process but leaving condylar process.



Fig. 3.33: Carcinoma cheek operated with radical neck dissection of same side lymph nodes. Reconstruction done using pectoralis major myocutaneous flap.

h. ***Postoperative radiotherapy is given in T_3 and T_4 tumours:*** N_2 and N_3 nodal status to reduce the recurrence and to improve the prognosis (in multiple nodes and nodes with extracapsular spread).

i. ***Prophylactic block dissection has become popular in N_0 diseases.***

Reasons are—even though clinically, lymph nodes are negative, there may be microscopic involvement of lymph nodes (25-65%).

- Clinically detectable disease in lymph nodes of the patient signifies extracapsular spread which has got poor prognosis.
- Recurrence rate is less after prophylactic block compared to block dissection with clinically positive nodes because



Figs 3.34A and B: Pectoralis major myocutaneous flap to cover the defect in the cheek after wide excision (*Courtesy:* Professor Kishore Chandra Prasad, ENT Surgeon and Head of the Department and Dr Sampath,ENT Surgeon, KMC, Mangalore).



Fig. 3.35: Marginal mandibulectomy.



Fig. 3.36: Rim resection of mandible done for carcinoma floor of the mouth.

there is no extracapsular spread in the former even if there is microscopic spread of tumour in many cases.

- Block dissection is an acceptable surgery as there is negligible mortality and less morbidity.
- It is advocated in T3, T4 lesions, carcinoma alveolus or floor of the mouth.

j. ***If growth is extending to upper alveolus:***
Partial maxillectomy or total maxillectomy may be required.

k. ***Role of chemotherapy:***
Drugs used are methotrexate, cisplatin, vincristine, bleomycin, adriamycin. Often it is given intraarterially through external carotid artery using arterial pump or by increasing the height of the drip more than 13 feet, so as to attain a pressure more than systolic pressure. Chemotherapy can also be given IV or orally - postoperatively.

l. Initial chemotherapy to downstage the tumour followed by surgery and later again end with chemotherapy.

m. Chemoradiotherapy is used in unresectable tumours – as consecutive therapies.

Reconstruction after Surgery

Flaps used for reconstruction after oral surgery

- ❖ Forehead flap based on superficial temporal artery
- ❖ Deltopectoral flap based on 1, 2 and 3 perforating vessels from internal mammary vessels
- ❖ Pectoralis major myocutaneous flap (PMMF) based on thoracoacromial artery
- ❖ Free microvascular flaps may be from radial artery forearm flap
- ❖ For small defects—tongue flap, buccal flap, palatal mucoperiosteal flap

- Split skin graft.
- Deltopectoral cutaneous flap.
- Forehead flap, radial artery forearm flap.
- Pectoralis major myocutaneous flap.
- Mandible reconstruction by cortical bone graft or rib, fibula or synthetic material like titanium, stainless steel plate.

In great attempts, it is glorious even to fail.



Figs 3.37A and B: Reconstruction of the mandible after segmented mandibulectomy using plate and opposite rib fixation (*Courtesy*: Jagadish Chandra, MDS).



Fig. 3.38: Harvesting fibular flap for mandibular reconstruction. (*Courtesy*: Dr Satish Bhat, MCh, Plastic Surgeon, Mangalore).

Approaches to Carcinoma Cheek

- Transoral/intraoral approach.
- Lip split incision.
- Patterson approach.
- *Visor approach* for anterior mandible, floor of the mouth and tongue. Here skin over the anterior curved margin of the mandible is incised to approach the floor of the mouth for needed procedure. (Visor is French derived word which means mobile lower part of the helmet which covers the chin).

Different mandibular resections

- Marginal mandibulectomy
- Partial mandibulectomy
- Segmental resection
- Hemimandibulectomy
- Rim resection of mandible
- Resection of the anterior mandible through visor approach

Marginal Mandibulectomy

- It is in continuity wide excision of tumour with gingival and adjacent margin of the mandible.
- Superior margin is removed using electric saw after proper marking leaving at least 1 cm of inferior margin.
- It is done in lesion which is close to mandible but not invading. Invasion needs segmental resection. Invasion is invariably through dental root leading into mandibular canal and cancellous bone.
- Mandibular involvement either clinically or radiologically, previous RT, retromolar lesion (as pterygoid clearance is needed here) are the contraindications.

Problems with surgery

- Mutilation (surgical)
- Anaesthesia complications
- Bleeding
- Infection
- Flap necrosis
- Requirement for reconstruction
- Mortality
- Morbidity—stiffness; contracture; cosmetic problem; cutaneous anaesthesia; speech and swallowing problems
- Problems of neck dissection—hypoglossal, accessory, phrenic nerve injuries; thoracic duct injury, carotid blow out; oedema neck and face



Fig. 3.39: Carcinoma cheek, on table wide excision. It requires pectoralis major myocutaneous flap for reconstruction.



Fig. 3.40: Radical neck dissection for secondaries in neck through MacFee incision.



Fig. 3.41: Radiodermatitis after RT to tonsillar growth.

Problems with radiotherapy

- When mandible is irradiated, chances of the dreaded problem, osteoradionecrosis is high which requires the removal of mandible
- Loss of taste sensation and dryness, xerostomia
- Infection, mucositis, dental diseases
- Skin excoriation, hair loss
- Trismus may get aggravated
- Can itself cause dysphagia, laryngeal oedema
- Hypothyroidism if neck is irradiated
- Radiation neuritis causing severe pain
- Carotid artery atherosclerosis
- Visual impairment
- Shoulder and neck dysfunction
- Soft tissue fibrosis

Problems with chemotherapy

- Bone marrow suppression
- Megaloblastic anaemia
- GIT symptoms
- Hepatotoxicity and renal toxicity
- Alopecia
- Nausea, vomiting and severe stomatitis

Prognostic factors in oral carcinomas

- Stage of the disease
  - Stage I and II has got 80% 5 years survival
  - Stage III and IV has got less than 20% 5 years survival rate
- T3 and T4 lesions has got poor survival rate
- Carcinoma lip has got best prognosis
- Carcinoma posterior 1/3rd tongue has got worst prognosis
- Cheek, floor of the mouth and palate has got intermediate prognosis
- Perineural invasion and angioinvasion carries poor prognosis
- Histologically positive nodes decrease the survival rate by 50%
- Level III and IV, node > 3 cm, bilateral nodes extracapsular nodal spread are poor prognostic factors
- Grading (differentiation) of the tumour
- Tumour thickness > 6 mm has got poor prognosis
- Exophytic tumour is better than infiltrating type



Fig. 3.42: Forehead flap is used after wide excision of carcinoma cheek. It is based on superficial temporal artery—anterior branch.


Donor area covered with SSG
Forehead flap rotated towards upper lip defect
A
B

Figs 3.43A and B: Forehead flap used to cover the defect after wide excision for carcinoma lip or cheek (*Courtesy:* Professor Kishore Chandra Prasad, ENT Surgeon and Head of the Department and Dr Sampath, ENT Surgeon, KMC, Mangalore).



Fig. 3.44: Deltopectoral flap used to cover defect after surgical clearance in carcinoma cheek. It is based on 2nd perforator, a branch of internal mammary artery (*Bakamjian—1965*).



Figs 3.45A and B: Mucositis in cheek and lip in a patient who is receiving chemotherapy for carcinoma.

LIP

Lip begins at vermilion border. It has got upper lip, lower lip and oral commissure. SCC is the commonest lip cancer (90%). SCC is common in lower lip; BCC is common in upper lip. Other cancers in lip are spindle cell carcinoma, adenoid squamous carcinoma, malignant melanoma, minor salivary gland tumour.

Mucous cyst of lip is a common condition. It can occur in upper or lower lip. It is a retention cyst derived from mucous glands of the lip. It presents as bluish, soft, fluctuant often transilluminating well localized swelling. It may resolve on its own. If it does not it should be excised under local anaesthesia. Absorbable suture is used to appose the wound starting from vermilion margin. Usually vertical elliptical incision is used to excise. Sutured wound heals rapidly with very limited scar.

Macrocheilia is enlargement of lip mass in other than neoplastic conditions. Lymphangioma is the common cause. Haemangioma, inflammatory conditions also can cause macrocheilia.

Papilloma, lipoma, pyogenic granuloma, keratoacanthoma, minor salivary tumours are other swellings which can occur in lip.

Cheilitis often associated with stomatitis is common in vitamin deficiency, malnutrition, sepsis, drug induced, RT induced presents as redness, pain, diffuse swelling. In chronic cases, there will be linear ulcers especially at commissure. *Actinic cheilitis* is a premalignant lesion. Cause is treated.

Pigmentation of lip occurs in Peutz-Jeghers syndrome (brown), Addison's disease (black).

Herpes labialis is formation ulcers in lip due to herpes simplex virus. Repeated multiple ulcers develop in lip. It is contagious by kissing. So kissing should be avoided including children. Touching repeatedly can transfer the virus to eye causing herpes keratitis.

Cleft lip is a common congenital condition.



Fig. 3.46: Mucous cyst upper lip. It requires simple excision. It is a retention cyst.



Figs 3.47A and B



Fig. 3.47C

Figs 3.47A to C: Mucous cyst seen in lower lip. It is bluish, localised, smooth, nontender, soft, fluctuant swelling, arising as a retention cyst from mucous glands of lip. It needs excision.



Figs 3.48A and B: (A) Haemangioma lip causing macrocheilia. (B) Macrocheilia due to inflammatory cause.



Fig. 3.49: Aphthous ulcer lower lip. It is painful, self limiting ulcer. It can occur in tongue, lip, cheek and other parts of the oral mucosa.

NEOPLASM OF LIP

> *One may…cure cancers of the lip without applying caustics or any similar thing….Pass a threaded needle through the cancer so the thread held in the left hand can lift and control the cancer without any of its escaping. One can then cut to good flesh with scissors in the right hand; and so cut that a layer of good flesh of the lip remains to serve as a base and foundation for regeneration of flesh in place of the portion amputated, supposing the cancer has not taken root and spread from top to bottom.*
>
> —**Ambroise Paré,** 1585

*Minor salivary gland tumour*s are common in upper lip. They are usually pleomorphic adenomas.

CARCINOMA LIP

- Incidence of carcinoma lip is 15% of head and neck cancers and 1% of all cancers.
- It may arise from vermilion surface or mucosa part of the lip.
- It is common after 40 years of age. In younger age group even though it is rare, carries poor outcome.
- It is more common in whites; rare in blacks. It is common in *Caucasians*.
- Khaini, a mixture of tobacco and lime kept under the lip called as *khaini chewers* are more susceptible for carcinoma lip.
- All'S's and irradiation are predisposing factors.
- *Verrucous carcinoma* can occur in lip. It is well differentiated SCC with exophytic, warty, dry surface. It usually will not invade the deeper tissue and lymph node spread is rare. It carries good prognosis.
- It is common in men (15:1). Common in *lower lip* (90%); upper lip 5-10%. Upper lip is not exposed to direct actinic radiation.
- Commonly due to exposure to sunlight (ultraviolet rays). Common in pipe smokers.
- Initially starts as a red, granular dry lesion which eventually gets ulcerated and forms an ulceroproliferative lesion. Occasionally it occurs at the angle of mouth.
- It spreads to submental nodes and later to other neck nodes on both sides.



Figs 3.50A to C: Carcinoma of lip involving extensively.



Figs 3.51A to C: Carcinoma lip.

- Usually it is a *well-differentiated squamous cell carcinoma*.
- Commissure tumours are 2% of all lip cancers but has higher rate of lymph node spread.
- Initially it is well localized. A depth of more than 5 mm will spread to lymph nodes mainly submental and submandibular (level I).
- Painless ulcerative lesion is the most common presentation. Pain develops once necrosis occurs or tumour infiltrates nerve, periosteum of bone underneath.
- Pigmented SCC can occur. It mimics melanoma.
- *Anaesthesia of chin* can occur if mental nerve is invaded.
- Staging is same as other oral cancers.

Clinical features of carcinoma lip

- Non-healing progressive ulcer, painless to begin with
- Everted edge with indurations
- Growth moves with the lip
- Submental, submandibular and upper deep neck nodes may get enlarged.
- Tender firm lymph node may be due to infection; hard initially nontender node is due to carcinoma spread.
- In half of the cases lymph nodes are enlarged due to infection or as reactive process
- Fungation, bleeding, halitosis

Predisposing Factors

- Cheilitis—actinic type
- Solar keratosis.
- Papilloma.
- Leukoplakia.
- Smoking, U-V rays, pipe smokers, reverse smoking.
- Tobacco chewing, Khaini chewers (tobacco+lime).
- Agriculturists who are commonly exposed to sunlight get carcinoma lip and is called as *countryman's lip*.

Differential Diagnosis

- Keratoacanthoma.
- Basal cell carcinoma. BCC occurs only in upper lip.
- Minor salivary gland tumours.
- Often carcinoma of lip is an extension from carcinoma of cheek.
- Pyogenic granuloma in early cases only.
- Malignant melanoma in case of *pigmented SCC*.



Figs 3.52A to C: Carcinoma lip involving different parts. Commonly they are squamous cell carcinomas.

Diagnosis

Edge biopsy, FNAC of lymph nodes.



Fig. 3.53: Carcinoma lip extending into the floor of the mouth.

Treatment

- If lesion is less than 2 cm, then curative radiotherapy, either brachytherapy or external beam radiotherapy. It gives a good cure.
- If tumour is more than 2 cm, wide excision is done. Excision of lower lip up to one-third can be sutured primarily, in layers keeping vermilion border in proper apposition without causing any microstomia.
- Excision of more than one-third of the lip requires reconstruction using different flaps.

Methods

1. *Abbe-Estlander's rotation flap* used for either upper or lower lip lesions (of less than ½ of lip) located *at the angle* based on labial artery. Here base at a later stage need not be disconnected unlike in Abbe lip.
2. *Fries' modified Bernard facial flap*—reconstruction using lateral facial flaps. It is used when defect is more than ½ of lip and midline.



Fig. 3.54: Primary repair of lip after wide excision of small tumour. One-third of the lip can be sacrificed. Lip is sutured in layers. First layer, muco-muscular layer with absorbable suture. Second layer is skin with non-absorbable monofilament sutures like polypropylene.



Fig. 3.55: Lower lip tumour after excision when primary suturing not possible, then upper lip flap based on upper labial artery can be used – *Abbe-Estlander flap.*

3. Microvascular flaps.
4. *Nasolabial flap*: It is used when defect is more than ½ of lip laterally or defect is in the floor of the mouth.
5. Cheek flap.
6. Free radial artery flap.
7. *Abbe flap* (switch flap) is used for upper or lower lip lesions at the *middle* or at the site *other than angle* based on the labial artery. Here at a later *2nd stage* base of the flap should be released once flap takes up.
8. *'W' flap plasty*: It is done for lower lip middle tumour which is less than 1/3rd of the lip.
9. *Gillies fan flap*: It is a cheek flap usually bilateral but can be unilateral. Incision is full thickness around commissures extending into nasolabial fold and upper lip upto upper lip vermilion border. Flap which is based on labial vessels is advanced towards the defect. Vermilion is reconstructed with tongue mucosal flap which is divided in 3 weeks.
10. *Karapandzic flap*: It is modified version of the Gillies flap used for lower lip defect with less angulation towards upper lip. Reverse Karapandzic flap is used for upper lip defect.
11. *Johansen 'stepladder'* procedure is used for extensive carcinoma of lower lip.
12. Other regular flaps like forehead flap, deltopectoral flap also can be used.
    - Lymph nodes are dealt with by radical neck dissection on one side and functional block or supraomohyoid block dissection on other side. For central tumour N_0 disease, bilateral elective (prophylactic) supraomohyoid dissection is done. For lateral tumour N_0 disease, elective ipsilateral supraomohyoid dissection is done.
    - Postoperative radiotherapy is given if tumour is large or if lymph nodes are involved.
    - When mandible is involved, segmental resection is done.


Abbe flap
Tumour
A
Excised bed
Rotated flap
Donor flap area
B
Rotated flap
Excised bed
Donor flap area
C
Rotated flap
Donor flap area
D
Suture lines
E

Figs 3.56A to E: For upper lip tumour when primary repair is not possible, then lower lip flap based on inferior labial artery can be rotated to upper lip—*Abbe flap*.


Burrow's triangles
Tumour removed defect

Fig. 3.57: It is used for central lip tumours. Angles of the lower part of the defect and upper part of the angles of the mouth are rotated inwards with Burrow's triangles at the site of rotation—*Bernard flap.*


Tumour
'W' flap

Fig. 3.58: It is done for lower lip middle tumour which is less than 1/3rd of the lip—*'W' flap*.

Anything the mind of man can conceive and believe, it can achieve.


Tumour removed
Gillies fan flap
A
B

Figs 3.59A and B: *Gillies fan flap*.


Inferiorly based nasolabial flap bilateral
A
B
Tumour in the floor of the mouth removed leaving a defect
Flap rotated into the defect in the floor of the mouth

Figs 3.60A and B: Nasolabial flap used in extensive lower lip defect or over the defect after wide excision of a tumour in the floor of the mouth.

Prognosis

- Prognosis is good, 5 years survival is 70%.
- Lip has best prognosis.
- Nerve involvement, fixation, nodal spread, upper lip or commissure lesions, age less than 40 years—are poor prognostic factors.

TONGUE

Anatomy of Tongue

Tongue is a muscular organ located in the floor of the mouth.

Parts

1. *Tip*: Anterior free end lies behind the upper incisor teeth.
2. *Root*: Attached to the mandible above and hyoid bone below.
3. *Body*: Dorsal surface is rough due to papillae; and is divided into anterior 2/3rd (oral part) and posterior 1/3rd (pharyngeal part) by *sulcus terminalis*. Ventral surface is smooth, has a median fold, *'frenulum linguae'* and deep lingual vein on either side.


Epiglottis
Median GE fold
Vallecula
Lateral GE fold
Lymphoid nodules
Sulcus terminalis
Circumvallate
Foliate
Fungiform
Filiform

Fig. 3.61: Anatomy of the tongue showing parts and papillae.

Papillae

1. *Vallate*—large, located in front of sulcus terminalis.
2. *Fungiform*—lies over the tip and margin of the tongue.
3. *Filiform*—lies over the dorsum of tongue, gives the velvety appearance—commonest.
4. *Foliate*—over the margin.

Muscles of Tongue

a. Intrinsic muscle: Superior and inferior longitudinal, transverse and vertical.
b. Extrinsic muscle: Genioglossus, hyoglossus, styloglossus, palatoglossus.

Blood supply is from lingual artery, a branch of external carotid artery. Venous drainage by deep lingual vein which drains into fascial vein or internal jugular vein.

Movements of the tongue

- ❖ Forward protrusion—genioglossus—most commonly affected by carcinoma
- ❖ Backward movement—styloglossus
- ❖ Elevation of tongue—palatoglossus
- ❖ Depression of tongue—hyoglossus

Lymphatic Drainage of the Tongue

- Tip of tongue drains into submental lymph nodes.
- Lateral margin drains to submandibular lymph nodes and into upper deep cervical lymph nodes. Many lymphatic vessels pass as subperiosteal lymphatics of mandible. So carcinoma can involve the bone through this route.
- Lymphatics in the midline of tongue freely cross communicate with each other and so spread of malignancy can occur to both side neck lymph nodes.



Fig. 3.62: Severe superficial glossitis.

- Lymphatics from posterior third of tongue drain into pharyngeal group of lymph nodes, as well as to the upper deep cervical lymph nodes. Early spread to the pharyngeal lymph nodes from carcinoma of posterior third of tongue has a poor prognosis.

Lymphatic vessels are named as:

1. Apical vessels.
2. Central vessels.
3. Marginal vessels.
4. Basal vessels.

Development and Nerve Supply of the Tongue

- *Anterior 2/3rd* develop from first branchial arch through two lingual swellings and one tuberculum impar. It is supplied by lingual nerve for general sensation and by chorda tympani for taste sensation.
- *Posterior 1/3rd* develops from third arch from cranial half of hypobranchial eminence. It is supplied by glossopharyngeal nerve for both general and taste sensations.
- *Posterior most part* develops from the fourth arch. It is supplied by vagus nerve (internal laryngeal nerve).
- *Muscles of the tongue* are derived from occipital myotomes and are supplied by hypoglossal nerve except palatoglossus, which is supplied by cranial part of accessory nerve.

TONGUE ULCERS

Differential diagnosis for tongue ulcers

- Dental ulcers—painful
- Aphthous ulcers—painful
- Ulcers in lichen planus—painless
- Syphilitic ulcers—painless
- Tuberculous ulcers—painful
- Malignant ulcers—painless

Dental Ulcer

It is common on sides of tongue due to sharp tooth, denture, and broken tooth. Usually it is acute painful, self limiting ulcer. Occasionally repeated trauma form an indolent chronic ulcer which mimic carcinoma; it should be excised to rule out carcinoma and to cure the ulcer.

Aphthous Ulcer

It can be (1) *Minor* aphthous ulcer, common in menstruating women as a crop with painful, round, yellow based ulcer with red margin. It regresses spontaneously in 2 weeks. (2) *Major* aphthous ulcer, large and deep which often becomes chronic and takes more time to subside with a scar. Chlorhexidine gluconate, local application of triamcinolone acetate, choline salicylate gel are different local applicants used to promote healing. (3) *Behcet's syndrome* is genital ulcer, conjunctival ulcer and multiple oral ulcers. *Reiter's syndrome* is urethritis, arthritis, periarteritis nodosa, conjunctivitis, and oral ulcers. (4) Herpetiform aphthous ulcer is not due to herpes simplex. They are small, 1-2 mm diameter ulcers in crops which heal by usual drugs mentioned above.

Syphilitic Ulcer

Extragenital chancre often occurs in tongue in *primary syphilis* which is painless with shotty, submental and submandibular lymph nodes. *In secondary syphilis*, multiple shallow snail track ulcers in the margins and undersurface; mucous patches on the tongue and fauces; *Hutchinson's condyloma* wart in midline of tongue can occur. *In tertiary syphilis*, gummatous ulcer occurs in anterior 2/3rd of tongue as a deep punched out painless ulcer as gumma with wash leather slough. Endarteritis is the cause for the punched out look. *Interstitial glossitis* with loss of papillae causes longitudinally fissured bald lobulated tongue in tertiary syphilis. In carcinoma arising from syphilitic ulcer, RT is *questionable* as blood supply is precarious due to endarteritis; RT further compromises it leading to tongue necrosis.

Tuberculous Ulcer

It is undermined shallow, often multiple, painful ulcer. Ulcer can occur in margins, tip or anterior 2/3rd of tongue. Neck nodes may be involved. Associated tuberculous larynx and lung may be present.

Herpetic Lingual Ulcer

It is involvement of lingual nerve presenting as acute neuralgia with vesicles which form multiple superficial painful ulcers.

Other Ulcers

Multiple ulcers in smokers due to glossitis (*smoker's ulcer*), ulcers due to vasculitis, eosinophilic granuloma. Post-pertussis ulcer in whooping cough occurs on upper part of frenum linguae and under the tip of tongue.

Macroglossia (Megaloglossia/Pachyglossia)

It is a disorder in which the tongue is larger than normal. It is commonly painless, diffuse enlargement of the tongue. Macroglossia is *usually* caused by an increase in the amount (volume) of tissue on the tongue, rather than by a growth, such as a tumour. It is often seen in haemangioma, lymphangioma, muscular macroglossia (in cretins), acromegaly, *Beckwith-Wiedemann syndrome* (hypoglycaemia, abdominal wall defects, Wilms' tumour, macroglossia, adrenal tumour), Down's syndrome, mucopolysaccharidoses, primary amyloidosis, occasionally plexiform neurofibromatosis. Often it causes functional and cosmetic problems.

Causes

1. *Lymphangioma*—soft, painless enlarged tongue with ulcers—bilateral; prevents closure of lip and jaw.
2. *Haemangioma*—soft, fluctuant, compressible, bleeding, red/blue lesion
   i. Both are treated by sclerotherapy (ethonalamine oleate)/partial excision
   ii. Angiogram/MR angiogram is a must in haemangioma
   iii. Ligation of lingual artery/ECA on both sides may be needed in large lesions

   Note:
   - Varicosities of sublingual veins mimic haemangioma.
   - Often causes *unilateral* enlargement of tongue.
   - Pressure on alveolus causes spacing of teeth and incisor deformity.
   - Combination of haemangioma and lymphangioma can occur.
3. *Neurofibroma*—partial excision is done
4. *Tongue muscular hypertrophy*: Partial excision is done.

- Elongation is corrected by wedge resection of anterior part of extra tongue from midline.
- Vertical thickening is rectified by slice cutting of lateral margins without injuring lingual artery and nerve.



Fig. 3.63: Macroglossia in Down's syndrome patient (*Courtesy*: Professor Kishore Chandra Prasad, ENT Surgeon, Dr Sampath, ENT Surgeon, Mangalore).



Fig. 3.64: Macroglossia.

BENIGN TUMOURS OF TONGUE

Benign tumours of the tongue

- Papilloma
- Fibroepithelial polyp
- Haemangioma and lymphangioma
- Neurofibroma
- Lipoma
- Granular cell myoblastoma

Fibroepithelial Polyp

It is due to repeated trauma at one place may be due to teeth (incisor) forming a thickened submucous scar which gets pulled out like a stalked polyp due to sucking and swallowing mechanism. It commonly enters the gap between the lower incisor teeth.

Granular Cell Myoblastoma

It is a benign noncapsulated firm mobile mass in the tongue showing pseudoepithelial hyperplasia of mucosa of tongue with eosinophilic granular cells in deeper plane. It is often mistakenly diagnosed as carcinoma of tongue. It is treated by excision.

TONGUE FISSURE

- Congenital fissures are transverse which run laterally from midline with normal papillae in between. Candida infection can occur on this.
- Syphilitic fissures are deep bald and longitudinal.

GLOSSITIS

Median Rhomboid Glossitis

- It is smooth, lobulated, triangular firm patch anterior to foramen caecum of tongue in midline with deeper colour.
- Candida infection can occur in it.


Median GE fold
Median GE fold
Congenital horizontal fissure
Longitudinal syphilitic fissure
Median GE fold
Foramen caecum
Median rhomboid glossitis

Fig. 3.65: Congenital fissures of tongue are transverse; syphilitic fissures are longitudinal. Median rhomboid glossitis is persistent tuberculum impar.

- It mimics carcinoma. Biopsy rules out malignancy. Carcinoma is uncommon in midline.

Glossitis Migrans (Geographic Tongue)

- It begins as benign small red patches with white furred margin which spread and recede in an irregular way to appear as fresh patches.
- White margin contains keratinized epithelium and inflammatory cells over filiform papillae.
- It is often seen in patients with congenital heart diseases and acute gastrointestinal diseases. Etiology is unknown.

Other Glossitis

- *Hunter's glossitis* is seen in pernicious anaemia.
- *Hairy tongue* is overgrowth of filiform papillae with black/brown stain on it due to bacteria, fungi, tobacco or drugs. There are no hairs. It is a misnomer. Cessation of causative agent, mechanical scraping, cleaning are the treatment methods.
- Agranulocytosis glossitis.
- Nonspecific glossitis.
- *Pellagra glossitis*, due to deficiency of nicotinamide (B12).
- Chronic superficial glossitis in malnutrition, iron and vitamin B deficiencies.

TONGUE TIE

- It is short, thick, fibrous frenum linguae.
- During protrusion lateral margin and tip of the tongue is everted with dorsal mid part heaping.
- It causes speech defect, difficulty in cleaning the inner part of lower teeth.
- It is treated surgically under local anaesthesia (or general in child). Tongue lifted upwards with a stay suture at the tip; fibrous frenum is divided using fine scissor; linear wound is closed longitudinally using fine catgut from the tip of the tongue towards the margin of the floor of the mouth.



Figs 3.66A and B: Tongue tie—on table photo.

CARCINOMA TONGUE

Incidence is equal in both sexes. Presently its incidence is increasing in females due to increase in number of female smokers.

Aetiology

- Leukoplakia.
- Erythroplakia.
- All 'S's (as mentioned in leukoplakia).
- Premalignant conditions mentioned earlier.

Hope sees the invisible, feels the intangible and achieves the impossible.



Fig. 3.67: Papilloma tongue. It is a premalignant condition. It requires surgical excision.



Fig. 3.69: Tongue showing fissuring. Fissuring is one of the presentations of carcinoma tongue.



Fig. 3.68: Pyogenic granuloma of tongue under surface.



Fig. 3.70: Horizontal fissures of tongue.

Types

Gross

1. Papillary.
2. Ulcerative or ulceroproliferative 60%.
3. Fissure with induration.
4. Lobulated, indurated mass—*frozen tongue.*

Histologically

1. Squamous cell carcinoma—commonest.
2. Adenocarcinoma, may arise from minor salivary glands or mucous glands.
3. Melanomas.
4. Transitional cell carcinoma and lymphoepithelioma rarely can occur in posterior 1/3rd of tongue.

Sites

1. Lateral margin—commonest—47-50%.
2. Posterior third—20%.
3. Dorsum—6.5%.
4. Ventral surface—9%.
5. Tip—10%.

Clinical Features

- Painless ulcer/swelling in the tongue which later may become painful. *Pain* in the tongue due to infection or



Fig. 3.71: Carcinoma tongue with leukoplakia.


Tonsillar pillar
Posterior 1/3rd
Anterior 2/3rd
1. Submental group
2. Submandibular group
3. Upper deep cervical group
4. Pharyngeal group
1
2
3
4

Fig. 3.72: Anatomy and lymphatic drainage of tongue.

ulceration or due to the involvement of lingual nerve (pain is referred to ear). Pain on swallowing, in case of carcinoma of posterior third of tongue.

- *Excessive salivation*. Saliva is often blood stained.



Fig. 3.73: *Frozen tongue* is feature of carcinoma tongue with ankyloglossia.



Fig. 3.74: Carcinoma tip of tongue. Well-circumscribed raised edge is seen.

- *Dysphagia* either due to fixed tongue or due to the involvement of genioglossus or growth in the posterior third of the tongue.
- *Visible ulcer* in anterior two-thirds of tongue. Ulcer can bleed on touch; edge, base and surrounding areas are indurated. Often indurated area is much more extensive than the primary tumour (it is also common in carcinoma penis). Edge is everted commonly. Ulcer may cross the midline; may extend into the floor of the mouth/alveolus/mandible. Growth or ulcer in posterior third, is usually not visible.



Figs 3.75A and B: Carcinoma tongue lateral margin (commonest site).



Fig. 3.76: Carcinoma tongue.

- *Ankyloglossia*—involvement of muscles of the tongue.
- Movements of the tongue especially forward protrusion is commonly affected.
- *Inability to articulate*.
- *Foetor* (Halitosis). Due to infection and necrosis in the oral cavity. It is due to release of ammonia, butyric acid and mercaptan by tumour cells.
- *Change in voice*. Occurs in posterior third tumours. Tumour in posterior third area is more aggressive.
- Palpable *lymph nodes* in the neck which are hard, nodular and get fixed to underlying tissues in advanced stages.
- Features of bronchopneumonia—due to aspiration during lying down/sleeping mainly to lower segment of lung.

Spread of Carcinoma Tongue

Local spread:

In case of anterior two-thirds of tongue, the spread occurs to genioglossus muscle, floor of the mouth, opposite side and mandible. In case of posterior third of tongue it spreads locally to tonsil, side of pharynx, soft palate, epiglottis, larynx and cervical spine.

Lymphatic spread:

From tip of tongue it spreads to submental nodes. From lateral margin it spreads to submandibular lymph nodes and later to deep cervical lymph nodes. Lymphatics in the tongue are freely communicating, and so involvement of bilateral neck lymph nodes is common. From posterior third it spreads to pharyngeal nodes and upper deep cervical lymph nodes.

Note:

- Any tongue lesion more than 4 mm depth has 30% metastasis to lymph nodes.
- Among oral cancers, carcinoma tongue is more aggressive, rapidly growing tumour with high potential for lymph node spread.
- Bilateral neck lymph node spread is common due to crossing of lymph vessels in tongue.
- Clearance of lingual lymph node which is located between tongue and submandibular lymph glands has to be done which may contain micrometastasis.
- Carcinoma tongue has got highest incidence of nodal spread.

Investigations

1. Edge biopsy.
2. FNAC of lymph nodes.
3. Indirect and direct laryngoscopy to see posterior third growth.



Fig. 3.77: Carcinoma left lateral margin of the tongue—ulcerative lesion. Note the proliferation. Induration extends for beyond the visible lesion.

4. CT scan to see the extension of posterior third growth, or to see the status of advanced secondaries. *MRI* is also very useful to assess the extent of primary tumour.
5. Chest X-ray to see bronchopneumonia.
6. Orthopantomogram.

***Note*:**
Staging is same as carcinoma cheek.

Treatment

Surgery, radiotherapy, chemotherapy.

Surgery

- *Wide excision* with 1 cm clearance in margin and depth is done in tumour less than 1 cm in size or in carcinoma in situ. Laser (CO_2 / diode) can be used.
- Tumour between 1-2 cm in size, *partial glossectomy* is done with 2 cm clearance from the margin with removal of 1/3rd of anterior two-third of the tongue.


Epiglottis
Median GE fold
Vallecula
Lateral GE fold
Lymphoid nodules
Sulcus terminalis
Circumvallate
Foliate
Tumour (1 cm)
Fungiform
1 cm
Filiform

Fig. 3.78: Wide excision is done in small lateral margin tumour of 1 cm size with 1 cm clearance.


Epiglottis
Median GE fold
Vallecula
Lateral GE fold
Lymphoid nodules
Sulcus terminalis
Circumvallate
Foliate
Fungiform
Tumour > 2 cm
Filiform
2 cm

Fig. 3.79: Tumour between 1-2 cm size is treated by partial glossectomy with 2 cm clearance.


Epiglottis
Median GE fold
Vallecula
Lateral GE fold
Lymphoid nodules
Sulcus terminalis
Circumvallate
Foliate
Tumour > 2 cm
Fungiform
Line of clearance
Filiform

Fig. 3.80: Tumour larger than 2 cm requires hemiglossectomy.

- Tumour larger than 2 cm, *hemiglossectomy* is done with removal of anterior 2/3rd of tongue on one side up to sulcus terminalis.
  - *Raw area* in these procedures can be left alone when area is wide allowing it to granulate and heal by epithelialisation. If area is small like in wide excision it can be closed by primary suturing. Wide raw area can also be covered with PMMF or *quilted split-skin-graft*.
- Larger primary tumour can be given preoperative radiotherapy, then later hemiglossectomy is done.
- Same side palpable, mobile lymph nodes are removed by *radical neck block dissection*.
- *Bilateral mobile lymph nodes are dealt with one side radical block and other side functional block dissection with essentially retaining internal jugular vein* (on opposite side) to maintain the cerebral venous blood flow. Other option is doing same side radical neck dissection and on opposite side supraomohyoid block dissection.
- *Wide excision* is done when growth is in *the tip* of the tongue.
- Posterior third growth can be approached by lip split and mandible resection, so as to have *total glossectomy—Kocher's approach*. It is not done commonly as it carries significant morbidity and mortality due to difficulty in speech, swallowing, aspiration, sepsis.
- When mandible is involved *hemimandibulectomy* is done.
- The procedure that involves wide excision or hemiglossectomy, hemimandibulectomy and radical neck dissection together is called as *Commando Operation*.
- Reconstruction of tongue and other area after surgery: By deltopectoral flap, forehead flap, pectoralis major muscle flap, skin grafting.
- Prophylactic block dissection is becoming popular at present.

Postoperative management

- Control of infection and oedema
- Regular mouth wash
- Maintaining the airway
- Prevention of aspiration
- Nutrition (through nasogastric tube commonly/TPN often)

He who believes, is strong; he who doubts, is weak.

Radiotherapy

1. In small primary tumour—curative radiotherapy (Brachytherapy using caesium or iridium^{192} needles).
2. Large primary tumour—initial radiotherapy is given to reduce the tumour size so that the resection will be better later.
3. Advanced primary as well as secondaries in the neck can be controlled by palliative external radiotherapy.
4. Postoperative radiotherapy is given in large tumours to reduce the chances of relapse.
5. In case of growths in the posterior third of tongue, radiotherapy is of curative as well as palliative mode.

Complications of radiotherapy

- Loss of sensation like taste
- Trismus and ankyloglossia
- Infection
- Pharyngeal and laryngeal oedema
- Dermatitis and skin infection

Chemotherapy

Given in postoperative period and also for palliation.

Price-Hill regimen is commonly used. Drugs are methotrexate, vincristine, adriamycin, bleomycin and mercaptopurine.

It is either given intraarterially, as regional chemotherapy through external carotid artery using arterial pump or through IV. It can also be given orally.

Complications of chemotherapy

- Megaloblastic anaemia
- Bone marrow suppression
- Alopecia
- Sepsis

For melanoma, Melphalan and DTIC are used.

Anterior chemotherapy (preoperative) is becoming popular to downstage the tumour.

Terminal events

- Inhalational bronchopneumonia
- Haemorrhage from erosion of lingual artery. In posterior third of the tongue, erosion of internal carotid artery can occur
- Cancer cachexia
- Asphyxia due to pressure on air passages or due to oedema glottis

Prognosis

Five-year survival for females is 50%, for males is 25%.

Nodal prognostic factors

- Positive histology in node reduces the survival
- Level III and IV has poor prognosis
- Bilateral/ contralateral nodes carry poor prognosis
- Extracapsular spread/size > 3 cm carry poor survival
- > 3 in number of nodes involved is poor sign

Prognostic Factors

- Size of the tumour > 4 cm caries poor prognosis.
- Site of tumour (posterior third has got poor prognosis).
- Tumour crossing the midline.
- Lymph nodes status.
- Differentiation.
- Bone involvement.

CARCINOMA OF POSTERIOR ONE-THIRD/BASE OF THE TONGUE

- Lesion may remain asymptomatic for long time.
- Clinically may be missed easily.
- Earlier symptoms are features mimicking sore-throat and throat discomfort.
- Dysphagia and change in voice (*hot potato voice*) occurs later.
- Referred pain in the ear, bleeding from mouth, visible mass in posterior third of tongue is late local features.
- Induration on palpation in posterior third tongue is diagnostic of the carcinoma.
- As posterior third tongue has got abundant lymphatics which cross communicates on either side, lymph node spread is common (70%). Bilateral nodal spread is common. Massive nodes and involvement of jugulodigastric node are also common.
- Infiltration into the tongue muscles like genioglossus, epiglottis, pre-epiglottic space, *tonsillar pillars* and hypopharynx are common.
- Carcinoma posterior third of the tongue is often poorly differentiated and so caries poor prognosis.
- Blood spread can occur into bones, liver and lungs in posterior third cancers.
- Palpation *under anaesthesia* gives better idea about the tumour, its spread and also allows the biopsy.
- Presentation as unknown/occult primary and often with blood spread can occur.
- CT scan/MRI is always needed to plan the staging and therapy.
- T_1, T_2, N_0 and N_1 diseases are treated by surgical wide excision or often by total glossectomy using midline mandibulotomy incision (mandible split) with neck dissection on both sides (MRND one side). Postsurgery radiotherapy is needed if it is a poorly differentiated type or nodal status is more than N_1.
- Advanced lesions need palliative radiotherapy or chemotherapy.
- T_4 lesions are often treated by total glossectomy with laryngectomy and neck dissection but overall outcome is not good.
- In many centers primary curative radiotherapy is used.
- Lymphoepithelioma and transitional cell carcinoma can occur in posterior third tongue (rarely).

Carcinoma floor of the mouth

- It is usually aggressive tumour
- It is rare in India
- It is 2nd common site of oral carcinoma (SCC) in western countries
- It invades hyoglossus, mylohyoid, genioglossus and anterior mandible early
- Bilateral neck nodes are commonly involved
- Rim resection of mandible with wide excision of tumour with muscles and soft tissues and bilateral neck dissection is necessary
- Often visor anterior approach with anterior mandible resection followed by proper reconstruction with bone graft and plates is needed
- Postoperative radiotherapy and later chemotherapy is used to prevent recurrence
- Prognosis is poor and also has poor cosmetic results

Carcinoma alveolus

- It is squamous cell carcinoma arising from gums
- It is common in males
- It is common in India
- It is commonly due to tobacco/pan chewing
- Features and precipitating factors are similar to other oral carcinomas
- There will be invariable bone involvement by direct extension
- Nodal spread is also common
- Wide excision with mandibulectomy and block dissection of neck is the treatment



Fig. 3.81: Carcinoma of floor of the mouth. It has got poor prognosis.

NASOPHARYNGEAL CARCINOMA

- Nasopharynx lies above the level of the soft palate which divides it from oropharynx below.
- It is also called as post-nasal space or epipharynx. Eustachian tube opens on its anterolateral wall. Fossa of Rosenmuller is located above and behind the opening of the Eustachian tube as a small depression.
- Nasopharyngeal carcinoma is common in China and Mongolia. In India it is common in North-East region. It is commonly squamous cell carcinoma (85%). Lymphoma, minor salivary tumours and sarcoma are other malignancies that can occur rarely in nasopharynx.
- It can be of proliferative, ulcerative, and infiltrative types. Commonest site is fossa of Rosenmuller in lateral wall of pharynx. It is three times common in males.
- *HO's triangle* in supraclavicular fossa (bounded by medial and lateral ends of clavicle and point where neck meets the shoulder) is the site where metastatic nodes commonly exist in nasopharyngeal carcinoma.
- In 50% of cases nodal involvement is bilateral. Often cervical lymphadenopathy may be the first presentation.
- *Clinical features* may be nasal, otogenic, ophthalmoneurogenic (involving most of the cranial nerves with facial pain, squint, diplopia, exophthalmos, and ophthalmoplegia), jugular foramen syndrome (cranial nerves IX, X, XI spread), nodal spread and distant spread to bones, lungs and liver.
- Unilateral serous otitis media may be the only presentation.

Clinical Features

1. Epistaxis, nasal speech, post-nasal discharge and nasal obstruction.
2. Pain in the ear with unilateral deafness due to compression of Eustachian tube with fluid collection in the middle ear.
3. Elevation and immobility of soft palate on the same side.
4. Pain in the area of distribution of trigeminal nerve due to direct infiltration of the nerve at foramen lacerum.
5. Palpable secondaries in upper deep cervical lymph nodes (70%).

Trotter's triad

- Unilateral deafness
- Immobile elevated soft palate
- Pain in the distribution of trigeminal nerve

Differential Diagnosis

- Lymphoma.
- Lymphoepithelioma.
- Minor salivary gland tumour.

Investigations

- Biopsy from the primary site.
- FNAC from the neck lymph nodes.
- X-ray of the skull to visualise erosions.
- CT scan skull.

Histological Type

Squamous cell carcinoma.

Treatment

- External irradiation for primary. RT is the main modality of treatment.
- Radical block dissection of cervical lymph nodes.
- In N2a, N2b and N2c contralateral neck dissection is needed. Spinal accessory nerve is never preserved while doing block dissection in nasopharyngeal carcinoma.

- Chemotherapy: Methotrexate, Vincristine.
- Skull base surgeries are useful.

MAXILLARY TUMOURS

They are rare.

- Maxillary sinus is the commonest site for malignancy of paranasal sinuses. Ethmoids, frontal and sphenoids are next in order.
- It is common in people working in furniture industries, mustard gas industries, and leather industries. It is common in Bantus in South Africa where snuff with nickel and chromium is commonly used.



Fig. 3.82: Carcinoma maxillary sinus in a boy. Note the extension into the palate.



Fig. 3.83: CT picture of carcinoma of maxillary sinus (left-sided).

Types

1. Squamous cell carcinoma 80%.
2. Adenocarcinoma.
3. Transitional cell carcinoma.
4. Salivary gland tumours.
5. Sarcomas and melanoma.
6. Burkitt's lymphoma.

Behaviour and Presentation

1. Initially may be symptomless or may present with *epistaxis* or *features of chronic sinusitis*.
2. When it spreads to the floor, loosening of the teeth, necrosis, antro-oral fistula can occur.
3. Extension medially causes nasal block, fungation, nasal discharge, blockage of nasolacrimal duct (*epiphora*).
4. Extension anteriorly causes pain, anaesthesia and swelling in the cheek, ulceration and fungation in the skin of cheek.
5. Spread above into the orbit causes epiphora, diplopia, proptosis.
6. *Posterior spread is most dangerous* as it is not revealed easily. It causes postnasal discharge, pain, trismus, limitation of temporomandibular joint movement.
7. Involvement of upper deep cervical lymph nodes in later stage is common.

Differential Diagnosis

Chronic sinusitis.

Classification

1. ***Ohngren's classification***

An imaginary plane is drawn extending between medial canthus of eye and the angle of mandible. Growth situated above this plane is called as *suprastructural* which has got poor prognosis. Growth below this plane is called as *infrastructural* and has got better prognosis.



Fig. 3.84: An imaginary plane is drawn extending between medial canthus of eye and the angle of mandible and line in this plane is called as *Ohngren's line*.



Fig. 3.85: Diagrammatic representation of Lederman's classification.

2. ***Lederman's classification***

Two horizontal lines are used, one passes through the floor of the orbit, another passes through the floor of the antra. These lines are called as *line of Sebileau*.

- *Suprastructure type*: In this type olfactory area of nose, ethmoidal, sphenoid, and frontal sinuses are involved.
- *Mesostructural type*: This involves maxillary sinus and nasal respiratory part.
- *Infrastructural type*: This type involves alveolar process.

Lederman's classification is further divided by two vertical lines over medial walls of the orbit to separate ethmoid sinuses and nasal fossa from maxillary sinuses.

TNM staging	***Staging***
• *T_1 Tumour* limited to antral mucosa • *T_2 Tumour* causing bone erosion/destruction including extension into hard palate or middle meatus of nose. • *T_3 Tumour* invading bone of posterior wall of maxillary sinus/skin of cheek/medial wall of orbit/infratemporal fossa/ pterygoid plates/ethmoid sinuses. • *T_4 Tumour* invading orbital contents beyond the floor or medial wall including orbital apex/cribriform plate/base of skull/nasopharynx/sphenoid or ethmoidal sinuses	Stage I T_1 N_0 M_0 Stage II T_2 N_0 M_0 Stage III T_3 N_0 M_0, $T_1/T_2/T_3$ N_1 M_0 Stage IVA T_4 N_0 M_0, T_4 N_1 M_0 Stage IV B Any T N_2 M_0, Any T N_3 M_0 Stage IVC Any T Any N M_1

Diagnosis

- X-ray of the part—pacity of the involved sinus with destruction of bony walls is seen.
- CT scan—ideal method.



Fig. 3.86: Incision for *Caldwell-Luc operation* which is used for taking biopsy from maxillary tumour. Incision is not used for definitive therapy for carcinoma maxilla. Incision also used in benign conditions to approach maxillary sinus. Gingivobuccal mucosa is incised and mucoperiosteum is raised. Bone of canine fossa is cut to reach the maxillary antrum.



Figs 3.87A and B



Figs 3.87C and D

Figs 3.87A to D: Carcinoma maxilla extending into the nose with X-ray and CT pictures. It is a fairly advanced growth.



Fig. 3.88: Carcinoma maxillary antrum extending outwards on to all walls. An advanced malignancy.



Fig. 3.89: *Weber-Fergusson's incision* used for total maxillectomy.

- Biopsy is done through nasal/oral or on early stage through Caldwell-Luc operation.
- Sinus endoscopy for detailed examination of sinus and for biopsy.

Treatment

- *Preoperative megavoltage radiotherapy* is given. After six weeks, *total maxillectomy* is done. Reconstruction of maxilla along with dental reconstruction is required.
- When lymph nodes are involved radical neck lymph nodes dissection is done.
- Postoperative radiotherapy and chemotherapy is given as an adjuvant therapy.
- Overall prognosis is 30-40%.

MALIGNANT TUMOURS OF TONSIL

- **Carcinoma of tonsil:** It is squamous cell carcinoma, similar to carcinoma cheek, but more aggressive with poor prognosis.
- **Carcinosarcoma** of tonsil.
- **Lymphoma**—NHL type.



Fig. 3.90: Lymphoepithelioma of tonsil.

CARCINOMA HARD PALATE

- Minor salivary gland tumours are more common in palate.
- In males, *in reverse smokers* (*Churat* is rolled tobacco leaf) squamous cell carcinoma is seen in palate due to repeated thermal injury.
- Malignant tumours may spread to periosteum, bone, maxilla, sinus, or nose.
- Salivary gland tumours are commonly malignant and are of adenoid cystic type. Other types also can occur. It presents as a single, solid, smooth swelling with ulcer over the summit.
- Squamous cell carcinoma is ulcerative with raised and everted edge.
- Upper deep cervical lymph nodes are involved in 25% of patients.



Fig. 3.91: Minor salivary gland tumour in posterior half of the palate. Note the nodular lesion with ulceration over the summit (*Courtesy:* Professor Kishore Chandra Prasad, ENT Surgeon and Head of the Department and Dr Sampath, ENT Surgeon, KMC, Mangalore).



Fig. 3.92: Carcinoma hard palate extending laterally.

- Investigations are edge biopsy, FNAC lymph node and CT scan to see extensions.
- *Treatment* is wide excision with removal of the underlying palatal bone. Often partial or total maxillectomy (*Weber-Fergusson* incision) may be required. Myocutaneous flap with dental prosthesis is essential to reconstruct after surgery. Postoperative radiotherapy and neck block dissection are often required.

LARYNGEAL TUMOURS

Benign

- *Epithelial* can be papilloma, vocal nodule or vocal polyp. Papilloma is usually single in adult, multiple in children.
- *Connective tissue tumours* like fibroma, myxoma, angioma. Indirect laryngoscopy (ILS) or direct laryngoscopy confirms the diagnosis.

Childhood papilloma	***Adult papilloma***
Multiple, of viral origin (Papova)	Single, of neoplastic origin
Can occur in glottic, supra and infraglottic	Glottic only
Not premalignant	Premalignant
Recurrence common	Not common after complete excision
Excision is difficult	Easier removal
Causes more dyspnoea, *stridor*, cough	Hoarseness only
May require tracheostomy	

***Note*:**
Stridor can be inspiratory, expiratory or biphasic.

Treatment

- Endoscopic removal. Application of podophyllum
- Cryosurgery, Laser surgery.

MALIGNANT TUMOURS OF LARYNX

Aetiology

- Smoking, tobacco.
- Alcohol intake.
- Occupational/industrial exposure to chemicals like mustard gas, asbestos, benzopyrones, petroleum products.
- Previous radiation.
- Genetic: Russians develop familial laryngeal cancers.
- Papillomavirus, keratosis, malnutrition.

Incidence

- Squamous cell carcinoma is commonest (95%).
- Common in males (10 : 1).
- Common in 5th/6th decade.

He who attempts the absurd can achieve the impossible.



Fig. 3.93: Anatomy of larynx showing supraglottic, glottic and subglottic regions.

Types

- Ulcerative.
- Proliferative.

Anatomical Types

- **Supraglottic (25%):** It arises from infrahyoid part of epiglottis, ventricles, and arytenoids. It spreads to neck lymph nodes early (40%) due to rich lymphatics in this area. Throat pain, dysphagia, palpable neck nodes and referred pain are common features. Hoarseness of voice, loss of weight, respiratory obstruction, and halitosis are late features. Carcinoma in epiglottis causes bilateral nodal spread. Local spread occurs to vallecula, base of tongue and pyriform fossa.
- **Glottic (65%):** It is the commonest type. It begins from upper part or free edge of vocal cords (mid or anterior) often extending 10 mm below. Lymphatic spread is slow (only 4%) as this area has got least lymphatics. Opposite vocal cord can involve as *kiss cancer*. Vocal cord mobility is unaffected in early cases. Vocal cord fixation signifies spread to thyroarytenoid which is a poor prognostic sign. It presents very early due to hoarseness of voice. Eventual cord fixation causes stridor. Locally it spreads anteriorly to anterior commissure, posteriorly to vocal process and arytenoids, above to ventricle and false vocal cords, below to subglottis.
- **Subglottic (2%)** is less common involving under-surface of true vocal cords and subglottic space. It spreads to deep cervical and paratracheal nodes (20%). Upward spread is rather late and so hoarseness is not an early symptom in this type. It can spread through cricothyroid membrane or thyroid gland.

Note:

- In Indian subcontinent supraglottic tumours are more common than glottic. Glottic type is common in Western countries.
- Fixation of cords is due to involvement of thyroarytenoid muscle or cricoarytenoid joint.

Clinical features	*Investigations*
• Hoarseness of voice	• ILS (Indirect laryngoscopy
• Pain and discomfort	• Direct laryngoscopy and biopsy
• Cough. dyspnoea, stridor, dysphagia in late cases	• CT neck—very useful investigation
• Bloody sputum	
• Palpable neck nodes, which eventually get fixed	• Chest X-ray
	• FNAC of lymph node
• Absence of laryngeal crepitus	• Microlaryngoscopy in small lesions to identify and to have proper biopsy
• Common in males—10:1	• Toluidine blue staining to stain early superficial cancers which facilitate the accurate biopsy
	• Hopkin's endoscopy
	• Flexible, fibreoptic laryngoscopy

Staging

Tumour

T1 Tumour confined to one anatomical site in larynx with normal cord mobility.
T2 Tumour confined to one anatomical region within larynx.
T3 Tumour spreads beyond one anatomical region within larynx with cord fixation.
T4 Tumour spreads beyond larynx.

Nodal staging is similar to any other oral carcinomas.

Treatment

- *Supraglottic*: Stage I—curative radiotherapy is the choice. In stage II and III total laryngectomy and block dissection of neck nodes.
- *Glottic:* Radiotherapy is the choice as nodes are commonly not involved. Endoscopic laser surgery or open partial laryngectomy can be done.
- *Subglottic:* Total laryngectomy is the treatment of choice with nodal block when needed.
- *In advanced stage IV* carcinomas surgery and radiotherapy both are not possible. Here chemotherapy is given using cyclophosphamide, cis platin and methotrexate.
- *In advanced resectable tumours, induction chemotherapy for 3 cycles with methotrexate and cisplatin 100 m/sq metre BSA (at 0, 22. 43 days) and total laryngectomy is under trial. Concurrent chemotherapy and radiotherapy are also under trial in these cases.*


Pyriform fossa
False cord
Ventricle
True cord
Supraglottic
Glottic
(1.0 cm)
Subglottic
Tumour
Supraglottic tumour
Tumour
Glottic tumour
Tumour
Subglottic tumour

Fig. 3.94: Laryngeal carcinoma, types. Note the typical sites. Glottic is the commonest site. Next is supraglottic. Subglottic is rare.


Median GE fold
Vallecula
Tubercle
Epiglottis
Vestibular fold
Vocal fold
Pyriform fossa
Lateral GE fold
Aryepiglottic fold
Tracheal rings
Cuneiform
Corniculate

Fig. 3.95: View of larynx as seen through a laryngoscope.



Fig. 3.96: Endoscopic view of vocal cords, pyriform fossa and aryepiglottic fold.


ILS mirror
Tongue
Larynx

Fig. 3.97: Indirect laryngoscopy to visualise larynx and its parts.

Role of Radiotherapy in Laryngeal Cancer

- In early growth with no impairment in motility curative RT is very useful with 90% cure rate with preservation of voice
- It is commonly used in superficial exophytic lesions, growth in tip of epiglottis and aryepiglottic folds.
- In subglottic extension, fixed growths, and in presence of nodes, radiotherapy is less effective.



Fig. 3.98A



Fig. 3.98B

Figs 3.98A and B: Carcinoma larynx—patients underwent total laryngectomy with permanent tracheostomy.

Conservative laryngeal surgery

Indications	*Advantages*
• Early growth without fixation especially glottic type	• Permanent tracheostomy is avoided Voice is retained
Types	*Disadvantages*
• Cordectomy through laryngofissure–excision of vocal cord after splitting of larynx	• Inadequate clearance • Recurrence of the disease
• Partial frontolateral laryngectomy–excision of vocal cord and anterior commissure	
• Partial horizontal laryngectomy–excision of supraglottis (epiglottis, aryepiglottic folds, false vocal cords and ventricle)	



Fig. 3.99: *Gluck-Sorenson's* laryngectomy incision. Extension lines sideward can be used for adding radical neck dissection.

Total laryngectomy

Indications	*Technique*
• T_3 lesions with cord fixation • All T_4 lesions • Bilateral arytenoids spread • Thyroid/cricoid spread • Transglottic cancers involving ventricle with fixation of the cord • Posterior commissure disease • Failure of conservative surgery or RT	• Entire larynx with hyoid bone, pre-epiglottic space, strap muscles, one or more rings of trachea are removed • Pharyngeal wall is repaired • Lower tracheal stump is sutured to the skin as permanent tracheostomy
Problems • Mortality of surgery • No speech • Having permanent tracheostomy and its problems	• Often laryngo-oesophagectomy is done when pharyngeal spread is present. Gastric pull-up is done to maintain GI continuity • Technique may be combined with neck nodal dissection both sides

Care after total laryngectomy

- ❖ Speech therapy by pseudoglottis creation, battery operated artificial larynx or Singer-Blom prosthesis or Panje's prothesis. Tracheo-oesophageal prosthesis (TOP) is ideal
- ❖ Social and job rehabilitation
- ❖ Care of permanent tracheostomy by avoiding immersion in the water, care during bath, shower use and swimming. Shower covers are available for this purpose
- ❖ Often along with total laryngectomy, total thyroidectomy and removal of parathyroid glands are required. Patient then needs supplementation of thyroxine and calcium for life time

TRISMUS

- ♦ It is inability to open the mouth adequately.
- ♦ Causes are—submucosal fibrosis, carcinoma buccal and gingivobuccal complex, post-radiotherapy sequelae, infection like tetanus, parotitis, dental or peritonsillar abscess.
- ♦ In carcinoma, invasion of tumour to pterygoids, buccinator, masseter, temporalis causes trismus.
- ♦ *Grading of trismus:* Interincisor distance more than 3.5 cm is—normal; Grade I is between 3.0–3.5 cm; Grade II is between 2.0—3 cm; Grade III is less than 2 cm.
- ♦ It is often clinically assessed by placing fingers perpendicularly between two jaws at incisor level. More than 3 fingerbreadth is considered as normal.
- ♦ *Problems with trismus* are—inability to put fingers or spoon into mouth; difficulty in cleaning the mouth; infection; difficulty in assessing the tumour / pathology clinically. During surgery, intubation is difficult and so tracheostomy may be needed in these patients.
- ♦ *Management*—treating the cause; release of soft tissue in case of fibrosis; draining the abscess and antibiotics for infection.

Chapter 4 Salivary Glands

> *(Three weeks after arriving at the anatomy laboratory of Gerhard Blasius in Amsterdam) fortune so favoured me that in the first sheep's head, which I…was dissecting alone in my room, I found a duct which, so far as I knew, had been described by no one before.*
>
> —**Niels Stensen,** 1661

CHAPTER OUTLINE

- Anatomy
- Saliva
- Sialography
- Salivary Calculus and Sialadenitis
- Sialosis
- Sialectasis
- Recurrent Childhood Parotitis
- Parotid Abscess
- Parotid Fistula
- Sjögren's Syndrome
- Mikulicz Disease
- Salivary Neoplasms
- Pleomorphic Adenoma
- Adenolymphoma
- Oncocytoma
- Basal Cell Adenoma
- Mucoepidermoid Tumour
- Adenoid Cystic Carcinoma
- Acinic Cell Tumour
- Malignant Mixed Tumour
- Adenocarcinoma of Salivary Glands
- Squamous Cell Carcinoma of Salivary Glands
- Submandibular Salivary Gland Tumours
- Management of Malignant Salivary Tumours
- Minor Salivary Gland Tumours
- Parotid Lymphoma
- Parotidectomy
- Frey's Syndrome
- Facial Nerve Injury

ANATOMY

Parotid Gland (Para—around, otis—ear)

It is the largest of the salivary gland, situated below the acoustic meatus between the ramus of mandible and sternomastoid muscle. The deep cervical fascia splits to form a capsule (parotid capsule) to enclose the gland. The superficial layer is thickened and adherent to the gland.

It is deep to parotid fascia, superficial to masseter. So parotid swelling occupies *below, behind, in front of the ear lobule*, obliterating the normal hollow below the ear lobule. When patient opens the mouth, parotid fascia stretches and swelling may become less preeminent but this test is difficult to elicit. When patient clinches his teeth, masseter contracts and parotid becomes more prominent.

Parts of the Parotid Gland

- Superficial part (80%)—lies over the posterior part of the ramus of mandible.
- Deep part (20%)—lies behind the mandible and medial pterygoid muscle; in relation to mastoid and styloid process.

Accessory Parotid

It is prolongation of the gland above the parotid duct (*socia parotidis*).

Parotid Duct

Parotid (*Stensen's*) duct is 2-3 mm in diameter, 5 cm in length, emerges from anterior surface of the gland, runs over the surface of the masseter muscle, passes through the buccinator

Both over-salivation and under-salivation are not advised. Only optimum salivation is accepted and ideal.

muscle, and opens into the oral mucosa opposite to the crown of upper second molar tooth. It is palpated *bidigitally*, one fingerbreadth below the zygomatic bone with index finger inside and thumb outside, in front of masseter which is felt during clinching of teeth. Transverse facial artery is *above* the parotid duct. Duct is 1 cm below the zygomatic arch.

Facial Nerve

It emerges from the stylomastoid foramen lying between external auditory meatus and mastoid process. It passes around the neck of the condyle of mandible and becomes superficial, later dividing into *temporofacial and cervicofacial branches* which in turn divides into many branches. Some of these may be interconnected *as pes anserinus* (goose foot). *Branches are* – temporal (auricularis anterior and superior part of frontalis), zygomatic (frontalis and orbicularis oculi), upper buccal and lower buccal (buccinator, orbicularis oris, elevators of the lip) mandibular (lower lip muscles) and cervical (platysma).

While exiting the skull through stylomastoid foramen (it is accompanied by stylomastoid branch of posterior auricular artery which enters the same foramen), it gives posterior auricular nerve and motor nerves to posterior belly of digastric and stylohyoid. Trunk is initially 1cm from posteromedial surface (*extraglandular*) and *intraglandular* for 1 cm before giving divisions.

Gland is often called as *parotid sandwich* due to transverse of facial nerve.

Blood Supply

It is from external carotid artery; and venous drainage is by external jugular vein.

Nerve Supply

It is from autonomic nervous system, parasympathetic is secretomotor from auriculotemporal nerve, sympathetic is vasomotor from plexus around the external carotid artery. *Faciovenous plane of Patey* is of surgical importance. Facial nerve is superficial to this plane which contains retromandibular vein and posterior facial vein. External carotid artery dividing into superficial temporal artery and maxillary artery is deeper to venous plane.



Fig. 4.1: Superficial lobe (80%) and deep lobe (20%) are separated by external carotid artery, retromandibular vein and facial nerve from deep to superficial.



Fig. 4.2: Anatomical relations of the parotid gland.

Lymphatic Drainage of Parotid

It drains into parotid lymph glands which are partly intraglandular and partly extraglandular (preauricular and infraauricular). Mainly intraglandular nodes are involved which later drains into deep cervical lymph glands. Parotid lymph nodes also drain from temple, side of scalp, lateral part of auricle, external acoustic meatus, upper part of cheek, parts of eyelids and orbit.

Structures within the parotid gland from deep to superficial

- External carotid artery, maxillary artery, superficial temporal artery, posterior auricular artery
- Retromandibular vein (by maxillary and superficial temporal veins)
- Facial nerve with its branches

Great auricular nerve (cutaneous sensory around angle and lower part of the ear lobule) and auriculotemporal nerve which is from mandibular division of trigeminal nerve (secretomotor to parotid gland) are other nerves present in relation to parotid gland.

Submandibular Salivary Gland

It is a ‘J’ shaped salivary gland situated in the anterior part of the digastric triangle.

Parts

- *Superficial part:* Lies in submandibular triangle, superficial to mylohyoid and hyoglossus muscles, between the two bellies of digastric muscle.
- *Deep part* is in the floor of the mouth and deep to the mylohyoid.


Temporal branch
Upper branch
Zygomatic branch
Buccal branch
Parotid
Mandibular branch
Lower branch
Cervical branch

Fig. 4.3: Pes anserinus.


Superficial temporal vein
Superficial temporal artery
Maxillary vein
Maxillary artery
Transverse facial artery
Parotid duct
Retromandibular vein
Maxillary vein
Posterior auricular vein
Parotid gland
Posterior auricular artery
Facial vein
External jugular vein
External carotid artery

Fig. 4.4: Vascular plane of parotid.


Lingual nerve
Nerve to mylohyoid
Medial pterygoids
Posterior belly of digastric
Hypoglossal nerve
Facial artery
Submandibular salivary gland

Fig. 4.5: Anatomical relations of the submandibular salivary gland.


Styloglossus
Deep lobe SMSG
Digastric
Mid constrictor
Hyoglossus
Hyoid bone
Mylohyoid
A
Submandibular ganglion
Digastric muscle
Sublingual gland
Lingual nerve
SMSG duct
Lingual artery and vein
Hypoglossal nerve (12)
B
Deep submandibular gland

Figs 4.6A and B: Relations of the submandibular salivary gland and its deep lobe.

Submandibular (*Wharton's*) duct (5 cm), emerges from the anterior end of the deep part of the gland, enters the floor of the mouth, on the summit of papilla beside the frenulum of the tongue.

Lingual nerve and submandibular ganglion are attached to upper pole of the gland. Hypoglossal nerve is deep to the gland.

Facial artery emerges from under surface of the stylohyoid muscle, enters the gland from posterior and deep surface, reaching its lateral surface crossing the lower border of mandible to enter the face.

Venous drainage is to anterior facial vein.

Nerve supply: Branches from the submandibular ganglion.

Resting salivary flow usually arises from the submandibular salivary gland. *Sialorrhoea* is increased salivary flow often seen due to drugs, in cerebral palsy, physically handicapped person, children, and psychiatry patients. Intractable sialorrhoea can be

How a person masters his fate is more important than what his fate is.

corrected by different surgeries to submandibular salivary gland like duct repositioning to excision of the gland.

Xerostomia is decreased salivary flow. It is seen in post-menopausal women, depression, dehydration, use of antidepressant drugs; anticholinergic drugs, Sjogren's syndrome, radiotherapy to head and neck region.

Minor Salivary Glands

There are around 450 minor salivary glands which are distributed in lips, cheeks, palate and floor of the mouth. Glands also may be present in oropharynx, larynx, trachea and paranasal sinuses. They contribute to 10% of total salivary volume.

Sublingual glands are minor salivary glands one on each side; located in the anterior aspect of the floor of the mouth in relation to mucosa, mylohyoid muscle, body of the mandible near mental symphysis. Gland drains directly into mucosa or through a duct which drains into submandibular duct. This duct is called as *Bartholin duct*.

Minor salivary glands are not present in gingivae and anterior portion of the hard palate.

Ectopic Salivary Gland

Ectopic salivary gland also called as aberrant salivary gland is nothing but ectopic lobe of the juxtaposed salivary gland. It is commonly seen in relation to submandibular salivary gland.

Commonest ectopic salivary tissue is *Stafne bone cyst* (Edward C Stafne, Dental Surgeon, Mayo Clinic). It is invagination of the juxtaposed submandibular salivary gland into the mandible bone on its lingual aspect.

X-ray shows radiolucent area due to the cyst below the angle of the mandible, lower to inferior dental vessels and nerve.

SALIVA

- 1500 ml of saliva is secreted per day. pH of resting saliva is less, 7.0; active saliva is 8.0.
- Saliva contains lingual lipase secreted from tongue glands, α amylase from salivary glands.
- Saliva contains mucin, glycoproteins, immunoglobulin IgA, lysozyme, lactoferrin which binds iron, proline rich proteins that protect enamel and bind toxic tannins.
- Parotid saliva is 20% of total secretion of saliva per day and is serous and watery; submandibular is 70% and is mucous and moderately viscous; sublingual is 5% and is mucous and viscous. Minor salivary and other oral glands—5%.
- Saliva facilitates swallowing, keeps mouth moist, serves as solvent for taste buds, facilitates speech, keeps oral cavity rinsed and clean, antibacterial, and neutralizes gastric acid content in regurgitation to relieve *heartburn*.

SIALOGRAPHY

Indications

1. Salivary fistulas.
2. Sialectasis.
3. Congenital conditions.
4. Extraglandular masses.
5. Parotid duct stones.

Dye used is lipiodol or sodium diatrizoate (Hypaque).

24-gauge cannula is passed into either Stensen's duct or Wharton's duct and one ml of the dye is injected into the duct and X-ray is taken.



Fig. 4.7: Sialogram X-ray done to visualise the ductal pattern in parotid.



Figs 4.8A and B: Submandibular gland sialogram pictures (*Courtesy:* Professor Kishore Chandra Prasad, ENT Surgeon and HOD, KMC, Mangalore; Dr Sampath, MS ENT, KMC, Mangalore).

Findings

- Narrowing (Stricture)
- Grape-like cluster appearance (Sialectasis)
- Dilatations
- Communications (Fistulas)
- Mass lesions

Precautions

1. *Sialography should never be performed in acute inflammation.*
2. Only one ml of dye should be injected, if more dye is injected it causes *extravasation and chemical sialadenitis*.

SALIVARY CALCULUS AND SIALADENITIS

- 80% Submandibular.
- 80% Radio-opaque.
- It is commonly calcium phosphate and calcium carbonate stones.
- Calculi are more common in submandibular gland, because the gland secretion is viscous, contains more calcium and also, its drainage is nondependent, causing stasis.
- Secretion from parotid is serous, contains less calcium and so stones are not common.



Fig. 4.9: Submandibular sialadenitis in a young boy who required excision of gland.



Fig. 4.10: Stone in the submandibular salivary gland as seen in X-ray (*Courtesy:* Dr Jagdish, Mangalore).

Salivary calculi

Submandibular gland	*Parotid gland*
80% common	20% incidence (*Rare*)
80% Radiopaque	Radiolucent
Seen in plain X-ray (intraoral)	Not seen in plain X-ray
Sialogram is not needed	Identified by sialogram

Calculi are common in submandibular salivary gland, because:
- Viscous nature and mucin content
- Calcium content
- Nondependent drainage
- Stasis
- Hooking of nerve by submandibular duct

Causes for submandibular sialadenitis	***Types of sialadenitis***
• Bacterial—more common. It is usually due to obstruction and stasis • Trauma over duct causing oedema/stricture and stasis • Viral—mumps—rare (Paramyxovirus)	• *Acute* – Bacterial—occurs following submandibular salivary ductal obstruction (Wharton's) or in parotid gland. In parotid, suppuration can occur leading into parotid abscess – Viral—common in parotid • *Chronic*—common after partial obstruction of submandibular gland duct or due to stones in submandibular gland or hilum proximal to the level of crossing of the lingual nerve over the duct

Presentation

Acute Sialadenitis—Features

- Pain, swelling, tenderness is seen in submandibular region and floor of the mouth.
- Dysphagia, trismus, fever.
- Double chin appearance due to spreading of oedema downwards.
- Duct is inflamed and swollen.

Chronic Sialadenitis—Features

- Pain is more during mastication due to stimulation (*Salivary colic* which can be induced by meals, lemon juice, etc). Salivary colic is pain induced by obstruction to the outflow of saliva may be ductal stone. During salivation size of the swelling will decrease again 2 hours after meal/stimulation.
- Salivary secretion is more during mastication causing increase in gland size.

Diagnosis means finding the cause of the disorder, not just giving its name.—**Sydney Walker**

- Firm/rubbery tender swelling is palpable bidigitally.
- When stone is in the duct, it is palpable in the floor of the mouth as a tender swelling with features of inflammation in the duct. Pus exudes through the duct orifice. (Irritation of the lingual nerve, which is in very close proximity to submandibular salivary duct, causes referred pain to tongue—*lingual colic*).
- In submandibular salivary gland, often the stones are multiple, with chronic inflammation of gland (*sialadenitis*).
- Often *acute on chronic sialadenitis* can occur.
- *Kuttner tumour* is chronic sclerosing sialadenitis of submandibular salivary gland.

Differential Diagnosis

- Submandibular lymphadenitis.
- Salivary neoplasm.

Investigations

- Intraoral X-ray (dental occlusion films) to see radiopaque stones (80%).
- FNAC of the gland to rule out other pathology.
- Total count and ESR in acute phase.
- USG will demonstrate stone *with posterior acoustic shadow*.

Note:

Radiological demonstration of stone/stones is called as *sialolithiasis*.

Treatment

- If the stone is in the duct, removal of the stone is done intraorally, by making an incision in the duct. Incised duct is not sutured as it may result in stricture. Laying open allows free drainage of saliva. Procedure is usually done under *local anaesthesia*.



Fig. 4.12: Excised specimen of submandibular salivary gland with stone in the gland.



Fig. 4.13: X-ray (OPG) showing left sided submandibular salivary stone.



Fig. 4.11: Stone in the duct of submandibular salivary gland (Wharton's duct).



Fig. 4.14: Incision for removal of the submandibular salivary gland.



Fig. 4.15: Incision for excision of submandibular salivary gland. It should be 2-4 cm below the margin of the mandible to avoid injury to marginal mandibular nerve.

- If stone is in the gland, *excision of submandibular* gland is done—*sialadenectomy*. It is always done under *general anaesthesia*.

Approach is from submandibular region (outside). An incision is made on the skin in submandibular region, about 5-8 cm length, parallel to and 2-4 cm below the mandible. Incision is deepened through the deep fascia until the gland is visualised without raising the flaps (so as to avoid injury to marginal mandibular nerve, branch of facial nerve). Facial artery is ligated twice. Lingual nerve and hypoglossal nerves are taken care of. Mylohyoid is retracted so as to remove the deep portion of the gland. Drain is placed after removal of the gland.

Antibiotic coverage is a must.

Facial artery lies in the groove on the deeper aspect of the gland; often embeds in the gland or runs around the gland with a variable course and so artery has to be ligated twice above anteriorly and below posteriorly.

Marginal mandibular nerve is in subplatysmal plane in neck, so incision should be deepened across the deep fascia without raising subplatysmal plane to avoid injury to this nerve.

Complications of Surgery

1. Haemorrhage.
2. Infection.
3. Injury to marginal mandibular nerve, lingual nerve, hypoglossal nerve.
4. Injury to nerve to mylohyoid causing anaesthesia over submental skin.

Note:
Stone in parotid duct can be removed by opening the duct longitudinally.
Stone in the gland or in collecting duct is treated by parotidectomy.

Indications for submandibular salivary gland excision	***Steps in submandibular salivary gland excision***
• Chronic sialadenitis • Submandibular salivary tumours *Pathway of secretomotor fibres of the submandibular and sublingual salivary glands* Superior salivary nucleus ↓ Preganglionic fibres ↓ Facial nerve, Chorda tympani nerve ↓ Lingual nerve ↓ Submandibular ganglion—post-ganglionic fibres ↓ Submandibular and sublingual salivary glands	• Anaesthesia—general
	• Position—neck extension with chin to opposite side
	• Incision—2-4 cm (3 cm) below and parallel to the margin of the mandible 5-8 cm in length (6 cm)
	• Mobilisation of the gland–intracapsular in sialadenitis; extracapsular in tumours with ligation of anterior facial vein
	• Facial artery ligation proximally and distally as artery is in the gland or in the groove posteriorly
	• Dissection of deeper lobe from mylohyoid muscle
	• Identification of lingual and hypoglossal nerves
	• Duct identification and ligation
	• Wound closure with a suction drain

Rule of 2 in submandibular salivary gland

- 2 parts divided by mylohyoid muscle
- 2 conditions affect it—tumour and stone
- 2 superficial nerves—cervical and mandibular branch of facial nerves
- 2 deep nerves—lingual and hypoglossal nerves
- Incision—2-4 cm below the mandible
- Ligate facial artery at 2 places

SIALOSIS

It is enlargement of the salivary gland due to fatty infiltration, as a result of various metabolic causes like diabetes, acromegaly, obesity, liver disease, alcoholism, bulimia, idiopathic, drug induced (sympathomimetics, carbimazole, thiouracil).

Clinical features: Bilateral diffuse enlargement of parotids, which is smooth, firm, nontender.

Treatment: The cause is treated.

SIALECTASIS

- It is an aseptic dilatation of salivary ductules causing *grape-like (cluster-like)* dilatations.

By perseverance the snail reached the ark.—**Charles Haddon Spurgeon**

- It is a disease of unknown aetiology with destruction of parenchyma of gland accompanied by stenosis and cyst formation in the ductules.
- It is common in parotids; often bilateral.
- Presents as a smooth, soft, fluctuant, nontransilluminating swelling which increases in size during mastication. It is tender initially. It lasts for many days with a long symptom-free period of the disease.
- Sialogram is diagnostic (grape or cluster-like dilatations).
- Treatment is conservative (nonsurgical).

RECURRENT CHILDHOOD PAROTITIS

It is a recurrent, rapid enlargement of one or both parotids with fever and malaise in children of age group between 3-6 years without any known aetiology. Recurrent episodes with a quiescent period in between are typical. Sialogram shows snowstorm punctate sialectasis. Low dose antibiotics for long period may be required. Occasionally patient may need total conservative parotidectomy especially if it occurs late in adolescent period.

PAROTID ABSCESS (SUPPURATIVE PAROTITIS)

- It is a result of an *acute bacterial sialadenitis* of the parotid gland.
- It is an ascending bacterial parotitis, due to reduced salivary flow, dehydration, starvation, sepsis, after major surgery, radiotherapy for oral malignancies and poor oral hygiene.
- Parotid fascia is densely thick and tough and so parotid abscess does not show any fluctuation until very late stage.
- Causative organism are *Staphylococcus aureus* (commonest), *Streptococcus viridans* and often others like gram-negative and anaerobic organisms.

Causes of acute parotitis (Differential diagnosis of suppurative parotitis)

- Viral—Mumps, Coxsackie virus A and B, parainfluenza 1 and 3, Echo and lymphocytic choriomeningitis
- Bacterial—*Staphylococcus aureus*
- Allergic
- HIV infection
- Radiotherapy, postoperative period
- Specific infections like syphilis
- Sjogren's syndrome often causes bilateral parotitis

Clinical Features

- Pyrexia, malaise, pain and trismus.
- Red, tender, warm, well-localised, firm swelling is seen in the parotid region (brawny induration).
- Tender lymph nodes are palpable in the neck.
- Features of bacteraemia are present in severe cases.
- Pus or cloudy turbid saliva may be expressed from the parotid duct opening.

Investigations

- U/S of the parotid region.
- Pus collected from duct orifice is sent for culture and sensitivity.
- Needle aspiration from the abscess is done to confirm the formation of pus.

Sialogram is contraindicated in acute phase, as it will cause retrograde infection leading into bacteraemia.

Note:
In suppurative parotitis patient may develop severe laryngeal or pharyngeal oedema and may require steroids, tracheostomy and critical care.

Complications of suppurative parotitis and parotid abscess

- Septicaemia
- Severe trismus
- Rupture into the external auditory canal

Treatment

1. Antibiotics are started depending on culture report.
2. When it is severely tender and localised, incision and drainage is done under G/A.

Areas where one should not wait for the abscess to form

- Parotid
- Breast
- Ischiorectal fossa
- Thigh

Skin is incised in front of the tragus vertically and then parotid sheath (pyogenic membrane) is opened horizontally. Pus is drained using sinus forceps and sent for C/S. Antibiotics are continued (***Blair's incision***).



Fig. 4.16: *Blair's incision* used to drain the parotid abscess.

3. Proper hydration, mouth wash using povidone iodine/potassium permanganate solutions, nutrition. Often patient with parotid infection needs admission and treatment.

PAROTID FISTULA

Parotid fistula may arise from *parotid gland* or *duct* or *ductules*. It may open inside the mouth as internal fistula; or open



Fig. 4.17: Parotid fistula with discharging saliva and pus.

outside onto the skin as external fistula. Fistula from the duct has profuse discharge. Fistula from the gland often shows only minimal discharge.

Incidence of salivary fistula is 0.2-3%.

Types

1. *Duct fistula* forms after superficial parotidectomy. It is profuse and often persisting. So duct should be ligated using nonabsorbable suture as far as possible, anteriorly to allow normal saliva drainage from deep lobe. If common duct is ligated deep lobe atrophies without causing any fistula.
2. *Gland fistula* occurs from the raw surface after superficial parotidectomy. It is mild and symptom subsides in a month with anticholinergic drugs. Jacobsom tympanic neurectomy completely stops the secretion from the fistula in this type.

Causes

- After superficial parotidectomy.
- After drainage of parotid abscess, ruptured abscess.
- After biopsy.
- Trauma.
- Recurrence of malignant tumour.

Clinical Features

- Discharging fistula in the parotid region of the face, and discharge is more during eating.
- Tenderness and induration.
- Trismus.

Diagnosis

- Sialography to find out the origin of the fistula whether from parotid gland or duct or ductules.
- Fistulogram or CT fistulogram.
- Discharge study.
- MRI.

Treatment

- Anticholinergics—hyoscine bromide (probanthine).
- Radiotherapy.
- Often exploration of fistula is required.
- Repair or reinsertion of the duct into the mucosa.
- *Newman Seabrock's operation*—a probe is passed into the parotid duct through the opening in the mouth. Another probe is passed through the fistula. Duct and fistula are dissected over the probe. After removal of the fistula track severed duct ends are identified; and ends are trimmed. Probes are removed. A tantalum wire is passed into the duct across the severed ends and duct is sutured over it using 4 zero vicryl. Tantalum stent is removed after 3 weeks.
- If still persists, auriculotemporal nerve which supplies secretomotor component of parotid is cut.
- If there is stenosis at the orifice of the Stenson's duct, papillotomy at the orifice may help.
- Total conservative parotidectomy is done in failed cases.

Remember about salivary fistula

- Commonly from the parotid
- It can be *internal* draining into the mouth or can be *external* draining outside
- It is *acquired commonly* but rarely can be congenital
- It can be due to surgery, trauma or due to sepsis
- Fistula arising from the *gland parenchyma* drains through suture line but usually closes spontaneously. Leakage will be more during meals. Saliva is confirmed by its high amylase content compared to seroma/serous fluid
- Fistula due to *ductal disruption* leaks profusely and invariably needs surgery to close it
- Submandibular gland fistula commonly closes spontaneously, rarely if not requires complete removal of the gland
- Anticholinergics, irradiation, denervation of the gland, duct ligation are done to reduce saliva production
- Excision of fistula, repair of the duct, diversion of the duct into the mouth are other options
- In severe intractable cases, removal of the gland/total conservative parotidectomy is needed

SJÖGREN'S SYNDROME

It is an autoimmune disease causing progressive destruction of salivary and lacrimal glands, leading to *keratoconjunctivitis sicca* (dry eyes), and *xerostomia* (dry mouth).

Types

1. Primary.
2. Secondary.

Tumours of ectopic salivary glands are of low grade malignancy (cylindroma) may ultimately metastasize to regional lymph nodes, the viscera and the skeleton. **—Kenneth Harrison**

Primary Sjögren's Syndrome (Primary Glandular Sicca Syndrome)

- Severe dry mouth.
- Severe dry eyes.
- Widespread dysfunction of exocrine glands.
- Incidence of developing lymphomas is high.
- There is no association of connective tissue disorders.

Primary extra glandular sicca syndrome

- Dry mouth, dry eyes.
- Hyperglobulinaemic purpura, vasculitis.
- Raynaud's phenomenon or B cell lymphoma.

Secondary Sjögren's Syndrome

- Dry mouth.
- Dry eyes.
- With association of connective tissue disorders like
  - Primary biliary cirrhosis (near 100%).
  - SLE (30%).
  - Rheumatoid arthritis (RA) (15%).
- Female to male ratio is 10 : 1.

Clinical Features

- It is common in middle aged females who present with dry eyes, dry mouth, enlarged parotids and enlarged lacrimal glands.
- Often they are tender.
- Superadded infections of the mouth, *Candida albicans* is common.

Investigations

1. Autoantibody estimation—rheumatoid factor, antinuclear factor, salivary duct antibody.
2. Sialography.
3. Estimation of salivary flow.
4. Slit lamp test of eyes.
5. Schirmer test – to detect lack of lacrimal secretion.
6. FNAC of parotids and lacrimal glands.
7. ^{99}Technetium pertechnetate scan for gland function.

Treatment: *It is conservative.*

1. Artificial tears.
2. Artificial saliva.
3. Frequent drinking of water.
4. Treat the cause.

MIKULICZ DISEASE

- It is a clinical variant of Sjögren's syndrome
- It is an autoimmune disorder of salivary and lacrimal glands, resulting in infiltration of the glands with round cells.
- It may be due to or associated with sarcoidosis, Sjögren's syndrome, leukaemia, lymphoma.

Triad

- Symmetrical and progressive enlargement of all salivary glands
- Narrowing of palpebral fissures due to enlargement of the lacrimal glands
- Parchment-like dryness of the mouth

SALIVARY NEOPLASMS

Aetiology

- *Genetic*—loss of alleles of chromosomes in 12q, 8q, 17q. Eskimos are more prone for salivary neoplasm.
- *Infective*—mumps, Epstein-Barr virus, chronic sialadenitis may be the cause; but not proved emphatically. Recurrent inflammation can cause duct dysplasia and carcinoma.
- *Radiation*—it is more common in survivors of atomic bomb explosion; mucoepidermoid carcinoma is more in these patients.
- *Smoking*—adenolymphoma of Warthin's shows 40% risk in smokers.
- *Sex*—benign tumours and many malignancies are common in females; Warthin's and some malignancies are common in males.
- *Environment and diet*—Arctic-Eskimos show dietary deficiency of vitamin A and develop salivary tumour. Industrial agents like nickel, cadmium, hair dyes, silica, preservatives may increase the risk of salivary tumours.

Classification (WHO)

a. ***Epithelial*** (90%):
  1. *Adenomas*
     - Pleomorphic adenoma.
     - Monomorphic adenomas.
       - Adenolymphoma (Warthin's tumour).



Fig. 4.18: Partoid enlargement in a boy of 11-year-old.

- » Oncocytoma (oxyphil adenoma) seen in elderly; seen in parotid gland.
- » Basal cell adenoma—it is a rare benign tumour.

2. *Carcinomas*
   - Mucoepidermoid carcinoma—most common malignancy.
   - Acinic cell carcinoma—1%.
   - Adenoid cystic carcinoma—very aggressive—10%; common minor salivary glands.
   - Adenocarcinoma.
   - Squamous cell carcinoma—2%.
   - Carcinoma in ex pleomorphic adenoma.
   - Undifferentiated carcinoma.

Note:

Carcinoma can be:

Low grade (acinic cell; adenoid cystic; low grade mucoepidermoid) or *High grade* (adenocarcinoma; squamous cell carcinoma; high grade mucoepidermoid) mesenchymal.

b. ***Nonepithelial:***

- ♦ Haemangioma—*commonly* seen in infants, usually in parotids. Spontaneous regression is common. Most common benign salivary gland tumour in paediatric age group.
- ♦ Lymphangioma.
- ♦ Neurofibromas and neurilemmomas.

c. ***Malignant lymphomas—NHL type:***

- ♦ Common in parotids.
- ♦ Common with HIV, Sjögren's syndrome (44 times more chances than normal people).

d. Secondary tumours from head and neck region; bronchus and skin.

e. Lymphoepithelial tumours:
   - ▸ Benign—it is 5% of all benign salivary tumours (*Godwin's tumour*). It is common in females; can be bilateral. Benign lymphoepithelial lesion (BLEL) is of unknown etiology characterized by replacement of salivary parenchyma with lymphoid tissue. It may be diffuse/focal/capsulated/unencapsulated. It may be associated with Mikulicz's disease or Sjögren's syndrome.
   - ▸ Malignant—it is rare tumour occurs in parotid and submandibular glands (ESKIMOMA).



Figs 4.19A and B: Neoplasm of parotid gland.

Incidence

- ♦ Eighty per cent salivary neoplasms are in the parotids of which 80% are benign; 80% of these are pleomorphic adenomas.
- ♦ Fifteen per cent of salivary tumours are in the submandibular salivary gland, of which 50% are benign. 95% of these are pleomorphic adenomas.
- ♦ Ten percent of salivary neoplasms are in the minor salivary glands—palate, lips, cheeks, and sublingual glands. Of these only 10% are benign.

Note:

- Parotid tumours are common but only 20% are malignant.
- Submandibular tumours are uncommon but 50% of them are malignant.
- Minor salivary gland tumours (other than sublingual glands) are rare and 90% of them are malignant.
- Sublingual salivary tumours are very rare but almost all sublingual salivary tumours are malignant.
- Incidence of malignancy in salivary glands is inversely related to size of the gland; in parotid it is 15%; in submandibular it is 50%; in sublingual it is 85%.

PLEOMORPHIC ADENOMA (Mixed Salivary Tumour)

- ♦ Commonest of the salivary gland tumour in adult.
- ♦ It is 80% common.
- ♦ More common in parotids (80%). 10% in submandibular salivary gland; 0.5% in sublingual salivary gland.
- ♦ It is mesenchymal, myoepithelial and duct reserve cell origin.

Grossly it contains cartilages, cystic spaces, solid tissues.

Microscopically it is biphasic in nature with epithelial and stromal components. Benign tumours will usually not show necrosis.

Histologically it shows:

- ❖ Epithelial cells
- ❖ Myoepithelial cells
- ❖ Mucoid material with myxomatous changes
- ❖ Cartilages/pseudocartilages

- ♦ Even though it is capsulated, tumour may come out as *pseudopods* and may extend beyond the main limit of the tumour tissue.
- ♦ When disease occurs in parotid, commonly it involves superficial lobe or superficial and deep lobe together.
- ♦ But sometimes only deep lobe is involved and then it presents as swelling in the lateral wall of the pharynx, soft palate and posterior pillar of the fauces. There may not be any visible swelling in the preauricular region. It is called as '*dumbbell tumour*'. This tumour is in relation to styloid process, mandible, stylohyoid, styloglossus, stylopharyngeus muscles.

Remember that the faith to move a mountain always carries a pick. **— Anonymous**



Fig. 4.20: Pleomorphic adenoma showing *curtain sign*.



Fig. 4.21: Deep lobe tumour of parotid is examined per orally.



Figs 4.22A and B: Typical parotid swelling with ear lobe raised. Facial nerve should be tested by clenching the teeth.

Clinical Features

Clinical features of parotid tumour

- Swelling, pain, ulceration, dysphagia (if deep lobe is involved)
- Raised ear lobule
- Cannot be moved above the zygomatic bone—curtain sign
- Deviation of uvula and pharyngeal wall towards midline in case of deep lobe tumour
- Facial nerve, masseter, skin, lymph node and bone involvement eventually occurs in case of malignancy

- 80% common.
- Common in females (3:1).
- Occurs in any age group. But common in 4th and 5th decade
- Usually unilateral.
- Present as a single painless, smooth, firm lobulated, mobile swelling in front of the parotid with *positive curtain sign* (As the deep fascia is attached above to the zygomatic bone, it acts as a curtain, not allowing the parotid swelling to move above that level. Any swelling superficial to the deep fascia will move above the zygomatic bone).
- Obliteration of retromandibular groove is common.
- The ear lobule is lifted.
- When deep lobe is involved, swelling is commonly located in the lateral wall of pharynx, posterior pillar and over the soft palate—10%. Deep lobe tumour passes through *Patey's stylomandibular tunnel* pushing tonsils, pharynx, soft palate often without any visible swelling or only small swelling when only deep lobe tumour is present; it also presents as dysphagia. Bidigital palpation of parotid is significant in such occasion with one finger inside mouth.
- Facial nerve is not involved.

Long-standing pleomorphic adenoma may turn into carcinoma (carcinoma in ex pleomorphic adenoma). Its features are:

- Recent increase in size
- Pain and nodularity
- Involvement of skin, ulceration
- Involvement of masseter
- Involvement of facial nerve—lower facial nerve palsy—(Difficulty in closing eyelid, difficulty in blowing and clenching teeth)
- Involvement of neck lymph node
- Restriction of jaw movements



Fig. 4.23: Typical parotid tumour—a pleomorphic adenoma.



Fig. 4.24: Parotid tumour showing typical raise in earlobe.

Pain in salivary tumours

- Benign tumours are usually painless
- Sudden onset of pain denotes malignant transformation
- Pain is dull boring at primary site or referred to ear through auriculotemporal nerve
- *Pain is due to:*
  - Capsular distension by tumour
  - Obstruction to free flow of saliva
  - Nerve infiltration
  - Inflammation like in Warthin's
  - Tumour necrosis

Complications

- Recurrence—5-50%.
- Malignancy.
  - 3-5% in early tumours.
  - 10% in long duration (15 or more years) tumours.

Investigations

- FNAC is very important and diagnostic.
- CT scan to know the status of deep lobe, local extension and spread.
- MRI is better method.

Note:

Incision biopsy of parotid tumour is contraindicated as chances of *seedling* and *recurrence* are high and also there is a chance of *injuring the facial nerve*, and chance of developing *parotid fistula* while doing the biopsy.

Open biopsy is contraindicated in parotid tumours due to:

- Chance of injury to facial nerve
- Seedling and high chance of recurrence
- Chance of parotid fistula formation



Fig. 4.25: CT picture of pleomorphic adenoma.

Anything the mind of man can conceive and believe, it can achieve.

Treatment

- Surgery—first line treatment.
- If only superficial lobe is involved, then superficial parotidectomy is done wherein parotid superficial to facial nerve is removed.
- If both lobes are involved, then total conservative parotidectomy is done by retaining facial nerve.

Note:

- Enucleation is avoided as it causes high recurrence due to extension of *tumour outside as pseudopods* across the capsule.
- Incomplete excision, 10% of tumours which are highly cellular are other causes for recurrence.
- RT is given after surgery even though it is benign.
- Inexplicable metastasis can occur even though it is benign.
- Tumour may implant due to spillage while surgical removal into retained residual parotid (deep lobe in superficial parotidectomy).



Figs 4.26A and B



Fig. 4.26C

Figs 4.26A to C: Recurrent parotid tumour which has attained large size. Note facial nerve is intact. Duct orifice should be inspected using retractor.

- *Recurrence after parotidectomy* in pleomorphic adenoma is 5%. It is due to spillage, improper technique, inadequate margin, retained pseudopods, multicentricity. Recurrent tumour is multinodular without any capsule. *Expression of MUC1/DF3* in the tumour is marker to predict recurrence.

ADENOLYMPHOMA (Warthin's Tumour, Papillary Cystadenolymphomatosum)

- It is a misnomer. It is not malignant, it is not lymphoma.
- It is a benign tumour that occurs only in parotid, usually in the lower pole.
- It is said to be due to trapping of jugular lymph sacs in parotid during developmental period.



Fig. 4.27: Warthins tumour of parotids. It is common in males; often bilateral; common in elderly.

- It composed of *double layer of columnar epithelium*, with papillary projections into cystic spaces with lymphoid tissues in the stroma.
- It usually involves only superficial lobe of parotid gland. It may also be *multicentric*.
- Smoking (40%/8 times more risk than nonsmokers) and radiation exposure may be the cause.

Clinical Features

- It presents as a slow growing, smooth, soft, cystic, fluctuant swelling, in the lower pole, often bilateral and is nontender.
- It is common in males—4:1. Common in smokers.
- Common in old people – 60 years.
- Its incidence is 10%. Common in Whites.
- It is 2nd most common benign tumour.
- It is often bilateral—10%.

Investigations

- Adenolymphoma produces a "hot spot" in ^{99}Technetium pertechnetate scan—*it is diagnostic* (Due to high mitochondrial content).
- FNAC.

Adenolymphoma does not turn into malignancy. But occasionally it can simultaneously be associated with pleomorphic adenoma, carcinoma or lymphoma of parotid.



Fig. 4.28: Warthin's tumour. It is seen in parotid gland usually in superficial lobe, in lower pole.

Treatment

Superficial parotidectomy.

ONCOCYTOMA (Oxyphil Adenoma)

- It is < 1% of salivary tumours.
- Usually benign, originating from *oncocytes* (oxyphilic cells).
- Radiation and occupational hazards are the causes.
- Common in parotid; but rarely can occur in submandibular salivary gland.
- Gross - small, *tan coloured*, well circumscribed encapsulated solid tumour.
- Microscopy - *large oncocytes* with *swollen granular cytoplasm* due to abundant mitochondria. Tyrosine crystals are present in glandular spaces.
- Predilection for ^{99}Tc with hotspots and FNAC are the investigations.

BASAL CELL ADENOMA

- It is rare, benign, now classified under monomorphic adenoma containing isomorphic basaloid cells with basal layer and basement membrane.
- It is common in minor salivary glands; in major salivary glands it is multicentric.
- Grossly it looks like lymph node.
- *Microscopy*—isomorphic basaloid cells with solid/trabecular/tubular/membranous pattern.
- *Canalicular adenoma* is its variant with bilayered ribbons of columnar cells separated by vascular stroma.

MUCOEPIDERMOID TUMOUR

- It is the commonest malignant tumour in parotid.
- It is 2nd common malignant tumour in submandibular and sublingual salivary glands.
- It is commonest malignant tumour of parotid in childhood.
- Incidence is 9% of salivary tumours; 20% of malignant salivary tumours.
- It occurs both in major as well as minor salivary glands. Parotid is the commonest site; palate is the commonest minor salivary gland site (In the palate adenoid cystic carcinoma is common).



Fig. 4.29: Mucoepidermoid tumour.

It's your imagination that can take you anywhere.

- Radiation is the commonest etiological factor.
- *Gross*—unencapsulted solid tumour with cystic spaces.
- *Microscopy*—biphasic with *mucin secreting* (+ve for PAS, - ve for diastase) low grade and *epidermoid* with high grade; *clear cell* with intermediate type.
- It is slowly progressive, often attains a large size and spreads to neck lymph nodes.
- It contains malignant epidermoid and mucous secreting cells.

Types

- Low grade—*mucous cells* mainly—spreads to regional nodes.
- Intermediate—*clear cell* variety
- High grade—*epidermoid cells* mainly—spreads to regional nodes and also shows high propensity for distant spread.

Facial nerve involvement is late in mucoepidermoid carcinoma of parotid.

Clinical Features

- Swelling in the salivary (parotid or submandibular) region, slowly increasing in size, eventually attaining a large size, which is hard, nodular, often with involvement of skin and lymph nodes.
- Common in females (3:1); slow growing.
- Pain, skin and facial involvement are not common unless it is high grade.

ADENOID CYSTIC CARCINOMA (10% of Salivary Tumours)

- It is *most common* tumour in submandibular and sublingual salivary glands. 50% of cases occur in minor salivary glands—*palate*.
- It is also called as *cylidromatous carcinoma*.
- It is 2nd most common malignant salivary tumour; but it is rare in parotid (2% of parotid tumours, 15% of malignant parotid tumours.
- It is common in females (3:2). Common in 5th and 6th decades.
- It is s*low growing but highly malignant* with remarkable capacity for recurrence. But it is classified under *low grade* malignancy.
- *Microscopy*: Cribriform, tubular, and solid are 3 types. *Cribriform* type shows cells in nests separated by round or oval spaces—'*Swiss-cheese*' pattern. Myo and duct epithelial cells with lace like pattern are also seen. It *invades* periosteum and bone medulla early and spreads extensively.
- It has got high affinity for *perineural spread* (both axially and circumferentially; antegrade and retrograde fashion) along mandibular and maxillary divisions of trigeminal (*common*) nerve and facial nerve. It infiltrates nerve more proximally for long distance. Tumour may reach Gasserian trigeminal ganglion, pterygopalatine ganglion and cavernous sinus.
- Blood spread can occur to *lungs*, bones and liver. Lung secondaries may remain *dormant for many years* and so is not a contraindication for surgery of primary tumour. Blood spread can occur decades after removal of primary tumour.
- Radical parotidectomy/wide or radical excision of submandibular and sublingual glands with neck nodal dissection and postoperative RT is the treatment of choice.
- Positive margin, perineural spread, solid type on microscopy carry poor prognosis. Lung metastasis will not affect the prognosis.
- Local recurrence is common. 5-year survival is 70%.
- Regional nodal spread can occur but rare.

ACINIC CELL TUMOUR

- It is a rare, slow growing tumour that occurs almost always in parotid and is composed of cells alike serous acini.
- It is more common in women. It occurs in adult and elderly.
- It is 3% of salivary tumours; 90% occurs in parotid.
- Microscopically it can be microcystic (commonest), papillary, follicular, medullary etc.
- It can involve facial nerve or neck lymph nodes.
- Clinically it is of variable consistency with soft and cystic areas.
- It is low grade malignant tumour.

MALIGNANT MIXED TUMOUR (MMT)

- It is 10% of salivary malignancy in incidence with epithelial and mesenchymal elements.
- It carries worst prognosis.

Types

- *Carcinoma ex pleomorphic adenoma*: It is the commonest type. Previous long standing parotid swelling shows rapid change, fixity, facial nerve spread, neck nodal involvement are typical. Transformation is 2% in tumour of 5 years duration; 10% in 15 years tumour. It is the most aggressive salivary malignancy. Radical parotidectomy is the treatment.
- *Primary malignant mixed tumour*: It is also called *as carcinosarcoma* which arises as *de novo*. It shows components of both carcinoma and sarcoma with metastatic potential both through lymph nodes and blood.
- *Metastasizing mixed tumours*: It contains structures typical of benign mixed tumour both at original and at metastases sites.
- *In situ non-invasive carcinoma* in pleomorphic adenoma: There is no evidence of capsular invasion. Lesion with less than 8 mm invasion in depth shows 100% of 5-year survival; > 8 mm invasion carries 5-year survival < 50%.

ADENOCARCINOMA OF SALIVARY GLANDS

- It is 3% of parotid and 10% of submandibular and minor salivary gland tumours.
- It is equal in both sexes.
- It is common in children
- It can be tubular, papillary and undifferentiated.
- 20% involve facial nerve clinically.
- Undifferentiated type is aggressive.

SQUAMOUS CELL CARCINOMA OF SALIVARY GLANDS

- It is rare in salivary glands.
- In salivary glands, parotid is the common site.
- It is almost never seen in minor salivary glands.
- It is classified as high grade tumour.
- It is common in men (3:1).
- It occurs in 6th or 7th decade. It is aggressive nonencapsulated tumour arising from ductal system
- It grows rapidly causing pain, facial palsy, skin fixity, ulceration.
- It spreads commonly to neck nodes.
- It carries poor prognosis.
- Radical parotidectomy and RT is the treatment of choice.

SUBMANDIBULAR SALIVARY GLAND TUMOURS

Benign tumours:

- They are commonly pleomorphic adenomas, are smooth, firm or hard, bidigitally palpable, without involving adjacent muscles or hypoglossal nerve or mandible bone.
- Diagnosis is by FNAC, Orthopantomogram (OPG) and CT scan.
- Excision of both superficial and deep lobes of the gland is done.

Malignant tumours of submandibular salivary gland:

- They are hard, nodular, often get fixed to skin, muscles, hypoglossal nerve and mandible.
- Diagnosis is by FNAC of primary tumour and of lymph nodes when involved, CT scan and OPG.
- *Treatment:*
  - Wide excision, with removal of adjacent muscle, soft tissues and mandible.
  - If lymph nodes are involved, block dissection of neck (Classical neck dissection) is done.



Fig. 4.30: Submandibular salivary gland tumour which is malignant. Patient underwent wide excision.

General features of malignant salivary tumours

- Fixation
- Resorption of adjacent bone
- Pain and anaesthesia in the skin and mucosa
- Muscle paralysis
- Skin involvement and nodularity
- Involvement of jaw and masticatory muscle
- Nerve involvement (facial nerve in parotid or hypoglossal nerve in submandibular salivary gland)
- Blood spread when occurs, commonly to lungs
- Mandibular branch of 5th cranial nerve may be involved when tumour tracks along the auriculotemporal nerve to the base of the skull causing severe pain in the distribution area

MANAGEMENT OF MALIGNANT SALIVARY TUMOURS

TNM Staging of Malignant Salivary Tumours (AJCC, 7th Edition, 2010, Clinical Staging)

T—Tumour
Tx—Tumour cannot be assessed.
T0—No evidence of primary tumour.
T1—Tumour < 2cm without extraparenchymal spread.
T2—Tumour 2-4 cm, without extraparenchymal extension
T3—Tumour >4 cm.
—or with extraparenchymal spread.
—but no facial nerve spread.
T4—Spread to facial nerve, skin, mandible, ear canal
—T_{4a}.
—or spread to base of skull, pterygoid plates, encased external carotid artery – T_{4b}.

Staging

Stage I – T1N0M0
Stage II – T2N0M0
Stage III – T3N0/N1Mo
Stage IVA – T4aN2N1N0M0
Stage IVB – T4b any NM0; any T N3M0
Stage IVC – Any T any N M1

Note:

Pathological TNM staging is also present which differs from clinical in many points. Example—T3 is tumor of size 4-6 cm; T4 is size > 6 cm.

N—***Lymph node***
Nx — Nodes not assessed.
N0 — Regional nodes not involved.
N1 — Single ipsilateral node < 3 cm.
N2a — Single ipsilateral node 3-6 cm.
N2b — Multiple ipsilateral nodes < 6 cm.
N2c — Bilateral or contralateral nodes < 6 cm.
N3 — Single node spread > 6 cm.



Fig. 4.31: Submandibular salivary gland tumour in old female.

M—***Metastases***
M0 — No blood spread.
M1 — Blood spread present.

Specific Investigations

- FNAC.
    - FNAC also confirms possibility of (35% of patients) lymphoma/inflammatory masses.
    - FNAC allows preoperative counselling regarding nature of tumour, likely extent of resection (conservative/ radical), management of facial nerve (high grade adenoid cystic), and likelihood of neck dissection (high grade).
    - But FNAC may cause haematoma leading to difficulty in surgical dissection. Sampling problem, difficulty in finding histological type.
    - Conservative approach for benign tumours in high risk surgical candidates may be thought of.
- CT scan to see the deep lobe of the parotid: the involvement of bone, extension into the base of the skull; relation of tumour to internal carotid artery, styloid process, deep lobe tumour, parapharyngeal space extension. Neck nodes are better assessed. Bony changes in the foramina, erosions and sclerotic margins in fissures or canals, enlarged diameter of canal and fissure are the CT features of perineural spread.
- *MRI is very useful* to find out perineural spread, bone marrow involvement, skull bones, internal architecture and intracranial extensions, recurrent tumours. Replacement of perineural fat with tumour, contrast (gadolinium) enhancement, increased size of the nerve are features of perineural spread.
- OPG.
- Blood grouping and cross matching; required amount of blood is kept ready.



Figs 4.32A and B: CT scan pictures of salivary tumours.

- FNAC of lymph node.
- MRI shows better soft tissue definition than CT scan. *Sialogram is not useful in assessment of tumour.*

Treatment

In Parotid

- ***Surgery***

Indications for surgery

- T1, T2, T3 tumours of low grade—total conservative parotidectomy
- T4 tumours, high grade tumours, SCC—radical parotidectomy

It includes facial nerve sacrifice, may involve resection of skin, mandibular ramus, masseter muscle, infratemporal fossa dissection, subtotal petrosectomy.

Note: In T1 low grade, superficial parotidectomy is often practiced; but not ideal.

a. *Radical parotidectomy* is done which includes removal of both lobes of parotid, soft tissues, part of the mandible with facial nerve.

- It is done in high grade malignant tumours and squamous cell carcinoma.

Indications for facial nerve sacrifice

- Preoperative weakness/paralysis of nerve
- Intraoperative evidence of gross invasion even in presence of normal preoperative function
- Tumours transgressing through facial nerve from superficial to deep lobe
- Nerve stump is checked for frozen section for negative margins, if positive mastoidectomy and nerve dissection in temporal bone is needed

- Facial nerve is reconstructed using greater auricular nerve, or sural nerve. All branches except buccal branch are repaired using cable graft. Nerve graft is not a contraindication for future RT.
- Often lateral tarsorrhaphy or temporal sling reconstruction is done.

b. *Total conservative parotidectomy* is becoming popular in many parotid malignancies.

Complications of surgery

- Haemorrhage
- Infection, flap necrosis
- Fistula
- Frey's syndrome
- Facial nerve palsy
- Facial numbness
- Numbness in ear lobule due to injury to great auricular nerve
- Sialocele

♦ *Postoperative radiotherapy*

It is quite useful to reduce the chances of relapse. Usually, external radiotherapy is given. It is given in all carcinomas, but more useful in adenoid cystic and squamous cell carcinomas.

Indications for radiotherapy

- T3, T4 tumours
- High grade tumours
- Perineural spread
- Adenoid cystic carcinomas
- Deep lobe tumour
- Vascular involvement
- Close clearance margin
- Multiple neck nodes involvement
- Recurrent malignant tumours
- Recurrent pleomorphic adenoma
- Spillage after surgery for pleomorphic adenoma
- Residual/refractory tumours/nerve involvement
- Inadequate clearance margin

Note:

- It is given in 3-6 weeks after surgery. Dose is 50-70 Gy; 1.5- 2.0 Gy in 5-8 weeks
- RT is delayed for 6 weeks if nerve grafting is done
- Neuron beam therapy is used

Complications

- Xerostomia
- Osteoradionecrosis of temporal bone/mandible
- Skin ulcers, mucositis
- Fibrosis of optical apparatus, brainstem injury
- Trismus due to fibrosis of masseter, pterygoids and TM joint
- Otitis media, localized hair loss

♦ *Chemotherpy*

It is also given. Drugs given here depends on tumour type. Intra-arterial chemotherapy is beneficial. But overall efficacy of chemotherapy is very less compared to RT. 5 FU, cisplatin, doxorubicin, epirubicin, cetuximab are used.



Figs 4.33A and B: Recurrent parotid tumour right side. Note the scar of previous surgery. It was adenoid cystic carcinoma. Recurrent has occurred after 6 years. Patient underwent radical parotidectomy. Neck nodes are involved in this patient even though it is rare in adenoid cystic carcinoma.

You will soon break the bow if you keep it always stretched.

- ***Preoperative radiotherapy***
  It is given in large tumours to reduce the size and make it better operable, i.e. to down stage the disease.
- If lymph nodes are involved, which is confirmed by FNAC, radical neck dissection is done. It is also done in N0 with high-grade tumour or T3/T4 tumours.

In Submandibular Salivary Gland

Wide excision is done, with removal of mandible, and soft tissues around—extraglandular excision. If lymph nodes are involved, then block dissection of the neck is done.

MINOR SALIVARY GLAND TUMOURS

- It is 10% of salivary tumours.
- It is common in — *palate* (40%).
  — *lip*.
  — *cheek*.
  — *sublingual glands*.
- *Palate* is the commonest site.
- 10% are benign—*commonly pleomorphic adenomas*.
- 90% are malignant—*commonly adenoid cystic carcinomas*.
- They present as swelling with ulcer over the summit.
- If it is malignant, then extension into the palate, maxilla, pterygoids can occur often with involvement of the lymph node.

Differential Diagnosis

Squamous cell carcinoma of oral cavity.

Investigations

1. Incision biopsy.
2. CT scan.
3. X-ray maxilla.
4. FNAC of lymph node.

Treatment

- Wide excision often with palatal excision or maxillectomy is done—for malignancy.
- If the tumour is *less than 1 cm* in size excision biopsy is done with 1 cm clearance margin. If the tumour is *more than 1 cm* in size, initially incision biopsy is done and then wide excision is done. Even in larger defect in hard palate region, it usually re-epithelialise if once left open to allow it to granulate. If bony palate is infiltrated then that part of palate bone is removed to get a clearance; area is reconstructed by moulds, synthetic materials.
- Reconstruction by dental plates, skin grafting, or flaps are done.
- Lymph node block dissection of the neck is done if involved.
- Excision with primary closure is done for benign tumours.



Figs 4.34A and B: Minor salivary gland tumour in the palate. Palate is the common site of minor salivary gland tumour.



Figs 4.35A and B: Minor salivary gland tumour of hard palate. It is excised with 1 cm margin; area is allowed to granulate and epithelialise.

Points to be remembered

- Salivary gland tumours are usually benign in an adult
- It is rare in children but when it occurs, it is commonly malignant
- Clinical and FNAC are diagnostic methods
- Open biopsy is contraindicated
- Sialogram is not useful in salivary tumours
- CT scan or MRI are often needed
- Nerve should be preserved in benign lesions
- Nerve can be sacrificed to achieve clearance in malignancies

PAROTID LYMPHOMA

- Parotid lymphoma can occur from the lymph nodes in the gland or from parotid parenchyma.
- It can occur in HIV patients; lymphoepithelial diseases and in Sjögren's syndrome.
- Common in elderly.
- Disease may be confined to parotid gland or may involve other nodes in neck, mediastinum.
- When it is confined to parotid total parotidectomy with radiotherapy and later chemotherapy is the treatment.
- When many other nodes are involved chemotherapy is the choice therapy.

Note:

Lymphoma occasionally can occur in other salivary glands also (10% of all salivary lymphomas).

PAROTIDECTOMY

Types

1. *Superficial parotidectomy*: It is the removal of superficial lobe of the parotid (superficial to facial nerve). Done in case of benign diseases of superficial lobe of the parotid.

Steps in parotidectomy

- Lazy 'S' incision—modified Blair's/Sistrunk's approach and raising the skin flaps
- Mobilisation of the gland
- Flap is reflected in front *just up* to anterior margin of the parotid; never beyond. After identification of sternocleidomastoid great auricular nerve is identified and can be sacrificed. Posterior belly of digastric is identified.
- Location of *stylomastoid branch* of posterior auricular artery is anterior to facial nerve trunk which enters the stylomastoid foramen.
- *Thrust* the mosquito haemostat 5 mm in front of facial nerve; *open* the blades for 5 mm; *lift* the blades for 5 mm.
- One should worry about the nerve not small bleeding and haemostasis.
- Identification of facial nerve trunk
- Dissection of the gland off the facial nerve using bipolar cautery
- Removal of parotid—superficial/both
- Distilled water (hypertonic) irrigation to kill spilled tumour cells
- Haemostasis and closure with a suction drain

2. *Total conservative parotidectomy*: It is done in benign diseases of parotid involving either only deep lobe or both superficial and deep lobes. Here both lobes are removed with preservation of facial nerve. Here initially superficial parotidectomy is done and facial nerve and its branches are retracted gently and deep lobe is removed.
3. *Radical parotidectomy*: Both lobes of parotid are removed along with facial nerve, fat, fascia, muscles (masseter,



Fig. 4.36: Incision for parotidectomy. Typical lazy 'S'.



Fig. 4.37: 'S' shaped incision for parotidectomy.



Fig. 4.38: On table exposure of facial nerve branches after superficial parotidectomy for a benign tumour.

pterygoids and buccinator), lymph nodes. It is done in case of carcinoma parotid. Later facial nerve reconstruction is done using great auricular nerve graft.

Conservative surgeries are becoming popular for malignancy but they are not universally accepted.

4. *Suprafacial parotidectomy* is done in lower pole parotid tumours wherein all branches of the facial nerve need not be dissected.

Identification of facial nerve

- Facial nerve is 1 cm deep and below the tip of the inferior portion of the cartilaginous canal—*Conley's point*
- By nerve stimulator
- It is inferomedial to tragal point
- Deep to digastric muscle and tympanic plate
- Nerve is just lateral to the styloid process
- Tracing branch from distal to proximal (Hamilton-Bailey technique)

Complications of parotidectomy

- Facial nerve injury
- Haemorrhage
- Salivary fistulas
- Infection—Flap necrosis is common
- Frey's syndrome
- Sialocele
- Numbness over the face and ear - due to injury to great auricular nerve. Female patients find difficult to wear ear rings. Spontaneous recovery may occur in 1½ to 2 years.

FREY'S SYNDROME (Auriculotemporal Syndrome, Gustatory Sweating); (Lucie Frey—Polish Surgeon—1932)

- Occurs in 10% of cases.
- It is due to injury to the auriculotemporal nerve, wherein post-ganglionic parasympathetic fibres from the otic



Figs 4.39A to D: Steps in parotidectomy and demonstration of facial nerve. Note the placement of drain after surgery (*Courtesy:* Professor Kishore Chandra Prasad, ENT Surgeon and HOD, KMC, Mangalore; Dr Sampath, MS, ENT, KMC, Mangalore).

ganglion become united to sympathetic nerves from the superior cervical ganglion (Pseudosynapsis). *There is inappropriate regeneration* of the damaged parasympathetic autonomic nerve fibers to the overlying skin.

- Auriculotemporal nerve has got two branches. Auricular branch supplies external acoustic meatus, surface of tympanic membrane, skin of auricle above external acoustic meatus. Temporal branch supplies hairy skin of the temple. Sweating and hyperaesthesia occurs in this area of skin.

Causes

1. Surgeries or accidental injuries to the parotid.
2. Surgeries or accidental injuries to temporomandibular joint.

Clinical Features

- Flushing, sweating, erythema, pain and hyperaesthesia in the skin over the face innervated by the auriculotemporal nerve, whenever salivation is stimulated (i.e. during mastication).
- Condition causes real inconvenience to the patient.
- Involved skin is painted with iodine and dried. Dry starch applied over this area will become blue due to more sweat in the area in Frey's syndrome—***Starch iodine test.***

Treatment

- Initially conservative and reassurance. Most often they recover without any active treatment in 6 months. Antiperspirants, anticholinergics like scopolamine 3%, glycopyrrolate 1%, methyl sulfate, radiation 50 Gy are used.



Fig. 4.40: Parasympathetic and sympathetic supply of the parotid gland. Otic ganglion located just below the foramen ovale close to mandibular nerve relays the parasympathetic supply from glossopharyngeal nerve through tympanic branch, tympanic plexus in middle ear and then lesser superficial petrosal nerve. Postganglionic fibres run in auriculotemporal nerve along with unrelayed sympathetic fibres from middle meningeal plexus.

- Occasionally (10%) they require surgical division of the tympanic branch of the glossopharyngeal nerve below the round window of middle ear [i.e. intratympanic parasympathetic (Jacobsen nerve) neurectomy].
- Dermal/fat graft; avulsion of auriculotemporal nerve; interposition of temporal fascia, fascia lata, sternomastoid muscle, acellular human dermal collagen; alcohol injection—are all tried.

Note:

Incidence is higher with a flap elevation superficial to platysma. Elevation of thick flap or insertion of fat flap under skin during surgery may reduce the chance of Frey's syndrome.

Treatment of Frey's syndrome

- Reassurance
- Jacobsen neurectomy (tympanic)
- Injection of botulinum toxin to the affected skin
- Antiperspirants like aluminium chloride
- Syndrome can be *prevented* on table by placing muscle (sternomastoid) or fascial (temporalis) flaps or artificial membranes over parotid bed, under the skin

FACIAL NERVE INJURY (Lower Motor Nerve Lesion, Surgically Related)

Causes

- Trauma
- Surgery—parotidectomy, drainage of parotid abscess
- Compression of facial nerve—Bell's palsy.
- Incidence of temporary/transient facial nerve palsy after parotidectomy is 30%. Recovery occurs usually in 12 weeks.
- It is due to transection of trunk or branches or excessive traction or over use of nerve stimulator.

Clinical Features

- Inability to close the eyelid.
- Difficulty in blowing and clenching.
- Drooping of the angle of the mouth.
- Obliteration of nasolabial fold.
- Loss of forehead wrinkles.
- Wide palpebral fissure.
- Epiphora.

Treatment

- Nerve grafting using greater auricular nerve, sural nerve, lateral cutaneous nerve of thigh or hypoglossal nerve.
- Suspension of angle of mouth to zygomatic bone using temporal fascia sling.
- Lateral tarsorrhaphy—to prevent corneal ulceration.
- Medial canthus reconstruction—to reduce epiphora.
- Cross facial nerve transplantation from opposite side using its insignificant branches.
- Dynamic neurovascular muscle graft.
- Upper lid gold weights to protect cornea.

Have equal love for all, and experience a life of equanimity.

Surgeries for facial nerve palsy

- *Static*
  - Suspension surgeries using temporal fascia
  - Correction of medial canthus
  - Lateral tarsorrhaphy—to prevent exposure keratitis due to widened palpebral fissure
  - Upper lid weights
- *Dynamic*
  - Muscle transfer—temporal to masseter
  - Free muscle graft. Gracilis muscle neurovascular transfer
  - Cross facial nerve transplant from opposite facial nerve to injured facial nerve using sural nerve
  - Nerve grafts

Heerfordt's syndrome is sarcoidosis of parotid swelling; anterior uveitis; facial palsy and fever.



Figs 4.41A and B: Features of post-parotidectomy facial nerve palsy.

Remember

- **Taste sensation** and general sensation (lingual nerve) should be checked. Patient is not allowed to speak but *asked to write* in a paper. Taste material is instilled on the surface of the diseased side first and then normal side. Prior to each instillation patient should wash his mouth with warm water. Usually four substances are used. After 10 seconds patient should identify the substance and write. *Facial nerve serves 3 tastes—salt* (rock salt) on the tip of tongue; sweet using syrup on the tip of the tongue; *sour* using lemon juice on the lateral aspect of the tongue. Bitter taste is mediated by glossopharyngeal nerve and is tested using quinine on posterior third of the tongue.
- **Secretomotor fibres of parotid:** Secretomotor preganglionic fibres from *inferior salivary nucleus* → glossopharyngeal nerve → tympanic branch → tympanic plexus → lesser superficial petrosal nerve → otic ganglion → post ganglionic fibres → auriculotemporal nerve, branch of mandibular division of trigeminal nerve → parotid gland.
- **Secretomotor fibres of submandibular salivary gland:** Preganglionic fibres from *superior salivary nucleus* → facial nerve → chorda tympani nerve → lingual nerve → Langley's submandibular ganglion → postganglionic fibres → submandibular and sublingual salivary glands.
- Parotid gland is *serous*. Submandibular gland is *mixed* (major is mucous). Sublingual is *mucous*. Minor salivary glands are *mucous* except *von Eber's glands* which empty into the circumvallate papillae and glands in the tongue tip.
- *70% of total saliva* is from submandibular salivary gland. *25% of saliva* is from parotids. 10% of total salivary volume is from minor salivary glands.
- Normal salivary secretion per day is 1500 ml. It is hypotonic fluid with pH 7.0. It contains α-amylase.

Note:

Accessory parotid tumour—Accessory parotid tumour is very rare tumour arising from accessory parotid usually above the parotid duct level in front of the master muscle. It can be benign or malignant. Pleomorphic adenoma is common. Tumour behaves like tumour from main parotid gland. Incidence is 1% of all parotid tumours. 30% of them are malignant. It is located in a line at central 1/3rd of the line joining the middle of the tragus to a point between the ala of the nose and vermilion border of upper lip. FNAC confirms the diagnosis. CT scan confirms the anatomical location. Main parotid gland is usually normal. Surgery is the treatment. Standard parotidectomy incision or direct cheek approach can be used. But direct cheek approach can cause higher incidence of buccal and zygomatic branches of facial nerve injuries (40%). Standard parotidectomy approach has got less chance of nerve branch injuries. Lymph node spread in the neck is dealt with radical dissection. Excision cures the benign disease.

Chapter 5 Neck

CHAPTER OUTLINE

- Anatomy of Lymphatics of Head and Neck
- Thoracic Outlet Syndrome
- Cervical Rib
- Branchial Cyst
- Branchial Fistula
- Pharyngeal Pouch
- Laryngocele
- Cystic Hygroma
- Ludwig's Angina
- Parapharyngeal Abscess
- Retropharyngeal Abscess
- Subhyoid Bursitis
- Carotid Body Tumour
- Torticollis
- Sternomastoid Tumour
- Tuberculous Lymphadenitis
- Cold Abscess
- Secondaries in Neck Lymph Nodes
- Chemotherapy for Head and Neck Cancers

ANATOMY OF LYMPHATICS OF HEAD AND NECK

Waldeyer's Lymphatic Ring (Inner)

It consists of adenoids above, lingual tonsils below and two palatine tonsils laterally one on each side.

Outer Circular Chain of Nodes (Outer Waldeyer's Ring)

Occipital, postauricular, preauricular, parotid, facial, submandibular, submental, superficial cervical and anterior cervical.

Facial nodes are:

a. Superficial
   - Upper—infraorbital.
   - Middle—buccinator.
   - Lower—supramandibular.

b. Deep groups—in relation to pterygoids.

Submandibular lymph nodes drain

- The side of the nose.
- The cheek.
- Angle of the mouth.
- Entire upper lip.
- Outer part of the lower lip.
- The gums.
- Side of the tongue.

Submental lymph nodes: Drain from the central part of the lower lip, floor of the mouth and apex of the tongue.

Superficial cervical nodes: They lie on outer surface of the sternomastoid around the external jugular vein. They drain the parotid region and lower part of the ear.



Fig. 5.1: Inner and outer Waldeyer's ring anatomy.

Deep cervical lymph nodes: Upper deep cervical lymph nodes—jugulodigastric nodes Below the digastric and in front of IJV.

Lower deep cervical lymph nodes—jugulo-omohyoid nodes—Above the omohyoid and behind the IJV.

They drain the ipsilateral half of head and neck, finally form a jugular lymph trunk from lower deep cervical nodes to join thoracic duct on the left side, and the junction of right subclavian and right jugular vein on right side.

Rule of 7 in the neck

- 7 days—inflammation
- 7 months—neoplasm
- 7 years—congenital defect

Note: The Rule of 7 provides a probable diagnosis of the neck mass based on the average duration of the patient's symptoms

Do not worry and hurry so much rather walk this earth lightly and leave your mark.—**Dr Saroj Kanna**



Fig. 5.2: Triangles of the neck.



Fig. 5.3: Lymphatic drainage of the neck.

THORACIC OUTLET SYNDROME (TOS)

It is syndrome complex due to neurovascular bundle compression in the thoracic outlet.

Thoracic outlet has got two main spaces:

- *Scalene triangle* is bound by scalenus anterior, scalenus medius and first rib. It contains subclavian artery and brachial plexus.
- *Costoclavicular space* is bound by clavicle, first rib, costoclavicular ligament and scalenus medius. It contains subclavian artery and vein and brachial plexus.

Causes

- Cervical rib.
- Long C_7 transverse process.
- Anomalous insertion of scalene muscles.
- Scalene muscle hypertrophy.
- Scalene minimus.
- Abnormal bands and ligaments.
- Fracture clavicle or first rib.
- Exostosis.
- Tumours in the region.
- Brachial plexus trauma and diseases.

Differential Diagnosis of TOS

- Carpal tunnel syndrome.
- Cervical spondylosis.
- Spinal canal tumours.
- Shoulder myositis.
- Angina.
- Raynaud's disease.
- Spinal stenosis.
- Ulnar nerve compression, epicondylitis.

Clinical Features

Neurological symptoms

- Paraesthesia.
- Pain in shoulder, arm, forearm and fingers.
- Occipital headache as referred pain from tight scalene muscles.
- Weakness in forearm, hand.

Vascular symptoms

- Claudication, ischaemic ulcers, gangrene.

Signs

- Scalene muscle tenderness.
- Pulsatile swelling in supraclavicular region with thrill and bruit (25%).
- Bony mass above clavicle.
- Adson's test (+ve).
- Roos test (+ve).
- Elevated arm stress test (+ve).
- Costoclavicular compression maneuver.
- Hyperabduction maneuver.

} reveals feeble/absence of radial pulse due to compression of the subclavian artery.

- Poor capillary refilling.
- Absence or feeble pulse.

(*Please refer Chapter on Arterial Diseases for details of tests*).

Investigations

- X-ray neck and cervical spine.
- Doppler.
- Subclavian angiogram, CT angiogram, CT neck.
- Nerve conduction studies, electromyography.

Treatment

- *Conservative*—if nerve velocity is > 60m/second
- *Surgical*—if nerve velocity is < 60m/second

Conservative treatment for TOS

- Exercises—neck stretching, postural and breathing exercises
- Drugs—analgesics, muscle relaxants, antidepressants
- Avoid weight lifting
- Physiotherapy

Surgical treatment of TOS

- Transaxillary (ROOS)—mainly for first rib excision and also cervical rib
- Supraclavicular approach for cervical rib and soft tissue excision, scalenotomy, neurolysis, arterial reconstruction
- Cervical sympathectomy may be needed

CERVICAL RIB

Definition

- It is an extension of costal element (anterior part) of transverse process of C_7 vertebra more than 2.5 cm (normal).
- Syndrome caused by it is called as *cervical rib syndrome, thoracic-inlet syndrome, thoracic-outlet syndrome, scalene syndrome*.
- It is 0.46% common; common in females; more frequent on right side.
- It can be *unilateral or bilateral (50%)* can be *asymptomatic* or *symptomatic*.

Types (Refer Fig. 5.4)

1. *Complete bony*: Cervical rib is radio-opaque, anteriorly ends over the first rib or manubrium.
2. *Complete fibrous*: Cannot be demonstrated radiologically.
3. *Combined*: Partly bony partly fibrous.
4. Partial bony: With free end expanding as *bony mass, which is felt in the neck.*

Pathology

- Cervical rib narrows the scalene triangle (bounded by scalenus anterior, scalenus medius and first thoracic rib below).

Compression of subclavian artery; C_8 and T_1 nerve roots due to cervical rib.
↓
Angulation of subclavian artery occurs.
↓
Causes constriction of artery at the site where artery crosses the cervical rib.
↓
'Eddie's current' created in the blood flow
causes sudden release of pressure distal
to the narrowing.
↓
Poststenotic dilatation → *Venturi phenomenon.*
(due to vessel wall ischaemia)↓
Stasis of blood occur.
↓
Thrombosis → *Embolus.*
↓ ↓
Features of ischaemia in the hand and forearm.
Later digital gangrene occurs.

- Rarely thrombus may extend proximally into the subclavian artery causing vertebrobasilar insufficiency.



Fig. 5.4: Cervical rib types.

- Compression of C_8 and T_1 causes tingling and numbness along its distribution, i.e. in the little finger, medial side of hand and forearm.
- ***Paget-Schroeter syndrome*** is subclavian vein compression by cervical rib. It is rare.



Fig. 5.5: Post-stenotic dilatation of subclavian artery in cervical rib *(Courtesy:* Dr Ashok Shetty, MCh, Cardiothoracic Surgeon, Mangalore*)*.

Clinical Features

Majority of patients are asymptomatic—(80%).

1. ***Vascular manifestations:***
    - *Pain* is due to ischaemia in the muscle. It is more during work, exercise, and is relieved by rest.
    - *Upper limb claudication* usually is observed in forearm and arm more obvious after usage of limb. Pain (dull pain) in posterior triangle of neck may be due to presence rib mass. Ischaemic pain in the digits and hand may be present.
    - *Vasomotor changes* with cyanosis, cold fingers, excessive sweating may be observed.
    - *Roos test* is raising the arm above the shoulder. The side where cervical rib is present, patient cannot continue and so drops the hand down.

Nothing dies quicker than a new idea in a closed mind.

- *EAST—Elevated Arm Stress Test (Modified Roos test)*: Arm is elevated above the shoulder, with elbow stretched fully. Rapid movements of fingers will cause fatigue on the side where cervical rib is present.
- *Adson's test*: The hand is raised above after feeling the radial pulse. The patient is asked to take a deep breath and turn the head to the same side. Any change in pulse, i.e. either becoming feeble or absent, is noted.
- *Modified Adson's test* is same as Adson's, but neck is turned towards the opposite side.
- *Costoclavicular compression manoeuvre*: While palpating the radial pulse of the patient he is asked to move his shoulder backwards and downwards (*exaggerated military position*) which may cause absence/feeble radial pulse and a bruit may be heard while auscultating the supraclavicular region—*military attitude test.* This is due to compression of subclavian artery between clavicle and first rib. Similary *Halstead manoeuvre* is done by 45° abduction and extension of arm with downward pushing of the shoulder with neck turned opposite side to cause radial pulse feebly palpable.
- *Hyperabduction manoeuvre (Wright's test):* While palpating the radial pulse, arm on the diseased side is passively hyperabducted causing feeble or absence of radial pulse. This is due to compression of artery by pectoralis minor tendon (*pectoralis minor syndrome*). An axillary bruit may be heard on auscultation.
- *Allen's test*: It is used in hand to find out the patency of radial and ulnar arteries. Both radial and ulnar arteries of the patient is felt and pressed firmly at the wrist. Patient clinches his hand firmly (often repeated clinching) and holds it tightly. After 1 minute clinch is released to open the palm of the hand which looks pale. Pressure on radial artery in the wrist is released to see area of distribution of the radial artery. Normally it becomes flushed with pink color. If there is block in radial artery, the area will remain white. Test is repeated again. This time pressure on the ulnar artery is released to check the patency of ulnar artery. Area will be pale and blanched after releasing in case of ulnar artery block. Otherwise it becomes pink after release in normal individual.
- ***Wasting*** of thenar, hypothenar and forearm muscles.
- Often digital gangrene, ischaemic ulcers in digits, oedema of fingers and hand are observed.
- Limb is colder and paler than the opposite side.

2. ***Neurological features*** is due to compression of T_1 and C_8 causing tingling and numbness in the little finger, medial side of hand and forearm.
    - Pain, on the medial side, weakness on the medial side of hand and anaesthesia may be evident.
    - *Card test* for interossei muscle weakness, *Froment's sign*/test to detect weakness in adductor pollicis are positive. Wasting may be due to neurological cause also.
3. ***Features in the neck:***
    - Hard, fixed, bony mass in the supraclavicular region.
    - *Palpable thrill* above the clavicle in the subclavian artery.
    - *Bruit* on auscultation.



Figs 5.6A to C: Anatomy of cervical rib and its relation to subclavian artery and vein and brachial plexus. Note the Eddie's current, post-stenotic dilatation due to arterial compression by cervical rib. X-ray picture shows left sided complete cervical rib.



Fig. 5.7: *Allen's test* done upper limb ischaemia to look for perfusion of hand.



Fig. 5.8: Adson's test—after palpating radial pulse, elbow stretched hand is slightly raised; neck is turned to same side; deep breath is taken; feeble or pulse becoming absent may be obvious in positive Adson's.



Fig. 5.9: Upper limb ischaemia showing ischaemic ulcers and gangrene of finger tips.

Note:

- Most common presentation is *neurological.*
- Most problematic presentation is vascular which requires surgery.

Differential Diagnosis

1. Cervical spondylosis—to differentiate, X-ray neck—lateral view should be taken.
2. Carpal tunnel syndrome.
3. Tumours or swellings compressing over the vessel or nerves in the neck.
4. Other causes of digital gangrene like atherosclerosis, Raynaud's syndrome, collagen diseases, diabetes mellitus, and embolism.
5. Syringomyelia, motor neuron disease.
6. Pancoast tumour.

Investigations

- Chest X-ray PA view and lateral view including neck—only (radio-opaque) bony rib can be identified.
- Nerve conduction studies to confirm neurological compression and also to rule out carpal tunnel syndrome or cervical spondylosis.
- Arterial Doppler of subclavian artery and of the upper limb.
- Subclavian angiogram.
- Other relevant investigations like blood sugar, lipid profile, cardiac assessment.
- CT scan neck and thorax and CT angiogram of subclavian artery are ideal investigations.

Treatment

Note:
For ***conservative treatment*** refer TOS above.

Surgical

1. In symptomatic cervical rib without arterial compression (subclavian artery), along with scalenotomy (cutting scalenus anterior muscle), extraperiosteal resection of cervical rib and often resection of first rib is done to increase the thoracoaxillary channel and so as to reduce arterial compression.
2. In symptomatic cervical rib with significant subclavian artery compression along with scalenotomy, extraperiosteal resection of cervical rib, resection of first rib, subclavian artery reconstruction with or without a graft is done.
3. Along with scalenotomy, extraperiosteal resection of cervical rib, resection of first rib, reconstruction of subclavian artery, cervical sympathectomy is also done to improve the circulation to the ischaemic upper limb.
4. Amputation of the gangrenous toe.
5. In pectoralis minor syndrome, pectoralis minor tendon is released from its insertion to coracoid process.

Approaches

- Supraclavicular approach—mainly when there is need for vascular reconstruction
- Transaxillary approach—through axillary crease, rib is approached and removed
- Thoracotomy approach

BRANCHIAL CYST

It arises from the remnants of second branchial cleft. Normally 2nd, 3rd, 4th clefts disappear to form a smooth neck. Persistent 2nd cleft is called as *cervical sinus (of His)* which eventually gets sequestered to form *branchial cyst.*

Epithelial infusion within lymph node may be the other cause as branchial cyst contains lymphoid tissues in their wall.

Six branchial arches with five pharyngeal pouches (endoderm lining) inside and five pharyngeal clefts (ectoderm lining) outside are present.

Features

- Swelling in the neck beneath the anterior border of upper third of the sternomastoid muscle. It is smooth, soft, fluc-



Figs 5.10A and B: Branchial cyst. It is only occasionally transilluminant.

tuant, often transilluminant with a sensation of '*Half-filled double hot water bottle*'.

- It is equal in both sexes. Even though congenital, it is seen in late adolescents and early 3rd decade.
- Usually painless unless it is infected.
- It contains *cholesterol crystals* which is from the lining of mucous membrane which contains sebaceous gland. *Cheesy toothpaste like* material is typical
- Histologically, it is lined by *squamous epithelium*. Occasionally it contains ciliated columnar epithelium. Cyst wall shows plenty of *lymphoid* tissue.
- It may get infected to form an abscess.
- FNAC shows *cholesterol crystals*.

Complications

- Recurrent infection.
- Rupture may cause *acquired branchial fistula* at upper third of sternocleidomastoid muscle.

Differential Diagnosis

1. Cold abscess, lipoma neck.
2. Lymph cyst.
3. Chronic lymphadenitis.

Treatment: *Excision* under G/A.
Cyst is in relation to carotids, hypoglossal nerve, glossopharyngeal nerve, spinal accessory nerve, posterior belly of digastric and pharyngeal wall. Medially it is close to the posterior pillar of tonsils. During dissection, all these structures should be taken care of.

Complications of Surgery

- Injury to major structures.
- Infection.
- Recurrence/fistula formation due to incomplete removal of the track.

Cholesterol crystals are seen in:

- Branchial cyst
- Dentigerous cyst
- Hydrocele



Fig. 5.11: Branchial cyst—both sides.



Fig. 5.12: Positions of branchial cyst and fistula.

BRANCHIAL FISTULA

Branchial fistula is ***commonly a congenital lesion***. It is due to *persistent precervical sinus* between 2nd branchial cleft and 5th branchial cleft having opening in the skin at lower 1/3rd of neck on the inner margin of sternocleidomastoid muscle, often ends as a *sinus* just proximal to the posterior pillar of fauces behind tonsil which is also the site of inner opening when presents as *fistula*. Fistula runs between the structures related to 2nd and 3rd branchial arches (2nd arch artery is ECA, nerve is facial; 3rd arch artery is ICA, nerve glossopharyngeal). From external opening at skin below, it runs in subcutaneous plane to pierce deep fascia at level of thyroid cartilage; to travel between ECA and ICA; behind posterior digastric belly and stylohyoid; outer to IJV, stylopharyngeus, hypoglossal and glossopharyngeal nerves; perforates superior constrictor to reach the internal opening.

Occasionally ***acquired branchial fistula*** can occur due to rupture of or after drainage of infected branchial cyst or incomplete excision of the cyst track. This type of fistula is located outside at skin at the level of upper third of sternomastoid muscle.

Features

- It is a persistent second branchial cleft with a communication outside to the exterior. It is commonly a congenital fistula. Occasionally, the condition is secondary to incised, infected branchial cyst.
- Often it is bilateral (30%).
- *External orifice* of the fistula is situated in *the lower third of the neck* near the anterior border of the sternomastoid muscle.
- *Internal orifice* is located on the anterior aspect of the posterior pillar of the fauces, just behind the tonsils.
- Sometimes fistula ends internally as blind end.
- Track is lined by *ciliated columnar epithelium* with patches of lymphoid tissues beneath it, causing recurrent inflammation.
- It usually presents at birth. It is common in *children* and early adolescent period. Equal in both sexes.
- *External orifice* is very small with a *dimple* which becomes more prominent on dysphagia with *tuck in appearance*.
- *Discharge* is mucoid or mucopurulent.



Figs 5.13A and B: Branchial fistula in two different patients. Note the location and discharge (*Courtesy:* Professor Kishore Chandra Prasad, ENT Surgeon and Head of the Department and Dr Sampath ENT Surgeon, KMC, Mangalore)

Investigations

Discharge study, fistulogram, MR/CT fistulogram.

Treatment

Always surgery:

- Under general anaesthesia, methylene blue is injected into the track. Probe is passed into the fistulous track. Through circumferential/elliptical incision around the fistula opening,



Figs 5.14A and B: Branchial fistula is usually operated using two transverse parallel incisions with step ladder dissection (*Courtesy:* Br Ganesh Pai, MCh)

There is only one degree difference between hotwater and steam.

entire length of the track is dissected until the internal orifice. Care should be taken to safeguard carotids, jugular vein, hypoglossal nerve, glossopharyngeal nerve and spinal accessory nerve. *Entire track should be excised.*

- *Step ladder dissection* is done using two parallel incisions one below at lower part another above at upper part of the neck, will make dissection easier and complete.

PHARYNGEAL POUCH

- It is a protrusion of mucosa through *Killian's dehiscence*, a weak area of the posterior pharyngeal wall between *thyropharyngeus (oblique fibres)* and cricopharyngeus (*transverse fibres*) of the *inferior constrictor muscle* of the pharynx.
- Thyropharyngeus is supplied by pharyngeal plexus from cranial accessory nerve. Cricopharyngeus is supplied by external laryngeal nerve.
- Pharyngeal pouch is a pulsion diverticulum. It starts in the midline of posterior pharyngeal wall. Once it expands and reaches the vertebra, it deviates towards left side of the neck because of resistance of vertebra.
- Imperfect relaxation of the cricopharyngeus increases the pressure in the pharynx, mainly during swallowing which leads to protrusion of mucosa through the Killian's dehiscence causing pharyngeal pouch.
- *The protrusion is usually towards left.*

Stages

1. Small diverticulum pointing towards vertebra. It is asymptomatic and incidentally diagnosed by barium meal X-ray. Foreign body sensation in pharynx may be present.
2. Large, globular diverticulum with vertical mouth/opening causing regurgitation, violent cough, dysphagia, respiratory infection. Regurgitation is more after meals and while turning the neck.
    - Large pouch which is visible in the neck as a globular swelling often tender, smooth and soft. Swelling is below the level of the thyroid cartilage and behind sternocleidomastoid muscle and can be emptied on pressure. Opening of the pouch is not vertical but horizontal. They present with dysphagia, features of respiratory infection like pneumonia and lung abscess, weight loss and cachexia. Pouch may itself get infected and may form an abscess. Often the pouch may descend downward and enter the superior mediastinum. Gurgling sound in the neck is observed.



Fig. 5.15: Pharyngeal pouch (*Zenker's diverticulum*).

Problems in pharyngeal pouch

- Progressive dysphagia
- Respiratory problems like pneumonia, lung abscess
- Abscess in the neck due to infection in the pouch
- Weight loss and cachexia

Differential Diagnosis

- Branchial cyst.
- Cold abscess in the neck.
- Lymph cyst.
- Haemangioma neck.

Clinical Features

- Pain, dysphagia, recurrent respiratory infection, swelling in the neck on the left side which is smooth, soft and tender.
- Regurgitation during night while turning neck, smooth, soft, tender swelling in the posterior triangle of the left side of the neck; typical gurgling noise while swallowing—are typical features. It is common in males.
- Swelling is deep to sternocleidomastoid muscle below the level of thyroid cartilage; initially soft and emptying; impulse on coughing may be evident unless opening of the pouch is blocked due to recurrent inflammation.

Investigations

- *Barium swallow*—lateral view shows pharyngeal pouch.
- Chest X-ray shows pneumonia.
- CT neck is very useful.



Fig. 5.16: Barium study showing pharyngeal pouch.

***Note*:**
Oesophagoscopy should be gentle or avoided as scope may enter the friable pharyngeal pouch and can cause perforation and life threatening mediastinitis.

Treatment

- Antibiotic is started to control infection.
- *Pharyngeal pouch is excised* by an oblique neck incision (approach from neck). As there is cricopharyngeal spasm, *cricopharyngeal myotomy* (i.e. cutting of cricopharyngeal circular muscle fibres without opening mucosa) is done to prevent the recurrence.

Indications for surgery

- Progressive symptoms.
- Recurrent respiratory complications.
- Dysphagia.

Technique

- Under anaesthesia endoscope is passed to identify the opening of the pouch.
- Pouch is packed with acriflavine soaked gauze for identification of the pouch.
- Under anaesthesia nasogastric tube is passed into the oesophagus under visualisation.
- Pouch is approached through neck with oblique incision along the anterior margin of sternocleidomastoid muscle for proper removal.
- Myotomy of cricopharyngeus and upper circular muscle of the oesophagus is done to relieve the spasm, at posterior midline.
- *Dohlman's operation* is endoscopic excision of the pharyngeal pouch.

Complications of surgery

- Infection, either mediastinitis or lung infection (Pneumonia or lung abscess)
- Pharyngeal fistula
- Abscess in the neck
- Oesophageal stenosis and recurrence

LARYNGOCELE

- It is a unilateral narrow necked, air containing diverticulum resulting from herniation of laryngeal mucosa.
- It occurs in professional *trumpet players, glass blowers and in people with chronic cough.*

Types

a. **External:** It is situated in the anterior third of the laryngeal ventricle, between the false cords and thyroid cartilage, herniates through the *thyrohyoid membrane* where it is pierced by superior laryngeal nerve.

b. **Internal:** Confined within the larynx, presents as a distention of false cords.

c. **Combined**.



Fig. 5.17: Laryngocele.

Clinical Features

- Swelling in the neck in relation to larynx, adjacent to thyrohyoid membrane which is smooth, soft, *resonant* and is more prominent while blowing, coughing and Valsalva manoeuvre.
- It moves *upwords* during swallowing with *expansile impulse* on coughing.
- Infection is quite common in the sac of laryngocele, leading to the blockade of opening of the sac causing an abscess.
- Pus often may be discharged into the pharynx repeatedly.
- Hoarseness and cough.
- If large, causes obstruction to larynx.



Fig. 5.18A

One-third of congenital torticollis is due to sternomastoid tumour and two-third due to abnormal position in utero which recovers spontaneously in a few weeks.
— Kenneth F Hulbert



Figs 5.18B and C

Figs 5.18A to C: Typical laryngocele in the neck which becomes prominent after blowing. X-rays (AP and lateral) show radiolucent air in the neck.

Diagnosis

Clinical features, X-ray neck, laryngoscopy, CT scan.

Treatment

External laryngocele: Excision through neck incision. Neck of the sac should be ligated. Thyrohyoid membrane is repaired using 3 zero nonabsorbable polypropylenes sutures.

Internal laryngocele: Marsupialisation, with the help of laryngoscope.

CYSTIC HYGROMA (Cavernous Lymphangioma)

- It is a cystic swelling due to sequestration of a portion of jugular lymph sac from the lymphatic system, during the developmental period *in utero*.
- Present at birth and so may cause obstructed labour. Occasionally present in early infancy.
- It is also called as ***hydrocele of the neck***.
- Cyst will not communicate with normal lymphatics and so existing lymph gets absorbed and cyst will be filled with clear watery mucous derived from endothelial lining of the cyst wall. Cyst even though is subcutaneous; it commonly extends into deeper planes across many anatomical planes and barriers. Cyst is *multilocular*. Often extension may occur across two or more lymphatic regions; example—involvement of both neck and axilla.
- *Lymphangioma circumscripta* (< 5 cm), *lymphangioma diffusum* (> 5 cm) and *lymphangioma ab agne* (reticulate pattern) are different variants. For detail refer chapter 'Swelling'.

Sites

1. *Posterior triangle of the neck*—75%—most common site. Eventually may extend upwards in the neck
2. Axilla—20%
3. Cheek
4. Tongue—lymphangiogenetic macroglossia
5. Groin
6. Mediastinum
7. Often multiple sites

Pathology

- It contains aggregation of cysts looking like *soap bubbles*. Cysts have *mosaic appearance* with larger cysts near the surface and smaller cysts in the deeper planes. Each cyst



Fig. 5.19: Cystic hygroma in newborn baby.

contains clear lymph with endothelial lining. Fluid *does not* coagulate.

Clinical Features

- Swelling is *present at birth* in the *posterior triangle of neck* causing obstructed labour.
- Swelling is smooth, soft, fluctuant (cystic), *partially compressible*, *brilliantly transilluminant*. It is *not reducible* completely.
- During crying swelling often increases in size.
- *Disfigurement* of face of the child which is more worrying factor for the parents.
- Swelling may rapidly increase in size causing *respiratory obstruction*—dangerous sign.
- It may get infected forming an *abscess* which is a tender, warm, soft swelling. It may cause septicaemia which may be life threatening.
- Rupture with lymph ooze can occur.



Fig. 5.20: Cystic hygroma.

Treatment

- Aspiration of the contents. Later once the sac or capsule gets thickened by fibrous tissue, it is excised.
- Care should be taken to have meticulous dissection across all planes including deeper muscular one to *clear entire cyst wall*; otherwise recurrence will occur.
- When it causes respiratory obstruction, *aspiration* and *tracheostomy* is done.
- Under proper antibiotics coverage, drainage of abscess is done. Later sac is excised.
- Preoperative injection of sclerosants (OK 432, PICIBANIL recently used) and later once fibrosis develops excision of entire aggregation of cysts. In olden days injecting boiling water into the cyst as a sclerosant used to be popular.

Complications

- Respiratory distress
- Infection Abscess Septicaemia
- Surgery itself may cause torrential haemorrhage

LUDWIG'S ANGINA

- It is an inflammatory oedema of submandibular region and floor of the mouth, commonly due to streptococcal infection.
- It causes diffuse swelling and brawny oedema of the submandibular region. It is common in severely ill and in advanced malignancy, causing *trismus, laryngeal oedema*. Extension of infection into *parapharyngeal space* may lead to dreaded *internal jugular vein thrombosis*.
- As the infection is deep to the deep fascia in a closed fascial plane, it spreads very fast causing dangerous complications.

Precipitating factors

- Caries teeth
- Oral or other malignancy
- Submandibular salivary infection/calculi
- Chemotherapy
- Chronic diseases like diabetes mellitus
- Cachexia of any cause

Special features

- Brawny oedema/diffuse swelling of submandibular and submental region
- Intraoral oedema in floor of the mouth
- Putrid halitosis
- Severe toxicity
- Dyspnoea, dysphagia
- May cause laryngeal oedema, septicaemia, extension of sepsis into other spaces in the neck



Fig. 5.21: Typical Ludwing's angina.

It is better to aim at good things and miss it , than to aim at a bad thing and hit it.

Clinical Features

- Fever, toxicity, diffuse swelling, dysphagia, dyspnoea, trismus.
- Intraoral oedema is common.
- Brawny swelling in submandibular region.
- Putrid halitosis.

Treatment

- Antibiotics.
- IV fluids.
- *Decompression of the submandibular region is done,* by making a deep incision extending into the deep fascia and also *cutting both the mylohyoid muscles*. Either it is left open and *delayed suturing is done* (better option) or it is loosely sutured.

Complications

- Laryngeal oedema and respiratory distress, may require tracheostomy
- Septicaemia
- Extension of infection into parapharyngeal space



Fig. 5.22: Incision for draining Ludwig's angina.



Fig. 5.23: Abscess in submandibular region. Note the redness and swelling. It needs incision and drainage under general anaesthesia.

PARAPHARYNGEAL ABSCESS

- It is *infection of pharyngomaxillary space*.
- This is a cone-shaped space; base is formed by the base of skull; apex is formed by the greater cornu of hyoid bone; medial wall by the superior constrictor; lateral wall is formed by the lateral pterygoid, angle of mandible and below by submandibular salivary gland.
- Usually, infection arises from the tonsils, after tonsillectomy and from the submandibular space.

Clinical Features

- It causes diffuse swelling in the upper neck, trismus, fever, toxicity.
- Swelling lies behind the posterior pillar with oedema of soft palate.

Complications

- Thrombosis of internal jugular vein.
- Erosion into the internal carotid artery causing torrential bleeding.
- Septicaemia.

Treatment

- Under G/A, drainage is done by making incision (deep incision) between angle of the mandible and hyoid bone. Early drainage is needed.
- Antibiotics are given.
- Causative pathology should be addressed.

RETROPHARYNGEAL ABSCESS

Surgical Anatomy

The wall of the pharynx has got 5 layers. Mucosa, submucosa, pharyngobasilar fascia, muscular layer (contains 3 constrictors and stylo, salpingo, palatopharyngeus muscles) and buccopharyngeal fascia covers outer part of constrictors and extends over buccinator. Buccopharyngeal fascia is adherent to prevertebral fascia posteriorly in the midline. Retropharyngeal lymph nodes are located between buccopharyngeal fascia and prevertebral fascia in paramedian (eccentric) position (not midline).

Types

- Acute.
- Chronic.

Acute Retropharyngeal Abscess

- It is infection and suppuration of retropharyngeal lymph nodes due to staphylococci or streptococci organisms.
- Commonly from tonsils or pharynx.
- Common in infants and children.

Clinical Features

- It presents as *lateral (paramedian, eccentric) smooth, tender swelling* in the pharynx with dysphagia, dyspnoea, cough, toxic features and neck rigidity.
- Diagnosis is obvious on proper clinical examination.



Normal anatomy



Acute retropharyngeal abscess



Chronic retropharyngeal abscess

1. Pharyngeal wall; 2. Buccopharyngeal fascia; 3. Retropharyngeal LN; 4. Prevertebral fascia; 5. Median septum; 6. Vertebra

Fig. 5.24: Note acute and chronic retropharyngeal abscess. Normal anatomy is also shown. Acute is eccentric and is due to suppuration of retropharyngeal lymph nodes. Chronic is central, midline and is due to tuberculosis of the cervical vertebra.

Treatment

- Antibiotics intravenously.
- Drainage is done usually *through per oral incision* under careful general anaesthesia. Only occasionally drainage may be done through a neck incision. Pus should be sent for culture.

Chronic Retropharyngeal Abscess

- It is invariably due to tuberculosis of cervical spine.
- Abscess is in the *midline behind the prevertebral fascia.*
- There is destruction of the body of the vertebra due to tuberculosis.

Clinical Features

- It is *midline swelling in the posterior pharyngeal wall,* which is smooth and nontender.
- Features of tuberculosis of cervical spine will be observed.
- Often abscess may point in the neck in relation to sternomastoid.
- Neurological manifestations may occur in severe disease.

Investigations

X-ray spine, chest X-ray, ESR, MRI of cervical spine are essential investigations.

Treatment

- Antitubercular drugs.
- Drainage of the abscess should be done *through neck approach (never intraoral approach).*
- Decompression of the vertebra and stabilisation is also often required.



Fig. 5.25: X-ray neck showing retropharyngeal abscess with tuberculosis lesion involving the C_2 cervical spine (*Courtesy:* Dr Navin Chandra Shetty, MD, Radiologist, Professor and Head, Department of Radiodiagnosis, KMC, Mangalore).

SUBHYOID BURSITIS

- Subhyoid bursa is space between posterior surface of the body of hyoid bone and thyrohyoid membrane. It lessens friction between these two structures during swallowing.
- Due to constant friction inflammatory fluid collects in the bursa leading to bursitis, which presents like a *horizontally placed* midline swelling between lower part of the hyoid bone and thyrohyoid membrane.

Features

- Smooth, soft, cystic, fluctuant, nontransilluminating swelling which moves upwards with deglutition but *not while protruding the tongue out*.
- It should be differentiated from thyroglossal cyst and pretracheal lymph nodes.
- It contains turbid fluid often may get infected to make the swelling tender or to form an abscess.



Fig. 5.26: Sagittal and front view showing location and relation of subhyoid bursa.

Happiness is a direction not a destination.

Treatment

- Excision under general anaesthesia.

CAROTID BODY TUMOUR (Potato Tumour, Chemodectoma, Nonchromaffin Paraganglioma)

- It arises from the carotid body, which is located at the bifurcation of the common carotid artery.
- The tumour is situated in the adventitia of the artery.
- They are benign or locally malignant tumours (10%), but in 20% cases spread can occur to the regional lymph nodes and lungs.
- Blood supply to the tumour is from *external carotid artery*. Tumour does not secrete epinephrine or any endocrine substances. Blood supply comes through *Meyer's ligament* on the posteromedial wall of the carotid at bifurcation.
- They can be *familial*.
- Common in high altitude area, common in females.
- Pathologically, it is well-encapsulated, hard creamy yellowish tumour with dense fibrous tissue. Carotid body tumour cells are not hormonally active.



Fig. 5.27: Carotid body tumour—note the site and location. *Splaying* of the carotid is common.

Carotid body

- ❖ Normal carotid body is 3-5 mm sized flat brownish nodule in the adventitious of common carotid artery
- ❖ It consists of chief cells (contains catecholamine granules) and supportive cells
- ❖ It gets its nerve supply from glossopharyngeal nerve
- ❖ These chemoreceptors are sensitive to changes in pH and temperature in the body especially in hypoxia, help in autoregulation of respiration and circulation
- ❖ Carotid body hyperplasia can occur in people residing in high altitudes who are exposed to chronic hypoxia
- ❖ Other chemoreceptors in the body are—aortic bodies in the arch of aorta; glomus jugular in the bulb of the internal jugular vein; glomus intravagale in relation to ganglion nodosum of the vagus nerve and others like pulmonary (near pulmonary artery) and myocardial (near coronary artery origin) receptors

Clinical Features (0.5%—Incidence)

- Usually unilateral.
- More common in middle age.
- Swelling (75%) in the carotid region of the neck which is smooth, firm, pulsatile (*transmitted pulsation*—due to pulsatile carotid vessel overlying its surface) and moves only side to side but not in vertical direction.
- It can often compress over oesophagus and larynx.
- Headache, neck pain (35%), dysphagia, syncope are other presentations.
- It can present with unilateral vocal cord palsy; can cause Horner's syndrome.
- Features of transient ischaemic attacks due to compression over the carotids, *"carotid body syncope."*
- Thrill may be felt and bruit may be heard.
- It is located at the level of hyoid bone deep to anterior edge of the sternomastoid muscle in anterior triangle, vertically placed, round, firm 'potato' like swelling.
- Often tumour may extend into the cranial cavity along the internal carotid artery as *dumbbell tumour*.

Sites where dumbbell tumours are seen

- ❖ Parotid tumour
- ❖ Spinal cord tumour
- ❖ Carotid body tumour

Shamblin classification of carotid body tumor

- ❖ Type I: Localised, easily resectable (26%)
- ❖ Type II: Adherent, partially surrounding the carotids (46%)
- ❖ Type III: Adherent, encased carotids completely (27%)

Investigations

- Doppler.
- Angiogram to see the *'tumour blush'*—DSA. Widening/splaying of the carotid artery with tumour blush in an angiogram is called as *Lyre sign*.
- CT scan, MRI, MR angiography.

No FNAC: No partial excision.

Differential Diagnosis

- Carotid artery aneurysm.
- Soft tissue tumour (Sarcoma).
- Lymph node enlargement.
- *Neurofibroma of the vagus nerve* presents as swelling in the carotid triangle in the region of thyroid as vertically placed, oval, hard swelling. On palpation of the swelling, patient often develops bradycardia and dry cough. It does not move with deglutition and has only transverse mobility. As the tumour lies behind the carotid it can stretch the carotid in front causing transmitted pulsation.

Treatment

- If it is small, it can be excised easily as the tumour is situated in the adventitia.
- When it is large, as commonly observed, *complete excision has to be done followed by placing a vascular graft.*

- During resection a *temporary shunt* (diversion of blood) is placed between common carotid below and internal carotid above to safeguard cerebral perfusion; external carotid artery is ligated. Venous or prosthetic graft is placed between common carotid and internal carotid arteries.
- Carotid body tumour is not *radiosensitive* (controversial).

Complications of the Surgery

- Bleeding.
- Blockage of common carotid artery, leading to contralateral side hemiplegia (3%). This can be prevented by *stenting the common carotid artery* towards internal carotid artery and is done *during surgical excision* of the tumour.
- Cranial nerve injury X and XI (40%).

Cystic swellings in the neck

- Cold abscess
- Cystic hygroma
- Branchial cyst
- Thyroglossal cyst
- Laryngocele
- Pharyngeal pouch
- Subhyoid bursa

TORTICOLLIS (Wry Neck)

It is turning of the neck to one side with chin pointing towards opposite side.

Causes

- Sternomastoid tumour.
- Trauma—spinal injury, disc prolapse, spondylosis.
- Inflammatory: Lymphadenitis either tuberculous or suppurative; tuberculosis of cervical spine.
- Spasmodic—due to spasm of sternomastoid muscle of same side or spasm of posterior cervical muscles of opposite side.
- Reflex.
- Rheumatic—after exposure to cold/draught.
- Burns—causing contracture.



Fig. 5.28: Boy having right-sided torticollis.

- Ocular causes.
- Compensatory due to scoliosis.

Clinical Features

- Restricted neck movements.
- Chin pointing towards opposite side.
- Squint.
- Features relevant of the causes.

Treatment

The cause is treated.



Fig. 5.29: Torticollis (right-sided) with chin towards opposite side.

STERNOMASTOID TUMOUR



Fig. 5.30: Sternomastoid tumour—typical location.

It is due to birth injury to the sternomastoid muscle. It is a *misnomer*. It is not a tumour.

Pathogenesis

- During child birth, injury to the sternomastoid muscle causes *haematoma* in the muscle which gets organised to form sternomastoid tumour.
- Common in breech delivery.

Clinical Features

- It is seen in infants of 3-4 weeks age.
- Swelling of about 2 cm size, in the sternomastoid muscle which is smooth, hard, nontender and adherent to the muscle—in the middle part.
- Chin pointing towards opposite side. Head towards same side *(Scoliosis capitis)*.
- In later age groups it causes *hemifacial atrophy* due to less blood supply as a result of compression of the external carotid artery by sternomastoid tumour and due to kinking by position of neck. Distance between the outer canthus of eye to angle of mouth is reduced, with less arched eyebrow, flat or less filled cheek and flat nose compared to opposite side.
- Compensatory cervical scoliosis.
- Compensatory squint.

Differential Diagnosis

Other causes for torticollis.

Treatment

- Division of the lower end of the sternomastoid muscle or excision of the muscle. Both sternal and clavicular heads of sternocleidomastoid muscle should be divided under general anaesthesia using horizontal incision. One should not injure IJV, carotid, vagus, spinal accessory nerve. Additional all fibrous bands are also cut. Usually over correction is done. Physiotherapy exercise and toricollis harness is used for 6-12 months.
- Exercise and active stimulation of muscles in early cases.



Fig. 5.31A



Fig. 5.31B

Figs 5.31A and B: Lymphoma neck involving both sides. Lymphomas are smooth, nontender, firm/India rubber consistency.

Differential diagnosis for neck lymph node enlargement

• Tuberculous lymphadenitis	• Secondaries in lymph nodes
• HIV infection	• Lymphomas
• Chronic lymphatic leukaemia	• Nonspecific lymphadenitis
• Infectious mononucleosis	• Sarcoidosis
• Actinomycosis	• Brucellosis
• Toxoplasmosis	



Fig. 5.32: Swelling in the neck well-localised. Note the scar of previous biopsy/excision. It could be lymph node enlargement due to lymphoma or tuberculosis.

TUBERCULOUS LYMPHADENITIS

Causative organism: *Mycobacterium tuberculosis* (not *M. bovis*).

Site

- Common in neck lymph nodes.
- Common in *upper deep cervical (jugulodigastric—54%) lymph nodes.*



Fig. 5.33: Cold abscess in the neck which has formed collar stud abscess. It eventually leads into sinus formation.



Figs 5.34A and B



Fig. 5.34C

Figs 5.34A to C: Cold abscess due to caseating tuberculous lymphadenitis in neck. Collar stud abscess in the neck. Tuberculous sinus formation after drainage.

- Next common is posterior triangle lymph nodes (22%).
- Disease can also occur in other lymph nodes like, axillary lymph nodes, para-aortic lymph nodes, mesenteric lymph nodes, inguinal lymph nodes.
- Disease may be associated with HIV infection, lymphomas.

Mode of Infection

- Usually through the *tonsils*, occasionally through blood from lungs. *Tonsillar* infection shows multiple tubercles on



Fig. 5.35: Tuberculous lymphadenitis—cut section of the specimen. Note the yellowish caseating material with periadenitis (matting). Caseating type is more common than hyperplastic type.

It takes 5 years to learn when to operate, and 20 years to learn when not to.


Stage 1: Lymphadenitis
(Discrete nodes, nontender, firm/hard mobile)
Stage 2: Matting
(Firm, nontender, move together en mass—due to periadenitis)
Stage 3: Cold abscess
(Deep to deep fascia)
Stage 4: Collar stud abscess
(Rupture through deep fascia under the skin, cross-fluctuant, adherent to skin)
Stage 5: Sinus formation

Fig. 5.36: Stages of tuberculous lymphadenitis (*Hogarth's Rake*).

its surface; from here infection spreads into jugulodigastric nodes (anterior triangle nodes) then to other nodes. Infection reach lymph node first into subcapsular space/sinus then to lymph node cortex which contains plenty of lymph follicles. Matting is due to periadenitis involving subcapsular sinus/space of lymph node. In children infection to neck node can come from either tonsils or adenoids or both. When it occurs from *adenoids*, lymph nodes in posterior triangle are involved through retropharyngeal lymphatics.

- It may be associated with pulmonary tuberculosis or renal tuberculosis. Through blood infection reaches medullary cords of lymph node and so medulla of lymph node.
- Rarely spread can occur from tuberculous lesion of the apex of lung through suprapleural Sibson's fascia/membrane to supraclavicular nodes.

Stages of tuberculous lymphadenitis

1. Stage of *infection, and lymphadenitis*
2. Stage of *periadenitis with matting*
3. Stage of *caseating necrosis and cold abscess* formation
4. Stage of formation of *collar stud abscess*
5. Stage of formation of *sinus* which discharges yellowish caseating material

- Often fibrosis and calcification can occur with or without treatment.

Gross Pathology

- Firm, matted, lymph node, with cut section showing yellowish caseating material.

Microscopic Features

- Epithelioid cells with caseating material are seen along with Langhan's type of giant cells.

Clinical Features

- Swelling in the neck which is firm, matted.
- Cold abscess is soft, smooth, nontender, fluctuant, without involvement of the skin. It is not warm.
- As a result of increased pressure, cold abscess ruptures out of the deep fascia to form *collar stud abscess* which is adherent to the overlying skin.
- Once collar stud abscess bursts open, discharging sinus is formed. It can be multiple, wide open mouth, often undermined, nonmobile with bluish color around the edge. It is usually not indurated.
- *Tonsils may be studded with tubercles* and so clinically should always be examined.
- Associated pulmonary tuberculosis should also be looked for. In 20% cases of tuberculous lymphadenitis, there may be associated pulmonary tuberculosis or it may be a primary focus.
- Cervical spine is examined for tuberculosis.

Types

1. *Hyperplastic*			2. *Caseating*	
a.	20% common	——	a.	80% common
b.	*Discrete*, firm or hard	——	b.	*Matted* due to periadenitis
c.	Occurs in the cortex of lymph node	——	c.	Involves medulla with periadenitis
d.	Host immunity is good	——	d.	Body resistance is not adequate
e.	Drugs act better	——	e.	Drugs do not reach in proper concentration and may not be effective
f.	Drug resistance is uncommon	——	f.	Drug resistance is common
g.	No cold abscess or sinus formation	——	g.	Cold abscess or sinus are common
h.	Blood spread	——	h.	Spread from tonsils

- Axillary nodes, when involved, is due to retrograde lymphatic spread from neck nodes or blood spread.
- Inguinal lymph nodes are involved occasionally through blood.
- Bluish hyperpigmented involved overlying skin is called as *scrofuloderma*.
- Tuberculous pus with *caseating cheesy creamy* material is *infective* as it contains multiplying organisms.
- Atypical mycobacterial tuberculosis can occur occasionally. Such disease may be *resistant* to drug therapy.
- *Sinus may persist due to*—fibrosis, calcification, secondary infection, inadequate reach of drug to maintain optimum concentration in caseation.

Clinical types

- *Acute type:* seen in infants and early childhood below 5 years
- *Hyperplastic type:* Lymphoid hyperplasia is typical; it is seen in patients with good resistance; hard discrete mobile lymph nodes; 15-20% common
- *Caseating type:* 75-80% common; matted nodes often with cold abscess; poor body resistance; seen in young adults
- *Atrophic type:* Rare type; seen in elderly; small lymph nodes but caseating type with atrophied nodes

Differential Diagnosis

1. Nonspecific lymphadenitis.
2. Lymphomas, and chronic lymphatic leukaemia.
3. Secondaries in the neck.
4. Branchial cyst mimics cold abscess.
5. Lymph cyst mimics cold abscess.
6. HIV with lymph node involvement.
7. When there is discharging sinus—actinomycosis.

Cold abscess

- Deep to deep fascia
- No evidence of signs of inflammation
- Not warm, nontender, smooth, soft and fluctuant, non-transilluminating
- Not adherent to skin (skin is free); no redness
- Contains cheesy caseating material
- It is seen in caseating tuberculous lymphadenitis due to caseation necrosis
- It may form collar stud abscess and later sinus
- FNAC, AFB, culture are useful investigations
- Differential diagnosis are branchial cyst, lymph cyst
- Treated by
  - Antituberculous drugs
  - 'Zig-zag' aspiration by wide bore needle in non dependent area to prevent sinus formation
  - Drainage using nondependent incision; later closure of the wound without placing a drain

Investigations

- Haematocrit, ESR, peripheral smear.
- FNAC of lymph node and smear for AFB and culture. FNAC is very useful but not as superior as open node biopsy. False negative, false positive results and altering the node architecture, and so eventual need of open biopsy are the problems. *Epithelioid cells* (modified histiocytes/macro-



Figs 5.37A to C: Typical cold abscess in the neck in which pus is aspirated. Pus should be sent for cytology (for epithelioid cells), staining (Ziehl-Neelsen—AFB) and culture.



Fig. 5.38: Tuberculous sinus excision with excision of diseased lymph nodes.



Fig. 5.39: Cold abscess with impending rupture.

phages) are diagnostic. *Langhans giant cells*, lymphocytes, plasma cells are other features.

- *Open biopsy* when FNAC is inconclusive. Open biopsy is more *reliable* for tuberculosis (and also in lymphoma; but it is contraindicated in node secondaries); entire node ideally two nodes if possible has to be taken intact; one in formalin for pathology, other in normal saline for microbiology (AFB).
- HIV test (ELISA and western blot).
- *Lowenstein Jensen media* is used for culture which takes 6 weeks to give result; *so selinite media* is often used which shows growth in 5 days.
- *Mantoux test* may be useful; but not very reliable.
- Chest X-ray to look for pulmonary tuberculosis.
- Polymerase chain reaction (PCR) is very useful method.

Treatment

- Drugs

Antitubercular drugs has to be started:

1. Rifampicin 450 mg OD on empty stomach. It is bactericidal. It discolours urine red. It is also hepatotoxic.
2. INH: 300 mg OD. It is bactericidal. It causes intolerance of GIT, Neuritis, Hepatitis (INH).
3. Ethambutol 800 mg OD. It is bacteriostatic. It causes GIT intolerance, retrobulbar neuritis (green colour blindness).
4. Pyrazinamide 1500 mg OD (or 750 mg BD). It is bactericidal. It is hepatotoxic, also causes hyperuricaemia and increases psychosis.

   Duration of treatment is usually 6-9 months.

- Aspiration

When there is cold abscess, initially it is aspirated. (Wide bore needle is introduced into the cold abscess in a nondependent site along a *"Z" track* (in zig-zag pathway) so as to prevent sinus formation.)

- *Incision and drainage*

If it recurs, then it should be drained. Drainage is done through a nondependent incision. After draining the caseating material, wound is closed without placing a drain.

- *Surgical removal*

Surgical removal of tubercular lymph nodes are indicated when

1. There is no local response to drugs or
2. When sinus persists.

It is done by raising skin flaps and removing all caseating material and lymph nodes. Care is taken not to injure major structures.

- *Excision of the sinus track* is often essential when sinus develops.

COLD ABSCESS

Cold abscess is common in neck. It can also occur in groin, intercostal space, loin or any site where tuberculous caseating material with cheesy content can get collected and localised.

Sites of Origin

Cold abscess may originate from tuberculosis of spine (thoracic or cervical spines), lymph node, internal organs, bone, etc.

In the Neck

- *Tuberculous lymphadenitis* is common cause. Here cold abscess is commonly seen in *anterior* triangle.
- *Tuberculosis of cervical spine* is also an important cause. Commonly here cold abscess occurs in *posterior* triangle. Caseating material from the cervical spine collects *in front of* the vertebra behind the prevertebral fascia which eventually ruptures either anteriorly or posteriorly.
  - *Anterior rupture* allows passage of caseating material *below* and behind the prevertebral fascia reaching superior mediastinum; *laterally* behind the prevertebral fascia and carotid sheath to form cold abscess in posterior triangle; in midline upper part, protruding *forwards* from behind the prevertebral fascia in *midline* presenting as chronic retropharyngeal abscess; in midline lower part protrudes into oesophagus; caseation runs along the axillary sheath and neurovascular plane to reach axilla and arm to cause cold abscess in axilla and arm/cubital fossa.
  - *Posterior rupture* occurs towards spinal canal facilitating the passage of caseation along the cervical nerves towards posterior triangle and brachial plexus and so axilla and arm.

Features

- It is common in young but can occur in any age group. Equal incidence in both sexes.
- Swelling in the neck, which is smooth, nontender, soft, fluctuant, nontransilluminating, with restricted mobility but is not adherent to skin.
- Neck pain, neck rigidity, restricted movements of cervical spine in case of cervical spine tuberculosis. With every change of position and often when patient is seated he supports his head with his hands and forearm—*Rust's sign* (Jan N Rust Surgeon, Poland).
- Evening fever, loss of weight and appetite, anaemia.

- Features of systemic disease if present like of pulmonary tuberculosis—cough, haemoptysis.
- Matted lymph nodes adjacent to cold abscess may be palpable.
- Oral cavity, tonsils, chest should be examined.
- Raised ESR, positive Mantoux test, anaemia, lymphocytosis, chest X-ray may show pulmonary tuberculosis, aspiration of cold abscess (FNAC) to see microscopically *epithelioid cells*. Acid fast bacilli may be identified from the aspirated fluid using Ziehl-Neelsen stain.
- X-ray neck in case of cervical spine tuberculosis to identify reduced joint space, vertebral destruction, soft tissue shadow.
- MRI of cervical spine, US/CT scan neck are needed to confirm the anatomical location, number of lesions.

Sequelae of Cold Abscess

- Secondary infection of the cold abscess making it tender.
- Formation of collar stud abscess, once pressure increases inside the cold abscess which will give way through the deep fascia to reach the subcutaneous plane to get adherent to skin.
- Sinus formation.
- Spread of disease to multiple lymph nodes and other organs.



Fig. 5.40: Tuberculous cold abscess and sinus in the neck.

Differential Diagnosis

- Branchial cyst and other cystic swellings in neck.
- Secondaries in neck lymph nodes.
- Secondaries in cervical spine.

Treatment

- Antituberculous drugs.
- Nondependent aspiration of the cold abscess.
- Excision of the diseased neck nodes.
- Immobilization of cervical spine by plaster jacket/collar for 4 months. Cervical spine fusion by open surgical method if diseased spine is unstable.

SECONDARIES IN NECK LYMPH NODES

Levels in Neck Nodes (Memorial Sloan—Kettering Cancer Centre Levelling of Neck Nodes)

Level I—Submental (Ia) and submandibular (Ib) lymph nodes.

Level II—Lymph nodes in upper deep cervical region. (It extends from base of skull to hyoid bone and from lateral margin of sternohyoid to posterior margin of sternomastyoid muscle).

Level III—Lymph nodes in middle cervical region (from hyoid bone to omohyoid muscle or cricothyroid membrane).

Level IV—Lymph nodes in lower cervical region (from omohyoid muscle to clavicle).

Level V—Lymph nodes in posterior triangle including supraclavicular region from posterior border of sternocleidomastoid muscle to anterior border of trapezius muscle.

Level VI—Lymph nodes in the midline neck—pretracheal and prelaryngeal from hyoid bone above to suprasternal notch below, medial border of carotid sheath on either side.

Level VII—Lymph nodes in the mediastinum. inferior to suprasternal notch to innominate artery below.

Note:

Level II and V are now subdivided into Level IIa/Level IIb and Level Va/Level Vb; depending whether these nodes are above the level (Level IIb/Level Va) of the spinal accessory nerve or below (Level IIa/Level Vb). *LevelI*node from oral cavity, lip, salivary gland, skin; *level II* node from oral cavity, oropharynx, nasopharynx, salivary gland; *level III* node from oral cavity, oropharynx, hypopharynx, larynx, thyroid; *level IV* node from oropharynx, hypopharynx, larynx, thyroid, cervical oesophagus; *level V* node from nasopharynx, scalp, GIT, breast, lungs.



Fig. 5.41: Levels of neck nodes.

Common sites of primary

- Oral cavity, tongue, tonsils
- Salivary glands
- Pharynx—nasopharynx
- Larynx
- Oesophagus
- Lungs
- GIT
- Thyroid

- It is commonly from squamous cell carcinoma, but can also be from adenocarcinoma or melanoma.
- Squamous cell carcinoma is mainly from oral cavity, pharynx.



Figs 5.42A to D: Typical secondaries in the neck. Note the different levels involved in different patients. Note the skin involvement and sinus formation in few photos.

- Adenocarcinoma is usually from GIT, commonly involving left supraclavicular lymph nodes.
- Breast, lungs, abdominal viscera are other areas where primary may cause secondaries in neck which should be examined when suspected.

Note:

- 20% of metastatic squamous cell carcinoma is from aerodigestive tract.
- Source of primary from head and neck region usually have frequency like this—nasopharynx, tonsil, base of tongue, thyroid, larynx, floor of the mouth, cheek, palate, pyriform fossa. Non-head and neck source of primary are—bronchus, oesophagus, breast, stomach.
- Histologically it is SCC (80%) or non-SCC. In non-SCC it may be poorly differentiated carcinoma (10-15%), adenocarcinoma (5-10%) or others like melanoma, poorly differentiated neoplasm (5%).
- In poorly differentiated neoplasm immunohistochemistry/immunoperoxidase staining, electron microscopy and chromosome analysis are needed to rule out lymphoma, neuroendocrine tumours, undifferentiated sarcomas.
- 3 years after treatment of one primary, if recurrence occur it is called as *new primary* in aerodigestive tract.
- Lower lip, tongue, soft palate and supraglottis can cause bilateral secondaries in neck.
- Soft palate, retromolar region, nasopharynx, hypopharynx posterior and lateral oropharynx can involve retropharyngeal nodes.
- Nasopharyngeal carcinoma spreads to level II-V, retro and parapharyngeal nodes.
- 15% of secondaries are from *infraclavicular primaries*—lung, pancreas, oesophagus, stomach, breast, ovaries, testis, prostate.
- Nodal spread below the lower border of cricoid (level IV and V; **L**ower) carries poor prognosis compared to nodes above cricoid (**U**pper).

Branchiogenic Carcinoma

It is a primary squamous cell carcinoma arising from remnants of branchial cleft or arch. It is a differential diagnosis for secondaries in neck. It is common in men. It is common near the area of carotid bifurcation. Histologically it contains malignant squamous cells with lymphoid tissues around. It spreads to lymph nodes and can infiltrate into adjacent soft tissues.

Treatment: Wide excision.

Features of Secondaries in Neck

- Common in adult/elderly male (Male to female ratio is 4:1), presents as painless rapidly increasing localised swelling in the neck.
- Nodular surface and hard in consistency, often fixed when it is advanced.
- Secondaries from *papillary carcinoma of thyroid* can be soft, cystic with brownish black fluid.
- Secondaries can infiltrate into carotids, sternomastoid, posterior vertebral muscles, spinal accessory nerve (shrugging of shoulder is affected), hypoglossal nerve (tongue will deviate towards the same side), cervical sympathetic chain *(Horner's syndrome)*.
- Secondaries spread into adjacent soft tissues and also to the skin causing fungation and ulceration. Often because of tumour necrosis, softer area develops in the hard node. Skin fold prominence due to infiltration of the platysma is typical.
- In advanced cases tumour may infiltrate into the major vessels like carotids, or branches of external carotid artery causing torrential haemorrhage.
- Dysphagia, dyspnoea, haemoptysis, hoarseness of voice, ear pain, deafness are other features depending on the primary site.



Fig. 5.43: Secondaries in the neck nodes from laryngeal carcinoma.

- *Hoarseness*—carcinoma larynx, thyroid
- *Dysphagia*—carcinoma posterior 1/3rd of the tongue, pharynx, oesophagus
- *Haemoptysis, cough, dyspnoea*—carcinoma lung
- *Ear pain, deafness*—nasopharyngeal carcinoma
- *Spinal accessory nerve*—shrugging of shoulder is difficult
- *Hypoglossal nerve*—tongue deviates to same side with wasting
- *Sympathetic chain*—Horner's syndrome with miosis, anhidrosis, upper eyelid droop (pseudoptosis), enophthalmos, loss of spinociliary reflex

Types of Secondaries in the Neck

1. Secondaries in the Neck with Known Primary

- Here secondaries are present and primary has been identified clinically in the oral cavity, pharynx, larynx, thyroid or other areas.
- Biopsy from the primary and FNAC from the secondaries are done.
- Primary is treated accordingly either by curative radiotherapy or by surgery (wide excision).
- Secondaries, when mobile are treated by radical lymph node block dissection in the neck.



Figs 5.44A and B: Advanced secondary carcinoma neck with ulceration and fungation.



Figs 5.45A and B: Large secondaries in neck with extensive fungation.

2. Secondaries in the Neck with Clinically Unidentified Primary

- Hard neck lymph nodes are the secondaries, but primary has not been identified clinically.
- FNAC of the neck node is done and secondaries is confirmed. Then search for the primary is done by various investigations.

They are:

a. Panendoscopy
  - Nasopharyngoscopy.
  - Laryngoscopy.
  - Oesophagoscopy.
  - Bronchoscopy.

b. Blind biopsies are taken from fossa of Rosenmuller, lateral wall of pharynx, pyriform fossa, tonsillar bed, base of tongue, subglottic region (larynx). It is called as *surveillance biopsy* and is done to reveal unknown primary in 15% of cases of secondaries in neck. If this surveillance biopsy is negative, then *ipsilateral tonsillectomy* may be needed.

c. FNAC of thyroid and suspected areas.

d. CT scan.

Once the biopsy confirms the primary, it is treated either by surgery or by *curative radiotherapy*.

Secondaries in the neck is treated by *radical neck dissection*.



Figs 5.46A and B: (A) Large secondaries in neck with nodularity, with involvement of platysma below. (B) Bilateral secondaries are observed. **Skin fold prominence is obvious**.



Fig. 5.47: Secondaries in neck with nodules and ulceration. Note the deviation of tongue towards same side due to hypoglossal nerve involvement.

3. Secondaries in the Neck with an Occult Primary

Occult primary sites which can cause secondaries in neck

- Fossa of Rosenmuller
- Lateral wall of pharynx
- Posterior third of the tongue
- Thyroid
- Paranasal sinuses
- Bronchus
- Oesophagus

Listen to the faintest sound; for opportunities knock only once.

Histologically secondaries in neck with occult primary may be of squamous cell carcinoma or of nonsquamous cell carcinoma, i.e. adenocarcinoma/poorly differentiated tumours (lymphoma/sarcoma/melanoma). In upper and midcervical region 80% are due to squamous cell carcinomas. In lower cervical and supraclavicular region 40% can be adenocarcinomas. Common sites of primary here (for adenocarcinoma) are thyroid, breast, gastrointestinal tract, salivary glands, lungs, prostate and kidney.

- Here secondaries in the neck lymph nodes are confirmed by FNAC, *but primary has not been revealed clinically and by any available investigations*.
- When all the investigations mentioned above are done, do not show any evidence of primary, only then it is called as *occult primary*.
- Primary tumor is not identified at the time when definitive therapy has started.
- 70% of occult nodes occur in jugulodigastric group.
- Differential diagnosis for secondary with occult primary is lymphoma and *primary branchiogenic carcinoma*.
- Reasons for primary lesion being occult—too small a primary to detect; possibility of immunological spontaneous regression of primary and inability of the present diagnostic tools to detect the primary.
- FNAC is the tool to confirm the occult secondary. If FNAC is inconclusive, only then open biopsy (incision/excision) is done to confirm. Open biopsy helps in high suspects of lymphomas or poorly differentiated carcinomas. It facilitates tissue study, immunohistochemistry, and special stains. Many studies prove that risk of seedling, survival and prognosis will not alter by open biopsy. But at present it is proposed only when FNAC fails or special methods are mandatory to type the disease. After open biopsy, frozen section confirmation and immediate neck dissection has to be done.
- Immunoperoxidase staining can be done in FNAC specimen or formalin fixed paraffin tissue using monoclonal or polyclonal antibodies. Immunoperoxidase is the most commonly used tool. It is mainly useful in lymphomas/neuroendocrine tumours. Electron microscopy is superior to immunohistochemistry as ultrastructure details can be assessed. But it is costly. Chromosomal analysis for tumour specific genes is used in B, T and germ cell lymphomas.
- Initially the secondaries in the neck are treated by *radical neck dissection*, then *regular follow-up* is done (at three monthly intervals) until the primary reveals.
- Once primary is revealed it is *confirmed by biopsy* and treated accordingly, either by *curative radiotherapy* or by *wide excision* depending on location of revealed primary.
- This type is usually less aggressive and has got better prognosis.



Fig. 5.48: Diagrammatic representation of neck lymph node staging in secondaries.

Nodal staging in secondaries

N_x—nodes cannot be assessed
N_0—no nodal metastasis
N_1—single node same side < 3 cm in greatest dimension
N_{2a}—single node same side 3-6 cm
N_{2b}—multiple nodes same side < 6 cm
N_{2c}—bilateral/contralateral nodes < 6 cm
N_3—node > 6 cm

Investigations for Secondaries in Neck

- *FNAC of secondary:* Open incision biopsy is not advised here. It destroys the fascial barriers and causes the spread of tumour faster and earlier into next level nodes or other soft tissues. Eventual neck dissection technically becomes difficult. Recurrence rate in neck will be higher after open biopsy. If FNAC of node and all investigations for primary become negative, then open biopsy of node following confirmation with frozen section and immediate neck dissection is undertaken. In such situation if neck dissection is delayed after open biopsy confirmation, chances of cure will be reduced.



Fig. 5.49: FNAC of neck lymph node. It is very useful method in secondaries in neck node and tuberculosis. Its use is equivocal in lymphoma where open biopsy of the node is preferred method. *(Courtesy:* Dr Krishna Upadhya Pathologist, Nandikoor Laboratory, Mangalore).



Fig. 5.50: CT neck showing secondaries.

- *Biopsy from primary:* Incision biopsy is the choice here.
- Blind biopsies from suspected areas.
- Nasopharyngoscopy, laryngoscopy, bronchoscopy, oesophagoscopy—*panendoscopy* with examination under anaesthesia.
- CT scan is to see the base of skull, paranasal sinuses, nasopharynx, extension of primary tumour/secondary deposits; CT scan of chest and abdomen.
- Chest X-ray to visualise primary or secondaries in case melanomas or mediastinal nodes.
- MRI scan or PET scan in conjunction with CT scan or MRI. MRI identifies soft tissue extension/changes; guided primary biopsy is possible; extension into bone is identified.
- CT chest and abdomen in case of infraclavicular primaries or to assess nodes.

Open incision biopsy is avoided in lymph node secondaries.

Triple endoscopy *includes direct/indirect laryngoscopy, oesophagoscopy and bronchoscopy.*

Differential Diagnosis

1. Lymphomas.
2. Tuberculous lymphadenitis.
3. Nonspecific lymphadenitis.
4. HIV.
5. Chronic lymphatic leukaemia.

In secondaries neck with occult primary

- FNAC of node/open biopsy to confirm
- Proper clinical methods to identify the location of primary
- CECT is the investigation of choice to look for primary
- Other methods are—MRI, triple endoscopy, examination under anaesthesia, blind biopsies from fossa of Rosenmuller, pyriform fossa, base of tongue, subglottic area and tonsils, FNAC of thyroid, ipsilateral tonsillectomy if surveillance biopsy and other methods are negative
- Once occult primary is confirmed and if node is less than 3 cm in size, it is treated as N_1 disease with RND/MRND
- Postoperative RT is essential if disease is N_{2a}; N_{2b} (more than 2 nodes are positive); if 2 or more levels are involved; if extracapsular spread is present
- In fixed lymph node/nodes, initially radiotherapy is given followed by surgery (RND) if nodes become mobile and later adjuvant chemotherapy
- In N_{2c} bilateral neck dissection (one side IJV preservation) with bilateral RT is given
- N_3 stage has got poor prognosis. RND and RT with later chemotherapy are used. In fixed nodes, RT and then chemotherapy is used
- Proper follow-up at regular intervals is essential with all diagnostic tools to identify the possible site of primary which may get revealed during follow up period



Figs 5.51A to C: (A) Secondaries in neck but no skin involvement is seen. (B and C) Secondaries with skin involvement is obvious.

Treatment

- Primary is treated depending on the site, either by *wide excision (surgery)* or by *curative radiotherapy*. Then the secondaries are treated.
- Secondaries when *mobile*, are treated by *radical neck dissection*.
- When *fixed* it is *inoperable. Palliative external radiotherapy* is given to palliate pain and to prevent the anticipated bleeding.
- Sometimes *initially, external radiotherapy* is given to *downstage* the disease so that it becomes operable and later classical block dissection can be done.

'Excellence' is an outcome, of good intentions and the right ways to do a work.

- *Postoperative RT* is given after neck dissection when—more than two lymph nodes are positive for metastases; nodes show metastases at two or more level; extracapsular spread in lymph node. Suspected occult primary is included/covered in the RT field. RT is also given to contralateral neck nodes in nasopharyngeal carcinoma. Level II lymph node *alone* from an occult is more likely to be from nasopharyngeal carcinoma and RT is preferred in such situation covering nasopharyngeal area; later RND is done.



Figs 5.52A and B: Secondaries in neck with ulcer over the summit.

Types of Block Dissection

1. Classic Radical Neck Dissection


Upper incision
2 cm
Lower incision

Fig. 5.53: MacFee incision for radical neck dissection. Upper incision is from mastoid process along the line of digastric to hyoid bone point, then upwards to chin. Lower incision is parallel to clavicle 2 cm above from anterior margin of trapezius to midline.

It is resection of lymph nodes (level I to V), fat, fascia, sternomastoid muscle, omohyoid muscle, internal jugular vein, external jugular vein, accessory nerve, sub-mandibular salivary gland, lower part of parotid, prevertebral fascia—*"en-block"(Criles' operation)*.

Incision that is commonly made is MacFee incision which are two parallel incisions, one at submandibular region, another at supraclavicular region. Blood supply of the flap remains intact and so healing will be better without flap necrosis.


1
2
2
3
4
1. Schobinger
2. Conley/Schechter
3. Hockey stick
4. Hayes Martin
(two break down point—good exposure)
A
7
5
7
6
5
5. Triradiate
6. Apron incision
7. Flschel T-J/Circles
'T' incision/Blair brown 'z'
B

Figs 5.54A and B: Incisions/different approaches for radical (RND/MRND) neck dissections. There are many incisions mentioned. Few of them are shown in diagram.



Fig. 5.55: Radical neck dissection, on table.

2. Conservative Functional Block Dissection (After BOCCA Surgeon): (Modified Radical Neck Dissection—MRND)

It is done only in selected cases where tumour is very well-differentiated and less aggressive like in papillary carcinoma



Fig. 5.56: Radical neck dissection on table photo. Note the internal jugular vein, digastric muscle, strap muscles, lower margin of the mandible.

of thyroid with lymph node secondaries. Structures preserved here are sternomastoid muscle, internal jugular vein and spinal accessory nerve.

- Only spinal accessory nerve is preserved—MRND type I (most important). **N**-Preserved.
- Accessory nerve and sternocleidomastoid are preserved—MRND type II. **NM**-Preserved.
- Accessory nerve, sternomastoid and internal jugular veins are preserved—MRND type III. **NMV**-Preserved. It is called as *functional neck dissection.*

3. Supraomohyoid Block

Removal of only fat, fascia, lymph nodes, muscles, submandibular salivary gland, with dissection above the omohyoid muscle is done. Done only in selected individuals with well-differentiated tumour and involvement of few submandibular lymph nodes *(Levels I, II, III are removed)*. Done in N0 lesions.

4. Bilateral Neck Dissection

Here internal jugular vein is preserved on one side. *Always the side where the vein is preserved, is operated first* (If both the jugulars are ligated, cerebral congestion occurs leading to cerebral oedema which is dangerous. Jugular veins are ligated as an inevitable procedure during surgery, the patient is kept in propped-up position; antibiotics, diuretics, steroids, mannitol infusion are given, repeated CSF taps are done to control the cerebral oedema).

Ligating one IJV increases the ICP by 3 fold; *both IJV ligations* increase ICP by 5 fold. ICP gradually falls over 8-10 days. For this reason pressure dressing should be *avoided* over the wound of neck dissection after surgery.

5. Commando Operation (Combined Mandibular Dissection and Neck Dissection)

It is *en-block removal*, which includes wide excision of primary tumour with hemimandibulectomy and neck block dissection, e.g. in tongue.

6. Lateral Neck Dissection (Anterolateral/Jugular/ALND)

It is done in laryngeal and pharyngeal primaries with clinically negative nodes. Levels II, III, IV are removed bilaterally.

7. Anterior (Central) Dissection

Level VI (pre, paratracheal) nodes are removed.

8. Posterolateral Dissection

Levels II, III, IV, V are removed for cutaneous malignancies, with suboccipital nodes.

9. Extended Radical Dissection

Additional nodes in the mediastinum are cleared (level VII). Nodes like level VI or parapharyngeal, retropharyngeal, external carotid artery, hypoglossal nerve, vagus nerve, parotid gland, mastoid tip—are addressed.

Complications of block dissection

- Haemorrhage
- Infection
- Lymph ooze
- Carotid blow out
- Seroma and flap necrosis
- Frozen shoulder is common
- Rarely pneumothorax and chylous fistula
- Drooping of shoulder due to paralysis of trapezius in radical neck dissection



Fig. 5.57: Ligation of external carotid artery should be done when needed distal to the origin of the superior thyroid artery.

Type of neck dissection	*Nodes removed*	*Structures preserved*
Comprehensive:		
Radical neck dissection (RND)	Level I-V	None
MRND type I	Level I-V	Spinal accessory nerve
MRND type II	Level I-V	Spinal accessory nerve; sternomastoid muscle
MRND type III	Level I-V	Spinal accessory nerve; sternomastoid muscle; IJV
Selective node dissection:		
Supraomohyoid neck dissection (N_0)	Level I-III	Spinal accessory nerve; sternomastoid muscle; IJV
Extended supraomohyoid dissection (N_0)	Level I-IV	Spinal accessory nerve; sternomastoid muscle; IJV
Anterolateral neck dissection (N_0)	Level II-IV	Spinal accessory nerve; sternomastoid muscle; IJV
Posterolateral neck dissection (N_0)	Level II-V with suboccipital, retroauricular nodes	Spinal accessory nerve; sternomastoid muscle; IJV
Anterior/central dissection	Level VI	Spinal accessory nerve; sternomastoid muscle; IJV

Note:

- To control haemorrhage in head and neck cancers and during head and neck surgeries (like radical parotidectomy, commando operation, maxillectomy) often ligation of external carotid artery is required. ***Ligation should be done distal to the origin of the superior thyroid artery***. It should never be ligated below the origin of the superior thyroid artery as this will lead to formation eddy current and thrombus at the carotid bifurcation and intracranial embolism. Ligation of ECA to control bleeding is usually done in continuity (Fig. 5.57).
- Middle of the neck, laterally over CCA is the poorly vascularised area of skin which can lead into skin necrosis. So vertical incision or three point junctions at this point should be avoided. Horizontal incisions are better in neck.
- Carotid artery should be protected by *muscle flap or free dermal graft*. *Levator scapulae* muscle flap is commonly used.

Carotid blow out is most dangerous complication. It is due to sepsis, wound breakdown, stripping of arterial adventitia, necrosis and drying of the artery. Ligation of the carotid is done to save the life of the patient but procedure itself has got 20% mortality and 50% morbidity (hemiplegia).

CHEMOTHERAPY FOR HEAD AND NECK CANCERS

It may be used alone or as multimodality therapy.

Types

- *Adjuvant chemotherapy*: Chemotherapy is used before, during or after main therapeutic modality (surgery or radiotherapy). When used before it is called as anterior/*nduction* chemotherapy. It reduces the burden, downstages the tumour, reduces the chance of micrometastasis that may occur during surgery. When used with radiotherapy (concurrent) it is used as radio sensitiser. When used after surgery/radiotherapy it is called as *posterior* chemotherapy.
- *Palliative chemotherapy*: It is used in advanced/ recurrent/ metastatic cancers to relieve symptoms like pain/dysphagia/ dyspnoea or to prevent chances of bleeding or fungation.

It may be single drug therapy like methotrexate/bleomycin/ cisplatin/5-fluorouracil or multidrug combination chemotherapy. Combination chemotherapy is more beneficial which increases efficacy.

- Methotrexate—40 mg/m^2 IV weekly. It causes mucositis, bone marrow suppression with liver and kidney toxicity. Hydration and alkalisation of urine before and after therapy is beneficial to reduce toxicity.
- 5 - Fluorouracil—10-15 mg/m^2 IV daily for 5 days. Complications are bone marrow suppression and gastrointestinal symptoms.
- Bleomycin—10-20 mg/m^2 IV weekly. Pneumonitis and *pulmonary fibrosis* are the complications.
- Vincristine—1-2 mg/m^2 IV monthly. *Neurotoxicity* (sensory and motor neuropathy), constipation and alopecia are the side effects.
- Cisplatin—80-120 mg/m^2 IV infusion once in 3 weeks. Complications are neurotoxicity, bone marrow suppression, renal toxicity, ototoxicity. Adequate hydration and mannitol diuresis may be needed.
- Cyclophosphamide—60-120 mg/m^2 IV for 5 days at regular 3 weeks cycles. Alopecia, bone marrow suppression and *cystitis* (haemorrhagic) are the toxicities (ABC). Barbiturates should be avoided during therapy.
- Adriamycin—60-90 mg/m^2 IV. It is *cardiotoxic* and hence cardiac monitoring is needed while infusion.
- Paclitaxel and carboplatin as empiric chemotherapy are used in neck secondaries with occult primary.

Mode of Administration

- It can be given by *intra-arterial route, through external carotid artery* (Never through internal carotid as it will cause cerebral damage). Site of arterial catheter should be confirmed by Doppler or angiogram. Drug is usually administered through an arterial pump. Other method is to increase the height of the drip stand to get a pressure above the level of the systolic pressure of the patient (i.e. more than 13 ft).

- Drugs can also be given intravenously or orally (methotrexate).

General toxicity of chemotherapeutic agents: Mucositis, alopecia, stomatitis, nausea and vomiting, diarrhoea, bone marrow suppression.

Often transfusions of blood/FFP/platelet are needed before or after chemotherapy depending on parameters.

Monitoring the Patient on Chemotherapy

- Clinical assessment—pulse, blood pressure, alopecia, urine output, jaundice, skin changes like rashes, fever, pallor.
- Biochemical parameters—total count, platelet count, blood urea and serum creatinine, liver function tests.
- Specific relevant tests—chest X-ray, endoscopy, CT scan, tumour marker if specific in some types of carcinomas.

Rule of 80 in the neck

- 80% of nonthyroid neck masses are neoplastic
- 80% of neoplastic neck masses are seen in males
- 80% of neoplastic neck masses are malignant
- 80% of malignant neck masses are metastatic
- 80% of metastatic neck masses are from primary sites above the clavicle

***Note*:**
For carotid artery aneurysm—refer Chapter on Arterial Diseases.

Courage is fear that has said its prayers,

Chapter 6 Thyroid

> *(The thyroid gland) has no very evident mechanical or local office to fulfill…. Yet we may one day be able to show, that a particular material principle is slowly formed, and partially kept in reserve; and that this principle (serves) important subsequent functions in the course of the circulation…. Something analogous to a reservoir function obtains in this part.*
>
> —**Thomas Wilkinson King,** 1836

CHAPTER OUTLINE

- Development
- Anatomy
- Physiology
- Congenital Anomalies
- Thyroid Function Tests
- FNAC of Thyroid
- Classification of Goitre
- Diffuse Hyperplastic Goitre
- Nodular Goitre
- Discrete Thyroid Nodule
- Solitary Thyroid Nodule
- Retrosternal Goitre
- Thyrotoxicosis and Hyperthyroidism
- Radioactive Iodine
- Thyroid Neoplasms
- Differentiated Thyroid Carcinoma
- Papillary Carcinoma of Thyroid
- Follicular Carcinoma of Thyroid
- Anaplastic Carcinoma of Thyroid
- Medullary Carcinoma of Thyroid
- Malignant Lymphoma
- Hashimoto's Thyroiditis
- De-Quervain's Subacute Granulomatous Thyroiditis
- Riedel's Thyroiditis
- Thyroid Incidentaloma
- Thyroidectomy
- Emil Theodor Kocher
- Kocher's Test
- Hypothyroidism
- Recurrent Laryngeal Nerve Palsy

DEVELOPMENT

The thyroid gland develops from a median down growth of a column of cells from the pharyngeal floor between the first and second pharyngeal pouches (subsequently marked by the foramen caecum of the tongue).

The canalised column becomes the *thyroglossal duct* which is displaced forward by the developing hyoid bone and then below the hyoid, lies slightly to one side, more commonly to the left. The duct bifurcates to form the thyroid lobes and a portion of the duct forms the pyramidal lobe.

ANATOMY

It is located in the anterior triangle of the neck. It weighs about 20 grams.

Parts

- *Right and left lateral lobes* located in a space (thyroid fossa) between trachea and oesophagus medially and carotid sheath laterally. Each lobe is 5 × 3 × 1.5 cm in size, extends from the middle of thyroid cartilage to 6th tracheal ring.
- *Isthmus* is the connecting part between two lateral lobes in midline extending from 2nd to 4th tracheal rings.
- *Pyramidal lobe* is upward extension as fibrous strands or muscular strands from the junction of the isthmus and left lateral lobe.
- Gland is invested by *pretracheal fascia*.
- *Berry's ligament* is a strong condensed vascular connective tissue between the lateral lobe and cricoid cartilage on each side.


Recurrent laryngeal nerve
Parathyroid
Oesophagus
Carotid sheath
Carotid artery
Vagus
Sympathetic chain
Internal jugular vein
Trachea
Thyroid
Internal jugular vein
Thyroid cartilage
Superior thyroid vein
Middle thyroid vein
Thyroid
Inferior thyroid vein
CCA
Left brachiocephalic vein

Fig. 6.1: Relations of the thyroid.

Blood Supply

- *Superior thyroid artery* is first anterior branch of external carotid artery enters the gland near superior pole as a larger anterior superficial branch and a smaller posterior branch.
- *Inferior thyroid artery*, a branch of thyrocervical trunk of subclavian artery passes behind the carotid sheath running medially reaching the posterolateral aspect of the gland.
- *Thyroidea ima artery*, a branch of aorta or brachiocephalic artery enters the isthmus or lower pole of one of the lateral lobes (10%).
- Tracheal and oesophageal branches serve blood supply to retained thyroid gland after thyroidectomy.

Venous Drainage

- *Superior thyroid vein.*
- *Middle thyroid vein* is short and drains into the internal jugular vein. It is first to be ligated in thyroidectomy.
- *Inferior thyroid veins* are many in number.
- *Kocher's vein* may be present which drains lower or middle thyroid.

Lymphatic Drainage

- *Primary*:
  - Tracheo-oesophageal nodes.
  - Prelaryngeal nodes (*Delphian nodes*). Formerly purpose of these lymph nodes were uncertain hence the name.

    Delphi is a place in Greece where Pythia, snake women after sulphurous fume inhalation uttered meaningless jargon purpose of it was unclear.
  - Mediastinal nodes.
- *Secondary*:
  - Deep cervical nodes.
  - Supraclavicular nodes.
  - Occipital nodes.
    - Ascending medial lymph vessels from the upper border of isthmus drain to prelaryngeal nodes which are located in the cricothyroid membrane.
    - Ascending lateral vessels from the upper pole of the gland along the superior thyroid artery drain into deep cervical nodes.
    - Descending medial vessels begins at lower part of the isthmus to reach pretracheal lymph nodes.
    - Descending lateral vessels run from the deep surface of the thyroid to recurrent laryngeal chain nodes.

Important Relations of Thyroid Gland

- Recurrent laryngeal nerve lies in the tracheooesophageal groove, in relation to Berry's ligament.
- Superior laryngeal nerve which gives a branch, external laryngeal nerve supplies cricothyroid muscle. It accompanies superior thyroid artery.
- Parathyroid glands—four in number, two on each side embedded in thyroid.


IJV
CCA
Superior thyroid artery
Superficial nodes
Delphian nodes
Deep nodes
Tracheo-oesophageal nodes
Inferior thyroid artery
Thyroid
Trachea
Supraclavicular nodes
Mediastinal nodes

Fig. 6.2: Lymphatic drainage of thyroid.

The art of medicine consists in amusing the patient while nature cures the disease.



Fig. 6.3: Anatomy of thyroglossal duct showing its pathway.

PHYSIOLOGY

Thyroid gland has two secretory cells:

1. *Follicular cells*—secretes thyroid hormones (Thyroxine (T_4), Tri-iodothyronine (T_3).
2. *Parafollicular cells* ('C' cells)—secretes calcitonin.

I_2 Metabolism

Ninety per cent of body iodide uptake is in the thyroid gland, whose uptake into the follicular cells is regulated by TSH and follicular iodide content.

Thyroid Hormone Synthesis

Iodothyronins (MIT, DIT) are formed in follicular cells by the coupling of inorganic iodide with tyrosine. These are biologically inert molecules. T_4 (Thyroxine) is formed by coupling of 2 DIT molecules and T_3 (Tri-iodothyronine) is formed by coupling of 1 MIT and 1 DIT molecules. Both are bound to thyroglobin which is the primary component of colloid matrix.

The hypothalamus-pituitary-thyroid axis regulates thyroid hormone production and releases in a classic feedback system. TRH is a regulatory hormone from hypothalamus and TSH is a regulatory hormone from anterior pituitary.

CONGENITAL ANOMALIES

Athyreosis is total absence of lateral lobes and isthmus with hypothyroidism.

Ectopic Thyroid

It is residual thyroid tissue along the course of thyroglossal tract.

Ectopic thyroid tissue may lie anywhere along the line of descent. Whole of the thyroid gland or residual thyroid lies in an abnormal position either in the posterior part of the tongue, or in the upper part of the neck in midline, or intrathoracic region. Carcinoma develops more commonly in ectopic thyroid tissue than normal thyroid. Radioisotope scan, CT scan for intrathoracic thyroid will confirm the diagnosis.

Lingual Thyroid

It is a thyroid swelling in the posterior third of tongue, at the foramen caecum, presenting as rounded swelling. It may be the only existing thyroid tissue which may cause:

a. Dysphagia, pain, speech impairment.
b. Respiratory obstruction, haemorrhage.
c. 70% present as hypothyroidism, 10% as cretin.
d. Common in females (3:1).

Bare tracheal rings in midline with absence of normal thyroid tissue may often be evident.

Any diseases which can occur in normal thyroid can also occur in lingual thyroid, i.e. nodularity, toxicity, malignancy (If turns malignant, *follicular carcinoma* is more common, papillary carcinoma is very rare).



Figs 6.4A and B: Lingual thyroid visible on the posterior 1/3rd of the tongue. Neck should be palpated for the presence or absence of normal thyroid.

Differential diagnosis for lingual thyroid

- Carcinoma of posterior third of tongue
- Angiofibroma
- Sarcoma
- Hypertrophied lingual tonsil

Diagnosis

- *Radioisotope study* shows the uptake of iodine by the lingual thyroid and also shows the status of the thyroid in normal fossa.
- U/S neck has to be done to see the absence of thyroid in normal location.

Treatment

- L-thyroxine is given daily orally.
- Often requires surgical excision and is technically easier.
- Radioisotope therapy for ablation is also often used.


Tc99m pertechnetate
Thyroid scan
Anterior view
RT
LT
A
B

Figs 6.5A and B: Technetium 99 radioisotope scan in lingual thyroid. USG of neck is done to assess lingual thyroid and normal thyroid region.


Foramen caecum
Tongue
1/3
2/3
1
2
3
Hyoid bone
4
Pyramidal lobe
Lateral lobe of thyroid
5
1. Ectopic lingual thyroid
2. Intralingual thyroid
3. Sublingual thyroid
4. Thyroglossal cyst
5. Retrosternal thyroid

Fig. 6.6: Ectopic sites of thyroid.

Thyroglossal Cyst

- Thyroglossal cyst is a swelling occurring in the neck in any part along the line of thyroglossal tract.

Possible sites for thyroglossal cyst

a. Beneath the foramen caecum
b. In the floor of mouth
c. Suprahyoid
d. Subhyoid—commonest site
e. On the thyroid cartilage—2nd common site

- It is usually congenital wherein there will be degeneration of a part of the tract causing cystic swelling. Normal thyroid may be present in the normal location (fossa). Sometimes, thyroid may not be present in the normal site but may be present in the wall of the thyroglossal cyst.
- It is a tubulodermoid type of cyst.
- It is lined by pseudostratified, ciliated columnar epithelium.

Clinical Features

a. Swelling in the midline, towards the left.



Figs 6.7A and B: Thyroglossal cyst.



Fig. 6.8: Thyroglossal cyst in a boy. It is a midline swelling with a 'TUG' feeling while protruding the tongue out.

The person who really wants to do something finds a way: the other finds an excuse.



Fig. 6.9: Infected thyroglossal cyst.

b. Moves with deglutition as well as with the protrusion of tongue. Patient is asked to open the mouth and keep the lower jaw still. Examiner holds the cyst between the thumb and forefinger. When the patient is asked to protrude the tongue, a "*tugging sensation"* can be felt.
c. Swelling is smooth, soft, fluctuant (cystic), nontender, mobile, often transilluminant.
d. Thyroid fossa is empty, if there is no thyroid in normal location.
e. Thyroglossal cyst can get infected and may form an abscess. Cyst wall contains lymphatic tissue and so infection is common.
f. Malignancy can develop in thyroglossal cyst (papillary carcinoma)—1%. Cyst will be harder, fixed, with palpable neck nodes. More often it is difficult to suspect and will be confirmed by histology after excision. If biopsy report is papillary carcinoma, then completion thyroidectomy is *indicated* if the remaining is nodular thyroid shows cold nodule or these are enlarged neck nodes, or with history of neck irradiation. If neck nodes are present, node dissection, and radioactive iodine therapy with suppressive dose of L thyroxine 0.3 mg OD is needed.
g. Incidence is equal in both sexes.

Investigations

a. Radioisotope study.
b. U/S neck.
c. FNAC from the cyst.

Differential diagnosis for thyroglossal cyst

- Subhyoid bursa
- Pretracheal lymph node
- Dermoid cyst
- Solitary nodule of thyroid—isthmus
- Submental lymph node
- collar stud abscess

Treatment

a. ***Sistrunk operation:***
Excision of cyst and also full tract upto the foramen caecum is done along with removal of central part of the hyoid bone, as the tract passes through it.

Technique

Through transverse neck incision placed over the cyst, skin flap is raised above along with platysma. Care should be taken not to open the cyst. Cyst with surrounding tissues is dissected up to the hyoid bone. Sternohyoid and thyrohyoid muscles are divided. Central part of the hyoid bone of 1 cm width is resected along with intact track within it. Geniohyoid and mylohyoid muscles are divided off from the hyoid. Track with adjacent tissues is dissected above upto the foramen caecum. Adjacent tissues also should be removed because of possibility of multiple tracks which otherwise lead to recurrence or fistula formation. Often anaesthetist is asked to apply digital pressure over the base of tongue near foramen caecum to facilitate the dissection and to confirm the reach up to the foramen caecum. Track is ligated at foramen caecum and removed. Recurrence rate by removal of only track without central hyoid is 25%. Removal of track with central hyoid o*f 1 cm width* reduces the recurrence rate to 5%. Complications are recurrence, thyroglossal fistula formation, haemorrhage/haematoma formation and infection. Low lying cyst often requires two parallel incisions to remove entire track up to foramen caecum.

b. If there is no normal thyroid gland after the surgery, maintenance dose of L-thyroxine 0.1 mg OD is given life long.

***Note*:**
If tract is not completely excised, it will result in thyroglossal fistula.

Thyroglossal Fistula

- *It is not a congenital condition.*
- It either follows infection of thyroglossal cyst which bursts open or after inadequate removal of the cyst.
- It is lined by columnar epithelium, discharges mucous and is a seat of recurrent inflammation. "*Hood sign*" is characteristic. Opening of fistula is indrawn and been overlaid by a fold of skin as '*hood*'.
- Peculiar crescentic appearance is called as *semilunar* sign.
- It secretes mucous discharge.
- Site of the fistula is just below the hyoid bone commonly; in infants it may be much lower.



Fig. 6.10: Thyroglossal fistula.

- **Investigations:** Radioisotope study and fistulogram.
- **Treatment:** Sistrunk operation.

Note:

(One more Sistrunk operation is done in case of lymphoedema.)

Lateral Aberrant Thyroid

- It is at present considered as a misnomer.
- It is the metastasis into cervical lymph node from a papillary carcinoma of thyroid.
- FNAC has to be done and treated as papillary carcinoma of thyroid.

Agenesis

- Total agenesis of one thyroid lobe may occur. This is rare but can be clinically important. It leads to confusion in diagnosis, especially in the toxic gland, where it could be diagnosed as a secreting nodule.

Dyshormonogenesis

- It is an autosomal recessive condition wherein there is either deficiency of thyroid enzymes (either peroxidase or dehalogenase) or inability to concentrate or to bind or to retain iodine.
- It may be familial and patient presents with large diffuse vascular goitre involving both lobes.
- They respond very well to L-thyroxine and may not require surgery at any time.
- Condition may be associated with congenital deafness which is being called as *Pendred's syndrome*. CT scan of temporal bone shows abnormal bony labyrinth. Condition shows thyroid peroxidase deficiency.

THYROID FUNCTION TESTS

1. *T_3* (Serum tri-iodothyronine): 1.2-3.1 nmol/litre. 80% of T_3 is from deiodination of T_4 at periphery in liver, muscle, kidney and pituitary. T_3 is 4 times more potent with half life of 24 hours.
2. *T_4* (Serum thyroxin): 55-150 nmol/litre. It reflects the output of the gland (Edward Calvin Kendall 1915).
3. TSH 0-5 IU/ml of plasma. TSH is secreted from anterior pituitary; its secretion is inversely related to circulating thyroid hormones. TSH secretion is regulated by TRH from hypothalamus.
4. *PBI* (Protein bound iodide)—8 ug/100 ml.
5. *Free* T_3 is 0.3% (3-9 nmol/litre). It is the best single test in assessing hyperthyroidism.
6. *Free* T_4 is 0.03% (8-26 nmol/litre).
7. *RA I^{123} scan* can show either cold nodule, hot nodule, or warm nodule.
8. *TRH stimulation test* for hypothalamic—pituitary axis: Intravenous TRH (200 μg) shows rise in serum TSH level in 20 minutes (from basal 1 μ unit/ml to 10 μ unit/ml) and reaches to normal in 2 hours. Patients with pituitary insufficiency develop a subnormal response; patient with hypothyroidism will show enhanced TSH response; in hyperthyroidism there will be no response. This test is useful in doubtful hyperthyroidism, hypothyroidism, T_3 thyrotoxicosis, ophthalmic Graves' disease.
9. Serum creatinine is increased in hyperthyroidism; decreased in hypothyroidism.
10. Serum cholesterol is increased in hypothyroidism and decreased in hyperthyroidism.
11. BMR is increased in hyperthyroidism.
12. *Thyroid autoantibodies* are also useful to evaluate the function (LATS). TSH receptor antibodies (TSH RAb) has got long acting potential and are reasons for all primary thyrotoxicosis.
13. *Werner's T_3 suppression test*: Initial isotope uptake study is done. 40 μg of T_3 is given to the patient orally 8th hourly for 5 days. Uptake study is repeated. In normal uptake suppression up to 80% is noted. In toxic goitre suppression is 10 - 20%. It is used in patients with antithyroid drugs for primary thyrotoxicosis to assess the remission status.
14. *Thyroglubulin estimation*: Normal value is 0.5-50 μg/L. It is used during follow up period especially in follicular carcinoma of thyroid. But if thyroglobulin antibodies are raised in patient, then it is of no use. Thyroglobulin is produced only by the thyroid tissue. After total thyroidectomy, its level drastically reduces. It is the ideal follow up marker in well differentiated thyroid carcinoma after thyroidectomy. Sudden raise in its serum can occur in thyroiditis, primary or secondary toxic goiter.

FNAC OF THYROID

- It is the investigation of choice in most the thyroid diseases to conclude pathological diagnosis.
- It is useful in papillary/medullary (amyloid)/anaplastic carcinomas, lymphomas, colloid nodule, thyroiditis.
- 23G needle is used. Suspicious solitary/multiple nodules/dominant nodules should be aspirated.
- *Karolinska hospital* (Lowhagen) at Sweden pioneered this method.
- Minimum 6 aspirations should be done. An adequate FNAC smear should have six aspirations with six groups of cells with each group containing 20 cells. USG guided aspiration is better.
- Diagnostic accuracy of FNAC is 95%; sensitivity 85%; specificity 94%.
- Aspiration is *graded* as: Thy 1—Nondiagnostic; Thy 2—Nonneoplastic; Thy 3—Follicular; Thy 4—Suspicious of malignancy; Thy 5—malignancy.
- In a cyst of thyroid FNAC may be less reliable; if cyst recurs after 3 aspirations, surgery is needed.
- Malignancy rate in a simple cyst is 5%; in a complex cyst it is 75%.
- FNAC is *not reliable* at present in follicular carcinoma of thyroid as capsular and vascular invasions cannot be found. But by newer technique it is possible to identify the differences—Benign is polyploidy, malignant is aneuploidy; benign are monoclonal, malignant are polyclonal; MR spectroscopy and thyroimmunoperoxidase estimation are useful to differentiate.
- FNNAC is fine needle nonaspiration cytology—is said to be more reliable.

In the case of retrosternal goitre, hemoptysis unmixed with sputum is due to rupture of an engorged tracheal vein.

—Peter Burgess

USG in thyroid

- To identify nodules, number, size, vascularity, echogenicity
- To do USG guided FNAC
- To identify neck lymph nodes
- To find out solid or cystic nature
- Benign lesion is *hyperechoic*, often cystic with well-defined margin; shows peripheral *egg shell calcification* with sonolucent rim (halo) around nodule
- Malignant lesion is *hypoechoic* with poorly defined margin, with high vascularity, with microcalcification without any halo around



Fig. 6.11: Examination of the thyroid gland from behind for any nodules. Thyroid enlargement in male is rare. Nodule in a male could be malignant.



Fig. 6.12: Thyroid swelling moves on deglutition because of attachment of pretracheal fascia through Berry's ligament to cricoid cartilage and to constrictor muscles.

CLASSIFICATION OF GOITRE

Goitre is enlargement of thyroid gland. (*'goiter'*-*latin*-guttur-throat)

1. *Simple nontoxic*
   a. Diffuse hyperplastic:
      – Physiological
         - Puberty.
         - Pregnancy.
      – Primary iodine deficiency (Endemic; dietary iodine intake less than 100 μg/day).
      – Secondary iodine deficiency:
         - Goitrogens of Brassica family, e.g. cabbage, soya bean. Common in hill stations.
         - Excess dietary fluoride.
         - Drugs: PAS, lithium, phenylbutazone, thiocyanates, potassium perchlorate, antithyroid drugs, radioactive iodine.
         - Dyshormonogenetic goitre.
   b. Colloid goitre.
   c. Nodular goitre (Multinodular).
   d. Solitary nontoxic nodule.
   e. Recurrent nontoxic nodule.
2. *Toxic*
   a. Diffuse (Primary)—*Graves' disease.*
   b. Multinodular (Secondary)—*Plummer's disease.*
   c. Toxic nodule (solitary) (Tertiary).
   d. Recurrent toxicosis.
3. *Neoplastic*
   a. Benign—adenomas: follicular, Hurthle cell.
   b. Malignant:
      – Carcinomas: Papillary, follicular, medullary, anaplastic.
      – Lymphomas.
4. *Thyroiditis*
   a. Hashimoto's autoimmune thyroiditis.
   b. de-Quervain's autoimmune thyroiditis.
   c. Riedel's thyroiditis.
5. *Rare causes:* Bacterial (suppurative), amyloid.



Figs 6.13A and B: Note the goitres in (A) male and (B) female patient.



Figs 6.14A and B: Familial goitre. Goitres in brother and sister.

WHO grading of goitre

Grade 0: No visible or no palpable goitre.
Grade 1: Palpable thyroid/goitre but not visible in normal positioned neck.
Grade 2: goitre which is visible in normal positioned neck.

In a case of thyroid disease following things should be made very clear

- Functional status—hyperthyroid/euthyroid/ hypothyroid
- Compression on trachea/recurrent nerve
- Neck lymph nodal status
- Tracheal deviation
- Carotid infiltration
- Retrosternal extension
- Systemic features like toxicity or malignant spread to different organs like bone/liver/lungs

DIFFUSE HYPERPLASTIC GOITRE

Initial persistent increase in TSH level causes diffuse active lobules. In late stages of diffuse hyperplasia,TSH stimulation decreases and many follicles become inactive, get filled with colloid and it is called *as colloid goitre*.

*As diffuse hyperplastic goitre is a reversible stage, L-thyroxine is beneficial***.**



Fig. 6.15: *Pizzillos method* to make the thyroid more prominent while examining the thyroid.



Fig. 6.16: Multinodular goitre surgical specimen—total thyroidectomy was done.

MULTINODULAR GOITRE (MNG)

- MNG is discordant growth with functionally and structurally altered thyroid follicles presenting as multiple nodules in thyroid.
- It may be due to mainly *fluctuation in TSH level*; other causes may be iodine deficiency, goitrogens, hereditary, dyshormonogenesis.

Pathogenesis

Persistent TSH stimulation.
↓
Diffuse hyperplasia of gland (all active lobules).
↓
Later with fluctuation of TSH level.
↓
Mixed areas of active and inactive lobules develop. It is also probably due to *increased sensitivity* of follicular cells to TSH.
↓
Active lobules become more vascular and hyperplastic.
↓
Haemorrhages occur with necrosis in the centre.
↓
Nodule formation.
↓
Centre of the nodule is inactive and only margin is active, i.e. internodular tissue is active.
↓
Formation of many nodules.
↓
Multinodular goitre (MNG).

Other factors involved are growth stimulating immunoglobulins and growth prone cell clones.

Stages of multinodular goitre formation

- Stage of hyperplasia and hypertrophy
- Stage of fluctuation in TSH
- Stage of formation of nodules (inactive); (inter-nodular tissues are active)

Colloid goitre is a goitre due to long standing iodine deficiency with localised accumulation of significant colloid in the gland.

Clinical Features

- More common in middle aged females (10:1).
- It is a slowly progressive disease with many years of history.
- Multiple nodules of different sizes are formed in both lobes, also in isthmus, which is firm, nodular, nontender, moves with deglutition.

Some people speak from experience; others, from experience, don't speak.

- Recent increase in size signifies malignant transformation or haemorrhage.
- Positive Kocher's test is due to compression over trachea (tracheomalacia/scabbard trachea) in a long standing MNG.
- Nodule when calcified becomes harder; necrosis softens the nodule.



Fig. 6.17: Multinodular goitre.



Fig. 6.18: Recurrent nodule thyroid. Note scar of previous surgery.



Figs 6.19A and B: Multinodular goitre.

Note:
Thyropharyngeus and cricopharyngeus parts of inferior constrictor muscle are attached to thyroid and cricoid cartilages respectively; during swallowing these muscles will contract to move thyroid and cricoid cartilages upwards. Thyroid is attached to larynx (cricoid) through condensed pretracheal fascia, *Berry's* ligament. So thyroid moves *upwards* with deglutition.

Complications of MNG

- Secondary thyrotoxicosis (30%)
- Follicular carcinoma of thyroid (10%)
- Haemorrhage in a nodule
- Tracheal obstruction, calcification
- Cosmetic problem

Investigations

- T_3, T_4, TSH, U/S neck, FNAC. FNAC is done from most *dominant* and *suspicious* nodule. FNAC from more than one



Fig. 6.20: Goitre neck, left sided.



Fig. 6.21: Multinodular goitre. Note the nodules marked.

nodule is better; US guided FNAC is more reliable. High resolution US identifies impalpable nodules, number, nature of nodule, vascularity of nodule. Nodule less than 0.3 cm is identifiable in US.

- X-ray neck shows ring or rim calcification; also reveals the position (displacement) and compression of trachea.
- Indirect laryngoscopy to see vocal cords prior to surgery (This is mainly for documentation and legal purpose as even in individual with normal voice, one of the vocal cords may have been paralyzed by viral infection like mumps, probably during childhood and have compensated)—occult *recurrent laryngeal nerve* (RLN) palsy.
- Radioisotope iodine scan—in selected patients when indicated only.
- Routine blood investigations, serum calcium.
- CT scan/MRI are routinely not indicated. It is done in retrosternal extension.

Treatment

Usually surgery is preferred. Reason for doing surgery in nodular goitre is—it is an irreversible stage and chances of complications like development of toxicity, haemorrhage and follicular carcinoma is high and also for cosmetic reason.

- When entire gland is diseased *total thyroidectomy* is a better option.
- *Subtotal thyroidectomy* is done depending on the amount of gland involved, amount of normal gland existing and location of nodules—commonly done procedure in multinodular goitre. Eight grams of thyroid tissue is retained in each lateral lobe.
- Often partial thyroidectomy or *Hartley Dunhill operation* (isthmus + one entire lateral lobe and opposite side subtotal or partial) is also done depending on the amount of diseased gland and normal tissues behind. Partial thyroidectomy is not well approved now.
- Postoperative L thyroxine is often given to prevent any fluctuation in TSH level which may cause recurrent nodule formation.



Fig. 6.22: Large multinodular goitre.



Fig. 6.23: Nodular thyroid involving both lobes in a female.



Fig. 6.24: X-ray neck showing calcification in thyroid. *Fine* calcification is seen in papillary carcinoma. *Coarse* calcification is seen in multinodular goitre.

- Prevention of multinodular goitre is possible by supplementing with L-thyroxine (0.1-0.2 mg) when patient develops goitre in puberty. Formation of nodular goitre can be prevented by correcting iodine deficiency by using iodine rich diet like eggs/seafood/milk or iodized salts and also avoiding goitrogenic drugs and diet.
- Suppressive dose of L-thyroxine alone may be used occasionally in small nodules with limited results. TSH level should be suppressed consistently below 0.5 mIU/L. Problems are need of periodic monitoring with TSH estimation; hormone insensitive part of thyroid tissue continue to grow; indefinite period of treatment; high recurrence after stopping L-thyroxine. So it is not ideally accepted therapy. It is found that TSH suppression is of no use in treating residual/recurrent MNG.



Figs 6.25A and B: Solitary nodule thyroid in one lateral lobe and isthmus.

Note:
Adequate thyroidectomy is essential, either total or subtotal, complete removal of diseased thyroid without retaining is considered, in view of chances of high recurrence in 10 or more years due to incomplete removal. Re-surgery for recurrent MNG is difficult due to loss of anatomical plane and fibrosis; hence total thyroidectomy is often advised.

DISCRETE THYROID NODULE

- ***Discrete thyroid nodule*** (4% of adult population) is *a* clearly palpable nodule in thyroid. It can be ***solitary (isolated) nodule*** (70%) if clinically only *a* nodule is felt without palpable remaining gland *OR* it can be ***dominant nodule*** (30%) if clinically *a* nodule is felt in a palpable remaining one or both lateral thyroid lobes.
- A *discrete thyroid nodule* is common in females. Discrete nodule may be solid or cystic. USG, CT, MRI may confirm the diagnosis.
- 15% solitary/isolated nodule may be malignant; 40% may be follicular adenoma. Other causes are thyroid cyst, thyroiditis or colloid degeneration.
- Incidence of malignancy in *dominant nodule* is 50% less than that of solitary nodule.
- Risk factors for malignancy in *discrete thyroid nodule* are—(1) ***solitary*** is 2 times more risk than dominant; (2) ***male*** is 4 times more than female (in solitary—48% to 12% in solid, 24% to 6% in cystic; in dominant 24% to 6% in solid, 12% to 6% in cystic); (3) ***solid nodule*** is 2 times more risk than cystic—Rule of 12.

SOLITARY THYROID NODULE

It is a single palpable nodule in thyroid on *clinical examination*, in an otherwise normal gland. *Rest of the gland is impalpable*.

Causes

1. Thyroid adenomas—20%.
    a. Follicular—colloid (commonest); embryonal; fetal.
    b. Hurthle cell.

***Note*:**
Papillary adenoma earlier called, was actually papillary carcinoma).



Fig. 6.26: Solitary nodule thyroid involving isthmus.

2. Papillary carcinoma of thyroid—20%
3. Only one nodule may be clinically palpable in an underlying multinodular goitre—50%.
4. Thyroid cyst—10%.

Types

1. Toxic solitary nodule—3-5% of solitary nodules of thyroid
2. Nontoxic solitary nodule.
   Based on radioisotope study:
    - *Hot*: Means autonomous toxic nodule. Normal surrounding thyroid tissue is inactive and so will not take up isotope. Nodule is overactive. It is 5% common of which only 5% can be malignant.
    - *Warm*: Normally functioning nodule. Nodule and surrounding normal thyroid will take up the isotope (active). It is 10% common of which 10% can be malignant.
    - *Cold*: Nonfunctioning nodule; may be malignant (need not be always). Nodule will not take up isotope (underactive). It is 80% common of which 20% are malignant.

Features

- Single nodule palpable in one or other lobes of the thyroid which is usually smooth and firm.
- Lahey's test does not show any other nodules in posterior part of the gland.
- *Hot or warm in* ^{99m}Tc *scan but cold in* I^{123} *scan (discordant nodule)* commonly they are malignant.
- Thyroid nodule in children and elderly can be malignant.
- Rapid enlargement of thyroid nodule can be malignant.
- Tracheal deviation towards opposite side is common– confirmed by *trail sign*, three-finger test, auscultation and X-ray neck.
- 30% of solitary nodules are cystic.
- 20% of cold nodules are malignant. Cold nodule may be due to malignancy, thyroiditis, thyroid cyst or haemorrhage, benign adenoma.
- Commonest site of a nodule is at the junction of isthmus with one of the lateral lobes.
- Solitary thyroid nodule is the most common thyroid surgical disease.

Possible features of suspected malignancy in solitary nodule thyroid

- Any nodule can be malignant whether it is hard/ firm/cystic/ small/large/asymptomatic
- Rapid onset/rapid recent increase in size
- Hoarseness of voice/dysphagia/stridor/dyspnoea
- Fixity of the nodule
- Palpable significant neck nodes
- Nodule in a male patient
- Nodule in a child (50% are malignant)
- Nodule in extremes of age group



Fig. 6.27: Solitary nodule thyroid, left-sided.



Fig. 6.28: Solitary nodule thyroid.



Figs 6.29A and B: Trachea should be clinically examined to find out whether it is central or deviated. In goitre involving both lobes, it is central. One lateral lobe enlargement usually causes deviation of trachea towards opposite side. Tracheal compression should be checked by *Kocher's test*. It confirms the *scabbard trachea*.

Success consists of a series of little daily efforts.

Investigations

- U/S neck (very useful).
- FNAC.
- T_3, T_4, TSH.
- *Power Doppler* is done to know the vascularity of the gland. Vascularity is described in ***resistive index (RI)*** (Harley De Nicola 2005). Normal RI is 0.65-0.7; if RI is more than 0.7 it indicates malignancy in that nodule. Malignant nodule shows anarchical angiogenesis. Flow pattern are: Type 0 – no flow; Type 1: only peripheral flow; Type 2: peripheral with small central flow; Type 3: peripheral with extensive central flow; Type 4: only central flow.
- Radioisotope study ($I^{123}/I^{131}/^{99m}Tc$).
- Serum calcitonin estimation if FNAC confirms medullary carcinoma.
- CT scan or MRI neck is not done routinely, but only in selected cases. Large swelling/to see vascularity/retrosternal extension are the indications.
- X-ray neck to see tracheal deviation.

Note:
True incidence of solitary nodule will come down to 50% from its original clinical diagnosis after investigations and surgical exploration.



Figs 6.30A and B: Ultrasound pictures of thyroid. It is often used to see nodules, content—solid/fluid, size and extent.



Fig. 6.31: FNAC of thyroid (*Courtesy:* Dr Krishna Upadhya, Pathologist, Nandikoor Laboratory, Mangalore).



Fig. 6.32: Patient earlier operated for nodular goitre. Note recurrent nodule and scar of previous surgery.

Treatment

Indications for surgery in solitary nodule thyroid

- Malignant nodule
- Follicular neoplasm
- Toxic nodule in young
- Nodules with obstruction
- Recurrent cystic nodule
- Complex cyst (both solid and cystic components)
- Cosmetic reason

- If it is a *nontoxic nodule due to any cause, hemithyroidectomy* with complete removal of lateral lobe and whole of the isthmus is done.
- If it is *papillary carcinoma thyroid*, then *near total thyroidectomy* is done along with suppressive dose of L-thyroxine given 0.3 mg OD daily.
- If it is a *toxic nodule, radioiodine therapy,* I^{131}—5 milli curie is given orally, if the age of the patient is more than 45 years.
- If age is less than 45 years, then initially toxicity has to be controlled by antithyroid drugs, always followed by *surgery—Hemithyroidectomy*.

- If FNAC report says follicular adenoma, then hemithyroidectomy is done. If histology report says follicular carcinoma (capsular and vascular invasion) then completion total thyroidectomy is done. *Completion thyroidectomy* is done usually within 7 days or after 3 weeks. If frozen section biopsy proves carcinoma then total thyroidectomy is done.
- If there is a nodule in the isthmus, isthmectomy is done with excision of part of adjacent lateral lobes.
- If FNAC report says medullary carcinoma of thyroid, then total thyroidectomy with bilateral neck nodal dissection including central compartment is done.
- Colloid nodule may respond for conservative drug treatment using thyroxine orally in 50% cases. If nodule reappears/ enlarges progressively and significantly/causing cosmetic problem then hemithyroidectomy is indicated in colloid nodule.

Thyroid cyst

- It is thyroid swelling which is cystic in nature eliciting positive fluctuation
- But tensely cystic swelling can be hard (*thyroid paradox*—with cellular tumour of thyroid can be soft also)
- Common cause is colloid degeneration—50%. There will be absence of epithelial lining
- Involution in follicular adenomas present like a cyst; 15% of such cysts may be malignant
- 30% of solitary nodules are cystic
- 15% cystic swellings in thyroid are malignant
- Cyst formation is common in papillary carcinoma of thyroid
- A cyst if contains both solid and cystic areas is called as complex cyst which is more likely to be malignant
- FNAC may cause regression of simple cyst. Even after three repeated aspirations if recurrence occurs, surgery is needed
- Surgery is indicated in complex cyst and if cyst is more than 4 cm in size

RETROSTERNAL GOITRE

Retrosternal goitre is defined as having > 50% goitre below the suprasternal notch.

- *Primary* is rare—1%. Primary retrosternal goitre arises from ectopic thyroid tissue from mediastinum. It gets its blood supply from mediastinum itself, not from the neck. And also it is not related to the existing thyroid in the neck.
- *Secondary* is common. It is extension from the enlarged thyroid from the neck. Usually arises from the lower pole of a nodular goitre. Commonly seen in short neck or obese individuals. Due to negative intrathoracic pressure, nodule gets drawn into the superior mediastinum.

Types

1. *Substernal type*: Part of the nodule is palpable in the lower neck.
2. *Plunging goitre*: An intrathoracic goitre is occasionally forced into the neck by increased intrathoracic pressure.
3. *Intrathoracic goitre* itself. Neck is normal.



Fig. 6.33: Lower border should be checked to confirm retrosternal extension whether present or not.



Fig. 6.34: Superior vena cava obstruction due to thyroid extending into the retrosternal area. Note the dilated veins over neck, chest wall and arm.

Clinical Features

- Dyspnoea at night during lying down or neck extended.
- Cough and *stridor* (stridor is harsh sound on inspiration).
- Dysphagia.
- Engorgement of neck veins and superficial veins on the chest wall.
- Lower border is not seen on inspection and not felt on palpation.
- *Pemberton's sign* is positive. The patient is asked to raise the arm above the shoulder level. Dilated veins are seen over neck and upper part of chest wall. Stridor and rarely dysphagia may occur. (When patient raises the arm above the shoulder level, retrosternal goitre compresses over the



Figs 6.35A to C: (A and B) X-rays (PA view and lateral view) showing retrosternal goitre. (c) Diagrammatic representation of the retrosternal goitre.

easily compressible structures like SVC and trachea causing dilated veins and dyspnoea respectively).

- Dull note over the sternum on percussion.
- Retrosternal goitre can be either nodular, toxic or malignant.
- Rarely recurrent nerve palsy can occur.

Differential Diagnosis

- Mediastinal tumours.

Investigations

- Chest X-ray shows soft tissue shadow under the sternum.
- Radioactive iodine study is diagnostic.
- CT scan is useful.

Treatment

- Surgical removal of retrosternal thyroid is done. Commonly it can be removed through an incision in neck (as blood supply of retrosternal goitre is from neck), but in case of large retrosternal extension or in malignant type median sternotomy is required (rarely).

***Note*:**

- *Radioiodine therapy is not accepted in retrosternal goitre.*
- Stridor due to compression of tracheobronchial tree by retrosternal goitre is very dangerous because it is often not possible to clear the airway either by intubation or by tracheostomy.
- Surgical removal should be complete because recurrent retrosternal goitre is very difficult to re-operate.

Breathing difficulties in thyroid swelling

- Retrosternal goitre—positive Pembertone's sign
- Multinodular goitre of long duration—positive Kocher's test—compressive stridor
- Secondary toxic goitre—congestive cardiac failure
- Carcinoma infiltrating the trachea—stridor on rest—without compression with fingers

THYROTOXICOSIS AND HYPERTHYROIDISM

> I have lately seen three cases of violent and long-continued palpitations in females, in each of which the sample peculiarity presented itself—viz., enlargement of the thyroid gland.... A lady, aged twenty, became affected with some symptoms which were supposed to be hysterical.... It was now observed that the eyes assumed a singular appearance, for the eyeballs were apparently enlarged, so that when she slept, or tried to shut her eyes, the lids were incapable of closing.
> **—Robert James Graves,** 1835 (Irish physician)

Thyrotoxicosis is *symptom complex due to raised levels of thyroid hormones***.**

Thyrotoxicosis refers to biochemical and physiological manifestations of excessive thyroid hormones. *Hyperthyroidism* is the term used for overproduction of the hormones by thyroid gland. In hyperthyroidism pathology is in thyroid gland itself. Hyperthyroidism is one of the causes of *thyrotoxicosis*. *Thyrotoxicosis* can also occur due to other causes other than hyperthyroidism.

Other causes of thyrotoxicosis without hyperthyroidism are—ectopic functioning thyroid, struma ovarii, functioning metastatic follicular carcinoma, trophoblastic tumours, thyrotoxicosis factitia.

Types

1. Diffuse toxic goitre—(Graves' disease, *Basedow's disease*. Primary thyrotoxicosis).
2. Toxic multinodular goitre (Secondary thyrotoxicosis) (*Plummer disease*).
3. Toxic nodule *(Goetsch's disease)*.
4. Thyrotoxicosis due to rarer causes:
    a. *Thyrotoxicosis factitia*—drug induced. Due to intake of L-thyroxine more than normal.
    b. *Jod Basedow thyrotoxicosis*—because of large doses of iodides given to a hyperplastic endemic goitre.
    c. *Autoimmune thyroiditis or de Quervain's thyroiditis*.
    d. Occasionally *carcinoma thyroid.*
    e. *Neonatal thyrotoxicosis*. It subsides in 3-4 weeks as TsAb titres fall in the baby's serum.
    f. Struma ovarii.
    g. Drugs like amiodarone—an antiarrhythmic agent.
    h. Very rarely, well-differentiated carcinoma can cause thyrotoxicosis.

[***Wolf-Chaikoff effect***—Iodides inhibit the further release of hormone causing hypothyroidism *(Hokkaido goitre)*.]

Graves Disease

Graves disease is an autoimmune disease with increased levels of specific antibodies in the blood (TSH receptor antibodies). It is often associated with vitiligo. It is often familial. Thyroid stimulating immunoglobulins (TSI)/thyroid stimulating antibodies (Ts Ab) and long acting thyroid stimulator (LATS) cause pathological changes in the thyroid. Histologically there is acinar cell hypertrophy and hyperplasia with absence of normal colloid in the tall columnar epithelium (normal is flat epithelium with colloid). As cells are empty, they look vacuolated. Tissues are highly vascular. Exophthalmos producing substance (EPS) causes Graves ophthalmopathy.



Figs 6.36A and B: Graves disease in a female and male patient. Note the exophthalmos with clearly visible lower sclera.

- Diffuse goitre, thyrotoxicosis and autoimmune manifestations like infiltrative ophthalmopathy, dermopathy, myopathy are essential components of Graves, disease. Thyroid stimulating immunoglobulins (TSI) are produced against thyroid antigen in Graves disease which is directed to TSH receptor acting as TSH receptor antibody. *This TSHR Ab is observed only in Graves disease*.
- Puberty, pregnancy, emotion and infection are the precipitating factors for primary thyrotoxicosis.
- Familial/genetic cause is also attributed in Graves disease (50%); both identical twins can develop Graves disease.
- There is *hyperplasia and hypertrophy* of entire thyroid due to prolonged continuous action by binding of abnormal thyroid stimulating antibodies to TSH receptor sites.

Toxic Adenoma

- It is benign functioning monoclonal thyroid tumour, usually more than 3 cm in size.
- It usually presents as *functioning (toxic) solitary nodule* of thyroid.
- It is autonomous functioning tumour; not TSH responding.
- Toxic adenoma secretes large quantity of thyroid hormones suppressing the function of the remaining normal thyroid tissue.
- There are no eye signs and other features of Graves disease.
- It commonly shows higher T_3 levels than T_4.
- TSH receptor or G protein genes show somatic mutation.
- US neck, T_3, T_4, TSH and radioisotope scan (shows *hot* nodule)—are the relevant investigations.

Hope sees the invisible, feels the intangible and achieves the impossible.

Treatment

- Initial control of toxicity with antithyroid drugs; later hemithyroidectomy is done after 6 weeks. Once thyroidectomy is done, suppressed remaining normal thyroid tissue starts functioning to secrete normal level of thyroid hormones.
- In patients after the age of 45 years radioactive iodine therapy can be used which selectively concentrates and ablates the thyroid adenoma; later remaining normal thyroid starts functioning.

T_3 Toxicosis

Here T_3 alone is raised; TSH is decreased; T_4 is normal.
Free T_3 estimation is important.

Subclinical Hyperthyroidism

- Here serum TSH is low; free T_4 is normal; there are no symptoms.
- Its incidence is 1% of hyperthyroidism.
- It is one of the causes for infertility often missed (both subclinical hyper- and hypothyroidism can cause infertility in females).
- It needs radioisotope study; US neck.
- It requires treatment—antithyroid drugs, often thyroidectomy.

Struma Ovarii

- Ovarian teratoma with thyroid differentiation will secrete T_3 and T_4 and suppress TSH.
- Function of normal thyroid in neck is suppressed.
- Radioisotope scan shows uptake in pelvis with no or less uptake in neck.

Note:

The River *Struma* arises in Bulgaria and flows into Aegean Sea. Endemic goitre exists in area along its banks; '*Struma*' means goitre.

Hashitoxicosis

- It is due to autoimmune Hashimoto's thyroiditis.
- Mild toxic features develop during initial stage of hyperplasia.
- Already formed thyroid hormones are released by inflamed gland causing toxicity. It eventually leads into euthyroid and later hypothyroidism in Hashimoto's disease.

Thyrotoxicosis Factitia

Intake of L thyroxine *without indications* to lose weight or over dose intake causes toxicity.

Postpartum Hyperthyroidism

It is exacerbation of previously confirmed or undiagnosed hyperthyroidism during pregnancy or after delivery due to increased autoimmune factors.

It is associated with HLA DR3 and HLA DR5.

Neonatal Thyrotoxicosis

It is seen in infants born to mother with Graves' disease due to crossing of the thyroid stimulating antibody (TSH RAb) across placental barrier. Infant will be toxic for 3-4 weeks which subsides gradually.

Trophoblastic Thyrotoxicosis

HCG secreted from vesicular mole, choriocarcinoma or metastatic embryonal carcinoma in females, acts like TSAb causing toxicity.

Jod Basedow Thyrotoxicosis

Patient with hyperplastic endemic goitre takes large doses of iodide, which will be taken up by hyperplastic gland in large quantity causing temporary hyperthyroidism called as *Jod Basedow thyrotoxicosis*. It differs from Basedow disease which is the other name for Graves disease ('*Jod*'—in German means iodine).

Apathetic Hyperthyroidism

- It lacks all usual clinical features of toxicity.
- It is commonly observed in old people.
- Thyroid gland is not enlarged.
- Patient presents with behavioral problems; often considered as psychiatry patient with decreased appetite.
- Such lethargic individual also often show features of recent angina and atrial fibrillation.
- Unless serum T_3, T_4 and TSH are done diagnosis is masked.

Clinical Features of Thyrotoxicosis

- It is eight times more common in females.
- Occurs in any age group.
- Primary type is seen commonly in younger age group.
- Secondary type is common in older age group.
- Graves disease often presents without any obvious thyroid swelling in the neck. Whenever there is unexplained behavioural problem, insomnia, myopathy, unexplained diarrhoea or loss of weight, tachycardia, Graves disease should be suspected and evaluated.

A. Symptoms of Hyperthyroidism/Toxicosis

Gastrointestinal system

- Weight loss in spite of increased appetite.
- Diarrhoea (due to increased activity at ganglionic level).

Cardiovascular system

- Palpitations.
- Shortness of breath at rest or on minimal exertion.
- Angina.
- Irregularity in heart rate.
- Cardiac failure in the elderly (CCF).

Differentiating points between primary and secondary hyperthyroidism

Primary thyrotoxicosis	***Secondary thyrotoxicosis***
1. Symptoms appear first, then thyroid swelling	1. Thyroid swelling appears first
2. Goitre is diffuse, smooth, firm or soft, both lobes are involved with thrill and bruit	2. Swelling is large nodular, obvious
3. Features are much more severe compared to that of secondary toxicosis of short duration	3. Symptoms appear after long time, which is less severe and slowly progressive compared to primary toxicosis
4. Eye signs and exophthalmos are common	4. Eye signs are not common
5. As it is an autoimmune disease, there may be hepatosplenomegaly	5. Cardiac features are more common
6. It occurs in younger age group	6. It occurs in adult and elderly individual
7. Entire gland is overactive	7. Internodular tissues are overactive
8. There is no preexisting goitre	8. Occurs in a long standing preexisting multinodular goiter
Histologically, there is hyperplasia of acini, lined by columnar epithelium, often containing vacuolated colloid scalloping with pseudopapillary formation	

Neuromuscular system

- Undue fatigue and muscle weakness.
- Tremor.

Skeletal system

- Increase in linear growth in children.

Genitourinary system

- Oligo- or amenorrhoea.
- Occasional urinary frequency.

Integument

- Hair loss, gynaecomastia.
- Pruritus.
- Palmar erythema.



Fig. 6.38: Primary thyrotoxicosis. Note the exophthalmos.



Fig. 6.37: Diffuse toxic goitre (primary) involves both lobes with hyperfunctioning acini.



Figs 6.39A and B: Note the dilated veins in an enlarged vascular thyroid gland. Auscultation is important to hear a bruit.

One person with passion is greater than ninety-nine who have only an interest.

Psychiatry

- Irritability.
- Nervousness.
- Insomnia.

Sympathetic overactivity

- It causes dyspnoea, palpitation, tiredness, heat intolerance, sweating, nervousness, increased appetite and decrease in weight.
- Because of the *increased catabolism* they have increased appetite, decreased weight and so also increased creatinine level which signifies *myopathy* (due to more muscle catabolism).

Fine tremor is due to diffuse irritability of grey matter.

B. Signs of Hyperthyroidism/Toxicosis

1. Eye Signs in Toxic Goitre

Eye signs are common in primary thyrotoxicosis. Lid lag, lid spasm can occur in secondary thyrotoxicosis also.

1. *Lid retraction:* Here upper eyelid is higher than normal; lower eyelid is in normal position. It is due to *sympathetic over activity* causing spasm of involuntary smooth muscle part of the levator palpebrae superioris (*Muller's muscle*). It is *a sign of* thyrotoxicosis, *not a sign* of exophthalmos.
2. *von Graefe's sign* (Lid Lag's sign): It is inability of the upper eyelid to keep pace with the eyeball when it looks downwards to follow the examiners finger.
3. *Dalrymple's sign*: Upper eyelid retraction, so visibility of upper sclera.
4. *Stellwag's sign*: Absence of normal blinking—so *staring look*. First sign to appear. It is due to widening of palpebral fissure due to lid retraction and also due to contraction of voluntary part of levator palpebrae superioris muscle.
5. *Joffroy's sign*: Absence of wrinkling on forehead when patient looks up (frowns).
6. *Moebius sign*: It is lack of convergence of eyeball. Defective convergence is due to lymphocytic infiltration of inferior oblique and rectus muscles in case of primary

Wayne's diagnostic indices (clinical)

	Symptoms	*Present*	*Absent*
1.	Dyspnoea on effort	+1	
2.	Palpitation	+2	
3.	Tiredness	+2	
4.	Preference to heat		–5
5.	Preference to cold (Heat intolerance)	+5	
6.	Excessive sweating	+3	
7.	Nervousness	+2	
8.	Appetite increased	+3	
9.	Weight decreased	+3	
	Signs	*Present*	*Absent*
1.	Bruit over thyroid	+2	
2.	Exophthalmos	+2	
3.	Lid retraction	+2	
4.	Lid lag	+1	
5.	Hyperkinetic movements	+4	–2
6.	Fine finger tremors	+1	
7.	Hands hot	+2	–2
	Moist	+1	–1
8.	Atrial fibrillation	+4	–3
9.	Pulse rate 80/minute	0	
	80-90/minute	+3	
	More than 90/minute	+3	
10.	Palpable thyroid		
	< 11 points—nontoxic goitre	11-19 equivocal	> 19 points—toxic

thyrotoxicosis. There will be diplopia. It may be an early sign of eventual ophthalmoplegia.

7. *Jellinek's sign*: Increased pigmentation of eyelid margins.
8. *Enroth sign*: Oedema of eyelids and conjunctiva.
9. *Rosenbach's sign*: Tremor of closed eyelids.
10. *Gifford's sign*: Difficulty in everting upper eyelid in primary toxic thyroid. Differentiates from exophthalmos of other causes.
11. *Loewi's sign*: Dilatation of pupil with weak adrenaline solution.
12. *Knie's sign*: Unequal pupillary dilatation.
13. *Cowen's sign*: Jerky pupillary contraction to consensual light.
14. *Kocher's sign*: When clinician places his hands on patient's eyes and lifts it higher, patient's upper lid springs up more quickly than eyebrows.
15. *Naffziger's sign*: With patient in sitting position and neck fully extended, protruded eyeball can be visualized when observed from behind.

Order of appearance of signs

- Stellwag's sign—mild; first sign to appear
- von Graefe's sign—mild
- Joffroy's sign—moderate
- Moebius sign—severe

EXOPHTHALMOS

- It is proptosis of the eye, caused by infiltration of the retrobulbar tissues with fluid and round cells, with *lid spasm* of upper eyelid (Lid spasm is spasm of levator palpebrae superioris muscle which is partly innervated by sympathetic fibres).
- Sclera can be seen clearly below the limbus of the eye.
- Proptosis can be measured by *exophthalmometer.*
- Exophthalmos is often self limiting, but not always. Sleeping in propped up position and lateral tarsorrhaphy will help to protect the eye.

Severe Exophthalmos

- Eyelid oedema, chemosis, conjunctival injection.
- Diplopia, ophthalmoplegia (complete weakness of all extraocular muscles and so no movements possible).
- Corneal ulceration.
- Papilloedema soon develops.
- Finally it may also cause loss of vision.

It is called as ***malignant exophthalmos*** (It is misnomer even though it is not malignant nor related to any malignancy).

Treatment is emergency, i.e. large doses of systemic steroids (Prednisolone) are given along with *orbital decompression*, systemic antibiotics, steroid drops, antibiotic drops.

- **Remember:**
  - *Antithyroid drugs may worsen exophthalmos and the patient should be observed once antithyroid drugs are started as steroid supplementation may be required.*
  - Ophthalmopathy may worsen by thyroidectomy or radioiodine therapy also.

Treatment of severe exophthalmos

- Steroids intravenously
- IV antibiotics
- Guanethidine, steroid, antibiotic drops
- Lateral tarsorrhaphy
- Orbital decompression by surgical removal of lateral wall or roof of orbit
- Diuretics
- Dark spectacles, protective eye patches
- Eyelid surgeries, extraocular muscle surgeries
- Local radiation therapy to orbital space
- 1% methylcellulose eye drops to prevent corneal ulceration.
- Sleeping with head end elevation

- **Lid retraction** is higher upper eyelid with normal lower eyelid with visible sclera adjacent to upper eyelid
- **Lid lag** is inability of the upper eyelid to keep pace with the eyeball when it looks downwards to follow the examiners finger
- **Exophthalmos** is visible sclera *first below* (lower part) the lower edge of the iris and later eventually upper part of sclera will be visible. It is due to pushing of the eyeball forwards due to fat, oedema fluid, cells like macrophages in retrobulbar space


Normal
Upper eyelid between upper limbus and pupil
Lid retraction
Upper eyelid raised lower eyelid normal
Exophthalmos
Both upper and lower eyelids away from the centre with visible sclera all around mainly below

Fig. 6.40: Diagram showing normal relation of eyelid and pupil in lid retraction and exophthalmos.



Fig. 6.41: Malignant exophthalmos.

You don't drown by falling in the water; you drown by staying there —**Edwin Louis Cole**

Important signs to be remembered

- *Visible lower sclera—sign of exophthalmos*
- Naffziger's sign
- von Graefe's sign-upper lid lag—contraction/overactivity of the involuntary part of the levator palpebrae superioris muscle—Muller's muscle
- Joffroy's sign
- Moebius sign—*most important—early sign of ophthalmoplegia*

Thyroid ophthalmopathy in Grave's disease-Werner's abridged classification of ocular changes with van Dyke's modification

Class-grade	*Definition*
0	No signs and symptoms
1	Eye signs only—refer table below for eye signs
2	Soft tissue involvement
3	Proptosis more than 22 mm
4	Extraocular muscle involvement
5	Corneal involvement- ulceration
6	Loss of sight/vision due to optic nerve and corneal involvement

Eye signs only

- Resistance to retro-displacement of eye
- Oedema of conjunctiva and caruncle
- Lacrimal gland enlargement
- Injection of conjunctiva
- Oedema and fullness of lids

Grading of exophthalmos

- **Mild:** Widening of palpebral fissure due to lid retraction
- **Moderate:** Orbital deposition of fat causing bulging with positive Joffroy's sign
- **Severe:** Congestion with intraorbital oedema, raised intra-ocular pressure, diplopia and ophthalmoplegia
- **Progressive:** In spite of proper treatment progression of eye signs is seen with chemosis, corneal ulceration and ophthalmoplegia

2. Cardiac Manifestations

1. Tachycardia is common.

   As per **Crile's grading**

   Sleeping pulse rate is usually checked for three consecutive nights and average is taken as the value.

Pulse rate

- Grade I: < 90/mt
- Grade II: 90-110/mt
- Grade III: >110/mt

2. Ectopic.
3. Pulsus paradoxus.
4. Wide pulse pressure.
5. Multiple extrasystoles.
6. Paroxysmal atrial tachycardia.
7. Paroxysmal atrial fibrillation.
8. Persistent atrial fibrillation (not responsive to digoxin).

3. Myopathy

1. Weakness of proximal muscles occurs, i.e. the front thigh muscles, arm muscles.
2. Weakness is more when muscle contracts isometrically either while getting down steps, or lifting a full bucket.
3. Often when it is severe it resembles myasthenia gravis. Once hyperthyroidism is controlled recovery occurs.

4. Pretibial Myxoedema

It is a misnomer. *Pretibial myxoedema* is often a feature of primary thyrotoxicosis:

- Is usually bilateral, symmetrical, shiny, red thickened dry skin with coarse hair in the feet and ankles.
- In severe cases skin of entire leg below the knee with involvement of foot and ankle can occur.
- It is due to deposition of myxomatous tissues (mucin like deposits) in skin and subcutaneous plane. Glycosaminoglycans (hyaluronic acid) deposition occurs.
- It might or might not regress completely after treatment for toxicity.
- It is associated with exophthalmos with high levels of thyroid stimulating antibodies.
- Skin becomes cyanotic when cold. Skin changes in toxicosis are called as *thyroid dermopathy*. They include—pretibial myxoedema, pruritus, palmar erythema, hair thinning, Dupuytren's contracture (fascial).

5. Thyroid Acropachy

Thyroid acropachy is clubbing of fingers and toes in primary thyrotoxicosis. Hypertrophic pulmonary osteoarthropathy can develop.

6. Others

- *Thrill is felt* in the upper pole of the thyroid and also bruit on auscultation. It is because in upper pole, superior thyroid artery enters the gland superficially and so thrill and bruit can easily be felt. In lower pole inferior thyroid artery enters the gland from deeper plane and so thrill cannot be felt.
- Hepatosplenomegaly.

TOXIC NODULE

- Is a solitary overactive nodule.
- There is an autonomous hypertrophy and hyperplasia of a part of the gland where there is a nodule. [It is not due to Thyroid stimulating antibody (Ts Ab)].
- Here high levels of circulating thyroid hormones suppress TSH secretion and so, normal thyroid tissue surrounding the nodule is itself suppressed and inactive.
- Once patient becomes euthyroid by drugs, surgery (hemithyroidectomy) or radioactive iodine therapy I^{131} in a therapeutic dose of 5 m curie is given orally.
- Because normal gland is inactive, radioactive iodine affects only the autonomous nodule, allowing the normal gland to remain intact which later gets activated and functions normally.

Causes of exophthalmos	***Causes of pulsating exophthalmos***
	Carotid-cavernous sinus A-V fistula
Endocrinal	Cavernous sinus thrombosis
• Thyrotoxicosis—common	Orbital vascular neoplasm
• Cushing's syndrome, acromegaly—rare	Orbital haemangioma
	Ophthalmic artery aneurysm
Congenital deformities of skull	
• Craniostenosis, oxycephaly, hypertelorism	
Primary tumours	
• Periorbital meningioma	
• Optic nerve glioma	
• Orbital haemangioma	
• Lymphoma	
• Osteoma	
• Pseudo tumour—granuloma	
Secondary tumours	
• Antral carcinoma, neuroblastoma	
Inflammatory	
• Orbital cellulites, frontal sinusitis	
Vascular causes	
• Cavernous sinus thrombosis/A-V fistula	
• Ophthalmic artery aneurysm	
Other eye causes	
• Severe myopia	
• Severe glaucoma—buphthalmos	

- Drugs are used initially, only for a temporary period to make the patient euthyroid.
- Before the age of 45, surgery is preferred.
- After 45 years age, radioiodine therapy is used.

Investigations

- *Thyroid function tests*

  Serum T_3 and T_4 levels are very high. TSH is very low or undetectable. Sometimes, only T_3 level is increased and is called as *T_3 toxicosis*. Here in T_3 toxicosis, *free T_3 estimation is important*. Free T_3, free T_4 estimation is done as total T_3 and total T_4 levels will vary depending on the amount of thyroid binding globulin (TBG). TBG will be raised in pregnancy, cirrhosis, hyperestrogenism. It decreases in conditions with high androgen level, hypoproteinaemia, acromegaly. Free T_3 and free T4 are measured using radioimmunoassay. Normal free T_3 is 3.0-9.0 pmol/L; free T_4 is 8-26 nmol/L.

Type of disease	***T_4***	***T_3***	***TSH***
Conventional hyperthyroidism	Increased	Increased	Undetectable
T_3 hyperthyroidism	→	Increased	Undetectable
Subclinical hyperthyroidism	→	→	Undetectable

- *Radioisotope study*
  - *Radioisotope study by I^{131}* (Diagnostic dose -5 microcurie is used) shows more uptake, i.e. *hot nodules* or hot areas. This is very useful in autonomous solitary toxic nodule.
  - I^{131} causes more irradiation and its half life is 8 days. So *intravenous ^{99m}Tc* is used for diagnostic purpose. 99m technetium has become isotope of choice for diagnosis as it is cheap, less radiation, scanning is done 20 minutes after IV injection of ^{99m}Tc (half life is 6 hours). Drawback of technetium is that it concentrates in carcinoma, so forms hot nodule (means hot nodule need not be benign in Tc scanning). Warm nodule in Tc scan may appear as cold nodule in RAI scan and so is called as *discordant nodule* which suggests malignancy. If radioactive iodine is used for diagnosis then I^{123} is better as it has got short half life (13 hours).
  - Autonomous toxic nodule is absolute indication for radioisotope scan in toxic thyroid showing *hot nodule*. Graves disease shows *diffuse* over activity (*uniform*); hypofunctioning cold nodule in Graves disease could be malignant. In secondary thyrotoxicosis internodular tissues are overactive (*heterogenous* activity). Nonhyperthyroid toxicosis shows increased uptake in nonthyroid areas of toxicity like struma ovarii in pelvis.
- TRH estimation.
- ECG—to look for cardiac involvement; if required opinion from cardiologists is taken and cardiac problems are managed.

Dissatisfaction and discouragement are not caused by the absence of things but the absence of vision.

- Total count and neutrophil count are very essential base line investigations before starting antithyroid drugs (as it may cause agranulocytosis).
- Thyroid antibodies estimation—antithyroglobulin antibody, TSH receptor antibody.

Treatment

- Antithyroid drugs
- Surgery
- Radioiodine therapy

1. ANTITHYROID DRUGS

Indications for antithyroid drugs:

- Toxicity in pregnant women—Propylthiouracil is preferred
- Toxicity in children and young adults
- Before subtotal thyroidectomy, to make the patient euthyroid
- Soon after starting radioactive I^{131} therapy for 6 to 12 weeks (Effects of radiotherapy start only in 6 to 12 weeks)

a. Carbimazole:

- Is the commonest drug used.
- Dose is 5-10 mg, exactly 8th hourly (as T1/2 of carbimazole is 8 hours). Each tablet is 5 mg.
- Usually given for 12-18 months.
- Peak plasma level should be maintained in optimum concentration to have a proper benefit.
- Often tri-iodothyronine 20 microgram 4 times daily or Thyroxine 0.1 mg daily are given in combination with antithyroid drugs, to prevent iatrogenic thyroid insufficiency or to prevent the increase in size of goitre.
- It acts by blocking thyroid hormone synthesis. Carbimazole also suppresses the autoimmune process in thyroid in Grave's disease.
- Carbimazole causes fever, rashes, arthralgia, myalgia, neuritis, lymph node enlargement, liver cell dysfunction, psychosis, agranulocytosis.

b. Methimazole: Alike carbimazole. Dose is 5 to 20 mg daily. long acting, once a day dose.

c. Propyl thiouracil:

- It acts by blocking thyroid hormone synthesis as well as by blocking peripheral conversion of T_4 to T_3.
- It also decreases the thyroid autoantibody levels.
- It can be given for hyperthyroidism in children and in pregnancy, lactation.
- Dose is 200 mg 8th hourly.

PTU causes dose unrelated hepatoxicity; agranulocytosis; antineutrophilic cytoplasmic antibody in 20% of patients after long term usage.

Antithyroid drugs are continued during and after surgery, for 7-10 days. It has to be given after starting radioactive iodine therapy for 6 weeks to 12 weeks.

Response to treatment and possibility of relapse in primary thyrotoxicosis can be assessed by studying HLA status and TsAb level.

d. Propranolol:

- It is a beta blocker, which is used as an antithyroid drug.
- Dose is 40 mg tid.
- It reduces the cardiac problems and also blocks the peripheral conversion of T_4 to T_3, as it is the T_3 which is the principle active agent in periphery.
- Contraindications are bronchial asthma, heart block, cardiac failure.
- Long acting nadolol 160 mg OD can also be used.

e. Lugol's iodine (5% iodine + 10% potassium iodide):
It decreases the vascularity of the gland and makes it more firm and easier to handle during surgery. Dose is 10-30 drops/day (minims) for 10 days prior to surgery. Potassium iodide tablets 60 mg tid also can be given instead of Lugol's iodine. But its use at present is disqualified.
(One minim = one drop. One ml = 16 drops).

Note:

Lugol's iodine prevents the release of hormone from the gland – **thyroid constipation**. After 2 weeks, effect of Lugol's iodine is lost causing thyroid escape from iodine control.

f. Block and replacement therapy:

It is giving high dose of carbimazole to inhibit T_3 and T_4 production compeltely with a maintenance dose of 0.1 mg of L thyroxine. It reduces the iatrogenic thyroid insufficiency.

g. High dose of glucocorticoids impair peripheral conversion of T_4 to T_3 and also lowers serum TSH level; hence can be used in severe resistant/refractory cases.

Advantages of Antithyroid Drugs

1. Avoids surgery and its complications.
2. Avoids radioiodine therapy.

Clinical improvement occurs in 2 weeks. Biochemical improvement occurs in 6 weeks.

Remission is confirmed by TsAb assessment, which will be low.

Permanent remission rate is very less in adults and is 20% in children.

Disadvantages

1. Prolonged course of treatment for 18 months, and in spite of this cannot predict the remission or relapse. Relapse rate is 40%. Large gland/severe disease/abnormal TSH receptor antibodies (TSH-RAbs) are likely to lead into high recurrence.
2. Size of swelling may not regress.
3. It may lead to *agranulocytosis and thrombocytopenia*, liver damage, hair loss (except propranolol).
   Sore throat is the earliest presentation of agranulocytosis. If it is so, drug is stopped, total count is done. If it is less, agranulocytosis is confirmed. High doses of injection benzyl penicillin 10-20 lac, 6th hourly, IV is started to prevent infection. If required, blood transfusion is done. Patient usually recovers by this. To control toxicity, Tab. Propranolol 40 mg tid is started. Rarely they need bone marrow transplantation.

Other Antithyroid Drugs which are not Commonly Used are:

- Potassium perchlorate inhibits iodide transport.
- Iopanoic acid 50 mg is used in severe unresponsive cases. . It inhibits peripheral conversion of T_4 to T_3.

- Lithium carbonate 300 mg 6th hourly.
- Guanethidine 40 mg orally 6th hourly.
- Reserpine 5 mg IM.
- Dexamethasone 2 mg orally 6th hourly. It inhibits peripheral conversion of T_4 to T_3. It is used in thyroid storm.
- 2 mg IV propranolol in thyroid storm.

2. SURGERY

Indications

- Failure of drug treatment in primary thyrotoxicosis in young patients
- Autonomous toxic nodule
- Nodular toxic goitre
- When malignancy cannot be ruled out
- Graves disease in children, Graves with nodules
- Need for antithyroid drugs for more than 2 years
- Large goitre, substernal/intrathoracic goitre
- Pressure symptoms, Graves ophthalmopathy
- Amiodarone induced thyrotoxicosis.

- Surgery done is *subtotal thyroidectomy*—Both lobes with isthmus are removed and a tissue equivalent to pulp of finger is retained at lower pole of the gland on both sides (5-8 grams).
- In autonomous nodule, *hemithyroidectomy* is done. Here entire lateral lobe with whole of isthmus is removed.
- It is now observed that *total thyroidectomy* may be a better option in Graves disease to achieve lowest relapse rate and successful stabilisation of thyroid ophthalmopathy as it clears the antigenic focus in thyroid completely.

Advantages

- Rapid and high cure rate.
- Problems of radioiodine therapy are avoided.
- Surgery provides tissue for biopsy, removes the occult malignant foci.
- Surgery is better option for ophthalmopathy due to thyrotoxicosis.
- It is the option for women planning for child.
- Coexisting parathyroid carcinoma can be removed.
- For intrathoracic retrosternal toxic thyroid, surgery is the choice. Antithyroid drugs and also radioactive iodine may increase the goitre size.

Patient should be made euthyroid before doing surgery. (It should be confirmed by repeated estimation of serum T_3, T_4 and TSH levels).

Disadvantages

- Recurrent thyrotoxicosis (5%).
- Thyroid insufficiency (20-45%). It is revealed in 6 months to 2 years and is confirmed by estimating T_3, T_4 and TSH levels. Hypothyroidism is better than recurrent thyrotoxicosis. It is treated by tab. L-thyroxine 0.1 mg daily (OD) for life-long.
- Complications of thyroid surgery itself.

3. RADIOIODINE THERAPY

Indications

- Primary thyrotoxicosis after 45 years of age
- In autonomous toxic nodule
- In recurrent thyrotoxicosis

- Radioiodine destroys the cells and causes the complete ablation of thyroid gland. It is given only after the age of 45 years, as the chances of genetic mutation (damage), leukaemia, carcinomas are high in younger individual.
- *Usual dose is 5 to 10 millicurie, or 160 microcurie/gm of thyroid.*
- Patient is made euthyroid using antithyroid drugs; drug is discontinued for 5 days; I^{131} 300-600 MBq is given orally; antithyroid drugs are started after 7 days and are continued for 8 weeks. In 30% of patients additional 2 or 3 doses may be required.

Choice of therapies

	Condition	***Age***	***Treatment***
1.	*Diffuse toxic goitre*:		
	a. Small goitre	Over 45 years	Antithyroid drugs for 18 months
	b. Large goitre	Under 45 years	Radioiodine therapy Surgery (*Subtotal thyroidectomy*)
2.	*Toxic nodular goitre*		Surgery (Subtotal thyroidectomy)
			Initially antithyroid drugs are given to make the patient euthyroid before surgery
3.	*Toxic solitary nodule*	Over 45 years	Radioiodine
		Under 45 years	Surgery (Hemithyroidectomy)
4.	*Recurrent thyrotoxicosis after surgery*	Under 45 years	Antithyroid drugs
		Over 45 years	Radioiodine therapy
5.	*Failure of antithyroid drugs or radioiodine therapy*		Surgery

Don't spend a dollars' worth of time for ten cents worth of results.

- It takes 3 months to get full response and so until then, the patient has to take antithyroid drugs. Often additional one or two doses of radioiodine are required to have complete ablation. Eventually they go for hypothyroidism and so require maintenance dose of L-thyroxine 0.1 mg daily.
- To give therapeutic dose, patient should be admitted and isolated for 7 days (Half life) to prevent irradiation. It is given orally soon after getting from the manufacturer without much delay to have optimal efficacy.

Advantages

1. No surgery.
2. No prolonged drug therapy.
3. Cure rate 90%.

Disadvantages

1. Availability of facilities.
2. Proper follow-up is essential.

TOXIC THYROID IN PREGNANCY

- *Radioiodine therapy is absolutely contraindicated* in pregnancy (High-risk to foetus).
- Antithyroid drugs can be administered carefully.
- But, the problem here is that both TSH and antithyroid drugs cross the placental barrier and baby born may be hypothyroid and goitrous.
- Propylthiouracil is preferred in pregnancy.
- Subtotal thyroidectomy can be done in second trimester.

TOXIC THYROID IN CHILDREN

- Radioiodine therapy is *absolutely contraindicated* in children because of the high-risk of developing thyroid carcinoma.
- Recurrence rate is also very high after surgery.
- So proposed treatment is, initially antithyroid drugs are given until adolescent period and then subtotal thyroidectomy is done.

THYROCARDIAC

Severe cardiac damage (partly or wholly) resulting from hyperthyroidism, usually secondary type, requires proper opinion from cardiologists and treatment with propranolol. Subtotal thyroidectomy is the treatment.

IN A PATIENT WITH THYROTOXICOSIS, WITH RECENT ONSET OF PROPTOSIS

Early thyroidectomy has to be avoided, because early surgery may precipitate malignant exophthalmos. Here the patient has to be treated initially with antithyroid drugs and if required with steroids, until the proptosis has remained static for six months. Then subtotal thyroidectomy is done.

Since half-life of L-thyroxine is 7 days, propranolol and antithyroid drugs has to be continued for 7 days after thyroidectomy.

T$_3$ Thyrotoxicosis should be suspected if the clinical picture is suggestive of toxicosis, but routine tests for thyroid function are within normal range.

RADIOACTIVE IODINE

It is used both as a diagnostic as well as a therapeutic agent.

1. **I^{131}**—*is used for radioactive iodine therapy* (β-rays are used).
2. **I^{123}**—*is used for diagnostic studies* (γ-rays are used).

For diagnostic purpose I^{123} is given orally in empty stomach on previous day *(dose—5 micro curie; $T_{1/2}$ (half life) of I^{123} is 13 hours* and so it is suitable for diagnostic purpose). Patient should not take L-thyroxine for 6 weeks prior to radioisotope study.

Note:
If patient is on T$_3$ (60 μg/day) medication, the drug is stopped 10 days before radioisotope scan.

Injection TRH, if given, radioisotope scan can be done in 24 hours.

Thyroid treats this I^{123} similar to inorganic I^{127}. This I^{123} enters the thyroid from the circulation and gets incorporated into T$_3$, T$_4$ and later released into circulation as protein bound iodide (PBI). *Normal value of PBI is 8 μgm%.*

Using *Gieger Muller's gamma ray counter,* scanning of thyroid gland is done to visualize the gland.

- *Hot* area suggests more uptake,
- *Warm* area suggests normal uptake,
- *Cold* area suggests no uptake.

I^{123} radioisotope can be safely used in children and pregnancy for diagnostic purpose only (5 microcurie) as the dose is low.

Note:

- Presently I^{131} is also becoming popular as a diagnostic tool. For treating malignancy β-rays are more used than γ-rays.
- Technetium 99 scan is used for diagnostic purpose at present as it is effective and faster (in 20 minutes). IV administration is used.

Indications for diagnostic radioactive iodine study

- Doubtful toxicity
- Ectopic thyroid
- Autonomous toxic nodule
- After total thyroidectomy, to look for secondaries in follicular carcinoma thyroid
- Retrosternal thyroid

Radioisotope study is done to look for secondaries by doing whole body scanning (total body scintygraphy). For diagnostic radioactive study Technetium 99 pertechnetate can also be used.

Therapeutic Uses

1. In primary thyrotoxicosis after 45 years.
2. In autonomous toxic nodule after 45 years, it is useful as remaining gland still will function adequately after radiotherapy (As during radiotherapy radioisotope will not be taken up by this retained normal gland as it is suppressed in the presence of toxic nodule which will function later adequately).
3. In follicular carcinoma of thyroid, after total thyroidectomy, if there are secondaries elsewhere in the body, as in bones

or lungs, then radioiodine therapy is given. I^{131} is given as its half-life is 8 days. Patient should be isolated for this period and careful disposal of urine has to be done during this period. It is given orally in a dose of 5 millicuries (160 microcurie/gm of thyroid).

Problems in Radioactive Iodine Therapy

- Permanent thyroid failure with hypothyroidism.
- Genetic damage, leukaemia, damage to foetus.
- Effects will be seen only after 3 months.
- Ophthalmopathy and dermopathy will be worsened.
- There is risk of malignant transformation of thyroid.
- It may induce hyperparathyroidism.

Dose of radioactive iodine

Diagnostic	***Therapeutic***
• For thyroid-5-50 microcurie	• Residual thyroid ablation—50 mCi
• For whole body iodine scan 5-10 millicurie in 72 hours	• Bone secondaries from FCT—100-120 mCi
	• Lung secondaries from FCT—180 mCi

Contraindications for Radioactive Iodine Therapy

- Pregnancy/females desiring to have pregnancy within 1 year/lactating mothers.
- Children/adolescents.

Radioactive isotopes used in thyroid

Isotopes	***Route of administration***	***Half life***	***Type of rays***
I^{123}	Oral	13 hr	γ rays
I^{125}	Oral	60 days	γ rays
I^{131}	Oral	8 days	β, γ rays
I^{132}	Oral	2.3 hr	
Tc 99 scan*	IV	6 hr	

* Used mainly for malignancy in thyroid itself. It is sensitive, convenient, low radiation exposure, inexpensive, with good images but nonspecific and not used for therapy.

Lithium is also used as isotope for diagnosis in thyroid diseases.

Technetium is better to identify nonfunctioning secondaries.

Note

- High dose of retinoic acid will make I^{131} to concentrate in tumour cells (70 mg/daily for 2 weeks)
- Fertility should be avoided for 1 year after I^{131} therapy
- Avoid contrast CT in thyroid diseases as much as possible because I^{131} study in later period will be difficult
- MRI is ideal when radioiodine therapy is needed

THYROID NEOPLASMS

A. *Benign*

a. Follicular adenoma—colloid, embryonal, fetal.

b. Hurthle cell adenoma.

Colloid adenoma (commonest adenoma).

Papillary adenoma—its existence is doubtful. It is invariably low-grade papillary carcinoma.

B. *Malignant* *(Dunhill classification).*

a. *Differentiated—80%*

1. Papillary carcinoma (60%).
2. Follicular carcinoma (17%).
3. Papillofollicular carcinoma behaves like papillary carcinoma of thyroid.
4. Hurthle cell carcinoma behaves like follicular carcinoma.

b. *Undifferentiated—20%*

Anaplastic carcinoma (13%).

c. *Medullary carcinoma* (6%).

d. *Malignant lymphoma* (4%)

e. *Secondaries* in thyroid (rare)—from colon, kidney, melanoma, breast.

Annual incidence of thyroid cancers is 3.7 per 1,00,000 population. It is common in females (3:1).

Papillary carcinoma mainly spreads through lymphatics; follicular through blood; anaplastic through lymphatics and blood.

Aetiology of Thyroid Malignancy

1. Radiation either external or radioiodine can cause papillary carcinoma thyroid. There is increased incidence of thyroid carcinoma among children following exposure to ionising radiation after the *Chernobyl nuclear disaster* in Ukraine in 1986.

   Earlier irradiation was practised to head and neck region to treat benign conditions like tonsillitis, adenoids, thymus enlargement, acne vulgaris, haemangiomas during first two decades of life. As a consequence papillary carcinoma of thyroid became common in these individuals. Radiotherapy received in adolescent period for Hodgkin's lymphoma may predispose to papillary carcinoma.
2. Pre-existing multinodular goitre. It turns into follicular carcinoma of thyroid.
3. Medullary carcinoma thyroid is often familial.
4. Hashimoto's thyroiditis may predispose to NHL/papillary carcinoma of thyroid.
5. Familial.
6. Elevated TSH is observed in papillary carcinoma of thyroid.
7. Genetic—*Cowden syndrome* is differentiated thyroid carcinoma, carcinoma breast, multiple hamartomas. It is due to germ cell mutation of *PTEN tumour suppressor gene*. Oncogenes—C myc, C erb, , C fos, Ras are associated thyroid neoplasms.

DIFFERENTIATED THYROID CARCINOMA (DTC)

- DTC is a spectrum of disease derived from follicular cells. Both papillary and follicular carcinomas are grouped under

Happiness is always an inside job.

this. 90% of thyroid malignancies are differentiated one. Papillary, follicular and Hurthle cell carcinomas are DTCs.

- AGES (Mayo Clinic, Hay); AMES (Lahey Clinic); MACIS; *Sloan Kettering* scoring—are different scoring systems used for DTCs. Sloan Kettering scoring includes low, intermediate and high risk groups. First three scoring systems have low and high risk groups.
- Papillary carcinoma spreads to lymph nodes; follicular carcinoma through blood. FCT causes pulsatile vascular secondaries.
- Incidence of thyrotoxicosis in DTCs is 2%.
- Galectin—3, RET/PTC rearrangements, CD44 are the probable tumour markers under evaluation.
- *TNM staging for DTCs are*: Tx—primary tumour size unknown; T1—< 2 cm; T2—2-4 cm; T3—> 4 cm limited to thyroid or only minimally extrathyroid extension (to sternothyroid soft tissue); T4a—invasion to subcutaneous tissue, larynx, trachea, oesophagus and recurrent laryngeal nerve; T4b—invasion to prevertebral fascia, carotid encasement. N0—no nodes; N1a—spread to level VI (pre/paratracheal, prellaryngeal); N1b—neck nodal spread same or opposite or both sides and superior mediastinal nodes. M0—no distant spread; M1—distant spread present. *Age* is included in staging.

Postoperative AJCC staging for DTCs for predicting risk of death

Age less than 45 years

Stage I – Ant T, any N, M0; Stage II – any T, any N, M1.

Age after 45 years

Stage I – T1, N0, M0; Stage II – T2, N0,M0;
Stage III – T3,N0,M0 or T1,N1a,N0; T2,N1a, M0; T3,N1a,M0
Stage IVA – T4a,N0,M0; T4a, N1a, M0; T1,N1b,M0; T2,N1b,M0; T3,N1b,M0; T4a,N1b,M0
Stage IVB – T4b, any N; M0
Stage IVC – Any T, any N, M1

American Thyroid Association for predicting the risk of recurrence

Low risk—90% of patients

- Microscopic tumour clearance
- No spread to node/blood
- No capsular/vascular invasion
- Extrathyroid I_{131} uptake is not found
- 25 year mortality is 2%

Intermediate risk

- Microscopic perithyroid invasion
- Vascular invasion

High risk

- Incomplete tumour removal
- Macroscopic invasion
- Distant spread
- Extrathyroid bed I131 uptake present
- 25 years mortality is 46%

- Total/near total thyroidectomy, central compartment dissection ± MRND, suppressive L-thyroxine radioactive iodine therapies are different modalities of treatment.
- They usually carry good prognosis.



Figs 6.42A and B: (A) Fungating follicular carcinoma thyroid in a female. (B) Pulsatile vascular skull secondaries from FCT in a male patient.

- Tall/columnar cell, trabecular, scirrhous, solid types of papillary carcinoma; oxyphilic, insular types of FCT carry poor prognosis.

PAPILLARY CARCINOMA OF THYROID (PCT)

- It is 60% common.
- Common in females and younger age group.

Aetiology

- Radiation either external or radioactive iodine therapy.

TSH levels in the blood of these patients are high and so it is called as *hormone dependent tumour.*



Fig. 6.43: Papillary carcinoma of thyroid with nodal infiltration—diagrammatic representation.

Woolner Classification

Types

i. Occult primary (< 1.5 cm).
ii. Intrathyroidal.
iii. Extrathyroidal.

Micropapillary carcinoma is a tumour, clinically not detectable or less than 1 cm.

- *Encapsulated variant of papillary carcinoma,* like adenoma shows capsule with local invasion, commonly nodal spread; it often mimics hyperplastic nodule; but this type carries good prognosis.
- *Diffuse sclerosing variant* is seen in children which is very aggressive type with lymphocytic infiltration; it shows near 100% nodal spread; it carries poor prognosis.
- *Encapsulated papillary variant* and follicular carcinoma may be found together as *papillofollicular (Lindsay tumour)*; it behaves like papillary carcinoma with good prognosis.

Gross

It can be soft, firm, hard, cystic. It can be solitary or multinodular. It contains brownish black fluid.

Microscopy

- It shows cystic spaces, papillary projections with *psammoma* bodies, malignant cells with '*Orphan Annie eye'* nuclei (intranuclear cytoplasmic inclusions).
- *Orphan Annie eye nuclei* are identified in histology (paraffin section of formalin tissue). It is not seen in FNAC. Orphan Annie is strip cartoon character with empty circled eyes.
- Tall cell type of papillary carcinoma (10% of papillary carcinomas) is very aggressive type seen in elderly, 30% show capsular and vascular invasion, with 25-30% 5 year survival rate.
- Columnar type is seen only in males with near 100% mortality in 5 years.

Spread

- It is a slowly progressive and less aggressive tumour.
- It is commonly multicentric.
- It spreads within the gland through intrathyroidal lymphatics to other lobe, comes out of the capsule and spreads to cervical lymph nodes.
- Usually there is no blood spread. Extrathyroidal disease—invasion into thyroid capsule can cause blood born secondaries occasionally.



Fig. 6.44: Papillary carcinoma thyroid, operated specimen.

Clinical Features

- Soft or hard or firm, solid or cystic, solitary or multinodular thyroid swelling.
- Compression features are uncommon in papillary carcinoma thyroid.
- Often discrete lymph nodes in the neck (40%) are palpable.
- May present with secondaries in neck lymph nodes with occult primary.

Diagnosis

- *FNAC* of thyroid nodule and lymph node.
- Radioisotope scan shows cold nodule.
- TSH level in the blood is higher.
- Plain X-ray neck shows fine calcification whereas nodular goitre shows coarse—ring/rim calcification.
- U/S neck or CT scan neck (better) to identify non- palpable nodes in neck.



Fig. 6.45: FNAC of thyroid *(Courtesy:* Dr Krishna Upadhya Pathologist, Nandikoor Laboratory, Mangalore).

Treatment

- *Total or near total thyroidectomy*, with central node compartment dissection (level VI).
- *Suppressive dose* of L-thyroxine 0.3 mg OD life long. TSH level should be < 0.1 m U/L.
- *MRND (modified radical neck dissection)* type III (functional neck dissection), is required if lymph nodes are involved.
- Occasionally if small lymph nodes are present, '*Berry picking'* may be done (universally not accepted). (Not done now).
- Present concept is extrathyroidal type also responds well to radioactive I^{131} therapy.

***Note*:**

- If tumour is < 1.0 cm, solitary, low grade, probably unicentric, hemithyroidectomy is done with proper follow up at regular intervals.
- Suppressive dose of L-thyroxine can cause osteoporosis and so often needs calcium and Vitamin D supplementation.

Prognosis

Prognosis is good and it is one of the curable malignancies.

AMES scoring
A : Age. Age less than 40 years has got better prognosis
M : Distant metastasis
E : Extent of the primary tumour
S : Size of the tumour. Size less than 4 cm has got better prognosis

AGES scoring
A : Age less than 40 years has got better prognosis
G : Pathologic grade of the tumour
E : Extent of the primary tumour
S : Size of the primary tumour. Size less than 4 cm has got better prognosis

Note:

- Lymph node status does not alter the prognosis of papillary carcinoma of thyroid.
- MACIS scoring system is metastases, age, and completeness of excision, invasion, and size.
- All scoring systems categorise the patients as *high risk* for death—40% in 20 years; low risk for death—1% in 20 years. 80% of patients are in low risk for death. Low death risk is achieved by complete clearance of macroscopic tumour without any possible retaining of the disease during first surgery.
- *Follow-up:* Regular estimation of TSH levels, helps to monitor recurrence.

Psammoma bodies are seen in:

- Papillary carcinoma thyroid
- Meningioma
- Serous cystadenoma of ovary

Berry's in thyroid

- Berry ligament
- Berry sign
- Berry picking

Thyroid paradox: *Cellular tumours are soft, and cystic tumours are firm or hard (tensely cystic). It is observed in papillary carcinoma of thyroid.*

Role of ultrasound (U/S) in thyroid diseases

- To detect number, size, nature of the nodules (cystic/solid/complex) (complex means cystic and solid together—more suspicious of carcinoma). Size up to 2 mm can be detected
- U/S guided FNAC is very useful
- U/S at regular intervals is advisable to observe a small nodule in thyroid
- To detect recurrent nodule
- To find out the invasion/spread/vascularity/status of carotid artery and internal jugular vein
- To find out enlarged lymph nodes in neck

Role of FNAC in thyroid swelling

- Highly sensitive in papillary carcinoma of thyroid and also its nodal spread
- Useful to differentiate between benign and malignant
- Should be done in all thyroid diseases especially when there is a nodule or multiple nodules
- Useful in lymphoma/anaplastic carcinoma/medullary carcinoma thyroid/Hashimotos thyroiditis
- It is not very useful in follicular carcinoma as it is difficult to differentiate it from follicular adenoma as main feature in follicular carcinoma is capsular invasion/vascular invasion which are not made out in FNAC

FOLLICULAR CARCINOMA OF THYROID (FCT)

- It is 17% common.
- It is common in females.
- It can occur either *de novo* or in a pre-existing multinodular goitre.
- Thyroglobulin immunostaining is positive.

Types

a. Noninvasive—blood spread not common.

b. Invasive—blood spread common.
Typical features: Capsular invasion and angioinvasion.



Fig. 6.46: Total thyroidectomy specimen—done for carcinoma thyroid.

Spread

- It is a more aggressive tumour.
- It spreads mainly through blood into the bones, lungs, liver.
- Bone secondaries are typically vascular, warm, pulsatile, localised, commonly in *skull,* long bones, ribs.
- It can also spread to lymph nodes in the neck occasionally (10%).

Clinical Features

1. Swelling in the neck, firm or hard and nodular.
2. Tracheal compression/*infiltration* and stridor.
3. Dyspnoea, haemoptysis, chest pain when there are lung secondaries.
4. Recurrent laryngeal nerve involvement causes hoarseness of voice, +ve '*Berry's sign'* signifies advanced malignancy (infiltration into the carotid sheath and so absence of carotid pulsation).
5. Pulsatile secondaries in the skull and long bones.

Investigations

- Most often FNAC is inconclusive, because capsular and angioinvasion, which are the main features in follicular carcinoma, cannot be detected by FNAC.
- Frozen section biopsy was said to be useful earlier; but it is questionable now. In 15% cases frozen section biopsy may be inconclusive or facility for frozen section biopsy may not be available in many places, then initial hemithyroidectomy is done.
- U/S abdomen, chest X-ray, X-ray bones are the other investigations required.
- *Trucut biopsy* gives tissue diagnosis, but danger of haemorrhage and injury to vital structures like trachea, recurrent laryngeal nerve, vessels are likely. It may be useful in lymphoma and anaplastic carcinoma; but it is *not very well accepted.*

Treatment

- *Total thyroidectomy is done* along with central node compartment dissection (level VI).
- *Functional neck node dissection* is done with preservation of sternocleidomastoid, spinal accessory nerve and IJV if nodes are present clinically or by imaging, FNAC shows positive node, and on table frozen section biopsy of lymph node shows positive for tumour.
- Maintenance dose of L-thyroxine 0.1 mg OD or T_3 80 μg/day is given lifelong. Immediate thyroxin supplementation is often not started following surgery to keep TSH level raised



Figs 6.47A and B: Thyroid swelling which is highly vascular and malignant in two different patients (male and female).

Voice can say both: What you have done and what you would not have done also !!



Fig. 6.48: Secondaries in the skull in a patient who underwent thyroidectomy earlier for follicular carcinoma thyroid.



Fig. 6.49: Secondaries in the skull from thyroid primary. Note well-localised, warm, pulsatile, vascular tumour with underlying bone erosion. It is common in flat bone like skull/ribs/sternum/scapula. Most common in frontoparietal part of skull.

so that all extrathyroidal tissues that takes up iodine will also take up radioiodine to achieve optimum radioablation. TSH level should be more than 30 mIU/L for this.

- *On table frozen section biopsy* is useful in negative FNAC but doubtful cases. Definitive procedure is undertaken once frozen section report comes on table. But in frozen section biopsy itself, 15% of follicular carcinoma report may be inconclusive or negative which causes difficulty in taking decision. In such occasion hemithyroidectomy is done and once histology report of follicular carcinoma is obtained completion thyroidectomy is done usually immediately within a week. If biopsy report is delayed then completion thyroidectomy is done after 6-12 weeks.

Follow-up

- It is by radioisotope I^{123} scan done at regular intervals (6 months) to look for secondaries.



Fig. 6.50: CT skull showing secondaries from follicular carcinoma thyroid.



Fig. 6.51: X-ray skull showing secondaries with lytic lesions from follicular carcinoma of thyroid as primary.

- ***Thyroglobulin estimation*** is a good follow-up method to decide for Radioisotope study. Normal value (0.5-50 μg/L). TG > 50 μg/L is abnormal. It should be done once in 3-6 months. Its raise signifies recurrent/metastatic disease. Serum thyroglobulin level estimation is of no value in preoperative assessment. After thyroidectomy thyroglobulin secretion is stopped, hence its level should not be traceable after total thyroidectomy.
- U/S neck or MRI neck to identify early relapse. MRI neck is better.

Further Treatment

- If secondaries are detected *therapeutic dose* Ra I^{131} is given orally. L-thyroxin has to be stopped 6 weeks prior to RT, then required dose of Ra I^{131} is given (50-150 m curie).
- Radio remnant ablation (RRA)
    - Initially thyroid radioisotope scan is done. If patient is on 300 μg suppressive dose of L-thyroxine, it should



Fig. 6.52: Follicular carcinoma of thyroid in a male patient. It involved mainly left lobe but it is extensive and spreading to soft tissues adjacent to it.

be stopped for 3-6 weeks so as to achieve serum TSH level above 30 M IU/l or two intramuscular injections of 0.9 mg of recombinant human TSH is given.

  - If iodine isotope scan detects remnant disease, then 30-100 mCi of radio ablation dose of I_{131} is given orally. RR will destroy occult microscopic disease. Post-ablation isotope scanning is done in 8 days. Later in intermediate and high risk patients, follow up body scan is done once in 6 months. Serum thyroglobulin estimation is done for 6-12 months, later once in 6 months; neck US at 6, 12 months and annually for 5 years. Raise in thyroglobulin level indicates for further whole body isotope scan. To detect metastases radioisotope I_{131} 100-200 mCi is given and 250-300 mCi is given for bone.
  - *Prior to radioactive iodine therapy following precautions* should be taken—low iodine diet for 10 days; isolation when dose is more than 30 mCi; increase intake of oral fluid to maintain high urine output to avoid radio iodine induced bladder injury; sucking of lemon to avoid sialadenitis; laxatives; reduced sperm count for 6-8 months; pregnancy should be avoided for 6-12 months.
- Secondaries in bone are treated by *external radiotherapy.* Internal fixation should be done whenever there is pathological fracture.
- There is *no role* of chemotherapy for follicular carcinoma thyroid.

Hurthle Cell Carcinoma

Hurthle cell carcinoma is a variant of follicular carcinoma of thyroid which contains *abundant oxyphill cells*. It spreads more commonly to regional lymph nodes than follicular carcinoma of thyroid.

Note:

- Hurthle cell carcinoma does not take up I^{131}
- It secretes thyroglobulin
- It has got poorer prognosis than follicular cell carcinoma
- 30% multicentric
- *99mTc sestamibi scan* is very useful for Hurthle cell carcinoma
- Regional nodes are commonly involved than follicular carcinoma
- 20% show distant spread
- Abundant oxyphill cells (*Askanazy*) are specific
- Total thyroidectomy, MRND and TSH suppression is the treatment

Central Node Compartment Neck Dissection

It is removal of paratracheal, tracheooesophageal, pretracheal and prelaryngeal nodes along with thymus and thyroid enbloc *extending* from hyoid bone above, brachiocephalic vein below, carotids on both sides.

Completion Thyroidectomy

- It is done after hemithyroidectomy if histology confirms as differentiated thyroid cancer, either papillary or follicular.
- It is indicated in—high-risk patients, age more than 45 years, family history, size more than 1 cm, opposite side thyroid nodule, nodal or distant spread, multifocal disease, extrathyroidal spread, capsular and vascular invasion.
- Reasons for completion total thyroidectomy are:
  - In differentiated thyroid cancer (for follicular carcinoma of thyroid) radioiodine I_{131} is the treatment for blood spread secondaries. It is only possible if entire thyroid gland is removed to make radioiodine to concentrate on tumour tissue to achieve needed efficacy.
  - In many indications papillary carcinoma of thyroid also needs radioablation like extrathyroid spread, size more than 4 cm etc.
  - During follow up, in DTCs/FCT thyroglobulin as tumour marker estimation at regular intervals (6 months; to suspect tumour bed recurrence/metastases) can be done if thyroid tissue is removed entirely.
  - Papillary carcinoma of thyroid are multicentric with intrathyroid spread and so completion thyroidectomy is better.
- Timing of completion thyroidectomy is within 7 days of first surgery or after 6-12 weeks to allow the settling of inflammatory response (dissection and to get surgical planes is difficult during this period).

ANAPLASTIC CARCINOMA OF THYROID

- It is an *undifferentiated* very aggressive carcinoma (1%) occurs in elderly females.

Only in advanced cases of hypothyroidism there is a substantial loss of hair.—**Richard A J Asher**

◆ It is a very aggressive tumour of short duration, presents with a swelling in thyroid region which is rapidly progressive causing:
  i. Stridor and hoarseness of voice due to tracheal obstruction.
  ii. Dysphagia.
  iii. Fixity to the skin.
  iv. *Positive Berry's sign*—involvement of carotid sheath leads to absence of carotid pulsation.

◆ Swelling is hard, with involvement of isthmus and lateral lobes.

◆ FNAC is diagnostic.

◆ Tracheostomy and isthmectomy has got a role to relieve respiratory obstruction temporarily.

◆ Treatment is *external radiotherapy*, as usually thyroidectomy is not possible.

◆ Adriamycin as chemotherapy.

◆ However prognosis is poor. Life span is counted in few weeks to months only.



Fig. 6.55: Anaplastic carcinoma of thyroid.



Fig. 6.53: Carcinoma of thyroid gland. It is anaplastic carcinoma. It carries poor prognosis.



Fig. 6.56: Anaplastic carcinoma thyroid in a female patient.



Fig. 6.54: Anaplastic carcinoma of thyroid with infiltration through the capsule. It commonly encases the carotid artery causing Berry's sign positive.



Fig. 6.57: Anaplastic carcinoma thyroid, an aggressive tumour with poor prognosis.

Follow-up in differentiated thyroid carcinoma

- Proper clinical examination in the neck for residual/nodal disease and for distant spread
- Whole body radioisotope scan after one week of surgery to see residual tumour in the neck or metastases
- Estimation of thyroglobulin at regular intervals is very important—once in 6 months
- Follow up whole body radioisotope scan at 3-6 months intervals. Thyroxine should be stopped for 6 weeks. But it is commonly done if thyroglobulin level in the blood is significantly high

STAGE GROUPING FOR PAPILLARY OR FOLLICULAR THYROID CARCINOMA (DIFFERENTIATED THYROID CANCER)

Patients younger than 45 years:

Stage I: The tumour can be any size and may or may not have spread to nearby lymph nodes. It has not spread to distant sites.

Stage II: The tumour can be any size and may or may not have spread to nearby lymph nodes. It has spread to distant sites.

Patients 45 years and older:

Stage I: The tumour is less than 2 cm across; no lymph nodes/distant spread.

Stage II: The tumour is 2 to 4 cm across; no lymph nodes/distant spread.

Stage III: The tumour is larger than 4 cm or slightly outside the thyroid; no lymph nodes/distant spread. OR The tumour is any size and has spread to lymph nodes around the thyroid in the neck (cervical nodes) but not to distant sites.

Stage IVA: The tumour is any size and has grown beyond the thyroid gland to invade nearby tissues of the neck. Cervical nodes ± but no distant spread. OR The tumour is any size and may have grown outside of the thyroid gland. It has spread to lymph nodes in the side of the neck (lateral cervical nodes) or upper chest (upper mediastinal nodes) but not to distant sites.

Stage IVB: The tumour is any size and has grown either back to the spine or into nearby large blood vessels. Nearby lymph nodes ± but no distant spread.

Stage IVC: The tumour is any size and may or may not have grown outside the thyroid. It may or may not have spread to nearby lymph nodes. It has spread to distant sites.

Stage grouping for medullary thyroid carcinoma

It is same as of differentiated thyroid cancer older than 45 years.

Stage grouping for anaplastic/undifferentiated thyroid carcinoma

All anaplastic thyroid cancers are considered ***stage IV***

Stage IVA: Tumour is still within the thyroid and may be *resectable* (removable by surgery). Nearby lymph nodes ± but no distant spread.

Stage IVB: Tumour has grown outside of the thyroid and is *not resectable*. Nearby lymph nodes ± but no distant spread.

Stage IVC: The tumour is any size and may or may not have grown outside of the thyroid. Nearby lymph nodes ± but distant spread *always present*.

Features of thyroid carcinoma

Any thyroid can be malignant of any size, of any texture—solid/cystic, of any number—single/multiple, in any age group.

Features of infiltration

- Infiltration of strap muscles often with sternomastoid muscle
- Infiltration of laryngotracheal complex causing stridor and often haemoptysis
- Infiltration of recurrent laryngeal nerve causes hoarseness of voice
- Infiltration of oesophagus causes dysphagia/ odynophagia (painful swallowing)
- Infiltration into carotid sheath causing absence of carotid pulsation—*Berry's sign*
- Infiltration of cervical sympathetic chain causing Horner's syndrome
- Rarely infiltration into cranial nerves or brachial plexus can occur

Features of lymph nodal spread

- Discrete neck node involvement can occur commonly in papillary carcinoma of thyroid, often in medullary carcinoma and occasionally in follicular carcinoma. Lymph node is often cystic (20%) and contains brownish— black material in papillary carcinoma
- Central neck (level VI) and mediastinal nodes often gets involved in thyroid malignancy. Primary nodes may be involved but clinically may not be palpable. Superior mediastinal nodes (level VII) can cause compression of SVC, recurrent laryngeal nerve with often dullness on percussion over the sternum. These nodes can get involved without palpable neck nodes
- In the neck commonly palpable nodes are levels—II, III, IV and occasionally level V. Secondary nodes—clinically palpable
- Only palpable neck node may be the presentation without clinically palpable thyroid—occult secondary with primary (papillary) thyroid carcinoma. FNAC of the node concludes the diagnosis
- Central node dissection is the common practice while doing total thyroidectomy in carcinoma thyroid especially in medullary carcinoma of thyroid

Features of blood spread

- Follicular carcinoma commonly spreads through blood to bone, lungs, and liver. Bone secondary is typical. It is well-localised, smooth, soft/hard, warm, nonmobile, vascular and pulsatile. It is common in the skull bone—frontal/parietal bone. It can occur in other bones also
- Lung secondaries present with chest pain, dyspnoea and haemoptysis
- Liver secondaries cause hepatomegaly and jaundice
- Blood spread also can occur in medullary carcinoma of thyroid

MEDULLARY CARCINOMA OF THYROID (MCT)

- It is uncommon (5%) type of thyroid malignancy.
- It arises from the *parafollicular 'C' cells* which is derived from the ultimobranchial body (neural crest). C cells are more in upper pole of the thyroid gland.
- It contains characteristic '*amyloid stroma'* wherein malignant cells are dispersed. Immunohistochemistry reveals calcitonin in amyloid.
- In these patients blood levels of *calcitonin* both basal as well as that following calcium or pentagastrin stimulation is high, a very useful tumour marker.
- Tumour also secretes 5-HT (serotonin), prostaglandin, ACTH and vasoactive intestinal polypeptide (VIP).
- It spreads mainly to lymph nodes (60%).



Fig. 6.58: Note the parafollicular cells. Cell of origin of medullary carcinoma thyroid.

- It may be associated with MEN II syndrome and pheochromocytoma with hypertension. MCT associated with MEN type II B with phaeochromocytoma (Sipple's disease) is most aggressive.
- There may be mucosal neuromas in lips, oral cavity, tongue, eyelids with marfanoid features.
- MCT is not TSH dependent and does not take up radioactive iodine.

Clinical Features

- Thyroid swelling often with enlargement of neck lymph node.
- Diarrhoea, flushing (30%).
- Hypertension, phaeochromocytomas and mucosal neuromas when associated with MEN II syndrome.
- Sporadic and familial types occur in adulthood whereas cases associated with MEN syndrome II occur in younger age groups.
- Paraneoplastic syndrome like Cushing's and carcinoids.

Note:
Consider MCT in thyroid swelling with significant diarrhoea and hypertension.

Types

1. Sporadic. Usually solitary—70%.
2. MCT with MEN II syndrome. It is more aggressive, bilateral, multifocal/multicentric, affects younger age group. MCT with MEN type IIb is most aggressive, often involves infants and children, with marfanoid features.
3. Familial MCT (20%). Commonly multicentric, autosomal dominant in chromosome no. 10. Familial non-MEN MCT is least malignant, occurs in 4th and 5th decades, shows extra and intracellular cysteine codon.

Investigations

- FNAC: shows amyloid deposition with dispersed malignant cells and "C" cell hyperplasia.
- Tumour marker: Calcitonin level will be higher. Unstimulated serum calcium more than 100 pg/ml is suggestive of MCT.
- Increased levels of calcitonin after injection of calcium 2 mg/kg or pentagastrin 0.5 µg/kg.

Note:
Calcitonin is undetectable in the serum of normal individuals (< 0.08 ng/L).

- U/S abdomen.
- U/S neck to see neck nodes. CT neck and chest is preferred method to identify neck and mediastinal nodes.
- Urinary VMA, urinary catecholamines, urinary metanephrine (24 hour estimation), serum calcium, serum parathormone estimation.
- 111 Indium octreotide scanning is useful in detecting medullary carcinoma thyroid (70% sensitivity). It is also useful in postoperative follow up to find out residual/metastatic disease.
- 50% of MCT shows rise in CEA.

Treatment

Surgery is the main therapeutic modality.

- *Total thyroidectomy with central node dissection* (level 6) in all patients even if there are no nodes in the neck + maintenance dose of L-thyroxin.
- Neck lymph nodes block dissection if lymph nodes are involved (bilateral modified radical dissection of neck nodes should include levels—II, III, IV, V and VI). Later regular U/S neck is done to detect early neck nodes.
- No role of suppressive hormone therapy or radioactive iodine therapy.
- External beam radiotherapy for residual tumour disease.
- Somatostatin/octreotide for diarrhoea.
- Adriamycin is the drug used as chemotherapy with limited results.
- If there is associated phaeochromocytoma it should be treated surgically by adrenalectomy first and later only total thyroidectomy is done.
- *All family members of the patient should be evaluated for serum calcitonin and if it is high they should undergo prophylactic total thyroidectomy* (Can also be assessed by genetic evaluation). If there is positive RET proto-oncogene in MCT

with MEN II A and familial MCT types, prophylactic total thyroidectomy is done at the age of ***5 years***. In positive RET proto-oncogene in MCT with MEN II B, prophylactic total thyroidectomy is done at the age of ***one year***.

- MCT with associated parathyroid hyperplasia (30%) in MEN IIA, total thyroidectomy with central nodal dissection with total parathyroidectomy and autotransplantation of half of gland in sternomastoid or nondominant forearm brachioradialis muscle is done.

Prognosis

- Sporadic MCT and MCT with MEN II are aggressive.
- Familial MCT not associated with MEN II has got better prognosis.

Calcitonin

- It is a polypeptide of 32 amino acids. It is derived from ultimobranchial body. It is secreted from C cells of thyroid (parafollicular cells).
- It lowers the plasma calcium and phosphorus levels. It blocks the PTH induced bone resorption. Calcium from the circulation is shunted into the bone. It increases the excretion of calcium, phosphorus, sodium and potassium. It rapidly lowers the serum calcium.
- Normally it is less than 0.08 ng/L (undetectable).
- It is increased in medullary carcinoma of thyroid. It is very good tumour marker for MCT. It confirms the relapse/metastases/residual disease. Increased levels in family members confirm the genetic relation and such relatives should undergo prophylactic total thyroidectomy.
- Calcitonin level will further increase after injection of calcium 2 mg/kg or pentagastrin 0.5 µg/kg.
- In disease free individual, after therapy for MCT calcitonin level decreases.
- Calcitonin as a therapeutic agent is used in hypercalcaemia, Paget's disease, bone pain of neoplastic diseases, menopausal osteoporosis. Calcitonin (pork), 4 units/kg is given SC or IM three times a week.
- Salmon calcitonin SC/IM/nasal spray—50-400 units can be given three times a week or daily depending on need.

MALIGNANT LYMPHOMA

- It is NHL type. Occurs in a pre-existing Hashimoto's thyroiditis (Not proved well).
- FNAC is useful to diagnose the condition (Often trucut biopsy).
- Chemotherapy and radiotherapy is the main treatment.
- Rarely total thyroidectomy is done to enhance the results.

Degroot's staging of carcinoma thyroid*

Stage 1: Malignancy is intrathyroidal
Stage 2: Malignancy is intrathyroidal with mobile lymph nodes
Stage 3: Malignancy is intrathyroidal with fixed lymph nodes
Stage 4: Distant metastasis

*This staging is applicable to all thyroid malignancy but mainly used in follicular carcinoma of thyroid

Differential diagnosis for carcinoma thyroid

- Multinodular goitre
- Solitary nodule of other causes
- Riedel's thyroiditis

HASHIMOTO'S THYROIDITIS (Struma Lymphomatosa)

- Also called as diffuse non-goitrous thyroiditis.
- It is an autoimmune thyroiditis—common in women (15 times more common).
- There is hyperplasia initially, then fibrosis, eventually infiltration with plasma cells and lymphocytic cells.
- *Askanazy cells* are typical (like Hurthle cells).
- The river Struma arises in Bulgaria and flows into Aegean Sea. Struma means goitre. Banks of this river are endemic area for goitre.

Features

- Painful, diffuse, enlargement of usually both lobes of thyroid which is firm, rubbery, tender and smooth (occasionally one lobe is involved).
- Initially they present with toxic features but later, they manifest with features of hypothyroidism.
  Hyperplasia → Hyperthyroid—*Hashitoxicosis*
  → Euthyroid.
  Fibrosis → Hypothyroid.
- There may be hepatosplenomegaly,
- It is often associated with other autoimmune diseases.
- In 85% cases significant rise in the thyroid antibodies (microsomal, thyroglobulin, or colloid antibodies) is observed.
- Often condition may be associated with or may predispose to *malignant lymphoma*. It is at present not well-proved.
- Common in perimenopausal females.
- Occasionally it can predispose to papillary carcinoma of thyroid also.

Investigations

FNAC, T_3, T_4, TSH. Thyroid antibodies assay. Usually ESR is very high (over 90 mm/hour).

Treatment

1. L-thyroxine therapy.
2. Steroid therapy often is helpful.
3. If goitre is large and causing discomfort, then subtotal thyroidectomy is done.

DE-QUERVAIN'S SUBACUTE GRANULOMATOUS THYROIDITIS

It is due to viral aetiology either mumps or coxsackie viruses causing inflammatory response with infiltration of lymphocytes, neutrophils, multinucleated giant cells.

You never get the second chance to make the first impression.

Features

- Painful diffuse, swelling in thyroid which is tender
- Commonly seen in females.
- Initially there is transient hyperthyroidism with high T_3 and T_4 but poor radioiodine uptake.
- FNAC is useful.
- It is usually a self limiting disease.
- Prednisolone 20 mg for 7 days helps.

RIEDEL'S THYROIDITIS (0.5% Common)

- A very rare benign entity wherein thyroid tissue is replaced by fibrous tissue which interestingly infiltrates the capsule into surrounding muscles, paratracheal tissues, carotid sheath.
- ('*Woody Thyroiditis*', '*Ligneus Thyroiditis*').
- It is often associated with retroperitoneal and mediastinal fibrosis and sclerosing cholangitis.
- There is both intrathyroidal as well as extrathyroidal fibrosis.
- It also encroaches parathyroids and recurrent laryngeal nerves.
- It may be unilateral or bilateral.

Clinical Features

- Swelling with *irregular* surface, *stony hard* consistency, stridor, with positive *Berry's* sign (absence/*impalpable* carotid pulsation); small goitre; common in males.

Differential Diagnosis

- Anaplastic carcinoma of thyroid.

Investigations

- T_3, T_4 may be low due to hypothyroidism.
- Radioisotope scan will not show any uptake.
- FNAC to rule out carcinoma.

Treatment

Isthmectomy is done to relieve compression on the airway. They require L-thyroxine replacement later, as hypothyroidism is common.

- High dose of steroid often used.
- Thyroidectomy is not necessary.

Causes of dyspnoea/stridor in thyroid diseases

- Carcinoma thyroid infiltrating recurrent laryngeal nerve/trachea
- Large, long standing goitre causing tracheomalacia
- Retrosternal goitre
- Congestive cardiac failure in thyrotoxicosis

Recent rapid increase in thyroid swelling is due to:

- Previous MNG undergoing malignant transformation
- Haemorrhage into a nodule
- Anaplastic carcinoma of thyroid

Remember

- *Goitre* is enlargement of the thyroid gland
- *Solitary nodule* is single palpable nodule on clinical examination without palpable rest of the gland
- *Dominant nodule* is single nodule with palpable enlargement of the remaining thyroid gland
- *Thyroid swelling* is confirmed by its *movement with deglutition* due to attachment of enclosed pretracheal fascia to inferior constrictor muscle which is attached to trachea and cricoid cartilage and so moves with deglutition
- *Berry's ligament* is condensed vascularised pretracheal fascia postero-supero-medially. It is important as it is close to recurrent laryngeal nerve
- Any thyroid swelling *can be malignant* unless proved otherwise
- U/S neck, FNAC, estimation of T3, T4, TSH are essential investigations
- CT scan neck is needed in large goitre and fixed or malignant thyroid
- Radioisotope study I^{123} is done only in selected cases like borderline toxicity, ectopic thyroid, retrosternal goitre and after thyroidectomy in follicular carcinoma thyroid to see secondaries during follow-up period
- Normal thyroid gland is usually not palpable
- A rare entity called as *black thyroid* shows lipofuscin deposition in thyroid in a patient who is on longstanding tetracycline therapy which may interfere with thyroid function

Occasions wherein thyroid swelling may not move upwards with deglutition

- Anaplastic carcinoma thyroid—often
- Carcinoma thyroid with extensive local infiltration into soft tissues, trachea/larynx and posterior muscles
- Intrathoracic retrosternal extension with infiltration/impaction
- Riedel's thyroiditis with encasement of trachea
- Massive thyroid wherein upward movement is difficult to observe and appreciate

Narrowing of trachea is seen in:

- Scabbard trachea in longstanding MNG
- Retrosternal goitre
- Carcinoma of thyroid
- Riedel's thyroiditis

THYROID INCIDENTALOMA

Clinically unsuspected and impalpable thyroid swelling which is identified while doing *imaging of head and neck for nonthyroid head and neck diseases is called as thyroid incidentaloma*. It is usually left alone with yearly review both clinically and sonologically. Such nodule is usually less than 1 cm.

THYROIDECTOMY

Types

1. *Hemithyroidectomy*: Along with removal of one lobe, entire isthmus is removed. It is done in benign diseases of only one lobe. It is also done in follicular neoplasm involving only one lobe. Solitary toxic or nontoxic nodule, thyroid cyst are other indications.
2. *Subtotal thyroidectomy* commonly done in toxic thyroid either primary or secondary and also often for nontoxic multinodular goitre. Here about 8 grams, or a tissue, size of pulp of finger is retained on lower pole, on both sides and rest of the thyroid gland is removed. It is also done in MNG.
3. *Partial thyroidectomy* (By Thomas) is removal of the gland in front of trachea after mobilisation. It is done in nontoxic multinodular goitre. Its role is controversial.
4. *Near total thyroidectomy*: Here both lobes except the lower pole (***one*** or both sides) which is very close to recurrent laryngeal nerve and parathyroid is removed (To retain blood supply to parathyroids). It is done in case of papillary carcinoma of thyroid. Here less than 2 grams of thyroid tissue is left behind near its lower pole *on one side usually opposite side of the diseased*, occasionally on both sides.
5. *Total thyroidectomy*: Entire gland is removed. It is done in case of follicular carcinoma of thyroid, medullary carcinoma of thyroid.
6. *Hartley Dunhill operation* is removal of one entire lateral lobe with isthmus and partial/subtotal removal of opposite lateral lobe. It is done in non-toxic multinodular goitre. 4 grams of tissue is left behind only on one side.

Preoperative preparation

- Blood grouping and cross matching. Keep the required blood ready
- Indirect laryngoscopy. Patient is asked to tell' E' to check the abduction of vocal cord
- Serum calcium estimation
- T_3, T_4, TSH
- Thyroid antibodies
- ECG and cardiac fitness especially in toxic goitre
- Lugol's iodine 10 days prior to surgery to make gland firm and less vascular.

Procedure

- *Position*:
  - Under general anaesthesia patient is put in supine position with neck hyperextended by placing a sand bag under shoulder—with table tilt of 15 degree head up to reduce venous congestion.
- *Incision*:
  - Horizontal crease incision is done, two finger breadth above the sternal notch, from one sternomastoid to the other (Kocher's thyroid incision) (Posterior margin of sternomastoid).
- *Procedure:*
  - Skin and platysma are incised (Subplatysmal plane)—upper flap raised up to thyroid cartilage, lower flap up to sternoclavicular joint. Deep fascia is opened vertically in the midline.



Fig. 6.59: Note the incision for thyroid surgery.



Fig. 6.60: *Hemithyroidectomy*: Entire one lateral lobe and entire isthmus are removed retaining entire opposite lateral lobe. It is done in solitary nodule/toxic or nontoxic adenoma in one lobe.


Part removed
Part retained
Sternomastoid muscle
Pulp of the finger or 4-8 gm thyroid in lower pole both sides

Fig. 6.61: *Subtotal thyroidectomy*—it is done in toxic/nontoxic multinodular goitre. Most of the gland except lower pole (4-8 gram) on both sides is removed.

Anything the mind of man can conceive and believe, it can achieve.


(Thyroid tissue in tracheo-oesophageal groove)
Part retained
Part removed
Part of both lateral lobes and entire isthmus
Sternomastoid muscle

Fig. 6.62: *Partial thyroidectomy*—it is done in nontoxic nodular goitre if there is adequate normal gland posteriorly. Tissue in the tracheo-oesophageal groove is retained. Isthmus and gland with nodules in front is removed. It is not commonly done now.


Except small tissue in lower pole near recurrent laryngeal nerve and parathyroids (one or both sides—1 g/1 cm)
(Both sides)
Part removed
Both lateral lobes and isthmus
Recurrent laryngeal nerve
Part retained
Parathyroid
Sternomastoid muscle

Fig. 6.63: *Near total thyroidectomy* is done in papillary carcinoma of thyroid. Here most of the gland except lower small tissue of 1 gram on one side usually is retained to safeguard recurrent laryngeal nerve and parathyroid gland. Tissue is retained either in one or both sides.


Part removed
Both lateral—lobes and isthmus
Sternomastoid muscle

Fig. 6.64: *Total thyroidectomy* is done for follicular carcinoma and medullary carcinoma of thyroid.


(One side partial—in tracheo-oesophageal groove)
Part removed
Isthmus, one entire lateral lobe and other side—partial/subtotal (4 grams retained)
Part retained
Sternomastoid muscle

Fig. 6.65: *Hartley Dunhill procedure:* Here one entire lateral lobe, isthmus, and most part of the opposite lateral lobe except small quantity of tissue in the lower pole/tracheo-oesophageal groove—subtotal/partial/one gram is retained.



Fig. 6.66: Skin flaps raised in thyroidectomy. Thyroid covered with pretracheal fascia is seen.

- *Strap muscles* are retracted; in large goitre they are often divided in upper part to retain their nerve supply *ansa cervicalis*. Often anterior jugular veins need to be ligated using 3 zero vicryl.
- *Pretracheal fascia* is opened vertically to expose thyroid gland. Short stout middle thyroid vein which enters the IJV is ligated immediately (first vessel to ligate; it is vein without accompanying artery) using vicryl or silk and divided. Avulsion of this vein from its junction to IJV will cause bleeding. Gland is mobilised medially using peanut dissection and bipolar cautery.
- *Superior pedicle* is dissected; artery and vein are individually ligated and divided. In olden days mass liga-



Fig. 6.67: Total thyroidectomy specimen done for follicular carcinoma of thyroid.



Fig. 6.68: Typical thyroidectomy postoperative scar.



Fig. 6.69: Note the relation of recurrent laryngeal nerve.

tion close to gland at superior pole was the practice. Chances of injuring external laryngeal nerve and AV fistula may happen in mass ligation. It is also always better to identify external laryngeal nerve entering the cricothyroid. Dissection is done in an avascular plane between cricothyroid and gland.

- *Parathyroids* both superior and inferior are identified. They are 6 × 4 × 2 mm in size weighing 50 mg with yellowish brown/orange brown colour. Superior (parathyroid IV) and inferior (parathyroid III) glands are identified and dissected. Both glands receive their blood supply from inferior thyroid artery and through an anastomotic branch. Superior parathyroid is *above and behind* the junction of RLN and inferior thyroid artery; inferior parathyroid is *below and in front* of this junction.
- *Recurrent laryngeal nerve* should be identified with careful dissection through its entire course. *Riddle's triangle* is between inferior thyroid artery above, carotid artery laterally trachea medially. From this area nerve runs upwards to enter the larynx at greater cornu of thyroid cartilage. Many branches of nerve and the variations should be remembered while dissecting here. One should not use monopolar cautery here; only bipolar cautery should be used carefully. Nerve usually crosses the inferior thyroid artery from deeper aspect; but variations are common. Posterior extension of lateral thyroid lobes close to Berry's ligament is called as *Zuckerkandl tubercle* which is seen in 40% of cases. Nerve runs upwards in a fissure between Zuckerkandl tubercle and trachea or main thyroid gland. *Nonrecurrent laryngeal nerve* (0.5%) is occasionally seen in right side due to failure of development of 4th aortic arch; it directly arises from vagus enters the larynx at the level of inferior horn of thyroid cartilage. Recurrent laryngeal nerve is in close contact with *suspensory ligament of Berry*.
- *Inferior thyroid artery* which is a branch of thyrocervical trunk ascends upwards reaching gland at its lower pole after turning towards midline behind the carotid artery. Here ligation is done at capsular level by identifying every small branch entering the gland (*capsular ligation of inferior thyroid artery*). This retains the blood supply of parathyroids which is very important. In olden days, ligation of inferior thyroid artery was done away from the gland often in continuation using absorbable suture material, is now no longer in practice.
- Mobilized gland is removed. *Critical points of recurrent laryngeal nerve injury* are—at the entry of inferior thyroid artery and crossing the nerve, at suspensory ligament of Berry, at lower pole of the gland.

Thyroid steal: In thyrotoxicosis, patient is taken to operation theatre daily for few days before doing surgery, so as to reduce the anxiety of the patient.

***MIVAI**—Minimally Invasive Video-Assisted Thyroidectomy* is becoming popular for small nodules and gland without thyroiditis. But it is costly.


1. Head end elevated 15 degrees
2. Sand bag under the shoulder
3. Head rest under the occiput
4. Hands tugged under the buttocks

Fig. 6.70: Position of the patient for thyroid surgery. Head end elevated, sand bag under the shoulder.



Fig. 6.71: Patient under anaesthesia with proper position for thyroidectomy surgery.



Fig. 6.73: Kocher's thyroid incision for thyroidectomy.



Fig. 6.72: Position of neck in thyroid surgery.



Fig. 6.74: Suction drain kept after thyroidectomy.

Complications of Thyroidectomy

1. *Haemorrhage:*
   May be due to slipping of ligatures either of superior thyroid artery or other pedicles or small veins. It causes tachycardia, hypotension, breathlessness and compression over the trachea may cause severe stridor, respiratory obstruction due to tension haematoma under strap muscles. As a first aid, immediate release of sutures including that of deep fascia has to be done and pressure over the trachea is released. Then patient is shifted to operation theatre and under general anaesthesia exploration is done and bleeders are ligated. Blood transfusion may be required.
2. *Respiratory obstruction*:
   It may be due to haematoma (if it is so, the haematoma has to be evacuated), or due to laryngeal oedema, or due to tracheomalacia or bilateral RLN palsy *(emergency endotracheal intubation* is done along with steroid injections). Often emergency tracheostomy may be required as a life-saving procedure.
   Laryngeal oedema is the commonest cause may be due to haematoma with tension along with intubation injury and surgical trauma. In such situation even though haematoma should be evacuated immediately to avoid further compression, airway obstruction will not be relieved due to laryngeal oedema and so endotracheal intubation is also

Complications of Thyroidectomy

Metabolic	***Nerve injuries***	***Other complications***
Hypoparathyroidism • Temporary hypoparathyroidism • Temporary hypocalcaemia without hypoparathyroidism (hungry bone syndrome) • Permanent hypoparathyroidism • Spurious hypoparathyroidism (total calcium is less but ionized calcium is normal) **Thyroid crisis** **Hypothyroidism / thyroid failure / myxoedema**	• External laryngeal nerve injury – pitch of the voice is lost • Recurrent laryngeal nerve injury **Vascular complications** • Haemorrhage – primary and reactionary • Haematoma formation • Compromised tracheooesophageal blood supply	• Respiratory obstruction • Skin flap necrosis – rare • Infection • Discharge and sinus formation • Wound granuloma • Keloid formation
Intraoperative	***Immediate postoperative***	***Late postoperative***
• Haemorrhage • Nerve injuries	• Haematoma • Laryngeal oedema • Respiratory obstruction – stridor • Hypoparathyroidism • RLN injury and its problems	• Hypothyroidism • Recurrent nodule • Recurrent toxicity • Wound infection • Granuloma / keloid



Fig. 6.75: Note the location of parathyroid glands.

needed immediately; in difficult situation if it is impossible to intubate, a needle tracheostomy using 12 gauge needle (2.3 mm diameter) is done temporarily.

3. *Recurrent laryngeal nerve palsy:*
   It can be transient or permanent. Transient is 3% common. They usually recover in 3 weeks to 3 months. Often they require steroid supplement and speech therapy. Permanent paralysis is rare. It presents with hoarseness of voice, aphonia, aspiration, ineffective cough. Unilateral injury can be well compensated. It is advisable to do routine postoperative ILS on 5th postoperative day. Later ILS is done in 4 weeks and 12 weeks.
4. *Hypoparathyroidism:*
   It is rare 0.5% common. Mostly it is temporary due to vascular spasm of parathyroid glands, occurs in 2nd-5th postoperative day. Present with weakness, +ve Chvostek's sign, carpopedal spasm, convulsions. Serum calcium estimation is done and then 10 ml of 10% calcium gluconate is given IV 8th hourly. Later supplemented by oral calcium carbonate 500 mg 8th hourly. After 3-6 weeks, patient is admitted, drug is stopped and serum calcium level is repeated.

   Note:
   Earliest symptom of hypocalcaemia is muscle weakness.
5. *Thyrotoxic crisis 2% (Thyroid storm):*
   Occurs in a thyrotoxic patient inadequately prepared for thyroidectomy and often a thyrotoxic patient presents in a crisis following an unrelated operation or stress. Other causes are—infection, trauma, preeclampsia, diabetic ketosis, emergency surgery, stress.
   Features: They present in 12-24 hours after surgery; with *severe dehydration*, *circulatory collapse, hypotension, hyperpyrexia*, tachypnoea, hyperventilation, palpitation, restlessness, tremor, delirium, diarrhoea, vomiting and cardiac failure; later coma.
   Bayley's symptom complex of thyroid storm are—insomnia, anorexia, diarrhea, vomiting, sweating, emotional instability, fever, tachycardia, aggravated toxic features, multi-organ dysfunction.
   Treatment: Injection hydrocortisone, oral antithyroid drugs, tepid sponging of whole body, beta blocker injection, oral iodides, large amount of IV fluids for rehydration, digitoxin, cardiac monitor, often ventilator support, with close observation. It has got high mortality rate with critical period of 72 hours. Fluid and electrolyte management, cardiac management are the important aspects to be monitored and treated.

Treatment of thyrotoxic crisis

- Injection hydrocortisone high dose—500-1000 mg IV; Tepid sponging; antipyretics, cooling blankets
- Rehydration with adequate IV fluids to control circulatory collapse

The same beam of light can illuminate two objects and produce two different effects.

- Injection sodium iodide IV-1 gram; oral iodides—Lugol's iodine 10-15 drops 8th hourly
- Injection propranolol—2 mg; esmolol; reserpine 500 µg/kg loading dose, then 5 µg/kg/minute; heart rate should be < 100/min
- Oral antithyroid drugs—propylthiouracil, 200 mg; carbimazole 20 mg 4th hourly ithium carbonate 300 mg 6th hourly
- Digitoxin; heparin; plasmapheresis
- Fluid and electrolyte management, antibiotics
- ICU care, ventilator support and cardiac monitor
- Exchange transfusion; charcoal plasma perfusion
- Heamodialysis

6. *Injury to external laryngeal nerve* causes weakness of cricothyroid muscle leading to alteration in pitch of voice, voice fatigue, breathy voice, frequent throat clearing. ILS reveals short hyperaemic vocal cords, lower level affected vocal cod, oblique glottis chink due to rotation of the posterior commissure to the paralyzed one.
7. *Hypothyroidism.* Revealed clinically after 6 months.
8. Wound infection, stitch granuloma formation.
9. Keloid formation.
10. Recurrent thyrotoxicosis is 5% common. It is due to retaining of more thyroid tissue during thyroidectomy for toxic thyroid. It is difficult to manage. It is treated with *antithyroid drugs, radioiodine therapy* or re-excision surgically which is technically demanding (so often avoided).

Remember in thyroidectomy

- Middle thyroid vein is present only in 30% of cases
- Bipolar cautery or harmonic scalpel (harmonic wave) are better to control bleeding and to prevent injury to RLN
- RLN should be identified in both sides. Variations should be remembered
- Parathyroids should be retained and also their blood supply
- Parathyroid autotransplantation may be needed if their blood supply is compromised
- Rapid influx of serum calcium into bones in immediate postoperative period may cause severe hypocalcaemia—***hungry bone syndrome*** which is initially corrected by IV calcium gluconate—10 ml of 10%. It is more commonly observed in patients with beta blockers. It is due to sudden drop in PTH level after surgery
- Tension haematoma under strap muscles is very dangerous and should be relieved by removing sutures from the skin and strap muscles
- Permanent hypoparathyroidism is rare (0.5-1%) whereas temporary hypoparathyroidism and hypocalcaemia is common (25%) which is corrected well with calcium for certain period of 3-6 months.
- External laryngeal nerve injury is more common than of RLN. There is loss of tension of vocal cords causing reduced power and range in voice (pitch).
- Thyroid insufficiency develops in 25-45% cases. It is confirmed by doing serum T_3, T_4 and TSH after 6 months.

EMIL THEODOR KOCHER

> *We have arrived at the point where we generally recommend the radical operation for goitre as the surest and simplest method of treatment.... Surgeons have simply assumed that the thyroid gland has no function whatever.... Patients with total excision... all show more or less severe disturbances in their general condition.... We cannot fail to recognise (the) relation to idiocy and cretinism.... We see no objection for the time being, to the use of the name cachexia strumipriva.*
>
> —**Emil Theodor Kocher**, 1883

He is the first surgeon to get Nobel prize. He did extensive work on thyroid surgeries and designed present technique of thyroid surgeries.

He was from Switzerland. He was the founder of:

- Kocher's vein.
- Kocher's forceps (has got tooth in the tip).
- Kocherisation (Duodenal mobilisation).
- Kocher's incision (Right subcostal for cholecystectomy).
- Kocher's thyroid incision.
- Kocher's test.
- Kocher's method for reduction of shoulder dislocation.

He died in 1917. *He is the father of thyroid surgery.*

Other surgeons who got Nobel prizes are—Alexis Carrell, for his work on vascular anastomosis; Christian Bernard, for heart transplantation, Charles Huggins, urologist, for management of carcinoma prostate.

KOCHER'S TEST

In case of a huge or long-standing thyroid enlargement, both lateral lobes of thyroid are pushed posteromedially with fingers. The test is positive, if it produces **stridor.** This signifies weakened tracheal (rings) cartilage because of constant pressure by the thyroid gland. But then trachea is kept patent by the thyroid itself. Once the gland is removed there is no support to trachea and so it collapses causing stridor (*scabbard trachea*). Such patient *requires temporary tracheostomy for 2-3 weeks*. By then trachea regains its strength back.

HYPOTHYROIDISM

Causes

- Agenesis or dysgenesis
- Enzyme deficiency
- Iodine deficiency
- Hashimoto's thyroiditis
- Antithyroid drugs
- Radioiodine
- *Drugs:* Lithium, amiodarone
- After thyroidectomy, common cause

Primary—is due to thyroid diseases or removal of thyroid.
Secondary—is due to hypopituitarism.
Tertiary—is due to hypothalamic diseases.

Cretinism

- It is fetal/infantile hypothyroidism due to inadequate thyroid hormone production during fetal and neonatal period. It may be due to agenesis, inborn error of thyroid metabolism, dyshormonogenesis or dietary deficiency (endemic).
- Typical hoarse cry, macroglossia, umbilical hernia, thickened skin are the features.
- TSH will be raised; T_3 and T_4 will be low.
- Incidence is 1:4000 live births.
- It is treated with L thyroxine once a day morning orally.

Clinical Features

- *General:* Tiredeness, weight gain, cold intolerance, goitre, hyperlipidaemia.
- *Cardiovascular*: Bradycardia, angina, cardiac failure, pericardial effusion.
- *Haematological*: Anaemia.
- *Dermatological*: Dry skin, vitiligo, Alopecia, erythema.
- *Reproductive:* Infertility, menorrhagia, galactorrhoea.
- *Gastrointestinal*: Constipation, ileus.
- *Developmental*: Growth and mental retardation, delayed puberty.
- *Other features*: Carpal tunnel syndrome, myalgia, hoarseness, deafness, ataxia, depression, psychosis (Myxoedema madness).

Myxoedema coma

Characteristic features	***Precipitated by***	***Treatment***
Hypothermia	Cold	Drug of choice—T_3, (Levothyronine) 10 μg given IV 6th hourly
Hypotension	Infection trauma	Levothyroxine—300 μg IV/1000 μg orally (large dose)
Hyponatraemia		Glucocorticoids
Hypoventilation		Antibiotics
Hypoglycaemia		Slow warming
Bradycardia		Electrolyte management
Skin is deadly cold like of a todd		
Coma		
Note: Myxoedema is severe thyroid failure.		



Figs 6.76A and B: Typical myxoedema patient.

Investigations

- T_3, T_4 estimation.
- TSH level estimation which is higher.

Treatment

- Replacement with L-thyroxine 100 to 150 μg/day. In old patients with ischaemic heart disease initial therapy is with 25-50 μg/day and then gradually increased upto the required dose.
- Initial rapid response can be achieved by giving L iodothyronine 20 μg tid.

RECURRENT LARYNGEAL NERVE PALSY

Anatomy and Relations of Nerves with Thyroid Gland

- *External laryngeal nerve* is a branch of superior laryngeal nerve. Vagus gives superior laryngeal nerve branch at inferior ganglion of vagus which is at the level of greater cornu of hyoid bone, which in turn divides into internal laryngeal and external laryngeal nerves. Internal laryngeal nerve pierces the thyrohyoid membrane and gives sensory supply to larynx above the vocal cord and hypopharynx. External laryngeal nerve runs close to superior thyroid vessels to supply cricothyroid muscle which is tensor of vocal cord.

Don't judge each day by the harvest you reap but by the seeds you plant.

It may get injured while ligating superior pedicle causing defective pitch of the voice. So upper pedicle of thyroid should be ligated close to gland.

- *Recurrent laryngeal nerve* is a branch of vagus which hooks around ligamentum arteriosum with arch of aorta on the left and right subclavian artery on the right side. It runs in the tracheo-oesophageal groove near the posteromedial surface close to thyroid gland. Nerve lies in between branches of inferior thyroid artery. So inferior thyroid artery should be ligated away from the gland. Anomalies of the nerve should be remembered. In 5% of cases nerve passes through the gland. Nerve may be much more away from the gland. Nerve may be closely adherent to gland posteriorly. Nerve may lie within the ligament of Berry (25%). Non-recurrent laryngeal nerve may be present in 1 in 1,000 cases with a horizontal course. RLN supplies all muscles (abductors, adductors) of the larynx except cricothyroid and also gives sensory supply of larynx below the vocal cords.

Muscles of the Larynx

- Cricothyroid: It is the only muscle which is located on the external aspect of the larynx. It is supplied by external laryngeal nerve. It is tensor and mild adductor of the vocal cord.
- Abductors of the vocal cord—Posterior cricoarytenoids.
- Adductors of the vocal cord—Lateral cricoarytenoids, transverse arytenoid, thyroarytenoids and cricothyroids.
- Relaxant of vocal cords—Thyroarytenoids and vocalis.
- Muscles which close the laryngeal inlet—Oblique arytenoids and aryepiglottic.
- Muscles which open the laryngeal inlet—Thyroepiglotticus.


Inferior thyroid artery
Carotid artery
– 50%
Thyroid
Rec laryngeal nerve
– 25%
Thyroid
Rec laryngeal nerve
– 20%
Thyroid
Rec laryngeal nerve
– 1.5%
Thyroid
Rec laryngeal nerve
– 0.25%
Thyroid
B
Vagus
Non-recurrent–(rec.) laryngeal nerve

Fig. 6.77B

Figs 6.77A and B: Anatomy of superior and recurrent laryngeal nerve. Superior laryngeal nerve divides into internal and external laryngeal nerves. Right recurrent winds round subclavian artery and left winds around arch of aorta.


Superior vagal ganglion
Jugular foramen
Superior laryngeal nerve
Inferior vagal ganglion
Internal laryngeal nerve
Cricoid
External laryngeal nerve
Common carotid artery
Vagus
Thyroid
Inferior thyroid artery
Right subclavian artery
Left recurrent laryngeal nerve
Right recurrent laryngeal nerve
Left subclavian artery
A
Trachea
Arch of aorta

Fig. 6.77A



Fig. 6.78: Recurrent laryeal nerve on table identification is a must during thyroidectomy.

Positions of Vocal Cord

Median; paramedian (1.5 mm); normal; cadaveric/neutral (3.5 mm); gentle abduction (7 mm); completely abducted (9.5 mm).

Assessment of voice change

- Pitch of the voice—whether raised/lowered or pitch locked
- Breath support during speaking is adequate or not
- Ability to alter the rapidity of speech—slow/fast/ medium
- Altered laryngeal and neck muscle tension
- *Indirect laryngoscopy*—with tongue pulled out using gauze, warmed ILS is placed into the oral cavity to see vocal cords. Patient is asked to say 'e' to see the vocal cord movements



Fig. 6.79: Vocal cord in recurrent laryngeal nerve palsies

Types

1. Unilateral recurrent laryngeal nerve palsy.
2. Bilateral recurrent laryngeal nerver palsy.
3. Unilateral, combined recurrent laryngeal and superior laryngeal nerve palsy.
4. Bilateral, combined recurrent laryngeal and superior laryngeal nerve palsy.

1. Unilateral Recurrent Laryngeal Nerve Palsy

All intrinsic muscles of the larynx except cricothyroid are paralysed. Vocal cord becomes median or paramedian position. Reasons are:

a. Only retained cricothyroid is a weak adductor of vocal cord causing median or paramedian position of vocal cords (*Wagner-Grossman hypothesis*).

b. Abductor fibres which are phylogenetically newer (to posterior cricoarytenoid) of the recurrent laryngeal nerve is more susceptible and paralysed than adductor fibres (*Semon's law).*

Causes for unilateral recurrent laryngeal nerve paralysis

- Infiltration from carcinoma thyroid
- Infiltration from carcinoma oesophagus
- Infiltration from carcinoma bronchus (left-sided)
- Mediastinal tumours (left-sided)
- Aortic aneurysms
- Trauma
- Idiopathic
- Thyroidectomy
- Neck or mediastinal lymph node mass

Clinical features

- Asymptomatic in 33% cases.
- Some change in voice, which gradually becomes normal with speech therapy.
- Aspiration never occurs.
- Airway obstruction never occurs.

Treatment

No specific treatment is required.

But steroid should be started. Prednisolone 20 mg tid for 10 days orally after food is given with gradual tapering in another 10 days.

2. Bilateral Recurrent Laryngeal Nerve Palsy

Both side intrinsic muscles are paralysed. So both vocal cords lie in median or paramedian position due to unopposed actions of the both side cricothyroid.

Clinical features

- Change in voice.
- Severe dyspnoea and stridor (more during exertion) leading to airway block and respiratory arrest.

Treatment

- Emergency tracheostomy.
- Lateralisation of the cord by:
    - Arytenoidectomy by open surgery or through an endoscope.
    - Vocal cord lateralisation through endoscope.
- Excision of vocal cord through an endoscope or laser cordectomy.
- Implantation of sternohyoid.
- Thyroplasty.

3. Unilateral, Combined Recurrent Laryngeal Nerve and Superior Laryngeal Nerve Palsy

All the muscles on one side are paralysed. Vocal cord is in cadaveric position, 3.5 mm from the midline.

Clinical features

- Hoarseness of voice.
- Aspiration through ineffective glottis.
- Ineffective cough.

Have, goals, they give direction, purpose and meaning to lofe.

Treatment

- Speech therapy (Commonly healthy opposite cord moves to opposite side of the midline so as to compensate for the paralysis of the opposite side).
- Injection of Teflon to the paralysed cord**.**
- Muscle or cartilage implant to the paralysed cord.
- Arthrodesis of cricoarytenoid joint.

4. Bilateral, Combined Recurrent Laryngeal Nerve and Superior Laryngeal Nerve Palsy

Causes

- All (total) paralysis of intrinsic muscles of larynx
- Total laryngeal anaesthesia

Clinical features

- Aphonia (no voice).
- Aspiration due to severe glottis incompetence and laryngeal anaesthesia.
- Absence of cough.
- Retention of secretions in the chest.
- Respiratory arrest.

Treatment

- Emergency tracheostomy.
- Fixing epiglottis over the arytenoids to prevent aspiration.
- Plication of vocal cords to prevent aspiration.
- Total laryngectomy.

- Unilateral recurrent laryngeal nerve palsy – Not dangerous
- Bilateral recurrent laryngeal nerve palsy – Most dangerous
- Unilateral combined palsy – Not dangerous
- Bilateral combined palsy – Dangerous

Chapter 7 Parathyroids and Adrenals

> *About three years ago I found on the thyroid gland…a small organ, hardly as big as a hemp seed, which was enclosed in the same connective tissue capsule as the thyroid, but could be distinguished therefrom by a lighter color. A superficial examination revealed an organ of a totally different structure from that of the thyroid, and with a very rich vascularity…. (I) suggest the use of the name Glandulae parathyreoideae; a name in which the characteristic of being bye-glands to the thyroid is expressed.*
>
> —**Ivar Victor Sandström,** 1879

CHAPTER OUTLINE

- Anatomy
- Calcium
- Hyperparathyroidism
- Parathyroidectomy
- MEN Syndrome
- Apudomas
- Hypoparathyroidism
- Tetany
- Adrenals
- Adrenal Cortical Tumours
- Adrenocortical Carcinoma
- Cushing's Syndrome
- Conn's Syndrome
- Virilising Syndrome or Adrenogenital Syndrome
- Neuroblastoma
- Pheochromocytoma

ANATOMY

- Parathyroids are endocrine glands situated behind the thyroid gland. They are four in number two on each side.
- Two upper glands are constant in position. Superior is *behind* recurrent laryngeal nerve. They develop from 4th pharyngeal pouch hence called as parathyroid IV.
- Two lower glands are variable in position. They develop from endoderm of 3rd pharyngeal pouch hence called as parathyroid III. It is usually *in front* of the recurrent laryngeal nerve, lower part.
- Each gland weighs *40-50 mg*. It is brownish (khaki coloured) firm gland, which sinks in the fluid unlike fat which floats. It is usually adjacent to the anastomosis between superior and inferior thyroid arteries posteriorly.
- Glands (chief cells) secrete parathormone (PTH) which controls the calcium metabolism.
- Variations are common in inferior parathyroids. It can be located in thyrothymic ligament, superior pole of thyroid, tracheooesophageal groove, behind oesophagus, carotid sheath. There may be more than two glands on one side called as supernumerary gland (2.5-22%).
- Both superior and inferior glands receive their blood supply from inferior thyroid artery and its anastomotic branch. Blood supply is through *an end arterial* branch.
- Gland contains *chief and oxyphil* (water clear) cells.

Parathormone—PTH

- Increases absorption of the calcium from the gut
- Mobilizes calcium from the bone
- Increases the calcium reabsorption from the renal tubules
- Half life of PTH is 4 minutes.

CALCIUM

Total calcium in plasma in ionised and nonionised (unbound and bound) form is 8.5-10.2 mg/dl (2.2-2.5 mmol/L). 55% is bound; 45% is unbound ionised free active part (4.5-5.0 mg/dl). Commonest protein part of bound calcium is albumin (80%); remaining is beta globulin, non-protein molecules. Ionised calcium is inversely related to pH of blood; raise in pH by 1 will reduce the ionized calcium by 0.36 mmol/L. Levels of calcium is controlled by PTH, calcitonin and vitamin D acting on bone,

Any adrenal tumour more than 50 gm is usually malignant.



Fig. 7.1: Anatomical location of parathyroids.

kidney and GIT. PTH (84 amino acids) is secreted by chief cells whenever serum calcium level falls. PTH stimulates osteoclasts for bone resorption; kidney to promote calcium reabsorption and production of 1,25 dihydroxy vitamin D; GIT to promote absorption of calcium and phosphorous. Vitamin D hydroxylation at carbon 25 occurs in liver, and later at carbon 1 occurs in kidney. It is important for blood coagulation, neuromuscular activity, cellular activity, bone integrity.

HYPERPARATHYROIDISM (HPT)

Types

1. Primary.
2. Secondary.
3. Tertiary.

Primary is unstimulated inappropriate high PTH secretion due to hyperplasia or adenoma causing hypercalcaemia**.**

Secondary is due to chronic renal failure or due to malabsorption, vitamin D deficiency rickets, i.e. due to chronic hypocalcaemia**.** There is always parathyroid hyperplasia. CRF causes hyperphosphataemia and reduced conversion of 25 DHCC to 1, 25 DHCC. So absorption of calcium from GIT is reduced causing chronic hypocalcaemia which stimulates PTH secretion and parathyroid hyperplasia.

Tertiary is due to autonomous reactive hyperplasia of parathyroids often seen like after renal transplantation.

Primary hyperparathyroidism

- ❖ Adenoma (75-90%)
- ❖ Hyperplasia (20-24%)
- ❖ Carcinoma, rare (1%)

Carcinoma of parathyroid is rare—1%. It is aggressive. It presents as nodule, palpable neck lymph nodes along with HPT. It is invasive to soft tissues, thyroid, perineural spaces. Often blood spread can occur. It needs wide tumour excision, hemithyroidectomy, neck node dissection and later radiotherapy to neck and mediastinum. With therapy 5-year survival rate is 85%.

Primary HPT is 3rd most common endocrine disease after diabetes and thyroid disease. Increased PTH causes hypercalcaemia.

Clinical Features

Clinical vignette of hyperparathyroidism—**“*Bones, stones, abdominal groans, and psychic moans*.”**

1. Hyperparathyroidism is common in middle aged women.
2. Presentation may be *asymptomatic*—> 50% cases.
3. *Nonspecific symptoms and psychiatric symptoms*: They are most often named as neurotics.
4. Behavioural problems.
5. In the bone there will be *osteitis fibrosa cystica* **(*von Recklinghausen disease*) *(5%)*,** which shows single or multiple cysts or pseudotumour in the jaw, skull or middle phalanges.
   Lamina dura of tooth is the first bone to show changes.
6. In the kidney**,** there may be bilateral, multiple *renal stones* or *nephrocalcinosis* (may go for renal failure).
7. It may be associated with the *peptic ulcer, pancreatitis, MEN I syndrome*.
8. They are more prone for skin necrosis, band keratopathy, pseudogout, myalgia, arthralgia, polyuria, glycosuria, hypertension (33%).

- ❖ Primary HPT is commonly sporadic than familial
- ❖ Histological difference between adenoma and hyperplasia is difficult to assess
- ❖ On table gross look is preferred method
- ❖ Adenoma is usually single. Multiple adenomas occur in elderly (5%)
- ❖ Hyperplasia involves all four parathyroids
- ❖ Parathyroid cyst may be developmental/secondary to degeneration of nodule or adenoma. Cyst aspiration shows clear fluid with high PTH level in the content fluid
- ❖ Preoperative IV methylene blue 5 mg/kg in 500 ml dextrose saline which stains parathyroids is used often to localise glands
- ❖ 50 percentage of one gland is sufficient to maintain function
- ❖ Persistent HPT is one in which HPT persists immediately even after initial surgery
- ❖ Recurrent HPT (initially after first surgery HPT is corrected but recurs 12 months after surgery) is due parathyromatosis, development of new adenoma, and hyperplasia of transplanted parathyroid. *Parathyromatosis* is due to rupture and spillage of parathyroid tissue in neck, mediastinum forming functioning nodules
- ❖ Re-exploration and removal in persistent/recurrent HPT needs on table PTH assay. On table PTH level drop more than 50% of preoperative value indicates the success of surgical removal
- ❖ CT, MRI, PET scan and selective angiography are usually done only for recurrent diseases

Acute Hyperparathyroidism (Crisis)

Causes

- ♦ Sudden increase in PTH level due to rupture of parathyroid cyst or bleeding in the parathyroid tumour.

- Severe dehydration precipitates crisis.
- Secondaries in bone (primary may be from breast).

Acute hyperparathyroidism is rare but dangerous presentation (crisis) wherein patient presents with abdominal pain, vomiting, dehydration, oliguria, muscular weakness and death.

Serum Ca^{++} is very high > 12 mg% (3.5 mmol/L).

Treatment of Crisis

- Forced diuresis using 3-5 litres of saline with frusemide.
- Rehydration using normal saline 300 ml/hour.
- Steroids, inhibits effects of vitamin D. dose is 400 mg/day IV for 5 days.
- Clodranate Na^{+}, Pamidronate (90 mg IV slowly in 4 hours). Zoledronic acid 4 mg IV initially and later 8 mg is also used.
- Drugs to reduce Ca^{++} level, i.e. *mithramycin, calcitonin, prednisolone, biphosphonates. Cinacalcet* is calcium receptor agonist which reduces the serum calcium level. Gallium nitrate inhibits osteoclast resorption of calcium at a dose of 200 mg/m^2/day for 5 days.
- Condition has high mortality rate.
  Patient develops hyperchloraemic metabolic acidosis.

Investigations for HPT

- High serum Ca^{++} —> 10 mg/100 ml.

Note:
Serum albumin should also be assessed to get accurate calcium level.

- Decreased serum phosphorus.
- Increased urinary Ca^{++} —> 250 mg/24 hr.
- Increased serum alkaline phosphatase.
- Increased PTH level in the serum is diagnostic—> 0.5 mg/L.
- X-ray skull shows *salt-pepper appearance.*
- X-ray phalanges and jaw are specific.

X-ray features in hyperparathyroidism

- Pepper lesions in the skull
- Sub-periosteal erosion of radial side of middle phalanx
- Calcification in bones

- U/S abdomen to find out problems in kidney, pancreas.
- U/S neck and CT/MRI scan neck and mediastinum.
- Selective venous sampling for PTH is also very useful.
- Thallium-Technetium scan shows *hot spots* which is diagnostic of parathyroid adenoma.
- *Technetium-99m labelled Sestamibi isotope* scan is better and sensitive (80%) than Thallium-Tc scan. As it is very expensive it is used in parathyroid re-exploration. It is often combined with *single photon emission computerised tomography* (SPECT).
- Urinary cAMP level increases in 90% cases.
- Angiography, venous sampling, SG guided biopsy are other methods.

Differential Diagnosis

- Secondaries in the bone—due to secretion of PTH related polypeptide by tumour. Actual PTH is suppressed.
- Multiple myeloma.
- Vit D intoxication.
- Sarcoidosis.
- Functioning carcinoma.
- *Familial hypocalciuric hypercalcaemia* is an autosomal dominant disease with mild raise in serum calcium and PTH levels secondary to mutation in the cell membrane calcium receptor. Urinary calcium excretion is low. It does not require parathyroidectomy. Calcium creatinine clearance



Fig. 7.2: Plain X-ray skull. Note the characteristic salt-pepper appearance of the skull bone.



Figs 7.3A and B: X-ray of humerus bone and hand bones showing bone features—**brown tumour**—osteitis fibrosa cystica.

The fact which Addison has published seem to lead to the conclusion that these little organ are essential to life.
—Charles Edward Brown-Sequard

ratio is less than 0.01 in this condition whereas it is > 0.02 in primary HPT.

Indications for parathyroidectomy

- Severe symptoms
- Young age group
- Markedly reduced bone density
- Serum calcium more than 11 mg%
- Urinary calculi
- Neuromuscular presentations
- Urinary calcium more than 400 mg /24 hours

Problems in parathyroidectomy

- Permanent hypoparathyroidism
- Persistent hyperparathyroidism—5%
- Recurrent hyperparathyroidism—hypercalcaemia recurs 12 months after first parathyroid surgery
- Recurrent laryngeal nerve injury—1%
- Often needs additional thyroidectomy
- Variations in positions of the gland especially lower-may be in mediastinum
- Sudden drop in calcium level after surgery due to increased absorption of calcium by bones—***hungry bone syndrome***

Treatment

- Surgical removal of the glands and implantation of fragments of the gland in forearm muscle mass (brachioradialis) or neck (sternomastoid). Marker stitch is placed at the transplantation site. 1/3rd of one gland or 100 mg of parathyroid gland is autotransplanted—subtotal parathyroidectomy.
- If it is carcinoma, additional hemithyroidectomy with postoperative radiotherapy is required.
- Adenoma when occurs in one gland with normal other glands, removal of that gland with adenoma may be sufficient.
- When all four glands are diseased, transcervical thymectomy is also added along with total parathyroidectomy to reduce persistent and recurrent disease.
- In familial and MEN syndromes, total parathyroidectomy is better.
- If it is mediastinal parathyroid adenoma, after proper localisation thoracoscopic removal may be sufficient.
- *Medical treatment of primary hyperparathyroidism* is usually ineffective and not popular. However occasionally as initial therapy and acute crisis it is being advocated. Estrogens, progestogens, raloxifene (estrogen receptor modulator), mithramycin, calicitonin are the few drugs used. *Mithramycin is* used *once a week* but it is hepatotoxic and causes thrombocytopenia.

PARATHYROIDECTOMY

Primary hyperparathyroidism—*Criteria (2002) for surgical intervention are*—raise in serum calcium level more than 1 mg/dl of upper limit of the normal calcium range; 24 hours urinary calcium if more than 400 mg; creatinine clearance when reduced more than 30%; bone density greater than two standard deviations below peak bone mass in lumbar spine/hip/lower end of radius; age below 50 years; when medical therapy is not possible.

Secondary HPT is an indication for removal of all four glands with autotransplantation of parathyroid only in severe cases or with renal osteodystrophy.

Preoperative Preparation

Vocal cords should be assessed by preoperative indirect laryngoscopy.

High calcium levels preoperatively may require treatment with hydration; diuresis; steroids (prednisolone 20 mg TID for 5 days before surgery); 100 mmol phosphate infusion in 6 hours; 200 units calcitonin subcutaneous injection for 5 days twice daily before surgery; diphosphanate—etiodronate disodium 7.5 mg/kg daily as slow IV infusion for 3 days; mithramycin 25 μg/kg as single dose.

Anaesthesia and Position

General anaesthesia is used with neck hyperextension by placing rolled sheet under the shoulder blades. Head is placed on the head ring; head end of the table is raised to semi-erect position (*Semi-fowler position).*

Incision and Dissection

It is same as for thyroidectomy. Flaps are raised in similar way. Strap muscles are separated after opening the deep fascia in the midline. Thyroid gland is mobilised to identify the parathyroid adenoma. Parathyroid having adenoma is mobilised which is close to recurrent laryngeal nerve. End artery of the parathyroid is identified and ligated. Adenoma is separated from adjacent thyroid tissue using gauze dissection. Either on table venous sampling for PTH assay is done or venous sample from cubital vein is done for PTH assay.

Parathyroid may be confirmed by frozen section biopsy or on table aspiration of parathyroid tissue which is analysed for PTH assay which will be more than 1500 pg/ml (confirms that removed tissue is parathyroid).

Total parathyroidectomy is done for parathyroid hyperplasia by removing all four glands and ⅓ of one gland is autotransplanted into the forearm muscle (brachioradialis) or sternocleidomastoid muscle with marker stitch. Gland to be transplanted is sliced into 1 mm pieces and around 18 pieces are embedded in decided muscle with a marker stitch or clip. If in postoperative period patient still presents with features of primary HPT; transplanted area is re-explored and further reduction in parathyroid tissue is done.

Wound is closed with proper haemostasis.

Complications

- Haemorrhage, recurrent laryngeal nerve palsy, hypocalcaemia and *hungry bone syndrome* are known to occur.
- *Persistent HPT* (serum calcium does not normalise immediately after surgery leading to total failure) or *Recurrent HPT* (serum calcium after surgery becomes normal but in 6-12 months, it again increases) may be a problem.

- Hypoparathyroidism with severe hypocalcaemia is a problem when all glands are removed (3½) with bilateral neck exploration. 10 ampoules of calcium gluconate is diluted with one liter of normal saline and given as continuous infusion at a rate of 30 ml/hour—initial method of management. Hypomagnesemia should also be corrected.
- Migration or inability to identify the transplanted parathyroid is often a problem in autotransplantation of parathyroid.
- **Hungry bone syndrome**
  - It occurs usually in patients with preoperative hyperthyroidism. They have increased bone breakdown in their hyperthyroid state. When a patient's thyroid hormone level drops acutely after surgery, stimulus to break down bone is removed. The bones are now "hungry" for calcium, remove calcium from the plasma rapidly.
  - It usually occurs after parathyroidectomy; thyroidectomy for toxic thyroid; prostate cancer patients on estrogen therapy. Sudden cessation of existing increased bone breakdown makes bones to absorb calcium, magnesium and phosphorus rapidly. Calcium levels in blood prior to operation cannot predict hungry bone syndrome.
  - Hypocalcaemia, hypophosphataemia, hypomagnesemia and hyperkalaemia are four typical features in these patients. Estimation and correction of all these four factors is essential. ECG changes can occur. Hyperkalaemia should be treated judicially. Magnesium infusion is needed. There is an unusually high need for calcium, with a low calcium excretion in the urine.
  - Bone-specific alkaline phosphatase (ALP) continues to rise in the first few weeks indicating increased bone reconstruction.
  - Supplementation of vitamin D and elemental calcium is needed during discharge for 6 months.
  - Postoperatively they need calcitriol (gradually increased to 16 mg in 1 month, then gradually reduced) with 2 gm calcium supplement.
  - Monitoring is done by evaluating serum calcium, albumin, magnesium, phosphorus and bone specific alkaline phosphatase.
- Injury to recurrent laryngeal nerve, oesophagus can occur.

Effects of Surgery

- Among neuromuscular symptoms of primary HPT, proximal muscle weakness responds better than respiratory muscle weakness by parathyroidectomy.
- Among psychiatric illnesses, depression and spatial learning and processing improve well by surgery.
- Bone mineral density in hip and lumbar spine becomes better.
- Nephrocalcinosis is improved by surgery; but hypertension and renal excretion will not improve much.
- Half life of PTH is 4 minutes. On table serial PTH assays are done at several intervals—before dissection of the gland, during dissection and after dissection. 50% reduction in PTH level from baseline in post-removal sample is a 96% predictor of complete removal.
- Operative failure rate is 1.5 to 6%. Intraoperative PTH assay improves the success rate very much (76-94%). Cure rate is defined as normocalcaemia in 6 months postoperative period.
- Radio guided parathyroidectomy using intravenous injection of 20 mCi of 99mTc sestamibi 2 hours before surgery is not routinely practiced but may be useful for removal of adenoma appropriately. Hand held quantitative gamma counter is used intraoperatively on the neck over all parathyroid tissues.

Surgical Approaches

Classic Approach (Traditional Approach)

It is under general anaesthesia exploring bilateral neck to remove parathyroid tissue which is confirmed by frozen section biopsy. It shows 95% cure rate with 2% complication rate.

Minimally Invasive Parathyroidectomy (MIP)

It is done in case of *single adenoma* of parathyroid under regional cervical block anaesthesia usually in ambulatory set up. It is actually unilateral parathyroidectomy with removal of adenoma and involved entire that particular one parathyroid gland using limited neck exploration (small incision of 2-4 cm). Procedure is not useful in multiple adenomas or hyperplasia. Preoperative localisation with sestamibi combined with SPECT is a must. Intraoperative PTH assay is a must to confirm drop in PTH level to required level. Cervical block is given by infiltrating the xylocaine (1%) with adrenaline along posterior and deep to sternocleidomastoid muscle and also along the neck incision. Direct field block along the anterior border of the sternocleidomastoid and over the incision is also used. Postoperative serum calcium and PTH level should be assessed until 7th day.

Median Sternotomy (3%) Extension

Median sternotomy is often needed when parathyroid is in anterior mediastinum along with thymus. Often parathyroids may be 5, 6 or 7 in numbers instead of four.

Video Assisted Parathyroidectomy (Paolo Miccoli)

It is done in *localised single adenoma* using multiple ports on one side with intermittent CO_2 insufflation and suction irrigation. 1.5 cm incision 1 cm above the sternal notch helps in tactile assessment and dissection. Strap muscles are retracted laterally and thyroid is retracted medially. Conversion rate is 11%; RLN palsy is 2%.

Endoscopic Parathyroidectomy

Entire parathyroidectomy is done using laparoscopy. It is first used (1994) for a mediastinal parathyroid adenoma. In 1996, it was used for neck parathyroid hyperplasia by Gagner for removing 3½ glands. Now technique is *limited to single adenoma* to remove tumour and gland. Low pressure insufflations with 5 mm four trocars are used. Placement of trocars is dependent on the need of the operating surgeon. Many place trocars on one side only; but few prefer to place working trocars on opposite side.

Remedial Parathyroidectomy

It is done for persistent HPT (serum calcium is not normalised immediately after surgery leading to total failure) or recurrent HPT (serum calcium after surgery becomes normal but in 6-12 months, it again increases). It is done through lateral approach (*Feind*) between anterior margin of sternocleidomastoid and strap muscles so that scar tissues are avoided from initial dissection. On table localisation methods, on table PTH assay are needed. Medial sternotomy often may be needed to explore the mediastinum for complete removal of the gland. Parathyroids in such situations may be embedded in the tissue of thyroid or thymus. So removal of these glands also may be a need in such situations.

Subtotal Parathyroidectomy

It is indicated in hyperplasia or secondary HPT wherein 3½ glands are removed, retaining ½ of one gland.

Total Parathyroidectomy with Parathyroid Autotransplantation

It is done alternatively in hyperplasia wherein all four glands are removed; ⅓ or ½ of one gland is transplanted into sternocleidomastoid or brachioradialis muscle with a marker. Disease control will not occur if more part of the gland is transplanted. It is removing all four glands and½ or ⅓ of one gland is autotransplanted into the forearm muscle (brachioradialis) or sternocleidomastoid muscle with marker stitch. Transplanting gland is sliced into 1 mm pieces and around 18 pieces are embedded in decided muscle with a marker stitch or clip. If postoperatively patient still presents with features of primary HPT; transplanted area is re-explored and further reduction in parathyroid tissue is done. Migration or inability to identify the transplanted parathyroid is often a problem in autotransplantation of parathyroid.

MEN SYNDROME (MEA SYNDROME)

- Commonly inherited as an *autosomal dominant*.
- Cells involved has got common features of *APUD cells (APUDomas)*.

Note:

- APUD—**A**mine **P**recursor **U**ptake **D**ecarboxylation.
- **MEN**—**M**ultiple **E**ndocrine **N**eoplasia; **MEA**—**M**ultiple **E**ndocrine **A**denomatosis.

Types

- ***Type—I*:** Parathyroid hyperplasia or adenomas; pituitary tumour; pancreatic tumour [Endocrine—Insulinoma, gastrinoma, glucagonoma, vipoma]. It is also called as *Werner's syndrome*. Here the defect is in chromosome 11.
- ***Type—II***: Also called as *Sipple's disease.*
  1. II a includes medullary carcinoma of thyroid+ phaeochromocytoma + parathyroid hyperplasia (50%). Here the defect is in chromosome 10.
  2. II b includes medullary carcinoma of thyroid + phaeochromocytoma mucosal neuromas in lips and eyelids with bumpy-lumpy lesions, with marfanoid face, megacolon.

Evaluation and management of MEN syndrome: Family history; biochemical screening with parathormone, serum calcium, prolactin, growth hormone, blood sugar, insulin, proinsulin, pancreatic polypeptide, glucagons, gastrin levels, calcitonin, urinary catecholamines estimation; genetic screening from isolated DNA from peripheral blood white cells for ret proto oncogene. Specific surgical treatment of conditions is needed.

APUDOMAS

APUD (Amine Precursor Uptake Decarboxylation) *cells* are cells having specific cytochemical characteristics. *They are*:

- High amine content.
- Capacity of amine precursor uptake.
- Property of decarboxylation of these precursors to form amines.

- Initially it is thought that APUD cells are derived from *neural crest cells* (Pearse) but now found to be from endoderm. Cells share *similarities* in structure, properties, histological, histochemical, immunocytochemical and electron microscopic appearance. *Neuron specific enolase* enzyme is specific for these cells.
- These cells have got capacity to *synthesize peptides* which has got different modes of action. They are:
  1. *Endocrine action* where peptides get secreted into circulation to have distant target actions.
  2. *Paracrine action* where peptides get secreted locally to have action at local sites.
  3. *Neurocrine action* where peptides act as neurotransmitter at neuronal synapses.
  4. *Neuroendocrine action* where peptides stimulate release of peptide product of the neuron into the circulation.
- Tumours arising from these cells are grouped as ***Apudomas.*** Many of parathyroid tumours, pancreatic tumours are under this group. Their presentations are commonly due to increased secretions of these neuroendocrine hormones. Commonly *presentation* is like syndromes. Insulinoma, glucagonoma, gastrinoma, VIPoma are different examples. Tumours are ***entopic type*** if they secret hormones normal to the tissue like insulinoma/glucagonoma. They are ***ectopic type*** if they produce hormones which are not normal to the tissue of origin like gastrinoma/VIPoma.
- APUDOMAS are commonly associated with ***MEN syndrome*** (commonly type I). Radioimmunoassay, MRI abdomen, CT neck are *useful investigations.*
- ***Treatment*** is of individual diagnosed components of the condition.

HYPOPARATHYROIDISM

Types

Temporary	More common (2-50%) average 10%	Usually lasts for 2 months maximum up to 6 months. Decrease in calcium; increase in phosphorous
Permanent	Less common (0.4-13%) average 1%	Permanent—continues beyond 6 months. Decrease in calcium; increase in phosphorous
Hungry bone syndrome	Common (5-13%)	Severe, rapid begins in immediate postoperative period. Decrease in calcium; decrease in phosphorous

- Inadequate production of PTH leads to hypocalcemia. Hypoparathyroidism and the resulting hypocalcemia may be permanent or transient. The rate of permanent hypoparathyroidism is 0.4-13%.
- *Causes* are - direct trauma to the parathyroid glands, devascularization of the glands, or removal of the glands during surgery.
- The rate of *temporary hypocalcemia* is reportedly 2-50%. The cause of transient hypocalcemia after surgery is due to temporary hypoparathyroidism caused by reversible ischaemia to the parathyroid glands, hypothermia to the glands, or release of endothelin-1. Endothelin-1 is an acute-phase reactant which suppresses PTH production. Other hypothesis is—calcitonin release and hungry-bone syndrome. Calcitonin is produced by the thyroid C cells which inhibits bone breakdown while stimulating renal excretion of calcium (opposite of PTH).
- An effective method of evaluation of parathyroid function is to assess ionized calcium (or total calcium and albumin) levels in the perioperative period. A normal postoperative PTH level can accurately predict normocalcemia after thyroid surgery. Immediate postoperative PTH level if <1.5 pmol/L and morning serum calcium <2.0 mmol/L, then patient is at risk of hypocalcemia.

Features of Hypoparathyroidism

- Circumoral tingling, numbness, paraesthesia.
- Carpopedal spasm, laryngeal stridor.
- Respiratory muscle spasm, suffocation.
- Convulsions, blurred vision due to intraocular muscle spasm.
- Cataract formation as late feature.

Treatment

- Patients who have *symptomatic hypocalcemia* in the early postoperative period or whose calcium levels continue to fall rapidly need treatment. In symptomatic patients, intravenous calcium gluconate 10 ml 10% solution (1 gm) is administered over 10 minutes. A calcium infusion is started at a rate of 1-2 mg/kg/hr if symptoms do not resolve. Rate of infusion is decided by repeated analysis of serum calcium and clinical features.
- One to two grams of elemental oral calcium should be given each day. Calcium carbonate 1250 mg provides 500 mg of elemental calcium; the patient should take 2500-5000 mg/day.
- The patient needs vitamin D supplementation with calcitriol 0.25-1 mcg/day. The calcium supplementation should be divided 4-5 times per day rather than in a single dose to maximize absorption by the GI tract.
- Intravenous/intramuscular magnesium 0.5 gm/4 mEq/kg body weight for 5 days; later magnesium gluconate tablets 500 mg orally.
- In 2 months, trial weaning of oral calcium can be made to identify whether the hypoparathyroidism is temporary. Need for calcium supplementation longer than 6 months, indicates *permanent* hypoparathyroidism.

Prevention of Hypoparathyroidism

- Proper preoperative parathyroid localisation.
- Maintaining blood supply of parathyroids.
- Capsular ligation of the thyroid vessels at lower pole to retain parathyroid end arteries.
- Parathyroid autotransplantation if all 4 parathyroids are removed.

Spurious Hypocalcemia

- It is decrease in total calcium, albumin and haematocrit in the first two postoperative days following any surgery including non-thyroid. Surgical stress releases ADH causing water retention and haemodilution. Albumin bound total calcium is decreased. Free ionized calcium is normal unlike in true hypocalcaemia.

TETANY

Decreased level of calcium in blood causing its effects.

Causes

- After thyroidectomy (It is decreased level of parathormone in the blood causing hypocalcaemia). It is usually temporary, lasts for 4-6 weeks. It is the commonest cause of hypoparathyroidism.
- Other causes of hypoparathyroidism are neck dissection, haemochromatosis, Wilson's disease, DiGeorge's syndrome.

- Severe vomiting, hyperventilation associated with respiratory alkalosis.
- Metabolic alkalosis.
- Rickets, osteomalacia.
- Chronic renal failure.
- Acute pancreatitis.

Decreased PTH causes decrease in calcium level in the blood leading to:

- *Circumoral paraesthesia*, paraesthesia of neck, fingers and toes.
- Twitching and weakness of tongue muscles, muscles of forearm, hand, foot and digits—*carpopedal spasm.* Fingers are extended except at the MCP joints and thumb is strongly adducted (obstetrician' / accoucheur's hand); there is extension of feet to develop carpopedal spasm.
- *Chvostek's sign*—Tapping above the angle of the jaw to stimulate branches of facial nerve causes the twitching of the angle of mouth and eyelids.
- Applying the sphygmomanometer to the arm and inflating the pressure more than systolic pressure (200 mm of Hg) of the patient for three minutes can demonstrate carpal spasm *(Trousseau's sign).*
- *Stridor* and difficulty in breathing due to paralysis of respiratory muscles.
- Generalised weakness and twitching all over the body in severe cases mimicking *convulsions.*
- Prolonged QT interval and QRS complex in ECG.

Management

- Serum calcium estimation is done. It will be less than 7 mg%.
- IV calcium gluconate 10% 10 ml sixth to eighth hourly is given.
- Later oral calcium (1 gram three times daily) with vitamin D supplementation (1-3 µg daily).
- Follow up at regular intervals by doing serum calcium level.
- Magnesium sulphate supportive therapy is also often needed—10 ml 10% magnesium sulphate intravenously.

DiGeorge's syndrome

- Absence parathyroids
- Thymic aplasia with immunodeficiency
- Cardiac defects

ADRENALS

> *The facts which Addison has published seem to lead to the conclusion that these little organs are essential to life.*
>
> —**Charles Edouard Brown-Séquard,** 1856

Adrenal cortex contains three layers:

1. Zona glomerulosa secretes mineralocorticoids.
2. Zona fasciculata secretes glucocorticoids.
3. Zona reticularis secretes sex hormones.
    - Cortex—85%; mesoderm; produces and secretes aldosterone, cortisol, DHEA.
    - Medulla—15%; neuroectoderm; produces and secretes norepinephrine, epinephrine.



Fig. 7.4: Anatomy of adrenal gland.

ADRENAL CORTICAL TUMOURS

- Are usually adenomas.
- Any tumour measuring 6 cm or more are likely to be malignant, or have high risk of turning into malignancy. So requires surgical resection.
- *Adenocarcinoma* is the commonest adrenal cortical malignancy (1%). It is very aggressive tumour.
- Cortical tumours may be functioning or nonfunctioning.
- Functioning tumours secrete mineralocorticoids, glucocorticoids or sex hormones or combinations of these.

Investigations

- U/S abdomen.
- CT scan, Hormone evaluation.

Treatment

Adrenalectomy.

Incidentalomas (3-5%)

- Incidentalomas are adrenal tumours incidentally identified either through U/S; CT scan; MRI; or any other methods done for other reasons.
- When incidentalomas are identified a proper biochemical work up for hormones is essential. Overnight dexamethasone suppression test; 24-hour urinary cortisol excretion assay; 24-hour urinary excretion of catecholamines; serum potassium, renin and aldosterone analysis are done in these patients. MRI in suspected malignancy is better.
- If secondaries are suspected adrenal mass biopsy is done. Otherwise it should not be done. Non-functioning adenomas (commonest—78%), Cushing's adenoma, adrenocortical carcinoma, phaeochromocytoma, secondaries, Conn's adenoma are different causes of adrenal incidentalomas. Adenoma with Cushing's syndrome is better than adenoma with Conn's syndrome. Tumour with adrenogenital syndrome is commonly malignant.
- Non-functioning adrenal tumour more than 4 cm should be operated. Smaller tumours that increase in size over specified

period should be removed. All functioning tumours should be operated.

- Non-functioning tumour less than 4 cm should be followed up at regular intervals by hormone tests and CT/MRI.

ADRENOCORTICAL CARCINOMA

- It is a rare malignancy with 1 case in 1000000 population. It is common in females with bimodal presentation.
- ***Features are***—tumour size; necrosis; haemorrhage; capsular invasion; vascular invasion. Immunohistochemistry is specific.
- ***Presentations are***—abdominal pain; back pain; Cushing's syndrome (60%); hyperaldosteronism; virilisation.
- It is *least common* malignant endocrine tumour.
- One of the *most malignant* endocrine tumour after anaplastic carcinoma of the thyroid.
- Can be functioning or nonfunctioning tumour.
- Larger tumours (>6 cm) are more likely to be malignant.
- Cytologic criteria alone are not diagnostic but should find capsular infiltration and vascular invasion.
- Often presents with no symptoms or only vague symptoms.
- May present with mass effect and compression of adjacent structures.
- Increased secretion of one or more steroid hormones can occur.
- ***Diagnosis is by***—hormone evaluation, CT/MRI; MR angiography to identify IVC tumour thrombus.
- Secondaries occur commonly in lungs. So HRCT of lungs is usually done.
- ***Mc Falane staging*****:** Stage I—tumour < 5 cm; Stage II—tumour > 5 cm; Stage III—tumour with local invasion; Stage IV—distant spread. In stage I and II, 5 year survival is 25%; in stage III and IV, 5-year survival is 5%.
- ***Treatment*** is en block adrenalectomy; removal of tumour thrombus from vena cava if present; chemotherapy using mitotane—Op-DDD (choice) with cis platin, etoposide and doxorubicin. Adjuvant radiotherapy may be used to prevent recurrence *(little role)*.
    - *Recurrence* is treated by debulking and chemotherapy.
    - Laparoscopic adrenalectomy is not advisable in adrenocortical carcinoma.

Secondaries in adrenal gland

- Common entity
- Commonly from breast, lungs, kidney, melanoma
- 1/3rd of above primaries show secondaries in adrenal gland
- Commonly bilateral
- In unilateral secondaries adrenalectomy can be done
- Bilateral secondaries are treated by chemotherapy depending on type of primary

Approches for adrenals (surgical)

- Posterior lumbotomy
- Anterior transabdominal
- Abdominothoracic
- Laparoscopic
- Retroperitoneoscopic

CUSHING'S SYNDROME

- Results from lengthy and inappropriate exposure to excessive glucocorticoids; iatrogenic administration of steroids (commonest cause); endogenous Cushing can also occur.
- More common in women.

Corticotropin (ACTH) Dependent—80%

- ACTH secreting pituitary adenoma.
- Ectopic ACTH secreting tumour.

Corticotropin Independent—20%

- Adenoma.
- Carcinoma.
- Macronodular adrenal hyperplasia.
- Primary pigmented nodular adrenal disease.

Features

- Centripetal obesity; redistribution of fat centrally.
- Moonface; fullness of supraclavicular pad of fat.
- Buffalo hump; proximal muscle wasting.
- "*Lemon on toothstick* appearance".
- Skin changes.

Diagnosis

- Loss of normal diurnal or circadian rhythm of serum cortisol. Values more than 4 fold the upper limit of normal is diagnostic.
- 24 hour urinary free cortisol is elevated > 90% of Cushings syndrome.
- *Low dose dexamethasone suppression test*: Dexamethasone is a potent glucocorticoid that suppresses adrenal production of corticosteroids in normal persons but not in persons with Cushing's syndrome. 1mg of dexamethasone is injected; normal—< 1.8 mcg/dl; in Cushings—high > 10 mcg/dl.
- *Late night salivary cortisol*—Cortisol concentration in saliva correlates with free plasma cortisol; it is independent of salivary flow rate; it shows high sensitivity and specificity.
- Negative urinary free cortisol and Low dose dexamethasone suppression test rules out Cushing's syndrome.
- *Measurement of corticotropin (ACTH)*: If low—corticotropin independent Cushing's syndrome; if high—corticotropin dependent Cushing's disease.
- *Localising methods/imaging*: **Adrenal**—CT scan/MRI abdomen; Iodocholesterol scan. **Pituitary -** MRI pituitary. It can be incidentaloma in pituitary. Inferior petrosal sinus sampling of blood for ACTH shows central to peripheral ratio of ACTH > 3.

Treatment

Medical: Metapyrone; ketaconazole; aminoglutethamide; mitotane.

Surgical

For Pituitary Disease

- Transsphenoidal microsurgery.
- Pituitary irradiation—conventional fractionated therapy; Sterotactic radiosurgery.
- Bilateral adrenalectomy.

For Adrenal Disease

- Unilateral adrenalectomy in adenoma, carcinoma.
- Bilateral adrenalectomy in macronodular adrenal hyperplasia and primary pigmented nodular adrenal disease.

CONN'S SYNDROME (Jerome Conn, 1954)

It is primary hyperaldosteronism with excessive secretion of aldosterone from the adrenal gland associated with suppression of plasma renin activity.

Aldosterone secretion is related to angiotensin I and II and plasma rennin with angiotensin converting enzyme.

Causes

Aldosterone producing adrenocortical adenoma—65%; Idiopathic hyperaldosteronism—30%.

Features

- ***Hypertension; hypokalaemia.***
- Hypernatremia or normal sodium; metabolic alkalosis
- In primary hyperaldosteronism—hypertension of early onset which is difficult to control and is with hypokalaemia.

Diagnosis

- *Hypokalemia*; increase in urinary potassium excretion.
- *Elevated* plasma aldosterone concentration (PAC); *suppressed* plasma renin activity (PRA); PAC: PRA > 30; it is confirmed by suppression test by oral or IV salt loading.
- *Localising tests*—CECT abdomen; Selective adrenal venous sampling—*Gold standard* to differentiate between unilateral versus bilateral aldosterone hypersecretion.

Treatment

- Adenoma—unilateral adrenalectomy.
- Idiopathic hyperaldosteronism—medical treatment with spiranolactone.

VIRILISING SYNDROME OR ADRENOGENITAL SYNDROME

- Virilising tumours/syndromes. Such tumours are excised.
  - *In female*: Virilism, ambiguous external genitalia, clitoral enlargement.
  - *In male*: Precocious puberty, premature fusion of epiphysis, short stature.
- Congenital adrenal hyperplasia (adrenogenital syndrome) is—enzyme 21 hydroxylase deficiency; autosomal recessive. It is treated by—replacement of deficient steroids. Adrenal hyperplasia does not require surgical intervention but the genital manifestations of excess androgen production, particularly in women, may require specialised surgery.

NEUROBLASTOMA

- Commonest childhood tumour.
- It is a tumour of adrenal medulla.
- An aggressive malignant tumour in childhood usually below the age of 5 years.
- Incidence is equal in both sexes.
- A reddish-grey tumour gets invaded early into kidney, pancreas and adjacent tissues. Can also cause distant spread to liver, bones (skull), orbit.

It can occur anywhere in sympathetic chain but common in adrenal gland (40%).

Types

1. *Pepper type is right side* adrenal neuroblastoma with *liver secondaries.* Common in infants.
2. *Hutchinson's type is left side* adrenal neuroblastoma with *secondaries in orbit and skull*. Common in late childhood.

Secondaries in the skull mimics spicular osteogenic sarcomas.

Risk Groups

- Low risk groups—Stage I disease; Stage II disease with single N myc value; Stage II with favourable Shimada histology.



Fig. 7.5: Left-sided adrenal neuroblastoma with secondaries in orbit. Note scar of left sided adrenalectomy.

- Intermediate risk groups—Stage III without N myc amplification; Stage III with favourable Shimada's histology.
- High-risk groups—all patients with N myc amplification; stage IV neuroblastoma.

Pathology

- *Gross*—tumour with vascularity, necrosis, haemorrhage and often calcifications.
- *Histologically* it contains uniform round cells with hyperchromatic speckled nucleus with Homer-Wright rosettes with central fibrillar core. PAS stain is negative and NSE stain is positive. Often histochemistry is needed to differentiate from other tumours.
- *Shimada's histological classification:*
  - Stroma rich tumour: Presence of Schwannian spindle cell stroma.
  - Stroma poor tumour: Absence of Schwannian spindle cell stroma.

Clinical Features

- Child presents as a huge mass per abdomen, in the loin which is non-mobile. Not moving with respiration. Knobby (nodular) surface, crosses the midline.
- *Dancing eye syndrome and opsomyoclonus.*
- *Racoon's eye sign* is infraorbital ecchymosis due to secondaries in retroorbital region.
- Hypertension, fever, weight loss, anaemia, flushing (due to catecholamine release) and sweating.
- Diarrhoea, hypokalaemia due to release of Vasoactive Intestinal Polypeptide (VIP). Other hormones like ACTH are also released.



Figs 7.6A and B: Figure shows typical secondaries in skull and orbit with primary in adrenal gland. Such patients carry poor prognosis. *Racoon's eye sign* is infraorbital ecchymosis due to secondaries in retroorbital region. Dancing eye syndrome and opsomyoclonus are other eye features. CT picture of the same patient shows obvious secondaries.

Staging of neuroblastoma

- Stage I: Localised tumour with gross complete excision. Same side representative nodes are negative on microscopy
- Stage II A: Localised tumour with incomplete gross excision. Same side representative nodes are negative on microscopy
- Stage II B: Localised tumour with or without complete gross excision. Same side nonadherent representative nodes are positive but contralateral nodes are (may be enlarged) negative on microscopy
- Stage III: Unresectable unilateral tumour infiltrating across midline/localised tumour with opposite side node spread/bilateral nodal spread/midline tumour with bilateral infiltration
- Stage IV: Any primary tumour with spread to distant nodes, bone, bone marrow, liver, skin and other organs
- Stage IV S: Localised primary tumour (stage I, IIA, IIB) with spread to skin, liver or bone marrow—limited to infants younger than one year

Differential Diagnosis

Wilm's tumour, which is mobile, with smooth surface, moves with respiration, does not cross the midline.

Diagnosis

- U/S, CT to assess the mass and secondaries in liver. MRI is better than CT.
- Plain X-ray abdomen shows stippled calcification.
- Urinary VMA and Homovanillic acid (HVA) estimation in 90% cases.
- MIBG scan.
- Bone marrow biopsy may be positive in 60% cases.

Treatment

- Adrenalectomy (Complete surgical excision).
- In inoperable cases debulking is beneficial.
- Postsurgical radiotherapy and folic acid supplements are useful.
- Chemotherapy is useful adjuvant. Drugs used are carboplatin, doxorubicin, cyclophosphamide and etoposide.
- Rarely spontaneous regression of tumour is known to occur.
- Low risk groups are treated by surgery. Intermediate risk groups are treated by surgery and multidrug chemotherapy. High risk groups are treated by high dose multidrug chemotherapy and later surgery.

Prognosis

- It depends on staging of the neuroblastoma—1, 2A, 2B, 3, 4, 4S.
- Low risk has got 3 years survival—90%; intermediate risk—70% and high risk group has got 30%.
- Factors are—age of the child; stage of the disease; Shimada's histology; N myc amplification status (more means high risk); DNA ploidy; neurotrophin receptor Trk A (increased favourable); neutrophin receptor Trk B (increased unfavourable).

One only gets to the top rung of the ladder by steadily climbing up one at a time.

PHEOCHROMOCYTOMA

- It is a tumour arising from chromaffin cells, commonly from the adrenal medulla but occasionally can arise from extraadrenal chromaffin tissues (*Organ of Zuckerkandl*).
- It is catecholamine secreting tumours that arise from chromaffin cells of sympathetic origin derived from neural crest representing a potentially curable form of hypertension.
- *Incidence* is 0.005% to 0.1% of general population; 0.1% to 0.2% of adult hypertensive population.
- It is a soft, brownish grey pink tumour, mainly *secretes noradrenaline* or other catecholamines.
- It may also secrete calcitonin, ACTH, VIP (vasoactive intestinal polypeptide), PTH related polypeptide.
- Prevalence of phaeochromocytoma is 0.05%. In patients with hypertension it is up to 0.6%. 4% of incidentalomas are pheochromocytoma.
- Often it is difficult to differentiate between benign and malignant types. Necrosis, haemorrhage, high Ki-67 positive cells, size of the tumour, increased pheochromocytoma of adrenal gland scale score (PASS), capsular invasion and vascular invasion, nuclear DNA ploidy and increased neuron specific enolase (NSE) level are possible features of malignant phaeochromocytoma.
- Currently mutations in at least six distinct genes predispose to pheochromocytomas—RET, NF1, VHL, SDHB, SDHC, SDHD.
- Extra-adrenal pheochromocytoma—10 % common; occurs in organ of *Zuckerkandl*, urinary bladder, paravertebral or para-aortic area, thorax, neck. It secretes norepinephrine rather than epinephrine because they lack the enzyme PNMT.
- Commonly benign (90%).

Tumour is
- 10% malignant
- 10% extraadrenal
- 10% bilateral
- 10% familial
- 10% childhood
- 10% multiple
- 10% not associated with hypertension
- 10% calcified

Clinical Features

- Clinical manifestations are due to increased secretion of epinephrine and norepinephrine.
- Commonest presentation is severe *headache.*
- Palpitation, dyspnoea, weakness, pallor, blurred vision and other symptoms of sympathetic overactivity.
- They may present as persistent or paroxysmal hypertension (90%).
- As an abdominal mass which is nonmobile, smooth, does not move with respiration, crossing the midline, palpitation may cause fluctuation in BP.
- It may precipitate hypertensive encephalopathy, cardiac arrhythmias or cerebral haemorrhage.
- Panic attacks and sudden death are known to occur.
- It may be associated with ***MEN-IIa*** or ***MEN-IIb*** syndromes which includes medullary carcinoma of thyroid and mucosal neuromas.
- It may be associated with familial multiple neurofibromatosis with cafe au lait spots in the skin ***(von Recklinghausen disease***). Or with ***von-Hippel-Lindau syndrome*** (cystic lesion of pancreas, non-functioning islet cell tumour, phaeochromocytoma), RCC, CNS and Retinal haemangioblastoma.
- *Familial paraganglioma syndrome* may be an association with carotid body and extraadrenal paraganglioma.

Differential diagnosis
- Hyperthyroidism
- Anxiety status
- Cardiac conditions
- Carcinoids (functioning)

Investigations

- *VMA excretion* in urine in 24 hours will be >7 mg/24 hr in pheochromocytoma.
- U/S abdomen, IVU, CT scan.
- MRI is preferred to CT as contrast used for CT scan can precipitate paroxysms.
- Measurement of *plasma free metanephrines* is the recommended *test of choice* for excluding or confirming diagnosis of pheochromocytoma.
- *Urinary normetadrenaline* or other catecholamines estimation.
- Arteriography.
- Iodine labelled metaiodobenzylguanidine *(I, MIBG*). MIBG is useful to find out extraadrenal involvement—SPECT scan is very useful. I^{131} MIBG scan is safe, noninvasive with 100% sensitivity and 95% specificity.
- Measurement of plasma free metanephrine and normetanephrine has the *highest sensitivity and specificity* and appears to be the *best initial test* for screening patients with pheochromocytoma.

Treatment

Adrenalectomy

- Before surgery, BP is controlled initially by α-blocking agent, phenoxybenzamine or doxazosin; then by β-blocking agent, propranolol. Then during surgery, sodium nitroprusside IV infusion is used.
- Careful anaesthetic management with a good postoperative care is very essential. In case of bilateral presentation opposite side can be operated in later period.
- Intraoperative hypovolemia and postoperative hypotension is a demanding situation for anaesthetist to manage.
- Handling of adrenal tumour on table must be careful and gentle.
- Adrenal vein should be ligated first. CVP, arterial lines should be present for monitoring.
- Rupture and spillage of tumour should be prevented.

Note:

- *Laparoscopic adrenalectomy is becoming popular.* It is choice of approach for benign functioning or non-functioning adrenal tumours that are less than 6 cm in size. It is contraindicated in malignant tumours and tumour more than 6 cm.
- *Recent trends are*—cortical sparing adrenalectomy; thoracoscopic transdiaphragmatic approach; Robotic assisted laparoscopic adrenalectomy.
- Specimen should be sent for *bichromate staining which stains the specimen brow*n.

Remember

- Pheochromocytoma is rarely malignant in MEN II
- Pheochromocytoma under 40 years of age suspect MEN 2A, VHL
- Beta-blocker is given only after patient is fully alpha blocked with phenoxybenzamine (20-60 mg/day) or doxazocin
- Alpha-blocker is given 4 weeks prior to surgery to control hypertension and beta-blocker is given one week before surgery to control tachycardia and arrhythmias
- Tumours, those secrete dopamine exclusively has got high malignant chances
- 5-year survival for malignant pheochromocytoma is 50%. It needs additional chemotherapy using vincristine, dacarbazine and cyclophosphamide.
- Pheochromocytoma in pregnancy has got 50% maternal mortality
- Vaginal delivery is contraindicated in pregnancy with pheochromocytoma
- Adrenal vein should be ligated first
- Avoid breach in the capsule of tumour during surgery
- Careful handling and haemodynamic monitoring is a must
- Sodium nitroprusside may be required on table to control the hypertension—10 μg/kg/minute

Malignant pheochromocytoma is 10% common. It is more common in extraadrenal site. It commonly spreads to lymph nodes, bone and liver. Adrenalectomy in early tumour and debulking in advanced cases with α blockers, mitotane and I^{131}MIBG therapy and combination chemotherapy are the therapeutic choices. Overall prognosis is not good with 5-year survival being < 50%.

Chapter 8 Breast

CHAPTER OUTLINE

- Anatomy
- Mammography
- Aberration of Normal Development and Involution (ANDI) of the Breast
- Fibroadenoma
- Fibrocystadenosis
- Sclerosing Adenosis
- Phyllodes Tumour
- Mastalgia
- Traumatic Fat Necrosis
- Galactocele
- Mastitis
- Antibioma
- Duct Ectasia
- Mondor's Disease
- Tuberculosis of the Breast
- Breast Cysts
- Galactorrhoea
- Gynaecomastia
- Duct Papilloma
- Zuska-Atkins Disease
- Mammary Fistula of Atkins
- Carcinoma Breast
- Management of Early Carcinoma Breast
- Advanced Carcinoma Breast
- Prognostic Factors in Carcinoma Breast
- Prophylactic Mastectomy
- Carcinoma of Male Breast
- Breast Reconstruction
- Breast Implants
- Nipple Retraction

ANATOMY

Breast is a modified sweat gland derived from ectoderm, as branching epithelial cords which form lactiferous ducts. About 15-20 lobes develop during puberty, each of which drains into a single lactiferous duct. True secretory alveoli develop during pregnancy and lactation under the influence of oestrogen, progesterone and prolactin.



Fig. 8.1: Secretory apparatus of the breast.

Secretory Apparatus of Breast

The breast is composed of acini which make up lobules, aggregation of which form the lobes of the gland. The lobes are arranged in a radiating fashion like the spoke of a wheel and converge on the nipple, each lobe is drained by a lactiferous duct.

Different portions of the duct system are associated with different diseases.

1. Larger ducts are sites of *duct papilloma and duct ectasia*.
2. The distal smaller ducts are the sites of *fibroadenoma* during development of the breast; and *cyst formation and sclerosing adenosis* during the involution period.

- *Estrogen*—ductal proliferation
- *Progesterone*—glandular proliferation
- *Prolactin*—milk secretion

Topography

Vertically—it extends from the second to the sixth rib in the mid-clavicular line and lies over pectoralis major, serratus anterior and external oblique muscles.
Horizontally—from the side of sternum to the mid-axillary line.

2/3rd of the breast rests upon pectoralis major.
1/3rd rest upon serratus anterior.

At its lower medial quadrant the gland rests on the external oblique aponeurosis, which separates it from the rectus abdominis.

Breast lies in superficial fascia. Deep to breast, structures related are—retromammary space containing loose areolar tissue, pectoral deep fascia, muscles (pectoralis major, serratus anterior, external oblique), chest wall.

Retromammary bursa/space is located between deep layer of superficial fascia and pectoral (deep) fascia allowing free mobility of breast.

Nipple is located at the level of 4th intercostal space just below the center/summit of the breast. It contains circular and longitudinal muscles to make nipple stiff or flat. It is pierced by 15-20 lactiferous ducts. Each duct independently opens into the nipple. It has rich sensory nerve endings. It also contains modified sweat and sebaceous glands. Nipple is supplied by 4th intercostal nerve.

Areola is circular pigmented area around the nipple. It is rich in modified sebaceous glands which enlarge during pregnancy and lactation as *Montgomery tubercles*. They secrete oily lubricant to nipple and areola. Areola and nipple do not contain hair and fat beneath.

Breast parenchyma contains 15-20 lobes. Each lobe contains alveoli, lactiferous sinus and lactiferous duct (2-4 mm in diameter). Alveolus is lined by cuboidal (in rest) and columnar (in lactation) epithelium; smaller duct is by single layer of columnar epithelium; larger ducts by many layered columnar; lactiferous duct is by stratified squamous epithelium. *Myoepithelial cells* lie between epithelium and basement membrane from alveoli to duct.

Axillary Tail of Spence

This is a prolongation from the outer part of the gland which passes up to the level of the 3rd rib in the axilla through a defect in the deep fascia (*Foramen of Langer*) where it is in direct contact with the main lymph node of the breasts (anterior axillary nodes).



Fig. 8.2: Axillary tail of *Spence*.



Figs 8.3A and B: Axillary tail of *Spence*–exact location and excision of hypertrophied axillary tail.



Fig. 8.4: Hypertrophy of the axillary tail.



Fig. 8.5: Accessory nipple.



Fig. 8.6: Accessory nipple is not an uncommon condition. Often it can be bilateral.

This process of the breast gets into axilla through an opening in the deep fascia, known as *foramen of Langer.* When it enlarges it is ofen mistaken for a lipoma. Axillary tail of Spence is deep to deep fascia.

Ligament of Cooper

The breast is anchored to the overlying skin and to the underlying pectoral fascia by bands of connective tissue called *ligament of Cooper.*

1. In cancer, the malignant cells may invade these ligaments and consequent contraction of these strands may cause dimpling of the skin or attachment of the growth to the skin, which in turn cannot be pinched off from the lump.
2. If the cancer grows along the ligament of Cooper binding the breast to the pectoral fascia, the breast gets fixed to the pectoralis major. It then cannot be moved along the long axis of the muscle.

Polands syndrome

- ❖ Absence of breast—Amazia
- ❖ Absence of sternal portion of pectoralis major
- ❖ Common in males



Fig. 8.7: Anatomy of the breast.

Note:

Amazia is very rare entity with congenital absence of breast.
Polymazia is accessory breasts along milk line like in axilla (most common site), groin, thigh and buttock.
Athelia is absence of nipple; accessory nipples are called as *polythelia* or supernumerary nipples.
Micromastia is small sized breast due to less hormonal stimulation due to ovarian deficiency.

Blood Supply to the Breast

- ♦ The lateral thoracic artery, from the 2nd part of the axillary artery—30%.
- ♦ The perforating cutaneous branches of internal mammary artery to the 2nd, 3rd and 4th intercostal spaces—60%.
- ♦ The lateral branch of the 2nd, 3rd and 4th intercostal arteries.
- ♦ Pectoral branches of acromiothoracic artery.
- ♦ Superior thoracic artery.

Venous Drainage

- ♦ The superficial veins from the breast characterised by their proximity to the skin drain to the axillary, internal mammary, and intercostal vessels.
- ♦ Phlebitis of one of these superficial veins feel like a cord immediately beneath the skin—***'Mondor's disease'.***
- ♦ Through posterior intercostal veins, venous drainage communicates with paravertebral venous plexus (*Batson's venous plexus*). So secondaries in vertebrae, is common in carcinoma of breast.

Nerves-related (During MRM)

- ♦ Long thoracic nerve—*Bell* supplies serratus anterior.
- ♦ Thoracodorsal nerve supplies latissimus dorsi.
- ♦ Medial pectoral nerve (from medial cord of brachial plexus) which lies *lateral,* runs and winds from lateral margin of pectoralis minor.
- ♦ Lateral pectoral nerve arises from lateral cord passes through the pectori either middle or medial part.
- ♦ Intercostobrachial nerve is communicating nerve between lateral cutaneous branch of 2nd intercostal nerve and medial cutaneous nerve of arm; denervation of this nerve causes sensory loss of skin over upper medial and inner aspect of the arm, apex and lateral axilla.

Nerve supply of breast is by anterior and lateral cutaneous branches of 4th to 6th intercostal nerves.

Milk secretion is brought by prolactin hormone from anterior pituitary—not by nerves.

Lymphatic Drainage of the Breast

Commonly into the axillary lymph nodes—75%.

1. Anterior group (pectoral, external mammary)—along lateral thoracic vessels. Main drainage node.
2. Central group—next common node. It is the node most easily properly clinically palpable in axilla.
3. Posterior group (subscapular)—rare to involve in carcinoma.

4. Lateral group—along axillary vein; rare to involve in carcinoma.
5. Interpectoral node *(Rotter's node)*—signifies the retrograde spread of tumour. It lies between pectoralis major and minor.
6. Apical. They are 4-6 nodes, also called as subclavicular or *Halsted nodes*. It lies most superior and deep to pectoralis minor medial to axillary vessels.



Fig. 8.8: Surgical levels of lymph nodes in the axilla draining the breast.

Later they drain into supraclavicular lymph nodes. 25% drains mainly from medial half of the breast into 2nd, 3rd and 4th intercostal space internal mammary lymph nodes. *Internal mammary nodes* are located in retrosternal intercostal spaces 1-2 cm lateral to the sternal margin; it is vertically placed parallel to internal mammary vessels in relation to endothoracic fascia; its efferent ends in subclavicular nodes.

Drainage into contralateral axilla and opposite lymph nodes also occur.

The concept of Sappey's subareolar drainage of lymph centripetally is not well accepted now.

Axillary reverse mapping (ARM): Here blue dye is injected into upper part of inner aspect of the arm to achieve a mapping of axillary lymphatic drainage.

Levels of the axillary nodes (Berg's levels)

- **Level I :** Below and lateral to the pectoralis minor muscle—anterior, lateral, posterior
- **Level II :** Behind the pectoralis minor muscle—central
- **Level III :** Above and medial to pectoralis minor muscle—apical

Note in carcinoma breast

- Spread restricted to level I nodes carries better prognosis
- Spread to level II has poor prognosis
- Spread to level III indicates worst prognosis

MAMMOGRAPHY

It is a plain X-ray of soft tissue of breast using low voltage and high ampearage X-rays. Two films are taken.

1. *Craniocaudal* from above downward.
2. *Mediolateral* from side to side.

Dose of radiation is 0.1 Gy, a low dose. So it is a safe and effective procedure.



Fig. 8.9: Mammography showing calcified lactiferous duct with a benign lesion.

Findings

- Microcalcifications signify malignancy. They are < 0.5 mm, pleomorphic/heterogenous, grouped, fine, linear and branching.
- Soft tissue shadow may be smooth, round/oval and regular in benign conditions or irregular in carcinomas. Lobulated mass is also suggestive of carcinoma.
- Size and location of mass lesion.
- Spiculations, duct distortion—features of malignancy.
- Margin may be circumscribed (benign lesion), microlobulated, obscure, ill-defined, spiculated or stellate.



Fig. 8.10: Different mammography pictures, craniocaudal and mediolateral films showing mass lesion, microcalcification (*Courtesy:* Dr Ganesh, MDRD, Mangalore).

Breast imaging reporting and data system (BIRADS)

Grade	Feature
0	Need further imaging
1	Negative
2	Benign—repeat mammography 1 year
3	Probably benign—mammography after 6 months
4	Suspicious of carcinoma—biopsy
5	Highly suggestive of carcinoma—biopsy
6	Known carcinoma

Indications

- *Screening mammography:* For screening purpose it is done after 40 years. Early screening is indicated when there is family history of carcinoma breast or histological risk factor. Mammography before 35 years of age is usually not done unless there is a suspicious lump or a strong family history. Screening is done in asymptomatic female where even cancer is suspected.
- *Diagnostic mammography* is done in a patient to evaluate the existing symptoms/features of breast disease like breast lump, nipple discharge; or in patient who had breast conservative surgery earlier.
- In obese patients.
- Whenever conservative breast surgeries are planned.
- To find out spread or de novo tumour in the opposite breast.
- Mammography guided biopsy can be done.
- Evaluation and follow-up in benign breast disease with malignant potential.
- Follow-up mammography after conservative breast surgery (of operated side and opposite side when needed.
- Mastalgias.

***Note*:**

- 5% of breast cancers are missed in total mammograhic screening.
- Breast imaging reporting and data system (BIRADS) have got its own categories, assessment (0-6) and recommendations.
- Digital mammography is computerised electronic image of the breast with enhanced magnified pictures.
- Digital spot-view mammography allows faster and more accurate stereotactic biopsy.
- The condition when lump is clinically not palpable but mammogram shows identifiable carcinoma is ideal for breast conservative surgery like quadrantectomy/QUART therapy.

Xeromammography is same as above, but here a photoconductor is used to produce a final image on a Selenium paper rather than on X-ray film.

Advantages: Edge enhancement effect, therefore, useful in dense breasts.

Disadvantage: Exposure to high radiation dose and selenium plates are needed.

ABERRATION OF NORMAL DEVELOPMENT AND INVOLUTION (ANDI) OF THE BREAST

ANDI includes variety of benign breast disorders occurring at different periods of reproductive periods in females—early, matured and involution phase of reproductive age group. It was first coined at Cardiff breast clinic in 1987 by LE Hughes. All conditions under ANDI should be carefully clinically examined and often mammography and FNAC/core cut biopsy should be done to rule out malignancy. ANDI includes different aberrations and diseases.

It is based on change in *normal three phases* of physiology of breast—(1) Lobular development; (2) Cyclical hormonal modifications; (3) Involution.

In early reproductive age group (15-25 years):

- Normal lobule formation may cause aberration as *fibroadenoma*. If it is more than 5 cm it is called *as giant fibroadenoma* as a *diseased status*. It is AND of a lobule.
- Normal stroma may develop juvenile hypertrophy as aberration and multiple fibroadenoma as *diseased status*.

In mature reproductive age group (25-40 years):

- Normal cyclical hormonal effects on glands and stroma get exaggerated by aberration causing generalised enlargement. Its *diseased status* is cyclical mastalgia with nodularity also called as *fibrocystadenosis.*

Involution age group (40-55 years):

- *Lobular involution* with microcysts, fibrosis, adenosis, apocrine metaplasia and eventual aberrations as macrocysts and cystic disease of breast. Macrocyst is an aberration of normal involution (ANI). Sclerosing adenosis is also a type of aberration.
- *Ductal involution* may cause ductal dilatation and nipple discharge as aberration. Later disease status develops with periductal mastitis, bacterial infection, nonlactational breast abscess and mammary duct fistula. Periductal fibrosis may cause partial nipple retraction.
- *Epithelial changes* leads into epithelial hyperplasia and atypia.

FIBROADENOMA

- It is a benign encapsulated tumour occurring commonly in young females of 15-25 years age group.
- Presently it is considered as hyperplasia of a single lobule of the breast (classified under ***ANDI***).
- It is the most common benign tumour of the breast below 30 years of age in females.
- It is aberration in normal development (AND) of a lobule.
- It shows similar hormonal activities of normal breast like lactation, perimenopausal involution.
- Incidence is 15% of palpable breast lumps. It is common in blacks and Negroes.
- It is bilateral in 20% of cases. 20% are multiple.

- *Juvenile fibroadenoma* occurs in adolescent girls, rarely (variant). Even though it shows rapid growth with stromal and epithelial hyperplasia, it does not show any alteration in stromal epithelial balance or cellular atypia or periductal cellular concentration. It may clinically mimic phyllodes tumour. But it does not turn into phyllodes tumour or carcinoma.
- *Complex fibroadenoma* (*Dupon et al)* is a condition (variant) having typical fibroadenoma with fibrocystic changes like apocrine metaplasia, cyst formation, sclerosing adenosis. 15% of proven fibroadenomas are complex. It occurs in older age group. *Occasionally* it may turn into malignancy unlike usual fibroadenomas. *Core biopsy* is needed to confirm the condition.
- 30% of fibroadenomas may disappear or reduce in size in 2-4 years.
- 10 -15% will increase in size progressively. It does not occur after menopause unless women are on hormones.
- Fibroadenoma *does not* turn into malignancy.

Types

Gross:

1. Soft—common after 30 years; more cellular; often bilateral.
2. Hard—common below 30 years; more fibrous.
3. Giant (> 5 cm in size)—common in Africa.

Microscopy:

1. Intracanalicular—large and soft—mainly cellular. Stroma with distorted duct.
2. Pericanalicular—small and hard—mainly fibrous. Stroma with normal duct.



Fig. 8.11: Fibroadenoma, on table look—well-capsulated neoplasm. It is part of ANDI.

Clinical Features

- It presents as a painless swelling in one of the quadrants, which is *smooth, firm, nontender, well-localised and moves freely* within the breast tissue (mouse in the breast).
- Axillary lymph nodes are not enlarged.



Fig. 8.12: US picture showing fibroadenoma left breast.



Fig. 8.13: Large fibroadenoma left breast in a 14-year-old female.



Fig. 8.14A



Fig. 8.14B

Figs 8.14A and B: Multiple fibroadenomas.



Figs 8.15A and B: Subareolar and submammary incision to excise benign lesions of the breast.

Investigations

- Mammography (well-localised smooth regular shadow).
- FNAC.
- Ultrasound (to confirm solid nature).

Treatment

Excision through a circumareolar incision (*Webster's*) or submammary incision (*Galliard Thomas incision*) is done under general anaesthesia.

Fibroadenoma which is small (< 3 cm)/single/age < 30 years can be left alone with regular follow-up with USG at 6 monthly interval. But anxiousness of patient and parents find difficult for this conservative approach.

Indications for surgery are:

- Size > 3 cm.
- Multiple.
- Giant type.
- Recurrence.
- Cosmesis.
- Complex type.

Points to be remembered

- *Size of giant duodenal ulcer is > 2 cm*
- *Size of giant gastric ulcer is > 3 cm*
- *Size of giant fibroadenoma is > 5 cm*
- *Diameter of transverse colon in toxic megacolon is > 6 cm*
- *Size of giant naevus is > 20 cm*



Fig. 8.16: Diagram showing circumareolar and submammary (*Galliard Thomas*) incisions.

FIBROCYSTADENOSIS (FIBROCYSTIC DISEASE OF THE BREAST/MAMMARY DYSPLASIA/CYCLICAL MASTALGIA WITH NODULARITY)

- It is due to **A**berration of **N**ormal **D**evelopment and **I**nvolution (***ANDI***) of breast causing.
- It is presently called as *cyclical mastalgia with nodularity.*

Microscopic changes

- Stromal fibrosis
- Microcyst formation
- Glandular proliferation (Adenosis)
- Hyperplasia (Epitheliosis)—in ducts and acini
- Papillomatosis—within the ducts, often with apocrine metaplasia

- It is an estrogen dependent condition. One of the cysts may get enlarged to become a clinically palpable, well-localised swelling—*bluedome cyst of Bloodgood.* It is fluctuant, transilluminant, nontender, often tensely cystic swelling (macrocyst) with thin bluish capsule. It should be aspirated initially. Surgical excision is done if it persists or recurs even after two aspirations; if it is blood stained; if there is residual lump after aspiration.
- When diffuse small, multiple cysts are the main component, it is called as *Schimmelbusch's disease.*
- *It is the most common breast disease.*
- It is common in upper and outer quadrant.
- It is an exaggerated response of breast stroma and epithelium to hormones and growth factors.
- It is rare in nulliparous/ovulating/OCP taking women.

Classification

- *Nonproliferative—moderate hyperplasia of ductal luminal cells*—no life time risk for cancer.
- *Proliferative without atypia (severe hyperplasia).*
- *Proliferative with atypia (Atypical ductal/lobular hyperplasia)*—is risk factor for breast cancer—often mimics *in situ* carcinoma. RR is 4.5.

Usual hyperplasia is presence of 3 or more layers of proliferating epithelial cells without atypia above the basement membrane in a lobular or ductal unit. It can be mild, moderate or florid. It is seen in 20% of biopsies. Risk of developing cancer is 1.5 times. Observation of such patient is the advice.

Atypical ductal hyperplasia (ADH) is defined as a lesion that has got some but not all features of DCIS; a lesion that has all features of DCIS but less than 2 mm in size; lesion with all features of DCIS but involving less than 2 duct spaces. It is incidence is 30% of all mammographies and 5% of benign breast disease biopsies. Risk of developing cancer is 5 times the normal women of that age.

Atypical lobular hyperplasia (ALH) is LCIS with half of the acini of lobular unit is involved. Developing invasive carcinoma in 10 years is 20%.

Stages

I—Stromal proliferation or hyperplasia.
II—Adenosis (increased glands).
III—Cyst formation.

Pathophysiology of fibrocystadenosis

- Oestrogen predominance over progesterone is considered causative
- Serum levels of oestrogen ≥
- Luteal phase is shortened
- Progesterone level decreased to 1/3rd normal
- Corpus luteum deficiency/anovulation in 70%
- Patients with premenstrual tension syndrome more likely to develop fibrocystadenosis
- Prolactin levels are increased in 1/3rd of women with fibrocystadenosis. It is probably due to oestrogen dominance on pituitary
- Thyroid in suboptimal levels sensitize mammary epithelium to prolactin stimulation
- Methylexanthiones derived from increased intake of coffee, tea, cold drinks, chocolate is associated with development of fibrocystadenosis
- Oestrogens stimulate proliferation of connective and epithelial tissues
- Fibrocystadenosis entails simultaneous progressive and regressive change

Clinical Features

- Presentation is during menstruating age group as a *bilateral, painful, diffuse, granular, tender, swelling* which is better felt with palpating fingers (poorly felt with palm).
- Common in upper outer quadrant.
- Pain and tenderness are more just prior to menstruation *(cyclical mastalgia).*
- It subsides during pregnancy, lactation and after menopause.
- Discharge from the nipple when present will be serous or occasionally greenish.
- Occasionally shotty enlargement of axillary lymph nodes can occur (20%).
- Not fixed to skin, muscle or chest wall.

Investigations

- FNAC (Epitheliosis, when florid is undoubtedly premalignant).
- Ultrasound.
- Mammography.

ANDI was coined by Cardiff breast clinic.

Treatment

I. *Conservative line of management* is preferred.
  1. *Reassurance,* avoid caffeine, chocolate, salt.
  2. *Medical (Drugs)*
    - Goal:
      - To stop progression.
      - To relieve pain.
      - To reverse changes.
      - To soften breast tissue.
    - Indicated when:
      - Fibroadenosis is not increasing in size.
      - No nipple discharge especially blood.
      - No psychological effect.

Drugs are:

- *Oil of evening primrose* used in moderate pain—*drug of choice*. It contains gamolenic acid which reverses saturated to unsaturated fatty acids. 1000-3000 mg/day for 4-6 months—but costly. It also contains 7% of linolenic acid and 72% of linoleic acid.
- Gamolenic acid—120 mg/day.
- Danazol—interferes with FSH and LH (gonadotrophin releasing hormone inhibitor); *most effective drug*; but *second drug of choice*; used in severe cases; 200 mg/day; very effective but causes acne, hirsutism, weight gain and amenorrhoea. It is teratogenic and so cannot be used if patient is planning for pregnancy.
- Bromocriptine—lowers prolactin—2.5 mg/day for 3 months.
- Tamoxifen—10 mg BD is an antiestrogenic drug.
- LHRH agonist (Goserelin) is *reserved for refractory cases*. It shows 96-99% success. But it causes reversible postmenopausal symptoms.
- Vitamin E and B_6 are tried.
- NSAIDs—oral and topical.
- Diuretics even though used by many—*not effective.*

II. *Surgery*:

- Subcutaneous mastectomy with prosthesis placement—only in severe, persistent disease.
- Excision of the cyst or localised excision of the diseased tissue.

Indications for surgery

- Intractable pain
- Florid epitheliosis—on FNAC
- Blood good cyst
- Persistent bloody discharge
- Psychological reason

***Note*:**

- *Subcutaneous mastectomy* is removal of entire breast with retaining skin over the breast, areola and nipple. It is done through a submammary Galliard Thomas incision. Adequate skin flap containing subcutaneous fat is raised which maintains the blood supply of the flap and prevents flap necrosis. After haemostasis drain is placed. Breast implant can be placed in subcutaneous/submuscular plane either immediately or as delayed reconstruction. Indications for subcutaneous mastectomy are—fibrocystadenosis with epitheliosis, sclerosing adenosis, persistent nodules, gynaecomastia and DCIS.
- *Macrocysts* (>1 cm) is an advanced form of fibrocystic disease; occurs in women in their forties and pericystic fibrosis develops later making cyst harder.

SCLEROSING ADENOSIS

Known cause of breast lump.

Features

- Occurs in 30-50 years of age.
- Patient may present as breast lump or mastalgia.
- On palpation—it is smooth, relatively mobile mass.
- It can mimic carcinoma clinically, radiologically and histologically.
- It contains proliferative terminal ductules and acini with proliferation of stroma often with deposition of calcium.
- Number of acini per terminal duct is increased more than double the number of normal lobule.
- *Complex type* is with papilloma and epithelial hyperplasia. Radial scar is variant of this.
- No risk of malignancy.
- It is included under ANDI.
- Treatment is like ANDI.

Histology

- Lobular enlargement and distortion.
- Fibrous stromal proliferation.

PHYLLODES TUMOUR (CYSTOSARCOMA PHYLLODES/SEROCYSTIC DISEASE OF BRODIE)

- They are not simply giant fibroadenoma.
- They show a wide spectrum of activity, varying from almost a benign condition (85%) to a locally aggressive and sometimes metastatic tumour (15%).
- Depending on mitotic index and degree of pleomorphism they are graded as low grade to high grade tumours.
- When malignant (sarcoma) spreads to lungs or bone.

Gross: Large capsulated area with cystic spaces and cut surface shows soft, brownish, cystic areas.



Fig. 8.17: Cystosarcoma phyllodes of right breast. Note the dilated veins. Tumour occupies the entire breast.

Microscopy:

- It contains cystic spaces with leaf like projections, hence the name (*Phyllodes*—Greek—leaf-like).
- Cells show hypercellularity and pleomorphism.
- It may be a variant of intracanalicular fibroadenoma of breast (*Giant type*).

Clinical Features

- They occur in premenopausal women (30-50 years).
- It is usually unilateral, grows rapidly to attain a large size with *bosselated* surface.
- Swelling is *smooth, nontender, soft, fluctuant with necrosis of skin* over the summit due to pressure.



Fig. 8.18: Phyllodes tumour of left breast (Cystosarcoma phyllodes of left breast).



Fig. 8.19: Operated specimen of cystosarcoma phyllodes.

- Skin over the breast is stretched, red and with dilated veins over it. Tumour is warmer, not fixed to skin or deeper muscles or chest wall. Nipple retraction is absent. Lymph nodes are usually not involved. These are the *differentiating features* from carcinoma.
- Tumour grows rapidly; undergoes necrosis at various places; causes cystic areas.
- Recurrence is common.



Figs 8.20A and B: Recurrent cystosarcoma phyllodes.

Investigations

- U/S.
- FNAC, core biopsy
- Mammography.
- Chest X-ray CT chest in malignancy to see secondaries.

Treatment

- Excision or subcutaneous mastectomy is done.
- If malignant (sarcoma), total mastectomy is indicated.

MASTALGIA (“Pain in the Breast”)

- 45% of women report breast pain, 21% severe.
- An entity that is ubiquitous; has an unknown aetiology, and a poorly understood.
- Mastitis, carcinoma presenting with only mastalgia (8%).
- Patients who are on HRT, caffeine, tobacco, large pendulous breasts, etc.

Types

- Cyclical—65%.
- Noncyclical—30%.
- Chest wall pain—5%.

Saying ‘no’ to something is actually much more powerful than saying ‘yes’. — **Tom Hanks**

Cyclical

- Pain related to menstrual cycles.
- Usually seen in ANDI like fibrocystadenosis.
- Present in women of menstruating age group.
- Pain is more during menstruation.
- It is bilateral, diffuse with "heavy feeling".

Treatment:

- Evening primrose oil 325 mg BD.
- Gamolenic acid 120 mg BD.
- Danazol (100-200 mg BD)—antigonadotrophin agent.
- Bromocriptine (2.5 mg BD)—prolactin inhibitor.
- Tamoxifen (20 mg daily).
- GnRH analogue 3.6 mg injection depot-monthly.
- Testosterone undecanoate 40 mg BD.
- Vit B_6, B_{12}.
- Analgesics.

Noncyclical

- Other causes of breast pain are periductal mastitis, malignancy, cervical root pain, musculoskeletal pain, previous surgery, Tietze's syndrome.
- It is unilateral, chronic, burning or dragging in nature, occurs both in pre- and postmenopausal age group.
- 5% of breast cancers present as pain during first presentation.

Treatment:

- Cause has to be identified.
- Malignancy has to be ruled out.
- Avoid coffee and stress.
- Proper support to breasts.

Tietze's syndrome:

Costochondritis of second costal cartilage, commonly seen in females, mimics mastalgia.

TRAUMATIC FAT NECROSIS

It may be due to either direct or indirect trauma (trauma may not be noticed many times).

Pathogenesis

Capillary ooze causes triglyceride in the fat to dissociate into fatty acids. It combines with calcium from the blood resulting in *saponification* which causes inflammatory reaction and later presents as a nonprogressive swelling in the breast.

Clinical Features

- Painless swelling in the breast which is *smooth, hard, nontender and adherent* to breast tissue.
- It is nonprogressive, nonregressive.

Investigations

- FNAC shows chalky fluid with fat globules.
- Mammography to rule out malignancy.

Differential Diagnosis

- Carcinoma breast.



Figs 8.21A and B: Traumatic fat necrosis.

Treatment

- Excision.

GALACTOCELE

- Seen in lactating women.
- Occurs during cessation of lactation. Often up to 10 months after lactation.
- It is due to the blockage of lactiferous duct resulting in enormous dilatation of lactiferous sinus.
- It contains milk and epithelial debris within.
- It is a retention cyst in subareolar region attaining large size.

Clinical Features

- Lump in the lower quadrant of the breast which is usually *unilateral, large, soft, fluctuant, with smooth surface.*
- It is usually nontender.

- It may get *precipitated, inspissated* or get *calcified*. When it is calcified it mimics carcinoma breast. If it gets infected it will form an abscess.
- When it is cystic other cystic swelling in the breast should be ruled out.



Fig. 8.22: Galactocele.

Investigations

- U/S.
- FNAC. Aspiration shows thick, creamy, greenish/brown fluid.

Treatment

- Aspiration of the content.
- Excision (submammary incision).
- Abscess when formed should be drained under general anaesthesia under cover of antibiotics.

MASTITIS

Types



Fig. 8.23: Diagram showing subareolar, intramammary and retromammary abscess.

1. Subareolar.
2. Intramammary.
3. Retromammary (submammary).

Subareolar Mastitis

- It is the infection under the areola due to cracks in the nipple or areola. It results from an infected gland of Montgomery or a furuncle of the areola.
- Often it is associated with duct ectasia—causing formation of abscess, sinus and fistula.
- It is common in nonlactating women.



Fig. 8.24: Severe infection caused sloughing of the skin and breast tissue, eventually granulating and is ready for graft.



Fig. 8.25: Subareolar abscess.

Clinical features

- Red, inflamed, edematous areola with a tender swelling underneath.
- Nipple retraction may develop.

Differential diagnosis

Paget's disease of the nipple.

When arms are raised fully above the head, visible signs of breast carcinoma frequently becomes more apparent.
—Hugh Auchincloss

Treatment

- Under cover of antibiotics pus is drained by making a subareolar incision.

Intramammary Mastitis (Breast Abscess)

a. Lactational abscess of the breast:
Commonly seen in lactating women. Usually up to 6 months of lactation period. It occurs in 3% of breastfeeding mothers.

Precipitating factors

- Cracked nipple
- Retracted nipple
- Improper cleaning of the nipple
- Inadequate milk sucking by baby or milk expression causing stasis
- Infection from the mouth of the baby
- Haematoma getting infected

Mode of infection:

Bacteria (*Staph. aureus*—most common) enters the breast during sucking through the cracked nipple. Occasionally it can be from haematogenous spread. Gram-negative and other bacterial infections can supervene later.

Staphylococcus aureus causes clotting of milk in the blocked duct and multiply. Duct initially gets blocked by epithelial debris or by retracted nipple. Initially it begins in one quadrant but later involves entire breast.

Clinical features:

- Continuous throbbing pain in the breast and high grade fever.
- Diffuse redness, tenderness, warmness and *brawny induration* in the breast.
- Purulent discharge from the nipple.
- Entire breast may get involved eventually.
- Occasionally tender fluctuant swelling (10%) may be felt; ulceration and discharge can occur at a later period.
- It is difficult to differentiate initial *stage of mastitis* (stage of cellulitis) from *stage of breast abscess* formation. When it is treated by a ntibiotics without incision and drainage eventually it may get organised to form a nontender, hard breast lump with sterile pus inside—*stage of antibioma* formation.

Differential diagnosis:

Inflammatory carcinoma of breast.



Figs 8.26A to D: Typical breast abscess with features of acute inflammation. Drain should be placed after incision and drainage in such abscesses. Often gauze drain can be used.



Fig. 8.27: Breast abscess in a male patient. Breast abscess eventhough is uncommon in males, it can occur in puberty and middle age.

Treatment:

- Antibiotics—cephalosporins, flucloxacillin and amoxicillin.
- *Repeated US guided aspirations* can be tried which avoids surgery and scar.
- Drainage under general anaesthesia, *a counter incision* may be needed.

It is not advisable to wait till the formation of abscess.

Often takes very long time to heal after surgery causing distress to patient and surgeon as well.

Indications for drainage in mastitis/breast abscess

- Mastitis not resolving with antibiotics in 48 hours
- Persistent fever and progression of mastitis
- Brawny induration

Do not wait for abscess to form (fluctuation to develop)

Complications:

- Antibioma formation.
- Sinus formation, skin necrosis, fistula formation.
- Recurrent infection, bacteraemia, septicaemia.

Suppression of lactation is often required by giving Bromocryptine 2.5 mg BD for 2 weeks.

***b. Nonlactational abscess of the breast*:**

It commonly occurs in duct ectasia and periareolar infections. Common organisms are *bacteroides, anaerobic streptococci*, enterococci and gram negative organisms. It is *commonly recurrent* with tender swelling under the areola.

Treatment:

- Antibiotics.
- Repeated aspirations.
- Drainage and later cone excision of the duct is done.

Retromammary Mastitis

- It is due to tuberculosis of the intercostal lymph nodes or ribs beneath or suppuration of the intercostal lymph nodes.
- Breast is normal.



Fig. 8.28: Incision and counter-incision for breast abscess.



Fig. 8.29: Photograph showing placement of drain in breast abscess.

Causes

- Tuberculosis of intercostal lymph nodes
- Tuberculosis of ribs beneath
- Suppuration of intercostal lymph nodes
- Empyema necessitans
- Infected haematoma

Transillumination in a case of duct papilloma may reveal an opacity in the line of the duct due to pent-up blood.
—William J Moore

Investigations:

- Chest X-ray, FNAC, ESR.
- Peripheral smear.
- U/S of breast and chest wall.
- Often CT scan chest may be needed.

Treatment:

- Cause has to be treated.
- Drainage through submammary/retromammary incision.

***Note*:**

- Mastitis of infancy (*Witch's milk*) is due to maternal hormone in infant blood. It usually subsides but may cause suppuration.
- Mastitis of infancy affects both sexes equally.
- Mastitis of puberty is common in boys, is invariably unilateral with tender, swollen and inflamed breast.
- Mastitis of mumps is usually unilateral and can occur in both sexes.
- Bacterial mastitis is seen in adult women, commonly lactating and is due to staphylococci infection.
- Subareolar mastitis is due to infection of gland of Montgomery or due to areolar furuncle.

ANTIBIOMA

If intramammary mastitis is not drained but only treated by antibiotics, pus localises and becomes sterile (flaques) with a thick fibrous tissue cover and it is called as antibioma.

Clinical Features

- Previous history of mastitis treated with antibiotics.
- Swelling which is painless, smooth, nontender, hard, fixed to breast tissue without involving the pectorals and chest wall.

Differential Diagnosis

Carcinoma breast (Scirrhous carcinoma breast).

Investigations

- FNAC; mammography; U/S breast.

Treatment

Excision (Submammary incision). Later antibiotics are given. It should be sent for histology.

DUCT ECTASIA

- It is dilatation of lactiferous ducts due to muscular relaxation (myoepithelial relaxation) of duct wall with *periductal mastitis*.
- It is also called '*plasma cell mastitis*' as periductal inflammation contains plasma cells.
- Commonly many ducts are involved.
- Hormonally induced myoepithelial relaxation with poor ductal absorption of secretions and desquamated cells causing obstruction are the probable other causes and features.

Clinical Features

- Greenish discharge or *creamy/paste* like from the nipple.
- Indurated mass under the areola which is often *tender*.
- Retraction of nipple which occurs at later stage of the disease. *Slit like retraction of nipple* due to fibrosis occurs.
- Eventually it forms an *abscess* and *fistula*.
- Often they are bilateral and multifocal.
- *More common* in smokers—in relation to arterial pathology.
- Common in multiple pregnancies, *perimenopausal age*, hyperprolactin status.
- May present as mastalgia.
- Axillary nodes may be palpable as nonspecific.
- Secondary bacterial infection (anaerobic) is common.

Differential Diagnosis

Carcinoma breast.

Investigations

- Discharge study, FNAC.
- Mammography.



Fig. 8.30: Duct ectasia—ductography.

Treatment

- It is important to stop smoking.
- Cone excision of involved major ducts (*Adair-Hadfield operation*).
- Antibiotics.
- *Melhem Novel modified* breast ductal system excision.

MONDOR'S DISEASE (Henri Mondor—Paris, 1939)

- Mondor's disease is *spontaneous* thrombophlebitis of the superficial veins of the breast and anterior chest wall.
- Cause is not known. History suggestive of injury or infection is not observed.
- Presents as a thrombosed subcutaneous cord (2-3 mm sized) which is attached to the skin.
- On raising the arm above, a narrow, shallow subcutaneous groove appears alongside the cord like thrombosed vein.
- The thoracoepigastric vein, the lateral thoracic vein, and the superior epigastric vein—are involved. The upper, inner portions of the breast are never involved.
- Trauma, infection, surgery may be the cause but clearly not proved and so controversial.

- Rarely penile Mondor's disease and Mondor's in the arm are observed.
- It is often a self-limiting disease without any recurrence, complication or deformity.
- It often mimics the lymphatic permeation of carcinoma breast.
- Restriction of arm movements, brassiere support and anti-inflammatory drugs may be needed. Occasionally refractory cases need surgical excision of involved segment of vein.

TUBERCULOSIS OF THE BREAST

- It is relatively rare. Even though it is rare, often seen in India (4% of benign breast diseases). It may be due to high resistance offered by mammary gland tissue to the survival and multiplication of the tubercle bacillus, a resistance similar to that offered by spleen and skeletal muscle.
- Usually associated with active pulmonary tuberculosis.
- Infection reaches through blood or retrograde lymphatic spread from lymph nodes of axilla.
- Common in lactation.
- Nipple and areola are *not commonly* involved.
- *Lump*—irregular ill-defined; peaud' orange; discharge, sinus, matted axillary nodes often with sinus are the features.
- Presents as a swelling in the breast with cold abscess, sinuses and a typical bluish appearance of surrounding skin with matted lymph nodes in the ipsilateral axilla.



Fig. 8.31: Tuberculosis of breast showing undermined lesion.

Differential Diagnosis

Carcinoma breast.

Investigations

- FNAC.
- Frozen section biopsy is useful to differentiate from carcinoma.
- Excision biopsy.

Treatment

- Antituberculous drugs—INH, rifampicin, ethambutol, pyrazinamide.
- Drainage of cold abscess.

Note:

- Mastectomy is not done.

BREAST CYSTS

- They are cavities lined by epithelium in the breast containing fluid. It arises from destruction and dilatation of breast lobule and terminal ductules. It is due to nonintegrated stromal and epithelial involution.
- Cyst may be microscopic or macroscopic. It contains straw coloured or green or opaque fluid.
- Incidence is very high (1 in 14 females). It is common after the age of 35 years up to menopause. It is uncommon after menopause. Hormone replacement can cause cyst formation in old women.
- Cyst size varies with menstruation due to influence of ovarian hormones.
- Cysts can be multiple (50%). Often bilateral.
- Cysts can be recurrent (50%).
- Risk of breast cancer in breast cyst is very less (0.1%). But incidental associated carcinoma may be present in 3% of breast cysts.
- *Clinically*—smooth, soft, fluctuant often transilluminating well-localised swelling may be felt.
- *Differential diagnoses* are—*Bloodgood cyst*, haematoma, cystic necrosis in a carcinoma, Brodie's disease, galactocele, lymph cyst, hydatid cyst.
- *Investigations*—US of breast; FNAC. Mammography to rule out associated carcinoma.

Treatment

- Aspiration for *two* times.
- Surgical excision is done if cyst *recurs* after two aspirations or if there is *bloody* discharge or *residual mass* if felt after aspiration.



Fig. 8.32A

In the presence of troubles some people grow wings; others buy crutches.



Fig. 8.32B

Figs 8.32A and B: US look of breast cysts—simple and complex type.



Fig. 8.33: Retention cyst in areola.

Cystic swellings of the breast

- Bloodgood cyst
- Breast abscess
- Hydatid cyst
- Galactocele
- Serocystic disease of Brodie
- Cystic necrosis in carcinoma breast
- Lymph cyst
- Haematoma in breast

GALACTORRHOEA

- It is secretion of milk not related to pregnancy or lactation.
- It is always bilateral.

Primary galactorrhoea is due to:

- Stress and other factors. It is physiological in puberty or menopause. Reassurance is the treatment.

Secondary galactorrhoea is due to:

- Dopamine receptor blocking agents like haloperidol, methyldopa, chlorpromazine, metoclopramide or by hyperprolactinaemia due to pituitary tumours. It enhances the prolactin activity.
- Hypothyroidism.
- Drugs like oral contraceptives, atenolol, clonidine, ranitidine.
- Ectopic prolactin secreting tumours usually from lungs (bronchogenic carcinoma).
- Chronic renal failure.

Management

- Estimation of serum prolactin, T3, T4, TSH, CT/MRI head.
- Bromocriptine therapy.
- Treatment of cause. Causative drug should be stopped and different drugs should be used for the needed condition.

Note:

Witch's milk is secretion of milk in both male and female infants due to maternal hormonal effects in foetus. It lasts up to three weeks after child birth.

GYNAECOMASTIA (Greek—Women Breast)

- It is hypertrophy of male breast more than usual due to increase in ductal (epithelial) and connective tissue (stromal) elements often attaining features of female breast.
- It can be unilateral or bilateral. Bilateral can be symmetrical or asymmetrical.



Fig. 8.34: Gynaecomastia—right side breast (diffuse type). Compare with opposite side to note the difference in size.

- It is nonphysiological *stimulatory* oestrogen excess or *inhibitory* androgen deficiency. There is nonphysiological hypertrophy of male breast attaining the size of female breast with increase in connective and ductal tissues.
- It can be *diffuse*—involving all quadrants or small *well localised* hard subareolar nodule.



Fig. 8.35: Right-sided gynaecomastia (well-localised—puffy nipple).

Etiology

- *Oestrogen excess*—increased estradiol secretion due to testicular tumour (*Leydig* cell) or nontesticular tumours from adrenal cortex, lung, liver; hyperthyroidism (increases conversion of androgen to estrogen), liver diseases, oestrogen therapy for prostate cancer.
- *Androgen deficiency*—aging, *Klinefelter's/Kallmann syndromes*, eunuch, ACTH deficiency.
- *Secondary testicular failure*—cryptorchidism, orchitis, trauma, CRF, etc.
- *Drugs* (25%):
  - Increases estrogen activity (digitalis, anabolic steroid)/estrogen synthesis (reserpine, theophylline, frusemide).
  - Inhibition of testosterone synthesis—cimetidine, phenytoin, spironolactone.

Initially there will be *florid proliferative stage* of ductal epithelium with oedematous stroma without acini (1 year); later there will be *quiescent stage* with ductal dilatation and stromal fibrosis.

- Always one should examine genitalia and liver.
- It is physically *embarrassing;* psychologically *devastating.*

Types

- *Neonatal* gynaecomastia is due to action of placental estrogen
- *Pubertal* (25%) in young boys is due to excess estrogen level in relation to testosterone. It is usually unilateral. Here breast tissue will be more than 2 cm in diameter in nonobese young male
- *Senescent* in old is due to fall circulating testosterone causing elative hyperestrinism
- *Prepubertal*—may also be seen in girl child

It can be:

- Puffy nipples
- Pure glandular
- Adolescent hereditary
- Adult—most common
- Androgenic

Simon's classification of gynaecomastia:

Group 1 – Minor visible type without skin redundancy
Group 2 A– Moderate without skin redundancy
Group 2 B – Moderate with minor skin redundancy
Group 3 – Gross pendulous breast

Differential Diagnosis

- Pseudogynaecomastia—adipose tissue deposition as a part of obesity; needs liposuction.
- Pectoral muscle hypertrophy.
- Lipoma, dermoid, haematoma.

Presentations

- Diffuse enlargement of breast occupying all quadrants.
- Often well-localised, small, firm or hard nodule under the areola which is often painful and tender.

Causes

- Idiopathic—25%
- Teratoma testis—3%
- Ectopic hormonal production in bronchial carcinoma
- Anorchism, after castration
- Adrenal and pituitary disease
- Leprosy, because of bilateral testicular atrophy
- Drugs (25%): Stilbestrol, digitalis, cimetidine, spironolactone, INH, phenothiazides
- Liver diseases and liver failure—10%
- Klinefelter's syndrome (XXY Trisomy), Kallman syndrome
- Primary or secondary hypogonadism
- Hyperthyroidism
- Renal diseases, dialysis induced (1%)

Investigations

Relevant to the cause, e.g. liver function tests, DNA study, hormone assay, FNAC, USG breast.

Treatment

- Well-localised type which is symptomatic or patient is psychologically worried is treated by surgical excision using circumareolar incision.
- Large diffuse gynaecomastia needs *Galliard Thomas* submammary incision for excision.
- *Reduction mammoplasty;* nipple reduction surgeries.
- *Drugs*—tamoxifen, clomiphene, androgens (dihydrotestosterone), danazol, testolactone as aromatase inhibitor—but less useful. Drugs are given only for 6 months. Gynaecomastia more than 2 years duration is less likely to show benefit from drugs.

A man is not the best because he works hard, he works hard because he is the best.

- Breast irradiation to prevent gynaecomastia in prostatic cancer patients who are on oestrogen therapy.
- Causative drugs should be stopped.
- Testicular tumours, hyperthyroidism should be treated if they are the causes.
- Testosterone can be given if hypogonadism is the cause.
- Endoscopic assisted subcutaneous mastectomy is done and under trial mainly for cosmetic purpose.

***Note*:**

- Rarely gynaecomastia may turn into malignancy. Gynaecomastia is a differential diagnosis for male breast cancer.
- 80% of Klinefelter's syndrome shows gynaecomastia; it has got very high-risk (20 times) of developing carcinoma.

DUCT PAPILLOMA

- It is the most common cause of bloody discharge from nipple
- It is usually single, from a single lactiferous duct
- It blocks the duct causing ductal dilatation

- They are epithelium lined true polyps of breast lactiferous ducts.
- Usually it is < 1 cm in size often with a small lump under areola. But can attain large size.
- Vascular stalk is present usually.
- Rarely a cystic soft swelling may be present underneath which is probably due to obstruction of the duct by papilloma.
- Papilloma may often project out like a pedunculated mass.

Types

- Subareolar—common.
- Peripheral—occasional.
- Solitary—common.
- Multiple.
- Unilateral—common.
- Bilateral.

Clinical Features

- Papilliferous swelling (projection), usually seen near the nipple orifice.
- Blood stained discharge from the nipple is common.
- But serous or serosanguinous discharge can also occur.
- Single papilloma is not premalignant.
- But multiple papillomas in many ducts can be premalignant.
- Peripheral papilloma should be differentiated from invasive papillary carcinoma.

Investigations

- Discharge study (FNAC).
- Injection of contrast into the duct (Ductogram).
- Mammography may show dense lesion under the areola.



Figs 8.36A and B: Papilloma breast which is large. Usually it is small intraductal.



Fig. 8.37: Breast papilloma. It usually arises from single duct. It projects near the nipple orifice.

Treatment

Microdochectomy: Probed lactiferous duct is opened, and the papilloma is excised using *tennis racquet* incision.

Probing of lactiferous duct is done up to 5 cm deep and excised with part of the areolar skin.

Note:

- Intraductal papillary carcinoma arises usually not from a preexisting duct papilloma but as ***de novo***.
- *Papillomatosis* is hyperplasia of the duct lining, filling the duct like a polyp without a pedicle/stalk (not a true polyp); it is not duct papilloma but part of fibrocystadenosis.
- Axillary nodes are not involved.

ZUSKA-ATKINS DISEASE

- A condition considered mainly by pathologists. Squamous metaplasia causes plugging and obstruction of the ducts; subsequent inflammatory reaction and infection.
- Nipple retraction, recurrent episodes of infection and presence of painful nodules under the areola in a nonlactating woman is seen.
- The presence of a sinus draining milky discharge in the areola is characteristic.
- Seen in smokers—men or women. Vitamin A deficiency is also the cause.
- It can mimic carcinoma.
- Treatment is antibiotics and surgical excision like for duct ectasia.

MAMMARY FISTULA OF ATKINS

- It is a fistula of lactiferous duct which opens on to the areola.
- It causes recurrent abscess that points on to the areola which discharges and continues to discharge for a week.
- It is a differential diagnosis for carcinoma breast.

Treatment

- Antibiotics.
- Excision of fistula along with lactiferous duct.

CARCINOMA BREAST

> *When cancer occurs in the breast of women under forty, it is more rapid in its progress than when the patient is older, and also more extensive; remote sympathy likewise takes place more readily in them than in the old, so that the operation succeeds better in the latter on this account.*
>
> —**John Hunter**, 1728-1793

Aetiology

- Carcinoma breast is more common in developed, western countries.
- In African-American women, it is more aggressive. It is less common in Japan, Taiwan.
- It is second most common carcinoma in females. Incidence is 19-34%. Median age is 47 years.
- Carcinoma in one breast increases the risk of developing carcinoma on opposite breast by 3-4 times. Incidence of bilateral carcinoma is 2%.
- It is more common after middle age, but can occur at any age group, after 20 years.
- It can be familial in 2-5% cases.
- Mutation of tumour suppressor genes BRCA1/BRCA2 is thought to be involved with high-risk of breast carcinoma. BRCA1 mutation is having more risk (35-45%) than BRCA2 mutation. It is located in long arm of chromosome 17, whereas BRCA2 is located in long arm of chromosome 13. *BRCA1* more commonly shows *ER negative* status, high grade, aneuploid with raised S fraction than *BRCA2* which shows *ER positive* status. BRCA1 is associated with increased risk in males. Lifelong risk of breast cancer in BRCA1 and BRCA2 mutations is 50-70%. Both are associated with high-risk for ovarian cancer.
- Occasionally mutation of BRCA3 and p53 suppressor gene is also involved.
- *Li-Fraumen's syndrome* (LFS) is autosomal dominant condition with breast cancer inheritance (90%) along with sarcoma, leukemia, brain tumours, adrenocortical tumours.
- Diet low with phytoestrogens and high alcohol intake have high-risk of breast cancer. Vitamin C reduces the risk.
- It is more common in nulliparous woman.
- Attaining early menarche and late menopause have high-risk of breast malignancy.
- Early child-bearing and breastfeeding reduces the chances of malignancy. Early 1st child birth reduces the risk; late first child birth after 35 years increases the risk.
- It is more common in obese individuals.
- Breast cancer relative risk is qualified as relative risk (RR). If RR is 2.0 means, risk is twice the normal population. If RR is 0.5 means, risk is 50% less than normal population.
- Risk is 3-5 times more if 1st degree relative is having breast cancer. Risk is more if 1st degree relative is younger or premenopausal or having bilateral breast cancers.
- In males, occasionally gynaecomastia turns into carcinoma—not proved.
- Benign breast diseases with atypia, hyperplasia and epitheliosis has got higher risk in a patient with family history. RR in nonproliferative fibrocystic disease is 1.0; proliferative without atypia is 1.5; proliferative with atypia is 4.0 (with family history 6.5, premenopausal 6.0).
- *Cowden's syndrome*—it is an autosomal dominant condition, with cutaneous facial lesion (100%), bilateral breast lesion (50%), GI polyps, brain, thyroid tumours.
- It is often associated with ataxia telangiectasia.
- Previous *therapeutic* radiation (*thoracic*) may predispose carcinoma breast especially when RT is given at younger age mainly for Hodgkin's lymphoma.
- Radial scar may predispose the carcinoma. It is a *complex sclerotic* condition of breast with microcyst, epithelial hyperplasia, adenosis, central sclerosis with lesions less than 1 cm in size. It mimics carcinoma clinically and mammographically.
- It is more common in individuals who are on oral contraceptive pills and hormone replacement therapy (HRT) for more than 5 years.

- Presently carcinoma breast is considered as a systemic disease. ***Halsted concept*** of spread is *sequential spread*. Breast—axillary lymph node—systemic spread. ***Fischer concept*** is early to begin with itself, there is distant blood spread because of *micrometastasis* without nodal disease. Only tumour lesser than 1 cm size can be sequential. ***Spectrum concept*** is new one where disease spreads loco-regionally as well as systemically which makes it to aim at both locoregional disease control as well as systemic disease control.
- Prior diagnosis of uterine/ovarian/colonic cancers.

Incidences in carcinoma breast

- 30% of all female cancers
- 20% of cancer related deaths in females
- 2-4% bilateral
- 2-5% hereditary
- Lump in the breast—most common presentation (75%)
- 10% presents with pain
- 35-45% with mutation of BRCA1 gene
- 70% blood spread occurs to bones

Modified Gail risk assessment model

- Age, age at menarche, age at 1st live child birth, race
- Number of 1st degree female relatives having breast cancer
- Number of previous breast biopsies
- Proliferative lesion with atypia

These risk factors are translated into risk scores by specified calculations

But model does not include genetic factor

Pathology

- Breast carcinoma arising from lactiferous ducts is called as ***ductal carcinoma.***
- Breast carcinoma arising from lobules is called as ***lobular carcinoma.*** It is 10% common.

Risk factors for breast carcinoma

- Breast carcinoma in 1st degree relative
- Breast carcinoma in contralateral breast
- BRCA1/BRCA2 gene mutation
- Obesity and alcohol intake
- Nulliparity
- Early menarche and late menopause

- ***In situ carcinoma*** is preinvasive carcinoma which has not breached the epithelial basement membrane. It may be:
  - *Ductal in situ carcinoma (Ductal Carcinoma In Situ, DCIS)* or
  - *Lobular in situ carcinoma (Lobular Carcinoma In Situ, LCIS*).
- ***Invasive carcinoma*** can occur eventually.



Fig. 8.38: Carcinoma right breast in an elderly—an atrophic scirrhous carcinoma.



Fig. 8.39: Examination with both arms raised above the shoulder.

Classifications

I. Ductal carcinoma.
   Lobular carcinoma.

II. (a) *In situ* carcinoma (Noninvasive)
   - DCIS (Ductal carcinoma *in situ*).
   - LCIS (Lobular carcinoma *in situ*).

   (b) Invasive.
   - Invasive ductal carcinoma—most common type. Adenocarcinoma with *no special type* (80%) is

Risk factors classification

Slight to moderate risk	*Moderate to high-risk*	*Very high-risk*
Florid hyperplasia	Age > 60 years	Therapeutic radiation
Solid duct papilloma	ATD / ALS/ LCIS	Family history of breast cancer in two 1st degree relatives
Obesity, alcohol, HRT	History of DCIS	Family history of breast and ovarian cancer
Nulliparity	Cancer on one side breast	BRCA1 and BRCA2 mutation carrier or 1st degree relative with mutation
Early menarche, late menopause		

more common. 60% of this will show micro or macroscopic spread to axillary nodes. Invasive type can be special type or no special type (*NST*) [not otherwise specified/*NOS*].

- Invasive lobular carcinoma. It is commonly multifocal and often bilateral.

III. Unilateral.
Bilateral—2-5% common.

IV. Unifocal.
Multifocal—tumour tissues within the same quadrant at multiple foci.
Multicentric—tumour tissues within the same breast but in different quadrant.

Foote Stewart original classification of invasive breast cancer

- Paget's disease of nipple
- Invasive ductal carcinoma (adenocarcinoma with productive fibrosis [scirrhous/simplex/no special type]—80%; medullary—4%; colloid—2%; papillary—2%; tubular and invasive cribriform—2%)
- Invasive lobular carcinoma—10%
- Rare other types—adenoid cystic, squamous cell, apocrine type

Classification of primary breast cancer

Noninvasive epithelial
- LCIS
- DCIS (intraductal)—papillary, solid, cribriform, comedo

Invasive epithelial
- Invasive lobular—10%
- Invasive ductal
  - Invasive ductal with NST (no special type)/NOS (not otherwise specified)—70%
  - Tubular—2%
  - Colloid—2%
  - Medullary—5%
  - Medullary variant—basal like
  - Invasive cribriform—2%
  - Invasive papillary—1%
  - Adenoid cystic—1%
  - Metaplastic—1%

Mixed connective tissue and epithelial
- Phyllodes, angiosarcoma, carcinosarcoma


Multifocal–in same quadrant
Multicentric–in different quadrants of same breast

Fig. 8.40: *Multifocal* is occurrence of 2nd *in situ* breast cancer whithin the same breast quadrant as the primary *in situ* cancer: *multicentricity* is occurrence of 2nd *in situ* breast cancer outside (other) the breast quadrant as the primary *in situ* cancer in the same breast.

DCIS (Ductal Carcinoma *In Situ*)

- It is intraductal carcinoma (proliferation of malignant mammary ducal epithelial cells) without any invasion into the basement membrane.
- It is 5-20% common.
- It can be:
  - Solid—*high grade.*
  - Comedo with necrosis is *high grade* with increased chances of microinvasion.
  - Cribriform—*low grade.*
  - Papillary—*low grade.*
  - Micropapillary.
- It is associated with high expression of C – erb2 gene (80%).
- It can be high grade DCIS or low grade DCIS.
- It can be comedo DCIS (more malignant and more likely to be invasive later) or noncomedo DCIS (less malignant).
- In 20% of cases synchronous invasive carcinoma in duct is seen.
- Untreated DCIS becomes invasive in > 50% cases (5 fold).
- 5% of *male* breast cancers are DCIS.
- Minor ductal epithelial proliferation is the typical histology.
- Invasive ductal cancer forms in the same breast and same quadrant of DCIS unlike LCIS. DCIS is an *anatomical precursor* of invasive DC.
- Presence of > 25% of DCIS component is present in the *main invasive tumour* or if DCIS is present elsewhere in the surrounding breast tissue, it is called as *extensive in situ component*.

Modern concept of breast cancer classification based on molecular markers

Type	*Marker*	*Treatment*
• ER positive	• ER positive; HER 2 negative	• Endocrine treatment
• HER 2 positive	• ER positive or negative; HER 2 positive	• Endocrine treatment + Standard – surgery/RT/CT?? trastuzumab
• Basal like	• ER negative; HER 2 negative	• Standard – surgery / RT / CT??

Accountable, dependable, reliable are qualities that make a person responsible.

- Nipple discharge and often small swelling are main presentations.
- U/S assisted FNAC and mammography are the needed investigations.
- Risk of lymph node spread in DCIS is less than 4%. So axillary dissection is not necessary.
- *Sentinel Lymph Node Biopsy* and proceed is the preferred method.

Van Nuy's prognostic index for DCIS

Score	***1***	***2***	***3***
Size in mm	< 15 mm	15-40 mm	> 40 mm
Clearance in mm	> 10 mm	1- 10 mm	< 1 mm
Grade and necrosis	not high grade	not high grade	high grade
	No necrosis	Necrosis present	Necrosis present
Total score is 9			
Score 3-4 conservative breast surgery (wide local excision)			
Score 5-7 conservative surgery + Radiotherapy			
Score 8-9 total mastectomy			

Nottingham Prognostic Index (NPI): (0.2 × Tumour size in cm) + Lymph node stage + Tumour grade

NPI score—< 3.4	Good prognosis with 80% survival (15 years)
NPI score—3.4 –5.4	Moderate prognosis with 40% survival
NPI score—> 5.4	Poor prognosis with 15% survival

Management of DCIS

- FNAC confirms the disease but will not differentiate from DCIS and invasive carcinoma
- Mammography, U/S breast, MRI breast
- Routine metastatic work up
- *Breast conservative surgery with RT* to breast and axillary dissection after SLNB (if +ve)
- *Hormone therapy* (tamoxifen) prevents both local recurrence and development of new primary breast carcinoma
- *Total mastectomy* is done in DCIS when—positive margin after wide local excision; two or more primary tumour; when radiation to breast is not possible (collagen diseases); tumour/breast size ratio is not appropriate for conservative surgery and DCIS in pregnancy. *Skin sparing mastectomy* (SSM) may be ideal in such occasions with immediate TRAM/LD flap

Types of Carcinoma Breast

1. ***Scirrhous carcinoma:*** It is 60% common. It is hard, whitish, or whitish yellow, noncapsulated, irregular, with *cartilaginous* consistency. It contains malignant cells with fibrous stroma.
2. ***Medullary carcinoma (5%):*** Also called as 'encephaloid type' because of its brain like consistency. It contains malignant cells with dispersed lymphocytes.
    - *Medullary variant with some features of pure form* shows uniformly high grade aggressive tumour cells with negative ER, PR, HER_2 NEU cell surface receptors (triple negative). They express molecular markers of basal/myoepithelial cells and so now termed as *basal-like breast cancers.*



Fig. 8.41: Specimen of carcinoma breast. Cut section showing tumour tissue of scirrhous type (most common type).

3. ***Inflammatory carcinoma/Lactating carcinoma/Mastitis carcinomatosis***:
    - Most aggressive type of carcinoma breast.
    - It is 2% common.
    - It is common in lactating women or pregnancy.
    - It mimics acute mastitis because of its short duration, pain, warmth and tenderness.
    - Clinically, it is a rapidly progressive tumour of short duration, diffuse, painful, warm often involving whole of breast tissue with *occurrence of peau d'orange*, often extending to the skin of chest wall also.
    - More than 1/3rd of skin over the breast is involved; diffuse lymphoedema is due to tumour emboli within *dermal lymphatics*. Underlying localised palpable mass is not evident clinically. It should be differentiated from other LACB with skin involvement where underlying palpable mass is well evident.
    - Mammography *may not* show any finding except skin thickening. Inflammatory carcinoma of breast is a *clinical diagnosis*.
    - *Ductal or lobular* type with cancer cells in dermal lymphatics is the histology.
    - It rapidly metastasises to chest wall, bone and lungs.
    - *It is always stage IIIB carcinoma (T_{4d}).*

    FNAC confirms the diagnosis—it contains undifferentiated cells. Punch biopsy is ideal and better which shows undifferentiated cells.
    - Total count is normal.

Treatment

- External radiotherapy and chemotherapy.
- Salvage surgery whenever possible.
- It has got *worst prognosis*.

Differential diagnosis

Acute mastitis—total count is increased here.

4. ***Colloid carcinoma:*** It produces abundant mucin, both intra- and extracellularly carrying better prognosis.
5. ***Paget's disease of the nipple***

> *I believe it has not yet been published that certain chronic affections of the skin of the nipple and areola are very often succeeded by the formation of scirrhous cancer in the mammary gland…. In the majority (the affection) had the appearance of a florid, intensely red, raw surface…like the surface of very acute diffuse eczema.*
>
> —**James Paget,** 1874

- It is superficial manifestation of an intraductal carcinoma. The malignancy spreads within the duct up to the skin of the nipple and down into the substance of the breast. It mimics eczema of nipple and areola.

Differences between Paget's disease and eczema of nipple

Paget's disease		*Eczema*	
1.	Unilateral	1.	Bilateral
2.	Edges are distinct	2.	Edges are indistinct
3.	Itching absent	3.	Itching present
4.	Seen in menopausal women	4.	Occurs during the time of lactation
5.	Vesicles absent	5.	Vesicles present
6.	Nipple is usually destroyed	6.	Nipple is usually intact
7.	Underlying lump is usually present	7.	No underlying lump

- In Paget's disease, there is a hard nodule just underneath the areola, which later ulcerates and causes destruction of nipple. Histologically, it contains large, ovoid, clear *Paget's cells* with malignant features. *Paget's hyperchromatic cells* are located in rete pegs of epidermis containing intracellular *mucopolysaccharides* as clear *halo* in cytosol.
- It is 2% common. 90% is invasive ductal carcinoma. 70% shows mass underneath nipple and areola.
- Breast conservation surgery (BCS) is difficult here; hence MRM is needed.

6. ***Tubular, papillary, cribriform*** are other types of duct carcinomas.
7. ***Atrophic scirrhous carcinoma:***
   - Seen in elderly females. It is a slow growing tumour which has got better prognosis.
   - FNAC is diagnostic.
   - Mastectomy or curative brachytherapy (using breast moulds) is the treatment of choice.
   - It is curable.
8. ***Lobular carcinoma in situ:***
   - It originates in terminal duct lobular unit *only of female breast* showing its distension and distortion.
   - It is 12 times more common in *white females*. Predominantly *perimenopausal.*
   - It is 3-5% common. High chance to predispose to invasive cancer. 35% of LCIS may develop invasive lobular carcinoma either in same or contralateral breast; 65% may develop invasive ductal cancer (same side/opposite side/both sides). LCIS is a *marker/predictor* of increased risk of invasive breast cancer; not an anatomical precursor unlike DCIS. It is now *advocated as a risk factor* for developing breast cancer.
   - It is multifocal, bilateral (50%).
   - It is an incidental pathological entity. *Classical type* carries better prognosis; *pleomorphic type* does not so; occasionally *mixed* ductal and lobular *in situ* may be seen.
   - Clinically it does not form a lump.
   - Need not be detected by mammography, as it does not provoke calcification.



Figs 8.42A and B: Paget's disease of the breast.



Fig. 8.43: Carcinoma breast involving axillary tail of Spence.

- 50% cancers can develop in the contralateral breast.
- Immunohistochemistry using e-cadherin antibody shows positive reaction in lobular carcinoma.
- It has poor prognosis due to bilateral, multifocal nature and difficulty in identifying it.



Fig. 8.44: Subareolar carcinoma with destruction of nipple-areolar complex.



Fig. 8.45: Carcinoma breast over the most common site—upper outer quadrant—more visible on raising the arm.



Fig. 8.46: Mass in the upper outer quadrant—is the most common site of the carcinoma breast.



Fig. 8.47: Carcinoma right breast with ulceration in the primary (P) with axillary lymph node secondaries (S).



Fig. 8.48: Quadrants of breast. Carcinoma is more common in upper outer quadrant as more breast tissue is located in this quadrant.

- Tamoxifen (risk reduction in premenopausal) or raloxifen (postmenopausal) often with bilateral total mastectomy is the treatment.

9. ***Disease of Reclus:*** It is a rare intracystic papilliferous carcinoma of breast presenting as a cystic swelling with bloody discharge from the nipple.

Grading of the Tumour

- It is based on nuclear pleomorphism; tubule formation; mitotic rate.
- It can be—well-differentiated (grade 1); moderately differentiated (grade 2) and poorly differentiated (grade 3).

Tumour doubling occurs in 6 months with reaching 1 cm in size in 30 doublings. Breast cancer more than 1 cm has its own blood supply and so high chances of systemic spread and so systemic therapy is a must.

Elston-Ellis Modified Bloom-Richardson Grading System

Parameters used

- **Nuclear pleomorphism**: Score 1—relatively small uniform nuclei; score 2—intermediate pleomorphic nucleoli; score 3—relatively large prominent nucleoli
- **Mitotic count**: Score 1—< 10% mitoses in 10 HPF; score 2—10-20% mitoses; score 3—>20% mitoses
- **Tubule formation**: Score 1—>75% cells in tubule forms; score 2—10-75% cells in tubule forms; score 3—< 10% cells in tubule forms

Grade	*Score*
Favourable	1
Unfavourable	Up to 3
Grade I	3-5
Grade II	6-7
Grade III	8-9

- Well differentiated low grade—grade 3, 4, 5
- Moderately differentiated intermediate grade—grade 6, 7
- Poorly differentiated high grade—8, 9



Fig. 8.49: Carcinoma breast with rib secondaries.



Fig. 8.50: Carcinoma breast with extensive skin involvement.

Biological Behaviour and Clinical Features of Carcinoma Breast

Most common site is *upper outer quadrant (60%) because breast tissue is more in this quadrant.*

Cutaneous Manifestations of Carcinoma Breast

- *Peau d'orange*: Due to obstruction of dermal lymphatics, openings of the sebaceous glands and hair follicles get buried in the oedema giving rise to orange peel appearance.
- *Dimpling of skin* due to infiltration of ligament of Cooper.
- *Retraction of nipple* due to infiltration of lactiferous duct.
- *Ulceration, discharge* from the nipple and areola.
- Skin ulceration and fungation.
- *Cancer-en-cuirasse*: Skin over the chest wall and breast is studded with cancer nodules appearing like an armour coat.
- *Tethering* to skin.

Spread into the Deeper Plane

- Into pectoralis major muscle (is confirmed by observing the restricted mobility of the swelling while contracting the PM muscle).
- Into latissimus dorsi muscle (extending the shoulder against resistance).
- Into serratus anterior (by pushing the wall with hands without flexing the elbow).
- Into the chest wall (breast will not fall forward when leaning forward, and while raising the arm above the shoulder, breast will not move upwards as it is fixed to the chest wall).



Fig. 8.51: *Peau d'orange* appearance of skin.

> *Mammary fistula presents as a recurrent abscess that points and discharges on to the areola and continues to discharge for weeks at a time.*
> **—Sir Headly Atkins**



Fig. 8.52: Ulcerated carcinoma breast with peau d'orange. Note the lymph node enlargement.

Lymphatic Spread

- It occurs through:
  - Subareolar Sappey's lymphatic plexus (presently its Significance is discounted).
  - Cutaneous lymphatics.
  - Intramammary lymphatics.



Fig. 8.53: Patient with carcinoma breast on chemotherapy having alopecia.



Fig. 8.54: Advanced carcinoma left breast involving entire breast with nodularity.

- Lymphatic drainage of the breast is predominantly through axillary (75%) and internal mammary lymph nodes.

Axillary group of nodes are:

1. *Anterior* along lateral thoracic vessels (Pectoral).
2. *Central* embedded in fat in the centre of the axilla.
3. *Posterior* along subscapular vessels.
4. *Lateral* along axillary vein.
5. *Apical* lies above pectoralis minor tendon in continuity with the lateral nodes and receive efferents from all the groups. Spread to these lymph nodes occur by *lymphatic permeation.*

- *Interpectoral,* lies between pectoralis major and minor muscle (***Rotter's nodes***). Presently involvement of these lymph nodes are considered due to retrograde spread.

  These lymph nodes are cleared during *Patey's mastectomy.*

Groups 1st and 2nd are commonly involved.
Groups 3rd and 4th are rarely involved.
Finally Group 5th is involved.

- From axillary lymph nodes spread occurs to supraclavicular lymph nodes by *lymphatic embolisation.*
- Through dermal lymphatics, it may spread to opposite breast or to opposite axillary lymph nodes.
- Spread restricted to level I nodes carries better prognosis.
  Spread to level II has poor prognosis.
  Spread to level III indicates worst prognosis.
- Spread may occur into internal mammary lymph nodes of same side and then to mediastinal lymph nodes.
- Contralateral internal mammary lymph nodes can also get involved by retrograde spread.
- *Fixed enlarged axillary nodes* can cause lymphoedema due to lymphatic block; venous thrombosis and venous oedema due to venous block; and severe excruciating pain along the distribution of the median and ulnar nerves (rare in radial nerve) with often significant sensory and motor deficits due to tumour infiltration of the cords of brachial plexus (medial cord often lateral cord).

Once axillary lymph nodes get fixed, it can result in ***lymphoedema of the upper limb.*** It develops gradually.

Compression of nodes on axillary vein can cause sudden onset of ***venous oedema of upper limb*** (Venous edema develops faster, and is more proximal with bluish discolouration of the skin of the upper limb. It may lead to venous gangrene and so the compression has to be relieved early by radiotherapy).

Causes of lymphatic block in carcinoma breast	***Treatment of lymphoedema of arm***
• Involvement and fixation of the axillary nodes level I, II and III	• Elevation of limb • Elastic stockings • Pneumatic compression
• After levels I, II and III dissection	• Drugs like diuretics and benzopyrones
• After radiotherapy to axilla	
• Inoperable fixed nodes in axilla	
• Recurrent axillary disease	
• May be associated with *cancer-en-cuirasse*	
• Secondary infection	
Effects of lymphatic obstruction	
• Peau d'orange	
• Brawny oedema of arm—indurated, painful, non-pitting—occurs in fixed nodes in axilla	
• Elephantiasis chirurgens—after radical mastectomy or radiotherapy to axilla	
• *Cancer-en-cuirasse*—seen in locally advanced carcinoma of breast. Skin of chest wall is studded with hard fixed nodules like armour coat (of soldiers)	
• Lymphangiosarcoma after radical mastectomy or MRM (Stewart-Treve's)	

Breast is in subcutaneous plane, but its extension, *axillary tail of Spence* passes through an opening in the deep fascia (*foramen of Langer)*. Often it is difficult to differentiate between lymph node in pectoral region and tumour invasion of axillary tail. Mobility will be independent if it is a lymph node, but if it is an axillary tail tumour, it is along with the primary tumour in the breast.

Haematogenous Spread

- ***Bone (most common)*** **(70%)**
    - Lumbar vertebrae, femur, ends of long bones, thoracic vertebrae, ribs, skull, in order.
    - They are *osteolytic* lesion often with pathological fracture.



Fig. 8.55: Carcinoma breast operated, with upper limb lymphoedema postoperatively.



Fig. 8.56: *Cancer-en-cuirasse* with malignant nodules in the chest wall and skin.



Fig. 8.57: Pathological fracture of the humerus due to metastatic secondaries from the carcinoma breast.

- Presents with painful, tender, hard, nonmobile swelling, with disability.
- *70% of secondaries in bone in a women is due to carcinoma breast.*
- Spine secondaries can cause paraplegia.

Wise man has got the art of knowing what to overlook.



Fig. 8.58: Intramedullary nailing as a treatment for pathological fracture.

Features of bone secondaries

- Pain
- Swelling
- Pathological fractures

- ***Liver***—either through blood, occasionally through transcoelomic spread.
- ***Lung***—causes malignant pleural effusion and 'cannon ball' secondaries.
- ***Brain***—causes increased intracranial pressure, coning.
- ***Adrenals and ovaries***.



Fig. 8.59: Osteolytic secondaries involving ischium and pubic bones.

Common sites of distant spread in carcinoma breast

- Bones—70% (lumbar vertebrae, pelvic bones, long bones)
- Lungs and pleura—20-30%
- Soft tissues—5-15%
- Liver—10-12%
- Brain—2-5%
- Adrenals—2-5%

Transcoelomic Spread

Through mediastinal lymph nodes, it may spread into peritoneal cavity causing secondaries in liver, peritoneum, ovary (*Krukenberg secondaries*—occurs in menstruating age groups. During ovulation, cells get attached over the ovarian capsule).

***Note*:**

Present concept of Krukenberg tumour is haematogenous and lymphatic modes of spread. Older concept of transcoelomic spread is no longer well-accepted.

Presentation of carcinoma breast

- Lump in the breast which is hard, painless (most common). At least tumour should become 1 cm to clinically palpable (Fig. 8.62)
- Nipple discharge is the second common presentation
- Ulceration and fungation
- Axillary lymph node enlargement; supraclavicular lymph node enlargement
- Chest pain and haemoptysis
- Bone pain, tenderness, and pathological fracture
- Pleural effusion, ascites
- Liver secondaries, secondary ovarian tumour
- Pain in the lump in 10% cases



Fig. 8.60: Recurrent carcinoma breast.

Note:

Dominant breast mass is three-dimensional, distinct from surrounding tissue of same breast, asymmetric in relation to other breast.

Breast Self-examination (BSE)

Breast self-examination plays a major role in early detection and intervention of breast carcinoma. This underlines the importance of advocating *self-examination of the breast.*

Ideally done once a month just after the menstruation, as during this time breasts are less engorged. In postmenopausal age group it is done at monthly regular intervals.

- Examine both breasts
- Remind the patient that 90% of breast lumps are not cancer.
- Better way is in lying down position with arm raised with a mattress support behind
- Palpation should be using the fingers over all quadrants of the breast
- If any doubtful swelling is palpable, consult the surgeon
- American Cancer Society recommends monthly BSE after 20 years of age
- Nursing mother should perform BSE just after feeding the baby



Fig. 8.61: Self-examination of breast is done in lying down position.

Staging of Carcinoma Breast (Manchester and TNM Staging)

Manchester Staging

1. Tumour in the breast, not involving pectoral or deeper plane. Skin involvement if present, it is lesser than the size of tumour. Lymph nodes are not palpable.
2. Same as stage I but with *mobile, discrete lymph nodes* palpable in the ipsilateral axilla.
3. Tumour fixed to pectoral muscle, or skin involvement more than the tumour size or ipsilateral axillary lymph nodes adherent to each other or fixed.
4. Tumour fixed to the chest wall, 'cancer-en-cuirasse', skin involvement wider than that of the breast, involvement of ipsilateral or contralateral supraclavicular lymph nodes or opposite breast or opposite axillary lymph nodes, spread to bone, lung, liver or inflammatory carcinoma of breast.

TNM Staging (AJCC Cancer Staging Manual, 2002, Sixth Edition)

Tumour:

T_x – Tumour cannot be assessed.

T_0 – No evidence of primary.

Tis – Carcinoma *in situ* (DCIS or LCIS)

Tis Paget's – Paget's disease of nipple with no tumour (with tumour underneath is staged according to size)

T_1 mic – Microinvasion < 0.1 cm.

T_1— Tumour size < 2 cm in greatest diameter (T_{1a}—0.1-0.5 cm; T_{1b}—0.5-1.0 cm; T_{1c}—1-2 cm).

T_2 – Size 2-5 cm.

T_3 – Size > 5 cm.

T_4 – Tumour fixed to chest wall or skin (T_{4a}—fixed to chest wall, T_{4b}—fixed to skin, T_{4c}-$T_{4a} + T_{4b}$, T_{4d}—inflammatory carcinoma breast).

Node:

N_X – Nodes cannot be assessed.

N_0 – No nodes.

N_1 mic – Node with micrometasiasis.

N_1 – Axillary nodes—ipsilateral, mobile, discrete.

N_2 –

N_{2a} – Axillary nodes—ipsilateral fixed to one another and other structures.

N_{2b} – *Clinically apparent** and ipsilateral internal mammary nodes in the absence of clinically palpable axillary nodes.

* *Clinically apparent* means nodes detected by imaging/clinically/pathologically.

N_3 –

N_{3a} – Spread to ipsilateral infraclavicular lymph nodes with or without axillary nodes.

N_{3b} – Spread to ipsilateral internal mammary nodes and axillary nodes.

N_{3c} – Spread to ipsilateral supraclavicular lymph nodes with/without axillary or internal mammary nodes.

Metastasis:

M_X – Metastases cannot be assessed.

M_0 – No metastasis.

M_1 – Distant Metastases.

Stage I : $T_1N_0M_0$
Stage IIa : $T_0N_1M_0;T_1N_1M_0;T_2N_0M_0$.
Stage IIb : $T_2N_1M_0;T_3N_0M_0$
Stage IIIa : $T_0N_2M_0;T_1N_2M_0;T_2N_2M_0;T_3N_1M_0;T_3N_2M_0$
Stage IIIb : $T_4N_0M_0;T_4N_1M_0;T_4N_2M_0$
Stage IIIc : Any TN_3M_0
Stage IV : Any T, any N, M

Early breast cancer—Stage I and II;T1N1,T2N1;T3N0
Locally advanced breast cancer (LABC)—Stage IIIA, IIIB
Metastatic breast cancer—Stage IV

Bilateral Breast Cancer

- It is separate primary breast cancer on the opposite side in a patient who is having or treated for ipsilateral breast cancer.
- It can be synchronous or metachronous.
- There is 5 fold increase in 2nd breast cancer on opposite side in a female who has had breast cancer on ipsilateral side.
- LCIS, multifocal breast cancer, family history are other risk factors.

If you don't know where you're going, you may miss it when you get there.



Fig. 8.62: Carcinoma breast presenting as lump in the breast. It is the most common presentation.

- *Choudary Millis criteria* that help to differentiate primary contralateral breast cancer from metastatic—*in situ* change, different histological pattern, different differentiation shown in opposite breast, clinically or by evaluation ipsilateral tumour has not shown any features of spread.
- It is investigated like any breast cancer, staged accordingly and treated.
- If tumour on the opposite side is metastatic then it will show separate histology and differentiation with mammography showing less infiltrative, diffuse, without microcalcifications but with oedema. If it is metastatic it is stage IV disease.



Fig. 8.63: Bilateral breast cancer operated.

Differential diagnosis for carcinoma breast

- Fibroadenosis
- Traumatic fat necrosis
- Tuberculosis of breast
- Blood good cyst
- Filariasis breast
- Mastitis
- Antibioma
- Galactocele
- Mondor's disease
- Cystosarcoma phyllodes

Investigations in Carcinoma Breast

- ***Mammography***.



Fig. 8.64: Mammography in carcinoma breast.

Findings

- Size and location of mass lesion
- Microcalcifications signify malignancy
- Soft tissue shadow is irregular
- Spiculations

- Bilateral mammography is done to identify multicentricity, to have guideline for assessing eventual chemotherapy or RT in LABC
- Stereotactic mammography guided biopsy is very useful
- LCIS may be missed in mammography
- 50% of breast cancers can be seen on mammography before they are palpable
- It is noninvasive with less radiation exposure
- 5% false-positive rate in mammography; hence biopsy is a must
- Mammogram is used during follow-up period after conservative breast surgery and of opposite side
- Ideally specimen mammography is a must after conservative breast surgery to assess the completion; and after core biopsy to confirm the sample tissue
- ***Ultrasound of breast:***
  - To find out whether the lesion is solid or cystic.

Ultrasound of breast

- To look for whether the lesion is solid or cystic, margin of the lesion, internal echoes, retro-tumour acoustic shadowing, compressibility, dimensions
- *Irregular margin, irregular internal echoes, irregular posterior shadowing, noncompressibility, ratio between anteroposterior to width (lateral/horizontal) dimensions more than 1 are the features of carcinoma.* Doppler will show high frequency signals with continuous flow. It is hypoechoic with more vertical taller growth
- Benign lesions are smooth, rounded with well-defined margins with weak internal echoes and compressibility. It can be elliptical, hyperechoic/hypoechoic smooth lesion
- Cyst is anechoic, oval/round, well circumscribed lesion
- Disadvantage is lesions less than 1 cm may not be identified
- FNAC can be done under U/S guidance
- It is cheaper, easily available and there is no risk of radiation
- It is preferred method of screening in young females where mammography is not done and in pregnancy and early lactation
- US of axilla also can be done to assess axilla and to do guided FNAC of node

- ***FNAC*** (Martin and Ellis 1930): It is very useful in diagnosing the carcinoma breast. U/S guided FNAC is also used. But negative results are difficult to interpret because it may be due to sampling errors and so requires further diagnostic methods. FNAC of opposite breast, lymph nodes, opposite axillary lymph nodes are also often required.

It is done with 23 gauge needle using FNAC aspiration special syringe (aspiration gun). With the lump held firmly, the needle is passed into the lump and with negative pressure continuous aspiration is done until adequate material comes through the needle (suction pressure of 40 cm of H_2O is created into the syringe). Needle with syringe is removed without negative pressure. Material is collected on a slide; a smear is made using 100% alcohol. Cytology is studied after staining it under microscopy.



Fig. 8.65: US picture of right breast showing breast mass.



Fig. 8.66: US breast is basic noninvasive simple investigation to assess breast lump.

The Columbia classification (Haagsen, Cooley and Stout)

GRAVE SIGNS:	
• Oedema of skin	Stage A—only tumour. No Grave signs
• Skin ulceration	Stage B—tumour + axillary lymph nodes < 2.5 cm
• Fixity to chest wall	Stage C—tumour + anyone of five grave signs
• Axillary lymph nodes >2.5 cm	Stage D—two or more Grave signs
• Fixed axillary lymph nodes	Supraclavicular lymph node involvement Distant metastasis

Stage A— No skin oedema, ulceration, or fixation to chest wall.
Axillary nodes are not clinically involved.

Stage B— Clinically involved axillary nodes less than 2.5 cm in diameter.
Not fixed.

Stage C— Grave signs of comparatively advanced carcinoma.
Oedema of skin, skin ulceration, fixation to chest wall.
Massive axillary involvement with nodes > 2.5 cm in diameter.
Axillary fixation.

Stage D— Advanced carcinoma including two or more signs in stage C.
In addition satellite nodules, supraclavicular nodes.
Inflammatory cancer, arm oedema or distant metastasis.

It is better to light a small candle than to curse the darkness.

- Minimum six aspirations are done.
- Giemsa, Papanicolaou, hematoxylin and eosin stains are used.
- Repeat FNAC can be done for further 2 times.
- But it gives only cytological diagnosis. Receptor study cannot be done.
- It is difficult to differentiate between *in situ* and invasive breast cancer by FNAC.

Advantages

FNAC is least painful, can be done on OP basis, reliable and cheaper. Malignant deposits will not occur along FNAC track (only contraindication for FNAC is testicular tumour).
Note:
FNNAC is **F**ine **N**eedle **N**on-**A**spirating **C**ytology.



Fig. 8.67: FNAC of breast lump.

Reliability of FNAC and mammography

	FNAC	*Mammography*
Sensitivity (true positivity)	90-98%	90%
Specificity (without false-positive)	98-100%	90%
False-negative	2-10%	10%
False-positive	Near 1-5%	10%

FNAC scoring

C_0 : No epithelial cells
C_1 : Scanty epithelial cells, benign
C_2 : Benign cells
C_3 : Atypical cells
C_4 : Suspicious cells
C_5 : Malignant cells

- ***Frozen section biopsy***: If FNAC fails even after two trials or in cases of negative FNAC, then on table frozen section biopsy is done for diagnosis. Frozen section biopsy also has got drawbacks. It has got 20% false-negative results. So its use at present is under debate eventhough it is practiced in few oncocenters. It is *not ideal method.*
- ***Corecut/Trucut biopsy:***
  - It is done under local anaesthesia. It gives clear histological evidence and also confirms DCIS (FNAC can not confirm DCIS). This allows proper neoadjuvant/primary chemotherapy, receptor status of the tumour. Wide bore needle biopsy with vacuum is also used.
  - 14-18 gauge spring loaded needle is used. Multiple punctures are needed. US guided biopsy is also done.
  - Large core biopsy is done using 6-14 gauge needle; single puncture is sufficient; large single sample of tissue is obtained.
  - Vacuum-assisted core biopsy is also done.
  - Stereotactic mammographic/MRI/US guided core biopsy are also used in small/impalpable lesions. Stereotactic core biopsy is done in prone position with compressed breast. Under local anaesthesia, 3 mm incision is made and 11 gauge core needle is passed under digital mammographic guidance. Multiple core biopsies are taken using vacuum. A clip may be placed under guidance at the site of the lesion as marker. Mammography of core biopsy specimen is done to confirm the sample tissue. If stereotactic biopsy is inconclusive then a wire localised surgical excision should be done.
  - Core needle biopsy is the *method of choice*.

Image guided biopsies

It is done when lump is not clearly palpable
- US guided core needle biopsy
- Stereotactic mammographic core needle biopsy
- Mammography guided wire localisation using needle sheath over the tumour and through an incision under local anesthesia hook is reached and biopsy is done. It is used if core needle biopsy fails in localising nonpalpable lesion
- MRI guided core needle biopsy

- ***Excision biopsy:***
  - It is done only when FNAC is inconclusive and a facility for frozen section is not available. Incision should be planned in such a way that it will be included in eventual mastectomy.
- ***Chest X-ray***:
  - To look for pleural effusion, cannon ball secondaries in lungs, mediastinal lymph nodes, secondaries in rib.
- ***CT chest:***
  - It is more reliable method to see lung secondaries.
- ***Ultrasound abdomen:***
  - To look for liver secondaries, ascites, 'Krukenberg' tumour.
- ***X-ray spine*** shows osteolytic secondaries.
- ***Oestrogen receptor study*:**
  - They are oestrogen sensitive receptors, which are cytosolic, glycoprotein present in the breast and tumour tissue. It is an important indicator of prognosis of carcinoma breast.
  - Tissue for receptor study is sent at low temperature in ice flasks. It is assessed by quantitative analysis (Frozen –70°).
  - If value is more than 10 units (f/mols) per n gram of tissue it is called as *ER +ve status*. ER positivity is common in postmenopausal women (60%) compared to premenopausal women (30%). If value is less than 10 units per gram of tissue it is called as *ER –ve status*.

  In ER +ve status
  - Prognosis is good.
  - Hormone therapy including tamoxifen is more beneficial.
  - Response to treatment is better.

In ER –ve status
  - Prognosis is poor.
  - Hormone therapy is not very beneficial (but used) as compared to ER +ve patients.
  - Response to treatment is not good.

- ***Progesterone receptor (PR status)*** study or *Her 2 Neu receptor status* or *cErb B2* (growth factor receptor study) are other studies done at present to plan the therapy and assess the prognosis.
  - *Her 2/Neu receptor* (Human epidermal growth receptor 2 Neu oncogene) is a tyrosine kinase receptor and is associated with ER negative, high grade, tumours. It carries poor prognosis. Over expression of Her 2/Neu shows good response to adriamycin.
- ***Study of discharge*** from the nipple.
  - Nipple discharge is usually unilateral in carcinoma breast. *Ductal lavage* may be useful in some patients. Microcatheter of 1 cm length is introduced gently into the ductal opening. 10 ml saline is infused through the catheter. Fluid is withdrawn into the syringe and cytological analysis is done.
- ***MRI of breast:***
  - To differentiate scar from recurrence.
  - To image breasts of women with implants.
  - To evaluate the management of axilla and recurrent disease.
  - It is useful in screening females with high-risk group and *young women*.
  - T1 and T2 weighed images are taken.
  - Irregular mass with spiculations, changes in skin and nipple, lymphoedema are the findings in carcinoma breast.



Figs 8.68A and B



Figs 8.68C and D

Figs 8.68A to D: MRI of breast is ideal method to assess or identify recurrence after BCS or after breast implants. (A) T1 weighted with contrast; (B) T1 weighted; (C) T1 weighted with contrast and fat suppressed; (D) MRI perfusion image (*Courtesy:* Dr Raghavendra Bhat, MD, Radiologist, Balmatta Scan and Research Centre, Mangalore).

  - Lesion indeterminate by US/mammography is assessed by MRI.
  - Ionising radiation is not there with MRI.
  - It is the method *choice of imaging* breasts in pregnancy.
  - It is better in dense breasts.
  - Patient lies in *prone position* with breasts placed over breast coils; both precontrast and postcontrast (*gadolinium*) MRI are taken.
  - *Disadvantages are*—it is costly; nonavailability; not sensitive for premalignant lesions. It cannot be done in patients who are having incompatible metal prosthesis in the body. It is not accurate if done within 9 months of the radiotherapy for carcinoma breast.
- ***Edge biopsy:***
  - Done only when there is ulceration and fungation. Diathermy should be avoided in incision biopsy as it may distort the histology of tumour and study of hormone receptor status may not be possible.
- ***Tumour markers:*** CA 15/3 (normal value < 40 U/ml of serum) are used mainly during follow-up period. CEA, CA 15-3, CA 27-29 may be useful.

The place to improve this world is first in one's own heart, head and hands.

- ***MRI spine/pelvis*** show osteolytic secondaries in the bone like vertebra and pelvic bones.
- ***Radioisotope bone scan*** to look for secondaries in bone in advanced cases. It is not done routinely in early carcinoma of breast.



Figs 8.69A and B: Isotope bone scan is a must in LABC/T3 disease.

Indications for whole body bone scan in carcinoma breast

- T3, T4 advanced disease
- Advanced nodal disease
- Bone pain, bone swelling, pathological fracture
- Chest/liver secondaries

- ***PET scan:***
  - It may be an effective single scan for bone, soft tissue or visceral metastases in patients with symptoms or signs of metastatic disease.

- ***Sentinel lymph node biopsy (SLNB):***
  - The first axillary node draining the breast (by direct drainage) is designated as the *sentinel node (SLN)*. SLN is first node involved by tumour cells and presence or absence of its histological involvement, when assessed will give a predictive idea about the further spread of tumour to other nodes. The incidence of involvement of other nodes without SLN is less than 3% and so if SLNB is negative nodal dissection can be avoided but regular follow-up is needed. SLNB is done in all cases of early breast cancers, T1 and T2 *without clinically palpable node.*
  - It is not done in clinically palpable axillary node as there is already distortion of lymphatic flow due to tumour. It is also not done in multifocal and multicentric tumours, as there is involvement of many lymphatic trunks from different places of breast, and chances of false-negative is high.
  - Sentinel node is localised by preoperative (within 12 hours prior) or peroperative injection of patent blue (Isosulfan vital blue dye 2.5-7.5 ml) or 99m TC radioisotope labelled albumin (one mCi on previous day)/ sulphur colloid (6 hours before) near the tumour (peritumour area) or into subdermal plexus around the nipple. Marker will pass through the sentinel node which can be visually detected as blue staining or with a hand held gamma camera; and is biopsied with a small incision made directly over it. Frozen section biopsy or touch imprint cytology is done for presence of malignant cells. If there is no involvement of sentinel node by tumour then further axillary dissection is not required as *skip lesions* (skipping sentinel node) occur only in less than 3% cases.
  - Detection rate of sentinel node for blue dye and radioisotope is 90% and 98%, respectively. Subdermal/subareolar injection of radioisotope *has got better* sentinel node localisation than peritumour injection. But better imaging is obtained by peritumour injection and so *peritumour injection is usually* practiced. Radioisotope tracer injection done in the early morning of the day of surgery into peritumour area and perioperative injection of patent blue dye in subareolar region—as a *combined method* is often used in many centers. After injection of patent blue, breast is massaged continuously to enhance the uptake. *Incision* is made after 5-7 minutes between pectoralis major and latissimus dorsi to identify blue stained lymphatics which are traced to 2-3 blue lymph nodes. Hand-held radioprobe is used to identify the sentinel node which is later excised. Often 2-3 nodes are removed.
  - *Paraffin section histology is better* than frozen section to identify positive sentinel lymph node. If report comes negative immunohistochemistry test is done to confirm that lymph node is negative for tumour. Sentinel lymph node biopsy *should be done before* wide local excision of the primary tumour.
  - Wide local excision of the primary tumour is done after SLNB in the same sitting.
  - SLNB is *less invasive* than axillary dissection. It is ideal in early invasive carcinoma. Positive SLNB is again classified as macrometastasis (> 2 mm) or micrometastasis (< 2 mm).
  - SLNB is *contraindicated* in patients who are allergic to vital blue dye or radio-colloid, in pregnancy and in inflammatory carcinoma of breast.

- *Complications* of SLNB are rare. They are—blue tattooing of skin which gradually fades; blue—green urine and stool for short period; allergic reactions; anaphylaxis (0.1%); seroma formation. Blue dye binds to oxyhaemoglobin and so artificially registers in oximeter as hypoxaemia.

Note:

Facility for SLNB is not available in many centres.

SLNB is done in:

- Carcinoma breast
- Carcinoma penis
- Malignant melanoma



Fig. 8.70: Sentinel lymph node biopsy (SLNB) of breast. Note: Spread by skipping the sentinel node is less than 3%.

- ***Axillary sampling***:
  - It is often done with an adequate axillary incision. 10-15 nodes are removed for sampling. It is not commonly practiced now (Minimum 10 nodes should be removed-level I nodes).
- ***CT scan of chest, abdomen and brain*** whenever needed.
  - CT is said to be more useful to detect secondaries in these regions.
- ***Ductography***:
  - It is contrast study of ducts of breast in case of unilateral nipple discharge. Fine cannula is passed under vision carefully through the duct opening into the duct and 0.2 ml of dilute water-soluble contrast media is injected into the duct. Craniocaudal and mediolateral X-ray films are taken. Contrast irregular filling defect may be observed.
- ***Breast ductal endoscopy:***
  - It is useful in direct visualisation of the tumour in DCIS and invasive ductal carcinomas. But it is technically difficult and demanding.
- ***Thermography***:
  - It is not very sensitive test (50%). Malignant tumours are hypervascular and so transmitted temperature is detected through different thermographic methods.
- ***Blood count, complete liver function tests*** are needed.

Triple assessment includes:

- Clinical assessment
- Radiological imaging US/MRI/ mammography (after 40 years)
- Cytological or histological analysis FNAC/core biopsy

Newer investigation modalities for carcinoma breast

- Stereotactic core biopsy using computer mammography
- Vacuum-assisted biopsy using 11-guage biopsy probe (becoming popular)
- Needle localised biopsy under mammographic guidance
- I^{125} – seed localisation biopsy

Treatment

Treatment of carcinoma breast

It is usually through a combined approach
- *Surgery*
- *Radiotherapy*
- *Hormone therapy*
- *Chemotherapy*



Fig. 8.71: Horizontal incision for total mastectomy.



Fig. 8.72: Oblique incision extending into the anterior axillary fold for radical mastectomy.

Failure is the only opportunity to begin again more intelligently.

A. Surgeries for Carcinoma Breast

- ***Total (simple) mastectomy*:**
  - Along with the tumour, entire breast, areola, nipple, skin over the breast, including axillary tail are removed. There is no axillary dissection. Often the patient is subjected to radiotherapy later (External) to axilla. *Pectoral fascia* is removed along with breast specimen; breast tissue superficial to axillary fascia is removed.


1-2 cm
Incision
Tumour
Incision
A
B

Figs 8.73A and B: *Stewart incision* for mastectomy.


Tumour
Incision

Fig. 8.74: *Gray incision* for mastectomy in carcinoma breast which extends to opposite side.


Incision
Tumour

Fig. 8.75: *Greenough incision* for mastectomy.


Incision
Tumour

Fig. 8.76: *Kocher's incision* for mastectomy.


Incision
Tumour

Fig. 8.77: *Orr incision* for mastectomy.


Tumour
Incision

Fig. 8.78: *Rodman incision* for mastectomy.

- ***Total mastectomy with axillary clearance*:**
  - Commonly used procedure. Total mastectomy is done along with removal of axillary fat, fascia and lymph nodes. *Level I and II axillary nodes* are removed along with total/simple mastectomy.

- ***Modified radical mastectomy [MRM]:***
  - ***Patey's operation*:** It is total mastectomy along with clearance of all levels of axillary nodes and removal of pectoralis minor muscle. It is enblock dissection of breast and axilla. An elliptical incision is made from medial aspect of the second and third intercostal space enclosing the nipple, areola and tumour extending laterally into the axilla along the anterior axillary fold. Upper and lower skin flaps are raised. Breast with tumour is raised from the medial aspect of the pectoralis major muscle. Dissection is proceeded laterally with ligating pectoral vessels. Once dissection reaches axilla, lateral border of pectoralis major muscle is cleared with level I nodes. Pectoralis minor is divided from coracoid process to clear level II nodes. Medial and lateral pectoral nerves should be preserved (otherwise atrophy of pectoralis minor muscle occurs). Later from the apex of axilla level III nodes are cleared. Nerve to serratus anterior, nerve to latissimus dorsi, intercostobrachial nerve, axillary vein, cephalic vein and pectoralis major muscle are preserved. Wound is closed with a suction drain.



Figs 8.79A to C



Figs 8.79D and E

Figs 8.79A to E: Different steps of Patey's mastectomy with incision, flap raise, dissection in breast and axilla and specimen after surgery.

  - ***Scanlon's operation:*** Is a modified Patey's operation wherein instead of removing pectoralis minor, it is incised to approach the affected level III lymph nodes.
  - ***Auchincloss modified radical mastectomy:*** Here pectoralis minor muscle is left intact and level III lymph nodes are not removed—*commonly done now*.

Mastectomy specimen should be carefully inspected and sent to pathology department

- Specimen is sent in formalin for histology.
- It is sent in saline in low temperature for ER/PR/Her 2 neu status study (histochemistry).
- Specimen mammography is often done.
- Tumour grading, tumour clearance, nodal involvement—its number and capsular breach are assessed histopathologially.

He who is afraid of doing too much always does too little.

- ***Halsted Radical Mastectomy**** (*Complete Halsted*) (***RM***): *Structures removed are*:
  - Tumour.
  - Entire breast, nipple, areola, skin over the tumour with margin.
  - Pectoralis major and minor muscles.
  - Fat, fascia, lymph nodes of axilla.
  - Few digitations of serratus anterior.

Structures retained are *(ABC)*

- ❖ **A**xillary vein
- ❖ **B**ells nerve (nerve to serratus anterior)
- ❖ **C**ephalic vein

Complications are lymphoedema and eventual lymphangiosarcoma (after 3 to many years later) of the limb.

- ***Conservative breast surgeries:***
  a. **Wide local excision:** It is removal of unicentric tumour with 1 cm clearance margin. Incision is made directly over the tumour. Skin flaps should not be raised. Normal breast tissue of *1 cm clearance* with excision of tumour is done. Pectoral fascia is usually not opened in wide local excision unlike in total mastectomy. The specimen is marked after placing in orientation grid and mammography of the specimen is done followed by frozen section biopsy to look for clearance. At least 1 mm clearance is needed for adequacy. Margins where clearance is less than 1 mm need re-excision at that particular margin. If margins show no clearance then patient requires probably total mastectomy. So prior consent for mastectomy should be taken. Drain is not placed; deeper cavity is usually not closed/obliterated as small seroma gets absorbed without any problem. Skin is closed cosmetically. It is often called as *lumpectomy or partial mastectomy*; but better term is *wide local excision*. It is ideal breast conservative surgery. Along with this, axillary dissection through separate incision and RT to breast and chest wall area is given.

  b. **Quadrantectomy:** It is removal of entire segment/ quadrant with ductal system with 2-3 cm normal breast tissue clearance. It is not advocated now as it is proved that there is no outcome benefit between wide local excision and quadrantectomy. Quadrantectomy is done as a part of *QUART therapy* (by Umberto Veronesi from Milan, Italy) along with axillary dissection (level I and II) through separate incision and RT to breast area.



Fig. 8.80: Note the original Halsted and modified Halsted incision.



Fig. 8.81: Complete Halsted operation—radical mastectomy with removal of fat, lymph nodes, pectoralis major, pectoralis minor, entire breast with tumour and skin over the breast, nipple and areola.

***Not commonly done at present.** If at all, it is done in early stage I carcinoma breast.

- ***Toilet mastectomy*:**
  - In locally advanced tumour, tumour with breast tissue and whatever possible is removed to prevent further fungation. But its use and significance is under question. It is often done after giving chemotherapy.
- ***Extended radical mastectomies*:**
  - It includes radical mastectomy + removal of internal mammary lymph nodes of same side with or without opposite side. **It is not done at present.**
- ***Skin sparing mastectomy*** (SSM/Key hole mastectomy) is becoming popular with different approaches.
- ***Lumpectomy/partial mastectomy is better called as wide local excision*** which includes removal of tumour with gross rim (1 cm) of normal breast tissue.
  - Small (< 0.5 cm), unicentric, low grade tumour of breast may be treated with lumpectomy with RT. But it is technically difficult to assess such indications. Stereotactic wire localisation, lumpectomy with clearance, specimen mammography and proper follow-up are the needed principles in such situations. One should achieve negative margin of 1 mm on frozen section and with post-excision mammography of retained breast to confirm adequacy of excision. Presently term 'lumpectomy' is ***rarely*** used to such procedure which basically is wide excision with 1 cm clearance. Patient always needs postoperative adjuvant RT and chemotherapy if poor prognostic factors are present.

Complications of MRM/mastectomy

- Injury/thrombosis of axillary vein
- Seroma—50-70%
- Shoulder dysfunction 10%
- Pain (30%) and numbness (70%)
- Flap necrosis/infection
- Lymphoedema (15%) and its problems
- Axillary hyperaesthesia (0.5-1%)
- Winged scapula
- Occasionally if on table injury occurs to axillary vein, it should be repaired by vascular suturing using 5 zero polypropylene
- Numbness over the medial upper part of the arm can occur due to intercostobrachial nerve injury
- Pectoral muscles atrophy if medial and lateral pectoral nerves are injured
- Weakening of internal rotation and abduction of shoulder occurs due to injury to thoracodorsal nerve

Lymphangiosarcoma (Stewart-Treve's syndrome) of upper limb can develop in patients who have developed lymphoedema after mastectomy with axillary clearance. Usually it occurs *3-5 years* after development of lymphoedema. Such patient may require fore-quarter amputation. It has got poor prognosis. It presents as multiple subcutaneous nodules.

B. Radiotherapy in Carcinoma Breast

Indications:

- Patient who undergo conservative breast surgery, breast is irradiated after surgery.



Figs 8.82A to D: (A to C) Mastectomy specimen with dissected axillary nodes. (D) Organ specimens removed during Patey's operation. Note the pectoralis minor, axillary area and tumour with breast tissue.

What lies within us is more important than what lies before or behind us.

Radiotherapy in carcinoma breast

To chest wall:	*To axilla:*	• *RT is a must* after conservation of breast
• T3 tumour > 5 cm	• 4 or more nodes positive	
• Residual disease-LABC	• Extranodal spread	• Local as well as to axilla
• Positive margin/close surgical margin of < 2 cm	• Axillary status not known/not assessed	• Tangential fields 50 Gy/25 fractions/5 weeks
• After conservative surgery		• Another 10 Gy to tumour bed
• Higher risk group • Inflammatory carcinoma		• Internal mammary and supraclavicular area may be included in radiation field



Fig. 8.83: Postmastectomy lymphoedema. Note the mastectomy scar.

- ♦ After total mastectomy, external irradiation is given to axilla.
- ♦ Patients with higher risk of local relapse after surgery:
  - a. Invasive carcinoma.
  - b. Extensive *in situ* carcinoma.
  - c. Patients under 35 years.
  - d. With multifocal disease.
- ♦ In bone secondaries, to palliate pain and swelling. If there is pathological fracture in the bone, internal fixation has to be done along with external irradiation.
- ♦ Inflammatory carcinoma of breast.
- ♦ In atrophic scirrhous carcinoma of breast, as a curative radiotherapy.
- ♦ As preoperative radiotherapy, to reduce the tumour size and downstage the tumour, so that the operability is better.
- ♦ More than 4 positive lymph nodes in the axilla, pectoral fascia involvement, positive surgical margins, extranodal spread or in patients with axillary status not known/not assessed.

> ***External radiotherapy*** is given over the breast area, axilla (in selected patients like if axillary dissection is not done or more than 4 positive axillary nodes), internal mammary and supraclavicular area
>
> ❖ Total dosage 5000 cGY units
>
> ❖ 200-cGY units daily 5 days a week for 6 weeks

C. Hormone Therapy in Carcinoma Breast

Principles:

- ♦ It is used in ER/PR positive patients in all age groups (earlier it is used in perimenopausal age groups).
- ♦ It is relatively safe, easy to administer.
- ♦ It gives prophylaxis against carcinoma of opposite breast.
- ♦ It is useful in metastatic breast carcinoma.
- ♦ Hormone therapy (tamoxifen) is useful in breast cancer in elderly (positive ER) after wide local excision or occasionally as tamoxifen alone.
- ♦ It is now not used in ER negative patients.
- ♦ Menopausal status; nodal status; chemotherapy used are not factors to defer the use of hormone therapy.
- ♦ Hormone therapy reduces the recurrence rate and so probably improves the life span and quality of life.

Includes:

- ♦ Oestrogen receptor antagonists—*tamoxifen*.
- ♦ Ovarian ablation by surgery (Bilateral oophorectomy) or by radiation.
- ♦ LHRH agonists (Medical oophorectomy).
- ♦ Oral aromatase inhibitors for postmenopausal women.
- ♦ Adrenalectomy or pituitary ablation.
- ♦ Progesterone receptor antagonist.
- ♦ Androgens—Inj testosterone propionate 100 mg IM three times a week.
- ♦ Aminoglutethimide—blocks the synthesis of steroids by inhibiting conversion of cholesterol to pregnenolone—*medical adrenalectomy*.
- ♦ Progestogens, e.g. medroxyprogesterone acetate.

Tamoxifen

- ♦ It is an antioestrogen. It blocks cytosolic oestrogen receptors.
- ♦ Dose is 10 mg BID or 20 mg OD for 5 years.
- ♦ Half life of tamoxifen is 7 days; it takes 4 weeks to show its benefits. It reduces the cholesterol and also cardiovascular morbidity.

Adverse effects:

- ♦ *Tamoxifen flare*—flushing, tachycardia, sweating, genital itching, vaginal atrophy and dryness (premenopausal), vaginal discharge (postmenopausal), fluid retention, weight gain.
- ♦ Occasionally it causes bone pain which should be differentiated from pain due to bone metastasis. It is due to loss of bone density in premenopausal women.
- ♦ It increases the incidence of endometrial cancer.
- ♦ DVT (3%), pulmonary embolism, CVA, TIA, cataract, fractures.

Side effects and endometrial cancer are less in selective drugs like raloxifene.

Advantages:

- ♦ It reduces the recurrence rate by 25%.
- ♦ It improves the prognosis.
- ♦ It is used presently in all age group, ER +ve patients.

Drugs used in hormone therapy

Drug	*Mechanism of action*	*Dose*	*Adverse effects*
Tamoxifen	Antioestrogen	20 mg	Nausea, weight gain, hot flushes, vaginal bleeding, bone pain, amenorrhoea
Medroxyprogesterone	Progestogen	400 mg	Nausea, flushing, vaginal bleeding
Aminoglutethimide	Aromatase inhibitor	250 mg QID	Rash, dizziness, lethargy, Cushing facies
Arimidex	Aromatase inhibitors	1 mg	Lethargy, GI upset
Letrozole	Aromatase inhibitor	2.5 mg OD	Vaginal dryness, hot flushes,vaginal bleeding, cardiovascular problem
Zoladex (Goserelin)	LHRH agonist	3.6 mg monthly	Amenorrhoea, nausea. It is expensive
Diethylstilbestrol	Oestrogen	15 mg daily	Fluid retention, vomiting, thrombosis, hypercalcaemia
Fluoxymestrone	Androgen	30 mg daily	Masculinization, nausea

It is more beneficial in ER +ve patient; perimenopausal patient with node +ve; postmenopausal patient.
Presently ***Tamoxifen and Oophorectomy*** are the commonly used methods.

- Cheap, easily available, less toxic effects, very effective.
- It is equally effective in carcinoma male breast.
- It is presently also **under trial** for certain benign diseases of breast (*ANDI, cyclical mastalgia*).

Selective oestrogen antagonists

- Do not cause endometrial hyperplasia or endometrial carcinoma.
- Drugs include droloxifen, toremifen, raloxifene.

Tamoxifen used in:

- Carcinoma breast
- Benign diseases of the breast like fibroadenosis
- Infertility in males
- Desmoid tumour
- Risk reduction therapy in high-risk females in premenopausal age

Letrozole

- It is a nonsteroidal competitive inhibitor of the enzyme 'aromatase'. This enzyme converts adrenal androgens to oestrogen (aromatization). So it is an aromatase inhibitor.
- Other aromatase inhibitors are *anastrozole and exemestane* (in postmenopausal). It is expensive but more effective than tamoxifen. It is also used in recurrent disease.
- Letrozole is used as an adjuvant endocrine therapy in post-menopausal women with hormone sensitive breast cancer (In premenopausal women this will cause rise in gonadotrophins and ovarian aromatase is not well suppressed). It can also be used in metastatic and recurrent cases. It slows down and stops the growth of oestrogen sensitive breast tumours. It reduces oestrogen level by 98%. Its half life is 45 hours. It decreases the bone density.
- Dosage of letrozole is 2.5 mg once daily.
- It is given for 5 years or for 2 years following 3 years of tamoxifen.
- Side effects of letrozole are vaginal dryness, night sweats, hot flushes, vaginal bleeding, cardiovascular problems and osteoporosis.

Transtuzumab (Herceptin)

- It is a monoclonal antibody that blocks HER-2/Neu receptors thereby preventing growth of cancer cells. It is a new drug. It is presently marketed as herceptin. It is c-ErbB2 (growth factor receptor) inhibitor. It is a newer biological agent. Her 2/Neu receptor is tyrosine kinase receptor.
- It has very little effect on HER-2/Neu negative cancers.
- It is useful only in HER-2/Neu positive cancers. It is currently approved by FDA for use only in metastatic disease. It is given as intravenous infusion.
- Studies have shown substantiate improvement in disease free and overall survival rate.
- Dose is 4 mg/kg as loading; 2 mg/kg as maintenance for 1 year.
- It has got cardiac side effects.

Note

- *Tamoxifen* interferes with oestrogen receptors
- *Letrozole* interferes with oestrogen production
- *Transtuzumab* (Herceptin) interferes with HER-2 Neu receptors
- *Bevacizumab*—vascular growth factor receptor inhibitor—newer agent
- *Lapitinab*—combined growth factor receptor inhibitor—newer agent

Hormone therapy for carcinoma breast

In premenopausal women

- Tamoxifen—antioestrogen
- Ovarian ablation by surgery/by Goserelin/by radiation
- Progestogens—medroxyprogesterone 400 mg
- Androgens—fluoxymestrone

In postmenopausal women

- Tamoxifen
- Aromatase inhibitor like letrozole 2.5 mg OD
- Progestogens
- Androgens
- Medical adrenalectomy using aminoglutethimide (Mitotane)—as major source of oestrogen after menopause is adrenal gland. Cortisone supplement is also needed to prevent feedback rise of ACTH which may block the effect of aminoglutethimide

Surgical endocrine ablations

- Bilateral oophorectomy (Beatson—1896) in premenopausal age
- Bilateral adrenalectomy
- Pituitary ablation

Note:

Present changing concept—is letrozole and tamoxifen are continued even after five years (probably life long) to reduce the chance of late recurrence.

D. Chemotherapy in Carcinoma Breast

- *Adjuvant chemotherapy* refers to administration of cytotoxic drugs to women after breast cancer surgery in the hope of eliminating clinically undetectable distant spread. Reduced recurrence rate and improved survival rate is observed in all women with *invasive* breast cancer. Chemotherapy is usually not indicated in DCIS.
- *Neoadjuvant chemotherapy* refers to administration of cytotoxic drugs in a large operable tumour to reduce the loco-regional tumour burden to make it better amenable for surgical resection, usually after 3 doses. It downstages the disease; may achieve breast conservative surgery in *selected patient*s (only); early systemic control is achieved.
- *Palliative chemotherapy* is used in advanced and metastatic carcinoma breast.

Indications:

- All node positive patients.
- Primary tumour more than 1 cm in size.
- Presence of poor prognostic signs of any tumour—vascular and lymphatic invasion; high nuclear and histologic grade; Her 2/Neu overexpression; negative hormone receptor status.
- In advanced carcinoma breast as a palliative procedure.
- In postoperative period after simple mastectomy in stage III carcinoma breast with fixed axillary nodes.
- In inflammatory carcinoma of breast.
- In stage IV carcinoma breast with secondaries in bone, lungs, liver.
- In premenopausal age group with poorly differentiated tumours.

Drugs used

CMF regime	*CAF regime*	*MMM regime*
Cyclophosphamide	Cyclophosphamide	Methotrexate
Methotrexate	Adriamycin	Mitomycin-C
5-Fluorouracil	5-Fluorouracil	Mitozantrone

Toxic effects are: Alopecia, bone marrow suppression, cystitis, megaloblastic anaemia, GIT disturbances, nephritis.

- ***CMF and CAF*** are commonly used with monthly/3 weeks cycles for 6 months.
- Other anthracyclines like doxorubicin or epirubicin should be used often for better result.
- ***Taxanes***: They are newer chemotherapeutic drugs which act by G2/M phase of cell cycle. It is commonly used in metastatic carcinoma of breast. Drugs are **paclitaxel and docetaxel**. Taxanes have no cross-resistance with anthracyclines and so can be used sequentially or concurrently with anthracyclines.
- Gemcitabine is also used often in selected cases for better results.

Chemotherapy regimes

- *1st line drugs*—anthracyclines—FEC regimen (better); CAF; CMF
- *2nd line drugs*—taxanes
- *3rd line*—gemcitabine

***Note*:**

- Neoadjuvant (primary) chemotherapy is useful in large operable primary tumour to make it amenable for conservative breast surgeries. Postoperative radiotherapy and chemotherapy is a must in this situation.
- High dose chemotherapy with stem cell rescue is not found to be beneficial by trials in patients with heavy large nodal spread.
- Hormone therapy is given after completion of chemotherapy for additive effect. Concurrent therapy of both (together) is not used at present. It is sequential—chemotherapy then hormone therapy. Chemotherapy gives quicker and better response initially and so it is used early and later only hormone therapy is continued.
- Adriamycin shows better response with Her-2 Neu overexpression patients.
- Paclitaxel may be combined with trastuzumab in Her-2 Neu (Human epidermal growth receptor 2) over expression patients.
- Chemotherapy and radiotherapy can be given concurrently or as sandwich therapy.
- Presently one day dose of all drugs of the regimen used as a *standard* at 3 weekly cycles for 6 cycles for stage III—CAF regime. For metastatic paclitaxel single day dose cycles or etoposide and cisplatin 3 days cycle—6 cycles.

Complications of chemotherapy—bone marrow suppression, alopecia, GI side effects, cardiac toxicity. Monitoring with haematocrit, blood urea, serum creatinine, LFT are needed. Cytoprotective agents like GMCF (granulocyte macrophage colony stimulating factor), GCSF (granulocyte colony stimulating factor) are given to reduce severity and duration of neutropenia. It is given in 24 hours as 30 million units.

MANAGEMENT OF EARLY CARCINOMA BREAST

- Early breast cancer is the one diagnosed by mammography or stage I carcinoma breast.
- Usually chest X-ray, blood count and liver functions are sufficient to screen the early breast cancer patients.

Aims of Treatment

- To achieve possible '*cure*'.
- Control of local disease in breast and axilla.
- Breast conservation, i.e. breast form and function.
- Prevention of distant metastasis.
- To prevent local recurrence.

Breast conservative surgery

Indications	***Contraindications***
• Lump < 4 cm	• Tumour > 4 cm
• Clinically negative axillary nodes	• Positive axillary nodes > N1
• Mammographically detected lesion	• Tumour margin is not free of tumour after breast conservative surgery needs MRM
• Well-differentiated tumour with low S phase	
• Adequate sized breast to allow proper RT to breast	• Poorly differentiated tumour
• Breast of adequate size and volume	• Multicentric tumour
• Feasibility of axillary dissection and radiotherapy to intact breast	• Earlier breast irradiation
	• Tumour/breast size ratio is more (centeral tumour)
	• Tumour beneath the nipple
	• Extensive intraductal carcinoma

Modalities of Treatment

- ***Breast conservative surgery (BCS)***—ideally done as *wide local excision* with axillary dissection with RT to breast and chest wall. Quadrantectomy as a part of QUART therapy may be used only in selected patients. RT is given to the entire breast with 4500 cGy dose.
- *Patey's operation* or simple mastectomy with axillary clearance.
- Postoperative radiotherapy in high-risk patients.
- Hormone therapy, i.e. tamoxifen 10 mg BID or 20 mg OD.
- Sentinel node biopsy when required.
- Regular follow-up often with radioisotope bone scan and CEA tumour marker.

In early breast cancer, breast conservative surgery like *wide local excision*/quadrantectomy, axillary dissection (level I and II) and postoperative radiotherapy (to the breast) is used which prevents the disfigurement and psychological trauma of mastectomy to the patient. Tumour is removed with a rim of normal tissue. Wide excision and QUART therapy are different procedures. *Wide local excision* is ideal and better where clearance margin is 1 cm. In *quadrantectomy* entire segment with ductal system with 2-3 cm clearance margin is achieved. But it is not advocated now as there is no benefit in outcome (survival/recurrence rate) by quadrantectomy over wide local excision.


Correct incision
Axillary incision
Curvilinear incisions
A
Radial and directly axillary extended incisions should not be used in conservative breast surgery
Wrong incisions
B

Figs 8.84A and B: Curvilinear incision should be placed in conservative breast surgeries. Never place wrong radial incisions because if conversion to total mastectomy is needed then placement of incision will be difficult. In conservative breast surgery for axillary dissection separate incision in the axilla should be placed.

Principles of Conservative Breast Surgery (Refer Table Above)

- Curvilinear nonradial incisions (radial incisions should not be placed, because if there is a need to convert into total mastectomy, then incision plan may be difficult).
- Separate incision for axillary dissection.
- Undermining of the skin flap must be avoided.
- Confirm tumour clearance by frozen section. It may be often difficult and so tumour is cut and only margin which is close and doubtful is advocated for frozen section.
- Radiotherapy is a must to breast and chest wall region (locally).

In time of test, family is best.

QUART Therapy

It is *quadrantectomy, axillary dissection* of level I and II nodes with separate axillary incision and *postoperative radiotherapy* to breast (5000 cGy) and axilla (1000 cGy). First it was started by *Umberto Veronesi* from Milan. Now Quart therapy is only occasionally used.

Skin Sparing Mastectomy (SSM)

- It is like a key-hole surgery of breast.
- Skin sparing/limited skin excision (5-10%) will not alter/affect the recurrence rate.
- *Indications are*—central tumour/multicentral/extensive intraductal/T1/not feasible for conservation.
- Excision of nipple-areola complex with very limited skin removal.
- Marginal skin excision over the tumour/biopsy site.
- Total glandular mastectomy.
- Axillary dissection using either same (extension of SSM incision) or separate incision in the axilla.

Indications for Total Mastectomy in Early Breast Cancer

- When tumour is more than 4 cm.
- Multicentric tumour.
- Poorly differentiated tumour—high grade.
- Tumour margin is not clear of tumour after breast conservative surgery.


Incision for axillary dissection
Deep tumour (retained after biopsy)
Incision scar of excision biopsy
Re-excision incision with 1 cm margin after excision biopsy
Nipple-areolar incision
A
Tumour
Skin sparing mastectomy (SSM) incision
Re-excision incision with 1 cm margin
SSM Incision
Tumour
Incision scar of previous biopsy
B
Incision for axillary dissection
Re-excision incision with 1 cm margin
Tumour
Skin sparing mastectomy (SSM) incision (1 cm margin)
Tumour
C

Figs 8.85A to C: Skin sparing mastectomy for carcinoma breast—different approaches. Skin sparing mastectomy (SSM) does not affect the recurrence rate.



Figs 8.86A to C: Skin sparing mastectomy incision with prosthesis implant for placement.

Management of Axillary Nodes when Clinically Not Palpable

- *Sentinel lymph node biopsy (SLNB)* is done. If node is positive for tumour then axillary dissection is done. But facility for SLNB is not available in most of the centres and so axillary dissection is done as a routine. Usually level I and II nodes—below the axillary vein are dissected.
- *Axillary sampling* is done by separate curved incision between the outer border of pectoralis major and latissimus dorsi 6 cm below the apex of axilla. About 10-15 nodes (level I) are sampled. Aim is to remove *largest nodes* in axilla which are likely to be involved. At least *4 lymph nodes* should be removed. All 4 nodes should be sent *separately* for histology. First level I nodes are removed; if they are not palpable then only level II or III are sampled. Axillary sampling is said to detect *skip metastasis* in level II and III. It is not commonly advocated now.

Principles of Axillary Dissection/ Axillary Clearance

- *Indications*: Axillary dissection is done when there is clinical involvement of nodes; when FNAC of lymph node or sentinel node biopsy proved malignancy; when in a large tumour where reconstruction is needed so that 2nd eventual axillary surgery is difficult at a later period.
- It is *removal* of fat, fascia, nodes in the axilla. Usually level I and II nodes are removed. Nodes below the axillary vein are only removed. Level III dissection increases the chances of lymphoedema. Risk of lymphoedema further rises if RT is given later along with level III dissection.
- Dissection is done through an individual crease transverse incision in the axilla, when it is advocated with breast conservative surgery.
- When it is advocated along with total mastectomy it is done like modified radical mastectomy—*Auchincloss* is commonly used.

Hope sees the invisible, feels the intangible and achieves the impossible.

Principles of axillary dissection/axillary clearance

It is removal of different levels of axillary nodes; with fat and axillary fascia

Why axillary dissection is done?	***Which levels?***	***Technical principles***
• For staging	• Level I—60%	• Any incision but caudal hair-line incision is preferred
• To assess the prognosis—number of nodes/size of the node	• Level I, II—20-25% • Level I, II, III—15-20%	• Nerve to serratus anterior/thoracodorsal nerve should be safeguarded
• As a treatment—regional control of		• Medial and lateral pectoral nerves should be retained when the dissection is done with the mastectomy
• To plan adjuvant therapy irradiation/chemo/hormone	• Level I and II dissection Low axillary dissection less chances of lymphoedema	• Drain should be kept to the area • After surgery specimen should be properly dissected for all lymph nodes, labelled and sent for histological study. Usual number of nodes in axilla are 20-32. So minimum of 10 nodes should be dissected, identified and sent for study. Nodes can be easily identified if fat dissolving agents are used over them.

- In *skin sparing mastectomy* also axillary dissection is done using an extension of SSM incision or by separate axillary incision.

Adjuvant therapy after surgery in early breast cancer

- Radiotherapy
- Chemotherapy—CMF, CAF regime commonly used. Taxanes are also used
- Endocrine manipulation:
  - Ablation
  - Tamoxifen (receptor antagonist)—20 mg/day for 5 years
  - Aromatase inhibitors—blocks oestrogen production. Letrozole 2.5 mg OD
  - LHRH agonists—Goserelin 3.6 mg/28 day's cycle for 2 years

ADVANCED CARCINOMA BREAST

Refers to:

- Locally inoperable (adherent to chest wall) tumour.
- Inflammatory carcinoma of breast.
- Fixed axillary lymph nodes, or supraclavicular lymph nodes, or opposite axillary nodes.
- Bilateral carcinoma breast.
- Metastatic carcinoma of breast, i.e. spread to bones, liver, lungs, brain.

Locally Advanced Carcinoma of Breast (LABC)

- It means locally advanced tumour with muscle/chest wall involvement, extensive skin involvement or fixed axillary nodes. It will be T3, T4a, T4b, T4c or T4d or N2 or N3.
- It is investigated by FNAC of tumour/core needle biopsy/incision biopsy/mammography of opposite breast, chest CT, CT abdomen or whole body bone scan. Biopsy is needed to assess receptor status.
- *Bilateral mammography* is done to assess tumour size and multicentricity which is needed to check the chemotherapy response at a later period. FNAC of axillary node is required. If bone scan is positive it becomes metastatic carcinoma of breast not LACB. Only when 60% of bone is dimeneralised in metastatic bone disease, plain X-ray bone will detect the lesion. Even though X-ray may be normal in stage III disease, in 30% of these patients bone scan will be positive making the disease stage IV metastatic.
- Treatment of LACB is always palliative by simple mastectomy/toilet mastectomy, chemotherapy and hormone therapy using tamoxifen.
- Initial neoadjuvant chemotherapy; surgery; radiotherapy; adjuvant chemotherapy are other therapeutic plan.
- Palliation is to control pain, to prevent fungation or bleeding.
- In inoperable fixed tumour chemotherapy is given initially. Later, after 3-4 cycles of chemotherapy, when tumour size reduces and becomes operable, total mastectomy is done.
- Postoperative radiotherapy is given to breast field and axilla.
- Usually axillary dissection is not necessary in LACB.
- Only chemotherapy and radiotherapy to breast and axilla (without palliative mastectomy) also can be done in LACB.
- There is usually no role of breast conservative surgery for LACB.
- 5-year survival is 40% and 10-year survival is less than 25%.

Present strategy of treatment for LABC

- *Initial neoadjuvant* (anterior) chemotherapy is given to downstage and achieve cytoreduction, to target possible micrometastases first, to assess chemosensitivity. *FEC*, CMF, CAF regimes are used.
- *Response to chemotherapy* is assessed by *complete responders* without palpable tumour; *partial responders* with > 50% decrease in tumour size; *nonresponders* with < 50% decrease in tumour size; *progressive disease* with > 25% increase in size
- Patients with nonresponders and progressive disease are treated by RT to breast, chest wall, axilla and supraclavicular region; taxanes; hormone therapy; surgery if operable
- *Responders* are later treated with total mastectomy/MRM, occasionally BCS. After surgery remaining 3 or 4 cycles of chemotherapy are completed. Later hormone therapy should be given for 5 years (tamoxifen 20 mg OD). ER +ve (> 10 fmol/mg) patients show 75% positivity
- Stage IIIA patients are *classified* as operable and inoperable

Inflammatory Carcinoma of Breast

Inflammatory carcinoma is T4d LACB (Stage IIIB). It is also called as mastitis carcinomatosis or lactating carcinoma of breast. It is 2% common. It is observed in younger age group usually in pregnancy or lactating period. There will be extensive skin involvement with pain. It often mimics mastitis of lactation. FNAC or incision biopsy concludes diagnosis. It is initially treated by chemotherapy or radiotherapy and later if tumour reduces in size total mastectomy with axillary clearance can be done. But most often it is inoperable. After surgery, chemotherapy and tamoxifen is given. 5-year survival for inflammatory carcinoma of breast is 25-30%.

Metastatic Carcinoma of Breast

It is blood spread into different places like bone, lungs and pleura, liver, soft tissues, brain and adrenals. It is evaluated by FNAC/incision biopsy, chest CT, LFT, U/S abdomen, CT abdomen, whole body bone scanning, CT brain, tissue study for ER/PR/HER-2 Neu receptor status. It is *stage IV* disease.

- *Bone* is the most common site of metastasis. Spread to vertebra is through posterior intercostal vein and *Batson's venous plexus (valveless)*. Vertebrae, ribs, upper end of humerus and femur are common bones involved.
- *Lungs and pleural* spread causes 'cannon ball' secondaries, effusion, consolidation, chest wall secondaries.
- *Liver* secondaries may develop either by haematogenous or through lymphatics across diaphragm from lower inner quadrant of breast.
- *Brain* secondaries present with headache, vomiting, convulsions, localising features.
- Soft tissue secondaries has got *better prognosis*; visceral secondaries has got worst prognosis.
- Response to treatment decreases with number of organs involved with secondaries.
- Receptor negative secondaries are more aggressive.
- Median survival time for metastatic breast cancer is 24 months.

Treatment concept in metastatic carcinoma of breast

- To improve quality of life.
- To relieve pain of secondaries like bone, lungs.
- To relieve neurological problems like convulsions, space occupying cranial problems.
- Other symptomatic relief.

Treatment strategy in metastatic carcinoma of breast

- *Chemotherapy*—CMF, CAF, Taxanes in combination. Chemotherapy in metastatic breast cancer is useful (indicated/commonly used) in rapidly spreading visceral and skin secondaries, lymphangitis or when predicted disease free survival is less than 2 years; if response is negative for first line hormone therapy; in receptor negative status.
    - High dose of chemotherapy using cyclophosphamide, cisplatin, carmustine, melphalan is tried in view to get high response rate of 55-70% along with bone marrow transplant. But toxic effects are often life-threatening. Its advantages are now doubtful when compared to toxic effects.
    - Haemopoietic growth factor is also used along with chemotherapy to enhance the cell kill with less bone marrow toxicity. It may also allow multiple high dose chemotherapy to increase the response rate.
- *Radiotherapy* is used in bone metastasis, brain secondaries, to prevent paraplegia in spine involvement, and advanced axillary nodes. It is also used in painful bone secondaries, chest wall secondaries.
- *Hormone therapy* has got important role. Tamoxifen, oophorectomy, adrenalectomy, androgens, progestogens, aminoglutethimide are used. It is useful in slow growing soft tissue or bone secondaries; or predicted disease-free survival is more than 2 years or age more than 35 years.
- Blockage of over expression of epidermal growth factor (EGF)/transforming growth factor alpha (TGF-alpha) which are related to ErbB1/ErbB2 receptors in relation to aggressive carcinoma factor is tried.
- Palliative surgeries done are total/toilet mastectomy, fixation of bones in case of pathological fractures, spinal cord decompression to prevent paraplegia, lung resection in case of localised secondaries, bilateral oophorectomy.
- Trastuzumab (herceptin) is monoclonal antibody used in cancers with good results. It blocks the Her-2/Neu and ErbB2 receptors. Bevacizumab and lapitinab are other newer biological agents of different actions.



Fig. 8.87: Carcinoma of breast operated earlier with skull secondaries. It is metastatic carcinoma of breast. Skull secondaries are not common. Common site of bone secondaries are lumbar vertebrae, pelvis, upper part of femur, ribs, etc.

- Metabolic complications like *hypercalcaemia* may be life-threatening emergency in metastatic breast cancer. It is treated with hydration, steroids, biphosphonates (palmidronate, clodronate) 90 mg intravenously once a month. It also reduces the demineralisation of bone, fracture, pain and paraplegia.

Bone secondaries in carcinoma breast

- Most common site of blood spread (70%)
- Lumbar vertebrae, femur, pelvis
- Pathological fracture can occur
- Spinal compression and paraplegia
- Radiotherapy, internal fixation, spinal decompression is required
- Biphosphonates 1600 mg/day

Malignant pleural effusion as secondaries from Ca breast

- It signifies terminal event
- It has got poor prognosis
- Respiratory distress and failure is the main feature
- HRCT is ideal diagnostic tool
- *Treated by*
    - Intercostal tube drainage
    - Pleurodesis using talc/tetracycline (1.5 gm)/bleomycin (60 units)
    - Chemotherapy

Causes of death in carcinoma breast

- Secondaries in lung—haemoptysis, respiratory failure
- Spine involvement—quadriplegia
- Secondaries in brain
- Cancer cachexia



Fig. 8.88: Secondaries in brain—primary is from breast.

PROGNOSTIC FACTORS IN CARCINOMA BREAST

Stage	*5 yr survival*
I	90%
II	70%
III	40%
IV	20%

- **Spread to axillary nodes** is the most important prognostic indicator.

Lymph node—as a prognostic factor

- Number of nodes: > 2 carries poor prognosis
- Location of nodes
- Capsular invasion
- Extranodal status
- Size of the node: > 2.5 cm has poor prognosis
- More than 4 nodes/level III (apical nodes) involvement has got worst prognosis (5-year survival is 30%) and also decides for radiotherapy to axilla

- **Age:** Younger the age worser the prognosis.
- **Sex:** Carcinoma male breast has got worser prognosis compared to female breast. Because of early spread in carcinoma male breast.
- **Stage I and II** has got better prognosis.
- **Atrophic scirrhous** has got best prognosis.
- **Medullary carcinoma** has got better prognosis than scirrhous carcinoma because of lymphocytic infiltration.
- **Invasive carcinoma** has got worser prognosis.
- **Inflammatory carcinoma** breast has worst prognosis.
- **ER +ve** tumours has got better prognosis.
- **Differentiation** also decides prognosis.
- **Presence of elastic fibres** in histology has got better prognosis.
- Tumour proliferation stages, growth factor and oncogene factors.
- Tubular, colloid, papillary types has got better prognosis.
- **Tumour grade**, growth factor and oncogene factors. ErbB2—Her-2/Neu positive has got poor prognosis. ErbB1 with overexpression of epidermal growth factor (EGF), TGF alpha and cathepsin D has got poor prognosis.
- **DNA flow aneuploid** status has got poor prognosis. Low S phase fraction (< 5%) has got good prognosis.
- **Size of the tumour**—tumour size less than 1 cm has got better prognosis.
- **p53 tumour suppressor gene** (guardian gene) shows bad prognosis.

Prognostic factors are classified as:

- *Host factors:* Age; sex; menopausal status; family history; previous breast cancer; immunosuppression; nutrition.
- *Tumour factors:* Tumour size; nuclear grade; staging; receptor status; DNA nature; spread, etc.

Breast cancer group	*Features*	*Prognosis—5-year survival*
Very low-risk primary	DCIS; tubular	> 90%
Low-risk primary	Node negative; favourable microscopy	70-90%
High-risk primary	Node positive; unfavourable microscopy	< 70%
Locally advanced	Inflammatory ca/large primary (T4)	< 30%
Metastatic	Blood spread	Poor

PROPHYLACTIC MASTECTOMY

It is removal of *entire breast including axillary tail of Spence* prophylactically as risk reduction procedure in high-risk patients with indications. It reduces the developing of invasive cancer by 90% in high-risk group and also decreases the chances of death due to the disease. Axillary dissection is not done.

Modified Gail model and evaluation of mutation carriers are used to assess the risk group for risk reduction surgeries.

Indications

- DCIS (noninvasive).
- LCIS.
- Florid changes in fibrocystadenosis.
- Suspicious lesion in mammogram.
- Strong family history with 1st degree relatives having carcinoma breast.
- BRCA1 and BRCA2 mutation carriers.

Risk Reduction Surgeries

- Total mastectomy.
- Subcutaneous mastectomy.
- Skin sparing mastectomy.

Mastectomy is done bilaterally in LCIS and in strong family history. In suspicious unilateral lesion only unilateral mastectomy may be done.

***Note*:**
Other risk reduction methods are—life style modifications, avoiding alcohol and HRT, *tamoxifen*.

CARCINOMA OF MALE BREAST

- It is less than 1% of cases of breast cancers. Mean age is 65 years.
- Commonly associated with BRCA2 gene mutation.
- Other *risk factors* are—radiation, excess oestrogen, cirrhosis, Klinefelter's syndrome, liver schistosomiasis, family history, testicular disease, infertility, obesity.
- Commonly it is *infiltrating duct carcinoma* (90%), DCIS (10%). Lobular carcinoma is *not seen* in male breasts.
- Unilateral hard breast lump often eccentric with nipple retraction and discharge, skin dimpling and axillary lymphadenopathy are the clinical features.
- Differential diagnosis—gynaecomastia, breast abscess, sarcoma, secondaries.
- Presentation, spread, behaviour are same as carcinoma of female breast. Investigations and treatment are same as carcinoma female breast.
- MRM (as pectoralis major is involved early) with RT to breast area and axilla is the treatment.
- *Tamoxifen* is very useful in carcinoma male breast.
- Carcinoma male breast has poorer prognosis when compared to carcinoma breast in females.
- 80% cases are ER positive. 75% PR +ve; 35% overexpress HER 2/Neu.
- LHRH agonists are also often used. It works at hypothalamo-pituitary axis level via tachyphylaxis. It produces reversible "*chemical castration*". Goserelin 3.6 mg/28 days for 2 years is the current recommendation.
- Bilateral orchidectomy which was earlier used is no longer commonly advocated. Orchidectomy may be only useful in metastatic male breast cancer.



Fig. 8.89: Carcinoma male breast in a pre-existing gynaecomastia. Note the gynaecomastia on opposite side.



Fig. 8.90: Carcinoma male breast showing mass under the areola, puckering and nipple retraction.

Carcinoma breast in pregnancy

- Incidence is 3%
- *Breastfeeding* should be avoided during chemotherapy. Lactation should be suppressed by giving bromocriptine 2.5 mg OD for 5 days
- *Hormone treatment* during pregnancy is potentially teratogenic
- During pregnancy breast shows increased vascularity, density, water content and cellularity. So US and mammogram may show false-positive results. Chest X-ray can be done with abdominal shield
- Alkaline phosphatase is elevated during pregnancy and so it is also not significant
- Bone isotope scan cannot be done during pregnancy
- *MRI is the* investigation of *choice* for primary in breast and also for metastatic work up
- Treatment is modified radical mastectomy (MRM)
- Chemotherapy can be given in 2nd trimester with care
- Radiotherapy has no role
- As commonly ER negative, hormone therapy is not used
- When distressing secondaries are present termination of pregnancy may be required
- *Women with breast cancer can become pregnant 2 years after the completion of therapy, as recurrence is more common in 2 years*

Management in carcinoma breast during pregnancy

1st trimester	*2nd trimester*	*3rd trimester*
MRM	MRM	MRM
If axillary node is +ve then pregnancy is terminated; chemotherapy is given	Chemotherapy carefully	After delivery, chemotherapy with suppression of lactation

Follow-up after Therapy for Carcinoma Breast

- Clinical examination in detail at regular intervals.
- Yearly/two yearly mammography of treated and contralateral breast is a must.
- Bone scan/CT chest, abdomen/tumour marker are done only if there is clinical suspicion of spread/metastases. It is not a regular routine follow-up method at present.

BREAST RECONSTRUCTION

- **Immediate reconstruction.**
  - In early stages of malignancies as well as in selected more advanced stages where the response to neoadjuvant chemo therapy has been good. Not advised in locally advanced disease.
  - *Advantages of immediate reconstruction* are—maximum amount of breast skin is preserved for reconstruction. It will not affect the long-term survival or recurrence rate.
- **Delayed reconstruction** (3-9 months after surgery).

Indications

- Locally advanced disease.
- Radiation needed in postoperative period.
- Patient unfit for prolonged surgical procedure.

Advantages

- Allows for postoperative radiation without prosthesis exposure.
- Avoids fibrosis and fat necrosis where TRAM flap is used.

Factors deciding the reconstruction

- Amount of skin retained
- Stage of the carcinoma
- Earlier radiotherapy
- Type of flap used

Methods of Reconstruction

- Oncoplastic techniques.
- Insertion of breast implants or expanders. They are best for small breasts. Healthy nonirradiated overlying skin is the requirement.
- Flap with implant or expanders.
- Flap reconstruction:
  - Pedicled flap—TRAM flap.
  - Free flap—free TRAM flap into internal mammary artery.
  - Muscle preserving perforator abdominal flap.

Types

- Silicon gel implant under pectoralis major muscle.
- Expandible saline prosthesis with prior tissue expansion.
- If there is less skin or after radiotherapy latissimus dorsi musculocutaneous flap (*LD flap*) or contralateral transversus abdominis muscle flap *(TRAM flap)* is used.
- Superior gluteal flap based on superior gluteal vessels.

- *Ruben's flap* using soft tissue pad overlying the iliac crest based on deep circumflex iliac vessels.

External breast prosthesis which fits within the bra is a simpler cosmetic method.


Skin
Skin
Ribs
Implant
Implant
Pectoral muscle
Intact (subcutaneous)
Pectoral muscle
removed (subcutaneous)

Fig. 8.91: Breast implant.



Fig. 8.92: LD flap.



Figs 8.93A and B: LD flap (A) Donor area; (B) Recipient area.



Fig. 8.94: Latissimus dorsi flap (LD flap) placed after mastectomy. It is based on thoracodorsal artery.


Superior epigastric
artery
IV
II
I
III
Inferior epigastric
artery

Fig. 8.95: Transverse rectus abdominis myocutaneous flap (TRAM). Note the blood supply of the flap.



Fig. 8.96A

LD flap	*TRAM flap*
Myocutaneous flap based on subscapular artery	Transverse rectus abdominis myocutaneous flap based on
Easy to perform	superior epigastric artery. ipsilateral or contralateral TRAM flap is used
Reliable flap, well vascularised	It gives the bulk needed for reconstruction and so implant is not needed
Can be placed over prosthesis	Donor site morbidity and fat necrosis can occur
Low complication rate	Free TRAM flap into internal mammary/thoracodorsal axis can be done
But causes unsightly donor area on the back	Limitations to position, shape and rotate; often needs mesh placement in the abdomen wound to prevent development of incisional hernia



Figs 8.96B to D

Figs 8.95A to D: Different operative steps in TRAM flap.

Note:

- Breast reconstruction is done in young patients with early stage disease.
- Skin sparing mastectomy with removal of nipple areola complex may be better for reconstruction.
- Symmetry is the most important factor in breast reconstruction.

Nipple is created using:

- Local breast flaps 3 months after breast reconstruction.
- Nipple sharing from contralateral nipple using composite graft.
- *Skate flap*: Local flap with de-epithelialised donor site around the periphery over which a full thickness graft is applied.
- Nipple prosthesis can be fitted.

Areola pigmentation is created using *(it is done 3 weeks after nipple creation):*

- Full thickness skin graft from non-hairy skin lateral to labia majora, as the pigmentation of this graft matches that of the areola.
- From contralateral areola if reduction mammoplasty is done on that side.
- Tattooing—colour tends to fade with time and may need to be repeated.
- SSG from retroauricular area or from thigh.

BREAST IMPLANTS

Fig. 8.97: Typical breast implant and its placement. It can be placed in subcutaneous or submuscular plane.

- Technically simple.
- Achieve symmetry easily.

- Implant in *submuscular plane* is better whenever muscle is not removed during surgery.
- If muscle is removed as in radical mastectomy, then *subcutaneous implant* is placed.
- Silicon gel implants are used.

Complications of breast implants

- Pain, exposure of implant and rupture
- Displacement, extrusion
- Infection
- Capsular contraction

Causes of massive enlargement of breast

- Benign hypertrophy—usually bilateral
- Giant fibroadenoma
- Serocystic disease of Brodie
- Sarcoma
- Colloid carcinoma
- Filariasis of breast

Changes that can occur in nipple

- Destruction
- Depression—retraction
- Discolouration
- Displacement
- Deviation
- Discharge
- Duplication

Causes of hard swellings in the breast

- Carcinoma breast
- Antibioma breast
- Traumatic fat necrosis
- Calcified haematoma
- Fibroadenoma—hard variety

NIPPLE RETRACTION



Fig. 8.98: Typical nipple retraction in carcinoma breast. It is circumferential retraction in carcinoma and partial slit like in duct ectasia.

- 25% of retractions are bilateral.
- Congenital nipple retraction is simple nipple inversion. It causes problems in breastfeeding, recurrent infection, collection of secretions.
- Slit like retraction is due to duct ectasia and periductal mastitis.
- Circumferential retraction is usually due to carcinoma.
- Any nipple retraction of recent onset should be evaluated.

Note:

- *Nipple inversion* is congenital, developmental one; it is seen in 25% of females; can be bilateral; does not interfere with infant feeding; can predispose periductal mastitis. Surgical correction is not usually required and is technically difficult. Suction device is often tried mechanically.
- *Nipple retraction* occurs in a nipple which was normal earlier and is now pathologically retracted. Duct ectasia, carcinoma, previous surgeries may be the cause.

Nipple discharge

Classifications	***Significant nipple discharge***	***Types of nipple discharge***	***Discharge which suspects' carcinoma***
It can be: • Physiologic – Bilateral, involves multiple ducts. – Usually not bloody. – Nonspontaneous	• Spontaneous. • Persistent. • Nonlactating patient. – Incidence of carcinoma in nonlactating nipple discharge is 4%.	Blood: • Papilloma/malignancy. *Purulent* • Infection, usually related to lactation; often in malignancy.	• Spontaneous discharge. • Age ≥ 40. • Unilateral discharge. • Bloody or guaiac-positive discharge. • Palpable lump/mass.
• Pathologic – Unilateral. – Spontaneous.	Causes of nipple discharge • Physiological is—during lactation and pregnancy.	*Milky:* • After childbearing up to one year; hypothyroidism,	*Management:* • Discharge study for cytology, culture.

Everytime something good happens to you, make something good happen to someone else.

– Can be often bloody. – Most common cause intraductal papilloma. *It can be*: • Spontaneous. • Nonspontaneous. *It can be due to:* • Benign cause—88%. • Malignant cause—12%.	• Galactorrhoea is milk secretion not related to pregnancy either primary or secondary. • Fibrocystic disease of breast—serous or greenish discharge. • Duct papilloma—bloody discharge. • Duct ectasia—thick, creamy discharge. • Carcinoma—bloody discharge. • Idiopathic—here cause of discharge is not identified in spite of all investigations. Patient can be reassured with regular follow-up. It may be improper reabsorption of the normal ductal secretions (Normally all ductal secretions which occur continuously are reabsorbed completely).	prolactinomas, galactorrhoea. • Medications: Oral contraceptives, tricyclic antidepressants, dopamine agonists. • In milk fistula; rarely in galactocele. *Grey, brown, green, sticky:* • Duct ectasia. Common in 5th decade, with nipple tenderness and pain. *Creamy discharge:* • Duct ectasia. *Serous*: • Fibrocystic disease (most common; but can be serous/greenish/greenish black), ectasia. *Serosanguinous:* • Carcinoma, infection. *Greenish:* • Fibrocystadenosis (commonly), duct ectasia. *Black:* • Duct papilloma/carcinoma.	• Mammography, US of breast and axilla, FNAC/core biopsy. • Ductography is specific for duct ectasia. • Treat the identified cause accordingly.

Chapter 9 Peritoneum

> *Among the inflammations of the abdominal region, I have given a place in our Nosology to the Peritonitis, comprehending under that title, not only the inflammations affecting the peritoneum lining the cavity of the abdomen, but also those affecting the extensions of this membrane in the omentum and mesentery.*
>
> **—William Gullen,** 1792

CHAPTER OUTLINE

- Anatomy
- Physiology
- Acute Peritonitis
- Spontaneous Bacterial Peritonitis
- Sclerosing Peritonitis
- Biliary Peritonitis
- Postoperative Peritonitis
- Other Forms of Peritonitis
- Pelvic Abscess
- Subphrenic Spaces and Subphrenic Abscess
- Mesenteric Cysts
- Mesenteric Panniculitis
- Acute Mesenteric Lymphadenitis
- Mesenteric Malignancy
- Mesenteric Trauma
- Peritoneal Malignancy
- Omental Cyst
- Omental Torsion
- Omental Tumour

ANATOMY

Peritoneum

It is a serous membrane lining the abdominal cavity. It is composed of outer fibrous tissue layer (which gives strength) and inner mesothelial cell layer (secretes fluid giving lubricating function to the peritoneum).

Parts of Peritoneum

1. *Parietal peritoneum*: It lines the inner surface of the abdominal wall, under surface of diaphragm and pelvic wall. It is loosely attached to the overlying walls and can be easily stripped off. It is innervated by the somatic nerves, so pain sensitive. Anterior peritoneum is most sensitive when compared to pelvic peritoneum.
2. *Visceral peritoneum*: It lines the outer surface of the abdominal viscera, firmly adherent, cannot be stripped off. It is innervated by autonomic nervous system; hence not pain sensitive.

Peritoneal Cavity

It is the potential space between the parietal and visceral peritoneum. Normally it contains 100 ml of clear, straw coloured fluid secreted by the mesothelial cells. Its quantity and quality varies in pathological conditions. It has got lubricating function, allowing frictionless movements of adjacent peritoneal surfaces.

Spaces in peritoneal cavity: Peritoneal cavity being largest cavity in the body is divided into *different spaces* by ligaments and mesenteries. Eleven ligaments are—coronary, gastrohepatic, hepatoduodenal, falciform, phrenicocolic, splenorenal, gastrosplenic, duodenocolic, gastrocolic; mesenteries are—transverse mesocolon and bowel mesentery. Intra-abdominal spaces are nine in number; they are—right and left subphrenic, subhepatic, lesser sac, supramesenteric, inframesenteric, right and left paracolic gutters, and pelvic. Peritoneal cavity is surgically divided basically into *supracolic and infracolic* compartments.

PHYSIOLOGY

Surface area of peritoneum is 2 m^2 equal to surface area of skin. It has property of bidirectional transfer of substances. It can absorb from or transfer to peritoneal cavity, fluid and electrolytes. This property is used in peritoneal dialysis. The mesothelial cells facilitate rapid healing following any injury, which takes place very fast in matter of hours. Adhesions occur due to delayed or incomplete peritoneal healing.

Diaphragmatic defense: Movement of peritoneal fluid and lymph in the peritoneal cavity depends on the diaphragmatic movement and phases of respiration. During expiration altered intrathoracic and intra-abdominal pressure makes all fluid, bacteria and particles to move/circulate upwards towards diaphragm; during inspiration, it facilitates the entry of these contents into lymph to clear it. There are fine intercellular pores in the peritoneum called as *diaphragmatic stomatas* covering the inferior surface of the diaphragm which leads into diaphragmatic lymphatics and so to regional lymph nodes and thoracic duct. During expiration intra-abdominal pressure is reduced and peritoneal fluid through capillary action travels upwards towards diaphragm. Peritoneal macrophages promote leukocyte migration into the peritoneal cavity. Peritoneal mast cells release vasoactive products causing vasodilatation on peritoneal surface and release of complements and immunoglobulins into the peritoneal cavity. Complements cause bacterial opsonisation and phagocytosis. Release of fibrin causes adhesions and localisation of infection to one place preventing generalised peritonitis; this often leads into localised abscess formation.

ACUTE PERITONITIS

Types

- *Primary*
- *Secondary*
- *Tertiary*

PRIMARY PERITONITIS

- It is commonly due to pneumococci, and can occasionally be due to streptococci, haemophilus, gonococcus (rare now) and other gram-negative (*Escherichia coli*) organisms. It is common in young girls between 3-9 years of age group and also in women.
- Here there is no documented source of infection. Infection usually spreads from lower genitals through fallopian tubes, from upper respiratory tract infection or from middle ear in males.
- It is uncommon after 10 years of age. It is common in malnourished child and child with nephritis. Child is toxic, severely ill and develops septicaemia very early.
- It is also seen in ascites, patient with indwelling catheter for peritoneal dialysis, patients with peritoneovenous shunt.
- It can also be due to Chlamydial, fungal or mycobacterial infection.
- TC is very high, > 30,000/mm^3.

Treatment

- Diagnostic tapping, tube peritoneal drainage and laparoscopic drainage and wash are useful methods.
- Laparotomy and peritoneal toilet**.**
- Broad spectrum antibiotics including combination of aminoglycosides, cephalosporins and metronidazole.
- Local instillation of antibiotics, into the peritoneal cavity to achieve quick and effective results.

Mortality is high.

SECONDARY PERITONITIS

It is secondary to any bowel or other visceral pathology, e.g. perforation, appendicitis. *Escherichia coli* (70%) is the most common organism involved. Other bacteria are—aerobic and anaerobic streptococci, *Clostridium welchii*, bacteroides, staphylococci, *Klebsiella, Salmonella typhi*.

TERTIARY PERITONITIS

- It occurs after any abdominal surgeries, which is usually severe and the patient may go in for SIRS or MODS early.
- Tertiary peritonitis is defined as persistent or recurrent intra-abdominal infection after an adequate treatment for primary or secondary peritonitis—usually after 48 hours.
- It is common in immunosuppressed individual with ineffective peritoneal host defenses against microbes. Infection due to *E. faecalis*, *E. faecium*, *S. epidermidis*, *P. aeruginosa*, *C. albicans* are common in such patients. Virulence and resistance to drugs are other factors.
- It is difficult to diagnose clinically causing delay in therapy. CT abdomen, total and platelet count, LFT, monitoring of renal functions, hourly urine output assessment, chest X-ray are *required investigations*.
- *Treatment* is aggressive antibiotic therapy, antifungal therapy, TPN, maintaining of haemodynamic stability, exploration of abdomen, thorough wash, colostomy/ileostomy or exteriorisation of bowel segment. FFP, packed cells, platelet transfusions may be required. Ventilator, ICU care is often needed.
- *Mortality rate* is > 50%. Problems are—DIC, septicaemia, uraemia (haemodialysis may be needed), haemorrhage, pneumonia, ARDS.

Bacteria Causing Peritonitis

a. *Bacteria from GIT—E. coli,* aerobic streptococci, *Streptococcus faecalis, Staphylococcus*, anaerobic streptococci, anaerobes (bacteroides), *Klebsiellla, Cl. welchii.*

b. *Bacteria not from GIT*—Gonococcus, pneumococcus, are from fallopian tubes, commonly occurs in young females. *Chlamydia*, β-haemolytic streptococci, *Mycobacterium* are few other bacteria which can cause peritonitis.

a.	*Primary*	Monomicrobial, extraperitoneal source, blood spread
b.	*Secondary*	Most common, polymicrobial, intra-peritoneal source
c.	*Tertiary peritonitis*	Due to superadded infection following treatment of secondary/primary

Most common bacteria during the phase of peritonitis is *E. coli* and during abscess formation is *B. fragilis. Mortality for diffuse peritonitis is 10%.*



Fig. 9.1: On table finding in a case of peritonitis, where the peritoneal cavity is filled with pus.

Mode of Infection

- Perforation of the GIT—duodenal/gastric/enteric/colonic ulcers; Meckel's diverticulitis perforation.
- Penetrating or blunt trauma.
- Surgery.
- Drains.
- Dialysis.
- Foreign body.
- Appendicitis, cholecystitis, diverticulitis.
- Intestinal obstruction with strangulation.
- Via fallopian tubes.
- Through blood spread—in septicaemia.
- Transmural spread.
- Following uterine perforation/injury during abortion or termination of pregnancy.



Fig. 9.2: Duodenal ulcer perforation causing peritonitis.



Fig. 9.3: Jejunal perforation due to trauma. Trauma is the common cause for jejunal perforation. It is commonly blunt abdominal injury due to shearing force (traction injury) causing jejunal tear near duodenojejunal junction.



Figs 9.4A and B: Ileal perforation with severe peritonitis. Note the closure done horizontally. It could be typhoid perforation.

Better three hours too soon, than one minute too later.

Factors affecting the spread of the infection in peritonitis

- Rapidity by which the pus is gushed into the peritoneal cavity, e.g. burst appendix, perforations
- Amount of peristalsis (more the peristalsis more the spread)
- Virulence of the organism
- Localising action of the omentum (in children localisation is poor as omentum is small)
- Immunosuppression—HIV, steroids
- Anatomical nature of the peritoneal cavity
- Age, associated diseases like malignancy, malnutrition, anaemia

Pathogenesis

- Lot of fluid is secreted into the peritoneal cavity which is infected, containing bacteria and toxins causing shock, toxaemia and its subsequent effects. Fibrinogen forms fibrin which tries to localise the infection. Bowel gets adhered to each other with fluid collecting between the loops. Thick flakes are formed adhering to the surface of the bowel. Peritoneum is thick, oedematous, becomes velvety and reddish with loss of its glistening appearance. Omentum is thickened, adherent. Often site of perforation may be identified by the location of the end of the omentum. Dilated bowel loops with site of obstruction/gangrene may be found. Pus, often with pockets may be present in subphrenic, paracolic and pelvic spaces.
- Peritoneal contents are initially sterile but eventually become infected in certain situations, as in acute pancreatitis, in haemoperitoneum, and in ruptured urinary bladder. It is due to transmural migration of bacteria.
- In perforated duodenal or gastric ulcers, contents in the peritoneal cavity are initially sterile but later get infected to form bacterial peritonitis.
- *Localised peritonitis*—initially localisation of peritonitis occurs based on the anatomical factors like supracolic/infracolic compartments; greater omentum; paracolic gutters; dilated small bowel, etc. Pathological factors are thickened peritoneum, fibrin deposition, omental adhesions, reduced bowel peristalsis. Localised peritonitis may resolve by proper therapy. It may form abscess—pelvic/subphrenic. If it progresses it may form generalised peritonitis.



Fig. 9.5: Small bowel perforation with peritonitis with thick plaques on the bowel surface.

- *Diffuse peritonitis* sets in due to poor localisation, rapid peritoneal contamination, violent peristalsis, virulent organisms, immunodeficiency status, and small omentum in children (not properly developed in children). Diffuse peritonitis may occasionally get localised to form abscess. Mortality in diffuse peritonitis is 10%.

Clinical Features

- Sudden onset of pain which is *severe*.
- Fever, vomiting.
- Tenderness—initially localised later becomes diffused.
- Rebound tenderness—*Blumberg sign.*
- Guarding and rigidity, dull flanks on percussion.
- Tachycardia, tachypnoea.
- Tenderness on P/R examination.
- Distension with silent abdomen.
- Eventually leading to Hippocrates facies, septicaemic shock and loss of consciousness.
- Bowel sounds are absent due to paralytic ileus.
- Fever may be absent in severe peritonitis due to loss of pyrogenic reaction. Total count also may be very low in severe peritonitis.

Investigations

- Plain X-ray abdomen (in erect posture)—will show *ground-glass appearance* along with gas under diaphragm in the presence of perforation.
- Total count is increased.
- U/S abdomen—shows fluid in the abdominal cavity.
- Also clinches the other causes like haemoperitoneum, pancreatitis.
- Electrolyte study.
- Blood urea and serum creatinine.
- Serum amylase if *four times the normal value*, it is significant. LFT also should be done. Platelet count, bleeding time, clotting time, prothrombin time are to be assessed in severe peritonitis.
- Four quadrant abdominal tap—reveals pus or infected fluid. In suspected pancreatitis fluid should be analysed for amylase level (which will be high). Often US guided aspiration is better and more accurate.



Fig. 9.6: Plain X-ray abdomen showing gas under diaphragm. Perforation is the most common cause of peritonitis.



Fig. 9.7: Multiple air fluid levels in plain X-ray abdomen—feature of intestinal obstruction.



Fig. 9.8: Plain X-ray abdomen showing ground glass appearance—a feature of peritonitis.

- ***Diagnostic laparoscopy. It can also be used as therapeutic for duodenal ulcer perforation or primary peritonitis to give peritoneal wash.***
- CT scan is often useful to confirm the cause or to rule out conditions like pancreatitis. CT scan detects bowel ischaemia, gangrene, perforation, internal hernias and quantity of pus/fluid in the peritoneal cavity.

Differential Diagnosis

- *Pancreatitis:* In pancreatitis back pain is common. But it is often difficult to differentiate clinically from acute peritonitis. Serum amylase is increased. CT abdomen may help in differentiating from peritonitis.
- *Intestinal obstruction*: There will be distension, vomiting and pain. Plain X-ray shows dilated bowel loops. CT scan confirms intestinal obstruction and its cause.
- *Ruptured ectopic pregnancy*: Urine pregnancy test will be positive. History of amenorrhoea is significant. Palor, tachycardia, lower abdominal pain and distension are common presentations. US abdomen and pelvis confirms the diagnosis.
- *Acute pyelonephritis*: Often clinically acute pyelonephritis mimics acute peritonitis. Guarding, tenderness, rigidity may be present in pyelonephritis also. Urinary symptoms, tender renal angle, urine microscopy revealing pus cells, US abdomen may confirm the diagnosis.
- *Acute mesenteric ischaemia*: Bloody diarrhoea, colicky pain, tender abdomen, toxicity are the features of mesenteric ischaemia. CT abdomen and angiogram are useful investigations.
- *Diabetic acute abdomen*: Patient with diabetes mellitus may present as acute abdomen. Free fluid in the flank may not be present. Patient may be ketotic also.

Treatment

- Intravenous fluids for resuscitation are essential. It improves the tissue perfusion, corrects the hypotension and also improves the urine output. Normal saline, Ringer's lactate are usually used. Usual requirement is 2 ml/kg/hour.
- Nasogastric tube aspiration—to decompress bowel; to reduce toxic fluid; to prevent aspiration.
- Total parenteral nutrition, CVP line to perfuse and to monitor.
- Blood transfusion, FFP, platelet transfusions if indicated.
- Catheterisation with maintenance of adequate urine output (30 ml/hour) (0.5 ml/hour/kg).
- Antibiotics—ampicillin, gentamicin, metronidazole, ceftazidime, cefoperazone, cefotaxime, tazobactum, piperacillin, meropenem, linezolid, etc.
- Analgesics to relieve pain by drugs, epidural analgesia.
- Sitting propped up position, early mobilisation, exercise, respiratory physiotherapy, prevention of DVT using heparin/ low molecular heparin are essential.
- Surgical correction of underlying cause.
- Use of dopamine, steroids, and management of shock.
- Often ICU and ventilator support is required during postoperative period.
- Monitoring the patient using PO_2, PCO_2, electrolytes, and pulse oximeter.

Laparotomy and proceed

  - On laparotomy, the cause for peritonitis is identified and corrected.
- In bowel perforation—perforation closure.
- In intestinal obstruction—resection and anastomosis.

Eyes are more accurate witness than ears.—**Hiraclitus.**



Figs 9.9A and B: X-ray showing gas under diaphragm due to perforation. Ground glass appearance of peritonitis is seen in another X-ray.

- In appendicitis—appendicectomy.
  - Proper peritoneal toilet (wash with 10 litres of saline) is given. A drain is placed (tube).
  - Pus should be sent for culture and sensitivity.
  - Tension sutures are placed when required to prevent burst abdomen.

Laparostomy—may be *open or closed method*. In *open method,* (Ettapan's lavage) abdominal wall/fascia and peritoneum are not sutured but kept open. It will reduce the chances of abdominal compartment syndrome and also allows easier and faster drainage of the infected fluid from the peritoneal cavity. But disadvantages are it causes lot of fluid loss and electrolyte imbalance and open area itself may allow infection to get into the peritoneal cavity. In *closed method,* abdominal fascial wound is closed using a zip. It facilitates the regular washing of the peritoneal cavity with normal saline without contaminating the cavity from outside and reduces the unnecessary fluid loss. But it may cause abdominal compartment syndrome.

Technique of emergency laparotomy

Abdomen is opened with midline incision (with wide exposure), often extending both above and below the umbilicus, with incision inclined towards the left side at umbilicus. Once peritoneum is opened gushing pus is removed using suction. Pus is collected for culture. Abdominal cavity is inspected thoroughly for site of origin of sepsis—appendicitis/perforation/gangrene, etc. Definitive procedure is done depending on the cause. Proper wash is given using normal saline (10 litres). Drain should be placed. Wound is closed with tension sutures using nonabsorbable monofilament sutures (zero or one number).



Fig. 9.10: Vertical midline incision is used for emergency laparotomy in peritonitis. Lengthy incision with wide exposure of the peritoneal cavity is advisible.



Figs 9.11A and B: Severe peritonitis showing pus in the peritoneal cavity.

Postoperative management

- Proper critical care (ICU) postoperatively.
- Ventilatory support; monitoring with urine output, temperature, breathing, pulse rate, blood pressure, arterial blood gas

analysis, total count estimation (both very high and very low counts signify severe sepsis/septicaemia), neutrophil count estimation, platelet count, prothrombin time analysis, blood urea and serum creatinine, liver function tests (altered liver function signifies septicaemia). These investigations need to be repeated as and when required.

- Proper fluid and electrolyte management.
- Total parenteral nutrition (TPN).
- Prevention of deep vein thrombosis by leg exercises, low molecular weight heparin.
- Prevention/identification of ARDS and its management.
- Prevention of bedsore.



Fig. 9.12: Abdomen is closed with tension sutures in case of peritonitis using monofilament nonabsorbable sutures to prevent postoperative burst abdomen. Drain also should be placed into the peritoneal cavity.



Fig. 9.13: Postoperative patient with tension sutures with fistula and leak. Patient has undergone resection and anastomosis for gangrene bowel.

Terminal Features in Peritonitis

a. *Hippocratic facies*—bright, hollow eyes; pale, pinched face; cold perspiration in eye brows; dry, fissured tongue; blue lips. Patient will be in severe shock. It signifies terminal status with high mortality rate. It is a typical facial sign of *severe end stage peritonitis.*



Fig. 9.14: *Hippocratic facies* in severe end stage peritonitis.

b. Septic shock (cold stage).
c. Systemic inflammatory response syndrome (SIRS).
d. Multiorgan dysfunction syndrome (MODS).

Complications and Sequelae of Peritonitis

- Septicaemia.
- Paralytic ileus, adhesions, intestinal obstruction.
- Respiratory infection.
- ARDS, bronchopneumonia.
- Electrolyte imbalance, DVT.
- Renal failure.
- MODS.
- DIC.
- Formation of subphrenic abscess, pelvic abscess and other intraperitoneal abscess.
- Burst abdomen; biliary/gastric/enteric/faecal fistula formation; later incisional hernia.

Note:

Complications may be systemic (septicaemia, respiratory, DIC, DVT, renal failure) or abdominal (ileus, intra-abdominal abscess, fistula, burst abdomen, portal pyaemia, adhesions).

SPONTANEOUS BACTERIAL PERITONITIS (SBP)

SBP is defined as bacterial infection of ascitic fluid in the absence of an intra-abdominal surgically treatable source of infection.

It is seen in:

- Infants and children commonly.
- In nephritic syndrome.
- In adults, with cirrhosis, most common cause. In cirrhotic patients, there is low Fc γ receptor on macrophage surface causing poor phagocytosis; opsonic action of peritoneal surface cells in presence of ascites is low causing poor control of bacterial load.
- In patients who has undergone splenectomy.
- Patients with ascites due to any cause.
- Malnutrition and malignancy.

Causative Organisms

- Gram-negative bacilli (70%)—*E.coli*, *Klebsiella*.
- Gram-positive cocci (20%)—pneumococci, streptococci and enterococci.
- Anaerobes (10%).
- In girls it is commonly through fallopian tubes. In males it is always blood born from respiratory tract infection or otitis media.

Features

- Features of peritonitis but initially with dull aching pain.
- Features of shock.
- Common in girls.
- High fever with neutrophilia is characteristic.
- Profuse diarrhoea is common.
- Features relevant of cause.
- Total count, LFT, U/S is useful tool.
- SBP is rare in ascites with high protein content like in peritoneal carcinomatosis. More than 250 neutrophils/cu mm^3 of ascitic fluid are diagnostic.

Note:

Scoring of the severity of the peritonitis is done based on age, sex, duration, cause, origin, content, general condition, haematocrit, electrolytes, O_2 saturation, blood urea, serum creatinine.

1. Mannheim peritonitis index.
2. Acute physiology and chronic health evaluation score (APACHE score).

Management

- Usually conservative with proper higher generation antibiotics. But condition has got high mortality.
- Tapping of the purulent fluid from the peritoneal cavity is done only with atypical needed cases.
- Laparoscopy is useful method.
- Often peritoneal purulent fluid tube drainage may be beneficial.
- Laparotomy and peritoneal wash is done occasionally if secondary peritonitis and toxicity develops.
- Plasma albumin is helpful in SBP with cirrhosis to reduce hepatorenal syndrome and to decrease mortality.

Note:

- Exudate in pneumococcal peritonitis is odourless, turbid and sticky.
- Exudate in streptococcal peritonitis, is odourless, thin, blood stained with flecks of fibrin. Greenish watery diarrhoea is common. It is common in infants and children. Upper respiratory tract infections, tonsillitis, pharyngitis are the causes. It is treated with penicillins, amoxycillins, cephalosporins.
- Staphylococcus aureus peritonitis is common in those who use intravaginal tampons causing toxic shock syndrome and DIC.

SCLEROSING PERITONITIS

It is usually Practolol (β blocker) induced peritonitis. It is fibrinous peritonitis causing thickening of bowel and other contents of abdomen. It leads to intestinal obstruction and malnutrition.

BILIARY PERITONITIS

Causes

- Trauma.
- Postoperative leak after surgery for gallbladder, CBD, duodenum, ERCP, pyloroplasty, post-gastrectomy duodenal stump leak/blow out, leak from choledochojejunal anastomosis.
- Perforation of gallbladder or CBD.
- Gangrenous cholecystitis and rupture.
- Idiopathic.
- Leakage from accessory bile duct after surgery; leakage from displaced T tube or displaced percutaneous stent.

Clinical Features

- Features of peritonitis—abdominal distension, guarding and rigidity.
- Jaundice: It may be due to CBD injury, liver biliary ductile injury, sectorial duct injury, cystic duct leak or by absorption of bile from free peritoneal cavity.
- Toxicity.
- Features of shock.

Investigations

- X-ray abdomen.
- Diagnostic peritoneal lavage.

Treatment

- Laparotomy, wash, drainage.
- Cause to be treated. US guided percutaneous drainage; ERCP stenting; duodenal stump exploration, wash and drainage or jejunal serosal patch over it; ligation of cystic or accessory duct; choledocho/hepaticojejunostomy, etc. depending on cause.
- It has got high mortality.
- It may get localise and form abscess or may lead into biliary fistula.

POSTOPERATIVE PERITONITIS

- It is the development of peritonitis in postoperative period, either due to anastomotic leak, or biliary leak; and there is collection of pus in the peritoneal cavity including interloop areas.
- It is often difficult to differentiate it from postoperative urinary infection, respiratory infection like bronchopneumonia, cardiac causes in old people, and infection in

other areas like intravenous cannula site (thrombophlebitis). Symptoms may mask if patient is on steroid therapy.

- In all abdominal surgeries patient initially develops paralytic ileus which lasts for 3-5 days. If it persists or progresses one should suspect postoperative peritonitis. Other suspicious features are—persisting toxaemia in spite of antibiotics, oliguria, pyrexia, altered liver functions, altered total WBC count (very high as well as very low and neutrophil count is more specific) and increasing leak from drain site either fecal/intestinal/biliary, increase in abdominal distension, pain and tenderness. Leak may be due to sepsis, hypotension in pre/per and postoperative period, hypoxia, blood loss, ischaemia of bowel and friability of bowel wall, and specific causes like tuberculosis, malignancy or Crohn‘s disease. Often multiple areas of the bowel become necrotic which eventually causes leak. Leak from multiple sites is difficult to manage and has got poor prognosis.

Management

- Immediate US or CT abdomen to find out the abdominal cause, total count, assessment of urinary parameters like blood urea and serum creatinine, liver function tests.
- Immediate exploration is the only way to save the life of the patient. Proper exploration with wide exposure of the abdomen, is done to identify the cause for infection is done. Resuturing of the anastomotic site can be done but chances of releak are more likely. It can be done, if leak site is small and less friable. Otherwise either ileostomy or colostomy is the better choice. Often continuous tube irrigation and drainage is needed to clear the infective material. Laparostomy using zip technique is also beneficial. Multiple cavities with multiple abscesses are often found which should be drained and irrigated adequately with normal saline. Extensive bowel necrosis is the finding often observed which needs massive bowel resection that leads to short bowel syndrome which is difficult to manage on long-term basis. Higher antibiotics like piperacillin, meropenem are required. Ventilator support, total parenteral nutrition (TPN) haemodialysis support and critical care management is required. Postoperative peritonitis has got high mortality and morbidity.

OTHER FORMS OF PERITONITIS

1. Meconium peritonitis.
2. Chronic bacterial peritonitis—tuberculous.
3. Chronic nonbacterial peritonitis—granulomatous peritonitis due to talc or starch (from surgical gloves)—starch peritonitis.
4. Gonococcal peritonitis with perihepatitis—*Curtis-Fitz-Hugh syndrome.*
5. ***Familial periodic peritonitis (Familial mediterranean fever):*** A rare entity gets recurrent pain abdomen often after appendicectomy. It is familidal, common in Arabs, Americans and Jewish populations. It is common in children; common in females; associated with MEFV gene mutation. Specific gene produces a protein—pyrin from neutrophils in these patients. Peritoneum adjacent to spleen and gallbladder are inflamed. But these two organs are normal. It is common in children and common in girls/females. Pain is usually in upper quadrant, left side. There is localised peritoneal inflammation. It is treated conservatively using colchicines.
6. ***Parturition/abortion peritonitis***: It occurs after delivery and abortion conducted without asepsis and instrumentation, incomplete instrumental abortion, uterine perforation with or without bowel injury. It causes pelvic peritonitis commonly, generalised peritonitis often. It is due to anaerobic bacteria, anaerobic streptococci, and gram-negative bacteria like *Escherichia coli*. It is often rapidly progressive causing septic shock. It needs emergency surgery. Complications are ARDS, intestinal obstruction, faecal fistula and intraperitoneal abscess formation.



Fig. 9.15: Perforation in the fundus of the uterus due to attempted abortion. It caused severe peritonitis.

PELVIC ABSCESS

- It is the most common intraperitoneal abscess (50-60%).
- It is the collection of pus in rectovesical or rectouterine pouch (pouch of Douglas).

Causes

- Appendicitis.
- Pelvic infections.
- Sequelae of diffuse peritonitis.
- Postoperative and other abdominal causes.

Bacteria: Bacteroides fragilis, *E. coli,* anaerobic streptococci.

Note:

Waltman-Walters syndrome: It is postcholecystectomy fluid collection in subphrenic space causing compression over IVC. It mimics coronary thrombosis.

The mother's heart is child's schoolroom.—**Henry Ward Beecher.**


Bladder
Abscess
Rectum

Fig. 9.16: Pelvic abscess.

Clinical Features

- Diarrhoea.
- Mucus discharge per rectum.
- High temperature with chills and rigors.
- Lower abdominal pain and distension.
- Frequency and burning micturition.
- P/R shows a soft, boggy, and tender swelling in the anterior wall of the rectum.

Investigations

- TC is raised.
- U/S is diagnostic—shows pus in rectovesical or pouch of Douglas.
- CT scan to find out the size and extent.



Fig. 9.17: CT pelvis showing pelvic abscess.

Treatment

- After starting antibiotics, under G/A, abscess is drained **per rectally**, through the boggy area. Catheter is passed to the bladder before draining the pus.
- In females, *posterior colpotomy* is done to drain the *pus*.
- Occasionally spontaneous rupture of the abscess into the rectum occurs leading to natural regression.
- When abscess is very large, when it is progressing into the general peritoneal cavity or when in doubt, laparotomy through lower abdomen incision is done to drain the pus and to correct the cause. Often in such cases, drainage tube can be placed through the abdomen under U/S guidance.
- CT or US guided insertion of drainage tube into the abscess cavity per rectally or per vaginally or percutaneously.
- But most often laparotomy is not necessary.


Intestine
Pelvic abscess
Rectum
Urinary bladder
Drainage through anterior wall of the rectum
In male patient
A
Urinary bladder
Uterine cavity
Intestine
Pelvic abscess
Rectum
In female patient
Posterior colpotomy to drain pelvic abscess
B

Figs 9.18A and B: In male, pelvic abscess is drained through an incision over the anterior aspect of the rectum. In female, it is drained through posterior colpotomy.

SUBPHRENIC SPACES AND SUBPHRENIC ABSCESS

Surgical Anatomy (By Boyd)

There are four intraperitoneal and three extraperitoneal spaces.


1
7
2
3
GB
4
5
6
1. Right anterior space
2. Left anterior space
3. Left posterior space
4. Right posterior space
5. Right perinephric space
6. Left perinephric space
7. Bare area of the liver

Fig. 9.19: Subphrenic spaces.

Intraperitoneal Spaces

Right anterior intraperitoneal space (Right subphrenic space): It is bounded by right lobe of the liver and diaphragm, posteriorly by anterior layer of coronary and right triangular ligament, and to the left by falciform ligament.

Causes: Abscess here occurs due to cholecystitis, perforated duodenal ulcer, postoperative, appendicitis, duodenal cap blow out.

Right posterior intraperitoneal space (Right subhepatic space): (*Rutherford Morison's kidney pouch*) is bounded in front by the liver and gallbladder, above by the liver, behind by the right kidney and diaphragm, below by the transverse colon and hepatic flexure, to the left by foramen of Winslow and duodenum. It is large and deepest space of all. *It is the most common site of subphrenic abscess.*

Causes: Appendicitis, cholecystitis, postoperative, perforated duodenal ulcer, intestinal obstruction.

Left anterior intraperitoneal space (Left subphrenic space): It is bounded above by the diaphragm, behind by left lobe of liver and left triangular ligament, gastrohepatic ligament and anterior surface of the stomach, to the right is the falciform ligament.

Causes for abscess here are surgeries of the stomach, tail of the pancreas, spleen, colon (splenic flexure), diverticulitis.

Left posterior intraperitoneal space: It is bounded by stomach, pancreas, greater omentum, liver, transverse colon (Lesser sac).

Most common *cause* here is pseudocyst of pancreas. Rarely perforated gastric ulcer.

Extraperitoneal Spaces

Right extraperitoneal space is right perinephric space **and left extraperitoneal space** is left perinephric space.

Causes: Abscess here are due to tuberculosis, trauma, haematoma.

Midline extraperitoneal is *bare area* of the liver. Pus collects here commonly due to ruptured amoebic liver abscess and pyogenic abscess of the liver.


Subphrenic abscess
Colonic resection
Gangrenous bowel
4
3
7
7
2
5
7
7
7
1
1. Appendicitis
2. Perforated duodenal ulcer
3. Cholecystitis
4. Amoebic liver abscess
5. Pancreatitis
6. Splenectomy
7. Postoperative
– Cholecystectomy
– Gastrectomy
– Biliary surgery
– Pancreatic surgeries
– Colonic surgeries
– Surgery for peritonitis, gangrene bowel
– Pelvic surgery

Fig. 9.20: Common causes of subphrenic abscess both right and left. Subphrenic abscess is common on right side.

Pathology of Subphrenic Abscess

- During expiration, intra-abdominal pressure (especially in subphrenic area) is reduced and so this with capillary action and upward movement of the diaphragm make the peritoneal fluid to move upwards towards the diaphragm. This is the reason why there is higher incidence of subphrenic abscess and *subphrenic abscess is the second most common type of intra-abdominal abscess,* first one being the pelvic abscess.
- Subphrenic abscess is more common on the right side than on left (left anterior) because infective conditions are more common on the right side (like appendicitis/perforation/liver abscess/cholecystitis); and right paracolic gutter is wide and deep without any barrier (unlike left side paracolic gutter which is narrow and limited above by colophrenic ligament). Left posterior space is lesser sac in which infected fluid commonly collects following pancreatitis. Right subphrenic abscess causes elevation of the diaphragm. Pus collects in front or posterior aspect of the liver (right anterior or right posterior spaces) or often in both. Pus may be in a single cavity or may be multiloculated. Occasionally pus may get thickened to form a thick fibrous wall around leading into a chronic stage which causes generalised ill health. Pus gets well localised with a thick pyogenic membrane pushing pleura away and above and peritoneum away and below making subphrenic abscess essentially *extraserosal*. Because of the congestion/hyperaemia of the pleura and elevation of the diaphragm, there will be *sympathetic pleural effusion* on the side of the abscess. In severe acute subphrenic abscess, empyema thorax can also occur.
- If infective organism is gas forming one, abscess will contain pus with gas. So it is resonant above the liver dullness; dull above it due to collapsed lung/atelectasis; then again resonant on topmost due to normal lung (From below upwards—dull liver—resonant gas in abscess cavity—dull collapsed lung—resonant normal lung topmost). But it is rare presently.

A superior man is modest in his speech, but exceeds in his actions.

- *Postoperative surgeries*—mainly of gastric/biliary/colonic and emergency surgeries (peritonitis) are *becoming most common cause* of the subphrenic abscess.

Clinical Features

Barnard's aphorism (Harold Barnard):
"*Pus somewhere, pus nowhere else, pus under diaphragm*".
History relevant of the specific causes; history of any previous surgery:

- Fever with chills and rigors.
- Pain in right hypochondrium, epigastrium or lower thorax.
- Tenderness in right hypochondrium.
- Sympathetic right sided pleural effusion due to congestion and hyperaemia of the diaphragm.
- Collapse of the lung/basal atelectasis—right side may be evident. Tachypnoea and respiratory distress can be observed.
- Pain in the right shoulder due to irritation of phrenic nerve.
- Hiccough, tachycardia.
- ***Hoover's sign***: Scoliosis towards same side in subphrenic abscess.
- Wasting and anorexia is common.
- Occasionally tender mass in the right hypochondrium may be palpable.
- Tenderness over 11th intercostal space may be evident in right subhepatic space abscess.

Bacteria causing:

- *E. coli.*
- *Klebsiella.*
- Streptococci.
- Anaerobic organisms.

Differential diagnosis

- Amoebic liver abscess
- Pylephlebitis
- Empyema
- Pulmonary collapse

Investigations

- Plain X-ray chest and abdomen shows soft tissue shadow, pleural effusion, tenting of diaphragm, collapse of the lung. Fluoroscopy shows elevated right diaphragm with reduced right sided diaphragmatic movement.



Fig. 9.21: CT scan of abdomen showing subphrenic abscess.

- U/S abdomen confirms the diagnosis.
- TC is high. There is raise in 'C' reactive protein.
- CT scan is very useful to find out the extent and relation. CT shows 'rind' sharp outer margin; septations; size, shape, extent, diaphragmatic position, pleural changes, displaced bowel and other organs and communications.
- Gallium 67 or iridium 111 isotope imaging.

Treatment

- **Antibiotics:** Ampicillin, metronidazole, gentamicin, cephalosporins.
- **Percutaneous drainage:** Initially ultrasound guided aspiration is useful. Here, under ultrasound or CT guidance, a catheter is placed and pus is drained. Catheters used are pigtail catheter, 16 French trocar catheter or sump catheter. 90% of subphrenic abscess are drained percutaneously.

Note:
Aspiration alone is not done in subphrenic abscess.

- **Open drainage is indicated** (Required in 10-20% of cases) in:

- When symptoms persist
- When abscess increases in size
- When there is thick pus or multiloculated pus or multiple abscesses
- Failure of/contraindications for catheter drainage
- Multiple abscesses
- Presence of foreign body/necrosis/haematoma/obstruction/fistula

  - Under G/A through anterior or posterior subcostal incision, abscess is approached extraperitoneally and extrapleurally (extraserosally), so as to prevent serosal contamination. Pyogenic membrane is opened, pus is collected for culture sensitivity. Pus is drained by breaking all loculi. Malecot's catheter is placed *in situ*.
  - Both *anterior and posterior extraperitoneal approaches* are used. Posterior approach allows dependent drainage; anterior approach (Clairmont approach for left side) is technically easier and allows proper assess.
  - *Transperitoneal approach* is needed whenever definitive procedure has to be undertaken like managing the existing fistula, treating the cause, removal of foreign body, multiple abscesses, active intra-abdominal pathology, etc.
- Antibiotics are continued. Malecot's catheter is removed once pus stops draining, usually after 14 days, which can also be confirmed by U/S abdomen or by X-ray with injection of dye.

Catheters used for drainage are:

- Malecot's catheter/wide Foley's catheter when open drainage is done
- Pigtail catheter
- Catheter placement through trocar under guidance (16 French trocar catheter)
- Sump catheter (double lumen tube which allows irrigation as well as suction drainage)

Note: Catheter is removed when pus drainage from the tube is <10 ml/day, normal total count, improvement in symptoms, U/S shows clearance of abscess cavity.

- Good nutritional supplement, respiratory physiotherapy are additional support required.

Complications

- Empyema.
- Respiratory arrest.
- Septicaemia.
- Sinus formation.
- Recurrence.
- Peritonitis.



Fig. 9.22: Subphrenic abscess open drainage. Incision must be extraserosal. Malecot's tube is placed in the abscess cavity.

MESENTERIC CYSTS

Causes

1. Chylolymphatic.
2. Enterogenous.
3. Cysts of urogenital remnant.
4. Teratomatous dermoid cysts.
5. Other causes:
    - Traumatic haematoma and cyst formation.
    - Tuberculous cold abscess of mesentery.
    - Hydatid cyst of mesentery.

Chylolymphatic cysts are the most common one.

- It arises from congenitally misplaced lymphatic system. It does not have efferent communication into lymphatic system.
- Common in ileum, is a thin walled cyst with flat endothelium occasionally containing lymph or chyle, which is either milky or cream coloured.
- It is solitary and commonly unilocular, with loop of the bowel in front.
- It has got independent blood supply, i.e. not from the adjacent bowel loop. So enucleation can be done without resecting bowel.
- They are often called as *non-neoplastic mesothelial cysts* as it is lined by mesothelium. It is common in small bowel mesentery (60%); but can occur in colonic mesentery (40%). It occasionally may contain chyle even though serous fluid is the common content. It is common in females.
- Cyst is *enucleated* surgically (*standard therapy*); aspiration should not be done; in a large cyst internal drainage of cyst into the peritoneal cavity is advocated by few. Cyst wall should be sent for histology to rule out neoplastic condition.

Enterogenous type arises as a diverticulum or duplication from the adjacent bowel.

Hence it is a thick walled cyst (contains all layers of the bowel) and receives its blood supply from the adjacent bowel (not independent). So resection of the adjacent bowel along with the cyst is essential. Enucleation is contraindicated.



Fig. 9.23: Mesenteric cyst.

Clinical Features

- It presents as a painless abdominal swelling in umbilical region, smooth, fluctuant, not moving with respiration.



Fig. 9.24: Mesenteric cyst.

- It is common in 2nd decade, often in childhood.
- It is freely mobile, mobile in the direction perpendicular to the line of mesentery.
- There is a band of resonance in front of the cyst.
- Presentation as complications.

Tillaux's triad

- Soft, smooth swelling in the umbilical region
- Freely mobile in a direction perpendicular to mesentery
- Zone of resonance all around

Complications of mesenteric cysts

- *Torsion of cyst* can lead to volvulus of the adjacent bowel
- *Rupture of the cyst*
- *Haemorrhage* into the cyst
- *Infection*—patient presents with acute painful swelling in umbilical region

Clothe yourselves with compassion, kindness, humility, meekness and patience.



Fig. 9.25: Mobility of mesenteric cyst.

Investigations

- U/S abdomen.
- Barium meal X-ray.
- Plain X-ray abdomen.
- CT scan of the abdomen is diagnostic.

Differential Diagnosis

- Hydronephrosis.
- Omental cysts.
- Tuberculosis.

Treatment

- In chylolymphatic cyst—*enucleation.*
- In enterogenous type, removal of the cyst with resection of adjacent bowel is done, because blood supply is from adjacent bowel.

MESENTERIC PANNICULITIS

- It is an inflammatory disease of mesentery with mesenteric *fat necrosis, acute/chronic inflammation and fibrosis*.
- Enormous thickening of the mesentery near its root with multiple discrete nodules are typical. Venous and lymphatic obstruction of mesentery develops, causing bowel oedema, congestion and ischaemia.
- It commonly involves small bowel mesentery; but can involve colonic mesentery also. Spontaneous resolution is known to occur.
- It is common in middle aged men. Recurrent abdominal pain, features of obstruction, distension of abdomen, tender resonant mass abdomen are the features.
- ESR and CRP is elevated. CT is useful with features like—pseudocapsule with well delineated fat margin; normal adipose tissue surrounding the mesenteric vessels—*fat ring sign*; no vascular deviation; intra-abdominal mass displacing bowel without infiltration. Laparoscopic biopsy of mesentery is conclusive.
- *Differential diagnoses* are—peritoneal carcinomatosis, carcinoid tumour, mesenteric or retroperitoneal sarcoma, mesenteric tuberculosis and intestinal obstruction.
- *Treatment:* Usually conservative using corticosteroids and immunosuppressive drugs. Laparotomy is done only when diagnosis is in doubt or intestinal obstruction is suspected.

ACUTE MESENTERIC LYMPHADENITIS

- It is nonspecific acute inflammation of the mesenteric lymph nodes (*Nurse's syndrome*) usually due to *Yersinia enterocolitica* infection; often in 30% of cases respiratory infection will be present. Occasionally virus, parasite, fungal infections may also be the cause. Other regional lymph nodes (axilla, groin, neck) are also often involved and enlarged.
- Mesenteric nodes in ileocaecal region are inflamed, enlarged often clinically palpable in right iliac fossa. Lymph nodes are red but not attached to mesenteric leaves or peritoneum. Appendix is normal.
- It is self-limiting recurrent disease.
- It is common in children and young females.
- Pain in right iliac fossa, slight fever, vomiting, abdominal colicky, but normal bowel habits; tender nodes may be palpable in RIF.
- Leucocytosis is common but regresses rapidly. US abdomen will be normal.
- Condition often mimics acute appendicitis.
- *Treatment:* Bed rest, re-assurance, analgesics, follow-up. Laparoscopy and appendicectomy is often needed to diagnose and to prevent missed appendicitis.

MESENTERIC MALIGNANCY

- The most common mesenteric malignancy is *secondaries*. GI adenocarcinoma is the most common site of origin. Carcinoid also can cause mesenteric metastasis. Mesentery is involved by either direct spread or through lymphatics or transperitoneal route. Distortion, fixation, desmoplastic reaction with intestinal obstruction are the features.

Mesenteric Desmoid Tumour

- It is the most common primary tumour of mesentery.
- It is common in familial adenomatous polyposis and Gardner's syndrome.
- FAP shows 75% intra-abdominal desmoid with 75% of them in mesentery.
- Mesenteric desmoid is aggressive tumour causing infiltration of adjacent structures.
- *Complications* are—intestinal obstruction, bowel necrosis and perforation, hydronephrosis, aortic erosion and bleeding.
- 10-year survival rate is 65%. But recurrence rate is also high—75%.
- *Investigations:* CT abdomen, laparoscopy and biopsy, colonoscopy in case of FAP, to look for other features of Gardner's syndrome.
- *Treatment:* Even though surgery is the treatment, in view of high recurrence rate and inability to clear tumour surgically, drug therapy is becoming popular many times. Drugs used are—sulindac; antiestrogen drugs, imatinib mesylate orally (inhibits tyrosine kinase receptor for PDGF and c-kit).

Mesenteric Lymphoma

It is also *not uncommon* as mesenteric fold contains plenty of lymph nodes. It is commonly NHL type. Other regional lymph nodes like of para-aortic, axillary, neck region may be enlarged. Liver and spine may be involved. CT abdomen, peripheral smear, laparoscopy and node biopsy, CT chest, bone marrow biopsy are investigations done. Treatment is usually chemotherapy.

MESENTERIC TRAUMA

Mesenteric injury is commonly seen in blunt abdominal trauma; traction injury or seatbelt injury causes mesenteric tear. Penetrating injury can also cause mesenteric injury.

Presentations

Features of haemoperitoneum—shock, pallor, abdominal distension and pain, guarding and rigidity.

Types

1. *Transverse tear* in mesentery causes not only more bleeding but also causes adjacent bowel ischaemia. So laparotomy and resection of bowel is needed.
2. *Longitudinal tear* can be sutured using interrupted absorbable sutures (vicryl) after haemostasis.

Investigations

- Us abdomen; diagnostic peritoneal lavage.
- CT abdomen.
- Always evaluate for associated injuries—fractures, thoracic and head injuries.
- Haematocrit, electrolyte estimation, blood grouping.

Treatment

Emergency laparotomy and resection of bowel or suturing of the mesentery.

PERITONEAL MALIGNANCY

The most common peritoneal malignancy is *secondaries*. Primaries causing peritoneal secondaries are—*GIT*: stomach, colon, pancreas, small bowel, liver, lower oesophagus; *Genitourinary*: ovarian tumour commonly; *Extra-abdominal*: Breast.

Peritoneal carcinomatosis is diffuse metastatic deposits all over parietal and visceral peritoneum.

Primary Peritoneal Malignancy

The most common is malignant mesothelioma; sarcomas are rare type.

Malignant mesothelioma: It is very aggressive primary type with survival rate of 6-12 months. Presentation is abdominal pain, ascites, weight loss, and cachexia. Omentum is involved with malignant nodules presenting like a nodular abdominal mass. Peritoneal cavity is studded with nodular deposits. Entire peritoneal cavity is involved often involving the organs like


Normal mesentery with vasculature
Bowel segment ischaemia
Horizontal mesenteric tear
Resection and anastomosis is done
Longitudinal tear
No bowel ischaemia
Tear in the mesentery is sutured after haemostasis

Fig. 9.26: Mesenteric tears due to trauma can be transverse or longitudinal; transverse tear needs bowel resection; longitudinal tear needs just suturing.

I am a great believer in luck and I find the harder I work, the more I have of it.

liver or their surfaces. It is often difficult to differentiate it from peritoneal carcinomatosis. However, extra-abdominal spreads to lungs and bone is uncommon in malignant mesothelioma. CT abdomen, ascitic fluid analysis are the diagnostic methods. Chemotherapy, intraperitoneal hyperthermic perfusion of mitomycin C, intraperitoneal chemotherapy of cis platin, surgical peritonectomy—are *treatment* options.

Pseudomyxoma Peritonei

- It is a rare malignant condition that develops due to ruptured malignant ovarian cyst or adenocarcinoma of appendix. Peritoneum is coated with mucus secreting tumour tenacious gel like mucus with cystic masses. It is common in old aged females.
- Vague abdominal pain with distension and dullness which is not shifting are typical findings. CT scan shows bowel displacement with fluid content in the peritoneal cavity.
- *Treatment:* If origin is known then it is treated accordingly. In patients operated by appendicectomy, removal of all mucus gel with right hemicolectomy with omentectomy is done. If ovarian tumour is the cause then panhystrectomy with omentectomy is done. In cases with unknown cause, after laparotomy, panhystrectomy, right hemicolectomy, omentectomy are done. Intraperitoneal chemotherapeutic agents like 5 FU, mitomycin C, oxaliplatin; intraperitoneal instillation of mucolytic agents like dextran, urokinase after surgery is beneficial.
- It shows better prognosis compared to mesothelioma and carcinomatosis.

Peritoneal carcinomatosis (carcinoma peritonei)

- Entire peritoneal cavity is studded with carcinomatous nodules—both parietal and visceral peritoneum
- Haemorrhagic ascites, interloop bowel adhesions, hard studded nodules in the omentum are common. Intestinal obstruction can occur
- It may be primary peritoneal carcinomatosis (mesothelial) or secondary from GIT, ovary, breast, pancreas
- Liver secondaries are often present
- It mimics peritoneal tuberculosis, acute pancreatitis, and multiple lymphomatous nodules, multiple peritoneal hydatids
- As malignant ascitic fluid contains high immunoglobulin, peritonitis is not common
- Instillation of radioactive gold and chemotherapy are the treatment
- It has got poor prognosis

OMENTAL CYST

- It arises from obstruction of omental lymphatics either congenital or acquired.
- It is unilocular or multilocular cyst lined by endothelium.
- It is common in children.
- When it attains large it presents as mass in central or lower abdomen which is smooth well localised mobile often moves with respiration.
- It can cause torsion, rupture and infection. Extrinsic compression of bowel can occur.
- US/CT shows cyst with internal septations.
- Differential diagnoses are—mesenteric cyst, retroperitoneal cyst and desmoid tumour.
- Treatment is laparotomy and cyst excision which can also be done laparoscopically.

OMENTAL TORSION

- Torsion of greater omentum is twist of omentum along its longitudinal axis; it usually occurs on right side of omentum.
- Primary torsion is torsion occuring without any existing cause.
- Secondary torsion is occurring due to some cause like omentocele in a hernial sac or tumour or adhesion.
- Torsion is more common in men (2:1) in 5th decade.
- Sudden severe abdominal pain, mainly right sided often mimicking acute appendicitis, cholecystitis, ureteric stone or twisted ovarian cyst.
- Often signs of peritonitis may be present.
- CT abdomen is diagnostic. Total count will be raised.
- Treatment is laparotomy and omentectomy which can also be done laparoscopically.

OMENTAL TUMOUR

- Metastatic omental deposits are common; usually from GIT cancers.
- Primary neoplasm of omentum is rare. It may be soft tissue tumour arising from fat of omentum.



Fig. 9.27: Omental secondaries.

Chapter 10 Abdominal Tuberculosis

> *In man the balance between immunity and susceptibility to tuberculosis is delicately adjusted: There is a small factor of safety.*
>
> —**Milton Rosenau,** 1927

CHAPTER OUTLINE

- Abdominal Tuberculosis
- Ileocaecal Tuberculosis
- Ileal Tuberculosis
- Peritoneal Tuberculosis
- Tuberculous Mesenteric Lymphadenitis
- Ano-recto-sigmoidal Tuberculosis
- Tuberculosis of the Omentun

ABDOMINAL TUBERCULOSIS

It is common in India and developing countries.

It is the 6th most common type of extrapulmonary tuberculosis. Its incidence is high in HIV infected patients.

Types

1. *Intestinal*
   Ileocaecal region
   - Ulcerative—60%.
   - Hyperplastic.
   - Ulcero-hyperplastic.

   Ileal region, commonly:
   - Stricture type.
2. *Peritoneal tuberculosis*
   a. Acute.
   b. Chronic.
      i. Ascitic type.
      ii. Encysted (loculated) type.
      iii. Plastic (fibrous/adhesive) type.
      iv. Purulent type.
3. *Tuberculosis of mesentery and its lymph nodes.*
4. *Ano-recto-sigmoidal*—present as fistula, fissure, abscess, mass.
5. *Involvement of liver, spleen and other organs as a part of miliary tuberculosis.*
6. *Tuberculosis of the omentum.*
7. *Rare types:* Oesophageal (0.2% of abdominal tuberculosis)/gastroduodenal (1% of abdominal tuberculosis)/retroperitoneal tuberculosis. Because of hydrochloric acid (acid media) gastric tuberculosis is rare.

Note:
- Chronic peritoneal tuberculosis may be associated with pleural effusion and pericardial effusion.
- Tuberculosis is not common in stomach, duodenum and jejunum.
- *Diffuse tuberculous colitis* is less commonly seen (4%), mimics ulcerative colitis in every respect even in colonoscopy. Patient recovers well with antituberculous drugs.
- *Intestinal tuberculosis is called as **Koenig's syndrome** (1892).*

Modes of Spread of Abdominal Tuberculosis

- By ingestion
  - Ingestion of food contaminated with tubercle bacilli causing *primary intestinal tuberculosis*.

Site spectrum	***Ileocaecal and terminal ileum—most common site***
• Luminal GI tuberculosis 75%	Jejunum and colon—less common
• Abdominal solid organ tuberculosis—liver, spleen, pancreas	Stomach, duodenum, oesophagus—rare
• Peritoneal tuberculosis—*adhesive* (cocoon/doughy/rolled up omentum)/*ascitic* (wet)—loculated. It could be acute or chronic	*Pathology:* • In malnourished poor resistance patients—ulcerative and or stricture types
• Abdominal lymph node tuberculosis—mesenteric/periportal/para-aortic/retroperitoneal. It could be caseating/hyperplastic/calcified	• In well nourished with good resistance—hyperplastic and nodular types
	• Combination types—ulcerostricture type; ulcero-hyperplastic type

Phthisis ia an ulcer of the lung that consumes the whole body.—**Bernard de Gordan,** 1495

Different clinical presentations of abdominal tuberculosis

Clinical presentation may be:

- Acute
- Acute on chronic
- Chronic

Constitutional symptoms:

- Low-grade fever, malaise, night sweats, anaemia, weight loss
- Observed in 30% of patients

Abdominal tuberculosis is 6th most common form of tuberculosis

It may be associated with HIV/lymphoma/carcinoma

Types:

- *Ulcerative*—diarrhoea and malabsorption
- *Stricture*—subacute or acute intestinal obstruction
- *Hyperplastic*—mass abdomen (RIF) and obstruction
- *Ascites*—generalised distension of abdomen
- *Peritoneal*—abdominal cocoon; vague abdominal pain, parietal peritoneal thickening as doughy abdomen; mass abdomen
- *Mesenteric*—tabes mesenterica, obstruction, mass
- Associated tuberculosis of other organs is seen in 30% of cases

Atypical presentations:

- Lower GI bleed, fistula-in-ano, PID like pain, gastric disease symptoms, dysphagia, GI fistulae, perforation

Tuberculosis of liver:

- Miliary type
- Granuloma/tuberculoma
- Like liver abscess/intra-hepatic calcification
- Obstructive jaundice
- PUO/altered LFT

Tuberculosis of pancreas:

- Like or part of miliary tuberculosis
- Common in immunocompromised
- Usually presents as acute or chronic pancreatitis
- Pancreatic mass or abscess may develop
- Can mimic malignancy

Tuberculosis of spleen:

- Disseminated or miliary form
- Can present as PUO with hepatosplenomegaly
- Can occur as multiple abscess

  - Ingestion of sputum containing tuberculous bacteria from primary pulmonary focus causing *secondary intestinal tuberculosis.*
- Haematogenous spread from tuberculosis of lungs.
- From neck lymph nodes (tuberculous cervical lymphadenitis—5-10%) through lymphatics.
- From fallopian tubes by retrograde spread to involve peritoneum (10%).

ILEOCAECAL TUBERCULOSIS

Most common site of abdominal tuberculosis due to presence of Peyer's patches; and stasis of luminal contents favoured by ileocaecal valve.



Fig. 10.1A



Fig. 10.1B

Figs 10.1A and B: Ileocaecal tuberculosis. (A) Note the multiple transverse undermined ulcers. (B) Note the ileocaecal tuberculosis with stricture.

Causative organism

Mycobacterium tuberculosis

- Acid fast 20% H_2SO_4
- Alcohol fast
- Gram neutral

Histology

- Epithelioid cells diagnostic
- Langhan's giant cells
- Features of granuloma
- Caseating necrosis

- *It is presently due to Mycobacterium tuberculosis,* earlier used to be due to *Mycobacterium bovis.* Mode of infection may be direct or blood spread, usually from lungs.
- Atypical mycobacteria can spread directly.
- *Mycobacterium avium* spreads through lymphatics.

Types

- *Ulcerative—most common 60%. Circumferential transverse often multiple 'girdle' ulcers*—with skip lesions. It is common in old, malnourished people. Long-standing ulcers cause fibrosis and later stricture formation. Stricture (*Napkin ring stricture*) is common in ileal part. Often related intestinal nodes are also involved with caseation, abscess (cold) formation. Bowel adhesions are common. Patient mainly presents with diarrhoea, blood in stool, loss of appetite and reduced weight.



Fig. 10.2: Obtuse ileocaecal angle—ileocaecal tuberculosis.

- *Hyperplastic*: Fibroblast reaction in submucosa and subserosa causing thickening of bowel wall and lymph node enlargement, leading to nodular mass (tumour-like) formation. It is 10% common, less virulent, with adequate host resistance, seen in young well nourished individuals. It is common in caecal part. It causes extensive chronic inflammation, fibrosis, bowel adhesions, nodal enlargement, often presents with mass in the right iliac fossa. Caseation necrosis is not common. When present as a mass, it can cause subacute intestinal obstruction. It is commonly primary intestinal tuberculosis. There is no primary focus in the lungs.
- *Ulcerohyperplastic*—30%.

Clinical Features

- Abdominal pain is the most common symptom (90%). It is dull in mesenteric type; colicky in intestinal type.
- Common in 25-50 years age group. Equal in both sexes.
- Anaemia, loss of weight and appetite (80%).
- Diarrhoea—10-20%.
- Fever—50-70%.
- *Mass in right iliac fossa*, (35%) which is hard, nodular, nonmobile, nontender with impaired resonance, which may mimic carcinoma caecum. Subacute obstruction can occur.
- Ileocaecal tuberculosis can be associated with adenocarcinoma of caecum, or large bowel lymphoma or HIV.
- Often ileocaecal TB can cause intestinal obstruction (20%).

Ileocaecal region is common site due to:

- Stasis
- Abundant Peyer's patches—organisms get trapped in Peyer's patches
- Bacteria contact time with mucosa is more
- M cells in Peyer's patches phagocytose bacilli and transfer to host cells
- Liquid content in the region
- Increased rate of fluid and electrolyte absorption
- Minimal digestive activity

Differences between ulcerative and hyperplastic types of ileocaecal tuberculosis

	Ulcerative type (60%)		*Hyperplastic type (10%)*
1.	Secondary to pulmonary tuberculosis	1.	Primary GIT tuberculosis, could be due to bovine bacilli
2.	Virulent organism	2.	Less virulent organism
3.	Poor body resistance, old people	3.	Good body resistance, young individual
4.	Multiple transverse ulcers commonly in the ileum, often in the caecum	4.	Chronic granulomatous lesion in the ileocaecal region
5.	Clinically presents with diarrhoea, bleeding P/R, loss of appetite and reduced weight	5.	Presents as a mass in right iliac fossa
6.	Complications: Stricture, intestinal obstruction	6.	Complication: Subacute intestinal obstruction
7.	Chest X-ray shows primary lesion	7.	No primary lesion in chest X-ray
8.	Barium study shows ileal strictures with hypermotility	8.	Barium study—pulled-up caecum, obtuse ileocaecal angle

> *Whilst meagre Pthisis gives a silent bow, her strokes are sure, but her advances slow. No loud alarms, nor fierce assaults are shown. She starves the fortess first, then takes the town.*
> **—Samuel Garth**



Fig. 10.3: Ileocaecal and mesenteric tuberculosis.

Differential diagnosis

- Carcinoma caecum
- Ameboma
- Appendicular mass
- Ectopic kidney
- Retroperitoneal tumour
- Lymph node mass
- Psoas abscess
- Crohn's disease



Fig. 10.4: Ileocaecal tuberculosis or tuberculous mesenteric lymphadenitis can present as mass in the right iliac fossa which is usually nontender, nonmobile, hard/firm resonant/impaired resonant.

Investigations

- Chest X-ray to find out primary focus.
- Mantoux test, ELISA (90%), SAFA (soluble antigen fluorescent antibody—80%), serum IgG.
- ESR is raised.
- U/S abdomen to see ascites, caecal thickening, nodal status and other organs.
- Plain X-ray abdomen, if presentation is of intestinal obstruction. It often shows calcification. It shows calcified lesion in the bowel; in the lymph node; in the liver (calcified granuloma). Perforation when it occurs (rare) shows gas under diaphragm.

Barium study X-ray (Enteroclysis followed by barium enema or barium meal follow through X-ray) (efficacy—75%)

- Pulled up caecum, conical caecum, pulled down hepatic flexure
- Obtuse ileocaecal angle
- Hurrying of barium due to rapid flow and lack of barium in inflamed segment (*Steirlin sign*)
- Narrow ileum with thickened ileocaecal valve *(Fleischner sign)* *(Inverted umbrella sign)*
- Calcifications
- Incompetent ileocaecal valve, ileocaecal spasm
- Ulcers and strictures in the terminal ileum and caecum—*Napkin lesions*
- Earliest signs are—increased transit time; hypersegmentation (chicken intestine); flocculation of barium
- Other signs are—persistent narrow stream (string sign); multiple strictures with enormous dilatation of proximal ileum (mega ileum); straightening of ileocaecal junction with 'goose neck' deformity



Figs 10.5A and B: Pulled-up caecum, obtuse ileocaecal angle—ileocaecal tuberculosis in barium study X-ray.

- Colonoscopy is of value to rule out carcinoma. It is *easiest and most direct method* in establishing the diagnosis. Colonoscopy shows mucosal nodules or ulcers; caecal and ileal strictures; deformed ileocaecal valve; mucosal oedema and pseudopolyps and occasionally diffuse colitis. Biopsy can be taken to confirm the diagnosis. Tissue culture or tissue PCR can be done.
- Capsule endoscopy is also useful to see small intestinal (tuberculous) pathology in difficult cases.
- FNAC of palpable mass.
- Laparoscopy is very useful method of investigation. Transabdominal peritoneoscopy is visualisation of the peritoneal cavity using endoscope through a small incision in the abdomen. It aids in visualisation, to collect ascitic fluid for analysis and to take biopsy. Biopsy can be taken from omentum, peritoneum, nodes and suspected areas. Ascitic fluid can be collected for analysis.



Fig. 10.6: Laparoscopic view of abdominal tuberculosis showing peritoneal nodules and thickening, ascitic fluid, bowel surface tubercles. Fluid for analysis, peritoneal, omental biopsy can be taken.

- Abdominal CT scan is better and more reliable.
- PCR assay of endoscopically biopsied tissue or of ascitic fluid. DNA—PCR can detect 1-2 organism or 8 fg of mycobacterial DNA. Positive PCR signifies infection but need not be active disease.
- Stool culture for AFB—not useful. Presence of tuberculous bacteia in stool does not signify disease.
- Blind percutaneous needle peritoneal biopsy using *Cope's/ Abraham's needle* is also practiced.
- Ascitic tap fluid analysis.
- Anticord factor antibody to differentiate it from Crohn's disease.
- Biochemical assay—proteins, ADA (Adenosine deaminase activity) and interleukins. ADA is specific and sensitive marker with 95-98% sensitivity and specificity. Its value more than 33 IU/litre in ascitic fluid and more than 42 IU/litre in serum is significant. Gamma interleukin is two times more expensive than ADA.

Note:

Serum ADA > 54 U/l; asctic ADA > 33 U/l; ascitic fluid: serum ADA > 0.985.

- **Bactec MGIT broth culture:** It is *Mycobacterium* growth indicator tube culture system containing Middlebrook Broth with silicon base; fluorescent technology is used.

Method used to isolate tuberculous bacteria	***AFB/ml specimen***	***Time taken for reporting***	***Sensitivity***	***Specificity***
Ziehl-Neelsen stain microscopy	5,000-10,000/ml	1-2 hours	75%	85%
Lowenstein Jenson solid media culture	100/ml	4-8 weeks	80%	90%
Bactec MGIT broth culture	10/ml	2-6 weeks	94%	92%
COBAS Taq-man PCR	Less than 10/ml	24-48 hours	97%	99%

Ascitic fluid in abdominal tuberculosis

- Exudate with protein level > 2.5 g/dl
- Serum-ascitic fluid albumin gradient is < 1.1
- Lymphocyte predominant cells with count as high as 4000/mm^3 > 250/cumm
- AFB in ascitic fluid is seen only < 3% cases
- ADA (Adenosine deaminase activity) in ascitic fluid (95% specificity and 98% sensitivity)
- Specific gravity >1.016
- Glucose < 30 mg
- Decreased pH
- LDH more than 90 units/litre

Ultrasound features observed in abdominal tuberculosis

- Thickened bowel wall, mesentery, omentum, peritoneum
- Loculated ascites with fine septae
- Interloop ascites with alternate echogenic and echofree areas—Club-sandwich appearance
- Bowel loop radiates from its mesenteric root—*stellate sign*
- Mesenteric thickness *more than 15 mm*
- Hepatosplenomegaly
- Lymph nodal enlargement matted
- Pulled up caecum presenting with a mass in subhepatic region and also sonologically visible—"pseudokidney sign"
- Concentric uniform mural thickening

CT scan in abdominal tuberculosis

- It is very useful and reliable investigation
- It is done with oral contrast—CT enteroclysis
- Findings are:
  - Thickened bowel wall, thickened peritoneum
  - Ileocaecal valve thickening
  - Enlarged/necrosed/matted mesenteric nodes often with cold abscess
  - Adhesions
  - Mesenteric thickening and nodules
  - Nodules in the peritoneum/solid organs like liver
  - Adhesions in the bowel/stricture/dilatations of the bowel/features of obstruction
  - Loculated ascites
- CT guided FNAC/biopsy/aspiration of fluid can be done

Complications of abdominal tuberculosis

- Obstruction—20%
- Malabsorption, blind loop syndrome
- Dissemination of tuberculosis to other areas of abdomen as well as extra-abdominal sites
- Faecal fistula
- Cold abscess formation
- Haemorrhage, perforation (rare)

Note:

Perforation is **rare** in GIT tuberculosis **but can occur**.

A man carries success or his failure with him; it does not depend on outside conditions.

Treatment

Drugs

- INH; rifampicin; pyrazinamide; ethambutol—*first line drugs*. In drug resistance cases second line drugs are needed. WHO recommends 6-9 months course. Commonly patient presents with complications and late presentations are also common in many. So, more often treatment for one year may be required in these patients. Recurrent abdominal tuberculosis has got high mortality and difficult to manage.



Figs 10.7A and B: CT scan of abdomen showing features of abdominal tuberculosis.

- As they are malnourished supportive therapy in the form of TPN, blood transfusion in preoperative as well as postoperative period is required. Often steroid is used to prevent adhesions along with antituberculous drugs.

Surgery

Indications for surgery

- Intestinal obstruction.
- Severe haemorrhage.
- Acute abdominal presentation like perforation.
- Intra-abdominal abscess formation or fistula formation.
- Uncertain diagnosis.

Surgeries are:

- *Limited ileocaecal resection* (with 5 cm margin) is the surgical therapy of choice for ileocaecal tuberculosis. This may be done in initial period depending on the obstructive and other presentations. Often during therapeutic period, healing with fibrosis causes stricture and obstruction in 3-6 weeks after drug therapy. Patient during this time needs limited ileocaecal resection.
- In single ileal stricture—stricturoplasty may be done. But if bowel wall is oedematous and friable then resection would be the ideal choice.
- In multiple strictures resection of ileum and anastomosis is done (ideal). Multiple strictures with long segment gaps between each can be treated by multiple stricturoplasty. But viability of the sutured area should be ensured. Resection is better option for stricture within 10 cm of ileocaecal valve.
- In perforation of ileal bowel, resection and anastomosis is done. Biopsy from perforation site and closure can be done in early perforations but chances of leak and fecal fistula formation is high (due to closure of perforation over a diseased bowel) and so resection is better option. In severely contaminated peritoneum, resection and exteriorisation is done. Bowel continuity is maintained after proper antituberculous chemotherapy and proper nutritional improvement.
- During therapy, if patient develops ileocaecal obstruction, ileotransverse colon anastomosis (bypass) can be done. But this is not a good procedure as it causes blind loop and tuberculous focus is retained. Now this bypass is used only in patient presenting with acute intestinal obstruction with poor general condition and in high-risk group patients as a life-saving procedure. A definitive second stage right hemicolectomy is needed in these patients at a later period.
- Adhesive obstruction may be released through laparoscopic adhesiolysis. It is often technically difficult to release dense adhesions even by open method.
- Drainage of intra-abdominal abscess, perianal abscess and treatment for tuberculous fistula-in-ano is done when necessary.



Fig. 10.8A



Figs 10.8B and C

Figs 10.8A to C: Ileocaecal limited resection with 5 cm bowel margin is the treatment of choice for ileocaecal tuberculosis.

ILEAL TUBERCULOSIS



Fig. 10.9: Ileocaecal tuberculosis with rolled up omentum. Note the sites and tubercles in ileocaecal valve, which will be incompetent due to fibrosis.

- It is usually *stricture* type.
- It may be multiple.
- It presents usually with intestinal obstruction.
- Bowel adhesion, localisation, fibrosis, secondary infections are quiet common.
- Perforation (5%) though rare culminates in peritonitis.
- Plain X-ray shows multiple air fluid levels.
- Treatment *is resection and anastomosis and to continue anti-TB drugs*.
  Often *stricturoplasty* is beneficial.



Fig. 10.10: Barium enema X-ray showing stricture in ileocaecal region due to ileocaecal tuberculosis.

PERITONEAL TUBERCULOSIS

Peritoneal tuberculosis

- Post-primary
- Becoming more common
- Activation of long-standing latent focus
- Blood spread
- Can develop from diseased mesenteric lymph node, intestine or fallopian tubes

Pathology in Peritoneal Tuberculosis

- Enormous thickening of the parietal peritoneum with multiple tiny yellowish tubercles.
- Dense adhesions in peritoneum and omentum with content inside as small bowel looking like ***abdominal cocoon***. It may precipitate intestinal obstruction.
- Multiple dense adhesions between bowel loops and between bowel and peritoneum and omentum.
- Thickening of bowel wall with adhesions.

Great things are done by a series of small things brought together.

Types

1. Acute Type—Mimics Acute Abdomen

Exploratory laparotomy reveals straw-coloured fluid with tubercles in the peritoneum, greater omentum and bowel wall. It is an on-table diagnosis. Fluid is evacuated and collected for AFB study and culture. Omental biopsy is taken. Abdomen is closed (without a drain) with tension sutures to prevent burst abdomen. ATD is started.

Acute peritoneal tuberculosis

- Rare
- On-table diagnosis
- Features of peritonitis
- Due to perforation or rupture of mesenteric tuberculous lymph nodes

2. Chronic Tuberculous Peritonitis

- Present as abdominal pain, fever, ascites, loss of weight and appetite, abdominal mass, ***doughy abdomen (10%).***
- Peritoneum is thickened with multiple tubercles. Omentum is thick, ***fibrosed, rolled up***.
- Infection is usually from mesenteric lymph nodes, ileocaecal tuberculosis, from fallopian tubes rarely blood born (from lungs).
- *Laparoscopy is very useful in this type to diagnose.*



Figs 10.11A and B



Fig. 10.11C

Figs 10.11A to C: On-table findings in intestinal tuberculosis, of extensive involvement with multiple tiny tubercles, thickening, adhesions and involvement of mesenteric lymph nodes.

Ascitic form

- **Ascitic form** shows enormous distension of abdomen with dilated veins.
- It presents with congenital hydrocele in male with patent processus vaginalis, umbilical hernia, rolled up omentum, shifting dullness, fluid thrill, and mass abdomen.
- ***Ascitic tap*** reveals straw coloured fluid from which AFB can be isolated. Fluid is pale yellow, clear, rich in lymphocytes, with high specific gravity.
- Chest X-ray, Mantoux test are other required investigations.
- ATDs for one year is required. Repeat tapping may be required initially as part of the treatment.

Note:

Ascites may be *free or loculated; clear or complex; debris or septae; 'sliced bread' appearance***.**

Encysted (Loculated) ascites

- Ascites gets loculated because of the fibrinous deposition.
- Dullness, which is not shifting, is the typical feature.
- They may present as intra-abdominal mass, which may mimic ovarian cyst, retroperitoneal cyst or mesenteric cyst.
- Treatment is U/S guided aspiration along with ATD's.



Fig. 10.12: Abdominal distension with ascites due to abdominal tuberculosis.



Figs 10.13A and B: US picture showing ascites. Straw coloured ascitic fluid tapping done under US guidance.



Fig. 10.14: CT scan abdomen showing ascites due to tuberculosis.

Plastic type

- Here there are wide spread adhesions between the coils of the intestine (ileum commonly), abdominal wall, omentum, with distension of the small bowel, leading to blind loop, ileus, intestinal obstruction (subacute, acute), thickened parietal peritoneum.
- They get recurrent colicky abdominal pain, diarrhoea, wasting, and loss of weight, mass abdomen, and *doughy abdomen*.
- *Differential diagnosis*: Peritoneal carcinomatosis. Open/laparoscopic peritoneal biopsy is very useful tool to diagnose.
- They respond well for drug treatment. Surgery is indicated if obstruction occurs.



Figs 10.15A and B: Laparoscopic picture of loculated ascites due to abdominal tuberculosis. Fluid is getting aspirated using a needle under laparoscopic vision.



Fig. 10.16A

Example isn't the best way to teach, it's the only way.



Figs 10.16B and C

Figs 10.16A to C: Laparoscopy showing plastic type of abdominal tuberculosis and multiple tubercles over parietal and visceral surface of the peritoneum.

Purulent form

- It is invariably due to tuberculous salpingitis, presenting as a mass in the lower abdomen containing pus, omentum, fallopian tubes, small and large bowel.
- Cold abscess gets adherent to the abdominal wall, umbilicus and may form an umbilical fistula.
- Patient commonly has got genitourinary tuberculosis.



Fig. 10.17A



Fig. 10.17B

Figs 10.17A and B: Laparoscopy showing adhesions between bowel and abdominal wall due to tuberculosis.

- U/S, discharge study, X-ray abdomen and other investigations are useful.
- *Treatment:* ATD's are started exploration of umbilicus, exploration of fistula and bowel by pass is done.
- Prognosis is poor in this type.

Ascitic form	***Loculated form***
Insidious onset Fatigue, weight loss, fever, anorexia	Loculated abdominal swelling Ascites which is not shifting
Abdominal pain usually absent	Diagnosis—US guided aspiration
Abdominal distension usually without pedal oedema	Antituberculous drugs
Rolled up omentum is common association as mass	
Fibrous form	***Purulent form***
Widespread adhesion of bowel loops	Due to tuberculous salpingitis
Adhesions, matting and dilatation	Presenting as lower abdominal mass
Act as blind loop—malabsorption	Umbilical fistula, abdominal wall abscess can occur
Abdominal pain, loss of weight, *doughy abdomen* due to thickened parietal peritoneum, diarrhoea, often mass abdomen—are usual features	Cold abscess adherent to abdominal wall

TUBERCULOUS MESENTERIC LYMPHADENITIS

- Infection is usually through the Peyer's patches of the intestine (i.e. through oral cavity). Usually several lymph nodes are involved often causing massive lymph node enlargement. Commonly right-sided lymph nodes are involved, but left sided nodes can also get involved.
- It presents with general symptoms (fever, malaise, weight loss).



Figs 10.18A to C: Mesenteric tuberculous lymphadenitis on table findings.

- Pain in umbilical region and right iliac fossa, mass in right iliac fossa, which is matted, nonmobile.
- It may present with features of *acute appendicitis*.
- Often coils of intestine get adherent to the caseated mesenteric lymph nodes leading to intestinal obstruction.
- Most often caseating material may collect between the layers of the mesentery, forming a cold abscess, mimicking a mesenteric cyst (***Pseudomesenteric cyst).***
- *Massive enlargement of mesenteric lymph nodes due to tuberculosis is called as* ***tabes mesenterica****.*
- Mesenteric tuberculous adenitis is more common in children. Present with anaemia, fever, loss of appetite and reduced weight, failure to thrive, palpable mass in right iliac fossa which is firm and nodular.



Figs 10.19A and B: Note the location of mesenteric tuberculous lymphadenitis in the rigth iliac fossa. But it can occur anywhere in the line of mesentery. On-table caseating tuberculosis lymphadenitis is also shown.

Presentations of mesenteric tuberculous lymphadenitis

- Mesenteric tuberculous adenitis—acute/chronic in right iliac fossa—mass
- Pseudomesenteric cyst
- Cold abscess within the mesentery
- Tabes mesenterica

The same beam of light can illuminate two objects and produce two different effects.

Differential Diagnosis

- Carcinoma caecum.
- Lymphoma.
- Retroperitoneal tumour.
- Nonspecific lymphadenitis.

(Acute nonspecific mesenteric lymphadenitis is called as **nurses' syndrome**).

Investigations

- X-ray abdomen shows calcification.
- U/S may confirm the diagnosis.
- Mantoux test may be positive.
- *Diagnostic laparoscopy*—is very useful in TB lymphadenitis. Mesenteric cold abscess can be drained safely through laparoscopy.

Treatment: ATD's; Laparoscopy and proceed. Prognosis is good.

ANO-RECTO-SIGMOIDAL TUBERCULOSIS

- It mimics carcinoma rectum.
- It presents as tenesmus, diarrhoea, and discharge from the fistula and occasionally as mass per abdomen. Rectal tuberculosis occurs usually within 10 cm of anal verge.
- Fistulas are *painful and characteristically not indurated.* Tuberculous fistulas are commonly multiple.
- Tuberculous anal ulcers when occur are shallow, bluish, with undermined edges.
- Sigmoidoscopy, U/S, discharge study, fistulectomy and biopsy confirms the diagnosis.
- Treatment is ATD's, fistulectomy, often *sigmoid resection.*

TUBERCULOSIS OF THE OMENTUM

- It usually occurs as a part of the other types of abdominal tuberculosis.
- *Rolled up omentum* with thickening is characteristic.
- Often cold abscess can develop *per se* in the omentum.
- If it is so it can be dealt with laparoscopy safely under the cover of ATDs.

In all abdominal tuberculosis, drug treatment is for one year In adrenal tuberculosis and severe adhesions steroids may be beneficial

Indications for steroids in tuberculosis

- Miliary tuberculosis
- Tuberculous meningitis
- Adrenal tuberculosis
- Tuberculous pericarditis
- Pleural and endobronchial tuberculosis
- In abdominal tuberculosis to prevent adhesions
- Tuberculosis of the mediastinal lymph nodes (Rapidly progressive)
- Genitourinary tuberculosis
- Ocular tuberculosis



Fig. 10.20: Omental tuberculosis showing tubercles.

Remember

- AFB staining of fixed tissue in abdominal tuberculosis is possible only in 5% cases. *Ziehl-Neelsen* staining is done. (Carbol fuchsin—steam heat for 7 minutes—water wash-decoloraisation with 20% H_2SO_4—95% ethanol wash—counterstain with Loeffer's methylene blue/1% picric acid/0.2% malachite green. Tuberculous bacilli are bright red rods seen under oil immersion lens).
- Culture takes 8 weeks to get the result. 35% of abdominal tuberculosis shows positive in culture. *Lowenstein Jenson media* is used. Guinea pig inoculation is also useful method.
- *WHO now recommends* antituberculous drugs for 6 months. Uncomplicated cases—4 drugs for 2 months and 2 drugs for 4 months. Complicated cases—4 drugs for 2 months and 2 drugs for 7 months. But many patients need one year treatment. Because of complications and difficulty in managing recurrent cases of abdominal tuberculosis one year therapy is commonly used in developing countries.
- *First line drugs* are—isoniazid—5 mg/kg; rifampicin—10 mg/kg; ethambutol—15 mg/kg; pyrazinamide—25 mg/kg.
- *Second line drugs* are—amikacin; kanamycin; PAS (Paraamino sulphuric acid); ciprofloxacin; ofloxacin; clarithromycin; azithromycin; rifabutin.
- Follow-up and prognosis is monitored by—regular weight check to see for gain; improvement in appetite; reduction of abdominal pain and distension; absence of fever; normal bowel habits; normal haemoglobin; ESR becoming normal; and US abdomen shows improvement in sonological features.
- Patients who are not responding in 6 weeks should be reassessed again for—drug resistance; associated other diseases like malignancy (carcinomas or lymphoma), Crohn's disease, eosinophilic enteritis.
- During therapy patient who is responding for drug therapy can also go for intestinal obstruction due to fibrosis during healing stage. It needs surgical intervention.
- Repeated surgery in abdominal tuberculosis is difficult and dangerous as chances of developing faecal fistula, further adhesions are more likely.

Chapter 11 Liver

> *The liver…that great maroon snail…. No wave of emotion sweeps it. Neither music nor mathematics gives it pause in its appointed tasks.*
>
> **—Richard Selzer,** 1976

CHAPTER OUTLINE

- Surgical Anatomy of Liver
- Liver Function Tests
- Alpha-Fetoprotein
- Liver Biopsy
- Liver Injury
- Infections of Liver
  - Amoebic Liver Abscess
  - Pyogenic Liver Abscess
  - Portal Pyaemia
  - Hydatid Cyst of Liver
  - Actinomycosis of Liver
- Liver Tumours
  - Benign Tumours of the Liver
  - Primary Malignant Tumours of the Liver
  - Hepatocellular Carcinoma
  - Secondaries in the Liver
- Liver Cysts
  - Congenital Liver Cysts
  - Neoplastic Liver Cysts
  - Traumatic Liver Cyst
- Portal Hypertension
- Oesophageal Varices
- Portal Hypertensive Gastropathy
- Ascites
- Ascites in Portal Hypertension
- Budd-Chiari's Syndrome
- Hepatic Failure
- Hepatic Encephalopathy
- Hepatorenal Syndrome
- Hepatic Resection
- Portal Biliopathy

SURGICAL ANATOMY OF LIVER

Liver has four lobes—*right lobe, left lobe, quadrate lobe and caudate lobe.*

Supporting structures are *right triangular ligament, left triangular ligament and falciform ligament*.

Blood Supply

It is a unique organ with dual blood supply. Hepatic blood flow is around 1500 ml/minute of which *portal vein* contributes 80% and *hepatic artery* 20%.

Hepatic artery commonly originates from coeliac axis. There are many variations of hepatic artery, both in its origin and its pathway and is considered surgically important. Hepatic artery ligation is one of the surgical palliation for advanced hepatocellular carcinoma and secondaries in liver as tumour tissue is supplied exclusively by hepatic artery but normal tissue is also supplied by portal vein.

Superior mesenteric vein and splenic vein join dorsal to the neck of pancreas to form portal vein.

Hepatic artery, portal vein and bile duct are located in the free edge of the lesser omentum until it enters the liver.

Venous drainage is usually through the three major hepatic veins, right, left, and middle which drain into the IVC. Often inferior hepatic vein may be present.

The liver parenchyma is entirely covered by a thin capsule called '*Glissons capsule'* and by visceral peritoneum in all but the posterior surface of liver termed 'bare area'.

> *I prefer to learn and to teach anatomy, not from books but from dissections; not from the positions of philosophers but from the fabric of nature.*
>
> **—William Harvey**



Figs 11.1A and B: Anatomical location of liver and its lobes.



Fig. 11.2: Segmental anatomy of the liver.

Segmental Anatomy of Liver

Liver is divided into functional right and left lobes by a line passing from the left of the gallbladder fossa to the left of IVC—*Cantlie's line* creating *Couniaud's* segments. There are *eight segments*:

Segments I, II, III, and IV are of left lobe.

Segments V, VI, VII, VIII are of right lobe.

Segment I is the caudate lobe of the liver and has independent supply of portal and hepatic veins. This hepatic vein directly joins IVC.

Right lobe is having right hepatic artery, right branch of portal vein, and right hepatic duct.

Left lobe is having left hepatic artery, left portal vein, left branch of bile duct.

Functional unit is called as hepatic lobule and it contains central hepatic vein and portal triad (hepatic arteriole, portal venule, bile ductule).

Functions of the liver

- Removal of gut endotoxins and foreign antigens—liver acts as the first filter
- Drug and hormone metabolism
- Formation of bilirubin and its metabolism
- Formation of urea from protein catabolism
- Glucose metabolism, glycolysis, and gluconeogenesis
- Clotting factors synthesis
- pH balance and correction of lactic acidosis
- Maintaining body temperature
- Storage of vit. B12, vit. A, Cu, Fe

LIVER FUNCTION TESTS (LFT)

1. Serum bilirubin which includes both direct and indirect. Test is known as *van den Bergh's test*.
2. Serum albumin, globulin and A : G ratio; serum albumin is the indicator of chronic liver disease.
3. Prothrombin time: Normal value is *12-16 seconds*. Difference between control and test more than 4 seconds or test being more than 1½ times the control is significant. When it is altered it is corrected by injecting vitamin K, 10 mg IM for 5 days or by fresh frozen plasma (FFP)—*For cell synthesis.*
4. Alkaline phosphatase—*Secretary function.*
5. Aspartate amino transaminase *5-40 IU/litre* (AST, SGOT)—*signifies inflammation.*
6. Alanine transaminase *5-40 IU/litre* (ALT, SGPT), liver specific.
7. 5 nucleotidase.
8. Gamma glutamyl transpeptidase (GGT) 10-48 IU/L.
9. Immunological tests: Antimitochondrial or antinuclear antibodies.
10. AFP.
11. Specific tests: (a) For haemochromatosis: Serum iron, total iron binding capacity, serum ferritin. (b) Wilson's disease: Serum copper, urinary copper, serum ceruloplasmin.
12. Fluorodeoxyglucose-positron emission tomography (FDG-PET): It is to find out the uptake of labelled glucose which varies in different diseases of liver, i.e. benign, malignant and inflammatory.
13. Technetium-99m labelled radioisotope scan shows the uptake and excretion of bile.
14. A sulphur colloid liver scan shows specifically Kupffer cell activity. Sulphur colloid will not show uptake in adenoma and haemangioma as Kupffer cells are absent in these lesions.
15. Urine for bile salts (*Hay's test*), for bile pigments (*Fouchet's test*) and for urobilinogen (*Ehrlich's aldehyde test*).

Hepatocyte function	***AST, ALT***
Synthetic function and metabolism	PT-INR, factor V. VII, albumin, bilirubin
Biliary canalicular function	ALP, 5' nucleotide, gamma glutamyl transferase, bilirubin

Other investigations for liver diseases

- U/S abdomen
- Angiography
- CT Scan
- PTC
- ERCP
- MRI
- Laparoscopy and laparoscopic U/S
- Liver biopsy

ALPHA-FETOPROTEIN (AFP)

- It is a normal component of plasma protein of the human foetus secreted by embryonal hepatocytes which disappears 2-3 weeks after birth.
- Normal value is up to 10 ng/ml of plasma.
- It is an important tumour *marker for HCC and more often HCC with cirrhosis* (between 100-1000 ng/ml).
- It also increases in *hepatoblastoma, testicular tumours and ovarian tumours.*
- It is a prognostic indicator.

- It also increases slightly in benign conditions of the liver (only upto 100 ng/ml if at all).
- It increases significantly in non-seminomatous testicular tumours and ovarian tumours (yolk sac tumour).
- AFP is a useful marker to suspect, relapse or residual tumour.

LIVER BIOPSY

Prerequisites:

- Prothrombin time should be normal before doing liver biopsy, otherwise severe bleeding can occur.
- Normal value of prothrombin time is 12-16 seconds (It is compared to control and difference should be less than 4 sec between test and control). It is corrected by giving inj. vit K 10 mg IM, for 5 days. After that if repeat PT is still high then fresh frozen plasma (FFP) is required to correct it.

Indications

1. Cirrhosis, chronic hepatitis, haemochromatosis, Wilson's disease.
2. Hepatoma, secondaries in liver.

Complications

- Haemorrhage.
- Bile leak and biliary peritonitis.
- Infection.

Contraindications

- Hydatid disease, where it will precipitate anaphylaxis.
- Haemangioma, bleeding disorders.
- Ascites.

Procedure

Needle used here is either *Vim-Silvermann needle* or *Menghini needle* (better option).

Needle is usually punctured through right midaxillary line in 9th intercostal space or under U/S guidance into any place as required.

Presently, guided liver biopsy is commonly recommended and popular, i.e. U/S guided, CT scan guided, laparoscopy guided.


a
a. Stilette b. Biflanged needle
b
A
a
b
c
B
a. Needle b. Locking pin c. Stilette

Figs 11.3A and B: Liver biopsy needles. A. Vim-Silvermann, B. Menghini.

LIVER INJURY

Causes

It can be due to blunt injury, stab, gun shot injury.

Types

It can be contusion, laceration, avulsion, extension into thorax and biliary tree may be associated with other organ injuries (spleen, kidney, duodenum, bowel, IVC) and with fracture ribs.

Liver injury can be:

- *Penetrating*: It often requires surgical intervention. After laparotomy with rooftop incision, laceration is assessed, clots and blood in the peritoneal cavity is removed. Using *Pringle manoeuvre* bleeding is temporarily controlled. Often suprahepatic IVC and infrahepatic IVC control may be required. Liver wound is sutured using specialized needle with vicryl using *co-opting sutures*. Gelfoam or Surgicel is placed over it. Other injuries like of diaphragm, biliary system, bowel should be looked for. Adequate amount of blood, FFP should be kept for transfusions. Postoperative assessment of BT, CT, PT, platelet count, observation for sepsis is needed. Ideal antibiotic coverage using 3rd generation cephalosporins or higher are needed.
- *Blunt trauma*: It is assessed by CT scan. It is usually treated conservatively. Indications for surgical intervention are—progressive deterioration and bleeding, grade 5 liver injury on CT scan, associated bowel injury. Commonly used procedure after laparotomy is keeping packs between liver and diaphragm which is removed in 48-72 hours. Occasionally venovenous bypass, hepatic resection may be required.

Clinical Features

- Features of shock due to severe torrential bleeding (pallor, hypotension, tachycardia, sweating).
- Distension of abdomen with dull flank, guarding, tenderness and rigidity.
- Oliguria.
- Tachypnoea, respiratory distress and often cyanosis.
- Rupture of right lobe is more common than left lobe leading to *haemoperitoneum.*
- Occasionally can cause localized haematoma which may form an abscess.
- Bile leak from the injured site can lead to *biliary peritonitis*.

Investigations

- Chest X-ray to look for rib fractures.
- U/S abdomen, CT scan of chest and abdomen (CT is ideal).
- Diagnostic peritoneal lavage.
- Hb%, PCV, blood grouping and crossmatching. Adequate amount of blood (5-10-15 bottles of blood) must be kept ready for transfusion, i.e. requires massive transfusion.
- Arterial blood gas analysis.

Regeneration of liver after resection is complete in 4-6 months. 80% of liver can be resected without compromising its function.

CT grading of liver injury

Grade and type	*Injury*
I – Haematoma – Laceration	Subcapsular haematoma less than 10% surface area. Capsular laceration less than 1 cm in depth.
II – Haematoma – Laceration	Subcapsular haematoma 10-50%; intraparenchymal less than 10 cm diameter. Capsular laceration 1-3 cm in depth; less than 10 cm length.
III – Haematoma – Laceration	Subcapsular haematoma more than 50%; intraparenchymal more than 10 cm diameter—expanding. Capsular laceration 3 cm in depth.
IV – Laceration	Parenchymal disruption 25-75% hepatic lobe; 1-3 Couinaud segments.
V – Laceration – Vascular	Parenchymal disruption more than 75% or more than 3 Couinaud segments. Major hepatic veins or retrohepatic venacaval injuries.
VI – Vascular	Hepatic avulsion

- *Coagulation profile.*
- *Thromboelastography* is dynamic form of assessing the coagulation status on table.
- Arteriography to visualise the bleeding branch/vessel in the liver and embolisation can be tried.

Treatment

General measures

1. IV fluids, blood transfusion (massive), FFP.
2. Have both central venous access, and peripheral venous access.
3. Bladder catheterisation has to be done to measure the urine output.

Initial conservative nonoperative management

- It is done in—nonprogressive liver injuries in patients who are haemodynamically stable, low grade (I-III) liver injury, need of less than 2 units of transfusion, without peritoneal signs, normal mental status.
- However CT abdomen (absence of extravasation of contrast during arterial phase can be treated nonoperatively) and repeat CT or regular ultrasound follow up is a must.
- Replacement of lost blood; prevention of sepsis; regular monitoring by haematocrit, liver function tests, prothrombin time are needed.
- *Angiographic embolisation* increases the success rate of nonoperative therapy.
- Intensive care unit (ICU) management for 2-5 days; repeat CT scan after 5 days; bed rest to be continued; patient can have normal activity only after 3 months.
- When at any time patient's condition worsens, he should be taken up for laparotomy.

Specific treatment

- *Push (direct compression); plug* (plugging the deep track injuries using silicone tube or SB tube); *Pringle's* manoeuvre; *pack* (liver wound is directly packed with mop).
- Laparotomy is done through a large *bucket handle* abdominal incision or thoracoabdominal incision, and extent of liver injury and also other associated injuries are looked for.
- Small liver tear is sutured with *vicryl* or *PDS* mattress sutures with placing of gel foam to control bleeding.
- To control bleeding on table, from hepatic artery and portal vein, both are temporarily occluded using fingers, compressing at foramen of Winslow-*Pringle manoeuvre*. Often bull-dog clamp or vascular clamps can be used.


Parallel mattress sutures on either side
Co-opting sutures perpendicular to laceration
Liver injury

Fig. 11.4: Co-opting sutures are placed perpendicular to already placed parallel mattress sutures.



Fig. 11.5: By placing 3-5 mops between injured liver and diaphragm tamponade can be achieved to control bleeding from the liver. After 48-72 hours electively abdomen is re-explored for further intervention. By then commonly bleeding will be controlled and further management becomes easier. Sepsis should be taken care of by higher generation antibiotics.

- In deep severe injuries, following methods are used:
  - Hepatic artery ligation, not usual.
  - Segmental resection.
  - Hemihepatectomy, not commonly used.
  - Packing the liver temporarily with mops and closing the abdomen.
- Ligation of bleeding vessel individually on the cut surface is needed and is called as *tractotomy*. Biliary ductules are also ligated. As vessels are supported by *fibrous adventitia* ligation suture holds well on these vessels even though liver parenchyma is soft and friable.
- Liver can be wrapped with absorbable mesh *(mesh hepatorrhaphy)* to achieve haemostasis.

- Cholecystectomy and placement of 'T' tube in CBD.
- In associated IVC injuries it is very difficult to manage (has high mortality). A *veno-venous bypass* between femoral vein and SVC is done and then repair of IVC is carried out.
- ICT placement to thorax and repair of diaphragmatic injury.
- Management of other organ injuries accordingly.
- *Kous Netzoff aluminium needle* is used to suture liver tear.
- Postoperatively patient requires ventilator support, blood transfusion, electrolyte management, antibiotics like third generation cephalosporins, ceftazidime, cefoperazone.
- FFP, cryoprecipitate are also required.

Management of liver trauma

- Control of haemorrhage—packing; tractotomy; mesh hepatorrhaphy; debridement of devitalized tissue; segmentectomy, vein repair with veno—venous bypass; transfusions.
- Management of metabolic disturbances—prevention of acidosis, DIC, FFP; platelets.
- Monitoring—repeat US; repeat CT; urine output; LFT; prothrombin time; platelet count; haematocrit.
- Prevention of sepsis—proper debridement; irrigation of liver wound with warm normal saline; antibiotics.
- Identification and management of complications of liver injury

Porta hepatic injury

- It is life threatening even though rare. Penetrating trauma commonly cause this injury.
- It is commonly associated with organ injuries. Isolated porta injury is rare. It is difficult to manage with mortality 50-80%.
- Portal vein is sutured after veno venous bypass.
- Common bile duct injury involving less than half the circumference can be sutured over a T tube. Injury more than 50% or transection needs choledochojejunostomy.

Complications and sequelae of liver injury

- Shock and haemorrhage
- Liver abscess or septicaemia—7%
- Bile leak, biliary peritonitis, biliary fistulas—10%
- Disseminated intravascular coagulation
- Hepatic artery aneurysm, arteriovenous and arteriobiliary fistulas—haemobilia
- Intrahepatic haematoma
- Intraabdominal abscess—subphrenic, pelvic
- Complications of massive blood transfusion
- Electrolyte imbalance
- Respiratory complications
- Liver failure
- **Late sequelae** of liver trauma is *CBD stricture* causing obstructive jaundice. It can be managed by endoscopic stenting or by open Roux-en-Y hepaticojejunostomy
- Mortality is 10%; morbidity is 30%. Associated injuries increase the mortality from isolated liver injury of 3% to 20%.

INFECTIONS OF LIVER

AMOEBIC LIVER ABSCESS

- It is common in India and other tropical countries and it is caused by a parasite entamoeba histolytica.
- It is more common in *alcoholics and cirrhotic* patients**.**
- It is the commonest extraintestinal presentation of amoebiasis. It is often called *as tropical abscess*.
- Infection commonly occurs from the caecum after an attack of amoebic typhlitis (inflammation of the caecum) through the superior mesenteric vein and portal vein. Infection from sigmoid (rectosigmoid) colon spreads through the inferior mesenteric vein and portal vein to liver. Right lobe is commonly involved over posterosuperior surface (because of streamline effect and larger size of the right lobe). Trophozoites destroy the hepatocytes by releasing *histiolysin*, a cytolytic agent. It causes amoebic hepatitis with multiple microabscesses formation. It leads into liquefaction necrosis, thrombosis of blood vessels, release and, breaking of red cells. It causes formation of "*Anchovy sauce'* pus which is chocolate brown coloured and odourless (Anchovy sauce is sauce prepared from a type of fish). Pus may be green coloured if mixed with bile. Secondary infection is common (30%).
- In western countries pyogenic abscess is much more common. Amoebic abscess is much more common than pyogenic abscess in endemic areas like Indian sub-continent, and Africa.
- Amoebic abscess is usually sterile unless infected. Trophozoites are found in the wall of the abscess not in the content.

Life Cycle of Entamoeba Histolytica

Mature cyst in faeces → contaminate food/water → ingestion of cyst → pass through stomach undamaged → in alkaline medium, cyst wall lysis occurs by trypsin → excystation → release of quadrinucleate amoebae—metacyst trophozoites formed → Habitat in crypts of caecum commonly, often in sigmoid colon *as to form trophozoites.*


90% asymptomatic
Mature cyst (after precyst, uni/bi/ quadrinucleate forms)
Intestinal amoebiasis (10%)
Trophozoites may pass in faeces without encystation
Asymptomatic cyst carriers
Activation and latent/ reactive amoebiasis
Acute
Chronic
Amoeboma
Liver abscess (10%)
Cannot infect

> *Amoebic liver abscess may be present as bulge in the right lower intercostal spaces and may exhibit pitting edema.*
>
> **—Ajit K Basu**

Note:

- 10% of amoebic infection causes intestinal amoebiasis commonly in caecum; 10% intestinal amoebiasis leads into amoebic liver abscess.
- Malnutrition, patients on steroid therapy, immunosuppression, cirrhosis and alcoholism increases the infection rate and also rate of amoebic liver abscess.
- Amoebic liver abscess is not common in females especially in menstruating age group.
- Anchovy sauce pus is odourless unless infected secondarily.
- Size is the independent important *risk factor* for rupture.

Pathology

- Initially from infected rectosigmoid or ileocaecal region, amoebic trophozoites reach the liver through portal veins causing amoebic hepatitis, may be in the form of micro-abscesses all over the liver. This might resolve on its own or with antiamoebic drugs, but often leads to a localized *amoebic liver abscess*.
- In 70% of cases it is *single large abscess,* in 30% it is multiple, may involve both lobes. Problems and difficulties in treating, in addition to poor prognosis are more common in *multiple abscesses*.
- Amoebic liver abscess is more common in *right posterior-superior* region (80%) because of streamline effect, i.e. the portal vein is in direct continuation with the right branch. It can be *multiloculated* also.
- Pus is *chocolate coloured,* classically called as **anchovy sauce,** contains dead liver cells, RBCs, necrotic material. Pus may be green due to bile admixture.
- Often secondary infection by *E. coli*, staph, strepto may occur (30%) and so may present with features of pyogenic liver abscess. Because of perihepatitis, liver is fixed to diaphragm or abdominal wall, hyperaemia in the diaphragm causes sympathetic *pleural effusion on right side*.
- Commonly amoebic abscess presents as an *acute entity*, but it can also be present as *chronic type* where it is covered by a capsule, that remains dormant for a long period.
- Sometimes it can get calcified also**.**



Fig. 11.6: Commonest location of amoebic liver abscess—right posterosuperior part of the liver.



Fig. 11.7: Spread of trophozoites occurs from ileocaecal region and sigmoid through mesenteric vessels.



Fig. 11.8: Anchovy sauce pus seen in amoebic liver abscess.

Course and Sequelae of Amoebic Liver Abscess

- It can *rupture into lungs* leading to expectoration of chocolate-coloured sputum resulting in natural regression of abscess—commonest site of rupture.
- It can rupture into the peritoneum causing *peritonitis* which requires emergency laparotomy.
- It can rupture into pleural cavity leading to *empyema*.
- Rupture into bronchus can cause bronchopleural fistula leading into coughing out of Anchovy sauce pus.
- Rupture into bare-area of liver causing *retroperitoneal abscess*.
- Rupture into the intestines, or to the skin (*Amoebiasis cutis).*
- Most dangerous complication is rupture into pericardial cavity (*cardiac tamponade*) which has very *high mortality* (30%) requiring emergency thoracotomy and pericardial decompression.
- *Septicaemia and liver failure* can occur in a patient with amoebic liver abscess with *cirrhosis.*



Fig. 11.9: Complications of amoebic liver abscess.

Clinical Features

- It is common in males (20:1), may be after an attack of amoebic dysentery or many months after the attack or history of dysentery may not be there at all.
- They present with fever, loss of weight, chills and rigors, non-productive cough, shoulder pain.
- Pain in the right hypochondrium—90%.
- Soft, tender, smooth, liver with increased liver span—70%.
- **Intercostal tenderness** is elicited which is a useful clinical sign.
- Right sided pleural effusion may be evident.
- Mild jaundice is not uncommon especially in cirrhotics and multiple abscesses which may signify poor prognosis—20%.
- Tenderness, rigidity and skin oedema in right hypochondrium may be present in acute cases.
- In chronic amoebic liver abscess, smooth, firm/hard, nontender liver may be palpable.

Amoebic liver abscess may be:

- *Acute*—present with high fever, chills, rigors, tender, soft palpable liver, with intercostal tenderness.
- *Chronic*—present with firm/hard, smooth, nontender palpable liver without acute features.

Features may be of:

- *Systemic*—present with fever, chills and rigors, loss of appetite, reduced weight, and jaundice.
- *Abdominal*—present with pain and tenderness, localised guarding and rigidity, mass in right upper abdomen (tender, soft liver), ascites, splenomegaly, abdominal wall oedema.
- *Thoracic*—present with dry cough, chest pain in right lower part, right shoulder pain, pleural effusion, and intercostal tenderness.
- *Features of complications*—rupture/infection/septicaemia/liver failure.

Differential diagnosis

For acute type

- Acute cholecystitis
- Acute presentation of hepatocellular carcinoma (HCC) due to haemorrhage or necrosis
- Subphrenic abscess
- Pyogenic liver abscess

Chronic amoebic liver abscess mimics hepatoma in every respect

Investigations

- Total count may be increased.
- Liver function tests may show altered bilirubin and albumin level.
- Prothrombin time may be widened and if it is so Inj. vit K 10 mg IM for 5 days should be given. Even with this if P.T. remains widened then fresh frozen plasma (FFP) is needed to rectify the P.T.
- Serum alkaline phosphatase, SGPT, SGOT levels are altered.
- U/S abdomen shows altered echogenicity (anechogenic, hypoechogenic), size, location, number of abscess, nature of the liver—90% sensitivity.
- Chest X-ray findings:

- Raised fixed diaphragm (tenting)
- Pleural effusion
- Soft tissue shadow

- Indirect haemagglutination test (95% positive rate), ELISA and gel diffusion precipitative test are reliable serological tests. Serological tests are reliable in non-endemic areas than endemic areas. Counter immunoelectrophoresis is more useful in active disease.
- CT scan-contrast study. CT scan shows raised diaphragm; abscess cavity (low density area)—its size, location, number; presence of effusion; changes in the lung—95% sensitivity.
- Sigmoidoscopy/colonoscopy are used to identify the active ulcers. Scrapings of the ulcer show trophozoites.



Fig. 11.10: US picture of amoebic liver abscess. US guided aspiration is very useful.

PIVKA II: Protein induced in the absence of vitamin K or antagonists-II.



Figs 11.11A and B: CT scan pictures showing single, large and multiple liver abscesses.

Treatment

Drugs

- Tab. metronidazole 800 mg tid or Inj. metronidazole 500 mg IV tid for 10 days.
- Tinidazole 600 mg BD dose for 5 days.
- IV or oral antibiotics are essential to control secondary infection (cefotaxime, ciprofloxacin, amoxycillin) (Small abscesses < 3 cm respond to drugs).
- *Other drugs:*
  1. Injection dihydroemetine 1.5 mg/kg/day IM for 5 days should be given under cardiac monitoring.
  2. Chloroquine 250 mg BD given for 10-14 days.

Drugs used for amoebic infection

- Metronidazole, Tinidazole, Secnidazole, Ornidazole
- Dihydroemetine injection
- Chloroquine, tetracycline
- Diloxanate furoate, iodoquinol, paromonycin—as *cyst eradicators*

Note:
Metronidazole is not given in 1st trimester of pregnancy.

Aspiration

- In case of large abscess and infected abscess aspiration with a wide bore needle is done under U/S guidance after correcting the P.T.
- Previously without U/S, aspiration used to be done by passing needle in right 6th intercostal space in midaxillary line.


Aspiration through 8th intercostal space
US guided aspiration from front ideal
Midaxillary line
Amoebic abscess
Liver

Fig. 11.12: Aspiration of the amoebic liver abscess under US guidance or through right 8th intercostal space in midclavicular line.

Percutaneous Drainage

- Under U/S guidance pigtail catheter is placed into the abscess cavity percutaneously to drain the pus. Catheter tube



Figs 11.13A and B: Amoebic liver abscess US picture. US guided aspiration is being done.

and abscess cavity has to be washed and irrigated at regular intervals with normal saline. It may fail if there is thick pus, multiloculated abscess, and multiple abscesses. Procedure may cause bleeding and infection.

Note:

Aspirated fluid is sent for C/S, cytology and for study of trophozoites (last part of the aspirated fluid should be sent for this).

Surgery

Indications for surgery

- Even after repeated aspirations if abscess cavity fills again
- Thick pus
- Multiloculated abscess
- Left lobe abscess, because of danger of rupture into pericardial cavity
- Ruptured abscess
- Caudate lobe abscess
- Multiple abscesses



Fig. 11.14: Drainage of amoebic liver abscess transperitoneally and placing Malecot's catheter into the abscess cavity.

Procedure

- Through transperitoneal approach, abscess area is opened, pus is evacuated. Malecot's catheter is placed and brought out through a separate stab incision. The catheter is kept *in situ* until drainage stops completely. Complete drainage of pus will be confirmed by repeat U/S. During discharge, advice is given to avoid alcohol, Chloroquine 250 mg BD for 10 days and Diloxanide furoate 500 mg tid is given for 10-14 days.
- *Complications of surgery*—anaesthetic problems; bleeding; liver failure (in cirrhotic patients); intraperitoneal abscess formation; bile leak—bile peritonitis and fistula.



Figs 11.15A to D



Fig. 11.15E

Figs 11.15A to E: Operative findings of amoebic liver abscess. Note the exposed abscess in the liver, its aspiration and drainage. Placement of Malecot's catheter in the abscess cavity and drain placed into the peritoneal cavity is also seen.

Follow-up

At regular intervals is important. Measures taken are proper counseling to avoid alcohol; repeat LFT; repeat ultrasound to confirm the complete resolution of the abscess cavity.

Prognosis

- *Mortality* in amoebic liver abscess is 4%. It rises with rupture especially pericardial (30%).
- *Poor prognostic factors* are—Rupture, serum bilirubin > 3.5 mg%, serum albumin < 2.0 g/dl, liver failure, cirrhosis, multiple abscesses, volume of abscess > 500 ml, anaemia, diabetes.

PYOGENIC LIVER ABSCESS

Aetiology

1. *Biliary sepsis* 35%; commonest route.
    a. Empyema gallbladder.
    b. Cholangitis.
    c. After biliary tract surgery.
    d. Instrumentation.
    e. Stone disease, Caroli's disease, biliary ascariasis, biliary enteric anastomosis.
2. *Portal vein sepsis:*
    a. Appendicitis.
    b. Diverticulitis.
    c. Inflammatory bowel disease, pancreatitis, perforation, PID, colorectal carcinoma.
    d. Omphalitis in newborn.
3. *Distant infections* (*through hepatic artery*):
    a. Pneumonia.
    b. Upper UTI.
    c. Endocarditis, osteomyelitis, bacteraemia.
4. *Super added infections:*
    a. Amoebic liver abscess.
    b. Hydatid cyst.
5. *Cryptogenic liver abscess*—No identified primary infection.
6. *Trauma* becoming common cause.
7. *Direct extension*:
    From suppurative cholecystitis, subphrenic abscess, perforation, perinephric abscess.

Causative bacteria

- ❖ *E. coli*—commonest
- ❖ *Klebsiella*
- ❖ *Proteus*
- ❖ *Pseudomonas*
- ❖ Clostridia
- ❖ Enterococci, streptococci viridians in polymicrobial infection

Pathology

- Due to laminar blood flow right lobe (75%) is commonly involved; left lobe (20%), caudate lobe (5%) are also often involved.
- Usually solitary—60%; occasionally it can be bilobar and multiple.
- Cavity contains pus with virulent organisms. Usually abscess is acute. In cryptogenic type chronic presentation is known to occur.
- Ascites and splenomegaly is not common.
- It is more common in diabetics.
- Male to female ratio is *2:1*. It is more common in old people after 55 years of age.
- *Blood culture* commonly shows positive for bacteria.

Clinical Features

- Pain in the right hypochondrium—60%.
- High fever, with rigors—90%.
- Weight loss.
- Jaundice—occasionally—20%.
- Intercostal tenderness.
- Tender, soft liver-60%.
- Features of toxicity.
- Constitutional symptoms like malaise, lethargy, vomiting.

Diagnosis

- Ultrasound abdomen, CT scan. Sensitivity is 90% for USG; 97% for contrast CT scan.
- LFT, total count.
- Ultrasound guided aspiration of pus after controlling PT.
- Chest X-ray shows elevated diaphragm often with right sided pleural effusion.
- Blood culture is very relevant.

Differential Diagnosis

- Amoebic liver abscess, hydatid cyst, subphrenic abscess.

Treatment

- Systemic antibiotics—combination of third generation cephalosporins and metronidazole.
- *Ultrasound guided aspiration/pigtail catheter—Percutaneous drainage* is the treatment of *choice* at present. Drainage tube/catheter are placed under US / CT guidance into the liver abscess. Pus should be sent for culture and sensitivity. Follow up USG, LFT, assessment of quantity of daily drainage—should be done to assess the response. 75% of pyogenic abscess is drained percutaneously. *Percutaneous aspiration* without drainage tube placement is also used; but repeated guided aspirations are required; otherwise success rate is similar to drainage.
- Occasionally open drainage is required. *Open drainage* is indicated in recurrent abscess, failure of percutaneous drainage, large abscess of size more than 5 cm. Open drainage is becoming *less common* at present; but in selected patients it may be a life saving essential therapeutic modality.
- Treating the primary causes is very essential.

Complications

- Septicaemia, liver failure.
- Rarely rupture and peritonitis can occur.
- Klebsiella hepatic abscess can cause dangerous endogenous endophthalmitis commonly in diabetic patients impairing vision.

PORTAL PYAEMIA (PYLEPHLEBITIS)

It usually follows after severe infection of areas drained by portal vein.

Causes

- Appendicitis.
- Diverticulitis.
- Any severe abdominal sepsis.

Presently it is becoming *rare* because of availability of good effective antibiotics.

Infective thrombus in the vein (draining the infective area)
↓
It dislodges as infective emboli
↓
Reaches the liver
↓
Causes multiple abscesses in liver parenchyma
↓
Pylephlebitis.

E. coli is the most common organism. Often staphylococci, anaerobes, or combined infections may be involved.

Note:

Gas and thrombus in portal vein is diagnostic of portal pyaemia.

Clinical features

- High fever with rigors
- Toxicity
- Drowsiness, jaundice
- Tender soft liver
- Ascites
- Blood culture is a useful investigation

Treatment

- *Antibiotics*: Combination of third generation cephalosporin + aminoglycoside, ceftriaxone sodium, cefoperazone, ceftazidime, amikacin, tobramycin, metronidazole.
- IV fluids, blood transfusion, FFP.
- Ventilator support.
- Mortality is very high and usually patients die of hepatic failure, septicaemia, MODS.
- It is better to prevent portal pyaemia by prior good antibiotics in suspected cases.
- Treatment of primary cause is very important.

HYDATID CYST OF LIVER

Word meaning is '*dew drop*' (Latin). In Greek it means 'watery vesicle'.

Caused by **Echinococcus granulosus (EG),** *dog tape worm*, a parasite.

Life-cycle: Infected offal of sheep
↓
Eaten by the dog (definitive host)
↓
EG released, develops in the dog's intestine into a parasite of 1 cm long with a head and three segments, last of which contains about 500 ova.
↓
Ova expelled from the dog's intestine to grass and vegetables
↓
Eggs are ingested by sheep, cattle or human beings *(intermediate host)*
↓
Through portal vein—liver—larva form
↓
Hydatid cysts (70% in liver).

It takes few years to evolve into a complete hydatid cyst.

Most commonly involved segment is segment VII—27%. Commonly right lobe—66%; both lobes in 16% and only left lobe is involved in 17%.

Pathology

It has got 3 layers

1. *Adventitia (pseudocyst)* is an inseparable fibrous tissue due to reaction of the liver to the parasite.
2. *Laminated membrane (ectocyst),* formed of the parasite itself is whitish, elastic, containing hydatid fluid, which can be peeled off readily from the adventitia.



Fig. 11.16: Anatomy of hydatid cyst.

3. *Germinal epithelium* is the only living part, lining the cyst (*endocyst).*

This layer secretes *hydatid fluid*, *brood capsules with scolices* (heads of future worms).

Features of hydatid fluid

- Clear
- High specific gravity (1.005-1.009)
- Shows hooklets and scolices

Once brood capsules disintegrate, it grows into daughter cysts.

Course of the Disease

- The parasite may die and cyst eventually may get *calcified.*
- Commonly cyst *enlarges* and is palpable per abdomen.
- It may cause complications like *jaundice* due to pressure over biliary tree.
- *Rupture into the peritoneal cavity* causes anaphylactic reaction which may cause life-threatening shock, requiring proper management with steroids.
- *Rupture into biliary channels is commonest (60%)*. Rupture into bowel, pleural cavity can occur.
- *Secondary infection* causing suppuration and septicaemia.
- *Secondary cysts* in the lung, spleen, mesentery, retroperitoneum and other organs can occur**.**
- *Hepatic dysfunction*.
- *Disseminated abdominal hydatidosis* can occur after silent rupture.

Clinical Features

- Asymptomatic palpable liver with *classical thrill (hydatid thrill)* elicited by *three-finger test.*
- Jaundice and pain.
- Features of anaphylaxis.
- Discomfort in right upper quadrant area; dyspepsia; hydatid cachexia in children; weight loss; fatigue; vomiting.
- Occasionally splenomegaly, pleural effusion, cholangitis, allergic asthma, fever.
- *Camellotte sign*: Following intrabiliary rupture, gas enters into cyst causing partial collapse of the cyst wall.

Differential Diagnosis

- Hepatoma.
- Amoebic liver abscess.
- Cystic disease of the liver.

Complications of hydatid

- Anaphylaxis
- Rupture
- Obstructive jaundice— ERCP sphincterotomy may be needed
- Infection
- Calcification
- Liver failure

Investigations

- U/S is diagnostic. It reveals rosettes of daughter cysts, double contoured membrane of the cyst due to detachment of the cyst membranes, and calcification of cyst wall. Intra-operative ultrasound (IOUS) is very useful tool.
- X-ray often shows calcification.
- CT scan abdomen is more accurate in identifying cyst characteristics—*cart wheel* like—multivesicular rosette like.
- *Primary serological tests*—ELISA; indirect haemagglutination test; latex agglutination test; immunofluorescence antibody test; immunoelectrophoresis. 80-95% sensitivity for liver hydatid.
- *Secondary laboratory tests*—Detection of precipitation line—arc 5; immunoblotting; polymerase chain reaction (PCR). More specific, very useful in extrahepatic hydatid disease and calcified non-fertile liver hydatid.
- Liver function tests.
- Casoni's test (intradermal test—75% sensitive); complement fixation test—historical interest.
- MRI when there is jaundice to visualise biliary tree and its relation to hydatid cyst; to find out cystobiliary communication; biliary hydatids in bile duct and hepatic ducts. ERCP can also be done to find out the communications. Other method to find out the cystobiliary communications is intraoperative cholangiogram.
- ERCP to find out biliary communications but not as useful as MRI.

Aspiration of the cyst should not be done due to risk of anaphylaxis but presently PAIR (Puncture-Aspiration-Injection-Reaspiration) is done effectively.

Hassen Gharbi's ultrasound based classification of liver hydatid cysts (1981)

Type 1 – Pure fluid collection
Type 2 – Fluid collection with split wall
Type 3 – Fluid collection with septa
Type 4 – Heterogeneous appearance
Type 5 – Reflecting thick walls

WHO classification of liver hydatid cyst

Type – CL – Active; unilocular; no cyst wall; early stage; not fertile
Type – CE 1 – Active; cyst wall present; hydatid sand present; fertile
Type – CE 2 - Active; multivesicular rosette like cyst wall; fertile
Type – CE 3 – Transitional; detaching laminated membrane; *water-lily* sign; beginning of degeneration
Type – CE 4 – Inactive; degenerative contents; no daughter cysts; not fertile
Type – CE 5 – Inactive; thick calcified wall; not fertile



Figs 11.17A to C: Hydatid cyst of the liver—typical look.



Fig. 11.18: CT scan of hydatid disease of the liver.



Fig. 11.19: MRI picture of multiple hydatid cyst of liver—MRI is very useful investigation in hydatid cyst of liver.

Treatment

Drugs

- *Indications for drug therapy*
  - 4 days prior to intervention and to continue it for 1 month (albendazole) to 3 months (mebendazole) after the intervention.
  - Inoperable cysts.
  - Multiple or multiorgan cysts.
  - Recurrent hydatids.
  - Surgically unfit patients.
  - Cysts in lungs, bone, brain, eyes.
- *Contraindications*
  - Large cysts.
  - Honeycomb cysts (with septae).
  - Infected cysts.

Venous hum, which is heard louder on inspiration in epigastrium, in portal hypertension is called as Kenawy's sign

- Calcified cysts.
- Pregnancy.

♦ *Drugs used are:*
  - Albendazole 4-week cycles with 2 weeks drug free interval. It is ovicidal/larvicidal/*vermicidal*. Commonly used.
  - Praziquantel—60 mg/kg along with albendazole for 2 weeks.
  - Mebendazole—600 mg daily for 4 weeks.

PAIR – (Puncture – Aspiration – Injection – Reaspiration) – Percutaneously Done [1980]

Indications for PAIR	*Results and problems of PAIR*
• Inoperable patients	• Complication rate—10-40%
• Patients who refuse surgery	• Mortality rate—0.9-2.5%
• CL, CE 1, CE 2 and CE 3 types/Gharbi type 1 and 2	• Fever—35% - disappears in 72 hours
• Relapse cysts	• Anaphylaxis—0.1-0.2%- Same as open surgery—but drugs should be kept ready for anaphylaxis
• Infected cysts	• Infection—10% well controlled by antibiotics
• In pregnant women; children less than 3 years	
• Cysts more than 5 cm in different liver segments	• Local recurrences—4% Repeat PAIR can be done
Contraindications for PAIR • Inaccessible cysts • Cysts with multiple septae—honeycomb cysts • Hyperechogenic cysts • Communicating cysts to bile duct • Calcified cysts • Cysts in the lung	

Technique of PAIR

♦ Done under US/CT guidance.

♦ Under local anaesthesia cyst is punctured using a cholangiography 22 gauge needle through thickest route/part of cyst wall.

♦ Cyst is entered through non-dependent wall and 50% of fluid is aspirated. All multiple/daughter cysts are aspirated. Radiopaque dye is injected to see if any communications are present. Scolicidal agents—15-20% hypertonic saline is injected into the cyst. After 20 minutes reaspiration is done. A sclerosant—alcohol is injected. If cyst is 6 cm or more, a drainage catheter is placed for 24 hours for complete drainage and later alcohol sclerosant is injected.

♦ Double—puncture aspiration and injection (D-PAI) or modified PAIR/PEVAC (Percutaneous EV Acuation of Cyst) are other procedures done.

♦ PAIR has gained wide acceptance as it is safe, less invasive, and easier to do, with low morbidity and mortality. Complications and results are same as open surgery.

Surgery

♦ Surgery is still the choice and *gold standard* therapy for hydatid disease. The abdomen is opened, and the peritoneal cavity is packed with mops [black or coloured mops are used to identify white scolices clearly so as to pick up all and prevent any spillage]. Fluid from the cyst is aspirated and scolicidal agents [cetrimide, chlorohexidine, alcohol, hypertonic saline (15%-20%), 10% povidone iodine or H_2O_2] are injected into the cyst cavity (formalin should not be used). Hypertonic saline should be left within the cavity for 15-20 minutes to have effective scolicidal effect.



Figs 11.20A and B



Figs 11.20C and D

Figs 11.20A to D: On table finding of hydatid cyst of liver. Black mops are used to identify and isolate scolices. Note the cavity containing bile suggestive of biliary communication.

- Detection of *cystobiliary communications* is very crucial as it may cause caustic sclerosing cholangitis when scolicidal agent like formalin is used. Communicating openings may be single or multiple. Cyst more than 10 cm is likely to have cystobiliary communications. Often clinical features of communications may not be present. Preoperatively there may be recurrent cholangitis; dilated bile duct. Factors important are—its size; number; site; involvement of hepatic/bile ducts; liver dysfunction. Finding of bile stained cyst on table during aspiration is highly suggestive of communication. White mops soaked with hypertonic saline are kept in the cyst cavity and gallbladder is gently squeezed to see for the bile staining of the mop in the cavity which confirms communication.
- *Laparoscopic pericystectomy* is becoming more popular. Contraindications are deeply situated cyst, densely adherent cyst, and inaccessible cysts; more than 3 cysts; calcified cysts and cysts in other organs. Main problem with laparoscopic pericystectomy is spillage and difficulty in preventing it.
- Liver resection—only occasionally segmental or hemihepatectomy is done.

Scolicidal agents

- Cetrimide—can cause acidosis
- Alcohol 80%—can cause cholangitis
- Hypertonic saline—hypernatraemia
- Sodium hypochlorite—hypernataraemia
- Hydrogen peroxide

In cases with biliary communication only hypertonic saline (15-20%) is used (not other agents)

Procedures used to correct the cystobiliary communications and to obliterate the cavity are:

- Suturing of the communication—simple suture using vicryl/PDS suture with T tube drain of bile duct.
- Pericystectomy (*Pericystectomy* is done by peeling off the cyst wall and abdomen is closed with or without a drain); marsupialization.
- Tube drainage of the cavity; *capitonnage*—spiral suturing of the bottom of the cavity upward from base of cavity to the edge of the cyst wall; *introflexion*—inverting the rim of the cyst edge without apposition; *omentoplasty.*
- Internal drainage procedures like choledochojejunostomy; transduodenal sphincteroplasty; Roux-en Y cysto/intracystic hepatico jejunostomy; Roux-en-Y hepaticojejunostomy.
- In cystobiliary communication (fistula), cystobiliary disconnection is achieved anatomically between cyst and fistula and a multiperforated transparenchymal drain is placed into the fistula through the cyst and another multiperforated drain is placed into the cyst cavity. A 'T' tube drain is placed into the bile duct (*perdomo procedure*) to achieve complete external drainage with facilitation of closure of the communication.
- Bipolar drainage—a drain is placed to cyst cavity and a T tube is placed into common bile duct.
- Reconstructive procedure like *pericysto jejunostomy*; bile duct repair.
- ERCP sphincterotomy.

Malignant hydatid disease

- It is a misnomer as it is a benign condition
- It is caused by *Echinococcus multilocularis (Alveolaris)*. It presents with multiple small cysts in both lobes of the liver, all over
- It is difficult to treat, and mimics clinically and prognosis-wise to malignancy, hence the name
- They die of liver failure

Every job is self portrait of the person who did it.

ACTINOMYCOSIS OF LIVER

- *Actinomyces israelii* reaches the liver—via portal vein from ceacum (60%) or via hepatic artery from distant focus—from faciocervical region—30%.
- Disease progresses gradually and slowly to destroy the liver tissue causing multiple actinomycotic abscesses which produce a typical '*honey comb liver.*'

Complications

- Secondary infection.
- Liver failure.

Investigations

- Liver function tests.
- Ultrasound guided aspiration and staining of pus shows '*sun-rays*' appearance.

Treatment

Penicillins for 3-6 months.

LIVER TUMOURS

BENIGN TUMOURS OF THE LIVER

Benign tumours of the liver

- It is two times common than malignant liver tumor
- It is seen in 20% of population
- Haemangioma is the most common benign tumor
- CT and MRI are the essential investigations
- MRI shows 95% accuracy
- Diagnostic accuracy of liver biopsy is low—40%
- Hepatic adenoma is potentially malignant
- FNH and haemangiomas are not premalignant
- Primary (HCC) tumour or secondaries are differential diagnosis; AFP and CEA are helpful to differentiate



Fig. 11.21: Solitary benign cyst of the liver. It is a rare entity. Polycystic liver also can occur. Polycystic liver is associated with polycystic kidney disease. Condition is a rare differential diagnosis for hydatid cyst, hepatoma, and solitary secondary.

1. Haemangiomas

- They are the *commonest benign* tumour of the liver.
- It is usually solitary but can be multicentric.
- *Compressibility of tumour is diagnostic.*
- It is common in females (3:1) in 5th decade.
- Commonly they are asymptomatic.
- They can occur in right and left lobes.
- In children it is 10-15% of liver tumours. They are multifocal, often involves other organs also. Large one can cause AV shunting leading to CCF. Large childhood hepatic haemangiomas have got 70% mortality due to rupture, DIC, thrombocytopenia. It is confirmed by MRI. It is treated by embolization, radiotherapy and often resection.
- Cavernous haemangioma, consumption coagulopathy, thrombocytopenia is called as *Kasabach-Merritt syndrome*.
- LFT, AFP and CEA are normal.

Complications

- Bleeding rupture
- Thrombosis
- DIC
- Infection

- Complication usually occurs if haemangioma is *more than 8 cm* in size.
- ***Needle aspiration and biopsy are contraindicated.***
- U/S and CT scan are confirmative.
- Angiogram may be needed if surgical intervention is planned.
- MRI is diagnostic.
- Giant haemangioma is of size > 4 cm.

Treatment:

- Prior radiotherapy is given to reduce the size and then hemihepatectomy is done.
- Surgery is done when size is large, symptomatic, impending rupture or any other complications. Enucleation or anatomical resection with inflow control is needed.

***Note*:**
It has got very little or no malignant potential.

2. Hepatic adenomas

- They are common in females (10:1). They present as a solitary nodular lesions in the liver.
- It is said to be due to use of oral contraceptive pills (OCPs).
- It is uncommon in males.
- It is relatively rare compared to FNH and haemangioma.
- It is commonly solitary; but 20% of cases can be multiple; situation where > 10 adenomas are present is termed as *adenomatosis*. Multiple adenomas are not related to OCP intake and not more common in females.
- Upper abdominal pain (65%) is the commonest presentation.
- AFP is normal but rises if there is malignant transformation.
- They might turn into malignancy, hence resection is advised.
- U/S, CT scan are diagnostic but angiography is needed prior to resection, as it is vascular.
- MRI is ideal tool.
- Haemorrhage is more common.
- Hepatic adenoma cells are larger, contain glycogen and lipids. They are devoid of bile ducts whereas FNH contains bile duct components.

- Surgical resection is the needed treatment. Limited resection is needed. It is better to do resection prior to pregnancy. In adenomatosis either hemihepatectomy or transplantation may be required.
- OCP should be stopped.

Indications for surgical resection

- Rupture of adenomas—50%
- If there is possibility of turning into malignancy (large adenomas)

Note:

Kupffer cells are not present in hepatic adenomas.

3. Focal nodular hyperplasia (FNH)

- It is a benign condition of unknown aetiology, seen in females showing focal overgrowth of functioning liver tissue with fibrous stroma support.
- It contains hepatic cells as well as Kupffer cells which is characteristic.
- It is 2nd most common benign tumour.
- Usually it presents as solitary nodule.
- A sulphur colloid liver scan is diagnostic, shows 'hot spot' with a spoke wheel pattern—85%.
- It is a harmless condition.
- CT scan shows central scar with stellate distribution of the blood vessels.
- Telangiectatic FNH and hyperplastic with adenomatous FNH are nonclassic forms of FNH, which are 20% common and more common in men.
- It is totally benign tumour; but often difficult to differentiate from fibrolamellar type of HCC. AFP is normal.
- Vague pain abdomen may be the presentation.
- Rupture, bleeding are very rare.
- Histologically it can be typical (*with central scar*) or atypical (*without central scar*)—15%.
- Usually it does not require any treatment. OCP should be stopped.

Note:

Von Meyenburg's complexes are benign liver malformations that originate from embryonic bile ducts that fail to involute with cystic dilatation. It mimics metastatic liver disease. MRI is essential to diagnose.

PRIMARY MALIGNANT TUMOURS OF THE LIVER

1. Hepatocellular carcinoma/Hepatoma/HCC (80%).
2. Cholangiocarcinoma (20%).
3. Hepatoblastoma in infants and children.

Hepatoblastoma occurs within 2 years of life. *It is most common primary malignant tumour of liver in children*. It is common in male child. It is derived from fetal or embryonic hepatocytes. Serum AFP is *elevated* in 90% of cases. CT scan shows vascular mass with speckled calcification. It is highly sensitive to chemotherapy (vincristine, doxorubicin, 5FU). If it is resectable, it is the initial choice of therapy. Liver transplantation is also beneficial.

HEPATOCELLULAR CARCINOMA (HCC/HEPATOMA)

- Its incidence is rising.
- It is common in cirrhotics and hepatitis B and hepatitis C virus infection.
- It is common in Mozambique, South East Asia, tropical Africa, Taiwan. In Mozambique it is often seen in younger age group - below 30 years.
- Male to female ratio is 4:1.
- It is usually unicentric but occasionally can be multicentric.
- Right lobe is commonly involved.



Fig. 11.22: Hepatocellular carcinoma (HCC/hepatoma) is usually solitary, common in right lobe, attains large size.

Aetiology

- Aflatoxin B_1, a product of fungus aspergillus. It is powerful carcinogen.
- Hepatitis B and hepatitis C virus infection. It is more common in individuals who have chronic positive status for HBs Ag and chronic carriers. Vertical transmission of virus at birth raises HCC rate. In Europe, Japan, USA, HCV infection is more common cause. It is not necessary to develop cirrhosis to cause HCC. It is the infection which is the cause.
- Alcoholic cirrhosis. It is co-carcinogen.
- Clonarchis sinensis infestation.
- Smoking.
- Haemochromatosis, α1 antitrypsin deficiency.
- Hepatic adenoma—potentially malignant.
- Environment related chemicals like DDT, nitrite and nitrate related food products; trichloroethylene (dry cleaning solvents), biphenyls, carbon tetrachloride, herbicides, solvents like dioxane.
- Tannins, griseofulvin, bush tea (pyrrolizidine), rice toxins.
- Anabolic steroids, polyvinyl chloride.

Pathology

Gross

It is highly vascular with indistinct margin. Often it is well demarcated by fibrous tissue. Haemorrhage and necrosis are common.

- *Hanging type of tumour*—tumour attached to normal liver by a small vascular stalk—always very well resectable.
- *Pushing type of tumour*—large, well demarcated, displaces normal vasculature—resectable.
- *Infiltrative type of tumour*—indistinct, infiltrative—often difficult to resect.

Histology

- Well/moderate/poorly differentiated tumour.

Okudas classification—multifocal; indeterminate; spreading; expanding.

Fibrolamellar Variant of HCC (FL HCC)

- FL HCC occurs in *younger* age group.
- Incidence is *equal* in both sexes.
- It does not show any elevated levels of serum AFP.
- *Tumour marker for FL HCC type is increase in serum vitamin B_{12} binding protein and increase in neurotensin levels.*
- It is not related to viral hepatitis or cirrhosis.
- Left lobe is commonly involved.
- It involves lymph nodes more commonly than HCC.
- CT scan shows characteristic central scarring.
- Fibrous stromas with thin hyaline bands are typical. Sheets of well differentiated hepatocytes are seen which are sandwiched between collagen and fibroblasts.
- It is fairly resectable (50-75%) with better prognosis than HCC.

Okuda staging system (1984) for HCC

Parameter		*Points*	*Stage*
Tumor size	< 50 %	0	Stage one—0 points
	> 50 %	1	Stage two—1-2 points
Ascites	Absent	0	Stage three—3-4 points
	Present	1	
Serum	< 3 mg %	0	
Albumin	> 3 mg %	1	
Serum	< 3 mg %	0	
Bilirubin	> 3 mg %	1	

Staging of HCC (AJCC)

T_0 – No tumour
T_1 – Solitary tumour without vascular invasion
T_2 – Solitary tumour with vascular invasion / multiple tumours equal or less than 5 cm
T_3 – Multiple tumours, more than 5 cm/tumour invading major branch of portal or hepatic veins
T_4 – Tumour with direct invasion of adjacent organs other than gallbladder or to visceral peritoneum
N_0 – No regional nodes are involved
N_1 – Regional nodes are involved
M_0 – No distant spread
M_1 – Distant spread is present

Cancer of liver Italian group scoring (CLIP scoring)

Parameters	*Values*	*Scores*
Child Pugh's stage	A B C	0 1 2
Tumour morphology—Gross	Uninodular less than 50% of extension Multinodular less than 50% of extension Massive—extension more than 50% of liver	0 1 2
AFP ng/dl	Less than 400 More than 400	0 1
Portal vein thrombosis	No Yes	0 1
Total scores 0-6 Early disease with potential long term survival 0-3 Advanced stage 4-6		

Chinese university prognostic index (CUPI) scoring system uses TNM staging, symptoms, ascites, bilirubin, alkaline phosphatase, AFP. It is used mainly for HBV induced HCC.

Clinical Features

- Painless mass in right hypochondriac region with loss of appetite and weight. Liver is hard, smooth/irregular and often massively enlarged. Cirrhotic liver may be nodular.
- Acute presentation is not uncommon, when the tumour undergoes necrosis and haemorrhage. Both types of presentations mimic amoebic liver abscess (Haemoperitoneum is also known).
- Jaundice when present is commonly due to hepatic dysfunction, but occasionally due to compression of bile ducts.
- Ascites (40%) often it is massive, splenomegaly and features of portal hypertension may be present.
- Hepatic thrill and bruit—25%.
- Fever (10-20%) may be present due to tumour necrosis.
- Dull aching pain in right upper quadrant is common.
- Features of chronic liver disease—jaundice, dilated veins, palmar erythema, gynaecomastia, testicular atrophy, etc.
- Liver failure sets in once tumour replaces the functioning liver parenchyma or portal vein gets occluded by tumour thrombus.
- Gastrointestinal bleeding may be the presentation in 10% of cases due to portal hypertension or portal vein invasion by tumour.
- Occasionally may present with paraneoplastic syndromes. 1%; hypercalcaemia, hypoglycaemia, hyperlipidaemia, hyperthyroidism, erythrocytosis.

Spread of Tumour

- *Lymphatic spread*: It can spread to other part of liver through lymphatics within the liver, to the lymph nodes in the porta hepatis and other abdominal lymph nodes later. Often spread occurs directly to cisterna chyli.
- *Blood spread*: To lungs, bones and adrenals often can occur.
- *Direct infiltration*: To diaphragm and neighbouring structures.

Differential diagnosis

- Secondaries in liver
- Polycystic disease of liver
- Amoebic liver abscess
- Hydatid cyst of the liver



Figs 11.23A and B: CT pictures of hepatoma. In right lobe and left lobe.

Investigations

- U/S abdomen—very useful method. It shows hyperechoic mass; mosaic pattern with thin halo and lateral shadows. Extent, tumour thrombi extension can be made out.
- CT scan abdomen (CECT) more reliable and ideal (hypodense, mosaic, vascular lesion with irregular margin).
  - reveals the size, location and extent, vascularity, portal vein invasion, nodal status, portal vein thrombosis.
  - helps to assess operability.
- *Tumour markers—α feto protein (AFP).* AFP will be raised more than 100 IU; as high as 1000 IU is possible in HCC. PIVKA II is des γ carboxy prothrombin protein induced by vitamin K abnormality/antagonists 2. It is increased in 80% of HCC patients. AFP is usually more than 400 IU in 70% of HCC patients.
- Celiac angiography/CT angiography—it shows the vascularity of the tumour, tumour blush, arterial pattern of the liver and tumour; venous phase can show portal vein invasion or thrombosis and invasion/spread to IVC. Angiogram is essential while planning for hepatic resection.
- Liver function tests like serum bilirubin, albumin, enzymes (alkaline phosphatase, transaminase, 5' nucleotidase) including prothrombin time.
- Liver biopsy is done after controlling prothrombin time if it is elevated (by Inj vitamin K IM 10 mg for 5 days; FFP transfusion). US / CT guided core liver biopsy is useful and mandatory before clinical trials. It is better than FNAC as it reveals tissue architecture. Problems with the core liver biopsy are spillage of tumour and bleeding (due to hypervascularity, associated thrombocytopenia and reduced liver dependent clotting factors like prothrombin). Such problems may be minimal in FNAC. Patients with high suspicious of HCC by clinical and imaging methods and who are appropriate for surgery may be taken up for surgery without a preoperative biopsy. In case of portal vein infiltration by tumour a portal vein biopsy may be done to exclude the patient for surgery or transplantation.

Note:

Preoperative liver biopsy is *not recommended* now. Biopsy is relatively contraindicated in any candidate for resection, as there is a significant risk of haemorrhage and peritoneal implantation of tumour cells. In case of potentially resectable tumour one should proceed to surgical exploration without tumour biopsy. Biopsy is done only in inoperable advanced cases wherein palliative therapies are undertaken to establish the diagnosis.

- Contrast MRI/CT scan 1-2 weeks following intrahepatic infusion of lipiodol (ethiodized oil emulsion 5-15 ml) with contrast agent through hepatic artery is very useful.
- MRI—T_2 weighted studies are useful for small HCC. MR angiography is also done to see tumour thrombus in portal vein, hepatic vein and IVC.
- Ascitic tap when ascites is present for cytology.
- Laparoscopic evaluation and laparoscopic US is useful for proper assessment of the tumour.
- Investigations in relation to hepatitis B and hepatitis C virus infections.
- Metastatic work up—HRCT of chest is essential.

Treatment

Definitive Treatment

- When limited to one lobe, *hemihepatectomy* is done (Removal of 80% liver is compatible with life). Laparoscopic resection is becoming popular. It is done only to Child's grade A and favourable Child's B group patients. It is the treatment of choice for operable HCC in noncirrhotic patients. There is no regenerative capacity in cirrhotic patients with poor coagulation status, portal hypertension, varices, and ascites.
- In cirrhotic patients with HCC, *total hepatectomy* with *orthotopic liver transplantation* is required. Now it is found

that even resection candidates will do better by transplantation than resection. But waiting period for transplantation is long. To bridge this waiting period for transplantation radiofrequency ablation, transarterial embolisation, ethanol/acetic acid injections are used.

Note:

Liver mass which is confirmed by CT/MRI and serum AFP is > 500 ng/dl is almost diagnostic and resection treatment can be started without tissue diagnosis.

Indications for transplantation in HCC

- Patient who is not a candidate for resection
- Tumour less or equal to 5 cm
- Tumour less than 3 in number
- Tumour without portal/hepatic vein invasion
- Tumour without extra hepatic spread

Palliative Treatment

- *Radiofrequency ablation (RFA)*: It is thermal ablation of the tumour by passing 18G needle into the middle of the tumour and passing electric current of 500 kHz. This creates frictional heat causing sphere of necrosis. Maximum zone of necrosis which can be created is 7 cm for a 5 cm tumour. This causes adequate cyto-destruction of the tumour. Tumour close to vessels and biliary tree, tumour more than 3-5 cm and multicentric tumours are difficult to manage by radiofrequency ablation. One course ablation takes around 20 minutes. It can be done percutaneously under US or CT guidance or through laparoscopy. Percutaneously it can be done on outpatient basis. It can be repeated several times. Tumour less than 3 cm, tumour deep in parenchyma, tumour away from hilum is ideal for radioablation.
- *Percutaneous ethanol or acetic acid injection:* (*Rule of 3* is used here—indicated in HCC not >3 cm and not > 3 nodules). Ethanol injection is minimally invasive, can be injected using fine needle, and is cheaper. Local recurrence is lower with acetic acid injection than ethanol. But radiofrequency ablation has got better result than ethanol/acetic acid injection. RFA is costly and not available in many centers.
- *Intra-arterial chemotherapy* using Adriamycin/cisplatin/mitomycin through gastroduodenal artery. It is often given along with lipiodol to make drugs to stay longer time in the liver tissue so that better results are achieved. This regional chemotherapy is much more successful in HCC.
- *Intra-arterial embolisation* using gelfoam, microspheres, gelatin sponge, or chemoembolisation.
- *Microwave or cryo ablations* similar to RFA.
- As it is considered that tumour tissue exclusively gets its blood supply from hepatic artery, *ligation of hepatic artery* can be a good palliation (to achieve tumour necrosis) for HCC. Normal tissue will still have its blood supply from portal vein.
- Transarterial I^{131} lipiodol, Yttrium 90 microspheres.

Adjuvant Therapy

- Systemic chemotherapy using intravenous adriamycin (doxorubicin), cisplatin, carboplatin, mitomycin C, 5 fluorouracil.
- Octreotide is used along with other chemotherapeutic agents. It decreases the size of the tumour.
- Neoadjuvant (preoperative) chemotherapy also practiced to increase the operability/resectability of the tumour.
- Newer treatments are tried using tamoxifen, interferons, EGFR antibody, interleukins, I^{131} lipiodol, Yttrium^{90} microspheres, etc.

Neoadjuvant therapy in HCC

Large primary tumour—downstaging/*downsizing* may make resection possible

- Transarterial chemoembolisation (TACE)
- Chemotherapy and radiotherapy
- Hepatic artery infusion of chemotherapy (HAI)
- Radioimmunotherapy
- Fractioned radiotherapy
- Transarterial ^{90}Y microspheres

Treatment strategies for HCC

- Surgical resection, only 20% have resectable liver
- Liver transplantation
- Radiofrequency ablation
- Percutaneous ethanol/acetic acid injection
- Transarterial embolisation/chemoembolisation
- Microwave/cryoablation
- Transarterial radiotherapy
- Transarterial Yttrium^{90} microspheres/I^{131} lipiodol
- Hepatic artery ligation
- Adjuvant systemic chemotherapy
- Immunotherapy/hormone therapy/growth factors

Hepatoma/hepatocellular carcinoma/HCC

- Common etiologies are aflatoxins, hepatitis B and hepatitis C virus infection, alcoholic cirrhosis, haemochromatosis, smoking, hepatic adenoma, clonorchis sinensis, polyvinyl chloride
- Unicentric and right lobe involvement is more common
- Fibrolamellar variant is common in left lobe, not related to hepatitis or cirrhosis without AFP level raise. There are increased serum vitamin B_{12} binding capacity and neurotensin levels
- Invasion to portal veins is common and it has got negative prognosis with lesser chances of resection or transplantation. It may cause portal vein thrombosis and so splenomegaly
- It can be multifocal/indeterminate/spreading/expanding—*Okuda classification*
- Presents as large, smooth, hard liver mass—later jaundice, fever, pain and tenderness, ascites and bruit over mass
- Spreads by lymphatics, blood and direct extension
- Mimics amoebic liver abscess, secondaries, hydatid cyst, polycystic liver disease
- LFT, CT scan, raised AFP, liver biopsy are the investigations
- *Liver mass, confirmed by CT/MRI and serum AFP > 500 ng/dl is almost diagnostic* and treatment can be started without tissue diagnosis

- Liver biopsy is done (FNAC) only in patients with nondiagnostic level of AFP and not a candidate for curative surgery but only for palliation
- Hemihepatectomy is the treatment in early operable growth
- Liver transplantation is the good surgical option
- Hepatic artery ligation/intra-arterial chemotherapy/chemoembolisation/percutaneous ethanol or acetic acid injection/radiofrequency ablation/chemotherapy using adriamycin, carboplatin, gemcitabine—are palliative procedures

SECONDARIES IN THE LIVER

It is the commonest malignant tumour in liver. The incidence of primary : secondary : : 1 : 20.

Secondaries are common malignant tumours

- In bone
- In liver
- In brain

Causes

***Abdominal*:** Carcinoma in stomach, colon, pancreas, small bowel, kidney, abdominal oesophagus, rectum, carcinoids.

Extra-abdominal:

- Melanoma.
- Carcinoma breast, lung, thoracic oesophagus, bladder, prostate.
- Testicular and adrenal tumours.
- Follicular carcinoma thyroid (FCT).

Commonly secondaries in liver are multiple, multiple in one lobe or in both lobes. It can be solitary (rare).

It is often also classified as:

Colorectal

- Colorectal carcinoma has got special interest in relation to its secondaries in liver. It carries good prognosis.
- Secondaries can be *synchronous or metachronous.*
- Resection of secondaries in liver often gives good outcome.
- PET scan is done to identify occult extrahepatic metastases. CEA is reliable indicator of spread or recurrence.
- Resection, chemotherapy, intra-arterial chemotherapy are therapeutic modalities.
- *Contraindications for liver resection* are—extrahepatic spread, nodal involvement along with primary, short disease free interval less than 1 year, four or more secondary deposits, bilobar spread, CEA more than 200 ng/dl, secondary more than 5 cm in size, involved histologic margin.
- Colorectal liver secondaries show good prognosis when secondary are solitary, and with absence of all poor prognostic indicators.
- 5 FU with irinotecan or oxaliplatin, bavacizumab (antivascular endothelial antibodies) are also useful.



Fig. 11.24: Secondaries in liver—solitary type from colonic primary.

Neuroendocrine

Gastrinoma, glucagonoma, somatostatinoma, nonfunctioning neuroendocrine tumours can cause liver secondaries.

- These tumours are slow growing.
- Main symptoms are often due to secreting peptides causing different clinical syndromes.
- Hormonal assay, CT abdomen, CT angiogram are needed.
- Hormone controlling therapies, chemotherapy and cytoreduction using liver resection gives good 5-year survival up to 75% in these patients.

Non-colorectal and Non-neuroendocrine

- These are aggressive primary tumour causing liver secondaries like from stomach, pancreas, small bowel, oesophagus, gallbladder, melanoma, urinary bladder and prostate.
- They carry poor prognosis.
- Treatment is chemotherapy. Early primary like—in stomach with isolated liver secondaries without extrahepatic spread can be benefited with liver resection.
- But overall prognosis is guarded.

Other classifications

- *Precocious:* Secondaries are presented/identified before primary is suspected—carcinoid, colorectal cancer.
- *Synchronous*: Both primary and secondaries are identified at the same time—carcinoma stomach.
- *Metachronous*: Secondaries develop much later may be long time after the treatment for primary—melanoma, breast carcinoma.

Route of Spread

a. *Direct spread*: Stomach, colon, gallbladder, bile ducts.
b. *Hepatic artery*: Melanoma.
c. *Portal vein*: Carcinoid tumours, other GIT malignancies.
d. *Lymphatic spread*: Breast, lung.

Clinical Features

- They are multiple, hard, nodular, with nodule showing umbilication due to *central necrosis.*
- Patient may have jaundice depending on the extent of liver involvement.
- Loss of appetite and weight.
- Ascites.
- Pain in liver secondaries is due to stretching of liver capsule/ tumour necrosis. Often pain may be of primary tumour.
- Rectovesical secondaries—'Blumer shelf'.
- Supraclavicular lymph node enlargement.



Fig. 11.25: Secondaries in liver. Note the multiple lesions (nodules) in both lobes of the liver.

- Clinical features of primary tumour, e.g. stomach, colon—
  - Stomach: Vomiting; visible gastric peristalsis; palpable stomach mass.
  - Colon: Constipation/diarrhoea; palpable mass; features of obstruction.
  - Pancreas: Jaundice; steatorrhoea; itching; palpable gallbladder.
  - History of earlier surgery: Like mastectomy/wide excision of the melanoma.
  - Testis: Fullness; hard mass; loss of testicular sensation.

Clinical features of secondaries in the liver

- Poor general condition
- Palpable liver which is hard, multinodular with umbilication
- Clinical features of primary
- Ascites ±
- Jaundice ±

Differential Diagnosis

- Multicentric hepatoma.
- Macronodular cirrhosis.
- Polycystic liver disease, hydatid cyst of liver.

Investigations

- Primary is identified by—gastroscopy, colonoscopy, contrast X-rays, CT scan.



Figs 11.26A to C: Secondaries in liver are multiple and often with umbilication. CT picture shows multiple secondaries with ascites. On table photo of multiple liver secondaries with umbilication.

- Liver biopsy is done, only if primary is not identified by any of these methods.
- Liver function tests.
- U/S abdomen—multiple hypo-or hyperechoic lesions; site of possible primary; nodal status; ascites.

- Tumour marker: CEA.
- MRI/CT scan whenever resection is indicated.
- Laparoscopy often with laparoscopic US is very useful to detect small secondaries.

Treatment

- Chemotherapy is the treatment of choice.
- *Surgery has a definitive role if primary is from the colon, kidney.*
- If the primary growth is in the colon, then a palliative hemicolectomy is done. Along with that if a solitary secondary in the liver is present, it can be resected. If secondaries are in single lobe, hemihepatectomy is done.

Criteria for selection for liver resection in secondaries in liver, when primary is in colon are-

- Stage of the primary
- Type of primary resection
- Size of the largest liver secondary
- Number of secondaries
- Segments involved
- Associated liver disease like cirrhosis

- Palliative procedures for other primaries like—for carcinoma stomach—palliative partial gastrectomy/anterior gastrojejunostomy; for carcinoma pancreas—triple anastomosis/ERCP stenting.
- Depending on the site of primary, drugs vary.
    - For carcinoma stomach, mitomycin and 5FU are given.
    - For carcinoma colon, 5-FU, oraloplatinum/VEGF or EGFR antibodies used with folinic acid.
- Hepatic artery ligation or therapeutic embolization with clot/gel foam can be tried to relieve pain.
- Intra-arterial chemotherapy is tried with little success.

Methods other than resection available to ablate the tumour locally in secondaries in liver

- Microwave therapy
- Radiofrequency ablation
- Laser hyperthermia
- Ultrasound or electrolyte therapy

Overall outcome is poor in liver secondaries.
They die of malignant cachexia, infection, liver failure.

Causes of massive enlargement of liver

- Hepatoma
- Secondaries in liver when primary is from melanoma, carcinoid tumour
- Syphilitic enlargement of liver (hepar lobatum)

LIVER CYSTS

CONGENITAL LIVER CYSTS

Simple Liver Cyst

- It is 3% common. It is common in males (2:1).
- Solitary simple cyst is congenital; developing from abnormal intrahepatic bile duct *in utero*.
- 1/4th of simple cysts are symptomatic only at 4th or 5th decade.
- It is thin bluish walled cyst in one or other lobe containing clear fluid. Simple cyst will never communicate with biliary system. If communication is found it should be cystadenoma.



Figs 11.27A and B: Simple liver cysts—CT pictures in two different patients.

Venous hum in epigastrium observed in portal HT is called as Kenawy's sign.

- 50% present with abdominal pain. Hepatomegaly is common. Jaundice can be present.
- *Differential diagnoses* are—hydatid cyst, cystic neoplasms, solitary secondary with tumour necrosis.
- US shows anechoic lesion with smooth margin.
- CT scan shows nonenhancing thin lesion. MRI shows hypointense T_1 image and hyperintense T_2 image.
- Aspiration confirms the diagnosis. Aspiration will not cure the cyst as it recurs 100%.
- *Treatment* is—aspiration with sclerosant therapy where the recurrence rate is 20%. Deroofing with partial excision of cyst wall, by laparoscopic or open method has recurrence rate of 10%. Complete excision has very less recurrence rate but surgical mortality of 2% is present.

Polycystic Liver Disease

- It is autosomal dominant condition associated with polycystic kidney disease in 40% of cases.
- It arises from biliary epithelium but doesn't communicate with biliary system.
- Usually they are asymptomatic.
- Hepatomegaly, pain abdomen, jaundice and portal hypertension are the presentations.
- Haemorrhage, biliary obstruction, Budd-Chiari syndrome, rarely malignant transformation - are the *complications*.
- Liver function is well preserved and so liver failure will not occur.
- US, CT, MRI are investigations done.
- *Treatment*: Percutaneous aspiration with sclerosant injection, deroofing of all cysts, resection, liver transplantation.

NEOPLASTIC LIVER CYSTS

- They are *acquired* cysts.
- They are common in *females*.
- They attain large size; multiloculated with papillary projections.
- 10% of neoplastic cysts are malignant.
- Cystadenoma is benign containing *mucinous or bilious* fluid.
- Cystadenocarcinoma contains *haemorrhagic* fluid.
- AFP, CEA are normal; CA 19/9 is elevated.

Hepatobiliary (Hepatic) Cystadenoma

- Incidence is 5% of biliary intrahepatic cysts.
- 50% are in right lobe; 30% are in left lobe; 15% bilateral.
- Cystadenoma *without mesenchymal stroma* is equal in both sexes and occurs in 5th decade. It is not associated with cystadenocarcinoma.
- Cystadenoma *with mesenchymal stroma* is common in *young females* and is often associated with cystadenocarcinoma.
- It is septated, multiloculated, whereas if cavity contains debris it suggests malignancy. It is surrounded by a smooth and thick fibrous capsule. It contains internal septations and intraluminal papillary projections and lined by cuboidal or columnar biliary epithelium.



Figs 11.28A to C



Fig. 11.28D

Figs 11.28A to D: Hepatic cystadenoma of right lobe of liver—CT picture and on table look (*Courtesy:* Dr Ashfaque Mohammed, DNB, KMC, Mangalore).

- It originates from—congenital aberrant bile duct/embryonic foregut cells/peribiliary endocrine cells.
- MRI is diagnostic. US/CT scan is also useful.
- ERCP is done to identify communication with biliary system; usually to proximal left hepatic duct.
- *Treatment*—enucleation of entire cyst with surrounding rim of normal liver tissue. Hepatic resection is also an option.
- *Note:* Aspiration/deroofing, partial excision, sclerotherapy *should not be* done.

Hepatic Cystadenocarcinoma

- It presents as large palpable smooth liver with abdominal pain.
- It carries better prognosis than HCC or cholangiocarcinoma.

It can be:

  - Cystadenocarcinoma arising from preexisting cystadenoma with mesenchymal stroma, which occurs only in young females, carries good prognosis.
  - Cystadenocarcinoma without mesenchymal stroma not associated with cystadenoma, which is common in males and is more malignant.
  - Cystadenocarcinoma without mesenchymal stroma occurring in women.
- Resection is the treatment. It carries good prognosis.

TRAUMATIC LIVER CYST

- It is an *acquired cyst* of liver after liver injury in a blunt abdominal trauma. Biliary duct which is injured will cause bile leak into the existing intrahepatic haematoma causing mixture of bile and blood. Cyst is pseudocyst in liver without an epithelial lining.
- It may resolve spontaneously or may cause abdominal pain, jaundice. It may present months or years later.
- CT scan, old history of liver trauma may be helpful. MRI is diagnostic.
- *Treatment* is conservative. Often deroofing or cyst excision with ligation of biliary ductile may be needed but technically demanding.

PORTAL HYPERTENSION

- *Definition*: Sustained elevation of portal pressure more than 12 mm Hg (normal 8-12 mmHg).



Fig. 11.29: Anatomy of the portal system.

- Left sided portal hypertension ***(sinistral)*** can be caused by isolated splenic vein thrombosis, which is often caused by adjacent pancreatitis.
- A rise in portal pressure stimulates portasystemic circulation.
- Portal vein carries 75% of blood flow to liver with all nutrients to maintain its integrity and gives 50% oxygen supply to liver. 25% hepatic arterial blood flow gives remaining 50% of oxygen supply to liver.
- Portal hypertension causes compensatory portosystemic venous collateral formation, altered intrahepatic circulation and increased splanchnic blood flow. High pressure portal blood is diverted via coronary (left gastric vein), short gastric and esophageal veins into azygos venous system.
- There is increased portal resistance and altered portal blood flow. Increased resistance may be presinusoidal, sinusoidal and postsinusoidal.
  - *Presinusoidal*
    - Extrahepatic—portal vein/splenic vein thrombosis.
    - Intrahepatic—schistosomiasis, sarcoidosis.
  - *Sinusoidal* – cirrhosis, haemochromatosis, Wilson's disease, congenital hepatic fibrosis.
  - *Postsinusoidal* – Budd-Chiari syndrome, conges-tive heart failure, veno-occlusive disease.
- There is *dysregulation* of compensatory increased hepatic arterial flow response in relation to decreased portal vein flow.
- 30% of varices patients will bleed; 30% of them will die of bleed; 30% of patients with cirrhosis will develop portal hypertension; 30% of them have variceal bleed in 2 years; 70% of patients who had bleeding once, will rebleed later.
- Variceal bleed accounts for 7% of upper GI bleed.

Glyceryl trinitrate should be given along with vasopressin to prevent coronary vasospasm.

- In western country more than 90% cases cirrhosis is the cause. In India extrahepatic portal vein obstruction (33%) and extrahepatic periportal fibrosis (33%) is becoming more common. As liver is normal in these two conditions, patients get better cure rate by shunt surgery.

Sites of Portosystemic Collateralisation

1. *Lower end of oesophagus*, between left gastric and short gastric veins with azygos vein resulting in *oesophageal varices*—commonest.



Fig. 11.30: Portosystemic collaterals.

2. *Umbilicus,* between paraumbilical vein and anterior abdominal vein resulting in *caput medusae.*
3. *Lower end of rectum,* between superior haemorrhoidal vein and inferior, middle haemorrhoidal vein resulting in *piles.*
4. *Retroperitoneum (*vein of Retzius).
5. *Bare area of the liver.*



Fig. 11.31: Photo showing caput medusae.

Presentations

- *Triad of portal hypertension*
  - i. Oesophageal varices.
  - ii. Splenomegaly.
  - iii. Ascites.
- Jaundice.
- Features of encephalopathy.
- Recurrent infection.
- Coagulopathy.
- Hepatorenal syndrome.

Investigations

- Liver function tests.
- Ultrasound.
- Alfa-feto protein.
- *MELD scoring is Model for End-stage Liver Disease,* is assessed by specific equation using creatinine and bilirubin.
- *Child-Pugh score system.*
- Serological assessment—AFP, iron studies, α_1-antitrypsin, ceruloplasmin, autoantibodies, investigations for hepatitis.
- Doppler imaging to see vascular pattern, direction of blood flow, size of the vein.

Causes of portal hypertension

Prehepatic	*Hepatic (80%)*	*Posthepatic*
Portal vein or splenic vein thrombosis	Portal pyaemia	Budd-Chiari syndrome
Hypercoagulable status	Alcoholic cirrhosis	Constrictive pericarditis
Periportal inflammation	Idiopathic portal hypertension	Congestive cardiac failure
Trauma	Primary biliary cirrhosis	Veno-occlusive disease
Extrinsic compression from pancreas, stomach	Schistosomiasis	
Neonatal umbilicus sepsis	Hepatitis	
	Nodular regenerative hyperplasia	
	Wilson's disease	
	Haemochromatosis	
	Congenital hepatic fibrosis	

Note: Commonest prehepatic cause of portal hypertension is portal vein thrombosis.



Fig. 11.32: Patient with portal hypertension showing massive ascites with oedema of limb and scrotum—end-stage liver disease.

- CT/MRI to look for cause, see collaterals and liver nodules. *Magnetic resonance venogram (MRV)* is very sensitive noninvasive method to study extrahepatic portal system mainly to confirm extrahepatic portal vein thrombosis.
- Hepatic venous pressure gradient (HVPG): It is done using a balloon catheter. Difference between free hepatic vein pressure and wedged hepatic vein pressure is HVPG. Normal HVPG is 8 mm Hg. It is more than 10 mm Hg in cirrhosis.
- *Splenoportography:*
  - Bleeding/clotting time and prothrombin time should be normal prior to the procedure.
  - Antibiotic prophylaxis is a must.
  - A fine lumbar puncture needle is passed into the spleen through left 9th intercostal space in midaxillary line. It is placed into the pulp of the spleen.
  - Splenic pressure is assessed by connecting to a manometer.
  - Water soluble iodine dye is injected under C arm guidance. Flow, anatomy of portal system, size of the splenic/portal vein, site of the obstruction, communications are assessed.
  - Complications are—bleeding, infection, left shoulder pain.
  - Its use is replaced by MR angiogram/celiac angiogram.
- GI scopy—to identify varices.
- Liver biopsy.
- Endosonography.



Fig. 11.33: Laparoscopic view of cirrhosis with nodules on the surface.



Figs 11.34A and B: CT scan pictures showing ascites, splenomegaly.

Management of Portal Hypertension

a. *General measures:*
  - Anaemia to be corrected.
  - Nutrition supplementation.
  - Inj. vitamin K—10 mg IM for 5 days.

b. *Specific measures:*
  - *Treatment of oesophageal varices.*
  - *Prevention of hepatic encephalopathy.*
  - *Treatment of ascites.*

- *Measures to reduce portal pressure:*
  - Surgeries—Portosystemic shunt.
    - Nonselective.
    - Selective.
  - TIPSS.
  - Drugs to reduce the portal pressure like propranolol, nadolol, isosorbide-5-mononitrate.
- *Liver transplantation*.

OESOPHAGEAL VARICES

- May be asymptomatic.
- May present with *haematemesis* or *melaena* or as *recurrent bleeding*. Varices begin to bleed when portal pressure exceeds 12 mmHg.
- When present with severe haematemesis, patient shows features of *shock*.
- Mortality in bleeding varices is 25-30%.
- Factors related to variceal bleed are—portal venous pressure; gastro-oesophageal reflux causing ulceration; variceal size; variceal wall tension.

Types of Varices

1. *Oesophageal* which is in the lower 1/3rd of the oesophagus, usually 3 or more in number, graded as I, II, III, IV (based on gastroscopic findings) (80%).
2. *Gastric* which is fundal or in upper part of the stomach (20%).

Gastric varices

Classification

A. Extension of oesophageal varices
  I. Into lesser curve
  II. Into fundus
B. Isolated gastric varices
  I. In fundus common
  II. In other parts—stomach, duodenum—rare



Fig. 11.35: Picture showing variceal bleed.

Gastric varices are *treated by endoscopic N butyl cyanacrylate glueing, sclerotherapy.* Banding is usually not done.

Differential diagnosis for oesophageal varices (Other causes for haematemesis)

Bleeding peptic ulcer	Carcinoma stomach
Mallory-Weiss syndrome	Acute erosive gastritis
Bleeding disorders	Dieulafoy's syndrome
Gastric polyps	Gastric leiomyoma
Gastric lymphoma	

Investigations

- Hb%, liver function tests, packed cell volume, blood grouping and crossmatching, prothrombin time, platelet count, blood urea, serum creatinine.
- Endoscopy—*Grading of varices:*

I. Minimal varices without luminal prolapse
II. Moderate varices, with luminal prolapse and with minimal obscuring of O-G junction
III. Large varices, with luminal prolapse and with moderate obscuring of O-G junction
IV. Very large varices, with luminal prolapse and with complete obscuring of O-G junction

"Cherry red spots" may be sign of impending rupture. *Endoscopic sclerotherapy or variceal band ligation* should be tried in acute bleed also, while doing initial endoscopy to confirm the variceal bleed. If facility for sclerotherapy is not available or sclerotherapy/banding fails or not possible due to massive bleed, then balloon tamponade should be used.

Occasionally patient may be having varices, but bleeding (upper GI bleed) is due to other causes like duodenal or gastric ulcer.

- Once acute bleed stops patient is investigated further by splenoportography, liver biopsy, and superior mesenteric or celiac angiography, MR angiogram.

Note:
Cruvielhier-Baumgarten syndrome is loud venous hum heard at umbilicus in case of portal hypertension through congenital patent umbilical vein to portal vein.

- U/S abdomen to see status of the liver and portal vein (size *more than 13 mm* is significant).

Treatment of Oesophageal Varices

- Treatment of varices prior to bleed (no history of earlier variceal bleed)—*primary prophylaxis.*
  - Drugs—propranolol (reduces the portal pressure by 20% with pulse rate below 55/minute or 25% of resting pulse); nadolol (long acting, less lipophilic, not metabolised by liver); isosorbide mononitrate. Drugs reduce bleeding by 40%.
  - Endotherapy.

Note:
No prophylactic shunt surgeries.



Figs 11.36A to C: Different grades of oesophageal varices—endoscopic views.



Figs 11.37A and B: Active spurting variceal vessel. Endoscopic variceal banding is gold standard for oesophageal varices. It is not very useful for gastric varix.

- Treatment of varices after one or more episodes of bleeding—*secondary prophylaxis*.
  - Endotherapy.
  - Shunt surgeries.
  - Drugs like propranolol. Drugs may prevent rebleed by 40%.

Treatment of varices is considered under two headings:

- Emergency management of bleeding varices.
- Definitive management of varices.

SAAG means Serum, Ascites, Albumin, Gradient.



Figs 11.38A and B: Typical tortuous gastric varix and cyanoacrylate glue injection to the same.

EMERGENCY MANAGEMENT IN SEVERE HAEMORRHAGE

Control of acute bleed

- Initial important measures
  - Volume and electrolyte corrections; volume replacement using crystalloids with central line (CVP line placement with CVP maintained at 5 cm of water, sudden overload should be avoided which may precipitate pulmonary oedema/ascites/hyponatraemia)
  - Blood (massive transfusion of 5,10,15 bottles) and blood products (FFP, platelets) replacement endotracheal intubation, ventilator, critical care/ ICU management
  - Antibiotics, nutrition (TPN)/Vitamin K injection
  - Catheterisation and hourly urine output monitoring
  - Prevention of encephalopathy
  - Rest/sedation only if needed with care
- Pharmacotherapy
- Endoscopic banding/sclerotherapy
- Balloon tamponade
- TIPSS
- Devascularisation surgical procedures

Pharmacotherapy (Drugs)

- *Inj. Vasopressin 0.4* units/min for 24 hours is commonly used. 20 units in 100 ml 5% dextrose IV in 20 minutes also can be given. Vasopressin infusion is combined with glyceryl trinitrate tablets sublingually (to reduce cardiac side effects and increase the efficacy). Vasopressin is contraindicated in ischemic heart disease as it causes coronary vasoconstriction. Nitroglycerin prevents the coronary vasoconstriction and also reduces the portal pressure. Vasopressin can cause fluid retention and hyponatraemia.
  - Vasopressin *constricts* the splanchnic vessels thus *lowers the portal pressure* controlling the variceal bleed. It controls acute bleed in 80% of cases; it is often used along with balloon tamponade to increase bleeding control to 95%. Complications are—MI, arrhythmias, intestinal ischaemia, hyponatraemia and reduction in hepatic, renal blood flow.
- *Glypressin* (terlipressin), *desmopressin*. Glypressin 2 mg IV bolus 5th hourly is better than vasopressin. It has got longer half life with fewer side effects.
- *Somatostatin*—half life 2 minutes. Somatostatin does not cause systemic vasoconstriction like vasopressin but reduces the splanchnic and hepatic blood flow. It is given as continuous IV infusion 250 µg/hour after an initial bolus of 250 µg.
- *Octreotide*—half life 2 hours. 50 µg IV bolus and 50 µg/hour for 5 days.
- *Propranolol* decreases the portal pressure. It is used at later period as prophylaxis to prevent bleeding. Nadolol is also used which has got a longer half life.
- Metoclopramide (20 mg IV, it causes lower oesophageal sphincter constriction); isosorbide 5 mononitrate which is not metabolized in liver can be safely used in patients in liver failure.
- Acid inhibiting drugs (ranitidine IV, pantoprazole IV); and antifibrinolysins (tranexamic acid) are also used.

Endoscopic Therapy

Endotherapy—banding/sclerotherapy/glueing is used to control acute bleed as well as to prevent further bleeding. Pharmacotherapy is often combined with endotherapy.

1. *Endoscopic variceal banding (EVB)*
   - It is done for oesophageal varices. Banding/band ligation has become *gold standard and ideal* for oesophageal varices.
   - Multishoot banding device is used.
   - It is not commonly done for gastric varix as banding is difficult in retroflexed position.
   - Banded varices thrombose and slough off leaving small discrete ulcers.
   - It controls the bleeding in 90% cases. It is technically easier; chances of rebleeding are less; complications like perforation or stricture are less.
   - Earlier single band application device was used. It should be passed through an oesophageal overtube as it requires repeated endoscopy for shooting many bands. Multishoot banding device/applicator carries 5/6/8/10 bands. It does not require repeated removal and insertion of endoscope and so overtube can be avoided.



Fig. 11.39: Types of sclerotherapy.

2. *Endoscopic variceal sclerotherapy (EVS)*
   - Endoscopic sclerotherapy is also commonly used. It is technically easier, and cheaper.
   - Both intravariceal and paravariceal or only intravariceal injections are given.
   - In large varix lower part and upper part of the varix is sclerosed. Around 6 ml of sclerosant to lower part and 2-3 ml to upper part is injected. In small varix, injection is sufficient to only lower part.
   - In combined para and intravariceal injection, first paravariceal injection is done into submucosal plane followed by intravariceal injection.
   - Sclerosants used are—*Fatty acid derivatives*: ethanolamine oleate (5%); sodium morrhuate (2-5%); *Synthetic:* sodium tetradecyl sulphate; polidocanol (3%). Polidocanal is hydroxyl polyethoxydodecan (HPD/aethoxy skletrol 1-3%)
   - Varices should not be injected blindly.
   - In acute bleed it is better to insert an endotracheal tube to the patient and give 45° elevation to the head end of the table.
   - Sclerotherapy causes intimal injury, submucosal vessel thrombosis, ulceration, submucosal fibrosis. 5-6 sclerotherapies are needed to create total obliteration. If after sclerotherapy aspiration fluid is clear, then it is called as successful sclerotherapy. Success rate is 80%. Sclerotherapy during bleeding is called as acute sclerotherapy; at bleed free intervals it is called as chronic.



Fig. 11.40: Endoscopioc view of variceal banding. Endoscopic variceal banding (EVB) is done for oesophageal varices. Not commonly used for gastric varices.

   - *Complications*
     - Fever, retrosternal pain, massive bleed, perforation, mediastinitis, stricture oesophagus.
     - Atelectasis, pleural effusion, ARDS are known to occur.
   - Sclerotherapy is done weekly for 6-8 sessions until varices are obliterated. Later follow up endoscopy is done once in 3 months for 6 months; and once in 6 months for 2 years; then yearly for life time.
   - Sclerotherapy causes 70- 80% control of bleeding but rate of re-bleed is higher than banding.
3. *Endoscopic gluing using tissue adhesives*
   - It is commonly used for gastric varices.
   - Butyl cyanoacrylate is used. It hardens in 20 minutes. If properly injected into the varix it controls the bleeding immediately with 90% success rate.
   - Risk of equipment damage is high if it spills into the working channel and blocks it. Lipiodol is used along with cyanoacrylate to delay premature hardening. Silicone oil is applied to the tip of the instrument to prevent the damage.
   - Needle tip is correctly placed into the gastric varix and 0.5-1 ml of adhesive is injected. Instrument should be removed immediately.
4. *Endoscopic thrombin/dilute adrenaline injection into the varices.*

Balloon Tamponade

- *Four lumen Minnesota tube/Sengstaken-Blakemore tube/ Linton's tube/modified 4 lumen Pitcher tube* are used for the procedure. If bleeding does not stop by banding/sclerotherapy/gluing, balloon tamponade should be tried. Most of the time bleeding comes under control by balloon tamponade.
- Initially gastric balloon is inflated with 300-400 ml of *air*, later the oesophageal balloon is inflated with air at 30-40 mmHg pressure. This should be deflated for a short period in 12-24 hours so as to prevent necrosis of oesophageal mucosa. Inflation of gastric balloon is most important. Oesophageal balloon inflation is done if needed only.

During infancy until about the end of the third year the normal liver extends one to two finger breadth below the costal margin. During inspiration at this period of life, the extreme edge of normal spleen is also palpable.



Fig. 11.41: Child with Sengstaken-Blakemore (SB) tube for haematemesis showing three channels.



Fig. 11.42: Sengstaken-Blakemore tube showing how it controls the bleeding varices. Oesophageal balloon is inflated with 40 mmHg pressure of air, gastric balloon with 400 ml of air.

- X-ray should be taken to confirm the position of balloons.
- Usually within 24-72 hours bleeding comes under control and in mean time resuscitative measures has to be undertaken. Success rate is very good but only temporary. It should be followed by definitive procedures like banding/sclerotherapy. Otherwise rebleed rate is 60%. Balloon tamponade is only a rescue procedure and emergency bridging method for more definitive procedures.

TIPSS (Transjugular Intrahepatic Portosystemic Shunt/Stenting)

It is used if all other earlier methods mentioned have failed, in less than 10% of acute bleed patients. It commonly controls the uncontrolled acute bleeding and prevents further bleed and also acts as *a bridge* for *future transplantation*.

Surgeries for Acute Bleeding Varices

- *Open oesophageal stapler transection and oesophagogastric anastomosis (*Jhonston).
- *Borema—Crile operation*: The oesophagus is opened. Oesophageal varices are under-run using vicryl.
- *Sugiura-Futagawa* operation: Oesophagogastric transection and devascularization, vagotomy, pyloroplasty and splenectomy.
- *Milnes-Walker* thoracic oesophageal transection
- *Tanner's* abdominal oesophagogastric resection.
- *Hassab* operation.

Shunt surgeries are not commonly used to control bleeding in acute stage.

***Note*:**
Once a bleed, there will be always a rebleed without treatment and rebleed is much more severe than earlier bleed. Time gap between each rebleed shortens.

Other Measures

- *Liver biopsy* to confirm the cause for the portal hypertension (after controlling PT).
- *Correction of clotting mechanisms* by Vit. K, blood, plasma or platelet concentrate.

Control of encephalopathy
- Purgatives
- Protein free diet
- Lactulose syrup 30 ml tid
- Lactitol
- Neomycin orally—1.5 gm 6th hourly
- Parenteral nutrition

Sclerotherapy

Sclerosants used	*Method of injection*	*Problems with sclerotherapy*
Ethanolamine oleate (5%)	Both intravariceally (6 ml) as well as para variceally (2-3 ml) to create thrombosis as well as fibrosis	Oesophageal ulceration
Sodium tetradecyl sulphate (1-3%)		Oesophageal perforation
Sodium morrhuate 2-5%		Worsening of bleeding
Polidocanol 3%	Repeated sessions in 2-3 weeks	Aspiration pneumonitis
Absolute alcohol	Total 15 ml in one session	Difficult to inject gastric varices
		Chest pain and dysphagia are common

DEFINITIVE MANAGEMENT OF VARICES

- ***Sclerotherapy***
- ***Shunt surgery***

  Prophylactic shunt surgery should not be done.

  Shunt surgeries should not be done if the varices have not bled before.

Indications

Child's Grades A and B.

(Child's grading is used for selecting patients for surgery and predicting prognosis.)

Surgery is contraindicated in Child C.

1. **Non-selective shunts**:
   - *Porta-caval shunt* (end-side, side-to-side).
   - Mesentericocaval shunt with or without graft.
   - Mesenterico-renal shunt.
   - *Proximal splenorenal shunt—Linton's shunt.*

Non-selective shunts control and prevent further bleeding as well as reduce the ascites. But since it diverts the blood from liver *there is high incidence of encephalopathy.*

Note:

End to side porta caval shunt is called as ECK fistula.

2. **Selective shunts:**
   a. *Distal splenorenal shunt—Warren's shunt*. End of splenic vein is shunted to the side of the left renal vein. Splenic vein should be more than 10 mm in size (diameter). It selectively decompresses the portal bed near oesophago-gastric area (so that it prevents bleeding). Liver is also perfused adequately and so possibility of encephalopathy is less.
   b. *Inokuchi shunt* is a selective shunt between IVC and left gastric vein (using a graft).

- ***Splenectomy***

Left sided portal hypertension also called as *segmental portal hypertension* (sinistral portal hypertension) is due to splenic vein thrombosis (If partial channels are present within it, it is called as *splenic vein cavernoma*). Here liver is normal and *splenectomy* alone will correct the condition.

- ***TIPSS (Transjugular Intrahepatic Portosystemic Stenting/ Shunt)***
  - Size of stent must be 10 mm. It is a nonsurgical, interventional radiological method wherein a stent is placed in the liver between hepatic venule and portal venule through a guidewire following dilatation.
  - It is a simple and easier method to reduce portal pressure.
  - It can cause hepatic encephalopathy, bleeding, bile leak and infection.
  - It is contraindicated in encephalopathy, tumours and liver cysts.
  - It is quite useful as a temporary measure to reduce portal bed pressure, before doing orthotopic liver transplantation in cirrhotic patients.



Fig. 11.43: TIPSS.

Child's grading of the severity of liver disease

Clinical and biochemical measurement	***Points scored***		
	1	2	3
Bilirubin (mg/dl)	< 2.0	2.0-3.0	> 3.0
Albumin (gm/dl)	> 3.5	3.0-3.5	< 3.0
Ascites	None	Controlled	Uncontrolled
Mental status	Normal	Disoriented	Coma
Nutrition	Very good	Good	Poor
Total Score	**< 6** *Child's 'A'* disease	**7-9** *Child's 'B'* disease	**10-15** *Child's 'C'* disease
(Pugh's modification)			
Prothrombin time seconds prolonged	Increase upto 3	Between 3-6	> 6



Fig. 11.44: End-to-side portocaval shunt (ECK fistula).


Portocaval shunt
Portal vein
Splenic vein
Spleen
Kidney
Inferior mesenteric vein
Kidney
IVC
Superior mesenteric vein

Fig. 11.45: Side-to-side portocaval shunt.


Portal vein
Splenic vein
Spleen
Kidney
IVC
Inferior mesenteric vein
Kidney
Mesentericocaval shunt
SMV
CIV
CIV

Fig. 11.46: Side-to-side mesenteriocaval shunt.


Portal vein
Splenic vein
Spleen
Kidney
Inferior mesenteric vein
Kidney
Superior mesenteric vein
CIV
Mesentericocaval shunt (graft)

Fig. 11.47: Side-to-side mesenteriocaval shunt using a graft.


Splenic vein
Spleen (removed)
Inferior mesenteric vein
Portal vein
Kidney
Proximal splenorenal shunt
Kidney
CIV
SMV

Fig. 11.48: Proximal splenorenal shunt (Linton's)


(End to side)
Left renal vein
Spleen
Splenic vein
Portal vein
Kidney
IMV
Kidney
Distal spleno-renal shunt
CIV
SMV

Fig. 11.49: Distal splenorenal shunt (Warren's, DSRS)—selective.


Oesophagus
Stomach
Gastrotomy
Stapler (end-to-end)
Duodenum

Fig. 11.50: Oesophageal open stapler transection.

Problems with TIPSS

- Post-stent encephalopathy—40%
- Stenosis (50%) and recurrent varices
- Bleeding
- Bile leak
- Sepsis

Surgeries for portal hypertension

- Devascularisation surgeries
- Decompression surgeries
- Orthotopic liver transplant (OLT)

Surgeries for oesophageal varices and portal hypertension

Nonselective shunts

- End-to-side portacaval shunt (ECK fistula)
- Side-to-side portacaval shunt
- Mesentericocaval shunt

- Mesentericocaval shunt with graft
- Proximal splenorenal shunt—Linton's shunt
- TIPSS

Selective shunts

- Distal splenorenal shunt—Warren's shunt
- Inokuchi shunt between left gastric vein and IVC through a graft.

Porta azygos disconnection

- Oesophageal stapler transection of Johnston
- Boerema-Crile operation—thoracic approach
- Milnes-Walker thoracic oesophageal transection
- Tanner's abdominal oesophagogastric transection
- Hassab operation. Devascularisation and splenectomy.
- Sugiura-Futagawa operation—vagotomy, pyloroplasty, devascularisation, splenectomy
- Splenectomy

Liver transplant

- ***Liver transplant (orthotopic)***

Liver transplant is becoming popular for cirrhosis with varices. It is ideal, final and best. But donor availability and cost is the problem. If patient is for orthotopic liver transplantation (OLT), open shunt surgeries should not be done as liver hilum should be kept virgin for effective transplantation. TIPSS can be done as a bridge in such patients.

PORTAL HYPERTENSIVE GASTROPATHY

- Portal hypertension causes vascular dilatation and ectasia in the stomach which appears pink, speckled, with red mosaic pattern in the gastric mucosa. It occasionally causes upper GI bleed (5% of total; 20% of portal hypertension bleed). Endoscopy is diagnostic.
- Mucosal changes are diffuse and so not amenable for endotherapy.
- Portal gastropathy is more common in cirrhotic patients.
- Commonly presents with chronic bleed causing anaemia; but acute bleed with haematemesis and melaena also can occur.
- Treatment is mainly to reduce the portal pressure using propranolol.

ASCITES

It is pathological collection of fluid in the peritoneal cavity.

In Western countries cirrhosis is the commonest cause (80%) of ascites. Ascites is the most common complication of cirrhosis. It is a poor prognostic factor. Portal hypertension, renin angiotensin aldosterone pathway causing renal sodium retention, increased hydrostatic pressure in hepatic sinusoids and splanchnic vessels cause ascites. In metastatic malignancy ascites develops due to liver secondaries, peritoneal carcinomatosis which secretes protein rich fluid and lymph. Leakage of pancreatic juice, bile, lymph also causes specific ascites.

Types

- Mild — Up to 150 ml amount required to demonstrate radiologically
- Moderate — 1500-2000 ml causes clinical dullness in flanks.
- Severe — > 2000 ml.

Classification

- *Transudate* (Protein < 2.5 gm/ dl).
  - CCF—Commonest (SAAG > 1.1).
  - Hypoproteinaemia.
  - Anaemia.
  - Beri-beri.
  - Nephrotic syndrome.
  - Portal hypertension.
  - Polyserositis.
- *Exudate* (Protein > 2.5 gm/dl) (SAAG < 1.1).
  - Peritoneal diseases.
    - Tuberculosis.
    - Bacterial, fungal and parasitic infection.
    - Neoplasm.
  - Collagen disorder.
  - Eosinophilic gastroenteritis.
  - Granulomatous peritonitis.

Management of oesophageal varices

Emergency management in acute bleed	***Definitive management***
1. Balloon tamponade	1. Sclerotherapy, Banding, Glueing
2. Pharmacotherapy	2. Nonselective shunts: Porta caval
3. Oesophagogastric transection	Mesentericocaval
4. Borema-Crile operation	Mesentericorenal
5. Sugiura-Futagawa operation	3. Selective shunts: Distal-splenorenal shunt
6. Sclerotherapy	Inokuchi shunt
	4. Splenectomy
	5. TIPSS
	6. Liver transplant

Clinical Features

Symptoms

- Gradual distention of abdomen
- Severe cases of ascites may lead to respiratory embarrassment.
- Specific features related to the cause may be evident.
- Risk of spontaneous bacterial peritonitis.

Signs

Mild:

- *Puddle sign*—Tapping around the umbilicus in knee-elbow position elicits dullness.

Moderate:

- Positive shifting dullness in the abdomen.

Severe:

- Positive fluid thrill.
- *Tanyol sign*: Umbilicus is shifted upward in pelvic mass (ovarian cyst) downwards in ascites.
- Hamilton ruler test is also used to differentiate ascites from ovarian cyst.
- *Blaxland (Athelstan Blaxland) ruler test* shows pulsation in ovarian cyst not in ascites. A flat ruler is placed on the abdomen just above the anterior superior iliac spines and pressed firmly backwards. If the swelling is due to ovarian cyst, transmitted aortic pulsation can be felt across the ruler.
- *Smiling* horizontal *umbilicus*.

Investigations

- U/S abdomen.
- *Ascitic tap*—Always should be done after emptying the bladder by placing the needle below the umbilicus lateral to the rectus muscle. It may be *Diagnostic* or *Therapeutic tap.* Fluid is sent for analysis.
  - Ascitic fluid having cells less than 1000/mm^3 is clear; from 1000-5000/mm^3 is unclear; more than 5000/mm^3 is turbid/cloudy.
  - Non-traumatic blood in the ascitic fluid does not clot. Traumatic (trauma during tapping) blood will clot.
  - Lipid in the ascitic fluid is seen in chylous ascites.
  - In cirrhotic patients ascitic fluid without SBP contains less than 500 cells/mm^3 with 50% of them are neutrophils. If ascitic fluid contains more than 250 neutrophils/mm^3 it suggests acute inflammation.
  - ***Serum ascites albumin gradient (SAAG)*** is calculated by subtracting ascitic fluid albumin level from serum albumin level. If SAAG more than 1.1, it is called as high gradient which suggests portal hypertension. If SAAG is less than 1.1, it is called as low gradient which suggests absence of portal hypertension. SAAG is 98% accurate.
    - *High gradient SAAG* is seen in—cirrhosis, alcoholic, cardiac ascites, multiple liver secondaries, fulminant liver failure, Budd-Chiari syndrome, portal vein thrombosis.
    - *Low gradient SAAG* is seen in—peritoneal secondaries, peritoneal tuberculosis, pancreatic ascites, biliary ascites, nephrotic syndrome, lymph leak, connective tissue diseases causing ascites.



Figs 11.51A and B: Ascites on CT scan and gross clinical look of severe ascites.

Treatment

- The cause is treated.
- Therapeutic tap—It should be slow and gradual or staged tapping. Up to 5 litres can be tapped in 90 minutes.
- Ascitic shunt surgeries.
- Spironolactone, salt restriction.
- Salt (sodium) restriction in diet is important. It is assessed by measuring 24 hour urinary sodium excretion. If it is more than 78 mmol/day patient will loose weight with salt restricted dite.
- Spironolactone 100 mg/day and frusemide 40 mg/day promotes natriuresis and reduces the ascites. It is very useful after paracentesis to prevent re-accumulation of fluid.
- TIPSS.
- Liver transplantation.

Complications of ascites

- Respiratory embarrassment
- Umbilical hernia with erosion, ulceration and leak
- Spontaneous bacterial peritonitis

ASCITES IN PORTAL HYPERTENSION

Causes

- Hypoproteinaemia.
- Increased hydrostatic pressure.
- Decreased colloidal osmotic pressure.
- Lymphatic blockage.
- Altered aldosterone mechanism.

Treatment of ascites in portal hypertension

- Medical—spironolactone, salt restriction
- Abdominal paracentesis
- TIPS as a bridge to liver transplant
- Liver transplantation

Abdominal fluid

- *Straw coloured fluid*
  - Cirrhosis
  - Tuberculosis
  - Hypoproteinaemia
  - Nephrotic syndrome
  - Budd-Chiari syndrome (Hepatic vein thrombosis)
  - Constrictive pericarditis
  - Chronic pancreatitis
  - Ovarian tumour (Meig's syndrome)
  - Malignancy
- *Haemorrhagic fluid*
  - Traumatic tap
  - Tumour
  - Acute haemorrhagic pancreatitis
  - Bleeding disorder
- *Chylous fluid*
  - Parasitic infestation—filariasis
  - Tuberculosis
  - Malignancy of thoracic duct
  - Trauma to thoracic duct
  - Thrombosis of subclavian vein
- *Purulent fluid*
  - Abdominal infections
  - Penetrating wounds or infections
  - Pyaemia and septicaemia
  - Rupture/perforation of an organ



Fig. 11.52: Ascites. Observe the dilated abdominal veins.

Investigations

Liver function tests, U/S, CT scan, MRI, gastroscopy.



Fig. 11.53: Massive ascites in severe portal hypertension.

Treatment

- Correction of serum proteins, salt restriction.
- *Ascitic tap*—Site of tap is below the umbilicus, lateral to the rectus muscle. Bladder should be empty before tapping. Slow gradual tapping is important, otherwise patient goes in for fluid and electrolyte imbalance. Up to 5 litres can be tapped at a time.
- *Spironolactone* 25 mg orally BD and other diuretics are often used.

- ***Le Veen shunt*** is a one way valve *peritoneo-venous shunt* done in order to drain ascitic fluid from peritoneal cavity to internal jugular vein**.**
- ***Denver* shunt** is similar to Le Veen type with additional facility of having a chamber to evacuate the debris by digital pressure.
- *Liver transplantation* may be beneficial for ascites in liver diseases.
- The cause is treated.
- TIPSS.

Ascitic shunts are not used when there is

- Hepatorenal syndrome
- Bacterial peritonitis

Complications of Ascitic Shunt Procedure

- Bleeding, infection.
- Displacement, blockage.
- Thrombosis of the vein, volume overload.

BUDD-CHIARI'S SYNDROME

It is a syndrome due to obstruction of the hepatic veins.

Usually three major hepatic veins are involved by thrombosis or block. It is common in *females*.

Causes

1. Spontaneous thrombosis of hepatic veins (due to myeloproliferative diseases (50%) commonly seen in adults and IVC webs commonly seen in children).
2. Neoplastic encroachment of hepatic veins.

Majority of cases

3. Polycythaemia.
4. Contraceptive pills.
5. A membranous web in suprahepatic portion of IVC—a curable type of Budd-Chiari syndrome.
6. Plant extracts of Senecio and Crotalaria used in herbal tea in Jamaica causes acute Budd-Chiari syndrome.
7. Protein C, S or antithrombin III deficiency, Behcet's disease.

Clinical Features

1. *In acute form:* Nausea, vomiting, severe pain in right hypochondrium, rapid enlargement of liver, hypotension and often death.
2. *In less sudden onset type:* Rapid development of ascites, hepatic insufficiency, oedema feet, features of IVC obstruction, hepatic coma can occur.
3. *Chronic type:* Present with hepatic cirrhosis, ascites, oesophageal varices, infection, which gradually leads to hepatic failure.
4. Jaundice, ascites and hepatomegaly is common.

Investigations

- Transcutaneous Doppler will show hepatic vein thrombosis and collaterals across retrohepatic IVC.
- CT shows caudate lobe (segment I) hypertrophy with nonhomogenous contrast enhancement.

Treatment

- Anticoagulation is the standard therapy.
- In membrane obstructing IVC, it can be cut by transatrial meatotomy, i.e. under guidance a catheter is passed, via right atrium to IVC and the web is cut. It is curable.
- In other types of portacaval or mesocaval shunts are tried but results are equivocal.
- Mesoatrial shunt between right atrium and SMV using Gortex graft.
- TIPSS is also useful.

HEPATIC FAILURE

Aetiology

- Cirrhosis.
- Congenital diseases.
- Terminal liver diseases.
- Drug induced.
- Fulminant hepatitis.

Precipitating Causes

- Infection.
- GIT bleeding.
- Surgery.
- General anaesthesia.
- Drugs—narcotics, analgesics.
- Old age.
- Electrolyte abnormality—hypokalaemia.

Clinical Features

- Weakness and jaundice.
- Cyanosis.
- Fever, fetor hepaticus.
- Features of hyperdynamic circulation: Bounding pulse, flushed extremities, fresh crops of spider naevi, palmar erythemas.
- Loss of axillary and pubic hairs.
- In male, gynaecomastia and testicular atrophy.

Fulminant Hepatic Failure

It occurs as a result of massive liver cell death due to:

1. Acute viral hepatitis.
2. Drugs like carbon tetrachloride, halothane, cytotoxic drugs.

Presentation

- Sudden onset of the disease
- Personality changes
- Delirium
- Altered behaviour
- Oliguria and kidney failure

Treatment

- Correction of precipitating factors, e.g. GIT bleed, infection, hypokalaemia.
- High carbohydrate diet.
- IV fluids or nasogastric feeding.
- Diuretics and morphine is avoided as it may precipitate coma.
- Correction of hypoglycaemia and electrolytes.
- Management of renal failure by haemodialysis.
- Correction of clotting factors.
- Temporary hepatic support like:
  - Exchange blood transfusion
  - Cross circulation between donor and patient
  - Extracorporeal perfusion of patient's blood through pigs liver.
  - Perfusion through columns of activated charcoal.

HEPATIC ENCEPHALOPATHY

It is a chronic neuropsychiatric disorder wherein blood bypasses the liver, as a result of which, detoxification of *toxic products* do not occur, which, in turn enters the brain to cause toxicity.

Toxic Products

1. Ammonia.
2. Aminobutyric acid.
3. Mercaptan.
4. Methionine.
5. Short chain fatty acids.

Collaterals developed in chronic liver disease like cirrhosis or after shunt surgeries, allow the blood with toxic products to enter the brain causing toxic effects (As toxic products of bacterial degradation, and nitrogenous material from the bowel is normally metabolized in the liver, these toxic products bypass the liver through collaterals to enter the cerebral circulation).

Encephalopathy is precipitated by:

- Large protein meal.
- GIT bleed.
- Hypokalaemia.
- Drug-induced diuresis.
- Uraemia.
- Narcotics.
- Infection.
- Dehydration.
- Constipation.

Clinical Features

- Disorientation, *flapping tremor*.
- Cogwheel rigidity of limbs, ankle clonus.
- Slurred speech, intellectual deterioration.
- Personality changes.

Grading of hepatic encephalopathy

- Decreased skills—Subclinical
- Confusion—Grade 1
- Drowsiness—Grade 2
- Somnolence, hyperreflexia—Grade 3
- Coma—Grade 4

Treatment

To reduce the entry of nitrogenous products and toxic products from the gut into the circulation.

- Restriction of dietary protein.
- Removal of blood from bowel by purgation or enemas.
- Antibiotics administration.

Oral neomycin to reduce bacterial load inside the bowel lumen. 1 gm 4-6 hours or metronidazole 250 mg every 8 hours.

- Oral lactulose 30-50 ml 4 times a day.
- Sedatives like benzodiazepines and opioids are avoided.
- Correction of vitamin and electrolyte deficiencies.
- Lactulose enema: 300 ml of lactulose in 700 ml of water can be given.

HEPATORENAL SYNDROME

- It is development of acute renal failure due to severe hepatic or biliary disease with jaundice.
- Patient develops oliguria, azotaemia and hyponatraemia.

Causes

- Bile salt sludging in the tubules.
- Absorption of toxins.
- Increased ADH release.
- Hypoperfusion and renal ischaemia.
- It may be precipitated by surgery, stress.

Treatment

- Mannitol infusion.
- Diuretics.
- The cause is treated.
- Dialysis.
- Liver transplantation.

HEPATIC RESECTION

Anatomy and Types of Resections

- Right hepatic artery divides into anterior and posterior segmental arteries. Left hepatic artery divides into medial and lateral segmental arteries.
- Portal vein divides at porta hepatis as right and left branches and these branches enter the respective lobes of the liver.
- Hepatic veins originate as central vein of the liver which is formed by liver sinusoids. Middle hepatic vein is located in main lobar fissure. Left hepatic vein is in left segmental fissure—upper portion; right hepatic vein is in right segmental fissure. Inferior part of middle and anterior segments are drained by middle hepatic vein. In 60% of cases middle and left hepatic veins join to form single trunk to enter IVC.
- Main portal fissure divides liver into two lobes by Cantlie's line from anteroinferior part of gallbladder fossa to left of the IVC with 75° angle with horizontal plane. It divides into right/left paramedian sectors/segments.
- Liver is divided into 8 segments (Couinaud segments). Right lobe is formed by segments V, VI, VII, VIII from front to

Nomenclature for liver resection

Segments	*Brisbane - 2000*	*Couinaud - 1957*	*Goldsmith and Woodburne—1957*
V-VIII	Right hemihepatectomy	Right hepatectomy	Right hepatic lobectomy
IV-VIII	Right trisectiontectomy	Right lobectomy	Extended right hepatic lobectomy
II-IV	Left hemihepatectomy	Left hepatectomy	Left hepatic lobectomy
II, III	Left lateral sectionectomy	Left lobectomy	Left lateral segmentectomy
II, III, IV, V, VIII	Left trisegmentectomy	Extended left hepatectomy	Extended left lobectomy

Indications	*Contraindications*
• Primary/Secondary malignancy from gallbladder or colorectum or carcinoids	• Acute hepatitis—viral/alcoholic
• Benign tumours of liver	• Severe chronic hepatitis
• Parasitic/non-parasitic cysts—hydatid cysts/simple liver cysts	• Poor liver reserve
• Refractory abscess/Caroli disease / RPC	• Severe portal hypertension
• LDLT	• Severe coagulopathy
• Klatskin's tumour	• Severe thrombocytopenia—platelet count less than 30,000/-
• Trauma to liver	

behind. Left lobe formed by segments II, III and IV. Segment I (Spigel lobe) is caudate lobe which has got independent blood supply.

- Resection along the main portal fissure (Cantlie's line) and removal on right side is *right hemihepatectomy* and removal on left side is *left hemihepatectomy*.
- Resection on right of the ligamentum teres is called as *right trisegmentectomy* (older—right lobectomy); and left of the ligamentum teres is called as *left lateral segmentectomy*-segment II and III (older left lobectomy).
- Removal of single segment is called as *unisegmentectomy.*
- *Plurisegmentectomy* is removal of two or more segments. Segments IV and V are removed in carcinoma of gallbladder.
- Removal of small portion of liver either within the segment or traversing segments is called as *wedge resection* of the liver.

Technical Principles

Inflow (portal vein, hepatic artery, bile duct) control; outflow (hepatic veins) control; parenchymal transection; preservation of adequate sized liver remnant with intact inflow, biliary drainage and venous outflow; mobilisation of left and right triangular ligament; ligation of branches of portal vein and hepatic artery and resection of hepatic duct branch of the side; ligation of hepatic vein at a later period; proper haemostasis and ligation of individual biliary ductules. Retrohepatic caval dissection includes—dissection of right adrenal vein, inferior hepatic veins and IVC ligament.

Types of Hepatectomy Techniques

- Preliminary vascular section (Lortat-Jacob).
- Primary parenchymal transection (Ton That Tung in 1965).
- Selective clamping.
- Total vascular exclusion.
- Pedicular clamping (Pringles).
- Suprahilar clamping (Glissonian approach).
- Intrahepatic portal control.

Procedure

- Proper preoperative preparation is essential. LFT, prothrombin time is done. Adequate blood, FFP, along with central line is kept ready.
- Subcostal or thoracoabdominal incision is needed.
- Proper mobilisation, identification and dissection of portal areas is essential; dissection of hepatic veins, usage of vascular clamp secured ligation of branches of portal vessels and major hepatic veins are essential steps.

Techniques of parenchyma dissection	*Intraoperative ultrasound is done to:*
• Kelly clamp and bipolar forceps	• Identifying tumour
• Water jet dissection	• Recognising the anatomy
• Ultrasonic dissection	• Unexpected contralateral tumour
• Ultrasound cutting	• Intrahepatic selective vascular control using a balloon catheter
• Dissecting sealer	• Guided biopsy

How much to cut:

- Remnant liver—≥30% of the original liver volume with complete venous drainage is safe

After completion of resection	*Complications*
• Check for bile leak by injecting dye through cystic duct	• Bleeding, infection, septicaemia
• Check for absolute haemostasis.	• Subphrenic abscess formation
• Cholangiogram to confirm contralateral biliary patency	• Bile leak, haemobilia
• Fix the left lobe	• Liver failure
	• Pleural effusion, empyema

- Liver is dissected by finger dissection, back of scalpel, Cavitron ultrasonic surgical aspirator (CUSA), laser ligation of biliary radicles and vascular branches individually using non-absorbable sutures are other methods.
- Control of bleeding is done by on table Pringle manoeuvre, gel foam, cautery, laser and vessel ligation.
- Proper antibiotic coverage is needed to prevent sepsis.
- Postoperative ICU care is needed.



Figs 11.54A and B: Liver resection. Suprahepatic outflow control and parenchymal marking is shown (*Courtesy:* Dr Ravishankar, MCh, Gastroenterologist and Liver Transplantation Surgeon, Bengaluru).



Figs 11.55A to C: Liver resection of left lobe tumour. CT picture, incision scar and specimen are also shown.

PORTAL BILIOPATHY

- In patients with portal hypertension, particularly with extrahepatic portal vein obstruction, *portal biliopathy* producing biliary ductal and gallbladder wall abnormalities are common. Portal cavernoma formation, *choledochal varices* and ischemic injury of the bile duct have been implicated as causes of these morphological alterations.
- Gallbladder varices, bile duct varices are typical. Often it may cause torrential haemorrhage per se or on table if patient is undergoing choledocholithotomy.
- While a majority of the patients are asymptomatic, some present with a raised alkaline phosphatase level, abdominal pain, fever and cholangitis.
- Choledocholithiasis may develop as a complication and manifest as obstructive jaundice with or without cholangitis.
- Endoscopic sphincterotomy and stone extraction can effectively treat cholangitis when jaundice is associated with common bile duct stones.
- Definitive decompressive shunt surgery is sometimes required when biliary obstruction is recurrent and progressive.
- Portal biliopathy is a specific entity which may cause severe technical difficulties especially bleeding during ERCP sphincterotomy or open biliary surgeries.

Differential diagnosis of space occupying lesions in the liver

- Hepatoma
- Amoebic liver abscess
- Secondaries in the liver
- Cysts of the liver
- Haemangioma

Chapter 12 Gallbladder

> *If the passages which convey the bile to the intestine, be obstructed from inflammation or scirrhous, the bladder gets over-distended, and the bile regurgitates; it therefore becomes mixed with the blood, and the blood, passing over the whole system, carries the bile to every part of the body, which acquires the appearance of bile. But the hardened faeces are white and clayey, as not being tinged with bile, because the bowels are deprived of this secretion.*
>
> **—Aretaeus the Cappadocian**

CHAPTER OUTLINE

- Surgical Anatomy
- Oral Cholecystogram
- IV Cholangiogram
- Endoscopic Retrograde Cholangiopancreatography
- Percutaneous Transhepatic Cholangiography
- Magnetic Resonance Cholangiopancreatography
- Radioisotope Scan Study
- Peroperative Cholangiogram
- Postoperative T-Tube Cholangiogram
- Congenital Anomalies of Gallbladder
- Choledochal Cysts
- Caroli's Disease
- Biliary Atresia
- Gallstones
- Acute Cholecystitis
- Acute Acalculous Cholecystitis
- Empyema Gallbladder
- Mucocele of the Gallbladder
- Chronic Cholecystitis
- Cholecystoses
- Dissolution Therapy for Gallstones
- Choledocholithiasis
- Sump Syndrome
- Courvoisier's Law
- Surgical Jaundice
- CBD Strictures
- Sclerosing Cholangitis
- Gallbladder Polyp
- Benign Biliary Papilloma
- Carcinoma Gallbladder
- Cholangiocarcinoma
- Klatskin Tumour
- Biliary Fistulas
- Gallstone Ileus
- Hemobilia
- White Bile
- Cholecystectomy
- Laparoscopic Cholecystectomy
- Single Incision Laparoscopic Surgery (SILS) in Cholecystectomy
- Bile Duct Injuries
- Post-cholecystectomy Syndrome
- Biliary Dyskinesia

SURGICAL ANATOMY

Gallbladder

It is a pear-shaped (size is 5-12 cm) reservoir, located in a fossa on the inferior surface of the liver.

Parts

- Fundus, body, infundibulum and neck. *Hartmann's pouch* is pathological one located in the infundibular region created by gallstones.

Your mind will give back exactly, what you put into it.



Fig. 12.1: Anatomy of gallbladder.



Fig. 12.2: On table finding of empyema gallbladder with inflamed areas near Calot's triangle.

- Gallbladder drains through cystic duct into common hepatic duct to form common bile duct.
- It is supplied by cystic artery, a branch of right hepatic artery.
- *Calot's triangle* is formed by common hepatic duct to the left, cystic duct below, and inferior surface of liver above. Cystic artery originating from right hepatic artery passes behind the common hepatic artery, enters the Calot's triangle to reach the gallbladder. It contains lymph node of '*Lund' (Fred Bates Lund)*.
- Often cystic artery, hepatic artery, cystic duct have anomalous positions and anomalous origins. Both gallbladder neck and cystic duct contain mucosal fold called *valves of Heister.*

Extrahepatic Biliary Tree

- The left hepatic duct is formed by the ducts draining II, III, IV segments of the liver. The right hepatic duct is formed by the ducts draining V, VI ,VII, VIII segments of the liver. Both join to form the *common hepatic duct*, which joins with the cystic duct to form the *common bile duct*.
- Common bile duct is normally 10-12 cm in length and 6-8 mm in diameter. It joins the major pancreatic duct in the wall of the 2nd part of duodenum to form the *ampulla of Vater*. Intraduodenal part of common bile duct (CBD) is surrounded by smooth muscle fibres called as *sphincter of Oddi.*

Blood supply: From gastroduodenal, retroduodenal, posterosuperior pancreaticoduodenal arteries.

Bile

- Daily up to 1000 ml of bile is secreted from the liver which contains water (98%), bile salts, bile pigments, fatty acids, lecithin, cholesterol, and electrolytes (sodium, potassium, chloride, bicarbonate, calcium, magnesium) with a pH more than 7.0.
- Main function of gallbladder is to concentrate and store the bile. Capacity of gallbladder is 40-50 ml.
- Bile salts form micelle which makes cholesterol soluble. Bile salts (i.e. salts of cholic and chenodeoxycholic acids) with formed deoxycholic acid (in the bowel) enters the enterohepatic circulation to get resecreted in the bile.
- Bilirubin conjugated in the liver is secreted into the bile, which in the bowel is converted into urobilinogen by bacteria. Urobilinogen gets absorbed in the bowel, enters the liver for resecretion again and part of it is excreted in the urine. Absence of urobilinogen in the urine signifies obstructive jaundice.
- In the absence of gallstones or any other disease, bile is sterile. Symptomatic gallstone disease shows positive culture for bacteria, commonest being *E. coli* and *Klebsiella*.



Fig. 12.3: CBD parts.

ORAL CHOLECYSTOGRAM (OCG; GRAHAM-COLE TEST)

- This test is done to study function of the gallbladder.
- Patient is advised to have fat free diet for 3 days. Previous night 6 tablets of *iopanoic acid* (Telepaque) is given orally. On the day of OCG, plain X-ray abdomen in erect posture is taken to visualise the gallbladder.



Fig. 12.4: Oral cholecystogram with smooth filling defect (Cystic duct stone).

- Later, fatty meal is given and one more X-ray is taken to see the change in the size of the gallbladder (which should be less in size compared to the earlier film, as the gallbladder contracts on stimulation with fat rich meal if it is functioning normally). Smooth filling defect signifies nonopaque stone.

Note:

- One tablet of Iopanoic acid is 500 mg.

Contraindications

- Patients with serum bilirubin > 3 mg%
- Acute cholecystitis
- Vomiting

IV CHOLANGIOGRAM

- It is to visualise bile ducts and biliary tree, by injecting IV *Meglumine ioglycamate* (Biligram) and taking X-ray abdomen.
- It can be combined with OCG.
- Problems with this method are poor visualisation, drug reaction. It is not very useful if serum bilirubin is > 3 mg%.



Fig. 12.5: Cholecystocholangiogram. Note the dilated CBD, complete block in lower CBD, dilated biliary radicles.

ENDOSCOPIC RETROGRADE CHOLANGIO-PANCREATOGRAPHY (ERCP)

Through a side viewing gastroduodenoscope, sphincter of Oddi is cannulated, and dye is injected. Biliary and pancreatic trees are visualised. It is done under C-ARM guidance and sedation like midazolam or propofol anaesthesia. Patient is placed in prone position with the head turned towards right. After passing



Figs 12.6A to D

There is little if any restriction to respiratory movements of the abdominal wall in pleuropneumonia.

—C Allan Birch



Fig. 12.6E

Figs 12.6A to E: ERCP being done. Note the gastroduodenoscope with injection of dye. (A) Shows filling defect in the CBD. (B) Shows dilatation of biliary radicles. (C) Shows radiolucent stone (smooth filling defect) in distal CBD which can be removed through ERCP. Antibiotics should be given to prevent cholangitis.

gastroduodenoscope, sphincter is identified and cannulated. Under visualisation 3 ml of water soluble iodine contrast is injected into the bile duct and pancreatic duct. When cannula goes upwards beside vertebra, it signifies that it is in bile duct; and if cannula goes across the vertebra it is in pancreatic duct.

Indications

- Malignancy—irregular filling defect.
- Chronic pancreatitis—*'chain-of-lakes'* appearance.
- Congenital anomalies.
- Stones.
- Stricture of biliary tree.
- Choledochal cyst.
- For sampling of biliary and pancreatic juices for analysis and cytology.
- Brush biopsy from tumour site.

Therapeutic uses

- Extraction of stone from biliary duct
- Nasobiliary drainage
- Stenting of tumour in the CBD or in the pancreas
- Dilatation of the biliary stricture
- Endoscopic papillotomy

Complications

- Pancreatitis.
- Duodenal injury, perforation.
- Cholangitis.
- Bleeding from pancreaticoduodenal artery.
- Sphincter stenosis.

Relative Contraindications

- Acute pancreatitis.
- Previous gastrectomy.

PERCUTANEOUS TRANSHEPATIC CHOLANGIOGRAPHY (PTC)

- It is done in case of severe obstructive jaundice under cover of antibiotics and after control of any bleeding tendency—by giving injection vitamin K or FFP transfusion.

Indications

- Failure of ERCP
- High biliary strictures
- Klatskin tumour
- High blocks when external caternal catheter drainage is needed
- Stenting in high tumours

- With the help of fluoroscopy (C-ARM)/US/CT guided, *Chiba* or *Okuda needle* which is long, flexible, thin, blunt, without a bevelled end (15 cm long and 0.7 mm in diameter) is passed into the liver through right 8th intercostal space in midaxillary line. Once needle is in the dilated biliary radicle, bile is aspirated (sent for culture, cytology, analysis) and then water soluble iodine dye is injected into the same so as to visualise the dilated biliary radicles, also the site and extent of the obstruction, i.e. tumour, stricture.
- Procedure can be used for therapeutic stenting across the biliary tree through the obstruction either in the hepatic ducts or in the CBD into the duodenum.
- It is used whenever ERCP fails, in high strictures (in CHD), in Klatskin tumour, in catheter drainage (external) in high blocks, in stenting high tumours.

Prerequisites for PTC

- Should have normal prothrombin time (or should be made normal by injection vitamin K or FFP).
- Should be a last and final inevitable method for evaluation or therapy.
- Blood for transfusion in case of bleed, consent for intervention in need, antibiotic prophylaxis—are a must prior to PTC.

Note:

- Chiba is an university in Japan. Okuda is the name of person.
- **PTBD** is percutaneous transhepatic biliary drainage. It can be *external or internal*. It is done through PTC.

Complications

- Bleeding
- Biliary leak and biliary peritonitis
- Septicaemia

MAGNETIC RESONANCE CHOLANGIOPANCREATOGRAPHY (MRCP)

- It is a noncontrast noninvasive imaging method, better than ERCP as diagnostic tool in biliary and pancreatic diseases.

RADIOISOTOPE SCAN STUDY

- *I^{131} Rose Bengal and Tc^{99} labelled imino diacetic acid (HIDA, PIPIDA)* are very useful in diagnosing acute cholecystitis and other biliary disorders, like biliary atresia.

Note:

HIDA is Hippuran Immuno Diacetic Acid.

PEROPERATIVE CHOLANGIOGRAM

- It is done during CBD exploration for stricture, residual CBD stones, atresia, choledochal cyst, cholangitis.
- Fine polythene catheter is passed into the CBD through cystic duct and dye is injected. *Under C-ARM image-intensifier*, any block or stricture can be identified and completion of the procedure can be confirmed.



Fig. 12.7: Preoperative cholangiogram. Fine catheter is passed through cystic duct into the CBD. Care should be taken to avoid air getting into the CBD (it will mimic stone). Dye is injected under C-ARM guidance.

Complications

- Infection.
- Bile leak.

Precaution

Air should not be present in the syringe, as it may mimic stones.

POSTOPERATIVE T-TUBE CHOLANGIOGRAM

After choledochotomy, *Kehr's T-tube* is *placed in CBD for 14 days* and then water soluble dye is injected into the tube and X-ray is taken. Complete free flow of dye into the duodenum indicates that there is no blockage. T-tube can then be removed safely. Block indicates residual CBD stones.

Residual CBD stones are removed by:

- Dormia basket
- Fogarty's catheter
- Choledochoscope
- ERCP



Fig. 12.8: T-tube cholangiogram.

CONGENITAL ANOMALIES OF GALLBLADDER

- *Absence of gallbladder*—rare
- *Phrygian cap*—cap like projection and bend over the fundus of the gallbladder (*Phrygia* is an ancient Asian country—Mongolia) (Liberte cap of French revolution). It is identified in cholecystogram. It is 6% common
- *Double/triple gallbladder*—additional one may be intrahepatic. Cystic ducts may join to form a common cystic duct which joins the CBD or cystic duct of each gallbladder may join separately into the CBD
- *Mobile/floating/mesenteric gallbladder*—gallbladder has a long mesentery attached. It may cause torsion. It can cause recurrent abdominal pain. Its removal is easier through laparoscopic or open method
- *Long cystic duct* with low insertion of the cystic duct into CBD near the ampulla. This is important in all pancreatic/biliary/laparoscopic biliary surgeries
- *Absence of cystic duct* with gallbladder directly entering the CBD through a wide opening near infundibulum
- *Accessory cholecystohepatic duct* (*duct of Luschka*) may be present(10%) which if not identified and ligated during cholecystectomy will cause biliary fistula/ peritonitis due to continuous leak
- *Cystic artery may originate anteriorly* (15%) from right hepatic artery/from common hepatic artery
- Very tortuous hepatic artery in front of the origin of the cystic duct is called as *Moynihan's caterpillar hump*. It is important cause of bleeding in cholecystectomy
- There may be *double cystic duct* or cystic duct may insert high into the common hepatic duct or right hepatic duct

If vomiting or distinct nausea preceeds pain, the case is not one of appendicitis.— **John B Murphy**



Fig. 12.9: Cystic duct is absent with wide communication into CBD. There is higher chance of CBD injury here.



Fig. 12.12: Long cystic duct joining the CBD very low.



Fig. 12.10: Accessory cholecystohepatic duct (*Duct of Luschka*—10%). It may cause bile leak postoperatively if it is not ligated during cholecystectomy.



Fig. 12.13: Cystic duct joining the right hepatic duct—a variation.



Fig. 12.11: Double cystic ducts from the gallbladder joining the CBD.



Fig. 12.14: *Phrygian (cap) gallbladder.*



Fig. 12.15: Gallbladder diverticulum.



Figs 12.16A and B: Double gallbladder. One may be intrahepatic. It may have separate cystic ducts joining CBD or two cystic ducts join to form single duct to join the CBD.



Fig. 12.17: Cystic artery originates from right hepatic artery which is anterior to common bile duct.



Fig. 12.18: *Moynihan's caterpillar turn/hump* is bend of right hepatic artery in front of/close to cystic duct. It may get injured during cholecystectomy causing torrential haemorrhage.

CHOLEDOCHAL CYSTS

- It is defined as isolated/focal or combined/diffuse congenital dilatation of extra or intrahepatic biliary tree.
- It is congenital cyst with partial or complete weakness of the CBD biliary wall.
- It may be single/multiple or extrahepatic or intrahepatic.
- It is more common in Asia. It is common in Japan. Its incidence is 1 in 1000.
- It is often associated with pancreaticobiliary maljunction. There is long common channel more than 2 cm. It causes reflux of pancreatic juice into the bile duct, enzymatic destruction of the bile duct wall, ductal wall weakening and dilatation—*Babbit theory*.
- During embryogenesis there is abnormal early canalisation of bile duct with distal obstruction causing increased proximal pressure, weakening and ductal dilatation.
- Reduced postganglionic autonomous neurons in the distal portion of the cyst causing its poor function distally.

Gangrenous cholecystitis is associated with thrombosis of cystic artery.



Fig. 12.19: Pancreaticobiliary maljunction. Here pancreatic duct joins CBD more proximally than normal causing reflux of pancreatic enzymes into the CBD. It leads into weakening, dilatation and choledochal cyst.

- Chronic inflammation, sparse mucin glands and metaplasia are the histological features. Histologically it is either glandular with normal cuboidal epithelium with cavities in the mucosa. Or fibrotic type with fibrous cyst wall with thickened bile duct.

Types of Choledochal Cysts (Todani Modification of Alonso-Lej Classification)

- Type I: Dilatation of extrahepatic biliary tree (60%).
  - Type Ia—cystic.
  - Type Ib—focal segmental (saccular).
  - Type Ic—fusiform.
- Type II: Diverticulum of extrahepatic biliary tree (5%).
- Type III: Choledochocele—cystic dilatation of intraduodenal part of CBD (5%).
- Type IV: Dilatation of extra- and intrahepatic or multiple parts of extrahepatic biliary tree (30%).
  - Type IVa: Dilatation of extrahepatic and intrahepatic biliary tree. It is 2nd most common.
  - Type IVb: Dilatation of multiple sections of the extrahepatic bile duct.
- Type V: Dilatation of the only intrahepatic biliary tree (*Caroli's disease*).

Presentations

- Common in females 4:1. Common in Japan.
- Present in infants, children and even in adults.
- Obstructive jaundice (80%), pain in right hypochondrium, cholangitis.
- Mass per abdomen—mass is to the right and above the umbilicus, smooth, soft, not moving with respiration, not mobile and resonant (30%).
- Failure to thrive.

Triad of choledochal cyst (seen in 10% of cases)

- ❖ Right upper quadrant pain
- ❖ Jaundice
- ❖ Palpable abdominal mass



Fig. 12.20: Different types of choledochal cysts—(1) Fusiform type, (2) Saccular type, (3) Choledochocele, (4) Fusiform + Intrahepatic type, (5) Intrahepatic type.

Swellings which appear and disappear

- ❖ Hydronephrosis
- ❖ Intussusception
- ❖ Pseudo pancreatic cyst
- ❖ Choledochal cyst

Complications

- Pancreatitis, mainly in type III.
- Suppurative cholangitis.
- Gallstone and CBD stone formation.
- Biliary cirrhosis—secondary; portal hypertension.
- Rupture of cyst and peritonitis.
- Cholangiocarcinoma in CBD (30% of cases). Incidence of malignancy increases with age and is more common in type I and V. Reflux, stasis, super infection, pancreaticobiliary maljunction are the causes for malignant transformation. Malignancy can develop even in residual cyst or at anastomotic site.
- Malignancy is common in posterior wall.

Diagnosis

- U/S abdomen—unilocular cyst mainly in infants.
- CT scan—mainly to see intrahepatic biliary system.



Figs 12.21A and B: CT picture of choledochal cyst (*Courtesy:* Dr Yogish Kumar, MS, Professor, KMC, Mangalore).

- Hepatobiliary nuclide scanning.
- ERCP, Cholangiography—to see ductal anatomy.
- MRCP—to see status of pancreatic and biliary system and pancreaticobiliary maljunction.
- Liver function tests.
- PTC to see intrahepatic biliary tree.

Treatment

- *Resection of extrahepatic biliary tree* with removal of choledochal cyst along with cholecystectomy and Roux-en-Y hepaticojejunostomy is the ideal treatment for choledochal cyst especially types I, II and IVb.
- In Type I—excision of cyst with its mucosa and reconstruction by Roux-en-Y hepaticojejunostomy.
- In Type II—excision of the diverticulum and suturing of the CBD wall is done.
- In type III—endoscopic sphincterotomy is done. Excision is also often needed.
- Intrahepatic dilatation is difficult to treat. If it is localised, hepatectomy is sufficient, but if it is diffuse, liver transplantation may be required.
- In type IV if cyst is adherent to portal vein posteriorly, that part of the cyst wall over the portal vein is left behind. But mucosa of the part should be removed (*Lily's operation*).



Fig. 12.22: Choledochal cyst on table look.

- Cholecystectomy is a must in all these types. Incidence of gallbladder carcinoma is also high in these patients.
- If cyst has already turned into malignancy—adenocarcinoma, then radical surgery and chemotherapy is given.

CAROLI'S DISEASE

- It is congenital, nonfamilial, multiple, irregular, dilatations of the intrahepatic ducts with stenotic segments in between. It is associated with *congenital hepatic fibrosis* and *medullary sponge kidney.*
- It can also be included under type V choledochal cyst.

Investigations

- CT scan
- ERCP
- LFT
- MRCP

Complications

- Recurrent cholangitis.
- Stones in biliary tree.
- Portal hypertension.
- Cholangiocarcinoma (7%).

Treatment

1. Liver transplantation.
2. Hepatectomy.

BILIARY ATRESIA

- It may be either due to viral infection or defective embryogenesis resulting in fibrosis of extra- and intrahepatic biliary tree.

Porcelain gallbladder is radiopaque gallbladder, due to calcification of the gallbladder wall following chronic cholecystitis which has got high malignant potential.



Fig. 12.23: Types of biliary atresia.

- Incidence is 1 in 10,000.
- It is obstructive cholangiopathy with inflammation, destruction and obliteration predominantly involving the extrahepatic biliary tree. There is bile duct proliferation, cellular and canalicular bile stasis, bile plugs in portal tract bile system, periportal inflammation and fibrosis.

Aetiology of biliary atresia

- Infections—cytomegalovirus, reovirus, rotavirus and human papilloma virus
- Immune and autoimmune diseases
- Abnormal development of the biliary system
- Toxins
- Vascular defects of the hepatic artery

Classification

- *Correctable—10%.*
- *Noncorrectable—90%.*

Biliary atresia

- Type I: Atretic CBD—10%
- Type II: Atretic CBD and common hepatic duct
- Type III: Atretic CBD, common hepatic duct and right and left hepatic ducts—88%

Biliary atresia can be:

- *Perinatal acquired* (70%), not associated with congenital anomalies.
- *Fetal/embryonic* (30%) is associated with congenital anomalies.

It may be associated with other congenital anomalies (20%) of the GIT—(malrotation, annular pancreas duodenal atresia) and congenital heart diseases, polysplenia, situs inversus, absent vena cava, preduodenal portal vein.

Clinical Features

- Progressive jaundice in a newborn.
- Steatorrhoea (Pale stool is common).
- Hepatomegaly.
- Splenomegaly with portal hypertension.
- Osteomalacia.
- Biliary rickets.
- Severe pruritus.
- Clubbing, skin xanthomas.

Differential Diagnosis

- Neonatal hepatitis.
- Choledochal cyst.
- Cholestatic jaundice.
- Sclerosing cholangitis.
- Metabolic diseases.
- Storage disorders.
- Alagille syndrome—hypoplastic biliary ducts.

Diagnosis

- Liver function test—conjugated hyperbilirubinaemia.
- US abdomen shows triangular cord, tubular echogenisity extending above the bifurcation of the portal vein which is more than 4 mm thick—diagnostic.
- MRCP—100% accuracy.
- Radioisotope study (HIDA or PIPIDA scan).
- On table cholangiogram.
- Liver biopsy (Percutaneous)—is usually first test obtained.
- Rose Bengal I^{131} study, if shows < 10% secretion it is biliary atresia. If secretion is > 10% it is more likely to be hepatitis.

Treatment

- *In correctable cases*: Roux-en-Y jejunal anastomosis.
- In noncorrectable cases, hepaticoportojejunostomy (*Kasai's operation*).
- Liver transplantation is becoming more popular in biliary atresia—ideal.
- Presently *Kasai (1974) porto enterostomy* is done (in 8 weeks) as a preliminary procedure followed by liver transplantation eventually. After opening the abdomen, gallbladder is cannulated and on table cholangiogram is done to confirm atretic segment. Liver biopsy should also be done at the same time. If biliary patency is found procedure is abandoned. In atretic biliary tree, gallbladder is dissected off the liver and by applying traction to it, fibrotic atretic biliary tree is felt and dissected upto intrahepatic segment (upto the segmental branches of portal vein). Portal plate is anastomosed to Roux-en-Y part of the small bowel. Postoperatively, antibiotics, intravenous corticosteroids initially, later orally (for 6-12 weeks), ursodeoxycholic acid (for 1 year), nutrition, medium chain and essential fatty acids, essential elements supplementation is given. Success of

procedure depends on age of the patient; presence of cholangitis; ductule size (more than 200 µm is better); bridging fibrosis; type of atresia; bilirubin level. Eventually cholangitis, portal hypertension, variceal bleeding will develop.

GALLSTONES

> *Thus with stone obstruction of the common duct, dilatation of the gallbladder is rarely observed; the organ has already undergone contraction; with obstruction from other causes, dilatation is to be expected.*
>
> —**Ludwig Courvoisier,** 1890



Fig. 12.24: Multiple gallstones removed along with gallbladder.

Types

1. *Cholesterol stones* (Cholesterol solitaire—radiating crystalline appearance) are 6% common, often solitary.



Fig. 12.25A



Fig. 12.25B

Figs 12.25A and B: Multiple gallstones in a plain X-ray. Only 10% gallstones are radio-opaque. Often they are faceted because of compactness and equal pressure exerted by each stone. Centre of the gallstone is often found radiolucent and is called as *Mercedes Benz sign/Seagull sign*.



Fig. 12.26: Lateral X-ray of spine showing radio-opaque shadow in front of the vertebrae—could be radio-opaque gallstone. Note also the fused intervertebral disc spaces.

2. *Mixed stones* are 90% common. It contains cholesterol, calcium salts of phosphate carbonate, palmitate, proteins, and are multiple faceted.
3. *Pigment stones* are small, black or greenish black, multiple. Often they can be sludge like.

> *It frequently happens that gallstones are found in the gallbladder after death. Where there was not the least suspicion of existence during life.*
>
> — **Mathew Baillie**


Altered GB function
- Stasis
- Poor emptying
- Poor absorption
- Infection
Supersaturated bile
- Female
- Fertile
- Fat
- Forty
- High calorie
Gallstones
Spleen
Haemolytic diseases
Cholesterol nucleation factors
Altered enterohepatic circulation
- Ileal resection
- Ileal diseases
- Altered bowel transit time
- Altered bowel flora
- Cholestyramine
- Deoxycholate

Fig. 12.27: Diagram showing different causes of gallstone formation.



Fig. 12.28: Pigment stones showing faceted look.

Common in *"Fat, Fertile, Forty, Flatulent, Female"*. Common in western countries and in north India.

Pathogenesis

I. ***Metabolic:***

- Cholesterol is synthesised in liver. Its solubility is determined by relative concentration of cholesterol, bile salts and lecithin. Altered levels of cholesterol, lecithin, and bile salts in bile reduces the micelle concentration in the bile leading to precipitation of insoluble cholesterol, hence, the stone formation *(Lithogenic bile)*.
- Normal ratio of bile salt and lecithin to cholesterol is 25:1. Ratio below 13:1 leads to precipitation of cholesterol. Insoluble cholesterol is within the soluble micelle which is formed by lecithin and bile salts. If cholesterol component increases bile gets supersaturated and inadequate micelle makes insoluble cholesterol to undergo crystallisation and cholesterol monohydrate stone formation (*Admiron's triangular hypothesis*).
- Some cholesterol remains as bilayered lipid vesicles which are soluble. A specific heat labile glycoprotein in bile induces cholesterol monohydrate crystal formation in the vesicle and causes their aggregation. It is called as *nucleation*.
- Eventual precipitation and stone formation occurs by infection/infestation; pancreatic fluid reflux into CBD causing conversion of toxic lecithin to lysolecithin which is also toxic (causes supersaturated bile); bile stasis or altered enterohepatic circulation.
- Any condition which either increases the cholesterol secretion in the bile or reduces the bile salt concentration causes cholesterol stone formation. Old age; OCP; obesity; clofibrate may increase cholesterol secretion. Oestrogen, ileal resection and cholestyramine reduce the bile salt concentration.
- Chenodeoxycholic acid and ursodeoxycholic acid prevent cholesterol stone formation by maintaining bile acid pool; reducing cholesterol synthesis and secretion; converting supersaturated bile into normal bile.

Factors altering the cholesterol to bile salt ratio

- Obesity
- Drugs
  - Oral contraceptive pills
  - Clofibrate
  - Cholestyramine
- Ileal disease
- Ileal resection
- Altered enterohepatic circulation

II. ***Infections and Infestations:***
Bacteria like *E. coli, Salmonella*
Parasites like *Clonarchis sinensis* and *Ascaris lumbricoides* are often associated.
Moynihan's aphorism: "A gallstone is a tomb stone erected to the memory of the organism within it."

III. ***Bile stasis:*** Occurs due to estrogen therapy, pregnancy, vagotomy and in patients who are on long term intravenous fluids or TPN.

IV. ***Increased bilirubin production*** due to any of the causes of haemolysis as in hereditary spherocytosis, sickle cell anaemia, thalassaemia, malaria, cirrhosis. Here pigment stones are common.

Saint's triad

- Gallstones
- Diverticulosis of the colon
- Hiatus hernia

- Rarely centre of the stone contains radiolucent gas which is either triradiate (*Mercedes Benz sign*) or biradiate *(Seagull sign*).



Fig. 12.29: Ultrasound gallbladder showing echogenic lesion. US should be done with change of position to find out movement of the lesion with posterior acoustic shadow to say it as gallstone. Otherwise it will be gallbladder polyp or sludge ball.

- Sometimes gallbladder may be filled by 'toothpaste like' material which is a mixture of calcium carbonate and phosphate, which on plain X-ray looks like an opacified gallbladder, so called *as limey gallbladder.*
- Only 10% of gallstones are radio-opaque, 90% are radiolucent.



Fig. 12.30: Multiple gallstones collected during cholecystectomy.

***Note*:**

- Black pigment stones are common in gallbladder. It is usually calcium bilirubinate, calcium phosphate and bicarbonate stone with a matrix. It is common in haemolytic disorders. They are usually multiple, small black and hard in consistency. Mucin A and mucin C5 secreted by biliary glands may be the aetiology. Cholesterol component here is less than 30%. It is often seen in cirrhosis. They almost always form in gallbladder. They are common in Asia and Japan.
- Brown pigment stones are formed in biliary tree as primary biliary stones. It is commonly due to infection like *Escherichia coli* and bacteroides (98%) with bacterial nidus at the centre (often *Ascaris lumbricoides* or *Clonorchis sinensis* infestation or foreign body or stents). They secrete β glucuronidase to cause hydrolysis of soluble conjugated bilirubin to insoluble calcium bilirubinate. It also contains calcium palmitate, calcium stearate and cholesterol. They are brownish yellow, soft and mushy.



Fig. 12.31: Gallstones removed, on cutting showing central nidus.



Fig. 12.32: Thickened gallbladder due to chronic cholecystitis with single cholesterol stone.



Fig. 12.33: Gallbladder with stone removed from Hartmann's pouch.

Effects of the Gallstones

a. ***In the gallbladder***

i. Silent asymptomatic stones occurs in 10% of males and 20% of females.



Fig. 12.34A



Figs 12.34B to E

Figs 12.34A to E: Different types of gallstones. Note the faceted stones; black stones; brown stones; green stones. Thickening of gallbladder is seen. Hartmann's pouch is obvious in one of the photos (with cholesteroses).

ii. *Biliary colic with periodicity*, severe within hours after meal (commonest presentation). Biliary colic is spasmodic pain often severe, in right upper quadrant and epigastrium radiating to chest, upper back and shoulder. It is self-limiting, recurs unpredictably, often precipitated by a fatty/heavy meal. Fever and increased WBC count may be observed.



Figs 12.35A and B: Plain X-ray showing (A) Mercedes Benz sign, (B) Multiple faceted stones.

iii. Acute cholecystitis.
iv. Chronic cholecystitis.
v. Empyema gallbladder.
vi. Perforation causing biliary peritonitis or pericholecystitic abscess.
vii. Mucocele of gallbladder.
viii. Limey gallbladder.
ix. Carcinoma gallbladder.

b. ***In the CBD***

x. Secondary CBD stones (occurs in 10% of gallstones).
xi. Cholangitis.
xii. Pancreatitis.
xiii. *Mirizzi syndrome* (compression of CBD by stone from cystic duct or cholecysto-choledochal fistula).



Fig. 12.36: Diagram showing complications of gallstones.

c. ***In the intestine***

xiv. Cholecystoduodenal fistula causing *gallstone ileus* and so intestinal obstruction.

Flatulent Dyspepsia

- It is discomfort in the abdomen, belching, heartburn, fat intolerance, sensation of fullness in the abdomen usually observed in *fatty, fertile, flatulent female.*

Gallstone Colic

- It is sudden, severe colicky abdominal pain in right upper quadrant which radiates to back and shoulder. This pain is due to sudden spasm of gallbladder wall when gallstone moves towards the neck of the gallbladder or cystic duct and gets impacted. Tachycardia and restlessness are common. Right hypochondrium is tender.
- It is precipitated by supine position while sleeping at night. It lasts for few hours and is episodic. It may precipitate acute cholecystitis or empyema gallbladder.
- There is reflex pylorospasm causing vomiting.

Mirizzi Syndrome (Physician from Argentina, 1948)

- In Mirizzi syndrome, gallstone impacts in the gallbladder wall and compresses it causing pressure necrosis which further gets adherent to CBD wall. It eventually causes compression and later occasionally leads into cholecystocholedochal fistula. It occurs either from Hartmann's pouch into CBD (common) or from fundus of gallbladder into the CBD.
- Mirizzi syndrome is suspected on CT scan, but usually identified on table. It needs cholecystectomy; on table cholangiogram; and exploration of CBD. It often needs choledochojejunostomy.
- Partial cholecystectomy with primary closure of CBD is done with a T tube insertion through a separate choledochotomy in type 2.
- Partial cholecystectomy with closure of gallbladder flaps is done with T tube insertion through a separate choledochotomy in type 3.
- Partial cholecystectomy with duodenal/jejunal anastomosis is done in type 4 is done in few centres.
- Open approach is ideal for Mirizzi even though laparoscopic approach is done in few centres.

Mirizzi syndrome

Type I : Compression of CBD without lumen narrowing
Type II : Compression causing CBD lumen narrowing
Type III : Compression causing CBD wall necrosis.
Type IV : Cholecysto-choledochal fistula

Silent gallstone

- *Asymptomatic stone in the gallbladder*
- Usually it is cholesterol stone, often single
- It is accidentally discovered by U/S
- It need not be treated unless:
  - Patient is diabetic/immunosuppressed
  - High chances of developing gallbladder carcinoma
  - Stone more than 2.5 cm/multiple stones
  - If gallbladder wall is thickened
  - If there is high risk for carcinoma GB



Figs 12.37A and B: Mirizzi syndrome type II and IV.

Management of Gallstones

- U/S abdomen (gallstones are seen with posterior acoustic shadowing); plain X-ray abdomen; LFT; total WBC count.
- Laparoscopic cholecystectomy ideal.
- Open cholecystectomy is done through right subcostal Kocher's incision. Open approach is used if patient is not fit for laparoscopic surgery (anaesthesia); in suspected CBD stones; Mirizzi syndrome, suspected carcinoma gallbladder. During laparoscopic cholecystectomy, if there is on table difficulty in dissection at Calot's triangle, then conversion into open approach may be required.
- Dissolution therapy for asymptomatic cholesterol stones using ursodeoxycholic acid can be tried. It is not very successful.

Differential diagnosis of radio-opaque shadow in X-ray

- Kidney stone
- Gall stone
- Calcified 12th rib tip
- Phlebolith
- Pancreatic stone
- Radio-opaque foreign body
- Faecolith
- Calcified lymph node
- Calcified renal tuberculosis
- Renal cell carcinoma—calcifications
- Adrenal tumour—calcification
- Teratomatous dermoid
- Calcification of atheroma in aorta
- Calcified lesion in liver—amoebic liver abscess/calcified hydatid cyst

ACUTE CHOLECYSTITIS

- Commonly it occurs in a patient with pre-existing chronic cholecystitis but often also can occur as a first presentation.
- Usual cause is impacted gallstone in the Hartmann's pouch, obstructing cystic duct.

Causative bacteria are:

- *E. coli*—most common
- *Klebsiella, pseudomonas, proteus*
- *Strep. faecalis*
- *Salmonella*
- *Clostridium welchii*

Classification

1. Acute calculous cholecystitis.
2. Acute acalculous cholecystitis.

Mode of Infection

- Haematogenous through hepatic artery—cystic artery.
- Portal vein.
- Through bile after filtering in the liver via portal circulation.

Pathogenesis of Acute Cholecystitis

- Stone causes obstruction at Hartmann's pouch or in cystic duct. Obstruction causes stasis, oedema of the wall, bacterial infection, acute cholecystitis and its effects.
- Impacted stone also causes mucosal erosion allowing bile salts to act over the submucosal tissues as bile is toxic to these tissues. It leads into necrosis, further infection and often perforation of the gallbladder usually at Hartmann's pouch.

Pathology of Acute Cholecystitis

- Gallbladder will be distended with oedematous friable wall. Wall contains dilated vessels.
- Areas of necrosis and patchy gangrene may occur in severe cases.
- Mucosa shows ulceration and necrosis.
- Lumen contains infected fluid/infected bile or frank pus.
- Histology shows features of acute inflammation with neutrophils, oedema, and areas of necrosis and cell death.

Complications of Acute Cholecystitis

Acute cholecystitis can lead to:

1. *Perforation***,** which usually occurs in the fundus or in the neck (Hartmann's). It can cause cholecystoduodenal, cholecystointestinal or cholecystobiliary fistula.
2. *Peritonitis.*
3. Pericholecystitic abscess, empyema GB.

4. Cholangitis and septicaemia.
5. Empyema gallbladder, gangrenous gallbladder.

Emphysematous cholecystitis

- Seen in elderly male patients
- Common in diabetic and immunosuppressed individuals
- *Clostridium welchii* is the causative organism
- Gas is seen in the gallbladder
- Results in life-threatening septicaemia
- It causes severe fulminant cholecystitis
- Gangrene, perforation and peritonitis are common
- Emergency cholecystectomy is needed
- Absence of stones—observed in more than 50% of cases.



Fig. 12.38: On table look of gallbladder with acute cholecystitis.

Clinical Features

- Sudden onset of pain in the right hypochondrium, with tenderness, guarding, and rigidity.
- Palpable, tender, smooth, soft gallbladder.
- Area of hyperaesthesia between 9th and 11th ribs posteriorly on the right side (*Boas's sign)*.
- Jaundice may be present**.**
- Fever, nausea, palpable tender mass in GB region (25%).
- Tachycardia and toxic features.

Investigations

- Ultrasound abdomen—very useful, reveals presence or absence of gallstones; and thickening of gallbladder wall.
- Plain X-ray abdomen—10% of gallstones are radio-opaque; also rules out other causes of acute pain abdomen. Gas is seen in emphysematous GB.
- Total count shows neutrophilia.
- HIDA/PIPIDA radioisotope study—very useful. Non-visualisation of gallbladder is diagnostic.
- LFT is important. Increased serum bilirubin often signifies cholangitis or stone in the CBD.



Fig. 12.39: Ultrasound picture of visualisation of multiple gallstones.



Fig. 12.40: Ultrasound showing roundworm in gallbladder.



Fig. 12.41: CT scan showing stone in the neck of the gallbladder.

- Plain X-ray abdomen is not very relevant but is often important to rule out duodenal ulcer perforation, peritonitis. Only 10% of gallstones are radio-opaque. In emphysematous cholecystitis gas shadow may be seen in the region of gallbladder. Porcelain gallbladder may be seen as opacified area in gallbladder region.

Success is the ability to go from failure to failure without losing enthusiasm.

Differential diagnosis

- Duodenal ulcer perforation
- Acute pancreatitis
- Acute appendicitis
- Acute pyelonephritis
- Lobar pneumonia, myocardial infarction
- Ruptured ectopic pregnancy

Treatment

- Advised hospitalisation.
- Initially *(nonoperative) conservative treatment (95%)*:
    - Nasogastric aspiration.
    - IV fluids.
    - Analgesics and antispasmodics.
    - Broad spectrum antibiotics (cefoperazone, ceftazidime, ceftriaxone, cefotaxime + amikacin, tobramycin + metronidazole {antimicrobial}).
    - Observation.
    - Follow-up U/S scan.
- *Later after 3-6 weeks*, *elective cholecystectomy*, either by open method through right subcostal (Kocher's) incision or through laparoscopy is done.

Cholecystostomy is done immediately if patient is having:

1. Empyema gallbladder.
2. Persisting symptoms.
3. Progressing symptoms.

Here the gallbladder is opened and all stones and pus are removed. Either a Foley's or Malecot's catheter is placed in the gallbladder and is exteriorised.

After 3 weeks, elective cholecystectomy is done.

Indications for cholecystostomy or emergency cholecystectomy (5%)

- Empyema GB
- Persisting symptoms/failure of medication
- Emphysematous cholecystitis
- Perforation/peritonitis
- Elderly



Fig. 12.42: A Foley's or Malecot's catheter is placed in severely ill-patient with acute cholecystitis to drain pus initially, and later elective cholecystectomy is done. Procedure is done in elderly, severely ill, empyema GB, emphysematous GB, perforation of GB (cholecystostomy).

Note:

- Cholecystostomy is better option than *emergency cholecystectomy* as chances of injuring adjacent structures are higher in emergency cholecystectomy. Other option is *partial/subtotal cholecystectomy* with removal of part of GB distal to the Calot's triangle.
- There is a *changing trend* now towards *early cholecystectomy* in acute cholecystitis. Laparoscopic cholecystectomy can be done in 48-72 hours in these patients. But conversion chances are high—5-6 times more than usual. Complications also may be higher due to difficulty in dissecting the Calot's triangle. It can be done in good set up with surgeons having adequate experience.
- When patient's condition is deteriorating, and acute cholecystitis is progressing, suspicious about forming empyema or necrosis and perforation; surgery should be done by abandoning conservative treatment. Usually open surgery, either cholecystectomy (may be partial) or cholecystostomy is done.



Figs 12.43A and B: On table photo of distended gallbladder. Note the Calot's triangle, liver and CBD.

ACUTE ACALCULOUS CHOLECYSTITIS (5%)

- It is not an uncommon entity, but can be commonly missed.
- It is common in patients who have undergone major surgeries, trauma, burns, or any other stress or in cases of *cholecystoses*.



Fig. 12.44: Acalculous cholecystitis. Note the necrotic gallbladder wall.

- Common in ICU patients—in critically ill patients. It is due to bile stasis and ischaemia.
- Exact cause is not known. Gallbladder distension, release of activation factor VII may be the causes.
- Pathology is oedema and necrosis of the gallbladder wall with features of acute inflammation.
- Presentation is usually acute.
- *Investigations:* Isotope study (HIDA), U/S abdomen.
- Treatment: Cholecystectomy.

Percutaneous US guided/CT guided or open cholecystostomy initially, later cholecystectomy is the treatment of choice.

EMPYEMA GALLBLADDER

- It is a type of acute cholecystitis wherein the gallbladder is filled with pus. In 30% cases pus may be sterile.
- It also can occur in a pre-existing mucocele of the gallbladder where it gets infected.
- It is commonly observed in impacted stone, diabetic individual, immunosuppressed people like HIV, long time steroid therapy.
- It can perforate; can form abscess or can cause peritonitis—biliary and bacterial.
- Condition has got high mortality.

Clinical Features

- Fever, toxicity.
- Pain and tenderness in right hypochondrium.
- Tender, smooth, globular, gallbladder is palpable in right hypochondrium to the right of the right rectus muscle.



Fig. 12.45: Gallstone obstructing the neck of the gallbladder in Hartmann's pouch, may lead into empyema or mucocele of the GB.



Fig. 12.46: Empyema gallbladder. Note the pus and stone.

Complications

- Septicaemia.
- Rupture and peritonitis.

Investigations

- U/S abdomen.
- Total count is raised.
- Radioisotope scan.

Treatment

- Antibiotics: Cefotaxime, quinolones, ceftriaxone.
- Cholecystectomy—an emergency procedure.

- Often initially cholecystostomy is done, with either Foley's or Malecot's catheter kept *in situ.* Later after 3-6 weeks, cholecystectomy is done.



Fig. 12.47: Gangrenous gallbladder.

MUCOCELE OF THE GALLBLADDER

- It is due to obstruction of the cystic duct by a stone in the neck (Hartmann's pouch) of the gallbladder, without any infection or inflammation in the gallbladder. This causes absorption of all bile and secretion of mucous into the gallbladder allowing gallbladder to distend causing *mucocele* of the gallbladder (*Hydrops* of the gallbladder).
- Rarely cholangiocarcinoma occluding cystic duct may cause mucocele of gallbladder.
- Content is usually sterile.

Clinical Features

- Painless swelling in the right hypochondrium.
- Nontender, smooth, soft, globular, palpable gallbladder (content is sterile).
- Features of dyspepsia.



Fig. 12.48: Mucocele of gallbladder.

Complications

- If infected, can cause empyema gallbladder.
- Rupture can cause pseudomyxoma peritonei (but rare).

Investigations

- U/S abdomen.
- Liver function tests.

Treatment

Cholecystectomy, either laparoscopic or open method.

CHRONIC CHOLECYSTITIS

It is chronically inflamed, thickened gallbladder, which is nonfunctioning and nondistending.

Causes

- Gallstones.
- Cholecystoses.
- Chronic acalculous cholecystitis.

Organisms

- *Klebsiella.*
- *Streptococci.*
- *Salmonella.*

Pathology

- Gallbladder is shrunken, contracted, small, non-functioning and fibrotic with thickened gallbladder wall. Mucosa proliferates into the lumen creating deep clefts in the wall projecting into the muscular wall of the gallbladder being lined by epithelium. It is called as *Rokitansky-Ashchoff's sinuses.*
- Muscular wall is atrophied and is often replaced by fibrous tissue.
- Histologically it shows dense chronic inflammation with fibrous tissue.



Fig. 12.49: Specimen of gallbladder showing thickened gallbladder wall with multiple gallstones. Faceting of stones is due to equal pressure.

Clinical Features

- Pain in right hypochondrium, may be colicky, or persistent.
- Positive *Murphy's sign,* where in sitting position during deep inspiration, while palpating in right hypochondrium, patient winces with pain at the summit of the inspiration. Same sign elicited in lying down position is called as *Moynihan's sign*. It may also be elicited in acute—on chronic cholecystitis.
- Flatulent dyspepsia.
- Intolerance to fatty meals.
- Biliary dyspepsia.

Complications

- CBD stone.
- Cholangitis.
- Pancreatitis.
- Mirizzi's syndrome.

Differential Diagnosis

- Peptic ulcer.
- Pancreatitis.
- Hiatus hernia.

Investigations

- U/S abdomen may show stone with posterior acoustic shadowing. Gallbladder wall will be thickened.



Figs 12.50A and B: Thickened GB due to chronic cholecystitis with multiple stones.



Fig. 12.51: Thick GB with single large stone.

- Isotope study may help to confirm the infection.
- LFT.
- Total count may be raised if there is an acute recurrent infection.

Treatment

Cholecystectomy (Laparoscopic or open method).

CHOLECYSTOSES

- Cholecystoses are chronic inflammatory conditions of gallbladder with cholesterol deposits.
- It is due to defective transport of the absorbed cholesterol which accumulates in mucosa. There is also increased absorption of cholesterol by gallbladder epithelium.
- Cholecystoses gallbladder is more prone for infection.
- It may precipitate stone formation.
- It is a premalignant condition.

Types

I. Aggregations of cholesterol crystals in the mucosa or submucosa—*cholesterosis* (*Strawberry gallbladder*). Lipoid contents are present in large foamy cells which has phagocytosed cholesterol. Here cystic duct is normal. Disease occurs only in gallbladder. It is a premalignant condition.
II. Cholesterol laden polypoid projections in the mucosa—*cholesterol polyposis* (Gallbladder polyp).
III. Granulomatous thickening and hyperplasia of the gallbladder—*cholecystitis glandularis proliferans.*
IV. Diverticula formation in the wall of the gallbladder—*diverticulosis of gallbladder*.
V. Gallbladder wall fistula.

Clinical Features

- Features of acalculous cholecystitis like dyspepsia, positive Murphy's sign.

Typhoid Mary: *Salmonella typhi infection with chronic cholecystitis acting as a carrier.*
Mary was a cook who spread typhoid to many people.



Fig. 12.52: Types of cholecystoses. (I) Cholesterosis, (II) Cholesterol polyposis, (III) Cholecystitis glandularis proliferans, (IV) Diverticulosis of gallbladder, (V) Fistula.



Fig. 12.53: Cholesterosis of gallbladder. It is a premalignant condition.

Investigations

- U/S abdomen.
- OCG.
- Isotope study.

Treatment

Cholecystectomy—always should be done whether it is symptomatic or not as it is potentially malignant.

DISSOLUTION THERAPY FOR GALLSTONES

Indications

- Functioning gallbladder with cholesterol stone.
- Single stone less than 1.5 cm.
- Radiolucent stone.
- Old age.
- Patients who are not fit for surgery.

Contraindications

- Nonfunctioning gallbladder
- Stone more than 1.5 cm
- Radio-opaque stone
- Multiple stones

Drugs Used

- Chenodeoxycholic acid (for 2 years).
- Ursodeoxycholic acid (15 mg/kg/day).

They inhibit absorption of cholesterol from the gut and synthesis of cholesterol in the liver. They inhibit HMG CoA—a rate limiting step in cholesterol synthesis. Ursodeoxycholic acid also inhibits absorption of cholesterol in GIT.

Other methods used

- Citrate
- Monoterpenes
- Percutaneous infusion of methyl-tertiary butyl ether (MTBE) into the gallbladder using a catheter
- Extracorporeal shock wave lithotripsy (ESWL)—not popular

Problems with Dissolution Therapy

- Drugs should be given for a long time.
- Results are not good.
- Expensive.
- Causes side effects like diarrhoea, pruritus.
- Hepatic dysfunction.

Overall results are not good by dissolution therapy.

CHOLEDOCHOLITHIASIS

It is stones in the CBD and biliary tree.

Classification

i. Primary—Rare—brown pigment stones.
ii. Secondary—Common—black pigment stones/cholesterol stones. It is seen in 15% of gallstone disease; 75% are cholesterol stones, 15% are pigment stones.

Primary stones

They are formed in CBD and biliary tree itself, and are multiple, often sludge like, commonly pigment or mixed type, extends into hepatic ducts (Brown pigment stones).

Causes:

1. Defective pathophysiology of biliary tree causing stasis, biliary dyskinesia
2. Congenital conditions like Caroli's disease, choledochal cyst.
3. Infections and infestations like clonorchiasis, ascariasis.
4. Others: Low protein diet, malnutrition, obesity, females, old age.

Secondary biliary stones

- They are from gallbladder (gallstones) passes through cystic duct to CBD. Here CBD and biliary tree are otherwise normal.
- *Secondary stones are better and easier to manage than primary stones*.
- Commonly gallstones get impacted in supraduodenal portion of CBD.



Fig. 12.54: Multiple stones removed from common bile duct and hepatic ducts. They cause cholangitis. After stone removal patient needs choledochoduodenostomy/sphincteroplasty/choledochojejunostomy.

Note:

- Black pigment stones are common in—haemolytic diseases, cirrhosis, ileal resection, fasting for long time, TPN for long time (home TPN).
- Intrahepatic stones are common—biliary sepsis, biliary stasis, parasitic infection, malnutrition.
- Retained stones means—if stones are found in CBD within 2 years of cholecystectomy.
- Recurrent stones means—if stones are found in CBD 2 years after cholecystectomy.

Clinical Features

- Incidental CBD stones along with jaundice/without jaundice.
- Pain: It may be biliary colic; nonspecific abdominal pain; pain of ascending cholangitis, pain of pancreatitis.
- Jaundice—most common clinical manifestation.
- Fever with chills and rigors.

Charcot's triad of ascending cholangitis

- Intermittent pain (may be colicky)
- Intermittent fever
- Intermittent jaundice

Stone moves proximally and floats, obstruction is relieved and symptoms subside (**Intermittent features**).


Stone in CBD due to impaction
Causes obstruction
Stasis
Jaundice
Pain
Infection, bacteraemia and fever

- ***Reynold's pentad** of acute obstructive cholangitis (suppurative cholangitis).*

Sometimes obstruction persists causing

- Persistent pain
- Persistent fever
- Persistent jaundice
- Shock (toxicity) and
- Altered mental status

Here biliary tree contains pus.

- Pain and tenderness in epigastrium and right hypochondrium.
- Steatorrhoea and darkening of urine.
- Pruritus.

Complications

- Liver dysfunction and biliary cirrhosis.
- White bile formation and liver failure.
- Suppurative cholangitis.
- Liver abscess.
- Septicaemia.
- Pancreatitis if CBD stone is near sphincter of Oddi blocking drainage of bile and pancreatic duct.

Differential diagnosis

Obstructive jaundice due to other causes:

- Carcinoma of head of pancreas
- Carcinoma of periampullary region
- Carcinoma of biliary tree
- Biliary stricture
- Viral hepatitis

Investigations

- U/S abdomen; CBD diameter > 1 cm indicates biliary obstruction.
- ERCP, gold standard for diagnosis.
- MRCP.
- Liver function tests.
- Endoultrasonography is useful (*EUS*). It is more accurate.
- PTC if only indicated.

Treatment

- Injection Vit. K 10 mg IM once a day for 5 days or FFP infusion to correct the prothrombin time.

Commitment is what transforms a promise into reality.

- IV antibiotics (cefoperazone, cefotaxime).
- *Correction of dehydration*.
- IV Mannitol daily 200 ml BD to prevent *hepatorenal syndrome*.
- **ERCP—Therapeutic,** i.e. endoscopic papillotomy (sphincterotomy) and stone extraction through Dormia basket or balloon catheter; or fragmenting the stone and extraction; or removal through baby endoscope. CBD stent is placed *in situ*.



Fig. 12.55: Plain X-ray showing stents in CBD and pancreatic ducts. It was placed in a patient who presented with recurrent pancreatitis with block/stricture in both terminal CBD and pancreatic duct. Later patient underwent choledochojejunostomy and pancreaticojejunostomy.



Fig. 12.56: ERCP showing CBD stones. Endoscopic view of stenting is also seen.

Complications of sphincterotomy

- Bleeding
- Sepsis
- Perforation
- Pancreatitis

Once CBD stones are extracted through ERCP, laparoscopic cholecystectomy is done.

- In open cholecystectomy
  - After the removal of gallbladder, on table cholangiogram is done through cystic duct using water soluble iodine dye to see any stones in CBD. Using stay sutures choledochotomy is done (opened longitudinally) to remove stones in CBD.

Indications for choledochotomy

(After open cholecystectomy)

- U/S shows stone in CBD
- Palpable stone in CBD
- CBD diameter >10 mm
- Recent history of jaundice, and with raised serum alkaline phosphatase level
- On table cholangiogram shows stone (done using C-arm image machine)
- Failure of stone extraction by ERCP prior to cholecystectomy.
- When in doubt



Fig. 12.57: Placing T-tube in CBD after choledocholithotomy. It is kept for 10-14 days.



Fig. 12.58: Diagram showing placement of T-tube in CBD after choledocholithotomy. Note the separate drain placed in the cholecystectomy bed to drain fluid, blood, bile.

- After choledochotomy, stones are removed using Des jardin's choledocholithotomy forceps. Bake's CBD dilator is used to confirm the CBD patency.
- T-tube (Kehr's) is then placed in the CBD and kept for 14 days.
- After 14 days a postoperative T-tube cholangiogram is done to see for free flow of dye into the duodenum, so that T-tube can be removed.
- If T-tube cholangiogram shows persistent stone, it can be extracted after 6 weeks, through a basket (Dormia) or catheter (Fogarty) through the track or through a choledochoscope. Retained stones can also be removed through ERCP.



Fig. 12.59: T-tube cholangiogram showing retained stone in the CBD (*Courtesy:* Dr Navin Chandra Shetty, HOD, Department of Radiodiagnosis, KMC, Mangalore).

- After open cholecystectomy, on table ERCP can be tried if there are indications for CBD intervention case of secondary CBD stone/s and if ERCP was not done prior to cholecystectomy. If secondary stone is retrieved by this method, open exploration of CBD can be avoided.
- Laparoscopic CBD exploration is becoming popular with availability of expertise and high technology imaging and instruments.

Methods to confirm the removal of T-tube

- Clamp the T-tube, after 10-14 days and observe 48 hours for development of pain, jaundice and fever
- Confirm free flow of dye in T-tube cholangiogram

Management of retained CBD stones

- Small stones may *spontaneously* pass down.
- Heparinised saline or bile acid *flushing* through the T-tube. (Wash 250 ml of normal saline with 25,000 IV heparin for 5 days)
- Burhenne technique (Canada)—after 6 weeks once T-tube track gets matured, track if needed is dilated using graduated dilators. Either using Dormia basket or Fogarty catheter or choledochoscope, stone is removed through T-tube track under fluoroscopic guidance (C-ARM)
- *ERCP* and stone removal in 3 weeks
- *Reoperation* if everything fails, either transduodenal sphincteroplasty or choledochojejunostomy
- ESWL with endoscopic sphincterotomy/extraction/lavage/stenting
- Through percutaneous transhepatic route, cholangioscope is passed and CBD is visualised, stone is identified and removed using Dormia basket or Fogarty catheter
- Laparoscopic choledocholithotomy
- Open choledocholithotomy often with choledochojejunostomy

Treatment of Primary CBD Stones

- *Difficult and is associated with more complications.*



Fig. 12.60: T-tube cholangiogram showing dye in the duodenum and visualisation of normal biliary tree without any obstruction.

Preferred procedures:

- *Transduodenal sphincteroplasty (open method),* or
- *Open choledochoduodenostomy,* side-to-side, or
- *Open choledochojejunostomy*—Roux-en-Y method.
  - These procedures attain complete drainage of bile.
  - Postoperatively they may often require long-term antibiotics.

Indications for choledochoduodenostomy/choledochojejunostomy:

- Multiple CBD calculi with distal narrowing (*Funnel syndrome*).
- Papillary stenosis.
- Impacted calculi.
- Biliary sludge—symptomatic.
- Residual stones.

Prerequisite for choledochoduodenostomy:

- CBD should be more than 1.4 cm and stoma should be 2 cm.

Advantages of choledochoduodenostomy are:

- Bile leak is minimal/not there.
- Beneficial as a permanent remedy in multiple stones/sludge/stenosis/strictures/intrahepatic stones.

Problem with choledochoduodenostomy:

- Sump syndrome.

Note:

Roux-en-Y choledochojejunostomy is equally good as choledochoduodenostomy.

You are the sole master of your thought processes.

Remember

- Gallstones are commonly radiolucent (90%).
- Multiple stones are usually faceted because of exertion of equal pressure in a compact gallbladder.
- Plain X-ray shows radio-opaque lesion to the right side of the vertebra below rib cage. It should be differentiated from kidney stones. In lateral view X-ray, gallstone will be in front of the vertebra whereas kidney stone overlaps the vertebra. Often gallstone has got central radiolucent area—*sea gull sign/Mercedes Benz sign.*
- *Silent/asymptomatic gallstone* is one which is identified on routine investigation where there are no specific relevant symptoms related to gallstones. Chances of developing symptoms in a silent gallstone is 5% in 5 years and 20% in 15 years.
- Presently ultrasound is ideal investigation for gallstones.
- To see gallbladder function or confirm cholecystitis radioisotope HIDA/PIPIDA scan is ideal.
- Cholecystitis can cause jaundice due to cholangitis. But other causes of jaundice should be ruled out—CBD stones/ Mirizzi syndrome.
- *Limey gallbladder* is gallbladder filled with toothpaste like mixture of calcium carbonate and calcium phosphate. Plain X-ray shows dense radio-opaque gallbladder shadow (*opacified gallbladder*).
- *Porcelain gallbladder* is one where gallbladder wall is calcified because of chronic cholecystitis. It is potentially malignant. It should be removed either by open or laparoscopic method.
- Cholesterol stone occurs when there is alteration in levels of cholesterol, lecithin and bile salts. This altered bile has got more cholesterol than adequate micelle and is called as *lithogenic bile*. Here bile is in supramicellar zone. Cholesterol stone is radiolucent but causes acoustic shadow in U/S
- Mixed stones are most common—90%.
- '*Gallstone is a tomb stone erected to the memory of the organism within it*'—Moynihan's aphorism.
- *Saint's triad*: Gallstones—colonic diverticulosis—hiatus hernia.
- *Complications of gallstones*: Acute cholecystitis, chronic cholecystitis, empyema gallbladder, mucocele of gallbladder, perforation and peritonitis, secondary CBD stones, cholangitis, pancreatitis, Mirizzi syndrome, gallstone ileus, pericholecystic abscess and carcinoma of gallbladder.
- Black pigment stones are more common in gallbladder; brown pigment stones are common in CBD.
- Cholesterol stones are common in Western countries; pigment/mixed stones are common in Asian countries.
- *Acute acalculous cholecystitis* is 5% common. It occurs after stress, major surgeries or in cholecystoses.
- *Xanthogranulomatous cholecystitis* is a rare pathological condition. Gallbladder is thickened with chronic inflammation. It is yellow xathogranulomatous in nature. It often extends to adjacent organs. It is due to reaction to penetrated bile.
- *Residual/retained bile duct stones* are one which is present in CBD within 2 years of initial surgery—cholecystectomy. They are usually missed secondary bile duct stones.
- *Recurrent bile duct stones* are one which is present 2 years after the initial surgery—cholecystectomy and CBD exploration. They are primary biliary stones.
- *Salmonella cholecystitis* (Typhoid Mary—a cook in New York transmitted typhoid through her infected faeces and urine) causes typhoid gallbladder. It can cause acute or chronic cholecystitis. Salmonella itself may predispose stone formation. Patient may be silent typhoid carrier.

SUMP SYNDROME

It is commonly observed after choledochoduodenostomy rarely after choledochojejunostomy. CBD distal to the choledochoduodenostomy acts as a reservoir with stasis of food particles, bile, stones and sludge. Often it causes cholangitis and narrowing of the stoma of choledochoduodenostomy. Conversion to end-to-end Roux-en-Y choledochojejunostomy is required.



Fig. 12.61: Technique of choledochoduodenostomy for CBD stones. Note the site of possible occurrence of *sump syndrome*.

COURVOISIER'S LAW

- **'In a patient with jaundice if there is palpable gallbladder, it is not due to stones'**.



Fig. 12.62: Courvoisier's law—"In a patient with jaundice if there is palpable gallbladder it is not due to stones". In stone disease gallbladder is contracted and fibrotic and so nondistensible.

- In obstruction due to CBD stone, gallbladder does not distend because it is chronically inflamed, thickened, fibrotic, contracted and nondistensible.
- In malignancy, like carcinoma of head of the pancreas or periampullary carcinoma, gallbladder will be distended and palpable to the right of rectus muscle in the right hypochondrium, as nontender, globular, smooth, soft, dull mass which moves with respiration and with horizontal mobility.

Rule may not be useful in:
- Absence of gallbladder
- Intrahepatic gallbladder
- Previous cholecystectomy

Exceptions to the rule are:
- Double impacted stone—one in CBD and one in cystic duct, with mucocele of gallbladder.
- Large stone in Hartmann's pouch.
- Empyema gallbladder with CBD stone.

SURGICAL JAUNDICE (Obstructive Jaundice)

Definition

It is the jaundice that develops due to biliary obstruction, partial or complete or intermittent. It causes conjugated hyperbilirubinaemia. Normal serum bilirubin level is 0.2-0.8 mg%. Scleral icterus is visible when serum bilirubin level exceeds 2.5 mg%.

Effects of Obstructive Jaundice

- *In liver*: Enlarged green bile stained liver (*hydrohepatosis*) shows dilated intrahepatic biliary radicles. Once intraductal CBD pressure increases bile secretion from liver is reduced causing formation of 'white bile' in CBD. Biliary cirrhosis may develop later.
- *In the biliary tree*: Recurrent inflammation—cholangitis—fibrosis can occur.
- *In bowel*: Absence of bile from bowel impairs digestion, reduces fat absorption making faeces bulky and fatty. Vitamin K absorption is reduced causing fall in prothrombin level raising PT-INR.
- *Retention of bile salts and bile pigments* in blood and body fluids occurs.
- *Altered coagulation profile; hepatorenal syndrome and renal failure; sepsis.*

Causes

1. Biliary atresia.
2. Choledochal cyst.
3. CBD stones.
4. Ascending cholangitis.
5. Biliary strictures.
6. Sclerosing cholangitis.
7. Carcinoma of head and periampullary region of the pancreas.
8. Cholangiocarcinoma.



Fig. 12.63: Different causes of obstructive jaundice (surgical jaundice).

9. *Klatskin tumour* (Carcinoma at the confluence of hepatic ducts above the level of the cystic duct and so will cause hydrohepatosis without GB enlargement).



Fig. 12.64: CT scan showing hydrohepatosis due to obstruction below, in a patient with obstructive jaundice.

10. Extrinsic compression of CBD by lymph nodes or tumours.
11. Parasitic infestations.

Clinical Features

- Severe jaundice.
- Pruritus, more on the back and forearms.
- Fever, may or may not be present.
- Loss of weight.
- Loss of appetite.
- Pain in right hypochondrium, *palpable gallbladder*, hydrohepatotic palpable, smooth, soft, nontender liver are other features.
- Courvoisier's law may suggest inflammatory/neoplastic cause.
- Charcot's triad/Reynold's pentad as presentation in cholangitis.
- Steatorrhoea (more fatty stool) due to improper absorption of fat soluble vitamins.

Accountable, dependable, reliable are qualities that make a person responsible.



Fig. 12.65: Sclera of the patient with obstructive jaundice is greenish yellow in colour.

Classification of Causes of Obstructive Jaundice

1. *Congenital*: Biliary atresia, choledochal cyst.
2. *Inflammatory*: Ascending cholangitis, sclerosing cholangitis.
3. *Obstructive:* CBD stones, biliary stricture, parasitic infestation.
4. *Neoplastic*: Carcinoma of head or periampullary region of pancreas, cholangiocarcinomas, Klatskin tumour.
5. *Extrinsic compression* of CBD by lymph nodes or tumours.

Benjamin's (1983) classification of biliary obstruction

Type 1: Complete obstruction

- Tumours—pancreatic, cholangiocarcinoma
- CBD ligation—iatrogenic
- Primary/secondary liver tumours

Type 2: Intermittent obstruction

- Choledocholithiasis
- Periampullary tumour
- Choledochal cyst
- Bile duct papilloma
- Hemobilia
- Duodenal diverticula

Type 3: Chronic complete obstruction

- Bile duct stricture
- Congenital
- Traumatic
- Post-radiotherapy
- Chronic pancreatitis
- Cystic fibrosis

Type 4: Segmental obstruction

- Traumatic
- Sclerosing cholangitis
- Cholangiocarcinoma, intrahepatic biliary stones (hepatolithiasis)

Investigations for Obstructive Jaundice

- Serum bilirubin. Normal value is less than 1.0 mg%. Both direct and indirect bilirubin are assessed. Direct is increased in obstructive jaundice, i.e. conjugated hyperbilirubinaemia. van den Bergh's test is done.
- Serum albumin, globulin and A : G ratio. Normal S. albumin is more than 3.5 gm%.
- Prothrombin time. Normal value is 12-16 seconds. It is significant if it is more than 4 from the control or more than one and half times the control. It is corrected by injection vitamin K, 10 mg IM OD for 5 days or by FFP—5-10 units.
- Serum alkaline phosphatase, SGPT, SGOT, 5' nucleotidase.
- Total count may be raised with neutrophilia in inflammatory conditions.
- U/S abdomen.
- ERCP to visualise the site of obstruction, brush biopsy, bile sample for analysis.
- PTC to decompress, assess proximal dilated obstructed biliary system if ERCP fails; dine polythene catheter can be kept *in situ* to have biliary drainage; PTC—stenting across the obstruction can be done under image (C arm) guidance.
- MRCP—Noninvasive diagnostic tool. It shows 96% sensitivity; 99% specificity.
- CT scan in case of tumours to assess operability.
- *Tumour markers*: CA 19/9 is useful for carcinoma pancreas (more than 70 units/L) with 70% sensitivity and 90% specificity. But it may also increase in other causes of biliary obstruction and cystadenoma.
- *Endoscopic US (EUS)*: It is done through endoscope. It is more accurate in assessing pancreatic mass, staging of the disease, to identify involvement of portal venous system, CBD stones. It is also useful in EUS guided FNAC, celiac axis neurolysis, EUS guided immunotherapy.
- *Intraductal US (IDUS):* It is very useful in assessing tumour stage, tumour margin in bile duct cancer. It is also used in assessing pancreatic duct to differentiate pancreatic cancer and chronic pancreatitis.
- *CT / MR angiogram or venogram* to assess vascularity and portal venous system in malignancy.
- Urine tests: Fouchet's test for bile pigments, Hay's test for bile salts and test for urobilinogen in urine.

Fouchet's test: 10 ml of urine + 5 ml of $BaCl_2$ + pinch of $MgSO_4$ causes formation of $BaSO_4$ which is filtered over a filter paper and few drops of Fouchet's reagent is added. Green or blue colour signifies presence of bile pigments in the urine.

Hay's test for bile salt: Sprinkle sulphur to 2 ml of urine. In presence of bile salts sulphur sinks to the bottom.

Ehrlich's test: 5 ml of freshly voided urine + 1 ml of Ehrlich reagent (p-dimethyl amino benzaldehyde) and wait for 5 minutes. Formation of red colour signifies presence of urobilinogen in urine. Normally it is present in traces, in obstructive jaundice it is absent and in haemolytic jaundice it is in excess.

Preoperative preparation of patient with obstructive jaundice

- Proper diagnosis and assessment
- Injection vitamin K IM 10 mg for 5 days
- Fresh Frozen plasma—often requires 6 bottles or more
- *Adequate hydration* is most important 5/10% dextrose
- Blood transfusion in case of anaemia
- Oral neomycin, lactulose
- Mannitol 100-200 ml BD IV to prevent hepatorenal syndrome

- Repeated monitoring by doing prothrombin time, electrolytes
- Antibiotics like third generation cephalosporins.
- Calcium supplements as calcium chloride IV
- *Preoperative decompression* is indicated if bilirubin is > 12 mg%, sepsis, hepatorenal syndrome, severe malnutrition or cardiopulmonary disease.
- Correction of coagulopathy, prevention of renal failure, infection, hepatic encephalopathy and electrolyte imbalance (correction of hypoglycaemia and dilutional hyponatraemia due to water retention; avoiding isotonic saline infusion).

Treatment of Obstructive Jaundice

- CBD stones—ERCP stone removal, choledocholithotomy, transduodenal sphincteroplasty, choledochojejunostomy or choledochoduodenostomy.
- Carcinoma periampullary or head of pancreas—Whipple's operation or triple bypass or ERCP stenting.
- Biliary stricture—Stenting, choledochojejunostomy, Roux-en-Y hepaticojejunostomy.
- Klatskin tumour—Radical resection or palliative stenting.
- Biliary atresia—Kasai's operation or liver transplantation.
- Choledochal cyst—Excision, hepaticojejunostomy, mucosal resection.
- *Management of pruritus:* Pruritus may be due to retention of bile salts which activates the release of histamine in skin, central mechanism or by release of endogenous opioids. It is often difficult to treat. Once cause is treated and obstruction is relieved, pruritus will regress. Drugs and therapies used are—cholestyramine (ion exchange resin binds bile salts in intestine inhibiting their absorption), rifampin, ondansetron, gabapentin, sertratine, ursodeoxycholic acid, antioxidants, phototherapy, plasmapheresis.

Postoperative Management

- Monitoring with prothrombin time, bilirubin, albumin, creatinine, electrolyte estimation.
- FFP or blood transfusion.
- Antibiotics.
- Observation for septicaemia, haemorrhage, pneumonia, pleural effusion, bile leak.
- Care of T-tube and drains.
- T-tube cholangiogram in 10-14 days.
- TPN, CVP line, nasogastric tube, urinary catheter.

CBD STRICTURES (BILIARY STRICTURES)

Causes

1. *Postoperative (80% common)*
    - After cholecystectomy [open or laparoscopic, more common following laparoscopic (0.8%) than open method (0.35%)].
    - Biliary surgery.
    - Gastrectomy.
    - Liver surgery.
    - Duodenal and pancreatic surgery.



Fig. 12.66: ERCP picture showing stricture and passing stent into CBD.

2. *Inflammatory:* Stricture following recurrent attacks of cholangitis due to:
    - CBD stones.
    - Parasites—*Ascaris lumbricoids, Clonorchis sinensis.*
    - Primary sclerosing cholangitis.
3. *Malignant:* Due to cholangiocarcinoma.
4. *Traumatic.*

Bismuth classification of biliary stricture

I. Low CBD stricture with stump (proximal to stricture) > 2 cm
II. Middle CBD stricture with proximal stump < 2 cm
III. Hilar. Confluence of right and left hepatic ducts is intact
IV. Separated right and left hepatic ducts
V. Stricture involving intrahepatic ducts

Clinical Features

- Obstructive jaundice.
- Pain abdomen.
- Features of ascending cholangitis.
- Profuse persistent bile leak.

Causes of postoperative stricture

- Too much traction to the GB during ' Fundus first cholecystectomy'
- Blind application of artery forceps in Calot's to control bleeding
- Anomalies of biliary tree
- Inflammatory adhesions at Calot's triangle
- Injury during other surgery like gastrectomy

Note:

Hogarth Pringle's manoeuvre is ideal to control bleeding on table by applying pressure using thumb and fingers over the Foramen Winslow.

The mother's heart is child's schoolroom.—**Henry Ward Beecher.**


Proximal
stump > 2 cm
Stricture
Type I
A
Proximal
stump < 2 cm
Stricture
Type II
B
Stricture at confluence
of RHD and LHD
Type III
C
Stricture
Right and left
duct separated
Type IV
D
Stricture
Intrahepatic
ducts
Type V
E

Figs 12.67A to E: Bismuth classification of stricture CBD.



Figs 12.68A and B: CBD stent and imaging after placement.

Investigations

- U/S abdomen.
- Liver function tests.
- ERCP.
- On table cholangiography.
- MRCP.

Treatment

- ERCP stenting.
- Choledochoduodenostomy or jejunostomy.
- Roux-en-Y hepaticojejunostomy—ideal.

SCLEROSING CHOLANGITIS

- It is fibrous thickening of the CBD and biliary ductular wall, associated with multiple strictures with dilatation in between the strictures. Both extra- and intrahepatic ducts are involved.
- They have increased risk of developing cholangiocarcinoma.

Types

1. *Primary* sclerosing cholangitis is one wherein no cause is found and is associated with ulcerative colitis, Sjogren's syndrome, Crohn's disease, Grave's disease. It eventually leads to biliary cirrhosis. *Primary sclerosing cholangitis* (PSC) is an idiopathic, progressive, chronic, cholestatic pathology with diffuse inflammation, sclerosis, and obliteration of intra- and extrahepatic biliary systems. There will be multiple areas of strictures and dilatations (1%/year). It has high risk for cholangiocarcinoma. It could be an autoimmune disease. It is common in HLA/B8/DR3 halotype.
2. *Secondary* sclerosing cholangitis is due to stones, trauma, congenital lesions. AIDS, chemotherapy (5FU), transplantation, collagen diseases, sarcoidosis, histiocytosis.

Features

- Common in young men (70%).
- Intermittent jaundice.
- Abnormal liver functions.
- Weight loss, pain, fever, pruritus.
- Features of ulcerative colitis in case of PSC (70%).
- PSC may be associated with retroperitoneal fibrosis, mediastinal fibrosis, Riedel's thyroiditis, orbital pseudotumour.
- *Hepatic duct confluence* is most severely strictured segment in PSC.

Investigation

- ERCP shows *beaded appearance* of biliary tree.
- LFT is altered.
- Liver biopsy is needed to identify the severity of hepatic fibrosis.

Treatment

- Stenting.
- T-tube drainage.
- Large dose steroids.
- Immunosuppression therapy—methotrexate, azathioprine, tacrolimus, cyclosporine.
- Ursodeoxycholic acid is beneficial.
- Liver transplantation.
- *Median survival in PSC* after diagnosis is 10 years.

GALLBLADDER POLYP

- Its incidence is 5% in routine US abdomen; 10% in cholecystectomy tissue specimen.
- It is usually less than 10 mm in size, pedunculated appearance.
- Sessile polyps are often more than 10 mm in size.
- 30% are multiple.
- Gallbladder polyp more than 10 mm in size, associated with gallstones, age above 60 years, symptomatic, sessile polyp and multiple polyps—are indications for surgical intervention.
- CT scan should be done if malignancy is suspected on US.
- It is treated by laparoscopic cholecystectomy. Histology is a must to confirm benign nature and to rule out carcinoma.

BENIGN BILIARY PAPILLOMA

- It is the most common benign biliary tumour.
- 50% occurs close to ampulla presenting as obstructive jaundice.
- Benign adenoma (soft), benign inflammatory pseudotumour and cholangiocarcinoma—are differential diagnosis.
- ERCP, CT scan, EUS, LFT—are the investigations.
- Treatment—papillotomy, wide local excision.

CARCINOMA GALLBLADDER

- It is more common in *India (Patna)* and Asian countries. It is also common in Chile.
- It is common in *females* and elderly. Male : Female :: 1 : 3.

Aetiologies for Carcinoma of Gallbladder

- 3% of gallstones with cholecystitis will develop carcinoma of gallbladder.
- 90% of carcinoma of gallbladder is associated with gallstones. Risk of developing carcinoma in gallstone disease is 7-10 times more than general population. Relative risk is less if stone size is less than 2 cm; if stone size is 2-3 cm in size it is 2.5; it is 10 or more if stone size is more than 3 cm.
- Choledochal cyst, anomalous pancreaticobiliary duct junction (20%), cholesteroses of gallbladder, gallbladder polyp more than 1 cm in size or more than 3 in number or adenomatous polyp, PSC.

You are the sole master of your thought processes.

- Chronic typhoid carriers, carcinogens, inflammatory bowel disease, hepatitis B and hepatitis C virus infection.
- Porcelain gallbladder is more prone for malignant transformation (25%) and 90% of them are inoperable tumours.
- Nitrosamines.

Gross Types of Carcinoma Gallbladder

- Polypoid/papillary—better prognosis.
- Scirrhous/nodular.
- Proliferative/infiltrative.

Microscopy

- Commonly it is adenocarcinoma (90%); occasionally squamous cell carcinoma, adenosquamous or carcinoid tumour can occur.
- 25% show only localised disease; 35% have lymph node spread; 40% have distant spread at the time of first diagnosis.
- It is very *aggressive* tumour.

Spread of Carcinoma Gallbladder

- Direct spread to liver (segment IV and V), bile duct, duodenum, colon and kidney.
- Lymphatic—lymph node of Lund, periportal nodes, peripancreatic and periduodenal nodes.
- Blood spread—to liver, lungs and bones.
- Perineural spread is also known to occur.

Staging of carcinoma gallbladder

Nevin's staging:
Stage I – Intramural
Stage II – Spread to muscularis propria
Stage III – Spread to serosa
Stage IV – Spread to cystic lymph node of Lund
Stage V – Direct spread to adjacent organs/metastases

TNM staging

Tumour	***Nodal spread***
Tis – Carcinoma *in situ*	N0 – No nodes
T1 – Spread to mucosa or muscle layer	N1 – Spread to cystic/ nodes in porta/hepatoduodenal ligament N2 – Spread to peripancreatic/celiac/periduodenal/superior mesenteric nodes
T1a – Only mucosal involvement	
T1b – Spread to muscle layer T2 – Spread to subserosa but not beyond serosa	
T3 – Spread beyond serosa or one adjacent organ or < 2 cm to liver	*Metastases*: M0 – No distant spread M1 – Presence of distant spread
T4 – Spread > 2 cm to liver, 2 or more adjacent organs—CBD, stomach, duodenum, colon, omentum	



Figs 12.69A to C: Specimen of gallbladder after extended cholecystectomy. Note the liver margin cleared of carcinoma, stone in the gallbladder and lymph nodes cleared.

Features of Carcinoma of Gallbladder

- Pain in right hypochondrium, mass in right upper abdomen which is hard and nontender.
- Jaundice is common.
- Significant weight loss in short duration.
- Acute presentation of cholecystitis.
- Palpable nodular liver secondaries, ascites.
- It is common in places where there is more prevalence of gallstone disease—Patna, Bihar
- It is common in females.
- Incidentally confirmed as carcinoma gallbladder histologically after cholecystectomy for chronic cholecystitis.

Investigations

- Ultrasound abdomen.
- CT abdomen to see operability.
- U/S guided FNAC.
- Liver function tests.
- MRCP.
- Laparoscopy.
- CA 19-9 is elevated in 80% of cases.

Treatment

- Cholecystectomy with resection of liver segments IV and V—*extended cholecystectomy with perihepatic nodal clearance*. At least 2 cm margin in the liver from the gallbladder bed should be cleared. All pericholedochal lymph nodes should be removed. Frozen section biopsy from cystic duct stump should be done to identify for the existence of microscopic tumour. If present, CBD resection and hepaticojejunostomy is done. *Open approach* rather than laparoscopic is ideal for carcinoma gallbladder.
- Hemihepatectomy with cholecystectomy with nodal clearance.



Fig. 12.70: Extended cholecystectomy technique.

- If patient has undergone laparoscopic cholecystectomy and histology confirmed carcinoma, then staging should be done. All port areas should be reexcised to prevent *port site recurrence*. Often extended resection of segment IV and lymph nodes may be needed. Spillage of bile during laparoscopic cholecystectomy is common (30% in nonmalignant GB, 50% in carcinoma GB).
- Chemotherapy either systemic or intraarterial, and adjuvant radiotherapy but with poor success rate.

Prognosis

- Overall prognosis for carcinoma gallbladder is poor due to early spread and aggressive nature of the tumour.
- 5-year survival is only 5%. Muscle invasion, nodal and distant spread carry poor prognosis. In stage T_1 simple and extended cholecystectomy will not make difference in prognosis. In T_2 stage extended cholecystectomy is very much beneficial which gives 60% 5-year survival rate. T_3 and T_4 carry poor prognosis.



Fig. 12.71: Gallbladder showing proliferative carcinomatous lesion.



Fig. 12.72: Gallbladder showing scirrhous carcinoma with pre-existing gallstones and cholesteroses.

CHOLANGIOCARCINOMA (Bile Duct Carcinoma)

- It is associated with sclerosing cholangitis, clonorchiasis infestation, Caroli's disease or choledochal cyst.
- It is an aggressive adenocarcinoma which presents as obstructive jaundice.
- It commonly occurs at the hepatic duct confluence.

Risk Factors for Cholangiocarcinoma

- Primary sclerosing cholangitis (PSC): Here commonly it is extrahepatic, usually at the confluence.
- Choledochal cyst.
- Hepatolithiasis.
- Hepatitis B and C are risk factors for intrahepatic cholangiocarcinoma.
- Lynch syndrome II.
- Multiple biliary papillomatosis.
- Previous biliary enteric anastomosis.
- Clonorchis sinensis infestation.
- Thorotrast, nitrosamines, dioxin.

Classification I

- Intrahepatic—10%.
- Perihilar—65%.
- Distal—25%.

Classification II—Pathological

Sclerosing (80%); nodular; papillary.

Classification III

- *Upper third*—from porta to cystic duct – 50%.
- *Middle third*—from cystic duct to upper margin of first part of the duodenum—25%.
- *Lower third*—from upper margin of first part of duodenum to ampulla—20%.
- *Diffuse—5%.*

Classification of perihilar cholangiocarcinoma (Bismuth)

- Type I : Below the confluence of RHD and LHD
- Type II : Reaching the confluence of RHD and LHD
- Type III : Involving CHD and RHD/LHD
- Type IV : Involving confluence and both RHD and LHD or multicentric tumour

Features

- Main presentation is painless obstructive jaundice of short duration.
- Palpable liver either smooth and soft (hydrohepatotic) or hard nodular (secondaries).
- Weight loss and anorexia is typical and significant.

Investigations

- ERCP and choledochoscope.
- Liver function tests.
- PTC.
- U/S abdomen, CT scan.
- MR scan—Best investigation. MRCP to *see duct*; MRI to *see nodes*; MR angiogram to *see vascularity.*

Assessment should be done to check the operability of tumour by—assessing the spread in bilateral hepatic duct up to secondary radicles, both hepatic arterial spread, portal vein encasement, hepatic lobe atrophy, distant spread.

TNM staging of cholangiocarcinoma

Tumour	*Nodes*	*Staging*
Tis – Carcinoma in situ	N0 – No regional nodes	Stage 0 – TisN0M0
T1 – Invasion of subepithelial connective tissue	N1 – Hepatoduodenal ligament nodes	Stage I – T1N0M0
T2 – Invasion of perifibromuscular tissue	N2 – Peripancreatic, periduodenal, periportal, celiac and or SMA lymph nodes	Stage II – T2N0M0
T3 – Invasion of adjacent organs	*Metastases*	Stage III – T1/2N1/N2M0
	M1 – Distant metastases present	Stage IVA – T3 any N M0
	M0 – No metastases	Stage IVB – Any T anyNM1

Treatment

- When operable, portal region clearance with hemihepatectomy can be done. *Intrahepatic type* is treated with hemihepatectomy. *Perihilar* is treated with hemihepatectomy or extensive bile duct resection, nodal clearance, caudate lobe removal, cholecystectomy. Distal tumour is treated with Whipple's pancreaticoduodenectomy.
- Most often it is inoperable. Stenting can be done to relieve jaundice, through PTC or ERCP or on table.
- Chemotherapy—5 FU; Gemcitabine, cis platin.
- Chemotherapy, with external beam radiotherapy (ERBT).

KLATSKIN TUMOUR

- It is cholangiocarcinoma at the confluence of the hepatic ducts and common hepatic duct above the level of the cystic duct (20% of cholangiocarcinomas).
- *It causes obstructive jaundice with hydrohepatosis without enlargement of gallbladder.*
- Management is like cholangiocarcinoma.
- Hilar resection with hepaticojejunostomy.
- Segment III left hepaticojejunostomy—Blumgart's.
- Longmire's left hepaticojejunostomy after left liver lobe resection.
- Cattell's hepaticojejunostomy.
- Smith's mucosal graft hepaticojejunostomy.
- Palliative PTC with stenting/ERCP stenting, intraoperative stenting. Metal stents show long period of patency (12 months) than polyethylene stents (4 months).



Fig. 12.73: Resected specimen of Klatskin tumour (*Courtesy:* Dr Arunkumar, MCh).



Fig. 12.74: Klatskin tumour.

Cholangiocarcinoma

- It is an uncommon tumour of elderly. 1 in 1,00,000 is the incidence
- Primary sclerosing cholangitis is the commonest association. 20 fold increased risk
- Choledochal cyst, Caroli's disease, pyogenic cholangiohepatitis, Clonorchis sinensis, opisthorchis viverrini infestation, hepatolithiasis, hepatitis C, Lynch syndrome II, bile duct adenoma and papillomatosis are other causes
- Chemical carcinogens like thorium, nitrosamines, diosmin also can cause
- Intrahepatic cholangiocarcinoma is 10%
- 60% cases are proximal to cystic duct CBD junction
- Features are jaundice, pain, hepatomegaly, cachexia, early satiety and weight loss
- It is adenocarcinoma type
- Lymph node spread is common
- Resection along with liver/resection along with pancreas are surgical options
- But surgical resection is possible only in 5% of cases
- Stenting/bypass are palliative options
- Doxorubicin, cis platin and I_{131} anti-CEA antibodies are adjuvant therapies
- Condition has got 90% mortality in one year

BILIARY FISTULAS

Types

a. *External:* Usually occurs as a complication of surgery following:
   - Gastrectomy.
   - Cholecystectomy open or laparoscopic.
   - CBD surgery.
   - Pancreatic surgery.

b. *Internal:*
   - Cholecystoduodenal fistula causing gallstone ileus.
   - Cholecystoenteric fistula.
   - Cholecystocholedochal fistula.

   External biliary fistulas are difficult to manage, often dangerous, but many a times resolve spontaneously.

Investigations

- Fistulogram.
- ERCP.
- Electrolyte estimation.
- Liver function tests.

Treatment

- Total parenteral nutrition (TPN).
- Antibiotics.
- Blood transfusion.
- Electrolyte management.
- Care of the fistula wound with regular dressing, using zinc oxide cream has to be done to protect the skin.
- Later continuity of biliary system has to be restored by open surgery or through ERCP and stenting.

GALLSTONE ILEUS

It is a type of acute intestinal obstruction, often seen in elderly and is due to blockage by a bolus or mass of gallstones which commonly enter the intestine through cholecystoduodenal fistula (75%) or rarely through cholecystointestinal or gastric fistulas.

The same beam of light can illuminate two objects and produce two different effects.



Fig. 12.75: Gallstone ileus.

Gallstones in the gallbladder
↓
Cholecystitis
↓
Suppuration and adhesion over the duodenal wall
↓
Communication of gallbladder into the duodenum
↓
Gallstones pass into the duodenum forms a *bolus ('Rolling stone gather mass')*
↓
Blocks narrow part in the ileum.
↓
Gallstone ileus

Clinical Features

- Pain abdomen and features of intestinal obstruction.
- Stones may perforate the ileum to cause peritonitis.
- It is 1% of all intestinal obstruction overall; 25% of obstruction in elderly.
- Recurrent episodic obstruction due to moving stone bolus is typical—*tumbling obstruction*.

Investigations

- Plain X-ray abdomen in erect posture shows *air in the biliary tract* (branching gas pattern) and multiple air fluid levels.
- U/S abdomen.
- CT is diagnostic.

Treatment

- Laparotomy, enterotomy, removal of gallstones and closure of enterotomy is done. Enterotomy is done not at the site of obstruction but more proximal to the site of obstruction and stones are milked towards the enterotomy site. If bowel is found ischaemic at the impacted area, resection and anastomosis is done.
- Laparotomy and crushing of stones with fingers to relieve the obstruction is only occasionally useful.
- Cholecystectomy, correction of fistula with T tube drainage can be done in same sitting if patient's general condition is good. Otherwise it is done after 12 weeks. If cholecystectomy and definitive corrective surgery is not done, recurrent gallstone ileus is likely to occur.

Causes for gas in the biliary tree

- Cholecystoduodenal fistula
- Choledochoduodenostomy
- Choledochojejunostomy
- Transduodenal sphincteroplasty
- Emphysematous cholecystitis

Bouveret's Syndrome

- A rare entity with cholecystoduodenal fistula causing gallstones from gallbladder to pass into the duodenum leading to *duodenal obstruction*.

HEMOBILIA

- It is bleeding commonly from the liver or occasionally from the gallbladder into the biliary tract.
- There is abnormal communication between a blood vessel and a bile duct or any part of the biliary tree.

Causes

- Accidental trauma, ***iatrogenic*** trauma (50%). In accidents hemobilia is more commonly caused by blunt trauma (3%) than by penetrating one.
- Percutaneous diagnostic and therapeutic procedures.
- Vascular diseases of the hepatic artery.
- Malignant liver diseases.
- Portal hypertension.
- Parasitic liver diseases like hydatid disease.
- Gallstones rarely erode into hepatic artery causing life-threatening hemobilia.
- Blood and necrotic material drains into the biliary tree causing gastrointestinal bleeding. As bile interferes with coagulation a fatal haemorrhage can occur.
- Arterial hemobilia is more common. Portal venous hemobilia is rare.
- Early rapid presentation can occur; but delayed, after weeks/months/years, presentations are known to occur which is often difficult to suspect and diagnose.
- These recurrent clots can cause pancreatitis, cholangitis.

Clinical Features

- Pain which is colicky in nature.
- Obstructive jaundice.
- Haematemesis and melaena.

Triad of Sandblom in hemobilia

- Jaundice—60%
- Pain—70%
- Upper GI bleed with melaena (90%), haematemesis (60%)

All 3 features of triad are seen only in 20% of cases.

Investigations

- LFT.
- U/S abdomen.
- Selective arteriography—test of choice in detecting bleeding site in 90% of cases.
- Upper GI scopy—useful only in 10% of cases.

Treatment

- *Aim: To stop bleeding and to relieve biliary obstruction.*
- Antibiotics.
- Blood transfusions.
- Selective arterial embolisation. Transarterial embolisation (TAE) shows 90% success rate. It is the *choice therapy* with least morbidity.
- Surgical intervention is *only rarely indicated* in failed TAE. Laparotomy, ligation of bleeding vessel or hepatic artery, excision of aneurysm, hepatic resection—are the procedures done.

  Hemobilia is often a fatal condition.

Note:
Bilhemia: It is different very rare entity wherein bile flows into the hepatic or portal venous system due to raise in intrabiliary pressure more than that of portal or hepatic venous pressure. It may be due to trauma, iatrogenic or gallstone eroding into the venous system. Large quantity of bile enters the venous system and later to lung becoming fatal. If flow is low which is common, subsides spontaneously. ERCP is diagnostic. Treatment is stenting. Septicaemia and mortality is common.

WHITE BILE

- It is double misnomer.
- It is *neither white nor bile.* It is opalescent.
- It is *mucous secreted by the lining of biliary tree*.
- It signifies severe obstruction due to stone (impacted in the CBD), or carcinoma head of pancreas or periampullary region.
- It is on table finding during surgery.
- It means liver is unable to secrete bile due to raised intraductal pressure, and so can anticipate hepatic failure.
- Indicates a poor prognosis.



Fig. 12.76: Demonstration of white bile on table. It is not white but opalescent. It is not bile but it is mucous.

CHOLECYSTECTOMY

It is the surgical removal of gallbladder.

Prophylactic cholecystectomy is done in

- Diabetic patients
- Congenital haemolytic anaemia
- Patients who has underwent bariatric surgery

Indications

- Gallstones—symptomatic.
- Cholecystitis—acute, chronic.
- Acalculous cholecystitis.
- Empyema gallbladder.
- Mucocele gallbladder.

Approach

- *Open*
  - Right subcostal incision (Kocher's).
  - Right paramedian.


Kocher's incision (open method)
10 mm port
5 mm port
Mayo-Robson incision
5 mm port
10 mm port (Laparoscope to pass)

Fig. 12.77: Incisions for open cholecystectomy and laparoscopic cholecystectomy.

  - Horizontal incision.
  - Mayo-Robson incision.
- *Laparoscopic approach.*

Technique

After opening the abdomen, colon is pushed downwards and stomach medially.

Duct—first method: Here *Calot's triangle* is dissected. Cystic artery is identified and ligated. Cystic duct is ligated close to the gallbladder. Gallbladder is separated from gallbladder fossa and removed. Haemostasis is maintained.

Fundus—first method: It is done in difficult gallbladder due to dense adhesions. Fundus is separated from the liver bed. Dissection is carried proximally until cystic duct and cystic artery are identified, which are then ligated.



Fig. 12.78: Kocher's incision used for open cholecystectomy.

Drain is placed, which is removed after 72 hours.

On table cholangiogram is a must after cholecystectomy.

Complications of Cholecystectomy

- Complications can occur either in open method or in laparoscopic method.
- Open method is done through either right paramedian incision or Kocher's incision (right subcostal).



Fig. 12.79: Ligation of cystic duct and cystic artery while doing cholecystectomy.

Complications which can occur in both:

- Infection and subphrenic abscess
- Bleeding from cystic artery, and from liver bed
- Injury to CBD or hepatic duct
- Bile leak and biliary fistula formation
- Biliary stricture formation
- Injuries to colon, duodenum, mesentery



Fig. 12.80: Diagram showing the partial cholecystectomy wherein GB is removed at Hartmann's pouch, distal to Calot's triangle. It is done when there is dense adhesions,with difficult surgical plane.

LAPAROSCOPIC CHOLECYSTECTOMY

It is the most popular method to remove gallbladder. It is the gold standard treatment for gallstone.

Position

- Supine, head end up and right side up.
  Anaesthesia—general.

Ports

- 10 mm port in umbilicus to pass 10 mm telescope.
- 10 mm port in midline epigastrium as working channel.
- Two 5 mm ports at midclavicular and anterior axillary line in subcostal region.

Procedure

After creation of pneumoperitoneum with 12-14 mm pressure, 10 mm umbilical port is inserted. Telescope is passed. Under vision remaining ports are passed. With lateral 5 mm port, gallbladder grasper forceps is passed and fundus of gallbladder is held and pushed up towards the diaphragm. With middle 5 mm port grasper is passed to hold Hartmann's pouch. With 10 mm port dissector is passed using reducer. Calot's triangle is dissected. Cystic duct is identified. Adhesions are released. First posterior dissection is completed. Cystic artery is above and deep to cystic duct. Cystic duct is clipped or ligated. Cystic artery is also clipped. Gallbladder is dissected off the liver bed using cautery (hook/spatula)/harmonic scalpel. Gallbladder is removed through 10 mm working port with reducer or using a sterile bag. Any bleeding points are coagulated. If needed saline wash is given to the bed. If infected, if gallbladder is opened, if there are adhesions, if there is oozing from gallbladder bed, a tube drain is placed through lateral 5 mm port. All ports are removed. Umbilical port is sutured in layers. Other ports are sutured. Patient is asked to take oral food in 24 hours and can be discharged in 24-48 hours.


GB
Hartmann's
Rouvier sulcus

Fig. 12.81: Rouvier sulcus on the undersuface of liver is a guideline during laparoscopic cholecystectomy wherein dissection in Calot's should be always kept in front of it to avoid CBD/hepatic duct injury.


Gallbladder
A
GB
Hartmann's
Calot's
Cystic duct
CBD
B

Figs 12.82A and B


Cystic duct clipped
C

Fig. 12.82C

Figs 12.82A to C: Photos of laparoscopic cholecystectomy showing cystic duct, gallbladder, Calot's triangle and clipped cystic duct.

Problems

- Difficult Calot's triangle.
- Dense adhesions.
- Bleeding.
- Anomalies of cystic duct, cystic artery.

Complications

- Bile duct injury—0.8 %.
- Bleeding.



Fig. 12.83: Post-cholecystectomy bile leak with fistula. It is common and problematic complication after cholecystectomy.

- Bile leak.
- Infection, cholangitis, septicaemia.
- Subphrenic abscess formation.
- Injury to colon, duodenum, mesentery.

SINGLE INCISION LAPAROSCOPIC SURGERY (SILS) IN CHOLECYSTECTOMY

SILS is an advanced minimally invasive surgical procedure wherein surgeon operates exclusively through a single umbilical entry port. It is also called as single port access surgery (SPA), one port umbilical surgery (OPUS), and Single port incision less conventional equipment-utilising surgery (SPICES), natural orifice transumbilical surgery (NOTUS).

It needs general anaesthesia, specialised umbilical large trocars which accommodates working instruments along with, flexible laparoscope, rotatable instruments, articulating handles, harmonic scalpel.

Here through a large 2.5 cm umbilical vertical incision dissection is done by open method to reach peritoneal cavity. Specialised port in which one can pass 10 mm telescope and two 5 mm instruments for work is used. Instruments are angled and flexible to meet the ergonomic principles to certain extent. Dissection of gallbladder is done in similar fashion like four port technique. Specimen is easily retrieved through umbilical port as it is wide enough. If difficulty arises any time one can add additional ports as required.

Figs 12.84A and B: Single incision laparoscopic surgery (SILS) for cholecystectomy.

Advantages

- There is no visible scar like a traditional multiport.
- Faster recovery time, early return to work.
- Cosmetically better.

Disadvantages

- Expensive trocars and instruments—cost factor.
- Skilled work, learning curve.
- Dissection against normal surgical ergonomics.

Complications

- Umbilical wound pain, infection.
- Umbilical hernia.
- Because of limited visibility time consuming.
- During learning curve complications of cholecystectomy and conversion rate may be more.

***Note*:**
Waltman-Walter syndrome: It is compression of IVC due to collection of fluid in subphrenic space during post-cholecystectomy period. It mimics coronary thrombosis.

BILE DUCT INJURIES

Causes

- Cholecystectomy—open or laparoscopic.
- Trauma.
- Instrumentation—ERCP, baby endoscope, choledochoscope.
- Other surgeries—pancreatic, duodenal, gastric.
- Anomalous biliary system increases the risk of injury.

Classifications

Strasberg classification

- Class A: Bile leak from the cystic duct or an accessory duct showing continuity with the common bile duct
- Class B: Section/injury of an accessory duct/sectorial ducts aberrant right hepatic duct with no continuity with the common bile duct with occlusion
- Class C: Leak/open drainage from a sectorial duct/aberrant right hepatic duct with no continuity with the common bile duct
- Class D: Partial section/lateral injury of an extrahepatic duct bile duct with no complete loss of continuity with the rest of the bile duct system
- Class E: Complete section/circumferential injury of the bile duct with subtypes according to the length of the stump at various levels
  - E1- Stricture/injury at more than 2 cm distal to bifurcation.
  - E2 – Stricture/injury less than 2 cm distal to bifurcation.
  - E3 – Stricture/injury at bifurcation
  - E4 – Stricture/injury involving right and left hepatic ducts
  - E5 – Complete obstruction of entire bile duct

Note: Only right and left partial injuries are not included in this classification

Stewart-Way classification

This classification involves four strata based on the mechanism and anatomy of injury.

- Class I: It refers to the incomplete section of bile duct with no loss of tissue. It has a prevalence rate of 8%
- Class II: It is a lateral injury of the common hepatic duct that leads to stenosis or bile leak. It is the consequence of thermal damage and clamping the duct with surgical staples. It has a prevalence of 2% with a concomitant hepatic artery injury in 20% of cases. T-tube related injuries are included within this class
- Class III: It is the most common (60%) represents the complete section of the common hepatic duct. It is subdivided into type IIIa, remnant common hepatic duct; type IIIb, section at the confluence; type IIIc, loss of confluence; and type IIId, injuries higher than confluence with section of secondary bile ducts. Associated injury of right hepatic artery occurs in 25% of cases
- Class IV: It is right (65%) and accessory right (25%) hepatic duct injuries with associated injury of the right hepatic artery (60%). Occasionally it includes the common hepatic duct injury at the confluence (5%) besides the accessory right hepatic duct lesion (prevalence of 10%)

Hannover classification (2007)

It classifies injuries in relationship to the confluence and also includes vascular injuries.

- Type A: It refers to cystic and/or gallbladder bed leaks.
- Type B is a complete or incomplete stenosis caused by a surgical staple.
- Type C represents lateral tangential injuries.
- Type D refers to complete section of the common bile duct emphasizing their distance to the confluence as well as the concomitant injuries of hepatic artery and portal vein.
- Type E is late bile duct stenosis at different lengths to the confluence.

Note: Bismuth classification (for open surgery/pre-laparoscopic era) is discussed under biliary stricture earlier.

Presentations

- Fever, pain, features of bile stasis like cholangitis, jaundice.
- 10% of laparoscopic bile duct injuries are identified on table; 30% with bile leak; 25% with obstructive jaundice; 30% with cholangitis. Patients with bile leak present early; with formed biliary stricture presents with jaundice and cholangitis months or years later.

Complications

- Biliary fistula with electrolyte imbalance.
- Biliary peritonitis, septicaemia.
- Subphrenic abscess formation.
- *Biloma* formation.
- Severe malnutrition, deficiencies.
- Late—biliary cirrhosis, portal hypertension.

Investigations

- LFT, coagulation profile.
- US abdomen, fistulogram.
- Dynamic CT scan will delineate the anatomy of injury.
- ERCP is useful if injury is only partial where stenting can also be done.
- PTC is the *investigation* of choice to identify site, nature, extent of stricture. It also facilitates drainage and stenting.
- Hepatobiliary scintigraphy may be useful.
- MRCP may be useful to identify ductal anatomy.
- CT arteriography is useful to identify associated hepatic artery or portal vein injury which is 20% in association with CBD injury.

Management

- General: antibiotics, nutrition, TPN.
- Conservative: Small partial injury to CBD may resolve spontaneously or with the help of ERCP, sphincterotomy and stenting is done.
- *Management of biliary duct injury on table* (during ***laparoscopic cholecystectomy***/open): Conversion into open surgery with a lengthy subcostal/bucket handle incision. Intraoperative cholangiogram should be done. Partial injury of CBD less than 30% of circumference is treated with primary repair with a T-tube in place. Extensive injury more than 30% of the circumference or cautery injury or complete CBD transection should be treated with Roux-en-Y choledochojejunostomy. Isolated hepatic duct injury less than 3 mm in size should be ligated. More than 3 mm in size should be reimplanted or Roux-en-Y hepaticojejunostomy should be done. If facility for surgical repair is available, patient should be sent to a higher centre after placing a drain with abdomen closure.
- *Management of bile duct injury identified at a later period*: In such situation it is better to wait for 6 weeks for the inflammation to subside which facilitates easier identification of proximal CBD. After proper assessment of injury, Roux-en-Y choledochojejunostomy or *Roux-en-Y hepaticojejunostomy* is done.
- *Hepp-Couinaud approach*: Here hilar plate is meticulously dissected; left hepatic duct is anastomosed to Roux jejunal loop to create hepaticojejunostomy often with creation of proximal 'access loop' for future endoscopic approach. Complications are—recurrent cholangitis, bile leak from stoma, hemobilia, stenosis of biliary enteric anastomotic site (10%, occurs often after many years).

POST-CHOLECYSTECTOMY SYNDROME (15%)

- Recurrent, new or persistent symptoms after cholecystectomy in patients who have no demonstrable abnormality is called as post-cholecystectomy syndrome.

Success means growth and growth means change.

- It may be due to loss of reserving function of the gallbladder or continuous bile flow into the duodenum may be causing oesophagitis/gastritis or diarrhoea and colicky pain. 20% causes are other than due to hepatopancreatic biliary problems.
- However importance lies in ruling out the other causes of the symptoms like peptic ulcer, hiatus hernia, pancreatic diseases, residual CBD stone, cystic duct remnant, papillary stenosis.
- True post-cholecystectomy syndrome is treated with proper counseling, psychiatric evaluation and drug therapy. It should be evaluated thoroughly.

Causes of post-cholecystectomy syndrome

Gallbladder	Residual or reformed gallbladder Stump stones in cystic duct Neuroma in the stump Slipped stones into the peritoneum Clips applied to cystic duct
Biliary tree	Residual stone in CBD Biliary dyskinesia Stricture Dilatation without obstruction Fistula Cholangitis Malignancy
Liver	Fatty liver, hepatitis, cirrhosis Sclerosing cholangitis
Pancreas	Pancreatitis, stones Carcinoma pancreas Sphincter of Oddi dyskinesia
GIT	Oesophagitis / hiatus hernia/ achalasia cardia Duodenal diverticula IBS, constipation, incisional hernia Mesenteric ischaemia
Cardiac	Coronary heart disease
Others	Adrenal tumour Thyrotoxicosis Intercostal neuralgia Arthritis *Psychiatric diseases*

BILIARY DYSKINESIA

Biliary dyskinesia is *motility disorder* of either gallbladder or sphincter of Oddi. Patient presents with features of biliary colic without any evidence of gallstone disease.

It can be:

- **Gallbladder dyskinesia**:
  - Here CT scan, gastroscopy, ERCP are normal. CCK is injected intravenously after filling gallbladder with radionuclide labeled Tc99m, gallbladder ejection fraction is assessed after 20 minutes. If it is less than 35% then it is called as gallbladder dyskinesia.
  - It is treated with laparoscopic cholecystectomy.
- **Sphincter of Oddi dysfunction**:
  - It is also known as *biliary sphincter dyskinesia or pancreatic sphincter dyskinesia*. It is benign acalculous obstruction to bile and/or pancreatic flow across sphincter of Oddi causing cholestasis, pancreatitis and pain.
  - It may be due to trauma, congenital anomalies.
  - In occurs in 1% of cholecystectomy patients. Condition is common in females.
  - Normally CCK relaxes sphincter by decreasing its pressure. After IV injection of CCK, if CBD diameter becomes more than 12 mm or if there is increase in CBD diameter in response to CCK on US evaluation it suggests dysfunction of sphincter of Oddi. If basal sphincter pressure, on study increases more than 40 mm Hg it also suggests the same.
  - *Milwaukee's classification*: ***Type I***: *Any one of the* following features—unexplained biliary pain for more than 6 months after cholecystectomy, ERCP showing CBD > 12 mm, delayed bile drainage > 45 minutes, altered liver enzymes. ***Type II***: Unexplained biliary pain for more than 6 months after cholecystectomy + *with* any one of the other criteria. ***Type III:*** *Only* unexplained biliary pain for more than 6 months after cholecystectomy, without any of other criteria.
  - ERCP/MRCP/sphincter of Oddi manometry, IV cholangiography are the *investigations.*
  - *Treatment*: Endoscopic sphincterotomy, botulinum toxin injection into the sphincter, nifedipine, transcutaneous electric nerve stimulation to raise serum VIP level which decreases the sphincter pressure.

Chapter 13 Spleen

CHAPTER OUTLINE

- Surgical Anatomy
- Functions of the Spleen
- Splenunculi
- Splenic Injury
- Splenomegaly
- Hereditary Spherocytosis
- Immune Haemolytic Anaemia
- Thalassaemia
- Sickle Cell Disease
- Idiopathic Thrombocytopenic Purpura
- Thrombotic Thrombocytopenic Purpura
- Splenectomy
- Overwhelming Postsplenectomy Infection
- Splenic Artery Aneurysm
- Splenic Abscess
- Hypersplenism
- Splenic Cyst

SURGICAL ANATOMY

- It is a wedge-shaped organ lying mainly in left hypochondrium, along the long axis of 10th rib.
- Hilum of spleen transmits splenic vessels and nerves. The visceral surface is related to stomach, splenic flexure of colon, kidney.

Ligaments of Spleen

Spleen is suspended by two ligaments *(a) lienorenal ligament, (b) gastrosplenic ligament.*

- Lienorenal ligament transmits blood vessels to spleen. The tail of pancreas lies in this ligament, which can be damaged during splenectomy.
- The gastrosplenic ligament contains short gastric vessels which supply the left half of greater curvature of stomach.
- Phrenicocolic ligament comes in contact with lower pole of spleen, which may be damaged during mobilization of splenic flexure of colon.

Blood Supply

Splenic artery is the branch of coeliac artery but may arise from aorta or superior mesenteric artery, blood flow is 300 ml/mt. *Splenic vein* joins the superior mesenteric vein at right angle behind the neck of pancreas to form the portal vein.

Splenic parenchyma contains *white pulp* and *red pulp*. *White pulp* lies in centre surrounding the central artery, which is a branch of trabecular artery. It is made up of lymphatic nodules with germinal centres and periarterial lymphatic sheaths with a network containing lymphocytes and macrophages. White pulp is surrounded by marginal zone which contains end arteries from central and peripheral peniciliary arteries. Marginal zone contains marginal sinus which filters the materials from the white pulp. Immunoglobulins secreted by white pulp enter marginal zone and into main bloodstream.

Red pulp is located outer to marginal zone. Red pulp contains cords and sinuses. Central artery gives reticular branches which open into these sinuses and cords wherein particles are phagocytosed. Commonly central artery eventually ends in these cords and sinuses. Few end branches of the central artery directly enters the pulp vein. Cords and sinuses eventually drain into pulp vein. Blood circulating through these cords and sinuses are called as '*open*' circulation (90%). Blood passing through white pulp but not entering these cords and sinuses are called as '*closed*' circulation (10%).

Spleen is palpated under left costal margin during inspiration. It has to enlarge 2-3 times its normal size to become palpable.

FUNCTIONS OF THE SPLEEN

Spleen has got two groups of functions:

1. *Cellular function.*



Fig. 13.1: Architecture of spleen showing red pulp (peripheral); white pulp (central); open and closed circulation; marginal zone and sinuses and trabecular artery and vein.

- Removal of non-deformable intracellular substances from deformable cells is called as "*pitting*". *Heinz bodies/ Howell-Jolly bodies, Pappenheimer siderotic bodies* are removed by this method from RBCs. Post-splenectomy patients will show these bodies in the RBCs in peripheral smear. In splenunculi, these bodies will be absent even after splenectomy.
- Removal of aged/abnormal red cells is done by a process of "*culling*". RBCs which loose osmotic balance and membrane integrity is called as non-deformable and they are removed by this method.
- Half life of platelets is 10 days. In splenomegaly 80% of platelets may be sequestered in spleen causing thrombocytopenia. Normally spleen is reservoir for platelets. 1/3rd of total platelet mass is present in spleen. In pathological status like immune diseases phagocytosis of platelets in spleen is accelerated by many folds.
- Splenomegaly and hypersplenism can cause neutropenia. Neutrophil half life is 6 hours.
- Bacterial clearance also occurs in spleen by phagocytosis. After splenectomy, patients are more prone for OPSI.

2. *Immunologic functions* like synthesis of antibody IgM; formation of lymphocytes; production of tuftsin, opsonins, properdin and interferons.

Functions of spleen

- Response to antigenic challenge—by secreting antibodies like IgM, tuftin, opsonins, properdin, interferons. These agents make bacteria and other organisms more vulnerable to phagocytosis. All bacteria including the capsulated types, virus and fungi are destroyed efficiently.
- Destruction or correction of abnormal cells like old RBCs, target cells, siderocytes, spherocytes or removal of inclusion bodies or parasites from the RBCs by culling and pitting.
- Phagocytosis of foreign substances.
- As platelet reservoir.
- Erythrocyte production: In fetal life, it is an important site of RBC production till 5th month of gestation. In adults erythropoiesis in spleen occurs only if marrow production is inadequate, e.g. in myelofibrosis.
- Iron reutilisation.

SPLENUNCULI (30%)



Fig. 13.2: On table photo of splenunculi with splenomegaly. Splenunculi should be removed otherwise disease will recur.

- These are single or multiple **accessory spleens**.

Sites

- Hilum of spleen (50%)
- Near splenic vessels
- Tail of the pancreas (30%)
- Splenic ligaments—gastrosplenic/splenorenal
- Mesocolon
- Greater omentum

- After splenectomy, they undergo hyperplasia and lead to recurrence of the disorder for which spleen was removed.
- Blood peripheral smear, in these patients with splenunculi *will not show* Howell-Jolly bodies. Pappenheimer siderotic bodies.
- Accessory spleen can also be occasionally present adjacent to left ovary or adjacent to left testis.

SPLENIC INJURY (RUPTURE SPLEEN)

Causes

- Splenic injury occurs commonly following road traffic accidents, other blunt injury or penetrating/stab injuries.
- Most often associated with fracture of left lower ribs, haemothorax, injury of liver (left lobe commonly, occasionally both lobes), bowel, tail of pancreas, left kidney.
- Injury is more common and severe in *enlarged spleen,* i.e. in malaria, tropical splenomegaly, infectious mononucleosis.
- Spontaneous rupture of spleen can occur in malaria and infectious mononucleosis.
- *Larang* was used to kill by the murderers in far east where malaria was endemic leading to splenomegaly, which ruptured more easily.

- Spleen is the most common solid organ injured in blunt abdominal trauma.

Types of Injury

1. *Splenic subcapsular haematoma:* After initial injury patient remains asymptomatic for a short period. But this haematoma ruptures later, may be after few days causing torrential haemorrhage.



Fig. 13.3: Large subcapsular splenic haematoma.

2. *Clean incised wound over the surface*: This can be treated by splenorrhaphy.
3. *Lacerated wound.*
4. *Splenic hilar injury* causes torrential haemorrhage, may even cause death. So immediate surgical intervention and splenectomy is done.
5. Splenic injury associated with other injuries (left kidney, left colon, small bowel, pancreas, diaphragm, left lung).



Figs 13.4A to D: Types of splenic injury. (A) Subcapsular haematoma, (B) Incised wound, (C) Lacerated wound and (D) Hilar injury.

Associated injuries

- Left lobe liver injury
- Tail of pancreas injury
- Left kidney, left colonic injury
- Small bowel injury
- Diaphragm and left lung injury
- Fracture lower ribs—left sided (30%)
- Left sided haemothorax

Presentation

Hilar injury presents with rapid development of *shock and deteriorates fast.* Even death can occur sometimes. Here *emergency surgery and splenectomy is mandatory*.

- In other types, features of shock (pallor, tachycardia, restlessness, hypotension), pain, tenderness and abdominal rigidity in left upper quadrant is seen.
- Later there will be abdominal distension due to haemoperitoneum.
- Dullness in the left flank which does not shift, as the collected blood gets clotted. *Dullness without shifting—**Ballance's sign***.
- Clot collected under the left side of the diaphragm irritates it and the phrenic nerve causing *refered pain in the left shoulder—**Kehr's sign***. There may be left sided haemothorax with fracture of ribs.

Delayed presentation is also possible due to formation of subcapsular haematoma which later gives way. Initially gets temporarily localized by greater omentum, later giving way leading to torrential bleeding. Blood clot temporarily seals off the bleeding which later gets dislodged causing severe bleeding. This time period in between is called **'*latent period of Bandet*'.**

- Pseudoaneurysm and traumatic splenic arteriovenous fistula formation can also occasionally cause delayed life threatening haemorrhage.
- Features of other abdominal organ injuries may be present.

Signs in splenic rupture

- *Kehr's sign*—pain in left shoulder 15 minutes after foot end elevation
- *Ballance's sign*—left sided abdominal dullness which will not shift
- *Saegesser's tender point* between left sternomastoid and scalenus medius
- Latent period of Bandet—refer above

Splenosis: Autotransplantation of fragments of splenic tissue may occur within the peritoneal cavity following rupture of spleen

A smile is the shortest distance between two people.



Figs 13.5A to C: Splenic injury with splenic haematoma.

Investigations

- U/S abdomen is the investigation of choice, as it is quicker, cheaper and non-invasive.
- Hb%, PCV, blood grouping and cross matching.
- *Adequate amount of blood must be kept ready for transfusion.*
- CT scan will show type of splenic injury and its class.

Plain X-ray abdomen. Findings are:

- Obliteration of splenic outline
- Obliterarion of psoas shadow (most important feature)
- Indentation of fundic gas shadow
- Fracture of lower ribs
- Elevation of left side of diaphragm
- Free fluid in the abdomen between coils of intestine

- ***Diagnostic peritoneal lavage (DPL):*** By subumbilical incision the peritoneal lavage catheter is introduced into the peritoneal cavity. One litre of crystalloid (normal saline) is introduced into the cavity. Patient is turned to both left and right side and fluid is collected back. It is sent for cytology, culture, microscopy and biochemical analysis.
  It is significant when the aspirated fluid contains:
  - Gross blood of 10 ml.
  - >100000/mm^3 of RBC.
  - >500/mm^3 of WBC.
  - Bile, bacteria or food fibres.
  - Amylase > 175 units/dl.



Fig. 13.6: Lacerated injury over the spleen. Patient underwent splenectomy.

- Angiogram, for diagnosis and often for angiographic embolisation to reduce the bleeding and to manage splenic injury non-operatively is also becoming routine in many centres.

Complications of Splenic Rupture/Trauma

- Blood loss.
- DIC.
- Sepsis.
- Splenic artery pseudoaneurysm.
- Splenic arteriovenous fistula.
- Problems of associated injuries like of pancreas.

Splenic organ injury scale (1994)

Grade I	Non-expanding subcapsular haematoma <10% surface area.
	Non-bleeding capsular laceration with <1 cm depth
Grade II	Non-expanding subcapsular haematoma 10-50% surface area.
	Non-expanding intraparenchymal haematoma < 5 cm in diameter

	Laceration—capsular tear 1-3 cm in depth which does not involve trabecular vessel
Grade III	Expanding subcapsular or > 50% surface area or ruptured bleeding subcapsular haematoma / intraparenchymal haematoma.
	Intraparenchymal haematoma > 5 cm or parenchymal laceration >3 cm depth involving trabecular vessels
Grade IV	Laceration involving segmental or hilar vessels with > 25% devascularization
Grade V	Shattered or avulsed spleen; hilar devascularization with entire spleen separation

Treatment

Initial Management

- Central venous line for perfusion and monitoring.
- Transfusion of blood as needed.
- Antibiotics coverage.
- Urinary catheterisation.
- Nasogastric tube aspiration.

Surgical Management

Emergency splenectomy

- It is done through midline/left subcostal incision. Thoracoabdominal extension of incision may be needed for rapid control of bleeding for injury to a large tropical spleen with severe bleeding. Other associated injuries should be looked for and dealt with (injury to left lobe liver/pancreas/ intestine/ colon).

Partial splenectomy (upper/lower)

- It can be done by retaining either of the upper or lower polar branches of the splenic artery.

Splenorrhaphy

- In especially clean incised wound, spleen can be salvaged by suturing the wound carefully with placement of gel foam, topical thrombin, absorbable mesh wrap over the wound. Suture repair, oxidised cellulose, debridement of lacerated spleen—are other methods used. Temporary occlusion of splenic artery is often needed during splenorrhaphy. 10% of splenic injuries undergo splenorrhaphy. Its application is getting reduced due to nonoperative approach in such patients
- But in class IV or V injuries splenorrhaphy is not possible.

Advantages of splenorrhaphy

- It avoids OPSI
- It avoids dead space and so prevents potential space for subphrenic abscess
- Cellular components of blood are better maintained

Salutary effect

- In traumatic rupture of spleen, spleen is cut into pieces of 0.5 cm and placed in omental pockets.

Nonoperative Management

- When facilities are available, splenic injury can be managed conservatively by non-operative management.
- Clinically close observation, serial haematocrit evaluation, serial CT abdomen/U/S abdomen at regular intervals to assess the progress or regress of the bleeding spleen has to be done.
- Absolute bed rest, sedation, antibiotic coverage and proper monitoring are needed.
- It is often supported by angiographic embolisation to improve the splenic salvage rate. But it may cause pain, splenic abscess or infarction.
- *Indications for nonoperative treatment*
  - Only splenic injury—no other associated injuries.
  - Grade I, II and III injuries.

Note:

- If patient shows features of haemodynamic instability—blood pressure below 90 mmHg, pulse rate above 120/minute, if patient does not show any positive response after 2 litre of crystalloid solution infusion, then nonoperative management should be abandoned.
- Nonoperative approach prevents possibility of OPSI, thrombocytosis causing possible *DVT*.
- 80% of children (due to more elastin in spleen and complete coverage with ribs in childhood) and 50% of adult with splenic injury are treated by nonoperative method.
- Failure rate in nonoperative management up to grade II is 15-20% which is gradually reducing to 5% in many centres. It is more in patients with age more than 55 years.
- Delayed splenic rupture and formation of splenic pseudoaneurysm are problems in nonoperative approach.
- Normal activity of the patient can be resumed only after 3 weeks following nonoperative treatment in grade I and II injuries; after 8 weeks in grade III or beyond usually with a confirmation by CT scan.

Complications of splenectomy

- Haemorrhage and shock
- Haematemesis
- Pancreatitis
- Pancreatic fistula
- Gastric dilatation
- Left sided pleural effusion
- Left sided colonic injury
- Severe sepsis
- Changes in cellular component of blood
- DIC

The best bridge between despair and hope is a good nights sleep—**E. Joseph Cossman**



Fig. 13.7: Splenorrhaphy is done in incised wound.



Fig. 13.8: Partial splenectomy is done when one of the branches of the splenic artery is ligated and other part is retained.



Fig. 13.9: Splenectomy is done in large wounds, lacerations, hilar injuries.

SPLENOMEGALY

Causes

1. *Infective:* Tuberculosis, splenic abscess, infectious mononucleosis, malaria, typhoid, kala azar.
2. *Blood diseases:* Chronic myeloid leukaemia, myelofibrosis, polycythaemia, hereditary spherocytosis, haemolytic anaemia, idiopathic thrombocytopenic purpura (ITP).
3. *Metabolic:* Gaucher's disease, amyloidosis, porphyrias,
4. *Portal hypertension.*
5. *Collagen diseases.*
6. *Malignancy*: Hodgkin's lymphoma, splenic sarcomas.

Masses which mimic enlarged spleen

- Kidney mass (Left sided)
- Retroperitoneal mass
- Left colonic mass
- Left adrenal mass

Clinical features of enlarged spleen

- Mass in the left hypochondrium
- Notch is felt
- Moves with respiration
- Dull to percuss
- Directed towards right iliac fossa
- Hook sign: Inability to hook under left costal margin
- Can not insinuate finger under left costal margin

HEREDITARY SPHEROCYTOSIS

It is an autosomal dominant disease effecting males and females equally.

Pathology

- Here there is an increase in red cell wall permeability to sodium. So sodium leaks into the red cells and it becomes spherical and more fragile. This leads to greater loss of membrane phospholipid resulting in weakening of the membrane with increase in energy and oxygen requirement. So these RBCs are destroyed in spleen causing haemolytic anaemia, haemolytic jaundice, unconjugated hyperbilirubinaemia, pigmented gallstones, cholangitis.
- Defect in components of red cell membrane like *spectrin (mainly),* ankyrin, band 3, or protein 4-2 causes weakness of red cell wall. This promotes the influx of sodium into the cell.
- Condition is common in North America.

Clinical Features

- Pallor, jaundice, recurrent fever, pain abdomen, splenomegaly, hepatomegaly, chronic leg ulcer. Gallstones are seen in 60% of cases.
- Spontaneous remission is uncommon.
- Patients are more prone for several infections.
- *Acute haemolytic crisis* precipitated by infection and stress; with features of acute pain abdomen, fever, vomiting and anaemia. It often mimics other acute abdominal conditions.

Investigations

- *Fragility test:* Here increased fragility of the erythrocytes is the typical feature. Haemolysis occurs in 0.6% or in even stronger solutions.



Figs 13.10A and B: Hereditary spherocytosis—on table and after surgery showing gallbladder and spleen specimens.

- LFT-↑ serum bilirubin.
- Reticulocyte count is increased significantly (25% increased).
- Faecal urobilinogen is increased.
- Labelled radioactive chromium shows faster red cell destruction.
- U/S abdomen is done to look for gallstones, spleen, liver, CBD.
- Peripheral smear shows spherocytes, haematocrit.

Problems with hereditary spherocytosis

- Haemolytic anaemia
- Haemolytic jaundice
- Pigmented CBD stones
- Cholangitis with Charcot's triad
- Gallstones (30%)
- Chronic leg ulcers

- Direct Coomb's test—negative.
- Radioactive chromium 51 labelled patients' red cells shows rate of sequestration of red cells in spleen.



Fig. 13.11: Specimen of gallbladder and spleen (postsurgical) in case of hereditary spherocytosis.

Treatment

- Blood transfusion to improve the Hb status. Later splenectomy is done—Optimum age for splenectomy is 7 years.
- Accessory spleen should be removed.
- Splenectomy prevents early RBC destruction thereby controlling anaemia, jaundice and also prevents further formation of leg ulcers.
- Pneumococcal vaccine should be given to all these patients before elective splenectomy—3 weeks prior to surgery; 3 weeks after surgery and later once in 5-6 years.
- If there are gallstones, cholecystectomy is done.
- Both splenectomy and cholecystectomy can be done through *laparoscopy.*
- Splenectomy for hereditary spherocytosis is not done before the age of 6 years.

Note:

- *Hereditary elliptocytosis* is an autosomal dominant condition where 90% of RBCs are elliptical. Mostly they are asymptomatic, if symptomatic splenectomy cures the condition.

IMMUNE HAEMOLYTIC ANAEMIA

Here IgG or IgM antibodies bind to erythrocyte antigens causing red cell destruction through complement and RE systems.

It can be:

- ***Alloimmune haemolytic anaemia*:** It occurs after exposure to allogenic erythrocytes during transfusion, pregnancy or transplantation.
- ***Drug-induced immune haemolytic anaemia*:** It is drug-induced antibody reaction for drugs like α methyl dopa, penicillins or 2nd generation cephalosporins. It occurs

Autosplenectomy can occur in sickle cell anaemia.

via new antigen formation with positive Coomb's test. Cessation of causative drug and steroid therapy will cure the disease.

- *Autoimmune haemolytic anaemia (AIHA*): Here there is Development of IgG and IgM antibodies that bind to RBCs which are identified by Fc receptors of macrophages and RE cells causing phagocytosis and destruction of red cells. Two types of antibodies are:
    - *Common warm antibodies*: They react at 98.6°F. Often it is associated with CLL. In classical type, platelets are normal. Evan's syndrome is combination of AIHA and ITP. Coomb's test is positive (95% cases). Clinical features are of any haemolytic anaemias like palor, jaundice, splenomegaly (50%), and gallstones (25%). Longterm prednisolone is the treatment of choice. Failure to respond after long-term treatment is an indication for splenectomy. 80% of patients benefit with splenectomy.
    - *Less common cold antibodies (Cold agglutinin syndrome)*: It is treated by avoiding exposure to cold; folic acid; chlorambucil; cyclophosphamide and plasmapheresis. Splenectomy is not beneficial in this condition.

THALASSAEMIA (Mediterranean Anaemia/ Cooley's Anaemia/Erythroblastic Target Cell Anaemia)

- It can be α, β and γ thalassaemia depending on defect in the synthesis of particular peptide.
- *Beta thalassaemia* is commonest. There is decrease in Hb-A and persistence of Hb-F. Homozygous, thalassaemia major is commonest type. Heterozygous, thalassaemia minor also can occur.
- Intracellular *Heinz bodies are typical*.
- Chronic anaemia, jaundice and splenomegaly are the features. Major type presents in first year of life with retarded growth, frontal bossing and prominent malar bones. Leg ulcers, recurrent infections, splenic infarction, pleural effusion, crisis, gallstones (25%) are other features.
- *Complications* are haemosiderosis, diabetes mellitus, pancreatitis, cirrhosis of liver, intractable sepsis and aplastic crisis.
- Haemoglobin electrophoresis, peripheral smear, LFT, bone marrow study and U/S abdomen are the investigations required.
- Regular blood transfusions, splenectomy are the treatment options.

SICKLE CELL DISEASE

- It is hereditary haemolytic anaemia seen commonly in blacks wherein HbA is replaced by *HbS* leading to formation of *crescent shaped* red cells which is deformed and more prone for trapping in spleen and destruction. Under low oxygen tension, HbS undergoes crystallisation causing elongated and deformed red cells. It increases the blood viscosity and causes stasis in circulation. Splenic micro infarcts are common causing initial splenomegaly and later autosplenectomy and calcification.
- Because of autosplenectomy patient is more prone for infection by pneumococcus and other organisms due to reduced production of antibodies.
- Patients are commonly asymptomatic.
- It is common in Africa. Patients in India have high HbF which protects them from developing symptoms.
- Anaemia, pain abdomen, leg ulcers are the usual features.
- Cerebral, pulmonary and mesenteric infarctions can occur which may be often life threatening.
- Peripheral smear and electrophoresis are diagnostic. U/S abdomen is needed to see spleen and for gallstones.
- *Treatment* is sodium cyanate (prevents sickling of HbS); hydration; partial exchange transfusion, antibiotics, symptomatic therapy by folic acid. Splenectomy has only limited role in initial sequestration stage.

IDIOPATHIC (IMMUNE) THROMBOCYTOPENIC PURPURA (ITP)

- It is development of *antiplatelet antibodies*, (IgG) which damage patient's own platelets. These platelets get sequestered earlier and faster in the spleen than normal causing thrombocytopenia. Spleen is the source of antiplatelet antibody production and destruction of formed platelet—antiplatelet antibody complex (by macrophage phagocytosis).
- Low platelet count, a normal bone marrow and absence of other causes of thrombocytopenia are the features. Bone marrow megakaryocytes are normal or increased but there is relative marrow failure in terms of compensatory platelet production for more destruction.
- In adult it is common in females (70%) who are young below the age of 40 years (70%). Chronic type is common in adults.
- In children it is equal in both sexes. Acute is common in children. Spontaneous remission (80%) is common. In girls it may become chronic continuing to adolescent period.
- Platelet count above 50,000/mm^3 usually will not cause spontaneous bleeding and undue bleeding is not common with invasive procedures. So specific therapy is not indicated. Regular platelet count estimation is needed.
- Regular careful observation is done clinically and haematologically for count between 30,000/- 50,000/mm^3 if there is no bleeding. If any spontaneous bleeding occurs or any invasive procedure is needed then platelet count should be corrected with steroids, platelet transfusion. With steroid/ prednisolone therapy count becomes more than 50,000/ mm^3 in 1-3 weeks.

Types

1. *Acute ITP:*
    - Initiated after viral infection.
    - Common in children (90%).
    - Spontaneous remission is common.
2. *Chronic ITP:*
    - Common in adults (90%).
    - Gradual, may be present for years.

Clinical features

- Common in young women (3:1 ratio)
- Purpuric patches in skin and mucous membrane (most common presenting sign)
- Epistaxis
- Menorrhagia
- Haematuria, haemarthrosis (rare)
- GIT bleeding
- Intracranial haemorrhage—2%; dangerous
- Tourniquet test is *positive* (*Hess test*)

- Purpuric and petechial patches are common in buttocks and limbs as these areas are more dependent having more vascular pressure. These patches and petechiae are mild or moderate.
- Splenomegaly is present in 25% of cases.
- After applying sphygmomanometer cuff and inflation (just below systolic pressure for 10 minutes), cubital fossa is observed for petechial haemorrhagic spots. More than 20 petechial spots in 3 cm circled area are significant—*Hess test*.

Differential Diagnosis

- Other causes for purpura—pregnancy, preeclampsia, drugs like heparin, quinidine, sulphonamides, HIV, rubella, infectious mononucleosis, myelodysplasia, congenital thrombocytopenia, thrombotic thrombocytopenic purpura, uraemia.



Figs 13.12A and B: Purpura spots in legs in case of ITP.

- Increased capillary fragility.
- Bone marrow suppression due to aplastic anaemia.
- Chemotherapy.
- DIC.
- Autoimmune diseases, SLE.

Investigations

- Bleeding time is increased times.
- Clotting and prothrombin time are normal.
- Platelet count is decreased.
- Bone marrow biopsy reveals increased megakaryocytes.
- Usually anaemia and neutropenia is not observed.
- U/S shows splenomegaly only in 25% cases.

Note:

Positive Hess test is formation of > 20 purpuric patches in an area of 3 cm diameter.

Treatment

Drugs

- In children, spontaneous regression occurs in 75% of cases after one attack.
- Short courses of *steroids* or *azathioprine* hastens the recovery.
- In adults, treatment is indicated when platelet count is < 30000/mm^3.
- Glucocorticoid—1 mg/kg is given. Response to treatment is seen within a week. Prednisolone 10 mg/day for 6 weeks is given. Response to steroid (prednisolone—1 mg/kg body weight) therapy showing complete remission is 25%.
- Danazol 200 mg TID decreases IgG receptor on phagocytes causing lesser degradation of platelets.
- Vincristine 2 mg per week for 6 weeks.
- IV immunoglobulin 0.4-1.0 g/kg × 5 days (action like danazol). It is very useful in acute bleed, in preparing the patient for surgery, in conducting delivery in pregnancy with ITP. Dose should be given for at least two days before taking up for surgery. It is also used in preparing ITP patient for therapeutic splenectomy.
- Anti-Rh D antibodies.

Indications for admission

- Platelet count less than 30,000/mm^3
- Platelet count less than 50,000/mm^3 showing bleeding episodes/mucosal bleed
- Risk factors association like existing peptic ulcer, hypertension.
- Life threatening haemorrhage

Indications for splenectomy

- Relapsed severe cases after treatment with steroids—for 6 weeks
- Girls attaining menarche
- ITP persisting even after 6-9 months refractory to treatment
- In 2nd trimester pregnancy, with platelet count <10000/mm^3 and severe bleeding problems

For every minute you are angry you lose sixty seconds of happiness.

- Recurrence after stopping/tapering steroids
- Profound GI bleed and intracranial bleed
- ITP with persistent platelet count below 10,000/ mm^3 for 6 weeks whether bleeding present or not, ITP with only transient response to drugs for 3 months with platelet count less than 30,000/mm^3

Note:

- Splenectomy is not indicated in nonbleeding ITP for 6 months with platelet count above 50,000/ cu mm^3.
- Response rate is 80%; it is usually achieved in first 10 days of splenectomy.
- Relapse of ITP after splenectomy is 10%. It is probably due to hepatic sequestration of platelets in such patients or presence of accessory spleens (10% of such cases). Such patients are difficult to treat. They need prednisolone, azathioprine (single agent—needs 4 months to achieve initial response in such patients), cyclophosphamide (single drug).
- Presence of accessory spleen is confirmed by blood smear and radionuclide imaging but exact anatomical number and location of accessory spleen is often difficult to identify preoperatively. Thorough exploration for possible all sites of splenunculi should be done to achieve good success rate.
- 15% of HIV patients develop ITP; splenectomy response is good in these patients; splenectomy does not progress HIV status.

Surgery

- *During surgery and in emergency,* fresh blood transfusions or platelet transfusions are required. Sometimes anti-platelet immune response is temporarily blocked by IgG transfusion so to allow the platelet count to rise at the time of surgery or in cases of severe bleeding or in pregnancy.
- Accessory spleen should be identified and removed.
- In 7 days platelet count raises to more than 100000/ cu mm.
- Laparoscopic approach is ideal in elective splenectomy for ITP.

Treatment for ITP

- Methylprednisolone IV for 3-5 days only
- Oral prednisolone tablets—drug of choice for 6-12 weeks
- IV immunoglobulin 0.4-1.0 gm/kg/day for 5 days only. It competes with antibodies
- Vincristine 2 mg/week for 6 weeks
- Danazol 200 mg tid
- Anti-Rh D antibodies
- Azathioprine
- Splenectomy
- FFP, platelet concentrate, fresh blood transfusions.

THROMBOTIC THROMBOCYTOPENIC PURPURA (TTP)

It is an idiopathic disease associated with bone marrow transplantation, drugs like penicillin, mitomycin, cyclosporine.

Main features are (pentad:

1. Microangiopathy haemolytic anaemia.
2. Thrombocytopenia.
3. Fever.
4. Neurological disturbances.
5. Renal dysfunction.

Features and management

- Here only arterioles and capillaries of microcirculation are involved. Venules are not involved. Platelet microthrombi, endothelial proliferation are the pathological features.
- Anaemia, platelet trapping in the spleen and thrombocytopenia are typical.
- Altered mental status, neurological deficits and renal failure are common.
- Plasmapheresis improves the survival which is the main treatment.
- Laparoscopic splenectomy is done only to reserved patients.

Felty's syndrome is chronic rheumatoid arthritis, mild leukopenia and splenomegaly.

SPLENECTOMY

Indications for Splenectomy

1. Trauma.
2. In radical gastrectomy—removed "*en bloc*" with stomach.
3. Staging laparotomy in case of Hodgkin's lymphoma.
4. Hereditary spherocytosis and other haemolytic anaemias.
5. Idiopathic thrombocytopenic purpura (ITP).
6. Portal hypertension with variceal bleeding.
7. Tuberculosis of spleen.
8. Others:
    - Gaucher's disease.
    - Chronic myeloid leukaemia.
    - Felty's syndrome.
    - Carcinoma of tail of the pancreas during distal pancreatectomy.
    - Schistosomiasis.
    - Splenic artery aneurysm.
    - Splenic infarction.
    - Cystic disease of spleen.
    - Splenic tumours.

Indications for splenectomy

Benefit is maximum/very good	***Benefit is equivocal***	***Benefit may be there/low***
• Splenic injury • Hereditary spherocytosis • ITP • Splenic cysts • Splenic tumours • Hypersplenism • Segmental left sided portal hypertension	• AIHA (autoimmune haemolytic anaemia) • Tropical splenomegaly • Felty's syndrome	• Thalassaemia • CML • Gaucher's disease • Hodgkin's lymphoma for staging laparotomy • Sickle cell anaemia

Procedure

- Incision—left paramedian or left subcostal or in case of large adherent spleen left thoracoabdominal approach.



Figs 13.13A and B: Incision for open splenectomy – left subcostal. Often in a massive spleen or adherent spleen incision need to be extended to opposite side and towards xiphisternum.

- Lieno-renal ligament and short gastric vessels are ligated. Splenic vessels are ligated at the hilum of spleen. Spleen is removed. Abdomen is closed after placing a drain *in situ*. Presently, drain is *indicated* only if there is injury to tail of pancreas during splenectomy.
- *Presently laparoscopic splenectomy is becoming popular.*
- Preoperative splenic artery embolisation is beneficial in massive spleens.

Complications of Splenectomy

- Haemorrhage—mainly from short gastric vessels. Re-exploration and control of bleeding is needed.
- Gastric dilatation.



Fig. 13.14: Splenic vessels should be ligated individually securely with double ligatures in large spleen during splenectomy.

Fig. 13.15: Laparoscopic splenectomy is also a good alternative in many splenectomies when splenomegaly is not massive. It is not useful in massive spleens and trauma.

- Haematemesis due to mucosal congestion following ligation of short gastric vessels.
- Left sided pleural effusion and left basal atelectasis (left lobe atelectasis is the commonest complication) (30%).
- Left subphrenic abscess.

Efforts and energies should be consistent, constructive and compassionate.

- Pancreatitis following damage to tail of the pancreas and pancreatic fistula (3%).
- Haematologic changes: Rise in WBC and platelet count, rise in abnormal RBCs and RBC bodies.
- Gastric fistulas.
- Left sided colonic injury.
- Infection—Postsplenectomy septicaemia, OPSI—most dangerous.
- Portal vein thrombosis can occur.
- *DVT as a late sequelae* after splenectomy is often dangerous. Risk is 4 times more than in non-splenectomised people and so also pulmonary embolism. It is better to put them on long term small dose of *aspirin* to reduce the incidence of thromboembolism.

OVERWHELMING POSTSPLENECTOMY INFECTION (OPSI)

- As there is reduced IgM, tuftin, properdin and other antibodies, phagocytosis of encapsulated bacteria is defective. So the postsplenectomised patient is more prone for *Pneumococcal septicaemia* (commonest), *N. meningitides, H. influenzae, Babesia microti* infections. Risk is more in patients on chemotherapy, radiotherapy and haemolytic diseases.
- Incidence is 4%.
- Common in first two years after splenectomy. But it can occur any time. Risk persists for lifetime.

Clinical Features

- Prodromal phase—fever, chills, sore throat.
- Hypotension, shock.
- DIC.
- Respiratory distress, coma, death.

Mortality for fully developed OPSI—50-70%.

Prevention

- *Pneumococcal vaccine* should be given to all splenectomised patients. Polyvalent pneumo-vac is given 2-3 weeks prior to surgery and soon after recovery from surgery and it is repeated once in 5 years (Given to patients older than 2 years).
- Other vaccines advised are meningococcal vaccine (only to those who travel with high-risk), *H. influenzae* 'B' vaccine (to all whatever the age, once in 10 years).
- In malaria endemic areas, antimalarial prophylaxis is given for patients after splenectomy.

Treatment of OPSI

- ❖ Antibiotics like Cefoperazone, Ceftazidime, Amikacin
- ❖ Ventilatory support—ICU care
- ❖ Blood transfusion
- ❖ Immunoglobulin transfusion
- ❖ Nutrition (TPN) and maintaining of urine output

Prevention of OPSI

- ❖ Life long prophylaxis using benzathine penicillin 12-24 lac units—controversial in adults
- ❖ Pneumococcal vaccine given 2-3 weeks prior to splenectomy—70% protection
- ❖ *H. influenzae* B type vaccine
- ❖ Meningococcal vaccine is given only to high-risk groups, as its effects are short term. So it is not routinely given
- ❖ *Note: Protection by vaccine is not completely guaranteed*

Note:

- OPSI is more common when splenectomy is done for malignancy or haematological diseases or done in young individuals.
- Usage of prophylactic penicillin (benzathine) is controversial in adult even though it is beneficial in children up to 16 years.
- OPSI can occur at any time after splenectomy. Drugs like erythromycin, amoxicillin are also used as prophylactic agents.
- Mortality in fully developed OPSI (hypotension, DIC, MODS) is 60%—very high.
- Patients who survived after OPSI with therapy may develop residual problems like – gangrene of limbs, deafness, meningitis, mastoid osteomyelitis, heart valve destruction.
- 7% of OPSI cases have S pneumonia sepsis. Others are—*N. meningitidis*, *H. influenzae*, *Capnocytophaga canimorus* after dog bite.
- *PPV 23* is the commonest vaccine used. Revaccination is done once in 5 years; decline in pneumococcal antibody level may be the criteria for revaccination.
- Preservation of *25% of spleen* is sufficient to protect against pneumococcal infection. So partial splenectomy is definitely helpful.
- Splenic autotransplantation into the omental pouch is under trial at present to reduce the chance of OPSI.

SPLENIC ARTERY ANEURYSM

- Most common intraabdominal site for aneurysm after abdominal aorta.
- Most common in women, due to atherosclerosis.
- Congenital splenic artery aneurysm can occur.
- Splenic artery pseudoaneurysm (10%) can occur after an attack of acute pancreatitis which may cause life threatening rupture.



Fig. 13.16: Splenic artery aneurysm. It is the commonest site of aneurysm in the abdomen after aorta.

- Rupture of splenic artery may be intraperitoneal or into the stomach, colon and intestine. Calcified aneurysm rarely ruptures.
- Plain X-ray shows calcified lesion in 70% of cases.
- Contrast CT, angiogram are needed.
- Indication for surgery:
  - >2 cm diameter.
  - Symptomatic aneurysm.
  - Anticipating pregnancy.
  - Aneurysm identified during pregnancy should be operated before 3rd trimester.

Treatment

- Splenectomy with ligation of artery proximal to aneurysm.
- Splenic artery embolisation under radiological guidance is also beneficial.

SPLENIC ABSCESS



Fig. 13.17: Splenic abscess due to tuberculosis.

- It is uncommon but potentially fatal.
- Incidence is 0.7%.
- **Precipitating factors**:
  - Endocarditis is commonest focus.
  - AIDS.
  - Polycythaemia.
  - Malignancy.
  - Sickle cell disease.
  - Splenic vein thrombosis.
  - Trauma.
  - Drug abuse.
  - Typhoid, osteomyelitis, puerperal sepsis, pancreatitis, otitis media.

Organisms responsible: *Staphylococcus*, *Streptococcus*, *Enterobacter*, *E. coli, Proteus, Klebsiella, Candida albicans*, *Mycobacterium tuberculosis* in developing countries.

Clinical features

- Fever
- Pain in left hypochondrium
- Pain in left side of chest
- Left sided pleural effusion
- Spleen when palpable is tender
- Single or multiple abscesses
- Need not move with respiration

Investigation

Ultrasound, ESR, chest X-ray, CT scan, blood culture.

Treatment

- High dose antibiotics has to be started.
- ATT in case of tuberculosis.
- Ultrasound/CT scan guided aspiration of abscess is done.
- Splenectomy.



Fig. 13.18: CT scan showing abscess in the spleen.

Note:

- Splenic abscess can rupture causing peritonitis and left subphrenic abscess.
- Splenic abscess has 80% mortality in immunocompromised patients and 20% in an otherwise normal individual.
- 2/3rd of splenic abscesses in adults are single and 1/3rd are multiple; in children 1/3rd are single, 2/3rd are multiple.
- Solitary abscess responds well for guided aspirations; whereas multiple abscesses need splenectomy.

HYPERSPLENISM

It is overactivity of spleen causing pancytopenia with more of hypercellular bone marrow.

Causes

- Primary hypersplenism.
- Portal hypertension.
- Malaria, kala-azar.

- Schistosomiasis.
- Tuberculosis.
- Myeloproliferative disorders.

Hypersplenism often requires splenectomy.

Note:
- Commonest primary splenic neoplasm is haemangioma
- *Littoral cell angioma* is rare splenic tumour
- Lymphangioma, inflammatory pseudotumours are rare splenic tumours
- Hodgkin's lymphoma commonly involves spleen
- Secondaries in spleen are rare. Occasionally spread can occur from lungs, stomach, pancreas, breast, melanoma
- Primary malignant splenic tumours are exceedingly rare. Angiosarcoma is the most common primary tumour
- *Wandering spleen* is due to failure to form suspensory ligaments of spleen so that the spleen is *not* fixed in position. It is due to failure of dorsal mesogastrium to fuse with the posterior abdominal wall. It shows long splenic pedicle. It is prone for torsion and recurrent ischaemia. It is common in females. CT scan is diagnostic. If there is no ischaemia, *splenopexy* is done; if there is ischaemia which is confirmed by absence of perfusion in CT scan, splenectomy is done

SPLENIC CYST

Splenic cysts can be –

1. ***True primary cyst (20%).***
   It can be -
   - *Non-parasitic* [simple congenital cysts, epidermoid cysts (75% of non-parasitic cysts)]. It is common in 3rd decade, usually lined by squamous epithelium. Even though they are truly benign without malignant potential, they often show +ve for Ca 19/9 and CEA. Usually they are asymptomatic, but may present with splenic mass with pain, chest pain and left shoulder pain usually when cyst attains more than 8 cm in size. Occasionally sepsis, rupture and bleeding in a cyst can occur.
   - *Parasitic* (hydatid) – one should look for associated liver hydatids. CT abdomen confirms the diagnosis. It is treated with splenectomy; care should be taken not to spill or rupture during surgery.
2. ***Pseudocyst/secondary cysts*** (80%) are due to old trauma, malaria, tuberculosis, infectious mononucleosis, old parenchymal haematoma and syphilis. They are not epithelial lined; they are smooth, unilocular, thick walled. Initially treatment is guided percutaneous drainage or partial splenectomy. Splenectomy is done when entire spleen is involved with pseudocyst.

Chapter 14 Pancreas

CHAPTER OUTLINE

- Anatomy
- Serum Amylase
- Magnetic Resonance Cholangiopancreatography
- Pancreatitis
- Acute Pancreatitis
- Complications of Acute Pancreatitis
- Pseudocyst of Pancreas
- Chronic Pancreatitis
- Pancreatic Tumours
- Exocrine Pancreatic Tumours
- Carcinoma Pancreas
- Endocrine Pancreatic Tumours
- Insulinomas
- Gastrinomas
- Glucagonomas
- Zollinger–Ellison Syndrome
- Cystic Fibrosis
- Annular Pancreas
- Ectopic (Accessory) Pancreatic Tissue
- Pancreatic Divisum
- Pancreatic Calculus
- Pancreatic Ascites
- Pancreatic Fistulae
- Pancreatic Abscess
- Pancreatic Necrosis
- Pancreatic Trauma
- Cystic Lesions of Pancreas
- Exocrine Pancreatic Disease

Pancreas is also called as *abdominal tiger.*

ANATOMY

Pancreas is an elongated retroperitoneal organ; 15-20 cm in length; lies against L_1–L_2 vertebra. It lies posterior to stomach, separated by lesser sac.

Parts

It is divided into head, neck, body, tail.

- The head lies in the concavity of duodenum and tail reaches the hilum of the spleen.
- The posterior surface of the neck of pancreas is related to terminal part of superior mesenteric vein and beginning of portal vein.

Ducts of Pancreas

1. Main duct of pancreas (*Duct of Wirsung*): It begins in the tail of pancreas and runs on the posterior surface of the body and head of pancreas, receives numerous tributaries at right angle along its length (*Herring bone pattern*).

   It joins the bile duct in the wall of the second part of duodenum to form hepatopancreatic ampulla *(of Vater*) and opens on the summit of major duodenal papilla (8-10 cm from pylorus).



Fig. 14.1: Ducts of pancreas.

2. Accessory pancreatic duct *(Duct of Santorini):* It begins in the lower part of the head and opens into the duodenum at minor duodenal papilla (6-8 cm from the pylorus).


Hepatic artery
Coeliac artery
Splenic artery
Gastro-duodenal artery
Superior pancreatico-duodenal artery
Superior mesenteric artery
Arteria pancreatica magna
Inferior pancreaticoduodenal artery

Fig. 14.2: Arterial supply of pancreas.

Blood Supply of Pancreas

1. Pancreatic branches of splenic artery.
2. Superior pancreaticoduodenal artery.
3. Inferior pancreaticoduodenal artery.

Venous drainage is into portal vein.



Fig. 14.3: Venous drainage of pancreas.

Nerve Supply

Parasympathetic supply is from vagus and sympathetic innervation is from splanchnic nerves.

Functions

- *Exocrine* part secretes pancreatic juice which helps in digestion of proteins, carbohydrates and fats.
- *Endocrine* part constitutes islets of pancreas which is distributed more numerous in tail of pancreas.
  β cells of islets secrete insulin.
  α cells secrete glucagon.

Normal pancreatic juice is colourless bicarbonate rich fluid containing around 15 gram of protein in total, 2.5 litres secretion/day. It alkalises duodenal content and helps digestion. Inactive proenzymes secreted into the duodenum from pancreatic juice are activated by trypsin in duodenum. Amylase and lipase can also be secreted in active forms. Basal secretion of these enzymes is low at rest; rapidly increases by hormonal and neural stimulation. It is controlled by secretin (cAMP) and cholecystokinin (phospholipase C, calcium). Protein part of the juice is secreted by *acinar cells*. *Duct cells* secrete fluid and electrolytes. Pancreatic secretion is very low in resting phase. During eating, cephalic phase stimulates 10% of pancreatic secretion through peripherally mediated acetylcholine; gastric phase stimulates further 15% of pancreatic secretion through gastrin release and vagal stimulation; finally in main intestinal phase, 75% of the pancreatic juice is secreted by release of secretin due to duodenal acidification, and by release of bile and cholecystokinin following the entry of fat and proteins in duodenum.

SERUM AMYLASE

- Normal value is up to 200-250 Somogyi units.
- It increases more than 1000 units or a rising titre is very significant in acute pancreatitis.
- Its half life is 24 hours.
- It is not very sensitive because it also increases in other conditions:
  - Salivary gland diseases.
  - Mesenteric ischaemia.
  - Ruptured aortic aneurysm.
  - Intestinal obstruction.
  - Ectopic gestation.
  - Salpingitis.
  - Perforated duodenal ulcer.

Types

- ***Amylase isoenzyme-P*** is specifically increased in pancreatitis.
- In other conditions, ***Amylase-S*** is commonly increased.

- It can be analysed with other proteolytic enzymes like lipase, elastase which are more relevant.
- In peritoneal tap, if amylase level of peritoneal fluid is more than serum amylase, then it is significant.

Note:
Amylase level in pseudocyst fluid is very high.

- Magnitude of amylase elevation is not related to severity of the pancreatitis. It increases once symptoms appear for 12-24 hours then decreases in 6 days. Persistent elevation suggests complications like pseudocyst, ascites and abscess formation.
- 10% cases of severe pancreatitis with necrosis show normal serum amylase level. This is due to necrosis of most of the acinar cells retaining hardly any functioning cells at time.
- Rise in pancreatic amylase will be very high in comparison with nonpancreatic causes of rise where it is only 2-3 times the normal.
- Raised urinary amylase level persists for longer period then serum amylase level.
- Amylase enters the lymphatics and circulation from the basal part of acinar cells and also, weakened intercellular adhesions in pancreatitis allow amylase to seep into the space to enter circulation.
- Circulating amylase inhibitors often when present, mask the true amylase level in pancreatitis.
- Occasionally amylase binds with large abnormal circulating albumin like protein which cannot be cleared normally causing false raise in serum amylase level (false positive) even though there is absence of pancreatitis. This *macroamylasaemia* is 0.5% common.

MAGNETIC RESONANCE CHOLANGIO-PANCREATOGRAPHY (MRCP)

It is a non-invasive diagnostic method using magnetic field and energy as resonance.

T_1 weighted images are used for pancreas.

T_2 weighted images are used for biliary tree.

Both images are used to see invasion and adjacent structures.

Advantages

- It is non-invasive.
- It gives equal or better imaging than ERCP.
- Pancreatic divisum or annular pancreas are identified easily by MRCP.
- Ductal dilatation in chronic pancreatitis and visualization of duct beyond stricture is possible.
- Islet tumours are better visualised and diagnosed by MRCP.

Disadvantages

- Availability.
- It is only diagnostic. Not therapeutic (ERCP is both diagnostic as well as therapeutic).
- Costly.

PANCREATITIS

> *We learn that pain was an early symptom in nearly one-half of the cases; that it was usually severe, and might be intense, and was to be found in the abdomen or lower chest.…The appearances found after death are conspicuously the hemorrhage within and near the pancreas.…It is evident that all treatment, at the onset, can be nothing but palliative.*
>
> —**Reginald Heber Fitz,** 1889

Pancreatitis is inflammation of the pancreas acute, chronic or relapsing which may lead into complications. It is one of the most devastating conditions in the abdomen.

Classification

I. *Marseilles' classification*:
  1. Acute pancreatitis.
  2. Acute relapsing pancreatitis.
  3. Chronic relapsing pancreatitis.
  4. Chronic pancreatitis.

  Acute means acute inflammatory changes which are reversible.

  Chronic means chronic continuous inflammatory changes which are morphologically irreversible.

II. *Trapnell's aetiological classification*:

Major causes

- Biliary tract disease 50%—stones—common cause
- Alcoholism 25%

Other causes

- Trauma
- After biliary, gastric, splenic surgery, ERCP
- Hyperparathyroidism
- Hypercalcaemia, hyperlipidaemia
- Diabetes
- Porphyria
- Drugs: Steroids(?), INH, diuretics (thiazides), septran, azathioprine, 5-amino salicylic acid, estrogens, tetracycline, valproic acid, petamidine – 5%
- Viral infections (mumps, coxsackie)
- Autoimmune diseases
- Vascular diseases
- Idiopathic
- Scorpion venom—Common in Trinidad
- Biliary ascariasis, Clonorchis sinensis
- Mycoplasma pneumoniae
- Infectious mononucleosis
- Pancreatic divisum

ACUTE PANCREATITIS

Acute pancreatitis is the development of acute inflammation of the normally existing pancreas. It may be *first* attack or *relapsing* attacks with an apparently normal gland in between. ***Biliary tract disease*** is the ***commonest*** cause for acute pancreatitis.

Pathogenesis

- *Present concept* is the biliary stone induced *pancreatic ductal* obstruction and ductal hypertension as etiological factor (*Pancreatic duct obstruction* occurs due to biliary tract stones (*commonest*), duodenal ulcer, duodenal Crohn's, periampullary diverticulum/tumour, trauma, pancreatic duct stricture, pancreatic divisum, ascariasis, Clonorchis sinensis).
- OR *alcohol* causes direct toxicity, hypersecretion of gastric and pancreatic juices, reflux, plugging of pancreatic proteins, injury by release of free radicals like superoxide and hydroxyl, spasm of Oddi and stimulates trypsinogen.

All these *aetiological* factors

↓

Either cause spasm of sphincter of Oddi and lead into the parenchyma (*common channel theory*), OR causes increased secretion of pancreatic enzymes

↓

Trypsinogen gets activated forming trypsin which activates other enzymes.

↓ ↓

Proelastase to elastase. | *Prolipase to lipase.*

↓ ↓

Causes capillary rupture. | Metabolises triglycerides to glycerol + fatty acids and fatty acids combine with calcium forming saponified fat.

↓ ↓

Sequestered fluid, saponified fat, blood, toxins all together forms a ***chicken broth fluid.***

Surgery is a painful procedure to relieve the pain.

↓

Lecithinase, amylase and factors like lysolecithinase, prostaglandins, bradykinins, kallikrein, myocardial depressant factor, free radicals, cytokines, tumour necrosis factor, and platelet activation factor are also released to have local and systemic effects.

↓

Infection occurs causing bacteraemia, septicaemia.

↓

Large volume of fluid sequestration occurs causing *hypovolemic shock.*



Figs 14.4A and B: Features of acute pancreatitis with necrosis in the omentum and over pancreas; with haemorrhage.

- Toxins released may lead to *acute tubular necrosis and so acute renal failure.*
- Left sided diaphragm gets elevated and *left sided pleural effusion* occurs.
- Lecithinase reduces the surfactant in the alveoli of lung, and infection leads to pulmonary insufficiency, *ARDS and respiratory failure.*
- Because calcium is utilised for saponification, *hypocalcaemia* sets in.
- Diffuse oozing in pancreatic bed occurs which utilizes platelets and causes *disseminated intravascular coagulation (DIC).*
- In severe cases, extensive necrosis with haemorrhage occurs causing *acute haemorrhagic necrotising pancreatitis (Fulminant pancreatitis), which has got a high mortality.*
- Here enzymes seep across the retroperitoneum causing haemorrhagic spots and ecchymosis in the flanks ***(Grey Turner's sign)***, or through falciform ligament causing discolouration around the umbilicus ***(Cullen's sign)***, umbilical black eye or below the inguinal ligament (***Fox sign***).
- SIRS and later MODS set in.
- *Sequence of events*:

Acute oedematous →→→→→→Severe acute pancreatitis → Acute sterile necrosis → Acute infected necrosis
pancreatitis

↓ ↓ ↓ ↓

Resolution/recovery/complications (rare)
Less mortality

Local or systemic complications with high mortality.
(pseudocyst/abscess/ARDS/MODS/haemorrhage, etc.)

- **Moynihan described acute pancreatitis as** *"The most terrible of all the calamities that occur in connection with abdominal viscera".*



Fig. 14.5: *Grey-Turner's sign* in a patient with acute pancreatitis.

Effects of alcohol on pancreas

- Hypertriglyceridaemia, fatty acids and ethyl ester metabolites → pancreatic injury
- Formation of pancreatic juice which contains high enzymes but low enzyme inhibitors → enzyme activation within pancreas; precipitation of proteins, intraductal plug formation, ductal hypertension and obstruction → pancreatic injury
- Formation of O_2 free radicals inside the pancreas → pancreatic injury
- Direct pancreatic acinar injury
- Sphincter of Oddi spasm by alcohol leading into ductal obstruction
- Repeated subclinical acute pancreatitis causes fibrosis and chronic pancreatitis

Note:

- *Hereditary pancreatitis*: In normal individuals small amount of spontaneous trypsinogen activation into trypsin occurs in pancreas which is further prevented and protected by trypsin inhibitors. In hereditary pancreatitis genetic mutation causes defective trypsin inhibitors and trypsin becomes resistant to trypsin inhibitors leading into high concentration of intrapancreatic active trypsin which activates all other enzymes leading into pancreatitis. Here even though acute pancreatitis can occur; this is commonly subclinical leading into chronic pancreatitis.

- *Autoimmune pancreatitis*: It can be associated with primary sclerosing cholangitis, Sjögren's syndrome, biliary cirrhosis. *Lymphoplasmacytic autoimmune pancreatitis* is a condition which causes high levels of circulating IgG_4, pancreatitis, bile and pancreatic ductal strictures (*double duct sign* like mimicking the pancreatic cancer), pancreatic head mass.
- ERCP, major surgeries activate pancreatic enzymes causing acute pancreatitis.
- Hypercalcaemia, hyperlipidaemia type I, IV, V can cause pancreatitis. It is due to activation of digestive enzymes, blockage of pancreatic microcirculation causing pancreatic ischaemia.
- *Idiopathic pancreatitis (20%)*: Even though it is due to some unidentified cause, it is probably due to gallbladder *sludge* or microcrystals which often can be very well controlled or further prevented by cholecystectomy and sphincterotomy. It also can be due to malfunction of sphincter of Oddi which is treated by sphincterotomy and pancreatic septotomy. Some genetic cause is also postulated.
- *Colocalisation hypothesis*: Trypsinogen within the cytoplasmic vacuoles of acinar cell gets colocalised into the lysosomal hydrolases, commonly cathepsin B to activate into trpsin which in turn activates other intracytoplasmic digestive enzymes leading into intrapancreatic inflammation and pancreatitis.
- *Infection* occurs by *bacterial translocation across gut* due to altered mucosal barrier.

Atlanta classification

1. Acute oedematous pancreatitis (80%): Milder form, mortality is <1%
2. Acute necrotising pancreatitis (20%): Characterised by pancreatic and peripancreatic necrosis. Mortality is ≈ 15% - 30%

Present Classification of Acute Pancreatitis

- *Interstitial acute pancreatitis* with mortality less than 1%.
- *Necrotizing pancreatitis*.
  - Sterile necrosis with mortality 10%.
  - Infected necrosis with mortality 30-40%. It is confirmed by CT guided aspiration and Gram's stain. When confirmed, needs pancreatic necrosectomy.

Note:
In *Ulm classification* pancreatic abscess and pseudocysts are also included.

Organisms Involved

Infection is commonly polymicrobial (60%). It may be from gallbladder, colon or small bowel via transmural migration or by haematogenous spread. Infection rate in one week is 24% and in 3 weeks it is 70%.

- *E. coli* (35%).
- Klebsiella (25%).
- Enterococcus (25%).
- Others—staphylococci, *Pseudomonas*, *Proteus*, *Enterobacter*, *Anaerobes*, *Candida* (10%).

Clinical Features

- Sudden onset of upper abdominal pain which is referred to back. Pain is severe, agonizing and refractory. Pain may be relieved or reduced by leaning forward.
- Vomiting and high fever, tachypnoea with cyanosis.
- Tenderness, rebound tenderness, guarding, rigidity and abdominal distension, severe illness.
- Often mild jaundice (due to cholangitis). Jaundice may also be due to bile duct disease / obstruction or cholestasis.
- Features of shock and dehydration.
- Oliguria, hypoxia and acidosis.
- Grey-Turner's sign, Cullen's sign, Fox sign.
- Haematemesis/malaena due to duodenal necrosis, gastric erosions, decreased coagulability/DIC.
- Hiccough when present is refractory.
- Ascites may be present. Paralytic ileus is common.
- Pleural effusion (20%), pulmonary oedema, consolidation, features of rapid onset ARDS is often observed.
- Neurological derangements due to toxaemia, fat embolism, hypoxia, respiratory distress can occur. It may be mild psychosis to coma.
- Occasionally haematemesis or melaena can occur.

Fluid, Metabolic, Haematologic and Biochemical Changes

- *Hypovolemia* due to diffuse capillary leak and vomiting causing raised haematocrit, blood urea, serum creatinine levels.
- *Hypoalbuminaemia* which is more revealed after fluid correction.
- *Hypocalcaemia* is either due to decreased albumin level or specific loss of ionized calcium. Hypocalcaemia due to reduced ionised calcium carries poor prognosis. Response of calcium reserve in bone to PTH is also reduced.
- Total count is raised with *neutrophilia. Thrombocytopenia*, raised FDP, decreased fibrinogen, prolonged partial thromboplastin time and PT—are common. DIC can develop later.
- *Hypochloraemic metabolic alkalosis* is common due to repeated vomiting.
- Reduced insulin secretion, increased glucagon and catecholamine secretion causes *hyperglycaemia*, more so in diabetic patients.
- *Hyperbilirubinaemia* may be due to biliary stone/obstruction or cholangitis or non-obstructive cholectasis.
- *Hypertriglyceridaemia* is common especially in hyperlipidaemic patients.
- *Methemalbuminemia*, when it occurs in acute pancreatitis indicates poor prognosis.

Clinical features are classified as:

- Mild attack
- Severe attack
- Fulminant attack

Working together is essential for success; even freckles would make a nice tan if they would get together.

Differential diagnosis

- Perforated duodenal ulcer
- Cholecystitis
- Mesenteric ischaemia
- Ruptured aortic aneurysm
- Ectopic pregnancy
- Salpingitis
- Intestinal obstruction
- Diabetic ketoacidosis

Investigations

- *Serum amylase* is very high (>1000 Somogyi units) or shows rising titre.
- *Amylase creatinine clearance* ratio is increased. It is - urine amylase/serum amylase X serum creatinine/ urinary creatinine X 100. Normal value is 1-4%. More than 6% signifies acute pancreatitis.
- *Serum lipase* more specific than amylase. Serum lipase level after rise persists for longer period than amylase. Pancreas is the only source unlike amylase, hence more specific.
- *Serum lactescence* (related to triglyceride metabolism)—Most specific in hereditary hyperlipidaemia or alcohol pancreatitis.
- Serum trypsin is the most accurate indicator but it is not commonly used.
- Trypsinogen activation polypeptide (TAP) assay in serum and urine reveals the severity of the acute pancreatitis. CRP (>150 mg/L) is also useful. Phospholipase A2, LDH levels are also often assessed.
- Liver function tests: Serum bilirubin, albumin, prothrombin time, alkaline phosphatase.
- Blood urea, serum creatinine.
- Blood glucose (hyperglycaemia is seen).
- Serum calcium level (hypocalcaemia occurs).
- Arterial PO_2 and PCO_2 level to assess pulmonary insufficiency (or ARDS).
- Urinary lipase estimation.
- Total count, haematocrit, platelet count, coagulation profile.
- Peritoneal tap fluid shows *high amylase* and protein level (very useful method). Lipase level in ascitic fluid is also useful.
- Plain X-ray shows
  - *'Sentinel loop'* of dilated proximal small bowel.
  - Distension of transverse colon with collapse of descending colon (*colon cut off sign)*.
  - Air-fluid level in the duodenum.
  - Renal halo sign.
  - Obliteration of psoas shadow.
  - Localized ground glass appearance.
- U/S abdomen.
- *Spiral CT is* better—gold standard. It is done after 72 hours. To look for oedema, altered fat and fascial planes, fluid collections, necrosis (non-enhancement area > 30% or 3 cm), bowel distension, mesenteric oedema and haemorrhage. CT guided aspiration (fluid should be sent for Gram's stain and bacterial culture); pigtail catheter insertion can also be done. If fluid culture shows bacterial growth with CT showing necrosis, it means it is infected necrosis and needs early pancreatic necrosectomy. CT guided aspiration and Gram's staining may need to be repeated.
- MRI, MRCP—should be done at a later date.
- ERCP is usually not done in acute phase.
- Chest X-ray for effusion and ARDS.
- EUS—to see necrosis, calcifications and to assess CBD.

Balthazar CT Scoring System (Emil J Balthazar, 1990)

CT grade:
- A—Normal pancreas—0
- B—Oedematous pancreatitis—1
- C—B+ mild extrapancreatic changes—2
- D—Severe extrapancreatic changes with one fluid collection—3
- E—Extensive/multiple extrapancreatic collections or gas bubbles in or adjacent to pancreas—4

Necrosis score:
- None—0
- < 1/3rd—2
- More than 1/3rd less than half—4
- More than half—6

CT severity index— CT grade + necrosis score
0—3, 4—6, 7—10.

Treatment

Treatment of acute pancreatitis

- Conservative, 70-90%
- Surgical treatment when indicated, 10-30%
- Management of complications like acute pseudocyst, abscess, fistula, haemorrhage; systemic complications like ARDS, renal failure, MODS



Fig. 14.6: CT picture showing features of acute pancreatitis.

Conservative Treatment

- Commonly opted.
- Rehydration is essential (250-400 ml / hour) as there is lot of fluid sequestration and 3rd space fluid loss. It is done by using ringer lactate, normal saline, dextrose saline, plasma and fresh blood transfusion/packed cells.
- Pain relief by pethidine and other analgesics. Morphine is not used as it causes spasm of sphincter of Oddi.
- In severe haemorrhagic episodes, fresh frozen plasma and platelet concentrate may be required in anticipation of DIC and haemorrhage.
- Nasogastric aspiration, urinary catheterisation to maintain and monitor urine output 50 ml hourly.
- Antibiotics like third generation cephalosporins, imipenem, meropenem, cefuroxime are used even though its role is not clear but it is commonly used to reduce the anticipated sepsis.

  Indications for antibiotics

  - In severe infected necrosis with proved culture.
  - Prophylactic antibiotic therapy, in severe pancreatitis.
  - In biliary pancreatitis with biliary stones and cholangitis.
  - Pancreatic abscess formation.
  - Clinically disease is rapidly progressing with deterioration.
  - No role of antibiotics in early pancreatitis.
  - Imipenem, cilastatin, cefuroxime are used.
- Calcium gluconate 10 ml 10% IV 8th hourly is given as patient will be hypocalcaemic.
- CVP line is essential to monitor, for rapid fluid therapy and for Total Parenteral Nutrition (TPN) using carbohydrate, amino acids, vitamins, essential elements.
- IV Ranitidine 50 mg 6th hourly or IV omeprazole 40 mg BD or IV pantoprazole 80 mg BD to prevent stress ulcers and erosive bleeding.
- Proper electrolyte management with monitoring is needed.

Mainly conservative treatment

1) (P) : **P**ain relief [pethidine, meperidine (no morphine)]
Protease inhibitors (aprotinin, antisnake venom, EACA etc.), **P**lasma
2) (A) : **A**ntibiotics (ceftazidime, cefoperazone, cefotaxime) imipenem
Anticholinergics (to reduce sphincter pressure)
3) (N) : **N**asogastric aspiration, **N**asal O_2
Nutritional support (TPN)
4) (C) : **C**alcium gluconate 10 ml 10% 8th hourly
Calcitonin
CVP line
5) (R) : **R**ehydration by IV fluids, plasma, blood
Ranitidine IV 50 mg 8th hourly
Respiratory support (ventilator)
Resuscitation when required
6) (E) : **E**ndotracheal intubation
Electrolyte management
7) (A) : **A**ntacids
8) (S) : **S**wan-Ganz catheter for CVP and TPN
Somatostatin and its analogue (*Octreotide*)

- It is always better to manage the patient in an ***intensive care*** set up so that when needed endotracheal intubation, ventilatory support, tracheostomy can be done as an emergency basis.
- In case of renal failure haemodialysis is required.
- Somatostatin/octreotide is often used to reduce pancreatic secretion.
- Anticholinergics, protease inhibitors and calcitonin are other agents used. Their efficacy is not sure.
- Steroid injection in initial phase of shock is beneficial. It is also useful in respiratory distress and ARDS.
- Nebulisation, bronchodilators are also tried.
- *Nasojejunal tube placement and feeding* should be started as early as possible once ileus subsides so that it reduces the infection rate by transmucosal migration of bacteria and it also improves nutritional status. During recovery period nasogastric feeding or jejunostomy feeding can be undertaken.
- Repeated calcium estimation, U/S examination to see the response is useful.
- Dopamine or low molecular weight dextran (to improve renal perfusion), somatostatin/octreotide (to reduce pancreatic secretion) are also often used.
- *Management of complications* like acute lung injury, atelectasis, renal failure, GI bleeding, metabolic encephalopathy, electrolyte deficiency as and when needed by repeated observation and evaluation.

Other measures:

Continuous monitoring, observation, maintaining good urine output 30 ml/hr. The required investigations are repeated to find out the response to treatment like serum calcium, total count, blood urea, creatinine, PaO_2, haematocrit, ECG.

Uses of octreotide

- Pancreatic surgeries
- Variceal bleeding
- Endocrine pancreatic tumours
- GI fistulas, pancreatic fistulas
- Dumping syndrome
- Carcinoid tumour, acromegaly
- Acute pancreatitis

Dose:

50 μg as loading dose IV

50 μg 1 hour in 5% dextrose as maintenance dose.

Surgery

Indications for Surgical Intervention (10% cases)

1. If condition of patient deteriorates in spite of good conservative treatment.
2. If there is formation of pancreatic abscess, or infected necrosis.

Each case has its lesson—a lesson that may be, but is not always, learnt for clinical wisdom is not the equivalent of experience.
— **William Osler**

3. When diagnosis is in doubt.
4. In severe necrotising pancreatitis as a trial to save the life of the patient which has got very high mortality.

Surgical management of acute pancreatitis

Surgery removes intra- and extrapancreatic necrotic materials, pancreatic fluid, and toxins. It permits preservation of viable pancreatic tissue. *Open surgery is the gold standard for infected pancreatic necrosis.*

- After opening the abdomen, all necrotic tissue, pus, infected fluid and toxins are removed. 10-12 litres of normal saline wash is given. Drainage tubes are placed liberally. Abdomen is closed in layers—*Conventional closed method* (necrosectomy, wide debridement, adequate drainage, cholecystectomy, closure). Re-laparotomy is done only on demand later.
- Laparotomy – necrosectomy – wide debridement – wash – wide packing. Wound is left open. Repeated wash and packings are done until healthy granulation develops – *open method*.
- Laparotomy – necrosectomy and closure with drain and re-laparotomy later—*semi-open* method**.**
- *Zip technique* can be used to give repeated wash to remove toxins and necrotic tissues until healthy granulation tissue develops in the pancreatic bed—*Bradley's repeated laparotomies and wash.*
- Continuous closed peritoneal lavage of the pancreatic bed and lesser sac is done with 10-12 litres of normal saline or hyperosmolar, potassium free dialysate fluid 2 litres/hour using multiple tubes to remove toxic material in the peritoneal cavity/retroperitoneal area until return fluid becomes clear—*Beger's lavage*. Procedure is done after initial surgical debridement.
- Extra peritoneal lavage through bilateral flank incisions is also used. But being a blind procedure it is technically difficult and one may not be sure about the adequacy of the procedure.
- Under laparoscopic visualisation, necrosectomy, wash and drainage can be done. But often it is difficult to create pneumoperitoneum in acutely ill patient. But it is increasingly becoming popular.
- A jejunostomy is often done along with these procedures to have early enteral nutrition.
- *Endoscopic necrosectomy* is often done in some centres. *Early endoscopic intervention* (within 48 hours) with ERCP, biliary stone removal and stenting in biliary pancreatitis is done and favored in many centres.
- *Further management* is important to prevent recurrence. Gallstones should be dealt by laparoscopic cholecystectomy in 2 weeks after acute attack during same admission period. Endoscopic sphincterotomy (ERCP) and often stenting may be needed if there are CBD stones.

Note:
GI fistula either enteric or pancreatic and incisional hernia are the late complications of these surgeries.

COMPLICATIONS OF ACUTE PANCREATITIS

- Shock—Hypovolemic and septic
- Respiratory failure and ARDS—Common in 7 days
- Septicaemia—Common after 7 days
- Hypocalcaemia
- Disseminated intravascular coagulation (DIC)
- Acute renal failure
- Pancreatic pleural effusion (left sided 20%)
- Pancreatic pseudo aneurysm
- Pancreatic ascites
- Colonic stricture
- Pseudocyst of pancreas
- Chronic pancreatitis
- Splenic vein thrombosis
- Pancreatic abscess

- *Acute fluid collection*
  - It is collection of fluid in or near the pancreas during an attack of acute pancreatitis with an ill-defined or lacking fibrin wall or granulation tissue.
  - It is 40% common; it usually occurs at peripancreatic area, occasionally intrapancreatic.
  - More than 50% of acute fluid collection regress spontaneously, remaining may form pseudocyst of pancreatic necrosis.
  - CT guided aspiration at one puncture site is often necessary to confirm that it has not formed abscess.
- *Acute pseudocyst*
  - It is collection of fluid with pancreatic juice in or near the pancreas localised by thin fibrin wall or granulation tissue.
  - Occurs in 2 weeks, usually resolves spontaneously.
  - Fluid can be removed percutaneously under guidance or through an endoscope.
- *Pancreatic pseudocyst*
  - It is collection of fluid in a false cavity which commonly contains brownish pancreatic enzyme rich fluid, *lined by granulation tissue* but *not true epithelium* with an organised thick fibrous covering.
  - It is commonly located in peripancreatic region, in lesser sac. It can be often intrapancreatic or in other places in the peritoneal cavity. It can be multiple also.
  - It usually forms 4 weeks after an attack of pancreatitis—*a chronic entity.*
  - It is usually sterile but can get infected.
  - Pseudocyst may rupture to form pancreatic ascites.
  - It may cause pancreaticopleural fistula when once it erodes into left side pleural cavity or it may erode into splenic vessels causing life threatening haemorrhage.
- *Pancreatic necrosis*
  - It is focal/diffuse area of non-viable pancreatic parenchyma with peripancreatic fat necrosis.
  - It is initially sterile but eventually gets infected.
  - It contains *paste/putty* like material.



Figs 14.7A and B: On table photos of acute pancreatitis. Note the typical saponification in the omentum and mesentery.

- It may form pseudocyst, abscess or may be replaced by fibrous tissue during healing.
- It can be sterile or infected necrosis.
- It is confirmed by CT scan and CT guided aspiration usually at one site; collected fluid should be sent for culture.
- *Infection of necrotic area* usually occurs within 4 weeks. It is ideally *conventionally* treated with laparotomy, debridement is done by removing all necrotic tissue with adequate drainage for remaining viable exocrine function. Often repeat laparotomies are done once in 3 days until all necrotic materials are cleared and jejunostomy is done in final approach.
- Laparotomy and debridement done once with continuous lavage; antibiotics with percutaneous drainage/only surgical drainage without debridement/debridement using minimally invasive methods—are *unconventional* approaches.

- *Pancreatic abscess*
  - It is collection of pus in lesser sac (intraabdominal) in relation to pancreatic surface which contains mainly pus with only less or no necrotic pancreas.
  - It may slough off the pancreatic/splenic vessel wall to cause torrential haemorrhage. Abscess may be single or multiple (60%). It is commonly in head/body or tail. But often entire gland may be involved (25%).
  - Abscess may rupture into viscera or extend into other part of the abdomen. Features of sepsis, tender palpable mass in the epigastrium with leukocytosis are observed.
  - It is treated by antibiotics, percutaneous U/S or CT guided aspiration or drainage or open drainage.



Fig. 14.8: *Beger's lavage* to pancreatic bed. Tubes are placed postoperatively. Continuous saline irrigation through the tube is done until irrigation fluid becomes clear.

- *Respiratory complications*
  - Thay are often severe and life-threatening. It is due to distension of abdomen, diaphragmatic elevation, pleural effusion, reduced surfactant (lecithin) activity in alveoli due to lecithinase, severe pain, pleural effusion (left), intravascular coagulation in lungs and ARDS. *Arterial blood gas analysis* should be done. Often it needs ventilator support.
- *Pancreatic pseudoaneurysm*
  - It is due to enzymatic digestion (elastase) of the wall and weakening and aneurysmal dilatation of the splenic (50%) or gastroduodenal vessels (15%) or inferior and superior pancreaticoduodenal arteries (10%).
  - It may rupture and cause life threatening haemorrhage or may rupture into stomach or duodenum to cause massive upper GI bleed or may rupture into pancreatic duct causing *haemosuccus pancreatitis*.
  - It is diagnosed by CT angiogram.
  - It is treated by critical care, blood transfusion, emergency angiographic embolisation or by open surgery and ligation of the involved vessel. It carries high mortality.
- *Pancreatic fistula*
  - It can occur due to ductal wall disruption and necrosis or after surgical intervention for acute pancreatitis (necrosectomy).

> *In case of chronic pancreatitis jaundice supervenes in only fifteen percent of cases, but diabetes is present on thirty percent.*
>
> **— Richard B Cattell**

  - It may be internal into bowel or external to skin.
  - Fistula may be low (< 200 ml) or high (> 200 ml) out put.
  - It can be straight or curved.
  - It is confirmed by biochemical analysis, ERCP, CT fistulogram.
  - If fistula persists for 6 months then sphincterotomy, resection of fistula with pancreatic resection, pancreaticojejunostomy is done.
- *Emphysematous pancreatitis*
  - It is gas in pancreatic parenchyma, a dangerous type and can be diagnosed by CT scan.

Note:

- Decrease serum calcium level is *worst prognostic indicator* of pancreatitis.
- These scoring systems differ for non-gallstone pancreatitis and gallstone pancreatitis.
- Other scoring systems which are often used are APACHE II (Acute Physiology And Chronic Health Evaluation II) and SAP (simplified acute physiology) scoring systems. Twelve variables are used to assess in APACHE II scoring.
- *C- Reactive Protein (CRP) > 210 mg* / L in first 4 days and > 120 mg/L in one week; phospholipase A2 assay; pancreas related protein; interleukin-6; polymorphonuclear elastase > 120 µg / L; serum ribonulcease assay—are other parameters used to assess the severity.

Criteria to Find Out Systemic Failure in Acute Pancreatitis

- *Cardiac*: Hypotension; pulse > 130/minute; arrhythmias, ECG changes.
- *Pulmonary*: $PaO_2 > 60$ mmHg; ARDS.
- *Renal*: Urine output < 40 ml/hour; increase in blood urea and serum creatinine.
- *Metabolic*: Falling serum calcium; magnesium and albumin.
- *Haematologic*: Fall in haematocrit; DIC.
- *Gastrointestinal*: Severe ileus; sequestration of fluid.
- *Neurologic*: Irritability; confusion; localising features.

PSEUDOCYST OF PANCREAS

- It is localized collection of sequestered pancreatic fluid, usually 3 weeks after an attack of acute pancreatitis.
- It can occur after trauma and recurrent chronic pancreatitis.
- Collection usually occurs in the lesser sac in relation to stomach, but can occur in relation with duodenum, jejunum, colon, splenic hilum.
- About 50% of acute pancreatitis leads to pseudocyst formation, but among that 20-40% will resolve spontaneously.

Sites of pseudocyst

- Lesser sac—commonest, i.e. between colon and stomach

In relation to:

- Duodenum
- Jejunum
- Colon
- Splenic hilum



Fig. 14.9: Pseudocyst of pancreas.

Ranson's prognostic criteria in gallstone pancreatitis	***Ranson's prognostic criteria in Non-gallstone pancreatitis***	***Glasgow – Imrie prognostic criteria***	***Acute Physiology and Chronic Health Evaluation (APACHE II) score > 8 points predicts 11% to 18% mortality***
On admission: • Age > 70 years • TC > 18,000/cu mm • Blood sugar > 220 mg% • LDH > 400 IU/L • AST > 250 IU/100 ml	On admission: • Age > 55 years • TC > 16,000/cu mm • Blood sugar > 200 mg% • LDH > 700 IU/L • AST > 250 IU/100 ml	On admission: • Age > 55 years • TC > 15,000/cu mm • $PaO_2 < 60$ mmHg • Blood urea > 16 mmol/L (No response to IV fluids) • Blood sugar > 200 mg% (no H/O diabetes)	• Equation includes the following factors: age, rectal temperature, mean arterial pressure, heart rate, PaO_2, arterial pH, serum potassium, serum sodium, serum creatinine, hematocrit, white blood cell count, Glasgow coma scale score.
Within 48 hours: • Haematocrit drop > 10% • BUN rise > 2 mg% • Serum calcium < 8 mg% • Base deficit > 5 mEq/L • Fluid sequestration > 4 L	Within 48 hours: • Haematocrit drop > 10% • BUN rise > 5 mg% • $PaO_2 < 60$ mmHg • Serum calcium < 8 mg% • Base deficit > 4 mEq/L • Fluid sequestration > 6 L	Within 48 hours: • Serum calcium < 2 mmol/L • Serum albumin < 3.2 gm/dl • LDH > 600 U/L • AST / ALT > 600 U/L	APACHE II modified (1996) LFT is added in biliary pancreatitis APACHE – O (Toh 1996) Obesity is added

Types

Depending on whether it communicates with pancreatic duct or not it is classified as:

1. *Communicating pseudocyst.*
2. *Noncommunicating pseudocyst.*

It can be

- *Acute pseudocyst*.
- *Chronic pseudocyst*.

D'Egidio Classification of Pseudocyst

- *Type I*: After an attack of acute pancreatitis. Normal duct anatomy; no fistula/communication.
- *Type II*: After an attack of acute on chronic pancreatitis. Abnormal duct anatomy without stricture; 50% chances of fistula.
- *Type III*: After an attack of chronic pancreatitis, abnormal anatomy with stricture; always communicating. It appears like retention cyst.
- Initially cyst wall is thin *(unformed),* but later it gets fibrosed and thickened *(formed)* (matured).
- It is lined by fibrin layer but no endothelium, hence called as pseudocyst.
- It contains typically brownish fluid with sludge like necrotic material. It can get infected to form *infected pseudocyst* or *pancreatic abscess.*
- Amylase level in the cyst fluid is very high (> 5000 units/ml).



Fig. 14.10: Pancreatic pseudocyst on table aspiration. Note the brownish black colour of the fluid.

Note:
It is not a true cyst as there is no epithelial lining.

Clinical Features

- A swelling in the epigastric region which is hemispherical, smooth, soft, not moving with respiration, not mobile, upper margin is diffuse but lower margin well defined, resonant or impaired resonant on percussion, with transmitted pulsation confirmed by knee-elbow position.
- If it is infected, it will be tender mass and patient will be toxic with fever and chills.
- Because stomach is stretched towards the abdominal wall, Ryle's tube passed will be felt per abdominally *(Baid test)***.**

Differential Diagnosis

- Aortic aneurysm.
- Retroperitoneal cyst or tumour.
- Cystadenocarcinoma of pancreas**.**



Fig. 14.11: Pseudocyst mass.

- Cyst of the liver.
- Mesenteric cyst.
- Hydatid cyst.

Investigations

- U/S abdomen (commonly done procedure), U/S reveals the size and thickness of the pseudocyst. Size less than 6 cm indicates that one can wait for spontaneous resolution. Endosonography (EUS) is very useful.
- CT scan is ideal and study of choice. It is two times more sensitive than U/S. It demonstrates size, shape, number, wall thickness, contents, pancreatic duct size, and extent of necrosis in pancreas, calcification and atrophy in chronic pancreatitis, regional vessels, pseudoaneurysm, splenic/ portal vein thrombosis.
- MRCP delineates the ductal anatomy and its abnormality.
- ERCP can be done to find out the communication.
- Barium meal (lateral view) shows widened vertebrogastric angle with displaced stomach (Not usually done now).
- LFT, serum amylase.

Indications for surgery/intervention

- Size more than 6 cm
- Formed pseudocyst
- Infected pseudocyst
- Cyst persisting after 6 weeks/progressive cyst
- Multiple cysts/cyst due to trauma
- Communicating cysts/cyst with severe pain
- Thick-walled pseudocyst



Fig. 14.12: Vertebrogastric angle.



Figs 14.13A and B: CT scan showing typical pseudocyst of pancreas.



Figs 14.14A and B: CT scan showing pseudocyst of pancreas both single and multiple. Note the cyst cavity and the thick cyst wall. Patient needs drainage procedure either cystogastrostomy or cystojejunostomy.

Surgery

- *Cystogastrostomy:* At laparotomy, anterior wall and posterior wall of the stomach is opened. *Brownish fluid* is aspirated. The thick capsule of pseudocyst is opened. All fluid with necrotic material are sucked. Fluid should be sent for cytology, culture and sensitivity and amylase estimation. Cyst wall always should be biopsied. Cyst cavity should be washed with normal saline after breaking septae. Pseudocapsule is anastomosed to posterior wall of the stomach—*Jurasz operation.*

Note:
Roux-en-Y cystojejunostomy is better with lesser recurrence rate than cystogastrostomy.

Other procedures

- Cystoduodenostomy.
- Cystojejunostomy is done in large cyst, recurrent cyst.
- If infected, cystogastrostomy with external drainage is done using Malecot's catheter (*Smith operation*).
- Endoscopic cystogastric stenting.
- ERCP and *transpapillary stenting* and drainage in communicating pseudocyst. There is loss of exocrine and endocrine functions with progressive pancreatic fibrosis.



Fig. 14.15: Pseudocyst of the pancreas aspiration on table. Note the brownish-black colour of the fluid aspirated.

- Laparoscopic cystogastrostomy is becoming popular, effective and less invasive.
- U/S guided aspiration is useful in initial phases.
- Along with cystojejunostomy, pancreaticojejunostomy should be done if there is ductal stricture and dilatation and communication with pseudocyst.
- Distal pancreatectomy with pseudocyst removal if cyst is in distal part.



Fig. 14.16: Cystogastrostomy for pseudocyst of the pancreas.

Complications of pseudocyst

- Rupture—3%—into bowel or peritoneum
- Infection, commonest—20%
- Bleeding from the splenic vessels—7%
- Cholangitis
- Duodenal obstruction
- Portal/splenic vein thrombosis and segmental portal hypertension
- Cholestasis due to CBD block



Fig. 14.17: Cystogastrostomy procedure, on table.

Pseudopseudopancreatic Cyst

It is a mass in epigastric region due to pancreatitis formed by bowel, omentum which clinically mimics a pseudocyst of pancreas. But fluid collection is absent.

Note:

- Small cyst can be drained through endoscopy. But debridement is not possible. Bleeding and cyst leakage are other problems.
- CT guided percutaneous catheter placement is done in critically ill patients, infected pseudocyst, unfit patients, cyst in pelvis/mediastinum. Improper drainage, recurrence and fistula formation are the problems.
- External drainage is done when cyst is infected, haemorrhagic or ruptured. Problem with external drainage is formation of fistula (20%).
- Therapy is decided based on thickness of the wall of pseudocyst; location of pseudocyst; contents of pseudocyst and ductal status.



Fig. 14.18: Roux-en-Y cystojejunostomy for pseudocyst of the pancreas.

> *Carcinoma pancreas should be suspected when an elderly person develops diabetes and in spite of adequate treatment, continues to loose weight.*
> **— Robert D Lawrence**

CHRONIC PANCREATITIS

- It is persistent progressive irreversible damage of the pancreas due to chronic inflammation.


It can be
Chronic relapsing pancreatitis
Chronic pancreatitis (persistent)
Chronic non-calcifying pancreatitis
Calcifying pancreatitis
In the duct (Stone in the pancreatic duct)
In the parenchyma

- Chronic pancreatitis is more common in males, common in Kerala (induced by diet, rich in Tapioca).



Fig. 14.19: Calcifications in the parenchyma of the pancreas.



Fig. 14.20: Pancreatic ductal stone removed—specimen. Patient underwent pancreaticojejunostomy.

Aetiology

- Alcohol—80% main cause
- Stones in biliary tree—rare cause
- Malnutrition, diet
- Hyperparathyroidism
- Hereditary (familial hereditary pancreatitis)
- Idiopathic—20%—as mutation
- Trauma
- Congenital anomaly (Pancreatic divisum)
- Cystic fibrosis
- Autoimmune pancreatitis
- Hyperlipidaemia

TIGAR-O Risk Factor Classification 2001

T – Toxic - alcohol/tobacco/dietary/drug.
Metabolic-hypercalcemia/lipidemia/lipoprotein lipase deficiency.
I – Idiopathic—early/late onset/tropical.
G – Genetic mutations—CFTR/SPINK 1.
A – Autoimmune primary/with Sjogren/Crohn's disease.
R – Recurrent and severe acute/ischemic.
O – Obstructive—pancreas divisum//annular pancreas/stenotic papilla/duodenal obstruction/trauma/pancreatic ductal stones/ choledochocele.

- Alcohol reduces pancreatic blood flow, alters cell viability, releases the free radicals, creates pancreatic ischaemia, and activates the pancreatic stellate cells which produce abundant extracellular matrix and collagen.
- Genetic predisposition may be the cause of idiopathic pancreatitis. Mutation in pancreatic secretory trypsin inhibitor causes activation of trypsin causing pancreatitis.
- Hereditary pancreatitis is an autosomal disorder with mutation in trypsinogen gene in chromosome 7. It causes recurrent painful episodes of acute pancreatitis in childhood, leading to chronic pancreatitis and pancreatic cancer in adulthood.

Theories and Concepts in Pathogenesis of Chronic Pancreatitis

- *Oxidative stress hypothesis*—Reactive by-products of hepatic mixed function oxidase activity damage the pancreas through chronic reflux of bile into the pancreatic duct.
- *The toxic-metabolic theory*—Alcohol is directly toxic to the acinar cell where it brings changes in intracellular metabolism causing pancreatic lipid accumulation, fatty degeneration, cellular necrosis, and eventual widespread fibrosis.
- *Stone and duct obstruction theory*—Alcohol increases the lithogenicity of pancreatic juice, leading to stone formation. Chronic contact of stones with duct epithelial cells produces ulceration, scarring, atrophy, fibrosis and chronic obstruction of the acini.
- *The necrosis-fibrosis theory*—Acute and chronic pancreatitis represents a spectrum of disease. Inflammation from acute pancreatitis leads to scarring, extrinsic compression of the pancreatic ductules, obstruction, stasis, atrophy and stone formation.
- *The genetic defect* of hereditary pancreatitis produces recurrent acute pancreatitis in early childhood, leading to chronic pancreatitis in early adulthood.
- *Cellular mechanisms* of pancreatic fibrogenesis is due to pancreatic *stellate cells* which are stimulated and activated by alcohol, oxidative stress, cytokines of acute pancreatitis; activated stellate cells migrate to the periacinar areas to deposit collagen and fibronectin. Transforming growth factor beta 1 is an important mediator of pancreatic fibrosis.
- *The sentinel acute pancreatitis event (SAPE) hypothesis*—An episode of acute pancreatitis, the sentinel event, sets the stage for the attraction of collagen-secreting stellate cells.
- *Heavy, prolonged alcohol use* is the most common cause of chronic pancreatitis. Alcohol-related chronic pancreatitis

is associated with more severe pain, more extensive calcification and ductal changes, and more rapid progression to endocrine and exocrine insufficiency. Often recurrent episodes of acute pancreatitis for several years are seen in these patients. Some cofactors amplify the effect of alcohol in these patients. Prevalence of some genetic mutations linked with pancreatitis like cystic fibrosis transmembrane regulator (*CFTR)*, serine protease inhibitor Kazal type-1 (*SPINK1*) has been noted in alcoholic pancreatitis. A high-fat diet and smoking affect pancreatic bicarbonate and water secretion adversely, inducing oxidative stress and increases the rate of pancreatic calcification.

- *Tropical pancreatitis* is endemic in some regions of India (Kerala), Africa, and South America. Episodic abdominal pain begins in childhood and is followed by rapid progression to endocrine and exocrine insufficiency with pancreatic calculi in non-alcoholic individuals. Dietary toxins (cyanogens in the cassava plant, tapioca) and micronutrients like zinc, copper, and selenium, vitamin A deficiencies, genetic factors, ductal abnormalities are the probable causes of tropical pancreatitis. *Linnamarin* and its methyl derivative, in acid pH of stomach releases hydrocyanic acid which is cytotoxic in presence of rhodanase releases thiocyanates causing depletion of methionine, damaging pancreas → pancreatitis. Gross look is small, firm fibrotic/adipose type.
- *Early-onset* idiopathic chronic pancreatitis manifests with severe abdominal pain in childhood, with relatively few structural and functional changes. *Late-onset* idiopathic chronic pancreatitis manifests in middle and late adulthood, often with minimal pain and pronounced exocrine insufficiency.

Pathology

- It shows atrophy of acini, hyperplasia of duct epithelium, interlobular fibrosis, calcifications, ductal dilatation, with strictures in the duct, focal necrosis.
- There is loss of exocrine function initially and endocrine functions eventually.
- Ductular metaplasia and acinar atrophy along with fibrosis and cyst formation develops.

Pathology of chronic pancreatitis

- Focal necrosis
- Segmental or diffuse fibrosis
- Parenchymal calcification or ductal stones
- Stricture or dilatation of the duct

Spectrum of Chronic Pancreatitis

- *Early* – pancreatic oedema – chronic inflammation – normal secretory function.
- *Moderate* – early fibrosis; only few acinar cells – exocrine dysfunction.
- *Late* – fibrosis – loss of secretory function – diabetes mellitus.
- *Complications* develop secondary to healing and fibrosis; deposition of inspissated proteinaceous material in the duct; over expression of CTGF and TGF-B1 that stimulate extracellular matrix.
- *Pain hypothesis include:*
  - Acute and chronic inflammation of the pancreas.
  - Increased pressure within the pancreatic ductal system and parenchyma, ductal dilatation, stasis.
  - Ischaemia of the parenchyma secondary to increased interstitial pressure.
  - Over expression of a particular protein in pancreatic nerve fibres.
  - Pancreatic nerve growth factor released by degenerating acinar cells and its high affinity receptor that promotes nerve growth and repair.
  - Pain may be due to perineural sheath destruction by toxins, ischaemia and also due to tissue acidosis.

Classification of Chronic Pancreatitis

I: Based on main duct dilated or not:

- Large duct disease—main pancreatic duct is dilated.
- Small duct disease—main pancreatic duct, is normal or smaller in size.

II: Staging/classification of chronic pancreatitis (Stages A, B, C)

A new classification of chronic pancreatitis, based on combination of clinical signs, morphology and function, is presented (2009 Büchler et al).

Specific definition of chronic pancreatitis stage A

- **Stage A chronic pancreatitis**

It is the early stage of chronic pancreatitis where complications have not yet appeared and the clinical exocrine and endocrine function is preserved. Subclinical signs (impaired glucose tolerance, reduced exocrine function but without steatorrhoea) might already be apparent.

Stage A is accepted under the following conditions: Pain of any type and degree and/or attacks of acute pancreatitis, no complications, no steatorrhoea, and no insulin-dependent diabetes mellitus.

Specific definition of chronic pancreatitis stage B

- **Stage B chronic pancreatitis**

It is the intermediate stage where chronic pancreatitis has led to complications but clinical exocrine and endocrine function is still preserved. The type of complication is specified (e.g. stage B, bile duct). Stage B is accepted under the following conditions: Patients with complications but without steatorrhoea or diabetes mellitus.

Specific definition of chronic pancreatitis stage C

- **Stage C chronic pancreatitis**

Stage C is the end stage of chronic pancreatitis, where pancreatic fibrosis has led to loss of clinical exocrine and/or endocrine pancreatic function (steatorrhoea and/or diabetes

mellitus). Complications of chronic pancreatitis might or might not be present. The type of exocrine and/or endocrine pancreatic function loss is specified (e.g. stage C, steatorrhoea).
Stage C can be sub-classified into three categories:
C1: Patients with endocrine function impairment.
C2: Patients with exocrine function impairment.
C3: Patients with exocrine/endocrine function impairment and/or complications—as they are defined.

Stage C is accepted under the following conditions: Patients with clinical manifestation of end-stage functional impairment with or without complications.



Fig. 14.21: Patient will occupy leaning forward position to relieve severe pain of pancreatitis.

Clinical Features

- *Pain in epigastric region* (80%)
  - It is persistent and severe, which radiates to back.
  - This pain is due to irritation of retropancreatic nerves, or due to ductal dilatation and stasis, or due to chronic inflammation itself.
  - *Two patterns of pain* have been described (Ammann and Muellhaupt). *Type A* pain is short relapsing episodes lasting days to weeks, with pain-free intervals. *Type B* pain is prolonged, severe, unrelenting pain.
  - Pain exacerbations *need not be always* associated with rise in amylase and lipase levels.
  - There is often a gradual diminish in pain over years due to "*pancreatic burnout*" by extensive calcifications, exocrine and endocrine insufficiency.
- *Exocrine dysfunction*: Diarrhoea, asthenia, loss of weight and appetite, steatorrhoea (signifies severe pancreatic insufficiency) (90%), malabsorption.
- *Endocrine dysfunction*: Diabetes mellitus. Pancreatic diabetes may often be *typically brittle* because of concomitant glucagon deficiency and *requires insulin*.
- *Mild jaundice* is due to narrowing of retropancreatic bile duct and cholangitis.
- *Mass per abdomen*, just above the umbilicus, tender, nodular, hard, felt on deep palpation, not moving with respiration, not mobile, resonant on percussion**.**

Triad of chronic pancreatitis

- Pancreatic calcification
- Steatorrhoea
- Diabetes mellitus

Triad is found in *less than one-third* of patients with CP

Mallet-Guys sign: In right knee-chest position, if left hypochondrium is palpated tenderness can be evoked in case of chronic-relapsing pancreatitis. In this position, bowel loops are being shifted to right so as to have a direct palpation of pancreas.

Chronic pancreatitis can lead to carcinoma pancreas.

Clinical presentations

- *Stage A*: 85%, recurrent / acute episodic pain with weight loss.
- *Stage B*: Severe prolonged progressive pain with impaired pancreatic function with cholestasis, pseudocyst, sinistral portal hypertension.
- *Stage C:* Severe exocrine / endocrine deficiency, less severe pain, complications like pseudocyst and obstruction.

Complications of chronic pancreatitis

- Pseudocyst of pancreas
- Pancreatic ascites
- CBD stricture due to oedema or inflammation
- Duodenal stenosis
- Portal thrombosis—segmental portal hypertension
- Peptic ulcer
- Carcinoma pancreas
- Pancreatic pleural effusion, pancreatic ascites
- Pancreatic fistula
- Splenic vein thrombosis
- Pancreatics enteric fistula

Differential Diagnosis

- Carcinoma of head of the pancreas.
- Retroperitoneal tumour.

Investigations

- Serum amylase—not very useful
- Blood sugar
- Liver function tests and prothrombin time
- U/S abdomen to see duct dilatation, stones, parenchyma, liver status, CBD (normally, diameter of pancreatic duct is < 3 mm)
- Endosonography
- CT scan—CT guided FNAC
- ERCP—*Chain of lake appearance.* Duct is dilated
- MRCP
- Plain X-ray shows calcification in 65% of patients
- Pancreatic secretory juice analysis
- *Pancreolauryl test*—pancreatic esterase cleaves fluorescein dilaurate after oral intake. Fluorescein is absorbed and quantified in urine after 2 days.
- Oral glucose tolerance test
- Faecal chymotrypsin and elastase analysis
- Bentiromide test

Investigations presently used are:

- *CT scan abdomen*: It is 95% reliable; to see pseudocyst, calcification, ductal stones, duct stricture and dilatation, vasculature, fibrosis, surrounding structures, CBD status. It shows 90% sensitivity; 95% specificity.
- *ERCP* is useful in chronic pancreatitis to see dilatations, strictures and altered ductal anatomy. It is mainly to assess *structural pathology* of the pancreas.

Cambridge grading of CP on ERCP

Grade	*Main pancreatic duct*	*Side branches*
I: Normal	Normal	Normal
II: Equivocal	Normal	<3 Abnormal
III: Mild	Normal	>3 Abnormal
IV: Moderate	Abnormal	>3 Abnormal
V: Severe	Abnormal with at least one of the following:	>3 Abnormal
	• Large cavity (>10 mm)	
	• Obstruction	
	• Filling defects	
	• Severe dilatation or irregularity	



Fig. 14.22: ERCP showing pancreatic duct.

- *MRCP* is noninvasive method to see ductal anatomy.
- *Endosonography (EUS)* to see possible malignant site and to take FNAC. Site, duct status, stricture, stones, parenchyma, pseudocyst, CBD status, nodes are identified in EUS. Positive five parameters suggest chronic pancreatitis. It also helps in assessing operability.

EUS criteria in chronic pancreatitis—parenchymal	*EUS criteria in chronic pancreatitis—ductal*
• Gland atrophy	• Narrowing, dilation, irregularity
• Hyperechoic foci	• Calculi
• Hyperechoic stranding	• Side branch dilation
• Cysts, lobularity	• Hyperechoic walls

Rosemont EUS criteria

Major:

- A—Hyperechoic foci with shadowing and calculi in main pancreatic duct (PD)
- B—Lobularity with honeycombing

Minor:

- Cysts
- Dilated ducts ≥3.5 mm
- Irregular PD contour
- Dilated side branches ≥1 mm
- Hyperechoic duct wall, strands
- Nonshadowing hyperechoic foci
- Lobularity with noncontiguous lobules





Figs 14.23A and B: Multiple stones in pancreatic duct with ductal dilatation. It needs removal of stones with pancreaticojejunostomy.

- *Secretin cholecystokinin test* is the gold standard for assessing pancreatic function. After over night fasting, double lumen tube is placed into the duodenum at the level of ligament of Treitz under C ARM guidance. Gastric and duodenal juices are aspirated. Continuous IV secretin 1 u/kg/hour and CCK are infused in 90 minutes. Sampling of duodenal juice is done in every 10 minutes for one hour for analysis of *volume, HCO_3*, amylase, lipase and proteases. It is to assess *functional deficiency*. In chronic pancreatitis volume is normal—> 2 ml/kg but less bicarbonate content —< 80 mEq/L. In malignancy volume is reduced due to obstruction—< 2 ml/kg; bicarbonate level is normal—> 80 mEq/L; enzyme levels are normal.

- *Pancreolauryl test*: After overnight fasting, blood sample is taken. IV secretin is injected 1 u/kg in 3 minutes. Test meal containing bread, butter, tea and fluorescein dilaurate is given to eat. IV metoclopramide 10 mg is injected. Blood samples are taken at 2, 2½, 3 and 4 hours to assess serum fluorescein concentration. It is also quantified in urine after 2 days.
- *LFT, prothrombin time* is needed to manage the patient.
- Serum trypsinogen < 20 ng/ml and fecal elastase < 200 mcg/g stool—severe exocrine insufficiency.

Treatment

Aim of treatment

- Control of pain
- Improvement in maldigestion and nutrition
- Management of complications

Conservative

- Avoid alcohol.
- Low fat, high protein, high carbohydrate diet; small and more frequent meals.
- Pancreatic enzyme supplements, vitamins and minerals, medium chain fatty acids.
- For pain—analgesics, splanchnic nerve or coeliac plexus block. *Pancreatic enzyme replacement therapy (PERT)* is used to relieve pain based on—negative feedback mechanism of pain; protease content responsible for pain relief (dose: >50,000 units). It may be beneficial only in females with idiopathic pancreatitis, small duct disease and pancreas divisum. Other drugs used are—antioxidants, amitriptyline, fluoxitine, octreotide. Novel pain therapies like NGF, antinociceptive agents, mast cell directed therapies are also used.
- Control of diabetes by oral hypoglycaemics or insulin.
- Somatostatin and its analogues. Its role is not clear.
- Repeated ascitic taps for pancreatic ascites.
- *Steatorrhoea* can be controlled by proton pump inhibitors with 1,50,000 units of oral lipase with low fat diet. PPI inhibits acid in stomach to prevent lipase getting inactivated in stomach.

Endoscopic Therapy in Chronic Pancreatitis

- It is used as it has got low morbidity.
- Main *indications* are—pain relief, ductal stones, main duct stricture, pseudocyst drainage, pancreatic ascites, effusion and fistula.
- It is quite useful for main pancreatic duct obstruction and pseudocyst. It is less useful for biliary stricture.
- *Procedures* are—pancreatic duct sphincterotomy, main ductal stone extraction using Dormia basket, main ductal stenting in strictures, stricture dilatation, ESWL of main duct stones, minor papillary sphincterotomy.
- *Pseudocyst* can be treated by *transmural stenting* across gastric wall if there is visible bulge, distance of cyst wall is less than 1 cm, no major vessel at puncture site. *Transpapillary stenting* is done if pseudocyst is communicating, if cyst is less than 6 cm, if there is no visible bulge in the stomach.
- *Complications* are—pancreatitis, stent displacement/occlusion, perforation, bleeding, sepsis, restenosis.
- *Advantages* of endotherapy are—less invasive, can be repeated, less severe complications, can be used as bridge therapy prior to surgery.
- *Disadvantages* are—long term benefits are less (50%). Definitive treatment is delayed. It is not useful in small duct disease; main duct dilatation decides the success rate.

Surgery

Indications for surgery

- Persisting pain—main indication
- Severe malabsorption
- Suspicion of malignant transformation
- Multiple relapses
- Complications like pseudocyst, segmental portal hypertension
- Biliary obstruction (*Wadsworth syndrome*)
- Pseudocyst
- Pancreatic ductal dilatation > 7 mm
- Pancreatic ascites/fistula
- Pancreatic ductal stenosis



Figs 14.24A and B



Fig. 14.24C

Figs 14.24A to C: CT scan abdomen showing features of chronic pancreatitis—calcification, ductal changes, and cyst formation.

Objectives of Surgery

- Pain relief when endotherapy has failed.
- Management of complications.
- Procedure is selected which shows less morbidity and mortality.
- Quality of life (QOL) should be preserved.

Problems and Limitations of Surgery

- Disease is irreversible parenchymal and ductal damage and so surgery *cannot cure* or reverse completely.
- Disease progression cannot be prevented or arrested by surgery.
- Risk of development of cancer continues.
- Complications of surgery are a drawback.

Benefits of Surgery in Relation to Pain Relief and Obstruction

- Relieves intraductal, interstitial, intracellular hypertension—through drainage procedures.
- Entrapped nerves are released and reduction in pancreatic enzyme reduces nerve irritation—resectional methods.
- *Pacemaker*—head of pancreas is removed in head coring procedure (Frey's) to relieve pain. It is less morbid and acceptable method.
- Resection is better than drainage procedure.

Principles of Surgery

- *Pancreatic duct decompression* (*drainage*) reduces the pain and retains the existing exocrine and endocrine functions. But chances of malignant transformation are still high. In significant number of patients recurrence of symptoms (50% recurrence of pain in 5 years) and progression of the disease pathology occurs and it does not give a complete cure. Normal diameter of pancreatic duct 4 mm in head; 3 mm in body; 2 mm in tail of the pancreas. *Pancreatic duct diameter more than 7 mm is an indication for surgery (pancreaticojejunostomy*).
- *Pancreatic resection* (total pancreatectomy) is the actually ideal technique which relieves pain, removes entire diseased tissue. But technical difficulty; high surgical mortality (21%); and severe exocrine and endocrine deficiency (brittle diabetes) are the drawbacks. Head of pancreas is considered as pacemaker of the pancreatitis disease and so pancreaticoduodenectomy (*Whipple's*) is the other option to give adequate relief. It is preferred in patients who are having relatively normal body and tail of the pancreas. Occasionally when disease is limited to tail and body then *distal pancreatectomy* with or without splenectomy often with distal pancreatico jejunostomy may be done. But it is not beneficial if disease is extensive and diffuse. Resection is the main method of treatment if ductal dilatation is not adequate.
- A *combined resection and drainage procedures* are also done. Head is decored at various levels and decompressed duct is anastomosed to jejunum.

Surgeries

- 95% *subtotal pancreatectomy.*
- *Distal pancreatectomy*—Spleen, body and tail of the pancreas are removed—*Child's operation.*
- *Puestow's operation* [*Puestow-Gilesby* (1958)]—As the duct is dilated more than 8 mm, duct can easily be opened longitudinally. After removing all stones from the duct, it is anastomosed to the jejunum as *Roux-en-Y anastomosis.* In Puestow's operation spleen is removed.
- *Partington-Rochelle operation*: Here longitudinal pancreaticojejunostomy is done using almost entire laid open pancreatic duct. Spleen is retained in this procedure. This is now commonly done procedure.


Oesophagus
Puestow's operation
Stomach
Spleen removed
Duct
Pancreas
Duodenum
Jejunum
Jejunal loop is telescoped into the entirely mobilised body and tail of pancreas and fixed

Fig. 14.25: *Puestow's pancreaticojejunostomy*. Here spleen is removed. Entire length of dilated duct is opened. Distal pancreas is mobilised up to superior mesenteric vessels. Pancreas with opened duct is telescoped into the Roux loop of jejunum and anastomosed.


Oesophagus
Spleen retained
Liver
Stomach
Pancreas
Duct
Duodenum
Jejunum
Partington-Rochelle operation

Fig. 14.26: *Partington-Rochelle operation*. Here spleen is retained and longitudinal pancreaticojejunostomy is done to the opened duct from front.


Oesophagus
Liver
Stomach
Pancreas
Duct
Duodenum
Jejunum
Decoring of head also done
Frey and Smith procedure

Fig. 14.27: *Frey's procedure*. Here head of pancreas is decored and opened duct with decored head is anastomosed to Roux loop of jejunum.

- *Total pancreatectomy* is indicated when entire gland is diseased. It relieves the pain and also prevents the diseased pancreas from turning into malignancy. Patient has to take insulin and oral pancreatic enzymes permanently (*brittle diabetes*).
- The cause is treated like cholecystectomy for gallstones.
- Therapeutic ERCP is useful in removal of stones in dilated duct.
- If disease mainly involves head of the pancreas, then pancreaticoduodenectomy can be done—*Whipple's procedure.*
- Duodenal preserving resection of head of pancreas in front of portal vein with jejunal loop anastomosis to transected neck of pancreas—*Beger procedure.* Here extensive resection of head (than Frey's) is done.


Oesophagus
Liver
Stomach
Pancreas
SV
PV
SMV
Duodenum
Jejunum
Beger's procedure
Decoring up to portal vein, neck transected to anastomose

Fig. 14.28: *Beger's procedure*. Here head is decored up to the visible portal vein. Neck is transected. Distal end of the pancreas with retained part is anastomosed to Roux loop of jejunum.


Liver
Stomach
Pancreas
Pancreatic duct

Fig. 14.29: Dilated pancreatic duct is laid open; multiple stones are removed and duct is ready for longitudinal pancreaticojejunostomy (LPJ).



Fig. 14.30: Pancreatic duct stones—removed during pancreaticojejunostomy.

- *Longitudinal pancreaticojejunostomy* after excision of peripancreatic duct tissue—here superficial part of the head of pancreas is removed to achieve improved drainage—*Frey procedure*. It is done when ductal dilatation is not adequate; head is more than 4 cm thick. Head coring is done with retaining 5 mm thick tissue in front of veins, close to duodenum. It shows 75% pain relief in 3 years.

- Resection of tail of pancreas with retrograde pancreaticojejunostomy—*Duval procedure*.


CDJ – Choledochojejunostomy
JJ – Jejunojejunostomy
Liver
CBD
CDJ
Stomach
Pancreas
Biliary stricture
JJ
Jejunum
A
Oesophagus
Liver
CDJ
CBD
Roux-en-Y loop
GJ
Spleen
PJ
JJ
Pancreas
JJ
CDJ – Choledochojejunostomy
PJ – Pancreaticojejunostomy
JJ – Jejunojejunostomy
GJ – Gastrojejunostomy
B

Figs 14.31A and B: *Choledochojejunostomy*. It is Roux-en-Y anastomosis. It is done whenever there is complication of biliary stricture after pancreatitis. Often triple anastomosis may be required—pancreaticojejunostomy, choledochojejunostomy and gastrojejunostomy. It is done whenever there is duodenal obstruction, biliary block and pancreatic duct dilatation (drainage procedure).


Oesophagus
Liver
Stomach
Pancreas
Duodenum
Jejunum

Fig. 14.32: *Retrograde pancreaticojejunostomy* after resection of the tail of the pancreas (Duval).

- When duodenal, biliary and pancreatic obstruction is present—choledochojejunal, pancreaticojejunal and gastrojejunal anastomosis may be needed—*triple anastomosis*. Only biliary stricture which can not be managed by ERCP needs choledochojejunostomy.

Complications of surgery:

- Pancreatic leak/fistula (10%); infection; bleeding; recurrence; brittle diabetes.
- *Pain relief* in chronic pancreatitis is achieved by drugs; decompression/drainage surgeries, resection surgeries, epidural analgesia, coeliac ganglion block, operative chemical splanchnicectomy, extra/intra peritoneal right and left splanchnicectomy, transhiatal bilateral splanchnicectomy, thoracoscopic splanchnicectomy.

Postoperative care

- Nutrition—TPN/jejunostomy feed
- Fluid and electrolyte management
- Prevention/control of sepsis
- Proper monitoring
- Octreotide on table and postoperatively—regular intervals or slow infusion—5 days

Surgery for chronic pancreatitis

Drainage	*Resection*
• Technically easier	• Technically demanding
• Less mortality < 2-5%	• Mortality 8-21%—very high
• Adequate pain relief	• Used when carcinoma is suspected or localised disease
• Recurrence of pain in 5 years—50%	• Head is the pacemaker of the disease
• Diseased tissue is left behind	• Whipple's is preferred
• Disease progression	• Total pancreatectomy causes high mortality, brittle diabetes; though ideal it is not done commonly
• Fear of existing occult carcinoma (17%) or later onset	

Many receive advice, only wise profit from it.

PANCREATIC TUMOURS

Classification

A. ***Exocrine tumours***

Benign: Benign cystadenoma. It is rare.

Malignant:

1. Adenocarcinoma in ampulla or periampullary region or head of pancreas. Periampullary carcinoma may arise from any of the component—duodenal mucosa or CBD or pancreatic duct component or all. Occasionally squamous cell carcinoma, or combination of adeno squamous can occur.
2. Cystadenocarcinoma of pancreas occurs commonly in body and tail of the pancreas, which usually attains a large size (5%).

B. ***Endocrine tumours***

1. Insulinoma (β cells)	Whipple's triad
2. Gastrinoma (G cells)	Peptic ulcer.
3. Glucagonoma (α cells)	Diabetes, necrolytic migratory erythema.
4. Vipoma—Pancreatic cholera (Verner-Morrison syndrome)	Watery diarrhoea, hypokalaemia achlorhydria. (WDHA syndrome)
5. Somatostatinoma. (S cells) δ cells	Diabetes, steatorrhoea, gallstones.

C. ***Lymphomas***

EXOCRINE PANCREATIC TUMOURS

Exocrine Pancreatic Tumours can be Solid (75%) or Cystic

Solid neoplasms

- *Infiltrating ductal adenocarcinoma* (85%) is common in head (yellowish white mass), neck and ampulla. There is evidence of ductal/glandular differentiation; with intense non-neoplastic desmoplastic stromal reaction; haphazard infiltrative growth pattern; growth along the nerve roots; and lymphovascular invasion. Initial early non-invasive epithelial proliferation is called as *pancreatic intraepithelial neoplasia* (PanIN). Immunohistochemistry shows CA 19-9; mucins (MUC1, 3, 4, 5); CEA; cytokeratins 9, 19. 5 years survival is < 5%. After surgery it may be 20%. *Signet ring, colloid, anaplastic types are variants.*
- *Acinar cell carcinoma* shows sheets of acinar structures with often metastatic fat necrosis, eosinophilia, polyarthralgia. Presence of zymogen granules; antibodies against trypsin / chymotrypsin and lipase are typical.
- *Pancreatoblastoma* are malignant tumour seen commonly in children.

Cystic neoplasms

- They mimic closely pseudocyst of pancreas.
- Cystic fluid analysis will commonly differentiate the problem. Pseudocyst is the fluid of low viscosity, with low levels of CEA, and tumour markers like CA 15/3, CA 72/4 but high levels of amylase with inflammatory cells on cytology. In cystic neoplasms fluid shows high viscosity, high CEA (mucinous) but low amylase and tumour markers with tumour cells on cytology.
- They are 1% of all pancreatic tumours; 10% of all cystic lesions of pancreas.
- They can be *mucinous* (commonest) or *serous cystadenoma*; *mucinous ductal ectasia of pancreas* (common in elderly males, common in head, can turn into malignancy); *papillary cystic tumours, teratomas,* etc. (Note: cystic islet tumours also cystic neoplasm but are endocrinal nonfunctioning with 30% malignant potential).

Types of cystic neoplasms

- ***Mucinous cystic neoplasms***:
  - They are more common.
  - They are common in females (90%) and often seen in early age group.
  - They are common in *tail and body*. They do not communicate with main pancreatic duct.
  - It can be unilocular or multilocular. Mucous secreting columnar epithelium (mucin rich goblet ells) with dense ovarian like stroma is typical histology. It is not associated with extrapancreatic neoplasm.
  - It can be mucinous cystadenoma; borderline; *in situ*; mucinous cystadenocarcinoma. Mucinous cystadenoma can turn into malignancy. Increased mitosis, atypia, tumour markers like CA 15/3, CA 72/4 will be positive with over expression of EGFR.
  - Mucinous tumours may show high levels of CEA but low levels of amylase.
  - Presentations may be mass abdomen (75%, large epigastric mass, non-mobile, not moving with respiration), abdominal pain, back pain, weight loss.
  - *Investigations*—CT scan; EUS; EUS guided aspiration for cytology, fluid analysis for CEA (↑), amylase (↓), angiography shows hypervascularity.
  - *Treatment:* Depends on location of tumour either Whipple's operation; distal pancreatectomy; median pancreatectomy.
  - Survival rate for mucinous cystadenocarcinoma is 50%.



Fig. 14.33A



Figs 14.33B and C

Figs 14.33A to C: Mucinous cystadenoma of pancreas. Only cystadenoma is removed and specimen was aspirated for fluid content (*Courtesy:* Dr Arunkumar, MCh).

- ***Serous cystic neoplasms***
  - They are almost always benign and are common in females (2:1).
  - It can be *microcystic adenomas* (90%) or *oligocystic adenomas* (10%).
  - Extrapancreatic neoplasm can be associated (20%) with it.
  - It is more common in *von Hippel Lindau syndrome*.
  - Abdominal pain, backache, features of pancreatitis (5%), jaundice (10%) and palpable mass in epigastrium (65%) are the presentations.
  - It is common in *head of pancreas*, usually solitary cells which contain only glycogen but *no mucin*.
  - Microcysts of 3-6 mm size within the cyst is common; cyst is lined by cuboidal epithelium.
  - CT scan shows central calcification with enhancing septae. EUS is very useful investigation.
  - Treatment: Central or distal pancreatectomy.

Intraductal papillary mucinous neoplasms (IPMN) (Ohashi 1982):

- It is '*intraductal papillary mucinous* neoplasm with tall, columnar, mucin containing epithelium with or without papillary projections, involving main pancreatic duct and or the branch ducts'.
- It is common in 7th decade; equal in both sexes.
- It can be ***main duct IPMN*** with duct (75% proximal part) dilatation ≥ 1 cm containing mucous bulges through ampulla; ***branch—duct IPMN*** involving side branches of the non-dilated main duct but communicating to main duct mainly involving uncinate process, often head, neck and body, seen as multifocal disease. ***Combined IPMN*** involving both main duct and branch ducts is also possible.
- IPMN can be benign; borderline; malignant *histologically*. 70% main duct IPMN and 25% of branch duct IPMN is associated with *malignancy*. *Invasive type* is more common with main duct IPMN. Adenoma—carcinoma sequence is commonly observed.
- IPMN is also classified as—PAN IN 1 with absence of dysplasia; PAN IN 2 with moderate dysplasia; PAN IN 3 with carcinoma in situ.
- Main duct IPMN presents *with* abdominal pain, features of pancreratitis, steatorrhoea where as branch duct IPMN can be asymptomatic. Jaundice, recent onset/worsening diabetes occur once it is *malignant*.
- ERCP shows *triad of Ohashi—a bulging ampulla of Vater, mucin secretion and dilated main pancreatic duct*. *Dynamic MR* is very useful. Endosonography and helical CT are useful. EUS aspiration is also useful.
- IPMN should be *identified first from other cystic* diseases of the pancreas; then *type* should be assessed; later *invasiveness* should be evaluated.
- *Features of malignant IPMN are*—presence of jaundice/steatorrhoea/worsening diabetes/cyst > 3 cm; thick wall cyst; nodules/papillary lesions; main duct > 1 cm; *raised CEA* (120 ng/ml) in pancreatic juice/cyst fluid.
- **Treatment:** Main duct IPMN should be resected always. Branch duct IPMN < 3 cm without nodules can be observed carefully. Middle pancreatectomy is done when needed in branch duct IPMN. Multifocal disease needs total pancreatectomy or extended resections to achieve clearance. Nodal spread in malignant IPMN is 45%. Long-term survival is good for noninvasive type.

CARCINOMA PANCREAS

- Carcinoma pancreas is higher in men.
- It is common in African American males.
- 80% of pancreatic cancers are metastatic at the time of first diagnosis.
- It is common in Jewish heritage and native Hawaiians.
- Its incidence is 9 new cases per 100000 people. Mean age is 60-65 years.

Aetiology

- Smoking.
- High energy diet rich in fat.

Surgical Triad: *Measure thrice, think twice, cut once.*

- Chronic pancreatitis.
- Familial pancreatitis.
- Diabetes mellitus.
- Carcinogens like benzidine.
- Hemochromatosis with pancreatic calcification.
- Cirrhosis, obesity.
- Occupational exposure to carcinogens like DDT, benzidine.
- Previous cholecystectomy.
- 85% show mutant *K ras gene on codon 12*; 60% show mutation of p53 gene in chromosome 17; over expression of EGFR.
- *Peutz-Jegher syndrome*, *HNCC* (Hereditary Nonpolyposis Colonic Cancer—Lynch II type), ataxia telangiectasia, *hereditary breast and ovarian cancers, hereditary atypical multiple mole melanoma syndrome*, familial adenomatous polyposis (FAP).

Sites

- Head and neck region
- Ampullary and periampullary region } 70%
- Body and tail—30%

Periampullary Carcinoma

It is tumour arising at or near the ampulla.
It could be:

- Adenocarcinoma from head of pancreas close to the ampulla—50%.
- Tumour from ampulla of Vater—30%.
- Distal bile duct carcinoma—10%.
- Duodenal carcinoma adjacent to ampulla—10%.

Pathology

Gross

- Grayish white scirrhous nodular gritty tumour in the head is the usual gross look. More than 3 cm sized tumour shows nodal and distant spread commonly. Induration, areas of haemorrhage and necrosis are common.
- Pancreatic duct may be dilated due to obstruction.
- Carcinoma head of pancreas present earlier than carcinoma body and tail of pancreas.

Microscopy

- It shows malignant cells with variable degree of differentiation, high mitotic index, severe *desmoplastic reaction* with fibrosis, a *halo* around the tumour due to obstruction of the adjacent ducts caused by the tumour leading into chronic pancreatitis in close proximity.
- Along with vascular and lymphatic invasion tumour has got high propensity for *perineural spread* and so to neural plexus causing back pain.
- Colloid (mucinous noncystic), signet cell, squamous, adenosquamous, anaplastic, sarcomatoid are variants of duct cell carcinoma.

Spread

Local Spread

- To adjacent structures like duodenum, portal vein, superior mesenteric vein, retroperitoneum.
- Spread is more likely in carcinoma head of pancreas than in periampullary carcinoma.
- Spread is common once carcinoma head of pancreas becomes more than 3 cm in size.
- Perineural spread is common.

Nodal Spread

- Usually to perihepatic nodes around the duodenum and CBD, subpyloric, celiac nodes.
- Hard dark greenish nodes are typical. Often nodal enlargement may be due to just reactive hyperplasia.

Distant Spread

- To *liver* commonly as multiple secondaries in both lobes.
- Occasionally to lungs, adrenals, bran, bone, etc.



Figs 14.34A to C: CT scan pictures of cystadenocarcinoma of pancreas.



Fig. 14.35: On table finding of cystadenocarcinoma of pancreas.

Clinical Features

Presentations

a. Ampullary tumours mainly present with *jaundice and weight loss.*
b. Carcinoma of head and neck region present with weight loss and jaundice.
c. Cystadenocarcinoma of pancreas present with pain, weight loss and mass.



Fig. 14.36: Carcinoma head of the pancreas.



Fig. 14.37: Obstructive jaundice due to periampullary carcinoma in male and female patients.

Features

- *Jaundice is of obstructive nature* which is of short duration, severe, progressive, associated with pruritus (due to deposition of bile salts in the skin which releases histamine). Painless jaundice is seen in ampullary malignancies.
- In periampullary carcinoma sometimes necrosis of tumour occurs, as a result of which jaundice may reduce temporarily thus being *intermittent.*
- Pain in the right hypochondrium, epigastrium, or left hypochondrium depending on location of the tumour.
- Back pain, when present, is due to involvement of retropancreatic nerves, or pancreatic duct obstruction or stasis, disruption of nerve sheath by tumour. Pain is more at night, after food and on recumbency; it is relieved by leaning forward.
- Diarrhoea, steatorrhoea, acholic stools, tea colored urine.
- Silvery stool (due to mixing of undigested fat with metabolised blood derived from the ooze of periampullary growth).
- Loss of appetite and weight.
- Scratch marks on the back.
- *Migratory superficial thrombophlebitis—Trousseau's sign* (10%) is due to release of platelet aggregating factors from the tumour or its necrotic material (Trousseau himself died of carcinoma pancreas who had migrating thrombophlebitis).
- Ascites.
- Left supraclavicular palpable lymph node.
- Secondaries in rectovesical pouch (Blumer's shelf).
- Gallbladder may be palpable which is nontender, soft, globular, smooth, moving with respiration, mobile horizontally, dull on percussion (30% in carcinoma head of pancreas; 50% in periampullary carcinoma). *Courvoisier law* favours gallbladder enlargement.
- Liver is enlarged, smooth, firm, nontender, due to dilated bile filled biliary radicles—*Hydrohepatosis*. Liver can show multiple hard nodules due to secondaries (70%).
- Cystadenocarcinoma of pancreas can present with mass in epigastric region, which is nonmobile, not moving with respiration, smooth, soft, nontender.
- Splenic vein thrombosis with splenomegaly (10%) can occur.

Cystadenocarcinoma of the pancreas

- Common in body and tail of the pancreas
- Epigastric pain which is radiating to back is common
- Mass in epigastrium which is nonmobile, smooth, soft/hard but not moving with respiration. It is resonant, does not fall forward
- Jaundice is not observed
- May mimic pseudocyst of pancreas or retroperitoneal tumours
- 1% of pancreatic malignant tumours
- Papillary cystadenocarcinoma is common
- Mucinous cystic tumours show high levels of CEA
- CT scan is diagnostic
- Distal pancreatectomy is the procedure of choice. In large tumours total pancreatectomy is required
- It has got better prognosis

> *To overcome rigidity of abdomen in refractory cases, with the base of the left hand pressing upon the lower part of the sternum, thoracic respiration is impeded and the abdominal muscles relax.* —**Neville J Nicholson**



Figs 14.38A to C: Mucinous cystadenocarcinoma of distal body and tail of pancreas—CT picture and on table look. Distal pancreatectomy was done (*Courtesy*: Dr Arunkumar, MCh).

Differential diagnosis

- Retroperitoneal mass/tumour/lymph nodes
- Advanced adherent carcinoma of stomach
- Advanced carcinoma of transverse colon
- CBD stone
- Bile duct stricture
- Lymph node compressing CBD
- Cholangiocarcinoma of CBD
- Chronic pancreatitis



Fig. 14.39: Ultrasound showing mass lesion in the pancreas.



Fig. 14.40: CT picture of carcinoma pancreas showing dilated CBD due to obstruction.

Investigations

- Liver function tests: Serum bilirubin, direct component (conjugated) is increased (van den Bergh's test). Serum albumin is decreased with altered A : G ratio. Prothrombin time is widened. Serum alkaline phosphatase is increased.
- U/S abdomen to see gallbladder, liver, growth, CBD size (normal diameter is < 10 mm), lymph node status, portal vein, ascites.
- Barium meal shows widened duodenal "*C" loop—pad sign*. *Reverse 3 sign* is seen in carcinoma—periampullary region.

Differences between presenting features of carcinoma of head of pancreas and periampullary carcinoma of pancreas

		Carcinoma of head of pancreas	*Periampullary carcinoma*
1.	Pain and weight loss	Early features	Late features
2.	Jaundice	Persistent and progressive	Intermittent
3.	Occult blood in stool	Absent	Present; stools are silvery
4.	Endoscopic examination	Growth not visible	Growth visible
5.	Prognosis	Not good	Good



Fig. 14.41: CT picture showing cystadenocarcinoma of pancreas.



Fig. 14.42: ERCP showing growth in the distal CBD.

- Spiral CT scan (ideal) shows portal vein infiltration, retroperitoneal lymph nodes, size of the tumour.
- ERCP with pancreatic juice cytology or brush biopsy is useful. MRCP to see biliary tree.
- CA 19-9 (carbohydrate antigen) is a useful tumour marker. More than 37 units/ml is significant with 85% sensitivity and specificity. CA 494 is useful to differentiate it from chronic pancreatitis. CEA is also often done in suspected cystadenocarcinoma.
- *Coeliac* and superior mesenteric angiogram can be done to reveal tumour circulation and invasion.
- Gastroduodenoscopy reveals ampullary tumour and biopsy can also be taken.
- *Endosonography* is useful to see the invasion and size, to stage and to do EUS guided FNAC.
- Urine for bile salts (*Hay's test*), bile pigments (*Fouchet's test*), urobilinogen.
- *Role of biopsy*:
  - Trucut biopsy and other biopsies are not advisable as it may cause bleeding, infection, leak and negative biopsy will not rule out malignancy. Biopsy is not done in potentially resectable tumour; it is probably useful in inoperable cases to start palliative therapy (chemotherapy). Transduodenal/transgastric or EUS guided trucut biopsy may be useful in such situation.
- Laparoscopy to assess. Laparoscopy and laparoscopic US is useful for staging and to identify peritoneal deposits which prevents unnecessary laparotomy. Palliative laparoscopic bypass like choledochojejunostomy can also be done.
- CT angiogram to see the vascularity. It also provides idea about resectability of the tumour in 70% cases.
- *PTC is useful* if ERCP fails to detect and assess the site of lesion proximally; to decompress the obstructed biliary system through a fine catheter left *in situ* or to place an endobiliary prosthesis across the obstruction.



Fig. 14.43: CT scan abdomen showing features of carcinoma of pancreas.

ERCP signs	***Important investigations***
• Abrupt block of pancreatic duct with irregular stricture • Pancreatic duct encasement • *Double duct sign*—cut off of both pancreatic and bile duct • Parenchymal filling • Scrambled egg appearance	• Spiral CT/3D CT is ideal—to detect operability, portal vein invasion, size, extent, pancreatic and biliary tree and nodal status • ERCP to take biopsy/brush cytology, stenting, to see the luminal extent of the tumour • MRCP is non invasive—entire biliary tree is visualised properly • Endosonography (EUS)—to assess size of primary properly; to take endosonographic FNAC • PTC often with PBD if ERCP fails
Barium meal X-ray	***Investigations to stage the disease***
• Is rarely done in periampullary carcinoma • *Rose thorn* appearance in hypotonic duodenography • *Reverse 3 sign* in periampullary carcinoma • *Pad sign*—widened C loop of duodenum in carcinoma head of pancreas • Features of Gastric outlet obstruction	• 3D/spiral CT scan • EUS • Laparoscopy • ERCP

TNM staging of carcinoma pancreas	***Metastases—M***
Tumour—T	Mx – Distant spread cannot be assessed
Tx – Primary cannot be assessed	M0 – No distant spread
T0 – No evidence of tumour	M1 – Distant spread present
Tis –Carcinoma in situ	
T1 – Growth limited to pancreas < 2 cm	
T2 – Growth limited to pancreas > 2 cm	
T3 – Extension to duodenum or bile duct	
T4 – Extension to portal vein, SMV, SMA, stomach, spleen, colon, celiac axis	
Nodes—N	Staging
Nx – Regional nodes cannot be assessed	0 – Tis N0 M0
N1 – No nodal spread	IA – T1 N0 M0
N2 – Nodal spread present	IB – T2 N0 M0
	IIA – T3 No Mo
	IIB – T1,2,3 N1 M0
	III – T4 Any N M0
	IV – Any T AnyN M1

Resection status

R0 – No residual tumour found after resection
R1 – Microscopic residual tumour after resection
R2 – Macroscopic residual tumour after resection

Preoperative Preparation in Carcinoma Pancreas

- Adequate hydration is important in prevention of dehydration postoperatively. Dehydration is common in obstructive jaundice.
- Glycogen reserve in liver will be inadequate which should be replenished by giving preoperative glucose orally or intravenously.
- Patient is prone to develop hepatorenal syndrome postoperatively, leading into renal failure due to sludging of the bile salts, due to toxins and sepsis; and so mannitol should be given intravenously for 3 days prior to surgery to flush the kidney (200 ml IV twice a day).
- Injection vitamin K 10 mg IM for 5 days.
- ERCP stenting is done to drain bile if serum bilirubin is high (> 30 mg %). Surgery is done after 2-3 weeks once bilirubin level drops down adequately. If ERCP is not possible then percutaneous transbiliary drainage (PTBD) or *cholecystostomy* using Foley's or Malecot's catheter is done. Surgical resection (Whipple's) is done after 3 weeks. Present indications for ERCP stenting are severe albumin deficit and cholangitis.
- Antibiotics one day prior to surgery—cephalosporins/aminoglycosides.
- Often TPN may be required preoperatively which is also continued postoperatively.
- Pulmonary function study and respiratory physiotherapy to have adequate postoperative pulmonary function.

Note:

- In obstructive jaundice, serum bilirubin level will not go beyond 40 mg%. At this point raised intrabiliary pressure (Normal is 12-22 cm of H_2O) to 25 cm of H_2O, blocks the formation of bilirubin and secretion of cholesterol and bile acids completely. Maximum production of bilirubin per day possible is 250 mg%. Normal maximum excretion of bilirubin by kidney per day is 210 mg%. So maximum possible raise of serum bilirubin is 40 mg% in obstructive jaundice.
- Cholangitis in malignant obstruction is rare; but when it occurs it is rather severe form.
- Preoperative albumin therapy is usually *not done.*

Treatment

Only 10-15% of pancreatic carcinomas (head) are operable. 40-50% are locally advanced. Another 40-50% will have distant spread to liver or lungs.

Criteria for resection

- Tumour size less than 3 cm
- Periampullary tumours
- Growth not adherent to portal system

In operable cases:

- *Whipple's operation* is done by removing tumour with head and neck of pancreas, C loop of duodenum, 40% distal stomach, 10 cm proximal jejunum, lower end of the common bile duct, gallbladder, peripancreatic, pericholedochal, paraduodenal and perihepatic nodes. Continuity is maintained by choledochojejunostomy, pancreaticojejunostomy and gastrojejunostomy. Few advocate pancreaticogastrostomy into posterior wall of the stomach. Mortality in Whipple's operation is 2-8%. Original Whipple's operation (1935) was two staged procedure– initial bypass and a second stage resection with closure of pancreatic stump. In 1941, Trimble performed one stage pancreaticojejunostomy. *Complications* are delayed gastric emptying (19%); pancreatic fistula (14%); infection (intraabdominal abscess, wound infection, cholangitis, pancreatitis, pneumonia); bile leak. Mortality is 3%.
- *Traverso-Longmire pylorus preserving pancreaticoduodenectomy* (1978): Here duodenum is cut 2 cm distal to the pylorus and continuity is maintained by anastomosing with jejunum.
- *Fortner's regional pancreatectomy* (extended Whipple's) includes resection like Whipple's along with removal of segment of superior mesenteric vein and clearance of all regional nodes; and portal vein continuity is maintained by a synthetic vascular graft. Even though technically it gives adequate clearance, results are only equivocal.



Fig. 14.44: Whipple's operation.



Fig. 14.45: Specimen of pancreaticoduodenectomy with tumour in the head of pancreas.



Fig. 14.46: Resected specimen (after Whipple's operation) of periampullary carcinoma of pancreas.



Fig. 14.47: On table finding in periampullary tumour showing dilated gallbladder and CBD.

- *Total pancreatectomy is presently said to be better*. It is done along with nodal clearance. Reasons are—possibility of multicentric nature of the disease, higher chance of recurrence after Whipple's operation, malignant cells may be present in pancreatic duct, morbidity by pancreatic fistula or pancreatitis after Whipple's operation is not seen here. Mortality in total pancreatectomy is higher 10-20%. Severe, resistant brittle diabetes mellitus may be seen after total pancreatectomy.


Stomach
C loop
Head
Body
Tail
Spleen
Duodenum

Fig. 14.48: Specimen of total pancreatectomy with C loop, head, body and tail of pancreas with spleen. Total pancreatectomy is done in refractory severe chronic pancreatitis and carcinoma pancreas.

- Distal pancreatectomy or central pancreatectomy or total pancreatectomy for cystadenocarcinoma of pancreas depending on the extent and size of the tumour.


Tumour
Spleen
Pancreas

Fig. 14.49: Photo showing spimen of distal pancreatectomy.

In inoperable cases:

Here mainly to *palliate* obstructive jaundice, duodenal obstruction and pain.

- Roux-en-Y choledochojejunostomy is ideal palliative procedure along with gastrojejunostomy after doing cholecystectomy. Choledochojejunostomy is better than cholecystojejunostomy as CCJ may get blocked either by tumour infiltration or by bile sludge or by inflammation. 30% of periampullary carcinoma/carcinoma of head of pancreas eventually develop gastric (duodenal) outlet obstruction and so gastrojejunostomy is undertaken.
- ERCP and stenting is done to drain bile. Problem here are recurrent cholangitis, stent blockage and displacement, requirement of repeated stenting procedure. Duodenal stenting for duodenal obstruction is tried.
- Chemotherapy; neoadjuvant chemotherapy.
- Steatorrhoea is treated by enzymes. Control of diabetes is important.


Liver
CBD
CDJ
Stomach
GJ
Pancreas
Tumour
JJ
Jejunum

Fig. 14.50: Choledochojejunostomy (CDJ) with gastrojejunostomy (GJ) and jejunojejunostomy (JJ). It is a Roux-en-Y anastomosis. CDJ should be 70 cm from the JJ.


Liver
Stomach
CBD
GB
Cholecysto-jejunostomy
Gastro-jejunostomy
Duodenum
Jejunum
Jejuno-jejunostomy

Fig. 14.51: Cholecystojejunostomy—is not a preferred method.



Fig. 14.52: White bile. It is neither white nor bile. It is opalescent; and is mucous. It suggests complete obstruction. It is usually observed in carcinoma pancreas. It is peroperative finding.

Adjuvant Therapy

- Adjuvant chemotherapy using gemcitabine—better but costly; dose is 1000 mg/m^2 surface area; 5-fluorouracil; mitomycin; vincristine, cisplatin, docetaxel, oxaliplatin are used along with gemcitabine.
- Radioactive iodine seeds I^{125} to the field are on trial. External radiotherapy 4000 cGy units to relieve pain and to reduce the tumour size.
- *Immunotherapy*—specific type to increase the effectiveness of chemotherapy and to improve the cure rate (allogenic tumour cell vaccine).

Neoadjuvant Chemoradiotherapy

Only 20% of pancreatic carcinomas are amenable for surgical resection. Even in these patients in spite of resection, overall outcome is poor. So neoadjuvant chemoradiotherapy is becoming popular [(50 Gy dose of *radiotherapy* for 5-6 weeks (25-30 fractions) with *infusion chemotherapy*, then *surgical resection*)] and under trial to improve the resectability and survival. It increases the R0 resection status and reduces the node positive rate. There is less chance of tumour hypoxia (which is more after surgery) by which increases the susceptibility of tumour to chemoradiotherapy; less chance of mucosal anastomotic toxicity. It reduces the tumour burden at surgery; decreases the local or regional recurrence; decreases the chances of pancreatic fistula. *But* there is no survival benefit.

Postoperative Management in Carcinoma Pancreas

- Maintenance of proper fluid and electrolyte balance.
- Observation for bleeding and its control by transfusion of blood, fresh frozen plasma (FFP), and prevention of DIC at initial period.
- Injection vitamin K 10 mg IM for 5 days.
- Respiratory care—ideally postoperative ICU care is better. Often ventilator is needed for 24 hours
- Maintaining adequate urine output—mannitol should be continued.
- Injection octreotide infusion for 5 days to suppress pancreatic secretion so as to prevent leak.
- Antibiotics, nasogastric aspiration.
- Continuous monitoring the patient with pulse/blood pressure/oxygen saturation/hourly urine output/inspection of drain site/abdomen distension/by doing HB%, LFT, serum creatinine, bilirubin, arterial blood gas analysis if needed, platelet count, prothrombin time.

Pain Control in Carcinoma Pancreas

- CT guided 50% of 20 ml ethanol injection into coeliac ganglion.
- Epidural anaesthesia.
- Opioids administration.
- Transthoracic splanchnicectomy—greater splanchnic nerve.
- Palliative radiotherapy—4000 cGy units.

Prognostic factors in carcinoma pancreas—poor prognosis

- Mean survival rate 6-9 months
- Growth more than 3 cm
- Nodal involvement
- Resection status—R0/R1/R2
- Portal vein infiltration
- Liver/lung secondaries
- Ascites/Trousseau's sign/left supraclavicular lymph nodal spread
- *White bile* on table carries poor prognosis
- Associated problems like pancreatitis, diabetes mellitus
- Liver dysfunction

ENDOCRINE PANCREATIC TUMOURS

- Most common is insulinoma.
  Others are gastrinoma, glucagonoma, vipoma, pancreatic polypeptidoma.
- They belong to group of tumours called "APUDOMAS".
- Endocrine tumours are associated with MEN syndrome (Type I Werner's syndrome).
- They are associated with:
  - Parathyroid adenoma.
  - Pituitary adenoma.
  - Peptic ulcer.
- They are usually multiple, small, 35-50% are malignant and presents with features of endocrine lesion. Commonly occurs in body and tail (except gastrinomas).
- Requires special method to identify.
- MRI, angiogram, hormone assay are the diagnostic methods required.
- Normal islet cells are < 2% of pancreatic mass. They contain α, β, δ, G, D2 and PP cells (pancreatic polypeptide).
- Incidence is 5 per 100000 per year.

Those who wish to sing always finds a song.

- 20% are nonfunctional.
- Insulinomas are commonly benign; glucagonomas are almost always malignant.

INSULINOMAS

- Insulinomas are commonest endocrine pancreatic tumour (60%) arising from B cells (β cells) of pancreas.
- They are commonly solitary but 10% can be multicentric and secrete insulin in excess causing profound hypoglycaemic features.
- Equal in both sexes.
- 90% of insulinomas are < 2 cm in size.
- 15% are malignant. 85% are benign.

Clinical Features

- Abdominal discomfort, trembling, sweating, hunger, dizziness, diplopia, hallucinations. Later epilepsy and unconsciousness. They are usually over weight.
- Weight gain is common due to overeating.
- Permanent neurological deficits can occur with behavioural changes.

Whipple's triad:

- An attack of hypoglycaemia in fasting state
- Blood sugar below 45 mg% during the attack
- Symptoms relieved by glucose

Diagnosis

- Insulin radioimmunoassay. An insulin level > 7 μU/ml; insulin/glucose ratio > 0.3 signifies insulinoma. Proinsulin level more than 24% of total insulin signifies insulinoma. Proinsulin level more than 40% of total insulin signifies malignant insulinoma. C peptide level > 1.2 μg/ml with glucose level < 40 mg% suggests insulinoma.
- MRI to localize the tumour.
- Angiogram (coeliac).
- Endosonography.
- On table U/S.
- Blood sugar estimation.
- Insulin provocation test using calcium gluconate or tolbutamide.

Radioimmunoassay in insulinoma

- Increase in insulin levels of plasma
- Increased ratio of proinsulin to insulin > 20%
- Increased circulating C-peptide
- Plasma insulin to glucose ratio > 0.3 is diagnostic

Differential Diagnosis

- Nesidioblastosis.
- Noninsulinoma pancreatogenous hypoglycaemia.

Treatment



Figs 14.53A to C: Insulinoma imaging picture and on table look (*Courtesy:* Dr Arunkumar, MCh).

Treatment of insulinoma

- Enucleation commonly, often distal pancreatectomy
- Diazoxide, beta blockers, phenytoin, verapamil, steroids, growth hormone to control hypoglycaemia
- Octreotide decreases the insulin secretion
- Calcium channel blockers
- Streptozotocin whenever secondaries are present in liver or elsewhere

- Enucleation of all tumours.
- Often distal pancreatectomy is required (spleen; tail and body of the pancreas are removed) 90% are curable.

GASTRINOMAS

- They arise from non-beta cells (G cells) of the pancreas, which secretes high levels of gastrin.
- It is 2nd most common endocrine pancreatic tumour.
- It is the commonest endocrine pancreatic tumour seen in MEN I syndrome. In MEN II syndrome lesion is often seen in duodenum (30%).
- It is common in males.
- Common in gastrinoma triangle (*Passaros triangle*).



Fig. 14.54: Passaros triangle.

Three points forming Passaros triangle:

1. Junction between the head and neck of the pancreas
2. Junction of cystic duct with CBD
3. Junction between the 2nd and 3rd parts of the duodenum

- Half of them are multiple and malignant (50%).
- It causes severe, multiple peptic ulcers in the stomach, duodenum and jejunum.
- It is due to hypergastrinaemia causing high levels of acid secretion.
- Other features are diarrhoea, steatorrhoea, hypokalaemia.
- It causes ZES type II.
- When malignant commonly present with secondaries in liver (80%)/lymph nodes/lungs or bones.

Salient features of ulcers in gastrinomas

- Multiple ulcer
- Resistant ulcer/refractory ulcer
- Jejunal ulcer
- Recurrent ulcer
- Ulcer which is more prone for bleeding and perforation

Investigations

- Gastrin assay (normal level < 200 pg/ml).
- Gastroscopy.
- U/S, Endosonography.
- MRI (more sensitive) or CT scan to detect the site of the tumour.
- Angiogram.
- Increased gastrin level by calcium (injection IV) provocation test.
- Pentagastrin test (both shows very high basal and peak levels).
- Secretin provocation test.
- Somatostatin receptor scintigraphy (SRS) with radiolabeled octreotide is used to locate the site of tumour.

Note:

Normal level of gastrin is 100-150 pg/ml. It is more than 200 pg/ml in gastrinoma patients. It usually reaches upto or greater than 1000 pg/ml in gastrinoma. Other causes of hypergastrinaemia like G cell hyperplasia, incomplete antrectomy, low gastric acid level, achlorohydria, pernicious anaemia, acid controlling drugs like H2 receptor block or proton pump inhibitors and atrophic gastritis should be ruled out. Basal acid output in gastrinoma is > 15 mEq/hour which is specific of gastrinoma (ZES II). Gastric pH more than 3 rules out gastrinoma. *Secretin stimulation test* by injecting 2 units/ kg secretin IV and assessing blood samples before and every 5 minutes after injection of secretin for 30 minutes will show rise in gastrin level more than 50% of baseline.

Treatment

60% are curable.

- Enucleation of tumours.
- Distal pancreatectomy.
- Pancreaticoduodenectomy.
- Subtotal pancreatectomy.
- Often total gastrectomy may be required.

Remember

- Gastrinomas are often associated with MEN syndrome and are multiple
- Sporadic gastrinomas are often solitary and then are malignant
- Gastrinoma often secretes ACTH
- Most common malignant endocrine pancreatic tumour is gastrinoma
- Gastrinoma causes ulcer of unusual nature (refractory/ resistant); unusual recurrence (repeated and multiple); unusual number (multiple); unusual sites (2nd/3rd part duodenum/jejunum); unusual age (young and aged)

It is better to aim at good things and miss it, than to aim at a bad thing and hit it.

Triad of somatostatinoma

- Diabetes mellitus
- Steatorrhoea
- Cholecystolithiasis

GLUCAGONOMAS

- Arise from α cells of pancreas.
- Common in body and tail of pancreas.
- It is common in females.
- It attains large size of 5-10 cm.
- It is commonly sporadic. 17% associated with MEN type II syndrome.
- It is commonly malignant (80%). 80% spreads to liver.

Clinical Features

- Necrolytic migratory erythema (65%).
- Diabetes (90%).
- Diarrhoea and weight loss.
- Stomatitis.
- Anaemia and features of amino acid deficiency.
- Vulvovaginitis is common.

Investigations

- MRI, CT scan.
- Endosonography.
- Angiogram.
- Increased serum glucagon level. Fasting glucagon level more than 50 p mol/litre is diagnostic.

Treatment

- Correction of anaemia, protein and amino acid deficiency by enteral/parenteral nutrition.
- Intravenous amino acid infusion to control necrolytic dermatitis.
- Prevention of DVT.
- Distal pancreatectomy.
- Occasionally Whipple's/total pancreatectomy is needed.
- Enucleation is rarely sufficient for glucagonoma.
- Dacarbazine is specifically effective in glucagonoma.

Vipoma

- Arising from D2 cells of pancreas
- Watery diarrhoea, hypokalaemia, achlorohydria (WDHA syndrome)
- Also called as *pancreatic cholera or Verner-Morrison syndrome, weak—tea syndrome*
- Usually malignant
- Secretes vasointestinal polypeptide > 150 pg/ml
- Common in body and tail—solitary
- Distal pancreatectomy is the treatment of choice
- Prednisolone controls the diarrhoea
- Octreotide is useful

ZOLLINGER-ELLISON SYNDROME

Type I: "G" cell hyperplasia with hypergastrinaemia and chronic peptic ulceration.

Treatment is partial gastrectomy with removal of "G" cell area.

TYPE II: Gastrinomas (see above).

Note:

- Somatostatinoma arises from δ cells of pancreas. It is exceedingly rare. Usually larger than 2 cm and single. It is common in head of pancreas and duodenum. Its association with MEN II syndrome is rare. It is often associated with neurofibromatosis type I and phaeochromocytoma. Presentations are steatorrhoea; diabetes mellitus; gallstones; hypochlorohydria and occasional jaundice. Tumour is commonly malignant and commonly present with nodal and liver spread. Elevated fasting somatostatin level is diagnostic. Treatment is pancreaticoduodenectomy.
- 20% of pancreatic endocrine tumours are nonfunctional. Nonfunctional means these tumours do not produce hormones or produced hormones will not produce any symptoms.
- Pancreatic polypeptide tumour (PP tumour) is classified under the non functioning endocrine tumour as it does not cause any symptoms even though there is high pancreatic polypeptide. It is commonly malignant, often with spread. PPoma occurs predominantly in head of pancreas. Pancreaticoduodenectomy is the treatment.

CYSTIC FIBROSIS

It is inherited as an autosomal recessive disease. It causes—

1. *Severe exocrine dysfunction*—due to blockage of pancreatic ducts as a result of precipitation of pancreatic enzymes leading to duct ectasia.
2. *Chronic pulmonary disease* due to blockage of bronchi and bronchioles.
3. *Elevated sodium and chloride*—in the sweat more than 90 mmol/L.
4. It is common in Caucasians. It is inherited as mutation in cystic fibrosis transmembrane conductance regulator gene in chromosome 7.

Presentations

- Chronic pulmonary disease with emphysema, bronchiectasis.
- Steatorrhoea.
- Meconium ileus with intestinal obstruction.
- Salty sweat (while kissing the baby).
- Poor growth due to malabsorption.
- Cirrhosis of liver due to bile plugging.
- Pancreatitis is common.
- Sialadenitis, choroiditis can occur.
- Absence of vas deferens in men.

Diagnosis

- DNA study.
- Vomitus when put on an exposed X-ray film will not digest the gelatin in half an hour (wherein in normal individual vomitus contains trypsin which will digest the gelatin of X-ray film and turns white).

- U/S abdomen.
- Sweat test for sodium and chloride.
- Pulmonary function tests.

Treatment

- Low fat and salt rich diet.
- Correction of malabsorption.
- Pancreatic enzyme supplements.
- Antibiotics.
- Respiratory physiotherapy.
- If meconium ileus is present, it might require surgery, i.e. Bishop-Koop operation.

Prognosis is poor.

Problems in cystic fibrosis

- Meconium ileus
- Recurrent respiratory infection and complications
- Sodium deficit
- Severe malnutrition
- Sialadenitis, choroiditis
- Cirrhosis of liver
- Usually die in childhood or early age group

ANNULAR PANCREAS

It is due to failure of complete rotation of ventral bud of pancreas, so that ring of pancreatic tissue encircles the 2nd part of the duodenum causing obstruction. It contains a duct that joins the main pancreatic duct.



Fig. 14.55: Annular pancreas.

Clinical Features

- Distension of upper abdomen.
- Bilious vomiting.
- Visible gastric peristalsis.
- It is often associated with the Down's syndrome, and other congenital gut abnormalities.

Types

- *Neonatal type*—produces symptoms of intestinal obstruction.
- *Adult type*—presents after the age of 20. Presents with features of duodenal ulcer and bilious vomiting.

Differential Diagnosis

- Duodenal atresia.
- Wilkies syndrome.

Investigations

- Plain X-ray abdomen shows double-bubble appearance.
- ERCP and Radioisotope study.
- Barium meal shows obstruction at 2nd part of duodenum.

Treatment

- *Duodenoduodenostomy—Ideal.*
- Duodenojejunostomy.
- **Do not resect the ring.** Attempt at resection will lead to pancreatic fistula.
- G-J is not done.

ECTOPIC (ACCESSORY) PANCREATIC TISSUE

Sites

- Stomach wall.
- Small intestine.
- Meckel's diverticulum.
- Greater omentum.
- Splenic hilum.
    - In the bowel it may be in the submucous or intramuscular plane. It may precipitate intussusception.
    - About 30-33% contain islet of Langerhan cells. Often endocrine pancreatic tumour can arise from ectopic pancreas.
    - It may cause upper GI bleed.

PANCREATIC DIVISUM

- During development ventral pancreatic bud with distal bile duct is towards right and dorsal pancreatic bud is towards left side. Ventral pancreatic bud forms uncinate process and inferior part of the head of the pancreas. Dorsal bud forms body and tail of the pancreas. Ventral bud rotates clockwise towards left from behind the duodenum to join dorsal bud to form pancreas. Ventral pancreatic bud duct forms main pancreatic *duct of Wirsung*; dorsal bud duct forms accessory pancreatic *duct of Santorini*.
- *Pancreatic divisum* is failure of fusion of ventral and dorsal pancreatic ducts. So that dorsal pancreas drains through duct of Santorini (proximal minor papilla); ventral one drains through duct of Wirsung into *major papilla of Vater*.

No problem can stand the assault of sustained thinking.

- Its incidence is 10%.
- Here major pancreatic secretion drains through minor papilla causing partial obstruction precipitating pancreatitis.

PANCREATIC CALCULUS

Causes

- Chronic pancreatitis commonly due to dietary factors, familial, hyperparathyroidism.
- Commonly they are multiple and associated with or due to chronic pancreatitis.

Pathogenesis

Stricture of pancreatic duct and stasis of pancreatic secretion.

Types

a. **Calculi in the duct**:
  - Here parenchyma is still functioning and less severely affected.
  - Duct is dilated significantly (more than 3 mm) with multiple large stones in the duct along with multiple strictures.
  - Duct is having dilatation alternating with strictures—*chain of lake appearance.*
    - Plain X-ray abdomen shows stones placed horizontally at L_1-L_2 level.
    - U/S, ERCP, MRCP are other useful investigations.
    - Blood sugar should be checked.



Figs 14.56A and B: CT scan picture showing pancreatic ductal stones. Stones that are removed from the same patient are also shown. Patient underwent longitudinal pancreaticojejunostomy.

Treatment

The duct is opened longitudinally and after removing all stones, side-to-side pancreaticojejunostomy is done.

b. **Calculi in the Parenchyma**
  - Here multiple calcifications occur in the pancreatic parenchyma with pre-existing chronic pancreatitis. Gland is fibrosed and severely affected with less functioning capacity.
  - Plain X-ray, U/S, ERCP, MRCP are the diagnostic methods.

Treatment

- *Total pancreatectomy.*
- It is more likely to turn into carcinoma pancreas.

PANCREATIC ASCITES

- It can occur in chronic pancreatitis or as a complication of acute pancreatitis or in ruptured pseudocyst of pancreas or after pancreatic trauma (10%, in children trauma is the cause).
- It may be associated with pleural effusion which can be both sided but commonly on left side. Often pleural effusion and ascites may be massive. It is due *to internal pancreatic fistula.*
- Incidence is 1%. If not treated mortality is 30%.
- It is due to leakage from disrupted pancreatic duct or ruptured pseudocyst. Anterior disruption causes pancreatic ascites. Posterior disruption causes fluid to travel along oesophageal and aortic hiatus resulting in pleural effusion.
- Pancreatic ascites and fistula are common in pancreatitis due to alcohol intake. It is less common in pancreatitis due to biliary tract disease.
- U/S, very high amylase and protein levels in ascites fluid, ERCP to identify leak, CT scan are the essential investigations.
- Repeated ascitic tap; pleural tap; TPN; somatostatin or octreotide to reduce pancreatic secretion are tried as conservative therapy for 3 weeks. 50% respond to this therapy.
- If there is no improvement beyond 3 weeks, ERCP stenting of pancreatic duct is done initially. Then resection (better option) or drainage (jejunal loop Roux-en-Y anastomosis directly over disrupted duct) surgery is done. Pancreatic pleural effusion disappears once abdominal cause or ascites is corrected.

PANCREATIC FISTULAE

Types

External and internal fistulae.

External Fistulae

Types

a. Low output fistulae < 200 ml.
b. High output fistulae >200 ml.
(*Note:* For other GI fistulae it is 500 ml)

Causes

- Whipple's operation.
- Pancreaticojejunostomy.

- Splenectomy.
- Colonic surgeries.
- Trauma.
- After external drainage of the infected pseudocyst of pancreas.
- After percutaneous drainage of the pseudocyst.

Clinical features

- Patient is in a catabolic state.
- Skin excoriation.
- Electrolyte imbalance.
- Malnutrition.
- Sepsis.

Investigations

- CT scan.
- ERCP.
- Fistulogram.
- Amylase estimation of the discharge.

Treatment

Conservative treatment:

- Total parenteral nutrition.
- Zinc oxide cream for skin excoriation.
- Correction of electrolyte imbalance.
- Antibiotics.
- Octreotide.

Surgery:

- Roux-en-Y anastomosis.
- Resection of fistula with pancreas.
- Endoscopic stenting of the pancreatic duct.

Internal Fistulae

- Communicating pseudocyst.
- Pancreatic ascites.
- Pancreatic pleural effusion.
- Pancreatic-enteric fistulae.

Complications of pancreatic fistulae

- Septicaemia
- Malnutrition
- Bleeding due to erosion of vessels
- Electrolyte imbalance
- Severe skin excoriation

PANCREATIC ABSCESS

- 5% common.
- It can occur immediately after an attack of acute pancreatitis or in an existing pseudocyst.
- Common in alcoholics and gallstone diseases.
- Mortality is 25%.
- *Pancreatic abscess* is collection of pus in lesser sac (intraabdominal) in relation to pancreatic surface which contains mainly pus with only less or no necrotic pancreas. It may slough off the pancreatic/ splenic vessel wall to cause torrential haemorrhage. Abscess may be single or multiple (60%). It is commonly in head/body or tail. But often entire gland may be involved (25%). Abscess may rupture into viscera or extend into other part of the abdomen.

Clinical Features

- Persistent pain abdomen.
- Tender epigastric mass.
  Commonest organism involved is *E. coli.*

Investigation

- Ultrasound and CT scan are diagnostic.
- CT guided FNA and Gram's staining and culture.

Treatment

- Antibiotics.
- Open surgical drainage with cystogastrostomy.
- U/S guided aspiration.
- *CT guided insertion of polythene catheter.*

Complications

- Septicaemia.
- Haemorrhage due to erosion of splenic vessels.
- Recurrent abscess formation.

PANCREATIC NECROSIS

It is diffuse or focal area of nonviable parenchyma of pancreas, occurs during an attack of severe pancreatitis that is associated with peripancreatic fat necrosis. It occurs in 20% of acute pancreatitis.

Types

- Sterile necrosis is 60% of total pancreatic necrosis. Mortality here is 10%.
- Infected necrosis is 40% of total necrosis. Mortality here is 30-40%, very high. Risk of infection is 25% in one week of acute attack; 35% at the end of 2nd week; and 70% at the end of 3rd week.
- Necrosis extends to retroperitoneal fat, mesentery, retrocolic and perinephric areas.

Pathogenesis

- Premature activation of proteolytic enzymes.
- Intrapancreatic vessel thrombosis.

- Pancreatic microcirculation failure.
- Release of inflammatory mediators.

Mode of Infection

- Haematogenous.
- Reflux through ampulla.
- Mucosal translocation of bacteria.
- From the biliary tree.
- Lymphatic route.
- Transperitoneal spread.

Bacteria

- 65% are polymicrobial.
- *E. coli* is commonest.
- Others are—*Proteus*, *Pseudomonas*, *Klebsiella*, staphylococci, *Streptococcus faecalis*, enterococci, anaerobes, *Clostridium welchii*.

Diagnosis

- Clinical features.
- CT scan abdomen and CT guided FNA for Gram's staining and culture.
- CRP value—> 120 mg/litre; interleukin level; elastase level; urinary TAP assessment.

Treatment

- Antibiotics—imipenem, cefuroxime, ofloxacin, meropenem.
- Percutaneous drainage.
- Laparotomy, necrosectomy, debridement, saline wash, closure with tube irrigations/lavage.

Complications

- Septicaemia, ARDS, renal failure, MODS.
- Pancreatic fistula after surgery.
- Intra-abdominal abscess.
- Abdominal dehiscence, incisional hernia after surgery.

PANCREATIC TRAUMA

- It is rare because of its anatomical location - retroperitoneum.
- Its injury is usually associated with injuries to liver/ duodenum/spleen/portal system/biliary system/ kidney.
- Deep force in epigastrium may cause crushing of body of pancreas against vertebra—closed injury.
- Penetrating injury may cause direct sharp injury of pancreas.

Types

- Parenchymal contusion/laceration without duct disruption.
- Parenchymal injury with duct disruption.
- Complete transection of pancreas.
- Massive destruction of pancreatic head.

Classification

Pancreatic injury
Class I Capsular damage; minor parenchymal injury
Class II Transection of duct in body or tail—partial or complete
Class III Major duct injury in pancreatic head or intrapancreatic CBD injury
Duodenal injury
Class I Contusion, hematoma, partial thickness injury
Class II Full thickness duodenal injury
Class III Full thickness duodenal injury with
1. More than 75% circumference injury
2. Extrapancreatic CBD injury

Combined pancreatico duodenal injury

Type I Class I injury to both organs/class I injury of one organ with class II injury to other
Type II Class II injuries of both organs
Type III Class III injury to one organ with less severe injury to other
Type IV Class III injury to both organs

Grading of pancreatic injury

Grade I – Minor contusion/laceration without duct injury
Grade II – Major contusion/laceration without duct injury
Grade III – Distal transection or injury with duct involvement
Grade IV – Proximal transection or injury with involving ampulla
Grade V – Massive disruption of pancreatic head

Features

- Pain in epigastrium.
- Features of associated injuries.
- Features of shock.
- Rise in serum amylase level is common.

Investigations

- CT scan is diagnostic.
- ERCP to confirm duct disruption.
- Assessment of blood loss and other injuries.

Treatment

- Commonly conservative with fluid management; blood transfusions; antibiotics; pain relief.
- Surgery is needed when there is:
    - Major ductal disruption.
    - Vascular injury.
    - Extensive injury to head.
    - Other organ injury.

Surgeries are

- Proper exploration and haemostasis.
- In neck transection, distal pancreatectomy with splenectomy.

- In injury to head, haemostasis and external drainage is done.
- Pancreaticoduodenectomy is done if there is major injury.
- Choledochojejunostomy is done if there is CBD injury.
- Different pancreatic drainage procedures are done to prevent sepsis and fistula.
- Portal system injury carries poor prognosis. It needs repair or intervening graft placement to control and maintain the continuity.

Prognosis

- Depends on type and class of injury and other associated injuries.

Complications

- Haemorrhage.
- Septicaemia.
- Pancreatitis—acute/recurrent.
- Pseudocyst formation.
- Pancreatic fistula.
- Pancreatic abscess.
- Pancreatic duct stricture at the site of duct injury as a delayed complication.

CYSTIC LESIONS OF PANCREAS

Types

1. True pancreatic cysts:
    - Congenital.
    - Not premalignant.
    - Asymptomatic.
    - May be associated with cystic diseases of liver, kidney.
    - Multiple true pancreatic cysts (polycystic disease of pancreas) are common than solitary true cyst. They are lined with cuboidal epithelium and are associated with *von Hippel Lindau disease* in 50% of patients. They don't require any treatment.
2. Pseudocyst of pancreas.
3. Cystic tumours of pancreas.
    a. Serous cystadenoma.
    b. Mucinous cystadenoma.
    c. Cystadenocarcinoma.
    d. Angioma.
    e. Cystic teratomas.
4. Hydatid cyst of the pancreas.

EXOCRINE PANCREATIC DISEASE

Causes

- Pancreatitis.
- Cystic fibrosis.
- Pancreatic resections.

Investigations

- *72 hours faecal collection* for estimation of daily faecal fat: In a person ingesting 100 gm of fat/day, if faecal excretion of fat is more than 7 gm/day, it signifies pancreatic insufficiency. It is the most sensitive and specific test (Presence of neutral fat suggests pancreatic disease whereas split fat suggests small bowel disease).
- *Secretin-cholecystokinin stimulation test* shows duodenal fluid normally contain more than 80 mEq/L HCO_3^- and HCO_3^- greater than 15 mEq/30 minutes.
- *PABA excretion in the urine* after ingestion of bentinomide, if less than 50% it signifies pancreatic insufficiency.
- Serum trypsin level is low in pancreatic insufficiency.
- Pancreolauryl test.
- Triolin breath test.
- *Lundh test*—Duodenal juice collected 2 hours after meal shows trypsin level > 8 mEq/ml. It is very low in chronic pancreatitis (Goran Lundh).
- Glucose tolerance test.

Treatment of Pancreatic Insufficiency

- Low fat diet.
- Pancreatin enteric coated tablets during meals.
- Cause is treated.

In between goals is a thing called life, which has to be lived and enjoyed.

Chapter 15 Retroperitoneal Space

CHAPTER OUTLINE

- Anatomy of Retroperitoneum
- Retroperitoneal Fibrosis
- Retroperitoneal Swellings
- Retroperitoneal Tumours
- Psoas Abscess

ANATOMY OF RETROPERITONEUM

This is the space between the peritoneal cavity and posterior abdominal wall. It is bounded anteriorly by posterior parietal peritoneum; posteriorly by vertebral column, psoas muscles, quadratus lumborum muscle and tendinous portion of transversus abdominis muscles; superiorly by diaphragm; inferiorly by pelvic levator muscles (by Ackerman). It is real potential space.

Diseases of retroperitoneal spaces

- Retroperitoneal fibrosis
- Retroperitoneal cysts
- Retroperitoneal tumours
- Retroperitoneal lymphomas
- Retroperitoneal vascular diseases, e.g. aneurysms
- Retroperitoneal trauma and haematoma
- Retroperitoneal infection, e.g. psoas abscess, pyogenic abscess

Diseases of the specific retroperitoneal organs, e.g. adrenals, kidney.

RETROPERITONEAL FIBROSIS

- *Idiopathic type (70%) is called as* ***Ormond's disease*** which is associated with mediastinal fibrosis, Dupuytren's contracture, plantar fasciitis, Peyronie's disease, Riedel's thyroiditis, sclerosing cholangitis, mesenteric panniculitis, pseudotumour of the orbit and other fibromatosis. It is nonspecific inflammation of fibrofatty tissue in the retroperitoneum.
- Patient presents with severe and persistent *back pain.*
- Diffuse fibrosis in retroperitoneum can compress both ureters leading to bilateral hydronephrosis and renal failure.
- Extravasation of urine, ascending lymphangitis, and autoimmune cause are the aetiologies.
- In 30% cases it is bilateral. Hypertension, lower limb oedema (lymphatic or venous block), feeble lower limb arterial pulses are common.
- It is like woody fibrous tissue which narrows ureters, vessels and nerves. Ureteric obstruction commonly in lower 1/3rd causing dysuria, frequency, oliguria, renal failure. Venous and lymphatic oedema of limbs can occur.
- It may be localised or generalised. Generalised type (15%) may extend into duodenum, CBD and pancreas. It is not encapsulated but margin is well-demarcated.
- It can also cause vascular compression, both venous and arterial.
- Disease is progressive one.



Fig. 15.1: Anatomy of retroperitoneal space.

Investigation

- U/S
- IVU—diagnostic:

Triad

- Deviation of middle 1/3rd of ureter medially
- Hydroureteronephrosis
- Extrinsic ureteral compression

- Blood urea and serum creatinine, raised ESR and CRP.
- CT scan.

Treatment

- *Drug therapy*: Methylprednisolone, azathioprine, penicillamine, tamoxifen.
- Cystoscopic stenting of the ureters to prevent renal failure.
- Symptomatic treatment: If stenting fails, bilateral nephrostomy is done.
- Ureterolysis.
- Lateral repositioning of ureters.
- Omental wrap after ureterolysis.
- Vascular bypass graft for vascular encasement.

Other causes for retroperitoneal fibrosis (30%)

- Methysergide and beta blocker drugs
- Urine leak and collection in the space
- Haematoma, blood collection
- Advanced malignancy, radiation.
- Ergot's alkaloids, dopamine agonists
- Retroperitoneal surgeries, haemorrhage
- Trauma, infection

RETROPERITONEAL SWELLINGS

Types of retroperitoneal (RP) tumours (0.3 to 3%)

Benign—20% of RP tumours

- Retroperitoneal lipoma
- Retroperitoneal neurofibroma, neurilemmoma
- Retroperitoneal leiomyoma
- Extra-adrenal chromaffinomas
- Paraganglioma
- Mucinous cystadenoma
- Haemangiopericytoma

Malignant—80% of RP tumours

- Retroperitoneal liposarcoma, leiomyosarcoma—50%
- Retroperitoneal lymphoma (commonly NHL)
- Malignant tumours from specific organs
- Germ cell tumours, chordomas
- RPLN secondaries with hard nodules

Note:

- Tumours of retroperitoneal organs like kidneys, ureters, pancreas, and adrenals are conventionally *not included* in retroperitoneal tumours.
- *Paragangliomas* are of neural crest origin that arises from paraganglionic tissues distributed along the major vasculatures (abdominal aorta in abdomen) or sympathetic chain, may be functioning or nonfunctioning. 20% secrete catecholamines. They may be multiple. Only 0.5% of cases present with hypertension. It can be familial, often associated with von Hippel Lindau disease and RET proto-oncogene. It may arise from *type I cells* as chromogranin A positive—NSE positive; or *type II cells* as S 100 positive with good prognosis.
- *Costello syndrome* is mental retardation, benign papilloma; develop embryonal rhabdomyosarcoma.
- *Retroperitoneal cysts* are—cysts arising from Wolffian remnants or urogenital tract; RP mesenteric cyst; teratomatous dermoid cysts; RP lymphatic cyst; parasitic cysts.



Fig. 15.2: Retroperitoneal tumour can attain very large size often. It causes deviation of ureter laterally often may invade the ureter (In retroperitoneal fibrosis ureter is deviated medially). It may invade or encase the IVC also causing IVC obstruction with features of bilateral oedema feet, dilated lateral abdominal wall vein with upward direction flow of blood.

Features of the Retroperitoneal Mass

- It is usually large.
- Not moving with respiration.
- Nonmobile.
- Does not fall forward (confirmed by knee-elbow position).
- Deeply placed.
- Resonant on percussion (because of the bowel in front).



Fig. 15.3A



Fig. 15.3B

Figs 15.3A and B: Retroperitoneal tumour—benign lipoma was excised with a loin retroperitoneal approach.

- In retroperitoneal cyst and sarcoma the swelling is smooth.
- In lymphoma it is smooth and firm.
- In aneurysm it is pulsatile (expansile pulsation) which will persist even in knee-elbow position.
- Confirmation is by U/S, CT scan, MRI.
- Most common retroperitoneal benign tumour is lipoma.
- Sarcoma (*commonest is liposarcoma 40%*) which attains a very large size, goes for myxomatous degeneration very early and is aggressive.

RETROPERITONEAL TUMOURS

- Retroperitoneal tumour can be *benign or malignant* (refer table above); *solid or cystic*. Solid tumours are commonly malignant (85%); cystic tumours are usually benign.



Fig. 15.4: Retroperitoneal leiomyosarcoma, CT picture.

- Malignant retroperitoneal tumour may be *mesodermal (75%),* neuroectodermal (24%) or embryonic remnant (1%) in origin. Rarely it can be urologic or metastatic also. Sarcoma is the most common malignancy; *in adult*—liposarcoma is the *most common* retroperitoneal sarcoma (50%); leiomyosarcoma is 30%; malignant nerve sheath tumour (5%); fibrosarcoma (5%); malignant fibrous histiocytoma (MFH—10%) can also occur. 20% show neurological deficit; 40% show distant blood spread. *In children* rhabdomyosarcoma is the most common one. 15% of all sarcomas are of retroperitoneal.



Fig. 15.5: Retroperitoneal tumour, on table finding. It was large and inoperable.

Aetiology

- Retroperitoneal tumors may be associated with radiation; exposures to chemicals like vinyl chloride/thorium dioxide, familial Gardner's syndrome, familial retinoblastoma or familial neurofibromatosis, Li Fraumeni syndrome, germline mutations of p53 in chromosome 17.

Features

- Tumor arises from fat, areolar tissue, vessels, nerves, skeletal and smooth muscle, fascia, lymph node and lymphatic systems and tissues of embryologic origin. Sarcomas can be commonly solid, cystic or mixed. Usually tumour develops a pseudocapsule. Liposarcoma often originates from (> 30%) perinephric fat.
- *Liposarcoma* can be well-differentiated (60%) or undifferentiated (dedifferentiated). It spreads along the fascial planes *enveloping* the organs. Infiltration of organs occurs only at late stage. It shows whorl like pattern in histology with myofibroblastic or osteoblastic differentiation. Insulin like production by tumour or rapid utilisation of glucose by active tumour causes intermittent *hypoglycaemia (paraneoplastic)*.
- Spread of retroperitoneal sarcoma mainly occurs through blood to lungs and often to liver. Nodal spread occurs rarely (5%).

Presentations

- Most patients have initial asymptomatic course with eventual presentation as *mass abdomen* (90%). Pelvic mass (20%), vague abdominal pain and discomfort (70%), anorexia, fatigue, vomiting, weight loss, fullness in abdomen, back pain due to compression over lumbar and pelvic nerves, leg pain, recurrent episodes of fever—are other features.



Figs 15.6A to C: Retroperitoneal tumour presenting as large mass abdomen with all features. CT pictures of the same patient.



Fig. 15.7: Retroperitoneal tumour showing encasement of major vessels. It becomes inoperable. Ureter, duodenum, intestines, kidney are other structures which may get infiltrated by tumour.

- *Other* presentations are—GI bleeding; intestinal/urinary obstruction (10%); neurological manifestations (20%) by compression or invasion of neurological systems by tumor; iliac vein or IVC compression can cause lower limb varicosities, varicocele, and dilated abdominal veins with venous flow from below upwards, and oedema.

Investigations

- CT abdomen—helical contrast CT (commonly used) and pelvis and *CT chest* (to see metastases) are essential investigations.
- *CT guided core biopsy*; laparoscopic biopsy are needed. FNAC has got limited role.
- *MRI* is better than CT with near 100% accuracy. It identifies extent, desmoplastic reaction. Liposarcoma shows decreased signal in T1 and increased signal in T2. MFH shows heterogamous signals.
- Retroperitoneoscopy may be ideal to take biopsy.
- IVU shows laterally deviated ureter. Plain X-ray may show soft tissue shadow, obliterated psoas shadow, and often calcification.
- AFP, HCG and other tumour markers are done often. LFT, blood urea and serum creatinine is done.
- Histochemistry is essential in many suspicious types.

TNM staging (AJCC 6th edition)	***AJCC (6th edition) grading***
Tumour (T):	Low grade
Tx: Cannot be assessed	High grade
T0: No tumour	
T1: 5 cm or less	
T2: > 5 cm	**Staging (AJCC 6h edition):**
Nodal (N):	I: T_1/T_2; N_0; M_0; low grade
N_x: Nodes cannot be assessed	II: T_1; N_0; M_0; high grade
N_0: No nodes	III: T_2; N_0; M_0; high grade
N_1: Nodes present	IV: Any T; N_1; M_1
Metastasis (M):	*Note:*
M_x: Distant spread cannot be assessed	Nodal spread carries poor prognosis; it is equal to M_1 when outcome is considered
M_0: No metastases	
M_1: Distant spread present	

Time neither subtracts nor divides, but adds to such a pace it seems like multiplication.

Treatment

- *Surgery is the main modality* of therapy with wide excision—*complete enblock excision* (possible only in 30% of cases) is the ideal. Limited resection; debulking (controversial) are other options. Often it needs extensive surgical dissection; resection of adjacent bowel. Wide exposure is the key for successful surgery (lengthy midline/thoracoabdominal). Limiting factors are encasement of major vessels; invasion of ureters; extension into duodenum or pancreas; extensive involvement of mesentery and spread. Proper bowel preparation, colostomy, urinary diversion, adequate blood to replace the lost blood, *hypotensive* general anaesthesia are the *requirements* during surgery. Posterior dissection along the IVC, aorta and near spinal canal are the difficult areas of dissection. *Complications* are—injury to major structures, bleeding, sepsis, and leak.



Figs 15.8A and B: Retroperitoneal lymph node mass. It could be tuberculosis/lymphoma/secondaries/autoimmune lymph node enlargement.

- Postoperative chemotherapy and radiotherapy is used as adjuvant method.
- *Radiotherapy* may be external beam RT (5000 cGy); or IORT (intraoperative RT during surgical resection) which reduces local recurrence and radiation enteritis. Problems with RT are radiation injury to kidney, bowel, liver and spinal cord. Preoperative intensity modulated RT (IMRT) is tried.
- Recurrent disease needs re-exploration but often difficult to do complete clearance.
- Mesna, *Adriamycin (main drug),* ifosfamide and dacarbazine (MAID) are the chemotherapeutic agents used.
- Germ cell tumour, lymphoma (NHL) are treated accordingly.
- *Prognosis* depends on:
  - Tumour grade—low or high;
  - Resectability;
  - Invasion into organs, veins, nerves;
  - Size of tumour < 5 cm or > 5 cm or > 10 cm;
  - Deep location;
  - Nonliposarcoma in histology—poor prognosis;
  - Recurrent disease;
  - Distant spread.
  - Tumour grade and completeness of resection without distant spread are important prognostic factors.
  - RP tumours has got overall 40% recurrence rate. Overall survival is 1½ to 2 years.
  - 5-year survival for well-differentiated tumour is 75%; < 40% for undifferentiated tumours.

Features of retroperitoneal sarcomas

- Mass per abdomen
- Pain in the back and compressive features
- GIT obstruction especially by leiomyosarcoma
- Compression over the ureter causing hydronephrosis
- Compression over the major veins causing varicose veins
- Arterial compression features are not common
- Liver and lung secondaries can occur
- CT guided biopsy is ideal method of investigations

Treatment of retroperitoneal tumours

- *Wide local excision.* Often requires removal of adjacent structures like colon, kidney, and spleen
- *Debulking operation* as a palliative
- *Enucleation* through pseudocapsule. It has got high recurrence rate—not done; may be useful in advanced cases
- *Radiotherapy* either brachytherapy or external beam radiotherapy or intraoperative RT
- *Chemotherapy* using adriamycin
- Retroperitoneal NHL is treated by *chemotherapy*



Fig. 15.9: Large pelvic retroperitoneal tumour.

Retroperitoneal sarcoma (RPS)

- Accounts for *15%* of all sarcomas
- Common *presentations* are—nontender palpable RP mass (90%); weight loss, pain and discomfort; neurologic (20%); urinary (10%); weight loss (20%); bowel obstruction; paraneoplastic syndrome (hypoglycaemia)
- 70% present with tumour more than 10 cm; 20% present with metastases
- Liposarcoma is the *most common* RP sarcoma; it can be well-differentiated, dedifferentiated, myxoid, round cell, pleomorphic
- *Histological grading* is important prognostic factor—*high grade* carries median survival of 2-3 years; *low grade* has got survival of 10 years
- CT scan, *CT guided core biopsy* through posterior approach, MRI (extremely accurate)—are the investigations needed. CT chest and abdomen, isotope renal scintigraphy or IVU to check the function of opposite kidney has to be done which may required to be removed
- A preoperative biopsy is *not usually* indicated in patients with resectable RPS; but is needed when preoperative therapy alters or lymphoma/germ cell tumours are suspected
- Open biopsy is also *not* done in a resectable tumour as it is potentially dangerous, can cause peritoneal contamination. It is done only if CT core biopsy is inconclusive
- FNAC in RPS is *not useful*
- PET scan do not have usual role in screening, diagnosis and staging. It *can be used* to quantify tumour activity; to assess the response of neoadjuvant chemotherapy and response of newer therapies targeted at specific molecular level to arrest the tumour growth
- **Dutch/memorial Sloan-Kettering cancer centre classification system of RPS (post-surgical)** is commonly used:
  - Stage I – Low grade, complete resection, no metastases
  - Stage II – High grade, complete resection, no metastases
  - Stage III – Any grade, incomplete resection, no metastases
  - Stage IV – Any grade, any resection, distant metastases
- ***Surgery is the choice of therapy***—monobloc complete surgical resection with dissection outside the pseudocapsule with adequate negative margin is possible only in 50% of cases
- Often associated visceral organ resection (in 50% cases) is needed—kidney and adrenals (45% cases), colon (25%), small bowel, pancreas (15%), spleen (10%). Need for removal of kidney arises when there is encasement of renal hilar vessels and fascia of Gerota, but not invasion of kidney
- **Adjuvant RT to retroperitoneum** is used to prevent local recurrence. It can be—preoperative, intraoperative (IORT), postoperative. It can be external beam (EBRT) or brachytherapy. *Advantages of preoperative RT* are—well demarcated gross tumour; radiosensitive viscera is displaced away by tumour itself without adhesions; absence of potential contamination of abdomen cavity; better oxygenated tumour bed. *IORT is given* as a single large dose (20 Gy) of RT to the retroperitoneum on table after displacing sensitive viscera away. *Intensity modulated RT (IMRT)* gives 45 Gy RT to planned gross tumour with 1.5 cm margin with intergrated booster doses of 65 Gy at 2.5 Gy per fraction to the margins at high-risk; IMRT has minimal local toxicity like damage to kidney, bowel (stricture), spinal cord. *Postoperative RT* has more disadvantages and toxicity but *allows* patient selection in terms of risk of local recurrence
- ***Chemotherapy (CT)***—no role of neoadjuvant CT. *Adjuvant CT* may be useful in synovial and myxoid types of liposarcoma. Palliative CT is used in unresectable and metastatic RPS—*MAID and AIM* regimes are used
- ***Specific targeted therapy on tumourogenesis***—antiangiogenetic agent, tyrosine kinase inhibitors, and mammalian target of rapamycin inhibitors (MTOR) are used. Trabectedin—synovial sarcoma, myxoid sarcoma, leiomyosarcoma
- ***Prognostic factors***—*tumour grade* and *completion of surgical resection* are the best prognostic factors (not tumour size)
- ***Local recurrence*** is common in 50% of cases. It is usually seen in high grade liposarcoma. Leiomyosarcoma, malignant peripheral nerve sheath tumours show distant spread commonly along with local recurrence

PSOAS ABSCESS

- Abscess in the psoas region in the iliac fossa, is commonly due to tuberculosis of spine (T 10) and lymph nodes, retroperitoneal structures, lower intercostal region.
- It can also be a pyogenic abscess.

Clinical Features

- Back pain, fever, spinal tenderness, paraspinal spasm and restricted spine movement.
- Swelling in iliac fossa which is smooth, nontender, nonmobile, not moving with respiration.
- When it extends across the groin and below the inguinal ligament, it is ***cross fluctuant*** across the inguinal ligament.
- Patient has typical *psoas muscle spasm* in which patient is able to flex his hip but finds it difficult to extend.



Fig. 15.10: Psoas abscess.

Swellings which are cross fluctuant

- Psoas abscess
- Ranula
- Compound palmar ganglion
- Bilocular hydrocele

Differential Diagnosis

a. Iliac artery aneurysm.
b. Ovarian cyst in females.
c. Soft tissue tumours and cysts in the iliac region.
d. Hernia.



Fig. 15.11: CT picture of large psoas abscess.

Investigations

- X-ray spine and chest, CT scan.
- Mantoux test, ESR, peripheral smear.
- U/S abdomen.



Fig. 15.12: On table finding of psoas abscess.

Treatment

- Antituberculous drugs are started—INH, ethambutol, rifampicin, pyrazinamide.



Figs 15.13A to C: Bilateral large psoas abscess—CT picture. Drainage and placement of Malecot catheters for the same. Note the location of incisions. It is obliquely placed incision above the lateral aspect of groin with extraperitoneal approach.

- Under G/A through lateral loin incision, the psoas region is reached extraperitoneally. The pus is drained and collected for culture and sensitivity, AFB, culture. The wound is closed. All caseating material and diseased parts of vertebra should be removed.
- Only lateral approach is advised. In thoracic region—*anterolateral decompression* with *costotransversectomy* with *bone grafting* is the treatment.

Note:
Posterior approach, i.e. laminectomy—**not advised.**

Chapter 16

Differential Diagnosis of Mass Abdomen

CHAPTER OUTLINE

- Mass in the Right Hypochondrium
- Mass in the Epigastrium
- Mass in the Left Hypochondrium
- Mass in the Lumbar Region
- Mass in the Umbilical Region
- Mass in the Right Iliac Fossa
- Mass in the Left Iliac Fossa
- Mass in the Hypogastrium

In a patient presenting with mass abdomen, generally following clinical features should be assessed carefully.

- *Pain:* Site, nature, aggravating or relieving factors, duration of pain, referred pain.
- *Vomiting*: Type, content, haematemesis, relation to food, frequency.
- *Jaundice*: It is an important factor in relation to liver, gallbladder or pancreatic masses.



Fig. 16.1: Obstructive jaundice in a patient with carcinoma head of pancreas. Note the sclera for discolouration. Severe itching is common in these patients.

- *Bowel habits*: Constipation, diarrhoea, bloody diarrhoea, furious diarrhoea, tenesmus.
- Decreased *appetite* and *weight*.
- *Inspection of the mass*: Anatomical location, margin, surface, movement with respiration.
- *Palpation of the mass:* Site, extent, surface, tenderness, consistency, movement with respiration, mobility, borders, plane of the swelling (by leg raising test), presence of other masses.



Fig. 16.2: Abdomen should be inspected by exposing from nipple level to knee level. Inspection is done from foot end and from right side.

- *Often mass needs to be examined for change of position*—in sitting, in standing, in side position, after a brisk walk, in knee elbow position for retroperitoneal mass and *for puddle sign* (but difficult to keep patient in this position).
- *Percussion* is an important aspect of examination in case of an abdominal mass. Percussion over the mass is important to predict the anatomical location of the mass. If mass is dull, then it is in the anterior abdominal wall or in front of the bowel intra-abdominally like liver, spleen, gallbladder. If the mass is with a impaired resonant note, then the mass is arising from the bowel like stomach, colon, small bowel. If the mass is resonant on percussion, then the mass is probably in the retroperitoneal region. Other than this, liver dullness, free fluid in the abdomen should be elicited during percussion.
- *Per rectal examination*: It is done to look for any secondaries in rectovesical pouch, primary tumour or relation of lower abdomen masses (pelvic masses).
- *Pervaginal examination* is done to assess pelvic masses.

Diagnosis of diseases os often easy; often difficult and often impossible. —**William Harvey**



Fig. 16.3: Superior vena caval obstruction causing dilated veins in the neck, chest wall and shoulder. Note the neck swelling extending into the mediastinum.



Fig. 16.4C

Figs 16.4A to C: Inferior vena caval obstruction causing dilated veins over the lateral aspect of the flank with flow of blood upwards.



Figs 16.4A and B



Fig. 16.5: Abdomen mass should be palpated clinically properly.



Fig. 16.6: Percussion over the mass is absolute need to find out the plane of the mass. Anterior masses are dull on percussion; posterior masses are resonant and mass from bowel has impaired resonance.



Fig. 16.7: Digital examination of rectum is a must in patients with mass abdomen to look for secondaries, possible primary and often to assess the mass itself.



Fig. 16.8: Neck should be examined for left supraclavicular lymph node enlargement in all abdominal masses.



Fig. 16.9: Different quadrants in the abdomen. They are four in number formed by two lines—one is vertical midline through the umbilicus; another is horizontal line passing through the umbilicus. Quadrants are—right upper, right lower, left upper and left lower.



Fig. 16.10: Regions in the abdomen.

Regions in the abdomen

1. Right hypochondrium
2. Epigastric region
3. Left hypochondrium
4. Right lumbar region
5. Umbilical region
6. Left lumbar region
7. Right iliac fossa
8. Hypogastrium
9. Left iliac fossa

Abdomen is divided into nine regions by four lines.

1. Upper horizontal or *transpyloric line* is mid-way between the umbilicus and xiphisternum.
2. Lower horizontal line is *transtubercular line* at the level of two tubercles on the iliac crest.
3. Right vertical line is the line through the midpoint of right anterosuperior iliac spine and pubic symphysis.
4. Left vertical line is the line through the midpoint of left anterosuperior iliac spine and pubic symphysis.

MASS IN THE RIGHT HYPOCHONDRIUM

Liver Palpable as Mass in Right Hypochondrium

- It is horizontally placed.
- It usually moves with respiration.
- Upper border is not felt.
- It is dull on percussion (This dullness continues over liver dullness above).
- Fingers can not be insinuated under right costal margin.

Conditions where liver gets enlarged:

1. *Soft, smooth, nontender liver:*
   - *Hydrohepatosis*: It is due to obstruction of CBD causing dilatation of intrahepatic biliary radicles.
   - Congestive cardiac failure.
   - Hydatid cyst of the liver: Here mass is well-localised in the liver with typical hydatid thrill. *Three finger test:* Three fingers are placed over the mass widely. When central finger is tapped fluid movement is elicited in lateral two fingers.

> *As beds and couches vary in height, the examiner to palpate the abdomen, if need be, must sit on a suitable chair or even kneel upon the floor, no matter how undignified this may appear.* — **Charles P**



Fig. 16.11: Mass abdomen.



1. Stomach mass
2. Pancreas body mass
3. Colonic mass
4. Mesenteric cyst
5. Omental mass
6. Carcinoma caecum
7. Appendicular mass
8. Ileocaecal tuberculosis
9. Pelvic mass
10. Gallbladder
11. Umbilicus
12. Liver

Fig. 16.12: Different causes of mass abdomen.

2. *Soft, smooth, tender liver:*
   - *Amoebic liver abscess:* Here liver often gets adherent to the anterior abdominal wall and will not move with respiration. Intercostal tenderness, right sided pleural effusion are common.

Amoebic liver abscess

- It is due to entamoeba histolytica infestation
- It is more common in alcoholics and cirrhotics
- Single abscess is common—70%; common in right postero-superior lobe—80%
- Chocolate colored Anchovy sauce pus is classical
- Secondary infection can occur—30%—life-threatening due to septicaemia
- It can be acute or chronic; both mimics hepatoma
- Rupture into lungs—most common site of rupture
- Most dangerous rupture is into pericardium—left lobe abscess
- Liver failure can develop in cirrhotic patient

Features

- Common in males (20:1), fever, pain, intercostal tenderness, tender liver
- Mimics cholecystitis, subphrenic abscess, hepatoma
- Total count, LFT, prothrombin time, US abdomen are relevant investigations
- Chest X-ray may show left sided sympathetic pleural effusion
- CT scan to differentiate from hepatoma
- *Treatment*—drugs like metronidazole, injection dehydroemetine, chloroquine tablets, diloxanate furoate; U/S guided aspiration after controlling prothrombin time using inj vitamin K or FFP; if recurs percutaneous guided drainage using pigtail catheter, or open laparotomy and drainage with placement of Malecot's catheter

3. *Hard, smooth liver:*
   - *Hepatoma* (HCC): Here a large, single, hard nodule is palpable in the liver. But occasionally there can be multiple nodules when it is multicentric. Rapidly growing tumour can be soft also. Hepatoma often can also be tender due to tumour necrosis or stretching of the liver capsule. Vascular bruit may be heard over the liver during auscultation. It mimics amoebic liver abscess in every respect.
   - Solitary secondary in liver.

Hepatoma/hepatocellular carcinoma/HCC

- Common aetiologies are aflatoxins, hepatitis B and hepatitis C virus infection, alcoholic cirrhosis, haemochromatosis, smoking, hepatic adenoma, clonorchis sinensis, polyvinyl chloride
- Unicentric and right lobe involvement is more common
- Fibrolamellar variant is common in left lobe, not related to hepatitis or cirrhosis without AFP level raise. There are increased serum vitamin B_{12} binding capacity and neurotensin levels.
- It can be multifocal/indeterminate/spreading/expanding—*Okuda classification*
- Presents as large smooth hard liver mass—later jaundice, fever, pain and tenderness, ascites and bruit over mass
- Spreads to lymphatics, blood and direct spread
- Mimics amebic liver abscess, secondaries, hydatid cyst, polycystic liver disease
- LFT, CT scan, raised AFP, liver biopsy (only needed) are the investigations
- Hemihepatectomy in early operable growth is the treatment
- Hepatic artery ligation/intra-arterial chemotherapy/chemoembolisation/percutaneous ethanol or acetic acid injection/radiofrequency ablation/chemotherapy using adriamycin, carboplatin, gemcitabine—are palliative procedures



Fig. 16.13: Hepatocellular carcinoma/hepatoma. It is common in right lobe, unicentric, attains large size.



Figs 16.14A and B: Multiple secondaries in liver with umbilication. It is due to central necrosis. Secondaries are the most common malignant tumour of the liver. It could be from GIT or extra-gastrointestinal sites like from breast, lungs, melanoma, thyroid, prostate, kidneys, etc. Patient with liver secondaries has got poor general condition. It should be differentiated from multicentric hepatoma. It is usually treated by palliative chemotherapy. Solitary secondary from carcinoma colon can be removed by segmentectomy.

4. *Hard, multinodular liver:*
    - Multiple secondaries in liver: Here hard nodules show umbilication which is due to central necrosis.
    - Macronodular cirrhotic liver.

Palpable Gallbladder in Right Hypochondrium

- It is smooth and soft (except in carcinoma gallbladder).
- It is mobile horizontally (side-to-side).
- It moves with respiration.
- It is located right of the right rectus muscle, below the right costal margin or below the lower margin of the palpable liver.
- It is dull on percussion.

Conditions where gallbladder is palpable:

1. *Soft, nontender gallbladder*:
    - Mucocele of the gallbladder.
    - Enlarged gallbladder in obstructive jaundice due to carcinoma head of the pancreas or periampullary carcinoma or growth in the CBD.
2. *Hard gallbladder:*
    - Carcinoma gallbladder.
3. Tender gallbladder—empyema GB.

Other Masses in the Right Hypochondrium

- *Pericholecystic inflammatory mass*: It is tender, smooth, firm or soft, nonmobile, intra-abdominal mass often with guarding.
- *Kidney mass arising from upper pole of the kidney*: It may be due to renal cell carcinoma or hydronephrosis.



Fig. 16.15: Large upper abdomen mass—could be liver mass, pancreatic mass, retroperitoneal mass.

MASS IN THE EPIGASTRIUM

Palpable Left Lobe of the Liver

- It is in the epigastric region.
- Its upper border cannot be felt.
- It moves with respiration.
- It extends towards left hypochondrium.
- It is dull on percussion.

After every end is a new beginning and every beginning has an end.

Conditions where left lobe of the liver is palpable

- Hepatoma
- Amoebic liver abscess in left lobe
- Left lobe secondaries
- Hydatid cyst of the left lobe

Features of Stomach Mass



Figs 16.16A to E: Carcinoma pylorus causes gastric outlet obstruction with palpable mass above the umbilicus. Carcinoma body of stomach mainly presents as loss of appetite and decreased weight with horizontally placed stomach mass. Carcinoma from fundus of the stomach presents as mass abdomen with loss of appetite and weight. Carcinoma oesophagogastric (OG) junction presents as dysphagia. Carcinoma stomach is one of the common causes of secondaries in liver.

- It is located in the epigastric region.
- It moves with respiration. It is intra-abdominal.
- It is resonant or impaired resonant on percussion.
- Mass may be better felt on standing or on walking.
- Mass is often mobile, unless it gets adherent posteriorly.
- In pylorus mass, all margins are well felt which is mobile with features of gastric outlet obstruction.
- Mass from the body of the stomach is horizontally placed without any features of obstruction.
- Mass from the upper part of the stomach near the OG junction causes dysphagia.
- Mass from the fundus of the stomach is in the upper part of the epigastric region towards left side.
- Carcinoma stomach is nodular and hard. It is the most common cause for stomach mass.
- Leiomyoma of stomach is smooth and firm.



Fig. 16.17: Epigastric mass arising from carcinoma stomach.

Management of gastric carcinoma

- Early growth—pylorus—lower radical gastrectomy with removal of tumour, proximal 5 cm clearance, nodal clearance, greater and lesser omentum, distal pancreas and spleen (now not regularly removed; it is removed to clear splenic nodes—one of the node stations) and Billroth II anastomosis or Roux-en-Y anastomosis is done. Postoperatively adjuvant chemotherapy should be given—5 fluorouracil, mitomycin, epirubicin, cisplatin
- Growth in body, proximal growth, diffuse carcinoma and generalised linitis plastica are the indications for total radical gastrectomy with oesophagojejunal anastomosis
- Neoadjuvant chemotherapy in advanced gastric cancer prior to surgery and later gastrectomy
- Instillation of mitomycin C impregnated charcoal intraperitoneally to control lymphatic disease (Japan)
- Palliative procedures like palliative partial gastrectomy, anterior gastrojejunostomy, Devine's exclusion procedure, luminal stenting in proximal inoperable growths, chemotherapy are used in inoperable cases
- In early carcinoma proper lymph nodal clearance is important

Pseudocyst of the Pancreas

- Mass in the epigastric region. It is smooth, soft. It can be tender if it is infected.
- It does not move with respiration.
- It is not mobile.



Fig. 16.18: Pseudocyst of pancreas presenting as epigastric mass.



Fig. 16.19: Pseudocyst of pancreas—CT scan picture.

- It has got transmitted pulsation. It is confirmed by placing the patient in knee-elbow position.
- Lower border is well felt. Upper border is not clear.
- It is resonant on percussion.
- *Baid test*: As the stomach is pushed in front, Ryle's tube when passed, can be felt per abdomen on palpation.

Investigations for pseudocyst of pancreas	***Indications for intervention***
• Ultrasound—commonly done procedure	• Size more than 6 cm
• CT scan, ideal and choice	• Formed thick-walled pseudocyst
• LFT, serum amylase, prothrombin time	• Infected pseudocyst
• ERCP to find out communications	
• Barium meal—not done now—shows widened vertebrogastric angle	
Interventions	***Complications***
• Roux-en-Y cystojejunostomy is ideal	• Rupture—3% • Infection—20%
• Cystogastrostomy—Jurasz procedure—commonly done cystoduodenostomy	• Bleeding—torrential 7% • Cholangitis
• Cystogastrostomy with external drainage if infected—Smith operation	
• Endoscopic stenting	
• Laparoscopic cystogastrostomy—popular—safer	
• Guided aspiration helps but high recurrence rate of 70%	
• Acute fluid collection—just fluid collection	
• Acute pseudocyst with thin wall	
• Chronic pseudocyst—thick walled	
• Pseudopseudocyst—inflammatory mass of bowel, omentum, etc. after acute pancreatitis mimics pseudocyst	

Cystadenocarcinoma of the Pancreas

Mass is smooth, firm, does not move with respiration, nonmobile, resonant on percussion. Patient complaints of back pain.

Colonic Mass

- It is due to carcinoma of transverse colon.
- It is mobile, horizontally placed, nodular, hard mass which does not move with respiration. Caecum will be dilated and palpable.
- It is resonant or impaired resonant on percussion.
- Patient will be having bowel symptoms, loss of appetite and decreased weight.

Para-aortic Lymph Node Mass

- Mass in the epigastric region which is deeply placed, nonmobile, not moving with respiration.

The same beam of light can illuminate two objects and produce two different effects.

- It is vertically placed, above the level of the umbilicus and resonant on percussion.
- Causes for enlargement are: *Secondaries, lymphomas* or *tuberculosis.*

Aortic Aneurysm

It is smooth, soft, pulsatile (expansile pulsation which is confirmed by placing the patient in knee-elbow position).

It is vertically placed above the level of the umbilicus, nonmobile, not moving with respiration and resonant on percussion.

MASS IN THE LEFT HYPOCHONDRIUM

Enlarged Spleen

- Spleen has to enlarge three times to be palpable clinically.
- It enlarges towards the right iliac fossa from left costal margin.
- It moves with respiration, mobile, obliquely placed, smooth, soft or firm, with a notch on the anterior edge which is directed downwards and inwards.



Fig. 16.20: Method of palpating spleen.



Fig. 16.21: Hepatosplenomegaly is the common condition (clinical entity). It is due to macronodular cirrhosis with portal hypertension, lymphoma, autoimmune diseases, congestive cardiac failure, hepatoma with portal hypertension, haemolytic diseases, etc. There may be ascites, supraclavicular palpable lymph node and pleural effusion (right-sided).

- Fingers cannot be insinuated over the upper border.
- "*Hook sign" is positive*, i.e. one cannot insinuate the fingers under the left costal margin.
- It is dull on percussion.

Left Sided Colonic Mass

- It is mobile, nodular, resonant.
- It does not move with respiration.
- It is commonly due to carcinoma colon.

Left Renal Mass from Upper Pole of any Cause

It has got features of renal mass.

Left Sided Adrenal Mass

- It does not move with respiration. It is not mobile.
- It is deeply placed mass. Often it crosses the midline.
- It is resonant on percussion. It mimics kidney mass.

Mass Arising from the Tail of the Pancreas

Clinical features are same as other pancreatic masses. Causes are pseudocyst in tail of the pancreas and cystadenomas.

MASS IN THE LUMBAR REGION



Fig. 16.22: Kidney should be palpated bimanually with two hands. Ballotability also should be checked.



Fig. 16.23A



Fig. 16.23B

Figs 16.23A and B: Renal (Kidney) punch. Renal angle should be palpated for tenderness. Renal angle is junction of 12th rib and erector spinae. *On percussion it is normally resonant* as it is occupied by colon. It is replaced by kidney in kidney enlargement. Renal angle should be inspected, palpated and percussed in sitting position from behind.

Palpable Kidney Mass

- There is fullness in the loin which is better observed in sitting position.
- Mass moves with respiration. It is vertically placed.
- It is bimanually palpable. It is ballotable.
- Renal angle is dull on percussion (normally it is resonant due to colon).
- There is a band of resonance in front due to reflected colon.
- It does not cross the midline.

Conditions Where Kidney Gets Enlarged

Hydronephrosis:

- It is smooth, soft, lobulated, nontender mass, nonmobile.

Pyonephrosis:

- History of throbbing pain in the loin, pyuria and fever with chills.
- It is smooth, soft and tender kidney mass, nonmobile.

Polycystic kidney:

- History of loin pain and haematuria.
- Hypertension, anaemia and features of renal failure.
- Usually bilateral. But one side can present early than on the other side.
- Lobulated smooth surface.

Renal cell carcinoma:

- History of mass in the loin, haematuria, fever and dull pain.
- Mass is nodular and hard.
- It does not cross the midline.
- Initially mobile; eventually it infiltrates gets fixed and becomes nonmobile.

Mass from the Ascending Colon on Right Side or Descending Colon on Left Side

- History of altered bowel habits with decreased appetite and weight.
- Mass is nodular, hard which does not move with respiration and is not ballotable.
- It is resonant or there is impaired resonance on percussion.
- Renal angle is resonant.
- Proximal dilated bowel may be palpable.

Adrenal Mass

- It is nodular and hard.
- It does not move with respiration.
- It is not mobile and often crosses the midline.
- It is felt on deep palpation.
- It is resonant in front.
- It is not ballotable.

Retroperitoneal Tumours

- They are not mobile, resonant and do not fall forward in knee-elbow position.
- They are deeply placed mass which are usually smooth and hard.
- They may be retroperitoneal sarcomas or teratomas or lymph node mass.



Fig. 16.24: Palpation of mass in knee-elbow position. Mobility and falling forward should be confirmed in knee-elbow position.



Fig. 16.25: Retroperitoneal tumour.

Retroperitoneal Cysts

They are *smooth and soft* with the same features as retroperitoneal tumours.

Cystic lesions in the abdomen

- Mucocele/empyema of gallbladder
- Pseudocyst of pancreas
- Hydatid cyst of liver
- Congenital nonparasitic cyst of liver
- Hydronephrosis
- Mesenteric cyst
- Ovarian cyst
- Omental cyst
- Aneurysm
- Retroperitoneal cyst
- Cystadenocarcinoma of ovary
- Loculated ascites

MASS IN THE UMBILICAL REGION

Usual masses are:

- Mesenteric cyst
- Omental cyst
- Ovarian cyst (pedunculated)
- Small bowel tumours
- Extension of masses from other region
- Transverse colon mass
- Mass in the body of pancreas
- Mesentery mass
- Lymph node mass—secondaries (primary from GIT, testis, ovary, melanoma)/lymphoma/tuberculosis
- Retroperitoneal tumour

Mesenteric Cyst

- ***Tillaux triad:***
  1. Soft intra-abdominal umbilical mass.
  2. Mobile in the direction perpendicular to the attachment of the mesentery.
  3. Resonant mass.
- May precipitate intestinal obstruction, volvulus.

Omental Cyst

- It is smooth, soft and nontender.
- It moves with respiration. It is mobile in all directions.
- It is dull on percussion.

Small Bowel Swellings

- Small bowel lymphomas.
- Small bowel carcinomas.
- Intussusception.

Intussusception

- Mass in umbilical region usually towards left and above the umbilicus.
- Occasionally towards right side.
- Mass is intra-abdominal which is *sausage shaped*, with concavity towards umbilicus, well-defined, smooth, firm and mobile.
- Mass does not move with respiration.
- Mass contracts under palpating fingers.
- Often mass disappears and reappears.
- Mass is resonant or there is impaired resonance on percussion.
- *"Red currant gelly"* stool with features of intestinal obstruction may be present.

MASS IN THE RIGHT ILIAC FOSSA



Fig. 16.26: Mass in right iliac fossa. All possible differential diagnosis should be considered and clinically analysed. Common masses are appendicular mass; carcinoma caecum; ileocaecal tuberculosis; lymph node mass; ameboma.

- Appendicular mass or abscess
- Carcinoma caecum
- Ileocaecal tuberculosis
- Amoeboma
- Psoas abscess
- Lymph node mass either mesenteric or external Iliac lymph nodes
- Bony swellings
- Ectopic kidney
- Undescended testis (Abdominal)
- Actinomycosis
- Crohn's disease
- Iliac artery aneurysm
- Ovarian swelling-ovarian cyst
- Tubo—ovarian mass
- Uterine mass like pedunculated fibroid

Appendicular Mass

- It is *smooth, firm, tender mass* in the right iliac fossa.
- It is not mobile. It does not move with respiration.
- It is *resonant on percussion*. It is well-localised mass with distinct borders.

Appendicular Abscess

It is *smooth*, *soft, tender and dull mass* in the right iliac fossa with indistinct borders.

Carcinoma Caecum

- It is nodular, hard, mass in the right iliac fossa.
- It does not move with respiration.
- It is mobile but mobility may be restricted once it gets adherent to psoas muscle.
- Mass is resonant or there is impaired resonance on percussion.
- Often features of intestinal obstruction may be present.

Ileocaecal Tuberculosis

- Mass in the right iliac fossa which is smooth, hard, resonant and nontender.
- It does not move with respiration and has restricted mobility.
- Caecum may be *pulled up* to lumbar region due to fibrosis.

Amoeboma

- History of dysentery with pain in the right iliac fossa.
- Smooth, hard, well-defined mass in the right iliac fossa which is nonmobile.
- It may or may not be tender.

Psoas Abscess

- It is localised, smooth, soft, nonmobile mass in the right iliac fossa.
- *Psoas spasm* (flexion of the hip joint) is typical.
- Spine may show *gibbus, tenderness, paraspinal spasm*. Spinal movements will be restricted.

MASS IN THE LEFT ILIAC FOSSA

- Carcinoma sigmoid or descending colon
- Bony masses
- Ovarian/uterine masses
- Psoas abscess
- Ectopic kidney
- Lymph node mass
- Undescended testis

MASS IN THE HYPOGASTRIUM

Bladder Mass

- It is in the midline. It is dull on percussion. Lower border is not felt.
- It can be mobile in horizontal direction. Mass reduces in size after emptying the bladder. It can be felt on per-rectal examination.
- It is either carcinoma bladder (common) or leiomyoma or sarcoma bladder.

Uterine Mass

- It is midline mass which is smooth, hard.
- Lower border is not felt which extends into the pelvis.
- It is felt on pervaginal examination.

Ovarian Mass

Pelvic soft tissue mass.

In all lower abdomen masses P/R and or P/V is a must.

In all regions ***parietal masses*** *can occur*:

- Benign and malignant soft tissue tumours.
- Common, is lipoma.
- Fatty hernia of linea alba.
- Desmoid tumour.
- Parietal wall abscess.

Blaxland ruler *test* (Athelstan J Blaxland): A flat ruler placed on the lower abdomen just above the anterosuperior iliac spines and pressed firmly backwards. In ovarian cyst aortic pulsation is transmitted to fingers through ruler; it is not so in ascites.

Carnett's Test

The patient, in lying down position, is asked to lift both legs off the bed with knee extended. This puts the abdominal muscles into contraction. Intra-abdominal mass becomes less prominent, parietal mass persists as same, but becomes less mobile.



Fig. 16.27: Looking for minimal ascites in knee-elbow position—Puddle sign.

Investigations for Mass Abdomen

- Haematocrit, liver function tests, renal function tests, stool/urine examination.
- Ultrasound abdomen.
- Endoscopies-gastroscopy-colonoscopy-ERCP-MRCP.
- Barium studies-Barium meal-Barium enema-Barium meal follow through.
- CT scan-MRI.
- Endosonography.
- Ascitic tap.
- Diagnostic laparoscopy.
- U/S guided/CT guided biopsy.
- IVU/RGP/Cystoscopy/Isotope renogram.
- Exploratory laparotomy.

Note:

- Hard mass in the abdomen is commonly malignant
- Firm mass may be tuberculous, lymphoma or many benign conditions
- Soft masses are hydronephrosis, pseudocyst, mesenteric cyst, omental cyst, and loculated ascites
- In tuberculosis abdomen may be doughy due to thickened parietal peritoneum or omentum
- It is difficult to elicit fluctuation in the mass abdomen as mass cannot be fixed properly
- Plane of the swelling should be checked by leg raising/head raising test/Valsalva manoeuvre/knee elbow test
- Bimanual palpation, ballotability, renal angle inspection, palpation and percussion should be done in case of renal mass
- Intrinsic mobility should be checked. Different mobilities/movements are—gallbladder shows side to side; stomach lateral; ovarian mass—all over; mesenteric cyst—right angle to line of mesentery; transverse colon mass—vertical; small bowel mass all over; appendicular mass/pancreatic mass/nodal mass (para-aortic)/retroperitoneal mass do not show any mobility; cystadenocarcinoma of pancreas may show false mobility (*tree top mobility*)

Percussion is very important method of examination to find out the anatomical plane of the mass. Mass in front of the bowel like liver/spleen/gallbladder/parietal mass are dull on percussion. Mass from the bowel is resonant on percussion like from stomach, small bowel and colon. Retroperitoneal masses like cyst, sarcoma, nodal mass, aneurysm, pancreatic mass are resonant on percussion

- Succussion splash and auscultopercussion tests are done for gastric outlet obstruction in pyloric stenosis
- Digital examination of rectum (P/R) and left supraclavicular examination for nodes is a must. PR is done to see Blumer shelf secondaries in rectovesical pouch. Pervaginal examination should be done in pelvic mass in females
- Bladder should be emptied while examining pelvic mass
- Bimanual examination is done often under general anaesthesia in case of pelvic mass
- Auscultation for bruit depends on condition and location of mass—over epigastrium, over liver
- Other relevant systemic examination is a must in examination of mass abdomen—respiratory system, skeletal and neurological systems

Mass that appears and disappears

- Pseudocyst of pancreas (communicating)
- Hydronephrosis (intermittent)
- Choledochal cyst
- Intussusception

Srinivasan Costal Sign

"Srinivasan costal sign" is an inspectory finding to assess the acute distended abdomen secondary to surgical or postoperative status or medical causes under treatment. The bilateral costal margin is visualised tangentially on the either side of the abdomen in supine position to appreciate this costal sign.

"Prominence of costal margins will be lost in distended abdomen. During therapy, once distension reduces, prominence of costal margins will be visible (during recovery)".



Fig. 16.28A



Figs 16.28B and C

Figs 16.28A to C: Srinivasan costal sign: This sign can be appreciated under inspection, the costal margin which is not visible or poorly visible in case of distended abdomen. Once the acute abdomen or distended abdomen secondary to medical cause start settling, the costal margins become visible and prominent, this holds good even in case of fatty protuberant abdomen.

Acknowledgements

With kind permission from Professor Narayanaswamy Srinivasan, MS, FRCS who was earlier worked as HOD, General Surgery, Bangalore Medical College; Director of Sanjay Gandhi Accident Hospital and Research Institute, Byrasandra, Bangalore; Dean and Director of Bangalore Medical College and Research Institute, Bangalore; Joint Director of Medical Education, Govt of Karnataka, India.

Chapter 17 Abdominal Wall and Umbilicus

> *Why do they meet this most unfortunate and lamentable fate? Have these vessels committed some great crime, that you, O Nature, a just and provident mother to all other parts of the body, have become a step-mother to these alone, so that they deserve to be visited with an affliction so dire, a punishment so severe as wasting and death? Did not the vein continuously supply blood to the fetus? Did not the arteries give life to it? Were they not the means of bestowing increase and nutrition upon the fetus?*
>
> **—Girolamo Fabrizio (Fabricius ab Aquapendente),** 1649

CHAPTER OUTLINE

- Diseases of the Umbilicus
- Omphalitis
- Umbilical Granuloma
- Anomalies of Vitellointestinal Duct
- Umbilical Sinus
- Umbilical Adenoma
- Umbilical Fistula
- Patent Urachus
- Burst Abdomen
- Abdominal Wall Tumours
- Desmoid Tumour
- Exomphalos
- Gastroschisis
- Rectus Sheath Haematoma
- Abdominal Wall Abscess
- Meleney's Progressive Synergistic Bacterial Gangrene of Abdominal Wall
- Diverication of Recti

DISEASES OF THE UMBILICUS

1. **Inflammations:**
    - Omphalitis.
    - Umbilical granuloma.
    - Pilonidal sinus.
2. **Fistulas:**
    a. *Faecal*
        - Patent vitellointestinal duct.
        - Neoplastic ulceration.
        - Tuberculosis of peritoneum.

    b. *Urinary*—Patent urachus.
3. **Neoplasms:**
    a. *Benign*
        - Adenoma (Raspberry tumour).
        - Endometrioma.

    b. *Malignant*
        - Primary (rare).
        - Secondary carcinoma—Sister Joseph's nodule through lymphatics of the round ligament, primary being in the stomach, colon, ovary, uterus, breast (often blood spread).
4. **Umbilical hernias.**
5. **Umbilical calculus (Umbolith).**



Fig. 17.1: Periumbilical pigmented lesion—could be melanoma.

OMPHALITIS

- It is infection and inflammation of umbilicus. It is usually seen in newborn babies.
- Umbilical cord which is severed during birth contains bacteria like staphylococci (50%), streptococci, *E. coli*, *Clostridium tetani* (occasionally). Proper aseptic technique

(by staff nurses and doctors) and cleaning of umbilical cord with chlorhexidine solution will reduce the umbilical infection.



Fig. 17.2: Omphalitis (Umbilical infection).

Causes

- Ligation of the umbilical cord without aseptic precautions.
- Poor asepsis and umbilical hygiene during delivery and after birth.

Bacteria

- Staphylococci, streptococci.
- Gram-negative organisms.
- *Clostridium tetani* causing neonatal tetanus.

Features

- Infection may spread along the hypogastric vessels into the abdominal wall causing abdominal wall abscess.
- Infection may spread into the peritoneum causing peritonitis.
- In severe cases, septicaemia can occur.
- Umbilical granuloma can occur once infection gets localised.
- Purulent discharge with red, swollen umbilicus.

Investigations

- Culture study of discharge.

Treatment

- Antibiotics.
- Drainage of the abscess.
- Aseptic precautions while ligating the cord will prevent the chances of umbilical sepsis.
- Excessive granulation tissue must be removed surgically or by cautery (commonly) using trichloroacetic acid or silver nitrate or copper sulphate in small quantity.

Complications

- Abdominal wall abscess
- Extensive abdominal wall ulceration and skin and subcutaneous gangrene formation
- Septicaemia via umbilical vein
- Peritonitis carries poor prognosis
- Umbilical granuloma, umbilical hernia
- Neonatal tetanus
- Portal vein thrombosis and portal hypertension
- Neonatal jaundice due to cholangitis—6 weeks after childbirth due to spread of infection into liver across umbilical vein



Fig. 17.3: Umbilical sepsis with profuse discharge.



Fig. 17.4: Umbilical infection causing abdominal wall abscess.

Umbilical black eye is Cullen's sign in acute pancreatitis and ruptured ectopic pregnancy.

UMBILICAL GRANULOMA

- It is due to chronic infection of the umbilical cicatrix, causing the granulation tissue to pout, leading to the formation of umbilical granuloma.
- It occurs in any age group, but common in infants and children. Presents as umbilical discharge with tender, red, swelling protruding from the umbilicus which bleeds on touch.
- It has to be differentiated from the anomalies of vitellointestinal duct. It also mimics umbilical adenoma.



Figs 17.5A and B: Umbilical granuloma due to sepsis.

Treatment

- Antibiotics, application of silver nitrate and dry dressings.
- Occasionally might require excision of granuloma or umbilectomy (rarely).

ANOMALIES OF VITELLOINTESTINAL DUCT

During development of fetus, midgut communicates with yolk sac through vitellointestinal or omphalomesenteric duct. This duct slowly narrows during the development of abdominal wall to lie within the cord, later this communication obliterates to free intestine from yolk sac. Any defect in obliteration causes different anomalies.

Anomalies are:

1. May remain completely patent, forming a *intestinal fistula.*
2. Only a small portion near the umbilicus may remain patent forming discharging *umbilical sinus*. Often the mucosa of this retained portion (epithelial lining) protrudes or evertes to form *umbilical adenoma*.
3. Duct is closed on either side, but the intervening portion may remain as a *intra-abdominal cyst*.
4. Vitellointestinal duct which is obliterated can retain *as a band* which may be a seat for intestinal obstruction, volvulus, internal herniation.
5. Intestinal end may remain patent forming Meckel's diverticulum, which may be attached to umbilicus with a fibrous band. *Meckel's diverticulum* itself can cause diverticulitis, obstruction.



Figs 17.6A to E: Anomalies of vitellointestinal duct. (A) Intestinal fistula, (B) Umbilical sinus, (C) Intra-abdominal cyst, (D) Band, (E) Meckel's diverticulum with band.

Anomalies of vitellointestinal duct

- Intestinal fistula
- Umbilical sinus
- Umbilical adenoma
- Intra-abdominal cyst
- Meckel's diverticulum
- Intra-abdominal band

Investigations

- Fistulogram.
- U/S abdomen.
- Radioisotope study.
- If obstruction is present, plain X-ray abdomen in erect posture is useful to visualise the multiple air-fluid levels.



Fig. 17.7: Patent vitellointestinal duct.

Treatment

Excision of vitellointestinal duct is done, along with resection of bowel segment containing Meckel's diverticulum.

UMBILICAL SINUS

Causes

- Persistent vitellointestinal tract partially towards umbilical side.
- Persistent urachus.
- Tuberculosis.
- Umbilical infection.
- *Umbolith*—desquamated epithelium of umbilicus gets collected and inspissated in the umbilical recess causing black/brown coloured stone (umbilical stone). It causes recurrent umbilical infection and sinus.
- Pilonidal sinus of the umbilicus.
- Malignancy in the urachus.

Clinical Features

- Pain, swelling, discharge and tenderness in the umbilicus.
- Features of the specific causes.

Investigations

- Study of the dischargeculture and sensitivity, cytology for malignant cells, AFB study.
- Sinusogram.
- U/S abdomen, CT abdomen.
- Chest X-ray, ESR.

Treatment

- Treat the cause.
- Antibiotics.
- Antitubercular drugs in case of tuberculosis.
- Umbilectomy.

UMBILICAL ADENOMA (Raspberry Tumour)



Fig. 17.8: Umbilical adenoma (Raspberry tumour).

- It is commonly seen in infants. It is due to partially obliterated vitellointestinal duct towards umbilical end, causing *prolapse of the mucosa* giving rise to *umbilical adenoma* also called *as Raspberry tumour*.
- It protrudes out as a red swelling, which is moist with mucus and tends to bleed on touch. It often gets infected, discharging pus through the umbilicus.
- Histologically, it consists of columnar epithelium rich in *goblet cells*.

Differential Diagnosis

- Umbilical granuloma.

Treatment

- If the tumour is pedunculated, a firm ligature is tied round it, so that tumour will fall off in few days. If it reappears, umbilectomy is done.
- Sometimes there may be a patent vitellointestinal duct or a Meckel's diverticulum, which may require resection along with the bowel segment.

***Note*:**

Umbilical adenoma *does not disappear after* silver nitrate application.

Tanyol's sign: Umbilicus is equidistant from xiphoid process and symphysis pubis. It is displaced downwards in ascites and upwards in pelvic masses.

UMBILICAL FISTULA

Causes

- Patent vitellointestinal duct.
- Patent urachus.
- Postsurgical.
- Tuberculosis.

Clinical Features

- Faecal discharge or urinary discharge, mucoid discharge.
- Recurrent infection.
- Pain, tenderness and excoriation in and around the umbilicus.

Investigations

- Fistulogram, CT fistulogram.
- Discharge study. C/S, AFB and cytology.
- U/S abdomen.

Treatment

- Fistulectomy, along with resection of bowel segment, patent vitellointestinal tract, and anastomosis of the bowel.
- Fistulectomy and excision of vitelline duct up to the antimesentric surface of the ileum. Opening in the ileum is closed transversely using vicryl or silk sutures.

PATENT URACHUS

Allantoic duct/stalk which is remnant of cranial part of ventral urogenital sinus forms urachus. It gets fibrosed and forms median umbilical ligament.

When urachus is patent it can form:

- *Patent urachus (Urachal fistula)* between umbilicus and dome of the urinary bladder (It is persistent median umbilical ligament).
- *Urachal sinus* if only umbilical side of the urachus is patent.
- *Urachal cyst* if only middle portion of the urachus is patent with lining and fluid content.
- *Urachal diverticulum* when bladder side of the urachus is patent.



Fig. 17.9: Different types of urachal anomalies.

Features

- Persistent discharge from the umbilicus often stained with urine if it is fistula.
- Recurrent infection and bleeding.
- Pain in the umbilicus and below.
- Recurrent urinary infection.



Fig. 17.10: Tuberculosis of urachus which is excised.

Investigations

- Fistulogram to see the extent.
- U/S abdomen.
- Discharge analysis and culture.
- Urine analysis.

Treatment

- Surgical excision of the tract.
- Often umbilical excision may be required.

Note:
Malignancy (adenocarcinoma) or tuberculosis can occur in patent urachus.

BURST ABDOMEN (Abdominal Dehiscence) (ACUTE WOUND FAILURE)

- It is disruption of a laparotomy wound, occurring usually between 5th and 8th postoperative day.
- Usually sutures opposing the deep layers, i.e. peritoneum and rectus sheath tear through, causing burst abdomen—*Acute wound failure*.
- There is postoperative separation of the abdominal musculoaponeurotic layers.
- It is 2% common.
- Other than technical errors, deep wound infection causes localised separation of the wound which in addition to raised intra-abdominal pressure leads to wound dehiscence.

Clinical Features (2%)

- A sudden feeling of giving way from the wound—on 5th to 8th postoperative day often precipitated by bouts of severe cough.



Figs 17.11A and B: Burst abdomen wound exposing intestines outside. It is covered with a mesh later.



Fig. 17.12: Abdominal faecal fistula. Note the tension sutures and faecal discharge.



Fig. 17.13: Ulcer over the postoperative wound.

Factors related to burst abdomen

- Choice of suture materials used
- Method of closure; continuous closure is more likely to disrupt than interrupted sutures
- Upper midline and vertical wounds are more likely to disrupt than transverse
- Surgical wounds of peritonitis, acute abdomen, major surgeries like pancreatic, hepatic, gastric, surgeries for malignancies have a high incidence of disruption
- Severe cough, vomiting and distension in postoperative period
- Poor general condition of the patient—anaemia, jaundice, hypoproteinaemia, obesity, uraemia and diabetes mellitus, old age, steroids, radiation, malignancy, chemotherapy.

- *Pinkish serosanguineous discharge* (salmon coloured large quantity of fluid) from the wound.
- Often omentum or coils of intestine are forced out of the wound.
- *Clinically burst abdomen can be diagnosed without fail*.
- Probing of the wound using gloved finger appreciates dehiscence of musculoaponeurotic layer.



Fig. 17.14: Incisional hernia which was repaired earlier has gaped exposing the mesh.

Truth is what is actually should be. Reality is what is happening. Every reality need not be truthfully right.



Fig. 17.15: Horizontal tension sutures.

Treatment

- Nasogastric aspiration, IV fluids.
- *Emergency surgery*, i.e. under anaesthesia, wound is opened up properly.
  - Coils of intestines are replaced into the abdominal cavity. Thorough wash is given. Wound is closed by *all layer sutures,* passing a nonabsorbable suture material through the red rubber or plastic collar—*tension sutures* (which is kept for 14 days).
  - *Modified Smead-Jones closure* mainly used to prevent burst abdomen—it is interrupted specialised suture used in the closure of abdomen as single layer excluding the skin. Linea alba is held with Allis' forceps. Number one polyethylene or PDS suture material is used. First bite on one side taken 3 cm away (width) from the margin from outside to inside; it is then passed through the corresponding opposite edge with 3 cm width from inside to outside; later again one small loop of 5 mm width from the edges of each side of the wound from first bite site to second bite site is taken; suture is knotted on the free edge of the first bite side. Full thickness bite holds the suture and maintains the tension in the wound. Smaller loop keeps the linea alba in apposed place. Large curved Ferguson needle is better to place these sutures. Each suture is placed at 2 cm interval. This is the type of suturing used at present in acute abdominal conditions instead of the retention sutures. Here also it is better to place all sutures under proper vision and knotting is done at the end. At least four knots should be placed. Excessive tension should be avoided. In upper abdomen peritoneum need not be included in the bite; but in lower abdomen as linea alba is indistinct, peritoneum is included in this.
- Antibiotics and IV fluids are continued.
- Wound usually heals well without much second dehiscence. Late problem, may be development of incisional hernia.
- Biological dressings, wound vacuum systems are newer modalities used.



Figs 17.16A and B: (A) Vertical tension sutures. (B) Shows tension sutures with multiple drains.

Newer present methods of managing the burst abdomen

- If the fascial edges are necrotic, *proper debridement* of the wound edges is done. One should not attempt forcible wound closure as it will increase intra-abdominal pressure further and re-dehiscence occurs (When fascia is strong and intact primary closure can be done). Wound and contents are covered with *absorbable mesh or biological prosthesis* like decellularised porcine submucosa and dermis or human cadaveric dermis. They prevent bowel desiccation, bacterial infection.
- *Wound vacuum system* using—open cell foam, semiocclusive drape over the foam and suction apparatus. It provides immediate coverage, minimises heat loss, by negative pressure it clears interstitial fluid, reduces the bowel oedema and contamination, increases wound blood flow and promotes wound healing. Once wound granulates wound is closed with primary closure or with skin graft or flaps depending on the size of the wound.

ABDOMINAL WALL TUMOURS



Fig. 17.17: Abdominal wall secondaries from carcinoma stomach.



Fig. 17.18: Sister Mary Joseph (Nee Julia Dempsey, Mayo Clinic USA) metastatic umbilical nodule from carcinoma stomach.

- They are not uncommon but often present late as they are usually asymptomatic.
- Common tumours are lipoma, fibroma, neurofibroma, and fibromatosis.
- Malignant tumours occasionally when occurs, are either from skin or soft tissues. They may be desmoid tumour, soft tissue sarcoma like fibrosarcoma, dermatofibrosarcoma, liposarcoma, umbilical secondaries (*Sister Joseph Mary tumour*).
- Presents usually as painless progressive swelling. Often ulceration can occur. Attaining large size is also known. It is dull to percuss. On contracting the abdominal wall muscles, swelling becomes prominent and less mobile.
- Differential diagnoses are—abdominal wall abscess, haematoma, intra-abdominal tumours (adherent to abdominal wall).
- U/S abdomen, CT abdomen is diagnostic. Biopsy is essential.
- *Treatment* is wide excision with adequate clearance with removal of adjacent skin and musculoaponeurotic layer. Defect is covered with a *large mesh*.



Figs 17.19A and B: Abdominal wall proliferative ulcer (A) and large tumour (B). (B) May be fibromatosis of abdominal wall also.

DESMOID TUMOUR

(*'Desmo' Means Band/Tendon in Greek*)

- It is a tumour arising from the musculoaponeurotic layer of abdomen, *below* the level of the umbilicus.
- It is unencapsulated, hard, fibroma, presently classified under ***aggressive fibromatosis.***

- 80% of cases occur in women, commonly after deliveries. It is common over old abdominal operation scars (lower abdomen), may be due to old haematomas. Oral contraceptive (OCP) use is more commonly associated with desmoid.
- It is often associated with the familial polyposis colon (FAP), osteomas, odontomes epidermal cysts—***Gardner's syndrome.*** Desmoid tumour is 1000 times more common in FAP.
- It is a slow growing tumour involving muscle and soft tissue of the abdominal wall, locally spreading, often undergoes myxomatous changes.
- Unlike fibromas, it never turns into sarcoma.
- It is often classified as superficial and deep. It is also classified as abdominal (common in females); extra-abdominal (common in males, common in back, head, scars, chest wall, neck).

Histologically it contains multinucleated plasmodial giant cells.

Gardner's syndrome

- Familial polyposis colon
- Osteomas
- Odontomes
- Epidermal cyst—20%

Management

- The possible association of Gardner's syndrome is looked for and Barium enema, X-ray, U/S abdomen are done. *MRI is useful.* Biopsy is done often to confirm the diagnosis.
- *Wide excision* of the tumour with a margin of 2.5 cm is done along with *placement of a mesh to* the abdominal defect.
- It is moderately radiosensitive.
- Drugs like sulindac and tamoxifen are also used.
- Chemotherapeutic agents like doxorubicin, actinomycin D, dacarbazine, carboplatin are used but with significant toxicity.
- Recurrence rate is high—20-40%.



Fig. 17.20: Recurrent abdominal wall tumour. It may be fibromatosis or recurrent dermatofibroma.

EXOMPHALOS (Omphalocele)

- It is the failure of all or a part of the gut to return to the coelomic cavity during early foetal life, as coelomic cavity has not developed properly.



Fig. 17.21: Exomphalos.



Fig. 17.22: Exomphalos major. Note the liver, small and large bowel.

- Sac covering the content is very thin, consists of three layers—outer amniotic membrane, middle Wharton's jelly and inner peritoneal layer. Sac may get ruptured during birth.
- *Omphalocele is often associated with congenital anomalies of cardiac and genitourinary system—70%.*
- Vitellointestinal anomaly, diaphragmatic hernia, malrotation can co-exist, exomphalos, macroglossia, gigantism (EMG) can co-exist in 2/3 of such babies—is called as *Beckwith-Weidman syndrome.*

- Chromosomal trisomies—13, 15, 18 and 21, bladder extrophy, imperforate anus, sacral vertebral anomaly, meningomyelocele.
- Abdominal wall defect can be confirmed *in utero* by U/S. Amniocentesis and chromosomal analysis can be done. This will allow deciding the possible need for termination of pregnancy, or management plan immediately after delivery.
- Abdominal wall muscle is normally developed but peritoneal layer is hypoplastic.

Types

Two types:

Differences between exomphalos minor and exomphalos major

Exomphalos minor	*Exomphalos major*
Small sac	Large sac
Defect < 5 cm	Defect > 5 cm
Content is small bowel only	Liver, small and large bowel
Primary closure is possible	Primary closure is not possible
Good prognosis	Poor prognosis

Exomphalos minor:

- Here the sac is small and *umbilical cord is attached to the summit*, with small bowel as the content. Treatment for E. minor is relatively easier. The sac has to be twisted so as to reduce the content to the peritoneal cavity through the umbilical defect and the abdomen is strapped. Later the defect is closed (Defect is < 5 cm).

Exomphalos major:

- A large defect (> 5 cm) is present with contents lying completely outside. *Umbilical cord is attached to the inferior aspect of the sac.* Contents being small bowel, large bowel and liver.
- Often the sac ruptures during delivery, which in turn leads to severe infection and high mortality. Here immediate surgery (within hours) is the only hope to save the child.



Fig. 17.23: Diagram showing differences between exomphalos minor and exomphalos major.

- As there is hardly any properly developed abdominal cavity, it is not possible to reduce the contents to the peritoneal cavity. So initially, relaxing incisions are placed over the lateral abdominal wall and also the subcutaneous layer has to be undermined so as to accommodate whatever possible contents in the cavity. The contents are not to be forced into the cavity, which in turn may cause intestinal obstruction, respiratory distress, venous engorgement.
- Often a sterile polythene bag *(Silastic silo)* can be wrapped over the content carefully. Gradual twisting of the bag over the summit at regular intervals over two to three weeks will stimulate the peritoneal cavity to increase in capacity and eventually the contents get reduced. Later the defect is closed properly.
- Antibiotics, IV fluids, nutritional support are required during this period.
- *Mortality is higher* in spite of all these—due to sepsis, dehydration, hypothermia and respiratory failure.
- Late ventral hernia should be corrected at later period.

Management of exomphalos

- Vitamin K injection, TPN
- Sepsis control with antibiotics
- Evaluation for other anomalies
- In E. major when sac is intact application of 0.5% mercurochrome with 65% alcohol to promote granulation tissue formation
- Prevention of aspiration
- Prevention of hypothermia
- Wrapping the content with sterile bag/wrapper
- Correction of dehydration
- Definitive surgical procedures like release incisions and closure

GASTROSCHISIS (Belly Cleft)

- It is a defect of the anterior abdominal wall just lateral to the umbilicus. It is common in premature babies.
- It is associated with defect in the involution of 2nd umbilical vein. It is common in mothers *younger than 20 years*, those who take, aspirin, ibuprofen, pseudoephedrine during 1st trimester and who regularly smoke and take alcohol.



Fig. 17.24A

A deaf husband and a blind wife are always a happy couple.



Fig. 17.24B

Figs 17.24A and B: Gastroschisis.

- Umbilicus is normal. The defect is almost always to the right of an intact umbilical cord. Evisceration of the bowel occurs through the defect during intrauterine life. There is no peritoneal sac and the irritating effect of amniotic fluid causes chemical peritonitis with formation of a thick, oedematous membrane.
- *Nonrotation and intestinal atresia are common associations (15%).* Cardiac anomaly is not common as in omphalocele.
- After delivery, these infants are more prone for fluid loss, hypothermia, hypovolaemia, sepsis, metabolic acidosis.
- Necrotising enterocolitis is also common in such infants (20%). They are also more prone for paralytic ileus.

Treatment

General:

- Fluid management.
- TPN.
- Antibiotics.
- R-T aspiration.
- Calorie supplement.

Specific:

- Later under G/A, intestines are pushed into the abdomen through the defect and defect is closed with interrupted nonabsorbable sutures. Often when bowel is not accommodating in the abdominal cavity, bowel is initially placed in sterile silastic silo bag. In later period, it is pushed into the abdomen gradually. Often a part of the bowel may not be viable, then resection and anastomosis has to be done.
- With proper surgery, nutrition, resuscitation, survival rate is 90% which is better than omphalocele.
- *Prolonged postoperative ileus* is the common problem in these patients.

Exomphalos	*Gastroschisis*
1. Defect through umbilicus	1. Defect lateral to umbilicus
2. Covered by sac which has three layers	2. No peritoneal sac
3. Associated with anomalies	3. Not associated (except malrotation)

RECTUS SHEATH HAEMATOMA

- Rectus abdominis muscle is supplied by superior and inferior epigastric arteries. Injury to one of these vessels will cause bleeding and haematoma in rectus sheath.
- Commonly it is *due to bleeding from inferior epigastric artery* in the lower abdomen.

Causes

- Trauma.
- Surgery.
- Spontaneous haematoma, typhoid fever.
- Blood dyscrasias, haemophila, anticoagulant therapy.
- Severe straining and exercises.
- Tetanus and other convulsions.
- Patients on anticoagulants.
- Puerperium.

Features

- Common in females.
- Sudden onset of swelling in lower abdomen, which is tender, warm, firm on one side of the abdomen. Swelling does not cross the midline.
- Bluish discoloration over the swelling.
- U/S and aspiration confirms the diagnosis.
- Should be differentiated from other masses and parietal hernias.
- Coagulation profile is a must.
- CT scan abdomen is often needed.

Treatment

- Usually conservative with analgesics and antibiotics.
- Angiographic *embolisation* of inferior epigastric artery.
- Occasionally requires drainage of haematoma and ligation of inferior epigastric artery.

ABDOMINAL WALL ABSCESS



Fig. 17.25: Abdominal wall abscess in a child.

Causes

- Infected haematoma.
- Umbilical sepsis spreading into the abdominal layers causing the abscess.
- Blood spread from distant focus.



Fig. 17.26: Abdominal wall infection with a wound.

Features

- Tender, soft/firm swelling which is well-localised, adherent to skin and abdominal muscles underneath and not mobile.
- Aspiration will show pus.
- Should be ruled out from intra-abdominal mass, cold abscess, parietal hernia.
- U/S and needle aspiration is confirmative.

Treatment

It is antibiotics and drainage under general anaesthesia.



Fig. 17.27: Abdominal wall abscess.



Fig. 17.28: Postoperative abdominal wall abscess.

MELENEY'S PROGRESSIVE SYNERGISTIC BACTERIAL GANGRENE OF ABDOMINAL WALL

- It is due to infection by microaerophilic streptococci, staphylococci and other anaerobes of the postoperative abdominal or thoracic wounds.
- It is common in HIV, diabetic and immunosuppressed people.



Fig. 17.29: Severe abdominal wall sepsis in a postoperative patient.

- Sudden pain, redness, blackening and gangrene of the skin of the abdomen with abdominal wall necrosis.
- Toxicity, septicaemia, renal failure can occur.

Success is peace of mind, which is a direct result of self-satisfaction.

Treatment

- Antibiotics like penicillins and metronidazole.
- Excision of necrotic and gangrenous tissue until it bleeds.
- Blood transfusion, nutrition supplement.
- Maintaining adequate urine output.
- Management of toxaemia, hyperbaric oxygen and critical care.
- Skin grafting and coverage, when it granulates well.

DIVERICATION OF RECTI (DIASTASIS RECTI)

- It is thinning of linea alba in midline in epigastrium.
- Abdominal wall protrudes in midline with prominent divaricated edges of both recti.
- Transversalis fascia remains intact and hence hernia will not be present; so impulse on coughing will be absent.
- Diastasis will become prominent on lifting the head from the bed.
- It does not require any treatment.



Fig. 17.30: Diverication of the recti with visible mass in epigastrium.

Chapter 18 Hernia

CHAPTER OUTLINE

- Hernia
- Aetiology
- Parts of Hernia
- Classification of Hernia
- Inguinal Hernia
  - Surgical Anatomy of Inguinal Canal
  - Classification of Inguinal Hernia
  - Indirect (Oblique) Inguinal Hernia
  - Newer Classification of Hernia
  - Direct Hernia
  - Recurrent Hernia
  - Hernioplasty
  - Malgaigne Bulging
  - Incarcerated Hernia
- Strangulated Hernia
- Sliding Hernia
- Pantaloon Hernia
- Infantile Hernia
- Femoral Hernia
- Ventral Hernia
- Incisional Hernia
- Umbilical Hernia
- Paraumbilical Hernia
- Epigastric Hernia
- Spigelian Hernia
- Obturator Hernia
- Richter's Hernia
- Lumbar Hernia
- Phantom Hernia
- Sciatic Hernia
- Complications of Hernia Surgery
- Parastomal Hernia
- Different Types of Hernia

HERNIA

Hernia means—*'To bud' or 'to protrude', 'off shoot' (Greek) 'rupture' (Latin).*

- *A hernia is defined* as an area of weakness or disruption of the fibromuscular tissues of the body wall. Often hernia is also defined as an actual anatomical weakness or defect. 75-85% of abdominal wall hernias are groin hernias. 15% of males and 5% of females will develop groin hernia. Presently all hernias in groin are grouped as groin hernias. But in this chapter discussion of the indirect/direct/femoral hernias are given, in detail as it is still practiced and followed in most of the centers and still it is important when surgical technical aspects are considered.
- Hernia is defined as an abnormal protrusion of a viscous or a part of a viscous through an opening, artificial or natural with a sac, covering it.
- *Inguinal hernia is the most common hernia (73%)* because the muscular anatomy in the inguinal region is weak and also due to the presence of natural weakness like deep ring and cord structures.
- Femoral is 17%; umbilical is 8.5%; others are 1.5% (Excluding incisional hernia).
- In general, incisional hernia is next to inguinal hernia in occurrence.



Fig. 18.1: Common and rare sites of hernias.

AETIOLOGY

- Straining.
- Lifting of heavy weight.

> *In order to achieve a radical cure of inguinal hernia it is absolutely essential to restore those conditions in the area of hernial orifice which exist under normal circumstances.*
>
> **—Edoardo Bassini**

- Chronic cough (tuberculosis, chronic bronchitis, bronchial asthma, emphysema).
- Chronic constipation (habitual, rectal stricture).
- Urinary causes
  - Old age—BPH, carcinoma prostate.
  - Young age—stricture urethra.
  - Very young age—phimosis, meatal stenosis.
- Obesity.
- Pregnancy and pelvic anatomy (especially in femoral hernia in females).
- Smoking.
- Ascites.
- Appendicectomy through McBurney's incision may injure the ilioinguinal nerve causing right sided *direct* inguinal hernia.



Fig.18.2: Old appendicectomy scar with direct inguinal hernia. It is due to injury to ilioinguinal nerve during appendicectomy.



Fig. 18.3: Inguinal hernia in a patient who is having benign prostatic hyperplasia (BPH) with Foley's urinary catheter. He is having paraphimosis probably for not replacing back the retracted prepuce after catheterisation.

- An indirect inguinal hernia occurs in a congenital, preformed sac, i.e. the remains of processus vaginalis. Chances of presence of bilateral preformed sac is 60%.
- Familial collagen disorder—*Prune Belly syndrome*.
- Acquired herniation is also probably due to collagen deficiency called as *metastatic emphysema of Read.*

PARTS OF HERNIA

Hernia comprises of:

- *Covering.*
- *Sac.*
- *Content.*

Sac is a diverticulum of peritoneum with mouth, neck, body and fundus. Neck is *narrow in indirect sac but wide in direct sac*. Body of the sac is thin in infants, children and in indirect sac but is thick in direct and long-standing hernia.

  - Hernia without neck: Those hernias with larger mouth lack neck, e.g. direct hernia, incisional hernia.
  - Hernia without sac: Epigastric hernia—it is protrusion of extraperitoneal pad of fat.

Coverings of the sac are the layers of the abdominal wall through which the sac passes.

Contents of Sac

  - Omentum—*Omentocele* (Epiplocele). Difficult to reduce the sac later, initially it can be reduced easily.
  - Intestine—*Enterocele*— commonly small bowel, but sometimes even large bowel.
  - Difficult to reduce the sac initially.
  - *Richter's hernia*: A portion of circumference of bowel is the content.
  - Urinary bladder may be the content or part of the posterior wall of the sac—*cystocele*.
  - Ovary, often with fallopian tube.
  - Meckel's diverticulum—*Littre's hernia*.



Fig. 18.4: *Littre's hernia* with Meckel's diverticulum as content.

  - *Fluid:* Fluid is secreted from congested bowel or omentum. It may be an infected fluid or ascitic fluid or blood from the strangulated sac.



Fig. 18.5: Parts of hernia. Note the fundus, body and neck of the hernia.

CLASSIFICATION OF HERNIA

Classification I (Clinical)

1. Reducible Hernia

Hernia gets reduced on its own or by the patient or by the surgeon. Intestine reduces with gurgling and it is difficult to reduce the first portion. Omentum is doughy, and it is difficult to reduce the last portion. Expansile impulse on coughing present.



Fig. 18.6: Diagram showing the differences between indirect and direct sacs.



Fig. 18.7: Inferior epigastric artery on table. It is very important landmark during surgery whether open or laparoscopic approach.

2. Irreducible Hernia

Here contents cannot be returned to the abdomen due to narrow neck, adhesions, overcrowding. Irreducibility predisposes to strangulation.

3. Obstructed Hernia

It is an irreducible hernia with obstruction, but blood supply to the bowel is not interfered. It eventually leads to strangulation.



Fig. 18.8: Inguinal hernia presenting with features of intestinal obstruction.

Garrey's stricture: Constriction that occurs due to ischaemic narrowing of small bowel which has reduced from an obstructed hernia.



Fig. 18.9: Garrey's stricture on table. Due to ischaemia, a stricture is formed in the bowel at the constriction ring after reduction.

4. Inflamed Hernia

It is due to inflammation of the contents of the sac, e.g. appendicitis, salpingitis. Here hernia is tender but not tense; overlying skin is red and oedematous.

5. Strangulated Hernia

It is an irreversible hernia with obstruction to blood flow. The swelling is tense, tender, with no impulse on coughing and with features of intestinal obstruction.

Features of intestinal obstruction may be absent in case of omentocele, Richter's hernia, Littre's hernia.

Classification II

Congenital—Common

It occurs in a preformed sac/defect. Clinically may present at a later period due to any of the precipitating causes like in indirect inguinal hernia.

Acquired

It is secondary to any causes which raise the intra-abdominal pressure leading into weakening of the area like in direct inguinal hernia.

Classification III: According to the Contents

- Omentocele—omentum.
- Enterocele—intestine.
- Cystocele—urinary bladder.
- Littre's hernia—Meckel's diverticulum.
  Note: Littre described Meckel's diverticulum in a hernial sac 81 years before Meckel was born.
- Maydl's hernia.
- Sliding hernia.
- Richter's hernia—part of the bowel wall.

Classification IV: Based on Sites

- Inguinal hernia—occurring in inguinal canal.
- Femoral hernia—occurring in femoral canal.
- Obturator hernia.
- Diaphragmatic hernia.
- Lumbar hernia.
- Spigelian hernia.
- Umbilical hernia.
- Epigastric hernia.



Fig. 18.10: Inguinal hernia on right side in a child. It needs only herniotomy.

Herniography (By Gullmo)

- Injection of contrast material into the peritoneal cavity and taking films in supine and prone positions to diagnose small protrusions of peritoneal sac is called as herniography.
- It was earlier also used for diagnosing undescended testis.

INGUINAL HERNIA

SURGICAL ANATOMY OF INGUINAL CANAL

Superficial inguinal ring is a triangular opening in the external oblique aponeurosis and is 1.25 cm above the pubic tubercle. The ring is bounded by a superomedial and inferolateral crus. Normally the ring does not admit the tip of little finger.

Deep inguinal ring is a U-shaped condensation of the transversalis fascia, lies 1.25 cm above the inguinal ligament midway between the symphysis pubis and the anterosuperior iliac spine.

Inguinal (Poupart's) ligament**:** It is formed by the lower border of the external oblique aponeurosis which is thickened and folded backwards on itself, extending from anterosuperior iliac spine to pubic tubercle.

Inguinal canal: It is an oblique passage in lower part of abdominal wall, 4 cm long, situated above the medial ½ of inguinal ligament, extending from deep inguinal ring to superficial inguinal ring.

In infants both superficial and deep rings are *superimposed* without any obliquity of the inguinal canal.

Inguinal canal in female is called as **'canal of Nuck.'**

Contents of inguinal canal

- Spermatic cord in males
- Round ligament in females
- Ilioinguinal nerve

Contents of spermatic cord

- Vas deferens
- Artery to vas
- Testicular and cremasteric artery
- Genital branch of genitofemoral nerve
- Pampiniform plexus of veins
- Remains of processus vaginalis
- Sympathetic plexus around the artery to vas



Ilioinguinal nerve
Pampiniform plexus of veins
Internal spermatic fascia
Artery to cremaster
Testicular artery
Cremasteric fascia with muscle
Genital branch of genitofemoral nerve
Lymph vessels
Vas deferens
Artery of ductus deferens

Fig. 18.11: Structures related to cord in the inguinal canal.

Coverings of Spermatic Cord

- Internal spermatic fascia from fascia transversalis
- Cremasteric fascia.
- External spermatic fascia from external oblique aponeurosis is seen below the external ring in the scrotum.


Conjoined tendon
Rectus muscle
ASIS
Deep inguinal ring
Superficial inguinal ring
Pubic tubercle

Fig. 18.12: Surgical anatomy of inguinal canal.

Boundaries

In front: External oblique aponeurosis and conjoined muscle laterally.

Behind: Inferior epigastric artery, fascia transversalis and conjoined tendon medially.

Above: Conjoined muscle (Arched fibres of internal oblique).

Below: Inguinal ligament.

Defence mechanism of inguinal canal

- Obliquity of inguinal canal
- Arching of conjoint tendon
- '*Shutter mechanism'* of internal oblique
- '*Ball valve mechanism'* due to contraction of cremaster muscle which plugs to superficial ring
- When external oblique muscle contracts, intercrural fibres of superficial ring appose causing '*slit valve mechanism'*
- Hormones


Internal oblique muscle
Anterosuperior iliac spine
Iliohypogastric nerve
Inferior epigastric vessels
Ilioinguinal nerve
Inguinal ligament
Genital branch of GF nerve
A

Fig. 18.13A


Iliohypogastric nerve
B
Ilioinguinal nerve
C

Figs 18.13B and C

Figs 18.13A to C: Nerves in inguinal canal: *Iliohypogastric nerve* (T_{12}, L_1) runs between transversus abdominis and internal oblique divides into lateral and anterior branches; anterior branch pierces internal oblique 2 cm medial to anterosuperior iliac spine and later pierces the external oblique 3 cm above the superficial inguinal ring to supply abdominal skin above the pubis. *Ilioinguinal nerve* (L_1) pierces the transversus abdominis near anterosuperior iliac spine, pierces the internal oblique just above the internal ring, and enters the inguinal canal within cremasteric fascia outside the cord supplies medial thigh, base of penis and proximal scrotum. *Genital branch of genitofemoral nerve* (L_1, L_2) enters the cord through internal ring supplying the cremaster and scrotum.

Fruchaud's Myopectineal Orifice

It is an osseo-myo-aponeurotic tunnel. *It is through this tunnel all groin hernias occur.*

It is bounded:

- Medially by lateral border of rectus sheath.
- Above by the arched fibres of internal oblique and transversus abdominis muscle.
- Laterally by the iliopsoas muscle.
- Below by the pectin pubis and fascia covering it.

> *When spermatic cord is rolled transversely beneath the gentle pressure of index finger. Thickening of the cord denotes presence of a hernia.*
> **— William E Ladd**


Rectus muscle
Supravesical external hernia site
Direct hernia site
Indirect hernia site
Internal ring (cord)
Femoral vessels
Femoral hernia site
Myopectineal orifice (MPO/Fruchaud's)

Fig. 18.14: *Fruchaud's myopectineal orifice* is bound—by lateral border of rectus, iliopsoas, conjoint tendon, pectin pubis.

CLASSIFICATION OF INGUINAL HERNIA (EARLIER)

Classification I

Anatomical Classification (in Inguinal Hernia)

Indirect hernia

It comes out through internal ring along with the cord. It is lateral to the inferior epigastric artery.

Direct hernia

It occurs through the posterior wall of the inguinal canal through 'Hesselbach's triangle' (bounded medially by lateral border of rectus muscle, laterally by inferior epigastric artery, below by inguinal ligament). Sac is medial to the inferior epigastric artery.


Antero-superior iliac spine
Inguinal ligament
Femoral hernia
Direct inguinal hernia
Indirect inguinal hernia
Pubic tubercle

Fig. 18.15: Location of direct and indirect inguinal hernia and femoral hernia.

Classification II

According to the Extent

- *Incomplete*:
  - **Bubonocele:** Here sac is confined to the inguinal canal.
  - **Funicular:** Here sac crosses the superficial inguinal ring, but does not reach the bottom of the scrotum.
- *Complete:* Here sac descends to the bottom of the scrotum.

Saddle-bag or pantaloon hernial sac has got both medial and lateral component.

Note:

Inguinal hernia is above and medial to the pubic tubercle. Femoral hernia is below and lateral to pubic tubercle.



Fig. 18.16: Bubonocele.



Fig. 18.17: Irreducible left side inguinal hernia. It is above the upper part of the testis (funicular). Taxis is the method used to reduce it.



Fig. 18.18: Bilateral complete inguinal hernia. Here hernia descends up to the bottom of the scrotum.

NEWER CLASSIFICATION OF HERNIA

I. Gilbert Classification

***Type I*:** Hernia has got snug internal ring through which a peritoneal sac passes out as indirect sac.

Type II: Hernia has a moderately enlarged internal ring which admits one finger but lesser than two finger breadth. Once reduced it protrude during coughing or straining.

Type III: Hernia has got large internal ring with defect more than two finger breadth. Hernia descends into the scrotum or with sliding hernia. Once reduced it immediately protrudes out without any straining.

Type IV: It is direct hernia with large full blow out of the posterior wall of the inguinal canal. The internal ring is intact.

Type V: It is a direct hernia protruding out through punched out hole/defect in the transversalis fascia. The internal ring is intact.

Type VI: Pantaloon/double hernia.

Type VII: Femoral hernia.

Type VI and VII are Robbin's modifications.

II. NYHUS Classification

Type I: Indirect hernia with normal deep ring.
Type II: Indirect hernia with dilated deep ring.
Type III: Posterior wall defect.
  a. Direct.
  b. Pantaloon hernia.
  c. Femoral hernia.
Type IV: Recurrent hernia.

III. BENDAVID Classification [Type, Staging, Diameter (TSD) Classification]

Type I: Anterolateral defect (indirect).
Type II: Anteromedial (direct).
Type III: Posteromedial (femoral).
Type IV: Posterior prevascular hernia.
Type V: Anteroposterior defect: Inguino-femoral hernia.

IV. Classification—Casten's Staging

Stage 1: An indirect hernia with a normal internal ring.
Stage 2: An indirect hernia with enlarged internal ring.
Stage 3: All direct or femoral hernias.

V. Halverson and McVay Classification

Class 1: Small indirect hernia.
Class 2: Medium indirect sac.
Class 3: Large indirect hernia or direct hernia.
Class 4: Femoral hernia.

VI. Ponka's Classification

1. Indirect inguinal hernia:
   - Uncomplicated indirect hernia.
   - Sliding indirect hernia.
2. Direct hernia:
   - Small defect on the medial aspect of the Hesselbach's triangle.
   - Diverticular hernia in the posterior wall with an otherwise intact inguinal floor.
   - A large diffuse direct inguinal hernia of the entire floor of Hesselbach's triangle.

INDIRECT (OBLIQUE) INGUINAL HERNIA

- This is the most common type of hernia (65%).
- It is more common in younger age group as compared to direct inguinal hernia which is more common in elderly.
- It is more common on right side in 1st decade but in 2nd decade the incidence is equal on both sides.
- Hernia is bilateral in 30% of cases.
- Sac is thin in indirect type. Neck is narrow and lies lateral to inferior epigastric vessels.



Fig. 18.19: Complete indirect hernia.



Figs 18.20A and B: Giant inguinal hernias in different sides. (A) Right side and (B) Left side.

Coverings of indirect hernia (from inside out)

- Extraperitoneal tissue
- Internal spermatic fascia
- Cremasteric fascia
- External spermatic fascia
- Skin

Precipitating causes for inguinal hernia

- Smoking
- Obesity
- Respiratory causes like bronchial asthma, tuberculosis, bronchitis
- Ascites
- Previous surgery like appendicectomy which can cause direct inguinal hernia
- Chronic constipation due to anorectal strictures. Rectal stricture may be due to chronic proctitis (amoebic), tuberculosis of anorectum, previous anorectal surgery, rectal carcinoma or stricture due to lymphogranuloma venereum
- Urinary problems like benign prostatic hyperplasia (BPH), urethral stricture
- Straining
- Multiple pregnancies

Types

Three types

1. *Bubonocele***:** Where the hernia is limited to inguinal canal.



Fig. 18.21: Surgical anatomy of indirect hernia.

2. *Funicular:* Processus vaginalis is closed just above the epididymis. Contents of the sac can be felt separately from testis, which lies below the hernia.
3. *Complete (Scrotal*): Testis appears to lie within the lower part of hernia. It can occur in any age group. It occurs in a congenital preformed sac (processus vaginalis). More commonly contents descend into the pre-existing sac, only when there are precipitating causes which force the content down.

Expansile impulse on coughing

- Hernia
- Laryngocele
- Meningocele
- Empyema necessitans
- Swellings with intracavitary communications like thorax, cranium, and abdomen like dermoid



Fig. 18.22: Types of indirect inguinal hernia.

Clinical Features

- Prevalence of inguinal hernia is 25% in males; 2% in females.
- It is more common in males (20 : 1 :: Male : Female).
- Patient presents with dragging pain and swelling in the groin which is better seen while coughing and standing; and felt together with an expansile impulse.
- In *complete* type, the content descends down to the scrotum completely.
- Contents are either small bowel, large bowel, omentum or combination of all these. In females, sometimes ovary and tubes may be the content. In infants, swelling appears when the child cries and is often translucent.
- It is usually reducible, but can go for irreducibility, inflammation, obstruction, strangulation.
- ***Internal ring occlusion test***: Internal ring is located half inch above the mid-inguinal point (center point between anterosuperior iliac spine and pubic symphysis). After reducing the contents, in lying down position, internal ring is occluded using the thumb. Patient is asked to cough. If a swelling appears medial to the thumb, then it is a direct hernia. If swelling does not appear and on releasing the thumb swelling appears during coughing, then it is an indirect hernia confirmed in standing position.
- ***Ring invagination test***: After reduction of hernia, the little finger/index finger of the examiner is invaginated from the bottom of the scrotum, gradually pushed up and rotated to enter the superficial inguinal ring. The impulse on coughing is felt at the tip of the invaginated finger. This test is done only in males.
- ***Zieman's test (Fig. 18.23)***: The examiner places his index finger on the deep inguinal ring and middle finger on the superficial inguinal ring, ring finger over saphenous opening. The patient is asked to cough or to hold the nose and blow. If the impulse is felt on the index finger, it is indirect hernia.
- ***Head*** or ***leg rising test (Fig. 18.24)*** is done to look for abdominal wall muscle tone and Malgaigne bulgings.
  Valsalva manoeuver is also used to check the tone of abdominal wall muscles.
- Abdominal, respiratory, urological examination is done to look for any precipitating factors like chronic bronchitis, ascites, stricture urethra, BPH.
- ***Per rectal*** examination is a must.
- ***Inguinal hernia in females:*** Increased thickness of labium majus on palpation, when compared to contralateral side.



Fig. 18.23: *Zieman's test*. Index finger on deep ring; middle finger on superficial ring and ring finger over saphenous opening—are placed after reducing the content. Patient is asked to cough and impulse is felt in finger corresponding to the existing hernia.



Fig. 18.24: Head or leg rising or Valsalva manoeuvre is important to elicit abdominal muscle tone.

- ***Silk glove sign:*** Index finger is invaginated across scrotum towards the external ring. When patient coughs, inguinal hernia is felt as a slit like sensation.
- Palpation of bulbar urethra for stricture (thickening/crescent like feel/button like depression).


Left inguinal hernia

Fig. 18.25: Left side inguinal hernia in a female.

Use five fingers of the hand to complete all tests for hernia

- Thumb—for deep ring occlusion test
- Index, middle and ring fingers for Zieman's test
- Little finger for superficial ring invagination test

Rules of hernia examination

- Never forget to examine opposite side
- Never forget to do per rectal examination
- Never forget to examine urethra
- Never forget to check abdominal muscle tone

Differential diagnosis

- Hydrocele—infantile/encysted/large vaginal/bilocular
- Undescended testis
- Femoral hernia
- Lipoma of the cord
- Hydrocele of the canal of nuck (in females)
- Inguinal lymph node enlargement
- Groin abscess


1
2
3
4
5
6
7
8
9
Differential diagnosis for groin swellings:
1. Inguinal hernia
2. Femoral hernia
3. Inguinal lymphadenitis
4. Infantile hydrocele
5. Saphena varix
6. Lipoma of cord
7. Groin abscess
8. Funiculitis
9. Undescended testis

Fig. 18.26: Differential diagnosis for groin swellings.

Indirect inguinal hernia	*Direct inguinal hernia*
Can occur in any age from childhood to adult	Common in elderly
Occurs in a pre-existing sac	Always acquired
Protrusion through the deep ring; herniation occurs later	Herniation through posterior wall of the inguinal canal
Pyriform/oval in shape; descends obliquely and downwards	Globular/round in shape; descends directly forward bulge

Hydrocele of canal of Nuck is the most common differential diagnosis for inguinal hernia in females.

Can become complete by descending down into the scrotum	Descent down into the scrotum is rare
Neck of the sac is narrow and lateral to inferior epigastric artery	Neck of the sac is wide and medial to inferior epigastric artery
Sac is anterolateral to the cord	Sac is posterior to the cord
Ring occlusion test does not show any impulse after occluding the deep ring	Test shows impulse even after occluding the deep ring
Invagination test shows impulse on the tip of the little finger	Impulse is felt over the pulp of the little finger
Zieman's test shows impulse on the index finger	Test shows impulse on the middle finger
Commonly unilateral but can be bilateral	Commonly bilateral
Obstruction/strangulation are common	Rare but can occur
Sac should be opened during surgery	Sac is not necessarily opened unless obstruction is present

In enterocele	***In omentocele (epiploecele)***
First part is difficult to reduce	First part is easier to reduce
but last part is easier. There	but last part is difficult. Has
will be gurgling sound on reduction	a doughy feeling
Resonant on percussion	Dull on percussion
Peristalsis is seen	No peristalsis seen
Bowel sounds may be heard	Bowel sounds not heard



Fig. 18.27A



Fig. 18.27B

Figs 18.27A and B: Indirect inguinal hernial sac on table and opening the sac over fundus.



Fig. 18.28: On table direct sac which is medial to inferior epigastric artery. Direct sac is usually not opened. Inverting sutures may be placed if needed.

Investigations

- Chest X-ray to rule out chronic bronchitis.
- Ultrasound of abdomen.
- Tests relevant for precipitating causes.

Treatment

> *This method reconstructs the inguinal canal as it is physiologically, with two rings, one abdominal, the other subcutaneous; and with two walls, one posterior and the other anterior, between which the spermatic cord passes obliquely.*
>
> —**Edoardo Bassini,** 1887

Always Surgery

In infants:

- Whether it is hernia or hydrocele, only *herniotomy* is done through inguinal approach (*Michaelis plank operation*).



Fig. 18.29: Inguinal hernia in 4-year-old child. Here just herniotomy is required. Repair is not done.

In adults:

- It includes *herniotomy,* i.e. excision of hernial sac and ***herniorrhaphy or hernioplasty (ideal)*** (strengthening of the posterior wall of inguinal canal either by repair or mesh). Precipitating causes should be treated first, like TURP for BPH, dilatation of stricture urethra, treatment of chronic bronchitis. Patient is advised to avoid smoking.
- Hernioplasty is the present choice (ideal) for all inguinal and groin hernias. Mesh is placed either onlay/underlay (over conjoint tendon to inguinal ligament) or inlay (in preperitoneal space). Polypropylene mesh is used. Herniotomy is done prior to mesh placement. TEP (Totally extraperitoneal laparoscopic preperitoneal mesh repair) is preferred method. (For detail refer hernioplasty in later part of this chapter).

Repair may be:

- *Pure tissue repair*: Shouldice, MacVay (Still very useful repairs) and Modified Bassini (not very useful—high recurrence rate as it is repair with tension and nonphysiological)
- *Prosthetic repair*: Lichtenstein, Rives, Gilbert, Stoppa, TEP, TAPP

Repair also can be:

- *Anterior repair*: Through anterior inguinal approach—Bassini's, Shouldice, MacVay, darning, Andrew's, Wilkinson, Copper's, Lichtenstein mesh repair, PHS repair, Rives preperitoneal repair
- *Posterior repair*: Through suprainguinal preperitoneal approach—Nyhus repair, Stoppas, TEP, TAPP, Kugel's repairs

Herniotomy

Anaesthesia: Spinal or G/A or local anaesthesia.

Procedure: After cleaning and draping, skin is incised—1.25 cm above and parallel to the medial two/third of inguinal ligament. Two layers of superficial fascia (outer Camper's fascia and inner Scarpa's fascia) are incised. External oblique aponeurosis is incised. Upper leaf is reflected above and lower leaf is reflected downwards to visualise and expose the inguinal ligament. Ilioinguinal nerve is safeguarded. Cremasteric muscle is opened. Cord structures are dissected. Sac which is anterior and lateral to cord is identified and is pearly white in colour. Dissection is usually started from the fundus and extended towards the neck which is identified by extraperitoneal fat. The neck is narrow and is lateral to inferior epigastric artery. Sac is opened at the fundus. Finger is passed to release any adhesions. Sac is twisted so as to prevent the content from coming back. It is transfixed using absorbable suture material (chromic catgut 2-0 or *vicryl*) and is excised distally.



Fig. 18.30: Large hernia with Foley's catheter. Patient had retention of urine due to benign prostatic hyperplasia. He underwent Transurethral resection of prostate [TURP] first and later hernioplasty.



Fig. 18.31: Incision for inguinal hernia. It is 1.25 cm above and parallel to medial third of inguinal ligament.



Fig. 18.32: Opened indirect sac in herniotomy.



Fig. 18.33: Hernia with enterocele as content.



Fig. 18.34: Sac should be twisted before transfixing to prevent contents getting in.

Modified Bassini's Herniorrhaphy

- ♦ Conjoint tendon and inguinal ligament are approximated using interrupted nonabsorbable monofilament sutures {polypropylene (prolene, blue in colour)}. Medial most stitch is taken from the periosteum of pubic tubercle (*called as key or Bassini's stitch*). External oblique is closed and other layers are also closed.
- ♦ It is strengthening of the posterior wall of the inguinal canal by approximation of the conjoint tendon to inguinal ligament using monofilament nonabsorbable suture material. Absorbable suture material like catgut should not be used as 50% of its tensile strength will be lost in 7 days. It takes 6 months to achieve more than 80% of tensile strength in repaired hernial wound; and so nonabsorbable suture material has to be used here to maintain the same adequate tensile strength in this period. Multifilament suture material like silk may precipitate infection because of the crevices in the suture material and tensile strength is not as good as monofilament suture material. Commonly used suture material is either *polypropylene* [*prolene* (blue in colour)] or *polyethylene* [*ethylon* (black in colour)]. Continuous sutures compromises the blood supply and interferes with proper healing; and strength will not be as adequate as interrupted sutures. So always interrupted sutures are used. Earlier, most common surgery done for groin inguinal hernia was modified Bassini's repair. But now hernioplasty is the commonly done procedure for both direct and indirect sac. In direct hernia, sac is usually not opened but in indirect hernia, sac is always opened.

Anaesthesia Used for Inguinal Hernia Repair

General/spinal/epidural or local anaesthesia can be used to do inguinal hernia repair. Local anaesthesia is becoming popular for open approach. General anaesthesia is needed in children and for TAPP and TEP procedures.

Technique of Local Anaesthesia

Around 50-60 ml of xylocaine 0.5% is used. Plain xylocaine 0.5% or xylocaine 0.5% with adrenaline can be used. Plain xylocaine—dose is 2 mg/kg body weight. Xylocaine with adrenaline—dose is 7 mg/kg body weight.

Two methods are used:

1. *Nerve block method (point block)*
   - 10 ml of xylocaine is infiltrated 2 cm above and medial to anterosuperior iliac spine to block the iliohypogastric nerve.
   - Midinguinal point is infiltrated with 10 ml xylocaine.
   - Pubic tubercle point is infiltrated with 10 ml xylocaine.
   - 10 ml of xylocaine is infiltrated just below the inguinal ligament lateral to femoral artery to block the genital branch of genitofemoral artery.
   - Line of skin incision is infiltrated with 10 ml of xylocaine.
   - Later neck of the hernial sac is infiltrated with 10 ml of xylocaine.
2. *Field block method (Shouldice method)*
   - Skin of around 4 cm wide area is infiltrated into the subcutaneous plane as first layer from anterosuperior iliac spine to pubic symphysis. Skin, subcutaneous and two layers of superficial fascia (Camper and Scarpa's) are incised.
   - Area deep to external oblique aponeurosis is infiltrated with 10 ml of xylocaine. External oblique aponeurosis is incised.

- Exposed inguinal canal and hernial sac is infiltrated with 10 ml of xylocaine to continue with the dissection.



Figs 18.35A and B: Inguinal hernia with mesh placement. Prolene mesh is white in colour. It is sutured to conjoint tendon and inguinal ligament by interrupted sutures using nonabsorbable monofilament suture material.


Internal ring
Inguinal ligament
Conjoint tendon
External oblique aponeurosis
Sutures (interrupted)
Cord
Testes

Fig. 18.36: *Modified Bassini's repair*. It is approximation of inguinal ligament to conjoined tendon using interrupted nonabsorbable monofilament sutures.



Fig. 18.37: On table inguinal hernia surgery with cord holding forceps.

Complications of herniorrhaphy

- Haemorrhage
- Haematoma, seroma
- Infection—1-5%
- Haematocele
- Post-herniorrhaphy hydrocele, lymphocele
- Hyperaesthesia over the medial side of inguinal canal due to injury to iliohypogastric nerve—neuralgia (15%)
- Recurrence—10-15%
- Osteitis pubis
- Injury to urinary bladder/bowel
- Testicular atrophy, penile oedema rarely can occur


Right side clean wound
Infected hernia wound left side

Fig. 18.38: Left side inguinal hernia wound infected. Right side hernia wound is clean.

> *In exomphalos, the protruding abdominal contents being covered only by a diphanous membrane, through which viscera are exposed to view, as if exhibited in a show case.*
> **— William E Ladd**



Fig. 18.39: Hernioplasty, mesh is infected. It needs removal of mesh.

Lytle's Repair

Often internal ring is narrowed by placing interrupted sutures over the medial side of the ring to the transversalis fascia using either thread or silk (To narrow the ring and push the cord laterally).



Fig. 18.40: *Lytle's repair*. It is narrowing of the widened internal ring.

Shouldice Repair

Even though transversalis fascia is thin, it is a tough layer and so double breasting of this fascia using continuous sutures (with nonabsorbable material) strengthens the posterior wall of the inguinal wall.

It is a multilayered repair. It was originated at *Shouldice hernia clinic in Toronto* where it was usually done under local anaesthesia. After doing herniotomy as in any other inguinal hernia, transversalis fascia is incised along the line of the wound from deep ring to pubic tubercle. Lower flap of fascia is sutured to posterior part of the upper flap. Upper flap is sutured to the inguinal ligament. It causes double-breasting of the transversalis fascia. Then conjoint tendon and inguinal ligament is further approximated by two layers of continuous sutures. External oblique aponeurosis is sutured in two layers (double-breasting) in front of the cord. Hence the original Shouldice repair is 6 layered procedure. First two layers of transversalis fascia, next two layers of conjoint tendon and last two layers of external oblique aponeurosis. Suture material used here is fine steel wire of 34 gauge (in original Shouldice repair) or polypropylene or polyethylene. Recurrence rate is 1%.

Berliner modified Shouldice repair—It involves double-breasting of the transversalis fascia like in Shouldice repair and single layer closure of the external oblique aponeurosis without any additional two-layered repair of conjoint tendon to inguinal ligament.

Note:
Cremaster is excised in Shouldice repair along with external spermatic fascia to achieve good success rate. As testis loses its support, it causes *hanging/clapper in bell testis*. It also injures genital branch of genitofemoral nerve.

Tanner Slide Operation

To reduce the tension in the repair area, relaxing incision is placed over the lower rectus sheath so that conjoined tendon is allowed to slide downward.



Fig. 18.41: *Tanner slide operation*—relaxing incision placed over the lower medial rectus sheath to reduce the tension after modified Bassini's repair.

Darning (Abrahamson Nylon Darning)

Continuous intervening network of nonabsorbable sutures are placed between conjoint tendon and inguinal ligament to give good support to posterior wall of inguinal hernia.



Fig. 18.42: Darning between inguinal ligament and conjoined tendon to act as a support to posterior wall of the inguinal canal.

Koontz Operation (New York, 1963)

In old people after taking consent, orchidectomy is done along with removal of entire cord, testis and total closure of posterior inguinal wall by repair so as to reduce the recurrence.

Removal of Cord at Inguinal Region (Hamilton-Bailey Operation)

Cord is removed from the inguinal canal by ligating both at external and internal ring. But testis is retained (for psychological reason) and closure of inguinal canal by repair is done.

Andrew's Operation

It involves overlapping of the external oblique apo-neurosis.

McVay Operation—1940 (Cooper's Ligament Repair)

It is repair by placing interrupted sutures between transversalis fascia to Copper's ligament (superior pubic ligament) starting from pubic tubercle medially towards femoral sheath and later continued as suture repair between transversalis fascia and iliopubic tract laterally up to the entrance of cord is reached. It is a pure tissue repair. It requires relaxing vertical incision at the lateral border of the anterior rectus sheath, from pubic tubercle point extending superiorly for 4 cm. It covers all three groin defects—indirect, direct and femoral.

Nyhus (Original) Iliopubic Repair

Here with a transverse incision and suprainguinal approach, lateral part of lower end of the rectus is retracted medially after opening anterior rectus sheath. Posterior rectus sheath is opened. Sac is dissected proximally and often ligated. Transaponeurotic arch (transverse abdominis muscle and transversalis fascia) is sutured below to Copper's ligament and iliopubic tract.

Wilkinson Method

Transversus abdominis and internal oblique are sutured to inguinal ligament with continuous monofilament sutures—1st layer; lower free edge of the external oblique is passed above, behind the cord and is sutured to internal oblique surface—2nd layer; upper free edge of the external oblique is brought down in front of the cord and is sutured to lower visible surface of the external oblique—3rd layer. It has less recurrence rate.

Hernioplasty

- Prosthetic mesh repair is used to strengthen the posterior wall of the inguinal canal.
- Onlay like Lichtenstein repair, underlay, PHS repair (Gilbert's), Stoppas, totally extraperitoneal preperitoneal (TEP), transabdominal preperitoneal (TAPP) mesh repair are different prosthetic repairs used. Usually polypropylene mesh is used.
- Recurrence rate has reduced significantly by prosthetic mesh repair. But incidence of mesh *inguinodynia* has increased due to entrapment of ilioinguinal or iliohypogastric nerves in the mesh.
- Even though it is commonly done procedure at present for inguinal hernia, in adolescents whether it should be used or not is a debate. In children it is not used. In strangulated hernia or in presence of sepsis it is not used, only tissue repair is done (Different procedures are discussed at a later part of this chapter).



Fig. 18.43: Hernioplasty: Mesh repair—Lichtenstein's method (done under local anaesthesia).

Conservative treatment

- ***Taxis:*** Patient is placed in supine position with hip and knee flexed and hip internally rotated. Contents are pushed with one hand directing with other hand
- ***Use of Truss:*** Rat-tailed sprung truss is used. Measurement is taken from the tip of greater trochanter to third piece of sacrum circumferentially
  - Complications are discomfort, ulceration, strangulation, inflammation, testicular atrophy, ilioinguinal neuritis, femoral neuritis
  - It may be used in elderly people, who are not fit for anaesthesia and surgery
  - Conservative treatment should be avoided in hernia as much as possible
  - Truss is absolutely contraindicated in femoral and sliding hernia
  - Truss increases the surgical bleeding, postoperative oedema, testicular pain

DIRECT HERNIA

- 10-15% of the hernias are direct.
- 50% of direct hernias occur bilateral.
- 35% of inguinal hernias are direct.
- It is uncommon in females and children.
- It is always acquired, due to weakening of posterior wall of inguinal canal.
- Hernia is medial to the inferior epigastric artery with wide neck. Sac is thick and often the medial wall or content may be bladder.
- Direct hernia occurs through *Hesselbach's* triangle which is bounded by inferior epigastric artery laterally, lateral border of rectus medially, inguinal ligament below. It is divided into medial and lateral halves by obliterated umbilical artery (medial umbilical ligament). So direct hernia is classified as *medial or lateral depending on which part of the Hesselbach's triangle, it is arising from.*



Figs 18.44A and B: *Hernia truss*. It is used only when patient is not fit for surgery. It may precipitate strangulation. Before placing truss, contents of the hernia should be reduced completely.



Fig. 18.45: Surgical anatomy of direct inguinal hernia.



Fig. 18.46: Surgical anatomy of Hesselbach's triangle.

Coverings of direct hernia (from inside out)

- Extraperitoneal tissue
- Fascia transversalis
- Conjoined tendon
- External spermatic fascia
- Skin

Predisposing factors

- Chronic cough, smoking
- Straining
- Constipation
- Heavy work
- Previous appendicectomy



Fig. 18.47: Bilateral direct inguinal hernia.

- ***Malgaigne bulgings*** are often seen in these patients on examination, more often than in indirect hernia. They are protrusion of abdominal wall muscle during leg raising test as weak, soft, supple, swellings which signifies poor abdominal muscle tone.
- Direct hernia rarely descends into the scrotum and strangulation is not as common as in indirect hernia. But in longstanding cases, it can descend down to the scrotum and strangulation can occur.



Fig. 18.48: Large bilateral direct hernia. Occasionally direct hernia descends down and becomes complete and then may cause obstruction. Descent is not as common as indirect hernia.

Treatment

Surgery:

- Usually direct sac is not opened.
- Care should be taken at the medial aspect due to the presence of bladder (*bladder should be emptied* before surgery).
- Ideally *hernioplasty (mesh repair*) is done. In case of bilateral hernia, mesh repair can be done on both sides together. Laparoscopic approach (TEP) or suprapubic approach may be better in bilateral cases.



Fig. 18.49: Bilateral direct hernia. Note the medial location of the direct hernias.

Funicular Direct Hernia (Prevesical Hernia)

- It is also called as *Ogilvie's hernia*.
- It is a type of direct hernia which is prone for strangulation.
- It is a narrow necked hernia with prevesical fat and a portion of bladder, and or intestine that herniates through a small defect in the medial part of the conjoined tendon just above the pubic tubercle.
- It occurs in elderly males.

Giant Inguinal Hernia

Hernia reaches below the mid-level of thigh when patient stands.

RECURRENT HERNIA (Inguinal)

- Incidence is 10%.
- If recurrence is within 3 years it is called as *early*; if after 3 years it is *late.*

Predisposing Factors

Preoperative

- Smoking.
- Chronic cough.
- Constipation.
- Old age.
- Anaemia.
- Hypoproteinaemia.
- Straining.
- Increased intra-abdominal pressure of any cause (BPH, carcinoma prostate, stricture urethra).
- Ascites.

Operative

- Tension in the sutures.
- Weak anterior abdominal wall.

Postoperative

- Infection (50%).
- Haematoma formation during earlier surgery.
- Retained sac in pantaloon hernia.
- Straining.

Recurrence Rate

- Bassini's repair—10%.
- Shouldice repair—1%.
- Hernioplasty—1 to 3%.
- Other methods—1 to 5%.

True or false recurrences are the types of recurrence. If hernia occurs in inguinal region after inguinal hernia repair it is called as *true recurrence*. If other groin hernia occurs after inguinal hernia repair like femoral hernia or obturator or other rare types, it is called as *false recurrence*. But presently hernia is classified grossly as groin hernias and so all recurrences are true recurrences.

Clinical Features

- Same as for inguinal hernia. Defect is usually narrow and so more likely to go in for strangulation.
- It can be *medial recurrence* or *lateral recurrence* depending on the location of the sac. Medial recurrence is common as tension in suture line is greatest near the pubic tubercle.

Treatment

- After thorough investigations, the cause of recurrence has to be treated and later *hernioplasty* is done.
- *Laparoscopic (TEP/TAPP) approach* is better for recurrent hernia. In open repair, preperitoneal mesh repair is ideal. In elderly people *Koontz orchidectomy* or cord excision at inguinal canal may be added after proper prior consent.



Fig. 18.50: Recurrent inguinal hernia is 10% common. It is commonly medial recurrence. It is treated by mesh repair.

Femoral hernia is never congenital.

Rerecurrent Hernia

1% common.

Causes

Infection, earlier mesh extrusion, failure of treating the precipitating causes.

Treatment

- The cause is treated and *mesh repair is done*.
- GPRVS (Giant prosthesis reinforcement of the visceral sac) or TEP through laparoscopy is ideal.

HERNIOPLASTY

It is strengthening of posterior inguinal wall in case of indirect hernia or in any large hernia with weak abdominal wall using a supportive material. This allows and supports good fibroblast proliferation which in turn strengthens the weak posterior wall of inguinal canal or abdominal wall.

Material Used

- *Synthetic:* Prolene mesh (white in colour) Dacron mesh, Morlex mesh, Mersilene sheath.
- *Biological:* Tensor fascia lata, temporal fascia and skin. (presently biological materials are not well-accepted as infection is common and its efficacy is not proved).

Prolene mesh is commonly used at present. Nonabsorbable interspersed absorbed mesh (Vipro/Ultrapro) are also used nowadays.

Indications

- Direct hernia.
- Recurrent hernia.
- Re-recurrent hernia.
- Incisional hernia.
- Old age.
- Hernia with weak abdominal muscle tone.
- Sliding hernia.

Complications

- Infection.
- Mesh extrusion.
- Foreign body reaction.
- Mesh *inguinodynia* causing hyperaesthesia and pain along the distribution of ilioinguinal or iliohypogastric nerves.
- Mesh erosion into bladder, bowel or vessels can occur occasionally (rare).

Principle

- Size of the mesh should be bigger than the size of the defect.
- Mesh should be fixed above and below to the conjoint tendon and inguinal ligament or abdominal wall using interrupted, nonabsorbable sutures.
- Absolute haemostasis and control (prevention) of infection is important.

Types of mesh repair

- Onlay repair
- Lichtenstein mesh repair—a type of onlay
- Inlay repair—mesh placed at myopectineal level—*bridging repair*
- Underlay repair—mesh placed at deeper plane usually in preperitoneal space
- Gilbert patch and plug repair/Gilbert's PHS repair (onlay + sublay)
- Nyhus preperitoneal mesh repair
- Kugel groin hernia mesh repair
- Modified Rives preperitoneal mesh repair through inguinal approach
- Stoppa GPRVS repair
- TEP mesh repair
- TAPP mesh repair

Hernioplasty is becoming the prime treatment for inguinal hernia.

Types

Different types are:

- *Onlay mesh* repair by placing mesh in front. It is sutured above to conjoint tendon and below to inguinal ligament using monofilament non absorbable suture material.
- *Lichtenstein tension free onlay mesh repair* (1993) where the cord is encircled with mesh which is often done under local anaesthesia. Suturing of mesh is done similar to onlay mesh repair. It has got less recurrence rate.
- *Nyhus preperitoneal mesh repair:* It is done through *suprainguinal*horizontal incision above the pubic symphysis and internal ring. Preperitoneum is approached through lateral border of the lower part of rectus muscle by making an opening in the posterior rectus sheath. Mesh is placed in the preperitoneal space deep to the cord, conjoint tendon, and transversalis fascia. Below, it is folded deep to the iliopectineal ligament of Cooper and sutured to it using two or three interrupted nonabsorbable sutures. It is sutured to transverse abdominis above and transversalis fascia from deep.
- *Modified Rives preperitoneal mesh repair (Read-Rives)* is preperitoneal mesh repair through *transinguinal approach*. Direct sac is inverted with sutures. For indirect sac a high ligation is done. Here mesh is placed in preperitoneal space, folded and sutured below to iliopectineal ligament, above to the transverse abdominis in deeper plane. Often transversalis fascia opened earlier is sutured back using nonabsorbable suture material in front of the placed mesh.
- *Stoppa's giant prosthesis reinforcement of visceral sac (GPRVS):* It is done in large hernias, hernias in elderly, bilateral hernias, recurrent and rerecurrent hernias, hernia with very lax abdomen, and hernia with collagen diseases like Marfan's syndrome. Horizontal length (size) of the mesh is 2 cm less than distance between two anterosuperior iliac spines and vertical length (size) is distance between the umbilicus and pubic symphysis. Large mesh is placed

between peritoneum and lateral, inferior, anterior abdominal wall which stretches in the lower abdomen and pelvis. It is done through lower midline or Pfannensteil incision. Usually such large mesh is placed without any anchorage.

- *Gilbert mesh repair (patch and plug):* After herniotomy, internal ring is plugged by cone-shaped (umbrella plug) piece of prolene mesh. Later onlay/inlay mesh repair of posterior wall of the inguinal canal is done.
- *Gilbert's PHS (Prolene Hernia System) repair (onlay and sublay—sandwich technique)*: It is an open transinguinal approach to place a specially devised mesh in both preperitoneal as inlay and in front as onlay mesh repair. This mesh has got a rounded deeper part which is placed in preperitoneal space and a modified quadrangular part which is placed as onlay. Both parts are connected through a connecting stiff rounded part in between which steadies the mesh in place preventing its displacement.


Part placed in preperitoneal space as sublay
Connector
Part placed in front as onlay

Fig. 18.51: Gibert's PHS mesh.

- *Transabdominal preperitoneal laparoscopic mesh repair (TAPP repair):* It is mainly used in irreducible and large hernias.
- *Totally extraperitoneal laparoscopic mesh repair (TEP)*—becoming popular.

Transabdominal Preperitoneal Mesh Repair (TAPP) Using Laparoscope

This is used in large indirect hernia or irreducible inguinal hernia. 10 mm umbilical port is used for laparoscope. 5 mm ports are placed one on each side on pararectal point at the or above the level of umbilicus so as to achieve adequate triangulation. Contents of the hernia are reduced. Hernial sac is dissected in preperitoneal plane after making horizontal incision at the upper part of the sac opening. Vas, gonadal vessels, pubic bone, inferior epigastric vessels are identified. Once sac is dissected and excised, a prolene/vipro/ultrapro mesh of 15 × 10 cm sized or smaller is placed in preperitoneal space. It is fixed to pubic bone using tacks. Peritoneum is closed with continuous prolene sutures.



Fig. 18.52: Mesh placement in TAPP procedure.

Totally Extraperitoneal Repair (TEP Repair) Using Laparoscope

- This technique is gaining more popularity than TAPP. Through subumbilical incision (10 mm) extraperitoneal space is reached. After CO_2 insufflation, another 5 mm port is inserted 4 cm below the first port in the midline. Third 5 mm port is inserted in the same line 4 cm below or in the right iliac fossa. Dissection is carried out downwards carefully, then medially up to the pubic tubercle, iliopectineal ligament, laterally to iliac vessels, and inferior epigastric vessels. Once adequate space is dissected 15 × 15 cm mesh is placed and spread. Care should be taken not to have any folding in the mesh. Mesh may be sutured to iliopectineal ligament. Displacement of mesh is not common. Other side also can be done together.

Anatomical Considerations

- Preperitoneal space is a potential space in front of the peritoneum, behind the transversalis fascia and anterior rectus muscle. Below in front of the urinary bladder it is called as *space of Retzius* (medially), laterally it is called as *space of Bogros*. Median umbilical fold is formed by urachus in the midline. Medial umbilical ligament is formed by obliterated umbilical arteries, lateral umbilical fold by inferior epigastric vessels. Three fossae are lying in relation to these folds—supravesical and medial fossae are medial to lateral umbilical fold which are sites of direct hernia whereas

Spigelian line: Runs along the lateral border of rectus sheath and extends from the pubic tubercle to the tip of the 9th costal cartilage.
Spigelian fascia: Is the fascia between the aponeurosis of external and internal oblique, transversus abdominis and recuts sheath.

lateral fossa is lateral to lateral umbilical fold and is site of indirect hernia.

- In 1956 *Fruchaud* described his *myopectineal orifice* bounded medially by the lateral border of rectus abdominis, laterally by iliopsoas, superiorly by conjoint tendon and inferiorly by pectin pubis. This area is the site of groin hernia which should be covered by mesh of adequate size to strengthen the defect and to prevent the recurrence. Iliopubic tract is analogue of the inguinal ligament, extends from Cooper's ligament to anterosuperior iliac spine which divides endoscopic view of preperitoneal space into *superior compartment* (contains inferior epigastric artery, Hesselbach's triangle, cord structures and is site of inguinal hernia) and *inferior compartment* (contains femoral canal, iliac vessels, iliopsoas muscle, genitofemoral nerve, lateral femoral cutaneous nerve). External iliac vessels lie in a triangle formed by gonadal vessels laterally, vas deferens medially and peritoneal reflection inferiorly (*triangle of doom*).


(TAPP)
10 mm port
5 mm (TAPP)
–5 mm (TAPP)
– 10 mm (TEP)
– 5 mm (TEP)
– 5 mm (TEP)

Fig. 18.53: Ports used for TEP and for TAPP.


Skin
Abdominal muscles (external/internal/transverse)
Rectus muscle
Transversalis fascia
Preperitoneal space
Peritoneum
Intestines
Normal anatomy of abdominal wall
Skin
Abdominal muscles (external/internal/transverse)
Rectus muscle
Transversalis fascia
Preperitoneal space
Peritoneum
Intestines
Preperitoneal approach (for TEP)
Skin
Abdominal muscles (external/internal/transverse)
Rectus muscle
Transversalis fascia
Preperitoneal space
Peritoneum
Intestines
Transabdominal preperitoneal approach (TAPP)

Fig. 18.54: Diagrammatic representations of TEP and TAPP.


10 mm camera port
5 mm working port
5 mm working port

Fig. 18.55: Port incisions in TEP.


Direct defect
IEA
Pubic symphysis
Cord
Cooper's ligament

Fig. 18.56: TEP after dissection prior to placement of mesh. Direct defect, inferior epigastric artery, pubic symphysis and Cooper's ligament are clearly seen.


IE vessels
Cooper's ligament
Indirect sac

Fig. 18.57: TEP after dissection showing indirect sac, inferior epigastric vessels, Cooper's ligament.



Fig. 18.58: TEP mesh placement in preperitoneal space.

- Aberrant obturator artery is an occasional branch of inferior epigastric artery replacing its pubic branch travels across Cooper's ligament, which during fixation of mesh can cause torrential haemorrhage—*circle of death*. *Triangle of pain* is formed by gonadal vessels medially, iliopubic tract laterally and peritoneal reflection below. Genitofemoral nerve and lateral cutaneous nerve of thigh traverse this triangle. Injury to these nerves either by dissection or by tacks cause postoperative pain. Tacks/staplers should not be placed in this triangle.

Indications for TEP	***Contraindications for TEP***
• Recurrent hernia • Bilateral hernia • Indirect/direct/femoral hernia	• Obstructed/strangulated inguinal hernias • Ascites • Bleeding disorders

Landmarks to be identified in TEP	***Principles in TEP***
• Pubic bone midline • Inferior epigastric artery • Copper's ligament • Iliopubic tract • Cord and vas deferens • Psoas muscle and nerves in relation	• Head-down supine position • Surgeon standing on opposite side of hernia • Camera person placed on opposite side of hernia • Monitor at foot end • Catheterise/empty the bladder properly prior to TEP • Adequate wide space creation • Careful dissection of cord and sac • Ligate indirect sac • Mesh should not be fixed laterally • Size of mesh is 15 × 15 cm • Two point fixation—one at pubic bone other at Cooper's ligament by tacks/staplers

Difficulties and complications in TEP repair

- Difficulty in dissecting indirect sac. Cord/vas injury
- Inadvertent opening of the sac/peritoneum and creation of pneumoperitoneum.
- Injuries to major structures like iliac vessels—0.5-1.0%
- Displacement of mesh or erosion into structures like urinary bladder—rarely may occur
- Nerve injury
- Formation of seroma/haematoma
- Infection
- Recurrence

Advantages of TEP repair

- Approach is totally extraperitoneal
- Small incision
- Proper placement of mesh in right space that is preperitoneal space
- Peritoneal cavity is intact and not opened

MALGAIGNE BULGING

- It is protrusion of abdominal wall muscles during leg rising test as weak, soft, supple, swelling, which signifies poor abdominal muscle tone. It also concludes that particular hernia requires mesh repair ***(hernioplasty)*** as surgical treatment.
- It is common in old age, obese patient.

INCARCERATED HERNIA

- Here the lumen of the portion of colon occupying a hernial sac is blocked with *faeces*. Here scybalous content of the bowel should be capable of being indented with the finger, like putty.
- In incarcerated hernia, sac and contents are densely adherent to each other (contents are fixed to sac). It is always irreducible; often obstructed but may not be strangulated.

STRANGULATED HERNIA

Pathology

It occurs when blood supply of the contents of hernia is seriously impaired leading to formation of gangrene.

Common bacteria in strangulated hernia

- *E. coli*
- Anaerobic streptococci
- Anaerobic bacteria
- *Klebsiella*

Obstruction
↓
Initially venous return is impaired
↓
Congestion of the bowel
↓
Further dilatation of the bowel which becomes purple coloured
↓
Fluid collects in the sac
↓
Eventually arterial blood supply is impaired
↓
Bowel becomes dark, brownish black coloured with flabby and friable wall
↓
Bacteria migrate transerosally and multiply in fluid of the sac
↓
Perforation occurs at the site of constriction ring
↓
Peritonitis occurs.

- Strangulation commonly occurs in the *small bowel* and also in large bowel. Occasionally strangulated omentocele also can occur without any intestinal obstruction.

Smile is the curve which puts everything straight.

- Strangulation can occur in inguinal, femoral, obturator, umbilical or any hernias.
- Indirect inguinal hernia is more prone for strangulation than direct inguinal hernia. It is due to narrow neck, adhesions, narrow external ring in children.



Fig. 18.59: Picture showing strangulated hernia with toxic fluid and site of constriction.



Fig. 18.60: Strangulated inguinal hernia will be tender and irreducible without impulse on coughing.



Fig. 18.61: Hernia with gangrenous omentum. Note the colour of the gangrenous omentum.

- Part of circumference of the bowel when strangulated, is called as ***Richter's hernia*** wherein the patient presents with diarrhoea, toxicity mimicking *gastroenteritis.* Richter's hernia is more common with femoral, obturator hernias.

Causes of strangulation

- Narrow neck
- Adhesions
- Irreducibility
- Long-time, large hernia with adhesions

Maydl's hernia (Hernia-in-W): Here a loop of bowel in the form of 'W' lies in the hernial sac and the centre portion of the 'W' loop is strangulated and lies within the abdominal cavity**.** Thus local tenderness over the hernia is not marked and hernia gets reduced with the strangulated loop in the centre of the ***"W"***. Strangulation in this case is often missed during surgery and may lead to peritonitis due to retained gangrenous loop.



Fig. 18.62: Maydl's hernia (Hernia-in-W).

Clinical Features of Strangulated Hernia

- Sudden severe pain, initially over a pre-existing hernia which later becomes generalised over the abdomen.
- Persistent vomiting, constipation and distension of the abdomen.
- *Hernia is tense, severely tender, irreducible and without any expansile impulse on coughing. Rebound tenderness is diagnostic.*
- Features of toxicity and dehydration.
- Electrolyte imbalance.
- Abdominal distension with guarding and rigidity.
- Oliguria.
- 3% in incidence.

Features of strangulated hernia

- Tense, tender, irreducible
- No impulse on coughing
- Shock, toxicity
- Features of obstruction when there is enterocele
- Abdominal distension, vomiting
- Rebound tenderness

Strangulation during infancy

Incidence is 4%. Female to male ratio is 5:1

In female infants, the content may be ovary with or without fallopian tube

Taxis

- Often in irreducible hernia, *reduction* of hernia is *tried* by elevation, sedation and ***taxis*** (i.e. with flexion and medial rotation of the hip, reduction of hernia is tried).
- *In obstructed hernia, taxis may be dangerous* as during taxis, contusion and rupture of the intestinal wall can occur. Reduction-en-masse may mask the gangrenous bowel existing in the sac. Inner gangrenous loop of Maydl's hernia may be missed. Rupture of the sac extraperitoneally is also a possibility.
- *Taxis has no role in femoral hernia and strangulated hernia.* If tried, contusion, reduction-en-masse and rupture of the sac can occur.

Taxis

- Used in irreducible or partially reducible hernia
- *Trial reduction by flexing and medially rotating the hip*
- It is dangerous in:
  - Obstructed hernia
  - Maydl's hernia

  (As rupture can occur leading to peritonitis)
- No role in femoral and strangulated hernia



Fig. 18.63: In an obstructed hernia, if reduction is forced it may get reduced with the sac and ring with the obstructed/strangulated bowel—*Reduction-en-masse*.

- ***In strangulated omentum*** features of obstruction are not present (i.e. vomiting, constipation). Omentum becomes congested, oedematous and black in colour which secretes toxic fluid with secondary bacterial infection. But here, initially the sepsis is slower than that of strangulated intestinal obstruction.
- Eventually the infection spreads causing diffuse peritonitis. Downward spread of infection can cause scrotal abscess.

Investigations

- Plain X-ray abdomen in erect posture shows multiple air-fluid levels.
- Serum electrolytes.
- Blood urea and serum creatinine.
- Total count is increased.
- U/S abdomen.

Strangulation without obstruction

- Richter's hernia
- Omentocele

Treatment of Strangulated Hernia

- The patient is admitted.
- Ryle's tube aspiration.
- Intravenous fluids to correct dehydration and electrolyte imbalance.
- Antibiotics.
- Catheterisation to maintain adequate urine output.
- *Emergency surgery*:



Fig. 18.64: Incision for strangulated hernia is obliquely placed extending to the scrotum.

Groin incision is made with incision extending into the most prominent area of the swelling.

↓

Sac is exposed.

↓

Constriction ring and superficial ring is released (cut).

↓

Sac is opened carefully *without allowing the spillage of fluid* (Usually spillage occurs extraperitoneally)

↓

Fluid is sucked with a suction apparatus.

↓

The bowel is held with fingers so as to prevent it from getting reduced.

↓

The viability of the bowel is checked by *colour, peristalsis, pulsation, bleeding*.

↓

When gangrenous, resection and anastomosis is done and drain is placed.

The most important thing that you wear is the expression on your face.



Figs 18.65A to D



Figs 18.65E and F

Figs 18.65A to F: Strangulated hernia—left side. It is tense, tender, without any impulse on coughing. Note the incision, discoloured sac, content (gangrenous bowel) and proximal viable bowel.

Bassini's repair is done by placing interrupted non-absorbable sutures. Antibiotics, IV fluids are continued. Drain is removed in 4-5 days. Once the bowel movement begins, oral diet is started (in 5 days).

Postoperative Problems

Infection, leak with fistula, septicaemia.

Note:

During surgery for strangulated hernia mesh is usually not used, only repair is done. Biological mesh can be used during the surgery for strangulated hernia.

SLIDING HERNIA (HERNIA-EN-GLISSADE)

- Here posterior wall of the sac is not only formed by the parietal peritoneum, but also by sigmoid colon with its mesentery on left side; caecum on right side and often with portion of the bladder (Both sides) (1:2000).
- Rarely small bowel sliding hernia or sacless sliding hernia can occur (1:8000).
- Content of the sac is usually small bowel or omentum.
- *Sliding hernia occurs exclusively in males. Mainly on the left side* (85%).
- It commonly occurs in *indirect sac* even though femoral and direct sliding hernias are known to occur.
- Bilaterality is extremely rare.
- It is seen commonly in adults and elderly.
- Huge hernia can occur which extends into the scrotum and do not get reduced totally.



Fig. 18.66: Sliding hernia with urinary bladder as posterior wall of the sac.

Clinical Features (2%)

Large globular swelling in the inguinal region descending into the scrotum, often irreducible.



Fig. 18.67: Sliding hernia (*Hernia-en-Glissade*).

Small bowel as the content of sliding hernia can lead to strangulation.

Treatment: *Always Surgery*

- *Posterior wall of the sac should not be separated from large bowel or bladder*. If tried, injury may result to these organs leading to faecal or urinary fistulas.
- Partially excised sac is pushed into the peritoneal cavity with posterior wall and repair is done usually using *prolene mesh* (Hernioplasty).
- In *LaRoque repair* deep ring is incised above and below; reefing of the sigmoid colon mesentery is done which forms the posterior wall of the inguinal canal so that entire sigmoid is replaced into the peritoneal cavity. Posterior wall of the sac should not be separated from large bowel or bladder. If tried it may lead into faecal or urinary fistulas. Often sac can be excised partially; this partially excised sac can be pushed into peritoneal cavity. Right sided sliding hernia will have caecum and appendix in its posterior wall; caecum should not be separated from posterior wall of the sac which may otherwise create faecal fistula. Appendix should not be removed as it may precipitate sepsis. Appendices epiploicae from sigmoid colon should not be removed as there are chances that they may contain small colonic diverticula which may get opened to contaminate the field. Bladder will be present on medial side of the sac and sac should not be separated; if bladder injury occurs it should be sutured in two layers with vicryl. Inside out purse string suture on the opened sac is applied and the sac with its posterior wall is pushed into the abdominal cavity. Urinary catheterisation is a must.
- Truss should not be used in sliding hernia.

PANTALOON HERNIA (DOUBLE HERNIA, SADDLE HERNIA, ROMBERG HERNIA)

- Here both direct and indirect inguinal sacs are present and clinically present *as direct hernia.*
- During surgery, indirect sac may be missed and so leads to *recurrent hernia* through retained (or unidentified) indirect sac.
- Here both medial and lateral sacs *straddle* the inferior epigastric artery.
- It is one of the causes for recurrent hernia.



Fig. 18.68: *Saddle/Pantaloon* hernia. It is on either side of the inferior epigastric artery having both direct and indirect sacs.

INFANTILE HERNIA

- Clinically difficult to diagnose.
- Often it is diagnosed on table.
- Processus vaginalis is closed at internal ring and hernial sac either invaginates processus vaginalis as “inverted umbrella’ or comes behind processus vaginalis.

FEMORAL HERNIA

Surgical Anatomy of Femoral Canal

It is the medial, most compartment of the femoral sheath, which extends from femoral ring above to saphenous opening below. It contains fat, lymphatics, lymph node of Cloquet. It is 1.25 cm long and 1.25 cm wide at the base. Below it is closed by cribriform fascia.

Femoral ring is bounded anteriorly by inguinal ligament; posteriorly by iliopectineal ligament of Cooper, pubic bone and fascia covering the pectineus muscle; medially by concave, sharp lacunar (Gimbernat's) ligament; laterally by a thin septum separating from femoral vein.



Fig. 18.69: Surgical anatomy of femoral hernia.



Fig. 18.70: Femoral triangle.



Fig. 18.71: Hernia; inguinal hernia is above and medial to tubercle, and femoral hernia is below and lateral.

Aetiology

- Wide femoral canal.
- Multiple pregnancies.

Pathology in Femoral Hernia

Through femoral canal, hernial sac descends down vertically up to saphenous opening and then escapes out into the loose areolar tissue to expand out like a ***retort.*** Because of its irregular pathway and narrow neck, it is more prone for obstruction and strangulation. During surgery, precaution should be taken about the femoral vein and pubic branch of obturator artery (or accessory obturator artery) which often may get injured leading to torrential haemorrhage.

Clinical Features

- Common in females (2:1 ratio), common in multipara.
- Rare before puberty. 20% occurs bilateral, however, more common on right side.
- Presents as a swelling in the groin *below and lateral* to the pubic tubercle (Inguinal hernia is *above and medial* to the pubic tubercle).
- Swelling, impulse on coughing, reducibility, gurgling sound during reduction, dragging pain, are the usual features.
- When obstruction and strangulation occurs which is more common, presents with features of intestinal obstruction—painful, tender, inflamed, irreducible swelling without any impulse. They also present with abdominal distension, vomiting and features of toxicity.
- Often femoral hernia can be associated with inguinal hernia also.
- 40% of femoral hernias present as emergency hernia with obstruction/strangulation.

Gaur's sign: In femoral hernia, distension of superficial epigastric and/or circumflex iliac veins occurs due to the pressure by the hernial sac.

Differential diagnosis

- Inguinal hernia
- An enlarged Cloquet lymph node of any cause
- Psoas abscess—psoas spasm with flexed hip but difficulty in extension
- Lipoma
- Femoral aneurysm
- Distended psoas bursa (Disappears on hip flexion)
- *Saphena varix*—it is enlarged terminal portion of long saphenous vein. It is soft, disappears on lying down, fluid thrill, impulse on coughing and venous hum on auscultation are present. There is associated varicose veins on leg
- Haematoma in the region

Hydrocele of femoral hernia occurs when adherent omentum which is the content secretes fluid into the sac.

Herniation through a gap in the lacunar ligament (medial) is always strangulated and is called as *Laugier's femoral hernia (L for L).*

In congenital dislocation of hip, femoral hernia occurs *behind* the femoral vessels—*Narath's femoral hernia.*

If sac lies under the pectineal fascia, is called as *Cloquet's hernia.*

Strangulation and Richter's hernia are *common* in femoral hernia.

Often on medial side, a portion of bladder forms the wall of the femoral hernial sac—*sliding—femoral hernia*.

- Femoral hernia—occurs medial to femoral vein
- Narath's hernia—occurs behind femoral artery, in congenital dislocation of hip
- Hesselbach's hernia—occurs lateral to femoral artery
- Serofini's hernia—occurs behind femoral vessels
- Laugier's hernia—through lacunar ligament
- Teale's hernia—in front femoral vessels
- Callison-Cloquet hernia—through pectineal fascia
- Cooper's hernia—femoral hernia with two sacs



Fig. 18.72: Femoral hernia on right side. Note the location below the inguinal ligament. Femoral hernia is common on right side. It is common in females.


Inguinal hernia
Inguinal hernia
Femoral hernia

Fig. 18.73: Right side femoral hernia in a male patient. Patient is also having bilateral inguinal hernia. Femoral hernia is rare in males.



Fig. 18.74: Right side femoral hernia in a female patient. Femoral hernia is common in females. In females the most common hernia is inguinal hernia.

Treatment

Approaches


Mc'Evedy-high
Lotheissen-inguinal
Lockwood-low
4
3
2
1
5
6
1. Femoral hernia
2. Femoral vein
3. Femoral artery
4. Femoral nerve
5. Lacunar ligament
6. Cooper's ligament

Fig. 18.75: Different surgical approaches for femoral hernia.


Lacunar ligament
Inguinal ligament
Repair
FN
FA
FV
Cooper's ligament

Fig. 18.76: Femoral hernia repair. Inguinal ligament is approximated to Cooper's (Iliopectineal line) ligament. In Lotheissen's repair conjoined tendon is sutured to iliopectineal line.

Love means sharing the same road, wherever it leads.

1. ***Lockwood-low operation***: Here sac is approached below the inguinal ligament through groin crease incision (or over the swelling) so that fundus of sac is dissected by direct vision and repair is done from below.
   Here inguinal ligament is sutured to Cooper's ligament. standard and ideal (Cooper's ligament repair).
2. ***Mc'Evedy-high operation:*** A incision is made over the femoral canal extending vertically above the inguinal ligament. Sac is dissected from below, neck from above and repair is done from above. It gives a very good exposure of both neck, fundus of sac and repair is also easier. It is done in strangulated femoral hernia.
3. ***Lotheissen's operation***: It is through inguinal canal approach (like for inguinal hernia). Transversalis fascia is opened and neck of the sac is identified in the femoral ring. Sac is dissected from above, neck is ligated and repair is done.
   Lotheissen's repair: After herniotomy, *conjoined tendon is sutured to iliopectineal line* (ligament) by interrupted sutures (2 or 3), using nonabsorbable monofilament sutures. Care should be taken to avoid injury to femoral vein, pubic branch of obturator artery, bladder. It is not as strong as Cooper's ligament repair.
   Complications: Bleeding haematoma, abscess formation.
4. ***AK Henry's approach***: Repair of bilateral femoral hernia through lower abdominal incision.
5. Polypropylene mesh can be buttressed over the femoral canal to close the defect.
6. Laparoscopic mesh repair—TEP/TAPP.

VENTRAL HERNIA

Any protrusion through abdominal wall with the exception of hernia through the inguinofemoral region is defined as *ventral hernia*. Incisional hernia (80%) and primary defects in abdominal fascia which can cause umbilical hernia, epigastric hernia, paraumbilical hernia or Spigelian hernia are grouped under ventral hernia.

Ventral hernia can be:

- Reducible.
- Irreducible.
- Obstructed.
- Strangulated.
- Single.
- Multiple small defects (*Swiss cheese hernia*).



Fig. 18.77A



Fig. 18.77B

Figs 18.77A and B: Large ventral hernias. It needs proper mesh repair.



Fig. 18.78: CT scan showing ventral hernia which is irreducible.

Causes
- Congenital defect.
- Obesity.
- Smoking.
- Chronic cough.

Preoperative preparation
- Proper skin hygiene.
- Respiratory care.
- Control of obesity.
- Antibiotics.

Management
- Relevant investigations
- Open mesh repair—inlay; onlay; sublay—retrorectus; underlay.

- Laparoscopic mesh placement—underlay (directly in front of the contents) using dual mesh or four layered mesh.



Fig. 18.79: Ventral hernias with Swiss cheese multiple defects.



Fig. 18.80: Port placement for laparoscopic ventral hernia repair. Left subcostal point is *Palmer point*.



Fig. 18.81: Laparoscopic view of ventral hernia with omentum as irreducible content. Content is released and duval or four-layered mesh is fixed with tackers or sutures.

INCISIONAL HERNIA

- It is herniation through a weak abdominal scar (scar of previous surgery).
- It is common in old age and obese individuals.
- It occurs in 10% of abdominal surgeries; 70% occurs in first 5 years; 30% occurs in 5-10 years.



Fig. 18.82: Incisional hernia adherent to skin. Note the ulceration over the summit. Patient underwent resection and anastomosis with removal of the ulcerated skin with mesh placement.

Additional History to be Collected in Incisional Hernia

- Details of surgery that patient has undergone earlier. Duration after how long incisional hernia has occurred is important.
- History of wound infection, wound dehiscence, whether surgery done was an emergency or elective, and tension sutures placed or not.
- History of pain, irreducibility and details of precipitating factors to be asked.
- Other precipitating factors are similar to inguinal hernia like smoking, urinary/respiratory/abdominal symptoms.

Predisposing Factors

- Vertical scar, midline scar, lower abdominal scar—may injure the nerves of the abdominal muscles.
- Scar of major surgeries (biliary, pancreatic).
- Scar of emergency surgeries (peritonitis, acute abdomen).
- Faulty technique of closure.
- Poor nutritional status of the patient.
- Presence of cough, tuberculosis, jaundice, anaemia, hypoproteinaemia.
- Malignancy, immunosuppression.
- Smoking in postoperative period.
- Causes which increases the intra-abdominal pressure (BPH, straining, stricture urethra or rectum, ascites).

Factors responsible for development of incisional hernia

- Vertical incision has got higher chances of incisional hernia than horizontal incision
- Layered closure of the abdomen has got higher chance than single layer

A friend is your second identity.

- Continuous closure has got higher chances than interrupted closure
- Using absorbable suture material has got higher chances of hernia than nonabsorbable sutures
- Emergency surgical wound has higher chances than elective surgical wound
- Laparotomy for peritonitis, acute abdomen, and trauma can commonly cause incisional hernia
- Drainage through the main laparotomy wound may precipitate formation of incisional hernia
- Chronic cough, smoking, obstructive uropathy, constipation can precipitate incisional hernia
- Diabetes, old age, malnutrition, malignancy, anaemia, hypoproteinaemia, jaundice, ascites, liver disease, uraemia, steroid therapy, immunosuppressive diseases are other precipitating factors

Clinical Features

- Swelling in the scar region.
- Pain.
- Impulse on coughing.
- Gurgling sound.
- Often bowel peristalsis may be visible under the skin.
- Eventually features of irreducibility, obstruction, strangulation is seen.



Figs 18.83A and B



Fig. 18.83C

Figs 18.83A to C: Incisional hernia in a patient during straining and during relaxing.



Fig. 18.84: Incisional hernia which is irreducible with visible bowel beneath.

Defect is felt and assessed during head rising, by placing fingers over the scar horizontally
Size of the defect is very important

- Hernia is common in lower abdomen.
- It may be *small or large; huge or massive (diffuse).*
- Scar, its extent and location, whether healed primarily or secondarily, skin over the scar and swelling is noted. Details of the swelling with expansile impulse on coughing and *examination both in lying down and standing are done.*
- *Gap cannot be assessed in an irreducible hernia.*

Type of defects in incisional hernia

- Small defect < 2 cm
- Large and wide defect > 2 cm
- Very large defect
- Massive/diffuse
- Multiple defects—*Swiss cheese pattern*

***Note*:**
- Size of the defect is important to decide the type of surgical closure in incisional hernia.
- Midline hernia expels the content more outwards due to contraction of rectus muscles on both sides.

Investigations: Always the precipitating factors must be looked for:
- Chest X-ray.
- U/S abdomen.
- Tests relevant for causes.

Complications of incisional hernia: Irreducibility, obstruction, strangulation, incarceration



Fig. 18.85: CT scan abdomen showing incisional hernia.

Preoperative Preparations for Incisional Hernia Surgery

- Reduction in weight and control of obesity.
- Nutrition, control of anaemia.
- Treatment for diabetes, hypertension, cardiac diseases, respiratory problems.
- Treating the precipitating causes.
- Chest X-ray, U/ S abdomen to be done.
- Massive incisional hernia after reduction might cause IVC compression, paralytic ileus and diaphragmatic elevation with respiratory embarrassment (*abdominal compartment syndrome*). It is prevented by prior increasing the capacity of peritoneal cavity by creating pneumoperitoneum using CO_2 so as to increase the peritoneal pressure by 12-15 cm of H_2O, daily for 3-6 weeks. Later definitive surgery is done.

Treatment Strategy for Incisional Hernia

- **Mesh repair of the incisional hernia** defect is always better and ideal with less chances of recurrence.
  - Adequate sized mesh is placed either outer to peritoneum *(sublay*), or outer to musculoaponeurotic abdominal layer *(onlay/overlay*), or occasionally combined sublay and onlay mesh placement, both deep and outer to musculoaponeurotic layer.
  - *Rive's Stoppa's mesh placement* for incisional hernia is placing mesh between posterior rectus sheath and rectus muscle—**retrorectus mesh placement** is easier for dissection and mesh placement.
  - Commonly polypropylene mesh is used. Other materials used are Dacron, polytetrafluoroethylene (PTFE) mesh, polyglycolic mesh (vicryl mesh) or combined polypropylene and polyglycolic acid mesh (vipro mesh). Drain (suction drain) must be placed after surgery.
  - Mesh repair is ideal approach for incisional hernia. Prevention of infection/haemostasis and drainage are important.
- **Laparoscopic mesh repair is done for incisional hernia** by placing a mesh under the defect laparoscopically in intraperitoneal plane. The only problem of this underlay placement is chances of adhesion and GI fistula formation, but still it is found to be safer. Laparoscopic preperitoneal mesh placement is also done for smaller defects. Now dual mesh (PTFE) or four layered mesh are available. Here mesh is placed under the peritoneum deep to the defect after reducing the contents. Mesh is fixed with sutures and tacks. In four-layered mesh, deepest 1st layer is absorbable cellulose which allows new peritoneum to creep underneath. 2nd layer is PDS/PTFE mesh 3rd layer is polypropylene mesh and the last 4th layer is again PDS/PTFE mesh. It is ideal but costly.
- **Cattell's operation**: When the defect is less than 3 cm, and if the patient is having adequate abdominal muscle tone, *layer by layer anatomical repair* is done using monofilament nonabsorbable suture material like *polypropylene/ polyethylene,* ideally with interrupted sutures. Sac should be dissected, ligated and excised prior to repair. Peritoneum and posterior rectus sheath is apposed as first layer and anterior rectus sheath as second layer.
- **Double breasting of the rectus sheath** using interrupted nonabsorbable sutures using monofilament suture material. It is overlapping the rectus sheath in two layers with two rows of sutures.
- **Keel operation** is done in large defect. Scar is excised and is dissected beyond the margin of the defect. Sac is never opened unless there is obstruction of the content. Sac in inverted using continuous/interrupted inverting nonabsorbable sutures, layer by layer until the defect margins are apposed together which is then again sutured with interrupted sutures. Keel is inverted beam of the ship.



Figs 18.86A and B: On table incisional hernia defect also showing mesh placement in retrorectus plane.

- **Nuttall's operation** is done for lower midline incisional hernia. Recti attachments are detached from the pubic bones and are crossed over to fix to opposite pubic bones so as to create a firm abdominal wall support by crossed recti muscles.



Figs 18.87A and B: (A) Keel operation and (B) Nuttall's operation.

Different Types of Mesh Repair for Incisional Hernia

- *Outer to peritoneum is ideal method (sublay):* Large sized mesh is placed in preperitoneum. It need not be fixed as abdominal pressure keeps it in position (according to Pascal's law).
- *Under the peritoneum, directly over the content (underlay):* Now it is accepted but there are chances of adhesions/fistula formation. It is used in laparoscopic repair. Dual mesh/four-layered mesh is used.
- *Overlay* mesh placed outer to musculoaponeurotic layer. Here mesh is placed under subcutaneous tissue; it carries high recurrence rate (30%). So it is *not recommended.*
- *Combined inlay and overlay* with two layers of mesh.
- *Rive's Stoppa's method* of placing mesh between posterior rectus sheath and rectus muscle widely. Dissection is done at least 10 cm beyond the defect under rectus muscle in front of the posterior rectus sheath; mesh should cover 5 cm beyond the defect all around. Recurrence rate with this is less than 10%.
- *Components separation technique* is better method in large defects. Here skin and subcutaneous fat are dissected of the anterior rectus sheath → external oblique is incised 2 cm lateral to rectus abdominis → external oblique is separated from internal oblique until posterior axillary line → additional relaxing incisions are made over rectus sheath, internal oblique, transverse abdominis → it is repeated on opposite side → 20 cm mobilisation is achieved → also reinforced with a large mesh. Component separation technique causes often lateral bulges on both sides. If it is done without mesh support recurrence rate is high. Advantage is defect up to 20 cm can be easily brought together. Technique is also called as *Autologenous repair by vascularised innervated muscle flaps) (Ramirez, 1990)*.

- *Bridging at myoaponeurotic level outer to peritoneum (inlay):* Adequate sized mesh is placed in the defect level bridging the gap to cover preperitoneum. It is better by principle but still shows high recurrence.

Surgeries for incisional hernia

- Mesh repair—commonly done and ideal
- Component separation technique
- Layer by layer closure—Cattell's operation
- Double breasting of the rectus sheath
- Keel operation—not commonly used now
- Nuttall's operation—not commonly used now

Postoperative Care

- Antibiotics.
- Analgesics.
- Nasogastric aspiration.
- Abdominal binder for support.
- Prevention of paralytic ileus.
- Control of obesity and other precipitating factors.
- Stop smoking and treat other associated causes.
- Early ambulation.
- Fluid management, catheterisation.
- Drain should be kept until drainage becomes minimal.
- Abdominal binder is used to support abdominal wall during recovery period.

Complications of incisional hernia surgery are:

- Wound infection, seroma formation
- Paralytic ileus, abdominal compartment syndrome in large hernias
- Wound sinus, enterocutaneous fistula
- Infection of the mesh, recurrence

Additional Problems in Large Incisional Hernia

- While reducing the bulky contents like bowel and omentum, inadequate intra-abdominal capacity leads to increased intra-abdominal pressure causing IVC compression, mesenteric oedema followed by stasis of splanchnic bed, paralytic ileus, diaphragmatic elevation and respiratory distress (*abdominal compartment syndrome*), urinary and bowel disturbances. Abdominal capacity can be raised by creating regular pneumoperitoneum over the period of 3-6 weeks.
- Lordosis and back pain may be presenting feature.
- Sac and contents may get adherent to the thin skin over the summit of the hernia leading to skin ulceration and occasionally fistula formation.
- Often might need resection of the adherent bowel segment.
- Large mesh placement is required.

Note:

- *It is now universally accepted that prosthetic repair is gold standard for all incisional hernia.* Prostheses used are polypropylene mesh, e PTFE, Dacron, dual intraperitoneal mesh, biologic grafts.
- Nonprosthetic repair has got only historical value as recurrence rate is very high (as high as 55%).

UMBILICAL HERNIA

Anatomy of Umbilical Region

Umbilical ring is a complex structure which is related to linea alba, falciform ligament, obliterated urachus (median umbilical ligament) and umbilical fascia (*Richet's fascia)*. It is located at the level of L_4 and L_5 vertebral disc. It is at lower position in infants. It is water shed area for venous and lymphatic drainage—above umbilicus it drains to axillary vein or lymphatics; below to inguinal area. Umbilical skin is supplied by T_{10} spinal cord. It is the meeting point of four folds of embryonic plate and three systems—GI (vitellointestinal), urinary (urachus), and vascular (umbilical vessels). Umbilical hernia develops due to either absence of umbilical fascia or incomplete closure of umbilical defect. Weakest part in the umbilical cicatrix is upper part where hernia begins.

- Umbilical hernia can be **congenital** in newborn and infants (common in males) or **acquired** in adults (common in females). Congenital umbilical hernia is *common* in Africa or in African origin people (8 times). Acquired is like any ventral hernia.
- It is herniation through a weak umbilical scar (cicatrix).
- It is common in infants and children, occurs commonly due to neonatal sepsis.
- Male : female :: 2:1.
- It is seen in 20% of newborn infants.
- Umbilical hernia is common in Down's syndrome, *Beckwith-Weidman syndrome*.

Clinical Features

- Presents with a swelling in the umbilical region within first few months after birth, the size increases during crying. It is hemispherical in shape.
- Defect can be felt with finger during crying.
- Occasionally it can go for irreducibility and obstruction which presents with pain, distension, vomiting.



Fig. 18.88: Umbilical hernia.



Figs 18.89A and B: Umbilical hernia. Often it can attain large size.

Treatment

Initially conservative. In 93 to 95% of cases, it disappear spontaneously in few months after birth (masterly inactivity). It can be hastened by adhesive strapping across the abdomen.



Fig. 18.90: Incision for umbilical hernia.

Indications for Surgery

- If persists even after the age of two years.
- If the defect is more than 2 cm in size.
- Acquired/adult umbilical hernia.

Different surgeries are:

Primary closure of the defect:

An infraumbilical incision is made encircling its lower half. Sac is dissected circumferentially and is released off from the umbilicus and subcutaneous tissue. Sac is opened; contents are reduced; excess part is excised up to the umbilical ring. Defect is closed with interrupted nonabsorbable polypropylene sutures.

Mayo's operation:

Here horizontally opened rectus sheath is approximated as double breasting with upper flap overlapping lower flap in front. It is rarely done today.

Sublay mesh repair:

In a large umbilical hernia (> 3 cm size defect) with a degenerated skin on its surface it is often difficult to retain the umbilicus. When umbilicus is tried to be saved, infraumbilical incision should extend laterally about 2 cm on each side at 3 and 9 o'clock positions. Sac is dissected similarly. Sac is excised after excision of redundant sac. Presently it is standard to use polypropylene mesh as sublay or in retrorectus position and then rectus sheath is closed.

Umbilectomy:

Unhealthy thin skin over the large umbilical hernia is a real problem. It is better to do umbilectomy in these patients (excision of umbilical cicatrix). It is done only in adult with large umbilical hernia with thinning of umbilical skin. Prior consent and eventual creation of umbilicus is needed.

Open dual PTFE and polypropylene mesh placement:

Umbilical hernia is dissected similarly through subumbilical incision. Redundant sac is excised. Peritoneum is not closed. A special composite mesh containing wider PTFE on the inner side with little smaller polypropylene mesh on the outer aspect is used. It has also got two additional straps of the mesh attached to the outer part of the main composite mesh which are used to hold and later to fix into the defect anteriorly. This has got excellent results with low recurrence rate.

Laparoscopic umbilical hernia repair:

It is similar like any ventral hernia repair through laparoscopy which is done under general anaesthesia. It is useful only in large umbilical hernia.



Fig. 18.91: Umbilical hernia. It needs surgical intervention.



Fig. 18.92: Umbilical hernia dual mesh to place both intraperitoneally and retrorectus plane with straps to fix.

PARAUMBILICAL HERNIA (Supra- and Infraumbilical Hernia)

- It occurs commonly in adults. It is a protrusion or herniation through linea alba, just above or below the umbilicus.
- It enlarges ovally, often attains a large size and sags downwards.



Figs 18.93A and B: Large ventral hernia front and side views. It needs preperitoneal mesh repair.

- Neck of the sac is relatively narrow. Contents are usually omentum, small bowel, sometimes large bowel.
- It has got tendency to go for adhesion, irreducibility and obstruction.

Predisposing factors

- Obesity
- Multiple pregnancies
- Flabby abdominal wall

Clinical Features

- Common in females (5:1 ratio).
- It presents as a swelling which has smooth surface, distinct edges, soft, resonant with dragging pain and impulse on coughing. Large hernias can present with intestinal colic due to subacute intestinal obstruction. Eventually strangulation can occur.

Treatment

Is always surgery

- Dissection of hernial sac and placement of mesh in retrorectus plane and under the umbilicus is the ideal treatment.
- Often *umbilectomy* is required and also *mesh placement is beneficial* (when defect is > 4 cm in size).
- If there is strangulation, resection of bowel segment and anastomosis is done followed by repair of the hernia.
- ***Mayo's operation*:** Through a transverse elliptical incision, sac is identified and dissected. Herniotomy is done. *Double breasting of the defect* in the rectus is done by interrupted nonabsorbable sutures.
- Additional lipectomy (panniculectomy) may be done in case of pendulous abdomen.
- Postoperative weight reduction, use of abdominal binder is required for these patients.

Mayo's operation

- It is done for umbilical and paraumbilical hernia
- Once lower flap or umbilicus is raised above, sac is identified, dissected and opened
- After reducing the contents sac is transfixed using vicryl
- Rectus sheath is repaired with double breasting using nonabsorbable sutures between superior and inferior fascial margins as 'vest on pant' imbrications
- Skin flap is closed with a drain. Infection, recurrences (30%) are known complications
- It is not commonly used now

EPIGASTRIC HERNIA (Fatty Hernia of Linea Alba)

- It is 10% common; common in males.
- 20% of epigastric hernias are multiple—Swiss *cheese like*.
- It occurs usually through a defect in the decussation of the fibres of linea alba, any where between xiphoid process and umbilicus.
- Extraperitoneal fat protrudes through the defect as fatty hernia of the linea alba presenting like a swelling in the upper midline with an impulse on coughing.
- *It is sacless hernia*. Later protrusion enlarges and drags a pouch of peritoneum, presenting as a *true epigastric hernia*.
- If the defect is less than 1.5 cm, lateral margin of the defect is formed by only anterior and posterior lamina of the rectus sheath; if the defect is > 1.5 cm, then lateral margin is also formed by rectus muscle.
- Content of true epigastric hernia is usually omentum, sometimes it may be small bowel.
- Common in muscular men; manual labourers.



Fig. 18.94: Epigastric hernia.

We do not remember days, we remember moments.



Fig. 18.95: Epigastric hernia with *Swiss cheese defects*.



Fig. 18.96: Epigastric hernia. Note the location of epigastric hernia above the umbilicus. Initially it is sacless but later sac with content develops.



Fig. 18.97: Epigastric hernia showing features of strangulation.

Clinical Features

- *Often asymptomatic.*
- Swelling in the epigastric region which is tender.
- Pain in epigastric region. It is often associated with peptic ulcer and so pain may be due to peptic ulcer. So gastroscopy is done to rule out acid peptic disease.
- Impulse on coughing; defect in the epigastric region are also found.
- Irreducibility, obstruction, strangulation as seen in any other hernia can also occur in epigastric hernia.

Treatment

- Through a vertical incision, sac is dealt with. Defect is closed with nonabsorbable interrupted sutures.
- Large defect is supported with preperitoneal mesh.
- Complete reconstruction of linea alba is needed from xiphisternum to umbilicus especially in *Swiss cheese* type using different methods like—interrupted primary closure using polypropylene sutures; *modified shoelace technique* is used after removing strip of medial margins of the linea alba; double breasting of the linea alba.



Figs 18.98A and B



Figs 18.98C and D

Figs 18.98A to D: Epigastric hernia—incision, sac and defect.

Interparietal hernias/interstitial hernias

- Herniation through parietal peritoneum into various layers of the abdominal wall
- Common in Down's syndrome, Prune Belly syndrome
- Often it can attain large size
- May mimic abdominal wall lipoma; haematoma
- As neck of the sac is often narrow, can present with irreducibility or obstruction
- Commonly it is deep to external oblique aponeurosis
- *Types:*
  - Preperitoneal—between peritoneum and transversus abdominis muscle—20%
  - Interparietal/intermuscular—between external oblique and internal oblique; most common—60%. It is commonly associated with inguinal hernia
  - Extraparietal (inguinosuperficial)—herniates through external oblique aponeurosis into subcutaneous plane—20%
- U/S; X-ray abdomen; often CT confirms the diagnosis
- Through a transverse incision, surgical ligation of sac, repair or mesh placement is the treatment

SPIGELIAN HERNIA

- It is a type of interparietal hernia occurring at the level of arcuate line through spigelian point. Hernial sac lies either deep to the internal oblique or between external and internal oblique muscles.
- It is lateral ventral hernia through *Spigelian fascia* at any point along its line. *Semilunar line of Spigel* is a line from pubic tubercle to tip of 9th costal cartilage. It marks the lateral margin of the rectus sheath. Semicircular arcuate line (fold) of Douglas is lower end of posterior lamina of rectus sheath below the umbilicus and above the pubis. Spigelian fascia is area between lateral border of the rectus muscle and external and internal oblique and transversus abdominis muscle.
- Spigelian hernia can occur above (10%) or below (90%) the umbilicus. Below the umbilicus it occurs at the junction of linea semilunaris and linea semicircularis (wider and weaker point). In Spigelian hernia, defect is formed by internal oblique and transversus abdominis muscle. External oblique is outer to the hernial sac.

Clinical Features

- Presents as a soft, reducible mass lateral to the rectus muscle and below the umbilicus, with impulse on coughing. Strangulation is common in spigelian hernia.
- Presence of precipitating factors like obesity, chronic cough, old age, multiple pregnancies.
- Common in females after 50 years of age.

Differential Diagnosis

- Abdominal wall lipoma.
- Soft tissue sarcoma.
- Abdominal wall haematoma.



Fig. 18.99: Spigelian hernia.

Investigation

- Ultrasound abdomen.

The wind of anger blows out the lamp of intelligence.

Treatment

- Through a lengthy transverse incision herniotomy and later closure of the defect layer by layer using nonabsorbable interrupted sutures.
- But *ideally* mesh is required to cover the defect properly.
- Laparoscopic dual mesh placement is also useful.



Figs 18.100A and B: Spigelian hernia. On table finding and placement of mesh in same patient.

OBTURATOR HERNIA

- It is hernia occurring through obturator canal between superior ramus of pubis and obturator membrane. It is a rare entity, seen in elderly females (6::1 ratio female to male).

Clinical Features

- Usually presents with features of intestinal obstruction (85%) and more often confirmed only on laparotomy.
- Rarely seen as a swelling in Scarpa's triangle (20%) deep to the pectineus muscle, with limb in flexed and abducted position. Movement of limb is painful.
- Referred pain in knee joint through geniculate branch of obturator nerve signifies not only obturator hernia but also strangulation—*Howship-Romberg sign* (50%).
- On per vaginal examination, tender swelling is felt over the obturator foramen.
- Here strangulation is usually of Richter's type.

Treatment

- Laparotomy is done and the sac is identified. It is dissected and ligated. If strangulation is present (common), resection and anastomosis is done. Broad ligament is stitched over the opening to prevent recurrence.
- Mesh placement is the ideal way of repairing the obturator defect.
- *In nonobstructive type,* if diagnosed clinically and by CT scan imaging, either TEP (laparoscopic) or lower abdominal midline extraperitoneal approach may be the method to manage the obturator hernia.
- In strangulated hernia, rarely additional exposure in thigh often may be required to reduce the content through a vertical medial pectineus muscle split incision.



Fig. 18.101: Obturator hernia through obturator canal in obturator foramen. Note also the locations of inguinal and femoral hernias.

RICHTER'S HERNIA

It is a hernia in which the sac contains only a portion of the circumference of the intestine (small bowel). It is usually *seen in femoral and obturator hernia.*

Clinical Features

- It *mimics gastroenteritis* with pain abdomen, diarrhoea, toxicity, vomiting.
- There are no features of intestinal obstruction.
- Constipation does not occur in Richter's hernia.
- Gangrene (strangulation) of a part of bowel occurs, eventually leading to peritonitis.



Fig. 18.102: Strangulated femoral hernia, Richter's type with perforation. Patient underwent resection and anastomosis.



Fig. 18.103: Richter's hernia.

Treatment

- Resection and anastomosis is done.
- The type of hernia is treated.
- Mortality increases with delay in surgical intervention.

LUMBAR HERNIA

- It is herniation either through superior or inferior lumbar triangle.
- Superior lumbar triangle *(Grynfelt's/Lesgaft's triangle)* is bounded by sacrospinalis, 12th rib and posterior border of internal oblique.
- Inferior lumbar triangle is bounded by latissimus dorsi, external oblique and iliac crest *(triangle of Petit)*.
- Lumbar hernia is more common through superior lumbar triangle.
- It can be:
  - **Primary.**
  - **Secondary,** which is due to previous renal surgery, more common.



Fig. 18.104: Lumbar triangles.

Differential Diagnosis

- Lipoma.
- Cold abscess.
- Lumbar phantom hernia.

Treatment

Repair using fascial flaps or mesh.

PHANTOM HERNIA

- It is a muscular bulge as a result of local muscular paralysis due to interference with nerve supply of the affected muscles, like poliomyelitis. It is common in lumbar region. It is often seen in lower abdomen.

Phantom hernia is muscular bulge due muscle paralysis in lumbar region
Phantom limb is feeling of pain in amputated toe or limb
Phantom tumour is tumour like lesion in lung like interlobar pleural effusion



Fig. 18.105: Lumbar incisional hernia—large. Previous lumbar incision scar is visible.

SCIATIC HERNIA

- It is a rare hernia.
- It is the protrusion of the peritoneal sac through the greater or lesser sciatic foramen.

Types

Classified based on their relationship to the pyriformis muscle and ischial spine.

1. Suprapyriformis.
2. Infrapyriformis.
3. Subpyriformis.

Sac lies deep to gluteus maximus. Large hernias protrude below the buttock crease.

Diagnosis

Usually on laparotomy for intestinal obstruction.

Treatment

Defect is covered by fascia mobilised from pyriformis muscle after reducing the sac contents.

COMPLICATIONS OF HERNIA SURGERY

Proper idea of complications of hernia surgery are important as often complications may become more problematic than hernia itself. 20 years back where tissue repair was popular recurrence was the most worried complication. Now since recurrence rates have come down due to standard usage of mesh, mesh related complications have become more common than recurrence. Inguinodynia, mesh extrusion, mesh infection, mesh erosion are the worried problems.

• Complications of open hernia surgery	• Early
• Complications of TEP/TAPP	• Delayed
• Complications of other hernia surgery—ventral/femoral	• Late • Life-threatening

Complications of open hernia surgery	*Complications of TEP/TAPP*
• Infection • Groin pain; ostetitis pubis • Ischaemic orchitis—due thrombosis of pampiniform venous plexus (0.5%) • Injury to vas • Injury to viscera • Recurrence • Hydrocele formation • Seroma, haematoma • *Inguinodynia*—neural • *Dysejaculation*—painful, burning sensation just before/during/after ejaculation due to cremaster dysfunction or vas stricture (0.25%)	• SC emphysema • Pneumothorax, hypercarbia • Vascular • Neural • Visceral • Infection, ileus • Conversion • Recurrence

Immediate	*Late/delayed*
• Vascular—injury to iliac vessels/IE vessels • Visceral injury—bowel/bladder • Vas injury • Anaesthetic complications	• Seroma/haematoma • Neural complications • Intestinal obstruction • Bowel adhesion/ fistula • Testicular atrophy • Mesh related complications • Recurrence

Inguinodynia

- It is chronic inguinal pain seen in post-hernia surgery patients (30%)—whether tissue or mesh repair.
- *Causes are*—traction, cautery, transection, entrapment. Even though it can occur in both tissue and mesh repair, it is more observed in mesh repair especially in onlay mesh repair. It is due to entrapment of nerve in the suture or in the mesh itself or nerve gets adherent to the mesh during fibrosis (perineural fibrosis) (*Mesh inguinodynia*).
- It may be transient or persistent.
- Nerves involved are—iliohypogastric, ilioinguinal, genital branch of genitofemoral nerve, paravasal nerves.
- *Features are*—distressing pain in the groin which often radiates to thigh, scrotum and loin. Arch and twist mobility of pelvis reproduce the pain. Bupivacaine injection relieves the pain. Imaging/nerve conduction studies are of no use.
- Open method has higher (32-38%) incidence of inguinodynia than TAPP/TEP. In open hernia surgery inguinodynia has replaced recurrence as a primary complication. It is distressing discomfort to both patient and surgeon. Incidence is less in posterior or laparoscopic approach.
- It is treated with analgesics/nerve block (Injection of steroid, local anaesthetic agents, phenol, and alcohol)/transcutaneous stimulation/cryotherapy/radiofrequency therapy/ neurectomy.
- Neurectomy is done via groin or suprainguinal or laparoscopic or laparotomy approach. Commonly groin approach is used. Ilioinguinal, iliohypogastric and genitofemoral nerves are carefully dissected. Nerve which is causing the problem is transected at a point where it comes out of the internal oblique muscle and proximal end should be ligated, otherwise end neuroma may form to cause recurrence of the pain. This ligated stump is buried in the internal oblique muscle. Just neurolysis may be sufficient but chances of re-adhesion are higher with recurrence of symptoms. In difficult cases nerve may be transected through laparotomy/ laparoscopy approach.

PARASTOMAL HERNIA

- It is herniation of intestine on the side of bowel stoma—ileostomy/colostomy/other stomas.
- Incidence is 8%.
- *Classification (Devlin's)*: (1) Subcutaneous—intestine herniates along the side of stoma to reach subcutaneous plane—most common. (2) Interstitial—along the side of stoma intestine herniates into intermuscular plane. (3) Intras-

tomal—bowel herniates between emerging and everted parts of the stoma. (4) Perstomal—herniation occurs between the layers of the prolapsed stoma.

- *Features:* Pain, features of obstruction, stomal malfunction, swelling which is tender, toxicity.
- *Diagnosis*: X ray; CT abdomen.
- *Treatment*: Surgery is indicated in recurrent obstruction, narrow neck, strangulation, interference with stoma.
  - Stoma is dissected, hernia content is reduced and defect is repaired. But it shows high recurrence.
  - Subcutaneous mesh repair as onlay placement after reduction of hernia.
  - Extraperitoneal mesh repair around the stoma.
  - Intraperitoneal mesh repair deep to peritoneum surrounding the stoma and defect.

DIFFERENT TYPES OF HERNIA

1. Gibbon's hernia—It is hernia with hydrocoele.
2. Berger's hernia—Hernia in pouch of Douglas.
3. Romberg hernia—Saddle hernia.
4. Obturator hernia—Hernia through obturator foramen (canal).
5. Grynfelt's hernia—Upper lumbar triangle hernia.
6. Petit's hernia—Lower lumbar triangle hernia.
7. Femoral hernia—Hernia medial to femoral vein.
8. Cloquet's hernia—Hernia through pectineal fascia.
9. Narath's hernia—Behind femoral artery, in congenital dislocation of hip.
10. Hesselbach's hernia—Lateral to femoral artery.
11. Serofini's hernia—Behind femoral vessels.
12. Laugier's hernia—Through lacunar ligament.
13. Teale's hernia—In front of femoral vessels.
14. Richter's hernia—Part of circumference of bowel wall is gangrenous.
15. Littre's hernia—Hernia with Meckel's diverticulum as the content.
16. Sliding hernia—Posterior wall of the sac is formed by colon or bladder.
17. Maydl's hernia—'W' hernia.
18. Phantom hernia—Localised muscle bulge following muscular paralysis.
19. Spigelian hernia—Hernia through spigelian fascia.
20. Mery's hernia—Perineal hernia.
21. Sciatic hernia—Hernia through greater or lesser sciatic foramen.
22. Little's hernia—Appendix in hernial sac.
23. Beclard's hernia—Femoral hernia through the saphenous opening.
24. Barth's hernia—Hernia between abdominal wall and persistent vitellointestinal duct.
25. Holthouse's hernia—Inguinal hernia that has turned outwards into the groin.

Chapter 19 Oesophagus

CHAPTER OUTLINE

- Anatomy
- Lower Oesophageal Sphincter
- Dysphagia
- Contrast Study of Oesophagus
- Oesophagoscopy
- Oesophageal Endosonography
- Gastro-oesophageal Reflux Disease
- Hiatus Hernia
- Rolling Hernia
- Reflux Oesophagitis
- Barrett's Oesophagus
- Barrett's Ulcer
- Oesophageal Motility Disorders
- Achalasia Cardia
- Plummer-Vinson Syndrome
- Corrosive Stricture of Oesophagus
- Schatzki's Rings
- Boerhaave's Syndrome
- Mallory-Weiss Syndrome
- Tracheo-oesophageal Fistula
- Oesophageal Diverticulum
- Carcinoma Oesophagus
- Benign Tumours of the Oesophagus
- Oesophageal Perforation
- Foreign Body Oesophagus

ANATOMY

Oesophagus is a hollow muscular tube which begins at the lower edge of the cricoid cartilage (C_6 vertebra) and ends at oesophagogastric junction (T_{12} vertebra). It is 25 cm in length. Upper end is closed by cricopharyngeus muscle which is 18 cm from upper incisors. Lower end is 40 cm from the upper incisors (Upper jaw is fixed and so is used as the landmark to measure, but not the lower jaw which is mobile).

It lies anterior to vertebral column and posterior to the trachea. It lacks serosal layer but is surrounded by a layer of loose fibroareolar adventitia.

Anatomical specialities

- Lacks serosa (other structure without serosa is rectum).
- Contains 2 different types of muscles (striated and smooth at proximal 1/3 and distal 2/3 respectively)
- Contains 2 different types of epithelium.
- Segmental blood supply.
- Only part of GIT which shows *very thinly scattered* Meissner's plexus.
- Longitudinal arrangement of veins and lymphatics.

It is lined by squamous epithelium throughout the length except the last 3 cm (OG junction) which is lined by columnar epithelium. Submucosa of the oesophagus is thick and strongest part.

Parts

1. ***Cervical oesophagus:*** It extends from cricopharyngeus which is the horizontal part of inferior constrictor muscle. Upper oblique part is called as thyropharyngeus. Gap between the two is called as *Killian's dehiscence* which is a *site of occurrence of pharyngeal pouch*. Cervical oesophagus is related to trachea and recurrent laryngeal nerve.
2. ***Thoracic oesophagus:*** Lies initially towards the right side. In lower third it deviates towards the left and continues as abdominal oesophagus. It is related to azygos vein, thoracic duct (which crosses the oesophagus posteriorly from right to left), aorta, pleura and pericardium.
3. ***Abdominal oesophagus*** is 2.5 cm long and grooves behind the left lobe of the liver.

Three areas of anatomic narrowing

- Cervical constriction—occurs at the level of cricopharyngeal sphincter—*narrowest point of GIT*—15 cm from upper incisor—site of F/B impaction
- Bronchoaortic constriction—located at the level of T_4 – 25 cm from upper incisor—site of endoscopic perforation
- Diaphragmatic constriction—occurs where oesophagus traverses the diaphragm (Level of T_{10})—40 cm from upper incisor

Arterial supply of oesophagus

By inferior thyroid artery, oesophageal branches of the aorta, gastric arteries and inferior phrenic arteries.

Venous drainage of oesophagus

By inferior thyroid vein, brachiocephalic vein, left hemiazygos vein, azygos vein, coronary vein, splenic vein and inferior phrenic vein. Veins are longitudinal and they lie in submucosal plane in lower third and in muscular plane above.


Oesophagus
Trachea
Thoracic duct
Right pulmonary artery
Aorta
Right bronchus
Left pulmonary artery
Left bronchus
Pulmonary trunk
Heart border
Diaphragm
Crus
Stomach

Fig. 19.1: Anatomical relations of the oesophagus.

Lymphatic drainage

Lymphatic arrangement in oesophagus is longitudinal and so spread of carcinoma to distant lymph nodes occurs early. Longitudinal lymphatics are 6 times more than transverse one There are *more lymph vessels* in submucosa than blood vessels. Lymph nodes are:

- *Paraoesophageal groups* located in the wall of the oesophagus and are cervical, thoracic, paraoesophageal and paracardial nodes.
- *Perioesophageal groups* located immediately adjacent to oesophageal wall. They are deep cervical, scalene, paratracheal, mediastinal, diaphragmatic, gastric and coeliac lymph nodes.
- *Lateral oesophageal groups* receive lymph from para and perioesophageal lymph nodes.


Descending artery
Clavicle
Horizontal artery
Ascending artery
A
SVC
Azygos vein
Oesophageal venous plexus
Left gastric vein
Portal vein
Splenic vein
B

Figs 19.2A and B: (A) Arterial supply and (B) Venous drainage of oesophagus.

- Upper oesophagus drains into supraclavicular nodes.
- Thoracic oesophagus drains into paraoesophageal and tracheobronchial nodes in thorax.
- Abdominal oesophagus drains into coeliac nodes.
- However due to longitudinal arrangement of lymphatic plexus in the wall of oesophagus, any group of (neck/thorax/coeliac) lymph nodes can get involved in diseases at any level.


1. Cervical group
2. Lateral cervical group
3. Deep cervical group
4. Upper thoracic group
5. Paratracheal group
6. Subcarinal group
7. Hilar group
8. Middle thoracic group
9. Lower thoracic group
10. Posterior mediastinal (para-aortic) group
11. Diphragmatic group
12. Paracardial group
13. Lesser curvature group
14. Coeliac left gastric group
15. Common hepatic group
16. Greater curvature group
17. Suprapyloric group
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17

Fig. 19.3: Lymphatic drainage of the oesophagus.

Nerve Supply

- Oesophagus is innervated by vagus.
- It has got both sympathetic and parasympathetic innervation.
- It has got mainly *Auerbach's plexus* between longitudinal and circular muscle layers.

Leugart's pouch is prolapse of the wall of the oesophagus like a diverticulum over a band *(Leugart's band)* between the left bronchus and adjacent vertebra.

Physiology

Three types of contractions in the oesophagus:

1. *Primary:* Progressive, triggered by swallowing.
2. *Secondary:* Progressive, generated by distension or irritation.
3. *Tertiary:* Nonprogressive.

Presbyoesophagus is less efficient oesophageal peristalsis.

LOWER OESOPHAGEAL SPHINCTER (LOS)

- It is a high physiological pressure zone located in the lower end of the oesophagus in terminal 4 cm, with a resting pressure of 10-25 mmHg.
- LOS prevents reflux of gastric and duodenal contents.
- It is influenced by food, gastric distension, gastric pathology, smoking, GI hormones, alcohol.

- Normally there is a *transient relaxation period* wherein reflux (*physiological*) occurs but then immediately gets cleared by oesophageal clearance mechanism.
- So *pathological reflux or GORD* can occur due to decreased LOS tone, altered relaxation time, reduced oesophageal clearance mechanism, or other altered mechanical factors.
- *Oesophageal clearance mechanism* is due to primary oesophageal peristalsis which carries saliva with high bicarbonate content which neutralizes and clears the transient physiological reflux. Manometry with special microtransducers are used to measure the LOS pressure.

DYSPHAGIA

- *Dysphagia* is difficulty in swallowing. Painful swallowing is *odynophagia*.
- It can be *acute*—due to foreign body impaction or acute infection or *chronic* due to causes like stricture or carcinoma, etc.
- Associated hoarseness of voice may be present in advanced pharyngeal or post cricoid carcinomas. At late stage laryngeal carcinoma also can cause dysphagia along with hoarseness of voice.
- Dysphagia can be *oropharyngeal* or *oesophageal* depending on the cause.
- Dysphagia may be due to pathology in *voluntary/pharyngeal phase* of the swallowing wherein patient also develops cough while swallowing. Dysphagia due to problem in *oesophageal involuntary phase* of swallowing is specified by food getting stuck in the pathway. But site of "*food getting stuck*" feeling is not relevant.
- Dysphagia can be *progressive or intermittent*.

Causes of Dysphagia

Common causes:

- Gastro oesophageal reflux diseases (GORD/GERD/Hiatus hernia).
- *Carcinoma oesophagus*: Here dysphagia is of short duration and progressive. 2/3 of the lumen should be blocked by tumour to develop dysphagia.
- *Foreign body in oesophagus*: It may be coin/bone piece/denture. It is common in children. It causes acute dysphagia. It may be often life threatening.
- Carcinoma of pharynx or posterior 1/3rd of the tongue.
- *Corrosive strictures*: It is usually alkali stricture. Squamous mucosa is resistant to acid effect to certain extent.
- *Oesophageal candidial infection*: It is becoming common due to immunosuppression in association with HIV infection; steroid therapy; cancer chemotherapy; post-transplant period, etc. Presentation is dysphagia and odynophagia. Oral candidiasis (thrush) is obvious. Endoscopy shows whitish curd-like plaques in the oesophageal mucosa which cannot be moved (whereas food particles can be moved). Barium swallow shows mucosal ulceration and irregular areas. Biopsy confirms the diagnosis. Treatment is oral antifungal as well as topical antifungal therapy.



Figs 19.4A and B: Endoscopic view of oesophageal candidiasis infection. Note the whitish curd-like plaques.

- Plummer-Vinson syndrome.
- Mediastinal swellings—primary tumours/nodal mass either lymphoma or secondaries or tuberculosis.

Rare causes:

- *Diffuse oesophageal spasm*: They are incoordinated contractions of oesophagus causing chest pain or dysphagia. It is common in distal 2/3rd of the oesophagus. Hypertrophy of circular muscle fibres with very high persistent pressure of 400-500 mmHg is specific. Treatment is calcium channel

Causes of dysphagia

Extraluminal causes	*Causes in the wall of oesophagus or other area*	*Causes in the lumen*
• Mediastinal nodes—secondaries/lymphoma/tuberculosis • Aortic aneurysm • Rolling hiatus hernia • Thyroid enlargement—malignant • Dysphagia lusoria • Congenital anomalies • Mediastinitis/mass	• Carcinoma oesophagus • Corrosive/tuberculous/inflammatory/congenital stricture oesophagus • GERD • Achalasia cardia • Plummer-Vinson syndrome • Oesophageal diverticulum • Carcinoma posterior 1/3rd of tongue/pharynx • Diffuse oesophageal spasm • Congenital anomalies • Retropharyngeal abscess/peritonsillar abscess (Quinsy)/acute tonsillitis/pharyngitis	• Foreign body in the oesophagus—coin/dentures/fish or meat bone *Other causes* Cranial causes (neurological): • Bulbar palsy/infarction/hemiplegia • Vertebro basilar insufficiency

blockers, vasodilators, endoscopic dilatation and extended oesophageal surgical myotomy up to the aortic arch (very useful especially for dysphagia; not much for chest pain).

- Oesophageal diverticula, Chaga's disease.
- *Dysphagia lusoria (Lusoria means in Latin "sport of nature"):* It is a congenital vascular anomaly of aortic root. *Aortic arch anomalies* are—double arch (40%), right arch and left ligamentum arteriosum (25%), anomalous innominate or common carotid artery or aberrant right subclavian artery (10%). It is due to disappearance of proximal right 4th aortic arch instead of distal portion. All patients having this anomaly (*dysphagia lusoria*) have got an *aberrant right subclavian artery* in a transposed position arising from descending aorta that courses posterior to oesophagus. Often there will be a complete *vascular ring* around trachea and oesophagus. It is categorised based on their specific subclavian anomaly—depends on presence of aneurysm, occlusive disease and compression. Commonly they are asymptomatic. Presentations may be dysphagia, chest pain, stridor, wheeze, recurrent respiratory infection (usually presents after the age of 40).
  Investigations: CT chest, MRI, chest X-ray, barium swallow (T4 level diagonal impression) and endoscopy (Shows pulsating extraluminal compressive mass).
  Treatment is reconstruction or ligation of aberrant right subclavian artery by sternotomy/by neck approach.
- *Thyroid swelling*: It is uncommon to develop dysphagia in a thyroid swelling. There will be always dyspnoea when dysphasia develops. Large malignant thyroid or anaplastic thyroid can cause dysphagia with dyspnoea or stridor.
- *Boerhaave's syndrome*: It is vertical full thickness tear of lower oesophagus due to vomiting with closed glottis. It is often life threatening and emergency.
- Neurological causes like stroke, bulbar palsy, motor neuron disease, Parkinson's disease, etc.
- Congenital anomalies of oesophagus.
- *Drug induced dysphagia*: Drugs like KCl, quinine, NSAID can cause dysphagia.
- Mediastinal fibrosis.

Evaluation of a Patient with Dysphagia

- Proper history.
- Haematocrit.
- Chest X-ray often shows mediastinal mass lesion/ foreign body.
- *Oesophagoscopy*: Once lesion is detected, it is treated accordingly. Biopsy from lesions, endotherapy if needed should be carried out (like F/B removal; stricture dilatation; sclerotherapy).
- Barium swallow may show irregular filling defect or extrinsic compression.
- CT scan chest is very useful method to identify the anatomical location of the cause (nodes/tumour/aorta/cardiac cause/ congenital). Extent, spread, nodal status, size and operability of tumour also well-assessed.
- Oesophageal manometry in achalasia cardia/GERD.
- 24 hours pH monitoring is ideal and most accurate for GERD. Small pH probe (transnasal catheter) is passed into the distal oesophagus 5 cm proximal to upper margin of LOS under manometry guidance. Probe is connected to a digital recorder worn by the patient for 24 hours. Record is analysed using a computer. A pH less than 4 for more than 4% of total 24 hours period (more than near to one hour in toto in 24 hours) is pathological reflux. It is often assessed by scoring system. Radio-telemetry pH probes are used now without any nasal tube. It is passed and placed on the oesophageal wall using endoscope.
- Endosonography is very useful in many conditions causing dysphagia. It can assess site, layers of the oesophagus, nodes, spread, etc. properly. Different layers are seen as alternating hyperechoic and hypoechoic bands.
- Ultrasound abdomen to see abdominal nodes/liver/ascites.
- MRI study.

Treatment for Dysphagia

Depends on cause—modified Heller's myotomy; oesophageal resection; dilatation; F/B removal, etc.

CONTRAST STUDY OF OESOPHAGUS

Types

1. Barium swallow using barium sulphate (thick paste).
2. Using water soluble contrast like 'Gastrografin'.



Figs 19.5A and B: Barium swallow X-rays showing narrowing and irregularity in carcinoma oesophagus.

Indications

1. *Barium swallow*
   - Dysphagia due to motility disorder like achalasia cardia, diffuse oesophageal spasm.
   - Dysphagia due to mechanical causes like carcinoma, benign strictures and neoplasms, external compression.
   - Pharyngeal pouch and other diverticula.
   - GORD.

Instrumentation is the most common cause of oesophageal rupture.

2. *Water soluble contrast radiograph*
   - In suspected oesophageal perforation.
   - Leaking oesophageal anastomosis.

Important Findings in Barium Swallow

- Achalasia cardia—*'Bird beak'* appearance, as the oesophagus is grossly dilated above an apparent narrowing at the cardia. In long standing cases—'sigmoid oesophagus'.
- Diffuse oesophageal spasm—*Corkscrew* appearance.
- GORD—shows reflux when done in Trendelenburg's position.
- Oesophageal carcinoma—irregular stenosing lesion with shouldering (*'Rat tail'* is a fluoroscopic finding).
- Pharyngeal pouch—demonstration of the pouch.
- External compression—indentation of barium column by superior or posterior mediastinal mass, enlarged left atria as in mitral stenosis.

OESOPHAGOSCOPY

Indications

Diagnostic

- To identify the lesion and to take biopsy in carcinoma oesophagus.
- For diagnosing other oesophageal conditions.

Therapeutic

- To remove foreign body
- To dilate stricture
- To place endostents for inoperable carcinoma oesophagus
- To inject sclerosants for varices



Fig. 19.6: Oesophageal candidiasis—note the multiple curd-like lesions.

Types

1. ***Rigid oesophagoscope (Negus type)***
   - It is done under general anaesthesia. Head is extended and head end of the table is tilted upwards, scope is passed behind the epiglottis and cricoid through the cricopharyngeal opening. This is the most difficult part in oesophagoscopy. After that, negotiating through the oesophagus is easier. The lesion is identified and biopsy is taken if required.
   - *Complications* are perforation (most common site of perforation is at the level of cricopharyngeus), bleeding.
2. ***Fibreoptic flexible oesophagoscope***
   - It can be done under local anaesthesia. Reflux and hiatus are well identified. Stomach also can be visualised. Easy to pass and perforation is unlikely.
   - But tissue taken for biopsy is smaller and removal of foreign body is also difficult.

OESOPHAGEAL ENDOSONOGRAPHY

- It is useful method of finding and assessing involvement or pathology of different layers of oesophagus especially in carcinoma oesophagus. It shows all layers clearly and distinctly and so invasion can be better made out and operability can be decided.
- **Endoscopic oesophageal staining** using labelled iodine is used to identify early carcinoma in oesophagus. Normal mucosal cells contain glycogen which takes up iodine and so stains brown, whereas carcinoma cells will not take up iodine and so mucosa appears pale (not stained).

GASTRO-OESOPHAGEAL REFLUX DISEASE (GORD/GERD)

- It is a pathological reflux from the stomach into the lower oesophagus.
- It accounts for 75% of oesophageal pathology (most common).
- Symptoms may be due to peptic oesophagitis, LOS dysfunction, aspiration due to reflux, due to late effects like stricture and obstruction.
- It is due to varied *anatomical and physiological factors.*

Anatomical Factors

- Obesity.
- Altered length of intra-abdominal oesophagus. Level of acid exposure is inversely related to length of the intraabdominal oesophagus. More the length more the need of intraabdominal pressure to cause the reflux and so less the reflux with more length.
- Alteration of phreno-oesophageal ligament.
- Altered obliquity of O-G junction (alteration in angle of *'His'*).
- Reduced pinching action (*Pinch-Cock effect*) of right crus of diaphragm.
- Alteration in normal mucosal rosette at O-G junction.
- Alteration in *sling mechanism* of gastric musculature.

Physiological Factors

- Reduced LOS pressure. Normal resting LOS pressure is 10-25 mmHg. During swallowing pressure drops to 1-3 mmHg for few seconds (10 seconds). Resting pressure is increased by gastrin, cholinergic, adrenergic, prokinetic drugs; decreased by secretin, cholecystokinin, glucagon, calcium channel blockers, deriphylline, coffee, fatty meal.

- Altered transient relaxation period in LOS.
- *Reduced oesophageal clearance* mechanism. Change in oesophageal clearance is due to *altered oesophageal body pump* (primary peristalsis with 30-80 mmHg amplitude propagative downwards waves; secondary by food bolus), *altered salivary bicarbonate* neutralizing mechanism of reflux acid, *altered mucosal defense* mechanism (mucous and surface active phospholipid).
- *Delayed gastric emptying* due to diabetes, neuromuscular block, gastroparesis, medications.
- *Increased gastric distension* and gastric acid hypersecretion.

Other Factors

- Alcohol, smoking, stress, lifestyle.
- It is seen in infants and children and also in pregnant women.

Pathogenesis

GERD begins from *distended fundus* due to variety of causes and other anatomical and physiological factors, repetitively unfolding the sphincter to the gastric juice leading to all problems. There is reduced and low LES resistance causing loss of barrier to reflux. It is probably due to gastric distension, delayed gastric emptying, and raised intragastric or intraabdominal pressure. Gastric distension may be due to overeating or aerophagia. Fundic distension → stretching of fundus → LOS squamous epithelium exposed to acid gastric juice → oesophagitis → increased stimulus to swallow saliva to neutralise oesophagitis → further fundal distension → cycle repeats → sphincter is taken into stretched fundus → effects like erosion, ulceration, fibrosis, mucosal metaplasia.

Types

Classification I

- *Symptomatic uncomplicated GORD* (NERD—*Nonerosive Reflux Disease*).
- *Symptomatic, complicated GORD***.**

Classification II

- *Primary*: Incompetent LOS.
- *Secondary*: Due to surgery/disease.

Classification III

- *GORD with sliding hernia.*
- *GORD without sliding hernia.*

Clinical Features

- Fatty dyspepsia.
- Chest pain and heart-burn **(pyrosis)**—80%—main symptom. Pain is more in lying down position and at night. It may mimic cardiac pain/angina. It often begins in the epigastrium and becomes substernal.
- Odynophagia (painful swallowing).
- Appearance of symptoms within seconds of ingestion of food is typical.
- Regurgitation—50%. It is return of oesophageal content.
- Laryngeal symptoms.
- Dysphagia will occur once complications begin.
- Symptoms are more with change of position.
- Chronic cough, shortness of breath and hoarseness—Nocturnal reflux—reflux is return of gastric content.
- Haematemesis.
- Postprandial fullness, choking, wheezing, recurrent pneumonia are other features.

Triad

- Heart burn
- Epigastric pain with dysphagia
- Regurgitation

Typical Symptoms

Heart burn, regurgitation, dysphagia mainly; odynophagia, haematemesis often.

Atypical Symptoms

Cough, hoarseness, wheezing, sore throat, noncardiac chest pain and palatal/dental erosions. It will eventually lead into recurrent pneumonia and pulmonary fibrosis. If pH of the cervical oesophagus is below 4, for less than 1% of time, then respiratory symptoms are due to GERD.

De Meester's scoring system

Grade	*Features*
	Heart burn
0	None
1	Minimal—occasional episodes
2	Moderate—medical therapy visits
3	Severe—interferes daily activities
	Regurgitation
0	None
1	Minimal—occasional episodes
2	Moderate—on position and straining
3	Severe—features of aspiration
	Dysphagia
0	None
1	Minimal—occasional episodes
2	Needs fluid to clear
3	Causes food impaction

Complications

- Reflux oesophagitis.
- Sliding hiatus hernia.

Reflux is precipitated by flexion of the trunk—Boot lacing sign.

- Stricture lower end oesophagus.
- Oesophageal shortening.
- Barrett's oesophagus.
- Carcinoma (adeno) oesophagus (10% of GERD).

Oesophageal	*Extraoesophageal*
• Oesophagitis • Stricture • Barrett's oesophagus • Oesophageal shortening • Carcinoma (adeno)	• Laryngitis • Recurrent pneumonia • Progressive pulmonary fibrosis

Investigations

- Barium study in head down position.
- Endoscopy to exclude other disease and to assess any mucosal injury—red inflamed mucosa often with ulceration. Sliding hernia can be identified through endoscopy. When patient retches, gastric mucosa will enter the OG junction and ascends upwards to variable distance.
- Mucosal biopsy to confirm metaplastic transformation.
- Oesophageal manometry to assess the function of LES. Length and pressure of LOS is important. Transient relaxation period which is increased is most important.
- 24 hours oesophageal pH monitoring—*gold standard*. PPI should be stopped for 3 weeks prior to pH monitoring.



Figs 19.7A to D: Gastro-oesophageal reflux disease (GORD) endoscopic views.

- ***Bernstein test:*** Instillation of 1:10 HCl into stomach of patient with reflux will reproduce the symptoms; and pH in the lower end of the oesophagus decreases. Later pain disappears with saline infusion.
- Dual probe pH monitoring (one in distal oesophagus and one in proximal oesophagus/trachea) is used to confirm the respiratory complications of GORD.
- *DeMeester scoring system* is used to assess the severity of the GORD.
- 99Tc sulphur colloid mixed with saline scan to study OG reflux and 99Tc HIDA scan to study and detect duodenogastric reflux are used.

Differential Diagnosis

- Achalasia cardia.
- Carcinoma oesophagus.
- Peptic ulcer.
- Gallstones.
- Pancreatic diseases.
- Gastritis.
- Cardiac angina.

Treatment of Uncomplicated GORD

A. ***General measure—Life-style changes***
- Control of obesity.
- Stop smoking and alcohol.
- Avoid tea, coffee and chocolate.
- Propped up position.
- Small frequent meals.

B. ***Drugs***
- **H_2 antagonists; antacids.**
- **Proton pump inhibitors (PPIs)—very effective**
  - Omeprazole 20 mg—BD for 3-6 months.
  - Lansoprazole 30 mg.
  - Pantoprazole 40 mg.
  - Esomeprazole 20 mg.
  - Rabeprazole 20 mg.
- **Prokinetic drugs**
  - Metoclopramide, Domperidone 30 mg.
  - Cisapride, Mosapride.
  - Itopride 50 mg—does not cause cardiac arrhythmias.
  - **Defoaming** semethicone, alginic acid along with antacids.
  - **Anticholinergic drugs**—pirenzipine.
  - **Mucosal protector drugs**—sucralfate, colloid bismuth.

C. ***Endoluminal therapies for GORD***
- Endoluminal *suturing* (Wilson-Cook)
- *Plexiglass microspheres* (PMMA). Microsphere suspended in gelatin is injected through endoscopic needle. Gelatin gets absorbed and spheres cause a tissue bulking
- *Gatekeeper reflux* repair system. Endoscopic delivery of preformed radiopaque hydrogel into submucosa
- *Stretta catheter*. Flexible, soft, 6 mm sized, 65 cm length tube with balloon/basket and 5.5 mm NITI electrode, irrigation and suction
- *Enteryx* injection technique (estrinyl vinyl alcohol)
- *Endocinch* technique
- Endoscopic full thickness *plication.*

D. ***Surgery***

- *Indications for surgical treatment*
  - Failure of drug treatment
  - Sliding hernia
  - Barrett's ulcer
  - Severe pain
  - Presence of complications like bleeding/stricture/shortening, respiratory problems

Surgeries

Principles of antireflux surgeries

- ❖ Operation should restore the LES pressure twice the resting gastric pressure
- ❖ The adequate length of the intraabdominal oesophagus should be maintained
- ❖ Apposition of diaphragmatic crurae, reduction of hiatus hernia when present
- ❖ Repaired OG junction should relax during swallowing adequately
- ❖ Tension free fundoplication should be done

Antireflux surgery is the only effective long-term beneficial therapy ideally available and considered now. *Laparoscopic fundoplication* (most popular), Collis-Nissen vertical gastroplasty and fundoplication, resection of OG junction when metaplasia is present, Belsey Mark 4 operation (technically difficult) are the procedures used now.

Fundoplication

- ♦ *Nissen's posterior total fundoplication:* Here after narrowing the crus of diaphragm, mobilised *posterior part of the fundus* of the stomach is wrapped totally 360° around the area of OG junction.
  - *Rudolph Nissen* (1959) first did total fundoplication.
  - Opening the peritoneum over the oesophagus to mobilise the lower end of oesophagus.
  - Dissection of the diaphragmatic crura of the oesophagus.
  - Mobilisation of entire fundus by ligating short gastric vessels.
  - Vagi are preserved.
  - In Nissen's, 60 French bougie wrap is ideal; after complete mobilisation, only *posterior part of the fundus* is wrapped around after crural repair (otherwise fundoplication may displace into thorax causing paraoesophageal hernia); intraabdominal length of 2 cm oesophagus is created (not more); fundus of the stomach is known to relax in concert with oesophageal sphincter so only fundus should be used to buttress the sphincter; wrapping should be done only around sphincter oesophagus not around body of stomach; fundoplication should be kept in abdomen without under tension and without displacing into thorax. Nonabsorbable polypropylene sutures are used.
  - Crural repair is done using interrupted polypropylene sutures.
  - Fundoplication should prevent sphincter shortening/unfolding during gastric distension, should preserve normal swallowing ability, allow proper belching and allow vomiting whenever needed.
  - Bougie; on table and postoperative manometry to assess the pressure of new LOS; on table and postoperative gastroscopy—are commonly used in fundoplication.
  - Mortality of procedure is very less; other parts of the abdomen can be assessed and addressed like gallstones.
  - *Complications* are—*gas bloat syndrome* (inability to belch); dysphagia; inability to vomit; slippage, proximal migration; paraoesophageal hernia, splenic injury. Floppy Nissen's fundoplication reduces the incidence of gas bloat syndrome.
  - *Laparoscopic Nissen's fundoplication* is ideal and equally successful.
  - *Transthoracic approach* is used for Nissen's fundoplication in patients who had hiatus hernia repair earlier; who has short oesophagus; in patients who is having sliding hiatal hernia that does not reduce below the diaphragm, associated pulmonary disease, in obese, in patients who are having narrow subcostal angle or barrel shaped chest.
- ♦ *Toupet's partial 180° posterior fundoplication*: It is similar to Nissen's posterior fundoplication; it controls reflux alike Nissen's but gas bloat is very less. It is commonly done procedure now. Short gastric vessels are divided completely or partially.
- ♦ *Rosetti Hell anterior fundoplication*: Here *anterior part of fundus* of stomach is used. Superomedial part of the fundus is brought around oesophagus to suture into anterior part of fundus. Here *short gastric vessels are not ligated* and much less fundus need to be mobilised.
- ♦ *Dor anterior fundoplication*: Here right margin of the fundus is sutured to left margin of the oesophagus; front part of fundus is sutured to right margin of the oesophagus; 2nd row is also sutured to right crus.
- ♦ *Watson's anterolateral fundoplication*: 5 cm intraabdominal oesophagus is created with blunt transhiatal dissection. 120° anterolateral fundoplication augments the LOS function during stomach distension. Bougie insertion, division of short gastric vessels are not needed here.
- ♦ *Lind both anterior and posterior fundoplication* of 300° with 60° anteriorly uncovered area is not routinely practiced now.
- ♦ *Partial fundoplication with mesh wrap* around is also used. But complications of mesh like erosion, stricture and adhesions are problems.

Fundoplications

- ❖ *Nissen's*—total 360° posterior fundoplication
- ❖ *Toupet's*—partial 180° posterior fundal/posterolateral
- ❖ *Rosetti Hell*—total anterior fundal
- ❖ *Dor*—anterior partial
- ❖ *Watson's*—anterolateral 120° partial
- ❖ *Lind*—posterior and anterior

Other Procedures

- *Hill's operation*: Intraabdominal fixation of OG junction (cardia) into median arcuate ligament to augment the effect of LOS, to enable the effective oesophageal peristalsis. Procedure is done by transabdominal approach which is assessed by intraoperative manometry. But it is technically difficult, may damage celiac plexus.
- *Belsey Mark IV operation* (1967): It is plication of oesophagus to the diaphragm through many interrupted mattress sutures so as to push the oesophagus downwards to make it intraabdominal with adequate length. It is done through left transthoracic approach. 240° fundoplication, creation of intraabdominal oesophagus, crural sling repair are the techniques. It corrects GERD and also maintains normal eructation and physiological reflux. But long hospital stay and respiratory complications are distressing problems.
- *Placement of Angelchik prosthesis*: Annular silicone gel filled angelchik prosthesis with a tape on either end. After insertion around OG junction ends are tied around.
- *Collis' vertical gastroplasty* is done using fundus of stomach. A vertical cut along the line of oesophagus is made on the fundus which is sutured to create extra length of oesophagus and new lesser curvature. It is done whenever oesophagus cannot be mobilised due to oesophageal shortening by a stricture developed as a complication of GORD. Partial fundoplication is added to this usually.
- *Thal's patch procedure*: It is done for localised nondilatable stricture oesophagus. Stricture is incised full thickness longitudinally. Mobilised fundus of stomach is placed and sutured as a serosal patch technique over the defect.
- *Narbona's ligamentum teres cardiopexy* (commonly done in Spain): Ligamentum teres is mobilised from falciform ligament with its blood supply from left lobe of liver; it is detached from umbilicus and brought around the mobilised lower oesophagus with traction until LOS pressure becomes 15-20 mmHg with manometry; flap end is sutured left of OG junction and anterior wall of stomach. It is more physiological and division of short gastric vessels is not required.
- *Boerema operation*: It is fixing OG junction in front into anterior abdominal wall. It is not practiced now.
- *Oesophagogastrectomy* is required whenever there is *failure of antireflux* procedure/*metaplasia* is present / *nondilatable stricture* is present. Lower end of oesophagus and proximal stomach is resected with oesophagogastric anastomosis is done through thoracoabdominal approach.
- *Transhiatal oesophagectomy* with anastomosis between cervical oesophagus and stomach in the neck is an alternate procedure which can be used in severe extensive disease and stricture.

Note:

Stricture oesophagus due to GERD which is dilatable can be treated by *regular oesophageal dilatation* and long term PPI therapy.



Fig. 19.8: Nissen's fundoplication.



Fig. 19.9: Toupet's partial fundoplication.



Fig. 19.10: Vertical gastroplasty is done to lengthen the intra-abdominal oesophagus.



Fig. 19.11: *Thal's patch* done for oesophageal stricture due to reflux oesophagitis.


Dor anterior fundoplicaton
I row
II row
First row behind
Second row front, also to right crus

Fig. 19.12: *Dor anterior fundoplication*. Right margin of the fundus is sutured to left margin of the oesophagus. Front aspect of the fundus is sutured to right margin of the oesophagus. Second row is also sutured to right crus.


Oesophagus
Fundus
Sutures to restore the angle
Diaphragm
Stomach
Anterior 2/3rd of fundal wrap
Stomach
Plication of OG junction
Stomach

Fig. 19.13: *Belsey mark 4 operation* for sliding hiatus hernia. It is done through thoracic approach. Here angle of oesophagus is restored with sutures and partial anterior fundal wrap is done. Then oesophagus is pushed down by oesophago-diaphragmatic plication sutures.

Complications of Surgery

- Oesophageal/gastric perforation.
- Haemorrhage.
- Pneumothorax/pyothorax.
- Vagus nerve injury.
- Cardiac arrhythmias.
- Sepsis – mediastinitis or septicaemia.
- Disruption/failure of fundoplication.
- Gas bloat syndrome.

HIATUS HERNIA

It is the most common type of diaphragmatic hernia.

Types of hiatus hernia—classification

- *Type I* hiatus hernia: It is the cephalad displacement of the gastrooesophageal junction through the hiatus into the mediastinum. It is usually small, asympto-matic and reducible. It is commonest type
- *Type II* hiatus hernia: It is superior migration of the fundus of the stomach along side the GE junction and oesophagus into the mediastinum with GE junction in normal intraabdominal location. It is rolling hernia
- *Type III* hiatus hernia: It is combination of type I and type II
- *Type IV* hiatus hernia: It is the hernia containing other abdominal viscera as content like transverse colon and omentum

Types

- Sliding hernia (85%).
- Rolling hernia (10-12%).
- Combined.



Figs 19.14A and B: Endoscopic view of oesophageal hiatus hernia.

Sliding hernia is commonly associated with GORD (Should be discussed like GORD).

Here the cardia migrates back and forth between the posterior mediastinum and peritoneal cavity.

Saint's triad

- Hiatus hernia
- Diverticulosis
- Gallstones

Kindness is a language which the dumb can speak, the deaf can understand



Sliding hernia

Rolling hernia

Fig. 19.15: Types of hiatus hernia.

ROLLING HERNIA (PARAOESOPHAGEAL HERNIA)

It is herniation of stomach fundus or rarely other abdominal contents colon/spleen through a hiatus, usually towards left side.

Clinical Features

- Common in elderly.
- Abdominal pain and chest pain.
- Hiccough, early satiety.
- Regurgitation, postprandial bloating.
- Cardiac abnormality (arrhythmia).
- Dysphagia dyspnoea.
- 40% presents as acute features with perforation/gangrene/bleeding.

Complications

- Gangrene of stomach.
- Perforation into the mediastinum.
- Perforation into the peritoneum.
- Gastric volvulus.
- Ischaemic longitudinal ulcer in the herniated stomach in rolling hernia is called as *Cameron ulcer*.

Investigations

- Plain X-ray—lateral and PA erect view showing retrocardiac air-fluid level.
- Barium meal study very useful.
- ECG.
- 3D CT scan is useful.



Sliding

Rolling

Combined

Fig. 19.16: Different types of hiatus hernia.

Treatment

- Treatment is always *surgical*.
  - Excision of sac and repair of the defect.
  - If it is gangrenous, gastrectomy is required.
  - Either abdominal or thoracic or laparoscopic approach can be used in treating rolling hernia surgically.
  - Mesh reinforcement to hiatus to close the defect may be needed.

REFLUX OESOPHAGITIS

Types

1. ***Acute:*** Following *burns, trauma, infection, peptic ulcer.*
2. ***Chronic*:** Reflux of acid in sliding hernia, after gastric surgery.

   Reflux is quite common in pregnancy.

   Site is always in lower oesophagus.

Pathology

There is bleeding granulation tissue in lower oesophageal mucosa with spasm of longitudinal muscle which pulls the adjacent gastric area upwards into the oesophagus causing sliding hernia.

Grading

1. Mucosal erythema
2. Mucosal erythema + superficial ulceration
3. Mucosal erythema + superficial ulceration + submucosal fibrosis
4. Mucosal erythema + extensive ulceration + paramural fibrosis

Savary-Miller classification of reflux oesophagitis—grading

1. Single or isolated erosive lesion(s), oval or linear but affecting only one longitudinal folds
2. Multiple erosive lesions, noncircumferential affecting more than one longitudinal fold with or without confluence
3. Circumferential erosive lesions
4. Chronic lesion: Ulcers, strictures and or short oesophagus alone or in association with grade 1-3 lesions
5. Columnar epithelium in continuity with the Z line, non-circular, star shaped or circumferential, alone or in association with grade 1-4 lesions

Los-Angeles classification of reflux oesophagitis—grading

A. One or more mucosal break *no longer than 5 mm* that does not extend between the tops of two mucosal folds
B. One or more mucosal break *more than 5 mm* long that does not extend between the tops of two mucosal folds
C. One or more mucosal break that continues between the tops of two or more mucosal folds but which involves *less than 75%* of the circumference
D. One or more mucosal break, which involves *at least 75%* of the oesophageal circumference

Clinical Features

- It is a part of GORD.
- Pain and burning sensation in retrosternal area often referred to shoulder, neck, arm.
- Heart burn is common.

- Dysphagia.
- Anaemia.

Diagnosis

- Barium meal X-ray.
- Gastroscopy and biopsy.

Barrett's ulcer is an ulcer with gastric (columnar) metaplasia in lower oesophagus.

Treatment

- *Antacids*
- *H_2 blockers*: Ranitidine, famotidine.
- ***Proton pump inhibitors***—*Main method and more effective.*
  - Omeprazole 20 mg BD one hour before food (Morning) for 6 months
  - Lansoprazole 30 mg
  - Pantoprazole 40 mg
  - Esomeprazole 20 mg
  - Rabeprazole 20 mg (can be given with food).
- ***Prokinetic drugs*** like metochlopramide, domperidone, cisapride, mosapride.
- *Treating GORD and associated causes*. By fundoplication and other surgeries.
- *Resection in severe cases*.

Note:
Erythromycin is a prokinetic drug (motilin agonist), which acts by binding with motilin receptor on GI smooth muscle cells.

BARRETT'S OESOPHAGUS (Norman Barrett, British, 1950)

- It is the metaplastic changes in the mucosa of the oesophagus as the result of GORD.
- Squamous epithelium of lower end of the oesophagus is replaced by diseased columnar epithelium (columnar metaplasia).
- There is macroscopic visible length of columnar mucosa with microscopic features of intestinal metaplasia.
- It affects lower oesophagus commonly often middle oesophagus also.

Types (Based on Length)

a. If the length of metaplasia is more than 3 cm, it is called as *long segment Barrett's oesophagus*—classic Barrett type.
b. If the length is less than 3 cm, it is called as *short segment Barrett's oesophagus*.

Histological Types

a. *Gastric type:* Contains chief and parietal cells.
b. *Intestinal type:* Contains goblet cells.
c. *Junctional type:* Contains mucous glands alike of gastric cardia.

Cardia metaplasia is metaplasia at OG junction without any macroscopic change in gastroscopy.

This diseased columnar epithelium is more prone for malignant transformation, i.e. when there is intestinal metaplasia, risk of malignant transformation increases. More the amount of dysplasia more is the risk of malignant transformation. *Dysplasia may be indefinite; low grade or high grade.*

Clinical Features

- Features of GORD.
- Haematemesis.
- Common in *men*; common in whites.

Complications of Barrett's oesophagus

- Ulcerations and stricture
- Dysphagia
- Bleeding
- Perforation
- Adeno carcinoma of O-G junction (25 times more common)

Management

- Regular endoscopic biopsy and surveillance for low grade dysplasia.
- Ablation of Barrett's oesophagus by laser.
- Photodynamic therapy—through endoscopy.
- Argon beam coagulation.
- Proton pump inhibitors—high dose for 3-6 months.
- Antireflux treatment by surgery.
- Resection—*Always better choice*—for high grade dysplasia. *Transhiatal* oesophagectomy is preferred.
- Endoscopic mucosal resection.

BARRETT'S ULCER

It is an ulcer in columnar epithelium lined Barrett's oesophagus at or just above the squamocolumnar junction.

It is more prone for:

- *Bleeding.*
- *Perforation.*
- *Adenocarcinoma of oesophagus.*

Treatment for Barrett's ulcer is endoscopic biopsy and resection.

OESOPHAGEAL MOTILITY DISORDERS

Primary

- ***Achalasia***, vigorous achalasia.
- ***Diffuse and segmental oesophageal spasm***: It is 5 times less common than achalasia, mainly primary spasm of the oesophagal body, predominantly presenting only as chest pain and less severe dysphagia. There is hypertrophy of oesophageal wall muscle with degeneration of vagal fibers; Simultaneous multipeak waveforms of high amplitude and long duration with 20 or more simultaneous waveforms out of 10 wet swallows is diagnostic. Often it can be segmental or involve distal 2/3rd of oesophagus. LES resting pressure is normal with normal deglutition relaxation time.

Barium swallow shows *corkscrew* pattern. Treated with nitrates, calcium channel blockers, bougie dilatation, long oesophageal myotomy either video assisted or thoracotomy approach.

- ***Nutcracker oesophagus*** (*supersqueeze oesophagus*): Common hypermotility disorder with high amplitude peristalsis, equal in both sexes,. Severe chest pain (noncardiac), dysphagia without regurgitation, odynophagia are the features. Waves of hypertensive amplitude pressure > 180 mmHg often can become very high > 400 mmHg; long duration contraction waves > 6 seconds with normal LES pressure and LES relaxation. It is treated with nifedipine, nitrates, antispasmodics, occasionally long myotomy.
- ***Hypertensive LES:*** LES pressure is above normal (> 26 mm Hg). LES relaxation, amplitude pressure, contraction waves, oesophageal body peristalsis are normal. Botulinum, balloon dilatation, modified Heller's myotomy are the treatment.
- ***Ineffective oesophageal motility disorders***: It is irreversible contraction abnormality of distal oesophagus in association with GORD. It is often due to secondary inflammation of oesophageal body following more exposure to gastric contents and poor oesophageal acid clearance. Reflux, dysphagia, heartburn, chest pain, are the features. Manometry shows—sum of total number of low amplitude contractions of less than 30 mmHg and nontransmitted contractions exceeds 30% of wet swallows.
- ***Nonspecific oesophageal motility disorders***: It shows slow transit incomplete emptying, with normal or hypertensive LES pressure, LES shows incomplete relaxation, decreased amplitude pressure < 35 mmHg, > 20% nontransmitted, prolonged waves of > 6 secs with abnormal peristalsis. Dysphagia, chest pain reflux and regurgitations are the features.

Secondary

- *Neurological*—stroke, bulbar palsy, motor neuron disease, multiple sclerosis, Parkinson's disease, poliomyelitis.
- *Muscular*—myasthenia gravis, muscular dystrophy, dermatomyositis.
- *Autoimmune* disorders—systemic sclerosis, polymyositis, SLE, CREST syndrome, sclreoderma.
- Eosinophilic allergic oesophagitis, alcoholic neuropathy.
- Endocrine and metastatic diseases.

ACHALASIA CARDIA (Cardiospasm)

> *The symptom—complex in cardiospasm (the term by which oesophageal achalasia was formerly known) is as a rule almost pathognomonic. It may be divided into the three stages—first, cardiospasm without food regurgitation; second, cardiospasm with immediate food regurgitation; third, cardiospasm with dilated oesophagus, the retention of food in the dilated portion and its regurgitation at irregular intervals after taking.*
>
> — **Henry Stanley Plummer,** 1908

It is failure of relaxation of cardia (oesophagogastric junction) due to disorganised oesophageal peristalsis, as a result of failure of integration of parasympathetic impulses causing *functional obstruction* (*Achalasia* means failure to relax—Greek). It is first identified by Thomas Willis in 1672.

Aetiology

- There is absence or less numbered ganglions in myenteric plexus.
  - Stress.
  - Vit B_1 deficiency.
  - Chaga's disease. It is caused by *Trypanosoma cruzi,* which is common in South America called as sleeping sickness.
  - Diffuse oesophageal spasm *(Corkscrew oesophagus).*
  - Most commonly it is *idiopathic*. There is *degeneration of Auerbach's myenteric plexus* along the entire length of oesophagus more so in LOS.
- There is pencil shaped narrowing of cardia (O-G junction) with enormous dilatation of proximal oesophagus, which contains foul smelling fluid and is more prone for aspiration pneumonia.
- Achalasia cardia *is a precancerous* condition—seven times chances of getting *squamous cell carcinoma* (8%, after 15 years).

Pathology

- Thickening of circular muscle fibres in distal oesophagus.
- Myenteric inflammation; depletion of ganglion cells; neural fibrosis, reduced nitric oxide and VIP (mediators of LES relaxation).
- Absence of peristalsis; Raised LES pressure; failure of relaxation with functional obstruction of OG junction.
- Dilatation of proximal oesophagus with atony.

Clinical Features

- Common in females between 20 and 40 years age group.
- Incidence is 6 per 1, 00,000 population.
- Chest pain occurs in early stage.
- Achalasia with diffuse oesophageal spasm is called as '*vigorous achalasia'.*
- Presents with progressive dysphagia, which is more for liquid than to solid food.
- Regurgitation and recurrent pneumonia are common (10%).
- Walking while eating, chin thrusting, neck and shoulder extension, Valsalva manoeuvre facilitates emptying of food from the oesophagus.
- Heartburn (50%) is common.
- Malnutrition and general ill health.
- Lung abscess formation.
- Odynophagia and weight loss.

Triad

- ❖ Dysphagia
- ❖ Regurgitation
- ❖ Weight loss

Staging

I: Proximal dilatation < 4 cm
II: Dilatation between 4-6 cm
III: Dilatation > 6 cm
IV: Sigmoid dilatation

Investigations

- *Barium swallow is diagnostic*—shows.



Fig. 19.17: Barium swallow X-ray showing features of achalasia cardia.

- ❖ Pencil like smooth narrowing of lower oesophagus—*Bird beak appearance*
- ❖ Dilatation of proximal oesophagus
- ❖ Absence of fundic gas bubble
- ❖ Sigmoid oesophagus or megaoesophagus

- Chest X-ray shows patches of pneumonia. *Double mediastinal strip* of dilated oesophagus is typical with air fluid level in posterior mediastinum on lateral view.
- Oesophageal manometry shows unrelaxed lower oesophageal sphincter with high resting pressure—very useful and gold standard. It shows failure of LES to relax completely during swallowing and complete absence of peristalsis. LES pressure is > 35 mmHg. Base line oesophageal pressure will be high without progressive oesophageal peristalsis with low amplitude muscular tone. Intraoesophageal pressure in relation to intragastric pressure is elevated.
- Oesophagoscopy is done to confirm the diagnosis and to rule out carcinoma oesophagus. It shows totally closed LES with atonic, dilated proximal oesophagus. Biopsy of mucosa at LES should be done.



Fig. 19.18: Endoscopic view of achalasia.



Fig. 19.19: Sigmoid oesophagus in achalasia cardia—Barium X-ray and endoscopic view.

Self-respect — that a corner stone of all virtue.

Differential Diagnosis

- Carcinoma oesophagus.
- Stricture oesophagus.
- Scleroderma.



Fig. 19.20: Diagrammatic representation of achalasia cardia.



Fig. 19.21: X-ray picture of achalasia cardia.

Treatment

Treatment for achalasia

- *Forcible dilatation*:
  - Plummer's pneumatic dilatation
  - Negus hydrostatic balloon dilatation
- Modified *Heller's* cardiomyotomy
- *Drugs*
  - Botulinum toxin A
  - Nitroglycernie, nifedipine

Surgery

- *Modified Heller's operation* (Heller—German, 1913): Oesophagocardiomyotomy. Success rate is 85%.
  - Either through thoracic or through abdominal approach, thickened circular muscle fibres are cut longitudinally for about 8-10 cm, 2 cm proximal to the thickened muscle to 1 cm distal to OG junction. Care should be taken not to open the mucosa (Anterior myotomy is done now. Original Heller's is both anterior and posterior myotomies).
  - *Nissen's or Toupet's fundoplication* is done along with the above procedure to prevent reflux.
- *Forcible dilatation* stretches spasmodic segment. Gradual repeated dilatations are required. Dilatation up to 54 French bougie can be done. Two types of dilatations are used—*pneumatic* and *hydrostatic*.
  - *Plummer's pneumatic dilatation* is done using balloons of 30-40 mm diameters. It is inserted over a guidewire. Risk of perforation (1%), need for repeated dilatations are the problems.
  - *Negus hydrostatic dilatation* is done to dilate O-G junction. It is not very well accepted method as chances of



Fig. 19.22: Heller's cardiomyotomy—on table look with partial fundoplication (*Courstesy:* Dr Yogishkumar, Professor of Surgery, KMC, Mangalore).



Fig. 19.23: Heller's cardiomyotomy for achalasia cardia. Only circular muscle layer is cut longitudinally in OG junction until mucosa protrudes out without perforating the mucosa.

perforation is high. Success rate is 65%. 30 mm diameter balloon is inflated for 3 minutes.

- *Laparoscopic/thoracoscopic* cardiomyotomy—ideal.
- Resection is done when failure of myotomy occurs or when megaoesophagus or metaplasia is present. *Transhiatal* total oesophagectomy with gastric pull up and oesophagogastric anastomosis in the neck is a good option in such patients.





Figs 19.24A and B: Laparoscopic port positions and view of Helller's cardiomyotomy for achalasia cardia (*Courtesy:* Dr Roshan, MS DNB, Laparoscopic Surgeon, City Hospital, Mangalore).

Drugs

a. Endoscopic injection of botulinum toxin to sphincter—high recurrence rate.
b. Calcium channel blocker, nitroglycerin sublingually.



Fig. 19.25: Negus hydrostatic dilator used for achalasia cardia. It has got only 65% success rate.

Note:

- *Pseudoachalasia* shows features like of achalasia cardia with dysphagia and weight loss, seen in an elderly due to carcinoma. Amylnitrate inhalation causes sphincter relaxation in Achalasia cardia but not in pseudoachalasia.
- *Botulinum toxin* is neurotoxic protein derived from Clostridium botulinum is highly toxic poisonous substance. Very small dose is used for therapeutic purpose. Seven types of toxins are found. A (A1 /A2 /A3) type is used for therapy. It blocks the cholinergic nerve ends reducing the cholinergic acetylcholine release causing flaccid paralysis of muscles. It is used in cosmetic facial line, strabismus, focal dystonia, tremor, tics, muscle spasms, achalasia, smooth muscle hyperactivity, Frey syndrome, and hyperhidrosis.

PLUMMER-VINSON SYNDROME (Paterson-Kelly Syndrome)



Fig. 19.26: Oesophageal web, endoscopic view.

Hope sees the invisible, feels the intangible and achieves the impossible.

- Here *oesophageal webs* are seen in uppermost portion of the oesophagus with spasm of circular muscle fibres.
- Common in patients with long standing *iron deficiency anaemia*.
- Common in females.
- *Superficial glossitis*, *cheilitis, koilonychia commonly seen.*
- Splenomegaly may be present.
- In oesophageal webs, mucosa is hyperkeratotic, friable, desquamated.
- It is a *premalignant condition* and presents with severe dysphagia.
- Oesophagoscopy and biopsy is required to rule out malignancy.

Treatment

- Oral iron—ferrous sulphate 300 mg TDS with vitamins.
- Blood transfusion is given when there is severe anaemia (Transfusion of packed cells).
- IV or IM iron therapy.
- Once anaemia comes under control, webs will clear and patient can swallow.
  Follow-up endoscopy is a must.
- Dilatation of web may be required.

CORROSIVE STRICTURE OF OESOPHAGUS

Features of oesophageal corrosive lesion

- *Acute/immediate*
  - Severe pain, shock, laryngeal oedema
  - Mediastinitis, septicaemia, haemorrhage, perforation
- *Late/chronic*
  - Dysphagia
  - Stricture—50%
  - Severe malnutrition
  - Recurrent respiratory infection
  - Oesophageal shortening
  - Malignant changes
  - Tracheo-oesophageal fistula formation

Corrosive strictures can be multiple. Damage is more in lower 1/3rd of oesophagus

- Corrosives are commonest cause of oesophageal stricture.
- Mainly due to ingestion of alkali (*Lye stricture*—Lye is strong alkali sodium hydroxide) sodium hydroxide, occasionally due to acid (sulphuric acid, nitric acid). Acid commonly damages the stomach.
- It causes extensive inflammation of the mucosa with perioesophagitis which, if not treated leads to multiple strictures in oesophagus.
- Sometimes it causes severe life-threatening necrotising lesion which requires immediate surgical intervention.
- Acute phase lasts for 3 weeks.
- Damage is more in lower 1/3rd of oesophagus.
- Alkali is odourless and tasteless and so large volume is ingested. Alkali causes liquefaction, saponification and thrombosis of vessels and later leading to fibrosis and stricture. Acid causes intense pylorospasm, antral pooling of acid, coagulation necrosis and eschar formation.
- Severity depends on type of agent, its concentration and volume.

Phases of tissue injury in corrosive ingestion	***Degrees of burns after corrosive oesophageal and gastric burns***
Phase 1: Acute necrosis—1-4 days	*1st degree*: Mucosal hyperaemia and oedema
Phase 2: Ulceration—granulation—4-12 days	*2nd degree*: Small bleeding, exudates, ulcers, pseudomembrane
Phase 3: Cicatrisation and scarring—3 weeks–6 months	*3rd degree*: Mucosal slough, deep ulcers, massive bleed, complete obstruction, charring, perforation



Figs 19.27A and B: Endoscopic view of corrosive injury. Endoscopy should be done very gently in corrosive injury.

Treatment

- *Acute phase management*:
  - *Neutralisation* with vinegar or citrus food if it is alkali ingestion (If pH of the solution is less than 11.5 then damage is less); it is with antacids, milk, egg whites if it is acid ingestion. Early endoscopy is needed to assess the severity and extent.
  - Emetics and $NaHCO_3$ are *avoided* as they may precipitate perforation.
  - *In 1st degree burns*: 48 hours observation; oral feeds are started once patient swallows saliva painlessly. Regular follow-up endoscopy at 1st, 2nd and 8th months. Stricture if formed can be identified by this time.
  - *2nd and 3rd degree burns*: They are treated with fluid therapy, antibiotics, nutrition, resuscitation, PPIs, aerosolised steroids, fiberoptic guided airway intubation if needed / tracheostomy; endoscopic oesophageal stenting, feeding jejunostomy, laparoscopy for evaluation. Unstable patients have high mortality. Laparotomy is done in such patients. If oesophagus and stomach shows full thickness necrosis, resection of these parts is done and end cervical oesophagostomy with jejunostomy is done. When in doubt re-exploration for second look is done after 36-48 hours to assess the stomach.
- Careful early gentle repeated endoscopy is mandatory.
- Though advocated often for 2-3 weeks, use of steroids is controversial and under debate.

- Antibiotics if there are chances of aspiration or perforation.
- *Regular oesophageal dilatation* is done for stricture. Stricture is dilated endoscopically using guidewire. Dilators are solid type with gradual increase in diameters. Often radiologic C-ARM guidance is needed to pass the guide wire into the stomach. Dilatation should be done up to minimum 16 mm diameter. Pneumatic or balloon dilatation is also practiced. Gum elastic dilators, mercury weighted dilators, Eder-Puestow dilators, Savary-Gilliard dilators, balloon dilators are other dilators used. Earlier, blind dilatation using oesophageal bougies of increased diameters was the practice, which is followed even now in many places, but chances of perforation is more.
- Oesophageal resection in corrosive strictures is technically difficult and may be hazardous. Oesophageal bypass is better and easier, and following later by regular endoscopic surveillance for malignant transformation (5%). Colon is used as replacing conduit as stomach itself may be diseased in corrosive pathology.
- In multiple strictures oesophageal resection and colonic transposition may be advocated if risk of malignancy is considered.

Note:

Malignancy can develop in corrosive strictures—5%. It is 1000 fold greater than general population.

Causes of stricture oesophagus

- Peptic stricture (oesophagitis induced)
- Corrosives—most common cause
- Foreign body
- Postsurgical, radiotherapy
- Congenital
- Infection like tuberculosis
- Drugs like tetracycline, vitamin C



Fig. 19.28: Endoscopic view of oesophageal stricture.



Fig. 19.29: Oesophageal dilatation is being done endoscopically.



Fig. 19.30: Barium swallow showing stricture at lower oesophagus. It may be due to oesophagitis, congenital, tuberculosis, malignancy, drug induced, etc.



Fig. 19.31: Patient underwent total oesophagectomy with colonic transposition. Colon placed in subcutaneous plane.

SCHATZKI'S RINGS

They are semicircular protrusion of lower oesophageal mucosa located at or just above the oesophagogastric junction (squamo-columnar junction). Its under-surface is lined by columnar gastric epithelium.

- They involve only the mucosa and submucosa of the oesophagus, not the muscle.
- They present with dysphagia and reflux.
- *Episodic aphagia* can occur causing, food bolus or meat bone to get impacted which requires emergency rigid oesophagoscopy to remove the food. 5 ml of 2.5% oral papain every 30 minutes to digest food protein along with 50 mg meperidine IV to dislodge the impacted food bolus can be tried initially.



Fig. 19.32: Barium swallow X-ray showing Schatzki ring, also shows features of hiatus hernia.



Fig. 19.33: Schatzki's ring—endoscopic view.

Treatment

- Intermittent oesophageal bougienage.
- Antireflux drugs.

Note:

Ring *should not* be excised.

BOERHAAVE'S SYNDROME

It is a tear in the lower third of the oesophagus which occurs when a person vomits *against a closed glottis,* causing leak into the mediastinum, pleural cavity and peritoneum.

Site

2-10 cm of posterolateral part of lower oesophagus.

Investigations

- Chest X-ray—shows pneumomediastinum *('V' sign of Naclerio*).
- MRI/CT chest.
- Total count.

Treatment

- Nil by mouth.
- Antibiotics, IV fluids, TPN.
- Feeding by jejunostomy.
- Most often surgery with resection may be required (thoracotomy and repair).
- *When severe mediastinitis occurs, condition has high mortality.*



Superficial tear with bleed in stomach near O-G junction
Deep tear with perforation in oesophagus lower 1/3rd
Mallory-Weiss syndrome
Boerhaave's syndrome

Fig. 19.34: Diagrams showing Mallory-Weiss syndrome and Boerhaave's syndrome.

MALLORY-WEISS SYNDROME

- It is seen in adults with severe prolonged vomiting, causing longitudinal tear in the mucosa of stomach at and just below the cardia, *leading to severe haematemesis***.**
- Violent vomiting often may be due to migraine or vertigo or following a bout of alcohol.
- Presents with severe *vomiting* and later *haematemesis*, with features of *shock.*
- It is common in one o'clock position.
- Only 10% of cases involve lower oesophageal mucosa.

Features of Boerhaave's syndrome

Presentations	***Differential diagnosis***	***Complications***
Sudden onset of symptoms	Myocardial infarction	Mediastinitis
Severe chest pain	Pancreatitis	Septicaemia
Pain abdomen		Peritonitis
Subcutaneous emphysema Shock		Emphysema

'Crunching effect in the chest' is called as *Hamman's sign*.
Mackler's triad: (1) vomiting, (2) chest pain, (3) subcutaneous emphysema.

Investigations

- Gastroscopy, Hb%, PCV, blood grouping.
- During gastroscopy, if stomach is not inflated properly, 50% cases may be missed.

Differential diagnosis

- Bleeding peptic ulcer
- Oesophageal varices
- Erosive gastritis
- Carcinoma stomach

Treatment

- Conservative, as it is only a mucosal tear.
- Blood transfusion.
- IV fluids.
- Sedation.
- Haemostatic agents like vasopressin.
- Endoscopic injection therapy is used if required.
- Surgery is rarely required.

TRACHEO-OESOPHAGEAL FISTULA

Types

- In **85% cases,** it is a blind upper end with lower end communicating with trachea.
- It may be associated with **VACTER** anomalies.

V — Vertebral defects
A — Anal atresia
C — Cardiac defect (PDA/VSD)
TE — Tracheo-oesophageal fistula
R — Radial hypoplasia and renal agenesis

Clinical Features

- TOF should be recognised within 24 hours of birth.
- Newborn baby regurgitates all feeds and there is continuous pouring of saliva from the mouth which is a *diagnostic feature.*
- *Cough and cyanosis*.
- It is commonly associated with maternal *hydramnios (50%).*

Investigations

- Obstruction is revealed while passing nasogastric tube.
- Contrast study will reveal fistula and obstruction (Dionosil 1 ml).
- Other anomalies are looked for.
- Chest X-ray.
- Echocardiography.

Treatment

Surgery

- Child requires feeding gastrostomy commonly.
- Often the procedure is staged one.
- Through right sided thoracotomy (opposite to the side of aortic arch), fistula is identified and resected. Lower segment is anastomosed to the blind upper segment. Occasionally if the length is inadequate or the atretic segment is long one then, colonic or gastric transposition is required.



Figs 19.35A to D: Types of tracheo-oesophageal fistula. (A) H type, (B) Lower end blind, upper end connected to trachea, (C) Both ends blind, (D) Upper end blind, lower end connected to trachea (85%).

Complications of surgery

- Pneumonia
- Leak from the anastomotic site
- Reflux
- Dysphagia

OESOPHAGEAL DIVERTICULUM



Fig. 19.36: Endoscopic view of oesophageal diverticulum

All things must change to something new and strange.

Types

1. ***Pulsion diverticulum:***

Pulsion diverticula are *false type* containing *mucosa and submucosa* only; is due to high abnormal intraluminal oesophageal pressure developed due to various motility disorders.

   a. Pharyngeal pouch through Zenker's or Killian's dehiscence (*Refer chapter NECK*).
   b. *Epiphrenic pulsion* diverticulum occurs in lower oesophagus, usually towards right side, due to obstruction in the distal oesophagus or due to incoordinated LOS relaxation.
      – *Site* is within 10 cm of OG junction. It is *false* type.
      – It is associated with *nonspecific oesophageal motility* disorders and often with achalasia and diffuse oesophageal spasm. Ehler Danlos syndrome and trauma are other causes.
      – It is common on *right* side with wide mouth.
      – *Features* are of motility disorders like dysphagia, regurgitation, cough, weight loss, chest pain.
      – Barium study, CT chest are *diagnostic*; endoscopic evaluation with EUS, manometry is a must.
      – *Treatment:* Diverticulopexy/diverticulectomy (excision) + oesophageal myotomy (Heller's) + repair of associated hiatus hernia/antireflux procedure.

2. ***Traction diverticulum:***

Occurs in mid-oesophagus or in parabronchial region, is due to mediastinal granulomatous disease like tuberculosis.

- Traction diverticulum is a *true* type containing all layers in its wall and is due to traction by the healing fibrosing mediastinal lymph nodes.
- It is seen commonly towards right side. It has got wide mouth and it rests on the spine.
- *Presentation* is dysphagia, chest pain and regurgitation.
- CT scan (chest), barium study, manometry, endoscopy to assess mucosa with EUS, blood test for tuberculosis (ESR, peripheral smear) are the *investigations*.
- *Treatment:* Treating the *cause* like tuberculosis, histoplasmosis. Diverticulum less than 2 cm is observed; progressive symptoms, size > 2 cm needs surgery. *Surgeries* are—diverticulopexy, long oesophageal myotomy.

CARCINOMA OESOPHAGUS

- Carcinoma oesophagus is common in China, South Africa and Asian countries.
- It is 6th most common cancer in the world.
- It is less than 1% of all cancers. It is 7% of all GI malignancies.
- It is less common in America and European countries.
- In India, it is common in Karnataka and Orissa.
- When patient presents with dysphagia, often it is fairly advanced and inoperable and only palliation is the possibility. But then surgery is the treatment of choice in early growths.

Aetiology

Diet, deficiencies (vit. A, C, Riboflavin)
Mycotoxin
Alcohol and tobacco
Fungal contamination of food

Achalasia cardia
Oesophageal webs
Barrett's oesophagus
Plummer –Vinson's syndrome
Corrosive strictures
Tylosis*
Nitrosamines

5% common
Common after 45 years
Common in men
Common in ***China*** – ***Henan*** province
In India, common in Orissa and Karnataka

* *Tylosis* is an inherited disease with thickening of skin of palm and sole

Tylosis

- Autosomal dominant condition seen from childhood
- Soles and palms are involved called as palmoplantar keratoderma
- Waxy, yellow lesions, which does not itch
- 60% of members of families develop carcinoma oesophagus after the age of 60
- Systemic retinoids are the drugs used for tylosis

Pathology

- Common in:
  - Middle third—50%.
  - Lower third—33%.
  - Upper third—17%.
- Lower 3 cm of oesophagus is lined by columnar epithelium, and so adenocarcinoma is common here. Barrett's columnar metaplasia which occurs in lower third of oesophagus is also more prone for adenocarcinoma.
- Squamous cell carcinoma is commonest type in India and Asian countries.



Figs 19.37A and B: Carcinoma oesophagus middle third—pathology specimen, gross and cut section.

Note:

- *In India 90% are squamous cell carcinomas.*
- *In western countries, adenocarcinoma is becoming more common.*

Adenocarcinoma arises from submucosal oesophageal glands/heterotrophic columnar epithelium/Barrett's oesophagus.

Gross Types

- Annular (15%).
- Ulcerative (20%).
- Fungating—cauliflower like (60%).
- Polypoid.
- Varicoid—diffuse submucosal type.



Figs 19.38A to D: Gross outer look and cut section of proliferative and indurated lesions of carcinoma oesophagus.

Spread

- *Direct*
  - Lack of serosal layer in oesophagus favours local extension. In upper third it spreads through muscular layer and get adherent to left main bronchus, trachea, and left recurrent laryngeal nerve (causes hoarseness), aorta or its branches (causes fatal haemorrhage, but rare).
  - It may perforate and cause mediastinitis.
  - It may get adherent to pleura also.
- *Lymphatic spread*
  - It spreads both by lymphatic permeation and lymphatic embolisation.
  - It can cause satellite nodules elsewhere in the oesophagus, away from the main tumour.
  - Above in the neck, it spreads to supraclavicular lymph nodes.
  - In thorax, it spreads to paraoesophageal, tracheobronchial lymph nodes to subdiaphragmatic lymph nodes.
  - In abdomen, it spreads to coeliac lymph nodes.
- *Blood spread occurs* to liver, lungs, brain and bones.

Clinical Features

- *Recent onset of dysphagia* is the commonest feature. *For the dysphagia to develop, two-third of the lumen should be occluded.*
- Regurgitation.
- Anorexia and loss of weight (severe), cachexia.
- Pain-substernal or in the abdomen.
- Liver secondaries, ascites.
- Bronchopneumonia, melaena.
- Features of broncho-oesophageal fistula in carcinoma of upper third oesophagus (30%).
- Left supraclavicular lymph nodes may be palpable.
- Hoarseness of voice due to involvement of recurrent laryngeal nerve.
- Hiccough, due to phrenic nerve involvement.
- Back pain—due to nodal spread (paraoesophageal/*coeliac* nodes).
- Male to female ratio is 3:1. In adenocarcinoma it is 15:1.

Investigations

- *Barium swallow*: Shouldering sign and irregular filling defect.
- *Oesophagoscopy*—to see the lesion, extent and type.
- *Biopsy*—for histological type and confirmation.
- *Chest X-ray*—to look for aspiration pneumonia, *to see vocal cord palsy, to identify fistula.*
- *Bronchoscopy*—to see invasion in upper third growth.
- *Oesophageal endosonography*—to look for the involvement of layers of oesophagus, nodes, cardia and left lobe of the liver. Nodes smaller than 5 mm can be very well visualised by EUS which may be missed in CT scan. EUS guided transmucosal nodal needle aspiration cytology can also be done.
- *CT scan* (95% accuracy)—to look for local extension, nodal status, perioesophageal/diaphragmatic/pericardial (1%)/ vascular infiltration, obliteration of mediastinal fat and status of tracheobronchial tree in case of upper third growth.

- *U/S abdomen*—to look for liver and lymph nodes status in abdomen.
- *Endoscopic oesophageal staining* with labelled iodine results in normal mucosa being stained brown, but remains pale in carcinoma (as mucosa in carcinoma will not take up iodine).
- *Blood tests*: Haematocrit; ESR; Liver function tests.
- *Laparoscopy*: It is useful to see peritoneal spread, liver spread and nodal spread. It is the only reliable method to detect peritoneal seedlings. Biopsy from different places can also be taken. It will prevent unnecessary laparotomy for anticipated surgical resection.
- *PET scan* using 18 F-fluorodeoxyglucose (FDG): 18 FDG is given to the patient. FDG enters highly active cells and gets phosphorylated to FDG 6 phosphate. It stays in the cell as end product and get polarised there. PET with CT scan is used to see response for therapy.
- *Video assisted thoracoscopic approach*—to stage oesophageal carcinoma.
- *Endoscopic mucosal resection (EMR)* is done using double channeled endoscope with tip having a soft plastic cap. Cap is firmly placed over the lesion and suction is created; a snare is brought over the lesion; biopsy specimen is snared off 1.5 cm in size containing mucosa and submucosa. It is basically a diagnostic biopsy tool; but can be therapeutic in early and premalignant lesion. Endoscopic submucosal dissection (ESD, Japan) is now devised using hook cautery and scissors to remove the lesion up to muscularis propria.

Treatment

Gastrostomy should not be done as a palliative procedure.

Principles

- Only 20% of oesophageal cancers present early and becomes *curable*. In such early growths confirmed with absence of nodal spread, curative surgery is the main approach—*radical oesophagectomy*. Proximal extent of resection should be 10 cm above the macroscopic tumour and distal extent of resection is 5 cm from macroscopic distal end of tumour. Proximal stomach has to be removed commonly especially in lower 1/3rd of tumour. Sufficient removal of contiguous structures may be needed in curative resection.
- If nodes are present, then multimodal approach should be used like—curative resection; radiotherapy and chemotherapy. Outcome of surgery depends on location of tumour; number, location and size of nodes; tumour grading.
- Neoadjuvant therapy by chemotherapy and/or radiotherapy prior to surgery may improve the survival.
- Aggressive chemoradiation also may be used as curative therapy in some patients especially upper 1/3rd growths and in patients who are unfit for surgery.
- In remaining patients (80%) *palliation* is the main modality of treatment. Palliation therapy is done if patient is not fit for major surgery; if there is blood spread; if there is spread to adjacent organ; if there is peritoneal/liver spread. It is to relieve pain and dysphagia and also to prevent aspiration and bleeding.

Indications for Curative Treatment

1. Early growth when patient is fit.
2. When there is no involvement of adjacent perioesophageal structures, bronchus, liver or distant organs.



Fig. 19.39: Carcinoma in upper oesophagus (Endoscopic view).

Indications for palliative therapy

- Relieve pain
- Relieve dyspahgia
- Prevent bleeding
- Prevent aspiration



Fig. 19.40: Carcinoma oesophagus (Endoscopic view).

TNM staging	***WNM staging (Wall penetration, Node, Metastases)***
T – Tumour: T_x - Tumour cannot be assessed T_0 – No tumour Tis – High grade dysplasia T_1 – Tumour invades lamina propria, muscularis mucosa or submucosa without breaching submucosa T_2 – Tumour invades into muscularis propria but not beyond T_3 – Tumour invades paraoesophageal tissues without adjacent structure invasion T_4 – Tumour invades adjacent structures **N – Nodal spread:** N_x – Regional nodes cannot be assessed N_0 – No regional node spread N_1 – Regional node spread present **M – Distant metastases:** M_x – Distant spread cannot be assessed M_0 – No distant spread M_{1a} – Upper oesophageal tumour spreads to cervical nodes; middle oesophageal tumour spreads to mediastinal nodes; lower oesophageal tumour spreads to celiac nodes. M_{1b} – Upper oesophageal tumour spreads to mediastinal or celiac nodes; middle oesophageal tumour spreads to cervical or celiac nodes; lower oesophageal tumour spreads to cervical or upper mediastinal nodes. *Staging TNM:* Stage 0 – Tis,N_0,M_0 Stage I – T_1,N_0,M_0 Stage IIA – T_2,N_0,M_0; T_3,N_0,M_0 Stage IIB – T_1,N_1,M_0; T_2,N_1,M_0 Stage III – T_3,N_1,M_0; T_4,anyN,M_0 Stage IVA – AnyT,AnyN,M_{1a} Stage IVB – AnyT,AnyN,M_{1b}	**Wall penetration:** W0 – Intramucosal mucosa penetration W1 – Intramural mucosa penetration W2 – Transmural mucosa penetration **N – regional nodes:** Nx – Regional nodes cannot be assessed N0 – No regional nodes N1 – 1-4 regional nodal spread N2 – More than 4 nodal spread **M – Distant metastases:** Mx – Distant spread cannot be assessed M1 – No distant spread M2 – Distant spread present *Staging WNM:* Stage 0 – W_0,N_0,M_0 Stage I – W_0,N_1,M_0; W_1,N_o,M_0 Stage II – W_1,N_1,M_0; W_2,N_0,M_0 Stage III – W_2,N_1,M_0; W_1,N_2,M_0; W_0,N_2,M_0 Stage IV – AnyW,AnyN,M_1
Variables considered for management: Histology of tumour—SCC / adeno Location of tumour—cervical, mid thoracic, lower Extension of tumour in depth Staging of tumour Distant spread Nutritional status of the patient—good/fair; serum albumin more or less than 3.4 mg% Pulmonary function, cardiac reserve Weight loss less or more than 10% Dysphagia present/absent	*Japanese added to TI of TNM system following:* T_1 – Mucosal epithelial—no node chance T_1 – Lamina propria—5% nodes chance T_1 – Muscularis mucosa—18% nodes chance T_1 – Superficial submucosal—50% node chance T_1 – Middle submucosal T_1 – Deep submucosal—55% node chance


Proximal oesophagus
Ulcerative growth
Early growth
Proliferative
Deep ulcer
Proliferative OG junction

Fig. 19.41: Endoscopic views of oesophageal carcinomas—at different levels and different gross types.



Fig. 19.42: Endoscopic view of carcinoma oesophagus in lower third.



Fig. 19.43: Barium swallow showing irregular filling defect and shouldering sign in middle third oesophagus.



Figs 19.44A to C: Barium swallow X-rays showing irregular filling defect at different levels—feature of carcinoma of oesophagus.

Approaches for Different Level Tumours

Post cricoid tumour (Squamous cell carcinoma):

- Treated mainly by radiotherapy. Radical radiotherapy—5000-6000 rads.
- Often pharyngolaryngectomy is done along with gastric or colonic transposition. But complications are more in this procedure. Free jejunal transfer is the other option.

Upper third growth (Squamous cell carcinoma):

- Treated mainly by radiotherapy.
- Commonly it is advanced with left recurrent laryngeal nerve palsy and bronchial invasion.
- If it is early and operable, *McKeown three phased oesophagectomy* and anastomosis is done in the neck. Initially laparotomy is done to mobilise the stomach. Then thoracotomy through right 5th space is done and oesophagus is mobilised. Through right side neck approach, oesophagus with growth is removed. Anastomosis between pharynx and stomach is done in the neck.
- Split sternum approach oesophagectomy is also practiced.

Middle third growth (Squamous cell carcinoma)**:**

Ivor Lewis operation (Lewis-Tanner two-phased oesophagectomy): After laparotomy stomach is mobilised. Pyloroplasty is done. Through right 5th space thoracotomy is done and growth with tumour is mobilised. Partial oesophagectomy and oesophagogastric anastomosis is done in the thorax. Intercostal tube drainage is placed during closure. Right gastroepiploic vessels should be retained safely (essential). Azygos vein should be ligated securely. Mediastinal nodes should be dissected. Thoracic duct should be ligated if needed. Feeding jejunostomy is better to maintain nutrition.

If the growth is inoperable, palliative radiotherapy is given.

Lower third growth (Squamous cell carcinoma + adenocarcinoma):

- Here through left thoracoabdominal approach, partial oesophagogastrectomy is done with oesophagogastric anastomosis.
  Often jejunal Roux-en-Y loop anastomosis is done.
- *Orringer approach,* i.e. *transhiatal blind total oesophagectomy* with anastomosis in the left side of the neck. Through laparotomy, stomach and lower part of the oesophagus are mobilised. Through left sided neck approach, upper part of the oesophagus is mobilised using finger. Blind dissection is completed by meeting both fingers above and below in the thorax. Later oesophagus is pulled up out above through the neck wound and removed. Continuity is maintained in the neck. It is a *palliative* surgery.



Fig. 19.45: Transhiatal blind oesophagectomy—on table surgical specimen.

Other Approaches

- *Thoracoscopic—laparoscopic oesophagectomy* and lymphadenectomy is becoming popular, safer and effective.
- *Radical oesophagectomy with 3-field clearance* of abdominal/thoracic and cervical nodes is also practiced in many centres. 3-Field clearance (coeliac, thoracic and neck) is done for mainly squamous cell carcinoma as spread in SCC

Truth, like surgery, may hurt, but it cures.

is upwards. In adenocarcinoma 2-field clearance is sufficient (abdominal—coeliac and thoracic) as spread is downwards.

Note:

When oesophagus is removed totally or subtotally an interposition is required between cervical oesophagus/pharynx and distal stomach. Different parts of GI is used for the same.

Oesophageal substitutes:

- **Stomach**: It is preferred one and is based on right gastric and right gastroepiploic arteries. It needs only one anastomosis and take up is well due to good vascularity. But it can cause postprandial fullness with bile or acid regurgitation (> 50%). It also needs a pyloroplasty for gastric drainage as vagotomy is done. Entire stomach or tubed part or reverse tubed part can be transposed.
- **Colon**: It is better as there is less postprandial problems. But technique is more with the need of three anastomoses. Right colon is used with middle colic artery based as isoperistaltic loop. Left colon is used with ascending branch of left colic artery as antiperistaltic loop. Complications are leak, fistula formation.
- **Jejunum**: Isolated required length of pedicled jejunum is transposed. Jejunal free transfer is also tried; vessels are sutured to internal mammary vessels or to the vessels available the neck. Pedicled jejunum is also *supercharged* with microvascular anastomoses with internal mammary vessels. It is used as a last option only.

Transposition is done through posterior mediastinum (*shortest route*), right pleural space (transpleural), retrosternal or subcutaneous route.

- *Skinner en bloc resection* used to be of practice in olden days in which tumour with oesophagus is resected along with thoracic duct, azygos vein, intercostal vessels crossing the vertebral bodies, pericardium and mediastinal pleura. There is no survival benefit with this procedure.
- *Vagal sparing oesophagectomy* with HSV is tried to preserve pylorus functioning with avoiding pyloroplasty to reduce the chances of postprandial fullness. But it is technically tedious.
- *Lymphadenectomy* in carcinoma oesophagus:
  - *Standard*: Nodes removed are—paratracheal, parabronchial, carinal, paraoesophageal, posterior mediastinal, paracardial, left gastric, along lesser curve of stomach.
  - *Extended/three field/ultraradical*: As like standard above, with bilateral cervical lymphadenectomy, removal of upper mediastinal, coeliac, retroperitoneal, subhepatic nodes.

Surgical approaches

- Ivor-Lewis 2-phase oesophagectomy
- McKeown 3-phase oesophagectomy
- Left abdominothoracic approach for lower oesophagus—*Sweet* approach
- Thoracoscopic—laparoscopic
- Transhiatal blind approach—Orringer's

Postoperative Management

- Fluid and electrolyte management.
- Antibiotics and proper analgesia.
- Respiratory care; ICT care; physiotherapy.
- Prevention of DVT—elevation, exercises, heparin.
- Monitoring for bleeding, sepsis, leak, oxygen saturation.
- TPN only during initial postoperative period and *early jejunostomy feeding* for nutrition.

Palliative Treatment

80% of patients with carcinoma oesophagus, when present first, have fairly advanced tumour and so they are amenable for only palliative treatment. It is to *relieve pain, dysphagia and to prevent aspiration and bleeding*. Palliation therapy is done –

- If patient is not fit for major surgery.
- If there is blood spread.
- If there is adjacent organ spread.
- If there is peritoneal/liver spread.

Different methods are

- ***Palliative external radiotherapy***
  - 3000 Rads. Severe mucositis, stricture and fistula formation are the complications.
- ***Intraluminal RT***
  - Brachytherapy (radiation intraluminally). Loading catheter is placed using endoscope and applicator is fixed to mouth to give 1500 cGy radiation with least systemic effects.



Fig. 19.46: Stricture oesophagus after radiotherapy given for carcinoma oesophagus.

- ***Chemotherapy***
  - Cisplatin; methotrexate; 5 FU; ***palcitaxel***, etoposide, bleomycin. *Platinum based chemotherapy* is beneficial especially in advanced adenocarcinoma of oesophagus.
- ***Intubation***

  Intubation was described by Symmonds in 1887. It is commonly used method. Guidewire is passes across the growth under X-ray screening or C-arm guidance; flexible introducer and prosthetic tube is pushed across the tumour along the guidewire. It carries 90% success rate. Problems are—tube intolerance, poor drainage, airway compression, reflux, aspiration, displacement, food blockage, tumour overgrowth beyond the prosthesis causing its failure.

Intubation is used for *tracheo-oesophageal fistula* or external compression. Prosthesis with a sponge filled balloon is used for fistula closure. Standard tube wrapped with multilayered polyvinyl sponge is other option. It is less expensive, single time, rapid acting.

They can be traction or pulsion tubes. Perforation chance is 10%.

Different tubes used are:

- *Atkinson tube.*
- *Celestin tube* (armoured rubber tube with a long tail)—ideal, commonly used tube. It is wider proximally. It can be passed through endoscopy or laparotomy.
- *Souttar tube (coiled German silver wire)*—block is first dilated with bougies; tube is passed over small sized bougie and pushed ascross the block. It is mainly useful for lower oesophagus.
- *Mousseau-Barbin tube*—cheaper but needs laparotomy. After laparotomy, anterior wall of the stomach is opened. MB tube is passed from mouth with the help of anesthetist by stitching its tip to nasogastric tube and pulled down into the stomach. Tip is cut near the cone part. It is sutured to anterior wall of the stomach. Gastrotomy is closed.

◆ ***Endoscopic therapy:***



Fig. 19.47: Oesophageal stent *in situ*—a look endoscopically.

- **Self-expanding metal stents (SEMS)** are passed through endoscope under C-arm guidance. It is the *ideal method of palliation*. Stent is collapsed during insertion and released once it is placed in proper position. There is no need to dilate oesophagus more than 8 mm to pass this expanding stent and so chances of perforation is minimal.

  Uncovered SEMS—here tissues project through the mesh to have a better grip with less chances of migration. But stent occlusion is more.

  Plastic covered SEMS—it shows less stent occlusion and less friction. Stent migration is more.

  SEMS may be—stainless wall stent; knitted nitinol Strecker stent; stainless steel covered *Gianturco-Rosch* stent.

  Problems of stents are—aspiration, displacement, erosion, bleeding, tumour growth across or beyond mesh, food bolus obstruction, retrosternal pain, need for reinsertion (40%). Mortality is 1-2%.
- **Endoscopic laser** is used to core a channel through the tumour to improve dysphagia (Nd YAG laser; Diode laser). It causes thermal destruction of tumour. It improves dysphagia but needs repeated laser ablation. It may be used more effectively to remove tumour block in previously placed stents.

  Exophytic tumour less than 6 cm is *suitable* for laser.

  Noncontact high power Nd:YAG 50-100 W laser from distal to proximal end facilitates visualisation of lumen and also reduces the chances of perforation.

  Contact low power Nd:YAG 10-20 W laser is used for fully occluded tumour with less smoke formation and less perforation chance.

  Success rate of palliation is 85%.

  Problems are—fever, chest pain, 3% mortality, perforation (2%) and fistula formation—5%, costly, takes one week to relieve dysphagia
- **Endoscopic bipolar diathermy** using a olive tip; argon beam plasma coagulation; endoscopic alcohol injection into the tumour.
- **Endoscopic photodynamic therapy** (PDT) is used to destruct tumor and to relieve dysphagia. It is often used as a therapy in early cancer. Photosensitive haematoporphyrin agent is injected intravenously 48 hours before endoscopy. It is activated over tumour using laser. Visible infrared light also can be passed to tumour endoscopically to create tumour necrosis by released cytotoxic singlet oxygen through photosensitiser. Sunburn, fever, perforation, pleural effusions are complications. It is effective only to superficial cancers; effects will be seen only after 1 week; need to avoid direct sunlight exposure by the patient for one month is the drawback.

◆ ***Surgery***

- Transhiatal Orringer's blind oesophagectomy is a palliative surgical procedure.
- *Kirschner palliative gastric bypass* done in advanced carcinoma oesophagus wherein mobilised stomach is brought to neck via retrosternal or subcutaneous route and anastomosed to divided cervical oesophagus. Lower cut end of oesophagus is anastomosed to a jejunal loop. Here oesophagus is not addressed (left alone).

Palliative procedures

- External or intraluminal RT (Brachytherapy)
- *Traction tubes* like Celestin or MB tubes through open surgery
- *Pulsion tubes* like self-expandable metal stents through endoscopes using C-arm
- Endoscopic laser
- Chemotherapy
- Transhiatal oesophagectomy—Orringer



Fig. 19.48: *Mousseau-Barbin* tube placed as a palliative method for carcinoma oesophagus.



Fig. 19.49: *Mousseau-Barbin* tube.

Complications of oesophagectomy

- 5-10% mortality
- Haemorrhage
- Respiratory infection, often severe
- Septicaemia
- Chylothorax, injury to thoracic duct
- Anastomotic leak—thoracic leak is most dangerous (5-10%)
- Hoarseness due to recurrent laryngeal nerve palsy
- Stricture formation (40%)
- Gastro-oesophageal *reflux* in gastric transfer
- *Conduit necrosis* due to ischaemia either stomach or colon
- *Colonic dysmotility* causing partial obstruction in colon transfer

Terminal Events in Carcinoma Oesophagus

- Cancer cachexia.
- Sepsis, mediastinitis.
- Immunosuppression.
- Malignant tracheo-oesophageal fistula (causes severe respiratory infection and death. Here expansile (self-expandable) *endoluminal stents* are used at the site of fistula to have temporary benefit).
- Erosion into major blood vessel—bleeding.

Prognosis

- Not good because of early spread, longitudinal lymphatics, aggressiveness, difficult approach, late presentation.
- Nodal involvement carries bad prognosis.
- 5-year survival rate is only 10%.

BENIGN TUMOURS OF THE OESOPHAGUS

- *Benign tumours* of the oesophagus are rare (0.5-1% of all oesophageal tumours).
- It grows slowly like a balloon by expansion, compressing surrounding structures. It never infiltrates or spreads.
- It can be solid, cystic, polypoid.
- It is usually in submucosal plane.
- It can cause obstruction/regurgitation/aspiration/ mediastinal compression.
- It can be squamous papilloma/polyp/inflammatory pseudo tumour/*leiomyoma (commonest benign tumour of oesophagus—65%)*/neurofibroma/rhabdomyoma/ lipoma. True adenoma in oesophagus is very rare.
- Features may be asymptomatic (85%—identified incidentally during contrast X-ray/endoscopy); dysphagia/airway obstruction/pneumonia/spluttering during swallowing; stridor/regurgitation.
- ***Leiomyoma*** (commonest—65%) is smooth, sessile, lobulated, firm, with grey-white whorled appearance.
    - Only when leiomyoma reaches 5 cm in size it causes obstruction.
    - Multiple localised leiomyomas can occur which can be enucleated independently.
    - *True diffuse leiomyomas* can occur occasionally in females (4%) in lower oesophagus, as diffuse hyperplasia and thickening of both muscular layers; often as part of the Alport's syndrome which needs total oesophagectomy with gastric pull up, even though benign.
    - Benign leiomyoma of oesophagus rarely turns into leiomyosarcoma.
    - 90% of oesophageal leiomyomas occur in *lower third of the oesophagus.*
    - Leiomyomas are common in men in 5th decade.
    - Leiomyoma which expresses the c-kit oncogene (CD117) is considered as GIST.
- *Investigations*—barium swallow X-ray (smooth circular outline/eccentric filling defect)/oesophagoscopy/endosonography/CT scan.
- *Treatment*—if tumour is more than 5 cm/symptomatic tumour/intraluminal tumour/when diagnosis is doubtful

surgical enucleation is indicated. Enucleation is the therapy of choice. Ideally it should be done through right-sided thoracotomy. Occasionally oesophageal resection is needed if tumour is very large/tumour with mucosal ulceration/if tumour is near OG junction. Thoracoscopic resection can be done. Leak, empyema, sepsis and stricture are the occasional complications.



Figs 19.50A and B: Oesophageal submucosal tumour—endoscopic view—leiomyoma.

Note:
Unlike in the stomach and intestine (gastric leiomyoma more than 6 cm/intestinal leiomyoma more than 4 cm are potentially malignant) increased size of the oesophageal leiomyoma does not predispose the malignant transformation.

- ***Oesophageal cysts***
  - It is 2nd commonest benign tumour of oesophagus.
  - It can be congenital or acquired. Congenital is derived from foregut. It contains mucous. It is lined by ciliated columnar epithelium. In infants it is common in upper third of oesophagus; often with a fistula into airway. It can cause obstruction.
  - Acquired cyst is from obstruction of the excretory ducts of oesophageal glands.
  - *Treatment*: Enucleation or resection. If fistula is present it should be ligated and divided.

OESOPHAGEAL PERFORATION

Causes

- Instrumental injuries—commonest cause, 75% commonest site is just above the level of cricopharyngeus.
- Foreign bodies.
- Alkali injuries.
- Carcinoma oesophagus 1%.
- Boerhaave's syndrome 15%.
- Trauma 9%.
- Surgical trauma (Vagotomy, thyroidectomy, Heller's operation, pneumonectomy, spine surgery).

Clinical Features

Chest pain, vomiting, shock, subcutaneous emphysema.

Investigations

- Chest X-ray—shows pneumomediastinum.
- CT scan.

Complications

- Mediastinitis.
- Septicaemia.
- Empyema, ARDS.

Treatment

- *Conservative treatment*: It is advocated in small perforations due to instrument where there is minimal air leak and contamination of mediastinum with less septic load. Crepitus should be absent; pleura should be clear and without any obstruction. Treatment is—antibiotics, nutrition (TPN/enteral through tube), fluid management, proper observation and monitoring the patient by repeated blood counts, and imaging. Biodegradable removable self expanding stents also can be used. It may also act as a bridge therapy for eventual major surgical exploration. Stents which are used for carcinomas cannot be used as they cannot be removed.
- *Thoracotomy,* proper saline wash to pleura, mediastinum and repair with buttressing the area using *pedicled intercostal musculopleural flap is done*. Nasogastric tube for long duration, jejunostomy tube for feeding, ICT for drainage is essential. Often in late cases decortication of lung is needed to achieve full expansion of the lung.
- Repair over T tube so as to create a controlled fistula along with feeding jejunostomy and ICT on both sides.
- Intraluminal stents/mediastinal irrigation and drainage.
- Resection of oesophagus with gastric pull up. As condition is an emergency situation and with sepsis it carries high mortality.
- Oesophageal exclusion with cervical oesophagostomy above and feeding jejunostomy below.
- Diversion surgeries using colon/stomach/jejunum.

FOREIGN BODY OESOPHAGUS

Common Foreign Bodies

- Coins, metals, plastics.
- Dentures.
- Pins, toothpicks, batteries.
- Fish or meat bones—dangerous—40%.
- Food (meat—common/vegetables) impaction—45%.

Sites of Impaction in Oesophagus

- Cervical constriction—C6.
- Broncho-aortic constriction—T4.
- Diaphragmatic constriction—T10.
- Pre-existing malignancy or inflammatory stricture site.



Fig. 19.51: Foreign body in the oesophagus.

Features

- Sudden dysphagia with chest pain and breathlessness.
- Later features of shock, sepsis, mediastinitis, empyema.

Management

- X-ray shows site and level of the F/B.
- Endoscopic removal can be tried.
- Impacted large F/B should be removed by thoracotomy.
- Antibiotics, jejunostomy, TPN, ICT are also required.



Fig. 19.52: Foreign body (COIN) in the lower oesophagus. Usually it can be removed by endoscope.

Chapter 20 Stomach

CHAPTER OUTLINE

- Anatomy
  - Blood Supply of Stomach
  - Nerve Supply of Stomach
  - Histology
  - Lymphatic Drainage of Stomach
  - Duodenum
- Gastric Physiology
- Gastric Function Tests
- Gastrin
- Barium Meal Study
- Gastroscopy
- Helicobacter Pylori
- Congenital Hypertrophic Pyloric Stenosis
- Gastritis
- Acute Peptic Ulcer
- Gastric Ulcer
- Duodenal Ulcer
- Pyloric Stenosis due to Chronic Duodenal Ulcer
- Perforated Peptic Ulcer
  - Perforated Duodenal Ulcer
  - Perforated Gastric Ulcer
  - Perforated Stomal Ulcer
  - Dry Perforation
- Bleeding Peptic Ulcer
  - Bleeding Duodenal Ulcer
  - Bleeding Gastric Ulcer
- Haematemesis
- Complications of Gastric Surgery
  - Duodenal Blow Out
  - Recurrent Ulcer
  - Dumping Syndrome
  - Roux Stasis Syndrome
  - Gastrojejunocolic Fistula
- Trichobezoar
- Chronic Duodenal Ileus
- Durban's Syndrome
- Acute Gastric Dilatation
- Gastric Volvulus
- Gastric Polyp
- Menetrier's Disease
- Duodenal Diverticula
- Carcinoma Stomach
- Gastric Lymphoma
  - Primary Gastric Lymphoma
  - Secondary Gastric Lymphoma
- Gastric Sarcomas
- Gastrointestinal Stromal Tumours
- Pyloroplasty
- Gastrostomy
- Gastrectomy
- Gastrojejunostomy
- Retrograde Jejunogastric Intussusception
- Vagotomy

ANATOMY

The stomach contains four anatomic regions:

1. Fundus.
2. Cardia.
3. Body.
4. Antrum.

The *duodenum* is 20-30 cm in length. It extends from pyloric sphincter to *ligament of Treitz*. It is divided into four parts.

90% of duodenal ulcer occurs in the 1st part of duodenum (duodenal bulb/cap).

CBD and pancreatic duct merges to form *ampulla of Vater* and enter the 2nd part of duodenum. The 3rd part of duodenum is wedged between aorta and superior mesenteric artery.



Fig. 20.1: Parts of stomach.

BLOOD SUPPLY OF STOMACH

Arterial Supply

- Left gastric artery, a branch of coeliac artery (Smallest branch of coeliac axis).
- Right gastric artery, a branch of hepatic artery.
- Gastroduodenal artery, a (largest) branch of hepatic artery.
- Right gastroepiploic artery, a branch of gastroduodenal artery.
- Left gastroepiploic artery, a branch of splenic artery.
- Short gastric arteries, branches of splenic artery.



Fig. 20.2: Blood supply of the stomach.

Venous Drainage

- Right and left gastric veins drain into portal vein.
- Right gastroepiploic vein drains into superior mesenteric vein.
- Left gastroepiploic vein and short gastric veins drain into splenic vein.
- Prepyloric vein of *Mayo* distinguishes pyloric canal from the first part of duodenum.

NERVE SUPPLY OF STOMACH

- Intrinsic innervation occurs through myenteric plexus of *Auerbach* and submucous plexus of *Meissner.*
- Right vagus is posterior and left vagus is anterior.
- Posterior vagus gives *criminal nerves of Grassi*, which supply lower oesophagus and fundus of stomach, which, if not cut properly during vagotomy, may lead to recurrent ulcer.
- Vagus also gives splanchnic branches (*hepatic and coeliac branches),* ends as *nerve of Latarjet* which supplies the antrum and maintains the antral pump.
- Parietal branches help in HCl secretion, which is an important concept in vagotomy that is done as a treatment in duodenal ulcer.
- *Truncal vagotomy* with posterior gastrojejunostomy is done for chronic duodenal ulcer with pyloric stenosis.



Fig. 20.3: Anatomy of nerve supply of stomach.

- *Highly selective vagotomy* **(***HSV)* is done in case of uncomplicated chronic duodenal ulcer which is not responding to available medical line of treatment. In HSV, nerve of Latarjet is retained so as to retain antral pump and no drainage is required. Here only the fibres entering the stomach are ligated close to the lesser curve to reduce the acid secretion.
- In *selective vagotomy* splanchnic branches are retained but it is presently not done.
- Gastroduodenal pain is sensed via sympathetic fibres (T_5-T_{10}).

HISTOLOGY

- The fundus and body contains parietal and chief cells.
- *Parietal cells* secrete acid and intrinsic factor.
- *Chief cells* produce pepsinogen. There are two types of pepsinogen secreted by chief cells—I and II. Pepsinogen I is produced only in stomach. In gastric atrophy pepsinogen I is decreased.
- In the antrum, *endocrine cells* produce gastrin (G cells) and somatostatin (D cells).
- 12% of epithelial cells of stomach are parietal (oxyntic) cells; 45% chief (zymogenic cells); 40% mucous cells; 3% endocrine cells.
- Pyloric sphincter is a thick circumferential layer of smooth muscle.

- Submucosa is strongest, collagen rich layer of gastric mucosa.
- Gastric mucus is a mucosal barrier containing mucopolysaccharides which maintains the integrity of gastric mucosa.

LYMPHATIC DRAINAGE OF STOMACH

- Lymphatics of proximal half of stomach drain into left gastric, splenic, and superior pancreatic lymph nodes. From antrum, it drains into right gastric, right gastroepiploic, and subpyloric lymph nodes. From pylorus, it drains into right gastric and subpyloric lymph nodes.
- Efferent lymphatics from suprapyloric region drain into para-aortic lymph nodes and so into left supraclavicular lymph nodes. Efferent lymphatics from subpyloric lymph nodes drain into superior mesenteric lymph nodes. Lymphatics near *oesophagogastric* (OG) junction communicate with oesophageal lymphatics.
- In carcinoma stomach if upper lymphatics are blocked, retrograde spread through lower lymphatics can occur.



Fig. 20.4: Lymphatic drainage of stomach.

- Presently in carcinoma stomach different resections are classified as R0, R1, R2, R3, or D1, D2 (dissection) based on levels of lymph nodes in the abdomen in relation to the stomach. R0 is *no residual disease*; R1 is microscopic residual disease; R2 is macroscopic residual disease; R3 is inoperable.

DUODENUM

Arterial Supply

It is mainly supplied by superior and inferior pancreaticoduodenal arteries. First part also gets supply from right gastric artery, supraduodenal artery, a branch of hepatic artery.



Fig. 20.5: After passing the Ryle's tube to the stomach, air from the syringe should be infused through the tube. When auscultated gush of air into the stomach can be heard which confirms that tube tip is in the stomach.

Venous Drainage

Drains into the splenic, superior mesenteric and portal veins.

Nerve Supply

- Sympathetic from spinal segments T_8 and T_{10}.
- Parasympathetic from vagus.

Lymphatic Drainage

Drains mainly to pancreaticoduodenal nodes present along the inside of the curve of duodenum.

GASTRIC PHYSIOLOGY

- *Gastric function* is regulated by hormonal and neural methods. Hormonal mediators control function through endocrine (through release into blood), paracrine (diffusion across interstitial space) and neurocrine (diffusion across synopsed target cell and receptor binding).
- *Gastric acid secretion* is regulated by acetylcholine, histamine and gastrin. Acetylcholine is the principal mediator of acid release through vagal parasympathetic ganglion cells. Vagus innervates parietal, G and *enterochromaffin-like* (ECL) cells. Basal acid secretion is 10% of maximal acid output (1-5 mmol/hour). It is reduced by 90% after vagotomy or H_2 receptor blockage. ***Phases of acid secretion*** are—(1) *Cephalic phase*—through central meditation (smell/sight/taste → vagus → acetylcholine → muscarinic receptors. (2) *Gastric phase*—food enters the stomach → antral G cells → acid release though gastrin (gastric distension causes direct acid release). Gastric phase lasts until stomach is empty and releases 70% of total acid release. (3) *Intestinal phase*—it is 10% of acid release and is mediated by chyme entering the small bowel—nongastrin related.

- *Receptors of acid secretions* are—(1) Gastrin—CCK receptors: Two types are present in parietal cell; Gastrin CCK type A receptor has high affinity for CCK but less to gastrin; Gastrin CCK type B receptor has got high affinity for both CCK and gastrin. (2) Muscarinic receptor (parietal cell)—its M3 type is mediator for acetylcholine. (3) Histamine receptor (parietal cell)—H_2 subtype binds to histamine to cause effect. (4) Somatostatin receptor—these are 5 subtypes. Its inhibitory action is through parietal cell subtype. (5) Second messengers involved are intracellular cAMP and calcium.
- *Luminal gastric pH* is 2. The pH at surface epithelial cells is 7. These cells secrete bicarbonate continuously into the lining mucus gel to keep the pH of surface mucus at 5. Bicarbonate in mucus barrier reduces once luminal pH reduces below 1.4.
- *Functions of gastric acid*: Conversion of pepsinogen to pepsin which in turn hydrolyses proteins into polypeptides; promotes release of duodenal secretin; prevents bacterial colonisation of upper GIT; formation of food chyme which contains food particles of 1 mm size or less.
- *Gastric juice* contains HCl, mucus, swallowed saliva, reflux content from duodenum. Parietal cells secrete electrolytes of 160 mmol/L. They also secrete *intrinsic factor*, a mucoprotein which is essential for absorption of vitamin B_{12} in ileum; its secretion is independent of acid secretion from parietal cell and is not influenced by PPIs. Pepsinogen is a proteolytic proenzyme (42,000 mol wt). Type I is secreted from chief cells and mucus neck cells of only acid secreting part of the stomach (acid secreting mucosa). Type II is secreted from surface epithelial cells of entire stomach and proximal duodenum. Mucus is secreted by surface mucus cells and mucus neck cells from acid secreting area of stomach and antrum. Gel like viscous mucus contains 85% water and 15% glycoproteins. It contains bicarbonate secreted from surface epithelial cells. Mucus is strong gastric barrier. Mucus secretion is inhibited by anticholinergics and NSAIDs. *H. pylori* break the mucin and so barrier.
- *Gastric motility* begins from *pacemaker cell of Cajal* located at proximal stomach. Special myoelectric migrating complex slow waves with electric spikes maintain gastric motility in three phases. Immediately after food intake resting tone of fundus and proximal stomach decrease causing receptive relaxation and gastric accommodation mediated by vagus. Vagotomy eliminates this causing early fullness, early satiety and rapid gastric emptying. Delayed gastric motility occurs in diabetes, *H. pylori* infection and after vagotomy. Many factors like stress, hormones increase the gastric motility. Prokinetics, erythromycin helps in gastroparesis.
- *Mucosal defense factors* are—mucus production, mucosal HCO_3, mucosal blood flow, growth factors, cell renewal, endogenous prostaglandins, epithelial barrier (hydrophobic phospholipids, restitution, NO, epidermal growth factor and microcirculation). *Aggressive factors* are—*H. pylori*, HCl secretion, pepsin, smoking, alcohol, duodenal bile reflux, ischaemia, NSAIDs.

GASTRIC FUNCTION TESTS

Gastric function tests

- Pentagastrin test/Kay's augmented histamine test
- Hollander's insulin test
- Radioisotope labelled gastric emptying study
- 24 hours intragastric pH monitoring
- Gastrin level estimation

Peak Acid Output Test (Pentagastrin/Augmented Histamine Test)

Initially stomach is emptied completely. Basal acid level of aspirated stomach content (aspiration is done for 1 hour on empty stomach) is analysed. Pentagastrin—6 µgm/kg or histamine 2 µgm/kg is injected IV/SC/IM and 15 minutes samples for subsequent hours (usually 1 hour) are collected and analysed. Peak acid output level is calculated. Test is useful in Zollinger-Ellison (Z-E) syndrome, duodenal ulcer and gastric ulcer. Basal acid output (BAO) is 2-3 mEq/hour. Peak acid output (PAO) is highest rate of secretion obtained in any of the 15 minutes samples following stimulation. Maximal acid output (MAO) is obtained by averaging the output of two final 15 minutes samples. In duodenal ulcer and Z-E syndrome basal and stimulated acid is increased; in pernicious anaemia, gastric atrophy and gastric cancer both are decreased.

	Basal	*Peak*
Normal	5 mmols	25-27
Gastric ulcer	2	15
Duodenal ulcer	6	35-38
Z-E syndrome	Very high	> than 60

Achlorhydria is defined as a condition in which stomach cannot produce secretions with a pH of less than 7.0 even after maximal stimulation. It is seen in 20% of carcinoma stomach.

Note:
Achylia means—no pepsin in the gastric juice.

Insulin Test (*Hollander*)

- This test is useful postoperatively to confirm the completeness of vagotomy. 0.2 units/kg body weight of insulin is injected intravenously to a fasting patient so as to create hypoglycaemia of below 35 mg%, which in turn stimulates the parietal cells through hypothalamus and through vagus to cause increased acid secretion. Patient who had undergone complete vagotomy does not show increase in acid secretion.
- *Early response* signifies incomplete vagotomy wherein there is increase in acid concentration in first hour of > 20 mmols/L.
- *Delayed response* signifies an increase in acid concentration in between first and second hours, and is probably due to vagal gastrin release.

GASTRIN

- Gastrin is secreted by the G-cells from gastric antrum.
- *Types of gastrin* are—*Big gastrin* (G_{34}); *little gastrin* (G_{17})—most common 90%; *mini gastrin* (G_{14}). Pentapeptide at the C terminal end of G_{17} is active part which is identical to CCK. Luminal peptides and amino acids are most potent stimulator of gastrin release. Luminal acid is the most potent inhibitor of gastrin release.
- *Gastrin promotes* the release of acid and also regulates it. It also maintains mucosal defense, has trophic effects on parietal and ECL cells (enterochromaffin like cells).
- Number of G-cells are increased in duodenal ulcer, G-cell hyperplasia, but not in gastric ulcer. Normal plasma value is 50 ng/L of plasma (fasting). It is analysed by radioimmunoassay.
- It increases to many 1000's in gastrinomas.
- *Hypergastrinaemia* can occur in *ulcerogenic conditions* like—antral G cell hyperplasia, retained excluded antrum, Z-E syndrome, short gut syndrome, gastric outlet obstruction; *nonulcerogenic conditions* are—PPIs, pernicious anaemia (–ve feedback), vagotomy, atrophic gastritis (hypochlorhydria), *H. pylori*, chronic renal failure.
- Gastrin is raised very high in *gastrinomas*.

Gastric hormones

- *Gastrin*
- *Somatostatin*—2 types, 14 and 28. In stomach, type 14 is common; from D cells of gastric mucosa of fundus and antrum. Antral acidification is the main stimulus; vagal acetylcholine inhibits its release. It has *paracrine* effect inhibiting acid secretion from parietal cell, gastrin release from G cell and histamine release from ECL cell. *H. pylori* decrease antral D cells and so somatostatin, leading into increased gastrin release
- *Gastrin releasing polypeptide* (GRP, Bombesin)—it stimulates gastrin and somatostatin release by binding to receptors on G and D cells. It is released from sympathetic nerve terminals of the gastric mucosa of body and antrum. Its half life is 1½ minutes
- *Histamine* is stored in ECL and mast cells. Its release is stimulated by gastrin, acetylcholine and epinephrine
- *Gherlin* (28 amino acids) is mainly secreted from endocrine cells of gastric mucosa. It has mainly got growth hormone releasing action; prolactin, ACTH, cortisol, aldosterone release is also promoted. Its action on islet cells reduces insulin release. *Gherlin* stimulates appetite. Gastric bypass, gastrectomy reduces the appetite.

Investigations for gastroduodenal diseases

- Gastroduodenoscopy is ideal and most common investigation used to visualise mucosa. Lesions if any biopsy is taken for *H. pylori* and carcinoma. Also often used for endotherapy
- Endosonography (EUS) is very sensitive method to assess tumours, visualise stomach layers (90% accuracy), lymph nodes (80%), and to detect early liver metastasis which may not be identified by CT especially from left lobe
- CT scan is good imaging method to detect the stage, spread, nodal status, liver secondaries, and status of lungs
- CT and PET scan (together) using FDG is better to assess early spread
- Laparoscopy is very good investigating tool to identify peritoneal secondaries, and to stage the disease. Laparoscopic US is very sensitive to detect the liver secondaries
- Barium meal studies are used to detect hiatus hernia
- Celiac angiography is useful in bleeding ulcers, both for diagnostic and therapeutic purpose (therapeutic embolisation)

BARIUM MEAL STUDY

Indications

1. Gastric ulcer—shows a *niche* which is the ulcer crater, a *notch* which is due to spasm of circular muscle on the greater curvature.
2. Chronic duodenal ulcer—shows absence or deformed duodenal cap (due to spasm of 1st part of duodenum, barium will not stay and so cap will not be formed).
3. Gastric outlet obstruction—the cause may be chronic duodenal ulcer with pyloric stenosis or carcinoma pylorus. Features are:
    - Enormous dilatation of stomach.
    - Greater curvature below the level of iliac crest.
    - Absence of duodenal cap.
    - No filling of dye in 2nd part of duodenum.
    - Mottled appearance of stomach because of retained food particles.
    - Evidence of gastritis.
4. Carcinoma stomach—irregular filling defect.



Fig. 20.6A

The stomach you can hear, the stomach you can see, the stomach you can feel.—**Sir James Walton**



Fig. 20.6B

Figs 20.6A and B: Barium meal X-rays showing normal picture in one and dilated stomach with features of gastric outlet obstruction in another.

5. Pseudocyst of pancreas—widened vertebrogastric angle.
6. Stomal ulcer in previous gastrojejunostomy.
7. In chronic duodenal ileus (*Wilkie's syndrome)*—shows dilatation of stomach, 1st and 2nd part of duodenum, proximal portion of 3rd part of duodenum.
8. Others—gastric volvulus, duodenal diverticula, trichobezoar, gastric fistulas, diaphragmatic hernias when stomach is the content.
9. Carcinoma of head of pancreas shows "*pad sign"*; in periampullary carcinoma—*reverse "3'* sign.
   Frostberg's reverse '3' sign (inverted '3' sign).
   Rose thorn duodenum in carcinoma head of pancreas.
10. Hiatus hernia.

Procedure

- Barium sulphate solution is used [Barium is neurotoxic, but in sulphate media it will not get absorbed and so barium sulphate is used (Barium phosphate is not used)].
- About 300 ml solution is given to the patient to drink and its flow down to the stomach is observed under fluoroscopic guidance. Films are taken as required. Commonly oblique views are taken.
- Microcrystalised barium sulphate (*Microbar solution*) is better as it does not get precipitated.

Complication

It may precipitate intestinal obstruction.

GASTROSCOPY

It is visualisation of interior of stomach, duodenum, oesophagus. It can be done as OP procedure.



Fig. 20.7: Technique of doing gastroscopy using videoendoscope.

Uses

1. *For diagnosing any pathology,* e.g.
   - Gastric ulcer.
   - Duodenal ulcer.
   - Gastritis.
   - Stomal ulcer.
   - Carcinoma stomach.
   - Oesophagitis.
   - Varices.
   - Biopsies from the suspected cases of malignancy or for *Helicobacter pylori* can be taken.
     - ***Endosonography*** can be done to assess the staging, operability of carcinoma stomach or oesophagus.
     - Presently fibreoptic, flexible, or video gastroduodenoscopy is used.
2. *Therapeutic*
   - ***Videoendoscopy*** is used not only for diagnosis but also mainly for therapeutic procedures.
   - Both end viewing and side viewing gastroscopes are available.
   - For therapeutic procedures and ERCP, side viewing gastroscope is required.

Therapeutic procedures done are:

- Variceal injection or ligation or glueing or banding
- Stenting of pseudocyst of pancreas through gastroscopy
- Polyp removal
- Submucosal resection
- For ERCP diagnostic and therapeutic procedures
- Percutaneous gastrostomy (PEG)

Procedure

Gastroscopy is done following eight hours of fasting. After lignocaine spray into the oral cavity, gastroscope is passed gently down the oesophagus when the patient does the swallowing action. Once the scope is inside the stomach, air is



Fig. 20.8: Gastroscopic views of different parts—vocal cords; pyriform fossa; oesophagus; oesophagogastric (OG) junction; body, fundus and pylorus of stomach, duodenum with clearly visible duodenal papilla (*Courtesy:* Dr Tantry and Dr Sandeep Gopal, Gastroenterologists, KMC, Mangalore).

inflated and different parts of the stomach is visualised. Fundus is visualised by retropulsion. Scope is passed through the pylorus to see the 1st and 2nd parts of duodenum and looked for any pathology. If required biopsy is taken.

Often sedation with midazolam is beneficial to have an easy passage.

- *Buscopan is used to relax stomach wall.*
- *Z-line signifies squamocolumnar junction.*
- *Multi-byte biopsy forceps is used.*



Fig. 20.9: Endosonography of stomach showing different layers with echogenicity.

Complications

- Bleeding.
- Aspiration.
- Perforation (rarely). Perforation occurs mainly in therapeutic procedures like oesophageal dilatation, endoscopic mucosal resection (EMR). It is common in proximal and middle oesophagus but can occur anywhere. Patient presents with hypotension, tachycardia, sudden severe pain in chest, abdomen, neck and surgical emphysema.

HELICOBACTER PYLORI

- It is gram –ve spiral like flagellated organism, first studied by Warren and Marshall (both got Nobel prize), which is commonly present in stomach. It is involved in pathogenesis of duodenal ulcer, gastric ulcer, gastritis (type B) and gastric cancer.

H. pylori

- Duodenal ulcer—95%
- Gastric ulcer—70%
- Gastritis—70-90%
- Gastric cancer—No. 1 carcinogen
- Gastric MALTOMA (mucosa associated lymphoid tissue lymphoma)

Pathogenesis

- It is the most common bacterial infection in the world. Rhesus monkey is the only natural reservoir. Its incidence increases with age.
- It releases enzymes like *urease* that hydrolyses urea so as to release ammonia which through negative feedback mechanism increases the gastrin release from G-cells.
- Infection occurs in stomach, i.e. body, fundus, antrum, disrupts the mucosal barrier, causes chronic inflammatory response leading to gastritis, gastric ulcer.
- Other than urease it also secretes dehydrogenase (converts alcohol to aldehyde which is toxic to mucosa), endopeptidase (disrupts mucosal barrier). Urease creates alkaline environment around it in mucus layer of gastric epithelium.

Control of *H. pylori* Infection

It is treated with antibiotics and other drugs with different combinations		
Clarithromycin 500 mg BD	Metronidazole 400 mg BD	Omeprazole 20 mg BD
OR	OR	OR
Amoxycillin 500-750 mg BD	Tinidazole 600 mg BD	Lansoprazole 30 mg BD
OR		OR
Tetracyclines, or Bismuth.		Pantoprazole 40 mg BD
The above regime is given for 7-14 days and then only proton pump inhibitors are continued.		

It can survive only in gastric epithelium or gastric metaplasia in duodenum or Barrett's oesophagus or in heterotopic gastric mucosa in Meckel's diverticulum or rectum. It is because receptors for organisms to adhere into mucosa are available only in gastric mucosa.

- *H. pylori* impair mucosal healing, cause degranulation of eosinophils. It releases various protease and lipases that break mucus and so strong protective mucus barrier.
- It also secretes ***cytotoxins*** (cagA and vacA) which may also be involved in inflammatory reaction or malignancy.
- Even though normal duodenum cannot harbour the *Helicobacter*, duodenum with gastric metaplasia can very well get infected by *Helicobacter* which explains why *Helicobacter* is involved in duodenal ulcer.
- *Helicobacter* is normally not found in saliva.
- Infection is transmitted through faeco-oral route, with a infection rate of 80-90% in a population (common and high).
- It is more common in lower socioeconomic group.
- It is considered to be a ***carcinogen for stomach***. It is not linked with carcinoma of OG junction.

Enzymes and toxins released by *H. pylori*

- *Urease*
- Dehydrogenase
- Endopeptidase
- *Vacuolising cytotoxin*
- Haemolysin
- *cagA and vacA*

It is identified by:

a. *Rapid urease test* (cod liver oil test/CLO test)
b. C13-C14 breath tests (labelled urea breath test)
c. Biopsy from the different parts of the stomach and staining to identify the organism.

For *H. pylori* three biopsies are taken one each from antrum, body and fundus.

Tests for *H. pylori*

- Rapid urease test—90% sensitivity, 98% specificity
- C13/ C14 breath tests—95% sensitivity and specificity—'gold standard'
  - C13 requires spectrometry and costly
  - C14 uses radioactivity
- Serology to identify IgG antibody—ELISA test with 90% sensitivity and specificity
- Biopsy and culture—very costly
- *Warthin's starry silver stain*, acridine orange are special stains used
- *Newer methods* – special fluorescent technique, PCR products of *H. pylori*—urease gene, 165 rRNA identified using specialised probes when organisms are in less number

CONGENITAL HYPERTROPHIC PYLORIC STENOSIS

It is hypertrophy of musculature of pyloric antrum, especially the circular muscle fibres, causing primary failure of pylorus to relax. Duodenum is normal.

Clinical Features

- Common in first born *males* (4:1).
- Incidence is 4 in 1000 births.
- It is familial.
- It is seen between 3rd and 6th weeks of age of an infant, the time taken by the hypertrophied muscle to cause complete obstruction.
- Vomiting—forcible, projectile and non-bilious.
- Visible gastric peristalsis (VGP).



Fig. 20.10: Visible gastric peristalsis.

- Palpable lump of hypertrophied pylorus which is better felt from left side, as a mobile, smooth, firm mass, with all borders well made out, moves with respiration, with impaired resonance on percussion. It is the most important clinical feature (95%).
- Constipation.
- Dehydration and loss of weight.
- Electrolyte imbalance—hypokalaemic metabolic alkalosis.

Clinical features of congenital pyloric stenosis

- Vomiting
- VGP
- Palpable mass
- Constipation and dehydration

In premature infants:

- VGP and mass is better seen and felt.
- Vomiting is regurgitant.
- Anorexia is common.

Diagnosis is established by:

- Clinical examination.
- U/S abdomen (very useful)—*Doughnut sign.*
  - Pyloric muscle 4 mm or more in thickness.
  - Length of pyloric canal > 1.8 cm.
- Barium meal shows obstruction.

Differential Diagnosis

- Duodenal atresia (Bilious vomiting is present).
- High intestinal obstruction (e.g. volvulus neonatorum).
- Intracranial haemorrhage.

Treatment

1. Correction of dehydration and electrolyte imbalance.
2. ***Surgery***: *Ramstedt's operation*—After laparotomy, hypertrophied muscle is cut along the whole length adequately until the mucosa bulges out. Mucosa should not be opened (pyloromyotomy). If mucosa is injured, it should be sutured horizontally using interrupted vicryl or silk sutures.



Fig. 20.11: Ramstedt operation for congenital hypertrophic pyloric stenosis. Note that here muscular layer is cut but not mucosal layer.

Complications of surgery

- Postoperative pyrexia (Hyperthermia).
- Gastroenteritis
- Electrolyte imbalance

3. ***Medical treatment***: Not advisable as cure is not guaranteed. Atropine methyl nitrate orally is tried to relax the pylorus muscle.



Figs 20.12A to C: *Ramstedt pyloromyotomy* for congenital hypertrophic pyloric stenosis. Only muscular layer is cut to allow mucosa to bulge out.

GASTRITIS

Types

1. Type A gastritis.
2. Type B gastritis.
3. Reflux gastritis.
4. Erosive gastritis.
5. *Others*: Stress gastritis, lymphocytic gastritis, granulomatous gastritis, phlegmonous gastritis.

Troubles waste the stomach like rust waste iron.—**Croatian proverb**

Type A Gastritis

- Autoimmune disease.
- There is formation of antiparietal cell antibodies.
- Parietal cell dysfunction occurs causing achlorhydria and vitamin B_{12} deficiency.
- Antrum is not affected.
- 'G' cell hyperplasia occurs with raised serum gastrin level.
- There is formation of microadenoma of enterochromaffin like cells (ECL cells) with predisposition to gastric carcinoma.

Type B Gastritis

- Occurs due to *Helicobacter pylori* infection.
- Antrum is affected.
- Peptic ulcer is common.
- *Helicobacter* related pangastritis commonly occurs which may turn into gastric cancer.

Reflux Gastritis

- Usually occurs after gastric surgeries.
- Prokinetic drugs are useful—metochlopramide, domperidone, cisapride, mozapride.

Erosive Gastritis

- *Occurs due to disturbed gastric mucosal barrier.*
- Induced by NSAIDs/alcohol.
- Due to inhibition of cyclo-oxygenase type 1 (COX-1) receptor enzyme, resulting in decreased prostaglandin production (Prostaglandin is cytoprotective).
- COX-2 mediated NSAIDs will not cause erosive gastritis.



Fig. 20.13: Endoscopic view of erosive gastritis.

Stress Gastritis

Treatment:

- IV ranitidine 50 mg 8th hourly.
- IV omeprazole/pantoprazole.
- Sucralfate orally.

Lymphocytic Gastritis

It is associated with *H. pylori* infection.

Granulomatous Gastritis

It is seen in Crohn's disease and tuberculosis.

Phlegmonous Gastritis

It is due to severe bacterial infection of stomach. It is rare but dangerous.

Nonulcer dyspepsia

- Symptom complex with pain and discomfort in the upper abdomen
- It is intermittent upper abdomen pain in the absence of peptic ulceration
- It occurs in 25% of population—large number
- Anatomical or biochemical abnormalities are not discovered in this condition
- *H. pylori* is not associated with this condition
- Often it lasts for long time decreasing the quality of life
- Differential diagnosis – GERD/acid peptic diseases/gallstones/pancreatitis/carcinoma
- *H. pylori* eradication is not required and there is no surgical role

ACUTE PEPTIC ULCER (DUODENAL OR GASTRIC ULCER)

They are usually multiple erosions due to disruption of the mucosal barrier.

Causes

Stress, drugs like analgesics, steroids, surgeries.

Clinical Features

- Sudden onset of acute pain and tenderness in epigastric region.
- Vomiting with or without haematemesis.
- Often acute peptic ulcers can lead to perforations.
  - Acute ulcers after cerebral trauma or neurosurgeries are called *as Cushing's ulcers*.
  - Acute ulcers after major burns are called *as Curling's ulcers*.

Diagnosis is by gastroscopy.

Treatment

- Intravenous ranitidine 50 mg, 8th hourly.
- IV fluids. IV pantoprazole/rabeprazole/omeprazole.
- Blood transfusions if there is bleeding.

Most of the time surgery is not required for acute ulcers. During follow-up patients are advised to take antiulcer drugs for 4-6 weeks—ranitidine, omeprazole or lansoprazole.

Curling's Ulcers

They are acute ulcers which develop after major burns, presenting as pain in epigastric region, vomiting or haematemesis. Treatment is conservative—IV ranitidine. IV pantoprazole 80 mg in 100 ml DNS—slow, later 40 mg IV maintenance.

Note:
Curling's ulcer occurs when burn injury is more than 35%. It is observed in the body and fundus not in antrum and duodenum.

Cushing's Ulcers

They are acute ulcers which develop after cerebral trauma or after neurosurgical operations. It is commonly single, deeper ulcer more frequently perforates. It can occur in oesophagus and duodenum also. Treatment is conservative by IV ranitidine.

GASTRIC ULCER

Aetiology

It occurs due to imbalance between protective and damaging factors of gastric mucosa.

- Atrophic gastritis, duodenogastric bile reflux, gastric stasis, abnormalities in acid and pepsin secretion. Acid becomes ulcerogenic even to normal gastric mucosa.
- Smoking, alcohol, NSAIDs, steroids.
- *Helicobacter pylori* infection (70%).
- There is either normochlorhydria or hypochlorhydria.
- Altered mucosal barrier mechanism.
- Lower socioeconomic group.

Factors Involved in Gastric Ulcer Formation

- Duodenogastric reflux—reflux containing bile salts and lysolecithin break the mucosal barrier making it more vulnerable for injury, action of drugs and pepsin injury.
- Gastric stasis.
- Ischaemia of the gastric mucosa.
- Type II and III gastric ulcers show acid hypersecretion.

Pathology



Fig. 20.14: Specimen of stomach (identified by the mucosal pattern and rugae) showing deep ulcer near lesser curvature. Margin of the ulcer is clear, not everted with gastric mucosal folds converging towards the base of the ulcer. 95% of benign gastric ulcer occurs towards lesser curve. Benign gastric ulcer is more common in lesser curvature, as it takes more burden of passage of food and so more of wear and tear. Benign gastric ulcer is rare in greater curvature, fundus and cardia. Histologically it shows destruction of epithelial lining; proliferation of margin; destruction of the part of the muscle layer; granulation tissue in the floor; infiltration with chronic inflammatory cells; endarteritis and fibrosis in the base.

- Gastric ulcer is large in size, usually lies in the lesser curvature, its floor being formed by the muscular layer.
- Posteriorly it may penetrate into the pancreas; it may cause torrential bleeding by eroding left gastric (commonly) vessles or splenic vessels or vessels in the gastric ulcer wall.
- Anteriorly it may perforate or penetrate into the liver. It may lead into *hour glass contracture, or tea-pot deformity*.
- Microscopically, it shows ulcer crater with chronic inflammatory cells and granulation tissue, endarteritis obliterans and epithelial proliferation.
  (Ulcer to the right of the incisura is malignant unless proved otherwise).
- Gastric ulcer > 3 cm is called as giant gastric ulcer. It has got 6-23% chances to turn into malignancy.
- Grossly, margin of the benign gastric ulcer is clear; deep; near lesser curve; edge is not everted with gastric mucosal folds *converging* towards the base of the ulcer.
- 95% of benign gastric ulcer occurs towards lesser curve, as it takes more burden of passage of food and so more of wear and tear. Benign gastric ulcer is rare in greater curvature, fundus and cardia.
- **Acute ulcer**: It is confined to mucosa and submucosa. It is commonly due to NSAIDs.
- **Chronic ulcer:** It penetrates muscularis layer of stomach.

Clinical Features

- Equal in both sexes. It is becoming more common in females.
- Common after the age of 40 years.
- *Pain* in epigastric region after taking food, lasting up to two hours. Pain is uncommon during night. It is relieved by vomiting or by inducing vomiting.



Fig. 20.15: Types of gastric ulcer (*Daintree Johnson*).

- *Periodicity*: Symptom free interval may be 2-6 months. Often with seasonal variation.
- *Vomiting* relieves pain and often it is induced by the patient for relief of pain.
- *Haematemesis and melaena*: Haematemesis is more common.
- Appetite is good but hesitant to eat, because eating induces pain and that results in loss of weight. But once complica-

It is consequences which are more important than rewards or punishments.

Types of gastric ulcer (Daintree Johnson)

Type	*Location*	*Incidence*	*Acid level*
Type I	In the antrum, near the lesser curve	55%	Normal
Type II	Combined gastric ulcer (in the body) with duodenal ulcer	25%	High
Type III	Prepyloric ulcer	15%	High
Type IV	Gastric ulcer in the proximal stomach or cardia	5%	Normal

tions occur, appetite decreases. Aversion to spicy, fried foods occurs.

- On deep palpation, tenderness is felt in epigastric region.

Note:
Often in lesser curve, saddle shaped ulcer can occur.

Differential Diagnosis

- Hiatus hernia.
- Cholecystitis.
- Chronic pancreatitis.
- Chronic gastritis.
- Dyspepsia.
- Carcinoma stomach.



Fig. 20.16: Barium meal showing *Niche* in the lesser curve as benign gastric ulcer.

Investigations



Fig. 20.17: Benign gastric ulcer endoscopic view. Biopsy is a must. Ideally 10 biopsies should be taken from the edge.

- Barium meal X-ray to see *niche and notch.*

Barium meal X-ray features of benign gastric ulcer

- *Niche* on the lesser curve with *notch* on the greater curvature
- Ulcer crater projects beyond the lumen of the ulcer
- Regular/round margin of the ulcer crater—*stomach spoke wheel pattern*
- Overhanging mucosa at the margins of a benign gastric ulcer—projects inwards towards the ulcer—*Hamptom's line*
- Converging mucosal folds towards the base of the ulcer
- Symmetrical normal gastric mucosal folds

- Gastroscopy is done to see the location, type of ulcer and also to take biopsy (10 biopsies).
- US abdomen mainly to rule out other diseases and to confirm associated diseases.



Fig. 20.18: Gastric ulcer in prepyloric region.



Fig. 20.21: Gastric ulcer in the body of the stomach.



Fig. 20.19: Multiple ulcers visualised on gastroscopy.



Fig. 20.20: Multiple gastric ulcers on endoscopy.



Fig. 20.22: Barium meal study showing *niche and notch*—gastric ulcer.

Treatment

- Drugs like H_2 blockers, proton pump inhibitors, carbenexolone (Biogastrone, Sucralfate, prostaglandins which coats the ulcer and so creates a mucosal barrier) helps in reducing or eliminating the symptoms.
- But asymptomatic ulcer may exist silently and may turn into malignancy.
- ***So surgery is the preferred line of treatment. Partial gastrectomy and Billroth I gastroduodenal anastomosis is done.***
- Type IV proximal gastric ulcer is difficult to manage. It is treated by subtotal gastrectomy. Often distal gastrectomy with selective sleeve like extension cut along the lesser curve to remove the ulcer is done—*Pauchet's procedure.*
- *Other surgical procedures:*
  1. *de Miguel's antrectomy*: Distal antrectomy, pylorectomy with excision of ulcer along with gastroduodenal anastomosis is done. It preserves gastric reservoir function, shows less recurrence rate and less operative morbidity.
  2. *Mak's pylorus preserving gastrectomy*: Hemigastrectomy with excision of pyloric ulcer but retaining 2 cm prepyloric stomach. It is only used in type I gastric ulcer. Even though it has got fewer incidences of postoperative diarrhoea and dumping, it has got high recurrence rate.

3. *HSV with excision of ulcer.*
4. *Kelling Madlener procedure*: It is antrectomy and excision of proximal gastric ulcer Type IV.
5. *Csendes procedure*: It is subtotal gastrectomy with sleeve extended resection along the lesser curve for type IV proximal gastric ulcer.

Complications of Gastric Ulcer

1. ***Hour glass contracture***: It occurs exclusively in ***women***, is due to cicatricial contracture of lesser curve ulcer.
   - Here stomach is divided into two compartments.



Fig. 20.23: Hour glass contracture.

   - *Clinical features*
     - Loss of periodicity.
     - Persistent pain.
     - Vomiting.
     - Loss of appetite and weight.
   - *Diagnosis*
     - *Barium meal*: It shows filling only in the proximal stomach or double pouched stomach.
     - Gastroscopy.
   - *Treatment*

     Partial gastrectomy wherein gastric ulcer with lower compartment of the stomach is removed and Billroth I anastomosis is done.
2. ***Tea-pot deformity* (Hand-bag stomach):** It is due to cicatrisation and shortening of the lesser curvature.
   - They present with features of pyloric stenosis.
   - Treatment is partial gastrectomy with Billroth I anastomosis.



Fig. 20.24: Tea-pot deformity.

3. ***Perforation***—most frequent.
4. ***Bleeding*** *by erosion into the left gastric and rarely splenic vessels or to vessels in the wall of ulcer*—35%. It is common in type II and III gastric ulcers.
5. ***Penetration*** *posteriorly into pancreas, anteriorly into liver.*
6. ***Malignant*** *transformation usually into* ***adenocarcinoma of stomach (2-5%)***.

DUODENAL ULCER

Aetiology

- Common in people with blood group O +ve.
- Stress, anxiety—'*hurry, worry, curry*'.
- *Helicobacter pylori* infection is an important aetiology for duodenal ulcer (90%).
- NSAIDs, steroids.



Fig. 20.25: Anatomical location of chronic duodenal ulcer.

- Endocrine causes: Zollinger-Ellison syndrome, MEN syndrome, hyperparathyroidism.
- Other causes: Alcohol, smoking, vitamin deficiency.
- *Dragstedt dictum*: "No acid – No ulcer".

Pathology

- Ulcer occurs in the first part of duodenum, usually with in the first inch,involving the muscular layer.

  Sites:
  a. In the bulb (bulbar)—95%.
  b. Post-bulbar (5%).
- Eventually it shows cicatrisation causing pyloric stenosis. Serosa overlying the site of duodenal ulcer shows petechial haemorrhages with speckled red dots, appearing like sprinkled *cayenne pepper*.



Fig. 20.26: Serosal surface in a chronic duodenal ulcer. It appears like *cayenne pepper*.

	Benign gastric ulcer	*Malignant gastric ulcer*
Mucosal folds	Converging mucosal folds upto the margin	Effacing mucosal folds
Site	95% lesser curve	Greater curvature
Margin	Regular margin	Irregular margin
Floor	Granulation tissue in floor	Necrotic slough in floor
Edge	Not everted; punched or sloping	Everted edge
Surrounding area	Surrounding area and rugae are normal	Surrounding area shows nodules, ulcers and irregularities
Size and extent	Small, deep up to part of muscle layer	Large and deep

- Microscopically, ulcer with chronic inflammation with granulation tissue, gastric metaplasia of duodenal mucosa, endarteritis obliterans are visualised.
- Sometimes two opposing ulcers, i.e. over anterior and posterior surfaces of duodenum are present and are called as *kissing ulcers*.
- An anterior ulcer *perforates* commonly, posterior ulcer *bleeds or penetrates* commonly.

Clinical Features

- In India, ratio of duodenal ulcer to gastric ulcer is 30 : 1. A very high incidence.
- It is common in all socioeconomic group, more with stressed professionals (Type A personality).
- *Pain* is more before food, in early morning and decreases after taking food. It is classically called as ***hunger pain*** as it is relieved by taking food. Night pains are common.
- Common *in males*.
- *Periodicity* is more common than in chronic gastric ulcer with seasonal variation.
- *Water-brash, heart burn, vomiting* may be present.
- *Melaena* is more common, *haematemesis* also can occur.
- Appetite is good and there is gain in weight. It decreases once stenosis develops.
- Eats more frequently without any restriction.
- Chronic duodenal ulcer can ***be uncomplicated or complicated.***

Differences between clinical features of gastric ulcer and duodenal ulcer

Gastric ulcer	*Duodenal ulcer*
Pain after food intake	Pain before food intake
Periodicity less common	Periodicity more common
Haematemesis more common	Malaena more common
Weight loss occurs	Weight gain occurs
Equal in both sexes	Common in males

Complications of Duodenal Ulcer

1. Pyloric stenosis: Due to scarring and cicatrisation of first part of the duodenum.
2. Bleeding (10%).
3. Perforation (5%). Both acute and chronic ulcers can perforate. Anterior ulcers perforate.
4. Residual abscess.
5. Penetration to pancreas.

Note:

- Chronic duodenal ulcer will not turn into malignancy.
- Ulcer which is more than 2 cm is called as *giant* duodenal ulcer.

Investigations

- Barium meal X-ray shows deformed or absence of *duodenal cap* (because of spasm). Appearance of *'trifoliate'* duodenum is due to secondary duodenal diverticula which occurs as a result of scarring of ulcer.



Fig. 20.27: Absence of duodenal cap—chronic duodenal ulcer.

- Gastroscopy reveals the type, location of ulcer, narrowing if any. Biopsy also can be taken to look for the presence of *Helicobacter pylori*. Usually biopsies are taken from duodenum, pylorus, antrum, body, fundus, and confirmed by rapid urease test or C13 or C14 breath tests.
- Estimation of serum gastrin level, serum calcium level.

Differential diagnosis

- Carcinoma stomach (pylorus)
- Dyspepsia due to other causes
  - Hiatus hernia
  - Oesophagitis
  - Cholecystitis
  - Chronic pancreatitis

Patients with peptic ulcer were regularly "milked" for acid, which was used for patients suffering from hypochlorhydria.
— Albert E Coates



Fig. 20.28: Endoscopic view of duodenal ulcer.



Fig. 20.29: Chronic duodenal ulcer, gastroscopic view.

Treatment

Aim of therapy:

To *relieve* symptoms; to heal ulcer; to prevent recurrence.

I. ***General measures:***
   - Avoid alcohol, NSAIDs, smoking, spicy foods. Have more frequent food.

II. ***Specific measures*:**
   - Intragastric pH should be maintained above 5.

Drugs

1. *H_2 Blockers:*
   - Promotes ulcer healing in 4-8 weeks, by reducing acid secretion.
     - Tab cimetidine.
     - Tab ranitidine (300 mg HS or 150 mg BID), (IV preparation is available).
     - Tab famotidine (IV is available) *Most potent H_2 blocker*. Dose is 20-40 mg/day.
     - Tab roxatidine.
     - Tab nizatidine.
2. *Proton pump inhibitors*:
   - Inhibit parietal cell H^+, K^+ ATPase enzyme responsible for acid secretion. They are used for 6-12 weeks. They stop acid secretion completely.
     - Omeprazole 20 mg OD 1 hour before food—IV preparation is available.
     - Esomeprazole 40 mg.
     - Lansoprazole 30 mg.
     - Pantoprazole 40 mg—IV preparation available.
     - Rabeprazole 20 mg—IV preparation available.
3. *Antacids*:
   - Neutralises the HCl to form water and salt and also inhibits peptic activity.
   - Aluminium hydroxide and magnesium trisilicate are commonly used.
   - Dose is 2 gram 2 hours *after food*.
   - Aluminium hydroxide causes constipation, magnesium trisilicate causes diarrhoea. Osteomalacia, milk alkali syndrome, rebound ulcer due to gastrin release are other complications.
4. *Sucralfate*
   - It is an aluminium salt of sulfated sucrose which provides a protective coat to ulcer crater thereby promotes healing. It inhibits peptic activity.
   - It binds to ulcer bed and stays for 12 hours; prevents back diffusion of hydrogen ion; raises endogenous prostaglandin level in tissues; binds bile acid and pepsin; prevents colonisation of gastric mucosa by bacteria.
   - Dose is 1 g qid for 6 weeks (Before food). It is an effective drug.
5. *Anti-Helicobacter pylori regime*:
   - It is very useful, given for 7-14 days—later the proton pump inhibitors are continued.
   - *Triple or quadruple* (tetracycline, bismuth, tinidazole, pantoprazole) regimes are used.
6. *Colloid bismuth sulphate* is a good drug for ulcer, but it stains the oral cavity and mucosa.
7. Misoprostol (200 mg tid) is the only prostaglandin agonist accepted.
   - PG E1 (mesoprostol) and E2 increase mucus and bicarbonate secretion, improves mucosal blood flow, but reduces acid secretion.

Follow-up gastroscopy is a must, to confirm that ulcer has healed.

***Note*:**

Antacids and H_2 blockers should not be used along with PPI as these drugs will reduce the action of PPIs by creating alkaline media.

Surgery for Uncomplicated DU

Indications for surgical intervention for chronic DU (Uncomplicated DU):

1. Uncomplicated DU, not responding to drug therapy of 8-12 weeks—**intractable duodenal ulcer**
2. Repeated recurrences
   Presently most of the uncomplicated DU does not require surgery

- *Highly selective vagotomy (HSV).*
  - In HSV, only fibres supplying the parietal cells are ligated. Nerve of Latarjet which supplies the antrum

Anti-Helicobacter regime (Triple regime)		
Clarithromycin 500 mg BD	Metronidazole 400 mg BD	Omeprazole 20 mg BD
OR	OR	OR
Amoxycillin 500-750 mg BD	Tinidazole 600 mg BD	Lansoprazole 30 mg BD
OR		OR
Tetracyclines, or Bismuth, etc.		Pantoprazole 40 mg BD

pump is retained and so no drainage procedure is required in HSV. HSV is also called *as parietal cell vagotomy or superselective vagotomy*. Here nerve fibres in last 6 cm of stomach, just proximal to pylorus are preserved (Crow's foot). Vagotomy reduces acid secretion, hence ulcer heals. *No acid, No ulcer*.

  - HSV was first described by *Amdrup and Johnston* in 1969.
  - Distal 6 cm oesophageal nerve fiber clearance is essential. Fibers up to 6 cm proximal to pylorus in stomach are cleared; nerve of Latarjet is preserved; adequate distal greater curve clearance is essential.
  - *Intraoperative test for completion of vagotomy* should be done—*Grassi test or insulin test*.
  - It has got distinct *advantages*—low operative mortality (0.2%) and postoperative morbidity (0.5%); postvagotomy diarrhoea and dumping syndrome is very low; chances of developing anaemia, weight loss, osteoporosis, tuberculosis, and carcinoma are very less.
  - *Problems*—lesser curve necrosis due to ischaemia; recurrent ulcer 10-15% in 10 years.

- *Selective vagotomy with pyloroplasty* (SV + P).
- *Truncal vagotomy with gastrojejunostomy* (TV + GJ).
- *Posterior truncal vagotomy with anterior seromyotomy—Taylor's operation*. It can be done through laparoscopy.
- *Vagotomy with antrectomy*: Gastrin producing antrum, vagal cholinergic pathway from ulcer bearing area is removed with gastroduodenal anastomosis. Ulcer recurrence is very low but has got morbidity.
- *Posterior truncal vagotomy* with HSV without drainage procedure (Kim's) often through laparoscopy is also done.
- *Linear gastrectomy* with posterior truncal vagotomy through laparoscopy.
- Most of these procedures presently can be done through *laparoscope*.

Note:

Presently, there is *no role of gastrectomy or gastrojejunostomy (Just GJ) for uncomplicated DU.*

PYLORIC STENOSIS DUE TO CHRONIC DUODENAL ULCER

Pathology

Chronic DU after many years undergoes scarring and cicatrisation causing total obstruction of the pylorus, leading to enormous dilatation of stomach.

Clinical Features

- Pain is severe, persistent, in epigastric region, and also with feeling of fullness.
- Vomiting—large quantity, foul smelling and frothy, vomitus contains food consumed on previous day (partially digested or undigested food).
- Loss of periodicity.
- Loss of appetite and weight.
- *Visible gastric peristalsis* (VGP)—may be elicited by asking the patient to drink a cup of water.
- *Positive succussion* splash which is done with 4 hours empty stomach, by placing a stethoscope over the epigastric region and shaking the patient adequately.
- *Auscultopercussion test* shows dilated stomach.
  Test is done by placing a stethoscope over the epigastric region. Skin is scratched from left side downwards, at several points away from the epigastrium (towards left side) using finger and these points are joined. Normally greater curvature of stomach is above the level of umbilicus (midway between the umbilicus and epigastrium). In gastric outlet obstruction it lies below the level of the umbilicus (Stomach we see; stomach we feel; stomach we hear).
- Confused status because of alkalosis and electrolyte changes.
- ***Electrolyte changes***: Because of vomiting, *hypochloraemic, hyponatraemic, hypokalaemic, hypocalcaemic, hypomagnesaemic alkalosis occurs. It causes **paradoxical aciduria**.*
- Mass is never palpable.
- *Goldstein saline load test*—half an hour after installation of 750 ml of saline, if volume remained and if more than 250 ml, suggest obstruction.

Investigations

1. *Barium meal study:*
   - Absence of duodenal cap.
   - Dilated stomach where greater curvature is below the level of iliac crest.
   - Mottled stomach.
   - Barium will not pass into duodenum.
2. Gastroscopy to rule out carcinoma stomach and to visualise the stenosed area.
3. Electrolyte study for correction of electrolyte imbalance.
4. ECG to check for hypokalaemia.

An inn has one entrance and three exist—to hospital, to asylum and to prison. —**Croatian Proverb**



Fig. 20.30: Pyloric stenosis with gastric dilatation.



Figs 20.31A and B: Barium meal pictures showing gastric outlet obstruction.

Differential Diagnosis

Carcinoma pylorus—here mass may be palpable.

Pyloric stenosis—causes

- Congenital
- Chronic DU—fibrosed/cicatrised
- Carcinoma pylorus
- Adult pyloric stenosis—it is treated by pyloroplasty (not by pyloromyotomy)
- Pyloric mucosal diaphragm—it should be excised surgically or endoscopically

Treatment

- Correction of dehydration and electrolytes by IV fluids—normal saline or double strength saline, calcium, potassium, magnesium.
- Blood transfusion is given if there is anaemia.
- TPN support.
- Stomach wash to clean the stomach contents (using normal saline) is given using stomach tube like Eswald's. It also reduces the oedema of stomach wall and improves gastric emptying time by increasing the gastric muscle tone.
- Surgery
  - *HSV with gastrojejunostomy* is present recommendation even though it is technically difficult. HSV is better than TV as it maintains the nerve supply of the chronically obstructed antrum and so may eventually reduce the chronic emptying problems.
  - Truncal vagotomy along with gastrojejunostomy of *Mayo (posterior, vertical/oblique, short loop, retrocolic, isoperistalsis) is done—ideal, commonly advocated procedure.*
  - Vagotomy, antrectomy (acid secreting area) with Billorth I anastomosis along with feeding jejunostomy for nutrition is the other option.



Fig. 20.32: *Gastric outlet obstruction* showing dilated stomach on table.

Note:

- Often gastric emptying may be delayed for 2-4 weeks after surgery in pyloric stenosis. It usually recovers in 7 days.
- After recovery eradication of *H. pylori* infection is routinely done even though infection may not be evident in many of patients with outlet obstruction.
- *No role of pyloroplasty or HSV in a scarred duodenum—as it can cause disruption and bile leak.*
- Gastrectomy and other procedures are usually not necessary in pyloric stenosis.
- Endoscopic balloon dilatation of the stenosed area benefits only temporarily with high recurrence rate.



Fig. 20.33: Truncal vagotomy and gastrojejunostomy. *It is posterior, vertical, short loop, retrocolic, isoperistaltic GJ of Mayo.*



Fig. 20.34: Gastrojejunostomy stoma view on endoscopy.



Fig. 20.35: Vagotomy and antrectomy. It is occasionally used for intractable resistant duodenal ulcer or chronic duodenal ulcer with obstruction. HSV is commonly used in intractable cases. GJ with vagotomy is commonly used in pyloric stenosis due to chronic duodenal ulcer.

ELECTROLYTE CHANGES IN PYLORIC STENOSIS

- Hyponatraemia.
- Hypokalaemia.
- Hypomagnesaemia.
- Hypochloraemia.
- Metabolic alkalosis.
- Paradoxical aciduria.

Because of severe vomiting which contains acid as well as undigested retained food, sodium, chloride, potassium, magnesium levels drop, causing metabolic alkalosis. Alkalosis can lead to hypocalcaemia causing tetany. It is called as ***'gastric tetany'.***

To control alkalosis, kidney secretes excess bicarbonate (In alkalosis without hyponatraemia, bicarbonate is secreted along with sodium). Here, due to hyponatraemia, body conserves sodium and so bicarbonate is secreted along with hydrogen ion. So urine becomes *acidic*. It is called as ***paradoxical aciduria.***

Clinical Features

- Irritability, confused status, dehydration.
- Often convulsions can occur.
- Features of alkalosis like rapid breathing—Cheyne-Stokes breathing and tetany.

Investigations

- Serum electrolytes.
- Arterial blood gas analysis.
- Serum calcium level estimation.

Treatment

- Double strength normal saline.
- IV potassium given slowly under ECG monitoring.
- The cause is treated.
- IV magnesium.

Note:

Metabolic changes are not severe in carcinoma pylorus as it is seen in pyloric stenosis due to chronic duodenal ulcer because in carcinoma stomach often there is hypochlorohydria or achlorohydria.

PERFORATED PEPTIC ULCER

- It is the terminology used for *perforation of duodenal ulcer or gastric ulcer or stomal ulcer.* Otherwise all clinical features and management are similar.
- Perforation is common in duodenal ulcer (75% of perforated peptic ulcers). Mortality is more in gastric ulcer perforation and perforation in elderly.

A. PERFORATED DUODENAL ULCER

- It is common in males (8:1) between 35-45 years of age group, but can occur in any age group.
- ***Anterior ulcer*** perforates, commonly
  - In 80% of cases, there is a history of chronic DU.
  - In 20% cases, it is silent perforation.
- Perforation can occur in acute ulcers or in acute presentation of a pre-existing chronic ulcer.
- Perforation may be precipitated by steroids, analgesics (NSAIDs), alcohol, antimalarials.
- Overall incidence is 5%.
- Active ulcers perforate commonly.

Stages of Perforation

- ***Stage of chemical peritonitis:***
  - Once perforation occurs, stomach contents escape into the peritoneal cavity. The acid from the stomach causes chemical peritonitis leading to severe pain in epigastric region, vomiting, tenderness, guarding, rigidity, tachycardia, sweating.

- ***Stage of reaction (Stage of illusion):***
  - Peritoneum secretes lot of fluid to neutralise the escaped content and so temporarily the pain reduces, and the patient feels better. This phase lasts for about 6 hours.
- ***Stage of diffuse bacterial peritonitis:***
  - After about six hours, bacteria from GIT (escape) migrate from the site of perforation causing diffuse peritonitis.

Clinical Features

- Presents with *severe persistent pain* in the epigastrium initially, later in the right side abdomen (as the inflammatory fluid spills along the right paracolic gutter) and finally becomes generalised. Pain is of sudden in onset, is due to contact of expelled gastric contents with the parietal peritoneum. Pain often radiates to right scapular region. Pain becomes more on movements.
- Tenderness and rebound tenderness is seen (*Blumberg sign*) all over the abdomen.
- Fever, vomiting, dehydration, oliguria occurs.
- Patient is toxic, with tachycardia, hypotension, tachypnoea.
- Abdominal distension occurs.
- Guarding and rigidity, initially in the epigastrium but later all over the abdomen.
- Dullness over the flank because of fluid.
- *Obliteration of liver dullness*—as a result of collection of escaped gas under the diaphragm.
- Silent abdomen with absence of bowel sounds.
- Tenderness felt on per rectal examination.
- Sometimes fluid from supracolic region slowly trickles down along the right paracolic gutter and collects in right iliac region causing pain and tenderness in RIF mimicking appendicitis.
- Often slow, small perforation presents with subacute features, but diffuse peritonitis eventually sets in 24-48 hours.



Fig. 20.36: Spread in DU perforation.

Terminal stage:

Patient may have oliguria, septicaemia, shock, *Hippocratic facies* (sunken eyes, cold periphery and shallow rapid breathing, ill look), with MODS (Multiorgan dysfunction syndrome).

Investigations

- *Plain X-ray abdomen (erect posture)*: Shows gas under diaphragm in 70% of cases. In 30% of cases, there is no gas under diaphragm. It may be due to, either the gas leak is less than 1 ml or due to previous surgery causing adhesions between liver and diaphragm, or sealed peptic ulcer.



Fig. 20.37: Note the site of the DU perforation, on table.



Fig. 20.38: Plain X-ray abdomen in erect position with ground-glass appearance and gas under diaphragm—perforation.



Fig. 20.39: Lateral decubitus X-ray showing air under diaphragm. This is done when patient is critically ill and cannot make the patient stand in erect posture.



Fig. 20.40: Approaches to manage duodenal ulcer perforation can be either open (upper midline incision) laparotomy incision or laparoscopic.



Fig. 20.41: Duodenal ulcer perforation closed horizontally using interrupted silk/vicryl sutures with omental patch over it.

(***Chilaiditi's syndrome*** is the interposition of the colon in front and above the liver. It is common in children and elderly. It may be mistaken for gas under diaphragm in plain X-ray abdomen).

- U/S abdomen shows free fluid and often gas.
- Blood urea, serum creatinine, total count, electrolytes, are helpful.
- CT scan abdomen is very sensitive investigation whenever there is absence of gas under diaphragm. It rules out other conditions like pancreatitis. Gastrograffin upper GI study also confirms the perforation.

Differential diagnosis

- Acute appendicitis
- Acute pancreatitis
- Acute cholecystitis
- Ruptured aortic aneurysm
- Myocardial infarction
- Mesenteric ischaemia
- Pneumonia

Treatment

- Patient is advised admission.
- IV fluids—Ringer lactate, normal saline, dextrose saline.
- Antibiotics—Cefotaxime, metronidazole, amikacin.
- Catheterisation.
- Ryle's tube aspiration.



Figs 20.42A and B: Duodenal ulcer perforation and its closure using omental patch.

- *Surgery:*
  - Emergency laparotomy through upper midline incision is done.
  - All infected fluid is sucked out.
  - Perforation is identified and closed with interrupted, horizontal sutures using *either silk or vicryl*. Omental patch is placed *before suturing*—it is called as ***Rosoe-Graham Operation.*** Because of its *adhesion property* it seals perforation; good vascularity and lymphatics promote the healing effectively.
  - Peritoneal wash (toilet) using 5-10 litres of saline is given.
  - Drain is placed and abdomen is closed, often if required with *tension sutures*. Drain is removed in 3-5 days. During discharge, patient is advised to avoid alcohol and to take H_2 blockers or proton pump inhibitors for 6-12 weeks.
  - After 12 weeks *follow-up gastroscopy must be done.*

65% of haematemesis is due to bleeding peptic ulcer. Among peptic ulcer, duodenal ulcer (35%) is the most common cause.

Note:

- Very rarely, in elderly people or in cases of subacute perforation which gets sealed on its own, *conservative treatment is* tried with careful observation, i.e. by giving IV fluids, antibiotics, Ryle's tube aspiration, maintenance of urine output and electrolytes. It is called as *Hermen-Taylor regime*. But it should not be a standard treatment.
- Laparoscopy is beneficial for both diagnoses, as well as for therapy for perforation closure using omental patch. It is proposed and widely used for early duodenal perforation. It can be useful for most of the duodenal ulcer perforations. If it is problematic, conversion options should always be kept in mind.
- Once perforation is closed, either by open or laparoscopic method, after recovery patient should be advised, *anti-Helicobacter pylori* therapy (triple regime for 14 days) with PPI for 3 months. It reduces rate of reperforation and ulcer recurrence in duodenal ulcer.
- In patients with severe peritonitis and critically ill, after perforation closure it is better to insert a nasojejunal tube or feeding jejunostomy for nutrition in postoperative recovery period. Even if patient develops a temporary duodenal leak, this supports nutrition well until the leak stops.
- Occasional large perforated duodenal ulcer with oedema which cannot be closed is managed by serosal patch/duodenal drainage and pyloric exclusion/gastrostomy, duodenostomy and jejunostomy/Roux-en-Y jejunal patch over the perforation.
- *Manheim peritonitis index* or *APACHE II* scoring system is used to assess the patient properly.
- Doing concomitant acid reducing surgical procedure like HSV is under debate and not used routinely (not advised) even though some centers advocate. HSV may be done if there is not much contamination of the peritoneal cavity or in early perforation of a chronic duodenal ulcer.

B. PERFORATED GASTRIC ULCER



Fig. 20.43: Malignant gastric ulcer showing perforation.

- ♦ Commonly ulcer in the lesser curve near the antrum perforates. Amount of gas escaped is more than the perforated DU. Malignancy should always be suspected and so *biopsy from the edge is a must.*
- ♦ Mortality in gastric ulcer perforation is high (20%).
- ♦ Commonly they are prepyloric in position.
- ♦ Primary closure with an edge biopsy is commonly used. Distal gastrectomy including ulcer area is better option if patient's general condition is favourable.
- ♦ Posterior gastric ulcer perforation is often difficult to diagnose both clinically and radiologically.



Fig. 20.44: Gastric ulcer perforation on table finding.

C. PERFORATED STOMAL ULCER

In perforation of stomal ulcer*, often undoing of GJ or partial gastrectomy may be required.*

D. DRY PERFORATION

(Perforated Duodenal Ulcer Sealed by Omentum)

- ♦ Patient is ambulatory.
- ♦ Vomiting is absent.
- ♦ Rigidity confined to epigastrium and right hypochondrium.

Different signs in X-ray in perforation

- ❖ *Cupola sign*—crescent shaped radiolucency under the diaphragm
- ❖ *Riglers sign*—visualisation of both aspects of the bowel wall being outlined by gas on either side
- ❖ *Inverted V sign*—gas on either sides of the falciform ligament
- ❖ *Football sign*—collection of gas in the center of the abdomen like a foot ball
- ❖ *Triangle sign*—gas between bowel loops

Conditions which mimic pneumoperitoneum—pseudopneumoperitoneum

- Subpulmonary pneumothorax
- Chilladiti syndrome
- Subphrenic abscess due to infections by gas forming organism like *Clostridium welchii*
- Subdiaphramatic fat or omental fat under the diaphragm may rarely mimic gas under the diaphragm

BLEEDING PEPTIC ULCER

- It is **bleeding either from duodenal ulcer, or gastric ulcer or stomal ulcer**.
- In bleeding from stomal ulcer, partial gastrectomy is required (Fig. 20.45).
- Mortality in bleeding peptic ulcer is high (20-30%). Elderly age, associated systemic diseases increase the mortality.
- NSAID's and *H. pylori* infection, coagulopathy, and anticoagulant drugs are common precipitating factors. Concomitant use of NSAID and steroids increase risk by 10 fold.
- Need of more than 5 units of blood transfusion during hospital stay is called as *massive haemorrhage*.



Fig. 20.45: Sites of gastric ulcer and duodenal ulcer bleeding. Note GU can erode into the left gastric artery. DU can erode into the gastroduodenal artery.

A. BLEEDING DUODENAL ULCER

- 10% common.
- Risk of bleeding in chronic duodenal ulcer increases to 35% if patient has not taken specific anti-*Helicobacter pylori* therapy and PPI.
- Bleeding from DU is either from the *small vessels in the wall of ulcer* crater or due to erosion into the *gastroduodenal artery*.



Fig. 20.46: In bleeding ulcer during endoscopy stomach should be inflated with air adequately so that bleeding ulcer is visualised well.

Precipitating causes

- Alcohol
- NSAIDs, steroids
- Excessive fibrosis
- Atherosclerotic disease

Forrest classification of bleeding or bled ulcer

Ia	Spurting and bleeding
Ib	Nonspurting but active bleeding
IIa	Visible vessel with red or blue protrusion or pulsatile pseudoaneurysm
IIb	Nonbleeding ulcer with clot overlying
IIc	Ulcer with haematin base
III	Clean ulcer—no clot, no vessel

- Usually *posterior* duodenal ulcer bleeds.
- Bleeding from small vessels in the wall of ulcer is due to sloughing of the ulcer. It is less severe, gradual and most often well-controlled by conservative treatment.
- Bleeding from erosion of gastroduodenal artery is severe, torrential and almost always needs early surgical intervention.

Clinical Features

- *Haematemesis and melaena.*



Fig. 20.47: Melaena—typical *black, tarry* coloured *foul* smelling stool. It signifies upper GI bleed. At least 50 ml bleeding should be there to cause melaena.

- Features of shock: Pallor, tachycardia, sweating, hypotension, tachypnoea, dry tongue, cold periphery.
- Past history of chronic DU may be present. But it is not always necessary in every patient, as some may have a silent ulcer which may present as bleeding and haematemesis to begin with.
- History of pain and tenderness in epigastric region which has increased in intensity recently.

Differential diagnosis

- Erosive gastritis
- Oesophageal varices
- Carcinoma stomach
- Bleeding gastric ulcer
- Mallory-Weiss syndrome
- Gastric polyps
- Bleeding disorders

Investigations

To look for in endoscopy, in bleeding ulcer

- Spurter
- Clot
- Visible vessel
- Aneurysmal dilatation of the arteriole in the wall of ulcer
- Ooze



Fig. 20.48: Bleeding duodenal ulcer endoscopic view.

- *Gastroscopy is confirmative*—it is a must. It identifies ulcer bleed in 90% of cases clearly. Possibility of rebleed is also assessed by endoscopy. A flat clear based ulcer is less likely to rebleed. Active ulcer/fresh clot/visible vessel/pseudoaneurysm/large ulcer are more likely to rebleed. *Rockall scoring system* is used to predict rebleed.
- *Coeliac angiogram* to identify the bleeder may be helpful.
- Hb% and PCV—should be repeated at regular intervals (once in 2-3 hours).
- Blood group and cross-matching.
- Estimation of serum electrolytes, blood urea, serum creatinine, platelet count.

Treatment

Seventy percent of bleeding duodenal ulcers are treated conservatively.

- The shock is corrected initially by:
  - Foot end elevation.
  - IV fluids, plasma expanders (haemaccel, dextran, crystalloids). CVP line is better in these patients.
  - Sedation.
  - Catheterisation—to assess urine output.
  - Blood transfusion to replace the lost blood.
- Stomach wash is given—1 : 2,00,000 adrenaline in saline wash is given to the stomach through Ryle's tube.
- IV ranitidine 50 mg 6th or 8th hourly. IV famotidine.
- IV pantoprazole 80 mg in 100 ml dextrose saline is given slow IV as starting dose and later 40 mg in dextrose saline IV OD/BD. Slow continuous infusion of pantoprazole 40 mg in dextrose saline, 500 ml IV can also be given.
- *Endoscopic cauterisation* of small vessel with either gastroscopic bipolar cautery or through Laser or through heater probe or through haemoclips can be tried to stop the bleeding.
- *Sclerotherapy*—ethanolamine oleate, distilled water. *Epinephrine injection* is also used *commonly.* Other agents used are absolute alcohol, polidocanol.
- Observation
  - Patients with bleeding from small vessels in the wall of DU will commonly respond to conservative treatment.
- *Angiographic embolisation of gastroduodenal artery.*



Fig. 20.49: Sclerosants like ethanolamine oleate or distilled water are used through endoscopy to control bleeding ulcer. It causes tamponade, vasoconstriction, sclerosis. It is the best method to control the bleeding.

Indications for surgical treatment

- In spite of conservative treatment condition of patient deteriorates
- Bleeding from gastroduodenal artery
- Recurrent bleeding
- Elderly patient
- If more than 4 units of blood required immediately

- ***Surgery***
  - After laparotomy, pyloric channel and first part of the duodenum (gastroduodenum) is opened longitudinally, bleeder is identified. *Underruning of* the bleeding area with vicryl is done.
  - If the bleed is from gastroduodenal artery, then it has to be *ligated* to stop the bleeding. Opened gastroduodenum is closed by ***Finney's pyloroplasty.***
  - Truncal vagotomy may be done together, if the general condition of the patient is good.



Fig. 20.50: Gastroduodenal artery ligation is required in case of severe massive upper GI duodenal ulcer bleed.



Fig. 20.51: Underrunning of the bleeding duodenal ulcer at ulcer bed is done to control haemorrhage. After that duodenum is closed with Finney's pyloroplasty.

- ***Further treatment***
  - During discharge, patient is advised to take *anti-Helicobacter pylori* (triple) therapy, proton pump inhibitors for 6-12 weeks (Omeprazole, or Lanzoprazole).
  - Healing of ulcer can be confirmed by doing a gastroscopy after 6-12 weeks.

Treatment schedule for bleeding duodenal ulcer

- Treatment of shock
- Blood transfusion
- Stomach wash with—1 : 2,00,000 adrenaline saline
- IV ranitidine, famotidine, pantoprazole, omeprazole
- Endoscopic sclerotherapy using ethanolamine oleate or distilled water
- Endoscopic bipolar cauterisation, laser therapy, heater probe, haemoclips
- Angiographic embolisation of gastroduodenal artery
- Open surgery and underrunning of the bleeding ulcer bed
- Ligation of gastroduodenal artery and then Finney's pyloroplasty
- Proton pump inhibitors during discharge
- Follow-up gastroscopy after 3 months

Sclerotherapy is the most popular endoscopic method used at present

B. BLEEDING GASTRIC ULCER

- It is similar to bleeding DU. Bleeding may be either from the ulcer bed or from the erosion of gastric vessels commonly but occasionally splenic vessels. They commonly present with severe haematemesis and shock.
- Bleeding is much more severe than bleeding DU.
- Surgery is the main treatment:
  After initial resuscitation, blood transfusion and a trial of conservative management, laparotomy is done.

On laparotomy one of the following procedures is done.

Underrunning of the ulcer bed.

OR ligation of splenic vessels with splenectomy with or without partial gastrectomy and gastroduodenostomy.

Postoperative management and follow-up is same like bleeding DU.

Treatment for bleeding gastric ulcer

- Underrunning of the ulcer bed
- Partial gastrectomy with Billroth I anastomosis
- Vagotomy with antrectomy
- Occasionally splenic vessel ligation with splenectomy may be required

HAEMATEMESIS

Causes:

- Chronic peptic ulcer (duodenal + gastric) (65%).
- Acute peptic ulcer.
- Acute erosive gastritis (Steroids, NSAIDs).
- Oesophageal varices.
- Mallory-Weiss syndrome (5-15%)
- Carcinoma stomach (5%)
- Gastric polyps, lymphomas, leiomyomas.
- Portal gastropathy.



Fig. 20.52: Gastroscopy showing carcinoma stomach which is bleeding. Note the slough and everted edge.



Fig. 20.53: Various causes of haematemesis.

- Bleeding disorders.
- Pernicious anaemia.
- Thrombocytopenia.
- ***Gastric antral vascular ectasia***
    - It is a rare endoscopically confirmed condition which shows segmented dilated vessel meshes in the antral mucosa (*water-melon/tiger stripe stomach*).
    - It is often associated with achlorhydria and hypergastrinaemia.
    - It is *common* in middle aged females; *common* in liver diseases (25%) and autoimmune connective tissue disorders.
    - *Pathologically* it shows mucosal fibromuscular hyperplasia and hyalinisation.
    - After confirmation with *gastroscopy*, often *antrectomy* is needed.
- Osler-Weber Rendu syndrome, aortoduodenal fistula, Crest syndrome are rare causes.
- ***Dieulafoy's disease***
    - A gastric arteriovenous malformation which is covered by apparently normal mucosa.
    - It occurs in proximal stomach near OG junction (within 6 cm) along lesser curve (80% of cases).
    - Bleeding often may be severe and torrential.
    - Vasculitis or atheroma are absent in the vessel.
    - It is 5% of nonvariceal upper GI bleed.
    - A large 1-3 mm tortuous abnormal submucosal artery (AVM) is the cause, which due to its pulsation erodes the mucosa to expose itself to acid which further erodes the artery causing bleeding.
    - Endoscopy and endoscopic therapy or excision of the lesion is required.
    - Angiography can be done to confirm the disease and to do therapeutic embolisation using gel foam.
    - Failure of endoscopic or angiographic therapy needs gastrotomy and excision of the entire lesion—*gastric wedge resection*. It can be done by open/laparoscopic approach. Prior endoscopic tattooing is mandatory to identify the lesion during resection.

Management of Haematemesis

- *Evaluation of patient* by measuring BP, pulse, respiration looking for features of shock, oxygen saturation, investigating for Hb%, blood grouping, blood urea, serum creatinine, LFT, prothrombin time, platelet count, arterial blood gas analysis, gastroscopy.
- *Initial treatment* is central line insertion, fluid and blood replacement; catheterisation; IV PPI; nasogastric tube placement (controversial but now universally accepted); FFP, platelet transfusion if needed; gastroscopic sclerotherapy, banding, laser, haemoclip application; SB tube for varices; pharmacotherapy.
- *Further treatment*—critical care (ICU); antibiotics; treatment of complications like sepsis, DIC, ARDS.
- *Specific treatment*—open surgery for uncontrolled bleeding, ligation of gastroduodenal artery and underrunning of ulcer bed with pyloroplasty, gastrectomy, ligation of varices with devascularisation.
- *Definitive surgery* for underlying cause—shunt surgery; vagotomy and GJ; gastrectomy; TIPSS; splenectomy, etc.

COMPLICATIONS OF GASTRIC SURGERY

- Haemorrhage.
- Stomal obstruction.
- Biliary fistula.
- Injury to CBD.
- Duodenal blow out—on 4th postoperative day.
- Pancreatitis.
- Recurrent ulcer/stomal ulcer.
- Gastrojejunocolic fistula.
- Dumping syndrome (Postcibal syndrome).
- Nutritional disturbances, diarrhoea.
- Pulmonary tuberculosis.
- Carcinoma in gastric remnant (after 10-15 years).
- Gallstone formation.
- Alkaline gastritis.
- Afferent and efferent loop syndrome.
- Afferent loop obstruction—*common.*
- Efferent loop obstruction.

Complications may be classified as:

Intraoperative—bleeding, injury to spleen, pancreas, CBD.

Early postoperative—bleeding either intraluminal (from stomal site) or extraluminal; leak along anastomotic line; delayed opening of stoma; gastroparesis; duodenal stump blow out; lesser curve necrosis; fistula formation—gastric/duodenal/jejunal; omental infarction.

Late postoperative—reflux gastritis, recurrence of ulcer; dumping syndrome; malnutrition; gastrojejunocolic fistula; motility disorders; small stomach syndrome; afferent or efferent loop obstruction; retrograde jejunogastric intussusception; remnant carcinoma; gallstones; pulmonary or GIT tuberculosis; bezoar formation.

Stomal obstruction after gastric surgeries is due to:

- Mucosal oedema—usually subsides eventually
- Retrograde jejunogastric intussusception
- Hypertrophied stomal mucosa causing ball-valve mechanism
- Efferent loop obstruction
- Gastric atony eventhough there is wide patent stoma causing apparent stomal obstruction

Nutritional deficiencies following gastrectomy

Iron deficiency anaemia	40%
Megaloblastic anaemia (after 5 years)	25%
(100 μg B_{12} is given IM weekly, later monthly)	
Vitamin B deficiency	10%
Calcium deficiency	40%
Calcium deficiency with bone changes (after 5 years)	5%

A. DUODENAL BLOW OUT

- It is a very serious complication of Billroth II gastrectomy, occurs usually on 4-5th day after surgery.
- Here contents in the afferent loop are not having free flow which in turn increases the pressure in the duodenal 'C' loop leading to giving way of the closed duodenal stump.
- It is due to improper closure of duodenal stump, oedematous inflamed duodenum, afferent loop block, distal obstruction, ischaemia of least vascular duodenum and sepsis.



Fig. 20.54: Duodenal blow out after Billroth II anastomosis usually occurs 4 days after the surgery. It is often life-threatening condition.

Features

- Sudden, severe pain abdomen postoperatively with features of shock.
- Forming a duodenal fistula through the drain placed.
- May cause peritonitis.
- Severe electrolyte imbalance.
- Features of biliary peritonitis, septicaemia.
- Skin excoriation and its problems.

Treatment

- *Conservative therapy* with nasogastric aspiration, IV fluids, TPN, antibiotics. Usually, patient will recover in 40-60 days.
- *Surgery is indicated* when there is peritonitis, fistula not responding, when there is distal obstruction.
- *Surgeries are*—afferent and efferent loop connection, relieving the obstruction distally, serosal patch over the duodenal stump after excision of the fistula, creating a controlled fistula after placing a tube into the duodenum.

Duodenal fistula

Causes

- Due to duodenal blow out—ischaemia, afferent loop obstruction, sepsis
- After closure of perforated DU
- Injury to duodenum by trauma, surgeries like hemicolectomy, renal surgeries, pancreatic surgeries, etc

Types

- High > 500 ml/24 hours
- Low < 500 ml

Features

- Pain abdomen
- Bile leak through the drain site or fistula track
- Skin excoriation
- Electrolyte imbalance
- Malnutrition, anaemia
- Recurrent infection

Investigations

- Electrolyte estimation, haematocrit
- CT fistulogram

Treatment

- TPN, feeding through jejunostomy
- Management of anaemia, electrolytes
- Blood transfusion
- Antibiotics whenever sepsis is suspected

What we need is cup of understanding, barrel of love and an ocean of patience.

- Care of skin—zinc oxide cream application, controlled fistula by placing a Foley's catheter into the fistula track
- Usually responds well by conservative therapy in 8-12 weeks
- If not improved then surgery is needed—anastomosis between afferent and efferent loops (jejuno-jejunostomy); serosal patch techniques; surgical closure of fistula, Roux-en-Y patch over fistula

B. RECURRENT ULCER

It is a wide terminology which includes stomal ulcers, recurrence of ulcer in the original ulcer site or different parts of stomach/duodenum or jejunum after a therapeutic surgical procedure.

Stomal ulcer can occur in gastrojejunostomy stoma or in gastroduodenostomy stoma. GJ stomal ulcer *per se* can occur after only gastrojejunostomy or after partial gastrectomy with Billroth II anastomosis. Recurrent ulcer at the original site is commonly referred to *ulcer recurrence* (after HSV commonly).

Recurrent ulcer is 3-7%. It may be after:

- Gastrojejunostomy.
- Billroth I or Billroth II anastomosis.

It may be:

- Gastrojejunostomy stomal ulcer
- Gastroduodenostomy stomal ulcer
- Jejunal ulcer
- Gastric ulcer
- *Ulcer recurrence*—10%

Causes

- Incomplete vagotomy.
- Zollinger-Ellison syndrome, gastrinomas.
- Alcohol, smoking.
- Hyperparathyroidism.



Fig. 20.55: *Stomal ulcer* after GJ may be due to incomplete vagotomy, Zollinger-Ellison syndrome.

- Gastrojejunostomy when done without vagotomy—40%.
- After HSV—10%.

Clinical Features

- Pain in the umbilical and left hypochondrium (severe, persistent).
- Back pain.
- Haematemesis.
- Anaemia, loss of weight.
- Features of obstruction—10%.

Note:

Stomal ulcer may complicate to gastrojejunocolic fistula, perforation, bleeding, obstruction, penetration.

Investigations

- Barium meal.
- Gastroscopy.
- Hollander's insulin test.
- Pentagastrin test.
- Gastrin level estimation.
- Serum calcium to rule hyperparathyroidism.
- *Visick grading* is used to assess the response to therapy to various procedures (Grade 1, 2, 3, 4 and 5).

Treatment

- Complete the vagotomy.
- Undoing of GJ.
- Conversion into another procedure, Roux-en-Y procedure.
- Treat hypergastrinaemia, hyperparathyroidism.
- Eradication of *H. pylori* infection using triple regime for 2 weeks and then continuation of therapy using PPI for 3 months.
- Subtotal gastrectomy in resistant recurrent ulcer cases.

Stomal ulcer

- It is the ulcer in anastomotic site of GJ/GD
- Overall incidence is 10% in 10 years after surgery
- It is common on jejunal side but can occur on gastric side or both sides or at junction

Causes

- After only gastrojejunostomy procedure—40%
- After vagotomy and GJ—5-7%
- After partial gastrectomy and gastroduodenostomy—Billroth I—3%
- After partial gastrectomy and GJ—Billroth II—3%
- Other causes like gastrinomas, hyperparathyroidism, incomplete vagotomy, smoking, alcohol

Features

- Pain and haematemesis/melaena is the main presentations
- Pain is persistent, severe over left upper abdomen often radiating to back
- Pain may be in the chest if it is antecolic anastomosis
- Weight loss and features of obstruction can occur

Investigations

- Acid tests (Hollander's), gastroscopy, tests specific for the cause
- Serum gastrin/calcium assay

Complications
- Bleeding stomal obstruction
- Perforation
- Gastrojejunocolic fistula
- Nutritional deficiency

Treatment
- Completion vagotomy
- Subtotal gastrectomy/revision gastrectomy
- Roux-en-Y anastomosis
- Treat the cause

C. DUMPING SYNDROME

(Post-cibal Syndrome)

It is common in *females*, seen after Billroth II surgery.

Types

1. *EARLY DUMPING SYNDROME:*
- It is common and more severe type
- Incidence is 10%
- Vasomotor symptoms appear immediately after food, lasts for 30-40 minutes, aggravated by bulky food. It is relieved by lying down, aggravated by more food

***Clinical features*:**
- Sweating, tachycardia, colicky pain and diarrhoea
- Hypotension and features of hypovolaemia

Pathogenesis: It is a *primary disorder of carbohydrate metabolism* wherein initial transient hyperglycaemia prevents further absorption of glucose, which in turn draws fluid from the bowel wall by high osmolarity resulting in increased intestinal activity, resulting in diarrhoea and fall in blood volume

Treatment: Small, dry, more frequent food, with avoidance of carbohydrates. Octreotide 100 µg given subcutaneously before meals is found to be beneficial

***Surgical treatment*:**
- Conversion of Billroth II to Billroth I
- Interposition of reversed jejunal loop (*Henley's loop*)

Early dumping syndrome can last for long time (many years)

2. *LATE DUMPING SYNDROME*:
- It is of less severe type
- Incidence is 5%
- It usually occurs 2 hours after meal
- It is relieved by glucose and aggravated by exercise

Pathogenesis: Due to initial hyperglycaemia insulin secretion is stimulated which in turn leads to hypoglycaemia

***Clinical features*:**
- Tremor, fainting, nausea
- Features of hypoglycaemia

***Treatment*:** Symptoms are less severe and so treated conservatively, by giving glucose and food

D. ROUX STASIS SYNDROME

- It is occurrence of *gastric atony* after subtotal or partial gastrectomy if Roux-en gastrojejunostomy is done.
- They present with fullness, vomiting, loss of appetite and weight, early satiety.
- It occurs in 25% of Roux-en-Y GJ. It is common in *females*.
- It is common in Roux-en-Y limb if *more* than 40 cm. It is late complication seen in months or year.
- There may be dysfunction of both gastric remnant and Roux limb. It is due to *ectopic pacemaker* in *Roux limb* which delays the gastric emptying.

Treatment

- Completion total gastrectomy is the choice.
- Isolated jejunal loop interposition of 40 cm length—Henley's loop.
- Intestinal pacing, OR usage of '*uncut Roux*' limb.

E. GASTROJEJUNOCOLIC FISTULA

It is a complication of gastrojejunal ulcer (stomal ulcer), wherein ulcer penetrates and erodes into the transverse colon leading to gastrojejunocolic fistula, a dreaded complication.

Clinical Features

- *Sudden onset of severe diarrhoea* after every meal with past history of GJ done and past history of gastrojejunal ulcer.
- Foul gas eructation.
- Dehydration.
- Rapid loss of weight, anaemia, cachexia, hypoproteinaemia (bacteria from colon enters the jejunum disrupting the absorptive mechanism).
- Steatorrhoea.
- Rarely faecal vomiting.



Fig. 20.56: Gastrojejunocolic fistula.

Investigation

Barium enema (not barium meal). CT scan, endoscopy (upper and lower).

Treatment

- IV fluids.
- Total parenteral nutrition (TPN).

Carcinoma stomach is the commonest cause of Krukenberg's tumour.

- Blood transfusions.
- Antibiotics.
- Rehydration, electrolyte management.
- Surgery: Resection of involved *stomach, jejunum, colon* has to be done and continuity has to be maintained (*Triple resection*). Surgery is the only treatment.

It has got high mortality.



Fig. 20.57: Resection of the gastrojejunocolic fistula (removal of involved parts of the stomach, jejunum and colon—triple resection) with maintaining the continuity.

TRICHOBEZOAR (Rapunzel Syndrome)

- It is a hair-ball commonly seen in stomach of *females with psychiatric illness,* who swallow hair regularly.
- It forms a ball like mass occupying the full stomach.



Fig. 20.58: Trichobezoar—CT and hair ball mass (*Courtesy*: Dr (Proffessor) BM Nayak, KMC, Mangalore)

Clinical Features

- Epigastric pain, early satiety.
- Haematemesis.
- Features of gastritis.
- Loss of appetite.
- Perforation.
- Epigastric mass.

Investigation

- Barium meal and endoscopy is confirmative.
- CT scan is very useful.

Treatment

- Gastrotomy and removal of hair ball. Duodenum and small bowel should be examined on table for additional bezoars in these sites.
- Psychiatric counselling.
- Enzymatic digestion and endoscopic breaking of the bezoars is also tried.
- It can also be removed by laparoscopy.

Phytobezoar

- It is due to solid ball formation in the stomach comprising plant fibres and seeds.
- Phytobezoar is common in gastric remnant after partial gastrectomy and in diabetics with autonomic neuropathy.
- *Enzymatic digestion* can be tried using papain (found in Adolph's meat Tenderizer, as one tsp in 300 ml of water taken orally many times a day to fragment bezoar), cellulase substance. If fails, removal by gastrostomy.

CHRONIC DUODENAL ILEUS (WILKIE'S SYNDROME)



Figs 20.59A and B: Superior mesenteric artery—SMA (*Wilkies'*) syndrome showing site of obstruction and dilated proximal gastroduodenum.

- It is also called as *superior mesenteric artery (SMA) syndrome.*
- It is due to obstruction of the 3rd part of the duodenum due to decreased angle between SMA and aorta.
- It can be congenital or due to low insertion of SMA or high insertion of duodenal end or due to traumatic aneurysm of SMA.
- It can be aggravated by plaster casts, lordosis, pancreatic tumour, enlarged lymph node in the 3rd part of duodenum (*Cast syndrome).*

Clinical Features

- Bilious vomiting.
- Upper abdominal fullness.
- Visible peristalsis.
- Dehydration.



Fig. 20.60: Wilkie's syndrome.



Fig. 20.61: Duodenojejunostomy, in case of chronic duodenal ileus.

Differential Diagnosis

- Pyloric stenosis with gastric outlet obstruction.
- Annular pancreas.

Investigation

- Barium meal is diagnostic.
- CT scan abdomen.

Treatment

- Duodenojejunostomy.

Note:

Gastrojejunostomy—not done.

DURBAN'S SYNDROME

- There is a connecting band between right and left crura which causes compression of celiac artery and SMA.
- It may cause foregut ischaemia due to inadequate collaterals, or midgut ischaemia due to diversion of blood to foregut.
- Presentation—chronic abdominal pain, murmur in epigastric region.
- It is often difficult to diagnosis. CT scan, CT angiogram may show poor perfusion. MRI may be useful.
- Treatment—cutting/excising the fibrous band through laparotomy or laparoscopy.
- Condition is also called as *median arcuate ligament syndrome* or *coeliac artery syndrome* or *coeliac band syndrome*.



Fig. 20.62: CT scan showing coeliac artery syndrome.

Many very skillful operators are not good surgeons.— **William J Mayo**

ACUTE GASTRIC DILATATION

- It is an enormous acute dilatation of stomach with atonic gastric wall without peristalsis.
- Stomach distends enormously occupying most of the abdomen and pelvis causing sequestration of lot of fluid resulting in hypovolaemia.

Causes

- After major surgery (abdomen, neurosurgery).
- Trauma, burns.
- Retroperitoneal haematoma.
- Electrolyte imbalance.
- Other causes: Anorexia nervosa, bulimia, polyphagia, drug abuse, diabetes, anaesthesia, debilitating diseases, spinal cord diseases, muscle dystrophy.

Clinical Features

- Features of hypovolaemia and shock.



Fig. 20.63: Acute gastric dilatation showing dilated stomach occupying entire abdomen and also pelvis.

- Vomiting, hiccough. Vomits large quantity of brownish black fluid like *"the storm water of a peat-laden stream."* Vomitus when placed in a test tube and held in a strong light, myriads of small particles may be suspended in the fluid.
- Dilated stomach confirmed by ausculto percussion test.
- Positive succussion splash.
- Electrolyte imbalance is seen.

Investigations

Plain X-ray abdomen, serum electrolytes, U/S abdomen.

Treatment

- Conservative treatment is given initially.
  - Large amount of intravenous fluids.
  - Ryle's tube aspiration.
  - Electrolyte management, blood transfusion.
- The cause is treated.
- Rarely surgical decompression is required. Condition has got high mortality.

Complications

- Aspiration pneumonia *(Mendelson syndrome).*
- Severe hypovolaemia and electrolyte imbalance.
- Raised intragastric pressure causes *venous congestion*, venous infarction, necrosis and perforation.

GASTRIC VOLVULUS

It is twist in the axis of the stomach.

- Rotation occurs around the axis made by two fixed points—cardia and pylorus.
- It can be idiopathic or secondary to—hiatus hernia, left sided eventration, adhesions or pyloric obstruction with long-standing gastric dilatation.

Twist may be:

- ***Organo-axial***: Common in elderly—horizontal.
- ***Mesenterico-axial***: Common in children—vertical.



Fig. 20.64: Types of gastric volvulus.

Pathology

- Here stomach twists upwards between oesophagogastric junction and pyloroduodenal junction. Colon along with omentum also moves upwards initially.
- It is often associated with rolling hiatus hernia or diaphragmatic eventration.

Clinical Features

Borchardt's triad

- Acute epigastric pain
- Violent ineffective vomiting
- Inability to pass a nasogastric tube

Types

- Acute.
- Chronic recurrent. It is common type.

Complications

- Perforation.
- Gangrene of the stomach.
- Bleeding.

Investigations

- Plain X-ray abdomen in erect posture.
- Barium meal X-ray.
- CT scan abdomen.

Treatment

- Untwisting of the volvulus and gastropexy by fixing the anterior wall of the stomach to anterior abdominal wall.
- Gastrojejunal fixation (gastrojejunostomy without a stoma).
- Gastrectomy when stomach is gangrenous.
- Treating hiatus hernia or eventration.
- Displacing colon downwards by dividing gastrocolic omentum—*Tanner's operation.*

GASTRIC POLYP

Gastric polyps are observed in 3% of total gastroscopies. 45% of them are found in fundus which does not show any malignant potential. These polyps are often associated with FAP or Gardener's syndrome and colorectal neoplasms; but these gastric polyps perse are non-neoplastic.



Fig. 20.65: Gastric polyp in prepyloric region.



Fig. 20.66: Polyp in the duodenum first part.

Types

1. Hyperplastic polyp—75% common, minimal risk of malignancy (2%).
2. Adenomatous polyp (10%)—neoplastic in origin. Size > 2 cm is potentially malignant (25% chance).

Features

- *Hyperplastic polyp* is randomly distributed throughout the stomach. They are usually less than 2 cm in size, often multiple. Spontaneous regression can occur. Often it is associated with *H. pylori* infection.
- *Adenomatous polyp* is usually single. It is common in antrum. It can be sessile (common) or pedunculated. It is usually 2 cm or more (80%). It has got hyperchromatic nuclei arranged in a picker fence pattern. Size more than 2 cm has got high malignant potential.
- Inflammatory, hamartomatous and heterotrophic are other gastric polyps of negligible malignant potential.
- 50% are asymptomatic.
- Fundal polyps are associated with PPI therapy and familial polyposis.
- Gastric carcinoids arise from enterochromaffin like cells (ECL). They usually present as small polyps with pernicious anaemia.
- It may present with pain, haematemesis and gastric outlet obstruction. Gastroscopy is diagnostic.
- Endoscopy and resection is needed. If not possible open resection is done.
- Small polyp can be under regular surveillance by endoscopy.

MENETRIER'S DISEASE

- It is a condition with giant gastric mucosal folds (hypertrophic gastropathy) in the fundus and body of the stomach-*'cobblestone appearance'*.
- Histologically, it shows hyperplasia, mucosal thickening and gastric gland atrophy.
- Hypoalbuminaemia, anaemia and hypochlorhydria is common.
- Antrum is not involved.
- There is over expression of transforming growth factor alpha (TGFα) peptide which binds to epidermal growth factor (EGF).
- There is foveolar surface mucus cell hyperplasia with absence of *parietal cells* causing excessive mucus production, protein loss and achlor/hypochlorhydria.
- It is associated with CMV infection in children and *H. pylori* infection in adult.

Clinical Features

- Epigastric pain, anaemia and weight loss.

Investigations

- Serum total proteins, albumin.
- Gastric function tests.
- Barium meal studies, gastroscopy.

Menetrier's disease

- Giant folds in fundus and body
- Gastric gland atrophy
- Hypochlorhydria
- Hypoalbuminaemia
- It may turn into malignancy
- Antral sparing

Treatment

- *Total gastrectomy* is the treatment if there is massive protein loss or dysplasia or carcinoma.

Menetrier's disease may turn into malignancy.

DUODENAL DIVERTICULA

Types

1. **Primary:**

- Occurs in the 2nd or 3rd part of duodenum.
- Are congenital in origin, with all the three layers of duodenum.
- Are usually asymptomatic.
- Diagnosed by endoscopy.
- Treated if required—excision by endoscope or open method.

2. **Secondary:**

- Most common type.
- Always of acquired type.
- Occurs in the 1st part of duodenum.
- Due to cicatrised chronic duodenal ulcer.
- Barium meal X-ray shows '*trifoliate duodenum*'.
- Treatment of chronic duodenal ulcer with pyloric stenosis—truncal vagotomy with posterior GJ.



Fig. 20.67: Primary and secondary diverticula of the duodenum.



Figs 20.68A and B: Barium meal picture showing trifoliate duodenum as secondary diverticulum due to chronic duodenal ulcer.

CARCINOMA STOMACH

> *My kinsman, Antonio Bruno, retained the food he had eaten for too short a time, and then threw it up undigested.... His body wasted away through lack of nourishment till little more than skin and bone remained. At last he was brought to his death. The body was cut open for reasons of public welfare. It was found that the opening of his stomach had closed up and it had hardened…with the result that nothing could pass through to the organs beyond, and death inevitably followed.*
>
> —**Antonio Benivieni,** 1507

- '*It is the captain of men of death*'.
- It is more common *in Japan*—70 per 1,00,000 population.
- It is more common in males 2:1.
- Decrease incidence in western world (Western Europe and US)—last four decades. But this decrease is confined to distal gastric cancers. Incidence of proximal gastric cancer is increasing. Carcinoma proximal stomach is not associated with *H. pylori* infection unlike cancers of body and distal stomach.

Risk Factors (Aetiology)

- *Familial*—10%. Napolean and many members of his family died of carcinoma stomach. *Familial gastric cancer* in associated with mutation of *e-cadherin gene* (90% risk). It causes hereditary diffuse gastric cancer. Relatives of such family show mutation of this gene. Whether prophylactic total gastrectomy is needed or not in these high-risk individuals is a debate.
- *Inactivation of p53, over expression of growth factors, bcl-2 gene mutations* are other genetic causes.
- *HNPCC, Li-Fraumen syndrome.*
- Gastric mucosa of people with *blood group 'A'* is more susceptible for carcinogens—diffuse type. It is due to different mucopolysaccharide secretion in stomach of blood group A patients who are more susceptible for carcinogens.
- *Gastric polyps, adenomatous polyp* > 2 cm.
- *Pernicious anaemia*—high-risk 6 times.
- *Gastric remnant*—15 years after gastrectomy and GJ.



Fig. 20.69: Gastrectomy specimen showing ulcerative gastric carcinoma.

- *Diet*—high salt diet, food with more nitrosamines increases the risk. Smoked salmon fish increases the risk. They release polycyclic hydrocarbons. Ingested nitrates and nitrites from preserved food are converted to nitrosamines by GI bacteria.
- Fruits and vegetables rich in vitamin 'C' protect from carcinoma stomach.
- *Chronic gastritis (atrophic, autoimmune)*, intestinal metaplasia. Type A causes proximal gastric cancer. Type B causes distal gastric cancer.
- *Gastric dysplasia*: Chronic gastritis → gastric atrophy → intestinal metaplasia → dysplasia → carcinoma *in situ* → carcinoma—this cycle occurs in body and distal stomach and is often called as *Correa cycle*.
- Smoking, alcohol.
- *Helicobacter pylori infection*—high-risk (Cag A strain) 6 fold increase in incidence. It causes intestinal type of gastric cancer.
- Agammaglobulinaemia—high-risk (2-5%).
- Chronic benign gastric ulcer. Carcinoma arising from benign gastric ulcer is called as *ulcer cance*r of stomach.
- Giant hyperplasia of gastric mucosal folds (*Menetrier's disease).*
- Carcinoma in proximal stomach is common in young and upper socioeconomic group.
- Carcinoma in distal stomach is common in old and lower socioeconomic groups.
- In western countries, carcinoma stomach is more common in proximal, near OG junction. Obesity, young individual, white people, smoking, alcohol intake, gastro-oesophageal reflux, higher social status, high calorie diet and probably genetic factors are the causes for proximal gastric cancers. It is more aggressive, spreads early due to thin muscularis mucosa. It is often diagnosed late. Signet ring type is common. It carries poor prognosis. It needs oesophageal resection.
- In Asian countries, it is still common in distal stomach.
- In India, it is common in south India (4 times than North India).
- Epstein-Barr virus, radiation exposure.
- Occupational—Rubber workers, coal workers.
- Zinc, lead, talc, asbestos all can cause carcinoma stomach.

Precursor Lesions of Carcinoma Stomach

- *Chronic atrophic gastritis*: It is the most common precursor lesion mainly intestinal subtype. In Japan 95% of atrophic gastritis develop early gastric cancer. Incidence is higher in elderly and in those associated with *H. pylori* infection.
- *Adenomatous gastric polyps.*
- *Intestinal metaplasia*: Risk of carcinoma depends on extent of metaplasia in mucosa. *H. pylori* eradication is important here.

  Based on histological and biochemical nature, two types are found:
  - *Complete*: Glands are completely lined with goblet cells and intestinal absorptive cells indistinguishable histologically and biochemically from their small bowel counterparts.
  - *Incomplete*: It contains columnar cells, goblet cells but without intestinal absorptive cells.

It also can be:
  - *Type I*—Mature; goblet cells secret sialomucin.
  - *Type II*—Cells in different levels of dedifferentiation. Cells secrete sialomucin and an abnormal sialomucin (sulphomucin)—a small quantity.
  - *Type III*—Marked dedifferentiation of cells, secreting mainly sulphomucin.

- *Menetrier's disease.*
- *Benign gastric ulcer*: Here risk is 2-5%. But it is related to the size, extent and duration of the benign gastric ulcer. Giant gastric ulcer has got as high as 6–23% risk. Cancer developing in a pre-existing benign gastric ulcer is called as *ulcer cancer.*
- *Stomach remnant (stump carcinoma)*: It can occur after Billroth II gastrojejunostomy (common) or vagotomy GJ. It takes around 15 years or more to develop cancer. Common site is close to the stoma. Atrophic gastritis—metaplasia—dysplasia and carcinoma develops. Altered acid level, duodenogastric bile refluxes are the pathogenesis which increases the peptic activity causing mucosal metaplasia and dysplasia. Earlier history of gastric surgery, recent history of loss of appetite and decreased weight with often a palpable mass are the features. Liver secondaries, ascites may develop in late cases. Gastroscopy with biopsy and CT scan confirms the diagnosis. Treatment is gastrectomy with nodal clearance.

Aetiology for gastric cancer

Environmental/ occupational/diet/habits

- Smoking/alcohol/ obesity
- Low vegetables, diet with low vitamin A and C
- Consuming red meat, smoked salmon fish, cabbage, diet rich in nitrosamines, lead
- Viral infections like EB virus
- Occupational—rubber/ coal workers
- Lower social status—distal cancers
- Higher social status—proximal cancers

Precancerous lesions:

- *H. pylori* infection, chronic gastritis
- Pernicious anaemia
- Intestinal metaplasia
- Adenomatous polyps more than 2 cm
- Agammaglobulinaemia
- Benign gastric ulcer
- Previous gastric surgery
- Menetrier's disease

Genetic and familial

- *E-cadherin* gene mutation in diffuse cancers
- Mutation in APC gene for β-catenin in intestinal cancers—50%
- Inactivation tumour suppressor gene p53 in 30% cases
- Loss of heterozygosity in the BCL2 gene, an inhibitor of apoptosis (intestinal type)
- Amplification/over expression of different growth factor receptors
- HNPCC—carries 5-10% risk of gastric cancer
- Li Fraumen syndrome
- Blood group A
- First degree relative carries 3-6 folds increased risk of gastric cancer.
- Monozygotic twins carry more risk than dizygotic
- When both parents have gastric cancer, the siblings are at risk of diffuse proximal gastric cancer
- FAP—10 folds more risk of gastric cancer
- Mutation of H-ras oncogene and over expression of c-erb B2 gene

Pathology



Fig. 20.70: Endoscopic view of carcinoma of stomach.

I. ***Gross types***:

Cauliflower type
Ulcerative type
Leather-bottle (Linitis plastica)

II. ***Lauren's classification*** (DIO classification):

a. *Intestinal type (53%)*:
  - Has got favourable prognosis.
  - Polypoid and superficial types are intestinal varieties—common in *H. pylori* induced. Gland formation and definite cellular architecture are the features.
  - Synchronous/polypoid/superficial types are common.
  - Gastric mucosa is replaced with epithelium that resembles small bowel mucosa.
  - It is common in men and aged individuals, probably has environmental factors, commonly shows haematogenous spread, *microsatellite instability*, APC gene mutations, p53, p16 inactivation.

b. *Diffuse type (33%)*:
  - It has got poor prognosis. Common in blood group A, familial type, young people and females.
  - It is usually poorly differentiated/signet type with early gastric wall penetration and both submucosal and subserosal lymphatic spread.
  - Linitis plastica, ulcerative growth without glandular formation is common in this type.
  - It shows decreased E-*cadherin* with p53, p16 inactivation.

c. *Others*—Unclassified (14%).

III. ***Depending on the depth of invasion***:

a. *Early gastric cancer* is defined as involvement of *mucosa and/or submucosa* only with or without involvement of lymph nodes – T1 + any N.

It is being classified as:

(Japanese's classification)

1. Protruded.
2. Superficial—elevated (a), flat (b), depressed (c).
3. Excavated.

It is:
  - More common in Japan—50% of gastric cancers treated are early gastric cancers. In USA—20%.
  - 10% of early gastric cancers will have nodal metastases. 3% in only mucosal lesions. 20% in submucosal lesions.
  - Nodal spread in early gastric cancer depends on tumour size (> 2 cm) and differentiation.
  - About 70% are well-differentiated.
  - Endoscopic mucosal resection (EMR) is possible in cancer of only mucosal lesions.
  - Overall cure rate with adequate gastric resection and lymphadenectomy—95%.

b. *Advanced gastric cancer* is defined as involvement of *muscularis and/or serosa* with or without involvement of lymph nodes.

It is classified as:

(Borrmann's classification):

I. Single, polypoid carcinoma.
II. Ulcerated carcinoma with clear cut margin.
III. Ulcerated carcinoma without clear cut margin.
IV. Diffuse carcinoma—linitis plastica.
V. Unclassified (See Fig. 20.71).

IV. ***Ming's classification***:

- Expanding—favourable prognosis.
- Infiltrative—unfavourable, poor prognosis.


Polypoid
Ulcer-clear margin
Ulcer without clear margin
Diffuse type

Fig. 20.71: Borrmann's classification of the advanced gastric cancer.


Type I
Protruded
Type IIa
Superficial elevated
Type IIb
Superficial flat
Type IIc
Superficial depressed
Type III
Excavated

Fig. 20.72: Japanese's classification for early gastric cancer.

V. ***WHO histological classification of gastric cancer (microscopic)***
- Adenocarcinoma—most common.
  - Papillary adenocarcinoma.
  - Tubular adenocarcinoma.
  - Mucinous adenocarcinoma.
  - Signet-ring carcinoma
- Adenosquamous carcinoma.
- Squamous cell carcinoma—rare, when occurs it is common near OG junction.
- Undifferentiated carcinoma.
- Others—unclassified carcinoma.

VI. ***Proximal gastric adenocarcinoma (Siewert classification)***

Type 1: Carcinoma in Barrett's oesophagus/true oesophageal carcinoma extending to GE junction. Here total oesophagectomy with gastric pull through to neck is needed.

Type 2: Tumour within 2 cm of squamocolumnar junction. Here total gastrectomy with Roux-en-Y oesophagojejunostomy is needed.

Type 3: Tumour in subcardial region. Here total gastrectomy with Roux-en-Y oesophagojejunal anastomosis is done.

VII. ***Morphovolumetric classification:***

It is based on ratio of invasion into muscle to mucosa in advanced carcinoma as:
- *Funnel type*—mucosa involvement is more compared to muscle with a ratio of < 0.15. It carries better prognosis.
- *Columnar type*—equal involvement in ratio of 0.75-1.25.
- *Mountain type*—muscle invasion is more with ratio < 1.25.

VIII. ***Morson and Dawson classification:***
- Nodular.
- Ulcerated.
- Fungating.
- Linitis plastica.

IX: ***Kajitani classification:***
- Localised.
- Intermediate.
- Infiltrating.


A
B
Stomach
Omentum
Tumour

Figs 20.73A and B: Specimen of stomach showing thickening of wall of part of the stomach with loss of rugosity. Omentum, proximal parts are also seen. Thickening is extending into serosa.



Fig. 20.74: Outer look of carcinoma stomach extensively involving including serosa.



Fig. 20.75: Specimen of stomach showing large ulcerative deep lesion in the stomach with raised and everted edge. Loss of rugosity also observed.



Fig. 20.76: Specimen of stomach showing thickening of pylorus—feature of carcinoma stomach. In Asian countries, pylorus is the most common site. In Western countries proximal stomach is the most common site.

Common Site of Occurrence

- Prepyloric and pyloric region (65%) (most common site)
- Body (25%).
- Fundus, OG junction.

But now the incidence of growth in the upper part, near oesophagogastric (OG) junction is increasing.

Note:

- *Synchronous gastric cancer* (Moertel) is histologically proved malignant conditions separated by normal stomach wall. Local extension and secondaries should be ruled out.
- *Distal gastric cancers* are diet related, environmental, epidemic, intestinal type, have better prognosis, with 30% respectability, treated with distal subtotal gastrectomy.
- *Proximal gastric cancers* are not diet related, not environmental, endemic, diffuse type, carries poor prognosis, with less than 20% respectability, treated with total gastrectomy.



Fig. 20.77: Ulcerative lesion with everted edge in the gastrojejunostomy stoma. It usually occurs only after 15 years of gastrojejunostomy surgery.

Spread (Biological Behaviour)

- ***Direct spread***:
  - *Horizontal submucosal* spread along stomach wall.
  - *Vertical spread by invasion* across to adjacent structures like—pancreas, colon, mesocolon, liver.



Figs 20.78A to C: Common sites of carcinoma stomach, (A) Pylorus, (B) Body, (C) Fundus.

- ***Lymphatic spread:***
  - Spread occurs by permeation and embolisation through lymphatics to subpyloric, gastric, pancreaticoduodenal,

splenic, coeliac, aortic, and later to left supraclavicular lymph nodes (Virchow's lymph node—*Troisier's sign).*
  - Retrograde spread to mesenteric nodes of small and large bowel can occur which signifies poor prognosis.

Zones of lymphatic drainage in stomach: Four zones.

Zone 1 lies in gastrocolic omentum along the right gastroepiploic vessels, draining pyloric portion of the greater curve to pyloric, coeliac and aortic lymph nodes.

Zone 2 lies in gastrocolic and gastrosplenic omentum along the left gastroepiploic vessels draining from upper half of greater curve to pancreaticosplenic and aortic lymph nodes.

Zone 3 is drainage from proximal two thirds of the stomach and the upper lesser curve along the left gastric artery. Zone 3 drains into perioesophageal lymph nodes.

Zone 4 is from distal portion of lesser curve and pylorus along hepatic artery into para-aortic nodes.

Lymph node groups

- *Group I:* Perigastric nodes
- *Group II:* Along the root of major vessels
- *Group III:* At the root of superior mesenteric artery and hepatoduodenal ligament
- *Group IV:* Distant lymph nodes

- ***Blood spread***
  - It occurs to liver (most common) causing multiple liver secondaries presenting as multiple, hard, nodules with umbilications due to central necrosis.



Fig. 20.79: Carcinoma stomach showing umbilicated secondaries in liver.

  - Later lungs and bones can get involved.
- ***Transperitoneal spread***
  - It can cause peritoneal seedlings (leading to ascites) and also can cause *Krukenberg's tumours in ovary* in menstruating age group (Commonly seen in colloid carcinoma of stomach).
  - Krukenberg's tumour can often occur without ascites. This is explained by possible *retrograde lymphatic spread* from stomach to ovary. This is favoured by absence of ascites, no denudation/implantation/adhesions on the ovarian surface. Through lymphatic spread, even early gastric cancer can cause *Krukenberg's tumour*. In Japan, 17% of ovarian tumours is Krukenberg's secondaries from carcinoma of stomach. Occasionally Krukenberg's tumour can arise from carcinoma breast (lobular), other abdominal organs also.
  - Rectal secondaries *(Blumer shelf), Sister Mary Joseph* umbilical secondaries are through transperitoneal spread.
  - Transperitoneal spread is best identified through laparoscopy and confirmed by laparoscopic biopsy.



Fig. 20.80: Krukenberg's tumour involving both ovaries from carcinoma of stomach. It is due to transcoelomic spread or through peritoneal lymphatics or blood spread. It usually occurs during ovulation period.

TNM Staging of Carcinoma Stomach

TNM Staging, 7th edition, 2010

Tumour – T

Tx—tumour cannot be assessed
T0—no evidence of tumour
Tis—carcinoma *in situ*, intraepithelial tumour without invasion
T1a—invades lamina propria or muscularis mucosa
T1b—invades submucosa
T2—invades muscularis propria
T3—invades subserosal connective tissue without invasion of visceral peritoneum or adjacent structures
T4a—invades serosa/visceral peritoneum
T4b—invades adjacent structures

Nodes – N

Nx—cannot be assessed
N0—no nodal spread
N1—1-2 regional nodes
N2—3-6 regional nodes
N3a—7-15 regional nodes
N3b—16 or more nodes

Metastases – M

M0—no distant spread
M1—distant spread present

Staging

0—T_{is} N_0 M_0
IA—T_1 N_0 M_0

His heart cannot be pure whose tongue is not clean.

IB—T_1 N_0 M_0 / T_2 N_0 M_0
IIA—T_1 N_2 M_0;T_2 N_1 M_0;T_3 N_0 M_0
IIB—T_1 N_3 M_0;T_2 N_2 M_0;T_3 N_1 M_0;T_{4a} N_0 M_0
IIIA—T_2 N_3 M_0;T_3 N_2 M_0;T_{4a} N_1 M_0
IIIB—T_3 N_3 M_0;T_{4a} N_2 M_0;T_{4b} N_{0-1} M_0
IIIC—T_{4a} N_3 M_0;T, N_{2-3} M_0
IV—Any T Any N M_1

Stage I, II,II—*locoregional disease*
Stage IV—*systemic disease*

Japanese classification of gastric carcinoma (JCGC)

It includes following *principles*:

- Basic rules for clinical, surgical, pathological, and final features
- Specific rules for histology
- Gastric biopsy specimen group classification
- Chemo RT response

Nodal spread as per JCGC:

N_x—nodes unknown/cannot be assessed
N_0—no nodal spreads
N_1—Group I nodes only involved
N_2—Group II nodes are involved but not group III
N_3—Group III nodes are involved

Birmingham staging

1—Confined to mucosa/muscularis propria
2—Muscularis/serosal involvement
3—Nodal spread
4a—Residual disease; 4b—metastatic disease

Leather-Bottle Stomach (Linitis Plastica) (7-10%)

- It is an aggressive diffuse type of carcinoma stomach wherein there is enormous proliferation of fibrous tissue involving submucosa of stomach which is thickened, (*Mother of pearl appearance*) but mucosa looks and feels normal.
- It is type IV gastric carcinoma.
- It is *poorly differentiated* type *lacking* glandular formation, showing clusters of small uniform cells often with *signet ring* cells.



Fig. 20.81: Linitis plastica.



Fig. 20.82: Specimen showing features of *linitis plastica*—a diffuse type of carcinoma stomach mainly involving submucosa and deeper layer (mother of pearl appearance). It carries poor prognosis. It is type IV gastric carcinoma. It may be generalised or localised. It is also called as *leather-bottle stomach*.

- It spreads *submucosally* without much inflammatory cells.
- Transmural, lymphatic, intraperitoneal spread and early metastasis is common.
- *Common* in young, females, blood group A and is familial.
- *Clinical features:*
  - Loss of appetite and weight. Later mass may be palpable from the body of the stomach.
- *Investigation:*
  - Small sized stomach in barium meal study.
  - Endosonography is also diagnostic.
- *Treatment:*
  - Total gastrectomy with oesophagojejunal anastomosis.
  - Prognosis is poor.
  - It may be occasionally localised linitis plastica in pyloric antrum which is better operable.

Colloid carcinoma of stomach

- It is 6% common among all gastric cancers, wherein tumour cells contain *colloid* which is histologically typical
- It also signifies *poorer prognosis*
- Common in women

Presentations of Carcinoma Stomach

- *Asymptomatic* in early gastric cancer or often in cancer of body of stomach.
- *Nonspecific symptoms*—indigestion/vague epigastric discomfort, constant nonradiating pain which is not related to food intake.
- *Specific* symptoms depend on the site of tumour—obstruction, dysphagia, mass, etc.
- *Metastatic disease*—liver secondaries, ascites, secondaries in ovary, rectovesical pouch, umbilicus, supraclavicular nodes, lung and bone secondaries.
- *Unusual presentations*—acanthosis nigricans, Irish nodes in the axilla.

Clinical Features

- Recent onset of loss of appetite and weight, early satiety, fatigue. *Microcytic, hypochromic anaemia* (iron deficiency) is common (40%).
- Upper abdominal pain.
- Vomiting with features of gastric outlet obstruction, i.e. [VGP +ve, +ve ausculto-percussion test, +ve succussion splash (to be checked with 4-6 hours empty stomach)].
- *Mass abdomen:* Mass in pylorus lies above the umbilicus, nodular, hard, with impaired resonance, mobile, moves with respiration, all border well made out.
- Dysphagia with mass in upper epigastrium.
- When it arises from the body of stomach, it may present as only mass abdomen.
- Along with jaundice, liver may be palpable with secondaries which are hard, nodular (50%) with umbilication.
- Ascites.
- +ve Troisier's sign.
- +ve rectovesical secondaries. (Blumer shelf) on per rectal examination.
- *+ve Trousseau sign*—migrating thrombophlebitis, also seen in carcinoma pancreas.
- Anaemia, cachexia.
- Haematemesis (15%), melaena.
- Occasionally carcinoma stomach can present as *perforation* to begin with (4%).
- Rarely as secondaries in the liver with silent primary in stomach.
- Secondaries in umbilicus, as Sister Joseph's nodules (spread through ligamentum teres).
- Cutaneous secondaries.
- Krukenberg tumours.



Fig. 20.83: Barium meal showing irregular filling defect in the body of the stomach suggestive of carcinoma stomach.



Fig. 20.84: Barium meal showing irregular filling defect in the pylorus suggestive of carcinoma pylorus.



Fig. 20.85: Barium meal showing irregular filling defect in the body of the stomach due to carcinoma.

Differential Diagnosis

- Acid peptic disease; pyloric stenosis with gastric outlet obstruction.
- Gastritis.
- Pancreatic mass—carcinoma.
- Transverse colon mass—carcinoma.
- Advanced fixed stomach mass may mimic retroperitoneal or nodal mass.

Without human being this world would have been heaven. Production of noble human being was the Perfect Tragedy to this world !!



Figs 20.86A and B: Polypoid carcinoma stomach seen in barium meal picture and also through endoscopy.



Fig. 20.87: Ulceroproliferative growth in the antrum—an endoscopic view.

Investigations

- Hb%, haematocrit.
- Barium meal (Irregular filling defect).
- Single contrast barium studies—sensitivity is 75%.
- Double contrast barium studies—sensitivity is 90-95% in the detection of gastric cancer, comparable to endoscopy.

Barium meal findings in carcinoma stomach

- Irregular filling defect
- Loss of rugosity
- Delayed emptying
- Dilatation of stomach in carcinoma pylorus
- Decreased stomach capacity in linitis plastica
- Margin of the lesion projects outward from the ulcer/lesion into the gastric lumen—*Carmanns meniscus sign*

- Gastroscopy with biopsy—10 targeted biopsies.
- Endosonography: EUS is useful to detect the involvement of layers of the stomach, nodal status and to define whether tumour is early or advanced. All 5 layers are visualised as alternate hypo- and hyperechogenic areas. It gives 90% accuracy for T staging and 80% of nodal staging.



Fig. 20.88: Endoscopic view of the growth in the pylorus.



Fig. 20.89: Carcinoma stomach endoscopic view showing irregular tumour.



Fig. 20.90: Carcinoma stomach as seen through gastroscopy.

- US abdomen to see liver secondaries, ascites, nodes, ovaries. It is not as sensitive as EUS and CT scan.
- Liver function tests and prothrombin time. Secondaries in liver can cause hepatic dysfunction and liver cell failure. Enlarged hepatic nodes can compress CBD and cause obstructive jaundice also.
- Often FNAC from left supraclavicular lymph node when it is significantly palpable.
- *Laparoscopy* to stage disease. Laparoscopy will pick up peritoneal secondaries; detect occult metastases, organ invasion. Guided biopsy of peritoneum and nodes, peritoneal lavage for cytology and laparoscopic US can be done. It will avoid unnecessary laparotomy. *Signs of inoperability will be better identified* like—peritoneal deposits (CT may miss), fixity, liver secondaries, fixed coeliac nodes, para-aortic nodes, ascitic fluid positivity on analysis. It is more accurate than CT.
- CT scan abdomen and CT thorax in proximal tumours to see size, extent, infiltration, LN status, secondaries and operability.



Fig. 20.91: CT scan showing carcinoma pylorus with luminal obstruction.



Fig. 20.92: CT scan showing primary tumour in the stomach with secondaries in the right lobe of the liver. Secondaries are commonly multiple; only occasionally it will be solitary.



Fig. 20.93: CT scan showing multiple secondaries in liver with primary in the stomach.

- *Tetracycline fluorescence test*—gastric cancer cells take up tetracycline given orally which becomes yellow in colour. Under UV light it shows yellow fluorescence.
- CA 72-4 is important tumour marker to evaluate the relapse. CEA, CA 19-9, CA 12-5 are other markers.
- Combined *PET*—CT scan is useful. It is to evaluate metabolic, physiologic and functional activity. It is mainly useful to identify recurrent gastric cancer.
- *Sentinel node biopsy*—99mTc colloid peritumoral injection during gastrectomy. It has got sensitivity—80%, specificity—100% but not widely used.

Treatment

Surgery is the treatment of choice for carcinoma stomach.

Most intelligent animal is human being, but he happened to be the most cruel animal also.

Preoperative preparation

- Correction of anaemia, nutrition, fluid and electrolyte
- Cardiac, respiratory and renal status assessment
- Stomach wash using normal saline
- Prophylactic antibiotic as achlorhydria in gastric lumen allows colonisation of *Streptococcus faecalis*, *E. coli*, bacteroides, *Staphylococcus ablus*
- Blood/FFP may be needed preoperatively and for surgery

1. If it is an early growth, as in case of pylorus, *lower radical gastrectomy* with proximal 5 cm clearance is (*Subtotal gastrectomy*), along with removal of greater omentum, lesser omentum, all lymph nodes, spleen (to clear splenic lymph nodes), tail of pancreas (when required); and later Billroth II anastomosis.
2. In case of growth in the OG junction or upper part of the stomach, *upper radical gastrectomy* is done along with removal of spleen, both omentum, lymph nodes; and later *oesophagogastric* anastomosis. *Total gastrectomy is ideal here.*
3. In case of growth in the body or *linitis plastica, total gastrectomy (radical) with* oesophagojejunal anastomosis is done.



Figs 20.94A to C: Gastrectomies for carcinoma stomach: (A) Lower radical gastrectomy; (B) Upper radical gastrectomy; (C) Total radical gastrectomy.

Note:

- In tumours of antrum or body of the stomach, *subtotal gastrectomy is ideal*. Total gastrectomy is not done.
- *Total gastrectomy* with reconstruction is better option for *proximal growth, aggressive growth from body or linitis plastica*. It reduces heartburn, dumping, improves appetite better with better functional outcome. Roux-en-Y oesophagojejunostomy is the reconstruction done.
- *Distal clearance* towards duodenum is 1 cm from tumour end; proximal clearance is 5 cm.
- *D1 gastrectomy* is clearance of perigastric nodes; *D2 gastrectomy* is clearance of nodes along major vessel trunks—along coeliac and splenic arteries. D2 is always better than D1.
- ***D2 gastrectomy and adjuvant chemoradiation is ideal present concept therapy in operable carcinoma stomach.*** *D2 gastrectomy includes*—removal of stomach with growth, omental bursa, greater and lesser omentum, anterior layer of mesocolon, anterior pancreatic capsule, D2 lymphadenectomy.
- Prophylactic splenectomy once practiced is no longer found useful. It is done only if the tumour is adherent to spleen or its vessels.
- In early well circumscribed lesion, clearance of 2.0 is adequate but infiltrating tumours need 5 cm clearance.
- D2 dissection is better than D1 dissection of lymph nodes.
- *Omentectomy* (both greater and lesser) and *bursectomy* (removal of outer leaf of transverse colon baring colic vessels) should be added.
- Absolute curative resection is done—when there is absence of serosal, peritoneal, hepatic spread; with free adequate resection margin, with adequate nodal clearance (D dissection exceeds one level more the N nodal involvement).
- In operable cases, *neoadjuvant chemotherapy* improves the survival.
- Ideal reconstruction is either directly into the duodenum or in total gastrectomy using jejunal interposition with creation of reservoir. In distal gastrectomy Polya reconstruction is used.
- When the tumour is located upper or middle posterior wall of the stomach with serosal involvement without distant metastases *left upper abdominal evisceration* can be done. This *extended combined resection* includes—total gastrectomy, pancreaticosplenectomy, transverse colectomy always, occasionally may include left hepatectomy, left nephrectomy, and left adrenalectomy with resection of part of the left diaphragm. Its significance is doubtful.
- *Extended resection* means total gastrectomy with distal pancreatectomy with splenectomy.
- Para-aortic dissection is removal of fatty tissue and nodes from aortic hiatus to origin of inferior mesenteric artery often with left adrenalectomy to clear area adjacent to left renal artery.

Presently newer staging for dissection is practiced in Japan—D1, D2, D3, D4 depending on levels of lymph nodes cleared ('D' for dissection). D1 or D2 dissections are commonly done.

- **D1** is done when nodes are N_0. It is removal of nodes along the lesser and greater curves and pylorus (Group I: stations 3-6).
- **D2** is done when nodes are N_1. Here nodes like left gastric/common hepatic/splenic/retropancreatic are removed. Splenic nodes can be cleared with or without splenectomy along with removal of tail of pancreas. Here node stations 1-11 are removed. Stations 12-18 are not removed. Average 27 nodes are removed.
- **D3** is done when nodes are N_2. Nodes removed for clearance are hepatoduodenal, nodes along mesentery, middle colic (1-16 stations). Average 43 nodes are removed.
- **D4** is *not commonly advocated*. It is removal of stations 1-18.

D1—involvement of group I lymph nodes
D2—involvement of group I and II lymph nodes
D3—involvement of group I, II and III lymph nodes
D4—involvement of group I, II, III and para-aortic nodes

Note:
All lymph nodes are numbered differently as 'stations' or 'echelons'.

Lymph node stations in gastric carcinoma (Japan)—18 stations are there

1. Right cardiac
2. Left cardiac
3. Nodes along the lesser curvature
4. Nodes along the greater curvature
    a. Along short gastric vessels—4sa
    b. Along left gastroepiploic vessels—4sb
    c. Along right gastroepiploic vessels—4sd
5. Suprapyloric nodes
6. Subpyloric nodes
7. Along left gastric artery
8. Along common hepatic artery
9. Along celiac axis
10. At splenic hilum
11. Along splenic artery
12. At hepatoduodenal ligament
13. Retroduodenal lymph nodes
14. At root of mesentery
15. Around middle colic artery
16. Para-aortic nodes
17. Around lower oesophagus
18. Supradiaphragmatic

First tier nodes: Nodes within 3 cm from primary tumour (stations 1-6)—N_1 (old TNM)
Second tier nodes: Nodes in main and intermediate arterial trunk (stations 7-11)—N_2 (old TNM)
Third tier nodes: Nodes at stations 12-18 (para-aortic and above)—N_3 (old TNM)
Note: 15 lymph nodes must be removed for adequate staging of nodes

4. *Endoscopic mucosal resection (EMR)*
    - It is practiced in Japan in early gastric cancer. Tumour less than 2 cm, elevated, well-differentiated tumours without nodal disease is the ideal selection for EMR. Proper regular endoscopic surveillance is essential in these patients after EMR.
    - Lesion is elevated by injecting normal saline submucosally and elevated lesion with adjacent mucosa is resected using cautery up to muscularis propria; later with clips defect is apposed.
    - It is done in protruded early gastric cancer or ulcer-free depressed cancer which is well-demarcated.
5. *Photodynamic therapy*
    - Intravenous injection of haematoporphyrin derivative photosensitiser is given initially; 48 hours later laser light is delivered to tumour through an endoscope to create interaction between two, releasing highly reactive singlet O_2 which causes tumour necrosis.

Adjuvant Therapy

Chemotherapy

- Mitomycin 10 mg IV single dose in monthly cycles.
- 5-fluorouracil, 250 to 500 mg IV in 5% dextrose daily for 5 days.
- Cisplatin and epirubicin, adriamycin, oxaliplatin, capecitabine are other drugs used at present. (*FAM regime* is 5-fluorouracil, adriamycin, mitomycin C).
- Chemotherapy is also used as palliation in inoperable cases/ metastatic cases whether surgical palliation (if obstruction or bleeding is present) is needed or not.
- Neoadjuvant chemotherapy to downstage the tumour is also used to make it operable later. ECF (Epirubicin, cisplatin, 5 FU), EAP (Epirubicin, adriamycin, cisplatin), FDT (% FU, doxorubicin, triazinate) are used.
- *Bevacizumab* (anti-VEGF) is currently under trial.
- Instillation of mitomycin C impregnated charcoal intraperitoneally is done to control lymphatic disease (Japan). It specifically kills the malignant cells in lymphatics and lymph nodes in the abdomen.

Chemoradiotherapy

- Postoperative radiotherapy (RT) with chemotherapy using 5 FU and leucovorin. Chemoradiation has become the *standard* adjuvant treatment.
- Some benefits are shown but controversial. It is said to be better than adjuvant chemotherapy alone.

Note:
Very less *role for radiotherapy at present.* Many radiosensitive structures in the gastric bed prevents tumour to have effective RT. RT is used as palliative method for painful bone secondaries.

Immunochemotherapy as an Adjuvant

- It is given in *stage III* carcinoma *after* radical gastrectomy. It starts from 5th postoperative day to the end of 2 years.
- It is based on the fact that preoperative T cell counts, percentage, are reduced which can be improved/modulated by this therapy.
- Residual cancer cells or micrometastases can be eradicated by this therapy.
- *Regime contains*—initially *immunotherapy* using weekly intramuscular injections of Picibanil (*Streptococcus pyogenes* derived) immune agent 1.0 clinical unit is given on 5th postoperative day. Later from 10th postoperative day onwards, *chemotherapy* regime consisting of mitomycin C and 5 FU is used as follows—mitomycin C 4 mg/50 kg IV twice weekly for 2 weeks, then weekly for 6 weeks; 5 FU as 500 mg/50 kg IV twice weekly for 2 weeks, then weekly for 6 weeks, then 600 mg/50 kg orally daily for 2 years.

Signs of inoperability

- *Adherent to pancreas or colon or mesocolon*
- *Ascites*
- *Para-aortic lymph nodes*
- *Secondaries in liver*
- ***Palpable mass is incurable but can be resectable surgically***
- Blumer shelf
- Left supraclavicular nodes
- Sister Mary Joseph nodule
- Irish node (Left axillary lymph node secondaries)



Fig. 20.95: Carcinoma stomach resected specimen.

Management of gastric carcinoma

- *Early growth in pylorus*: Lower radical gastrectomy with removal of tumour, proximal 5 cm clearance, nodal clearance, greater and lesser omentum, distal pancreas and spleen (now not regularly removed; it is removed to clear splenic nodes—one of the node stations) and Billroth II anastomosis or Roux-en-Y anastomosis is done. Postoperatively adjuvant chemotherapy should be given—5-fluorouracil, mitomycin, epirubicin, cisplatin, oxalilatin, capecitabine
- *D1 or D2 nodal dissection* should be done for adequate clearance in curative surgery
- *Growth in body, proximal growth, diffuse carcinoma and generalised linitis plastica* are the indications for total radical gastrectomy with oesophagojejunal anastomosis.
- Neoadjuvant chemotherapy in advanced gastric cancer prior to surgery and later gastrectomy.
- Instillation of mitomycin C impregnated charcoal intraperitoneally to control lymphatic disease (Japan)
- Palliative procedures like *palliative partial gastrectomy*, anterior gastrojejunostomy, Devine's exclusion procedure, luminal stenting in proximal inoperable growths, chemotherapy are used in inoperable cases
- In early carcinoma proper lymph nodal clearance is important

Palliative Treatment

- To palliate pain
- To palliate vomiting
- When there is bleeding
- To improve appetite
- *Partial gastrectomy (palliative) is the best method*

Palliative Procedures

- Palliative anterior gastrojejunostomy with jejuno-jejunostomy.
- *Devine's exclusion procedure* wherein instead of removal of tumour, it is excluded with Billroth II anastomosis.
- For unresectable growth in upper part of the stomach, palliation can be attained by inserting tubes through the oesophagus to the stomach like Mousseau-Barbin tube, Celestin tube (like in carcinoma oesophagus). Endoscopic stenting can also be tried.
- Palliative chemotherapy is used in advanced stage.
- RT and analgesia like morphine is used to relieve pain.
- Surgery / endotherapy is used to relieve obstruction. Palliative partial gastrectomy (limited local resection), anterior GJ, laser, stenting are different options.
- Surgery (partial gastrectomy) or endotherapy is required in bleeding.
- Palliation for ascites is difficult even though repeated tapping and chemotherapy is done.

Palliative procedures for carcinoma stomach

- *Palliative partial gastrectomy is the best palliation*
- Palliative anterior gastrojejunostomy with jejuno-jejunostomy
- Devine's exclusion procedure
- M-B tube/Celestin tube insertion for proximal stomach growths
- Endoscopic stenting/dilatation
- Laser recanalisation
- Palliative chemotherapy—FAM regime



Fig. 20.96: *Anterior gastrojejunostomy* is one of the palliative procedures used in case of inoperable carcinoma stomach. It is anterior, antecolic GJ.



Fig. 20.97: *Devine's exclusion* procedure. Here inoperable pyloric tumour is left and excluded. Proximal stomach is transected and used for Billroth II like gastrojejunostomy.

Prognosis

- In early gastric cancer which has undergone good surgical resection, 5-year survival rate is 70-90% in Japan. In India, 5-year survival rate is 20%.
- In advanced gastric cancer it reduces to 20-25% in Japan. In other countries it is still worser.
- Overall prognosis is worse in carcinoma stomach.
- When serosa is not involved 5-year survival is 50%. When serosa is involved it is 20%.
- Nodal spread is a bad prognostic factor.
- Involvement of more than 4 nodes carry poor prognosis.
- In Japan, prognosis is better due to early diagnosis and better technical and staging approach.
- Early gastric cancer has got better prognosis.
- Intestinal type has better prognosis than diffuse type.
- Size of the tumour (2 cm); tumour depth; and histological type and grading.

Prognostic factors

- Early or advanced
- Histological grading
- Staging
- Gross types
- Lymph node status
- Liver secondaries
- Serosal involvement—an important factor
- Intestinal type—got better prognosis than diffuse type
- Ascites
- Response to treatment

Note:

- Recurrence rate is very high in first 3 years after therapy.
- If primary tumour can be removed surgically, it is called as *resectable tumour*. Resectability can be for palliation or along with radical surgery for cure.
- *Operable tumour* means radical gastrectomy with (amenable for) nodal clearance.
- *Inoperable tumour* means not amenable for radical surgery.
- Inoperable tumour can be resectable for palliation.
- **R_0** is resection with complete clearance—no *residual disease*. **R_1** is resection but with microscopic residual tumour. **R_2** is resection with macroscopic residual tumour, **R_3** is unresectable.
- D1 and D2 dissections are different for proximal and distal tumours.
- In early gastric cancers, laparoscopic endoluminal transgastric mucosal resection of the lesion is under trial now.
- Adjuvant chemoradiation (RT with 5-FU as radiosensitiser) is also under trial for proximal tumour, undifferentiated high grade tumour.
- Antrectomy is also called as *hemigastrectomy*. Removal of 60-75% stomach is called as *partial gastrectomy*. Removal of more than 80% of stomach is called as *subtotal gastrectomy*.
- Perforation in gastric cancer has got high mortality.
- Most common site of recurrence is stomach bed, then lymph node and anastomotic site.
- Will Roger's stage migration phenomenon is thorough staging with stage for stage to improve the outcome.

GASTRIC LYMPHOMA

There are two types of gastric lymphomas.

- Primary.
- Secondary.

Note:

- Gut lymphomas are 10% of all lymphomas. It is common in males (2:1). Coeliac disease, alpha chain disease, ulcerative colitis, HIV, transplantation—are the aetiology in general for gut lymphomas. *H. pylori* is relevant for gastric lymphoma.
- It occurs in stomach (55%), small bowel (30%), colon (10%), ileocaecal region (5%).

A. PRIMARY GASTRIC LYMPHOMA

- Primary gastric lymphoma is most common one among GI primary lymphomas.
- It is second common malignant neoplasm of the stomach (5% of gastric malignancies).
- It is common in elderly men and common in the antrum of the stomach.
- It can be infiltrative, ulcerative, nodular, polypoid or combined.
- Gastric lymphomas are commonly of non-Hodgkin's type (NHL—B cell type 98%).
- It is arising from B cells—derived from mucosal associated lymphoid tissue (MALT). So often called as MALTOMA
- Diffuse mucosal thickening which eventually ulcerates—is the pathology.
- Disease remains in the stomach for long time and later spreads to liver and other lymph nodes.
- Association of primary gastric lymphoma with *H. pylori* is well-established. Normal gastric mucosa does not contain lymphocytes but mucosa with *H. pylori* infection contains lymphocytes.
- Usually disease is localised to stomach without any other lymph nodes in the abdomen or mediastinum with normal liver, spleen, bone marrow and total count.

- It is basically a localised disease of stomach to begin with but later to have systemic spread.
- *Main presentation* is mass abdomen, pain, vomiting and loss of weight. Perforation, bleeding, obstruction, gastrocolic fistula are also not uncommon.
- *Dawson's criteria for primary GI lymphoma* (NHL): No palpable superficial lymph nodes; no thoracic lymph nodes in CT scan; normal WBC count and bone marrow; predominant bowel pathology; liver, spleen are normal.
- *Ann Arbor staging:* Stage IE—confined to GIT; IIE – GIT + regional nodes; IIIE – GIT + nodes away from and beyond regional; IVE – GIT + other intra-abdominal organs or extra-abdominal.
- *It can be*—B cell, T cell, low grade, high grade, pure centroblastic, unclassified.

Clinical Features

- Pain abdomen, melaena and mass abdomen which is smooth and firm.
- Loss of weight, loss of appetite.

Gastric lymphoma is associated with:

- Wiskott Aldrich syndrome
- Klinfelter syndrome
- HIV, *H. pylori* (75%)
- Ataxia telangiectasia
- SLE
- Chronic gastritis
- MALT

Complications

- Obstruction.
- Perforation.
- Bleeding.
- Spread to other lymph nodes and liver—only late event.



Fig. 20.98: Gastric lymphoma, endoscopic view. It can be primary or secondary. Secondary is common. Primary occurs first in stomach and later other lymphatic system are involved. Gastrectomy is the treatment with chemotherapy.

Investigations

- Gastroscopy and biopsy.
- Endosonography.
- Peripheral smear, bone marrow aspiration.
- CT abdomen and CT chest and mediastinum.

Treatment

- Radical subtotal gastrectomy is done in primary gastric lymphoma at antrum. Radical total gastrectomy is done in primary lymphoma of proximal stomach.
- *Anti-Helicobacter pylori* therapy. Early primary gastric lymphoma may regress by triple regime.
- Chemotherapy as adjuvant. Drugs are same as used for NHL. RT is also useful.

B. SECONDARY GASTRIC LYMPHOMA

- It is the most common type of lymphoma occurring in stomach. It differs from primary in many aspects.
- Here mainly systemic lymph nodes are involved first and the disease begins in lymph nodes at different regions, later to occur in stomach.
- Peripheral smear shows lymphocytosis; bone marrow shows changes; CT abdomen and chest shows multiple nodal enlargement.
- It is basically a systemic disease extending to stomach.
- Perforation and bleeding are the complications.
- Treatment is mainly chemotherapy—CHOP/ABVD/MOPP/BACOP and other regimes.
- Surgery is not done unless any local complications occur.

Gastrointestinal mesenchymal tumours

- *GIST*—CD 117; CD 34; smooth muscle actin
- *Smooth muscle tumours*—CD 34; smooth muscle actin; Desmin
- *Neural tumours*—S-100; CD 34

GASTRIC SARCOMAS

- Stomach is the most common site of GI sarcoma.
- Leiomyosarcoma is the most common type of gastric sarcoma. Other type is malignant leiomyoblastoma.
- Leiomyosarcoma is common in proximal stomach.
- It attains enormous size with rubbery consistency.
- Mainly spreads through the blood to the liver.

Clinical Features

- Pain, vomiting, anorexia.
- Mass in upper abdomen.

Complication

- GI bleeding.

Investigations

- U/S abdomen and CT scan.
- Gastroscopy is useful in less than 50% of cases.

Treatment

- Subtotal gastrectomy.
- Chemotherapy.

Leiomyosarcoma has got better prognosis compared to adenocarcinoma and lymphoma of stomach.



Fig. 20.99: Gastric sarcomas.

GASTROINTESTINAL STROMAL TUMOURS (GIST)

- It is a rare tumour of GI tract—0.2% of all GI tumours.
- But it is the most common nonepithelial tumour of the gastrointestinal tract. *Stomach is the most common site* of all GISTs—50%; 25% of all GISTS are from small bowel; rectum—15%; colon—10%.
- Equal in both sexes and common in 50-70 years age group.
- GIST arises from interstitial cell of Cajal (pacemaker cell which intercalates between smooth muscle cells and intramural neurons). Mutation of tyrosine kinase and platelet derived growth factor alpha (PDGFα) are the newer pathogenetic theories.
- GIST is classified as very low-risk (2 cm); low-risk (2-5 cm); intermediate risk (5-10 cm) and high-risk (> 10 cm) based on *tumour size* and *mitotic activity* of cells.
- 95% of GISTS express c-kit – CD117 mutations – a specific molecular marker.
- *Kit protein* (CD117, stem cell factor receptor) is a transmembrane tyrosine kinase receptor which is detected by immunohistochemistry. It distinguishes from true smooth muscle neoplasms. 80% of GISTs are positive for CD34—haematopoietic progenitor cell antigen.
- Abdominal pain; weight loss; *GI bleed (most* common presentation) and large mass abdomen are typical. Mass is extraluminal as it is of submucosal origin but expands and compresses the mucosa. 50% of GIST can present as metastatic disease to liver and peritoneum (ascites).
- GIST's almost *never* metastasise to regional lymph nodes.
- It can be spindle shaped (70%); epithelioid (25%); combination.
- *Carney's triad*—extra-adrenal paraganglioma; pulmonary chondroma; gastric GIST.



Figs 20.100A and B: Barium meal X-ray showing gastric teratoma presenting as a large mass lesion compressing gastric lumen. Inset shows CT picture also. Operated specimen is also shown.



Fig. 20.101: Gastric leiomyosarcoma near the fundus—endoscopic view. It is now classified under GIST.

***Investigation*:**

- Mainly CT scan.
- Tumour/molecular marker to differentiate it from sarcomas (immunohistochemistry).
- Endosonography guided biopsy/guided FNAC are important to get histological confirmation.
- 18 FDG PET scan is very useful adjunct to CT but reserved for difficult/equivocal cases.

***Treatment*:**

- Surgical resection of the tumour with part of the adjacent bowel.
- *Imatinib mesylate*—a specific *oral* drug (year 2000) that inactivates tyrosine kinase kit and so prevents phosphorylation of the receptor and proliferation of tumour is very much

beneficial in advanced cases. Now it is also used if tumour size is more than 10 cm; in intraperitoneal rupture/spillage; haemorrhage in GIST; multifocal occurrence. Duration of imatinib is usually one year.

- Newer drug—*SU11248* inhibits tyrosine kinase receptor as well as blocks PDGFRA. Another newer derivative—*sunitinib and dasatinib* is used in imatinib refractory cases.
- Doxorubicin ± ifosfamide is tried in metastatic disease but with only 5% response rate.

***Prognostic factors*:**

- Size of GIST more than 5 cm, male sex.
- High mitotic activity (> 15 mitoses per 30 high power field), mixed pathology (spindle + epithelioid).
- Liver spread.
- KIT exon 9 mutation which is more aggressive than KIT exon 11 mutations—carries poor prognosis.

GIST

- GIST is the most controversial topic.
- Primary nonepithelial tumours are classified as: Group I—smooth muscle type expressing smooth muscle actin and desmin; Group II—gastrointestinal autonomic nerve tumours (GANs/myenteric plexus tumour/plexosarcomas) express neuron specific enolase and s-100 and are aggressive; Group III—dual differentiation; Group IV—uncommitted type.
- GIST can be benign, intermediate/borderline, or malignant. Size and mitotic activity are main factors of malignancy; others are—necrosis, haemorrhage, hypercellularity.
- GIST is common in fundus of stomach. It can be submucosal (60%), subserosal (30%), intramural. Fundal GIST carries better prognosis than small bowel GIST.
- Small bowel GIST is common in jejunum (40%), ileum and duodenum. It can be submucosal or subserosal. It presents with GI bleed, abdominal pain, intestinal obstruction, mass abdomen, intussusception, perforation and cachexia. It often produces HCG causing hyperemesis.
- *GISS*—is gastrointestinal stromal sarcoma. It is common in stomach (50%), small bowel. GISS accounts for 2% of soft tissue sarcomas. 70% of them are symptomatic at early stage. Surgical resection is the treatment.

PYLOROPLASTY

Indications

- Bleeding duodenal ulcer.
- As a drainage procedure after vagotomy in uncomplicated-DU which is not responding to medical line of treatment.
- As a part of procedure like Ivor-Lewis operation and Siguira-Futagawa operation.

Contraindications

- Duodenal ulcer with cicatrisation and scarring.

Types

- ***Finney's pyloroplasty.***
- ***Heineke-Mikulicz pyloroplasty***.

Complications

- Duodenal leak—very dangerous one.
- Later reflux.



Figs 20.102A and B: Types of pyloroplasty. (A) Finney's pyloroplasty, (B) Heineke-Mikulicz pyloroplasty.

GASTROSTOMY

- It is the procedure wherein a tube is passed into the stomach per abdominally for the purpose of enteral feeding.
- It can be *temporary or permanent.*

Types

A. *Serous lined*—for temporary gastrostomy.
B. *Mucosa lined*—for permanent one.



Figs 20.103A and B: Types of gastrostomy. (A) Temporary gastrostomy, and (B) Permanent gastrostomy.

After minilaparotomy, gastrotomy is done. Foley's or Malecot's catheter is placed in the stomach. It is fixed to parietal peritoneum through two circular purse string sutures.

Other Types

- Stamm's temporary gastrostomy.
- Kader-senn temporary gastrostomy.
- Janeway's permanent gastrostomy.
- *Endoscopic percutaneous gastrostomy*—becoming popular (PEG).

Indications

- Oesophageal strictures.
- Any conditions where tube feeding is required for more than 4 weeks (e.g. burns, severe sepsis).
- Major neck surgeries.

Contraindications

- Previous gastrectomy.
- Gastric diseases with impaired gastric emptying.
- Intestinal obstruction.



Figs 20.104A to C: Percutaneous endoscopic gastrostomy (PEG). It is easier and acceptable method and less invasive.

Complications

- Infection.
- Trauma to other organ, e.g. colon.
- Leak from gastrostomy site.
- Aspiration pneumonia.
- Blockage.

GASTRECTOMY

Types

1. *Billroth I* is done for benign condition. Here along with partial gastrectomy, gastroduodenostomy is done.
2. *Billroth II* is done for carcinoma stomach. After partial gastrectomy, gastrojejunostomy is done and duodenal stump is closed.
3. *Lower radical gastrectomy* is done in early carcinoma pylorus. Here along with the growth and proximal 5 cm of stomach, omentum, lymph nodes, spleen with tail of pancreas are removed and Billroth II anastomosis is done.
4. In growth of upper part or OG junction, *upper radical gastrectomy* is done along with *oesophagogastric anastomosis*.
5. In some cases like linitis plastica, *total gastrectomy* along with *oesophagojejunal anastomosis is* done.



Figs 20.105A and B: Types of gastrectomy. (A) Billroth I anastomosis and (B) Billroth II anastomosis.

Indications

- Chronic benign gastric ulcer.
- Benign tumours of stomach (Leiomyoma).
- Carcinoma stomach.
- Stomal ulcer.
- Bleeding ulcer.
- Leimyosarcoma, gastric lymphoma.
- Menetrier's disease.

Complications

- Bleeding.
- Bile leak.
- Duodenal blow out.
- Gastric fistula.
- Dumping syndrome.
- Anaemia.

Pleasure in the job puts perfection in the work.



Fig. 20.106: Different types of gastrectomy. Subtotal—more than 80% of stomach is removed; partial—60-75% removed.

GASTROJEJUNOSTOMY (GJ)

Types

1. Anterior GJ.
2. Posterior GJ.

Anterior gastrojejunostomy is done as a palliative procedure in case of advanced inoperable (adherent posteriorly) carcinoma pylorus to palliate vomiting. It is anastomosis between jejunum and anterior surface of stomach, in front of transverse colon (antecolic).

Posterior GJ is done along with truncal vagotomy, in pyloric stenosis due to chronic duodenal ulcer. *It is posterior, vertical, retrocolic, short loop, isoperistaltic (of Mayo*).

GJ is also done as part of the Billroth II gastrectomy.



Fig. 20.107: Gastrojejunostomy stoma view on endoscopy.

Problems with GJ

- Stomal obstruction.
- Afferent or efferent loop obstruction.
- Dumping syndrome.
- Duodenal blow out.
- Retrograde intussusception.
- Reflux gastritis.
- It is a rare entity occurs after gastrojejunostomy.
- It can occur immediately, in weeks or in months.

RETROGRADE JEJUNOGASTRIC INTUSSUSCEPTION



Fig. 20.108: Retrograde jejunogastric intussusception with gangrene—resected specimen.

- Presents with *pain* above and left of the umbilicus, *haematemesis,* firm, tender *mass* above and towards the left side. Patient becomes better in erect posture.
- Condition causes stomal obstruction.
- Barium meal shows *coiled spring look* within the stomach remnant. *Gastroscopy* is diagnostic.
- It is treated by open reduction of the intussusception with anchoring stitch to the bowel or enteroanastomosis. When gangrenous, resection and *Roux-en-Y anastomosis* is done.

VAGOTOMY

> *In an inquiry which I had formerly instituted, respecting the functions of the stomach, I divided these nerves (the vagi) in the neck of a dog, for the purpose of ascertaining the influence which they possess on the secretion of the gastric juice.... We may conclude that the suppression of the secretions...sufficiently demonstrate, that the secretions of the stomach and intestines are very much under the control of the nervous system.*
>
> —**Benjamin Collins Brodie,** 1814

Types

1. ***Truncal vagotomy*** along with GJ as drainage procedure, is done in case of pyloric stenosis due to chronic DU.



Figs 20.109A to C: Types of vagotomy. (A) Highly selective vagotomy, (B) Selective vagotomy with pyloroplasty, (C) Truncal vagotomy with gastrojejunostomy.

In uncomplicated DU, with failure of medical treatment and when HSV cannot be done, then truncal vagotomy with pyloroplasty is done.



Fig. 20.110: Foreign body in the stomach. It usually does not harm and commonly passes down.

2. ***HSV (Highly selective vagotomy)*** or ***Parietal cell vagotomy or Super selective vagotomy*** is done in case of uncomplicated DU where medical treatment fails. Here only fibres entering the stomach is divided both anteriorly as well as posteriorly. Nerve of Latarjet is retained to supply antrum and so *no drainage procedure is required* (Amdrup). *It has got 10% recurrence rate.*
3. ***Selective vagotomy*** is at present not done often. Here along with a drainage procedure, either GJ or pyloroplasty, vagotomy is done with retaining of coeliac and hepatic branches. It has got 10% recurrence rate.

Complications of vagotomy

Intraoperative	***Late complications***
Injury to spleen/oesophagus/liver/pancreas/thoracic duct stomach Bleeding from phrenic veins/gastric vessels/perioesophageal vessels Pneumothorax Oesophagogastric disconnection *Early postoperative* Gastric atony Lesser curve necrosis in HSV Transient dysphagia	• Vagotomy diarrhoea—20% – Most common complication of vagotomy – Gastric stasis – Hypoacidity with fermentation with bacterial overgrowth causing enteritis – Alteration in intestinal villi and enzyme content, altered small bowel motility due denervation – Altered biliary and pancreatic exocrine function – Cholestyramine 4 gram tid/reverse jejunal loop is the treatment for intractable case • Reflux oesophagitis • Oesophageal stricture • Gallstones—due to bile stasis and gastric atony—15%

Chapter 21 Small Intestine

CHAPTER OUTLINE

- Anatomy
- Meckel's Diverticulum
- Regional Enteritis
- Surgical Complications of Typhoid
- Surgical Complications of Roundworm
- Pneumatosis Cystoides Intestinalis
- Mesenteric Vessel Ischaemia
- Necrotising Enterocolitis
- Small Bowel Tumours
- Benign Tumours of Small Bowel
- Malignant Tumours of Small Bowel
- Carcinoid Tumour
- Short Bowel Syndrome
- Massive Bowel Resection
- Small Bowel Enema
- Capsule Endoscopy
- Small Bowel Enteroscopy
- Enteric/Gastrointestinal Fistula

ANATOMY

The small intestine is 6 m in length. This includes upper fixed (duodenum, 25 cm), lower mobile part (proximal 2/5th is jejunum and distal 3/5th is ileum).

Differences Between the Features of Jejunum and Ileum

	Jejunum	Ileum
1.	Long and few vasa rectae	Short and numerous vasa rectae
2.	Long plicae	Small plicae
3.	Thick wall	Thin wall
4.	Mesentery transparent	Mesentery contains fat
5.	Peyer's patches are scanty	Peyer's patches are abundant, located in the antimesenteric border
6.	Villi, leaf like and more abundant	Villi, finger like and less abundant.
7.	Proximal 40% of small bowel	Distal 60%

Mesentery attaches the small intestine to the posterior abdominal wall, contains blood vessels, lymphatics, fat.

Nerve Supply

Sympathetic supply is from T_9-T_{11} and parasympathetic supply is from vagus. Both pass through coeliac and superior mesenteric plexus.

Bowel wall contains the myenteric plexus of Auerbach which lies between the circular and longitudinal muscle coats; and submucous plexus of Meissner.

Sympathetic nerves are motor to sphincter, inhibitory to peristalsis; parasympathetic nerves are inhibitory to sphincter and stimulates peristalsis.



Figs 21.1A and B: Vascular pattern in (A) jejunum, (B) ileum.



Fig. 21.2: Blood supply of the small bowel.

Normal GIT secretions	
Saliva	1000 ml
Gastric	1500 ml
Intestinal	4000 ml
Bile	1000 ml
Pancreas	1500 ml

Cell type	*Function*
Goblet cells	Mucous
Paneth cells	Lysozyme, tumour necrosis factor, cryptidins
Enterocytes	Absorption
Enteroendocrine cells	Different hormones

Investigations for small bowel diseases

- Barium meal follow through
- Small bowel enema *(Enteroclysis)*
- Plain X-ray abdomen to see intestinal obstruction
- Selective splanchnic angiography to see vascular bleed or malformation (DSA)
- Isotope scintigraphy to see Meckel's diverticulum
- Estimation of faecal fat in 24 hours—normal is less than 7 gram
- *Schilling test* to find out the absorption of vitamin B_{12} from terminal ileum
- SeHCAT bile acid absorption test (selenium labelled) to find out the absorption of bile acids from the terminal ileum
- Many different breath tests are used to find out malabsorption, bacterial overgrowth and transit time
- Jejunal biopsy
- CT scans to see fistula, tumour, and spread
- Capsule endoscopy is very useful

MECKEL'S DIVERTICULUM

> *It appears at a specific site in the ileum and the wall contains each of the several layers of the intestinal tract.... The proof that the diverticulum is a residuum of the communication between the intestinal canal and the umbilical stalk rests in the findings which I have observed in three stillborn, full-term fetuses.*
>
> —**Johann Friedrich Meckel,** 1809

It is a congenital diverticulum arising from the terminal ileum and is part of the unobliterated proximal portion of the vitello intestinal duct.

It is:

- 2% common.
- 2 feet from the ileocaecal valve.
- 2 inch in length.
- 2% of Meckel's diverticulum only will be symptomatic.
- 50% of symptomatic are below 2 years of age.
- 2:1 female preponderance is seen.
- It is congenital, results from incomplete closure of vitello-intestinal duct.
- It is the most common congenital anomaly of small intestine.
- Arises from the antimesenteric border of the ileum, containing all three layers of the bowel with independent blood supply.
- In 20% of cases mucosa contains heterotopic epithelium like gastric (commonest—50%), colonic and pancreatic tissues (5%).
- It may be connected to or communicated with the umbilicus through a band or fistula.
- It may be associated with oesophageal atresia, exomphalos, and anorectal malformations.



Fig. 21.3: Anatomy of Meckel's diverticulum.

Presentations in Meckel's Diverticulum

- Asymptomatic—in majority cases.
- Severe haemorrhage most common, seen in children aged 2 years or younger (*Maroon coloured blood)*.
- Intestinal obstruction due to bands/adhesions/ intussusception.
- Perforation.
- Intussusception, volvulus of small bowel.
- Peptic ulceration.
- Diverticulitis (20%)—features mimic acute appendicitis.
- *Littre's hernia*—it is presence of Meckel's diverticulum in hernial sac as content. It is observed in inguinal/femoral hernia.
- Silent Meckel's diverticulum found during laparotomy or laparoscopy or by radioisotope study.
- Carcinoid or GIST can occur in Meckel's diverticulum.



Fig. 21.4: Meckel's diverticulum.

One cannot love what he cannot respect, whether it be himself or another.

Diagnosis

- Technetium (Tc^{99}) radioisotope scan is very useful (90-95% accuracy). Ninety per cent of heterotrophic gastric mucosa can be identified in Meckel's diverticulum by radioisotope study. It can detect Meckel's diverticulum with minimal bleeding also (0.1 ml/minute). So it is very useful investigation in children presenting with bleeding.
- X-ray abdomen to see complications like obstruction, perforation.
- *Laparoscopy is very useful.*
- Enteroclysis/small bowel enema under fluoroscopy may show the Meckel's diverticulum. It is probably the most accurate investigation.



Fig. 21.5: Laparoscopic view of Meckel's diverticulum. Patient presented with features of acute appendicitis. On laparoscopy, Meckel's diverticulum which was adherent to umbilicus by a cord was found. Appendix was identified separately. Appendicectomy and Mecklian diverticulectomy was done.

Treatment

- Asymptomatic Meckel's diverticulum can be left alone when identified during laparotomy.
- *Resection of a short segment of ileum containing Meckel's diverticulum and end-to-end anastomosis is done.*
- *Meckelian diverticulectomy* with closure of enterotomy also can be done, but chances of retaining heterotopic tissues and stenosis are higher.

Indications for Surgery

- Surgery is done whenever the base is narrow, and in lengthy diverticulum.
- Presence of adhesions or band which may precipitate obstruction, intussusception or volvulus.
- Symptomatic patients or presence of complications.
- If it is found in children below 2 years.


Colon
Meckel's diverticulum
Ileum
Meckel's diverticulum
Meckel's diverticulum
Ileum
Resected Meckel's diverticulum
End-to-end anastomosis
Resected Meckel's diverticulum with ileum
Meckelian diverticulectomy linear stapler can be used
Note:
Care of clearing heterotopic gastric epithelium should be taken. Shoulc avoid stricture formation later.

Fig. 21.6: *Meckel's diverticulum*—surgical treatment. Meckelian diverticulectomy is done by obliquely clamping beyond the base of the Meckel's diverticulum. Care should be taken not to retain heterotopic gastric (or other) epithelium which can be felt like indurated area. Enough precaution should be taken so that stricture will not form later. When heterotopic tissues extend beyond the Meckel's diverticulum into the ileum, then resection of ileum with Meckel's and anastomosis is done. Clamping distal to the base of the Meckel's diverticulum like appendicectomy should not be done. It will cause stricture, leak or retaining heterotopic tissues in the part.

Note:
"Meckel's diverticulum frequently suspected; often sought; seldom found"—Charles Mayo.

- *Duodenal diverticulum* is the most common acquired diverticulum of small bowel.
- *Meckel's* is the most common true congenital diverticulum of small bowel.
- *Duodenal diverticulum*:
  It is common in females; 65% occur within 2 cm of ampulla. Commonly they are asymptomatic; < 5% need surgery. It can be congenital/acquired; true/false; intra or extraluminal. Biliary obstruction, pancreatitis, cholangitis, haemorrhage are *complications*. Diverticulectomy; duodenotomy and invagination of diverticulum when it is very close to ampulla embedded in pancreas; sphincteroplasty are the *treatment*. Perforated diverticulum is treated with serosal jejunal patch/duodenal diversion/duodeno or gastrojejunostomy. Trifoliate diverticula is an acquired one, occurs in chronic duodenal ulcer.
- *Jejunoileal diverticula*:
  It is rare (0.1%). It is false type, common in elderly. They are common in jejunum, often multiple, protrudes from mesenteric border. Chronic pseudo-obstruction, vague pain, malabsorption, haemorrhage, perforation can occur occasionally. Diverticulitis leads into perforation and peritonitis or abscess. Bile salt deconjugation with steatorrhoea, megaloblastic anaemia (vitamin B_{12} deficiency) can occur. *Treatment*—enterotomy with removal of enterolith or resection and anastomosis.



Fig. 21.7: Jejunal diverticula are rare. Often can cause obstruction, haemorrhage. It needs surgical resection.



Figs 21.8A and B: Jejunal diverticula—multiple.

REGIONAL ENTERITIS (Crohn's Disease)

> *We propose to describe, in its pathologic and clinical details, a disease of the terminal ileum, affecting mainly young adults, characterised by a subcutate or chronic necrotising and cicatrising inflammation. The ulceration of the mucosa is accomplished by a disproportionate connective tissue reaction…a process which frequently leads to stenosis of the lumen of the intestine, associated with the formation of multiple fistulas.*
>
> —**Burrill Bernard Crohn, Leon Ginzburg,**
> **Gordon D Oppenheimer,** 1932

- It is a *granulomatous, noncaseating inflammatory condition of the ileum commonly and of the colon often.*
- It is independent of age, sex, socioeconomic status and geographic areas.

Aetiology

- Unknown, but a familial and infective nature is thought of.
- Increased autoantibodies.
- Diet and food allergy.
- It is slightly more common in females.
- DNA of Mycobacterium paratuberculosis was found in intestines of 60% of patient's with Crohn's disease but antituberculous drug therapy has not helped them.
- Focal ischaemia as a vasculitis may be the cause.
- 10% of first degree relatives; 50% of monozygotic twins develop Crohn's disease. Genes NOD2/CARD15 in chromosome 16q12 has got strong association with Crohn's disease. CARD15 is expressed in Paneth cells of the ileum.
- Smoking is related to Crohn's disease as aetiology, as for relapse and for exacerbations.

Causes for Crohn's

- *Infectious—Mycobacterium paratuberculosis* and atypical mycobacteria
- *Immunologic*
- *Genetic*—chromosome 16q—IBDI with $CARD_{15}/NOD_2$ gene (40 fold risk)
- *Environmental*
- *Jews* are more prone
- Smoking, diet, OCPs (controversial), psychosocial factors



Fig. 21.9: Multiple ulcers in the jejunum—Crohn's or tuberculosis.

Pathology

Transmural inflammation
↓
Granuloma formation with linear snake like ulcers
↓
Cicatrisation
↓
Thickening of the bowel wall *(Hose pipe pattern)*
↓
Adhesions
↓
Fistula formation

- There is increased mucous membrane permeability → antigen induced cell mediated inflammatory response → release of cytokines like TNF, interleukin 2 → defect in suppressor T cell → granuloma and other pathology.
- Fibrosis, stricture formation, deep ulcers, oedema of mucosa between ulcer areas which looks like '*cobble stone*', skipped normal areas in between, serosal opacity, mesenteric fat stranding, enlarged mesenteric lymph nodes, abscesses in the mesentery, fistula are the pathology. Small mucosal aphthous ulcers are earliest gross feature.
- Disease may be *inflammatory, stricturing or perforating types*.
- Noncaseating giant cell granuloma with chronic inflammation of all layers; focal arterial blocks in muscularis propria are the microscopic features.
- Extensive *fat wrapping around bowel* which is been thickened, firm, rubbery, incompressible, segmental is typical.

Main features of Crohn's disease

- ❖ Ileum—most common site of occurrence—60%
- ❖ Rectal sparing is usual and common
- ❖ Skip lesion
- ❖ Hose-pipe pattern
- ❖ Linear ulcers and cobble stone appearance of mucosa
- ❖ Transmural

- Mesentery is thickened, oedematous, with enlarged lymph glands which will neither break nor calcify.
- Rarely jejunum, stomach and other parts of GIT like oral cavity, oesophagus are involved.
- In colon (30%), it is commonly observed in caecum and ascending colon.
- Toxic megacolon with acute colitis even though rare, can occur in Crohn's disease.

Note:
Anal fissure is most common anal problem in Crohn's disease. It may lead into perianal abscess and fistula.

Vienna classification of Crohn's disease

- ❖ *Age in years*:
  - A_1: < 40; A_2: ≥ 40
- ❖ *Behaviour*:
  - B_1: Nonstructuring, nonpenetrating
  - B_2: Stricturing
  - B_3: Penetrating
- ❖ *Location:*
  - L_1: Terminal ileum
  - L_2: Colon
  - L_3: Ileocolon
  - L_4: Upper GIT



Fig. 21.10: Crohn's disease in small bowel. It is transmural full thickness disease. In 30% cases colon is involved. Skip lesion, stricture, fistula are common. It can involve any part of GIT occasionally.

Clinical Features

- It is common in young age group.
- Abdominal pain and diarrhoea is the initial slow insidious presentation. There is also asymptomatic period in between.
- Diarrhoea is usually less severe without blood, pus or mucous.
- Mild fever, weight loss, lethargy.
- Crohn's disease may present as tender, firm, resonant mass in right iliac fossa
- Obstruction, fistula formation, often perforation.
- Bleeding which is usually chronic but occasionally massive can occur.

- Perianal disease with fissure, fistula, and abscess can occur in 25% of patients with small bowel Crohn's. It can be the only presentation of Crohn's in 5% of cases. 50% of colonic Crohn's will have perianal disease.
- Extraintestinal manifestations occur in 30% of Crohn's disease.

Presentations

a. ***Acute presentations*** *(5%):*

It mimics acute appendicitis with severe diarrhoea. Often there will be localised or diffuse peritonitis.

b. ***Chronic Crohn's:***

First stage—Mild diarrhoea, colicky pain, fever, anaemia, mass in right iliac fossa which is tender, firm, nonmobile along with recurrent perianal abscess.

Second stage is either acute or chronic intestinal obstruction due to cicatrisation with narrowing.

Third stage—Fistula formation—enterocolic, enteroenteric, enterovesical, enterocutaneous, etc.

It is *precancerous condition but not as much as ulcerative colitis*.

Extraintestinal manifestations of Crohn's disease

- Skin: Erythema nodosum, pyoderma gangrenosum—most common
- Eyes: Iritis, uveitis
- Joints: Arthritis, ankylosing spondylitis
- Sclerosing cholangitis
- Nephrotic syndrome
- Pancreatitis
- Amyloidosis
- *Blood:* Anaemia, thrombocytosis, DVT, arterial thrombosis.

Investigations

- Plain X-ray abdomen, ultrasound abdomen.
- *Barium meal follow through or small bowel enema shows*—
  - Straightening of valvulae conniventes.
  - Multiple defects (*cobblestone* appearance).
  - Cicatrisation of ileum (*string sign of Kantor*).
  - *Rose thorn appearance of the bowel wall.*
  - Radiologically Crohn's disease is classified as non-stenosing type or stenosing type.
- CT scan and CT fistulogram is useful method.
- Colonoscopy usually shows normal rectum; with colon showing aphthoid like ulcers and reddened mucosal margin. Deep ulcers, stricture and fistula will be evident in late cases. Colonoscopy also shows segmental, deep, cobblestone look.
- Blood tests for anaemia, protein loss, mineral and trace element loss like magnesium, zinc, and selenium. There will be raised *C reactive protein and orosomucoid* in active disease.
- Capsule endoscopy is useful investigation.
- MRI to diagnose anal disease.
- *Serum markers*: 90% of patients with Crohn's disease show ASCA (anti saccharomyces cerviside antibody) positive and pANCA (perineural antineutrophil cytoplasmic antibody) negative, whereas in 98% of patients with ulcerative colitis, ASCA is negative but pANCA positive.

Complications of Crohn's

- Intestinal obstruction
- Stricture
- Bleeding
- Fistula formation
- Carcinoma small and large bowel
- Perianal abscess
- Peritonitis
- Pericolic abscess

Differential Diagnosis

- Radiation enteritis and *Yersinia enteritis*.
- Ulcerative colitis.
- Intestinal tuberculosis, *Salmonella*, *Shigella*, CMV
- Carcinoma ileum or caecum.
- Differential diagnosis for mass in the right iliac fossa (carcinoma caecum, actinomycosis, appendicular mass, ileocaecal TB, ectopic kidney, mesenteric lymphadenitis).

Treatment

Medical

- *Cessation* of smoking
- Bed rest, protein and vitamin supplementations. Often nasogastric tube nutrition or TPN is required.
- *Steroids* are mainly used to induce remission of the disease in initial phase. It is less useful for maintenance. Dose is 20-40 mg/day of perdnisolone (0.5 mg/kg/day) for 3-6 weeks. Methylprednisolone infusion IV 60 mg/day for 5-7 days can be given initially. *Budesonide*, a newer steroid shows high first phase metabolism in liver and so in high dose achieves targeted delivery into the intestine. It is often combined with mesalamine or used as an alternate first line therapy.
- *Azathioprine* is used for maintenance therapy. It inhibits the cell mediated immunity. 6-mercaptopurine and cyclosporine are also used. *Tacrolimus* (FK-506) inhibits production of IL_2 and is effective in improving fistula.
- *Salazopyrines* are mainly used in acute ileitis and colitis. It is not useful in inducing remission. 5-aminosalicylic acid (5-ASA) and sulfasalazine are also used. 5-ASA inhibits leokotriene, TNF, interleukin production. It acts mainly on colonic and partly on small bowel mucosa. *Mesalamine* which causes slow release of 5ASA is better with a dosage of 4 gram/day. It is released throughout its passage along the small and large bowel. Mesalamine remains the *first line therapy* for Crohn's disease.
- *Metronidazole* is useful in reducing the anal and colonic pathology by suppressing the cell mediated immunity and also as antibacterial. It is not beneficial for small bowel disease.

When you get to the end of your rope, tie a knot and hang on.

- Monoclonal antibody like *infliximab* is used in severe refractory cases which act against tumour necrosis factor alpha (TNFα). Single dose is used for induction. Later given after 2nd week, 6th week and then once in 8 weeks at a dose of 5 mg/kg. It is also useful in promoting closure of fistula in 60 - 80% cases. But its long term side effects are not confirmed.
- Anti IL_1, anti IL_{12}, anti IL_{18}, anti interferon γ antibodies are tried. *Natalizumab* is recombinant human monoclonal antibodies against α integrin.
- *Antibiotics* are useful in controlling sepsis in fistula, colitis.

Medical therapy

- To induce remission—steroids
- For maintenance—immunomodulating drugs like azathioprine
- Antibiotics, metronidazole (as immunomodulator)
- Monoclonal antibody—infliximab
- Nutritional support

Note:
Patients with Crohn's disease should avoid NSAIDs

Surgery

Indications

- Failure of medical treatment.
- If patient cannot be weaned off systemic steroid after 6 months.
- Intestinal obstruction—*most common indication.*
- Fistula formation, bleeding, malignant change.
- Perforation, fulminant colitis.
- Perianal problems.
- Crohn's disease children with growth retardation.

Note:
Surgery is not to cure the disease, but to correct complications. Recurrence of complications and relapse of disease can occur even after surgery. Patient should be on postoperative azathioprine/6 MP/5ASA.

Surgeries

- Ileocaecal resection (common procedure done because commonly ileocaecal region is involved).
- Segmental resection—conservative resection is better.
- Total colectomy and ileorectal anastomosis. It is only done in extensive colonic Crohn's. Ileoanal anastomosis with pouch is not done after total proctocolectomy or continent ileal pouch is not done as disease may later recur in the pouch itself.
- Stricturoplasty.
- Temporary ileostomy.
- Right hemicolectomy is done occasionally.
- Emergency colectomy may be needed in 8% of patients with extensive severe colitis but with rectal sparing.
- Laparoscopic resection is good alternative.
- Occasionally if rectum is diseased or anal disease is severe then total proctocolectomy with ileostomy is done.
- Corrective surgery for anal diseases like fissure, abscess and fistula.
- Definitive procedures for internal fistulas like ileovesical, ileocolic with faecal and urinary diversions.
- Bypass and exclusion procedures are not commonly used at present.
- In free perforation and peritonitis ileostomy is needed. But later, it is difficult to decide the timing of closure of ileostomy as disease is extensive; it is wiser to do right ileocolic resection or right hemicolectomy in these patients.
- Enterocutaneous fistula is treated with excision of fistula with resection and anastomosis of that particular segment. Organ fistulas are also treated with resection of adherent bowel and closure of organ like urinary bladder wall.
- Small bowel Crohn's causes chronic bleeding; colonic Crohn's often may cause massive bleed. In massive bleed angiographic control or colonoscopy is needed.



Fig. 21.11: Stricturoplasty can be done in Crohn's disease in case of short strictures in the absence of active inflammation.

Note:
Appendicectomy should not be done in acute phase of appendicitis as it may lead to external faecal fistula; if there is no acute inflammation, *elective appendicectomy can be/should be done* as it eliminates appendix as a source of future abdominal pain.

SURGICAL COMPLICATIONS OF TYPHOID

- Typhoid (Enteric fever) is caused by organism—*Salmonella typhi.*
- Mode of transmission is faecooral route.
- Presents initially with fever, chills, abdominal pain.

Typhoid

- *S typhi, S paratyphi* A, B and C
- Gram-negative flagellated bacilli
- Faecooral route is commonest mode of spread
- Asymptomatic human carriers are most important reservoirs (*Typhoid Mary*)
- Peyer's patches, mesenteric lymph nodes, gallbladder, spleen, liver and bone marrow are commonly involved

Complications of typhoid

- Paralytic ileus is the *most common* complication
- Intestinal haemorrhage—as the Peyer's patches in terminal ileum are enlarged and ulcerated—20%. Usually blood transfusion and antityphoid therapy is sufficient to control bleeding. Rarely in massive bleed resection anastomosis is needed

- Perforation
- Cholecystitis and carrier stage
- Venous thrombosis particularly of common iliac vein is known
- Typhoid cystitis, bacilluria, epididymo-orchitis
- Arthritis
- Typhoid osteomyelitis (granular sequestrum)
- Typhoid perichondritis and laryngitis leading to airway obstruction
- Typhoid abscess in liver, spleen, brain and parotid
- Myositis, myocarditis, meningitis

Typhoid (Enteric) Perforation

Perforation usually occurs in 3rd week of the infection:

- Ulcers are multiple, arranged in parallel and in antimesenteric border of the ileum.
- One or more ulcers might perforate and many ulcers may be on impending perforation.
- Patient is toxic, presents with:

- *Severe diarrhoea*
- *Relative bradycardia*
- *Soft abdomen*
- *Obliterated liver dullness*
- *Abdomen without guarding and rigidity (because of Zenker's degeneration)*
- *Initial history of fever for few days then pain abdomen and tenderness, which is progressive*

Associated features

- Splenomegaly
- Fever, headache
- Rose spots in the skin

Investigations

- Possibility of missing typhoid perforation is very high.
- X-ray in erect posture shows gas under diaphragm.
- Widal test is positive.
- Neutropenia is seen in blood.
- Blood culture (90% + ve) and stool cultures are often required. Marrow culture is useful.
- Identification of specific and sensitive markers (to detect Ig G/IgM). These tests are positive even when blood culture is negative.
- PCR assay for typhoid infection is also useful.

Note:

- Incidence of typhoid perforation is 2% of total cases.
- 75-80% of perforations are single which needs simple closure after taking biopsy from the edge of ulcer.
- 20-25% of perforations are multiple which requires either resection or exteriorisation as ileostomy.
- In paratyphoid B fever colon perforation can occur.
- CT scan abdomen is ideal investigation to detect early pneumoperitoneum and fluid collection.

Treatment

- Antityphoid drugs (Quinolones, chloramphenicol, ceftriaxone sodium) are started.
- Later laparotomy is done to close the perforation.
- Ulcers which are on impending perforation should be sutured with serosa.
- Presently, resection and anastomosis is also accepted as treatment when multiple perforated ulcers are present.
- ZIP technique (laparostomy) to reopen the abdomen whenever required is also beneficial.
- Exteriorisation of ileum is ideal in a critically ill patient. Once patient recovers properly after 6-12 weeks closure and continuity is maintained.



Fig. 21.12: Enteric perforation is often severe causing faecal peritonitis. Resection/exteriorisation may be needed in severe cases.

- Closure of perforation with ileotransverse anastomosis is the other option.
- ICU care, TPN/enteral feeding/monitoring/blood transfusion/fluid and electrolyte management/ prevention or management of other complications like DVT/DIC/ARDS/septicaemia.

SURGICAL COMPLICATIONS OF ROUNDWORM *(Ascaris Lumbricoides)*

Life Cycle

Eggs → faecooral route → larvae → portal circulation → liver → hepatic veins → IVC, heart, pulmonary artery → lungs → maturation of larvae (8 weeks) → alveoli, trachebronchial tree → coughed out or swallowed to intestine → adult roundworms → male + female worms union → release of eggs → stool → reinfection.



Fig. 21.13: Roundworm removed from peritoneal cavity. Note the faecal contamination.



Fig. 21.14: Specimen of ileum showing roundworm *bolus*. Bolus causes intestinal obstruction, commonly near terminal ileum.



Figs 21.15A and B: Gastroduodenoscopy view of roundworm. It was removed through endoscopy. Roundworm in proximal bowel can cause pancreatitis, cholangitis. Vomiting of roundworms signifies intestinal obstruction. It need not be due to roundworm obstruction. Because of the obstruction and proximal bowel irritation, worms move proximally into stomach and come out through the mouth. (*Courtesy:* Dr Tantry and Dr Sandeep Gopal, Gastroenterologists, KMC, Mangalore).

Features

- Worm colic.
- Toxicity—fever, tachycardia.
- Subacute intestinal obstruction.
- Acute intestinal obstruction with palpable roundworm bolus per abdomen.
- Perforation—common in the ileum.

Note:

Perforation usually occurs at the site of pre-existing disease like nonspecific ileal ulcer, amoebic ulcer, typhoid ulcer, and suture line.

- Intraperitoneal abscess.
- Dyspepsia, malabsorption, iron deficiency anaemia.
- Due to migration of worm into the CBD/pancreatic duct causes ascending cholangitis with fever, jaundice and upper abdominal pain or features of pancreatitis.



Fig. 21.16: Plain X-ray abdomen in a child showing features of intestinal obstruction due to roundworms in the bowel.

- *Loeffler's syndrome* is due to larvae in the alveoli causing fever, dry cough, chest pain, dyspnoea.



Fig. 21.17: Roundworm obstruction. Worms removed through an enterotomy.

Investigations

- Small bowel enema/barium meal follow through may show roundworms in the ileum.
- US can demonstrate the worms/worm bolus/worm in CBD or pancreatic duct.
- Blood may show eosinophilia, anaemia, hypoalbuminaemia. LFT for worm in CBD.
- Chest X-ray may show bronchitis.
- Sputum or bronchial wash may show larvae or Charcot-Leyden crystals.
- Stool examination may show ova.
- CT/MRI will show worms/obstruction/worm in CBD or pancreatic duct.

Treatment

- Antihelminthic drugs like piperazine citrate 60 ml is given immediately if there are features of obstruction, otherwise at night time. Albendazole, mebendazole are other drugs used. Proper nutrition is important.
- Nasogastric aspiration; IV fluids; observation is sufficient in most of the situations. In 48 hours, obstruction will be relieved and child passes worm bolus per anally.
- Occasionally laparotomy and milking of the worm bolus into the caecum without enterotomy is needed. Once worms are in the colon, hypertonic saline wash per anum makes them to disperse and pass outside.
- Removal of worms by enterotomy is rarely done. Enterotomy should *be securely sutured using silk otherwise reperforation* from sutured site can occur by worm toxins or by worm activity and migration.
- If there is perforation (common site is ileum) or gangrene with peritonitis, peritoneal worms should be essentially removed. Ideally ileum should be exteriorised to prevent suture line breakdown after closure due to worms. Once patient recovers bowel ends are sutured to maintain the continuity and abdomen is closed. Even though it is *ideal method*, it is not commonly performed.
- ERCP, worm extraction and stenting is done for worm in CBD/pancreatic duct.

Treatment of roundworm obstruction

- Drugs—piperazine citrate, mebendazole, albendazole
- Most often by conservative treatment, worms get dispersed and passed per anally. But patient requires nasogastric aspiration, IV fluids, antibiotics, and observation
- If patient is not responding then laparotomy is done. *Worm bolus* in the distal ileum is milked into the caecum. Often enterotomy and removal of worms is required
- Perforation due to worm requires immediate laparotomy, removal of worms and closure of perforation
- Only rarely, resection and exteriorisation is required

PNEUMATOSIS CYSTOIDES INTESTINALIS

- It is transient, thin cysts containing nitrogen in submucosa and subserosa of ileum.
- It is due to increased intraluminal pressure, which forces N_2 through the layers of the bowel due to hyperperistalsis.
- It is associated with chronic duodenal ulcer, chronic pulmonary disease, bowel obstruction.
- In neonates it is associated with necrotising enteritis.
- It is common in subserosal and submucosal planes. Cysts contain nitrogen and hydrogen.
- They can occur anywhere in GIT but commonly seen in jejunum. Later in ileocaecal and colon region.
- Mesentery and peritoneum may also be involved.
- It is equal in both sexes.
- These gas filled cysts in small bowel may rupture into peritoneal cavity to cause *sterile pneumoperitoneum*. Peritonitis is unusual.
- Abdominal pain, distension, bowel disturbances, vomiting are the presentations.
- Intestinal obstruction, haemorrhage, perforations are complications.

Treatment

- *Oxygen therapy* by 70% oxygen for 5 days or hyperbaric oxygen 2.5 atmospheres for 2 hours daily for 3 days.
- Metronidazole therapy.
- Treating the cause; resection only in refractory cases.



Fig. 21.18: Pneumatosis cystoides intestinalis.

Small bowel strictures

Causes

- Tuberculosis of ileum/jejunum
- Crohn's disease
- Radiation enteritis
- Ischaemic strictures—after bowel ischaemia, necrotising enterocolitis
- Nonspecific causes
- *Garrey's stricture* following long standing irreducible hernia occurs after reduction and surgery (due to constriction band causing ischaemia at the site)

Management

- Small bowel enema/capsule endoscopy/CT scan—investigations
- *Treatment*: Treating the cause; resection anastomosis, and stricturoplasty

MESENTERIC VESSEL ISCHAEMIA

Superior mesenteric artery is commonly involved than inferior mesenteric artery. Often superior mesenteric vein can also get involved.

Causes

- *Embolism* (50%)—*Sources*
  - From left auricle, as seen in atrial fibrillation.

  - A mural infarct.
  - Atheroma from aorta or aneurysm.
  - Endocarditis vegetations.
  - Left atrial myxoma.
- *Thrombosis*
  - It may block the origin of the superior mesenteric artery and can cause ischaemia of full length of small bowel. It is life-threatening.
  - It may be due to atherosclerosis or occasionally TAO.
  - Often all main splanchnic vessels—coeliac, superior and inferior mesenteric arteries may be involved by atherosclerosis.
- *Nonocclusive*
  - It is due to hypotension/hypoperfusion.
  - It is due to *vasospasm* due to shock—*nonocclusive mesenteric ischaemia (NOMI)*.
- *Superior mesenteric vein thrombosis,* occurs in patients with portal hypertension, portal pyaemia, sickle cell disease, women with contraceptive pills (OCP).



Figs 21.19A and B: Ischaemic bowel necrosis. It will lead to perforation and peritonitis. So always requires surgical resection.



Fig. 21.20A



Figs 21.20B and C

Figs 21.20A to C: Acute extensive mesenteric ischaemia causing small bowel gangrene. Patient will develop short gut syndrome.

Pathology

- Bowel and mesentery will be oedematous, friable, discoloured, and collected with fluid and blood.
- Once gangrene sets in, perforation can occur leading to peritonitis.



Fig. 21.21: Gangrene of small bowel due to mesenteric vascular ischaemia.

Clinical features

In acute

- *Abdominal pain that is out of proportion* in relation to tenderness; pain is around umbilicus to begin with later diffuse.
- Persistent vomiting, bloody diarrhoea; later shock and toxicity.
- Initially abdomen will be soft but later develops tenderness, rebound tenderness, distension, guarding and rigidity.
- Rectal examination shows bloody stool.

In chronic

- *Post-prandial abdominal pain* is the most important symptom with aversion to food and weight loss.
- *Abdominal angina*—recurrent colicky pain, diffuse in nature occurs with or without food intake.
- *Bloody diarrhoea*—it is a feature of both acute and chronic and is confirmed by rectal examination.
- Later, once severe infarction of bowel occurs; it may present with acute features.

Types

It can be:

- *Acute type,* sloughing of intestinal mucosa occurs in 3 hours; infarction of entire thickness of bowel occurs in 6 hours.
- *Chronic type,* it is slow and gradual process.

It can also be:

- *Extensive* involving large segment of bowel, small or large.
- *Localized:*
  - Colonic localised ischaemia at splenic flexure – commonest.
  - Focal segmental ischaemia often with necrosis in small bowel.
  - Chronic mucosal infarction.

Specific Features of Mesenteric Ischaemia

- It is often considered as intestinal failure.
- It can be *thrombotic; embolic; and nonocclusive* (low flow status—is due to reduced SMA perfusion by underlying causes like cardiogenic shock, mesenteric vasoconstriction or part of systemic disease. There is no documented thrombosis or embolus).
- It is rapidly progressive causing early mortality.
- Clostridium, anaerobic and streptococci infections are evident.
- *Gas bubble in the mesenteric vein* is pathognomonic sign of irreversible mesenteric ischaemia.
- CT/CT angiogram is very useful. An occlusion at the ostium of SMA signifies thrombosis. Embolic occlusion is smooth filling defect, usually distal to origin of middle colic artery sparing proximal small bowel, right side colon and transverse colon. Emboli can be fragments causing multiple patchy necrosis of bowel at different sites.
- Decreased blood volume; poor tissue perfusion; metabolic acidosis; myocardial depression by depressant factor; endotoxaemia; ARDS; renal failure; septicaemia and MODS are the pathological events.
- On laparotomy—*musty smell and dusky look of extensive gangrenous bowel is typical*. When in doubt, ischaemia should be confirmed by oxygen support; warming; on table Doppler.

Investigations

- Plain X-ray in erect posture and US of abdomen.
- CT scan is the investigation of choice.
- Angiogram or CT angiogram is the *most reliable* investigation especially in NOMI. It is also *ideal* for chronic ischaemia.
- Angiogram—on-table angiogram
- Doppler study—on table.
- *Blood tests*: Total count is raised with drop in haemoglobin. Raise in blood urea and serum creatinine is common. Serum phosphate level is increased very early in 4 hours as small bowel is rich in phosphate. Arterial blood gas analysis is often essential. Blood culture may be needed.

Treatment

- *Emergency laparotomy* is done. With the help of Doppler the block is identified and the vessel is opened. The block is removed and the bowel is reperfused.
- If patient has presented after 24-48 hours, gangrene might have already occurred, then resection and anastomosis is done.
- If patient presents within 6 hours, it is possible to prevent gangrene and to salvage the bowel. Emergency SMA angiography is done. Papaverine is injected for vasodilatation (by many studies its benefit is not confirmed). Often heparin (20,000 units loading dose and then maintenance dose of 5000-10000 units 6th hourly) or thrombolytics are injected. Immediate laparotomy is done. SMA is opened (arteriotomy) over the obstruction and thrombus/embolus is removed using Fogarty catheter. Perfusion is maintained. Close monitoring is essential for possibility of formation of bowel gangrene and if it is so relaparotomy should be done for bowel resection.
- In acute condition, *thrombolysis* using streptokinase, urokinase and recombinant tissue plasminogen activator can be tried. It should be done within 8 hours of onset of pain.
- NOMI is often treated with *selective infusion of vasodilator* ***papaverine*** into SMA. It is also used in all types of mesenteric ischaemia. Catheter is placed into SMA under guidance; 45 mg of papaverine given as a bolus initially, later 30 mg/hour continuous infusion with 1 mg/ml concentration. Catheter is usually kept for 2 weeks and repositioning with regular angiographic confirmation is needed. Papaverine being a vasodilator increases the bowel perfusion through end arteries as well as collaterals.
- *Chronic mesenteric arterial ischaemia* is treated with *surgical revascularisation* using aortomesenteric bypass graft and mesenteric endarterectomy. It also can be treated with *PTA with or without stenting*. PTA should not be done if there is bowel infarction. It is done through transfemoral or transaxillary route; balloon should be longer than the lesion and 10% wider than the arterial diameter.

- *Chronic mesenteric vein thrombosis* is treated with anticoagulation or propranolol or oesophageal variceal banding or portocaval shunt.
- Eventually patient requires *oral anticoagulant therapy* using warfarin for 12 months.
- Repeated *post-therapy angiography* is needed in all patients.
- Steroids are given to reduce lysosomal membrane destruction and effects of endotoxins; to maintain arterial resistance and complement activity. High dose hydrocortisone is used.
- Higher generation antibiotics; critical care; ventilator, fluid, electrolytes and nutritional support (TPN) are essential.

Note:

- Minimum bowel length required to be retained is 1.2 meters, otherwise the patient will have high mortality (due to short bowel syndrome).
- Small bowel transplantation is under trial for the same.
- Mesenteric bowel ischaemia has got very high mortality.
- Development of septicaemia, ARDS, DIC, postoperative leak are common.

NECROTISING ENTEROCOLITIS

- Necrotising enterocolitis is an acquired inflammatory disease commonly seen in infants and newborn but occasionally can occur in children and adults. It is more commonly seen in premature babies. It is more common in formula fed babies than breastfed babies. Reduced gut flora make virulent pathogens to act and cause sepsis.
- Common site is terminal ileum, caecum and ascending colon. Often it can involve entire small bowel.
- Gas in the bowel wall and often in portal vein is typical.

Incidence

- Often associated with low birth weight babies.
- Preterm babies 90%.
- Term babies 10%.

Pathogenesis

Hypoxia
Hypothermia
Hypotension
Hyperviscosity
Acidosis

Umbilical artery cannulation
Exchange transfusion
Hyperosmolar feeds
Packed cell transfusion
Over dosage with calcium antagonists

↘ ↙

Mesenteric ischaemia.
↓
Bacterial invasion of mucosa and bowel wall.
↓
Necrosis—skip lesions are common.
↓
Necrotising enterocolitis.

Sites

- Common in small bowel.
- Terminal ileum and caecum.



Fig. 21.22: Necrotising enteritis. Note the segmental involvement of the disease.

Clinical Features

Most babies present with:

- Bilious vomiting.
- Abdominal distension, guarding and rigidity.
- Bradycardia.
- Apnoea, lethargy.
- Gross or occult blood in stool (75%).
- Erythema and oedema of anterior abdominal wall—late feature.
- DIC.
- Mortality is 20%.



Figs 21.23A and B: Necrotising enterocolitis. Skin necrotic lesions are typical. It is common in infants and children but can be seen in adolescents occasionally (*Courtesy:* Dr Rupen, MS, KMC, Mangalore).

Investigations

a. Plain X-ray abdomen:
   - Linear gas shadow in bowel wall.
   - Free intraperitoneal air implies perforation.

b. Blood examination—leukocytosis, anaemia, hyperkalemia, metabolic acidosis.

Complications

- Stricture—small bowel.
- Perforation—peritonitis.
- Colonic stricture can develop lately after healing of ischaemic area. It is seen in 10% of cases.

Management

I. ***Medical therapy***
   - Nasogastric aspiration.
   - Broad spectrum IV antibiotics.

- TPN for 10-14 days.
- Oxygen supplement is required.

II. ***Surgery***

Indications

1. Pneumoperitoneum.
2. An abdominal mass.
3. Dilated intestinal loops.

Procedures done

- Bowel necrosis and perforation—resection with stoma.
- Localised disease—resection and primary anastomosis.

Complication: Extensive bowel resection—short bowel syndrome.

SMALL BOWEL TUMOURS

- They are rare neoplasms—3% of all GI tumours (Even though 80% total length and 90% of mucosal surface area of the GIT is small bowel).
- Common in elderly men.
- Common in New Zealand and Hawaii.
- It can be benign or malignant.
- Early diagnosis is difficult.
- Presentations are vague initially.



Fig. 21.24: Jejunal haemangioma. Surgical resection cured the condition.



Fig. 21.25: Jejunal tumour.

Reasons why malignancy is uncommon in the small bowel (even though it comprises 75% of length and 90% of GI mucosa):

- Rapid transit time, 30 minute to 2 hours. So exposure of mucosa to toxins and metabolites is less.
- Alkaline mucus rich luminal content is protective.
- Cells of small bowel produce the enzyme benzopyrene hydroxylase which detoxifies the carcinogen—benzopyrone.
- High levels luminal IgA provides immunity.
- Plenty of lymphoid tissue in the wall provides immunity.
- Healthy small bowel has got less bacterial load and so their toxic metabolites (as compared to colon).

Risk factors implicated are:

- Bile acids and their metabolites.
- Post-cholecystectomy status.
- Familial adenomatous polyposis (FAP) especially with duodenal adenomas has got very high chance of developing adenocarcinoma.
- Crohn‘s disease has got 100 times increase in incidence of adenocarcinoma.
- Celiac disease increases the risk of lymphoma.
- Peutz-Jegher’s syndrome has got increased risk of small bowel adenocarcinoma.
- Patients with chronic immunosuppression have very high-risk of developing NHL (PTLD—post-transplant lymphoproliferative disorder, HIV) or sarcoma.
- Patient with von Recklinghausen’s disease of neurofibromatosis is prone to develop GI neurofibroma or neurofibrosarcoma.
- Smoking, red meat, alcohol, salt food.



Figs 21.26A and B: Jejunal tumour coming out of serosa.

Presentations

- Asymptomatic initially.
- Features of obstruction/intussusception/bleeding.
- Vague abdominal discomfort.

Investigations

- Often it is very difficult to assess small bowel. It may be on table finding during surgery, while presenting as complication like obstruction.
- Small bowel enteroclysis.
- CT abdomen is better investigation to assess bowel/ nodes/ organs. *CT enteroclysis* shows 90% accuracy.
- Video capsule endoscopy enables to visualise small bowel mucosa properly.
- CT angiography is useful in identifying vascular tumours.
- Enteroscopes (push type or Sonde pull enteroscopes) are technically difficult.
- Intraoperative enteroscopes are useful.

BENIGN TUMOURS OF SMALL BOWEL

- Benign tumors of small bowel are 50% of primary small bowel tumors.
- Adenoma can be potentially malignant.

Types

Leiomyoma or GIST

- It is the most common symptomatic benign tumour of small bowel.
- It arises from interstitial cell of *Cajal*. It can be spindle cell type (70%) or epithelioid type.
- Commonly they are benign in small bowel.
- GIST express CD_{117} (90%), the c kit proto oncogene protein membrane receptor for stem cell growth factor and CD_{34} (80%), a human progenitor cell antigen.



Fig. 21.27: Leiomyoma of jejunum.

Adenomas

- It is 15% of all benign small bowel tumours.
- 50% are in ileum; 30% in jejunum; 20% in duodenum.
- Commonly single but can be multiple when familial or associated with FAP.
- Commonly presents as bleeding and obstruction.

Adenomas can be:

- *Brunner gland adenoma*
  - It occurs as benign hyperplastic tumour in proximal duodenal submucosa which secretes alkaline bicarbonate rich fluid.
  - Bleeding is the usual problem.
  - It is treated by endoscopic resection.
  - It never turns into malignancy.
- *Villous adenoma*
  - It can occur anywhere in small bowel presenting as intestinal obstruction or haemorrhage.
  - But commonly seen in periampullary region presenting as obstructive jaundice, upper abdominal pain.
  - Size more than 3 cm can lead into adenocarcinoma with an adenoma—carcinoma sequence.
  - EUS is ideal tool to assess size and depth.
  - ERCP is done to relieve obstruction, to biopsy and to remove if it is small in size.
  - Malignant potentiality is very high—50%.
  - Transduodenal excision/pancreaticoduodenectomy are the surgical options. Small bowel adenomas are treated by reception.
- *True adenomas*
  - It can be tubular or tubulovillous.
  - It is usually single.
  - Endoscopic excision is the treatment; resection/pancreaticoduodenectomy is done if there is invasive lesion.
- *Familial adenomas*
  - It is associated with FAP with 5% risk for adenocarcinoma in duodenum.
  - It is diffuse throughout the duodenum.
  - *Spigelman classification* is used for assessment of FAP related duodenal adenomas. Villous adenomas larger than 3 cm or suspicious lesions identified on endoscopy are biopsied.
  - *Screening endoscopy* to be done every year.
  - Endoscopic or open polypectomy; argon beam or photodynamic therapy is tried in benign lesions.
  - Pancreaticoduodenectomy is done in high grade, carcinoma in situ, Spigelman IV classification.

Spigelman classification of duodenal adenomatosis

Parameter about polyps	Point 1	Point 2	Point 3
Number	1-4	5-20	More than 20
Size	1-4 mm	5-10 mm	More than 10
Histology	Tubular	Tubulovillous	Villous
Dysplasia	Mild	Moderate	Severe

Stage	**Points**
0	0
1	1-4
2	5-6
3	7-8
4	9-12

Lipoma

- It mainly causes intussusception.
- It is common in *elderly men*.
- It is usually *single intramural submucosal* lesion.
- Lipoma *does not* have malignant potential.

Peutz-Jegher's Syndrome

- Autosomal dominant condition with melanotic pigment patches and GI polyps.
- Brown black pigments of 1-2 mm diameter in circumoral face, cheek, forearms, palms, soles, digits, perianal region.
- Hamartomas are located in entire jejunum and ileum; 50% of colorectum; 25% of stomach.
- Intussusception, bleeding, anaemia—presentations.
- Cancer of small intestine, stomach, pancreas, ovary, lung, uterus and breast can occur.
- Cure is not possible. Segment which is causing complication is resected.

Haemangioma

- It is 4% of all small bowel benign tumours.
- They are multiple in 60% of patients.
- They are usually submucosal abnormal proliferative vessels.
- Jejunum is the commonest site.
- They are often seen in association with *Osler Weber Rendu disease, Turner's syndrome*.
- It presents as small bowel bleed.
- It can be diagnosed by angiography, $^{99}m_{Tc}$ RBC scanning or capsule endoscopy.
- *Treatment*: Endoscopic sclerotherapy or angiographic embolisation or resection of bowel segment.

General Features

- They cause haemorrhage, colicky pain, and intussusception.
- Diagnosis is by suspicion. Small bowel enema, capsule endoscopy, radioisotope study, CT scan or MRI may help in identifying the disease. Laparoscopy and proceed may be useful.
- Commonly it is on table finding during exploration for acute presentations.
- Adenomas are potentially malignant depending on the size (> 3 cm).

Treatment

- It depends on type, number, nature, size of the tumour.
- Resection and anastomosis cures the condition.
- Surgery is not done for Peutz-Jegher's syndrome unless it presents with complications.

MALIGNANT TUMOURS OF SMALL BOWEL

1. Adenocarcinoma

- Its incidence is 40% of small bowel tumours.
- It is most common primary malignant small bowel tumour.



Fig. 21.28: Resected small bowel specimen showing small bowel adenocarcinoma.

- In 80% cases it is in the duodenum and jejunum.
- FAP, adenoma, Crohn's, coeliac diseases are the causes.
- Adenocarcinoma in *Crohn's disease* occurs in younger age group and commonly in ileum (70%).
- Nonspecific features, anorexia, crampy pain abdomen, bleeding and diarrhoea, obstruction or features of metastases (liver).
- CT scan, capsule endoscopy are the investigations.
- TNM system is used for staging.
- Nodal spread is the important prognostic factor.
- Surgical resection is the choice of therapy. *Pancreaticoduodenectomy* is done for duodenal tumour; for ileal/jejunal site tumours *radical resection* with 10 cm margin with adjacent mesenteric clearance is done. Adenocarcinoma of terminal ileum is treated with *right hemicolectomy*.
- RT and chemotherapy are less beneficial.
- It carries a poor prognosis.



Fig. 21.29: Carcinoma ileum near ileocaecal junction. It (adenocarcinoma of ileum) carries poor prognosis. It is often on table diagnosis.



Fig. 21.30: Jejunal adenocarcinoma presenting as stricture with features of proximal small bowel obstruction.

2. Non-Hodgkin's lymphoma (NHL)—25%



Fig. 21.31: Gross look of small bowel lymphoma.

- GI is the commonest extranodal site of NHL (20%), with small bowel (primary intestinal NHL) as second common site (30%) for extranodal site of NHL (First common site is stomach—60%).
- Lymphadenopathy/mediastinal lymph node enlargement are absent. Normal spleen, liver, blood peripheral smear are observed.
- B cell type is the commonest type 75%. It is common in ileum.
- T cell type (25%) carries poor prognosis.
- Presentations are malabsorption, obstruction, perforation, haemorrhage or palpable mass.
- In children lymphomas are the most common intestinal neoplasm.
- 25% of patients develop perforation.
- Fever when present suggests systemic spread.
- CT scan with CT guided biopsy or laparoscopic biopsy is needed.
- Surgical resection and chemotherapy are the treatment.
- Prognosis is poor.

3. Carcinoid tumour—30%.

4. GIST (gastrointestinal stromal tumour)

- It is rare but most common nonepithelial small bowel tumours.
- 25% of GIST occurs in small bowel (stomach—50 to 60%). It is 0.2% of all GI tumours.
- It is equal in both sexes.
- It arises from interstitial cell of Cajal.
- More than 95% show c-kit (transmembrane receptor tyrosine kinase) mutation.
- Many mesenchymal tumours of small bowel are now classified as GIST. GIST attains massive size when presenting clinically.
- Palpable mass, compression, haemorrhage are the features; has *less affinity* for lymphatics.
- CT is diagnostic. Histochemistry and tumour markers are needed.
- GIST can be low risk or high risk group based on tumour size and mitotic index.
- Surgical wide resection is the treatment.
- Imatinib mesylate a KIT kinase inhibitor is used successfully. SU11248 with similar effect is also used.



Fig. 21.32: GIST of small bowel (*Courtesy:* Dr Chinivalar, MS, Surgeon).

5. Liposarcoma and myxoliposarcoma.

6. Secondaries in small bowel

They are very rare—if it is present, primary being commonly melanoma.

Malignant tumours of small bowel

- Adenocarcinoma is commonest—40%. Order of occurrence—duodenum, jejunum and ileum
- GIST is new entity comprising smooth muscle tumours also
- Carcinoid and lymphoma has got better prognosis
- Adenocarcinoma and GIST has got poor prognosis
- Presentations are pain, diarrhoea, weight loss, anaemia, melaena, palpable mass, intestinal obstruction and metastatic features
- Bleeding and perforation are common in lymphoma and sarcoma
- Enteroclysis/capsule endoscopy/CT scan/histochemistry are needed to diagnose
- Surgery is the main therapy
- Imatinib is used in GIST with favourable results

CARCINOID TUMOUR

- The term *'Karzinoids'* was coined by Oberndarger in 1907.
- They arise from the enterochromaffin cells (Kulchitsky cells) found in the crypts of Lieberkuhn.
- These cells are capable of APUD (Amine precursor uptake and Decarboxylation) and can secrete vasoactive peptides.
- It commonly occurs in appendix (45%), ileum (25%) and rectum (15%). Other (15%) sites are—other parts of GIT (including pancreas and biliary tract), bronchus and testis. In the ileum it is almost always in the terminal 2 feet.
- Metastasis occurs in 3% of appendiceal carcinoid; 35% of ileum.
- 75% of carcinoids are less than 1 cm and 2% of them will spread; carcinoid of 1-2 cm shows 50% chances of spread; more than 2 cm shows 85% chances to spread.
- 75% of carcinoids are asymptomatic and found incidentally.
- It secretes amines (**5 HT**, 5 HIAA, 5 HTP—85%, histamine, and dopamine), tachykinins (kallikrein, substance P, neuropeptide k), peptides (**chromogranins**—100%, pancreatic polypeptide—40%, neurotensin, HCG α, HCG β, motilin), prostaglandins.
- 10% of cases are associated with MEN syndrome type I.
- Pathologically it is smooth, firm, yellowish submucosal nodule seen in antimesenteric border of bowel with mesenteric nodal mass having desmoplastic reaction.
- Carcinoid in appendix is usually single. But commonly it causes luminal obstruction and so presents with features of appendicitis. Common site is at tip/distal 2/3rd.
- Small bowel carcinoids are multiple in 40% cases. In 50% of cases other primary malignancy is observed like of breast and colon.
- Small bowel carcinoids (jejunoileal) < 1 cm incidence, of nodal and liver spread is 20-30%. If it is 1-2 cm, nodal spread is 60-80% and spread to liver is 20%. If it is > 2 cm, nodal spread is more than 80% and spread to liver is 50%.

Types of Small Bowel Carcinoids

1. *Foregut carcinoids* (Bronchial, thymic, gastroduodenal, pancreatic): Produce low levels of serotonin, but may secrete 5 HPT (5 hydroxy tryptophan) and ACTH.
2. *Midgut carcinoids* (Jejunal, ileal, appendiceal, right colic): Secretes high levels of serotonin.
3. *Hindgut carcinoids (*Distal colon, rectum): Rarely produce serotonin, but produce somatostatin and peptide YY. They present as submucosal nodules without ulcer. Hormonally inactive.

Foregut carcinoids—argyrophillic (cells can be stained with metallic silver only in the presence of reducing agent)
Midgut carcinoids—argentaffin (stained with metallic silver without a reducing agent) and argyrophillic both
Hindgut carcinoids—do not stain with silver



Fig. 21.33: Carcinoid of ileum. It often presents when liver secondaries develop as carcinoid syndrome. Resection and anastomosis is the treatment.

Features of Small Bowel Carcinoids

- Primary tumour is usually small < 1 cm.
- Age: Seen in 50-60 years.
- May be multicentric in small bowel—40%.
- May coexist with synchronous adenocarcinoma of small or large bowel (10%).
- Highest propensity to metastasise to liver to produce carcinoid syndrome.

Clinical Features

- Most often asymptomatic—an incidental finding.
- May present with abdominal pain, features of intestinal obstruction, diarrhoea.
- Hindgut carcinoids present with constipation, bleeding per rectum, rectal tenesmus.
- Once secondaries develop in the liver (which is yellowish) ***Carcinoid syndrome*** develops (10%), which is due to release of 5-HT, kinins, prostaglandins, histamine and indoles causing flushing, diarrhoea, cyanosis, asthmatic attacks, hepatomegaly, cardiac lesion on right side.
- *Attacks can be induced by alcohol.*

Investigations

- *Urine shows increased 5-hydroxyindoleacetic acid (5HIAA) levels. (Normal value—2-8 mg/24 hours).*
- ^{111}In-octreotide scintigraphy to detect the tumour.
- CT scan is very useful for evaluation.
- I_{131} MIBG scan is also done.
- *Plasma level of chromogranin A* will be elevated in 80% of patients.
- Provocative tests using pentagastrin, calcium or epinephrine may be used.
- PET scan using 1C 5 HTP and 18 F L DOPA isotopes when fused with CT scan will give the best image; with urine 5 HIAA and serum chromogranin A, diagnosis will be accurate.

Treatment

- If it is in the tip of the appendix (*tip is common*), appendicectomy and regular follow up with urine 5HIAA is sufficient.
- If it is in the base of appendix or appendicular lesion > 2 cm size or terminal ileum, right hemicolectomy is required.
- In small bowel, if the primary tumour is < 1 cm, with no lymph nodes, then segmental intestinal resection and anastomosis is sufficient. Radical resection of bowel is necessary in case of large, multiple carcinoids, with involvement of lymph nodes.
- In liver secondaries, along with surgical debulking hepatic resection, hepatic artery ligation or embolisation is tried.

Surgical treatment

- *Appendix*
  - Tip/lesion less than 2 cm but not involving base—appendicectomy
  - Lesion more than 2 cm/involving base—right hemicolectomy
- *Gastroduodenum*
  - Less than 1 cm—endoscopic resection
  - More than 1 cm—subtotal gastrectomy/pancreaticoduodenectomy
- *Small bowel lesion*
  - Less than 1 cm—segmental resection
  - More than 1 cm—radical resection with adjacent mesentery
  - Terminal ileum—right hemicolectomy
- *Rectal lesion*
  - Less than 1 cm—endoscopic resection
  - 1 cm invasive—wide excision
  - More than 1 cm—anterior resection

Medical treatment

- Mainly symptomatic
- Long acting somatostatin analogue—octreotide can be given—90% symptom palliation is achieved
- Slow release formulation of octreotide (*Sandostatin LAR*) is also used
- *Pasireotide* is 2nd generation octreotide which has got wide somatostatin receptor inhibition action (40 fold than octreotide) is said to be very effective
- Ketanserin (to control diarrhoea), cyproheptadine, ondansetron are also effective
- Bevacizumab (antiangiogenesis factor), sunitinib (Tyrosine kinase inhibitor), everolimus (m TOR inhibitor) are other agents tried
- Others: Serotonin antagonists, antihistamines, alpha methyl dopa, 5-fluorouracil
- Bromocryptine, streptozocin, doxorubicin, dacarbazine, 5 FU, methylsergide, diphenoxylate hydrochloride, interferon
- Radiolabelled somatostatin analogue
- Indium 111 labelled pentetreotide is also effective

Note:

- Methysergide causes retroperitoneal fibrosis and so not used now.
- Anaesthesia may precipitate carcinoid syndrome during surgical treatment; IV octreotide infusion 50 µg/hour with steroid and antihistamines are needed in such patients.

Carcinoid Syndrome

- It occurs in 10% of carcinoid tumours.
- It is common in small bowel carcinoid, but can occur in other sites also—bronchus, pancreas, testis, ovary.
- It is the (first pass metabolism site) *liver secondaries* which cause the *carcinoid syndrome*. Carcinoids of ovary, testis and retroperitoneum bypass the first pass metabolism in liver and so causes syndrome without liver secondaries. Rarely carcinoid syndrome develops in noncarcinoid malignant tumour and dermatomyositis.
- Syndrome is due to release of 5 HT, 5 HTP, histamine, dopamine, bradykinin, prostaglandin, kallikrein and substance P.
- **Presentations**
  - *Vasomotor:* Flushing (80%) is the *commonest manifestations* which may be short lived, *diffuse, erythematous* involving face, neck and upper chest; longer, often permanent *cyanotic violaceous flush* with watery eyes; *prolonged flush* for 3 days affecting entire body with oedema face and hypotension; *red patchy flush* seen in carcinoid stomach.
  - *GIT:* Diarrhoea (75%) is next common which is episodic, watery, explosive occurs after meals and is due to raised serotonin level. Hepatomegaly (70%) is common.
  - *Cardiac:* Pulmonary stenosis (90%), tricuspid insufficiency (45%), tricuspid stenosis (40%) are features of right valvular fibrosis—due to serotonin. Bronchospasm (asthma—25%) is due to serotonin and bradykinin.
  - *Diversion of dietary tryptophan causes malabsorption and pellagra.*
- Symptoms are precipitated by intake of alcohol, cheese, chocolate and red wine.
- Severe bronchospasm, circulatory collapse, when not diagnosed can lead into '***carcinoid crisis***'.
- *Treatment*
  - Assessment by 5 HIAA, and other methods mentioned above.
  - IV octreotide infusion, management of circulatory failure effectively using critical care.
  - Treatment of hepatic secondaries—embolisation, chemotherapy, TACE (transarterial chemoembolisation), hepatic artery ligation, radiofrequency ablation.

Prognosis

- Prognosis is very good for carcinoid of appendix. 5-year survival is 90% and commonly appendiceal carcinoid is identified incidentally; they are commonly in the tip or distal 2/3rd of the appendix; nodal spread and liver spread is rare; 75% are less than 1 cm. Two histological types of carcinoid *appendix are goblet cell and classical type*. Goblet cell type carries poor prognosis.

- Small bowel carcinoid has got poorer prognosis compared to carcinoid of appendix. Prognosis depends on size of primary tumour; nodal spread; multicentricity; hepatic spread. Carcinoid has better prognosis than adenocarcinoma of small bowel.

SHORT BOWEL SYNDROME (Short Gut Syndrome)

- It is the symptom complex after massive small bowel resection, i.e. *resection more than 70% of the bowel*. Minimum bowel required is 1.2 meters.
- Proximal jejunal resection is better tolerated than distal ileal resection.
- Ileum is more adaptive and has got capacity to increase the absorption capacity more efficiently. So in massive resections, patients with retained ileum will do better. Adaptation is better if ileum and caecum is preserved.

Causes

- Massive small bowel resection as in superior mesenteric artery ischaemia.
- Multiple sequential resections.
- Recurrent Crohn's disease—common cause.
- Necrotising enterocolitis in neonates and children.
- Intestinal atresia.
- Midgut volvulus.
- Radiation enteritis.

Adaptive changes in the retained small bowel

- Villous hypertrophy and hyperplasia
- Increased absorptive surface
- Increased capacity of small bowel
- Lower transit time of bowel content

Factors Deciding the Outcome in Short Gut Syndrome

- Age—infants tolerate massive resection better.
- Retaining ileocaecal valve shows better outcome. Ileocaecal resection interrupts the enterohepatic circulation of bile salts which in colon get metabolised into secondary bile salts. Secondary bile salts block the absorption of water and electrolytes.
- Delayed clearance of gastrin causes hyperacidity and peptic ulcer.
- Adaptability of the small bowel. Adaptation is better if ileum and caecum are preserved.
- Additional colectomy increases the morbidity. In such occasion retained jejunum will function as either of two ways. '*Net absorbers*' have adequate absorption of water and sodium and usually will have more than 100 cm of retained jejunum. '*Net secretors*' have less than 100 cm of jejunum and lot of sodium and water are secreted into the lumen from plasma. These patients should avoid hypotonic solutions like water/ tea; instead should take hypertonic saline with glucose containing 90 mmol sodium/L. WHO cholera fluid is ideal (contains 90 mmol sodium/L).

Clinical features

- Diarrhoea
- Fluid and electrolyte deficiency
- Severe malnutrition
- Recurrent bacterial enteritis

Outcome of Short Bowel Syndrome

- Severe malabsorption.
- Severe dehydration.
- Gallstone formation due to altered bile metabolism.
- Urinary calculi due to increased oxalate level.
- Water and electrolyte imbalance.
- Diarrhoea is common.
- Recurrent bacterial enteritis.
- Fulminant hepatic failure often can occur.
- Osteomalacia, tetany, hypomagnesaemia.
- Bleeding diathesis, peripheral neuropathy.

MASSIVE BOWEL RESECTION

- Resection of *more than 200 cm* of small bowel is called as massive resection.
- *Metabolic sequelae* in massive resection depend on – extent and anatomical site of resection; functional capacity and adaptation of the small or large bowel; cause for the resection. It causes gastrin hypersecretion, increased parietal cell mass in stomach, peptic ulceration; increased endocrine pancreatic secretion; hypoalbuminaemia, oedema.
- *Resection of more than 100 cm of distal ileum* causes diarrhoea and steatorrhoea (steatorrhoea is faecal fat > 6 gram/day); increases bile lithogenicity; causes deficiency of vitamins A, D, E, K; colonic bacteria converts unabsorbed fatty acids and conjugated bile salts into hydroxy fatty acids and deconjugated bile salts.
- *Ileum* maintains enterohepatic circulation of bile salts, absorption of vitamin B_{12} and vitamin D. Resection of middle part of small bowel is better tolerated.
- *Removal of ileocaecal valve* reduces the intestinal transit time; reduces absorption of vitamin B_{12}, calcium, magnesium, zinc; increases diarrhoea and contamination of shortened small bowel by bacteria.
- In massive resection, *colonic bacteria* degrade fatty acids into lactate and short chain fatty acids; lactate reduces colonic pH which inhibits bacteroides; due to this acid resistant anaerobes will increase in colon which produces large amount of D lactate which is absorbed causing *D lactic acidosis* presenting with confusion, ataxia and nystagmus.
- *TPN* was introduced by Dudrick. It is very useful in short gut syndrome.

Treatment

Early phase

- Total parenteral nutrition.

A man who does nothing never has time to do any thing.

- Fat and fibre free but protein rich liquid diet with essential fatty acids.
- Diarrhoea is controlled by loperamide/codeine phosphate.
- Oral cholestyramine to bind bile salts is needed in massive resection which includes ileum.
- Parenteral vitamin B_{12} injection regularly.
- H_2 antagonists/PPIs/somatostatin (to reduce secretions from stomach, liver and pancreas).
- Octreotide reduces the secretion and reduces GI motility.
- Fluid and electrolyte management.
- Control of diarrhoea.

Late phase

- Enteral nutrition to stimulate intestinal adaptation.
- TPN supplement—often permanently required.
  Home parenteral nutrition is universally used method in western countries. But in Asian countries it is yet not practicable.
- Hormones and glutamine administration are under trial.
- Surgical techniques to delay the intestinal transit time or small bowel transplantation are under trial but with less success.
  - *Reversal of 10 cm intestinal segment* to delay transit time.
  - *Intestinal lengthening* to delay transit time and increase the absorption surface.
  - *Small bowel transplantation*, ideal but graft rejection and failure is the problem.
  - Antiperistaltic colonic interposition into the small bowel segment.
  - Regeneration of intestinal mucosa over denuded serosa.
  - Longitudinal splitting of the intestine and closing of these as separate tubes which are anastomosed to each other to achieve lengthening—*Binachi's surgery.*
  - Mucosal *stem cell transplantation using enterocytes* without lymphoid tissue.
  - Seeded mucosal autografts in a prosthetic tubes.

SMALL BOWEL ENEMA (Enteroclysis)

It is the contrast study of the small bowel by infusing contrast agent either high density microbar solution with methyl cellulose or water soluble iodine dye through Nolan intestinal tube.



Fig. 21.34: Enteroclysis X-ray film showing entire small bowel. It is still commonly used investigation to assess small bowel pathology.

Indications

- Small bowel tumours.
- Stricture small bowel.
- Congenital anomalies.
- Crohn's disease, intestinal tuberculosis.

Findings to look for:

- Narrowing.
- Filling defects, irregular or regular.
- Mass lesions.

Problems

- Poor patient acceptance.
- Technically difficult.

CAPSULE ENDOSCOPY


Radiofrequency tag with polyimide coating
26 mm
×
11 mm
4 grams
Lactose body with 10% barium

Fig. 21.35: Capsule endoscopy—diagrammatic look.

- It is a type of endoscopy wherein highly sensitive miniature video-camera which after activation is swallowed by the patient. It is 26 mm × 11 mm in size. It weighs 4 grams.
- It contains single use video-camera, with 6 light emitting diodes, a lens, a colour camera chip, two batteries, radiofrequency transmitter with an antenna. Capsule takes 2 pictures per second which is transmitted to a worn recording device through radiofrequency. From the recording device data is downloaded to special computer.
- It is swallowed with 12 hours fasting.
- After activation it functions for 8 hours. It is mainly used to study small bowel diseases like vascular malformations, narrowing, tuberculoses, ulcers and tumours.
- This capsule camera sends signals and endopictures at regular intervals to the receiver (digital recorder) tied over the patient's waist.
- This receiver is later attached to specialised computer software to get different level pictures for study.
- Capsule gets deactivated in 8 hours and is passed out in the stool.
- It is available only at few centers and is costly.
- Capsule retention is the complication in 5% cases.
- It may not give proper evaluation in obstructive pathology and motility disorders of small bowel.

SMALL BOWEL ENTEROSCOPY

It is a difficult technique done to visualise the small bowel.

Indications

- Occult or obscure GI bleed. 5% of GI bleed is not diagnosed by any methods like gastroduodenoscopy, colonoscopy, contrast imaging. Angiodysplasia and ectasias are common causes for such type.
- Small bowel tumours.
- Crohn‘s disease.
- Celiac disease.
- Refractory sprue.
- HIV related small bowel diseases.
- Intraoperative enteroscopes to assess lumen on table.

Technique

Push Enteroscopy

- It is easier and faster. It reaches 60 cm beyond the ligament of Treitz.
- Flexible enteroscopes or paediatric colonoscopes are used.
- Simethicone is given prior to enteroscopy.
- BT, CT, LFT and prothrombin time should be checked. Aspirin should be stopped 5 days prior if patient is taking it.
- Oesophageal overtube is used to pass the entero-scopes through upper GI.
- Enteroscopes is passed through overtube into stomach, duodenum, and jejunum. Proper evaluation of the mucosa is done during withdrawal. If there is a bleeder point, it is fulgurated.

Sonde Enteroscopy

- It is a 5 mm diameter, 275 cm enteroscope passed through nose by a piggyback technique with a paediatric colonoscope. Its two internal channels are for air inflation and for balloon inflation. Biopsy or working channel is not there.
- Scope is passed through pylorus and further it is moved with subsequent inflation of balloon and distal progression by peristalsis. Distal position is confirmed by fluoroscopy. It takes 6 hours to pass through the entire small bowel.
- Once it is in the terminal part of the small bowel, small bowel is inflated with air and mucosa is inspected.

Intraoperative enteroscopy

- Abdomen is opened. By a small enterotomy scope is passed into the lumen. It is guided manually by compression and release to visualise entire mucosa of small bowel.

Complications and Problems

- Epistaxis due to nasal irritation.
- Perforation.
- Pancreatitis.
- Failure to pass enteroscopes as needed.
- Time consuming and not acceptable by the patient.

ENTERIC/GASTROINTESTINAL FISTULA

Enteric fistula is a challenging problem due to its high mortality of 30%, management of electrolyte imbalance, malnutrition, and sepsis.

Classifications

Anatomical

- *External:* They are **enterocutaneous fistulas** which are discussed in detail here.
  - 75% of enteocutaneous fistulas are of *postoperative* cause due to disruption of the anastomotic site.
  - 25% are *spontaneous* due to malignancy, radiotherapy, inflammatory bowel disease (most common in spontaneous cause), diverticular disease and bowel ischaemia.
  - 70% of external fistula will close spontaneously.
- *Internal*
  - Most of the internal fistula need surgical correction, if they are symptomatic or causing complications.

Aetiological

- Anastomotic disruption in postperative period.
- Trauma to normal bowel—inadvertent enterotomy/injury.
- Disease of the bowel extending into the adjacent structures.
- Disease outside the bowel extending into the normal bowel.



Figs 21.36A and B: Enterocutaneous fistula in two different patients.

Depending on the site

- *Oropharyngeal*
- *Oesopharyngeal*
- *Gastric:* Commonest cause is the site of gastrostomy tube, either with tube *in situ* or after tube removal. Other causes are—post-gastrectomy and anastomotic leak after surgery for carcinoma stomach, surgeries for benign gastric diseases, reflux diseases, and obesity.
- *Duodenal*: It occurs after surgery for pancreas, biliary system, duodenal stump leak, gastroduodenal anastomosis, renal, aortic, colonic surgeries. Spontaneous fistula occurs in Crohn's, ulcers, malignancy and trauma. It can be duodenal stump fistula which often closes spontaneously; lateral duodenal fistula which less commonly closes spontaneously.
- *Small bowel*: It is the commonest site of GI fistula. More than 75% are postoperative. Crohn's disease is the most common cause of spontaneous small bowel fistula in which 50% each are internal and external.
- *Colonic:* It can be due to postappendicectomy, postcolonic surgeries. It is common after emergency surgeries, and surgeries in unprepared bowel. Appendicectomy in acute phase of Crohn's may cause fistula due to adhesion of inflamed terminal ileum to abdominal wall wound, not from appendicular stump. Spontaneous fistula even though rare, occurs in diverticulitis, malignancy, ulcerative colitis, radiation and pancreatitis.



Fig. 21.37: Fistula at gastrostomy site. This is becoming the common cause.

Fistula may be due to:	***Physiological—based on quantity of daily output:***	***Fistula may be:***
• Complete disruption of anastomotic site • Partial disruption • Lateral fistula with distal obstruction • Fistula in stricture bowel	• *High output*—> 500 ml/day—usually small bowel; 50% mortality; less chance of spontaneous closure. • *Moderate output*—200-500 ml/day—colonic and small bowel mixed. • *Low output*—< 200 ml/day—colonic; mortality is 15%; more chance of spontaneous closure.	*Favourable:* • Site—oropharyngeal, oesophsgeal, duodenal stump, pancreaticobiliary, jejunal, colonic. • Cause—postoperative, appendicitis, diverticulitis. • Low output, absence of sepsis, transferrin level more than 200 mg/dl. • Healthy adjacent tissues with intestinal continuity, without distal obstruction. • Fistula track more than 2 cm; bowel wall defect less than 1 cm^2. *Unfavourable:* • Site—gastric, lateral duodenal, ileal. • Cause—malignancy, inflammatory bowel disease. • High output, poor nutrition, sepsis, transferrin < 200 mg/dl. • Diseased adjacent bowel, presence of distal obstruction, large abscess, complete bowel disruption, radiation. • Track < 1 cm; bowel wall defect > 1 cm^2. Track epithelialisation, presence of foreign body.
Fistula may be: • *End fistula* • *Lateral fistula* **Fistula may be:** • Single • Multiple	**Fistula stoma categories:** *Category 1*: A single orifice fistula through an intact abdominal wall or healed scar with normal skin adjacent *Category 2*: Single or multiple fistulas passing through abdominal wall close to bony part or umbilicus or surgical scar *Category 3*: Fistula through a small dehiscence through the main wound *Category 4:* Fistula through a large dehiscence through main wound or dehiscence at the bottom of wound	
Fistula may be: • *Simple* • *Complicated*—if multiple tracks, track with an abscess, communication to more sites or more than one viscus. **Note:** Fistula of duration of more than 3 months is called as *chronic fistula*		



Fig. 21.38: Complete disruption of the anastomotic site causes fistula which is unlikely to close spontaneously.



Fig. 21.39: Partial disruption also is equally problematic.



Fig. 21.40: Distal obstruction precipitates fistula formation and also prevents its closure.



Fig. 21.41: End fistula. It is seen in duodenal stump leak.



Fig. 21.42: Lateral fistula is seen in anastomotic leak from suture line.



Fig. 21.43: Epithelialisation of the fistula track prevents spontaneous closure.

To be blind does not mean to be in darkness.



Figs 21.44A to C: Multiple enterocutaneous fistulas can occur from same site or from different sites.

Factors Precipitating the Fistula Formation

- *Patient factors:* Anaemia, malnutrition, sepsis, hypotension, hypothermia, poor oxygen saturation, associated respiratory diseases/failure, emergency surgeries, specific diseases like malignancy, Crohn's, tuberculosis, adhesions.



Fig. 21.45: Fistula can have multiple tracks even though it is opening at one point in the skin.

- *Technical factors*: To reduce the chances of fistula formation technical care is essential like—proper mobilisation, meticulous dissection, tension free anastomosis, proper secure anastomosis, most important is proper blood supply at the bowel cut edges, care to avoid cautery injury as bowel is very sensitive to heat/cautery injury, proper prior preparation of patient and bowel.

Problems with enterocutaneous fistulas	***Factors which prevents spontaneous closure of fistula***
• Skin excoriation • Electrolyte imbalance • Severe malnutrition • Recurrent sepsis—locally and systemic like pneumonia, candida, varicella • Pellagra, osteomalacia, zinc deficiency	• *Distal obstruction* • Foreign body in the track • Abscess in the track, infection • Definitive disease like carcinoma, Crohn's, tuberculosis • Epithelialisation of the track • Anaemia, hypoalbuminaemia (2.5 g/dl) • Complete disruption of anastomotic site

Management of Fistula

Phase 1

- *Resuscitation and restoration* of volume with crystalloids and colloids, blood transfusion to achieve haematocrit of 30%, maintenance of albumin level at 3.0 gm/dl with albumin infusion.
- *Sepsis control* with antibiotics, percutaneous drainage of abscess under guidance or open drainage.
- *Skin care* to prevent excoriation using Karya powder, zinc oxide cream/powder, ion exchange resins, stoma adhesive and controlled fistula drainage using sump constructed suction catheter drain system or vacuum assisted closure (VAC) system or silicone barrier or created inverted cone system.

- *Reduction of output of fistula*—proton pump inhibitors, histamine antagonists, sucralfate, octreotide, infliximab (in fistula in Crohn's patients). Long term nasogastric aspiration should be avoided.
- *Nutrition*: Nutritional status should be assessed by clinical (weight, anthropometry), biochemical methods. 30 Kcalories/kg/day; 1.5 grams/kg/day of protein is the basic need. Initially TPN is used. Once patient tolerates oral, enteral feeding should be started ideally. Enteral feeding (oral/gastrostomy/jejunostomy) is contraindicated in presence of distal obstruction. Enteral feeding reduces the sepsis, improves the bowel activity, caliber, thickness and ability to hold sutures. It also avoids TPN related problems.

Phase 2

- *Investigations* are done to assess fistula and its causes. It is done in 7-10 days of fistula formation.
- *Fistulogram* using water soluble contrast, *CT fistulogram* to see the pathological anatomy of fistula—site, number, length, status of bowel, distal obstruction, presence of abscess cavity.
- *Biochemical analysis* (electrolytes, haematocrit and albumin) and renal, hepatic, respiratory, cardiac status should be assessed carefully.

Phase 3

- *Decision* by observation and assessment, whether fistula will close spontaneously or not. Favorable fistulas are likely to close spontaneously but not unfavorable.
- *Definitive procedure* is done for fistula only after 6 weeks. Mortality and recurrence is higher if operated prior to 6 weeks due to obliterative peritonitis.
  - *Definitive surgical procedure* is lengthy, complex and *team work*. Optimum nutrition, proper planning, prophylactic antibiotics are needed.
  - *Reopening* should be done through a *new distant* often transverse incision.
  - *Bowel refunctionalisation* by freeing entire bowel from ligament of Treitz to rectum should be done to clear adhesions and obstructions and all areas of sepsis and abscesses. *Sharp dissection* using scissor should be done to clear adhesions. As much as possible bowel injury should be avoided; if occurs it should be closed transversely using interrupted 3 zero silk sutures.
  - *Resection of the bowel adjacent to fistula* with track is the ideal procedure with end to end meticulous two layered closure using interrupted 3 zero silk sutures.
  - When it is not possible, fistula area bypass, Roux-en-Y drainage, serosal patch technique is used. Duodenal fistula is better managed by bypass using gastrojejunostomy and vagotomy without intervening the fistula.
  - *Proper irrigation of abdominal cavity* with saline and antibiotics during procedure, omental flap around the anastomosis, various solutions to prevent repeat adhesions are also often done. Supportive jejunostomy may be added for enteral feeding.
  - *Abdominal wall closure* is important by primary closure or by using myocutaneous flap. Mesh should not be used for closure as *recurrent fistula* may occur.

Phase 4

- Treatment during recovery and healing time also should be adequate and optimum.
- Supplementing of nutrition, protein, vitamins and essential element are important.
- Physical, psychological therapy is needed.

Happiest people are not only happy in themselves; they are the cause of happiness to others.

Chapter 22 Large Intestine

CHAPTER OUTLINE

- Anatomy
- Hirschsprung's Disease
- Diverticular Disease of the Colon
- Ulcerative Colitis
- Ischaemic Colitis
- Pseudomembranous Colitis
- Surgical Complications of Intestinal Amoebiasis
- Tumours of Colon
  - Benign Tumours/Polyp of the Colon
  - Juvenile Polyps
  - Metaplastic/Hyperplastic Polyp
  - Peutz-Jegher's polyp
  - Adenoma of Colon
  - Familial Adenomatous Polyp
  - Gardner's Syndrome
- Carcinoma Colon
- Angiodysplasia of Colon
- Ogilvie's Syndrome
- Colostomy
- Stoma Care
- Stoma Appliances
- Faecal Fistula
- Preparation of Large Bowel for Surgery
- Surgical Pouches
- Barium Enema

ANATOMY

- The colon (large intestine) is 135 cm long, and is divided into caecum, ascending colon, transverse colon, descending colon and sigmoid colon.
- The wall of the colon is composed of mucosa, submucosa, innercircular muscle layer and outer longitudinal muscle layer which, in turn, is concentrated into 3 separate longitudinal strips—*taeniae coli.*
- Small pockets of fat filled peritoneum—*appendices epiploicae* is scattered all over the colon except appendix, caecum and rectum.
- *Haustra* are sacculations between the taeniae.
- All the 3 above are important features of colon.
- *Ileocecal valve* serves as a sphincter to prevent the back reflux to terminal ileum.

Blood Supply

- Iliocolic, right colic, and middle colic arteries which are branches of superior mesenteric artery supply the colon from caecum to splenic flexure.
- Left colic, sigmoid, superior rectal arteries which are branches of inferior mesenteric artery supply the descending and sigmoid colon.
- The anastamotic arcade formed between the branches of superior and inferior mesenteric arteries is called '*arc of Riolan'*.
- Venous drainage occurs into superior mesenteric vein (which joins the splenic vein to form the portal vein) and inferior mesenteric vein (drains into the splenic vein).


Marginal artery of Drummonds (Sudeck's)
Middle colic artery
Arc of Riolan
SMA
Principal LN
Intermediate LN
Epicolic LN
Right colic artery
Paracolic LN
Sudeck's critical point
Ileocolic artery
Superior rectal artery
Inferior mesenteric artery

Fig. 22.1: Arterial supply and lymphatic drainage of colon.

Lymphatic Drainage

- Mucosa contains no lymph channels, so mucosal cancers rarely metastasize.
- Nodes are *epicolic* (located in the colonic wall), *paracolic* (located along the inner margin), *intermediate* (located near mesenteric vessels), *principal* (located near main mesenteric vessles).

Nerve Supply

- Colonic motility is under control of autonomic nervous system; parasympathetic via vagi and pelvic nerves, sympathetic via superior and inferior mesenteric ganglia.
- The effect of meal on colonic activity is termed as *gastrocolic reflex.*

HIRSCHSPRUNG'S DISEASE (CONGENITAL MEGACOLON)

> *My first specimen is a colon, but a colon of such a size that it will no doubt surprise you to learn that it comes from a child only 11 months old when it died.... Only (the) rectum was not dilated, nor indeed subject to any obstruction.*
>
> **—Harald Hirschsprung,** 1888

- It is a congenital, familial condition, occurring in newborn due to the *absence of ganglion cells—Auerbach's* and *Meissner's plexus in anorectum*, which may extend proximally either a part or full length of the colon.
- It always involves the anus, internal sphincter and rectum (partly or entirely).
- There is narrow, spasmodic, non relaxing pathological segment.
- Transitional zone proximal to it contains only few ganglion cells with formation of cone.
- Still proximal to it, colon is dilated enormously with hyperaemia, multiple ulcers and hypertrophied circular muscle fibres.
- It is one of the causes of neonatal intestinal obstruction.
- Severe enterocolitis can occur which may be fatal. Perforation, peritonitis and septicaemia can occur.
- Often there will be a chronic course of the disease with malnutrition, abdominal distension.

Types

1. *Ultrashort segment HD*—only anal canal and terminal rectum is aganglionic.
2. *Short-segment HD*—anal canal and rectum is completely involved (80%).
3. *Long-segment HD*—anal canal, rectum and part of the colon is involved (10%).
4. *Total colonic HD*—anal canal, rectum and full length of the colon is involved - 10%.



Fig. 22.2: Types of Hirschsprung's disease.



Fig. 22.3: Zones in Hirschsprung's disease.



Fig. 22.4: Congenital megacolon showing spasmodic aganglionic segment, coning (transitional zone), and proximal dilated normal ganglionic segment.



Fig. 22.5: Newborn with Hirschsprung's disease with intestinal obstruction (*Courtesy:* Dr Vivek Prabhu, MCh, Mangalore).

Once you learn to quit, it becomes a habit.



Fig. 22.6: Barium enema X-ray showing parts of congenital megacolon—spasmodic area, cone, proximal dilated segment.

It has got ***three zones***

I. *Distal immobile spastic segment,* i.e. aganglionic zone.
II. Proximal, *middle transitional zone* of about 1–5 cm length with less, sparse number of ganglions (*cone).*
III. A still more proximal, *hypertrophied dilated* segment is actually the normal ganglionic area.

Clinical Features



Fig. 22.7: Child suffering from Hirschpurung's disease undergone initial sigmoid colostomy.

Presentations: Acute, recurrent, chronic.

- It is common in males (80%).
- Its incidence is 1 in 5000 live births.
- It is common in infants and children, occasionally it occurs in adults also.
- Often it is associated with Down's syndrome (10%). (Commonest association).
- In 90% of cases, symptoms appear in early neonatal period, i.e within three days of birth. *The child fails to pass meconium.* After introducing finger into the rectum, child passes *toothpaste like stool*, with evidence of straining. Distension of the abdomen with features of intestinal obstruction is seen.
- In children, there is passage of *goat pellet* like stools, malnutrition, abdominal distention—chronic type. Constipation, with history of passing stools once in 3-4 days with straining is seen throughout the childhood and also in adolescent period. Occasionally, condition can cause intestinal obstruction.
- 10% familial.
- Gene mutation can occur in chromosome no. 10 commonly; occasionally in chromosome no. 13.
- ***Rectal examination*** shows tight sphincter with empty rectum. Child passes lot of gas and meconium.

Diagnosis

- History of failure of passing meconium.
- Plain X-ray abdomen—shows intestinal obstruction. Useful in case of perforation.
- Biopsy from all three zones to study the *ganglions and hypertrophic nerve terminals* in spasmodic segment. Starting from 2 cm above the dentate line, a full thickness rectal biopsy is ideal.
- ***Barium enema*** is done to look for the extent of disease and three zones. *Foley's catheter should not be used while doing barium enema in case of Hirschsprung's disease.*
- ***Anorectal manometry***—shows the absence of rectoanal reflex in Hirschsprung's disease, which is diagnostic.
- *Acetylcholine esterase staining shows hypertrophied nerve bundles*.



Fig. 22.8: Barium enema X-ray showing features of Hirschsprung's disease in a newborn.

Complications

- Colitis (Intramucosal gas in plain X-ray). Enterocolitis may be fulminant and fatal.
- Intestinal obstruction.
- Growth retardation.
- Constipation.
- Perforation.
- Peritonitis.
- Septicaemia.

Differential Diagnosis

- Total neuronal dysplasia
- Acquired megacolon—rectum is loaded with stool
- Anorectal malformations (ARM)
- Hypothyroidism
- Meconium plug syndrome

Treatment

- Initially, colostomy is done either transverse or transitional, so to have normal bowel function.
- Nutritional supplementation.
- Once the child attains 10 kg of weight, definitive procedure is done, i.e.
  a. Excision of aganglionic segment (spasmodic segment).
  b. Maintenance of continuity by doing coloanal anastomosis.
  c. Closure of colostomy later.

  Common procedures done are:
- *Modified Duhamel Operation*—resection of upper part of the rectum and a part of colon; anastomosis of colon to posterior part of the lower rectum and crushing the spurs to create the rectal pouch. It is *technically easier and a retro-rectal pull through*. New pouch is created by anterior part of the aganglionic rectum and by ganglionic proximal pulled down colon. Biopsy should be taken from proximal pulled down colon to look for evidence of ganglions. Pulled down proximal colon is sutured to full thickness posterior anal canal just above the dentate line. Spur between these two segments is crushed by Kocher's forceps or specialized instrument to create a single pouch.
- Soave's mucosectomy and pull through operation.
- Coloanal anastomosis after proctocolectomy.
- Total proctocolectomy with ileo-anal anastomosis in case of total colonic HD.
- *Swenson's operation*—through abdomino-anal approach, aganglionic segment is resected and colo-anal anastomosis is done.
- *Anorectal myectomy* is found to be very useful for ultrashort segment and short-segment Hirschsprung's disease. Mucosa in incised horizontally 1 cm proximal to mucocutaneous junction. A strip of muscularis with part of internal sphincter is excised with both muscle layers of the rectum for about 6-10 cm length. Mucosa is sutured back. Complications are abscess formation and failure.



Fig. 22.9: Modified Duhamel operation. Normal colon is brought behind the aganglionic rectum and anastomosed just above the dentate line.

Complications of surgery

- Severe colitis
- Faecal fistula
- Stenosis
- Stunted growth

Acquired megacolon

- No contracted segment in rectum
- Seen in children with faulty toilet training
- Rectum and sigmoid colon are dilated
- Normal ganglions in all levels
- Improper bowel habit causing chronic bowel dilatation
- Repeated enemas, manual evacuation, toilet training, educating the parents are required
- Should be differentiated from Hirschsprung's disease

DIVERTICULAR DISEASE OF THE COLON

- They are acquired herniations of colonic mucosa through circular muscles at the points where blood vessels penetrate (points of least resistance).
- It is more commonly localised to *sigmoid colon (90%)* but occasionally seen in full length of the colon.
  Rectum is not affected.

Saint's triad (5%)

- Diverticulitis
- Hiatus hernia
- Gallstones

- It is rare in Asian and African countries because of the high fibre diet. It is common in western countries.
- Colonic diverticulosis is usually of false type with only mucosal herniation.



Fig. 22.10: Diverticular disease of colon.

Much wisdom often goes with fewer words.

Aetiology

- *Diet*—it is the main factor. Low fibre diet increases the stool transit time, reduces the stool weight, reduces the bulkiness of stool which increases the intraluminal pressure and muscle hypertrophy. High fibre diet prevents this.
- Disease is more common in females. It is more common in aged.
- It is more common in nonvegetarian than in vegetarian.
- NSAID intake by inhibiting prostaglandin synthesis may cause diverticular disease. It is more common in individuals with steroid therapy or immunocompromised people.
- Smoking and alcohol.
- Long standing constipation increases the stool transit time and causes diverticulosis.



Fig. 22.11: Diagram showing the formation of diverticula. Note the difference between congenital and acquired diverticula.

Types

- ***Diverticulosis*** is the initial primary stage of the disease, wherein there is hypertrophy, muscular incoordination leading to increased segmentation and increased intraluminal pressure. At this stage they are asymptomatic, but often get severe spasmodic pain due to colonic segmentation called as *painful diverticular disease*.
- ***Diverticulitis*** is the second stage due to inflammation of one or more diverticula with pericolitis.It presents with persistent pain in left iliac fossa, fever, loose stool, recurrent constipation, tenderness in left iliac fossa, palpable and thickened sigmoid colon. P/R may reveal a tender mass.

Diverticulitis can be:

- *Uncomplicated diverticulitis* presenting with pain and spasm over left iliac fossa, fever. Recurrent attacks need sigmoid colectomy. It can be done electively through laparoscopy.
- *Complicated diverticulitis* presents with *haemorrhage, abscess, fistula* formation, perforation, peritonitis and obstruction due to stenosis. Vesicocolic fistula presents with *pneumaturia*.
- *Diverticula associated colitis* (DAC) presents with tenesmus, diarrhoea, haematochezia. DAC is a distinct clinical entity with segmental colitis.

Pathology

There is hypertrophy and thickening of the muscle layer with progressive colonic narrowing and segmentation with raised intraluminal pressure causing pulsion diverticula of only mucosa adjacent to taenia in antimesentric region. Pathology is common in sigmoid colon.

Features of Diverticular Disease

- In western countries, 50% risk to develop diverticular disease for an individual is at the age of 60 years. Only 15% of patients with diverticulosis develop diverticulitis. 75% of patients with diverticulitis have uncomplicated course with features of only diverticulitis. 25% of patients with diverticulitis develop complications like abscess, perforation, stenosis and fistula. Abscess can be commonly pericolic and pelvic, rarely in buttock and ischiorectal fossa.
- Features of diverticulosis—fullness of abdomen, bloating, flatulence, vague discomfort.
- Features of diverticulitis—pain in left iliac fossa which is constant radiates to back and groin, tenderness, bloody stool, often massive haemorrhage, fever, rigidity and mass in left iliac fossa. Mass is usually tender, firm, resonant, nonmobile.
- Features of fistula—colovesical is the commonest type of fistula. It causes passage of gas in the urine (*pneumaturia*) commonly and occasionally feces.

Complications of diverticulitis

- Perforation and pericolic abscess or peritonitis
- Progressive stenosis and intestinal obstruction
- Profuse colonic haemorrhage (17-20%)
- Fistula formation (5%)—vesicocolic, vaginocolic, enterocolic, colocutaneous



Fig. 22.12: Sigmoid diverticula causing pericolic abscess as a known complication.



Fig. 22.13: Diverticular disease causing colovesical fistula. Patient will have urine stained with faecal matter and severe urinary infection. Contrast dye study, CT scan is required. Initial colostomy and ureterostomy as diversion is required before definitive procedure.

Note:
Diverticulitis is not a precancerous condition.

It may coexist with malignancy, irritable bowel syndrome, Crohn's disease.

Hinchey's classification of diverticulitis

- Stage I: Pericolic or mesenteric abscess
- Stage II: Walled off pelvic abscess
- Stage III: Generalised purulent peritonitis
- Stage IV: Generalised faecal peritonitis

Investigations

- *Barium enema (best method to diagnose)* shows '*saw-teeth'* appearance. *Champagne glass sign*—partial filling of diverticula by barium with stercolith inside—seen in sigmoid diverticula.
- *Sigmoidoscopy* is useful but should not be done in acute stage. Once acute stage subsides, barium enema, sigmoidoscopy, colonoscopy can be done (To rule out associated malignancy).
- CT scan in acute phase to see pericolic abscess.
  - CT scan shows thickening of muscle layer, abscess, perforation, fistula, involvement of organs like urinary bladder and associated pathology. CT scan is the ideal investigation.
- Cystoscopy and colonoscopy in case of fistula. Ureteric stenting is needed to make eventual surgery easier.



Fig. 22.14: Colonoscopic view of sigmoid diverticula.

Differential Diagnosis

- Carcinoma sigmoid colon.
- Amoebic colitis, ulcerative colitis, ischaemic colitis and Crohn's disease.
- Tuberculosis.

Coexistence of carcinoma and diverticulitis can occur in 12% of cases.

Treatment

Medical treatment

- High fibre diet
- Antibiotics
- Bulk purgatives
- Avoid constipation
- Regular follow-up of the progress of disease and onset of complications
- Abscess can be drained by CT guided aspiration or percutaneous drainage tube

- In acute stages, conservative treatment like bowel rest, antispasmodics, antibiotics are advised.
- *Guided aspiration* of the abscess is sufficient if abscess is small. Proper antibiotics are needed.
- Later, surgery is required**.** *Resection of sigmoid colon and anastomosis (colorectal) is done.*

Indications for surgery

- Recurrent diverticulitis
- Diverticulitis with complications



Fig. 22.15: Resection and primary anastomosis can be done in sigmoid diverticula after proper bowel preparation electively.

The eyes see only what the mind is prepared to comprehend.

- If colon is loaded wth faecal matter, initially a transverse colostomy is done. Then resection and anastomosis; later colostomy closure is done as a staged procedure.



Fig. 22.16: Resection of sigmoid colon for sigmoid diverticula with primary anastomosis and defunctioning diversion colostomy.

- In case of perforation, proximal colostomy and exteriorisation of the affected bowel with later resection and anastomosis is done as it has high mortality.



Fig. 22.17: Resection and formation of end colostomy and mucus fistula for acute sigmoid diverticulitis.



Fig. 22.18: Hartmanns operation for acute diverticulitis with sepsis/perforation/peritonitis. Hereafter resection proximal colon is exteriorised as end colostomy. Distal rectal stump is closed.

- Occasionally, Hartmann's procedure (combination of sigmoidectomy, end colostomy and closure of rectal stump) is better and life saving.
- Fistulas are treated by resection of the diseased bowel and closure of the fistula along with diversion procedures like colostomy, cystostomy, ureterostomy.
- In certain cases of diverticulosis, a longitudinal incision through the taenia and muscular layer without opening the mucosa is sufficient (like Heller's/Ramstedt's myotomy)—*Reilly's sigmoid myotomy*.

Note:

- It is basically **a benign condition**, therefore the prognosis is good. High fibre diet is advised.
- Complications like *perforations, fistulas are dangerous and life threatening*.
- Right sided diverticulum in the caecum and ascending colon is usually solitary and congenital.

Myotomy

- Heller's myotomy—achalasia cardia
- Ramstedt's myotomy—congenital pyloric stenosis
- Reilly's myotomy—diverticulosis

ULCERATIVE COLITIS

- It is an inflammatory condition of rectum and colon of unknown aetiology perhaps related to stress, westernized diet, autoimmune factor, familial tendency, allergic factor.
- Disease commonly starts in the *rectum,* spreads proximally to the colon and often into the ileum as ***back wash ileitis*** (5%).

Aetiological Factors

- Westernized diet, red meat; less common in vegetarians.
- Defective mucin production in the colonic mucosa and mucosal immunological reaction.
- Autoimmune factors—cytotoxic T lymphocytes against colonic epithelial cells and presence of anticolon antibodies. Association with HLA DR2 is observed in ulcerative colitis. DR 1501 is associated with less severe type' DR 1502 is associated with more severe form.
- Appendicectomy and smoking protects ulcerative colitis especially from extraintestinal features and from postoperative complications.
- Familial in nature.
- Allergy to milk (cow milk) and other dietary factors.
- Excess reactive oxidative metabolism in ulcerative colitis.
- Psychological aspects, stress, life style, personality disorders.

Pathology

To begin with, multiple minute ulcers
(*pin point ulcers*) occur with proctitis and colitis
↓
These ulcers extend into the deeper layer
↓
Spasm of the bowel

↓

Stricture of the colon

↓

Permanently contracted colon (*pipe stem colon*)

↓

In between ulcers, epithelial thickening occurs which appears like polyps

↓

Pseudopolyposis.



Fig. 22.19: Operated specimen showing colon with features of ulcerative colitis.

- It is a disease confined to mucosa and submucosa.
- There is no bowel wall thickening and no granuloma formation.
- There are no skip lesions. Rectum is always involved. Distal bowel is involved to begin with, then spreads proximally. Distal involvement is more severe. Entire colon including caecum and appendix may be involved.
- Only rectum involvement, as proctitis occurs in 25% cases. Such patients will have 5% risk of developing rectal cancer. In 15% cases, it is left sided ulcerative colitis presenting with severe recurrent diarrhoea. In 25% patients, total proctocolitis is the presentation. Bloody diarrhoea, malnutrition, complications like *toxic megacolon*, perforation (steroid may mask the features) and carcinoma are common here.
- Pseudopolyps are of inflammatory in nature. Absence of normal mucosa between these pseudopolyps is important to differentiate it from neoplastic polyps.
- Intense inflammation in the ***mucosa and submucosa*** with typical feature like:
  - *Multiple crypt abscesses*
  - *Sparing of the deeper layers* of the colonic wall
  - Inflammatory *pseudopolyps*
  - Multiple *pin point ulcers*
  - Increase in *substance p containing nerve fibres*
  - *Lymphoid hyperplasia* in mucosa and submucosa (25%)
  - Presence of *anti neutrophil cytoplasmic antibodies* with a perinuclear staining pattern (86%)
  - Decreased goblet cell mucin
- Only in **toxic megacolon** (1.5-2.5%) there is acute inflammation extending to entire thickness of the colonic wall including the serosa. It is not the colon that is toxic but it is the patient who is toxic, hence the name. It is precipitated by non specific causes, during barium enema study, due to drugs like opiates, antidiarrhoeal drugs and anticholinergics. Toxic megacolon commonly affects the *transverse colon* which will be more than 6 cm in diameter. Left colon or entire colon also may be involved. Caecum when rarely involved; becomes more than 10 cm in diameter. Colon will be like *wet blotting paper*. It is prone for perforation, peritonitis which carries high mortality (25-50%). C-reactive protein will be increased. It needs emergency laparotomy with total colectomy/proctocolectomy with ileostomy. Occasionally toxic megacolon can occur in pseudomembranous colitis, amoebic colitis or typhoid colitis.
- **Carcinoma in ulcerative colitis** is more prevalent than in Crohn‘s disease.

Factors involved are:

- *Extent* of involvement (more in total colonic).
- *Duration* of the disease; *continuous active disease* than intermittent disease.
- Incidence is 5% when duration is 15 years; 25% in 25 years; 35% in 30 years; 45% in 35 years; 65% in 40 years.
- Incidence of developing cancer in left sided colitis is 10 years later than universal ulcerative colitis.
- Incidence of carcinoma developing in ulcerative colitis is *equal* in both sexes.
- Carcinoma in ulcerative colitis is commonly *aggressive and poorly differentiated, multicentric, synchronous, infiltrative and scirrhous;* half the patients will have colloid carcinoma (signet ring), more advanced at the time of presentation, *dysplasia* developing into cancer is common.
- Ulcerative colitis with primary sclerosing cholangitis has still increased risk of developing cancer.
- In ulcerative colitis, dysplasia is very important factor to transform into carcinoma. It may be mild, moderate or marked. It is often called as *dysplasia associated lesion or mass* (DALM).



Fig. 22.20: *Multiple pseudopolyposis* involving entire colon in ulcerative colitis. Disease involves only mucosa and submucosa.

Clinical Features

Disease usually begins in rectum as **proctitis** later becomes **left sided colitis** and eventually causes severe **total proctocolitis.**

- More common in females (2:1), begins in 3rd decade.
- Watery diarrhoea, mucus or blood stained discharge per rectum.
- Colicky pain, spasms.
- Decreased appetite and loss of weight.
- Relapses and remissions at regular intervals.

Clinical grading of ulcerative colitis

	Mild	Moderate	Severe
Stool frequency	< 4	4-6	> 6
Pulse	< 90	90-100	>100
Haematocrit	Normal	30-40	< 30
Weight loss in %	None	1-10%	> 10%
Temperature	Normal	99-100	> 100
ESR	< 20	20-30	> 30
Albumin	Normal	3-3.5	< 3.5

Two types of *presentations:*

a. ***Fulminant type,*** 5% common:
   - It is a severe form, with continuous diarrhoea with passage of blood, mucus and pus.
   - Patient is ill and dehydrated.
   - Mimics fulminant amoebic colitis; severe typhoid and dysentery.
   - Fever, hypokalaemia, acidosis, dehydration and shock.
   - Abdominal distension occurs.
   - A*cute toxic dilatation* (1.5%) of *transverse colon* may occur where the diameter of transverse colon > 6 cm. It has high mortality and requires *emergency surgery,* i.e. either colostomy or resection with ileostomy and later ileo-anal anastomosis. Here colon is like *wet blotting paper*.

b. ***Chronic type*** (95%):
   - Lasts for months to years with diarrhoea, blood loss, anaemia, invalidism, abdominal discomfort and pain.
   - Severe malnutrition and hypoproteinaemia.

Note:

- Prevalence is 40-100/1,00,000.
- It is common before 30 years.
- Smoking increases Crohn's but protects ulcerative colitis.
- Incidence of colonic stricture is 10% in ulcerative colitis and is due to muscular hypertrophy. Strictures are usually benign. But 60% stricture appear after 20 years; 80% of stricture occur proximal to splenic flexure; stricture causing obstruction are likely to be malignant.
- *Perinuclear staining antinuclear cytoplasmic antibodies (pANCA)* are seen in 85% of patients with ulcerative colitis and is diagnostic test to differentiate from Crohn's.
- Arthritis (20%), ankylosing spondylitis (5%), erythema nodosum (15%), pyoderma gangrenosum are extraintestinal features *which resolve after total colectomy.*
- Primary sclerosing cholangitis (PSC, 5%) is common in ulcerative colitis before 40 years of age; common in males; related to HLA B_8 and HLA DR_3 (10 times). Malignant transformation in colon is 5 times more in these patients compared with ulcerative colitis without PSC. It causes pain abdomen, obstructive jaundice, later liver cirrhosis and failure. Total colectomy *will not resolve* PSC.
- *Surveillance colonoscopy* to identify transformation to carcinoma in ulcerative colitis is done as follows – Every year from 8 years after the onset of pancolitis and 15 years after the onset of left sided colitis. 10-30 random biopsies should be done. No dysplasia (less chance of carcinoma)/low grade dysplasia (10% chance)/high grade dysplasia (40% chance)/DALM (50% chance). All dysplasia types need proctocolectomy. Flow cytometry of biopsy specimens to study DNA aneuploidy or polyploidy is needed for further confirmation. 30% of high grade dysplasias show invasive carcinomas.

Investigations

- *Barium enema*—shows loss of haustrations, narrow contracted colon *(hose pipe colon)*, mucosal changes, pseudo-polyps. *It is avoided in fulminant cases.*
- *Sigmoidoscopy and biopsy.*
- *Colonoscopy* is also required.



Figs 22.21A and B: Colonoscopic view of ulcerative colitis and multiple ulcers.

Due to very high incidence of malignant transformation in ulcerative colitis (10-20%), multiple biopsies should be taken from suspected areas of the colon. Risk increases with age of the patient and duration of the disease (20%).

Sigmoidoscopic grading of ulcerative colitis

0—Normal mucosa
1—Loss of vascular pattern
2—Granular, non-friable mucosa
3—Friability on rubbing
4—Spontaneous bleeding, ulcerations

- Plain X-ray abdomen is useful in obstruction, toxic megacolon, perforation.
- C reactive protein will be very high in acute phase.

Differential diagnosis

- Crohn's disease
- Ischaemic colitis
- Irritable bowel syndrome
- Amoebic colitis
- Bacillary dysentery
- Carcinoma colon
- Collageous colitis in females
- Infectious colitis by *Clostridium difficile, Campylobacter jejuni*

Differences between Crohn‘s disease and ulcerative colitis

Crohn‘s disease	Ulcerative colitis
• It affects ileum and often colon but can involve any part of GIT—rectal sparing is common	• It affects rectum and colon from distal to proximal
• Full thickness—transmural disease	• It affects mucosa and submucosa—not deeper
• Skip lesions are typical	• Skip lesions are not observed
• Granulomatous lesion on histology—deep ulcers; pseudopolyps are not found	• Not a granulomatous lesion—superficial ulcers, pseudopolyps are present
• Stricture and fistula are common	• Narrowing can occur but not very common
• Anal fissure and perianal abscess are more common	• Fissure and perianal disease can occur but not as common as in Crohn's disease
• May mimic appendicitis	• Will not mimic appendicitis
• Bleeding is not common	• Bleeding is common
• Fever is common	• Fever is uncommon
• Mass in RIF is common	• Mass is not a common feature
• Anal pathology very common	• Anal pathology is rare
• Discontinuous segmental asymmetrical colitis	• Continuous mucosal disease—colitis
• Toxic megacolon is rare	• Toxic megacolon is common
• Normal vascular pattern	• Distorted vascular pattern
• Fistula is very common	• Fistula is uncommon
• Recurrence is common after resection	• Total proctocolectomy cures the disease

Complications

GIT

- Pseudopolyposis
- Turning into malignancy
- Stricture formation, commonly in recto sigmoid and anal canal—10%
- Toxic megacolon in transverse colon
- Massive haemorrhage—1%
- Fistula in ano—20%
- Perforation—10-20%

Extraintestinal

- Severe malnutrition
- Liver cirrhosis (50%)
- Skin lesions—pyoderma, erythema nodosum
- Arthritis, iritis, ankylosing spondylitis—common
- Sclerosing cholangitis, carcinoma of bile duct

Treatment

General

- Correction of anaemia.
- Fluid and electrolyte supplimentation.
- Nutrition (high protein, carbohydrate, vitamin, but low fat diet), TPN.
- Sedatives and tranquillisers.
- Psychological counselling.

Drugs

In active disease, drugs are used to *induce remission*. Later drugs also should be given for *maintenance* of remission and to prevent relapses.

- *Salazopyrine/sulfasalazine* splits into 5 amino-salicylic acid and sulphapyridine in colon. It is used as *first line therapy*. Its dose is 2-4 gm/day. It is mainly used to induce remission. It suppresses PG E1 and PG E2 to reduce the inflammation, inhibits proteolytic enzymes and also causes immunosuppression. 5 ASA is the most active ingredient. Side effects are skin rashes, bone marrow suppression, folic acid deficiency, haemolysis in glucose 6 phosphate dehydrogenase deficiency patients, temporary fertility problems in men.
- *5 ASA (Mesalamine)* is also used in active disease as *first line therapy*. It is used with an azo bond to prevent its absorption in small bowel. Its induction of remission is same as sulfasalazine. Idiosyncrasy and temporary infertility is not present in mesalamine. Its *oral* dose is 2-4 gm/day. It is also used as *retention enema* which is better than steroid enema in left sided ulcerative colitis/proctitis. But mesalamine enema (4 gm in 100 ml saline) is costly. Enema is combined with oral mesalamine or oral steroid in acute cases. Mesalamine 500 mg *suppository* is also used in BID doses. Daily oral (1.6

gm) and topical 4 gm enema, twice weekly is often used for maintenance therapy. Headache, dyspepsia and myocarditis are the complications.

- *Steroids* are used in cases where salazopyrine fail to induce remission. It is a drug for *refractory cases*. Oral prednisolone 60 mg/day tapering in 4 weeks is the dose. Intravenous hydrocortisone 100 mg 8th hourly is used in acute cases. 100 mg hydrocortisone enema/40 mg methylprednisolone enema (steroid retention enema) are used for 2 weeks in acute active diseases. Most patients with moderate to severe disease need steroid therapy. *Budesonide* is a newer steroid hydrocortisone analogue is also equally effective with lesser side effects and less adrenal suppression.
- *Immunomodulators* are used often to induce remission and for maintenance. *Azathioprine and 6-mercaptopurine* are used. They act at DNA level (purine ribonucleotide) and inhibit lymphocyte function (of T cells). But this action is slow.
- *Cyclosporin* is used in refractory, fulminant severe ulcerative colitis as a reserve drug. Dose is 4 mg/kg/day IV.
- *Mebeverine HCl* and *Tegaserod* (6 mg) are the other drugs used in ulcerative colitis. Other measures are using sucralfate, short chain fatty acids, probiotics, antidiarrhoeal drugs (diphenoxylate, loperamide, codeine), avoiding milk products, fibre, fruits.
- Antitumour necrosis factor alpha—*Infliximab* is also used selectively (in some studies). It is given intravenously at interval of 6 weeks. It shows 70% remission in ulcerative colitis.
- Newer drugs with a targeted delivery into the colon is used nowadays, e.g. Olsalazine (azobond); Balsalazine (4 aminobenzoyl carrier).

Management of severe ulcerative colitis

- It is more than 6 stools per day, with cramping pain, toxicity, fever, raised ESR, anaemia, tachycardia, more than 10% weight loss, hypoalbuminaemia less than 3.5 gm%
- It always needs hospitalisation
- IV corticosteroids [hydrocortisone] 300 mg/day/oral prednisolone/5 ASA orally or as enema
- IV cyclosporine with azathioprine or 6 mercaptopurine
- Fluid and electrolyte management
- TPN/enteral nutrition
- Proper monitoring of the patient for complications
- Surgery

Indications for Surgery—30% Cases

- Intractability—commonest indication
- Toxic dilatation
- Perforation
- Haemorrhage
- Risk of malignant transformation, dysplasia (DALM)
- Onset at early age
- Chronic invalidism
- Progressive disease with stricture, abscess, fistulae
- Steroid dependency, persistent active disease
- Malignancy
- Severe extraintestinal manifestations
- Growth retardation in children

Toxic megacolon

- 1.5% incidence
- Common in transverse colon
- Colon is more than 6 cm in diameter
- Colon is like wet blotting paper
- Commonly seen in ulcerative colitis
- Can occur in bacterial colitis, pseudomembranous colitis, fulminant amoebic colitis
- May be precipitated by antidiarrhoeal drugs
- IV fluids, blood transfusion, antibiotics, steroids are also needed
- Can be life threatening
- Plain X-ray is very useful
- Emergency surgery, colectomy, colostomy/ileostomy may be required
- In olden days *blow hole procedure* was advocated for toxic megacolon, may be still useful in severe cases. Skin level transverse colostomy, sigmoid colostomy and a loop ileostomy is done to decompress entire small and large bowel. After many months (6-8 months) once patient recovers from acute illness, total proctocolectomy with ileal pouch anal anastomosis is done

Surgeries

- *Total proctocolectomy with ileo-anal anastomosis with pouches as reservoir* ("J', 'S', or "W' pouches). It is called as *restorative proctocolectomy with ileal pouch anal anastomosis (IPAA)*. It is *ideal curative procedure* for ulcerative colitis. Anal sphincter complex is preserved. 30 cm ileal pouch is created either hand sewn or with stapler. Created ileal pouch reservoir is anastomosed just above the anal canal using end to end stapler. Diameter of the pouch should be twice the diameter of the ileum. Obstruction (25%), diarrhoea, *pouchitis (25%)*, leak, sepsis, incontinence are the complications.



Fig. 22.22: Different pouches are used after restorative proctocolectomy and during ileoanal anastomosis. Pouch acts as reservoir and reduces the frequency of stool. It avoids ileostomy with natural stool passage with continence. Pouchitis can occur with diarrhoea, blood in stool, perianal pain. Occasionally, redoing or conversion may be required. J type is commonly used.

- Total proctocolectomy with ileostomy (permanent, continent Kock's ileostomy, with one way valve is done). It is used at present only *in revision surgery* when needed after restorative proctocolectomy.
- *Total proctocolectomy with end non continent ileostomy* was the earliest operation done for ulcerative colitis. It is now *reserved only* for ulcerative colitis complicated with

carcinoma of rectum. *Ileostomy site* should be marked in standing and sitting position. Stoma should be within the right rectus abdominis muscle at the summit of infraumbilical fat, away from midline incision, bony prominences and umbilicus.

- *Total colectomy* with ileorectal anastomosis. Proper follow-up at regular intervals by regular sigmoidoscopy evaluation should be done as rectum is also diseased and vulnerable for complications. It is *not commonly* practiced now.
- Total colectomy with rectal mucosectomy and anastomosis above the dentate line on posterior aspect is also occasionally used.

Ileostomy

It is usually end ileostomy. But often loop ileostomy is also done

Indications:

- After total proctocolectomy for ulcerative colitis, total colonic Hirschsprung's diseases, Crohn's disease (occasionally), and total colectomy for carcinomas
- Loop ileostomy is done in critically ill patient with acute ileal conditions like multiple ileal perforations, ileal gangrene or distal fistulas or sepsis. It is temporary ileostomy
- Ileostomy is *placed in right iliac fossa* through the right rectus muscle.
- Ileostomy may be temporary (loop) or permanent (end)
- Brooke's classic end non continent ileostomy or Koch's continent ileostomy (with continent intra-abdominal pouch) are used
- Ileum should project as a spout at least 4 cm above the skin surface, which facilitates the effluent to pass directly into the bag
- Ileostomy usually acts in 48 hours
- Ileostomy bag, ileostomy care, nutrition and electrolyte management are important
- **Complications** like prolapse, stenosis, haemorrhage, retraction can occur

Complications of Surgery for Ulcerative Colitis

- Pouchitis (20%) with pain, diarrhoea, fever, bleeding, toxicity, pouch—vaginal fistula, foecal incontinence (5%). Pouchitis disease activity scoring index is at present used which is based on clinical, endoscopic and histological inflammatory features.
- Stenosis, pelvic abscess formation.
- Leak, fistula formation.
- Problems with ileostomy—psychological trauma, skin excoriation, retraction, stenosis (25%), prolapse, bleeding, enteritis, ileal necrosis, ileal volvulus, paraileostomy hernia, paraileostomy abscess.
- Sexual dysfunction following proctocolectomy by nerve injury.
- Persistent perineal sinus after total proctocolectomy.
- Risk of cancer persists if only total colectomy is done.

ISCHAEMIC COLITIS

It occurs in **splenic flexure** where blood supply is precarious. Splenic flexure is the *water shed* area of colon, receiving blood supply from terminal branches of superior and inferior mesenteric arteries.

- Ischaemic colitis is common in females; common in aged.
- It is related to atherosclerosis, emboli, vasculitis, diabetes, chronic renal failure, autoimmune diseases, polycythaemia, haemodialysis, etc.
- *Water shed point*—Griffith's point in artery of Riolan gets poor perfusion by arterial disease/low perfusion pressure/altered viscosity causing ischaemic colitis.

Types (Marston's Classification)

1. Gangrenous type—*ischaemia of full thickness* colon causing peritonitis.
2. Stricture type— *ischaemia of muscularis* layer causing scarring.
3. Transient type—most vulnerable layer, *mucosal* involvement usually recovers completely.

Clinical Features

- Pain in left iliac fossa and left hypochondrium.
- Vomiting, diarrhoea.
- Passing blood in the stool**.**

Differential Diagnosis

- Carcinoma colon.
- Ulcerative colitis.
- Crohn's disease.
- Tuberculosis.



Fig. 22.23: Ischaemic colitis in splenic flexure.

Investigation

- *Plain X-ray* reveals '*thumb printing sign*' due to mucosal oedema and submucosal haemorrhage. Perforation is also diagnosed.
- *CT scan shows* colonic wall thickening with posterior fat shadowing. Angiography is not helpful.
- *In acute stage,* barium enema or contrast study or sigmoidoscopy or colonoscopy is avoided due to risk of perforation.
- *In chronic stage*, colonoscopy and contrast study is a must.

God gives every bird its food, but he does not throw it into the nest.

Treatment

- 80% of patients will recover from conservative treatment—bowel rest, fluids, antibiotics, adequate perfusion.
- Surgery is indicated in gangrene and peritonitis, stricture (15%), segmental ischaemia (20%).
- Laparotomy, resection and anastomosis (splenic flexure) is done.
- In acute phase with peritonitis (covering), diversion colostomy is needed.

Colonic ischaemia

- Colon is the *commonest* site of intestinal ischaemia
- Most of colonic ischaemia results from *small vessel occlusion* or low flow ischaemia.
- Vascular diseases, vasculitis, diabetes, hypotension, aortic surgery with ligation of inferior mesenteric artery, aortic atherosclerosis blocking opening of IMA, OCP intake, cocaine abuse, coagulopathies, CMV, *E. coli* infections, long distance running—are the causes
- *Splenic flexure* is the most common site; but any segment like sigmoid colon can be involved
- Rectum is *spared* due to rich collaterals

PSEUDOMEMBRANOUS COLITIS

- It is an acute diarrhoea due to toxins produced by the overgrowth of *Clostridium difficile* after antibiotic therapy (usually after clindamycin).
- *Clostridium difficile* is a Gram positive, anaerobic, spore forming bacillus. It produces toxin A (enterotoxin) and toxin B (cytotoxin, more potent).
- It is also often seen in immunocompromised patients and patients who are on cancer chemotherapy.
- Incidence is 2%. Mortality is 30%.
- Stool cytotoxin assay is highly sensitive and specific. ELISA test for toxins is also useful.
- Colonoscopy is ideal as right side involvement is more common.
- It can occur up to 6 weeks after stopping the drug.
- Diarrhoea, toxaemia, perforation, haemorrhage also can occur.

Treatment

- IV vancomycin 500 mg 8th hourly.
- IV metronidazole 8th hourly.

SURGICAL COMPLICATIONS OF INTESTINAL AMOEBIASIS

Trophozoites of *Entamoeba histolytica* by digesting mucosa, submucosa of *rectosigmoid* (75%) region commonly or *ileocaecal* region of the colon, causes *retort shaped amoebic ulcers* which exudes blood, pus and necrotic material.

- Cyst is the infective agent. It enters through faeco oral route. It forms trophozoite which multiplies and causes inflammation and *flask shaped ulcers* in the rectosigmoid, caecal and often in the terminal ileal region.
- It causes blood with mucus diarrhoea, toxaemia, secondary bacterial infection, fulminant colitis, perforation and peritonitis, rarely toxic megacolon, extraintestinal amoebiasis.
- Amoebic liver abscess is the *commonest form* of extraintestinal amoebiasis. Others are cutaneous amoebiasis, amoebic empyema, and very rarely amoebic brain abscess, amoebic pericarditis.
- *Chronic amoebiasis* causes vague abdominal pain, decreased appetite, intestinal colic and psychological trauma to the patient.



Fig. 22.24: Amoebic ulcer is common in left side (sigmoid colon). Amoeboma can occur in caecal region where it forms granuloma in pericolic area presenting as mass abdomen. Amoebic ulcers are classically flask/retort shaped.

Presentations

1. *Amoebic dysentery* with diarrhoea, colicky pain, tenderness in left iliac fossa (in“ *Sir Philip Manson-Bahr amoebic point’*).
2. *Amoebic typhlitis* (inflammation of caecum) presentation with pain and tenderness in right iliac fossa and often also as a *mass in the right iliac fossa mimicking carcinoma caecum* called as ***amoeboma*** (amoebic granuloma) (1.5%).

Differential diagnosis for amoeboma

- Appendicular mass
- Ileocaecal tuberculosis
- Carcinoma colon
- Retroperitoneal tumour
- Lymph node mass

3. *Acute fulminant amoebic colitis* is a severe type with sloughing of colonic and rectal mucosa causing torrential bleeding, toxicity which can be life-threatening.

Investigations for intestinal amoebiasis

- Saline wet mount of fresh stool—trophozoites in 90% cases
- Serology—indirect haemagglutination test
- PCR
- P/R and proctoscopy

Complications of amoebic colitis

- *Amoeboma*—right side common
- Perforation in rectosigmoid/caecal region bleeding, peritonitis
- Stricture rectum and colon
- Intestinal obstruction
- Pericolic, paracolic, ischiorectal abscess and fistula formation
- Amoebic typhlitis, amoebic liver abscess

Treatment

- In acute cases, hospitalization and proper rehydration is done.
- Antispasmodics to alleviate pain is given.
- Metronidazole IV or metronidazole retention enema is given. It is very effective in both intestinal and extraintestinal amoebiasis.
- In less severe disease, tab metronidazole (400-800 mg) 3 times daily is given for 10 days or tab tinidazole 2 gm daily for 3 days.
- Diloxanide furoate is very effective in chronic amoebiasis and cyst passers. Dose is 500 mg, 3 times daily for 10 days.
- Other drugs used are—paromomycin, iodoquinol.

TUMOURS OF COLON

BENIGN TUMOURS/POLYP OF THE COLON

- *Polyp* is a tumour/swelling arising from mucosal surface with a pedicle/stalk. ‘*Poly*’ means many; ‘*pous*’ means foot in Greek.
- *Polyp* is a mass projecting into the bowel lumen beyond the surface epithelium.

Classification

Inflammatory

- Ulcerative colitis.
- Segmental colitis.
- Crohn’s disease.
- Diverticulitis.
- Dysenteric colitis.

Hyperplastic (Metaplastic)

- Also called as metaplastic mucosal polyps.

Hamartomatous

- Peutz-Jegher’s syndrome.
- Juvenile polyp.
- Cronkhite—Canada syndrome.

Neoplastic

- Tubular—pedunculated.
- Villous—sessile.
- Tubulo—villous.
- FAP—familial adenomatous polyposis.

Others

- Lipoma, haemangioma, leiomyoma.

JUVENILE POLYPS

- *Commonest* polyp of colorectum in *infants and children.*
- Can cause intussusception, prolapse through rectum, bleeding.
- Colonoscopic polypectomy is done.
- Not a premalignant condition.

METAPLASTIC/HYPERPLASTIC POLYP

- Metaplastic—indicates a difference in appearance from normal mucosa.
- Very minute in size—1-2 mm. Multiple.

Polyps

Inflammatory	Hyperplastic	Hamartomatous	Neoplastic
Ulcerative colitis	(Metaplastic)	Peutz-Jegher syndrome	Adenomatous
Segmental colitis		Juvenile polyp	– Tubular
Dysenteric colitis		Cronkhite-Canada syndrome	– Tubulovillous
Crohn’s disease			– Villous
Diverticulitis			Malignant (Carcinomatous)

Children, like animals use all their senses to discover the world.

- Common in rectum. Also occurs in other parts of colon. It is most common colonic polyp.
- Contains columnar epithelium, cystic dilatation, goblet cells, and lymphocytes.
- Not a pre-malignant entity.

PEUTZ-JEGHER'S POLYP

- It is common in *small intestine* (jejunum) but can also occur in large intestine.
- ***Features*** are multiple, familial, hamartomatous intestinal polyps.
- Asssociated with *melanosis* of the oral mucosa, lips (lower lip) and occasionally digits (*not in tongue*).
- Microscopically it contains tree like branching filaments of mucosa with smooth muscle wall.
- It can occasionally turn into malignancy.
- It is autosomal dominant disease with germline defect in suppressor serine threonine kinase 11 (STK11).

Complications

Bleeding or intussusception, when occurs requires surgery either resection—anastomosis or colonoscopic removal.

ADENOMA OF COLON

- It can be *tubular, villous, tubulovillous (*Histologically). Tubular is the commonest—70%. 25% tubulovillous; 5% villous.
- It also can be *solitary or multiple*, sessile or pedunculated.
- Tubular is commonly 1-2 mm sized and sessile is 3-4 mm sized.



Fig. 22.25: Colonoscopic view of colonic polyp.

- ***It has malignant potential***.
  Potentiality increase with:
  - *Size, is an important factor* in causing carcinoma. If size of adenoma is > 2 cm—30-50% chances of developing carcinoma; 1-2 cm —10% chances of carcinoma; < 1 cm —1-5% chances of carcinoma.
  - Sessile nature.
  - Villous architecture.
  - Dysplasia.

Grading of adenoma

- I: Minimal hyperplasia, no cellular atypia
- II: Mild hyperplasia, cellular atypia
- III: Moderate hyperplasia, cellular atypia
- IV: Severe hyperplasia, cellular atypia
- V: Carcinoma *in situ*

Features of Adenoma

- Can be asymptomatic.
- Bleeding per anum is usually chronic but rarely can be acute.
- Anaemia.
- Prolapse—common in tubular type.
- Diarrhoea common in villous type; mucus discharge.
- Tenesmus, colicky abdominal pain.
- Spurious diarrhoea.
- Poor general health.
- Electrolyte imbalance—*hypokalaemia.*
- Per-rectal examination should be done to feel the adenoma/ polyp.
- Carcinomatous changes.

Investigations

- Serum electrolytes.
- *Barium enema* study—shows filling defect—usually multiple.
- *Colonoscopy—biopsy is a must.*
  - Size should be noted.
  - Texture—harder tumour more likely to be malignant.
  - Colour of the lesion—pale is benign, pink, red and active—could be carcinoma.
  - Ulceration on the surface if it has turned into malignancy.

Treatment

- Colonoscopic polypectomy using snare. Any adenoma more than 5 mm in size should be removed colonoscopically.
- Diathermy excision/coagulation with sigmoidoscope.
- Per-anal polypectomy.
- Per-anal excision with clear margin of the rectal sessile adenoma.
- Open-abdominal colotomy and polypectomy in case of huge adenoma.
- Segmental resection of the colon if polyps/adenomas are limited to one segment of the colon confirmed by colonoscopy.

- Total colectomy/proctocolectomy if multiple polyps present all over colorectum and if associated with FAP.
- Blood transfusions, correction of electrolytes, protein supplements.

Problems in therapeutic colonoscopy

- Perforation due to necrosis
- Haemorrhage—secondary
- Intracolonic explosions
- Sepsis

FAMILIAL ADENOMATOUS POLYP (FAP)

- It is inherited as an autosomal dominant neoplastic condition (chromosome no. 5q21).
- It presents in younger age group—15-20 years.
- Incidence is equal in both sex, involving commonly the large intestine but can also occur in stomach, duodenum and small intestine.
- It is familial with a *high potential for malignant transformation*. If there is no adenoma at the age of 30 years, then it is not FAP of colon.
- It can be associated with duodenal or ampullary carcinomas, *Gardner's syndrome* [Desmoid tumour in the abdomen, osteomas (75%) and epidermoid cysts] and also *Turcot"s syndrome* [FAP + brain tumour (medulloblastoma or gliomas)] or sarcoma of bone.
- Usually multiple (over 100).
- Presents with lower abdominal pain, loose stools with blood and mucus, weight loss.

Investigations

- Double contrast barium enema.
- Colonoscopic biopsy.



Fig. 22.26A



Figs 22.26B and C

Figs 22.26A to C: Multiple polyps extensively involving the colon.



Figs 22.27A and B: Colonoscopic view of polyp colon in two different patients.

Self-respect — that a corner stone of all virtue.

- Screening of *all the members of the family is a must*.

  Pigment spots in retina (Congenital hypertrophy of the retinal pigmented epithelium of the iris, CHRPE / CHIRPES) and DNA tests for FAP are good screening methods, but cost and availability limits its use.
- Patients with FAP will develop colorectal cancer almost 100% in the absence of surgical intervention.

Treatment

1. *Proctocolectomy with ileoanal anastomosis with ileal pouch* is commonly done.
2. Alternatively a conservative *total colectomy* with ileo rectal anastamosis can be done, but with a regular follow-up with sigmoidoscopy for any *rectal polyps*. If present *snaring of polyps* should be done.

Sulindac (NSAID) 300 mg BD/*aspirin* 325 mg OD is given to these patients, causes disappearance of polyps in the rectum.

GARDNER'S SYNDROME

- It is commonly associated with FAP—10%.
- Presents with bone, skin, soft tissue and dental abnormalities. Jaw osteomas are very common. Other features are epidermoid cysts (50%), exostoses, fibromas, lipomas.
- Associated with desmoid tumours seen in the scar, abdomen, intraabdominal region and mesenteric fibromatosis.
- Congenital hypertrophy of pigment layer of retina (seen as pigment spots)—commonly seen.
- Often associated with MEN IIb syndrome.

Turcot's syndrome

- Autosomal recessive disorder
- Colonic polyps + brain tumours like
- medulloblastoma or gliomas
- Often associated with FAP

Cronkite-Canada syndrome

- Polyps in stomach, duodenum and colorectum. No polyps in oesophagus, small intestine
- Intractable diarrhoea, pigmentation, cachexia, alopecia, onychodystrophy
- In females
- 15% will have malignancy

Cowden syndrome
(multiple hamartoma—neoplasia syndrome)

- Autosomal dominant
- Penetrance at age 20 with PTEN suppressor gene mutation
- Benign ectodermal tumour—tricholemmoma—80%
- Macrocephaly—40%
- GI polyposis—35% and no risk of GI malignancy
- 10% risk of thyroid cancer
- 30-50% risk of breast cancer

Bannayan-Riley-Ruvalacaba syndrome
(Ruvalacaba Myhre Smith)

- Autosomal dominant
- GI hamartomatous polyp
- Macrocephaly, mental retardation
- Delayed psychomotor development
- Lipid storage myopathy
- Hashimoto's thyroiditis
- Hyperpigmentation of penile skin
- No risk for GI or extra GI malignancy

CARCINOMA COLON

- It is commonly *adenocarcinoma*.
- Very rarely adenosquamous, squamous carcinoma can occur.

Adenocarcinoma

- Sigmoid colon (21%) is the most common site of malignancy after rectum (38%).
- In caecum it is 12% common.

Aetiology

- ***Diet:***
  - Red meat and saturated fat increases the incidence of colonic cancer.
  - Cholesterol increases the bile acid concentration in the intestinal lumen which acts as cocarcinogen.
  - High fibre diet protects the colon against cancer.
  - Calcium in diet prevents colonic cancer by combining with bile salts and reducing bile salt concentration in the colon. It directly acts on the colonic mucosal cells to reduce their proliferative potential.
  - Diet with lack of fibre increases the risk. Diet with high fat increases the risk.
  - Dietary vitamins A,C, E and zinc reduces the risk.
- ***Genetic:***
  - Carcinoma colon is more common in individuals with *adenoma colon* or with *familial adenomatous polyposis (FAP)*, Gardner's syndrome, Turcot's syndrome.
  - Relatives of colonic cancer patient have got 2-4 times increased risk of developing carcinoma of colon.
- Long standing *ulcerative colitis, Crohn's disease* has high risk of colonic cancer. Crohn's disease is a premalignant condition but not as much as ulcerative colitis.
- *Alcohol and cigarette smoking increases the risk.*
- *Hereditary nonpolyposis colonic cancer (HNCC)* has got high incidence (25%) of synchronous and metachronous growth, so total colectomy is needed.
- After cholecystectomy and ileal resection there is increased bile salts and so more prone for carcinoma colon.
- Radiation increases the risk (mucinous type).

- Ureterosigmoidostomy increases the risk by 100-500 times.
- Acromegaly may increase the risk.

Note:
Aspirin, calcium and other NSAIDs protect against colonic cancer.

Pathogenesis

- Adenoma—carcinoma sequence
  - Most of the colonic carcinoma develops from polyp/adenoma pathway.
  - Normal epithelium →initiation by 5q loss APC gene → dysplasia (hyperproliferative) → DNA methylation → early adenoma → 12p activation K ras → intermediate adenoma →18q loss DCC → late adenoma → action by 17p loss p53 →carcinoma → spread .
- 80% of colorectal cancer arises from *loss of heterozygosity (LOH) pathway*. LOH pathway is due to APC gene defects (in FAP), K ras mutation altering the cell cycle [K ras binds to GTP (guanosine triphosphate) hydrolyse to GDP which inactivates G protein normally; K ras mutation blocks GTP hydrolyse leading into permanently active form of G protein causing carcinoma]; loss of DCC tumour suppressor gene; mutation of tumour suppressor gene p53. LOH pathway is microsatellite stable (MSS) and carries poor prognosis compared with MSI.
- 20% of colorectal cancer develops from mutation from *RER (Replication Error Repair) pathway* wherein repair mechanism of DNA replication error is lost. It causes microsatellite regions of genome to have repeated sequences leading into error and is called as *microsatellite instability* (MSI). In colon, it is seen in right side growths and is associated with better prognosis.

Colonic cancer may be:

Nonhereditary colon cancer

- It can be sporadic colon cancer—60%.
- It can be familial colon cancer—30%. Common in Ashkenazi – Jewish population.

Hereditary colon cancer

- FAP.
- HNCC.
- Peutz Jeghers syndrome—2-3% risk of cancer colon.
- *Cronkite—Canada syndrome.*
- *Juvenile polyposis syndrome*—it differs from isolated juvenile polyps discussed earlier. It is an autosomal dominant condition, occurs in children and adolescent. Germ line mutation of SMAD-4 gene is observed. It increases the risk of colonic cancer.

HNCC (hereditary nonpolyposis colonic cancer)

- No polyps. Autosomal dominant
- Three members of the family have colonic cancers
- Two first degree relatives will have same cancer
- Two consecutive generations observed
- One relative with less than 50 years age will have colonic cancer
- *Lynch syndrome* I is site specific—commonly right sided, occurs in early age group, 40% are metachronous
- *Lynch syndrome* II has other malignancy in, stomach, breast, ovary, endometrium and urinary bladder. It is cancer family syndrome
- Microsatellite instability (MSI) at DNA level occurs in HNCC
- Accounts for 3-5% of colonic cancers
- Amsterdam criteria I (1990); Amsterdam criteria II (1999) and revised Bethesda guidelines (2002) are used to diagnose HNCC

Types

Patient can have *de novo multiple primary* carcinomas in different parts of the colon at the same time, i.e. ***synchronous* (5-10%),** or can present with growth in different parts of the colon in different periods, i.e**. *metachronous* (10-20%).**
Gross types: *Annular, tubular, ulcerative, cauliflower like.*

Amsterdam criteria	Bethesda criteria
• At least 3 relatives of common cancer	Amsterdam criteria or one of the following:
• One affected person is 1st degree relative of other two affected persons	• 2 cases of HNPCC associated cancer in one patient including synchronous or metachronous cancer
• Two successive generations affected	• Colon cancer and 1st degree relative with HNPCC associated cancer and or colonic adenoma
• At least one case of colon cancer diagnosed before the age of 50 years	• Colon or endometrial cancer diagnosed before the age of 45
• FAP excluded	• Right sided colon cancer that has an undifferentiated pattern or signet cell type before the age of 45
Modified Amsterdam criteria	• Adenoma diagnosed before 45
Same as Amsterdam except cancer must be associated with HNPCC (colon, endometrium, small intestine, renal pelvis and ureter) instead of specifically colon cancer	


Annular
Tubular
Ulcerative
Cauliflower like (proliferative)

Fig. 22.28: Gross types of carcinoma colon. Annular and tubular types are common in left side, ulcerative and proliferative are common in right side.

Annular (stenosing) type:
- It is more common on left side.
- Here the growth spreads round the internal wall and so it often presents with intestinal obstruction.

Ulcerative type:
- It is common on right side.

Proliferative type:
- Common in right side. It is fleshy, bulky and polypoid. It is less malignant.


Colon
Growth
Ileum
Caecum
Appendix
A
B

Figs 22.29A and B: (A) Carcinoma caecum showing proliferative lesion. (B) Thickening of the wall is seen.


Ascending colon
Growth
Caecum
Ileum
Appendix

Fig. 22.30: Carcinoma ascending colon. Note the growth, caecum and ileum. It is proliferative type.


Transverse colon
Growth

Fig. 22.31: Carcinoma transverse colon. It is ulceroproliferative lesion.

Histology (WHO)

- Adenocarcinoma—90%.
- Mucinous adenocarcinoma—5-10%.
- Signet ring cell carcinoma.
- Small cell/oat cell carcinoma—rare—extremely poor prognosis.
- Squamous cell carcinoma.
- Undifferentiated carcinoma.

Duke's histological grading of carcinoma colon (Now modified Morson-Dawson)

- Grade I—low grade.
- Grade II—average grade.
- Grade III—high grade.
- Grade IV—anaplastic.

Carcinoma confined to muscularis mucosa does not metastasize.



Fig. 22.32: Carcinoma descending colon. Note the proliferative tumour. Commonly it is stricture type/annular type on left side.



Figs 22.33A and B: Annular type of growth observed in left sided/ sigmoid colon.

Haggitt's Invasion of Malignant Polyp

In pedunculated polyp
Level 0—noninvasive carcinoma over the summit.
Level 1—invasion to head of the pedunculated polyp.
Level 2—invasion to neck of the pedunculated polyp.
Level 3—invasion to stalk of the pedunculated polyp.
Level 4—invasion to base of the pedunculated polyp.
In sessile polyp—all lesions are level 4.



Fig. 22.34: Ulceroproliferative lesion in the colon. Note the everted edge.



Fig. 22.35: Carcinoma colon—types.

Sessile Malignant Polyp Invasion

Sm 1: Submucosal invasion into upper 1/3rd (superficial/ inner).
Sm 2: Submucosal invasion into middle 1/3rd (inner 2/3rd).
Sm 3: Submucosal invasion lower 1/3rd (deep).

Staging of carcinoma colon

Duke's

A. Confined to bowel wall, mucosa and submucosa
B. Extends across the bowel wall to the muscularis propria with no lymph nodes involved
C. Lymph nodes are involved

Modified Duke's

A. Growth limited to rectal wall
B. Growth extending into extrarectal tissues but no lymph node spread
    B1: Invading muscularis mucosa
    B2: Invading into or through the serosa
C. Lymph node secondaries
D. Distant spread to liver, lungs, bone, brain

Astler-Coller's grading of colorectal/rectal cancer

A. Intramucosal
B1 Involvement up to muscularis propria
B2 Spread through the wall in to peritoneum
C1 B1 + involvement of lymph nodes
C2 B2 + involvement of lymph nodes
D Distant spread

Spread

Direct spread:

- Locally it can invade the bladder, obstruct ureter and so cause hydronephrosis.
- Can perforate and cause peritonitis/pericolic abscess/faecal fistula.
- Growth may get adherent to psoas muscle posteriorly.
- Carcinoma sigmoid colon can infiltrate and cause colovesical or colovaginal fistula. It can infiltrate ureter, ovary, uterus etc. It can cause pericolic abscess or abscess in lateral abdominal wall.

Lymphatic spread:

- Growth through lymphatics spreads to pericolic, epicolic, intermediate and principal group of lymph nodes.

Groups of lymph nodes draining colon

- N1: Nodes immediately adjacent to bowel wall.
- N2: Nodes along ileocolic/right colic/middle colic/ left colic/ sigmoid arteries.
- N3: Nodes near the origin of SMA and IMA.
- Nodal spread in carcinoma colon is sequential from N1 → N2 → N3.

Blood spread:

- 40% of carcinoma colon spreads to *liver via portal veins.*
- *Secondaries* may be either *solitary* or *multiple*, present as liver with hard, umbilicated nodules.
- Rarely it spreads to *bone, lung, skin.*

Cunderson-Sosin staging

A – Lesion limited to mucosa
B_1 – Through mucosa, still within bowel wall
B_2 – Through entire bowel wall
B_3 – Adherent to or invading adjacent organs
C_1 – Limited to bowel wall but node +ve
C_2 – Through entire bowel wall, node +ve
C_3 – Adherent, invasion to adjacent organs with node +ve
D – Distant spread / locally unresectable tumour

TNM staging of colorectal cancer

Tumour—T

T_x – Primary tumour cannot be assessed
T_0 – No evidence of tumour
Tis – Carcinoma *in situ*—intraepithelial/invasion into lamina propria
T_1 – Invasion into submucosa
T_2 – Invasion into muscularis propria
T_3 – Invasion into pericolorectal tissues/fat
T_{4a} – Invasion into surface of the visceral peritoneum
T_{4b} – Direct Invasion or adherent to adjacent structures/organs

Regional nodes—N

N_x – Nodes cannot be assessed
N_0 – No nodal spread
N_1 – Regional nodes 1-3 involved
  – N_{1a} – 1 regional node
  – N_{1b} – 2 to 3 regional nodes
  – N_{1c} – Tumour deposits in serosa/mesentery/nonperitonealised pericolic or perirectal tissues without regional nodes
N_2 – Regional nodes 4 or more involved
  – N_{2a} – 4-6 regional nodes
  – N_{2b} – 7 or more regional nodes

Distant metastases—M

M_0 – No distant spread
M_1 – Distant spread present
  – M_{1a} – Spread confined to one organ or site—liver/lung/ ovary/nonregional nodes;
  – M_{1b} – Spread to more than one organ or site/peritoneum.

Histological grade—G

G_x – Grade cannot be assessed
G_1 – Well differentiated
G_2 – Moderately differentiated
G_3 – Poorly differentiated
G_4 – Undifferentiated

Residual tumour—R

R_0 – No residual tumour after resection
R_1 – Microscopic residual tumour after resection
R_2 – Macroscopic residual tumour after resection

Stage Group

0 – Tis N_0 M_0
I – T_1 N_0 M_0; T_2 N_0 M_0
IIA – T_3 N_0 M_0
IIB – T_{4a} N_0 M_0
IIC – T_{4b} N_0 M_0
IIIA – T_{1-2}, N_{1-1c}, M_0; T_1 N_{2a} M_0
IIIB – T_{3-4a} N_{1-1c} M_0; T_{2-3} N_{2a} M_0; T_{1-2} N_{2b} M_0
IIIC – T_{4a} N_{2a} M_0; T_{3-4a} N_{2b} M_0; T_{4b} N_{1-2} M_0
IVA – Any T Any N M_{1a}
IVB – Any T Any N M_{1b}
V_0 – No venous invasion; V_1—Presence of venous invasion
L_0 – No lymphatic vessel invasion; L_1—Presence of lymphatic vessel invasion

Clinical Features

- Occurs usually after 50 years. Familial type can present in younger age group. Common in males (M : F :: 3 : 2).
- Commonly present with loss of appetite and weight, anaemia, abdominal discomfort and mass per abdomen.
- 20% of cases present as an acute intestinal obstruction.
- 20% of colonic/colorectal cancer has stage IV disease at the time of first presentation.
- ***Right sided growth*** commonly presents with *anaemia, palpable mass* in the right iliac fossa, which is not moving with respiration, mobile, nontender, hard, well-localised with impaired resonant note.

Differential diagnosis for mass in the right iliac fossa

- Ileocaecal tuberculosis
- Appendicular mass
- Actinomycosis
- Ectopic kidney
- Mesenteric lymph nodes
- Ovarian tumour in females
- Retroperitoneal tumour
- Amoeboma

Carcinoma caecum occasionally presents like acute appendicitis or intussusception with intestinal obstruction.


Multiple liver nodules (Secondaries)
Pleural effusion
Ascites
Tumour
Enlarged nodes
Right sided tumour
- Anaemia
- Mass RIF
- Like appendicitis
- Intussusception
- Pericolic abscess
- Altered bowel habits
- Loss of appetite
- Decreased weight
- Jaundice
- Left supraclavicular LN (Troisier sign)
Perforation peritonitis
Left sided tumour
Obstructive symptoms
Pericolic abscess
- Tenesmus
- Diarrhoea
- Mucus
- Mass LIF
- Back pain
Bleeding per anum
- Urinary symptoms
- Fistula into bladder/vagina
- Hydronephrosis by ureter infiltration
- Blumer shelf (rectovesical secondaries)

Fig. 22.36: Clinical features of carcinoma of colon—diagrammatic representation.

- ***Left sided growth*** presents with *colicky pain, altered bowel habits (alternating constipation and diarrhoea*), palpable lump, distension of abdomen due to *subacute/chronic obstruction*. Later may present like complete colonic obstruction. Tenesmus, with passage of blood and mucus, with alternate constipation and diarrhoea, is common. Bladder symptoms may warn colovesical fistula.
- Features of pericolic abscess/obstruction (15%)/perforation/peritonitis may be the first presentation.
- *Closed loop obstruction* can occur in transverse colon growth (stricture type causing block) with competent ileocaecal valve. Enormously dilated right sided colon is prone for *stercoral ulcer,* perforation and faecal peritonitis.
- Enlarged liver with multiple umbilicated hard secondaries, ascites, rectovesical secondaries, palpable left supraclavicular lymph nodes are other presentations.
- Faecal strength of *Streptococcus bovis* bacteria increases many fold in patients with colonic cancer compared to individuals without colonic cancer.


Abdominal wall
Carcinoma colon
Pericolic abscess

Fig. 22.37: Carcinoma with pericolic abscess right sided. Mass here will be tender and localised. Patient may be having fever, tachycardia. Associated obstruction may be there occasionally.



Fig. 22.38: Dilated colon in colonic growth with obstruction.


Tumour causing complete block
Dilated ascending colon and caecum (closed loop obstruction)
1.
Ileum
Competent ileo-caecal valve
2.
Stercoral ulcer in the caecum
1 and 2 are sites of perforation

Fig. 22.39: Carcinoma transverse colon or near hepatic flexure can cause complete block, leading into the enormous dilatation of caecum. If ileocaecal valve is competent, then there will be closed loop obstruction of right-sided colon causing *stercoral ulcer* due to pressure ischaemia over the summit of the caecum. Perforation can occur in stercoral ulcer or in growth site itself. It is treated by emergency surgery with resection and temporary ileostomy.


Growth in transverse colon—stricture type
Terminal ileum
Appendix
Dilated caecum and ascending colon

Fig. 22.40: *Closed loop obstruction* specimen showing in a operated patient with growth in mid-transverse colon. Extended right hemicolectomy was done.

Local complications of carcinoma colon

- Intestinal obstruction
- Closed loop obstruction
- Perforation and peritonitis
- Vesicocolic fistula
- Invasion of ureter
- Pericolic abscesss

Investigations

Screening and surveillance for colon cancer

- *Faecal occult blood test (FOBT)*—it is nonspecific test for peroxidase contained in haemoglobin. It is simple but with low specificity
- *Flexible sigmoidoscopy*—once in 5 years to identify the adenoma; it is often combined with FOBT
- *Colonoscopy* is the most accurate and most complete method for evaluating the entire colon. It allows identification of small polyps (< 1 cm), allows biopsy, polypectomy, control of bleeding, stricture dilatation if needed. Problem as a screening method is—prior need for mechanical bowel preparation
- *Air contrast barium enema (ACBE)* detects polyps greater than 1 cm. Its accuracy is more in proximal colon than in sigmoid colon as one may misinterpret a polyp for diverticulosis
- *CT colonography (Virtual colonoscopy)*—it is helical CT 3 dimensional intraluminal colon imaging. It needs bowel preparation, air insufflation, CT imaging

- *Barium enema*: Shows irregular filling defect and *'apple core' lesion* (in left sided carcinoma). It also helps in finding colonic polyps (*Air-contrast barium enema*).
- *Colonoscopy and biopsy* confirms the diagnosis.
- Virtual colonoscopy (CT colonography) is also useful to visualize entire colon.



Fig. 22.41: Carcinoma colon—colonoscopic view.

- U/S, to see secondaries in liver, peritoneum, lymph node status, rectovesical secondaries.
- **CEA (*Carcinoembryonic antigen*):**
  - It is a *cell surface glycoprotein* discovered by Gold and Freedman.
  - It is normally produced by colonic epithelium.
  - Its serum ½ life is up to 10 days and is cleared by liver through Kupffer cells. So its ½ life prolongs in cholestasis and hepatocellular dysfunction.
  - Normal level is < 2.5 ng/ml. Level > 5 ng/ml is significant.
  - Even though it is a widely used tumour marker, it has got low sensitivity.



Figs 22.42A and B: Carcinoma colon. (A) Barium enema study, (B) Air-contrast study.



Figs 22.43A and B: X-rays with barium enema showing narrowing in sigmoid region (A) and irregularity (B).

  - CEA is primarily associated with colorectal cancers, but it can also increase significantly in pancreatic, gastric, lung, breast carcinomas. Often its level also increases in nonmalignant conditions like pancreatitis, hepatitis, obstructive jaundice, BPH.
  - *Uses in colorectal cancers are*:
    a. Preoperative levels >7.5 ng/ml signifies poor prognosis.
    b. If postoperative level does not fall, it indicates either incomplete resection, or occult metastasis elsewhere.
    c. Increase CEA during follow-up indicates recurrence or secondaries.



Fig. 22.44: Barium enema X-ray showing irregular filling defect in caecum—feature of carcinoma colon.

  - A slow rise indicates loco regional disease.
  - A rapid rise signifies metastasis.
  - It is not useful in assessing follow-up in poorly differentiated adenocarcinoma as such tumour will not produce CEA.
- Left supraclavicular lymph node if palpable, its FNAC may clinch the histological diagnosis.
- Hb%, PCV, haematocrit, ESR. Look for *occult blood in stool* is the initial test for anaemia.
- CT scan abdomen and pelvis—to see local spread, invasion, size and extent, stage, nodal status and liver secondaries.
- LFT—mainly enzyme studies like alkaline phosphatase, SGPT.



Fig. 22.45: CT scan picture showing growth in the right side colon.



Fig. 22.46: Colonoscopic view of carcinoma colon.

Treatment



Area of resection
in right sided growth
Area of resection
in left sided growth
Growth in colon
Line of
resection

Fig. 22.47: Levels of resection in growths in different portions of the colon.



Growth in transverse colon
Line of
resection
Terminal 6 cm
of ileum

Fig. 22.48: Diagram showing extended right hemicolectomy.

Art is long, life short, judgement difficult, opportunity transient.


Ileotransverse bypass anastomosis in inoperable right side growth
Colocolic bypass anastomosis in inoperable left side growth

Fig. 22.49: Ileotransverse anastomosis in case of inoperable hepatic flexure growth. Colosigmoid bypass in case of inoperable growth in splenic flexure. .

Mainly Surgical

- *Right sided early growth*:
  - *Right radical hemicolectomy* with ileo transverse anastomosis is done. Structures removed are terminal 6 cm of ileum, caecum and appendix, ascending colon, 1/3 of transverse colon, lymph nodes (epicolic, paracolic, intermediate).



Fig. 22.50: Specimen of hemicolectomy done for carcinoma caecum. Note the different parts—terminal ileum, ascending colon, hepatic flexure and omentum.

  - In inoperable right sided growth, *ileotransverse anastomosis* is done as a by-pass procedure.
- *Transverse colon growth*
  - *An extended right hemicolectomy* is the procedure done for transverse colon growth which includes division of right colic, middle colic arteries at their origin, with removal of terminal 6 cm ileum, ascending and transverse colon; anastomosing terminal ileum and proximal part of the descending colon—*ileocolic*.
  - Alternatively, in mid-transverse colon growth, transverse colon with both flexures can be removed; anastomosing cut ends of ascending and descending colon—*colocolic*.
- *Left sided early growth*:
  - Left radical hemicolectomy is done, where in left ½ of transverse colon and descending colon is removed along with lymph nodes.
  - *Left sided stenosing type of growth* can present with acute intestinal obstruction, in which case initially colostomy is done. Later, after 3-6 weeks, following proper preparation, required formal procedure is done, followed by colostomy closure after 8 weeks (*3 stage operation*).
  - Often growth in the transverse or left sided colon, which is stenosing or obstructive type, can cause *closed loop obstruction* because of the competent ileocaecal valve. As a result, pressure increases in the caecum eventually leading to its perforation. Perforation can also occur occasionally at the site of tumour. They need *emergency intervention*—caecostomy or colostomy, or ileostomy with resection and anastomosis. If severe peritonitis sets in, it may be life-threatening.
  - Left sided colon growth *with obstruction* can be treated with resection of tumour, saline lavage and cleaning the rest of the colon by passing a catheter through the appendix into the caecum followed by primary anastomosis thus avoiding colostomy.
  - In severely *obstructed sigmoid growths* are often alternatively treated as tumour resection with removal of entire proximal colon and continuity is maintained with ileo sigmoid/ileorectal anastomosis. It also avoids diversion.
  - During exploration, presence of any synchronous growths has to be looked for. Now it is found that carcinoma colon can be *associated with tuberculosis or lymphoma of colon*. So this association is also looked for.
  - In acute left sided growths, *trans anal self-expanding metal stents* can be used instead of defunctioning colostomy.
  - *Turnball's 'No touch technique':* Here the vessels are ligated at its origin, at the beginning, in order to prevent the tumour spread—due to tumour handling.
- *Multiple synchronous primaries* in the colon.
  - *Total abdominal colectomy* with ileorectal anastomosis is done if there are multiple primary tumours or in HNPCC. Significant chronic diarrhoea is the problem due to defective water absorption.
- Surgical treatment of *liver secondaries.*
  - *In solitary liver secondary*, segmental hepatic resection is useful.
  - In case of multiple secondaries confined to one lobe of the liver, hemihepatectomy can be tried.
  - *Metastasectomy*—it is done in one secondary/one lobe secondaries/less than 3 metastases in both lobes/without any extrahepatic spread.
- '*A second look operation'* is most often helpful in carcinoma of colon, to resect the residual or recurrent tumours (*Owen Wangensteen's Second look surgery).*
- If there are synchronous growths or growth with other area having multiple potential polyps, then total colectomy with colorectal anastomosis is done.
- Recurrent tumour should be treated by re-exploration and resection with adjuvant chemotherapy of different regime.
- Laparoscopic evaluation and resection is becoming popular. Laparoscopic assisted colonic resection is also done [*Hand assisted laparoscopic surgery (HALS)*].

Note:

- *Caecum and ascending colon*—right radical hemicolectomy (terminal ileum to mid transverse colon); *hepatic flexure and transverse colon*—extended right radical hemicolectomy (terminal ileum to proximal descending colon); *splenic flexure*-extended left radical hemicolectomy (hepatic flexure to rectosigmoid); *descending colon and sigmoid*—left radical hemicolectomy (splenic flexure to rectosigmoid).
- Minimum *5 cm* margin clearance at colonic side/sides is needed; *6 cm terminal ileum* clearance is sufficient in case of right sided growth.
- Duodenum, ureter, IVC, superior mesenteric vein should be taken care of during dissection in right hemicolectomy; spleen, stomach, tail of the pancreas should be taken care of in left hemicolectomy.
- It is *ideal* to mobilize both flexures adequately in all colonic surgeries to reduce the anastomotic tension.
- Bleeding *at anastomotic site edges* should be adequate; in emergency obstructive situation, better to do temporary covering colostomy or ileostomy to prevent anastomotic leak.
- On table and postoperative *hypoxia and hypotension* should be prevented to minimize anastomotic leak.
- *Preoperative mechanical bowel preparation* is important in elective colonic resection using polyethylene glycol / mannitol, oral bowel antiseptics like neomycin and metronidaziole.
- Infiltration into adjacent local structures is *not a contraindication* for surgical resection.
- At least *12 nodes should be examined* during histology after resection.
- *Blood transfusion* before or during surgery for colonic cancer may alter the immunological aspect of the colonic cancer and may increase the recurrence rate and so may alter the prognosis. It is presently not very well-proved. *Reason thought is*—blood transfusion raises the suppressor T cells leading into immunosuppression. So autologous blood transfusion is better when in case of need.
- Proper preoperative bowel preparation by mannitol/ polyethylene glycol/hypertonic saline/bowel wash/ bowel antiseptics (neomycin or gentamycin or streptomycin and metronidazole orally).
- Antibiotic prophylaxis; DVT prophylaxis by crepe bandage or stockings bandage, heparin or low molecular weight heparin.
- Pulmonary function tests and pulmonary exercise preoperatively as well as postoperatively.
- Urinary catheterisation, nasogastric tube placement.
- Postoperative proper care with fluid, electrolyte, drain care, early mobilisation, monitoring.
- Complications of surgery are leak (fecal fistula), bleeding, infection like intraperitoneal/pelvic abscess, respiratory problems, DVT, wound infection, burst abdomen.

Adjuvant Therapy

Chemotherapy

Indications for chemotherapy

- Positive nodes.
- T4 lesions.
- Venous (microscopic) spread.
- Signet cell type.
- Poorly differentiated tumour/aneuploidy.
- Changes in CEA level.

Postoperative chemotherapy is used commonly. Occasionally also given preoperatively.

Regimes are:

- 5 fluorouracil (5 FU) with folinic acid (leucoverin/ LV) is the most commonly used regime for 6 months as monthly cycles. Folinic acid potentiates the action of 5 FU.
- Levamisole 150 mg/day for 3 days given once in 15 days for one year with intravenous 5 FU monthly for one year.
- Irinotecan/5 FU/LV—IFL regime is also used.
- Folinic acid (LV)/5 FU/oxaliplatin—FOLFOX regime is also used. It is becoming treatment of choice.
- Irinotecan/oxaliplatin—IROX regime is used in previously untreated metastatic colonic cancer.
- Capecitabine (xeloda) an oral drug which generates 5 FU at tumour tissue, shows significantly greater response than 5 FU/LV regime.
- Phase II trials are going on for capecitabine/oxaliplatin and capecitabine/irinotecan combination regimes.
- 5 FU infusions into the portal vein during and immediately after surgery have shown benefits in terms of outcome and recurrence.

EGFR and VEGF blockers (EGFR is epithelial growth factor receptor; VEGF is vascular endothelial growth factor):

- They are used as single agent and also in combination with chemotherapy drugs in phase II and III trial.
- Drugs are monoclonal antibody, cetuximab which blocks EGFR, bevacizumab which binds VEGF.

- Dose of 5 FU is 400 mg/m^2/day IV × 5 days once in 3-4 weeks for 6-12 months
- Dose of leucoverin is 20 mg/m^2/day × 5 days once in 3-4 weeks for 6 months
- Dose of levamisole is 150 mg/day × 3 days once in 2 weeks for one year
- Capecitabine is given orally 1250 mg/m^2 twice daily

Radiotherapy

- Usually there is no role for RT as tumour is radioresistant.
- It is often used in locally advanced tumour, infiltrating the psoas major muscle or lateral abdominal wall, left sided colonic growth.
- It is also used in inoperable recurrent tumour.

Follow-up of Carcinoma Colon

- For 3 years at regular intervals, once in 3-6 months.



Fig. 22.51: Patient has undergone left hemicolectomy earlier for sigmoid growth with a colostomy; now presenting as recurrence at colostomy site. It could be recurrence of original disease or could be new metachronous disease in the mucosa of the colostomy site. CT scan/CEA/PET scan will help to differentiate. Re-excision can be done if it is metachronous local growth.

The most vital test of a man's character is not how he behaves after success, but how he sustains defeat.

This is by:
- Regular CEA analysis
- Ultrasound abdomen
- Barium enema X-ray
- Colonoscopy
  Rise in CEA is a definite indicator of recurrence or secondaries
  In patients with raised CEA, radioisotope antibody study will show the site of recurrence or secondaries
- Serum alkaline phosphatase

Note:
- ***Local recurrence***: Incidence of local recurrence after radical resection is 15%. 85% of recurrence is detected in 2 years. It is more in colocolic and colorectal anastomosis than ileocolic. *Recurrence may be*—local/locoregional/regional/metastatic. *Recurrence may be*—true recurrence at anastomotic site, probably mucosal; adjacent and close to anastomotic site, at the original primary tumour bed; peritoneal recurrence; recurrence in adjacent organ. It is due to implantation of spilled tumour cells during easier surgery, incomplete resection, metachronous new lesion, retrograde lymphatic spread. It is identified by CEA, CT scan, radioisotope/radioimmuno assay, colonoscopy. It is treated by curative surgery with clearance, chemotherapy, RT.
- Colonoscopy after 1 year to see anastomotic site, new / missed polyp/metachronous growth.
- Later colonoscopy is done once in 3-5 years unless there is a family history (here yearly colonoscopy is needed).
- CEA estimation once in 3 months for 2 years. If there is a raise any time, further screening is done for recurrent/metastatic disease by CT/MRI/PET scan.

Prognosis

Depends on:
- *Site*—left sided tumours has got better prognosis as they present early.
- *Type*—colloid carcinoma has got poorer prognosis.
- *Size* of the tumour.
- *Lymph nodes status: Number of lymph nodes* involved decides the prognosis.
- *Liver secondaries has poor prognosis.*
- *Age of the patient.*
- Associated diseases like *HIV.*
- *Stage of* the tumour.
- Presence of complications, perforation, peritonitis.

On the whole, it is a curable malignancy with proper surgery and adjuvant therapy.

5 year survival is:
Stage I – 90%.
Stage II – 75%.
Stage III – 50%.
Stage IV – less than 5%.

ANGIODYSPLASIA OF COLON

- It is a vascular ectasia seen *commonly in right side* colon.
- It is uncommon in healthy individual.
- It is commonly seen in elderly of 70 years age. It is acquired malformation of aging.
- It is not common in left side colon. It is often associated with calcified aortic stenosis; and ectasia bleeding if present, stops once aortic stenosis is corrected.
- Common cause of rectal bleed in adults and elderly.
- *An acquired condition seen in caecum* and ascending colon due to degeneration of the mucosal and submucosal vessels of the colon.
- Diagnosis is by mesenteric angiography. *Angiographic criteria in angiodysplasia*—early and prolonged filling of draining veins; cluster of small arteries; visualisation of vascular tuft.
- Colonoscopic fulguration or resection is the treatment.
- Therapeutic embolisation is useful in 85% of cases.

OGILVIE'S SYNDROME

- *Described by* Sir William Heneage Ogilvie in 1948.
- Also called as *colonic pseudo-obstruction.*
- Severe colonic ileus occurs without any mechanical obstruction.
- *Tympanic, nontender, distended* abdomen and bowel sounds will be normally present—are the clinical features. Features of causative etiology may be present.
- Occurs in critically ill patients.
- Due to sacral parasympathetic nerve dysfunction.
- Commonly seen in *right and transverse colon.*
- Due to sacral parasympathetic malfunctioning, there is atony of descending colon causing functional obstruction. Splenic flexure will be the junction of dilated and collapsed parts of the colon wherein parasympathetic supply of vagus ends and of sacral parasympathetic begins. Increased sympathetic activity causes colonic dilatation.
- It is seen in:
  - Scleroderma, SLE, dermatomyositis.
  - Chaga's disease.
  - Myotonic dystrophy, multiple sclerosis.
  - Neuropathies.
  - Myopathies.
  - Hypothyroidism, diabetes mellitus.
  - CRF, renal transplantation.
  - Poisoning, sepsis, hypoxia.
  - Radiotherapy, orthopedic procedures.
  - Psychiatric disorders, drug abuse.
  - Retroperitoneal irritation by blood, urine, pancreatic enzymes.
  - Lumbar spine and pelvic trauma, shock, stroke.
  - Septicaemia, burns, MI.
  - Can be *idiopathic* also.
- *Investigations:*
  - Plain X-ray abdomen shows dilatation of colon.
  - Barium enema will be normal.
  - Careful gentle colonoscopy is useful as therapeutic also.
  - CT abdomen to rule out mechanical obstruction of large bowel.

Treatment

- Mainly conservative.
- Motility enhancing drugs like neostigmine and erythromycin are used. *Neostigmine* is given 2.5 mg IV for 3 minutes, showing response in 10 minutes in 90% of patients. But bradycardia should be watched for and atropine should be kept ready.

- Prokinetic drugs like cisapride/mosapride are used.
- Ceruletide decapeptide 0.3 μg/kg IM is used to stimulate intestinal motility.
- Ryle's tube aspiration.
- Flatus tube insertion. It is not very useful as disease is common in proximal colon.
- *Epidural anaesthesia* causes sympathetic blockade relieving pseudo-obstruction.
- *Colonoscopic decompression* is also useful.
- Correction of electrolyte imbalance.
- Sodium enema.

Caecal diameter more than 12 cm (critical) on X-ray indicates surgical exploration.

- Tube caecostomy; resection and exteriorisation.

COLOSTOMY

It is an artificial opening made in the colon to the exterior (skin) to divert faeces and flatus.

Types

1. ***Temporary:*** Is done in conditions wherein diversion is required to facilitate healing distally in the rectum or distal colon. And this is closed once the purpose is over.

   Site of temporary colostomy is usually right hypochondrium and left iliac fossa.

   It can be *loop colostomy* or *Devine's double-barrel colostomy* (wherein there is a gap between the two openings of colostomy which prevents spillage into the distal loop).
2. ***Permanent*** colostomy is always *end colostomy* placed in left iliac fossa, 6 cm above and medial to the anterior superior iliac spine.

Indications

Temporary	Permanent
Congenital megacolon	AP-Resection.
Anorectal malformations	Carcinoma anal canal.
Sigmoid volvulus	After Hartmann's operation
Perforation of left sided colon	
Left sided colonic growth	
High anal fistula	
Trauma to left sided growth	

Colostomy can be:

- Loop, end, double barrel.

It can be:

- *Diversion colostomy*: It is done when there is breach in bowel wall, trauma, destruction, sphincter injuries, Crohn's, carcinoma rectosigmoid. It is usually brought out as an end colostomy with a mucus fistula or with a Hartmann's resection. It can be at sigmoid, descending and transverse colon.



Figs 22.52A to D: Types of colostomy. (A) Temporary colostomy, (B) Loop colostomy, (C) Devine's double barrel colostomy, (D) Permanent colostomy.



Fig. 22.53: Different types of stomas used in colostomy.

- *Decompression colostomy*: It is done for obstructive lesions in rectosigmoid, toxic megacolon. Types—(1) *Blow hole* procedure is done as a single or multiple small stomas onto the skin to decompress colon in acutely ill patients with massively dilated or impending perforation of colon. Problems are—remaining possible ischaemic parts of the colon is not identified still risking perforation; peristomal skin complications and mucosal prolapse is common. (2) *Tube caecostomy*—It is technically easier without much complications; but tube getting blocked limits its use regularly. (3) *Loop transverse colostomy*—It serves as decompressing and diverting long stoma without getting blocked. It is done only in mobile colon.
- *Irrigation colostomy*: It avoids need for appliance wear; reduces the passage of uncontrolled gas with less leak of stools. But it is time consuming with chance of water intoxication due to excess water absorption during irrigation.



Fig. 22.54A

Better alone than in bad company.



Fig. 22.54B

Figs 22.54A and B: Diagram of colostomy in a patient with colostomy bag.

Complications of colostomy

- Prolapse of mucosa (prolapse of distal loop mucosa is common)—commonest complication
- Retraction
- Necrosis
- Stenosis
- Herniation
- Bleeding
- Diarrhoea
- Enteritis
- Skin excoriation

Educating the patient regarding the proper usage of colostomy bags and proper care of the colostomy is very essential.

Colostomy Care

- Similar to stoma care.
- Initially stoma bag should be transparent as content is liquid stool but later it can be opaque.
- Regular consultation with stoma therapist.
- Care of the skin.
- Training for managing colostomy, its care to prevent leak, odour, and discomfort.

Closure of Colostomy

Criteria for temporary colostomy closure:

- Integrity of distal colon should be normal and adequate.
- Anorectal sphincter should be normal.
- Cause for construction of colostomy is cured completely without any suspicious of recurrence of same disease distally.
- When temporary colostomy is done, it is closed usually after 3 months.
- *Two types of closure are present*—extraperitoneal and intraperitoneal type. *Now intraperitoneal closure is done*. Earlier extraperitoneal closure was done in loop colostomy by placing a spur in between and closing the antimesentric part of the colon. It prevents the peritoneal contamination. But inadequate closure, leak, adhesions are the problems. *Intraperitoneal closure*—commonly advocated technique now, is done by placing a circumferential incision over the margin with skin edge. Incision is deepened to enter the peritoneum and pull out the colostomy stoma. Part adjacent to the skin is resected and anastomosed using silk/vicryl. Sutured bowel is placed into the peritoneal cavity. Drain is placed into the peritoneal cavity. Abdomen is closed in layers.
- Closure of colostomy is done after proper bowel preparation, under general or spinal anaesthesia.
- Proper postoperative care is important.
- Patient should perform anal sphincter exercises to prevent sphincter atrophy and to maintain sphincter tone.



Fig. 22.55: Patient with colostomy bag. He has undergone abdominoperineal resection (APR) for carcinoma rectum.



Fig. 22.56A



Fig. 22.56B

Figs 22.56A and B: Prolapse of colostomy is a common complication.



Fig. 22.57: Caecostomy is often done in acute colonic conditions as diversion procedure after surgery distally like perforation closure and resection. But it is not as popular as colostomy because it may not function adequately, may get displaced or blocked. But it is technically easier and usually done by doing appendicectomy and passing Malecot's tube through appendicular stump. Removal is easier without any surgical intervention.

STOMA CARE

Definition of Stoma

Stoma is an artificial opening or 'mouth like' to the exterior, the abdominal wall so as to drain the content from the tubular structures inside, like bowel or ureter. It is done for diversion of urine or faecal matter in case of malignancy, trauma, and sepsis or after surgery.

Types

- ***Ileostomy***—terminal 5 cm ileum is projected out, on to the skin of abdominal wall to drain semi-liquid, faecal matter.
- ***Colostomy***—colon at different levels, can be brought out to the skin as required as colostomy, to divert faecal matter.
- ***Cutaneous ureterostomy***—cut ends of one or both ureters are apposed to the skin of abdominal wall.
- ***Ileal urinary conduit***—segment of isolated ileum can be used to drain urine from the ureter as urinary ileal conduit. Ureters are anastomosed to a closed ileal conduit. Ileal stoma is brought out as stoma. Different types of continent ileostomies are in use to prevent leak, soakage and discomfort.
- ***Vesicostomy***—it is done in children. Here anterior wall of bladder is brought out and bladder mucosa is sutured to the skin of abdominal wall.

Stoma created may be *round* (commonly) or *square* in shape.

Preparation and Counselling of the Patient for Stoma

- To certain extent stoma of any type causes psychological and physical trauma to the patient, as it is nonphysiological, distressing and socially not acceptable.
- Patient should be explained about the procedure and should be convinced and consoled about the stoma.
- Detailed meaning, explanation and after care of the stoma should be discussed.
- Indication for the stoma and consent for the same should be taken.
- Reassurance about the stoma, its care, and its position should be diagrammatically explained to the patient and his close relative.
- In case of obstructive disease, stoma is done as an inevitable procedure to relieve the obstruction, often it may be temporary.
- Proper bowel preparation by bowel wash, gut irrigation is required before surgery.
- *The surgeon selects the site of the stoma.*
  - Stoma is usually sited midway between anterior superior iliac spine and umbilicus.
  - It should be away from the belt line.
  - It should be away from the scar, creases, and bony points.
  - Patient should be assessed for proper size, adequacy for stoma in lying down, sitting, and standing positions.
  - Proper stoma appliances should be decided after thorough check-up and discussion with patient and patient's relative.
  - Stoma site should be marked properly before surgery.
  - Ileostomy is usually sited in the right iliac fossa, colostomy in left iliac fossa.
  - Allergy for the particular appliances should be checked for.
  - The patient should consult stoma therapist.

Postoperative Care for the Stoma

- Stitches are removed in 6-10 days.
- Dressing should be done first over the stoma and after placement of appliance, laparotomy wound is dressed otherwise stoma appliance will not sit properly.
- Patient should be observed for any complications.
- Once wound has healed patient can take bath by removing the appliances. After bath skin is dried up and stoma appliances can be fit again.
- Patient should be taught about the stoma care and its appliances.
- Care and prevention of skin excoriation due to leak is also looked into.
- Psychotherapy is given for the patient.
- Skin should be *absolutely dry* prior to placing the stoma appliances.



Fig. 22.58: Right sided temporary loop colostomy. Note the tube kept in between.

Complications of Stoma

- Skin excoriation.
- Mucosal prolapse—common complication.



Fig. 22.59: Colostomy prolapse is the common complication.

- Stenosis and block.
- Infection either bacterial or candidial.
- Diarrhoea due to irritation.
- Leak due to improper fitting of the appliances, scar, irregularity of stoma, prolapse.
- Bleeding from the stoma edge.
- Herniation of the abdominal contents adjacent to stoma.

Skin Excoriation

It is a major problem in stoma patients. It is basically due to leak adjacent to appliances.

Causes for Excoriation

- Leak due to improper appliances.
- Wet skin before placing the appliance.
- Inadequate stoma hole.
- Improper and inadequate adhesive sheet usage.
- Allergy.
- Infection like of bacteria and candida.
- Altered weight of the patient.
- Stoma bag is overfilled or kinked or air in the stoma bag.

Treatment of Excoriation

- Control of infection by antibiotics and control of moniliasis.
- Allergy has to be confirmed, and if it is the cause, the agent is found out and treated as required.
- Zinc oxide cream application.
- Change of the type of appliance.
- Refashioning of the stoma.

STOMA APPLIANCES

Stoma appliances are devices, which are used to collect and dispose the effluent materials which come out of the stoma.

Ideal stoma appliance is*:*

- Leak proof
- Should not damage the stoma and surrounding skin
- Should prevent odour
- Should be available
- Easier to use

Types of Appliances

It can be:

- *Closed type* is discarded when full and is used in patients with well-formed stool.
- *Drainable type* is used in patients with loose liquid stool. It can be emptied and retained and reused. Immediately after colostomy, drainable appliance is used. Later, it can be changed over to closed type.

It can also be:

- *One-piece stoma* appliance as a bag with adhesive system attached which adheres to skin around the stoma.

- *Two-piece stoma* appliance has got a flange with adhesive system and a bag over it, which can be removed and replaced with a new one without disturbing the flange underneath.

Bag can be:

- *Transparent,* in which fluid can be visualised. It is used in initial period of the stoma.
- *Opaque,* in which fluid cannot be visualised. It is used eventually later.

General Care and Advice to Patients with Stoma

- Patient can have normal diet. Diet, which regulates the bowel action, is better. Plenty of water is advisable.
- Patient can go for normal work, exercise like sports, swimming, tennis. Stoma appliances suitable for these works are available.
- Antidepressants, anticholinergics might cause constipation. So these drugs should be taken carefully.
- Using irritant solutions near stoma should be avoided. It may lead to dangerous complications.
- Patient can have normal sexual activity.
- Patient should have additional stoma bags in hand so as to use if required urgently.
- Patient should be aware of different appliances available and should be well-versed with its use. He can take the help of the stoma societies.

FAECAL FISTULA

- This is a dangerous entity.
- It commonly occurs after appendicectomy (gangrenous), ileal resection, colonic surgery, malignancy, ileocaecal TB, actinomycosis and Crohn's disease.
- It may be from the ileum or the colon.
- It may be single or multiple openings.
- More proximal the fistula, more is the severity in fluid and electrolyte imbalance.
- It may be from the main incision wound or from the drain wound.
- If there is no distal obstruction, the fistula will heal spontaneously, but may take a longer time.
- *Fistulogram* often delineates the track.
- CT fistulogram with CT scan abdomen is essential.
- Often gastrograffin study is also useful to study the fistulous track in detail.

Factors preventing closure (FRIENDS)

- F : Foreign body in fistula tract
- R : Radiation enteritis
- I : Inflammatory bowel disease
- E : Epithelialisation of tract
- N : Neoplasm
- D : Distal obstruction
- S : Sepsis

Factors preventing spontaneous closure of faecal fistulas

- High output > 500 ml/24 hr
- Distal bowel obstruction
- Sepsis, inflammatory bowel disease
- Tuberculosis
- Cancer
- Radiation enteritis
- Foreign body in fistula tract
- Epithelialisation of tract



Fig. 22.60: Multiple faecal fistulous openings in the abdominal wall. Patient has undergone laparotomy for acute peritonitis.

Investigations for faecal fistula

- Fistulogram using gastrograffin
- CT scan and CT fistulogram
- Barium enema study



Fig. 22.61A

An essential aspect of creativity is not being afraid to fail.



Fig. 22.61B

Figs 22.61A and B: Gastrointestinal faecal fistula after an emergency surgery for ileal perforation with severe peritonitis. Patient recovered after long-term stay in the hospital.

Treatment

- TPN and blood transfusion may be required to improve the nutritional status of the patient.
- Sepsis is controlled with proper antibiotics.
- Management of fluid and electrolyte loss.
- Skin is protected from excoriation by using zinc oxide cream.
- If it persists, later exploration and resection is done.
- The cause is treated.
- Bypass may be required. (*Most of the time, the decision is, taken on table during surgery*).

PREPARATION OF LARGE BOWEL FOR SURGERY

Principle Behind Bowel Preparation

Colon contains large amount of bacteria up to 10^9 / ml of faeces. Most common anaerobe is bacteroides; commonest aerobe is *Escherichia coli; Pseudomonas, Enterococcus, Proteus, Klebsiella, Streptococcus* are other organisms. Bowel preparation is done to clear this bacterial load to reduce postoperative complications.

Methods Used

1. **Mechanical bowel preparation**
   - *Polyethylene glycol (PEG)* is a non absorbed sodium sulphate solution, 2-3 litres of which is asked to drink by the patient along with plenty of additional fluids orally. It cleans the bowel by passing loose stool for 10-15 times in 12 hours. It acts by its hygroscopic action. *Side effects* are—nausea, vomiting, and abdominal cramps. Antiemetics are often needed. It is ideal in renal failure, ascites, cirrhosis, CCF.
   - *Sodium phosphate* is an alternative to PEG as smaller volume is sufficient to take. But it causes electrolyte imbalance. Its efficacy is similar to PEG. But patient compliance is better with sodium phosphate. It can cause hyponatraemia, hypocalaemia, hypocalcaemia and hypophosphataemia in case of renal dysfunction. In such patients it is contraindicated.
   - *Other methods*—(1) *Total gut irrigation* daily using 200 ml of *oral mannitol* or through nasogastric tube for 3 days prior to surgery. (2) *Bowel wash* daily for 3 days prior to surgery using 2 litres of normal saline (not water as it will cause water intoxication); it cleans entire large bowel. (3) Senna, castor oil, bisacodyl. (4) Repeated enemas. *PEG or sodium phosphate has taken over all this methods*.

   Contraindications for mechanical bowel preparation: Complete bowel obstruction and perforation.
2. **Antibiotics—parenteral and as bowel antiseptics**
   - *Oral neomycin* (gentamycin, streptomycin were used in olden days) 1 gram, *erythromycin* 1 gram, is used 3 days prior to surgery. Alternatively *ciprofloxacillin and metronidazole* are used. IV fluids should be given in addition to these patients to maintain adequate hydration.
   - *IV antibiotics 4 hours before* making incision, reduces the incidence of sepsis. Usually cephalosporins are given.

Controversies

- There is doubt about the advantages of preoperative mechanical bowel preparation even though it is practiced universally.
- Oral antibiotics to reduce the bacterial load in the colon is also controversial. However, preoperative single dose parenteral antibiotic improves the result and reduces the sepsis.

Indications for Large Bowel Preparation

- Carcinoma colon (especially left sided).
- Anorectal malformations.
- Megacolon.
- Carcinoma rectum.
- Surgery for ulcerative colitis.
- FAP.
- Diverticulitis.
- High pelvirectal fistulas.
- Before colonoscopy.

SURGICAL POUCHES

Pouches are created as reservoir whenever needed as a replacement for the existing reservoir like stomach, rectum, and urinary bladder.

Types

- *Jejunal pouches:* It is used for stomach. Hunt Lawrence pouch, omega loop, Roux en loop are the examples. It is commonly used after total gastrectomy. Hunt Lawrence pouch is 15 cm in length.
- *Ileal pouch*: It is used as rectal reservoir, urinary reservoir, ileostomy reservoir. Examples are—J, S, W, H pouches

Pathological pouches	Experimental physiological pouches	Natural pouches
• *Zenker's diverticulum* causing pharyngeal pouch • *Physick's pouch* in the rectal wall in between rectal valves • *Hartmann's pouch* is protruded pathological gallbladder infundibulum	• *Heidenhein pouch*: To study gastric physiology done in stomach • *Pavlov pouch:* Gastric pouch created with retaining *vagii* to study gastric physiology	• *Rathke's pouch* in pituitary • *Seessel's pouch* in pharynx • *Morrison's hepatorenal* pouch • Rectouterine pouch of *Douglas*

after proctocolectomy with ileo anal anastomosis; Koch's pouch for ileostomy; Ileal pouch for bladder replacement or cutaneous ureterostomy.

- *Colonic*: Sigmoid reservoir or caecal/ileocaecal reservoir is often used to replace urinary bladder.

Principles

- Blood supply should be preserved.
- Mesentery should extend adequately.
- Bowel is opened on the antimesenteric border and sutured using vicryl posterior and anteriorly.
- Created pouch is anastomosed to the required area from its summit or from open end.

Complications

- Obstruction (25%) is the common complication. It may be due to stomal stricture, internal hernia, volvulus and adhesions.
- Pouch disruption and leak can occur which is usually treated conservatively.
- Pelvic abscess formation in ileoanal pouch is confirmed by clinical features of fever, back pain, raised total count, CT scan. It is treated with antibiotics, drainage per abdomen or reservoir excision and ileostomy.
- Pouchitis: It is the common problem (20%). Tenesmus, bloody diarrhoea, spasm, back pain, fever, cramps, dehydration are the presentations. It is treated conservatively with antibiotics, hydration, *probiotics*.
- Vaginal fistula formation.
- Anal canal stricture formation.
- Faecal incontinence.
- In urinary conduits, sepsis, acidosis, electrolyte imbalance, stone formation, urine leak are the complications.

Note:
Pouch is contraindicated in *Crohn's disease*.

BARIUM ENEMA

- It is the contrast X-ray done to visualise large bowel.
- Therapeutic barium enema is done in intussusception in children.

Barium enema

Indications	Finding
Carcinoma colon	Irregular filling defect
Ileocaecal tuberculosis	Pulled up caecum, obtuse ileocaecal angle
	Filling defect, incompetent ileocaecal valve
Ulcerative colitis	Loss of haustrations, lead pipe appearance
Colonic polyps	Smooth, regular filling defect
Congenital mega colon	Narrow zone, zone of cone, dilated proximal segment
Diaphragmatic hernia	Colonic shadow in the left thoracic cavity
Gastrojejunocolic fistula	Leak into the stomach from colon



Fig. 22.62: Barium enema showing normal peristaltic movement.

Arrogance is the obstruction of wisdom.

Procedure

Laxative is given previous evening. Enema is given on same day before doing the procedure. About one litre of barium sulphate solution is infused into the colorectum per anally through enema tube. In children 12F Foley's catheter is used. Once complete filling occurs, X-ray is taken. Patient is asked to evacuate the barium and postevacuation film is taken. After that, air is inflated into the colon which gives a better contrast to visualise thin mucosa of the colon (**air-contrast barium enema).**

Contraindications

Acute colonic conditions.



Figs 22.63A to C: Barium enema X-ray in different indications should be taken with complete filling, postevacuation and after air-contrast.

Chapter 23 Intestinal Obstruction

CHAPTER OUTLINE

- Intestinal Obstruction
- Dynamic Obstruction
- Duodenal Atresia
- Small Intestine Atresia
- Malrotation
- Meconium Ileus
- Intussusception
- Volvulus
- Sigmoid Volvulus
- Paralytic Ileus
- Adhesions and Bands
- Internal Hernias

INTESTINAL OBSTRUCTION: TYPES

Classification I: Depending on Aetiopathology

A. Dynamic.
B. Adynamic.

Classification II: Depending on Type of Obstruction

1. Acute: Common in small bowel.
2. Chronic.
3. Acute on chronic: Common in large bowel.
4. Closed loop obstruction.

	Dynamic		***Adynamic***
Outside the wall	*In the wall*	*In the lumen*	
Hernia—25% Adhesions—40% Volvulus Intussusception	Tuberculous stricture Crohn's disease Malignancy	Gallstones Roundworm Inspissated faeces Meconium ileus	Cessation of peristalsis Postoperative period Electrolyte imbalance Spinal injuries Uraemia Diabetes mellitus Retroperitoneal—haematomas and surgeries Renal surgeries Mesenteric ischaemia Pseudo-obstruction

Classification III: Depending on Site of Obstruction

	Proximal small bowel	***Distal small bowel***	***Large bowel***
Site of obstruction	*Duodenum and jejunum*	*Ileum*	*Any where in large intestine*
Causes:	Congenital Lipomas Leiomyomas Malignancy Bands and adhesions	Tuberculosis strictures Malignancy Crohn's Gallstones Hernias—common cause Roundworm Congenital	Malignancy Tuberculosis stricture Anorectal malformation Volvulus Congenital megacolon Bands
Clinical features:	Severe vomiting, dehydration, no or less distension, colicky pain	Central distension, vomiting, dehydration central abdominal pain	Constipation, distension—early; Late vomiting less pain
Special features:			
Plain X-ray	Valvulae conniventes	Characterless Central fluid level	Dilatation and haustration

Today's friction is tomorrow's destruction.

Classification IV

A. Congenital.
B. Acquired.

Congenital	*Acquired*
Anorectal malformations	Hernia (commonest)
Congenital megacolon	Postoperative
Adhesions	Intussusception
Duodenal atresia	Roundworm
Intestinal atresia (ileal)	Gallstones
Bands and adhesions	Tuberculosis
Malrotation	Malignancy
Volvulus neonatorum	Internal hernias

Bolus obstruction

- Worms
- Gallstones
- Trichobezoars
- Phytobezoars
- Meconium pellets
- Foreign body
- Food bolus
- Stercoliths

Intestinal obstruction still is a challenging, commonly acute condition in surgical practice. *Adhesions* are becoming the more common cause of intestinal obstruction than hernia nowadays. Common causes for adhesions are gynaecologic surgeries, appendicectomy, colonic and pelvic surgeries. 20% cases of intestinal obstruction are due to malignancy or its peritoneal *carcinomatosis* spread. More than 50% of intestinal obstruction in western countries are due to adhesions; 20% due to malignancies; 10-15% due to hernias. Crohn's disease is also becoming a common cause of obstruction.

Note:
Adhesions and hernias are most common causes of intestinal obstruction.

DYNAMIC OBSTRUCTION

- It is mechanical blockage of normal propulsion and passage of intestinal contents.
- Obstruction may be external/internal; partial (incomplete or subacute)/complete; acute/acute on chronic/or chronic; simple/closed loop/strangulation; congenital/acquired; proximal/distal.
- Earlier, hernia was the commonest cause of intestinal obstruction. Now adhesions (40%) are the commonest cause especially in developed countries and hernia being 15-25% common. In developing countries both adhesions and hernia are the common causes of intestinal obstruction.
- Adhesions commonly cause small bowel obstruction than large bowel.
- Eighty per cent of intestinal obstruction occurs in small bowel; 20% in colon. 70% of colonic obstruction is due to malignancy. Other 30% is due to volvulus; diverticulitis, inflammatory cause like tuberculosis, etc.
- Mortality is 3% in obstruction without strangulation; 30% in obstruction with strangulation.
- Recurrent obstruction is more common in adhesions.

Pathology and Pathogenesis

- ***Changes proximal to the bowel obstruction***:

Intestinal obstruction
↓
Increased peristalsis
↓
Becomes vigorous
↓
Obstruction not relieved
↓
Peristalsis ceases.
↓
Flaccid, paralysed, dilated bowel

  - Fluid collects just proximal to the obstruction which is derived from saliva, stomach, pancreas and intestine. Because of oedema and inflammation absorption decreases, sequestration of fluid from the circulation into the lumen occurs and bacteria *(E. coli, Klebsiella,* anaerobes, bacteroides and other organisms) multiply, toxins are released—*toxaemia* occurs. This leads to severe dehydration, electrolyte imbalance.



Fig. 23.1: Intestinal obstruction due to band. Note the ischaemic bowel under the band.



Fig. 23.2: Postoperative internal hernia with obstruction.

- Proximal to the collected fluid, air accumulates (derived from swallowed air (70%), diffusion from blood into the lumen (20%), from digested product and bacterial action (10%)), in which, main component is nitrogen (90%) and also hydrogen sulphide. During vigorous peristalsis air enters the distal fluid, results in c*hurning,* is the reason to cause *multiple air-fluid levels in plain X-ray abdomen.*
- *Defective absorption*, decreased fluid intake, loss of fluid by vomiting, sequestration of fluid into the bowel lumen—leads into severe dehydration, fluid and electrolyte imbalance.
- Inflammatory response in the bowel wall (*intramural inflammation*) causes accumulation of activated neutrophils and macrophages in the muscle wall which release reactive enzymes and cytokines. These substances damage secretory and motor process of muscle leading into dilatation of the bowel. Increased release of *nitric oxide* in muscle wall and production of intramural reactive oxygen metabolites alter gut motility and permeability.
- *Intestinal wall hypoxia* is also the cause for dilatation.
- In first 12 hours of obstruction, there is *only decreased absorption* which causes accumulation of fluid and electrolytes in the lumen.
- After 12 hours, there is also *increased intestinal secretion* causing further accumulation of the fluid.
- Accumulation of bacterial toxins, bile salts, prostaglandins, and mucosa derived free radicals, VIP—all increases the luminal secretion of fluid in obstructed bowel.
- Dilatation of bowel wall increases *intraluminal pressure* which exceeds the bowel wall *venous pressure* causing ischaemia which causes further dilatation and *ischaemic injury*. This leads into eventual blockage of arterial perfusion causing bowel wall necrosis/ gangrene.
- *Increased bacterial colony* in the bowel (Normal flora is less than 10^6 colonies/ml in jejunum and 10^8 colonies /ml in the ileum) due to altered luminal content and environment → multiplication → toxins → further mucosa damage → disrupted mucosal defense/ barrier/ integrity → *translocation of bacteria across mucosa* into submucosa and also absorption of bacterial and other toxins into the circulation → bacteraemia/toxaemia/ septicaemia/SIRS/MODS.

Factors causing systemic problems in intestinal obstruction

- Dilatation of the bowel
- Decreased absorption across mucosa
- Increased secretion into the lumen
- Intramural inflammation and hypoxia
- Increased intraluminal pressure
- Venous congestion and increased venous pressure
- Disrupted mucosal barrier → bacterial translocation

- ***Changes at the site of the obstruction:***

Initially venous return is impaired.
↓
Congestion, oedema of bowel wall occurs which turns purple.
↓
Later this jeopardizes the arterial supply.
↓
Loss of shineness, blackish discolouration, loss of peristalsis.
↓
Gangrene.
↓
Perforation occurs.
↓
Bacteria and toxins migrate into the peritoneum.
↓
Peritonitis.



Fig. 23.3: Intestinal obstruction showing dilated bowel loops.



Fig. 23.4: Gangrenous bowel with proximal dilated and distal collapsed bowel segments.

> *The coexistence of intestinal colic and borborygmi, establishes the diagnosis of obstruction of the small intestine in more than 9 out of 10 cases.*
>
> **—Clarence Dennis**

Note:
- Causes for strangulation are—external like hernia (by constriction ring of the sac), adhesions, bands; compression in the wall causing mechanical block and compromised blood supply like in volvulus, intussusception; increased intraluminal pressure like closed loop obstruction; mesenteric ischaemia.
- Morbidity, poor outcome and mortality are more common in intraperitoneal strangulation than in strangulation of hernia as it is localised with less fluid loss.
- Outcome also depends on age of the patient, extent of the disease and time at which patient reaches for therapy.
- *Massive 3rd space fluid loss*, dehydration, hypovolaemia, hypotension, hypochloraemia, hypokalaemia, metabolic alkalosis, oliguria, azotemia, haemoconcentration (after fluid therapy haematocrit falls indicating the need for blood transfusion).
- *Translocation of bacteria* across oedematous small bowel wall causes septicaemia.

- ***Closed loop obstruction***:
  - When there is obstruction in the large bowel, with ileocaecal valve competence (40%), pressure increases in the caecum.

↓

Stercoral ulcer in the caecum.

↓

Gangrene.

↓

Perforation.

↓

Peritonitis (Faecal).

  - Perforation also can occur at the site of obstruction due to the malignant growth.



Fig. 23.5: Closed loop obstruction. Here loop of the bowel is obstructed at its point of entry and exit creating closed loop.



Fig. 23.6: Closed loop obstruction.

  - Closed loop obstruction also can occur when bowel get obstructed at both proximal and distal parts of the loop of the bowel. It can occur in external or internal hernias, volvulus, etc. Necrosis and perforation are both common at obstructed site and over the convex summit of the bowel content.
- ***Bowel distal to the obstruction*** *is inactive and collapsed.*

Clinical Features



Fig. 23.7: Step ladder peristalsis seen in small bowel obstruction. Note the previous laparotomy scar signifies obstruction is due to adhesions. Laparoscopy and proceed—is the needed management.

- ***Abdominal pain***:
  - Initially colicky and intermittent: later continuous and severe.
  - Pain is the first symptom to develop which is sudden and severe. Initial colicky pain suggests obstruction and eventual diffuse persistent pain suggests strangulation. Pain begins usually around umbilicus in small bowel obstruction.
  - In small bowel obstruction, it is crampy, recurrent paroxysms occurring as short crescendo/decrescendo episodes (of 30 seconds).
  - In large bowel obstruction, it is of longer episodes of minutes (In paralytic/adynamic ileus, pain is diffuse and mild).
- ***Vomiting***:
  - In *jejunal* obstruction, it is early and persistent.
  - In *ileal* obstruction, it is recurrent occurring at an interval; initially bilious later faeculent.
  - In *large bowel* obstruction, vomiting is a late feature.
- ***Distension***:
  - It is absent or minimal in case of *jejunal* obstruction
  - Obvious with visible intestinal peristalsis (VIP) and borborygmi sounds in case of *ileal* obstruction—*Step ladder peristalsis*.
  - It is enormous in case of *large bowel* obstruction.
- ***Constipation***:
  - It is *absolute,* i.e. neither faeces nor flatus is passed.

Exceptions

- Richter's hernia obstruction
- Gallstone obstruction
- Mesenteric vascular occlusion
- Intestinal obstruction with a pelvic abscess

- ***Dehydration***:
    - Leads to oliguria → renal failure.
- ***Features of toxaemia and septicaemia***:
    - Tachycardia, tachypnoea, fever, sunken eyes, cold periphery.
- ***Abdominal tenderness*:**
    - It is initially localised but later becomes diffuse—is a feature of intestinal obstruction. Rebound tenderness and guarding will not be present in simple obstructions which are features of strangulation.
- ***Features of strangulation*:**
    - Continuous severe pain, shock, tenderness, rebound tenderness *(Blumberg's sign).*
    - Guarding and rigidity, absence of bowel sounds.
    - In case of strangulated hernia, a swelling which is tense, tender, rigid, irreducible, no expansile impulse on coughing and history of recent increase in size is seen.
- ***Temperature*:**
    - Fever signifies inflammation in the bowel wall/ ischaemia/perforation.
    - Hypothermia can occur when septicoemia develops due to lack of pyrogenic response. It suggests poor prognosis.
- ***Bowel sounds*:**
  They are increased—high pitched metallic (rushes and groans) sounds followed by metallic tinkling sounds of dilated bowel. Eventually once fatigue occurs or gangrene develops, bowel sounds are not heard—silent abdomen of peritonitis develops (In paralytic ileus, there are only continuous metallic sounds of dilated bowel).
- ***Per-rectal examination*:**
    - Shows *empty, dilated rectum*, often with tenderness. If rectal growth is the cause for obstruction, it may be palpable.

Investigations



Fig. 23.8: Plain X-ray abdomen in erect posture showing dilated bowel and colon—a feature of intestinal obstruction.



Fig. 23.9: Multiple air fluid levels in intestinal obstruction.



Fig. 23.10: Plain X-ray abdomen showing multiple air fluid levels due to bowel obstruction.

- ***Plain X-ray abdomen***: (initially supine abdominal X-ray is taken; later if needed X-ray in erect posture is taken if perforation is suspected).
    - *Multiple air-fluid levels.*
    - Proximal the obstruction → Lesser the air fluid level.
    - Distal the obstruction → More the air fluid level.

Normally, *three fluid levels can be seen* in plain X-ray film—at fundus of stomach, at duodenum and often at caecum.

- *Jejunum* shows *concertina effect* due to *valvulae conniventes (Herring bone pattern)—by the valves of Kerckring.*
- *Ileum is smooth and characterless* (by Wangensteen).
- *Large* bowel shows *haustration.*
- *Pneumobilia* (gas in biliary tree) may be due to gallstone ileus.

- Distended caecum is shown as round gas shadow in the right iliac fossa. Dilated caecum signifies large bowel obstruction.
- Small bowel > 3 cm diameter; proximal large bowel > 9 cm; transverse colon > 5.5 cm; sigmoid colon > 5 cm are suggestive of intestinal dilatation. But this increased diameter need not suggest intestinal obstruction everytime.

Triad of small bowel obstruction in plain X-ray

1. Dilated small bowel loops > 3 cm
2. Multiple air fluid levels in erect X-ray
3. Paucity of air in the colon

- *Barium (micro bar solution) enema or gastrografin contrast enema X-ray* is useful in intussusception. [*Barium meal is usually contraindicated in acute intestinal obstruction*. However dilute (micro bar) barium meal/gastrografin meal follow through X-ray may be done with caution in suspected subacute/partial intestinal obstruction under fluoroscopy, otherwise it may precipitate complete obstruction or may cause perforation and barium peritonitis which is very dangerous].
- Haematocrit, blood urea and serum creatinine; arterial blood gas analysis (acidosis is common), LFT, platelet count (In severe sepsis there will be altered LFT with thrombocytopenia).
- Serum electrolytes estimation. Hypokalaemia is common.
- Total count is increased. But can be significantly low in severe stage of sepsis.
- Estimation of serum D lactate, CPK – BB isoenzyme, intestinal fatty acid binding protein are different investigations may be useful to predict bowel ischaemia/gangrene.
- *US abdomen* is useful to see dilated bowel and fluid in the peritoneal cavity. It is better than X-ray but not as good as CT scan. It has got 95% sensitivity; 80% specificity; 80% accuracy. Doppler US is useful in detecting strangulation.
- *CT scan* is very reliable investigation for intestinal obstruction. It has got 93% sensitivity; 94% accuracy and 100% specificity. In CT scan small bowel loop > 2.5 cm suggests dilatation. It can show dilated loop, transition zone and collapsed part which are definitive features of intestinal obstruction. It can also give idea of changes in the bowel wall, ischaemia, strangulation, mesenteric oedema and thickening. It also shows *bowel wall gas, portal venous gas* and mass lesion.
- Basic electrical rhythm of small bowel will be changed in ischaemia. It can be determined by noninvasive method using *superconducting quantum interference device (SQUID)*.

Complications of intestinal obstruction

- Peritonitis
- Hypovolaemic and septic shock
- Renal failure
- ARDS
- Intra-abdominal abscess formation
- Moribund status

Differential diagnosis

- Paralytic obstruction
- Pseudo obstruction
- Ascites

Treatment

- *Nasogastric aspiration*: To reduce toxic effects, to reduce bowel distension which indirectly improves pulmonary ventilation and to reduce possibility of aspiration pneumonia.
- *Replacement of fluid and electrolytes*.
- *Antibiotics:* Ampicillin, gentamycin, metronidazole, cephalosporins.
- *Blood transfusion*: FFP or platelet transfusions are often needed in critical patient.
- *ICU critical care*: Systemic management of complications like ARDS, DIC, SIRS are important. If there is hypotension, dopamine/dobutamine are also needed.
- *CVP for fluid and monitoring*: PCWP (pulmonary capillary wedge pressure) monitoring are often needed in haemodynamically unstable patient.
- *Surgery*:
  - ***Immediate laparotomy*** is done and the site (by finding the junction of dilated proximal and collapsed distal bowel) and cause of the obstruction is identified. The obstruction is relieved.

To check for viability of bowel, look for

- Peristalsis
- Pulsations
- Bleeding in mesentery and bowel wall
- Friability—friable, flabby muscle is seen in ischaemia
- Colour (black/pink)—dull and lusterless serosa is seen in ischaemia
- Serosal shining



Fig. 23.11: Bowel resection and anastomosis for gangrene in case of intestinal obstruction. Cheatle's cut on the antimesenteric margin of the collapsed distal segment is often needed to avoid discrepancy in luminal width. Single layer interrupted (silk/vicryl) or two layered continuous sutures can be used. Single layer is better in acute conditions.

- *Warm saline soaked mop* is placed over the doubtful area with 100% oxygen inhalation for 20 minutes; if colour becomes normal with peristalsis then bowel is viable.
- *On table Doppler* study may be useful.
- *Fluorescein fluorescence study* may be helpful on table to check the viability.
- If bowel is not viable *resection and anastomosis is done.* A good peritoneal wash is given and the abdominal cavity is drained.
- Abdomen is closed in layers using nonabsorbable sutures (polyethylene, polypropylene, nylon). Often tension sutures are required.
- Small bowel can be decompressed using *Savage's decompressor.*
- In case of *right-sided colonic* obstruction, *right hemicolectomy with ileocolic* anastomosis is done.
- In case of *left-sided colonic* obstruction, *left hemicolectomy* (resection) and *colo-colic* anastomosis is done with a *defunctioning colostomy* (right-sided transverse) which is closed after 6 weeks.
- Obstruction due to *rectosigmoid* growth with patient being severely ill—*Hartmann's operation* can be done to save the life of the patient wherein distal stump after removal of the growth is closed, proximal colon is brought out as *end colostomy.*
- *Second look operation* may be needed in doubtful cases or multiple segment obstructions in 24-48 hours to confirm viability.
- *Laparoscopic approach* may be useful in partial obstruction, proximal obstruction, obstruction due to band. Conversion when needed should be done without hesitation.
- *Acute postoperative obstruction* is difficult to identify and manage. CT is very useful. Initially it is treated conservatively (90%), but suspected ischaemic cases or persistent obstruction becomes an indication for surgery. Resection with exteriorization may be the choice.

Postsurgery Complications

- Pelvic abscess.
- Subphrenic abscess.
- Biliary or faecal fistulas.
- Burst abdomen.
- Bands and adhesions.
- Incisional hernias.

DUODENAL ATRESIA

- It is the commonest site of intestinal atresia.
- It is usually a complete stenosis of the second part of duodenum at the level of ampulla of Vater.
- It is defective fusion of foregut and midgut with failure of recanalisation.
- Incidence is one in 10,000 live births.

Types



Fig. 23.12: Types of duodenal atresia—complete; fibrous cord; duodenal stenosis and windsock deformity.

- Type 1: Duodenal complete atresia: It is the commonest type (50%). It is usually complete separation with intact wall. In 25% cases complete separation with wall also occurs.
- Type 2: Fibrous cord.
- Type 3: Incomplete or partial obstruction. It can be stenosis or web with an aperture.
- Duodenal diaphragm/web can present as complete; incomplete with a fenestra; incomplete diaphragm with central aperture which causes '*windsock' deformity* due to proximal dilatation. Here actual diaphragm will be proximal to the site of obstruction.
- Duodenal atresia may be *preampullary* (nonbilious vomiting) or *postampullary* (bilious vomiting). Postampullary is common (80-90%).

Associations

- Duodenal stenosis is often associated with annular pancreas.
- It can be isolated duodenal atresia or in association with Down's syndrome (30%)/incomplete rotation of gut (20%)/ congenital heart diseases (30%)/trisomy (30%)/anorectal malformations (10%), etc.
- It is commonly associated with maternal polyhydramnios (50%). Antenatal US can confirm it. 50% infants are premature.

Features

- Jaundice.
- Bilious/nonbilious vomiting immediately after birth.

- Features of gastric outlet obstruction.
- Dehydration. Electrolyte changes are common.
- Growth retardation of newborn due to deprived nutrition (by swallowed amniotic fluid in fetus).

Investigations

- Plain X-ray shows classic *double-bubble sign with absence of air in the distal part.*



Fig. 23.13: Double-bubble sign in duodenal atresia.

- In partial obstruction, air may be present in distal loop and so contrast study has to be done. Risk of aspiration in newborn infant should be remembered.
- U/S will show distended stomach and proximal duodenum, *rail road track* duodenum and features of associated anomalies. Maternal and fetal ultrasound in pregnancy may identify the pathology and also maternal polyhydramnios.

Treatment

- Proper preoperative preparation like correction of fluid and electrolytes; gastric decompression; TPN; injection vitamin K; evaluation for associated anomalies.
- *Duodenoduodenostomy* is done. Associated malrotation should be corrected in these patients (Ladd's operation). Side-side duodenoduodenostomy may cause dilated duodenum (megaduodenum—30%); anastomotic dysfunction; and delayed transit of the content.
- *Kimura's diamond shaped anastomosis* between transversely opened proximal pouch and longitudinally opened distal pouch reduces the problems of anastomosis. Presence of bile in the duodenum and proximal and distal patency should be confirmed by saline irrigation.
- Transanastomotic nasojejunal or gastrostomy tube for feeding purpose is needed as prolonged postoperative ileus is the usual problem.



Fig. 23.14: Duodenoduodenostomy is ideal in duodenal atresia. Kimura's modification has got lesser chance of developing side effects like gastroparesis.

- Duodenojejunostomy may cause blind loop problems. Gastrojejunostomy should not be done due to high incidence of marginal ulceration and bleeding.

SMALL INTESTINE ATRESIA (INTESTINAL ATRESIA)

- It is jejunoileal atresia.
- It is due to intrauterine mesenteric vascular accidents (occlusion) of the segments affected. V-shaped mesentery; presence of bile pigments in the distal segments suggesting earlier period of patency—are supportive for the above theory.
- It is often associated with malrotation, gastroschisis, volvulus—20%.
- Common site is proximal jejunum; next common is distal ileum.
- Maternal polyhydramnios occurs in 35% of jejunal atresia.
- Proximal bowel wall is dilated with hypertrophy but villi are normal. Distal bowel is collapsed but with hypertrophied villi. Narrow collapsed large intestine (microcolon) is seen in proximal atresia.



Fig. 23.15: Typical intestinal atresia.

Griesfield Modification of Martin's Classification of Intestinal Atresia

- Type I: Membranous/mucosal with normal mesentery—20%.
- Type II: The lumen is atretic—fibrous cord between proximal and distal parts of the segment involved (only one atretic segment) but mesentery is normal—40%.
- Type III (a): Atresia with complete separation of proximal and distal ends and V-shaped defect of mesentery—35%.
- Type III (b): Atresia with christmas tree-shaped defect in mesentery with distal bowel being supplied by single artery—right colic/ileocolic/superior mesenteric—*apple peel atresia*.
- Type IV: Multiple atresias—5%.


Type I: Mucosal atresia
Type II: Fibrous atresia
SMA
Jejunum
Type IIIa: Complete single atresia—V shaped mesentery
Type IIIb: Complete jejunal atresia with coiled ileum—christmas tree deformity
Type IV: Multiple atresias

Fig. 23.16: Types of intestinal atresia.

Clinical Features

- Equal in both sexes.
- Commonly infant is of low birth weight.
- Bilious vomiting with features of intestinal obstruction like distension.
- Features of associated anomalies.
- Respiratory distress.
- Jaundice.

Investigations

- Plain X-ray abdomen shows—*triple-bubble appearance* in jejunal atresia; multiple air fluid levels in ileal atresia.
- Barium enema may show narrow microcolon. Calcification suggests antenatal fetal bowel perforation.
- US abdomen to confirm associated anomalies.

Differential Diagnosis

- Other causes of neonatal intestinal obstruction like duodenal atresia, malrotation, volvulus of midgut.



Fig. 23.17: X-ray abdomen of a patient with intestinal obstruction in a newborn as neonatal intestinal obstruction.

Treatment

- Resection and anastomosis is the choice of therapy.
- Treatment of associated anomalies.
- Tapering proximal jejunoplasty is done if extensive length of jejunum is involved.
- Prognosis depends on length of atretic bowel; multiple atresias; associated anomalies.

MALROTATION

It is interference in the process of normal rotation of midgut in fetus and its mesenteric fixation.

Stages of Normal Rotation of Midgut

- *Stage 1*: In 4th-8th week of intrauterine period, midgut supplied by superior mesenteric artery (SMA) grows rapidly. As coelomic cavity cannot accommodate growing midgut during that period, it protrudes into the umbilical cord as *physiological hernia*.

> *If the hand is kept flat upon the abdomen the underlying coil may be felt to harden and soften alternately much like in a pregnant uterus, in a case of intestinal obstruction.*
> — **Arthur H Burgess**

- *Stage 2*: In 10th-12th week, midgut migrates into coelomic cavity. First, small bowel returns towards the left side of the abdomen. Then caecocolic loop returns to left lower abdomen. It rapidly rotates 270° counterclockwise to reach right iliac fossa. Then duodenojejunal segment rotates 270° counterclockwise to reach left of SMA and behind the colon.
- *Stage 3*: Fusion of different parts of mesentery and posterior peritoneum.

Different Errors of Rotation

- *Stage 1*: Exomphalos major/minor or gastroschisis.
- *Stage 2*: Errors of rotation in this stage is important and is usually considered under malrotation.
    - *Nonrotation*: Causing small bowel in right side; colon in left side; caecum in midline as suspension.
    - *Incomplete rotation*: It is the *most common type* of malrotation. Caecum is located in subhepatic right hypochondrium. *Ladd's peritoneal band* connects from caecocolic loop to posterior abdominal wall compressing the 2nd part of the duodenum. Entire midgut is hanging down along with SMA with a narrow based mesentery causing midgut volvulus.



Fig. 23.18: Diagram showing incomplete gut rotation and small bowel volvulus.

-
    - *Reverse rotation*: Final 180° rotation occur clockwise bringing colon posterior to duodenum and SMA.
    - *Hyperrotation*: Rotation up to 360° or 450° causing caecum on left side of the abdomen.
    - Encapsulated small bowel occurs while fetal midgut returns into coelomic cavity.
- *Stage 3*: Final defect in fixation causes mobile caecum and ascending colon leading into caecal volvulus.

Associated Anomalies (20%)

- Congenital diaphragmatic hernia of Bochdalek.
- Prune belly syndrome.
- Duodenal atresia.
- Oesophageal atresia.

Presentations

- Acute/recurrent/subacute intestinal obstruction.
- Midgut volvulus (30%) (usually clockwise rotation) with features of strangulation, perforation, peritonitis.
- Shock, septicaemia, passage of dark blood per rectum, oedema and erythema of anterior abdominal wall.
- In children—failure to thrive, recurrent abdominal pain, cyclical vomiting, constipation and diarrhoea.

Investigations

- Plain X-ray abdomen shows air fluid levels.
- Barium meal (dilute/microbarium) and follow through X-ray is the investigation of choice.
- US abdomen/CT abdomen, if needed.
- Haematocrit, serum electrolytes estimation.

Treatment

- Resuscitation, antibiotics, fluid and electrolytes, blood transfusion.



Fig. 23.19: Ladd's operation for incomplete gut rotation. Ladd's band is released. Duodenum is straightened. Appendicectomy is done.

- *Laparotomy* through horizontal incision is done. Clockwise rotated midgut which is congested and cyanotic is identified. Untwisting of the midgut in counterclockwise direction is done. Viability of bowel is confirmed (colour, vessels in mesentery, peristalsis, on table Doppler). *Ladd's band* is divided *large bowel is repositioned in left side.* The entire duodenum is *Kocherised* and the ligament of Treitz is divided so that *duodenum becomes straight towards right* iliac fossa. This achieves *wide root of the mesentery* and places the *small bowel in the right* side of the abdomen thus preventing further volvulus. A *complementary appendicectomy* is done—*Ladd's operation.*
- After laparotomy, if bowel is gangrenous, it is resected and remaining parts of the bowel are exteriorised as enterostomies. A second look operation is done to look for viability of remaining bowel and also to maintain the continuity. Often it will be extensive bowel resection leading into poor prognosis.

MECONIUM ILEUS

- It is neonatal manifestation of fibrocystic disease of the pancreas wherein thick meconium, which is viscid and paste like, gets collected in the terminal ileum. Because of inspissation it forms a firm bolus leading to obstruction of the ileum.
- Neonates present with features of ileal obstruction as well as respiratory dysfunction, exocrine pancreatic insuffi-

ciency, and high salt in the sweat (Na^+ and Cl^- more than 90 mmol/L).

- Meconium ileus occurs in 15% of patients with cystic fibrosis. Cystic fibrosis is an autosomal recessive disease involving bronchioles, exocrine pancreas and sweat glands. Condition is common in Caucasians. Exocrine pancreatic insufficiency and malabsorption is seen in 90% of patients with cystic fibrosis.
- There is hypertrophy and dilatation of the proximal ileum containing thick, viscid, tenacious dark green meconium. Distal ileum and colon are narrow and contracted having grayish meconium pellets. Meconium gets calcified very rapidly. Gangrene, perforation, volvulus can occur in 50% of cases.
- Intrauterine perforation causes fetal meconium peritonitis which leads to dense adhesions and calcification in peritoneum. Fetal meconium peritonitis is sterile.



Fig. 23.20: Pathology of meconium ileus. Note the meconium pellets in the distal ileum and colon; thick viscid meconium in proximal ileum.

- Plain X-ray shows calcified meconium pellets with multiple air fluid levels which appear as 'soap-bubbles' (*Neuhauser sign*).
- Vomitus of the patient which does not contain trypsin, when poured on the exposed X-ray film will not digest the gelatin of the film whereas the vomitus of individual with normal pancreas will digest the gelatin of X-ray film—*very useful test.*
- Pilocarpine, a cholinergic drug is injected into skin to stimulate the sweating and collected sweat (100 µg sweat) is analysed for sodium and chloride.
- Elevated albumin level in meconium, sodium level assay in nail clipping, serum immune active trypsin assay are other investigations.

Meconium ileus

- Commonly associated with cystic disease of pancreas but not necessarily always
- Respiratory dysfunction
- Exocrine pancreatic insufficiency
- High salt in the sweat > 90 mmol/L
- Ileal obstruction
- Soap-bubble appearance in X-ray
- Gelatin in X-ray film will not get digested by patient's vomitus
- Bishop-Koop operation, ileostomy, dissolving ileal meconium pellets are required

Complications of meconium ileus

- Intestinal bolus obstruction
- Perforation and peritonitis
- Gangrene, volvulus formation

Treatment

Nonoperative measures

- Dissolution through enema can be tried using *gastrografin* which is hyperosmolar and contains Tween 80 as dissolving agent. *Gastrografin* is diatrizoate meglamine with Tween 80 (polysorbate 80) as dissolving agent. Acetyl choline (2-4%) also can be used for irrigation per-anally.
- Acetyl choline wash through nasogastric tube also can be used—5-10 ml 6th hourly.
- Treatment for cystic fibrosis.

Operative measures

- When patient's condition is critical with obstruction, *Bishop-Koop operation* is done. Proximal dilated segment is resected and resected end is anastomosed to side of the distal collapsed ileum. End of the distal ileum is brought out as ileostomy. Through the ileostomy gastrografin or acetyl cystine wash is given regularly to dissolve meconium pellets. This ileostomy can be kept for long time. Continuity is maintained at later period.
- *Santulli operation* is done where proximal ileum is brought as ileostomy for irrigation using a fine tube and distal ileum is sutured to proximal ileum as end to side anastomosis.
- *Resection and anastomosis* is ideal if patient is fit and if proximal bowel is suitable for anastomosis.



Fig. 23.21: *Bishop-Koop operation*. Here distal ileum is brought as ileostomy and proximal part sutured to distal bowel.

Management of meconium ileus

- *Nonoperative wash per rectally* using acetyl cysteine or gastrografin through Foley's catheter passed per anally. Acetyl cysteine can also be passed for irrigation per orally through a Ryle's tube as 10 ml 6th hourly.
- *Bishop-Koop and Santulli operations* done in very sick neonates.
- *Resection and anastomosis* is ideal when child is adequately fit.



Fig. 23.22: *Santulli operation* done for meconium ileus wherein proximal ileum is brought out as ileostomy. Distal ileum is sutured to proximal.

Causes neonatal intestinal obstruction

- Hirschsprung's disease
- Duodenal atresia
- Intestinal atresia
- Malrotation
- Midgut volvulus/volvulus neonatorum
- Meconium ileus
- Anorectal malformation

INTUSSUSCEPTION (ISS)

Definition

It is telescoping or invagination of one portion (segment) of bowel into the adjacent segment.

Types

1. ***Antegrade***: Most common.
2. ***Retrograde***: Rare (jejunogastric in gastrojejunostomy stoma).

In elderly intussusception:

- Colocolic is most common type
- Apex is formed usually by growth
- No role of hydrostatic reduction

- It can be single or multiple (rare).
- It can be *ileo-colic (most common type, 75%),* colocolic, ileoileocolic, colocolic.
- It is common in weaning period of a child (common in male), between the period of 6-9 months.
- It is the *commonest cause* of intestinal obstruction in children of *6-18 months* age.

Aetiology

- Idiopathic ISS is common in children, occurs in terminal 50 cm of ileum.
- During weaning, change in diet causes inflammation and oedema of Peyer's patches—may stimulate ISS.
- Upper respiratory tract viral infection which causes oedema of Peyer's patches is also thought as an aetiology for intussusception in children.
- Other causes in adolescents and adults are submucous lipoma, leiomyoma, polyps in jejunum (Peutz-Jegher syndrome), other polyps and carcinomas with papillary projections.

Causes

- Change in diet during weaning
- Upper respiratory tract viral infection
- Intestinal polyps
- Submucous lipoma
- Leiomyoma of intestine
- Meckel's diverticulum
- Carcinoma
- Purpuric submucosal haemorrhages



Figs 23.23A and B



Fig. 23.23C

Figs 23.23A to C: Intussusception in different patients. Different parts and apex point is also clearly seen.

Pathology

- ***Apex*** is the one which advances;
- ***Intussuscipiens*** is the one which receives (outer sheath);
- ***Intussusceptum*** are the tubes which advances (middle and inner sheath).
  - Apex and inner tubes will have compromised blood supply which lead to gangrene.
  - Because of ischaemia, apex sloughs off and bleeds, which mixes with the mucous to produce the classic *red-currant jelly* that is passed per anum.
  - Gangrene which sets in leads to perforation and peritonitis.
  - Red currant jelly is not commonly observed in ISS in adult, but it can occur.



Fig. 23.24: Parts of intussusception.

Clinical Features

- Common in males (3:2).
- Common in 6-9 months. But can also occur at later age grouped children.
- Common in spring and winter, coinciding with the gastroenteritis and respiratory infections in respective periods.
- Commonest cause of intestinal obstruction in infancy.
- Initial colicky abdominal pain (75%) which eventually becomes severe and persistent.
- Sudden onset of pain in a male child, with progressive distension of the abdomen, vomiting, with passage of *"red-currant-jelly" stool.* It is usually not found in adult ISS.
- Often ISS is recurrent, when it gets reduced, child automatically becomes asymptomatic (Mother often complains "Bachha rotha he, Bachha sotha he". It means child cries during an episode and sleeps peacefully once it gets reduced).



Fig. 23.25: Sausage-shaped mass of intussusception.

- *On examination*, a mass is felt either on the left or right of the umbilicus which is sausage shaped with concavity towards umbilicus, smooth, firm, resonant, not moving with respiration, mobile, *contracts under the palpating fingers.* Often mass appears and disappears.
- Right iliac fossa is empty *(Sign of Dance).*
- After 24-48 hours, abdominal distension appears and increases progressively with features of intestinal obstruction.
- Features of intestinal obstruction with *step-ladder peristalsis*.
- Blood stained stool is often obvious on digital examination of the rectum. Occasionally ISS can be seen per anally and felt with a long mesentery.
- Eventually, gangrene and perforation occurs with features of the peritonitis.

Abdominal palpatory findings in ISS

- Palpable mass (85%)
  - Sausage shaped smooth, firm mass
  - Mass does not move with respiration
  - Mobile in all directions
  - Resonant
  - Mass contracts under the palpating fingers
  - Mass appears and disappears
- Empty right iliac fossa
- Features of intestinal obstruction/peritonitis—later

In the field of observation, chance favours only the prepared mind.



Fig. 23.26: A rare condition where colonic intussusception has occurred through rectum, coming out per anally. Part is already gangrenous.

Complications

- Intestinal obstruction
- Perforation
- Peritonitis

Differential Diagnosis

In children:	Acute gastroenteritis.
	Purpura with intestinal symptoms.
In adults:	Carcinoma colon.
	Mesenteric mass.

Investigations

- Barium enema shows typical *claw sign or coiled spring* sign (Pincer end).
- Ultrasound shows *target sign or pseudokidney sign or bull's eye sign, which is diagnostic*.
- *Doppler* may show mass with *doughnut sign* and is useful to check *blood supply* of bowel.
- Plain X-ray abdomen shows *multiple air fluid levels*.

Treatment

Initial management

- Ryle's tube aspiration.
- IV fluids.
- Antibiotics.
- Catheterisation.

Later management

Nonoperative management

- *Reduction by hydrostatic pressure* using either *warm saline or microbarium sulphate solution or air* (popular in ***China).*** Barium or saline is infused into the rectum through a catheter (Foley's catheter). Under fluoroscopy, reduction can be observed. Child will pass large quantity of air and faeces; distension reduces; child shows recovery and stops crying. Air or contrast enters the proximal bowel freely. *Palpable abdominal mass disappears*. Rare complication is perforation of colon. It is done in early stage within 24 hours of presentation. 70% cases of ISS will respond to nonoperative method. It is *contraindicated* in complete obstruction; perforation and peritonitis.



Fig. 23.27: Barium enema showing the typical 'Claw sign' of intussusception.



Fig. 23.28: Barium enema X-ray showing claw sign in intussusception.

Indications for surgery in ISS

- ISS more than 48 hours
- Features of perforation, strangulation, peritonitis
- Recurrent ISS
- In adult commonly resection is required

Surgery

- *Cope's method:* If reduction does not occur, *laparotomy* is done under G/A. By gently *milking out* the intussusception with warm packs, it is reduced. After reduction, viability of the bowel is checked carefully. If manual reduction is not possible, it is understood that the bowel is likely to be gangrenous which requires resection and anastomosis. In case of viable bowel, often terminal ileum is anchored to the ascending colon and *Jackson veil band is* cut. Patient also requires nasogastric tube aspiration, IV fluids, antibiotics.
- Laparoscopic approach may be used to reduce the intussusception.
- If intussusception persists for more than 48 hours or intussusception in adult requires resection.
    - Ileocolic resection is sufficient.

Recurrence Rate

- In hydrostatic reduction—10%.
- In open manual reduction—2%.
- In resection—very less < 1%.

VOLVULUS

Definition

It is the *twist (rotation)* in the axis of the loop of the bowel either clockwise or anticlockwise.

- 15% of large bowel obstruction is due to volvulus.
- Sigmoid colon is the commonest site (*anticlockwise*)—65%.
- ***Caecal volvulus***
    - Caecum is the second common site (*clockwise*) (C for C)—30%.
    - It is common in females, present as intestinal obstruction.
    - *Caecal bascule* is the presence of constricting band across the ascending colon (*Bascule*—French—see-saw and balance).
    - Caecum will be markedly distended and found in the centre of the abdomen.
    - It is due to lack of fixation of the caecum—*mobile caecum*.
    - Occasionally it is associated with malrotation.
    - Caecal volvulus is the commonest cause of large bowel obstruction in pregnancy.
    - X-ray shows *round gas shadow* in right iliac region. CT scan is very useful. Barium enema is also helpful.
    - *Resection and anastomosis (surgery*) is the only treatment.
- Volvulus of small intestine (midgut), volvulus neonatorum, gastric volvulus are other volvulus which can occur.

SIGMOID VOLVULUS (Volvulus of Pelvic Colon)

- It is common in Asia, common in India (7% of intestinal obstruction) and especially South India because of high fibre diet.
- It is very common cause of large bowel obstruction in Peru and Bolivia due to high altitude.
- More common in males and old age.
- It is common in patients with chronic constipation with laxative abuse.

It is common in:

- Ogilvie's syndrome
- Mentally retarded individuals
- Chaga's disease
- Hypothyroidism
- Anticholinergic drugs
- Multiple sclerosis
- Scleroderma
- Parkinson's disease



Fig. 23.29: Causes of sigmoid volvulus.

Predisposing factors

- Adhesions
- Peridiverticulitis
- Overloaded redundant pelvic colon
- Long pelvic mesocolon
- Narrow attachment of sigmoid mesocolon

- Always rotation is *anticlockwise.*
- It requires *one and half turn* of rotation to cause vascular obstruction and gangrene which eventually leads into perforation either at the root or at the summit of the sigmoid loop.

Nine-tenths of wisdom consist of being wise in time.

- Enormous distension of the colon occurs. Sometimes ileum comes to the root of the sigmoid volvulus and encircles it causing ***compound volvulus*** in which case knotted small bowel also becomes gangrenous—***ileosigmoid knotting.***



Fig. 23.30: Sigmoid volvulus. Note the dilated sigmoid colon.

Types

1. Acute.
2. Recurrent.

Clinical Features

- Pain in the abdomen—initially left sided, eventually all over.
- Absolute constipation *(obstipation*—no faeces, no flatus).
- Enormous distension of abdomen, starting from left iliac fossa extending to the whole of the abdomen (Tympanic abdomen).
- Late vomiting and eventually dehydration.
- Features of peritonitis.
- Hiccough and retching can occur.
- *Tyre like feel* of the abdomen is diagnostic.



Fig. 23.31: Dilated sigmoid in early volvulus.

Differential Diagnosis

- *Ogilvies's syndrome*: It is acute colonic pseudo obstruction. It is due to malfunctioning sacral parasympathetic nerves. Splenic flexure is the junction of collapsed and dilated large bowel. Descending colon is atonic causing acute functional obstruction. It may be due to trauma, retroperitoneal irritation, antidepressants, uraemia, diabetes, myxoedema, hypokalaemia, etc. Prokinetic drugs, colonoscopic decompression, tube caecostomy are the treatment.
- Faecal impaction.
- Carcinoma rectosigmoid region.
- Idiopathic megacolon.

Investigations

1. ***Plain X-ray***:(diagnostic in 70-80%)
    - Ω *sign (omega sign)*—single, grossly distended loop of colon arising out of the pelvis and extending towards the diaphragm.
    - *Coffee-bean sign* or *Bent-inner tube sign*.
2. ***Contrast enema:*** (dilute barium/water soluble contrast media is used):
   Birds beak sign (ace of spades appearance)—Upper end of barium column tapers into the spirally twisted distal sigmoid colon.
3. ***CT scan*** (for difficult cases):
   Shows characteristic whirl pattern.
4. **Blood**—Haematocrit, renal function tests, serum electrolytes.

Treatment

- RT aspiration.
- IV fluids.
- Catheterisation.
- Antibiotics.
- *A flatus tube or Sigmoidoscope* is passed in operation theatre (proper care is taken otherwise it leads to perforation). If it derotates, patient will pass flatus and faeces; and distension reduces.
- If derotation does not occur, laparotomy through midline incision should be done. Dilated sigmoid colon is derotated manually and checked for viability. If viable, it can be fixed to the lateral wall of abdomen or pelvis—***sigmoidopexy***.
- If sigmoid colon is gangrenous, it is resected and proximal cut end is brought out as colostomy and distal end is brought out as mucous fistula, from the rectum *(Paul-Mikulicz Operation*). Later after 6 weeks, continuity is maintained after proper preparation.
- Resection of the gangrenous sigmoid done; proximal cut is brought out as end colostomy: distal end closed—*Hartmann's operation*. Later in 6-12 weeks colorectal anastomosis is maintained.
- Primary resection and anastomosis is not advisable because of the contamination and anastomotic leak.

Mortality in sigmoid volvulus is due to *perforation, peritonitis and septicaemia*.



Figs 23.32A to F: Sigmoid volvulus—note distended tympanic abdomen; X-ray showing typical sigmoid volvulus; on table gangrenous sigmoid volvulus; underwent resection with colostomy and mucous fistula (exteriorisation).

A little may save a deal of friction.



Fig. 23.33: Paul-Mikulicz operation.

PARALYTIC ILEUS (Adynamic Intestinal Obstruction)

- It is a state in which intestines fail to transmit peristalsis due to failure of neuromuscular mechanism, i.e. Auerbach's and Meissner's plexus.
- It may be localised or generalised.

Causes

- Postoperative
- Infective—pus, blood, bile, toxins, enteritis
- Uraemia
- Hypokalaemia
- Spinal injury
- Retroperitoneal haemorrhage
- Spinal surgery
- Plaster jacket

Clinical Features

- No passage of flatus.
- No bowel sounds.
- Marked abdominal distension.
- Vomiting of large volume of fluid.
- Tachycardia.
- Respiratory distress due to pressure over the diaphragm.
- High pitched tinkling note '*like bells at evening pealing'*.
- Dull abdominal pain (not colicky).
- Features of fluid/protein/electrolyte imbalance.

Investigations

- Serum electrolyte estimation: Especially serum potassium.
- ECG.
- X-ray abdomen.
- Ultrasound abdomen to find out the possible cause of ileus, e.g. sepsis.

Treatment

- Nasogastric aspiration.
- The primary cause is treated.
- IV fluids.
- Electrolyte management.
- Catheterisation and urine output measurement.
- *Do not stimulate the peristalsis ("Don't flog a tired horse").*
    - **Measurement of abdominal girth** is necessary to see whether patient is recovering or not.
    - Decompression of the large bowel can be tried by inserting a flatus tube per anally into the rectum and keeping in place for few hours.
    - Most often, patient recovers in 3-6 days by conservative treatment.
    - In prolonged, life threatening paralytic ileus, laparotomy is done and bowel is decompressed with *Savage's decompressor* and closed with tension sutures.
- *Catchpole regime*: Adrenergic blocking agent along with cholinergic stimulant (neostigmine) is used rarely only in resistant cases as medical therapy.

ADHESIONS AND BANDS

Adhesions and bands are the most common causes of intestinal obstruction in Western countries. In India, hernia and then adhesions are the two common causes of intestinal obstruction.



Figs 23.34A and B: Adhesions causing intestinal obstruction.



Figs 23.35A and B: Congenital band causing intestinal obstruction. These bands are often vascular.

Causes

- Infection due to peritonitis, appendicitis, postlaparotomy, and other acute infective abdominal conditions.
- Materials used during surgery can cause dense inflammatory reactions—suture materials like silk, thread, and foreign body, mop, and gauze, talc powder, drugs like sulphonamides and penicillins.
- Ischaemia of bowel due to poor blood supply, sepsis.
- Gynaecological conditions, bowel injury, radiation-induced enteritis, Crohn's disease, other inflammatory bowel diseases.
- Specific conditions like tuberculosis, malignancy.

Note:

- It is often called as *adhesive small bowel obstruction* (ASBO). 80% cases showed earlier laparotomies; 35% multiple laparotomy. 75% of surgeries in such patients are emergency one.
- *Causes may be classified as—Congenital* adhesions; Ischaemic—Reduced blood supply of the bowel, *Traumatic*—Patients have undergone laparotomies for intraabdominal injuries; *Irritants*—Talc powder used for gloves, starch, antibiotics, nonabsorbable suture materials, gauze and cotton filaments, barium; *Inflammatory:* Appendicitis, cholecystitis, pelvic infection, Crohn's disease, tuberculosis; *Others*—Serosal denudation during surgery precipitates adhesions.
- Initial cause ischaemia/injury → inflammatory exudates → fibrinous adhesions → fibrous adhesion → fibrinolysis. Fibrinous adhesion is avascular. Often thick vascular adhesions develop. Adhesions can be localized or extensive.

Types

Type I—Fibrinous adhesions occur during 5-10th post-surgical period. It usually gets resolved completely. It is avascular and flimsy.

Type II—Fibrous adhesions. Due to lack/poor blood supply, bowel gets attached to part of peritoneum or omentum or other parts of the bowel with dense vascular adhesions to maintain blood supply. It will persist and precipitate intestinal obstruction, often-subacute and recurrent type.

Adhesions due to tuberculosis are severe, dense and difficult to separate.

Clinical features

- Pain abdomen—colicky type and recurrent and episodic
- Distension, vomiting
- Constipation
- Reduced bowel sounds on auscultation
- Previous surgical scars commonly observed
- Dehydration, tachycardia, hypotension
- Commonest symptom in adhesions is ***pain*** which is sharp, sudden, recurrent, episodic and colicky. Colicky pain is more common in midlevel obstruction. *Gilroy Bevan triad* of adhesive pain is—(1) Pain may get aggravated or relieved on change of posture. (2) Pain in the region of old abdominal scar. (3) Tenderness is elicited by pressure over the scar
- Lower adhesions will have more distension compared to proximal adhesion
- Presents with features of obstruction initially, later features of strangulation (toxicity, fever, tachycardia, guarding, rigidity, rebound tenderness)
- Adhesions may be asymptomatic for many years but later become symptomatic

Investigations



Fig. 23.36: X-ray showing intestinal obstruction with dilated colon—colonic obstruction.



Figs 23.37A and B: X-ray showing small bowel obstruction with multiple air fluid levels.

- *Plain X-ray abdomen shows dilated bowel loops.*
- *Oral contrast with CT scan is very useful.*
- *In partial obstruction only enteroclysis with water-soluble iodine dyes can be done.*

Level of obstruction should be assessed probably by X-ray and CT scan.

- CT may show radiological features of strangulation -
  - Intramesenteric fluid.
  - Mesenteric oedema, congestion.
  - Bowel wall thickening more than 2 mm.

  - Reduced mural enhancement in strangulated bowel compared to adjacent bowel.
  - Small bowel loop may go for volvulus showing *Whirl sign* in CT scan with whirlpool mesentery of that part of the bowel.
- Electrolyte estimation, total count, serum creatinine, blood grouping.

Treatment

Initial Treatment

- IV fluids.
- Nasogastric aspiration.
- Antibiotics.
- Often per anal flatus tube insertion.
- Commonly patient responds in 4-5 days of therapy.

Later Treatment

- Open surgical adhesiolysis using fingers gently.
- *Laparoscopic adhesiolysis* is becoming popular, safer, ideal with less recurrent adhesion rate and gives good results.



Fig. 23.38: Laparoscopic view of dense adhesions—postoperative cause.



Fig. 23.39: Methods used to prevent recurrent adhesions and so to reduce the chances of intestinal obstruction. *Nobles plication* is plication of intestines.



Fig. 23.40: *Childs-Phillips operation* done to prevent adhesive obstruction by plicating mesentery.

- *Noble's plication* of intestines—wherein adjacent coils of small bowel are sutured to prevent in going for further recurrent adhesions.
- *Childs-Phillips mesenteric plication* is similar way of plication of intestinal mesentery, which will prevent crumpling of bowel and adhesion formation.
- Passing long stiff tube from exterior through an opening in the proximal bowel up to the entry into the large bowel, which acts as intraluminal splinting.
  - Intestinal intubation is technically difficult with chances of perforation and fistula formation.
  - *Baker's tube* insertion through *jejunostomy* site; *Stewardson insertion of Baker tube* through nasogastric route; In *Nelson and Nyhus* method, 2nd balloon to Baker tube 25 cm proximal to the first to facilitate easier insertion of the tube—are different tubes and techniques used.



Fig. 23.41: Intestinal intubation via a jejunostomy tube used for adhesions.

- Expandable PTFE membrane barriers or hyaluronic acid and carboxymethyl cellulose membrane barriers are also used.

Prevention of adhesions

- Instilling drugs like hyaluronidase, steroids, dextrans, dextrins, polyvinyls, silicone, fibrinolysins, chondroitins, streptomycins
- Gentle handling of the bowel
- Prevention of spillage of contents like bile, faeces
- Ideal peritoneal wash using 8-10 liters of saline before closing the abdomen
- Careful placing of the drains
- *Laparoscopic procedures has got lesser chance of getting adhesions than open method*





Figs 23.42A and B



Fig. 23.42C

Figs 23.42A to C: Postoperative adhesions have become commonest cause of intestinal obstruction. Note the abdominal distension in a previous laparotomy patient and on table adhesions.

Obstruction due to Bands

- These are *dense fibrous strings* attached from one portion of the abdomen to another area or bowel causing entrapment of intestines leading into obstruction and often dangerous *strangulation.*
- Common causes are vitellointestinal duct, Ladd's band, omental band, postsurgical fibrous band, tuberculous band.
- Clinical features are like of intestinal obstruction.
- Management is release of the band either through laparoscopy or through laparotomy.

INTERNAL HERNIAS

- It is rare entity.
- A portion of small bowel gets entrapped in one of the retroperitoneal fossae or congenital internal defects (e.g. mesenteric defect).

Sites

- Mesenteric defect; defect in transverse mesocolon.
- Foramen Winslow.
- Diaphragmatic hernia.
- Hernia through duodenal/caecal/appendiceal/ intersigmoid retroperitoneal fossae.
- Hernia through broad ligament.

Mesocolic/paraduodenal hernias: They are rare congenital small bowel herniation behind the mesocolon due to midgut malrotation. It can be right or left types. In right type small bowel is right of the superior mesenteric artery (SMA is medial to neck of the sac) behind right side colonic mesentery with ileocolic, right colic, middle colic vessels in front in the sac. Left type is commonest (75%) with herniation of small bowel between inferior mesenteric vessels and attachment of descending mesocolon. Presentation is acute intestinal obstruction. Contrast CT is diagnostic. Often condition is diagnosed on table during surgery. Incising peritoneum sac adjacent to vessels carefully and adequately is the needed surgical treatment. Malrotation should be surgically corrected.

Mesenteric defect hernias (small bowel mesentery/ mesocolon) even though can occur anywhere, are common near ileocolic junction.

Acquired internal hernias occur through defects developed after surgeries like gastrojejunostomy (*Stammer's* hernia); colostomy; ileostomy; surgeries for morbid obesity.

Features

- Herniation occurs in these sites whenever there are adhesions.
- Features of intestinal obstruction—acute/subacute/recurrent.
- Diagnosis is usually on table. But enteroclysis, contrast CT scan are useful.

Treatment

- Release of adhesion, reduction of hernia, if bowel not viable resection and anastomosis.
- Often major vessels may be present adjacent to the constriction ring which may get injured while releasing causing torrential haemorrhage. Decompression is first done prior to reduction.

Chapter 24 Appendix

CHAPTER OUTLINE

- Surgical Anatomy
- Duplication of Appendix
- Acute Appendicitis
- Incidental Appendicectomy
- Appendicular Mass
- Appendicular Abscess
- Faecal Fistula after Appendicectomy
- Mucocele of Appendix
- Neoplasms of the Appendix
- Laparoscopic Appendicectomy

SURGICAL ANATOMY

It is located at the terminal end of the caecum where three taeniae join, about 2 cm below the ileocaecal orifice. Usually, around 5-10 cm in size but can be varible. Size of its lumen is that of matchstick. Diameter of appendix is 3-8 mm; diameter of lumen is 1-3 mm (matchstick).

Mesoappendix is extension of the mesentery contains appendicular artery, a branch of ileocolic artery. Often an accessory appendicular artery *(of Seshachalam*) may be present. Thrombosis of these vessels leads to gangrenous appendicitis.



Fig. 24.1: On table demonstration of mesoappendix with appendicular artery. Note the appendix (A); mesoappendix (B); caecum (C); ileum (D); taenia (E).



Fig. 24.2: Different anatomical positions of the appendix.

DUPLICATION OF APPENDIX (Wallbridge Classification) (Fig. 24.3)

Type A: Partial duplication in a single caecum.
Type B: Two separate appendices in a single caecum.
Type C: Double caecum with each one having one appendix.

- **Most common position** *is retrocaecal (75%). Next common is pelvic (21%).*

Charm strikes the sight, but merit wins the soul.

Other sites are:
- Preileal—rarest (1%)
- Postileal
- Paracaecal
- Subcaecal
- Subhepatic



Fig. 24.3: Duplication of appendix.



Fig. 24.4: Laparoscopic view of subhepatic appendix.

- Often it may be in subserosal plane leading to difficult dissection during appendicectomy.
- In *situs inversus* appendix is on *the left side.*
- Mucosa of appendix is lined by columnar cells with crypts.
- Submucosa contains numerous lymphatic aggregations (follicles*) ('abdominal Tonsil').*
- Opening of the appendix into caecum is guarded by *'valve of Geralch'*.

ACUTE APPENDICITIS

> *The partial inflammation of the peritoneum, in the liac fossa, is sometimes set up by disease in the Appendix caeci.... The appendix having been perforated by ulcerations, occasioned by the lodgement of the faecal concretions in its cavity, extravasation takes place, and inflammation of a more severe and serious kind is originated.... Nature sometimes succeeds in limiting the inflammation to a part of the right side; but it is at other times diffused over the whole abdomen ...and quickly proves fatal.*
>
> —**Thomas Hodgkin,** 1836

Aetiology

- It is common in young males.
- It is common in white races.
- Fibre rich diet prevents appendicitis. Less fibre diet increases chance of appendicitis.
- It is common in May and August—seasonal variation—often called as *epidemic appendicitis*.
- Viral infection may cause mucosal oedema and inflammation which later gets infected by bacteria causing appendicitis.
- Family history may be relevant in 30% of appendicitis in children with appendicitis occurring in first degree relatives.
- Obstruction of the lumen of appendix causing obstructive appendicitis.
  - Blockage occurs due to—faecoliths, stricture, foreign body, round worm or threadworm.
  - Adhesions and kinking—carcinoma caecum near the base, ileocaecal Crohn's disease.
- Distal colonic obstruction.
- Abuse of purgatives.
- Faecolith is the *most common* cause.

Organisms:

E. coli (85%), enterococci, (30%), streptococci, *Anaerobic streptococci, Cl. welchii,* bacteroides.

Pseudoappendicitis is appendicitis due to acute ileitis following Yersinia infection. It is often due to Crohn's disease.



Fig. 24.5: Removed appendix with its mesoappendix.



Fig. 24.6: Severely infected appendix with faecolith inside. Faecolith is one of the causes of obstructive appendicitis.

Pathogenesis

- Acute inflammation of the mucus membrane with secondary infection without obstruction causes *acute nonobstructive appendicitis*. It may lead into resolution, fibrosis, recurrent appendicitis or eventual obstructive appendicitis.

- Luminal obstruction by faecolith, lymphoid hyperplasia, pinworm (oxyuris vermicularis), other worms, foreign body, carcinoma/Crohn's disease → mucus and inflammatory fluid collects inside the lumen → increases intraluminal pressure → leads to blockage of lymphatic and venous drainage → resulting in increased oedema of mucosa and wall → causes mucosal ulceration and ischaemia → bacterial translocation → bacterial spread through submucosa and muscularis propria → *acute obstructive appendicitis* → thrombosis of appendicular artery → ischaemic necrosis of full thickness of the wall of the appendix → gangrene of the appendix → perforation at the tip or at the base → peritonitis.



Fig. 24.7: Laparotomy showing perforated appendix with peritonitis.



Fig. 24.8: Appendicolith with appendicitis.

- After perforation → localisation by greater omentum and dilated ileum occurs → with suppuration and pus inside forming *appendicular abscess*.
- In severe acute appendicitis → localisation can occur by omentum and dilated ileum without pus inside → forming *appendicular mass*.
- Acute appendicitis with blockage at the opening of the lumen → inflammation rarely subsides → mucus collects inside the lumen of the appendix resulting in its enlargement → *Mucocele of the appendix*.

Types

1. ***Acute nonobstructive appendicitis (catarrhal):***
   Inflammation of mucous membrane occurs with redness, oedema and haemorrhages which may go for following courses:
   - Resolution.
   - Ulceration.
   - Fibrosis.
   - Suppuration.
   - Recurrent appendicitis.
   - Gangrene—rare initially in nonobstructive type but later can occur.
   - Peritonitis.



Figs 24.9A and B: Gangrenous obstructive appendicitis—on table.

Appendices epiploicae are absent in rectum, appendix and caecum.

2. ***Acute obstructive appendicitis*****:** Here pus collects in the blocked lumen of appendix which is blackish, gangrenous, oedematous and rapidly progresses leading to perforation either at the tip or at the base of appendix. This leads to peritonitis, formation of appendicular abscess or pelvic abscess. Most often, there will be thrombosis of the appendicular artery.
3. ***Recurrent appendicitis:*** Repeated attacks of nonobstructive appendicitis leads to fibrosis, adhesions causing recurrent appendicitis.
4. ***Subacute appendicitis*** is milder form of acute appendicitis.
5. ***Stump appendicitis*** is retained long stump of appendix after commonly laparoscopic appendicitomy.

Clinical Features


Umbilicus
Spino-umbilical line
McBurney's point
Anterosuperior iliac spine
2/3
1/3
McBurney's incision (Gridiron/McArthur)

Fig. 24.10: *McBurney's point* is junction of lateral 1/3rd and medial 2/3rd of spinoumbilical line. McBurney's/Gridiron's/McArthur's incision is perpendicular to this line in this point.

- It is rare before the age of two, common in children and other age groups.
- *Pain*: It is the earliest symptom. Visceral pain starts around the umbilicus due to distension of appendix, later after few hours, somatic pain occurs in right iliac fossa due to irritation of parietal peritoneum due to inflamed appendix. Pain eventually becomes severe and diffuse which signifies spread of infection into the general peritoneal cavity.
- *Vomiting:* Due to reflex pylorospasm.

Murphy's triad

- Pain
- Vomiting
- Temperature

- *Constipation* is the usual feature *but diarrhoea* can occur if appendix is in postileal or pelvic positions.
- *Fever, tachycardia, foetor oris* are other features.
- *Urinary frequency:* Inflamed appendix may come in contact with bladder and can cause bladder irritation.
- Tenderness and rebound tenderness at *McBurney's point* in right iliac fossa *(release sign—Blumberg's sign)* are typical.
- *Rovsing's sign:* On pressing left iliac fossa, pain occurs in right iliac fossa which is due to shift of bowel loops which irritates the parietal peritoneum.
- Hyperextension (in case of retrocaecal appendix—*Cope's psoas test*) or internal rotation (in case of pelvic appendix—*obturator test*) of right hip causes pain in right iliac fossa due to irritation of psoas muscle and obturator internus muscle respectively.
- *Baldwing's test* is positive in retrocaecal appendix—when legs are lifted off the bed with knee extended, the patient complains of pain while pressing over the flanks.
- P/R examination shows tenderness in right side of the rectum.
- Hyperaesthesia in *'Sherren's triangle'*. This triangle is formed by anterosuperior iliac spine, umbilicus, pubic symphysis.



Fig. 24.11: *Sherren's triangle*. It is area of hyperaesthesia found in acute appendicitis between anterosuperior iliac spine; umbilicus and pubic symphysis.

Often infection gets localised by omentum, dilated ileum and parietal peritoneum leading to *appendicular mass.* Often suppuration occurs in the localised area resulting in *appendicular abscess.*

Clinical signs in appendicitis

- Rovsing's sign
- Blumberg's sign (Release sign)
- Cope's psoas test
- Obturator test
- Baldwing's test
- Bastede sign
- *Dumphy's* cough tenderness sign
  (Refer fascinating signs for detail)
- Bapat bed shaking test
- Heel Drop test

- ***Acute appendicitis in infancy:***
  - Eventhough it is rare, when it occurs, it has got 80% chances of perforation with high mortality (50%).
- ***Acute appendicitis in children:***
  - Here localisation is not present, and so peritonitis occurs early.
  - It *requires early surgery.* Dehydration, septicaemia are common.
- ***In elderly:***
  - Gangrene and perforation are common. Because of lax abdominal wall, localisation is poor and so peritonitis sets in early.

- ***In pregnancy:***
  - *Incidence* is 1 in 2,000 pregnancies. It is more common in 1st and 2nd trimesters.
  - Appendix shifts to upper abdomen. So pain is higher and more lateral.
  - Rebound tenderness and guarding *may not* be evident.
  - TC will be very high with neutrophilia.
  - Risk of *premature labour* is 15%.
  - *Foetal death* in early appendicitis is 5% but becomes 29% once appendix perforates in pregnancy.
  - After 6 months, maternal mortality increases by 10 times than usual and also leads to premature labour.
  - Appendicitis is the most common non-gynaecologic surgical emergency during pregnancy.
  - Incidence of perforation is highest in 3rd trimester.
  - Surgery is the treatment.

Differential Diagnosis for Acute Appendicitis

Many conditions mimic acute appendicitis. It differs in children, adult, elderly and females.

- *Perforated duodenal ulcer*: In duodenal ulcer perforation, fluid trickles down along right paracolic gutter and mimics appendicitis. Upper abdominal pain, obliterated liver dullness, gas under diaphragm in X-ray and CT scan differentiate it from acute appendicitis.
- *Acute cholecystitis*: Pain in right upper abdomen, fever, jaundice, upper abdominal guarding are the features of acute cholecystitis. US; HIDA scan, LFT will differentiate it from acute appendicitis.
- *Acute pancreatitis*: Pain in epigastrium, radiating to back, raised serum amylase and lipase, CT abdomen with a history of alcohol intake often are diagnostic.
- *Right ureteric colic*: Pain is colicky in nature which often refers to genitalia. Haematuria, urinary symptoms are common. It mimics retrocaecal/pelvic acute appendicitis. Often in ureteric stone, abdomen is soft and nontender. CT is the important way to differentiate.
- *Acute typhlitis*: Inflammation of caecum is called as typhlitis. Often it is difficult to differentiate it from acute appendicitis. Intravenous/oral metronidazole completely controls the disease.
- *Acute bacterial enterocolitis*: It presents with pain abdomen, diarrhoea, toxaemia, dehydration. Often it is difficult to differentiate from acute appendicitis.
- *Acute mesenteric lymphadenitis* is difficult to differentiate from acute appendicitis. It is treated conservatively. CT may be helpful to identify it. Laparoscopic evaluation is ideal.
- *Right sided acute pyelonephritis*: Here there will be pain and tenderness in loin. Urine analysis, US are diagnostic. Often DTPA scan may be needed.
- *Crohn's disease* presenting with acute symptoms will have similar features of acute appendicitis.
- *Pelvic inflammatory disease* like salpingo-oophoritis mimics acute appendicitis. Twisted/haemorrhagic/ruptured ovarian cyst/ruptured ectopic gestation/endometriosis/tubo-ovarian abscess mimics acute appendicitis. US, laparoscopy helps to differentiate it from others. *Mittelschmerz* is lower abdominal pain due to rupture of follicular cyst during midcycle. It subsides on its own. There are no systemic features.
- *Meckel's diverticulitis* presents clinically like acute appendicitis. It is not possible to differentiate between two clinically.
- *Intussusception* mimics acute appendicitis in children. ISS is common before the age of 2 years. Acute appendicitis is rare before the age of 2 years. Palpable mass, features of intestinal obstruction, barium enema X-ray, US are useful methods to differentiate.
- *Worm infestation (round worm bolus/ball):* It often presents as pain in right iliac fossa. Features of intestinal obstruction are common here.
- *Right-sided lobar pneumonia* and pleurisy are often not easy to differentiate from acute appendicitis. Pleural rub, change in breath sounds, chest X-ray can identify pneumonia.
- *Testicular torsion/acute severe orchitis* often look like acute appendicitis. Referred pain in iliac fossa, and if scrotum is not palpated clinically these conditions are mistaken for acute appendicitis. These problems are much more obvious if *testis is undescended* one.
- *Sigmoid diverticulitis* in elderly with loop lying towards right side may present as pain in the right iliac fossa.
- *Carcinoma caecum* may present with features of acute appendicitis without any earlier typical features.
- *Ruptured aortic aneurysm*, *acute intestinal obstruction, mesenteric ischaemia* may present like acute appendicitis.
- Rare conditions like preherpetic pain of the right 10th and 11th dorsal nerves may mimic acute appendicitis. Guarding and rigidity will not be present. There will be significant hyperaesthesia.
- Tabetic crisis, tuberculosis of spine, secondaries in spine, multiple myeloma, osteoporotic pain often can mimic acute appendicitis.
- Acute crisis of porphyria and diabetes mellitus mimic acute appendicitis with severe abdominal pain.

Differential diagnosis

- Perforated peptic ulcer
- Ruptured or twisted ovarian cyst
- Acute cholecystitis
- Right ureteric colic
- Enterocolitis
- Right acute pyelonephritis
- Mesenteric lymphadenitis
- Lobar pneumonia
- Crohn's disease
- Acute pancreatitis
- Meckel's diverticulitis
- Acute crisis of porphyria
- Salpingitis
- Diabetic abdomen
- Ectopic gestation—ruptured
- Typhlitis

Perforated appendix rarely causes pneumoperitoneum.

Differential diagnosis in children

- Meckel's diverticulitis
- Acute colitis
- Acute iliac lymphadenitis
- Intussusception
- Roundworm colic
- Lobar pneumonia

Differential diagnosis in females

- Ruptured ectopic gestation
- Mittelschmerz rupture of ovarian follicle during mid-menstrual period
- Ovarian cyst torsion
- Salpingo-oophoritis

Differential diagnosis in elderly

- Acute diverticulitis
- Carcinoma caecum—acute features
- Mesenteric ischaemia
- Intestinal obstruction
- Aortic aneurysm leak
- Crohn's disease

Sequelae of acute appendicitis

- Resorption
- Relapse and recurrent appendicitis
- Appendicular mass
- Appendicular abscess
- Perforation—has got 20% mortality
- Peritonitis, septicaemia
- Portal pyaemia
- *Intestinal obstruction* due to obstructive ileus, inflammatory adhesion, formation of band between appendix and omentum or between appendix and small bowel

Investigations



Fig. 24.12: Radio-opaque appendix in a plain X-ray. It could be calcified or have calcified content.

- Total leucocyte count is increased.
- *Ultrasound* is done to rule out other conditions like ureteric stone, pancreatitis, ovarian cyst, ectopic pregnancy and also to confirm appendicular mass or abscess.
- Laparoscopy is the most useful method.

Sonographic criterias for appendicitis (85% Specificity)

- Noncompressible appendix of size > 6 mm AP diameter, hyperechoic thickened appendix wall > 2 mm—*target sign*.
- Appendicolith.
- Interruption of submucosal continuity.
- Periappendicular fluid.



Figs 24.13A and B: US showing dilated noncompressible appendix in two different patients.

- *Contrast CT scan* is very much useful when diagnosis is difficult especially in old people. Dilated appendix; dilated lumen; thickened wall; nonfilling of the lumen by contrast or air; periappendicular fluid collection; presence of mass/abscess/associated pathology like carcinoma can be identified. It has 95% sensitivity and specificity with 95% accuracy. *Dirty fat thickened mesoappendix*, appendicular *phlegmon*, appendicular *faecolith* and thickened caecum funneling contrast into the orifice of the appendix as *arrowhead sign*—are all relevant features in CT scan.
- *C-reactive protein,* even though nonspecific increases in acute phase. *99mTc HMPAO labeled leukocyte* imaging may give guidance in deciding the management.

- *Plain X-ray may show* lumbar scoliosis towards right due to psoas spasm which is not uncommon; faecolith on the right side; obliteration of preperitoneal fat line due to retrocaecal appendicitis; segmental ileus in caecum and terminal ileum; speckled extraluminal gas in right iliac fossa, gas in appendix, pneumoperitoneum (very rare); intestinal obstruction (occasionally only); soft tissue mass in mass or abscess of appendix—all these features are very much nonspecific. X-ray is useful to rule out DU perforation, intestinal obstruction, ureteric stone.

Different Scoring Systems Used

Alvarado scoring for appendicitis (1986):	*Score*
Migrating pain	1
Anorexia	1
Nausea and vomiting	1
Tenderness in right iliac fossa	2
Rebound tenderness	1
Elevated temperature	1
Leucocytosis with count more than 10,000	2
Shift to left with neutrophilia in peripheral smear	1
Total score	**10**
Score less than 5: Not sure.	
Score between 5-6: Compatible.	
Score between 6-9: Probable.	
Score more than 9: Confirmed.	

- *Kalam modified* Alvarado scoring system (1994) where shift to left is removed.
- *Tzanakis scoring system* 2005—lower abdominal tenderness—4; rebound tenderness—3; total count > 12,000/cm—2; USG features—6.
- *RIPASA scoring system* (2010)—with 15 parameters.
- *Anderson scoring system*—8 parameters.

Treatment

Surgery-Appendicectomy:

Approaches

1. ***Gridiron incision***: Incision is placed perpendicular to the right spinoumbilical line at the McBurney's point (i.e. at the junction of lateral one-third and medial two-third of spinoumbilical line). (Gridiron is a frame of cross beams to support a ship during repairs. This incision was first described by *McArthur*).
2. ***Rutherford Morison's muscle*** cutting incision *(Muscles are cut upwards and laterally*).
3. ***Lanz crease incision*** centering at McBurney's point—cosmetically better.
4. ***Right lower paramedian incision/lower midline incision***—when in doubt or when there is diffuse peritonitis.
5. ***Laparoscopic approach:*** Becoming popular and better.
6. ***Fowler-Weir approach*** by cutting muscle medially over the rectus.



Fig. 24.14: Approaches for appendicectomy.



Fig. 24.15: Appendix, on table during appendicectomy.

Procedure

- Under general anaesthesia, skin is incised. Two layers of superficial fascia are cut. External oblique aponeurosis is opened in the line of incision. Internal oblique and transverse muscles are split in the line of fibres. Peritoneum is opened in the line of incision. Caecum is identified by taeniae, and ileocaecal junction. Omentum when adherent is separated. Appendix is held with Babcock's forceps. Mesoappendix with appendicular artery is ligated. Using thread or silk, a purse—string suture is placed around the base of the appendix. Base of the appendix is crushed with artery forceps and transfixed using vicryl (absorbable). Appendix is cut distal to the suture ligature and removed. Stump is cleaned with antiseptics. Purse string suture is tightened so as to bury the stump.

Poverty knows how extremely expensive it is to be poor.



Figs 24.16A and B: Burst appendicitis showing pus. Tip of appendix is burst causing collection of pus adjacent. Usually proximal site of appendix just distal to the site obstruction will burst.

- In difficult cases—*Retrograde appendicectomy* can be done. In presence of pus or burst appendix, the peritoneal cavity is drained.
- Postoperatively, IV fluids, antibiotics are given. Once bowel sounds are heard, oral diet is started.

Complications after appendicectomy

- Paralytic ileus
- Reactionary haemorrhage due to slipping of ligature of the appendicular artery
- Residual abscess (pelvic, paracolic, local, subdiaphragmatic)
- Pylephlebitis (Portal pyaemia)
- Adhesions, kinking and intestinal obstruction
- Right inguinal hernia *(direct)*—due to injury to ilioinguinal nerve
- Wound sepsis 10%
- Faecal fistula
- Respiratory problems and DVT



Fig. 24.18: Gangrenous appendix. It is gently ligated at the base using 2 zero vicryl. It is not buried as stump will be friable (Burying is not necessary to any appendicectomy).



Fig. 24.17: Steps in open appendicectomy. Note the base of appendix, mesoappendix; its ligation; transfixation of the base using 2 zero vicryl; cutting of appendix and closure of the wound. Burying is not essential; it is optional. Burying is done using silk/vicryl using purse string suture.



Fig. 24.19: Transfixation of the base of appendix using 2 zero vicryl is an important step after secured ligation of appendicular artery.

Portal pyaemia

- It is rare nowadays
- It is septic portal system thrombosis
- Commonly seen in immunosuppressed individuals
- Infection spreads to liver through portal vein causing rapid multiplication of virulent organisms leading into septicaemia (toxaemia with hypotension, tachycardia), jaundice, tender palpable liver. Patient will be drowsy
- Treatment—antibiotics like cefoperazone, amikacin, metronidazole, meropenem; fluid management; ventilator support
- It carries poor prognosis



Fig. 24.20: Faecal fistula after appendicectomy. Most of the time faecal fistula subsides by conservative treatment unless there is distal obstruction or specific causes like Crohn's, tuberculosis or malignancy.



Fig. 24.21: Wound infection after appendicectomy in patient with burst appendicitis.

Troubles in Appendicectomy

- During surgery if appendix is found normal, other cause for symptoms should always be looked for like Meckel's diverticulum, Crohn's disease, ovarian/pelvic causes in females, malignancy, etc.
- Appendicular tumour may be found. If it is in the tip, appendicectomy is sufficient. It could be carcinoid tumour. If it is in the base right hemicolectomy is done.
- Absence of appendix—a rare occasion can occur. Caecum and taeniae should be traced properly before finalising it.
- Appendicular abscess/pelvic abscess formation.
- Malignancy in the caecum is identified on table—right hemicolectomy should be done.
- If Crohn's disease is identified during surgery, appendicectomy can be done with care, if base of the appendix is normal. But in rare occasion where appendix is involved by Crohn's disease, appendicectomy should not be done but treated only with antibiotics and steroids, otherwise fistula can develop.

INCIDENTAL APPENDICECTOMY

- Here removal of normal appendix is done at laparotomy for other conditions, e.g. hysterectomy.
- It is done in vague lower abdominal pain of doubtful severity.
- It is a useful procedure to tackle *'Munchausen syndrome,* i.e. the patient is always worried of pain abdomen and gets relieved after the procedure (psychological benefit).
- It is done along with Ladd's procedure for malrotation.
- It is also done during on table colonic lavage *(Doodleys lavage).*
- It is not done in Crohn's disease (during acute phase of appendicitis), postradiation, immunosuppression, aortoiliac grafts.

Those who can't hear the music think the dancer's mad.

Remember

- Appendicitis is common in white races, young males and in those who are on westernised diet
- It most commonly affects individuals of age group 10-20 years. 2/3rd will develop perforation due to rapid progression and poor localisation
- Gangrene, perforation and peritonitis are rare in nonobstructive type; but recurrent appendicitis of nonobstructive origin can cause perforation
- Pneumoperitoneum is not common in appendicular perforation
- Appendicular artery which is an end artery can undergo infective thrombosis and can cause gangrene and perforation
- In retrocaecal appendicitis rigidity is not common; psoas spasm is known to occur
- Pelvic and post-ileal appendicitis can cause diarrhoea. Post ileal appendicitis is difficult to diagnose
- It is difficult to remove subhepatic appendix through McBurney's incision
- Pain will be above and lateral in appendicitis in pregnant women. Appendicitis is the most common acute abdominal condition in pregnancy (1:1500 pregnancies). Incidence of foetal loss is 5% without perforation and it becomes 20% if there is perforation. It is better to do laparotomy to remove the appendix in pregnancy
- In elderly atypical features are more common and so diagnosis is often missed. Gangrene and perforation are common in elderly. Often it mimics subacute obstruction
- In obese patients diagnosis is often difficult
- Appendicitis is rare before 2 years. But when it occurs perforation and peritonitis are common carrying poor prognosis
- *Negative appendicectomy*—incidence is 30%
- *Reginald Fitz of Boston* coined the term appendicitis. *McBurney* described clinical features; *Claudius Amyand* (1736) did first appendicectomy
- Appendix is found on the *left side in situs inversus* patient. Situs inversus may be *both thoracic and abdominal or only abdominal*
- Acute pancreatitis (straw/haemorrhagic chicken broth fluid), DU perforation (bile fluid), perforated Meckel's diverticulum, twisted ovarian cyst/ectopic pregnancy (bloody fluid) are *important life-threatening conditions* which may be missed for appendicitis and patient might undergo appendicectomy as a wrong procedure in these patients
- ***Simple appendicitis*** is one where the symptoms are of less than 48 hours duration with imaging studies showing appendicitis without abscess or phlegmon
- ***Chronic appendicitis'*** earlier this term was not used, but is presently accepted terminology; few attacks of recurrent appendicitis will lead into chronic appendicitis. It presents with episodic often vague discomfort with colicky pain in RIF, anorexia, malaise, pain with movement and is often called as *grumbling appendicitis*. TC, US, CT scan may be normal in these patients
- *Perforation rate* in appendicitis is 25% in general; in children and elderly it becomes 45-50%. *High fever* more than 102˚F, *TC* > 18,000/- are suspected features of rupture
- *Mortality rate of appendicectomy* is less than 1%. Morbidity and complications are more after surgery for perforated appendicitis
- *Surgical site infection* is 5% in uncomplicated appendicitis; 20% in perforated appendix after surgery
- *Small bowel obstruction* postoperatively is 1% with simple appendicitis; 3-5% in perforated appendicitis after surgery. More than 50% of obstruction occurs in first year of postoperative period
- In children with appendicitis, there is poor localisation and so peritonitis is common. So conservative therapy should be avoided. Surgery is the only choice of treatment otherwise early peritonitis is the danger.
- Appendicular mass is initially treated with *Ochsner Sherren* regime. After 6 weeks, *interval appendicectomy* is done.
- Children, old age, faecolith, laxative abuse, diabetes mellitus, immunosuppression and pelvic appendix are high-risk factors for perforation in appendicitis
- In pelvic and retrocaecal appendicitis, adjacent ureteral inflammation can occur in which urine on analysis shows blood cells and pus cells
- Incidence of removal of normal appendix is 30%
- *Stump appendicitis* is inflammation and infection in the remaining portion of the appendix in the stump after appendicectomy. It is a rare entity
- On table during surgery, normal appendix if found, it is called as '*Lily white appendix*'. Then other pathology like Meckel's, ileal/mesenteric lymph node/ovarian disease has to be looked for

APPENDICULAR MASS (Periappendicular Phlegmon)

- It is the localisation of infection occurring 3 to 5 days after an attack of acute appendicitis.



Fig. 24.22: Appendicular mass—a well localised one.

- Inflamed appendix, greater omentum, oedematous caecum, parietal peritoneum and dilated ileum (Ileus) forms a mass in the right iliac fossa.
- This mass is tender, smooth, firm, well localised, not moving with respiration, not mobile, all borders well made

out (well localised) and resonant on percussion. Patient may have fever and features of toxicity.



Fig. 24.23: Appendicular mass is formed by dilated ileum; greater omentum; inflamed appendix and caecum. It is resonant, smooth, firm, and tender with well defined borders which does not move with respiration and does not have mobility.

Differential diagnosis

- Carcinoma caecum
- Crohn's disease
- Ovarian disease
- Twisted ovarian cyst
- Actinomycosis
- Mesenteric lymphadenitis
- Ruptured ectopic pregnancy
- Ileocaecal tuberculosis

Investigations

- TC is increased.
- U/S confirms the mass.

Treatment

Conservative ***(Ochsner-Sherren Regimen***), as nature has already localised the infection, if now disturbed will cause faecal fistula.

Includes observation:

- Temp, BP, pulse chart.
- *Marking the mass to identify the progression/regression.*
- Antibiotics (Ampicillin, metronidazole, gentamicin, or other drugs given depending on severity and requirement).
- IV fluids.
- Analgesics.
- Initial nasogastric aspiration.
  - Patient usually shows response by 48 to 72 hours and mass reduces in size, temperature and pulse becomes normal. Appetite is regained. 90% of patients respond to conservative therapy.
  - Patient is discharged and advised to come *for* ***interval appendicectomy*** after 6 weeks.

Contraindications for Ochsner-Sherren regimen

1. When diagnosis is in doubt.
2. In acute appendicitis in children and elderly.
3. In burst, gangrenous appendicitis.
4. In patients in whom diffuse peritonitis sets in.

Criteria to discontinue *Ochsner-Sherren* regimen

- Patient becomes more toxic (tachycardia, high fever)
- Persistent vomiting
- Increase or spread of pain abdomen (means onset of diffuse peritonitis)
- Increased size of the mass
- Suppuration (abscess formation) in the mass

In these patients the regimen is discontinued. The patient is taken for immediate surgery, either through laparotomy or through classic approaches

APPENDICULAR ABSCESS

- It occurs due to suppuration in an acute appendicitis or suppuration in an already formed appendicular mass.
- Abscess commonly *occurs in retrocaecal* region but often can occur in subcaecal, preileal lumbar or postileal regions.
- *Pelvic abscess is also common after an attack of acute appendicitis*.



Fig. 24.24: Appendicular abscess. Swelling with ill-defined lower border.

Clinical Features

- High fever, features of toxicity, tender, smooth, dull (to percuss), soft swelling in right iliac fossa which lies towards right lateral and lower side with clear upper margin but indistinct lower margin**.**
- U/S confirms the diagnosis.

Treatment

- Antibiotics are started.
- Under G/A, incision is made in the lower lateral aspect of the swelling above the inguinal ligament. Skin, external oblique muscle is cut. Abscess cavity is opened and pus is drained *extraperitoneally*, which is sent for culture and sensitivity. Wound is closed. A drain is placed through a separate incision. Antibiotics are continued.

An essential aspect of creativity is not being afraid to fail.



Fig. 24.25: Different sites where abscess can occur after appendicitis retrocaecal, appendicular; pelvic; subphrenic; preileal and lumbar. Portal pyaemia can occur with multiple pyaemic abscesses in the liver.

- *Interval appendicectomy is done after 3 months.*

Pelvic abscess is drained per-rectally or through posterior colpotomy (in females).

FAECAL FISTULA AFTER APPENDICECTOMY

Causes

- It can occur when appendicectomy is done in gangrenous/perforated/friable base appendix.
- It can occur after drainage of appendicular abscess.
- It can occur if appendicectomy is done/attempted in appendicular mass.
- If there is underlying additional pathology like Crohn's disease/carcinoma/ileocaecal tuberculosis/actinomycosis during appendicectomy, fistula can occur.

Features

- Faeculent, foul smelling discharge from either main wound or drain site.
- Features of infection.
- Skin excoriation.
- Features suggestive of cause.



Fig. 24.26: After appendicectomy fistula can occur. Note the faecal discharge.

Investigations

- CT fistulogram to delineate the track.
- CT scan abdomen to find out the other pathology.
- Other relevant investigations, Hb%, albumin level, etc.

Treatment

- Conservative—antibiotics, IV fluids, dressing, zinc oxide cream over the skin, observation.
- Most of the time fistula subsides provided there is no distal obstruction by adhesions or kinking or specific causes like carcinoma or tuberculosis.
- If persists even after 6 weeks, resection of ileocaecal segment and anastomosis is done.

MUCOCELE OF APPENDIX

- It can be neoplastic or non-neoplastic.
- It occurs when proximal end of the lumen of appendix gets slowly and completely occluded, usually by a fibrous stricture causing collection of sterile fluid (mucus) in the lumen. It is a retention cyst.
- Appendix is grossly enlarged with features of sub-acute appendicitis.
- Mucocele can get infected leading to *empyema* of appendix.
- Rupture of mucocele can lead to *pseudomyxoma peritonei*. Neoplastic type causes generalised pseudomyxoma peritonei; non-neoplastic type causes localised pseudomyxoma peritonei.
  (Other cause for pseudomyxoma peritonei is ruptured mucinous carcinoma of ovary).
- Often mucocele of appendix is also caused by a mucus secreting adenocarcinoma and if it is so right hemicolectomy is done.

Clinical Features

- Colicky pain in right iliac fossa.
- Tenderness in the right iliac fossa.

Investigations

- U/S abdomen.

Pseudomyxoma peritonei

- Jelly like mucoid yellowish-brown substance accumulates in peritoneal cavity
- Due to ruptured adenocarcinoma appendix/mucocele or mucinous carcinoma of ovary
- Common in females
- Painless progressive distension of abdomen with intestinal obstruction occurs eventually
- Shifting dullness is absent
- Surgical debulking, oophorectomy, appendicectomy, omentectomy are often done
- Chemotherapy is useful—cisplatin
- Carries poor prognosis

Treatment

- Appendicectomy.

Note:
Pseudomyxoma peritonei is presently considered to be due to neoplastic adenocarcinoma of appendix with gelatinous fluid collection in the peritoneal cavity. It is also seen in cystadenocarcinoma of ovary. Treatment is surgery and chemotherapy.

NEOPLASMS OF THE APPENDIX

- It is rare.
- It is often postappendicectomy histological diagnosis.
- ***Cystic neoplasms of appendix***: Simple cyst (non-neoplastic mucocele); mucinous cystadenoma; mucinous cystadenocarcinoma (most common form of cystic neoplasms); pseudomyxoma peritonei. Simple cyst is non-neoplastic obstruction of the lumen and is less than 2 cm in size which contains mucin. Mucinous cystadenoma attains progressively large size of up to 8 cm with CT showing calcification of the wall. Laparoscopic appendicectomy is not used in mucinous cystadenoma. Hemicolectomy is done in mucinous cystadenocarcinoma and cystadenoma of large size and if base is involved.
- ***Carcinoid tumour*** is the most common type. It is less aggressive. It is often incidentally found. It is arising from Kulchitsky cells in crypts of Lieberkuhn (argentaffin tissue). It is ten times more common than other types (One in 400 appendices). Commonly its location is in the tip. 75% are less than 1 cm; 15% are 1-2 cm; 10% are > 2 cm in size. It stains chromograninB immunohistochemically. Distant and nodal spread occurs if tumour is more than 2 cm. Carcinoid of appendix may be goblet cell type or classical type histologically. Goblet cell has got more mortality than classic type. Treatment is appendicec-tomy. Right hemicolectomy is done if base is involved or size is more than 2 cm or nodes are involved. 5-year survival is 90%.
- ***Primary adenocarcinoma of the appendix*** is rare. It can be mucinous (common) or colonic (less common) type. Acute presentation as appendicitis is common in colonic type. It is staged as Duke's staging A, B, C and D. 5-year survival rate for each is 100%; 65%; 50% and 5% respectively. Mucinous type has got better prognosis. 5-year survival for mucinous type is 70% and colonic type is 40%. Mucinous type can rupture into the peritoneal cavity and can cause pseudomyxoma peritonei.

Tumours of the appendix

- Carcinoid tumour—most common site is appendix
- Primary adenocarcinoma of appendix
- Mucocele of appendix leading into pseudomyxoma peritonei



Figs 24.27A and B: Carcinoid tumour in two different patients. If it is in the tip or away from the base, then appendicectomy is sufficient. If it is in the base or extending into the caecum then right hemicolectomy is needed.

LAPAROSCOPIC APPENDICECTOMY

This is newer, popular and ideal method of appendicectomy. *It has become gold standard method of treatment*.

Advantages

- Diagnosis is confirmed.
- Other parts of the abdomen are visualised.
- In females pelvic structures are assessed properly.
- Trauma of access is less.
- Faster recovery.
- Laparoscopic appendicectomy is definitely better whenever there is vague abdominal pain; atypical pain; situs inversus; in women; subhepatic appendix and as interval appendicectomy.

Art is long, life short, judgement difficult, opportunity transient.

Disadvantages

- Technical difficulties especially in burst appendix.
- Cost factor and availability.

Note:

Consent for conversion should be taken.

Technique

- Procedure is done under general anaesthesia. Head down position with right tilt is needed. Surgeon and camera man stands on the left side. Scrub nurse on the right side. Monitor is kept on the foot end right side.
- 10 mm camera port is placed at the umbilicus. Working ports are two 5 mm, one on each side of lower abdomen or one on left side and another on the lower midline. One of the working ports can be 10 mm in difficult appendectomies.



Fig. 24.28: Different possible port placements for appendicectomy.

- Pneumoperitoneum is created using CO_2.
- Appendix is held with grasper or *Babcock's forceps*. Mesoappendix is cauterised by bipolar or unipolar cautery.
- Appendix is dissected up to the base of the appendix.
- Base of the appendix is ligated with loop ligature. Intracorporeal ligature also can be placed using vicryl 2 zero suture material. Appendix is removed through 10 mm working port along with reducer. Often retrieval bag can be used to remove the appendix.
- Umbilical port is closed in two layers. Other ports are closed by skin sutures. If gangrenous or burst appendix drain can be placed through one of the ports.
- Oral food is started in 12 hours.

Laparoscopic assisted appendicectomy can be done if caecum is mobile without much adhesions and mobilised appendix can be delivered through the 10 mm umbilical port. As in regular laparoscopic procedure, appendix is identified and mobilised. Appendix which is not friable and not turgid can be delivered through umbilical port gently. During this procedure gas flow should be stopped so that all gas in the cavity will be empty. Mesoappendix is ligated. Appendix is transfixed like in open method and removed. Stump is pushed back into the place. Telescope is passed again to confirm the position and security of the stump. Advantage is that it is faster.



Figs 24.29A and B: Laparoscopic appendicectomy. Note the mesoappendix is being cauterised. Ligation of the appendix is done using vicryl (*Courtesy:* Dr Keshava Prasad, MS, KMC, Mangalore).



Fig. 24.30: Laparoscopic assisted appendicectomy.

Complications

- Injury to bowel, vessels while passing the ports.
- Complications of pneumoperitoneum.
- Accidental cautery injury to bowel, vessels and other vital structures.
- Bleeding.
- Bowel perforation, peritonitis.
- Ligature slipping, leak, peritonitis, fistula formation.

Chapter 25 Rectum and Anal Canal

CHAPTER OUTLINE

- Anatomy
- Per-rectal Examination
- Proctoscopy (Kelly's)
- Sigmoidoscopy
- Colonoscopy
- Carcinoma Rectum
- Solitary Ulcer Syndrome
- Rectal Prolapse
- Anorectal Malformations
- Pilonidal Sinus
- Piles/Haemorrhoids
  - External Piles
- Anal Fissure
  - Sentinel Pile
- Anorectal Abscess
- Fistula-In-Ano
- Anorectal Strictures
- Condyloma Acuminata
- Anal Intraepithelial Neoplasia
- Malignant Tumours of Anal Area
- Anal Margin Tumours
- Sacrococcygeal Teratoma
- Anal Incontinence
- Descending Perineal Syndrome
- Proctitis
- Proctalgia Fugax
- Hidradenitis Suppurativa of Anal Region
- Pruritus Ani
- Gastrointestinal Haemorrhage
  - Upper GI Bleed
  - Lower GI Bleed
  - Obscure GI Bleed

ANATOMY

Rectum

- It is the distal portion of the large gut, placed between the sigmoid colon above and anal canal below; in front of last three pieces of sacrum and coccyx (From S3).
- The three cardinal features of large intestine (sacculation, appendices epiploicae and taeniae) are absent.
- The upper third of rectum is covered by peritoneum on front and sides, mid third only on the front, lower third is infraperitoneal.
- The rectum is pulled forward by the puborectalis muscle forming the anorectal sling which is primarily responsible for rectal continence.
- It has got three lateral flexions left, right and left from below upwards (*Valves of Houston*).

Rectosigmoid Junction

- Implies a segment of bowel comprising the last seven centimetre of sigmoid colon and upper five centimetre of rectum.
- On sigmoidoscopic examination it is taken as a point 15 cm from the anal verge.

Supports of Rectum

- Pelvic floor.
- *Fascia of Waldeyer*: It is the condensation of pelvic fascia behind rectum, contains superior rectal vessels and lymphatics.
- *Lateral ligaments of rectum*: It is the condensation of pelvic fascia, attaches rectum to the posterolateral wall of lesser pelvis.
- *Denonvillier's fascia:* It is the fascial condensation which separates rectum from prostate in males and vagina in females.
  - Rectum is supplied by rich network of vessels that originates from superior and middle rectal arteries and median sacral artery.
  - Lymphatic drainage from upper half of rectum is to inferior mesenteric nodes; from lower half to internal iliac nodes.


Anorectal junction
Upper part—15 mm
Anal column
Anal valve
Pectinate line
Pectin
Middle part—15 mm
White line of Hilton
Lower part—8 mm

Fig. 25.1: Interior of the anal canal.


Circular muscle
Puborectalis
Longitudinal muscle
External sphincter
Fibroelastic septa
Skin

Fig. 25.2: Sphincters of anal canal.

It is innervated by autonomic nervous system; sympathetic (L_1, L_2) is motor to sphincter and inhibitory to musculature; parasympathetic (S_{234}) is motor to musculature and inhibitory to sphincter. Sensation of distension is carried through parasympathetic; pain sensation is carried by both.

Anal Canal

- It is 4 cm long, extends from levator ani muscle to anal verge.
- The *dentate line* represents the former site of the embryonic anal membrane.
- The lining of the canal above this line is columnar epithelium and below is skin.
- The mucosa above this line has an autonomic nerve supply, below is by pudendal nerve.
- The venous drainage above this line is by inferior mesenteric and portal circulation, whereas below to systemic venous circulation.
- Internal haemorrhoids develop above this line.

Sphincters of Anal Canal

Internal sphincter: Downward extension of circular muscle of rectum, under control of autonomic nervous system.

External sphincter: Surrounds the internal and continuous with the levator muscle.

Blood supply is from inferior rectal artery.

Venous drainage: Internal rectal venous plexus lies in the submucosa of the anal canal. It drains mainly into the superior rectal vein but communicates freely with external plexus. It is an important site of portasystemic communication. They are situated in anal column at 3,7,11 o'clock. Their saccular dilatation forms *'primary internal piles'*.


Inferior mesenteric artery
Aorta
Superior rectal artery
Inferior iliac artery
Middle rectal artery
Inferior rectal artery

Fig. 25.3: Blood supply of rectum.

PER-RECTAL EXAMINATION (Digital Examination of the Rectum)

> *We had almost come to the conclusion that the case (of vasovesiculitis) was one of acute appendicitis, but decided to make a rectal examination for the sake of completeness.*
>
> **—Ulysses Grant Dailey, WS Grant,** 1924

No abdominal examination is complete without a per rectal examination.

a. It is done to palpate.
   1. Carcinoma rectum.
   2. Stricture rectum.
   3. Polyps.
   4. Thrombosed piles.
   5. BPH and carcinoma prostate.
   6. Secondaries in the rectovesical pouch (Blumer shelf).
   7. Sphincter tone.
   8. Pelvic abscess (is felt as boggy swelling).
b. To feel the internal opening of anal fistulas.
c. In bimanual palpation of the bladder or pelvic tumours.
d. In acute abdominal conditions—it reveals dilated empty rectum with tenderness.

Positions for Per-rectal Examination

- Right lateral position.
- Left lateral position.

> *in the case of acute abdomen, it is more important to insert the finger into the lower end than to put the thermometer into the upper end of the alimentary tract.*
>
> **— sir zachary cope**

- Dorsal position in ill-patients.
- Lithotomy position.
- Knee-elbow position.
- Picker position: Patient in standing position leans forward by grasping a chair or stool. This method is used to palpate seminal vesicles which is involved by tuberculous seminal vesiculitis (as craggy feeling) or in trichomonas vaginalis infestation of seminal vesicle.

Per-rectal examination is contraindicated in acute fissure-in-ano.

PROCTOSCOPY (KELLY'S)

Indications

a. *Diagnostic*—piles, fissure in ano, polyps, stricture, etc.
b. *Therapeutic*—injection therapy for partial prolapse or piles, cryotherapy for piles, polypectomy, biopsy for carcinoma rectum or anorectum.



Figs 25.4A and B: Types of proctoscopes: (A) Non-illuminating, (B) Illuminating.

Types

a. Illuminating.
b. Nonilluminating.

Parts (10 cm)

Proctoscope is conical shape, with proximal diameter more than the distal, so as to illuminate the light at the required site properly. *Obturator* is the inner part which allows the easy insertion of the proctoscope.

Positions for Proctoscopy

- Left lateral position (common).
- Right lateral.
- Lithotomy.
- Knee-elbow position.

Technique of Proctoscopy

After doing digital examination, proctoscope with the obturator is introduced inside, through the anal canal in the direction towards the umbilicus.The obturator is removed. Proctoscope is withdrawn and during the course of withdrawal, any pathology has to be looked for.

Acute anal fissure is contraindication for proctoscopy.

SIGMOIDOSCOPY

> *Annual sigmoidoscopy for all, after their fortieth birthday: something to look forward to.*
>
> — **Henry George Miller,** 1968



Fig. 25.5: Rigid sigmoidoscope with inflation balloon and biopsy forceps.

- It is used to visualize rectum and sigmoid colon, take biopsies from suspected lesions and do therapeutic procedures (polypectomy, control of bleeding, etc).
- There are *two* types:
  1. ***Rigid***—25 cm long, with illumination.
  2. ***Flexible***—60 cm long.
- In lateral position as in P/R examination or proctoscopy, sigmoidoscope with obturator is passed into the rectum and obturator is removed. Rectosigmoid is inflated with air and scope is negotiated into the sigmoid through *Alpha* (α) *manoeuvre*. Looked for any disease, biopsies are taken and also any required procedure is done.

Precaution: Care should be taken in acutely inflamed sigmoid colon, because chance of perforation is high.

COLONOSCOPY

- It is 160 cm long, flexible.
- Technique is same as sigmoidoscopy, but is passed up to the caecum.

Technique

It is often done under GA using propofol or with laryngeal mask airway (LMA). It can be also done under high sedation. But patient finds difficult to tolerate pain and distension. Passage by *elongation; looping with a manoeuvre; dither-torquing* (clockwise-anticlockwise rotations) methods are used. Difficulty is encountered while passing through sigmoid colon, splenic flexure, and hepatic flexures. Continuous air inflation is important. It is better to visualise the lumen and then pass the colonoscope. Often it can also be negotiated into the terminal ileum. Changing position, abdominal pressure is required for better negotiation of the colonoscope. Technique differs in patients after haemicolectomy or through colostomy.

Indication

- Bleeding per rectum, resistant anaemia.
- To take biopsies from different parts of the bowel.
- To identify synchronous growths, ulcerative colitis.
- To remove polyps.
- When barium enema shows irregularity.
- For therapy—colonoscopic polypectomy, dilatation of stricture colon, fulgaration.

Contraindication

Acute ulcerative colitis.

Advantage

It helps to visualise full length of the colon. GA is not used, except in children.

Disadvantage

Takes a long time and requires expertise to do the same.

Hazards

- Perforation of bowel, splenic flexure is the commonest site.
- Trauma to anorectum.
- Sepsis.
- Haemorrhage.
- Problems of incomplete therapeutic procedures.

CARCINOMA RECTUM

> *Bubo is an apostem breeding within the anus in the rectum with great hardness but little aching. This I say, before it ulcerates, is nothing else than a hidden cancer.... Out of bubo (cancer) goes hard excretions and sometime they may not pass, because of the constriction caused by the bubo, and they are retained firmly within the rectum.... I never saw nor heard of any man that was cured... but I have known many that died of the foresaid sickness.*
>
> —**John of Arderne,** 1414

- It is common in females.
- Usually originates from a pre-existing adenoma or papilloma (tubular polyp).
- In 3% of cases, it occurs in multiple sites (synchronous).

Aetiology

- Red meat and saturated fatty acids increase the risk.
- High fibre diet reduces the risk.
- Alcohol and smoking increases the risk.
- FAP and adenomas are more prone to carcinomas.



Fig. 25.6: Polyps of colon. It is important premalignant condition for colorectal cancers.



Fig. 25.7: Large rectal polyp which has come out of the anal canal. It is potentially malignant.



Fig. 25.8: Pathological specimens of anal canal, rectum and sigmoid colon after abdominoperineal resection for low rectal carcinoma and midrectal carcinoma.

Never insult the vagina by examining the rectum first —**An old axiom**

- Villous adenoma has 40% chance of turning malignancy, size more than 2 cm is at high-risk.
- Ulcerative colitis; Crohn's disease; HNPCC carries higher incidence of carcinoma of rectum.
- Family history of rectal cancer—any first degree relative of a person with rectal cancer will show two times increased risk of carcinoma rectum.
- Risk of developing other cancers like of endometrium (40%); stomach (20%); biliary tree (20%); ovary (10%) in the same patient also increases.
- '*Adenoma—carcinoma sequence*' like in carcinoma of colon is known common method of occurrence.

Gross: It can be:

- *Ulcerative.*
- *Papilliferous.*
- *Infiltrative.*
- *Annular*: It is common in rectosigmoid junction.
- *Diffuse type:* Often observed in patients with ulcerative colitis which carries poor prognosis.

Histologically: It is *adenocarcinoma* which may be:

- *Well-differentiated—10%*
- *Moderately differentiated—65%*
- *Undifferentiated—25%*

Spread

- *Local spread*: Initially, it spreads, locally circumferentially (takes 12-18 months to complete the circumference of the bowel). Later spreads out to the muscular coat and perirectal tissue. Then to prostate, bladder, seminal vesicles in males, and uterus and vagina in females. Posteriorly into the sacrum and sacral plexus, laterally into the ureters.

Haggitt's invasion of malignant polyp (Similar to carcinoma colon)

In pedunculated polyp

Level 0—noninvasive carcinoma over the summit
Level 1—invasion to head of pedunculated polyp
Level 2—invasion to neck of the pedunculated polyp
Level 3—invasion to stalk of the pedunculated polyp
Level 4—invasion to base of pedunculated polyp
In sessile polyp—all lesions are level 4

Duke's staging of carcinoma rectum

A. Confined to bowel wall, mucosa and submucosa
B. Extends across the bowel wall to the muscularis propria with no lymph nodes involved
C. Lymph nodes are involved

Modified Duke's staging

A. Growth limited to rectal wall (15%)
B. Growth extending into extra rectal tissues but no lymph node spread (35%)
  B1: Invading muscularis mucosa
  B2: Invading in to or through the serosa
C. Lymph node secondaries (50%)
D. Distant spread to liver, lungs, bone, brain

Note:
Astler-Coller's grading (Refer Page No. 967, Chapter 22).

Colloid carcinoma of the rectum

It is 12% common in young people

Types

- Primary and secondary
- *Secondary* colloid carcinoma is common type and is due to mucoid degeneration of adenocarcinoma itself.

Primary is mucus within the cell with displaced nucleus *(signet ring)*

Primary type has got poorer prognosis compared to secondary

TNM staging of rectal cancers

Tx—Primary not assessed
T_0—No primary tumour
Tis—Carcinoma *in situ*
T_1—Invasion to submucosa
T_2—Invasion to muscularis propria
T_3—Invasion of subserosa or non-peritonealized perirectal tissues
T_4—Involvement of visceral peritoneum, other organs or structures
N_0—No nodal spread
N_1—1-3 nodal spread
N_2—4 or more nodal spread
M_0—No distant spread
M_1—Distant spread present

- *Lymphatic spread:* Above the peritoneal reflection, spread occurs upwards along the colonic lymph nodes. In mid-rectum, into the para rectal and mid-rectal lymph nodes. Downward spread is rare occurs when growth is close to the anal canal into the inguinal lymph nodes. Obturator nodes may be involved in 8% of lower rectal growths.
- *Venous spread* occurs to the *liver 35%, lungs 20%, adrenals 10%* and other areas.
- *Perineural spread* carries poor prognosis.

Clinical Features

- Bleeding per rectum/anum (may mimic haemorrhoids)—earliest symptom.
- *Spurious diarrhoea*: It occurs in *early morning* due to overnight mucus accumulation in the rectum causing urgency for defecation, but results in spurious diarrhoea with incomplete evacuation.
- *Tenesmus*: It is painful incomplete defecation with bleeding.
- *Bloody slime*: Mucus with blood in stool.
- Sense of incomplete evacuation, constipation.
- Presenting as piles due to proximal venous congestion by tumour or as fistula in perianal region (which itself is tumour extension into the anal canal).
- Anaemia, malnutrition, loss of appetite and weight.
- Altered bowel habits.
- Urinary symptoms are due to infiltration of bladder or prostate.
- Back pain, due to invasion of sacral plexus.
- Ascites, liver secondaries, urinary symptoms.

90% of rectal growths can be felt by per-rectal examination. Depth of tumour penetration can be assessed through digital examination as superficial tumours are mobile; deep penetrating tumours are not mobile.

Investigations

- Proctoscopy.
- Sigmoidoscopy.



Fig. 25.9: Air-contrast CT of colon and rectum showing significant narrowing in rectosigmoid junction.



Fig. 25.10: CT picture of carcinoma rectum. CT is useful in evaluating the extent, nodal status and operability.



Fig. 25.11: CT scan showing carcinoma of rectum.

- Biopsy using *Yeoman's* forceps.
- Barium enema in case of FAP and synchronous growths.
- Colonoscopy is ideal to rule out presence of any synchronous growths proximally (5%) or polyps.
- Even though *colonoscopy* is done *rigid proctosigmoidoscopy* is a must to identify the precise location of the tumour and to measure the tumour distance from anal sphincter accurately.
- U/S abdomen—to look for secondaries in liver, ascites.
- CT scan to see operability, local extension, size, nodal status, ureteral involvement, presence of perforation or fistula. CT is very useful to assess *nodal status*. Local extension is better assessed by TRUS. Any mesorectal node detected in CT is considered as malignant spread. Liver secondaries are well-identified in CT. Ureteral involvement in CT scan signifies requirement of stenting prior to surgery. Chest CT is essential to look for secondaries.
- *Endorectal ultrasonography*—very useful to assess the local extent of the tumour. *Transrectal ultrasound (TRUS)*/ endorectal ultrasound gives more accurate picture of primary tumour, layers, perirectal tissues and nodes. TRUS is superior in T staging of rectal cancers. Its accuracy is 95% compared to MRI (85%); and CT (75%). Endorectal US based T staging and N staging used now depends on layers involved and presence of nodes. TRUS detects nodes more or equal to 5 mm size.
- *Endorectal coil MRI* (*EC MRI)* is very useful as it gives larger field of view compared to TRUS; extent, adjacent organ spread are better assessed by MRI. Recurrent tumour is better assessed by MRI.



Figs 25.12A and B: MRI showing carcinoma of rectum and adjacent structures. MRI is good method to evaluate the spread and staging.

- *Fluorine—18 fluorodeoxyflucose PET scan* is useful to detect recurrent local tumours; metastatic disease; to detect pathologic response in preoperative chemoradiation. PET is not accurate for nodal spread.
- Blood tests like haematocrit; CEA; blood urea and serum creatinine; serum electrolytes and proteins for management purpose. *CEA estimation*—it is raised in metastatic disease. It is important during follow-up after treatment.

Diseases of the soul are more dangerous than those of the body.

Differential diagnosis

- Inflammatory stricture
- Amoebic granuloma
- Tuberculosis
- Carcinoid
- Solitary ulcer syndrome

Treatment

Surgery

Principles

- Surgery is the main method of treatment. Preoperative chemoradiotherapy is often used if growth is invading into adjacent tissues (T4). Adjuvant chemotherapy and radiotherapy is a must.
- Genetic, morphologic, biologic features of rectal cancers are similar to colonic cancers.
- But *anatomical factors* make it more complex than colonic cancers, like its location deep in the pelvis, relation to important structures like ureters, bladder, genital, autonomic nerves and anal sphincters. So surgical approach is very difficult.
- *Avascular endoplelvic fascial plane* is important during dissection to avoid injury laterally to autonomic nerves (will cause impotence in men and bladder dysfunction in both sexes); more medial dissection leads into incomplete clearance and high local recurrence.
- *Abdomino perineal resection (APR)* is the gold standard. But if tumour is well-differentiated and if there is adequate margin above the anal canal, a sphincter saving *anterior resection (AR)* can be done. *Low anterior resection (LAR)* is possible if EEA stapler is used for anastomosis. But anterior resection should not be done by compromising the adequacy of tumour clearance. Tumour clearance is still the priority in rectal cancer as it decides the eventual outcome.
- *Total mesorectal excision (TME) should be the goal* in all procedures as mesorectum contains nodes and lymphatics, clearance of which gives better result.
  - It is a *sharp dissection* (not blunt) in avascular areolar plane between fascia of rectum which encroach the mesorectum and parietal pelvic wall fascia.
  - Mesorectum should not be breached.
  - Absolute haemostasis, *preservation of autonomic nerves* and dissection under vision are the essential principles.
  - Both layers of membranous anterior Denonvillier's facia should be dissected off the prostate and seminal vesicles in male to have proper clearance.
  - In TME for middle and lower rectum, entire mesorectum should be removed.
  - For upper rectal tumors, TME is done 5-6 cm below the lower margin of the tumour.
  - TME improves the quality of life in relation to *impotence, retrograde ejaculation and urinary incontinence.* These complications are around 50% or more in APR whereas in TME it is less than 20%.
- Recommended *distal rectal margin clearance is 5 cm*, however 2 cm distal margin is an *acceptable* clearance.
- *Circumferential resected margin—CRM* (*radial margin, > 2 mm*) is more important than proximal and distal margin. A 5 cm clearance of mesorectum from the primary tumour is essential as tumour implants can occur only for up to 4 cm from primary tumour margin.
- *Principles to be followed*—adequate lymphatic and vascular clearance; en bloc resection of primary tumour; no / less touch technique; avoiding spillage; adequate radical surgery.
- *Ultra low anterior resection or intersphincteric* resection can be considered in low rectal tumours.
- After resection (on table*) irrigation of rectal bed* with cetrimide or hypertonic solution like distilled water is often practiced as they are tumoricidal.
- Selection of the procedure AR or APR is decided by proper staging using TRUS and MRI.
- Neoadjuvant chemotherapy or neoadjuvant chemoradiotherapy is often used in T3 lesions which also may avoid APR; and AR may be sufficient.
- Local wide excision approaches are often used when tumour is < 4 cm; < 40% circumference involved; T1 N0/ T2 N0 tumour:
  - *Transanal approach* is used in small tumours that is 3-5 cm above the dentate line but within 10 cm from the anal verge:
  - *Transcoccygeal Kraske's approach* for posterior wall rectal tumours (dangerous posterior faecal fistula can occur);
  - *Transanal endoscopic microsurgery* (Buess) using operating microscope and videoscope can also be done. This *endosurgical device* is 4 cm in diameter, specialized sealed proctoscope with ports for CO_2 insufflation, water irrigation, and suction and for monitoring intrarectal pressure. CO_2 insufflation distends the rectum and local excision is done with proper positioning of the device.
- In females, partial vaginectomy with or without hysterectomy and bilateral oophorectomy may be needed in T4 lesions to achieve surgical resection. Removal of uterus and ovaries prevents patient from developing possible associated cancers of these organs. Carcinoma rectum also spreads to ovaries commonly which can be prevented by oophorectomy.
- Often resection of liver secondaries can be undertaken in selected patients when one lobe is involved or solitary secondaries are present.
- *Laparoscopic APR/AR* is becoming popular.

  Features are:
  - Dissection will be more meticulous.
  - Less blood loss, less postoperative pain.
  - Early bowel function.
  - Clearance is same as open method in relation to primary tumour and nodes.
  - Short hospital stay, mortality and morbidity are similar to open method.
  - Port site recurrence chances are 0.5-2% (Earlier it was higher; now it has reduced due to proper technique, careful handling of the specimen, specimen isolation prior to extraction, trocar site irrigation with cytotoxic agents and povidone iodine).

- For carcinoma rectum presenting with obstruction, an initial proximal colostomy is done. Neoadjuvant chemoradiation is given. Patient is reassessed for operability. Then APR is done with permanent colostomy.
- Incidence *of local recurrent rectal cancer* is 30%.
  - 80% of local recurrence occurs within 2 years of surgery.
  - Common site of recurrence is in the pelvic wall. It also can occur at distal anastomotic margin.
  - Intractable pelvic pain, urinary symptoms, sepsis, bleeding, perineal sinus, swelling and induration, bowel disturbances are the features.
  - It is evaluated by CEA, biopsy, CT abdomen, MRI of pelvis and PET scan.
  - It is often difficult to manage.
  - Incidence of recurrence will come down to 5% in proper TME.
  - Palliative chemoradiation, end colostomy, ureteral stenting are the palliation. RT controls pain and bleeding.
  - Extensive radical surgery like removal of tumour with pelvic structures can be undertaken with diversions but with a high mortality rate and failure rate.
- Proper *preoperative bowel preparation* is a must in all rectal cancers which reduces the postoperative problems like sepsis, leak and increases the early chance of recovery.
  - Bowel preparation by polyethylene glycol; electrolytes *orally*; bowel wash *per anally*; bowel antiseptics like neomycin 1 gm tid previous day/erythromycin 1 gm tid/ metronidazole tid *orally.*
- Systemic antibiotics like cefazolin, metronidazole, gentamycin.
- Prophylactic heparin or low molecular weight heparin.
- Foley's catheterisation and nasogastric tube should be passed.
- Preoperative adequate hydration using IV fluids.
- Blood grouping and crossmatching and required bottles of blood should be reserved if needed to transfuse during the procedure.

Different surgeries for carcinoma rectum are:

1. **Abdominoperineal resection** (A-P resection) (APR) wherein sigmoid, descending colon and upper rectum is mobilised per abdominally. Anal canal with perianal and perirectal tissues are dissected per anally. Retained colon is brought out as *end colostomy* in *left iliac fossa*.

APR—types

- *Miles*—abdomen first, perineum later
- *Gabriel*—perineum first, abdomen later
- *Lioyd-Davis*—synchronised (together), (combined)

- APR is done through lower midline incision in lithotomy position. Left-sided colon and entire rectum is mobilised from above. Rectum is mobilised posteriorly in avascular plane in front of nerve plane (hypogastric nerve) between mesorectum and sacrum. Inferior mesenteric artery is ligated high proximal (as lymphovascular ligation) at its origin or just beyond its first branch. Colon is transected and proximal cut end is fashioned for end colostomy in *left iliac fossa*. Through perineum, a purse string suture is placed around anal margin. Circumferential incision is placed around the anus. Dissection is deepened using scissor and cautery into the perineal body, coccyx, ischial tuberosity, ischiorectal fossa. First posterior and lateral dissections are undertaken until it reaches above. Lastly, anterior dissection is done to reach above and specimen is removed through perineal wound. Perineal wound is closed in layers often with a drain. Abdomen drain is placed. Colostomy is created by suturing skin to mucosa using silk.



Fig. 25.13: Laparoscopic view of mobilised rectum in APR.



Figs 25.14A and B: Colostomy done in left iliac fossa after APR. Colostomy care is important.

- *Complications of APR* are:
  - Bleeding.
  - Infection of perineal wound.
  - Complications of colostomy like prolapse, stenosis, and infection.
  - Injury to urinary system, ureter, impotence, urinary incontinence.
  - Operative mortality is less than 2%.

APR is the treatment of choice when mesorectum is involved or when it is poorly differentiated tumour or when nodes are involved. It gives adequate clearance.

- *Sphincter saving APR with coloanal anastomosis*: It is done in operable distal rectal tumour in young individual wherein within oncological principle anal sphincter need not be sacrificed but adequate oncological tumour clearance can be achieved. Here a permanent colostomy stoma is avoided. Approach is both abdominal and perineal. Initial dissection of rectal mobilisation is done from above; dissection of rectal mucosa from the anal sphincter at the level of dentate line and complete dissection of distal rectum is done through anal canal. Entire rectosigmoid is removed retaining only the anal sphincter. Colonic J pouch or coloplasty reservoir is created in the mobilised descending colon; coloanal anastomosis is done per anally using hand sutures under direct visualisation.
- *APR with neo sphincter reconstruction* is also occasionally sought; but technically difficult with complications. Perineal colostomy is done with gracilis muscle wrap which is made to produce sphincter like muscle twitch using an implanted pacemaker.

2. **Anterior resection** (Abdominal radical restorative operation) is done in growths located in the mid and upper part of the rectum, which is well-differentiated, small-sized and with a clear adequate length for anastomosis after resection.

- *Anterior resection* is also called as *anterior proctosigmoidectomy* through *abdominal* approach wherein rectum *above* the peritoneal *reflection* is resected with colorectal anastomosis.
- *Low anterior resection (LAR)* is resection of rectum *below the peritoneal reflection* along with the sigmoid colon (as sigmoid should be removed due its precarious blood supply after dissection), with total mesorectal excision (TME) *through abdominal approach* (laparotomy) and *colorectal anastomosis* using *circular* stapler device (EEA stapler). Stoma should be inspected using proctoscope for integrity and when in doubt a covering temporary proximal colostomy should be done. LAR often leads into frequent small bowel movements causing more frequent stools called as *low anterior resection syndrome (LAR syndrome)/clustering*. It can be avoided by creating reservoir either by doing *colonic J pouch* or by doing *coloplasty* 6 cm from proximal divided end of colon (longitudinal colostomy between taeniae of 10 cm which is sutured horizontally).

Criteria for anterior resection—(Low anterior resection, LAR)

- Upper and middle third rectal growth
- Above peritoneal reflection
- Well-differentiated tumour
- < 4 cm size tumour
- In females, growth 7 cm above the anal verge
- T1 N0/T2 N0 tumour
- Tumour without lymphatic or venous spread

Advantages:

- Avoids permanent colostomy.
- Sphincter is retained.
- Patient's acceptance.



Fig. 25.15: Anterior resection for carcinoma upper rectum using stapler device.

Disadvantages:

- Uncertainity of clearance which is very important in cancer surgeries and so chances of **local recurrence** is high.
- Anastomotic leak, infection; stenosis.

3. **Hartmann's operation** is an excellent palliative procedure—done in elderly people who are not fit for major surgery like AP resection and also in locally advanced tumours. Here rectal growth is resected and upper end of the rectum is closed completely. Proximal colon is brought out as *end colostomy*.
4. **Pelvic evisceration (Brunschwig's operation):** It is removal of rectum with the tumour, all the lymph nodes, urinary bladder, fat, fascia, uterus, vagina, with colostomy and urinary diversion. It is neither favourable nor popular.


Growth
A
Carcinoma rectum (lower)
After A-P resection
B
Carcinoma upper rectum—anterior resection
Resected
C
Advanced carcinoma rectum—Hartmann's resection

Figs 25.16A to C: Surgeries for Ca rectum (A) A-P resection, (B) Anterior resection, (C) Hartmann's resection.

5. **Palliative colostomy** is done in advanced unresectable growth which presents with intestinal obstruction.

Radiotherapy

It is beneficial in carcinoma rectum showing increased survival rate. It is useful when growth is below the level of peritoneal reflection.

Radiotherapy in carcinoma rectum

- Only rectal adenocarcinoma in GIT responds well for RT
- Preoperative RT can be given to down stage the tumour so as to make it amenable for APR or make it for anterior resection
- Postoperative RT is commonly used
- In small well-differentiated growths *papillon's* intracavitary curative RT can be tried with proper follow-up
- Palliative RT
- IORT (Intraoperative RT) is used in pelvic wall disease. It can cause peripheral neuropathy and ureteral stenosis
- As a component of chemoradiation
- Short course 25 Gy in 5 fractions in 5 days
- Long course 5040 Gy in 28 fractions in 6 weeks
- RT sterilises field; causes down staging of tumour; preserves sphincter

Chemotherapy

It has been tried using endoxan, 5 FU, semustine also with leucoverin (Folinic acid) or levamisole.

- Capecitabine, oxaliplatin are newer drugs used (refer chapter large intestine for detail). Indications are positive nodes; T2 stage; blood spread; for chemoradiation; recurrent tumour; advanced/ metastatic disease.
- Biologic agents.
  - Bevacizumab VEGF receptor antagonist.
  - Cetuximab EGFR antagonist.

Other Methods

- Electrocoagulation and decoring of the tumour, as a palliative procedure; stenting.
- Laser photocoagulation, cryotherapy.
- *Portal vein infusion*; hepatic artery infusion for metastases.
- *Tumour vaccines*: Tumour antigen does not elicit immune response *in situ*; but vaccines are injected to evoke immune response. (1) BCG with irradiated tumour cells (2) Monoclonal antibodies 17-1A [Murine Ig G2A] (3) CEA vaccines.

Chemoradiation in Carcinoma Rectum

- It is very useful *adjuvant therapy.*
- To prevent recurrence after anterior resection.
- Neoadjuvant (preoperative) chemoradiation can be used in tumour like T3 to downstage the disease and make it possible for AR.
- Postoperative chemoradiation.
- Palliative chemoradiation in locally advanced disease or metastatic disease also.
- Recurrent local carcinoma of rectum.
- In carcinoma of rectum presenting with obstruction, chemoradiation is given after loop colostomy.

Prognosis in carcinoma rectum

5-year survival is	***Prognostic factors are***	***Follow-up***
• Stage I 90% • Stage II 75% • Stage III 40% • Stage IV 5%	• Size of the tumour • Differentiation • Mesorectal involvement • Stage of the disease • Nodal status, perineural spread • Distant spread • Circumferential resected margin • Adjuvant therapy used	• Regular colonoscopy • CEA assessment • PET scan • CT/MRI • Colostomy care in APR

SOLITARY ULCER SYNDROME

- It is mainly thickening and disorganisation of muscularis mucosa with superficial ulceration.
- It is usually 4-12 cm from the anal verge in the anterior wall of the rectum. But often can occur in sigmoid colon.
- Attempt to defaecate in the closed pelvic floor causes funneling of the rectum and descent of the anterior rectal wall. Raised intrarectal pressure and hidden intussusception is the cause. It is often seen in sexual abused individuals. Often typical crater like ulcer is seen/felt on the *anterior rectum*. Chronic ischaemia at that point may be the cause.
- In 30% cases, there are multiple ulcers.
- Often there will be inflammation and induration of the area without an ulcer.
- ***Presentations are***—common in young females, constipation, bleeding, mucosal prolapse, chronic pain in the anal canal, incontinence. But sphincter tone on rectal examination is usually normal.
- ***Investigations:*** *Defaecography* shows nonrelaxing persistent puborectalis impression waves. EMG shows decreased electrical activity. Colonoscopy should be done to rule out other conditions like neoplasm, ulcerative colitis. Colonic transit time shows rapid filling of the rectum but delayed clearance of 7 days from the rectum.
- Condition is commonly associated with rectal prolapse.
- ***Differential diagnosis*** are carcinoma, tuberculosis, ulcerative colitis.
- ***Treatment:***
  - High fibre diet.
  - Treatment for rectal prolapse.
  - Avoid surgical excision in solitary ulcer syndrome as much as possible.

The place to improve this world is first in one's own heart, head and hands.

RECTAL PROLAPSE

- It is *circumferential descent* of recetum (bowel) through the anal canal.
- It is commonly seen in infants, children and elderly individual**.**
- It is common in females (6 : 1).
- *Faecal incontinence* is very common feature; urinary incontinence occurs in 35% of patients; 15% of patients are associated with vaginal vault prolapse.
- Rectal prolapse can be:
  - *Partial.*
  - *Complete.*
  - *Hidden/concealed*—it is internal intussusception of the sigmoid into the rectum or part of the rectum distally; they do not come out of the anal orifice. Here only mucosa and submucosa separates from muscularis layer and descends.



Fig. 25.17: Rectal prolapse.

Aetiology

- *Alexis Moschowitz* put his theory of 'rectal prolapse is due to sliding herniation of the pouch of Douglas through pelvic floor fascia into the anterior aspect of the rectum'.
- *Broden and Snellman* proposed that 'procidentia is a full thickness rectal intussusception starting approximately 7.5 cm above the dentate line which is extending beyond the anal verge'.
- Decreased sacral curvature and decreased anal canal tone are the probable causes in infants.
- *Chronic constipation* with straining is the common cause.
- Diarrhoea, cough, malnutrition are the additional factors in children.
- It may be due to reduced ischiorectal fossa fat, neurological causes, fibrocystic disease of pancreas or poorly developed pelvis.
- There is diastasis of the levator ani, abnormally deep cul de sac, redundant sigmoid colon, patulous sphincter, loss of rectal sacral support, lax and atonic pelvic floor musculature.
- *Pudendal nerve damage* is said to be the cause for pelvic floor and anal sphincter weakness. It may be due to obstetric injury, diabetes, sacral nerve damage.
- In adults, it is common in females, common in multipara—repeated birth injuries to perineum results in damage to the perineal nerve supply.
- Additional factors are due to increased intra-abdominal pressure due to any cause like chronic cough, stricture urethra.

Types

Partial Rectal Prolapse

Here only mucosa and submucosa of the rectum descends, not more than 3.75 cm. There is no descent of the muscular layer. It is the *commonest type of rectal prolapse*.



Fig. 25.18: Partial rectal prolapse is less than 3.75 cm and only mucosal.

Clinical Features of Partial Rectal Prolapse

- History of mass per anum, which can be observed when child is allowed to strain in squatting position.
- It is *pink in colour and circumferential*.
- It differs from *piles* (differential diagnosis), the piles are not circumferential and *are plum or blue coloured (not pink)*.

Treatment for Partial Prolapse

1. The nutrition of the child is improved and digital repositioning is tried. *Correction of constipation* is important.
2. Submucosal injections of 10 ml of 5% phenol in almond oil or ethanolamine oleate is given into the apex of the prolapse under. G/A so as to create an aseptic inflammation leading to tethering of mucosa to the underlying muscular coat. Injection can also be given at the base or both at the apex and base.
   - Alternatively 30 ml of tetracycline or oxytetracycline or hypertonic saline injection can also be used. Initial injection is supported by *Thiersch wiring* using (temporary) chromic catgut until adhesion occurs between the mucosa and muscular layer (in 3 weeks).
   - In adults, injection therapy is tried for partial prolapse, results are not as good as in children.
3. Thiersch wiring alone is tried with good success rate in children.
4. *Goodsall's operation* is excision of the prolapsed mucosa at its base, usually in three positions.

5. Stapled transanal rectal resection surgery *(STARR)* is also often used.



Fig. 25.19: Goodsall's ligature for partial prolapse. Prolapsed mucosa is ligated at different positions using nonabsorbable suture material often with double needled. Usually, it is done for one side in three portions.

Complete Rectal Prolapse

- Also called as *procidentia,* is *less common than partial prolapse.*
- It is common in females (6 : 1 :: female : male).
- It is due to weakened levator ani and supporting pelvic tissues.
- The descent is always more than 3.75 cm, contains all layers of the rectum (i.e. including muscular layer). Often descends down up to 10-15 cm.
- It is often associated with the uterine descent *(uterine prolapse*).
- It is also thought to be as an intussusception of the rectum.
- Once complete prolapse is more than 5 cm, anteriorly it drags peritoneum as pouch which often contains small intestine. On digital pushing it reduces with gurgling.
- Patulous anal sphincter is typical with mucus discharge and faecal incontinence.



Fig. 25.20: Complete rectal prolapse.



Figs 25.21A and B: Complete rectal prolapse. It should be confirmed by observing the patient during straining in squatting position.



Fig. 25.22: Female patient presented with both complete uterine and rectal prolapse (Procidentia).

- Mucosa of the chronic rectal prolapse is *thickened, ulcerated, bleeds*, and often *incarcerated* below the level of anal verge.

Aetiological factors

- Weak anus, external sphincter and pelvic muscle
- Lax, mobile rectum
- Obliterated ano-rectal angle
- Abnormally mobile rectum with descent

Clinical Features of Complete Rectal Prolapse

- *Complete descent of rectum as mass per anum* circumferentially which is *red* in colour. Mass is usually reducible and painless. Incarcerated or infected rectal prolapse is painful.
- Rectal prolapse may be associated with the *uterine prolapse* (uterine procidentia) in females.

- Faecal incontinence (75%) is very common. It is due to disruption of the anal sphincter and prolapsed rectal mucosal discharge.
- Bleeding can occur because of the congestion.
- Sepsis, discharge, fever, anaemia are other features.
- P/R examination shows lax sphincter. Anteriorly, peritoneal sac comes down as a pouch which may contain small bowel.



Figs 25.23A to C: Complete rectal prolapse. It is more than 3.75 cm, prolapse of mucosa with muscular layer.

Differential Diagnosis

Rectosigmoid intussusception, third degree piles, large rectal polyp.

Folds in rectal prolapse are *concentric* and *red* in colour; in piles there are *radial nonconcentric* invaginations of haemorrhoidal cushions which are *plum* coloured with a cutaneous component.

Complications of rectal prolapse

- Ulceration, bleeding, anaemia
- Proctitis, sepsis
- Irreducibility, gangrene
- Rupture with evisceration

Investigations

- Defecography reveals increased mobility of the rectum from sacral fixation point with redundant mesorectum and funnel formation. It is fluoroscopic and spot filming in lateral projection after instilling radio-opaque material into the rectum done in sitting posture over a radiolucent commode.
    - Cinedefecography, triple contrast cinedefecography, dynamic MRI defecography, colpocystodefecography are helpful to delineate complex pelvic floor problems.
    - *Defecography detected abnormalities*—megarectum, incontinence, nonrelaxing puborectalis, abnormal perineal descent (2.5 cm), mucosal prolapse, solitary ulcer rectocoele, enterocele.
    - *Preprolapse (*in defecography): Rectum is funnel shaped, lack of fixation to sacrum, excessive rectosigmoid mobility, ring pocket formation, intussusception.
    - *Rectal prolapse (*in defecography)**:** Redundant sigmoid colon, wide deep pouch of Douglas.

Defecographic grading of rectal prolapse

N—normal rectal fixation and sphincter relaxation and rectal emptying
1—nonrelaxed puborectalis
2—mild intussusception
3—moderate intussusception
4—severe intussusception
5—prolapse
R—rectocele

- *Sigmoidoscopy:* It is to detect the tumour in the intussuscepted prolapsed rectum which is an occasional cause.
- *Anal manometry: Resting* (40 mmHg of internal sphincter) and *squeeze* (80 mmHg, exteranal sphincter) pressures at various points in anal canal is measured by placing water filled balloons attached to catheters and transducers placed in the anal canal.
- *Pudendal nerve latency study: Specialized transducer* attached to a glove like device is to be worn on the finger through which digital rectal examination is done. Electrode in the finger is directed over the right and left levator ani complex to measure pudendal nerve terminal motor latency (PNTML) which is normally 1.8-2.2 msec. It is prolonged in pudendal nerve damage.
- *Electromyography study* of the puborectalis muscle tone is also very useful.

Treatment for Complete Prolapse

Aim of Treatment

- To *control* the prolapse; to *restore* continence; to *prevent* constipation.
- *In young males, abdominal repair should be avoided as it injures pelvic nerves leading to sexual impotency*. So perineal approach is better.
- Rectopexy is fixing the rectum to sacrum by sutures or mesh after complete mobilisation of the rectum. Laparoscopic rectopexy using polypropylene mesh and sutures gives good result and has become very popular.
- *Delorme's operation* is better option in young individual with complete prolapse.
- In elderly perineal proctectomy with anterior and posterior reefing of the sphincter muscle is accepted method now. It is similar to Altemeier technique (It is perineal rectosigmoidectomy). Here entire prolapsed rectum and redundant sigmoid is resected through perineum prior to reefing of the sphincter.
- Anal encircling surgeries using synthetic wires/mesh/suture materials are limited to extremely ill patients and elderly who will not withstand perineal proctectomy.
- *Choice of procedure* depends on age, sex, operative risk, pelvic floor defect, degree of incontinence, history of constipation.

Surgery—Types

Abdominal Procedures

Laparoscopic rectopexy

- It is ideal and good approach to fix the rectum to sacrum.
- *Laparoscopic posterior mesh rectopexy (LPMR)* is the procedure done. Prior bowel preparation is needed. Head down, low lithotomy position is needed. Ports are placed as shown in diagram. Sigmoid colon is held with left sided port. Surgeon does dissection from right side. Peritoneum on the right of the rectum is opened from sacral promontory downwards to reach presacral avascular plane. Care should be taken to avoid injury to autonomic nerves, ureters. Dissection is extended down as posterior mobilisation into the pelvis with adequate mobilisation of the rectum. Lateral ligaments are either divided or left alone. *Anterior mobilisation* is also important. Anterior mobilisation along the Denonvillier's fascia is done 5 cm below the peritoneal reflection. 15 × 10 cm polypropylene mesh is placed in the presacral space deep to rectum which is fixed to presacral fascia along the sacrum and sacral promontory. Mesh is sutured to rectal wall also on both sides using interrupted polypropylene sutures. Only partial wrapping of mesh is done. Peritoneum is closed using vicryl.
- Many advocate laparoscopic mobilisation and fixation of mobilised rectum to sacral promontory using polypropylene sutures without mesh.
- *Laparoscopic sigmoid resection and rectopexy* (Laparoscopic resection rectopexy, LRR) is done when there is rectal prolapse with constipation, with excess redundant sigmoid colon with kinking.



Fig. 25.24: Laparoscopic rectal prolapse—ports.

Well's operation

- *Polyvinyl alcohol sponge* is wrapped around the mobilised rectum and is fixed to sacrum. Infection, fistula formation is high.
- Polypropylene mesh is used as a modification now instead of polyvinyl sponge; wrapping is only partially done to reduce the incidence of constipation.

Ripstein operation

After mobilisation of the rectum, 5 cm width Teflon mesh sling is passed around the rectum to fix it behind to fascia 5 cm below and in front of the sacral promontory. Sling is also fixed in front and laterally to rectum.

Goligher's operation

Rectum is entirely mobilised up to anorectal ring and its posterior muscular layer is fixed to presacral fascia using interrupted polypropylene sutures.

Devadhar rectal plication

Through abdominal approach, junction between thicker lower part and thinner upper part of the intussusception is identified. A purse string suture using silk is placed in front and laterally; further 3-4 interrupted submucosal Lambert sutures are placed to create reverse intussusception.

Lahaut's operation

Rectosigmoid is mobilised fully; mobilised loop of rectosigmoid is passed in front through posterior rectus sheath behind the rectus muscle; extraperitonealisation is done to pull the rectus forward to prevent descent.

Rosoe Graham operation

- After mobilisation of the rectum, levator muscles are exposed and sutured in front of the rectum along with removal of pouch of Douglas.

- *In Dumphy operation* it is done through combined abdominoperineal approach with perineal rectosigmoidectomy. Both procedures control prolapse well but not incontinence.

Muir low anterior resection

In a redundant rectosigmoid with prolapse, rectosigmoid resection is done; excision of redundant pouch of Douglas is done; rectum is fixed to sacrum behind.

Perineal Procedures

Delorme's operation (Mucosal sleeve resection and plication)

After prior bowel preparation, under spinal anaesthesia, in lithotomy position, completely prolapsed rectum is held with Babcock's forceps. 1 in 2,00,000 adrenaline solution is injected into the submucosal plane of the rectum to cause haemostasis. By making longitudinal incision, with sharp scissor and cautery dissection, mucosa is stripped off from the deeper muscular layer from 1 cm below the anal margin to the apex of the prolapsed rectum. Muscular layer of rectum is plicated using absorbable vicryl 2 zero interrupted sutures all around; approximately 12-15 plication stitches are needed. These sutures are tied after finishing the passage of all sutures. Cut end of the mucosa of the apex is sutured to anal margin using interrupted vicryl sutures. It is technically easier. But incontinence may persist and recurrence chance is high.

Perineal posterior fixation of the rectum of Lockhardt-Mummery

Retrorectal space is dissected through perineal approach and posterior rectal wall is sutured to sacrum and coccyx, additionally placing a retrorectal gauze pack to stimulate adhesions.

Wyatt operation

Through perineal post anal approach dissected retrorectal space is placed with a Marlex/mersilene mesh which is sutured high to the sacral promontory and rectal wall laterally.

Mickulicz Miles perineal transanal rectosigmoidectomy/ amputation of prolapse

Prolapsed rectum is excised and sigmoid is sutured to the anal margin.

Altemeir's rectosigmoidectomy

After rectosigmoidectomy, colonic anastomosis and pelvic floor is supported by suturing puborectalis muscle in front of the rectum using nonabsorbable sutures.

Anal encircling

- In 1891, Thiersch did anal encircling using silver wire to provoke inflammatory fibrosis as well as to give mechanical support to the anal orifice—*Thiersch wiring*. It is done under local anaesthesia. Two small incisions are made at lateral parts of the anal canal. Silver wire is passed around deeper to these incisions and tied after placing the *index finger* into the anal canal. Wire can be removed after 12 months. Polypropylene, nylon are the other materials that can be used. *Complications*: Pain due to wire erosion, infection, faecal impaction, incarceration, high recurrence of 50% or more. In children with rectal prolapse, *temporary wiring* along with Goodsall's ligature or injection sclerotherapy using thick catgut are often advocated.
- *Supralevator high encirclement of anal orifice* (of Notaras) is done above the level pf levator muscles by placing Teflon or nylon ribbons through anterior and posterior incisions. It gives better support and will not cut through. *Thoralsksen* modified this by placing plastic/mersilene tape around the bowel high up.

Procedures for repair of rectal prolapse

Perineal operations	*Abdominal operations: Open/Laparoscopic*
• Mucosal sleeve resection (Delorme)	• Suture rectopexy—Goligher, Lahaut, Devadhar, Rosoe Graham
• Perineal rectosigmoidectomy (Altemeier)	• Prosthetic or mesh rectopexy—anterior/ posterior—Well's, Ripstein
• Posterior fixation of the rectum of Lockhardt-Mummery	• Resection rectopexy—Muir's
• Wyatt operation	• Anterior resection
• Mickulicz Miles perineal transanal rectosigmoidectomy/ amputation of prolapse	• Lahaut's operation
• Anal encircling (Theirsch)	

Complications of Surgery

- Injury to hypogastric nerve causing impotence.
- Bladder dysfunction.
- Bleeding from sacral venous plexus.
- Injury to rectum and colon causing faceal fistula.
- Constipation after rectopexy is a known complication.
- Recurrence of prolapse.
- Improper correction of continence occurs in 50% cases.
- Infection—proctitis/pelvic abscess, etc.

ANORECTAL MALFORMATIONS (ARM)

- It is due to imperfect fusion of the post-allantoic gut with the proctodaeum.
- Incidence is one in 4500 newborns.



Figs 25.25A and B: Anorectal malformation with fistula in (A) Females and, (B) Males.

Wingspread classification of anorectal malformations
('Wingspread'—name of the place where the conference was held)

Low	*Intermediate*	*High*
It is below the level of pelvic floor, (Puborectalis). Easy to diagnose and treat with good outcome. It may be—	It occurs at the level of puborectalis, with or without fistula	It can be with or without a fistula into the bladder urethra, uterus, vagina It may be:
– Covered anus		– Anorectal agenesis
– Anovestibular fistula		– Rectal atresia
– Anal stenosis		– Cloaca (only in females, with confluence of rectum, vagina, bladder and urogenital sinus)
– Anal membrane.		

Clinical Features

- New born presents with inability to pass meconium, abdominal distension, features of intestinal obstruction, improper anal dimple, sometimes with complaints of passing meconium per urethra.
- It can be associated with—cardiac anomaly, tracheo-oesophageal fistula, renal anomalies, spinal anomalies. VATER/VACTERL anomaly.
- Most common ARM in boys is *rectobulbar fistula* with fistula beginning distal to puborectalis from distal rectum to bulbar urethra.
- Most common ARM in females is *rectovestibular fistula*.



Fig. 25.26: Anal stenosis.



Fig. 25.27: Anorectal malformation, Cloaca type.

Investigations

1. *Wangenstein's invertogram:* Usually done 6-12 hours after birth, so as to allow air to reach the rectal pouch. A metal coin (marker) is strapped at the presumed site of anus and X-ray is taken. Length between the rectal pouch and anal dimple marker is more than 2.5 cm in high anal fistula.
    a. In *low fistula*, rectal pouch is distal to the *Stephen's line (Pubococcygeal line).*
    b. In *intermediate,* pouch is at the level of ischial spine *(Kelly's point*).
    c. In *high fistula,* rectal pouch is proximal to the Stephen's line.
2. *Murugassu's technique:* Through visible anal dimple, meconium is aspirated by passing a needle into the rectal pouch in sitting propped up position. Watersoluble iodine dye is injected. Lateral X-ray is taken to study the level through Stephen line and Kelly's point.
3. U/S abdomen.
4. Evaluation of cardiac function is also important.
5. MRI spine.



Fig. 25.28: *Stephen's line*.

We make a living by what we get; we make a life by what we give.

Treatment

1. In ***low fistula**,* single stage reconstruction is done under G/A with very good results.
    i. Anoplasty.
    ii. Anovestibuloplasty.
    iii. Anal dilatation.
    iv. Incision of anal membrane.
2. In ***high fistula***, initial colostomy is done. Later definitive procedure, i.e. *Pull through operation* through puborectalis and anastomosis of rectal pouch to create the anal canal is done. Closure of colostomy is done later.
    - *Posterior sagittal anorectoplasty* is commonly done procedure.

Note:

Level of rectal pouch and normal/abnormal sacrum are the deciding factors for good results.

Complications

- Infection
- Faecal fistula
- Stenosis
- Colitis
- Malnutrition
- Faecal incontinence

PILONIDAL SINUS/DISEASE (Jeep Bottom; Driver's Bottom)

Pilus—hair; Nidus—nest

- It is of infective origin and occurs in sacral region between the buttocks, umbilicus, axilla.
- It is epithelium lined tract, situated short distance behind the anus, containing hairs and unhealthy diseased granulation tissue. It is due to penetration of hairs through the skin into subcutaneous tissue. It forms granuloma/unhealthy granulation tissue in the deeper plane.
- *Types of hair* (H), *force of hair insertion* into subcutaneous tissue (F), *vulnerability of the skin* (V) are the three factors that cause pilonidal sinus. Number of hairs collected, acuteness of root end of hairs, type of hair—tough/silky, shape of hair—straight/curled, scaliness of hair are the deciding features of hair. Cut hairs from above descend into cleft and stay there to get buried deep into pilonidal sinus. Depth, narrowness, friction movements in the natal cleft; soft/macerated skin with erosions, splits, wide skin pores, wounds, presence of moisture and sweat are other factors.



Fig. 25.29: Site and types of pilonidal sinus.

- It is common in hair dressers (seen in interdigital clefts), jeep drivers.
- It is common in 20-30 years of age. It is common in males and mostly affects hairy men.



Fig. 25.30: Typical site of pilonidal sinus in the sacral region. Note the primary and secondary sinuses.



Fig. 25.31: Recurrent pilonidal sinus. 25-40% of pilonidal sinuses can recur.

Commonest site: Interbuttock sacral region.

Pathology



Fig. 25.32: Specimen of typical excised pilonidal sinus. Note the tuft of hair.

Hair penetrates the skin
↓
Dermatitis
↓
Infection
↓
Pustule formation
↓
Sinus formation
↓
Hair gets sucked into the sinus by negative pressure in the area
↓
Further irritation and granulation tissue formation
↓
Pus forms
↓
Multiple discharging sinus

Primary sinus occurs in the midline.
Secondary sinus occurs laterally (paramedian).

Note:

Theories like Preen gland, medullary canal vestige, traction dermoid, inclusion dermoid are no longer accepted. Now it is considered as acquired condition.

Remember about pilonidal sinus

- Congenital theory is no longer considered; it is an acquired entity
- Hair follicles have never been demonstrated in the wall of the sinus (only hairs have found)
- Number, sharpness, nature, shape of hairs; depth and narrowness of the natal cleft; friction movements; nature of the skin, moisture and sweating are the factors predisposing pilonidal sinus
- Hair need not be local, tract always traverses cephalad
- Male preponderance—74%, male sex hormone effect, hairy body, more sweat and maceration
- Occurs in young—20-29 years, who are having active pilosebaceous glands
- Dark haired—stiff hairs, rare in Negroes
- Obese and overweight—deep natal cleft
- Prolonged sitting
- Many procedures for treatment are available with each one having their own advantages and disadvantages



Fig. 25.33: Pilonidal sinus—primary and secondary sinuses are clearly seen.

Clinical Features

- *Discharge*—either sero sanguinous or purulent.
- *Pain*—throbbing and persistent type.
- *A tender swelling* seen just above the coccyx in the midline *(primary sinus*); and on either sides of the midline *(secondary sinus*).
- Tuft of hairs may be seen in the opening of the sinus.
- Presentation may be *as an acute* exacerbation (abscess), or as a *chronic one.*
- It causes recurrent infection, abscess formation which bursts open forming recurrent sinus with pain, discharge and discomfort.

Complications

- Chronic pilonidal sinus can cause occasionally sacral osteomyelitis, necrotising fasciitis and rarely meningitis.
- It is not a life threatening condition but often it can be a morbid disease because of high recurrence rate.

Treatment

In acute phase initially—drainage of the abscess and antibiotics; later definitive treatment is undertaken.



Figs 25.34A and B: Pilonidal sinus—operative jack knife position.

Definitive treatment:

- In prone position (*jack knife* position, i.e. prone with buttocks elevated) excision and primary closure is done under general anaesthesia or local anaesthesia. All sinus tracks, unhealthy granulation tissues with hairs are removed completely. Methylene blue is injected to demonstrate the multiple tracks properly.



Figs 25.35A to G: Rhomboid-Limberg flap for pilonidal sinus. It gives good result.

- Excision and skin grafting—has got high recurrence rate.
- Excision with Z plasty—good result.
- Excision with multiple Z plasty.
- Karydakis excision through a semilateral incision and lateralised suturing of the wound away from the midline gives good result.
- Excision with closure using Limberg (Rhomboid) buttock flap (single or double rhomboid flaps)—good result.
- V-Y gluteal advancement flap.
- *Bascom technique* of excision through lateral approach is a good method. Through small lateral incision or multiple small lateral incisions 2-4 mm sized sinus is approached and pus is drained; hairs are removed with only minimal excision of sinus done. Cavity walls are not excised. Lateral small wounds are either sutured or left open for spontaneous healing.
- *Lahey and Cattell's relaxing skin incisions* on one buttock to relieve tension on main wound sutures with later closure of secondary wounds by sutures or advancement.
- *Davies and Starr buttock skin flap rotation* into the defect and secondary defect is closed at a later period.
- After excision of entire sinus completely, wound is left open to granulate and heal by epithelialisation with regular dressings.
- *Buie's marsupialisation of the sinus track*—after making incision on the sinus track, edge of the laid opened area is sutured to the skin edge all round using silk or vicryl. This reduces healing time and promotes healing.
- *Lord and Millar's limited excision of primary track* for 0.5 cm depth with removal of tuft of hairs, debris and unhealthy granulation tissue using tiny brush and nylon bristle.
- *Injection of phenol to the track* destroys the epithelium after removal of the tufted hairs. Phenol is allowed to be in contact with epithelium for 3 minutes to create a blanch in the track orifice.



Fig. 25.36: 'Z' plasty is done for pilonidal sinus. It gives good result. Multiple Z plasties are also used.

Nonoperative treatment/prevention of recurrence after surgery :

- Regular shaving of natal cleft to have meticulous hair control. *Laser, depilatory cream, electrolysis* are other methods used.
- Proper perineal hygiene.

Causes for high recurrence rate

- Improper removal
- Overlooking of existing diverticulum
- Entry of new tuft of hairs
- Breakage of scar

Note: Condition has got high recurrence rate (20%)

PILES/HAEMORRHOIDS

> *If bile or phlegm be determined to the veins in the rectum, it heats the blood in the veins: and these veins becoming heated attract blood from the nearest veins, and being gorged the inside of the gut swells outwardly, and the heads of the veins are raised up, and being at the same time bruised by the faeces passing out, and injured by the blood collected in them, they squirt blood, most frequently along with the faeces, but sometimes without faeces.*
>
> —**Hippocrates,** (460-375 BC)

Piles = a ball or mass, Haemorrhoids = blood to ooze, Figs = a fruit (Anjoora).

- The word '*Haemorrhoids*' is derived from Greek word Haima (bleed) + Rhoos (flowering), means bleeding. The *pile* is derived from the Latin word 'Pila' means Ball.
- It is downward sliding of anal cushions abnormally due to straining or other causes.
- *Anal cushions* (Thomson, 1975) are aggregation of blood vessels (arterioles, venules), smooth muscles and elastic connective tissue in the submucosa that normally reside in left lateral, right posterolateral and right anterolateral anal canal.
- Piles can be mucosal or vascular (Graham Stewart, 1963). Vascular type is seen in young; mucosal is seen in old.
- *Present concept* is weakening of Park's ligament which is the lower end of the external sphincter.

Types

Internal—above the dentate line, covered with mucous membrane.
External—below the dentate line, covered with skin.
Interno-external—together occurs.



Fig. 25.37: Anatomical locations of internal and external piles.



Fig. 25.38: Parts of piles—plum coloured internal part and black cutaneous external component.

Classification I

Primary haemorrhoids: Located at 3, 7, 11 o'clock positions, related to the branches of the superior haemorrhoidal vessel which divides on the right side into two; left side it continues as one.



Fig. 25.39: Positions of haemorrhoids.

Secondary haemorrhoids: One which occurs between the primary sites.

Classification II

First degree haemorrhoids
Piles within that may bleed but does not come out

Second degree haemorrhoids
Piles that prolapse during defecation, but returns back spontaneously

Third degree haemorrhoids
Piles prolapsed during defecation, can be replaced back only by manual help

Fourth degree haemorrhoids
Piles that are permanently prolapsed

Piles begin as pedicle and it is located at the origin of the internal pile, i.e. at the level of anorectum.



Fig. 25.40: Degrees of haemorrhoids.

Aetiology

- Hereditary.
- Morphological—weight of the blood column without valves causes high pressure. Veins in the lower rectum are in loose submucosal plane, but the veins above enter the muscular layer, which on contraction increases the venous congestion below (more prevalent in patients with constipation). Superior rectal veins have no valves (as they are tributaries of portal vein) and so more congestion.
- Other causes are straining, diarrhoea, constipation, hard stool, low fibre diet, overpurgation, carcinoma rectum, pregnancy, portal hypertension (rare cause). *During pregnancy* factors causing haemorrhoids—raised progesterone relaxes the venous wall and reduces its tone, enlarged uterus compresses the pelvic vein, and constipation is common problem.



Figs 25.41A to F: Different types of prolapsed piles.

- *Bulging of haemorrhoidal plexus* (*anal corpus cavernosum, by Stelzner*) occurs due to raised luminal pressure and transmission of arterial pressure; pressure in *rectal ampullary pump* (Wannas) during straining raises the portal as well as systemic pressure causing obstruction to venous outflow causing haemorrhoids. *Disruption of suspensory tissues* which hold plexus in position (*sliding lining theory*); raised *basal anal pressure;* unsupported superior haemorrhoidal vein in the loose submucosal connective tissue in the anorectum when passes through the muscular coat gets *constricting effect* leading into congestion of haemorrhoidal plexus—are the *other theories* of haemorrhoid formation.
- *Idiopathic cause:* It is very difficult to pinpoint the cause for production of piles.



Fig. 25.42: Thrombosed prolapsed pile. Note the colour of the thrombosed pile. It is very painful and tender.

An arterial pile is haemangiomatous condition of superior rectal artery entering the pedicle of internal haemorrhoid which will bleed profusely.

Clinical Features

- The *prevalence rate* of piles is 4.4% in the world, in about 10 million people.
- It may occur at any age but mostly seen in the age between 30 to 65 years.
- Incidence is equal in both the sexes.
- *Bleeding*—1st symptom—'Splash in the pan'—'bright red and fresh'—occurs during defecation.
- Mass per anum.
- Discharge—a mucoid discharge.
- Pruritus.
- Pain—may be due to prolapse, infection or spasm.
- Anaemia—secondary.
- On inspection, prolapsed piles will be visualized.
- On P/R examination, only thrombosed piles can be felt.
- Through *proctoscopy,* exact position can be made out as a bulge into the proctoscope.
- Points to be noted during proctoscopy:
    - The numbers, degrees and size.
    - The surface and appearance of piles.
    - Features chronicity of the prolapse.



Fig. 25.43: Proctoscopic view of the internal pile (grooved proctoscope).

Causes for bleeding per anum	
Piles	Carcinoma rectum
Fissure-in-ano	Carcinoma colon
Polyps	Diverticulitis
Ulcerative colitis	Intussusception
Amoebic colitis	Vascular anomaly of the colorectum
Fistula-in-ano	Mesenteric ischaemia

    - One should look for other rectal lesion such as external tags, anal papillae and fissure, proctitis.



Figs 25.44A to C: Different positions of piles and parts.

We do not see things as they are, we see them as we are.

  - Any gynaecological, genitourinary or abdominal conditions like—carcinoma of rectum, polyps, tumours, features of ulcerative colitis should be identified.
  - Presence of other discharge like blood, pus, mucous.
- Sigmoidoscopy or colonoscopy or barium enema should be done if there is any suspicion of associated malignancy.

Differential Diagnosis

- Carcinoma.
- Rectal prolapse.
- Perianal warts.

Investigations

- Haematocrit.
- Colonoscopy to evaluate proximally for any cause.
- Barium enema X-ray.

Complications

- Profuse haemorrhage which may require blood transfusion.
- Strangulation—piles is being gripped by anal sphincter.
- Thrombosis—piles appear dark purple/black, feels solid and tender.
- Ulceration.
- Gangrene.
- Fibrosis.
- Stenosis.
- Suppuration, leads to perianal or submucosal abscess.
- Pylephlebitis (Portal pyaemia) is rare, but can occur in 3rd degree piles after surgery.

Treatment

Preventive	*Therapeutic/curative*
Diet—more fibre/liquid Laxatives	**Medical**—local applications; sitz bath, diet, laxatives, drugs—analgesics **Parasurgical** • Sclerotherapy • Banding • Cryotherapy • Infrared coagulation (IRC) • Laser therapy • Doppler guided haemorrhoidal artery ligation (DGHAL) **Surgical** • Open haemorrhoidectomy • Closed haemorrhoidectomy • Stapled haemorrhoidopexy • Anal stretching—Recamier, Lord's

1. ***Nonoperative:***

- *Sitz bath*—means the patient has to sit in warm water with the anal region dipped in water for 20 minutes, 2-3 times a day.This reduces the oedema, pain and promotes healing.



Fig. 25.45: Prolapsed, strangulated piles.

- *Local applications* to reduce pain, itching and oedema can be used.
- Antibiotics, laxatives, anti-inflammatory drugs are beneficial.
- Fibre diet 35 gram/day, plenty of water. *Fibre alternatives* (bulk-forming agents e.g. ispaghula husk, sterculia, methylcellulose) can be used to supplement a high-fibre diet; squatting position may reduce the incidence of piles; plenty of liquid intake.
- *Laxatives* such as lactulose solution which soften bowel motions and relieve the constipation. Bulk laxatives such as psyllium mucilloid, Konsyl or polycarbophil may be necessary.

2. ***In case of inflamed, permanently prolapsed, oedematous piles,*** initially, manual stretching of the anal canal sphincter is tried. This prevents congestion of anal cushions and relaxes the anal sphincter, as a result of which the prolapsed piles gets reduced—*Lord's dilatation (8 fingers)*. Once oedema subsides, in 1-2 weeks, formal procedure is done.

Complications of anal dilatation (3-4 fingers dilatation)

- Incontinence—rectal—usually temporary
- Infection
- Haemorrhage/haematoma
- Prolapse rectum

3. ***Injection-Sclerosant therapy*:**

- It is done in 1st degree and early 2nd degree piles (internal)—outpatient procedure.
- Using proctoscope and Gabriel syringe, 3-5 ml of 5% phenol in almond oil is injected into the submucosal plane just above the anorectal ring to the pedicle. All three piles can be injected separately—3-5 ml to each site in single sitting. Technique can be repeated after 6 weeks. This technique is not done in the presence of sepsis or prolapse.
- The drug causes fibrosis in the submucosal region (sclerosis leading to mucosal fixation on to deeper planes and occlusion of lakes) and thereby fixation of the anal cushions which do not prolapse, causes strengthening of the vessel wall and obliteration of the vessel lumen.
- It is quick and painless; gives 95% cure rate in 1st degree piles; done on OP basis.

- *Contraindications are*—thrombosed/prolapsed piles, presence of proctitis/fissure/fistula-in-ano, pregnancy and diabetes mellitus.
- Sclerotherapy has not gained popularity, oily solution is difficult to handle and inject.
- *Complications*—recurrence (15%), hypochondriac pain due to entry of drug into the portal system, tenesmus, mucosal sloughing/ulceration, submucosal abscess, anal canal pain, anal stricture.
- Inadvertent deep injection can precipitate pelvic abscess, prostatitis, impotence, rectovaginal fistula.



Fig. 25.46: *Gabriel syringe*—It is used for injection sclerotherapy for internal piles using 5% phenol in almond/olive oil (almond/vegetable oil acts as a vehicle which holds phenol for long period of action). It is a stainless steel syringe with two metallic finger brims near the proximal end. One more metallic finger brim is present on the proximal end of the piston to place thumb while injecting.



Fig. 25.47: *Barron's band* instrument for 1st and early 2nd degree piles.



Fig. 25.48: Cryosurgery instrument set up for cryohaemorrhoidectomy.

4. ***Barron's banding:***

- It is done for 2nd degree piles. It causes ischaemic necrosis and piles fall off.
- At one time only two piles can be banded. Repeat banding can be done only after 3 weeks.
- Band should be placed 2 cm above the dentate line.
- Usually 2 bands are used for pile mass to take care of breakage. Tissue sloughs off in 1-2 weeks leaving an ulcer which heals by scarring.
- Equipment is inexpensive, simple to perform; done without anaesthesia on OP basis; results are consistent, stops bleeding and tackles the prolapsing anal cushion.



Fig. 25.49: Cryo instrument for cryosurgery.



Fig. 25.50: Cryosurgery for piles. Note the probe, grooved proctoscope, freezing the internal pile mass.

- It is contraindicated in fissure/fistula/proctitis.
- *Complications*: if applied low into skin it causes severe pain; discomfort; secondary haemorrhage, ulceration.

Note:

Suction banding is used presently. Suction is used to suck the internal pile into the banding gun.

5. ***Cryosurgery:***

- Using nitrous oxide (–98°) or liquid nitrogen (–196°), extreme cold temperature is used to coagulate and cause necrosis of piles which gets separated and falls off subsequently.
- It is relatively painless and can be done on OP basis.
- All masses can be tackled at one sitting.
- This is carried out with the help of a *cryoprobe*. Nitrous oxide is preferred since it produces adequate freezing. Nitrous oxide delivery system/cryoprobe does not require special rewarming circuit. Liquid nitrogen produces quick destruction and damage of sphincter muscle; also needs special rewarming circuit for its release and is costlier.
- The patient is put in lithotomy position; cryoprobe is applied in the longitudinal axis of internal pile above the dentate line; the pressure must be maintained above 700 lb continuously; the rapid adhesion with freezing (white area formation on piles) occurs; traction and slight rotation in both directions is done to draw entire pile mass

Life is ten percent, to make it and ninety percent, how you take it.

to come in contact with the probe; when entire tissue is frozen in 20-30 seconds, the probe is detached after warming (defrosting/thawing). Procedure is repeated on other pile masses.

- *Advantages*: It is reasonably painless, simple, safe, can be done on OP basis, with less bleeding.
- *Disadvantages:* It causes *profuse watery discharge*, itching, pain if skin is frozen; marked oedema of adjacent skin, incontinence occasionally.

6. ***Infrared coagulation:***

- Here heat is used to burn the piles so as to allow it to fall off.
- Pulses of infrared radiation are applied through a handheld applicator. The specific infrared wavelengths produce chemical changes that cause blood coagulation within the haemorrhoid itself, which causes the haemorrhoid to seal, shrivel, shrink or slough off. Source of infrared rays of 14 volt Wolfram halogen lamp with a gold plated reflector rays are transmitted from fiber optic cable which terminates in a probe or pistol for coagulation.
- In left lateral position, the probe is applied at the base of pedicle above the dentate line and bursts are given in clover leaf fashion. Timer is set at 2 secs giving a depth of 2 mm; total time taken 2-5 minutes. It is done in 1st, 2nd, and 3rd degree piles.
- It produces a discrete area of necrosis (coagulates tissue proteins and evaporates water from the cells) which heals to form a scar; reduces or eliminates blood flow through the haemorrhoid thereby shrinking it and mucosa becomes fixed to the underlying tissue.
- Often 3 or 4 sittings are needed at 1 month intervals.
- It does not cause noncontact coagulation; does not cause interference with electromagnetic devices such as pacemakers. It is *contraindicated* in external pile, proctitis. Long-term results are not good. Equipment is expensive; multiple sessions are needed.

7. ***Laser therapy for piles***—for 3rd degree piles.

- Nd-YAG , diode and carbon dioxide lasers can be used but are expensive and tedious.
- The intense beam of light interacts with tissue and can be used to cut, coagulate or ablate the tissue, sealing off nerves and tiny blood vessels can be done by laser beam. By sealing superficial nerve endings patients have minimum postoperative discomfort. Laser is used for dissecting and excising pile masses.
- It is done for internal haemorrhoids.
- *Advantages*—less operative time; less intraoperative and postoperative bleed and pain; rapid healing; quick recovery; done under LA/SA; less complications; minimal pain, constipation and urinary retention.
- *Disadvantages*—needs skill; sphincter should be taken care of; non contact burning can occur; secondary haemorrhage can occur due to heat tissue destruction; and also injury to sphincter can occur.



Figs 25.51A to C: Laser surgery for piles—CO$_2$ laser and diode laser.

8. ***Doppler guided haemorrhoidal artery ligation (DGHAL)***

- DGHAL is an advanced instrument that works under Doppler guided ultrasound. It is painless, 20-minute procedure that cures all degrees of haemorrhoids. It causes choking and blocking of the blood supply of piles. It is done using proctoscope with an incorporated Doppler probe.
- This proctoscope is inserted and used to locate the haemorrhoidal arteries by an audible signal. Once located, a needle holder is inserted into the lumen of the proctoscope and the artery ligated with a 'figure of eight' absorbable suture into the submucosa. The procedure is repeated until no more Doppler signals are identified.
- Advantages: Anaesthesia is not needed; blood loss, pain, residual problems are minimal; done as day care surgery; early return for work; may be safe in diabetic, cardiac, old age patients, and in pregnancy.
- It is under trial and too early to confirm the efficacy.

9. ***Stapled haemorrhoidopexy (Antonio Longo)***

- It is circumferential excision of the mucosa and sub-mucosa 4 cm above the dentate line using circular haemorrhoidal stapler passed per anally (MIPH—minimally invasive procedure for haemorrhoids).
- *Advantages* are—it is less painful; less blood loss; faster recovery; short hospital stay and equally efficacious.
- It is done only for prolapsed piles.



Figs 25.52A and B: Stapler haemorrhoidopexy. It is minimally invasive procedure for haemorrhoids. It is high mucosal rim excision including vascular pedicles using circular (single use) staplers. It is done for prolapsed piles.

  - This procedure avoids wound in the sensitive peri of anal skin thereby reducing the postoperative pain. Using stapling gun, a unique circular stapler which reduces the degree of prolapsed piles by excising a circumferential strip of mucosa from the proximal anal canal. The strip of mucosa and sub mucosa is excised circumferentially above the dentate line. The veins leading to the haemorrhoids are thus incorporated in this excision. Activation of the gun also simultaneously recovers the cut mucosa and sub mucosa by stapling the edges together.
  - *Disadvantages*—need for experience in advanced surgical skill; costlier; may cause a full-thickness excision of the rectal wall; may injure the anal sphincter. *Improper purse string* can cause incomplete doughnut leading to severe haemorrhage.
  - *Contraindication*: Associated anorectal disease like fissure, fistula in ano.

***Note*:**
Doughnut should be *sent for histology* for muscular layer; proper doughnut should not contain muscular layer.

10. ***Open operative methods: Still gold standard.***

Indications

- 3rd degree piles
- Failure of nonoperative methods
- Fibrosed piles

Haemorrhoidectomy is the best treatment for haemorrhoids The haemorrhoidectomy is performed using an open or closed technique. The open technique is commonly used in U.K. and is known as *Milligan-Morgan operation*. The *closed technique (Hill Ferguson)* is more popular in U.S.A. Both involve ligation and excision of the haemorrhoid, but in the open technique the anal mucosa and skin are left open to heal by second intention, and in the close technique the wound is sutured. Efficacy of surgery is 95% with 2-5% recurrence rate.

Methods are:

- *Ligation and excision of piles*—commonly done procedures *(Milligan-Morgan) (Open method).*
  - Under anaesthesia, in lithotomy position, initially the sphincter should be dilated to reduce the postoperative pain. Later skin is held with Allis forceps, internal pile is held with artery forceps. Skin is cut in "V' shaped manner and internal sphincter is separated and pushed up. Pedicle is transfixed with vicryl or catgut and distal part is excised. All the three piles can be dealt in a single sitting.
  - Postoperatively**,** *sitz bath*, antibiotics, laxatives, analgesics, local applications are given. Often few finger dilatation of the anal canal is required to prevent stenosis.
- *Submucosal haemorrhoidectomy of 'Parks'*—approach is above the skin through submucosal plane.
- *Hill-Ferguson closed method*: Here patient in prone position, under GA/caudal anaesthesia, retraction is done using Hill-Ferguson retractor. Incision is made around pile mass, pedicle is dissected to its proximal base; it is ligated with transfixation using 2 zero vicryl or silk; mucosa and anal skin is sutured using 3 zero vicryl/dexon after proper haemostasis using cautery.

One cannot love what he cannot respect, whether it be himself or another.



Fig. 25.53: During haemorrhoidectomy, skin part is held with Allis forceps; internal pedicle is held with artery forceps. A 'V' cut is placed over the outer skin up to mucocutaneous junction. Dissection is deepened to visualise the internal sphincter. Once pedicle is dissected, it is transfixed using vicryl suture material. Distal tissue is excised. Technique is repeated on other sites also.

Postoperative complications

- Pain—due to spasm, nerve irritation, muscle injury
- Retention of urine—commonest—50%
- Reactionary or secondary haemorrhage
- Anal stricture
- Anal fissure
- Recurrence
- Anal discharge for sometime
- Incontinence for faeces or gas
- Ectropion (Whitehead deformity)

11. ***Management of strangulated/thrombosed/gangrenous piles*:** Here initially conservative treatment is done using warm water sitz bath; antibiotics; elevation; bed rest; saline compression dressing; analgesics. This reduces the oedema and piles shrink. Later in 4-5 days haemorrhoidectomy is done. Doing haemorrhoidectomy immediately may precipitate portal pyaemia and also increases risk of developing anal stricture.
12. ***Newer methods*:** Using ultrasound or controlled electric energy (Harmonic scalpel or ligasure), haemorrhoidectomy can be done with less postoperative pain. But tissue charring may precipitate secondary haemorrhage.

EXTERNAL PILES

Causes

- As a part of internal piles.
- Sentinel pile associated with anal fissure.
- Anal skin tags.

Treatment

- The cause is treated.
- Sitz bath.
- Excision.



Fig. 25.54: Typical external pile. It causes haematoma, abscess, pain, itching.

Problems

- Pruritus ani.
- Perianal haematoma.
- Perianal abscess formation.

ANAL FISSURE (FISSURE-IN-ANO)

- It is an ulcer in the longitudinal axis of the lower anal canal.
- Commonly it occurs in the *midline, posteriorly (more common in males),* but can also occur in the midline anteriorly (more common in females)**.**
- 95% of anal fissures in men are posterior; 5% are anterior. 80% of anal fissures in females are posterior; 20% are anterior. Anterior anal fissure is common in females.
- It is superficial, small but distressing lesion.
- Fissure ends above at the *dentate line***.**



Fig. 25.55: Anatomy of anal canal with fissure-in-ano. It is commonly posterior.

Internal Sphincter

- The internal sphincter is formed from a thickening of the smooth muscle of circular coat of upper end of anal canal.

Circular muscle is the continuation of the inner coat of the rectum. This involuntary muscle commences where the rectum passes through the pelvic diaphragm and ends just within the anal orifice, where its lower border can be felt.

- The internal anal sphincter is 2.5 cm long and 2 to 4 mm thick. The internal sphincter is closed by a sheath of striped muscle.
- Spasm and contracture of this muscle play a major part in fissure and several other anal infections.

External Sphincter

It can be divided into three parts—deep, superficial and subcutaneous portion. It is considered to be one muscle.

- Deep part encircles the upper end of anal canal and has no bony attachment.
- Superficial part is attached posteriorly to the coccyx, anteriorly inserted into the mid-perineal point in the male, in female it fuses with the sphincter vagina.
- Subcutaneous part encircles the lower end of the anal canal and has no bony attachment.

Causes

- Because of the curvature of the sacrum and rectum, hard faecal matter while passing down causes a tear in the anal valve leading to posterior anal fissure.
- Anterior anal fissure is common in females due to lack of support to pelvic floor.
- Hard stool; diarrhoea; *increased sphincter tone; local ischaemia;* trauma; sexually transmitted diseases.
- *Other causes*—haemorrhoidectomy, Crohn's disease, venereal disease, ulcerative colitis, tuberculosis.

Types

- Anal fissure can be *acute or chronic*.

Acute Anal Fissure

- It is a deep tear in the lower anal skin with severe sphincter spasm without oedema or inflammation.
- It presents with *severe pain and constipation*.

Chronic Anal Fissure

- It has got inflamed, indurated margin with scar tissue.
- Ulcer at its inferior margin is having a skin tag which is oedematous, acts like a guard—*sentinel pile.*
- Proximally *hypertrophied anal papilla* is observed.
- It can cause repeated infection—fibrosis—abscess formation—fistula formation.
- Chronic fissure is less painful than acute one.
- Multiple fissures are seen in inflammatory bowel disease, homosexuals and venereal diseases.
- Chronic fissure can cause *complications* like—abscess, fistula formation.



Fig. 25.56: Chronic fissure-in-ano with ulcer and sentinel (pile) skin tag.



Fig. 25.57: Parts of chronic fissure-in-ano. Ulcer in the lower anal canal; sentinel pile below and hypertrophied papilla above.



Fig. 25.58: Fissure-in-ano with sentinel pile.



Fig. 25.59: Lateral fissure-in-ano.

Clinical Features

- Common in middle aged women, not in elderly.
- Pain is severe in nature in acute type, whereas less severe in chronic.
- Constipation, bleeding and discharge.
- P/R examination and proctoscopy is not possible in acute fissure-in-ano. General anaesthesia is required for examination.
- In chronic fissure, ulcer is felt with button like depression, induration and often sentinel pile.

Differential Diagnosis

- Carcinoma anal canal.
- Inflammatory bowel disease.
- Venereal diseases.
- Anal chancre (painful).
- Tuberculous ulcer.
- Proctalgia fugax.

Treatment

General measures for anal fissure

- Adequate fluid intake (6-8 glasses of liquids)
- Fiber rich diet (vegetables, fruits, brown rice)
- Bulk forming agents (psyllium husk, bran)
- Stool softeners (lactulose)
- Local anaesthetic agents (lignocaine 5%)
- Sitz bath
- Avoid constipation
- Once recovers, regular anal dilatation

***In an acute* case**

- *Lord's dilatation* is done under G/A to relax the sphincter. It is the *manual dilatation* (Lord, 1969) of the anus under general anaesthesia with relaxation using *four fingers of each hand* (*8 fingers*) to cause vigorous stretching of the anal canal to break the circular constricting band in the wall of the anorectum.
- Later, use of laxatives, xylocaine surface anaesthetic application, and anal dilatation with finger can be carried out for certain period**.**
- Bed rest; 2% nifedepine ointment.
- *Stretching of the anal sphincter* (Recamier, 1829) using *two fingers of each hand* (*4 fingers*) under anaesthesia is also an alternative one. It is better than Lord's dilatation as complications are less.

For chronic fissure

- *Dorsal fissurectomy with sphincterotomy* is done under anaesthesia. Specimen should be sent for biopsy to rule out carcinoma, tuberculosis, etc. Here transverse fibres of internal sphincter is divided in the floor of the fissure.
- *Lateral anal sphincterotomy*
  - Here internal sphincter is divided partially away from the fissure either in right or left lateral positions (also gives a good result).
  - Here *closed or open methods* (Notaras) are used. Sphincterotomy is done below the dentate line. In *closed method* no 11 blade is inserted into the intersphincteric groove to pass upwards. Blade is moved medially to cut lower 1/3 or 1/2 of the internal sphincter. In *open method* skin is incised laterally, external to anal verge. Hypertrophied band of lower part of internal sphincter is dissected and divided. Wound is left open.
  - Haematoma, perianal abscess, bruising, fistula, incontinence are the complications of lateral sphincterotomy.
- Topical nitroglycerine 0.2% is also used to relax the sphincter. It causes severe headache.
- Botulinum toxin 25 units injected into the internal sphincter. It causes temporary denervation of the internal sphincter; reducing its tone, improving the blood supply and control of ischaemia. It causes temporary incontinence for flatus (10%).
- Diltiazem (2%), L arginine are the other agents used.
- Regular anal dilatation is also often important to prevent recurrence.

SENTINEL PILE

('sentinel' means guard)

- It is commonly associated with *Fissure-in-ano* of chronic type wherein, in the lower part of fissure, skin enlarges and appears like guarding the fissure.



Fig. 25.60: Perianal haematoma—it should be drained to remove clot. Small haematoma may resolve on its own. Larger one if not drained will form an abscess.

- It can cause perianal haematoma, abscess formation, discomfort.
- The chronic fissure is treated along with excision of the sentinel pile.
- There may be low grade *infection* and *lymphatic oedema*. Haematoma/abscess can develop in it.



Fig. 25.61: Lithotomy position used for all perineal surgeries like for fissure, piles, fistula, and APR.



Fig. 25.62: *Sitz bath* is used after perineal surgeries like for piles, fissure, and fistula. Patient sits in warm water bath with perineum dipped in the water. Often small quantity of antiseptics or $KMNO_4$ is added.

ANORECTAL ABSCESS

- Most common causative organism is *E. coli (60%)*. Others are *Staphylococcus, Bacteroides, Streptococcus, B. proteus.* Commonly occurs due to infection of anal gland in perianal region. 95% of anorectal abscesses are due to infection of anal glands in relation to crypts—*cryptoglandular* disease.
- Common in diabetics and immunosuppressed.



Fig. 25.63: Anatomy of anorectal abscess.

- **Other causes:**
  - Injury to anorectum.
  - Cutaneous infection (e.g. Boil).
  - Blood born infections.
  - Many anorectal abscesses are associated with anal fistulas.
  - Fissure-in-ano.
  - Perianal haematoma.
  - Post anorectal surgery.
  - Crohn‘s disease.
  - Tuberculosis.

Differential diagnosis of anorectal abscess

- Periurethral abscess
- Bartholin abscess
- Tuberculous abscess

Investigations

- MRI is the *investigation* of *choice* for anorectal abscess.
- *Perineal and anal US* is also very useful.
- Investigations relevant to specific cause may be done.
- Proctosigmoidoscopy is needed to identify secondary cause in anorectum.

Classification

1. Perianal.
2. Ischiorectal.
3. Submucous.
4. Pelvirectal.
5. *Fissure abscess* (in relation to fissure-in-ano).

Perianal Abscess (60%)

- This usually results due to suppuration of anal gland or suppuration of thrombosed external pile or any infected perianal condition.
- It lies in the region of subcutaneous portion of external sphincter.



Fig. 25.64: Perianal abscess. Note the swelling and inflammation.

Our senses don't deceive us; our judgement does.

Clinical Features

- Severe pain in perianal region with difficulty to sit.
- Tender, smooth, soft swelling in the region.



Fig. 25.65: Sites of anorectal abscess.

Treatment

- Sitz bath, antibiotics, analgesics, local application of anaesthetic agents and laxatives.
- Drainage under G/A.



Fig. 25.66: Perianal abscess showing pus oozing out.

Ischiorectal Abscess (30%)

Surgical Anatomy

Ischiorectal fossa (pyramidal shape 5 cm depth and 2 cm width) lies between anal skin and levator ani. Right and left communicates with each other. Laterally, it is related to fascia covering obturator internus; medially to levator ani and external sphincter; posteriorly sacrotubercous ligament and gluteus maximus; anteriorly urogenital diaphragm; below, the floor by skin. Above it is related to lunate fascia and pudendal neurovascular bundle in pudendal canal (Alcock's canal).

- Commonly it is due to extension of low intermuscular anal abscess, laterally through external sphincter.
- But often it can be blood or lymphatic born.
- Fat in the fossa is more prone for infection because it is least vascularised.



Fig. 25.67: Anatomy of ischiorectal fossa. Note the boundaries and Alcock's canal.

- Fossa communicates with that of opposite side through postsphincteric space and so *horse-shoe like* abscess can occur.
- It presents with tender, indurated, brawny swelling in the skin over the ischiorectal fossa with high fever.
- *Swelling is not well-localised and fluctuation is absent in ischiorectal abscess.*

Treatment

Under G/A in lithotomy position, through a cruciate incision a portion of skin is excised (de roofing) and pus is drained. Pus is sent for C/S and presence of any internal opening to rectum should be looked for (for possibility of an existing fistula).



Fig. 25.68: Cruciate incision is used for drainage of ischiorectal abscess.

Submucous Abscess (5%)

- It occurs above the dentate line, which can be drained with sinus forceps, through a proctoscope.
- Aching pain in the anorectum with significant perineal discomfort.
- On digital examination (P/R), tender, soft, smooth swelling in the lower rectum and anal canal.
- It may be missed clinically as there is no obvious swelling externally.
- *Treatment* is proper antibiotics; incision and drainage under general anaesthesia.

Pelvirectal Abscess

- It is situated between the upper surface of levator ani and pelvic peritoneum. It is almost like a pelvic abscess,



Figs 25.69A to C: Ischiorectal abscess drainage done under general anaesthesia. Note the cruciate incision placed and pus gushing out.

occurs secondary to appendicitis, salpingitis, diverticulitis, Crohn's.

- U/S abdomen is done to rule out the above factors.
- Treated accordingly, after thorough investigations for diabetes, Crohn's and other conditions.

Problems with anorectal abscess

- Recurrent abscess formation
- Fistula formation

FISTULA-IN-ANO

- It is a track lined by granulation tissue which connects perianal skin superficially to anal canal; anorectum or rectum deeply.
- It usually occurs in a pre-existing anorectal abscess which burst spontaneously.

Fistula-in-ano can be:

- Cryptoglandular—90%.
- Non cryptoglandular (other causes)—10%.

Cryptoglandular Hypothesis

- The intersphincteric space is the surgical plane between the internal and external sphincters and is found between the longitudinal muscle and external sphincter, where it exists as a sheet of fat containing loose areolar tissue. The fat-filled ischioanal fossa lies lateral to the sphincter complex and is traversed by a network of fibroelastic connective tissue. Proximal half of the anal canal is characterized by longitudinal mucosal folds, the anal columns of Morgagni. The distal aspect of each column is linked to its neighbour by a small semilunar fold (the anal valves), which in turn forms small pockets (the anal sinuses, or *crypts of Morgagni*). The distal undulating limit of these valves is the dentate (pectinate) line, which also marks the most distal aspect of the anal transitional zone, a histologic junction between anal squamous and rectal columnar epithelium. The dentate line lies 2 cm proximal to the anal verge and is important landmark in fistula-in-ano because the anal glands empty into the crypts that lie proximal to the valves. These glands secrete mucus to lubricate anus, and are the source of infection. These glands present in the subepithelium, internal sphincter, and two-thirds of these glands are located within the intersphincteric space. It is the infection of these intersphincteric glands that initiates the fistula in ano, known as the "*cryptoglandular hypothesis*".
- These glandular infection leads into an intersphincteric abscess due to blockage of the draining duct by infected debris. This abscess may resolve by spontaneous drainage into the anal canal or may progress to an acute anorectal abscess. Treatment of this abscess is incision and drainage; but source of infection in the intersphincteric space persists, leading into development of a fistula in ano. Acute anorectal abscess and fistula in ano are believed to be acute and chronic manifestations, respectively of the same disease.
- While most fistulas start as a *simple single primary* tract, recurrent infection eventulally causes formation of *extensions (secondary tracts)*. Extensions may be intersphincteric, ischioanal, or supralevator (pararectal). The ischioanal fossa is the commonest site for an extension. Extensions also occur in the horizontal plane known as "horseshoe" if there is ramification on each side of the internal opening.



Fig. 25.70: Anatomy of anal glands (Cryptoglands of Morgagni).

Other causes are (Non-cryptoglandular)

- Tuberculosis
- Carcinoma
- Crohn's disease
- Ulcerative colitis
- Lymphogranuloma venereum
- Hydradenitis suppurativa
- Traumatic

Plenty of lymphoid aggregates surround the anal glands, which explain the high incidence of anal fistula in *Crohn's* disease.


Rectum
Dentate line
Anal valves

Fig. 25.71: Anatomy of fistula-in-ano.

Classifications

Standard (Milligan Morgan, 1934; Goligher 1975)	***Park`s classification (1976)***
• Subcutaneous commonest • Low anal—common • Submucous • High anal • Pelvi rectal	• Intersphincteric – commonest 70% • Transphincteric 25% • Supralevator/ suprasphincteric 4% • Extrasphincteric 1%

It can be:

1. ***Low level fistulas—****these open into the anal canal below the internal ring.*
2. ***High level fistulas****—these open into the anal canal at or above the internal ring.*


1
2
3
4
5
1. Pelvi-rectal fistula
2. Submucosal fistula
3. Subcutaneous fistula
4. High-anal fistula
5. Low-anal fistula

Fig. 25.72: Classification of fistula-in-ano (*Standard classification).*


A
Intersphincteric fistula

Fig. 25.73A


B
Transphincteric fistula
C
Supralevator fistula
D
Extrasphincteric fistula

Figs 25.73B to D

Figs 25.73A to D: *Park's classification* of fistula-in-ano—(A) Intersphincteric fistula. (B) Transphincteric fistula. (C) Supralevator fistula. (D) Extrasphincteric fistula.

It can be:

- *Simple fistula* without extensions.
- *Complex fistula* with extensions.

It can be with:

- *Single external opening*.
- *Multiple external openings* which are often seen in tuberculosis, ulcerative colitis, Crohn's disease, LGV, hidradenitis suppurativa, actinomycosis.

LOW-LEVEL FISTULAS

Clinical Features

- It has a prevalence of 0.01% and is common in young adult males (2:1, male to female).
- It presents with seropurulent discharge (65%), along with skin irritation and one or more external opening may be present with induration of the surrounding skin.
- Often it may heal superficially but pus may collect beneath forming an abscess which again discharges through same or new opening.
- Ischiorectal fossa on each side, most often communicates with each other behind the anus causing *horseshoe* fistula.





Figs 25.74A and B



Fig. 25.74C

Figs 25.74A to C: Fistula-in-ano (*simple type*)—typical look and site.



Fig. 25.75: *Complex* fistula-in-ano.

Goodsall's (1900) Rule

- Fistulas with an external opening in relation to the anterior half of the anus is of *direct type.*
- Fistulas with external openings in relation to posterior half of the anus, has a curved track may be of horse-shoe type, opens in the midline posteriorly and may present with multiple external opening all connected to a single internal opening.
- *P/R examination shows indurated internal opening usually in the midline posteriorly*.
- Most of the fistulas are on posterior half of anus.
- *Probing in the ward and fistulogram* in the ward before surgery using *Lipiodol* is not advisable as it may cause



Fig. 25.76: *Goodsall's rule*. Anterior fistulas are having straight track. Posterior fistulas are having curved track with internal opening in the posterior midline.

recrudescence of inflammation. It can be done with adequate precaution. Probing is done under *general anaesthesia* gently with care without creating extensions.



Fig. 25.77: Anterior fistula-in-ano with probe in place. Anterior low fistula has got straight track. Both internal and external openings are seen.

Investigations

- Chest X-ray, ESR and barium enema X-ray.
- *If required fistulogram is done only under anaesthesia.*
- **MRI/MRI fistulogram** ideal.
- Endorectal U/S (US perineum) is useful to assess deeper plane.
- Discharge study, methylene blue dye study, biopsy.
- Colonoscopy often when ulcerative colitis/Crohn's is suspected.
- Specific blood test.

Tuberculous fistulas do not have induration, will have pale granulation tissue with watery discharge and they are most often multiple. Here, the infection occurs in lymphoid tissue over the lower part of anal canal, around anal gland opening.



Fig. 25.78: Fistulogram X-ray showing track.



Fig. 25.79: MR fistulogram.



Fig. 25.80: Multiple fistulas-in-ano. It may be Crohn's disease; carcinoma or HIV. Biopsy should be done prior to formal therapy. MRI of perineum is of great help in such patients to anatomically evaluate the fistula-in-ano.

Differential diagnosis for fistula-in-ano

- Urethral fistula in male
- Chronically infected Bartholin's gland
- Pilonidal sinus
- Hidradenitis suppurativa
- Carcinoma
- Crohn's tuberculosis, ulcerative colitis



Fig. 25.81: Probing of the fistula track during surgery to find out its inner opening.

Treatment

Principles in management	***Procedures***
• Identify the cause—cryptoglandular or other • Delineate exactly the fistula anatomy—MRI/EUS • Identify relation of fistula to anal sphincter • Drain all sites of infection • Eradicate **track** and secondary **extensions** • Preserve anal incontinence function The *primary objectives* are to eradicate the tract and drain all associated sites of infection while simultaneously preserving anal continence	• Laying open the fistula—fistulotomy with curetting • Fistulectomy • Gluing of fistula—not much useful • Mucosal flap procedure • Fistulectomy with primary repair • Fistulectomy with primary repair with episiorectopexy • Fistulectomy with secondary repair • Anal fistula plug repair (AFP) • LIFT Technique (Ligation of intersphincteric fistula track) • Seton technique (Latin—seta—*a bristle*) • Colostomy—lay open, fistulectomy, later closure of colostomy—for high type • VAAFT procedure (Video assisted anal fistula track ligation)

- *Fistulectomy*
  - Under G/A or spinal anaesthesia, probe is passed through external opening up to the internal opening which is felt as an induration. Fistula is opened along the probe using a knife. Fibrous track along with unhealthy granulation tissue and additional external openings are excised. Specimen is always sent for histopathology.



Fig. 25.82: Methylene blue injection to delineate track on table in fistula-in-ano.

  - Postoperatively—sitz bath, antibiotics, analgesics, laxatives are given.
  - *Fistulectomy for low level fistulas do not cause rectal incontinence*.
  - Proper curetting of the infected anal gland area is essential.
- *Fistulotomy*
  It is done in low anal fistula. It is technically easier. After passing the probe through the entire fistulous track, incision is made over the probe to cut and lay open the fistulous track. It is allowed to granulate and heal from the floor/surface. Technique is safer, easier and can be done on outpatient basis.
- *Advancement flaps* are used occasionally to get better result—mucosal flap procedure.
- *Gluing of the fistula* track is tried but success rate is not good. Fibrin glue is a multicomponent system containing mainly human plasma fibrinogen and thrombin. Once prepared it is injected into the fistula track which hardens in few minutes and fills the entire track. Success rate is 70%.
- *Anal fistula plug (AFP) repair*: Surgisis anal fistula plug (*porcine small intestine submucosa, SIS*) is used with 85% success rate in simple fistula. It contains naturally derived extracellular matrix which acts as scaffolding, ingrowth of tissue, remodeling.
- *LIFT technique* (Ligation of intersphincteric fistula track): Under anaesthesia in lithotomy position, intersphincteric space is reached through a transverse incision. Fistula running across is identified and ligated using vicryl on either side. Part is excised; outer part is curetted through external opening.
- *VAAFT procedure* (Video assisted anal fistula track ligation): Fine specialized endoscope is passed through the outer opening into the fistula track; with continuous irrigation fistula track is cleaned and wall is cauterized. Inner opening is ligated through vicryl from luminal side.

His heart cannot be pure whose tongue is not clean.

HIGH-LEVEL FISTULAS

- Its upper opening is at or above the anorectal ring. It is difficult to treat.

Common causes are:

- Crohn's disease
- Ulcerative colitis
- Trauma
- Carcinomas
- Foreign body

- Incontinence may follow after lay opening of these fistulas.

Investigations

- Barium enema X-ray, colonoscopy, chest X-ray, biopsy.

Treatment

- Requires staged procedure—*initial colostomy* is done followed by definitive procedure. This prevents sepsis and promotes faster healing.
- Later closure of colostomy is done.

Seton Technique

- A *silk or linen ligature* is passed across the fistula and left in place with a tie.
- *Striated muscle* superficial to fistula track is encircled with Seton material and tied securely and left *in situ* to create ischaemic necrosis, dividing the muscle slowly without allowing it to spring apart avoiding gutter deformity. Even though internal sphincter is divided in this, causing adequate laying open of entire fistula track, it will well-preserve the sphincter function and pressure.
- This allows the fistula to granulate and heal from above and to close completely. Usually takes longer duration to heal.
- It is done for intermediate and intersphincteric fistula. It is used prior to definitive procedures like fistulectomy or advancement flap.



Fig. 25.83: *Seton technique* for intersphincteric fistula-in-ano. It is kept for 3 months. It can be tight or loose seton depending on the indications. It promotes formation of granulation tissue, healing by fibrosis and track recedes downwards.

- Seton can be kept for 3 months. It can be regularly replaced by new silk or any material by rail road technique without anaesthesia.
- *Two types of setons are present*.
    - Loose setons are used mainly to drain for long period in recurrent/postoperative fistulas and due to specific causes like Crohn's. There is no tension in seton.
    - Cutting setons are used when enclosed muscle is needed to cut (cheese wiring through ice effect). It is placed tight.

ANORECTAL STRICTURES

Causes

- Congenital
- Fibrotic anal fissure
- Irradiation
- Senility
- LGV (in females)
- Ulcerative colitis
- Crohn's disease
- Carcinomas
- Postoperative (surgery for piles, coloanal anastomosis)

Clinical Features

- Progressive constipation.
- On P/R examination, stricture can be felt as a tight ring.
- Features relevant of specific cause.



Figs 25.84A and B: *Anal dilator*. Many proctology surgeries require regular anal dilatation postoperatively. Note how to hold the dilator to pass into the anus after applying lubricant.

Investigations

- Barium enema X-ray, biopsy, colonoscopy

Treatment

- The cause is treated.
- Dilatation of the anal canal under general anaesthesia.
- Resection in severe recurrent cases.

CONDYLOMA ACUMINATA

- It is most common sexually transmitted anal disease. It is common in homosexual men.
- Penile warts or female genital warts may be present.
- It is caused by Human Papilloma Virus (HPV).
- Pruritus, discharge, pain and bleeding are the features.
- Pinkish white warts in anal canal, often attaining large size causing *Buschke Lowenstein tumour*.
- Large wart may block the anal canal orifice.
- Whitening occurs on applying acetic acid on it.
- Biopsy confirms the diagnosis.
- Treatment is local application of 25% podophyllin cream; surgical excision of the wart; intralesional injection of interferon α 2b.
- Malignancy should be ruled out by histology.

ANAL INTRAEPITHELIAL NEOPLASIA (AIN)

- It is dysplasia of anal or perianal epidermis.
- It is seen in individuals with HIV infection; HPV infection (16, 18); individual who do anorectal intercourse.

Classification:

AIN I—absence of keratocyte maturation and cellular atypia observed in outer 1/3rd of epithelium—low grade.

AIN II—cellular atypia observed in middle 1/3rd—low grade squamous intraepithelial neoplasia.

AIN III—cellular atypia full thickness—high grade squamous intraepithelial neoplasia.

- 30% of anal warts will show AIN.
- It is raised scaly white/pigmented/cracked lesion.
- Biopsy confirms the disease.
- Treatment: Excision; topical imiquimod, 80% tricholoro-acetic acid and oral retinoids.

MALIGNANT TUMOURS OF ANAL AREA

- *Anal malignant tumours* are < 2% of large bowel tumours. It can be below the dentate line (SCC, 80% of anal tumours); above the dentate line (Basaloid/transitional/cloacogenic).
- Causes may be HPV infection; HIV infection; AIN (Anal intraepithelial neoplasia); organ transplant recipients; immunosuppression.

Classification of tumours of anal area

It can be:
- Benign
- Malignant

It also can be:
- Tumour of the anal canal (proximal to dentate line)—SCC, adenocarcinoma, melanoma
- Anal margin tumour (distal to dentate line)—ANI, Bowen's disease, Paget's disease, BCC, anal margin SCC



Figs 25.85A to C: Anal canal carcinoma. Squamous cell carcinoma is commonest type—80%.

Types

1. *Squamous cell carcinoma* is the commonest type. Predisposing causes: Papilloma, irradiation, dermatitis, long standing fistula-in-ano.
2. Basaloid carcinoma—it is rare, non-keratinising squamous cell carcinoma. Highly malignant.
3. Muco-epidermoid carcinoma—arises near squamo–columnar junction.
4. Basal cell carcinoma.
5. Melanoma—blue/black in colour mistaken for thrombosed pile—poor prognosis (5 years—10%).
6. Adenocarcinoma from the anal glands in a pre-existing fistula-in-ano.

God gives every bird its food, but he does not throw it into the nest.

Features	*Investigations*
• Ulceration	• Biopsy from anal region
• Bleeding	• FNAC of inguinal node
• Pain, pruritus and discharge	• U/S abdomen
• Irregular indurated mass	• MRI perineum is very useful
• Anovaginal fistula in females	• *P/R is a must to assess upper extent of the growth*
• Faecal incontinence in late cases	*AJCC staging* Tis—carcinoma *in situ*
• Inguinal node—hard, nontender	T1—tumour < 2 cm T2—tumor 2-5 cm T3 —tumor > 5 cm T4—invasion into adjacent organs like vagina/urethra N1—perirectal nodes + N2—unilateral internal iliac/inguinal nodes N3—perirectal + inguinal/ iliac or bilateral nodes M 0—no distant spread M1—distant spread present
• Iliac nodes	
• Later—late constipation—obstruction	

- ***Squamous cell carcinoma of anal canal,*** usually present as a fungating or ulcerative growth, which spreads to inguinal lymph nodes.
  - Biopsy and FNAC of lymph nodes are the essential investigations.
  - *Treatment:* Wide excision of the lesion with 3 to 5 cm clearance and ilioinguinal block dissection for lymph nodes are done. Follow-up radiotherapy is also often given.
  - Nigro regime

Nigro Regime

Nigro Regime for Anal Carcinoma
(Norman Nigro, et al. 1974)

- Initial radiotherapy for 3 weeks 3000 rads (30 Gy total) to perineum and pelvis
- Then chemotherapy—5 FU, for 4-5 days; is a radiosensitizer, started on 1st day of RT as 1000 mg/m^2 continuous infusion. Mitomycin C is 15 mg/m^2 as single dose on 1st day of RT
- Later after 3 weeks abdominoperineal resection (APR)

  - ***Chemoradiation*** is becoming popular for carcinoma of anal canal.
  - Drugs used for chemotherapy are 5 FU, bleomycin, vincristine, adriamycin.
  - In advanced growths radiotherapy is the only treatment.
- ***All other tumours***: *Abdominoperineal resection with* permanent colostomy is done.

Paget's

- Paget's disease of breast
- Paget's disease of anal margin—of apocrine glands
- Paget's disease of penis
- Paget's test
- Paget's disease of bone

ANAL MARGIN TUMOURS

It is the tumour below the level of dentate line.

1. Bowen's disease.
2. Paget's disease.
3. Basal cell carcinoma.
4. Squamous cell carcinoma.
5. Verrucous carcinoma (Giant condyloma acuminatum or Buschke-Lowenstein tumour).
6. Epidermoid carcinoma (SCC; cloacogenic/transitional/ basaloid carcinoma).

SACROCOCCYGEAL TERATOMA

- It is an uncommon tumour, but most common of the large tumours in first 3 months of life.
- More common in females.
- Retention of large amount of primitive toti-potential cell in this region may be the reason for this tumour.
- It occurs between coccyx and rectum
- It is attached to coccyx, extends commonly downwards as a huge mass, occasionally upwards into the pelvis.



Figs 25.86A and B: Sacrococcygeal teratoma, typical site (*Courtesy:* Professer Suresh Kamath, MS, Mangalore).

- It is a congenital condition arising from totipotent cells.
- X-ray and CT scan are must.

Complications	*Differential diagnosis*
Ulceration	Sacral meningocele
Infection	Sacral chordoma
Urinary obstruction	Postanal dermoid
Malignant changes	



Fig. 25.87: X-ray of a patient with sacrococcygeal tumour (*Courtesy:* Professor Suresh Kamath, MS, Mangalore).



Fig. 25.88: Recurrent chordoma of sacrum.

Treatment

- Excision soon after birth.

ANAL INCONTINENCE

Continence of anal canal is maintained by two factors:

- Normal rectal and colonic pressure and activity.
- Normal pelvic floor function.

Types

- *Urge incontinence*—here rectal and colonic pressure and activity is increased but normal pelvic floor.
- *True incontinence*—here rectal and colonic pressure and activity is normal but defective pelvic floor function.
- *Full incontinence*—here rectal and colonic pressure and activity is reduced and also defective pelvic floor function.
- *Temporary*—treated by reassurance. Often seen after Lord's dilatation.
- *Permanent*—needs definitive therapy.

Causes

Causes of anal incontinence

- Denervation—spinal injury, spina bifida
- Damage—childbirth, wounds, surgeries
- Descent—rectal prolapse, perineal descent
- Debility—old age, diseases
- Destruction—RT, malignancy
- Dementia—senility, psychosis
- Deficiency—congenital anomalies

- Irritable bowel syndrome, severe diarrhoea.
- Prolapsed piles, rectal prolapse.
- Old age, malnutrition, debilitating illness.
- Congenital anomalies.
- Trauma, surgeries, injury during childbirth in females.
- Spina bifida, spinal tumours, spinal injuries and surgeries.
- Malignancy, postirradiation.
- Psychological causes.

Evaluation of the patient

- For specific causes
- Anorectal manometry
- Per-rectal examination
- Sigmoidoscopy
- Electromyography
- Defaecography
- Perineometer to assess level and angle of anorectal junction

Treatment

- Suturing of the torn sphincter.
- Repair of puborectalis muscle and plication of external sphincter.
- Encircling operations around anal canal to give support using gracilis sling or mersiline sutures.
- Electrical stimulation of the puborectalis.
- *Secca therapy*: Temperature controlled radiofrequency energy in the anal canal and distal rectum to create scarring and fibrosis of internal sphincter and adjacent tissues.

DESCENDING PERINEAL SYNDROME

- When a healthy person increases the intra-abdominal pressure and relaxes the pelvic floor muscles, there will not be any changes in the concavity of the perineum.

Diseases of the soul are more dangerous than those of the body.

- In chronic ill-patients, malnourished, and people with preprolapse, perineal descent can occur with obliteration of the normal concavity of the perineum. It is called as *descending perineal syndrome*.
- Levators got injured directly or indirectly causing weakening of pelvic floor.
- Anal canal is situated many centimeters below the pubo coccygeal line. Usually 3-4 cm low during straining.
- *Defecography* is ideal to evaluate such patients. Perineometer is also used.
- Presentations are tenesmus; incomplete evacuation; incontinence.
- *Treatment* is diet, laxatives, avoiding straining, and suppositories.
- Restoration of pelvic floor by various surgical methods may be needed often with rectal resection and suspension.
- Total pelvic marlex mesh repair; transcoccygeal posterior hitching of the rectum (Kraske); correction of cystocele, rectocele and enterocele.
- Results are *not very good* as recurrence or residual problems may persist.

PROCTITIS

It is inflammation of rectal mucosa often with the inflammation of colon and anal canal.

Types

- Acute.
- Chronic.
- Nonspecific—common.
- Ulcerative proctocolitis as part of ulcerative colitis.
- Specific
  - Bacillary dysentery.
  - Amebic proctitis—common.
  - Combined amoebic and bacillary.
  - Gonococcal proctitis.
  - Lymphogranuloma inguinale (LGV).
  - Tuberculous proctitis.
  - Bilharzial proctitis due to schistosoma haematobium.
  - Enema induced proctitis especially of herbal enemas.

Clinical features

- Pain per rectum and anum
- Tenesmus
- Passage of mucus and blood
- Frequent urge to pass stool
- Fever, loss of appetite
- Pain and tenderness in left lower abdomen
- P/R is tender

Investigations

- Sigmoidoscopy is more relevant than just proctoscopy.
- Stool study, stool culture.
- Mucosal biopsy.
- Serological tests.
- Relevant investigations like ESR, blood smear, and chest X-ray.

Treatment

- Antibiotics, antiamoebic drugs like metronidazole.
- In severe cases, retention enema using metronidazole, prednisolone, salazopyrin.
- IV fluids, IV antibiotics and IV metronidazole are often required.
- Treating the specific causes like tuberculosis, gonococcal infection and bilharzial infection.

PROCTALGIA FUGAX

- It is sudden severe recurring pain in the rectum of unknown cause with segmental pubococcygeal spasm.

Features

- It is common in young people may be due to stress, straining.
- Common at night, starts suddenly, lasts for few minutes and then subsides spontaneously.
- Pain is unbearable and severe with often constipation.
- Gradually subsides on its own.
- Occasionally, only cutting of puborectalis muscle is required but with danger of developing incontinence.

HIDRADENITIS SUPPURATIVA OF ANAL REGION

- It is a chronic suppurativa condition of apocrine glands of the skin in axilla/perineum/mons pubis/ thighs/scrotum etc.
- Apocrine gland duct obstruction → bacterial infection → multiple glands involvement → secondary infection (*Staphylococcus aureus*, streptococci) → skin oedema, multiple raised pustules → multiple communicating fistulae formation.
- Disease does not extend above dentate line or into sphincter.
- It is common in young obese females.
- Sinus; scarred areas; discharge; skin changes; pain and tenderness; foul smelling fluid are the presentations.
- *Differential diagnosis* are—Crohn's disease; fistula-in-ano; pilonidal sinus; tuberculosis; actinomycosis; LGV.
- *Treatment*:
  - Weight reduction; proper hygiene.
  - Antibiotics; analgesics.
  - Incision and drainage of abscess.
  - Laying open of all communicating tracks and regular dressing.
  - Radical local excision of entire apocrine bearing perineal skin with reconstruction using flap.
  - Recurrence is known to occur.

PRURITUS ANI

- It is intractable itching in and around anal canal.
- Skin is reddened, hyperkeratotic, cracked and moist.

Causes

- Poor hygiene.
- Anal discharge due to fissure/fistula/piles/warts/ polyp.
- Trichomonas vaginalis infection of vagina in females.
- Parasites.
- Epidermophytosis.
- Allergic cause.
- Dermatitis/psoriasis.
- Intertrigo/erythrasma (Corynebacterium minutissimum).
- Diabetes mellitus; psychological cause.

Treatment

Proper cause should be assessed and treated. Good hygiene; local steroid application; topical xylocaine; strapping of the buttocks are needed.

GASTROINTESTINAL HAEMORRHAGE (GI BLEED)

GI bleed is classified as upper GI and lower GI bleed.

- ***Upper GI bleed*** is bleeding above the level of ligament of Treitz.
- ***Lower GI bleed*** is bleeding below the level of ligament of Treitz.

  Ligament of Treitz is a fibromuscular band, which extends from right crus of diaphragm to duodenojejunal flexure with upper part made up of striped muscle fibres, lower part smooth muscle fibres and middle part with elastic fibres.



Fig. 25.89: Anatomy of ligament of Treitz.

UPPER GI BLEED

It is considered as:

- Variceal.
- Nonvariceal.

Causes

- Peptic ulcer 55%. Ulcer bleeding is precipitated by NSAIDs, steroids, alcohol. Ulcer bleeding is overall common in men. But NSAID induced ulcer bleeding is common in females. *Duodenal ulcer* (35%) more commonly bleeds than *gastric ulcer* (20%)
- Gastroduodenal erosions.
- Oesophageal varices.
- Oesophagitis and erosions.
- Carcinoma stomach—5%
- Mallory-Weiss syndrome—5-15%.
- Vascular anomalies—Dieulafoy’s syndrome (A-V malformation in the fundus of the stomach), Osler-Weber-Rendau syndrome, Ehlers-Danlos syndrome.
- Aortoduodenal fistula.
- Bleeding disorders.
- H/O drug intake—anticoagulants, clopidogrel, ecospirin.

Factors which aggravate the bleeding

- Gastric acid which inhibits the platelet aggregation
- Pepsin, by its proteolytic action causes erosion of the ulcer into the vessel. It also digests the clot, so as to aggravate the bleeding
- Mucosal blood supply pattern
- Gastric motility
- Alcohol, drugs

  Major haemorrhage occurs when erosion of gastroduodenal artery or left gastric artery or splenic artery occurs or when bleeding occurs from varices

Clinical Features

Acute Bleed

- Features of shock.
- Haematemesis.
- Melaena.

Chronic Bleed

- Hypochromic microcytic anaemia, glossitis, koilonychia, congestive cardiac failure.
- Mortality in upper GI bleed is 10%.

Investigations

- *Gastroscopy* to see the spurting vessel, oozing, clot in the ulcer, collected blood in the lumen of the stomach.
- CT angiography of coeliac trunk and SMA.
- Hb%, packed cell volume, CVP measurement, blood grouping and crossmatching. U/S abdomen.
- LFT; prothrombin time; platelet count; blood urea and serum creatinine; serum electrolytes.
- *Modified Forrest classification* (refer Chapter 20—Stomach) and *Rockall scoring system* (better) is used. In ***Rockall scoring system*** parameters used are—*age* (60 [0], 60-79 [1], > 79 [2] Years); *shock* (none [0], pluse > 100 [1],) pluse > 100 with hypotension [2]); *comorbidity* (none [0], IHD [2], renal/liver failure/advanced maligancy [3]); *condition diagnosed* (Mallory Weiss [0], all but mailigancy [1], upper GI maligancy [2]); *endoscopic finding* (none [0], dark spot, blood/clot/visible vessel [2]). *Score*: < 3 low-risk; 3-8 moderate; > 8 high.

Treatment

Treatment of upper GI bleed

- *General*
- *Medical*—**PPI**/tranexamic acid/octreotide
- *Endoscopic*
- *CT angiography guided embolisation*
- *Surgical*

- General: IV fluids, catheterisation, Ryle's tube aspiration, blood transfusion.
- Injection ranitidine IV 50 mg 8th hourly, or famotidine IV, omeprazole IV, pantoprazole IV.



Figs 25.90A and B: Bleeding peptic ulcer (duodenal ulcer) is the commonest cause of upper GI bleed. Oesophageal varix causes dangerous severe life-threatening bleed.

- Antifibrinolytics like tranexamic acid, EACA.
- Somatostatin or octreotide, *PPI infusion.*
- *Endoscopic therapy* (tamponade, laser, haemoclip, banding, sclerotherapy, etc.) is the first line of therapy in all upper GI bleed. *CT angiography guided transcatheter embolisation* of artery (gastroduodenal) is very useful in bleeding duodenal ulcer if endoscopic therapy fails. *Persistent recurrent bleeding* needs surgical intervention.
- For varices, vasopressin, propranolol, isosorbide dinitrate, Sengstaken tube tamponade, sclerotherapy, Boerema-crile operation, Hasaab operation (devascularisation with splenectomy), oesophageal transection, Siguira-Futagawa operation or TIPSS.
- For peptic ulcer, saline wash with 1 : 2,00,000 adrenaline, Nd:YAG laser therapy, cautery coagulation, thrombin injection, Finney's pyloroplasty, partial gastrectomy, ligation of gastroduodenal or left gastriartery, cytoprotectant mesoprostil injection.
- The cause is treated, once acute episode is under control.

Prognosis

- Varices and gastric ulcer bleed has higher mortality.
- Bleeding duodenal ulcer has got better prognosis.

LOWER GI BLEED

- Bleeding in the GIT below the level of the ligament of Treitz.
- Normal faecal blood loss is 1.2 ml/day. A loss more than 10 ml/day is significant.



Fig. 25.91: Causes of lower GI bleed.

Causes

- Angiodysplasia.
- Diverticular disease—commonest cause in Western countries.
- Tumours of colon or small bowel.
- Anorectal diseases—haemorrhoids, fissure-in-ano.
- Ulcerative colitis, Crohn's disease.
- Colorectal polyps; rectal carcinomas.
- Intussusception.
- Tumours, either benign or malignant of colon or small bowel.
- Meckel's diverticulum.
- Ischaemic colitis.
- Stercoral ulcer.
- Infectious colitis.
- Mesenteric artery occlusion.

Lower GI bleed can be:

- Occult bleed: > 10 ml/day but not revealed
- Overt bleed: Bleeding which is revealed
  - Overt acute
  - Overt acute massive (bleed > 1.5 litre/day)
  - Overt chronic

Common causes

- Internal piles
- Diverticular disease
- Neoplasia
- Inflammatory bowel diseases
- Angiodysplasia

Classification

I. Bleeding may be:

Small bowel bleed: Polyp', Meckel's diverticulum, mesenteric ischaemia, intussusception; small bowel tumor.

Large bowel bleed: Angiodysplasia, carcinoma, colitis, diverticulitis, carcinoma.

Anorectal diseases: Piles, fissure-in-ano, carcinomas.

II. Bleeding may be:

Congenital: Polyp's, Meckel's diverticulum.

Inflammatory: Ulcerative colitis, infective, amoebic, Crohn's disease.

Neoplastic: Adenomas, carcinomas, polyps.

Vascular: Angiodysplasia, mesenteric artery ischaemia, colitis.

Others: Piles, fissure-in-ano.

Angiodysplasia is common in caecum and ascending colon.

Bleeding more than 1.5 litres per day is called as *acute massive GI bleed.*

Acute bleed occurs in:

- Mesenteric ischaemia
- Angiodysplasia
- Ischaemic colitis
- Meckel's diverticulum
- Intussusception
- Acute episodes of ulcerative colitis

80% of acute bleed regress spontaneously
20% will become either massive or recurrent

Presentations

- Acute bleeding presents with features of shock.
- Chronic blood loss occurs in piles, fissures, colitis. Presents with hypochromic, microcytic anaemia.
- Tenesmus, subacute obstruction, loss of appetite, decreased weight, bloody diarrhoea is seen in carcinoma distal, large bowel.
- Per-rectal examination is a must which may reveal polyp, growth, ulcerations.
- Haematochezia.
- Mass palpable per abdomen in left or right iliac fossa or mass of intussusception.

- *Blood with mucus*—colitis, carcinoma
- *Fresh blood as splashes in the pan*—piles
- *Maroon coloured stool*—Meckel's diverticulum
- *Red currant jelly in stool*—intussusception
- *Bright red blood in stool*—polyps

Investigations

- Hb%, packed cell volume, ESR.
- Bleeding time; clotting time; prothrombin time; platelet count; blood urea and serum electrolytes.
- Occult blood in the stool—positive faecal blood test using Guaiac reagent.
- Barium enema.
- Proctoscopy for piles and sigmoidoscopy for rectosigmoid diseases.
- Colonoscopy for colitis, carcinomas, polyps.
- Small bowel enema (enteroclysis).



Figs 25.92A and B: Sigmoid diverticula on colonoscopy. It is the common cause of lower GI bleed in Western countries.

Use your imagination not to scare yourself to death, but to inspire yourself to life.

- U/S abdomen.
- Mesenteric angiogram is very useful investigation in acute bleed, especially in angiodysplasia.
- Technetium scan for Meckel's diverticulum.
- Capsule endoscopy.

Treatment

- Endoscopic fulguration or therapeutic embolisation or right hemicolectomy (for angiodysplasia).
- Endoscopic polypectomy for polyps.
- Treatment for ulcerative colitis with mesacol enema or drugs or total proctocolectomy with ileo-anal anastomosis.
- Surgical resection of colonic carcinoma.
- Massive resection of small bowel in mesenteric ischaemia.
- Sigmoid colectomy in sigmoid diverticula.
- Cause is treated.
- Proper exploration through a lengthy midline incision is essential.

OBSCURE GI BLEED

- It is intermittent GI bleed for which *no source has been found* endoscopically/radiologically.
- It is 5% common.
- Commonly, it is due to either missed common cause or angiodysplasia.
- If it is angiodysplasia, angiography, nuclear scintigraphy, capsule endoscopy; then angiographic embolisation or resection of the part of the bowel is done.
- Enteroscopy, upper and lower GI scopies are needed in other conditions.
- All other conditions are treated accordingly.

Investigations for GI bleed

Blood

- Haematocrit, LFT, blood urea, serum creatinine
- Serum ferritin, iron, binding capacity
- Coagulation profile—platelet count, BT, CT, PT, APTT

Occult stool blood test (1-2 ml/day)

- Benzidine test
- Guaiac test
- Haemoccult—guaiac impregnated electrophoresis paper
- Fecal test
- Immunological test

Endoscopy

- Gastroduodenoscopy
- Proctosigmoidoscopy
- Colonoscopy—often difficult in acute bleed for clarity visualisation, if bleeding point is seen it can be controlled by cautery, laser, haemoclips, injection sclerotherapy, heater probe etc. But still it becomes the test of choice once bleeding has controlled/stopped temporarily
- Small bowel endoscopy—push type (160 cm); Sonde enteroscope (275 cm, 5 mm diameter with balloon tip) are used. Entire small intestine is visualised while withdrawing but therapy or biopsy is not possible

Angiography

- It identifies when bleeding rate is 0.5 ml / min; useful in active bleed; in therapeutic embolisation, injection vasopressin can be done. Embolisation of small bowel vessel may cause bowel infarction which is dangerous and resection is needed in such situation. Visualisation in angiography can be improved by selective infusion of vasodilators like tolazoline and prostaglandins, using magnification films, using vasoconstrictor drugs
- *Angiogragraphic criteria in angiodysplasia are*—early and prolonged filling of draining veins; cluster of small arteries; visualisation of vascular tuft

Nuclear scintigraphy

- Identifies 0.1 ml/min of bleed ; *Tc sulphur colloid scan* is very sensitive and is completed in 1 hour but increased uptake in spleen and liver obscures bleeding point and needs repeated administration due to rapid clearance; *Tc labeled RBC* reciculates and so effective for 1 day with better localisation
- *Advantages are*—high-sensitivity even with active continued bleed; screening test prior to angiography
- *Problems are*—no specificity; therapy is not possible

Other methods

- *CT* angiography; *MR* angiography
- *Aortography* for aortoenteric fistula
- *Intraoperative localisation*—on table enteroscopy; on table Doppler; on table bowel lavage and colonoscopy

Chapter 26 Urology

A. Kidney

> *It is no exaggeration to say that the composition of the blood is determined not by what the mouth ingests but by what the kidneys keep; they are the master chemists of our internal environment, which, so to speak, they synthesize in reverse.*
>
> **—Homer William Smith,** 1939

CHAPTER OUTLINE

- Anatomy of Kidney and Ureter
- Plain X-ray—Kidney, Ureter and Bladder
- Intravenous Urogram
- Retrograde Pyelography
- Renal Angiogram
- Micturating Cystourethrography
- Ascending Urethrogram
- Isotope Renography
- Cystoscopy
- Catheters
  - Foley's Catheter
  - Malecot's Catheter
  - Red Rubber Catheter
- Nephrostomy
- Suprapubic Cystostomy
- Haematuria
- Horseshoe Kidney
- Cystic Diseases of the Kidney
  - Polycystic Kidney Disease
  - Solitary Renal Cyst
- Duplication of Renal Pelvis and Ureter
- Retrocaval Ureter
- Uretrocele
- Injuries to Kindney
- Renal Tuberculosis
- Hydronephrosis
- Pyonephrosis
- Carbuncle of Kidney
- Perinephric Abscess
- Renal Calculus
- Ureteric Calculi
- Staghom Calculus
- Benign Tumours of Kidney
- Wilm's Tumour
- Renal Cell Carcinoma
- Approaches to Kidney

ANATOMY OF KIDNEY AND URETER

KIDNEY—ANATOMY

- They are a pair of excretory organs situated retroperitoneally, on the posterior abdominal wall; one on each side of vertebral column.
- Vertically it extends from the upper border of T_{12} vertebra to the centre of the body of L_3 vertebra. The right kidney is slightly lower than the left, left kidney is slightly nearer to the median plane.
- Each kidney is about 11 cm long, 6 cm broad, 3 cm thick. Lateral border is convex. Medial border is concave with a hilum. Structures seen in the hilum are (from anterior to posterior)—(1) renal vein, (2) renal artery, (3) renal pelvis.
- Upper pole is related to suprarenal gland; lower pole lies 1 inch above the iliac crest.
- Capacity of renal pelvis is 10 ml.
- The angle between the 12th rib and the outer border of the sacrospinalis is the kidney angle. Kidney pain is usually referred here and pressure over this point elicit pain in kidney lesions.

- Hepatorenal pouch is a peritoneum lined deep recess, related to the upper pole of kidney. It is the lowest site when the body is in horizontal position, excluding the pelvis. Collection of extravasated fluid is likely to occur in this pouch following surgeries to liver and biliary tract.

Capsules of Kidney

1. Proper capsule—fibrous membrane which can easily be stripped off from the organ.
2. Perirenal fat is in the space of Gerota.
3. Renal fascia of Gerota—has got anterior layer *(Fascia of Toldt)* and posterior layer *(Fascia of Zuckerkandl)*.
4. Pararenal body of fat.

Structure of Kidney

Gross

Coronal section shows outer brownish cortex, inner pale medulla, renal sinus.

Renal sinus is a space that extends into the kidney from hilus. It contains (1) branches of renal artery, (2) branches of renal vein, (3) renal pelvis.

The pelvis divides into 2-3 major calyces which in turn divides into 7-13 minor calyces.

Histology

Each kidney is composed of 1-3 millions of uriniferous tubules; each of which has a collecting part *(collecting tubules)* and secretory part *(nephron)*.

Blood Supply

It is from renal artery, which arises from the aorta at right angles, at the level of intervertebral discs between L_1 and L_2 vertebrae. About 95% of abdominal aortic aneurysm arises below the level of origin of renal artery.



Fig. 26.1: Segments of kidney.

The kidney is divided into anatomic segments based on blood supply. In the hilum, the main artery, divides into anterior and posterior divisions. The anterior division supplies the apical, upper, middle and lower segments; posterior segment is supplied by the posterior division. The knowledge of this is important in the operation of anatrophic nephrolithotomy, where a functionally *avascular plane* (*Brodel*) between the posterior segment and the upper and middle segments exist on the posterior half of the kidney, about two-thirds of the way from the hilum to the lateral margin of the kidney.

Nerve Supply

$T_{10,11,12}$ through the lesser and lower splanchnic nerves.

Lymphatics

They are drained into para-aortic nodes. Perinephric fat is removed during nephrectomy (for malignancies), as intrarenal lymphatics freely communicates with the plexus in the perinephric fat.

URETER—ANATOMY

- Each ureter is 25-30 cm long. It begins within the renal sinus as a funnel shaped dilatation called renal pelvis.
- It enters the bladder wall obliquely to open at the lateral angle of the trigone.
- It lies in the retroperitoneal space not attached to any fixed structures, so can be displaced or obstructed by retroperitoneal masses like tumours or aneurysms.
- Abdominal portion of ureter lies on the medial portion of psoas major muscle near the tips of transverse processes of lumbar vertebra (which is very well seen in IVP).
- The ureter enters the pelvis crossing the end of common iliac or beginning of external iliac artery.
- In females, uterine artery crosses the ureter from lateral to medial side, about 2 cm lateral to the cervix (this has to be remembered while ligating the uterine arteries in hysterectomy).

Normal sites of constrictions: (1) PUJ, (2) At the brim of lesser pelvis, (3) Along its passage through the bladder wall

- ***Arterial supply:*** Upper segment of ureter receives blood supply from branches of renal and adrenal arteries; the middle portion from the branches of arteries of posterior abdominal wall; the pelvic portion from the branches of internal iliac arteries.
  - Vessels reach the abdominal portion of ureter on the medial side; whereas the pelvic portion receives on the lateral side (This has to be remembered while mobilising the ureter). The vessels form an anastomotic plexus in the adventitia of the ureter, which is found to be deficient in 10-15% of individuals leading to necrosis of cut ends of ureter following extensive mobilisation.

PLAIN X-RAY—KIDNEY, URETER AND BLADDER (KUB)

- Preparation of the patient: Enema/bowel wash/laxative is given on the previous day and the patient is asked to fast in order to reduce the bowel gas shadows in X-ray.
- High penetration X-ray is taken in supine position which covers *pubic symphysis and lower two ribs*.
- Interpreting the film:
  a. First bony parts are looked for, i.e. the hip, pelvis, lumbar vertebrae for fractures, scoliosis, spina bifida, secondaries in the spine.
  b. ***Kidney shadow***: Kidney shadows are visualised in plain X-ray KUB due to difference in the density between kidney (high vascularity) and perinephric fat (low vascu-

larity). Findings noted are size, location, calcification and stones. In children, perinephric fat is absent and so kidney shadows are not visualised.

c. ***Psoas shadow***: It is visualised well in normal KUB.

Psoas shadow is obliterated in:

- In enlarged kidney
- In scoliosis due to inflammatory or infiltrative causes
- In malignancy
- Tuberculous spine with cold abscess (psoas abscess)
- Splenic injury—in left sided shadow
- Retroperitoneal tumours

d. ***Ureteric line****:* It is looked for any radio-opaque shadow (ureteric stone). It runs along the tips of the *transverse processes of the lumbar vertebrae*, crosses the *sacroiliac joints* and reaches up to a point medial to the *ischial spine.*

e. Bladder, prostate and urethral areas are visualised for any lesion.



Fig. 26.2: Plain X-ray KUB AP-view. Note the psoas shadow.

INTRAVENOUS UROGRAM (IVU)



Figs 26.3A and B



Fig. 26.3C

Figs 26.3A to C: IVU showing hydronephrosis with clubbing of calyces and dilatation. Delayed post-lasix film often should be taken whenever there is poor secretion in initial films. Film can be taken as late as 72 hours. This delayed film shows dilatation (*Courtesy:* Dr Navinchandra Shetty, MD, HOD of Radiology, KMC, Mangalore).

Procedure

Renal function must be normal.

- Overnight fasting for 8 hours is advised. Laxatives are given to reduce bowel shadow and get a good quality film.
- First, a plain X-ray KUB is taken (IVU should not be read without doing KUB).
- Then 1 ml test dose of **sodium diatrizoate** (*Urograffin)* or **meglumine iothalamate** is injected IV and waited for



Fig. 26.4: IVU showing hydronephrosis.

The remedy for injuries is not to remember them.

IVU (Intravenous Urogram)

Indications	***Findings***
1. Hydronephrosis	Clubbing of calyces
2. Congenital anomalies	
a. Horseshoe kidney	Flower vase appearance
b. Duplex kidney and double ureter	
c. Ureterocele	Adder (cobra) head appearance
d. Polycystic kidney disease	Spider leg appearance
e. Retrocaval ureter	Reverse 'J' sign with hydronephrosis
3. Renal cell carcinoma	Irregular filling defect; spider leg appearance
4. To see the function of the kidneys in bilateral diseases	Bilateral stones, obstructive uropathy
5. After surgery for urinary diseases	To see the function of kidneys and outcome of the surgery
6. Renal injury	To see the function of other kidney (a very specific investigation)

Contraindications

1. Iodine sensitivity—may go for anaphylaxis. Hence, all precautions must be taken and essential drugs should be available while doing IVU
2. Multiple myeloma and hypergammaglobulinaemias (Acute renal failure may be precipitated due to dehydration)
3. Toxic thyroid

5-10 minutes for any reaction. If no adverse reaction occurs, then full dose 1 ml/kg body weight, IV urograffin is given (40-50 ml).

- X-ray is taken in 1-5 minutes, which shows the nephrographic and secretory function of the kidneys.
- Later 15 minutes and then 20-30 minutes films are taken.
- Further films are taken depending on the need.
- Film can be taken as late as 72 hours. Late films show bladder pathology as well as residual urine.
- In case of *renal failure* with high blood urea, dose of dye is increased to 2 ml/kg body weight to get a better film—***Infusion IVU***. Often diuretics are used in these patients to have better secretion.



Fig. 26.5: IVU showing hydronephrosis on right side; normal secretion on left side; with bladder filling.

- Lower abdominal compression is done for 10 minutes to have better definition of calyces, but not done in children and patients with abdominal aortic aneurysm.
- ***Minute IVU***: In case of renal artery stenosis, within first minute many films are taken to see nephrographic shadow (where a small, concentrated kidney is seen).
- ***Nonvisualization of kidney:*** No contrast is seen in the film even after 12 hours.

RETROGRADE PYELOGRAPHY (RGP)

Indications

- ❖ Failure of showing any secretions in an IVU as late as 72 hours film
- ❖ Urinary tuberculosis
- ❖ Urothelial tumours from the renal pelvis

Procedure

- Under G/A, cystoscope is passed. Ureteric orifice is visualised.
- Ureteric catheter is passed. Dye, sodium diatrizoate is injected.
- Patient is put in 15° head down position to allow the dye to reach upper urinary system.
- X-ray is taken.

Advantages

a. Prior to dye injection selective urine sample can be taken from each ureter.
b. Brush biopsy from suspected urothelial tumours of upper urinary tract can be taken.
c. Better-delineation of anatomy (due to more concentration of dye).



Fig. 26.6: Left RGP—normal study.

Disadvantage

Anaesthesia is required and is laborious.

RENAL ANGIOGRAM

Indications

- ❖ Renal artery stenosis
- ❖ Renal artery atheroma
- ❖ Renal artery aneurysm
- ❖ Occasionally renal cell carcinoma
- ❖ Arterial anomalies

Procedure

Retrograde Seldinger technique:

- ♦ Through femoral artery, using Seldinger's needle selective angiogram is done to visualise tumour vascularity, narrowing, anomalies. Dye used is Hypaque. Dose: 6-7 ml.
- ♦ Therapeutic embolisation, transluminal balloon angioplasty for renal artery stenosis can also be done by this approach.
- ♦ Translumbar approach for angiogram (through aortogram) is also used. Hypaque used is 30 ml.

Complications

- ❖ Paraplegia
- ❖ Embolism
- ❖ Dissecting aneurysm
- ❖ Bleeding
- ❖ Renal tubular necrosis

Renal pharmacoangiogram:

- ♦ Noradrenaline is injected along with the dye. Normal vessels will constrict in response to noradrenaline. But since tumour is autonomous, vessels in renal cell carcinoma do not respond to noradrenaline and so *tumour blush* is seen.

MICTURATING CYSTOURETHROGRAPHY (MCU)

Indications

a. Vesicoureteric reflux.
b. Posterior urethral valve.

Procedure

Catheter is passed into the bladder. Dilute iodine dye is infused. X-ray is taken during micturition. *Free reflux* is looked for. Applying pressure over the suprapubic region, X-ray is taken. *Pressure reflux* is studied.

Vesicoureteric reflux is graded depending on the severity of the reflux—as:

I—Ureters seen
II—Ureters and pelvis are seen
III—Ureters, pelvis, calyces are seen
IV—With grossly distended calyces
V—Tortuous elongated serpentine ureters

It can be unilateral or bilateral. Often it is associated with posterior urethral valve. It is often complicated by infection, pyonephrosis and renal failure

Investigations: MCU, IVU, U/S, blood urea and serum creatinine

Treatment: Tailoring of ureter with reimplantation



Fig. 26.7: Micturating cystourethrogram showing concomitant existence of posterior urethral valve (causing dilatation of proximal urethra) and vesicoureteric reflux (left side).

ASCENDING URETHROGRAM

- ♦ It is the investigation of choice for *stricture urethra*.
- ♦ Red rubber catheter is passed into the external meatus.

If someone is greedy, bribe him, if someone is foolish, advise him; if someone is wise, listen to him.

- Water soluble iodine dye is injected through the catheter.
- Oblique X-ray films are taken to visualise the urethra.
- Site, size, extent of stricture and extravasation can be found out in urethrogram.



Figs 26.8A and B: Ascending urethrogram showing stricture urethra.

ISOTOPE RENOGRAPHY

- A measure of individual kidney function is obtained by this method using a gamma camera.
- Radiolabelled Technetium 99m **DMSA** (Dimercapto-succinic acid) **or DTPA** (Diethylenetriamine-penta acetic acid) is given intravenously.

DTPA—renal function.

DMSA—renal parenchymal changes.

It shows:

a. *Early* vascular phase.
b. *Then* secretory phase.
c. *Later* excretory phase.

- This allows the assessment of renal plasma flow to each kidney and the efficiency and effectiveness of pelvicalyceal excretion also.
- Secretion < 20% is precarious.


Right background
Left background
Summed function image
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
A
32000
28000
24000
20000
16000
12000
8000
4000
0
0
2
4
6
8
10
12
14
16
18
20
22
24
26
28
30
Minutes
B

Figs 26.9A and B: Isotope renogram showing reduced secretion on right side.

Problems

1. Positioning of counters.
2. Often difficult to differentiate from muscle mass. It is only a supportive investigation.



Figs 26.10A to C: Renography showing (A) Normal study, (B) Hydronephrosis and (C) Renal failure.

CYSTOSCOPY

Uses

- To examine urethra, bladder, ureteric orifice for any pathology (tumour, infection)
- To visualise any bladder fistulas
- To treat
  - Urethrotomy (in stricture urethra)
  - TURP for BPH and carcinoma prostate
  - Bladder tumour resection
  - Bladder stone removal (cystolithotripsy, cystolitholapaxy)
  - Ureteric catheterisation
  - Fulguration of posterior urethral valve

Contraindication: Acute cystitis and prostatitis



Fig. 26.11: Isotope renogram showing kidney function.

Types

- ***Rigid.***
- ***Flexible.***

Procedure

- Patient is placed in lithotomy position.
- Under G/A or spinal anaesthesia after cleaning and draping, through urethra, cystoscope is passed using continuous *glycine irrigation* (to avoid TURP syndrome).
- The parts of the urethra are visualised while passing the cystoscope.
- Once bladder is reached, it is looked for diverticula, hypertrophy and other pathologies.
- Ureteric orifices are visualised.



Fig. 26.12: Cystoscope.

Complications

- Urethral injury.
- Bleeding.
- Water intoxication.

Fig. 26.13: Cystoscopy is being done for different procedures like TURP; diagnostic, etc. (*Courtesy:* Dr Ashok Pandit, MCh, Urologist, Mangalore).

CATHETERS

They are hollow tubes used to relieve urinary retention, obtain urine for analysis, irrigate bladder and to instill drugs into bladder.

> *The skilful doctors know what is wrong by observing alone, the middling doctor by listening and the inferior doctor by feeling the pulse.*
> **—Chang Chung-Ching**



Fig. 26.14: Photo showing red rubber catheter; Malecot's catheter and Foley's catheters.

Types

a. **Nonself-retaining catheter:** Simple red rubber catheter.
b. **Self-retaining catheter:** Foley's catheter, Malecot's catheter, Gibbon's catheter, De-Pezzer catheter.

Types of Catheterisation

a. ***Indwelling catheterisation*:** When a catheter is left behind in bladder and remains so it is called an indwelling catheter. *It is achieved by:*
   - Ballon tip of catheter—Foley's catheter.
   - Flower tip of catheter—Malecot's catheter, De- Pezzers.
   - Straping catheter externally—Gibbon's catheter.

b. ***Intermittent catheterisation*:** A sterile catheter is introduced intermittently by the patient or by others.



Gibbon's catheter with strap

Catheter in male



Catheter in female

Figs 26.15A to C: Gibbon's catheter. Note the look and method of fixing in male and female. It is a self-retaining catheter made up of plastic with a stillete in it which makes its passage easier through urethra. Sizes differ for males and females because of the difference in length of the urethra in male and female. Catheter has two ribbons attached which can be used to fix to the genitalia by adhesive plaster. Gibbon's catheter is least irritant to urethra.

FOLEY'S CATHETER (Fredrick Eugene Basil Foley—American Urologist)

It is a *self-retaining* urinary catheter made of *latex*. It has got a balloon near the tip into which distilled water is infused to make it *self-retainable*. Usually, Foley's catheter is kept for 7 days. *Sterilized* by γ-radiation.

Size: Adults—16 F.
Children—8 F or 10 F.

(F—French unit, Charriere unit, where each unit equals 0.33 mm). 16 F means circumference of the catheter is 16 mm. Diameter is one-third of circumference).



Figs 26.16A and B: Foley's catheter. Two way/three way Foley's catheters are available.

Uses

1. To pass per urethrally in retention of urine of any cause (BPH, stricture, trauma).

2. To measure the urine output in renal failure, postoperative patients, terminally ill patients.
3. Percutaneous cystostomy.
4. Cholecystostomy.
5. To drain fistulas.

Types

1. Two-way Foley's.
2. Three-way Foley's—to give bladder irrigation, e.g. following TURP.
3. Silicon coated Foley's—to reduce reaction and so as to keep for longer period (3 months).

Procedure

- After cleaning under strict asepsis, lignocaine gel is lubricated onto the urethral meatus. Catheter is passed into the urethra.
- Sometimes *Maryfield introducer* is used to pass Foley's catheter.
- Once catheter is in the bladder, urine flows out. It is now connected to a *urosac bag*.
- Balloon is inflated with 20-30 ml (amount is written on the catheter) of distilled water to make it self-retainable.
- During removal of the catheter same amount of water should be removed from the balloon before pulling out the catheter.

Complications

- Infection
- Encrustation
- Bleeding
- Stone formation
- Blockage
- Stricture
- Difficulty in removal of the catheter due to blockage of the balloon channel. Here bulb of Foley's can be punctured either from above under U/S guidance or injecting ether into the balloon so as to burst it but may cause chemical cystitis or passing a stilette into the channel

MALECOT'S CATHETER

- Self-retaining urinary catheter with an umbrella or flower at the tip. It is made of red rubber, contains sulphur and so it is radio-opaque.
- It is never introduced per urethrally.
- It is sterilised by boiling.



Fig. 26.17: Malecot's catheter—photo.



Fig. 26.18: Malecot's catheter—diagram.

Uses

- Suprapubic cystostomy (SPC)
  - In case of urinary retention when Foley's catheterisation fails (after two trials)
  - For diversion of urine following bladder, prostate or urethral surgeries
- Perinephric abscess
- Pyonephrosis
- Cabot's nephrostomy
- Subphrenic abscess
- Cholecystostomy
- Infected pseudocyst of the pancreas
- Amoebic liver abscess
- Gastrostomy

Advantages

- Malecot's catheter can be kept for a longer duration (3 months).
- It drains fluid adequately.
- Less infection rate.
- Removal is easier.

Disadvantage

- Surgery (open method) is required to insert the catheter.

RED RUBBER CATHETER

- It is a non self-retaining urinary catheter.
- Its tip is blunt. It has got only side opening.

Uses

1. Used to drain urine from the bladder temporarily.
2. To find out residual urine. After passing urine, catheter is introduced into the bladder. The amount of retained urine is measured. If it is more than 30-50 ml it signifies obstruction. It often increases up to 200-300 ml in conditions like BPH.

> *When the patient dies the kidneys may go to the pathologist, but while he lives the urine is ours. It can provide us a serial story of the major events going on within the kidney.*
> **—Thomas Addis**

3. Other uses
   - To administer nasal oxygen.



Fig. 26.19: Simple red rubber catheter. It has got only side opening. No opening in the tip (Flatus tube has got opening on both sides as well as at the tip).

   - For throat suction.
   - As a tourniquet for venesection and surgeries of fingers and toes.

NEPHROSTOMY

Nephrostomy is diversion of urine by passing a tube through the kidney into the calyces**.**

Indications

- Pyonephrosis
- Severe hydronephrosis
- Postoperative—following renal surgeries
- Obstruction in ureters



Figs 26.20A to C: Nephrostomy types: (A) Cabot's nephrostomy, (B) Tresidder's nephrostomy and (C) Percutaneous nephrostomy.

Types

1. ***Cabot's nephrostomy***: Malecot's catheter is placed into the calyces.
2. ***Tresidder's through and through loop nephrostomy***: Loop tube is placed with central part in the kidney and ends outside percutaneously to drain urine. This achieves double drainage. New tube can be placed using rail road technique.
3. ***Percutaneous nephrostomy***: Done under U/S guidance using guide wire and dilators.

Complications of nephrostomy

- Bleeding
- Sepsis
- Blockage

SUPRAPUBIC CYSTOSTOMY (SPC)

- It is placing of Malecot's catheter into the bladder above the pubis by open method, or percutaneously under the guidance using Foley's catheter.
- It is a temporary opening through the abdominal wall into the bladder.

Prerequisite

Bladder must be full and is confirmed by dullness below the umbilicus or by U/S.

Indication

Retention of urine, when urethral catheterisation fails.



Fig. 26.21: Suprapubic cystostomy (SPC). Malecot's or Foley's catheter can be used.

Procedure

- Under local anaesthesia (Xylocaine 2% above the pubis, in the midline) or G/A, a vertical midline incision of 3 cm in length is placed through linea alba. Skin, fascia, anterior rectus sheath are incised. Recti are retracted. In extraperitoneal space, peritoneum with pad of fat is reflected upward.
- Bladder is identified by the pattern of detrusor muscle and vesical venous plexus and is also confirmed by aspirating urine through a syringe.



Fig. 26.22: X-ray showing radio-opaque Malecot's catheter.

- The bladder is opened near the fundus. Urine is aspirated. Bladder wall is inspected for any pathology.
- Malecot's catheter is straightened using artery forceps and placed in the bladder. Sutures are placed around the Malecot's catheter. Wound is closed in layers.
- In percutaneous SPC, Foley's catheter is passed into the bladder using trocar and cannula.

Complications

- Injury to bowel, peritoneum.
- Infection.



Fig. 26.23: Ectopic kidney right sided IVU picture. It is un-ascended kidney. It often presents as mass in the right iliac fossa. CT scan is diagnostic. Differential diagnoses for masses in right iliac fossa are nodal mass; carcinoma caecum; tuberculosis; psoas abscess; retroperitoneal tumour. Sepsis; stones; tumour; can occur in ectopic kidney. Management of whatever problems arise is done through open method. Bilateral ectopic kidney may lead into eventual renal failure. Isotope scan is diagnostic.

HAEMATURIA

Types

a. *Gross* (visible to unaided eye).
b. *Microscopic* (> 5 RBC's/HPF).

- *Early* (initial) haematuria: Urethral origin, distal to external sphincter
- *Terminal* haematuria: Bladder neck or prostate origin
- *Diffuse* (total) haematuria: Source is in the bladder or upper urinary tract

False haematuria: Discolouration of urine from pigments such as food colouring and myoglobin.

Silent haematuria is due to tumours of kidney or bladder unless proved otherwise.

Causes

- Renal injury
- Urinary stones
- Wilm's tumour
- Tuberculosis
- Renal cell carcinoma
- Cystitis
- Bladder tumour
- Urinary bilharziasis
- BPH, carcinoma prostate
- Renal infarct
- Glomerulonephritis
- Blood dyscrasias


Benign
Malignant
Glomerulonephritis
Infarct
Renal stone
Tuberculosis
Trauma
Ureteric stone
Bleeding disorders
Renal tumour
Papillary carcinoma
Ureteric tumour
Cystitis
Tuberculosis
Bladder stone
Endemic haematuria
Benign prostatic hyperplasia
Urethral injury
Bladder tumours
Carcinoma prostate
Urethral tumours

Fig. 26.24: Causes of haematuria.

Good health is a serious business: like life itself, it has to be worked at and it takes on added meaning with effort.
—Normour Cousins

Investigations

- Urine culture and sensitivity (urine test for haematuria—*Benzidine test).*
- Ultrasound to look for the stone, tumour in the urinary tract.
- Cystourethroscopy to look for bladder or urethral pathology.
- IVU look for function of the kidneys.
- Urinary cytology for diagnosing urothelial malignancy.
- Bleeding time; clotting time; prothrombin time; platelet count.
- CT abdomen.
- Renal function tests—blood urea, serum creatinine.

Management

- Cause should be identified and treated.
- Blood transfusion.
- Antibiotics.
- Nephroureterectomy for RCC; removal of stone from kidney, ureter, urinary bladder.
- Treatment of bladder tumour by cystoscopic resection; intravesical chemotherapy using BCG; radiotherapy; systemic chemotherapy.
- Treatment of medical causes like glomerulonephritis.
- Correction of BPH.
- Correction of bleeding diathesis.

HORSESHOE KIDNEY

- It is a developmental anomaly where there is failure of complete ascent of kidneys with the fusion of lower or upper poles. It is due to fusion of subdivisions of mesonephric duct, when the embryo is as early as 30-40 days old.
- This condition is common in males.
- Fusion of lower pole is common (rarely upper poles).



Figs 26.25A and B: (A) Horseshoe kidney and (B) Plain X-ray KUB showing horseshoe kidney with renal stones.

- Most common site is in front of 4th lumbar vertebrae. The part in front of the vertebra is called as *isthmus*. It has blood supply which freely communicates one kidney to other. Isthmus usually lies in front of aorta.

Clinical Features

- Presents as a fixed, nonmobile, firm mass in the midline at the level of 4th lumbar vertebra which is resonant on percussion.
- It is more prone for infection, stone formation, hydronephrosis, tuberculosis.

Diagnosis

- IVU—medialisation of lower calyces and curving of ureter like a ***'flower vase'.***



Fig. 26.26: IVU showing flower vase appearance of horseshoe kidney.

- U/S abdomen.
- Urine analysis, blood urea and serum creatinine are supportive investigations.
- CT abdomen.

Treatment

- Whatever the complication occurs in horseshoe kidney, it is treated accordingly.
- *Per se* separation of isthmus is not indicated, unless to approach aorta for aortic diseases.

CYSTIC DISEASES OF THE KIDNEY

Types

a. ***Genetic***
  - Adult polycystic kidney disease (Autosomal dominant).
  - Infantile polycystic kidney disease (Autosomal recessive)—fatal.

b. ***Nongenetic***: Simple cyst, multicystic kidney, medullary sponge kidney.

c. ***Acquired renal cystic disease*** may develop in patient on long-term dialysis.

POLYCYSTIC KIDNEY DISEASE (PCKD)

- Adult PCKD is inherited as autosomal dominant disease. It is common in females.
- It is bilateral and presents in third decade. One side presents little earlier than other side.
- *Associations*
  - Polycystic diseases of liver (18%), pancreas and lungs.
  - Berry aneurysm in the circle of Willis.
- Cyst formation occurs at the junction of the distal tubule and the collecting duct.
- Grossly it contains multiple cysts with a clear or brownish fluid (due to haemorrhage).



Figs 26.27A and B: Polycystic kidney disease, picture and CT scan. It is bilateral, multiple.

Clinical features

- Bilateral palpable renal mass
- Loin pain
- Haematuria
- Infection
- Hypertension
- Uraemia

- Renal mass, which is lobular, firm, mobile, moves with respiration, ballotable, with dull renal angle and resonant band in front.
- Pain, which is due to stretch of renal capsule or haemorrhage into a cyst.
- Haematuria (25%), due to overdistended cyst rupturing into the renal pelvis.
- Infection is due to stasis.
- Hypertension (75%).
- Uraemia occurs in late stage due to renal failure.

Differential diagnosis

- Renal cell carcinoma
- Hydronephrosis
- Solitary renal cyst

Investigations

- U/S confirms the presence of cysts.
- IVU—*Spider leg pattern* with an elongated compressed renal pelvis, narrowed and stretched calyces.
- Blood urea and serum creatinine.
- Urine shows low specific gravity.

Treatment

- Wait and watch policy.
- If one of the cysts overdistends causing pain, haemorrhage, infection, then surgical intervention is required.
- ***Rovsing operation***: The kidney is exposed. The cyst is opened. The fluid is evacuated. The cut edge is marsupialised.
- Presently U/S guided aspiration is done as a simpler approach.
- Laparoscopic/retroperitoneoscopic aspiration/de-roofing of the renal cyst.
- Once renal failure sets in, then initial haemodialysis followed by bilateral nephrectomy, is done and later renal transplantation should be planned for.

SOLITARY RENAL CYST

- Solitary renal cyst is never congenital.
- It is due to an earlier trauma or infection resulting in blockage of tubule, leading to cyst formation.
- It is usually unilateral, presents as a renal mass which is smooth, often tender if infected or haemorrhagic**.**

Differential Diagnosis

- Renal neoplasm.
- Hydronephrosis.
- Polycystic disease.
- Hydatid cyst.

Investigation

- U/S and IVU confirms the diagnosis.
- CT scan.

The value of experience is not in seeing much but in seeing wisely—**William Osler**



Fig. 26.28: Solitary renal cyst. It is acquired, unilateral.



Fig. 26.29: Left side renal cyst—CT picture. It could be solitary renal cyst. It can be aspirated or de-roofed by laparoscopy/retroperitoneoscopy.

Treatment

- Kidney is exposed. The cyst is aspirated and a portion of the cyst wall is removed ***(Kirwin's operation*)** and cavity is filled with perinephric fat.
- Occasionally if the cyst is in one of the pole, partial nephrectomy is done.
- Laparoscopic approach.

DUPLICATION OF RENAL PELVIS AND URETER

- It is most common congenital anomaly of the upper urinary tract (4%).
- Usually unilateral. Common on the left side.
- In 3% of cases it is associated with duplication of ureter.
- Upper renal pelvis is small, drains the upper calyces. Lower renal pelvis is larger, drains the middle and lower calyces.
- Double ureter when associated, may be *partial* where two ureters join in lower third or *complete* where upper ureter opens into the bladder at a lower level and lower ureter opens into the bladder at the upper, normal ureteric orifice. This is called as "*Weigert Meyer Law*".
- In partial duplex, there is reno-renal reflux resulting in infection, stone formation and hydronephrosis.

Investigations

- IVU—diagnostic.
- U/S to look for complications**.**
- Cystoscopy shows **double ureteric orifices** on the same side.
- DTPA scan to see the function.



Figs 26.30A and B: (A) Duplex renal system and (B) X-ray showing bilateral duplex system.

Treatment

- Ureteric meatotomy is done if there is narrowing of the orifice.
- The co-existing complications are treated.



Fig. 26.31: IVU showing bilateral duplex kidney.

- Often heminephrectomy including removal of corresponding ureter may be essential as treatment.
- In females with complete duplication, lower ureteric orifice is ectopic, causing urinary incontinence which needs partial nephrectomy or ureteric reimplantation.

RETROCAVAL URETER



Fig. 26.32A



Fig. 26.32B

Figs 26.32A and B: Retrocaval ureter—IVU picture showing reverse J sign. On table finding of retrocaval ureter. It is treated by Anderson's Hynes operation. It causes hydronephrosis. It is due to anomalous development of IVC.

- It is due to developmental defect of IVC, as a result of which right ureter passes behind the IVC, causing right sided hydronephrosis with upper third hydroureter.
- IVU shows hydronephrosis with '*reverse J sign*'.
- *Treatment:* Anderson Hynes' operation.



Fig. 26.33: Retrocaval ureter. It is due to developmental problem of IVC.

Always make a total effort even when the odds are against you.

URETEROCELE

- It is a *cystic enlargement of the intramural portion of ureter* due to congenital atresia of the ureteric orifice. Its wall contains mucous membrane only.
- It is common in females, often bilateral (10%).

Complications

- Stone formation
- Recurrent infection
- Hydronephrosis

Stephen classification:
Stenotic, sphincteric, sphincterostenotic.



Fig. 26.34: IVU reveals left sided ureterocele with duplex kidney. Note the characteristic Cobra (Adder) head pattern of left ureterocele.

Investigations

- IVU—shows A*dder head* appearance or *cobra head* appearance.
- Cystoscopy—shows translucent cyst which is thin walled surrounding the ureteric orifice.

Treatment

- *Cystoscopic ureteric meatotomy* with the removal of cyst wall.
- In addition to that co-existing complications should be treated.
- Often ureteric reimplantation is needed.



Fig. 26.35: U/S picture of ureterocele—Adder head appearance.

INJURIES TO KIDNEY

- Commonly it is due to a blunt injury.
- Often it is associated with other abdominal injuries—of liver, spleen, bowel, mesentery, etc.
- *Per se renal injury is extraperitoneal.*



Fig. 26.36: Renal trauma causing extensive laceration. Patient underwent nephrectomy (*Courtesy:* Dr Ashfaque Mohammed, DNB; KMC, Mangalore).

Types

1. Small subcapsular.
2. Large subcapsular.
3. Cortical laceration.
4. Laceration with perinephric haematoma.
5. Medullary laceration with bleeding into the renal pelvis.
6. Corticomedullary complete rupture.
7. Hilar injury (most dangerous).

Grading of renal injury

1. Subcapsular nonexpanding haematoma without parenchymal laceration
2. Cortical laceration < 1 cm of parenchymal depth, no extravasation; perirenal haematoma
3. Cortical laceration > 1 cm depth; no urine extravasation
4. Parenchymal laceration extending through cortex and medulla with collecting system; with extravasation of urine
5. Renal pedicle avulsion; shattered kidney

Clinical Features

- Features of *shock.*
- *Haematuria*—may be mild to profuse depending on the type of injury.
- *Sudden delayed profuse haemorrhage* causing haematuria can occur between 3rd day to 3rd week after trauma.

- *Clot colic.*
- Bruising, swelling and tenderness in the loin.
- Paralytic ileus with abdominal distension occurs due to retroperitoneal haematoma implicating splanchnic nerves.

Investigations

- ***IVU (high dose)***: It is the investigation of choice. Here function of not only the injured kidney but also of the contralateral kidney can be seen. It is observed that often opposite renal artery undergoes a reflex spasm, temporarily ceasing the function of the contralateral kidney.
- ***U/S abdomen***: Done to see the type of injury, amount of haematoma and other associated injuries in the abdomen. U/S is repeated at regular intervals to see the progress (at 12-24 hourly).
- Blood urea and serum creatinine should be repeated at regular intervals.
- Blood grouping and cross-matching for blood transfusion.
- Emergency CT scan is very useful.



Figs 26.37A to G: (A) Small subcapsular, (B) Large subcapsular, (C) Cortical laceration, (D) Laceration with perinephric haematoma, (E) Medullary laceration with bleeding into the renal pelvis, (F) Corticomedullary complete rupture, (G) Hilar injury (most dangerous).

Treatment

I. *Initially always conservative:*
  - Catheterise and watch the urine colour and output.
  - Blood transfusion.
  - Strict observation with regular monitoring of the pulse, BP, temperature, *U/S follow-up daily.*
  - Sedation, analgesic and antibiotics.
  - 75% of patients respond to conservative management.
  - While treating conservatively, regular monitoring of blood urea and serum creatinine is a must.
  - If the patient goes in for renal failure, haemodialysis should be done for 6-8 weeks. Meanwhile, other kidney starts functioning again and patient recovers without any further problem.

II. *Indications for surgical intervention:*
  - When there are signs of progressive blood loss with the condition of the patient deteriorating.
  - Formation of progressive perinephric haematoma.
  - When there are associated other injuries.
  - Hilar injury.

Surgery (Only in 10-20% of Patients)

Options:

- Gentle suturing of the laceration. Often kidney is friable, this is not possible.
- Then nephrostomy (Cabot's) is done.
- When the injury is in the poles partial nephrectomy is done.
- In *hilar injury and severe laceration, nephrectomy is the only choice.*

	Types	*Treatment*
I	Only bruise/contusion	Conservative
II	Breach in calyceal system rupture of one of the small branches of renal artery	Conservative/ nephrectomy
III	Rupture of pelvi-calyceal system/renal substance	Nephrectomy

Complications

- Clot retention in the bladder and may go for renal failure
- Pararenal pseudohydronephrosis
- Infection
- Perinephric abscess
- Aneurysm of the renal artery
- Renal failure
- Hypertension occurs 3 months later

RENAL TUBERCULOSIS

- Commonly it is *secondary*. Primary may be in the lung.
- Tuberculous bacilluria occurs with an early lesion in the renal cortex, and the disease spreads along the ureter causing tuberculous ureteritis and stricture ureter.
- Tuberculous kidney results in any of the following pathological types.

Pathological Types

Through blood, bacteria reach the glomeruli causing caseating granuloma with Langhan's type of giant cells and epithelioid

Variability is the law of life, and so no two faces are the same, so no two bodies are alike, and no two individuals react alike and behave alike under the abnormal conditions which we know as disease. **—William Osler** cells. These granulomas coalesce to form a papillary ulcer and other consecutive different forms.

- *Tuberculous papillary ulcer.*
- *Cavernous form.*
- *Hydronephrosis*.
- *Pyonephrosis* [due to (secondary) superadded infection by *E. coli*, *Klebsiella*].



Figs 26.38A to C: Specimen of kidney showing dilatation and caseous material as content. It is tuberculous pyonephrosis. Ureter is visualised in the specimen. Often there may be ureteric stricture due to tuberculosis.

- *Tuberculous perinephric abscess*.
- *Calcified tuberculous area* (mimics calculi, hence called as pseudocalculi).
- *Caseous kidney*—often called as *putty kidney* or *cement kidney* (it goes for autonephrectomy).
- *Miliary tuberculosis*.
- Tuberculous bacilluria occurs from an early stage of the disease which causes tuberculous ureteritis and stricture ureter. Most common site is *ureterovesical junction*; second common site is pelviuretric junction.
  - Tuberculous cystitis eventually results in *golf hole ureter and thimble bladder* (cystoscopic findings*)*. This is due to fibrosis causing rigid withdrawn dilated ureteric orifice looking like *golf hole*. Entire urinary bladder gets fibrosed, stiff and unable to dilate and accommodate urine causing *thimble systolic bladder*.
  - Tuberculous prostatitis, seminal vesiculitis (P/R—palpable seminal vesicle), tuberculous epididymitis and funiculitis are other associations. Thickened epididymis with ulcer on the posterior aspect of the scrotum may be often found. Tuberculous funiculitis with beaded, thickened vas deferens.



Fig. 26.39: Mode of spread in urinary tuberculosis.

Clinical Features

- Common in males.
- Common on right side.
- Frequency—both day and night.
- Polyuria.

- ***Sterile pyuria***: Urine is pale and opalescent with presence of pus cells without organisms in an acid urine—*abacterial aciduria* (Other causes: Interstitial cystitis, chlamydia).
- ***Painful micturition with often haematuria.*** Haematuria may be overt or microscopic (50%).
- Renal pain and suprapubic pain. Suprapubic pain is more common due to cystitis.
- ***Tuberculous kidney is rarely palpable*** unless there is hydronephrosis or perinephric abscess.
- Enlarged prostate and seminal vesicle, thickened beaded vas, thickened epididymis, impotence, infertility are other features.
- Presentation like acute pyelonephritis.
- Features of urinary stones; recurrent urinary tract infection; renal failure if both kidneys are diseased; hypertension.
- Haemospermia; pelvic pain.
- Dyspareunia; menstrual dysfunction; vaginal discharge; infertility in females.
- Fever and weight loss.
- Often cough with expectoration and haemoptysis may be present.

Investigations

- ↓Hb%.
- ↑ESR. Mantoux skin test is usually positive.
- Chest X-ray.
- U/S abdomen.
- *Three consecutive early morning samples of urine* **(EMSU)** are collected and sent for microscopy (Ziehl-Neelsen staining), culture (L-J media) or guinea pig inoculation.
- Plain X-ray KUB—shows calcification.
- CT scan of abdomen and pelvis to see hydronephrosis, shrunken kidney, stricture, necrosis.
- IVU—hydrocalyx, narrowing of calyx, stricture ureter which are often multiple with dilatations in between.
- Often RGP is very useful, as better definition of ureter, pelvis, calyces and selective sampling of urine are possible.



Fig. 26.40: Renal tuberculosis types.



Fig. 26.41: Stricture of left ureter lower part—IVU picture. Common cause is tuberculosis of ureter.

- Cystoscopy reveals multiple tubercles, bladder spasm, oedema of ureteric orifice eventually forming "*golf hole ureter*", scarring, ulceration, bleeding, stone formation.
- Polymerase chain reaction (PCR) for tuberculosis. Radioisometric culture.
- Voiding cystourethrography (MCU) to see ureteric stricture and reflux.

Treatment

- Antitubercular therapy is started. INH, rifampicin, ethambutol and pyrazinamide. Duration of treatment is *one year*.
- After 6-12 weeks of drug therapy, surgical treatment is planned. Kidney is exposed. Pyocalyx is drained. Cut edge of the capsule is sutured—*Hanley's renal cavernostomy.*
- Hydronephrosis—*Anderson Hynes* operation or nephrostomy or stenting ("J" stent) of ureter is done.
- Renal tuberculous abscess not resolving for 2 weeks should be drained.
- Ureteral stricture—stenting/reimplantation of the ureter into the bladder/psoas hitch/Boari's flap/ileal conduit (*Koch's ileal conduit*).
- Thimble bladder—hydraulic dilatation/ileocystoplasty/caecocystoplasty/sigmoid colocystoplasty is done.
- In unilateral lesion, with gross impairment of renal function—*nephroureterectomy* is done.

Indications for nephroureterectomy

- Nonfunctioning kidney
- Disease extensively involving the kidney
- Disease causing hypertension and severe obstruction
- Tuberculous pyonephrosis
- Coexisting renal cell carcinoma

Difficulties are like mirror on the wall, that show a person what they are in reality.

HYDRONEPHROSIS (HN)

It is an aseptic dilatation of pelvicalyceal system due to *partial* or *intermittent obstruction* to the outflow of urine.

Aetiology

It can be unilateral or bilateral.

Unilateral

A. *Extramural*:
1. Aberrant renal vessels (vein or artery). It is common on *left side.*
2. Compression by growth (carcinoma cervix, carcinoma rectum).
3. Retroperitoneal fibrosis.
4. Retrocaval ureter.

B. *Intramural:*
1. Congenital PUJ obstruction.
2. Ureterocele.
3. Neoplasm of ureter.
4. Narrow ureteric orifice.
5. Stricture ureter following removal of stone, pelvic surgeries or tuberculosis of ureter.

C. *Intraluminal:*
1. Stone in the renal pelvis or ureter.
2. Sloughed papilla in papillary necrosis.

Bilateral

A. *Congenital:*
- Congenital stricture of external urethral meatus, pin-hole meatus.
- Congenital posterior urethral valve.

B. *Acquired:*
- BPH.
- Carcinoma prostate.
- Postoperative bladder neck scarring.
- Inflammatory/traumatic urethral stricture.
- Phimosis.
- Carcinoma cervix.
- Bladder carcinoma.

- *Congenital PUJ is the most common cause of HN*.
- Often it is bilateral and presentation on one side is earlier than the other side.
- ***Aberrant renal artery*** or ***vein*** in the lower pole of kidney can compress the PUJ causing HN. Renal angiogram confirms the diagnosis.

Treatment of aberrant renal vessels

If it is a vein it can be ligated safely. But if it is an artery, it exclusively supplies the lower pole of the kidney and so cannot be ligated. So kidney is mobilised; upper and lower poles are approximated together so that artery is made to slip away from the site of compression—*Hamilton Stewart operation*.

- ***In pregnancy*** dilatation of ureters and both pelvis occur due to atony of ureteric musculature by progesterone. It starts as early as in the first few weeks of pregnancy and lasts until few weeks after delivery. Involution occurs 2-12 weeks after delivery.



Fig. 26.42: Aberrant renal vessels are one of the known causes of hydronephrosis.



Figs 26.43A and B: Aberrant renal vessels causing obstruction and hydronephrosis. As this often supplies lower pole of kidney exclusively, it need to be retained.

Classifications

Classification I
- Unilateral HN
- Bilateral HN without renal failure
- Bilateral HN with renal failure

Classification II
- *Intermittent HN*: Obstruction occurs, swelling and pain appear in the loin. After sometime patient passes large amount of urine following which swelling and pain disappear—*Dietl's crisis*
- *Persistent HN*: It is due to persistent partial obstruction

Classification III

- HN only
- HN with hydroureter

Classification IV

- Extrarenal pelvic HN (80%)
- Intrarenal pelvic HN (20%). Destruction of kidney is earlier and severe here, as compared to extrarenal pelvic HN

Pathology

- Initially pressure burden is taken up by the pelvis; later calyces and renal parenchyma. Gradually, parenchyma thins out due to destruction and it dilates. Eventually leading to compromised secretory function. Parenchymal thickness of less than 2 mm is unlikely to function. In bilateral cases such patients will go for renal failure.


Hydronephrosis of kidney
Dilated pelvis
Obstructed congenital pelviureteric junction

Fig. 26.44: Hydronephrosis due to congenital PUJ obstruction. It is the common cause of hydronephrosis.


Parenchyma
Calyces
Renal pelvis
A

Fig. 26.45A


Renal parenchyma
Dilated calyces
Renal pelvis (dilated)
PUJ
Ureter
B

Fig. 26.45B

Figs 26.45A and B: Specimens showing hydronephrosis.


Cup
Flat
Club
Broadened

Fig. 26.46: Stages of HN.



Figs 26.47A and B: Types of renal pelvis (A) Intrarenal and (B) Extrarenal.



Figs 26.48A to C: CT scan showing hydronephorosis of left kidney with extrarenal pelvis. Patient underwent laparoscopic pyeloplasty (*Courtesy:* Dr Ashok Padit, MCh, Urologist, Mangala Hospital, Mangalore).

Clinical Features

A. *In unilateral cases:*
- Congenital PUJ obstruction and calculus are the most common causes.
- M : F : : 2 : 1.
  - Right side kidney is affected more commonly.
  - Dull aching loin pain with dragging sensation or heaviness.
  - Mass in the loin which is smooth, mobile, ballotable, moves with respiration with dullness in renal angle and a band of colonic resonance in front.
  - Attacks of acute renal colic.
  - Often patient may be having ***Dietl's crisis***—after an acute attack of renal colic, swelling in the loin is seen which disappears after sometime following passage of large volume of urine.
  - Dysuria, haematuria, if infected fever and tenderness in renal angle.
  - Occasionally hypertension.

B. In bilateral cases:
- From lower urinary tract obstruction.

❖ Loin pain
❖ Features of bladder outlet obstruction—frequency, hesitancy, poor stream
❖ Kidneys are often not palpable if renal failure develops early



Fig. 26.49: IVU showing bilateral hydronephrosis and hydroureter.

- From bilateral upper urinary tract obstruction.

❖ Loin pain, mass in the loin, attacks of renal colic
❖ In bilateral cases, when it is severe, features of renal failure like oliguria, oedema, hiccough may be present

Complications

1. Pyonephrosis.
2. Perinephric abscess.
3. Renal failure in bilateral cases.

Investigations

- Blood urea and serum creatinine.
- Urine for microscopy.
- U/S abdomen: Investigation of choice.



Fig. 26.50: Hydronephrosis as seen in CT scan.

Type of pelvis, thickness of parenchyma, site of obstruction and cause of obstruction, e.g. stones, can be made out (Refer Fig. 26.54).

- *IVU*: To find out the function of diseased as well as opposite kidney. Normal calyx is *cup* shaped. It gets *flattened* and later *club shaped* which eventually becomes *broadened* in hydronephrosis (Refer Fig. 26.47).
- ***Whitaker test***: A fine needle is passed into the renal pelvis through loin. Pelvis is perfused with saline at a rate of 10 ml/minute. Normally, initially the pressure increases and later it will remain constant. Persistent increase in pressure suggests HN.
- CT scan is diagnostic.
- ***Isotope renography*** is also useful to study the function of the kidney before and after the surgical treatment and also to see the efficacy of surgery as far as function is considered—DTPA scan.



Fig. 26.51: Retroperitoneal tumour causing ureteral obstruction with hydronephrosis.



Fig. 26.52: CT scan showing bilateral hydronephrosis. One side large (left side); another side early hydronephrosis.



Fig. 26.53: IVP showing right hydronephrosis. Note the dilated right renal pelvis and delay in the excretion of the dye from the affected kidney.



Fig. 26.54: U/S picture of hydronephrosis showing dilated pelvis.

> *In the case of perinephric abscess bending the trunk away from the side of the abscess may produce pain, whereas the patient can bend his body towards the lesion without much discomfort.* **—George S**

Treatment

- Always conservative surgeries which are aimed at conserving the kidneys are done. Nephrectomy is not done unless indicated.



Fig. 26.55: Isotope scan showing hydronephrosis on the left side.

1. The cause is treated: Stone, congenital anomaly, aberrant renal vessels, stricture urethra (dilatation, urethrotomy, urethroplasty); phimosis (circumcision); BPH (TURP); posterior urethral valve (cystoscopic fulguration of valve).
2. ***Anderson-Hyne's operation*** (*Dismembered pyeloplasty*): In congenital PUJ obstruction, the spasmodic segment and redundant pelvis are excised. A new pelvis is created and the cut end of pelvis is anastomosed to the ureter in the *dependent* position.



Fig. 26.56: Anderson-Hyne's operation.

3. *Davis T-tube ureterostomy:* Placement of T tube in the ureter by making longitudinal incision.
4. *Non-dismembered pyeloplasties*: Here PUJ is not transected. Reconstruction is done without PUJ transection by different methods, e.g. **Foley's Y-V plasty.**
5. In bilateral HN, without renal failure, *kidney which is functioning better should be operated first.* Three months later, otherside kidney is dealt with.
6. In bilateral HN with renal failure, *bilateral nephrostomy and haemodialysis* support is required initially. After 3-6 weeks IVU is done and the functions of both kidneys are looked for. If they function, then treated accordingly by Anderson-Hyne's operation.

   If kidneys are still not functioning (renal function < 20% on isotope study) then nephrectomy and renal transplantation is the only option left.
7. *Laparoscopic* or *retroperitoneoscopic pyeloplasty* is becoming popular but is expensive and time consuming. It gives good result as well.
8. *Endoscopic pyelolysis*, even though technically easier results are not assured.

PYONEPHROSIS

It is collection of pus in pelvicalyceal system, which is converted into a multiloculated sac. Occurs due to:

a. Infection of pre-existing hydronephrosis.
b. Following acute pyelonephritis.
c. As a complication of renal calculus—either stone in the renal pelvis or staghorn calculus.

Clinical Features

- Usually unilateral.

Triad

- Anaemia
- Fever
- Loin swelling

- Tender mass in the loin which is smooth, soft, not mobile, not moving with respiration.
- Patient may also have cystitis, pyuria, burning micturition.
- Features of toxicity such as fever with chills and rigors.

Investigations

- Plain X-ray, KUB, may show renal calculus.
- IVU shows HN poor secretion.
- *Cystoscopy* reveals cystitis with *efflux of purulent pus* through the ureteric orifice**.**
- U/S shows dilatation.
- DTPA scan later.

Treatment

- After starting antibiotics, pus is immediately drained from the kidney through a loin incision and *nephrostomy* tube (Cabot's nephrostomy) (Malecot's catheter) is placed.
- If kidney is totally destroyed, *subcapsular nephrectomy* is done. This also prevents other kidney from getting infected through perirenal lymphatic connections.
- In bilateral pyonephrosis, *bilateral nephrostomy* is the only choice. *'J' stenting* is done often to keep the ureters patent.

CARBUNCLE OF KIDNEY (RENAL CARBUNCLE)

- A localised inflammatory necrotic mass of tissue involving renal parenchyma, caused by *Staphylococcus aureus* and coliform organisms, source of which is cutaneous infections like boil and carbuncle.



Fig. 26.57: Cut section of specimen of kidney showing pus, necrotic area, and multiple infected abscesses—renal carbuncle with multiple abscesses. Condition is common in diabetics.

- It presents as ill-defined tender swelling in the loin, with pyrexia and leucocytosis.
- Staphylococci can be isolated from the urine.
- IVU shows obliteration of group of calyces, ***mimics renal cell carcinoma***.
- **Treatment**: Antibiotics, drainage of carbuncle, with placement of Malecot's catheter.
- Often, in severe type nephrectomy may be needed.
- Severe septicaemia may occur in renal carbuncle.

Renal abscess/renal carbuncle

- A localised inflammatory necrotic mass of tissue involving renal parenchyma, caused by *Staphylococcus aureus* and coliform organisms, source of which is cutaneous infections like boil and carbuncle. Eventually infection may spread to entire kidney causing multiple abscesses
- It presents as ill defined tender swelling in the loin, with pyrexia and leucocytosis
- Staphylococci can be isolated from the urine
- IVU shows obliteration of group of calyces, *mimics renal cell carcinoma*
- Treatment: Antibiotics, drainage of carbuncle with Malecot catheter placement
- Often, nephrectomy may be needed in severe type
- Life-threatening septicaemia can occur which often needs not only nephrectomy but also higher antibiotics like mereponem, linezolid, and intensive critical care, ventilator support

PERINEPHRIC ABSCESS

Causes

- Infection of a perinephric haematoma.
- Perforation through renal capsule from pyonephrosis or renal carbuncle.
- Tuberculous perinephric abscess.
- Extension of cortical abscess.
- Haematogenous spread.
- Extension of appendicular abscess.
- Periureteral lymphatic spread.



Fig. 26.58: Perinephric abscess.

Clinical features

- High fever
- Fullness in the loin
- Tenderness and rigidity
- Scoliosis with concavity towards the side of abscess

Investigations

- Total count is increased.
- Plain X-ray KUB—obliteration of psoas shadow, scoliosis, elevation of hemidiaphragm.
- IVU—two films taken one in lying down position and another in erect posture.

  Normally in erect posture, downward displacement of the kidney is seen. Downward displacement is not seen in case of perinephric abscess—*Mathe's sign.*
- U/S abdomen.
- CT scan is diagnostic.

Treatment

1. Antibiotics are started.
2. Under G/A through loin approach (lumbar incision), pus is drained adequately. Pus is sent for culture and sensitivity. Collection in the cortex of the kidney should also be drained. A Malecot's catheter is kept in place.

RENAL CALCULUS

> *The Times whereat you often in a day have the Urinary Excretion performed with Ease, are times which invite you very frequently to lift up your Hearts unto God with such an Acknowledgment as This; 'O, My most merciful God, I bless thee, that the grinding Torments of the Stone, are not now grinding of me'*
>
> —**Cotton Mather,** 1724

Efficiency is, doing better what is already done.

It is more common in males; 90% are radio-opaque (gallstones are more common in females; 90% are radioluscent).



Fig. 26.59: Large staghorn calculus—both surfaces of the stone were shown.

Aetiology

- *Diet:* Vitamin A deficiency—it causes desquamation of epithelium which acts as a nidus for stone formation.
- *Climate*: In hot climate urinary solutes will increase with decrease in colloids, which leads to chelation of solute with calcium forming a nidus for stone.
- *Citrate level* in urine (300-900 mg/24 hours) maintains the calcium phosphate and carbonate in soluble state and any decrease in citrate level in urine causes stone formation.
- *Infection* in kidney: Urea splitting organisms commonly cause stone formation, i.e. *E. coli*, *Staphylococcus, Streptococcus, Proteus.*
- *Prolonged immobilisation* causes decalcification of bones and so hypercalciuria leading to stone formation.
- *Hyperparathyroidism* causes hypercalciuria causing multiple bilateral stones or often bilateral nephrocalcinosis (5%).
- *Hyperoxaluria,* as a result of altered glycine metabolism.
- *Cystinuria* (Autosomal recessive).
- *Stasis* due to obstruction to urine flow.
- *Medullary sponge kidney*.
- *Randall's plaque theory* is erosion and deposition of urinary salts as Randall's plaque at the apex of renal papillae.
- *Carr's postulates* states that minute concretions called as microliths normally develop in the subendothelial part of the tubule which will be carried away as particles by renal lymphatic network vessels. If these lymphatics are blocked, microliths enlarge and act as nidus for stone formation.
- *Others:* Sarcoidosis, myelomatosis, gout, idiopathic hypercalciuria, hypervitaminosis D, neoplasms on treatment, hypomagnesuria (Mg^{++} in urine acts as a complexing agent and prevents nucleation normally).
- *Renal tubular acidosis*: Commonly causes calcium phosphate stone (10%).

Stages of stone formation

I. Supersaturation
II. Nucleus formation
III. Crystallisation
IV. Aggregation
V. Matrix formation
VI. Stone

Epitaxy: Growth of one type of stone on another type.



Fig. 26.60: Plain X-ray KUB showing bilateral large renal stones and right ureteral stone.

Types

1. *Oxalate stones (75%):* Also called as *mulberry stone* as it is brown in colour, with sharp projections. It is invariably calcium oxalate stone, shows *envelope crystals in urine.*
2. *Phosphate stones (10-15%):* It is either calcium phosphate or calcium, magnesium, ammonium phosphate stone usually occurring in an infected urine. It is smooth and white in colour. In an alkaline urine it enlarges rapidly, filling renal calyces taking their shape called as *staghorn calculus*. It is radio-opaque and attains a large size.
3. *Uric acid stones (5%)* are smooth, hard, yellowish, multiple and radioluscent. They are seen in gout, hyperuricosuria, altered purine metabolism.
4. *Urate stones*.
5. *Cystine stones (2%)* occur in *cystinuria* where there is defective absorption of cystine from the renal tubules (autosomal recessive condition).

It is seen in young girls, occurs only in *acidic urine.* It is multiple, soft, yellow in colour and the colour changes to *greenish hue* on exposure. It attains large size. It is radio-opaque because it contains sulphur.

6. *Xanthine stones* are very rare, smooth, brick red in colour, due to altered xanthine metabolism.

   Here there is deficiency in xanthine oxidase enzyme.
7. *Indigo stones*: Very rare. Blue in colour.
8. *Struvite stone*: It is compound of magnesium, ammoniumphosphate mixed with carbonate. It occurs in presence of ammonia and urea splitting organisms in urine, e.g. *Proteus; Klebsiella.*

Shapes of Stone Crystals in Urine

	Type of crystal	*Shape of the crystal*
a.	Calcium oxalate monohydrate	Dumbell shaped
b.	Calcium oxalate dihydrate	Envelope shaped
c.	Uric acid	Yellowish of varying size and shape
d.	Cystine	Hexagonal, very soft stones
e.	Triple stone	Coffin lid shaped

Clinical Features

- *Pain—renal pain* is located over renal angle, hypochondrium and lumbar region. Often severe radiating to groin and testis in male, with vomiting due to pylorospasm. Pain worsens on movements.
- *Haematuria* is common.
- Pyuria.
- Fever.
- Tenderness in renal angle, with often a mass in the loin due to hydronephrosis which moves with respiration and is bimanually palpable, ballotable, smooth, soft.
- As urinary tract infection.
- Incidental finding.
- Often hypertension.

Note:
Food rich in oxalates are, spinach, tea, cola, alcohol, citrus fruits.

Investigations

- *Blood*: ESR, serum calcium, phosphate, creatinine, blood urea, uric acid, PTH level.
- *Urine*: Calcium, urate, cystine if suspected only, pH, specific gravity.
- *Plain X-ray, KUB*: To see kidney shadow, stones (90%—*radio-opaque*).
- IVU to see renal functions and HN.
- RGP if required.
- U/S abdomen—can detect even radioluscent stones and gives information about the changes in renal parenchyma.
- Urine analysis and C/S to identify bacteria.
- *CT scan* will identify the small missed stones in ureter.



Fig. 26.61: Plain X-ray, KUB, showing multiple stones in the right kidney.

Treatment

1. ***PCNL (Percutaneous Nephrolithotomy).***

Indications

- ❖ Stones more than 2.5 cm in size
- ❖ Multiple stones
- ❖ Stones not responding for ESWL

Procedure: Initially cystoscopy is done and ureteric stent/catheter is placed and renal pelvicalyceal system is identified under C-Arm guidance. Under the guidance of C-Arm or U/S, needle puncture is made in the loin percutaneously. Through kidney, calyx and pelvis are approached. Guidewire is passed. Graduated dilators are passed and so track is widened. Then through that, a nephroscope is passed. After fragmentation, stone is removed using different methods [Laser (Holmium), pneumatic, ultrasonic or electrohydraulic].



Fig. 26.62: Plain X-ray KUB showing phosphate stone in the kidney and oxalate stone in urinary bladder.

Enthusiasm is the greatest asset in the world. It beats money, power and influence.



Figs 26.63A to C: Stages in PCNL.

Complications of PCNL

- Haemorrhage
- Perforation of collecting duct causing extravasation of irrigation fluid
- *Injury to colon or pleura* while creating initial track for nephroscope

2. ***ESWL (Extracorporeal Shock Wave Lithotripsy):***

A
MEDILITH
MEDICO
B

Figs 26.64A and B: ESWL table and machine used for renal stones. It needs C-Arm to guide the exact point of stone to be fragmented.

- *Piezo-Ceramic* or *Electromagnetic* shock waves are passed to the stone through water bath or water cushion which acts as a media. Shocks are produced at 2/sec. 1000-4000 shocks are required for each stone.
- *Dornier Lithotripter* is used for fragmenting stones.
- Stone is located and observed through fluoroscope (C-Arm) or ultrasound. Shock waves are triggered to create *compressive waves* over the stone, to *fragment* it. These fragments are flushed out later.

Advantages

- No anaesthesia is required
- Can be done as an OP procedure
- Less than 2.5 cm sized stones are well fragmented
- Hard stones, oxalate stones are better eliminated by ESWL
- ESWL can be done repeatedly in different sittings
- If it is not successful one can switch over to PCNL

Complications

- Renal haematoma
- Severe haematuria
- Injury to adjacent structures
- Fragmented stone retains in the ureter

Contraindications

- Pregnancy
- Bleeding disorders
- Patients with abdominal aneurysms
- Sepsis and renal failure (Serum creatinine more than 3 mg%)

3. ***Conservative treatment:***
   - Flush therapy—mainly *used for lower ureteric stones.*
   - IV fluids.
   - Inj frusemide 60-80 mg IV.
   - Anti-inflammatory and antispasmodic agents are given to relieve the pain.
4. ***Surgery for renal stones*****:** Presently most of the renal stones can be removed without open surgery (PCNL, ESWL, URS). But limiting factors are cost and availability.

Surgeries

1. *Pyelolithotomy.*
   - Suitable for stones in extrarenal pelvis.
   - By loin (posterior subcostal) incision, kidney is approached.
   - Renal pelvis is opened, the stone is removed and the pelvis is closed. A drain is placed and wound is closed.
2. *Extended pyelolithotomy (Gil-Vernet*): In case of intrarenal pelvis, incision is done on the hilum between the pelvis and kidney over the renal sinus, dissection is carried out so as to remove the stones from pelvis as well as calyces.
3. *Nephrolithotomy*: By placing incision just behind the most convex surface (*Brodel's line*), stone is removed.
4. *Nephropyelolithotomy*: By making incisions both over the kidney and pelvis, stone/stones are removed. It is often done in *staghorn calculus.*



Fig. 26.65: Plain X-ray showing right-sided renal stone with 'J' stent on left side.



Figs 26.66A to F: Surgeries for renal stones. (A) Pyelolithotomy, (B) Extended pyelolithotomy, (C) Nephropyelolithotomy, (D) Nephrolithotomy, (E) Partial nephrectomy, (F) Coagulum pyelolithotomy.



Figs 26.67A to D

You may be disappointed if you fail, but you are doomed if you don't try.



Figs 26.67E to G

Figs 26.67A to G: Very large renal pelvic stone of more than 8 cm in size weighing 610 grams. It is one of the largest renal stone extracted (*Courtesy:* Dr Ashok Padit, MCh, Urologist, Mangala Hospital, Mangalore).

5. *Partial nephrectomy:* Done when there are multiple stones occupying a pole, usually lower pole of the kidney or when there is damage to the calyx, if not removed may encourage further stone formation.
6. *Bench surgery:* Kidney is removed out temporarily, cooled by ice packs or inosine or liquid nitrogen. Stones are searched and removed completely. Later kidney is replaced in right iliac fossa.
7. *Coagulum pyelolithotomy*: Coagulum solution which contains fibrinogen is poured into the renal pelvis. It is activated so that it solidifies, meanwhile entangling the stones in renal pelvis. This entangled mass is removed en masse.
8. *Anatrophic pyelolithotomy*: After exposing the kidney, it is cooled with ice packs for 20 minutes and posterior branch of the renal artery is clamped temporarily using bull-dog clamp. The most avascular plane behind the Brodel’s line is thus visualised properly. Kidney is opened through this line and stone/stones are removed (anatrophic means “to prevent atrophy”).

URETERIC CALCULI

- Always of renal origin.
- Nature of stones are same as that of renal stones.
- They are commonly of elongated shape.
- They can get impacted at various narrow junctions.

Sites

- PUJ.
- Where ureter crosses the iliac vessels.
- Where ureter crosses vas deferens/broad ligament.
- Where ureter penetrates outer layer of bladder muscle.
- In the intramural portion of ureter near the ureteric orifice.

Stones less than 5-8 mm size may pass spontaneously.



Fig. 26.68: Sites of ureteric narrowing.

Problems with ureteric stones

- Obstruction
- Hydronephrosis
- Infection
- Impaction
- Ureteral stricture

Clinical Features

1. *Pain*—it is of colicky type and radiates from loin to groin often to the tip of the genitalia, testis in males, labia majora in female (referred along the genitofemoral nerve).

   It is severe in intensity, increases with exercise.

   It mimics *appendicitis, cholecystitis, ovarian* or *tubal pathology*.
2. Nausea, vomiting, sweating due to pain and reflex pylorospasm.
3. Haematuria, dysuria, frequency, strangury.
4. Tenderness in iliac fossa and renal angle (no rebound tenderness).

Investigations

- Urine—microscopy, C/S.
- Plain X-ray, KUB—radio-opaque stones are visible in 90% of cases—in the line of ureter (near the tips of transverse processes of lumbar vertebrae, sacroiliac joint and medial to ischial spine).

  Lateral or oblique films are required to differentiate from other opacities which mimic stone.
- IVU shows hydronephrosis and hydroureter. Function may be accurately assessed by isotope renogram.
- Blood urea, serum creatinine, serum calcium, uric acid level.
- U/S is useful.
- CT scan is *diagnostic.*



Fig. 26.69: A plain X-ray, KUB, showing left ureteric calculi.

Differential diagnosis

- Appendicitis
- Cholecystitis
- Ovarian cyst
- Tubo-ovarian disease
- Mesenteric adenitis
- Ruptured ectopic gestation



Fig. 26.70: USG showing vesicoureteric junction (VUJ) stone which needs cystoscopic meatotomy and extraction.

Faith is like electricity, you can't see it, but you can see the light.

Treatment

1. Plenty of water orally.
2. Diuretic—oral frusemide to flush the stone.
3. Suitable antibiotics to control sepsis; antispasmodics to relieve pain.
4. IV fluids—fast infusion of about 1.5 to 2 litres and injection frusemide 60 to 80 mg. Usually given for 3 to 5 days.
5. Surgical intervention for ureteric stones:

Indications

- Size of the stone more than 5 to 8 mm
- IVU showing deterioration of function
- Co-existing infection
- If stone is impacted in the ureter with persistent symptoms



Fig. 26.71: Ureteric stone.

Procedures

Upper third stone:

- ESWL for stone in upper third ureter.
- The stone is pushed into the renal pelvis and then PCNL is done.
- URS—*Ureterorenoscopic stone removal*:
  - Through ureteroscope, stone is visualised and often fragmented using pneumatic bombarder. It is then extracted by ureteroscope.
  - Complications are perforation of ureter and extraperitoneal leakage of urine, bleeding.
- Open *ureterolithotomy* through loin incision.

Stone in middle third ureter:

- URS.
- Open ureterolithotomy.

Stone in lower third ureter:

- URS.
- *Dormia basketing*:



Fig. 26.72: 'J' stent right side—used after URS (ureterorenoscopy) in ureteric stone extraction.



Fig. 26.73: Dormia basket is used to remove the stone in the lower ureter. Single stone less than 1 cm can be removed.

Indications for Dormia basketing

- Stone in lower third ureter
- Stone below pelvic brim
- Stone less than 10 mm size
- Single stone

Basket is passed into the proximal ureter beyond the stone and opened. The stone is then pulled out.

Complications of Dormia basket

- Stone dislodgement
- Urethral injury
- Avulsion of ureter
- Stricture ureter

- Open ureterolithotomy.
- Using cystoscope under general anaesthesia, *ureteric meatotomy* is done for stones impacted at the ureteric orifice. It is released by cutting the orifice at upper and lateral aspects.

Note:

All ureteric stones can be removed through laparoscopy or retroperitoneoscopy.



Fig. 26.74: Approaches for removal of ureteric stones.

RECURRENCE OF STONES

Types of recurrence:

a. False recurrence—during intervention, tiny fragments may be left behind.
b. True recurrence—recurred again once all stones are cleared by intervention.

Causes for recurrence:

Existing causes like hyperparathyroidism, hypercalciuria, hyperuricaemia, gout, cystinuria.

Prevention and advice

- Hydration is the main method of prevention. Per day 3 to 4 litres of fluid should be taken.
- Diet:
  - Avoid diets rich in calcium oxalate, sodium (natriuresis causes hypercalciuria) and vitamin C (gets converted into oxalate).
  - Increased intake of dietary fibre—binds with intestinal calcium and decreases the calcium absorption. *Sodium cellulose phosphate is used* for the same.
- *Allopurinol* reduces the uric acid level and so uric acid stone. It also reduces the oxalate level.
- Diet rich in *magnesium* makes calcium oxalate less soluble.
- *Aluminium gel* or *ammonium chloride* prevents the excessive alkalinity and so prevents the recurrence of phosphate stones.
- *Penicillamine* or *alpha-mercaptopropinyl-glycine* may reduce the recurrence rate of cystine stones.
- In idiopathic hypercalciuria, strict low calcium diet along with 5 mg bendrofluzide which reduces loss of calcium in urine or indomethacin 25 mg tds which reduces the calcium secretion or sodium phytate can be given.
- Acetohydroximic acid due to structural similarity to urea is a potent inhibitor of urease and so reduces the bacterial originated stone.

STAGHORN CALCULUS

- It is the stone occupying the renal pelvis and calyces.
- It is usually phosphate or ammonium, magnesium phosphate *(Triple phosphate*) stone.
- It is white in colour, soft, smooth, occurs in pre-existing infection (commonly *E. coli*).
- It can be *unilateral* or *bilateral***.** Patient with *bilateral* stones may go in for *renal failure.*



Fig. 26.75: Staghorn calculus.



Fig. 26.76: Staghorn calculus (diagrammatic representation).

Presentation

- Pain in loin
- Fever
- Burning micturition
- Haematuria
- In bilateral cases, symptoms are bilateral and often with features of renal failure (hiccough, oedema feet, oliguria, anaemia)



Fig. 26.77: Bilateral staghorn calculi.

Investigations

- U/S, abdomen.
- Plain X-ray, KUB.
- IVU to see the renal function.
- Blood urea and serum creatinine.
- Urine microscopy and urine C/S.
- Isotope renogram—DTPA.



Fig. 26.78: A plain X-ray, KUB, revealing staghorn calculus on right side.

Treatment

Antibiotic is started.

1. *Unilateral stone* is removed by *nephropyelolithotomy*. Multiple incisions are made over the Brodel's line (avascular plane) and assisted by pelvic incision. Stone is removed. Blood transfusion may be necessary as bleeding can occur.
   After that, nephrotomy and pyelotomy incisions are sutured with chromic catgut or vicryl.
2. In *bilateral cases* IVU is very essential. The kidney which is functioning better should be treated first. After 3 months, the other side kidney should be operated upon.
3. If there are *bilateral staghorn calculi with pyonephrosis,* then initially bilateral nephrostomy is done using Malecot's catheter *(Cabot's nephrostomy*). IVU is done later to see the renal function. If function is present, then both kidneys are operated one after the other in a gap of 3 months. They often need *haemodialysis.*
4. Sometimes in case of severe infection *nephrectomy* is required.

Presently, PCNL is becoming a popular procedure for unilateral or bilateral staghorn calculi.

But when required, *conversion to open nephropyelolithotomy* should be considered.



Fig. 26.79: Nephropyelolithotomy. Note the incisions placed.

Complications of staghorn calculus

- Pyelonephritis
- Pyonephrosis
- Perinephric abscess
- Renal failure

Differential diagnosis for radio-opaque shadow which mimics renal stone

- Calcified lumbar or mesenteric lymph node
- Gallstone (10% are radio-opaque)
- Concretion in appendix
- Phleboliths
- Ossified tip of 12th rib
- Chip fracture of transverse process of vertebra
- Calcified renal tuberculosis
- Calcified suprarenal gland
- Drugs or foreign body in the alimentary canal

BENIGN TUMOURS OF KIDNEY

They are rare.

Types

- *Renal papillary adenoma*: Small discrete adenoma arises from tubular epithelium, < 5 mm in size, cortical, yellow circumscribed tumour. It is potentially malignant, may turn into papillary type of RCC, especially if size > 3 cm.
- *Angiomyolipoma*: It contains fat, vessels and smooth muscles. It is commonly associated with tuberous sclerosis (50%). Tumour is susceptible for spontaneous haemorrhage.
- *Oncocytoma:* It is an epithelial tumour arising from intercalated cells of collecting ducts. Its cells show large nucleoli. These large eosinophilic cells contain numerous mitochondria. Tumour is homogenous well encapsulated tan coloured. It can attain large size and can be multicentric.

WILM'S TUMOUR (NEPHROBLASTOMA)

> *The patient was a 3-year-old girl with a kidney tumour which had grown to immense proportions in a short time. The child, anemic and emaciated, was admitted with an enormous mass in the right abdomen and with definite ascites. After nephrectomy, the little child recovered uneventfully. A few months later, however, a recurring abdominal mass was again palpable and shortly afterward the child died.*
>
> —**Max Wilms,** 1899

- It arises from embryonic connective tissue containing epithelial and connective tissue elements.
- It is located in one of the poles of the kidney.
- It is bilateral in 5% cases. It is common in first 4 years of life.

Pathology

Gross

It is smooth, soft, fleshy, pinkish white in colour, often with haemorrhagic areas.

Microscopically

Malignant primitive glomeruli and primitive tubules, with epithelial and connective tissue cells exist side by side, one of the types is usually prominent.

Types

A. *Favourable histology (FH)—Wilms'—means without anaplastic features*
B. *Unfavourable histology (Un FH)—Wilms'—means with anaplastic features*

Histological Types

- Cystic nephroma.
- Mesoblastic nephroma.
- Nephroblastoma.

Spread

Mainly through blood into the lungs, liver and rarely to bones.

Clinical Features

- Incidence is equal in both sexes.

Triad

Mass, fever, haematuria

- *Mass abdomen is commonest presentation*. Mass is smooth, mobile, firm or hard, lobular, located in the loin, moves with respiration, bimanually palpable, ballotable, with dullness in renal angle and with resonant band in front. It does not cross the midline (Differential diagnosis is adrenal neuroblastoma which is knobby and nodular, does not move with respiration and crosses the midline).



Fig. 26.80: X-ray showing mass lesion in right abdomen. It could be Wilm's tumour.



Fig. 26.81: Renal tumour.

- *Fever*—may be due to tumour necrosis.
- *Haematuria* is a grave sign as it signifies rupture of tumour into the renal pelvis.
- *Hypertension*—in 25% cases.
- 12% of cases are associated with congenital anomalies and syndromes (Glaucoma, aniridia, Beckwith syndrome).

Staging of Wilm's

I. Disease confined to kidney and completely resectable
II. Tumour extends beyond kidney, but can be excised completely
III. Residual disease after resection with positive lymph nodes and massive spillage
IV. Blood born metastasis
V. Bilateral disease

Investigations

- U/S abdomen, CT scan abdomen.
- IVU.
- Renal angiography.

Imagination is the highest kite one can fly.

- X-ray, abdomen—*egg shell* peripheral calcification is diagnostic.
- MRI.

Differential diagnosis

- Adrenal tumour
- Retroperitoneal tumour
- Renal cyst
- Polycystic kidney disease

Treatment

- *Nephrectomy and postoperative radiotherapy in case of unilateral tumours.*
- In bilateral cases, either bilateral partial nephrectomy or nephrectomy on one side with partial nephrectomy on the other side is done *(Nephron sparing surgery)*.



Fig. 26.82: Partial nephrectomy.

- *Chemotherapy:* Actinomycin D, vincristine, doxorubicin.
- Preoperative RT in locally inoperable cases—later surgery and then chemotherapy is given.

Prognosis

Five years survival rate is 80% under the age of one year. Recurrence rate is high within one year.

Prognostic Factors

Age, bilaterality, size of the tumour, presence of haematuria, spread of tumour, histology type.

RENAL CELL CARCINOMA (RCC)

Also known as *Hypernephroma—(it is a misnomer), Grawitz tumour, clear cell carcinoma, Internist tumour.*

- It is an adenocarcinoma arising from renal tubular cells, most common site is proximal renal tubule. More common in males; more common in 5th-6th decade of life.
- It is 3% of all adult malignancies.
- **RCC types**:
    - *Clear cell* (75%)—nonpapillary, associated with loss of sequence in short arm of chromosome no.3. It can be sporadic (common, 95%) or familial.
    - *Papillary* (15%)—multifocal commonly, with papillary pattern.
    - *Chromophobe RCC* (5%)—arising from intercalated cells of collecting duct; shows halo around the nucleus; carries excellent prognosis.
    - *Collecting duct of Bellini carcinoma* (1%)—arises from collecting duct of medulla; tumour with fibrous stroma typically in medullary location.

Aetiology

- It is associated with von Hippel-Lindau disease (cerebellar haemangioblastoma, retinal angiomatosis, tumour or cysts of pancreas). Here RCC is commonly bilateral
- Diet high in animal fat
- Environmental factors like asbestos, lead, cadmium and tobacco
- Cigarette smoking
- Chromosomal aberration, tuberous sclerosis
- Acquired cystic kidney disease after long-term dialysis
- *Birt-Hogg-Dube' syndrome* with hereditary chromophobe RCC and oncocytoma
- Cortical renal adenoma could be RCC by itself
- Analgesic nephropathy

Pathology

Gross

It attains a large size. Commonly located in *upper pole*, sometimes in lower pole but rare in the middle. Cut section is *yellowish* due to lipoid content with areas of haemorrhage and necrosis. This noncapsulated tumour is very vascular.

Microscopy

Malignant cells which are cubical or polyhedral containing lipid, cholesterol and glycogen.

Histological types—clear (75%), granular, spindle, sarcomatoid, papillary (15%)

Spread

1. *Local*: Into the perinephric pad of fat, calyces and renal pelvis.
2. *Blood spread*: RCC enters the renal vein as *proliferating tumour thrombus,* which extends into the IVC and later gets detached causing "*cannon ball secondaries"* in the lung, which are often calcified. Once primary tumour is removed, secondaries may regress due to tumour immunity. Occasionally, secondaries occur in bone, liver and brain. Left testicular vein which drains into left renal vein may gets blocked by proliferating tumour thrombus resulting in *irreducible left sided varicocele. More than 50% spread to lungs; 30% to bones*; then liver, adrenal and brain.
3. *Lymphatic spread*: To hilar lymph nodes, para-aortic lymph nodes.



Figs 26.83A to C: Renal cell carcinoma in upper pole of kidney—resected specimen. It is from two different patients.

AJCC (American Joint Committee on Cancer) Staging: TNM Staging

Tx: Primary tumour cannot be assessed
T0: No primary tumour
T1: Tumour less than 7.0 cm size, limited to kidney
T1a is tumour 4 cm or less; T1b is tumour 4-7 cm in size
T2: Tumour more than 7.0 cm size, limited to kidney
T3: Tumour extends into major veins, adrenals, perinephric fat but not into the Gerota's fascia
  T3a : Into adrenal or perinephric tissue
  T3b : Into renal vein or IVC below diaphragm
  T3c : Tumour extends into IVC above the diaphragm
T4: Tumour invades Gerota's fascia and extends beyond
N0: No lymph nodes
N1: Spread to single regional lymph nodes
N2: Spread to more than one regional lymph nodes
M0: No blood spread
M1: Distant spread to—lungs (75%); soft tissues (25%); bones (20%); liver (15%); CNS (8%); skin (8%)

Robson-Flocks and Kadesky staging

Stage 1 Tumour confined to renal parenchyma
Stage 2 Tumour invasion to perinephric fat but confined within Gerota's fascia
Stage 3 a. Tumour invasion to renal vein or IVC
  b. Invasion to regional lymph nodes
  c. Both a + b
Stage 4 Invasion to adjacent organs other than adrenal
  Distant metastasis

Note:

45% present as early disease; 25% as locally advanced disease; 30% as metastatic disease.



Fig. 26.84: CT scan showing RCC—left sided.

Clinical Features

- M : F :: 2 : 1.
- Haematuria—30%.

The men who make history have no time to write it.

- Clot colic.
- Dragging discomfort in the loin.
- Mass in the loin which moves with respiration, mobile, nodular, hard, with dull renal angle and resonant band in front.
- Left-sided *varicocele* which is *irreducible* in left-sided RCC.

Triad of RCC

- Pain
- Haematuria
- Palpable renal mass

Atypical presentations: 25%

- Due to secondaries:
  1. Pathological fractures.
  2. Persistent cough and haemoptysis.
- *Persistent pyrexia* with no evidence of infection ***(P**yrexia of **U**nknown **O**rigin)—20%
- *Constitutional symptoms:* Malaise, lethargy and severe anaemia.
- *Polycythemia:* 4%—due to increased secretion of erythropoietin.
- Hypercalcaemia, hypertension. Hypercalcaemia due to PTH like hormone secretion, hypertension is due to increased secretion of renin from kidney tissue adjacent to tumour.

Surgical renal conditions associated with hypertension

- Polycystic kidney disease
- Renal cell carcinoma
- Renal artery stenosis

- *Nephrotic syndrome:* Very rare.
- *Stauffer's syndrome:* Nonmetastatic reversible liver dysfunction which gets corrected after nephrectomy. It is 7% common. It carries poor prognosis.
- Cushing's syndrome.
- Leukaemoid reaction due to bone marrow stimulation.
- Secondary amyloidosis 5%.

Investigations

- Urine microscopy for RBCs.
- IVU—shows mass lesion and irregular filling defect.
- U/S, abdomen—to know the size, extension, lymph node involvement, spread to the liver, status of renal vein and IVC.
- *CT scan*: It is confirmatory and also helps to know the status of renal vein and IVC. Multi-detector CT and CECT (contrast enhancement CT) are very useful in detecting early lesion/function/spread/venous status. Lymph node status, tumour extension are well made out with CT. Contrast enhancement CT scan helps to find out function of opposite kidney and tumour thrombus in renal vein or IVC.



Figs 26.85A and B: CT scan showing features of renal cell carcinoma.

- *Renal angiogram* through Seldinger technique via transfemoral route, to see the vascularity. *Pharmacoangiogram* (Inject noradrenaline along with dye while doing angiogram). As tumour vessels are autonomous they will not constrict whereas adjacent normal vessels will constrict, so *tumour blush* is visualised. Through angiogram therapeutic embolisation of tumour can be done to reduce the vascularity of tumour.
- Chest X-ray shows *cannon ball s*econdaries. Often it is *calcified.*
- *CT chest is ideal and more reliable.*
- Bone scan to see bone secondaries.
- Peripheral smear, serum calcium, haematocrit and ESR.
- *Inferior venacavagram* to assess the tumour extension through renal vein into IVC and extension in the IVC infra- or supradiaphragmatic.
- MRI is diagnostic to assess the tumour thrombus in IVC. MRI/MR angiogram is unique in identifying the spread into IVC especially in the thorax. In such occasion oesophageal endosonography is also useful to visualise thoracic extension of the tumour thrombus.

Differential diagnosis

- ❖ Polycystic kidney disease
- ❖ Solitary cyst of kidney
- ❖ Adrenal tumour
- ❖ Retroperitoneal tumour
- ❖ Carcinoma colon



Fig. 26.86: CT scan of carcinoma right kidney.

Treatment

Surgery is the treatment of choice.

- ♦ *Radical nephrectomy*:

Structures removed are:

- ❖ Entire kidney along with tumour
- ❖ Perinephric tissue
- ❖ Ipsilateral adrenal gland
- ❖ Proximal 2/3rd ureter/as low as possible
- ❖ Lymph nodes from crus of diaphragm to aorta bifurcation with renal hilar nodes

  - ▸ Transperitoneal approach is often used. Retroperitoneal/Nagamatsu (resection of 11th ribs) approach/thoracoabdominal approach/posterior vertical are other approaches used. Patient will be in lateral position. After laparotomy, colon is mobilised medially. Vessels are identified and dissected and ligated securely (transfixation and three ligatures proximally using nonabsorbable silk/polypropylene sutures).
  - ▸ Preoperative renal artery embolisation can be done to decrease vascularity and to facilitate the removal of entire tumour.
  - ▸ Always renal vein is ligated early so as to prevent tumour dislodgement (But early ligation of renal vein may cause congestion and torrential bleeding and so renal artery is ligated first commonly in practice). But usually renal artery which is posterior is dissected and clamped or ligated in continuity; then renal vein is ligated and divided; later ligated renal artery is divided. In case of IVC extension, after applying an oblique vascular clamp, IVC is opened, tumour thrombus is removed and IVC is sutured. In supradiaphragmatic vena caval extension of thrombus, cardiopulmonary bypass is necessary. First renal vessels (artery and vein) should be ligated to prevent tumour dissemination and bleeding.



Fig. 26.87: Renal cell carcinoma, on table after nephrectomy. Note the vascular pedicles.

- ♦ Even in large fixed tumour, palliative nephrectomy or debulking is advised as it may cause regression of secondaries.
- ♦ *Nephron sparing surgeries* is done in bilateral RCC (Bilateral partial nephrectomy). Renal artery is temporarily occluded using vascular clamps and kidney is cooled to have proper control of bleeding and adequate visualisation of the line of resection. Partially resected specimen is assessed by frozen section biopsy. Retained partial capsule is sutured after haemostasis. Renal arterial clamp is released.
- ♦ *No role for radiotherapy.*
- ♦ *Chemotherapy:* Vinblastine and progesterone can be tried. RCC is a remarkably refractory solid tumour—chemoresistant.
- ♦ Interferons and interleukins have shown beneficial effects.
- ♦ Preoperative renal artery embolisation can be done to decrease the vascularity of the tumour (Using clot, gelfoam, spheres).
- ♦ Antiangiogenic drugs like endostatin and angiostatin are under trial. RCC is highly vascular and there is highly angiogenic environment to give possible benefit by anti-angiogenesis.
- ♦ Patient with solitary lung metastasis may get benefited by wide resection of the secondary.
- ♦ Humanised monoclonal antibodies like bevacizumab which neutralises VEFG are under trial.

Note:

- Laparoscopic approach is becoming popular. Here renal artery is ligated first.
- ***Sisitinab***, a multitargeted tyrosine kinase inhibitor prevents angiogenesis and tumour proliferation is said to be useful.

Prognosis

- Five-year survival rate is 40%.
- In early localised disease, it is 70-90%. In advanced and metastatic disease it is 10-15%
- 5-year survival is 65% for stage I and II; 40% for stage III; 10% for stage IV

Prognostic factors are:

- Tumour size more than 4 cm carries poor prognosis
- Extension into the renal vein
- Presence of secondaries
- Differentiation
- Local extension
- Hypercalcaemia and Stauffer's syndrome carry poor prognosis

Note:

- Most common type of renal pelvis and ureteric tumours is transitional cell carcinoma (90%).
- Renal pelvic tumours account for 5% of renal tumours. It is common in Taiwan.
- It is more aggressive.
- Treatment is radical nephroureterectomy with removal of cuff of bladder adjacent to ureteric orifice.

APPROACHES TO KIDNEY (SURGICAL)

- Posterior subcostal (oblique lumbar incision).
- Laparotomy approach (anterior approach).
- Thoracoabdominal approach.
- Nagamatsu approach (approach following excision of 11th rib in case of upper pole tumour).
- Posterior vertical lumbotomy approach (Gilvernet's approach).
- Laparoscopic approach.
- Retroperitoneoscopic approach.



Fig. 26.88: On table position to approach kidney surgically.

B. Urinary Bladder

CHAPTER OUTLINE

- Anatomy
- Ectopia Vesicae
- Urachal Anomalies
- Vesical Calculus
- Cystitis
- Recurrent Cystitis
- Interstitial Cystitis
- Schistosoma Haematobium
- Thimble or Systolic Bladder
- Bladder Tumours
- Transitional Cell Carcinoma
- Ureterosigmoidostomy
- Rupture Bladder
- Residual Urine
- Malakoplakia
- Neurogenic Bladder
- Vesicoureteric Reflux
- Bladder Diverticula
- Urinary Diversion
- Urinary Fistulas

ANATOMY

- It is a muscular reservoir of urine situated in the pelvis, posterior to the pubic bone from which it is separated by the retropubic space.
- The size, shape, position of bladder depends on the amount of urine it contains.
- In females, the peritoneum is reflected from the superior surface of the bladder onto the anterior wall of the uterus close to the junction of the body of the uterus and cervix.
- In males, the peritoneum is reflected from the superior surface of the bladder over the superior surface of the ductus deferens and seminal vesicles.
- The neck of the bladder is the most fixed part, lies 3-4 cm behind the pubic symphysis. In males it lies on the prostate and in females it rests on the anterior vaginal wall which is also supported by the levator ani muscle.

Structure of the Bladder

- The bladder wall consists of interlacing fibres of smooth muscle. The urothelium consists of transitional epithelium which is loosely attached and easily separated from the bladder wall except over the *trigone*.
- *Trigone* is a triangular area over the lower part of the base of the bladder. The ureters opens into the posterolateral angles of the trigone. The internal urethral orifice opens at the inferior angle of trigone.

Sphincters

- *Internal sphincter*: Smooth muscle, situated at the neck of the bladder, micturition follows its relaxation. It is innervated by autonomic nervous system.
- *External sphincter*: It consists of striated muscle, innervated by the perineal branch of pudendal nerve (S_2,S_3).



Fig. 26.89: Anatomy of urinary bladder—posterior aspect.



Fig. 26.90: Urinary bladder—inner anatomy.

Retrograde cystogram is the most reliable investigation in case of bladder rupture.

Blood Supply

- Superior vesical artery, a branch of internal iliac artery.
- Inferior vesical artery:
  - Venous drainage is by the vesical plexus of veins, which drains into the internal iliac veins. These veins connect directly to veins of hip bones, the heads of femoral and vertebral bodies. This accounts for the site of occurrence of bony metastasis in carcinoma of the bladder and prostate.

Lymphatic Drainage

Lymphatics drain into internal iliac and external iliac nodes.

ECTOPIA VESICAE (Extrophy of the Bladder)

- It is incomplete development of the infraumbilical part of the anterior abdominal wall and anterior wall of the bladder. It is of embryological origin.
- It is often associated with the spina bifida and other congenital anomalies.
- It is more common in males (4 : 1).
- Red mucus membrane of posterior bladder wall protrudes out with visible urine efflux from ureteric orifice.
- Umbilicus is absent.
- There is separation of pubic bones.
- In males, *epispadias* is commonly present with rudimentary prostate and seminal vesicle.



Fig. 26.91: Child showing extrophy bladder.

- Testes are normal.
- Bilateral inguinal hernias are common.
- In females defective external genitalia is common.

Problems

- Repeated soakage
- Ulceration
- Pain
- Recurrent pyelonephritis
- Renal failure
- Metaplastic changes in mucosa can lead into *adenocarcinoma*
- **50%** of patients die of renal failure

Treatment

- Staged procedure.
- Initial diversion of urine to colon/rectum.
- Iliac osteotomy and closure of the abdominal wall.
- Correction of epispadias.
- Sometimes cystectomy and permanent ureterosigmoid diversion is required.
- Condition has got high mortality due to infection and renal failure.

URACHAL ANOMALIES

- *Patent urachus with urine leak*: It signifies obstruction distal to bladder.
- *Urachal sinus with discharge.*
- *Urachal cyst:* Present as immobile, fluctuant swelling in the abdominal wall.

Sepsis, tuberculosis, adenocarcinoma, can occur in patent urachus.

VESICAL CALCULUS

> *The signs of a stone in the bladder are, great and frequent irritations to make water, a stoppage in the middle of making it, and a pain with heat just after it is made; a tenesmus, pain in the extremity of the urethra, incontinence or suppression of urine, together with a quiet pulse, and the health in no bad state.*
>
> —**William Heberden,** 1802



Figs 26.92A and B: Ectopia vesicae in a man of 25 years old.

Types



Fig. 26.93: Bladder stones—oxalate and phosphate. Phosphate stone has occurred in an indwelling J ureteric stent.

- ***Primary vesical calculus*****:** Occurs in sterile urine.
  - Usually comes down from kidney through ureter into the bladder and it gets enlarged here. It is usually *oxalate* stone (Jack stone).
  - Oxalate stone is usually single, primary stone, brownish black in colour (due to deposited blood pigment over the surface), hard and with spikes over the surface which irritates bladder mucosa causing haematuria *(mullberry stone)*.
- ***Secondary vesical calculus***: Occurs in the presence of infection. Most common bladder stone.
  - It is usually *phosphate stone*, occurs in bladder only.
  - Phosphate stone is smooth, soft, ivory-white in colour. It is either calcium phosphate or ammonium, calcium and magnesium phosphate *(Triple phosphate stone)*.
  - *E. coli* is the common organism.
- ***Uric acid and urate stones*** are single or multiple, primary, nonradio-opaque, smooth, pale yellow in colour.
- ***Cystine calculus**:* Occurs in cystinuria and is radio-opaque due to high sulphur content.

Aetiology

- Infection
- Hypercalciuria of any cause
- Hyperoxaluria
- Cystinuria
- Bed ridden and paraplegic patients
- Gout and other hyperuricaemic patients
- Diverticula bladder
- Obstruction to urine flow by BPH, urethral stricture, bladder neck obstruction
- Neurogenic bladder
- Schistosomiasis
- Foreign body in bladder



Fig. 26.94: Large bladder stone removed by open suprapubic extraperitoneal cystolithotomy.



Fig. 26.95: Plain X-ray KUB showing large bladder stone.

Clinical Features

- Common in males. Often occurs in children.
- *Frequency* is more during day than night, because during day, due to ambulation stone comes in contact with the trigone of the bladder and irritates, whereas during night, stone slips towards the fundus, away from the trigone and so less frequency and pain.
- *Pain*: More during day which is referred to the tip of penis or labia. Also increases during jolting movements. Suprapubic pain and tenderness may be present.
- *Haematuria***:** Often terminal.

It is better to have an idea than to have thousand opinion.

- Interruption of urinary stream and often acute urinary retention.
- Features of cystitis: Burning micturition, fever, pain.
- P/R or P/V: Large stone may be palpable.
- Stone may be identified incidentally in plain X-ray, KUB or U/S, abdomen.



Fig. 26.96: Plain X-ray showing dermoid cyst of ovary with calcification. It is teratoma of ovary.

Investigations

- Urine microscopy
  - Envelope crystals in oxalate stone,
  - Hexagonal type in cystine stone.
- Urine C/S.
- Blood urea, serum creatinine, serum calcium, inorganic phosphate, uric acid.
- Plain X-ray, KUB shows radio-opaque stones—90% are radio-opaque.

Radiological D/Ds for vesical calculi in females:

- Calcified fibroid uterus
- Dermoid cyst ovary

- IVU to see function of the kidney.
- U/S abdomen is diagnostic.
- Cystoscopy to see radioluscent stone.



Figs 26.97A and B: A plain X-ray, pelvis showing (A) Phosphate stone. Note the laminations. (B) Oxalate stone. Note the spiculated margins.



Fig. 26.98: Plain X-ray revealing multiple bladder calculi.



Fig. 26.99: Dermoid cyst ovary. Note the radio-opaque teeth.



Figs 26.100A and B: X-ray showing vesical calculus. Note the laminated appearance.



Figs 26.101A and B: Two types of bladder stones—one with surface projections, other with smooth surface.

Treatment

1. **Cystoscopic litholapaxy**
   Under GA, cystoscope is passed and the stone is visualised. It is fragmented by pneumatic, laser, electromagnetic waves or mechanohydraulic lithotripsy. The bladder is flushed using an irrigator (Freyer's evacuator or irrigator or Ellik's evacuator).

Contraindications

- Too large stone
- Too small stone. Too soft stone. Too many stones
- Stone in bladder diverticula
- Bladder tumour
- Contracted bladder
- Patient's age below 10 years
- When patients general condition is poor, as the procedure takes a longer duration it is avoided and open removal is advised

2. **Suprapubic open cystolithotomy**
   Through pfannenstiel incision, bladder is approached extraperitoneally. Bladder is identified by its detrusor muscle pattern, which is criss-cross and also its venous pattern. Bladder is opened near the fundus and stone is removed. Bladder is closed often with SPC using Malecot's catheter and Foley's catheter is passed per urethera. Wound is closed in layers with a drain.
3. **Suprapubic percutaneous litholapaxy**
   This procedure is becoming popular. When cystoscope cannot be passed per urethra, bladder is approached suprapubically. Through a needle, guidewire and dilators, a track is created through which a nephroscope is passed to remove the stone after fragmenting.
   The cause is treated.



Fig. 26.102: Asepto syringe used for bladder wash in patients with urinary catheter which has been blocked; or when haematuria is noticed in the catheter. It is also used to fill the bladder with saline.

CYSTITIS

Inflammation of the bladder mucosa due to different causes.

Causes

- Acute bacterial cystitis
- Chronic cystitis due to tuberculosis, syphilis
- Interstitial cystitis
- Radiation cystitis
- Cystitis due to schistosomiasis
- Postmenopausal atrophic cystitis

Predisposing Factors

- Congenital urinary tract anomalies
- Short urethra in females may cause ascending infection and cystitis.
- Initial period of sexual contact in females can cause cystitis—Honeymoon cystitis.
- Catheters, instrumentation.
- Bladder stone.
- BPH, carcinoma prostate.
- Cystocele, bladder diverticulum.
- Stricture urethra, bladder neck obstruction.
- Bladder tumours.
- Pregnancy.
- CNS diseases, spinal injury.

Organisms

- *E.coli, Klebsiella, Pseudomonas, Staph. aureus, Staph. albus, Proteus.*
- *Candida albicans*, fungal infection.

Features

- Painful urination, frequency, strangury, incomplete emptying, with often retention.
- Occasionally haematuria can occur.
- Burning urine, discoloured foul smelling urine.
- Fever, chills, rigors, suprapubic pain and tenderness and often loin pain.
- Septicaemia can develop in severe cystitis.

Investigations

- Total count will be raised.
- Urine will show pus cells and culture will reveal the organisms.
- X-ray may show a stone. IVU, cystogram are also helpful.
- U/S abdomen will show thickening of bladder mucosa, stone, tumour.
- Cystoscopy reveals bladder inflammation, mucosal changes.

Treatment

- Appropriate antibiotics like quinolones, aminoglycosides, cephalosporins.
- Plenty of water intake to flush the bacteria from the bladder.
- Often admission and parenteral antibiotics may be needed.
- Evaluation and therapy for cause should be done.
- Strict aseptic precaution is used while catheterisation, cystoscopy.
- Often long-term antibiotics are needed to prevent recurrent infection.

RECURRENT CYSTITIS

Causes

- Failure of early treatment for acute cystitis
- Reinfection by same or different organisms.

Types

- Chronic cystitis.
- Phosphate deposition in the ulcerated mucosa causing encrusted cystitis.
- Proliferation of mucosa and submucosa causing proliferative cystitis. It may be cystitis follicularis, cystitis polyposa, cystitis glandularis, cystitis cystica.
- Gas filed cysts in the submucosa causing cystitis emphysematosa.
- Necrosis of bladder wall can occur leading to gangrenous cystitis.

Management

- Urine microscopy and culture.
- Antibiotic and urinary antiseptics like hippuric acid, mandelic acid.
- Proper hygiene.
- Plenty of oral fluid intake and frequent emptying of the urine.

INTERSTITIAL CYSTITIS (Hunner's Ulcer, Elusive Ulcer)

- It is common in females
- Common in western countries
- Common in psychic females

Pathology

There is pancystitis with fibrosis of vesical musculature along with linear ulcers in the bladder mucosa. Microscopically, severe inflammation of all layers of bladder with fibrosis is observed. Bladder eventually becomes **thimble (systolic) bladder** with decreased bladder capacity up to 30-60 ml (less than 100 ml).

Clinical Features

- Pain.
- Decreased bladder capacity.
- Pain increases with bladder distension.
- Frequency and often haematuria.

Investigation

Cystography and cystoscopy are diagnostic.

Treatment

- Hydrostatic dilatation.
- Instillation of dimethyl sulphoxide (Rimso 50).
- Ranitidine instillation.
- Ileocystoplasty or caecocystoplasty, to increase the bladder capacity.
- Urinary diversion.

Differential Diagnosis

Other causes for thimble bladder.

SCHISTOSOMA HAEMATOBIUM (Endemic Haematuria, Urinary Bilharziasis) (Swimmer's Itch)

Life Cycle

Fresh water snail—(Intermediate host)
↓
Bifid tailed embryos (cercariae) in infected water
↓
Penetrate the skin
↓
Through circulation enters the liver
↓
Male and female worms formed
↓
Sexual fusion and maturity occurs
↓
Flows through the portal vein in retrograde direction along the inferior mesenteric vein
↓
Vesical venous plexus
↓
Bladder wall and submucosa
↓
Ova are released
↓
Enters the bladder through the mucosa
↓
Ova are released into the urine and to water
↓
Ciliated miracidium
↓
Fresh water snail
↓
Death of snail releases thousands of cercariae.

Pathology in the Bladder

- Bilharzial pseudotubercles—earliest sign.
- Nodules.
- Sandy patches—calcified dead ova with degeneration of overlying epithelium.
- Granulomas.
- Ulceration and papilloma.
- Fibrosis and thimble bladder formation.
- In due course of time, development of *squamous cell carcinoma*.
- Other pathologies: Ureteral and urethral stricture, recurrent UTI, bladder calculi, urinary fistula.

Clinical Features

- Initially cutaneous lesions like utricaria develops lasting for few days.
- Then after a period of 4-8 weeks, fever, along with features of eosinophilia develops.
- Eventually, after many months it causes intermittent, painless, *terminal haematuria*.

Investigations

- Cystoscopy and biopsy.
- IVU.
- Cystography.
- Urine microscopy: Last few ml of early morning urine sample is collected to see for ova and RBCs.

Differential diagnosis

- Tuberculosis
- Recurrent cystitis
- Malignancy

Treatment

- Long-term *Praziquantel* or metrifonate.
- Surgery for thimble bladder—ileo-or caecocystoplasty.
- Cystoscopic diathermy fulgaration of papillomas.
- Radical cystectomy, if it is squamous cell carcinoma of the bladder.

THIMBLE OR SYSTOLIC BLADDER

It is inability of the bladder to relax and distend and so inability to retain the urine as required.

Causes

- Tuberculous cystitis
- Schistosoma haematobium
- Interstitial cystitis
- Radiotherapy
- Malignancy
- Previous bladder surgery

- Bladder is fibrotic and contracted, with difficulty in dilating and accommodating urine as needed.
- Bladder capacity is less than 100 ml (60 ml).

Time won't stand with us; we have to stand with time.

Clinical Features

- Features of decreased bladder capacity
- Frequency of urine
- Features of recurrent cystitis

Investigations

- Cystoscopy.
- Cystography.
- IVU.
- Urine C/S.
- Specific diagnostic tests.

Treatment

- The cause is treated.
- Hydrostatic dilatation.
- Augmentation of bladder by doing ileocystoplasty or *caecocystoplasty* or *sigmoidocystoplasty*.
- Steroids are also tried.

BLADDER TUMOURS

They are urothelial tumours. They are commonly malignant. Benign tumours are rare. Transitional cell carcinoma (TCC) is the most common.

1. Primary

a. ***Epithelial***
  - *Transitional cell carcinoma* (90%).
  - *Adenocarcinoma*, arising from urachal remnant or in exstrophy bladder or from glandular metaplasia (2%).
  - *Squamous cell carcinoma* originates from bilharzial infection (5%) or calculus.

b. ***Connective tissue tumour:***
  - Myoma, angioma, fibromas, sarcomas.
  - Extra-adrenal phaeochromocytoma.

2. Secondary

From adjacent organs like sigmoid colon, rectum, uterus, ovary, prostate.

TRANSITIONAL CELL CARCINOMA (TCC)

- It is the most common type of bladder tumour.
- It is the 4th most common nondermatological cancer in man.

Aetiology

3C's
  - Chemical carcinogens.
  - Cigarette smoking.
  - Cyclophosphamide.

- Chemical carcinogens are the main factor. 2-Naphthylamine, aminobiphenyl, benzidine, chloro-O-toluidine, chloro-aniline, other dyes.
- Occupation wise it is common in textile, dye, cable, tyre, petrol, leather workers, painters, chemical workers, sewage workers.
- Abnormal tryptophan metabolism can cause bladder cancer.
- Schistosoma haematobium; chronic irritation, etc.

Classification I

1. ***Nonmuscle invasive tumour without involving lamina propria*:** Has got excellent prognosis (70%).
2. ***Nonmuscle invasive tumour with involvement of lamina propria.***
3. ***Muscle invasive type*** (25%): Carries poor prognosis.
4. ***Carcinoma in situ*** *(flat noninvasive—5%)*:
   - Contains irregularly arranged cells with large nuclei, with high mitotic index, replacing normal urothelium.
   - This may occur alone—*Primary carcinoma in situ.*
   - It may occur in association with a new tumour—*Concomitant carcinoma in situ.*
   - It can occur in a patient who had a previous tumour—*Secondary carcinoma in situ.*
   - It has got high malignant potential with 50% mortality rate.
   - It was called earlier as 'malignant cystitis' as it causes severe dysuria, suprapubic pain and frequency (terminology not used presently).



Fig. 26.103: Pathology specimen of bladder (tumour) showing multiple papillary tumours projecting into the lumen.

Classification II

a. ***Superficial bladder tumour***:
  - It may be *papillary*, pedunculated with narrow stalk, which is often multiple.
  - It may be *sessile* with a wide base, can be single or multiple, and has got tendency to invade the muscle earlier.
  - Mucosa in and around the tumour is oedematous, red, with dilated vessels, often with encrustations. It is 70% common. Less than 5% of superficial TCC develop metastatic carcinoma.

b. ***Muscle invasive TCC***:
  - Almost always they are solid, sessile, with a broad base and with irregular ulcerated surface.



Fig. 26.104: Staging of bladder tumour.

  - It may spread through lymphatics to pelvic lymph nodes or through blood to the lung, liver and bones.
  - It has got poor prognosis.

c. ***Carcinoma in situ:***
  - Bladder tumor can be papillary or villous type. It can be low grade or high grade.

Sites

- *Lateral wall—most common (35%).*
- Trigone—next common (32%).



Figs 26.105A and B: CT scan showing bladder tumour.

Staging (Refer Fig. 26.104)

Jewett-Strong-Marshall staging

I Tumour confined to subepithelial connective tissue
II Muscle infiltration superficially
III Full thickness muscle and perivesical tissue infiltrated, but mobile
IV Fixed to adjacent organs
  IVa (prostate)
  IVb (pelvic wall)

Staging is done by bimanual palpation under G/A.

TNM staging (AJCC)

Tis – Carcinoma *in situ*
Ta – Noninvasive papillary tumour
T1 – Invading only lamina propria
T2 – Tumor invades muscularis propria
  – p T2a – Invading the inner half of the muscle
  – p T2b – Invading the outer half of the muscle
T3 – Invading the perivesical tissues
  – p T3a – Microscopic invasion
  – p T3b – Macroscopic invasion
T4 – Invasion into prostate/uterus/vagina/pelvic wall/abdominal wall
  – T4a – Into prostate/uterus/vagina
  – T4b – Into pelvic/abdominal wall
N0 – No nodes
N1 – Single regional nodal spread up to 2 cm in size
N2 – Spread to single node 2-5 cm in size or multiple nodes less than 5 cm
M0 – No distant spread
M1 – Distant spread present

Clinical Features

- Painless haematuria anaemia.
- Features of cystitis, with suprapubic pain, frequency, dysuria.
- Hydronephrosis can occur when tumour obstructs the ureteric orifice.
- Pain in groin, back, perineum, when tumour invades the pelvic wall.
- Common in males—3:1.

Investigations

- Urine microscopy: For RBC's and malignant cells.
- Blood: Hb%, blood urea, serum creatinine.
- IVU: Shows filling defect with distortion and often hydronephrosis.
- *Cystoscopy* and biopsy/resection.
- *Bimanual examination under G/A*—to stage the tumour.
- U/S abdomen to see bladder wall, pelvis, liver, lymph nodes.
- CT scan to evaluate the extension.
- MRI to see invasion and pelvic wall status.



Figs 26.106A to C: CT scan picture showing irregularity in bladder mucosa—carcinoma urinary bladder.



Fig. 26.107: Bimanual palpation is done for bladder tumour under general anaesthesia to evaluate the tumour.



Fig. 26.108: Carcinoma urinary bladder—U/S picture.

Treatment

a. ***Noninvasive tumour***:

- *Endoscopic resection* of tumour.
- *Intravesical chemotherapy* using BCG (Dose: 120 mg in 150 ml of normal saline weekly for six weeks), mitomycin C, epirubicin, adriamycin, thiotepa, methotrexate can be given especially for carcinoma *in situ*.
  - BCG is very useful. Very rarely *BCG provocation* can occur. Fever, joint pain, granulomatous prostatitis, sinus formation, disseminated tuberculosis are the features. Dysuria, frequency and urinary irritation can occur. BCG is *live attenuated vaccine*; its advertent IV entry can be *life threatening* and so if there is haematuria its infusion should be postponed.
  - Mitomycin C causes skin desquamation and rash.
- *Systemic chemotherapy*: Using cisplatin, 5 FU, adriamycin, mitomycin.
- *Helmstein balloon degeneration* for large papillary tumour. Balloon is passed into the bladder and inflated so as to cause pressure necrosis of the summit of the tumour. Later remaining part of the tumour can be resected easily through cystoscopy.

b. ***Invasive bladder tumour*:**

- *Curative interstitial radiotherapy* using implantation of radioactive gold grains (Au 198) (half life is two and half days), or radioactive tantalum wires (Ta 182) (half life is 4 months).
- *Radical deep external beam radiotherapy* (45 Gy) using cobalt 60 is useful, as bladder is retained and so normal act of micturition and potency can be maintained. Complication is that it may eventually lead to formation of thimble bladder.
- ***Surgery***:

Indications for surgery

- ❖ Multiple bladder tumours
- ❖ Sessile tumours
- ❖ Recurrent tumours
- ❖ Poorly differentiated tumours
- ❖ *In situ* carcinomas
- ❖ Squamous cell carcinoma
- ❖ Adenocarcinomas

  - *Partial cystectomy* done when tumour is confined to fundus of the bladder and is single, with a margin of clearance of 2.5 cm. External beam RT and chemotherapy should be given.

  - *Radical cystectomy*: CT scan is a must before doing radical cystectomy to see the pelvis and lymph node status. Here urinary bladder, urethra, paravesical tissues, lymph nodes (pelvic) are removed. In females hysterectomy with removal of part of the vagina is done. After surgery urinary diversion is done either by doing continent ileal conduit, or ureterosigmoidostomy or by creating rectal urinary pouch.
- *Intravesical chemotherapy* by BCG, mitomycin C, adriamycin and interferons.
- *Systemic chemotherapy* by cisplatin, adriamycin, mitomycin, vinblastine—adjuvant therapy. Neoadjuvant cisplatin based chemotherapy is beneficial improving survival by 7%. MVAC regime is methotrexate; vinblastine; adriamycin and cisplatin.

Prognosis

- Depends on type, differentiation, location, stage, invasion, number, lymph node status, pelvis involvement and response to treatment.
- TCC alone—85%; TCC with SCC or adenocarcinoma—6%; SCC/adenocarcinoma alone—3%; spindle cell carcinoma—2%.

URETEROSIGMOIDOSTOMY

- It is a procedure done for urinary diversion after radical cystectomy or as a permanent diversion for many other causes, e.g. bladder dystrophy.
- *Left ureter is implanted to the sigmoid colon, right one to the upper rectum or rectosigmoid junction.*

Complications

- Because the pressure in sigmoid colon is more, it causes *pyelonephritis* and recurrent upper urinary tract infection.
- Because of diarrhoea it causes *hypokalaemia.*
- Because of reabsorption of chloride, *hyperchloraemic acidosis* occurs.

Treatment

- IV sodium bicarbonate (8.4%) with slow IV potassium.
- IV antibiotics.
- Patient is advised to take potassium citrate and sodium bicarbonate and to **avoid salt.**
- In many cases conversion to *ileal conduit* may be required.



Fig. 26.109: Ureterosigmoidostomy.

RUPTURE BLADDER (BLADDER INJURY)

Causes

- ❖ Blow, kick or fall
- ❖ Road traffic accidents
- ❖ Stabs, gunshot injuries
- ❖ Endoscopic trauma
- ❖ Diathermy
- ❖ Instrumentations



Fig. 26.110: Rupture urinary bladder causing extravasation and lower abdominal swelling. It needed surgical intervention, repair of bladder; suprapubic cystostomy.

Types

I. *Intraperitoneal rupture*—20% common.
Occurs in fully distended bladder due to blow, kick, or fall.

II. *Extraperitoneal rupture*—80% common.
Due to road traffic accidents, golf playing, fall over the manhole.
Its features and management are same as rupture of posterior (membranous) urethra.



Figs 26.111A and B: (A) Intraperitoneal rupture. (B) Extraperitoneal rupture.

Conduct has the loudest tongue.

I. Intraperitoneal Rupture

- It is 20% common.
- It occurs in full bladder.

Clinical features

- Sudden pain in suprapubic region.
- Shock and syncope.
- Diffuse abdominal pain.
- Urine leaks into the abdominal cavity causing distension of abdomen.
- Later it causes features of peritonitis, with guarding, rigidity, tenderness and rebound tenderness, dull flank.
- *Patient does not have the desire to micturate.*

Investigations

- Plain X-ray shows ground glass appearance.
- Peritoneal tap is done to confirm urine.
- Cystogram: After passing a small catheter gently per urethra, water soluble iodine dye is passed to visualise the tear in the bladder and entry of the dye into the free peritoneal cavity. This can be done now through C-Arm image intensifier easily.
- U/S abdomen to look for other injuries in the abdomen.
- CT scan abdomen.

Treatment

- *Surgery is the only treatment for intraperitoneal rupture of the bladder*. Emergency laparotomy is done.
- Bladder tear is sutured in two layers using **vicryl**. Peritoneal wash is given.
- Malecot's catheter is placed from above as SPC.
- Prevesical space and peritoneal cavity are drained separately.
- Foley's catheter from below is also passed.
- Adequate specific antibiotics are given to prevent sepsis.

Complications of rupture bladder

- Cystitis and pyelonephritis
- Peritonitis
- Pelvic abscess
- Fistula formation (vesicovaginal or rectovesical)
- Paralytic ileus
- Haemorrhage

Without surgery mortality is 100%

II. Extraperitoneal Rupture of the Bladder

- It is 80% common.
- Occurs in road traffic accidents, in a nondistended bladder.

Clinical features

- There is collection of urine and blood in the extraperitoneal space in front, with fullness, diffuse pain and tenderness in lower abdomen.
- Swelling in the scrotum or labia, and abdominal wall.
- Strangury and inability to pass urine.
- Often blood in the external meatus is noted.
- Features of shock and of other associated injuries may be noted.

Investigations

- Plain X-ray pelvis shows fracture pelvis.
- Cystogram shows leak from the bladder.

During cystoscopy

- Bladder cannot be distended
- Endoscopy light may be shining through the abdominal wall
- Irrigating fluid cannot be retrieved back

Associated urethral injury is looked for

Treatment

- The bladder is exposed extraperitoneally, the tear is identified and sutured. The extraperitoneal space is irrigated with saline. Bladder is closed with a SPC using Malecot's catheter and a drain is placed in prevesical space (cave of Retzius).
- If there is urethral injury it should be treated accordingly.

Note:
- **Bladder injury can also occur** during hystrectomy (both abdominal and vaginal), surgery of colon or rectum, repair of direct inguinal or femoral hernias.

RESIDUAL URINE

- It is the amount of urine retained in the bladder after voiding (at the end of completion of the act of micturition).
- Normal value is 30 ml.
- Amount more than 50 ml is significant. It signifies obstruction in the urethra like BPH.
- Residual urine more than 200 ml in BPH indicates the need for surgical intervention.
- High residual urine is also seen in different types of neurogenic bladder.
- Residual urine precipitates infection because of stasis.

Residual urine is assessed by the following methods:
- The patient is asked to pass urine and then a red rubber catheter is passed to empty the retained urine which is measured to quantify.
- Ultrasound for evaluation of the bladder after voiding urine.
- Intravenous urogram (IVU)—postmicturition film.

MALAKOPLAKIA

- It is usually associated with chronic cystitis of unknown aetiology causing greyish raised patches in the bladder mucosa.
- Microscopically it shows infiltration of submucosa with lymphocytes, plasma cells and large multinucleated malakoplakia giant cells with concretions, called as ***Michaelis Gutmann bodies*** present both inside the giant cell as well as outside.
- It does not turn into malignancy.
- It presents as cystitis.
- Management is urine analysis; culture; antibiotics; urinary antiseptics like pyridium; cystoscopic evaluation and biopsy to rule out other causes.

NEUROGENIC BLADDER

It is the altered bladder function due to defects anywhere in the pathway of micturition reflex.

Causes

- Spinal cord trauma
- Disc prolapse
- Spina bifida
- Spinal cord root lesions
- Tabes dorsalis
- Diabetes mellitus
- Cerebral diseases
- Poliomyelitis

Types

Uninhibited Neurogenic Bladder

- It occurs in CNS diseases due to block in the corticospinal tract.
- There is increased frequency, urgency and incontinence.
- There is early desire to micturate with inability to hold urine.
- Bladder capacity is decreased.
- Awareness of filling and distension, and voiding pressure is normal.
- No residual urine.

Reflex Neurogenic Bladder (Automatic Bladder)

- Lesion here is above the level of micturition centre S_2, S_3 and S_4.
- There is no desire to micturate.
- No awareness of filling or distension.
- Bladder capacity is normal or increased.
- Voiding pressure varies.
- Residual urine present.
- Infection is common.

Autonomous Bladder

- Here micturition centre is destroyed (S_2, S_3, S_4). Both sensory and motor parts are destroyed.
- There is no awareness of filling.
- Bladder is incapable of contraction and so bladder capacity is increased.
- No voiding pressure.
- High residual urine and infection.
- Stress incontinence is present.
- Patient empties the urine by manual pressure.

Sensory Paralytic Bladder

- Here sensation from the bladder to micturition centre is selectively affected.
- It is common in tabes dorsalis and pernicious anaemia.
- There is complete loss of awareness of filling.
- Varying voiding pressure.
- Increased bladder capacity and residual urine.
- Infection is common.

Motor Paralytic Bladder

- It is due to selective destruction of motor pathway from the micturition centre to the bladder.
- It is seen commonly in polio, tumours, trauma.
- There is normal awareness of filling and painful distension.
- Voiding pressure is zero. It is atonic bladder.
- There is residual urine with normal bladder capacity.

Investigations

- Spine X-ray.
- Micturating cystogram.
- Urodynamic studies.
- U/S abdomen to find out residual urine.
- Urine culture and microscopy.

Treatment

- The cause is treated.
- Condom drainage.
- Intermittent catheterisation.
- Drugs like carbachol, distigmine can be given.
- Alpha adrenergic agents.
- Physiotherapy and pelvic exercises.
- Electrical stimulation of perineal muscles.
- Treating the stress incontinence surgically.
- Antibiotics whenever there is infection.

VESICOURETERIC REFLUX

- Normal flow of urine is always from ureter to bladder through ureteric orifice. It is called as efflux.
- If urine enters the ureter from the bladder through ureteric orifice, it is called as reflux. It is always *pathological.*



Fig. 26.112: Micturating cystourethrogram (MCU) showing gross vesicoureteric reflux on both sides.

Aging is "immobility, incontinence, instability and intellectual deterioration.

Causes

- *Congenital:* It is commonly associated with posterior urethral valve.
- *Acquired:* Trauma, after surgery or intervention.
    - Reflux has got **5 grades** depending on the amount of reflux (for grades refer back—MCU).
    - Reflux can be unilateral or bilateral.

Clinical Features

- Features of recurrent urinary tract infection.
- Renal failure in bilateral cases.
- Palpable kidney mass in the loin.

Investigations

- Urine microscopy and C/S.
- Blood urea and serum creatinine.
- IVU.
- Micturating cystourethrogram (MCU).

Treatment

- Tailoring of the ureter with ureteric re-implantation.
- Antibiotics.
- In severe cases nephrectomy, renal transplantation are required.

BLADDER DIVERTICULA

Normal intravesical pressure is 30-50 cm of water. Pressure reaches as high as 150 cm of water in obstruction. This causes hypertrophy of bladder mucosa → saccule formation → diverticulum.

Diverticula can be:

- *Acquired*—common
    - Pulsion diverticulum occurs due to increased intravesical pressure
    - Traction diverticula occurs due to traction into a hernial sac in the groin—often as a sliding hernia
- *Congenital*—due to remnant urachus in midline



Fig. 26.113A



Fig. 26.113B

Figs 26.113A and B: Diverticula bladder. In acquired type only mucosal protrusion is seen in paraureteric orifice region. In congenital type it is full thickness protrusion, commonly over the dome of the bladder.

1. *Congenital diverticula:*
    - It occurs over the dome of the bladder.
    - It is due to unobliterated end of the urachus.
    - As it contains muscle in the wall and it contracts during micturition.
    - Rare type.
2. *Acquired diverticula*:



Fig. 26.114: X-ray showing bladder diverticula. It can be pulsion or traction diverticula. It can be congenital or acquired. Acquired occurs in paraureteric region. Congenital occurs in midline over the dome of the urinary bladder.

- They are more common.
- It occurs as a result of chronic urinary obstruction like BPH.
- It occurs adjacent to ureteric orifice and contains only mucosa (above and outer to ureteric orifice).
- It is prone for stasis, sepsis, stone formation, metaplasia and malignancy.
- Common in males (95%). Common in adults of 50 years.
- Haematuria (30%); fever; pyelonephritis.
- Micturition twice in rapid succession to empty the diverticular urine—is often typical.

Complications of bladder diverticula

- Recurrent infection
- Bladder stone formation
- Obstructive uropathy
- Malignant transformation—less than 5%

Investigation

- Urine C/S, cystoscopy, cystogram, IVU, U/S abdomen.
- CT scan abdomen.

Treatment

- Removal of the diverticula through open surgery.
- Approach is combined intravesical and extravesical. Through cystoscopy, ureteric stent is placed. Suprapubic transverse extraperitoneal open approach is used. Anterior wall of bladder is vertically opened in midline. Diverticulum is packed with gauze. Junction between urinary bladder and, diverticulum is dissected from outside; transected and diverticulum is excised. Bladder surface is closed with vicryl 2 zero single layer sutures. Midline vesicotomy is closed with a Malecot's catheter. Retropubic space is drained. Indwelling urinary catheter is kept *in situ* for 7-10 days.

URINARY DIVERSION

- It is diversion of urine temporarily or permanently, proximal to the site of obstruction.
  - Temporary type is done in benign conditions and distal obstructions, to promote healing.
  - Permanent type is done in advanced malignancies which block the urine flow distally, after radical cystectomy, after radiotherapy with frozen pelvis, etc.



Fig. 26.115: Perineal urethrostomy after total amputation of penis.


Uretero-ureterostomy
Ureter
Skin
Vesicostomy
Urethra
Nephrostomy
Pyelostomy
Ring cutaneous ureterostomy

Fig. 26.116: Types of urinary diversions.


Kidneys
Ureter
Ileum
Stoma
Small bowel
Abdominal wall and skin
Anastomotic site
Caecum

Fig. 26.117: Ileal conduit as urinary diversion.

Temporary Diversions

- Suprapubic cystostomy (SPC).
- Vesicostomy in children in ectopiae vesicae, epispadias, urethral anomalies.
- Ureteric J stent—pigtail stents kept for 3 months.
- Urethrostomies.

A man who does nothing never has time to do any thing.

- Nephrostomies in pyonephrosis and high obstructive uropathies.
- Pyelostomy.

Permanent Diversions

External Diversions

- *Noncontinent ileal conduit*
  Here 20 cm of vascularised distal ileum (30 cm from IC valve) is prepared. Ureters are re-implanted over the ileum. Other end of ileum is brought out as a 3 cm stoma in right iliac fossa. Patient has to wear a bag over it.
- *Continent ileal conduit* is similar conduit with creation of specialised valve (Koch's continent) within, using ileal mucosa or appendix. Patient has to empty the conduit by passing self catheters once in 6 hours.
- Cutaneous ureterostomy/cutaneous ring ureterostomy.

Internal Diversions

- Ureterosigmoidostomy (*Leadbetter-Palitano*).
- Rectal bladder creation.
- Ileocystoplasty.
- Caecocystoplasty/sigmoidocystoplasty.
- Creation of neobladder using ileum/caecum/sigmoid colon which is sutured to urethra.

Types of urinary diversions

- Nephrostomy
- Pyelostomy
- Cutaneous ureterostomy
- Cutaneous ring ureterostomy
- Suprapubic cystostomy
- Vesicostomy in children
- Urethrostomy
- Ureterosigmoidostomy
- Rectal bladder
- Urinary ileal conduit (Koch's conduit)

Complications of Diversions

- Urine leak, faecal leak, intestinal obstruction, sepsis.
- Hyperchloraemic hypokalaemic metabolic acidosis.
- Pyelonephritis.
- Osteomalacia, growth retardation.
- Calculi formation—4%.
- Continent failure, blockage of diversion stoma (stenosis).
- Reflux of urine.
- Vitamin B_{12} and folate deficiency due to absence of ileum.
- Complications of stoma.
- Renal failure.
- Metaplasia and adenocarcinoma especially at uretero sigmoidostomy junction.

URINARY FISTULAS

It is the leak of urine at abnormal sites.

Causes

Congenital

- Patent urachus.
- Ectopiae vesicae.
- In association with anorectal malformation—rectovesical fistula.

Acquired

- Trauma to perineum.
- Pelvic surgery.
- *Vesicovaginal fistula*—due to obstructed labour; after hysterectomy, bladder may get injured while pushing it down; anterior colporrhaphy in elderly after vaginal hysterectomy; radiation induced; infiltrating carcinoma cervix. Usually it takes one week to cause necrosis and present as fistula. Features are—passage of urine per vagina, dribbling of urine in vagina on per speculum examination, *swab test is positive* (Methylene blue is injected through urethra after placing a swab in the vagina. Swab turns blue if there is fistula). Treatment is difficult. Surgical exploration—transvaginal repair in low fistula. Suprapubic repair if fistula is high. Often urinary diversion is needed.
- Specific causes like tuberculosis.
- Staghorn calculi can cause fistula after nephrostomy.
- Fistula can develop after surgery of renal pelvis, ureter, bladder. It will persist if there is distal obstruction like stricture urethra, otherwise it will subside spontaneously.
- Renal pelvis involved by Crohn's disease.

Investigations

- Discharge study for creatinine level.
- Urine C/S; leaking fluid for C/S.
- U/S abdomen; CT scan.
- MR fistulogram.

Treatment

- Correction of cause.
- Urinary diversion in initial period.
- Excision of fistula track and repair.
- Fistula can recur based on cause, nutrition, local blood supply, specific causes.

C. Prostate

CHAPTER OUTLINE

- Anatomy
- Acid Phosphatase
- Prostate Specific Antigen
- Benign Prostatic Hyperplasia
- Prostatitis
- Bladder Outlet Obstruction
- Carcinoma Prostate

ANATOMY

It is an accessory gland of male reproductive system. It is composed of glandular tissue embedded in fibromuscular stroma. It surrounds the first 3 cm of the urethra.

Lobes

- It is composed of 5 lobes—anterior, posterior, 2 lateral, 1 middle/median lobe.
- Primary carcinoma is said to begin in posterior lobe. Middle lobe produces an elevation in the lower part of the trigone of bladder *(uvula vesicae)*. Adenoma is more common here due to more amount of glandular tissue.

Capsules

1. *True capsule*: Formed by the condensation of the peripheral part of the gland; continues with the stroma of the gland.
2. *False capsule*: Derived from the pelvic fascia. On each side prostatic venous plexus are embedded in it.

McNeal Divided Prostate into Three Zones

- *Peripheral zone*—prone for carcinoma.
- *Periurethral transition zone* where BPH arises.
- *Central zone*.

Note:

- Prostate carcinoma develops in prostatic gland proper.
- BPH develops in submucosal glands.

ACID PHOSPHATASE

- It is the enzyme that splits organic phosphates.
- It is found in many human tissues, but more concentrated in prostate.
- It is active at pH 5.
- Acid phosphatase secreted by prostate drains into the urethra through prostatic ducts and so blood levels of this enzyme remain low.
- Serum acid phosphatase estimation should be done ***on empty stomach*** because heavy meals alter the level of the acid phosphatase.
- Normal value is *0-5 King Armstrong units per 100 ml of serum*.



Figs 26.118A to D: Parts of prostste.

- It is raised significantly in carcinoma prostate with metastases.
- *It does not increase in BPH.*
- Slight increase in acid phosphatase level occurs in acute prostatitis, Paget's disease of bone and hepatic cirrhosis.
- Prostatic fraction of acid phosphatase is more relevant in carcinoma prostate.

PROSTATE SPECIFIC ANTIGEN (PSA)

- It is a protease, produced from the prostatic epithelium secreted in the semen to cleave and liquefy the seminal coagulum formed after ejaculation.
- PSA is organ specific. *Normal value is 4 ng/ml of plasma. More than 10 ng/ml is significant*.
- PSA elevation occurs not only in carcinoma but also in prostatic hyperplasia and prostatitis.
- But the increase is much more in carcinoma than in benign conditions.
- PSA is in two forms: *Major,* bound form and *minor,* free form.
- Major, bound form increases in carcinoma. Minor, free form is increased in benign conditions.
- PSA density, i.e. PSA level per gram of prostate tissue is more relevant.
- Serial estimation of PSA is very useful to suspect spread and recurrence after treatment.

The formula to be complete happy is to be very busy.

- 25% of men with PSA 4-10 ng/ml show prostate carcinoma.
- 20% of men with normal PSA (1-4 ng/ml) will show prostate carcinoma.
- PSA more than 10 ng/ml is suggestive of carcinoma prostate.
- PSA more than 35 ng/ml is almost diagnostic of advanced carcinoma of prostate.
- Decrease in PSA after therapy suggests adequate ablation.
- Men aged > 50 years with PSA $\geq$ 3 ng/ml should undergo prostatic biopsy.

Prostatic calculi:
It is the calcification of corpora amylaceae which contains calcium phosphate, protein and fat.

BENIGN PROSTATIC HYPERPLASIA (BPH)

> *He was very often, both in the Day and the Night, forced to make Water, seldom in any Quantity, because he could not retain it long enough.*
>
> —**Edward Hyde (first Earl of Clarendon),** 1759

It is benign enlargement of prostate which occurs after 50 years, usually between 60 and 70 years.

Aetiology

Theories

- It is involuntary hyperplasia due to disturbance of the ratio and quantity of circulating androgens and estrogens.
- BPH is a benign neoplasm, also called as ***fibromyoadenoma.***
- Hypothalamus → pulsatile release of LHRH → release of luteinising hormone (LH) from anterior pituitary → stimulates Leydig cells of testes → releases testosterone (TS) → reaches prostate → releases 5α reductase type II of prostate → converts TS to DHT (dihydrotestosterone) for its effects. DHT is five times more potent than TS. 90% TS is from testes. Remaining 10% TS is from adrenal cortex.
- With age TS level drops slowly. But fall of oestrogen level is not equal. So prostate enlarges through intermediate peptide growth factor.
- BPH arises from submucosal glands of periurethral transitional zone with stromal proliferation and adenosis. It eventually compresses the peripheral zone and enlarges as lateral lobe.
- BPH arising from subcervical glands of central zone enlarges as middle lobe projecting up into the bladder.

Pathology

- BPH usually involves median and lateral lobes or one of them.
- It involves adenomatous zone of prostate, i.e. submucosal glands.
- Median lobe enlarges into the bladder.
- Lateral lobes narrow the urethra causing obstruction.
- *Urethra above* the verumontanum gets elongated and narrowed.
- *Bladder* initially takes the pressure burden causing *trabeculations, sacculations* and later *diverticula* formation.
- Enlarged prostate compresses the prostatic venous plexus causing congestion, called as *vesical piles leading to haematuria.*



Fig. 26.119: Prostate anatomy.

- Incrimination of BPH as the source of haematuria before excluding other causes is termed as ***"Decoy prostate"***.
- *Kidney and ureter*: Backpressure causes *hydroureter and hydronephrosis*.
- Secondary ascending infection can cause *acute* or *chronic pyelonephritis*.
- Often severe obstruction can lead to obstructive uropathy with *renal failure.*
- BPH causes *impotence.*

Clinical Features

- Frequency occurs due to introversion of sensitive urethral mucosa into the bladder or due to cystitis and urethritis.



Fig. 26.120: Retention of urine in bladder due to BPH.

- Urgency, hesitancy, nocturia.
- Overflow and terminal dribbling.
- Difficulty in micturition with weak stream and dribble.
- Pain in suprapubic region and in loin due to cystitis and hydronephrosis respectively.
- Acute retention of urine.
- Retention with overflow. High pressure chronic retention with functional obstruction.
- Impaired bladder emptying with its problems like cystitis, urethritis, stone formation and residual urine.
- Haematuria.
- Renal failure.
- *Prostatism* is a combination of symptoms like frequency both at day and night, poor stream, delay in starting and difficulty in micturition.

- Tenderness in suprapubic region, with palpable enlarged bladder due to chronic retention. Hydronephrotic kidney may be palpable.
- **Per rectal examination shows enlarged prostate. It should be done when bladder is empty.**
- Features of urinary infection like fever, chills, burning micturition.
- International prostate symptom score is available now.

Lower urinary tract symptoms (LUTS)

Symptoms of voiding	*Symptoms of storage*
• Hesitancy • Poor flow not improving by straining • Dribbling even after micturition • Intermittent stream—stops and starts • Poor bladder emptying • Episodes of near retention	• Frequency • Nocturia • Urgency • Urge incontinence • Nocturnal incontinence

Differential Diagnosis

- Stricture urethra.
- Bladder tumour, carcinoma prostate.
- Neurological causes of retention of urine like diabetes, tabes, disseminated sclerosis, Parkinson's disease.
- Idiopathic detrusor activity.
- Bladder neck stenosis; bladder neck hypertrophy.

Investigations



Fig. 26.121: IVU showing bladder with enlarged median lobe of prostate.

- Urine for microscopy and C/S.
- Blood urea and serum creatinine.
- U/S abdomen—look for presence of residual urine.
- Urodynamics.
    - Urine flow rate > 15 ml/sec is normal. 10-15 ml is equivocal; < 10 ml is low.
    - Voiding pressure < 60 cm of water is normal; 60-80 is equivocal; > 80 is high.
- Cystoscopy.
- Transrectal US (TRUS) is useful to find out nodules/possibility of carcinoma prostate. It is not done routinely.
- Acid phosphatase.
- Prostate specific antigen (PSA).
- IVU—to see kidney function.
- Serum electrolytes.

Note:
Normal peak urine flow rate is 20 ml/sec. In obstruction it is less than 10 ml/sec.

Management

- Patient with ***acute retention*** of urine requires *urethral catheterisation.*
- If urethral catheterisation fails, then *suprapubic cystostomy (SPC)* is done.
- If patient presents with ***uraemia***, then urethral catheterisation is a must. That allows the kidney to function adequately and further obstructive damage is prevented.
- Serum electrolytes should be corrected properly in these patients.

Indications for Surgery

- Prostatism (frequency, dysuria, urgency).
- Acute retention of urine.
- Chronic retention of urine with residual urine more than 200 ml.
- Complications like hydroureter, hydronephrosis, stone formation, recurrent infection, bladder changes.
- Haematuria.

Surgeries

1. *Transurethral resection of prostate (TURP)*:



Fig. 26.122A

In cases of complete intrapelvic rupture of the urethra, the tip of the catheter can be felt per rectum protruding from the urethral tear as a longitudinal cord lying beneath the anal canal. **—Wallace**



Fig. 26.122B

Figs 26.122A and B: Endotherapy for BPH—TURP is the most common procedure; laser (holmium), stenting—are different procedures. TURP set is shown on the table with evacuator to remove fragmented prostate tissue.

- Using cystoscope with fluid like glycine irrigating continuously, enlarged prostate is identified and resected using a loop with a hand control. Resection is done using high frequency diathermy current, above the level of verumontanum.
- After surgery, continuous bladder irrigation using normal saline is done using three way Foley's catheter. Antibiotics should be given. Catheter is removed within 72 hours.

Postoperative complications are:

- Water intoxication with congestive cardiac failure—TURP syndrome
- Hyponatraemia
- Haemorrhage
- Infection
- Incontinence
- Perforation of the bladder or prostatic capsule
- Stricture urethra
- Retrograde ejaculation and impotence
- Recurrence

TURP

- No suprapubic incision
- Most common and popular method
- Done using resectoscope
- Recurrence may occur in large prostate
- TURP syndrome can develop
- Continuous postoperative irrigation using glycine solution is needed for 72 hours
- Faster recovery and early discharge is possible

2. *Freyer's suprapubic transvesical prostatectomy*. Before TURP, it was a popular and was the procedure of choice for enlarged prostate.

   Complications are haemorrhage, infection, stricture urethra, incontinence, impotence, bladder neck contracture.
3. *Millin's retropubic prostatectomy*. It is done without opening the bladder. (It is not commonly practiced).
4. *Young's perineal prostatectomy* through perineal approach.
5. Microwave hyperthermia treatment with temperature of 45–50 degree.
6. Laser treatment is becoming popular, using holmium laser.
7. High energy electromagnetic treatment.
8. Placement of intraurethral stents at prostatic urethra.
9. Placement of extraurethral stents which are inert.
10. Transurethral balloon dilatation of the prostate.
11. If patient presents with acute retention of urine, initial urethral catheterization is done. If not possible then *suprapubic trocal cystostomy* ideally or formal open SPC is done. Once patient's obstructive uropathy is under control, TURP is done after 7-14 days after evaluation.

Specific Problems after Surgical Intervention of Prostate

- Retrograde ejaculation—65%.
- Erectile dysfunction—5%.
- Failure, recurrence of symptoms and enlargement—10%.
- Need for re TURP/surgery in 10 years—15%.
- Severe sepsis—6%.
- Recurrent late urinary infection—20%.
- Postoperative haematuria—3% needs transfusion.
- Mortality in TURP is 0.5%.

Other methods used for BPH

- Transurethral incision of prostate—TUIP
- Laser ablation
- Transurethral microwave therapy—TUMT
- Transurethral needle ablation using high frequency radiowaves—TUNA
- High intensity US energy
- Water induced thermotherapy—through a balloon placed in prostatic urethra
- Prosthetic stents
- Balloon dilatation

Drugs Used for BPH

- *Alpha 1 adrenergic blocking agents*—which inhibit smooth muscle contraction of prostate. They reduce the bladder neck resistance so as to improve the urine flow.
  - Short acting drugs are *prazosin* and *indoramin.*
  - Long acting drugs are *terazocin* and *doxazosin*.
  - Selective alpha$_{1A}$—adrenoceptor blocking agent: *Tamsulosin* 0.2 to 0.4 mg OD for 12 weeks.
- *5-alpha reductase inhibitor* inhibits conversion of testosterone to dihydrotestosterone.
  - It is effective in palpably enlarged prostate.
  - Drug used is *finasteride* 5 mg daily. Duration of treatment is about 6-8 months.
  - It is contraindicated in obstructive uropathy or carcinoma prostate.

PROSTATITIS

Types

Acute or chronic.

Acute Prostatitis

Causes:

- Due to instrumentation.
- Ascending infection from below.
- Haematogenous.
- Descending infection from above.

Bacteria involved:

- *E. coli, Klebsiella, Proteus.*
- *Staphylococcus.*
- *Streptococcus faecalis.*
- *Gonococcus.*

Clinical features:

- Pain, frequency, fever with chills and rigors.
- Retention of urine.
- **Perineal heaviness, pain on defaecation.**
- Tender prostate on per rectal examination.
- Initial fraction of urine is turbid which is sent for culture and sensitivity.

Investigations:

- Urine C/S.
- U/S abdomen.

Treatment:

- Prolonged rigorous antibiotics—for 2 months.
- Avoidance of alcohol and sexual intercourse for 6 weeks.

Complications

- Formation of single or multiple abscess. It is common in diabetics
- Chronic prostatitis
- Retention of urine

Prostatic abscess has to be drained—through perineal approach under U/S guidance

Chronic Prostatitis

Caused by *E. coli*, *Staphylococcus, Streptococcus, Trichomonas, Chlamydia.*

- There is always associated posterior urethritis.
- Epididymitis.
- Pain in the perineum, rectum, low back pain, leg pain.
- Fever.
- Sexual dysfunction.
- Per rectal examination shows tender prostate.
- Prostatic fluid obtained by prostatic massage shows 15 or more pus cells/HPF.
- In three glass urine test—first glass contains prostatic threads.

Treatment: Antibiotics—Co-trimethoxazole, trimethoprim, doxycycline.

Prostatic Abscess

- It is infection, suppuration and pus formation in the prostate gland.
- Presentation is fever, rigors, perineal pain, urinary disturbances, and tender soft fluctuant swelling in the prostate on rectal examination.
- Often presentation may be retention of urine.
- Total count will be increased.
- Urine will show pus cells.
- US is diagnostic. US is often done over perineum also.
- Treatment is antibiotics; US guided aspiration transperineally in lithotomy position or transperineal incision and drainage.
- Suprapubic cystostomy is better in case of retention of urine.
- After drainage antibiotics are needed for longer period of 6 weeks to prevent recurrent infection.

BLADDER OUTLET OBSTRUCTION (BOO)

- It is low urinary flow rate with the presence of high voiding pressure. It is an urodynamically confirmed entity.
- It is diagnosed by urodynamic pressure flow study.
- Flow rate will be les than 10 ml/second with voiding pressure more than 80 cm of water.
- Eventually detrusor inefficiency occurs causing significant residual urine.
- *Causes of BOO*—BPH; bladder neck hypertrophy or stenosis; carcinoma of prostate; urethral stricture; functional bladder neck obstruction.
- *Effects of BOO*—acute retention of urine; chronic retention of urine; impaired bladder emptying; uraemia; infection; stone formation, haematuria.
- US; renal function tests; IVU; PSA are the investigations.
- *Management* is by treating the cause by cystoscopic bladder neck incision, urethrotomy; TURP, etc.

Evaluation of patient with lower urinary tract infection (LUTI)

- Urine analysis and culture
- Hemoglobin, total count, ESR, blood urea and serum creatinine
- Digital examination of rectum (P/R)
- CNS examination
- PSA, acid phosphatase
- Uroflowmetry, flow rate assessment, residual urine analysis
- US abdomen, IVU to see upper urinary tract, CT abdomen in selected patients only
- Cystoscopy, transrectal US (TRUS)
- Prostatic abscess aspiration/drainage through perineal approach under guidance

Do all the good you can, by all the means you can, in all the ways you can, in all the places you can, at all the times you can, to all the people you can, as long as ever you can—

CARCINOMA PROSTATE

> *During the last six months, (I.B.) had suffered …excruciating pain in the region of the kidneys and bladder, attended with almost constant desire to void urine, which was effected with the greatest difficulty.…An examination per rectum proved that there existed an enlarged…prostate gland, and slight pressure occasioned great pain.…The bladder was found (at autopsy) to contain a tumour as big as a large orange…discovered to derive its origin from the prostate gland.… The fungus …plugged up both ureters.… In the liver there were several tumours (and) several…in the lungs.*
>
> —**George Langstaff,** 1817

- It is the *most common malignant tumour* in men over 65 years.
- Carcinoma prostate occurs in peripheral zone in prostatic gland proper, i.e. *commonly in posterior lobe*. So prostatectomy for BPH does not confer protection against development of carcinoma prostate.
- Incidence of prostate cancer in men over 80 years is 70%.

Types of carcinoma prostate

- Microscopically latent
- Tumours incidentally found either by TURP or by PSA estimation
- Early localised carcinoma
- Advanced local prostatic carcinoma
- Metastatic carcinoma either into the bone commonly or other organs

Histology: It is an *adenocarcinoma,* wherein there is loss of myoepithelial cell layer which normally surrounds the prostatic glands (Gleason). Glands here appear in confluence. *Grading of carcinoma* is based on dedifferentiation as proposed by Gleason.

Staging of carcinoma prostate

Occult—Diagnosed after investigation due to suspicion
Stage I—Tumour confined to prostate/local nodule
Stage II—Tumour involving capsule or diffuse type
Stage III—Tumour involving seminal vesicle
Stage IV—Extension into adjacent tissue



Figs 26.123A to E: Staging of Ca prostate (A) Occult, (B) Stage I, (C) Stage II, (D) Stage III, (E) Stage IV.

TNM staging of carcinoma prostate

T1 – Incidentally confirmed carcinoma after prostatectomy
- T1a – Tumour occupying less than 5% of specimen
- T1b – Tumour occupying more than 5% of specimen
- T1c – Tumour impalpable but suspected by high PSA

T2 – Tumour nodule palpable on rectal examination
- T2a – Single nodule palpable on digital examination within prostate capsule
- T2b – Nodule involving both lobes

T3 – Tumour extends through the capsule
- T3a – Extension through capsule one or both
- T3b – Extension to seminal vesicles
- T4 – Tumour which is fixed or spread to adjacent structures like pelvic wall and rectum other than seminal vesicles

Note:
For T1a progress rate is slow—15-20% in 8 years
For T1b and T2 it is 35%
For T3/T4 M0 it is 50% in 5 years with bone spread
For M1 average survival is 3 years

Note:
Gleason score *more than 7* carries poor prognosis.

Spread

Local spread:
- Upward into seminal vesicles, bladder neck, trigone, later into both ureters causing anuria. Downward into distal sphincter.

Blood spread:
- Into the bones commonly—pelvic bones, lumbar vertebrae, femoral head, ribs, skull—in that order.
  - Pathological fractures can occur in long bones and vertebrae.
  - Paraplegia may occur if spine is involved.
  - Rarely spread to liver and lung can occur.

Lymphatic spread:
  - Into the obturator lymph nodes, then to internal iliac lymph nodes.
  - Through seminal vesicles, into external iliac and retroperitoneal lymph nodes.
  - Eventually mediastinal, left supraclavicular lymph nodes get involved.



Fig. 26.124: A plain X-ray AP view of lumbar spine in a patient with carcinoma prostate. Note the typical osteosclerotic secondaries.

Clinical features

- Commonly asymptomatic
- Bladder outlet obstruction and so retention of urine
- Haematuria, frequency

- Pelvic pain, back pain, arthritic pain in sacroiliac joint—features of secondaries
- On per rectal examination, prostate feels hard, nodular, irregular often with loss of median groove
- Incidental carcinoma after TURP or after PSA analysis
- Features of renal failure
- Anaemia secondary to extensive bone marrow invasion and also due to renal failure

Differential Diagnosis

- Are other causes of retention of urine and other causes of back pain.

Investigations

- Hb%, peripheral smear. In metastatic disease, there may be leukoerythroblastic reaction with bone marrow invasion causing anaemia, thrombocytopenia, DIC and increased fibrinogen degradation products (FDP). Anaemia may also be due to renal failure
- Prostate specific antigen (PSA): More than 10 nmol/ml is suggestive.
- Prostatic fraction of acid phosphatase is increased.
- Blood urea, serum creatinine, liver function tests.
- Transrectal ultrasound (TRUS) is very useful.
- Transrectal prostatic biopsy. 10 biopsy cores are taken.
- Plain X-ray, KUB, may show *dense coarse sclerotic* secondaries. Osteolytic or combination of lytic and sclerotic lesions are also often seen.
- Technetium radioisotope bone scan to see secondaries.



Fig. 26.125: Carcinoma prostate showing skeletal secondaries in bone scan.

- U/S, abdomen, to see the tumour extension into the bladder and to see kidneys for hydronephrosis.
- MRI/CT scan is better for staging the disease. MRI is ideal. It can be combined with TRUS to have an accurate staging.

Note:
Osteoblastic secondaries occasionally can be seen in carcinoma breast.



Figs 26.126A and B: Osteoblastic secondaries in pelvic bones and lumbar spine.

Treatment

> *In prostatic cancer with marked elevation of acid phosphatase, castration or injection of large amounts of estrogen caused a sharp reduction of this enzyme to or towards the normal range.… In 3 patients with prostatic cancer, androgen injections caused a sharp rise of serum acid phosphatase.*
> —**Charles Brenton Huggins, Clarence Vernard Hodges,** 1941

- *Radical prostatectomy* is done in early growth with removal of prostate, seminal vesicle, distal sphincter along with reconstruction of the urethra.

Look at happiness and misery the same; Look at success and failure the same. —True way of life it is called as.

- *Radical radiotherapy* for early carcinoma prostate can be given using both interstitial and external radiation.
- *Pelvic lymph node dissection with* I^{125} *radiation seeds implantation.*
- *Bilateral subcapsular orchidectomy* is done to reduce the testosterone level. Very useful method. First started by ***Charles Huggins***—Urologist *(Nobel Prize winner)*. (Other condition where orchidectomy is done is carcinoma of male breast.)
- ***TURP*** + ***Bilateral orchidectomy*** + ***External radiotherapy for bone secondaries*** + ***Flutamide*** or ***Honvan***—commonly advocated method.
- External radiotherapy for spine and pelvis.
- Strontium isotope radiotherapy.
- *Drugs:*
  - Phosphorylated diethylstilbestrol ***(Honvan)***—initially given intravenously and later orally. It is very effective. Complications are cardiac congestion, DVT, gynaecomastia.
  - LHRH agonists (Medical castration)—Leuprolide, Goserelin.
  - Androgen receptor blocking agents *like flutamide*, bicalutamide.
  - Cyproterone acetate (also has got progestogenic effect).
- In elderly people with early carcinoma prostate *inactivity with wait and watch policy* is practised.
- Sometimes permanent suprapubic cystostomy (SPC) is required in these patients.

Phosphorylated diethylstilbestrol

- Initially IV 100 mg/daily later orally 100 mg/daily
- Can cause cardiac congestion, DVT, gynaecomastia
- Prior RT to breasts to prevent gynaecomastia often advocated
- Response starts appearing in 48 hours

Prognosis is good

Remember

- Wait and watch policy is ideal in elderly patient with early carcinoma (P/R; PSA) above 70 years
- TURP if there is obstruction with bilateral subcapsular orchidectomy; LHRH agonists; androgen blockage
- Radical prostatectomy/radical RT in young T1a or T1b—early disease. The criteria for radical prostatectomy—life-expectancy should be more than 10 years; PSA < 20 mmol/ml; bone scan should be negative
- Brachytherapy using guided RI seeds of I^{125} and palladium
- Orchidectomy; LHRH agonists (Leuprolide); androgen receptor blockade (flutamide, bicalutamide); TURP if needed—commonly done procedure
- External RT/IV radiopharmaceutical Strontium 89 (bone seeking isotope) for bone secondaries—used

D. Urethra

CHAPTER OUTLINE

- Anatomy
- Urethral Injury
- Stricture Urethra
- Hypospadias
- Epispadias
- Posterior Urethral Valve
- Urethral Calculi
- Urethritis
- Extravasation of Urine
- Retention of Urine

ANATOMY

Posterior urethra:
- Prostatic urethra.
- Membranous urethra.

Anterior urethra:
- Bulbar urethra.
- Penile urethra.



Fig. 26.127: Anatomy of urethra.

URETHRAL INJURY

Classification

I. *Depending on site of rupture:*
   1. Rupture of the membranous urethra.
   2. Rupture of the bulbous urethra.



Fig. 26.128: Common sites of urethral injuries.

II. *Depending on circumference of the urethral wall involved:*
   1. Complete.
   2. Incomplete.

III. *Depending on the thickness of the urethra involved:*
   1. Total.
   2. Partial.

RUPTURE OF MEMBRANOUS URETHRA AND/OR PROSTATIC URETHRA (POSTERIOR URETHRA)

Causes

- It is usually associated with pelvic fracture, commonly due to road traffic accidents
- Injury can also occur during instrumentation
- Calculus passage and catheterisation
- In prolonged labour, due to long-standing pressure on the urethra by foetal head

- Prostate is attached to pubis by puboprostatic ligament and disruption of puboprostatic ligament with complete rupture of urethra can lead to *floating prostate—Vermooten's sign.*
- Injury can lead to incomplete rupture of urethra or may be associated with extraperitoneal rupture of bladder.

Based on ascending urethrogram, posterior urethral injury is classified as (McCallum-Colapinto classification).

Type I: Elongation of posterior urethra, but intact

Type II: Prostate "plucked off" membranous urethra with extravasation of urine above sphincter only—*Floating prostate—Vermooten's sign*

Type III: Total disruption of urethra with extravasation of urine both above and below the sphincter

Clinical Features

- Blood in external meatus. Failure or difficulty in passing urine.
- Extravasation of urine to scrotum, perineum and abdominal wall.
- *Shock* with pallor, tachycardia, hypotension.

Silence is not only the absence of sound but also stillness of the mind.

- Features of associated injuries like head injury, thorax and or abdominal organs which take priority in initial phases of management.
- On P/R examination, prostate may be felt high or may not be palpable at all. Signifies *floating* prostate.

Investigations

- X-ray pelvis to see for fracture.
- U/S abdomen to see pelvis and other injuries.
- *Urethrogram* is done to see the site and type of tear (often reserved to do at later stage).

Treatment

The shock and associated injuries are treated.

- In *floating prostate:*
    - *As rupture is complete*, bladder is opened from above. A metal bougie is passed from above through the bladder and one more metal bougie is passed from below through urethra and both are manipulated so as to meet each other.
    - Lower bougie is negotiated along the upper one and so into the bladder. Red rubber catheter is tied to the tip of the lower (urethral) bougie which has already entered into the bladder. When lower bougie is pulled out per urethrally, catheter tied to it will pass through urethra from above, to which Foley's catheter is tied and pulled up, so as to keep it in position.
    - Bladder is closed with a SPC using Malecot's catheter—*Railroad technique*.

In ***incomplete rupture:*** *Two approaches:*

- *First approach proposed by Mitchell*:
    - *Do not pass catheter from below* as it may further damage the urethra and also may damage sphincter mechanism and so may cause incontinence later. Here SPC is done using Malecot's catheter.
    - After three to six weeks, an urethrogram is done. Using endoscope or along with open method Foley's catheter is passed, often after dilatation.
- *Second approach advocated by Blandy*:
    - *Single attempt to pass a small soft catheter per urethrally* gently may lead into the bladder, which will be kept *in situ*, to maintain the continuity.
    - If this fails SPC is done. On second day, in operation theatre (OT), bladder is opened from above and flexible cystoscope is passed from below and using this, catheter is passed from below.
    - Bladder is closed with a SPC.
- If patient with incomplete rupture presents later, then it is managed once a stricture forms, accordingly as stricture urethra, after 3 months. Until then patient may require SPC.
- Other measures: Antibiotics, blood, fluid replacement, treatment of other injuries.

Complications

- Urinary incontinence
- Impotence
- Stricture urethra
- Infection



Fig. 26.129: Penetrating injury in the perineum causing rectal and urethral injury which is communicating. Note the catheter passed per urethra has gone into the rectum and come out through the anal canal. It needed colostomy and suprapubic cystostomy diversions. (*Courtesy:* Dr Ashfaque Mohammad, DNB, KMC, Mangalore)

RUPTURE OF BULBOUS URETHRA (Anterior Urethra)

- Usually, due to a fall astride a projecting object, like in sailing ships, cycling, over loose manhole cover, gymnasium.

Clinical features: *Triad*

- Blood in external meatus (Urethral haemorrhage)
- Perineal haematoma
- Retention of urine

- Rupture may be *complete* or *incomplete*.
- *Total* or *partial*.

Investigations

X-ray pelvis, and U/S abdomen. Condition is diagnosed clinically.

Treatment

- *Patient should be told not to try to pass urine*, if passed, then extravasation of urine occurs.
- In operation theatre, *one attempt of urethral catheterisation is tried gently*. If able to pass a catheter, then it is left in place.
- Often perineal haematoma which occurs, has to be drained.
- Antibiotics should be given to prevent sepsis.
- *If catheter fails to pass*, then under general anaesthesia, in lithotomy position, SPC is done. Bulbous urethra is exposed through perineal midline incision and tear is sutured with an indwelling Foley's catheter. Drain is then placed into the perineum.

- If suturing is not possible (sometimes), then *perineal urethrostomy* is done and at later stages continuity is maintained (usually after 3 months).

Complications

- Infection
- Extravasation of urine
- Stricture urethra

STRICTURE URETHRA

Classification I: *Aetiologically*.

1. Congenital.
2. Inflammatory:
   a. Post-gonococcal is most common (70%).
      - Gonococcal stricture occurs one year after infection.
      - Retention develops only 10-15 years later.
      - Common in the bulb of urethra especially in the roof.
      - Here multiple strictures are common, proximal stricture is the narrowest.

   b. Tuberculous.
   c. Other infection (urethritis).
3. Traumatic: Bulbous, membranous.
4. Postinstrumentation: Catheter, dilator, cystoscope.
5. Postoperative: Prostate surgery (4%), urethrostomy.

Classification II:

1. Proximal: Common in *bulbous urethra* (70%).
2. Distal: Congenital (in the external meatus). Often traumatic in children.

Classification III:

1. Permeable: Permits urine to pass.
2. Impermeable.

Classification IV:

1. Passable: Allows catheter to pass.
2. Impassable.

Classification V: It can be single or multiple.

Classification VI: According to the part involved. In the roof (most common) or in the floor.

Clinical features

- Poor urinary stream
- Forking and spraying of the stream
- Incomplete emptying
- Frequency, dysuria
- Retention and often with overflow
- Pain, burning micturition, suprapubic tenderness
- Thickening and button-like feeling in bulbar urethra (Bulbous urethra is felt clinically by lifting the scrotum in midline in the perineum)

Investigations

- Urine microscopy and culture.
- Blood urea and serum creatinine.
- IVU to see hydronephrosis and function of kidney.
- U/S abdomen.
- X-ray of pelvis to see old fracture with history of trauma.
- *Ascending urethrogram* is an essential investigation to see the site, type, extent and false passage.



Fig. 26.130: Ascending urethrogram showing failure of dye to pass due to stricture urethra.



Fig. 26.131: Ascending urethrogram showing stricture urethra.



Fig. 26.132: Cystoscopic view of urethral stricture.



Fig. 26.133: Ascending urethrogram showing multiple urethral stricture.

- The dye is injected through suprapubic needle puncture into the bladder and visualisation is done using C-Arm image intensifier.
- Urodynamic studies.
- Urethroscopy.

Treatment

1. **Intermittent dilatation**:
   Gradual dilatation, initially with thin dilators, later with thicker dilators of increasing size. Dilatation should be done in OT under aseptic precaution.

   *Should avoid forcible dilatation or over dilatation***.**

   Dilatation is done "***Once a week for one month, once a month for one year, and later once a year (on his birthday)"***.

   Dilators used:
   a. Lister's dilator [has got olive tip (blister)].
   b. Clutton's dilator.
   c. Filiform bougies.



Fig. 26.134: Filiform bougies are used to dilate narrow stricture urethra. One of the bougies will be passed into the urethra.

Complications of dilatation

- Infection and bleeding due to trauma
- False passage
- Fistula formation

2. **Visual internal cystoscopic urethrotomy or stricturotomy**:
   - Here using cystoscope, stricture is visualised and is cut at 12 o'clock position, until it bleeds (fibrous tissue is cut completely).
   - After that Foley's catheter is passed and kept in position for 48 hours.
3. **External urethrotomy** by open method. Presently not commonly done as cystoscopic urethrotomy is more popular. It is presently done as an initial stage surgery for urethroplasty *(Wheelhouse's operation*).
4. **Urethroplasty:** Stricture is excised and urethra is reconstructed using *prepuceal skin* or scrotal skin *(Johanson's urethroplasty)*.

Problems in urethroplasty

- Staged procedure and so prolonged hospitalisation
- Infection
- Necrosis of skin flap
- Leak and fistula formation
- Restenosis

Complications of stricture urethra

- Retention of urine
- Urethral fistula
- Infection—urethritis, cystitis, pyelonephritis
- Urethral diverticula
- Periurethral abscess
- Bilateral hydronephrosis
- Stone formation
- Renal failure
- Due to straining—hernia, haemorrhoids, rectal prolapse

HYPOSPADIAS



Fig. 26.135: Hypospadias.

It is the most common congenital malformation of urethra wherein external meatus is situated *proximal* than normal, over the *ventral* (under) aspect of the penis.



Figs 26.136A and B: Hypospadias in coronal region of glans penis with typical chordee.



Fig. 26.137: Penoscrotal hypospadias.

Classification

- Glandular: Meatal opening in glans. It is the most common type.
- Coronal.
- Penile.
- Penoscrotal.
- Perineal with split scrotum. This is associated with bilateral undescended testes.



Fig. 26.138: Types of hypospadias.

Features

- Absence of urethra and corpus spongiosum distal to abnormal urethral orifice.
- Bowing or bending of penis distal to abnormal urethral opening *(chordee),* with poorly developed prepuce over inferior aspect.
- Urine soakage over the scrotum with dermatitis and infection.
- Associated congenital anomalies are known to exist.

Treatment: Staged Procedure

I. At the age of one and half years, surgical correction of the chordee is done.

II. At the age of 5-7 years, reconstruction of urethra is done using *prepucial skin* (ideal) or scrotal skin if the patient has been circumcised. Best is prepucial skin.

- *Perineal urethrostomy is done for diversion***.**
- Perineal urethrostomy should be there until reconstruction of urethra takes up well *(Denis-Browne procedure).*
- *Magpi repair*: Meatal advancement glandular repair—for glandular hypospadias.

In hypospadias, circumcision is contraindicated as prepucial skin is required for future urethroplasty.

EPISPADIAS

- Here the urethra opens on the dorsum of the penis, proximal to the glans.
- Most common site is at the abdominopenile junction.
- It is associated with a dorsal chordee, ectopia vesicae, urinary incontinence, separated pubic bones.
- It is uncommon in females.



Figs 26.139A and B: Bladder extrophy. X-ray pelvis showing separation of pubic bones. Epispadias is the common association.

Treatment

- Correction of incontinence of urethra.
- Urinary diversion.

POSTERIOR URETHRAL VALVE

- They are congenital symmetrical valves in the posterior urethra, just below the verumontanum.
- It allows the passage of catheter without obstructing its ingress. But it obstructs the outflow of urine.

- Proximal urethra is enormously dilated with obstructive pathology in the bladder (sacculations and diverticula formation).
- Bladder wall is thickened and hypertrophied so much so that it is palpable in suprapubic region as a firm swelling *(cricket-ball bladder)*.
- There is poor urinary stream, with hydronephrosis, often with infection.
- Child finds difficult to pass urine.
- Often it is associated with vesicoureteral reflux.
- Renal failure and atrophy of kidney occurs due to back pressure.

Investigations

- *Micturating cystourethrography (MCU)* is diagnostic. It shows dilated proximal urethra.
- U/S abdomen.
- Blood urea and serum creatinine.
- IVU.
- Antenatal US shows fetal urinary tract dilatation.

Differential Diagnosis

- ***Marion's disease:*** Bladder neck obstruction due to hypertrophied interureteric bar. MCU differentiates it from posterior urethral valve. Treatment is Y-V plasty ***(Bonin's Y-V Plasty).***
- Neurogenic bladder.

Treatment

Initial SPC and later cystoscopic resection of the posterior valves is done usually after several weeks.

URETHRAL CALCULI

Stone from the bladder is commonly passed out through urethra if it is small, but the stone can get impacted due to a *stricture* or *urethral diverticulum*.

Sites of impaction

- Prostatic urethra
- Bulbous urethra
- Fossa navicularis
- External meatus

Clinical Features

- Painful urination with thin stream and forking of urine.
- Retention of urine.
- Lower urinary tract infection.
- Haematuria.
- Pain in the penis and perineum.
- Stone may be palpable when it is in the bulbar or penile urethra.

Investigations

- Plain X-ray, KUBU (kidney, ureter, bladder urethra).
- U/S abdomen.
- Urine examination.



Fig. 26.140: Stone at urethral meatus (external meatus) which is extracted.



Fig. 26.141: X-ray showing urethral stone.

Treatment

- If it is impacted in the external meatus or fossa navicularis, meatotomy and extraction of the stone is done (Meatotomy is cutting and widening of external meatus so as to have an easy stone extraction).
- If it is impacted in other parts of the urethra, urethroscopy and removal of stone from urethra is done or through a cystoscope the stone is pushed into the bladder and then extracted.
- In case of retention of urine, initial suprapubic cystostomy is required before removal of the stone.
- Diverticulum and stricture urethra should be treated accordingly.



Fig. 26.142: Plain X-ray KUB showing stone in the bladder; stone in the terminal end of ureter; stone in the prostatic urethra.

Complications

Bleeding, stricture urethra and infection.

URETHRITIS

Causes

- Gonococcal urethritis.
- Nongonococcal urethritis:
    - Trichomonal urethritis.
    - Lymphogranuloma venereum (LGV).
    - Mycoplasma.
    - Ureoplasma ureolyticum.
    - *Candida*.
- Trauma, catheters, cystoscopes, stones.
- Chemical urethritis.
- *Reiter's disease*: Arthritis, conjunctivitis, urethritis.
- Allergy.

Reiter's syndrome

- Nongonococcal urethritis
- Conjunctivitis
- Arthritis

Clinical Features

- Urethral discharge, dysuria, burning micturition, haematuria and increased frequency.
- Perineal pain, tenderness over the site.
- Suprapubic pain and tenderness.

Investigations

- Urine microscopy and culture.
- U/S abdomen.

Treatment

- Antibiotics given according to culture and sensitivity.
- The cause is treated.



Fig. 26.143: Periurethral abscess.

EXTRAVASATION OF URINE

Urine extravasates from the bladder or urethra and collects in the layers of the perineum or in the prevesical space (cave of Retzius).



Fig. 26.144: Extravasation of urine showing the collection of urine in the scrotum and perineum after trauma.

Causes

- Trauma to bladder or urethra.
- Instrumentation like dilatation, catheterisation, cystoscopy.
- Infection like gonococcus *(water can perineum)*.

True victory means complete control over sense-organs.

Types

It may be superficial or deep.

1. *Superficial:* It is due to either bulbar urethral injury or due to bursting of periurethral abscess after urethral stricture. Once urine extravasates due to full thickness disruption of the urethra anteriorly, it collects in superficial perineal space. This space is a closed cavity all round except anteriorly where it communicates with scrotal subcutaneous tissue deep to fascia Colles, penis between superficial fascia and deeper Buck's fascia, in the anterior abdominal wall deep to Scarpa'a fascia. It does not spread to thigh and ischiorectal space as Scarpa'a fascia is attached firmly to fascia lata of thigh. Superficial perineal space is closed above by inferior fascia of perineal membrane; below by fascia of Colles; laterally by ischiopubic rami. It is open and communicating only anteriorly. Entire scrotum, penis and often lower abdominal wall are swollen containing urine. It is painful; patient cannot pass urine through urethra; severe pain and shock due to pelvic injury. Often sepsis occurs and skin sloughs of leading into urinary fistulas.
2. *Deep:* Urine spreads upwards into the extraperitoneal space of the pelvis around the bladder and prostate into the anterior abdominal wall causing deep extravasation of the urine. Here rupture of urethra is at membranous part of the urethra much more proximal than superficial type.

Clinical Features

- Pain, swelling in the perineum.
- Retention of urine.
- Suprapubic pain, tenderness and fullness.

Treatment

- The cause is treated:
  - Antibiotics.
  - Suprapubic cystostomy.

Often multiple incisions may be placed in the perineum to evacuate the extravasated urine.

Complications

Abscess formation, sinus/fistula formation.

RETENTION OF URINE

- It is *accumulation of urine* in the urinary bladder. Kidneys excrete urine in normal quantity. But patient passes only small amount of urine or does not pass urine at all causing *distended bladder*. In anuria due to renal failure, patient does not pass urine as kidney does not secrete any urine and bladder is not distended.
- Retention can be *acute; chronic; retention with overflow*. Retention differs in male, female and in infants and children.
- Chronic retention is due to BPH, bladder neck contracture, urethral stricture, etc. and is painless with suprapubic dullness.
- It is one of the common conditions seen in surgical casualty.

Causes

Urethral injury
Stricture urethra
Stone in the urethra
Phimosis with meatal stenosis
Posterior urethral valve

Prostatic hyperplasia (BPH)
Carcinoma prostate
Bladder tumour near bladder neck
Bladder neck hypertrophy
Prostatitis or urethritis

Neurogenic causes like head and spinal injuries
Postoperative period following pelvic and perineal surgeries
Drug induced retention of urine: Anticholinergics, antihistamine drugs, antidepressants

In males

- BPH in old.
- Stricture urethra in young.
- Trauma—urethral/pelvic.
- Postsurgical—perineal surgeries like haemorrhoidectomy; fistulectomy; fissurectomy; pelvic surgeries; surgeries for fracture hip/fracture pelvic bone.
- Bladder outlet obstruction.
- Carcinoma of prostate.

In females

- Uterine prolapse.
- Urethral stricture.
- Uterine/Ovarian surgeries.

In infants and children

- Posterior urethral valve.
- Meatal stenosis.

Clinical Features

- Pain and swelling (fullness) in the suprapubic region.
- Inability to pass urine.
- Smooth, soft, tender swelling in hypogastric region which is dull on percussion.
- Features relevant of specific causes.
  - Per rectal examination to see prostate and other causes. In full bladder often prostate cannot be assessed properly.

Types

- Acute
- Chronic
- Retention with overflow

Acute retention: It is rare. It is sudden inability to pass urine. It is painful distension of the bladder. It is seen in urethral trauma, due to anaesthesia, or surgery (perineal/abdominal). There is increased desire to pass urine.

Chronic retention is gradual collection of urine in the bladder due to ineffective emptying of the bladder completely. Bladder is distended and is painless. It is common in elderly. Frequency, difficulty in urination, overflow incontinence is common. Infection in such chronic retention makes it painful.

Acute on chronic retention: Patient is having chronic obstructive condition like BPH; due to infection and acute inflammation and oedema of mucosa of urethra sudden total blockage sets in causing acute on chronic retention of urine.

Investigations

- U/S abdomen.
- Blood urea, serum creatinine.
- Urine microscopy.

Treatment

- Urinary catheterisation using Foley's catheter.
- If it fails then suprapubic cystostomy (SPC) using Malecot's catheter is done.
- The cause is treated.
- Intermittent catheterisation in case of neurogenic bladder.

Management of retention of urine

- Clinical and sonological assessment of kidney, ureter and bladder
- Evaluation for cause
- Evaluation for obstructive uropathy and renal function
- Urinary catheterisation by Foley's catheter/red rubber catheter/metallic catheter.SPC with Malecot catheter by open method or using Foley's catheter by trocal puncture method
- Intermittent catheterisation
- Vesicostomy in children
- Treating the cause
- Postoperative retention is a common cause. It is treated by reassurance, placing hot water bag over suprapubic region, change of position or standing, only occasionally by catheterisation

The quality of our thoughts determines our own personal degree of happiness.

E. Penis

> *The functioning role of the penis is as well established as that of any other organ in the body. Ironically, there is no organ about which more misinformation has been perpetrated. The penis constantly has been viewed but rarely seen. The organ has been venerated, reviled, and misrepresented with intent in art, literature, and legend through the centuries.*
>
> **—William H Masters, Virginia E Johnson,** 1966

CHAPTER OUTLINE

- Phimosis
- Paraphimosis
- Circumcision
- Balanoposthitis
- Chordee
- Priapism
- Peyronie's Disease
- Ram's Horn Penis
- Carcinoma Penis
- Buschke-Lowenstein Tumour


Superficial dorsal vein of penis
Deep dorsal vein of penis
Dorsal artery of penis
Albuginea
Corpus cavernosum
Deep artery of penis
Corpus spongiosum
Urethra

Fig. 26.145: Anatomy of penis.



Fig. 26.146: Degloving injury of penis which needed skin grafting later.

PHIMOSIS

It is inability to retract the prepuce over the glans.

Causes

1. Congenital—in which case the child has pinhole meatus and ballooning of prepuce occurs when the child urinates.



Figs 26.147A and B: Pinhole meatus with phimosis. It is an indication for circumcision. Often clinically there will be ballooning of the prepuce during urination.

2. Balanitis (inflammation of glans) and balanoposthitis (inflammation of glans, prepuce and sac). Common in diabetics.



Fig. 26.148: Posthitis and balanoposthitis are common causes of phimosis in adult. It may be common in diabetics. Carcinoma should also be ruled out. Specimen should be sent for histology after circumcision.

Patients with phimosis are more prone for recurrent infection, smegma collection and *carcinoma penis*.

Treatment

Circumcision.



Fig. 26.149: Phimosis. It is inability to retract prepuce over glans.

Problems due to phimosis

- Recurrent balanoposthitis
- Paraphimosis
- Ballooning of prepuceal skin
- Retention of urine
- Prepuceal calculi formation due to smegma collection in prepuceal sac
- Carcinoma of penis later

PARAPHIMOSIS

- Inability to place back (cover) the retracted prepucial skin over the glans is called as paraphimosis.
- It causes ring like constriction proximal to the corona and prepuceal skin.
- As a result the glans will be swollen, oedematous with severe pain and tenderness.
- Often glans will undergo necrosis or becomes gangrenous**.**



Fig. 26.150: Paraphimosis.



Figs 26.151A and B: Paraphimosis showing constricted ring with infection in the groove.



Fig. 26.152A

If you want to advance in life, make sure that your WANTS don't advance.



Figs 26.152B and C

Figs 26.152A to C: Paraphimosis is inabiliy to place back the retracted prepuce.

Paraphimosis is precipitated after sexual intercourse or iatrogenically after urethral catheterisation.



Fig. 26.153: Paraphimosis developed after catheterisation due to failure of replacing back of the prepuce.

Treatment

- Manual reduction of prepuceal skin is to be tried.
- If not possible, *initial dorsal slit* is made to relieve the oedema and compression. Antibiotics and analgesics are given. *Circumcision* is done after 3 weeks.
- Sedation and hyaluronidase injection in 10 ml saline into the constriction ring or multiple needle punctures over the oedematous part, reduces the oedema and makes the paraphimosis to get reduced. Later circumcision should be done.

CIRCUMCISION

> *And God said to Abraham, "As for you, you shall keep my covenant, you and your descendants after you throughout their generations. This is my covenant.... Every male among you shall be circumcised. You shall be circumcised in the flesh of your foreskins, and it shall be a sign of the covenant between me and you. He that is eight days old among you shall be circumcised."*—**The Bible,** date unknown

Indications

- Religious
- Phimosis
- Paraphimosis after doing initial dorsal slit
- Balanitis and balanoposthitis (common in diabetics)
- Early carcinoma of prepuce or glans penis—both diagnostic as well as therapeutic purpose
- Certain sexually transmitted diseases, e.g. herpes infection

Procedure (Refer Fig. 26.154)

- In children, it is done under G/A. In adults, it is done under local anaesthesia.
- After cleaning and draping, LA [1% lignocaine *(plain)* injected circumferentially near the root of the penis] is given (ring block).
- Dorsal skin is cut up to the corona and later circumferentially and ventrally.
- The skin is cut with inner layer.
- Care is taken to see that optimum (less) skin is cut ventrally to prevent the occurrence of *chordee*.
- Frenular artery is transfixed and ligated ventrally using chromic catgut (2-0 or 3-0). Small bleeders are also ligated.
- Skin is apposed to the cut edge of corona using interrupted chromic catgut sutures.
- Postoperatively, antibiotics and analgesics are given.

Complications

- Reactionary haemorrhage due to slipping of ligature from frenular artery and dorsal vein
- Infection
- Stricture urethra near the external meatus in *children*
- Chordee due to removal of excess skin on the ventral aspect
- Rarely priapism can occur

- *Hollister Bell cap technique* (Plastibel device): This specially devised plastic cap can be fitted over the glans



Fig. 26.154: Operative steps of the circumcision.

penis and prepuce is rolled over it. A tight ligature is tied over it near base of the prepuce. In 7 days skin and prepuce sloughs off and sheds with the cap. Bleeding will not occur due to thrombosis of prepuceal vessels. Technique can be used for religious circumcision/balanoposthitis without phimosis. It is contraindicated in phimosis and paraphimosis.

Note:

- Circumcision *by guillotine* is a method done by pulling and stretching the prepuceal skin beyond the glans and cutting the prepuce. It should be condemned and not be done as injury to glans is common. It is practiced in religious circumcision.
- ***Monopolar cautery should not be used*** in circumcision.

BALANOPOSTHITIS

It is inflammation of glans and prepuce—(Inflammation of prepuce is posthitis; of the glans is balanitis).

Causes

- Diabetes mellitus.
- Candidiasis.
- Veneral diseases like syphilis, herpes.

It can cause phimosis, carcinoma penis.

Clinical Features

Pain, swelling, discharge.

Treatment

- Antibiotics.
- Circumcision.
- The diabetes is controlled.

CHORDEE (CORDEE)

It is fixed bending of glans penis, more obvious during erection.



Fig. 26.155: Chordee.

Types

a. Ventral.
b. Dorsal.

Causes

- Hypospadias, where urethra opens more proximally than normal *(ventral cordee).*
- After circumcision, if more skin is cut over the ventral aspect (*ventral cordee*).
- In epispadias *dorsal cordee* occurs.

Treatment

- Chordee due to hypospadias is corrected during staged procedure.
- In chordee following circumcision, initially stilbestrol 6 mg daily is given. Later chordee is corrected surgically by excising fibrous tissue and later doing skin grafting. More often they require surgical intervention.

PRIAPISM

- It is persistent, painful erection of penis.
- Corpora cavernosa are filled with blood due to defective venous drainage. Glans and corpus spongiosum are not involved.

Causes

- Idiopathic *thrombosis of corpora cavernosa*
- Idiopathic thrombosis of prostatic venous plexus
- Sickle cell disease
- Leukaemia
- Secondary deposits in corpora cavernosa
- Spinal injury or diseases

Investigations

Relevant for specific causes.

Treatment

- Anastomosis between corpora cavernosa and saphenous vein.
- Anastomosis between corpora cavernosa and corpus spongiosum.

PEYRONIE'S DISEASE (Induratio-penis Plastica)

- It is development of fibrous tissue plaque on the covering of corpus cavernosum and later involving its full extent resulting in induration of corpus.
- It is a slowly progressive disease of uncertain aetiology, may be due to old trauma, often associated with *Dupuytren's contracture, retroperitoneal fibrosis and plantar fasciitis.*

- Initial active phase has painful erection with changing deformity of penis.
- Later quiescent phase has disappearance of painful erection with development of deformity which is painless.
- Later erectile dysfunction; penile shortening occurs.
- Indurated plaque is noticed in the penis.

Treatment

- Some cases resolve spontaneously.
- Drugs
  - Steroids.
  - Vitamin E.
  - Potassium amino benzoate 12 mg/day.
  - Tamoxifen 20 mg daily.
  - Terfenadine and fexafenadine.
  - Colchicine therapy.
  - Intralesional injection of verapamil 10 mg once in 2 weeks—12 injections.
- Surgery is needed in many cases
  - Excision and plication to opposite side—*Fitzpatric operation*.
  - Multiple incisions over the fibrous plaque and temporal fascia bridging—*Gelhard's operation*.
  - Excision of fibrous plaque and corporotomy is covered with overlay flap like tunica vaginalis flap (*Lockhart's*)/ dermal flap (*Devine and Horton's*).
  - Intracorporeal penile prosthesis placement.

RAM'S HORN PENIS

Filarial involvement of penis where it becomes thick, distorted and resembles horn of a ram.

CARCINOMA PENIS

- It is commonly *squamous cell carcinoma*, but melanoma, adenocarcinoma from Tyson's gland, basal cell carcinoma and secondaries may also occur.



Fig. 26.156: Carcinoma of penis involving glans extensively.



Fig. 26.157: Carcinoma penis earlier operated by total amputation of penis has now developed secondaries in inguinal lymph nodes which has already fungated. Note the perineal urethrostomy done.



Figs 26.158A and B: Carcinoma penis in two different patients.

Aetiology

- Chronic balanoposthitis, phimosis.
- Sexually transmitted diseases.
- Leukoplakia of glans.
- Long-standing genital warts.
- *Paget's disease* of penis (Erythroplasia of Querat is persistent rawness of glans penis).



Fig. 26.159: Carcinoma penis—circumferential proliferative exophytic lesion.



Fig. 26.160: Small ulcerated lesion over glans penis—carcinoma.

- Condyloma acuminata (by human papilloma virus), balanitis xerotica obliterans.
- HIV infection—HPV-16.



Fig. 26.161: Genital warts—in glans penis. It is a premalignant condition. Biopsy, excision and podophyllin application is needed.

  - *Circumcision during infancy confers total immunity against carcinoma penis*.
  - It is common in Asia and Africa.

Pathology

- *Infiltrating type* occurs in a preexisting leukoplakia. It often presents as indurated area.



Figs 26.162A and B: Erythroplasia of glans penis. It is a premalignant condition.



Fig. 26.163: Carcinoma of penis causing destruction of entire penis.

- *Papilliferous type* eventually attains a large size forming a fungating foul smelling lesion which often gets infected.
- *Ulcerative type*.
  - Glans penis is the most common site (coronal sulcus for basal cell carcinoma).
  - 80% are of low grade tumours.

Our senses don't deceive us; our judgement does.



Fig. 26.164: Carcinoma penis with proliferative lesion.

Spread

- Through lymphatics, it spreads to the horizontal group of inguinal lymph nodes which become nodular and hard. Lymph nodes on both sides can get involved. Later, external iliac group are involved (above and on medial aspect of the inguinal ligament).
- Once inguinal lymph nodes are fixed, it causes severe excruciating pain and lymphoedema. *Fixed lymph node status indicates the advancement of the disease.* It may erode into the femoral vessels causing torrential haemorrhage and death. Fungation can occur.
- From glans, it also spreads to Cloquet lymph node which is located in femoral canal.
- Carcinoma from shaft of penis can spread directly to the external iliac lymph nodes.
- It spreads proximally to the body of penis causing induration.
- Urethral meatus may get involved causing alteration in urinary stream. *It is a locoregional malignant disease.*
- *Blood spread is rare*.

Clinical Features

- In an adult, recent onset of phimosis should raise the suspicion of carcinoma penis.



Fig. 26.165A



Fig. 26.165B

Figs 26.165A and B: Verrucous carcinoma of penis.

- Lesion is painless initially but later becomes painful due to secondary infection, often accompanied by discharge which is foul smelling, purulent and irritating.
- Altered urinary stream.
- Fungation and induration, everted edge, often extending into the body of penis.
- Palpable hard, nodular inguinal lymph nodes on both sides may be present. External iliac lymph nodes may be palpable.
- Pain, oedema, tenderness, redness develops once infection occurs.

Investigations

1. *Edge biopsy* from the lesion shows squamous cell carcinoma with epithelial pearls.

Broder's grading

- Very well differentiated (75% epithelial pearls)
- Well differentiated (50-75%)
- Moderately differentiated (25-50%)
- Undifferentiated (< 25%)

2. *FNAC of lymph nodes* (No open biopsy for lymph nodes).
3. U/S abdomen, to look for involvement of external iliac lymph nodes.
4. *SLNB*—**Cabana sentinel node** is located above and medial to the junction of saphenous and femoral vein. It is the first node to get involved in carcinoma penis. So this Sentinel Lymph Node Biopsy (SLNB) after isosulphan blue dye injection in to the primary is done to decide for the necessity for ilioinguinal block dissection.



Fig. 26.166: Carcinoma of penis.

Staging of Carcinoma of Penis

Jackson's staging of carcinoma penis

Stage I – Tumour involving only glans/prepuce/both	90% five-year survival
Stage II – Tumour extending into body of penis	70%
Stage III – Tumour having mobile inguinal nodes	50%
Stage IV – Tumour spreading to adjacent structures/fixed nodes	5%

TNM staging

T_0 – No primary tumour
Tis – Carcinoma *in situ*
T_1 – Tumour < 2 cm without deep invasion
T_2 – Tumour between 2-5 cm with minimal deep invasion
T_3 – Tumour > 5 cm with deep invasion/urethral spread
T_4 – Tumour spread to adjacent tissues
N_0 – No nodal spread
N_1 – Mobile regional nodes—unilateral
N_2 – Mobile regional nodes—bilateral
N_3 – Fixed regional nodes
M_0 – No distant spread
M_1 – Distant spread present

Treatment

- If growth involves the glans without extending into the proximal part of shaft of the penis, then *partial amputation of the penis* is done. A length of 2.5 cm stump is retained. Clearance of 2 cm from the proximal extended part of the tumor is needed. Advantage is proper streaming of the urine is possible.
- Partial amputation of penis with bilateral ilioinguinal lymph node block dissection is called as *Young's operation.*



Fig. 26.167: *In situ* carcinoma penis over the glans.

- If tumour involves the proximal part of the body of penis or if it is anaplastic/poorly differentiated tumour *total amputation of penis* is done with *perineal urethrostomy*. Problems with perineal urethrostomy are scrotal ammoniacal dermatitis and stricture at urethrostomy site. Dermatitis is prevented by asking the patient to urinate in sitting position lifting the scrotum upwards. Stricture needs dilatation.



Fig. 26.168: Partial amputation of penis with catheter *in situ*.

- Total scrotectomy with orchidectomy is done along with total amputation of the penis—*Sir Piersey Gold operation*. It prevents frequent dermatitis of the scrotal skin because of the perineal urethrostomy and also reduces the sexual desire.
- In case of carcinoma *in situ*, T_1 lesion of glans penis or well differentiated tumour in young individual, circumcision and curative radiotherapy to the penis can be given using radio-active tantalum wire implantation (6000 cGy in 7 days) or by wearing radium penile mould continuously or intermittently (6000 cGy in 7 days) or by linear accelerator external beam radiotherapy (6000 cGy in 5 weeks). Involve-ment of nodes in these patients is less than 10%.

Violence at home can lead to blood in the streets.



Fig. 26.169: Specimen of total amputation of penis done for carcinoma of penis.

- When lymph nodes are involved and are mobile, *bilateral ilioinguinal nodal dissection* is done.
  - *Primary inguinal block* is doing block dissection within 4 weeks of surgery for primary tumour.
  - *Secondary inguinal block* is doing block dissection after 4 weeks of surgery for primary disease. Only 50% of palpable inguinal nodes are involved by metastatic spread. So often a course of antibiotic is given and waited for 4-6 weeks. Complications of ilioinguinal block dissection are *flap necrosis*, lymphoedema of lower limb, femoral blow out, infection, lymphorrhoea and haemorrhage.
  - If primary tumour is poorly differentiated, and if tumour is T_2 or above, chances of inguinal nodal spread is more than 50% and so a prophylactic inguinal nodal dissection is done.
  - Often, involvement of inguinal nodes may be due to infection. So a trial of antibiotic therapy is given for 4-6 weeks to reduce the size of the inguinal node.
  - Removal of iliac nodes does not alter the outcome. It is done to confirm the spread, so that further therapy can be planned and prognosis can be predicted.
- Postoperative radiotherapy to inguinal region is often given.
- In advanced fixed inguinal nodes palliative external radiotherapy is given. It is to palliate pain, fungation and anticipated erosion into femoral vessels.
- Topical 5 FU cream or Nd:YAG laser photoirradiation is useful in carcinoma *in situ*.
- *Chemotherapy:*
  5 FU; methotrexate, bleomucin, cisplatin and vincristine. MBP/VBM combinations are used.
  Bleomycin is a radiosensitiser and so beneficial if RT is planned later.

Note:

- *Dresslers quadrangle*—upper border is formed by line joining anterosuperior iliac spine and pubic tubercle; laterally line joining anterosuperior iliac spine and a point 20 cm below it; medially pubic tubercle and a point 15 cm below it. Nodal block dissection for carcinoma penis should cover this area adequately.
- *Elective prophylactic inguinal block* is done in high-risk group—invasive carcinoma; T_2 and T_3 tumours; with vascular invasion.
- *Therapeutic inguinal block* is done whenever FNAC of node shows positive tumour.
- *Superficial lymph node block* is dissection superficial to fascia lata in N_0 disease. It should undergo frozen section biopsy. If nodes are positive, then formal block dissection should be done.
- *Standard inguinal lymphadenectomy*—is classical block dissection.
- *Modified inguinal block dissection* (Catalona)—small incision, limited dissection, preservation of saphenous vein.



Fig. 26.170: S shaped incicion for ilioinguinal block dissection. Many modification incisions are also used.

Role of radiotherapy in carcinoma penis

- Carcinoma *in situ*
- Small lesion less than 2 cm
- Lesion confined to glans
- Small lesion in young individual
- Advanced inoperable disease
- Palliation to inoperable inguinal nodes in groin
- Postoperative RT



Fig. 26.171A




Bladder
Urethra
Foley's catheter
Urosac bag
C

Figs 26.171B and C

Figs 26.171A to C: Perineal urethrostomy is done for urethral injury, urethral surgeries like urethroplasties as diversion and after total amputation of penis in carcinoma penis.

Complications of inguinal block dissection

- Haemorrhage
- Lymphorrhoea
- Lymphoedema
- Infection
- Flap necrosis—*common*


Carcinoma
Incision
Partially amputated penis
Urethra
Urethra
Retained stump

Fig. 26.172: Partial amputation of penis is done in penile carcinoma in the glans not extending into the body of the penis.



Fig. 26.173: Total penectomy for carcinoma penis. Note the drain placed; sutures; urethrostomy site.

BUSCHKE-LOWENSTEIN'S TUMOUR

It is verrucous carcinoma of penis (5-15% common).

- *It is a curable malignancy*.
- It is locally destructive, locally invasive.
- It is often large, exophytic, dry, verrucae-like growth.
- Neither spreads through lymphatics nor blood.
- After biopsy and confirmation, surgical excision or partial amputation is the treatment of choice.
- Radiotherapy should not be given**.**
- Virus aetiology is proposed—HPV—6 and 11.
- Systemic interferon α therapy and Nd:YAG laser therapy is successful.

To every disadvantage, there is a corresponding advantage

F. Scrotum

CHAPTER OUTLINE

- Anatomy
- Fournier's Gangrene
- Hydrocele
  - Primary Vaginal Hydrocele
  - Secondary Hydroscele
- Haematocele
- Pyocele
- Cyst of Epididymis
- Spermatocele
- Varicocele

ANATOMY

It is a cutaneous bag containing the right and left testis, epididymis and lower part of spermatic cord.

Layers (from without inwards)

1. Skin
2. Dartos muscle
3. External spermatic fascia
4. Cremasteric fascia
5. Internal spermatic fascia

Blood Supply

From external pudendal, deep external pudendal and internal pudendal arteries.

Nerve Supply

- Anterior 1/3rd portion by ilioinguinal nerve and genital branch of genitofemoral nerve.
- Posterior 2/3rd portion by posterior scrotal branch of pudendal nerve and perineal branch of posterior cutaneous nerve of thigh.
- Dartos is supplied by sympathetic nerve.

FOURNIER'S GANGRENE

- It is also called as *idiopathic gangrene of the scrotum*.
- It is a vascular gangrene of infective origin, caused by haemolytic streptococci, microaerophilic streptococci, staphylococci, *E. coli*, *Cl.welchii, Bacteroides fragilis*.
- There will be fulminant inflammation of the scrotal skin and subcutaneous tissues resulting in *obliterative arteritis* of the arterioles of the scrotal skin leading into cutaneous gangrene.
- It is common in diabetics, old age, malnourished, immunosuppressed individuals.

Clinical Features

- Condition is common in old age.
- Sudden pain in the scrotum, fever, severe toxicity.
- Very fast spreading cellulitis of scrotal skin, extending to the groin and often to anterior abdominal wall.
- Extensive skin sloughing occurs *leaving normal testis exposed.*
- Sometimes toxicity is so severe that they may go for renal failure and other complications.
- Sometimes the condition may worsen rapidly leading to death (25% mortality).



Fig. 26.174: Carcinoma of scrotum with inguinal node secondaries.



Fig. 26.175A



Fig. 26.175B

Figs 26.175A and B: Fournier's gangrene. Testes are normal. It is an infective gangrene of scrotum, rapidly spreading.

Treatment

- Treated as an in-patient always.
- IV fluids and catheterisation—for maintenance of urine output.
- Antibiotics, blood transfusion.
- Nutritional support (TPN, enteral).
- Liberal excision of all slough.
- Once patient recovers and wound granulates well, *skin grafting is done.*
- ***Orchidectomy is not necessary as testis is normal and viable.***
- Testis can be placed in the pouch in medial aspect of the thigh.

HYDROCELE

It is the collection of fluid between the two layers of tunica vaginalis of testis.

Types

- Congenital
- Acquired
  - Primary
  - Secondary

Aetiology

- Defective absorption of fluid by the tunica vaginalis, probably due to damage to the endothelial wall by low-grade infection.
- Excessive production of fluid as in secondary hydrocele.
- Interference with drainage of fluid by lymphatic vessels of the cord.
- Communication with the peritoneal cavity.



Fig. 26.176: Bilateral hydrocele.



Figs 26.177A and B: Massive hydrocele wherein penis is buried completely within the hydrocele area.

The smallest good deed is better than the grandest intention.

Hydrocele fluid is amber-coloured with specific gravity of 1.022 to 1.024. It contains water, salts, albumin, fibrinogen. Per se, hydrocele fluid does not clot, but if it comes in contact with the blood, fibrinogen gets activated and clots firmly. Often fluid contains cholesterol and tyrosine crystals.



Fig. 26.178: Types of hydrocele.

Cysts which contain cholesterol crystals

- Vaginal hydrocele
- Branchial cysts
- Dentigerous cyst

PRIMARY VAGINAL HYDROCELE

- Occurs in middle-aged, common in tropical countries.
- Testis is not palpable as it usually attains a large size (unlike secondary hydroceles which are small, except in filarial hydrocele).
- *Fluctuant* (elicited by, fixing the hydrocele with hand and feeling for the fluid movement using fingers placed in *two perpendicular directions*).

Note:

A relaxed muscle can demonstrate fluctuation in one direction even though there is *no fluid* in it.

- *Initially transilluminant* (elicited in front of the swelling, side to side), but long-standing hydrocele is nontransilluminant (due to thickened dartos, thickened spermatic fascia, thickened hydrocele sac, infected content, chylous fluid, often filarial hydrocele, haematocele).
- Can *get above the swelling* (you can feel only cord structures and nothing else at the root of the scrotum, unlike in hernia).
- Testicular sensation can be elicited in vaginal hydrocele by transmitting the pressure sensation through the fluid.



Fig. 26.179: Hydrocele which is brilliantly transilluminant.



Fig. 26.180: Get above the swelling is possible in case of hydrocele.

Swellings which are brilliantly transilluminant

- Vaginal hydrocele
- Epididymal cyst
- Cystic hygroma
- Ranula
- Meningocele



Fig. 26.181: Hydrocele is transilluminant. It may be negative in long-standing hydrocele, thick sac, thick dartos, thick skin and infected fluid or chylocele.



Figs 26.182A and B: Hydrocele in two different patients. One is average sized; another is large and penis is buried into the hydrocele swelling.

Infantile Hydrocele

Here tunica and processus vaginalis (hydrocele) are distended up to internal ring, but sac has no connection with the general peritoneal cavity.

Congenital Hydrocele

- Processus vaginalis communicates with the peritoneal cavity.
- As this communicating orifice is too small, bowel does not descend and so hernia usually will not develop. While lying down, fluid disappears gradually and while standing fluid recollects.
- Hydrocele cannot be emptied by digital pressure as it causes "*inverted ink bottle*" effect. Ascites, tuberculous peritonitis are the aetiologies for the same.

Encysted Hydrocele of the Cord

- It is the *fluid collection* in a portion of patent funicular process part of the tunica vaginalis; but closed above and below; located in inguinal/inguinoscrotal/scrotal part which is fluctuant and transilluminant.
- On gentle traction to the testis, the swelling becomes less mobile (*traction test*).
- Differential diagnosis: Epididymal cyst, inguinal hernia, lipoma of cord, varicocele.
- Treatment is excision under local anaesthesia.

Hydrocele-en-bisac (Bilocular Hydrocele)

Hydrocele has got two intercommunicating sacs, one above and one below the neck of the scrotum. Upper one lies superficial or in the inguinal canal or may insinuate itself between the muscle layers—*cross-fluctuant.*

Other conditions where cross-fluctuation is elicited:

- Plunging ranula
- Compound palmar ganglion
- Psoas abscess

Hydrocele of the Canal of the Nuck

It occurs in females, in relation to the round ligament, always in the inguinal canal.

Hydrocele of the Hernial Sac

It is due to adhesions of the content of hernial sac. Fluid secreted collects in the hernial sac and forms hydrocele of the hernial sac.

SECONDARY HYDROCELE

Causes

Infection:	Filariasis Tuberculosis of epididymis—30% cases have secondary hydrocele Syphilis
Injury:	Trauma, postherniorrhaphy hydrocele
Tumour:	Malignancy

Secondary hydrocele rarely attains large size

It is usually small, lax and testis is usually palpable (unlike primary hydrocele). *Exception is, secondary hydrocele due to filariasis.* It can be very large.

Postherniorrhaphy Hydrocele

It is a secondary hydrocele occurring after the surgery for inguinal hernia. It is due to the damage to lymphatic vessels of the tunica vaginalis and is 0.2% common. It is treated like any hydrocele but usually after about 6 months.

Filarial Hydrocele and Chylocele



Fig. 26.183: Chylocele.

- Occurs commonly in coastal region, and in and around the equator.
- Usually occurs after repeated attacks of filarial epididymitis.
- Hydrocele is usually of large size and the sac is thickened.
- Fluid contains fat, rich in cholesterol, and is derived from ruptured lymph varix into the tunica.
- It is often difficult to differentiate from primary hydrocele.



Fig. 26.184: Hernia of hydrocele is a rare complication of hydrocele. Herniation occurs through dartos.

Complications of hydrocele

- Infection
- Pyocele
- Haematocele
- Atrophy of testis, hernia of hydrocele (rare)
- Infertility
- Hernia of hydrocele sac (rare)

Differential diagnosis

- Inguinal hernia
- Epididymal cyst
- Spermatocele
- Testicular tumour
- Scrotal oedema

Treatment for Hydrocele

Surgery

- Sub-total excision
- Partial excision and eversion (Jabouley's operation)
- Evacuation and eversion
- Lord's plication

Procedure

- Under G/A or spinal or L/A, after cleaning and draping, vertical incision of about 6-8 cm in length is made over the scrotum, anteriorly 1 cm lateral to the median raphe.
- Skin, dartos, external spermatic fascia, internal spermatic fascia are incised.

  Bluish hydrocele sac is identified, i.e. parietal layer of the tunica vaginalis of testis.

  Fluid is evacuated using trocar and cannula. Sac is opened.



Fig. 26.185: Trocar and cannula used to evacuate the hydrocele fluid.



Fig. 26.186: Trocar and cannula used for hydrocele surgery.



Figs 26.187A and B



Figs 26.187C to E

Figs 26.187A to E: Bluish hydrocele sac and hydrocele fluid in the sac.

- *If the sac is small, thin and contains clear fluid,* either *Lord's plication*, i.e. tunica is bunched into a "ruff" by placing series of multiple interrupted chromic catgut sutures so as to make the sac to form fibrous tissue (It is relatively avascular and so haematoma will not occur).
- Or *evacuation and eversion* of the sac behind the testis (after eversion, everted sac is sutured with chromic catgut by continuous sutures) is done.
- *If the sac is thick, in large hydrocele and chylocele***,** *subtotal excision of the sac* is done (as tunica vaginalis is reflected on to the cord structures and epididymis posteriorly, total excision leads to orchidectomy with division of cord).
- Often the sac is excised partially and then eversion is done, which is called as *Jabouley's* operation.
- After evacuation, the sac with the testis is placed in a newly created pocket between the fascial layers of the scrotum *(Sharma and Jhawer's technique).*
- *Aspiration must be avoided as much as possible* as it is only a temporary measure (recurrence occurs very early) and chances of haematocele, infection are higher.
- A drain is placed near the root of the scrotum on the lateral aspect because it becomes the most dependent portion, when scrotal support is given. Scrotal support is given to reduce the scrotal oedema.
- Wound is closed in layers.
- Drain is removed in 48 hours.



Fig. 26.188: Transillumination of hydrocele sac during surgery just prior to placing the trocar for evacuation after exposing the sac.

Surgeries for hydrocele

- Subtotal excision of the sac
- Jabouley's operation
- Evacuation and eversion
- Lord's plication
- Sharma and Jhawer's technique

Complications of surgery

- Reactionary haemorrhage
- Infection
- Pyocele
- Sinus formation
- Recurrent hydrocele

> *In early testicular tuberculosis there is often a loss of cutaneous elasticity as shown by smoothening out of rugae consequent upon wasting of the cellular tissue beneath the dermis.*
> **—A Clifford Morson**



Figs 26.189A to D: Hydrocele surgery showing sac; trocar and cannula; its insertion and evacuation of fluid.

Conditions which cause loss of testicular sensation

i. Testicular tumour
ii. Lepra orchitis
iii. Syphilitic orchitis
iv. Chronic haematocele

Conditions where orchidectomy is done in hydrocele

- Pyocele with testicular destruction
- Clotted haematocele with testicular destruction



Fig. 26.190: Multiloculated hydrocele—on table look.

HAEMATOCELE

Types

a. Recent Haematocele

- It is due to rupture of one of the vessels in the tunica causing bleeding into the sac.
- Often it may occur following aspiration of a hydrocele.
- It may be precipitated by trauma also.

Clinical features:

- Sudden onset of pain and swelling after an history of trauma.
- It is tender, warm, fluctuant, but nontransilluminant.
- Occasionally aggressive testicular tumour mimics the presentation of acute, recent haematocele.
  - U/S of scrotum is done in such suspected cases to rule out neoplasm and also to find out the viability of testis.



Figs 26.191A to C: Haematocele in different patients. Orchidectomy is often required in these patients if testis is not viable.

Complications

- Chronic (old clotted) haematocele
- Infection
- Pyocele

Treatment: The scrotum is explored under general anaesthesia. The clot is evacuated and the wound is closed with a drain.

b. Chronic or Old Clotted Haematocele

- It is usually due to slow, spontaneous haemorrhage into the tunica vaginalis, without any proper history of trauma.
- It is painless, hard, nontender, nonfluctuant, often calcified swelling, with *loss of testicular sensation*.
- Because of the constant pressure, testicular function and so testicular sensation is lost. It mimics testicular tumour in many aspect.
- U/S of the scrotum is done.
- **Treatment is** *orchidectomy,* as testis is functionless (Low orchidectomy through scrotal approach).



Fig. 26.192: Low orchidectomy is done in case of haematocele, pyocele. Here incision is in the scrotum. Cord is doubly ligated using thick chromic catgut.

PYOCELE

- It is collection of pus in the layers of tunica vaginalis.
- It can occur in a previously normal tunica or in a pre-existing haematocele or hydrocele (which gets infected).



Fig. 26.193: Pyocele—clinical look. US confirms the diagnosis. TC will be raised.

Features

- Fever, toxicity, tender swelling in the scrotum, with scrotal wall oedema.
- Often in young individuals, it may be difficult to differentiate this from the torsion testis.
- Pus under tension eventually causes infective thrombosis of testicular vessels, leading to nonviability of the underlying testis or testicular gangrene.



Fig. 26.194: Pyocele of scrotum. It is pus collection in the tunica vaginalis testis. It needs immediate exploration; drainage; often orchidectomy.

Treatment

- Antibiotics are started.
- Scrotum is explored immediately and pus is evacuated.
- Viability of the testis is checked.
- If viable, pus is evacuated and sent for C/S, wound is closed with a drain.
- If the testis is not viable, then *orchidectomy* is done (after taking consent).
- When in doubt, always testis is left in place and observed. Often, testis will show signs of viability. If not, then orchidectomy is done at a later stage.

CYST OF EPIDIDYMIS

It is due to the cystic degeneration of:

- Paradidymis (organ of Geraldes)—is the most common cause
- Appendix of the epididymis
- Appendix of the testis
- The vas aberrans of Haller

- Even though it is of congenital origin, it occurs in middle age.
- It is tensely cystic, contains clear fluid.
- Often bilateral.
- They are aggregation of number of small cysts and so *multiloculated.*
- They feel like '*bunch of tiny grapes*' situated behind the body of the testis.
- It is situated behind the body of testis.

In transposition of the viscera (situs inversus) the right testis hangs lower.—**C Allan Birch**

- Because of numerous septae they are finely tessellated and so are brilliantly transilluminant, appear like ***'chinese lantern pattern'.***



Fig. 26.195: Epididymal cyst showing multiloculated 'Chinese lantern' pattern. Its location is behind the body of testis.



Fig. 26.196: Epididymal cyst.

Differential Diagnosis

- Spermatocele.
- Encysted hydrocele of the cord.

Treatment

- Avoid excision as much as possible as it results in infertility due to blockage.
- In old age, excision can be done.

SPERMATOCELE

It is a *unilocular, acquired retention cyst* derived from blockage of some portion of the sperm conducting mechanism of the epididymis.

- It is situated in the head of the epididymis, above and behind the body of the testis.
- Swelling contains *barley water like fluid,* which contains spermatozoa.
- It is soft, cystic and transilluminant. It is often considered by the patient as having an additional testis.
- Aspiration cytology confirms the diagnosis.

Treatment: It can be left alone. If it is large, excision is done.



Fig. 26.197: Spermatocele occurs behind and above the testis. It is unilocular containing 'barley' like fluid.



Fig. 26.198: Spermatocele. It was earlier mistakenly called as 3rd testis.

Differential Diagnosis

- Epididymal cyst.
- Hydrocele.

Epididymal cyst	*Spermatocele*
Congenital	Acquired retention cyst
Behind the body of the testis	Behind and above the testis
Multilocular	Unilocular
Bunch of grapes appearance	Looks like 3rd testis
Clear fluid as content	Barley water fluid contains sperms
Brilliantly transilluminant	Transilluminant
Excision should be avoided in young	Can be excised

VARICOCELE

- It is dilatation and tortuosity of the pampiniform plexus of veins and so also the testicular veins. Normally, there will be numerous plexus of veins (pampiniform) in the scrotum, which all join together to form about 4-8 veins in the inguinal canal. Above, in the abdominal cavity, in the posterior abdominal wall all join to form a single testicular vein. On left side, it drains the left renal vein; on the right side it drains the inferior vena cava.
- Varicocele is common in *tall, thin young men*.
- More common on the *left side*, but often can be bilateral.



Fig. 26.199: Clinical photo of left sided varicocele—'bag of worms' look.



Fig. 26.200: Anatomy of testicular veins. Left testicular vein joins into left renal vein in perpendicular fashion. Right vein joins IVC directly.



Fig. 26.201: Scrotal U/S showing varicocele.

- Commonly, it is idiopathic in origin, may be due to absence or incompetent valve at the junction of left testicular vein and left renal vein causing inefficient drainage of blood. Other reason is, due to perpendicular (right angle) entry of the left testicular vein into the left renal vein.
- In left sided renal cell carcinoma, tumour proliferates into the left renal vein and blocks the entry of left testicular vein causing varicocele on left side which is *irreducible.*
- Varicocele causes increased temperature in the scrotum which depresses the spermatogenesis and so causes *infertility* (correctable infertility).



Fig. 26.202: Varicocele it is common on left side.

> *When the scrotal skin of the affected side is less rugose than the normal side, it is probable that, that half of the scrotum never contained a testis.W*
>
> **—Kenneth I Macrosson**



Figs 26.203A and B: Varicocele—on table look of tortuous pampiniform plexus of veins.

Types of Varicocele

- *Primary/idiopathic*—95%: No cause is found. There is incompetence of valves of the testicular vein. It is common on left side because left testicular vein joins left renal vein perpendicularly and left side vein is longer and liable to get compressed by loaded sigmoid colon. Left renal vein is often compressed between aorta and SMA.
- *Secondary*—due to specific cause like left-sided renal cell carcinoma with a tumour thrombus in left renal vein causing obstruction to venous flow of left testicular vein.
- *Subfertility/infertility* are observed even in unilateral varicocele. It is a debate whether it really causes subfertility. Possible causes are:
- Altered heat exchange mechanism of the scrotum due to varicocele → hyperthermia → inhibition of spermatogenesis.
- Increased blood flow → increased temperature in the testes → increases the metabolic activity using glycogen storage → depletion of glycogen → injury of parenchyma of testes → oligospermia.
- Hypoxia of testes.
- Same cause leads into Leydig cell dysfunction, decreasing testosterone levels.
- Final effect is maturation arrest → poor spermatogenesis.

Clinical features

- Swelling in the root of the scrotum
- Dragging pain in the groin and scrotum
- *"Bag of worms"* feeling
- Impulse on coughing
- On lying down it gets reduced (except in renal cell carcinoma)

Bow sign: After holding the varicocele between thumb and fingers, patient is asked to bow. Varicocele gets reduced in size. Bowing reduces the blood flow of testicular vein and pampiniform plexus causing reduction in size.

Grading of varicocele

I. Small
II. Moderate
III. Large
IV. Severely tortuous

Differential Diagnosis

- Hydrocele.
- Inguinal hernia.
- Lymph varix.
- Lipoma of the cord.

Investigations

- Venous Doppler of the scrotum and groin.
- U/S abdomen to look for kidney tumour.
- Semen analysis.

Treatment



Fig. 26.204: On table varicocele finding.

- ***Palomo's operation***: Suprainguinal extraperitoneal ligation of the testicular vein.
- ***Inguinal approach (Inavissevich approach)***: Easier and safer.
- ***Subinguinal approach*** *(Marc-Goldstein)*: It is subinguinal approach at superficial inguinal ring outside the external oblique aponeurosis without opening the external oblique aponeurosis. Here cord is easily identified through a small incision.
- ***Scrotal approach***: In case of grade IV, veins have to be excised through this approach.
- ***Laparoscopic approach***: Presently accepted, good approach.

Indications for surgery

- Pain
- Oligospermia—usually in 6-12 weeks oligospermia improves very well and also the conception rate

Complications of varicocele surgery

- Haemorrhage and scrotal haematoma
- Infection, pyocele
- Injury to testicular artery
- Injury to ilioinguinal nerve and pain
- Recurrence—5-10%

Chapter 27 Neurosurgery

CHAPTER OUTLINE

- Head Injuries
- Extradural Haematoma
- Subdural Haematoma
- Subarachnoid Haemorrhage
- Depressed Skull Fracture
- Hydrocephalus
- Intracranial Abscess
- Intracranial Aneurysms
- Intracranial Tumours
- Pituitary Tumours
- Craniopharyngiomas
- Spinal Dysraphism
- Meningocele
- Spina Bifida
- Intervertebral Disc Prolapse
- Tuberculosis of Spine
- Spinal Tumours

HEAD INJURIES

> *Now as soon as thou findest that smash which is in his skull like those corrugations which form on molten copper, (and) something therein throbbing and fluttering under thy fingers like the weak place of an infant's crown before it knits together-when it has happened there is no throbbing and fluttering under thy fingers, until the brain of his (the patient's) skull is rent open- (and) he discharges blood from both his nostrils and both his ears, (and) he suffers stiffness in his neck.*
>
> — **(Anonymous),** circa 2500 BC

Mechanism

1. *Distortion of the brain*: Brain is a soft structure, therefore has a 'mobility' and readily distorts. This distortion and mobility is accentuated by CSF and vascular components. Any impact creates shearing forces in the brain causing damage to neurons, supporting tissues and blood vessels. This leads to loss of consciousness, focal neurological deficits. Such distortive damage may be temporary or permanent.
2. *Mobility of the brain in relation to the skull and membranes* causes cerebral damage and bleeding in dural spaces from torn vessels in the dura, commonly the veins. In old age, the brain shrinks, as a result of which 'mobility' of brain increases favouring rupture of veins which cross the subdural space.
3. *Configuration of interior of skull:* Damage is less severe over the smooth area but is more severe over the rough and sharp areas. So the damage is severe over the anterior cranial fossa, over the falx, and over the tentorium.



Fig. 27.1: Exposed skull after trauma with sepsis. It needs multiple burr holes to allow granulation tissue formation from depth. Later skin grafting can be done. Otherwise local rotation flap is needed.

4. *Deceleration and acceleration injuries: Deceleration injuries* occur when moving head strikes an immovable object (like in road traffic accidents). *Acceleration injuries* occur when stationary skull is struck by a moving object (like in assault).
5. *Cerebral concussion* is slight distortion causing temporary physiological changes leading to transient loss of consciousness with complete recovery.
6. *Cerebral contusion* is more severe degree of damage with bruising and cerebral oedema leading to diffuse or localized changes.

7. *Cerebral laceration* is tearing of brain surface with collection of blood in different spaces and with displacement of dural parts.

Effects of Brain Injuries

1. *Brain oedema* is accumulation of fluid, both intracellular and extracellular. It is due to congestion and dilatation of blood vessels. It may be diffuse or localized.
2. *Brain necrosis* is of severe variety with destruction and is due to haemorrhagic infarction.
3. *Extradural haematoma* occurs usually in temporoparietal region. It is commonly due to tear in middle meningeal veins and often middle meningeal artery. It causes intracranial hypertension, displacement, Kernohan's effect and often death.
4. *Subdural haematoma* is due to tear of veins between cerebrum and dura due to shearing forces. It is diffuse and commonly associated with cerebral injury.
5. *Intracerebral haematoma* can occur in different parts of cerebrum may be in frontal lobe, temporal lobe.
6. *Intraventricular haemorrhage* is very severe type of haemorrhage.
7. *Brain ischaemia* is due to increased pressure. This in turn leads to alteration in the perfusion of brain which itself aggravates the ischaemia and this forms a vicious cycle, causing progressive diffuse ischaemia of brain.
8. *Coup injury* occurs on the side of the blow to the head. *Contre-coup injury* occurs on the side opposite to the blow on the head.
9. *Coning*: It is due to raise in intracranial pressure causing either:
   - i. Herniation of contents of supratentorial compartment through *the tentorial hiatus* or
   - ii. Herniation of the contents of infratentorial compartment through the *foramen magnum.*

In supratentorial herniation, there is compression of ipsilateral third cranial nerve and midbrain. Midbrain is displaced away from the mass (haematoma) and midbrain is pressed by the sharp edge of tentorium cerebelli of opposite side leading to dysfunction of corticospinal fibres (which after decussation supplies the opposite side of the body, i.e. same side of the injury).



Fig. 27.2: Coning with Kernohan's notch.

This leads to:

- a. Deterioration in the level of consciousness.
- b. Dilatation of pupil on the side of compressing mass (haematoma).
- c. Hemiparesis on the same side of the mass lesion (haematoma) due to compression of the contralateral corticospinal tract. This effect is called as ***"Kernohan's notch"***.

  Herniation of infratentorial contents through the foramen magnum causes obstruction of cerebral aqueduct which further damages the brain function.

10. *Respiratory failure* altering PO_2 and PCO_2 levels.
11. *Raised intracranial pressure* causing bradycardia, hypertension, vomiting. Raised intracranial pressure may precipitate coning and thus aggravates brain ischaemia.
12. *Fluid and electrolyte imbalance.*
13. *Hyperpyrexia.*
14. *Convulsions* due to irritation of grey matter.
15. *CSF rhinorrhoea or CSF otorrhoea.*



Figs 27.3A and B: Balck eye in two different patients.

Pathology of Head Injury

Primary lesions	*Secondary lesions*
• Diffuse neuronal damage • Shearing lesions • Contusions • Lacerations	Brain swelling • Oedema, venous congestion, hypoxia Intracranial haemorrhage • Extradural • Subdural • Intracerebral Infections • Open head injury – Generalised meningitis – Subdural empyema • Closed head injury – Pott's puffy tumour
Cerebral concussion	***Cause of death in head injury***
• Temporary physiological paralysis of nervous system • Loss of consciousness • Post-traumatic amnesia • Full recovery is expected • Residual complications may develop	• Brain hypoxia • Coning • Diffuse severe irreversible neuronal injury • Death may be due to other injuries like abdo-minal/thoracic • Metabolic changes • Aspiration in unconscious patient

Other features

- ❖ CSF leak or bleeding from nose
- ❖ Blood collection in the orbit
- ❖ Black eye
- ❖ *Battle's sign*—ecchymosis over the mastoid
- ❖ Haematoma of scalp
- ❖ *Panda sign*—bilateral black eye

Clinical Approach of a Patient with Head Injury

1. Detail history of injury has to be taken and also the process of deterioration—rapid or gradual.
2. History of alcohol intake: Alcohol intake mimics head injury and alcoholism itself may mask the features of head injury.
3. *Neurological assessment*: By

- ❖ Level of consciousness
- ❖ Glasgow coma scale
- ❖ Pupillary reaction to light and size
- ❖ Pulse
- ❖ Temperature
- ❖ Blood pressure
- ❖ Respiratory rate
- ❖ Reflexes
- ❖ Limb movements—normal/mild weakness/ severe weakness/ spastic flexion/extension/no response

4. Status and protection of airway.
5. General assessment and other injuries like fractures, abdominal organ injuries, thoracic injuries are looked for.
6. Presence of any scalp haematoma, fractures of skull bone which may be depressed has to be looked for.
7. Any blood from nose or ear, CSF rhinorrhoea or CSF otorrhoea has to be looked for.

Indications for Hospitalisation

- ❖ Any altered level of consciousness
- ❖ Skull fracture
- ❖ Focal neurological features
- ❖ Persistent headache, vomiting, systolic hypertension, bradycardia
- ❖ Alcohol intoxication
- ❖ Bleeding from ear or nose
- ❖ Associated injuries



Fig. 27.4: Degloving injury scalp. Note all layers of the scalp stripped off.



Fig. 27.5: Patient with head injury having black eye.

Glasgow coma scale

Eye opening		***Verbal response***		***Motor response***	
Spontaneous	–4	Oriented	–5	Obeys commands	–6
To speech	–3	Confused	–4	Localises pain	–5
To pain	–2	Inappropriate words	–3	Flexion to pain	–4
None	–1	Incomprehensible words	–2	Abnormal flexion	–3
		None	–1	Extension to pain	–2
				None	–1

Total score-15
Mild head injury: score 13-15
Moderate head injury: 9-12
Severe head injury: less than 8 (3-8)

Adelaide coma scale

It is used in children

Scores for eye opening and motor responses are same as Glasgow coma scale

But *verbal response score differs*—Oriented-5. Words-4. Vocal sounds-3. Cries-2. Nil-1

Orientation cannot be evaluated below 5 years. For first 6 months, the best verbal response is CRY

Investigations

- X-ray skull: To look for fracture, relative position of the calcified pineal gland, presence of intracranial air.
- Serum electrolyte measurement.
- Blood grouping and cross matching.
- CT scan: Plain (not contrast) to look for cerebral oedema, haematomas, midline shift, fractures, ventricles, brainstem injury.
- Carotid arteriography.



Fig. 27.6: CT scan head showing scalp haematoma on both sides. There is no internal injury.



Fig. 27.7: CT scan head showing intracerebral haematoma.

- Investigations for other injuries like ultrasound of abdomen.
- Monitoring of intracranial pressure.

Treatment

General

- Protection of airway using mouth gag, endotracheal intubation or tracheostomy, whenever required.
- Throat suction, bladder and bowel care and good nursing are very essential.
- Nasal oxygen, or often ventilator support.
- IV fluids initially, later Ryle's tube feeding has to be done.
- Electrolyte maintenance.

Drugs

- Sedation is avoided.
- Analgesics and anticonvulsants like phenytoin or phenobarbitone is started.
- Diuretics are given to reduce cerebral oedema—either mannitol 20%, 200 ml IV 8th hourly or frusemide 40 mg IV 8th hourly. It should not be given in case of intracranial haematoma.

In great attempts, it is glorious even to fail.



Figs 27.8A and B: CT scan head showing sharp head injury causing through and through cut across skull and brain. Patient survived and went home.

- Antibiotics like penicillins, ampicillins are given to prevent the onset of meningitis.
- Corticosteroids, either dexamethasone or betamethasone is used commonly, but its beneficial effect is not confirmed.
  Indications for surgery
  - Acute extradural haematoma.
  - Acute subdural haematoma.
  - Depressed skull fracture.

Procedure

Craniotomy is done and cranial flap is raised. Clot is evacuated followed by applying *hitch stitches* between dural layer and scalp. Postoperative antibiotics, analgesics, anticonvulsants are given.

Complications of Head Injuries

Early

- Brainstem injury—due to coning.
- Compression over cerebellum and medulla.
- ***CSF rhinorrhoea***: Due to communication between intracranial cavity and the nose. There is a tear in the dura following the fracture involving the sinuses—frontal, ethmoid, sphenoid sinuses. Meningitis is the common complication of CSF rhinorrhoea.
  Treatment: Initial management is only conservative, for 10 days—by antibiotics and observations.

Indications for surgical intervention

- Fracture of middle third face
- CSF rhinorrhoea persisting for more than 10 days
- Fracture of sinuses
- An aerocoele
- An attack of meningitis

  Surgeries:
  i. Reduction of fracture of middle third face.
  ii. Exploration of anterior cranial fossa.
- Meningitis—common.
- Pituitary damage and endocrine failure—requires high dose of hydrocortisone 200 mg, 6th hourly.
- Aerocoele.
- CSF otorrhoea.
- Depressed fractures, often causes injury to dural venous sinuses and may lead to torrential haemorrhage, which may be life threatening. So such depressed fractures should never be elevated.



Fig. 27.9: Multiple burr holes done to promote formation of granulation tissue from vascular diploe of the skull. Once granulation tissue covers the entire defect, skin grafting can be placed.

Late

- Chronic subdural haematoma.
- Early post-traumatic epilepsy—they need anticonvulsants for 3 years.

- Late post-traumatic epilepsy is due to scarring and gliosis of cerebrum.
- Post-traumatic amnesia.
- Post-traumatic hydrocephalus.
- Post-traumatic headache.

EXTRADURAL HAEMATOMA

- It is collection of blood in the extradural space between the dura and skull.
- Most common site is *temporoparietal* region. It can *be unilateral or bilateral*

Vessels commonly involved

- Middle meningeal veins
- Anterior branch of middle meningeal artery
- Posterior branch of middle meningeal artery

Usually it is associated with fracture of temporoparietal region.

Pathology

Direct blow, like from cricket ball or road traffic accidents or fall and impact or coup and contre-coup injuries
↓
Fracture of thin temporal bone
↓
Tear of vessels
↓
Bleeding initially outward towards the scalp and under temporalis muscle
↓
Formation of haematoma
↓
Gradual stripping of dura from skull and collection of blood occurs
↓
In 6-12 hours extradural haematoma occurs which raises the intracranial pressure
↓
Coning of supratentorial content (uncus of temporal lobe) through tentorial hiatus
↓
Shift of midbrain towards opposite side which gets injured by sharp edge of the tentorial cerebelli
↓
Corticospinal tract before decussation on opposite side gets injured
↓
So hemiparesis, and pupillary changes occur on the same side of haematoma
↓
This effect is called as ***Kernohan's notch effect***.

- Immediately after injury, there is transient loss of consciousness and the patient soon becomes normal. Later after 6-12 hours, he again falls ill and the condition deteriorates. This is the time taken to develop raised intracranial pressure, coning and its effects. This crucial time gap which is unnoticed and often missed is called as ***"lucid interval".***

Clinical Features

- History of transient loss of consciousness following a H/o blow or fall.
- Patient soon regains consciousness and again after 6-12 hr starts deteriorating ***(Lucid interval)***.
- Later the patient presents with confusion, irritability, drowsiness, hemiparesis on same side of the injury. Initially pupillary constriction and later pupillary dilatation occurs on the same side, finally becomes totally unconscious – *Hutchinsonian pupils*.
- Death can occur if immediate surgical intervention is not done.
- *Features of raised intracranial pressure* like high blood pressure, bradycardia, vomiting is also seen. Occasionally *convulsions* may be present.
- *Wound and haematoma in the temporal region of scalp* may be seen.

Investigations

- X-ray skull may show fracture of temporal bone.
- Electrolyte estimation.
- CT scan head is diagnostic. Extradural haematoma shows *biconvex* lesion.



Fig. 27.10: Extradural haematoma. Note the biconvex configuration of the haematoma.

Treatment

Immediate surgical intervention is a must to save the life of the patient.

Fourth nerve when paralysed causes diplopia when going downstairs (that is on looking downwards).
—**Sir Benjamin W Ryeroft**



Figs 27.11A and B: CT scan head showing extradural haematoma with biconvex lesion.

- Craniotomy is done and cranial flaps are raised. The dura is opened and the clot is evacuated. The dura is fixed to galea using interrupted sutures—*Hitch stitches*.
- Antibiotics and anticonvulsants are given postoperatively.
- Recovery is good after surgery.

Treatment of extradural haematoma

- Earliest surgery and evacuation is the need
- 5 cm vertical incision in parietal region above the zygoma
- Galea is incised. Skull is opened using perforator and burr
- Meninges are kept aside
- *Black currant jelly clot* is evacuated
- Bleeding vessels are cauterized—bipolar cautery
- Dural hitch stitches are placed
- Opposite side if needed should be evacuated
- Antibiotics; anticonvulsants
- Analgesics
- General measures—catheter; fluid therapy
- Prevention post-traumatic complications

Complications

- Post-traumatic epilepsy
- Meningitis
- Post-traumatic amnesia

SUBDURAL HAEMATOMA

Types

- *Acute*
- *Chronic*

Acute Subdural Haematoma

- It is a collection of blood between the brain and dura. It is due to injury to the cortical veins and often due to laceration of cortex of brain which bleeds and blood gets collected in the subdural space forming a haematoma.
- Here haematoma is extensive and diffuse. There is no lucid interval. There is severe primary brain damage.
- Haematoma may be of coup and contre-coup type.
- Loss of consciousness occurs immediately after trauma and is progressive.
- Convulsion is common.
- Features of raised intracranial pressure is obviously seen—high BP, bradycardia, vomiting.
- Focal neurological deficits or hemiparesis can occur.
- CT scan shows concavo-convex lesion.

Treatment

- Antibiotics, anticonvulsants.
- *Surgical decompression is done by craniotomy*.

Chronic Subdural Haematoma

- It is due to the rupture of veins between dura and brain (cerebral hemispheres), causing gradual collection of blood in subdural space.
- It is commonly seen in elderly people following any minor trauma like fall, slipping (which might have gone unnoticed).
- In elderly people, brain atrophies and even minor injuries can cause shearing and bleeding from these veins.
- Blood collects gradually over 2-6 weeks. Plasma and cellular components get separated. Eventually cellular part gets absorbed leaving only fluid component. It is called as ***chronic subdural hygroma.***
- Usual haematoma collection is 60-120 ml. Often in 50% of cases, it is bilateral.

Clinical Features

- Common in old age, with history of minor trauma.
- Patient presents with confusion, disorientation, gradually with altered level of consciousness and drowsiness.
- Later convulsions, features of intracranial hypertension, features of coning develops.
- Extensor plantar response and pupillary changes develop eventually.

Investigations

- CT scan (shows *concavo-convex* lesion).
- Serum electrolytes.
- Blood grouping and cross matching.

Differential Diagnosis

- Electrolyte imbalance.
- Intracranial space occupying lesion.



Fig. 27.12: Subdural haematoma. Note the concavo-convex configuration of the lesion.



Fig. 27.13: CT scan head showing subdural haematoma with concavo-convex lesion.

Treatment

- Craniotomy and evacuation of clot is done when required on both sides.
- Antibiotics.
- Anticonvulsants for 3 years.

Complications

- Epilepsy
- Meningitis
- Coning
- Neurological deficits

Chronic Subdural Empyema

- It may be primary infection of subdural space from sinusitis focus causing suppuration and pus formation.
- It can be complication of the chronic subdural haematoma.
- It is due to secondary bacterial infection of collected clot/fluid.
- Infection is from sinusitis scalp (common)/through earlier trauma wound/Haematogenous.
- Commonly Gram positive organisms cause empyema like streptococci (viridans/milleri) but other virulent organisms like Gram negative bacteria occasionally can cause.
- There is cortical venous thrombophlebitis and cortical infarction.
- Headache, fever, meningism and convulsions are the features.
- MRI is ideal than CT to diagnose.
- *Treatment*: Antibiotics, craniotomy and drainage; anticonvulsants, ICU care, proper monitoring, regular follow up.
- Condition has got 10% mortality.

SUBARACHNOID HAEMORRHAGE (SAH)

> *The Abbot by chance wished to decide with him the fate of the servants, found (him) prostrate upon the ground, insensible to shouts, to shaking and pinching of the body…senseless….I saw him livid from pallor, deprived of all sensation and animate motion….The first hour after midday of the same day he ceased to live…. By the indulgence of the Most Reverend Lord Abbot… I opened the head….Much blood flowed from the space….The (blood) covered (the brain) all over….The ventricles laid open I found them all filled up with blood.*
>
> —**Johann Jakob Wepfer,** 1658

It is a type of intracranial haemorrhage into the subarachnoid space usually from basal cisterns.

It may be spontaneous or following trauma.

Causes

- Intracranial aneurysms—commonest cause (50%)
- Hypertension
- A-V malformations
- Blood dyscrasias
- Anticoagulant drugs
- Brain tumours (malignant)

Two black eyes following one injury indicate fracture of the base of skull.—**Sir Earnest Finch**

Clinical Features

- Sudden onset of severe headache with vomiting.
- Features of raised intracranial pressure.
- Photophobia.
- Neck stiffness.
- Focal neurological deficits: hemiplegia, dysphasia.
- Eye changes: ptosis, dilated pupil, changes in the eyeball movements.
- Sudden loss of consciousness.
- Features of brain oedema and cerebral ischaemia.

In 40% of recovered patients, rebleeding occurs in 6-8 weeks which is commonly fatal.

Hunt and Hess grading for subarachnoid haemorrhage

Grade 1:	Asymptomatic
Grade 2:	Severe headache and neck stiffness
Grade 3:	Drowsy, confused or mild focal deficit
Grade 4:	Stupor, hemiparesis
Grade 5:	Decerebrate rigidity, coma

Fischer grading of SAH

I—minimal < 8 mm size
II—moderate 8-15 mm size
III—severe > 15 mm size

Differential Diagnosis

- Meningitis.
- Coning due to any cause.

Investigations

- Lumbar puncture should be done to differentiate from meningitis.
  It has to be done carefully as it may precipitate coning.
  In subarachnoid haemorrhage, blood stained CSF is collected.



Fig. 27.14: CT scan showing intracerebral brain haemorrhage.

- CT scan.
- Carotid and vertebral angiogram.

Treatment

- Clipping, or wrapping the aneurysm.
- Craniotomy and proceed.
- Ligation of common carotid artery—there is risk of hemiplegia.
- Therapeutic embolisation.
- Excision of vascular malformations.
- Coiling of aneurysm with instruments.

DEPRESSED SKULL FRACTURE

- It is a common neurosurgical problem among the head injuries.
- It means fracture depression is more than the depth of inner table of the skull.

Problems in depressed fracture

- Tear in the dura beneath
- Haematoma in the deeper plane
- Injury to the cerebrum
- Injury to the venous sinuses—may cause life-threatening haemorrhage. *Fracture should not be elevated* in such occasion, as it itself can precipitate bleeding
- Convulsions
- Meningitis

Investigations

- CT scan.



Fig. 27.15: Depressed skull fracture.

Treatment

- Antibiotics, anticonvulsants.
- *Elevation of the depressed fracture*: Burr holes are made in the adjacent normal skull. Fracture is elevated. Bony

fragments and necrotic materials are removed. Dural tear is closed with interrupted sutures.

HYDROCEPHALUS

> *The heads of children sometimes grow enormously large, the sutures give way, and the membranes of the brain are pushed up with the water within, and make a soft tumour rising above the edges of the sutures…. They daily become more and more stupid, with a pulse not above seventy-two.*
>
> —**William Heberden,** 1802

It is dilatation of ventricles due to blockage of cerebrospinal fluid flow (CSF) or due to increased secretion or due to defective absorption of CSF.

Classification I

- **Communicating type:** Ventricles communicate freely into the subarachnoid space.
  Here there is defective absorption of CSF following any inflammation, subarachnoid haemorrhage or trauma.
- **Noncommunicating type**: Obstruction is in the ventricle or its exit, due to any tumours or any inflammatory process.

Clinical Features

Bulging of anterior fontanelle, engorged scalp veins, separation of suture lines, *sun-setting sign* (decreased upward gaze), increasing head circumference, papilloedema, lethargy, ataxia.

Investigations

CT scan, ventriculography, air encephalography, MRI.

Treatment

- Tapping of lateral ventricles.
- Ventriculocysternostomy using polythene catheters—*Torkildsen operation.*
- Ventriculoatrial (VA) shunt.
- Ventriculoperitoneal (VP) shunt.



Figs 27.16A and B: Hydrocephalus child. CT scan head picture in hydrocephalus.

Classification II

Congenital	*Acquired*
Associated with spina-bifida and myelomeningocele. It is due to:	May be unilateral or bilateral (midline obstruction), due to:
• Failure of formation of CSF pathways	• Chronic meningitis
• Arnold-Chiari malformation	• Trauma
• Congenital stenosis of aqueduct of Sylvius	• Subarachnoid haemorrhage
• Presents with widening of sutures, tense fontanelles and decreased cortical thickness • Enlargement of head occurs, either prenatal (can cause obstructed labour) or postnatal	• Brain tumours—(pineal/cerebellar/craniopharyngiomas) • Colloid cyst of 3rd ventricle • Arachnoid cysts

The blessing of health is realised on the sick bed.—**Mr Tut-Tut**

INTRACRANIAL ABSCESS

Types

- ***Extradural abscess***: Caused by:
    - Osteomyelitis of skull.
    - Middle ear infection.
    - Frontal sinusitis.

  Pott's puffy tumour is subperiosteal swelling with infection and inflammation of the scalp. There is acute localized headache and tenderness in the skull, localized pitting oedema of the scalp usually in the frontal region.
- ***Subdural abscess***: is caused by septic thrombophlebitis from the frontal sinusitis or other infections. It is often very severe with extension into the venous sinuses.
- ***Intracerebral abscess***: is caused by
    - Extension from middle ear or sinuses.
    - Blood-born infection.
    - After intracranial injuries.

Common sites: Temporal lobe, cerebellum, frontal lobe.

It can be:

a. *Acute*—There is acute septic encephalitis without pus formation. It may cause ventriculitis or localized abscess formation

b. *Subacute*—Occurs in 3 weeks, by the formation of a glial wall, i.e. thickness is more near the cortex and less towards ventricle

c. *Chronic*—Occurs in 6 weeks with thick wall which may persist or may get enlarged behaving like a space occupying lesion

d. *Metastatic*—Abscess in brain occurs either in cerebrum (parietal or temporal lobes) or in ventricles (Ventriculitis is more dangerous and often fatal)

Clinical Features

- Evidence of focus of infections are seen, i.e. middle ear (CSOM), sinusitis.
- Focal neurological features are seen, depending on the location of abscess. In temporal lobe abscess features of dysphasia, contralateral hemiparesis are seen; in cerebellar abscess, all cerebellar symptoms are seen.
- Epilepsy.
- Features of raised intracranial pressure: (a) slow pulse, (b) rising BP, (c) headache and vomiting, (d) papilloedema, (e) deterioration in level of consciousness, (f) visual disturbances.

Differential Diagnosis

- Intracranial tumour.
- Tuberculoma.
- Meningitis.

Investigations

- CT scan.
- MRI.
- Carotid angiogram.
- Ventriculography.
- EEG.
- Isotope brain scan.
- Total count, ESR.
- Investigation specific for focus of infection.

Lumbar puncture should be avoided in acute abscess as coning can occur.



Fig. 27.17: Intracranial abscess. It needs drainage. It could be tuberculosis. It is a space occupying intracranial lesion, mimics malignancy often.

Treatment

- Antibiotics—high dose penicillins, benzyl penicillins are given.
- Burr hole exploration is done and Dandy's brain cannula is placed. Pus is aspirated and sent for culture and cytology.
- In case of chronic abscess, exploration of cranial cavity and excision of brain abscess is done.

Complications

- Intracranial hypertension
- Coning
- Neurological deficits

INTRACRANIAL ANEURYSMS

Types

- ***Subclinoid type*** occurs in the internal carotid artery within the cavernous sinus. It causes ptosis, defective external ocular movements, 5th nerve palsy. It can cause carotid-cavernous fistula.
- ***Supraclinoid type*** is commonest type.
    - *Berry aneurysms: A congenital type* occurs in circle of Willis in relation to internal carotid artery [40%

(most commonly at the origin of posterior communicating artery)], anterior communicating artery, middle cerebral artery, vertebrobasilar artery. It occurs due to weakness in the media of major arteries.

- *Acquired aneurysms* due to atheromas, hypertension.
- *Mycotic aneurysms* occurs due to infection in the wall of cerebral vessels, as a result of any bacteraemia.

Common sites are peripheral branches of middle cerebral artery.

Presentations

- Subarachnoid haemorrhage
- Pressure effects
- Convulsions
- Eye and pupillary signs

Investigations

- CT scan.
- Carotid and vertebral angiogram.

Treatment

- Clipping or wrapping of aneurysms.
- Therapeutic embolisation.
- Open neurosurgical approaches.

INTRACRANIAL TUMOURS

> *There was discovered on (the corpus callosum) of the brain a remarkable round fleshy tumour like an acorn. It was hard and full of holes and was as large as a medium-sized apple. It was covered with its own membrane and was entwined with veins.... We perceived that this ball by compressing the brain and its ducts with its mass and by flooding them, had been the occasion of the lethargy and listlessness and finally of death.*
>
> —**Felix Platter,** 1614

***Secondaries are the commonest malignant tumour in the brain.** Metastasis occurs usually from lung (commonest), nasopharynx or from any other organ in the body.*

Secondaries in brain

- Commonest malignant brain tumour
- Primary are—lungs (40%), breast (30%), melanoma (15%), others (15%)
- Usually multiple
- Headache, focal lesions, convulsions, hypertension, altered level of consciousness are the features
- CT scan, CT chest or evaluation of primary—needed
- Radiotherapy and chemotherapy of particular primary is treatment
- Solitary metastasis can be removed surgically
- Steroids reduce the cerebral oedema and so symptoms



Fig. 27.18: Orbital secondaries from adrenal neuroblastoma.



Fig. 27.19: CT scan head showing brain secondaries.

Primary Brain Tumours

1. ***Gliomas (43%).***
   a. *Astrocytomas* are the commonest type. They are usually malignant. They can occur anywhere in the cerebral hemispheres, medulla, brainstem. Peak incidence is in 4th decade.

   They can be *diffuse, solid or cystic*. They contain star-shaped cells resembling adult neuroglial cells. Astrocytic

Disease is no absolute physical entity but a complete intellectual construction, an amalgam of biological state and social definitions.
—Charles E Rosenberg

gliomas are graded as *Grades I, II, III, IV based on the quantity of adult and primitive cells*.

Grade I – Cystic
Grade II – Diffuse
Grade III –Anaplastic
Grade IV – **Glioblastoma multiforme** – It is high grade aggressive type of astrocytoma. It is treated by surgical removal / debulking; high dose radiotherapy, chemotherapy with carmustine inserted into the surgical cavity and oral temozolomide. Median survival is 12 months; 2-year survival rate is 25% or less.



Fig. 27.20: CT scan showing astrocytoma – aggressive variety—grade IV—gliobalstoma multiforme.

b. *Oligodendrogliomas*.

c. *Spongioblastoma polare* arises from the primitive spongioblasts, affects optic chiasma, third ventricle, hypothalamus. They are irremovable but are radiosensitive.

d. *Medulloblastoma* occurs in children, affecting vermis of the cerebellum which grows rapidly with seedling elsewhere in the brain.

e. *Ependymomas*: Cells here resemble ependymal cells. It can occur through out the cerebral hemespheres.

2. ***Meningiomas (18%)***: They are usually globular, arising from the arachnoids. Tumour gets attached to the dura. It gets blood supply from dural arteries and veins, from emissary veins and veins of diploe and scalp. Along these veins tumour cells invade the bone, causing bone destruction and reactive hyperostosis.

Meningiomas are *classified as fibroblastic, endothelial and angioblastic*.

Sites

- Parasagittal
- Frontobasal
- Posterior fossa
- Choroid plexus

Microscopic: It contains whorls of spindle cells, with central hyaline material, with *psammoma bodies*.

Meningioma

- 18% common
- Arising from arachnoids
- Gets blood supply from dural vessels
- Invades the skull bone through emissary and diploe veins.
- Destruction and reactive hyperostosis of bone is common
- *Psammoma bodies* are often seen histologically
- CT/MRI diagnostic
- Surgery is the choice therapy
- It has got good prognosis

3. ***Schwannoma (8%)***: Common in auditory nerve, also called as *acoustic neuroma*.

Occurs in the internal auditory meatus which projects into the cerebellopontine angle (C- P angle), compressing 5, 6, 7, 8th nerves. It presents with compressive features like unilateral deafness, trigeminal neuralgia, squint, cerebellar compression syndrome.

4. ***Pituitary tumours (12%)***.
5. ***Craniopharyngiomas (5%)***.
6. ***Blood vessel tumours (2%)***.

Clinical Features

- Initial period of silent growth.
- Focal syndromes with epilepsy.
- Raised intracranial pressure with headache, vomiting, deterioration of level of consciousness, altered vision, slow pulse, high BP, papilloedema.
- Brain displacement and stage of coning.

Note:
First sign in acoustic neuroma is loss of corneal reflex.

Specific Features

- Frontal lobe tumours: Personality and emotional changes, epilepsy of generalised type, contralateral facial weakness.
- Parietal lobe tumours: Jacksonian epilepsy, progressive hemiparesis, astereognosis, acalculia.
- Occipital lobe tumours: Aura of flashing of light in contralateral field, homonymous hemianopia.
- Temporal lobe tumours: Progressive aphasia, visual, auditory, smell and taste hallucinations, hemiparesis, superior quandrantic hemianopia.
- Midline tumours: Produces bilateral hydrocephalus.
- Tumours of the third ventricle (colloid cyst is common): Causes bilateral hydrocephalus, progressive cerebral atrophy, dementia, sexual precocity, endocrine disturbances.
- Pineal tumours: Causes precocious puberty.
- Cerebellar vermis tumours: Usually medulloblastomas, occur in young children, presents with progressive hydrocephalus and features of herniation of cerebellar tonsils through foramen magnum.
- Cerebellar hemisphere tumours: Commonly are astrocytomas, produce cerebellar syndromes, nystagmus.



Fig. 27.21: CT scan head showing large meningioma frontal region.



Figs 27.22A and B: MRI brain showing glioma brain.



Fig. 27.23: MRI brain showing glioblastoma multiforme. It is very aggressive malignant tumour.



Fig. 27.24: Skull X-ray showing mass calcified lesion. It could be meningioma, dermoid extending intracranially.

Investigations

- X-ray skull.
    - Calcifications like in meningiomas, craniopharyngiomas.
    - Separation of sutures.
    - A beaten silver appearance.
    - Lateral displacement of pineal body.
    - Hyperostosis, expansion, destruction in skull bones.
- Isotope scan.
- CT scan.
- MRI.

A very bold surgeon is the one who realise that, his patient takes all the risks.

- Positron Emission Tomography (PET).
- Carotid angiogram (Introduced by Egas Moniz).
- Ventriculography.
- EEG.



Figs 27.25A and B: Craniopharyngioma from sellar region.

Treatment

- Relief of raised intracranial pressure:
  a. Ventricular tap and drainage through a posterior parietal burr hole.
  b. Tapping of cystic tumours and abscesses.
  c. Administration of mannitol.
  d. Emergency decompression by partial removal of tumour.
  e. Steroid therapy—dexamethasone.
- Establishment of pathological diagnosis:
  a. Burr-hole and biopsy.
  b. Craniotomy and biopsy using brain cannula.
  c. Frozen section biopsy.
  d. CT guided stereotactic biopsy.
- Removal of benign tumours—by different craniotomy approaches.
- Decompressive surgeries for malignant tumours.
- Shunt surgeries to drain CSF—ventriculoperitoneal shunt or ventriculoatrial shunt.
- Radiotherapy—external radiotherapy is used as primary treatment or as an adjuvant therapy after surgery.
- Chemotherapy is occasionally used.

Prognosis

Tumour which is benign and surgically accessible has better prognosis.

PITUITARY TUMOURS

> *A young student…suddenly (sleepy and lethargic) died in convulsions within two weeks. In his brain the ventricles were found swollen with blood… which had gone down to the base of the skull…. The olfactory bulbs were not swollen at all. The pituitary gland…was completely blocked by a…viscous and gelatinous mass about the size of a small bean… Hence a dropsy of the brain ensued.*
>
> —**Richard Lower,** 1672

Classifications I

1. ***Eosinophil (Acidophil) adenomas***: Tumour is usually small. Rarely it causes compressive features.

   It secretes excess growth hormone causing acromegaly in adults and gigantism in children.
2. ***Chromophobe adenomas*** are common in females and in the age group—20-50 years.

   Initially it is *intrasellar* and after sometime becomes *suprasellar*. Later, it extends *intracranially* often massively, causing features of intracranial space occupying lesion. It presents with myxoedema, amenorrhoea, infertility, headache, visual disturbances, bitemporal hemianopia, blindness, intracranial hypertension, epilepsy.

   Differential diagnosis: Meningiomas, aneurysms.

   CT scan, angiogram, X-ray skull are diagnostic.

   Treatment is surgical decompression by craniotomy through subfrontal approach or transsphenoidal approach. Deep external radiotherapy and steroids are also used.
3. ***Basophil adenomas*** are usually small. They secrete ACTH and presents as Cushing's disease with all its features.
4. ***Prolactin-secreting adenomas*** causes infertility, amenorrhoea and galactorrhoea.



Figs 27.26A and B: Acromegaly due to pituitary tumours. Note the operated scar in the frontal region.

Classification II

- Hypersecreting
- Hyposecreting by compression and atrophy

Classification III

- Micronodular: Tumour size less than 10 mm
- Macronodular: Tumour size more than 10 mm

Stages

- Stage of intrasellar development
- Stage of suprasellar extension
- Stage of massive intracranial extension

Investigations

- X-ray skull—shows calcifications, destruction of sella turcica, mass lesion, enlarged pituitary fossa.
- CT scan.
- MRI.
- Hormone assay—like serum prolactin, growth hormone, ACTH, steroids, sex hormones, etc.

Treatment

- Surgery: By subfrontal craniotomy approach or transphenoidal approach.

  Care should be taken not to injure optic chiasma, arteries, cavernous sinus.
- External radiotherapy.

CRANIOPHARYNGIOMAS

They are large masses with cystic cavities, lined by ciliated epithelium containing cholesterol crystals. Areas of calcifications may be present and coral-like masses may be formed. They are adherent to the basal arteries and adjacent nerves. They are *irremovable.* They are tumours of sellar region.

Clinical Features

- *Intrasellar craniopharyngiomas* inhibits sexual maturation causing obese, impotent dwarf with bitemporal hemianopia (due to compression of optic chiasma)—***Frolich's syndrome.***
- *Suprasellar craniopharyngiomas* produces Frolich's syndrome; pressure on hypothalamus which controls sleep and water metabolism (causes somnolence and diabetes insipidus).
- *Massive intracranial extension* causes intracranial hypertension and also hydrocephalus by obstructing CSF flow.

Investigations

- Skull X-ray shows calcification.
- CT scan is diagnostic.

Treatment

- Through craniotomy or through transsphenoidal approach cystic tumours are evacuated.
- Ventriculoatrial shunt has to be done to drain CSF in case of hydrocephalus.
- Ventriculocisternostomy—*Torkildsen's operation is done in cases of large masses blocking the 3rd ventricle obstructing the CSF outflow.*
- Radiotherapy.

SPINAL DYSRAPHISM

It is posterior midline congenital deformity of spine due to incomplete fusion of ectodermal, mesodermal or neuroectodermal elements either singly or in combination. It is due to arrest of closure of neural tube.

Truth always exists; only lies are invented.

Types

Myelocele

There is failure of closure of neural as well as vertebral arch. There is raw oval defect uncovered over central canal which is incompatible with life and newborn infant dies soon. Loss of lower limb power, incontinence of urine, talipes, CSF discharge, and meningitis is common. Very occasional infant who survives develop a skin coverage from periphery but neurological problems are irreversible. It is common but least survival chance.

Syringomyelocele

It is rarest type. Central canal of spinal cord is dilated with bulging out of the canal under the skin of the dilated centrtal canal as thin cystic sac containing cord with meninges and nerve roots. Gross paralysis is common. It is identified on table as it is difficult to differentiate from myelomeningocele clinically.

Myelomeningocele

It occurs 2 in 1000 live births. Here part of the cord or cauda equina or both present as median cystic swelling at back. It is not transilluminant. It is common in lumbosacral region. Adhesion of spinal cord or cauda equina to sac causes neurological deficit. Kinking, compromised blood supply causes neurological deficit (30%). Monoplegia, paraparesis, paraplegia, talipes and incontinence are the features. It is almost always associated with Arnold Chiari syndrome or Dandy Walker syndrome (atresia of foramina Lushka and Magendie).

Meningocele

Protrusion of spinal meninges through a congenital defect in the spinal laminar defect.

Spina Bifida

Neural arches failure to unite over a limited area and externally there is no protrusion but there is obvious defect.

MENINGOCELE

It is the herniation of meninges through a weak point of spine where bony fusion has not taken place effectively.

Swelling is covered with pia mater and arachnoid mater without dural covering and contains CSF.

Clinical Features

- Present since birth.
- Soft, cystic, fluctuant with transillumination.
- Signs of compressibility.
- Expansile impulse when asked to cough or when child cries.

Location

- Lumbosacral—commonest.
- Occipitocervical—2nd most common.

Investigations

- CT scan head to look for hydrocephalus.
- MRI spine.

Treatment

Excision as early as possible. Transverse elliptical incision. Closure of defect by plication. Approximation of muscles.

Early closure prevents infection.

Complications

- Ulceration.
- Haemorrhage.
- Closure may cause hydrocephalus which needs shunting of CSF.

Meningocele	*Meningomyelocele*
• Membranes content • Soft, cystic • Brilliantly transilluminant • Longitudinal furrow absent • No neurological defect • Good prognosis after repair	• Membranes with nerve roots • Soft to firm • Nontransilluminant • Longitudinal furrow is seen due to adherence of nerve roots • Trophic ulcer, bowel/ urine incontinence, motor problems • Neurological deficit present • Not good results

SPINA BIFIDA

- It is also classified under *spinal dysraphism*.
- It is failure of enfolding of nerve elements within the spinal canal during developmental period.
- It is usually seen in lumbosacral region. There is failure of fusion of one or more posterior vertebral arches.
- It is often associated with other anomalies.

Sites

- ❖ Lumbosacral
- ❖ Thoracolumbar

Types

a. ***Spina bifida occulta***—commonest type
  - There is dimpling of skin with dermoids, lipomas in the site. Impulse on coughing can be seen.

  - Initially there is no neurological deficit but later due to tethering, traction on dura, infection, can lead neurological deficits.

b. ***Spina bifida aperta***
  - Here neurological deficit is present. It may be *myelomeningocele* wherein spinal cord and nerve roots are in the sac. It may be *meningocele* wherein sac consists of meninges and fluid only.
  - Meningocoele is brilliantly transilluminant. Myelomeningocoele is not transilluminant.

Clinical features

- ❖ Motor paralysis
- ❖ Sensory paralysis
- ❖ Visceral paralysis with incontinence of urine and faeces
- ❖ Swelling in the spine at the site of the lesion, may be lipoma or dermoid, with impulse on coughing
- ❖ Bony defect at the site
- ❖ Hydrocephalus



Fig. 27.27: Spina bifida occulta. Note the dimple and tuft of hair.



Fig. 27.28A



Fig. 27.28B

Figs 27.28A and B: Spina bifida with protruding dermoid through the defect.

Investigations

- ♦ Plain X-ray of the spine.
- ♦ CT scan/MRI of spine and head.

Treatment

- ♦ Correction of deformity.
- ♦ Maintaining the visceral function.
- ♦ Development of limb function.
- ♦ Ventriculoperitoneal shunt or ventriculoatrial shunt surgery for hydrocephalus.



Fig. 27.29: Infant with encephalocele. It is non-transilluminant whereas meningocele is brilliantly transilluminant.

INTERVERTEBRAL DISC PROLAPSE (IVDP)

- ♦ Herniation of part of the gelatinous nucleus pulposus through a rent in the annulus fibrosus, commonly at posterolateral part which is a weak point.

The first sign of Pott's disease is deepened midline spinal sulcus at about T10 level due to increased muscular tonicity of sacrospinalis muscle. It is a NATURE'S PLASTER CAST. —**Francis E Jardine**

- ***In cervical spine*** discs between C_5 and C_6; C_6 and C_7 are commonly affected impinging 6th and 7th nerves respectively.
- ***In lumbosacral region,*** discs between L_5 and S_1; L_4 and L_5 are commonly affected impinging first sacral nerve and 5th lumbar nerve respectively.
- Initially protrusion bulges through the pain sensitive posterior longitudinal ligament causing back pain.
- Later it herniates through the posterior ligament compressing the nerve causing typical root pain.

Types

- Posterolateral is common.
- Central-posterior is not common. It is due to trauma. It is severe type, even though rare.

Secondary changes: Osteoarthritis of joints.


Intervertebral disc prolapse
Vertebra with nucleus pulposus and annulus fibrosis

Fig. 27.30: Intervertebral disc prolapse.

Clinical Features

- Pain in the distribution of the root which gets aggravated by straining, coughing, twisting, stooping.
- Pain radiates along the distribution of the nerve with tingling and numbness.
- Lumbar scoliosis is significant.
- Restricted forward flexion but free lateral flexion.
- Positive straight leg raising on the affected side with positive Lasegue's manoeuvre.
- Wasting in the muscles with blunting of sensation, with absence knee and ankle jerks.
- Loss of bladder sensibility and retention of urine.



Fig. 27.31: Intervertebral disc prolapse.

Differential Diagnosis

- Spinal cord tumours.
- Tuberculosis of the spine.
- Osteoarthritis.
- Ankylosing spondylitis.
- Spondylolisthesis.
- Vascular problems.
- Retroperitoneal and pelvic tumours.

Investigations

- X-ray spine both AP and lateral. It is not useful in acute prolapse.
- Myelography or Radiculography.
- CT scan.
- MRI is very useful method.

Treatment

- Rest in bed.
- Spinal jacket.
- Continuous or intermittent traction.
- Analgesics and relaxants.
- Intradiscal injection of the chymopapain enzyme which dissolves the fibrocartilaginous tissue and nucleus pulposus.
- Surgical treatment:

  Indications:
  - Persistent pain for 12 weeks which is not relieved by drugs.
  - Severe neurological disturbances like involvement of bladder, bowel or sexual functions.

  Surgery: Discectomy.



Fig. 27.32: Compression fracture spine—traumatic, pathological.

TUBERCULOSIS OF SPINE (CARIES SPINE)

- It is commonly of *secondary* type.
- Primary focus is in the lungs or lymph nodes.

- Commonly involved vertebra is dorsilumbar vertebra T_{10}.

Mode of infection: Mainly haematogenous.



Fig. 27.33: Tuberculosis of spine.

A. Tuberculosis of Cervical Vertebra

Common in C_6 and C_7 vertebra.

Clinical Features

- Pain in the neck, often referred to occipital region through suboccipital or posterior auricular nerves.
- Pain, when referred through anterior cervical primary rami causes *brachial neuralgia.*
- Rigidity in the neck.
- Patient supports the chin on the palm of his hand (*Rust sign*).
- Tenderness and paraspinal spasm with rigidity of the skull muscles.
- All passive and active movements of spine are painful and restricted.
- Cold abscess may be present in the neck, posterior to sternomastoid muscle or in the retropharyngeal region or in the axilla.
- Chronic tuberculous retropharyngeal abscess in midline, situated behind the prevertebral fascia. It is painless, soft, often causing dysphagia and dyspnoea.

Differential diagnosis

- Cervical spondylosis
- Congenital torticollis
- Secondaries
- Spinal cord tumours

Investigations

- X-ray cervical spine, chest X-ray.
- MRI is ideal.

Treatment

- Antitubercular drugs.
- Anterolateral decompression of vertebra.
- Drainage of cold abscess.

B. Tuberculosis of Thoracolumbar Vertebra (Pott's Disease, Caries Dorsilumbar Spine)

Commonest site is dorsilumbar region —T_{10}.

Reasons

- It is the junction of fixed (thoracic) and mobile (lumbar) segments of spine
- It bears the maximum stress
- It has got large amount of cancellous bone
- Bulky nucleus pulposus
- Relative avascularity of the body of dorsilumbar vertebra
- Close proximity to the thoracic duct through which infection can occur
- Adjacent prevertebral veins

Types

- ***Tuberculosis of the body of vertebra***
  - *Tuberculous metaphysitis*—Here contiguous surfaces of the vertebra are involved. It is the most common type in children.
  - *Tuberculous osteomyelitis* (central type—through central artery of the vertebra)—It occurs in the centre of the body of vertebra.
  - *Tuberculous periostitis* (peripheral or periosteal) — It is seen in adults. It is situated deep to the anterior longitudinal ligament.



Fig. 27.34: Tuberculosis of spine. Note the area of involvement.

- ***Tuberculosis of the appendages***
  - Spinous process.
  - Pedicle.
  - Transverse process.
  - Lamina.

Features

- Contiguous surfaces of paired vertebra are involved.
- Lower half of one vertebra and upper half of adjacent vertebra below, with intervertebral joints are involved as they share a common blood supply.
- Destruction of the vertebra and intervertebral disc; collection of caseous material behind the anterior longitudinal ligament.

Pathology

- Tuberculous endarteritis
- Decreased blood supply
- Formation of tubercles with caseation
- Destruction of bone
- Failure of subperiosteal new bone formation

Effects

1. Deformity—*Kyphosis (Gibbus*) is excessive posterior curvature of the spine. It is due to complete anterior collapse of the vertebra.
2. *Cold abscess* formation:
   a. Close to the midline, when caseating material passes through the medial dorsal cutaneous nerves.
   b. Away from the midline, when caseating material passes through the lateral cutaneous nerve.
   c. Cold abscess may form in relation to psoas muscle (in dorsilumbar or lumbar).

   It passes through psoas sheath. It causes psoas spasm causing flexion of hip with inability to extend. If abscess extends below the inguinal ligament, then it is cross-fluctuant.
3. Spinal cord involvement—causes *paraplegia* (10%). This is common in thoracic spine, as the spine is narrow.
   a. *Early paraplegia ('Paraplegia in flexion', 'paraplegia with active disease'*).
   It is due to:
     - Pressure by caseating material, granulation tissue and sequestrum.
     - Tuberculous meningitis.
     - Spinal cord oedema.
     - Endarteritis of segmental spinal artery.
     - Pressure from distended disc.

   b. *Late paraplegia* ('*Paraplegia with a healed disease', 'paraplegia with extension').*
   It is due to:
     - 'Gibbus' causing stretching of the spinal cord.
     - Longitudinal shrinkage of the spinal cord due to gliosis.

Clinical Features

- Pain in the back, often with tingling sensation along the distribution of nerve roots.
- In upper thoracic tuberculosis, typical '*military attitude'* with raised shoulder which is drawn backwards is seen.
- Kyphosis (*gibbus)* is the commonest deformity. It can be angular but also can be rounded.
- Tenderness in the spine with paraspinal spasm.
- All active and passive movements of spine are restricted.
- '*Coin test'*—inability to pick up a coin is positive.
- Weakness and decreased power in the limb muscles, with altered sensation.

Investigations

- X-ray spine shows:
  - Narrowing of the disc space.
  - Wedging of the vertebra.
  - Rarefaction of the adjacent vertebra.
  - Soft tissue shadow of cold abscess.
- Chest X-ray PA view.
- ESR.
- Radioisotope bone scan.
- CT scan or MRI of spine.



Figs 27.35A and B: Typical tuberculosis of spine involving L4 and L5 spine X-ray features.

Differential Diagnosis

- Secondaries in the spine.
- Spinal tumours.
- Scheuermann's disease (osteochondritis).
- Old compression fracture of the vertebra.
- Ankylosing spondylitis.

Complications of Pott's spine

- Kyphosis
- Cold abscess
- Paraplegia
- Sinus formation
- Dissemination

Treatment

- Antituberculous drugs for one year.
- Rest with plaster jacket (SPICA).

Patient gains weight, X-ray shows re-calcification and healing. ESR becomes normal. Pain and spasm disappears.

Indication for surgery

- When the disease is progressive
- When there is neurological manifestation
- Cold abscess formation

Surgeries

Note:

No posterior approach, no laminectomy for TB spine.

- Anterolateral approach and costotransversectomy with removal of all caseating material with bone grafting.
- Drainage of cold abscess.
- Posterior spinal fusion using bone graft. Bone graft is taken from the iliac crest.

SPINAL TUMOURS

Classification

A. ***Extradural tumours***
- Commonest is secondaries.
    - They lie between the dura, bone and ligamentum flavum.
    - Primary sites are bronchus, breast, prostate, kidney. Rare extradural tumours are sarcomas, osteoclastoma, chondroma, lipoma.



Fig. 27.36: MRI spinal cord showing spinal cord tumour—ependymoma.

B. ***Intradural tumours***

1. *Extramedullary* (75% of intradural)
    - Neurofibromas are the commonest, more common in males.
        - Arises from the posterior nerve root. It can be *'dumb-bell'* tumours.
    - Spinal meningiomas are seen exclusively in females.
2. *Intramedullary* (25% of intradural)
    - Commonest is diffuse gliomas (50%).Others are ependymomas, vascular malformations.
    - Common in cervical cord.

Clinical Features

- Weakness of limbs, often with paraplegia.
- Tingling and numbness.
- Disturbance in micturition.
- Changes in tendon reflexes.
- Pain in the back.

Spinal cord or cauda equina compression is a surgical emergency.

Investigations

- X-ray shows widening of space and destruction.
- Myelography.
- Lumbar puncture *per se* has no role, as it is dangerous.
- CSF below the block may be yellow and proteinaceous and is called as '*Frolin's syndrome'.*
- Protein levels in lumbar CSF is usually raised in the presence of lumbar tumours, commonly 'Schwannomas'.
- CT scan.
- MRI.

Surgery

- Surgery is the main treatment—*Decompression of spinal cord and removal of tumour* by doing laminectomy.
- Adjuvant therapy: Radiotherapy and chemotherapy.
- Intrathecal methotrexate is also beneficial.

> *No head injury is so slight that it should be neglected, or so severe that life should be despaired of.*
>
> **—Hippocrates, Father of Medicine**

Chapter 28 Thorax

CHAPTER OUTLINE

- Chest Injuries
- Fracture Ribs
- Flail Chest and Stove in Chest
- Pneumothorax
- Tension Pneumothorax
- Haemothorax
- Pleural Tap
- Bronchoscopy
- Empyema Thoracis
- Empyema Necessitans
- Lung Abscess
- Intercostal Tube Drainage
- Shock Lung
- Pulmonary Embolism
- Surgical Emphysema
- Lung Cysts
- Mediastinal Tumours
- Thymomas
- Pancoast Tumours
- Chest Wall Tumours
- Pericarditis
  - Acute Pericarditis
  - Chronic Constrictive Pericarditis
- Pericardial Tap
- Cardiac Tamponade
- Diaphragmatic Hernia
- Pulmonary Complications during Postoperative Period
- Surgical Management of Pulmonary Tuberculosis
- Video Assisted Thoracoscopic Surgery

CHEST INJURIES

Types

- Crush injuries involving lung, pleura, ribs.
- Single rib fracture.
- Two or more rib fractures.
- *Steering wheel injury*—causes multiple rib fractures, bilaterally often with flail chest, with fracture dislocation of upper end of sternum.
- Stove in chest or flail chest.
- Traumatic pneumothorax.
- Haemothorax, haemopneumothorax, with fracture ribs.
- Tension pneumothorax.
- Pericardial, cardiac injuries and rupture of bronchus.
- Associated injuries in liver, spleen, diaphragm, major vessels.

Causes

- Road traffic accidents.
- Industrial accidents.
- Blast injuries.
- Crush injuries.
- Stab injuries.

  - In children, ribs are malleable and so fracture ribs are rare.
  - In elderly because of rigid ribs fracture is common.
  - First and second ribs are protected by clavicle and so their fracture is uncommon.
  - 11th and 12th ribs are floating ribs and so their fracture is rare.

Classification of Chest Injuries

As per the *American College of Surgeons Committee on Trauma* chest injuries are classified as:

1. Immediately life-threatening injuries.
2. Potentially life-threatening injuries.

Immediately life-threatening injuries	***Potentially life-threatening injuries***
• Airway obstruction	• Tracheobronchial disruption
• Tension pneumothorax	• Aortic disruption
• Open pneumothorax	• Diaphragmatic disruption
• Massive pneumothorax	• Esophageal disruption
• Cardiac tamponade	• Cardiac contusion
• Flial chest	• Pulmonary contusion

Pathological Effects of Chest Injuries

Immediate	*Late*
Hypoxia	Empyema, fibrothorax
Hypercarbia	Lung abscess
Acidosis	Mediastinitis
Hypovolemic shock	Cardiac arrhythmias
Bronchospasm	

Clinical Features of Thoracic Injuries

- History of trauma, painful breathing, cough, haemoptysis, pain in the chest wall, sometimes external wound may be present (in communicating wounds).
- Features of shock when major vessels are involved, i.e. tachycardia, hypotension, cold periphery.
- Respiratory distress—tachypnoea, cyanosis, respiratory difficulties.
- Tenderness over the fracture site.
- Dullness on percussion with decreased breath sounds signifies haemothorax. Resonant with decreased breath sound confirms pneumothorax.
- Surgical emphysema with palpable crepitus may be present.

Investigations

- Chest X-ray shows haemothorax, pneumothorax, fracture ribs.
- Hb%, PCV to assess blood loss.
- Blood grouping and cross matching.
- Blood gas analysis, i.e. PO_2 and PCO_2.
- U/S abdomen to look for associated abdominal injuries. FAST (Focused abdominal sonar trauma).
- CT chest and CT abdomen.

Treatment

Initial First Aid

- *Airway:* Prevention of aspiration, plastic airway, intubation, tracheostomy.
- *Breathing*: ICT placement, supportive measures.
- *Circulation:* Fluid therapy, CVP line, blood transfusion.
- Look for disability.
- Expose the patient properly for proper breathing and assisting.
- Assess the patient properly.
- Examine the patient thoroughly.
- Evaluate the patient for associated injuries like of head, abdomen, fracture limbs, spine.

Further Treatment

- Fracture rib without complication is treated with analgesics and rest.
- Haemothorax, pneumothorax should be treated with ***intercostal tube drainage*** (ICT) with underwater seal.
- Flail segment should be treated accordingly.
- Blood transfusion is done whenever required.
- Antibiotics like penicillin, cefotaxime, etc. to prevent infection.
- Nasal oxygen, throat suction.
- Ventilator support with IPPV (Intermittent positive pressure ventilation), with regular monitoring of blood gas.
- Tracheostomy/endotracheal intubation is done whenever required.
- Antibiotics, bronchodilators, often steroids are other supportive measures required.

Indications for thoracotomy

- Haemothorax more than 1500 ml found when ICT is placed or hourly collection in ICT is 200-300 ml
- ICT placed shows persistent drainage of blood
- Diaphragmatic injury
- When associated with liver and spleen injuries
- Bronchus and major vessel injuries
- Haemopericardium
- Oesophageal and thoracic duct injuries

Principles of Management of Chest Injuries

- Pulmonary physiotherapy.
- Aspiration of secretions—trachea, nasotracheal, oral, pharyngeal.
- Pain relief—oral narcotics, intercostal nerve block, epidural anaesthesia.
- Respiratory supports—encourage coughing, chest percussion, deep inspiration efforts, humidification, mobilisation.
- ICT placement for haemo/pneumothorax.
- Management of shock.
- Focused abdominal sonography on trauma (FAST).
- Surgery when indicated—thoracotomy and proceed.
- Management of complications—DVT and embolism, tracheostomy problems, ICT problems, sepsis, ARDS, empyema treatment, bronchopleural fistula, bronchial stenosis, chylothorax, clotted haemothorax, atelectasis.

Complications

- Infections—empyema, lung abscess, pneumonia, septicaemia.
- Respiratory failure.
- Traumatic asphyxia.
- Traumatic shock lung.
- Disseminated intravascular coagulation (DIC).
- ARDS (Adult respiratory distress syndrome).

FRACTURE RIBS

- Rib fractures are rare in children as ribs are malleable.
- Fracture ribs are common in elderly as ribs are rigid and nonmalleable.
- 1st and 2nd ribs are covered by clavicle and so rarely fractures.
- Floating 11th and 12th ribs rarely get fractured.

There are no disease of aged but diseases among the aged.—**Leonard Larson**

Causes for Fracture Ribs

- Road accidents, chest injuries.
- Direct trauma.
- Blast injuries.

Features of Rib Fracture

- Difficulty and pain during breathing.
- Tenderness over fracture site.
- Spring test is positive.
- Propped up position is more comfortable than lying down.
- Features of haemothorax, lung injuries.
- Features of abdominal injuries like of liver and spleen injuries.

Problems in Fracture Ribs

- Surgical emphysema.
- Haemothorax, pneumothorax.
- Cardiac and or major vessel injury.
- Diaphragmatic injury.
- Flail chest.
- Asphyxia, cyanosis, respiratory failure.
- Pneumonia.

Investigations

- Chest X-ray is diagnostic.
- CT chest or abdomen to check deep or solid organ injury.
- Arterial blood gas analysis.

Treatment

- Control of pain.
- Prevention of infection.
- Respiratory physiotherapy.
- Treatment for definitive conditions like flail chest, ICT placing for haemo/pneumothorax.

Non-traumatic rib fracture

- Stress fracture
- Metastatic fracture
- Metabolic cause like hyperparathyroidism
- Osteogenesis imperfecta
- Child abuse
- Old age—osteoporosis

FLAIL CHEST AND STOVE IN CHEST

- It is fracture *of two or more consecutive ribs,* with each rib having *two or more* fracture sites. Such segment is called as ***flail segment.***
- **Stove in chest** is depression of a portion of chest wall due to severe chest injury, otherwise features and management are like flail chest.

Pathophysiology

Flail segment moves independent of the adjacent thoracic cage. During inspiration flail segment moves inwards (unlike normal thoracic cage which moves outward), and during expiration the segment moves outwards (unlike normal cage which moves inward) causing pathophysiological derangements.

- This *paradoxical respiration* causes reduction in ventilatory lung surface and so respiratory dysfunction.
- *Mediastinal flutter*: Movement of mediastinum during different phases of respiration occurs, often causing kinking of great vessels and sudden cardiac arrest.
- *Pendular movement of air* from one lung to other occurs, and thus preventing atmospheric air to get into both injured and otherside normal lung leading to respiratory failure.
- All these derangements gets aggravated by *haemothorax, pneumothorax* and other associated injuries.
- There is *hypoventilation:* carbon dioxide retention and respiratory failure.

Flail chest

Derangements	***Types***	***Problems***
• Paradoxical respiration • Mediastinal flutter • Pendular movement of air • Pulmonary contusion	• Anterior—near costochondral junction • Lateral—in rib shafts • Posterior—safer, due to support of scapula	• Cardiac arrest • Respiratory failure • Haemothorax • Infection • ARDS

First Aid

The paradoxical movement of flail segment is prevented by applying pressure over it using hand or clothes (It is often life saving.) It makes other lung function adequately.

Investigations

- Chest X-ray—to identify the fracture segment.
- Blood grouping.
- Arterial PO_2 and PCO_2 and serum electrolytes.

Treatment

- Intercostal tube drainage.
- Applying clips to fracture ribs and fixing above and below to normal ribs.
- Antibiotics like penicillins, cefotaxime.
- Blood transfusion, IV fluids.
- Bronchodilators, steroids.
- Ventilator support with IPPV—IPPV is treatment of choice. Assisted ventilation is required for several days until the chest wall stabilises. If ventilator support is required for more than 10 days, then tracheostomy is done to prevent laryngeal stenosis which can occur due to prolonged endotracheal intubation.
- Thoracotomy—when required only.

PNEUMOTHORAX

> *The means we possess of reducing (a diseased lung) to a state of collapse, or of divesting it for a time of its peculiar functions, are equally simple and safe. In those cases in which the disease is placed in one of the lungs only, the remedy (i.e. induced pneumothorax) would appear to be simple, safe, and complete*
>
> —**James Carson,** 1820

It is the presence of air between the layers of pleura.

Classification I

a. Pneumothorax.
b. Hydropneumothorax.
c. Pyopneumothorax.
d. Haemopneumothorax.
e. Artificial pneumothorax.
f. Tension pneumothorax.

Classification II

a. Open pneumothorax
b. Closed pneumothorax
  - Simple
  - Tension

Causes

- Traumatic.
- Spontaneous.
  1. Tuberculous.
  2. Non-tuberculous:
     a. Rupture of emphysematous bullae.
     b. Rupture of solitary lung cyst.
     c. Honeycomb or cystic lung.
     d. Idiopathic.

Spontaneous pneumothorax can be acute, chronic, recurrent.



Fig. 28.1: Plain X-ray chest PA-view showing air-fluid level and collapsed lung margin (Hydropneumothorax)

Clinical Features

Hyperresonant, absence of breath sounds, tracheal deviation.

Chest X-ray reveals

- Radiolucency on the affected side
- Absence of lung markings
- Collapsed lung margin

Treatment

- In tension pneumothorax, emergency needle aspiration is done followed by ICT placement.
- ICT placement.
- The cause is treated.
- Often thoracotomy is required, if there is persistent broncho-pleural fistula or ruptured cyst or bullae.

TENSION PNEUMOTHORAX

- During inspiration, air is pumped into the pleural cavity through a valvular opening in the visceral pleura and underlying injured lung.
- Lung collapses first, and as air continuously collects in the pleural cavity, mediastinum shifts towards the opposite side, further decreasing the volume of the functioning lung.
- Further increase in the pleural pressure, reduces the venous return, atrial filling, and ventricular filling and so cardiac output and cardiac function.



Fig. 28.2: Emergency decompression through 2nd intercostal space.

It causes sudden death and hence emergency treatment is required.

Clinical features

- Tachypnoea and tachycardia
- Decreased/absent breath sounds
- Resonant on percussion with severe mediastinal/tracheal shift
- Cyanosis and hypotension
- Chest pain

Experience teaches slowly at the cost of mistake.

Management

- *Once clinically diagnosed, a wide bore needle is immediately placed in the second intercostal space in midclavicular line*, and a sterile glove is kept on the hub (blunt) end of the needle to create a valve so as to prevent inward sucking of air from outside.
- Nasal oxygen is used.
- Once patient is better, chest X-ray is done.
- Later an intercostal tube is passed.
- Antibiotic, analgesics are given.
- In severe cases ventilator support with IPPV is required.

HAEMOTHORAX

It is blood in pleural cavity. It causes pain, shock, as it is very irritant to pleural cavity.

It is a good culture media for bacteria and so infection is quite common.

Causes

- Trauma.
- Postoperative: pulmonary, cardiac, oesophageal surgeries, cervical sympathectomy, leak from CVP monitor line.
- Tumours of lung, mediastinum, pleura.
- Leaking aneurysms.
- Spontaneous.

There may be rib fractures in traumatic haemothorax.

Clinical features

- Pain in the chest, tenderness
- Difficulty in breathing, dullness on percussion diminished breath sounds
- Features of shock

Investigations

- Chest X-ray.
- Aspiration (pleural tap).
- Chest CT scan.

Treatment

1. ICT placement in the mid-axillary line in the 6th intercostal space.
2. Antibiotics, bronchodilators.
3. Thoracotomy:

Indications of thoracotomy

- Initial chest tube output of 1500 ml of blood or persistent drainage of 200-300 ml/hr.
- Clotted haemothorax is difficult to manage. It requires thoracotomy, evacuation and decortication of lung. Initially liquefaction of the clot is tried by infusing of streptokinase and trypsin into the pleural cavity

Complications

- Infection and empyema.
- ARDS: respiratory failure.

PLEURAL TAP

Indications

- Pleural effusion—both for diagnostic as well as therapeutic purpose. The fluid is sent for culture, cytology, microscopy, specific gravity, biochemical analysis of proteins for diagnosis of tuberculosis, malignancy.
- In empyema thoracis, for diagnostic purpose before placing an ICT.



Fig. 28.3: Sites of pleural tap.

Position

In sitting position, leaning forward over a wooden support.

Site

Tip of scapula at 7th intercostal space (posteriorly).
Under local anaesthesia wide bore needle (Abraham needle) is passed to tap the fluid.

Complications

- Infection
- Dry tap or bloody tap
- Sudden vagal shock
- Pain and respiratory distress



Fig. 28.4: Position for pleural tap is sitting and leaning forward over a support. Site is below the scapula, posteriorly through the seventh intercostal space.

BRONCHOSCOPY

Indications

Diagnostic: To take biopsy in conditions like carcinoma lung, lung abscess, pulmonary tuberculosis.

Therapeutic: To remove foreign body, to suck out the bronchial secretions.



Fig. 28.5: Foreign body in trachea. This can be removed using a bronchoscope. Patient may develop collapse of lung, pneumonia, respiratory failure and ARDS.



Fig. 28.6: Bronchoscope.

Types

- *Rigid bronchoscopy*—it is used for removal of foreign body and bronchial wash. It reaches up to third generation bronchioles. It is used to take biopsy from carcinoma of proximal divisions but not from carcinoma of peripheral lung. Rigid scope has got multiple holes to allow ventilation during the procedure (Oesophagoscope does not have side holes). It is done under general anaesthesia.
- *Flexible bronchoscopy*—it reaches up to 5th generation bronchioles. It can be done under local anaesthesia. It is mainly used for diagnosis and biopsy.

Complications

- Bleeding
- Infection
- Perforation
- Bronchospasm

EMPYEMA THORACIS

> *The pleurisie is an inflammation of the membrane, investing the ribs, caused by subtile and cholerick blood.... If it tend to suppuration, it commonly infers a pricking pain, a fever and difficulty of breathing.... If nature being too weak...the disease is turned into an empyema, wherefore the Chirurgeon must then be called, who...may make a vent between the third and fourth true and legitimate ribs.... The pus or matter must be evacuated by little and little at several times; and the capacity of the chest cleansed from the purulent matter.*
>
> —**Ambroise Paré,** 1575

It is collection of pus in pleural cavity.



Fig. 28.7: Causes of empyema.

Causes

An empyema is never primary.
Secondary causes are:

- From chest wall: Wounds, osteomyelitis of ribs.
- From lung: Pneumonia, abscess, bronchiectasis, tuberculosis, growth.
- Postoperative: After thoracotomy.
- From oesophagus: Perforations, carcinoma.
- From below diaphragm: Subphrenic abscess.

Tuberculosis and pneumonia are common causes in developing countries.

Pathology

Stages of empyema

- Acute empyema
- Subacute empyema
- Chronic empyema

Initially serous fluid collects, which eventually becomes purulent. Intrapleural clotting of pus occurs with thickening of

For all the happiness mankind can gain, is not in pleasure but in rest from pain.—**Dryden** pleura and later fibrinous adhesion forms resulting in matured empyema.

Chest is withdrawn inwards and is immobile, mediastinum is drawn inwards, diaphragm gets elevated.

It leads to rigid contracted immobile chest with functionless lung underneath—*frozen chest.* Often pus perforates through intercostal space and forms *empyema necessitans*.

Organisms: Initially staphylococci, streptococci, pneumococci, and later *Entamoeba coli*, *Pseudomonas,* drug-resistant staphylococci.

Clinical types

- ❖ Acute empyema
- ❖ Acute fulminant toxic empyema
- ❖ Subacute empyema
- ❖ Chronic empyema
- ❖ Latent empyema
- ❖ Persistent empyema
- ❖ Empyema necessitans
- ❖ Chronic empyema with sinus
- ❖ Interlobar empyema

Pathological types

- ❖ Exudative
- ❖ Fibrinopurulent
- ❖ Organising

Anatomical types (Depending on the anatomical location)

- ❖ Apical
- ❖ Mediastinal
- ❖ Interlobar
- ❖ Diaphragmatic
- ❖ Lateral

Clinical Features

- ♦ Pain in the chest, tenderness, fever.
- ♦ Difficulty in breathing.
- ♦ Features of toxicity in acute type of empyema.
- ♦ Dullness on percussion, absence of breath sounds.
- ♦ Decreased chest wall movement.

Complications

- ❖ Frozen chest (functionless lung)
- ❖ Empyema necessitans
- ❖ Osteomyelitis/chondritis of ribs or vertebra
- ❖ Pericarditis
- ❖ Mediastinitis
- ❖ Bronchopleural fistula
- ❖ Dissemination of infection

Investigations

- ♦ Chest X-ray, ESR.
- ♦ Peripheral smear.
- ♦ Diagnostic aspiration.
- ♦ Pus C/S, AFB.
- ♦ Bronchoscopy.
- ♦ CT scan and MRI for carcinoma bronchus.

Treatment

Stage 1

- ♦ Antibiotics.
- ♦ Repeated aspirations.
- ♦ Intercostal tube drainage.
- ♦ Antituberculous drugs.

Stage 2

- ♦ ICT drainage.
- ♦ Rib resection *(Eloiser's method)*.
- ♦ Antibiotics, antituberculous drugs.
- ♦ Respiratory physiotherapy.

Stage 3

- ♦ ***Decortication*** *is very* useful and favourable method. Here, thickened pleural sac is stripped off from the lung through thoracotomy approach.
- ♦ Often ***lobectomy*** may be required, rarely pneumonectomy is done.
- ♦ Physiotherapy, antibiotics, ATD'S are also essential.

EMPYEMA NECESSITANS



Fig. 28.8: Empyema necessitans.

It is a complication of empyema thoracis, *wherein empyema* which is not drained perforates through the chest wall presenting as subcutaneous collection of pus communicating directly or often with a tortuous route with the pleural cavity.

Causes

- ♦ Neglected empyema either of tuberculous or nontuberculous aetiology.
- ♦ Following incomplete aspiration of pus of empyema through a thin needle—needle track itself allows pus to form a track and leads to *empyema necessitans*.

Clinical Features

A diffuse, tender, smooth, soft, fluctuant, swelling in the intercostal space having *impulse on coughing.*

Features of empyema necessitans

- ❖ Bulge in the intercostal space
- ❖ Restricted movement of chest wall
- ❖ Tenderness
- ❖ Dullness on percussion without breath sounds
- ❖ Impulse on coughing

Investigations

- Chest X-ray.
- Total count is increased.
- ESR.

Treatment

- Antibiotics.
- Empyema is drained by placing an ICT. Pus is sent for C/S and AFB.
- If it is tuberculous, antitubercular drugs are started.
- Empyema necessitans subsides on its own when empyema is treated.
- But often may require separate incision and drainage when track is tortuous.

LUNG ABSCESS

- It is localised suppuration in the lung with tissue necrosis.
- It is end-stage of suppurative pneumonitis with thrombosis of associated artery.

Aetiology

- Pneumonias due to *Streptococcus, Pneumococcus, Haemophilus, Staphylococcus,* anaerobic and other bacteria.
- Bronchial obstruction due to tumours or foreign body.
- Chronic upper respiratory infection due to sinusitis, tonsillitis and dental infection (anaerobic infection).
- Septicaemia.
- Aspiration.

As pus accumulates, tension increases inside the abscess cavity causing spread into other areas of the lung or may rupture into the bronchus.

Note:
Lung abscess secondary to aspiration is commonly seen in apical lower lobe.

Clinical features

- Acute onset of fever, but often it is recurrent in nature
- Cough with expectoration
- Haemoptysis with foul smelling sputum.
- Chronic illness with debilitation
- Pleuritic pain

Complications

- Spread into other areas of the lung.
- *Metastatic cerebral abscess*—Lung abscess is the *commonest* focus for metastatic cerebral abscess. Occurs as a result of pyaemic emboli through paravertebral veins.
- Haemorrage, may be torrential due to erosion of the vessel in the abscess wall.
- Empyema thoracis.

Differential Diagnosis

- Pulmonary tuberculosis.
- Carcinoma lung.
- Fungal infections like aspergillosis.
- Pneumoconiosis.
- Lung cysts.

Investigations

- Chest X-ray shows localised opacity with smooth margin and fluid level.
- Bronchoscopy and biopsy is done to rule out carcinoma.
- Sputum for culture, AFB and cytology.
- CT scan.



Fig. 28.9: CT scan of lung showing right-sided lung abscess with fluid level.

Treatment

Medical

1. Appropriate *high dose antibiotics* are started depending on sputum culture like penicillins, third generation cephalosporins like cefoperazone, ceftriaxone *for 3-6 weeks.*
2. *Postural drainage* for 2-3 hours, 3 times daily.
3. *Periodic culture* of sputum is done to study the response of treatment.
4. 80-90% of acute abscesses resolve by medical therapy.

Surgical

1. External surgical drainage with rib resection is done in severe acute lung abscess only. Not commonly used procedure.
2. *Lobectomy* is done when medical treatment fails.

Clubbing is frequently present in those with a chronic discharging empyema sinus.
—Hippocrates, Father of Medicine



Figs 28.10A and B: Lung abscess X-ray picture and CT of the same patient.

INTERCOSTAL TUBE DRAINAGE

It is the method of draining fluid collected in the pleural cavity safely, so as to allow the underlying lung to expand.

Indications

- Haemothorax
- Pneumothorax
- Haemopneumothorax
- Empyema thoracis
- Traumatic lung contusion
- After thoracotomy, to drain pleural cavity

Procedure

- **Sites:** An ICT is placed in 6th intercostal space in midaxillary line for haemothorax and pyothorax; in 3rd or 4th space in midaxillary line for pneumothorax.


Lung
Pleural cavity
Intercostal tube
Collecting bottle
Water column

Fig. 28.11: Intercostal tube drainage underwater seal.



Fig. 28.12: Intercostal tube drainage showing haemothorax.

- Under local anaesthesia, a small incision is made in midaxillary line (as the muscle bulk is less here and so passage of ICT is easier), parallel to intercostal space (above the rib, i.e. in lower part of intercostal space so to avoid injury to neurovascular bundle which are located in the groove in the lower part of rib). Tube with side openings is pushed into the pleural cavity.
- Other end is connected *to under water seal. Air-water column moving* with respiration can be observed. Tube is fixed with skin sutures.
- Usually for pneumothorax, ICT is kept for 2-3 days (till lung expands—confirmed by—repeat chest X-ray). For haemothorax and pyothorax it is kept for 4-6 days or until it stops draining and lung expansion is confirmed by repeat chest X-ray.
- To have proper expansion of lungs, patient is asked to blow football bladder (balloon) and do breathing exercise. If there is bronchopleural fistula, ICT should be placed for a longer time, until the fistula heals.

Complications

- Infection.
- Displacement and inadequate functioning.
- Injury to intercostal vessels and bleeding.
- Pain at the site of ICT placement.

SHOCK LUNG (Stiff lung)

Causes

- Major chest trauma.
- Septicaemia.
- Massive blood transfusions.
- DIC.

Pathogenesis

Development of microthromboembolism in small lung vessels following extensive intravascular coagulation, leading to pulmonary consolidation, which reduces the lung compliance markedly, causing severe depression of gas exchange in the lung—***a stiff lung***.

It has got high mortality as lung cannot expand at all. Outcome is fatal if emergency treatment is not given.

Treatment

- Endotracheal intubation.
- Ventilator support with IPPV.
- Antibiotics.
- High dose of steroids.
- Monitoring the patient with PCWP and cardiac monitor.
- Bronchodilators.
- The cause is treated.

PULMONARY EMBOLISM (PE)

> *From my Stanford days… I had known that excessive bed rest gave rise to thromboembolic complications….The death rate from thromboembolism was always much less at the County Hospital than it was at Stanford Hospital…. When (the County Hospital patients) got up to go to the bathroom, (they) dislodged only tiny clots from their veins and these did not harm them when they got to the lungs and were dissolved, while the wealthier patients (at Stanford) who remained in bed and formed large clots in their legs and pelvises suffered the major consequences of large pulmonary emboli.*
>
> —**William Dock,** 1984

- It is due to deep venous thrombosis (DVT) which gets detached to cause pulmonary embolism.
- It may be from femoropopliteal or ileo-femoral region.

The thrombi most commonly develop in the leg veins due to stasis and hypercoagulable state. They subsequently enlarge and propagate proximally, dislodge to form emboli.

Types

- **Small emboli**: Causes pulmonary hypertension of features of bronchopneumonia.
- **Medium emboli** lodges in branches of pulmonary artery causing chest pain, haemoptysis, dyspnoea.
- **Large (massive) emboli** causes block at bifurcation of pulmonary artery trunk or right/left pulmonary artery leading to sudden chest pain, severe dyspnoea, shock, raised venous pressure and ***sudden death.***

Effects of pulmonary embolism

- Decreased cardiac output
- Pulmonary vasospasm and pulmonary hypertention
- Bronchospasm
- Defective oxygenation of blood

Risk Factors

- Postoperative and trauma patients who are bed ridden.
- Pregnant women.
- Old age.
- Obesity and heart disease.
- Varicose veins.
- All aetiologies which cause DVT.
- Carcinoma.

Clinical features

- Dyspnoea, chest pain and haemoptysis
- Tachycardia, tachypnoea and cyanosis
- Pleural rub and cardiac gallop

The patient dyspnoeic due to pulmonary embolism prefers to lie flat.—**Ronald Gibson**



Fig. 28.13: Chest X-ray showing wedge shaped pulmonary infarct.

Investigations

- Chest X-ray PA view—hyperlucency in an area of oligaemia—*Westermark sign.*
- CT scan and MRI—can detect PE.
- Pulmonary angiography: It is diagnostic (100%).
- Arterial blood gas analysis.
- Isotope radionuclide ventilation—perfusion (V/Q) lung scanning: While normal scan rules out PE, evidence of V/Q mismatch is highly suggestive of pulmonary embolism.
- Doppler study and venogaphy—To rule out DVT.

Management

- Thrombolytics: Streptokinase, 6 lakhs units to begin with and later one lakh units hourly.
- Pulmonary embolectomy with or without bypass by immediate thoracotomy.
- Venous thrombectomy using Fogarty catheter.
- Ventilator support.
- To prevent further embolisation of embolus into the lungs, IVC filters can be placed.
- Treatment of DVT.

Note:
Heparin should not be combined with thrombolytics.

SURGICAL EMPHYSEMA

It is collection of gas/air in the subcutaneous or and fascial planes.

Causes

- Lung injury.
- Tracheal injury.
- Chest wall injury.
- After laparoscopic procedure.



Fig. 28.14: Chest X-ray PA and lateral views showing surgical emphysema.

Types

- Localised—observed at the site of trauma.
- Generalised—extensive in the neck, face, eyelids, chest wall, etc.—in the injury of bronchus, oesophagus and mediastitum.

Features

- Pain, diffuse swelling of the subcutaneous region.
- Palpable *crepitus* is diagnostic.
- X-ray chest and neck is confirmatory.



Fig. 28.15: Surgical emphysema. Note the demonstration of crepitus.

Treatment

- Conservative treatment—treat the cause.
- In severe cases—ICT one side or both sides placement.

LUNG CYSTS

Types

- Epithelial cyst
- Emphysematous cyst
- Parasitic cyst (Hydatid cyst)
- Pseudocyst of the lung

Pseudocyst of the lung: It occurs in a cavity due to tuberculosis, lung abscess or *Staphylococcus* pneumonia.

Epithelial Cyst

- It is of d*evelopmental* origin.
- It can be large single cyst or small, multiple cysts.
- It is lined by *respiratory epithelium.*
- It is often associated with cervical rib or cardiac anomalies.
- It is common in *infants and children.*
  - Usual *clinical features* are dyspnoea and chest pain. When infected, presents with fever, cough and haemoptysis.
  - *Treatment* is excision of the cyst. Antibiotics are given when infected.
  - *Here spontaneous pneumothorax is uncommon. Infection and haemorrhage are common.*

Emphysematous Cyst

- *It is a progressive disease of lung with rupture of alveolar wall and distension with air.*
- It is an *acquired* condition.
- Cyst *does not have epithelial lining.*
- Compression of adjacent lung tissue with poor gaseous exchange is common.

Usual *clinical features* are dyspnoea and severe, persistent cough.

Complications

- Spontaneous pneumothorax.
- Severe chronic bronchitis.



Figs 28.16A and B: (A) Hydatid cyst in lung (B) Ruptured hydatid cyst with water-lily sign.

Treatment

- Localised cyst is excised.
- Generalised cysts are treated conservatively.
- Pleurodesis is often required.

Here spontaneous pneumothorax is very common. Infection and haemorrhage are uncommon.

Hydatid Cyst of the Lung

- It is caused by the parasite, *Echinococcus granulosus.*
- It is often associated with hydatid cysts of the liver.
- Incidence is 15%.
- It is usually single. But multiple hydatids can occur.

Presentations

- Dyspnoea, chest pain and haemoptysis.
- Rupture into bronchial tree causes anaphylaxis.
- Rupture also causes expectoration of fluid and grape skins (vesicles).
- Fever, cough and expectoration due to secondary infection.
- Asymptomatic hydatid, identified during chest X-ray.

Investigations

- Chest X-ray:
  1. Dense homogenous opacity.
  2. Collapsed laminated membrane produces an irregular projections in a fluid level due to rupture of the cyst—*Water-lily* appearance.
  3. *Crescentic cap of air,* when it communicates into bronchial tree.
- Positive Casoni's test.
- Blood shows eosinophilia.
- Complement fixation test.
- Indirect haemagglutination test.
- CT scan—diagnostic.

Complications

- Rupture of the cyst
- Anaphylaxis
- Secondary infection
- Collapse of lung
- Pleural effusion
- Secondary pleural hydatid formation
- Hepatobronchial fistula formation (produces bilious sputum)

Differential diagnosis

- Lung abscess
- Epithelial lung cysts
- Aspergillosis

Treatment

- Thoracotomy and *enucleation of the cyst:* It is achieved by taking a good anaesthetist's help by creating positive pressure ventilation. Cyst extrudes intact. It should not be held with forceps to avoid rupture.
- *Lobectomy* is done in cases with difficulty and complications.
- Drugs like *praziquantel* or *albendazole* is given for a long period.

MEDIASTINAL TUMOURS

- It occurs at any age group, in both sexes.
- It is often identified on a routine chest X-ray, as about 50% are symptomless.



Fig. 28.17: Superior mediastinal tumour—could be thymoma, nodal mass.

Presentations

- Chest pain and back pain.
- Respiratory distress.
- Venous congestion (SVC syndrome).
- Hoarseness of voice (due to compression over recurrent laryngeal nerve).
- Dysphagia, due to oesophageal compression.
- Horner's syndrome, due to compression over sympathetic chain.
- Scabbard trachea.
- Later diaphragmatic paralysis may occur.
- Pleural effusion.
- Haemorrhage, due to erosion of major vessels by malignant tumour.


I
1
2
3
4
2
VI
5
2
X
I. Retrosternal goitre
2. Neural tumours (neurofibroma) meningocele, meningomyelocele
3. Lymphoma, foregut, duplication
4. Teratoma thymoma lymphoma
5. Pleuropericardial cyst

Fig. 28.18: Sites of mediastinal tumours.

Classification

Superior mediastinal tumour: Retrosternal goitre.

Anterior mediastinal tumours

- Retrosternal goitre, aortic arch aneurysm lymph node enlargement.
- Thymic tumours—thymomas are commonly associated with myasthenia gravis.
- Teratomas and dermoids.
- Pleuro-pericardial cyst (spring *water cyst*).

Midmediastinal tumours

- Lymphadenopathies of all causes—secondaries, lymphomas, tuberculosis—common.
- Foregut duplication cysts.
- Lipomas.



Figs 28.19A and B: Chest X-ray showing mediastinal tumour.

Posterior mediastinal tumours

- Neurofibromas—commonest, 75%.
- Ganglioneuromas.
- Aneurysm of descending aorta.
- Lymph node mass.

Investigations

- Chest X-ray, both PA view and lateral view.
- CT scan.
- MRI.
- Mediastinoscopy and biopsy.

Treatment

- Thoracotomy and removal of tumour.
- If malignant, adjuvant therapy like radiotherapy and chemotherapy are given.



Fig. 28.20A



Fig. 28.20B

Figs 28.20A and B: CT scan showing mediastinal tumour.

- Sternotomy for superior and anterior mediastinal tumours.
- Thoracoscopic and mediastinoscopic approaches.



Figs 28.21A and B: Plain X-ray chest showing posterior mediastinal mass.



Fig. 28.22: Malignant effusion—right-sided.

THYMOMAS

- Thymomas are the most common tumours of the anterosuperior mediastinum in the adult.
- They are most common in the fifth and sixth decades of life. Both sexes are equally affected.

Histological types

- Epithelial cell—has poor prognosis
- Lymphocytic
- Mixed
- Spindle—has better prognosis

50% of thymomas are malignant

Staging

I — Confined to the capsule
II — Tumour spread to periglandular fat
III — Tumour spread to adjacent tissue

Clinical Features

- Asymptomatic—50%.
- 30-40% of thymomas have associated myasthenia gravis.
- Chest pain.
- Dysphagia and dyspnoea.
- Superior vena caval obstruction.

Investigations

- *Tensilan diagnostic test:* By injecting 10 mg IV to symptomatic myasthenia will be relieved in one minute temporarily.
- Chest X-ray, lateral view shows opacity in the mediastinum.
- CT scan.

Treatment

- *For myasthenia*—tab. neostigmine bromide 15 mg tds, daily.
- *Thymectomy* is very useful.
  - When the disease is less than 5 years.
  - Myasthenia gravis without thymoma.
  - In young, females.

Features of myasthenia gravis

- An autoimmune disease
- Presence of antibodies to acetylcholine receptors in NMJ resulting in reduced muscular contraction
- Weakness of muscle on exertion
- Ptosis, diplopia, dysarthria, dysphagia
- Drooping of jaw
- Paralysis of respiratory muscle
- Periodic remission

Comedy is the Tragedy that happens to other people.



Fig. 28.23: Bronchogenic carcinoma—X-ray picture.

PANCOAST TUMOURS (Superior sulcus tumour)

> *When the tumour extends its feet from all sides of its body into the veins, the sickness produces the picture of a crab.*
>
> —**Galen,** (130-200)

- It is a type of peripheral lung carcinoma arising from the apex of the lung (5% of lung cancers).

Features

- It invades brachial plexus, sympathetic chain, upper ribs and vertebrae.



Fig. 28.24: X-ray showing right sided Pancoast's tumour.

Presentations

Pancoast's syndrome

- Lower brachial plexus palsy
- Horner's syndrome
- Rib erosion
- Apical shadow

Horner's syndrome

- Miosis
- Enophthalmos
- Anhydrosis
- Ptosis
- Loss of spino-ciliary reflex

- Intractable pain in upper chest, arm and also weakness in the arm.

Investigations

- Chest X-ray.
- CT scan.
- Bronchoscopy and biopsy.
- CT guided biopsy.
- MRI is better than CT in Pancoast tumour as brachial plexus and sympathetic chain is involved which better visualised in MRI.

Treatment

- Lobectomy/pneumonectomy.
- Radiotherapy—external tele cobalt.
- Chemotherapy—methotrexate.

Prognosis: Poor.

CHEST WALL TUMOURS

- Tumours arising from the chest wall components like muscles or ribs. They can be benign or malignant.
- Commonest benign tumour is chondroma arising from ribs.



Fig. 28.25: Chest wall tumour. Benign tumours are usually chondromas.

- Malignant tumours are *secondaries (commonest)*, chondrosarcoma arising from ribs (common among primary malignant tumours), rhabdomyosarcoma from muscles, fibrosarcoma from ribs/muscles/other soft tissues, Ewing's sarcoma and invasion from other tumours like from pleura or lungs or breast.



Fig. 28.26: Fungating tumour invading chest wall.

Benign Tumours

- *They are slow growing, nonmobile, painless and usually from the rib cartilage, near costochondral junction.*
- X-ray is diagnostic, shows rib expansion with intact cortex.
- One or more ribs can be involved. Treatment is rib resection.

Primary Malignant Tumour

- *It has got all features of sarcoma—progressive rapid enlargement, attaining large size, warm, vascular, nonmobile, often extends into the thoracic cavity or with skin ulceration.*
- *Secondaries in lung/brain/liver can occur.*
- Chest X-ray, CT chest, US abdomen should be done to see secondaries.
- CT scan can also give idea about the tumour extension and operability.
- Open incision/trucut biopsy is essential for histological confirmation.
- Treatment *is wide excision with chest wall reconstruction using different osteomyocutaneous flaps, rib grafts, mesh or acrylic plates.*
- Postoperative adjuvant chemotherapy is always needed to prevent relapse. In advanced cases radiotherapy to chest wall is advised.



Fig. 28.27: Multiple cannon ball secondaries in lung. Primary sites are—breast, kidney, sarcomas, testis, prostate, thyroid.

PERICARDITIS

> *Water contained in the sac of the heart, likewise if the sac contain within either a fluid putrid and smelling badly, or stones, it causes throbbing....Adhesions of the pericardium to the body of the heart itself...was observed in two dropsical patients.*
>
> —**Guillaume de Baillou (Ballonius),** 1735

Types

1. Acute pericarditis.
2. Chronic pericarditis.
3. Chronic constrictive pericarditis.

ACUTE PERICARDITIS

Usually by bacteria like *Staph. aureus, H. influenzae, Streptococci, Neisseria.* It is uncommon at present, because of availability of good antibiotics.

Other causes

- Viral infection
- Uraemia
- Trauma
- Malignancy
- Connective tissue disorders

- Here pus collects in the pericardial space causing decreased cardiac function and toxicity.

Treatment

- Antibiotics.
- Pericardial aspiration.
- Drainage of purulent fluid by open pericardiotomy.

Don't let the skin stand between you and the diagnosis.

CHRONIC CONSTRICTIVE PERICARDITIS (Pick's Disease)

- Here pericardium is thickened, fibrosed and calcified. Heart is encased in a rigid cavity which decreases the cardiac function as well as the venous return.

Causes

- *Tuberculous pericarditis* is the commonest cause.
- Trauma.
- Viral pericarditis.
- After cardiac surgery.

Clinical Features

- Decreased cardiac output and tachycardia.
- Dyspnoea on exertion, easy fatigability.
- Raised jugular veins, hepatomegaly, ascites and oedema feet.

Investigations

- ECG.
- Echocardiography.
- Chest X-ray.
- CT scan.

Treatment

- Pericardiotomy with biopsy.
- Pericardiectomy.
- Antitubercular drugs is started when tuberculosis is the cause.

PERICARDIAL TAP

Indications

- Pericardial effusion due to any cause—viral, tubercular
- Haemopericardium
- Purulent pericardium

Procedure

A 16 or 18-gauge needle is passed into the pericardium just below the Xiphoid process, directing upwards and backwards, towards left side with an angle of 45° to the surface.



Fig. 28.28: Pericardial tap for pericardial effusion/tamponade.

This site is used because:

- Most dependent aspiration
- Unlikely to traumatise heart
- Pleura is not punctured
- Coronary vessels are not interfered

Presently U/S guided aspiration is commonly done.

Complications

- Injury to heart.
- Infection.

CARDIAC TAMPONADE

Rapid accumulation of fluid or blood in the pericardial space causing increase in the ***intrapericardial pressure*** is called as cardiac tamponade.

This results in compression of cardiac chambers.
↓
↓ venous return
↓
↓ cardiac output

Causes

- Trauma
- Progressive pericardial effusion due to tuberculosis, viral, bacterial infections
- Often, uraemia can cause significant pericardial effusion

Clinical Features

- Hypotension.
- Widened cardiac dullness.
- Muffled or decreased heart sounds.
- Increased venous pressure with raised jugular veins.
- Pulsus paradoxus (pulse becomes weaker on inspiration than expiration).
- In severe cases, heart is unable to expand causing *shock and often sudden death*.

Beck's triad

- Hypotension
- Muffled heart sounds
- Raised jugular venous pressure

Investigation

Chest X-ray and U/S confirms the diagnosis.

Treatment

- ***Pericardial tap,*** as early as possible to allow heart to expand adequately.
- Occasionally, ***open pericardiotomy*** is required.

DIAPHRAGMATIC HERNIA

It is herniation of abdominal content through diaphragm into the chest.


Congenital
Acquired
Traumatic
Oesophageal hiatus (Commonest type of diaphragmatic hernia)
May be associated with malrotation with **Ladd's band**
Eventration
Hernia through foramen Bochdalek
Hernia through foramen Morgagni
Congenital oesophageal hernia (rare)

Etiology of congenital diaphragmatic hernia

- Genetic
- Decreased lung fluid pressure
- Failure of the closure of pleuroperitoneal canal (foramen of Bochdalek)
- Early return of bowel into peritoneal cavity from physiological hernia

Eventration

- It is weakening of diaphragm due to atrophy and loss of muscle of a part or all of one leaf of the diaphragm, with thin fibrous tissue formation, covered with pleura and peritoneum on either side.



Fig. 28.29A



Fig. 28.29B

Figs 28.29A and B: Eventration of diaphragm on table look (*Courtesy:* Dr Sadashiva Rao, MCh, Paediatric Surgeon, KMC, Mangalore).

- Diaphragm is *attenuated and inactive*.
- *Classification of eventration*:
  1. *Congenital*—marked decrease in the muscle fibres in the diaphragm, clinically it may mimic CDH with sac.
  2. *Acquired* or secondary—(a) Phrenic nerve palsy due to trauma (with Erb's palsy); viral—usually in adults (Polio, Herpes zoster, Influenza, Diphtheria). (b) Neoplasia. (c) Autoimmune neuropathy involving diaphragm or phrenic nerve. (d) Iatrogenic.
- Most of them present in the infancy and childhood. A few of them escape to adulthood.
- This thin diaphragm is raised higher and immobile. It is actually not a true herniation. But features mimic hernia.
- *Presentation*: Asymptomatic, wheezing, recurrent LRTI, exercise intolerance, extreme respiratory distress.
- Symptomatic patients have functional deficit in ventilation perfusion (V/P) ratio because lung growth is affected.
- Larger the defect more the hypoplasia. More the hypoplasia lesser the perfusion and severe the symptoms.
- Paradoxical movement compromises the gas exchange.
- *Sniff test*—fluoroscopic evaluation for paradoxical movement.
- Chest X-ray (CT scan/MRI) shows the abnormality
- Differential diagnosis are diaphragmatic hernia through foramen Bochdalek.
- Condition causes respiratory embarrassment.

Words that enlighten are more precious than jewels.



Fig. 28.30: Chest X-ray showing left sided diaphragmatic hernia. Note the bowel shadows in the left side thorax.



Fig. 28.31: Anatomy of diaphragm showing different sites where hernia can occur.

Types



Fig. 28.32: Diaphragmatic hernia.

Treatment is plication of diaphragm through laparotomy.

Indications for surgery

- Symptomatic patients
- Decreased ventilation perfusion ratio
- Prolonged (> 3 to 6 months) exertional dyspnoea
- Impairing daily activity in idiopathic / viral
- Phrenic nerve palsy

Hernia Through Foramen Bochdalek (Through Pleuroperitoneal Canal) (95% Left Sided, Only 5% Right Sided)

- It is commonest congenital diaphragmatic hernia.
- This is a developmental defective condition, due to failure of fusion of pleuroperitoneal canal leaving a direct communication between pleura and peritoneum on left side. This allows herniation of contents of abdomen into the left side thorax.
- Common content is *colon*. Occasionally small bowel, stomach are the contents.
- 80% cases do not have hernial sac. Only 20% cases has got sac.



Fig. 28.33: Postmortem look of a newborn baby with classical diaphragmatic hernia (*Courtesy*: Dr Subramanya Bhat K, Sonologist Kanhangad). Note the entire bowel occupying the left side thorax.

Pathogenesis

Pulmonary hypoplasia → *Acidosis* → Pulmonary vascular bed spasm
↗ ↓
Persistent pulmonary hypertension
↙
Persistent fetal circulation

- Hypoplasia not only on left side, it may be bilateral.
- Generations of bronchial branches decreased.
- Extension of tunica media beyond respiratory bronchioles.
- Decreased total lung mass
- Incidence: 1 in 3000 live births, M:F—2:1.
- 90% present in newborn period.
- 90% of CDH are Bochdalek hernias
- Left—80%, right—15%, bilateral—5%.
- Defects are large in babies and small in adults.
- Associated anomalies—10 to 50%, commonest—nonfixation/midgut malrotation. Other anomalies—CNS, cardiac are known to occur and commoner with large/bilateral CDH.

- Very small percentage of patients escape and pass on to adulthood. Incidence—0.17% to 6%
- Incidental detection while evaluating for some other problem. So usually they are asymptomatic.

Poor prognostic criterias in Bochdalek hernia

- Early antenatal detection (before 5th month)
- Small left ventricle
- Large diaphragmatic defect / hemiagenesis
- Stomach in chest
- Polyhydramnios

Clinical features

- Respiratory embarrassment
- Scaphoid abdomen
- Bowel sounds in left side of chest
- Mediastinal shift towards right side
- Occasionally features of intestinal obstruction

Investigations: Chest X-ray, *barium enema (common)* or barium meal, *arterial blood gas analysis (ABG).*

Treatment

- Laparotomy and dissection of the sac (when present) and closure of the defect in the diaphragm (using nonabsorbable suture material).

Note:
Persistent fetal circulation is the major problem in these newborns. It aggravates the postsurgical mortality.

Management

Antenatal	*Postnatal*
• Fetal interventions • Discontinue the pregnancy (poor prognosis) • Continue pregnancy and observation • Shift the mother to higher centre • Mode of delivery—LSCS/ normal	• Stabilise the neonate • Do not resuscitate with Ambu bag • Tracheal intubation and ventilation • Pass nasogastric tube *Surgical correction of CDH* after stabilisation

Triad of congenital diaphragmatic hernia (CDH)

- Respiratory distress
- Scaphoid abdomen
- Mediastinal shift (Pseudodextrocardia)

Association of CDH

- Pulmonary hypoplasia with persistent fetal circulation—is the actual cause for hernia
- Respiratory acidosis

Hernia Through Foramen of Morgagni

- The defect lies between the sternal and costal attachments of diaphragm and is situated in front, towards right. Colon is commonest content. Usually, it is symptom free.

Oesophageal Hiatus Hernia

- Oesophageal hiatus hernia can be congenital or acquired (common).

Traumatic Diaphragmatic Hernia

- Either on right or left side, resulting from road traffic accidents, crush injuries, penetrating injuries, or blunt injuries.
- Patient is under shock.
- On right side along with the liver, the intestines may also get herniated.
- Patient is pale, presents with respiratory distress, guarding and rigidity over the abdomen.

Investigations

- X-ray chest and abdomen.
- U/S abdomen.
- Often CT scan of abdomen and chest is done.



Figs 28.34A and B: (A) Plain X-ray chest, (B) Barium enema, showing bowel loops within thoracic cavity on the right side (diaphragmatic hernia).

Treatment

- Immediate laparotomy and exploration is done. Tear in the diaphragm is sutured.
- Associated injuries in liver or spleen or bowel are treated accordingly.
- Adequate blood transfusion and antibiotics is required.
- Ventilator support is often necessary.

PULMONARY COMPLICATIONS DURING POSTOPERATIVE PERIOD

Precipitating Factors

- Age: Common in infants and elderly.
- Sex: Common in males.
- Common in *smokers.*

An error gracefully acknowledged is a victory.

- Common in people with chronic bronchitis, asthma, tuberculosis or COPD.
- Postoperative pain.
- Deep venous thrombosis and pulmonary embolism.
- Type of surgery: Common in thoracic or upper abdomen surgeries.
- Septicaemia.
- Paralytic ileus.
- Anaesthetic complications.
- Aspiration and its problems.
- Obesity.

Complications

- Bronchopneumonia.
- Lung collapse.
- Bronchitis.
- Lung abscess.
- *Adult respiratory distress syndrome (ARDS).*
- *Respiratory failure.*
- Alkalosis.
- Pleural effusion or empyema.

Investigations

- Chest X-ray.
- Arterial blood gas analysis.

Management

- Suction—aspiration of tracheobronchial tree.
- Respiratory physiotherapy.
- Analgesics to control pain.
- Ventilator support with endotracheal intubation.
- Tracheostomy.
- Control of sepsis by proper antibiotics.

SURGICAL MANAGEMENT OF PULMONARY TUBERCULOSIS

Indications for Surgery

- Failure of medical therapy.
- Tuberculoma.
- Tuberculous bronchiectasis.
- Destruction of lobe.
- Persistent foci, persistent cavity.
- Empyema thoracis.
- Presence of neoplasm with tuberculosis.

Surgeries Done

- Pleural tap.
- Intercostal tube drainage for empyema.
- Rib resection and Eloisier's drainage.
- Lung resection is undertaken when medical treatment fails or when there is tuberculoma. It is commonly used method.
- Lobectomy or pneumonectomy.
- Decortication.
- Thoracoplasty collapse therapy—it causes elastic relaxation of lung around the lesion leading to closure of cavity.
- Creation of artificial pneumothorax (nitrogen is used).
- Temporary phrenic nerve palsy.
- Extrapleural pneumothorax.
- ***Plombage:*** It is extrapleural pneumolysis using lucite spheres.

VIDEO ASSISTED THORACOSCOPIC SURGERY (VATS)

It is visualisation and doing surgical procedures through video thoracoscopy.

It can be:

- Diagnostic—lung cyst, pleural pathology, malignancy, tuberculosis, lung abscess, emphysematous bullae.
- Therapeutic—cervical sympathectomy, oesophageal mobilisation for carcinoma of oesophagus, lung resection, excision of lung cysts, etc.

Requirements

- Expert skilled personal.
- Double lumen endotracheal tube for one lung anaesthesia.
- Instruments.

Advantages

- Open thoracotomy and its complications are avoided.
- Less painful, fast recovery.
- Magnification and precise dissection.

Disadvantages

- Injury to major structures.
- Longer duration of surgery.
- Learning curve.

Cardiac Surgery

CHAPTER OUTLINE

- Anatomy
- Preoperative Assessment and Preparation of the Cardiac Patient
- Cardiopulmonary Bypass
- Congenital Heart Diseases
- Patent Ductus Arteriosus
- Coarctation of Aorta
- Atrial Septal Defect
- Ventricular Septal Defect
- Pulmonary Stenosis
- Transposition of Great Vessels
- Tetralogy of Fallot
- Acquired Heart Disease
- Mitral Regurgitation
- Aortic Stenosis
- Aortic Regurgitation
- Valve Replacement Surgery
- Ischaemic Heart Disease
- Cardiac Pacemakers
- Postoperative Care

ANATOMY

Heart consists of right and left atrium, right and left ventricle with mitral (bicuspid) valve between left atrium and left ventricle and tricuspid valve between right atrium and right ventricle. Aorta begins from the left ventricle to have systemic circulation. Superior vena cava (SVC) and inferior vena cava (IVC) enters the right atrium to return venous blood. From right ventricle pulmonary artery begins which transport the unoxygenated venous blood into the lungs. From lungs four pulmonary veins collect the oxygenated blood to reach right atrium and to complete the cycle.

Pressure in the right ventricle is low. Pressure in the left ventricle is high.

Chordae tendinae act as guy ropes which connect valves (mitral and tricuspid) to heart through papillary muscles.

Aortic and pulmonary valves are semilunar valves.



Fig. 28.35: Normal heart anatomy.

First heart sound is produced by closure of atrio ventricular valves. ***Second heart sound*** is produced by closure of semilunar valves. Valvular heart disease may be congenital or acquired. Rheumatic heart disease is the commonest acquired cause for valvular disease. Mitral stenosis is the commonest type.

Right and left ventricles are separated by interventricular septum. Right ventricle is thinner than left ventricle. SVC and IVC opens into right atrium.

Heart derives its blood supply from two ***coronary arteries—right and left***. Left coronary artery once origins at ostium runs for 2 cm, divides into ***anterior descending and circumflex artery***. Anterior descending artery runs in the anterior interventricular groove to reach apex and ascends short distance in posterior interventricular groove. ***The circumflex arter***y runs around the base of left ventricle. Right coronary artery through atrioventricular groove reaches the posterior interventricular groove and runs along it.

Right coronary artery supplies right atrium, entire right ventricle except anterior part, posterior part of the interventricular septum, conducting system except left branch.

Left coronary artery supplies left atrium, entire left ventricle except posterior part, anterior part of the interventricular septum.

There are collaterals within the heart and extracardiac but is not sufficient enough to maintain the adequate perfusion in case of coronary block to the dynamic heart leading into myocardial infarction.

Venous drainage of heart is through superficial and deep veins. Superficial veins (great cardiac, middle cardiac, small cardiac, oblique and posterior veins) form ***coronary sinus*** ending at right atrium. Deep veins directly enter the heart called as ***Thebesian veins.***

First blood passes to the elastic vessels then resistant vessels and capillaries later to veins and then back to heart. In capillary because of great cross-sectional area, rapid transfer of substances across tissues occur.

Have a heart that never hardens and a temper that never tires and a touch that never hurts.

Flow of blood from left side heart through aorta and its branches to capillaries and return to right heart is called as ***systemic circulation.***

Blood from right heart through pulmonary artery to lungs and from lungs through pulmonary veins to left heart is called as ***pulmonary circulation***.

Conduction system of heart consists of ***SA node*** (Sinu atrial node) which is pacemaker of the heart, ***AV node*** (Atrio ventricular node) located in lower part of the atrial septum, ***AV bundle*** (Atrio ventricular bundle) with right and left branches and terminal ***Purkinje fibres*** in subendocardial region.



Fig. 28.36: Conduction system of heart.

Surface marking of the heart: Upper border is between 2nd and 3rd costal cartilage at the level of sternum. Lower border is from 2 cm to the right of sternal margin at 6th costal cartilage to the apex of heart at 5th intercostal space 9 cm from the midline.

PREOPERATIVE ASSESSMENT AND PREPARATION OF THE CARDIAC PATIENT



Fig. 28.37: Surface marking of the heart.

- Since cardiac surgery is a major surgery, proper evaluation is essential. Consent, explanation, discussion in initial phases is absolute need.
- Patient will be anxious. He needs proper consolation, moral support.
- Proper history related to smoking, alcohol intake, diabetes, previous cardiac surgery, drug intake is essential.
- ECG, chest X-ray, haemoglobin, haematocrit, blood urea, serum creatinine, blood sugar, lipid profile, blood grouping are essential basic investigations.
- ***Echocardiography*** is ultrasound examination of heart. Heart chambers, pericardium, pumping capacity, valves and their structure, ejection fraction are found through this. Usually cardiologists do this test and give opinion about it.
- **Treadmill stress test** *to find out the response of heart to work.*
- ***Coronary angiogram*** is done to find out the amount of coronary function or its block. Special coronary artery catheter is passed through the brachial or femoral artery like in seldinger angiogram. This catheter is negotiated into the coronary arteries both right and left. Radio-opaque water soluble dye is injected into the catheter and coronaries. X-ray film will confirm the status of the coronaries. Procedure is done under guidance using C-arm. Amount of block is assessed and categorised.
- ***Cardiography*** is the procedure wherein dye is injected into the heart chambers using specialised catheters and size, shape, presence of clot in the chambers, valvular incompetence are studied.
- ***Cardiac catheterisation*** is done to get cardiac ***oximetry and pressures*** in different chambers of the heart. Cardiac catheter is flexible 100 cm long tube passed to the heart under guidance. Right and left sides are assessed separately. Catheter is infused with heparinised solution to prevent intravascular clotting during procedure.
- ***Catheter to the right side*** of the heart is passed through the cubital vein, subclavian vein, SVC. Pressures at systole and diastole are studied in right atrium, right ventricle, pulmonary artery. Blood samples are collected from these three levels to study ***oxygen saturation (oximetry).***
- ***Left side of the heart*** is approached by two approaches—one is through the right atrium penetrating the atrial septum, catheter reaches the left atrium, and so to left ventricle and aorta. Pressure is recorded in each chambers. Blood samples are collected for oxygen saturation.
- ***Pressure*** will alter in valvular diseases like stenosis or regurgitation.
- ***Oxygen saturation*** is altered in shunts between right and left sided. Shunt occurs between systemic and pulmonary circulation.
- *Cardiac isotope scanning.*

- Pressure in atrium is low 0-10 mmHg. Right atrium is little lower than left
- Pressure in the right ventricle is 15-30 mmHg systolic and 0-8 diastolic
- Pressure in pulmonary artery is 15-30 mmHg systolic and 3-12 diastolic
- Pressure in left ventricle is 100-140 systolic and 3-12 mmHg diastolic
- Pressure in aorta is 100-140 systolic and 10-80 mmHg diastolic

- Pulmonary function study is done by chest X-ray, spirometry, blood gas analysis.
- Focus of infection should be looked for like dental infection, throat infection, skin infection.

CARDIOPULMONARY BYPASS

Here functions of the heart and lungs are temporarily replaced by heart—lung machine which acts as a pump and oxygenator to the body.

Heart is exposed through a midline sternotomy incision.

Venous blood from the SVC and IVC is diverted to the heart lung machine by placing tubes to them.

From the heart lung machine oxygenated blood is pumped through a tube which is passed to the ascending aorta so as to bypass the heart and lungs with retaining the function so tissues will have adequate required perfusion. Blood should be heparinised to prevent clotting. Often venous tube is placed in the right atrium.

Temperature is lowered over the heart by poring cold saline. Ventilation is discontinued.

Once procedure in the heart is over, air in the chambers of the heart is cleared. Coronary artery perfusion is restored and heart is made to beat spontaneously or using DC shock. Acidosis and hypocalaemia is corrected. Patient is warmed.

Heart is allowed to fill gradually and slowly heart lung machine blood flow is reduced. Cannulas are removed from the veins (SVC and IVC) and also from the aorta. Protamine sulphate is given to reverse the effect of heparin.



Fig. 28.38: Figure showing cardiopulmonary bypass.

Myocardial protection is achieved by:

- Infusion of solution with 20 mmol/litre of potassium into the coronaries
- Cooling cardioplegic infusate to 6°C
- Surface of the heart is sprayed with 4°C Hartmann's solution
- Body temperature is reduced to 20-27°C

Heart can be kept arrested for 2 hours.

CONGENITAL HEART DISEASES

Left to right shunt—it leads into overloading of the pulmonary circulation. Usually it is acyanotic.

PDA—patent ductus arteriosus.

ASD—atrial septal defect.

VSD—ventricular septal defect.

Right to left shunt—Blood from the systemic veins enter the systemic arteries bypassing the lungs allowing severe hypoxic blood to enter the systemic circulation. It will cause cyanosis. Examples are tetralogy of Fallot and transposition of great vessels.

Conditions without shunts—coarctation of aorta, aortic stenosis, pulmonary stenosis.

Also classified as ***cyanotic and acyanotic heart diseases.***

PATENT DUCTUS ARTERIOSUS (PDA)—10%

Ductus arteriosus is essential in fetal life wherein blood from pulmonary artery reaches the aorta through this ductus arteriosus by passing the lung. Once child is born, this ductus closes because of the beginning of the lung function. Prostaglandin prevents closure. Indomethacin promotes closure. If it persists in child it is called as PDA.

In PDA, part of the blood from aorta flows back to pulmonary artery because of high pressure in aorta (left to right shunt). This causes pulmonary hypertension.

Occasionally pressure is so severe that flow may reverse and deoxygenated blood from pulmonary artery may flow towards aorta causing reversal of left to right shunt converting acyanotic shunt to a cyanotic one. It is called as ***Eisenmenger's syndrome***. It can occur in other left to right shunt also (ASD, VSD).

Child presents with dyspnoea, chest pain, machinery murmur.

Aortogram and echocardiography are diagnostic.



Fig. 28.39: Patent ductus arteriosus.

Treatment—closure of the PDA either through interventional cardiology or more conveniently through open surgery.

Complications of PDA—congestive cardiac failure, bacterial endocarditis.

COARCTATION OF AORTA—5%

Narrowing of the aorta just distal to the origin of left subclavian artery. It is often associated with PDA, VSD.



Fig. 28.40: Coarctation of aorta.

There is increased perfusion of upper limb, cranium, face. But less blood supply occurs to lower limb, kidneys.

Types

- It can be preductal or postductal depending on relation to the ligamentum/ductus arteriosus.

Features

- It causes left ventricular hypertrophy, differential blood pressure (pressure upper limb is higher but pressure in lower limb is lower). Often there is differential cyanosis.



Fig. 28.41: Collaterals development in intercostal vessels in coarctation of aorta.

- Visible dilated intercostal vessels through collateral perfusion is more obvious when patient leans forwards.
- X-ray will show dilated proximal aorta, notching of ribs due to erosion of the intercostals vessels.
- Aortogram is diagnostic.

Treatment *is widening of the narrowed segment of aorta with Dacron patch graft, or removal of stenosed segment and arterial graft.*

Complications

- Congestive cardiac failure, bacterial endocarditis, aortic rupture.

ATRIAL SEPTAL DEFECT (ASD)—7%

- An ASD is the hole in the atrial septum thus causing communication between left and right atrium.

Types

- ***Secundum type*** is the commonest one. It is elliptical, in the middle of the atrial septum and is due to defect in the site of foramen ovale
- ***Primum type*** is lower part. It is rare
- ***Sinus venosus type*** is near SVC opening

Features

- There is shunting of blood from left atrium to right atrium. It causes left ventricular hypertrophy, pulmonary hypertension, eventually occasionally reversal of shunt as right to left leading into cyanosis.
- Dyspnoea, fixed split of second heart sound, systolic murmur due to increased blood flow through the pulmonary valve are the clinical features.
- It is diagnosed by echocardiography, cardiac catheterisation and angiocardiogram.



Fig. 28.42: Atrial septal defect.

Treatment

- Closure of the defect by direct suturing or using patch either pericardium or Dacron.

VENTRICULAR SEPTAL DEFECT (VSD)—15%

- VSD is defect in the ventricular septum causing left to right shunt. There is pulmonary hypertension, ventricular hypertrophy.

Types

- Four types of VSD are present depending on location of the defect. Defect can be small or large.
- It may be associated with tetralogy of Fallot.
- *Severe cases of shunt become reversal causing* **Eisenmenger's** *syndrome.*

Clinical Features

- Pansystolic murmur, palpable thrill, split second sound with pulmonary accentuation, recurrent respiratory infections.



Fig. 28.43: Ventricular septal defect.

- 40-50% of defects especially when they are small, will close spontaneously. Spontaneous closure will not occur after the age of 6.

Investigations

Echocardiography, cardiac catheterisation.

Treatment

Closure of the defect using pericardial patch or Dacron. While suturing care should be taken not to inure atrioventricular conduction system.

Complications of VSD

Recurrent respiratory infection, pulmonary hypertension, cardiac failure.

PULMONARY STENOSIS

It is narrowing of the pulmonary valves due to fusion of cusps. Narrowing may be as less as 2-4 mm. Patient develops right ventricular hypertrophy and later right ventricular failure. Pressure in the right ventricle is higher, in pulmonary artery is lower. Treatment is pulmonary valvotomy.

TRANSPOSITION OF GREAT VESSELS

Here aorta begins from right ventricle and pulmonary artery begins from left ventricle. So venous blood enters the aorta and causes hypoxia and cyanosis. It is usually not compatible with life but often through bronchial collaterals communication may develops and become compatible. When it is often associated with ASD or VSD or PDA mixing occurs and is compatible.

It is cyanotic heart disease.

It is diagnosed by an emergency echocardiography and aortocardiogram.



Fig. 28.44: Transposition of great vessels.

Treatment

- Immediate palliative method is ***Rashkind balloon septostomy***. A balloon is passed into the right atrium and through the septum into the left atrium. Balloon is inflated and rapidly pulled out through the atrial septum causing widening of the defect in the septum. It allows flow of oxygenated blood from pulmonary veins through the septum and so to the right ventricle and aorta.
- ***Albert-Mustard atrial redirection of flow of blood:*** Atrial septum is excised and using either pericardial or Dacron

patch left atrial blood is directed to the right ventricle and right atrial blood is directed to the left ventricle.

- Later definitive correction is done either at atrial level or at great arterial level.

TETRALOGY OF FALLOT

It is a cyanotic congenital heart disease.

Components

- Ventricular septal defect
- Infundibular and pulmonary stenosis causing right ventricular outflow obstruction
- Right ventricular hypertrophy
- Dextroposition of aorta

Because of right ventricular outflow obstruction venous blood gets diverted through the existing VSD into the left ventricle and so to the aorta. So systemic circulation is provided with unoxygenated venous blood causing cyanosis.

Features

- Cyanosis with dyspnoea. Ejection systolic murmur which diminishes during cyanotic attack.



Fig. 28.45: Tetralogy of Fallot.

- Echocardiography, cardiac catheterisation are the essential investigations.

Treatment

- ***Blalock-Taussig operation***—it is done as initial treatment in newborn baby with Fallot's tetralogy. Left subclavian artery and pulmonary artery is connected using a graft which allows the pulmonary arterial perfusion.
- ***Second stage definitive correction*** by relieving the right ventricular outflow obstruction completely and closure of VSD using Dacron patch.

ACQUIRED HEART DISEASE

Mitral Stenosis

Commonest acquired heart disease. Valve here cannot open completely during left atrial contraction.

It is scarring and thickening of the mitral valves due to inflammation of valves with valve area less than 2.5 cm^2 (normal is 4-6 cm^2). It will later lead into fusion of chordae tendinae, calcification of the valve cusps. It is commonly due to rheumatic fever with streptococcal pharyngitis.

Features

Mitral stenosis
↓
Hypertrophy of the left atrium
↓
Sluggish blood flow, left atrial hypertrophy
↓
Atrial fibrillation → atrial thrombus → emboli
↓
Pressure in pulmonary vein increases
↓
Lung congestion, oedema
↓
Pulmonary artery hypertension
↓
Right ventricular failure and tricuspid regurgitation (CCF).

Mitral stenosis—clinical features and investigations

- Dyspnoea, orthopnoea
- Cough, haemoptysis
- Mid-diastolic murmur, with loud heart sound
- Features of atrial fibrillation
- Chest X-ray shows straightening of the left border of the heart
- ECG and echocardiography will demonstrate mitral stenosis, clot
- Cardiac catheterisation shows increased right atrial pressure
- Pulmonary capillary wedge pressure (PCWP) shows increased left atrial pressure

Indications for surgery

- Severe stenosis
- Calcification of cusps
- Clot in the left atrium
- Right ventricular hypertrophy

Surgeries for mitral stenosis

- Closed mitral valvotomy—through left thoracotomy incision, heart is exposed. Left atrium is opened with purse string suture so as to allow the finger to pass inside. Left ventricular tip is incised with a purse string suture and Tubb's valve dilator is passed. Under finger guidance through left atrial purse string wound, valve and cusps are separated using ***Tubb's dilator.***



Fig. 28.46: Mitral valvotomy using Tubb's dilator.

- *Open mitral commissurotomy*—it is done with cardiopulmonary bypass, left atrium is opened, valve and commissures are separated, valve is dilated using finger, clot in the left atrium is removed.
- Open valvuloplasty by doing repair of the valve.
- Percutaneous balloon valvotomy.
- Valve replacement surgery.

MITRAL REGURGITATION

Mitral valve here cannot close completely during left ventricular contraction. It can be associated with mitral stenosis also.

Causes

- Rheumatic heart disease causing fibrosis, rigidity and shortening of chordae tendinae leading to inability to close the mitral valve.
- Myxomatous degeneration of the valve.
- Marfan's syndrome.
- Connective tissue disease.
- Sarcoidosis.

Mitral regurgitation
↓
Left ventricular hypertrophy but reduced cardiac output
↓
Left atrial enlargement with increased pressure
↓
Pulmonary venous pressure increases
↓
Lung congestion, oedema (CCF)

Features

- Cough, haemoptysis, chest pain, dyspnoea
- Pansystolic murmur
- Features of failure
- Often associated features of mitral stenosis
- Features of associated diseases
- Echocardiography, cardiac catheterization and PCWP are the investigations

Treatment

Valve replacement surgery.

AORTIC STENOSIS

Narrowing of the aperture of aorta is due to rheumatic heart disease, bicuspid stenosis, calcification. Valve is thickened, fibrosed, calcified and narrowed.

Features

- There is left ventricular hypertrophy with reduced left ventricular capacity.
- Because of the narrowing of the valve, cardiac output decreases.
- Systolic murmur is better heard over aortic area.
- Later may lead into failure.
- Echocardiography is diagnostic.

Treatment

Valve replacement surgery.

AORTIC REGURGITATION

There is incompetence of aortic valve.

Causes

- Rheumatic disease.
- Connective tissue disorder.
- Marfan's syndrome.
- Tertiary syphilis.
- Endocarditis.
- Aortic dissection.

Features

- There is left ventricular hypertrophy, and cardiac failure later
- Early diastolic murmur is characteristic
- Collapsing pulse
- Dyspnoea, chest pain
- Echocardiography is diagnostic
- It may be associated with ischaemic heart disease

Treatment

Valve replacement surgery.

VALVE REPLACEMENT SURGERY

Indications

- Severe valvular disease with fixity, stenosis
- Valve disease with thrombosis like in mitral stenosis
- Multivalvular disease

Types

1. ***Biological valves***—Capentier's glutaraldehyde preserved porcine valve with a sewing ring and frame is used. It is not thrombogenic. So, it is used in child bearing age and in whom warfarin is contraindicated. But its life span is less. So it is useful in elderly.
2. ***Mechanical valves***
   - Starr-Edwards ball—valve prosthesis
   - Bjork-Shiley tilting disc—valve prosthesis.

Mechanical valves are long lasting but they are thrombogenic. Embolic phenomenon can occur. Patient requires oral anticoagulant to keep prothrombin time twice normal. If anticoagulants cannot be used, then aspirin, dipyridamole can be used.

Problems with mechanical valves

- Thrombogenic
- Require warfarin anticoagulant therapy
- Prone for severe epistaxis, intracranial haemorrhage while on warfarin therapy
- Prone for infections by bacteria, fungi, yeasts
- Mechanical haemolysis and anaemia
- Valve malfunction may occur



Fig. 28.47: Different types of valve prosthesis.

3. ***Free homograft valve***.

ISCHAEMIC HEART DISEASE (IHD)

Main major arteries of the heart are right coronary, left coronary and circumflex artery. Blockage can occur in one or two or all three vessels. Involvement of all three vessels is called as triple vessel disease.

IHD presents as ***asymptomatic*** with sudden massive cardiac ischaemia with sudden death.

Or ***symptomatic angina,*** is progressive if not treated and eventually may lead in to severe MI.

Atherosclerosis is the commonest cause.

Risk factors are:

- Hypercholesterolaemia
- Cigarette
- Diabetes mellitus
- Hypertension
- Family history and age

Atheroma plaques deposits in the coronary artery and narrows it. Block above 70% is called as critical block. Angina is initially treated with calcium antagonists, beta blockers, nitrates.

Investigations

- ECG.
- Coronary angiography is diagnostic.
- Echocardiography.
- Lipid profile (done on empty stomach).



Fig. 28.48: Coronary artery: Anatomy and sites of CABG.

Treatment

1. *Coronary balloon angioplasty* is done in case of angina, only one or two vessels are involved. It is done by interventional radiologists in presence of cardiologists. Balloon tip catheter is passed through femoral or radial artery to reach proximal aorta and entered into the coronary artery opening. Coronary angiogram is done after injecting the dye. Balloon tip of the catheter is passed across the site of the block. Balloon is inflated to crush the atheroma.

Problems with angioplasty

- Restenosis
- May precipitate block

2. Coronary artery stenting after balloon angioplasty.
3. Coronary artery bypass graft (CABG).

Indications

- Triple vessel stenosis
- Left main stem stenosis
- Chronic stable angina
- Angina with persistent chest pain
- Block more than 70%

Grafts Used

- Patient's own long saphenous vein—*commonly used graft*
- Patient's own internal mammary artery—*choice graft* as it is reliable, less occlusion, long-term patency.

Usually 3-4 grafts are used.

Technique—It is done under cardiopulmonary bypass. Aortic cross clamps are used to help proper graft anastomosis.

Complications of CABG

- Graft thrombosis
- Narrowing
- Atherosclerosis in the graft
- Respiratory infection

CARDIAC PACEMAKERS

Cardiac rate is made regular using specialised device which stimulates the heart and acts as pacemaker.

Temporary Pacing

It is done in myocardial infarction, arrhythmias, and cardiac surgery.

Permanent Pacing

It is done in congenital and acquired atrioventricular block, sick sinus syndrome (SA node dysfunction), atrial fibrillation, certain tachycardia.

Routes of Pacing

Transvenous route is commonly used. A needle is passed into the subclavian vein and guide wire is passed through the needle into SVC. Dilators are passed through the guide wire. Then sheath is passed. Electrode is passed into the atrium or ventricle. It is endocardial pacing.

Transthoracic pacing—it is not commonly used. It requires open thoracotomy. One lead is placed to the atrium and two other to ventricle.

Pacemaker may be ***external*** usually used as temporary.

Internal pacemaker is placed in the upper chest wall below the middle of the clavicle in subfacial plane under local anaesthesia (pacemaker pocket).

POSTOPERATIVE CARE

- Proper monitoring and ICU care is essential.
- ECG, temperature, BP, CVP, cardiac monitor, urine output has to be assessed regular intervals.
- Serum electrolytes, blood gas analysis, assessment of isoenzymes, haematocrit, blood urea, creatinine.
- Acidosis and hypercalcaemia to be corrected early.

Complications of pacing

- Arrhythmias
- Infection
- Phlebitis, haematoma, thrombosis, bleeding
- Failure of battery, electrode
- Electrode displacement

Types of electrode activity

- Fixed rate—ventricular pace—no sensing
- Demand release—ventricular pace—sensing-triggered mode
- Inhibited rate—ventricular pace—sensing-inhibited mode

- *Pacemakers are sensitive to electromagnetic interference.*
- Drains from pericardium, mediastinum should be assessed carefully.
- Hypovolaemia, cardiac tamponade, myocardial infarction, hypoxia, acid-base imbalance has to be corrected.
- Dopamine, dobutamine, isoproterenol are the drugs used when there is low cardiac output.
- Digoxin, pacing, cadioversion may be required if there is cardiac arrhythmias.
- Management of respiratory system—when the patient is alert and having adequate cough reflux, endotracheal tube is removed. Breathing exercises, physiotherapy, observation for respiratory distress, prevention of pneumonia to set in are important care required.
- Care of the endotracheal tube, suctioning, checking the parameters in intermittent positive pressure ventilation (IPPV).
- Neurological system should be observed—alertness, speech, level of consciousness, any deficits are looked for.
- Strict asepsis is undertaken in cardiac postoperative period by avoiding unnecessary visitors, separate dress in postoperative ward, wearing gloves, cap, masks while attending the patient.

Strong convictions precede great actions.

Chapter 29 Adjuvant Therapy

CHAPTER OUTLINE

- Radiotherapy
- Chemotherapy
- Cell Cycle
- Antimalignancy Drugs
- Hormone Therapy in Cancer
- Immunosuppression
- Immunotherapy
- Hybridoma
- Gene Therapy

RADIOTHERAPY

> *The effect of radiations on living cells is the more intense: (1) the greater their reproductive activity, (2) the longer their mitotic phase lasts, and (3) the less their morphology and function are differentiated.*
>
> —**Jean Alban Bergonié, Louis Mathieu Frédéric Adrien Tribondeau,** 1906

- It is use of ionizing radiation as therapy, mainly in malignant conditions.
- Megavoltage X-rays or gamma rays which generates energy greater than 1×10^6 V are used.

Principles and Factors in Radiotherapy

- Penetration of the beam into the deep seated tumour.
- Building of the radiation dose under the skin over the tumour tissue so as to minimize the skin reactions.
- Precise targeting of radiation towards the tumour.
- Radiosensitivity, tumour volume and tumour size are the factors which determine the radiation efficacy.

Physicochemical Effects of the Radiation

- Direct action on the target tissues.
- Indirect action, by releasing free radicals which cause cell destruction.
- It acts on the different phases of cell cycle to destroy the cell.

Changes in the Tumour Cells after Irradiation

1. Repair of the damaged but retained cells.
2. Repopulation is by proliferation and reproduction of the retained cells.
3. Redistribution of the cells. Cells in the ‘S’ phase of the cell cycle (where DNA is being synthesised) are radioresistant. These cells after radiotherapy will go to ‘G_2’ or ‘M’ phase.
4. Reoxygenation of the cells which were hypoxic at the time of radiotherapy. Hypoxic tumour cells are radioresistant. About 10% of tumour cells are in hypoxic state.

Thus fractionation of the radiotherapy allow retained cells to go for active and sensitised phase making radiotherapy more effective.

Oxygen is a good radiosensitiser. So hyperbaric oxygen is used many times as radiosensitiser.

Radiation Unit

It is called as grey unit. It is defined as the absorption of 1 J of radiation energy by 1 kg of tissue.

Types of Radiotherapy (Therapeutic)

1. ***Curative (radical) radiotherapy:*** It is given in early malignancies as a curative or primary method to tumours which are radiosensitive.
2. ***Palliative radiotherapy:*** It is used to alleviate the symptoms when the tumour is beyond cure.

Symptoms are:

- ***Pain*** in secondaries in the bone
  - Myeloma.
  - Carcinoma breast.
  - Advanced lymph node metastasis.
- ***Bleeding***
  - Carcinoma oral cavity, cervix.
  - Carcinoma bladder, rectum.
  - Advanced secondaries in the lymph nodes.

Common tumours

- Seminoma testis
- Hodgkin's lymphoma
- Squamous cell carcinoma
- Ewing's sarcoma
- Carcinoma lung
- Gliomas
- Bladder tumours
- Carcinoma cervix, vagina, nasopharynx,
- head and neck, oesophagus
- Basal cell carcinoma

Dose is 60 Gy in 30 fractions over 6 weeks.

- ***Fungation***
  - Breast carcinoma
  - Rectal carcinoma.
- ***Obstruction***
  - Bronchogenic carcinoma obstructing inferior vena cava
  - Carcinoma cervix causing obstruction to the ureter.
- ***Pathological fracture*** due to secondaries.
- ***Spinal cord compression*** due to secondaries.

Dose is 10-25 Gy in 1 to 5 fractions.

Principle

Radiation is used to kill actively proliferating malignant cells at their mitotic level.

Common malignancies which are radiosensitive

- Squamous cell carcinoma
- Basal cell carcinoma
- Bladder tumours
- Carcinoma cervix
- Seminoma testis
- Hodgkin's lymphoma

Other areas where radiotherapy is used commonly:

- In carcinoma breast during postoperative period, for secondaries in bone, sometimes as preoperative radiotherapy, as part of *QUART Regime.*
- In follicular carcinoma of thyroid: For secondaries radio active I^{131} 5 m curies is given orally. External radiotherapy is also given for bone secondaries along with internal fixation if there is pathological fracture.
- Malignant brain tumours like astrocytomas.
- Many sarcomas.
- Carcinoma prostate.
- Carcinoma oesophagus.
- Carcinoma lung.
- Fixed secondaries in neck as palliation to palliate pain, fungation and erosion into major vessels.
- Multiple myelomas.

Radioresistant Tumours Include

- All GI malignancies.
- Melanoma.
- Medullary carcinoma of the thyroid.

Source of Radiotherapy

- Cobalt 60 machine—most commonly used.
- Kilovoltage machines.
- Linear accelerator.
- Betatron/microton.
- Radioactive materials like Cesium 137 (pellets), Iridium 192 (wire), Gold 198 (seeds), Iodine 125 (seeds).

Measurement of Ionising Radiation

Roentgen unit is a measure of ionisations produced per unit volume of air by X-rays and gamma rays but it is not used for photon energies above 3MeV. SI unit for exposure is Coulomb per kg.

Radiation Absorbed Dose (RAD)

Absorbed dose is De/dm. It is mean energy imparted by the ionizing radiation to material of mass dm.

Old unit is *rad* which is equivalent to 100 ergs of energy per gram.

Newer International Unit is Presently Used

One Grey *(Gy)* is one joule of energy deposited per kilogram of material. One Gy = 100 rads = 100 cGy. 1 cGy = 1 rad.

Radiotherapy Plan

Type and doses of radiotherapy is decided by following factors:

- Site of tumour.
- Lymphatic field.
- Tumour size and extent.
- Histological type and grading.

Types of radiotherapy (Technical)

- Superficial X-ray therapy (100 KV)
- Orthovoltage X-ray therapy (200/300 KV)
- Caesium (^{137}Cs) or cobalt (^{60}Co) teletherapy
- Intracavitary or intralesional radiotherapy (Brachytherapy)
- Radioactive I^{131} therapy for follicular carcinoma thyroid

Brachytherapy

- It is radiation given with source close to the tumour.
- It is given using iridium^{192} caesium^{137}.
- It is curative radiotherapy.
- It is used in carcinoma oral cavity, penis, breast, cervix and bladder.
- Radiation material placed in the cavity is called *intracavitory* RT.
- Radiation material is inserted into the tissues—*interstitial* RT.
- Implants can be kept permanently or temporarily.
- Radioactive material is placed into the cavity/tissue through applicators under general anaesthesia.
- Intraoperative radiotherapy is also becoming popular.
- It has only localised effect with adjacent tissue being spared.

"Cancer" word itself is lethal many times than cancer.

Radiotherapy sources	*Classification*	*Efficacy depends on:*
• X-rays, electrons-from high energy X-ray machine, i.e. Linear accelerator • Gamma and beta rays from radioactive isotopes like Cobalt-60, Caesium 137, Iridium 197 • Protons, neutrons and heavy ion nuclei from cyclotrons	• *Low LET* (Low Energy Transfer) radiation—X-rays, gamma rays, electron • *High ET* radiation—Neutrons, protons, alpha particles and negative ions. It has heavier mass with dense localisation and hence biologically more effective	• Cell cycle phase • Oxygen content of cells *Methods of delivery* • External beam radiation (Teletherapy) • Brachytherapy • Systemic irradiation using radioisotopes like I^{131}
Preoperative radiotherapy *Advantages*	*Postoperative radiotherapy*	*Radiotherapy and chemotherapy combined*
• Down-stage the tumour and reduces the tumour bulk • No change in oxygenation of tissues • Blockage of lymphatics by RT prevents tumour spread during surgical dissection • Reduces the chances of microscopic spread *Disadvantages* • Delayed healing due to reduced vascularity • Flap necrosis, fistula formation • Carotid blow-out	• More effective and extent of RT is well defined • Flap necrosis, fistula complications are less *Indications* • When resected margin is positive for tumour • When bone/cartilage are involved • Extracapsular nodal spread • Multiple neck nodes/node more than 3 cm in case of neck disease • Poorly differentiated tumour	• Commonly used before or during RT • Chemotherapy after RT is not commonly followed • Chemotherapy before RT is called *as induction chemotherapy* which reduces the bulk of tumour without altering the vascularity • Chemotherapy with RT is called as *concomitant RT* which improves the effect of RT. Methotrexate and bleomycin are radio sensitisers

External beam radiation:

Given using cobalt 60 teletherapy or X-ray source.

Advantages—Deep penetration, skin sparing, better dose distribution.

Internal radiation:

Used for diagnostic and therapeutic purpose, e.g. in carcinoma thyroid for treatment of secondaries.

Complications of Radiotherapy

- Oral mucosal oedema, ulceration, dysphagia, dyspnoea, loss of taste, oral thrush.
- Bone marrow suppression.
- Oophoritis in women and oligospermia in men.
- Effecting lens, eyelashes and lacrymal glands causing dryness, cataract.
- Mucosa in GIT is very sensitive causing nausea, vomiting and diarrhoea.
- Radiation dermatitis, pigmentation in skin.
- Radiation myelitis of the spinal cord—causing hemiplegia, paraplegia.
- Radiation pneumonitis and pulmonary fibrosis.
- Radiation nephritis and renal failure.
- Radiation osteomyelitis.
- Radiation-induced malignancies.
- Radiation-induced thimble bladder.
- Radiation-induced frozen pelvis.
- Infection—bacterial, viral, candidial *(oral thrush).*

Brachytherapy

Type	*Advantages*	*Disadvantages*
• *Intracavitary* like in uterus, urinary bladder, maxillary antrum, bronchial or oesophageal tree • *Interstitial* wherein radioactive needles/wires/ribbons/seeds are inserted into the tumour area like in bladder or oral cavity • *Surface brachytherapy* using moulds like in tumours of skin/eye/breast • Radionuclides used are Caesium 137 (Cs^{137}), Iridium 192 (Ir^{192}), Gold 198 (Au^{198}) and Iodine 125 (I^{125}) • Brachytherapy is often combined with external beam radiotherapy	• High, localised, single continuous dose of RT • Deeper and adjacent tissues are spared • High dose rate with short time • Less side effects • Curative and effective in early cancers • After loading devices are available which reduces personal exposure • Surgery is avoided and part is retained	• Technically difficult • Availability of the facility • Local complications like displacement/erosion

CHEMOTHERAPY

- Chemotherapy, today is an important modality of treatment in managing a case of cancer.
- It is the main modality of treatment in most of the advanced malignancies.
- It is used preoperatively to downstage the tumour so as to increase the possibilities of surgical resection.
- When used postoperatively it reduces the rate of recurrence.
- It is the primary treatment for NHL, leukaemia.
- These drugs mainly act by blocking the mitotic activity in the nucleus in different phases of the cell cycle.
- It is given either oral, intravenous (*systemic*), intra-arterial, intrathecal and intravesical *(regional*) or as isolated limb perfusion.
- Intra-arterial chemotherapy is used in head and neck cancers and hepatic cancers.
- *Isolated limb perfusion* is used in melanoma.

CELL CYCLE

The cell cycle is composed of:

1. ‘G_0’—resting phase or nonproliferative phase.
2. Presynthetic phase (G_1)—resting cells that are not preparing for cell division are said to be in this subphase G.
3. ‘S’ phase—DNA synthesis takes place during this phase.
4. ‘M’ phase—formation of mitotic spindle, i.e. period of mitosis.
5. Postsynthetic phase (G_2)—premitotic interval, which follows the termination of DNA synthesis.

Most potent cytotoxic agents act by damaging DNA. Their toxicity is high during the DNA synthetic phase, ‘S’ phase of the cell. Some agents block the formation of mitotic spindle in M phase (vinka alkaloids and taxanes). So the agents have activity only against cells that are in the process of division. Hence, tumour with high fraction of actively dividing cells are more susceptible to chemotherapeutic agents.



Fig. 29.1: Cell cycle.

When chemotherapy is given with interferons and interleukins, it is called as **biochemotherapy**.

ANTIMALIGNANCY DRUGS

I. Classification

1. *Alkylating agents:*
   a. Nitrogen mustards: Mechlorethamine (mustine hydrochloride), cyclophosphamide, chlorambucil, melphalan.
   b. Ethylenimines.
   c. Alkylsulfonates—busulfan.
2. *Antimetabolites*:
   a. Folic acid antagonists—methotrexate.
   b. Purine antagonists—azathioprine, 6-mercaptopurine.
   c. Pyrimidine antagonists—5-fluorouracil,
3. *Antibiotics:* Actinomycin-D, mitomycin, doxorubicin, bleomycin.
4. *Vinca alkaloids:* Vincristine, vinblastin.
5. *Miscellaneous:* Cisplatin, procarbazine.

II. Classification of antimalignancy drugs based on the action on cell cycle

S-phase specific agents: Cytosine arabinoside, hydroxyurea, 6-mercaptopurine.

M-phase specific agents: Vincristine, vinblastine, palcitaxel.

Phase nonspecific agents: Alkylating agents, nitrosoureas, antitumour drugs, procarbazine, cisplatin, dacarbazine.

Mode of Action

These drugs damage the active cells by affecting the process of cell division. Hence, they also affect haemopoiesis, cellular activity, epithelial tissues and gonads. They also suppress the immune system.

Adverse Effects in General

Bone marrow suppression, alopecia, hepatotoxicity, nephrotoxicity, damage to gonads, damage to GI mucosa and ulceration.

HORMONE THERAPY IN CANCER

Ablative Procedures

- Oophorectomy and adrenalectomy in carcinoma breast.
- Orchidectomy in carcinoma prostate.

Added Hormone

- Prednisolone, progestogens, estrogens and androgens.

Hormone Antagonists

- Tamoxifen is estrogen receptor antagonist. Estrogen receptor level is assayed. If it is more than 10 units/gm of tissue, it is called as ER positive and if less than 10 units, it is called as ER negative.
- Cyproterone acetate, competes with testosterone for binding receptors.

The miserable have no other medicine but only hope.—**William Shakespheare**

	Drugs	*Used in*	*Adverse effects*
1.	Mustine hydrochloride	Hodgkin‘s lymphoma	Alopecia, bone marrow suppression
2.	Cyclophosphamide: Dose: 3 mg/kg IV daily for 5 days in dextrose, as monthly cycle for 6 months Orally as 50 mg tablets.	Ovarian carcinoma, lymphomas, colonic and bronchogenic carcinoma	Alopecia, bone marrow suppression, haemorrhagic cystitis
3.	Melphalan Dose:10 mg daily × 3 weeks. Available as 2 mg tablets	Multiple myeloma and melanoma	
4.	Busulfan: 10 mg for 3 weeks	Chronic myeloid leukaemia	Pulmonary fibrosis
5.	Chlorambucil: 10 mg for 3 weeks	Chronic lymphatic leukaemia	
6.	Methotrexate: 2.5-5 mg/d orally;10 mg intrathecally 1-2 times a week	Choriocarcinoma, ALL, soft tissue sarcoma, breast cancer	Oral and GIT ulceration, bone marrow suppression, hepatic damage
7.	6-Mercaptopurine Dose: 2.5 mg/kg/d orally	Leukaemias and choriocarcinoma	Hyperuricaemia
8.	5-Fluorouracil Dose:15 mg/kg/d IV	Adenocarcinomas of GIT, breast cancers and cancer cervix	Neurotoxicity, stomatitis, bone marrow suppression
9.	Vinca Alkaloids. Vincristine: Dose:1.5 mg/sq.m Vinblastine: Dose: 0.1 mg/kg body weight	Leukaemia Hodgkin’s lymphoma	Neurotoxic Bone marrow toxicity
10.	Rubidomycin: Dose: 40 mg/m/ day IV	Acute myeloblastic leukaemia	Myocardial depressant
11.	Adriamycin: 60 mg/m^2 IV	NHL, hepatoma, medullary carcinoma thyroid, osteosarcoma and soft-tissue sarcomas	Cardiotoxic
12.	0‘-p DDD(Mitotane): Dose: 10 gm orally for 8 weeks	Carcinoma adrenal cortex	
13.	Bleomycin: 20 units IV or IM	Squamous cell carcinoma of skin and other regions and lymphomas	Pulmonary fibrosis
14.	Cytosine arabinoside Dose: 4 mg/kg IV	Leukaemias and lymphomas	Leukopenia and thrombocytopenia
15.	Lomustine (CCNU) and Carmustine (BCNU)	Brain tumours and lymphomas	
16.	Procarbazine	Hodgkin‘s lymphoma and Oat cell carcinoma lung	Bone marrow and CNS depression
17.	Cisplatin: Dose: 20 mg/m^2/d	Testicular and ovarian tumours	Nephrotoxicity
18.	Etoposide: Dose: 100 mg/sq.m	Testicular tumour, bladder tumour, lymphomas	
19.	Hydroxyureas	Myeloma, leukaemias	

- LHRH analogue—Goserelin (Zoladex) acts as an antagonist to carcinoma breast.
- Phosphorylated diethylstilbestrol (Honavan) is used in carcinoma prostate.

Drugs that Interfere with Hormone Synthesis or Release

- Aminoglutethimide is an adrenal inhibitor. It is also an aromatase inhibitor inhibiting the peripheral conversion of androstenedione to estrogen.
- *Papillary carcinoma of thyroid is (TSH) hormone dependent.* TSH can be very well-suppressed by giving L-thyroxine, suppressive dose, daily 0.3 mg for life long.

Steroids (corticosteroids) are used as component of chemotherapy regime. They also improve the anorexia and also control hypercalcaemia seen in patients with malignancies on treatment. They reduce cerebral oedema in intracranial malignant neoplasms.

IMMUNOSUPPRESSION

- It is mainly used in transplantation to prevent graft rejection, e.g. in transplantation of kidney, liver, heart, small bowel, pancreas.

Drugs used are:

- *Azathioprine* (Imuran, Purine analogue)—Inhibits purine synthesis.
- *Cyclosporine:* It is a very good immunosuppressant, derived from fungus. It causes inhibition of lymphocytic activity, delayed hypersensitivity, interleukins, memory cells, etc. It binds to cyclophilin, decreases IL-2 and other cytokine release from T cells. It is initially given intravenously and later given orally. It is given usually for long duration, for 12-24 months. It is *nephrotoxic* as well as *bone marrow suppressant*. So, constant monitoring by blood urea, serum creatinine, blood count, Hb% at regular intervals is required. Dose should be adjusted depending on these parameters. Cyclosporine is very effective immunosuppressant in transplantation.
- Antilymphocytic globulin—Antibodies against T-cell receptors (CD_2, CD_3, CD_4, CD_8), B-cells and macrophages.
- Steroids (methylprednisolone)—Alters transcription and translation, affects T-cells and macrophages.
- Cytosine arabinoside—Anti-inflammatory and immunosuppressive effect.
- Tacrolimus (FK506)—Bind to FK binding proteins, effects are similar to cyclosporine.
- OKT3—Acts against CD3 and T-cells.
- Mycophenolate mofetil—Inhibits inosine monosphosphate, affects lymphocytes.

Types of Immunosuppression

1. *Induction regimens*—Mainly aims to avoid rejection and to establish a good graft function during the immediate post-transplant weeks (2 weeks). Antilymphocytic sera, along with either cyclosporine or azathioprine or steroids are used here.
2. *Antirejection regimens*—It aims at reversing the acute rejections. High dose steroids and antilymphocytic sera are used here.
3. *Maintenance therapy*—Using cyclosporine or FK506 along with steroids and azathioprine.

Complications

- Infection—commonest
- Malignancy—squamous cell carcinoma, lymphoma, Kaposi's sarcoma
- Nephrotoxicity
- Bone marrow toxicity
- GIT toxicity
- Neurotoxicity

IMMUNOTHERAPY

It is enhancing the host response of patient whenever required, commonly against malignant cells. Often it is used in other conditions also, where there is severe immunosuppression due to any reason like bone marrow suppression or in specific conditions like severe hepatitis.

Immunotherapy can be:

- Active
- Passive
- Restorative
- Adaptive

Immunotherapy agents

- Monoclonal antibodies.
- Bone marrow transplantation.
- Cell transfer.
- Lymphokines.
- Thymic hormones.
- Levamisole and BCG (as immunomodulators).
- Prostaglandins.
- Interferons, interleukins.
- Immunoglobulins.
- Antibody derived specific to certain tumour like melanoma.

Tumours where immunotherapy is used

- Melanoma
- Bladder tumour
- Carcinoma colon
- Renal cell carcinoma
- In many tumours it is under trial

Disadvantages

- Very costly.
- Nonavailability.
- Effect is not 100%.

HYBRIDOMA

- It is a biotechnological process wherein *multiplication* property of *Myeloma cells* is combined with *synthetic* property of some other required cells, *to achieve rapid* and large quantity manufacturing of required chemical.
- Myeloma cells with only retained multiplication activity is fused with human cells or lymphocytes or other cells (of nature to produce the required product) by ***hybridisation***. The resulting cell has got the capacity to multiply rapidly and to produce required product in large quantity. It is called as ***hybridoma***.
- It is used to generate monoclonal antibodies, insulin and many other antibodies, immunoglobulins, etc.

Monoclonal antibodies are used for

- Immunodiagnosis—for radioimmunoassay, radionuclide scan
- Antibody for detection of tumour antigen
- For cancer therapy
- For serotherapy
- As conjugates (with drugs, toxins, isotopes)
- For production of other chemicals and as a *research tool*

GENE THERAPY

The ability to alter specific genes of interest is, nowadays an exciting and powerful tool in the potential management of a wide range of diseases. Instead of giving a patient a drug to treat or control the symptoms of the genetic disorder, physicians may be capable of treating the basic problem by altering the genetic makeup of the patient's cell.

Typically two methods have been considered: Germ line and somatic cell gene therapy.

- *Germ cell therapy* involves insertion of a gene into fertilised egg for the correction of a genetic disease. Because these genes are dispersed throughout the tissues of the egg, they end up in the germ cells of the foetus, and hence are passed on to the future generations.
- *Somatic cell therapy* involves the insertion of genes or otherwise manipulating the gene machinery of a cell to treat a disease. In this case the cells are restricted to the population that has been treated and any genetic change remains restricted to these cells and is not passed onto the germ cell line.

The goals of human somatic therapy are usually one of the following:

- To repair or compensate for a defective gene.
- To enhance the immune response directed at a tumour or pathogen.
- To protect vulnerable cell populations against treatments such as chemotherapy.
- To kill tumour cells directly.

Several single gene disorders are candidates for gene therapy and in addition, current thinking has expanded to include treatment of AIDS and atherosclersis using gene therapy techniques.

Vectors used for gene therapy fall into ***two main classes***—*Viral and nonviral.*

- **Viral:** Initially retroviruses were used as vectors. Other potential vectors include Adenovirus, Herpes virus and Vaccinia virus.
- **Non-viral systems**
  - Liposome mediated DNA transfer.
  - DNA protein conjugates.

However exciting and appealing the prospects of gene therapy may appear, this technique is still in the experimental stages.

Chapter 30 Anaesthesia

> *It has long been an important problem in medical science to devise some method of mitigating the pain of surgical operations. An efficient agent for this purpose has at length been discovered. A patient has been rendered completely insensible during an amputation of the thigh, regaining consciousness after a short interval.*
>
> —**Henry Jacob Bigelow,** 1846

CHAPTER OUTLINE

- Preoperative Assessment
- General Anaesthesia
  - Anaesthetic Agents
  - Oxygen
  - Muscle Relaxants
  - Reversal Agents
  - Instruments in Anaesthesia
  - Complications of General Anaesthesia
  - Postoperative Care
  - Monitoring the Postoperative Patient
- Regional Anaesthesia
  - Topical Anaesthesia
  - Infiltration Block
  - Field Block
  - Nerve Block
  - Intravenous Regional Anaesthesia
- Spinal Anaesthesia
  - Saddle Block
- Epidural Anaesthesia
  - Caudal Anaesthesia

PREOPERATIVE ASSESSMENT

History

1. Chronic cough, smoking, alcohol, drug intake, drug allergy.
2. Any previous diseases like hypertension, diabetes mellitus, epilepsy, bronchial asthma, tuberculosis, hepatitis, cardiac diseases.
3. Drug therapy: Steroids, antihypertensives, sedatives, antibiotics, antiepileptics.

Examination

General: Posture, teeth, mouth opening, dilated veins, neck movements, tremor, airway.

Anaemia, oedema, jaundice, cyanosis.

Respiratory system: To look for asthma, tuberculosis, emphysema, COPD.

Airway: Mouth opening, Mallampati scoring, thyromental distance, temporomandibular joint assessment.

Thyromental distance: It is the distance between mentum and thyroid cartilage, measured externally. If it is more than 6.5 cm (i.e. more than 4 fingers breadth) intubation is easier, if it is less than 6.5 cm intubation is difficult.

Cardiovascular system: Hypertension, ischaemic heart disease, arrhythmias, cardiac failure, valvular diseases.

Spine: Curvature, intervertebral space, skin over the area for any infection.

Other systems: Abdomen, skeletal system.

Scoring to assess intubation

Mallampati scoring:

Class I — Faucial pillar, soft palate, uvula are seen
Class II — Faucial pillar, soft palate are seen
Class III — Only soft palate is seen
Samsons Young modification:
Class IV — Only hard palate seen
Class I, II: Easy intubation
Class III, IV: Difficult intubation

Preoperative Investigations

Haematocrit, blood sugar, blood urea, serum creatinine, electrolytes, chest-X ray, ECG, blood grouping, blood-gas analysis, cardiac assessment.

> *When giving mouth-to-mouth resuscitation, the important thing to remember is to remove your denture first.*
>
> **—WU McClenahan**

Preoperative Treatment

- Control of respiratory and cardiac diseases.
- Improvement of Hb% status, if anaemia is present.
- Preoperative antibiotics are given.
- Blood should be kept ready for major cases.
- *Starvation for 4 hours for liquids and six hours for solids.*
- Bladder and bowel should be emptied to prevent soiling on the operation table. Urinary catheter may be passed and enema may be given.
- Dentures, contact lenses, jewellery must be removed.
- Surgical area should be cleaned and properly prepared.

GENERAL ANAESTHESIA

It means abolition of all sensations, i.e. touch, pain, posture and temperature with a state of reversible loss of consciousness.

It has got three components:

(1) Analgesia. (2) Hypnosis. (3) Muscle relaxation.

ANAESTHETIC AGENTS

- ***Volatile anaesthetics*****:** They vaporise in room air.
  - Agents used are: Ether, trichloroethylene, halothane, enflurane, isoflurane, sevoflurane.
  - *Ether* which is irritant, unpleasant, flammable, is commonly used agent in developing countries.
  - Enflurane and isoflurane are non-inflammable, non-explosive, non-irritant and stable. Here anaesthesia is rapid with faster recovery.
- ***Gaseous anaesthetics*****:**
  - *Nitrous oxide*: It is non-inflammable, non-irritant, good analgesic but weak anaesthetic agent. It is given along with 30-50% oxygen for balanced anaesthesia (blue coloured cylinder in India).
  - Cyclopropane is highly flammable.
- ***Intravenous anaesthetics*****:**
  - *Thiopentone*: It is ultrashort acting barbiturate which causes hypnosis during induction of anaesthesia. It does not have analgesic effect. It causes hypotension, respiratory depression, laryngeal and bronchospasm. Recovery is rapid. Extravasation of drug can cause skin ulceration. Intra-arterial injection causes vasospasm and gangrene. Dose: 4-7 mg/kg.
    Methohexitone sodium.
    Propanidid. 4-7 mg/kg. It can cause anaphylaxis.
  - *Ketamine:* Dose: 2 mg/kg IV. It is a good analgesic. It causes dissociative anaesthesia. It can lead to hypertension, apnoea, laryngospasm. In children it can be given IM-5 mg/kg. It does not require intubation for small procedures.
  - *Propofol***:** It is widely used induction agent which has got predictable onset and recovery. It has got least side effects on CVS and respiratory system. It is also used for total IV anaesthesia. Dose: 1-2.5 mg/kg.
  - Fentanyl is neuroleptanalgesic. It causes sedation, catatonia, dissociation, hypotension and preferred in asthmatics.

OXYGEN

- Oxygen is given through Boyles apparatus (33.3%).
- Oxygen in high concentration is respiratory depressant and also affects eyes.
- A 5% CO_2 mixture in oxygen is called as carbogen.
- Oxygen is available in black and white coloured cylinder.

MUSCLE RELAXANTS

Depolarising Muscle Relaxants

They act at the level of acetylcholine receptors which widens the refractory period after depolarisation causing paralysis. It is short acting muscle relaxant.

a. *Suxamethonium chloride (scoline*):
  - It lasts for 2-4 minutes.
  - It causes muscle twitching—fasciculations—paralysis.
  - It is metabolised by plasma pseudocholinesterase. Atypical or deficiency of this enzyme prolongs the action of the scoline.
  - *Side effects* are hyperkalaemia, myotonia, apnoea and cardiac arrest.

b. *Suxthonium bromide.*

Non-Depolarising Muscle Relaxants

They block the channels of entry of acetylcholine. They are long acting relaxants.

1. *Tubocurarine*: It lasts for 45 minutes. 30 mg is the dose.
2. *Gallamine. (Flaxedil*): Dose is 1-2 mg/kg. It is cheaper. It is contraindicated in renal diseases.
3. *Pancuronium bromide (Pavulon*): It is synthetic steroid muscle relaxant. It's action lasts for 45 minutes. Dose is 0.08-0.1 mg/kg.
4. *Vecuronium bromide*: It is a steroid muscle relaxant, given at a dose of 0.05-0.1 mg/kg.
5. *Rocuronium is* short acting steroid muscle relaxant. It starts its action in one minute.
6. *Atracurium*: It lasts for 20-30 minutes. Dose is 0.6 mg/kg.
7. *Mivacurium*: Dose is 0.15-0.25 mg/kg.

REVERSAL AGENTS

They are anticholinesterase drugs which increase the acetylcholine and thus act as antagonising agents for non-depolarising muscle relaxants. They cause bradycardia.

Neostigmine (2.5 mg) is used commonly along with atropine (1.2 mg).

Edrophonium (short acting) and pyridostigmine (long acting) are other drugs.

INSTRUMENTS IN ANAESTHESIA



Fig. 30.1: Different sized airways have different colours.



Fig. 30.2: Different sized masks used during anaesthesia.



Fig. 30.3: Boyle's apparatus used for anaesthesia.



Fig. 30.4: Direct laryngoscope with endotracheal tube and tongue depressor.

1. ***Boyle's apparatus:***
   It consists of:
   a. Cylinders for N_2O and O_2.
   b. Pressure gauge—to know the amount of gas remaining.
   c. Pressure regulator—to regulate the pressure of gas used.
   d. Rotameter—to know the flow of gas.
   e Vaporiser.

Note:

Pin index code: It is safety mechanism to fix gas cylinder onto the Boyle's machine. Different gases have different pin index codes, so that interchanging of cylinders does not take place.
Pin index code for N_2O is 3, 5.
Pin index code for O_2 is 2, 5.
Pin index code for air is 1, 5.

2. ***Endotracheal tube*****:** These are tubes inserted into the trachea and is used to conduct gases and vapours to and from the lungs. Depending on the diameter, it is available in various sizes. It has a cuff at one end which, when inflated stabilises the tube in position and also prevents regurgitation. Non-cuffed tubes are also available. The other end near the mouth is connected to the breathing circuit through which anaesthetic gases are delivered. The tube is inserted using a direct laryngoscope. The proper placement in the airway is confirmed by auscultating for the breath sounds over the chest when the gases are delivered.

Complication

- Postoperative sore throat
- Hoarseness after intubation
- Upper airway oedema

3. Magill's forceps.
4. Mouth gag.



Fig. 30.5: Magill's forceps.

5. Laryngoscope.
6. Connectors.
7. ***Laryngeal mask airway (LMA):***
   - Laryngeal mask consists of a wide bore tube whose proximal end connects to breathing circuit and distal end is attached to an elliptical cuff which can be inflated.
   - These come in various sizes for various age groups. It is made up of silicone rubber.
   - The deflated cuff is lubricated and inserted into the hypopharynx, so that once inflated, the cuff forms a low pressure seal around the entrance into the larynx.

The future belongs to those who believe in the beauty of their dreams.

Advantages

- Does not require laryngoscope for insertion
- Does not cause irritation of airway
- Less incidence of laryngospasm
- In case of inability to intubate can save the life of the patient

Contraindications

- Pharyngeal pathology
- Full stomach as it can cause aspiration
- Bronchospasm

Components of general anaesthesia

- Premedication
- Induction
- Maintenance
- Recovery

Premedication

It is given one hour before surgery:

- *For sedation and relief of anxiety*. Pethidine 50 mg/morphine 10 mg/diazepam 10 mg, midazolam 1-2.5 mg.
- To suppress vagal activity. Atropine 0.6 mg IM.
- *To reduce vomiting*. Promethazine (phenargan) 12.5 mg.

Induction: Patient is preoxygenated with 100% oxygen for 3 minutes then induced with IV thiopentone, given 4-5 mg/kg. Patient *loses consciousness*. Induction is maintained by 67% nitrous oxide and 33% oxygen.

Scoline is given IV to relax muscles so as to facilitate *endotracheal intubation*.

Once intubated, *ventilation* can be either *controlled* using muscle relaxants or *spontaneous* using a volatile anaesthetic agent.

Reversal is done using neostigmine and atropine or glycopyrrolate.

COMPLICATIONS OF GENERAL ANAESTHESIA

- Intra-arterial injection of the drug.
- Myocardial depression and cardiac arrest.
- Hypertension.
- Laryngeal and bronchial spasm.
- Cardiac arrhythmias.
- Respiratory failure.
- ARDS.
- ***Mendelson's syndrome***: It is due to regurgitation of the acid from the stomach causing aspiration of acid leading into bronchospasm, pulmonary oedema and circulatory failure. This is treated with oxygen, suction, hydrocortisone, aminophylline, antibiotics, Ryle's tube aspiration and ventilator support.
- Hypoxia.
- Pneumothorax.
- Anaphylaxis.
- ***Malignant hyperthermia***: It is an inherited myopathic disorder occurs under anaesthesia due to drugs like halothane, scoline. There is marked increase in metabolic rate, with rise of temperature. There is high levels of CPK enzyme. Condition will cause metabolic acidosis and hyperkalaemia. It has got high mortality. Treatment is IV dantrolene, cooling, oxygen and cold IV fluids.
- Hypothermia.

POSTOPERATIVE CARE

Immediate postoperative period is important and critical, because patient may not be fully conscious. Patient should be kept in recovery room until he/she recovers from anaesthesia.

1. *Care of respiratory system*: Adequate breathing is important, otherwise hypoxia sets in, which gradually leads to cardiac arrest.

Respiratory problems may be:

- Laryngeal spasm
- Falling of tongue backwards blocking the airway
- Aspiration
- Bronchospasm
- ARDS
- Respiratory failure

Oxygen supplement through mask, observation, proper positioning are the treatment.

2. Hypercarbia.
3. Circulatory problems:

- Hypotension
- Arrhythmias
- Hypertension
- Cardiac arrest

4. GIT:

- Vomiting
- Regurgitation
- Mendelson's syndrome

5. *Renal problems:* Oliguria, i.e urine output is less than 30 ml/hour. It may be due hypovolaemia, hypotension, acidosis, sepsis, transfusion reaction, toxins.

   The ratio of urine/plasma osmolality of 2:1 signifies pre-renal failure. Ratio of 1.7:1 indicates renal failure.

   Blood urea and serum creatinine is done at regular intervals.

   Fluid and electrolyte imbalance, if any is corrected.

   100 ml 20 % mannitol or frusemide 40-80 mg are often required.

6. Other problems:

   Restlessness, shivering, pain.

MONITORING THE POSTOPERATIVE PATIENT

- Pulse, temperature, BP chart.
- Breathing type.
- Level of consciousness.
- Urine output.
- Oxygen saturation and heart rate using pulse oximeter.
- Checking and encouraging limb movements.
- Skin colour, tongue colour for adequacy of oxygenation.
- Tongue for hydration.

- Cardiac monitor.
- Blood gas analysis in case of patient on ventilator.
- Serum electrolytes assessment.

REGIONAL ANAESTHESIA

Carl Koller, an ophthalmologist introduced cocaine as local anaesthetic in ophthalmic practice.
Mode of action: It causes temporary conduction block of the nerve, thus preventing the propagation of nerve impulse.

Advantages of local anaesthetic agent:

- Technically simpler.
- General anaesthesia is avoided.
- Consciousness is retained.
- Patient can have food earlier after surgery.

Drugs used:

- Cocaine, procaine, cinchocaine—amino esters.
- Lignocaine, prilocaine, bupivacaine, ropivacaine—amino amides.

Lignocaine/lidocaine/xylocaine: It is the commonest local anaesthetic agent used. It is available as 0.25-5% concentrations.

It is metabolised in the liver and excreted in the kidney as xylidines. It is also an antiarrhythmic drug and so commonly used in cardiology and cardiac surgery.
Side effects: Giddiness, headache, postural hypotension, tinnitus, circumoral anaesthesia.
Dose: 4 mg/kg effect lasts for 90 minutes.

Uses

- Topical-4%.
- Infiltration block: 0.25%.
- Field block 0.5%.
- Nerve block 1.0 %.
- Epidural 1.5, 2.0%.
- Spinal 5%.

It can be used with or without adrenaline.

Xylocaine with adrenaline has got longer duration of action. It creates relatively bloodless field.

But it should not be used in places where end arteries are present like glans penis, ear lobule, tip of the nose, lip, fingers and toes.

Bupivacaine (Marcaine): It has got prolonged action. It is a vasodilator also.

Dose: 3 mg/kg.
Epidural block: 0.5%
Spinal 0.5% 3 ml.

TOPICAL ANAESTHESIA

- It is used for minor surgeries of eye, laryngoscopy, bronchoscopy, cystoscopy, gastroscopy.
- It is available as instillation, spray, viscous, ointment, gel, EMLA (Eutectic mixture of local anaesthetic).

INFILTRATION BLOCK

Direct injection of local anaesthetic under the skin for small procedures.

FIELD BLOCK

It is achieved by blocking the entire field of excision where lesion is located.

NERVE BLOCK

- Block of inferior dental nerve and lingual nerves in the region of the mental foramen for extraction of teeth.
- Finger block of digital nerves. Here plain xylocaine is used (without adrenaline).
- Intercostal block.
- Ankle block.
- Median and ulnar nerve block.
- Brachial plexus block *(Winnie's block).*
  It can be given through:
  - Interscalene,
  - Axillary,
  - Supraclavicular approaches.

Supraclavicular approach is commonly used. 1 cm above the mid-point of the clavicle, needle is passed downwards, backwards and medially towards first rib. Once needle hits the first rib, 15-20 ml of 1.5% xylocaine is injected (with walking or stepping over the first rib). Complications are pneumothorax and injury to the great vessels.

Other blocks:

Cervical plexus block.
Sciatic nerve block.
Femoral nerve block.

INTRAVENOUS REGIONAL ANAESTHESIA (BIER'S BLOCK)

Limb is exsanguinated and occluded with tourniquet. Pressure in the tourniquet must be 30 mmHg more than the systolic pressure of the patient. Needle is placed in the selected vein. 40 ml of 0.5% xylocaine for upper limb and 80 ml of 0.25% of xylocaine for lower limb is injected into the vein. *Xylocaine with adrenaline should not be used.* It gives very good analgesia for 2 hours.
Side effects: Sudden release of drug into the circulation can cause hypotension, convulsions and often death.

Bupivacaine should not be used.

Indications

For upper and lower limb surgeries, it can be used without G/A or S/A.

SPINAL ANAESTHESIA

It is the injection of local anaesthetic into the subarachnoid space causing loss of sympathetic tone, sensation and motor function. The sympathetic block is 3 segments higher than sensory block, motor block is 3 segments lower than sensory block.

Position: Lateral decubitus position with head, hips and knees being fully flexed so as to open the inter-laminar spaces. Highest point of iliac crest corresponds to 4th lumbar vertebra.

Drugs used:

Lignocaine 5% in 6% dextrose, 2 ml.
Bupivacaine 0.5% in 5% dextrose, 3 ml.
Cinchocaine 0.5% in 6% dextrose, 2 ml.

Technique: 24-26 gauge needle with stillette is used. Needle is passed through the interspinous space and ligamentum flavum to reach the subarachnoid space to get clear fluid (0.5 ml/ sec). Needle is rotated 360 degrees and drug is injected slowly. Patient is repositioned to supine. Drug takes 15 minutes to act.

Types

1. Caudal (up to L_5)
2. Low spinal (up to L_1)
3. Mid-spinal (up to T_{10})
4. High spinal (up to T_6)
5. Unilateral spinal

Advantages

- Economical
- Hypotension reduces the bleeding
- Adequate relaxation is achieved
- Respiratory complications are less



Fig. 30.6: Spinal anaesthesia being given. Note the position of the patient.

Disadvantages and Complications

- CSF leak and aseptic inflammation of meninges causing headache.
- Meningism.
- Infection.
- Paraplegia. It is very rare.
- Occasionally it can become total spinal which requires intubation and ventilator support.

Contraindications

- Cardiac patient
- Allergy
- Increased intracranial pressure. It may precipitate coning
- Sepsis
- Spinal tumours
- Back pain and spinal diseases
- Neurological conditions like syringomyelia
- Kyphosis, scoliosis

SADDLE BLOCK

- It is used for surgeries in perineal and anorectal region.
- It is spinal anaesthesia using xylocaine or bupivacaine given in sitting position.

EPIDURAL ANAESTHESIA

- It is a potential space between dura anteriorly and ligamentum flavum posteriorly which has got negative pressure inside. It extends from foramen magnum to sacral hiatus.
- ***Touhy needle*** is used for epidural anaesthesia. Once the needle is in the space there will be sudden indrawing of air or saline drop.
- An epidural catheter is placed in the space and fixed. 2% xylocaine with adrenaline or 0.5% bupivacaine is injected into the space to achieve anaesthesia up to the desired level.



Fig. 30.7: Epidural anaesthesia with epidural catheter placed.

Advantages

- It can be used for continuous repeated prolonged anaesthesia.
- It can be used for postoperative analgesia.
- It can be kept for several days.

CAUDAL ANAESTHESIA

Caudal space is the sacral component of epidural space and access is through the sacral hiatus.

Indications

- Haemorrhoidal surgery
- Circumcision
- Small procedures in the perineum like cystoscopy

Procedure

It is given in lateral position. Needle is inserted through the sacral hiatus to enter the caudal epidural space. Drug is then injected into the space.

Complications

- Trauma to anal canal
- Intravascular injection
- Failure of caudal block

Chapter 31 Advanced Imaging Methods

> *What would it be like in a radiologist's shoes? To spend most of my day dealing with images of people: plain black-and-white X-ray images, or speckled images caused by sound waves bouncing off organs, or images caused by dyes outlining arteries and veins, or contrast medium filling loops of bowel, or images reconstructed by computers into cross sections of the body-all without speaking to a patient.*
>
> **—Abraham Verghese,** 1994

CHAPTER OUTLINE

- Ultrasound
- Doppler
- CT Scan
- MRI
- Radionuclide Imaging
- PET Scan

ULTRASOUND

Ultrasound contains waves with a frequency of more than 20,000 cycles/second which the human ears cannot hear.

In medical sonography, frequencies used are commonly 2-10 MHz. The transducer or the probe works as both transmitter of ***sound waves*** and receiver of ***echoes.*** The piezoelectric crystal is the producer of ultrasound waves. Received signals from the patient are fed into the computer which forms the image.

There are three types of ultrasound image display.

1. **A-mode**: Only one dimensional static display as spikes are obtained. It is used only in eye scan.
2. **B-mode**: Two dimensional real time images in the form of grains. It is most widely used type. Using this mode *Transverse, Longitudinal or Oblique* sections can be taken.
3. **M-mode**: Here images are recorded as dots. It is mainly used in moving parts like echocardiography. M-mode is also called as TM mode, i.e. *Time Motion Mode*.

Uses

1. Used in all abdominal and pelvic conditions, often in thoracic conditions.
2. ***Ultrasound of thyroid*** is very useful method to differentiate between solid and cystic lesions.
3. Ultrasound is used in testicular tumours, epididymoorchitis, trauma to testis, erectile dysfunction, etc.
4. Ultrasound breast is used to differentiate solid from cystic tumours.
5. Soft tissue and musculoskeletal ultrasound.
6. Ocular ultrasound is ideal method to image eye and intraocular structures.

Advantages

- No radiation
- Noninvasive
- Effective with efficiency
- Painless
- Low cost
- Available even as portable machines
- Stones are well visualised with *acoustic shadow*

Disadvantages

- Interpretation can be inadequate
- Bowel shadow may prevent proper visualisation
- In obese patient image will be inadequate
- **Interpretation** is based on echogenicity either *hyperechogenic* or *hypoechogenic*

Advanced ultrasound techniques

- Endosonography (EUS) is used in visualisation of walls of oesophagus or stomach through gastroscopy
- Transvaginal ultrasound
- Transrectal ultrasound to see prostate
- Doppler ultrasound to study arterial and venous diseases


Aneurysm of abdominal aorta
Long
Transverse

Fig. 31.1: US showing abdominal aortic aneurysm.



Fig. 31.2: US showing appendix—appendicitis.


Liver
Liver

Fig. 31.3: US showing liver mass.


Cranial sonography
LV
3
4

Fig. 31.4: Cranial sonography is done to see intracranial problems through suture lines—usually done in infants and children.


Thyroid
Trachea
Right lobe
Left lobe
A
Right lobe—thyroid
B

Figs 31.5A and B: US thyroid showing thyroid both lobes in one; solid and cystic components in another.

It's your imagination that can take you anywhere.



Fig. 31.6: US picture of a pelvic mass.

Ultrasound as therapeutic use

- To guide aspiration of amoebic liver abscess, pericardial tap
- On table ultrasound can be done to assess the operability of tumour. (During laparotomy to assess the extent of tumour, lymph node status, etc.)

DOPPLER

Doppler effect is a change in the perceived frequency of sound emitted by a ***moving source***. So it measures blood flow. Spectral Doppler wave form and ultrasound image are combined in **Duplex scanning**.

Types

1. Continuous waves.
2. Pulsed waves.

Doppler will provide both audio and video signals.

Colour Doppler imaging displays flowing blood as ***red*** when direction of flow is towards the transducer. Image will be ***blue*** if flow is away from transducer.

Uses

- To study cardiovascular system.
- To study vascularity of tumours.
- To study blood flow and velocity in arterial diseases so as to assess stenosis (its extent, cause, etc.) like in atherosclerosis, TAO, cervical rib, aneurysm, A-V fistulas.
- To find out deep venous thrombosis (DVT), varicose veins, perforator incompetence.
- To study grade of varicocele in males.

Advantages

- It has replaced venogram and angiogram in many places as a diagnostic tool.
- It is reliable and non-invasive.

CT SCAN

Computerised tomography scan was invented by ***Godfrey Hounsfield*** in 1963. He was a physicist. He received **Nobel prize** (1972) for the same. The first CAT scan is in the London museum.

Narrow X-ray beams are passed from rotating X-ray generator through **the gantry** where patient is placed. When X-rays pass through the tissues, some of the X-rays get absorbed and some pass through, depending on the tissue density. The different grades of absorption in different tissues are detected through sensitive detectors which are translated to a Gray scale image by a computer.

- Density of tissues is numbered as **Hounsfield Number (HN)**
- Water—Zero HN
- Air—Minus 1,000
- Bone—Plus 1,000

The density of other tissues come in between air and bone with different HNs

Presently spiral CT scan has become popular. They are faster and in a single breath holding time, whole CT scan can be taken.

Both plain and contrast CTs are done whenever required.

Contrast Agents

- **Ionic**: Water soluble iodide dyes like *Sodium diatrizoate, Meglumine iothalamate (Conray, Urograffin, Angiograffin).* They are cheaper but often toxic and cause anaphylaxis.
- **Non-ionic are** safer but expensive, like *Iohexol (Omnipaque), Iopamiro.*

In abdominal CT, contrast agents can be given orally to delineate bowel properly.



Fig. 31.7: CT scan picture showing liver secondaries.

Indications

- **Trauma** like head injury, chest injury, abdomen trauma. In trauma *only plain CT scan* is taken.
- **Neoplasms:** To see the exact location, size, vascularity, extent and operability.

For example, brain, abdominal, retroperitoneal, thoracic and spinal tumours.

- **Inflammatory conditions,** in various sites.
  For example, psoas abscess, pseudocyst of pancreas.



Fig. 31.8: CT scan showing ascites (gross).



Fig. 31.9: CT scan abdomen showing right renal mass (RCC).



Fig. 31.10: CT scan showing retroperitoneal tumour.



Fig. 31.11: CT scan showing brain secondaries. Secondaries are the commonest malignant tumours of brain. Breast is the common site of primary.

Advantages of CT scan

- One to 2 mm sized sections are possible
- Amount of exposure to radiation is less
- More accurate, sensitive, and specific
- Small lesions are also detected
- CT guided biopsies are done at present, safely



Fig. 31.12: CT picture showing astrocytoma.

Disadvantages

- **Interpretation** by an experienced radiologist is important
- **Artefacts** can be present
- **Cost factor** and **availability**

Findings

- Extradural haematoma—*Biconvex lesion.*
- Subdural haematoma—*Concavoconvex lesion.*

Ultrasound and CT scan are conveyors of morphological information.

- Smooth margin in benign condition.
- Irregular margin in malignant condition.

Advantages of spiral CT scan

- Reduced scan time. Useful in children and critically ill-patients
- Imaging in both arterial and venous phases is possible
- Improved lesion detection. Missing a lesion is uncommon
- Multiplanar and 3-dimensional analysis like CT angiography, complex joint imaging, facial bone imaging is possible

High resolution CT *(HRCT)* is a CT technique used in chest scan where thin sections are taken to have better quality images.

MAGNETIC RESONANCE IMAGING (MRI)

Earlier, named as *Nuclear magnetic imaging*, the term is not used now.

It can be **Plain MRI** or **Contrast MRI**. Contrast agent is *Gadolinium,* given intravenously**.**

Principle

When patient is placed in an *external high magnetic field*, protons of hydrogen atoms rotate in phase with each other and gradually return to their original position releasing small amounts of energy which is detected by sensitive coils. Proton density and relaxation time are assessed by radiofrequency pulse and the computer generates a Gray scale image from this data.

T1 relaxation time is the time taken to return to original axis. *T1 images* are used to find out *normal anatomical details.* It has got high soft tissue discrimination. Here fluid (CSF) looks black.

T2 relaxation time is the time taken by the proton to diphase. It is used to assess *pathological processes. In T2 images* fluid looks white.

In proton density images fluid looks in between black and white.



Fig. 31.13: MRI showing spine tuberculosis. Note the lesion and vertebral collapse.



Fig. 31.14: MRI showing AV malformation.



Fig. 31.15: MRI picture, which shows extradural schwannoma.

Uses of MRI

- It is very useful in intracranial, spinal and musculoskeletal lesions including *joint pathologies.*
- It gives direct anatomical sections of the area, with lesions at a high resolution.
- **MR angiogram** is done without injecting IV contrast agents.
- **Cardiac MRI** is very useful.
- **Breast MRI** is used in multifocal recurrent cancers.
- **Magnetic resonance cholangiopancreatography** *(MRCP)* is a very useful noncontrast diagnostic tool which may replace diagnostic ERCP.
- **MR spectroscopy** is chemical analysis of elements in a tissue to differentiate between tumour, inflammation, and degeneration.

Advantages

- Artefacts are not common.
- More sensitive and specific than CT scan.

Contraindications

Patients with ***prosthesis in the body, metallic foreign bodies, pacemakers, cochlear implants, cranial aneurysm clips should never*** undergo MRI

Precaution

Before entering the MRI room, the patient and other personnel should remove all magnetically attractive materials

Disadvantages

- ***Availability*** and ***cost factor.***
- It is time consuming.
- Patient compliance is poor.
- It is not feasible in patients suffering from ***Claustrophobia***.
- It is not ideal in emergencies and critically ill patients.
- It is not useful in lung pathology and subarachnoid haemorrhage.

RADIONUCLIDE IMAGING

- It represents function of an organ than morphology.

Rays:

- α-particles are emitted by the natural radionuclides like radium, which are no longer used in medicine.
- β-particles are useful for therapy but not for diagnosis.
- γ-rays pass out of the body and so used for the diagnostic purpose.
- Mapping is done using sophisticated gamma camera

Technetium 99^m

- It is commonest radionuclide used (99- is mass number; m- metastable.)
- It is administered IV.
- Pure γ-rays emitter.
- Short half life.
- Widely used gamma ray detectors are specified to $Tc99^m$.

Uses

$Tc99^m$	labelled serum albumin is used to detect pulmonary emboli
$Tc99^m$	labelled phosphate is used to image bone
$Tc99^m$	labelled sulphur colloid is used to detect the functions of liver, spleen, bone marrow
$Tc99^m$	labelled HIDA (Hippuric immuno diacetic acid) or PIPIDA is used to study the functions of hepatocytes and biliary tract
$Tc99^m$	labelled DMSA (Dimercapto succinic acid) which is taken up by the renal cortical cells, is used in renal function tests
$Tc99^m$	labelled DTPA (Diphenyl triamine penta acetic acid) measures G.F.R
$Tc99^m$	labelled HMPAO (Hydroxy methyl propylamine oxime) is used in Alzheimer's disease and schizophrenia as it crosses the blood brain barrier

Other radionuclides used:

- Thallium 201 chloride for cardiac imaging
- Gallium 67 nitrate to detect tumours and inflammation
- I^{123}

Advantages	***Disadvantages***
Safer	Availability
Easier	Cost factor
No side effects	Not specific
	Fast half life

POSITRON-EMISSION TOMOGRAPHY (PET Scan)

It is a non-invasive diagnostic method to assess the biochemical and physiological status of a tissue.

It is used in complimentary with CT scan and MRI.

Two protons are used, they are positive electrons (*positrons*).

Most clinically used positron emitting radionuclides is fluoro-deoxyglucose (FDG), others are $^{82}Rb, ^{15}O, ^{13}N$.

Detectors used are Bismuth germanate (BGO) crystals or sodium iodide crystals.

Principle of *electronic collimation* is used to produce images from the radiation emitted from positron emitting tracers.

Uses

- To assess myocardial perfusion (^{82}Rb) and viability (FDG) study.
- Epilepsy—To localise temporal lobe epilepsy (FDG)
- Cancer imaging—Lung cancer (detection and staging).
- Colorectal cancer.
- Melanoma.
- Head and neck cancer and breast cancer.
- Musculoskeletal tumours.
- Thyroid cancer (I^{131}).

Advantage

Very specific.

Disadvantage

Very expensive and limited availability.

Note:

Most of the U/S pictures, CT and MRI pictures in this book are from Balmatta Scan Center, Mangalore, I am thankful to consultants Dr Raghavendra Bhat and Dr Ravichandra there.

Radioisotope studies are indicators of physiological processes

Chapter 32 Operative Surgery

A. Asepsis and Sterilisation

> *Bearing in mind that it is from the vitality of the atmospheric particles that all the mischief arises, it appears that all that is requisite is to dress the wound with some material capable of killing these septic germs, provided that any substance can be found reliable for this purpose, yet not too potent as a caustic.*
>
> **—Joseph Lister,** 1867

CHAPTER OUTLINE

- Sterilisation
- Disinfection
- Antisepsis
- Asepsis
- Different Methods of Disinfection/Sterilisation

STERILISATION

- It is freeing an article by removing or killing all bacteria, spores, fungi and viruses.

DISINFECTION

- It is killing of all bacteria, fungi and viruses but not spores.

ANTISEPSIS

- It is inhibition of growth of microorganisms.

ASEPSIS

- Asepsis means—organisms are prevented to access the patient or individual.

DIFFERENT METHODS OF DISINFECTION/ STERILISATION

Physical Agents

- ***Burning*** or ***incineration*** is used to disinfect contaminated articles like dressings.
- ***Hot-air oven***: Here temperature used is 160 to 180 degree for one hour.
- ***Boiling:*** It kills bacteria but not spores and viruses. Temperature is between 90 to 99 degree. It is used to disinfect syringes, utensils. It is not useful for gloves, rubber materials.
- ***Autoclave***: It is steam under pressure. Temperature attained is between 120-135 degree. It is sterilised for 20 minutes with 15 pounds/sq. inch pressure. It kills all organisms including spores. Completeness of sterilisation is confirmed by using specific gelatin protein which precipitates only in steam underpressure for 20 minutes. Green coloured strip turns to black if autoclave is complete *(signaloc)*. Surgical gloves, linen, cotton, dressings, surgical instruments are sterilised by this method. Sharp and plastic instruments cannot be sterilised by this method. Bacillus thermophilus spores are used to assess the completeness of the sterilisation in mass scale. Double autoclaving is done for instruments of orthopaedic or ophthalmic surgeries.
- *The Bowie-Dick* method is also used to check the completeness of sterilisation.
- ***Radiation:*** *Ionising type of radiation:* Atomic gamma radiation is used as commercial method to sterilise suture materials, disposable materials in packets. It is viable, safe and cheaper.
- *Non-ionizing radiation* either infrared radiation or ultraviolet radiation is used to reduce the bacteria in air, water. Bacteria and virus are vulnerable to ultraviolet rays below 3000Å. Exposure to eyes and skin can cause burn injury.

Materials	*Method of sterilisation*
All theatre appliances	Autoclave
Sharp instruments (scissors, needles, blades)	Glutaraldehyde 2%, lysol
plastic materials	
Endoscopes	Glutaraldehyde
Rubber equipments	Glutaraldehyde
Syringes	Autoclave, hot air oven, gamma radiation
Heart-lung machine	Ethylene oxide
Disposable articles	Gamma radiation
Operation theatre and rooms	Ideally by U-V radiation or by formaldehyde
Sera and biological materials	Filtration
Lab glassware	Hot-air oven
Ward, sick room, furniture	Formaldehyde, iodophor spray, glutaraldehyde
Clothes, bed sheets especially for burns patients	Autoclaving
Soiled dressings, materials, animal carcasses	Incineration, lysol, iodophors
Excreta	Lysol, iodophors
Cleaning of skin before surgery	Iodophors 2%, savlon, spirit
For cleaning infected wounds	Iodophors, acriflavine, savlon, H_2O_2
To remove slough from the wounds	EUSOL, H_2O_2
Before injection	Spirit is used to clean the skin
Cleaning the ward	Phenol, cresol, lysol
Hand wash	Chloroxylenol, savlon, spirit, iodophors
Bladder wash	0.1% potassium permanganate solution (Condy‘slotion), solution of acetic acid and silver nitrate
Water	Chlorination, potassium permanganate
Fruits, vegetables	Potassium permanganate



Fig. 32.1: Autoclave machine for sterilisation.

Chemical Agents

- ***Phenol:*** It is used as standard to compare the efficacy of other agents.
- ***Cresol*** is more powerful and nontoxic. 5% solution is used.
- ***Lysol*** is emulsified cresol with soap. 2% solution is effective.
- ***Chlorhexidine (hibitane***) is useful antiseptic.
- ***Hexachlorophane***: It is not used in infants and children because it can get absorbed through intact skin in this age group causing severe neurotoxicity.
- ***Dettol (chloroxylenol***) 5% solution is used.
- ***Cetrimide*** is cationic surfactant (cetavlon) 2% solution is used.
- ***Savlon*** is combination of cetrimide and hibitane. It is very commonly used antiseptic in operation theatres, wards.

Halogens

- Bleaching powder.
- Sodium hypochlorite.
- ***EUSOL: Edinburg University Solution*** contains sodium hypochlorite, boric acid and calcium hydroxide.
  EUSOL bath is dipping the ulcer bearing part in dilute EUSOL solution for 30 minutes 2-3 times a day.
- Iodine
- ***Iodophors:*** These are antiseptics and also sporicidals. They are non-irritant and do not stain skin. ***Povidone-iodine*** is a good example which is commonly used.
- ***Alcohols***: Ethyl or isopropyl alcohols are used.

Treat the patient as a whole, “Half a sheep is mutton”.

- ***Formaldehyde:*** It is useful to disinfect the rooms like operation theatre. It is effective at a high temperature and humidity of 80-90%. It is commonly used to fumigate the room. 500 ml of formalin with one litre of water is boiled to get formaldehyde vapour. Formaldehyde vapour can be created by adding potassium permanganate to the same solution. Room is kept closed for 12 hours.
- ***Glutaraldehyde (cidex 2%)*:** It is used to sterilise sharp instruments. Instrument should be dipped for 10 hours to achieve complete sterilisation. It is potent bactericide, sporicide, fungicide and viricide.
- ***Hydrogen peroxide (H_2O_2)*:** It is used as topical oxygen therapy. Because of its effervescence and release of nascent oxygen it removes the tissue debris. It is used to clean wounds, cavities, ulcers, as mouth wash and as ear drops to clear earwax.
- ***Acriflavine and proflavine*** are orange-red coloured dyes used as antiseptics. It is effective against gram-positive and few gram-negative organisms. It retains its activity in pus and body fluids.

Figs 32.2A and B: Operation theatre mop rack to keep 'used mops' during surgery after use.

B. Instruments

CHAPTER OUTLINE

- Cheatle's Forceps
- Sponge Holding Forceps
- Mayo's Towel Clip
- Artery Forceps
- Right Angle Forceps
- Kocher's Forceps
- Allis' Tissue Holding Forceps
- Babcock's Forceps
- Lane's Tissue Holding Forceps
- Morant-Baker's Appendix Holding Forceps
- Volkmann's Retractor
- Langenbeck's Retractor
- Czerny's Retractor
- Morris' Retractor
- Deaver's Retractor
- Doyen's Retractor
- Self-retaining Retractor
- Single Hook Retractor
- Plain Non-toothed Dissecting Forceps
- Toothed Dissecting Forceps
- Surgical Needles
- Needle Holder
- Joll's Thyroid Retractor
- Moynihan's Occlusion Clamp
- Payr's Crushing Clamp
- Desjardin's Choledocholithotomy Forceps
- Bake's Dilator
- Sinus Forceps
- Scissors
- Volkmann's Scoop
- Tracheostomy Tube
- Drains
- Foley's Catheter
- Malecot's Catheter
- Simple Red Rubber Catheter
- Lister's Urethral Dilator
- Ryle's Tube
- Infant Feeding Tube
- Kehr's 'T' Tube
- Proctoscope
- Flatus Tube

CHEATLE'S FORCEPS

- ♦ It is used to pick sterilised articles like instruments and drapes so that touching of the instruments is avoided while transferring them. It is kept dipped in antiseptic solutions. It does not have lock.



Fig. 32.3: Cheatle's forceps.

SPONGE HOLDING FORCEPS (RAMPLEY'S)

- ♦ It has got fenestrated, serrated, flat distal end. It is used to clean the operative field, to swab the cavities, to mop the oozing area, to hold gallbladder and cervix during surgeries, for blunt dissections, as ovum forceps.



Fig. 32.4: Sponge holding forceps.

MAYO'S TOWEL CLIP (FIG. 32.5)

- ♦ It is used to fix drapes in operative field.
- ♦ It is used to fix suction tubes, diathermy wires, laparoscopic cables in operative table.
- ♦ It is used to fix ribs in flail chest.

ARTERY FORCEPS (HAEMOSTAT)

Types

Based on size:

a. Small or mosquito artery forceps.
b. Medium sized artery forceps.

Anger is a short madness which often creates life-long tragedy.

c. Large artery forceps.

Based on shape:

a. Straight artery forceps.

b. Curved artery forceps.



Fig. 32.5: Mayo's towel clip



Figs 32.6A to C: Artery forceps: (A) Straight, (B) Curved, (C) Mosquito.

Features of Artery Forceps

Distal blades have transverse serrations which are well-apposed. Lock in the proximal part.

Uses

- To catch bleeding points
- To open the fascial planes in different surgeries
- To pass a ligature
- To hold fascia, peritoneum, aponeurosis
- To hold sutures
- To drain an abscess like a sinus forceps
- To hold gauze as peanut

RIGHT ANGLE FORCEPS

- It is used to dissect pedicles and to pass ligatures.

KOCHER'S FORCEPS

- It has got serrations in the distal blades and apposing tooth in the tip.
- It is used to hold pedicles, tough structures, cut ends of the muscles.
- It is used to hold gauze for blunt dissection, to hold resected bowel, to hold ribs during rib resection.



Fig. 32.7: Kocher's forceps.

ALLIS' TISSUE HOLDING FORCEPS

- Here distal blades are not apposing each other.
- Tip has got teeth in each blade which are apposing.
- It has got a lock on the proximal part.
- It is used to hold skin flaps, fasciae, aponeurosis, bladder wall.



Fig. 32.8: Allis' tissue holding forceps.

BABCOCK'S FORCEPS

- Its distal part of distal blades are curved with a triangular fenestra in it which allow soft tissues to bulge out. Tip is non-traumatic with transverse serrations on it. It has got a lock in the proximal part.



Fig. 32.9: Babcock's forceps.

- It is used to hold any part of the bowel, fallopian tubes, appendix, ureter, cord, etc.

LANE'S TISSUE HOLDING FORCEPS

- It has got thick, stout distal blades with oval fenestra in each blade.
- It has got apposing tooth in the tip.
- It has got a lock in the proximal part.



Fig. 32.10: Lane's tissue holding forceps.

- It is used to hold bulky and tough structures, to hold lymph nodes.
- It is also used as towel clip, as sponge holding forceps.

MORANT-BAKER'S APPENDIX HOLDING FORCEPS

- It is like Lane's forceps but with apposing serrations proximal to the tooth. These serrations give a good grip in mesoappendix while holding appendix in appendicectomy. Its use is replaced by Babcock's forceps.



Fig. 32.11: Morant-Baker's appendix holding forceps.

VOLKMANN'S RETRACTOR

- It is used to retract fasciae in soles and palms.



Fig. 32.12: Volkmann's retractor.

Retractors

- Superficial retractors
- Deep retractors
- Self-retaining retractors

LANGENBECK'S RETRACTOR

- It has got a long handle and a small solid blade. It is used in hernia surgery or any superficial surgeries to retract skin, fasciae and aponeurosis, etc.



Fig. 32.13: Langenbeck's retractor.

CZERNY'S RETRACTOR (HERNIA RETRACTOR)

- This retractor has got thick, small blade on one side and biflanged hook on the other side in opposite directions. It is used in surgeries like hernia, laparotomy especially during closure.



Fig. 32.14: Czerny's retractor.

MORRIS' RETRACTOR

- It may be single blade type or double blade type.
- It is used to retract abdominal wall.



Fig. 32.15: Morris retractor.

DEAVER'S RETRACTOR



Fig. 32.16: Deaver's retractor.

- It is a retractor with a broad, gently curved blade.
- It is used to retract liver, spleen and other abdominal viscera.

- It is atraumatic and gives adequate exposure of the surgical field.

DOYEN'S RETRACTOR

- It is used in pelvic surgeries.



Fig. 32.17: Doyen's retractor.

SELF-RETAINING RETRACTOR

- It has got different adjustable blades so as to retract abdominal wall and tissues during surgery (Balfour's retractor).



Fig. 32.18: Self-retaining retractor.

SINGLE HOOK RETRACTOR

- It is used to retract skin.



Fig. 32.19: Single hook retractor.

PLAIN NON-TOOTHED DISSECTING FORCEPS

- It is used to hold delicate structures like peritoneum, vessels, bowel, nerves, tendons (Fig. 32.20).

TOOTHED DISSECTING FORCEPS

- It is used to hold skin and tough structures.



Figs 32.20A to C: Dissecting forceps: (A) Non-toothed, (B and C) Toothed.

SURGICAL NEEDLES

Types

Based on the edge

- Round body needle
- Cutting needle
- Reverse cutting needle
- Taper cut needle
- Side-to-side flat—Hagedron needle

Based on curvature

- Straight needle
- Curved needle. Half circle; 5/8 circle, etc.

Based on Existence of the Eye

- ***Atraumatic needle*** is eyeless. Here suture material is attached to the needle by swaging. Size of the suture material and that of needle is same and so tissue trauma is less. Needle once used is disposed of (not reusable).
- ***Traumatic needle:*** It is eyed needle. Needle in the eye area is wider than the body of the needle and so tissue trauma is more. These needles are reusable.


Traumatic cutting type needle
Atraumatic needle
Reverse cutting needle with eye
Straight needle
Round-bodied needle

Fig. 32.21: Needles.

- *Round body needles* are used in soft structures like peritoneum, muscle, vessel, nerves, tendons, bowel, soft tissues.
- *Cutting needles* are used to suture skin, aponeurosis and tough structures.
- Reverse cutting needle is used to suture mucoperiosteum.

NEEDLE HOLDER

- Smaller distal blades with criss-cross serrations often with a groove in the middle are the features of a needle holder.



Fig. 32.22: Needle holder.

- It may be straight or curved. It may be available with different sizes. While holding a needle in a needle holder one should get a good control and good grip. This is achieved by placing the needle at the junction of proximal 2/3rd and distal 1/3rd. Needle holder should be held between thumb and ring finger.

JOLL'S THYROID RETRACTOR

- It is a self-retaining retractor specifically used for thyroid surgeries.



Fig. 32.23: Joll's thyroid retractor.

MOYNIHAN'S OCCLUSION CLAMP

- It has got long distal blades with longitudinal serrations.
- It may be straight or curved.
- It is non-traumatic, non-crushing type.
- It occludes lumen of the bowel/stomach and so prevents spillage of the content of the bowel.
- It also occludes the vessels in the wall of the bowel and so prevents bleeding during surgery.
- It is used during anastomosis of the stomach and other parts of the bowel.



Fig. 32.24: Moynihan's occlusion clamp.

PAYR'S CRUSHING CLAMP (GASTRIC)

- It is stout and heavy instrument with double lever in the handle.



Fig. 32.25: Payr's crushing clamp.

- It crushes the bowel once applied. So before applying it, line of resection of stomach/bowel should be assessed properly. It is applied to the part which is removed. Viability of the bowel is lost once it is applied.
- It is used in gastrectomy and resection and anastomosis of the bowel.

DESJARDIN'S CHOLEDOCHOLITHOTOMY FORCEPS

- It has got long distal blades with smooth serrations and fenestra in the tip. It does not have lock and so accidental damage of CBD mucosa or crushing of the CBD stone are avoided.



Fig. 32.26: Desjardin's choledocholithotomy forceps.

- It is used for choledocholithotomy (removal of CBD stones).

BAKE'S DILATOR

- It is long malleable metallic instrument with club at the terminal end.

Surgery is always second best; if you can do something else, its' better.—**John Kirklin**

- It is used to assess the CBD, duodenal papilla for patency or block.



Fig. 32.27: Bake's dilator.

SINUS FORCEPS (LISTER's)

- It has got straight, long blades with serrations in the tip. It does not have a lock.
- It is used to drain pus from abscess cavity (Hilton's method). It is called as sinus forceps because it was initially originated to pack the sinus cavities. It is less traumatic.
- Sinus forceps has no lock; no serrations; broad tip; blunt.



Fig. 32.28: Lister's sinus forceps.

SCISSORS



Fig. 32.29: Scissors.

VOLKMANN'S SCOOP

To scoop cavities, ulcer bed, granulation tissues.

On either side different sized scoops are present.



Fig. 32.30: Volkmann's scoop.

TRACHEOSTOMY TUBE

- ***Fuller's bivalved tracheostomy tube***: It has got outer tube and inner tube. Outer tube is biflanged and so insertion is easier. Inner tube is longer with an opening on its posterior aspect. Inner tube can be removed and reinserted easily whenever required.
- ***Jackson's tracheostomy tube***: It has got outer tube, inner tube and an obturator.
- Red-rubber tracheostomy tube.
- PVC tracheostomy tube.

Modern tracheostomy tubes are made of plastic. They are soft, least irritant and disposable. They have inflatable cuff which makes it easier to give assisted ventilation. Cuff should be deflated at regular intervals to prevent tracheal pressure necrosis (For assisted ventilation, endotracheal, tube can be kept for 7 days. Beyond that period, patient needs tracheostomy for further ventilation).



Figs 32.31A and B: Tracheostomy tube: (A) Fuller's, (B) Jackson's tracheostomy tube.

Indications for tracheostomy

- In head, neck and facial injuries
- Tetanus
- Tracheomalacia after thyroidectomy
- Laryngeal oedema/spasm
- Major head and neck surgeries like commando's operation, block dissection, etc.

DRAINS

A drain is a created channel which allows any fluid collected, to come out after closure of the main wound.

Types

- *Corrugated rubber drain:* It drains by capillary action and gravity. It is cheaper and technically easier. But it allows soakage of dressings and causes discomfort to the patient.
- *Tube drains*
  - Malecot catheter can be used as a tube drain.
  - Penrose soft latex rubber tube.
  - Multiple perforated tubes.



Figs 32.32A to C: Drains: (A) Corrugated rubber drains, (B) Multiple perforated drains, (C) Tube drain.

Advantages of tube drains

- Quantity of fluid like bile, pus can be measured
- It can be kept for longer time
- Skin excoriation will not occur
- Patient remains more comfortable
- Infection rate is less
- Removal is easier
- Dye can be injected and cavity or communication can be assessed using 'C-ARM'

- *Closed suction tube drain system.*
- *Glove drain.*
- *Wick drain* is a gauze drain to drain pus, discharge, etc.
- *Sump drain:* This is a type of drain where parallel air vent prevents the adjacent soft tissues from being sucked into the drain when negative pressure is applied.

Advantages of sump drain

- No drain blockade
- Resists collapse of the structure when suction is applied.

Uses of sump drain

- Collection of irritant discharges (enterocutaneous fistula)
- Collection of secretions having activated enzymes (high small bowel, pancreatic fistula)
- Draining proximal stump in TEF with esophageal atresia to prevent aspiration



Fig. 32.33: Suction drain used in thyroid surgery.



Fig. 32.34: Romovac suction drain. Here suction is created by pressing the suction corrugation. There is a sharp metallic introducer to pass the tube into the required area after puncturing the skin. It is used for thyroidectomy, mastectomy, radical dissection, wide excisions, flap surgeries, etc.

Classification of Drain Systems

- ***Open (static) drain:*** For example, corrugated drain, penrose drain. Infection rate is higher.
- ***Closed siphon drain:*** Here drain is connected to a sterile bag with or without one-way valve. It reduces the infection.
- ***Closed suction drain:*** Here negative pressure of—100 to 500 mmHg is used to create vacuum to drain the secretions.
- ***Sump suction drain:*** Here negative suction with a parallel air-vent is used to prevent the adjacent soft tissues being sucked into the lumen of the drain.
- ***Under water seal drain*** to drain pleural space.

Indications for drains

- In drainage of an abscess
- In bleeding surgical conditions like trauma, peroperative bleed
- In haemo, pyo or pneumothorax
- In acute abdominal conditions like peritonitis, haemoperitoneum
- In major abdominal surgeries like of pancreas, biliary tree, stomach, etc.
- In thyroid surgery
- In hydrocele surgery

Problems in Drains

- Infection can occur through the drain.
- Displacement.
- It may not drain adequately and can give a false information.
- It may interfere with healing process inside.

Presently keeping a drain itself is a questioned debate and controversy all over.

Older dictum was 'when in doubt keep a drain and the surgeon can sleep happily'—is questioned at present.

DRAINS IF NOT USED PROPERLY MAY BE COUNTER-PRODUCTIVE.

> *The postoperative treatment is as essential as the operation and the surgeon is as much responsible for the postoperative treatment as for the operation.*
> **— Roscoe C Giles**

FOLEY'S CATHETER

Refer Urology



Fig. 32.35: Foley's catheter.

MALECOT'S CATHETER

Refer Urology



Fig. 32.36: Malecot's catheter.

SIMPLE RED RUBBER CATHETER

Refer Urology



Fig. 32.37: Red rubber catheter.

LISTER'S URETHRAL DILATOR

It has got olive tip and it is used to dilate stricture urethra. Other dilators are Clutton's dilator and filiform bougies.



Fig. 32.38: Lister's urethral dilator.

RYLE'S TUBE

It is one meter long and is made of red rubber or plastic.

It has got *three lead shots* in the tip which makes it radio-paque. It also facilitates easy passage of the tube through the oesophagus.

It has got markings at different levels:

- At 40 cm distance, at the level of gastro-oesophageal junction.
- At 50 cm distance, at the level of body of the stomach.
- At 60 cm distance, at the level of the pylorus.
- At 65 cm distance, at the level of the duodenum.



Fig. 32.39: Ryle's tube.

Indications

- Diagnostic:
- For gastric function tests—to assess free acid and total acid
- Hollander's test for completion of vagotomy
- To diagnose tracheo-oesophageal fistula
- Baid test for pseudocyst of the pancreas
- Therapeutic:
- In acute abdominal conditions like peritonitis/ obstruction
- In abdominal trauma
- After abdominal surgeries
- In pyloric stenosis
- In upper GIT bleeding
- In paralytic ileus
- For feeding purpose in conditions like comatose patients, faciomaxillary injuries, major head and neck surgeries

INFANT FEEDING TUBE

- There are *no lead shots* and markings on the tube.
- It is used for feeding purpose in infants who is under coma, with faciomaxillary injuries and anorexia.



Fig. 32.40: Infant feeding tube.

KEHR'S 'T' TUBE

- It is used after opening CBD (choledochotomy). CBD is closed with 'T" tube placed in the CBD.
- It is made up of latex or red rubber.



Fig. 32.41: Kehr's 'T' tube.

- 'T' tube has got horizontal part which is placed in the CBD and vertical part which is allowed to come out, to drain bile. Amount of bile draining daily is measured.

Before removal of the "T" tube, patency of CBD should be confirmed.

It is done by following methods:

- The vertical limb is clamped (done in 12-14 days) and the patient is observed for development of pain, fever and jaundice in 24 hours. If normal, then one can presume that there is no obstruction in the CBD.
- Water soluble iodine dye is injected through the tube to visualize biliary tree and free flow of dye into the duodenum. (postoperative 'T' tube cholangiogram). It is done in 14 days which is the time required to develop fibrous track. Once there is free flow, tube is removed and track gets closed on its own.

PROCTOSCOPE

(Refer Rectum and Anal Canal)



Fig. 32.42: Proctoscope.

FLATUS TUBE



Fig. 32.43: Flatus tube

It is made up of India rubber, 45 cm in length. There is one opening in the tip and another on the side proximal to the tip. (Urinary catheter like red rubber catheter has no opening in the tip, only side opening is present). It is used in sigmoid volvulus to decompress and derotate; in paralytic ileus; in subacute intestinal obstruction. It is passed per anal into the recto-sigmoid area. Proximal end is connected to water container to observe the quantity of air bubble which signifies the amount of gas getting deflated.

C. Suture Materials

CHAPTER OUTLINE

- Classification I
- Classification II
- Classification III
- Classification IV
- Classification V

Features of ideal suture material

- Adequate tensile strength
- Good knot holding property
- Should be least reactive
- Easy handling property
- Should have *less memory*
- Should be easily available and cost effective

CLASSIFICATION I

Absorbable Suture Materials

- **Plain catgut** is derived from submucosa of jejunum of sheep.
  - It is yellowish white in colour.
  - It is absorbed by inflammatory reaction and phagocytosis—absorption time is 7 days.
  - It is used for subcutaneous tissue, muscle, circumcision in children.
- **Chromic catgut** is catgut with chromic acid salt.
  - It is brown in colour.
  - Its absorption time is 21 days.
  - It is used for suturing muscle, fascia, external oblique aponeurosis, ligating pedicles, etc.
- **Vicryl** (Polyglactic acid):
  - It is synthetic absorbable suture material.
  - It gets absorbed in 90 days.
  - Absorption is by hydrolysis.
  - It is violet in colour (braided).
  - It is multifilament and braided.
  - It is very good suture material for bowel anastomosis, suturing muscles, closure of peritoneum.
- **Dexon** (Polyglycolic acid) is synthetic absorbable suture material like vicryl. It is creamy yellow in colour (braided).
- **Maxon** (Polyglyconate) monofilament.
- **PDS (P**oly **D**ioxanone **S**uture material) is absorbable suture material. It is creamy in colour with properties like vicryl. It is costly but better suture material than vicryl.
- **Monocryl** (Polyglecaprone) monofilament.
- **Biosyn** (Glycomer) monofilament.

Uses of absorbable suture materials

- In bowel anastomosis like gastrojejunostomy, resection and anastomosis. Vicryl is used
- In cholecystojejunostomy (CCJ), choledocho-jejunostomy (CDJ), pancreaticojejunostomy. Vicryl is used
- In suturing muscle, fascia, peritoneum, subcutaneous tissue, mucosa
- In ligating pedicles. 1-zero chromic catgut or vicryl are used, e.g. ligation of pedicles during hysterectomy
- In circumcision, usually 3-zero plain or chromic catgut are used

Absorbable suture materials should not be used for suturing tendon, nerves, vessels (vascular anastomosis).

Nonabsorbable Suture Materials

- ***Silk*** is natural, multifilament, braided, non-absorbable suture material derived from cocoon of silkworm larva. It is black in colour. It is coated suture material to reduce capillary action.
- ***Polypropylene*** (Prolene) is synthetic, monofilament suture material. It is blue in colour. It has got high memory. (*Memory of suture material* is recoiling tendency after removal from the packet. Ideally suture material should have low memory.) (Prolene mesh used for hernioplasty is white in colour).
- ***Polyethylene*** (Ethylene) is synthetic monofilament nonabsorbable suture material. It is black in colour.
- ***Cotton*** is twisted multifilament natural nonabsorbable suture material. It is white in colour.
- ***Linen*** is derived from bark of cotton tree.
- ***Steel, polyester, polyamide, nylon*** are other nonabsorbable suture materials.

Uses of nonabsorbable suture materials

- In herniorrhaphy for repair
- For closure of abdomen after laparotomy
- For vascular anastomosis (6-zero), nerve suturing, tendon suturing
- For tension suturing in the abdomen
- For suturing the skin

CLASSIFICATION II

Natural

- Catgut.
- Silk.
- Cotton.
- Linen.

Synthetic

- Vicryl, dexon, PDS, maxon.
- Polypropylene, polyethylene, polyester, polyamide.

CLASSIFICATION III

- **Braided:** Polyester, polyamide, vicryl, dexon, silk.
- **Twisted:** Cotton, linen.

CLASSIFICATION IV

- **Monofilament**: Polypropylene, polyethylene, PDS, catgut, steel.
- **Multifilament**: Polyester, polyamide, vicryl, dexon, silk, cotton.

CLASSIFICATION V

- Coated.
- Uncoated.

Numbering of Suture Material

2-Thick. For pedicle ligation.
1-
0-zero.
1-zero.
2-zero. For bowel suturing.
3-zero.
4-zero.
5-zero. For vascular anastomosis.
6-zero.
7-zero.
8-zero.
9-zero. For ophthalmic surgery. Requires operating microscope.

Fig. 32.44: Photo showing different types of suture materials (with pack).

Types of suturing

- Continuous suturing
- Interrupted simple suturing
- Interrupted mattress suturing
- Subcuticular suturing
- Horizontal tension suturing
- Vertical tension suturing



Fig. 32.45: Types of suturing.

Types of knots

- Reef knot
- Granny knot
- Surgeon's knot



Fig. 32.46: Types of knots.

Sadness is a from of fatigue.

D. Diathermy (Electrocautery)

It is the method to control bleeding or to cut the tissues during surgery.

TYPES

Based on type of current used:

- Unipolar cautery.
- Bipolar cautery. It is safer because its effect is seen only in between electrode points. Adjacent tissues will never get damaged.

Based on type of action:

- ***Coagulation cautery*** which causes haemostasis by tissue coagulation. Here temperature is 100 degree (blue switch).
- ***Cutting cautery***: Here temperature is 1,000 degree which disintegrate the tissues. It is not haemostatic (yellow switch).
- ***Blended current*** is combination of both coagulation and cutting.

Differences Between Unipolar and Bipolar Cautery

Unipolar cautery	*Bipolar cautery*
• Can be used for both coagulation and cutting	• Only for coagulation
• Conducting plate should be kept	• No need
• Cannot be used in patient with artificial valves	• Can be used
• Should be careful about adjacent tissues	• Adjacent tissues will never get damaged

Uses

- For coagulation of bleeders during surgery to achieve haemostasis.
- To cut muscles, fascia, etc.
- It is essential for laparoscopic surgical procedures. Bipolar is commonly used.
- It is used to remove small cutaneous lesions, to control bleeding duodenal ulcer.

Disadvantages

- Infection.
- Cauterisation of normal tissues.
- Problem of explosion.
- Diathermy burn to the patient at the site where diathermy plate is kept.
- Burn injury or electrical shock to surgeon and assisting personnel.

Precautions

- Proper earthing.
- Avoid loose contact of electrodes.
- It should be kept off when not in use during procedure.



Fig. 32.47: Diathermy machine with plate, foot switch for use.

E. Operative Procedure

CHAPTER OUTLINE

- Abdominal Incisions
- Vasectomy
- Circumcision
- Hydrocele
- Inguinal Hernia
- Appendicectomy
- Thyroidectomy
- Tracheostomy
- Cryosurgery
- Lasers in Surgery
- Staplers in Surgery
- Nasojejunal Tube Feeding
- Gossypiboma

ABDOMINAL INCISIONS

Principles

- Incision should be long enough for a good exposure.
- Splitting the muscle is better than cutting, except rectus muscle.
- Avoid cutting nerves and vessels in the abdominal wall.
- Retract muscle, abdominal organs towards the neurovascular supply.
- Insert a drainage tube through a separate incision.
- Transverse incisions are better than vertical incisions.
- Close the wound layer by layer.

Requirements

- Accessibility
- Extensibility
- Security

Factors affecting the strength of the scar

- Type of surgery (acute abdomen, surgery for malignancy, major surgery)
- Obesity
- Pregnancy
- Straining
- Cough
- Ascites
- Nutrition
- Diabetes
- Immunosuppression
- Type of incision

Complications of Abdominal Incision

- Wound infection.
- Burst abdomen.
- Fistula formation.
- Wound pain.
- Incisional hernia.
- Adhesion and its complication.


1
2
3
4
5
6
7
1. Rt subcostal incision
2. Lt subcostal incision
3. Upper midline
4. Rt upper paramedian
5. Subumbilical
6. Lt lower paramedian
7. Lower midline
8
9
10
11
12
13
14
15
16
8. Lt thoracoabdominal
9. Roof-top-(Chevron) incision
10. Upper horizontal
11. Lt lumbar sympathectomy incision
12. Lower horizontal
13. Lanz incision
14. McBurney's incision
15. Pfannenstiel incision
16. Incision for inguinal hernia

Fig. 32.48: Different incisions in the abdomen.

Different abdominal incisions are:

- Upper midline.
- Upper right paramedian.
- Upper left paramedian.
- Kocher's incision (right subcostal).
- Left subcostal.
- Bucket handle.
- Upper horizontal.
- Thoracoabdominal.
- Subumbilical.
- Incision for lumbar sympathectomy.
- Lower midline.
- Lower right or left paramedian.
- Incisions for appendicectomy—McBurney's, Rutherfold Morrison's, Lanz, laparoscopic.

Surgery is an irreversible repair but often it can be irreversible damage also !!!

- Pfannenstiel incision.
- Lower horizontal.
    - Upper incisions are always better.
    - Horizontal incisions are better.
    - Paramedian is better than midline.

VASECTOMY

Indications

- Family planning (parents should have two healthy children, consent should be obtained).
- After prostatectomy, vasectomy is done to prevent retrograde infection of testes.

Procedure

After cleaning and draping, 2 ml of 1% injection xylocaine (local anaesthetic) is injected to the root of the scrotum on the antero-lateral aspect.

Skin, external and internal spermatic fasciae are incised, cord is held with Allis forceps. Thick, firm, vas is dissected, two artery forceps are applied. A small piece of vas is excised and cut ends are ligated with silk or thread (nonabsorbable). Skin is sutured. Procedure is repeated on the other side.

Advice

To avoid sexual contact or to use contraception for 3 months.

Complications

- Haematoma
- Haematocele
- Infection
- Pyocele
- Sperm granuloma
- Recanalisation occurs rarely but dangerous

- When there is hernia or hydrocele, vasectomy is done along with specific procedures for hernia or hydrocele.
- ***No scalpel vasectomy,*** using specialised instruments is becoming popular. Procedure does not require any suturing.



Figs 32.49A and B: No scalpel vasectomy instruments and technique.

CIRCUMCISION

Indications

- Religious.
- Phimosis.
- Paraphimosis after doing initial dorsal slit.
- Balanitis and balanoposthitis (common in diabetics).
- Early carcinoma of prepuce or glans penis—both diagnostic as well as therapeutic purpose.
- Certain sexually transmitted diseases, e.g. herpes infection.

Procedure

In children, it is done under G/A. In adults, it is done under local anaesthesia.

After cleaning and draping, LA (1% lignocaine *(plain)* is injected circumferentially near the root of the penis) is given (ring block). Dorsal skin is cut up to the corona and later circumferentially and ventrally. The skin is cut with inner layer. Care is taken to see that optimum (less) skin is cut ventrally to prevent the occurrence of *chordee*. Frenular artery as well as dorsal vein is transfixed and ligated ventrally using chromic catgut (2-0 or 3-0). Small bleeders are also ligated. Skin is apposed to the cut edge of corona using interrupted chromic catgut sutures.

Postoperatively, antibiotics and analgesics are given.

Complications

- Reactionary haemorrhage due to slipping of ligature from frenular artery and dorsal vein.
- Infection.
- Stricture urethra near the external meatus in *children.*
- Chordee due to removal of excess skin on the ventral aspect.
- Rarely priapism can occur.

HYDROCELE

Types of Surgery

- Subtotal excision.
- Partial excision and eversion (Jabouley's operation).
- Evacuation and eversion.
- Lord's plication.
- Sharma and Jhawers technique.

Procedure

- Under G/A or spinal or L/A, after cleaning and draping, vertical incision of about 6-8 cm in length is made over the scrotum, anteriorly 1 cm lateral to the median raphe.
- Skin, dartos, external spermatic fascia, internal spermatic fascia are incised.

  Bluish hydrocele sac is identified, i.e. parietal layer of the tunica vaginalis of testis.

  Fluid is evacuated using trocar and cannula. Sac is opened.
- *If the sac is small, thin and contains clear fluid,* either *Lord's plication,* i.e. tunica is bunched into a "ruff" by placing series of multiple interrupted chromic catgut sutures so as to make the sac form a fibrous tissue which is relatively avasular and so haematoma will not occur, or *evacuation and eversion* of the sac behind the testis (after eversion, everted sac is sutured with chromic catgut by continuous sutures) is done.
- *If the sac is thick, in large hydrocele and chylocele***,** *subtotal excision of the sac* is done (as tunica vaginalis is reflected on to the cord structures and epididymis posteriorly, total excision of the sac leads to orchidectomy with division of cord).
- Often the sac is excised partially and eversion is done, which is called as *Jabouley's* operation.



Fig. 32.50: Trocar and cannula used for tapping hydrocele. It prevents spillage of fluid.

- After evacuation, the sac with the testis is placed in a newly created pocket between the fascial layers of the scrotum *(Sharma and Jhawer's technique).*
- *Aspiration must be avoided as much as possible* as it is only a temporary measure (recurrence occurs very early) and chances of haematocele, infection are higher.
- A drain is placed near the root of the scrotum on the lateral aspect because, it becomes the most dependent portion once scrotal support is given. Scrotal support is given to reduce the scrotal oedema.
- Wound is closed in layers.
- Drain is removed in 48 hours.

Surgeries for hydrocele

- Subtotal excision of the sac
- Jabouley's operation
- Evacuation and eversion
- Lord's plication
- Sharma and Jhawer's technique

Complications of surgery

- Reactionary haemorrhage
- Infection
- Pyocele
- Sinus formation
- Recurrent hydrocele

Conditions where orchidectomy is done in hydrocele

- Pyocele with testicular destruction
- Clotted haematocele with testicular destruction

INGUINAL HERNIA

Surgery is the treatment of choice for inguinal hernia.

In infants, whether it is hernia or hydrocele, only *herniotomy* is done through inguinal approach *(Michaelis plank operation*).

In adults: It includes *herniotomy,* i.e. excision of hernial sac and *herniorrhaphy* (strengthening of the posterior wall of inguinal canal either by repair or mesh).

1. Herniotomy

*Anaesthesia***:** Spinal or G/A

Procedure: After cleaning and draping, skin is incised 1.25 cm above and parallel to the medial two-third of inguinal ligament. Two layers of superficial fascia (outer Camper's fascia and inner Scarpa's fascia) are incised. External oblique aponeurosis is incised. Upper leaf is reflected above and lower leaf is reflected downwards to visualise and expose the inguinal ligament. Ilioinguinal nerve is safeguarded. Cremasteric muscle is opened. Cord structures are dissected. Sac which is anterior and lateral to cord is identified and is pearly white in colour. Dissection is usually started from the fundus and extended towards the neck which is identified by extraperitoneal fat. The neck is narrow and is lateral to inferior epigastric artery. Sac is opened at the fundus. Finger is passed to release any adhesions.

Sac is twisted so as to prevent the contents from coming back. It is transfixed using absorbable suture material (chromic catgut 2-0) and is excised distally.

2. Modified Bassini's Herniorrhaphy

Conjoined tendon and inguinal ligament are approximated using interrupted nonabsorbable monofilament sutures [polypropylene (prolene, blue in colour)]; medial most stitch is taken from the periosteum of pubic tubercle *(called as key or Bassini's stitch)*; external oblique is closed and other layers are closed.

Complications of herniorrhaphy

- Haemorrhage
- Haematoma
- Infection
- Haematocele
- Postherniorrhaphy hydrocele
- Hyperaesthesia over the medial side of inguinal canal due to injury to ilioinguinal nerve
- Recurrence
- Osteitis pubis

Hernioplasty

Prolene mesh is used for hernioplasty (white in colour). Other materials which can be used are Dacron, tensor fascia lata, skin.

Relation of sac to the cord

- Indirect inguinal hernia—anterolateral
- Direct inguinal hernia—posteromedial

APPENDICECTOMY

Approaches:

- ***Grid-iron incision*** *(McBurney's incision)*: Incision is placed perpendicular to the right spino-umbilical line at the McBurney's point, i.e. at the junction of lateral one-third and medial two-third of spino-umbilical line.
- ***Rutherford Morison muscle*** cutting incision *(Cut upwards and laterally*).
- ***Lanz crease incision*** centering at McBurney's point-cosmetically better.
- ***Right lower paramedian*** incision—when in doubt or when there is diffuse peritonitis.
- ***Laparoscopic approach:*** Becoming popular.
- ***Fowler-Weir approach:*** Medial muscle cutting incision.

Procedure

Under general anaesthesia, skin is incised. Two layers of superficial fascia are cut. External oblique aponeurosis is opened in the line of incision. Internal oblique and transverse muscles are split in the line of fibres. Peritoneum is opened in the line of incision. Caecum is identified by taeniae, and ileo-caecal junction. Omentum when adherent is separated. Appendix is held with Babcock's forceps. Mesoappendix with appendicular artery is ligated. Using thread or silk, a purse-string suture is placed around the base of the appendix. Base of the appendix is crushed with artery forceps and transfixed using vicryl (absorbable). Appendix is cut distal to the suture ligature and removed. Stump is cleaned with antiseptics. Purse-string suture is tightened so as to bury the stump.

In difficult cases *Retrograde appendicectomy* can be done. In presence of pus or burst appendix, the peritoneal cavity is drained.

Postoperatively, IV fluids, antibiotics are given. Once bowel sounds are heard, oral diet is started.

Complications after Appendicectomy

- Paralytic ileus.
- Reactionary haemorrhage due to slipping of ligature of the appendicular artery.
- Residual abscess (pelvic, paracolic, local, subdiaphragmatic).
- Pylephlebitis (Portal pyaemia).
- Adhesions, kinking and intestinal obstruction.
- Right inguinal hernia *(direct)* due to injury to ilio inguinal nerve.
- Wound sepsis.
- Faecal fistula.

THYROIDECTOMY

Types

- ***Hemithyroidectomy*****:** Along with removal of one lobe, entire isthmus is removed. It is done in benign diseases of only one lobe.
- ***Subtotal thyroidectomy:*** Commonly done in toxic thyroid either primary or secondary and also often for nontoxic multinodular goitre. Here about 8 grams or a tissue, size of pulp of the finger is retained at the lower pole, one or both sides and rest of the thyroid gland is removed.
- ***Partial thyroidectomy*** is removal of the gland in front of trachea after mobilisation. It is commonly done in nontoxic multinodular goitre.
- ***Near total thyroidectomy*****:** Here both lobes, except the lower pole which is very close to recurrent laryngeal nerve and parathyroid is removed. It is done in case of papillary carcinoma of thyroid.
- ***Total thyroidectomy*****:** Entire gland is removed. It is done in case of follicular carcinoma of thyroid, medullary carcinoma of thyroid.

Procedure

Position: Under general anaesthesia patient is put in supine position, with neck hyperextended by placing a sand bag under shoulder—with table tilt of 15 degree head up to reduce venous congestion.

Incision: Horizontal crease incision is done, two finger breadth above the sternal notch, extending from sternomastoid of one side to the other.

Skin and platysma are incised—upper flap raised up to thyroid cartilage, lower flap up to sternoclavicular joint. Deep fascia is opened vertically in the midline. Strap muscles are retracted or cut in between two Kocher's forceps. Pretracheal fascia is opened to mobilise the thyroid. First, short stout middle thyroid vein is ligated, then superior thyroid pedicle is ligated close to the gland so as to avoid injury to external laryngeal nerve. Inferior thyroid artery is ligated away from the gland so as to avoid injury to recurrent laryngeal nerve. Mobilised gland is removed. Bed is sutured with catgut so as to prevent bleeding. Drain is placed. The wound is close in layers.

Thyroid steal: Patient with thyrotoxicosis is taken to operation theatre daily for few days before doing surgery so as to reduce the anxiety of the patient.

Complications of Thyroidectomy

1. ***Haemorrhage***: May be due to slipping of ligatures, either of superior thyroid artery or other pedicles. It causes tachycardia, hypotension, breathlessness and compression over the trachea which inturn may cause severe stridor, respiratory obstruction. As a first aid, immediate release of sutures including that of deep fascia has to be done and pressure over the trachea is released. Then patient is shifted to operation theatre and under general anaesthesia exploration is done and bleeders are ligated. Blood transfusion may be required.
2. ***Respiratory obstruction*:** It may be due to haematoma (if it is so, the haematoma has to be evacuated), or due to laryngeal oedema. For laryngeal oedema, *immediate emergency endotracheal intubation* is done along with steroid injections. Often emergency tracheostomy may be required as a life-saving procedure.
3. ***Recurrent laryngeal nerve palsy*:** It can be transient or permanent. Transient is 3% common. They usually recover in 3 weeks to 3 months. Often they require steroid supplement and speech therapy. Permanent paralysis is rare.
4. ***Hypoparathyroidism*** is rare (0.5%). Mostly it is temporary due to vascular spasm of parathyroid glands, occurs in 2nd-5th postoperative day. Presents with weakness, +ve Chvostek's sign, carpopedal spasm, convulsions. Serum calcium estimation is done and then 10 ml of 10% calcium gluconate—is given IV 8th hourly. Later supplemented by oral calcium 500 mg 8th hourly. After 3-6 weeks, patient is admitted, drug is stopped and serum calcium level is repeated.
5. ***Thyrotoxic crisis* (Thyroid storm):** Occurs in a thyrotoxic patient inadequately prepared for thyroidectomy and rarely a thyrotoxic patient presents in a crisis following an unrelated operation or stress. They present in 12-24 hours with severe dehydration, circulatory collapse, hypotension, hyperpyrexia and often cardiac failure.

   Treatment is injection hydrocortisone, oral antithyroid drugs, tepid sponging of whole body, beta blocker injection, oral iodides, large amount of IV fluids for rehydration, digitoxin. Cardiac monitor, often ventilator support with close observation is necessary. It has got high rate of mortality with critical period of 72 hours. Correction of fluid and electrolyte imbalance and cardiac monitoring are the important aspects of management.
6. ***Injury to external laryngeal nerve*** causes weakness of cricothyroid muscle leading to alteration in pitch of voice.
7. ***Hypothyroidism:*** Revealed clinically after 6 months.
8. Wound infection, stitch granuloma formation.
9. Keloid formation.

TRACHEOSTOMY

Types

- Emergency tracheostomy.
- Elective tracheostomy.

Tracheostomy Tube

- ***Fuller's bivalved tracheostomy tube***: It has got outer tube and inner tube. Outer tube is biflanged and so insertion is easier. Inner tube is longer with an opening on its posterior aspect. Inner tube can be removed and re-inserted easily whenever required.
- ***Jackson's tracheostomy tube***: It has got outer tube, inner tube and an obturator.
- Red rubber tracheostomy tube.
- PVC tracheostomy tube.

Modern tracheostomy tubes are made of plastic. They are soft, least irritant and disposable. They have inflatable cuff which makes it easier to give assisted ventilation. Cuff should be deflated at regular intervals to prevent tracheal pressure necrosis. (For assisted ventilation endotracheal tube can be kept for 7 days. Beyond that period patient needs tracheostomy for further ventilation.)

Indications for tracheostomy

- In head, neck and facial injuries
- Tetanus
- Tracheomalacia after thyroidectomy
- Laryngeal oedema/spasm/surgeries
- Major head and neck surgeries like commando's operation, block dissection, etc.
- ICU ventilation after 7 days



Fig. 32.51: Tracheostomy tube with inflation part and syringe (Inflated with air)

Surgery is not just cutting, but it is an art; it is not only an art but also a merciful art.



Fig. 32.52: Figure showing the position of tracheostomy tube.



Fig. 32.53: Vertical midline or transverse incisions are used for tracheostomy. ***Vertical midline*** extends from cricoid cartilage to sternal notch. It is used both in emergency and elective tracheostomy and commonly used incision. It gives rapid access with less dissection but leads into poor scar. ***Transverse incision*** can be used in elective tracheostomy. It is placed two finger breadths above the sternal notch with a length of about 5 cm transversely. It has got a better cosmetic scar.

Technique of Tracheostomy

Neck of the patient is hyperextended by placing sand bags under the shoulder. Vertical (midline) or horizontal incision is made. Deep fascia is opened. Strap muscles are retracted laterally. Isthmus is divided or retracted below. 2nd and 3rd tracheal rings are opened and circular opening is made. Tracheostomy tube is placed. It is tied around the neck.

Note:
Endotracheal tube can be kept *in situ* only for 7 days.



Fig. 32.54: Advanced secondaries in neck with tracheostomy tube to control respiratory stridor.

Tracheostomy Care

- Regular suctioning of the tube.
- Cleaning of tracheostomy tube.
- Humidification of the inspired air.

Complications of tracheostomy

- Tracheal stenosis
- Bleeding
- Aspiration
- Pneumothorax
- Surgical emphysema in the neck
- Mediastinal emphysema
- Tracheostomy dependency

CRYOSURGERY

- It is the destruction of tissues by ***controlled cooling.***
- System contains an automatic defrosting device with a cryoprobe.

Gases used are:

- Nitrous oxide—minus 98°C temperature.
- CO_2—minus 60°C.
- Liquid N_2—minus 180°C.
- Freon—minus 190°C.

Commonly nitrous oxide is used as it is easily available, cheaper and achieves optimum temperature required for different procedures.

Mode of Action

- It produces intracellular crystallisation, dehydration and denaturation of proteins and cell death.
- It causes the obliteration of microcirculation and so cell death.

Indications

- To remove warts and lesions in the skin.
- Cryotherapy for piles.
- For chronic cervicitis.

Advantages

- Relatively bloodless and painless.
- Adequate control of extent and depth in freezing.
- Equally effective.

Disadvantages

- Infection.
- Discharge from the site.

LASERS IN SURGERY (Light Amplification Stimulated Emission of Radiation)

Molecules are placed in a compact area and power is passed through this so as to activate the molecules. Molecules get activated at different periods and move in different directions, which they hit to each other releasing energy. This energy is allowed to act through optical system to the area wherever required.

It is named depending on the molecules used as:

- Argon Laser.
- **Neod**ymium **Y**ttrium **A**luminum **G**arnet Laser (Nd: YAG Laser).
- CO_2 Laser.
- Neon Laser.
- Holmium Laser.
- Erbium Laser.

Uses of Laser

- In *cranial surgery* in children.
- In *ENT* it is used to treat vocal cord lesions, laryngeal lesions.
- In *ophthalmology,* it is very useful in retinal surgery:
  - Detachment.
  - Iridotomy.
  - Dacryocystitis.
  - Capsulotomy.
  - To liquefy human lens.
  - Glaucomas.
- In *general surgery*:
  - In bleeding duodenal ulcer.
  - For palliative decoring of tumours in carcinoma oesophagus.
  - In Ca rectum.
  - In treatment of haemorrhoides (1st and 2nd degree).
  - In resection of bladder tumour.
  - In cervical cancer.
  - To achieve bloodless field.
  - Often in making incisions in abdomen and other places.

Advantages of Laser

- Bloodless field
- Faster
- Small lesions can be removed easily and completely

Precautions

- All reflecting instruments should be avoided otherwise laser gets reflected and injure normal tissues or the working team in the OT.
- All should wear protective spectacles to their eyes.

Disadvantage

Availability and cost factors.

STAPLERS IN SURGERY

Staplers are used for apposition of tissues. Used in skin, bowel, lungs, etc.

Types

- **Cutaneous staplers** give clean apposition. It is faster and technically easier. Problem is removal requires specific instrument and costlier than sutures.
- **Linear staplers** are used to close the bowel either completely or partially.
- **Circular staplers** also called as EEA stapler—**E**nd to **E**nd **A**nastomosis. It is commonly used for colorectal anastomosis in anterior resection for carcinoma rectum, oesophagogastric anastomosis after oesophagogastric resection in case of carcinoma at O-G junction.



Fig. 32.55: Circular stapler for colorectal anastomosis.

> *Remember, the most important person in an operation theatre is the patient.*
>
> **—Berkehy George Andrew Moynihan**

Parts: *Stapler gun,* and *cartridge* with two rows of stapler pins for apposition. Loaded cartridge is detachable. Cut ends of bowel are placed over *gun* and *cartridge*. Once gun is shot, cartridge moves to the gun and creates anastomosis.

- **GIA stapler** (Gastrointestinal anastomosis stapler) for *side to side* anastomosis, like small bowel or ileo-colic anastomosis.
- **Stapler for lung apposition.**
- **Endostaplers:** These are used during laparoscopic surgeries. It is commonly used for bowel anostomosis. ***Endovascular staplers*** are used to ligate vascular pedicles like renal pedicles during laparoscopic nephrectomy.
- Stapled haemorrhoidopexy—costly.

Disposable staplers are available but are costly.

Advantages: Technically easier and faster.

Disadvantages: Cost factor, availability.

Problems with staplers:

- It is not completely haemostatic and so bleeding can occur.
- Leak from anastomosis, improper apposition.
- Intestinal obstruction.

NASOJEJUNAL TUBE FEEDING

- It is one of the methods of *enteral nutrition*. It is commonly used in acute pancreatitis. It is also useful in other enteral nutrition needs.



Fig. 32.56: X-ray showing nasojejunal tube for enteral nutrition purpose. It is useful and effective method of enteral nutrition. Its passage needs expertise, C-ARM guidance. It can be kept for long time for 3 months. Its position often to be confirmed by X-ray.

- It is passed under C-ARM guidance per nasally. It is passed up to the first loop of the jejunum across the duodenal C loop. It should be fixed properly to the nostril. Its position should be confirmed by X-ray. One should take care not to displace the tube.
- *Advantages* are—it is safer, easier and can be kept for 3 months. Complications of long-term TPN are not there.
- Disadvantages—irritation by tube, displacement, aspiration.

GOSSYPIBOMA (Gossypium—Cotton Based in Latin)

- By definition, it is the presence of *cotton based foreign body* that is in place of concealment following surgery.
- Forgotten foreign bodies (mop, gauze, etc.) intraoperatively especially in *abdominal cavity* (can occur in any cavities (thorax, pelvis) cause adhesions, provoke sepsis, often get encapsulated.
- It may cause an inflammatory mass, bowel erosion/perforation/peritonitis, intra-abdominal abscess, septicaemia, fistula formation.
- *Presentations* may be as—asymptomatic, pseudotumour, abscess, septicaemia, fistula.
- Often foreign body erodes and enters the bowel lumen and with peristalsis reaches ileocaecal valve causing intestinal obstruction. There are incidences patient has passed the foreign body like mop per anally few months after surgery (in 6% gossipyboms).
- Ultrasound, *CT scan* and MRI identifies the foreign body (gossipyboma). Plain X-ray is of less value.
- Incidende of gossipyboma is 1 in 3,000 surgeries. Migration commonly occurs into intestine either small or large but can occur into urinary bladder or stomach.
- 70% of retained foreign bodies are sponges/mops; 30% are instruments.
- *Commonest site* is abdominal cavity 55%, vagina (20%), thorax (10%) and rest on other cavities.
- Commonly gossipyboma present 3-12 weeks; rarely it can present as later as 5-7 years.
- It is more commonly observed in emergency surgery, truma, and surgery for malignancies.
- *Treatment:* Surgical exploration and extirpation of the foreign body, antibiotics.
- *Legal problem:* Gossypiboma amounts for criminal negligence. Surgeon or team or hospital can be sewed for negligence either in consumer court or criminal court.

F. Laparoscopic Surgery

CHAPTER OUTLINE

- Advantages of Laparoscopic Surgery
- Laparoscopic Cholecystectomy
- Laparoscopic Appendicectomy
- Advanced Laparoscopic Surgeries
- Diagnostic Laparoscopy
- Retroperitoneoscopy
- Natural Orifice Transluminal Endoscopic Surgery

History

First laparoscopic cholecystectomy was done by Muhe of Germany in 1985 and by Mouret in Lyon in 1987.

McKeran and Saye performed the first laparoscopic cholecystectomy in USA in 1988.

First laparoscopic appendicectomy was done by Semm as prophylaxis.

First laparoscopic appendicectomy for acute appendicitis was done by Schreiber in 1987.

Semm changed 75% open gynaecological surgeries into laparoscopic surgeries.

Prof TE Udwadia, Mumbai did first laparoscopic cholecystectomy in India.

ADVANTAGES OF LAPAROSCOPIC SURGERY

- Relatively less painful compared to open surgery. Trauma of access is very less.
- Shorter hospital stay and early return to work.
- Faster postoperative recovery.
- Better visualisation of the anatomy, i.e. better approach for dissection and visualisation of other parts of abdomen for any other pathology.
- Instrumental access to different abdominal locations is many times better compared to open method.
- Minimal scar on the abdomen.

Instruments Used

- Zero degree laparoscope is commonly used. Side viewing scopes are also used to have better visualisation 30°.
- Cold light source either halogen lamp or xenon lamp is used. Halogen lamp is used commonly and is cheaper. Xenon lamp gives high visualisation.
- Camera: 3 chip camera is commonly used with high resolution.
- Video-monitor to display images.
- CO_2 insufflator.
- Long fine dissectors like in open surgical techniques.

Figs 32.57A and B: Laparoscopic set showing trolley, telescope and monitor instruments

- Hooks and spatulas are used along with cautery for dissection.
- Clip applicators.
- Needle holders.
- Endostaplers.
- Veress needle.
- Suction-irrigation apparatus.
- Trocars of different sizes—10 mm, 5 mm.
- Reducers to negotiate smaller instruments through larger ports.

Preparation

Always general anaesthesia. Other preparations are same as for open method.

Technique

Pressure bandages are applied to both legs to improve the venous return and to decrease the stasis.

Head end of the table is lowered to have easier insertion of veress needle and scope.

Ryle's tube and Foley's catheter are essential before insertion of the trocars.

Pneumoperitoneum is created using veress needle through umbilical incision. Access can be achieved by open method through an umbilical incision.

CO_2 is commonly used to create pneumoperitoneum as:

- It is readily available
- It is cheaper
- It suppresses the combustion
- It is easily absorbed by tissues
- It has a high diffusion coefficient
- It is quickly released via respiration

Other gases used are: Air, nitrous oxide, helium, argon.

Pneumoperitoneum is created upto a pressure of 15 mmHg which distends the abdominal cavity adequately to have proper visualisation of the abdominal contents.

Laparoscope is inserted through the umbilical port (10 mm). Abdomen is evaluated for any pathology. Liver, gallbladder, pelvic organs are visualised.

Additional ports (3-4) through trocars are placed depending on the procedure to be done. It may be either 5 mm port or 10 mm port. These ports are placed in such a way to have a proper triangulation of instruments for dissection.

To use clip applicator 10 mm port is required.

Physiologic Changes due to Pneumoperitoneum

- CO_2 causes hypercarbia, acidosis and hypoxia.
- Pneumoperitoneum exerts pressure on the IVC, decreases the venous return and so the cardiac output.
- It increases the arterial pressure also.
- It compromises the respiratory function by compressing over the diaphragm impairing the pulmonary compliance.

Complications

- CO_2 narcosis and hypoxia.
- Sepsis—subphrenic abscess, pelvic abscess, septicaemia.
- IVC compression.
- Bleeding.
- Leak from the site, e.g. bile leak.
- Organ injury during insertion of ports, e.g. major vessels, bowel, mesentery, liver.
- Subcutaneous emphysema and pneumomediastinum.
- Gas emboli, though is rare but fatal.
- Postoperative shoulder pain due to irritation of diaphragm.
- Cardiac dysfunction due to decreased venous return.
- Injury to the abdominal wall vessels and nerves.
- Cautery burn to abdominal structures.
- Abdominal wall hernias.
- Wound infection.
- Mortality—0.5%.

Relative Contraindications

- Patients with compromised cardiac status.
- Peritonitis.
- Previous abdominal surgeries.
- Bleeding disorders.
- Morbid obesity.
- Third trimester pregnancy.
- Portal hypertension.

Basic Laparoscopic Surgeries

- Laparoscopic cholecystectomy.
- Laparoscopic appendicectomy.

LAPAROSCOPIC CHOLECYSTECTOMY

It is becoming popular method of treatment.

Indications

- Gallstones—symptomatic
- Cholecystitis
- Biliary colic



Fig. 32.58: Portals for laparoscopic cholecystectomy.

Relative Contraindications

- End stage cirrhosis, ascites or portal hypertension.
- Cholangitis: Cholecystectomy should be done after the control of cholangitis.
- CBD stones: Here, initially ERCP and stone extraction is done from CBD, then laparoscopic cholecystectomy is done.

Technique

After pneumoperitoneum, patient is placed in head up and slight left tilt position so as to make bowels to fall below and towards the left side. One 10 mm trocar is placed at umbilicus and through this umbilical port, laparoscope is passed. One 10 mm port in the epigastric region and two 5 mm ports in the right subcostal line are placed for grasping the gallbladder and for dissection. Initially, through the working channel gallbladder is held and Calot's triangle is dissected. Cystic duct and cystic artery are clipped.

An intraoperative cholangiogram is done with C-arm. Through the epigastric port, clips or ligatures are applied to the cystic duct and cystic artery, close to the gallbladder. Care should be taken to avoid bleeding and not to injure or clip the CBD or hepatic ducts. Gallbladder is separated from its bed using cautery and spatula and removed through the epigastric port. Abdomen may be drained. Patient is discharged after 48-72 hours.



Fig. 32.59: Laparoscopic cholecystectomy. Applying clip to cystic duct is shown.

Complications

- CBD injury
- Bile leak
- Haemorrhage
- Postoperative jaundice
- Subphrenic and other intra-abdominal abscess
- Septicaemia

When problem arises, one should be ready to convert into open cholecystectomy. Conversion rate to open cholecystectomy is 2-10%. It is indicated when there is uncontrolled bleeding, dense adhesions, suspected CBD injury, when anatomy is indistinct.

When required one should not be hesitant to do conversion.

LAPAROSCOPIC APPENDICECTOMY



Fig. 32.60: Ports for laparoscopic appendicectomy.

Indications

Acute appendicitis. Here main advantage is confirmation of the diagnosis. Other parts of the abdomen are also visualised.

Relative Contraindications

Appendicular mass and abscess.

Technique: Laparoscope is passed through the umbilical port. Two additional ports are placed, one in lower midline (5 mm), another at right lumbar region. Mesoappendix is clipped or cauterized, using bipolar cautery. Appendix base is clipped or ligated using Roeder knot and ligature.

Complications

- Appendicular stump leak.
- Pelvic abscess.
- Bleeding.
- Injury to caecum, ileum.

ADVANCED LAPAROSCOPIC SURGERIES

- Presently most of the abdominal surgeries can be done through laparoscopy.
- It requires advanced technology and skill. Surgeon should be expert in doing intracorporeal and extracorporeal knotting.

Procedures

- Laparoscopic hernia repair.
- Laparoscopic splenectomy.
- Laparoscopic fundoplication.
- Laparoscopic vagotomy and gastrojejunostomy.
- Laparoscopic Nissen's fundoplication.
- Laparoscopic colectomy.
- Laparoscopic hysterectomy. It is becoming very popular.
- Laparoscopic urologic surgeries.
- Laparoscopic paediatric surgeries.

Laparoscopic Inguinal Hernia Repair

It is becoming popular method, lately. It is a skilled laparoscopic surgery.

1. *Transabdominal preperitoneal repair (TAPP repair)*: Through abdomen, using laparoscope Hesselbach's triangle is exposed and mesh is placed in the preperitoneal space. Peritoneum is sutured back or stapled.
2. *Totally extraperitoneal repair (TEP repair)*: Through subumbilical incision, preperitoneal space is created with the help of a balloon. Laparoscope is passed to this space. Inguinal canal is dissected and mesh is placed.

Triangle of 'Doom': It is bounded by ductus deference medially, testicular vessels laterally, with apex at internal ring. This is dangerous area in laparoscopic hernia repair as dissection may injure iliac vessels and cause torrential haemorrhage.

When light pressure is exerted over area of surgical emphysema, a sensation similar to that of likewise pulpating a horse hair mattress is experienced.
—Denis Dooley

Complications

- Subcutaneous emphysema.
- Abdominal wall haematoma.
- Injury to major vessels.
- Recurrence.

DIAGNOSTIC LAPAROSCOPY

Indications

- Acute pelvic conditions.
- Tubal pregnancy.
- Ovarian diseases.
- Infertility.
- Staging of the malignancy.
- Biopsy from the tumours.
- In chronic pain abdomen where ultrasound, endoscopies, barium studies are negative, then diagnostic laparoscopy is useful.



Figs 32.61A and B: Diagnostic laparoscopy showing ectopic pregnancy in right fallopian tube. It is removed by salpingectomy through laparoscopy.

Needle laparoscopy of 2 mm sized becoming popular (especially for diagnostic purpose).

Advantages

- Laparotomy is avoided.
- Once diagnosis is made, therapeutic procedure also can be carried out in the same sitting.

RETROPERITONEOSCOPY

- It is becoming popular in urology to assess kidney, ureter, adrenals for various urologic procedures.
- Through a small loin approach, retroperitoneum is expanded by inflating balloon in the space. Once space is created, different ports are placed to do dissections.

Procedures done through retroperitoneoscopy are:

- Nephrectomy
- Pyeloplasty
- Adrenalectomy
- Pyelolithotomy
- Uretero-lithotomy
- Retroperitoneal lymph node dissection (RPLND)



Fig. 32.62: Port positions for retroperitoneoscopy.

Complications

- Injury to vessels.
- Paralytic ileus.
- Bowel (colon) injury.

Advantage

- Complications of pneumoperitoneum is not present and so respiratory reserve is well-maintained.

NATURAL ORIFICE TRANSLUMINAL ENDOSCOPIC SURGERY (NOTES)

It is an experimental surgical technique whereby "*scar less" abdominal operations* can be performed with an *endoscope passed through a natural orifice* (mouth, urethra, anus, etc.) then through an internal incision in the stomach, vagina, bladder or colorectum, thus avoiding any external incisions or scars.

- This technique has been used for diagnostic and therapeutic procedures in animal models, including transgastric (through the stomach) organ removal. The transvesical and the transcolonic approaches are also used. Transgastric and transvesical combined approach is also used to increase the feasibility of moderately complex procedures such as cholecystectomy.
- NOTES was originally described in animals by researchers at Johns Hopkins University (Dr Anthony Kalloo, et al.), and was recently used for transgastric appendectomy in humans in India (by Drs GV Rao and N Reddy).
- On June 25 2007 Swanstrom and colleagues reported the first human transgastric cholecystectomy. In late 2008 surgeons from Johns Hopkins School of Medicine removed a healthy kidney from a woman donor using NOTES. The surgery was called transvaginal donor kidney extraction.
- The ***transvaginal access*** to NOTES seems to be the *safest and feasible*. In 2007, the NOTES Research Group in Rio de Janeiro, Brazil, lead by Dr Ricardo Zorron, performed the first series of transvaginal NOTES cholecystectomy in four patients. With fewer potential complications, the procedure has a disadvantage of being possible only in women.
- Proponents and researchers in this field recognize the potential of this technique to revolutionize the field of minimally invasive surgery by eliminating abdominal incisions. NOTES could be the next major paradigm shift in surgery, just as laparoscopy was the major paradigm shift during the 1980s and 1990s.
- **Advantages are**—lower anaesthesia requirements; faster recovery and shorter hospital stays; avoidance of the potential complications of transabdominal wound infections (e.g. hernias); less immunosuppression; better postoperative pulmonary and diaphragmatic function; and the potential for “scar less” abdominal surgery.
- **Disadvantages are**—it is single port surgery and difficulty in visualisation of the area in need from all directions which is essential for proper surgical dissection. Poor manoeuverability is the problem. Sepsis through this potentially infected area into sterile peritoneal cavity is a real risk. After procedure non closure of the port site opening in these approach sites or if closing their inadequacy are the real risk in NOTES.
- The general impression is that NOTES will be accepted as the newest frontier in minimally invasive surgery. As of today non-Bariatric minimally invasive surgery fellowships offer the best opportunity to train in this new approach.

G. Dressings and Bandages

CHAPTER OUTLINE

- Dressings
- Bandages

DRESSINGS

They are the materials used to cover wounds, ulcers to provide support and to encourage healing.

Advantages

- It covers the wound and so prevents further contamination.
- It gives comfort to the patient.

Disadvantages

- It may get soaked.
- It may delay the epithelial layer formation.

Types

- *Dry dressings:* It is used in clean, sutured operated wound. It is not changed at regular intervals.
- *Wet dressings:* It is used in ulcers and wounds. Dressings are made wet by using jelly or sofra tulle sheets.

Components of Dressing

- *Inner contact layer.* It is non-absorbent and only allows secretion to pass into the absorbent layer. It does not allow penetration of granulation tissue. It is usually kept wet. Either mesh gauze or sofra tulle is used.
- *Intermediate absorbent layer* made up of cotton which absorbs the secretions.
- *Outer layer as supportive* is made up of gauze.

Dressings are fixed to the place by:

- Bandages
- Plasters
- Dynoplast
- Crepe bandages.

Depending on the condition and amount of discharge from the wound/ulcer it is changed as required—twice a day/once a day/once in two days.

Small dressings are done without anaesthesia.

Large areas like burn wounds or dressing in children require general anaesthesia.

BANDAGES

Technique of bandaging is called as ***Dysmergia***.

Indications

- To reduce the swelling like in lymphoedema
- To keep dressings in position
- To support splints
- To stop bleeding/oozing

Types of Bandages

a. *Roller bandages*
   - It is a continuous roll of material, which is rolled over the part to cover the area.
   - It is used in limbs.
   - It is available in different lengths and widths—1 inch, 2 inches, 4 inches or 6 inches.
   - It is used in different ways.
     - *Circular turns:* Continuous rolls placed over the same place.
     - *Spiral turns:* After the initial turn of the bandage, it ascends proximally overlapping the distal 2/3 of the previous turn.
     - *Reverse spiral turn:* Here each spiral turn is reversed in opposite direction so as to attain uniform pressure. It is used in limbs and areas which end as cones.
     - *Figure eight turn:* It is used in knee, elbow, wrist, ankle and for clavicle.
     - *Recurrent turn:* It is used in head, amputation stump. Here initially circular rolls are made and over that half turns are made to cover other parts of the area required.
     - *Spica bandage:* It has got ascending and descending turns, with each turn overlap and cross each other. It is used in hip, groin, shoulder, breast or thumb. *Spica means eye of a bean.*

b. *'T' bandages:* It is used in perineum and groin.

c. *Tailed bandages*: It may be four tailed bandages or many tailed bandages. It is used to support dressings on a wide area like in burns dressing, over abdomen or chest wall.

d. *Tubular bandages:* These are stockings which are unrolled over the limb to give pressure effects. It is used in lymphoedema, varicose veins and in the postoperative period following surgeries of the limb (Tubifix, Tubipress).

e. Triangular bandage: These are used for supporting the elbow or forearm. Here a wide gauze is used to cover the arm, forearm and elbow, which again winds around the neck.

f. *Cravat bandages:* It is a folded type of triangular bandage, which is used as sling around the neck, when elbow requires to be rested.

Principles of Bandaging

- Bandage is applied to the part from distal to proximal end.
- Proper positioning of the limb is a must before bandaging.
- After initial few circular turns, the required type of bandaging is then done.
- Bandage is unrolled outwards.
- During bandaging, latter turn should overlap 2/3rd of earlier turn.
- Firm, adequate pressure should be used during bandaging.
- After completing the procedure, the knot should not lie over the area or over the bony points or over the back.
- It should not cause venous or arterial compression.
- Digits should be left open and circulation in the digits should be observed for:

Anatomical place	Types of bandage
Finger/toe	One inch
Arm	Two and half inches
Leg	Four inches
Thigh	Six inches
Trunk	Six inches
Head	Four inches

H. Day Care Surgery

CHAPTER OUTLINE

- Day Care Surgery
- Surgical Audit
- Surgeon and Law

DAY CARE SURGERY

- *Day care surgery* is discharge within 23 hours (USA); surgery done without night stay (UK).
- ***Day care surgery*** *means* patient is fit to return home in 23 hours usually with overnight stay. *Ambulatory surgery means* patient recovers after surgery and returns home on the same evening. *Office surgery means* patient recovers from surgery and returns home in few hours. *Outpatient surgery* is different from day care surgery in that, patient is not previously fully assessed in outpatient surgery. Only minor procedures are done in this. Patient is not admitted in outpatient surgery. In day care and ambulatory surgery patient is admitted in the hospital.
- ***Day care surgery*** has been defined by *the Royal College of Surgeons* as when the surgical day case patient is admitted for investigation or operation on a planned non-resident basis and who nonetheless requires facilities for recovery. This definition excludes upper and lower GI endoscopies, outpatient procedures such as flexible cystoscopy, and minor superficial surgery under local anaesthetic, none of which require full day case facilities for recovery.
- *Day care surgery* is an upcoming field in surgical practice. It is an unique method wherein general practitioner, nurse at day care ward and theatre, surgeon, anaesthetist work in hand so that hospital stay and so the cost is reduced.
- Patient comes to hospital at morning for surgery and leaves the hospital on same day evening.

Procedures done in day care surgery

- Excision of cysts, lipomas, bursae, neurofibromas.
- Lymph node biopsy, haemorrhoid surgery, endoscopies, circumcision, hydrocele
- Wound suturing, toe amputation

Advantages

- Minimal hospital stay
- Becomes cheaper
- Patient acceptance

- *Contraindications* for day care surgery are—age > 70 years; high risk cardiac and respiratory patients; patients with bleeding disorders.

Basic Requirements are:

- In house anaesthesiologist; recovery room; theatre and recovery room/ward nurse; all essential surgical set up including monitor, ventilator.
- *Alertness; ambulation; analgesia and alimentation—basis for* day care of surgery.

Assessment Done Prior to Surgery are by:

- *Pre anesthetic clinics* with system evaluations; *health questionnaire* by surgeon and physician; *telephonic interviews*.
- Patient selection, patient information, patient acceptance are important parts in day care surgery.

Selection Criteria are

American Society for Anaesthesiologist (ASA) category I and II patients can be taken up for day care surgery. ASA III/or beyond are contraindicated for day care surgery.

ASA (American Association of Anesthesiologists) grading of the patient for surgery

- Normal individual
- Mild-moderate systemic disease—diabetes and hypertension under control
- Severe systemic disease—uncontrolled diabetes and hypertension
- Incpacitating systemic disease
- Moribund status

Class E—emergency surgery

Exclusion criteria for day care surgery are:

- ASA grade beyond III or more
- Obesity (BMT > 35). Hypertension—not controlled
- Surgery requiring more than one hour
- Surgery with anticipation of major fluid/blood loss or needs post operative critical care
- Preterm babies and infants less than 3 month's age
- Patient living in far and not easily reachable or able transport easily
- Unstable psychiatric illness
- If proper caregiver is not available
- Uncontrolled diabetes, alcohol abuse, COPD, severe asthma, epilepsy
- Pregnancy

Problems

Postoperative nausea and vomiting (50%); postoperative pain and postoperative drowsiness / dizziness (50%) are the *common complications* in day care anaesthesia.

Precautions

- Patient should be assessed properly before sending to day care surgery.
- The nurse should give proper instruction to the patient as patient stays in the hospital for a short period.
- Patient should be warned about possible problems like bleeding, vomiting, pain, discomfort, and sedation.
- Before discharging, patient should be seen by the doctor for the fitness.
- All records should be carefully documented.
- Patient should be advised to rush to hospital if any problems arise or to communicate immediately.
- Now hernia; small gynaecology procedures; ENT, cataract surgeries are done as day care procedures.

Nurses hold an important role in day care surgery.

SURGICAL AUDIT

'Clinical audit' is a process used by clinicians who intend to improve the patient care. The process involves comparing various aspects of patient care that includes *structure, process and outcome* against *explicit criteria*.

Aspects of Patient Care

- Structure—includes what is there in that place—the people in place, their training and knowledge, the equipments and facilities provided, the organization, management and their payment, etc.
- Process—includes what procedure is followed in that place in managing referred patients, what antibiotics used, what diagnostic tests done, use of ICU facilities, use of postoperative rehabilitation care, what procedure used for discharge of patients, etc.
- Outcome—includes the overall results that include the morbidity, mortality, readmission, improvement /deterioration of the patient's condition.

Explicit Criteria

Proposal for changes can be made in the care of the patient if it falls short of the criteria chosen which can be undertaken at one or more levels:

- Individual level—more training can be given to the doctors.
- Infrastructure—upgrading of the newer diagnostic tools.
- Team level—nurses getting more trained in handling the procedures along with the doctors.
- Institution—change in the treatment strategy, or antibiotic policy.
- Regional level—providing a good referral centre with all facilities and trained personnel.
- National level—introduction of screening programmes and health campaigns.

Surgical audit is a systematic, critical analysis of the quality of surgical care that is reviewed by peers against explicit criteria or recognised standards, and then used to further inform and improve surgical practice with the ultimate goal of improving the quality of care for patients.

In surgical practice, there will be definitely variations in the results of the surgery done by a trainee or an experienced surgeon, variations in outcome of the operation done in peripheral setup and in referral institutions, usage of modern equipments and technique used.

Step 1

Determine scope

It should be clearly defined, otherwise results in ineffective/ inappropriate data collection.

It should also be relevant, easily measurable.

Common areas in scope of an audit include—duration of hospital stay/unplanned admissions/readmissions/operative specific complications/30 days mortality /morbidity/investigations done/management strategy/patient satisfaction.

Step 2

Select standards

Standards for the selected topic/practice area is decided based on relevant information obtained from:

- Evidence based research and guidelines.
- Local guidelines for local relevance.
- New guidelines developed based on references from a library.

The standard which was already existing or developed must be clearly described, measurable, specific, and realistic.

Step 3

Collect data

It is important aspect of the audit which has to be informative for the audit to be successful. The best quality data collected depends on by whom it is being collected; when—retrospective/prospective collected; how—on form/PDA/computer; at/

Surgical Audit Cycle


Re-audit
Step 1 Determine scope
Step 5 Introduce changes and monitor progress
Step 2 Select standards
Step 4 Present and interpret result with peer review
Step 3 Collect data

So long as enthusiasm lasts, so long is life still with us.

fter the time of surgery; follow-up data when collected; patient identification in a prospective/retrospective study.

Collected data must be relevant to the objectives of the surgical audit. Sometimes, the standards may need to be expanded or reduced/or the data collection methods may need to be modified.

Step 4

Present and interpret result with peer review

Audit aims in continuous improvement by experience and by making changes which is ultimately rewarding.

The outcome of the audit should be presented and discussed in a clinical meeting. It should undergo peer review. It involves viewing and analyzing one's outcome by one's own peers who are none other than other experienced trained surgeons. It should be conducted in an atmosphere of confidentiality, trust and teamwork, should not be an opportunity to blame or brag but exchange of frank, non-confrontational discussions between the colleagues. Mortality/morbidity meetings, grand rounds are one form of peer review.

Step 5

Introduce changes and monitor progress

Based on the conclusion of the audit and meetings certain changes to be made in respect to the patient care are decided and all the personnel involved in the process are informed or educated. The outcome due to changes made are monitored by follow-ups either by reauditing the whole process/ or only the part that has been changed.

SURGEON AND LAW

- It is important to a surgeon to know legal aspects in relation to his profession. Consumer Protection Act and criminal negligence are the two things surgeons are regularly worried about and face often problems.
- It is better to have a fair idea about Consumer Protection Act in relation to patient treatment.
- Surgeon should keep all documents regarding the patient with him or in the hospital.
- Case sheet should be written in detail. Daily follow-up should be written with date and time of visit with progress about the patient.
- It is better to take detailed consent after proper explanation about the disease and treatment protocol to patient and his close attender/relative. It is better to get signature about discussion given from them with date and time. In many centers, it is practiced to record the explanation part to keep it as document.
- Surgical method, its problems, risks due to anaesthesia, high-risk if any, risk of bleeding, complications, duration of hospital stay should be discussed.
- One should make sure that anaesthetist will do preanaesthetic check up prior to surgery; he should also write his preoperative/operative/postoperative anaesthetic notes.
- Daily information sheet should be used wherein patient or party should be informed about the condition of the patient. Timing of this and signature of surgeon and party should be taken.
- After surgery detailed surgical procedure technique should be written in case sheet and should be informed to patient. Specimens should be shown to patient party and should be sent for histology.
- Approximate cost of the procedure and entire bill in the hospital should be informed. One should also inform that it may change depends on complications, number of days in ICU, critical care, need for higher antibiotics, etc.
- Negligence about retaining mops/instruments are legally not acceptable; it is better to take care of enough precautions about that.
- Surgeon has got vicarious liability about the mistakes done by ward boys, nurses, theatre nurses, etc. So it is better to train them for proper care in OT, postoperative wards and ICU.
- It is ideal to show all reports to patient party and discuss/ brief with them about the condition especially when patient is in ICU.
- If patient or party become arrogant or aggressive it is better to make a note of it in case sheet and inform police people about the same.
- It is better to make a professional indemnity insurance policy always to cover these problems in case if needed.
- It is again ideal to have an advocate to discuss these matters whenever needed.
- It is care which surgeon gives not cure always.

Chapter 33 Miscellaneous

A. Fascinating Signs in Surgery

> *"If it is a question of doubt in diagnosis, you may often observe that one man solves the doubt when the others could not, and the way in which one man happened to solve it is this: he applied to the diagnosis of the case some method of examination which others had not applied."*
>
> **—Charles Barrett Lockwood,** 1856-1914

SIGN: Sign is an indication of existence of an objective evidence of a disease, i.e. such evidence as is perceptible to the examining physician, as opposed to the subjective sensation (symptoms) of the patient.

PATHOGNOMONIC SIGN (patho = disease, gnoma = signature, pathognomonic = signature of the disease): Specially distinctive or characteristic sign of a disease or pathological condition on which a diagnosis can be made.

ACCESSORY SIGN (Assident sign): Any nonpathognomonic sign of disease, which adds on to the surety of the diagnosis when present.

ANTECEDENT SIGN: Any precursory indication of an attack of disease. These signs are to be identified at the earliest.

1. **Aaron's sign:** A sensation of pain and/or distress in the epigastric or precordial region on pressure over McBurney's point in appendicitis.
2. **Abadie's sign:**
   Charles Abadie—Spasm of levator palpebrae superioris muscle—A sign of Graves' disease.
   Jean Abadie—Insensibility of Achilles tendon to pressure, seen in tabes dorsalis.
3. **Air cushion sign** (Syn: Klemm's sign): In the radiograph of chronic appendicitis, there is often an indication of tympanitis in the right lower quadrant.
4. **Alder's sign** of shifting tenderness: This sign is useful to diagnose acute appendicitis in pregnancy.
   Locate the most tender spot and mark it on the skin. Now request the patient to turn on the left side and wait for a full minute. If the tenderness is of uterine origin it will shift with the uterus while the position remain constant in case of appendicular origin.
5. **Angell's sign:** Helpful in diagnosing *"Torsion testis"* due to developmental anomaly—The presence of mesentery between the testis and the epididymis is invariably bilateral.
   The sign is usually obscured on the affected side and can be made out by examining the patient in the standing position wherein the opposite testis will be found to lie horizontally instead of in the normal vertical position.
6. **Anghelescus' sign:** Seen in Pott's disease of spine (TB spine) wherein the victim is unable to bend the spine while lying on the back so as to rest on the head and heel alone.
7. **Argyll Robertson pupil sign:** Typically described for neurosyphilis wherein light reflex is lost while accommodation reflex is retained. Such an eye responds poorly to mydriatics. This is due to destruction of fibres between pretectal nucleus and Edinger-Westphal nucleus. Other conditions where this sign may be seen—encephalitis, vascular and traumatic lesions, cerebral tumours, diabetes mellitus and chronic alcoholism.
8. **Auenbrugger's sign:** Bulging of the epigastrium due to massive pericardial effusion. This sign highlights the importance of examining thorax in patients with abdominal symptoms.
9. **Babinski's sign** (Not syn with Babinski's reflex):
   a. Loss or weakening of the Achilles tendon reflex in sciatica. This sign helps distinguish true sciatica from hysterical sciatica.
   b. In hemiplegia the contraction of platysma muscle in the healthy side is more pronounced than on the affected side. It can be elicited by asking the patient to open the mouth, whistling, blowing, etc.

Everything is funny as long as it is happening to somebody else.

   c. When a hemiplegic patient is lying with arms crossed upon the chest and makes an effort to sit up, the thigh on the paralyzed side is flexed upon the pelvis and the heel lifted from the floor while limb on the healthier side does not move.
   d. When the paralyzed forearm is placed in supination it turns over to pronation. It is seen in organic paralysis and is also called 'Pronation sign'.
10. **Baid sign:** Described for pseudocyst of pancreas and is well appreciated in thin individuals. When Ryle's tube is passed into the stomach, it may be palpated over the swelling because the stomach is displaced anteriorly by the pseudocyst pancreas.
11. **Ballances' sign:** Seen in about 25% of ruptured spleen. There is a dull note in both the flanks due to haemoperitoneum. The dullness on the right side can be made to shift, but that on the left side remains constant/fixed because the blood in the vicinity of the ruptured spleen gets coagulated soon.
12. **Ballet's sign:** This sign is helpful in Graves' disease and hysteria wherein there will be persistence of involuntary pupillary and reflex eye movements with loss of all voluntary eye movements (external ophthalmoplegia).
13. **Bamberger's sign:** A sign described in pericardial effusion—Presence of signs of consolidation at the angle of scapula which disappears when the patient leans forwards.
14. **Banana sign:** An ultrasonographic sign described for Arnold-Chiari deformity—a cause for congenital hydrocephalus. Sonography of the fetal skull reveals flattened and curved (banana like) shape of the cerebellar hemisphere.
15. **Bastede's sign:** A sign described in a case of appendicitis—Mentioned to be condemned—when colon is inflated with air through a rectal tube, pain and tenderness can be elicited in the right iliac fossa in a suspected case of appendicitis. Such manoeuvre carries risk of perforation and hence should not be entertained.
16. **Battle's sign:** It is relevant in middle cranial fossa fracture—bruising/ecchymosis over the mastoid process in the line of posterior auricular artery is a tell-tale sign of underlying middle cranial fossa fracture (temporal bone fracture).
17. **Bergman's sign:** A urologic radiographic sign:
   a. The ureter is dilated immediately below an obstructing neoplasm rather than collapsed as seen in cases of obstructing stones.
   b. The ureteral catheter passed in such cases tends to coil in this dilated portion of the ureter.
18. **Berry's sign:** Indicated by the absence of carotid artery pulsation in a patient presenting with goitrous swelling, is an ominous sign of thyroid malignancy (due to carotid sheath infiltration by the malignant tissue).
19. **Bezold's sign:** Described in a case of mastoiditis—An inflammatory swelling seen below the apex of the mastoid process.
20. **Biederman's sign:** A dark colour instead of normal pink colour of the anterior pillar of the throat is seen in some patients with syphilis.
21. **Bird's sign:** Described for hydatid disease of lung wherein a definite zone of dullness with absence of the respiratory sounds may be appreciated.
22. **Biernacki's sign:** Analgesia of ulnar nerve in general paresis and tabes dorsalis.
23. **Blatin's sign** (Syn: Hydatid thrill): A sign elicited in cases of hydatid cystic disease. It is due to displacement of daughter cysts in the fluid of the mother cyst.
24. **Boas sign:** An area of hyperaesthesia, posteriorly extending 2.5 cm lateral to the spinous process of vertebrae to the posterior axillary line and vertically from the level of the 11th dorsal to the 1st lumbar spine—A definitive sign of the presence of cholecystitis.
25. **Blumberg sign** (Syn: Rebound tenderness; Release sign): It is a sign of peritonitis due to presence of an inflamed organ underneath it.
26. **Bonnet's sign:** Pain on thigh adduction in sciatica.
27. **Boston's sign** (Syn: von Graefe's sign): It constitutes the lid lag elicited in cases of thyrotoxicosis.
28. **Bowler's hat sign** (Syn: Double ring sign): A radiological sign which describes the appearance of a gastric polyp seen on end-on position in a double contrast barium meal study. There will be a central lucency with two rims of barium around. May also be seen in cases of sessile intestinal polyp or a diverticulum.
29. **Boyce's sign:** A gurgling sound heard on pressure by the hand on the side of neck, in cases of oesophageal diverticulum.
30. **Bozzolo's sign:** A visible pulsation of the arteries in the nostrils. A sign believed to indicate the presence of aneurysm of the thoracic aorta.
31. **Branham sign** (Syn: Nicoladoni sign): This sign is elicited when arteriovenous fistula is suspected. A pressure on the artery proximal to the fistula will cause:
   a. Reduction in size of the swelling.
   b. Disappearance of bruit.
   c. Fall in pulse rate.
   d. Pulse pressure returns to normal.
32. **Brodie's sign:** A black spot on the glans penis—a sign of gangrene due to urinary extravasation into the corpus spongiosum.
33. **Bald fundus sign:** A radiological sign described for atrophic gastritis. The fundus of the stomach looks like a small dome with absence of mucosal pattern indicated by a very thin smooth appearing gastric wall.

34. **Bent inner tube sign:** A radiological sign described for sigmoid volvulus—an important diagnostic sign. A plain X-ray abdomen taken in the supine position reveals a massively distended ahaustral sigmoid colon arising from the pelvic loop.
35. **Bird of prey sign:** A radiological (Barium enema) sign which helps in confirming the diagnosis in doubtful cases of sigmoid volvulus. Barium enema reveals a smooth tapered narrowing at the point of torsion of the colon. Mucosal folds show a screw pattern around the point of twist.
36. **Border sign:** Describes the appearance of ventral hernia in barium study follow through done in suspected cases, in the postoperative period. Lateral and inferior border of the hernia are sharply outlined while the medial and upper border blends with the abdominal shadows.
37. **Cardarelli's sign:** Transverse pulsations in the laryngotracheal tube in suspected cases of aneurysms and dilatation of the aortic arch.
38. **Chvostek's sign** (Syn: Chvostek Weiss sign; Schultze's sign): A clinical sign typically described for hypocalcaemic tetany. The sign is elicited by tapping over the muscles and/or superficial nerves to induce the muscle spasm. It may be:
    a. **Facial sign:** A light tap over the facial nerve branches in front of the ear lobe causes muscular twitching over the whole of that side of the face.
    b. **Peroneal sign:** Tapping the peroneal nerve near the fibular neck will cause dorsiflexion and abduction of the foot.
39. **Cobra head sign** (Adder head appearance): A radiological sign seen in cases of ureterocele—congenital dilation of lower end of ureter. Urography done in suspected cases produces a characteristic appearance which resembles a cobra head and hence the name.
40. **Crescent sign:** A radiological sign described in relation to two different conditions affecting the lungs and the kidneys:
    a. In plain chest X-ray taken in a patient suspected of hydatid disease or aspergilloma (fungus ball) of the lung reveals a crescent of air in the shadow of partially ruptured hydatid cyst or in the cavity containing fungus ball.
    b. On IVP, the nephrogram reveals a crescent sign in cases of congenital hydronephrosis.
41. **Cullen's sign** (Syn: Cullen Hofstatter sign): A clinical sign which was typically and initially described for ruptured ectopic pregnancy wherein there is discolouration (ecchymosis) of the umbilicus and the surrounding skin (aptly referred to as umbilical black eye). It is due to haemoperitoneum and may be seen in conditions like ruptured ectopic pregnancy (a bluish tinge), acute haemorrhagic pancreatitis (a yellowish tinge).
42. **Carman's sign** (Syn : Carman-Kirklin meniscus sign): A radiographic sign helpful in the analysis of gastric ulcers in barium meal study. It is a reliable indicator of malignancy. Nonprojecting ulcers lying intraluminal in all projections surrounded by an elevated rim of tumour produces a curval interface resembling a meniscus and is called Carman's meniscus sign. Whether the meniscus is convex or concave towards the lumen is mainly dependent upon the site of ulcer in relation to incisura angularis. Meniscus is concave towards the lumen in cases of ulcer being proximal to the incisura while it is convex when the ulcer is distal to the incisura.
43. **Carnett's sign:** A clinical sign which helps differentiate the plane of abdominal swelling. The abdominal wall muscle is made tense by asking the patient to raise both the legs with knee extended. If the lump is intraperitoneal it disappears or becomes less prominent, while it becomes prominent or persists when the lump arises from the abdominal wall.
44. **Chilaiditi's sign** (Syn: Chilaiditi's syndrome; Hepatoptosis): A radiological sign seen in plain X-ray abdomen which is helpful in the diagnosis of this syndrome wherein there is interposition of colon between liver and diaphragm. It needs to be differentiated from the conditions causing gas under the diaphragm. The presence of haustrations in the gas shadow in a plain X-ray abdomen tilts the favour in the diagnosis of Chilaiditi's syndrome.
45. **Coiled spring sign:** A radiological sign (Barium enema) classically described for intussusception. The passage of barium beyond the apex of the intussusception into the intussuscipien gives a coiled spring appearance. The sign may also be seen in cases of:
    a. Post-traumatic haematoma of duodenum.
    b. Acute appendicitis.
    c. Mucocele of appendix.
    d. Endometriosis of appendix.
    e. Intestinal carcinomas.
46. **Coles' sign:** A radiological sign. Barium meal follow through study reveals deformity of the duodenal contour in the presence of duodenal ulcer.
47. **Colon cut off sign:** A radiographic sign of appendicular perforation or colonic spasm. Absence of gas and feces in the right lower quadrant, reflex dilatation of transverse colon and sharp cut-off of gas at the hepatic flexure. This sign is also seen in acute pancreatitis
48. **Coopernail's sign:** Ecchymosis on the perineum and scrotum/labia. A sign of fracture pelvis.
49. **Cope's sign** (Syn: Psoas sign): Clinical signs which are relevant in cases of acute appendicitis. This has two tests:
    a. **Cope's psoas test:** In acute appendicitis there is psoas muscle spasm secondary to the inflamed organ and hence the patient keeps the thigh in a flexed position. This pain can be aggravated by passively hyper-extending the hip joint which stretches the psoas muscle.

Many look but only few see.—**Maxwell M Wintrobe**

b. **Cope's obturator test:** Principles are same as above except the muscle involved is obturator internus which is passively stretched by internally rotating the right leg which is flexed at the hip and knee.

50. **Cupola sign:** A radiological sign helpful in the diagnosis of pneumoperitoneum. A plain X-ray abdomen (erect position) reveals gas under the diaphragm when there is relatively large amount of air in the peritoneal cavity—Cupola sign.
51. **Crow foot sign** (Syn: Mercedes Benz sign; Seagull's sign): A radiological sign described in relation to cholelithiasis (Gallstones). Nearly 80-90% of the gallstones are radiolucent with only 10-20% being radio-opaque. However rarely a non-opaque gallstone can be diagnosed in plain radiography by the presence of gas containing crevices within the stone. These radiolucent crevices give the appearance of the crow foot; Hence the name crow foot sign, Mercedes Benz sign or the Seagull's sign.
52. **Courvoisier's sign** (Syn; Courvoiser's law): In a patient with obstructive jaundice, if the gallbladder is palpable it is not due to gallstones.
53. **Cowen's sign:** A clinical sign elicited in cases of Graves' disease. In response to a light shone on one eye there is jerky constriction of the contralateral pupil.
54. **Crowe's sign:** Refers to axillary freckling seen in neurofibromatosis.
55. **Cruveilhier's sign** of the saphena varix: A clinical sign elicited in cases of varicose viens (Saphena varix). A thrill is felt over the saphena varix when the patient is asked to perform a Valsalva manoeuvre/cough in an erect position and is due to a jet of blood entering and filling the pouch.
56. **Coleman's sign:** Helps in the clinical evaluation of fracture mandible. There is obvious swelling and bruising over the bony injury and a haematoma in the floor of the mouth if the body of the mandible is fractured.
57. **(Meniscus) Claw sign:** A radiological sign (Barium study) diagnostic of ileo-colic intussusception. The barium in the intussuscipien is seen as a claw around the negative shadow of the intussusceptum.
58. **Coffee bud sign:** It is a radiological sign seen in volvulus of sigmoid colon.
59. **Dalrymple's sign:** It is one of the manifestations of Graves' ophthalmopathy. It consists of retraction of the upper eyelid so that the palpebral opening is abnormally wide and upper sclera is visible.
60. **Delbet's sign:** A prognostic indicator in cases of aneurysm of the main artery of the limb. If the nutrition of the part distal to the aneurysm is maintained then the collateral circulation is said to be sufficient even though the distal pulse is not felt.
61. **de Musset's sign:** Rhythmical jerking movement of the head with each heart beat and is seen in cases of aortic insufficiency and aortic aneurysm.
62. **Dance sign** (Syn: Signe de Dance): A feeling of emptiness in the right iliac fossa—A sign of intussusception.
63. **Demarouay's sign:** Fixation or lowering of larynx during phonation and deglutition. A sign of syphilis of trachea.
64. **Dew's sign:** A clinical sign described in relation to the diaphragmatic hydatid abscess beneath the right cupola of the diaphragm. The area of resonance moves caudally with the patient in knee-elbow position.
65. **Dixon Mann's sign** (Syn: Mann's sign): In case of Graves' orbitopathy the two eyes appear not to be on the same level.
66. **Dorendorf's sign:** The sign identifies the fullness in the supraclavicular groove on one side in aneurysm of aortic arch.
67. **Double bubble sign:** A radiological sign described in cases of duodenal obstruction. A plain X-ray abdomen reveals two foci of gas, one in the stomach and the other in the duodenum—a sign of duodenal atresia. A similar feature is observed in the foetus in ultrasonography done in the antenatal period.
68. **Drummond's sign:** A whiff sound heard over the open mouth during respiration in cases of aortic aneurysm.
69. **DTP sign** (Syn: Distal tingling on percussion; Tinel's sign; Formication sign): A prognostic indicator which is helpful in the evaluation of nerve recovery following nerve injury. If percussion over the site of nerve injury causes tingling sensation in the distal end of the limb it suggests that the nerve injury was a partial one or it heralds the recovery from the nerve injury—a good prognostic sign.
70. **Dubois sign:** Shortness of the little finger in congenital syphilis.
71. **Duchenne's sign:** This clinical sign identifies the sinking of the epigastrium during inspiration (a paradox). It is classically seen in cases of paralysis of the diaphragm and in certain cases of hydropericardium (Pericardial effusion).
72. **Dupuytren's sign:** It is described in two conditions:
    a. A crackling sensation on pressure over a sarcomatous bone.
    b. In congenital hip dislocation, it refers to free up and down movement of the head of the femur.
73. **Dott's sign:** It is helpful in differentiating pain due to acute appendicitis and basal pneumonia with pleuritis. Compression of lower thorax from side to side elicits obvious distress when the lesion is above the diaphragm whereas in appendicitis it has no effect.
74. **Dock sign:** A radiological sign described in relation to coarctation of aorta. A chest X-ray PA view reveals rib notching on the inferior margins of 3rd-9th ribs while sparing the first two ribs and is indicative of collateral circulation developed in coarctation of aorta.
75. **De Weese sign:** A clinical sign helpful in cases presenting with history suggestive of intermittent claudications with palpable peripheral pulses. The patient is asked to exercise by walking or running sufficiently to bring on the pain. If prompt re-examination reveals absence of peripheral pulses it suggests that the pain was truly due to intermittent claudication.
76. **Echo sign:** A percussion sound resembling an echo which is heard over a hydatid cyst.
77. **Elliot's sign:** Refers to presence of indurated edge of a syphilitic skin lesion.

78. **Enroth's sign:** Identifies the abnormal fullness of the eyelids—a manifestation of Graves' orbitopathy.
79. **Escherich's sign** (Syn: Escherich's reflex): Described in relation to tetany, where percussion of the inner surface of the lips or tongue produces contraction of lips, tongue and masseter muscles.
80. **Ewart's sign:** It is said to be positive in cases of pericardial effusion if there is bronchial breathing and dullness on percussion at the lower angle of the left scapula and is due to pressure and collapse of the lingular lobe due to enlarged pericardial sac.
81. **E- sign** (Syn: Reverse 3 sign): A radiological sign seen on barium swallow radiograph in patient suspected of coarctation of aorta and is due to indentation produced on the barium filled oesophagus by the aorta.
82. **Figure of three sign:** A radiological sign seen in the plain chest X-ray PA view in patient with coarctation of aorta. A pair of bulges is seen in the wall of the aortic arch one above and one below the aortic knuckle and is due to pre- and post-stenotic dilatation of the aorta.
83. **Frostberg's sign:** A radiological sign seen in barium study in carcinoma of the head of pancreas involving the duodenum. In carcinoma of the head of the pancreas, there is widening of the 'C' loop of the duodenum and with the involvement of the ampulla of Vater, the expanded loop assumes a reversed 3 configuration—Frostberg's sign. Once the carcinoma of the head affects the duodenum the surgical cure is remote.
84. **Fox sign:** Discolouration near the inguinal ligament—seen in few cases of haemorrhagic pancreatitis.
85. **Fuchsig's sign** (Syn: Crossed leg test): This sign is more relevant when popliteal artery is not clinically palpable along with absent distal pulses. The patient is made to sit with his legs crossed. Normally, oscillatory movements of the foot occur synchronously with the pulse if the popliteal artery is patent while a negative result is more suggestive of popliteal artery block in a patient with absent distal pulses.
86. **Federici's sign:** An interesting sign described in relation to pneumoperitoneum (due to intestinal perforation) wherein on auscultation of the abdomen, the cardiac sounds can be heard.
87. **Flush tank sign:** A clinical sign described in relation to hydronephrosis. The patients classically present with features suggestive of Dietle's crisis, i.e. passage of a large amount of urine with consequent disappearance of a lumbar swelling—Flush tank sign.
88. **Flare sign:** The precursor of varicose ulcer is a splay of fine venules that courses from the medial (sometime the lateral) malleolus, and spreads out to be lost beneath the thick skin of the heel and is known as the "Flare sign".
89. **Gifford's sign:** A clinical sign which helps in differentiating unilateral exophthalmos and proptosis due to intraorbital tumours. If the upper eyelids cannot be easily everted on the affected side, the exophthalmos is more likely to be due to thyrotoxicosis, whereas if the lid is easily everted it is more likely due to an intraorbital mass.
90. **Grey Turner sign:** Skin discolouration (bruising) in the left flank (left costovertebal angle) in cases of acute haemorrhagic pancreatitis.
91. **Gilbert's sign:** Opsiuria indicative of hepatic cirrhosis (opsiuria means excretion of urine more rapidly during fasting than after a meal).
92. **Glasgow's sign:** A clinical sign—presence of systolic murmur over the brachial artery is found in latent aortic aneurysm.
93. **Griffith sign:** It is one of the clinical signs of Graves' orbitopathy wherein there is lower lid lag on upward gaze.
94. **Guyon's sign:** Ballottement and palpation of a floating kidney.
95. **Gaur sign:** A clinical sign seen in femoral hernia. Distension of superficial epigastric and/or circumflex iliac veins on the affected side due to pressure on these vessels by the hernial sac.
96. **Guerin's sign:** Haematoma at greater palatine foramen seen in maxillary fracture.
97. **Homan's sign:** Pain on sudden dorsiflexion of the foot—a sign of deep vein thrombosis of calf veins.
98. **Hamilton Bailey sign:** A clinical sign described for intussusception. A sausage shaped mass with concavity towards the umbilicus which is felt to harden as a wave of peristalsis commences.
99. **Hall's sign:** This sign identifies a tracheal diastolic shock felt in the aneurysm of aorta.
100. **Hatchcock's sign:** Refers to the tenderness towards the angle of the jaw in mumps.
101. **Haudek's sign** (Haudek's niche): A radiological sign identified in barium meal X-ray done in patient suffering from gastric ulcer. It describes a projecting shadow (niche) in radiographs due to settlement of barium in pathological niches of stomach wall.
102. **Hitzelberger's sign:** A clinical sign described in case of acoustic neuroma wherein there is anaesthesia of medial, posterior or superior areas of the external auditory canal because of the tumour tissue compressing on the facial nerve.
103. **Hook sign:** This clinical sign identifies flexion of fingers in a case of acute suppurative tenosynovitis.
104. **Horn's sign:** This sign identifies the pain produced by traction on the right spermatic cord in acute appendicitis.
105. **Howship Romberg sign:** A sign described in the patients suffering from obturator hernia. The patient complains of pain passing down the inner side of the knee due to pressure on the obturator nerve by the hernial sac.
106. **Harvey's sign:** Two index fingers are placed by the side on a vein. The fingers are now pressed firmly and the finger near the heart is moved proximally keeping the steady pressure on the vein so as to empty the short length of vein between

the two fingers. The distal finger is now released. This will allow venous refilling to be observed which will be poor in ischemic limb and increased in arteriovenous fistula.

107. **Hamman's sign** (Syn: Hamman's mediastinal crunch or murmur): A clinical sign—precordial crunching, clicking or knocking sound synchronous with each heart-beat heard on auscultation in conditions such as:
    - Acute mediastinitis
    - Pneumomediastinitis
    - Pneumothorax.
108. **Inflammatory signs** (Syn: Cardinal signs in inflammation):
    - Rubor—Redness
    - Calor—Temperature
    - Dolor—Pain
    - Tumour—Oedema/swelling
    - Functio lesa—Loss of function
109. **Jendrassik's sign:** Paralysis of extraocular muscles—A manifestation of Graves' orbitopathy.
110. **Jugular sign** (Syn: Quekenstedt's sign; Tobey Ayer test): On spinal canal block (e.g. spinal tumour) when pressure is applied over jugular veins, in the manometer connected to LP needle, either pressure will not raise or if raises falls slowly.
111. **Joffroy's sign:** Absence of wrinkling of the forehead when the head is bent down and the patient is asked to look upwards—A sign of Graves' ophthalmopathy.
112. **Kernig's sign:** A sign which is positive in meningitis. With the hip flexed, the knee is extended, normally it can be done upto 175°. In meningitis it is restricted due to spasm of the hamstrings.
113. **Kaposi Stemmer sign:** Failure to pick up or to pinch a fold of skin at the base of the second toe. It is characteristic of lymph oedema.
114. **Kocher sign** (Syn: Mean's sign): A sign of Graves' orbitopathy. The examiner places one hand on a level with the patient's eye and then lifts it higher. The upper eyelid springs up more quickly than the eyeball.
115. **Kanavel sign:** This sign is useful in the diagnosis of ulnar bursitis. In case of ulnar bursitis the site of maximum tenderness is over that part of the ulnar bursa lying between the transverse palmar creases.
116. **Kantor's sign** (String sign of Kantor): A radiological sign described in barium enema follow through in patients suffering from Crohn's disease. A string like configuration of contrast material through a filling defect is seen in the radiography.
117. **Kehr sign:** This sign identifies the pain elicited in the left shoulder in patients with suspected splenic rupture. The pain (referred pain) experienced by the patient is due to blood in the peritoneal cavity irritating the diaphragm.
118. **Klemm's sign:** It is the radiological sign found in chronic appendicitis where there is often an indication of tympanitis in the right lower quadrant.
119. **Knie's sign:** Unequal dilatation of the pupils—a sign of Graves' orbitopathy.
120. **Krisowski's sign:** Cicatricial lines radiating from the mouth in congenital syphilis.
121. **Kenawy's sign:** A clinical sign usually associated with bilharzial fibrosis of liver (Egyptian splenomegaly) but may be present in any type of portal hypertension. Auscultation over the xiphoid process reveals a venous hum (splenic vein engorgement) which becomes prominent on inspiration.
122. **Klein's sign** (of shifting tenderness): A clinical sign useful in acute nonspecific mesenteric lymphadenitis. When patient is shifted to left lateral position, point of maximum tenderness also gets shifted to the left side in contrast to acute appendicitis. It may also be positive in Meckel's diverticulitis.
123. **Lemon sign:** A radiological sign of Arnold-Chiari deformity. There is scalloping of the frontal bones giving the skull a lemon shaped configuration in sonography of the fetal skull during second trimester of pregnancy.
124. **Lennhoff's sign:** A furrow appearing on deep inspiration below the lower rib and above an echinococcal cyst of liver.
125. **Sign of Leser Trelat:** Sudden appearance and rapid increase in size and number of seborrhoeic keratoses, a sign of internal malignancy of the GIT.
126. **Lloyd's sign:** A clinical sign elicited in a patient with renal calculus. Pain elicited in the loin on deep percussion over the kidney even when there is no pain on applying deep pressure.
127. **London's sign:** It is useful in ruptured intestine suspected in an accident case. The presence of pattern of bruising of the skin (i.e. an imprint of the clothing is noted on the skin) indicates that a crushing force has been applied sufficient to rupture the bowel against the vertebral column. This sign is a strong indication to carry a laparotomy.
128. **Mallet Guy's sign:** A clinical sign identified in chronic relapsing pancreatitis. It is elicited by placing the patient in the right lateral position with the patient's hip and knee flexed and deeply palpating the abdomen in the epigastric and the left subcostal region. This will evoke tenderness in chronic relapsing pancreatitis.
129. **McBurney's sign:** Finger tip pressure is made over the McBurney point elicits severe tenderness in patients with appendicitis.
130. **Murphy's sign** (Moynihan's method): This clinical sign is classically described in patients suffering from cholecystitis. It is elicited by asking the patient to breath deeply while exerting moderate pressure with the left hand such that thumb lies over the fundus of the gallbladder. The patient catches his breath as the inflamed gallbladder which is pushed down by the diaphragm gets imposed against the thumb.

131. **McEwen's sign:** A clinical sign elicited in children with hydrocephalus. On percussion of skull behind the junction of frontal, parietal and temporal bones and auscultation over opposite mastoid bone there is a more resonant note than normal, seen in internal hydrocephalus and cerebral abscess in children (syn: cracked pot sign, cranial cracked pot sound).
132. **Meniscus sign:** Refer No. 57.
133. **Moebius sign:** Inability to keep the eyeballs converged due to insufficiency of medial rectus muscle— A clinical sign of Graves' ophthalmopathy.
134. **Milian's ear sign:** A clinical sign which is useful to differentiate facial erysipelas from cellulitis. Erysipelas being a cuticular lymphangitis spreads from the face to the pinna while the cellulitis which is spreading inflammation of the subcutaneous tissue stops short of pinna because of close adherence of the skin to cartilage.
135. **Mahler's sign:** A steady increase of pulse rate without corresponding increase of temperature seen in thrombosis.
136. **Mann's sign** (Syn: Dixon Mann's sign): In Graves' disease the two eye appears not to be on the same level.
137. **Marie's sign:** Tremors of body extremities in Graves' disease and other types of hyperthyroidism.
138. **Mean's sign** (Syn: Kocher's sign): Refer No. 114.
139. **Medusa Lock sign:** A radiological sign described in patients with intestinal obstruction due to roundworm infestation. A plain X-ray erect film of the abdomen reveals trapped intestinal gas within the worm mass giving a characteristic appearance of coiled locks of hair—Medusa Lock sign.
140. **Meitzer's sign:** Loss of normal second heart sound on auscultation of the heart after swallowing. Seen in occlusion or contraction of lower part of oesophagus.
141. **Mercedes Benz sign** (Syn: Crow foot sign): Refer No. 51.
142. **Mexican hat sign:** A radiological sign described in barium enema (filling defect) done in patients with pedunculated polyp of the inferior wall of the colon.
143. **Maulage sign:** Waxy cast appearance of bowel segments—A radiographic sign of coeliac disease.
144. **Mose's sign:** A clinical sign suggestive of deep vein thrombosis. It is elicited by squeezing the relaxed calf muscles from side to side which is painful in case of deep vein thrombosis.
145. **Niche sign** (Syn: Haudek's sign): Refer No. 101.
146. **Nicoladoni's sign** (Syn: Branham's sign): Refer No 31.
147. **Oliver's sign** (Syn: Porter's sign; Tracheal tug): Tracheal tug is seen in:
    - Aneurysm of the aorta.
    - Neoplasm which fixes bronchus to aorta.
148. **Omega sign:** A radiological sign observed in patient suspected of sigmoid volvulus on the X-ray. A plain X-ray abdomen taken in the supine position shows a massively distended sigmoid colon with haustrations arising from the pelvis resembling Greek letter 'omega' (ω).
149. **Payr's sign:** Pressure over the sole of the foot elicits severe pain in cases of thrombophlebitis.
150. **Peroneal sign:** Tapping the peroneal nerve near the fibular neck causes dorsiflexion and abduction of foot in hypocalcaemic tetany.
151. **Perez's sign:** A friction sound heard over the sternum when the patient raises and drops his arms. A sign of mediastinal tumour or aneurysm of arch of aorta.
152. **Parrot's sign** (Syn: Parrot's nodes, hot cross bun skull, Natiform skull): Bony nodes on the outer table of the skull of infants with congenital syphilis, so that it has a hot cross bun or buttock shape.
153. **Pfuhl sign:** A clinical sign which helps in differentiating between subphrenic abscess and pyopneumothorax. Inspiration increases the force of flow in paracentesis in subphrenic abscess, but lessens in case of pyopneumothorax. This distinction is however lost in cases where diaphragm is paralyzed.
154. **Pitre's sign:** Hypoaesthesia of scrotum and testes in tabes dorsalis.
155. **Plummer's sign** (Syn: Quadriceps sign): Inability to step up onto the chair or to walk up steps seen in Graves' disease and other forms of hyperthyroidism.
156. **Pool Schlesinger's sign:** In tetany if patients leg is held at the knee joint and flexed strongly at the hip joint, within a short time there will be an extensor spasm at the knee joint with extreme supination of foot.
157. **Porter's sign:** Tracheal tugging in aneurysm of aortic arch and neoplasms which fix the left bronchus to aorta.
158. **Potain's sign:** Extension of percussion dullness over the arch of the aorta from the manubrium to the third costal cartilage on the right side—seen in cases of dilatation of the aorta.
159. **Prehn's sign:** Elevation and support of the scrotum will relieve the pain in epididymo-orchitis but not in torsion testis.
160. **Psoas sign** (Syn: Cope's test): Refer No. 49.
161. **Puddle sign:** Describes a clinical method to detect small amount of ascites (150-500 ml). Patient lies prone for 5 minutes and then goes for knee-elbow position. In this position dullness is elicited in the umbilicus in case of minimal ascites.
162. **Pemberton's sign:** This sign refers to symptoms of faintness with evidence of facial congestion and external jugular vein distension when the arms are raised above the head touching the ears. This manoeuvre reduces the thoracic inlet thereby hampering venous drainage of the face in the presence of retrosternal thyroid.

Absolute diagnosis are unsafe and are made at the expense of the conscience.—**William Osler**

163. **Pointing sign:** Ask the patient to point to the site of maximum pain. If this proves to be the site of localized tenderness it is also certainly the site of diseased organ, e.g. appendicitis.
164. **Patel's sign:** It is important in paralytic ileus. Apply the stethoscope firmly to the skin just below and right of the umbilicus for full 3 minutes. In paralytic ileus there will be omnious silence, broken by patient's own heart sounds believed to be transmitted via the over distended coils of the intestine with added succussion splashes if the patient moves and very occasionally by faint tinkles.
165. **Pad sign:** A radiological sign identified in patients with carcinoma of the head of pancreas wherein the 'C' loop of barium filled duodenum may be widened.
166. **Panda sign** (Raccoon sign, Spectacle haematoma, Black eye): Haemorrhages in soft tissues around the eye and in the eyelids is known as Panda sign as it resembles panda eyes. It is caused by:
    1. Direct trauma, such as punch to the eye.
    2. Blunt impact to the forehead, the blood gravitating downwards over the supraorbital ridge.
    3. Fracture of the floor of the anterior fossa of the skull.
167. **Queckenstedt's sign** (Jugular sign; Tobey Ayer test): Refer No. 110.
168. **Quenu Muret sign:** A prognostic indicator. In aneurysm, when the main artery of the limb is compressed and a puncture is made at the periphery, if the blood flows, then the collateral circulation is probably established.
169. **Rat-tail sign:** A radiological sign described in relation to oesophageal carcinoma.
170. **Ridge sign:** A clinical sign of dehydration. In considerable dehydration if the skin is picked up in between the thumb and fingers and then released, instead of it springing back with normal elasticity, a ridge is formed that subsides slowly.
171. **Rovsing sign:** In acute appendicitis, when left iliac fossa is pressed; pain is felt in right iliac fossa.
172. **Release sign** (Syn: Rebound tenderness; Blumberg's sign): Refer No. 25.
173. **Reversed 3-sign:** Refer No. 81.
174. **Reisman sign** (Syn: Snellen's sign): The bruit heard over the closed eye in Graves' disease.
175. **Rocher's sign:** A clinical sign which helps in the differentiation of epididymitis from torsion of the testes. In torsion testes, the epididymis cannot be distinguished from the body the testes, whereas in epididymitis the body of the testes can be felt in the enlarged crescent of epididymis.
176. **Rommelaere's sign:** An abnormally small proportion of normal phosphates and of sodium chloride in urine in cancerous cachexia.
177. **Rotch sign:** A clinical sign identified in case of pericardial effusion. Dullness is felt on percussion on the right 5th intercostal space.
178. **Rovighi's sign:** A fremitus felt on percussion and palpation of the superficial hepatic hydatid cyst.
179. **Racoon sign** (Syn: Panda sign, Spectacle Haematoma, Black Eye): Refer No. 166.
180. **Sign of splashing** (Syn: Succussion splash): Seen in gastric outlet obstruction.
181. **Saegesser's sign:** A clinical sign identified in patients with splenic rupture. An excruciating tenderness is elicited in the Saegesser's point or splenic point (seen in the lower part of the posterior triangle of the neck between the left sternomastoid and scalenus medius muscle above the clavicle).
182. **Sternomastoid sign** (Syn: Trail's sign): The sternal head of the sternomastoid muscle will become more prominent on the side to which trachea is deviated.
183. **Saenger's sign:** Refers to the light reflex of the pupil that has ceased, returns after a short stay in the dark. Observed in cerebral syphilis but not in tabes dorsalis.
184. **Sansom's sign:** Described in two separate context:
    - Marked increase in the area of dullness in the second and third intercostal space – Due to pericardial effusion.
    - A rhythmical murmur heard with a stethoscope applied to the lips in aneurysms of the thoracic aorta.
185. **Schlesinger's sign** (Syn: Pool's phenomenon): Refer No. 156.
186. **Schultze sign** (Syn: Schultze Chvostek sign): Refer No. 38.
187. **Silex's sign:** Furrows radiating from the mouth in congenital syphilis.
188. **Sisto's sign:** Constant crying in infancy—a sign of congenital syphilis.
189. **Setting sun sign:** A clinical sign described in patients suffering from raised intracranial tension. There is downwards deviation of the eyes so that each iris appears to set beneath the lower eyelid with white sclera exposed between it and the upper lid. This sign is observed in cases:
    - Hydrocephalus
    - Intracranial haemorrhage
    - Brain tumours
190. **Snellen's sign** (Syn: Reisman sign): Refer No. 174.
191. **Sumner's sign:** This sign is said to be positive when there is increase in the tone of the abdominal muscle on gentle palpation of the right iliac fossa. It may indicate:
    - Appendicitis
    - Right ureteric or renal stones
    - Torsion ovarian cyst.

192. **Simon's sign:** Identifies absence of usual co-relation between the movements of diaphragm and thorax, seen in early cases of meningitis.
193. **Stierlin's sign:** A radiological sign observed in barium enema study of the colon where there is absence of normal shadow due to an indurating or ulcerative process such as tuberculosis of caecum or colon.
194. **String sign** (Syn: Kantor's sign): Refer No. 116.
195. **Suker's sign:** Deficient complementary fixation in lateral eye rotation—a manifestation of Graves' orbitopathy.
196. **String of beads sign:** A series of round shadows resembling a string of beads or pearls, seen on a radiograph of small intestine, indicating of trapped gas surrounded by the fluid of obstructed and distended bowel.
197. **Stellwag's sign:** Identifies the widening of palpebral fissures (staring look) due to retraction of upper eyelids, an early sign of Graves disease.
198. **Stemmer sign** (Kaposi Stemmer sign): Refer No. 113.
199. **Slip sign:** A clinical sign which helps in differentiating a solid swelling, e.g. lipoma, from a cystic swelling. Here, when the edge of the swelling is palpated, the margin of the solid swelling does not yield but slips away from it unlike a cystic swelling which yields to the pressure of the palpating finger and does not slip away.
200. **Solius sign:** A radiological finding observed in a chest X-ray lateral view in patient's with enlarged thymus. An enlarged thymus being a firm swelling does not get flattened against sternum by the pressure of heart and great vessels.
201. **Shrinkage sign:** A radiological sign of thymus enlargement. In a chest X-ray there is a paradoxical alteration of the shape of the chest with respiration (Decrease in transverse diameter with deep inspiratory film than the expiratory film).
202. **Seagull sign:** Refer No. 51.
203. **Suzmann's sign:** A clinical sign described in patient with coarctation of aorta. The collaterals which develop display visible and palpable pulsations together with thrills and murmurs which are most obvious in the inter-scapular and infra-scapular regions of the back. The Dock sign is the radiological counterpart of this sign.
204. **Trail's sign** (Syn: Sternomastoid sign): Refer No. 182.
205. **Tap sign** (Syn: The percussion sign; Chevrier's sign): If the valves are incompetent an impulse will be felt by the fingers overlying the long saphenous vein when the varicosities are percussed below.
206. **Thornton's sign:** Refers to the severe pain complained by the patient in the region of the flanks in nephrolithiasis.
207. **Tinel's sign** (Syn: DTP sign; Formication sign): Refer No. 69.
208. **Tresilian sign:** This sign identifies reddish appearance (congestion) in opening of Stensen's duct in cases of mumps.
209. **Trimadeau's sign:** A radiological sign identified in barium swallow X-ray done in patient's with dysphagia. If the dilatation above an oesophageal stricture is conical, the stricture is fibrous; while it is cup shaped (shouldering) it is likely to be malignant.
210. **Tanyol's sign:** In ascites umbilicus shifts downwards and in mass arising from pelvis it shifts upwards.
211. **Troisier's sign:** Identifies enlargement of left supraclavicular lymph node (Virchow's node). Seen in:
    - Ca stomach
    - Ca testes
    - Ca bronchus
    - Malignancy of any other abdominal organ.
212. **Trousseau's sign:** This sign is described under two different context:
    - The blood pressure cuff is applied to the arm and inflated to pressure above systolic pressure for 3-5 minutes. This will elicit typical carpopedal spasm (obstetrician's hand) in cases of hypoparathyroidism and other conditions associated with hypocalcaemia.
    - Migrating superficial thrombophlebitis—a sign of visceral carcinomas especially of pancreas or the stomach.
213. **Tracheal fluctuation sign:** A unique sign elicited in patients suffering from achalasia cardia.
214. **von Graefe's sign** (Syn: Graefe's sign): Persistent lagging of upper lid behind the corneoscleral limbus when patient is asked to follow the finger moved up and down several times. Seen in Graves' disease.
215. **Vermooten's sign:** A clinical sign helpful in the intrapelvic rupture of urethra. On per rectal examination, the prostate cannot be felt but in its position a doughy swelling (blood and urine) is felt. If prostate is felt, it is displaced upwards.
216. **Vas sign:** This sign is helpful in differentiating testicular neoplasm and an inflammatory lesion of the testes. Inflammatory lesions causes vas deferens to become considerably thickened which remains normal in cases of neoplasm.
217. **Vein sign:** A bluish cord along the mid-axillary line formed by the swollen junction of the thoracic and superficial epigastric vein. Seen in:
    - Tuberculosis involving the bronchial glands
    - Superior vena cava obstruction.
218. **Wegner's sign:** A postmortem finding—A broadened discoloured appearance of the epiphyseal line in infants who have died from congenital syphilis.
219. **Wilder's sign:** An early clinical sign of Graves' disease consisting of slight twitch of the eyeball when it changes its movement from adduction to abduction or vice versa.

Observe, record, tabulate, communicate. Use your five senses.—**William Osler**

220. **Wimberger's sign:** Symmetrical erosions of the proximal tibia seen radiographically in infants with congenital syphilis.
221. **Water lily sign** (Syn: Lily pad sign): A radiological sign identified in cases of hydatid cyst of the lung. When the hydatid cyst ruptures, the daughter cyst floating within the cavity appear like a water lily hence the name water lily sign.
222. **Smith's sign:** Murmur heard in cases of enlarged bronchial lymph nodes on auscultation over the manubrium with the patients head thrown backwards.
223. **'H' Bomb sign:** A radiological sign seen in cases of atrophic gastritis. The gastric folds within fundus and the body of stomach are very thin and the thin walled fundus becomes distended with air (in erect posture) or with barium contrast.

B. Triads in Surgery

1. **Saint's triad:**
    Diverticulosis of colon
    Gallstones
    Hiatus hernia.
2. **Whipples' triad:** Seen in insulinoma.
    Features of hypoglycaemia
    Blood sugar less than 45 mg%
    Symptoms are relieved by glucose.
3. **Charcot's triad:** Seen in ascending cholangitis.
    Intermittent fever
    Intermittent pain
    Intermittent jaundice.
4. **Virchow's triad:**
    Change in the vessel wall
    Diminished rate of blood flow
    Increased blood coagulability.
5. **Murphy's triad:** Seen in acute appendicitis.
    Pain in right iliac fossa
    Vomiting
    Temperature.
6. **Hutchinson's triad:** Seen in late congenital syphilis
    Interstitial keratitis
    8th nerve deafness
    Hutchinson's teeth.
7. **Trotter's triad:** Seen in nasopharyngeal carcinoma.
    Conductive deafness
    Elevation and immobility of same side soft palate
    Pain in the side of the head.
8. **Tillaux's triad:** Seen in mesenteric cyst.
    Soft fluctuant swelling in the umbilical region
    Freely mobile in the direction perpendicular to mesentery
    Zone of resonance all around.
9. **Triad of portal hypertension:**
    Varices
    Splenomegaly
    Ascites.
10. **Cushing's triad:** In intracranial hypertension.
    Increased blood pressure
    Decreased pulse rate
    Decreased respiratory rate.
11. **Triad of renal cell carcinoma:**
    Anaemia
    Haematuria
    Mass in the loin.
12. **Borchardt's triad:** Seen in gastric volvulus
    Acute epigastric pain
    Violent vomiting
    Inability to pass nasogastric tube.
13. **Beck's triad:** Seen in cardiac tamponade.
    Muffled heart sounds
    Distended neck veins
    Hypotension.
14. **Pancoast's triad:** Seen in Pancoast tumour.
    Excruciating pain in the arm
    Horner's syndrome
    Erosion of ribs.
15. **Prune-Belly triad:** Seen in Prune-Belly syndrome.
    Cryptorchidism
    Abdominal wall defects
    Genitourinary defects.
16. **Mackler's triad:** Seen in Boerhaave's syndrome.
    Vomiting
    Chest pain
    Subcutaneous emphysema.
17. **Triad of Sandblom:** Seen in haemobilia
    Jaundice
    Pain
    Melaena.
18. **Galezia triad:**
    Dupuytren's contracture
    Retroperitoneal fibrosis
    Peyronie's disease of penis.
19. **Dieulafoy's triad:** Seen in appendicitis
    Hypersensitiveness of skin
    Reflex muscular contraction
    Mac Burney's tenderness.
20. **Triad of congenital diaphragmatic hernia**
    Respiratory distress
    Apparent dextrocardia
    Scaphoid abdomen.
21. **Carney's triad**
    Functioning adrenal para ganglioma—nonfamilial
    Gastric leiomyosarcoma—GIST
    Pulmonary chondroma.
22. **Triad of Ohashi in IPMN in ERCP**
    A bulging ampulla of Vater
    Mucin secretion
    Dilated main pancreatic duct.
23. **Haimovici triad of revascularisation of an acutely ischaemic limb**
    Muscle infarction
    Myoglobinuria
    Acute renal failure.
24. **Triad of small bowel obstruction in plain X-ray**
    Dilated small bowel loops > 3 cm
    Multiple air fluid levels in erect X-ray
    Paucity of air in the colon.
25. **Gilroy Bevan triad of adhesive pain is**
    Pain may get aggravated or relieved on change of posture
    Pain in the region of old abdominal scar
    Tenderness is elicited by pressure over the scar.

C. Misnomers in Surgery

1. *White bile*: It is neither white nor bile. It is opalescent. It contains mucous. It signifies severe obstructive jaundice due to which secretion of bile from liver is stopped. Mucous is derived from biliary tree lining.
2. *Mycotic aneurysm*: It is not due to fungal infection. It is due to bacterial infection.
3. *Lateral aberrant thyroid*: It is not an aberrant thyroid. It is secondaries in neck lymph node from occult primary in the thyroid, i.e. papillary carcinoma thyroid.
4. *Adenolymphoma of parotid gland*: It is not lymphoma. It is a benign tumour of the parotid. It never turns into malignancy.
5. *Pretibial myxoedema*: It is not seen in myxoedema. It is seen in thyrotoxicosis.
6. *Sternomastoid tumour:* It is not a tumour. It is due to birth trauma which causes organised haematoma in sternomastoid muscle.
7. *Dissecting aneurysm:* It is aortic dissection, not dissecting aneurysm.
8. *Malignant hydatid:* It is not malignant. It is due to *Echinococcus alveolaris*. It behaves like a malignant condition.
9. *Malignant exophthalmos:* It is due to primary thyrotoxicosis. It is not a malignant condition.
10. *Spina ventosa*: It is tuberculous dactylitis. It is not related to spine.
11. *Mycosis fungoides:* It is cutaneous "T" cell lymphoma. It is not due to fungal infection.
12. *Hypernephroma*: It is renal cell carcinoma. It is not above the kidney.
13. *Hepatoma:* It is hepatocellular carcinoma. It is not benign tumour.
14. *Melanoma:* It is melanocarcinoma. It is not benign.
15. *Surgical ganglion:* It is arising from the synovial sheath. It is not from nerve ganglion.
16. *Brain fungus*: It is not a fungal infection. It is seen in cranial injury wherein due to injury brain protrudes out of the wound as fungus.
17. *Cock's peculiar tumour*: It is not a tumour. It is ulcerated sebaceous cyst. It mimics SCC of skin.
18. *Pott's puffy tumour:* It is not a tumour. It is osteomyelitis of the frontal bone with cellulitis of the frontal region of the scalp. It may spread intracranially through emissary veins which endangers the life of the patient.
19. *Tumour alba*: It is tuberculosis of synovial sheath of knee joint.
20. *Umbilical adenoma*: It is not a tumour. It is prolapse of mucosa of cutaneous end of vitello-intestinal duct
21. *Madelung's deformity*: It is not associated with any of the conditions in the lung. It is a congenital subluxation or dislocation of the lower end of the ulna, from malformation of the bones.
22. *Ray fungus:* Actinomycoses, a bacteria infection.
23. *Malignant pustule:* Anthrax infection.
24. *Malignant oedema:* Gas gangrene.
25. *Juvenile melanoma:* It is not a melanoma. It is benign SPITZ naevus.
26. *Hydrocele of the neck*: It is cystic hygroma
27. *Kuttner tumour*: It is chronic sclerosing sialadenitis of submandibular salivary gland.
28. *Aneurysmal bone cyst:* It is not related to artery. It is expanding lesion in the bone containing blood mixed fluid of unknown aetiology.
29. *Hairy leukoplakia*: It is hairy leukoplakia with white confluent patches of fluffy / hairy hyperkeratotic thickening almost always situated in the lateral border of the tongue. It is not hair in tongue; not related hair diseases; not structurally hair component.

D. Triangles in Surgery

1. *Hesselbach's triangle:* The medial border of the triangle is formed by the rectus sheath, superolateral border by the inferior epigastric artery, inferior border by the inguinal ligament.

   Importance: Helps in differentiating direct from indirect hernias.
2. *Bryant's triangle:* Patient lies in supine position, three lines are drawn, one from the anterior superior iliac spine vertically down to the bed; another from the tip of the greater tronchanter to join the first line at the right angles; third line from anterior superior iliac spine to the tip of the greater tronchanter—this forms a triangle.

   Importance: Diminution in the length of the second line indicates upward displacement of the greater trochanter. Third (oblique) helps determine the anteroposterior displacement of the greater tronchanter.
3. *Triangle of Doom:* Bounded by the ductus deferens medially, spermatic vessels laterally in the male and the apex of the triangle is at the level of internal inguinal ring.

   Importance: External iliac artery and vein, femoral nerve are located in the triangle and so stapling is avoided in this triangle while doing laparoscopic preperitoneal repair for hernia.
4. *Calot's triangle:* Formed medially by the common hepatic artery, laterally by the cystic duct and the apex is formed by the junction of the cystic and the hepatic ducts. Base is formed by the cystic artery.

   Importance: Cystic lymph node of 'Lund' is present in the fork created by the junction of the cystic and common hepatic artery.
5. *Anal triangle and urogenital triangle:* A transverse line joining the anterior parts of the ischial tuberosities and passing immediately anterior to the anus divides the perineum into two triangles, anal and urogenital triangle. Anal triangle contains the termination of the anal canal in the median plane and an ischiorectal fossa on each side.

   Importance: Both the perineal and ischiorectal spaces in the anal triangle are common sites of abscess.
6. *Femoral triangle:* It is triangular depression on the front of the upper one-third of the thigh below the inguinal ligament, bounded medially by the medial border of adductor longus, laterally by the medial border of sartorius, apex is formed by the meeting point of the medial and lateral boundaries.

   Importance: Femoral vein in this site is most suitable for intravenous injection in the infants; femoral artery pulsations are an important aid for clinicians (in diagnosing peripheral vascular disease).
7. Lumbar triangle:
   a. *Inferior lumbar triangle of Petit*—bounded by the crest of ilium below, external oblique laterally and medially by the latissimus dorsi.

      Importance: Most primary lumbar hernia occur through this triangle.

   b. *Superior lumbar triangle of Grynfelt*—bounded by the 12th rib above, medially by the sacrospinalis and laterally by the posterior border of the inferior oblique.

   Importance: Grynfelt hernia appears through superior lumbar triangle.
8. *Triangle of auscultation*: This is a small triangular interval bounded medially by the lateral border of the trapezius, laterally by the medial border of the scapula and inferiorly by the upper border of latissimus dorsi. Floor of the triangle is formed by the 7th rib, 6th and 7th intercostal spaces and *rhomboids minor*.

   Importance: This is the only part of the back which is not covered with muscles. Respiratory sounds are better heard with a stethoscope here than that heard elsewhere in the back.

   On the left side, the cardiac end of the stomach lies deep to this triangle and in days before X-rays were discovered, sounds of swallowed liquids were auscultated over this triangle.
9. *Simon's triangle:* Bounded anteriorly by the recurrent laryngeal nerve, posteriorly by the common carotid artery and base is formed by the inferior thyroid artery.

   Importance: Aids in identification of the recurrent laryngeal nerve.
10. *Lumbosacral triangle of Marcille:* It is a triangular interval on each side of the body of the 5th lumbar vertebra, bounded medially by the body of the 5th lumbar vertebra, laterally by the medial border of the psoas muscle, apex by the junction of the psoas major muscle and the body of the 5th lumbar vertebra. Base is formed by the upper surface of the ala of the sacrum and floor by the transverse process of the 5th lumbar vertebra and the iliolumbar ligament.

    Importance: Ureter crosses the common iliac vessels at the lateral angle of the triangle.

Dead men are always good men !!

11. *Retromolar trigone:* Base overlies the ascending ramus of the mandible from the last molar, apex terminates at the maxillary tuberosity, laterally continuous with the buccal mucosa and medially blends with the anterior tonsillar pillar.
    Importance: Common site for oral malignancy.
12. *Sherren's triangle:* Bounded by the umbilicus, symphysis pubis and the anterior superior iliac spine.
    Importance: Indicates the area of hyperaesthesia in an acute episode of appendicitis.
13. *Scalene triangle:* Bounded by scalenus anticus anteriorly, scalenus medius posteriorly and first rib inferiorly.
    Importance: Subclavian artery and trunks of the brachial plexus pass through the scalene triangle where they may be compressed causing thoracic outlet syndrome.

E. Drugs at a Glance

> *Remember how much you do not know. Do not pour strange medicines into your patients.*
> **—William Osler,** 1903

ANTIBACTERIALS

> *It seems likely that in the next few years a combination of antibiotics with different antibacterial spectra will furnish a "cribrum therapeuticum" from which fewer and fewer infecting bacteria will escape.*
> **—Alexander Fleming,** 1946

SULFONAMIDES

They act by inhibiting folic acid synthetase which converts PABA to folic acid.

Side effects: Intolerance, crystalluria, agranulocytosis, goitre, neuritis, jaundice.

Drugs

Sulfadiazine: 1 gm 6th hourly.
Sulfamethizole: 200 mg 6th hourly.
Sulfadimidine: 1 gm 6th hourly.
Sulphamethoxazole:
Sulfaguanidine: 3 gm 6th hourly.
Sulfamethoxale: 1 gm 6th hourly.
Used in meningitis, UTI, chancroid, trachoma, ulcerative colitis, toxoplasma, Bacillary dysentery.
Silver sulphadiazine cream 1% for burns.
Sulphacetamide as ophthalmic solution.

Cotrimoxazole: Combination of trimethoprim and sulfamethoxazole in a ratio of 1 : 5 in different strengths

Trimethoprim inhibits dihydrofolate reductase enzyme which converts dihydrofolate into tetrahydrofolate. It has got synergistic action with sulphamethoxazole.

It is used as BID dose in typhoid, plague, UTI, prostatitis.

Side effects: Severe skin reactions, megaloblastic anaemia.

QUINOLONES

They act by interfering with the synthesis of DNA.

They are useful against gram-negative organisms, enteric fever, respiratory infections, gastroenteritis, urinary infections, tuberculosis.

Side effects: Allergic reactions, CNS manifestations, hallucinations, nephritis, arrhythmias.

Drugs

Nalidixic acid 1 gm 6th hourly.
Norfloxacin 400 mg BD for 10 days.
Ciprofloxacin 500 mg BD for 10-14 days.
Pefloxacin 400 mg BD.
Ofloxacin 200 mg OD or BD for 10-14 days.
Lomefloxacin 400 mg OD.
Sparfloxacin 200 mg BD.
Levofloxacin 500 mg OD for 7-14 days.
Gatifloxacin 200 mg OD.

He is the best physician who knows the worthlessness of many medicines.—**Benjamin Frunklin**

PENICILLIN

It acts by interfering with the cell wall synthesis of bacteria.

Used in *Streptococcus, Pneumococcus, Meningococcus* and gonococcal infections, syphilis, tetanus, gas gangrene, actinomycosis, plague. It is also used as prophylaxis in rheumatic fever. It is used in pelvic infections, lymphoedema.

Side-effects: Anaphylaxis, serum sickness, Jerisch-Herxheimer reaction.

Drugs:

Benzyl penicillin. 4-10 lakhs 4th or 6th hourly intravenously after test dose.

Procaine-penicillin 4-10 lakhs IM after test dose OD for 7-14 days.

Benzathine penicillin 12-24 lakhs deep IM into the buttocks after test dose once in 3 weeks.

AMPICILLIN/AMOXYCILLIN/TALAMPICILLIN/PIVAMPICILLIN

Used in respiratory infections, meningitis, endocarditis, cutaneous infections.

It is not useful in penicillin-resistant staphylococci infections.

Dose: 500 mg 6th hourly.

METHICILLIN

It is a penicillin group of antibiotic which is used in penicillin resistant staphylococcal infections.

Dose: 1-2 gm. IM 6th hourly.
1 gm in 5-10 ml normal saline can be used as intrapleural or intra-articular therapy.

CLOXACILLIN/DICLOXACILLIN/FLUCLOXACILLIN

These drugs are used in penicillin resistant staphylococcal infections.

Dose: 500 mg 6th hourly.

CARBENICILLIN/TICARCILLIN

It is used in septicaemias, urinary tract infections mainly due to *Pseudomonas* and *Proteus* infections.

Dose: 1 gm 6th hourly IV.

PIPERACILLIN/AZOCILLIN/MEZLOCILLIN

It is active against *Pseudomonas.*

Dose: 2 gm 4th–6th hourly.

CLAVULANIC ACID

It is a beta lactamase inhibitor used against beta lactamase producing bacteria.

It is used along with amoxycillin/ticarcillin/ampicillin.

SULBACTUM

It is a beta lactamase inhibitor.

It is combined with ampicillin.

TAZOBACTUM

It is a beta lactamase inhibitor combined with piperacillin.

CARBAPENEM/IMIPENEM/MEROPENEM

These are bactericidal beta lactam antibiotic.

They are used in septicaemia, *Pseudomonas, Klebsiella* and *Proteus* infections.

LINCOMYCIN/CLINDAMYCIN

They act on bacterial ribosomal RNA.

Side effect: Pseudomembranous colitis.

Dose: 500 mg tds.

VANCOMYCIN/TEICOPLANIN

It inhibits cell wall synthesis.
Side effects: Nephritis, ototoxicity.
Used in pseudomembranous colitis.
Dose: 500 mg 6th hourly IV.

CEPHALOSPORINS

They are bactericidal. They inhibit bacterial cell wall synthesis.
Useful in most of the bacterial infections.
Side effects: Anaphylaxis, Hepatotoxicity, Nephrotoxicity.

Ist Generation	*IInd Generation*
Cephalexin 500 mg TDS oral.	Cefuroxime 500 mg BD oral.
Cephadroxyl 500 mg BD oral.	Cefaclor 500 mg 8th hourly.
Cephadrine 250 mg QID oral.	Cefamandone 2 gm 6th hourly.
Cephazolin 1 gm BD IV.	Cefoxitin 2 gm 8th hourly.
Cephalothin 2 gm 6th hourly.	Cefonicid 2 gm 6th hourly.
Cepharin 2 gm 6th hourly.	Ceforanide 2 gm 12th hourly.
IIIrd Generation	*IVth Generation*
Cefetoxime 1 gm 6th or 8th hourly.	Cefepime 200 mg BD orally.
Ceftriaxone 1 gm 12th hourly.	Cefpodoxime 200 mg BD orally.
Ceftizoxime 2 gm 8th hourly.	
Ceftazidime 2 gm 8th hourly.	
Cefaperazone 2 gm 12th hourly.	
Cefixime 200 mg BD orally.	

MACROLIDES

They act by inhibiting protein synthesis and also by blocking ribosomal activity.
Side effects: Allergic reactions, gastric irritation, cholestasis.
Uses: Respiratory infections, skin infections.
Drugs:
Erythromycin: 500 mg QID.
Roxithromycin: 150 mg BD.
Azhithromycin 500 mg OD before food for 3 days.
Clarithromycin 500 mg BD. It is also used as anti-*Helicobacter pylori* in treating duodenal ulcer.
Spiramycin 1-5 millions BD.

AMINOGLYCOSIDES

They block the RNA-ribosome combination and also inhibits the enzymes involved in Krebs' cycle.
Side effects: Ototoxicity (vestibular), nephrotoxicity.

Aminoglycoside will not get absorbed through the GIT because of high pH. So they are given either IM or IV. As bowel antiseptic they can be given orally.

Drugs:
1. Streptomycin: 0.75 gm IM OD for 3 months. Used in tuberculosis, plague, chancroid, granuloma inguinale, brucellosis, respiratory infections, gut sterilisation during large bowel preparation.
2. Kanamycin: 1.5 gm/day. It is more cochlear toxic.
3. Gentamicin: 80 mg BD IM or IV. 1 mg/kg body weight. Antipseudomonal drug.
4. Tobramycin 5 mg/kg body weight. More effective against *Pseudomonas* than gentamicin.
5. Amikacin 250 mg BD IM/IV. 15 mg/kg body weight.
6. Netilmycin: 3-6 mg/kg body weight.

7. Neomycin 1 gm 6th hourly. Mainly used in hepatic failure and in gut sterilisation.
8. Framycetin as 0.5% ointment.
9. Paromomycin: 2 gm QID. Used in amoebic dysentery.

TETRACYCLINES

They are bacteriostatic.

They act by inhibiting enzyme system, protein synthesis and ribosomal activity.

Side effects: Hepatic dysfunction, gastric irritation, permanent yellow staining of teeth, suppresses the bone growth.

Uses: Plague, cholera, sexually transmitted diseases like syphilis, gonorrhoea, chancroid, actinomycosis.

It is also used to identify malignant cells as brilliant yellow fluorescence under UV light after giving tetracycline for 5 days.

Dose: 500 mg QID.

Doxycycline: 100 mg OD/BD for 10-14 days.

CHLORAMPHENICOL / THIAMPHENICOL

It interferes with protein synthesis.

Side effects: Bone marrow suppression, Grey-baby syndrome, liver damage.

Uses: Typhoid fever, meningitis, plague.

Dose: 2 gm/day.

DRUGS FOR TUBERCULOSIS

RIFAMPICIN:

It inhibits DNA-dependent RNA polymerase. It is bactericidal.

Side effects: Hepatotoxicity, orange-red coloured urine, flu-like syndrome.

Uses: Tuberculosis.

Other uses: Leprosy, Meningococcal carrier, brucellosis, mycetoma, Q-fever, *Legionella, Chlamydia.*

Dose: 450-600 mg/day (OD) before food.

RIFABUTIN: 150 mg/day.

ISONICOTINIC ACID HYDRAZINE (INH):

It inhibits the synthesis of phospholipid synthesis of cell wall of bacteria. It is bactericidal.

Side effects: **I**ntolerance, **N**euritis, **H**epatitis.

It crosses the blood-brain barrier and placenta.

Dose: 300 mg orally OD.

ETHAMBUTOL: It is bacteriostatic.

Side effects: Gastric intolerance, retrobulbar neuritis (green colour vision is defective).

It crosses the blood-brain barrier and concentrates in CSF.

Dose: 25 mg/kg body weight. 800 mg OD after food.

PYRAZINAMIDE: It is bactericidal.

It acts on dormant bacteria, bacteria inside the macrophages and caseating material.

Side effects: Hepatotoxicity, hyperuricaemia, photosensitivity.

Dose: 1.5 gm OD after food or 750 mg BD after food for 2 months.

MORPHAZINAMIDE: 3 gm/day.

STREPTOMYCIN.

CYCLOSERINE: 2 gm daily. It is a reserve drug.

VIOMYCIN: 1 gm twice a week. IM. It is used in multi-drug-resistant tuberculosis.

AMIKACIN/KANAMYCIN.

CAPREOMYCIN.

PAS: Para-amino salicylic acid: It interferes with PABA metabolism of the bacteria.

Side effects: GIT intolerance, hepatotoxicity, blood abnormalities.

ETHIONAMIDE and PROTHIONAMIDE.

CLARITHROMYCIN.

AZHITHROMYCIN.

ANTIAMOEBIC DRUGS

DEHYDROEMETINE:
It acts on the trophozoite. But not on the cyst.
It is used for extra-intestinal amoebiasis.
Side effects: Myocarditis, myalgia.
Dose: 60 mg deep IM OD for 10 days given under monitor.

DIIDOHYDROXYQUINOLINE: 2 gm/day. It is more useful against trophozoites.

IDOCHLOROHYDROXYQUINOLINE: 0.75 gm/day. It is more useful in cyst passers.

CHLOROQUINE: Used for only extra-intestinal amoebiasis.
500 mg BD for 2 days.
250 mg BD up to 3 weeks.

METRONIDAZOLE:
400-800 mg tds for 10 days. Or 500 mg (1 mg/ml) tid IV.
It is used for intestinal and extra-intestinal amoebiasis.

TINIDAZOLE:
300-600 mg tid for 3-5 days.

SECNIDAZOLE:
2 gm single dose after food for intestinal amoebiasis.
2 gm OD for 5 days.

ORNIDAZOLE:

DILOXANIDE FUROATE:
500 mg tid for 10 days.
Used in cyst passers and chronic carriers.

TETRACYCLINES:
2 gm/day for 10 days.
It is used only as an adjuvant drug.

IMPORTANT ANTIHELMINTHICS

PIPERAZINE CITRATE:
Dose: 5 gm single dose. 1 ml = 150 mg.
Used for Ascariasis.
Side effects: Cerebellar ataxia, vertigo, convulsion.

TETRAMISOLE: 150 mg for adult, 50 mg for children. Used in ascariasis and ankylostomiasis.

MEBENDAZOLE: 100 mg BD for 3 days. 600 mg tid for 21 days.
Used in Ascariasis, Ankylostomiasis, Trichuris trichura, hydatid cyst.

ALBENDAZOLE: 400 mg single dose.

PRAZIQUANTEL: 500 mg tid for 15 days.

THIABENDAZOLE: 25 mg/kg for 3 days.

PYRANTEL PALMOATE: 11 mg/kg. 15 ml. (1 ml = 50 mg).

LUCANTHONE 1 gm tid for 3 days. **HYCANTHONE** 4 mg/kg orally for 4 days.
Used in S. haematobium, S. mansoni.

METRIFONATE: 7.5 mg/kg for 3 days.

NIRIDAZOLE: 25 mg/kg. Used in schistosomiasis.

ANTIMONY COMPOUNDS: Given intramuscularly.
Used in S. haematobium and leishmaniasis.

DIETHYL CARBAMAZINE CITRATE (DEC): 100 mg tid for 21 days.
Used in Filariasis, tropical eosinophilia, larva migrans.

LEVAMISOLE: 150 mg OD.
Used in ascariasis, hookworms, strongyloidosis, as immunomodulator in cancer.

> *It seems likely that in the next few years a combination of antibiotics with different antibacterial spectra will fernish a "cribrum therapeuticum" from which fewer and fewer infecting bacteria will escape.* **—Alexander Fleming**

ANTICOAGULANTS

HEPARIN: 10,000 units IV and later 5,000 subcutaneously 8th hourly.
Uses: DVT, pulmonary embolism, DVT prophylaxis.
Heparin therapy should be monitored by partial thromboplastin time (PTT).
Side effects: Haemorrhage, alopecia.
Protamine sulphate neutralizes the action of heparin. It is given IV slowly. Dose should not exceed 50 mg.

LOW MOLECULAR WEIGHT HEPARINS:
It has got longer duration of action. Monitoring is not required. Given as once a day regime.
Dalteparin 2500-10, 000 IV- SC/IV.
Enoxaparin: 40 mg SC.
Parnaparin.
Fraxiparin.

WARFARIN SODIUM:
It is an oral anticoagulant. It is monitored using prothrombin time.
Available as 5 mg tablets.
Dose: 10 mg OD.
It causes haemorrhage and drug interactions.

OTHER DRUGS

- **VITAMIN K:** 10 mg OD IM for 3-5 days. It is used in bleeding disorders, Vitamin K deficiencies in children, liver disorders.
- **ERYTHROPOIETIN**: 500 IU/kg thrice a week. It is used in chronic renal failure.
- **BROMOCRIPTINE**: *Dose:* 20 mg/day.
  It is used to suppress lactation, galactorrhoea, hyperprolactinaemia, parkinsonism, acromegaly.
- **CLOMIPHENE CITRATE**: Used in infertility.
  Dose: 50 mg for 5 days from 5th day of menstruation.
- **OCTREOTIDE:** 0.1 mg BD. Used after pancreatic surgeries in haematemesis, gut endocrine tumours.
- **VASOPRESSIN:** 20 IU IV/SC. Used in bleeding oesophageal varices.
  DESMOPRESSIN 4 microgram/day-SC-IV-NASAL SPRAY.
  TERLIPRESSIN: 2 mg IV.
- **L-THYROXINE**: 25, 50, 100, 200 microgram tablets.
  Uses: Myxoedema, cretinism for maintenance therapy after total thyroidectomy, as suppressive therapy in papillary carcinoma thyroid (300 μgm) in physiological goitre, in dyshormonogenesis.
- **ANTITHYROID DRUGS:** *Side effects:* Agranulocytosis and alopecia.
  CARBIMAZOLE: 5-20 mg daily exactly 8th hourly.
  METHIMAZOLE: 5-20 mg daily.
  PROPYLTHIOURACIL: 600 mg tid. Used in pregnancy and children.
- **DANAZOL**: It is used in fibrocystic disease of breast, gynaecomastia, mastalgia, infertility, precocious puberty.
  Dose: 800 mg OD.
- **ANTACIDS**: Aluminium hydroxide, magnesium trisilicate, sodium bicarbonate.
  Dose is variable.
- **CARBENOXOLONE:** 100 mg tid. It is used in peptic ulcer.
  It causes water and sodium retention, hypokalaemia.
- **H_2 RECEPTOR BLOCKERS**: Used in peptic ulcer.
  Cimetidine 1000 mg/day.
  Ranitidine 150 mg BD or 300 mg at bed time. Injection ranitidine 50 mg IV 6th-8th hourly.
  Famotidine: 40 mg OD.
  Roxatidine 75 mg OD.
  Nizatidine.
- **PROTON PUMP INHIBITORS:** Used in peptic ulcer.
  Omeprazole: 20 mg OD/BD 1 hour before food.
  Lanzoprazole: 30 mg OD before food.
  Esomeprazole 40 mg OD.
  Pantoprazole 40 mg OD before food.
- **PIRENZEPINE**: 50 mg BD. Used in peptic ulcer.

- **BISMUTH COLLOIDS**: Used in peptic ulcer. It is also anti-*Helicobacter pylori.* It stains the oral mucosa.
- **SUCRALFATE:** Used in peptic ulcer.
  Dose: 1 gm tid.
- **ONDANSETRON**: 8 mg BD. Orally or IV. It is used to prevent vomiting before starting chemotherapy.
- **LAXATIVES:**
  Castor oil: 16 ml HS.
  Phenolphthalein 300 mg HS.
  Bisacodyl 5 mg orally. HS or 100 mg as rectal suppositories.
  Isabgol as bulk laxative. 15 mg HS.
  Liquid paraffin: 30 ml HS.
- **ANTIDIARRHOEAL:**
  Bismuth kaolin.
  Diphenoxylate, atropine.
  Loperamide 2-4 mg 8th hourly or as required up to maximum of 16 mg/day dose.
- **PROKINETIC DRUGS:**
  Metoclopramide: Used in vomiting, dyspepsia, hiccough. It causes extra-pyramidal reactions.
  Domperidone: *Dose:* 10 mg tid before food. It does not cause extra-pyramidal reaction as it does not cross the blood-brain barrier.
  Cisapride: 10-40 mg/day before food. It can cause cardiac arrhythmias.
  Mosapride.
- **POTASSIUM:** It should be given only in IV drip slowly. IV *Bolus should not be given*. 2 mEq/ml.
  Dose: 20-40 m equivalents. IV should be given under ECG monitoring.
- **SODIUM BICARBONATE**: 7.5% w/v in correction of acidosis.

Appendix

Important Laboratory Values

URINE

Specific gravity:
Normal: 1.010 to 1.025. Low: less than 1.010. High: more than 1.025.
Fixed: 1.010 to 1.014.
Reaction: Acidic with a pH of 6.0.
Colour: Clear and amber coloured.

Parameter	**Values**
Aldosterone	2-10 µg/day
Nitrogen	0.4-1.0 gm/day
Amylase	30-250 Somogyi units/hour
Calcium	< 3.8 mmol/day
Catecholamines	< 100 U/day
Copper	< 25 µg/day
Creatinine	1.0-1.6 gm/day
Creatinine clearance	140-150 ml/min in males 105-130 ml/min in females
Estrogens	4-25 µg/day in males 5-100 µg/day in females. Very high in pregnancy
17-hydroxy corticosteroids	2-10 mg/day
5-HIAA	2-9 mg/day
17-ketosteroids	7-25 mg/day in men 4-15 mg/day in women
Magnesium	6.0-8.5 mEq/24 hours
Metanephrines	1.3 mg/day
Urine osmolarity	38-1400 mOsm/kg water
Phosphorus	0.9-1.3/day
Porphyrins	
Coprophyrin	50-250 µg/day
Uroporphyrin	10-30 µg/day
Potassium	25-100 mmol/day
Protein	< 150 mg/day
Sodium	100-250 mEq/day
Urobilinogen	1-3.5 mg/day
VMA	< 8 mg/day

BLOOD

Acetoacetic acid	< 0.3 mmol/litre
Acid phosphatase	1.0-5.0 King-Armstrong units
Alkaline phosphatase	20-90 IU/litre

Amino nitrogen	3.5-5.5 mg/dl
Amylase	60-180 Somogyi units
Ascorbic acid	0.4-1.0 mg/dl
Bicarbonate	23-29 mmol/litre
Bilirubin	Total 0.3-1.0 mg/dl. Direct 0.1-0.3 mg/dl Indirect 0.2-0.7 mg/dl
Calcium	9-11 mg/dl
Ionised	4.5-5.6 mg/dl
CO$_2$ in plasma	20–30 mmol/L. (50-70 volume %)
CO$_2$ tension in artery	35-45 mmHg
Ceruloplasmin	27-37 mg/dl
Chlorides	98-106 mmol/L
Cholesterol—total	150-250 mg%
Copper	115 + or –15 µg/dl
Cortisol	5-20 µg/dl
Creatine phosphokinase (CPK).	25-90 units/ml in males. 10 m-70 units/ml in females
Creatinine	< 1.5 mg/dl
Free fatty acids	0.7 mmol/litre
Gastrin	40-200 mg/dl
Glucose	70-110 mg/dl
17-OH corticosteroids	2-10 mg/day
IgG	800-1500 mg/dl
IgM	40-150 mg/dl
IgA	90-320 mg/dl
Insulin	6-26 µU/ml
17-keto steroids	7-25 mg/day in males. 4-15 mg/day in females
Lipase	1.5 units
Magnesium	0.8-1.3 mmol/litre
5’ nucleotidase	0.3-2.6 Bodansky units/dl
Osmolality	280-300 mOsm/kg of water
Oxygen.	17-21 volume % in arterial blood 10-16 volume % in venous blood
Oxygen saturation	97% in arterial blood. 60-85% in venous blood
pH of blood	7.36-7.44
Phosphorus, inorganic	1-1.4 mmol/litre
Potassium	3.5-5.0 mmol/litre
Protein—total	5.5-8.0 gm/dl
Albumin	3.5-5.5 gm/dl
Globulin	2.0-3.5 gm/dl
Sodium	136-145 mmol/litre
Sulphate inorganic	0.8-1.2 mg/litre
Testosterone	< 100 ng/dl in females. 300–1000 ng/dl in males
TSH	0-5 IU/ml plasma
Thyroxine (T4)	5-12 µg/dl
Triiodo thyronine (T3)	80-200 ng/dl
SGOT/AST	6-18 units/litre
SGPT/ALT	3-26 units/litre
Uric acid	2.5-8.0 mg/dl in males 1.5-6.9 mg/dl in females
Urea nitrogen (BUN)	10-20 mg/dl

RBC count	4.6-6.2 millions/mm^3 in males 4.2-5.4 millions/mm^3 in females 4.5-5.1 millions/mm^3 in children
Reticulocyte count	25,000-75,000/mm^3
WBC count	4,300-10,000/mm^3
Platelet count	1,50,000-4,40,000/cu mm
Bleeding time	1-4 minutes

Haematocrit	40-54 ml/100 ml
Clotting time	2-15 minutes
Clot retraction time	Apparent in 60 minutes, complete in 24 hours Usually < 6 hours
Plasma fibrinogen	160-400 mg/dl
Partial thromboplastin time	68-82 seconds Activated is 32-46 seconds
Prothrombin time	11-15 seconds
Haemoglobin	14-18 gm/dl males 12-16 gm/dl females 11-16 gm/dl children 16-19 mg/dl newborn
Fetal haemoglobin	< 2%
HaemoglobinA2	1.5-3.5%
Osmotic fragility	Begins in 0.45-0.39% NaCl and completes in 0.33-0.30%
Sedimentation rate (ESR)	< 10 mm in one hour in males < 20 mm in one hour in females

STOOL EXAMINATION

Bulk	100-200 gm
Water	75%
Osmolarity	250 mOsm/L
Colour	Brown
pH	7.0-7.5
Fat	< 7 gm/day
Stercobilinogen	50-280 mg/day
Urobilinogen	30-200 mg/100 gm
Nitrogen	< 2.5 gm/day
Calcium	0.6 gm/24 hours
Trypsin	20-90 units/gram

Further Reading

1. Bailey and Love’s Short Practice of Surgery, 25th edition.
2. Oxford Textbook of Surgery, 2nd edition.
3. Maingot’s Abdominal Operations, 11th edition.
4. Fischer’s Mastery of Surgery, 6th edition.
5. Sabiston Textbook of Surgery, 19th edition.
6. The Washington Manual of Surgery, 5th edition.
7. Farquharson’s Textbook of Operative General Surgery, 9th edition.
8. Surgery of Anus, Rectum and Colon by John Goligher, 5th edition.

Life ends always as “Incomplete”.

Index

A

Abdomen quadrants 773
Abdomen, blunt trauma 150
Abdominal cocoon 621
Abdominal compartment syndrome 827, 829
Abdominal dehiscence 788
Abdominal diagnostic paracentesis 151
Abdominal fluid 663
Abdominal incisions 1259
Abdominal tonsil 1006
Abdominal trauma 148
Abdominal trauma, management 151
Abdominal wall abscess 794
Abdominal wall, Meleney's bacterial gangrene 795
Abdominoperineal resection 1026, 1027
Aberrant renal artery 1084
Aberrant right subclavian artery 841
Abscess 40
Abscess drainage, Hilton's method 43
Abscess, alveolar 386
Abscess, amoebic liver 774
Abscess, anorectal 1049
Abscess, appendicular 781
Abscess, breast 556
Abscess, cold 45, 472, 473, 474
Abscess, collar stud 162, 472
Abscess, complications 42
Abscess, dental 386
Abscess, extradural 1182
Abscess, intracerebral 1182
Abscess, intracranial 1182
Abscess, ischiorectal 1050
Abscess, lung 1201
Abscess, metastatic 46
Abscess, metastatic cerebral 1201
Abscess, parapharyngeal 466
Abscess, parotid 438
Abscess, pelvic 607
Abscess, pelvirectal 1050
Abscess, perianal 1049
Abscess, perinephric 1089
Abscess, psoas 781
Abscess, pyaemic 45, 46
Abscess, pyogenic 40
Abscess, sites 41, 42
Abscess, splenic 723
Abscess, subdural 1182
Abscess, submucous 1050
Abscess, subphrenic 608
Abscess, treatment 43
Abscess, types 40
Acanthosis 392
Accessory appendicular artery of Seshachalam 1005
Accessory parotid tumour 454
Achalasia cardia 850
Achalasia cardia, barium swallow 851
Achalasia cardia, staging 851
Achalasia cardia, treatment 852
Achalasia cardia, triad 850
Achalasia, laparoscopic cardiomyotomy 853
Achalasia, Negus hydrostatic dilatation 852
Achalasia, Plummer's pneumatic dilatation 852
Achlorhydria 872
Achrochordon 84
Achylia 872
Acid phosphatase 1121
Acid-base balance 98
Acidosis, metabolic 99
Acidosis, respiratory 100
Acriflavine 1246
Acrocyanosis 211
Actinomyces israelii 56, 642
Actinomycosis 56
Actinomycosis jaw 386
Acute haemolytic reaction 125
Acute pyomyositis 67
Acute suppurative tenosynovitis 164
Adamantinoma 383
Adelaide coma scale 1175
Adenoma colon 962
Adenoma colon grading 962
Adenoma colon, therapeutic colonoscopy 963
Adenoma sebaceum 295
Adenomas, basophil 1186
Adenomas, chromophobe 1186
Adenomas, eosinophil 1186
Adenomas, prolactin-secreting 1186
Adhesiolysis, laparoscopic 1002
Adhesion, Gilroy Bevan triad 1001
Adhesion, prevention 1003
Adhesions and bands 1000
Adhesions, Child's-Phillips plication 1002
Adhesions, CT scan 1001
Adhesions, Noble's placation 1002
Adiposis dolorosa 71
Admiron's triangular hypothesis 680
Adrenal gland, secondaries 539
Adrenal incidentalomas 538
Adrenal mass 779
Adrenalectomy 542
Adrenalectomy, laparoscopic 543
Adrenocortical carcinoma 539
Adrenocortical carcinoma, Mc Falane staging 539
Adrenocortical tumours 538
Advanced trauma life support 143
Adynamic obstruction 983
Aerophobia 59
α-fetoprotein 645
Aflatoxin B1 643
AGES scoring 510, 512
Aggressive fibromatosis 84, 326, 791
Ainhum 215
Alcohol effects on pancreas 728
Alemtuzumab 356
Alkalosis, metabolic 99
Alkalosis, respiratory 99
Allograft 340
Allopurinol 1097
Alopecia, moth eaten 28
Alpha fetoprotein 628
Altemeir's rectosigmoidectomy 1034
Ambulatory venous pressure 242
Ameloblastoma 383
AMES scoring 510, 512
Aminoglutethimide 585, 1228
Amoebiasis cutis 632
Amoebic colitis, acute fulminant 961
Amoebic colitis, complications 961
Amoebic liver abscess, aspiration 634
Amoebic liver abscess, chronic 633
Amoebic liver abscess, percutaneous drainage 634
Amoebic liver abscess, sequelae 632
Amoebic liver abscess, treatment 634
Amoebic typhlitis 960
Amoeboma 781, 960
Ampulla of Vater 670
Amputation of penis, partial 1145

Amputation of penis, total 1145
Amputation stump, conical bearing 331
Amputation, 'Peg-leg' 335
Amputation, above-knee 213, 335
Amputation, below-knee 213, 334
Amputation, Boyd's 333
Amputation, Buerger's 213
Amputation, Burgess 334
Amputation, Chopart's 333
Amputation, complications 337
Amputation, forequarter 336
Amputation, Gritti-Stokes 335
Amputation, Guillotine 336
Amputation, hind quarter 335
Amputation, ideal stump 330
Amputation, incisions 331
Amputation, interscapulothoracic 336
Amputation, Krukenberg 336
Amputation, Lisfranc's 332
Amputation, modified Syme's 333
Amputation, patient evaluation 331
Amputation, Pirogoff's 334
Amputation, principles 331
Amputation, prosthesis 339
Amputation, Ray's 332
Amputation, Sir-Gordon Taylor's 335
Amputation, Syme's 333
Amputation, transmetatarsal (Gillies') 332
Amputation, Wagner's 333
Amputations 330
Amputations, types 330
Amsterdam criteria 965
Amsterdam criteria, modified 965
Amylase creatinine clearance ratio 730
Anaemia, Cooley's 718
Anaemia, erythroblastic target cell 718
Anaemia, mediterranean 718
Anaesthesia, caudal 1237
Anaesthesia, epidural 1236
Anaesthesia, general 1232
Anaesthesia, instruments 1101
Anaesthesia, intravenous regional 1235
Anaesthesia, postoperative care 1234
Anaesthesia, preoperative assessment 1231
Anaesthesia, regional 1235
Anaesthesia, spinal 1235
Anaesthesia, topical 1235
Anaesthetic agents 1232
Anaesthetic, gaseous 1232
Anaesthetics, intravenous 1232
Anaesthetics, volatile 1232
Anal canal, anatomy 1021
Anal canal, malignant tumours 1057
Anal canal, malignant tumours, AJCC staging 1058
Anal canal, sphincters 1021
Anal carcinoma, NIGRO regime 1058
Anal circling 1034
Anal cushions 1039
Anal dilatation 1042
Anal fissure, acute 1047
Anal fissure, chronic 1047
Anal fissure, chronic, dorsal fissurectomy 1048
Anal fissure, chronic, lateral anal sphincterotomy 1048
Anal fistula plug repair 1055
Anal incontinence 1059
Anal incontinence, secca therapy 1059
Anal intraepithelial neoplasia (AIN) 1057
Anal manometry 1032
Anal margin tumours 1057, 1058
Anal sphincter, external 1021, 1047
Anal sphincter, internal 1021, 1046
Anaplasia 282
Anastomosis, Kimura's diamond shaped 990
Anchovy sauce 631, 632
Anchovy sauce pus 33
Andy gump deformity 399
Anel's procedure 203
Aneurysm 44
Aneurysm, Berry 1182
Aneurysm, carotid artery 209
Aneurysm, cirsoid 225
Aneurysm, dissecting 209
Aneurysm, intracranial 1182
Aneurysm, mycotic 1183
Aneurysm, popliteal 208
Aneurysm, ruptured aortic 207
Aneurysm, splenic artery 722
Aneurysms 202
Aneurysms, abdominal 203
Aneurysms, abdominal, aortic 204, 205
Aneurysms, berry 202
Aneurysms, dissecting 202
Aneurysms, endoluminal stent 207
Aneurysms, false 202
Aneurysms, mycotic 203
Aneurysms, peripheral 208
Aneurysms, true 202
Angelchik prosthesis 846
Angiodysplasia, colon 974
Angiogram, aortic 180
Angiogram, coronary 1216
Angiogram, renal 1069
Angiogram, transbrachial 187
Angiography 180
Angiography, digital substraction, DSA 180
Angiography, indication 180
Angiography, retrograde transfemoral Seldinger 180
Angiolipoma 72
Angiomyolipoma 1098
Angiomyoneuroma 82
Angioplasty, balloon 216
Angioplasty, coronary balloon 1222
Angioplasty, percutaneous transluminal balloon 190
Angioscope 192
Angioscopy 216
Angle of 'His' 842
Anion gap 100
Anorchism 1161
Anorectal malformation, 'Wingspread' classification 1035
Anorectal malformation, treatment 1036
Anorectal malformations 1034
Anorectal myectomy 951
Anorectal strictures 1056
Antacids 884
Anterior resection 1028
Anthrax 61
Antibioma 42, 556, 558
Anticoagulants 252
Anticoagulants, *in vitro* 253
Anticoagulants, oral 253
Anti-*Helicobacter* regime 884
Anti-HIV antibody 63
Antilymphocytic globulin 355, 1229
Antimalignancy drugs 1227, 1228
Antiplatelet antibodies 718
Antiplatelet drugs 253
Antirabies serum 60
Antirabies vaccines, indication 59
Antireflux surgeries 845
Antisepsis 1244
Antitetanus globulin 51
Antitetanus serum 51
Antithyroid drugs 506
Antitubercular drugs 474
Antrectomy, de Miguel's 881
Antylus procedure 203
Aortic aneurysm 778
Aortic clamping 152
Aortic regurgitation 1221
Aortic stenosis 1221
Aortocaval fistula 205
Aortoenteric fistula 205
Aortofemoral bypass graft 184
Aortoiliac endarterectomy 183
Aortoiliac occlusive disease 183
Aortoiliac occlusive disease, types 183
APACHE II scoring system 890
Ape thumb deformity 276
Appendicectomy 1011, 1262
Appendicectomy, complications 1012
Appendicectomy, Fowler-Weir approach 1011
Appendicectomy, Fowler-Weir incision 1262
Appendicectomy, grid-iron incision 1262
Appendicectomy, incidental 1013
Appendicectomy, interval 1014, 1015
Appendicectomy, Lanz crease incision 1262
Appendicectomy, laparoscopic 1017
Appendicectomy, laparoscopic assisted 1018
Appendicectomy, negative 1014
Appendicectomy, retrograde 1012, 1262
Appendicectomy, Rutherford Morison incision 1262
Appendicectomy, troubles in 1013
Appendicitis sequelae 1010
Appendicitis, acute nonobstructive 1006, 1007

Appendicitis, acute obstructive 1007, 1008
Appendicitis, Alvarado scoring 1011
Appendicitis, Alvarado scoring, Kalam modified 1011
Appendicitis, children 1008
Appendicitis, chronic 1014
Appendicitis, CT scan 1010
Appendicitis, differential diagnosis 1009
Appendicitis, elderly 1008
Appendicitis, epidemic 1006
Appendicitis, grumbling 1014
Appendicitis, infancy 1008
Appendicitis, pregnancy 1009
Appendicitis, recurrent 1008
Appendicitis, simple 1014
Appendicitis, sonographic criterias 1010
Appendicitis, stump 1008, 1014
Appendicitis, subacute 1008
Appendicular abscess 1007, 1015
Appendicular mass 781, 1007, 1014
Appendix, carcinoid tumour 1017
Appendix, cystic neoplasms 1017
Appendix, duplication (Wallbridge classification) 1005
Appendix, duplication 1005
Appendix, mucocele 1007, 1016
Appendix, neoplasms 1017
Appendix, primary adenocarcinoma 1017
Appendix, surgical anatomy 1005
Apple-jelly nodule 26
Apudomas 536, 755
Arc of Riolan 948
Arimidex 585
Arm-foot venous pressure 242
Arterial diseases 175
Arterial diseases, treatment 190
Arterial graft 192
Arterial occlusion, acute 196
Arterial occlusion, traumatic 197
Arterial pile 1041
Arterial substitutes 220
Arteries, lower limb 175
Arteries, upper limb 175
Arteriovenous fistula 225
Arteriovenous fistula, acquired 227
Arteriovenous fistula, congenital 225
Artery, inferior thyroid 485, 523
Artery, superior thyroid 485
Artificial blood 127
ASCA 927
Ascending urethrogram 1069
Ascites 661
Ascites in portal hypertension 663
Ascites, encysted 622
Ascitic tap 662, 663
Ascoli's thermoprecipitation test 61
Asepsis 1244
Asepsis, wound scoring 36
Asepto syringe 1109
Askanazy cells 519
Astrocytomas 1183
Astrup formula 100
Atherectomy 191
Atherosclerosis 182
Atherosclerosis, management 183
Atherosclerosis, pathogenesis 182
Athlete's foot 172
Athyreosis 486
Atkinson tube 865
Atresia, apple peel 991
Atresia, duodenal 989
Atresia, intestinal (small intestine) 990
Atresia, intestinal, Griesfield modification of Martin's classification 991
Atrial septal defect, primum type 1218
Atrial septal defect, secundum type 1218
Atrial septal defect, sinus venosus type 1218
Atrophic blanche 238
Audit, clinical 1275
Audit, surgical 1275
Auerbach's plexus 839, 870
Autoclave 1244
Autograft 340
AV node 1216
Axillary nerve sampling 547
Axillary nodes management 589
Axillary nodes, Berg's levels 547
Axillary tail of Spence 545
Axonotmesis 273
Azathioprine 356, 927, 1229

B

Bacillus anthracis 61
Back wash ileitis 954
Bactec MGIT broth culture 619
Bacteraemia 45
Baker's tube 1002
Balanoposthitis 1141
Ball valve mechanism 801
Bandage, spica 1272
Bandages 1272
Bandages, cravet 1273
Bandages, roller 1272
Bandages, 'T' 1272
Bandages, tailed 1272
Bandages, triangular 1272
Bandages, tubular 1272
Bandaging, principles 1273
Bands 1003
Bariatric surgery 107
Barium enema 981
Barium enema, air contrast 982
Barium meal study 873
Barium swallow 841
Barnard's aphorism 610
Barrett's ulcer 849
Basal cell adenoma 445
Basal cell carcinoma, treatment 306
Basal cell naevus syndrome 303
Basal cell papilloma 298
Bascom technique 1038
Base ball finger 170
Bassini's repair 820
Bassini's stitch 808
Bat rabies 58
Bazin's disease 27
Beck's triad 1210
Bednar's tumour 296
Bedsore 21, 214
Beger's procedure 744
Beger's lavage 732
Belatacept 356
Belly cleft 793
Bench surgery 1094
Benign prostatic hyperplasia 1122
Benign prostatic hyperplasia, drugs in 1124
Benign prostatic hyperplasia, surgical management 1123
Benzidine test 1076
Berry picking 512
Berry's ligament 484, 492, 520
Bethesda criteria 965
Bevacizumab 585
Bile 670
Bile duct carcinoma 702
Bile duct injuries 708
Bile duct injuries, Hannover classification 709
Bile duct injuries, Stewart-Way classification 709
Bile duct injuries, Strasberg classification 708
Bilhemia 705
Biliary atresia 677
Biliary colic 683
Biliary dyskinesia 710
Biliary fistulas 703
Biliary obstruction, Benjamin's classification 696
Biliary papilloma, benign 699
Biliary sphincter dyskinesia 710
Biliary strictures 697
Biligram 671
Biliopancreatic diversion 110
Billing gate hump 86
Billroth I gastroduodenal anastomosis 881, 886
Biloma 709
Binachi's surgery 942
Biobrane 136
Biochemotherapy 1227
Biological valves 1222
Biopsy 286
Biopsy, excision 289
Biopsy, frozen section 290
Biopsy, incision 288
Biopsy, trucut 289
Biosyn 1256
Bisgaard method 250
Bite, bee 363
Bite, black widow spider 362
Bite, brown spider 363
Bite, mammalian 363
Bite, snake 362
Bite, spider 362

Bladder carcinoma, transitional cell 1112
Bladder carcinoma, treatment 1114
Bladder diverticula 1118
Bladder diverticula, acquired 1118
Bladder diverticula, congenital 1118
Bladder mass 781
Bladder outlet obstruction 1125
Bladder systolic 1082
Bladder tumour, carcinoma *in situ* 1113
Bladder tumour, Helmstein balloon degeneration 1114
Bladder tumour, intravesical chemotherapy 1114
Bladder tumour, muscle invasive 1113
Bladder tumour, radiotherapy 1114
Bladder tumour, superficial 1112
Bladder tumours 1112
Bladder tumours, Jewett-Strong-Marshall staging 1113
Bladder tumours, TNM staging (AJCC) 1113
Bladder, autonomous 1117
Bladder, cricket ball 1134
Bladder, extraperitoneal rupture 1115, 1116
Bladder, intraperitoneal rupture 1115, 1116
Bladder, motor paralytic 1117
Bladder, neurogenic 1117
Bladder, reflux neurogenic 1117
Bladder, sensory paralytic 1117
Bladder, systolic 1110, 1111
Bladder, thimble 1082, 1110, 1111
Bladder, uninhibited neurogenic 1117
Blair's incision 438
Bleeding duodenal ulcer, endoscopy 892
Bleeding duodenal ulcer, sclerotherapy 892
Bleeding gastric ulcer 893
Bleomycin 482
Block dissection, complication 481
Block, Bier's 1235
Block, field 1235
Block, infiltration 1235
Block, nerve 1235
Block, saddle 1236
Block, Winnie's 1235
Blood coagulation, mechanism 129
Blood fractions 124
Blood loss, measurement 122
Blood substitutes 126
Blood transfusion 124
Blood transfusion, autologus 127
Blood transfusion, blood collection 124
Blood transfusion, complication 125, 126
Blood transfusion, donor criteria 124
Blood transfusion, massive 126
Blood vessels, palpation 179
'Blow-out' fracture, orbit 376
Blue toe syndrome 207
Bluedome cyst of Bloodgood 551
Blumer's shelf 749, 907, 909
Blunt abdominal trauma 150
BM Achauer classification of burns contracture 137
Body mass index 106
Boil 46
Boiling 1244
Bolus obstruction 984
Bonin's Y-V plasty 1134
Borchardt's triad 900
Bottle nose 297
Botulinum toxin 853
Bouin's fluid 1163
Bourneville's disease 295
Bowen's disease 298
Boyle's apparatus 1233
Brachytherapy 1225
Brachytherapy, interstitial 1225, 1226
Brachytherapy, intracavitary 1225, 1226
Brachytherapy, surface 1226
Bradley's repeated laparotomy 732
Brain tumours, primary 1183
Brain death, criteria 353
Brain ischaemia 1173
Brain necrosis 1173
Brain oedema 1173
Brain, secondaries 1183
Branchia fistula, acquired 461
Branchia fistula, congenital 460
Branchial cyst 459
Branchial cyst, treatment 460
Brasdor's ligation 203
Breast cancer, Foote Stewart classification 565
Breast carcinoma 563
Breast carcinoma, tumour receptors 577
Breast carcinoma, advanced 590
Breast carcinoma, axillary clearance 589
Breast carcinoma, axillary sampling 579, 589
Breast carcinoma, bilateral 573
Breast carcinoma, biological behaviour 569
Breast carcinoma, bone secondaries 592
Breast carcinoma, BRCA genes 563
Breast carcinoma, chemotherapy 586
Breast carcinoma, chemotherapy regimes 586
Breast carcinoma, classification 565
Breast carcinoma, Columbia classification 575
Breast carcinoma, conservative surgeries 582
Breast carcinoma, core biopsy 576
Breast carcinoma, cutaneous manifestation 569
Breast carcinoma, discharge study 577
Breast carcinoma, ductal endoscopy 579
Breast carcinoma, ductography 579
Breast carcinoma, early, management 586
Breast carcinoma, edge biopsy 577
Breast carcinoma, Elston-Ellis modified Bloom-Richardson grading 569
Breast carcinoma, excision biopsy 576
Breast carcinoma, Fischer concept of spread 564
Breast carcinoma, FNAC 575
Breast carcinoma, FNAC scoring 576
Breast carcinoma, grading of the tumour 568
Breast carcinoma, haematogenous spread 571
Breast carcinoma, Halsted concept of spread 564
Breast carcinoma, hormone therapy 584, 585
Breast carcinoma, image guided biopsy 576
Breast carcinoma, locally advanced 590
Breast carcinoma, lymphatic spread 570
Breast carcinoma, male 593
Breast carcinoma, Manchester staging 573
Breast carcinoma, metastatic 591
Breast carcinoma, metastatic, chemotherapy 591
Breast carcinoma, metastatic, hormone therapy 591
Breast carcinoma, metastatic, radiotherapy 591
Breast carcinoma, metastatic, treatment 591
Breast carcinoma, modified Gail risk assessment model 564
Breast carcinoma, MRI breast 577
Breast carcinoma, neoadjuvant chemotherapy 586
Breast carcinoma, newer investigation modalities 579
Breast carcinoma, oestrogen receptor study 576
Breast carcinoma, Paget's cells 567
Breast carcinoma, pleural effusion 592
Breast carcinoma, pregnancy 594
Breast carcinoma, progesterone receptor status 577
Breast carcinoma, prognostic factors 592
Breast carcinoma, radiotherapy 583
Breast carcinoma, sentinel node biopsy 578, 589
Breast carcinoma, thermography 579
Breast carcinoma, TNM staging 573
Breast carcinoma, triple assessment 579
Breast carcinoma, trucut biopsy 576
Breast carcinoma, ultrasound 575
Breast carcinoma, wide local excision 582, 587
Breast conservative surgery 587
Breast cyst 559
Breast implants 596
Breast reconstruction 594
Breast self-examination 573
Breast, anatomy 544
Breast, ANDI 548, 551
Breast, atrophic scirrhous 567
Breast, blood supply 546
Breast, cystic swelling 560
Breast, ductal carcinoma 564
Breast, ductal carcinoma *in situ* 564, 565
Breast, fibrocystic disease 551

Breast, frozen section biopsy 576
Breast, hard swellings 597
Breast, inflammatory carcinoma 566, 591
Breast, lactating carcinoma 566
Breast, lactational abscess 556
Breast, lobular carcinoma 564
Breast, lobular carcinoma *in situ* 564, 567
Breast, lymphatic drainage 546
Breast, massive enlargement 597
Breast, medullary carcinoma 566
Breast, milk secretion 546
Breast, nerve supply 546
Breast, nerves-related 546
Breast, nipple discharge 597
Breast, nipple inversion 597
Breast, nipple retraction 597
Breast, nonlactational abscess 557
Breast, scirrhous carcinoma 566
Breast, secretory apparatus 544
Breast, topography 544
Breast, transcoelomic spread 572
Breast, tuberculosis 559
Brittle diabetes 744
Bronchial cast 141
Bronchoscopy 1199
Bronchoscopy, flexible 1199
Bronchoscopy, rigid 1199
Brown's vasomotor index 181
Brunner gland adenoma 936
Bubo 28
Buerger's angle of vascular insufficiency 179
Buerger's disease 184
Buerger's, exercise 188
Buerger's, position 188
Buffalo hump 260
Bunion 86, 173
Bupivacaine 1235
Burhenne technique 693
Burn contracture classification, BM Achauer 137
Burn contracture classification, Ifeanyichukwu 137
Burns 130
Burns contracture 137
Burns contracture, classification 137
Burns contracture, complication 137
Burns contracture, treatment 137
Burns, acid 141
Burns, alkali 141
Burns, assessment 132
Burns, assessment of airway injury 133
Burns, biologic dressings 136
Burns, chemical 141
Burns, classification 130
Burns, effects 134
Burns, first aid 134
Burns, first degree 130
Burns, fluid resuscitation 135
Burns, fourth degree 131
Burns, full thickness 132
Burns, inhalation 141
Burns, local management 135
Burns, management 134
Burns, Marjolin's ulcer 137
Burns, medicolegal aspects 142
Burns, metabolic changes 133
Burns, partial thickness 132
Burns, pathophysiology 132
Burns, second degree 131
Burns, sepsis 133
Burns, third degree 131
Burns, topical agents 136
Burns, toxic shock syndrome 134
Burns, types 130
Burns, wound coverage 136
Bursa anserina 86
Bursa bicipito-radial 85
Bursa, adventitious 86
Bursa, anatomical 85
Bursa, Brodie's 86
Bursa, complication 85
Bursa, infrapatellar 85
Bursa, olecranon 85
Bursa, porter's 86
Bursa, prepatellar 85
Bursa, psoas 85
Bursa, radial 164
Bursa, retrocalcaneum 86
Bursa, semimembranosus 86
Bursa, subacromial 85
Bursa, subhyoid 85
Bursa, tailor's 86
Bursa, ulnar 164
Bursa, Weaver's 86
Bursae 85
Bursae, types 85
Bursitis 85
Bursitis, retro-Achilis 86
Bursitis, subcalcaneal 86
Burst abdomen 788
Burst abdomen, modified Jones closure 790
Buschke Lowenstein tumour 1057

■ C

Cadaver donor 353
Caecal bascule 997
Café-au-lait spots 91, 92
Calcifying epithelioma of Malherbe 295
Calcinosis cutis 89
Calcitonin 518, 519
Calcitonin gene related peptide 1161
Calcium 531
Calculus, staghorn 1090, 1097
Calculus, urethral 1134
Calculus, vesical 1106
Calculus, uerteric 1094
Calf musculovenous pump 231
Callosity 170
Calot's triangle 670
Campbell de Morgan spots 229
Canal of Nuck 800
Canalicular adenoma 445
Cancer, Chimney sweep 299
Cancer, Kang 299
Cancer, Khangri 299
Cancer, management strategy 291
Cancer, tear 303
Cancer-en-cuirasse 569
Cancrum oris 391
Cantlie's line 666
Capitonnage 641
Capsule endoscopy 942
Carbimazole 506
Carbuncle 47
Carbuncle, renal 48
Carcinoembryonic antigen 970
Carcinogens, chemical 284
Carcinogens, microbial 284
Carcinogens, radiation 284
Carcinoid crisis 940
Carcinoid syndrome 939, 940
Carcinoid tumour 939
Carcinoma 282
Carcinoma alveolus 423
Carcinoma cheek 396
Carcinoma cheek, advanced 401
Carcinoma cheek, approaches 406
Carcinoma cheek, biological behaviour 398
Carcinoma cheek, Broder's classification 401
Carcinoma cheek, chemotherapy 407
Carcinoma cheek, clinical features 399
Carcinoma cheek, halitosis 399
Carcinoma cheek, premalignant lesions 396
Carcinoma cheek, radiotherapy 407
Carcinoma cheek, reconstruction after surgery 405
Carcinoma cheek, staging 399
Carcinoma cheek, TNM staging 399
Carcinoma cheek, treatment 401
Carcinoma cheek, verrucous 398
Carcinoma colon, adjuvant therapy 973
Carcinoma colon, air contrast barium enema 970
Carcinoma colon, Aster-Coller's staging 967
Carcinoma colon, barium enema 970
Carcinoma colon, chemotherapy 973
Carcinoma colon, colonoscopy 970
Carcinoma colon, Cunderson-Sosin staging 968
Carcinoma colon, Duke's histological grading 966
Carcinoma colon, Duke's staging 967
Carcinoma colon, local complications 970
Carcinoma colon, local recurrence 974
Carcinoma colon, modified Duke's staging 967
Carcinoma colon, Owen Wangensteen's second look operation 972
Carcinoma colon, radiotherapy 973
Carcinoma colon, screening 970
Carcinoma colon, TNM staging 968
Carcinoma colon, treatment 971
Carcinoma floor of the mouth 423

Carcinoma gallbladder 699
Carcinoma gallbladder, Nevin's staging 700
Carcinoma gallbladder, TNM staging 700
Carcinoma gallbladder, treatment 701
Carcinoma hard palate 427
Carcinoma *in situ* 284
Carcinoma lip 410
Carcinoma lip, treatment 412
Carcinoma oesophagus 840, 858
Carcinoma oesophagus, endoscopic mucosal resection 860
Carcinoma oesophagus, palliative treatment 864
Carcinoma oesophagus, TNM staging 861
Carcinoma oesophagus, treatment 860
Carcinoma oesophagus, types 859
Carcinoma of gingivobuccal complex 395
Carcinoma of penis, Broder's grading 1144
Carcinoma pancreas 747
Carcinoma pancreas, barium meal X-ray 752
Carcinoma pancreas, biopsy 751
Carcinoma pancreas, CA19-9 751
Carcinoma pancreas, endosonography 751, 752
Carcinoma pancreas, ERCP 751, 752
Carcinoma pancreas, laparoscopic US 751
Carcinoma pancreas, periampullary 748
Carcinoma pancreas, preoperative prepararion 752
Carcinoma pancreas, PTC 751
Carcinoma parathyroid 532
Carcinoma penis 1142
Carcinoma penis, Jackson's staging 1145
Carcinoma penis, radiotherapy 1146
Carcinoma penis, TNM staging 1145
Carcinoma penis, treatment 1145
Carcinoma peritonei 614
Carcinoma prostate 1126
Carcinoma prostate, Gleason grading 1126
Carcinoma prostate, TNM staging 1126
Carcinoma rectum 1023
Carcinoma rectum, tumour vaccine 1029
Carcinoma rectum, chemoradiation 1029
Carcinoma rectum, chemotherapy 1029
Carcinoma rectum, CT scan 1025
Carcinoma rectum, Duke's staging 1024
Carcinoma rectum, endorectal ultrasonography 1025
Carcinoma rectum, Haggitt's invasion of malignant polyp 1024
Carcinoma rectum, local recurrence 1027
Carcinoma rectum, lower anterior resection 1026, 1028
Carcinoma rectum, modified Duke's staging 1024
Carcinoma rectum, radiotherapy 1029
Carcinoma rectum, TNM staging 1024
Carcinoma rectum, total mesorectal excision 1026
Carcinoma stomach 902
Carcinoma stomach, adjuvant therapy 913
Carcinoma stomach, aetiology 902
Carcinoma stomach, barium meal study 910
Carcinoma stomach, biological behaviour 906
Carcinoma stomach, Birmingham staging 908
Carcinoma stomach, Borrmann's classification 904
Carcinoma stomach, chemoradiotherapy 913
Carcinoma stomach, chemotherapy 913
Carcinoma stomach, colloid 908
Carcinoma stomach, endomucosal resection 913
Carcinoma stomach, endosonography 910
Carcinoma stomach, immunochemotherapy 913
Carcinoma stomach, Japanese classification 904
Carcinoma stomach, laparoscopy 911
Carcinoma stomach, Lauren's classification 904
Carcinoma stomach, lymph node station (Japan) 913
Carcinoma stomach, lymphatic spread 906
Carcinoma stomach, Ming's classification 904
Carcinoma stomach, palliative treatment 914
Carcinoma stomach, precancerous lesion 904
Carcinoma stomach, precursor lesions 903
Carcinoma stomach, presentations 908
Carcinoma stomach, sentinel node biopsy 911
Carcinoma stomach, Siewert classification 905
Carcinoma stomach, TNM staging 907
Carcinoma stomach, transperitoneal spread 907
Carcinoma stomach, WHO histological classification 905
Carcinoma tongue 417
Carcinoma tongue, chemotherapy 422
Carcinoma tongue, clinical features 418
Carcinoma tongue, Commando operation 421
Carcinoma tongue, posterior one-third/ base 422
Carcinoma tongue, Price-Hill regimen 422
Carcinoma tongue, radiotherapy 422
Carcinoma tongue, spread 420
Carcinoma tongue, terminal events 422
Carcinoma tongue, treatment 421
Carcinoma, basal cell 303
Carcinoma, basisquamous 303
Carcinoma, branchiogenic 476, 478
Carcinoma, caecum 781
Carcinoma, cuniculatum 302
Carcinoma, cylindromatous 446
Carcinoma, Merkel cell 295
Carcinoma, nasopharyngeal 423
Carcinoma, squamous cell 24
Carcinoma, verrucous 24, 300, 301
Card test 458
Cardiac arrest 118
Cardiac catheterisation 1216
Cardiac massage, external compression 119
Cardiac massage, internal open 119
Cardiac pacing, postoperative management 1223
Cardiac pacemakers 1223
Cardiac patient, preoperative assessment 1216
Cardiac tamponade 1210
Cardiography 1216
Cardiopulmonary bypass 1217
Cardiospasm 850
Caries spine 1190
Carney's triad 917
Carotid blow out 482
Carotid body 468
Carotid body tumour, Shamblin's classification 468
Carotid body, syncope 468
Carpopedal spasm 538
Carr's postulates 1090
Catchpole regime 1000
Catgut, chromic 1256
Catgut, plain 1256
Catheter, Fogarty 198
Catheter, Foley's 1072
Catheter, Malecot's 1073
Catheter, red rubber 1073
Catheterisation, indwelling 1072
Catheterisation, intermittent 1072
Catheters 1071
Causalgia 275
Cautery, bipolar 1258
Cautery, blended 1258
Cautery, coagulation 1258
Cautery, cutting 1258
Cautery, unipolar 1258
Cavernous sinus thrombosis 37
CBD stones, primary, treatment 693
CBD stones, retained/residual, management 693
CBD strictures 697
CBD strictures, Bismuth's classification 697
Celestin tube 865
Celiac angiography 645
Cellcycle 1227
Cellulitis 37
Central node compartment neck dissection 515
Central venous pressure 116

Cerebral concussion 1172
Cerebral contusion 1172
Cerebral laceration 1173
Cervical rib 457
Cervical rib, treatment 459
Cetrimide 1245
CFTR 739
Chancroid 28
Charcot's triad 691
Charles Huggins 1128
Chassaigne tubercle 179
Cheek, anatomy 396
Cheilitis 408
Cheilitis, actinic 409
Cheilosis 391
Chemodectoma 468
Chemotherapy 1227
Chemotherapy, head and neck cancers 482
Chernobyl nuclear disaster 509
Cherry angiomas 229
Cherubism 388
Chest injuries, classification 1194
Chest injuries, management 1195
Chest injuries, thoracotomy indications 1195
Chest wall tumours, benign 1209
Chest wall tumours, primary malignant 1209
Chiba needle 672
Chick embryo cell culture vaccine 59
Chief cell 870
Child turcote pugh (CTP) scoring system 357
Child's grading 659
Child's grading, Pugh's modification 659
Chiropady 188
Chlorhexidine 1245
Cholangiocarcinoma 702
Cholangiocarcinoma, perihilar, Bismuth classification 702
Cholangiocarcinoma, risk factors 702
Cholangiocarcinoma, TNM staging 702
Cholangiogram IV 671
Cholangiogram, peroperative 673
Cholangiogram, postoperative T-tube 673
Cholangitis, sclerosing 699
Cholangitis, sclerosing, primary 699
Cholangitis, sclerosing, secondary 699
Cholecystectomy 705
Cholecystectomy, complications 706
Cholecystectomy, extended 701
Cholecystectomy, laparoscopic 705, 706
Cholecystectomy, laparoscopic, single incision 708
Cholecystectomy, open 705
Cholecystectomy, prophylactic 705
Cholecystitis acute, complications 684
Cholecystitis acute, treatment 686
Cholecystitis glandularis proliferans 689
Cholecystitis, acute 684
Cholecystitis, acute acalculous 684, 686, 694
Cholecystitis, chronic 688
Cholecystitis, emphysematous 685
Cholecystitis, *Salmonella* 694
Cholecystitis, xanthogranulomatous 694
Cholecystolithiasis 110
Cholecystoses 689
Cholecystostomy 686, 752
Choledochal cyst 675
Choledochal cyst, Todani modification of Alonso-Lej classification 676
Choledochal cyst, treatment 678
Choledochoduodenostomy 693
Choledochojejunostomy 693, 745
Choledocholithiasis 690
Choledocholithiasis, complications 691
Choledocholithiasis, primary stones 690
Choledocholithiasis, recurrent stones 691
Choledocholithiasis, retained stones 691
Choledocholithiasis, secondary stones 691
Choledochotomy 692, 693
Cholesterol crystals 460
Cholesterol polyposis 689
Cholesterosis 689
Chondrosarcoma 327
Chordee 1133
Chordee 1140, 1141
Chordee, dorsal 1141
Chordee, ventral 1141
Chordoma 93
Choudary Millis criteria 574
Christmas disease 129
Chronic duodenal ileus 898
Chronic venous insufficiency 237
Chylocele 1152
Chylothorax 271
Chylous ascites 271
Chyluria 271
Cidex 1246
Cilostazol 218
Circle of death 817
Circulatory failure 122
Circumcision 1139, 1140
Circumcision 1260
Cisplatin 482
Cisterna chyli 255
Clamp, Moynihan's occlusion 1251
Clamp, Payr's crushing 1251
Classification, deBakey's 210
Classification, Stanford 210
Claudication, arterial 176
Claudication, neurogenic 176
Claudication, venous 176
Claw hand 278
Claw hand, median 279
Claw hand, ulnar 278
Cleft disorder, LAHS classification 368
Cleft disorder, problems 368
Cleft lip 368
Cleft lip, Millard criteria 369
Cleft palate 368, 370
Cleft palate, treatment 372
Cleft surgery, Delaire timing 370
Clergyman's knee 85
Climatic bubo 29
Closed loop obstruction 969, 986, 972
Clostridium difficile 960
Clostridium tetani 49
Clostridium tetani, exotoxin 50, 53
Clostridium welchii 52
Clostridium welchii, exotoxins 53
Clotting factors 129
Clutton's joint 28
Clutton's joint 28
Coagulation cascade system 129
Coagulation, extrinsic 129
Coagulation, intrinsic 129
Coarctation of aorta 1218
Coffin corner 395
Coin test 1192
Cold abscess 474, 1192
Cold abscess, sequelae 475
Cold recovery time 189
Colitis, ischaemic 959
Colitis, pseudomembranous 960
Colitis, ulcerative 954
Collecting duct of Bellini carcinoma 1100
Collis' vertical gastroplasty 846
Colloid bismuth sulphate 884
Colloid carcinoma rectum 1024
Colocalisation hypothesis 729
Colon, benign tumours/polyp 961
Colon, diverticular disease 951
Colon, hamartomatous polyp 961
Colon, juvenile polyps 961
Colon, metaplastic/hyperplastic polyp 961
Colonic ischaemia 960
Colonic mass 777
Colonic mass, left side 778
Colonoscopy 1022
Colostomy 975
Colostomy, care 976
Colostomy, closure 976
Colostomy, complications 976
Colostomy, decompresseion 975
Colostomy, Devine's double-barrel 975
Colostomy, diversion 975
Colostomy, irrigation 975
Colostomy, loop transverse 975
Colostomy, permanent 975
Colostomy, temporary 975
Combined recurrent/superior laryngeal nerve palsy 529
Compartment excision 94
Compartment syndrome 8
Compartment syndrome, problems 9
Complete rupture urethra, treatment, railroad technique 1130
Compound palmar ganglion 165
Compression bandages, grading 251
Condyloma acuminata 1057
Condyloma lata 28
Congenital heart diseases 1217
Congenital hypertrophy of the retinal pigmented epithelium of iris (CHIRPES) 964

Congenital PUJ obstruction 1084, 1086
Coning 1173, 1177
Conley's point 452
Contracture, Dupuytren's 168
Contracture, hour-glass 882
Contracture, treatment 137
Contracture, Volkmann's ischaemic 168
Contre-coup injury 1173
Cooper's ligament repair 811
Corn 171
Corona phlebectatica 235
Coronary arteries 1215
Coronary balloon angioplasty 1222
Coronary sinus 1215
Correa cycle 903
Costoclavicular compression manoeuvre 458
Couinaud segments 666
Countryman's lip 411
Coup injury1173
Courvoisier's law 694, 749
Craniopharyngiomas 1187
Cresol 1245
Criles operation 480
Criminal nerve of Grassi 870
Crohn's disease 925
Crohn's disease, barium meal follow through 927
Crohn's disease, Vienna classification 926
Crossed leg test 178
Crurum puellarum frigidum 211
Crush syndrome 10
Crush syndrome, effects 10
Crush syndrome, treatment 10
Crutch palsy 280
Cryoprecipitate 125
Cryosurgery 1264
Cryptorchidism 1161, 1166
Csendes procedure 882
CSF rhinorrhoea 1176
CT scan 1240
CT scan, contrast agents 1240
CT scan, high resolution 1242
CTscan, spiral 1240, 1242
Culling 712
Cultured skin 136
Cushing's syndrome 539
Cutaneous neurofibromatosis 91
Cutaneous ureterostomy 977
CVP 116
Cyclical mastalgia 551
Cyclophosphamide 482
Cyclosporine 1229
Cyclosporine A 356
Cyst, acquired 74
Cyst, apoplectic 74
Cyst, chylolymphatic 611
Cyst, classification 74
Cyst, clinical features 74
Cyst, congenital 74
Cyst, degenerative 74
Cyst, dental 385
Cyst, dentigerous 384
Cyst, distention 74
Cyst, effects 75
Cyst, enterogenous 611
Cyst, epidermoid 79
Cyst, epididymis 1155
Cyst, false 74
Cyst, lymph 88
Cyst, mesenteric 780
Cyst, Morrant Baker's 87
Cyst, omental 614, 780
Cyst, parasitic 74
Cyst, periapical 385
Cyst, pseudopseudopancreatic 737
Cyst, radicular 385
Cyst, retention 74
Cyst, retroperitoneal 780
Cyst, sebaceous 79
Cyst, solitary renal 1077
Cyst, splenic, nonparasitic 724
Cyst, splenic, parasitic 724
Cyst, splenic, pseudo 724
Cyst, spring water 1206
Cyst, thyroglossal 487
Cyst, traumatic 74
Cyst, true 74
Cystectomy, partial 1114
Cystectomy, radical 1115
Cystic fibrosis 758
Cystic hygroma 89, 464
Cystic lesion, abdomen 780
Cystic swelling, neck 469
Cystitis 1110
Cystitis, interstitial 1110
Cystitis, recurrent 1110
Cystocele 800
Cystogastrostomy 736
Cystogram 1116
Cystosarcoma phylloides 552
Cystoscopic litholapaxy 1109
Cystoscopy 1071
Cysts 74
Cysts, lung 1204
Cysts, mesenteric 611

D

Dacron patch graft 1218
Danaparoid 252
Danazol 552
Dandy's brain cannula 1182
Darning, Abrahamson nylon 810
Davies and Starr buttock skin flap rotation 1038
Davis T-tube ureterostomy 1088
Day care surgery 1274
Day care surgery, ASA grading of patient 1274
Day care surgery, exclusion criteria 1274
DCIS 565
DCIS, management 566
DCIS, Nottingham prognostic index 566
DCIS, Van Nuy's prognostic index 566
D-dimer test 233
Deceleration injuries 1172
Decoy prostate 1122
Deep veins 230
Defaecography 1029, 1032
Defibrillation 120
Degloving injuries 10
Delayed capillary filling 178
Delayed venous refilling 178
Delphian nodes 485
Demodex folliculorum 79
Denis-Browne procedure 1133
Denonviller's fascia 1020
Dentate line 1021
Dermal flares 235
Dermal histiocytoma 296
Dermatofibroma 296
Dermatofibrosarcoma 326
Dermatofibrosarcoma protuberans 296
Dermoid, external angular 75
Dermoid, implantation 78
Dermoid, internal angular 75
Dermoid, sublingual 390
Dermoid, teratomatous 78
Dermoid, tubulo 78
Dermoids, sequestration 75
Dermoids, sequestration, complication 77
Dermoids, submental 78
Dermoids, types 75
Desmoid tumour 84
Dettol 1245
Devine and Horton's dermal flap 1142
Devine's exclusion procedure 914
Dexon 1256
Dextrans 126
Diabetic foot 213
Diagnostic peritoneal lavage (DPL) 149, 151
Diagnostic peritoneal lavage 714
Dialysis 359
Dialysis, peritoneal 360
Diaphragmatic defence 600
Diaphragmatic hernia, congenital 1211
Diaphragmatic hernia, traumatic 1213
Diastasis recti 796
Diathermy, types 1258
Diethylstilbesterol 585
Dietl's crisis 1084, 1086
Dieulafoy's disease 894
Dilator, Bake's 1251
Dilator, Clutton's 1132
Dilator, filiform 1132
Dilator, Lister 1132
Dilator, Lister's urethral 1254
Dionosil 857
Diosmin 242
Disease, Basedow's 499
Disease, Caisson's 202
Disease, Caroli's 676, 677
Disease, decompression 202
Disease, Dercum's 71
Disease, Goetsch's 499
Disease, Grave's 490, 499
Disease, hide porter's 61
Disease, Marion's 1134
Disease, Menetrier's 901, 903

Disease, Mondor's 546
Disease, Nonne-Milroy's 257
Disease, Ormond's 764
Disease, Parry-Romberg 229
Disease, Peyronie's 1141
Disease, Pick's 1210
Disease, Plummer's 490, 499
Disease, Reclus 568
Disease, Reiter's 1135
Disease, Schimmelbusch's 551
Disease, Sipple 518
Disease, Sipple's 536
Disease, Von Ricklinghausen 532
Disease, Wool sorter's 61
Disinfection 1244
Disinfection, methods 1244
Dislocation, mandible 380
Disobliteration 191
Disseminated intravascular coagulation 128
Distal run off 180, 186
Diverication of recti 796
Diverticular disease, colon 951
Diverticulitis 952
Diverticulitis, Hinchey's classification 953
Diverticulosis 952
D-lactic acidosis 941
DMSA 1070
Dohlman's operation 463
Donor organ retrieval 353
Doodleys lavage 1013
Doppler 179, 1240
Doppler test 240
Dormia basket 692, 693
Drain system, classification 1253
Drain, closed siphon 1253
Drain, closed suction 1253
Drain, corrugated rubber 1252
Drain, indications 1253
Drain, sump 1253
Drain, sump suction 1253
Drain, tube 1252
Drain, under water seal 1253
Drain, wick 1253
Drains 1252
Drains, problems 1253
Dressings 1272
Dressings, components 1272
Dressings, dry 1272
Dressings, wet 1272
Dresslers quadrangle 1146
Driver's bottom 1036
Dry perforation 890
DSA 180
DTPA 1070
Duct ectasia 558
Duct of Luschka 673
Duct papilloma 562
Duct, Bartholin 434
Duct, Santorini 725, 759
Duct, Stensen's 431
Duct, Wharton's 433
Duct, Wirsung 725, 759
Duodenal adenomatosis, Spigelmn classification 936
Duodenal atersia, 'Wind sock' deformity 989
Duodenal blow out 895
Duodenal diverticula 902
Duodenal diverticulum 924
Duodenal injury grading 153
Duodenal ulcer, barium meal X-ray 883
Duodenal ulcer, bleeding 891
Duodenal ulcer, bleeding, Forrest classification 891
Duodenal ulcer, bleeding, treatment 892, 893
Duodenal ulcer, complications 883
Duodenal ulcer, perforated 887
Duodenal ulcer, surgeries 884
Duodenal ulcer, treatment 884
Duodenoduodenostomy 990
Duodenum, anatomy 871
Duoderm 136
Duplex scan 179, 233, 241
Duplex scanning 1240
Duval procedure 745
DVT, prevention 235
Dynamic obstruction 983
Dysejaculation 836
Dyskeratosis 392
Dysmergia 1272
Dysphagia 840
Dysphagia lusoria 841
Dysphagia, causes 840
Dysplasia 283

E

EAST 179
E-cadherin gene 904
ECF excess 96
ECF loss 96
Echinococcus granulosus 637
Echinococcus granulosus, life cycle 637
Echocardiography 1216
Echosclerotherapy 243
Ectopia vesicae 1106
EGFR and VEGF blockers 973
Electric burns 139
Electric burns, complications 140
Electric burns, types 140
Electron microscopy 290
Elephant boot 333, 339
Elephantiasis, endemic 260
Elephantiatic neurofibromatosis 91
Eloiser's method 1200
Embolectomy 198, 200
Emboli lodging sites 197
Emboli, paradoxical 197
Embolisation, therapeutic 201
Embolism 197
Embolism, air 201
Embolism, arterial 197
Embolism, fat 201
Embolism, features 198
Embolism, investigations 198
Embolism, pulmonary 254, 1203
Embolus, saddle 200
Emil Theodor Kocher 526
Emphysema, surgical 1204
Emphysematous cyst, lung 1205
Emprosthotonus 51
Empyema necessitans 1200
Empyema thoracis 1199
Empyema thoracis, decortication 1200
Empyema thoracis, types 1200
Empyema, chronic subdural 1179
EMSU (early morning samples of urine) 1083
Endarterectomy 191
Endoscopic mucosal resection 860
Endoscopic necrosectomy 732
Endoscopic oesophageal staining 842, 860
Endoscopic pyelolysis 1088
Endoscopic retrograde cholangiopancreatography (ERCP) 671
Endoscopic surgery, natural orifice transluminal 1270
Endoscopic ultrasound 696
Endotracheal tube 1233
Endovascular aneurysm repair (EVAR) 206
Endovascular stapler 1266
Enlarged spleen 778
Entamoeba histolytica 960
Entamoeba histolytica, life cycle 631
Enteral feeding 102
Enteral feeding, advantages 103
Enteral feeding, complication 102
Enteral feeding, contraindication 103
Enteric perforation 929
Enteritis, regional 925
Enterocele 800, 806
Enteroclysis 942
Enteroscopy, push 943
Enteroscopy, Sonde 943
Enucleation 94
Ependymomas 1184
Epididymitis 171
Epididymitis, tuberculous 1171
Epididymo-orchitis, acute 1165
Epignathus 93
Epineurorrhaphy 274
Epi-perineurorrhaphy 274
Epiplocele 806
Episodic aphagia 856
Epispadias 1106, 1133
Epitaxy 1090
Epithelioid cells 473
Epithelioma 24, 299
Epstein pearls 367
Epstien-Barr virus 270
Epulis 382
Epulis, carcinomatous 383
Epulis, congenital 382
Epulis, fibrous 382
Epulis, giant cell 383
Epulis, granulomatous 383

Epulis, myelomatous 382
Epulis, pregnancy 382
ERCP, therapeutic 692
Erysipelas 38
Erysipeloid disease 39
Erythema induratum 27
Erythrocyanosis frigida 27
Erythromelalgia/erythralgia 210
Erythroplakia 393
Erythropoietin 127
Eschar 131, 136
Eschar, circumferential 137
Escharotomy 136
Eschmann blade 340
Eskimoma 441
Essen regimen 60
Esthiomene 29
Ether 1232
Ethrombosis 232
Ethylene 1256
Ettapan's lavage 604
Euro-Collins solution 354
Eusol 1245
EUSOL 251
Eusol bath 1245
Evan's formula 135
EVAR 206
Eve's disease 383
Eventration 1211
Exocrine pancreatic disease 763
Exomphalos 792
Exomphalos, major 793
Exomphalos, minor 793
Exophthalmometer 503
Exophthalmos 503
Exophthalmos, grading 504
Exophthalmos, malignant 503
Exophthalmos, pulsating 505
Exophthalmos, severe 503
Exophthalmos, treatment 503
Expansile impulse on coughing 804
External laryngeal nerve 527
External laryngeal nerve, injury 1263
External piles 1046
Extracorporeal shock wave lithotripsy (ESWL) 1092
Extrahepatic biliary tree 670

F

Facial nerve 432
Facial nerve injury 453
Facial nerve palsy, surgeries 454
Facial nerve, identification 452
Faciomaxillary diseases 367
Faciovenous plane of Patey 432
Factor VI and IX concentrate 125
Faecal fistula after appendicectomy 1016
Familial adenoma 936
Familial adenomatosis polyp 963
Familial hypocalciuric hypercalcaemia 533
Fascia of Waldeyer 1020
Fasciotomy 7, 9, 199
Fatty hernia of linea alba 831
Felon 161
Femoral canal, anatomy 822
Femoral canal, pathology 822
Femoral hernia 822
Femoral hernia, AK Henry's approach 824
Femoral hernia, hydrocele 822
Femoral hernia, Laugier's 822
Femoral hernia, Lotheissen's repair 824
Femoral hernia, Narath's 822
Femoral hernia, sliding 823
Femoropopliteal bypass graft 184
FFP 124
Fibrin cuff theory 236
Fibrinogen 125
Fibrinolysins 199, 234
Fibroadenoma 548
Fibroadenoma, complex 549
Fibroadenoma, giant 548
Fibroadenoma, juveline 549
Fibrocystadenosis 548, 551
Fibroepithelial polyp 416
Fibrolipoma 71
Fibroma 84
Fibroma, classification 84
Fibroma, hard 84
Fibroma, soft 84
Fibromyoadenoma 1122
Fibrosarcoma 336
Fibrous dysplasia of bone/jaw 386
Filariasis 259
Filariasis, extrinsic incubation period 259
Filarisis, biological incubation period 259
Finasteride 1124
Fine needle aspiration cytology (FNAC) 289
Fine needle non-aspirating cytology (FNNAC) 290
First heart sound 1215
Fish handler's disease 39
Fissure-in-ano 1046
Fistula 30
Fistula, aortoenteric 205
Fistula, aortocaval 205
Fistula, cimino 227, 360
Fistula, duodenal 895
Fistula, ECK 659
Fistula, enteric/gastrointestinal 943
Fistula, external 30
Fistula, faecal 979
Fistula, gastrojejunocolic 897
Fistula, internal 30
Fistula, parotid 438
Fistula, rectobulbar 1035
Fistula, rectovestibular 1035
Fistula, thyroglossal 488
Fistula, tracheo-oesophageal 857
Fistula, types 30
Fistula, umbilical 788
Fistula, urinary 1120
Fistula, vesicovaginal 1120
Fistula-in-ano 1051
Fistula-in-ano, cryptoglandular hypothesis 1051
Fistula-in-ano, gluing 1055
Fistula-in-ano, high level 1052, 1055
Fistula-in-ano, low level 1052, 1053
Fistula-in-ano, Park's classification 1052
Fistula-in-ano, standard classification 1052
Fistulectomy 1055
Fistulogram 33
Fistulotomy 1055
5-fluorouracil 482
Flap, Abbe 412
Flap, Bakamjian 348
Flap, cross leg 350
Flap, cutaneous 345
Flap, deltopectoral 348
Flap, Estlander's rotating 412
Flap, fasciocutaneous 345
Flap, forehead 348
Flap, free 347
Flap, Fries modified Bernard 412
Flap, gastrocnemius muscle 350
Flap, Gillies fan 412
Flap, groin 349
Flap, island 347
Flap, Karapandzic 412
Flap, latissimus dorsi muscle/myocutaneous 349
Flap, LD 594, 596
Flap, Limberg 350
Flap, local rotation 346
Flap, muscle 346
Flap, myocutaneous 346
Flap, Narayanan's 348
Flap, nasolabial 412
Flap, osteomyocutaneous 346
Flap, pectoralis major myocutaneous 349
Flap, radial forearm 350
Flap, Ruben's 595
Flap, saltatory 347
Flap, TRAM 594, 596
Flap, transposition 346
Flap, transverse rectus abdominis muscle (TRAM flap) 350
Flaps 344
Flaps, axial pattern 345
Flaps, random pattern 344
Flariasis, clinical incubation period 259
Flatulent dyspepsia 683
Flexor retinaculum 156
Flial chest 1196
Flial segment 1196
Fluid therapy 100
Fluids, colloids 101
Fluids, crystalloid 101
Fluorine-18 fluorodeoxyflucose PET scan 1025
Fluosoleda 127
Fluoxymestrone 585
Flutamide 1128
Foaming liver 53
Focused abdominal sonar trauma (FAST) 151
Fogarty catheter 198, 693
Foley's Y-V plasty 1088

Follicular odontome 384
Foot drop 280
Foramen of Langer 545, 546
Forceps, Allis' tissue holding 1248
Forceps, artery 1247
Forceps, Babcock's 1248
Forceps, Cheatle's 1247
Forceps, Desjardin's choledocholithotomy 1251
Forceps, Kocher's 1248
Forceps, Lane's tissue holding 1249
Forceps, Lister's sinus 1252
Forceps, Morant-Baker's appendix holding 1249
Forceps, non-toothed dissecting 1250
Forceps, Rampley's 1247
Forceps, right angle 1248
Forceps, sinus (Lister's) 1252
Forceps, sponge holding 1247
Forceps, toothed dissecting 1250
Fordyce's disease 81
Formaldehyde 1246
Fracture middle third area 375
Fracture nose 373
Fracture ribs 1195
Fracture ribs, non-traumatic 1196
Fracture, depressed skull 1180
Fracture, Guardsman 378
Fracture, Guerin 374
Fracture, mandible 378
Fracture, pyramidal 375
Fracture, zygomatic bone and arch 376
Fracture, zygomatic complex 376
Fractures, Le Fort 374
Fragility test 716
Freckle 308
French disease 56
Frequency 1107
Frey procedure 743, 744
Frog hand 162
Frostbite 23, 215
Frozen chest 1200
Frozen tongue 418
Fruchaud's myopectineal orifice 801
Fuezalida vaccine 59
Functional neck node dissection 513
Fundoplication, Dor anterior 845
Fundoplication, laparoscopic 845
Fundoplication, Lind anterior and posterior 845
Fundoplication, Nissen's 845, 852
Fundoplication, partial with mesh wrap 845
Fundoplication, Rosetti Hell anterior 845
Fundoplication, Toupet's 852
Fundoplication, Toupet's partial 180° posterior 845
Fundoplication, Watson's anterolateral 845
Fundoplications 845
Furuncle 46

G

Gabriel syringe 1043
Gaiter's zone 28, 249
Galactocele 554
Galactorrhoea 560
Galactorrhoea, primary 560
Galactorrhoea, secondary 560
Galezia triad 168
Gallbladder dyskinesia 710
Gallbladder polyp 699
Gallbladder, congenital anomalies 673
Gallbladder, diverticulosis 689
Gallbladder, double/triple 673
Gallbladder, empyema 687
Gallbladder, hydrops 688
Gallbladder, mobile/floating 673
Gallbladder, mucocele 688
Gallbladder, palpable mass 775
Gallbladder, polyp 689
Gallbladder, porcelain 694
Gallbladder, Strawberry 689
Gallbladder, surgical anatomy 669
Gallstone colic 683
Gallstone ileus 703
Gallstones 679
Gallstones, asymptomatic 694
Gallstones, dissolution therapy 690
Gallstones, effects 682
Gallstones, management 684
Gallstones, mixed 679
Gallstones, pigment 679
Gallstones, stones 679
Galveston regime 135
Ganglion 93
Ganglioneuroma 89
Gangrene 177, 211
Gangrene, diabetic 213
Gangrene, dry 177, 212
Gangrene, Fournier's 1148
Gangrene, wet 177, 212
Garrey's stricture 799, 931
Garrod's pads 168
Gas gangrene 52
Gas gangrene, complications 53
Gas gangrene, organism 52
Gas gangrene, polyvalent antiserum 54
Gas gangrene, prevention 54
Gas gangrene, treatment 54
Gas gangrene, types 53
Gastic pH 872
Gastrectomy 919
Gastrectomy, Billroth I 919
Gastrectomy, Billroth II 919
Gastrectomy, D1 912
Gastrectomy, D2 912
Gastrectomy, linear 885
Gastrectomy, lower radical 912, 919
Gastrectomy, Mak's pylorus preserving 881
Gastrectomy, nutritional deficiency 895
Gastrectomy, partial 881
Gastrectomy, total 912
Gastrectomy, upper radical 912, 919
Gastric acid, secretion 871
Gastric acid, function 872
Gastric adenocarcinoma, proximal, Siewart classification 905
Gastric antral vascular ectasia 894
Gastric cancer, advanced 904
Gastric cancer, distal 906
Gastric cancer, early 904
Gastric cancer, familial 902
Gastric cancer, Kajitani classification 905
Gastric cancer, morphovolumetric classification 905
Gastric cancer, Morson and Dawson classification 905
Gastric cancer, proximal 906
Gastric cancer, synchronous 906
Gastric cancer, WHO histological classification 905
Gastric carcinoma 776
Gastric carcinoma, Japanese classification 908
Gastric dilatation, acute 900
Gastric dysplasia 903
Gastric function test 872
Gastric hormones 873
Gastric lymphoma 915
Gastric lymphoma, Ann Arbor staging 916
Gastric lymphoma, Dawson's criteria 916
Gastric lymphoma, primary 915
Gastric lymphoma, secondary 916
Gastric motility 872
Gastric physiology 871
Gastric polyp 901
Gastric sarcomas 916
Gastric surgery, complications 894
Gastric tetany 887
Gastric ulcer 879
Gastric ulcer, bleeding 893
Gastric ulcer, complications 882
Gastric ulcer, pathology 879
Gastric ulcer, perforated 890
Gastric ulcer, types (Daintree Johnson) 880
Gastric varices 654
Gastrin 873
Gastrin releasing polypeptide 873
Gastrin-CCK receptors 872
Gastrinoma triangle 757
Gastrinoma, gastrin assay 757
Gastrinomas 757
Gastritis 877
Gastritis, chronic atrophic 903
Gastritis, erosive 878
Gastritis, granulomatous 878
Gastritis, lymphocytic 878
Gastritis, phlegmonous 878
Gastritis, reflux 878
Gastritis, stress 878
Gastritis, type A 878
Gastritis, type B 878
Gastrocolic reflux 949
Gastroduodenal diseases, investigation 873

Gastrograffin wash 993
Gastrointestinal mesenchymal tumours 916
Gastrointestinal stromal tumours 917
Gastrointestinal stromal sarcoma 918
Gastrojejunostomy of Mayo 886, 920
Gastro-oesophageal reflux disease (GORD/GERD) 840, 842
Gastro-oesophageal reflux disease, endoluminal therapies 844
Gastroschisis 793
Gastroscopy 874
Gastroscopy, therapeutic procedures 874
Gastrostomy 103, 918
Gastrostomy, Janeway's 104
Gastrostomy, Kader-Senn 104
Gastrostomy, percutaneous endoscopic 104
Gastrostomy, Stamm temporary 104
Gate control theory 364
Gelatin 126
Gene therapy 1230
General anaesthesia, complications 1234
General anaesthesia, premedication 1234
Geographic tongue 417
Germ cell therapy 1230
Gherlin 873
GI bleed 1061, 1064
GI bleed, angiography 1064
GI bleed, endoscopy 1064
GI bleed, modified Forrest classification 1061
GI bleed, nuclear scintigraphy 1064
GI bleed, occult 1063
GI bleed, Rockall scoring system 1061
Giant cell arteritis 190
Giant cell reparative granuloma 384
Gianturco-Rosch stent 865
Gibbus 1192
Gieger Muller's gamma ray counter 508
Gimbernat's ligament 822
GIST 917, 918
Glands of Blandin 389
Glasgow coma scale 1175
Glioblastoma multiforme 1184
Gliomas 1183
Glisson's capsule 627
Glomangioma 82
Glossitis 416
Glossitis, chronic superficial 417
Glossitis, Hunter's 417
Glossitis, median rhomboid 416
Glossitis, migrans 417
Glossitis, pellagra 417
Glucagonoma 758
Glutaraldehyde 1246
Glypressin 656
Godwin's tumour 441
Goiter, colloid 491
Goiter, diffuse hyperplastic 490, 491
Goiter, Hokkaido 499
Goiter, multinodular 490, 491
Goiter, plunging 497
Goiter, retrosternal 497
Goitre, classification 490
Goitre, WHO grading 491
Goodsall's operation 1030
Goodsall's rule 1053
Goose's foot 86
GORD, De Meester's scoring system 843
GORD, endoluminal therapy 844
GORD, treatment 844
Goserelin 1128
Gossypiboma 1266
Grading of duodenal injury 153
Graduated elastic compression garments 262
Graft 340
Graft contracture 343
Graft intake, stages 342
Graft rejection 359
Graft, endovascular 216
Graft, full thickness 344
Graft, partial thickness 340
Graft, skin 340
Graft, split thickness 340
Graft, Thiersch 340
Graft, Wolfe 344
Grafts, arterial 192
Granular cell myoblastoma 416
Granulation tissue 17
Granulation tissue, exuberant 19
Granulation tissue, healthy 18
Granulation tissue, unhealthy 19
Granuloma pyogenicum 49
Grawitz tumour 1100
Gray 1225
Great pox 56
Green IVC filter 254
Grynfelt's triangle 835
Gummatous ulcer 28
Gunthur-Tulip filter 254
Gustatory, sweating 452
Guyon's canal 278
Gynaecomastia 560
Gynaecomastia, neonatal 561
Gynaecomastia, pubertal 561
Gynaecomastia, senescent 561
Gynaecomastia, Simon's classification 561
Gynaecomastia, treatment 561

H

H_2 blockers 881, 884
Haemaccel 126
Haemangioma 221, 937
Haemangioma, capillary 222
Haemangioma, cavernous 223
Haemangioma, strawberry 222
Haemangiosarcoma 328
Haematemesis, causes 893
Haematemesis, management 894
Haematocele 1154
Haematoma, acute subdural 1178
Haematoma, chronic subdural 1178
Haematoma, extradural 1173, 1177
Haematoma, extradural, treatment 1178
Haematoma, rectus sheath 794
Haematoma, subdural 1173, 1178
Haematuria 1075
Haematuria, diffuse 1075
Haematuria, early 1075
Haematuria, endemic 1111
Haematuria, false 1075
Haematuria, microscopic 1075
Haematuria, silent 1075
Haematuria, terminal 1075, 1111
Haemobilia 631
Haemodialysis 360
Haemolytic anaemia, alloimmune 717
Haemolytic anaemia, autoimmune 718
Haemolytic anaemia, drug-induced immune 717
Haemolytic anaemia, immune 717
Haemophilia 129
Haemophilia, B 129
Haemophilia, classic 129
Haemorrhage 121
Haemorrhage, acute 121
Haemorrhage, acute on chronic 122
Haemorrhage, arterial 121
Haemorrhage, capillary 121
Haemorrhage, chronic 121
Haemorrhage, classification 121
Haemorrhage, concealed 121
Haemorrhage, gastrointestinal 1061
Haemorrhage, nonsurgical 122
Haemorrhage, pathophysiology 122
Haemorrhage, primary 121
Haemorrhage, reactionary 121
Haemorrhage, revealed 121
Haemorrhage, secondary 121
Haemorrhage, subarachnoid 1179
Haemorrhage, subarachnoid, Fischer grading 1180
Haemorrhage, subarachnoid, Hunt and Hess grading 1180
Haemorrhage, surgical 122
Haemorrhage, treatment 123
Haemorrhage, venous 121
Haemorrhagic shock, classification 122
Haemorrhoidectomy 1045
Haemorrhoidectomy, Hill-Ferguson method 1045
Haemorrhoidectomy, submucosal (Parks) 1045
Haemorrhoids 1038
Haemorrhoids, Barron's banding, 1043
Haemorrhoids, classification 1039
Haemorrhoids, cryo surgery, 1043
Haemorrhoids, Doppler guided artery ligation 1045
Haemorrhoids, infrared coagulation 1044
Haemorrhoids, laser therapy 1044
Haemorrhoids, primary 1039
Haemorrhoids, sclerosant therapy 1042
Haemorrhoids, secondary 1039
Haemorrhoids, treatment 1042
Haemostasis 129
Haemostat 1247

Haemothorax 1198
Haemothorax, thoracotomy indications 1198
Haggitt's invasion of malignant polyp (Colon) 967
Haimovici triad 199
Hairy tongue 417
Halitosis 420
Hallux valgus 173
Halogens 1245
Halsted nodes 547
Hamartoma 229
Hamartomata 229
Hand-bag stomach 882
Hand infections 157
Hand infections, complications 160
Hand infections, general features 157
Hand infections, management 159
Hand infections, types 157
Hand, blood supply 156
Hand, modified Verdan zones 156
Hand, muscles 156
Hand, nerve supply 156
Hand, surgical anatomy 156
Hard chancre 28
Hard corn 171
Hare lip 368
Harris Benedict equation 104
Hartmann's pouch 669
Hashitoxicosis 500
Hashitoxicosis 519
Hassab procedure 658
Heart, anatomy 1215
Heart, conducting system 1216
Heart, surface marking 1216
Heberdon's nodes 170
Heinz bodies 712
Helicobacter pylori 874, 875
Helicobacter pylori, enzymes and toxins 876
Helicobacter pylori, tests 876
Hemicolectomy, left sided 972, 973
Hemicolectomy, right 972, 973
Hemihepatectomy 645, 649, 666
Hemipelvectomy 336
Hemobilia 704
Henderson equation 99
Henderson-Hasselbalch equation 99
Hepar lobatum 28, 649
Heparin 252
Heparin, low molecular weight 252
Hepatectomy, total 645
Hepatic adenoma 642
Hepatic cystadenocarcinoma 651
Hepatic encephalopathy 665
Hepatic encephalopathy, grading 665
Hepatic failure 664
Hepatic failure, fulminant 664
Hepatic resection 665
Hepatic resection, techniques 666
Hepatobiliary cystadenoma 650
Hepatoblastoma 643
Hepatocellular carcinoma 643
Hepatoma 643, 774
Hepatoma Okuda staging system 644
Hepatoma, AJCC staging 644
Hepatoma, CLIP scoring 644
Hepatoma, CUPI scoring 644
Hepatoma, fibrolamellar varient 644
Hepatoma, intra-arterial chemotherapy 646
Hepatoma, neoadjuvant therapy 646
Hepatoma, Okuda classification 644
Hepatoma, palliative treatment 646
Hepatoma, percutaneous ethanol injection 646
Hepatoma, radiofrequency ablation 646, 649
Hepatoma, spread 644
Hepatoma, treatment 645
Hepatorenal syndrome 665
Her2/Neu receptor 577
Hereditary elliptocytosis 717
Hereditary nonpolyposis colonic cancer (HNCC) 964
Hereditary spherocytosis 716
Hermen-Taylor regime 890
Hernia 798
Hernia examination, rules 805
Hernia surgery, complications 836
Hernia through foramen Bochdalek 1212
Hernia through foramen of Morgagni 1213
Hernia, acquired 800
Hernia, Callison-Cloquet 823
Hernia, classification 799
Hernia, Cloquet's 822
Hernia, congenital 800
Hernia, contents 798
Hernia, Cooper's 823
Hernia, coverings 798
Hernia, diaphragmatic 1211
Hernia, different types 837
Hernia, double 821
Hernia, epigastric 831
Hernia, funicular direct 813
Hernia, giant inguinal 813
Hernia, Hesselbach's 823
Hernia, hiatus 847
Hernia, hiatus, classification 847
Hernia, incarcerated 817
Hernia, incisional 825
Hernia, infantile 821
Hernia, inflamed 799
Hernia, inguinal 800
Hernia, irreducible 799
Hernia, Littre's 800, 923
Hernia, lumbar 835
Hernia, Maydl's 818
Hernia, mesenteric defect 1004
Hernia, mesh repair, material used 814
Hernia, mesh repair, types 814
Hernia, mesocolic 1003
Hernia, obstructed 799
Hernia, obturator 834
Hernia, pantaloon 821
Hernia, paraduodenal 1003
Hernia, paraoesophageal 848
Hernia, parastomal 836
Hernia, parastomal, Devlin's classification 836
Hernia, paraumbilical 831
Hernia, parts 798
Hernia, prevesical 813
Hernia, recurrent 813
Hernia, reducible 799
Hernia, re-recurrent 814
Hernia, Richter's 800, 818, 834
Hernia, rolling 848
Hernia, Romberg 821
Hernia, sac 798
Hernia, saddle 821
Hernia, sciatic 836
Hernia, Serofini's 823
Hernia, sliding 820, 847
Hernia, Spigelian 833
Hernia, strangulated 800, 817
Hernia, strangulated omentum 819
Hernia, strangulated, in infancy 819
Hernia, strangulated, treatment 819
Hernia, Swiss cheese 824, 831, 832
Hernia, Teale's 823
Hernia, truss 812
Hernia, umbilical 829
Hernia, umbilical, laparoscopic repair 830
Hernia, umbilical, open dual PTFE and polypropylene mesh placement 830
Hernia, umbilical, sublay mesh repair 830
Hernia, ventral 824
Herniaaetiology 797
Hernia-en-glissade 820
Hernia-in-W 818
Hernias interparietal/interstitial 833
Herniography 800
Hernioplasty 811, 814, 1262
Herniorrhaphy, complications 809
Herniorrhaphy, modified Bassini's 807, 808, 1262
Herniotomy 807, 1261
Herpes labialis 409
Hesselbach's triangle 802, 811
Hexachlorophane 1245
Hiatus hernia, oesophageal 1213
Hibernoma 71
Hibitane 1245
HIDA scan 673
Hidradenitis suppurativa 46
Hidradenitis suppurativa, anal region 1060
Hilar injury, spleen 713
Hip disarticulation 335
Hippocrates facies 605
Hippocratic facies 888
Hirschsprung's disease 949
Histamine 873
Histamine receptors 872
Hitch stitches 1176
HIV infection, clinical classification 63
HIV, CD4 count 63
HIV, GIT problems 64
HIV, hospital and surgeon 65
HIV, modes of transmission 63

HIV, neurological problems 64
HIV, pulmonary problems 64
HIV, tests 63
HIV, treatment 64
HIV, tumours 64
HIV, universal precautions 65
HNPCC 902
HO's triangle 423
Hogarth Pringles's manoeuvre 697
Hollister bell cap technique 1140
Home parenteral nutrition 942
Honey comb liver 57
Honvan 1128
Hormone antagonist 1227
Hormone therapy, cancer 1227
Horse antirabies serum 60
Hose pipe colon 956
Hot-air oven 1244
Hounsfield number 1240
Housemaid's knee 85
Howell-Jolly bodies 712
Human albumin 4.5% 126
Human diploid cell vaccine 59
Human leucocyte antigen 353
Human rabies immunoglobulin 60
Humburg classification 221
Humby's knife 340
Hunger pain 883
Hunter's ligation 203
Hunterian chancre 28, 56
Hutchinson's contagious condyloma 392
Hutchinson's freckle 307
Hutchinson's melanotic freckle 311
Hutchinson's teeth 56
Hutchinson's triad 56
Hutchinsonian pupil 1177
5-hydroxyindoleacetic acid (5HIAA) 939
Hybridoma 1229
Hydatid cyst, complication 1205
Hydatid cyst, liver 637
Hydatid cyst, liver, Hassen Gharbi's ultrasound based classification 638
Hydatid cyst, liver, treatment 639
Hydatid cyst, liver, WHO classification 638
Hydatid cyst, lung 1205
Hydatid cyst, Water-lily appearance 1205
Hydatid disease, malignant 641
Hydatid fluid 638
Hydatid thrill 638
Hydradenoma 306
Hydrocele 1149
Hydrocele fluid 1150
Hydrocele of the neck 464
Hydrocele, bilocular 1151
Hydrocele, canal of Nuck 1151
Hydrocele, complications 1152
Hydrocele, congenital 1151
Hydrocele, encysted 1151
Hydrocele, filarial 1152
Hydrocele, hernia sac 1151
Hydrocele, infantile 1151
Hydrocele, postherniorrhaphy 1151
Hydrocele, primary vaginal 1150
Hydrocele, secondary 1151
Hydrocele, surgeries 1153
Hydrocele, tapping 1261
Hydrocele, treatment 1152
Hydrocele, types of surgery 1261
Hydrocele-en-bisac 1151
Hydrocephalus 1181
Hydrocephalus, classification 1181
Hydrogen peroxide 1246
Hydrohepatosis 695, 702, 749, 773
Hydronephrosis 1083
Hydronephrosis, intermittent 1084
Hydronephrosis, persistent 1084
Hydrophobia 58
Hydrotherapy 141
Hydroxyethystarch 126
Hygroma, chronic subdural 1178
Hypaque 434, 1069
Hypen veins 235
Hyperabduction manoeuvre 458
Hyperbaric oxygen 118
Hyperkalaemia 98
Hypermagnesaemia 98
Hypernatraemia 97
Hypernatraemia, types 97
Hypernephroma 1100
Hyperparathyroidism 532
Hyperparathyroidism, acute 532
Hyperparathyroidism, acute, treatment 533
Hyperparathyroidism, primary 532, 534
Hyperparathyroidism, secondary 532
Hyperparathyroidism, tertiary 532
Hyperparathyroidism, X-ray 533
Hypersplenism 723
Hyperthyroidism 499
Hyperthyroidism, apathetic 500
Hyperthyroidism, postpartum 500
Hyperthyroidism, signs 502
Hyperthyroidism, subclinical 500
Hypertrophic scar 12
Hypocalcemia, spurious 537
Hypocalcemia, temporary 537
Hypokalaemia 97
Hypokalaemic alkalosis 98
Hypomagnesaemia 98
Hyponatraemia 96
Hyponatraemia, hypervolemic 96
Hyponatraemia, normovolemic 96
Hypoparathyroidism 535, 537, 1263
Hypoparathyroidism, permanent 537
Hypoparathyroidism, temporary 537
Hypospadias 1132
Hypothyroidism 526
Hypovolaemia, types 113

■ I

I^{123} 508
I^{131} 508
Idiopathic gangrene of the scrotum 1148
Ifeanyichukwu classification of burns contracture 137
Ileal conduit 1120
Ileal interposition with sleeve gastrectomy 110
Ileal urinary conduit 977
Ileostomy 959, 977
Ilzarov method 188
Imatinib mesylate 917
Immunohistochemistry 290
Immunosuppression 1229
Immunosuppression, risks related 356
Immunosuppression, types 1229
Immunosuppressive agents 355
Immunotherapy 755, 1229
Immunotherapy, tumours used in 1229
Impetigo 49
In situ hybridisation, fluorescence (FISH) 290
In situ hybridisation 290
Incineration 1244
Incision, Galliard Thomas 550, 552
Incision, Grid-iron 1011, 1262
Incision, Lanz crease 1011
Incision, Mc'Burney 1014, 1262
Incision, Rutherford-Morrison 1011
Incision, Webster's 550
Incisional hernia, laparoscopic mesh repair 827
Incisional hernia, mesh repair 827
Incisional hernia, mesh repair, overlay 827
Incisional hernia, mesh repair, sublay 827
Incisional hernia, mesh repair, underlay 827
Incisional hernia, mesh replacement, Rive's Stoppa's 827, 828
Incomplete rupture urethra, treatment, Blandy approach 1130
Incomplete rupture urethra, treatment, Mitchell approach 1130
Index, ankle-brachial pressure 180
Index, pack year 185
Index, smoking 185
Induratio-penis plastica 1141
Infection, apical subungual 161
Infection, deep palmar space 162
Infection, HIV 62
Infection, hospital acquired 61
Infection, nosocomial 61
Infection, opportunistic 61, 62
Infection, terminal pulp space 161
Infection, web space 162
Infliximab 928, 958
Infrainguinal arterial occlusive disease 184
Infusion IVU 1068
Ingrowing toe nail 172
Inguinal block dissection, bilateral 1146
Inguinal block dissection, modified (Catalona) 1146
Inguinal block dissection, prophylactic 1146
Inguinal block dissection, superficial 1146
Inguinal block dissection, therapeutic 1146
Inguinal canal, anatomy 800
Inguinal canal, contents 800

Inguinal canal, defence mechanism 801
Inguinal hernia repair, anaesthesia 808
Inguinal hernia repair, local anaesthesia 808
Inguinal hernia, Bendavid classification 803
Inguinal hernia, classification 802
Inguinal hernia, direct 803, 805, 811
Inguinal hernia, direct, coverings 812
Inguinal hernia, Gilbert classification 803
Inguinal hernia, Gilbert classification, Robbin's modification 803
Inguinal hernia, indirect 802, 803, 805
Inguinal hernia, indirect, bubonocele 802, 804
Inguinal hernia, indirect, Casten's staging 803
Inguinal hernia, indirect, complete 802, 804
Inguinal hernia, indirect, coverings 804
Inguinal hernia, indirect, funicular 802, 804
Inguinal hernia, indirect, Halverson and McVay classification 803
Inguinal hernia, indirect, Ponka's classification 803
Inguinal hernia, indirect, scrotal 804
Inguinal hernia, NYHUS classification 803
Inguinal hernia, precipitating factors 804
Inguinal ligament 800
Inguinal ring, deep 800
Inguinal ring, superficial 800
Inguinodynia 811, 814, 836
Injuries, blast 147
Injuries, bullet 146
Injuries, chest 1194
Injuries, hand 166
Injuries, hand, classification 166
Injuries, hand, treatment 166
Injuries, head 1172
Injuries, kidney 1080
Injuries, kidney, grading 1080
Injuries, maxillary 374
Injuries, maxillofacial 372
Injuries, neck 146
Injuries, penetrating 148
Injury, axillary nerve 281
Injury, bladder 1115
Injury, brachial plexus 275
Injury, colon 154
Injury, common peroneal nerve 280
Injury, duodenal 152
Injury, duodenal, grading 153
Injury, lacrimal apparatus 373
Injury, liver 154
Injury, long thoracic nerve 281
Injury, medial poplitial nerve 281
Injury, median nerve 276
Injury, pancreatic 153
Injury, parotid duct 373
Injury, radial nerve 279
Injury, renal 154
Injury, reperfusion 199
Injury, seatbelt 155
Injury, small bowel 153
Injury, spinal 145
Injury, splenic 154, 712
Injury, steering wheel 1194
Injury, ulnar nerve 278
Injury, urethral 1129
Injury, urinary bladder 154
Insulinomas 755, 756
Insulinomas, radioimmunoassay 756
Insulinomas, treatment 757
'In transit nodules' 284, 312
Intercostal tube drainage 1202
Interleukin 2 receptor 356
Intermittent claudication 175
Intermittent claudication, Boyd's classification 176
Internal hernias 1003
Internal mammary nodes 547
Internal piles, primary 1021
Internist tumour 1100
Intervertebral disc prolapse 1189
Intestinal amoebiasis, surgical complications 960
Intestinal atresia, plain X-ray 991
Intestinal metaplasia 903
Intestinal obstruction, adynamic 1000
Intestinal obstruction, barium enema (microbar solution) 988
Intestinal obstruction, complications 988
Intestinal obstruction, CT scan 988
Intestinal obstruction, gastrograffin contrast enema 988
Intestinal obstruction, neonatal 994
Intestinal obstruction, pathogenesis 984
Intestinal obstruction, plain X-ray abdomen 985, 987
Intestinal obstruction, treatment 988
Intestinal obstruction, types 983
Intestinal obstruction, ultrasound 988
Intestinal tuberculosis, primary 615
Intestinal tuberculosis, secondary 616
Intra-abdominal pressure grading (Busch) 155
Intracranial abscess, acute 1182
Intracranial abscess, chronic 1182
Intracranial abscess, metastatic 1182
Intracranial abscess, subacute 1182
Intraductal ultrasound 696
Intravenous urogram 1067
Intrinsic factor 872
Intrinsic minus deformity 228
Intrinsic plus deformity 228
Intussusception 780, 994
Intussusception, Cope's method 997
Intussusception, retrograde jejunogastric 920
Intussusceptum 995
Intussuscipiens 995
'Inverted ink bottle' effect 1151
Iodophors 1245
Iohexol 1240
Iopamiro 1240
Iopanoic acid 670
Ischaemia, features 178
Ischaemia, upper limb 216
Ischaemia, upper limb, bypass surgeries 218
Ischaemia, upper limb, investigations 217
Ischaemia, upper limb, management 217
Ischaemic colitis, Marston's classification 959
Ischaemic heart disease 1222
Isograft 340
Isotope lymphoscintigraphy 257
Isotope renography 1070, 1087
IVC filter 254
IVU, Adder head appearance 1068
IVU, flower vase appearance 1068
IVU, horseshoe kidney 1076
IVU, hydronephrosis 1087
IVU, spider leg appearance 1068
IVU, ureterocele 1080
IVU-high dose 1081
IVU-polycystic kidney 1077

J

Jack stone 1107
Jack-knife position 1037
Jaffe's tumour 384
Jarisch-Herxheimer reaction 56
Jaundice 749
Jaundice, intermittent 749
Jaundice, obstructive 695, 749, 752
Jaundice, obstructive, classification 696
Jaundice, obstructive, pruritus 697
Jaundice, surgical 695
Jeep bottom 1036
Jejunoileal bypass 108
Jejunoileal diverticula 924
Jejunostomy 104
Jejunostomy, needle 104
Jejunostomy, Witzel 104
Johansen 'stepladder' procedure 412

K

K ras gene 748
Kaposis's sarcoma 328
Kaposis's sarcoma, African 328
Kaposis's sarcoma, AIDS associated 328
Kaposis's sarcoma, Europian 328
Kaposis's sarcoma, transplant associated 328
Kasai porto enterostomy 678
Keetly-Torrek procedure 1163
Keller's operation 173
Kelling Madlener procedure 882
Kelly's point 1035
Keloid 11
Keratin pearls 300, 401
Keratoacanthoma 296
Keratoconjunctivitis sicca 439
Kernohan's notch 1173
Kernohan's notch effect 1177
Ketamine 1232

Khaini chewers 410
Kidney shadow 1066
Kidney, anatomy 1065
Kidney, approaches 1104
Kidney, avascular plane (Brodel) 1066
Kidney, benign tumours 1098
Kidney, capsule 1066
Kidney, caseous/putty 1082
Kidney, cystic diseases 1076
Kidney, horseshoe 1076
Kidney, palpable mass 779
Kidney, polycystic disease 1077
Kidney, structure 1066
Killian's dehiscence 462, 838
Kirschner palliative gastric bypass 865
Kiss cancer 284
Kistner's valvuloplasty 250
Kit protein 917
Klatskin tumour 702
Koch's ileal conduit 1083
Kocher's vein 485
Koontz orchidectomy 813
Kous Netzoff aluminium needle 631
Krukenberg secondaries 572
Krukenberg's tumour 285, 907
Kuntz nerve 194
Kussmaul's breathing 100
Kuttner tumour 436
Kyphosis 1192

■ L

Ladd's band 992, 1211
Ladd's operation 990, 992
Ladd and Gross procedure 1163
Lahey and Cattell's relaxing skin incision 1038
Langerhan's cell 293
Laparoscopic adjustable gastric banding 108
Laparoscopic APR 1026
Laparoscopic cholecystectomy 1268
Laparoscopic posterior mesh rectopexy (LPMR) 1033
Laparoscopic sigmoid resection and resctopexy 1033
Laparoscopic surgery, advantages 1267
Laparoscopic surgery, complications 1268
Laparoscopic surgery, history 1267
Laparoscopic surgery, instruments 1267
Laparoscopic surgery, pneumoperitoneum 1268
Laparoscopic TAPP repair 1269
Laparoscopic, advanced surgeries 1269
Laparoscopic, appendicectomy 1269
Laparoscopic, TEP repair 1269
Laparoscopy, diagnostic 1270
Laparostomy 604
Large bowel, preparation for surgery 980
Large intestine, anatomy 948
Large intestine, lymphatic drainage 949
Laryngeal tumours, glottic 428
Laryngeal tumours, subglottic 428
Laryngeal tumours, supraglottic 428
Laryngeal cancer, radiotherapy 428, 429
Laryngeal mask airway 1233
Laryngeal nerve, recurrent 485, 523, 528
Laryngeal nerve, superior 485
Laryngeal surgery, conservative 430
Laryngocele 463
Laryngocele, external 464
Laryngocele, internal 464
Larynx, muscles 528
Lasers in surgery 1265
Latent period of Bandet 713
Leflunomide 356
Left to right shunt 1217
Leiomyosarcoma 327
Leprosy 55
Leprosy, multibacillary 55
Leprosy, paucibacillary 55
Leprosy, surgical complications 55
Leprosy, types 55
Lesgaft's triangle 835
Letrozole 585
Leugart's band 839
Leugart's pouch 839
Leukoplakia 392
Leukoplakia, hairy 392
Leuprolide 1128
Lid lag 502, 503, 504
Lid retraction 502, 503, 504
Lid spasm 503
Ligament of Cooper 546
Ligament of Treitz 1061
Ligation and excision of piles (Milligan-Morgan) 1045
Ligation of intersphincteric fistula track (LIFT) 1055
Ligation, Hunter's, 229
Ligation, quadruple 228, 227
Lignocaine 1235
Lily white appendix 1014
Limb ischaemia 176
Limb ischaemia, critical 177, 185
Limb ischaemia, Fontaine classification 176
Limb ischaemia, functional 177
Limb ischaemia, Rutherford classification 176
Limb ischemia, acute, classification 198
Limey gallbladder 681
Line of demarcation 177, 178
Lingual colic 436
Linitis plastica 908
Lintons tube 657
Lip, mucous cyst 408
Lip, verrucous carcinoma 410
Lipiodol 33, 434
Lipodermatosclerosis 236, 238, 250
Lipoedema 260
Lipoma 71
Lipoma arborigens 71
Liposarcoma 74, 325, 766
Lithogenic bile 680, 694
Littoral cell angioma 724
Livedo reticularis 210
Liver 627
Liver abscess, pyogenic 636
Liver abscess, pyogenic, open drainage 637
Liver abscess, pyogenic, percutaneous drainage 637
Liver biopsy 629, 645
Liver cyst 649
Liver cyst, congenital 649
Liver cyst, neoplastic 650
Liver cyst, simple 649
Liver cyst, traumatic 651
Liver function tests 628
Liver injury 629
Liver injury, CT grading 630
Liver injury, management 630
Liver transplantation, orthotopic 645, 661
Liver tumours 642
Liver tumours, benign 642
Liver, actinomycosis 642
Liver, amoebic abscess 631
Liver, blood supply 627
Liver, focal nodular hyperplasia 643
Liver, functions 628
Liver, haemangioma 642
Liver, honeycomb 642
Liver, massive enlargement 649
Liver, palpable left lobe 776
Liver, palpable mass 773
Liver, primary malignant tumours 643
Liver, secondaries 647
Liver, secondaries, classification 647
Liver, secondaries, treatment 649
Liver, segmental anatomy 628
Liver, space occupying lesions 668
Liver, surgical anatomy 627
Local haemostatic agents 123
Local recurrent rectal cancer 1027
Lockhart's tunica vaginalis flap 1142
Lord's anal dilatation 1042, 1048
Lord's plication 1153
Lowenstein-Jensen media 474, 619, 626
Lower GI bleed 1061
Lower GI bleed, classification 1063
Lower oesophageal sphincter 839
Lucid interval 1177
Ludwig's angina 38, 465
Lugol's iodine 506
Lung cyst 1204
Lung cyst, epithelial 1205
Lupus vulgaris 26
Lye stricture 854
Lympedim 262
Lymph node of '*Lund*' 670
Lymph node, microanatomy 256
Lymph nodes, deep cervical 455
Lymph nodes, facial 455
Lymph nodes, submandibular 455
Lymph nodes, submental 455
Lymph nodes, superficial cervical 455
Lymphangiography 257
Lymphangioma 88

Lymphangioma ab igne 464
Lymphangioma circumscripta 464
Lymphangioma diffusum 88, 464
Lymphangioma, capillary 88
Lymphangioma, cavernous 89, 464
Lymphangioma, circumscriptum 88
Lymphangiosarcoma 262, 328, 583
Lymphangitis 39
Lymphatic watersheds of skin 255
Lymphatics 255
Lymphatics of head and neck, anatomy 455
Lymphatics, function 256
Lymphoedema ab igne 88
Lymphoedema, Browse classification 257
Lymphoedema, Brunner's grading 260
Lymphoedema, complex decongestive therapy 262
Lymphoedema, lymphangiographic classification 257
Lymphoedema 257
Lymphoedema, filarial 259
Lymphoedema, Kinmonth classification 257
Lymphoedema, pathophysiology 258
Lymphoedema, primary 257
Lymphoedema, secondary 257, 259
Lymphoma, Ann-Arbor staging 267
Lymphoma, Burkitt's 270
Lymphoma, cutaneous T cell 270
Lymphoma, Hodgkin's 265
Lymphoma, Hodgkin's, treatment 268
Lymphoma, malignant of Africa 270
Lymphoma, MALT 270
Lymphoma, non-Hodgkin's 269
Lymphoma, non-Hodgkin's, Rappaport classification 269
Lymphoma, non-Hodgkin's, treatment 269
Lymphoma, non-Hodgkin's, working classification 269
Lymphoma, REAL classification 265
Lymphoma, Rye's classification 265
Lymphoma, staging laparotomy 267
Lymphomas 264
Lysol 1245
Lytle's repair 810

M

MACIS scoring system 512
Mackler's triad 857
Macroamylasaemia 726
Macrocheilia 408
Macroglossia 416
Madura foot 57
Madura hand 58
Madurella mycetomi 57
Mafenide acetate 136
Magnetic resonance cholangiopancreatography (MRCP) 673, 727, 1242
Magnetic resonance imaging 1242
Magpi repair 1133
Major histocompatibility complex 353
Major papilla of Vater 759
Malabsorptive bariatric surgery 107
Malaena 891
Malakoplakia 1116
Malgaigne bulging 812, 817
Malignant fibrous histiocytoma 326
Malignant histiocytoma 326
Malignant hyperthermia 1234
Malignant laryngeal tumours 427
Malignant laryngeal tumours, staging 428
Malignant mesothelioma 613
Malignant oedema 52
Malignant peripheral nerve sheath tumour 328
Malignant pustule 61
Mallampati scoring 1231
Mallet finger 170
Malrotation 991
MALTOMA 915
Mammary dysplasia 551
Mammary fistula of Atkins 563
Mammography 547, 574
Mammography, bilateral 590
Mammography, diagnostic 548
Mammography, screening 548
Mandibular resections 406
Mandibulectomy, marginal 406
Mannheim peritonitis index 606, 890
Manoeuvre, costoclavicular compression 179
Manoeuvre, hyperadduction 179
Manoeuvre, scalene 179
Marjolin's ulcer 300, 302
Maryfield introducer 1073
Mass abdomen, differential diagnosis 771
Mass abdomen, investigations 782
Mass, epigastrium 775
Mass, hypogastrium 781
Mass, left hypochondrium 778
Mass, left iliac fossa 781
Mass, lumbar region 778
Mass, right hypochondrium 773
Mass, right iliac fossa 780
Mass, umbilical region 780
Massive bowel resection 941
MAST 116
Mastalgia 553
Mastalgia, cyclical 551, 553
Mastalgia, noncyclical 553
Mastectomy, Auchincloss modified radical 581
Mastectomy, complications 583
Mastectomy, extended radical 583
Mastectomy, Halsted radical 582
Mastectomy, prophylactic 593
Mastectomy, simple 480
Mastectomy, skin sparing 583, 588
Mastectomy, subcutaneous 552
Mastectomy, toilet 583
Mastectomy, total 580
Mastectomy, total with axillary clearance 580
Mastitis 555
Mastitis carcinomatosis 566
Mastitis, intramammary 556
Mastitis, periductal 558
Mastitis, plasma cell 558
Mastitis, retromammary 557
Mastitis, subareolar 555
Matas endoaneurysmorrhaphy 203
Maxillary tumours 424
Maxillary tumours, behaviour 424
Maxillary tumours, Lederman's classification 425
Maxillary tumours, Ohngren's classification 424
Maxillary tumours, TNM staging 425
Maxillofacial injuries, classification 372
Maxillofacial injuries, Le Fort's classification 374
Maxillofacial injuries, primary care 374
Maxon 1256
Mayo's procedure 173
McFarlane staging 539
McBurney's point 1008
McBride procedure 173
McCune-Albright syndrome 92
MCR foot wear 212
Mebeverine HCl 958
Mechanical valves 1222
Meckel's diverticulectomy 924
Meckel's diverticulum 786, 923
Meconium ileus 992
Meconium ileus, complication 993
Median nerve palsy 276
Mediastinal flutter 1196
Mediastinal tumours 1205
Medusa head 61
Megacolon, acquired 951
Megacolon, congenital 949
Megaloglossia 416
Meggitt's classification 213
Meglumine ioglycamate 671
Meglumine iothalamate 1067, 1240
Meissner's plexus 870
Melanoblast 308
Melanocyte 308
Melanoma 308
Melanoma, acral lentiginous 312
Melanoma, AJCC classification 309
Melanoma, amelanotic 312
Melanoma, biochemotherapy 316
Melanoma, Breslow's classification 309
Melanoma, Clark's concept 312
Melanoma, Clark's level 309, 310
Melanoma, clinical types 310
Melanoma, desmoplastic 312
Melanoma, endolymphatic therapy 316
Melanoma, Glasgow criteria 312
Melanoma, immunotherapy 316
Melanoma, isolated limb infusion 316
Melanoma, isolated limb perfusion 316
Melanoma, lentigo maligna 311
Melanoma, newer TNM staging 313
Melanoma, nodular 310
Melanoma, occult 313
Melanoma, ocular 312

Melanoma, risk factors 309
Melanoma, satellite nodules 312
Melanoma, sentinal lymph node biopsy 315
Melanoma, staging 313
Melanoma, subungual 312
Melanoma, superficial spreading 310
Melanoma, treatment 314
Melanoma, tumour markers 313
Melanophages 308
Melanophores 308
Melanosis 962
Melanuria 313
MELD score 357
Meleney's infection 65
Melon seed bodies 165
Melphalan 316
MEN syndrome 536
MEN syndrome type 71, 91
Menghini needle 629
Meningiomas 1184
Meningocoele 1188, 1189
Meningomyelocoele 1188, 1189
Meralgia paraesthetica 281
Mercurochrome 343
Mesalamine 957
Mesenteric desmoid tumour 612
Mesenteric lymphoma 612
Mesenteric malignancy 612
Mesenteric tear 152
Mesenteric trauma 613
Mesenteric vessel ischaemia 931
Mesenteric vessel ischaemia, treatment 933
Mesh repair, Gilbert 815
Mesh repair, Gilbert's PHS repair 815
Mesh repair, inlay 814
Mesh repair, Lichtenstein tension free 814
Mesh repair, modified Rives preperitoneal 814
Mesh repair, Nyhus preperitoneal 814
Mesh repair, onlay 814
Mesh repair, totally extraperitoneal laparoscopic (TEP) 815, 817
Mesh repair, transabdominal preperitoneal laparoscopic (TAPP) 813, 815
Mesher 343
Metastatic emphysema of Read 798
Methimazole 506
Methotrexate 482
Michaelis Gutmann bodies 1116
Mickulicz Miles perineal transanal rectosigmoidectomy 1034
Microbar solution 874
Microdochectomy 562
Microfilaria 259
Micturating cystourethrography 1069, 1134
Mikulicz disease 440
Military antishock trouser 116
Military attitude 1192
Milker' nodes 166
Miller procedure 264
Mill-Wheel murmur 201
Milnes-Walker thoracic oesophageal transection 658
Milwaukee's classification 710
Miner's beat knee 85
Miner's elbow 85
Minimal incision aortic surgery (MIAS) 206
Minnesota tube 657
Minute IVU 1068
Mitotane 586
Mitral commissurotomy, open 1221
Mitral regurgitation 1221
Mitral stenosis 1220
Mitral volvotomy, closed 1220
Modified Brooke formula 135
Modified radical neck dissection 512
MODS 45, 46, 112, 114, 117, 132, 888
MOHS 306
Mole, hairy 307
Mole, nonhairy 307
Molluscum sebaceum 296
Mongolian's spot 308
Monilial thrush 391
Monks localising zones 153
Monoclonal antibodies 1230
Monoclonal antibody 356
Monocryl 1256
Montgomery tubercles 545
Morison's aphorism 37
Moth eaten alopecia 28
Mount Vernon box frame 376
Mousseau-Barbin tube 865
Moynihan's aphorism 680, 694
Moynihan's caterpillar hump 673
Mucocele of frontal sinus 75
Mucus glands of Nuhn 389
Muir and Burclay regime 135
Muir low anterior resection 1034
Mulberry stone 1107
Muller's muscle 502
Multiple cylindroma 306
Murphy's triad 876
Murugassu's technique 1035
Muscarinic receptors 872
Muscle relaxant, depolarising 1232
Muscle relaxant, nondepolarising 1232
Myasthenia gravis 1207
Mycetoma pedis 57
Mycobacterium tuberculosis 54
Mycophenolate mofetil 356, 1229
Mycotic aneurysm 203
Myelinic neuroma 89
Myelocele 1188
Myotomy 954
Myotomy, cricopharyngeal 463
Myotomy, Heller's 954
Myotomy, Ramstedt's 954
Myotomy, Reilly's 954
Myxoedema coma 527
Myxoedema, pretibial 504

N

Naevi 306
Naevolipoma 71
Naevus flammeus 222
Naevus of Ota 307
Naevus sebaceous of Jadassohn 294
Naevus spilus 307
Naevus, blue 307
Naevus, compound 307
Naevus, dysplastic 307
Naevus, giant 308
Naevus, halo 307
Naevus, intradermal 307
Naevus, Ito 307
Naevus, junctional 307
Naevus, juvenile 307
Naevus, spindle cell 307
Naevus, Spitz 307
Nagler reaction 54
Nail, floating 160
Nail, hang 160
Napkin ring stricture 617
Narbona's ligamentum teres cardiopexy 846
Narcotic analgesics 366
Nasojejunal feeding 1266
Nasopharyngeal carcinoma 423
Nasopharyngeal carcinoma, treatment 423
Neck dissection, bilateral 481
Neck dissection, classic radical 480
Neck dissection, extended radical 481
Neck dissection, modified radical 480
Neck dissection, supraomohyoid block 481
Neck dissection, types 480, 482
Neck lymph nodes, memorial Sloan-Kettering cancer centre levels 475
Neck lymph nodes, secondaries 475
Neck lymph nodes, secondaries with occult primary 477, 479
Neck lymph nodes, secondaries, blind biopsy 477
Neck lymph nodes, secondaries, features 476
Neck lymph nodes, secondaries, FNAC 478
Neck lymph nodes, secondaries, staging 478
Neck lymph nodes, secondaries, treatment 479
Neck lymph nodes, secondaries, types 477
Necrosis 177
Necrotising enterocolitis 934
Necrotising fasciitis 65, 67
Needle holder 1251
Needle, Hagedorn 1250
Needles, atraumatic 1250
Needles, cutting 1251
Needles, round body 1251
Needles, surgical 1250
Needles, traumatic 1250

Negri bodies 58
Neoadjuvant chemoradiotherapy 755
Neoplasia, etiological factors 284
Neoplasm 282
Neoplasm, benign 282
Neoplasm, malignant 282
Neoplasm, malignant, locally 282
Neoplasm, malignant, locoregionally 282
Neoplasm, malignant, systemic 282
Neostigmine 1232
Nephrectomy 1100
Nephrectomy, partial 1094
Nephrectomy, radical 1103
Nephrectomy, subcapsular 1088
Nephroblastoma 1099
Nephrolithotomy 1092
Nephron sparing surgery 1103
Nephropyelolithotomy 1092, 1098
Nephrostomy 1074
Nephrostomy, bilateral 1088
Nephrostomy, Cabot's 1074, 1088, 1098
Nephrostomy, percutaneous 1074
Nephrostomy, Tresidder's loop 1074
Nephroureterectomy 1076, 1083
Nerve of Latarjet 870
Nerve suturing 274
Neurilemmoma 92
Neuroblastoma 89, 540
Neuroblastoma, Hutchinson's type 540
Neuroblastoma, Pepper type 540
Neuroblastoma, *Shimada* histological classification 541
Neuroblastoma, staging 541
Neurofibroma 90
Neurofibroma, complications 92
Neurofibroma, nodular 91
Neurofibroma, plexiform 91, 92
Neurofibroma, vagus nerve 468
Neurolipoma 71
Neuroma 274
Neuroma, end 89
Neuroma, false 89
Neuroma, lateral 89
Neuroma, true 89
Neuroma, types 89
Neuropraxia 273
Neurotmesis 273
Niche 873, 880
Nitrous oxide 1232
NNIS system 68
'No re-flow' phenomenon 199
No scalpel vasectomy 1260
Nocardia asteroids 57
Nocardia madurae 57
Noma 391
No-man's land 157
Nonchromaffin paraganglioma 468
Non-heart beating donors 354
Non-narcotic drugs 366
Non-nucleoside reverse transcriptase inhibitor (NNRTI) 64
Nonocclusive mesenteric ischaemia (NOMI) 932
Nonulcer dyspepsia 878
Normal rotation of midgut, errors 992
Normal rotation of midgut, stages 991
Notch 873, 880
Nucleoside reverse transcriptase inhibitor (NRTI) 64
Nutrition 101
Nutritional support 102
Nyhus iliopubic repair 811

O

Obesity 106
Obesity, causes 106
Obesity, medical management 107
Obesity, morbid 106
Obesity, morbid, problems 106
Obstipation 998
Obstruction, proximal small bowel 983
Obturator 1022
Ochsner-Sherren regimen 1015
Ochsner-Sherren regimen, contraindication 1015
Ochsner-Sherren regimen, criteria 1015
Octreotide 656, 731
Odontomes 382
Odynophagia 840
Oesophageal carcinoma, endoscopic bipolar diathermy 865
Oesophageal carcinoma, endoscopic laser 865
Oesophageal carcinoma, endoscopic photodynamic therapy 865
Oesophageal carcinoma, endoscopic therapy 865
Oesophageal clearance mechanism 840
Oesophageal cyst 867
Oesophageal dilatation 855
Oesophageal diverticulum 857
Oesophageal diverticulum, pulsion type 858
Oesophageal diverticulum, traction type 858
Oesophageal endosonography 842, 859
Oesophageal manometry 844
Oesophageal motility disorders 849
Oesophageal perforation 867
Oesophageal substitutes 864
Oesophageal varices 654
Oesophageal varices, balloon tamponade 657
Oesophageal varices, definitive management 659
Oesophageal varices, emergency management 656
Oesophageal varices, endoscopic gluing 657
Oesophageal varices, endoscopic therapy 656
Oesophageal varices, endoscopic variceal banding 657
Oesophageal varices, endoscopic variceal sclerotherapy 657
Oesophageal varices, endoscopic variceal thrombin injection 657
Oesophageal varices, grading 654
Oesophageal varices, pharmacotherapy 656
Oesophageal varices, treatment 654
Oesophagectomy, complications 866
Oesophagectomy, McKeown three phased 863
Oesophagectomy, Orringer approach 863
Oesophagectomy, radical 860, 863
Oesophagectomy, vagal sparing 864
Oesophagogastrectomy 846
Oesophagoscope, fibreoptic flexible 842
Oesophagoscope, rigid 842
Oesophagoscopy 841, 842
Oesophagus, 'bird beak' appearance 842
Oesophagus, 'corkscrew' appearance 842
Oesophagus, abdominal 838
Oesophagus, anatomical narrowing 838
Oesophagus, anatomical specialities 838
Oesophagus, anatomy 838
Oesophagus, arterial supply 838
Oesophagus, Barrett's 849
Oesophagus, benign tumours 866
Oesophagus, candidiasis 840
Oesophagus, cervical 838
Oesophagus, contrast study 841
Oesophagus, corkscrew 850
Oesophagus, corrosive stricture 854
Oesophagus, corrosive stricture, degree of burns 854
Oesophagus, corrosive stricture, treatment 854
Oesophagus, diffuse spasm 840, 849
Oesophagus, foreign body 840, 867
Oesophagus, leiomyoma 866
Oesophagus, lymphatic drainage 839
Oesophagus, nutcracker 850
Oesophagus, sigmoid 842
Oesophagus, thoracic 838
Oesophagus, venous drainage 838
Oil of evening primrose 552
OK 432 465
Okuda classification 774
Okuda needle 672
Omental torsion 614
Omental tumour 614
Omentocele 800, 806
Omentoplasty 188, 195
Omentoplasty, complications 196
Omphalitis 784
Omphalocele 792
Oncocytoma 445, 1098
Onghren's line 303
Onychocryptosis 172
Onychogryphosis 172
Onychomycosis 172
Operation Koontz' 810
Operation, Anderson- Hyne's 1088
Operation, Andrew's 811
Operation, Belsey Mark IV 846
Operation, Bishop-Koop 759, 993
Operation, Blalock-Taussig 1220
Operation, BOCCA 480

Operation, Boerema 846
Operation, Boerema-Crile 658
Operation, Brunschwig's 1028
Operation, Cattell's 827
Operation, Charle's 263, 264
Operation, child's 743
Operation, Commando 481
Operation, Delorme's 1033, 1034
Operation, Fitzpatric 1142
Operation, Fowler's 172, 279
Operation, Gelhard's 1142
Operation, Goligher's 1033
Operation, Hadfield-Adair 558
Operation, Hamilton-Bailey 810
Operation, Hamilton-Stewart 1084
Operation, Hartley-Dunhill 493, 521
Operation, Hartmann's 989, 998, 1028
Operation, Hill's 846
Operation, Homan's 263
Operation, in Dumphy 1034
Operation, Ivor Lewis 863
Operation, Jabouley's 1153, 1261
Operation, Jurasz 736
Operation, Keel 827
Operation, Kirwin's 1078
Operation, Kondolean's 264
Operation, Ladd's 991
Operation, Lahaut's 1033
Operation, Lily's 677
Operation, Lockwood low 824
Operation, Lotheissen's 824
Operation, Macey's 264
Operation, Max-Page 169
Operation, May-Husni 234
Operation, Mayo's 830, 831
Operation, McEvedy-high 824
Operation, McVay 811
Operation, Michaelis plank 806
Operation, modified Duhamel 951
Operation, modified Heller's 852
Operation, Newman-Seabrock's 439
Operation, Nielubowitz 263
Operation, Nuttall's 828
Operation, O'Brien's 263
Operation, Ombredanne's 1163
Operation, Palma 234
Operation, Palomo's 1159
Operation, Partington-Rochelle 743, 744
Operation, Patey's 581
Operation, Paul Brand's 279
Operation, Paul-Mickulicz 998
Operation, Puestow's 743
Operation, Ramstedt's 877
Operation, Riordan 279
Operation, Ripstein 1033
Operation, Rose Graham 1033
Operation, Roscoe-Graham 889
Operation, Rovsing 1077
Operation, Santulli 993
Operation, Scanlon's 581
Operation, Sever's 275
Operation, Sir Piersey Gold 1145
Operation, Sistrunk 263, 488, 489
Operation, Smith 736
Operation, Stye-Bunnell's 279
Operation, Sugiura-Futagawa 658
Operation, Tanner slide 810
Operation, Tanner's 901
Operation, Taylor's 885
Operation, Thompson's 263
Operation, Torkildsen 1181, 1187
Operation, Trendelenburg 244
Operation, Wardill-Kilner push back 372
Operation, Well's 1033
Operation, Wheelhouse's 1132
Operation, Wyatt 1034
Operation, Young's 1145
Operation, Zadik's 172
Operative surgery 1244
Opisthotonus 51
OPSI 722
OPSI, prevention 722
OPSI, treatment 722
Opsite 136
Opsomyoclonus 541
Optease filter 254
Oral and upper aerodigestive cancers 394
Oral carcinoma, prognostic factors 414
Oral cavity, premalignant condition 394
Oral cavity, syphilitic lesions 392
Oral cholecystogram 670
Oral submucosal fibrosis 393
Orbital cellulitis 37
Orchidectomy 1163
Orchidopexy 1163
Orchitis 1170
Orchitis, bilateral interstitial 1170
Orchitis, syphilitic 1170
Orf 166
Organ of Geraldes 1155
Orphan Annie eye nucleus 511
Orthopantomogram 367, 401
Orthotonus 51
Orthoses 339
Osler Weber Rendu disease 937
Osteitis fibrosa cystica 532
Ovarian mass 781
Oximetry 1216
Oxygen 1232
Oxygen therapy 118
Oxyphil adenoma 445

■ P

PABA excretion in urine 763
Pacemaker cell of Cajal 872
Pachydermatocele 91
Pachyglossia 416
Pack year index 185
Packed cells 124
Paget's disease of nipple 567
Paget's disease penis 1142
Paget's, recurrent fibroid of 84
Pain 364
Pain pathway 364
Pain, clinical assessment 364
Pain, deep 365
Pain, grading 365
Pain, periodicity 365
Pain, psychogenic 365
Pain, radiation 365
Pain, referred 365
Pain, segmental 365
Pain, shifting/migration 365
Pain, superficial 365
PAIR (Puncture-Aspiration-Injection-Reaspiration) 638, 640
Palate, diseases 367
Palatoplasty, principles 372
Palcitaxel 586
Palmar aponeurosis 156
Panarteritis 185
Pancoast tumours 1208
Pancreas pseudocyst 732, 734
Pancreas pseudocyst, complication 737
Pancreas pseudocyst, D'Egidio classification 735
Pancreas, accessory 759
Pancreas, acute pseudocyst 732
Pancreas, anatomy 725
Pancreas, annular 759
Pancreas, blood supply 726
Pancreas, cystadenocarcinoma 749, 777
Pancreas, cystic lesions 763
Pancreas, ectopic 759
Pancreas, function 726
Pancreas, intraductal mucinous neoplasm (IPMN) 747
Pancreas, mucinous cystic neoplasm 746
Pancreas, nerve supply 726
Pancreas, periampullary carcinoma 748
Pancreas, pseudocyst 777
Pancreas, serous cystic neoplasm 747
Pancreatectomy, distal 627, 636, 743
Pancreatectomy, Fortner's regional 753
Pancreatectomy, total 743, 744, 754
Pancreatic abscess 761
Pancreatic ascites 760
Pancreatic calculus 760
Pancreatic carcinoma, adjuvant therapy 755
Pancreatic carcinoma, pain control 755
Pancreatic carcinoma, prognostic factors 755
Pancreatic carcinoma, TNM staging 752
Pancreatic cholera 758
Pancreatic divisum 759
Pancreatic duct decompression 743
Pancreatic enzyme replacement therapy (PERT) 742
Pancreatic fistula 733, 760
Pancreatic fistulae, complications 761
Pancreatic juice 726
Pancreatic necrosis 732, 761
Pancreatic polypeptide tumour 758
Pancreatic pseudoaneurysm 733
Pancreatic resection 743
Pancreatic sphincter dyskinesia 710
Pancreatic trauma 762
Pancreatic trauma, classification 762

Pancreatic trauma, grading 762
Pancreatic tumours 746
Pancreatic tumours, acinar cell carcinoma 746
Pancreatic tumours, cystadenocarcinoma 749
Pancreatic tumours, endocrine 755
Pancreatic tumours, exocrine 746
Pancreatic tumours, infiltrating ductal adenocarcinoma 746
Pancreatic, abscess 733
Pancreaticoduodenectomy 743
Pancreaticoduodenectomy, Traverso-Longmire pylorus preserving 753
Pancreaticojejunostomy 743
Pancreatitis 727
Pancreatitis, acute 727
Pancreatitis, acute interstitial 729
Pancreatitis, acute physiology and chronic health evaluation 734
Pancreatitis, acute, APACHI II scoring 734
Pancreatitis, acute, Atlanta classification 729
Pancreatitis, acute, Balthazar CT scoring system 730
Pancreatitis, acute, complications 732
Pancreatitis, acute, conservative treatment 731
Pancreatitis, acute, metabolic/biochemical changes 729
Pancreatitis, acute, plain X-ray 730
Pancreatitis, acute, spiral CT 730
Pancreatitis, acute, surgical treatment 730
Pancreatitis, autoimmune 729
Pancreatitis, chronic 738
Pancreatitis, chronic, classification 739
Pancreatitis, chronic, conservative treatment 742
Pancreatitis, chronic, CT abdomen 741
Pancreatitis, chronic, endocrine dysfunction 740
Pancreatitis, chronic, endoscopic therapy 742
Pancreatitis, chronic, endosonography 741
Pancreatitis, chronic, ERCP 740, 741
Pancreatitis, chronic, ERCP Cambrige grading 741
Pancreatitis, chronic, exocrine dysfunction 740
Pancreatitis, chronic, pathogenesis 738
Pancreatitis, chronic, surgery 742
Pancreatitis, chronic, TIGAR-O risk factor classification 738
Pancreatitis, early-onset idiopathic 739
Pancreatitis, emphysematous 734
Pancreatitis, fulminant 728
Pancreatitis, gallstone, Ranson's prognostic criteria 734
Pancreatitis, Glasgow-Imrie prognostic criteria 734
Pancreatitis, haemosuccus 733
Pancreatitis, hereditary 728
Pancreatitis, idiopathic 729
Pancreatitis, Marseille's classification 727
Pancreatitis, necrotising 729
Pancreatitis, non-gallstone, Ranson's prognostic criteria 734
Pancreatitis, Trapnell's classification 727
Pancreatitis, tropical 739
Pancreatitis, Ulm classification 729
Pancreatoblastoma 746
Pancreolauryl test 763
Panendoscopy 477
Papilloma 83
Papilloma, complications 84
Papilloma, duct 84
Papilloma, fibroepithelial 84
Papilloma, infective 83
Papilloma, true 83
Papillomatosis 563
Pappenheimer bodies 712
Para-aortic lymph node mass 777
Paradidymis 1155
Paradoxical aciduria 887
Paradoxical respiration 1196
Parafollicular 'C' cell 518
Paraganglioma 765
Parakeratosis 392
Paralysis, Erb-Duchenne 275
Paralysis, Klumpke's 275
Paralytic ileus 1000
Paraneoplastic syndromes 286
Paraoesophageal lymph nodes 839
Paraphimosis 1139
Paraplegia in extension 1192
Paraplegia in flexion 1192
Paratesticular tumours 1070
Parathormone 531
Parathyroid anatomy 531
Parathyroid, autotransplantation 526, 536
Parathyroidectomy 534, 536
Parathyroidectomy, complications 534
Parathyroidectomy, endoscopic 535
Parathyroidectomy, indications 534
Parathyroidectomy, minimal invasive 535
Parathyroidectomy, remedial 536
Parathyroidectomy, subtotal 536
Parathyroidectomy, video assisted 535
Parathyromatosis 532
Parenteral nutrition, home 105
Parenteral nutrition, peripheral 104
Parenteral nutrition, total 104
Parietal cell 870
Parkland regime 135
Paronychia, acute 160
Paronychia, chronic 161
Parotid gland, accessory 431
Parotid gland, anatomy 431
Parotid lymphoma 451
Parotid, lymphatic drainage 432
Parotidectomy 448
Parotidectomy, chemotherapy 449
Parotidectomy, complications 449
Parotidectomy, radical 449
Parotidectomy, radiotherapy 449
Parotidectomy, superficial 451
Parotidectomy, suprafacial 452
Parotidectomy, total conservative 449
Parotitis, acute 438
Parotitis, suppurative 438
Parotitis, suppurative, complications 438
Passaro's triangle 757
Patent ductus arteriosus 1217
Patey's stylomandibular tunnel 442
Patient controlled analgesia 366
Patterson operation 402
Pavulon 1232
PCWP 116
PDS 1256
Peau d'orange 569
Pel-Ebstein fever 266
Pelvic evisceration 1028
Penis, Ram's horn 1142
Peptic ulcer, acute 878
Peptic ulcer, bleeding 891
Peptic ulcer, perforated 887
Peptic ulcer, perforation, plain X-ray abdomen 888
Percarditis, chronic constrictive 1210
Percussion 771
Percutaneous nephrolithotomy (PCNL) 1091
Percutaneous transbiliary drainage (PTBD) 752
Percutaneous transhepatic biliary drainage 672
Percutaneous transhepatic cholangiography (PTC) 672
Percutaneous transluminal angioplasty 184
Percutaneous transluminal balloon angioplasty 190
Perdomo procedure 641
Perforator veins 231
Periappendicular phlegmon 1014
Pericardial tap 1210
Pericardiotomy, open 1210
Pericarditis 1209
Pericarditis, acute 1209
Pericystectomy 641
Pericystectomy, laparoscopic 641
Pericystojejunostomy 641
Perineal urethrostomy 1131
Perioesophageal lymph nodes 839
Periodicity 879, 883
Peripheral nerve injuries, causes 275
Peripheral nerve injuries, Seddon's classification 273
Peripheral nerve injuries, Sunderland's classification 274
Peripheral nerves 273
Peripheral nerves, classification 273
Peritoneal carcinomatosis 614
Peritoneal cavity 599
Peritoneal cavity, spaces 599
Peritoneal malignancy 613
Peritoneal malignancy, primary 613
Peritoneal tuberculosis 615
Peritoneum, anatomy 599

Peritoneum, parts 599
Peritoneum, physiology 599
Peritonitis, acute 600
Peritonitis, biliary 606
Peritonitis, diagnostic laparoscopy 603
Peritonitis, diffuse 602
Peritonitis, emergency laparotomy 604
Peritonitis, familial periodic 607
Peritonitis, laparotomy 603
Peritonitis, localised 602
Peritonitis, parturition/abortion 607
Peritonitis, postoperative 606
Peritonitis, primary 600
Peritonitis, sclerosing 606
Peritonitis, secondary 600
Peritonitis, spontaneous bacterial 605
Peritonitis, tertiary 600
Perleche 391
Perniosis 23
Per-rectal examination 1021
Pes anserinus 432
Peutz-Jegher's polyp 962
Peutz-Jegher's syndrome 937
Phagedena 27, 392
Phantom hernia 835
Phantom limb 338, 835
Phantom tumour 835
Pharyngeal pouch 462
Pharyngeal pouch, problem 462
Phenol 1245
Pheochromocytoma 542
Pheochromocytoma, malignant 543
Phimosis 1138
Phlebectomy, ambulatory 248
Phlebectomy, electrodesiccation 248
Phlebectomy, transilluminated 248
Phlebography 241
Phlegmasia alba dolens 232
Phlegmasia cerulea dolens 232
Phosphorylated diethylstilbestrol 1128
Phrygian cap 673
Phytobezoar 898
Picibanil 465
Picker position 1022
Piezo-ceramic shock waves 1092
Piles 1038
Pilomatrixoma 295
Pin index code 1233
PIPIDA scan 673
Pitting 712
Pituitary tumours, classification 1186, 1187
Plain- X-ray (KUB) 1066
Plantar fasciitis 172
Plasma 124
Platelet concentrate 125
Pleomorphic adenoma, recurrence after excision 444
Plethysmography 241
Plethysmography, air 242
Plethysmography, photo 241
Pleural tap 1198
Pleurothotonus 51
Plombage 1214
Pneumothorax, tension 1197
Pneumatosis cystoides intestinalis 931
Pneumaturia 952
Pneumobilia 987
Pneumococcal vaccine 722
Pneumothorax 1197
Pneumothorax, classification 1197
Podoconiosis 260
Policeman's heel 172
Polyarteritis nodosa 210
Polycystic liver disease 650
Polyethylene glycol (PEG) 980
Polymerase chain reaction (PCR) 290
Polyvalent antisnake venom 362
Porta hepatic injury 631
Portal biliopathy 668
Portal hypertension 651
Portal hypertension, management 653
Portal hypertension, segmental 659
Portal hypertension, sinistral 651
Portal hypertensive gastropathy 661
Portal pyaemia 46, 637, 1013
Portosystemic collateralisation 652
Port-wine stain 222
Positron-emission tomography 1243
Post-cricoid tumour 863
Posterior urethral valve 1133
Postoperative obstruction, acute 989
Postoperative patient, monitoring 1234
Postoperative synergestic gangrene 26
Postphlebitic limb 250
Post-thrombotic syndrome 237
Potato nose 297
Pott's puffy tumour 1182
Pott's puffy tumour 48
Pott's spine 1191
Pott's spine, complication 1192
Pouch of Douglas 981
Pouch, coonic 981
Pouch, Hartmann's 981
Pouch, Heidenhain 981
Pouch, ileal 980
Pouch, jejunal 980
Pouch, Morrison's hepatorenal 981
Pouch, Pavlov 981
Pouch, pharyngeal 981
Pouch, Physick's 981
Pouch, Rathke's 981
Pouch, Seessel's 981
Pouches, surgical 980
Pouchet's procedure 881
Poupart's ligament 800
PPV 23 722
Pregangrene 177
Pre-hospital trauma life support 143
Prepyloric vein of Mayo 870
Presbyoesophagus 839
Pressure sore 21
Pressure sore, factors causing 21
Pressure sore, staging 22
Pressure sores 214
Pretracheal fascia 484
Priapism 1141
Pringle manoeuvre 154, 629
Proctalgia fugax 1060
Proctitis 1060
Proctoscope 1022, 1255
Proctoscopy 1022
Profundaplasty 184, 188, 191
Prolene 1256
Propofol 1232
Propranolol 506
Propylthiouracil 506
Prostate specific antigen 1121
Prostate, anatomy 1121
Prostate, capsule 1121
Prostate, floating 1129, 1130
Prostate, McNeal's three zones 1121
Prostatectomy, Freyer's suprapubic transvesical 1124
Prostatectomy, Millin's retropubic 1124
Prostatectomy, radical 1127
Prostatectomy, Young's perineal 1124
Prostatic abscess 1125
Prostatic calculi 1122
Prostatism 1122
Prostatitis 1125
Prostatitis, acute 1125
Prostatitis, chronic 1125
Prosthesis, Canadian Syme's 339
Prosthesis, computer-assisted designing 339
Prosthesis, internal 339
Prosthesis, lower limb 339
Prosthesis, nonsuction type 339
Prosthesis, patellar tendon bearing (PTB) 339
Prosthesis, SACH 339
Prosthesis, suction type 339
Prosthesis, tilting table 339
Prosthesis, types 339
Prosthesis, upper limb 339
Protamine sulphate 252
Prothrombin complex concentrate 125
Prothrombin time 628
Proton pump inhibitors 884
Proud flesh 19
Pruritus ani 1060
Psammoma bodies 512, 1184
Pseudoachalasia 853
Pseudoappendicitis 1006
Pseudocyst, lung 1204
Pseudoeschar 137
Pseudogynaecomastia 561
Pseudohyponatraemia 96
Pseudolipoma 71
Pseudomesenteric cyst 625
Pseudomyxoma peritonei 614, 1016
Pseudopneumoperitoneum 891
Psoas abscess 769
Psoas shadow 1067
PTA 190
PTFE mesh 827
Pudendal nerve latency study 1032
Pulmonary capillary wedge pressure 116
Pulmonary circulation 1216
Pulmonary complications, postoperative period 1214

Pulmonary stenosis 1219
Pulseless disease 188
Pumping veins 230
Purified chick embryo cell culture vaccine 59
Purified vero cell rabies vaccine 59
Purpura, idiopathic thrombocytopenic (ITP) 718
Purpura, thrombotic thrombocytopenic (TTP) 720
Pyaemia 45
Pyelolithotomy 1092
Pyelolithotomy, anatrophic 1094
Pyelolithotomy, coagulum 1094
Pyelolithotomy, extended 1092
Pyeloplasty, dismembered 1088
Pyeloplasty, laparoscopic 1088
Pyeloplasty, non-dismembered 1088
Pylephlebitis 637
Pyloric stenosis, barium meal study 885
Pyloric stenosis, chronic duodenal ulcer 885
Pyloric stenosis, congenital hypertrophic 876
Pyloric stenosis, electrolyte changes 885, 887
Pyloric stenosis, treatment 886
Pyloroplasty 918
Pyloroplasty, Finney's 893
Pyloroplasty, Finney's 918
Pyloroplasty, Heineke-Mikulicz 918
Pyocele 1155
Pyogenic granuloma 19, 49
Pyonephrosis 1088
Pyrosis 843

Q

Quadrantectomy 582
QUART therapy 582, 588

R

Rabies 58
Rabies, avian vaccine 59
Rabies, BPL inactivated vaccine 59
Rabies, cell culture vaccine 59
Rabies, dogs 60
Rabies, fixed virus 58
Rabies, immunisation in animals 60
Rabies, nervous tissue vaccine 59
Rabies, passive immunity 60
Rabies, pathogenesis 58
Rabies, post-exposure prophylaxis 60
Rabies, pre-exposure prophylaxis 60
Rabies, street virus 58
Rabies, sylvatic 58
Rabies, urban 58
Rabies, vaccines 59
Rabies, wild life 58
Rabies, wound classification 59
Rabies, wound treatment 59
Radiation 1244
Radiation absorbed dose 1225
Radiation unit 1224
Radical excision 94
Radio-remnant ablation 514
Radioactive I^{123} scan 489
Radioactive I^{125} fibrinogen study 233
Radioactive iodine 508
Radionuclide imaging 1243
Radioresistant malignancies 1225
Radiosensitive malignancies 1225
Radiotherapy 1224
Radiotherapy, complications 1226
Radiotherapy, concomitant 1226
Radiotherapy, curative 1224
Radiotherapy, induction 1226
Radiotherapy, interstitial 1225
Radiotherapy, intracavitory 1225
Radiotherapy, palliative 1224
Radiotherapy, physicochemical effects 1224
Radiotherapy, postoperative 1226
Radiotherapy, preoperative 1226
Radiotherapy, sources 1225, 1226
Radiotherapy, types 1224, 1225
Rains factor 123
Ram's horn nail 172
Ram's horn penis 260
Randall's plaque theory 1090
Ranula 389
Ranula, marsupialisation 390
Ranula, plunging 389
Rashkind balloon septostomy 1219
Ray fungus 56
Raynaud's disease 189, 216
Raynaud's phenomenon 188, 216
Raynaud's phenomenon, treatment 219
Raynaud's syndrome 188, 216
Raynaud's syndrome, Coffman criteria 189
Reactive hyperaemia time 189
Reboring 191
Reconstruction 340
Rectal plication, Devadhar 1033
Rectal prolapse 1030
Rectal prolapse, aetiology 1030
Rectal prolapse, defecographic grading 1032
Rectal prolapse, hidden/concealed 1030
Rectal prolapse, partial 1030
Rectal prolapse, treatment 1030
Rectal proplapse, complete 1031
Rectopexy 1033
Rectosigmoid junction 1020
Rectum, anatomy 1020
Rectum, perineal posterior fixation of Lockhardt-Mummery 1034
Rectum, supports 1020
Recurrent childhood parotitis 438
Recurrent fibroid of Paget's 84
Recurrent laryngeal nerve palsy 523, 525, 527, 1263
Recurrent laryngeal nerve palsy, bilateral 529
Recurrent laryngeal nerve palsy, unilateral 529
Recycled blood 127
Red currant jelly 780
Red currant jelly stool 995
Reed-Sternberg cells 265
Refeeding syndrome 102, 106
Reflux oesophagitis, Los Angeles classification 848
Reflux oesophagitis, Savary-Miller classification 848
Renal abscess 1089
Renal angiogram 1102
Renal calculus 1089
Renal calculus, aetiology 1090
Renal calculus, indigo 1091
Renal calculus, struvite 1091
Renal calculus, urate 1090, 1107
Renal calculus, uric acid 1090, 1107
Renal calculus, xanthine 1091
Renal carbuncle 1088
Renal cavernostomy, Hanley's 1083
Renal cell carcinoma 1100
Renal cell carcinoma, AJCC staging 1101
Renal cell carcinoma, chemotherapy 1103
Renal cell carcinoma, CT scan 1102
Renal cell carcinoma, MRI 1102
Renal cell carcinoma, Robson-Flocks and Kadeskey staging 1101
Renal cell carcinoma, triad 1102
Renal cell carcinoma, types 1100
Renal injury, grading 1080
Renal pain 1091
Renal papillary adenoma 1098
Renal pelvic tumour 1104
Renal pelvis, duplication 1078
Renal pharmacoangiogram 1069
Renal stones, conservative management 1092
Renal stones, cystine 1090, 1107
Renal stones, oxalate 1090, 1107
Renal stones, phosphate 1090, 1107
Renal stones, recurrence 1097
Renal stones, struvite 1091
Reperfusion injury 199
Residual urine 1116
Resistive index 496
Rest pain 176
Resting salivary flow 433
Restrictive bariatric surgery 107
Retention of urine, acute 1136
Retention of urine, acute on chronic 1137
Retention of urine, chronic 1136
Retractor, Balfour's 1250
Retractor, Czerny's (hernia) 1249
Retractor, Deaver's 1249
Retractor, Doyen's 1250
Retractor, Joll's thyroid 1251
Retractor, Langenbeck's 1249
Retractor, Morris' 1249
Retractor, self-retaining 1250
Retractor, single hook 1250
Retractor, Volkmann's 1249
Retractors 1249

Retrograde pyelography 1068
Retrograde Seldinger technique 1069
Retromammary space 545
Retromolar trigone 396
Retroperitoneal cyst 765
Retroperitoneal fibrosis 764
Retroperitoneal fibrosis, triad 764
Retroperitoneal mass 765
Retroperitoneal radical lymph node dissection (RPLND) 1169
Retroperitoneal radical lymph node dissection, modified (RPLND) 1169
Retroperitoneal sarcoma 769
Retroperitoneal sarcoma, Dutch/memorial Sloan-Kettering cancer centre classification 769
Retroperitoneal sarcoma, features 768
Retroperitoneal space, anatomy 764
Retroperitoneal swellings 765
Retroperitoneal tumours 765, 766
Retroperitoneal tumours, AJCC grading 767
Retroperitoneal tumours, TNM staging 767
Retroperitoneal tumours, treatment 768
Retroperitoneoscopy 1270
Retropharyngeal abscess 466
Retropharyngeal abscess, acute 466
Retropharyngeal abscess, chronic 467
Reversal agents 1232
Reynold's pentad 691
Rhabdomyosarcoma 327
Rhinophyma 297
Richet's fascia 829
Riddle's triangle 523
Right to left shunt 1217
Ringer's lactate 101
RIPASA scoring system 1011
Risus sardonicus 50
Rituximab 356
River struma 519
Robertson's cooked meat media 53
Rockall scoring system 892
Roentgen unit 1225
Rokitansky-Aschhoff's sinuses 688
Rose Bengal I^{131} study 678
Rotter's nodes 547, 570
Roundworm obstruction 931
Roux- en-Y procedure 754
Roux-en-Y gastric bypass 108
Roux-en-Y gastric bypass, laparoscopic 109
Rupture bladder 1115
Rupture bladder, complications 1116
Rupture, anterior urethra 1130
Rupture, bulbous urethra 1130
Rupture, bulbous urethra, treatment 1130
Rupture, membranous urethra 1129
Rupture, membranous urethra, MaCallum-Colapinto classification 1129
Rupture, posterior urethra 1129
Rutherford Morison's kidney pouch 609

S

SA node 1216
SAAG 662
Sabre tibia 28
Sacrococcygeal teratoma 1058
Saddle embolus 200
Saegesser's tender point 713
SAG-M blood 125
Saint's triad 680, 694, 847, 951
Salazopyrine 927, 958
Saliva 434
Salivary tumour, acinic cell 446
Salivary tumour, adenocarcinoma 446
Salivary tumour, adenoidcystic carcinoma 446
Salivary tumour, adenolymphoma 444
Salivary tumour, AJCC, TNM staging 447
Salivary tumour, carcinoma expleomorphic adenoma 446
Salivary tumour, carcinosarcoma 446
Salivary tumour, facial nerve sacrifice 449
Salivary tumour, FNAC 448
Salivary tumour, malignant mixed 446
Salivary tumour, malignant, general features 447
Salivary tumour, management 447
Salivary tumour, mucoepidermoid 445
Salivary tumour, open biopsy 443
Salivary tumour, parotid, surgery 448
Salivary tumour, radiotherapy 449
Salivary tumour, squamous cell carcinoma 447
Salivary tumour, submandibular 447
Salivary calculus 435
Salivary colic 435
Salivary gland excision, submandibular 437
Salivary gland tumour, minor 450
Salivary gland, ectopic 434
Salivary gland, minor 434
Salivary gland, sublingual 434
Salivary neoplasm 440
Salivary neoplasm, WHO classification 440
Salivary nucleus, inferior 454
Salivary nucleus, superior 454
Salivary tumour, mixed 441
Salivary tumour, papillary cystadenolymphomatosum 444
Salivary tumour, pleomorphic adenoma 441
Salmon patch 222
Sandblom triad 704
Santulli operation 993
Saphena varix 238, 822
Saphenous neuralgia 244
Saphenous vein graft, *in situ* 192
Saphenous vein graft, reverse 192
Saphenous vein, long 230
Saphenous vein, short 230
Sarcoidosis 272
Sarcoma 282
Sarcoma, Enneking classification of surgical resection 323
Sarcoma, FNAC 320
Sarcoma, incision biopsy 320, 321
Sarcoma, isolated limb perfusion 325
Sarcoma, trucut biopsy 320
Sarcomas 318
Sarcomas, chemotherapy 325
Sarcomas, features 318
Sarcomas, lymph node spread 329
Sarcomas, radiotherapy 324, 325
Saturday night palsy 280
Savage's decompressor 989
Savlon 1245
Scabbard trachea 526
Scalene manoeuvre 179
Scalene triangle 174, 456
Scalvo's serum 61
Schatzki's rings 856
Schiller-Duval bodies 1166
Schistosoma haematobium 1111
Schwannoma 92, 1184
Scissors 1252
Scleroderma/systemic sclerosis 211
Sclerosing adenosis 552
Sclerosing angioma 296
Sclerotherapy, advantages 244
Sclerotherapy, catheter directed 243
Sclerotherapy, disadvantages 244
Sclerotherapy, foam 243
Sclerotherapy, micro 243
Sclerotherapy, transillumination 243
Scolicidal agents 641
Scoline 1232
Scoliosis capitis 470
Scoop, Volkmann's 1252
Scrofuloderma 473
Scrotum, anatomy 1148
Scrum pox 49
Sebaceous horn 81
Seborrhoeic keratosis 298
Seborrhoeic wart 298
Second heart sound 1215
Segmental pressure measurement 179
Segmentectomy 666
Self-expanding metal stents (SEMS) 865
Semilunar line of Spigel 833
Seminoma testis 1166
Semon's law 529
Semple vaccine 59
Sengstaken-Blakemore tube 657
Senile keratosis 298
Sentinal lymph node biopsy 566, 1144
Sentinel node biopsy 317
Sentinel node, Cabana 1144
Sentinel pile 1047
SEPS 247
Septal defect, atrial 1218
Septal defect, ventricular 1219
Septicaemia 45
Septicaemia, complications 45
Septicaemia, stages 45

Septicaemia, types 45
Sequestrum 34, 177
Serocystic disease of Brodie 552
Serum amylase 726
Serum ascites albumin gradiant 662
Serum lactescence 730
Serum lipase 730
Seton technique 1056
Sharma and Jhawer's technique 1153, 1261
Shepherd crook deformity 387
Sherren's triangle 1008
Shianoya's criteria 185
Shock 111
Shock index 115
Shock lung 1203
Shock, anaphylactic 111, 115
Shock, cardiac compression 114
Shock, cardiogenic 113
Shock, cardiogenic, management 113
Shock, causes 111
Shock, clinical features 115
Shock, distributive 117
Shock, effects 112
Shock, hypovolaemic 111
Shock, neurogenic 111, 113
Shock, pathophysiology 112
Shock, septic 114
Shock, septic, pathophysiology 114
Shock, septic, stages 114
Shock, septic, treatment 114
Shock, stages 112
Shock, treatment 115
Shock, types 112, 113
Shock, vasovagal 113
Shouldice repair 810
Shouldice repair, Berliner modified 810
Shunt, Denver 664
Shunt, distal splenorenal 659
Shunt, Inokuchi 659
Shunt, LeVeen 664
Shunt, Linton's 659
Shunt, porta-caval 659
Shunt, proximal splenorenal 659
Shunt, Warren's 659
Shunts, nonselective 659
Shunts, selective 659
Shutter mechanism 801
Sialadenectomy 437
Sialadenitis 435
Sialadenitis, acute 435
Sialadenitis, chronic 435
Sialectasis 437
Sialography 434
Sialolithiasis 436
Sialorrhoea 433
Sialosis 437
Sick cell syndrome 113, 122
Sickle cell disease 718
Sideropenia 394
Sideropenic dysphagia 394
Sigmoidopexy 998
Sigmoidoscopy 1022
Sign 'V' 162
Sign of 'V' of Naclerio 856
Sign of Dance 995
Sign of vas 1168
Sign, 'C' loop-pad 750
Sign, Angell's 1165
Sign, Ballance's 713
Sign, Battle's 1174
Sign, bent-inner tube 998
Sign, Berry's 512, 513, 516, 517, 520
Sign, bird's beak 998
Sign, Blumberg's 602, 888, 987, 1008
Sign, Boas's 685
Sign, Bow 1158
Sign, Branham's 228
Sign, bull's eye 996
Sign, Camellotte 638
Sign, Champagne bottle 238, 249
Sign, Champagne glass 953
Sign, Chvostek's sign 538
Sign, claw 996
Sign, coffee-bean 998
Sign, coiled spring 996
Sign, Coleman's 378
Sign, colon cut off 730
Sign, Cowen's 503
Sign, Cullen's 728
Sign, Cupola 890
Sign, Curtain 442
Sign, Dalrymple's 502
Sign, Deming's 1165
Sign, double duct 752
Sign, double-bubble 990
Sign, Doughnut 877, 996
Sign, Enroth 503
Sign, fat ring 612
Sign, Fleischner 618
Sign, football 890
Sign, Fox 728
Sign, Froment's 278, 458
Sign, Frostberg's reverse '3' 874
Sign, Gaur's 822
Sign, Giffrod's 503
Sign, Grey Turner's 728
Sign, Guerin's 375
Sign, Hamman 857
Sign, Harvey's 178
Sign, Homan's 233
Sign, Hood 488
Sign, Hook 164, 778
Sign, Hoover's 610
Sign, Howship-Romberg 834
Sign, Hutchinson 312
Sign, inverted beer bottle 249
Sign, inverted umbrella 618
Sign, inverted V 890
Sign, Jellinek's 503
Sign, Joffroy's 502
Sign, Kanavel 164
Sign, Kehr's 713
Sign, Knie's 503
Sign, Kocher's 503
Sign, Loewi's 503
Sign, London's 153
Sign, Lyre 468
Sign, Mallet-Guys 740
Sign, Mathe's 1089
Sign, Mercedes Benz 680, 694
Sign, Milian's ear 39
Sign, Moebius 502
Sign, Mose's 233
Sign, Moynihan's 689
Sign, Murphy's 689
Sign, Nafziger's 503
Sign, Neuhauser's 993
Sign, Neuhof's 233
Sign, Nicoladoni's 228
Sign, Omega 998
Sign, pad 874
Sign, Panda 373, 376, 1174
Sign, Pemberton's 266, 497
Sign, Prehns 1165
Sign, pseudokidney 996
Sign, puddle 662
Sign, Racoon's eye 541
Sign, reverse '3' 750
Sign, reverse 'J' 1068
Sign, Riglers 890
Sign, Rosenbach's 503
Sign, Rovsing's 1008
Sign, Rust's 474, 1191
Sign, Seagull 680, 694
Sign, Silk glove 805
Sign, slip 72
Sign, Srinivasan costal 782
Sign, Stellwag's 502
Sign, Stemmer's 260
Sign, Stierlien's 618
Sign, string 618
Sign, sun-setting 1181
Sign, Tanyol 662
Sign, target 996
Sign, thumb printing 959
Sign, Tinel's 275
Sign, trial 495
Sign, triangle 890
Sign, Troisier's 907, 909
Sign, Trousseau's 99, 252, 538, 749, 909
Sign, Vermooten's 1129
Sign, Von Graefe's 502
Sign, Westmark 1204
Sign, Whirl 1002
Silastic silo 793
Silk 1256
Simmond's procedure 173
Single photon emission computerised tomography (SPECT) 533
Sinus 30
Sinus forceps 43
Sinus, discharge 33
Sinus, median mental 33
Sinus, pilonidal 1036
Sinus, pilonidal, Buie's marsupialisation 1038
Sinus, pilonidal, Lord and Millar's excision 1038
Sinus, pilonidal, treatment 1037
Sinus, preauricular 35, 380

Sinusogram 33
Sir Philip Manson-Bahr amoebic point 960
Sirolimus 356
SIRS 112, 117, 132
Sister Joseph's nodules 784, 791
Sister Mary Joseph nodules 907, 909
Sister-Joseph nodule 294
Sitz bath 1042
Siver suphadiazine 136
Skin adnexal tumours 284
Skin cancer, TNM staging 300
Skin tag 84
Skin tumours, classification 293, 294
Skin, anatomy 293
Skin, eccrine gland tumours 294
Skin, hair tumour 294
Skin, melanotic cancer 294
Skin, non-melanotic cancer 294
Skin, premalignant conditions 298
Skin, squamous cell carcinoma 298
Skin, squamous cell carcinoma, prognostic factors 301
Skin, squamous cell carcinoma, treatment 301
Skinner en bloc resection 864
Slit valve mechanism 801
Sloan Kettering scoring 510
Slough 177
Small bowel carcinoid 939
Small bowel enema 942
Small bowel enteroscopy 943
Small bowel strictures 931, 934
Small bowel swellings 780
Small bowel tumours 935
Small bowel, adenocarcinoma 937
Small bowel, adenoma 936
Small bowel, benign tumours 936
Small bowel, carcinoid tumour 938, 939
Small bowel, GIST 938
Small bowel, leiomyoma 936
Small bowel, lipoma 937
Small bowel, malignant tumours 937, 938
Small bowel, malignant tumours, treatment 940
Small bowel, non-Hodgkin's lymphoma 938
Small intestine, anatomy 922
Small intestine, diseases investigation 923
Smoking index 185
Snail track ulcer 392
Socia parotidis 431
Sodium diatrizoate 1067, 1240
Sodium tetradecyl sulphate 3% (STDS) 242
Sodium trizoate 434
Soft chancre 28
Soft corn 171
Soft sore 28
Soft tissue sarcoma 318
Soft tissue sarcoma, features 320
Soft tissue sarcomas, amputation in 322, 324
Soft tissue sarcomas, compartment resection 324
Soft tissue sarcomas, grading 322
Soft tissue sarcomas, GTNM staging 322
Solar keratosis 298
Solitary ulcer syndrome 1029
Somatic cell therapy 1230
Somatostatin 656, 873
Somatostatin receptors 872
Somatostatinoma 758
Somatostatinoma, triad 758
Southampton wound grading system 36
Souttar tube 865
Space of Bogros 815
Space of Retzius 815
Space, midpalmar 162
Space, of parona, infection 164
Space, thenar 162, 163
Spermatic cord, contents 800
Spermatic cord, coverings 801
Spermatocele 1156
Sphincter of Oddi 670
Sphincter of Oddi dysfunction 710
Sphincterotomy 692, 693
Sphincterotomy, complications 692
Spider veins 235
Spigelian fascia 833
Spina bifida 1188
Spina bifida aperta 1189
Spina bifida occulta 1188
Spina ventosa 170
Spinal dysraphism 1187
SPINKI 739
Splash in the pan 1041
Spleen, accessory 712
Spleen, blood supply 711
Spleen, function 711
Spleen, ligaments 711
Spleen, red pulp 711
Spleen, rupture 712
Spleen, salutary effect 715
Spleen, surgical anatomy 711
Spleen, wandering 724
Spleen, white pulp 711
Splenectomy 659, 720
Splenectomy, complication 154, 715, 721
Splenectomy, emergency 715
Splenectomy, indications in ITP 719
Splenectomy, laparoscopic 721
Splenectomy, partial 715
Splenectomy, portal hypertension 659
Splenic artery 711
Splenic organ injury scale 714
Splenic rupture, signs 713
Splenic vein 711
Splenic vein cavernoma 659
Splenomegaly 716
Splenoportography 653
Splenorrhaphy 715
Splenosis 713
Spongioblastoma polare 1184
Spread of malignant tumours 284
Spurious diarrhoea 1024
Squamous cell carcinoma, Broder's classification 300
Squamous cell carcinoma, Broder's grading 285
SQUID 988
SSI risk index 68
Stafne bone cyst 434
Staghorn calculus 1097, 1107
Stapler haemorrhoidectomy 1045
Staplers in surgery 1265
Staplers, circular (EEA) 1265
Staplers, cutaneous 1265
Staplers, endo 1266
Staplers, GIA 1266
Staplers, linear 1265
Stenting, intravascular 216
Step ladder paristalsis 986, 995
Stephen's line 1035
Stephen-Fowler's technique 1163
Stercoral ulcer 969
Sterile pyuria 1083
Sterilisaion, methods 1245
Sterilisation 1244
Stiff lung 1203
Stings and bites 362
Stoma appliances 978
Stoma care 977
Stoma, complications 978
Stoma, general care and advice 979
Stoma, patient counselling 977
Stoma, postoperative care 978
Stoma, skin, excoriation 978
Stoma, types 977
Stomach, anatomy 869
Stomach, blood supply 870
Stomach, leather-bottle 908
Stomach, lymphatic drainage 871
Stomach, lymphatic drainage zones 907
Stomach, nerve supply 870
Stomach, palpable mass 776
Stomach, tiger stripe 894
Stomach, water melon 894
Stomal obstruction 895
Stomal ulcer, perforated 890
Stomatitis 390
Stomatitis, aphthous 391
Stomatitis, *Candida* 391
Stomatitis, nutritional 391
Stomatitis, traumatic 391
Stomatitis, Vincent's ulcerative 391
Stool occult blood test 1064
Stoppa's giant prosthesis reinforcement of visceral sac 814
Stork bite 222
Stove in chest 1196
Strawberry scrotum 82
Streptokinase 199
Stretta catheter 844
Stricture urethra 1131
Stricture urethra, classification 1131
Stricture urethra, complications 1132
Stricture urethra, intermittent dilatation 1132

Stridor 497
String sign of Kantor 927
Stripper, Codman's 244
Stripper, Myer's 244
Stripper, Oesch pin 246
Stripping, complications 244
Struma lymphomatosa 519
Struma ovarii 500
Student's elbow 85
Stump carcinoma 903
Stump neuroma 338
Subepithelial benign nodular fibrosis 296
Subhyoid bursitis 467
Submandibular salivary gland, anatomy 432
Subphrenic abscess, pathology 609
Subphrenic abscess, treatment 610
Subphrenic spaces 608
Succussion splash 885
Sucquet-Hoyer canal 82
Sucralfate 884
Sulfamylon 136
Superior mesenteric vein thrombosis 932
Superobesity 106
Supralevator encirclement of anal orifice of Notaras 1034
Suprapubic cystostomy 1074
Suprapubic open cystolithotomy 1109
Suprapubic percutaneous litholapaxy 1109
Surgeon and law 1276
Surgery, endovascular 215
Surgical complications, pulmonary tuberculosis 1214
Surgical complications, roundworm 929
Surgical complications, typhoid 928
Surgical infection 36
Surgical site infection (SSI) 67
Surgical site infection, classification 68, 69
Surgical site infection, management 70
Surgical site infection, prevention 69
Suture aterial, ideal 1256
Suture knots 1257
Suture materials, absorbable 1256
Suture materials, classification 1256
Suture materials, memory 1256
Suture materials, nonabsorbable 1256
Suture materials, numbering 1257
Suturing types 1257
Suturing, delayed primary 7, 8
Suturing, primary 7, 8
Suturing, secondary 7, 8
Suxamethonium chloride 1232
Swelling, cross-fluctuant 94
Swellings, brilliantly transilluminant 1150
Swellings, cross fluctuant 770
Swellings, cross-fluctuation 1151
Swenson's operation 951
Swimmer's itch 1111
Sylvatic rabies 58
Sympathectomy, cervical 190, 194
Sympathectomy, cervicothoracic preganglionic 193
Sympathectomy, chemical 188, 195
Sympathectomy, lumbar 188, 194
Sympathectomy, thoracoscopic 194
Syndactyly 169
Syndrome Cronkite-Canada 964
Syndrome, abdominal compartment (ACS) 155
Syndrome, adrenogenital 540
Syndrome, auroculotemporal 452
Syndrome, Bannayan-Riley-Ruvalacaba (Ruvalacaba Myhre Smith) 964
Syndrome, Beckwith-Weidman 792, 829
Syndrome, Birt-Hogg-Dube 1100
Syndrome, blue toe 207
Syndrome, Boerhaave's 841, 856
Syndrome, Bouveret's 704
Syndrome, Brown-Sequard 146
Syndrome, Budd-Chiari 664
Syndrome, carpal tunnel 276
Syndrome, cast 899
Syndrome, central cord 146
Syndrome, cervical rib 457
Syndrome, Chilaiditi's 889
Syndrome, coeliac artery 899
Syndrome, coeliac band 899
Syndrome, cold agglutinin 718
Syndrome, compartment 196, 197, 199
Syndrome, Conn's 540
Syndrome, Costello 765
Syndrome, Cowden (multiple hamartoma-neoplasia syndrome) 964
Syndrome, Cowden's 509, 563
Syndrome, CREST 189
Syndrome, Cruvielhier-Baumgarten 654
Syndrome, Curtis-Fitz-Hugh 607
Syndrome, dancing eye 541
Syndrome, descending perineal 1059
Syndrome, diGeorge's 538
Syndrome, disappearing pulse 178
Syndrome, dumping 897
Syndrome, Durban's 899
Syndrome, Eisenmenger's 1217, 1219
Syndrome, familial paraganglioma 542
Syndrome, Felty's 720
Syndrome, Ferguson-Smith 300
Syndrome, Frey's 452
Syndrome, Frey's, treatment 453
Syndrome, Frolich's 1187
Syndrome, Frolin's 1193
Syndrome, Gardner's 792, 963
Syndrome, Gorlin 303
Syndrome, Heerfordt's 454
Syndrome, Horner's 193, 476, 477, 1208
Syndrome, Hungry bone 526, 535
Syndrome, juvenile polyposis 965
Syndrome, Kasabach-Merritt 223, 642
Syndrome, Klinefelter's 1166
Syndrome, Klippel-Trenauny 252
Syndrome, Klippel-Trenauny-Weber 223
Syndrome, Koenig's 615
Syndrome, Leriche's 175, 178, 200
Syndrome, Letessier-Meige's 257
Syndrome, Li-Fraumen's 563, 902
Syndrome, Loeffler's 930
Syndrome, Lynch I 965
Syndrome, Lynch II 965
Syndrome, Maffucci 223
Syndrome, Mallory-Weiss 856
Syndrome, McCune Albright's 387
Syndrome, MEA 536
Syndrome, median arcuate ligament 899
Syndrome, MEN 71, 536
Syndrome, MEN II 518
Syndrome, MEN IIb 964
Syndrome, Mendelson's 900, 1234
Syndrome, Mirizzi 683
Syndrome, Munchausen 1013
Syndrome, nurses' 612, 626
Syndrome, Ogilvies's 998
Syndrome, Osler-Rendu-Weber 223, 894
Syndrome, Paget-Schroetter 232, 457
Syndrome, pancoast 1208
Syndrome, Parkes-Weber 223
Syndrome, Paterson-Kelly 853
Syndrome, pectoralis minor 458
Syndrome, Pendred's 489
Syndrome, Pierre-Robin 368, 388
Syndrome, Plummer-Vinson 853
Syndrome, Polands 546
Syndrome, post-cholecystectomy 709
Syndrome, post-cibal 897
Syndrome, primary extraglandular sicca 440
Syndrome, *Proteus* 223
Syndrome, Prune Belly 798, 1161
Syndrome, Rapunzel 898
Syndrome, Reiter's 1135
Syndrome, Roux stasis 897
Syndrome, scalene 457
Syndrome, Sezzary 270
Syndrome, short bowel 941
Syndrome, short gut 941
Syndrome, Shprintzen's 368
Syndrome, Sjögren's 439
Syndrome, Sjögren's, primary 440
Syndrome, Sjögren's, secondary 440
Syndrome, Stauffer's 1102
Syndrome, Stewart-Treves 262, 320, 328, 583
Syndrome, Stickler's 368
Syndrome, Sturge-Weber 223
Syndrome, subclavian steals 196
Syndrome, sump 694
Syndrome, superior mesenteric artery 899
Syndrome, thoracic inlet 457
Syndrome, thoracic outlet 174, 456
Syndrome, thoracic outlet, causes 174
Syndrome, Tietze's 554
Syndrome, Torre-Muir 294
Syndrome, Treacher-Collins 381
Syndrome, Turcot's 963, 964
Syndrome, Turner's 937
Syndrome, Verner-Morrison 758
Syndrome, virilising 540
Syndrome, von Hippel Lindau 542, 747, 763, 765

Syndrome, Waltman-Walters 607
Syndrome, weak-tea 758
Syndrome, Werner' s 536
Syndrome, Wilkie's 874, 898
Syndrome, Zollinger-Ellison 758
Synovial sarcoma 328
Syphilis 56
Syphilis, congenital, 56
Syphilis, late 56
Syphilis, latent 28, 56
Syphilis, primary 28, 56
Syphilis, secondary 28, 56
Syphilis, tertiary 28, 56
Syphilis, types 56
Syphilitic chronic glossitis 392
Syrigomylocele 1188
Systemic circulation 1216
Szilagyi classification 221

T

T3 489
T3 toxicosis 500, 505, 508
T4 489
Tabes mesenterica 625
Tacrolimus 356, 927, 1229
Taeniae coli 948
Takayasu's arteritis 188
Tamoxifen 552, 584
Tamsulosin 1124
Tangential excision 135
Tanner's resection 658
TAO 184
TAO, classification 185
TAO, pathogenesis 185
Tapeworm, dog 637
Taste sensation 454
Taxis 811, 819
^{99m}Tc scan 495
^{99m}Tc sestamibi scan 515
Tea-pot deformity 879, 882
Technetium 99 pertechnetate 508
Technetium 99m 1243
Technetium 99m labeled sestamibi
  scan 533
Tegaserod 958
Telepaque 670
Teletherapy 1226
Temporal arteritis 190
Tendon 351
Tendon graft 352
Tendon healing 351
Tendon healing, stages 351
Tendon repair 351
Tendon suturing 351
Tendon suturing, Goldner method 351
Tendon suturing, Kessler method 351
Tendon transfer 352
Tenesmus 1024
Teratoma testis 1166
Tessari technique 243
Test, Adson's 179, 458
Test, Allen's 179, 458
Test, augmented histamine 872
Test, auscultopercussion 885
Test, Baid 735, 777
Test, Baldwing's 1008
Test, Bernstein 844
Test, Blaxland ruler 662, 781
Test, Brodie-Trendelenburg 238
Test, Buerger's postural 179
Test, C13/C14 breath 876
Test, card 278
Test, Carnett's 781
Test, Casoni's 638
Test, Cope's psoas 1008
Test, EAST-Elevated Arm Stress 458
Test, Ehrlich's 696
Test, Falconer 179
Test, Fegan's 239
Test, Fouchet's 696
Test, Fuchsig's 178
Test, Goldstein saline load 885
Test, Graham cole 670
Test, Halstead 216, 458
Test, Hay's 696
Test, head rising 805
Test, Hess 719
Test, Hollander 872
Test, Ian-Arid 239
Test, insulin (Hollander) 872
Test, internal ring occlusion 804
Test, Javid 196
Test, Kocker's 492, 526
Test, leg rising 804
Test, Linton's 233
Test, Lundh 763
Test, Mantoux skin 54
Test, military attitude 458
Test, modified Adson's 458
Test, modified Perthes' 239
Test, modified Roos 179
Test, Morrissey's cough impulse 239
Test, obturator 1008
Test, Orr chair 1164
Test, pancreolauryl 740, 742
Test, peak acid output 872
Test, pen 276
Test, pentagastrin 872
Test, Perthes' 239
Test, Phalen's 277
Test, Pratt's 239
Test, rapid urease 876
Test, ring invagination 804
Test, Roos 458
Test, Schwartz 239
Test, secretin cholecystokinin 741
Test, secretin cholecystokinin
  stimulation 763
Test, secretin stimulation 757
Test, Simian thumb 276
Test, sniff 1211
Test, Starch iodine 453
Test, tensilan diagnostic 1207
Test, three fingers 638, 773
Test, three tourniquet 239
Test, traction 1151
Test, Triolin breath 763
Test, Whitaker 1087
Test, Zieman's 804
Testicular descent, embryology 1161
Testicular sensation, loss 1154
Testicular tumours 1165
Testicular tumours, chemotherapy 1169,
  1170
Testicular tumours, classification 1166
Testicular tumours, germ cell 1166
Testicular tumours, histological
  classification 1166
Testicular tumours, hurricane type 1168
Testicular tumours, interstitial cell 1167
Testicular tumours, Leydig cell 1167
Testicular tumours, nongermcell 1166
Testicular tumours, Sertoli cell 1167
Testicular tumours, sex cord
  stromal 1166
Testicular tumours, staging 1168
Testicular tumours, TNM staging 1168
Testicular tumours, treatment 1169
Testicular tumours, tumour markers 1168
Testis, 'clapper in bell'1164
Testis, anatomy 1160
Testis, appendage, torsion 1165
Testis, billiard 1170
Testis, ectopic 1163
Testis, ectopic, Lockwood theory 1163
Testis, gumma 1170
Testis, hanging/clapper in bell 810
Testis, maldescended 1161
Testis, retractile 1164
Testis, torsion 1164
Testis, torsion, treatment 1165
Testis, undescended 1161
Testis, undescended, complications 1162
Testis, undescended, hormone
  therapy 1163
Testis, undescended, laparoscopic
  approach 1163
Testis, vanishing 1161, 1162
Tetanus 49
Tetanus, ascending 50
Tetanus, bulbar 51
Tetanus, cephalic 50
Tetanus, complications 51
Tetanus, descending 50
Tetanus, early 50
Tetanus, incubation period 50
Tetanus, late 50
Tetanus, latent 50
Tetanus, localised 50
Tetanus, neonatorum 51
Tetanus, organism 50
Tetanus, pathogenesis 50
Tetanus, postoperative 51
Tetanus, postures in 51
Tetanus, predisposing factors 49
Tetanus, prophylaxis 52
Tetanus, staging 51
Tetanus, toxoid 52
Tetanus, treatment 51
Tetanus, types 50
Tetanus, urban 51

Tetany 99, 537
Tetracycline fluorescence test 911
Tetralogy of Fallot 1219
Thal's patch procedure 846
Thalassaemia 718
Thebesian veins 1215
Theirsch wiring 1030, 1034
Thiopentone 1232
Thoracic outlet, surgical anatomy 174
Thread veins 235
Throid, incidentaloma 520
Thrombectomy 191
Thrombectomy, venous 234
Thrombin inhibitors 253
Thromboangiitis obliterans, TAO 184
Thrombolysis 199
Thrombolytic agents 253
Thrombophlebitis 251
Thrombophlebitis migrans 252
Thrombosis, axillary vein 232
Thrombosis, deep vein 231
Thrombosis, spontaneous 232
Thrombosis, traveller's 231
Thrombus, fixed 233
Thrombus, free 234
Thymectomy 1207
Thymomas 1207
Thymomas, histological types 1207
Thymomas, staging 1207
Thyrocardiac 508
Thyroglobin estimation 514
Thyroglossal cyst, tugging sensation 488
Thyroglossal duct 484
Thyroid acropachy 504
Thyroid antibodies 489
Thyroid cancer, Degroot's staging 519
Thyroid carcinoma, anaplastic, stage grouping 517
Thyroid carcinoma, blood spread 517
Thyroid carcinoma, differentiated 509
Thyroid carcinoma, differentiated, American thyroid association 510
Thyroid carcinoma, differentiated, postoperative AJCC staging 510
Thyroid carcinoma, differentiated, TNM staging 510
Thyroid carcinoma, features of infiltration 517
Thyroid carcinoma, lymph node spread 517
Thyroid carcinoma, medullary, stage grouping 517
Thyroid carcinoma, papillary/follicular, stage grouping 517
Thyroid constipation 506
Thyroid cyst 497
Thyroid dermopathy 504
Thyroid diseases, stridor 520
Thyroid function tests 489, 505
Thyroid gland, anatomy 484
Thyroid gland, blood supply 485
Thyroid gland, congenital anomalies 486
Thyroid gland, development 484
Thyroid gland, ectopic 486
Thyroid gland, physiology 486
Thyroid hormone synthesis 486
Thyroid myopathy 504
Thyroid neoplasms 509
Thyroid neoplasms, Dunhill classification 509
Thyroid ophthalmopathy, Werner' abridged classification 504
Thyroid opthalmopathy, Werner's abridged classification 504
Thyroid paradox 497, 512
Thyroid steal 523
Thyroid stimulating antibodies 499
Thyroid storm 525
Thyroid, adenoma 494
Thyroid, agenesis 489
Thyroid, anaplastic carcinoma 515
Thyroid, black 520
Thyroid, cold nodule 494
Thyroid, discordant nodule 505
Thyroid, discrete nodule 494
Thyroid, dominant nodule 494, 520
Thyroid, Doppler 496
Thyroid, dyshormonogenesis 489
Thyroid, FNAC 489, 512
Thyroid, follicular carcinoma 512
Thyroid, follicular carcinoma, FNAC 513
Thyroid, hot nodule 494
Thyroid, Hurthle cell carcinoma 515
Thyroid, Kocher's incision 521
Thyroid, lateral aberrant 489
Thyroid, lingual 486
Thyroid, malignant lymphoma 519
Thyroid, medullary carcinoma 518
Thyroid, papillary carcinoma 510
Thyroid, papillary carcinoma, AGES scoring 512
Thyroid, papillary carcinoma, AMES scoring 512
Thyroid, papillary carcinoma, Woolner classification 510
Thyroid, pyramidal lobe 484
Thyroid, radio-remnant ablation 514
Thyroid, radioisotope study 505
Thyroid, solitary nodule 494, 520
Thyroid, Tracheal deviation 495
Thyroid, USG 490, 512
Thyroid, vocal cord position 529
Thyroid, warm nodule 494
Thyroidectomy 521
Thyroidectomy, completion 497, 515
Thyroidectomy, complications 524, 1263
Thyroidectomy, hemi 496, 507, 521, 1262
Thyroidectomy, minimally invasive video-assisted (MIVAI) 523
Thyroidectomy, near total 496, 512, 521, 1262
Thyroidectomy, partial 521, 1262
Thyroidectomy, prophylactic total 518
Thyroidectomy, subtotal 493, 507, 521, 1262
Thyroidectomy, total 493, 507, 512, 513, 518, 521, 1262
Thyroidectomy, total, prophylactic 519
Thyroiditis, autoimmune 499
Thyroiditis, de-Quervain's 499, 519
Thyroiditis, Hashimoto's 519
Thyroiditis, Ligneus 520
Thyroiditis, Reidel's 520
Thyroiditis, Woody's 520
Thyrotoxic crisis 525, 1263
Thyrotoxicosis 499
Thyrotoxicosis factitia 499, 500
Thyrotoxicosis, autoimmune 499
Thyrotoxicosis, cardiac manifestation, Crile's grading 504
Thyrotoxicosis, Jod Basedow 499, 500
Thyrotoxicosis, neonatal 499
Thyrotoxicosis, primary 501
Thyrotoxicosis, secondary 501
Thyrotoxicosis, T3 508
Thyrotoxicosis, trophoblastic 500
Thyrotoxicosis, Wayne's diagnostic indices 502
Tillaux's triad 611
Tinea pedis 172
Tongue fissure 416
Tongue muscles 414
Tongue tie 417
Tongue ulcers 415
Tongue, anatomy 414
Tongue, aphthous ulcer 415
Tongue, benign tumour 416
Tongue, dental ulcer 415
Tongue, development and nerve supply 415
Tongue, herpetic lingual ulcer 415
Tongue, lymphatic drainage 414
Tongue, movements 414
Tongue, papillae 414
Tongue, smoker's ulcer 415
Tongue, syphilitic ulcer 415
Tongue, tuberculous ulcer 415
Topical O_2 therapy 118
Torticollis 469
Torus palatinus 367
Total abdominal colectomy 972
Total laryngectomy 430
Total laryngectomy, after care 430
Total proctocolectomy 958
Touhy needle 1236
Tourniquet palsy 280
Tourniquets 127
Tourniquets, complications 128
Tourniquets, types 128
Towel clip, Mayo's 1247
Toxerutin 242
Toxic adenoma 499
Toxic megacolon 955, 958
Toxic thyroid, children 508
Toxic thyroid, pregnancy 508
Toxic thyroid, radioactive isotopes 509
Toxic thyroid, radioiodine therapy 507
Toxic thyroid, surgery 507
TPN, complications 105
TPN, components 105
Tracheostomy tube 1252

Tracheostomy tube, Fuller's bivalved 1252
Tracheostomy tube, Jackson's 1252
Tracheostomy, care 1264
Tracheostomy, complications 1264
Tracheostomy, indications 1263
Tracheostomy, technique 1264
Transcutaneous oximetry 181
Transcyte 136
Transfusion related graft versus host disease 126
Transfusion related lung injury 126
Transhiatal oesophagectomy 846
Transillumination, 'Chinese lantern pattern' 1156
Transitional cell carcinoma, classification 1112
Transjugular intrahepatic portosystemic shunt (TIPSS) 658, 659
Transplantation 353
Transplantation, bone marrow 359
Transplantation, donor criteria 353
Transplantation, heterotopic liver 357
Transplantation, isolated pancreatic islet 359
Transplantation, liver 357
Transplantation, liver, complications 358
Transplantation, liver, donor criteria 357
Transplantation, organ procurement 354
Transplantation, orthotopic liver 357
Transplantation, pancreatic 359
Transplantation, preoperative evaluation 353
Transplantation, renal 354
Transplantation, small bowel 359
Transposition of great vessels 1219
Transpyloric line 773
Transrectal ultrasound 1025
Transtubercular line 773
Transtuzumab (Herceptin) 585, 591
Transurethral resection of prostate (TURP) 1123
Trauma 143
Trauma, management 143
Trauma, mechanism 145
Traumatic fat necrosis 554
Treponema pallidum 56
TRH stimulation test 489
Triad of CDH 1213
Triad of Ohashi 747
Triad, Tillaux 780
Triage 143
Triage algorithm 143
Triage system, types 143
Triamcinolone, intrakeloidal 11
Triangle of Doom 816, 1269
Triangle of pain 817
Triangle of Petit 835
Trichobezoar 898
Trichoepithelioma 294
Trifoliate duodenum 902
Trigone 1105
Triple anastomosis 745
Triple endoscopy 479
Triple phosphate stones 1097, 1107
Trismus 430
Trivex 248
Trotter's triad 423
Truss 811
T-tube removal methods 693
Tubb's dilator 1220
Tube caecostomy 975
Tube, flatus 1255
Tube, infant feeding 1255
Tube, Kehr's T' 1255
Tube, Ryle's 1254
Tubercle 54
Tuberculosis 54
Tuberculosis spine 1190
Tuberculosis, abdomen 615
Tuberculosis, abdomen, ascitic fluid 619
Tuberculosis, abdomen, barium X-ray 618
Tuberculosis, abdomen, CT scan 619
Tuberculosis, abdomen, treatment 620
Tuberculosis, abdomen, ultrasound 619
Tuberculosis, cervical vertebra 1191
Tuberculosis, ileal 621
Tuberculosis, ileocaecal 616, 663, 781
Tuberculosis, intestinal, acute 615
Tuberculosis, intestinal, chronic 615
Tuberculosis, liver 616
Tuberculosis, pancreas 616
Tuberculosis, peritoneal 615, 621
Tuberculosis, peritoneal, acute 622
Tuberculosis, peritoneal, chronic 622
Tuberculosis, renal 1081
Tuberculosis, spleen 616
Tuberculosis, thoracolumbar vertebra 1191
Tuberculous colitis, diffuse 615
Tuberculous dactylitis 170
Tuberculous lymphadenitis 470
Tuberculous lymphadenitis, clinical types 473
Tuberculous lymphadenitis, stages 472
Tuberculous lymphadenitis, treatment 474
Tuberculous lymphadenitis, types 472
Tuberculous, ano-recto-sigmoidal 626
Tuberculous, drugs, WHO recommendation 626
Tuberculous, mesenteric lymphadenitis 624
Tuberculous, omentum 626
Tuberculous, role of steroids 626
Tumour markers 290, 291
Tumour suppressor gene p53 284
Tumour, Buschke-Lowenstein 1147
Tumour, carotid body 468
Tumour, Cock's peculiar 81
Tumour, desmoid 84, 791
Tumour, dumbbell 441, 468, 1193
Tumour, glomus 82
Tumour, Klatskin 695
Tumour, Lindsay 511
Tumour, phylliodes 552
Tumour, potato 468
Tumour, Raspberry 787
Tumour, staging 285
Tumour, sternomastoid 469
Tumour, sternomastoid, treatment 470
Tumour, superior sulcus 1208
Tumour, turban 306
Tumour, ubiquitous 71
Tumour, universal 71
Tumour, Warthin's 444
Tumours, abdominal wall 791
Tumours, cerebellar vermis 1184
Tumours, chest wall 1208
Tumours, colon 961
Tumours, frontal lobe 1184
Tumours, intracranial 1183
Tumours, jaw 381
Tumours, maxillary 426
Tumours, occipital lobe 1184
Tumours, odontogenic 383
Tumours, parietal lobe 1184
Tumours, pituitary 1186
Tumours, retroperitoneal 779
Tumours, spinal 1193
Tumours, temporal lobe 1184
Tumours, third ventricle 1184
Tumours, tonsil 426
Tunica albuginea 1160
Tunica vaginalis 1160
Turnball's '*no-touch*' technique 972
Tween 80 993
Tylosis 858
Tylosis 858
Typhoid Mary 694
Typhoid perforation 929
Tzanakis scoring system 1011

■ U

Uereter-golf hole 1082
Uerteric calculus 1094
Uerteric calculus, Dormia basket 1096
Ulcer 14
Ulcer cancer 903
Ulcer, 'girdle' 617
Ulcer, arterial 23
Ulcer, assessment 19
Ulcer, Bairnsdale 23
Ulcer, base 14
Ulcer, Buruli 23
Ulcer, callous 16
Ulcer, Cameron 848
Ulcer, carcinomatous 24
Ulcer, chilblains 23
Ulcer, chronic 20
Ulcer, classification, clinical 15
Ulcer, classification, pathological 16
Ulcer, cleaning 19
Ulcer, clinical examination 29
Ulcer, cortisol 16
Ulcer, Curling's 134, 878
Ulcer, Cushing's 878, 879
Ulcer, debridement 20
Ulcer, decubitus 21, 214
Ulcer, definition 14
Ulcer, diabetic 25
Ulcer, diabetic, problems 26
Ulcer, discharge 18

Ulcer, Douglas 338
Ulcer, dressing 20
Ulcer, Ducrey's 28
Ulcer, duodenal 882
Ulcer, edge 14
Ulcer, edge biopsy 19
Ulcer, edge, everted 14
Ulcer, edge, punched out 14
Ulcer, edge, raised beaded 14
Ulcer, edge, sloping 14
Ulcer, edge, undermined 14
Ulcer, elusive 1110
Ulcer, floor 14
Ulcer, footballer's 21
Ulcer, frostbite 23
Ulcer, gravitational 28, 249
Ulcer, gummatous 28
Ulcer, healing 16
Ulcer, Hunner's 1110
Ulcer, induration 15
Ulcer, investigation 19
Ulcer, ischaemic 23
Ulcer, kissing 883
Ulcer, malignant 16
Ulcer, management 19
Ulcer, margin 14
Ulcer, Marjolin's 13, 24, 28
Ulcer, Martorell's 23
Ulcer, melanotic 24
Ulcer, Meleney's 26
Ulcer, neurogenic 21
Ulcer, neuropathic 21
Ulcer, nonspecific 16
Ulcer, parts 14
Ulcer, penetrating 21
Ulcer, perforating 21
Ulcer, recurrent 896
Ulcer, rodent 24, 303
Ulcer, specific 16
Ulcer, spreading 15
Ulcer, syphilitic 28
Ulcer, traumatic 20
Ulcer, trophic 21, 214
Ulcer, tropical 16
Ulcer, tuberculous 27
Ulcer, venous 28, 249
Ulcer, Wagener's grading 17
Ulcerative colitis, barium enema 956
Ulcerative colitis, sigmoidoscopy 957
Ulcerative colitis, surgeries 958
Ulcerative colitis, treatment 957
Ulcers, in gastrinoma 757
Ulnar paradox 278, 279
Ultrasound 1238
Ultrasound, A-mode 1238
Ultrasound, B-mode 1238
Ultrasound, M-mode 1238
Umbilectomy 830
Umbilical adenoma 786
Umbilical granuloma 786
Umbilical sinus 786, 787
Umbilicus, diseases 784
Umbolith 787
University of Wisconsin solution 353
Unna boots 242, 250, 251
Upper GI bleed 1061, 1062
Urachal anomalies 1106
Urachal cyst 788, 1106
Urachal diverticulum 788
Urachal fistula 788
Urachal sinus 788, 1106
Urachus, patent 788, 1106
Urban rabies 58
Ureter, anatomy 1066
Ureter, golf hole 1082
Ureter, retrocaval 1079
Ureter, sites of constrictions 1066
Ureteric line 1067
Ureteric meatotomy 1078, 1096
Ureterocele 1080
Ureterocele, Stephen's classification 1080
Ureterorenoscoic stone (URS) removal 1096
Ureterosigmoidostomy 1115
Ureterostomy, Davis-T-tube 1088
Urethra, anatomy 1129
Urethral calculus 1134
Urethral dilatation, complications 1132
Urethritis 1135
Urethroplasty, Johanson's 1132
Urethroplasty, problems in 1132
Urethrostomy, perineal 1145
Urethrotomy, external 1132
Urethrotomy, visual internal cystoscopic 1132
Urinary bilharziasis 1111
Urinary bladder, anatomy 1105
Urinary bladder, sphincter 1105
Urinary diversion 1119
Urinary diversion, complication 1120
Urinary diversion, permanent 1120
Urinary diversion, temporary 1119
Urinary diversion, types 1120
Urine, extravasation 1135
Urine, retention 1136
Urine, retention, management 1136
Urograffin 1067
Urokinase 199
Uterine mass 781

V

VAAFT procedure 1055
VACTER anomalies 857
Vacuum assisted closure 22
Vagotomy, complications 921
Vagotomy, highly selective 870, 884, 921
Vagotomy, parietal selectve 921
Vagotomy, posterior truncal 885
Vagotomy, selective 870, 885, 921
Vagotomy, super selective 921
Vagotomy, truncal 870, 885, 886, 920
Vagotomy, with antrectomy 885
Valve of Geralch 1006
Valve prosthesis, Bjork-Shiley tilting disc 1222
Valve prosthesis, Starr-Edwards ball 1222
Valve replacement surgery 1222
Valves of Houston 1020
van den Bergh's test 628
Varices, reticular 235
Varicocele 1157
Varicocele surgery, Inavissevich approach 1159
Varicocele surgery, laparoscopic approach 1159
Varicocele surgery, Marc-Goldstein approach 1159
Varicocele, grading 1158
Varicocele, infertility 1157
Varicocele, irreducible 1157
Varicocele, primary 1158
Varicocele, secondary 1158
Varicography 242
Varicose vein, stripping 244
Varicose vein, subfascial endoscopic perforator ligation 247
Varicose vein, subfascial ligation of Cockett and Dodd 246
Varicose veins 235
Varicose veins surgery, problems 249
Varicose veins, aetiology 237
Varicose veins, CEAP classification 236
Varicose veins, classifications 235
Varicose veins, complications 240
Varicose veins, compression bandages 251
Varicose veins, compression therapy 251
Varicose veins, drugs 242
Varicose veins, endovenous laser ablation 248
Varicose veins, familial 238
Varicose veins, ligation of short saphenous vein 247
Varicose veins, Linton's approach 247
Varicose veins, pathogenesis 236
Varicose veins, radiofrequency ablation 247
Varicose veins, sclerotherapy 242
Vas aberrans of Haller 1155
Vascular anomalies 221
Vascular malformation 221, 225
Vasectomy 1260
Vasopressin 656
VATER anomaly 1035
'Veins of conduit' 230
Veins of lower limb, anatomy 230
Venogram 233, 241
Venography, ascending 241
Venography, descending 241
Venous blood flow, lower limb, physiology 231
Venous disabilty scoring system 240
Venous diseases 230
Venous Doppler 240, 241
Venous flares 235
Venous haemodynamic mapping 241
Venous refilling time 242
Venous segmental disease score 240
Venous ulcer, complications 251
Verocay bodies 92
Veronesi QUART therapy 582
Verruca necrogenica 84
Verruca plantaris 84
Verrucous carcinoma, cheek 398

Vertical banded gastroplasty 107
Vesical calculus, females 1108
Vesical piles 1122
Vesicostomy 977
Vesicoureteric reflux 1069, 1117
Vicryl 1256
Video assisted thoracoscopic surgery (VATS) 1214
Vigorous achalasia 850
Villous adenoma 936
Vim-Silverman needle 629
Vin rose patch 225
Vincent's angina 391
Vipoma 536, 758
Virchow's triad 231
Visible gastric peristalsis 885
Visick grading 896
Visor approach for oral malignancy 406
Vitellointestinal duct, anomalies 786
VNUS closure 247
Voice change 529
Volkmann's sign 169
Volvulus 997
Volvulus, caecal 997
Volvulus, compound 998
Volvulus, gastric 900
Volvulus, pelvic colon 997
Volvulus, sigmoid 997
von Eber's gland 454
Von Meyenburg's complexes 643
Von Recklinghausen's disease 91, 92, 542
von Willebrand's disease 129
Von-Hippel-Lindau disease 1100
Voval cord position 529

■ W

'W' flap plasty 412
Wagner-Grossman hypothesis 529
Waldeyer's lymphatic ring 455
Wallace's rule of nine 130
Waltzing 347
Wangenstein's invertogram 1035
Wardrop's procedure 203
Warfarin 253
Warthin's starry silver stain 876
Warts 84
Warts, Butcher's 84
Warts, plantar 84
Warts, senile 84
Water can perineum 1135
Water excess 95
Water intoxication 95
Water loss 95
Water shed point 959
Wayne's diagnostic indices 502
Weber-Fergusson incision 427
Weigert Meyer law 1078
Weir-Mitchell's skin 276
Wen 79
Werner's T_3 suppression test 489
Whipple's procedure 743, 744, 753
Whipple's triad 756
White bile 705, 755
White cell trapping theory 236
Wide excision 94
Wild life rabies 58
Wiley's eversion endarterectomy 191
Wilm's tumour 1099
Wilm's tumour, staging 1099
Winging of scapula 281
Witch's milk 558, 560
Wlikinson method 811
Wolf-Chaikoff effect 499
Wound classification 5
Wound failure, acute 788
Wound healing 5
Wound healing, factors affecting 7
Wound healing, phases 6
Wound healing, primary 5
Wound healing, problems 13
Wound healing, secondary 5
Wound healing, stages 6
Wound healing, tertiary 6
Wound healing, types 5
Wound suturing, principles 8
Wound, closed 5
Wound, debridement 7, 8
Wound, excision 8
Wound, open 5
Wound, radical excision 8
Wound, toilet 8
Wounds, management 7
Wrist drop 280
Wry neck 469
Wuchereria bancrofti 39
Wuchereria bancrofti, life cycle 259

■ X

Xenograft 340
Xenon 133 isotope test 182
Xeroderma pigmentosa 298
Xeromammography 548
Xerostomia 434
Xylocaine 1235

■ Y

Yaws 29

■ Z

'Z' plasty 346
Zenker's diverticulum 981
Ziehl-Neelsen stain 619, 626
Zip technique 604
Zoladex 585
Zuckerkandl tubercle 523
Zuska-Atkins disease 563



THIRD EDITION

SRB'S MANUAL OF SURGERY

Sriram Bhat M

Foreword Prakash Rao

Ripped by Dr. Prodigious

JAYPEE

SRB's
Manual of Surgery

SRB's
Manual of Surgery

THIRD EDITION

Sriram Bhat M MS (General Surgery)
Associate Professor in Surgery
Kasturba Medical College
Mangalore
Karnataka, India
e-mail: meera_sriram2003@yahoo.com

JAYPEE BROTHERS MEDICAL PUBLISHERS (P) LTD.

New Delhi • Ahmedabad • Bengaluru • Chennai • Hyderabad
Kochi • Kolkata • Lucknow • Mumbai • Nagpur • St Louis (USA)

Published by
Jitendar P Vij
Jaypee Brothers Medical Publishers (P) Ltd
Corporate Office
4838/24 Ansari Road, Daryaganj, **New Delhi** - 110002, India, Phone: +91-11-43574357
Registered Office
B-3 EMCA House, 23/23B Ansari Road, Daryaganj, **New Delhi** - 110 002, India
Phones: +91-11-23272143, +91-11-23272703, +91-11-23282021, +91-11-23245672
Rel: +91-11-32558559, Fax: +91-11-23276490, +91-11-23245683
e-mail: jaypee@jaypeebrothers.com, Website: www.jaypeebrothers.com

Branches

- 2/B, Akruti Society, Jodhpur Gam Road Satellite
  Ahmedabad 380 015, Phones: +91-79-26926233, Rel: +91-79-32988717
  Fax: +91-79-26927094, e-mail: ahmedabad@jaypeebrothers.com
- 202 Batavia Chambers, 8 Kumara Krupa Road, Kumara Park East
  Bengaluru 560 001, Phones: +91-80-22285971, +91-80-22382956, 91-80-22372664
  Rel: +91-80-32714073, Fax: +91-80-22281761, e-mail: bangalore@jaypeebrothers.com
- 282 IIIrd Floor, Khaleel Shirazi Estate, Fountain Plaza, Pantheon Road
  Chennai 600 008 Phones: +91-44-28193265, +91-44-28194897, Rel: +91-44-32972089
  Fax: +91-44-28193231, e-mail: chennai@jaypeebrothers.com
- 4-2-1067/1-3, 1st Floor, Balaji Building, Ramkote Cross Road
  Hyderabad 500 095, Phones: +91-40-66610020, +91-40-24758498, Rel: +91-40-32940929
  Fax:+91-40-24758499, e-mail: hyderabad@jaypeebrothers.com
- No. 41/3098, B and B1, Kuruvi Building, St. Vincent Road
  Kochi 682 018, Kerala, Phones: +91-484-4036109, +91-484-2395739, +91-484-2395740
  e-mail: kochi@jaypeebrothers.com
- 1-A Indian Mirror Street, Wellington Square
  Kolkata 700 013, Phones: +91-33-22651926, +91-33-22276404, +91-33-22276415
  Rel: +91-33-32901926, Fax: +91-33-22656075, e-mail: kolkata@jaypeebrothers.com
- Lekhraj Market III, B-2, Sector-4, Faizabad Road, Indira Nagar
  Lucknow 226 016, Phones: +91-522-3040553, +91-522-3040554, e-mail: lucknow@jaypeebrothers.com
- 106 Amit Industrial Estate, 61 Dr SS Rao Road, Near MGM Hospital, Parel
  Mumbai 400 012, Phones: +91-22-24124863, +91-22-24104532, Rel: +91-22-32926896
  Fax: +91-22-24160828, e-mail: mumbai@jaypeebrothers.com
- “KAMALPUSHPA” 38, Reshimbag, Opp. Mohota Science College, Umred Road
  Nagpur 440 009 (MS), Phone: Rel: +91-712-3245220, Fax: +91-712-2704275, e-mail: nagpur@jaypeebrothers.com

USA Office
1745, Pheasant Run Drive, Maryland Heights (Missouri), MO 63043, USA, Ph: 001-636-6279734
e-mail: jaypee@jaypeebrothers.com, anjulav@jaypeebrothers.com

SRB’s Manual of Surgery

© 2009, Sriram Bhat M

All rights reserved. No part of this publication should be reproduced, stored in a retrieval system, or transmitted in any form or by any means: electronic, mechanical, photocopying, recording, or otherwise, without the prior written permission of the author and the publisher.

This book has been published in good faith that the material provided by author is original. Every effort is made to ensure accuracy of material, but the publisher, printer and author will not be held responsible for any inadvertent error(s). In case of any dispute, all legal matters are to be settled under Delhi jurisdiction only.

First Edition: 2004
Second Edition: 2007
Third Edition: **2009**

ISBN 978-81-8448-551-6

Typeset at JPBMP typesetting unit
Printed at Replika

God could not be everywhere all the time,
so, He created Mothers

This Book is in the memory of my mother
Late Mrs Devaki Krishna Bhat
who continues to inspire and guide me

Foreword

A true surgeon is never fearless; he fears for his patients, he fears for his shortcomings, his own mistakes, but never fears for himself or his professional reputation.

—Samule J Mixter

The manual is written for the students in this firing line for their MBBS degree. Common conditions seen on a day-to-day basis have dealt with a little more detail. The uncommon and rare conditions have been dealt briefly. The mode of clinical presentation and the physical signs are mentioned vividly so as to register in the mind of the reader. There is a brief mention of necessary investigations in each of the surgical conditions. The accepted mode of recent advances in investigation and treatment has been included. This manual is meant for Final MBBS degree examination and not a consolidated textbook. Certain chapters are included at the end of the book for the more enthusiastic students and for those interested in participating in quiz programmes.

The clinical photographs are of very good quality, which are self-explanatory of the conditions. The clinching physical signs have been highlighted in box forms with different shades of colour. This mode of presentation emphasises the point to be conveyed to the students which they can recollect when required either while arriving at a diagnosis in their examination or while in practice after obtaining the degree. This book gives a good foundation in surgery for those who wish to pursue surgery as a career.

What does the surgeon ought to be?

The conditions necessary for the surgeon are four—*first*, he should be learned; *second*, he should be an expert; *third*, he must be ingenious; *fourth*, he should be able to adapt himself.

Foremost, it is required that the surgeon should know not only the principles of surgery, but also those of medicine in theory and practice; second, he should have seen others operate; third, he should be ingenious, of good judgement and memory to recognize conditions; and the fourth, he should be adaptable and able to accommodate himself to circumstances.

Let the surgeon be bold in all sure things, and fearful in dangerous things, let him avoid all faulty treatments and practices. He ought to be gracious to the sick, considerate to his associates, cautious in his prognostications. Let him be modest, dignified, gentle, pitiful, merciful; neither covetous nor an extortionist of money; but rather let his reward be according to his work, to the means of the patient, to the quality of the issue, and to his own dignity.

—Ars Chirurgica

I thank Sriram Bhat M for giving me this privilege of writing a foreword to his excellent manual.

Dr Prakash Rao MS
Professor in Department of Surgery
Kasturba Medical College, Mangalore

Preface to the Third Edition

It is my pleasure to release the third edition within two years of release of second edition of *SRB's Manual of Surgery*. Earlier editions were well-accepted by undergraduates and postgraduates. I felt to bring out the third edition in the intention of making it much more illustrative with more diagrams and clinical and operative photographs. I have extensively done corrections in this edition. I added many new materials, text details, new additional topics in different chapters. Malignancies are discussed in much more detail with new staging and present oncological trends. Mistakes are corrected and insufficient topics are upgraded. I have referred many books, journals and took help of my colleagues in surgery and other departments like radiodiagnosis and ENT from my college KMC Mangalore. I have retained all chapters with some rearrangements of few chapters and topics.

I sincerely express my thanks to everybody who have helped me and also to the publishers who are the backbone of this upgraded edition.

I hope this new book will be well-accepted by the teachers, undergraduates and postgraduates of surgery department. I sincerely welcome all criticisms.

December 2008

Sriram Bhat M

Preface to the First Edition

This book is born out of a desire to provide a complete, authoritative, current textbook on Surgery. For the past fifteen years of my teaching profession, watching students hurriedly jotting down notes during classes, an urge was born within me to put my thoughts in print. I am fortunate to have been guided by my teachers and supported by my students towards this goal.

An attempt has been made to make this book simple and reader-friendly while not compromising on the aspect of providing students with necessary information and a better clinical understanding of surgery. Recent advances in surgery till date have been included to the best of my knowledge. Text has been presented in a simple and lucid language so as to help students understand and recapitulate the subject better. Since a picture is worth than thousand words, over 500 photos, X-rays and illustrations have been incorporated in this work to make surgery more interesting and understandable. Inspirational quotes have been interspersed to motivate students to go the extra mile.

Discussion on Instruments and Operative Procedures has been dealt with in necessary detail separately. A chapter containing a list of interesting new developments in surgery and uniquely new topics like Fascinating Signs, Misnomers, Triads and other interesting chapters have been included.

While this book has been compiled with undergraduates in mind, I'm confident that it will serve as a useful reference for postgraduates and practitioners.

In compiling this book I have consulted many authoritative books and publications and I sincerely express my appreciation and gratitude to all of them.

Suggestions and constructive criticisms towards improving this book in subsequent editions are always welcome.

November 2003 **Sriram Bhat M**

Acknowledgements

I am happy to bring out one more edition (third) of the book *SRB's Manual of Surgery*. This is due to constant help and support of many.

I thank our Chancellor Dr Ramdas M Pai; Pro-Chancellor Dr HS Ballal; Vice-Chancellor of MAHE Prof Rajashekaran Warrier; our beloved Dean Prof CV Raghuveer; our Vice-Deans Prof Anand Kini and Prof Venkatraya Prabhu for their academic support.

I thank Prof Thangam Varghese, Head of Department of Surgery, KMC Mangalore for her constant encouragement in academic work and progress.

I always remember my senior teachers, Prof CR Ballal and Prof Suresh Kamath for their constant help.

Our senior faculty in the department, Prof K Prakash Rao who is a guide and encourager to everybody, will be remembered as a special person by me always.

Surgical unit heads in our college Dr BM Nayak, Dr Jayaram Shenoy, Dr Jayaprakash Rao, Dr Harish Rao, Dr Ramachandra Pai, Dr Alfred Augustine and Dr Shivananda Prabhu are always supportive for my work and are worth to be remembered always.

I am grateful to all my teachers and colleagues in Surgery Department who directly or indirectly helped me to bring out this third edition.

I appreciate District Medical Officer and Resident Medical Officer of Government Wenlock Hospital, Mangalore for their kind help.

I thank very much to the faculty, Department of Surgery and Paediatric Surgery, JJMMC Davangere for providing the needed photographs.

I sincerely thank Prof Navin Chandra Shetty, Head of Radiology Department, KMC Mangalore and also other faculty of the department for their help in providing and guiding me in X-rays, CT scans and imaging methods.

I acknowledge Prof Kishore Chandra Prasad, Head of Department of ENT for his help, guidance and encouragement in bringing out this book.

I thank Dr Shivaprasad Rai; Dr Ahfaque Mohammed; Dr Kalpana Sridhar; Dr Yogish Kumar; Dr Ramesh; Dr K Akbar; Dr Keshava Prasad; Dr Kishore Reddy; Dr Achaleshwar Dayal; Dr Raghav Pandey; Dr Rupen; Dr Ashwini Mallya; Dr Praveen; Dr Ashok Hegde; Dr Rajesh Ballal; Dr Devidas Shetty; Dr Venkatesh Sanjeeva; Dr Sunil; Dr Shanbogh; Dr Harish Nayak; Dr Subraya Kamath; Dr Venkatesh Shanbogh; Dr Tantri; Dr Sandeep Gopal; Dr Ganesh; Dr Sampath for their help in various aspects.

I sincerely appreciate Dr Raghavendra Bhat and Dr Ravichandra, consultants in Radiology Department, Yenepoya Medical College, Mangalore for their contribution and affectionate help.

I thank Dr Ganesh Pai MCh (Paediatric Surgery); Dr Suresh Pai MCh; Dr Ashok Shetty (Cardio Thoracic Surgery); Dr Muralidhar Pai MCh (Neurosurgery); Dr Vivekanand Prabhu (Paediatric Surgery); Dr Sadashiva Rao (Paediatric Surgeon); Dr Narayana Bhat (Paediatric Surgeon); Dr Prashanth Mallya (Anaesthetist); Dr Subramanya Bhat (Sonologist) for their help and contributions.

I will never forget my close associates Dr Ganapathy MD, Mangala Hospital, Kadri, Mangalore and Dr Ashok Pandit, MCh (Urologist) for their affectionate help and encouragement in all my endeavours. They always stood with me in my difficulties.

I thank my friend Dr Jagadish MDS for his contributions to X-ray and opinion on dental and faciomaxillary topics.

My special thanks to Dr Harikiran Chekuri, Hyderabad for his help in correcting the mistakes.

My wife Dr Meera Karanth helped me day and night in revising this edition and without her help this could not have been possible. My beloved daughter Ananya helped me in drawing new diagrams artistically. I enjoy her love and affection towards me.

I remember my students Dr Ravi CR; Dr Ashwini Polnaya; Dr Ishwara Keerthi; Dr Sudesh; Dr Narasimha Murthy; Dr Nithin for their special contributions.

I thank all my students especially postgraduates of Surgery Department who were helping regularly in bringing out this edition.

Words are not sufficient to remember all my patients who are the main material for the book. I pray for their good health always.

I appreciate Shri Jitendar P Vij (Chairman and Managing Director), Mr Tarun Duneja (Director-Publishing) and all staff of the Jaypee Brothers Medical Publishers (P) Ltd, New Delhi for doing appreciable work in their respective field of printing and publishing.

Sriram Bhat M

Contents

1. General Surgery 1
- a. *Wounds and Wound Healing* *1*
- b. *Ulcer* *12*
- c. *Sinus and Fistula* *25*
- d. *Infectious Diseases* *30*
- e. *Swellings* *61*
- f. *Electrolyte and Nutrition* *81*
- g. *Shock* *91*
- h. *Haemorrhage and Blood Transfusion* *100*
- i. *Burns* *106*
- j. *Trauma* *118*
- k. *Hand and Foot* *128*
- l. *Arterial Diseases* *144*
- m. *Hamartoma and Vascular Lesions* *179*
- n. *Venous Diseases* *187*
- o. *Lymphatics* *209*
- p. *Peripheral Nerves* *224*
- q. *Neoplasm* *232*
- r. *Skin Tumours* *243*
- s. *Sarcomas* *263*
- t. *Amputations* *271*
- u. *Reconstruction* *279*
- v. *Transplantation* *290*
- w. *Stings and Bites* *296*
- x. *Pain* *298*

2. Faciomaxillary Diseases 300

3. Oral Cavity 321

4. Salivary Glands 356

5. Neck 377

6. Thyroid 403

7. Parathyroids and Adrenals 444

8. Breast 453

9. Peritoneum 498

10. Abdominal Tuberculosis 512

11. Liver 525

12. Gallbladder 561

13. Spleen 599

14. Pancreas **612**

15. Retroperitoneal Space **647**

16. Differential Diagnosis of Mass Abdomen **653**

17. Abdominal Wall and Umbilicus **666**

18. Hernia **677**

19. Oesophagus **717**

20. Stomach **745**

21. Small Intestine **797**

22. Large Intestine **817**

23. Intestinal Obstruction **851**

24. Appendix **873**

25. Rectum and Anal Canal **888**

26. Urology **928**

a. *Kidney* *928*
b. *Urinary Bladder* *969*
c. *Prostate* *986*
d. *Urethra* *995*
e. *Penis* *1004*
f. *Scrotum* *1015*
g. *Testis* *1026*

27. Neurosurgery **1037**

28. Thorax **1060**

a. *Throax* *1060*
b. *Cardiac Surgery* *1081*

29. Adjuvant Therapy **1091**

- *Radiotherapy* *1091*
- *Chemotherapy* *1094*
- *Hormone Therapy in Cancer* *1096*
- *Immunotherapy* *1097*
- *Gene Therapy* *1097*

30. Anaesthesia **1099**

31. Advanced Imaging Methods **1107**

32. Operative Surgery **1114**

a. *Asepsis and Sterilisation* *1114*
b. *Instruments* *1117*
c. *Suture Materials* *1127*
d. *Diathermy (Electrocautery)* *1129*
e. *Operative Procedures* *1130*
    i. Abdominal Incisions *1130*
    ii. Vasectomy *1131*
    iii. Circumcision *1131*
    iv. Hydrocele *1132*
    v. Inguinal Hernia *1132*
    vi. Appendicectomy *1133*

    - *vii. Thyroidectomy* *1134*
    - *viii. Tracheostomy* *1135*
    - *ix. Cryosurgery* *1136*
    - *x. Lasers in Surgery* *1136*
    - *xi. Staplers in Surgery* *1137*
- f. *Laparoscopic Surgery* *1139*
- g. *Dressings and Bandages* *1144*
- *h. Day Care Surgery* *1146*

33. Miscellaneous 1147

- *Fascinating Signs in Surgery* *1147*
- *Triads in Surgery* *1159*
- *Misnomers in Surgery* *1161*
- *Triangles in Surgery* *1162*
- *Drugs at a Glance* *1164*

Appendix *1171*

Further Reading *1175*

Index *1177*

1

General Surgery

Wounds and Wound Healing

> ***One having a wound in his eyebrow. An ailment which I will treat. Treatment [of a wound in the eyebrow]: Now after thou hast stitched it, [thou shouldst bind] fresh meat upon [it] the first day. If thou findest that the stitching of this wound is loose, thou shouldst draw it together for him with two strips (of plaster), and thou shouldst treat it with grease and honey every day until he recovers.***
>
> **—[Anonymous]**, circa 2500 BC

Wounds
Wound healing
Compartment syndrome
Crush injury
Crush syndrome
Degloving injuries
Keloid
Hypertrophic scar

WOUNDS

Wound Definition

A wound is a break in the integrity of the skin or tissues often, which may be associated with disruption of the structure and function.

CLASSIFICATION OF WOUNDS (Rank and Wakefield)

a. *Tidy Wounds*

They are wounds like surgical incisions and wounds caused by sharp objects.

Usually primary suturing is done. Healing is by primary intention.

b. *Untidy Wounds*

- They are due to:
  - Crushing.
  - Tearing.
  - Avulsion.
  - Devitalised injury.
  - Vascular injury.
  - Multiple irregular wounds.
  - Burns.
- Fracture of the underlying bone may be present. Wound dehiscence, infection, delayed healing are common.
- Liberal excision of devitalised tissue and allowing to heal by secondary intention is the management.
- Secondary suturing, skin graft or flap may be needed.

Other Classification

1. ***Clean incised wound*** is a clean cut wound with linear edge.
2. ***Lacerated wounds*** have ragged edges with devitalisation of some part of tissues. Wound excision and primary suturing is done.

I dressed him and God healed him.— Ambroise Pare



Fig. 1.1: Lacerated wound in the scalp.

3. ***Bruising and contusion***: Minor soft tissue injury with discoloration and haematoma formation without skin break.
4. ***Haematoma***: It may be subcutaneous/intramuscular/subfascial/intraarticular. Small haematoma will get absorbed. Large haematoma once get infected forms an abscess and so it should be drained under general/regional anaesthesia adequately. Often haematoma contains only reddish plasmatic fluid which can be aspirated with wide bore needle.
5. Closed blunt injury.
6. Puncture wounds and bites.
7. ***Abrasion***: It is superficial and is due to shearing of skin where the surface is rubbed off. It heals by epithelialisation. It is only epidermal injury exposing dermis and dermal nerves.



Fig. 1.2: Haematoma in the groin being aspirated. Haematoma may get infected or can compress adjacent structures.



Fig. 1.3: Subungual haematoma. Often nail may need to be removed to evacuate the blood clot.

8. Traction and avulsion injury.
9. ***Crush injury:*** It is caused by war wounds, road traffic accidents, tourniquet. It leads to:
   - Compartment syndrome.
   - Muscle ischaemia.
   - Gangrene, loss of tissue.
10. War wounds and gunshot injuries.
11. Injuries to ***bones and joints, may be open or closed.***
12. Injuries to ***nerves, either clean cut or crush.***
13. Injuries to ***arteries and veins*** (major vessels).
14. Injury to internal organs, may be of penetrating or nonpenetrating (blunt) types.
15. Penetrating wounds – commonly due to stab injuries. Common example is stab injury abdomen. Stab wound may be small on body surface but damage to the deeper organs like liver, spleen, major vessels like inferior vena cava / mesenteric vessels or intestines may be extensive and life threatening. Patients with stab injury over abdomen should be admitted and evaluated by ultrasound or CT scan abdomen and observed. Often wound exploration is needed under general anaesthesia in operation theatre.

CLASSIFICATION OF SURGICAL WOUNDS

1. **Clean wound**
   - Herniorrhaphy.
   - Excisions.
   - Surgeries of the brain, joints, heart, transplant.
   - Infective rate is less than 2%.
2. **Clean contaminated wound**
   - Appendicectomy.
   - Bowel surgeries.



Fig. 1.4: Clean wound for inguinal hernia surgery.



Fig. 1.5: Clean wound for thyroidectomy surgery.



Fig. 1.6: Appendicectomy wound, which is a clean contaminated wound.



Fig. 1.7: Hernia surgery with hernia sac. It is a clean wound.

- Gallbladder, biliary and pancreatic surgeries.
- Infective rate is 10%.

3. **Contaminated wound**
   - Acute abdominal conditions.
   - Open fresh accidental wounds.
   - Infective rate is 15-30%.
4. **Dirty infected wound**
   - Abscess drainage.
   - Pyocele.
   - Empyema gallbladder.
   - Faecal peritonitis.
   - Infective rate is 40-70%.

Wound Classifications	
• *Simple wounds* – only skin is involved. • *Complex wounds* – vessels, nerves, tendons or bones are involved.	• *Tidy wounds* • *Untidy wounds*
Closed wounds – • Contusion • Abrasion • Haematoma *Open wounds* – • Incised wounds • Lacerated wounds • Crush injuries • Penetrating wounds	• Clean wound • Clean contaminated wound • Contaminated wound • Dirty wound

A great part, I believe, of the art of medicine is the ability to observe—Hippocrates, Father of Medicine



Fig. 1.8: Degloving injury in the thigh extending into the leg.



Fig. 1.9: Wound causing extensive skin loss and necrosis.





Figs 1.10A and B: Wound with tension sutures after surgeries for acute abdomen/peritonitis. It is a contaminated wound. Both vertical and horizontal tension sutures are shown.

WOUND HEALING

> ***A scab is a beautiful thing—a coin the body has minted, with an invisible motto: In God We Trust. Our body loves us, and, even while the spirit drifts dreaming, works at mending the damage that we do.***
>
> **—John Updike,** 1984

Types of Wound Healing

Primary Healing (First intention)

It occurs in a clean incised wound or surgical wound. Wound edges are approximated with sutures. There is more epithelial regeneration than fibrosis. Wound heals rapidly with complete closure. Scar will be linear, smooth, and supple.

Secondary Healing (Second intention)

It occurs in a wound with extensive soft tissue loss like in major trauma, burns and wound with sepsis. It heals slowly with fibrosis. It leads into a wide scar, often hypertrophied and contracted. It may lead into disability.



Fig. 1.11: Wound in the abdomen healing with second intention which requires secondary suturing once it granulates well. Secondary suturing is done after 10-14 days, once wound granulates well with proper control of infection. Scar in such type is prone to form incisional hernia.

Stages of Wound Healing

- Stage of inflammation.
- Stage of granulation tissue formation and organisation. Here due to fibroblastic activity synthesisation of collagen and ground substance occurs.
- Stage of epithelialisation.
- Stage of scar formation and resorption.
- Stage of maturation.

Phases of Wound Healing

Inflammatory Phase (Lag or Substrate or Exudative phase)

- It begins immediately after wound healing. It lasts for 4-6 days.
- Features of inflammation are rubor, calor, tumour, dolor and loss of function.
- Macrophages secrete fibroblastic growth factor which enhances angiogenesis.
- Polymorphonuclear leukocytes (PMN leukocytes) appear after 48 hours which secrete inflammatory mediators and bactericidal oxygen derived free radicals.
- These cells also remove clots, foreign bodies and bacteria.
- Chemical factors involved in wound healing are:
  - Growth factor—platelet derived, epidermal, transforming.
  - Interleukin.
  - Tumour necrosis factor.
  - Prostaglandins.
  - Collagenase.
  - Elastase.





Figs 1.12A and B: Healing ulcer with healthy granulation tissue which is ready for skin grafting.

Proliferative Phase (Collagen/Fibroblastic phase)

- Collagen and glycosamines are produced by fibroblasts.
- It begins in 7 days and lasts for 6 weeks.
- Hydroxyproline and hydroxylysine are synthesised by specific enzymes using iron, alpha ketoglutarate and vitamin C.
- Tropocollagen is produced which aggregates to form collagen fibrils.
- 80-90% of their final strength (in postoperative wounds) is achieved in 30 days.

Remodeling Phase (Maturation phase)

- It begins at 6 weeks and lasts for 2 years.
- There is maturation of collagen by cross-linking which is responsible for tensile strength of the scar.
- Collagen production is not present after 42 days of wound healing.

Factors Affecting Wound Healing

Local Factors

1. Infection
2. Presence of necrotic tissue and foreign body
3. Poor blood supply
4. Venous or lymph stasis
5. Tissue tension
6. Haematoma
7. Large defect or poor apposition
8. Recurrent trauma
9. X-ray irradiated area
10. Site of wound, e.g. wound over the joints and back has poor healing
11. Underlying diseases like osteomyelitis and malignancy
12. Mechanism and type of wound – incised/lacerated/crush/avulsion

Start by doing what's necessary, then do what's possible and suddenly you are doing the impossible.

General Factors

1. Age, obesity, smoking
2. Malnutrition
3. Vit deficiency (Vit C)
4. Anaemia
5. Malignancy
6. Uraemia
7. Jaundice
8. Diabetes, metabolic diseases
9. HIV and immunosuppressive diseases
10. Steroids and cytotoxic drugs
11. Neuropathies of different causes

Management of Wounds

1. Wound is inspected and classified as per the type of wounds.
2. If it is in the vital area, then
   - The airway should be maintained.
   - The bleeding, if present, should be controlled.
   - Intravenous fluids are started.
   - Oxygen, if required, may be given.
   - Deeper communicating injuries and fractures etc. should be looked for.
3. If it is an incised wound then primary suturing is done after thorough cleaning.
4. If it is a lacerated wound then the wound is excised and primary suturing is done.
5. If it is a crushed or devitalised wound there will be oedema and tension in the wound. So after wound debridement or wound excision by excising all devitalised tissue, the oedema is allowed to subside for 2-6 days. Then delayed primary suturing is done.
6. If it is a deep devitalised wound, after wound debridement it is allowed to granulate completely. Later, if the wound is small secondary suturing is done. If the wound is large a split skin graft (Thiersch graft) is used to cover the defect.
7. In a wound with tension, fasciotomy is done so as to prevent the development of compartment syndrome.
8. Vascular or nerve injuries are dealt with accordingly. Vessels are sutured with 6-zero polypropylene nonabsorbable suture material. If the nerves are having clean cut wounds it can be sutured primarily with polypropylene 6-zero or 7-zero suture material. If there is difficulty in identifying the nerve ends or if there are crushed cut ends of nerves then marker stitches are placed using silk at the site and later secondary repair of the nerve is done.
9. Internal injuries (intracranial by craniotomy, intrathoracic by intercostal tube drainage, intra-abdominal by laparotomy) has to be dealt with accordingly. Fractured bone is also identified and properly dealt with.
10. Antibiotics, fluid and electrolyte balance, blood transfusion, tetanus toxoid, (0.5 ml intramuscular to deltoid muscle) or antitetanus globulin (ATG) injection.

Wound debridement (wound toilet, or wound excision) is liberal excision of all devitalized tissue at regular intervals (of 48-72 hours) until healthy, bleeding, vascular tidy wound is created.

Primary suturing means suturing the wound immediately within 6 hours. It is done in clean incised wounds.

Delayed primary suturing means suturing the wound in 48 hours to 10 days. It is done in lacerated wounds. This time is allowed for the oedema to subside.



Figs 1.13A and B: Delayed primary suturing is done once oedema over the wound subsides. It is done as single layer interrupted deep sutures using monofilament polypropylene or polyethylene.

Secondary suturing means suturing the wound in 10-14 days or later. It is done in infected wounds. After the control of infection, once healthy granulation tissue appears, secondary suturing is done.

Principles of wound suturing

- Primary suturing should not be done if there is oedema/infection/devitalised tissues/haematoma
- Always associated injuries to deeper structures like vessels/nerves or tendons should be looked for before closure of the wound
- Wound should be widened by extending the incision whenever needed to have proper evaluation of the deeper structures – *proper exploration*
- Proper cleaning, asepsis, wound excision/debridement
- Any foreign body in the wound should be removed
- Skin closure if it is possible without tension
- Skin cover by graft/flap – immediate or delayed
- Untidy wound should be made tidy and clean before suturing
- Proper aseptic precautions should be undertaken
- Antibiotics/analgesics are needed
- Sutured wound should be inspected in 48 hours
- Sutures are removed after 7 days

Remember

- *Wound toilet* is washing the wound thoroughly using normal saline
- *Wound debridement* (french- letting loose) is allowing content to come out by release incisions or faciotomies. But commonly debridement is used for wound excision
- *Wound excision* is actually correct terminology for excision of devitalised tissues once or serially
- *Radical wound excision* is (pseudotumour approach) is excising entire devitalised tissues leaving tissues with visible bleeding from all layers



Fig. 1.14: Necrotizing fasciitis with extensive skin involvement which requires adequate wound excision and eventual skin coverage.

COMPARTMENT SYNDROME

It is common in calf and forearm. Closed injuries cause haematoma leading to increased pressure. It is often associated with fracture of the underlying bone which in turn compresses the major vessel further aggravating the ischaemia causing ***pallor, pulselessness, pain, paraesthesia, diffuse swelling*** and ***cold limb***.

If allowed to progress it may eventually lead to ***gangrene*** or ***chronic ischaemic contracture*** with deformed, disabled limb.

Problems with the compartment syndrome

- Infection, septicaemia and abscess formation
- Renal failure
- Gangrene of the limb
- Chronic ischaemic contracture
- Disabled limb

Muscle necrosis releases myoglobulin which is excreted in the urine, damages the kidneys leading into renal failure.

Note: Affected muscle when passively stretched worsens the pain – the most reliable clinical sign.

Treatment

- Compartment pressure will be persistently more than 30 mm Hg. It can be measured by placing a fine catheter in the compartment and using a pressure monitor. This is an indication for *fasciotomy*. Adequate lengthy incision involving skin, fat and deep fascia should be done until underneath muscle bulges out properly. Multiple incisions should be made if needed. Separate incision in each compartment should be done.



Fig. 1.15: Fasciotomy for compartment syndrome should be longitudinal, deep and lengthy and should decompress the compartment to expose the underlying muscle.

> *Clinical diagnosis is an art, and the mastery of an art has no end: you can always be a better diagnostician.*
>
> —Logan Clendening

- Antibiotics.
- Catheterisation.
- Mannitol or diuretics to cause diuresis, so as to flush the kidney.
- Fresh blood transfusion.
- Hyperbaric oxygen.

CRUSH INJURY

Crush injury is one where a part of the body is being squeezed/compressed between two high force or pressure systems. It causes extensive lacerations, bruising, compartment syndrome, crush syndrome, fractures, haemorrhage etc. with extensive tissue destruction and devitalisation. Renal failure, hypovolaemic shock and sepsis are the most dreaded problems in crush injuries.

CRUSH SYNDROME

It is due to crushing of muscles causing extravasation of blood and release of myohaemoglobin into the circulation leading to *acute tubular necrosis* and *acute renal failure*.

Causes

- Earthquakes.
- Mining and industrial accidents.
- Air crash.
- Tourniquet.

Initially tension increases in the ***muscle compartment*** commonly in the limb, which itself impedes the circulation and increases the ***ischaemic damage***. In 3 days, urine becomes discoloured and scanty, patient becomes restless, apathy and delirious with onset of ***uraemia***. Crush syndrome is often life threatening. *Injury* is much worser than initial look.

Effects of crush syndrome

- Renal failure
- Toxaemia
- Septicaemia
- Disability with extensive tissue loss
- Gas gangrene

Treatment

- Tension in the muscle compartment is relieved by placing *multiple parallel deep incisions* in the limb so as to prevent further damage.
- Rheomacrodex, or Mannitol is given to improve the urine output by improving the renal function.
- Alkalisation of urine is done by giving sodium citrate or sodium bicarbonate. It increases the solubility of acid haematin in the urine and so promotes its excretion. Urinary pH should be above 6.5 until urine does not show any myoglobin. Mannitol – alkaline diuresis should be 8 liter/day.
- Initial aggressive volume load using saline about 1–1.5 liters/hour is ideal in these patients.
- Haemodialysis is done sometimes as a life-saving procedure.
- Other measures:
  - Catheterization.
  - Oxygen therapy.
  - Antibiotics.
  - Blood transfusion.
  - Correction of severe hyperkalaemia.

Note: Doing fasciotomy several days after crush injury may not be safe as it may lead to sudden release of myoglobulin causing myoglobulinuria and renal failure.

DEGLOVING INJURIES

- It occurs due to shearing force between tissue planes as traction – avulsion injury. It usually occurs between subcutaneous tissue and deep fascia or between muscle and bone. It can be localised or circumferential.
- It can be in one plane or multiple planes.
- It is commonly observed in machinery injuries or major road traffic accidents. It is much more extensive than of on initial presentation.
- Under anaesthesia fluoroscein is injected intravenously and viable skin is visible as fluorescent yellowish – green colour under ultraviolet light. As injection of fluoroscein is not fully safer, serial excision is better to look for dermal punctate bleeding.
- It needs examination under general anaesthesia, wound excision/radical excision, flap coverage, micro flap surgeries, skin grafting, with proper asepsis, and blood transfusion as there is significant blood loss in these injuries.



Fig. 1.16: Degloving injury wherein skin often with soft tissues gets avulsed off the deeper plane to create extensive raw area which may bleed/get infected.

KELOID: '*Like a claw*'

- Keloid is common in blacks. Common in females.
- Genetically predisposed. Often familial.
- There is defect in maturation and stabilization of collagen fibrils.

- Keloid continues to grow even after 6 months, may be for many years. It extends into adjacent normal skin. It is brownish black/pinkish black (due to vascularity) in colour, painful, tender and sometimes hyperaesthetic.
- Keloid may be associated with Ehlers – Danlos syndrome or scleroderma.
- When keloid occurs following an unnoticed trauma without scar formation is called as *spontaneous keloid*, commonly seen in Negros.
- Some keloids occasionally become non-progressive after initial growth.
- Pathologically keloid contains proliferating immature fibroblasts, proliferating immature blood vessels and type III thick collagen stroma.

Site: Common over the sternum. Other sites are upper arm, chest wall, lower neck in front.

Differential diagnosis: Hypertrophic scar.

Treatment: Controversial.

1. Excision and skin grafting.



Figs 1.17A and B: Keloid in chest below the sternum and upper part of arm near shoulder – common sites of occurrence.



Figs 1.18A and B: Keloid over sternum. Note the typical common site.



Fig. 1.19: Keloid in the upper part of the scar. It is the previous parotidectomy scar.

When you smile world smiles with you. When you cry, it will be your alone.



Figs 1.20A and B: Keloid in the chest wall due to burn wound.

2. Irradiation.
3. Excision and irradiation.
4. Steroid injection—***Intrakeloidal triamcinolone***, is injected at regular intervals, may be once in 7-10 days, of 6-8 injections.
5. Steroid injection—Excision—Steroid injection.
6. Methotrexate and vitamin A therapy into the keloid.
7. Silicone gel sheeting.
8. Laser therapy.
9. Vitamin E/palm oil massage.
10. *Intralesional excision* retaining the scar margin may prevent recurrence. *It is ideal and better than just excision.*

Recurrence rate is very high—more than 50%.

HYPERTROPHIC SCAR

- Occurs anywhere in the body.
- Not genetically predisposed. Not familial.


Epidermis
Linear scar in clean wound
Dermis
Scar (linear)
Subcutaneous tissue
Hypertrophic scar in infected wound limits to scar
Scar (hypertrophic)
Keloid in genetically predisposed extends to normal skin
Scar (keloid)

Fig. 1.21: Diagrammatic representation of linear, hypertrophic and keloid scar.

- Growth usually limits up to 6 months.
- It is limited to the scar tissue only. It will not extend to normal skin.
- It is pale brown in colour, not painful, nontender.
- Often self limiting also. It responds very well for **steroid** injection.
- Recurrence is uncommon.

Differences between Keloid and Hypertrophic scar

	Keloid	*Hypertrophic scar*
a. Genetic predisposition	Yes	No
b. Site of occurrence	Chest wall, upper arm, lower neck, ear	Anywhere in the body, Common in flexor surfaces
c. Growth	Continues to grow without time limit	Growth limits for 6 months
	Extends to normal skin	Limited to scar tissue only
d. Treatment	Poor response	Good response to steroids
e. Recurrence	Very high	Is uncommon
f. Collagen synthesis	20 times more than normal skin (Type III thick)	6 times more than normal skin (Type III fine collagen)
g. Relation of size of injury and lesion	No relation. Small healed scar can form large keloid	Related to size of injury and duration of healing
h. Age	Adolescents, middle age	Children
i. Sex	Common in females	Equal in both
j. Race	More in blacks (15 times)	No racial relation
k. Structure	Thick collagen with increased epidermal hyaluronic acid	Fine collagen with increased alpha actin



Figs 1.22A and B: Different contractures in hypertrophic scars over forearm, finger and neck.

- It is common in wounds crossing tension lines, deep dermal burns, wounds healed by secondary intention.



Fig. 1.23: 'Z' plasty is very useful method to release small contractures.

Complications

- Often this scar breaks repeatedly and causes infection, pain.
- After repeated breakdown it may turn into ***Marjolin's ulcer***.
- It is controlled by ***pressure garments*** or often revision excision of scar and closure, if required with skin graft.

Self-assessment Questions

- Factors affecting wound healing.
- Classify wounds.
- Keloid.
- Hypertrophic scar.
- Compartment syndrome.
- Crush syndrome.
- Wound debridement.

Success is getting what you want. Happiness is liking what you get.

Ulcer

Ulcer—*Definition, parts of an ulcer, induration of an ulcer, classification*
Granulation tissue
Investigation of an ulcer
Trophic ulcer
Ulcer due to chilblains
Ulcer due to frostbite
Martorelle's ulcer
Bairnsdale ulcer
Diabetic ulcer
Meleney's ulcer
Lupus vulgaris
Bazin's disease
Tropical ulcer
Clinical examination of an ulcer

ULCER

Definition

An ulcer is a break in the continuity of the covering epithelium, either skin or mucus membrane due to molecular death.

Parts of an Ulcer

1. *Margin*: It may be regular or irregular. It may be rounded or oval.



Fig. 1.24: Parts of an ulcer.

2. *Edge:* Edge is the one which connects floor of the ulcer to the margin. *Different edges are:*
   Sloping edge. It is seen in a healing ulcer.
   Its inner part is *red* because of red, healthy granulation tissue.
   Its outer part is *white* due to scar/fibrous tissue.
   Its middle part is *blue* due to epithelial proliferation.

   Undermined edge is seen in a tuberculous ulcer. Disease process advances in deeper plane (in subcutaneous tissue) whereas (skin) epidermis proliferates inwards.

   Punched out edge is seen in a gummatous (syphilitic) ulcer and trophic ulcer. It is due to end arteritis.

   Raised and beaded edge (pearly white) is seen in a rodent ulcer (BCC). Beads are due to proliferating active cells.

   Everted edge (rolled out edge): It is seen in a carcinomatous ulcer due to spill of the proliferating malignant tissues over the normal skin.
3. *Floor:* It is the one which is seen. Floor may contain discharge, granulation tissue or slough.
4. *Base*: Base is the one on which ulcer rests. It may be bone or soft tissue.

Induration of an Ulcer

Induration is a clinical palpatory sign which means a specific type of hardness in the diseased tissue. It is obvious in well-differentiated carcinomas. It is better felt in squamous cell carcinoma. It is also observed in long standing ulcer with underlying fibrosis. It is absent or less in poorly differentiated carcinomas and malignant melanoma. Less indurated carcinoma is more aggressive. Specific types of indurations are observed in venous diseases and chronic deep venous thrombosis. Brawny induration is a feature of an abscess. Induration is felt at edge, base and surrounding area of an ulcer. Induration at surrounding area signifies the extent of disease (tumour). Outermost part of the indurated area is taken as the point from where clearance of wide excision is planned.

Classification I (Clinical)

1. *Spreading ulcer:* Here edge is inflamed and oedematous.
2. *Healing ulcer:* Edge is sloping with healthy pink/red granulation tissue with serous discharge.
3. *Callous ulcer*: Floor contains pale unhealthy granulation tissue with indurated edge/base. It lasts for many months to years. *Ulcer does not show any tendency to heal.* It is due to callous attitude of the patient.

Classification II (Pathological)

1. *Specific ulcers:*
   - Tuberculous ulcer.



Fig. 1.25: Callous ulcer without any sign of healing, without any granulation tissue. *It is due to callous attitude of the patient.*

- Syphilitic ulcer: It is punched out, deep, with "wash-leather" slough in the floor and with indurated base.
- Actinomycosis.
- Meleney's ulcer.

2. *Malignant ulcers:*
   - Carcinomatous ulcer. (Fig. 1.29); (Fig. 1.30)
   - Rodent ulcer. (Fig. 1.28)
   - Melanotic ulcer.


Sloping edge
Punched out edge
Undermined edge
Raised and beaded edge
Everted edge
Beaded

Fig. 1.26: Ulcer edges.



Figs 1.27A and B: Tuberculous ulcer in chest wall and ankle in two separate patients. Note the undermined edge. Discharge study, biopsy and later antituberculous drugs are the treatment.

3. *Non-specific ulcers:*
   - *Traumatic ulcer*: It may be mechanical, physical, chemical-common.
   - *Arterial ulcer:* Atherosclerosis, TAO. (Fig. 1.31)

The wards are the greatest of all research laboratories.— Sir Henry Wade



Fig. 1.28: Basal cell carcinoma of face (rodent ulcer). Ulcer edge is raised and beaded in appearance.



Fig. 1.29: Squamous cell carcinoma scalp. Note the ulcero-proliferative lesion with everted edge.



Fig. 1.30: Squamous cell carcinoma in the arm with secondaries in the axillary lymph node. Friable tumor tissues in the floor cause bleeding after trauma. Secondaries are fixed with ulceration. It is advanced disease.



Fig. 1.31: Ischaemic ulcer foot. Middle three toes are already amputated because of gangrene.

- *Venous ulcer:* Gravitational ulcer, post-phlebitic ulcer. (Fig. 1.32)



Fig. 1.32: Venous ulcers in both feet. Site is around ankle (Gaiter's zone). There are healthy granulation tissues. It needs skin grafting and definitive procedure for varicose veins after evaluation.



Fig. 1.33: Infective ulcer in the foot. Note the quantity of slough, exposed tendon and gangrenous great toe. Patient might require below knee/above knee amputation.

- *Trophic ulcer/Pressure sore.*
- *Infective ulcers*: Pyogenic ulcer (See Figure 1.33).
- *Tropical ulcers*: It occurs in tropical countries. It is callous type of ulcer, e.g. Vincent's ulcer.
- *Ulcers* due to chilblains and frostbite (*cryopathic ulcer*).
- *Martorell's hypertensive ulcer.*
- *Bazin's ulcer.*
- *Diabetic ulcer.*
- *Ulcers* due to leukaemia, polycythemia, jaundice, collagen diseases, lymphoedema.
- *Cortisol ulcers* are due to long time application of cortisol (steroid) creams to certain skin diseases. These ulcers are callous ulcers last for long time and require excision and skin-grafting.

Wagner's grading/classification of ulcer

Grade 0 – preulcerative lesion/healed ulcer
Grade 1 – superficial ulcer
Grade 2 – ulcer deeper to subcutaneous tissue exposing soft tissues or bone
Grade 3 – abscess formation underneath/osteomyelitis
Grade 4 – gangrene of part of the tissues/limb/foot
Grade 5 – gangrene of entire one area/foot



Fig. 1.34: Non-healing ulcer with pale unhealthy granulation tissue.

GRANULATION TISSUE

It is proliferation of new capillaries and fibroblasts intermingled with red blood cells and white blood cells with thin fibrin cover over it. (See Figs 1.40 and 1.41)



Figs 1.35A and B: Ulcer in the foot, initially with slough; later after slough excision and regular dressings. Area requires skin grafting.



Figs 1.36A to C: Ulcer leg with exposed bone. Patient underwent local rotation flap to cover. Area from where flap is rotated is covered with split skin graft. When the bone is exposed, skin grafting is not possible.

Surgery is a teamwork which divides the task and doubles the success.



Fig. 1.37: Large ulcer in the leg with exposed tendon.



Fig. 1.38: Ulcers with healthy granulation tissue. Ulcer is ready for split skin grafting.



Fig. 1.39: Non-healing ulcer foot in a diabetic patient with *Pseudomonas* infection. Note the greenish discharge in the wound. *Pseudomonas* infection is commonly hospital acquired.

Different discharges in an ulcer (as well as from a sinus)

a. *Serous*: In healing ulcer
b. *Purulent:* In infected ulcer
    Staphylococci: Yellowish and creamy
    Streptococci: Bloody and opalescent
    Pseudomonas: Greenish colour due to pseudocyanin
c. *Bloody:* Malignant ulcer, healing ulcer from healthy granulation tissue
d. *Sero-purulent*
e. *Sero-sanguinous*: Serous and blood
f. *Serous with sulphur granules*: Actinomycosis
g. *Yellowish:* Tuberculous ulcer



Fig. 1.40: Healing ulcer with healthy granulation tissue. Note the sloping edge.



Fig. 1.41: Exuberant granulation tissue (proud flesh) in an ulcer. It should be scooped out using Volkmann's scoop prior to skin grafting.

Types

- ***Healthy granulation tissue***: It occurs in a healing ulcer. It has got sloping edge. It bleeds on touch. It has got serous discharge. 5 Ps of granulation tissue—*Pink, Punctate haemorrhages, Pulseful, Painless, Pin head granulation.* Skin grafting takes up well with healthy granulation tissue. Streptococci growth in culture should be less than 10^5/gram of tissue before skin grafting.
- ***Unhealthy granulation tissue:*** It is pale with purulent discharge. Its floor is covered with slough. Its edge is inflamed and oedematous. It is a spreading ulcer.
- ***Unhealthy, pale, flat granulation tissue***: It is seen in chronic nonhealing ulcer (callous ulcer).
- ***Exuberant granulation tissue (Proud flesh)***: It occurs in a sinus or ulcer wherein granulation tissue protrudes out of the sinus opening or ulcer bed like a proliferating mass. It is commonly associated with a retained foreign body in the sinus cavity.
- Sprouting granulation tissue of sinus.
- ***Pyogenic granuloma***: It is a type of exuberant granulation tissue. Here granulation tissue from an infected wound or ulcer bed protrudes out, presenting as a well-localised, red swelling which bleeds on touching.

Differential diagnosis: Papilloma, skin adnexal tumours.

Treatment: Antibiotics, excision and sent for biopsy.

INVESTIGATIONS FOR AN ULCER

- *Study of discharge*: Culture and sensitivity, AFB study, cytology.
- *Edge biopsy*: Biopsy is taken from the edge because edge contains multiplying cells. Usually two biopsies are taken. Biopsy taken from the centre may be inadequate because of central necrosis.
- X-ray of the part to look for periostitis/osteomyelitis.
- FNAC of the lymph node.
- Chest X-ray, Mantoux test in suspected case of tuberculous ulcer.

Note: Ulcer will not granulate if haemoglobin is less than 10 gm % and serum albumin is < 3 gm%.



Fig. 1.42: X-ray showing osteomyelitis with sequestrum inside. Osteomyelitis prevents ulcer healing. Bone thickening on clinical examination is typical.

Assessment of an Ulcer

- Cause of an ulcer should be found – diabetes/venous/arterial/infective.
- Clinical type should be assessed.
- Assessment of wound is important – anatomical site; size and depth of the wound; edge of the wound; mobility; fixity; induration; surrounding area; local blood supply. Wound perimeter may be useful in assessing this.
- Wound imaging is done by tracing it on a transparent acetate sheet at regular intervals.
- Presence of systemic features; regional nodal status; function of the limb/part; joint movements; distal pulses; sensations should be assessed.
- Severity of infection should be assessed – culture of discharge.
- Specific investigations like edge biopsy; X-ray of part; blood sugar; arterial/venous Doppler; angiogram.

Management of an Ulcer

- Cause should be found and treated
- Correct the deficiencies like anaemia, protein and vitamins deficiencies
- Transfuse blood if required
- Control the pain
- Investigate properly
- Control the infection and give rest to the part
- Care of the ulcer by ***debridement, ulcer cleaning and dressing is done***
- Remove the exuberant granulation tissue
- Topical antibiotics for infected ulcers only like framycetin, silver sulphadiazine, mupirocin
- Antibiotics are not required once healthy granulation tissues are formed
- Once granulates, defect is closed with secondary suturing, skin graft, flaps.

Ulcer cleaning is done using dilute povidone iodine and normal saline. It should be done daily or two times a day depending on the severity.

Debridement of an ulcer

- It is removal of devitalised tissue
- Small ulcers are debrided in ward
- Large ulcers are debrided in operation theatre under general anaesthesia
- All dead, devitalised, necrotic tissues are removed
- Slough should be separated adequately before debridement
- Often devitalised tissue separates on its own by autolysis
- Enzymes like collagenase are used for debridement.

Dressing of an ulcer is done

- To keep ulcer moist
- To keep surrounding skin dry
- To reduce pain
- To soothen the tissue
- To protect the wound
- As an absorbent for the discharge

Conflict is the primary engine of creativity and innovation.—Ranold Heifetz



Fig. 1.43: Ulcer after wound debridement. Adequate wound excision is essential whenever there is slough and necrosis to allow granulation tissue to develop.



Figs 1.44A and B: Solutions commonly used for ulcer dressing – povidone iodine (brownish); EUSOL (colourless); hydrogen peroxide and normal saline. Note the EUSOL bath. Dilute EUSOL solution in a basin is used wherein ulcer foot is dipped and kept in place for 20-30 minutes. EUSOL removes the slough and cleans the ulcer bed. Hydrogen peroxide releases nascent oxygen and helps in removing necrotic material.

Ulcer dressings

- *Cotton dressing*
- *Paraffin dressing*
- *Polyurethane dressings* used in clean wounds
- *Alginates (seaweed) dressing* used when there are heavy exudates
- *Type 1 collagen dressings* cause haemostasis, proliferation of fibroblasts and improve the blood supply
- *Foam dressings* are highly absorbent, decrease the wound maceration, and reduce the frequency of dressing
- *Hydrocolloid dressings* help in separation of slough and autolysis of dead tissues
- *Transparent film dressings* are waterproof, permit oxygen and water vapour across and prevent contamination
- *Hydrogel dressings* used for clean wounds.

Causes of formation of chronic ulcers in the skin

- Recurrent infection
- Trauma
- Absence of rest
- Poor blood supply
- Hypoxia
- Oedema of area
- Loss of sensation
- Malignancy
- Specific cause like tuberculosis
- Fibrosis
- Periostitis or osteomyelitis of the underlying bone

TROPHIC ULCER (PRESSURE SORE)

Pressure sore is tissue necrosis and ulceration due to prolonged pressure. Blood flow to the skin stops once external pressure becomes more than 30 mm Hg (more than capillary occlusive pressure) and this causes tissue hypoxia, necrosis and ulceration. It is more prominent between bony prominence and an external surface.

It is due to

- Impaired nutrition.
- Defective blood supply.
- Neurological deficit.

Sites

- Over the ischial tuberosity.
- Sacrum.
- In the heel.
- In relation to heads of metatarsals.
- Buttocks.
- Over the shoulder.
- Occiput.



Figs 1.45A and B: Trophic ulcers in the heel in two different patients. It often requires rotation flap/transposition flap to cover.



Fig. 1.46: Trophic ulcer.

Due to the presence of neurological deficit, trophic ulcer is also called as *neurogenic ulcer/neuropathic ulcer*. Initially it begins as callosity due to repeated trauma and pressure, under which suppuration occurs and gives way through a central hole which extends down into the deeper plane up to the underlying bone as *perforating ulcer (penetrating ulcer*).

Bedsores are trophic ulcers.

Factors causing pressure sore

- Normal stimulus to relieve the pressure is absent in anaesthetised patient
- Nutritional deficiencies worsens the necrosis
- Inadequate padding over the bony prominences in malnourished patients
- Urinary incontinence in paraplegia patient causes skin soiling – maceration – infection – necrosis

Clinical Features

- Occurs in 5% of all hospitalised patients.
- Painless ulcer which is punched out.
- Ulcer is nonmobile with base formed by bone.



Figs 1.47A and B: Bed sore (decubitus ulcer) over the greater trochanter, ischium and sacrum. Bed sore is a trophic ulcer. It is usually with punched out edge.

Neurological causes

Diabetic neuropathy
Peripheral neuritis
Tabes dorsalis
Spina bifida
Leprosy
Spinal injury
Paraplegia
Peripheral nerve injury
Syringomyelia

Staging of pressure sore

1. Nonblanching erythema – early superficial ulcer
2. Partial thickness skin loss – late superficial ulcer
3. Full thickness skin loss extending into subcutaneous tissue but not through fascia – early deep ulcer
4. Full thickness skin loss with fascia and underlying structures like muscle/tendon/bone, etc – late deep ulcer

To strengthen your heart, forgive yourself and others.

Investigations

Study of discharge, blood sugar, biopsy from the edge, X-ray of the part, X-ray spine.

Treatment

- Cause should be treated.
- Nutritional supplementation.
- Rest, antibiotics, slough excision, regular dressings.
- *Vacuum assisted closure (VAC)* – It is the creation of intermittent negative pressure of minus 125 mm Hg to promote formation of healthy granulation tissue. Negative pressure reduces tissue oedema, clears the interstitial fluid and improves the perfusion, increases the cell proliferation and so promotes the healing. A perforated drain is kept over the foam dressing covered over the pressure sore. It is sealed with a transparent adhesive sheet. Drain is connected to required vacuum apparatus.
- Once ulcer granulates well, flap cover or skin grafting is done.
- Excision of the ulcer and skin grafting.
- Flaps- local rotation or other flaps (transposition flaps).
- Cultured muscle interposition.
- *Proper care* – Change in position once in 2 hours; lifting the limb upwards for 10 seconds once in 10 minutes; nutrition; use of water bed/air bed/air-fluid floatation bed and pressure dispersion cushions to the affected area; urinary and faecal care; hygiene; psychological counseling. Regular skin observation; keeping skin clean and dry (using regular use of talcum powder); oil massaging of the skin and soft tissues using clean, absorbent porous clothing; control and prevention of sepsis helps in the management.

ULCER DUE TO CHILBLAINS

- It is due to exposure to intense cold causing blisters and ulcerations in the feet.
- These ulcers are ***superficial.***
- It is due to excessive cutaneous arteriolar constriction.
- The condition is also called as ***perniosis.***

ULCER DUE TO FROSTBITE

- It is due to exposure of a part to wet cold below the freezing point (cold wind).
- There is arteriolar spasm, denaturation of proteins and cell destruction.
- It leads to gangrene of the part.
- Ulcers here are always ***deep.***

MARTORELLE'S ULCER

- It is seen in *hypertensive* patients often with atherosclerosis.
- It is seen in *calf*. Often it is *bilateral* and *painful*.
- Necrosis of calf skin occurs with sloughing away and formation of deep, punched out ulcers extending into the deep fascia.
- There is sudden obliteration of the arterioles of the calf skin.
- All *peripheral pulses* are present.
- *It takes months to heal.*

  Treatment: Once ulcer granulates well, skin grafting with lumbar sympathectomy is done.



Fig. 1.48: Ischaemic ulcer foot. This ulcer is likely to lead into gangrene and eventual amputation.

BAIRNSDALE ULCER

- It is a chronic, irregular, undermined ulcer due to *Mycobacterium* ulcerans infection.
- Deep severe form, with extensive dermal necrosis is called as ***'Buruli ulcer.'***
- Discharge study will show acid-fast bacilli.
- Antituberculous drugs resolve the ulcer usually. Skin grafting may be required later.



Fig. 1.49: Venous ulcer around the ankle, the commonest site.



Fig. 1.50: Ischaemic ulcer foot with gangrene of toes without evidence of any bleeding with exposed tendons.



Fig. 1.51: Marjolin's ulcer in the leg. It occurs in an instable scar of long duration. It does not spread through lymphatics.



Fig. 1.52: Diabetic ulcer foot.

DIABETIC ULCER

Causes

- Increased glucose in the tissue precipitates infection.
- Diabetic microangiopathy which affects microcirculation.
- Increased glycosylated haemoglobin decreases the oxygen dissociation.
- Increased glycosylated tissue protein decreases the oxygen utilization.
- Diabetic neuropathy involving all sensory, motor and autonomous components.
- Associated atherosclerosis.



Fig. 1.53: Foot is the commonest area for diabetic infective problems. It can cause abscess, ulcer, osteomyelitis, gangrene, septicaemia. Initially patient undergoes toe amputation but later eventually land with below knee or above knee amputation.

Sites

- Foot-plantar aspect—is the commonest site.
- Leg.
- Upper limb, back, scrotum, perineum.
- Diabetic ulcer may be associated with ischaemia.
- Ulcer is usually spreading and deep.

Investigations

- Blood sugar both random and fasting.
- Urine ketone bodies.
- Discharge for culture and sensitivity.
- X-ray of the part to see osteomyelitis.
- Arterial Doppler of the limb.

A man without purpose is like a ship without rudder.

Problems with diabetic ulcer

- Neuropathy, in foot - clawing of toes, hammer toe (due to intrinsic muscle paralysis)
- Multiple deeper abscesses; osteomyelitis of deeper bones are common
- Reduced leukocyte function; resistant infection; spreading cellulitis
- Arterial insufficiency
- Septicaemia; diabetic ketoacidosis
- Associated cardiac diseases like ischaemic heart disease

Treatment

- Control of diabetes using insulin.
- Antibiotics.
- Nutritional supplements.
- Regular cleaning, debridement, dressing.
- Once granulates, the ulcer is covered with skin graft or flap.
- Toe/foot/leg amputation.
- Microcellular rubber (MCR) shoes to prevent injuries; care of foot.

MELENEY'S ULCER (POSTOPERATIVE SYNERGISTIC GANGRENE)

- It is commonly seen in *postoperative wounds* in abdomen and chest wall like empyema drainage or after surgery for peritonitis.
- It is an acute rapidly spreading ulcer with destruction of skin and subcutaneous tissues.



Fig. 1.54: Meleney's ulcer.

Aetiology

- It is common in old age and immunosuppressed individuals and after surgery for infected cases.
- It is caused by microaerophillic streptococci, *Staphylococcus aureus* and anaerobes.

Sites

- It is common in abdomen and thorax. It begins in wound margin and spreads rapidly. It can also occur in other areas of skin.
- Infection is severe, often with endarteritis of the skin leading to ulcer and destruction.

Clinical Features

- Features of toxaemia.
- Spreading painful ulcer with discharge.
- Abundant granulation tissue with purple and red zones.

Management

- Random blood sugar is checked, if diabetic it has to be controlled.
- Antibiotics.
- Blood transfusion, critical care.
- Adequate excision of dead tissues until it bleeds.
- Once healthy granulation tissue is formed skin grafting is done.

LUPUS VULGARIS ('lupus'—wolf)



Figs 1.55A and B: Lupus vulgaris in forearm and thumb. Biopsy confirmed tuberculosis. Patient needs antituberculous drugs. (*Courtesy by Dr Ashfaque DNB, surgeon KMC Mangalore*)

- It is *cutaneous tuberculosis* which occurs in young age group.
- Commonly seen on face, starts as *typical **apple-gelly nodule*** with congestion of skin around. Eventually a superficial ulcer with *undermined edge* is formed.
- The ulcer is active and destruction occurs at the periphery with healing takes place at the centre.
- Often lesion extends into nose and oral cavity involving the mucosa.
- Due to lymphatic obstruction facial oedema can occur.
- Long-standing lupus vulgaris can turn into *squamous cell carcinoma.*

Investigation

ESR, discharge study, biopsy, chest X-ray.

Treatment

1. Antituberculous drugs.
2. If complete healing does not occur, then ***excision and skin grafting*** is required.

BAZIN'S DISEASE (Erythrocyanosis Frigida)

- It is also called as ***Erythema induratum***.
- It is localised area of fat necrosis affecting exclusively adolescent girls.
- Symmetrical purple nodules develop in the ankles and calves which eventually break down forming indolent ulcers with pigmented scars.
- It may be due to tuberculosis.
- Antitubercular drugs and sympathectomy are the treatment.

TROPICAL ULCER

- It is an acute ulcerative lesion of the skin observed in tropical regions like Africa, India and South America. It is associated with lower socioeconomic group, anaemia, malnutrition and vitamin deficiency.
- It is commonly caused by Fusobacterium fusiformis (Vincent's organisms) and Borrelia vincenti.
- There are abrasions, redness, papule and pustule formation, acute regional lymphadenitis and severe pain.
- Eventually it forms a chronic large ulcer.
- Treatment – improvement in nutrition, penicillin, Eusol dressing, skin grafting at a later date.

CLINICAL EXAMINATION OF AN ULCER

History

- Mode of onset
- Duration
- Pain – its time of onset, progress, severity
- Discharge from ulcer
- History suggestive of associated disease / treatment history

Local examination of an ulcer

Inspection

- Site of ulcer – arterial ulcer over the digits; venous ulcer over the malleoli; trophic ulcer over heel / pressure points
- Size of ulcer
- Shape of ulcer
- Number
- Margin whether regular/irregular/well-defined/ill-defined
- Edge of ulcer
- Floor of the ulcer – floor is the one what is seen. It rests on the base. (Base is not seen; it is only felt). Red color in floor – healing ulcer; slough with pale/purulent discharge – nonhealing ulcer or tubercular; wash leather slough – syphilitic ulcer/proliferative and nodular floor – squamous cell carcinoma; pigmented – melanoma, pigmented basal cell carcinoma
- Discharge from ulcer bed – serous, serosanguinous, bloody, purulent; color of discharge – greenish in pseudomonas infection
- Surrounding area to be examined for inflammation, oedema, eczema, scarring, pigmentation
- Inspection of the entire part/limb

Palpation

- Tenderness over edge, base and surrounding area
- Warmness over surrounding area
- Edge palpation for induration
- Palpation of base for induration/fixity
- Depth of ulcer – trophic ulcer is deep with bone as its base – often it is measured gently in mm
- Bleeding on palpation and touching
- Palpation for deeper structuresand its relation to ulcer

When you cease to dream, you cease to live.

- Surrounding skin and tibia/calcaneum/other related bones for thickening
- Examination of adjacent joint for mobility
- Examination of regional lymph nodes is essential – tenderness (acute infection), mobility, consistency may be hard (carcinoma metastasis)/firm/soft and non tender (inflammatory); fixity (malignancy); ulceration or fungation (malignancy); sinus (non specific, tuberculosis or carcinoma)

Specific systems

Examination of arterial pulse, peripherally in relation to ulcer and cardiovascular system for murmur
Examination for varicose veins in standing position
Examination of the abdomen for splenomegaly (sickle cell disease); hepatomegaly
Examination of spine (gibbus, paraspinal spasm, movements) and neurological system like sensation and muscle power

Self-assessment Questions

- Define an ulcer. Classify ulcers clinically as well as pathologically.
- Meleney's ulcer.
- Granulation tissue.
- Pyogenic granuloma.
- Bazin's disease.
- Diabetic ulcer.
- Trophic ulcer.
- Neurogenic ulcer.
- Callous ulcer.

Sinus and Fistula

Sinus
Fistula
Medial mental sinus
Sequestrum

SINUS

It is a blind track lined by granulation tissue leading from an epithelial surface into the surrounding tissues.

Sinus means ***"hollow"*** or ***"a bay" (Latin)***.



Fig. 1.56: Sinus.

Causes

Congenital: Pre-auricular sinus.

Acquired: Actinomycosis, tuberculosis, pilonidal sinus, chronic osteomyelitis, median mental sinus.

FISTULA

It is an abnormal communication between the lumen of one viscus to another or the body surface or between the vessels. Fistula means ***"flute"*** or ***"a pipe*** *or* ***tube***."



Fig. 1.57: Fistula.

Causes

Congenital:

- Branchial fistula.
- Tracheo-oesophageal fistula.
- Congenital AV fistula.
- Umbilical fistula (patent vitello-intestinal duct)

Acquired:

1. Traumatic:
   a. Following surgery—intestinal fistulas (biliary, pancreatic, faecal).
   b. Following instrumental delivery or difficult labour (vesicovaginal fistula, rectovaginal fistula, uretero-vaginal fistula).
2. Inflammatory—intestinal actinomycosis, tuberculosis.
3. Malignancy—when the growth of one organ penetrates into the nearby organ (Rectovesical fistulas as in carcinoma rectum, vesico uterine fistulas as in uterine cancer).

External fistula	*Internal fistula*
• Oro-cutaneous	• Tracheo-oesophageal fistula
• Branchial fistula	• Cholecysto duodenal fistula
• Thyroglossal fistula	• Colovesical fistula
• Enterocutaneous fistula	• Recto-vesical fistula
• Appendicular fistula	

Clinical Features

- Discharge from the opening of sinus.
- No floor.
- Raised indurated edge, indurated base, nonmobile.
- Often *sprouting granulation tissue over the sinus opening.*
- Bone thickening in osteomyelitis.

Causes of persistence of a sinus or fistula:

1. A foreign body or necrotic tissue underneath, e.g. suture, sequestrum
2. Insufficient or non-dependent drainage
3. Persistent obstruction in the lumen, e.g. in faecal fistula, biliary fistula (distal obstruction)
4. Lack of rest, persistent infection
5. Wall become lined with epithelium or endothelium
6. Dense fibrosis prevents contraction and healing
7. Specific infections: Tuberculosis, actinomycosis
8. Presence of malignant disease, post-irradiation

Note: Commonest cause of sinus in neck is tuberculosis. Commonly it is tuberculous lymphadenitis. It shows yellowish cheesy discharge with bluish margin. Usually tuberculous sinus/ulcer do not show any induration.

When a man looses his health he begins to take care of it.— John Billings



Fig. 1.58: Discharging abdominal faecal fistula showing extensive skin excoriation.



Fig. 1.59: Abdominal fecal fistula in a patient who underwent surgery for acute intestinal obstruction due to tuberculosis.



Figs 1.60A and B: Secondaries in neck causing discharging sinus. (A) and (B) in two different patients.



Fig. 1.61: Mandibular sinus. It is usually due to infected tooth causing osteomyelitis of mandible. It also could be due to tumor, trauma, actinomycosis and radiation. X-ray (orthopentamogram), study of discharge and biopsy are relevant investigations. Such fistula should be excised with extraction of the causative tooth.



Fig. 1.62: Discharging sinus in the neck due to tuberculosis of lymph nodes with a cold abscess underneath.



Fig. 1.63: Sinus opening in the thigh. Note there is no floor.



Fig. 1.64: Pilonidal sinus showing primary and secondary sinus.



Fig. 1.65: Fistula in ano both sides.



Fig. 1.66: Postoperative gastro-intestinal fistula. Note the skin excoriation. It can be controlled by using zinc oxide cream local application.

Different discharges in a sinus/fistula

- *Purulent*—bacterial infection
- *Caseous*—tuberculous
- *Sulphur granules*—actinomycosis
- *Mucus*—branchial fistula
- *Saliva*—parotid fistula
- *Faeces*—faecal fistula
- *Bile*—biliary, duodenal fistula
- *Bone*—osteomyelitis sinus
- *Urine* – urinary fistula

Investigations

a. Fistulogram/sinusogram using ultrafluid lipiodol or water soluble iodine dye (Lipiodol is poppy seed oil containing 40% iodine).
b. Discharge for C/S, AFB, cytology, staining.
c. Biopsy from the edge.
d. Chest X-ray.
e. ESR.
f. CT sinusogram.
g. Probing gently with care.
h Digital examination of the rectum and proctoscopy in fistula in ano.

Treatment

- Treat the cause.
- ***Excision*** of sinus or fistulas. Always specimen should be sent for histology.

MEDIAN MENTAL SINUS

It is a chronic infective acquired condition wherein there is infection of roots of one or both lower incisor teeth forming root abscess which eventually tracks down between two halves of lower jaw in the midline presenting as discharging sinus on the point of chin at midline.

Clinical Features

- Usually painless discharging sinus in the midline on the point of chin.
- Often incisor infection may be revealed (in many patients clinically tooth looks normal even though root is infected invariably).
- It is often mistaken for infected sebaceous cyst
- Osteomyelitis of the mandible is the possible complication.

Differential Diagnosis

- Infected sebaceous cyst.
- Tuberculous sinus.
- Osteomyelitis.

> *Be strong enough to face the world each day.*
> *Be weak enough to know you cannot do everything*—Nabil Mourad.



Fig. 1.67: Median mental sinus. Note the origin of the sinus from the root/roots of the lower incisor/incisors.

Investigations

- Dental X-ray is diagnostic. (Plain X-ray mandible may not reveal the disease).
- Discharge study—C/S, cytology, AFB.

Treatment

- Antibiotics, after doing discharge study(C/S).
- Lay opening and excision of the sinus track with *extraction of incisor tooth/teeth*.

SEQUESTRUM

- Sequestrum is dead bone *in situ*.
- It can be pyogenic, tubercular (feathery), salmonella (granular), syphilitic (ivory), tubular and ring (in amputation stump).
- It can be *unformed* – means separation between sequestrum and adjacent normal bone has not occurred or *formed* – means there is proper adequate separation between normal bone and sequestrum by forming granulation tissue. Radiologically formed sequestrum shows clear lucent area/zone of demarcation.
- Sequestrum is denser because of the absence of decalcification in the dead bone as there is no blood supply (dead bone is dense bone).
- Sequestrum should be formed prior to surgical intervention – sequestrectomy and saucerisation.



Fig. 1.68: Diagram showing osteomyelitis with sequestrum and sinus. Sequestrum is dead bone *in situ.*



Figs 1.69A and B: Osteomyelitis patient with scar. Also showing on table photo of sequestrectomy and saucerisation.



Figs 1.70A and B: X-ray pictures showing features of osteomyelitis with sequestrum, sinus, cavity.



Fig. 1.71: X-ray of foot showing osteomyelitis of metatarsal bones. Metatarsal osteomyelitis is commonly seen in diabetes mellitus and trauma.



Fig. 1.72: Osteomyelitis of femur with sequestrum and sinus.

Self-assessment Questions

- Causes for persistence of sinus or fistula.
- Median mental sinus.

The mother's heart is child's schoolroom.—Henry Ward Beecher.

Infectious Diseases

> ***But however secure and well-regulated civilized life may become, bacteria, protozoa, viruses, infected fleas, lice, ticks, mosquitoes, and bedbugs will always lurk in the shadows ready to pounce when neglect, poverty, famine, or war lets down the defenses.***
>
> **—Hans Zinsser,** 1934

Surgical infection
Cellulitis, Erysipelas
Abscess
Boil
Hidradenitis suppurativa
Carbuncle
Pott's puffy tumour
Pyogenic granuloma
Impetigo
Bacteraemia, Septicaemia
Pyaemia
Tetanus
Gas gangrene
Tuberculosis
Leprosy
Syphilis
Actinomycosis
Madura foot
Rabies
Anthrax
Nosocomial and Opportunistic infections
HIV infection and AIDS
Necrotising Fasciitis
Acute Pyomyositis

SURGICAL INFECTION

- Surgical infection is major problem in surgical practice. Asepsis (prevention of entry of organisms) and antisepsis (killing of the bacteria in the skin or tissues) has made a difference in surgical practice. Epithelial surfaces act as mechanical barrier and phagocytes, antibodies; complements, macrophages, leukocytes, opsonins, etc. act as protective mechanisms.
- Malnutrition, diabetes mellitus, obesity, uraemia, jaundice, malignancy, immunosuppression, radiotherapy, chemotherapy, HIV, ischaemia, foreign body, haematoma are the risk factors for surgical infections. Virulence of organisms, blood supply, body immunity and support of antibiotics are the decisive factors in proper response to control infection.
- Surgical infection can be superficial surgical site infection in the wound or deep surgical site infection in deeper fascio – muscular layers or organ space infection like abdomen/thoracic cavity, etc.
- Health care associated infection occurs after hospital admission in intensive unit/postoperative ward, etc.
- *Southampton wound grading system for healing and infection—*
  - Grade 0 is normal healing;
  - Grade 1 is with bruising/mild erythema;
  - Grade 2 is severe erythema with other features of inflammation at or around wound;
  - Grade 3 is serous or bloody discharge;
  - Grade 4 is presence of pus or deep infection or tissue breakdown or significant haematoma.

ASEPSIS wound score system is used to assess the wound infection.

ASEPSIS wound scoring

Parameters	*Score*
• **A**dditional treatment	
1. Antibiotics	10
2. Pus drainage	05
3. Wound debridement	10
• **S**erous discharge – for 5 days of first 7 days of wound infection	0-5 daily
• **E**rythema - for 5 days of first 7 days of wound infection	0-5 daily
• **P**urulent fluid - for 5 days of first 7 days of wound infection	0-10 daily
• **S**eparation of deep tissues - for 5 days of first 7 days of wound infection	0-10 daily
• **I**solation of Bacteria	10
• **S**tay in the hospital (in-patient) more than 14 days due to infection	05

CELLULITIS

- It is ***spreading inflammation*** *of subcutaneous and fascial planes.*
- Infection may follow a small scratch or wound or incision.

Causative Agents

- Commonly due to *Streptococcus pyogenes* and other Gram +ve organisms.

- Often gram –ve organisms like *Klebsiella, Pseudomonas, E. coli* are also involved (usually Gram –ve organisms cause secondary infection).

Sequelae

- Infection can get localized to form ***pyogenic abscess***.
- Infection can spread to cause ***bacteraemia, septicaemia, pyaemia***.
- Often infection can lead to ***local gangrene.***

Clinical Features

- Fever, toxicity (tachycardia, hypotension).
- Swelling is diffuse and spreading in nature.
- Pain and tenderness, red, shiny area with stretched warm skin.
- Cellulitis will progress rapidly in diabetic and immunosuppressed individuals.
- Tender regional lymph nodes may be palpable which signify severity of the infection.

Management

- Elevation of limb or part to reduce oedema so as to increase the circulation
- Antibiotics
- Dressing (often glycerine dressing is used as it reduces the oedema because of its hygroscopic action).
- Bandaging.



Fig. 1.73: Cellulitis face. Note the oedema of the face and eyelids.

Cellulitis in Special Areas

a. *Orbital Cellulitis*

Cellulitis in orbit causes *proptosis,* leading to impairment of ocular movements and blindness. It can spread



Figs 1.74A to E: Note the cellulitis in different patients. It is common in lower limbs. There is no edge without any formed pus. It should never be incised with certain exceptions like Ludwig's angina. It is treated by antibiotics. It can cause bacteraemia/septicaemia.

Oedema gives rise to soft pitting, while if pus present, induration can always be felt.—Allan B. Kanavel through ophthalmic veins into cavernous sinus causing *cavernous sinus thrombosis*. It requires admission and immediate aggressive treatment with higher generation antibiotics (Penicillins, Cephalosporins).



Fig. 1.75: Severe cellulitis face involving nose, eyelids and facial skin. It can cause septicaemia, cavernous sinus thrombosis or intracranial spread of infection. This area is called as dangerous zone in face. It needs hospitalization for treatment.

b. *Ludwig's Angina*

It is cellulitis of upper part of the neck involving submandibular region and floor of the mouth along the fascial planes.

It may be precipitated by tooth extraction, oral cancer, submandibular gland infection, diabetes mellitus, chemotherapy, etc.

Clinical Features

- Diffuse swelling, redness, tenderness and induration in the floor of the mouth and submandibular region.
- Difficulty in opening of the mouth (***Trismus***).
- Toxic features like fever, tachycardia and tachypnoea.
- ***Severe laryngeal oedema*** (presents with respiratory distress, stridor and cyanosis).
- Dysphagia and putrid halitosis.

Complications

- ***Septicaemia.***
- Spread of infection into the parapharyngeal space leads to ***thrombosis*** of internal jugular vein which may extend above into the sigmoid sinus which may be fatal.

Treatment

- Antibiotics.
- Early surgical intervention (decompression) is required. Under G.A, horizontal incision is placed in submandibular region extending on both sides, deepened to include deep fascia. ***Mylohyoid*** muscles on both sides are cut. It releases the tension, preventing laryngeal oedema and so further spread of infection is prevented. Antibiotics should be continued.
- Incised wound is closed by ***secondary suturing*** once infection is controlled completely (not earlier).

ERYSIPELAS

It is a **spreading inflammation** of the skin and subcutaneous tissues due to infection caused by *Streptococcus pyogenes*. There will be always cutaneous lymphangitis with development of ***rose pink rash*** with cutaneous lymphatic oedema. Vesicles which form eventually will rupture to cause serous discharge.



Fig. 1.76: Lymphangitis of the leg. Note the redness and spread. It gets blanched on pressure.



Fig. 1.77: Lymphangitis of one leg. Note the typical streaky redness.

Sites

- Orbit.
- Face.
- Scrotum.
- Umbilicus in infants.

In the face and orbit, it causes severe oedema.

Clinical Features

- ***Toxaemia*** is always a feature.
- ***Rash*** is fast spreading and blanches on pressure.
- ***Rash*** *is raised with sharp margin.*
- ***Discharge*** *is serous. (In cellulitis discharge is purulent.)*
- ***Milian's ear sign*** is a clinical sign used to differentiate erysipelas from cellulitis wherein ear lobule is spared. Skin of ear lobule is adherent to the subcutaneus tissue and so cellulitis cannot occur. Erysipelas being a cutaneous condition can spread into the ear lobule.
- Disease is common in poorly hygienic debilitated individuals.
- Septicaemia, localised cutaneous and subcutaneous gangrene are the dangerous problems.
- Lymphoedema of face and eyelids can occur later due to lymphatic fibrosis.

Treatment is with ***penicillins.***

Erysipeloid disease: Also called as *'Fish handler's disease.'* Occurs following any cuts or scratches. It has features of both erysipelas and cellulitis. It is self-limiting with relatively mild symptoms.

ABSCESS

> ***If you examine a swelling of pus in any limb of a man and you find it (with) its head raised and it is enclosed and it is rounded, you shall say concerning it: "a swelling of pus, an illness which will be treated by me with the knife treatment. There is something in it like mucus. Something comes forth like wax. It makes a pocket. If anything (remains) in its pocket, it recurs."***
>
> — **(Anonymous),** circa 1500 BC

Types

- Pyogenic abscess
- Pyaemic abscess
- Metastatic abscess
- Cold abscess due to chronic infection like tuberculosis

Pyogenic Abscess

It is a ***localized collection*** of pus in a cavity lined by granulation tissue, covered by pyogenic membrane. It contains pus in loculi. Pus contains dead WBC's, multiplying bacteria, toxins and necrotic material.

Protein exudation causes fibrin deposition and formation of pyogenic membrane. Macrophages and polymorphs release lysosomal enzymes which cause liquefaction of tissues leading into pus formation. Toxins and enzymes released causes tissue destruction and pus formation.



Fig. 1.78: Pyogenic abscess—parts.

Mode of infection

- Direct
- Haematogenous
- Lymphatics
- Extension from adjacent tissues

Bacteria causing abscess

- *Staphylococcus aureus.*
- *Streptococcus pyogenes.*
- Gram-negative bacteria (*E. coli*, *Pseudomonas*, *Klebsiella*).
- Anaerobes.



Fig. 1.79: Abscess forehead. Patient is diabetic and has had trauma to the site.



Fig. 1.80: Abscess in the face. Note the localisation and redness.



Fig. 1.81: Abscess in the nape of the neck-suboccipital region. Note the redness and visible pus.

Factors precipitating abscess formation

- General condition of the patient: Nutrition, anaemia, age of the patient
- Associated diseases: Diabetes, HIV, immunosuppression
- Type and virulence of the organisms
- Trauma, haematoma, road traffic accidents

Clinical Features

- Fever often with chills and rigors.
- Localised swelling which is smooth, soft and fluctuant.
- Visible (pointing) pus.
- Throbbing pain and pointing tenderness.
- Brawny induration around.
- Redness and warmth with restricted movement around a joint.

(Commonly cellulitis occurs first which eventually gets localised to form an abscess.)



Figs 1.82A to C: Pyogenic abscess in different locations in chest wall; in plantar aspect of the foot and in the thigh. Note the redness and visible pus.

Visible (pointing) pus, tenderness, fluctuation are the features of formed abscess.

Cellulitis	*Pyogenic abscess*
• Diffused – no edge • Pus not formed – non-suppurative initially • Not fluctuant • Spreading – SIRS can occur • Blood culture may be negative • Never incise; if done danger of bacteraemia, antibiotics, elevation, dressing – are treatment	• Well-localised with clear edge • Formed pus • Fluctuant • Culture of pus is usually positive • Drainage is essential

Sites of Abscess

a. *External Sites*

- Fingers and hand.
- Neck.
- Axilla.
- Breast.
- Foot, thigh—here it is deeply situated with brawny induration.
- Ischiorectal and perianal region.
- Abdominal wall.
- Dental abscess, tonsillar abscess and other abscesses in the oral cavity.



Fig. 1.83: Perineal abscess.

b. *Internal Abscess*

- Abdominal: Subphrenic, pelvic, paracolic, amoebic liver abscess, pyogenic abscess of liver, splenic abscess, pancreatic abscess.
- Perinephric abscess.
- Retroperitoneal abscess.
- Lung abscess.
- Brain abscess.
- Retropharyngeal abscess.

Investigations

- Total count is increased.
- Urine sugar and blood sugar is done to rule out diabetes.
- USG of the part or abdomen or other region is done when required.
- Chest X-ray in case of lung abscess.
- Gallium isotope scan is very useful.
- CT scan or MRI is done in cases of brain and thoracic abscess.
- Investigations, relevant to specific types: Liver function tests, PO_2 and PCO_2 estimation, blood culture.



Fig. 1.84: Abdominal wall abscess. Note the well localized swelling.

Complications of an abscess

- Bacteraemia, septicaemia, and pyaemia.
- Multiple abscess formation.
- Metastatic abscess.
- Destruction of tissues.
- Antibioma formation (common in breast abscess). Once abscess forms, thick fibrous tissue develops around abscess cavity because of antibiotics. Cavity contains sterile pus as thick flaques. It is non tender, localized, smooth, hard swelling which may mimic

Happy is he who has no serious consequences of his erroneous diagnosis to regret—Fredrick H. Marsh

carcinoma (in breast – carcinoma breast). It should be differentiated clinically from carcinoma (it is not progressive whereas carcinoma is progressively increasing). FNAC is essential to differentiate. Antibioma should be excised.
- Sinus and fistula formation.
- Large abscess may erode into adjacent vessels and can cause life threatening torrential haemorrhage, e.g. as in pancreatic abscess.
- Abscess in head and neck region can cause laryngeal oedema, stridor and dysphagia.
- Specific complications of internal abscess:
  - Brain abscess can cause intracranial hypertension, epilepsy, neurological deficit.
  - Liver abscess can cause hepatic failure, rupture, jaundice.
  - Lung abscess can lead to bronchopleural fistula or septicaemia or respiratory failure or ARDS.



Fig. 1.85: Abdominal wall abscess being aspirated. Note the aspirated pus in the syringe. Abscess should be aspirated prior to drainage.



Fig. 1.86: Multiple abscesses in neck, chin, face. It is common in HIV, diabetes and immunosuppressed.

Treatment of an abscess

Abscess should be formed before draining. Exceptions for this rule are:
- Parotid abscess
- Breast abscess
- Axillary abscess
- Thigh abscess
- Ischiorectal abscess



Fig. 1.87: Scrotal abscess, which is well-localised and ready for drainage. Patient has undergone surgery for hernia earlier.

Features of a formed abscess
- Visible pus
- Pointing tenderness
- Fluctuation
- Excruciating pain

Procedure

***Hilton's** method* of draining an abscess.
- Initially broad spectrum antibiotics are started (depending on severity, extent and site of the abscess).
- Under general anaesthesia or regional block anaesthesia,* after cleaning and draping, abscess is aspirated and presence of pus is confirmed.



Fig. 1.88: Incision for draining an abscess by Hilton's method. Note the longitudinal incision.

---

* As the pus is acidic L/A will not act and hence it is not used.

Differences between Pyogenic Abscess and Cold Abscess

Pyogenic abscess	*Cold abscess*
(a) Red, warm, tender, with signs of acute inflammation	(a) No signs of acute inflammation
(b) Pyogenic bacteria are nonspecific organisms *(Streptococcus, Staphylococcus)*	(b) Tuberculous bacteria
(c) For drainage, dependent incision is used	(c) Nondependent incision is used
(d) Suturing of the wound is not done	(d) Wound is sutured
(e) Drain is placed	(e) Drain is not placed (otherwise sinus will form which is difficult to treat)



Fig. 1.89: Cold abscess in the loin region. It does not show any signs of acute inflammation. It should be drained through non-dependent incision and incision should be closed without placing a drain. Prior to drainage antituberculous drugs should be started.



Fig. 1.90: Abscess with loculi and breaking of loculi using finger for drainage.

- Skin is incised adequately, in the line parallel to the neurovascular bundle in the most dependent position.
- Next, pyogenic membrane is opened using ***Sinus forceps**** and all loculi are broken up. Abscess cavity is cleared of pus and washed with saline.
- A **drain** (either gauze drain or corrugated rubber drain) is placed.
- Wound is ***not closed***. Wound is allowed to granulate and heal. Sometimes *secondary suturing* or *skin grafting* is required.
- Pus is sent for ***culture and sensitivity***.
- Antibiotics are continued.
- Treating the ***cause*** is important.

Counter-incision is placed in breast abscess which is placed in upper quadrant.

Incision should be deeper while draining pus in radial and ulnar bursae, palmar spaces and tenosynovitis.

Problems in drainage

- Improper drainage
- Bleeding
- Residual abscess or sinus formation

Differential Diagnosis

- ***Aneurysm:*** Especially in popliteal, femoral and axillary regions. So before draining the abscess, presence of pus is confirmed by aspirating with a needle. It should be remembered that thrombosed aneurysm may not be pulsatile but can be warm, soft and tender.

---

* Sinus forceps do not have lock and has got serrations in the tip. It is called as sinus forceps because it was initially designed and used to pack sinuses.

Joseph Lister is father of modern surgery and started antiseptic surgery in 1912.

- ***Soft tissue tumours:*** Sarcomas may be smooth, soft and warmer.
- Haematoma.

BOIL (Furuncle)

It is an acute staphylococcal infection of a hair follicle with perifolliculitis which usually proceeds to suppuration and central necrosis. Often boil opens on its own and subsides (*S. aureus* infection). Furuncle in external auditary canal is very painful because of rich cutaneous nerves. Here skin is adherent to perichondrium.



Fig. 1.91: Furuncle/boil are infection of hair follicle with perifolliculitis due to staphylococcus aureus.

Treatment

- Antibiotics.
- Drainage of boil.

Complications

- Cellulitis.
- Lymphadenitis.
- Hidradenitis (*Infection of group of hair follicles*).
- Boil in dangerous zone can cause cavernous sinus thrombosis.

HIDRADENITIS SUPPURATIVA

It is a chronic infective and fibrous disease of the skin bearing *apocrine* sweat glands. Apocrine sweat glands are coiled glands which open into the hair follicles.

Sites of apocrine sweat glands:
- Axilla
- Areola
- Umbilicus
- Groin
- Perineum



Fig. 1.92: Hidradenitis suppurativa. It is chronic infection of apocrine sweat glands of the skin. It is common in axilla. (*Courtesy by Dr Achaleshwar Dayal MS KMC Mangalore*)

Aetiology

- Obesity, smoking.
- Poor hygiene.
- Diabetes mellitus.
- Steroids.

Common bacteria involved are staphylococci, streptococci, staphylococcus aureus, propioni-bacterium acnes.

Pathogenesis

Obstruction of duct of apocrine sweat gland by keratin.
↓
Dilatation of the duct of gland.
↓
Infection and abscess formation.
↓
Involvement of subcutaneous tissue and adjacent apocrine glands.
↓
Fibrosis, scarring, sinus formation.
↓
Spread to surrounding tissues.

Clinical Features

- Common in females 4 : 1.
- Commonest site is axilla.
- Multiple discharging sinuses, with nodules in the skin which is tender.
- Induration due to fibrosis.

Investigation

- Discharge study.
- Biopsy.

Differential Diagnosis

- Tuberculous sinus.
- Malignancy (squamous cell carcinoma of skin).

Treatment

- Antibiotics.
- Excision of the involved area widely followed by skin grafting or flaps.
- Excision of the involved area widely followed by skin grafting or flaps (radical wound excision).
- Antiandrogen drugs.

CARBUNCLE

*Word meaning of carbuncle is **charcoal.***

- It is *an infective gangrene of skin and subcutaneous tissue*.
- ***Staphylococcus aureus*** is the main culprit.
- Common site of occurrence is ***nape of the neck and back.***
- It is common in ***diabetics*** and after forty years of age**.**
- It is common in males.

Infection

↓

Development of small vesicles

↓

Sieve like pattern

↓

Red indurated skin with discharging pus

↓

Many fuse together to form a central necrotic ulcer with peripheral fresh vesicle looking like a *"**rosette**"* (cribriform).

↓

Skin becomes black due to blockage of cutaneous vessels

↓

Disease spreads to adjacent skin rapidly.

Patient is ***toxic*** and in diabetics they are ***ketotic.***



Fig. 1.93: Carbuncle in the buttock. Note the vesicles and typical colour.



Fig. 1.94: Carbuncle in the nape of the neck – typical site. Note the wide area of involvement and dark area – charcoal like.

Investigations

- Urine sugar and urine ketone bodies.
- Blood sugar.
- Discharge for C/S.

Treatment

- Control of diabetes is essential using insulin.
- Antibiotics like penicillins, cephalosporins or depending on C/S is given.
- Drainage is done by a cruciate incision and debridement of all dead tissues is done. Excision is done later.
- Once wound granulates well, ***skin grafting*** may be required.

Renal Carbuncle is an entity which occurs in kidney due to infection, forming localized infective mass lesion.

POTT'S PUFFY TUMOUR

- It is a misnomer.
- It is formation of diffuse external swelling in the scalp due to **subperiosteal pus** formation and **scalp oedema**.
- It originates commonly in frontal region and may extend into other regions.
- Often there is acute osteomyelitis of frontal bone.

> *In tuberculus arthritis, starting pain at night is very important, as it attracts more attention than occasional discomfort during the day.*
> — Royal Whitmann



Fig. 1.95: Pott's Puffy tumour. Note the swelling over the frontal region and eyelid.

Causes

- Chronic frontal sinusitis which eventually suppurates and extends into subperiosteal region.
- Trauma – subperiosteal haematoma.
- Chronic suppurative otitis media.

Clinical Features

- Pain and swelling in frontal region which is warm, tender.
- Toxicity and drowsiness.

Complications

- *Osteomyelitis* of frontal bone.
- Spread of infection into intracranial cavity leads to *intracranial abscess* (Extradural or subdural abscess). So may present with features of raised intracranial tension like headache, coning and convulsions.

Investigations

- Total leucocyte count—increased.
- ESR—raised.
- X-ray skull.
- CT scan.

Differential Diagnosis

Secondaries in the skull or brain.

Treatment

- Antibiotics and drainage under general anaesthesia before it spreads into cranial cavity.
- Once it extends into cranial cavity, it is treated accordingly by formal neurosurgical decompression (often using ***Dandy's brain cannula***).
- Osteomyelitis of skull bones requires radical removal with reconstruction of skull defect.

PYOGENIC GRANULOMA (GRANULOMA PYOGENICUM)

- It is a common condition which occurs on the face, scalp, fingers and toes.
- It may be due to minor trauma or minor infection.
- Infection leads to formation of unhealthy granulation tissue which protrudes through the wound.

It is also called as acquired lobular capillary haemangioma.

Clinical Features

- Usually single, well localised, red, firm, nodule, which bleeds on touch.
- May or may not be tender.



Fig. 1.96: Pyogenic granuloma in postauricular region. Differential diagnoses are hamartoma and naevus.



Fig. 1.97: Pyogenic granuloma in the nose. It is due to infected nasal stud.



Fig. 1.98: Pyogenic granuloma scalp. Note the well-localised red swelling.

Sites

- Face
- Scalp
- Fingers
- Toes.

Differential Diagnosis

- Haemangioma.
- Papilloma.
- Skin adnexal tumours.
- In recurrent cases, haemangioendothelioma and melanoma.

Treatment

- Excision, laser surgery.
- Tissue to be sent for histopathological study.

IMPETIGO

- It is highly infectious superficial skin infection caused by staphylococci/streptococci organisms.
- Usually seen in children, with formation of multiple blisters that rupture and coalesce, to cover as honey-coloured crust.
- Treatment is oral antibiotics and topical antiseptics.

SCRUM POX

It is a type of impetigo seen in Rugby players (Staphylococcal infection).

BACTERAEMIA

Presence of bacteria in blood.

SEPTICAEMIA

Presence of overwhelming and multiplying bacteria in blood with toxins causing SIRS (Systemic Inflammatory Response syndrome) or MODS (Multi Organ Dysfunction Syndrome).

Types

a. ***Gram +ve septicaemia*** is due to staphylococci, streptococci, pneumococci, etc. It is common in children, old age, diabetics and after splenectomy. After splenectomy, Overwhelming Post-splenectomy sepsis (OPSI) is not uncommon. Common origin is skin, respiratory infection.

b. ***Gram -ve septicaemia*** is common in acute abdomen like peritonitis, abscess, urinary infections, biliary infections, postoperative sepsis. It is commonly seen in malnutrition, old age, diabetics, immunosuppressed people. Common bacteria are *E. coli*, *Klebsiella*, *Pseudomonas*, *Proteus*. Condition is also called endotoxic shock. Common focus of gram-negative sepsis are urinary infection, abscess or infected wounds, biliary sepsis, postoperative wounds.

Stages of Gram-negative Septicaemia

1. ***Warm stage*** is *reversible stage*. Here existing fever is due to pyrogenic response. Patient is toxic with fever, chills and rigors.
2. ***Cold stage*** is *irreversible stage*. Here fever is not present due to absence of pyrogenic response. Patient is having renal failure, ARDS, liver failure and multi-organ failure.

Investigations

- Urine/pus/discharge culture.
- Blood culture.
- Haematocrit.
- Electrolyte assessment.
- PO_2 and PCO_2 analysis.
- Blood urea, serum creatinine, liver function tests.

Treatment

- Antibiotics like cefoperazone, ceftazidime, cefotaxime, amikacin, tobramycin, metronidazole.
- Fresh blood transfusion.
- Adequate hydration.
- Oxygen supplementation.
- Ventilatory support.
- Electrolyte management.
- Parenteral nutrition (TPN).
- CVP line for monitoring and perfusion.
- FFP or platelets in case of DIC.

> *An external sore may be obvious on external genitalia—hot and tender in gonorrhea and chancroid, painless and indolent in syphilis.*
> — Angus E.W. McLachlam

Complications of septicaemia

- Disseminated intravascular coagulation (DIC)
- ARDS
- Liver dysfunction
- Renal failure
- Bone marrow suppression—thrombocytopenia
- Multiorgan failure

PYAEMIA

Presence of multiplying bacteria in blood as emboli which spread and lodge in different organs in the body like liver, lungs, kidneys, spleen, brain causing ***pyaemic abscess.*** This may lead to ***Multi Organ Dysfunction Syndrome (MODS***). It may endanger life if not treated properly.

Clinical features

- Fever with chills and rigors
- Jaundice, oliguria, drowsiness
- Hypotension, peripheral circulatory collapse and later coma with MODS

Common Causes

- Urinary infection *(most common).*
- Biliary tract infection.
- Lower respiratory tract infection.
- Abdominal sepsis of any cause.
- Sepsis in diabetics and immunosuppressed individuals like HIV, steroid therapy.

Investigations

- Total leucocyte count.
- Pus culture.
- Blood culture.
- Urine culture.
- Blood urea and serum creatinine.
- LFT.

Treatment

- Monitoring of vital parameters.
- Antibiotics, (ceftazidime, cefoperazone, ceftriaxone sodium).
- IV fluids, maintenance of urine output.
- Hydrocortisone.
- Blood and plasma transfusion.
- Nasal oxygen, ventilator support, monitoring of pulmonary function.

Metastatic Abscess and Pyaemic Abscess

Metastatic abscess is an abscess which occurs as a spread from other abscess. For example, lung abscess causing metastatic abscess in the brain (common example). Presentation here is of features of focus abscess and of metastatic abscess (localised features).

Pyaemic abscess is from any infective focus which need not be always from an abscess (from cellulitis or skin infections etc) causing pyaemic emboli leading into multiple abscess in different places like brain, kidneys, liver etc. Presentation here, is mainly of systemic features involving multiple organs with toxicity.

TETANUS

> ***It is painful for him to open his mouth. His heart beats too slowly (or weakly) for speech. You observe his saliva falling from his lips, but not falling completely.... He suffers stiffness in his neck. He does not find he can look at his two shoulders and his breast.***
>
> **—(Anonymous),** Circa 1500 BC

It is an infective condition caused by *Clostridium tetani* organisms leading to reflex muscle spasm, often associated with tonic clonic convulsions.

Organism

- ***Clostridium tetani*** is a *gram-positive, anaerobic, motile, noncapsulated,* organism with *peritrichous flagella*, and ***terminal spores*** *(Drum stick appearance)*.
- Spore is the infective agent. They are found in soil, manure, dust.
- Spore can gain entry through any wound, pricks, injuries resulting from road traffic accidents, penetrating injuries.

Pathogenesis


Spore
Enters the wound
It germinates in anaerobic media releasing bacteria, which multiply
Release of *Exotoxins*
Tetanospasmin
Tetanolysin
Through the perineural sheath
Circulation
Haemolysis.
Enters the central nervous system Blocks cholinesterase enzymes at anterior horn cells
Toxaemia (through blood) Blocks the NMJ (neuro muscular junction) by acting on cholinesterase enzyme
Causing hyperexcitability and reflex spasm of muscles often with *tonic, clonic convulsions*
Aggravates the muscle spasm.
Once toxin is fixed in nerve tissue, it can no longer be neutralised by antitoxin.

Clinical Features

Symptoms

- Jaw stiffness, pain and stiffness in the neck and back muscles
- Anxiousness, sweating
- Headache, delirium, sleeplessness
- Dysphagia
- Dyspnoea

Signs

- ***Trismus***, due to spasm of masseter and pterygoids.
- ***Risus sardonicus*** (smiling facies), due to spasm of the facial muscle-zygomaticus major. Looks as if patient is smiling.
- Neck rigidity.
- Spasm and rigidity of all muscles.
- Hyperreflexia.
- Respiratory changes—due to laryngeal muscle spasm, infection, aspiration.
- ***Tonic clonic convulsions***.
- Abdominal wall rigidity often with haematoma formation.
- Severe convulsion may often lead to fractures, joint dislocations and tendon ruptures.
- Fever and tachycardia.
- Retention of urine (due to spasm of urinary sphincter), constipation (due to rectal spasm).



Fig. 1.99: Different types of postures seen in tetanus.

- Rarely features of ***carditis*** are seen due to involvement of the cardiac muscle, which is dangerous, as it often leads to cardiac arrest and death. Here ***steroids*** are very useful.
- Symptoms will be aggravated by stimuli like light, noise.

Incubation Period

- Time between the ***entry of spore and appearance of first symptom***.
- Usually 7-10 days.
- Shorter the incubation period worser the prognosis and more severe the course of disease.

Period of Onset

- *Time between appearence of first symptom and appearance of first sign.*
- Shorter the period of onset worser the prognosis and vice versa.

Effects on Respiratory System

Diaphragm and other muscles of respiration undergo spasm causing tachypnoea, respiratory distress, respiratory infections, aspiration, cyanosis, respiratory failure with altered PO_2 and PCO_2 levels.

Types of Tetanus

- ***Early tetanus***: It is a severe form with a short incubation period and poor prognosis.
- ***Latent tetanus***: Wound is healed and forgotten. After a long incubation period, may be years later, under favourable environment, spores release bacteria and cause tetanus. It carries better prognosis.
- ***Late tetanus***: Disease develops many months after injury.
- ***Ascending tetanus:*** Symptoms and signs progress from below upwards.
- ***Descending tetanus***: Symptoms and signs progress from above downwards.
- ***Cephalic tetanus:*** Facial muscles are involved first (3rd, 4th, 6th and 7th cranial nerves can get involved).
- ***Localised tetanus.***
- ***Bulbar tetanus***: When muscles of deglutition and respiration are involved. Highly fatal.
- ***Tetanus neonatorum*** (7th day tetanus): Tetanus occurring in neonates. Spread is through umbilical cord.
- ***Urban tetanus***. Due to repeated injections in IV drug abusers.
- ***Postoperative tetanus*** due to improper sterilisation.

> *Even if you're on the right track, you'll get runover if you just sit there.* — Arthur Godfrey

Different Postures in Tetanus

- ***Opisthotonus**:* Posterior muscles are acting more, so *backward bending*.
- ***Orthotonus***: *Straight posture*. Both front and back muscles are acting equally.
- ***Emprosthotonus:*** *Forward bending* as front muscles are acting more.
- ***Pleurosthotonus***: *Lateral bending* as lateral muscles act more.

Complications of tetanus

- Fracture bones
- Haematoma
- Aspiration pneumonia, respiratory failure, ARDS
- Carditis
- DVT, pulmonary embolism
- Toxaemia
- Secondary infection- septicaemia
- Bed sore. Malnutrition, stress gastric ulcers.

Staging of Tetanus

- ***Mildly ill**:* Rigidity, spasm, trismus and different postures.
- ***Seriously ill***: Spasm, rigidity, severe respiratory infections.
- ***Dangerously ill:*** Cyanosis with ***respiratory failure*** and tonic-clonic convulsions.

Differential Diagnosis

- Strychnine poisoning (here patient is normal in between).
- Trismus due to other causes like—dental, oral, tonsillar sepsis, oral malignancy.
- Meningitis.
- *Hydrophobia.*
- Convulsive disorders.

Culture media for clostridium tetani are RCM (Robertson's cooked meat) media and nutrient agar.

Cause of death in tetanus

- Respiratory failure with aspiration pneumonia and ARDS
- Severe carditis—an ominous sign
- Mortality is 45-50%

Treatment

- Patient is admitted and isolated in a dark, quiet room
- Antitetanus globulin (ATG), 3,000 units IM single dose is given. Test dose is not required. (It is a human Ig.)
- Antitetanus serum (ATS): When ATG is not available or when patient cannot afford, after ***IV test dose*** (1,000 units of ATS), full dose is given, i.e. 1,00,000 units, half of it is given IM and half of it is given IV. It is a horse serum, so possibility of anaphylactic reactions should be borne in mind.
- Wound debridement, drainage of pus, injection of ATG 250-500 units locally to reduce the toxin effect.
- Ryle's tube has to be passed, initially to decompress, so as to prevent aspiration, but later for feeding purpose.
- Catheterisation.
- IV fluids and electrolyte balance has to be maintained. TPN is also required.
- ***Tetanus toxoid*** should be given as disease will not give immunity against further infections. To start—first dose, second dose after one month, third dose after six months.
- IV *diazepam* 20 mg 4th or 6th hourly. Dose is adjusted depending on severity and convulsions.
- IV *Phenobarbitone* 30 mg 6th hourly.
- IV *Chlorpromazine* 25 mg 6th hourly.
- Injection crystalline penicillin 20 lacs 6th hourly and inj. Gentamicin and metronidazole to prevent secondary infection.
- Regular suction and clearance of respiratory tract.
- Nasal oxygen.
- In ***severe cases***, patient is ***curarised*** and placed in ***ventilator (IPPR).***
- ***Endotracheal intubation*** or ***tracheostomy*** are often ***life-saving procedures***
- ***Good nursing care***—Change of position, prevention of bedsores, prevention of DVT (which is common in tetanus and often requires heparin injection).
- Chest (respiratory) physiotherapy during recovery period.
- ***Steroids*** are given when carditis is suspected.

Following treatment patient often gets spasm of different muscles (**tics**) for a long period which can be prevented by giving methocarbamol for 6 months to one year.

General measures

- Isolation
- Avoid noise and light
- ATG 3,000 units IM
- ATS-50,000 IM and 50,000 IV—After test dose
- Antibiotics like inj penicillin 20 lacs 6th hourly
- Inj tetanus toxoid 0.5 ml IM - to deltoid muscle
- IV fluids with TPN
- Urinary catheterisation
- Nasogastric tube is passed to prevent aspiration initially, later for feeding
- Regular suction of throat
- Nasal oxygen when required

- Prevention of bedsore formation
- Prevention of DVT by low molecular weight heparin
- Good nursing care

Specific measures

- IV diazepam 20 mg 6th hourly
- IV phenobarbitone 30 mg 6th hourly
- IV chorpromazine 25 mg 6th hourly
- Endotracheal intubation and ventilator support
- Tracheostomy if there is severe respiratory secretions
- Steroids
- Bronchodilators like deriphylline
- Wound care- debridement, drainage, and local injection of ATG

Prophylaxis against tetanus

- In adults, fresh immunisation to start—second in one month, next in 6 months period. Tetanus toxoid 0.5 ml IM
- In infants—Triple antigen (DPT)—6 weeks, 10 weeks, 14 weeks, 18 months, and 5 years
- To pregnant mother tetanus toxoid injections are given in 4th and 6th months of pregnancy
- Additional booster dose given in major injuries or high-risk injuries
- ATG 500-1000 units IM given as a prophylaxis in road accidents, severe burns, crush injuries, war wounds. Here tetanus toxoid also should be given separately at separate site IM

Monitoring during therapy

PCO_2, PO_2, haemotocrit, blood urea, serum electrolytes, chest X-ray, ECG are done at regular intervals.

GAS GANGRENE

It is an infective gangrene caused by clostridial organisms involving mainly skeletal muscle. Earlier it was called as ***malignant oedema***.

Organisms

- Clostridium welchii (perfringens): Gram-positive, central spore bearing, nonmotile, capsulated organisms.
- Clostridium oedematiens.
- Clostridium septicum.
- Clostridium histolyticus.

Clostridium welchii produce toxins—
- Alpha (commonest)
- Beta
- Epsilon
- Iota
- *Phi toxin* – myocardial depressant
- *Kappa toxin* – destruction of connective tissue and blood vessels

Various *strains* include—A, B, C, D, E.
'A' strain is commonest.

Note: Non clostridial gas producing organisms like coliforms can also cause gas gangrene.

Exotoxins

- ***Lecithinase*** is important toxin which is haemolytic, membranolytic and necrotic causing ***extensive myositis***.
- ***Haemolysin*** causes extensive haemolysis.
- ***Hyaluronidase*** helps in rapid spread of gas gangrene.
- ***Proteinase*** causes breaking down of proteins in an infected tissue.

Spores enter through the devitalized tissues commonly in road traffic accidents, crush injury.
↓
Spores germinate
↓
Released bacteria will multiply
↓
Exotoxins are released
cause their effects.

Effects

- Extensive necrosis of muscle with production of gas (hydrogen sulphide; nitrogen; carbon dioxide) which stains the muscle brown or black.
- Usually muscle is involved from origin to insertion.
- Often may extend into thoracic and abdominal muscles.
- When it affects the liver it causes necrosis with frothy blood—***foaming liver***, is characteristic.

Clinical Features

Incubation period is 1-2 days.

- Features of toxaemia, fever, tachycardia, pallor.
- Wound is under tension with foul smelling discharge (sickly sweety odour).
- Khaki brown coloured skin due to haemolysis.
- ***Crepitus*** can be felt.
- Jaundice may be *ominous sign* and also oliguria *signifies renal failure*.

Ancients discovered much, and yet left much more to be discovered.

Clostridium welchii can infect limbs, abdominal wall, appendix, gallbladder, common bile duct, intestine, uterus (during septic abortion).

Clinical Types

- ***Fulminant type*** causes rapid progress and often death due to toxaemia, renal failure or liver failure or MODS or ARDS.
- ***Massive type*** involving whole of one limb containing fully dark coloured gas filled areas.
- ***Group type:*** Infection of one group of muscles, extensors of thigh, flexors of leg.
- ***Single muscle type*** affecting one single muscle.
- ***Subcutaneous type*** of gas gangrene involves only subcutaneous tissue (i.e. superficial involvement).



Fig. 1.100: Gas gangrene in upper limb. It is after effect of an assault using an axe by a drunken husband.



Fig. 1.101: Gas gangrene involving entire leg extensively. Note the black/ khaki coloured area. Patient died of toxaemia.

Investigations

- X-ray shows gas in muscle plane or under the skin.
- Liver function tests, blood urea, serum creatinine, total count, PO_2, PCO_2.
- CT scan of the part may be useful especially in chest or abdominal wounds.

Prevention of gas gangrene

- Proper debridement of devitalised crushed wounds
- Devitalised wounds should not be sutured.
- Adequate cleaning of the wounds with H_2O_2 and normal saline.
- Penicillin as prophylactic antibiotic.

Treatment

- Inj. Benzyl penicillin 20 lacs 4th hourly. + Inj. metronidazole 500 mg 8th hourly + Inj. aminoglycosides (if blood urea is normal) or third generation cephalosporins.
- ***Fresh blood transfusion****.*
- ***Polyvalent antiserum*** 25,000 units given intravenously after a test dose and repeated after 6 hours.
- ***Hyperbaric oxygen*** is very useful.
- Liberal incisions are given. All dead tissues are ***excised*** and **debridement** is done until healthy tissue bleeds.
- Rehydration and maintaining optimum urine output (30 ml/hour) (0.5 ml/kg/hour).
- Electrolyte management.
- In severe cases ***amputation*** has to be done as a ***life-saving procedure*** - stump should never be closed.
- Often ventilator support is required.
- *Once a ward or operation theatre is used for a patient with gas gangrene, it should be fumigated for 24-48 hours properly to prevent the risk of spread of infection to other patients especially with open wounds.*
- Hypotension in gas gangrene is treated with whole blood transfusion.

TUBERCULOSIS

> ***Whilst meagre Pthisis gives a silent bow, Her strokes are sure, but her advances slow. No loud alarms, nor fierce assaults are shown: She starves the fortress first, then takes the town.***
>
> —**Samuel Garth**, 1699

- It is commonly caused by *Mycobacterium tuberculosis;* occasionally by *Mycobacterium bovis, M. kansasii, M. fortuitum, M. marinum, M. ulcerans.*
- *M. Tuberculosis* is ***gram neutral, acid fast, alcohol fast*** straight or slightly curved rods.
- It is prevalent in most of the developing countries and has made its resurgence in the developed countries with the advent of AIDS.

Pathogenesis

- The characteristic lesion here is '*tubercle*', which is an avascular granuloma composed of a central zone containing giant cells, with or without caseation necrosis, surrounded by a rim of epithelioid cells, lymphocytes and fibroblasts.
- It can occur in almost all organs in the body. Presentation may vary depending on the individual sites.



Fig. 1.102: Tuberculous lymphadenitis with tuberculous ulcer.

General Features

- Low grade fever with evening rise of temperature.
- Loss of appetite.
- Decreased weight.

Investigations

- ESR is often raised; peripheral smear—Lymphocytosis.
- AFB (Acid fast bacillus) staining using Ziehl-Neelsen stain.
- Chest X-ray is done to rule out pulmonary tuberculosis.
- Culture of the organism in Lowenstein Jenson media.
- Mantoux skin test—read after 48 hr of inoculation.
- Guinea-pig inoculation.
- Relevant investigations depending on the site of the tuberculosis.

Treatment

- Anti-tuberculous drugs are given for 6 months to one year.
- Specific treatment is given depending on the site of the tuberculosis.

(Please refer individual chapters for details about tuberculosis at different locations and also chapter drugs for Antituberculous therapy.)

LEPROSY

- It is caused by *Mycobacterium leprae.* It is a gram-positive, acid fast bacillus.
- It mainly involves skin, nasal mucosa and peripheral neural tissues.
- It involves only the cooler parts of the body. (So axilla, gluteal region are not involved.) Testicular involvement is seen but not the ovary. It does not involve the vital organs. Though not acutely fatal, the disease leaves the victim severely deformed and crippled for life.



Figs 1.103A to D: A leprosy patient with the typical face (leonine); skin patches; hand deformities and trophic changes; trophic ulcer in heel.

Right is right even if everyone is against it, and wrong is wrong even if everyone is for it.

Types

a. *Multibacillary Types*

- ***Lepromatous leprosy***: Denotes little or no host resistance. Bacilli are seen in large numbers in the superficial nodular lesions and the patient is highly infective.
- ***Borderline lepromatous.***
- ***Borderline.***

b. *Paucibacillary Types*

- ***Borderline tuberculoid.***
- ***Tuberculoid leprosy***: Here strong host resistance is observed. The disease is more localised, but it causes more deformities due to early involvement of nerves. Bacilli are scanty in the lesion and so infectivity is minimal.

Investigations

- Regular checking of sensation of the suspected area.
- Split skin smear.
- Nerve biopsy.

Treatment

- Dapsone 100 mg daily.
- Rifampicin 600 mg once a month.
- Clofazimine 50 mg daily + 300 mg once a month.

For paucibacillary types, treatment is for 6 months.
For multibacillary types, treatment is for 2 yr or more.

Surgical Complications in Leprosy

a. *Primary Deformities*

- Leonine facies.
- Collapsed nasal bridge.
- Upper branch facial nerve palsy (causes lagophthalmous).
- Keratitis and blindness.
- Claw hand either ulnar or combined ulnar and median nerves.
- Radial nerve palsy—wrist drop (1%).
- Clawing of toes due to involvement of posterior tibial nerve.
- Foot drop due to involvement of lateral popliteal nerve.
  (Medial popliteal nerve which supplies the tibialis posterior is never involved.)

b. *Secondary Deformities*

- Anaesthesia of the part makes it prone to trauma, infection, infective gangrene, destruction, autoamputation and functionless parts.
- Trophic ulcers in the foot are common.

Treatment

- Reconstructive surgeries.
- Release of contractures.
- Tendon transfers.
- Arthrodesis.
- Ulcer management.
- Physiotherapy and rehabilitation.

SYPHILIS (GREAT POX) (French Disease)

> ***It is concluded…that this disease which amongst the Italians is called Gallicus, that is to say, the French disease, should now be named Patursa, …a disease filthie and Saturnall. It is a filthie disease, because it maketh women to be esteemed unchast and irreligious…. There is a twofold kinde of causes…. The first is the only influence or corruption of the aire, from whence we must charitably thinke, that it infected those which were religious. The second is conversation, as by kissing and sucking, as appeareth in children, or by carnall copulation.***
>
> **—Juan Almenor,** 1502

It is a venereal infection caused by *Treponema pallidum.*

Early syphilis: It lasts for 2 years and the patient is infective during this period.

Primary syphilis: It presents as a *Hunterian chancre* (Hard chancre). It is a shallow, painless, indurated, non-bleeding ulcer usually seen in the genitalia and often on the lips, breasts and anal region. It occurs in 3-4 weeks after the infection. It is confirmed by dark field microscopic study of the discharge for the organism.

Secondary syphilis: It occurs in 6-12 weeks.
It presents as

- Cutaneous coppery rashes.
- Snail-track oral ulcers.
- Condyloma lata: raised, flat, white lesions seen at the mucocutaneous junctions (mouth, anus vulva).
- Painless, shotty lymphadenopathy-epitrochlear suboccipital.
- Moth-eaten alopecia.
- Hepatitis, arthritis, iritis.
- Syphilitic osteitis with "ivory" sequestrum.
- Meningitis.

Latent syphilis: It lasts between 2 years to lifetime. Serum tests are positive.

***Late (tertiary) syphilis*:**

- Painless, punched out, *gummatous ulcers* are seen with *"wash leather base" and silvery tissue paper scar.*

- It is seen over the tibia, sternum, ulna, skull, scrotum.
- It is a hypersensitivity reaction occurs as a result vasculitis and obliterative endarteritis.
- *Neurosyphilis.*
- *Cardiovascular syphilis*–aneurysm of arch of aorta.

Investigations

- VDRL test; Kahn test.
- Treponema pallidum haemagglutination test (TPHA).
- Treponema pallidum immobilisation test (TPI).

Treatment

Penicillin for 15 days is the drug of choice.

Doxycycline 100 mg can be given thrice daily for 15 days.

Others: Erythromycin, tetracycline, cephalosporins.

Jarisch-Herxheimer reaction is commonly seen after penicillin, which often requires steroid therapy.

CONGENITAL SYPHILIS

Here the infection is transmitted from the mother to foetus through placenta.

Early congenital syphilis: It is seen in newborn.

Features are:
Rash, syphilitic snuffles
Nasal discharge, weight loss
Periostitis, meningitis, hepatosplenomegaly
Pneumonia alba

Late congenital syphilis:

- *Hutchinson's triad:*
  - *Interstitial keratitis*
  - *8th nerve deafness*
  - *Hutchinson's teeth: Peg shaped upper incisors Moon's molar, molars with cusps*
- Congenital neurosyphilis
- Cutaneous, skeletal or visceral gummas
- Saddle nose
- Sabre tibia, Clutton's joint
- Perforated palate

Congenital syphilis is treated with penicillins.



Fig. 1.104: Saddle nose.

ACTINOMYCOSIS

- It is caused by ***Actinomyces israelii***.
- It is an anaerobic gram-positive ***fungal like bacterium***, which is a branching filamentous organism. It is called as ***"Ray fungus"*** because of ***sun-ray*** appearance.

Clinical Types

- **Facio-cervical**: It is the commonest type. Infection spreads either from tonsil or from adjacent infected tooth. Initially an induration develops. Nodules form with involvement of skin of face and neck. It softens and bursts through the skin as ***sinuses*** which discharge *pus which contains sulphur granules* (60%).
- **Thorax**: Lungs and pleura get infected by direct spread from pharynx or by aspiration. Empyema develops. Later chest wall nodules appear leading to sinuses with discharge (20%).
- In right iliac fossa. It presents as a ***mass abdomen*** with discharging sinus.
- **Liver** is infected through portal vein (Honey Comb liver).

Pathogenesis

Organism enters through deeper plane of the tissue, causes subacute inflammation with induration and nodule formation. Eventually discharging sinus forms at the surface. Pus collected in a swab or sterile tube will show sulphur granules.

Clinical Features

- ***Discharging sinus*** with induration and nodules.

Life is like a mirror. If you smile at it, it also smiles at you.

- *No lymph nodal involvement*.
- Through blood spread it may cause pyaemia and endanger life.

Investigations

- Pus under microscopy shows branching filaments.
- ***Gram's staining*** shows ***gram-positive mycelia*** in centre with ***gram-negative radiating peripheral filaments***. These clubs are due to host reaction which are lipoid material (antigen – antibody complex).
- Cultured in brain heart infusion agar and Thioglycolate media.

Differential Diagnosis

- Chronic pyogenic osteomyelitis.
- Carcinomas at the site.
- Tuberculous disease.

Treatment

- Penicillins for longer period (6-12 weeks).
- Tetracyclines, lincomycin, streptomycin.
- Dapsone and iodides may be useful.
- Antifungals are often given because it is fungal like bacterium.
- Surgical debridement is occasionally required.

MADURA FOOT (MYCETOMA PEDIS)

- It is a chronic granulomatous condition of the foot causing multiple discharging sinuses in the foot.
- It was first identified in ***Madurai, Tamil Nadu (India)*** *by* ***Gill***.
- It is common in India and Africa.
- It is common in Tamil Nadu.

Organisms

- ***Nocardia madurae*** (commonest)
- *Nocardia brasiliensis*
- *Nocardia asteroides*
- *Actinomyces israelii*

Pathogenesis

Organism enters through a prick in the foot usually who walks barefoot
↓
Reaches deeper plane in the foot
↓
Evokes chronic granulomatous inflammation
↓
Causes pale, painless, firm nodule
↓
Formation of vesicles
↓
Burst to form a discharging sinuses.

- Discharging granules may be *Black, Red, Yellow*.
- In black type of Madura foot, infection is mainly subcutaneous.
- In red and yellow types, it burrows into the deeper plane including bone causing bone necrosis (osteomyelitis). Eventually gross swelling of the limb with multiple discharging sinuses with disability will occur.
- Muscles and bones are involved.
- Tendons and nerves are affected.
- **Regional lymph nodes are not involved.**
- Condition will deteriorate by secondary bacterial infection.

Clinical Features

- Painless diffuse swelling in the foot of long duration.
- Later multiple discharging sinuses develop on the skin.
- Lymph node involvement will not occur unless secondary bacterial infection is present.
- Significant limb disability is common.



Fig. 1.105: Madura foot. Note the multiple sinuses.



Figs 1.106A and B: Mycetoma thigh and foot in two different patients. Note the discharging sinuses.

Differential diagnosis

- Chronic osteomyelitis
- Tuberculous osteomyelitis
- Carcinoma

Investigations

- Discharge study will show branching filamentous appearance of the organism.
- Culture in Sabouroud's dextrose agar medium.
- Gram stain for actinomycosis will show sun-ray appearance with gram +ve centre and gram –ve clubs.
- X-ray of the foot is done to look for osteomyelitis.

Treatment

- Antifungal drugs—amphotericin.
- Long term penicillins.
- Dapsone.
- Iodides.
- In severe cases amputation may be required.

If infection occurs in the hand it is called as ***Madura hand***.

RABIES (Hydrophobia)

It is an acute fatal encephalomyelitis caused by *Lyssavirus type 1*.

- It is rare in developed countries. It is common in developing countries. It is common in India.
- Only country where rabies is not seen is *Maldives*.

Pathogenesis

- It commonly occurs following dog bite. Other animals which often can cause rabies are cat, jackal, wolf, bat, mongoose, monkey, horse, sheep, goat.
- Transmission is through saliva of the animals. It is commonly through bite or lick.
- Asymptomatic carrier stage can occur in animals but they are unlikely to be infective during carrier stage.
- It is considered that only symptomatic animals are infective.
- Street virus of Lyssavirus type 1 is the infective one. (Fixed virus is noninfective and is used for vaccine.)
- Virus passes through the peripheral nerves into the central nervous system and develops ***Negri bodies*** in the brain leading to ***fatal encephalomyelitis.***
- It also involves the salivary glands to get secreted in the saliva to cause infection.

Clinical Features

- Incubation period is 3-6 weeks.
- Prodromal symptoms like fever, headache.
- Hyperexcitability and irritability.
- Hydrophobia (fear of water).
- Aerophobia (fear of air).
- Mental instability.
- Once disease starts, patient dies within 72 hours.

Fear of water is seen only in affected human beings not in animals.

Prophylaxis

Postexposure Prophylaxis

1. Cleaning of the wound initially with running water and soap for 5 minutes and later with povidone iodine or alcohol (40-70%).
2. Suturing of the wound should not be done. Because suturing will cause faster spread of virus into the deeper plane.
3. Local application of antirabies serum into the wound as early as possible is effective in reducing the infection rate.
4. Antibiotics.
5. The dog is observed for 10 days. If dog shows symptoms, then antirabies vaccine is advised.
6. Vaccination.
7. Antirabies serum.

Classification of Wounds

Class I: Lick over intact skin or scratches without oozing of blood.

Class II: Licks on broken skin, scratches with blood ooze, all bites except over head, face, palms and fingers.

Minor wounds less than five in number.

Class III: All bites over head, face, palms and fingers. Lacerated wounds, wounds more than five in number, wild animal bites.

Indications for Antirabies Vaccination

- All rabid animal bites.
- If animal is killed or dies during 10 days of observation period.
- Bite by an unidentified animal.
- If lab tests in animal show positive for rabies.
- All wild animal bites.

Vaccines for Rabies

1. **BPL inactivated vaccine**: It is nervous tissue vaccine.

It is 5% emulsion of the infected brain of the sheep containing the inactivated fixed virus.

> *The best rose bush is not the one with the fewest thorns, but that which bears the finest roses.*
> — Jerry Van Dyke

Dosage: (as recommended by Pasteur Institute, Coonoor)

	Adult	Children	
Class I	2 ml	1 ml	7 days
Class II	3 ml	3 ml	10 days
Class III	5 ml	3 ml	10 days

Mode of administration: Into the abdominal wall subcutaneously using long needle.

Antibody develops in 7-30 days. Protection lasts only for 6 months.

Booster doses are given when used along with antirabies serum.

Side effects

Headache, palpitation, allergic reactions.

Redness, tenderness and swelling at the site of the vaccination.

Post-vaccinal neuroparalysis—a dangerous life-threatening complication.

During therapy, patient *should avoid alcohol and steroids.*



Fig. 1.107: Sites of ARV injections.

2. **Nervous tissue vaccine** derived from suckling mouse brain.
3. **Duck embryo vaccine** (DEV) has got less neuroparalytic side effects. It is not available in India.
4. **Cell culture vaccines**: They are more potent and safer.
    a. *Human diploid cell vaccine* (HDCV): Safest vaccine. But it is costly. It is available in India.
    b. *Second generation tissue culture vaccines*: They are potent and cost effective. They are derived from nonhuman base sources. Examples are chick embryo fibroblast, foetal bovine kidney, hamster kidney cells, vero cells.

Dosage: 2.5 IU in one ml. One ml is injected IM into the deltoid on 0, 3, 7, 14, 28 and 90 (optional) days.

Side effects: Headache, redness at the site, fever. No other serious side effects.

Second generation tissue culture vaccine can also be given intradermally. Intradermal dose is one-fifth of the intramuscular dose (0.1 ml).

PASSIVE IMMUNITY

It is used in all severe exposures and in all exposure to wild animal bites.

Types

a. ***Horse antirabies serum (ARS):*** It is given on first day with a dose of 40 IU/kg body weight (maximum up to 3000 units). Half is given into the wound and another half is given into the gluteal muscle (IM). Single dose. Maximum up to 3000 units.
b. ***Human rabies immunoglobulin*** (HRIG): Dose is 20 units/kg body weight. Part is injected into the wound remaining part into the muscle (IM). Single dose. Maximum up to 1500 units.

Patient should be immunised actively along with serum with additional booster doses.

Side effects: Serum sickness, anaphylaxis.

Pre-exposure prophylaxis is given to veterinarians, animal handlers.

Dose: 1 ml of cell culture vaccine IM or 0.1 ml intradermally on 0, 7, 28 days.

Booster doses are given once in every 2 years.

Postexposure vaccination is given if individual has been vaccinated earlier: Doses at 0, 3 and 7 are given. Passive immunity is not given in individuals who had vaccination earlier.

RABIES IN DOGS

Incubation period: 10 days to 8 weeks.

Types

Furious type: Here dogs are aggressive.

Dumb type. Dog is paralytic and sleepy.

Once symptoms of rabies develop in a dog *it rarely survives more than a week.*

Dog brain is sent for study in 50% glycerol-saline solution.

Lab tests to confirm rabies in dogs/animals:

- Fluorescent antibody test (FRA test): It is a reliable test.
- Microscopy examination of the brain of the infected dead animal to look for NEGRI bodies.

- Mouse inoculation test is very sensitive test.
- Corneal test is simpler but negative result does not rule out the infection possibility.

Immunisation in animals:

1. BPL inactivated nervous tissue vaccine: Single dose, 5 ml to dogs; 3 ml to cats. Second dose after 6 months. Then once a year regularly.
2. Modified live virus vaccine: Dose: 3 ml single dose which is repeated once in 3 years.

Control of stray dogs and immunisation of all dogs will reduce the incidence of rabies.

ANTHRAX

- It is caused by *Bacillus anthracis*, which is a *gram positive,* aerobic, spore forming, capsulated, non-motile, nonacid-fast bacillus and is *resistant to heat and antiseptics*.
- Disease is common in cattle and seen in people who handle carcasses, wool, hairs.
- It is often used in *biological war.*

Types

1. **Cutaneous type** (Hide porter's disease)
   - It is the commonest type and occurs within 3-4 days after infection.
   - Indurated papule with black slough surrounded by vesicles—***malignant pustule.*** Itching is common in papule.
   - Regional lymph nodes are involved.
   - ***Toxaemia*** is common.
2. **Respiratory type** (Wool Sorter's disease) is due to inhalation of spores, causing ***pneumonia***. It is more dangerous and life-threatening.
3. **Alimentary type** due to ingestion of spores.

Diagnosis

- Culture of fluid will show ***Medusa head appearance.***
- It shows positive M'Fadyean's reaction and positive Ascoli's thermoprecipitation test.

Treatment

- ***Penicillins.***
- Ciprofloxacin.
- Scalvo's serum prepared by active immunisation of asses.

NOSOCOMIAL AND OPPORTUNISTIC INFECTIONS

NOSOCOMIAL INFECTION (Hospital Acquired Infection)

It is an infection acquired because of *hospital stay.*

Sources

- Contaminated infected wounds.
- Urinary tract infections.
- Respiratory tract infections.
- Opportunistic infections.
- Abdominal wounds with severe sepsis.

Spread can occur from one patient to another, through nurses or hospital staff who fail to practice strict asepsis.

It is **more common** in

- Diabetics
- Immunosuppressed individuals
- Patients on steroid therapy and life-supporting machines
- Instrumentations (indwelling catheter, IV cannula, tracheostomy tube)
- Patients with artificial prosthesis

Organisms

- *Staphylococcus aureus* is the commonest organism causing hospital acquired wound infection. Others are *Pseudomonas, Klebsiella, E. coli, Proteus.*
- *Streptococcus pneumoniae, Haemophilus*, Herpes, *Varicella, Aspergillus, Pneumocystis carinii* are the commonest pathogens involved in hospital acquired respiratory tract infection which spreads through droplets.
- *Klebsiella* is the commonest pathogen involved in hospital acquired UTI which is highly resistant to drugs.

Management

Most of the time, organisms involved are *multidrug resistant, virulent* and hence, cause *severe sepsis*.

- Antibiotics.
- Isolation.
- Blood, urine, pus for culture and sensitivity to isolate the organisms.
- Blood transfusion, plasma or albumin therapy.
- Ventilator support.

Your life is not a coincidence but it's a reflection of you.

- Maintaining optimum urine output.
- Nutritional support.

Prevention

- Isolation of patients with badly infected open wounds, severe RTI/UTI.
- Following strict aseptic measures in OT and in ward by hospital attendants.
- Proper cleaning and use of disinfectant lotions and sprays for bedpans, toilets and floor.
- The precipitating causes has to be treated, along with caring for proper nutrition and improving the anaemic status by blood transfusion.

OPPORTUNISTIC INFECTIONS

They are normally of *low pathogenicity*, occur through therapeutic invasive procedures and are common in immune deficiency status.

Immune deficiency may be due to

- Diabetes
- HIV
- Steroid therapy
- Radiotherapy
- Immunosuppressive therapy in transplantation
- Cytotoxic chemotherapy
- Starvation and old age

Therapeutic invasive procedures may be in the form of IV cannula, bladder catheter, tracheostomy and other minor surgical procedures which permit the skin organisms like *staphylococcus epidermidis* to penetrate the skin and invade the deeper tissues.

Organisms

Bacteria: *Gram-negative: E. coli, Pseudomonas, Klebsiella, Proteus, Serratia.*

Gram-positive: *Staphylococcus epidermidis, Streptococcus pneumoniae.*

Viruses: *Herpes, CMV, Varicella zoster*, may cause fatal pneumonia.

Fungal: *Candida, Aspergillus*, yeast.

Protozoal: *Cryptosporidia* (causes diarrhoea), *Pneumocystis carinii.*

Because of the poor defence mechanism, infection is severe and often life-threatening.

Investigations

- Swab culture.
- Blood culture.
- Pus culture.

Treatment

- These infections are difficult to treat as they are often *multi drug resistant.*
- Combination of broad spectrum antibiotics—cephalosporins, aminoglycosides, metronidazole are given.
- Depending on culture and sensitivity appropriate antibiotics are given.
- Often ventilatory support and critical care are necessary.

HIV INFECTION AND AIDS (Acquired Immunodeficiency Syndrome)

> ***Even if I'd made no money, even if it was the pariah of specialties by virtue of its lack of procedures, an unexpected fringe benefit had become evident with the appearance of AIDS: In those early days, dealing with AIDS made us an elite group, an unexpectedly glamourous group. Even the cardiac surgeons could not approach our kind of heroism. Yes, they dealt with death every day. But it was somebody else's death they had to worry about. Never their own.***
>
> **—Abraham Verghese,** 1994.

History

- 1983: Discovery of the virus
- First case of AIDS detected in UK
- 1984: Development of an antibody test

Definition of AIDS

Confirmed HIV infection with CD_4 T lymphocyte count $< 0.2 \times 10^6/l$ with symptoms.

Human Immunodeficiency Virus

It was discovered by *Barre-Sinoussi and Montagnier in 1983.*

Types

It is classified under HTLV Type III. HIV is subdivided into Type 1 and Type 2.

They are *retroviruses*.

Clinical Classification of HIV Infection

I: Acute infection
II: Asymptomatic but positive HIV
III: Persistent generalised lymphadenopathy
IV: AIDS (HIV related diseases)
  a. Constitutional diseases like weight loss, fever, diarrhoea
  b. Neurological diseases, dementia, neuropathy, myelopathy
  c. Opportunistic infections
  d. Malignancies. Kaposi's sarcoma, non-Hodgkin's lymphomas, primary cerebral lymphomas
  e. Other diseases attributable to HIV infection

Mode of Transmission

- Sexual intercourse—Vaginal or anal.
- Needle pricks—Using unsterilised needles for injections, in IV drug abusers, careless handling.
- Mother to child—During birth through vaginal secretion, trans-placental, through breast milk.
- Blood transfusions, organ transplantations.

Disease is common in Africa and Asian countries. HIV mainly harbours in semen, genital secretions, blood, pus, sputum, saliva and other body fluids.

Anti-HIV antibody

- It appears about 3 weeks to 3 months after exposure
- It always indicates infection
- It has got weak neutralising capacity
- It persists throughout the HIV infection

Tests for HIV

1. ELISA test (**screening test**).
2. Western blot test (**diagnostic test**).
3. Polymerase Chain Reaction (PCR).
4. Anti-HIV antibody detection.
5. *Viraemia quantification*—to start treatment and to see the response of antiviral drugs (useful if it is within 0.5 log 10).
6. *CD$_{4+}$ count*

- Normal value > 500/mm^3.
- Values between 200-500/mm^3 is seen in Kaposi sarcoma, *Candida* infection, *Mycobacterium tuberculosis.*
- Values between 50-200/mm^3 is seen in *Pneumocystis carinii* and *Toxoplasma* infections.
- Values < 50/mm^3 is seen in atypical mycobacteria, cytomegalo virus, lymphomas.



Fig. 1.108: HIV patient presented with tuberculous cold abscess with discharging sinus.


CLASSIC
AIDS KIT
A) STERI DOWN - POLY - 1 PC
B) MASK AND CAP SET - 1 SET
C) SHOE COVER - POLY - 1 SET
RETAIL PRICE RS. 244·30
ALL TAXES EXTRA
Manufactured by
CLASSIC LAB
A
B

Figs 1.109A and B: Picture showing HIV kit and wearing of the HIV kit as a precaution while doing surgery for HIV infected individuals.



Fig. 1.110: Severe infection of ear cartilage in a HIV infected patient.

Live your life as an exclamation not an explanation.

After HIV infection, there is a time gap for the patient to become reactive to tests. This time gap is called as *"Window period"*. This period is variable. But during this period, the individual is infective.

Pathogenesis

Envelope glycoprotein of HIV binds with the surface molecule CD_4 of 'T' lymphocytes, monocytes, macrophages, cutaneous Langerhan's cells, dendritic cells of all tissues.

CD_4 of lymphocytes—T helper cells induce and control the normal immune response.

HIV suppresses immune response completely directly by suppressing 'T' cell, indirectly by suppressing 'B' cell. Finally it dismantles and destroys the immune system making the individual prone to opportunistic infections.



After HIV infection, antibodies develop to virus envelope and core proteins which persists throughout life.

General Features in HIV

- Weight loss more than 10%.
- Fever more than 1 month.
- Diarrhoea more than 1 month.
- Neuralgia, arthralgia, headache.
- Lymphadenopathy.
- Cutaneous rashes, dermatitis, fungal (*Candida*), bacterial, viral (herpes simplex 1 and 2) infection.
- Dental infection, gingivitis, candidiasis of oral cavity and oesophagus.
- Varicella zoster infection.
- Opportunistic infections.
- Poor healing after surgery, trauma, infection with more complications.

Tumours in HIV Infection

- Kaposi's sarcoma—40% common.
- Lymphomas (NHL common) (3-4%).
- Cervical cancer.
- CNS lymphomas.
- Ano-genital squamous cell carcinoma.
- Testicular tumours (Germ cell types).
- Lung cancer.
- GIT lymphomas and adenocarcinomas.
- Squamous cell carcinoma of anal canal and cervix.

Pulmonary Problems in HIV Infection

- Pneumonia.
- Tuberculosis.
- Fungal infections.
- *Pneumocystis carinii pneumonia.*
- Cytomegalovirus pneumonia.



Fig. 1.111: Kaposi's sarcoma.

GIT Problems in HIV Infection

- GIT infections—bacterial, protozoal, viral.
- Kaposi's sarcoma, lymphomas, adenocarcinomas.
- Hepatitis ('C' virus), cholestasis.
- Anorectal diseases.
- Abdominal tuberculosis.

Neurological Problems in HIV Infection

- Encephalitis, aseptic meningitis, myelitis.
- Neuropathies with demyelination.
- Opportunistic infections like *Toxoplasma, Cryptococcus* causing severe meningitis.
- Primary CNS lymphomas.
- CNS tuberculosis (Tuberculomas).
- Visual problems.

MANAGEMENT

Investigations

- Tests for HIV.
- Tests for specific and opportunistic infections.
- Tests relevant for associated tumours.

Treatment

1. Antiviral therapy:
   - *Nucleoside reverse transcriptase inhibitor (NRTI):* zidovudine, didanosine, abacavir, lamivudine, stavudine.
   - *Non-nucleoside reverse transcriptase inhibitor (NNRTI)*: Nevirapine, delavirdine.
   - *Protease inhibitors*: Ritonavir, indinavir, amprenavir.
2. Treatment of **opportunistic infections**.
3. Treatment of **tumours.**
4. Immunotherapy:
   - Alpha and gamma interferons.
   - Interleukins.
5. Bone marrow transplantation.
6. Anti-CD$_3$ or IL-2 after **HAART** (**H**ighly **A**ctive **A**nti-**R**etroviral **T**herapy).
7. ***Psychotherapy***.
8. Counselling of HIV patients and their families.
9. Life expectancy after initial HIV infection is 8-10 years.

Prevention

Continues to be our best weapon in combating the menace of HIV infection.

- Safe sex.
- Condom usage reduces the risk of transmission.
- Health education.
- Use of disposable needles to prevent infections.

Universal precautions against HIV

- Care in handling sharp objects like needles, blades.
- All cuts and abrasions in an HIV patient should be covered with a waterproof dressing
- Minimal parenteral injections
- Equipments and areas which are contaminated with secretions should be wiped with sodium hypochlorite solution or 2% glutaraldehyde
- Contaminated gloves, cottons should be incinerated
- Equipments should be disinfected with glutaraldehyde
- Disposable equipments (drapes, scalpels etc) should be used whenever possible
- Walls and floor should be cleaned properly with soap water
- Separate operation theatre and staff to do surgeries to HIV patients is justifiable
- Avoid shaving whenever possible before surgery in HIV patients
- All people inside the theatre should wear disposable gowns, plastic aprons, goggles, overshoes and gloves
- Surgeons, assistants and scrub nurse should wear in addition double gloves
- Suction bottle should be half-filled with freshly prepared glutaraldehyde solution
- Spilled body fluids should be diluted with glutaraldehyde
- Accidental puncture area in surgeon or scrub nurse should be immediately washed with soap and water thoroughly
- Theatre should be fumigated after surgery to HIV patient

HIV, Hospital and Surgeon

- Isolation per se of HIV patient is not required.
- Proper care should be taken to prevent transmission of the virus.
- Open wounds, disposal of excreta, fluids, discharge, pus and other infective materials should be taken care of properly.
- Risk of HIV infection through needle prick is very less (0.03%).

Following measures should be taken while managing HIV patients:

- Wearing double gloves.
- Wearing proper spectacles (as HIV can get transmitted through eyes directly).
- Wearing proper head mask, theatre shoes, apron.
- Measures to prevent spread of infection from patient to patient in the hospital.
- Disposal of needles through a sharp disposing container.

Disinfection

- Autoclave is ideal.
- Boiling.
- Sodium hypochlorite solution.
- 2% Glutaraldehyde solution.

NECROTISING FASCIITIS

- It is spreading inflammation of the skin, deep fascia and soft tissues with extensive destruction, toxaemia commonly due to *Streptococcus pyogenes* infection, but

The fragrance always remains in the hand that gives the rose.

often due to mixed infections like anaerobes, coliforms, gram-negative organisms.
- It is common in old age, smoking, diabetics, immunosuppressed, malnourished, obesity, steroid therapy and HIV patients. Trauma is a common precipitating factor/cause – 80%.
- It can occur in limbs, lower abdomen (Meleney's infection), groin, perineum. There is acute inflammatory response, oedema, extensive necrosis and cutaneous microvasculature thrombosis.
- Muscle is usually not involved in necrotising fasciitis.



Figs 1.112A to C: Necrotising fasciitis of skin, deep fascia and soft tissues without involvement of muscle.



Fig. 1.113: Fournier's gangrene. Note the destruction of skin over penis, scrotum and lower abdominal wall.

Types

Type I—It is due to mixed infection.

Type II—It is due to *Streptococcus pyogenes*, usually due to minor trauma like abrasions.

Clinical Features

- Sudden swelling and pain in the part with oedema, discoloration, necrotic areas, ulceration.
- Foul smelled discharge.
- Features of toxaemia with high-grade fever and chills, hypotension.
- Oliguria often with acute renal failure due to acute tubular necrosis.
- Jaundice.
- Rapid spread in short period (in few hours).
- Features of SIRS, MODS with drowsy, ill-patient.
- Condition if not treated properly may be life threatening.

Management

- IV fluids, fresh blood transfusion.
- Antibiotics depend on C/S or broad-spectrum antibiotics. High dose penicillins are very effective. Clindamycin, third generation cephalosporins, aminoglycosides are also often needed.
- Catheterisation and monitoring of hourly urine output.



Figs 1.114A to C: The typical necrotizing fasciitis showing gangrenous skin. In second photo, arm is extensively involved. Also note the granulating area after extensive wound excision of the necrotic skin (debridement).

- Haematocrit, serum creatinine assessment.
- Pus culture, blood culture.
- Electrolyte management and monitoring.
- Control of diabetes, if patient is diabetic
- Oxygen, ventilator support, dopamine, dobutamine supplements whenever required.
- Radical wound excision of gangrenous skin and necrosed tissues at repeated intervals.

Necrotising fasciitis

- 80% are polymicrobial – *streptococci, staphylococci, E coli, pseudomonas, proteus, clostridium*
- It is a surgical emergency condition as it is very rapidly progressive
- Lower limb is the commonest site – 60%
- Oedema beyond erythema, woody hard texture on palpation
- Crepitus with subcutaneous emphysema, skin vesicles, dish water pus with grayish discharge are common
- Lymphangitis is usually absent
- Pink/orange skin stain and later focal skin gangrene
- Shock, multiorgan failure
- Resuscitation, wound excision, antibiotics, critical care (oxygen, intubation, ventilator) is needed
- Hyperbaric oxygen given in high pressure chamber with 100% oxygen in 2-3 atmospheric pressure reduces the mortality to 10-20%. It is bactericidal and promotes the neutrophil function
- In spite of adequate therapy mortality is 30 - 50% or more

- Vacuum assisted dressing is better.
- Once patient recovers and healthy granulation tissue appears, spilt skin grafting is done. As it commonly involves large area, mesh graft (meshing of SSG) is needed.

ACUTE PYOMYOSITIS

- It is infection and suppuration with destruction of the skeletal muscle, commonly due to *Staphylococcus aureus* and *Streptococcus pyogenes*, occasionally due to gram-negative organisms.
- It is common in muscles of thigh, gluteal region, shoulder and arm.
- Precipitating factors are similar to necrotising fasciitis.
- Creatine phosphokinase will be very high and signifies acute phase.
- Renal failure is common.
- MRI is useful.
- Treatment is antibiotics, wound excision and compartment release often with haemodialysis.

A successful team beats with one heart.

Self-assessment Questions

- Pyogenic abscess.
- Cold abscess.
- Hilton’s method of drainage.
- Opportunistic infection.
- Nosocomial infection.
- Carbuncle.
- Anthrax.
- Tetanus.
- Gas gangrene.
- Congenital syphilis.
- Surgical complications of leprosy.
- HIV and surgeon.
- Universal precautions.
- Cellulitis.
- Erysipelas.
- Pott’s Puffy tumour.
- Ludwig’s angina.
- Parapharyngeal abscess.
- Actinomycosis.
- Madura foot.
- Necrotising fasciitis.

Swellings

Lipoma
Cysts
Dermoids
Sebaceous cyst
Glomus tumour
Papilloma
Fibroma
Bursae
Semimembranosus bursa
Morrant Baker's cyst
Lymph cyst
Calcinosis cutis
Neuroma
Neurofibroma
Neurilemmoma
Ganglion
Chordoma
Epignathus

LIPOMA

- It is a benign tumour arising from yellow fat.
- Tumour arising from brown fat is called as ***hibernoma (reddish brown).***
- It is called as ***universal tumour*** (ubiquitous tumour) as it can occur anywhere in the body (except in brain).
- It is the ***commonest benign tumour (Karyotype 12q change)***.
- It can be ***diffused*** or ***localised***.
- Diffuse lipomas are not encapsulated, not well localised. Common in palm, sole, head and neck region, difficult to be removed. It is seen in subcutaneous and intermuscular tissues.
- It can be *single or multiple (5%)*. Multiple lipomas often associated with many syndromes like ***MEN syndrome*** *(Multiple endocrine neoplasia syndrome).*

Types

- Painful lipomas are called as ***neurolipomas.***
- ***Dercum's disease*** is tender deposition of fat especially on the trunk, is also called as ***adiposis dolorosa****. It is basically multiple neurolipomatosis.*
- *Fibrolipoma*–Lipoma with fibrous component.
- *Naevolipoma*–Lipoma with telangiectasis.
- *Lipoma arborigens* is pedunculated lipoma.

Lipomas attain large size in thigh, shoulder, retroperitoneum, back and often may turn into sarcoma.

Sites

1. Subcutaneous.
2. Subfascial.
3. Intramuscular.
4. Intermuscular in anterior abdominal wall.
5. Parosteal.
6. Subserosal.
7. Submucosal (GI tract).
8. Extradural (not intradural).
9. Intra-articular.
10. Subsynovial.
11. Superiosteal.

Clinical Features

- Localised swelling, which is lobular, nontender.
- Semifluctuant (because fat in body temperature remains in semiliquid condition).



Figs 1.115A and B: "Lovely" lipoma.

Eyes that look are common; eyes that see are rare.— J. Oswald Sanders



Fig. 1.116A: Pedunculated lipoma.

- Mobile, with edges slipping between the palpating fingers ('slip sign').
- Skin is free.
- Lipomas may be pedunculated at times.



Fig. 1.116B: Pedunculated lipoma. It often mimics papilloma.



Fig. 1.116C: Slip sign of lipoma.



Fig. 1.117: Large lipoma in the back over scapula.



Fig. 1.118: Pedunculated lipoma with ulceration.



Fig. 1.119: Lipoma in lateral chest wall near posterior axillary fold.

Differential Diagnosis

- Neurofibroma,
- Cystic swellings.

Note: FNAC/incision biopsy in suspected cases and CT scan in cases of deeply located/intracavitary lipomas/ large lipomas is done.



Fig. 1.120: Submuscular lipoma under Gastrocnemius muscle.

- Application of ice over the swelling hardens lipoma but not neurofibroma.

Complications

- Sarcomatous changes—liposarcoma (Commonest type of sarcoma).
- Myxomatous changes.
- Saponification.
- Calcification.
- Submucosal lipoma can cause intussusception and so intestinal obstruction.

Liposarcoma

- Common in retroperitoneum, thigh and back
- Rapid growth
- Warm and vascular
- Dilated veins over the surface
- Infiltration in to deeper plane with restriction of the mobility
- Skin fixation and fungation
- Blood spread to lungs.

Treatment

- Excision.
- Small lipoma is excised under local anaesthesia and larger one under general anaesthesia.
- If it is liposarcoma, CT chest should be done to see secondaries in lungs. Later wide excision is done alongwith adjuvant chemotherapy and radiotherapy.

Note: *Lipoblastoma*, a benign tumour is seen in infant boys in extremity subcutaneous tissue.

CYSTS

Cyst is a collection of fluid in a sac lined by epithelium or endothelium. **Word meaning of cyst is** *"bladder"*. **(Greek).**



Figs 1.121A and B: Gross feature of specimen of lipoma.

True Cyst

- Cyst wall is lined by epithelium or endothelium.
- If infection occurs cyst wall will be lined by granulation tissue.
- Fluid is usually serous or mucoid derived from the secretion of the lining.

False Cyst

- It does not have epithelial lining.
- Fluid collection occurs as a result of exudation or degeneration.

Example:

1. Pseudocyst of pancreas.
2. Wall of cystic swelling in tuberculous peritonitis.
3. Cystic degeneration of tumour.
4. After haemorrhage, in a haematoma, RBC's are lysed, gets absorbed and fluid remains as a false cyst.

"Apoplectic cyst" is formed in brain as a result of ischaemia, causing collection of fluid.

> *There can be no substitute for detailed appraisal of the history of clinical signs.*— Harold Ellis

Classification

a. *Congenital cyst*
  - Dermoids: Sequestration dermoid.
  - Tubulodermoids: Thyroglossal cyst, postanal dermoid, ependymal cyst, urachal cyst.
  - Cysts of embryonic remnants: Cysts from paramesonephric duct and mesonephric duct, cysts of urachus and vitellointestinal duct.

b. *Acquired cysts*
  - *Retention cysts*: They are accumulation of secretions of a gland due to obstruction of the duct, e.g. sebaceous cyst, Bartholin's cyst, cyst of parotid, breast, epididymis.
  - *Distention cyst:* Lymph cyst, ovarian cyst, colloid goiter.
  - *Exudation cyst:* Bursa, hydrocele.

c. *Cystic tumours*: Dermoid cyst of ovary, cystadenomas.

d. *Traumatic cyst*: Due to trauma, haematoma occurs usually in thigh, loin, shin. It eventually gets lined by endothelium containing brown coloured fluid with cholesterol crystals.

e. *Degenerative cyst*: Due to cystic degeneration of a solid tumour (due to necrosis of tumour).

f. *Parasitic cyst*: Hydatid cyst, trichiniasis, cysticercosis.

Clinical Features of a Cyst

- Hemispherical swelling which is smooth, fluctuant, nontender, well-localised. Some cysts are transilluminant. Presentation varies depending on its anatomical location.

Effects of a Cyst

- Compression of adjacent structures: Choledochal cyst compressing over the CBD.
- Infection.
- Sinus formation.
- Haemorrhage.
- Torsion, e.g. ovarian cyst.
- Calcification.
- Cachexia: In malignant ovarian cyst patient goes for severe cachexia.

Swellings which are brilliantly transilluminant:
- Ranula
- Cystic hygroma and lymph cyst
- Hydrocele
- Epididymal cyst (Chinese-lantern pattern)
- Meningocele

DERMOIDS

Types

1. *Sequestration Dermoids*

It occurs at the line of embryonic fusion, due to inclusion of epithelium beneath the surface which later gets sequestered forming a cystic swelling in the deeper plane.

Common sites are:
1. Forehead, neck, post auricular dermoid.
2. External angular dermoid.
3. Root of nose.
4. Sublingual dermoid.
5. Anywhere in midline or in the line of fusion.

Dermoids occurring in the skull may extend into the cranial cavity. When it occurs as external angular dermoid, it extends into the orbital cavity. Or it can extend into any cavity in relation to its anatomical location (e.g. thorax, abdomen).



Fig. 1.122: Types of angular dermoid (A) External angular dermoid, (B) Internal angular dermoid (Midline dermoid).

Dermoid cyst contains putty like desquamated material, hair follicle, sebaceous and sweat glands. It is lined by both dermal and epidermal components.

Types of angular dermoid

a. ***External angular dermoid:*** It is a sequestration dermoid situated over the external angular process of the frontal bone. Outer extremity of the eyebrow extends over some part of the swelling. This typical feature differentiates it from the swelling arising from the lacrimal gland. It may extend into the orbital cavity also (Fronto zygomatic suture). (Figs 1.22A; 1.24)

b. ***Internal angular dermoid:*** It is a sequestration dermoid cyst in central position near the root of the nose. It occurs in fronto nasal suture line. It is rare. (Fig. 1.22B)

Clinical features

- Painless swelling in the line of embryonic fusion.
- Presents in the second or third decade onwards.
- Smooth, soft, nontender, fluctuant (*Paget's test positive* i.e. swelling is fixed with two fingers and summit is indented to get yielding sensation due to fluid).
- Nontransilluminating.
- Free skin, often adherent into the deeper plane.
- There will be ***resorption and indentation*** of the bone beneath.
- Impulse on coughing may be present only if there is intracranial extension.

Differential diagnosis

- Sebaceous cyst.
- Lipoma.

Investigations

- X-ray—skull or part.
- CT scan head or part.

Complication of sequestration dermoid

- Infection
- Haemorrhage, rupture
- Surface ulceration
- Pressure effects if there is intracavitary extension like into cranial cavity or thoracic cavity, etc
- Calcification

Treatment

- Excision is done under general anaesthesia. Often formal neurosurgical approach is required by raising cranial osteocutaneous flaps.



Figs 1.123A and B: Postauricular dermoid.



Fig. 1.124: External angular dermoid, right sided.

Count your blessing not your problems.



Fig. 1.125: Dermoid in the ear. It arises due to sequestration at the fusion line of the one of the six developmental ear tubercles. (Each ear develops from SIX ear tubercles).

Submental dermoid

- It is a congenital sequestration dermoid occurs during fusion of 1st and 2nd branchial arches. It is deep to deep fascia of neck.
- It presents as soft, cystic, fluctuant, nontransilluminating, swelling in midline in submental region which does not move with deglutition nor moves while protruding the tongue out.
- It should be differentiated from thyroglossal cyst, cold abscess from submental lymph nodes or sebaceous cyst.
- It is excised under general anaesthesia with a curvilinear submental incision.

2. *Tubulodermoids*

It arises from the embryonic tubular structures. Examples include

- Thyroglossal cyst.
- Ependymal cyst.
- Postanal dermoid.

3. *Implantation Dermoid*

- Due to minor pricks or trauma, epidermis gets buried into the deeper subcutaneous tissue which causes reaction and cyst formation (Trauma is forgotten often). It is an acquired cyst.
- It is common in fingers (common in tailors, gardeners), toes and feet.

Clinical features (Figs 1.126; 1.127)

- Swelling is painless, observed after minor trauma, slowly progressing in fingers or toes.
- It is smooth, soft, mobile, tensely cystic, nontransilluminating and is often adherent to skin.
- It contains only squamous epithelium, without hair follicle/sweat or sebaceous glands.
- Complications are infection, rupture and pressure effect over digital nerves.



Fig. 1.126: Implantation dermoid finger—classical site.

Differential diagnosis

- Lipoma.
- Bursa.

Treatment

- Excision.

4. *Teratomatous Dermoid*

- It arises from all germinal layers ecto, meso and endoderms.
- It occurs in ovary, testis, retroperitoneum, mediastinum.
- It contains hair, teeth, cartilage and muscle.
- It can be benign or malignant.

SEBACEOUS CYST (WEN, EPIDERMOID CYST)

- It is a *retention cyst.* It is due to blockage of the duct of sebaceous gland, causing a cystic swelling. Sebaceous glands are situated in dermis which secretes sebum through sebaceous duct which opens either directly to skin surface or in to a hair follicle.
- It is common in face, scalp, scrotum.
- *It is not seen in palms and soles* as there are no sebaceous glands.
- Sebaceous cyst contains yellowish white cheesy material with fat and epithelium. It has putty like consistency, with a parasite in the wall of the sebaceous cyst—***demodex folliculorum****.* It is lined by only epidermal layer of squamous epithelium. (See Figs 1.132, 1.133)



Figs 1.127A and B: Implantation dermoid in (A) Fingers (B) little toe.



Fig. 1.128: Dermoid cyst ovary right sided.



Fig. 1.129: Dermoid in the midline sternum. It may extend in to deeper plane and so it needs CT chest and evaluation.



Fig. 1.130: Cut section of dermoid cyst ovary showing sebum.



Fig. 1.131: Twisted gangrenous cyst ovary.

The most valuable diagnostic instrument is passage of time. — Henry George Miller



Fig. 1.132: Large ovarian cyst right sided.



Fig. 1.133: Large sebaceous cyst in face.

Clinical Features

- Painless swelling which is *smooth, soft, nontender, freely mobile, adherent to skin especially over the summit, fluctuant (positive Paget's test), nontransilluminating with punctum over the summit.*
- It moulds on finger indentation.
- ***Punctum*** is present over the summit in 70% of cases because here sebaceous duct opens directly into the skin which gets blocked. Punctum is depressed black coloured spot over the summit of the sebaceous cyst. Because of the denuded squamous epithelium (keratin) it is black in colour. In 30% cases sebaceous duct opens into the hair follicle and so punctum is not seen.

  (**Fordyce's disease** is heterotopic sebaceous glands in mucosa of the lip and oral cavity).



Figs 1.134A and B: Sebaceous cyst in face and scalp. Note the hair loss on the skin over the cyst. Sebaceous cyst in the face is infected.

- Hair loss over the surface is common due to constant pressure over the roots of the hair follicles.

Complications

- Infection and abscess formation.
- Surface gets ulcerated leading to formation of a painful, fungating mass with discharge called as—***Cock's peculiar tumour***—often resembles epithelioma. It is a misnomer as it is not a tumour. It is a chronic granuloma on an ulcerated surface of a sebaceous cyst.
- ***Sebaceous horn*** results from hardening of slowly discharged sebum through the punctum.

Multiple sebaceous cysts may be associated with syndromes like Gardner's syndrome.

Sebaceous cyst in the scrotum is usually multiple, firm and often calcified without any punctum. It is often treated by partial or total scrotectomy.



Figs 1.135A and B: Multiple sebaceous cysts in the scrotum. Occasionally partial scrotectomy is done in these patients.



Fig. 1.136: Small sebaceous cyst in face with typical punctum over the summit.



Fig. 1.139: Multiple sebaceous cysts back



Fig. 1.137: Sebaceous horn scalp.



Fig. 1.140: Cock's peculiar tumour over scalp and ear.



Fig. 1.138: Sebaceous horn back.



Fig. 1.141: Incision for sebaceous cyst is elliptical which includes punctum.

Treatment

- Excision including skin adjacent to punctum.
- Incision and avulsion.
- If abscess is formed, then drainage initially and later excision is done.
- If capsule is not removed properly the cyst will recur.

The worth of your lives comes neither in what we do nor whom we know but by whom we are.

Sequestration dermoid	***Sebaceous cyst***
• Occurs in the line of fusion	• Occurs anywhere except palm and sole
• Skin is not adherent (free)	• Skin is adherent over summit
• Extends often into deeper plane or cavities through suture line	• Subcutaneous plane – do not extend to deeper plane
• Punctum is absent	• Punctum is present – 70% cases
• Bone resorption and indentation is common	• Freely mobile without bone resorption
• With restricted mobility	• Superficial swelling, mobile
• Needs proper evaluation with X-ray/CT scan	
• Excision is done under general anaesthesia	• Excision is done under local anaesthesia

GLOMUS TUMOUR

- It is also called as ***glomangioma***.
- It arises from the cutaneous glomus composed of a tortuous arteriole which communicates directly into the venule and these vessels being surrounded by network of small nerves making this lesion very painful.
- Tumour consists of a mixture of blood spaces, non-medullated nerve tissue, muscle fibres derived from the wall of the arteriole, with large cuboidal glomal cells—***angiomyoneuroma***.
- They are often seen in limbs and common in nail-beds near the finger tips, as purple red swelling.
- It is 2-3 mm in size.
- It does not turn into malignancy.

Clinical Features

- *Severe burning sensation and pain, out of proportionate to the size. Commonest site is nail bed.*
- Even the slightest pressure will give rise to severe pain. Dilated vessels compress over nerves.
- **It is compressible and pain is more when the limb is exposed to sudden changes in temperature.**
- On increasing the pressure in the arm above systolic, pain disappears.

Differential Diagnosis

- Pyogenic granuloma.
- Subungual melanoma.

Treatment

- Excision cures the condition.

PAPILLOMA

- It is warty swelling from the skin or often from the mucous membrane.
- It has got a central axis of connective tissue, blood vessels and lymphatics.

True Papilloma

It is a benign tumour with localised overgrowth of the epidermis. It is commonly pedunculated but rarely can be sessile.

Pedunculated papilloma is villous with a central axis of connective tissues, blood vessels and lymphatics.



Fig. 1.142: Pedunculated papilloma. Note the incision for the same.

Infective Papilloma

Infective papilloma is a warty lesion due to infection, e.g. Condyloma acuminata.

Papilloma may be	single.
	multiple.
Papilloma may be	pigmented.
	nonpigmented.



Fig. 1.143: Pedunculated papilloma with its pedicle.

- True papilloma may turn into squamous cell carcinoma occasionally. There will be sudden increase in size, bleeding or ulceration.
- Papilloma can occur in the breast called as *duct papilloma* which is the commonest cause of bloody discharge from the nipple.
- Papilloma can occur in mucous membrane like in *oral cavity, urinary bladder* (transitional papilloma), in the *rectum* (columnar), in the *larynx*, in the *gallbladder* (cuboidal).

Differential Diagnosis

Amelanotic melanoma, pedunculated lipoma, carcinoma.

Treatment

- *True papilloma* is excised with its base along with surrounding 1 cm skin margin.
- *Infective warts* can be treated by excision or CO_2 snow or diathermy coagulation.

Complications of papilloma

- Bleeding
- Malignant transformation
- Ulceration
- Mechanical disability like voice change when it occurs in vocal cord

Fibroepithelial papilloma also called as skin tags / achrochordon is very common benign skin lesion of usually 5 mm diameter in size; common in adults; common in neck, axilla, thigh and groin. It is a vascularized keratinized squamous epithelium, can cause local irritation and insignificant bleeding. If it causes cosmetic problem it is removed by laser / cautery or excision.

FIBROMA

It is a benign tumour arising from fibrous tissue. It is capsulated.

Classification of True Fibroma

1. *Soft fibroma*—contains immature fibrous tissue. Common in face, presents as soft brown swelling.
2. *Hard fibroma*—contains well-formed fibrous tissue.

Note: True fibroma is rare and cannot be diagnosed clinically. It is mostly combined with mesodermal tissues like nerve sheath (neurofibroma), fat (fibrolipoma), muscle (fibromyoma).



Fig. 1.144: Papilloma right waist. Note the warty surface.



Fig. 1.145: Papilloma tongue. Note: Papilloma can occur in mucous membrane also like oral cavity, urinary bladder, gallbladder and rectum.

Treatment

Treatment of true fibroma is excision.

An entity called ***aggressive fibromatosis*** is known to occur as unencapsulated proliferation of fibrous tissue, common in abdominal and chest wall. It is considered presently *as locally malignant*. It does not spread through lymphatics or through blood. *But recurrence is common.*

Desmoid tumour is a variant of aggressive fibromatosis, seen in females, often associated with Gardner's syndrome. (Desmos = tendon, eidos = appearance). *Refer chapter abdominal wall and umbilicus*.

Recurrent fibroid of Paget's is a rare type of fibrosarcoma occurring in a scar tissue after many years.

BURSAE

Bursa is a sac like cavity containing fluid within, which in normal location prevents friction between tendon and bone.

If we are to grow good corn, we must help our neighbours grow good corn.—Steve Goodier.

Minor injuries and pressure leads in to bursitis, which will present as a swelling at the site.

Inflammation of this bursa due to friction causes ***bursitis***, which commonly presents as swelling, pain, and restricted movements.

Different Types

It can be ***anatomical or adventitious***.

Anatomical

- *Subhyoid bursa*—An horizontally oval swelling situated below the hyoid bone and in front of the thyrohyoid membrane.
- *Subacromial bursa*—In front and lateral to humeral head in relation to supraspinatus tendon between acromion and greater tuberosity of humerus.
- *Bicipito radial bursa.*
- *Olecranon bursa* (*Student's elbow, Miner's elbow*)—It is subcutaneous bursa in relation to olecranon which becomes distended due to prolonged periods of leaning on elbow.
- *Psoas bursa*—A tensely cystic swelling situated beneath and below the inguinal ligament, in the lateral aspect of the femoral triangle. But it will not extend above the inguinal ligament in to the iliac region (unlike in psoas abscess which extends above and is cross fluctuant).
- *Prepatellar bursa* (*Housemaid's knee)*—It lies subcutaneously in front of lower half of patella and upper half of patellar tendon (upper part) undergoes inflammation in people who do much kneeling.
- Infrapatellar bursa (*Clergyman's knee*) lies lower to prepatellar bursa.
- *Semimembranosus bursa*



Fig. 1.146: Bursa near elbow joint.



Fig. 1.147: Adventitious bursa over lateral aspect of foot – a common site.



Fig. 1.148: Prepatellar (Housemaid's knee) and infrapatellar bursae (Clergyman's knee).



Fig. 1.149: Location of olecranon bursa (Student's elbow).



Fig. 1.150: Common site of adventitious bursa (Bunion).

- *Bursa anserina*—under the tendons of Guy ropes (sartorius, gracilis and semitendinosus tendons). (Goose's foot).
- *Retro calcaneum bursa*—between calcaneum and tendo achilis.

Adventitious Bursa

Adventitious bursa occurs in an unusual site like in hallux valgus (***bunion)*** over first metatarsal, over lateral malleolus(***tailor's bursa***), between clavicle and skin near shoulder (*porter's bursa*) or between gluteus maximus muscle and ischial tuberosity (*weaver's bursa*), between tendoachilis and skin (***retro achilis bursitis***) or over gluteal tuberosity. It occurs due to friction or pressure.

Differential Diagnosis

- Soft tissue tumour.

Management

- X-ray of the part and often FNAC are required.
- Excision of the bursa.

SEMIMEMBRANOSUS BURSA

It is a cystic swelling in the upper medial aspect of the popilteal fossa under the semimembranosus tendon. It is said to be due to friction under the tendon causing bursitis.

Clinical Features

- Common in young individuals.
- Soft, smooth, cystic, often transilluminant and non-tender, non-compressible swelling located in upper and medial aspect of the popilteal fossa.
- On flexion of knee the swelling disappears and on extension it becomes more prominent.
- Swelling does not communicate into the knee joint cavity.
- Knee joint is normal.



Fig. 1.151: Semimembranosus bursa typical location.



Figs 1.152A and B: Semimembranosus bursa – typical location. On flexion it disappears.

> *Look well to this day for yesterday is but a dream and tomorrow is but a vision. But today, well lived, makes every yesterday a dream of happiness and every tomorrow a vision of hope.*—Kalidasa.

Treatment

- Ultrasound of popilteal fossa shows the cystic swelling under semimembranosus tendon.
- X-ray knee joint is normal.
- Excision is done under general anaesthesia using tourniquet. Complete excision of the sac is needed to prevent recurrence.

MORRANT BAKER'S CYST

It is a cystic swelling containing gel like fluid in the lower midline of the popliteal fossa. It occurs due to herniation of the synovial membrane of the knee joint as a result of chronic arthritis.

Clinical Features

- It is common in middle-aged individuals.
- It is smooth, soft and cystic, often tender swelling located below and in midline of the popilteal fossa.
- On flexion swelling increases and on extension swelling decreases in size.
- Pain and tenderness are present in knee joint with effusion showing positive patellar tap.
- The knee joint movements are painful and restricted.

Management

- X-ray of joint shows arthritic changes.
- MRI may be needed occasionally.

Treatment

Arthritis is treated and Baker's cyst is excised under general anaesthesia in prone position.



Fig. 1.153: Morrant Baker's cyst – typical location.

LYMPH CYST (LYMPHATIC CYST)

- It is an *acquired type* of *distension cyst* wherein lymphatics form a localised swelling with a capsule around it.
- It usually occurs in subcutaneous plane, which is smooth, soft, nontender, mobile, and brilliantly transilluminant. It is usually not adherent to the skin.
- **Common sites** are neck and limbs.
- It can get infected and form an abscess.



Fig. 1.154: Lymph cyst, which is transilluminant. It is an acquired condition.

Differential Diagnosis

- Cold abscess, dermoid cyst.

Treatment

- Excision.

CALCINOSIS CUTIS

- It is a condition of calcification (dystrophic) in or under the skin. Usually presents as a circumscribed lesion in the skin.
- Commonly seen in females. Common site is in the waist. (Fig. 1.155)
- Usually bilateral.
- It is said to be due to friction causing degeneration of skin and immediate deeper structure with increased local alkalinity of the tissue causes precipitation of the calcium leading to solid, hard, swelling in the skin. Cut section shows hard, yellowish material.
- It may mimic calcified lipoma or neurofibroma.
- **Treatment** is excision and closure of defect often with local flaps.

NEUROMA

Two types of neuromas are found.

- **False neuroma.**
- **True neuroma.**



Fig. 1.155: Calcinosis cutis near waist is a common site. It is common in females.

False Neuroma

- It occurs due to injury to the nerve either after trauma or amputation which presents as a tender swelling.
- It arises from the connective tissue of nerve sheath.
- It contains fibrous tissue with coiled nerve fibres.
- It can be ***end neuroma,*** commonly seen in amputation stump as a tender localised firm swelling often adherent to the stump scar. It can cause neuralgia in the stump. It prevents the proper usage of prosthesis. So during amputation, nerve should be pulled down and cut so as to make cut end to retract more proximally, which prevents the formation of neuroma.
- It can be ***lateral (side) neuroma*** which is observed after partial nerve injury, usually after trauma. It presents as a tender, firm swelling along the line of the peripheral nerve.



Figs 1.156A and B: Types of false neuromas – (A) End neuromas (B) Lateral neuromas.

True Neuroma

- It is a rare tumour.
- It occurs in connection with sympathetic system.

Types

Ganglioneuroma

- It contains ganglion cells and nerve fibres.
- It occurs in connection with sympathetic chain. So it is observed in neck (parapharyngeal mass), thorax, retroperitoneum, adrenal medulla.
- It is relatively benign and symptomless and often attains a large size.
- Early complete excision can give a cure.

Neuroblastoma

- It is poorly differentiated, aggressive, embryonic type of tumour.
- It is seen in infants and children.
- It spreads through blood but can go for spontaneous remission occasionally.

Myelinic Neuroma

- It contains only nerve fibres.
- Ganglion cells are absent.
- It occurs in spinal cord or pia mater.

NEUROFIBROMA

- **It is tumour arising from connective tissue of the nerve.**
- It can be single or multiple. Neurofibromas may be associated with pheochromocytomas, hypertension and few syndromes.

Sites

- Cranial
- Spinal. Neurofibroma is the commonest intradural extramedullary spinal tumour.
- Peripheral.

Types

- ***Nodular neurofibroma*** presents as single smooth, firm, tender (often) swelling which moves horizontally or perpendicular to the direction of the nerve, not in the direction of the nerve. There is pain and hyperaesthesia in the distribution of the nerve.
- ***Plexiform neurofibroma*** commonly occurs along the distribution of 5th cranial nerve in the skin of face. It often occurs in the cutaneous distribution of the peripheral nerve. It attains enormous size with

There is only one pretty child in the world, and every mother has it.— Chinese proverb.



Figs 1.157A and B: Multiple neurofibroma.



Figs 1.158A and B: Patient with multiple neurofibromatosis underwent laparotomy showing serosal neurofibroma.

thickening of the skin which hangs downwards. It causes erosion into the bone, orbit and deeper structure. It may also cause myxomatous degeneration. It causes cosmetic problem. Paraesthesia along the distribution of the trigeminal nerve (commonly ophthalmic division) is common.

Pachy dermatocele—a variant of plexiform neurofibroma where neck is involved.

- ***Generalised neurofibromatosis (von Recklinghausen's disease***): (1:4000 births)
  - It is an inherited autosomal dominant disease wherein there will be multiple neurofibromas in the body—chromosome 17.
  - It may be cranial, spinal or peripheral.
  - It is associated with pigmented spots (coffee coloured) in the skin, commonly seen on the back, abdomen, thigh **(*café au lait spots*)**. More than 5 in number, with each 1.5 cm or more in size is significant. *Café au lait* signifies common neuroectodermal origin of nerve sheath cells and melanocytes.
  - Axillary/groin freckles and Lisch nodules may be present.
  - Neurological disturbance is uncommon.



Figs 1.159A and B: Plexiform Neurofibroma in the (A) Face and neck and (B) Buttock.



Fig. 1.160: Plexiform neurofibromatosis involving trigeminal (5th cranial) nerve.



Figs 1.161A and B: Multiple neurofibromatosis with café au lait spots in the skin.

  - May be associated with MEN type IIb (Multiple neurofibromas of eyelids, lips, and face; medullary carcinoma of thyroid; pheochromocytoma and hyperparathyroidism).
- ***Elephantiatic neurofibromatosis***: It is of congenital origin. It involves limbs. Skin of the limb is greatly thickened, dry and coarse.

Complications

1. *Sarcomatous changes*: Common in generalised type (5%). When it occurs it shows rapid enlargement, warmness, more vascularity with dilated veins. Secondaries in lungs can occur through blood spread.
2. Cystic degeneration.
3. Haemorrhage into the tissues.
4. Spinal and cranial neurofibromas can cause neurological deficits.
5. Erosion into deeper planes, bone, orbit.
6. Muscle atrophy.
7. Spinal dumbbell tumour can cause compression of spinal cord and paralysis of the limb.

Note: Familial type of neurofibroma may be associated with scoliosis.

Treatment

- Excision.

Indications
- Symptomatic neurofibroma—Pain and pressure symptoms
- Cosmetically problematic lesion
- Recent increase in size
- Malignant transformation 5%

Remember about neurofibroma
- Neurofibroma is fusiform swelling which has got horizontal mobility but not longitudinal mobility (neurilemmoma has got free mobility in all directions)
- Café au lait spots signify common neuro-ectodermal origin of nerve sheath and melanocytes
- Kyphoscoliosis may be an association in familial variety
- Phaeochromocytoma with hypertension may be an association
- *Plexiform neurofibromatosis* commonly involves trigeminal cranial nerve mainly ophthalmic division causing paraesthesia, can obstruct the vision when it is large, have grossly thickened pendulous skin hanging down to various levels
- Calcification, saponification, myxomatous changes, sarcomatous transformation (fungation, rapid recent increase in size, warmness, dilated surface veins, redness with increased vascularity, fixity, persistent severe pain, immobility, lung spread) and cosmetic problem are the complications
- Intestinal neurofibroma may precipitate intussusception

NEURILEMMOMA (SCHWANNOMA)

It is arising from Schwann (neurilemmal cells) cells. They are lobulated, encapsulated, soft, whitish grey in appearance. They displace the nerve from which they arise and can be removed. They are common in acoustic nerve (cerebello-pontine angle) but also can occur in a peripheral nerve. Often they are multiple. Calcification is common.

The mother's heart is child's schoolroom.—Henry Ward Beecher.



Fig. 1.162: Lingual schwannoma. (*Courtesy by Dr Harish Rao Professor in surgery KMC Mangalore*)

Two types:
Anthony A—Two rows of spindle cells with central acellular area (Verocay bodies).
Anthony B—Acellular myloid areas.

Presentation is pain along the distribution of the nerve, hyperaesthesia and tenderness and as, soft or firm, lobulated, well localised mobile swelling.



Fig. 1.163: Schwannoma in the forearm.

Treatment

- Excision—easier without causing neurological damage.

Recurrent schwannoma could be malignant.

GANGLION

It is a cystic swelling occurring in relation to tendon sheath or synovial sheath or joint capsule. It contains clear gel like fluid.

Common sites

1. Dorsum of wrist (Near scaphoid-lunate articulation)
2. Flexor aspect of wrist
3. Around ankle joint—occasionally



Figs 1.164A and B: Neurilemmoma – gross look and cut section.



Figs 1.165A and B: Ganglion over the dorsum of the wrist – typical location. It can occur over the flexor aspect also. It can be transilluminant also.

Pathogenesis

- Cystic degeneration of the tendon sheath.
- Leakage of synovial fluid through joint capsule.
- There are small islets of microspaces in synovial sheath which often fuse together or one of them gets enlarged to form ganglion.

Clinical Features

- Well localised swelling which is smooth, soft, cystic, or tensely cystic, (Paget's test is +ve), nontender, transilluminant. It is mobile but mobility is restricted when tendon is contracted against resistance.
- Occasionally it is communicating with joint capsule.
- Often pain, tenderness and restricted joint movement may be the presentation (but rare).



Fig. 1.166: Ganglion over the wrist.

Differential Diagnosis

- Lipoma.
- Lymph cyst.
- Sebaceous cyst.
- Small ganglion often mistaken for sesamoid bone or exostoses.
- Bursa.

Treatment

- Asymptomatic ganglion is better left alone because of high recurrence rate.
- **Excision.** Usually done under local anaesthesia (lignocaine plain 2%). Patient should be explained of **high recurrence** rate (30%). After excision always it should be sent for histopathology. Firm crepe bandage application for 4 weeks is better in these patients.
- Aspiration and sclerosant injection may be useful.

  (In olden days people used to rupture the ganglion using bible book).

CHORDOMA

Tumour arising from the remnants of notochord.
It is seen in—

  - Sacrococcygeal region
  - Sphenoid sinus region.
  - Around the foramen magnum.
- It invades into the surrounding structure like nerves.
- Resection is difficult.
- Radioresistant.

EPIGNATHUS

This is a type of growth anomaly seen in neonates wherein growth from the base of skull protrudes through the mouth.



Fig. 1.167: Epignathus.

Swellings which are cross fluctuant

- Psoas abscess
- Bilocular hydrocele
- Ranula (plunging)
- Compound palmar ganglion

Note:

- *Enucleation* is removal of the swelling within the tissue of origin with normal part of tissue of origin is being retained. E.g., enucleation of prostate in benign prostatic hyperplasia (BPH).
- *Excision* is removal of tissue/tumour entirely with its capsule.

Move to the rhythm of soul and you'll never miss a beat.—Vicki Virk



Elliptical incision partially occupying the swelling- includes the punctum in this



Straight incision over swelling



Elliptical incision occupying the entire swelling (circumferential)

Fig. 1.168: Different incisions used in surgical approaches to remove swelling.

- *Wide excision* is removal of tumour with surrounding tissue margin adequately for clearance.
- *Compartment excision* is removal of tumour/diseased tissue with all adjacent soft tissues in one compartment except neurovascular bundle. It is done in limbs for soft tissue sarcoma as a curative but limb saving procedure.
- *Radical excision/radical block dissection* is removal of tumour widely with adjacent soft tissues with lymph node dissection.

Self-assessment Questions

- Lipoma.
- Dercum's disease.
- Diffuse lipoma.
- Complications of lipoma.
- Sebaceous cyst.
- Dermoids.
- Tubulodermoid.
- Sequestration dermoid.
- Angular dermoid.
- External angular dermoid.
- Ganglion.
- Compound palmar ganglion.
- Neurofibroma.
- von Ricklinghausen disease.
- Glomus tumour.
- Classification of cyst.

Electrolyte and Nutrition

Normal physiology
Water loss
Water intoxication
ECF loss
ECF excess
Hyponatraemia
Hypernatraemia
Hypokalaemia
Hyperkalaemia
Hypermagnesaemia
Hypomagnesaemia
Acid-base balance
Fluid therapy
Nutrition
Gastrostomy
Jejunostomy
Total parenteral nutrition (TPN)
Refeeding syndrome
Obesity

NORMAL PHYSIOLOGY

Total body water is 60% of body weight in males, 50% of body weight in females, i.e. 30 litres.

- Intracellular water—20 litres (2/3).
- Extracellular water—10 litres (1/3).
  - Plasma (1/4) (2.5 litres).
  - Interstitial fluid (7.5 litres).

Ion	*ICF*	*ECF and plasma*
Sodium	10 mmol/L	140 mmol/L
Potassium	150 mmol/L	4.5 mmol/L
Chloride	Trace only	105 mmol/L

ECF volume and osmolality regulation is controlled by three hormones. Aldosterone, ADH, atrial natriuretic hormone.

WATER LOSS

Decrease in the whole body fluid volume, both ECF and ICF.

Causes

- **Poor intake.** • **Diabetes insipidus.**

Drop in ECF is balanced by drop in ICF. So clinically patient is not dehydrated even though there is water drop.

Thirst, confusion and hypothermia are the clinical features.

Investigations

Raise in plasma sodium and urea.

Treatment

Oral water or IV isotonic fluid. 5% dextrose.

WATER INTOXICATION

Causes

- Excessive amount of intravenous dextrose 5%.
- During colorectal bowel wash for preparation of large bowel for surgery, if water is used instead of saline, especially in children.
- In TURP (Transurethral resection of prostate) when excess irrigating fluid water or Glycine is used (commonly used).
- In syndrome of inappropriate antidiuretic hormone (SIADH) which is commonly associated with lobar pneumonia, empyema, oat cell carcinoma and head injury.

Clinical features

- *Drowsiness, weakness*
- *Convulsions and coma*
- *Nausea, vomiting*
- *Passage of dilute urine*

Investigations

- Haematocrit and sodium level (will show fall in level).
- Low potassium. Low blood urea.

Treatment

- Water restriction and observation.
- Monitoring in ICU
- Management of fluid and electrolyte balance.
- Infusion of hypotonic sodium chloride.

Administration of diuretics and hypertonic saline should be avoided, as it may cause rapid changes in serum sodium and water level which will lead to neuronal demyelination and *fatal outcome.*

You cannot harm a bandaged wound.— Croatian Proverb

ECF LOSS

- Here only ECF loss is present with normal ICF.
- It is seen in vomiting, diarrhoea, intestinal obstruction.
- Treatment is infusion of normal saline.

ECF EXCESS

- Only ECF excess without an ICF excess.
- Excessive infusion of saline with impaired excretion.
- Raised JVP (earliest and best clinical sign), cardiac failure and peripheral oedema.
- Treatment is fluid restriction and diuretics like frusemide.

HYPONATRAEMIA

Sodium level less than 130 mEq/litre.

It can be due to water overload (dilutional) or sodium loss.

Types of Hyponatraemia

- Acute—presents as neurological manifestations
- Chronic—causes pontine myelinolysis. It presents as behavioural changes, progressive weakness, and cranial nerve palsies.

Causes

- Intestinal obstruction.
- Intestinal fistulas—biliary, duodenal, gastric, pancreatic.
- Gastric outlet obstruction with severe vomiting.
- Ryle's tube aspiration.
- Severe diarrhoea due to viral cause, in colitis, colorectal polyps.
- Syndrome of inappropriate antidiuretic hormone. (SIADH).
- Immediately after surgery and trauma, sodium depletion occurs.
- Stroke.

Clinical features

- *Dry coated tongue*
- *Sunken eyes*
- *Dry wrinkled skin*
- *Hypotension*
- *Dark scanty urine*
- *Irritability, disorientation and neurological manifestations*
- *Convulsions*
- *In chronic hyponatraemia- hypothermia, reduced tendon reflexes, pseudobulbar pasly*

Investigations

Serum electrolytes. Urinary sodium is low.

Treatment

- IV normal saline or double strength saline or Ringer lactate IV, 0.3% NaCl.
- The cause is treated.

HYPERNATRAEMIA

Serum sodium level > 150 mEq/L.

Excess infusion of normal saline causes overload in circulating salt and water.

It is usually due to water deficit.

Causes

- Renal dysfunction.
- Cardiac failure.
- Drug induced like NSAID, corticosteroids.

It may be either primary sodium excess or primary potassium excess or primary water deficit.

Types of Hypernatraemia

- Euvolemic (pure water loss)
- Hypovolaemic (among the loss of water and sodium, more water is lost than sodium)
- Hypervolaemic (both sodium and water gain but sodium gain is more than water gain).

Clinical Features

- Pitting oedema.
- Puffiness of face.
- Increased urination.
- Often dilated jugular veins.
- Features of pulmonary oedema.

Investigation: Serum electrolytes.

Management is restriction of saline and sodium. Treatment of pulmonary oedema.

Hypernatraemia should be corrected slowly as follows:

Initial infusion of normal saline, then infusion of half strength saline and later with 5% dextrose, i.e. gradual controlled correction is done. Otherwise cerebral oedema and hyperglycaemia can develop.

HYPOKALAEMIA

Sudden Hypokalaemia

Serum potassium level less than 3.5 mEq/L.

It occurs in patients in diabetic coma treated by insulin and saline infusion.

Gradual Hypokalaemia

Causes

- Diarrhoea of any causes, villous tumour of the rectum, ulcerative colitis.
- After trauma or surgery.
- Pyloric stenosis with gastric outlet obstruction.
- Duodenal fistula, ileostomy.
- After uretero sigmoidostomy.
- Insulin therapy.
- Poisoning.
- Drugs like beta agonists.

Clinical Features

- Slurred speech.
- Muscular hypotonia.
- Depressed reflexes.
- Paralytic ileus.
- Weakness of respiratory muscles.
- Cardiac arrhythmias.
- Inability to produce concentrated urine and so causes nocturia and polyuria.

ECG shows prolonged QT interval, depression of the ST segment and inversion of T wave, prominent U wave.

Often hypokalaemia is associated with *alkalosis.* Serum potassium will be decreased.

Treatment

- Oral potassium 2 g 6th hourly.
- IV KCl 40 mmol/litre given in 5% dextrose or normal saline *slowly*, often under ECG monitoring. (Total dose is 40 mmol. Maximum dose per hour is 20 mmol).
- *Hypokalaemic alkalosis which occurs in pyloric stenosis* should be treated carefully by IV potassium as there will be severe potassium loss.

HYPERKALAEMIA

Normal range of potassium is 4.0 to 4.5 mEq/litre.

Hyperkalaemia manifests when potassium ***exceeds 6 mEq/litre.***

Causes

- Renal failure.
- Rapid infusion of potassium.
- Transfusion of stored blood.
- Diabetic ketoacidosis.
- Adrenal insufficiency.
- Potassium sparing diuretics, cyclosporine, beta blockers.
- Metabolic acidosis.
- Insulin deficiency.
- Tissue destruction.

Potassium excess is a dangerous condition which can cause sudden cardiac arrest.

Investigations

High serum potassium level. Peak 'T' wave in an ECG.

Treatment

- IV administration of 50 ml of 50% glucose with 10 units of soluble insulin, slowly.
- Infusion of 10% calcium gluconate (as cardio-protection) intravenously.
- Calcium chloride is given in severe cases as calcium in this form is released immediately without hepatic metabolism.
- Diuresis using frusemide injection.
- Haemodialysis when required - very useful.
- Continuous ECG monitoring is a must.
- Polyesterene sulphonate ion exchange resin 30 g/hour in 50 ml of 70% sorbitol as an enema.
- Salbutamol nebulisation or intravenously 0.5 mg in 4 ml of saline/Albuterol nebulisation.
- IV sodium bicarbonate - shifts potassium in to cells. 7.5%, with 50-100 ml intravenously in 10 minutes.

HYPERMAGNESAEMIA

It is rare. Serum magnesium > 2.5 mEq/litre.

Causes

- Advanced renal failure treated with magnesium containing antacids, diabetic ketoacidosis.
- Intentionally produced hypermagnesaemia while treating pre-eclampsia.

Clinical Features

- Loss of tendon reflexes (commonest).
- Neuromuscular depression.
- Flaccid quadriplegia.
- Respiratory paralysis.
- Somnolence.
- Hypotension.

HYPOMAGNESAEMIA

- Serum magnesium < 1.5 mEq/litre.

> *Sir, it is plain that if he is too fat he has eaten more than he should have done.*— Samuel Johnson

Causes

- Malnutrition, alcohol.
- Large GI fluid loss.
- Patients on total parenteral nutrition.

Clinical Features

- Hyperreflexia.
- Muscle spasm.
- Paraesthesia.
- Tetany.

It mimics hypocalcaemia.

It is often associated with hypokalaemia and hypocalcaemia. Two gram (16 mEq) of magnesium sulphate slow intravenously, in 10 minutes. Later maintenance dose of 1 mEq/kg/day as slow continuous infusion is given/oral magnesium is needed.

ACID-BASE BALANCE

Normal pH (– log 10 of H^+) is 7.36-7.44.

Factors which control the pH:

- *Buffer system*
    - Bicarbonate buffer
    - Protein buffer
    - Phosphate buffer
- *Renal control of pH*
- *Respiratory control of pH*

METABOLIC ALKALOSIS

Primary base excess, i.e. HCO_3. *A standard bicarbonate above 27 mmol/litre*

Causes

- Repeated vomiting due to any cause. Commonly seen in cases of pyloric stenosis. Here ***hypokalaemic alkalosis*** occurs which is an important aspect for managing the patient.
- Excess alkali ingestion, e.g. antacids.
- Cortisol excess either due to over administration or Cushing's syndrome.

Clinical Features

- Cheyne stokes breathing with period of apnoea of 5-30 seconds.
- ***Tetany*** due to alkalosis. More often *latent tetany* which is revealed by *Trousseau's sign*.

Investigations

Serum electrolytes, arterial blood gas analysis.

Treatment

Normal saline or double strength normal saline IV infusion, with slow IV potassium chloride 40 mmol/litre in saline, slowly under ECG monitoring.

RESPIRATORY ALKALOSIS

Arterial PCO_2 is below normal.

Causes

- Hyperventilation during anaesthesia.
- High altitude.
- Hyperpyrexia.
- Encephalitis, hypothalamic tumours, drugs like salicylates.
- Hysteria.

It may lead to tetany.

Respiratory suppression due to alkalosis is treated by CO_2.

METABOLIC ACIDOSIS

It is an excess acid or base deficit. **A standard bicarbonate below 21 mmol/litre.**

Causes

Increase in fixed acid:

- Diabetic ketoacidosis.
- Starvation.
- Hypoxia.
- Renal insufficiency.
- Cardiac arrest.
- Excessive exercise.
- Intestinal strangulation. Here anion gap is increased.

Loss of base:

- Diarrhoea.
- Ulcerative colitis.
- Gastrocolic fistula.
- Intestinal fistula.
- Ureterosigmoidostomy causes hyperchloraemic hypokalaemic acidosis. Here anion gap is normal.

Features

- Rapid, deep, noisy breathing (air-hunger).
- Cold clammy skin, tachycardia, right heart strain, altered level of consciousness.
- Capillary stasis.
- Urine is strongly acidic.
- Low standard HCO_3 level.
- Base deficit.

Treatment

- Correction of hypoxia.
- **50 mmol of 8.4% Sodium bicarbonate infusion IV.**

Sodium bicarbonate required in mEq/L = Body weight in kg × Base deficit × 0.3.

Astrup formula

Total base excess or deficit = Base excess/base deficit × body weight in kg × 0.3

RESPIRATORY ACIDOSIS

It is a feature of respiratory failure with high arterial PCO_2 causing fall in pH.

Causes

- During and after anaesthesia.
- Chronic bronchitis.
- Emphysema.
- Thoracic diseases.
- Upper abdominal surgeries and diseases.
- Respiratory air-way obstruction.
- Myasthenia gravis.
- Poliomyelitis.

ANION GAP

- It is calculated estimation of the undetermined or unmeasured anions in the blood.
- It is $(Na^+ + K^+) — (HCO_3^- + Cl^-)$.
- Normal anion gap is 10-16 mmol/litre.

Increased anion gap is seen in	*Normal anion gap is seen in*
• Metabolic acidosis due to ketoacidosis	• Diarrhoea
• Lactic acidosis	• GIT fistulae
• Poisoning	• Hyperchloraemic acidosis
• Renal failure	

FLUID THERAPY

Osmolality of a solution is assessed by the amount of solute dissolved in a solvent like water measured in weight (Kg).

Osmolarity of a solution is assessed by the amount of solute dissolved in a solvent like water measured in volume (litre).

Normal plasma Osmolality is 285 mOsm / kg — (275-295).

Principles of Fluid Therapy

Indications

- For rapid restoration of fluid and electrolytes in dehydration due to vomiting, diarrhoea, shock due to haemorrhage or sepsis or burns.
- Total parenteral nutrition.
- Anaphylaxis, cardiac arrest, hypoxia.
- Post gastrointestinal surgeries.
- For maintenance, replacement of loss or as a special fluid.

Advantage

Controlled, accurate and adjustable, rapid and predictable.

Problems in Fluid Therapy

- Needs hospitalisation; costly; needs asepsis
- Fluid overload; pulmonary oedema and cardiac failure; infection.
- Thrombophlebitis; haematoma; cellulitis in local area
- Pyrogenic reaction; air embolism; bacteraemia
- Discomfort; poor patient acceptance

Daily requirement of sodium is 100 mEq; potassium is 60 mEq; calcium is 5 mEq; magnesium 1 mEq.

One liter of normal isotonic saline contains 154 mEq of sodium.

Ringer's lactate is the most physiological fluid (*crystalloid*) containing sodium – 130 mEq/lt; potassium – 4 mEq/lt; chloride – 109 mEq/lt; lactate (bicarbonate) – 28 mEq/lt; and calcium – 3 mEq/lt. It should be avoided in liver failure patients. As it does not contain glucose it can be used in diabetics.

Other *crystalloid* fluids – normal saline, dextrose saline, 5% dextrose, isolyte P, isolyte G, isolyte M

Colloids are of large molecules which shift the fluid from interstitial compartment to intravascular compartment and are used as plasma expanders. Haemaccel, hetastarch, pentastarch, dextran 40 / 70 are colloids.

Special purpose fluids are sodium bicarbonate 7.5 % and 8.4% used in metabolic acidosis, forced diuresis, hyperkalaemia; mannitol 10% / 20% used as an osmotic diuretic agent; hypertonic saline 1.6%, 3%, 5% and 7.5% used in hyponatraemia of different severity; albumin 4.5% as plasma expander; albumin 20% in severe hypoalbuminaemia.

Calculation of Drop Rate of IV Fluids

1 ml =16 drops in usual drip set. For micro drip set one ml = 60 drops.

Less you eat, you are malnourished. More you eat, more you are diseased.

1. Quantity of fluid required in liters per day × 10 = Drop rate / minute. 2.5 liters is usually used quantity of fluid / day. So 2.5 × 10 = 25 drops / minute
2. Fluid volume in ml to be infused in one hour divided by four = Number of drops/minute. Example: 100 ml/hour means 25 drops/minute.
3. Number of micro drop/minute = Volume in ml/hour (50 micro drop/minute = 50 ml/hour)

Note:

- Weight loss more than 10% of individual's weight in 6 months is called as significant weight loss.
- Body Mass Index (BMI) is body weight in kilograms divided by height in meters squared. BMI less than 18.5 signifies nutritional impairment and below 15 signifies severe malnutrition.
- Daily fluid loss from kidneys is 1500 ml; from lungs is 400 ml; from skin is 800 ml; from stool is 60-150 ml.
- Energy requirement per day is 20-30 kcal/kg, i.e. around 2000 kcal/day total.
- Glucose requirement is 200 g per day; fat requirement is 200 g per week; nitrogen (protein) requirement is 0.15 g/kg per day. Nitrogen need increases to 0.25 g/kg/day in hyper catabolic status.
- Transit time is rapid in jejunum; three times slower in ileum; still slower in colon.
- Fluid absorption capacity is 40% in jejunum; 70% in ileum; 90% in colon.
- Electrolyte and vitamin B_{12} absorption and enterohepatic circulation occurs in ileum and so ileum is more important than jejunum.

NUTRITION

> ***We (now) devote more attention to the patient's diet and habits, and more often send him away with good advice than with hastily-written prescriptions.***
>
> —**Robert Hall Babcock,** 1901

Caloric requirement:

Neonatal 100 kcal/kg/day.
Adult 40 kcal/kg/day.
Adult with catabolism 60 kcal/kg/day.

It is given as

Carbohydrates 50%.
Fat 30-40%.
Protein 10-15%.

Caloric values

Carbohydrate 4 kcal/g.
Protein 4 kcal/g.
Fat 9 kcal/g.

Indications for Nutritional Support

1. Preoperative nutritional depletion.
2. Postoperative complications: Sepsis, ileus, fistula.
3. Intestinal fistula: High type wherein output is more than 500 ml/day. It may be duodenal, biliary, pancreatic, intestinal.
4. Pancreatitis, malabsorption, ulcerative colitis, pyloric stenosis.
5. Anorexia nervosa and intractable vomiting.
6. Trauma—multiple fractures, fascio maxillary injuries, head and neck injuries.
7. Burns.
8. Malignant disease.
9. Renal and liver failure.
10. Massive bowel resection causing short bowel syndrome.

Assessment

1. Body weight
2. Mid-arm circumference
3. Triceps skin fold thickness
4. Serum albumin
5. Lymphocyte count

Nutritional requirements: Carbohydrates, fat, proteins, vitamins (includes fat soluble vitamins also), minerals, trace elements.

Methods of Feeding

ENTERAL:

1. *Gastrointestinal tract is the best route to provide nutrition.*
2. *Enteral feeding can be delivered by bolus, by gravity or using mechanical pump.*
   a. *By mouth:* Requires—
      - Common sense,
      - Cleanliness,
      - Compassion.

   b. *By nasogastric tube:* Confirmation of the tube in the stomach is made by injecting 5 ml of air down the tube and listening through a stethoscope for its bubbling entry into the stomach. Feeding rate is 30-50 ml/hours. 5 hours night time gap is given to allow gastric pH to return to normal.

Problems with tube feeding are—

- Blockage
- Nausea and vomiting, aspiration
- Hyperosmolarity
- Diarrhoea
- Tube discomfort
- Cholestasis

c. *By enterostomy:*
Gastrostomy.
Jejunostomy.



Fig. 1.169: Nasogastric tube passed should be confirmed in place using stethoscope. Tube is used for feeding purpose.


Oesophagus
Gastrostomy tube
Stomach
Duodenum

Fig. 1.170: Gastrostomy tube in place for enteral feeding.


Oesophagus
Gastroscope
Abdominal wall
Guide wire
Stomach
Trocar
Gastrostomy catheter
Oesophagus
Guide wire
Stomach
A
Oesophagus
Guide wire
Abdominal wall
Gastrostomy catheter (tube)
Stomach
Oesophagus
Abdominal wall
Gastrostomy catheter (tube)
Stomach
B

Figs 1.171A and B: Percutaneous endoscopic gastrostomy (PEG). Guide wire passed through a trocar in the abdominal wall in to the stomach is pulled out across the oesophagus and mouth under visualisation using gastroscope. Gastrostomy catheter (tube) is passed along the guide wire and pushed downwards across mouth and esophagus to reach the stomach. It is further pushed along the abdominal wall through the trocar. Gastrostomy tube is pulled out through abdominal wall and fixed. Trocar is removed. Placement of tip of gastrostomy tube can be confirmed by doing gastroscope.

Life will give you back everything you have given to it.

Different preparations and formulas are available for enteral feeding. Soluble fibre containing diets along with nutrients are better to prevent diarrhoea.

Complications of enteral feeding

- Aspiration
- Wound infection and leak
- Diarrhoea due to rapid feeding or hyperosmolarity
- Hyperglycaemia
- Hypokalaemia
- Refeeding syndrome due to severe hypokalaemia and hypophosphataemia

GASTROSTOMY

It is done if feeding is required for more than *one month.*

Indications

- Severe malnutrition
- Major surgeries
- Severe sepsis
- Trauma
- Head and neck surgeries

Types

Based on duration of use:

- Temporary.
- Permanent.

Based on lining:

- Mucus lined (permanent).
- Serosal lined (temporary).

Based on technique:

1. ***Stamm temporary gastrostomy:*** After opening the abdomen, anterior wall of the stomach is opened. Feeding tube (Malecot's catheter) is placed in position. Two layers of purse string sutures are put around the tube. Wound is closed.
2. ***Kader-Senn temporary gastrostomy***.
3. ***Percutaneous endoscopic gastrostomy*** - popular – now becoming common method.
4. ***Janeway's mucus lined permanent gastrostomy*** by creating tunnel in stomach wall.

Problems in gastrostomy:

- Leak - gastric fistula
- Infection
- Aspiration and pneumonia.
- Diarrhoea is common – 30%
- Bloating, abdominal cramps
- Displacement, blockage of the tube

Contraindications

- Previous gastric surgeries.
- Intestinal obstruction.
- Gastric outlet obstruction.

JEJUNOSTOMY

Jejunostomy for enteral nutrition is becoming more popular because of:

- Its comfort,
- Easy to do,
- Can be kept for long time,
- Lesser complication than gastrostomy.

Indications are same as gastrostomy.

Types

1. *Witzel jejunostomy:* Site of placing jejunostomy is 30 cm from duodenojejunal junction.
2. *Needle jejunostomy* using catheter of small gauge.



Fig. 1.172: Needle jejunostomy.

TOTAL PARENTERAL NUTRITION (TPN)

All nutritional requirements are given only through intravenous route, not through gastrointestinal tract. It can be through a central catheter through the subclavian /internal jugular vein where the tip of venous catheter is at distal part of superior vena cava.

It can also be a peripheral (Peripheral Parenteral Nutrition / PPN) through a peripherally inserted central venous catheter (PICC) or through a formal peripheral venous line.

Indications

1. Failure or contraindication for any enteral nutrition.
2. High output abdominal fistulas, duodenal, biliary, pancreatic fistulas.
3. Major abdominal surgeries of liver, pancreas, biliary, colonic.
4. Septicaemia,
5. Multiple trauma.
6. Short bowel syndrome

About 5% of hospital admissions require TPN.

Technique

Using a needle and guide wire a *Subclavian vein catheter* is passed just below the clavicle and fixed securely to the skin.

TPN is given through *central vein* and not through a peripheral vein.

Peripherally inserted central catheter (PICC) is also commonly used - (PPN)

Components used in TPN

- Carbohydrates.
- Fat and amino acids.
- Vitamins and trace elements.

Monitoring the patient by body weight, fluid balance, blood glucose, electrolytes, blood urea, LFT serum calcium, magnesium, phosphate should be done at regular intervals.

A weight gain more than one kg/day signifies fluid overload.

Complications

Technical

1. Air embolism.
2. Pneumothorax.
3. Bleeding.
4. Catheter displacement, sepsis, blockage.
5. Infection, thrombosis.

Biochemical

1. Electrolyte imbalance: Hyponatraemia, hypokalaemia, hypophosphataemia.
2. Hyperosmolarity.
3. Hyperglycaemia. – common.
4. Dehydration.
5. Altered immunological and reticuloendothelial function.
6. Azotaemia.

Others

1. Dermatitis.
2. Anaemia and increased capillary permeability.
3. Cholestatic jaundice: It is common.
4. Severe hepatic steatosis.
5. Metabolic acidosis.
6. Candida infection (candidiasis), staphylococcal infection. (10-15%).

Contraindications

1. Cardiac failure
2. Blood dyscrasias
3. Altered fat metabolism

Anabolic steroid durabolin 25 mg IM weekly is given to improve nitrogen balance.

Home parenteral nutrition—

- It is becoming popular
- It is commonly used in western countries
- It is indicated in short bowel syndrome or any other conditions wherein enteral feeding is not possible but patient can be sent home with provision for home parenteral nutrition
- Patient himself uses the TPN fluids as advised at home. He will be with TPN catheter
- Patient should attend TPN clinic weekly for follow up or immediately whenever complications arise
- Patient will be comfortable psychologically and often can attend his job also

REFEEDING SYNDROME

Refeeding syndrome is occurrence of severe fluid and electrolyte imbalance in severely malnourished individual while starting the proper feeding enteral or parenteral nutrition. It is more common in TPN. It causes hypo-magnesaemia, hypocalcaemia and hypophosphataemia leading into myocardial dysfunction, respiratory changes, altered liver functions, altered level of consciousness, convulsions and often death. Gradual feeding and correction of magnesium, phosphate and calcium and other electrolytes is important. Condition is common in chronic starvation, severe anorexia and alcoholic patients.

OBESITY

Definition

Weight more than 20% above the normal.

Body mass index is weight in kilogram divided by height in metres squared [wt in kg/ (Ht in metres)^2.]

Classification

Normal BMI is 20-25.
BMI 25-30—pre-obesity.
BMI 30-35—mild—class I obesity.

We will not know unless we begin.

BMI 35-40—moderate—class II obesity.
BMI more than 40—morbid obesity—class III obesity.

Weight more than the double the expected weight to that age and height of the individual is called as Morbid obesity.

Causes of Obesity

- Familial.
- Hyperinsulinism.
- Hyperadrenocorticism.
- Hypogonadism.

Complications of obesity

General: Difficulty in work, fatigue, depression, back pain, arthritis and gout

Cardiovascular: Hypertension, stroke, thrombophlebitis, pulmonary embolism

Pulmonary: Hypoventilation, poor respiratory effort

GIT: Hiatus hernia with reflux, changes in liver, pancreatitis, gallstones

Endocrine: Diabetes mellitus

Obesity and Surgery

- Hernia is more common in obese individual.
- Gallstones are more common.
- Burst abdomen, incisional hernia are more common in obese individuals.
- Delay in recovering from anaesthesia.
- Infertility is more common.

Treatment for Obesity

- Dieting.
- Exercise.
- Vertical banded gastroplasty.
- Gastric bypass.
- Laparoscopic gastroplasty or gastric bypass.
- Jaw wiring.
- Bilio-pancreatic diversion.
- Jejuno-ileal bypass.

Self-assessment Questions

- Hyponatraemia.
- Hypernatraemia.
- Hyperkalaemia.
- Hypokalaemia.
- Parenteral nutrition.
- TPN.
- Gastrostomy.
- Jejunostomy.
- Metabolic acidosis.
- Metabolic alkalosis.
- Respiratory acidosis
- Respiratory alkalosis.
- Anion gap.
- Water intoxication.

Shock

> ***The first noteworthy characteristic of the blood in shock is a high capillary red count.… When haemorrhage as a complicating factor tending to reduce the blood count is considered, these high counts are striking. They indicate that in shock a concentration of the blood occurs, at least in the superficial capillaries.***
> **—Walter Bradford Cannon, J. Fraser, A.N. Hooper,** 1918

Shock
CVP
PCWP
SIRS
Oxygen therapy
Cardiac arrest

SHOCK

Shock is a state of poor perfusion with impaired cellular metabolism manifesting with severe pathophysiological abnormalities. It is due to circulatory collapse and tissue hypoxia.

CAUSES OF SHOCK

1. **Hypovolaemic shock—**due to reduction in total blood volume.
   It may be due to
   a. *Haemorrhage*
      — external from wounds, open fractures
      — internal from injury to spleen, liver, mesentery or pelvis
   b. *Severe burns*, which results in loss of plasma
   c. Peritonitis, intestinal obstruction
   d. Vomiting and diarrhoea of any cause
2. **Cardiac causes—**
   a. Acute myocardial infarction, acute carditis
   b. Acute pulmonary embolism wherein embolus blocks the pulmonary artery at bifurcation or one of the major branches
   c. Drug induced
   d. Toxaemia of any causes
   e. Cardiac surgical conditions like valvular diseases, congenital heart diseases
   f. Cardiac compression causes
      i. Cardiac tamponade due to collection of blood, pus, fluid in the pericardial space which prevents the heart to expand leading to shock.
      ii. Trauma to heart
3. **Septic shock—**is due to bacterial infections which release toxins leading to shock
4. **Neurogenic shock—**due to sudden anxious or painful stimuli causing severe splanchnic vessel vasodilatation. Here, patient either goes for cardiac arrest and dies or recovers fully spontaneously
5. **Anaphylactic shock—**is due to Type 1 hypersensitivity reaction
6. **Respiratory causes**
   a. Atelectasis (collapse) of lung
   b. Thoracic injuries
   c. Tension pneumothorax
   d. Anaesthetic complications
7. **Other causes**
   a. Acute adrenal insufficiency (Addison's disease)
   b. Myxoedema

Shock may be *hypovolaemic, cardiogenic, obstructive, distributive or of endocrine* variety.

Pathophysiology of Shock

Any cause of shock
↓
Low cardiac output
↓
Vasoconstriction occurs as a compensation to perfuse vital organs like brain, heart, muscle, kidneys, liver
↓
Because of vasoconstriction and tachycardia
↓
Dynamic circulation increases
↓
Tachypnoea occurs to increase the oxygen saturation
↓
Peripheral veins (capacitance vessels) constrict diverting blood from splanchnic system towards essential vital organs
↓
Decreased renal blood flow reduces the GFR and thereby the urine output
↓

Ideas have a short shelf life—that's why we must act before the expiry date.

Renin angiotensin mechanism gets activated causing further vasoconstriction and aldosterone release
↓
Causes salt and water retention
↓
ADH is released
↓
Further concentration of urine occurs.

When shock persists cardiac output falls further
↓
Hypotension and tachycardia occurs leading to poor perfusion of coronaries.
↓
Hypoxia — ***metabolic acidosis.***
↓
Release of cardiac depressants.
↓
Cardiac (pump) Failure.

Hypoxia
↓
Anaerobic metabolism
↓
Lactic acidosis
↓
Cell wall damage
↓
Sodium and calcium enter the cell
↓
Potassium leaks out of the cell
↓
Causes hyperkalaemia, hyponatraemia and hypocalcaemia
↓
Intracellular lysosomes break down releasing powerful enzymes which destroy own cell.
↓
SICK CELL SYNDROME.

Platelets are activated forming small clots in many places
↓
Disseminated Intravascular Coagulation (DIC) (Consumption coagulopathy)
↓
Further bleeding.

STAGES OF SHOCK

Factors like infection, trauma, burns, haemorrhage, hypovolaemia
↓
Hypoxia and its effects.
↓
SIRS *(Systemic Inflammatory Response Syndrome)* is due to vasodilatation, increased endothelial permeability, thrombosis, leukocyte migration and activation.
↓
All these lead to altered cytokines level, abnormal **NO (nitric oxide)** synthesis, abnormal arachidonic acid metabolism, neutrophil activation, free radical production, altered complement activation, failure to have a localisation of inflammation. It is severe type of ***reversible shock.***
↓
Which will lead to established microvascular occlusion, cellular dysfunction, sick cell syndrome, DIC and PUMP failure.
↓
MODS *(Multi Organ Dysfunction Syndrome)* ***(Irreversible shock)*** - of lungs, kidneys, liver, clotting system and brain.

Distributive shock is one in which there is vasodilatation, decreased vascular resistance, hypotension, altered micro vascular perfusion with arterio venous shunting, altered cellular oxygen metabolism. It is seen in septic shock, spinal trauma, adrenal crisis and anaphylaxis.

EFFECTS OF SHOCK

Heart*:* Low perfusion → low venous return → decreased cardiac output → hypotension → tachycardia. Persistent shock causes hypoxia and release of myocardial depressants leading to further cardiac damage.

Lung*:* Interstitial oedema → decreased gaseous exchange → pulmonary arteriovenous shunting → tachypnoea → *Adult/Acute respiratory distress syndrome (ARDS)* and pulmonary oedema.

Metabolic*:* Shock leads to hypoxia, which activates anaerobic metabolism leading to lactic acidosis. Antidiuretic hormone (ADH) is released which increases the reabsorption of water from renal tubules. Other hormones released are ACTH, prostaglandins, histamine, bradykinin, and serotonin to compensate the effects of shock to increase the perfusion of vital organs like heart, brain and lungs.

Cellular changes occur in persistent shock due to release of lysosomal enzymes, which alters the cell membrane permeability causing cell death—*sick cell syndrome.*

Sympathetic overactivity alters the microcirculation leading to capillary dysfunction.

Brain perfusion, when decreases the patient becomes drowsy. *Brain is the last organ to get underperfused in shock.*

Kidneys: GFR decreases and tubular reabsorption of salt and water increases for compensatory response. But in severe cases tubular necrosis sets in leading in to irreversible damage.

Blood*:* Alteration in cellular components including platelets leads to *Disseminated intravascular coagulation (DIC)*. It causes bleeding from all organs.

Gastrointestinal tract: Mucosal ischaemia develops causing bleeding from GIT with haematemesis and malaena. It is aggravated by DIC. Hepatic ischaemia leads into increased enzyme levels.

Types of Hypovolaemia

a. *Covert compensated hypovolaemia:* When blood volume is reduced by 10-15% , there will not be significant change in heart rate, cardiac output and splanchnic blood compensates for the same.

b. *Overt compensated hypovolaemia*: Here patient has cold periphery, tachycardia, a wide arterial pressure, tachypnoea, confusion, hyponatraemia, metabolic acidosis, but systolic pressure is well-maintained.

c. *Decompensated hypovolaemia:* Here all features of hypovolaemia are present like hypotension, tachycardia, sweating, tachypnoea, oliguria, drowsiness, eventually features of SIRS is seen and often if not treated on time leads to MODS, i.e. irreversible shock.

Types of Shock

1. ***Vasovagal shock:*** It is sudden dilatation of peripheral and splanchnic vessels causing reduced cardiac output and shock. Often it may be life threatening due to hypoxia.
2. ***Neurogenic shock*** is usually due to spinal cord injury, which causes dilatation of splanchnic vessels.
3. ***Hypovolaemic shock - commonest type***
   a. Haemorrhage, may be due to injury to the liver, spleen, bone fractures, haemothorax, vascular injury, severe bleeding on table during surgeries of thyroid, liver, portal vein or major vessels.
   b. Vomiting, diarrhoea due to any cause.
   c. Burns.
4. ***Cardiogenic shock***
   a. Occurs when 50% of left ventricle wall is damaged by infarction. It also leads to pulmonary oedema and hypoxia, further worsening cardiac damage.
   b. Acute massive pulmonary embolism from a thrombus or an air embolism (***50 ml of air***), obstructing more than 50% of pulmonary vasculature leads to severe shock and sudden death.
   c. Tachycardia, hypotension, pulmonary oedema, raised JVP, gallop rhythm are the features.
5. ***Cardiac compression shock*** is probably due to pericardial tamponade of any cause or kinking of great vessels, massive pulmonary embolism, tension pneumothorax, air embolism causes obstructive shock with reduced preload to heart.
6. ***Septic shock***: Septic shock may be due to gram positive organisms, gram negative organisms, fungi, viruses or protozoal origin.
   Gram negative septicaemia/gram negative septic shock is called as *endotoxic shock*. It occurs due to Gram negative bacterial infections, commonly seen in strangulated intestines, peritonitis, gastrointestinal fistulas, biliary and urinary infections, pancreatitis, major surgical wounds, diabetic wounds and crush injuries.

Pathophysiology of Septic Shock

Toxins/endotoxins from organisms like E Coli, Klebsiella, Pseudomonas, and Proteus

↓

Inflammation, cellular activation – of macrophages, neutrophils, monocytes

↓

Release of cytokines, free radicals

↓

Chemotaxis of cells, endothelial injury, altered coagulation cascade - SIRS

↓

Reversible hyperdynamic warm stage of septic shock with fever, tachycardia, tachypnoea

↓

Severe circulatory failure with MODS (failure of lungs, kidneys, liver, heart) with DIC

↓

Hypodynamic, irreversible cold stage of septic shock.

Stages of Septic Shock

1. *Hyperdynamic (warm) shock*: This stage is *reversible stage***.** Patient is still having inflammatory response and so presents with fever, tachycardia, and

Tears shed for self are tears of weakness, but tears shed for others is a sign of strength.

tachypnoea. Pyrogenic response is still intact. Patient should be treated properly at this stage. Based on blood culture, urine culture (depending on the focus of infection), higher antibiotics like third generation cephalosporins, aminoglycosides, metronidazole are started. The underlying cause is treated like draining the pus, laparotomy for peritonitis, etc. Ventilatory support with ICU monitoring may prevent the patient going for the next *cold stage of sepsis*.

2. *Hypodynamic hypovolaemic septic shock (cold septic shock)***:** Here pyrogenic response is lost. Patient is in decompensated shock. It is an irreversible stage along with MODS (Multi Organ Dysfunction Syndrome) with anuria, respiratory failure (cyanosis), jaundice (liver failure), cardiac depression, pulmonary oedema, hypoxia, drowsiness, eventually coma and death occurs - (*Irreversible stage).*

Treatment of Septic Shock

- Correction of fluid and electrolyte by crystalloids, blood transfusion.
- Appropriate antibiotics.
- Treat the cause or focus – drainage of an abscess; laparotomy for peritonitis; resection of gangrenous bowel; wound excision.
- Pus/urine/discharge/bile/blood culture and sensitivity for antibiotics.
- Critical care, oxygen, ventilator support, dobutamine/dopamine/noradrenaline to maintain blood pressure and urine output.
- Activated C protein prevents the release of inflammatory mediators and blocks the effects of these mediators on cellular function.
- Monitoring the patient by pulse oximetry, cardiac status, urine output, arterial blood gas analysis.

Septic shock

- Common causes are biliary, urinary, GIT sepsis (peritonitis, strangulation), respiratory (pneumonia)
- Common bacteria are *E.coli, Klebsiella, pseudomonas*
- Common pathophysiologies are release of toxins, neutrophil activation, cytokine release, and sick cell syndrome, SIRS, MODS
- Clinical stages are hyperdynamic amd hypodynamic
- Find out the source of the infection by U/S, CT scan
- Do pus/ blood/ urine culture
- Start antibiotics of high generations like ceftazidime, amikacin, cefoperazone
- Dopamine/dobutamine infusion (slow)
- Monitoring by pulse, BP, respiration, urine output, level of consciousness
- Ventilator support, ICU management
- ***Treat the causes like peritonitis, abscess***

7. ***Anaphylactic shock*****:** Injections—penicillins, anaesthetics, stings, venom, shellfish may be having antigens which will combine with IgE of mast cells and basophils, releasing histamine and large amount of SRS-A (Slow releasing substance of anaphylaxis). They cause bronchospasm, laryngeal oedema, respiratory distress, hypotension and shock. Mortality is 10%.

   Rashes all over the body are commonly observed.

Anaphylactic shock

- Sudden onset
- Distributive shock
- Bronchospasm, laryngeal oedema
- Generalised rashes and oedema
- Hypotension, feeble pulse
- Mortality 10%
- To start Adrenaline 100 ug IV, steroids, IV fluids, oxygen with foot end elevation
- Ventilator in severe cases
- Cardiac massage, defibrillation

Clinical Features of Shock

- In early stage—tachycardia, sweating, cold periphery, hypotension, restlessness, air hunger, tachypnoea, oliguria, collapsed veins.
- In late stage—cyanosis, anuria, jaundice, drowsiness.

Clinically shock may be –

- *Compensated* with mild tachycardia, normal blood pressure, urine output, normal respiration and mild lactic acidosis.
- *Mild* shock with mild lactic acidosis, tachycardia, tachypnoea and anxiousness.
- *Moderate* shock with significant lactic acidosis, decreased urine, tachycardia, tachypnoea, drowsiness, and mild hypotension.
- *Severe* shock with severe lactic acidosis, anuria, tachypnoea with gasping, severe tachycardia, profound hypotension and unconsciousness.

Shock index is ratio of pulse rate to blood pressure. Normal is < 1. In shock, it reverses.

Investigations

- Regular monitoring of BP, pulse.
- Heart rate.

- Respiratory rate
- CVP line (Central Venous Pressure).
- PCWP (Pulmonary Capillary Wedge Pressure).
- Pus, urine, blood culture in case of septic shock.
- U/S, CT, X-ray depending on location of pathology or septic focus.
- Measurement of urine output.
- Arterial PO_2 and PCO_2 analysis.
- Electrolyte estimation.

Treatment

Guidelines:

- *To treat the cause*
- *To improve cardiac function*
- *To improve tissue perfusion*

- Treat the cause, e.g. arrest haemorrhage, drain pus.
- Fluid replacement: Plasma, normal saline, dextrose, ringer lactate, plasma expander (haemaccel) (maximum 1 litre can be given in 24 hours). Initially crystalloids then colloids are given. Blood transfusion is done whenever required.
- Inotropic agents: Dopamine, dobutamine, adrenaline infusions - mainly in distributive shock like septic shock.

***Note*:**

- Dopamine improves renal and splanchnic blood
- Dobutamine improves the cardiac output
- Adrenaline/Levarterenol IV in anaphylaxis
- Amrinone and milrinone are newer inotropic drugs



Fig. 1.173: Trendelenburg position—head down position, used in patient in shock.

- Correction of acid base balance. Acidosis is corrected by using 8.4% sodium bicarbonate intra venously.
- *Steroid* is often life saving. 500–1000 mg of hydrocortisone can be given. It improves the perfusion, reduces the capillary leakage and systemic inflammatory effects.
- Antibiotics in patients with sepsis; proper control of blood sugar and ketosis in diabetic patients.
- Catheterisation to measure urine output (30-50 ml/hour or > 0.5 ml/kg/hour should be maintained).
- Nasal oxygen to improve oxygenation or ventilator support with intensive care unit monitoring has to be done.
- CVP line to perfuse adequately and to monitor fluid balance. TPN is given when required.
- PCWP to monitor very critical patient.
- Haemodialysis may be necessary when kidneys are not functioning,
- Control pain-using morphine (4 mg IV).
- Ventilator and ICU/ critical care management.
- Injection ranitidine IV or omeprazole IV or pantoprazole IV.
- *Activated C protein* even though costly is beneficial as it prevents the release and action of inflammatory response.
- *MAST (military anti shock trouser)—Provides circumferential external pressure of 40 mmHg. It is wrapped around lower limbs and abdomen, and inflated with required pressure. It redistributes the existing blood and fluid towards centre. It should be deflated carefully and gradually.*

Remember

- Response to dynamic fluid therapy can be checked in patient in shock by perfusing 500 ml of fluid rapidly in 10 minutes and patient is checked as non-responder / transient only initial responder or proper responder.
- Vasopressor like dobutamine is used only in distributive shock like due to sepsis (not in hypovolaemic, haemorrhagic shock where there is low preload).
- Intubation and ventilator may be needed in shock.
- The patient is monitored with ECG, pulse oximetry, blood pressure/invasive blood pressure, CVP/PCWP, urine output, pupillary reaction (dilated or not), serum electrolytes, arterial PO_2 and PCO_2 analysis.

Excuses are the nails used to build a house of failure.

CENTRAL VENOUS PRESSURE (CVP)

It is a method to measure the right atrial pressure by placing a venous catheter (20 cm) into the SVC. Commonly for CVP monitoring, a venous catheter is passed through internal jugular vein or infraclavicular subclavian vein to the SVC (used for TPN purpose). Occasionally a long catheter (60 cm) can be passed through basilic vein (not commonly done). Under radiological guidance, initially a needle is passed 3 cm above the medial end of the clavicle, in the hollow between the two heads of sternomastoid muscles, directing towards the suprasternal notch into the right internal jugular vein. Then through a guide wire, a venous catheter is passed into the SVC through right internal jugular vein, which can also be confirmed by changes in flow during inspiration and expiration.

Catheter is connected to saline manometer, taking manubriosternal angle (angle of Louis) as zero point.

Normal value is 2-10 cm of saline.

If less than 2 cm, more fluid is infused.

If more than 10 cm, fluid infusion should be restricted.



Fig. 1.174: CVP cannula. Note the location of tip of CVP line in the SVC (or can be in the right atrium).

Complications of CVP

- Pneumothorax
- Haemothorax
- Injury to brachial plexus and vessels
- Bleeding
- Sepsis
- Catheter displacement

PULMONARY CAPILLARY WEDGE PRESSURE (PCWP)

It is a better indicator of circulating blood volume and left ventricular function.

Catheter used is *Swan Ganz* triple channel pulmonary artery balloon catheter.



Fig. 1.175: CVP line for monitoring and perfusing the patient in shock.

It is used to –

- Differentiate right and left ventricular failure, pulmonary embolus, septic shock
- To measure and monitor cardiac output during the use of inotropic agents, vasodilators and fluid therapy

Procedure

Under strict aseptic precaution, using cannula and guide wire, catheter is passed through internal jugular vein, into the right atrium. Balloon is inflated by 1.5 ml of air and then negotiated into pulmonary artery, until it reaches a small branch and wedges it. Pressure at this point is called as *pulmonary capillary wedge pressure.*

PCWP normally is 8-12 mmHg, considering mid axillary point as zero reference point.

After that, balloon is deflated to get pulmonary artery pressure which is normally 25 mmHg systolic and 10 mmHg diastolic.

PCWP catheter can be kept *in situ* only for 72 hours.

Complications

- Arrhythmias
- Pulmonary artery rupture
- Balloon rupture
- Pulmonary infarction
- Pneumothorax
- Haemothorax
- Bleeding, sepsis, thrombosis



Fig. 1.176: Pulmonary Capillary Wedge Pressure. Note the wedged balloon in the tip of the venous catheter in the pulmonary arteriole.

SYSTEMIC INFLAMMATORY RESPONSE SYNDROME (SIRS)

SIRS is body's systemic response to an infected wound. It causes either hyperthermia (>38°C) or hypothermia (< 36°C); tachycardia (pulse > 90 / minute); tachypnoea (> 20 / minute); total white cell count > 12,000 / cu mm.

- It is final common pathway in shock due to any cause (trauma, sepsis, endotoxaemia, burns) where there is failure of inflammatory localization with vasodilatation, increased endothelial permeability with damage, thrombosis, leucocyte migration and activation.
- It is associated with release of free radicals, abnormal arachidonic acid release, cytokine release, neutrophil sequestration, abnormal NO synthesis, complement activation, DIC.
- It is a part of severely decompensated *reversible shock* which eventually leads to MODS (Multi organ dysfunction syndrome), a state of *irreversible shock* wherein patient is anuric, drowsy, cold and terminally ill.
- SIRS carries poor prognosis.

Distributive shock is sudden change in vascular capacity leading to shock like in anaphylaxis and adrenal crisis.

OXYGEN THERAPY

Indications

1. Chest injuries, any severe haemorrhage.
2. Gas gangrene with toxic haemolysis.
3. Coal gas poisoning.
4. Over morphinisation.
5. Pulmonary embolism and fat embolism.
6. Spontaneous pneumothorax, pulmonary oedema, cardiac infarction, pneumonia, cor pulmonale.
7. Cardiogenic shock and acute bronchitis.

27% Oxygen is delivered through ventimask (disposable polythene mask) at a rate of 4-6 litres per minute. Oxygen is also given along with positive pressure ventilation.

HYPERBARIC OXYGEN

It is administration of oxygen 1 or 2 atmospheres above the atmospheric pressure in a compression chamber. It increases the arterial oxygen saturation so that oxygen perfusion of tissues will be increased.

Differences between CVP and PCWP

CVP	*PCWP*
1. Technically easier	1. Requires skilled experts
2. Normal pressure is 2-10 cm of saline	2. 8-12 mmHg
3. Gives gross idea about fluid balance	3. Better and specific
4. Left ventricular function is not assessed	4. Left ventricular function is very well-assessed
5. Not used to differentiate between right and left ventricular function	5. Very well-differentiated
6. Can be kept *in situ* as long as desired	6. Can not be kept *in situ* for more than 72 hours
7. Catheter tip is in SVC	7. Catheter tip is in pulmonary capillary with wedging
8. Plain tip catheter	8. 1.5 ml air filled balloon tip
9. Can be used for TPN, fluid infusion etc	9. Can not be used for TPN, or fluid infusion
10. Complications are easy to tackle	10. Often difficult to tackle
11. Not as sensitive and specific as PCWP	11. Sensitive and specific

Hope puts a smile on our face when the heart cannot manage.

Indications

1. Carbon monoxide poisoning.
2. Tetanus, gas gangrene infections.
3. Bedsores, frostbites, necrotising fasciitis.
4. Drenching in paralytic ileus to reduce the nitrogen gas in distended bowel.
5. As a radiosensitizer in the treatment of cancer.

Complications

- Cerebral gas embolism.
- Rupture of tympanic membrane.
- Visual defects.
- O_2 toxicity.
- CO_2 narcosis.
- Respiratory depression.

Contraindication

- Asthma/emphysema.
- High fever.
- Chronic sinusitis.
- Viral infection.
- Pregnancy.

TOPICAL O_2–THERAPY

H_2O_2 to release nascent oxygen in ulcers and abscess.

CARDIAC ARREST

It is the cessation of the heart. Heart stops contracting.

Causes: All causes for shock.

Features of cardiac arrest

- No palpable pulse
- Heart sounds not heard
- Cessation of respiration—cyanosis occurs
- Development of unconsciousness
- Pupils start dilating

Critical period

Once heart and lungs stop, *brain death occurs in 3 minutes*.

Immediate measures—

- **A**irway
- **B**reathing
- **C**ardiac compression
- **D**rugs and **D**efibrillator
- **E**CG, **E**ndotracheal tube and **M**onitor

1. **External cardiac compression (massage)**— Patient is laid flat on a *hard surface (never on soft surface)*. Manual compression is exerted over the lower sternum using both hands one over other without bending the elbow at a rate of 60 to 70 per minute. Rib cage damage during procedure can be very well ignored. (Heel of right hand is placed over the sternum 8 cm above xiphoid process and left hand is placed over it).
2. Another person at the same time should give *mouth to mouth breathing* at a rate of 20 to 30 per minute after clearing the airway by removing froth and dentures. A bag with mask can be used to ventilate using air or oxygen.
3. Endotracheal intubation and ventilator support.
4. Injection of 1:10,000 adrenaline and 10% calcium chloride intravenously.
5. Sodium bicarbonate 8.4% injection, hydrocortisone injection.
6. Defibrillator, if there is ventricular fibrillation.
7. Analysis of blood gas (PCO_2 and PO_2), and serum electrolytes assessment at repeated intervals.
8. Urinary catheterization, Ryle's tube insertion.
9. Monitoring the patient with BP, pulse, respiration, and temperature chart.



Fig. 1.177: Technique of external cardiac massage.

Observations to be made are —

- Groin pulse.
- Respiration and breath sounds.
- Blood pressure.
- Pupillary reaction.
- ECG activity.

Once patient recovers, the cause and sequelae has to be managed properly.



Fig. 1.178: Technique of mouth-to-mouth respiration. Note patient's nose should be held closed with right hand of the doctor/assistant and with left hand lower jaw should be pushed forward.

Sequelae are due to hypoxia and circulatory collapse

- Cerebral oedema and permanent brain damage
- ARDS (Adult respiratory distress syndrome)
- Renal failure

Internal Open Cardiac Massage

This method is used when cardiac arrest occurs in the operation theatre during surgery, acute tamponade, and acute bilateral pneumothorax.

Left side thorax is opened through a lengthy incision along 4th or 5th intercostal space. Initially heart with intact pericardium is rhythmically compressed and relaxed using left hand against sternum. Mean while costal cartilages above and below are cut with a knife to have a better exposure. Pericardium is opened in front of the phrenic nerve. Direct cardiac massage is undertaken until heart regains its function and later shifted to ventilatory support and critical care.

Defibrillation Technique

Apply gelly to the site of electrodes. One electrode at the base of heart to the right of the sternum other over the estimated area of the apex of the heart. ***Ensure that nobody is in contact with the patient***. Activate the defibrillator. Resume ventilation and ECG monitor immediately. After that, monitor continuously, correct the acidosis, catheterise and observe urine output. Arrange for ICU care.



Fig. 1.179: Left thoracotomy for open internal cardiac massage.



Fig. 1.180: Defibrillator used in case of cardiac arrest.

Self-assessment Questions

- Shock—pathogenesis, clinical features, management
- Septic shock.
- Endotoxic shock.
- Cardiac-compression shock.
- CVP.
- PCWP.
- Differences between CVP and PCWP.
- SIRS.
- MODS.
- Oxygen therapy.

Today's preparations determine tomorrow's achievement.

Haemorrhage and Blood Transfusion

> ***There are canals (or vessels) in it (the heart) to (every) member. Now if the priests of Sekhmet or any physician put his hands (or) his fingers (upon the head, upon the back of the) head, upon the two hands, upon the pulse, upon the two feet, (he) measures the heart, because its vessels are in the back of the head and in the pulse; and because its (pulsation is in) every vessel of every member.***
>
> **—(Anonymous),** Circa 2500 BC

Haemorrhage—*classification, pathophysiology, management*
Blood transfusion
Blood substitutes
Massive blood transfusion
Autologous blood transfusion
Tourniquets

HAEMORRHAGE

CLASSIFICATION

I. Based on the source of bleeding:

a. ***Arterial*** is bright red in colour, spurting like jet along with pulse of the patient.

b. ***Venous*** is dark red, steady and continuous flow. Blood loss may be severe and rapid when bleeding is from femoral vein, jugular vein, other major veins, varicose veins, portal vein, oesophageal varices.

Pulmonary arterial blood is dark red in colour and pulmonary venous blood is bright red in colour.

c. ***Capillary:*** Here bleeding is rapid and bright red. It is often torrential due to continuous ooze.

II. Based on the time of onset of bleeding in relation to any operative procedure:

1. ***Primary:*** Occurs at the time of injury or operation.
2. ***Reactionary:*** It occurs within 24 hours after surgery or after injury.(commonly in 4-6 hours).

Precipitating factors	*Common causes*
Coughing	Thyroid surgery
Vomiting	Cholecystectomy
Straining	Major abdominal surgeries
Rise of blood pressure	Circumcision
Restlessness	Hydrocele surgery
Venous refilling during recovery from anaesthesia.	Tonsillectomy
Slipping of ligature	
Clot dislodgement.	

3. ***Secondary:*** It occurs in 7-14 days after surgery.

Factors	*Common causes*
Infection	Erosion of carotid artery by cancer (secondaries in the neck)
Pressure by drain or bone	Haemorrhoidectomy
Malignancy	Inguinal block dissection

III. Based on the type of haemorrhage:

Revealed haemorrhage	*Concealed haemorrhage*	*Initially concealed but later revealed*
It is visible external haemorrhage	It constitutes internal haemorrhage. • Liver injury • Spleen injury • Fracture femur • Ruptured ectopic gestation • Cerebral haemorrhage • Haemothorax	• Haematemesis • Melaena • Haematuria

IV. Based on the duration of haemorrhage:

1. ***Acute haemorrhage:*** It is sudden, severe haemorrhage after trauma, surgery.
2. ***Chronic haemorrhage:*** It is chronic repeated bleeding for a long period like in haemorrhoids, bleeding peptic ulcer, carcinoma caecum etc. They present with chronic anaemia with hyperdynamic cardiac failure. They are in a state of chronic hypoxia. It is corrected by *packed cell transfusion* not by whole blood itself. Cause has to be treated accordingly.
3. ***Acute on chronic haemorrage:*** It is more dangerous as the bleeding occurs in individuals who are already hypoxic, which may get worsened faster.

V. Based on the possible intervention:

1. *Surgical haemorrhage* – can be corrected by surgical intervention.
2. *Non-surgical haemorrhage* – is diffuse ooze due to coagulation abnormalities and DIC.

Pathophysiology of Haemorrhage

Bleeding
↓
Hypovolaemia
↓
Low cardiac output
↓
Tachycardia and shunting of blood from splanchnic vessels by venoconstriction so as to maintain perfusion of vital organs like brain, heart, lungs, kidneys.
↓
Hypoxia
↓
Activation of cardiac depressants
↓
Anaerobic metabolism and altered cell membrane function causing influx of more sodium and calcium inside the cell and potassium comes out of the cell
↓
Hyponatraemic, hyperkalaemic, hypocalcaemic metabolic acidosis.
↓
Lysosomes of cell get lysed releasing powerful enzymes which is lethal to cell itself
↓
SICK CELL SYNDROME

Platelets and coagulants are activated leading to formation of small clots DIC and further bleeding.
↓
Progressive haemodilution leading to ***total circulatory failure.***

Initially there is compensatory hypovolaemic shock and later there is decompensatory hypovolaemic shock which will lead to MODS and death.

DIC, acidosis and hypothermia are the major factors in worsening the situation in haemorrhage.

Classification of haemorrhagic shock (circulatory failure)

Class	Blood loss	Features
I	Up to 15% (< 750 ml)	Normal
II	Blood loss 15-30% (750-1500 ml)	Palor, thirsty, tachycardia
III	Blood loss 30-40% (1500-2000 ml).	Hypotension, tachycardia, oliguria, confusion
IV	Blood loss > 40% (> 2000 ml).	Rapid pulse, low BP, anuria, unconsciousness, MODS

Clinical Features of Haemorrhage

- Pallor, thirsty.
- Cyanosis.
- Tachycardia.
- Tachypnoea.
- Air hunger.
- Cold clammy skin due to vasoconstriction.
- Dry face, dry mouth and goose skin appearance (due to contraction of arrector pilorum).
- Rapid thready pulse.
- Oliguria.
- Features related to specific causes.
- Hypotension.

Signs of significant blood loss-

- Pulse > 100/minute
- Systolic BP< 100 mmHg
- Diastolic BP drop on sitting or standing > 10 mmHg
- Pallor/ sweating
- Shock index (ratio of pulse rate to blood pressure) > 1

Measurement of Blood Loss

- Clot size of a clenched fist is 500 ml.
- Blood loss in a closed tibial fracture is 500-1500 ml; in a fracture femur is 500-2000 ml.
- Weighing the swab before and after use is an important method of on-table assessment of blood loss.

Rains Factor

$$\text{Total amount of Blood loss} = \left\{ \begin{array}{l} \text{Total difference in swab weight} \times 1.5 \\ \quad\quad\text{or} \\ \text{Total difference in swab weight} \times 2 \\ \text{(For larger wounds and larger operations)} \end{array} \right.$$

- Hb% and PCV estimation.
- Blood volume estimation using radioiodine technique or micro haematocrit method.
- Measurement of CVP or PCWP.
- Investigations specific for cause: U/S abdomen, Doppler and often angiogram in vascular injury, chest X-ray in haemothorax, CT scan in major injuries, CT scan head in head injuries.

Effects of haemorrhage

- Acute renal shut down
- Liver cell dysfunction
- Cardiac depression

No problem is too large for God's intervention and no person is too small for God's attention.

- Hypoxic effect
- Metabolic acidosis
- GIT mucosal ischaemia
- Sepsis
- Interstitial oedema, AV shunting in lung- ARDS
- Hypovolaemic shock- MODS

Treatment

- Restoration of blood loss: By blood transfusion, albumin 4.5%, SAG-M blood, saline, Haemaccel (Gelatin), dextran, plasma infusions.
  Note: One unit of blood should raise 1 gm% of haemoglobin.
- Catheterisation, foot end elevation, monitoring.
- Oxygen support/intubation/ventilator and critical care.
- Pressure and packing.
- Wound exploration and proceeding, i.e. ligation of the small vessel, suturing the wound part, vessel suturing (anastomosis), excision of the tissues.
- Absolute rest, analgesics, morphine 10-20 mg IM/IV to relieve pain, sedation.
- ICT placing for haemothorax.
- Laparotomy for liver or spleen or mesentery or bowel injuries, suturing, splenectomy.
- Topical applications for local ooze — Oxycel, gauze soaked with adrenaline, bone wax for oozing from bone and other local haemostatic agents (collagen, thrombin).
- In venous haemorrhage, elevation, ligation of vein or in case of large vein suturing of venous wall, pressure bandaging, packing will be helpful.
- Tourniquet are often used in operation theatre for control of haemorrhage in limbs. But it is not advisable as a first aid measure.
- TPN, CVP monitoring, electrolyte management are all equally important.
- Steroid injection, antibiotics, ventilator support are often required.

Management concepts

- Confirm shock, hypovolaemia and haemorrhage by clinical assessment
- Immediate resuscitation by blood, oxygen, fluid
- Identify site of haemorrhage – ultrasound, endoscopy, CT scan, diagnostic peritoneal lavage (DPL), blood tools
- Control of haemorrhage – surgery, endoscopic control, therapeutic embolisation
- Definitive treatment if any
- Sepsis control
- Prevention of coagulopathy by FFP, platelet concentrate, fresh blood
- Critical care management
- End point resuscitation, fluid and electrolyte management, prevention of organ failure

Local haemostatic agents:

- Gelatin sponge (Gel foam)
- Oxidised cellulose (Surgicel)
- Collagen sponge (Helistat)
- Microfibrillar collagen (Avitene)
- Topical thrombin
- Bone wax (derived from bees wax + almond oil)
- Gelatin matrices (Floseal)
- Topical EACA, topical cryoprecipitate

BLOOD TRANSFUSION

> ***This noon I met with Mr. (Robert) Hooke, and he tells me the dog which was filled with another dog's blood at the (Gresham) College the other day, is very well, and like to be so as ever. And doubts not its (i.e. blood transfusion) found being of great use to men.***
>
> —**Samuel Pepys,** 1666

Indications

- Acute blood loss following trauma, >15% of total body volume in otherwise healthy individuals (liver, spleen, kidney, GIT injuries, fractures, haemothorax, perineal injuries).
- During major surgeries—Abdominoperineal surgery, thoracic surgery, hepatobiliary surgery.
- Following burns.
- In septicaemia.
- As a prophylactic measure prior to surgery.
- Whole blood is given in acute blood loss.
- Packed cells are given in chronic anaemia.
- Blood fractions are given in ITP, haemophilias.

Donor Criteria

- Donor should be fit without any serious diseases like HIV1 and HIV2 and hepatitis infections and malaria.
- Weight of donor should be more than 45 kg.

Collection of Blood

Blood is collected in a sac containing 75 ml of CPD (Citrate Phosphate Dextrose) solution and stored in special refrigerators at 4 degree celcius. CPD blood lasts for 3 weeks.

In stored blood

1. RBC's last for 3 weeks
2. WBC's are destroyed rapidly
3. Platelets also get reduced in 24 hours
4. Clotting factors are labile and so their levels fall quickly

Blood Fractions

1. *Packed cells*
   - It is obtained by centrifuging whole blood at 2000-2300 g for 15-20 minutes.
   - It is used in chronic anaemias, in old age, in children.
   - It minimises the cardiac overload due to transfusion.
   - It can be stored for 35 days at 1°C-6°C.
2. *Plasma:*
   - This is obtained in the same way as packed cells by centrifugation.
   - It is indicated in *burns, hypoalbuminaemia, severe protein loss*
   - It can be fractionalised into different fragments:
     a. ***Human albumin 4.5%*** is obtained after repeated fractionations and can be stored for several months in liquid form at 4°C**.**
     b. ***Fresh frozen plasma (FFP)*****:** Fresh plasma obtained, is rapidly frozen and stored at –40°C. It contains all coagulant factors. 1 unit of FFP increases the clotting factors levels by 3%. It can be stored for 2 year. Rhesus D positive FFP can be transfused to Rhesus D negative female.
        Uses:
        - Severe liver disease with abnormal coagulation function.
        - Congenital clotting factor deficiency
        - Deficiency following warfarin therapy, DIC, massive transfusion.
     c. ***Cryoprecipitate*****:** When fresh frozen plasma is allowed to thaw at 4°C, visible white supernatant layer develops and is called as cryoprecipitate which is rich in Factor VIII and fibrinogen. It is stored at minus 40°C and can be kept for 2 year.
     d. ***Fibrinogen*** is obtained by organic liquid fractionation of plasma and is stored in dried form. It is very useful in DIC and afibrinogenaemia. It has risk of transmitting hepatitis.
3. ***Platelet rich plasma***: It is obtained by centrifugation of freshly donated blood at 150-200 g for 15-20 minutes.
4. ***Platelet concentrate:*** It is prepared by centrifugation of platelet rich plasma at 1200-1500 g for 15-20 minutes. Used in thrombocytopenia and drug (aspirin, clopidogrel) induced haemorrhage.
5. ***Prothrombin complex concentrate (PCC)*** are derived from pooled plasma which contains factors II, IX and X; used in emergency reversal of warfarin therapy in uncontrolled haemorrhage.

SAG-M Blood

A proportion of donations will have plasma removed and will be replaced by crystalloid solution of SAG-M.

S — Sodium chloride.
A — Adenine.
G — Glucose anhydrate.
M — Mannitol.

Advantages

- *This allows good viability of cells*
- *But it is devoid of any protein*
- *It is very useful in anaemias*

Precautions

- For every four units of SAG-M blood, one whole blood has to be given.
- Later for every two units of SAG-M blood, one unit (400 ml) of 4.5% human albumin has to be given.
- Coagulation status and platelet count should be checked regularly.

After grouping and cross matching, 540 ml of blood is transfused in 4 hours (40 drops per minute), using a filtered drip set.

One litre of blood contains 350 mg of Iron. Normal excretion of iron is 1 mg/day. Iron overload can occur after many transfusions. Iron excretion can be increased by desferrioxamine infusion.

Complications of blood transfusion

1. Congestive cardiac failure
2. Transfusion reactions
   - Incompatibility. Major and minor reactions with fever, rigors, pain, hypotension
   - Pyrexial reactions due to pyrogenic ingredients in the blood
   - Allergic reactions
   - Sensitisation to leukocytes and platelets
   - Immunological sensitisation

Every obstacle introduces a person to himself.

3. Infections
   - Serum hepatitis
   - HIV infection
   - Bacterial infection
   - Malaria transmission
   - Epstein barr virus infection
   - Cytomegalo virus infection
   - Syphilis, Yersinia
   - Babesia microti infection
   - Trypanosoma cruzi infection
4. Air embolism
5. Thrombophlebitis
6. Coagulation failure
   - Dilution of clotting factors
   - DIC
   - Dilutional thrombocytopenia occurs in patients with massive blood transfusion
7. Circulatory overload causing heart failure
8. Haemochromatosis in patients with CRF receiving repeated blood transfusions
9. Citrate intoxication causes bradycardia and hypocalcaemia. For every four units of blood 10 ml of 10% calcium chloride or gluconate should be infused intravenously
10. Iron overload

BLOOD SUBSTITUTES

- ***Human albumin*** **4.5%**
  There is no risk of transmitting hepatitis.
- ***Dextrans*** are useful to improve plasma volume. They are polysaccharides of varying molecular weights.
  a. *Low molecular weight dextran* (40,000 mol wt.) (*Dextran 40, Rheomacrodex*).
     Dextran 40 is very effective in restoring blood volume immediately. But small molecules are readily excreted in kidney and so effect is transitory. It may be useful in prevention of sludging in kidney and hence renal shut down.
  b. *High molecular weight dextran* (*Dextran 110 and Dextran 70*)

  Less effective but long acting and so useful to have prolonged effect.

Precautions

1. Blood samples for blood group and cross matching should be taken before giving dextrans as it interferes with rouleaux formation of red cells.
2. Dextrans also interfere with platelet function and so may precipitate abnormal bleeding.
3. Total volume of Dextrans should not exceed 1000 ml.

- ***Gelatin,*** in a degraded form of mol. wt. 30,000S, is used as a plasma expander. Up to 1000 ml of 3.4-4% solution containing anions and cations is given intravenously—***Haemaccel.***

MASSIVE BLOOD TRANSFUSION

- It is defined as *replacement or transfusion of blood equivalent to patient's blood volume in < 24 hours corresponding to that particular age (In adult it is 5-6 litres, in infants it is 85 ml/kg body weight.)* Or single transfusion of blood more than 2,500 ml continuously.
- Massive transfusion is used in severe trauma associated with liver, vessel, cardiac, pulmonary, pelvic injuries. Often it is required during surgical bleeding (primary haemorrhage on table) of major surgeries.
- Adverse effects of massive transfusion
  a. Severe electrolyte imbalance (hypocalcaemia, hyperkalaemia, acidosis).
  b. Coagulopathy—altered platelet and coagulation factors.
  c. Citrate toxicity.
  d. Hypothermia.
  e. Poor oxygen delivery.
  f. Infections.
  g. Incompatibility and transfusion reactions.
  h. ARDS.

AUTOLOGOUS BLOOD TRANSFUSION

An healthy individual with no infection and haematocrit of > 30% can predonate blood few weeks prior to any elective surgeries which in turn can be used at the time of surgery.

RECYCLED BLOOD

In major surgeries if there is significant blood loss, then patient's bled blood is carefully sucked out through a sterile system and is filtered and reused again to the patient. This will reduce the number of transfusions.

ARTIFICIAL BLOOD

1. Perfluorocarbon (Fluosoleda) - abiotic substitute as synthetic oxygen carrier.
   - It has got high affinity for O_2.
   - It is inert.
   - It is biocompatible.
2. Stroma free haemoglobin - biomimetic haemoglobin based substitute.
3. Chelates which reverse bound O_2.
   - Intraoperative–salvage of blood: On table blood is collected, washed, filtered and transfused. Used in trauma.

ERYTHROPOIETIN injection 1000-3500 units preoperatively also used to increase the RBC count.

It is used in CRF patients who are on haemodialysis. It is given twice weekly but it is costly.

TOURNIQUETS

Tourner means to turn (Greek). A tourniquet is used to cut off the blood supply to a limb temporarily so that a bloodless field is created while performing the surgery. Limb should be exsanguinated before applying / inflating the cuff of the tourniquet. It is done using a bandage or pressurized Rhys- Davis exsanguinator. A tourniquet is applied in mid thigh above the knee joint in lower limb and in mid biceps level above the elbow in upper limb. It should not be closer to joints. It is not applied over the forearm or leg. It is applied over layers of gauze or cotton, not over a bare skin. Pressure used in upper limb is 250 mm Hg; lower limb is 500 mm Hg (In children, it is 150 and 250 mm Hg for upper and lower limbs respectively).

Uses

- To attain bloodless field in limb surgeries—upper and lower limbs, orthopaedic surgeries, soft tissue tumours, amputations.
- It is used (rubber tourniquet) to access veins for IV injections and IV sampling.
- Tourniquet is used in diagnostic tests for varicose veins, purpura (ITP), carpal tunnel syndrome, tetany.
- It is used as a first aid in bleeding conditions of limbs, snake bite (it is controversial).
- Tourniquets are often used for small procedures in fingers and toes.

Types

- **Rubber tourniquet:** Simple red rubber catheter is used for drawing blood, to have access to veins.
- Martin's tourniquet made up of India rubber.
- **Pneumatic tourniquet:** Used in limbs, will give the arterial pressure and also acts as a tourniquet. (Sphygmomanometer cuff is simpler and easily available type).
- Esmarch rubber **elastic bandage tourniquet.**
- Conn pneumatic tourniquet is manually operated tourniquet where air is pumped upto the required pressure.
- Specialized sophisticated tourniquets are available which gauge pressure and time accurately - automatic tourniquet.

Tourniquet time for upper limb is one hour and for lower limb is two hours

Contraindications

- In all peripheral vascular diseases and atherosclerosis.



Fig. 1.181: Esmarch rubber tourniquet.



Fig. 1.182: Automatic gauged pressure tourniquet.

- Infection.
- Deep venous thrombosis.
- Crush injuries.
- Sickle cell disease.

Complications

- Crushing effect on muscles in thigh occurs leading to crush syndrome.
- Tourniquet palsy in upper limb (radial nerve involvement) - neuropraxia.
- Infection.
- Improper application of tourniquet leads to more bleeding.
- Forgetting the removal of tourniquet or taking more time to release may compromise the blood supply of the limb leading to severe ischaemia and gangrene.
- Skin blistering and necrosis.

Self-assessment Questions

- Pathophysiology, classification and management of blood loss.
- Rains factor.
- Reactionary haemorrhage.
- Blood substitutes.
- Complications of blood transfusion.
- Massive blood transfusion.
- Tourniquets.

The very act of believing creates strength of its own.

Burns

> ***The infusion of large quantities of fluid, mainly a salt solution, as many as 3-4 litres daily, has proved satisfactory. Sometimes a life is saved if not more than one-quarter of the body surface has received a third-degree burn…. I have given blood transfusions to two patients with severe burns, with recovery in one case and postponement of death in the other.***
>
> —**Gustav Riehl**, 1925

Burns—*Types, classification, pathophysiology, management, complication*
Complications of burns contracture
Electrical burns
Inhalation injury
Chemical burns

BURNS

Types of Burns

- Thermal injury
  - Scald – spillage of hot liquids
  - Flame burns
  - Flash burns due to exposure of natural gas, alcohol, combustible liquids
  - Contact burns – contact with hot metals/objects/materials
- Electrical injury
- Chemical burns – acid/alkali
- Cold injury — frost bite
- Ionising radiation
- Sun burns

Classification of Burns

Depending on the Percentage of Burns

Mild (Minor):

- Partial thickness burns < 15% in adult or <10% in children.
- Full thickness burns less than 2%.
- Can be treated on outpatient basis.

Moderate:

- Second degree of 15-25% burns (10-20% in children).
- Third degree between 2-10% burns.
- Burns which are not involving eyes, ears, face, hand, feet, perineum.



Figs 1.183A and B: Percentage of burns in (A) Adults (B) Children

Rule of Nine (Wallace's rule of "9")

	Adults	*Children*	*Infants*
Head and neck	9%	18%	20%
Front of chest and abdominal wall	9 × 2 = 18%	18%	10 × 2 = 20%
Back of chest and abdominal wall	9 × 2 = 18%	18%	10 × 2 = 20%
Lower limb	18 × 2 = 36%	13.5 × 2 = 27%	10 × 2 = 20%
Upper limb	9 × 2 = 18%	18%	10 × 2 = 20%
Perineum	01%	01%	
	100%	100%	100%

Note: It is head and lower limb percentage which differ in adults and children.

Major (severe):

- Second degree burns more than 25% in adults, in children more than 20%.
- All third degree burns of 10% or more.
- Burns involving eyes, ears, feet, hands, perineum.
- All inhalation and electrical burns.
- Burns with fractures or major mechanical trauma.



Fig. 1.184: Second degree burns with blisters.



Fig. 1.185: Extensive burns more than 50%.



Fig. 1.186: Degrees of burns.

I. Depending on thickness of skin involved

a. ***First degree*****:** Here the epidermis looks red and painful, no blisters, heals rapidly in 5-7 days by epithelialization without scarring.

b. ***Second degree***: The affected area is mottled, red, painful, with blisters, heals by epithelialization in 14-21 days.
   - Superficial second degree burn heals, causing pigmentation.
   - Deep second degree burn heals, causing scarring, and pigmentation.

c. ***Third degree***: The affected area is charred, parchment like, painless and insensitive, with thrombosis of superficial vessels. It requires grafting. Charred, denatured, insensitive, contracted full thickness burn is called as **eschar.** These wound must heal by re-epithelialization from wound edge.

d. ***Fourth degree***: Involves the underlying tissues—muscles, bones.

II. Depending on thickness of skin involved

a. ***Partial thickness burns:*** It is either first or second degree burn which is red and painful, often with blisters

b. ***Full thickness burns:*** It is third degree burns which is charred, insensitive, deep involving all layers of the skin.

Assessment of Burns

- Wallace's rule of nine is used for early assessment – refer figure.
- *Using the Lund and Browder chart* is better method for assessing the burns wound. Here each part of the body is individually assessed for involvement of burns.

44°C temperature takes 6 hours to cause deep burns. 65°C takes 45-60 seconds to cause deep full thickness burn.

Clinical Features

- H/o burn.
- Pain, burning, anxious status, tachycardia, tachypnoea, fluid loss.
- In severe degrees features of shock.

Tolerable temperature to human skin is 40°C for brief period.

Success lies not in achieving what you aim at, but in aiming at what you ought to achieve.



Fig. 1.187A: Burns in a child.



Fig. 1.187B: Face burns in an adult—severe 3rd degree.

Pathophysiology

Heat causes coagulation necrosis of skin and subcutaneous tissue.

↓

Release of vasoactive peptides

↓

Altered capillary permeability

↓

Loss of fluid → **Severe hypovolaemia**

↓

Decreased cardiac output → Decreased myocardial function

↓

Decreased renal blood flow (Renal failure) → Oliguria

↓

Altered pulmonary resistance causing pulmonary oedema

↓

Infection

↓

Systemic Inflammatory Response Syndrome (SIRS)

↓

Multi Organ Dysfunction Syndrome (MODS).



Fig. 1.188: Burn zones — (Jackson's).

Massive oedema in the body is due to altered pressure gradient because of the injury to basement membrane.

Cardiac dysfunction is due to:
- Hypovolaemia.
- Release of cardiac depressants.
- Hormonal causes like catecholamines, vasopressin, angiotensins.

Renal changes are due to:
- Release of ADH from posterior pituitary to cause maximum water reabsorption.
- Release of aldosterone from adrenals to cause maximum sodium reabsorption.
- Toxins released from the wound along with sepsis causes acute tubular necrosis.
- Myoglobin released from muscles (in case of electric injury or often from eschar) is most injurious to kidneys.

Pulmonary changes are due to:
- Altered ventilation-perfusion ratio.
- Pulmonary oedema due to burn injury, fluid overload, inhalation injury.
- ARDS.
- Aspiration.
- Septicaemia.

Assessment of airway injury is important in burns
- Occurs in burns around face and neck, or trapped in burning room
- Presents with hoarseness or stridor
- Inhaled burning gases can cause upper airway burns and laryngeal oedema
- Smoke inhalation can cause chemical alveolitis, pulmonary oedema, ARDS and respiratory failure
- Steam inhalation can cause damage to respiratory epithelium and subglottic oedema
- Carbon monoxide inhalation more than 10% is dangerous as it forms carboxyhaemoglobin (CO has

got 240 times more affinity to haemoglobin than oxygen) which blocks oxygen transport completely causing respiratory arrest, hypoxia and metabolic acidosis.

- Chest wall burn causes mechanical block of ventilation – needs escharotomy in chest wall and procedure is painless
- Airway burn may require early elective intubation or tracheostomy or emergency cricothyroidotomy as a life saving method

GIT changes are due to:

- *Acute gastric dilatation* which occurs in 2-4 days.
- Paralytic ileus.
- Curling's ulcer.
- Cholestasis and hepatic damage.

Metabolic Changes

- Hypermetabolic rate (BMR).
- Negative nitrogen balance.
- Electrolyte imbalance.
- Deficiencies of vitamins and essential elements.
- Metabolic acidosis due to hypoxia and lactic acid.

Infections are commonly due to:

- Streptococci - (Beta haemolytic – commonest)
- *Pseudomonas*
- *Staphylococci*
- Other gram-negative organisms
- *Candida albicans*



Fig. 1.189: Burns over chest wall with eschar. Note the extent of involvement.



Fig. 1.190: Deep burns face with eyelid involvement.



Fig. 1.191: Second degree burns in the leg with blebs.

Effects of Burn Injury

1. Shock due to hypovolaemia.
2. Renal failure.
3. Pulmonary oedema, respiratory infection, adult respiratory distress syndrome (ARDS), respiratory failure.
4. Infection by *Staphylococcus aureus*, beta haemolytic *Streptococcus*, *Pseudomonas*, *Klebsiella* leads to bacteraemia, septicaemia. Fungal and viral infections of dangerous types can also occur.
5. GIT: Hypovolaemia, ischaemia of mucosa, erosive gastritis—**Curling's ulcer (seen in burns > 35%).**
6. Fluid and electrolyte imbalance.
7. Postburn immunosuppression predisposes to severe opportunistic infection.
8. Eschar formation and its problems like defective circulation, ischaemia when it is circumferential.
9. Electrical injuries often cause fractures, major internal organ injury, convulsions.
10. Development of contracture is a late problem. It leads to ectropion, microstomia, disability of different joints, defective hand functions, growth retardation causing shortening.

Life's disappointments are opportunity's hidden appointment.

11. Inhalation burn causes pulmonary oedema, respiratory arrest, ARDS.
12. Chemical injury causes severe GIT disturbances like erosions, perforation, stricture oesophagus (**alkali**), pyloric stenosis (**acid**), mediastinal injury.
13. Other problems commonly seen are DVT, pulmonary embolism, urinary infection, bed-sores, severe malnutrition with catabolic status, respiratory infection.
14. Complications of burns contracture itself like hypertrophic scar, keloid formation.
15. **Toxic shock syndrome:** It is a life-threatening exotoxin mediated disease caused by *Staphylococcus aureus*. It is common in children, presents with rashes, myalgia, diarrhoea, vomiting, and multi-organ failure with high mortality.

Causes of death in burns

a. Hypovolaemia and shock
b. Renal failure
c. Pulmonary oedema and ARDS
d. Septicaemia
e. Multiorgan failure



Fig. 1.192: Burns hand both palmar and dorsal aspect.



Fig. 1.193: Deep burn in the scalp involving extensively.

MANAGEMENT OF BURNS

First Aid

- Stop the burning process and keep the patient away from the burning area.
- Cool the area with tap water by continuous irrigation for 20 minutes (not cold water as it can cause hypothermia).

Indications for admission in burns

- Any moderate and severe burns
- Airway burns of any type
- Burns in extremes of age
- All electrical/deep chemical burns

Initial management

- Clothing should be removed
- Cooling of the part by running water for 20 minutes
- Cleaning the part to remove dust, mud etc
- Chemoprophylaxis – tetanus toxoid; antibiotics; local antiseptics
- Covering with dressings by different methods
- Comforting with sedation and pain killer

Definitive Treatment

- Admit the patient.
- Maintain Airway, Breathing, Circulation.
- Assess the percentage, degree, and type of burn.
- Keep the patient in a clean environment.
- Sedation and proper analgesia.
- Patient should be in ***burns unit*** (ideally air-conditioned) with barrier nursing, sterile clothes, bed sheets with all aseptic methods.

Fluid Resuscitation

Formulas to calculate the fluid replacement:

a. **Parkland regime: Commonly used**
   4 ml/% burn/kg body weight/24 hours.
   Maximum percentage considered is 50%.
   Half the volume is given in first 8 hours, rest given in 16 hours.

b. **Muir and Burclay regime:**

$$\frac{\%\text{ Burns} \times \text{Body weight in kg}}{2} = 1 \text{ Ration}$$

   3 Rations given in first 12 hours.
   2 Rations in second 12 hours.
   1 Ration in third 12 hours.

c. **Galveston regime (pediatric)**
   5000 ml/m^2 burned + 1500 ml/m^2 total

d. **Modified Brooke formula-**
   First 24 hours-
   RL: 4 ml/kg/% burns in 24 hours
   (first half in first 8 hours)
   Colloid- none.
   Second 24 hours-
   Crystalloids- to maintain urine output
   Colloids- 0.3 ml to 0.5 ml/kg/burns in 24 hours. (Albumin in RL solution) (Albumin alone should be given with care if really indicated only).

e. **Evan's formula-**
   In first 24 hours-
   Normal saline 1 ml/kg/% burns
   Colloids 1 ml/kg/% burns
   5 % dextrose in water, 2000 ml in adult.
   In second 24 hours-
   Half of the volume used in first 24 hours.

Fluids used are normal saline, ringer lactate, Hartmann fluid, plasma. Ringer lactate is the fluid of choice. Blood is transfused in later period (after 48 hours).

First 24 hours only *crystalloids* should be given. (Crystalloids are one which can pass through capillary wall like saline either hypo, iso or hypertonic, dextrose saline, ringer lactate.)

Sodium is assessed by formula: 0.52 mmol × kg body weight × % body burns, given at a rate of 4.0 to 4.4 ml/kg/hour.

After 24 hours up to 30-48 hours, *colloids* should be given to compensate plasma loss. (colloids are one which are retained in intravascular compartment). Plasma, haemaccel (gelatin), dextrans, hetastarch are used. Usually at a rate of 0.35-0.5 ml/kg/% burns is used in 24 hours.

- Urinary catheterization to monitor output; 30-50 ml/hour should be the urine output.
- Tetanus toxoid.
- Monitoring the patient: Hourly pulse, BP, PO$_2$, PCO$_2$, electrolyte analysis, blood urea, nasal oxygen, often intubation is required.
- IV Ranitidine 50 mg 8th hourly.
- **Ryle's tube insertion initially for aspiration purpose later for feeding** *(Enteral feeding).*
- Antibiotics: Penicillins, aminoglycosides, cephalosporins, metronidazole.
- Culture of the discharge; total white cell count and platelet count at regular intervals are essential to identify the sepsis along with fever, tachycardia and tachypnoea.
- In burns of oral cavity tracheostomy may be required to maintain the airway.
- **Total Parenteral Nutrition (TPN)** is required for faster recovery, using carbohydrates, lipids, vitamins ***(through a CVP line).***
- Tracheostomy/intubation tube may be required in impending respiratory failure or upper airway block.
- Intensive nursing care.

Local Management

- **Dressing** at regular intervals under general anaesthesia using paraffin gauze, hydrocolloids, plastic films, vaseline impregnated gauze or fenestrated silicone sheet or biological dressings like amniotic membrane or synthetic biobrane.
- **Open method** with application of silver sulfadiazine without any dressings, used commonly in burns of face, head and neck.
- **Closed method** is with dressings done to soothen and to protect the wound, to reduce the pain, as an absorbent.
- **Tangential excision** of burn wound with skin grafting can be done within 48 hours in patients with less than 25 % burns. It is usually done in deep dermal burn wherein dead dermis is removed layer by layer until fresh bleeding occurs. Later skin grafting is done.
- In burns of head and neck region, exposure treatment is advised.
- Slough excision is done regularly.
- **After cleaning with povidone iodine solution silver sulfadiazine** ointment is used. It is an antiseptic and soothening agent. It causes neutropenia.
  Other agents used are *Sulfamylon* (***Mafenide acetate***) and *Silver nitrate.*
  Sulfamylon is antipseudomonal and anticlostridial agent. It penetrates well in to the tissues but it is very irritant. It causes acidosis.
  Silver nitrate causes staining of burnt area.

> *If anything is sacred, the human body is sacred.*— Walt Whitman

Topical agent	*Advantages*	*Problems*
Silver sulfadiazine 1 %	- Antiseptic (G +ve and G –ve) - Soothening, good penetration, - Hydration and softening of eschar occurs	- Neutropenia, pseudoeschar - Causes hypertrophic granulation and so not used once wound is clean and eschar is separated - Causes wound maceration - It should be avoided in pregnancy, nursing mother and infants below 2 years of age
Sulfamylon – 5% (Mafenide acetate)	- Antipseudomonal, anticlostridial - Penetrates very well in to tissues	- Very irritant, painful - Causes acidosis
Silver nitrate – 0.5%	- Antiseptic	- Stains burnt area
Povidone iodine (5%)	- Antiseptic(G +ve, G –ve) - Used on granulation tissue after eschar separation - Used in perineum and buttocks to prevent maceration	- Irritant and painful - Not used in partial burns
Silver sulphadiazine and cerium nitrate	- Boosts cell mediated immunity and forms sterile eschar	

Regular culture and sensitivity for bacteria is required, to see for streptococcal growth which should be less than *1,00,000 (10^5) per gram of tissues.*

- Once the area granulates well, in 3 weeks usually, split skin grafting is done (SSG, Thiersch graft).
- For wider area MESH split skin graft is used.
- If there is eschar, escharotomy is required to prevent compression of vessels.
- In certain areas like face and ear, full thickness graft (Wolfe graft) or flap is required.

ESCHAR

- It is charred, denatured, full thickness, deep burns with contracted dermis.
- It is insensitive, with thrombosed superficial veins.
- **Circumferential eschar** in the upper limb, lower limb, neck, thorax can cause more oedema which initially causes venous compression and later arterial compression causing ischaemia, gangrene of the distal part. So distal area should be monitored for circulation.
- If required deep longitudinal full thickness incisions are made in different areas so as to prevent collection of oedema fluid and also to prevent compression over the vessels. This is called as **escharotomy**. Escharotomy causes large quantity of blood loss and so blood transfusion is needed while doing escharotomy. Incision should be of adequate length and depth during escharotomy. It should be placed in such a way so as to avoid injury to major neurovascular system. Release of muscle compartment is needed often in these patients.
- Early rapid separation of eschar indicates severe sepsis underneath.
- Eventually eschar should be excised and the area is allowed to granulate and skin grafting should be done.
- **Pseudoeschar** is thickened burnt skin due to repeated silver sulphadiazine application.

COMPLICATIONS OF BURNS CONTRACTURE

1. Ectropion of eyelid causing keratitis and corneal ulcer.
2. Disfigurement in face.
3. Narrowing of mouth **microstomia.**
4. Contracture in the neck causing restricted neck movements.
5. Disability and nonfunctioning of joints due to contracture.
6. Hypertrophic scar and keloid formation.
7. Repeated breaking of scar and infection, ulcer, cellulitis.
8. Pain and tenderness in the scar contracture.



Fig. 1.194: Burns contracture. Patient is left severely handicapped due to contracture.

9. ***Marjolin's ulcer:*** It is a very well-differentiated squamous cell carcinoma occurring in a scar ulcer due to repeated breakdown *(unstable scar of long duration).*
   - It is locally malignant.
   - As there are no lymphatics in the scar, so there is no spread to lymph nodes.
   - As there are no nerves in the scar it is painless.
   - It has raised and everted edge with induration.
   - Biopsy confirms the diagnosis.

Treatment: *Radiotherapy is not given* for Marjolin's ulcer. Treatment is either *wide excision* or *amputation. It is curable.*

Once it spreads out of the scar tissue it behaves like any other squamous cell carcinoma and so can spread to regional lymph nodes.



Figs 1.195A to C: Contracture at different parts of the body – chest, face and neck.

> *Complete and lasting freedom from disease is but a dream remembered from imaginings of garden of Eden.*
> — Reni Jules Dubos



Fig. 1.196: Marjolin's ulcer developed over burns contracture.



Fig. 1.198: Same patient with knee contracture undergoing release surgery.

Treatment for Contracture

- Release of contracture surgically and use of skin graft or "Z" plasty or different flaps.
- Proper physiotherapy and rehabilitation is essential.
- Pressure garments to prevent hypertrophic scars.
- Management of itching in the scar using aloe vera, antihistamines and moisturizing creams.



Fig. 1.197: Severe contracture at knee joint causing deformity.

Prevention of development of contracture

- Joint exercise in full range during recovery period of burns
- Pressure garments for a long period
- Topical silicon sheeting
- Saline expanders for scars



Fig. 1.199: Burn contractures over neck and chest wall causing cosmetic problem.



Fig. 1.200: Infant had burns in head and neck region causing severe contracture.



Fig. 1.201: Hypertrophic burn scar with contracture neck in a female.



Figs 1.202A and B: Elbow contracture due to burns.



Fig. 1.203: Keloid in the hand after burn injury.

ELECTRICAL BURNS

Types of Electrical Injury

- *Low tension injury*
- *High tension injury* – may be due to current itself causing intense damage on the tissues upto 2000°C; flash injury due to electrical arc upto 4000°C; flame injury by catching of fire to the clothing and body; traumatic injury like fractures and internal organ injuries.
- It is always a deep burn (***always a major burn***).
- There is a *wound of entry and wound of exit*.
- Patient may also have major internal organ injuries. GIT, thoracic injuries.
- Often convulsions can develop.
- Death may occur due to cardiac arrhythmias (***instant death due to ventricular fibrillation***).
- ***Gas gangrene*** is common after electric injury.
- Release of myoglobin can cause renal tubular damage and ***renal failure***.
- Acidosis is common and so often bicarbonate infusion is needed.
- Patient should *always be admitted* and should be assessed by ECG, cardiac monitor, U/S abdomen, chest X-ray, sometimes even CT scan head, cardiac enzyme analysis.
- Depending on the injury it is managed accordingly.
- Fractures and dislocations are common in electrical injuries which is treated accordingly.
- *Mafenide acetate* is better agent as it penetrates well and it is useful against clostridial infection.
- *Mannitol* is used to prevent myoglobin induced renal failure.
- Wound excision, amputation, surgery for internal organ injury, cardiac monitoring are essential part of the surgical management.



Fig. 1.204: Wound of entry in an electric burn.

> *There is no right way to do something wrong.*



Fig. 1.205: A tell-tale sign of electric burns.

INHALATION INJURY

It occurs after major fire burns.

It is due to:

- Inhalation of heat.
- Noxious gases and incomplete products of combustion.
- At the site of fire, oxygen concentration is less than 2% which can cause death in 45 seconds due to hypoxia.
- Inhaled carbon monoxide binds with Hb immediately to form carboxyhaemoglobin causing severe anoxia and death.
- Symptoms of carbon monoxide intoxication– headache, disorientation, visual changes, fatigue, vomiting, hallucinations, shock and cardiac arrest.
- Smoke contains hydrocyanide which causes tissue hypoxia and profound acidosis.
- Laryngeal oedema and laryngospasm.
- Bronchial oedema and bronchospasm.

Later Problems

- ARDS.
- Pneumonia.
- Atelectasis.
- Pulmonary embolism.
- Pulmonary oedema.
- Pneumothorax.

Clinical Features

- They have low oxygen saturation.
- Charring of mouth, oropharynx with facial burns.
- Carbon sputum.
- Change in the voice, singed facial and nasal hair.
- Decreased level of consciousness with stridor or dyspnoea.

Management

- Replacing the patient from the site earliest.
- Ventilator support.
- Antibiotics.
- Bronchoscopy.
- Tracheostomy whenever required.

CHEMICAL BURNS

- In chemical burns, tissue destruction is more and progressive. It is always a deep burn.
- **Acid** burn occurs in skin, soft tissues and GIT. In GIT, it is common in **stomach** either due to nitric acid or sulphuric acid which may lead to severe gastritis or pyloric stenosis. Other acids are formic acid, hydrofluoric acid. They cause metabolic acidosis, renal failure, ARDS, haemolysis. Acidaemia should be corrected by IV sodium bicarbonate.
- **Alkali** burns occur in oral cavity and **oesophagus** which leads to multiple oesophageal strictures. Sodium hydroxide, lime, potassium hydroxide and bleach are common alkalis involved. They cause saponification of fat, fluid loss, release of alkali proteinates and hydroxide ions which are toxic.
- ***External chemical burns*** are always deep and cause extensive disfigurement with cosmetic problems.
- *Initial treatment* is dilution with water (***Hydrotherapy).***
- *Neutralisation with antidote should never be done at initial phase* of treatment as it creates exothermic reaction which aggravates the tissue damage. Late neutralisation is done, if required by 0.2% acetic acid in alkali burns, sodium bicarbonate, calcium gluconate 10% gel, topical ziphrin solution in acid burns.
- Treatment should always be with hospitalisation.
- Mannitol diuresis, haemodialysis, calcium gluconate IV, pain relief, serum electrolyte management, TPN, ventilator support are systemic management required.
- Late treatment is reconstruction of the face.
- Oesophageal dilatation or colonic transposition is done for oesophageal stricture due to alkali burn.
- Gastrojejunostomy is done for acid induced pyloric stenosis.

Medico-legal and ethical aspects in burns

- Police should be informed whenever a female, pregnant patient arrives with burns
- Consent for high risk should be taken especially in burns > 30%
- Burns should be assessed whether it is accidental or homicidal
- Relatives should be informed about the duration of stay, problems, repeated surgeries
- In patients with severe burns who is likely to die, when suspected, dying declaration should be arranged
- Cost of therapy, long duration of stay and cosmetic problems should be informed to the relatives

- Tar burns are treated additionally with neosprin which contains Tween – 80 emulsifier of tar.

Self-assessment Questions

- Classification of burns.
- Fluid calculation and management in burns.
- Complications of burns.
- Burns contracture.
- Electric burns.
- Inhalation burns.
- Eschar.
- Surgical management of burns.
- Pathophysiology of burns.

Move to the rhythm of soul and you'll never miss a beat.

Trauma

Triage—*triage algorithm, management of trauma*
Spinal injury
Neck injuries
Bullet injuries
Blast injuries
Penetrating injuries
Abdominal trauma

Trauma is the major public health problem in all countries.



Fig. 1.206: Trauma causing large tissue defect exposing the bone.

TRIAGE

Triage means *"To sort"* in French.

Triage is a system to attend trauma patients, formulated by *Committee of Trauma of the American College of Surgeons.*

Advanced Trauma Life Support (ATLS) is essential for first hour care of an injured patient.

Pre Hospital Trauma Life Support (PHTLS) is to prevent deaths while injured patients are transported to the hospital.

Types of Triage System

- *Multiple casualties* – Staff and facilities are sufficient but priority is given to life threatening injuries.
- *Mass casualties* – Staff and facilities are not sufficient to manage. Here those who are likely to have highest chance of survival are given priority.

Assessment of four components

i. Physiologic response
ii. Anatomical injury
iii. Biomechanical injury
iv. Comorbid factors

TRIAGE ALGORITHM

STEP ONE (Assess physiological impact)

Measure vital signs and level of consciousness

- By Glasgow coma scale
- Systolic blood pressure
- Respiratory rate
- Revised trauma score. It is based on airway, laryngeal injury, spine injury, maxillofacial injury

STEP TWO (Assess anatomical impact)

All penetrating injuries to head, neck, thorax, major burns, fracture bones, pelvic fractures, paralysis

STEP THREE (Assess mechanism)

Automobile accidents, crash or blast injuries, high energy injuries, fall from more than 20 feet. Bullet injury

STEP FOUR (Assess history)

- Patient's age below 5 years or age more than 55 years
- Cardiac diseases, respiratory and metabolic diseases
- Pregnancy
- Patients with bleeding disorders
- Immunosuppressed individuals

BASED ON THESE STEPS CONSIDER TO SHIFT THE PATIENT TO TRAUMA CENTER and TRAUMA TEAM SHOULD BE KEPT ALERT.

It is important in multiple and mass casualities (fire, blasts, automobile accidents, train accidents).

Management

- Initial evaluation of the patient.
- Physiologic stabilisation.
- Control of haemorrhage.
- Management of thoracic and abdominal injury.
- Management of cranial injury.

I. Primary Management

- **A**irway management (blocked by food, vomitus, clot, fallen tongue).
- **B**reathing.
- **C**irculation.
- **D**isability and level of consciousness assessment by Glasgow coma scale.
- **E**xposure of the patient from head to toe for final assessment.
- **F**ingers and tubes: Finger evaluation, Foley's catheterisation.

Goals

- Identify life-threatening conditions.
- Decide and implement appropriate treatment to the area of trauma.
- First think to salvage the life, then think to salvage the limb.
- Rapid assessment, rapid resuscitation, rapid stabilisation.
- Optimum, complete care.
- Transport efficiently to higher trauma centre.

Categorise the patient

I: Deceased
II: Walking wounded
III: Immobile wounded
IV: Trapped wounded

Tag the patient accordingly

Red colour	: Immediate treatment is required
Yellow colour	: Urgent treatment is required
Green colour	: Delayed treatment is required
Blue colour	: Expectant treatment is required
Black colour	: Deceased

AIRWAY	*BREATHING*
Chin lift	100% oxygen
Jaw thrust	Assess bilateral chest raise
Nasal airway	Assess breath sounds
Oral airway	Use pulse oximetry
Endotracheal intubation	Treat flail chest, pneumothorax
Tracheostomy	Intercostal tube drainage
(assess airway patency)	

CIRCULATION	*DISABILITY EVALUATION*
Monitor vitals	Neurological examination
Heart sounds	Glasgow coma scale
ECG	Pupillary reaction
IV fluids Blood transfusion	
Treatment of shock	
Control of external bleed	
Use two IV lines—14G/16G	

EXPOSE THE PATIENT FULLY	*FINGERS AND TUBES*
Undress the patient	Examine all orifices like P/R, P/V etc
Hypothermia assessment	Use required tubes like catheter, Ryle's tube
Assess injuries	
Examine joints, bones, abdomen, other systems	
Look for identification marks	

II. Investigations

- X-ray spine, chest, pelvis, extremities.
- CT scan.
- Blood group and cross-matching.
- Arterial blood gas analysis.
- Serum electrolytes.
- U/S abdomen.

III. Secondary Survey

Re-evaluate the patient completely again.



Fig. 1.207: Crush injury leg due to road traffic accident.



Fig. 1.208: Ankle injury with open wound.

IV. Definitive Care

(All discussed under individual topics.)



Fig. 1.209: Degloving injury involving entire left lower limb, perineum, and left groin. Patient has lost scrotum and both testes. There were no internal injuries and vessels and nerves were intact. Patient underwent wound excision extensively and colostomy was done to promote healing of perineal wound and prevent contamination.

> *During an injury, unsuspected lesions of the spinal cord may cause the most excruciating abdominal pain.*
> —Theodore Schrire



Fig. 1.210: Class III dog bite on face in a boy.



Fig. 1.211: Degloving of scalp with bone periosteum exposing the skull bone. Outer table was actually dead and required bone removal and graft after healthy granulation tissue was formed.

Trauma Mechanism

- Blunt trauma – direct or indirect blunt injury can occur. Seat belt reduces the blunt injury in vehicles.
- Penetrating injury – severity depends on the extent of deeper injury.
- Blast injury.
- Crush injury – earth quake, industrial accidents, and train accidents – causes crush syndrome; compartment syndrome.
- Burn injury.
- Injury in alcohol patients.

Concepts in Trauma Management

- Concept of '*golden hour*' to treat the trauma patient is important.
- Multidisciplinary approach.
- Planning, setting up, organizing, team work.
- Assess respiratory system; circulation; bleeding areas – as priority.
- Assess also whether patient is haemodynamically stable or unstable.
- Arrange fluids, blood, catheters, ventilator, etc.
- Further definitive therapy depending on severity and site of injury.

Damage Control Surgery

- Resuscitation and early therapy in operation theatre itself.
- Minimum but essential surgery to control bleeding and prevent contamination.
- Secondary definitive surgery at a later period to have final control.

SPINAL INJURY

- Assess the type, extent and severity of the injury.
- Careful first aid and transfer to prevent further damage to the spinal cord.
- Assess the sensory loss or motor loss properly.
- Assess fractures clinically, by X-ray and MRI.
- *Central cord syndrome* is common and is due to hyperflexion or hyperextension of the neck in an injured patient causing ischaemia of spinal column due to interfering of spinal artery blood flow.
- *Brown-sequard syndrome:* It is due to partial transection of the cord causing ipsilateral motor function loss and contralateral sensory function loss.



Fig. 1.212: Hand injury involving all fingers.



Figs 1.213A and B: A person has bitten this patient during a fight and removed the central part of lower lip. It is repaired primarily by Y repair. *Remember human bites are most dangerous.*

- High dose of steroid is very useful to prevent further damage.
- Rest, traction to neck.
- Decompression of spinal canal surgically by removing bone, disc, haematoma is useful.
- Spinal stabilisation.

NECK INJURIES

Neck is divided into zones for managing neck injuries
Zone I: from clavicle to cricoid cartilage
Zone II: from cricoid cartilage to angle of the mandible
Zone III: above the angle of the mandible



Fig. 1.214: Degloving scalp trauma and exposed bone is granulating well.

Indications for Neck Exploration in Injuries

- Expanding haematoma.
- Uncontrolled external haemorrhage.
- Decreased carotid pulse.
- Stridor, hoarseness, dysphonia, haemoptysis.
- Severe dysphagia, odynophagia.
- Blood in oropharynx.

Treatment

- The neck is explored with adequate incision under general anaesthesia.
- The injured structure like vessels, oesophagus, trachea, muscles are sutured.
- Antibiotics.
- Blood transfusion is given as required.
- Ryle's tube for 5-7 days.



Fig. 1.215: Neck trauma zones.

Remember what you do not know. It differs you from others.

Other injuries like head, thorax, abdomen, maxillofacial area are discussed in respective chapters.

BULLET INJURIES

Bullet injury has *wound of entry* and *wound of exit*. Extent of damage is not related to the external wounds. It is related to the travel of bullet inside and extent of blast or cavitation effect inside caused by the bullet. It causes burn damage.

It can damage vessels, organs like liver, spleen, kidneys, bowel, lungs, heart, cranial structures, soft tissues, bones and joints.

Management

- The wounds are explored properly under general anaesthesia.
- All dead tissues and dead muscles are excised.
- Skin is generously and adequately incised.
- Injured nerves are cleaned and silk marker stitches are placed to identify for later secondary suturing. (Nerve should not be sutured primarily in bullet injury.)
- All foreign bodies are removed.
- Tendon repair should not be done primarily.
- Wound should not be closed. It should be left open.
- Adequate blood transfusion and antibiotics coverage should be given.



Fig. 1.216: Multiple pellets over elbow region after gunshot.

- Major artery or vein are sutured. Vein graft can be used. But *synthetic graft should never be used.*
- Thorough inspection, irrigation and debridement of injured joints is done.
- Immobilisation is done.
- Tetanus toxoid, antitetanus globulin (3000 units IM), antigas gangrene serum is given.
- Second look surgeries at a later period is done once patient has been stabilised.
- Delayed primary closure in 4-7 days or secondary closure in 14 days is done.
- Depending on extent of defect, skin grafting or flaps are used.
- Laparotomy, thoracotomy, craniotomy are done depending on the site of the injury.

BLAST INJURIES

Here extent of damage is much more than bullet injuries.

It creates ***complex blast wave*** which contains ***blast pressure wave*** and ***mass movement of air.***

This explosion pressure wave is more than 1000 pounds per square inch. This pressure wave has got incident pressure and reflected pressure. Both will cause severe damage.

Factors causing the damage

- High pressure wave
- Mechanical injury
- Chemical injury
- Thermal injury
- Inhalation of toxic gases and smoke

Organs Affected

- Ear drums.
- Lungs.
- GIT.
- Brain.
- Skeletal system.

Individual becomes ***deaf*** after blast and so rescue work may be delayed.

Management

- Critical trauma care.
- Management of shock and triage primary management.
- Urgent surgeries like laparotomy, thoracotomy, craniotomy.
- Massive blood transfusion.
- Antibiotics.
- Ventilator support.
- Management of specific organs like eye, ear.



Fig. 1.217: Degloving injury buttock. It needs colostomy to protect the wound from sepsis. Later once skin coverage is done colostomy is closed.



Fig. 1.218: Crush injury foot with retained skin from plantar aspect was rotated forward. (*Courtesy by Dr Mayur Rai orthopaedician KMC Mangalore*)

PENETRATING INJURIES

- It can occur in abdomen, thorax, cranial cavity.
- It causes haemorrhage, damage to internal organs like liver, bowel vessels, lung, pericardium and heart, brain.
- It is life-threatening and immediate surgical intervention is the only treatment. Patient requires adequate amount of blood transfusion, antibiotics, shock management.



Fig. 1.220: Stab wound on the back communicating into the thoracic cavity. Wound was explored and sutured, with an ICT inserted into the thoracic cavity.

ABDOMINAL TRAUMA

It can be

- Blunt trauma
- Stab injury
- Abdominal wall injury



Fig. 1.219: Penetrating injury. Pole missed all the major vessels. Miraculously the patient survived, after a Marathon surgery to tell her tale to her children.

Well done is better than well said.



Fig. 1.221: Traumatic haemoperitoneum.

Types

- Liver injury.
- Spleen injury.
- Gastric/small bowel/colonic injuries.
- Duodenal injuries.
- Pancreatic injuries.
- Injuries to kidney/bladder/urethra.
- Mesenteric injury.
- Vascular injuries.
- Associated injuries like of diaphragm, lungs.
- Abdominal compartment syndrome.
- Gun shot or blast injuries.

General Clinical Features

- Features of shock—pallor, tachycardia, hypotension, cold periphery, sweating, oliguria.
- Abdominal distension.
- Pain, tenderness, rebound tenderness, guarding and rigidity, dullness in the flank on percussion.
- Respiratory distress, cyanosis depending on the amount of blood loss.
- Bruising over the skin of the abdominal wall.
- Features specific of individual organ injuries.

Investigations

1. U/S abdomen. FAST is *Focused Abdominal Sonar Trauma*: It is rapid, noninvasive, portable bedside method of investigation focusing on pericardium, splenic, hepatic and pelvic areas. Blood more than 100 ml in cavities can be identified. It is not reliable for bowel or penetrating injuries. It often needs to be repeated.
2. **Diagnostic peritoneal lavage (DPL):** It is done in case of blunt injury abdomen. Through a subumbilical lavage catheter one litre of normal saline/Ringer's lactate is infused into the peritoneal cavity. Patient is changed to different positions and side-to-side. Fluid content is aspirated from the abdomen for assessment.
   It has got 98% accuracy rate.

One of the criterias signifies positive lavage.

- 10 ml or more of gross blood
- RBC count more than 1,00,000/cu mm
- WBC count more than 500/cu mm
- Amylase level in the fluid more than 175 IU/ dl
- Presence of bile, bacteria, food particles or foreign body

It is the procedure of choice in physiologically unstable patient with blunt abdominal injury (like with spinal injury, unconscious patient).

Contraindications for DPL

- When laparotomy is definitely indicated
- Previous laparotomy
- Pregnancy
- Obesity

3. CT scan is indicated in assessing retroperitoneum, solid organ injuries. It is noninvasive and highly specific.
4. Diagnostic laparoscopy (DL) is valuable method in stable abdominal trauma patient.

Treatment

Emergency laparotomy.

Indications

- Frank haemoperitoneum
- Significant diagnostic peritoneal lavage
- Haemodynamically unstable patient
- U/S or CT scan shows significant intra-abdominal injuries

DUODENAL INJURY

- Its severity depends on the type and extent of the injury.
- It can be haematoma or lacerations.
- Lacerations can cause duodenal disruption, may be < 50% or > 50% or 75% or more.
- Laceration may extend into the ampulla, distal CBD, pancreas or with duodenal devascularisation.

Management

- CT scan is more relevant investigation.
- Associated other injuries should be managed accordingly.

- Haematoma without extension is managed conservatively with nasogastric aspiration, antibiotics and IV fluids.
- Lacerations are sutured surgically with a stenting or often with bypass like gastro-jejunostomy.
- ERCP stenting or CBD bypass is also often required.

Complications

- Infection.
- Duodenal leak.
- Peritonitis.
- Haemorrhage.

PANCREATIC INJURY

- It can be in the head or body and tail of the pancreas.
- It may be associated with injury to duodenum or portal or superior mesenteric veins.
- It can be contusion or severe lacerations.

Management

- High resolution CT scan is diagnostic.
- Distal pancreatectomy for injuries distally.
- Conservative treatment is useful with antibiotics, IV fluids.
- Whipple's operation or total pancreatectomy is done as a last resort.
- Drainage of the pancreatic bed is simple and often useful method.

Complications

- Pancreatitis.
- Septicaemia.
- Pancreatic fistula.
- Pancreatic abscess formation.

Pancreatic injury has got high mortality (> 45%).

SMALL BOWEL INJURY

- It can be blunt injury or stab injury.
- Blunt injury causes disruption of either duodenojejunal region or at ileocaecal region.
- Presentation is like haemoperitoneum or features of peritonitis.
- *Monks localising zones* in the abdomen signify the location of the small bowel injury.



Figs 1.222A and B: Assault causing stab injury abdomen. On opening the abdomen, multiple perforations were found in the small bowel and was sutured. Patient recovered well.

- Presence of pattern bruising over the abdominal wall signifies the small bowel injury and its site. It is called as *London's sign.*

Management

- Plain X-ray abdomen shows gas under abdomen with ground-glass appearance.
- U/S abdomen is useful.
- Laparotomy and closure of the perforation if it is small.
- In presence of extensive bowel injury or multiple injuries, resection and anastomosis is done.
- Any associated injuries should be dealt with accordingly.

Only bed of thorns can give crown of roses.

COLONIC INJURY

- Left sided injury is treated with proximal colostomy with closure of the wound if it is small, or resection and anastomosis if it is wider area. Closure of colostomy is done at later stages after 3-6 months.
- Small wound over right sided colon can be sutured primarily.
- Ileostomy alone or ileostomy with ileo-transverse anastomosis or right hemicolectomy with ileostomy is indicated in following situations:
  1. Extensive peritoneal contamination.
  2. Colonic vascular injuries.
  3. Haemodynamically unstable patients.
  4. Long-term hypotension after trauma.

LIVER INJURY

It can be subcapsular haematoma, lacerations, deeper injuries, lacerations with disruption of hepatic lobes or segments or liver injury with vascular injuries like of inferior vena cava or hepatic veins.

Present with features of haemorrhagic shock, distension of the abdomen, tenderness, rebound tenderness, guarding, rigidity.

- CT is diagnostic tool
- Liver injury is graded depending on involvement of hepatic veins, portal system, biliary system and duodenum
- Often high grade liver injury also can be managed nonoperatively
- *Push* (direct compression); *Pringle* (occluding portal triad at foramen Winslow with fingers temporarily); *plug* by embolisation; *pack* the liver bed; repair of vena cava or portal vein; stenting of biliary tree and hemihepatectomy – are the treatment strategies

Management

- Small tear is sutured.
- For larger tears—
  - Deep sutures.
  - Packing.
  - Debridement.
  - Haemocoagulants.
- Liver resection is not done (not advisable) usually for injuries.
- ***Pringle manoeuvre***—by compressing the porta near foramen Winslow—to control bleeding (not more than 30 minutes).
- Blood transfusions.
- Treatment of associated injuries like of diaphragm, lung, duodenum, colon.
- Antibiotics.

Complications of Liver Injury

- Haemorrhage.
- Septicaemia.
- Bile leak.
- Liver failure.
- Haemobilia.
- Subphrenic abscess.
- CBD stricture.

SPLENIC INJURY

It can be subcapsular haematoma, laceration or hilar injury.

It can be associated with other organ injuries like left kidney, left lobe of the liver, splenic flexure of the colon or pancreas.

It can cause torrential haemorrhage and shock.

It is the commonest organ injured in blunt injury abdomen.

Management

- U/S abdomen, diagnostic peritoneal lavage are the investigations.
- Blood transfusions.
- Splenorrhaphy is done in selected patients so as to save the spleen.
- Splenectomy.
- Management of associated injuries.

Complications of Splenectomy

- Left lung atelactasis.
- Overwhelming postsplenectomy infection (OPSI).
- Pancreatitis and pancreatic fistula.
- Gastric bleeding.
- Subphrenic abscess.

RENAL INJURY

- It is commonly managed conservatively.
- IVU is the investigation of choice in renal injury.
- Surgery is indicated when there is hilar injury, progressive bleeding, failure of conservative treatment or perinephric abscess formation.

URINARY BLADDER INJURY

Intraperitoneal bladder injury occurs in distended bladder. It is treated always by surgical exploration

ABDOMINAL COMPARTMENT SYNDROME (ACS)

Causes	*Features*	*Management*
Postoperative ileus	Hypoxia, hypercarbia	Bladder pressure assessment
Acute abdomen	Decreased urine output	Ryle's tube aspiration
Acute gastric dilatation	Hypotension	Resuscitation
	Tense abdomen-distended	ICU care
Laparoscopic procedures	Decreased venous return	Surgical decompression
Intestinal obstruction	Bowel ischaemia	
	Cardiac arrest	

through transabdominal approach. Bladder tear is sutured with keeping a supra pubic cystostomy using Malecot's catheter.

Extraperitoneal injury can be treated conservatively by placing a Foley's catheter for 2-3 weeks.

ABDOMINAL COMPARTMENT SYNDROME

- There is sudden increase in intra-abdominal pressure which causes decreased venous return to heart (Pressure more than 85 cm of H_2O).
- It causes increased peak inspiratory pressure, hypoxia, hypercarbia, decreased urine output and hypotension due to decreased venous return to heart.
- Bladder pressure measurement is diagnostic.
- Rapid decompression by opening the abdominal wound is choice treatment.

Intra-abdominal pressure grading (Burch) in cm of water

I—10—15 cm of H_2O
II—15—25
III—25—35
IV—more than 35

Self-assessment Questions

- Triage of trauma.
- Primary management of trauma patient.
- Assessment of trauma patient.
- Trauma critical care.
- Peritoneal lavage.

What we need is cup of understanding, barrel of love and an ocean of patience.

Hand and Foot

Hand
Surgical anatomy of hand
Hand infections
Acute paronychia
Chronic paronychia
Apical subungual infection
Terminal pulp space infection
Infection of web spaces
Deep palmar space infection
Acute suppurative tenosynovitis
Compound palmar ganglion
Hand injuries
Dupuytren's contracture
Volkmann's ischaemic contracture
Syndactyly
Mallet finger
Heberden's nodes
Spina ventosa
Foot
Callosity
Corn
Plantar fasciitis
Ingrowing toe nail
Onychogryphosis
Onychomycosis
Athlete's foot
Hallux valgus

HAND

Surgical Anatomy of the Hand

Flexor Retinaculum

- It extends medially from pisiform and hook of hamate, laterally to scaphoid tubercle and trapezium crest as a strong fibrous band so as to bridge carpus to create a carpal tunnel.
- Ulnar nerve and vessels, palmar cutaneous branches of median and ulnar nerves, palmaris longus muscle are superficial to the carpal tunnel.
- Median nerve, tendons of flexor digitorum superficialis, profundus and pollicis longus, radial and ulnar bursa are deep to flexor retinaculum.

Palmar Aponeurosis

It is a thickened, modified deep fascia in the palm with its apex pointing proximally (as continuation of palmaris longus) and base distally which in turn gets divided into four parts. They extend over deep transverse ligament into lumbrical tunnel.

Blood Supply of the Hand

- Superficial palmar arch is mainly formed by ulnar artery and completed by superficial palmar branch of radial artery. It gives four digital branches to medial three fingers.
- Deep palmar arch is formed by radial artery and is completed by deep branch of ulnar artery. It gives three palmar metacarpal arteries which communicate with superficial palmar arch. It also gives communicating, perforating branches to dorsal metacarpal arteries.

Muscles of the Hand

- ***Thenar muscles***: Abductor pollicis brevis, flexor pollicis brevis, opponens pollicis and adductor pollicis.
- ***Hypothenar muscles***: Palmaris brevis, abductor digiti minimi, flexor digiti minimi and opponens digiti minimi.
- ***Lumbricals*** are four in number—named from lateral to medial.
- Four ***palmar interossei***.
- Four ***dorsal interossei.***

Nerve Supply

- Abductor pollicis brevis, flexor pollicis brevis, opponens pollicis and 1st and 2nd lumbricals are supplied by median nerve (5 muscles).
- Rest of the muscles in hand are supplied by ulnar nerve (15 muscles).

Modified Verdan Zone System in the Hand (Tendon zones)

Zone I

From the fingertip up to the attachment of flexor digitorum superficialis (middle of middle phalanx). It contains tendon of Flexor digitorum profundus.

Zone II

It begins proximal to metacarpophalangeal joint at distal palmar crease and extends up to the attachment of flexor digitorum superficialis at the middle of the middle phalanx. It is called as ***"No-Man's-Land."*** Here flexors are tightly enclosed within a fibro-osseous tunnel. It is the ***most dangerous zone*** in hand injuries (***critical zone***).



Fig. 1.223: Anatomy of flexor retinaculum and palmar aponeurosis.

Zone III

It begins at the distal end of flexor retinaculum (base of the palm) and ends at the transverse crease of the palm. It contains lumbricals attached to flexor digitorum profundus.

Zone IV

It begins at the proximal end of the flexor retinaculum and ends at its distal end.

Zone V

It extends from the proximal end of flexor retinaculum up to distal third of the forearm.



Fig. 1.224: Modified Verdan zone system in the hand.

HAND INFECTIONS

Hand is a compact actively functioning unit. It contains neurovascular bundles, muscles, bones and ligaments.

Infection may be due to minor injuries or blood borne.

Precipitating causes

- Diabetes
- Immunosuppression
- Trauma
- HIV infection
- Steroid therapy
- Vascular diseases

Common organisms

- *Staphylococcus aureus—commonest*
- *Streptococcus*
- Gram-negative organisms like *E. coli*, *Klebsiella*, *Pseudomonas*
- Occasionally fungal infection causing chronic paronychia, Madura hand due to Nocardia group of fungi, viral infection like *orf* can occur

General Features of Hand Infection

- Infection spreads faster in all areas.
- Causes oedema over the dorsum of hand due to lax skin and more lymphatic network even though infection per se is more over the volar aspect. It looks like ***frog hand.***
- Restricted movements of fingers and hand. The hand functions like ***hook***, ***pinch, grip***, ***grasp*** are lost.
- Severe pain and tenderness, with fever.
- Tender palpable axillary lymph nodes are often present.

Different Types of Hand Infections

- Acute paronychia.
- Chronic paronychia.
- Terminal pulp space infection (***felon***).
- Subungual infection.
- Web space infection.
- Mid palmar space infection.
- Thenar space infection.
- Deep palmar abscess.
- Acute suppurative tenosynovitis.
- Chronic tenosynovitis of flexor tendon sheath of palm and forearm—compound palmar ganglion.
- Lymphangitis of the hand.

An ounce of action is worth a ton of theory.



Figs 1.225A to F: Different types of hand infections. Note the oedema of hand even in dorsal aspect. Small infective focus can aggravate rapidly and so early proper drainage from deeper plane is important in managing the hand infections. Often it may cause extensive destruction exposing the tendons.

Investigations

- Pus for culture and sensitivity.
- Blood sugar.
- Urine sugar and ketone bodies.
- X-ray of the part.



Fig. 1.226: Hand positions.



Fig. 1.227: Hand infection. Infection of ring finger extending into the palm.



Fig. 1.228: Infection of little finger with dorsal oedema.



Fig. 1.229: Hypertrophic scar and keloid in hand and forearm after burn contracture.

General Principles of Managing Hand Infections

1. Antibiotic therapy.
2. **Position of rest** with wrist slightly abducted and extended, thumb and index fingers away (glass-holding position). Position of function is in which thumb and index fingers are pinching firmly with wrist extension.
3. Elevation of hand reduces the oedema, increases perfusion, promotes healing.
4. Early recognition of localised **pus.** Once localised, **Incision** and **Drainage** is done ideally under general anaesthesia or regional block **(not local anaesthesia).** Draining incision should not cross the palmar crease. Incision should have adequate length and adequate depth (deep to palmar fascia, otherwise evacuation of pus is inadequate). Care should be taken not to injure neurovascular bundles. Pus should be sent for culture and sensitivity. **Slough,** if present should be excised thoroughly. Gauze drain is placed. Regular dressings are done with continuation of antibiotics. Communications into other areas of hand should also be drained.
5. **Bloodless field** (using tourniquet) is better to drain pus from hand.
6. Proper measures must be taken after treatment. Initial rest, elevation of hand and later proper physiotherapy and regular exercise of hand and fingers are encouraged to restore normal function.

Complications of hand infections

- Stiffness of digits and hand (ankylosis)
- Deformity and disability
- Bacteraemia and septicaemia
- Osteomyelitis of bones depending on the location of abscess like metacarpal bones, terminal phalanx
- Suppurative arthritis of joints
- Paralysis of median nerve

> *Early signs of Volkmann's contracture are pain, pallor, puffiness, pulselessness and paralysis.*
> —David L Griffiths

Remember

- Hand should be flexible and strong; sensitive and pain free and coordinated to show all fine and powerful functions
- *Pinch* (picking a small object); *power grip* (holding a hammer); *key grip* (holding a key); *chuck grip* (holding a pen); *hook grip* (carrying a bag) – are the functions of hand
- Hand should be properly examined clinically for tendon functions; neurological problems – sensations (sweat test, two point discrimination test); for circulation (Allen's test); joint movements; examination of entire upper limb; opposite hand; axillary lymph nodes and other relevant systemic examinations
- Nerve conduction studies; electrophysiology; MRI hand; radioisotope bone scan; selective angiograms; X-ray hand are the relevant investigations other than systemic investigations
- Principles of treatment—elevation to reduce oedema; splintage to prevent contracture; early movements once inflammation subsides; early exploration of wound or surgical drainage of infective area; regional anaesthesia; usage of tourniquet; incisions when done across the flexor creases, should be at 45° angle

ACUTE PARONYCHIA

- It is the most common hand infection.
- It occurs in subcuticular area under the **eponychium**.
- Minor injury to finger is the common cause.
- Suppuration occurs very rapidly.
- It tracks around the skin margin and spreads under the nail causing **hang nail** or **floating nail**.
- Organisms are *Staphylococcus aureus* and *Streptococcus pyogenes*.

Clinical Features

Severe throbbing pain and tenderness (dependent throbbing) with visible pus under the nail root. Nail on touch is very tender (paronychia means "**Run around**").

Treatment

- Pus is sent for culture and sensitivity.
- Antibiotics like cloxacillin, amoxycillin.
- Analgesics.
- The pus is drained by making an incision over the eponychium.
- If there is a **floating nail,** then the nail is dead and it has to be removed.

Recovery is fast.



Figs 1.230A and B: Paronychia showing pointing pus in one picture and sloughed area granulating in another picture.



Fig. 1.231: Acute paronychia.

CHRONIC PARONYCHIA

It is commonly due to fungal infection.

Clinical Features

- Itching in the nail bed.
- Recurrent pain.
- Discharge.
- Secondary bacterial infection may supervene.

Investigation

Culture of scrapings for fungus and other causative agents.

Treatment

- Long term antifungal therapy.
- Antibiotics for secondary infection.
- In severe cases removal of nail is required.

APICAL SUBUNGUAL INFECTION

- It is infection of the space between subungual epithelium and the periosteum.
- It occurs after minor trauma or rarely after formation of subungual haematoma.
- Beneath the free edge of the nail, pus comes to the surface.

- Excruciating tenderness with small visible pus under the tip (summit) of the nail is the feature.
- Drainage with 'V' incision over the summit is the treatment along with antibiotics.
- Osteomyelitis is not common.



Fig. 1.232: Apical subungual infection and pus formation. Note the 'V' shaped incision to drain the same.

TERMINAL PULP SPACE INFECTION (FELON)

- It is the second most common hand infection (25%).
- Index and thumb are commonly affected.
- Usually by a minor injury like finger prick.

Surgical Anatomy

- Terminal pulp space contains fat and is partitioned by septae which is attached from periosteum of terminal phalanx to skin.
- Proximally deep fascia is attached to the periosteum distal to the base of terminal phalanx, i.e. distal to the attachment of flexor tendon.
- So, terminal space is a closed compartment, as the result of which pressure increases when there is infection, compressing terminal artery leading to thrombosis, resulting in osteomyelitis of terminal phalanx.



Fig. 1.233: Anatomy of the terminal pulp space.



Fig. 1.234: Pulp space infection.

Bacteria

- *Staphylococcus* commonest.
- *Streptococcus*.
- Gram-negative organisms.

Clinical Features

- Pain, tenderness, swelling in the terminal phalanx.
- Fever.
- Tender axillary lymph nodes.

Often suppuration is severe, forming **collar stud abscess** which eventually may burst.

Causes of ***collar-stud abscess***
- Tuberculous cold abscess
- Terminal pulp space infection (Felon)
- Deep palmar space infection

Investigations

- X-ray of the part is required often to rule out osteomyelitis of terminal phalanx.
- Pus for culture and sensitivity.

Treatment

- Antibiotics and analgesics.
- **Drainage** of terminal pulp space by an oblique deep incision.
- If there is osteomyelitis of the terminal phalanx, it has to be amputated.



Fig. 1.235: Incision for pulp space drainage.

Dupuytren's contracture typically affects the ring finger and years later the little finger becomes implicated. In 30% cases little finger is primarily affected. —Peter F Early

Complications

- **Osteomyelitis** of the terminal phalanx.
- **Septicaemia.**

INFECTION OF WEB SPACES

Surgical Anatomy

There are three triangular web spaces filled with fat between the dorsal and volar skin. When the space is filled with pus it straddles the deep transverse ligament. Even though pus is volar, it points out dorsally.

It originates from—

- Abrasion.
- Infection of proximal volar space of finger.
- Callosities.
- Infection of proximal spaces.

Bacteria

- *Staphylococcus.*
- *Streptococcus.*
- Gram-negative organisms.

Clinical Features

- Fever.
- Pain and tenderness.
- Oedema of dorsum of hand.
- **Maximum tenderness** is on the volar aspect.
- **'V' sign—**Separation of fingers.
- If untreated, infection may spread into other web spaces and hand spaces.

Treatment

- Elevation of hand.
- Antibiotics and analgesics.
- **Drainage** under regional or general anaesthesia. A **horizontal** incision is placed on volar skin of the web and deepened to reach the space by dividing fibres of palmar fascia. Pus is drained and sent for culture and sensitivity. If other web spaces are involved they should be drained through a separate incision. Edges of the wound are cut to leave a diamond shaped opening in front. Often counter-incision over dorsal skin of web is needed.



Fig. 1.236: Incision for web space drainage.

DEEP PALMAR SPACE INFECTION

Surgical Anatomy

Two deep palmar spaces are present

- **Midpalmar space.**
- **Thenar space.**

Midpalmar space is bound in front by palmar aponeurosis, behind by medial three metacarpals, laterally by a vertical line from lateral margin of the middle finger. It contains flexor tendons, neurovascular bundles and lumbricals. It is the common site of the infection.

Thenar space is located anterior to lateral two metacarpals. Infection here is usually due to extension from midpalmar space.

Causes

- Trauma.
- Spread from infection of finger spaces and web spaces.
- Haematogenous spread.
- Spread from tenosynovitis.

Clinical Features

- Pain and tenderness in the palm.
- Oedema of dorsum of hand **(frog hand).**
- Loss of concavity of palm.
- Painful movement of metacarpophalangeal joint (but interphalangeal joint movements are normal and painfree).
- Fever.
- Palpable tender axillary lymph nodes.
- Eventually pus may come out of palmar aponeurosis forming collar stud abscess and later sinus formation. X-ray of the part is required.

Treatment

- Elevation of the affected limb.
- Antibiotics and analgesics.
- **Drainage** under general anaesthesia. A horizontal incision is placed on the volar aspect without crossing the palmar creases and should be extended deep to palmar aponeurosis. A drain is placed. Pus is sent for culture and sensitivity and appropriate antibiotics are continued.

Complications
- Osteomyelitis of metacarpals
- Stiffness of hand
- Suppurative arthritis
- Extension of infection into other spaces

ACUTE SUPPURATIVE TENOSYNOVITIS



Fig. 1.237: Bursae hand.

It is the bacterial infection of flexor tendon sheaths.

Surgical Anatomy

- **Radial bursa** is flexor sheath of flexor tendon of thumb which extends to the digit.
- **Ulnar bursa** is flexor sheaths of medial four flexor tendons of hand which extends into the digit of the fifth (little) finger.
  - Extensor tendons are devoid of sheaths.
  - Radial and ulnar bursa communicate with each other in 80% of cases.

Common bacteria: Staphylococcus aureus, Streptococcus pyogenes.

Clinical Features

- Symmetrical swelling of entire finger.
- Flexion of finger—**Hook sign**.
- Severe pain on extension.
- Tenderness over the sheath.
- Oedema of whole hand, both palm and dorsum (due to lymphatic spread).
- As ulnar bursa extends into the little finger its infection results in pain and tenderness extending up to little finger but not much to other fingers.

Kanavel signs:
- Swollen finger held in flexion
- Exquisite pain on passive extension
- Tenderness precisely over the tendon sheath.
- *Area of greatest tenderness over the part of ulnar bursa lying between transverse palmar creases*

- In infection of radial bursa thumb is swollen with pain and tenderness over the sheath of the flexor pollicis longus and there is inextensibility of interphalangeal joint.
- Swelling just above the flexor retinaculum is common.

Treatment

- Elevation of the affected limb.
- Antibiotics and analgesics.
- Position of rest.
- **Drainage** under general anaesthesia. Incisions are placed over the site of maximum tenderness and flexor sheath should be opened up. Many a times multiple incisions are required.

Complications
- Spread of infection proximally into forearm
- Stiffness of fingers and hand
- Suppurative arthritis
- Osteomyelitis
- Median nerve palsy
- Bacteraemia and septicaemia

COMPOUND PALMAR GANGLION

- It is chronic tenosynovitis of flexor tendon sheaths due to tuberculosis (tuberculous tenosynovitis) or rheumatoid arthritis.
- It can be unilateral or bilateral.

Pathology

- Flexor tendon sheath on either side of the wrist is involved i.e. both in the volar surface of palm and lower forearm.
- Swelling contains fluid with typical ***melon seed bodies***.
- Condition is often bilateral in case of rheumatoid arthritis.

Clinical Features

- Swelling in the palm and lower forearm which is smooth, soft, nontender, fluctuant and also *cross*

> *When a hand is seriously inflamed it takes up the position of greatest ease, which is, in fact, the position of rest.*
> — Frederic Wood Jone

fluctuant across flexor retinaculum, nontransilluminating.
- Wasting of hand and forearm muscles are seen.
- Matted axillary lymph nodes may be palpable.
- Primary focus may be present in lungs.

Investigations

- ESR.
- Chest X-ray.
- FNAC of axillary lymph node and swelling itself.

Treatment

- Start antituberculous drugs: INH, rifampicin, ethambutol and pyrazinamide for 9 months.
- Excision of flexor tendon sheath is done along with scraping of caseating material, tubercles, melon seed bodies.
- Care should be taken not to injure median and ulnar nerves.

ORF is contagious pustular dermatitis of the hand due to a parapox virus infection.

MILKER'S NODES is similar viral infection of the hand seen in cow handlers.

HAND INJURIES

Classification

- ***Tidy injuries*:** They are clean incised wounds and are usually treated by primary suturing but depends on the tissues involved like nerves, tendons and muscles.
- ***Untidy injuries*:** They are lacerated wounds. Treated by debridement and later by delayed primary or secondary suturing.
- ***Compartment injuries.***
- ***Degloving injuries***
- ***Indetermined injuries*** which could not be assessed.

Assessment of Injury

Should include:
- Number, extent, depth, deformity and disability, neurovascular injuries, tendon injuries, muscle injuries bone and joint injuries.



Figs 1.238A and B: Indeterminate and untidy hand injuries.

In HAND

DO'S	*DON'TS*
Do examine hand carefully	Do not incise every infected digit
Do think of other diagnosis	Do not make puncture incisions or over pads
Do wait for abscess to localise	Do not injure the digital nerves or vessels
Do place adequate length and depth of incisions	Do not place incisions crossing the crease line
Do immobilise, elevate the hand	Do not close human bites or lacerated wounds
Do give antibiotics and proper dressings	Do not forget to send pus for culture and sensitivity

Parona's space is space in the forearm to which infection can occur as a result of extension from the hand.



Fig. 1.239: Hand injury exposing tendons. Note the marker stitch in the tendon. It needs local transposition flap or groin flap to cover. Skin grafting is not possible over tendons.

Principles of Treatment

- Haemostasis.
- Use of tourniquet.
- Wound debridement and cleaning.
- Antibiotics and antitetanus treatment (toxoid and antitetanus globulin).
- Primary suturing if it is a incised wound or delayed primary suturing if there is odema.
- Skin grafting or flaps for skin loss.
- Tendon suturing or tendon graft for tendon injuries.
- Rest and elevation of the affected parts.
- Management of fractures by splint, wiring.
- Nerve repair for nerve injuries.
- Immobilisation up to 21 days.
- Later physiotherapy with warm, exercise, was bath active movements.
- Microsurgical restoration of digits. Reimplantation of the digits.
- Amputation of digits or metacarpals only when inevitable.



Fig. 1.240: Stuck finger by a ring. It is removed by applying soap, fat, and wax. String method is winding and unwinding a thread under and across the stuck finger. Sawing is done only when every method fails.



Fig. 1.241: Avulsion injury of thumb causing raw area. This needs proper skin cover to get the function adequately.

Primary repair of tendons and nerves are of lesser priority in untidy injuries. Priority is wound debridement/ wound excision and early skin cover. Cut ends of nerves and tendons are tagged with coloured stitches for future identification purpose.

Complications and morbidity of hand injuries

- Infection
- Osteomyelitis
- Arthritis of joints
- Stiffness
- Loss of function due to disability



Fig. 1.242: Typical deformity of finger which needs correction for proper function.

Disease is the fate of poor, but also punishment of rich.— Ivo Andrick

DUPUYTREN'S CONTRACTURE

> ***Individuals pre-disposed to the affection we are describing, observe that it is more difficult to extend the fingers of the affected hand… The first (interphalangeal joint) is flexed at nearly a right angle…the most powerful efforts are insufficient to extend it…. Hence, it was natural to conclude, that the commencement of the disease was in the unusual tension of the palmar aponeurosis.***
>
> **—Guillaume Dupuytren,** 1833

It refers to localised thickening of palmar aponeurosis and later formation of nodules with severe permanent changes in metacarpophalangeal and interphalangeal joints.

- It starts in ring and little fingers, with flexion of ring and little fingers. Later involving all fingers.
- There is thickening and nodule formation in the palm with adherent skin.
- It is often familial and bilateral 45%.
- Pads (of fat) develop in knuckles and are called as ***Garrod's pads*** (in proximal IP joints).

Conditions often associated with:
- Plantar fasciitis 5%—Ledderhose's disease
- Mediastinal and retroperitoneal fibrosis
- Peyronie's disease of penis 3%
- Nodules in the face and ear

Aetiology

- Repeated minor trauma.
- Cirrhosis, alcoholism.
- Epileptics on treatment with phenytoin sodium.
- Diabetics.
- Other metabolic conditions.
- Familial – autosomal dominant.

Galezia triad
- Dupuytren's contracture
- Retroperitoneal fibrosis
- Peyronie's disease

Complications

- Restriction of hand function and so disability.
- Arthritis of MCP and IP joints.

Treatment

- Fasciotomy of palmar aponeurosis and later physiotherapy, Z plasty.
- In severe cases fasciectomy partial or complete.
- Treatment of the cause.

  Recurrence can occur in 5-50% cases.



Fig. 1.243: Typical 'Z' plasty done in hand surgeries.

VOLKMANN'S ISCHAEMIC CONTRACTURE

It is a vascular injury leading to muscular infarction and subsequent contracture.

Causes

- Supracondylar fracture of the humerus.
- IV chemotherapy.



Figs 1.244A and B: Dupuytren's contracture in the hands. Note the involvement of the ring finger. Note the fibrous band on the other hand as early finding.



Fig. 1.245: Z plasty done for Dupuytren's contracture.

- Burns.
- Closed forearm crush injuries.
- Tight plaster after reduction of fracture.

Pathogenesis

Injury of brachial artery (tear, contusion, spasm, compression)

↙ ↘

Results in infarction of forearm flexor muscle

↓

Aseptic muscle necrosis

↓

Fibrosis of flexor muscle of forearm

↓

Contracture

Injury to median nerve (mainly) and ulnar nerve both by ischaemia and infarction.

Clinical Features

***Acute phase*:**

- Pain (persistent pain in fore arm, hand, fingers—ominous symptom).
- Pallor.
- Puffiness (due to oedema).
- Pulseless (absence of radial pulse; but its presence does not rule out the onset of impending contracture).
- Paresis.

Late phase: Deformity

Deformity (due to injury to median nerve):

- Wrist joint extended.
- Extended metacarpo-phalangeal joints.
- Flexed interphalangeal joints.

***Volkmann's sign*:**

In early stage, the fingers can be extended at the interphalangeal joints, only when the wrist is flexed fully. The fingers tend to flex if any attempt to extend the wrist is made.

Treatment

***In acute phase*:**

- Removal of plastic cast applied after fracture reduction.
- Correction of fracture.
- Exposure of brachial artery and application of 2.5% papaverine sulphate to relieve the spasm if any.
- Suture of arterial tear if present, often with placement of arterial graft.
- Lateral incision over the deep fascia of forearm is placed to decompress the oedema.

***In late phase (once deformity occurs)*:**

- Physiotherapy
- Dynamic splints.
- ***Max-Page operation***: Release of flexor muscles (forearm muscles) from their origins from the bone and allowing it slide down until full extension.
- Excision of fibrous tissue and damaged muscles along with tendon transfer.
- Arthrodesis.

SYNDACTYLY

It is *webbing* or *fusion* of fingers.

Causes

- Congenital and hereditary—Common.
- Traumatic like burns.



Fig. 1.246: Syndactyly.

"Impossible" is a word found only in the dictionary of fools.—Napoleon



Fig. 1.247: Syndactyly and polydactyly of both hands and both feet.

Types

- Cutaneous—simple.
- Fibrous.
- Bony—complex.

It can be unilateral or bilateral.

Often all four limbs may be involved with webbing of toes.

It may be associated with polydactyly or visceral anomalies.

If bony type is suspected, X-ray of the part should be taken.

Treatment

- If cutaneous, release of web is done as a staged procedure along with "Z" plasty or skin grafting.
- If fibrous, release can be done.
- If bony type, release is difficult because blood supply may be compromised which leads to gangrene of the digit.

MALLET FINGER (Base ball finger)

The terminal phalanx can not be extended because of tear at insertion of extensor tendon or avulsion fracture of the base of the terminal phalanx.

HEBERDEN'S NODES

These are seen in osteoarthritis, occurring behind the distal interphalangeal joints of *index,* middle, little and ring fingers.

SPINA VENTOSA

Refers to phalangeal tuberculosis (***Tuberculous dactylitis***). It is called as spina ventosa because of its appearance as "air filled balloon."



Fig. 1.248: Spina ventosa.



Fig. 1.249: Localised gigantism of index finger, thumb and part of the medial aspect of the hand.

FOOT

CALLOSITY

- It is a hard, thickened skin occurs as a protective measure seen in wider area usually over heel and heads of metatarsals.
- A callosity protrudes outwards from the skin.



Fig. 1.250: Callosity in the great toe.



Fig. 1.251: Callosity in the foot.

CORN

Types

- Hard corn.
- Soft corn.

Hard Corn

- It is localised area of thickening over a bony projections like heads of metatarsals.
- Histologically it differs from callosity by having severe keratoses with a central core of degenerated cells and cholesterol.
- It presses over the adjacent nerves causing pain. It can get infected causing severe pain and tenderness with inability to walk.

Treatment

- Excision.



Fig. 1.252: Corn under great toe.



Fig. 1.253: Diagram showing differences between corn and callosity.

Soft Corn

It usually occurs between 4th and 5th toes due to friction of bases of adjacent proximal phalanges. (See Fig. 1.254).

PLANTAR FASCIITIS (Policeman's Heel)

It occurs due to friction or tear of the ossified posterior insertion of the plantar fascia which is common in people who stand or walk for long-time.



Fig. 1.254: Corns in the plantar aspect of the foot.

You become successful by helping others to become successful.

Treatment

Analgesics, rest, steroid injections to the site.



Fig. 1.255: Subcuticular abscess over great toe.

INGROWING TOE NAIL (Onychocryptosis)

- It is also called as embedded toe nail.
- It is due to curling of the side of nail inwards, causing it to form a lateral spike resulting in repeated irritation and infection of overhanging tissues in the nail fold.

Causes

- Tight shoes.
- Improper cutting of nails (very short and convex).

Clinical Features

- It is common in ***great toe*** and is often ***bilateral***.
- Both medial and lateral sides of the toe can be involved.
- Recurrent attacks of acute and subacute paronychia occurs.
- Pain, tenderness, swelling of margins of the toe, often along with granulation tissue and foul smelling discharge.


Eponychium
Root of nail
Germinal matrix
Lunula
Hyponychium (Subungual space)
Anatomy of the nail
ZADIK'S PROCEDURE
Hypertrophied infected tissue
Incision for ingrowing toe nail

Fig. 1.256: Zadik's or Fowler's operation.

Treatment

- Regular dressing and packing.
- Antibiotics. Discharge is sent for culture and sensitivity.
- Nails should be cut concavely or straight without leaving lateral spikes towards soft tissues.



Figs 1.257A and B: Ingrowing toe nail. Note the granuloma caused by repeated infection and inflammation.

- *Zadik's* or *Fowler's operation*: Skin in lateral margin and root is incised so as to expose the lateral spike and germinal matrix. ***Infected tissues with pus and germinal matrix of ingrown part of the nail is excised or often entire nail with its root and germinal matrix is excised.***



Fig. 1.258: Incision for nail excision. Note the germinal matrix. Removal of nail, entire or partial with adjacent germinal matrix is called as radical nail excision.

ONYCHOGRYPHOSIS

- It is curving of nail upwards (***Ram's Horn Nail***).
- It occurs due to repeated trauma or fungal infection.

ONYCHOMYCOSIS

It is fungal infection of the nail.

ATHLETE'S FOOT

- It is the fungal infection of the skin between the toes—*Tinea pedis.*
- Fungi enter through cracks; survive due to moisture in between toes.
- Skin is swollen, red, with sticky fluid, macerated with blisters.
- Itching, deep cracks, pain and discharge are common.

Treatment

- Part should be kept dry. Cotton, clean socks should be worn.
- Oral antifungals, antihistaminics and topical antifungals are used.
- Condition is contagious.

HALLUX VALGUS

Here great toe is deviated laterally at metatarsophalangeal joint. It is common in females. It may be due to persistent lateral force or occasionally hereditary. There is outward deviation of big toe with medial deviation of first metatarsal head. Thick walled bursa (bunion) over medial aspect of the head of the first metatarsal bone and osteoarthritis of the metatarsophalangeal joint are the eventual complications. Treatment may be – excision of bursa; corrective osteotomy; Keller's excisional arthroplasty or arthrodesis of metatarsophalangeal joint.



Fig. 1.259: Hallux valgus.

Self-assessment Questions

- Anatomy of the hand.
- Hand infections.
- Acute suppurative tenovitis.
- Felon.
- Terminal pulp space infection.
- Paronychia.
- Dupuytren's contracture.
- Ganglion.
- Compound palmar ganglion.
- Mid-palmar space.
- Radial bursa.
- Thenar space infection.
- Kanavel sign.
- Ingrowing toe nail.
- Hand injuries.
- Flexor tendon zones.
- Syndactyly.

A positive attitude is like a magnet for positive results.

Arterial Diseases

Surgical anatomy of thoracic outlet
Arteries of upper limb
Arteries of lower limb
Arterial diseases
Intermittent claudication
Limb ischaemia—*classification, critical limb ischaemia, Fontaine classification, investigation*
Diseases of the arteries—*Thromboangiitis obliterans, Takayasu's arteritis, Raynaud's phenomenon*
Subclavian steal syndrome
Acute arterial occlusion—*traumatic acute arterial occlusion, embolism, Caisson's disease*
Aneurysm—*Abdominal aneurysm, peripheral aneurysm, carotid artery aneurysm, dissecting aneurysm*
Reperfusion injury
Acrocyanosis
Gangrene
Diabetic foot and diabetic gangrene
Trophic ulcer, Bedsores
Frostbite
Ainhum
Endovascular surgeries
Upper limb ischaemia

SURGICAL ANATOMY OF THORACIC OUTLET

Thoracic outlet is bounded by manubrium sternum in front, spine posteriorly, and the first rib laterally. At the superior aperture of thorax subclavian vessels, brachial plexus traverse the cervicoaxillary canal to reach the upper limb.

Cervico axillary canal is divided into proximal *Costoclavicular space* and *distal axilla* (divided by first rib).

Costoclavicular space is bounded superiorly by clavicle, inferiorly by first rib, anteromedially by the costoclavicular ligament, and posterolaterally by scalenus medius muscle along with long thoracic nerve.

Scalenus anticus muscle divides the costoclavicular space into two compartments, the anterior one containing subclavian vein and the posterior one containing subclavian artery and brachial plexus.

This posterior compartment is called as *Scalene triangle* bounded by scalenus anticus anteriorly, scalenus medius posteriorly, and the first rib inferiorly.

Cervical rib narrows this triangle and causes compressive features of the C_8, T_1 nerve roots and subclavian artery. Anything that narrows costoclavicular space causes *Thoracic outlet syndrome*.

Causes of thoracic outlet syndrome

- Cervical rib
- Long C_7 transverse process
- Anomalous insertion of scalene muscles
- Scalene muscle hypertrophy
- Scalene minimus
- Abnormal bands and ligaments
- Fracture clavicle or first rib
- Exostosis
- Tumours in the region

Differential diagnosis for thoracic outlet syndrome

- Carpal tunnel syndrome
- Cervical spondylosis
- Spinal canal tumours
- Shoulder myositis
- Angina
- Raynaud's disease
- Spinal stenosis
- Ulnar nerve compression

ARTERIES OF UPPER LIMB

Right subclavian artery begins from brachiocephalic trunk (innominate artery) whereas left subclavian artery arises directly from the arch of aorta. From underneath the sternoclavicular joint artery arches over the pleura and apex of lung about 2.5 cm above the clavicle and then reaches the lateral border of first rib to continue as axillary artery.

Subclavian artery is divided into three parts by scalenus anterior muscle.

Axillary artery is divided into three parts by pectoralis minor muscle.

At the lower border of teres major muscle it enters the arm and continues as brachial artery.

About 2.5 cm below the crease of the elbow joint, it bifurcates into radial and ulnar arteries which run in the forearm.

Ulnar artery forms the superficial palmar arch which is completed by superficial palmar branch of radial artery.

Radial artery after passing through the anatomical snuff box enters the dorsum of hand and first intermetacarpal space to form deep palmar arch. It is completed by deep palmar branch of ulnar artery and is 1 cm proximal to superficial palmar arch.

ARTERIES OF LOWER LIMB

Abdominal aorta bifurcates at the level of fourth lumbar vertebra (corresponds to the level of the umbilicus in anterior abdominal wall) into two common iliac arteries.

Common iliac artery is about 5 cm in length passes downward and laterally; and at the level of lumbosacral intervertebral disc, anterior to sacroiliac joint, it divides into external and internal iliac arteries. Internal iliac artery supplies pelvic organs.

External iliac artery continues as common femoral artery at the level of inguinal ligament.

About 5 cm below the inguinal ligament common femoral divides into superficial femoral and deep femoral (Profunda femoris) arteries.

Deep femoral provides collateral circulation around the knee joint and also communicates above with gluteal vessels to maintain collateral circulation around the gluteal region.

Superficial femoral artery at the hiatus in the adductor magnus, continues as popliteal artery up to the inferior angle of the popliteal fossa where it divides into anterior and posterior tibial arteries.

Anterior tibial artery supplies anterior compartment of leg and ankle, continues as dorsalis pedis artery which forms dorsal arterial arch of the foot.

Posterior tibial artery supplies posterior compartment of leg and ends as medial and lateral plantar arteries which forms plantar arterial arch of the foot.

Posterior tibial artery gives peroneal artery which runs close to fibula supplying calf muscles.

ARTERIAL DISEASES

1. **Stenosis** due to trauma, atherosclerosis, emboli. It may be:
   - In the brain causing transient ischaemic attacks,
   - In the limbs causing claudication and rest pain,
   - In the abdomen causing pain, bloody stool,
   - In the kidney causing haematuria.
2. **Dilatations are aneurysms.**
3. **Arteritis.**
4. **Small vessel abnormalities.**

INTERMITTENT CLAUDICATION

Claudio means *"I limp"* a Latin word. It is a crampy pain in the muscle seen in the limbs. Due to arterial occlusion, metabolites like lactic acid and substance P accumulate in the muscle and cause pain.

The site of pain depends on site of arterial occlusion.

- Commonest site is calf muscles.
- Pain in foot is due to block in lower tibial and plantar vessels.
- Pain in the calf is due to block in femoropopliteal segment.
- Pain in the thigh is due to block in the superficial femoral artery.
- Pain in the buttock is due to block in the common iliac or aortoiliac segment, often associated with impotence and is called as **Leriche's syndrome.**



Figs 1.260A and B: CT angiogram of aortoiliac segment showing aortoiliac block due to atherosclerosis. Collaterals are also well-developed.

Pain commonly develops when the muscles are exercising. Cause for pain is accumulation of substance P and metabolites. During exercise increased perfusion and increased opening of collaterals wash the metabolites.

Boyd's classification of claudication

Grade I: Patient complains of pain after walking, and distance in which pain develops is called as 'claudication distance'. If patient continues to walk, due to increased blood flow in muscle and opening of collaterals metabolites causing pain are washed away and pain subsides.

Grade II: Pain still persists on continuing walk; but can walk with effort.

Grade III: Patient has to take rest to relieve the pain.

Today's preparations determine tomorrow's achievement.

Claudication

- *Arterial* – typically develops after walking for certain distance and resolves rapidly within 5 minutes once walking is stopped
- *Neurogenic* – pain develops in standing or walking and disappears immediately after stopping walk; normal feeling pulses without ischaemic changes are present. It is usually due to narrow lumbar canal (spinal canal stenosis)
- *Venous* – it is rare but definitely occurs. It is observed in chronic pelvic venous obstruction as a mechanical high venous pressure. It is usually due to iliac vein thrombosis. Peripheral pulses are normal.

Rest Pain



Fig. 1.261: Rest pain in a patient suffering from TAO. Holding the foot reduces the pain slightly.

It is continuous aching in calf or feet and toes or in the region even at rest depending on site of obstruction. It is *'cry of dying nerves'* due to ischaemia of the somatic nerves. It signifies severe decompensated ischaemia. Pain gets aggravated by elevation and is relieved in dependent position of the limb. Pain is more in the distal part like toes and feet. It gets aggravated with movements and pressure. Hyperaesthesia is common association with rest pain.

Claudication is not that common in upper limb but can occur during writing or any upper limb exercise.

Features of arterial stenosis/block in limbs

- Intermittent claudication
- Rest pain
- Cold periphery, numbness, paraesthesia
- Color changes, ulceration, gangrene
- Altered sensation and decreased function/ movements
- Diminished/absent arterial pulsation
- Thrill/bruit over the stenosed artery
- Altered venous filling—normally it is in few seconds; it is delayed in arterial stenosis; it is rapid AV fistula

LIMB ISCHAEMIA

Causes

- Atherosclerosis.
- Embolism (acute).
- Arteriopathies—Buerger's disease, Raynaud's disease, Takayasu's disease.
- Diabetes.
- Scleroderma.
- Physical agents—trauma, tourniquet, radiation injury.

Fontaine classification of limb ischaemia

Stage 1: No clinical symptoms
Stage 2: Intermittent claudication
  2a: Well compensated
  2b: Poorly compensated
Stage 3: Rest pain
Stage 4: Gangrene, ischaemic ulcer

Critical Limb Ischaemia

It is persistently recurring ischaemic rest pain for 2 weeks or ulceration or gangrene of the foot or toes with an ankle systolic pressure < 50 mmHg or toe systolic pressure < 30 mmHg.

Pregangrene

It is the changes in tissue which indicates that blood supply is inadequate to keep the tissues alive and presents with rest pain, colour changes, oedema, *hyperaesthesia* with or without ischaemic ulceration.

Gangrene

It is macroscopic death of tissue *in situ* with or without putrefaction.



Fig. 1.262: Gangrene of great and little toes in a patient with vascular compromise.

Dry Gangrene

It is dry, dessicated, mummified tissue caused by gradual slowing of blood stream. There is a line of demarcation and is localised.



Fig. 1.263: Gangrene of little toe with line of demarcation.

Wet Gangrene

It is due to both arterial and venous block along with superadded infection and putrefaction. It spreads proximally and there is no line of demarcation. It spreads faster.



Fig. 1.264: Ischaemic ulcer foot in a diabetic patient.



Fig. 1.265: Ischaemic right leg. Note the wasting and hair loss.

Organs in which gangrene can develop—appendix, bowel, gallbladder, testis, pancreas.

Necrosis*:* It is microscopic cell death.

Sequestrum is dead bone *in situ.*

Slough is dead soft tissue.

Line of Demarcation

It is a line between viable and dying tissue indicated by a band of hyperaemia. It also indicates that disease is well-localised. *Final separation* between healthy and

Severely diseased distal aorta in atherosclerosis on arteriography is called as "shaggy aorta".

gangrenous tissue occurs by development of a layer of granulation tissue in between. It is hyperaesthetic due to *exposed nerve endings.*

Type of Separation

- Separation by *aseptic* ulceration is seen in dry gangrene.
- Separation by *septic* ulceration is seen in infected condition and *wet* gangrene.

FEATURES OF ISCHAEMIA

- Marked pallor, purple blue cyanosed appearance.
- Thinning of skin
- Diminished hair
- Loss of subcutaneous fat
- Brittle nails, with transverse ridges
- Ulceration in digits
- Wasting of muscles
- Tenderness and temperature (cold)



Fig. 1.266: Gangrene of all toes at their distal phalanges. All ischaemic features are obvious.



Fig. 1.267: Ischaemic changes in the right leg. Third and fourth toes are gangrenous with line of demarcation. Great and little toes are partly gangrenous. There are ischaemic features in the right foot and leg like hair loss/skin changes/ wasting.

Aortoiliac block causes claudication in both buttocks, thighs, and calves; absence of femoral and distal pulses bruit over aortoiliac region. *Impotence* occurs due to defective perfusion through internal iliac arteries and so into the penis causing erectile dysfunction (*Leriche's syndrome*).

Iliac artery obstruction causes claudication in thigh and calf; bruit over iliacs with absence of femoral and distal pulses.

Femoropopliteal obstruction causes claudication in calf with absence of distal pulses but with palpable femoral.

Distal obstruction shows absence of ankle pulses with palpable femoral and popliteal pulses.

Paraesthesia over the skin of the foot is due to shunting of blood from the skin to muscles in deeper plane.

Sensation in gangrenous area is absent. But, at the line of demarcation, skin is hyperaesthetic.

- **Delayed capillary filling**: Blanched nails or pulp of fingers, on pressure, will show delay in refilling (to turn pink) after release of pressure.
- **Delayed venous refilling**: Two fingers are placed over the vein. Finger nearest to heart is moved away so as to empty the vein. Distal finger is released to observe the venous refilling. Delay in filling is called *Harvey's sign*, signifies ischaemia. Venous filling is increased in AV fistulas.
- **Crossed leg test (Fuchsig's test):** Patient is asked to sit with the legs crossed one over the other so that the popliteal fossa of one leg will lie against the knee of other leg. Oscillatory movements of foot can be observed synchronous with the popliteal artery pulsation. This movement is absent with blockage of popliteal artery.
- **Disappearing pulse syndrome:** Exercise the limb after feeling the pulse. Pulse disappears once patient develops claudication. It is due to vasodilatation and increased vascular space occurring as the result of exercise wherein arterial tension can not be kept adequately and so pulse will disappear (unmasking the arterial obstruction).
- **Buerger's postural test:** Patient lying down on his back is asked to raise the leg above. In normal individuals, limb (plantar aspect of foot) remains pink even after raising above 90°. Ischaemic limb, when elevated shows marked pallor and empty veins. The angle in which pallor develops is called as *Buerger's angle of vascular insufficiency*. If this angle is < 30°, it indicates severe ischaemia.
- **Systolic bruit** may be heard over stenosed artery like subclavian artery, femoral artery, carotid artery, iliacs, renal artery.
- **Adson's test (Scalene manoeuvre):** In a patient sitting on a stool, the radial pulse is felt. The patient is then asked to take a deep breath (to allow the rib cage to move upwards so as to narrow the cervico axillary channel) and turn the face to same side (to contract scalenus anterior muscle so as to narrow the scalene

triangle). If the radial pulse disappears or become feeble it signifies cervical rib or scalenus anticus syndrome.

- **Elevated arm stress test; (EAST) or modified Roos test:** With both the arms kept in 90° abduction and external rotation position, patient is asked to make a fist and release repeatedly for 5 minutes. In normal side, patient will continue to do the manoeuvre whereas in diseased (Thoracic outlet syndrome) side patient gets pain and paraesthesia with difficulty in continuing the manoeuvre. Patient drops the arm down to relieve the symptoms.
- **Costoclavicular compression manoeuvre (Falconer test):** Radial pulse becomes absent when patient draws his shoulders backwards and downwards in excessive military position. This is because at this position, subclavian artery is compressed between first rib and clavicle, leading to feeble or absent radial pulse.
- **Hyperabduction manoeuvre (Halsted test):** When affected arm is hyperabducted, radial pulse becomes absent or feeble due to compression of artery by pectoralis minor tendon.
- **Allen's test:** It is done to find out the patency of radial and ulnar arteries. Both the arteries are compressed near the wrist and allowed to blanch completely in one minute. (In the mean time patient closes and opens the fist several times for further venous outflow.) Palm appears pale and white. One of the arteries is released and colour of hand is noted. Normally hand will become pink and flushed in no time; whereas in obstruction, the area will still remain pale. Other artery is also released and looked for changes in hand. Often test has to be repeated to get proper information.
- Abdomen should be examined for the presence of abdominal *aortic aneurysms*. It presents as pulsatile mass above the umbilicus, vertically placed, smooth, soft, nonmobile, not moving with respiration, resonant on percussion. Expansile pulsation is confirmed by placing the patient in knee-elbow position.

Palpation of Blood Vessels

- *Dorsalis pedis artery* is felt just lateral to the extensor hallucis longus tendon at the proximal end of first web space, felt against the navicular and middle cuneiform bones. It is absent in 10% cases.
- *Posterior tibial artery* is felt against the calcaneum just behind the medial malleolus midway between it and tendon achilles.
- *Anterior tibial artery* is felt anteriorly in the midway between the two malleoli against the lower end of tibia just above the ankle joint, lateral to extensor hallucis longus tendon.
- *Popliteal artery* is difficult to feel. It is palpated better in prone position with knee flexed about 90-130°, to relax the popliteal fascia. It is felt in the lower part of the fossa over the flat posterior surface of upper end of tibia. In upper end of the fossa, artery is not felt as there is no bony area in intercondylar region.
- *Femoral artery* in the groin is felt just below the inguinal ligament midway between anterior superior iliac spine and pubic symphysis. Often hip has to be flexed for about 10-15° to feel it properly.
- *Radial artery* is felt at the wrist on the lateral aspect against lower end of the front of radius.
- *Ulnar artery* is felt at the wrist on the medial aspect against lower end of the front of ulna.
- *Brachial artery* is felt in front of the elbow just medial to biceps brachii tendon.
- *Axillary artery* is felt in apex of the axilla against shaft of the humerus.
- *Subclavian artery* is felt against first rib just above the middle of the clavicle.
- *Facial artery* is felt against body of mandible at the insertion of masseter.
- *Common carotid artery* is felt medial to sternomastoid muscle at the level of thyroid cartilage against carotid tubercle (Chassaigne tubercle) of transverse process of 6th cervical vertebra (in carotid triangle).
- *Superficial temporal artery* is felt just in front of the tragus of the ear against zygomatic bone.

INVESTIGATIONS FOR ARTERIAL DISEASES

- Blood tests: Hb%, blood sugar, lipid profile, peripheral smear, platelet count.
- Doppler to find out the site of block - hand held Doppler.
- Duplex scan: It is combination of B mode ultrasound and Doppler study. Difference in transmitted beam of the ultrasound and reflected beam is called as *Doppler shift* which is assessed and converted into audible signals. It is used to study the site, extent, severity of block, and also about collaterals. Audible sound is heard with normal flow, and sound is important. Turbulence is heard when there is stenosed partially blocked artery. Audible sound will be absent if there is complete block. Using Doppler probe blood pressure at various levels can be assessed. Pulse wave tracing along the artery is also important.

> *Half of us are blind, few of us feel and we are all deaf.*—William Osler

- Treadmill test/ECG/echocradiography to assess cardiac/coronary status.
- Ultrasound abdomen to see aneurysm/aorta and its anatomical changes/other vessels in the abdomen/other organs.
- Plethysmography.
- ***Ankle-brachial pressure index***:
  Normally it is 1. If it is less than 0.9, it means ischaemia is present. If it reaches 0.3 or below then it signifies severe ischaemia with gangrene.
- ***Angiography:***
  Retrograde transfemoral Seldinger angiography: Commonly done. It is done only when femorals are felt. If femoral pulsation is not felt then angiogram is done either *transbrachially (left brachial artery)*, or *transaortic*.

Indications for angiogram

1. TAO
2. Atherosclerosis
3. Raynaud's phenomenon
4. AV fistulas
5. Haemangiomas
6. Thoracic outlet syndrome (e.g. cervical rib)
7. Aneurysms
8. Neoplastic conditions

Other angiograms are carotid angiogram, coeliac angiogram, superior mesenteric angiogram, coronary angiogram.



Fig. 1.268: Seldinger angiogram – retrograde femoral approach. (*Courtesy by Dr Vasudeva Rao, Vascular surgeon Manipal Hospital Bengaluru*).

Seldinger technique (steps)

- Arterial cannula is passed into the artery, e.g. femoral artery
- Needle is removed and guide wire is passed through the cannula
- Cannula is removed
- Dilator is passed over the guide wire
- Dilator is removed and arterial catheter is passed over the guide wire
- Guide wire is removed

Water soluble iodine dye (Sodium diatrizoate) is injected. X-rays are taken to see the block, its extent in the affected limb.

In TAO *cork screw* appearance is characteristic**.** *Distal run off* through collaterals is also important.

If catheter is passed still proximally angiogram of opposite side is possible.

Seldinger technique can also be used (to study) to do renal angiogram to detect renal artery stenosis, renal carcinomas, renal anomalies (vascular).

Complications of retrograde angiogram

1. Bleeding
2. Dissection of vessel wall
3. Haematoma formation
4. Thrombosis
5. Infection
6. Anaphylaxis

- *Direct aortic angiogram*, practiced earlier, is discouraged at present because of the risk of aortic dissection and paraplegia due to blockage of anterior spinal artery.

Digital Subtraction Angiography (DSA)

Here vessel (artery) is delineated in a better way by eliminating other tissues through computer system. AV fistulas, haemangiomas, lesion in circle of Willis, vascular tumours, other vascular anomalies are well made out.

Dye is injected either to an artery or vein. Injecting into a vein is technically easier but larger dose of dye is required. Injecting into an artery is technically difficult but small dose of dye is sufficient.

Advantages: Only vascular system is visualised; other systems are eliminated by computer subtraction. Small lesion, its location and details are better observed with greater clarity.



Fig. 1.269: DSA showing total block of right common iliac artery due to thrombosis.

Disadvantages: Cost factor and availability.

Complications: Anaphylaxis, bleeding, thrombosis.

- CT angiogram/MR angiogram.



Fig. 1.270: CT angiogram showing abdominal aorta, branches and renal vessels.

Treatment Plan for Arterial Diseases

- Stopping smoking; supervised exercises; regular controlled walk, diet (carbohydrate and lipid free diet); care of limbs
- Control of hypertension, diabetes; antilipid drugs like atorvastatin 10 mg or pravastatin 40 mg; low dose aspirin 75 mg; clopidogrel 75 mg; vasodilators; ticlopidine; dipyridamole; cilostazole 100 mg are different drugs used.
- Percutaneous transluminal balloon angioplasty (PTA) done mainly to iliac arteries, subclavian arteries, renal artery, carotid and occasionally leg arteries and mesenteric or gastrointestinal arteries. PTA with stenting using expandable stents to the arteries is also often done to get a better result.
- Bypass graft surgeries – aortofemoral; femorofemoral; iliofemoral etc. Dacron, human umbilical vein (3 mm), saphenous vein; PTFE (Polytetraflouoro ethylene) – are different grafts used.
- Endarterectomy, atherectomy, thrombectomy, profundaplasty etc.

DISEASES OF THE ARTERIES



Fig. 1.271: Angiogram showing atherosclerosis.

1. Atherosclerosis:

RISK FACTORS

- Hypercholesterolaemia, hypertriglyceridaemia and hyperlipidaemia
- Cigarette smoking
- Hypertension
- Diabetes mellitus
- Age—elderly
- Common in males
- Sedentary life
- Family history

The peroneal artery replaces the anterior tibial artery in 5% of cases.—Solly M Cohen

2. Thromboangiitis obliterans (TAO) (Buerger's disease).
3. Raynaud's disease.
4. Conditions causing Raynaud's phenomenon: Like scleroderma, rheumatoid arthritis, SLE, granulomatosis, vasculitis of other causes.
5. Embolus.
6. Aneurysms.
7. Other causes: Fibromuscular dysplasia, radiation, Takayasu's arteritis.

THROMBOANGIITIS OBLITERANS (TAO)

Syn. Buerger's Disease

> ***The disease (occurs) in young adults between the ages of twenty and thirty-five or forty years…. Upon examination we see that one or both feet are markedly blanched, almost cadaveric in appearance, cold to the touch, and that neither the dorsalis pedis nor the posterior tibial artery pulsates…. After months… trophic disturbances make their appearance…. Even before the gangrene, at the ulcerative stage, amputation may become imperative because of the intensity of the pain.***
>
> —**Leo Buerger**
>
> 1908 (Professor of Urology 1879 to 1943)

It is a disease exclusively seen in males of young age group (Not seen in females due to genetic reason). Seen only in smokers and tobacco users. Always starts in lower limb, may start on one side and later on the other side. Upper limb involvement occurs only after lower limb is diseased.

It is nonatherosclerotic inflammatory disorder involving medium sized and distal vessels with cell mediated sensitivity to type I and type III collagen.



Fig. 1.272: Ischaemic features in upper and lower limbs (four limbs).

Pathogenesis

Smoke contains *carbon monoxide* and *nicotinic acid*

↓

Causes initially vasospasm and hyperplasia of intima

↓

Thrombosis and so obliteration of vessels occur, commonly medium sized vessels are involved.

↓

Panarteritis is common.
Usually involvement is segmental.

↓

Eventually artery, vein and nerve are together involved

↓

Nerve involvement causes rest pain.

↓

Patient presents with features of ischaemia in the limb

↓

Once blockage occurs, plenty of collaterals open up depending on the site of blockage either around knee joint or around buttock.

Once collaterals open up, through these collaterals, blood supply is maintained to the ischaemic area.

↓

It is called as *compensatory peripheral vascular disease*.

↓

If patient continues to smoke, disease progresses into the collaterals, blocking them eventually, leading to severe ischaemia and is called as *decompensatory peripheral vascular disease*. It is presently called as ***critical limb ischaemia***. It causes rest pain, ulceration, gangrene.

Smoking index (SI) =
Number of cigarettes smoked per day × Number of years of smoking
SI > 300 is a Risk Factor

Pack Years Index(PYI) =
Number of years of smoking × Number of *packets of* cigarettes per day
PYI > 40 is a Risk factor

Shianoya's criteria for Buerger's disease

1. Tobacco use. Only in males
2. Disease starts before 45 years
3. Distal extremity involved first without embolic or atherosclerotic features
4. Absence of diabetes mellitus or hyperlipidaemia
5. With or without thrombophlebitis



Fig. 1.273: Gangrene of leg and foot.



Fig. 1.276: Dry gangrene of leg. Patient needed above knee amputation.



Fig. 1.274: Ischaemic ulceration in the foot.



Fig. 1.277: Ischaemic ulcer foot. Note the poor blood supply and unhealthy granulation tissue.

Clinical Features

- Intermittent claudication in foot and calf progressing to rest pain, ulceration, gangrene.
- Recurrent migratory superficial thrombophlebitis.



Fig. 1.275: Gangrene of mid toes, distal part.



Fig. 1.278: Bilateral TAO in a young male with large ischaemic ulcers. Patient underwent amputation of both limbs (Below-knee).

Dacron is polyethylene terephthalate.



Fig. 1.279: Great toe gangrene. Note the clear line of demarcation.



Fig. 1.280: Gangrene foot.

Investigations

1. Hb%. Blood sugar.
2. Arterial Doppler and Duplex scan (Doppler + B mode U/S).
3. ***Transfemoral retrograde angiogram*** through Seldinger technique-
    - Shows blockage – sites, extent, and severity.
    - *Cork screw* appearance of the vessel due to dilatation of vasa vasorum.
    - Inverted tree/spider leg collaterals.
    - *Severe vasospasm causing corrugated / rippled artery.*
    - *Distal run off* is amount of dye filling in the main vessel distal to the obstruction through collaterals. If distal run off is good then ischaemia is compensated. If distal run off is poor then ischaemia is decompensated.
4. ***Transbrachial angiogram*:** If femorals are not felt, then transbrachial angiogram (through left side brachial artery—left subclavian artery—and so to descending aorta) should be done.



Fig. 1.281: CT angiogram of lower limb (leg area) showing segmental block.



Fig. 1.282: Angiogram showing block in main vessel with opened up collaterals and adequate distal run off.



Fig. 1.283: Angiogram showing adequate collaterals.

5. Ultra sound abdomen to see abdominal aorta for block/aneurysm.
6. Vein, artery, nerve biopsy.

Treatment

Stop smoking. "Opt for either cigarette or limb, but not both."

Drugs

- Vasodilators, e.g. nifedepine.
- Pentoxiphylline increases the flexibility of RBC's and helps them reach the microcirculation in a better way so as to increase the oxygenation.
- Low dose of aspirin - 75 mg once a day – antithrombin activity.
- Prostacyclins, Ticlopidine, Praxilene.
- Clopidogrel 75 mg; atorvastatin 10 mg; parvostatin 40 mg; cilostazole 100 mg bid – is a phosphodiesterase inhibitor which improves circulation.

All drugs act at the collateral level than on the diseased vessel.

Care of the Limbs

- Buerger's position and exercise – regular graded exercises upto the point of claudication improves the collateral circulation.

Buerger's exercise, Buerger's position, heel raise, analgesics, care of feet (Chiropady), *proper footwear are advised.*

Surgery

1. *Lumbar sympathectomy* to increase the cutaneous perfusion so as to promote ulcer healing.
2. *Omentoplasty* to revascularise the affected limb.
3. *Profundaplasty* is done for blockage in profunda femoris artery so as to open more collaterals across the knee joint. (It often makes better perfusion to the knee joint and flap of below-knee amputation.)
4. *Amputations* are done at different levels depending on site, severity and extent of vessel occlusion. Usually either below- knee or above-knee amputations are done.
5. Ilzarov method of bone lengthening helps in improving the rest pain and claudication by creating neoosteogenesis and improving the overall blood supply to the limb.

Gene Therapy

- Intramuscular injection of vascular endothelial growth factor (VEGF) which is an endothelial cell mitogen that promotes angiogenesis.

TAKAYASU'S ARTERITIS (Pulseless disease)

- It is pan-arteritis involving aortic arch and branches arising from aorta.
- Of unknown aetiology probably immunological.
- It is common in young females (85%).
- Commonest site is subclavian artery (85%).

Clinical Features

- Fever, myalgia, arthralgia.
- Visual disturbances.
- Upper limb claudication.
- Absence of peripheral pulses.
- Hypertension.
- Bruit.

Complications

- Ischaemia.
- Embolism.
- Myocardial infarction.

Investigations

- DSA.
- MR angiography.
- Doppler.

Treatment

- To suppress immunity.
  Prednisolone – 50 mg/day.
  Cyclophosphamide.
- Vascular reconstruction.

RAYNAUD'S PHENOMENON

> ***Under the influence of a very moderate cold, and even at the height of summer, she (case 1) sees her fingers become ex-sanguine, completely insensible, and of a whitish yellow colour…. One might indeed have suspected that the local asphyxia was connected with a spasmodic state of the vessels,…a functional trouble localised to the arterioles immediately contiguous to the capillaries.*** **—Maurice Raynaud,** 1862

The art of seeing invisible things is called as 'clinical vision'.

It is an episodic vasospasm, i.e. arteriolar spasm. It leads to sequence of clinical features called as Raynaud's syndrome.

Raynaud's syndrome

Sequence of clinical features due to arteriolar spasm.

1. *Local syncope:* It is due to vasospasm, causing white cold palm and digits along with tingling and numbness
2. *Local asphyxia*: It is due to accumulation of deoxygenated blood as the result of vasospasm causing bluish discolouration of palm and digits with burning sensation (due to accumulated metabolites)
3. *Local recovery:* It is due to relief of spasm in the arteriole, leading to return of blood to the circulation causing flushing and pain in digits and palm (pain is due to increased tissue tension)
4. *Local gangrene*: If spasm persists more than ischaemic time (more than one hour in upper limb), then digits go for ulceration and gangrene. Does not occur regularly but is an occasional phenomenon in the cycle

Coffman criteria for Raynaud's syndrome – "episodic attacks of well-demarcated reversible self limiting colour changes for 1–20 minutes on exposure to cold/emotional stimuli and is symmetrical/bilateral lasting for 2 years".

Causes for Raynaud's Phenomenon

1. ***Raynaud's disease***: It is seen in females, usually bilateral.

   It occurs in upper limb with normal peripheral pulses.

   It is due to upper limb (hand) arteriolar spasm as a result of abnormal sensitivity to cold. Patient develops blanching, cyanosis and later flushing as in Raynaud's syndrome. Occasionally if spasm persists it results in gangrene. Symptoms can be precipitated and observed by placing hands in cold water.
2. Working with ***vibrating tools***: Like pneumatic road drills, chain saws, wood cutting, fishermen travelling in machine boats.
3. ***Collagen vascular diseases***: Like Scleroderma, Rheumatoid diseases causing vasculitis (all autoimmune diseases).
4. ***Other causes***: Cervical rib, Buerger's disease, Scalene syndrome.

It is often associated with CREST syndrome. (**C**alcinosis cutis**, R**aynaud's phenomenon, **E**sophageal defects, **S**clerodactyly, **T**elangiectasia).

Types of Raynaud's phenomenon:

1. Vasospastic
2. Obliterative

Raynaud's can be

- *Primary Raynaud's* is an idiopathic vasospastic disorder without underlying identifiable causes. Usually there is no significant pain in primary type. Primary is probably due to increased sensitivity of alpha 2 receptors to non-epinephrine; decreased nitric oxide and endothelin 1 in endothelial cells; increased serotonin and thromboxane. It is common in females and younger age group. Usually it is bilateral involving all digits.
- *Secondary Raynaud's* is vasospasm due to some underlying cause. Significant pain will be present especially during rewarming stage. There are positive auto antibodies; equal in both sexes; occurs at any age group; need not be bilateral.

Investigations

- Type is identified by angiogram of hand (DSA/MR angiogram), arterial Doppler/Duplex scan.
- Other investigations required are X-ray of the part, antinuclear antibody (ANA assay) tests specific for different conditions
- Assessment of segmental blood pressure gradient from brachial – forearm – wrist – fingers; finger tip thermography; cold recovery time (normal is less than 10 minute, but in Raynaud's it is more, often upto 30 minutes); reactive hyperaemia time (pneumatic cuff is inflated and kept for 5 minutes and released to observe hyperaemia); nail fold capillary microscopy; Laser Doppler flux to assess microvascular perfusion of ginger skin – are *special methods* of evaluations.
- Other routine investigations for arterial diseases like blood sugar/lipid profile/hypercoagulability status.

Treatment

- Treat the cause.
- Avoid precipitating factors - protect from cold/proper dress/hand warmer electrical or chemical/hand gloves.
- Vasodilators/pentoxiphylline/low dose aspirin (75-100 mg per day)
- ACE inhibitors, nitrates, endothelin inhibitors (bosentan), epoprostenol – prostaglandin a potent vasodilator and antiplatelet drug (continuous intravenous infusion can be given), iloprost – prostacycline analogue, PG E1, misoprostal (oral PG E 1) – are all tried at different stages of the disease.

- Cervical sympathectomy – is used for non healing digital ulceration. Not very beneficial to Raynaud's syndrome.

TREATMENT OF ARTERIAL DISEASES

a. Medical

General measures:
- Stop smoking.
- Reduction of weight.
- Change in life style.
- Exercise.
- Care of feet.
- Control of diabetes and hypertension.
- Buerger's position and exercise.

Drugs:
- Nifedepine, praxilene, pentoxiphylline, low dose aspirin, prostacycline, dipyridamole, ticlopidine.
- Clopidogrel (75 mg).
- Cilostazol (type III phosphodiesterase inhibitor) 100 mg BD.

b. Surgery

1. ***Percutaneous transluminal balloon angioplasty (PTA):*** Through transfemoral Seldinger approach, initially angiogram is done. Then under guidance (fluoroscopic) stenosed area is approached. Balloon of the angioplasty catheter is inflated at stenosed area *for one minute* and repeated if required. Catheter is withdrawn. It is useful in cases of localised stenosed areas.
   Complications: Thrombosis, bleeding, sepsis.



Fig. 1.284: Percutaneous transluminal balloon angioplasty (PTA). Note the inflated balloons on both side iliac arteries.



Fig. 1.285: DSA showing left sided aorto iliac block and correction after doing PTA.



Fig. 1.286: DSA showing superior mesenteric artery stenosis. It is corrected by PTA.

2. ***Atherectomy:*** It is removal of atheroma either through open surgery or by percutaneous route from the wall of the vessels.
3. ***Thrombectomy:*** It is removal of thrombus through an arteriotomy of larger vessels. Done in aortoiliac, femoropopliteal region.
4. ***Endarterectomy:*** It is removal of thrombus along with diseased intima through an arteriotomy. Endothelium of the vessel is removed, hence the name.
5. Placement of ***intraluminal stent for localised stenosis***.
6. ***Profundaplasty:*** It is done when there is localised block in opening of profunda femoris (deep femoral).

Learn to see, learn to hear, learn to feel, learn to smell—that is clinical method.

Profunda femoris is opened, thrombus if present, is removed. Opening is widened using either venous or synthetic (Dacron or PTFE) grafts. This procedure allows collaterals across the knee joint to open through profunda femoris and so gives good blood supply below-knee level and may prevent patient going in for above-knee amputation.

(May be able to save knee joint with below-knee amputation with better prosthesis.)


Atheroma
Artery
Artery
Arteriotomy
Atheroma intima removed
Ring stripper

Fig. 1.287: Endarterectomy technique. Both thrombus and diseased intima are removed through an arteriotomy. Often ring stripper is used to remove the atheromatous plaque.


Common iliac artery
Internal iliac artery
External iliac artery
Ing ligament
Common femoral artery
(Deep femoral artery) profunda femoris artery
Superficial femoral artery (blocked)
Dacron graft

Fig. 1.288: Profundaplasty for deep femoral block.

7. ***Reverse saphenous vein graft***: In case of femoro-popliteal block, saphenous vein is dissected out, reversed and sutured above to the femoral artery and below to popliteal segment so as to bypass the blood through reverse saphenous vein graft. Saphenous vein is reversed to nullify the action of valves so as to allow easy flow of blood.
8. ***In situ saphenous vein graft:*** It is arterialisation of saphenous vein. Saphenous vein intact in same position is sutured above and below the blocked femoropopliteal region to bypass the blood across. Venous valves are removed through valvulotomy instrument so as to allow the blood to pass. Here nutrient supply of vein is left intact with proximal part of the vein sutured to wider part of the femoral artery, narrow distal part is sutured to narrow part of the artery.
9. ***Arterial/venous grafts***:

Synthetic:

- Dacron woven graft
- Dacron knitted graft
- PTFE—Polytetrafluoroethylene graft.

Natural:

- Internal mammary artery (ideal one)
- Long saphenous vein either reverse or *in situ*
- Umbilical vein graft (cryo preserved) - 3 mm vein is the minimum diameter required
  Grafts of different length and size are available

Different procedures

- Aorto femoral bypass graft (end to side) - 5% mortality.
- Ileo-femoral bypass graft.
- Femoro-femoral bypass graft.
- Axillo femoral graft.
- Femoro-popliteal graft.
- Femorodistal graft.
- Axillo-femoral graft.

Problems with grafts: Leak, infection, thrombosis, cost factor, availability, reblock.


Bypass graft
Occluded vessel

Fig. 1.289: Bypass graft.

Note: Angioscope is used to visualise the valves in saphenous vein or to visualise the completion of the by pass grafts like Femoro-distal graft.



Fig. 1.290: Femoropopliteal bypass graft.



Fig. 1.291: Aorto-femoral bypass graft (End to side).



Fig. 1.292: On table picture of aorto-femoral arterial graft.

10. ***Cervico-thoracic pre ganglionic sympathectomy*:** It is removal of 2nd and 3rd thoracic ganglia which contains cells of postganglionic fibres supplying the upper limb. Preganglionic white rami communicantes fibres from 2nd and 3rd sympathetic nerves enter thoracic T1 ganglion and supplies head and neck region through upper part of the stellate ganglion. Pre ganglionic sympathetic nerve entering the 2nd and 3rd ganglia from below, supplies sympathetic fibres for upper limb through the lower part of the stellate ganglion. In cervical sympathectomy for upper limb ischaemia, lower part of stellate ganglion with Kuntz nerve is divided. For head and neck hyperhidrosis entire stellate ganglion should be removed which leads to development of Horner's syndrome. For hyperhidrosis of axillary area, along with stellate ganglion upper four thoracic ganglia has to be removed.

Indications:
- Cervical rib with vascular manifestations—Useful
- Raynaud's phenomenon—Useful
- Hyperhidrosis—Very useful
- Upper limb vasospasm due to other causes—Useful
- Acrocyanosis—Useful
- Causalgia—Very useful
- Sudeck's osteodystrophy

Not just 'Go' through the life, but better 'Grow' through the life.

Approaches



Fig. 1.293: Cervical sympathectomy scar in the neck and patient has developed Horner's syndrome. Healed ulcer over tip of index finger on left side is seen. Patient is asymptomatic after sympathectomy.

a. *Supraclavicular approach:* Through a supraclavicular incision sternomastoid, (omohyoid is retracted or divided) scalenus anterior muscles are divided. Phrenic nerve is displaced medially; subclavian artery is pushed downwards; thyrocervical trunk is identified and ligated securely, suprapleural membrane is depressed, stellate ganglion is identified in the neck of the first rib. All rami communicantes from second and third ganglia are divided. Grey ramus from second ganglion to first thoracic nerve called as *Kuntz nerve* is also divided.

Complications
- Bleeding
- Injury to subclavian artery and nerves
- Pneumothorax and haemopneumothorax
- Horner's syndrome with ptosis, miosis, anhydrosis, enophthalmos

b. *Transthoracic/axillary approach (Hedley atkins)*: This gives better visibility and easier removal of rami, lower down compared to supraclavicular approach.

c. *Thoracoscopic sympathectomy* is the choice, and popular approach at present.
Advantages are better visibility with magnification, less trauma of access (wound), faster recovery, and precise.



Fig. 1.294: Ptosis of right eye in Horner's syndrome.

11. ***Lumbar sympathectomy***:

Indications:
- Peripheral vascular disease like TAO.
- To promote healing of cutaneous ulcers.
- To change level of amputation and to make flaps to heal better after amputation.
- Causalgia of lower limb (it is common in upper limb).
- Hyperhidrosis.

Principle: It increases the cutaneous blood supply thereby promoting healing of ulcer and skin flaps in amputation. It is a preganglionic sympathecetomy. Ganglion L2 and L3 supplies legs below knee level. L1 supplies upper part of thigh and buttock region. L1 lies under the crus of diaphragm. L4 lies under the common iliac vessels below.

Procedure:
Under general or spinal anaesthesia, ganglia are approached through a transverse incision in the loin at the level of umbilicus, through extraperitoneal approach, by dividing external oblique, and splitting internal oblique, and transverse abdominis muscles. Inferior vena cava on right side, aorta on left side are identified. Sympathetic chain is identified by its rami. L_2, L_3, L_4, L_5 ganglia are removed. L_2 is identified by its size (**Larger**) and more number of rami. L_1 is retained on one side in bilateral cases. If both are removed it will lead to failure of ejaculation and so sterility *(Dry ejaculation).*



Fig. 1.295: Lumbar sympathectomy scar with ischaemic ulcer foot showing healing sign.

Complications:

- Injury to IVC or aorta
- Bleeding lumbar veins
- Spinal vessel spasm and so ischaemia of spinal cord and paraplegia, dry ejaculation
- Injury to bowel and ureter
- Wound infection and abscess formation

Its effects are only temporary (3-4 wk). Long term results are doubtful. It can be combined with omentoplasty.

It can also be done along with below-knee amputation to increase the blood supply of skin flap so as to have better healing.

Limb will become warmer immediately after sympathectomy.

12. ***Chemical sympathectomy:*** It is done in lateral position using a long spinal needle under local anaesthesia. Position is confirmed by injecting dye under fluoroscopy. Later 5 ml of *phenol* in water or absolute alcohol is injected lateral to the vertebral bodies of fourth and second lumbar vertebrae. Care should be taken to see that the needle does not enter IVC or aorta.

    Procedure is contraindicated in patients with *bleeding disorders* and in patients who are on *anticoagulants.*

13. ***Omentoplasty:***

Indications:

- Peripheral vascular disease—to improve circulation
- For lymphoedema, it helps by providing lymphatics and so to drain lymph from the limb
- It is also tried for revascularisation of pharynx, cranial cavity



Figs 1.296A to C: Omentoplasty procedure for revascularisation of the ischaemic limb.

Omentum is supplied by omental vessels

Coeliac artery
↓
Right gastric artery — Splenic artery
↓ ↓
Gastroduodenal artery — Left gastroepiploic artery
↓ ↓
Right gastroepiploic artery → *Omental vessels*

Absolute diagnosis are unsafe and are made at the expense of the conscience.—William Osler

Four layers of omentum has got omental arcades of vessels. Omentum is also rich in lymphatics. It has got adhesive property. By retaining one of the pedicles, omentum can be mobilised so as to reach the limb to maintain the circulation. It can also be mobilised up to the ankle. It promotes ulcer healing, reduces the pain and controls the features of ischaemia. It can also be used in upper limb ischaemia. But, if patient continues to smoke, disease spreads to these omental vessels also. Often it can be mobilised to both lower limbs in bilateral diseases.

Complications of omentoplasty:

- Abdominal sepsis.
- Incisional hernia, where omental pedicle is tunneled into the limb from the abdomen.
- Adhesions and intestinal obstruction.

Procedure: Under general anaesthesia, abdomen is opened with upper midline incision. Omental vessels are identified. Omentum with its blood supply is carefully mobilised to get an adequate length. Lengthened, mobilised omentum is brought into the subcutaneous plane through abdominal wall, lateral to the lower part of rectus muscle. Later this pedicle is mobilised in the subcutaneous tunnel across the leg, burried in the deep fascia.

14. ***Other treatment methods***: *Amputations* are done at different levels depending on extent of gangrene, site of block, amount of collaterals.



Fig. 1.297: Below knee amputation stump which is also ischaemic. Patient underwent below knee amputation for gangrene foot. But patient might need above knee amputation.

SUBCLAVIAN STEAL SYNDROME

Following obstruction of the first part of subclavian artery, vertebral artery provides collateral circulation to the arm by reversing its blood flow. This causes *cerebral ischaemia with syncopal attacks*, visual disturbances, diminished blood pressure in the affected limb.

Symptoms are aggravated by arm exercise.

Javid test: Here compression of carotid artery makes ipsilateral radial pulse feeble.



Fig. 1.298: Subclavian steal syndrome.

Investigations

Duplex scan and angiogram. DSA is useful.

Treatment

- Transluminal balloon angioplasty.
- Endarterectomy or bypass graft. (Common carotid- Subclavian graft).

ACUTE ARTERIAL OCCLUSION

Causes

1. Trauma.
2. Embolism.

TRAUMATIC ACUTE ARTERIAL OCCLUSION

Causes

1. Thrombus due to trauma.
2. Subintimal haematoma.
3. Acute compartment syndrome.
4. During femoral or brachial arterial catheterisation for either diagnostic or therapeutic procedures.

Clinical Features

History of trauma, *pain, swelling at the site, pallor, pulselessness, cold limb.*

Investigation

Duplex scan, Angiogram.

Treatment

Wound is explored and tear in the artery is identified. It is sutured using nonabsorbable monofilament material, *polypropylene 6-0*. Often venous or dacron graft is required for interposition.

Proper antibiotics and heparin are required to prevent thrombosis of the vessel. Later patient is advised to take oral warfarin for maintenance.

Compartment syndrome is common in anterior compartment of leg and in front of forearm. Here because of the closed compartment, pressure increases following fracture, haematoma which compresses over the vessel. It leads to blockade of vessel causing acute ischaemia of the limb presenting with severe pain, pallor, pulselessness.

Treatment: Immediate decompression by longitudinal fasciotomy, is the treatment of choice, wherein deep fascia is cut adequately to relieve the compression. Otherwise limb may go for severe ischaemia, gangrene and may land in amputation.

Associated fractures, haematoma, vessel tear has to be managed accordingly.

EMBOLISM

It is due to a solid, liquid or gaseous, material which is floating and travelling in the blood stream, eventually blocking the vessel on its pathway.

1. ***Arterial emboli:*** *Source*—due to mural thrombus following
    - Myocardial infarction
    - Mitral stenosis
    - Atrial fibrillation
    - Aortic aneurysms
    - Cervical rib causing poststenotic dilatation of subclavian artery
    - Endocarditis
    - Prosthetic valves
2. ***Venous emboli*** are due to DVT causing pulmonary embolism.
3. ***Venous-arterial paradoxical emboli:*** Seen in intracardiac shunt (ASD) or intrapulmonary shunts (A-V malformations) *(Osler-Weber-Rendau syndrome)*
4. ***Fat embolism***.
5. ***Air embolism***.

Effects of Arterial Embolism

1. *Brain:* Blockage at *middle cerebral artery* causes hemiplegia, transient ischaemic attacks (TIA), visual disturbances
2. Blockage at *central retinal artery* causes amaurosis fugax or permanent blindness
3. Blockage at *mesenteric vessels* causes intestinal gangrene
4. Blockage at *renal artery* leads to haematuria, loin pain
5. Blockage at *limb vessels* causes pain, pallor, pulseless, paraesthesia, paresis, ulceration, gangrene
   Most common site of arterial emboli is *common femoral artery*

Features of Embolism

- Earlier history of claudication is absent but history suggestive of disease for source of emboli will be present.
- Sudden, dramatic, rapid development of pain with numbness.
- Limb becomes rapidly cold and mottled with blebs.
- Loss of sensation and movements.
- Absence of distal pulses but forcible, expansile, prominent proximal pulse. Example – prominent femoral artery pulsation with embolic bock at popliteal level.
- Toxic features.

Investigations for Arterial Embolism

- Emergency Doppler angiogram, ECG and echocardiography.
- Relevant tests for origin of emboli.

Note: Once embolism occurs irreversible changes occur distally in 6 hours, so ideal period for intervention is within 6 hours.

Treatment

1. *Embolectomy* is done as early as possible as an emergency operation.
    - Under fluoroscopic guidance, *Fogarty catheter* (interventional radiology) is passed beyond the embolus and balloon is inflated. Catheter is withdrawn out gently with embolus. Procedure has to be repeated until embolectomy is completed and good back bleeding occurs. Angiogram is repeated to confirm the free flow.
    - Postoperatively initially heparin and later oral anticoagulants are used. Procedure is done under general anaesthesia or local anaesthesia.
    - *Open arteriotomy and embolectomy* can be done by *direct approach* and later the arteriotomy has to be

Einstein died of ruptured aortic aneurysm.

sutured. Postoperatively anticoagulants and antibiotics are given.

2. *Intra-arterial thrombolysis using fibrinolysins*: After passing arterial catheter, angiogram is done and agents are injected intraarterially through the arterial catheter.

   Drugs used are:
   - Streptokinase (here lysis occurs in 48 hours).
   - Urokinase.
   - Tissue plasminogen activator (TPA). Alteplase, Reteplase—here lysis occurs in 24 hours.
   - TPA pulse-spray method—here lysis occurs in 6 hours.

Contraindications for thrombolysis
- Recent stroke
- Recent major surgery or major bleed like of varices
- Recent eye surgery
- History suggestive of or confirmed active duodenal /gastric ulcers
- Pregnancy
- Uncontrolled hypertension or coagulation disorders

Note: Heparin should not be used concomitantly with fibrinolytics.

3. Anticoagulant therapy to prevent recurrent emboli.

Immediate infusion of heparin 5000 units intravenously to prevent further extension of thrombus.

SADDLE EMBOLUS

It is an embolus blocking at *bifurcation of aorta.*

Causes

- Mural thrombus after myocardial infarction.
- Mitral stenosis with atrial fibrillation.
- Aortic aneurysm.

The embolus which blocks at aortic bifurcation is usually large.



Fig. 1.299: Saddle embolus blocking the bifurcation of abdominal aorta. It causes severe, rapid, dramatic symptoms.

Clinical Features

- Features of sudden, rapidly progressive ischaemia in both lower limbs.
  ***Note*:** In aortic bifurcation thrombus, there is earlier history of claudication in the buttock often with *Leriche's syndrome*. Symptoms are slow and gradual but not dramatic. Collaterals between aorta and iliac arteries have well-formed and so sudden, rapid development of gangrene will not occur.
- Gangrene of both lower limbs.
- Features of associated infection.

Investigations

- Arterial Doppler.
- Aortic angiogram.
- U/S abdomen.

Treatment

- Initially, heparin is injected intravenously —10,000 units and later 5,000 units subcutaneously 8th hourly.
- Embolectomy can be done using Fogarty's catheter.
- Open arteriotomy and embolectomy can also be tried.
- Antibiotic prophylaxis is given to prevent infection.

EMBOLECTOMY

Indications

Acute embolic blockade of artery commonly seen in common femoral, cranial vessels, mesenteric vessels.

It should be done within 6 hours as after 6 hours irreversible changes occur.

It can be done either in GA/LA.



Fig. 1.300: Embolectomy technique.

Methods

1. *Interventional method* is usually employed using Fogarty's catheter. Good back bleed signifies completeness of embolectomy.

   Intraoperative arteriogram is a must after embolectomy to confirm the adequacy of blood flow.
2. *Open arteriotomy method* is done directly over the artery followed by suturing the artery.

Complications

- Bleeding
- Sepsis
- Thrombosis
- Narrowing
- Incomplete removal





Figs 1.301A and B: Fogarty's catheter. It is 80 cm in length with 4 to 7 French size. It is used for embolectomy. Note the inflated balloon at the tip.

After Embolectomy

Patient is placed in ICU care.
Monitoring with—PTT, thromboplastin time.

FAT EMBOLISM

It is commonly seen after *fracture femur, tibia,* or *multiple fractures* and occasionally following electroconvulsive therapy, usually occurs in 24-72 hours.

It is due to aggregation of chylomicrons, derived from bone marrow, causing fat embolism.

It is often a fatal condition.

Clinical Features

1. *Cerebral*: Drowsy, restlessness, disoriented, constricted pupils, pyrexia, coma.
2. *Pulmonary:* Cyanosis, tachypnoea, right heart failure, froth in mouth and nostrils, fat droplets in sputum, eventually respiratory failure.
3. *Cutaneous*: Petechial haemorrhages in the skin.
4. *Retinal artery emboli* is the earliest sign to appear, causing *striae haemorrhages, fluffy exudates* confirmed on fundoscopic examination.
5. *Kidney*: Blockage in renal arterioles results in fat droplets in urine.

Treatment

- Oxygen.
- Heparinisation.
- Low molecular weight dextran.
- Ventilator support and ICU management.

AIR EMBOLISM

Causes

- Through venous access like IV cannula, commonest cause.
- During artificial pneumothorax.
- During surgeries of neck and axilla.
- Traumatic opening of major veins sucking air inside, causing embolism.
- During fallopian tube insufflation.
- During illegal abortion.

Amount of air required to cause air embolism is 50 ml.

When the air enters the right atrium, it gets churned up forming a foam which enters the right ventricle and blocks the pulmonary artery.

> *In early painful stage the ischemic foot (gangrene threatened) is nearly always pink, the skin being atrophied as though it were stretched tightly over underlying structure.* —Wilfrid G Oakley

Mill-Wheel murmur heard over the precordium through a stethoscope is diagnostic.

Treatment

Patient is placed in Trendelenburg position. By passing a needle, the air has to be aspirated from the right ventricle. Often requires life saving open thoracotomy to aspirate the excess air causing the block.

THERAPEUTIC EMBOLISATION

Indications

1. Haemangiomas.
2. AV fistulas.
3. Malignancies like renal cell carcinoma, hepatoma.
4. Cerebrovascular problems.
5. To arrest haemorrhage from GIT, urinary and respiratory tract.

In bleeding duodenal ulcer or gastric ulcer, embolisation is done to occlude gastroduodenal artery or left gastric artery respectively.

It is also useful in bleeding oesophageal varices, secondaries in liver (mainly due to carcinoids), hepatoma.

Materials used for therapeutic embolisation

- Blood clot
- Gel foam
- Balloons
- Quick setting plastics
- Stainless steel coils
- Human dura
- Plastic microspheres
- Ethyl alcohol
- Wool

CAISSON'S DISEASE OR DECOMPRESSION DISEASE

It occurs due to rapid decompression from high altitude, aircraft, compressed air chambers, deep sea divers causing bubbling of nitrogen which blocks the small vessels.

1. In joints and muscles it causes excruciating pain *(bends).*
2. Spinal cord ischaemia causing neurological deficits.
3. Lungs may be affected causing choking with chest pain, tightness and dry cough.

Treatment

- Oxygen therapy.
- Recompression and gradual decompression in special chamber.

(*Note:* **Reperfusion Injury**—can occur after re-establishment of arterial flow to an ischaemic tissue bed which further leads to tissue death. It is due to sudden release of oxygen-free radicals which blocks the micro circulation, high potassium, myoglobin.)

ANEURYSM

> ***There is no disease more conducive to clinical humility than aneurysm of the aorta.***
> **—William Osler,** Circa 1900

It is an abnormal permanent dilatation of localised segment of arterial system.

True aneurysm contains all three layers of artery.

False aneurysm contains single layer of fibrous tissue as wall of the sac and it usually occurs after trauma.

Types

- *Fusiform*
- *Saccular*
- *Dissecting*



Fig. 1.302: True and false aneurysms. In true type, all layers are intact. In false type all layers breached with haemotoma having a false capsule.



Fig. 1.303: Fusiform and saccular types of aneurysms.



Fig. 1.304: Thoracic aortic aneurysm.

Causes

- Atherosclerosis.
- Syphilis.
- Traumatic.
- Collagen diseases like Marfan's syndrome.

Sites

- Aorta.
- Femoral.
- Popliteal.
- Subclavian.
- Cerebral, mesenteric, renal, splenic arteries.

Commonest is *true, fusiform, atherosclerotic, aortic aneurysms.*

Berry aneurysms are multiple aneurysms occurring in circle of Willis.

Effects of aneurysms

- Thrombosis
- Release of emboli
- Expansion and erosion of adjacent structures like bone
- Rupture

Clinical Features of Aneurysms

1. Swelling at the site which is *pulsatile (expansile)*, smooth, soft, warm, compressible, with thrill on palpation and bruit on auscultation. Swelling reduces in size when pressed proximally.
2. Distal oedema due to venous compression.
3. Altered sensation due to compression of nerves.
4. Erosion into bones, joints, trachea or oesophagus.
5. Aneurysm with thrombosis can throw an embolus causing gangrene of toes, digits, extending often proximally also.

Differential Diagnosis

1. Pyogenic abscess: Abscess has to be always confirmed by aspiration; especially in axilla, popliteal region, groin.
2. Vascular tumours.
3. Pulsating tumours: Sarcomas, pulsating secondaries.
4. Pseudocyst of pancreas mimics aortic aneurysm.
5. AV fistula.

Investigations

- Doppler study, duplex scan, angiogram, DSA.
- Tests relevant for the cause, like blood sugar, lipid profile, echocardiography.

Treatment

- Reconstruction of artery using arterial grafts.
- Arterial endoaneurysmorrhaphy—MATAS. It is done usually for peripheral saccular aneurysm. Matas aneurysmorrhaphy may be restorative or endo-obliterative or reconstructive.
- Therapeutic embolisation.
- Clipping the vessel under guidance (e.g. cranial aneurysms).
- Older methods which are now not used but popular earlier were – wiring of the aneurysmal sac/ wrapping of the aneurysmal sac/ligatures at different levels (ligation just proximal to aneurysmal sac – *Anel's;* ligation proximally proximal to an arterial branch – *Hunter's;* ligation just distal to aneurysmal sac – *Brasdor's*; ligation distally distal to an arterial branch – *Wardrop's*; ligature one proximal and another distal to aneurysmal sac – *Antylus'*).

MYCOTIC ANEURYSM

- It is a ***misnomer***.
- It is not due to fungus but due to bacterial infection.
- Common bacteria are gram-positive organisms *like Staphylococcus aureus (commonest)* and *Streptococcus.*

Unless you try to do something beyond what you have already mastered, you will never grow.



Matas aneurysmorrhaphy for saccular aneurysm

Excision and graft in fusiform aneurysm (dacron graft)

Ligation and exclusion using autologous vein by-pass graft

Excision of aneurysm and by-pass using autologous vein graft

Figs 1.305A to D: Different methods of aneurysm repair. (A) Matas aneurysmorrhaphy for saccular aneurysm. (B) Excision and Dacron grafting. (C) Ligation and exclusion of the aneurysm using autologous vein graft. (D) Excision of aneurysm and bypass using autologous vein graft.

- Common aetiology is bacterial *endocarditis* but could be any infective site.
- Common vessels involved are aorta, visceral, head and neck and intracranial.
- Commonly it is saccular, multilobed, with a narrow neck.
- Patient presents with fever, toxaemia and tender pulsatile mass if it is in the periphery.

Investigations

- Leucocytosis. Positive blood culture, MR or CT angiogram are relevant.

Treatment

- Broad spectrum antibiotics
- Resection of aneurysm; debridement and drainage of the infected aneurysm with adequate blood transfusions.
- Extra-anatomic bypass through uninfected tissue planes to avoid contamination of the graft.
- Long-term antibiotic therapy is necessary.
- It has got 25% mortality.

(Note: *Microbial arteritis with aneurysm* is a different entity is due to bacteraemia occurring in an atherosclerotic vessel due to *Salmonella* infection).

ABDOMINAL ANEURYSM

Abdominal aortic aneurysm is the commonest aortic aneurysm. 2% incidence. More common in males. Smoking is an important risk-factor.

Causes

Atherosclerosis: 95%.

Others: Syphilis, dissecting, traumatic, collagen diseases.

Classification I

- Infrarenal—Commonest 95%.
- Suprarenal 5%.

Classification II

- *Asymptomatic:* Found incidentally either on clinical examination or on angiography or on ultrasound. Repair is required if diameter is over 5.5 cm on ultrasound.
- *Symptomatic without rupture:* Present as *back pain, abdominal pain, mass abdomen* which is smooth, soft, nonmobile, not moving with respiration, vertically placed above the umbilical level, pulsatile both in supine as well as knee-elbow position with same intensity, and resonant on percussion. GIT, urinary,



Figs 1.306A and B: Abdominal aortic aneurysm (A). Thrombosis of the aneurysm (B).

venous symptoms can also occur. Hypertension, diabetes, cardiac problems should be looked for and dealt with.

Investigations

- Blood urea, serum creatinine.
- U/S, aortogram.
- DSA, CT scan, MRI.



Fig. 1.307: CT scan picture showing right arch aorta (anomaly) with thrombosed aneurysm.



Fig. 1.308: Chest X-ray showing aortic aneurysm.

Treatment

If aneurysm is *more than 5.5 cm, then surgery is the choice*. Options are

1. Open surgical aneurysm repair using PTFE or dacron graft.
2. *Endoluminal stent* graft procedure using interventional radiology with Seldinger's technique. Adequate amount of blood is required for the procedure.

   It is approached through femoral artery at groin. Dacron or PTFE with an integral metallic stent for support and firm attachment is used as stent/ endovascular prosthesis. One aortic and iliac (of one side) stent is commonly used together. Other iliac is maintained with a separate iliac stent. Procedure can cause leak, thrombosis, recurrence, infection. Procedure is now becoming popular especially in old age.
3. *Symptomatic ruptured aortic aneurysm:* Risk of rupture is 1%, if diameter is within 5.5 cm in size. Risk increases to 20% once the diameter = 7 cm.

It may be *anterior rupture* (20%) into the free peritoneal cavity causing severe shock and *death* very early; or *posterior rupture* (80%) with formation of *retroperitoneal haematoma* of large size causing severe back pain, hypotension, shock, absence of femoral pulses and with a palpable mass in the abdomen.



Fig. 1.309: Infra-renal aortic aneurysm repair. It is the commonest site of aortic aneurysm. Adventitia of aorta is opened; aneurysm is excised; graft is sutured above and below; adventitia is wrapped around.

Management of Ruptured Aortic Aneurysm

- Immediate diagnosis by ultrasound.
- Resuscitation.
- Massive blood transfusions (10-15 bottles).
- Emergency surgery is the only life-saving procedure in these cases.

Patient has to be shifted to the operation theatre. Abdomen is opened. *Vascular clamps* or *bull dog* clamps

We will not know unless we begin.

Complications

- Haemorrhage
- Colonic ischaemia – 10%
- Renal failure
- Sexual dysfunction
- Aorto duodenal fistula
- Graft leak, graft thrombosis, graft failure
- Aorto venacaval fistula
- Spinal cord ischaemia
- Prosthetic infection/migration

are applied to the aorta above and below the aneurysm. Adventitia is opened and the clot is removed. Aneurysm is excised and the *arterial graft* either *PTFE (Polytetrafluoroethylene), knitted dacron graft*, or *woven dacron graft* is placed. The graft is sutured to the vessel above and below using monofilament, nonabsorbable suture material, polypropylene 5-zero.

Remember

- Pulsation of an aneurysm is expansile. Pulsation may be absent if it is thrombosed
- Abdominal aneurysm of any size which is painful or tender should be operated
- Abdominal aortic aneurysm of any size causing embolus should be operated
- Abdominal aortic aneurysm more than 5.5 cm should be operated
- In ruptured abdominal aortic aneurysm emergency surgery is the only choice operation with rapid resuscitation; immediate opening and repair using graft. Systolic pressure in this patient should be just adequate to maintain the cardiac function but should not be more than 100 mm Hg as it will cause more bleeding
- Anterior rupture is more dangerous than posterior rupture
- Endoluminal stenting is becoming popular

PERIPHERAL ANEURYSM

Popliteal Aneurysm

- Is commonest (70%).
- 65% are bilateral.
- 25% cases are associated with abdominal aortic aneurysm.
- 75% cause complications in 5 years.

Presentations

- Swelling in popliteal region which is smooth, soft, pulsatile, well localised, warm, compressible, often with thrill and bruit. *It may mimic a pyogenic abscess.*
- Thrombosis and emboli from popliteal aneurysm can cause distal gangrene which may spread proximally and may lead to amputation.
- Rupture may cause torrential haemorrhage.

Investigations

- Duplex scan.
- Angiogram.
- CT scan.
- MRI.

Treatment

- Aneurysmorrhaphy.
- Repair with arterial graft using PTFE, Dacron.
- Endoluminal stenting.

CAROTID ARTERY ANEURYSM (extracranial)

Incidence is less than 4% of peripheral aneurysms.

Commonest site: Common carotid artery bulb, often extends into the internal carotid artery.

Causes

- Atherosclerosis.
- Trauma.
- Syphilis.
- Marfan's syndrome.
- Ehler-Danlos syndrome.
- Congenital.

Clinical Features

- 10% bilateral.
- Swelling in the neck at the level of the thyroid cartilage, below the angle of mandible.
- Pulsatile (expansile pulsation).
- Smooth, soft, nontender, horizontally mobile.
- Bruit felt.
- Neurological features due to embolic episodes (50%).
- Hoarseness of voice.
- Horner's syndrome.
- Dysphagia.
- Swelling extending into the tonsillar bed.

Differential Diagnosis

- Carotid body tumour.
- Neurofibroma arising from the vagus.
- Abscess in neck.

Complications

- Rupture.

- Thrombosis.
- Hemiplegia.

Investigations

- Doppler of neck.
- Carotid angiogram.
- DSA.
- CT scan.

Treatment

- Reconstruction of the artery using vascular graft.
- Ligation of the bulb as a life-saving procedure, but results in hemiplegia.
- Intravascular stents.



Fig. 1.310: Basilar artery aneurysm—angiogram (*By Dr Muralidhar Pai MCh, Mangalore*).

DISSECTING ANEURYSM

It is a misnomer. It is not an aneurysm, only an aortic dissection.

It is the dissection of media of the aorta after splitting through intima creating a channel in the *media* of the vessel wall.

Causes

- Hypertension. (It is associated in 80% of dissecting aneurysms.)
- Cystic medial necrosis.
- Marfan's syndrome and collagen diseases.
- Trauma.
- Weakening of the elastic layers of the media due to shear forces.

Features

- It is always seen in thoracic aorta, common in ascending aorta (70%).
- It is uncommon in other parts of aorta or other vessels.
- It can occur in aortic arch or thoracic descending aorta.
- This dissected aortic channel gets lined by endothelium, often reopens distally into the aorta causing *double-barrelled aorta* which, in fact, prevents complications.
- It is commonly associated with aortic insufficiency.

Atherosclerosis is not a usual cause for dissecting aneurysm.

I. Classification (DeBakey's)

Type I: Dissection begins in ascending aorta extends into descending thoracic aorta (70%)

Type II: Dissection originates in ascending aorta and extends only up to the origin of the major vessels. It is safer type with less complications

Type III: Dissection begins in the descending thoracic aorta beyond the origin of the left subclavian artery

II. Stanford classification

A. Proximal—includes DeBakey's Type I and II
B. Distal—includes DeBakey's Type III

III. Dissecting aneurysm can be—

- Acute
- Chronic
- Healed dissecting aneurysm which communicates distally again to aorta as double barrelled aorta



Fig. 1.311: Dissecting aneurysm.

When you cease to dream, you cease to live.

Complications

Acute: Rupture into the pericardium or pleura – *dangerous* type

Chronic: Blockage of coronary vessels and major vessels like carotid and subclavian arteries with aortic insufficiency

Clinical Features

- Pain in the chest, back which is excruciating.
- Features of ischaemia due to blockage of different vessels.

Investigations

- Chest X-ray shows mediastinal widening.
- Arterial Doppler.
- Angiogram

Treatment

Antihypertensives.

Surgery: Using Dacron graft reconstruction of aorta has to be done with cardio-pulmonary bypass.

Indications for surgery
- Progressive disease
- Significant ischaemia
- Impending rupture
- Type A aortic dissection

REPERFUSION INJURY

- It occurs after reestablishment of arterial flow to an ischaemic tissue bed which further leads to tissue death. It is due to sudden release of oxygen free radicals which blocks the microcirculation, with release of high levels of potassium and myoglobin. Haemodynamically patient becomes unstable with lactic acidosis, intracellular changes, interstitial oedema and cardiac dysfunction.
- Severe ischaemia causes oedema in the muscular compartment with raise in compartment pressure more than the essential capillary perfusion pressure causing *acute compartment syndrome*. It is common in the anterior compartment of the leg.
- Acidosis, acute renal failure and cardiac arrhythmias set in and become life threatening.
- Features are – toxaemia; oliguria; persistent pain and oedema in the leg with muscular tenderness; raised blood urea and serum creatinine with features of acute ischaemia in the limb.
- Treatment – mannitol to prevent renal failure; fluid therapy; fasciotomy to reduce raised compartment pressure; antibiotics.
- Condition may be life-threatening.

ACROCYANOSIS (CRURUM PUELLARUM FRIGIDUM)

- It is persistent, painless cyanosis seen in fingers and often in legs with paraesthesia and chilblains affecting young females.
- It is chronic persistent arteriolar constriction with slow rate of blood flow.
- Trophic changes and ulcerations are not seen.
- Cyanosis *which is persisting* may aggravate on exposure to cold.
- It may be associated with endocrine dysfunction.

Treatment

- Vasodilators.
- Cervical sympathectomy (effective).

Raynaud's phenomenon	*Acrocyanosis*
• Episodic	• Persistent
• Painful	• Painless
• Acute arteriolar spasm	• Chronic constriction.
• Ischaemic changes are common	• Ischaemic changes are not seen

GANGRENE

> ***If the tips of (the patient's) fingers are falling off and are black, he will die.***
>
> **—(Anonymous),** circa 2000 BC

It is *macroscopic death* of tissue *in situ* (in continuity with adjacent viable tissue) with or without putrefaction.

It can occur in sites like—
- limbs
- appendix
- bowel
- testes
- gallbladder

Causes

1. Secondary to arterial occlusion like atherosclerosis, emboli, diabetes, TAO, Raynaud's disease, ergots.
2. Infective: Boil, carbuncle, gas gangrene, Fournier's gangrene, cancrum oris.
3. Traumatic: Direct, indirect.
4. Physical: Burns, scalds, frostbite, chemicals, irradiation, electrical.
5. Venous gangrene.

Clinical Features

1. *Colour changes*: Pallor, greyish, purple, brownish black due to disintegration of haemoglobin to sulphide.
2. *Absence of pulse*, loss of sensation, loss of function.



Figs 1.312A and B: Gangrene of foot and leg. Note the line of demarcation. But skip lesion proximally shown signifies more proximal spread of gangrene which may need above knee amputation.



Fig. 1.313: Gangrene of lower and upper limbs in two different patients.

3. *Line of demarcation* between viable and dead tissue by a band of hyperaemia and hyperaesthesia along with development of a layer of granulation tissue.

   In *dry gangrene* the separation occurs by aseptic ulceration with minimum infection and the gangrene is dry and mummified.

   In *wet gangrene,* separation takes place by septic ulceration. Often demarcation is vague with *skip lesions* more proximally and so landing with higher level of amputations. Even after amputation skin flap may show *die back* process, leading to failure of taking up of flap of amputation and so requiring still higher level of amputation.
4. *Proximal ischaemic features* may be present with rest pain, colour changes, hyperaesthesia – pregangrene.

Types of gangrene

- *Dry gangrene* is due to slow, gradual loss of blood supply to the part causing dry, desiccated, wrinkled, mummified part with proper line of demarcation from the viable adjacent tissues
- *Wet gangrene* is due to infection with putrefaction, causing oedematous, swollen, discoloured part, spreading proximally, with vague line of demarcation from the adjacent viable tissues

Investigations

- Hb%, blood sugar.
- Arterial Doppler, angiogram (Seldinger technique).
- U/S abdomen to find out the status of aorta.

Differences between dry gangrene and wet gangrene

Dry gangrene	*Wet gangrene (Moist)*
Clear line of demarcation is seen	Line of demarcation is vague
Dry, shriveled, mummified	Oedmatous, putrified, discoloured (H_2S)
Slow, gradual loss of blood supply	Sudden loss of blood supply
Separation is by aseptic ulceration	Septic ulceration causes separation
Limits to the demarcation	Can extend proximally rapidly
Causes are atherosclerosis, TAO	Emboli, trauma are the causes
Limited amputation is sufficient	Major higher amputation is often needed

Today's impossibilities are tomorrow's miracle.

Treatment

***Limb saving methods*:**

1. Drugs: Antibiotics, vasodilators, pentoxiphylline, praxilene, dipyridamole, small dose of aspirin, ticlopidine.
2. Care of feet and toes:
   - The part has to be kept dry.
   - Any injury has to be avoided.
   - Proper footwear is advised (Microcellular rubber footwear, MCR)..
   - Measures for pain relief is taken.
   - Nutrition supplementation is done.
   - The limb should not be warmed.
   - Pressure areas has to be protected.
   - Localised pus has to be drained.
3. Cause is treated.
4. Diabetes is controlled.
5. Surgeries to improve the limb perfusion: Lumbar sympathectomy, Omentoplasty.

Profundaplasty, femoropopliteal thrombectomy or endarterectomy, arterial graft bypass are done according to the need.

***Life-saving procedures*:** *Amputations may have to be done occasionally.*

Level of amputation is decided on skin changes, temperature, line of demarcation, Doppler study.

1. *Below-knee amputation* is a better option as *BK prosthesis* can be fitted better and also the movements of knee joint are retained. There is no need of external support and limp is absent.
2. In *above-knee amputation* range of movements are less, limp is present, and often requires third (stick) support to walk.

Different amputations done are *Ray amputation*, below-knee amputation *(Buerger's amputation)*, *Gritti-Stokes transgenial amputation*, above-knee amputation**.**

Lisfranc's, Chopart's, Symes', Modified Symes' amputations are not commonly used in ischaemic limb as flaps will not survive.

DIABETIC FOOT AND DIABETIC GANGRENE

Foot is a complex structure with many layers of muscles, ligaments, joints, arches, fat, thick plantar fascia, vascular arches, neurological system which maintains weight bearing, gravity, normal walk, stability and gait (swing and stance phases).

Problems in diabetic foot

1. Callosities, ulceration
2. Abscess and cellulitis of foot
3. Osteomyelitis of different bones of foot like metatarsals, cuneiforms, calcaneum
4. Diabetic gangrene
5. Arthritis of the joints



Fig. 1.314: Diabetic with extensive sepsis and gangrene. It requires amputation.

Meggitt's classification of diabetic foot

Grade 0: Foot symptoms like pain, only
Grade 1: Superficial ulcers
Grade 2: Deep ulcers
Grade 3: Ulcer with bone involvement
Grade 4: Forefoot gangrene
Grade 5: Full foot gangrene

Pathogenesis of Diabetic Foot/Gangrene:

1. High glucose level in tissues is a good culture media for bacteria. So infection is common.
2. *Diabetic microangiopathy* causes blockade of microcirculation leading to hypoxia.
3. *Diabetic neuropathy*: Due to sensory neuropathy, minor injuries are not noticed and so infection occurs. Due to motor neuropathy, dysfunction of muscles, arches of foot and joints occurs. And loss of reflexes of foot occurs causing more prone for trauma and abscess. Due to autonomic neuropathy, skin will be dry, causing defective skin barrier and so more prone for infection.
4. *Diabetic atherosclerosis* itself reduces the blood supply and causes gangrene. Thrombosis can be precipitated by infection causing infective gangrene. Blockage occurs at plantar, tibial, and dorsalis pedis vessels.
5. *Increased glycosylated haemoglobin* in blood causes defective oxygen dissociation leading to more hypoxia. At tissue level there will be increased glycosylated tissue proteins, which prevents proper oxygen utilization and so aggravates hypoxia.

Clinical Features

- Pain in the foot.
- Ulceration.
- Absence of sensation.
- Absence of pulsations in the foot (Posterior tibial and dorsalis pedis arteries).
- Loss of joint movements.
- Abscess formation.



Figs 1.315A to C: Diabetic foot with ischaemic ulceration and gangrene. Note in one of the photos distal part of foot is gangrenous and proximal part is pregangrenous. This patient underwent above knee amputation.



Fig. 1.316: Gangrene of 3rd and 5th toes in a diabetic. Patient already underwent amputation of 4th toe earlier for gangrene.

- Change in temperature and colour when gangrene sets in.
- Patient may succumb to *keto acidosis, septicaemia or myocardial infarction*.

Investigations

- Blood sugar, urine ketone bodies.
- Blood urea and serum creatinine.
- X-ray of part to look for osteomyelitis.
- Pus for culture and sensitivity.
- Doppler study of lower limb to assess arterial patency.
- Angiogram to look for proximal blockage.
- Ultrasound of abdomen to see the status of abdominal aorta.

Treatment

- ***Foot can be saved only if there is good blood supply.***

1. Antibiotics—decided by *pus C/S*.
2. Regular dressing.
3. *Drugs:* Vasodilators, pentoxiphylline, dipyridamole, low dose aspirin.
4. Diabetes is controlled by *insulin only*.
5. Diet control, control of obesity.
6. Surgical debridement of wound.
7. Amputations of the gangrenous area. Level of amputation has to be decided by skin changes and temperature changes or Doppler study.
8. Care of feet in diabetic:
    - Any injury has to be avoided
    - MCR footwears must be used (Micro Cellular Rubber).
    - Feet has to be kept clean and dry, especially the toes and clefts.
    - Hyperkeratosis has to be avoided.

TROPHIC ULCER

Aetiology

Diabetic neuropathy, spinal injury and diseases, other neuropathies.

Causes

- Pressure
- Anaemia
- Malnutrition
- Injury
- Moisture

A positive thought is a seed of positive result.

Common Sites

Heel, heads of metatarsals, sacrum, ischium, occipital region. *Bedsore is a trophic ulcer*.

Clinical Features

They are deep, punched out, nonmobile ulcers, with bone as its base.

Investigations

X-ray spine, nerve conduction studies, blood sugar, Hb%.

Treatment

- Nutrition is improved.
- Anaemia is treated.
- Diabetes is controlled.
- Regular dressing is done.
- Pressure and injuries has to be avoided.

BEDSORES (Decubitus Ulcer) (Pressure sores)

Bedsore is a *trophic ulcer* with bone as the base.
It is nonmobile, deep, punched out ulcer.

It is common in			
Old age Diabetic	Bedridden Paraplegic	Tetanus Comatose	Patients with orthopaedic and head injuries

Sites of bedsore are occiput, heel, sacrum, ischium, scapula.

Factors: Malnutrition, pressure, anaemia, sensory loss, moisture.

Treatment

- Change of positions is always encouraged.
- Use of water bed, ripple bed is advised.
- Moisture has to be avoided.
- Soaking by urine, sweat, pus, and faeces has to be taken care off.
- Good nursing, regular dressing, good nutrition are necessary.
- Antibiotics, blood transfusions are very essential.
- Excision of dead tissue followed by skin grafting or local rotation flaps may have to be done.
- Rehabilitation.

FROSTBITE

- It is due to exposure to cold wind or high altitude.
- It is common in old age during cold spells.
- Damage to vessel wall occurs causing oedema, blistering, gangrene formation.
- Part is painless and waxy.



Figs 1.317A and B: Large bedsore over the sacrum in a bedridden patient. Note the size and slough on the surface.

Treatment

- *Gradual warming is done*. Part should be wrapped with cottonwool and rested.
- Warm drinks, analgesics, paravertebral injections to sympathetic chain, *hyperbaric oxygen* are effective.
- If gangrene develops, amputation is needed.

AINHUM



Fig. 1.317C: Typical Ainhum. Note it is bilateral. Note the constriction ring in the little toe.

- Commonly affects males (can also occur in females).
- Common in blacks, in Negroes.
- History of running barefoot in childhood is common.
- *Fifth toe* is commonly affected.
- A fissure develops at the interphalangeal joint which becomes a fibrous band, that encircles the digit causing necrosis (Gangrene of little toe).
- Often it can be bilateral.

Treatment: is early "Z" plasty. Amputation is often required later. Most often autoamputation occurs.

ENDOVASCULAR SURGERIES

It is mainly used in peripheral vessels like femoro-popliteal, renal, coronary, cerebral vessels.

Types

- *Balloon angioplasty:* It is useful in short segment stenosis in large vessles like renal vessels, ilio-femoral, coronary vessels. It is less effective compared to open surgery.
- *Intravascular stenting:* Balloon expandable and self-expanding stents are used at stenosed area.
- *Endovascular grafts* (PTFE, DACRON).
- Endovascular atherectomy.
- *Angioscopy:* Flexible, small, fibreoptic scopes to visualise vessel wall with sufficient irrigation to avoid opacification by blood.
- *Intravascular ultrasound:* To evaluate the vessel wall morphology.

Indications

- Aneurysm for stenting and grafting
- Aorto-iliac constrictive disease
- Renal artery stenosis
- Carotid occlusive disease
- AV fistulas
- Management of pseudo-aneurysm

Complications

- Thrombosis.
- Rupture.
- Sepsis.
- Fluid overload.
- Air embolism.

UPPER LIMB ISCHAEMIA

It is a rare entity compared to lower limb ischaemia but important because of its difficulty in managing. *Higher-level amputations are rare in upper limb ischaemia.*



Fig. 1.318A: Upper limb ischaemia with gangrene extending proximally towards elbow joint.



Fig. 1.318B: Left upper limb ischaemia with gangrene of three fingers and ischaemic changes in hand, forearm and arm.



Fig. 1.318C: Gangrene of left index finger. Patient has undergone cervical sympathectomy.

Imagination is the highest kite one can fly.

Causes

- Thoracic outlet syndrome.
- Raynaud's disease and phenomenon.
- Embolism due to causes like atrial fibrillation and endocarditis.
- Trauma – commonest cause.
- TAO upper limb (along with lower limb TAO).
- Atherosclerosis of upper limb vessels.
- Takayasu's arteritis.
- Poly arteritis nodosa.
- Scleroderma.
- Infection.

Features

- Upper limb claudication and ischaemic rest pain.
- Ischaemic features.
- Ulcers and gangrene commonly in fingers.
- Wasting of hand and forearm muscles.
- Mass in the neck, bruit in the neck in supraclavicular region.
- Adson test, hyperabduction test, Roos test, Allen's tests are important.

Investigations

- Arterial Doppler.
- Subclavian angiogram.
- Investigations to confirm vasculitis.
- Blood sugar.
- Lipid profile.
- Cardiac evaluation.
- X-ray neck to find out cervical rib.
- CT scan—neck and thorax.

Treatment

- Treatment of the cause.
- Extraperiosteal resection of the cervical rib.
- Cervical sympathectomy.
- Drugs like vasodilators, pentoxiphylline, ticlopidine. Small dose of aspirin.
- Arterial reconstruction of the subclavian artery.
- Arterial embolectomy when there is an embolus.

(*Note:* Individual topics about causes of upper limb ischaemia are discussed in different places).

Upper limb ischaemia

- Trauma/cervical rib are the common causes
- Opposite limb, lower limbs should be examined
- Cardiovascular system should be examined
- Neck should be examined
- Wasting/girth should be checked
- All relevant clinical methods are equally significant
- Auscultation over neck/axilla/carotids for bruit are important
- Doppler; angiogram; nerve conduction studies; CT neck and thorax are essential investigations
- Arterial repair; therapy for cervical rib; scalenotomy; cervical sympathectomy are the different modalities of treatment
- Digital amputation may be required

Self-assessment Questions

- Discuss aetiology, clinical features and management of Buerger's disease.
- TAO.
- Classify gangrene. Discuss its features and management.
- Critical limb ischaemia.
- Diabetic foot.
- Claudication.
- Arteriography.
- Embolectomy.
- Cervical sympathectomy.
- Lumbar sympathectomy.
- Leriche's syndrome.
- Cervical rib.
- Surgical anatomy of thoracic inlet.
- Saddle embolism.
- Decubitus ulcer.
- Popliteal aneurysm.
- Aortic aneurysm.
- Abdominal aortic aneurysm.
- Cirsoid aneurysm.
- Dissecting aneurysm.
- Retrograde angiogram.
- Fat embolism.
- Air embolism.
- Ainhum.
- Acrocyanosis.
- Raynaud's phenomenon.
- Mycotic aneurysm.
- Line of demarcation.
- Doppler study.
- AV fistula.

Hamartoma and Vascular Lesions

Hamartomata
Haemangioma
Vascular malformations
Cirsoid aneurysm
Arterio venous fistula
Campbell De Morgan spots
Parry-Romberg disease

HAMARTOMATA

Hamartano means *'I miss' (Greek).* Or 'fault' or 'misfire' or 'error'.

- It is a benign lesion with aberrant differentiation producing a mass of disorganised but mature specialised cells or tissue indigenous to the particular site.
- It is tumour like overgrowth of tissue or tissues proper to that part.
- It may be single lesion or multiple lesions.
- Haemangiomas, lymphangiomas, A-V malformations, neural malformations are the examples.

Problems with hamartomas

- Pressure symptoms locally
- Bleeding
- Infection
- Gigantism
- Cosmetic problem

Treatment

- Depends on site, type, extent.
- Cryotherapy, ligation of feeding vessels, sclerotherapy, excision or laser therapy.

HAEMANGIOMA

- It is benign vascular endothelial tumour, common in girls (3 : 1).
- It is commonly seen in skin and subcutaneous tissue but can occur anywhere in the body like in liver, brain, lungs or other organs.
- It grows rapidly in first year and 70 % involutes in 7 years.
- Early proliferative lesion is bright red, irregular; deep lesion is bluish coloured. Involution causes colour fading, softness, shrinkage leaving crepe paper like area.
- Commonly it is central; common in head and neck region (60%).

Classification

- *Capillary*
  - Salmon patch (stork bite)
  - Strawberry haemangioma
  - Port wine stain (naevus flammeus)
- *Cavernous*

Capillary Haemangioma

1. ***Salmon patch (stork bite):*** It presents at birth. It commonly occurs in nape of the neck (50%), face, scalp and limbs. It usually involves wide area of skin. It is caused by an area of persistent fetal dermal circulation. With age, it goes for spontaneous regression and disappears completely (usually in one year). Hence masterly inactivity is the treatment.



Fig. 1.319: Salmon patch.

2. ***Strawberry haemangioma***: It may start at birth or child is normal at birth; between one to three weeks it appears as red mark which rapidly increases in size in 3 months to form strawberry/raspberry haemangioma. It contains immature vasoformative tissues. There will be eventually intravascular thrombosis, fibrosis and mast cell infiltration.
   - It is a *true capillary* haemangioma.
   - It is 20 times more common than port wine stain.
   - It is common in *white girls*. Male to female ratio is 3 : 1.
   - It is common in head and neck region.

You may be disappointed if you fail, you are doomed if you don't try.

- It is clinically *compressible,* warm with bluish surface.
- Bleeding can occur after minor trauma and also ulceration.
- It involves skin, subcutaneous tissues and often muscles also.
- After one year of age, it slowly begins to disappear, and *completely* in 7-8 years (70% in 7 years).
- It is the commonest haemangioma.



Fig. 1.320: Strawberry haemangioma.

- Haemangioma in periorbital region obstructs the vision in newborn with amblyopia and if it persists for 7 days causes permanent visual damage. Astigmatism also can occur
- Haemangioma in nasal area in newborn may obstruct nasal airway seriously [as newborn cannot breathe through mouth—obligatory nasal breathing]
- Skin ulceration may cause haemorrhage
- Infection can occur which may lead into sepsis, necrosis or rarely septicaemia
- Systemic steroids for 3 weeks induces involution
- Usually there is no role for surgery. Surgery is done only for retained tissue after involution

3. ***Port wine stain (Naevus flammeus)***: It presents at birth and persists throughout life without any change. Spontaneous regression will not occur. It presents as smooth, flat, reddish blue/intensely purple area; common in head, neck and face; often with maxillary and mandibular dermatomes of 5th cranial nerve. Eventually surface becomes nodular and keratotic.
   - It persists throughout life.
   - It is actually a *capillary malformation* even though considered under haemangioma. It results from defect in maturation of sympathetic innervation of skin causing localised vasodilatation of intradermal capillaries.
   - It is often associated with Sturge-Weber syndrome, Klippel - Trenaunay-Weber syndrome and Proteus syndrome.
   - It needs treatment – laser (pulsed dye/diode); excision and grafting; cosmetic coverage. Expected result by treatment is not possible many times.



Fig. 1.321: Port wine stain (Naevus flammeus).

Indications for surgery or intervention–

- Uncontrolled growth
- Functional impairment like vision or hearing.
- Accidental haemorrhage

Treatment

- Allowed for spontaneous regression.
- Otherwise by laser therapy – pulsed dye laser (diode laser).
- CO_2 snow therapy.
- Sclerosant therapy.
- Steroid - oral / intralesional / systemic.
- Therapeutic embolisation

Associated syndromes

- ***Klippel Trenaunay Weber syndrome***: Naevus flammeus + osteohypertrophy of extremities (soft tissue and bone hypertrophy) + varicose veins of lower limbs. If there is an association of arterio venous fistula (AV fistula), it is called as ***Parkes – Weber syndrome***

- ***Kasabach Merritt syndrome***: Capillary haemangioma + DIC (Disseminated intravascular coagulation) with thrombocytopenia
- ***Sturge Weber syndrome**:* Haemangiomas (Naevus flammeus) + hemiplegia and Jacksonian epilepsy (calcified vascular cerebral and meningeal deposits) + glaucoma
- ***Maffucci syndrome*****:** Cavernous haemangioma + dyschondroplasia
- ***Proteus syndrome*****:** Naevus flammeus + regional gigantism with lymphaticovenous malformation (asymmetrical hypertrophy)
- ***Osler-Rendu - Weber syndrome***: Haemangioma of skin and lip with gastrointestinal tract haemangioma (hereditary haemorrhagic telangiectasia), (autosomal dominant)

Cavernous Haemangioma

- It is present at birth and consists of a multiple venous channels.
- Its size increases gradually and may cause problems.
- It often contains feeding vessels which is of surgical importance.
- *Sites***:** Head, neck, face, limbs, tongue, liver and other internal organs.
- Large or multiple cavernous haemangiomas can cause *congestive heart failure* (hyperdynamic) due to shunting of large quantity of blood.
- Cavernous haemangioma with dyschondroplasia is called as Maffucci syndrome.
- Cavernous haemangioma is often mixed with lymphatic component also (mixed vascular and lymphatic).



Figs 1.322A and B: Cavernous haemangioma in (A) tongue and (B) knee.

Clinical Features

- It is smooth, soft, well-localised, warm, fluctuant, compressible, nonpulsatile swelling with bluish surface occurring in skin and subcutaneous tissue (often in mucosa like oral cavity) without any transillumination.
- *Compressibility and bluish surface* is diagnostic. When swelling is pressed it reduces partially/often completely but when pressure is released it slowly attains its original size and shape. Vascular and lymphatic malformations are compressible.
- It is usually nontender unless it gets infected or undergoes thrombosis or causes haemorrhage.



Figs 1.323A and B: Cavernous haemangioma in the cheek near angle of the mouth and in the tip of the tongue. Haemangioma tongue is one of the causes of macroglossia.

> *When I was young, I observed that nine out of ten things I did were failures. So I did ten times more work.*
> —George Bernard Shaw



Fig. 1.324: Laparoscopic view of cavernous haemangioma of liver. It is commonest benign tumour of the liver.

Differential Diagnosis

- Lymphangioma – It is brilliantly transilluminant unless it is infected or fibrosed.
- Lipoma, cold abscess, lymph cyst – clinically it is easier to differentiate.

Complications

- Haemorrhage.
- DIC.
- Thrombosis.
- Infection, ulceration and septicaemia.
- Erosion into the adjacent bone.
- High output cardiac failure.

Investigations

- Ultrasound.
- Doppler.
- Angiogram to find out feeding vessel.
- Platelet count.
- MRI/MR angiogram to see feeding vessels and deeper extension.

Treatment

- Sclerosant therapy – It is the initial first line of therapy. It causes aseptic thrombosis and fibrosis of the cavernous haemangioma with less vascularity and smaller size. It is directly injected into the lesion. Sodium tetradecyl sulphate/hypertonic saline are used. Often multiple injections are needed to achieve complete required effect. Later excision of the lesion is done.
- Ligation of feeding artery and often at later stage excision is done once haemangioma shrinks.
- Therapeutic embolisation.
- If small and located in accessible area, excision is the initial therapy.
- Laser ablation – diode pulsed laser is becoming popular because of good control of bleeding. CO_2/Nd YAG laser is also equally effective.

VASCULAR MALFORMATIONS

- Secondary to defect in development of vascular components, in 8th week of intrauterine period
- Associated with many syndromes
- Can be in skin or in deeper planes
- Present at birth and grows in proportion to child's growth
- Low flow malformations can cause skeletal hypoplasia; high flow malformations can cause hypertrophy
- Consumption coagulopathy (DIC) can occur
- It is equal in both sexes

Vin rose patch: It is a congenital intradermal pale pink vascular malformation with dilatation of vessels in subpapillary dermal plexus. It may be associated with haemangiomas; AV malformations in limbs; congenital lymphoedema.

CIRSOID ANEURYSM

- It is a rare variant of capillary haemangioma occurring in skin, beneath which abnormal artery communicates with the distended veins.
- Commonly seen in **superficial temporal artery** and its branches.
- Often the underlying bone gets thinned out due to pressure.
- Occasionally extends into the cranial cavity.
- Ulceration is the eventual problem which will lead to uncontrollable haemorrhage.

Clinical Features

Pulsatile swelling in relation to superficial temporal artery, which is warm, compressible, with arterialisation of adjacent veins and with bone thickening (due to erosion). It feels like a *'pulsating bag of worms'*.

Investigations

- Doppler study.
- CT scan.
- Angiogram.
- X-ray of the part.

Treatment

- Ligation of feeding artery and excision of lesion, often requires preliminary ligation of external carotid artery.
- Intracranial extension requires formal neurosurgical approach.

ARTERIO VENOUS FISTULA (AVF)

It is an abnormal communication between an artery and vein.

Types

- Congenital—is arterio-venous malformation.
- Acquired (Trauma is common cause).

Congenital Arterio – Venous Fistula (AVF)

During developmental period AV communications occur.



Fig. 1.325: MR angiogram of AV malformation in cranial cavity.



Fig. 1.326: MRI picture of AV malformation.

Sites

- Limbs, either part or whole of the limb is involved. It may be localised to toes or fingers.
- Lungs.
- Brain: in circle of Willis.
- Other organs like bowel, liver.

Clinical Features

Structural changes in the limb:

- Limb is **lengthened** due to increase in blood flow since developmental period.
- Limb **girth** is also increased.
- Limb is **warm.**
- **Continuous thrill and continuous machinery murmur** all over the lesion.
- **Dilated arterialised varicose veins** are seen due to increased blood flow and also due to valvular incompetence.
- Often there is **bone erosion** or extension of AVF into the bone as such.

> *When stethoscope is applied aneurysm is either silent or a systolic bruit can be heard, but an arteriovenous fistula emits a continuous murmer throughout the systole and diastole.* —Charle G Rob



Figs 1.327A and B: Hypertrophic changes due to AV malformation.

Physiological Changes

Because of the hyperdynamic circulation, there is **increased cardiac output** and so often **congestive cardiac failure**.

Complications

- Haemorrhage
- Thrombosis
- Cardiac failure

Investigations

- Angiogram.
- Doppler study.
- X-ray of the part.

Treatment

- Injury is avoided.
- Ligation of feeding artery.



Figs 1.328A to E: Congenital arterio venous malformation involving right upper limb, axillary region and part of right half of neck and face. Note the limb lengthening and widened girth. Limb is warmer. Limb should be measured at each level. Auscultation reveals continuous bruit over the limb. Note the dilated tortuous veins due to hyperdynamic circulation.

- Sclerosant therapy.
- Therapeutic embolisation.
- Amputation is done when required (only) as a life-saving procedure.

Acquired Arterio-Venous Fistula (AVF)



Fig. 1.329: AV fistula.

Causes

1. Trauma in (commonest cause)—
   - Femoral region.
   - Popliteal region.
   - Brachial region.
   - Wrist.
   - Aorta venacaval.
   - Abdomen

   It may be following road traffic accidents, penetrating wounds, cock-fight injury (common in South India).
2. After surgical intervention of major vessels.
3. Therapeutic: For renal dialysis, AVF is created (**cimino fistula**) to achieve arterialisation of veins and also to have hyperdynamic circulation. It is done to have easy and adequate venous access for long time **haemodialysis.**

Common sites are **wrist, brachial, and femoral** region.

Pathophysiology

- *Physiological changes: Cardiac failure due to hyperdynamic circulation*.
- *Structural changes:*

  Changes at the level of fistula: Blood flows from high pressure artery to low pressure vein causing diversion of most of the blood. Between the artery and vein, at the site of fistula, dilatation develops with formation of fibrous sac called as **aneurysmal sac.** This presents as warm, pulsatile, smooth, soft, compressible swelling at the site with **continuous thrill and continuous machinery murmur**.

  Changes below the level of the fistula: Because of diversion of arterial blood **distal part becomes ischaemic**. Because of high pressure arterialisation of veins and valvular incompetence occurs causing **varicose veins**.

  Changes proximal to the fistula: **Hyperdynamic circulation** causes cardiac failure.

  If pressure is applied to the artery proximal to the fistula, swelling will reduce in size, thrill and bruit will disappear, pulse rate and pulse pressure becomes normal. This is called as **Nicoladoni's sign** or **Branham's sign.**

  Cardiac failure may be very severe in traumatic AVF (often resistant to drug therapy).



Figs 1.330A and B: Acquired arterio-venous fistula in the wrist over radial vessels. It should be palpated for compressibility and thrill. It should be auscultated for bruit.

Investigations

- Doppler.
- Angiogram.
- ECG.
- Echocardiography.

Treatment

- **Excision** of fistula and **reconstruction** of artery and vein with graft.
  Done in early stages- larger vessels. Venous or Dacron graft is used.
- In emergency situation, **quadruple ligation**, i.e. both artery and vein above and below are ligated without touching the fistula and sac. Patient recovers well from cardiac failure.
- Therapeutic embolisation may be tried.

Honesty breeds respect and respect breeds trust.



Fig. 1.331: AV fistula created for treating chronic renal failure has become an aneurysm. It may rupture to cause severe haemorrhage. Thrombosis or sepsis also can occur in this.


Artery
Vein
Ligations
(4)
AV fistula

Fig. 1.332: Quadruple ligation of AV fistula.


Artery
Vein
Artery
Vein
AV fistula with
aneurysmal sac
Dacron graft

Fig. 1.333: Reconstruction of AV fistula using graft.


Artery
Vein
Hunter's ligation
should not
be done
Collaterals
AV
fistula

Fig. 1.334: Hunter's ligation is ligation of artery proximal to AV fistula. It should not be done as it causes diversion of all blood from periphery leading to gangrene of distal part.

Hunter's ligation should be avoided. It is used as life-saving measure because it invariably causes limb ischaemia and gangrene even though patient recovers from cardiac failure. It is ligation of both artery and vein proximally so as to make cardiac function normal. But it invariably steals the blood from the limb leading to gangrene.

CAMPBELL DE MORGAN SPOTS

- It is usually smaller (0.2 to 6 mm) in size, circular, elevated and bright red swelling.
- It is common in trunk. Common in elderly.
- Also called as *cherry angiomas.*
- Usually it does not require treatment.
- When needed, excision or electrodesiccation or laser removal is done.

PARRY-ROMBERG DISEASE

- It is hemifacial atrophy of skin, soft tissue and bone.
- Common in females.
- It usually begins at twenties.
- Atrophy of skin, fat, muscle, cartilage and bone causing *coupe de sabre* deformity.
- It is a self-limiting disease.
- Aesthetic reconstruction is offered when severe deformity develops.

Self-assessment Questions

- Hamartoma.
- Cavernous haemangioma.
- Capillary haemangioma.
- AV malformations.
- AV fistula.
- Branham's sign.

Venous Diseases

Anatomy of veins of lower limb
Physiology of venous blood flow
Deep vein thrombosis
Varicose veins
Venous ulcer
Compression therapy for varicose veins
Thrombophlebitis
Anticoagulants

ANATOMY OF VEINS OF LOWER LIMB


Perforators
Short saphenous system
Long saphenous system

Fig. 1.335: Anatomy of lower limb veins

Deep Veins

1. Tibial, popliteal, femoral veins are called as "*veins of conduits*" which drain blood into iliac veins and then to IVC.
2. *Pumping veins*: They are venous sinuses existing in the calf muscles which pump blood towards major veins. They are better termed as *musculovenous pumps*. They are also called as the *peripheral heart*.

Superficial Veins

- *Long saphenous vein*: It is a subcutaneous vein over the inner aspect of the leg and thigh, joins into femoral vein at fossa ovalis. Tributaries of long saphenous vein are posterior arch vein, anterior vein of leg, anterolateral vein, posteromedial vein and sometimes accessory saphenous vein.
- *Short saphenous vein*: It is over the lateral and posterior aspect of the leg enters the deep fascia in the upper calf region and later joins popliteal vein at variable distance.
- Posterior arch vein of 'Leonardo' (from medial ankle to the long sephanous vien below the knee).
- Anterior arch vein to peroneal veins.

Superficial veins have got multiple valves which facilitates blood flow towards heart. Superficial veins usually drain about 10% of lower limb blood i.e. from skin and subcutaneous tissues.


Superficial circumflex iliac
Superficial epigastric
Superficial ext pudendal
LSV
Anterior vein
Post vein
Perforators

Fig. 1.336: Long saphenous vein anatomy and its tributaries.


SP Junction
Perforators
SSV

Figs 1.337A and B: Short saphenous vein varicosity.

You may be disappointed if you fail, you are doomed if you don't try.

Perforator Veins

They are the veins which connect superficial to deep veins at various levels. They travel from superficial fascia through an opening in the deep fascia before entering the deep veins. The direction of blood flow here is from superficial to deep veins. These perforators are also guarded by valves so that the blood flow is unidirectional, i.e. towards deep veins. Reversal of flow occurs due to incompetence of perforators which will lead to *varicose veins*.

Types

- Ankle perforators (May or Kuster)
- Lower leg perforators: I, II, III (of Cockett)
- Gastrocnemius perforators (of Boyd)
- Mid thigh perforators (Dodd)
- Hunter's perforator in the thigh

PHYSIOLOGY OF VENOUS BLOOD FLOW IN LOWER LIMB

Veins are thin-walled vessels with collapsible walls, that assume an elliptical configuration in collapsed state and circular configuration in the filled state.

Venous valves are abundant in the distal lower extremity and the number of valves decreases proximally, with no valves in superior and inferior vena cava.

Venous Return

1. Arterial pressure across the capillary increases the pumping action of vein.
2. *Calf musculovenous pump*: During contraction phase of walking, pressure in the calf muscles increases to 200-300 mmHg. This pumps the blood towards the heart. During relaxation phase of walking, pressure in the calf falls and so it allows blood to flow from superficial to deep veins through perforators. Normally while walking, pressure in the superficial system at the level of ankle is 20 mmHg.
3. During walking, foot pump mechanism propels blood from plantar veins into the leg.
4. Gravity.

Note: Pressure in *arteriolar end of the capillary* is 32 mmHg; *venular end of capillary* is 12 mm Hg.

Factors responsible for venous return

1. Negative pressure in thorax
2. Peripheral pump—calf muscles
3. Vis-a-tergo of adjoining muscles
4. Nonrefluxing valves in course of veins

DEEP VEIN THROMBOSIS (DVT)

Aetiology: Factors—

Virchow's triad—

a) Stasis
b) *Hypercoagulability*
c) Vein wall injury

Causes

1. Following childbirth.
2. Trauma- to leg, ankle, thigh, pelvis.
3. Muscular violence.
4. Immobility–Bed ridden patients, individuals on long duration air or bus travel ***(Traveller's thrombosis*)**.
5. Debilitating illness, obesity, immobility, bed rest, pregnancy, puerperium, oral contraceptives, estrogens.
6. Postoperative thrombosis: *(Most common cause).* Common after the age of 40 years. Incidence following surgeries is 30%. In 30% of cases both legs are affected. Usually seen after prostate surgery, hip surgery, major abdominal surgeries, gynaecological surgeries, cancer surgeries. Bedridden for more than 3 days in the postoperative period increases the risk of DVT.
7. *Spontaneous thrombosis* is common in visceral neoplasm like carcinoma pancreas or carcinoma stomach. It is often migrating type.
8. Thrombus may start in a venous tributary which eventually may extend into the main vein causing DVT.
9. Axillary vein thrombosis can occur spontaneously, following compression by cervical rib, by various causes of thoracic inlet syndrome, or arm being in the hyper-abduction state for prolonged period (e.g. painting the ceiling), after axillary lymph node block dissection, after radiotherapy to axilla, occasionally as a complication of venous cannulation.
10. Polycythaemia vera, thrombocytosis.
11. Deficiencies of antithrombin III, protein C, protein S, factor V of Leiden, Thrombophilia.
12. Recent myocardial infarction, heart failure, nephrotic syndrome.
13. Thrombosis can occur in individuals who sit with computers for long time—'***ethrombosis*'.**

Sites

1. Pelvic veins—common
2. Leg veins—common in femoral and popliteal veins (Common on left side). Incidence of bilateral leg DVT



Fig. 1.338: Deep vein thrombosis (DVT) in both legs. 30% cases of DVT are bilateral.



Fig. 1.339: Unilateral left leg DVT. Note the oedema and colour changes.

is 30% which should be differentiated from bilateral pedal oedema due to other causes like hypoproteinaemia, renal failure and cardiac causes.

3. Upper limb veins—not uncommon (Axillary vein thrombosis).

Phlegmasia alba dolens

It is DVT of *femoral vein* (deep femoral vein commonly) causing painful congestion and oedema of leg, with lymphangitis, which further increases the oedema and worsens the situation (*white leg*).

Phlegmasia caerulea dolens

It is extensive DVT of *iliac and pelvic veins* causing *blue leg* with either venous gangrene or areas of infarction.



Fig. 1.340: Right leg venous gangrene. Note the discolouration, blebs and oedema.

Features of DVT

- Fever-commonest
- Tense, tender, warm, pale/bluish, shiny swelling calf
- Positive Homan's, Mose's or Neuhof's signs
- Inverted champagne bottle sign
- Commonly it is asymptomatic
- Features of pulmonary embolism

Clinical Features

1. Fever—earliest symptom.
2. Pain and swelling in the calf and thigh (often). Pain is often so severe that the patient finds it difficult to flex (or move) the leg.
3. Leg is tense, tender, warm, pale or bluish with stretched and shiny skin.
4. *Positive Homan's sign*: Passive forceful dorsiflexion of the foot with extended knee will cause tenderness in the calf.
5. *Mose's sign*: Gentle squeezing of lower part of the calf from side-to-side is painful. Gentleness is very important otherwise it may dislodge a thrombus to form an embolus.
6. *Neuhof's sign*: Thickening and deep tenderness elicited while palpating deep in calf muscles.
7. Most often, DVT is *asymptomatic* and presents suddenly with features of *pulmonary embolism* like *chest pain*, *breathlessness* and *haemoptysis*.

Oral contraceptives increases the risk of DVT by 3-5 times.

Differential diagnosis for DVT

- Ruptured Baker's cyst
- Ruptured plantaris tendon
- Calf muscle haematoma
- Cellulitis leg
- Superficial thrombophlebitis

Investigations

1. Venous Doppler.
2. Duplex scanning.
3. Venogram.
4. Radioactive I^{125} fibrinogen study.
5. Haemogram with platelet count.
6. Ventilation – perfusion scanning with mismatched defects; pulmonary artery CT scan with filling defect; pulmonary angiography are the investigations to confirm the pulmonary embolism.



Fig. 1.341: Doppler study showing DVT.



Fig. 1.342: U/S showing thrombosis of the IVC.

Treatment

1. Rest, elevation of limb, bandaging the entire limb with crepe bandage.
2. Anticoagulants: Heparin/low molecular weight heparin, warfarin, phenindione.
3. For *fixed thrombus*
   - Initially high dose of heparin of 25,000 units/day for 7 days is given. Then later patient is advised to continue warfarin for 6 months. Dose is controlled by assessing *Activated Partial Thromboplastin Time (APTT)*. Duration of heparin treatment is usually for 7-10 days.
   - Low molecular weight heparin is preferred to heparin.
   - Warfarin should be started as early as possible. Day one and day two – 10 mg each day; day three – 5 mg. On day three prothrombin time should be done. Warfarin is given for 6 – 12 months with regular monitoring.
4. For *free thrombus*:

Free thrombus:

a. Fibrinolysins
b. Thrombectomy using Fogarty's catheter
c. IVC filter

a. *Fibrinolysins*—Streptokinase, 6 lakhs to start with and later one lakh hourly. It is commonly infused directly into the affected vein through a venous catheter. Urokinase or tissue plasminogen activator may also be used to dissolve thrombus (it should not be given when patient is on heparin).

Fibrinolysins

- Tissue plasminogen activator – directly into the thrombus through popliteal / femoral vein
- Urokinase - 1,20,000 to 2,50,000 units / hour; derived from human urine
- Reptilase – 0.5 – 1 unit / hour
- Streptokinase- 6 lakh to start with later one lakh hourly; derived from streptococci

b. Venous thrombectomy is done using Fogarty venous balloon catheter.
c. Thrombotic emboli is prevented from reaching the heart by filtering it at IVC level using intracaval filters—Kim ray Greenfield filter, suture sieve plication, stapler plication, vena caval ligation, Mobin Uddin umbrella filter.
d. Special thrombectomy device of 7-9 French sheath is passed through the thrombosed segment to have partial mechanical thrombectomy and through that thrombolytics are infused. Thrombus can be removed nowadays through balloon angioplasty tube. Open venotomy and thrombectomy also can be done.

5. *Palma operation*: In ilio femoral thrombosis, common femoral vein below the block is communicated to

opposite femoral vein through opposite long saphenous vein.

6. *May-Husni operation*: When blockage is in popliteal vein, popliteal vein below the block is anastomosed to long saphenous vein (end to end) so as to bypass the blood across the popliteal block.



Fig. 1.343: Palma operation for ilio femoral block. Using opposite saphenous vein femoral vein is connected to other femoral vein.



Fig. 1.344: Crepe bandages applied to both legs in bilateral varicose veins and DVT.

Prevention of DVT

- Categorise the patient as low/moderate and high risk
- Mechanical methods – elastic compression bandage; elevation; external pneumatic bandage
- Pharmacological – low molecular weight heparin – once a day

1. Care has to be taken to see for proper positioning of legs with no pressure on the calf muscles.
2. Pressure bandage to the legs has to be applied during major surgeries, laparoscopic surgeries. During postoperative period, elevation, massaging, pressure bandage, early ambulation, maintaining hydration are essential measures.
3. Low dose heparin is given in suspected cases, in major surgeries and continued during postoperative period till the patient is ambulated. 5,000 units is given subcutaneously 2 hours before surgery. Low molecular weight heparin is preferred drug than heparin as it can be used once a day; it does not require monitoring; it does not cause thrombocytopenia (like heparin); and there is lesser risk of bleeding.
4. Various measures like graduated static compression, elastic stockings, electrical stimulation of calf muscles, pneumatic compression are used to prevent sluggish flow of blood.
5. Dextran 70, intravenously 500 ml during surgery and another 500 ml postoperatively in 24 hours can also be used to prevent DVT.
6. Smoking increases the viscosity of blood and so should be stopped.
7. Patients on oral contraceptives or oestrogens should stop the drug 6-8 weeks prior to any elective surgery.

Effects and sequelae of DVT

1. Pulmonary embolism
2. Infection
3. Venous gangrene
4. Partial recanalisation, chronic venous hypertension around the ankle region causing venous ulcers
5. Recurrent DVT
6. Propagation of thrombus proximally—20-30%

VARICOSE VEINS

They are dilated, tortuous, elongated veins in the leg. There is reversal of blood flow through its faulty valves.

Types

1. Long saphenous vein varicosity.
2. Short saphenous vein varicosity.
3. Varicose veins due to perforator incompetence.
4. Thread veins (or dermal flares/telangiectasis/spider veins are 0.5 – 1 mm in size): Are small varices in the

Pulsatile varicose veins in lower limb is seen in Klippel Trenauny syndrome.



Fig. 1.345: Varicose veins in lower limbs

skin usually around ankle which look like dilated, red or purple network of veins.

5. Reticular varices (1-3 mm in size): Are slightly larger varices than thread veins located in subcutaneous region.
6. Combinations of any of above.

Small varicose vein is < 3 mm in diameter. Large varicose vein is > 3 mm in diameter.

Pathogenesis

Two Theories:
- Fibrin cuff theory
- White cell trapping theory

Incompetence of venous valves
↓
Stasis of blood
↓
Chronic ambulatory venous hypertension
↓
Defective microcirculation
↓
RBC diffuses into tissue planes
↓
Lysis of RBC's
↓
Release of haemosiderin
↓
Pigmentation
↓
Dermatitis
↓
Capillary endothelial damage
↓
Prevention of diffusion and exchange of nutrients
↓
Severe *anoxia*
↓
Chronic venous ulceration ***(Fibrin cuff theory)*.**

Inappropriate activation of trapped leucocytes release proteolytic enzymes which cause cell destruction and ulceration—***White cell trapping theory***. Fibrin deposition, tissue death, scarring occurs together, called as *lipodermatosclerosis***.**



Figs 1.346A and B: Lipodermatosclerosis is pigmentation, thickening, and induration of the skin due to venous diseases.

Classification of lower-extremity venous diseases (CEAP classification)

C — Clinical signs (grade 0-6); (A) for asymptomatic or (S) for symptomatic presentation.
E — Etiologic classification (congenital, primary, secondary).
A — Anatomic distribution (superficial, deep or perforator).
P — Pathophysiologic dysfunction (reflux or obstruction).

Aetiology of Varicose Veins

Varicosities are more common in lower limb because of erect posture and long column of blood has to be supported which can lead to weakness and incompetency of valves. Incidence is 5% of adult population.

a. *Primary varicosities* due to:
   1. Congenital incompetence or absence of valves.
   2. Weakness or wasting of muscles—defective connective tissue and smooth muscle in the venous wall.
   3. Stretching of deep fascia.
   4. Inheritance (family history) with FOXC2 gene.
   5. Klippel – Trenaunay syndrome.
b. *Secondary varicosities*:
   1. Recurrent thrombophlebitis,
   2. Occupational – standing for long hours (traffic police, guards).
   3. Obstruction to venous return like abdominal tumour, retroperitoneal fibrosis, lymphadenopathy.



Fig. 1.347: Bilateral varicose veins with pigmentation, ulcer and lipodermatosclerosis.



Fig. 1.348: Long saphenous vein varicosity.



Fig. 1.349: Long saphenous vein varicosity on the medial aspect.



Fig. 1.350: Bilateral varicose veins.

Venous claudication is acute bursting pain on ambulation due to chronic venous insufficiency.



Fig. 1.351: Ankle flare seen around ankle, which eventually leads into complications of varicose veins.

4. Pregnancy (due to progesterone hormone).
5. AV malformations—Congenital or acquired.
6. Iliac vein thrombosis.

Sites where varicosities can occur

- i. Lower limb
- ii. Pampiniform plexus of veins
- iii. Vulva
- iv. Sites of portosystemic anastomosis

Predisposing factors for varicose veins are - age, sex, race, obesity, height, left > right, occupation, family history, erect posture.



Fig. 1.352: Typical site of venous ulcer. Note the pigmentation and chronicity.

Clinical Features

Symptoms in varicose veins

- Dragging pain
- Heaviness in the legs
- Night time cramps – usually late night
- Oedema feet
- Discolouration/ulceration in the feet/painful walk

Causes of pain / cramps in varicose veins / venous diseases

- Increased venous wall tension – chronic venous hypertension
- Hypoxia of tunica media of the venous wall due to altered function of vasa vasorum
- Increased capillary pressure
- Hyperviscosity of red cells – haemorrheological disorders
- Platelet hyperaggregation
- Reduction in capillary permeability causing *capillary functional disorder*
- Altered cutaneous microcirculation due to leukocyte adhesion and accumulation into the venous wall; release of free radicals cause *microvascular lesional disease*

Oedema in venous diseases

- Can be localised or generalised
- Localised oedema is due to ankle flare or dilatation of medial marginal vein
- Cellulitis and lymphangitis association causes oedema
- Scarring and thickening of dermal and subdermal tissues – *lipodermatosclerosis* (brawny induration)
- Ankle becomes narrower due to contraction of skin and subcutaneous tissues but calf remains prominent – *champagne bottle appearance*
- Pale atrophic skin with white patches surrounded by dilated capillaries and pigmentation – *atrophic blanche*

It is more common in females (10 : 1). Often it is familial. *Familial varicose veins* begin in younger age group, seen bilaterally, involves all veins including deep veins.

1. Visible dilated veins in the leg with pain, distress, nocturnal cramps, feeling of heaviness, pruritus.
2. Pedal oedema, pigmentation, dermatitis, ulceration, tenderness, restricted ankle joint movement.
3. Bleeding, thickening of tibia occurs due to periostitis.
4. Positive cough impulse at the sapheno-femoral junction.
   Saphena varix – a large varicosity in the groin, which becomes visible and prominent on coughing.



Fig. 1.353: Saphena varix site – in the groin lower part just below the inguinal ligament.

5. **Brodie-Trendelenburg test**: Vein is emptied by elevating the limb and a tourniquet is tied just below the sapheno-femoral junction (or using thumb, sapheno-femoral junction is occluded). Patient is asked to stand quickly. When tourniquet or thumb is released, rapid filling from above signifies sapheno-femoral incompetence. *This is Trendelenburg test I.*

   In *Trendelenburg test II*, after standing tourniquet is not released. Filling of blood from below upwards rapidly can be observed within 30-60 seconds. It signifies perforator incompetence.



Fig. 1.354: Brodie-Trendelenburg test. Note the reversal of blood flow while releasing the tourniquet.



Figs 1.355A and B: Tourniquet tests for long saphenous vein and short saphenous vein.

6. ***Perthe's test:*** The affected lower limb is wrapped with elastic bandage and the patient is asked to walk around and exercise. Development of severe cramp like pain in the calf signifies DVT.
7. ***Modified Perthe's test***: Tourniquet is tied just below the sapheno-femoral junction without emptying the vein. Patient is allowed to have a *brisk walk* which precipitates *bursting pain* in the calf and also makes superficial veins more prominent. It signifies DVT.

   DVT is contraindicated for any surgical intervention of superficial varicose veins. It is also contraindicated for sclerosant therapy.
8. ***Three tourniquet test***: To find out the site of incompetent perforator, three tourniquets are tied after emptying the vein.
   1. at sapheno-femoral junction
   2. above knee level
   3. another below knee level.

   Patient is asked to stand and looked for filling of veins and site of filling. Then tourniquets are released from below upwards, again to see for incompetent perforators.
9. ***Schwartz test:*** In standing position, when lower part of the long saphenous vein in leg is tapped, impulse is felt at the saphenous junction or at the upper end of the visible part of the vein. It signifies continuous column of blood due to valvular incompetence.
10. ***Pratt's test***: Esmarch bandage is applied to the leg from below upwards followed by a tourniquet at

Everybody is in favour of progress. It is the change they don't like.

sapheno-femoral junction. After that the bandage is released keeping the tourniquet in the same position to see the *"blow outs"* as perforators.

11. ***Morrissey's cough impulse test:*** The varicose veins are emptied. The leg is elevated and then the patient is asked to cough. If there is sapheno- femoral incompetence, expansile impulse is felt at saphenous opening. It is a venous thrill due to vibration caused by turbulent backflow.
12. ***Fegan's test***: On standing, the site where the perforators enter the deep fascia bulges and this is marked. Then on lying down, button like depression (crescent like) in the deep fascia is felt at the marked out points which confirms the perforator site.
13. ***Ian-Aird test***: On standing, proximal segment of long saphenous vein is emptied with two fingers. Pressure from proximal finger is released to see the rapid filling from above which confirms sapheno-femoral incompetence.
14. Examination of the abdomen has to be done to look for pelvic tumours, lymph nodes, which may compress over the veins to cause varicosity

Grading of clinical signs

0 — No visible or palpable signs of venous disease
1 — Telangiectases, reticular veins or malleolar flare
2 — Varicose veins
3 — Oedema without skin changes
4 — Skin changes ascribed to venous diseases (pigmentation, venous eczema, lipodermatosclerosis)
5 — Skin changes as above with healed ulceration
6 — Skin changes as above with active ulceration



Fig. 1.356: Bilateral varicose veins. Note the tortuous long saphenous vein.

Venous disability scoring system

Score 0	Asymptomatic
Score 1	Symptomatic but able to carry out activities without any therapy
Score 2	Symptomatic – can do activities only with compression/limb elevation
Score 3	Symptomatic – unable to do daily activities even with compression or limb elevation

Venous segmental disease score (venous clinical scoring system) is done based on different symptoms/signs/ulcer activity/compression therapy with 10 parameters with each having 3 scores as mild/moderate/severe.

Investigations

1. ***Venous Doppler***: With the patient standing, the doppler probe is placed at sapheno-femoral junction and later wherever required. Basically by hearing the changes in sound, venous flow, venous patency, venous reflux can be very well-identified.

Fig. 1.357: Doppler machine to assess venous system and its problems.

2. ***Duplex scan*** is a highly reliable U/S Doppler imaging technique (here high resolution B mode ultrasound imaging and Doppler ultrasound is used) which along with direct visualisation of veins, gives the functional and anatomical information, and also colour map. Examination is done in standing lying down position and also with valsalva manoeuvre. *Hand-held Doppler* probe is placed over the site and visualised for any block and reversal of flow. DVT is very well-identified by this method.

Venous Doppler in varicose veins

- To find out DVT- very important
- To find out sapheno-femoral, sapheno-popliteal incompetence
- To find out perforator incompetence

- Uniphasic signals signify flow in one direction – normal
- Biphasic flow signifies reversal flow with incompetence

3. ***Venography:***
   - *Ascending venography* was very common investigation done before Doppler period.

     A tourniquet is applied above the malleoli and vein of dorsal venous arch of foot is cannulated. Water soluble dye injected, flows into the deep veins (because of the applied tourniquet). X-rays are taken below and above knee level. Any block in deep veins, its extent, perforator status can be made out by this.

     It is a good reliable investigation for DVT.

     If DVT is present, surgery or sclerotherapy are contraindicated.
   - *Descending venogram* is done when ascending venogram is not possible and also to visualise incompetent veins. Here contrast material is injected into the femoral vein through a cannula in standing position. X-ray pictures are taken to visualise deep veins and incompetent veins.

Phlebography

- Ascending phlebography defines obstruction
- Descending phlebography identifies valvular incompetence
- Regularly not required to be done

4. ***Plethysmography*****:** It is a noninvasive method which measures volume changes in the leg.
   - ***Photo plethysmography*****—**Using probe transmission of light through the skin, venous filling of the surface venules which reflects the superficial venous pressure is measured. Initially patient performs dorsiflexion at ankle for 10 times to empty the venules and pressure tracing falls in photo plethysmography. Patient takes rest and refilling occurs. In normal people, it occurs through arterial inflow in 20-30 seconds. In venous incompetence filling also occurs by venous reflux and so refilling time is faster than normal.

     Disadvantage: Site of reflux cannot be localised by this method.
   - ***Air plethysmography*****—**Patient is initially in supine position with veins emptied by elevation of leg. Air filled plastic pressure bladder is placed on calf to detect volume changes. Minimum volume is recorded. Patient is turned to upright position and venous volume is assessed. Maximum venous volume divided by time required to achieve maximum venous volume gives the *venous filling index (VFI)*. VFI is a measure of reflux. *Ejection fraction* is volume change measured prior and after single tiptoe maneuver which is a measure of calf pump action. *Residual venous fraction* is an index of overall venous function which is venous volume in the leg after ten toetip maneuvers divided by venous volume prior to maneuver. *Increased VFT and diminished ejection fraction in a patient will benefit from surgery.*
5. ***Ambulatory venous pressure (AVP)*****:** It is an invasive method. Needle inserted into dorsal vein of foot is connected to transducer to get its pressure which is equivalent to pressure in the deep veins of the calf. Ten tiptoe maneuvers are done by the patient. With initial rise in pressure, pressure decreases and eventually stabilises with a balance. Pressure now is called as *ambulatory venous pressure (AVP)*. After stopping exercise, veins are allowed to refill with return of pressure to baseline. Time required for pressure to return to 90% of baseline is called as *venous refilling time (VRT).* Raise in AVP signifies venous hypertension. Patients with AVP more than 80 mmHg has got 80% chances of venous ulcer formation.
6. ***Arm-Foot venous pressure:*** Foot pressure is not more than 4 mmHg above the arm pressure.
7. ***U/S abdomen***, peripheral smear, platelet count, other relevant investigations are done depending on the cause of the varicose veins.
8. If venous ulcer is present, then the discharge is collected for culture and sensitivity, biopsy from ulcer edge is taken to rule out Marjolin's ulcer.
9. Plain X-ray of the part is taken to look for periostitis.
10. ***Varicography***: Here non-ionic, iso-osmolar, non-thrombogenic contrast is injected directly into the variceal vein to get a detailed anatomical mapping of the varicose veins. It is used in recurrent varicose veins.

Differential diagnosis

- Lymphoedema
- A-V malformation
- Orthostatic oedema
- Renal and cardiac disease
- Hepatic causes

An ounce of action is worth a ton of theory.

- Vasculitis
- Metabolic diseases like gout, myxoedema, and morbid obesity
- Chronic infections like tuberculosis, syphilis

Treatment

1. ***Conservative treatment:***
    - *Elastic crepe bandage application* from below upwards or use of pressure stockings to the limb—pressure gradiant of 30-40 mmHg is provided.
    - *Diosmin therapy* which increases the venous tone.
    - *Elevation of the limb*—relieves oedema.
    - *Unna boots*—provide nonelastic compression therapy. It comprises a gauze compression dressings that contain zinc oxide, calamine, and glycerine that helps to prevent further skin break down. It is changed once a week.
    - *Pneumatic compression method*—provide dynamic sequential compression.
2. ***Drugs used for varicose veins:***
    - Calcium dobesilate—500 mg BD. Calcium dobesilate improves lymph flow; improves macrophage mediated proteolysis; and reduces oedema.
    - Diosmin—450 mg BD
    - Diosmin 450 mg + Hesperidin 50 mg (DAFLON 500 mg). Mainly used in relieving night cramps but not to improve healing of ulcers.
    - Toxerutin 500 mg BD, TID. Anti erythrocyte aggregation agent which improves capillary dynamics.

    Benefits of all these drugs are doubtful.
3. ***Injection—sclerotherapy***: (Fegan's technique). By injecting sclerosants into the vein, complete sclerosis of the venous walls can be achieved.

    Indications
    - Uncomplicated perforator incompetence.
    - In the management of smaller varices—reticular veins, thread veins (telangiectasis).
    - Recurrent varices.
    - Isolated varicosities.
    - Aged/unfit patients.

Sclerosants used are—
- Sodium tetradecyl sulphate 3% (STDS)–commonly used
- Sodium morrhuate
- Ethanolamine oleate
- Polidocanol

Mechanisms of action
- Causes aseptic inflammation
- Causes perivenous fibrosis leading to block
- Causes approximation of intima leading to obliteration by endothelial damage
- Alters intravascular pH/osmolality
- Changes surface tension of plasma membrane

A 23 gauge needle is inserted into the vein (3-8 mm sized) and vein is emptied. 0.5-1 ml of sclerosant is injected into the vein and immediately compression is applied on the vein (prevent the entry of blood which may cause thrombosis, which later gets recanalised, further worsening the condition) so as to allow the development of sclerosis and to have proper endothelial apposition.

Usually injection is started at the ankle region and then proceeded upwards along the length of the veins at different points. Later pressure bandage is applied for six weeks. Often injections may have to be repeated at 2-4 weeks intervals for 2-4 sessions. Technique is called as *macrosclerotherapy.*

Microsclerotherapy: Very dilute solution of sclerosing agent like STDS, (0.1% of 0.1 ml –dilute) Polidocanol is injected into the thread veins and reticular veins followed by application of compression bandage (30 G needle). Dermal flare will disappear well by this method.

Transillumination microsclerotherapy *(vein – lite)* is better imaging of the veins using light generated by halogen bulb with high quality fibre illumination over the skin uniformly and passing 30 gauge needle for microsclerotherapy.

Foam sclerotherapy by Tessari-

STDS taken in a syringe is passed rapidly into another syringe which contains air to result in formation of foam. This foam in much larger quantity is injected into the superficial vein. Air get absorbed between foam and endothelial lining is destroyed. Foam minimises thrombosis by pushing the blood out of the site of the vessel where action is needed. Polidocanol is used for foam sclerotherapy. Headache, transient blindness, stroke, air embolism are the rare complications specific to foam sclerotherapy.

Echosclerotherapy-

Sclerotherapy is done under duplex ultrasound image guidance.

Contraindications for sclerotherapy
- Sapheno femoral incompetence
- Deep venous thrombosis
- Huge varicosities – may precipitate DVT
- Peripheral arterial diseases
- Hypersensitivity/immobility
- Venous ulcer – relative contraindication

Advantages
- It can be done as an outpatient procedure.
- It does not require anaesthesia.

Disadvantage
- Inadvertent subcutaneous injection can cause skin necrosis or abscess formation.
- Anaphylaxis.
- Hyperpigmentation.
- Thrombophlebitis.
- Deep venous thrombosis can occur.

Remember about sclerotherapy
- Current place of sclerotherapy is mainly for recurrent varicosities and thread/telangiectatic veins
- Sodium tetradecyl sulphate (STDS) is most commonly used sclerosant
- Hyperpigmentation is common after STDS
- Anaphylaxis is common after sodium morrhuate
- Anaphylaxis is least with polidocanol
- Extravasation (presence of pain/irritation/burning) should be avoided as it will cause skin necrosis
- Post sclerotherapy walking immediately after injection for 30 minutes with elastic bandage in place prevents/minimises the chances of DVT
- Compression bandage should be worn for minimum period of 6 weeks
- Sclerotherapy can be – macrosclerotherapy; microsclerotherapy; echo (ultrasound guided) sclerotherapy; foam sclerotherapy; transilluminated sclerotherapy

4. ***Surgery:***

   a. ***Trendelenburg operation*:** It is juxta-femoral flush ligation of long saphenous vein (i.e. flush with femoral vein), after ligating named (superficial circumflex, superficial external pudendal, superficial epigastric vein), deep external pudendal vein and unnamed tributaries. All tributaries should be ligated, otherwise recurrence will occur. Double saphenous vein is the commonest anomaly occuring near sapheno-venous junction.

   b. **Stripping of vein:** Using *Myer's stripper* vein is stripped off. Stripping from below upwards is technically easier. Immediate application of crepe bandage reduces the chance of bleeding and haematoma formation. Stripping avulses the vein as well as obliterates the tributaries. Babcock's stripper and rigid metal pin stripper can also be used.

   Stripping of the short saphenous vein is done from ankle below upwards after passing stripper from above downwards. It obliterates the mid calf perforator vein which is the common reason for recurrences.

   Complication is injury to saphenous nerve causing *saphenous neuralgia.*

   Stripping is not usually done for the veins in the lower part of the leg in LSV.

   Stripping of the vein is more effective.

   'Inverting or invaginating stripping' using rigid *Oesch pin stripper* is better as postoperative pain and haematoma is less common and also there is tissue damage. Vein should be very firmly fixed to the end of the stripper and pulled out to cause the inverting of the vein.

   Stripping of short saphenous vein is more beneficial than just ligation at sapheno popliteal junction. It is done from above downwards using a rigid stripper to avoid injury to sural nerve.



Fig.1.358: Linton's vertical approach for subfascial perforator ligation in the leg.

INR (International Normalised Ratio): Ratio of measured PT to a mean lab control PT corrected for the sensitivity of thromboplastin


A
Olive tips (knobs)
Handle
Detachable tip
Stripper
B

Figs 1.359A and B: Photo of Myer's stripper with Olive tips and also diagrammatic look of the same.


Inguinal ligament
Anterior superior iliac spine
Incision
LSV

Fig. 1.360: Incision for juxta-femoral flush ligation of long saphenous vein (Trendelenburg operation).


TRIBUTARIES
SF JUNCTION
LSV
A
ALL TRIBUTARIES LIGATED
LSV
SF JUNCTION
B
LSV
SFJ
SJF ligation
C

Figs 1.361A to C: Sapheno-femoral junction and its ligation. Tributaries are well seen.



Fig. 1.362: Stripper knob on the distal part of the vein before stripping of the vein.





Figs 1. 363A to D: Long saphenous vein stripping. Note the stripped vein. Stripping is better than just ligation at the junction.

c. ***Subfascial ligation of Cockett and Dodd*:** Perforators are marked out by Fegan's method. Perforators are ligated deep to the deep fascia through incisions in antero medial side of the leg.
d. ***Ligation of short saphenous vein*** at sapheno-popliteal junction. It is done in prone position

A man without purpose is like a ship without rudder.



Fig. 1.364: Typical perforator ligation.



Fig. 1.365: Cockett and Dodd subfascial ligation of perforators using multiple small horizontal incisions.

with horizontal incision. Variations in SP junction are common. But stripping is better.

e. Removal of superficial varicose veins by *hook phlebectomy.*

f. ***Linton's vertical approach***—subfascial ligation of perforators.

g. Stab avulsion of varicose vein and perforators. Avulsion is done using mosquito forceps or avulsion hooks. Multiple incisions are made and veins are carefully and gently avulsed/teased to clear it. Post operative compression bandage is a must.

h. *Subfascial endoscopic perforator ligation surgery* (*SEPS*). It is becoming cosmetically popular.



Fig. 1.366: Avulsion of the perforator using hook or mosquito forceps through a small skin incision.

i. ***Radiofrequency ablation (RFA) method (VNUS closure method***) (VNUS medical technologies Inc; Sunnyvale, CA, USA) (by Goldman 2000): This procedure is done under general or regional anaesthesia. A RFA catheter is passed into long/short saphenous vein near sapheno femoral or sapheno-popliteal junction under guidance. 85°C temperature is used for longer period of time to cause endothelial damage, collagen denaturation and venous constriction. Phlebectomy is done while withdrawing the catheter. Wall of the vein is destroyed through its full thickness. Vein forms a cord, which gets dissolved by macrophages and immune cells.

j. ***Trivex method*** **:** Under subcutaneous illumination and local anaesthesia, a large quantity of fluid is injected percutaneously to identify the superficial veins under. Tumescent anaesthesia created causes hydrodissection. Trivex resector and illuminator are placed under the skin. Resector gently extracts veins by suction and morcellation. Further stages of tumescence flushes all blood and delivers vasoconstriction solutions. Solution is passed through 18 gauze needle to clear all blood underneath. Method is cosmetically acceptable; removes all sized veins; achieves good pain relief; with minimal complications like bruising, induration which gets resorbed eventually; and can be used when there are venous ulcers.

k. ***Endo venous laser ablation (EVLA)***: It is done as an outpatient procedure or as day- care surgery. Patient lies supine with diseased leg flexed, hip externally rotated and knee flexed. With aseptic precaution, under U/S guidance LSV is cannulated above the knee and a guide wire is passed beyond SFJ and 5- French catheter is passed over guide wire and tip is placed 1 cm distal to the junction. 200 ml of 0.1 % lignocaine (crystalloid with local anaesthetic) is infiltrated along the length of the LSV. Laser fibre is inserted up to the tip of the catheter and catheter is withdrawn for 2 cm and laser fibre protrudes for 2 cm. Laser fibre is fired step by step using diode laser, one mm withdrawal in 2 seconds. Once procedure is over catheter is removed and pressure bandage is applied for 2 weeks. Heat produced (729°C – 1000°C at tip) by the laser produces steam bubbles with thermal damage of endothelium leading into occlusion of the vein. Laser energy acts on the blood within the vein rather directly through the wall and heats the blood and in turn heats the vein wall. *Drawback of laser* therapy is inability to create flush occlusion allowing tributaries to open up to cause possible recurrence.







Figs 1.367A to D: Endovenous laser ablation (EVLA) for varicose veins.

1. ***Other methods*:** *Transilluminated phlebectomy* is done by passing transilluminating light under the skin and passing a rotating blade through another small incision. Veins are grasped and removed by rotating movements. *Ambulatory phlebectomy* is done through tiny small incisions using special phlebectomy instruments. *Electrodessication* using weak electric current through a fine needle directly into the spider veins (telangiectasis) is also used.

Strong convictions precede great actions.

Problems in varicose vein surgery

- Infection—10%
- Haematoma formation
- DVT—0.01%
- Saphenous neuralgia, sural nerve injury
- Recurrence

Note: Contraindication for surgery is deep vein thrombosis (DVT).

Complications of Varicose Veins

- Haemorrhage: Venous haemorrhage can occur from the ruptured varicose veins or sloughed varicose veins, often torrential, but can be controlled very well by elevation and pressure bandage.
- Eczema and dermatitis.
- Periostitis causing thickening of periosteum.
- Venous ulcer.
- Marjolin's ulcer.
- Lipodermatosclerosis.
- Ankylosis of the ankle joint.
- Talipes equino varus.
- Deep venous thrombosis.
- Calcification.
- Thrombophlebitis.

VENOUS ULCER (Gravitational ulcer)

It is the complication of varicose veins or deep vein thrombosis.



Fig. 1.368: Venous ulcers in the lower limb.

Pathogenesis of Venous Ulcer

Varicose veins or DVT which are recanalised, eventually causes *chronic venous hypertension* around ankle.

↓

Causes haemosiderin deposition in the subcutaneous plane from lysed RBC's

↓

Eczema

↓

Dermatitis

↓

Lipodermatosclerosis

↓

Fibrosis

↓

Anoxia

↓

Ulceration

- *Area where venous ulcer commonly develop, is around and above the medial malleoli* because of presence of large number of perforators which transmit pressure changes directly into superficial system. This area is called as *Gaiter's zone*. It can also be on both malleoli.
- Ulcer is often large, nonhealing, tender, recurrent with secondary infection. Vertical group of inguinal lymph nodes are usually enlarged and tender.
- Often it leads to scarring, ankylosis, Marjolin's ulcer formation. Slough from the ulcer bed may give way causing venous haemorrhage.
- *Periostitis is common* which also prevents ulcer from healing.
- Most of the venous ulcers have surrounding lipodermatosclerosis. *Lipodermatosclerosis is pigmentation, thickening, chronic inflammation and induration of the skin in calf and around ankle.*
- Due to regular walking on toes so as to relieve the pain causes contraction and extra-articular fibrosis of achilles tendon. Proper exercise is the remedy for– *talipes equino varus.*

Note: 70-80% of leg ulcers are venous ulcers.

Investigations

- Discharge from the ulcer for culture and sensitivity.
- X-ray of the area to look for periostitis.
- Biopsy from the ulcer edge to rule out Marjolin's ulcer.
- Investigations to rule out other causes of leg ulcers like arterial; neurological; diabetes; sickle cell disease and other haemolytic diseases.
- Erythrocyte sedimentation rate; C reactive protein, peripheral smear; red cell counts.
- Doppler – venous and often arterial.

Treatment

Bisgaard method of treating venous ulcer:

- Measures to reduce oedema, increase venous drainage, so as to promote ulcer healing.
  - Elevation.
  - Massage of the indurated area and whole calf.
  - Passive and active exercise.

- Pressure bandage (crepe bandage).
- Care of ulcer by regular cleaning with povidone iodine, H_2O_2.
- Dressing with EUSOL.
- Four layer bandage (45 mm Hg pressure) technique to achieve high compression pressure. It is changed once a week.
- Antibiotics depending on culture and sensitivity of the discharge.

Once ulcer bed granulates well, split skin graft (SSG) is placed *(Thiersch Graft).*

Specific treatment for varicose veins should be undertaken—Trendelenburg operation, stripping of veins, perforator ligation.

Fifty percent of venous ulcer occurs as a result of recanalisation of DVT, and the leg is commonly called as ***postphlebitic limb (leg).*** It presents with all complications of venous diseases like eczema, ulceration, lipodermatosclerosis and venous ulcers. Here surgery for superficial varicose veins are contraindicated. Venous valve repair ***(Kistner's valvuloplasty)*** or *valve transplantation* or drugs like ***Stanazolol,*** which reduces the fibrous tissue thereby increasing the oxygenation are beneficial.



Fig. 1.369: Patient should wear stockings regularly in postoperative period for 3-6 months. It will reduce the recurrence rate and symptoms.



Fig. 1.370: Skin grafting over a venous ulcer after formation of healthy granulation tissue.

Complications of venous ulcers

- Haemorrhage
- Marjolin's ulcer (in unstable scar of long duration)
- Infection
- Talipes equino varus
- Periostitis is common over the tibia
- Disability
- Calcification

(**EUSOL** is Edinburgh University solution of lime containing *boric acid, sodium hypochlorite, calcium hydroxide.)*

Note:

- Present concept is to treat the ulcer first by compression bandage; regular dressing; skin grafting. Once ulcer has healed definitive procedure for varicose veins is done. Studies show that rapidity of healing of ulcer perse is not dependent on the surgery for varicose veins.
- Recurrence rate of venous ulcer after proper therapy is 30%. Reulcer formation is more in post phlebitic/thrombotic limb.

COMPRESSION THERAPY FOR VARICOSE VEINS

- Compression reduces the venous wall tension; prevents reflux; controls the venous over-distension
- Compression diverts the blood towards deep veins through perforating veins; prevents the outward flow of blood in perforator incompetence; improves the efficacy of calf muscle pump. Compression reduces

the oedema and improves the venous and lymphatic drainage; improves venous elasticity; improves the microcirculation and more important is it prevents further damage of the venous wall.

- Compression may be elastic/inelastic/combination of elastic and inelastic (*Unna boot*)/multilayered (four layered) compression system which can provide sustained high compression for several days - usually up to a week/intermittent pneumatic compression. Unna boot is three-layered paste gauze compression dressing containing calamine, zinc oxide, glycerin, sorbitol, gelatin and aluminium silicate which has mainly inelastic inner component with partly elastic outer layer wrap.
- Recommended pressure in mild varicose veins, pregnancy and postoperative period is 20 mmHg; in symptomatic varicose veins and after sclerotherapy is 30 mm Hg; in venous ulcer and post phlebitic leg it is 40-45 mm Hg; in phlebolymphoedema (venous oedema with lymphatic oedema which is more dangerous) it is more than 45 mm Hg.
- Skin maceration, excoriation, dryness, infection, ulceration and failure are the complications of compression therapy.

Remember

- Compression improves ulcer healing rate
- Supplementation of phlebotonic drugs in conjunction with compression therapy is accepted
- Inelastic compression causes more improvement (reduction) in venous filling index (VFI) than elastic compression. But elastic compression is more commonly used because it is better accepted
- Multi-layered bandage system is most effective
- Ankle-arm pressure index less than 0.6 is contraindication for compression therapy as it may precipitate ischaemic ulcer formation
- Exercise may improve the muscle – pump action

Compression garments standard

British standard

- Class I: 14-17 mm Hg
- Class II: 17-24 mm Hg
- Class III: 24-35 mm Hg

International (European) standard

- Class I: 20-30 mm Hg
- Class II: 30-40 mm Hg
- Class III: 40-50 mm Hg
- Class IV: 50-60 mm Hg

Compression Bandages

- *Type I* – Light weight confirming stretch bandages. These comprise light weight elastomer with high elasticity but little power. It is used to retain dressings.
- *Type II* (short stop) - Light support bandages. Minimal stretch. Exhibit limited elasticity but tends to lock out on minimal extension. In ambulant patient CVI they form an essentially inelastic covering to the leg which will exert pressure during calf systole but not during diastole. They are unsuitable for control of oedema.
- *Type III* (Long stop) - are extensible elastic and powerful to a varying degree.

THROMBOPHLEBITIS

It is the inflammation of veins, usually superficial veins due to different causes. It is actually superficial vein thrombosis with inflammation (slight).

Types

1. *Acute***:** Due to IV cannulation, trauma, minor infections, hypercoagulability.
2. Recurrent.
3. *Spontaneous:* Polycythaemia vera, polyarteritis, Buerger's disease.
4. *Thrombophlebitis migrans (Trousseau's sign)*: It is spontaneous migrating thrombophlebitis seen in visceral malignancy like pancreas, stomach.

Clinical Features

Pain, redness, tenderness, cord like thickening of veins, fever.

It can be seen either in upper limb or lower limb.

Complications

- Destruction of venous valves resulting in varicose veins.
- DVT.
- Embolism.
- Infection.

Treatment

- Elevation.
- Anti-inflammatory drugs, antibiotics.
- Application of crepe bandage.

ANTICOAGULANTS

These are the agents used to prevent and treat thrombosis and thromboembolic events.

HEPARIN

- It is a natural anticoagulant, a mucopolysaccharide.
- It prevents clotting of blood both *in vivo* and *in vitro* by acting on all three stages of coagulation. It *prolongs clotting time* and *activated thromboplastin time* in specific (by 1.5-2.0 times the control).
- Heparin also causes hyperkalaemia, thrombocytopenia.
- Commercial heparin is derived from lung and intestinal mucosa of pigs and cattle.
- The onset of action is immediate after administration, lasting for 4 hours.
- It is metabolised in the liver by heparinase.
- It does not cross placental barrier and is not secreted in breast milk.

Indications

- As prophylaxis in major surgeries, postoperative period, puerperium.
- As therapy in DVT.

Dose

- For prophylaxis: 5,000 units/subcutaneously 8th hourly.
- For therapy: 10,000 units/IV 6th or 8th hourly. Later changed to subcutaneous dose.
- In severe cases, 5,000 units to 20,000 units is given daily through IV infusion at a rate of 1,000 units per hour. Daily dose should not exceed 25,000 units.

Heparin should not be given intramuscularly and should not be combined with streptokinase or urokinase. Heparin is not given orally.

Heparin administration should always be monitored with APTT.

Complications

Allergy, bleeding, thrombocytopenia.

Danaparoid is an antifactor Xa, heparinoid, is an anticoagulant used in patients where heparin is contraindicated.

LOW MOLECULAR WEIGHT HEPARIN (LMWH)

It is a commercially prepared heparin with a molecular weight of 4,000 to 6,500.

- Enoxaparin.
- Dalteparin.
- Parnaparin.
- Reviparin.
- Fraxiparin.

Advantages

- Have a longer duration of action - once a day
- Have a better anticoagulant effect
- Less interaction with platelets
- Less antigenic
- Usage is easier and more acceptable
- Monitoring is not necessary

Disadvantages

They are expensive.

Presently LMWH are becoming very popular.

Heparin antagonist: 50 mg of 1% protamine sulphate solution is given slow intravenous. 1 gm reverses 100 units of heparin. It is given only after doing activated thromboplatin time. Overdosing or infusion without indication may itself precipitate bleeding.

ORAL ANTICOAGULANTS

They are given orally and are slow acting.

Types

1. *Coumarin derivatives*: Bishydroxycoumarin (Dicoumarol): First coumarin drug derived from sweet clover. *Warfarin sodium: Commonest oral anticoagulant used.*
2. *Indandione derivative*: Phenindione, anisindione.

Mode of Action of Oral Anticoagulant Therapy

- By suppressing synthesis of prothrombin, factors VII, IX and X.
- By inhibiting Vit K mediated carboxylation of glutamic acid.
- Oral anticoagulant does not have *in vitro* action.
- They are slow acting, and long acting.
- Control of oral anticoagulant therapy is by *monitoring prothrombin time*.
- PT comes to normal only 7 days after cessation of the drug.
- *They cross placental barrier and are known to cause teratogenicity when given in 1st trimester.*
- *They are secreted in breast milk.*

Indications

1. In DVT after cessation of heparin for maintenance therapy.
2. After valve replacement surgery.

To achieve adequate anticoagulant effect and to prevent thromboembolic episodes the *INR* has to be maintained within 2-3.

Attitudes are more important than facts.

Side Effects

1. Bleeding—It may require blood transfusion or vitamin K injection intramuscular or oral to control.
2. Cutaneous gangrene.
3. Fetal haemorrhage and teratogenicity.
4. Alopecia, urticaria, dermatitis.
5. Drug interactions: with NSAIDS, cimetidine, omeprazole, metronidazole, cotrimoxazole, erythromycins, barbiturates, rifampicin, griseofulvin.

WARFARIN (**W**iskonian **A**lumini **R**esearch **F**oundation + coum**ARIN** derivative) *SODIUM* is the commonest drug used. It has got lesser side effects. It has got cumulative action and so given in tapering dose.

Dose is 5 mg, once a day.

It should be discontinued 7 days before any surgery like tooth extraction and prothrombin time should return to normal level. During surgery, if excess bleeding occurs, fresh frozen plasma may be given.

The effects of warfarin sodium is reversed by inj. Vit K; the dose depends on INR and emergency of reversal (takes 24 times to reverse).

IN VITRO ANTICOAGULANTS: Oxalates, citrates, EDTA (Ethylene diamine tetra-acetic acid).

Thrombolytic agents

- Streptokinase
- Urokinase
- Anistreplase
- Alteplase

Differences between oral anticoagulants and heparin

	Oral anticoagulant	*Heparin*
	Slow acting	Immediate
	Long acting	Short acting
	Only *in vivo* action	Both *in vitro* and *in vivo* action
Monitored by:	Prothrombin time	Partial thromboplastin time
	Crosses the placental barrier	Does not cross the placenta
	Secreted in milk	Not secreted in milk
Administration:	Orally	Intravenously

Contraindications for anticoagulant therapy:

- Ongoing bleeding
- Recent surgery/invasive procedure
- Severe trauma
- Bleeding tendency (clotting factor deficiency)
- Intracranial haemorrhage
- Pericarditis/pericardial effusion
- Patient prone to fall

DIRECT THROMBIN INHIBITORS

A. Recombinant hirudin and hirudin analogues—derived from leeches, are direct inhibitors of thrombin.
B. Argatroban—synthetic direct thrombin inhibitor.

ANTIPLATELET DRUGS

- Small dose aspirin—inhibits platelet synthesis of thrombaxane A2
- Ticlopidine (125 mg BD)—alters platelet membrane, thereby platelet aggregation
- Clopidogrel—action similar to ticlopidine
- Dextran—decreases platelet aggregation
- Abciximab—glycoprotein IIb/IIIa inhibitors, block platelet aggregation, and platelet adhesion to fibrin.
- Dipyridamole—xanthine oxidase inhibitor.

Self-assessment Questions

1. Describe aetiology, pathogenesis, clinical features, complications, management of varicose veins.
2. Classify ulcers. Discuss pathogenesis, clinical features, and management of venous ulcer due to DVT.
3. Deep venous thrombosis.
4. Management of varicose ulcers.
5. Venous ulcers.
6. Phlebothrombosis.
7. Trendelenburg sign.
8. Trendelenburg test.
9. Trendelenburg operation.
10. Discuss management of perforator incompetence.
11. Injection sclerosant therapy.
12. Bisgaard's regimen.
13. Heparin.
14. Oral anticoagulants/Warfarin.
15. Postphlebitic leg ulcer.
16. Lipodermatosclerosis.
17. Pulmonary embolism.
18. Short saphenous vein.
19. Modified Perthe's test.

Lymphatics

Lymphangiography
Isotope lymphoscintigraphy
Lymphoedema
Lymphomas—*Hodgkin's lymphoma, non-Hodgkin's lymphoma, Burkitt's lymphoma, Cutaneous T cell lymphoma*
Chylous ascites
Chylothorax
Chyluria
Sarcoidosis

LYMPHANGIOGRAPHY

Indications

- Congenital lymphoedema like aplasia, hypoplasia, hyperplasia.
- Lymphomas show *reticular* pattern. It is also useful to assess the response to treatment.
- Secondaries in lymph nodes, especially iliac and para-aortic lymph nodes.

Technique

Patent blue dye or 1 ml Isosulphan blue is injected subcutaneously between toes. Dye is taken up by lymphatics which will be visualised clearly. After making incision, one of the lymphatic vessels is dissected and 30G needle is passed. Ultra fluid lipiodol which is an oily contrast medium is injected slowly using pressure pump at a rate of 1 ml in 8 minutes (total quantity is 7 ml). Slowly in 24 hours, it passes through the lymphatics and reaches the iliac and paraaortic lymph nodes. Radiographs taken will help to visualize both lymphatic vessels as well as lymph nodes.

Secondaries in lymph nodes causes filling defects. Lymphomas shows enlarged nodes which have foamy or reticular appearance.

Disadvantages

- Technically difficult.
- Extravasation of dye can occur.
- Dye may not reach the required area.
- Time consuming and invasive procedure.

Lymphangiographic classification of lymphoedema ***(Browse classification):***

- *Congenital hyperplasia (10%)* – Congenital; common in males; entire leg is involved; one or both sides; with often family history; progressive; involves increased number of lymphatics and lymph nodes associated with chylous ascites, chylothorax and protein losing enteropathy
- *Distal obliteration (80%)* – Common in females; starts at puberty; calf and ankle are involved; often bilateral; with often family history; slow progression; aplasia/hypoplasia of lymphatics
- *Proximal obliteration (10%)* – Occurs at any age; equal in both sexes; leg and thigh involved; unilateral; rapid progression; proximal aorto iliac nodal block

ISOTOPE LYMPHOSCINTIGRAPHY

Radioactive technetium labelled antimony sulphide colloid particles are injected into the web space using fine needle. These particles are specifically taken up by lymphatics. Using gamma camera, limb and inguinal region is exposed to visualise the lymphatics and inguinal lymph nodes. In 3 hours, it reaches the para-aortic lymph nodes, other abdominal lymph nodes and liver. Later thoracic duct also can be visualised. It can be compared to the take up on the other limb.

Advantages

- It is more sensitive.
- Technically easier and faster compared to lymphangiography.
- Thoracic duct, other lymph nodes and liver can be visualised.

LYMPHOEDEMA

It is accumulation of fluid (lymph) in extracellular and extravascular fluid compartment, commonly in subcutaneous tissue. It is primarily due to defective lymphatic drainage. It is protein rich interstitial fluid.

CLASSIFICATION

Kinmoth classified lymphoedema as

- Primary without any identifiable lymphatic disease.
- Secondary is acquired due to definitive cause. ***Most common form.***

> *In very early oedema, during pinching, there is a resistance that is not present on normal site, owing to thickening of dermis and subcutaneous tissue.*
> —Sidney S Rose

Primary type

It affects commonly females.

It is common in lower limb and left side.

It can be

- Familial
- Syndromic

It can be

- Lymphoedma congenita — present at birth - < 2 year
  — Familial type is called as *Nonne – Milroy's disease*
- Lymphoedema praecox — present at puberty—up to 2-35 years. 80%
  — Familial type is called as *Letessier – Meige's syndrome*
- Lymphoedema tarda — present in adult life—after 35 years

It can be radiologically (lymphangiography)-

- Hypoplasia 70 %
- Aplasia 15 %
- Hyperplasia (varicose lymphatics) 15 %



Fig. 1.371: Right side congenital lymphoedema in a girl.



Fig. 1.372: Early lymphoedema left side – pitting type.



Fig. 1.373: Late lymphoedema – grade 2.



Fig. 1.374: Lymphoedema leg extending into the thigh with lymphangitis.



Fig. 1.375A



Fig. 1.375B



Fig. 1.375C



Fig. 1.375D

Figs 1.375A to D: Lymphoedema foot in different patients-severe with vesicles/oedema/skin changes/fissures

Causes of secondary lymphoedema

- Trauma
- Surgery—inguinal block or axillary block dissection/post mastectomy with axillary clearance
- Filarial lymphoedema due to Wuchereria bancrofti Common cause in coastal region
- Tuberculosis
- Syphilis
- Fungal infection
- Advanced malignancy—Hard, fixed lymph nodes in axilla or in inguinal region
- Postradiotherapy lymphoedema
- Bacterial infection
- Rare causes: Rheumatoid arthritis, snake and insect bites, DVT, chronic venous insufficiency

Pathology (*commonly in filarial lymphoedema*)

Recurrent lymphangitis causes obliteration of lymph vessels

↓

Dermal lymphatic backflow

↓

Retrograde obliteration (or die back of lymphatics)

↓

Oedema, initially pitting but later nonpitting

↓

Recurrent cellulitis—thickening of skin

↓

Accumulation of proteins, growth factor, glycosaminoglycans

↓

Activation of collagens and keratinocytes

↓

Protein rich lymphoedematous tissue formation

↓

Deposition of ground substance, subdermal fibrosis

↓

Dermal thickening and dermal proliferation, Fissuring → Cracks — Ulceration – Abscess formation

↓

Stout leg with unbearable weight

↓

Elephantiasis.

Rarely it causes protein losing diarrhoea, chylous ascites, chylothorax, chyluria, lymphorrhoea. Recurrent lymphadenitis occurs in the region which aggravate the condition.

Disease in the limb is confined to skin and subcutaneous tissue, i.e. often, only superficial lymphatics are involved by the disease, deep lymphatics are not. Superficial and deep lymphatics are not communicating

Don't consume your tomorrow's feeling on your yesterday.

with each other. (Unlike the veins in the limb where superficial and deep veins are freely communicating with each other.)

Sites of lymphoedema

1. Lower limb—commonest
2. Upper limb
3. Scrotum, penis (Ram's horn penis)
4. Breast—requires reduction mammoplasty
5. Labia
6. Eyelid
7. Localised lymphoedema



Fig. 1.376: Ram's horn penis.

Clinical Features

- Swelling in the foot, extending progressively in the leg.
- *Buffalo hump* in the dorsum of the foot.
- Squaring of toes.
- Skin over the dorsum of foot can not be pinched because of subcutaneous fibrosis—*Stemmer's sign.*
- Initially pitting oedema occurs, which later becomes nonpitting.
- Dull ache/severe pain/burning/bursting/cramps; 50% patients will have pain.
- Debility/immobility/obesity/muscle wasting.
- Athlete's foot with joint pain and disability.
- Eczema, fissuring, papillae formation, ulceration, lymph ooze, elephantiasis are other features.
- Fever, malaise, headache.
- Recurrent abscess formation.
- Psychological and social discomfort causing severe morbidity.
- *Endemic elephantiasis/podoconiosis* is common in Africa; seen in barefoot workers; due to destruction of lymphatics by silica derived from soil containing alkaline volcanic rocks.

Brunner's grading of lymphoedema

Latent—subclinical: No clinically apparent lymphoedema.

Grade I	Pitting oedema which more or less disappears on elevation of the limb—is due to excess deposition of interstitial fluid
Grade II	Nonpitting oedema occurs which does not reduce on elevation
Grade III	Oedema with irreversible skin changes like fibrosis, papillae, fissuring

Differential Diagnosis

1. Cardiac causes, hypoproteinaemia, malnutrition, nephrotic syndrome, liver failure.
2. Myxoedema.
3. Trauma.
4. Venous diseases like DVT.
5. Lipodystrophy and lipoidosis (lipoedema). Lipoedema occurs exclusively in females; begins in puberty; bilateral and symmetrical; trunk may be involved; feet are not involved; not pitting; not related to elevation/compression; MRI shows only fat without fluid.
6. Arterial diseases including A-V malformations.
7. Gigantism.
8. Drug induced—Steroids, estrogens, nifedipine.
9. External compression of veins as caused by abdominal tumours.



Figs 1.377A and B: Filariasis-Elephantiasis (A) Leg and Foot and (B) Hand.



Figs 1.378A to C: Different lymphoedema pictures. Note the oedema, fissuring, cracks. All these make it more vulnerable for infection.



Fig. 1.379: Lymphoedema of lower limb developed after ilioinguinal block dissection for nodal secondaries from melanoma.



Fig. 1.380: Recurrent filarial leg with nodules and ulceration.



Fig. 1.381: Extensive scrotal lymphoedema of filarial origin. Patient underwent scrotal reduction.



Fig. 1.382: Lymphoedema *right arm and forearm.* Common causes for upper limb lymphoedema are filarial and post mastectomy with axillary nodal clearance.

Knowledge speaks, but wisdom listens.



Figs 1.383A and B: Lymphoedema of penis. It needs reduction and reconstruction otherwise it may cause urinary problem and sexual dysfunction.

Investigations

- For the cause
- ESR, peripheral smear
- Lymphangiography
- Isotope-lymphoscintigraphy.
- MRI

Complications

1. Skin thickening
2. Recurrent cellulitis with nonhealing ulcers
3. Lymphangiosarcoma.

Treatment

Conservative

1. Elevation of the limb, exercise, weight reduction.
2. Static isometric activities like prolonged standing or carrying weights should be avoided; rhythmic isotonic movements like swimming/massaging should be encouraged.
3. Diuretics to reduce the oedema is controversial. It more often causes eletrolyte imbalance than being beneficial.
4. Benzopyrones are protieno lytic agents/*lympedim.*
5. Daily wearing of below knee stockings.
6. Avoid trauma and infection.
7. Intermittent pneumatic compression devices (Pressure > 50 mmHg); multilayered lymphoedema bandaging (MLLB) – non elastic type is preferred method; graded stockings.
8. Antibiotics—Flucloxacillin, erythromycin, long acting penicillins.
9. Topical antifungal 1% clotrimazole and systemic griseofulvin 250-1000 mg.
10. Regular washing and keeping the limb clean is very important.
11. Diethyl carbamazine citrate (DEC) 100 mg TID for 3 weeks.
12. Pain relief – by suitable means.
13. Skin care –
    - Keratolytics like salicylic acid 5%; bland emollient; soft/liquid paraffin.
    - Avoidance of skin sensitisers like some soaps.
    - Topical steroids.
    - Control of allergy.
    - Control of fungal infection by drugs like fluconazole.
    - 3% benzoic acid ointment to prevent Athlete's foot.
    - Control of lymphorrhoea.
    - Prevention/control of skin infections.
14. **Complex decongestive therapy** is a comprehensive two phase program of elevation, exercise, massaging, and compression wraps. First phase is *intensive therapy* and second phase is *maintenance therapy*.

    Compression wraps may be high stretch wraps or low stretch wraps. Low stretch wraps are better accepted. It should be worn initially for 24 hours. Compression wraps are used in initial intensive phase of therapy. *Graduated elastic compression garments* are used in maintenance phase which provides maximum pressure of 50 mm Hg at the distal part with gradual reduction of pressure in proximal portion.

Manual lymphatic drainage is a specialised technique to stimulate the contractility of lymph collecting vessels and enhance fluid and protein transport by gentle, light, superficial massaging of the skin so as to open up new lymphatic vessels. Technique is done first on the opposite normal side; then trunk, same side trunk; same side proximal; same side distal and later same side distal to proximal fashion, so as to redirect the lymph towards functioning lymphatic territories.

Surgery

Surgeries for lymphoedema has been classified as:

a. *Excisional*
   - Charle's operation.
   - Homan's operation.

b. *Physiological*
   - Omentoplasty.
   - Nodovenous shunt (Neibulowitz)
   - Lymphovenous shunt (O'Brien's).
   - Ileal mucosal patch.

   Here either communication between superficial and deep lymphatics are created or new lymphatic channels are mobilised to the site.



Fig. 1.384: Charles excisional surgery. Here after excising lymphoedematous tissue, area is covered with skin graft.

Omentoplasty (Omental pedicle): As omentum contains plenty of lymphatics, omental transfer with pedicle will facilitate lymph drainage.

c. *Combined:* Both excision + creation of communication between superficial and deep lymphatics.
   - Sistrunk operation.
   - Thompson's operation.
   - Kondolean's operation.

d. *Bypass procedure*:
   - Handley's silk thread burial in subcutaneous tissue.
   - Skin bridge across the thigh and abdomen (Gillies).
   - Nodovenous shunt.
   - Lymphovenous shunt using microscope.
   - Ileal mucosal patch (Kinmonth).
   - Baumeister lymphatic grafting.
   - Autotransplantation of free lymphatic flap from opposite side – done in post mastectomy lymphoedema (Trevidic and Cormier).

e. *Limb reduction surgeries*:
   - ***Sistrunk operation:*** Along with excision of lymphoedematous tissue, window cuts in deep fascia is done, so as to allow communication into normal deep lymphatics.
   - ***Homan's operation:*** Excision of lymphoedematous tissue is done after raising skin flaps. Later skin flaps are trimmed to required size and sutured primarily. Medial and lateral sides of the limb are done at separate sittings with 6 months interval.
   - ***Thompson's operation***: Lymphoedematous tissue is excised under the skin flaps. Epidermis and part of the dermis of one of the skin flaps is shaved off using Humby's knife. It is buried under opposite flap, deep to the deep fascia like a *swiss roll (Swiss roll operation* or *buried dermal flap operation).* Problems here are formation of epidermal cysts and sinus.
   - ***Kondolean's operation***: Along with excision of lymphoedematous tissue, vertical strips of deep fascia is removed so as to open the deep



Fig. 1.385: Thompson's Swiss-roll operation. Here after removal of lymphoedematous tissue, deep fascia is opened to expose the muscle. Epidermis abraded using skin graft knife. This shaved dermis is buried into the muscle to get communication into the deeper lymphatics.

Indecisive people are like a blind man looking in a dark room for a black cat that isn't there.

lymphatics which creates communication between superficial and deep lymphatics.

- ***Macey's operation***: Here skin and subcutaneous tissue are peeled back with deep fascia and split skin grafting is done over the denuded area. Overlying pad of tissue is sutured back temporarily and after 10 days, it is trimmed away.
- ***Miller's procedure*****:** It is excision of subcutaneous tissues under the skin flap with deep fascia in two stages. First stage is done over the medial aspect of the limb; second stage done after two months over lateral aspect of the limb.
- ***Charle's operation*****:** Done in severe lymphoedema with elephantiasis. Along with excision of lymphoedematous tissue, skin grafting is done. It reduces the size and weight of the limb. Patient becomes ambulatory.
- Reduction surgeries are done for lymphoedema of scrotum, penis, labia and eyelid.

In severe type, occasionally amputation may be required.



Fig. 1.386: Diagram showing right side groin nodovenous shunt between iguinal lymph node and long saphenous vein. Left side showing lymphovenous shunts between dilated lymphatics and long saphenous vein. At least 4 lymphatics should be anastomosed using 7 zero/11 zero prolene-using operative microscope.

LYMPHOMAS

They are progressive neoplastic condition of lymphoreticular system arising from stem cells.



Fig. 1.387: Enlarged, B/L, rubbery neck LNs of lymphoma. Note the involvement of lacrimal sac.



Figs 1.388A and B: Stage IV lymphoma with neck nodes/sternal swelling/axillary nodes which has ulcerated (ulceration is not common in lymphoma).

Lymphomas are the 3rd most common malignancy among children comprising 15% of paediatric cancers.

Aetiology

- Genetic predisposition.
- Sjogren's syndrome – 30 fold increase of NHL.
- HIV infection.
- Wiskott – Aldrich syndrome.
- Ataxia – Telangiectasia.
- Bloom's syndrome.
- Virus etiology – Epstein Barr virus.
- Celiac sprue – intestinal T cell lymphoma.
- H pylori may be associated with MALT lymphoma.
- Occupation causes – hair dye workers; herbicide exposure.
- Ionizing radiation.
- Smoking; alcohol consumption; tobacco usage.
- Lymphomas are more common in western countries than in Asia.

Types

- *Hodgkin's lymphoma (HL).*
- *Non-Hodgkin's lymphoma* (NHL).

WHO modified **REAL** classification (**R**evised **E**uropean **A**merican **L**ymphoma) of lymphoma:

1. B-cell neoplasms
    - I. Precursor B cell neoplasm—ALL, LBL.
    - II. Peripheral B cell neoplasm—It includes all B cell related non-Hodgkin's lymphomas
2. T-cell and putative NK cell neoplasms
    - I. Precursor T cell neoplasms—ALL and LBL T cell related.
    - II. Peripheral T cell and NK cell neoplasm—It includes all T cell related non-Hodgkin's lymphomas.
3. Hodgkin's lymphoma
    - I. Predominant HL—Nodular lymphocyte type
    - II. Classical HL
        - Nodular sclerosis
        - Lymphocyte rich
        - Mixed cellularity
        - Lymphocyte depletion

Note: ALL is acute lymphoblastic leukaemia. LBL is lymphoblastic lymphoma.

Older classifications *(Not practiced now):*

- Jackson and Parker (1944) – Paragranuloma; granuloma; sarcoma.
- Lukes and Butler (1966) – Lymphocytic and histiocytic nodular; lymphocytic and histiocytic diffuse; nodular sclerosis; mixed cellularity; diffuse fibrosis; reticular.

HODGKIN'S LYMPHOMA (HL)

> ***(The lymph glands of the neck) exhibited a firm cartilaginous structure of a light colour and very feeble vascularity, but with no appearance of softening or suppuration. Glands similarly affected accompanied the vessels into the chest, where the bronchial and mediastinal glands were in the same state and greatly enlarged…. The spleen was enlarged to at least four times its natural size… presenting the same structure as the enlarged glands.***
>
> **—Thomas Hodgkin,** 1832

- It is the most common type of lymphoma.
- Grossly lymph nodes are fleshy, pinkish grey, and rubbery in consistency.
- Microscopically contains cellular infiltration with lymphocytes, reticulum cells, histiocytes, fibrous tissue and ***Reed-Sternberg*** cells. (Reed-Sternberg cells are giant cells with two large mirror image nuclei.)

Rye's classification

1. Lymphocytic predominance. Has got *good prognosis.*
2. Mixed cellularity.
3. Nodular sclerosis.
4. Lymphocytic depletion. Has got *poor prognosis.*

(Reed-Sternberg cells are also seen occasionally in certain other conditions like glandular fever).

Clinical Features

- It is more common in males.
- It has got bimodal presentation. It is seen in young and adolescents (20-30 years) as well as in elderly (> 50 years).
- Painless progressive enlargement of lymph nodes. They are smooth, firm, nontender, typically *India rubber* consistency.

Site

- Cervical lymph nodes commonest—82% (lower deep cervical group and in posterior triangle).
- Others include axillary, mediastinal, inguinal, abdominal.

Specific Features

- Nodular sclerosis is most commonest type.
- Consecutive group of lymph nodes are involved.
- *Splenomegaly* is very common (45%).
- Hepatomegaly with jaundice—jaundice is due to haemolysis or due to diffuse liver involvement.

A successful team beats with one heart.



Figs 1.389A and B: Lymphoma in a boy and in an adolescent with neck nodes. Note the diffuse nature. Nodes are usually India rubber consistency.

- *Constitutional symptoms like fever, pruritus, weight loss may be present which signifies stage "B", which has got poor prognosis. Stage "A" is absence of these symptoms which signifies better prognosis.*

  Stage 'B' symptoms:
  - Weight loss, more than 10% in 6 months.
  - Fever, earlier called as *Pel Ebstein fever* is actually is due to brucellosis.
  - Pruritus
  - Anaemia
  - Bone pain
- Mediastinal lymph node involvement may cause compression features like SVC obstruction.
- Occasionally bone like vertebrae may get involved.
- Anaemia, pancytopaenia.



Fig. 1.390: Hodgkin's lymphoma in neck region.



Fig. 1.391: Fungating lymphoma in both axilla of a patient.

Ann-Arbor Clinical Staging:

Stage 1: Confined to one group of lymph node.
Stage 2: More than one group of lymph nodes on one side of the diaphragm.
Stage 3: Nodes involved on both sides of the diaphragm.
Stage 4: Extra nodal involvement like liver, bone marrow.
Suffix 'S'—Spleen involved
Suffix 'B'—Presence of constitutional symptoms
Suffix 'A'—Absence of constitutional symptoms

Note: In modification, following additions are there.

- Single extra lymphoid site is IE
- An extra lymphoid site with one or more lymph nodes same side of diaphragm is II E.
- An extra lymphoid site with lymph nodes on both sides of diaphragm III E.
- An extra lymphoid site with spleen and lymph nodes on both sides of diaphragm III SE.
- Spleen with lymph nodes on both sides of diaphragm is III S.

N—Nodes H—Liver S—Spleen L—Lung
M—Marrow P—Pleura O—Bone D—Skin

Stage III (1) is nodes above renal vein level and Stage III (2) is below it.

Differential Diagnosis

- Tuberculosis.
- NHL.
- HIV.
- Chronic lymphatic leukaemia.
- Nonspecific lymphadenitis.
- Sarcoidosis.
- Secondaries in lymph nodes.



Fig. 1.392: Secondaries in neck lymph nodes. It is hard, large probably fixed and nonmobile making it advanced and inoperable.

Investigations

- Blood: Hb%, ESR, peripheral smear, blood urea, serum creatinine.
- FNAC of lymph nodes.
- Excision biopsy of lymph nodes. Full lymph node is excised to retain the architecture of the lymph node. It is important to grade the tumour.
- Chest X-ray—to look for mediastinal lymph nodes, pleural effusion.
- U/S abdomen—to look for the involvement of liver, spleen, abdominal lymph nodes.
- CT scan of mediastinum and abdomen better method.
- Lower limb lymphangiography to look for the pelvic and retroperitoneal lymph nodes.
- Bone marrow biopsy to stage and also to see the response to treatment.
- *Staging laparotomy*: The abdomen is opened. Splenectomy is done mainly to remove the tumour bulk, as spleen is commonly involved and also to avoid irradiation to splenic area which often causes unpleasant pulmonary fibrosis. Biopsies are taken from both lobes of the liver (needle biopsy) from paraaortic, celiac mesenteric, iliac nodes. In females ovaries are fixed behind the uterus to prevent radiation oophoritis *(oopheropexy/ovarian translocation).*

  Staging laparotomy is not routinely done now. It is done only if it benefits the patient to have better plan of treatment or better result.



Fig. 1.393: Staging laparotomy for Hodgkin's lymphoma. Needle and wedge biopsies from liver/nodal biopsies from paraaortic, celiac, mesenteric, iliac nodes/splenectomy/ovarian translocation/iliac crest biopsy are the components of staging laparotomy. This can be very well-achieved through laparoscopy also now. Staging laparotomy is not commonly done now.

> *The difference between ordinary and extraordinary is that little extra.*—Zig Ziglar

Treatment for HL

Treatment strategy for HL

- Early favourable stage – extended field radiation only
- Early unfavourable stage – extended radiation plus chemotherapy
- Advanced stage – extensive chemotherapy often with local radiation

Unfavourable signs in early HL

- Large mediastinal mass
- Extranodal disease
- Elevated ESR
- Four or more involved regions
- Presence of B symptoms
- Anaemia; low serum albumin level
- Age more than 50
- Male gender

Note: First five parameters are most important.

- Stage I and II:
  1. Mainly ***radiotherapy***—External high cobalt RT.
     - Above the diaphragm—*"Y" field therapy*, covering cervical, axillary, mediastinal lymph nodes.
     - Below the diaphragm, *mantle* or *inverted "Y" field therapy*, covering paraaortic and iliac nodes.
  2. Chemotherapy is also given.
- Stage III and IV: Mainly ***chemotherapy***.

Drugs used include—

• Mustine.	**M**. (Mechloroethamine).
• Oncovine.	**O.** (Vinca alkaloids).
• Procarbazine.	**P.**
• Prednisolone.	**P.**

Other regimens available — MVPP, ABVD



Figs 1.394A and B: Mediastinal nodes involved in lymphoma as seen in chest X-ray and Chest CT scan.

Differences between HL and NHL

	HL (more common)	*NHL*
Age:	Young and elderly	Middle age and elderly
Pattern of involvement:	Symmetrical and consecutive	Asymmetrical
Cervical lymph node:	Commonly involved	Any group can be involved
Splenomegaly:	Common	Not common
Peripheral lymph node involvement (e.g. epitrochlear nodes).	Not common	Common
Treatment:	Mainly radiotherapy Chemotherapy (MOPP regime)	Mainly chemotherapy
Prognosis:	Better	Poor

Treatment for Relapses

- Autologous stem cell transplantation.
- High dose chemotherapy.
- High dose chemotherapy with autologous stem cell transplantation.
- MOPP/ABV hybrid regime.
- Single dose vinorelbine (new vinca alkaloid); gemcitabine; immunotherapy; tumour vaccination; gene therapy.

Prognosis

- Stage I and II – 80%.
- Stage II IA – 70%.
- Stage III B and stage IV – < 40%.

Prognostic factors

1. Stage I and II has got better prognosis.
2. Lymphocytic predominance has got better prognosis.
3. Stage "A" without constitutional symptoms has got better prognosis.

NON-HODGKIN'S LYMPHOMA (NHL)

- It occurs in middle aged and elderly. It is more aggressive than HL.
- It involves asymmetrical group of lymph nodes.
- General condition is poor.
- Inner Waldeyer ring, epitrochlear lymph nodes, peripheral lymph nodes are commonly involved.
- Spleen is not commonly involved.
- Hepatomegaly is common.
- Vertebral involvement is common; paraplegia can occur.
- Secondary infection, cachexia and immunosuppression is more common.

Types

- Nodular (Follicular)
- Diffuse lymphocytic
- Undifferentiated
- Histiocytic type.

Rappaport classification	*Working classification*
• Nodular • Diffuse	• Low grade • Intermediate grade • High grade

Note: Many different classifications are there for NHL. Students have to refer pathology book when needed.

Treatment

Mainly **chemotherapy**

Various regimens available include:

- ChOPP—Chlorambucil, Oncovin, Procarbazine, Prednisolone.
- ABVD—Adriamycin, Bleomycin, Vincristine, Dacarbazine.
- ABVP—Adriamycin, Bleomycin, Vincristine, Prednisolone.
- Combinations of above.

Role of radiotherapy in NHL: When vertebra is involved.

Prognosis is poor compared to HL.

BURKITT'S LYMPHOMA (Malignant Lymphoma of Africa)

> ***Thirty-eight cases of a sarcoma involving the jaws of African children are described. This is a syndrome which has not previously been fully recognized. It is by far the commonest malignant tumour of childhood seen at Mulago Hospital.***
>
> **—Denis Parsons Burkitt,** 1958

- It is common in South Africa and New Guinea.
- *Epstien Barr virus* may be the etiological agent. It is common in children.
- It is associated with infectious mononucleosis.
- It is common in malaria endemic area.
- The tumour is multifocal, rapidly growing, painless.
- Different groups of lymph nodes can also be affected.

Microscopy

Primitive lymphoid cells with large clear histiocytes—*starry night (starry sky*) pattern.

Sites

- It is common in jaw—either lower or upper.
- Abdominal presentation and renal involvement is common (75%).
- Renal involvement often may be bilateral.
- In females, ovaries are commonly affected.

Types

1. Endemic (African)—Commonly occurs in jaw
2. Nonendemic (sporadic)—Commonly occurs in abdomen
3. Aggressive lymphoma—Occurring in HIV patients.

Man cannot discover new oceans unless he has courage to lose sight of the shore—Anonymous

Investigation

- FNAC and biopsy confirms the diagnosis.
- Jaw X-ray shows osteolytic lesions.
- U/S abdomen is done to look for involvement of kidneys.
- Blood urea and serum creatinine estimation is done.

Treatment

- Radiotherapy.
- Chemotherapy: Cyclophosphamide, Methotrexate, Orthomelphalan.
- Surgery is usually not indicated unless it is localised or in case of involvement of ovaries.

Prognosis is good.

CUTANEOUS T CELL LYMPHOMA

- Cutaneous T cell lymphoma comprises mycosis fungoides, Sezzary syndrome, reticulum cell sarcoma of skin and other cutaneous lymphocytic dysplasias. Mycosis fungoides is the commonest among them.
- Cutaneous T cell lymphoma can be indolent (commonly mycosis fungoides); aggressive (Sezzary syndrome); provisional (granulomatous/panninculitis like T cell lymphoma).
- Initial macular patch/plaque phase slowly changes into tumour phase with painful, pruritic erythroderma often with visceral spread. Alopecia mucinosa and follicular mucinosis are common in mycosis fungoides. Lymph nodes may get involved. Tumor cells in peripheral smear are also important in deciding therapy and prognosis.
- Multiple skin biopsies/peripheral smear/node biopsy/immunohistochemistry/pheo or genotyping are important investigations
- Prognosis depends on extent of skin involvement (more the 10% body surface area carries poor prognosis)/nodal spread/blood spread.
- *Treatment:* Localised external beam radiotherapy; topical chemotherapy (bexarotene gel/carmustine ointment); phototherapy; total skin electron beam therapy; extracorporeal photochemotherapy. Bexarotene is a type of retinoid.
- *Sezzary syndrome* is a type of cutaneous T cell lymphoma with skin lesions with special Sezzary cells having cribriform nucleus. It is often associated with leukaemias. It is treated like any other cutaneous T cell lymphoma.

CHYLOUS ASCITES

It is collection of lymph in the peritoneal cavity. It is due to obstruction of intestinal lymphatics and subsequent leak.

Causes

- Filarial lymphoedema causing obstruction.
- Malignancy either nodal secondaries or nodal primary causing obstruction.
- Tuberculosis causing blockage of lymph drainage and rupture and leak into the peritoneal cavity.
- Post-surgical cause.

Features

- Ascites, often massive.
- Severe malnutrition and protein deficiency.
- Features specific to the cause.
- Ascitic fluid aspiration is chalky white in colour and it shows chylomicrons. It should be studied for fat globules, proteins, AFB and malignant cells.
- Laparoscopy and biopsy is necessary when lymphoma/secondaries are suspected.
- CT scan and CT guided biopsy may be needed.
- Lymphangiography to find out the site of leak.

Treatment

- Control of infection.
- Antituberculous and antifilarial drugs.
- Fat free, protein rich diet.
- Nutritional support.
- Medium chain triglycerides can be given as it directly gets absorbed into the blood rather into the lymphatics.
- Repeated tapping, peritoneo-venous shunts are often required.

CHYLOTHORAX

It is accumulation of lymph in the pleural cavity.

It is *common on right side* because of long course of thoracic duct towards right side.

Causes

- Injury due to trauma/surgeries in neck or chest. Surgical trauma is the commonest cause—may be oesophageal surgeries, pneumonectomy, cervical sympathectomy, neck dissections or aortic surgeries.
- Tuberculosis, lymphoma or secondaries in the mediastinum.
- Carcinoma lung or oesophagus.

Features

- Chest pain, dyspnoea, pleural effusion.
- Protein loss and malnutrition
- Pleural tap will show chalky white fluid rich in chylomicrons.
- Chest X-ray, CT chest are needed.

Treatment

- ICT placement
- Fat free protein rich diet
- Antibiotics therapy for the cause.
- Often pleurodesis using bleomycin, talc, tetracycline or pleural stripping is needed.
- Thoracic duct ligation is beneficial in traumatic/ iatrogenic cases.

CHYLURIA

- It is passage of milky white chylous urine, which is aggravated after fatty meal.
- It may be due to obstruction of intestinal lymphatic vessels leading to high lymphatic pressure causing diversion of lymph into renal lymphatics or it often may be due to rupture of intestinal lymphatics into renal pelvis or ureter leading into a lymphourinary fistula.
- Commonest cause is filarial. Other causes are tumour, tuberculosis, malaria and ascariasis infestation.
- Urinary infection, protein loss is common.
- It mimics bacterial/tuberculous pyuria or phosphaturia.
- Urine study, culture, IVU, lymphangiography, U/S abdomen is needed.
- Treatment is low fat, protein rich diet, antibiotics, DEC, plenty of oral fluid intake, ligation of dilated lymphatics through laparotomy or sclerosing the lymph vessels.
- Condition causes severe psychological and nutritional problem.

SARCOIDOSIS

It is a differential diagnosis for lymph node mass. It is basically a granulomatous condition of unknown cause with bilateral hilar lymphadenopathy; with involvement of lungs, liver, spleen, lymph nodes, lacrimal glands, parotid glands, CNS, hypercalciuria, acute onset of erythema nodosum in the skin. Fever and loss of weight are not common. It shows noncaseating epithelioid granuloma with positive Kveim-Siltzbach skin test (80%); high levels of serum angiotensin converting enzyme (SAGE). Investigations needed are - CT chest; mediastinoscopy; nodal biopsy; slit lamp examination of eye; often abnormal immunoglobulins in the circulation. It is treated by corticosteroids with good response. It should be differentiated from other causes of lymphadenopathy especially Hodgkin's lymphoma.

Note: **For topics tuberculous lymphadenitis and lymph node secondaries please refer chapter 'Neck'.**

Self-assessment Questions

- Discuss causes, clinical features and management of lymphoedema.
- Filarial lymphoedema.
- Elephantiasis.
- Treatment of lymphoedema.
- Lymphangiogram.
- Hodgkin's lymphoma.
- Staging laparotomy.
- Staging of Hodgkin's lymphoma.
- Treatment of Hodgkin's lymphoma.
- Burkitt's lymphoma.
- MOPP regime.
- Causes of cervical lymphadenopathy.

Laugh at obstacles and cry at your success.

Peripheral Nerves

> *The power of moving in every part of the body by means of the muscles which obey the will, or by means of others the actions of which are involuntary; the various perceptions by the five external senses; and lastly those mental powers named memory, imagination, attention, and judgement, together with the passions of the mind; all these seem to be exercised by the ministry of the nerves; and are impaired, disturbed, or destroyed, in proportion to any injury done to the brain, the spinal marrow, and nerves, not only by their peculiar diseases, of which we know little, but by contusions, wounds, ulcers, and distortions, and by many poisons of the intoxicating kind.*
>
> —**William Heberden**, 1802

Peripheral nerve injuries
Brachial plexus injuries
Causalgia
Median nerve injury
Carpal tunnel syndrome
Ulnar nerve injury
Claw hand
Radial nerve injury
Common peroneal nerve injury
Foot drop
Medial popliteal nerve injury
Axillary nerve injury
Long thoracic nerve injury

PERIPHERAL NERVE INJURIES



Fig. 1.395: Cross-section of a nerve

CLASSIFICATION

Seddon's Classification

- *Neuropraxia:* It is temporary physiological paralysis of nerve conduction. Here recovery is complete. There is no reaction of degeneration.
- *Axonotmesis:* It is division of nerve fibres or axons with intact nerve sheath. There is reaction of degeneration distally with near complete recovery. Patient can present with sensory loss, paralysis of muscles or causalgia.



Fig. 1.396: Dermatomes

- *Neurotmesis:* Here complete division of nerve fibres with sheath occurs. Degeneration occurs proximally up to the first node of Ranvier as well as distal to the injury. Recovery is incomplete even after nerve suturing. There is complete loss of motor and sensory functions with loss of reflexes. If the nerve is mixed type other than pure motor or sensory recovery is still poorer.

Injuries may be incised or lacerated or crushed one.

Cut end of the nerve forms proximally *neuroma* and distally *glioma.*

Neuromas may be –
- True neuroma or false neuroma.
- End neuroma or side neuroma.

Sunderland's classification

I: Conduction block—temporary neuronal block
II: Axonotmesis but endoneurium is preserved
III: Axonotmesis with disruption of endoneurium, but perineurium is preserved
IV: Here disruption of endo and perineurium has occurred but epineurium is intact
V: Neurotmesis with disruption of endo, peri and epineurium has occurred

Clinical Features

- Loss of sensory, motor, autonomous and reflex functions.
- Secondary changes in the skin and joint.

Primary nerve suturing is done if it is a clean incised wound.

Secondary nerve suturing is done after 3 weeks if it is a crushed wound.

Management

- Associated injuries like fracture, vessel injury, injuries in other systems should be looked for.
- Assessment of nerve injury is done by checking sensation, muscle power, reflexes.
- Nerve conduction studies.
- Investigations relevant for associated injuries.
- Exploration of the wound.

Debridement of the area is done. If injury is incised one, then nerve is sutured with 8-0 to 10-0 nonabsorbable interrupted sutures (polypropylene).

Types of Nerve Suturing

Usually microscope or loup is used for nerve suturing.

i. *Epineurorrhaphy*: Only epineurium is sutured using interrupted sutures.
ii. *Epi-perineurorrhaphy*: Initially perineural sheath and then epineurium is sutured.

If nerve is lacerated, then *marker stitches (using silk)* are placed at the cut end site to identify the nerve for suturing at a later period.

If nerve suturing fails or if could not be done, then tendon transfer is done at a later period after 4-6 months.

Incomplete injury usually does not require any suturing.

Easier suturing is achieved by following methods:

- Relaxing incisions.
- Transpositioning of the nerve.
- Shortening of the bone.
- Nerve graft—usually sural nerve is used for nerve graft.
- Positioning of the limb.
- Initially *neurolysis* (release of the scar tissue adjacent to injury) is done in case of secondary suturing.

Prognostic factors in healing of the nerve injury:

- Higher the lesion worser the prognosis.
- More the gap between the cut ends worser the prognosis.
- Associated injuries alter the prognosis.
- Children do better with nerve injury.
- Type of the injury also decides the prognosis.

The rate of growth of nerves after peripheral nerve suturing is 1 mm/day.

TINEL'S SIGN

It is the clinical sign (Prognostic indicator) used to assess the level of regeneration. It is elicited 3 weeks after the nerve injury. (Regeneration begins after the completion of nerve degeneration.)

Tapping over the course of the nerve is done *from distal to proximal* to elicit a sensation of "*pins and needles*" or *hyperaesthesia.*

If sensation is felt at the site as well as distally along the distribution of the nerve, that means good recovery can be expected. If sensation is felt only at the site of tapping, then result is equivocal. If no sensation is felt it means no recovery.

CAUSES OF PERIPHERAL NERVE LESIONS

- Traumatic: Either closed or open injury
- Inflammatory: Leprosy, Herpes zoster, diphtheria
- Compression neuropathies
- Lead poisoning
- Arsenical poisoning
- Alcoholism
- Diabetes mellitus
- Vitamin B_1 deficiency
- Porphyria
- Neurofibroma and other neural tumours
- Idiopathic

BRACHIAL PLEXUS INJURIES

It can be

• Supraclavicular injury	65%
• Infraclavicular injury	25%
• Combined	10%

It can also be

- Upper plexus injury
- Lower plexus injury

It's how you deal with failure determines how you achieve success.



Fig. 1.397: Brachial plexus anatomy.

It can be

Pre-ganglionic injury	**Post-ganglionic injury**
Avulsion injury	Usually less severe
More dangerous	Better recovery
Extends into the spinal cord	

Investigations

- Nerve conduction studies.
- CT/MRI.
- Electromyogram.
- X-ray cervical spine and part.

Treatment

- Conservative
- Nerve repair.
- Tendon transfer.
- Physiotherapy.

CAUSALGIA

It is severe burning pain and hyperaesthesia in the distribution of a peripheral nerve due to *incomplete injury* to the nerve.

Sites

Common in upper limb.

Commonly seen in median nerve, also often in brachial plexus injuries. In the lower limb it is seen in sciatic nerve or tibial nerve injuries.

Pathology

Incomplete nerve injury produces abnormal impulse towards sensory nerve ending causing vasomotor instability and pain.

Clinical Features

- Hyperaesthesia with severe disabling and burning pain.
- Skin becomes red, shiny and glossy which sweats profusely—*Weir-Mitchell's skin*
- Eventually skin becomes atrophic, cyanotic, cold and blotchy.
- Skin is less sensitive to heat, cold, and pin prick, but hypersensitive to touch and tender to pressure
- Nails are rigid, brittle with change in colour.

Investigation

Nerve conduction studies.

Treatment

- Anti-inflammatory drugs, steroids, physiotherapy.

Features of Upper and Lower Plexus Injuries

Upper plexus injury *(Erb-Duchenne paralysis)*	**Lower plexus injury** *(Klumpke's paralysis)*
1. It is due to depression of shoulder by trauma	1. Forcible hyperabduction of shoulder causes this injury
2. After difficult labour in newborn	2. In newborn it result due to difficult breech delivery
3. Here C_5 and C_6 roots are injured	3. Here C_8 and T_1 are injured
4. Muscles affected are deltoid, biceps brachioradialis and supinator	4. Intrinsic muscles of the hand are involved
5. *Effects are:*	5. *Effects are:*
a. Elbow will be extended, pronated and upper limb is internally rotated (*Policeman receiving tip)*	a. Combined median and ulnar claw hand
b. Sensory deficit over the lateral aspect of arm and upper part of the lateral forearm	b. Horner's syndrome
	c. Sensory deficit over the medial aspect of forearm, hand, and medial 1½ finger

- IV guanethidine regionally
- If not improved, sympathectomy—cervical for upper limb, lumbar for lower limb.

MEDIAN NERVE INJURY

- Median nerve arises from lateral ($C_{5,6,7}$) and medial cord (C_8 and T_1) of the brachial plexus. It is initially lateral to the axillary artery and becomes medial in the lower part of the arm and in the cubital fossa. It passes through the pronator teres, descends in relation to flexor muscles and enters the palm through the carpal tunnel at the wrist.
- It supplies pronator teres, flexor carpi radialis, palmaris longus and flexor digitorum superficialis. Anterior interosseous branch of the median nerve supplies pronator teres, lateral half of the flexor digitorum profundus, flexor pollicis longus and pronator quadratus.
- In the wrist, it supplies abductor pollicis brevis, flexor pollicis and opponens pollicis of thenar eminence and lateral two lumbricals. It gives sensory supply to lateral three and half fingers of the hand.

Median nerve is affected in

1. Injuries
    a. Supracondylar fracture of the elbow
    b. Fracture-dislocation of the elbow
    c. Direct cut injuries
2. Leprosy.
3. Carpal tunnel syndrome
4. As a part of brachial plexus injury

Clinical Features of Median Nerve Palsy

In high median nerve palsy

- Wasting of the thenar eminence. Loss of sensation on lateral three and half fingers.
- Ochsner's clasping test shows pointing index because of the inactivity of lateral two divisions of the profundus.
- *"Ape or Simian thumb deformity"* is due to overaction of the adductor pollicis which is supplied by the deep branch of ulnar nerve. As all other thenar muscles are paralysed, thumb comes in the same plane of the metacarpals.
- *"Pen test"*: In median nerve injury, pen held in front of the hand can not be touched by thumb as abduction is not possible due to paralysis of the abductor pollicis brevis.

In low median nerve palsy profundus is not paralysed and so *pointing index* is not seen.

Investigations

- Nerve conduction studies.
- X-ray of the part in case of fracture.
- Electromyogram.

Treatment

- Nerve suturing or nerve graft.
- Tendon transfer.
- Treat the cause like carpal tunnel syndrome.

CARPAL TUNNEL SYNDROME

- It is the compression neuropathy of median nerve in the carpus, deep to flexor retinaculum.
- Flexor retinaculum (transverse carpal ligament) maintains the concavity of wrist and extends laterally from trapezium and scaphoid to pisiform and hook of the hamate medially.

Carpal tunnel is formed by carpal bones behind and flexor retinaculum in front. It contains median nerve and long flexor tendons of fingers and thumb. Ulnar nerve lies superficially, not in the carpal tunnel.

Median nerve gets compressed if space of the carpal tunnel gets reduced.

Causes

- Lunate dislocation.
- Mal-united Colle's fracture.
- Radiocarpal arthritis.
- Flexor tendon tenosynovitis.
- Myxoedema.
- Acromegaly.
- Pregnancy.

Clinical Features

- Common in females.
- Tingling, numbness, paraesthesia and burning sensation in the lateral three and half fingers supplied by median nerve. Burning sensation gets aggravated at night.
- Ape thumb deformity, wasting of thenar muscles, weakness of opponens pollicis and abductor pollicis brevis, i.e. features of low median nerve palsy.
- When BP cuff is inflated patient feels the typical pain in the fingers.

In lesions of S_1 there is no dropped big toe.—Gosta Norlen

- Tapping the median nerve at the distal end of forearm with the wrist held in extension aggravates the symptoms.
- Condition is often bilateral.

Phalen's Test (Wrist flexion test)

Flexion of the wrist causes exacerbation of the symptoms within 1 minute and the symptoms will disappear as the wrist is straightened.

Differential Diagnosis

- Cervical spondylosis.
- Cervical rib syndrome.

Diagnosis

Nerve conduction studies.

Treatment

- Surgical decompression of median nerve by cutting both superficial and deep part of flexor retinaculum completely, by 'S' shaped incision.
- Postoperatively **good physiotherapy** is required.
- Condition is permanently curable.

ULNAR NERVE INJURY

- After arising from the medial cord of the brachial plexus (C_8 and T_1), it runs on the medial aspect of the axillary artery up to middle of the arm. Then it enters the posterior compartment in relation to triceps muscle. After passing behind the medial epicondyle and through two heads of flexor carpi ulnaris, it runs in front of the flexor digitorum profundus (FDP) in the forearm. It reaches the hand in front of the flexor retinaculum through *"Guyon's canal"*. Here it divides into superficial and deep branches.
- Ulnar nerve supplies flexor carpi ulnaris, medial half of flexor digitorum profundus, all muscles of the hypothenar eminence (palmaris brevis, abductor digiti minimi, opponens digiti minimi, flexor digiti minimi), adductor pollicis of the thenar eminence and all interossei of the hand. It also gives sensory supply to medial part of the hand, medial one and half fingers.

Ulnar nerve is affected in:
- Supracondylar fracture
- Injury to the medial epicondyle
- Tardy ulnar palsy
- Leprosy
- Cubitus valgus deformity

Clinical Features

- *Claw hand* deformity.
- Weakness of all the muscles supplied by the ulnar nerve.
- *"Card test"*: A card is placed between the two fingers of the patient to grasp. As the palmar interossei are weak, patient can not grasp (palmar interossei are adductors of the fingers (*P*AD)).
- Abduction of fingers are checked (Dorsal interossei are abductors (*D*AB)).
- *Froment's sign*: A book is placed to grasp between fingers and thumb of the patient. Normally thumb will be straight because of the action of adductor pollicis muscle. As it is paralysed in ulnar palsy, grasp is achieved by the action of flexor pollicis longus and there will be flexed thumb.
- Loss of sensation over medial one and half fingers and hand.

Investigations

- Nerve conduction studies.
- Electromyogram.

Treatment

- Nerve suturing or nerve grafting.
- Tendon transfer.

Intrinsic minus deformity: It is due to loss of intrinsic muscle power, i.e claw hand.

Intrinsic plus deformity: It is due to muscle contracture and fibrosis.

Ulnar paradox: In ulnar palsy, higher the lesion, lesser the deformity, lower the lesion more the deformity. In higher lesion, FDP is also paralysed. In lower lesion FDP is intact and so FDP causes more flexion (overaction) and so aggravates the claw hand.

CLAW HAND

- It is the hyperextension of the metacarpophalangeal joint with flexion of the interphalangeal joints of the hand.
- Extension of MCP joint is due to unopposed action of extensor digitorum.
- Flexion of MCP joint and extension of interphalangeal joints are by extensor hood of interossei and lumbricals. So extensor hood is functioning mainly by ulnar nerve and also by median nerve. In ulnar or median nerve palsies, these actions are paralysed and so patient develops claw hand.
- It is actually *intrinsic minus deformity.*

Causes

- Leprosy
- Trauma
- Entrapment neuropathies
- Tardy ulnar palsy
- Klumpke's palsy

Clinical Features

- Typical claw hand.
- Loss of sensation along the distribution of the nerve.
- Inability to grasp card between the fingers.
- While holding the book between the thumb and fingers, thumb will be flexed in ulnar claw hand. (positive Froment's test).

Types

1. ***Ulnar claw hand***: Only medial two fingers are involved.
   a. *Low ulnar palsy*: Here lesion is in the wrist (at Guyon's canal). Here deformity is more because of the overaction of the FDP.
   b. *High ulnar palsy*: Here FDP is also paralysed and overaction is not there. So lesser deformity occurs.

   Ulnar paradox: Higher the lesion lesser the deformity, lower the lesion more the deformity.
2. ***Median claw hand***: Only lateral two fingers are involved. It is less common.
3. ***Combined median and ulnar claw hand***: Here all four fingers of the hand are involved.

Investigations

- Electromyogram.
- Nerve conduction studies.

Treatment

- ***Paul Brand's operation***: Extensor carpi radialis longus or brevis (ERCB) is transferred with a graft to the extensor hood through the lumbrical canal. Graft is taken from palmaris longus or plantaris muscle.
- ***Stye-Bunnell's operation***: Flexor digitorum superficialis of index finger is used (only in ulnar claw hand) to transfer to extensor hood.
- *Fowler's operation*: Extensor digitorum is used to transfer to extensor hood.
- *Riordan operation*: Flexor carpi radialis is used for tendon transfer.
- *Anterior transpositioning* of the ulnar nerve in case of tardy ulnar palsy.

RADIAL NERVE INJURY

- Radial nerve is derived from the posterior cord of the brachial plexus ($C_{5, 6, 7, 8}$ and T_1). It descends behind the axillary artery in front of the subscapularis, latissimus dorsi and teres major. It passes through the medial and lateral heads of the triceps muscle, winds round the humerus through the radial groove and enters the forearm in front of the lateral epicondyle in relation to brachioradialis, brachialis and extensor carpi radialis longus muscles.
- In the arm it supplies triceps, anconeus, brachioradialis, extensor carpi radialis longus and part of brachialis. It gives posterior and lower lateral cutaneous nerves of the arm and posterior cutaneous nerve of the forearm.
- *Superficial branch* of the radial nerve from the elbow runs in the forearm in relation to supinator and brachioradialis and ends by forming five digital nerves which gives sensory supply to lateral three and half fingers on the dorsal aspect.
- *Deep branch* also called as posterior interosseous nerve winds round the radius supplying supinator and extensor carpi radialis brevis. It gives three short branches to extensor digitorum, extensor digiti minimi and extensor carpi ulnaris. It also gives two long branches—one to abductor pollicis longus and extensor pollicis brevis and another to extensor digitorum, extensor carpi ulnaris and extensor digiti minimi.

Conditions where radial nerve is affected:

In the ***axilla***
  - *Crutch palsy*. It is neuropraxia
  - Fracture upper end of the humerus
  - Bony or soft tissue growth

In the ***radial groove***
  - Pressure on the arm from the edge of the operating table
  - *Saturday night palsy*—An individual with excessive alcohol consumption compresses his arm over the chair or by fall. It is neuropraxia
  - Prolonged tourniquet application—*tourniquet palsy*
  - Fracture of the shaft of the humerus
  - *Rarely* intramuscular injection of drugs can cause radial nerve palsy

In the ***elbow***
  - Dislocation or fracture neck of the radius

To know how to laugh whole heartedly, you have to know how to weep also.

Clinical Features

- *Wrist drop* because of inability of extending the wrist.
- Inability to extend metacarpo-phalangeal joint, but extensions of the interphalangeal joints are normal.
- Inability to extend the forearm.
- Inability to extend the thumb.
- Flexion of the elbow against resistance with forearm in mid-prone position is difficult because of the weakness of the brachioradialis muscle.
- Loss of sensation in back of the arm, forearm, hand and lateral three and half fingers.

Posterior interosseous nerve is purely motor and so sensation is intact when it gets injured. *It causes only dropped fingers.*

Investigations

- X-ray of the part.
- Nerve conduction studies.

Treatment

- Nerve suturing or nerve graft.
- Tendon transfer.

COMMON PERONEAL NERVE INJURY

This nerve supplies the extensor and peroneal group of muscles and sensory supply to the skin over the front and lateral aspect of the leg and dorsum of the foot.

Common peroneal nerve is affected in

- Fracture neck of the fibula
- Leprosy
- Lead poisoning
- Iatrogenic

Clinical Features

- Foot drop with high stepping gait.
- Talipes equinovarus deformity.
- Loss of sensation on the lateral side of the leg and dorsum of the foot.

Management

- Treating the foot drop.
- MCR chappals.

FOOT DROP

Inability to dorsiflex and evert the foot due to paralysis of the peroneal and extensor group of muscles, as a result of common peroneal nerve injury.

Causes

a. Fracture neck of the fibula
b. Leprosy
c. Lead poisoning
d. Iatrogenic
e. Direct incised wound

Clinical Features

- High stepping gait.
- Loss of sensation over lateral and dorsum of the foot.

Treatment

Tendon transfer using tibialis posterior muscle. Tendon of the muscle is detached from its navicular insertion and with a tendon graft (from plantaris) it is transferred to cuboid and cuneiform bones to get dorsiflexion and eversion.

1. Ober's procedure.
2. Barr's procedure.

MEDIAL POPLITEAL NERVE INJURY

It supplies the soleus, gastrocnemius, popliteus, plantaris, tibialis posterior, flexor digitorum longus and flexor hallucis longus.

Medial popliteal nerve is rarely involved by any disease process. Trauma can cause medial popliteal nerve palsy.

Clinical features

- Inability to plantar flex the foot
- Claw toes
- Sensory loss in the sole of the foot

AXILLARY NERVE INJURY

Axillary nerve supplies the deltoid and teres minor muscle and also sensory supply to the skin over the upper lateral aspect of the arm.

Axillary nerve is affected in

- Fracture neck of the humerus.
- Dislocation of humeral head.
- Following IM injection into the deltoid.

Clinically there will be loss of abduction of the shoulder and anaesthesia of the skin over the lateral part of the arm.

LONG THORACIC NERVE INJURY (NERVE OF BELL)

It supplies serratus anterior muscle. It arises from $C_{5,\,6,\,7}$ cervical roots.

The nerve is injured commonly in malignancy, during breast, axillary or chest wall surgeries.

Clinically, when outstretched (elbow extended) arm is pushed against the wall, the inferior angle of the scapula will become prominent (*Winging of the scapula*).

Self-assessment Questions

- Classification of peripheral nerve injuries.
- Tinel's sign.
- Brachial plexus injury.
- Median nerve injury.
- Ulnar nerve injury.
- Radial nerve injury.
- Carpal Tunnel syndrome.
- Claw hand.
- Wrist drop.
- Foot drop.

Open confession is good for the soul.

Neoplasm

Definition
Classifications
Anaplasia
Dysplasia
Carcinoma *in situ*
Aetiology
Paraneoplastic syndromes
Biopsy
FNAC
Immunohistochemistry
Tumour markers

DEFINITION

Willis defined neoplasm as *"it is an abnormal mass of tissue, the growth of which exceeds and is uncoordinated with that of the normal tissues and persists in the same excessive manner even after cessation of the stimuli."*

Neoplasia is

- **P**rogressive
- **P**urposeless
- **P**erverted
- **P**ersistent
- **P**ervasive
- **P**roliferative mass of tissue.

CLASSIFICATIONS

I

BENIGN	*MALIGNANT*
Well-differentiated	Lack of differentiation
Structures are typical of tissue/cell of origin	Atypical structure with anaplasia
Smooth, slow, progressive rate of growth	Erratic, rapid growth
Normal mitotic figures	Abnormal mitotic activity
Well localised and capsulated	Not localised. Not capsulated
Do not infiltrate surrounding normal tissues	Infiltrate the surrounding tissues
No metastasis	Metastasise through lymphatics or blood
Curable	May not be completely curable
Few benign tumours after a long time may turn into malignancy	
Treatment is simple	Treatment is complex and complicated
No recurrence	Recurrence can occur

II

SARCOMA	*CARCINOMA*
Arising from mesenchymal tissues	Arising from epithelial cells derived from any of the three germ layers
'*Sar*' means flesh (Greek), *Oma* means tumour	*Carc* means crab like
Smooth, firm or hard swelling	Hard, proliferative, with everted edge
Warm and vascular with dilated veins over the surface	
Spreads mainly through blood commonly to lungs, e.g. liposarcoma, fibrosarcoma, etc	Spreads through lymphatics as well as blood, e.g. squamous cell carcinoma, renal cell carcinoma, adenocarcinoma

III

- **Neoplasms which are only locally malignant**: No blood spread. No lymph node spread—Marjolin's ulcer, Rodent ulcer, Verrucous carcinoma, Adamantinoma.
- **Neoplasms which are loco-regionally malignant**: Spread only to regional lymph nodes is observed—Squamous cell carcinoma, Papillary carcinoma thyroid.
- **Neoplasms which are systemic** and spreads through blood and often also to lymph nodes. Melanoma, carcinoma breast.

Components

Parenchyma: It contains proliferating neoplastic cells.

Stroma: It contains supporting connective tissues and blood vessels.

Features of anaplasia

- Lack of cellular differentiation
- Pleomorphism-variation in size and shape
- Hyperchromatism-dark staining nuclei
- Anisocytosis
- Anisonucleosis
- Abnormal mitotic activity

Features of malignant tissues

- Altered differentiation, anaplasia
- Rapid rate of growth
- Local invasion - locally, lymphatic, vascular and perineural
- Metastasis
- Not capsulated
- Increased vascularity
- *Microscopic changes* – necrosis, numerous atypical mitotic activities, nuclear changes like pleomorphism/enlargement/hyperchromatism/clumping of chromatin/enlargement and multiplication of nucleoli

DYSPLASIA

It means "disorderd growth." There is loss in the uniformity of the cells with pleomorphism and hyperchromatism, as well as loss in their architectural orientation.

CARCINOMA *IN SITU*

Here dysplasia involves the entire thickness of the epithelium, and is preinvasive. Basement membrane is intact in carcinoma *in situ.*

AETIOLOGIC FACTORS

Age

It is more common in elderly. But it is variable.



Fig. 1.398: Squamous cell carcinoma scalp. Note the everted edge. It is ulceroproliferative lesion.



Fig. 1.399: Soft tissue sarcoma thigh.



Fig. 1.400: Melanoma lipoma. Note the extension.

The creation of a thousand forests is in one corn.—Ralph Waldo Emerson

Heredity

- Familial: Familial polyposis of colon
- MEN syndrome
- Neurofibromatosis
- von-Hippel-Lindau syndrome
- Familial breast and ovarian cancers

Genetic

- Xeroderma pigmentosa
- Ataxia telangiectasia
- Fanconi anaemia, Bloom syndrome

Acquired causes

- Chronic atrophic gastritis
- Solar keratosis
- Leukoplakia of oral cavity
- Ulcerative colitis

Chemical carcinogens

- Alkylating agents
- Hydrocarbons
- Smoking—lung, aerodigestive system, bladder cancer
- Asbestos—lung cancer
- Alcohol—liver cancer
- Amides, Azo dyes—bladder cancer
- Aflatoxin B_1
- Arecoline, collagenases and tannins (present in Betel nuts)
- Nitrosoamines, vinyl chloride, insecticides

Geographical variation

Japan—Carcinoma stomach
China, France—Carcinoma oesophagus
Hongkong—Nasopharyngeal carcinoma
Australia—Melanoma
India—Carcinoma oral cavity, gallbladder carcinoma
Newzealand—Small bowel tumours

Radiation Carcinogens

- UV rays, ionising radiation.

Microbial Carcinogens

- Human papilloma virus—Carcinoma cervix
- Epstein barr virus—Burkitt's lymphoma, nasopharyngeal carcinoma
- Hepatitis 'B' virus—Liver cancer
- Human T cell leukaemia virus Type I
- Helico bacter pylori can cause carcinoma of stomach and is associated with lymphomas (Mucosa Associated with Lymphoid Tissue (MALT))

Tumour suppressor gene p53 plays important role in prevention of the cancers. Its function is prevention of replication of damaged DNA. If damaged DNA replicates there is high chances of abnormal mitotic activity and cancer transformation of the tissue. *Loss or reduction of ability/function of p53 suppressor gene* can lead into cancers. Common cancers associated with p53 loss are cancers of breast, colo-rectum, retina, bone, brain, soft tissues, blood and familial related type.

SPREAD OF MALIGNANT TUMOURS

1. **Local spread**: Into adjacent structures like soft tissues, vessels, bone.
2. **Lymphatic spread**
   - ***By permeation***: Here malignant cells proliferate through lymphatic vessels up to lymph node level. For example, in carcinoma breast malignant cells permeate into axillary lymph nodes.
   - ***By embolisation:*** Here cells get dislodged from lymphatic vessels and freely travel to spread into further level of lymph nodes. In carcinoma breast by embolisation, spread occurs from axillary lymphnode to supraclavicular lymph node.
   - ***Retrograde lymphatic spread*** occurs once lymph vessel get blocked by malignant infiltration. In carcinoma breast retrograde spread occurs to opposite breast, opposite axilla, or to mediastinum. In melanoma, through dermal lymphatics and retrograde spread '***in transit nodules***' occur in the skin.
3. **Blood spread**

   Occurs through veins, as veins are thin-walled and infiltration is easier (Arteries contain elastic fibres in their wall, which resist malignant infiltration).

   Both by ***permeation*** (e.g. in renal cell carcinoma permeation through renal vein is common) and by ***embolisation*** (in other malignancies).

   Blood spread is commonly to lungs, bone (upper end of femur and humerus, ribs, skull), liver, brain, adrenals and other organs.

   In carcinoma prostate, due to increased pressure and venous blockade, retrograde venous spread occurs through vertebral venous plexus which causes **osteoblastic secondaries** in pelvic bones and vertebrae.
4. **Seedling:** For example
   1. From lower lip cancer to upper lip as **kiss cancer.**

Kiss cancer

- Lip
- Bladder
- Cervix
- Vocal cord
- Vulva

2. Recurrence in the scar after surgery for malignancy, e.g. deposition of malignancy in the scar of SPC from bladder tumour.
3. Seedling in the peritoneal cavity from abdominal malignancy is common causing intractable ascites.

5. **Transcoelomic spread:** Spillage or dislodge of malignant cells occurs from primary site resulting in seedling on other organ, e.g. In carcinoma stomach secondaries in ovary (***Krukenberg tumour***) occurs due to transcoelomic spread. Here cells get deposited on the raw surface of ovary during ovulation. (So it occurs in menstruating age group only.)



Fig. 1.401: Secondaries in neck. FNAC is the investigation to diagnose.



Fig. 1.402: Carcinoma ovary specimen. It was malignant teratomas of ovary. Other ovary was normal. So chemotherapy is used as an adjuvant. Patient was 23 year young female.



Fig. 1.403: Ethmoidal sinus tumour. Biopsy and CT scan is needed to confirm and assess the extent.

GRADING OF TUMOUR

It signifies aggressiveness of tumour.

It is based on differentiation of tumour cells and mitotic activity.

Broder's grading of squamous cell carcinoma: Based on keratin/epithelial pearls
Grade I: Well differentiated: >75% epithelial pearls
Grade II: Moderately differentiated: 50-75% epithelial pearls
Grade III: Poorly differentiated: 25-50% epithelial pearls
Grade IV: < 25% epithelial pearls

Special Features of Malignant Cells

- Independent and autonomous nature without any control or check
- Normal telomeric shortening is altered. Normal cell divides for 40-60 times. Later telomere gets shortened and cell division stops. It is altered in malignancy with infinite cell division.
- Reduced cellular apoptosis. Normal cell has capacity to die once its function is over. It is normal programmed death of a cell. It is activated by tumour suppressor gene p53. If this gene loses its function, tumour will form.
- Tumour has got capacity to create and construct blood supply called as *angiogenic* capacity.
- Malignant cells invade through the basement membrane and spread through blood and lymphatics.

A man carries success or his failure with him; it does not depend on outside conditions.

It is through secretion of special enzymes, increased interstitial pressure, capacity to have motility, release of collagenases/proteases/integrins.

- Spread occurs by proliferation and permeation as well as embolisation.
- Creation of instability and alteration of existing tissue function (not obeying normal tissue function of that particular site).
- *Gompertzian growth* – rapid growth of a tumour occurs prior to its clinically detectable stage. Once it becomes clinically detectable which needs thirty generation of cell divisions (1 mm tumour is 10^9 cells), its growth slows down later. This late slow growth is due to decreased oxygen to tumour/by competition between host cells and tumour cells and also between tumour cells themselves.
- Tumour mutation occurs at different generation of divisions stabilising the tumour further.

STAGING OF THE TUMOUR

It is based on the size of the primary tumour, nodal spread and blood spread.

It is called as 'TNM' staging.

'TNM' staging is more relevant than grading in managing and predicting prognosis.



Fig. 1.404: Carcinoma tongue is more common in lateral margin. Incision biopsy from the margin is done here.

PARANEOPLASTIC SYNDROMES

Certain symptom complexes which are not specifically explained by the tumour, but are relevant, often problematic and life-threatening are called as paraneoplastic syndromes.

Incidence: Seen in 10% of patients.

Paraneoplastic Syndromes

Syndrome	*Cause*	*Type of tumour*
Cushing's syndrome ACTH	or ACTH like substance	Small cell carcinoma lung Neural tumour Pancreatic tumour
Syndrome of inappropriate ADH secretion	ADH	Small cell carcinoma lung Brain tumour
Carcinoid syndrome	Serotonin, bradykinin	Bronchial adenoma Gastric and pancreatic carcinoma
Hypoglycaemia	Insulin Insulin like substance	Fibrosarcoma Hepatoma
Hypercalcaemia	PTH related peptide	Renal cell carcinoma Carcinoma breast, SCC lung Ovarian carcinoma, leukaemia
Polycythaemia	Erythropoietin	Renal cell carcinoma, hepatoma Cerebellar haemangioma
Myasthenia	Immunologic	Lung cancer
Acanthosis nigricans	Epidermal growth factor	Lung cancer, uterine cancer, gastric carcinoma
Dermatomyositis	Immunologic	Lung carcinoma, breast carcinoma
Clubbing and hypertrophic Osteoarthropathy of fingers		Ca lung
Migrating thrombophlebitis (Trousseau phenomenon)	Tumour product mucin It activates clotting	Ca pancreas, lung



Fig. 1.405: Typical malignant cachexia observed in GIT malignancies. It is totally malnourished incapacitated situation.



Figs 1.406A and B: Carcinoma cheek – advanced. It needs incision biopsy/orthopentomogram X-ray/CT of the part.



Fig. 1.407: Secondaries in skull – solitary.



Fig. 1.408: Carcinoma breast. Note the dilated veins on the surface. FNAC should be done to confirm the diagnosis.

INVESTIGATIONS FOR NEOPLASM

I. BIOPSY

Bio means life or tissue. *Opsis* means vision or microscopy.

Biopsy means study of tissues using microscopy.
OR *life by vision*
OR *vision for life* (to save life).

> *Keep your face to the sunshine and you cannot see the shadow.*—Helen Keller



Fig. 1.409: Soft tissue tumour of buttock. It could be sarcoma.



Fig. 1.410: CT picture of brain tumour—Astrocytoma.



Fig. 1.411: Contrast MRI of spinal column showing extradural schwannoma.



Fig. 1.412: CT scan picture of retroperitoneal leiomyosarcoma.



Fig. 1.413: Alopecia (hair loss) is common after chemotherapy for cancers.

Types of biopsies

- Incision biopsy
- Excision biopsy
- Trucut biopsy
- Pap smear
- FNAC
- Frozen section biopsy
- Punch biopsy
- U/S guided biopsy
- Laparoscopic biopsy
- CT guided biopsy
- Thoracoscopic biopsy

- Endoscopic biopsy (gastroscopic or colonoscopic or through ERCP or through cystoscopy).
- Proctoscopic biopsy.
- Open biopsy either laparotomy or thoracotomy or craniotomy using Dandy's brain cannula.

- Biopsy is sent in 10% formaldehyde solution. In special occasions like, to assess receptors/to do histochemistry, biopsy is sent in low temperature; in normal saline or in specialised ingredients. Tissues are kept in formalin for 24 hours and then taken for 'cut up' by pathologists. Sections are done after making tissue blocks using microtome upto 5 microns thickness. These sections are placed on a slide for staining with haematoxylin and eosin. This is studied under microscopy by pathologist to give the report. Detailed history, findings, markings of the specimen should be done by the surgeon prior to sending the specimen. Bone specimens are decalcified in hydrochloric acid for 7-21 days before sectioning and staining. So its report will be delayed usually.
- Inadequate sampling and improper reports may be due to – limited tissue sent; tissues are nonviable; too superficial biopsy done; cautery use on the tissues; crushing effect on the tissues (gentle meticulous biopsy is important without rough handling and without over use of cautery on the required tissues).
- Specimens are kept for 6 weeks. Blocks are kept for 30 years. Slides are kept for 10 years.
- Risk of false positivity in malignancy should be remembered. It is probably due to contamination, interchanged specimens, wrong interpretation, ulceration etc. Re biopsy/reinterpretation/repeat sectioning may be needed in such situations.
- Often additional methods like deeper sections; extra blocks; special stains are needed. Special stains are PAS (Periodic Acid Schiff) for glycogen, mucin and fungi; D (diastase) PAS for mucin; Perls Prussian blue for iron in haemochromatosis; reticulin for fibrous tissue; elastin stains for fibrosis; congo red for amyloid; Ziehl – Neelsen for mycobacteria; Grocott for fungi; Giemsa stain for protozoa; Warthin – Starry stain for spirochaetes.

Incision Biopsy

- It is taken from the edge of the lesion as in ulcer, not from the centre as there is necrosis.
- Incision biopsy is contraindicated in a case of melanoma where excision biopsy is preferred.
- In secondaries in lymph nodes, FNAC is preferred. If it fails to give information, incision biopsy is done.

(*Note:* Biopsy taken from the centre of the lesion is only in post-radiation ulcer and syphilitic gumma. Because of irradiation there is no blood supply in the margin and tumour proliferates in the center of the lesion).

Excision Biopsy

In small lesions excision biopsy is done, e.g. lymph node biopsy is done in case of lymphoma.

Trucut Biopsy

It is done using a specialised device wherein gun with Trucut tip is inserted into the surface tissue / organ and gun is fired to close the punching tip of the needle to catch and cut adequate tissue. It is done in prostate, breast and surface tumours. It can not be done to deeper tissues or tissues which are close to major vessels/ structures.

FNAC (Fine Needle Aspiration Cytology)



Fig. 1.414: Fine needle aspiration cytology (FNAC) of thyroid. It is also done in breast, lymph node and other swellings. It is not done for testicular tumour.

It is cytological study of tumour cells to find out the disease and also to confirm whether it is malignant or not.

The pathological fracture is a transverse one, and although it unites readily, refracture is not unusual.
—Max E Lake

Tumour Markers

Category 1
Hormonal:
Human chorionic gonadotrophin (HCG). — Trophoblastic tumour, nonseminomatous testicular tumour
Calcitonin — Medullary carcinoma of thyroid
Catecholamines and VMA. — Pheochromocytoma
Ectopic hormones — In tumours of paraneoplastic syndromes

Category 2
Isoenzymes:
Prostatic acid phosphatase — Carcinoma prostate
Neuron specific enolase — Small cell carcinoma lung, neuroblastoma

Category 3
Oncofetal antigens:
Alpha feto protein — Liver cancer, nonseminomatous germ cell tumour
Carcinoembryonic antigen (CEA) — Carcinoma colon (common). Carcinoma pancreas, lung, stomach and breast

Category 4
Mucin and other proteins:
CA –125 (Carbohydrate antigen) — Ovarian cancer
CA –15-3 — Breast cancer
CA—19-9 — Pancreatic and colon cancer

Procedure: It is done using ***23*** or ***24*** gauge needle fixed to specialised syringes which creates negative pressure for aspiration and contents are smeared on the slides. Dry slides as well as slides fixed with 100% methanol are used for study.

- It is done in parotid, thyroid, lymph node, breast and all other surface lesions.
- In follicular carcinoma of thyroid it is not very useful, as angioinvasion and capsular invasion which are specific can not be detected.
- In lymph nodes it is useful for detecting secondaries and tuberculosis.
- U/S guided or CT guided FNAC are popular at present - especially when it is done from liver, lungs, kidneys etc (from deeper structures/organs).

It is absolutely contraindicated in testicular tumour. Because tough tunica albugenia usually prevents tumour spread and once it get disrupted by FNAC, spread can occur.

Cytological study is done after Papanicolaou stain; Giemsa staining or Romanowsky staining.

Advantages

- Very sensitive.
- Done on OP basis.
- Least invasive, safer, fast and cheaper.
- Anaesthesia is not required.
- Tumour dissemination through the track is not present (except in testicular tumour where it is not done).
- Presently DNA study of the cell can detect very early malignancy.

Disadvantages

- Negative result can not rule out malignancy.
- Tissue study is not possible.
- Further studies not amenable.

Note: **FNNAC** – Fine Needle Non Aspirating Cytology is done in some tissues (in some centers). Here needle is passed into the tissue and material collected from the needle (without any aspiration) is studied for cytological analysis.

Frozen Section Biopsy

Frozen section is done whenever biopsy report is needed at the earliest. It is usually done in a pathology set up existing adjacent to the operation theatre. An unfixed fresh tissue is frozen (using CO_2) in a metal and sections are made and stained. It is technically difficult; processing and staining is of inferior quality and often it is difficult to give accurate results. But advantage is it is quick and surgeon can decide the further steps of procedure in same sitting like nodal clearance/type of resection to be done, etc.

- It is done in carcinoma breast or in follicular carcinoma of thyroid when FNAC fails.
- During surgery after resection of the tumour to look for (on table) the clearance in the margin and depth and also to study the lymph nodes for their positivity.

II. IMMUNOHISTOCHEMISTRY

It is detection of specific antigen using an antibody. Antibody labelled with a dye, binds to antigen in a section of tissue causing specific colours like brown, and determines its presence and distribution in the tissues. It is safe, specific and quick.

It is used in

1. *Neoplasia*
    - To confirm, to find differentiation, to detect metastases; to plan type of therapy.
    - To categorise leukaemias or lymphomas; either of 'T' cell or of 'B' cell type.
    - To find out site of origin of metastatic tumours - E.g. by doing prostate specific antigen in prostate cancer or doing thyroglobulin in thyroid carcinomas or clear cells in the lung in metastatic renal cell carcinoma.
    - Detection of receptors or molecules - E.g. estrogen receptors [ER] in breast cancer. ER positive has got better prognosis. Presence of onco-protein product c—erbB2 in breast cancer signifies poor prognosis.
    - Gastrointestinal stromal tumour (GIST) can be treated with imatinib if it shows CD 117 expression.
    - Endocrine tumours are assessed on ki67 proliferative index.
2. *Infections*
    - Detection of specific antibodies to the antigens of certain specific infective agents like Epstein Barr virus, Cytomegalo virus, human herpes virus 8, herpes simplex virus etc.
3. *To identify abnormal accumulation* of various proteins like ά – 1 – antitrypsin; deposition of amyloid.
4. *Assessment of immunoglobulins.*
5. *Screening for mutations.*

III. TUMOUR MARKERS (See Page no. 240 – table)

- Tumour markers are biochemical indicators of presence of a tumour. They are not used for primary patho-logical diagnosis.
- They are of prognostic value.
- Presence of tumour marker signifies recurrence or residual tumour.

IV. OTHER METHODS

Electron Microscopy

- It is visualisation of tissue in very high magnification of 1000 × 500 000 in difficult deciding cases. But it is time consuming and expensive.

In Situ Hybridisation

- It is determination of presence or absence of a specific gene and its location in a fresh/fixed tissue sections using an oligonucleotide probe, targeting at specific DNA or RNA sequence.

Polymerase Chain Reaction (PCR)

DNA is amplified using this special method and detected by technique like electrophoresis. PCR can be done on blood or nontissue samples. It is highly sensitive, fast and safe. Disadvantages are – expensive and risk of DNA contamination.

Uses of PCR are –

- Detection of mutations in congenital conditions like von – Hippel – Lindau disease (vHL gene); haemochromatosis (HFE gene); colorectal carcinoma (APC gene).
- Gene rearrangements in different conditions like lymphoma or other diseases can be detected by PCR (clonality).
- Assessment of loss of heterozygosity in tumours like oligodendroglioma (1p, 16q).
- PCR study for infections like tuberculosis.

Fluorescence *in situ* Hybridisation (FISH)

- It is a type of cytogenetics (study of chromosomes) that can be done in fixed or fresh tissues; used in haematological malignancies or trisomy 23. It is safe and quick.

MANAGEMENT STRATEGY FOR CANCERS

- Diagnosis is confirmed by biopsy from primary usually.
- Evaluations for staging – metastatic work up.
- Approaches for primary – surgery/radiotherapy/chemotherapy.
- Approaches for secondary.
- Palliation in advanced stage – palliation of distressing symptoms.

To different minds, the same world is a hell, and a heaven.

Treatment of tumours

- Surgery-wide excision/radical
- Radiotherapy-curative/palliative
- Chemotherapy
- Immunotherapy
- Gene therapy.

Malignancies which are curable:

- Basal cell carcinoma.
- Adamantinoma.
- Verrucous carcinoma.
- Marjolin's ulcer.
- Papillary carcinoma of thyroid.
- Carcinoma colon.

Sarcomas which spread to lymph nodes.

- Synovial sarcoma.
- Ewing's sarcoma.
- Lymphosarcoma.
- Kasposi's sarcoma.
- Rhabdomyosarcoma.
- Angiosarcoma.

Self-assessment Questions

- Biopsy.
- FNAC.
- Spread of malignant tumours.
- Tumour markers.
- Sarcomas.
- Dysplasia.
- Carcinogens.

Skin Tumours

Anatomy
Classification of skin tumours
Skin adnexal tumours
Dermatofibroma
Dermatofibrosarcoma
Keratoacanthoma
Rhinophyma
Seborrhoeic keratosis
Premalignant conditions of skin
Squamous cell carcinoma
Marjolin's ulcer
Basal cell carcinoma
Turban tumour
Naevi
Melanoma

ANATOMY

Epidermis: Layers

- Stratum corneum—1/3 of epidermis
- Stratum granulosum—1-3 layers of cells
- Stratum spinosum—3-5 layers of cells
- Stratum basale—columnar cells
- Stratum lucidum is seen in palms and sole.

Melanocytes—one melanocyte is seen for every 10 basal cells

Langerhan's cell—a clear cell in stratum spinosum.

Basement membrane is seen at dermo-epidermoid junction.

Epidermis is avascular.



Fig. 1.415: Skin anatomy

Epidermis is 5% of the total skin. It is thickest (0.5 – 1 mm) in palm, sole, back and buttocks. It is thinnest in eyelids (0.05 – 0.09 mm).

Dermis—contains collagen fibres, elastic fibres, capillaries, venules, arterioles, lymphatics, nerves, erector pilorum muscle, sweat glands (eccrine, apocrine), sebaceous glands. Merkel cells, Meissner and Pacinian corpuscles are receptors in dermis. Dermis constitutes 95% of the skin. Dermis is 15-40 times thicker than epidermis.



Fig. 1.416: Extensive infective destruction of the eyelids, face exposing bone and deeper structures. Maggots are seen on the surface. It mimics carcinoma but it was of infective origin. Phagedena is infective destruction without proliferation. It often mimics malignancy.

CLASSIFICATION OF SKIN TUMOURS

Benign

Epidermal.

- Seborrhoeic keratosis.
- Trichilemmal tumour.
- Sebaceous adenoma.
- Sebaceous epithelioma.
- Hydrocystoma, syringoma, spiradenoma.

Dermal tumour.

- Neurofibroma.
- Dermatofibroma.

Probability is the rule of life, especially under the skin. Never make a positive diagnosis.—William Osler

Malignant

- Squamous cell carcinoma.
- Basal cell carcinoma.
- Melanoma.
- Malignant skin adnexal tumour.
- Secondaries in the skin. Sister-Joseph nodules around umbilicus.

CLASSIFICATION OF SKIN TUMOURS

Epidermal

Benign—Papilloma, seborrhoeic keratosis
Malignant – BCC, SCC

Melanocytic

Benign – All types of naevi
Malignant melanoma

Skin adnexal tumour

Benign-Syringoma, hidradenoma, sebaceous adenoma, trichofolliculoma, trichilemmoma
Malignant- Hidradeno carcinoma, sebaceous carcinoma

Dermal tumours

Neurofibroma, dermatofibroma, dermatofibrosarcoma protuberans

Note

- Multiple sebaceous adenomas with visceral malignancy are called as *Torre-Muir syndrome*.
- Secondaries in skin can occur like ***sister –Joseph nodules*** around the umbilicus.

SKIN ADNEXAL TUMOURS

Features

- They are tumours arising from accessory skin structures like sebaceous glands, sweat glands, hair follicles.
- It is not uncommon. It may be **benign** or **malignant**.
- It presents as protruding well-localised swelling in the skin.
- Malignant skin adnexal tumour forms a nodular, hard, indurated swelling in the skin, often with involvement of regional **lymph nodes** which are hard and nodular.
- It mimics **squamous cell carcinoma of skin.**

Classification

- *Eccrine gland tumours*—syringoma, hidradenoma, syringo cystadinoma
- *Hair tumours*—Trichoepithelioma, tricholemmoma



Fig. 1.417: Skin adnexal tumour in the face.



Fig. 1.418: Skin adnexal tumour turned out to be hair follicle tumour.

Differential Diagnosis

- Squamous cell carcinoma of skin
- Dermatofibrosarcoma protuberans

Diagnosis

- Biopsy
- FNAC of lymph node



Fig. 1.419: Benign skin adnexal tumour.



Fig. 1.420: Skin adnexal tumour. Vascularity is increased and it is malignant.

Treatment

- Benign tumour—excision.
- For malignant tumour—wide excision and regional lymph node block dissection when required.

Prognosis is good. It is better than squamous cell carcinoma.

Note:

- **Merkel cell carcinoma** is aggressive malignant condition arising from neuroendocrine receptor cells of the skin (dermis) which mimics histologically oat cell carcinoma. It is common in white elderly females (4 : 1) may be due to UV rays. Treatment is wide excision with radiotherapy.
- **Adenocarcinoma arising from the apocrine glands** of skin is called as extramammary Paget's disease of skin (intraepidermal adenocarcinoma) commonly observed in perianal region.

DERMATOFIBROMA (Sclerosing angioma or Subepithelial benign nodular fibrosis)

- It is a benign tumour arising from skin from dermal dendritic cells.
- It is formation of firm, single or multiple nodules occurring commonly in extremities (limbs).
- It can be red, brownish yellow (due to lipid), or bluish black (due to haemosiderin).

  Histologically, spindle cells are arranged in 'mat like' or 'cart-wheel' pattern.
- It is also called as ***dermal histiocytoma.***

Differential Diagnosis

- Squamous cell carcinoma of skin.
- Melanoma.
- Basal cell carcinoma.
- Skin adnexal tumour.

Treatment

- Excision.

DERMATOFIBROSARCOMA PROTUBERANS

- It is a low grade fibrosarcoma which grows slowly but persistently.
- Occurs in head and neck, limbs, abdominal wall and back–Trunk is commonest site (50%).
- It is not a rare entity, often attains a large size with multiple, nodular, hard, swelling with often involvement of lymph nodes. Malignant spindle cells are seen histologically.
- Rarely it spreads into lungs through blood.
- It mimics squamous cell carcinoma of skin and skin adnexal tumour.
- Positive for CD34 and ring chromosome.
- With melanin pigmentation it is called as *Bednar's tumour*.

Diagnosis

- Biopsy of the lesion.

It's when the fish opens his mouth that he gets caught.



Fig. 1.421: Dermatofibrosarcoma

- Chest X-ray.
- FNAC of the lymph node.

Treatment

- Wide excision and follow up.
- Recurrence is common - 50%.
- Prognosis is good.



Fig. 1.422: Malignant skin tumour with ulceration of the skin over chest wall. Axillary nodes were enlarged in this patient.

KERATOACANTHOMA (MOLLUSCUM SEBACEUM)

- It is an overgrowth and subsequent spontaneous regression of **hair follicle** seen commonly in adults.
- Cause is unknown. It may be self limiting, benign neoplasm of viral origin (papilloma virus).
- It presents as a rapidly growing, painless, single swelling in the skin with central brown area.



Fig. 1.423: Dermatofibrosarcoma protuberans.

- It grows usually for 4 weeks and later shows spontaneous regression in 4 months. It is a pseudo-malignancy.
- During regression phase, central area separates from the lesion leaving a deeply seated scar.



Figs 1.424A and B: Typical keratoacanthoma with central brownish area. It is self-limiting disease. It never turns into malignancy but looks like SCC.

Clinical Features

- Mobile, hard painless, nontender, lump with a central brownish area.
- Lymph nodes are not enlarged.
- *It is totally benign.*

Differential Diagnosis

- Squamous cell carcinoma.

Treatment

- Excision. The tissue is sent for histopathological study.

RHINOPHYMA (Potato Nose) (Bottle Nose)

- It is a **glandular form of acne rosacea** causing immense thickening of **distal part of skin of nose** with visible openings of sebaceous follicles. Nose is bluish red in colour with dilated capillaries.
- It is due to hypertrophy and adenomatous changes in sebaceous glands.

Treatment

- Excision of excess tissue and reconstruction.



Figs 1.425A and B: Rhinophyma. Typical look and site.

SEBORRHOEIC KERATOSIS (Seborrhoeic wart, basal cell papilloma)

It is a benign overgrowth of the basal layer of epidermis with excess of small darkly stained basal cells, which protrudes from the surface of the epidermis to give oily appearance.

Features

- It is common in elderly. Common sites are the back, face, neck.
- It grows slowly with widening in area without altering in thickness.
- It often gets infected but uncommon to bleed on touch.
- It is pigmented due to melanin and so mimics naevus or melanoma.



Figs 1.426A to C: Seborrhoeic keratosis in face, ear and in periumbilical region. It is not a premalignant condition.

Never surrender your dream to noisy negatives.

- Often when it falls off, it leaves a pale pink patch on the skin with visible small surface capillaries.
- It is not a premalignant condition. (Note: Solar keratosis is a premalignant condition).
- It is hard and stiffer than normal skin.
- Lymph nodes are not involved.
- It does not occur in palms and soles.
- It can be picked off from the skin.
- *'Stuck on' appearance is characteristic.*

Differential Diagnosis

- Melanoma
- Pigmented BCC
- Naevus.

Treatment

- Excision cures the condition.
- Shave excision or curettage can be done.

PREMALIGNANT CONDITIONS OF THE SKIN

- *Bowen's disease* of skin: It is an intradermal precancerous condition. It presents as brownish induration with a well-defined edge. Microscopically it contains large clear cells. Eventually, it will turn into carcinoma (10%). Entire epidermis is disorganised and irregular. It shows parakeratosis, acanthosis, hyperkeratosis. Chronic solar exposure; arsenic; human papilloma virus 16 are the aetiologies. Topical 5 fluorouracil or imiquimod; 4 mm margin surgical excision; MOHS; laser are the therapeutic options.

  Erythroplasia of Queyrat is Bowen's disease occurring over glans penis.
- *Paget's disease* of nipple
- Leukoderma
- *Senile* or *solar keratosis:* It is multiple, dry, hard, scaly, lesions on the face and back of hands due to exposure to sunlight, occurs after middle age. Squamous cell carcinoma occurs later
- *Radiodermatitis,* Arsenic dermatitis
- *Chronic scars* develop into Marjolin's ulcer
- Albinism
- *Xeroderma pigmentosa* wherein there is defective DNA excision repair mechanism. It turns into malignant melanoma, BCC, SCC
- *Chronic lupus vulgaris*
- *Prolonged irritation of skin* by various chemicals like dyes, tar, soot

SQUAMOUS CELL CARCINOMA (Epithelioma) (Khangri cancer) (Chimney cancer)

- It occurs in premalignant conditions like Bowen's disease, Paget's disease, leukoplakia, chronic scars, chemically induced chronic irritation, radiodermatitis, senile keratosis, e.g. Khangri cancer in Kashmir, Chimney scrotal cancer, Kang cancer of Tibetans.
- It arises from squamous layer of the skin. Usually it occurs in a pre-existing predisposing lesion; occasionally can develop in denovo skin.
- It can be grossly proliferative/ulcerative/red plaque like.
- It expresses cytokeratins one and ten.
- It is the 2nd most common skin cancer. It is common in males.



Fig. 1.427: Squamous cell carcinoma eyelid. Note the involvement.



Fig. 1.428: Squamous cell carcinoma on the labial surface of vagina.

Aetiology of SCC

- Bowen's disease
- Chronic scars and sinuses (burns; osteomyelitis; venous ulcer)
- Lupus vulgaris
- Solar keratosis - 20% chances of SCC
- Senile keratosis
- Xeroderma pigmentosa
- Tobacco use
- Viral cause – human papilloma virus (HPV) five and sixteen
- Chemically induced chronic irritation
- Radiodermatitis
- ***Kangri cancer***- It is due to constant placing of the hot charcoal pot (kangri) over the abdominal wall to control cold. Seen in Kashmir
- ***Kang cancer*** is seen in buttocks and heel of Tibetans due to sleeping over oven bed to control cold
- ***Chimney sweep cancer*** is observed in scrotum due to constant irritation by tar
- *SCC is more common in immunosuppressed individuals*

Clinical Features

- An ulcerative or ulceroproliferative lesion.
- **Raised** and **everted edge**.





Figs 1.429A and B: Squamous cell carcinoma in the forearm and foot. It is proliferative cauliflower like lesion.

- **Indurated** base and edge.
- Bloody discharge from the lesion.
- Regional lymph nodes are commonly involved, which are hard, nodular, initially mobile but eventually fixed to underlying structures.
- Usually blood spread does not occur.

Variants

- *Marjolin's ulcer* which occurs in chronic scar is a type of squamous cell carcinoma without lymph node spread.
- *Verrucous carcinoma* is a squamous cell carcinoma, commonly occurring in mucus membrane or mucocutaneous junction without lymph node spread. It is dry, exophytic, warty, indurated growth. It has good prognosis. It is a curable malignancy.

Histology

- Malignant whorls of squamous cells with epithelial or **keratin pearls** are characteristic feature.
- Spindle cells, invasion, deep and peripheral margin clearance.

Broder's classification

I: Well differentiated: 75% or more keratin pearls
II: Moderately differentiated: 50-75% keratin pearls
III: Poorly differentiated: 25-50% keratin pearls
IV: < 25% keratin pearls

Differential Diagnosis

- BCC.
- Melanoma.
- Keratoacanthoma.
- Skin adnexal tumours.
- Actinic keratosis.
- Pyoderma gangrenosum.

Investigations

- Edge biopsy.
- FNAC from lymph node.

Treatment

- **Radiotherapy** using radiation needles, moulds etc. is given.
- **Wide excision**, 2 cm clearance followed by skin grafting or flaps.

Finding fault is easier. Finding remedy is the one which is more difficult.

TNM staging for skin cancer other than melanoma

Tumour	*Node*	*Metastasis*
T 0 no tumour found	N 0–No nodes	M 0–No distant spread
T is Tumour *in situ*	N 1–Regional nodes ++	M 1–Distant spread ++
T 1 Tumour < 2 cm		
T 2 Tumour 2-5 cm	G1 – Low grade	
T 3 Tumour > 5 cm	G2 – Moderate grade	
T 4 Spread to cartilage, muscle or bone.	G3 – High grade	



Fig. 1.430: Squamous cell carcinoma foot – ulceroproliferative lesion with fungating inguinal node secondaries. It is an advanced disease. Opposite inguinal nodes are also significantly enlarged.

(Presently for tumour less than 2 cm, 4 mm clearance and for tumour more than 2 cm, 1 cm clearance is sufficient).

- **Amputation** with one joint above.
- For lymph nodes, block dissection of the regional lymph nodes is done.



Fig. 1.431: Squamous cell carcinoma and BCC in face of a patient.

- In advanced cases with fixed lymph nodes, **palliative external radiotherapy** is given to palliate pain, fungation and bleeding.
- **Chemotherapy** is given using methotrexate, vincristine, bleomycin.
- Field therapy using cryo probe or topical fluorouracil or electrodessication.

Prognostic factors in SCC

- Tumour size > 2 cm is worse
- Tumour border—Ill-defined border is worse
- Associated immunosuppression is worse
- Differentiation—Poorly differentiated is worse
- Perineural involvement has worse prognosis
- Invasion; depth < 2 mm has got better prognosis; depth more than 16 mm has got worst prognosis
- Local recurrence rate is 20%. Recurrence period is 5 years, not beyond

Verrucous Carcinoma

- Dry, exophytic, warty growth.
- No lymph node spread.
- No blood spread.
- Surgery is the treatment—wide excision.
- No radiotherapy.
- Examples:
  - Giant condyloma acuminatum (Buschke-Lowenstein tumour, Verrucous carcinoma of genitalia). (Fig. 1.432)
  - Oral florid verrucous carcinoma.
  - Verrucous carcinoma of feet—***carcinoma cuniculatum.***

MARJOLIN'S ULCER

- It is a well-differentiated squamous cell carcinoma which occurs in chronic scars like burn scar, scar of venous ulcer.



Fig 1.432: Verrucous carcinoma of penis. It is an exophytic, dry, warty, locally malignant lesion (Squamous cell carcinoma).

- As it develops in a scar due to chronic irritation and there are **no lymphatics** in scar tissue, **it will not spread to lymph nodes**.
- As scar is relatively avascular it grows slowly. As scar does not contain nerves, it is painless.
- Once it reaches the normal skin it may behave like any other squamous cell carcinoma, i.e. it will spread to lymph nodes. It occurs in *unstable scar of long duration*.





Figs 1.433A and B: Marjolin's ulcer foot in a pre-existing chronic venous ulcer and burns scar. It is a well-differentiated squamous cell carcinoma occuring in an unstable scar of long duration.



Figs 1.434A and B: Marjolin ulcers over elbow and over foot. First one occurred over elbow in a pre-existing snakebite scar. Second one occurred in a long-standing venous ulcer.

Clinical Features

- History of pre-existing venous ulcer or burn scar.
- Indurated, painless, nontender, ulcer with raised and everted edge.
- Biopsy from the edge **confirms the diagnosis.**

Moles must never be cauterised or curetted.

Treatment

- **Wide excision**.
- In case of large ulcer, **amputation** is required.
- ***Radiotherapy should not be given*** as it may turn into poorly differentiated squamous cell carcinoma.
  It is a curable malignancy.

BASAL CELL CARCINOMA (Rodent ulcer)

It is a low grade, locally invasive, carcinoma arising from basal layer of skin (or adnexal basal layer of hair follicle) or muco-cutaneous junction. ***It does not arise from mucosa.***

- It is the commonest malignant skin tumour.



Fig. 1.435: Basal cell carcinoma

- It is more common in white-skinned people than blacks.
- Common in places where exposure to UV light is more (***Australia).***
- It is common in males, common in middle-aged and *elderly*.
- Common site is ***face***—above the line drawn between angle of mouth and ear lobule (90%).
- It is called as ***tear cancer*** because it is commonly seen in area where tears roll down.
- Often it can occur in muco-cutaneous junctions.
- *Basal cell naevus syndrome* (Gorlin) with BCC; medulloblastoma; bifid ribs.
- ***It is only locally malignant***. It does not spread through lymphatics nor through the blood. But it erodes deeply into local tissues including cartilages, bones causing extensive local destruction. Hence the name ***"rodent ulcer".***

Types

1. Nodular.
2. Cystic/nodulocystic.



Fig 1.436: Rodent ulcer lateral aspect of the eyebrow. Note the typical beaded edge.



Fig 1.437: BCC in perianal region. It is nodular type. Wide excision is required.



Figs 1.438A and B: BCC in different places–below the ear and in the inner angle of the eye.



Fig 1.439: Note the common site of BCC—in the face above the line drawn between angle of mouth and ear lobule.



Figs 1.440A and B: Nodular BCC in the nose.



Fig. 1.441: Sebaceous epidermal naevus. It is common in females, often extensive, begins in childhood. It needs surgical excision and skin grafting. It has got 10% chances of turning into BCC.

3. Ulcerative.
4. Multiple, often associated with syndromes and other malignancies.
5. Pigmented BCC—mimics melanoma.
6. Geographical or field fire or forest fire BCC is wide area involvement with central scabbing and peripheral active proliferating edge.
7. **Basisquamous**—behaves like squamous cell carcinoma which spread into lymph nodes. BCC which has not been treated for long time can turn into Basisquamous carcinoma.

   Note: *Nodulocystic* and noduloulcerative is the commonest form (70-90%).

Clinicopathological types

1. *Superficial type*—Small buds of tumour masses.
2. *Morpheic type*—Dense stroma with basal cells.
3. *Fibro-epithelioma type* of PINKUS shows elongated cords of basaloid cells with mesh work.

It contains outer palisading columnar cells with central polyhedral cells but no *prickle cells* or *keratinisation*.



Figs 1.442A to C: Basal cell carcinoma in different locations. Note the nodularity and ulceration. Note the beaded edge.

Clinical Features

- Ulcer on the face in a middle-aged man which is nontender, dry, slowly growing, nonmobile, with raised and beaded edge with central scab.
- Site of beading signifies the area of active proliferating cells. In between beaded areas dormant nonactive cells are present.
- No lymph node or blood spread occurs.

Adversity reveals genius, prosperity conceals it.

High risk BCC
- Size > 2 cm
- Near the eye/nose/ear
- Ill-defined margins
- Recurrent tumours
- Immunosuppressed individuals

Differential Diagnosis

1. Squamous cell carcinoma.
2. Melanoma.
3. Keratoacanthoma.
4. Seborrhoeic keratosis.

Investigations

Edge biopsy, X-ray of the part, CT scan.

Treatment

- It is ***radiosensitive***. If lesion is away from vital structure (like away from eyes), then curative radiotherapy can be given. **Radiotherapy is not given, once it erodes cartilage or bone.**
- *Surgery:* Wide excision (2 cm clearance) with skin grafting or flap is the procedure of choice.
    - Laser surgery.
    - Cryosurgery.
    - **MOHS** (*Microscopically Oriented Histographic Surgery*) is useful to get a clearance margin and in conditions like BCC close to eyes, nose or ear, to preserve more tissues. MOHS is becoming popular in BCC/dermatofibrosarcoma protuberans/melanoma. Procedure is done by dermatological surgeon along with a histotechnician/histologist. Under local anaesthesia, a saucerised excision of the primary tumour is done and quadrants of the specimen are mapped with different colours. Specimen is sectioned by histotechnician from margin and depth, and it is stained using eosin and haematoxylin. It is studied by MOHS surgeon or histologist. Residual tumour from relevant mapped area is excised and procedure is repeated until clear margin and clear depth are achieved. Clearance must be complete and proper in BCC otherwise there will be very high chance of recurrence (70%).

Indications for surgery:
- Rodent ulcer eroding into cartilage or bone
- BCC close to the eye
- Recurrent BCC

TURBAN TUMOUR

- It is also called as *cylindroma* of scalp.
- Locally malignant, rare tumour of the skin of the scalp.
- Grows over the span of years to involve the entire scalp.
- Skin shows reddish, lobulated lesions with deep crevices.

Differential Diagnosis

- Multiple sabeceous cyst.
- Multiple neurofibroma.
- Multiple skin adnexal tumours.

Management

- Biopsy.
- Wide excision and grafting.

NAEVI

- It is a *hamartomata* of melanocytes due to excessive stimulation.
- It may present during birth or appear later in life.



Fig. 1.443: Different types of naevi.

Types

1. ***Hairy mole*** is a mole with a hair growing on its surface.

2. ***Nonhairy mole.***
3. ***Blue naevus.*** It is seen in children. It is located deep in the dermis, hence appears blue. It is common in buttock (Mongolian spot), hand, feet.
4. ***Junctional naevus.*** It lies centred in the junctional layer (basal layer) of the epidermis as clusters. It is immature, unstable and premalignant. Microscopically there is proliferation of melanocytes at the epidermal junction. Features of malignant transformation are—change in the size, colour, bleeding, ulceration, crusting, satellite spots.
5. ***Compound naevus.*** It is combination of intradermal and junctional naevus. Intradermal part is inactive but junctional part is potentially malignant.
6. ***Juvenile melanoma (Spitz naevus)*** (It is a misnomer). It appears as junctional like mole before puberty. It is seen in children on face.
7. ***Hutchinson's freckle.*** It is seen in elderly with large area of dark pigmentation. In the macular stage it is smooth and brown. In the tumour stage it is dark and irregular. It can turn into melanoma commonly.
8. *Halo naevus* – Halo of depigmentation around the pigmented naevus.
9. *Intradermal naevus* – Cluster of dermal melanocytes is seen without junctional component. Common in face.
10. *Spindle cell naevus* – It is dense, black pigmented lesion containing spindle cells and atypical melanocytes at dermo epidermal junction; seen in females with high malignant potential.
11. *Naevus spilus* – It is hyperpigmented speckles throughout, also called as *speckled lentiginous naevus*. Malignant potential is rare.
12. *Naevus of Ota* is dermal melanocytic hamartoma seen in distribution area of trigeminal nerve (ophthalmic /maxillary). It is seen in oriental and African race adolescent females with a hormonal influence.
13. *Naevus of Ito* is similar lesion occurring in shoulder region.



Fig. 1.444: Hairy naevus.



Fig. 1.445: Congenital naevus.



Fig. 1.446: Compound naevus.



Fig. 1.447: Junctional naevus.

An investment in knowledge always the best interest.

Treatment

Excision. Always should be sent for histopathology.

***Note*:** Naevus more than 1% of body surface area or more than 20 cm is called as **giant naevus.**

MELANOMA

- Melanoblast—Primitive cell derived from the neural crest.
- Melanocyte—The cell which synthesises melanin is located in the basal layer (melanocyte : basal cell : : 1 : 10).
- Melanophores are pigment melanin carriers through dendrites into the epidermis.
- Melanophages are macrophages having melanin pigment.
- Melanoblasts and melanocytes contain DOPA oxidase enzyme and synthesise melanin. They show +ve DOPA reaction.
- Melanophores and melanophages show –ve DOPA reaction.

DOPA reaction:

$$\text{Tyrosine} \xrightarrow[\text{Tyrosinase}]{} \text{DOPA} \xrightarrow[\text{Oxidase}]{} \text{Melanin}$$

- Melanin synthesis is controlled by melanocyte stimulating hormone, ACTH and sex hormones.

Melanoma is a malignant tumour arising from the epidermal melanocytes.



Fig. 1.448: Xeroderma pigmentosa with BCC in the nose. Such patients are prone for other skin malignancy like melanoma also. There is defective DNA excision repair.

Its incidence is equal in both sexes. Its incidence is increasing over the years.

It is most aggressive malignant cutaneous tumour.

Sites

Sites of melanoma

- Head and neck – 25%
- Trunk – 25%
- Lower limb – 25%
- Upper limb – 11%
- Other sites – 14%

- In females, *leg* is the commonest site.
- In males, the *front* or *back* of the trunk.
- In the Bantu tribe, *sole* is the commonest site.



Fig. 1.449: Clark's level

Other sites: Eyes (iris, ciliary body, choroids), mucocutaneous junction (anorectal region, genitalia), head and neck (meninges, oropharynx, nasopharynx, paranasal sinuses).

- It is most common in Queensland, Australia.

Risk Factors

- Exposure to sunlight (exposure to UV light; more common in white-skinned).
- Ethnic factors, socioeconomic status (high society), lifestyle, climate.
- Albinism.
- Xeroderma pigmentosa. RR is 1000.
- Junctional naevus.
- Familial dysplastic naevus syndrome.
- Sporadic dysplastic naevi. 10% risk.
- Large congenital naevi (larger than 20 cm).
- Family history of melanoma (10% through chromosomes 1p, 6q, 7 and 9).
- History of earlier skin cancers other than melanoma.
- Patients who are on immunosuppressive drugs or after renal transplantation or NHL (RR - 30).

Malignancies which spread from mother to foetus

- Melanoma
- Lymphosarcoma

Classifications

Breslow's classification: Based on thickness of invasion measured by optical micrometer - most important prognostic indicator until nodal spread

I: Less than 0.75 mm
II: Between 0.76 to 1.5 mm
III: 1.51 mm to 4 mm
IV: more than 4 mm

Relation of tumour thickness to nodal spread – based on AJCC classification

Lesion	*Tumour thickness*	*Nodal spread*
Thin	< 1 mm	< 10%
Intermediate	1-4 mm	20-25%
Thick	> 4 mm	60%

Clark's levels (Fig. 1.449)

Level 1: Only in epidermis
Level 2: Extension into papillary dermis
Level 3: Filling of papillary dermis completely
Level 4: Extension into reticular dermis
Level 5: Extension into subcutaneous tissue

Differential diagnosis for melanoma (other pigmented lesions of the skin)

- Seborrhoeic keratosis, dermatofibroma
- Pigmented BCC, pigmented SCC
- Naevus, sebaceous epidermal naevus
- Kaposi's sarcoma, mycosis fungoides
- Cutaneous haemangioma
- Certain skin adnexal tumours.
- Solar keratosis
- Pyogenic granuloma
- Cutaneous angiosarcoma

Types

- Cutaneous melanoma
- Extra cutaneous (ocular is common site)
- Occult (Unknown primary)

Clinical Types

1. *Superficial spreading:* **Most common**. 64%. Occurs in any part of the body with variegated irregular look. It has more radial growth and better prognosis. It commonly arises from a pre-existing naevus.
2. *Nodular melanoma:* 12-25%. **More aggressive**. It is common in younger age group, occurring in any part of the body. It has more vertical growth. Common in mucosa and muco-cutaneous junction; uniform;



Fig. 1.450: Melanoma in the sole. Often such pigmentation may be unnoticed.



Fig. 1.451: Large melanotic lesion in the heel.



Figs 1.452A and B: Primary melanoma with lymph node secondaries in two different individuals. Note the pigmented ulcerated secondaries in one.



Fig. 1.453: Melanoma in tongue.

Your mind will give back exactly, what you put into it.



Figs 1.454A to C: Melanoma in vagina – in muco-cutaneous junction. On table and excised specimen of melanoma.



Figs 1.455: 'In-transit' nodules in melanoma. They are secondary depositions in dermal lymphatics.



Fig. 1.456: Satellite nodule in melanoma occurs within 2 cm of primary. Note the primary in the heel and satellite nodule adjacent to it.

nodular; more vertical growth; nodal spread is common; has got poor prognosis. It usually appears as denovo. Common in men; common in trunk, head and neck.

3. ***Lentigo maligna melanoma:*** 7-15%. **Less common, least malignant**. Occurs in old age and common in face (**Hutchinson's melanotic freckle**). It is slow growing, variegated, brown macule/lentigo; common in face/neck/hands; common in elderly women. Lentigo maligna is *in situ* type.
4. ***Acral lentiginous melanoma:*** 5%. Occurs in palms, soles and subungual region. Common in **Japan**. It has got a **poor prognosis**. It is **least common**. Usually attains large size; nodular type with more vertical growth phase. It is common in Africa and Asia. It is less common in whites. It is often flat, irregular macule. It mimics fungal infection/pyogenic granuloma.
5. ***Amelanotic melanoma:*** This is the **worst type.** Because of the undifferentiation, tumour cells loose their capacity to synthesise melanin. It presents as pinkish fleshy growth of rapidly progressive tumour. It may mimic soft tissue sarcoma. It needs markers like S100, HMB45 for diagnosis.
6. ***Desmoplastic melanoma*** has high affinity for perineural invasion; is common in head and neck with higher recurrence rate.

***Note*:** *Subungual melanoma* which was earlier thought of acral lentiginous type is now considered as superficial spreading type. It is involvement of nail fold matrix (not nail plate). Triangular, macular, progressively widening pigmen-tation of nail fold with nail dystrophy is typical – *Hutchinson's sign*. It should be differentiated from benign racial melanonychia which are dark streaks under the nail.

Clark's concept—Two phases of growth: Initial radial growth phase occurs horizontally, later vertical growth phase occurs with invasion.

Melanoma

- 5 % of all skin cancers—Incidence
- 20 times more common in whites than blacks
- Mucosal melanoma has got poor prognosis
- Can spread from mother to foetus
- Multiple melanomas are 1% common
- Melanoma in choroid will not cause lymph node involvement, as it has no lymphatic drainage. But late massive liver secondaries even after 10-20 years is known to occur
- 10% of melanomas are familial
- Satellite nodules are secondary skin nodules within 2 cm of primary
- In transit' nodules are secondary skin nodules beyond 2 cm of primary any where up to lymph node region
- Melanoma may present as secondary (in liver, lungs, bone, brain) with occult primary when primary is situated in anus, genitalia, eye, external auditory canal, adrenal gland, nail bed and scalp – 7%

Clinical Features

- It can start in a pre-existing **naevus** (commonly junctional naevus)—50-60% or as **de novo** in a normal skin—40-50%.
- Melanoma is **unknown before puberty.**
- ***No induration is seen in melanoma.***
- Pigmentation with irregular surface and margin with rapid growth.
- **Ulceration, bleeding, itching, change in the colour.**

Note: When a mole turns malignant, following changes should be observed -

- ***Major signs*****:** Change in size (diameter more than 6 mm), shape and colour
- ***Other changes***:
  - Inflammation, crusting, bleeding, itching
  - Nodularity, ulceration, halo around a mole
  - Satellite lesions
  - Doppler positive pigmented lesions using hand held Doppler (> 1 mm thick lesion)

Five most important features of melanoma:

- **A**symmetry
- **B**order irregularity
- **C**olour variation
- **D**iameter > 6 mm
- **E**levation

Spread

- **Through lymphatics** it spreads to regional lymph nodes either by permeation or by embolisation.
- **In-transit nodules or satellite nodules** are seen in the skin between the primary lesion and regional lymph node area, and is due to retrograde spread to dermal lymphatics.
- **Through blood**: To lungs, liver (huge liver), brain, skin, bones. Secondaries are typically black.

Blood spread in melanoma

- *Brain*—Convulsions, localising features and raised intracranial pressure
- Lung—Cannon ball secondaries, pleural effusion-haemoptysis, chest pain and cough
- Liver (massive liver), ascites
- Skin—Cutaneous nodules often pigmented
- Bones—Bone pain, pathological fracture. Paraplegia/ neurological deficits in spine metastasis

Extensive visceral involvement causes ***melanuria***

- Melanoma **in choroid** has got better prognosis, because as there are no lymphatics, spread is delayed.
- Sometimes primary is very small and unnoticed (in anus, subungual region). They present with features of secondaries only.

Note: Infiltration into deep fascia by melanoma is rare in initial stages as deep fascia acts as a strong barrier.

Staging of Malignant Melanoma (It is older staging system)

IA: Thickness less than 0.75 mm.
IB: Thickness between 0.76 to 1.5 mm.
IIA: Thickness between 1.51 to 4.0 mm.
IIB: Thickness more than 4.0 mm.
IIIA: Any of the above + nodes less than 3 cm.
IIIB: Any of the above + nodes more than 3 cm.
IV: Any of the above + any node + M1 (distant spread).

Occult melanomas (primary unknown) are common in

— Anus
— Scalp
— External auditory canal
— Nail bed
— Genitalia
— Eye
— Adrenal medulla

You will soon break the bow if you keep it always stretched.

Newer TNM staging (2002) for melanoma

Tumour
T 0 No tumour
T is *In situ* tumour
T 1a < 1 mm level II, level III no ulceration
T 1 b < 1 mm, level IV with ulceration
T 2 a 1-2 mm no ulceration
T 2 b 1-2 mm with ulceration
T 3 a 2-4 mm no ulceration
T 3 b 2-4 mm with ulceration
T 4 a > 4 mm no ulceration
T 4 b > 4 mm with ulceration

Node
N 0 No nodes
N 1 a—one node micrometastasis
N 1 b—one node macrometastasis
N 2 a—2 or 3 nodes micrometastasis
N 2 b—2 or 3 nodes macrometastasis
N 2 c—no nodes but satellite or in transit lesions
N 3-4 or more nodes; nodes with satellite or in transits

M—Metastasis
M 0—no blood spread
M 1 a—Skin, subcutaneous tissue, distant node
M 1 b—Lung spread
M 1 c—Other viscera or distant spread and increase in LDH

Tumour markers for melanoma

- MELAN-A
- S 100
- HMB 45 (Hydroxy Methyl Bromide)
- LDH

Investigations

- **No incision biopsy.** It can cause early blood spread.
- Excision biopsy of primary.
- FNAC of lymph node.
- U/S abdomen to look for liver secondaries (usually huge hepatomegaly occurs).
- Chest X-ray to look for secondaries in lung ("cannon ball" appearance). HRCT of chest is ideal.
- Relevant other methods depending on site and spread, e.g. CT scan of head, chest, abdomen, pelvis.
- Urine for melanuria signifies advanced disease.
- Sentinel lymph node biopsy (**SLNB).**

Treatment

Surgery is the main treatment.

For primary:

1. **Wide excision** with a clearance margin of 3-5 cm. (Presently recommendation - for melanoma < 1 mm depth, clearance of 1 cm is sufficient; for deeper disease 2 cm clearance margin is sufficient).
2. If primary area is wide, then amputation with one joint above is done.
3. In fingers and toes, disarticulation is required.



Fig. 1.457: Wide excision of melanoma from the heel. Note the clearance margin and depth of dissection.



Fig. 1.458: Wide excision and skin grafting done for melanoma.



Figs 1.459A and B: Widely excised melanoma specimen from heel. Cut section of widely excised specimen of melanoma from heel shows the depth of the tumour.



Figs 1.460A and B: Secondaries in inguinal lymph nodes from primary melanoma sole-on table finding. Specimen of ilio-inguinal block is also shown. Pigmented nodes are observed.

4. Melanoma in anal canal may require abdomino-perineal resection.
5. Enucleation of eye in case of melanoma in eye.



Fig. 1.461: Disarticulation of lateral two toes for interdigital melanoma.



Fig. 1.462A: Melanoma secondaries in groin nodes after block dissection. Black lesions are observed in cut section.

For lymph node secondaries:

1. In a clinically palpable lymph node, FNAC of lymph node is done. In case of spread, then regional block dissection, i.e. ilio-inguinal or axillary or neck is done.
2. In a fixed lymph node, only chemotherapy is the treatment because it is inoperable.
3. *Lymphatic mapping and sentinel node biopsy:* Radio active colloid is injected around primary site and lymphoscintigraphy is done using hand held gamma camera to visualise the micrometastasis in the nodal field. If there are micrometastasis, then regional block dissection (therapeutic LND) is done.
4. Prophylactic regional block dissection which was previously advocated is now controversial. But still used in many centres. Elective lymph node dissection (ELND) is done when tumour thickness is 1-4 mm.

For loco regional recurrent melanoma:

1. *Isolated limb perfusion* using cytotoxic agents like Melphalan (M for M).
   Melphalan is injected at high temperature of 41°C with a pump and oxygenator through cannulas in femoral artery and vein with a proximal tourniquet *in situ.* Hyperthermia and oxygenation increase the metabolic activity of tumour cells to make it more vulnerable to melphalan. Procedure controls the local disease well with preserving the functioning limb. Complications like DVT, bleeding, sepsis can occur. It is used in local recurrence or ' In – transit' deposits.
2. Laser ablation of multiple small cutaneous lesions.

Chemotherapy:

Indications:

1. Secondaries in lungs, liver, bones.
2. After surgery for melanoma. Usually it is given intravenously.

Creativity begins with thinking different and progress with acting different, thus giving unique results.

Drugs are:

1. DTIC: Diethyl Triamine Imino Carboxamide.
2. *Melphalan* (Phenyl alanine mustard) (Melphalan for melanoma).
3. Carboplatin, vindesine.

Immunotherapy/biological therapy using specific tumour antibodies, BCG, levamisole, Corynebacterium parvum, alpha interferon, interleukins and tumour vaccines is tried with some success rate up to 40% in advanced melanomas.

Endolymphatic therapy can be done to control disease in the nodes using radioactive I_{131} or P_{32} with ultrafluid lipiodol along with lymphangiography.

There is not much role for radiotherapy.

Note: Radiotherapy is beneficial only in secondaries in brain and bones.

Prognosis is not good since it is a very aggressive tumour.

Prognostic factors - *overall poor*	Staging as prognostic factor
• **Tumour thickness** - very important factor • **Nodal spread** – once regional nodes are positive, 85% of patients will have occult distant spread. Number of positive nodes is also important. • Ulceration • In transit nodules • Vertical growth – poor prognosis • Metastatic disease • Staging • Mitotic activity	Stage I - > 90% prognosis Stage II - 70% Stage III - 35% Stage IV - < 2%

Sentinel node biopsy:

1. Carcinoma breast
2. Melanoma
3. Carcinoma penis

Note: Melanoma also can occur in fishes, dogs and horses.



Fig. 1.462B: Melanoma involving face extensively with destruction. Note the maggots over the surface of tumour. Melanoma is *most aggressive* cutaneous malignancy.

Self-assessment Questions

- Naevi.
- Skin adnexal tumour.
- Rodent ulcer.
- Epithelioma.
- Malignant melanoma.
- Junctional naevus.
- Treatment for melanoma.
- Staging of melanoma.

Sarcomas

Features of sarcoma
Liposarcoma
Kaposi's sarcoma

FEATURES

- Sarcomas are much lesser in incidence compared to carcinomas.
- It occurs in younger age group compared to carcinomas.
- They can arise from bone (osteosarcoma) or from any soft tissues (soft tissue sarcomas). (Mesenchymal tissue).
- They are much more aggressive compared to carcinomas.
- They are rapidly growing tumours with fleshy appearance.
- They are not encapsulated but are having pseudocapsule.
- They spread through blood especially to lungs often also to other organs.
- Lymphatic spread is not common with certain exceptions.
- They are not radiosensitive.
- Main method of treatment is surgery, i.e. wide excision, amputation.
- In inoperable cases debulking is the accepted method of treatment.
- Chemotherapy is the adjuvant therapy.

Important features of sarcoma

- More aggressive
- Rapidly spreading
- Not very much radiosensitive
- Blood spread
- Painless soft tissue mass is the presentation.
- Very vascular

SOFT TISSUE SARCOMA

- 1 % of adult malignancy
- 15 % of paediatric malignancies
- Incidence-
  - 35 % occurs in lower limb (commonest site)
  - 15 % upper limb, 15% retroperitoneum
  - 10% trunk, 10% viscera, 10 % other areas
- Soft tissue tumour > 5 cm should be biopsied in suspicious of sarcoma

- Commonest sarcoma of ***bone is osteosarcoma.***
- Commonest soft tissue sarcoma is ***liposarcoma.***
- *Usual clinical features* are: Diffuse swelling which is smooth, hard, warm and very vascular.

Note:

- Many liposarcomas arise at sites devoid of adipose tissue. Most rhabdomyosarcomas arise in locations that lack voluntary muscle.
- 40% of soft tissue sarcomas are more than 10 cm in size at the time of presentation; 30% are 5-10 cm and 30% are less than 5 cm.


Fig. 1.463: Soft tissue sarcoma foot. Note the vascularity.


Fig. 1.464: Osteosarcoma of the upper end of humerus in an adolescent boy.


Fig. 1.465: Osteosarcoma upper tibia. Note the size of the tumour and ulceration. It is very vascular.

All things are difficult before they are easy.



Figs 1.466A and B: X-ray pictures of osteosarcoma in tibia and femur.

Clinical Features of Soft Tissue Sarcoma

- Painless swelling of short duration with progressive increase in size- *soft tissue mass*.
- Compression of adjacent structures
- Smooth, hard, warm and vascular
- Features of secondaries in lung- cough, haemoptysis and chest pain.

Aetiology

- *Genetic-*
  - von Recklinghausen disease
  - Gardner's syndrome
  - Tuberous sclerosis
  - Basal cell naevus syndrome
  - Li-Fraumeni syndrome
- *Chemicals*—PVC, tetrachlorodibenzodioxin, arsenic
- *Viral*—HIV in Kaposi's sarcoma, cytomegalo virus



Figs 1.467A and B: Soft tissue sarcoma upper chest wall. Note the vascularity and extent.

- *Ionising radiation*—Malignant fibrous histiocytoma (p53)
- Lymphangiosarcoma in post mastectomy lymphoedema – *Stewart – Treves syndrome*.
- Osteogenic sarcoma in Paget's disease of bone / exposure to radium
- Retinoblastoma associated sarcoma
- Gorlin's syndrome
- Thorotrast, vinyl chloride, arsenic, pesticides

Investigations

- ***Incision biopsy*** is the main method of diagnosis.
- Excision biopsy is done if the tumour size is < 3 cm.
- Tru-cut biopsy.
- CT scan or MRI of the part to see the extent and invasion.
- MRI is the investigation of choice as it determines the vascularity, relation to vessel and fascial planes.
- Chest X-ray is done to look for secondaries.
- CT chest is ideal to see early lung secondaries. It is done in all deep seated, high grade and tumour more than 5 cm in size.
- Angiogram may be required to find out the tumour vascularity.
- Radio nuclide scintigraphy (Gallium-67)
- p-MRS (p-Magnetic Resonance Spectroscopy) and FDG(Fluor-2-Deoxy Glucose) PET are done to assess the metabolic activity of tumour.
- Immunohistochemistry and FISH (fluorescence *in situ* hybridisation).

Incision biopsy for soft tissue sarcoma–

- It is the ideal tool to conclude sarcoma histologically
- Incision should be placed in such a way that it can be included in wide tumour excision at later period

- Incision should be longitudinal in limbs
- Injury to vessels and nerves should be avoided
- Flaps should not be undermined
- Adequate haemostasis is needed, as tumours are vascular
- Immunohistochemistry and cytogenetics are possible, and often needed

FNAC is less useful for sarcomas. Core/Trucut biopsy can be done but not equal to incision biopsy.



Fig. 1.468: MRI picture of the soft tissue tumour thigh encasing vessels partially and eroding the bone. Patient needed high level, above knee amputation.



Fig. 1.469: CT picture of retroperitoneal leiomyosarcoma.

Staging of the soft tissue tumour is done depending on the tumour size, nodal status, metastasis and histological grading of the tumour **(GTNM staging).**

TNM staging of soft tissue sarcoma

Grade (G)	*Tumour (T)*
Gx Cannot be assessed	Tx Cannot be assessed
G1 Well-differentiated	T0 No primary
G2 Moderately differentiated	T1 Size < 5 cm or 5 cm (maximum dimension)
G3 Poorly differentiated	T1a: Superficial
	T1b: Deep tumour
G4 Undifferentiated	T2 Size > 5 cm
	T2a: Superficial
	T2b: Deeptumour
Regional lymph nodes (N)	*Distant spread (M)*
Nx Nodes cannot be assessed	Mx Cannot be assessed
N0 No nodes	M0 No distant spread
N1 Nodes present	M1 Distant spread present

Note: *Superficial tumour is outside the superficial fascia. Deep tumour is deep to superficial fascia or any tumour invading the superficial fascia.*

Grading of sarcomas

Low	Desmoid, dermatofibrosarcoma, Liposarcoma
High	Synovial, Rhabdomyosarcoma, Angoisarcoma Malignant fibrous histiocytoma, Extraosseous chondrosarcoma
Undetermined	Fibrosarcoma, Leiomyosarcoma

Differential diagnosis for soft tissue sarcoma–

- Haematoma
- Abscess
- Aneurysm
- Myositis

Treatment

- **Wide excision** is the treatment of choice with 3-5 cm clearance with adequate depth.
- **Compartment resection** is a radical limb saving procedure. Here muscle group of one compartment (anterior, posterior or medial) is resected entirely from its origin to insertion with the tumour. It is done only when tumour is intracompartmental. It is not suitable when tumour is extracompartmental or many compartments are involved or encased to major neurovascular bundle.

Knowledge is fire and it is antidote to fear.



Figs 1.470A and B: Recurrent chest wall tumour, could be secondaries, as patient was earlier amputated for soft tissue tumour hand (forearm amputation). X-ray of the same patient shows large tumour mass.

Indications for amputations in soft tissue sarcoma–

- Major neurovascular encasement
- Bone involvement
- Multiple compartment involvement
- Limb itself is diseased like lymphoedema
- Recurrence with multicentricity

- Amputation is done in large tumours of upper or lower limbs.
- Debulking surgery is useful in large advanced tumours like retroperitoneal sarcomas.
- Preoperative radiotherapy or chemotherapy followed by wide excision.
- **Postoperative radiotherapy** is commonly used because of less tumour burden and less wound problems. Titanium clips are placed during surgery at high risk areas to identify the site to concentrate proper RT.
  - *Brachytherapy* is very effective in local control of the tumour. Initially precise mapping of the area is done in the operation theatre. Loading catheters are placed in surgical field peroperatively. Later these catheters are loaded with iridium 192.
  - Permanent radioactive sources can also be placed to the area.
  - Palliative external radiotherapy can be given to prevent bleeding, fungation and to reduce pain in advanced cases. It is also used in secondaries in brain, bone.
- Primary radiotherapy alone (radical) is of less beneficial in soft tissue sarcoma.
- Chemotherapy drugs— *VAC* (*Vincristine, Adriamycin, Cyclophosphamide*) are commonly used. Other drugs *ifosfamide, dacarbazine* are used in combination with above drugs. *Mesna* is used as a protection for haemorrhagic cystitis. Chemotherapy is used when tumour is more than 5 cm or high grade. Usually postoperative chemotherapy is given.
- *Neoadjuvant chemotherapy* is used to make the primary tumour better operable.
- *Isolated limb perfusion using cytotoxic drugs and tumour necrosis factor* with hyperthermia is also often used.
- *Pulmonary metastasis* can be treated with wedge resection, segmentectomy, lobectomy, pneumonectomy. Surgery is done only when primary is well-controlled. Radiotherapy and chemotherapy are also tried. More than three number metastases in lung signify poor prognosis.

Radiotherapy in soft tissue sarcoma–

- Brachytherapy is given in high grade tumour
- External beam radiotherapy is used in low grade tumour
- All tumours more than 5 cm need adjuvant radiotherapy (external beam)
- Preoperative radiotherapy is also beneficial
- Deep seated tumour; high grade; size more than 5 cm needs chemoradiation

Prognostic factors

- Size > 5 cm - important factor
- High grade
- More than one compartment involvement
- Deep tumours and multicentric
- Neurovascular invasion
- Lung secondaries
- Clearance margin

LIPOSARCOMA

- It is the ***commonest type*** of soft tissue sarcoma arising from the fat cells (of primitive mesenchymal cells).
- It can occur as *de novo* or from a pre-existing lipoma.
- It is 20% of all soft tissue sarcomas.

Common Sites

1. Thigh—Commonest site.
2. Retroperitoneum.
3. Back.
4. Shoulder.

Types are—

i. Well-differentiated.
ii. Myxoid.
iii. Round cell.
iv. Pleomorphic (5%)—poor prognosis

Microscopically, it contains lipoblasts with 'signet ring' malignant cells. It is low grade type.

Spread is to lungs.

Treatment is wide excision or radiotherapy with surgical debulking in places where complete removal of tumour is not possible like in retroperitoneal liposarcoma.

FIBROSARCOMA

- It can arise from ***the bone*** or from ***soft tissues.***
- It is the next common soft tissue malignancy after liposarcoma.
- It is arising from fibroblasts.
- Commonest site is thigh.
- Spindle fibroblasts with *'herring bone'* pattern are typical on microscopy.



Fig. 1.471: Recurrent dermatofibrosarcoma protuberans.

Types

1. Well-differentiated.
2. Poorly differentiated.
3. Dermatofibrosarcoma protuberans. It is common in trunk.



Fig. 1.472: Malignant dermatofibrosarcoma left side of the chest wall.

4. Aggressive fibromatoses are variant of fibrosarcoma which are locally malignant in which desmoid tumour is also included.

Fibrosarcoma are slow growing tumour which attains large size.

Clinically it is smooth, hard, warm, localised tumour.

It compresses or infiltrates the adjacent structures like neurovascular bundle.

MALIGNANT FIBROUS HISTIOCYTOMA (MFH)

It is group of malignant soft tissue tumours with a fibrohistiocytic appearance. *It is the commonest extremity sarcoma* (lower > upper). Myxoid/giant cell/inflammatory/angiomatoid/pleomorphic are the types. It is common in adults and elderly.



Fig. 1.473: Dermatofibrosarcoma

People can be divided into three groups: (1) Those who make things happen, (2) Those who watch things happen, (3) Those who wonder what's happening.

LEIOMYOSARCOMA

- It arises from smooth muscle. Cut section shows whorled appearance.
- It is undetermined grade.
- It is common in retroperitoneum and viscera, but can occur in limbs and skin.
- Recurrence is common. It has got poor prognosis.
- It can occur in the piloerector muscle of skin; inferior vena cava; pulmonary artery.
- Desmin and actin are the most common immunohistochemical stains.



Fig. 1.474: Large soft tissue tumour over gluteal region with ulceration and vascularity. It was confirmed as malignant fibrous histiocytoma. Patient was successfully operated.

RHABDOMYOSARCOMA

It arises from striated muscle. It is common in *head and neck*, upper thigh and arm. *It is commonest sarcoma in children.*

Types:

1. Pleomorphic—commonest type of rhabdomyosarcoma. It is common in adult, aggressive with poor prognosis.
2. Embryonal—common in infants and children – *is seen in viscera like urinary bladder.*
3. Botryoidal—slow growing polypoidal – respond well to chemotherapy and radiotherapy.
4. Alveolar—chromosomal translocation is common. It is more aggressive tumour with poorer prognosis. (High grade)

   It also metastasises to lymph nodes.



Fig. 1.475: Recurrent soft tissue tumour thigh. Note the scar of old surgery.

CHONDROSARCOMA

- It arises from chondroblasts.
- It attains large size with slow growing nature.
- Common sites are ribs, flat bones.



Figs 1.476A and B: Chondrosarcoma leg lateral aspect. X-ray shows calcified tumour. It was successfully removed as limb salvage procedure.

HAEMANGIOSARCOMA

It originates from blood vessel endothelium.

Types

Malignant haemangioendothelioma.
Malignant haemangiopericytoma.



Fig. 1.477: Aggressive haemangiosarcoma of the scalp.

LYMPHANGIOSARCOMA

- It arises from lymph vessel endothelium.
- It commonly occurs after radical lymph node dissection.

SYNOVIAL SARCOMA



Fig. 1.478: Synovial sarcoma.

- It originates from synovial cells.
- It is common in thigh, leg, shoulder, hand and foot.
- Occasionally it can occur in the abdominal wall and retroperitoneum.
- It is common in young individuals.
- It occurs adjacent to joint but uncommon to involve the synovial sheath of the joint.
- It spreads both through blood as well as through ***lymph nodes (20%).***
- It is very aggressive soft tissue sarcoma (High grade).
- Calcification with or without ossification is common – 10%.
- Synovial sarcoma may be biphasic or monophasic.
- It possess specific chromosomal translocation (96-100%) – t(X; 18)(p11.2; q11.2).

MALIGNANT NEURILEMMOMA

- It is commonly associated with multiple neurofibromatosis of von Recklinghausen's disease.
- It produces pain, tenderness and paraesthesia.

KAPOSI'S SARCOMA

- It is malignant blood vessel tumour of multicentric origin arising from vascular smooth muscle or pericytes.
- It is seen commonly in HIV patients due to immunosuppression.
- Primary tumour commonly occurs in skin, mucus membrane, lymph nodes or viscera.
- It is linked with Human Herpes Virus 8(HHV8) as causative agent.

Types

1. *European Kaposi's sarcoma*: It is common in old age. It is first described by Kaposi in 1862. It mainly involves skin especially lower extremity. Visceral involvement is rare.
2. *African Kaposi's sarcoma*: It occurs commonly in children and young individual. It involves skin and lymph nodes commonly. It resembles lymphoma.
3. *Transplant associated Kaposi's sarcoma*: It is due to drug induced immunosuppression. It involes mainly skin and often regresses once immunosuppression is discontinued.
4. *AIDS associated Kaposi's sarcoma*: It occurs in 30-40% of AIDS patients. It is common in homosexuals. It has got wide, disseminated involvement with metastases. It is very aggressive. It is often associated with lymphoma and other malignancies.

Note: Kaposi's sarcoma is not found in transfusion related AIDS.

Clinical Features

- Multiple reddish-blue nodules in the skin with ulceration over the nodule.
- Lymph node enlargement.
- Koebner phenomenon is common in areas of trauma.

Differential Diagnosis

- Lymphomas.
- Cutaneous angiomatoses.
- Mycobacterial infection of skin.

Investigations

- Biopsy from the skin lesion.
- Tests for HIV infection.

Small minds are first to condemn great ideas.

Sarcomas which also spread to lymph nodes

1. Synovial sarcoma
2. Lymphangiosarcoma
3. Rhabdomyosarcoma—alveolar type
4. Ewing's sarcoma
5. Angiosarcoma
6. Epitheloid sarcoma
7. Carcinosarcoma of uterus

Treatment

- Irradiation.
- Chemotherapy. Drugs used are adriamycin, bleomycin and vinblastine.
- Antiretroviral therapy.
- Interferons.

Self-assessment Questions

- Liposarcoma.
- Kaposi's sarcoma.
- Differentiate between sarcoma and carcinoma.
- General features, management of soft tissue sarcomas.

Amputations

> ***"Amputations is one of meanest yet one of the greatest operation is surgery, i.e. mean—when resorted to where better may be done. Great—as the only step to give comfort and prolong life."***
>
> ***—Sir William Ferguson***

Amputation
Prosthesis

AMPUTATION

Indications

- Gangrene due to atherosclerosis, embolism, TAO, diabetes, ergots.
- Trauma: To save life in crush injuries.
- Neoplasms: Osteosarcomas, Marjolin's ulcer, melanomas.
- Gas gangrene.
- Severe sepsis.
- Occasionally severe elephantiasis, madura foot, when all other methods have failed to help.
- **Dead, dying, devitalised tissues.**
- Severe deformity congenital or acquired.

Types

I.
- *Non end bearing/side bearing.*
- *End bearing/cone bearing.*

II.
- *Weight bearing.*
- *Nonweight bearing.*

Types of flaps

- *Long posterior flap* in below-knee amputation.
- *Equal flaps* in above-knee amputation.



Figs 1.479A and B: Different levels of amputation in upper limb and lower limb.

Ideal Stump

- Should heal adequately.
- Should have rounded, gentle contour, with adequate muscle padding.
- Should have sufficient length to bear prosthesis.
  - For B-K 7.5 (minimum) to 12.5 cm from tibial tuberosity
  - For above and below elbow 20 cm stump.
  - For A-K 23 cm from greater trochanter.



Fig. 1.480: Little toe amputation for gangrene. Wound has healed well.



Fig. 1.481: Forefoot amputation.

Asking for help is strength, not weakness.



Fig. 1.482: Above-knee amputation done for osteosarcoma of the upper end of the tibia. Here equal flaps are used.

- Should have thin scar which does not interfere with prosthetic function.
- Should have adequate adjacent joint movement.
- Should have adequate blood supply.

Conical bearing

- Here healing is by primary intention
- Bone should not be projecting
- Myoplastic
- No neuroma
- Scar should not be tender
- Proximal joint should be supple

Evaluation of the Patients who need Amputation

- Haematocrit, control of anaemia by transfusing blood/packed cells.
- Control of infection using antibiotics.
- Decision of level of amputation by skin temperature, arterial Doppler.
- Informed consent should be taken.
- Plan for prosthesis and rehabilitation by physiotherapist and rehabilitation team.

Different incisions for amputation

- *Circular incision amputation*– skin and muscles are divided circularly at a lower level than that of bone
- *Elliptical/oval incision* amputation
- *Racquet incision amputation* – for digital disarticulation
- *Amputation using flaps* – it may be of equal flap (above knee amputation) or with long posterior single flap (below knee amputation). Total length of single flap or combined length of two flaps should be equal to 11/2 times the diameter of the limb at the line of amputation. Flap should be semicircular to get a conical stump, not rectangular

Principles in Amputation

- Adequate blood supply of the flap should be maintained.
- Proper marking of the skin incision is essential.
- Tourniquet *should not be used* if amputation is done for vascular diseases.
- Proximal part of the flap contains muscle component but distal part should contain only skin and deep fascia.
- Flap length should be adequate; not short. It should be ideally semicircular not rectangular to get a conical stump.
- Nerve should be pulled down and cut using a sharp knife and allowed to retract into the soft tissue otherwise neuromas may develop.
- In crush injury/entrapment injury/sepsis - guillotine amputation is done. Later skin is pulled down by using skin traction, eventually to have better skin coverage.
- Bone should be cut with beveling and all sharp margins should be rounded.
- Postoperatively regular dressings are done. Patient is mobilised using axillary crutches. After 3 months, once scar has matured and stump has become supple, proper prosthesis is fit. Berlamont first started immediate postoperative fitting of prosthesis to leg for early mobilisation. *Plaster pylon* is applied to the stump and a prosthetic extension is fit to facilitate partial weight bearing immediately after surgery. It as got more stump complications and so it has not become popular.



Fig. 1.483: Pylon is plaster cast with walking component used for immediate mobilisation after below-knee amputation.

- Stumps can be side bearing (sutures are on the side); end bearing/conical (sutures are on the end) or cylindrical.
- Postoperatively active exercise should be given to the proximal joint so that prosthesis can be fit to it properly.
- If there is sepsis especially in gangrene limb, flaps should be left open or loosely sutured otherwise flap necrosis occurs.
- Proper anatomy of muscles and neurovascular bundle around should be known in all amputations.

Different Amputations


8
7
Gritti-stokes
6
5
4
3
2
1
1. Ray's
2. Transmetatarsal (Gillies)
3. Tarso metatarsal (lisfranc's)
4. Midtarsal (Chopart's)
5. Syme's
6. Below-knee (Burgess)
7. Transcondylar
8. Above-knee

Fig. 1.484: Different levels of amputation in lower limb.

- *RAY amputation* – Amputation of toe with head of metatarsal or metacarpals.


Incision for ray amputation

Fig. 1.485: Ray amputation for toes-incision.

- *Transmetatarsal amputation (Gillies')* – Here amputation is done proximal to the neck of the metatarsals, distal to the base.
- *Lisfranc's amputation* (Tarso metatarsal amputation) Here tarso metatarsal joint is disarticulated with a long volar flap.
- *Chopart's amputation* (Midtarsal amputation) – Here talonavicular joint and calcaneo cuboid joints are disarticulated. Tibialis anterior muscle is sutured to drilled talus bone. A long volar flap is used and immobilised for 6 weeks after surgery.
- *Syme's amputation* – It is removal of the foot with calcaneum and cutting of tibia and fibula just above the ankle joint with retaining heel flap (dividing both malleoli). Heel flap is supplied by medial and lateral calcaneal vessels (branches of posterior tibial artery). *Elephant boot* is used for the limb after Syme's which is inexpensive. Many patients walk well with Syme's stump without difficulty. It is presently mainly used in trauma (crush injury) and malignancies in distal part of the foot. In vascular diseases, calcaneal vessels may not be adequate to maintain the viability of the flap. While raising the flap, knife should be very close to the calcaneum so as to avoid injury to calcaneal vessels and to maintain the viability of the flap.


Level of bone cutting (tibia and fibula just above malleoli)
Incision for Syme's amputation

Fig. 1.486: Syme's incision and level of amputation.



Fig. 1.487: Elephant boot used after Syme's amputation.

Imagination is the highest kite one can fly.

- *Modified Syme's amputation* – Here heel flap is elliptical. Tibia and fibula are divided slightly higher. But variation here is the elliptical flap.


Level of bone cutting
(tibia and fibula
above malleoli)
Incision for modified Syme's

Fig. 1.488: Modified Syme's incision is elliptical one.

- *Pirogoff's amputation* – It is like Syme's amputation except posterior part of the calcaneum is retained along with heel flap. It provides longer stump than Syme's amputation.


Cut ends tibia
and fibula
Incision
Heel flap
Calcaneum-part

Fig. 1.489: Pirogoff's amputation.

- *Below-knee amputation* – Here we use a long posterior flap with scar placed over anterior aspect is used. Prosthesis placement is better here with greater range of movements without limp and without support. It is also called as *Burgess amputation*. Fibula should be divided first, higher than the proposed site of cut of tibia otherwise its sharp end will press on the skin flap. Tibial stump should be beveled anteriorly. Posterior muscles are sutured across the bone end, to the periosteum in front. In more proximal type of below knee amputation, fibula often is removed to allow the proper use of flap. Length of the flap should be 11/2 times the circumference of the site (around 12 cm). Stump length is 14-17 cm from knee joint. Minimum length required for prosthesis is 8 cm. If need to extend more proximally, it is better to do above knee amputation. Modern artificial limbs like *suction socket prosthesis* are used now.


Fibula
Tibia
Muscle
Myocutaneous flap
Incision
Tibia
Muscle
Flap
Anterior view
Posterior view

Fig. 1.490: Below-knee amputation technique – incision, flap and levels of cutting bones.



Fig. 1.491: Below-knee amputation – long posterior flap. Note the placing of the drain.



Fig. 1.492: Below-knee amputation flap necrosis has occurred which eventually granulated with repeated dressings. Area is ready for skin grafting.

- *'Peg-leg' amputation* – It is amputation 5 cm below the knee level – proximal most below knee amputation. It is *not practiced* nowadays. Here anterior flap is rotated posteriorly like a hood and patient kneels and bears weight which is well-accustomed to pressure. It is done whenever prosthesis cannot be used probably due to economic causes (in developing countries).



Fig. 1.493: 'Peg-leg' amputation is below-knee amputation done close to the knee joint (5 cm stump) with folding flap and metallic support down. It is not used now.

- *Transcondylar-Gritti-Stokes amputation* with long posterior flap. Femur is divided just above the articular surface and patella is anchored to the divided femur. There is risk of nonunion between patella and femur. This procedure is *no longer performed*.
- *Above-knee amputation* – Usually equal anterior and posterior flaps are used. Lower third and middle third level amputations are done. Ideally the required length of the femur as stump is 25 cm from the tip of the trochanter. Femur length lesser than 10 cm is not possible and here one needs to do hip disarticulation. In children as growing epiphysis of femur is in lower end, it is essential to preserve as much length of femur as possible.



Fig. 1.494: Above-knee amputation incision and approach.



Fig. 1.495: Above-knee amputation wound which is infected in a diabetic patient.

- *Hip disarticulation*– It is done whenever it is not possible to save the minimum 10 cm length of the femur. Incision used is either single posterior flap – Solcum's approach (better) or anterior racquet incision – Boyd's approach.
- *Hind quarter amputation* – Inter innominato abdominal amputation (Sir Gordon Taylor's amputation):

The most popular Jaipur foot was designed by PK Sethi

Removal of one side pelvis with innominate bone, pubis, muscles and vessels. Original ligation of common iliac artery is modified to individual ligations of external and internal iliac vessels. Internal iliac artery is ligated beyond the origin of the superior gluteal artery to keep the large posterior flap viable. *Now hind quarter name is replaced by hemipelvectomy*. It may be *standard hemipelvectomy* with classic gluteal flap; *extended hemipelvectomy* with removal of posterior part of the sacrum; *conservative hemipelvectomy* with retaining part of the pubis, ilium bones on that side. *Internal hemipelvectomy* is new method wherein *hemipelvectomy* is done with preserving the limb.

- *Krukenberg's amputation* is done in upper limb following any trauma. Here forearm amputation is done in such a way that it creates a gap between radius and ulna like a claw to have a hold or grip.
- *Inter scapulo thoracic amputation (Forequarter amputation)* (Little wood's posterior approach or Berger's anterior approach): It is removal of entire upper limb with scapula and lateral 2/3rd of the clavicle and muscles attached to it. It is done in malignancies involving scapula, upper part of humerus and near shoulder joint.
- In emergency conditions like severe sepsis, gas gangrene and machinery entrapment, *Guillotine amputation* is done without suturing. Suturing is done at later period. All tissues are divided at same level.

Postoperative Period

- Physiotherapy is advised.
- Regular dressings are done.
- Crutch is used initially, after 3 months prosthesis is placed.
- Rehabilitation is important.



Fig. 1.496: Upper limb Guillotine amputation-above elbow done for trauma induced gas gangrene.



Fig. 1.497: Forequarter amputation done for sarcoma proximal to shoulder joint.



Fig. 1.498: Above-knee amputation stump having small sinus.



Figs 1.499A and B: Below-knee amputation stump infected. In 'B' tibia is exposed.



Fig. 1.500: Ulcer in the below-knee amputated stump.



Fig. 1.501: Ulcer after great toe amputation done for vascular gangrene.

Complications

Early–

- Haemorrhage.
- Haematoma.
- Infection.

Late–

- Pain.
- Ulceration of stump.
- Ring sequestrum formation.
- Flap necrosis.



Fig. 1.502: Patient with axillary crutches.

- Painful scar.
- ***Phantom Limb***: Feeling of amputated part *in toto* or partially with pain over it. Reassurance, analgesics, rehabilitation are the treatment. Control of pain prior to amputation reduces the chances of developing phantom limb. It is common in upper limb.

PROSTHESIS

It is the substitution to a part of the body to achieve its optimum function.

(Orthroses are supplement for limb function.)

- *Syme's amputation*: Elephant boot, Canadian Syme's prosthesis.
- *Below-knee amputation*: Patellar tendon bearing (PTB) prosthesis and solid ankle cushion heel (SACH).
- *Above-knee amputation:* Suction type prosthesis. It is placed above the stump. It is better and well-tolerated.
- *Nonsuction type prosthesis*: It is placed at the ends. It requires additional support.
- *Hind-quarter amputation:* Tilting table prosthesis (TTP) or Canadian prosthesis is used here.

In Upper Limb

1. Above elbow prosthesis is a high technology prosthesis. It is sophisticated device with harness, socket, elbow joint unit, control cable, forearm and wrist device.

We make a living by what we get; we make a life by what we give.



Figs 1.503A to C: Below-knee amputee with prosthesis. It gives good range of movements, normal walk and comfort.

2. Below elbow prosthesis.

Krukenberg's amputation does not require any prosthesis.

Advantages of Prosthesis

- Cosmetic.
- Function of the part relatively can be got.
- Ambulation in lower limb prosthesis.

Disadvantages

- Infection.
- Pressure ulcers.
- Joint disability.

Prosthesis Types

- Exoskeletal prosthesis.
- Endoskeletal prosthesis with modular system.

Internal prostheses are one used inside. They are placed by open surgery. They are nonreactive, long durable materials, e.g. hip prosthesis in total hip replacement.

Self-assessment Questions

- Ideal stump.
- Prosthesis.
- Krukenberg amputation.
- BK amputation.

Reconstruction

Graft—*types*
Skin graft—*partial thickness graft, full thickness graft*
Flaps
Tendon—*tendon repair, tendon transfer, tendon graft*

GRAFT

Graft: It is transfer of tissue from one area to other without its blood supply or nerve supply.

Autograft: It is tissue transferred from one location to another on the same patient.

Isograft: It is tissue transfer between two genetically identical individuals, i.e. between two identical twins.

Allograft: It is tissue transfer between two genetically different members, e.g. kidney transplantation (Human to human) (Homograft).

Xenograft: It is tissue transfer from a donor of one species to a recipient of another species (Heterograft).

SKIN GRAFTS

> ***We bring back, refashion, and restore to wholeness the features which nature gave but chance destroyed, not that they may charm the eye but that they may be an advantage to the living soul, not as a mean artifice but as an alleviation of illness, not as becomes charlatans but as becomes good physicians and followers of the great Hippocrates. For although the original beauty of the face is indeed restored, yet this is only accidental, and the end for which the physician is working is that the features should fulfil their offices according to nature's decree.***
>
> **—Gaspare Tagliacozzi,** 1597

SKIN GRAFTING: It is transfer of skin from one area (donor area) to the required defective area (recipient area). It is an autograft.

Types

1. PARTIAL THICKNESS GRAFT (Split thickness graft—SSG)

Also called as *Thiersch graft*, is removal of full epidermis + part of the dermis from the donor area.

It may be

- *Thin SSG.*
- *Intermediate SSG*, all depends on the amount of thickness of dermis taken.
- *Thick SSG.*

Indications

1. Well granulated ulcer
2. Clean wound or defect which can not be apposed
3. After surgery to cover and close the defect created
   For example:
   After wide excision in malignancy
   After mastectomy
   After wide excision in squamous cell carcinoma

Graft can survive over periosteum or paratenon or perichondrium

Pre-requisite

1. Healthy granulation area.
2. B-haemolytic streptococci load less than 10^5 per gram of tissue, otherwise graft failure will occur

Contraindications

SSG can not be done over bone, tendon, cartilage, joint.

Technique

Donor area: Commonly *thigh,* occasionally arm, leg, forearm.

- Knife used is *Humby's Knife.*
- Blade is *Eschmann blade, Down's blade.*
- Using Humby's knife graft is taken, punctate bleeding is observed which says that proper graft has been obtained.

Different instruments used to harvest the skin graft

- Humby's knife
- Watson modification of Humby's knife
- Power dermatome is also used (Brown)
- Sterilised razor blade can be used with a specialised device to harvest small grafts under local anaesthesia

Donor area is dressed and dressing is opened *after 10 days*, not earlier.

Recipient area is scraped well and the graft is placed after making window cuts in the graft to prevent the

Goals and actions must meet.

development of seroma. Graft is fixed and *tie-over* dressing is placed. If graft is placed near the joint, then the part is immobilised to prevent friction which may separate the graft. On *5th day*, dressing is opened and observed for graft take up.



Fig. 1.504: Commonest donor area for spilt skin grafting is thigh.





Figs 1.505A to E: Technique of split skin grafting.

Stages of Graft Intake

1. *Stage of plasmatic imbibition*: Thin, uniform, layer of plasma forms between recipient bed and graft.
2. *Stage of inosculation*: Linking of host and graft which is temporary.



Fig. 1.506: Humby's knife with Eschmann blade.

3. *Stage of neovascularisation*: New capillaries proliferate into graft from the recipient bed which attains circulation later.
   Note: Graft is stored at low temperature of 4°C for not more than 21 days.



Fig. 1.507: Harvesting a skin graft



Figs 1.508A and B: Donor area of split skin graft in the thigh and graft placed over raw area in the leg.

Disadvantages of SSG

1. Contracture of graft. Two types:
   A. *Primary contracture* means SSG contracts significantly once graft is taken from donor area (20-30%). Thicker the graft more the primary contracture.
   B. *Secondary contracture* occurs after graft has taken upto recipient bed during healing period, due to fibrosis. Thinner the graft more the secondary contracture.
2. Seroma and haematoma formation will prevent graft take up.
3. Infection.
4. Loss of hair growth, blunting of sensation.
5. Dry, scaling of skin due to nonfunctioning of sebaceous glands. So after healing, oil (coconut oil) should be applied over the area.
6. Graft failure.

Advantages

1. Technically easier.
2. Wide area of recipient can be covered. To cover large area like burns wound, graft size is increased by passing the graft through a ***Mesher*** which gives multiple openings to the graft, which can be stretched on the wider area like a net. It can cause expansion upto 6 times.
3. Graft take up is better.
4. Donor area heals on its own.



Fig. 1.509A

Goodness is the only investment that never fails.



Fig. 1.509B



Fig. 1.509C

Figs 1.509A to C: Mesher used in split skin grafting to increase its surface area for coverage wider area like burns wound. A large defect can be covered by this. It can cause expansion upto six times.



Figs 1.510A to C: Mesh graft placed over donor area and photo of it, once it takes up.

2. FULL THICKNESS GRAFT (Wolfe graft)

- It includes both epidermis + full dermis.
- It is used over the face, eyelid, hands, fingers and over the joints.
- It is removed using scalpel blade. Underlying fat should be cleared off properly. Deeper raw donor area is closed by primary suturing. If large area of graft is taken, then that donor area has to be covered with SSG which is a disadvantage in full thickness graft.

Common sites of donor area

1. Post auricular area
2. Supraclavicular area
3. Groin crease area

Advantages

1. Colour match is good. Especially for face.
2. No contracture (unlike in SSG).
3. Sensation, functions of sebaceous glands, hair follicles are retained better compared to SSG.
4. Functional and cosmetic results are better.

Disadvantages

1. It can be used only for small areas.
2. Wider donor area has to be covered with SSG to close the defect.
3. Can not be used to cover ulcers.

OTHER GRAFTS

1. Composite graft which includes skin + fat + other tissues like cartilage.
2. Tendon graft.
3. Bone graft.
4. Nerve graft.
5. Venous graft.
6. Corneal graft.
7. Combined graft (allograft + autograft).

FLAPS

It is transfer of donor tissue with its blood supply to the recipient area.

Parts of Flaps

Base, pedicle, tip of flap. Vasculature is usually through the pedicle in the centre of the flap. Tip is the place where often flap goes for necrosis.

Indications

1. To cover the wider, deeper defects
2. To cover over bone, tendon, cartilage
3. If skin graft repeatedly fails

Types

1. *Random pattern flaps*: Here vascular basis is subdermal plexus of blood vessels. No known blood vessel is supplying it. Rectangular flap with length to width ratios 1 : 1 or less than 1.5 : 1.
2. *Axial pattern flaps*: Here superficial vascular pedicles pass along their long axes, e.g. forehead flap, deltopectoral flap, groin flap. Anatomically a known blood vessel is supplying it. It is long lengthy flap.



Fig. 1.511: Traumatic exposure of the bone. Flap is needed to cover this defect. It could be cross leg flap or rotation flap. Skin grafting is not possible in this situation.



Fig. 1.512: Anatomy and blood supply of a skin flap.



Fig. 1.513: Flap which has taken up well-placed over the defect on the bone with osteomyelitis.

Anatomical types depending on the types of tissue in the flap:

1. *Cutaneous flap*: Forehead flap, deltopectoral flap.
2. *Fasciocutaneous flap*: Radial forearm flap, scapular flap, lateral arm flap.

Great achievements begin with small opportunities.


A
Inguinal ligament
Anterior superior iliac spine
Groin flap
Superficial circumflex iliac artery
Femoral artery
B

Figs 1.514A and B: Groin flap is based on superficial circumflex iliac artery. It can be used in defects in hand and forearm. It is a cutaneous flap.

3. *Muscle flap*: Gluteus maximus muscle flap, gracilis flap, tensor fascia lata muscle flap.
4. *Myocutaneous flap*: Pectoralis major myocutaneous flap, latissimus dorsi flap - composite flap.
5. *Osteomyocutaneous flaps*: Radius with brachioradialis and skin, rib with intercostal muscles and skin - commosite flap.
6. *Local rotation flaps, transposition flaps*: When the flap moves laterally it is called as transposition flap. When the flap rotates laterally towards defect it is called as rotation flap. Transposition flap is squarely designed which moves laterally to close the defect creating a larger area on its original place which has to be covered with split skin graft.


Thoraco-acromial artery
PM muscle

Fig. 1.515: Pectoralis major myocutaneous flap.


SSG
Lesion excised
Flap raised
Flap rotated (transposed)
A
B

Figs 1.516A and B: Transposition flap.

7. *'Z' plasty*: It is a procedure which involves transposition of two inter-digitating triangular flaps. There is change in direction as well as gain in length of the common limb of Z. Angle size and length of the limb are the most important factors. It is used in managing contracted scars, facial scars, Dupuytren's contracture and to cover the excised defects like pilonidal sinus (example). There should be transverse skin slack available equal to the

length between the axes of Z. It can be single or multiple Z plasty. Complications are flap necrosis near the angle tip, infection, failure.

8. *Free flaps*: Vascular pedicle of the flap, both artery and vein are anastomosed to recipient vessels using operating binocular microscopes.
9. Omental flaps.
10. *Island flap*: Localised flap is swung around a stalk from the donor area to the recipient area often with the pedicle buried underneath the skin bridge in between. Pedicled flap is also an island flap.



Fig. 1.517: Technique of 'Z' plasty. It is used in contracture release. Dupuytren's contracture and pilonidal sinus.



Fig. 1.518: Rhomboid flap



Fig. 1.519: Technique of V-Y plasty and Y-V plasty.



Fig. 1.520: Bilobed flap is used in lesions of the nose commonly.



Fig. 1.521: Advancement flaps, used in distal defects.

Areas where flaps are commonly used: Oral cavity, neck, breast, limbs (leg), buttock, bedsores.

Flaps mobilised from donor area with its pedicle is placed and sutured to recipient area. Once flap takes up usually in 3-6 weeks, base of the flap is cut and sutured to recipient area.



Fig. 1.522: On table marking of glabellar flap to place after excising a lesion in the root of the nose.

Duty makes us do things well, but love makes us do them beautifully.



Fig. 1.523: Waltzing of a flap.

Saltatory flap is mobilising the flaps in stages from distant donor area towards recipient area. It requires many staged surgeries and long term hospitalisation.



Fig. 1.524: Saltatory flap. Flap raised from the abdomen is reached to the cheek in stages – from abdomen to wrist; from wrist to cheek.

Waltzing is a technique wherein flap is moved from donor area and attached adjacent to the recipient defect area. Later in 2nd stage, it is moved towards the defect formally. It reduces the tension on the flap and increases the success rate.

Advantages of Flaps

1. Good blood supply, good take up.
2. Gives bulk, texture, colour to the area.
3. Allows required movements in the recipient area. For example, jaw movements after pectoralis major flap after wide excision with hemimandibulectomy for carcinoma cheek.
4. Cosmetically better.

Disadvantages of Flaps

1. Long-term hospitalisation.
2. Infection.
3. Kinking, rotation and flap necrosis.
4. Staged procedure.

Positioning of the patient for long time is important to have a good flap take up which is a real discomfort to the patient.

Note: Delaying of the flap after mobilisation is done to reorient its blood supply so as to decrease flap necrosis and increase flap survival. Delaying period is 10-14 days. Flap is raised properly as required and resutured to same place so as to allow the formation of reorientation of vasculature near the tip of the flap. This delayed flap is raised again in 10-14 days to place in required area.

Deltopectoral flap - It is based on first three perforating branches of the internal mammary artery (mainly 2nd perforator). Flap runs horizontally across the chest wall anteriorly towards shoulder tip from its base over the sternal border. Its upper border is along the line of the clavicle; its lower border is along the line of anterior axillary fold line. Raw area often requires a spilt skin grafting. It is usually rotated upwards often with waltzing. It is tubed and attached above. Tube is drained to prevent any collection to occur. Rotation angle is important to prevent any kinking in the pedicle. It is usually used to cover the defects in cheek, chin, mastoid and parotid region. Often flap is delayed to get adequate length.



Fig. 1.525: Deltopectoral cutaneous flap.

Groin flap: It is based on superficial circumflex iliac artery which is 2-3 cm below and parallel to the inguinal ligament. Artery originates from femoral artery over medial border of the sartorius and ends at anterior superior iliac spine. 1:1 rectangular flap with deep fascia is used. Secondary defect can usually be closed with sutures. It is used mainly for defects in wrist/forearm where positioning is easier.



Figs 1.526A and B: Groin flap used for burns defect in the hand.

Latissimus dorsi muscle/myocutaneous flap: It is based on thoracodorsal artery, a branch of subscapular artery. Skin over the upper and anterior border of Latissimus dorsi is used for transfer. It is commonly used to cover the defect after mastectomy. But it does not give the bulk. It is technically easier. It can be used as muscle flap also. It helps as skin cover. Prosthesis is needed to place underneath to provide bulk in post mastectomy defect.

Pectoralis major myocutaneous flap - It is based on the pectoral branches of thoracoacromial artery. Usually skin below and medial to nipple over the muscle is used. Muscle pedicle is made as broad as skin. It used to cover the defect over the cheek/neck/pharynx/intraoral lesions after wide excision with removal of skin over the tumour. Vessel marking is 2 cm medial to coracoid process, obliquely below the clavicle at the junction between middle third and outer third. Skin with muscle is dissected from the deeper structures like ribs, intercostal muscles and pectoralis minor. Flap is raised upwards upto the coracoid. Lateral pectoral vessels if possible are retained, otherwise can be sacrificed. Defect below is usually closed primarily with sutures. Often it needs spilt skin grafting. Pectoralis major flap can be used along with deltopectoral flap with proper planning.



Figs 1.527A and B: Pectoralis major myocutaneous flap used for carcinoma cheek.

Gastrocnemius muscle flap: It is either medial or lateral and is commonly used to cover the upper part of the tibia and knee joint. It is technically easier and functional deficit occurring at donor area is insignificant. It is rarely used as myocutaneous flap.

Transverse rectus abdominis muscle flap (TRAM flap): It is either superior pedicle based on the superior epigastric vessels or inferior pedicle based on the inferior epigastric vessels. Superior pedicle based flap is used to cover postmastectomy area or chest wall defect. To cover post mastectomy area opposite side superior pedicle is used to reduce the arc through which flap has to rotate (but rotating from opposite side is technically difficult). Inferior pedicle flap is used to cover the defects in groin and thigh. Proper marking of the flap is essential. Skin incision is made like an ellipse. Anterior rectus sheath is cut in the line of incision and is raised upwards carefully of the rectus muscle upto the xiphisternum. Muscle is gently separated of the posterior rectus sheath with care not to injure the epigastric vessels. Once dissection is complete lower part of the muscle is cut in superior pedicle to rotate upwards carefully. In the upper part again anterior rectus sheath is opened to pass the flap towards the defect in subcutaneous plane. TRAM flap gives bulk and contour to the defect. But it is technically difficult. Usually opposite side of the defect is taken as flap as it is easier to rotate from opposite side. Defect in the abdomen usually needs mesh to support and close. It is not possible to do this flap in obese individuals and if patient has undergone laparotomy earlier (with a lengthy scar). Inferior cut end of the inferior epigastric artery in superior pedicle flap can be anastomosed to a vessel in recipient bed to improve the perfusion *(supercharging).* Inferior epigastric artery in inferior pedicle can be additionally perfused using opposite inferior epigastric artery (*recharging*).

Radial forearm flap – It is perfused from the radial vessels and raised on the flexor aspect of the forearm. Perforating branches of these vessels supply deep fascia and skin over it. Flap can be fasciocutaneous or osteofasciocutaneous/osteomyofasciocutaneus if radial bone is also used as part of the flap. Radial forearm free flap is commonly used for mandible defects. It is technically easier and safer. Flap is raised along with skin, segment of the radius along its intermuscular septum through which vessels pass and brachioradialis as components. Care is taken in dissecting vessels of the bed and not to injure the radial nerve. In free flap artery is sutured to the recipient artery like facial artery using microscope. Other similar flaps are – ulnar forearm flap, scapular flaps, and vascularised fibular transfer.

Limberg flap is a type of rhomboid flap used in pilonidal sinus with base at gluteal skin.

Cross leg flap is commonly used to cover the defect in the foot/leg from opposite leg.



Fig. 1.528: Cross leg flap.



Fig. 1.529: Rotation flap. It is commonly used in gluteal region in managing bedsores.

TENDON

- Tendon is the continuity of the muscle to have its action at the site especially in hand, foot and digits.
- It is covered by synovial sheath with a thin layer of fluid in between which allows smooth gliding of the tendon.

Tendon after injury heals by

1. **Intrinsic healing method** occurs through synovial fluid when tendon is not under stress.
2. **Extrinsic healing method** occurs through proliferation of fibroblasts across epitenon. It occurs when tendon is under stress. It forms a mass of fibrous tissue at the site called as "*tenoma*". It may interfere with the proper gliding of the tendon.

Stages of tendon healing

1. By 21 days, weak healing occurs and contraction of muscle is possible
2. By 6 weeks, mild traction can be applied to the tendon
3. By 3 months, moderate stress can be used
4. By 8 months, full tensile strength is recovered

Tendon injuries may be cut wound, lacerations, injury associated with nerve or vessel injury.

TENDON REPAIR

1. ***Primary repair*** is done within 24 hours.
2. ***Delayed repair*** within a week after 24 hours.
3. ***Secondary repair*** anytime after one week.

Types of Suturing the Tendon

1. ***Kessler method***. Here knot comes in the cut part of the tendon.
2. ***Goldner method***. Here knot comes away from the cut ends of the tendon.

Suture material used is monofilament nonabsorbable suture material (poly-propylene, 3 or 4 zero).

- Continuous sutures are used for suturing.
- Epitenon can be later apposed with interrupted sutures.
- Postoperative immobilisation is advised for 3-4 weeks.
- Later passive and active exercise is done with the help of a physiotherapist.

Complications of tendon suturing are infection, adhesion, stiffness and failure.



Fig. 1.530: Types of tendon suturing.

TENDON TRANSFER

- It is the transfer of one tendon from its existing site to another site where its function is required to have a function required at the newer site.
- Function of the transferred tendon should be maintained by other tendons.
- Tendon should be able to acquire the function at the newer site properly.
- For example, in ulnar claw hand, the tendon of flexor digitorum superficialis (FDS) (of index finger) is transferred to lumbrical canal of the digits to have flexion at MCP joint and extension of proximal IP joint.

TENDON GRAFT

- When tendon suturing or transfer is not possible because of inadequate length, tendon of a muscle which is not of much help functionally, is taken as a graft to obtain required length.

  Common grafts used are:
  - Palmaris tendon in forearm.
  - Plantaris tendon in leg.
  - For example, extensor carpi radialis brevis (ECRB) is lengthened using tendon graft to transfer to lumbrical canals in claw hand.
- ***Problems in tendon graft***: Infection, adhesions, graft failure, stiffness of the part.

Self-assessment Questions

- Skin grafting.
- Stages of graft intake.
- Thiersch graft.
- Wolfe graft.
- Flaps.
- Complications of flaps.
- Tendon repair.
- Tendon transfer.
- Tendon graft.

Every job is self portrait of the person who did it.

Transplantation

Preoperative evaluation
Organ procurement
Renal transplantation
Cyclosporin A
Liver transplantation
Bone marrow transplantation
Pancreatic transplantation
Small bowel transplantation
Graft rejection
Dialysis—*cimino fistula*

PREOPERATIVE EVALUATION

- General evaluation: Pulmonary, cardiac, GIT, renal status and cancer screening.
- Immunologic evaluation: Serology for hepatitis, HIV, Cytomegalovirus.
- Placing the organ in the same position is called as orthotopic transplantation, e.g. liver.
- Placing the organ in new position is called as heterotopic transplantation.

Donor Criteria

a. *Cadaver donor*

- Individuals with severe brain injury resulting in brain death.
  Brain death is defined as "complete irreversible cessation of all brain functions".

Criteria for brain death

- Absence of spontaneous respiration
- Absence of cranial reflexes
- Absence of response to stimuli
- Irreversible causes
- Absence of cerebral blood flow
- Isoelectric EEG
- Sustained apnoea with elevated CO_2

Other criteria for cadaver donor.

- Normothermic patient.
- No respiratory effort by the patient.
- Brain—dead donor.
- The heart is still beating.
- No depressant drugs intake should be there while evaluating the patient.
- Individual should not have any sepsis, cancer (except brain tumour).
- Not a HIV or hepatitis individual.

b. *Living donor*

- Living unrelated donor.
- Living related donor.
- Individual should have normal health.

Requirements

- ABO typing.
- Serology tests.
- Angiogram.
- Intravenous urography.
- HLA typing.

Human Leucocyte Antigens (HLA)

They are cell surface molecules which are highly antigenic. They play main role in graft rejection and hence called as *major histocompatibility complex/antigens* MHC) (Dausset - 1958). *Class I* are located in nucleated cells. *Class II* are located in dendritic cells/macrophages/B cells, etc.

Major Histocompatibility Complex (MHC)

- MHC is located in chromosome number 6
- Individual will have two HLA (*Human Leucocyte Antigens*) genes inherited from each parents, which together called as HLA types
- Class I— HLA is HLA-A, HLA-B and HLA-C. Intracellular antigens
- Class II—HLA is HLA-DP, HLA-DQ and HLA-DR. Extracellular antigens
- HLA-DR is most important in kidney transplantation

ORGAN PROCUREMENT

- Once brain death has been confirmed in cadaver donor, after giving inotropic support drugs (T3 and argipressin) various organs are surgically removed carefully with preservation of their vessels. After removal, organs are flushed with chilled preservative solution (in specific organ procurement like of kidney, *in situ* perfusion of organs (kidneys) is done by placing double balloon catheter into the abdominal aorta and a balloon catheter into the femoral vein) and placed in sterile bags containing saline and organ preservative solutions which are then immersed in 0-4°C box containing ice. Donor specimens are transported to the site of the recipient centre. *Wisconsin and Euro-Collins solutions* are commonly used.
- *Non heart beating donors (NHBD)* – Here organs are procured from individuals who are just dead on arrival to the hospital or who have died in the

hospital in spite of resuscitation. *Category I* – Dead on arrival; *Category II* – Unsuccessful resuscitation; *Category III* – 'Awaiting cardiac arrest' after support withdrawal; *Category IV* – Cardiac arrest with brain death.

- *University of Wisconsin solution* contains – potassium lactobionate; sodium phosphate; magnesium sulphate; adenosine; allopurinol; glutathione; raffinose; hydroxyethyl starch; insulin; dexamethasone; potassium; sodium; with 320 mosmol/l osmolality and pH of 7.4.
- *Living donor's organs* are used commonly in kidney transplantation from genetically related individuals. It can be used from genetically unrelated donors after proper MHC match. Donor nephrectomy is done through loin incision (commonly from left side). Laparoscopic donor nephrectomy has become popular and safe.

RENAL TRANSPLANTATION

> ***An animal which has undergone a double nephrectomy and grafting of both kidneys from another animal can secrete almost normal urine with his new organs, and live in good health for at least a few weeks.***



Fig. 1.531: Renal transplantation.

Three types of donors

1. Living related donors.
2. Living nonrelated donors.
3. Cadaver donors.

Highest chances of success in any transplant (renal) is seen when the donor is the identical twin.

Compatibility should be checked by tissue typing, i.e. ABO blood group system and major histocompatibility complex.

Evaluation of living donor:

- Tissue typing, ABO, MHC typing.
- Renal function—blood urea, serum creatinine.
- IVP.
- Selective renal angiogram. Single vessel is better.
- HIV/hepatitis evaluation.

Usually *left kidney* is taken for *transplantation* because of *long left renal vein.* It is placed in right iliac fossa with ureter connected to the urinary bladder; renal artery to internal iliac artery (end-to-end); renal vein to external iliac vein (end to side). Renal artery (end) to external iliac artery (side) through Carrel stitch is also used for arterial continuity.



Fig. 1.532: Another method of getting arterial perfusion of the transplanted kidney by suturing (Carrel stitch) external iliac artery to renal artery side to end.

Technique

Before the removal of kidney, the donor receives IV mannitol to prevent kidney ischaemia, diuretics and IV heparin. After removal of donor kidney, protamine sulphate is given to the donor. Removed donor kidney is perfused with cold perfusion fluid at 4°C and cold intravascular electrolytes. Solutions used to preserve the donor kidney are *Euro-Collins* solution or *University of Wisconsin (UW)* (both contains inert sugar which prevents swelling of cells). First renal vein, then renal artery and at the end ureter is anastomosed.

The winner always has a programme;the loser always has a excuse.

Azathioprine, cyclosporine and prednisolone should be started 3 days prior to surgery. Diuretics and Mannitol should be continued as required.

Bilateral nephrectomy in recipient is required only in:

- Polycystic kidney disease.
- Haematuria.
- Severe hypertension.

Kidney will stand cold ischaemia for 72 hours.

Note: Overall survival is 90% in one year and 80% in five years.

Postoperative Management

1. Immunosuppression: By cyclosporine, azathioprine, prednisolone, antithymocytic globulin and antilymphocytic serum.
2. Proper fluid balance has to be taken care of.

Complications

1. Acute tubular necrosis.
2. Rejection (Rejection is identified by radioisotope study and percutaneous kidney biopsy). Chronic rejection is the common cause of graft failure.
3. Obstruction of the collecting system.
4. Infection.
5. Urine leakage-5%.
6. Secondary haemorrhage.
7. Renal infarction.
8. Hazards of immunosuppression—
    a. Infection by unusual organisms like cytomegalovirus, herpes, pneumocystis carnii, varicella and other bacterial infections, candidial infection.
    b. Changes in the cellular component of blood.
    c. Uncommon malignancies of CNS, skin.
    d. Nephrotoxicity, GIT bleeding and perforation.
    e. Hirsutism, delayed wound healing, cataract formation.
9. Renal artery stenosis-10%.
10. Renal vein thrombosis-5%.
11. Lymphocele.

CYCLOSPORIN A

- It is a fungal metabolite, a potent immunosuppressant used to prevent transplant rejection.
- It is initially given intravenously 4 mg/kg in 500 ml saline and later given orally 12 mg/kg daily. After few weeks dose is reduced to 5 mg/kg orally daily.
- Regular cyclosporin estimation, twice weekly is essential as well as estimation of blood urea, serum creatinine, and haematocrit is done.
- Oral therapy is required for a long time.
- It is commonly given along with prednisolone and azathioprine.

Toxic effects

- Nephrotoxicity
- Infections, (CMV, *Candida*, pneumocystis, secondary infections)
- Hirsutism
- Often lymphomas and malignancies of skin, CNS

LIVER TRANSPLANTATION

> ***An ideal treatment for several kinds of liver disease would be removal of the diseased organ and orthotopic replacement with a hepatic homograft.***
>
> **—T.E. Starzl, T.L. Marchioro, K.N. von Kaulla,** et al, 1963

Indications

- Primary biliary atresia, metabolic liver disease.
- Cirrhosis.
- Malignant disease of the liver.

Children respond better for liver transplantation. Tissue typing and cross matching are not that necessary and do not influence the results.

If the transplantation is done at the same site after doing hepatectomy, it is called as ***orthotopic liver transplantation***. If it is placed in a different site it is called as *ectopic* or ***heterotopic liver transplantation***. Success rate in liver transplantation is better.

BONE MARROW TRANSPLANTATION

Indications

- Leukaemias.
- Aplastic anaemias.
- Immune deficiencies etc.

Recipients are initially treated with total body irradiation. As bone marrow is an active immune system, *proper tissue typing* is essential. *Infant bone marrow* is better marrow as a *donor*. Marrow aspirated from donor's bone is transplanted by *intravenous injection* to the recipient.

Immunosuppression with cyclosporin-A is always needed. It will take few weeks to show the response.

Problems

1. Graft rejection.
2. *Graft-Versus-Host* disease (GVH) is more dangerous.

PANCREATIC TRANSPLANTATION

- It is used in diabetic patients, taken from cadaver donor to replace insulin.
- It can be combined with kidney transplantation to patients who have diabetes with end stage kidney disease.
- Donor criteria are individuals without pancreatitis.
- Entire pancreas with duodenum (Lillehei) or part of the pancreas (body and tail of the pancreas) can be transplanted.
- It is placed in the ***right iliac fossa*** with anastomosis done between portal vein and iliac vein, duodenum fixed to bladder.
- Graft take up is 60-70%.

Complications

Graft pancreatitis, pancreatic leak, bleeding, urinary infections like cystitis, failure.



Fig. 1.533: Pancreatic transplantation with duodenum and small bowel to achieve adequate exocrine function. Exocrine function is achieved immediately; endocrine (insulin) function is achieved after few days.

Isolated Pancreatic Islet Transplantation

Islets of Langerhans are obtained by mechanical disruption of pancreas by injecting collagenase into the pancreatic duct. Tissue disrupted is collected and purified by density gradient centrifugation. These islet cells are injected into the liver through portal vein. Islet cell rejection is prevented by covering them with semipermeable membrane which prevents antibodies reaching islet cells but allowing insulin to get secreted. By this method animal pancreatic islet cells transplantation is also under trial.



Fig. 1.534: Pancreatic transplantation

SMALL BOWEL TRANSPLANTATION

- Indication is short bowel syndrome following massive resection, atresia, necrotising enteritis, Crohn's disease.
- Bowel anastomosis with a stoma (ileostomy) is usual method.
- As small bowel is rich in lymphoid tissue, graft versus host reaction is a major problem. So graft take up is poor.
- It is an immunological challenge even though technically easier.

GRAFT REJECTION

1. **Hyperacute** rejection is due to antibody reaction which occurs within minutes of vascularization of the graft
2. **Acute** rejection results due to cell mediated immunity, occurring in a few days to first 3 months of transplant. It responds well to steroids and immunosuppressants
3. **Chronic rejection** occurs in 12 months after transplant, is not very common. It is due to late vasculitis. When it occurs, responds very poorly to steroids or other drugs. It is common type

If there were no obstacles, there would have been no achievements.

DIALYSIS

It is technique for the removal of waste product of metabolism, normalisation of plasma electrolytes and removal of plasma water.

Types

1. Peritoneal dialysis.
2. Haemodialysis.

Peritoneal Dialysis

Indications

1. Acute renal failure until renal function recovers.
2. Chronic renal failure until long term dialysis is instituted.

Contraindications

1. Abdominal surgery.
2. Hypercatabolic states.
3. Infection.
4. Pre-existing malignancy.

Insertion of Catheter

A rigid plastic catheter is inserted through the abdominal wall into the peritoneal cavity using a trocar through a small cut made in the skin under L/A. Catheter is bound to abdomen.

Dialysis is done using sterile dialysate solution instilled into and drained out of abdomen.

Complications

- Leakage
- Pain—Short lasting, mild
- Peritonitis
- Membrane failure
- Hernia

Continuous ambulatory peritoneal dialysis (CAPD) is the preferred method of dialysis in some centre.

Haemodialysis

Indications

- Acute renal failure.
- Chronic renal failure.
- Acidosis.
- Electrolyte disturbance.
- Intoxication.
- Uraemia (pericarditis and polyneuropathy due to uraemia are absolute indications).

Haemodialysis requires access to circulation which is achieved by creating a fistula between the radial artery and the cephalic vein at the wrist *(Cimino fistula)*. Here dialysis occurs in a dialysing machine across a semipermeable membrane (usually cellulose membrane).

Complications

- Access site—arterial and venous stenosis, thrombosis, infection.
- Hypotension.
- Dyspnoea.
- Bleeding (due to dysfunctional platelets due to uraemia and due to heparin use).
- Disequilibrium syndrome.



Fig. 1.535: Patient with CRF undergoing haemodialysis using a dialysis unit.



Figs 1.536A and B: Arterio-venous fistula between radial artery and cephalic vein at wrist is done to attain increased venous engorgement and arterialisation so as to achieve rapid blood flow which is necessary for haemodialysis. Patient with chronic renal failure who requires regular haemodialysis needs this.

Even though repeated dialysis (in CRF, at least twice a week is needed) helps, patient needs repeated blood transfusions, which will lead in to haemochromatosis/ iron overload. Patient should be given erythropoietin injection 3,000 units twice weekly to prevent repeated blood transfusions. But it is expensive. Transplantation is the best answer eventually, in all these individuals.

CIMINO FISTULA

It is an arterio-venous fistula created for *haemodialysis.* Usually at wrist, radial artery is anastomosed to cephalic vein side-to-side and a created good fistula shows continuous thrill and bruit, with increased venous engorgement along with hyperdynamic circulation. At the ankle, often fistula is created between posterior tibial artery and saphenous vein; in the thigh between femoral artery and long saphenous vein. Distal gangrene is not common.

Complications

Infection, bleeding, hyperdynamic circulation.

Self-assessment Questions

- Cyclosporin A.
- Cadaver donor.
- Donor criteria.
- Renal transplantation.
- Cimino fistula.
- Immunosuppressants after transplantation.

Success is never final and failure is never fatal; its courage that counts.

Stings and Bites

Snake bite
Spider bite
Bee bite
Mammalian bite

SNAKE BITE

Snakes belong to Crotalidae, Elapidae and Viperidae family. Common poisonous snakes are cobra, krait and viper.

Common snakes are cobra, Russell's viper, saw scaled viper, pit viper, krait.

It causes renal failure, pulmonary oedema, cardiac complications and neurological problems.

Clinical Features

Local

- Burning pain, oedema and erythema.
- Swelling, echymoses and haemorrhagic bullae.
- Tissue necrosis, ulceration and gangrene.

Systemic

- Weakness, peri-oral paraesthesia, muscle twitching
- Shock.
- Pulmonary oedema.
- Renal failure
- Neurological manifestations
- Bleeding tendency.

Vipers affect multiple organs and soft tissues. Cobra and coral snakes are neurotoxic.

Investigations

- Blood count.
- Coagulation studies like bleeding time, clotting time and prothrombin time.
- Blood urea and serum creatinine
- Serum electrolytes.
- Creatine phosphokinase [CPK].
- Urine analysis for RBCs, albumin, myoglobin
- PO_2 and PCO_2 assessment.

Management

First Aid

- Reassurance.
- Immobilisation.
- The site has to be incised and cleaned.
- Tourniquet to *occlude lymphatics* only but not venous or arterial circulation.
- The snake has to be identified.
- The patient must be transferred to proper medical centre as early as possible.
- The bite wound is identified and assessed.
- It is thoroughly cleaned with debridement.
- *Polyvalent antisnake venom* (against cobra, krait, vipers) should be given. It should be given earliest within 4-24 hours.

  Dose is 20-150 ml depending on the type, severity and age of the individual. It is dissolved in normal saline and given as IV infusion in 500 ml saline with


Snake venom secreted from saliva of the snake parotid
Peptides
Enzymes
Other chemicals
Damage endothelium of the vessel
Oedema and hypovolaemic shock
Protease l-amino acid Oxidases
Tissue necrosis
Hyaluronidase
Spread of venom through tissues
Phospholipase A2
Damage RBC's and muscle cells (Myotoxic)
Alters coagulation, platelet function, fibrinolysis, vascular integrity changes, DIC
Haemorrhagic episodes

20 drops/minute as flow rate. If the snake has been identified monovalent serum is better and more potent.
- Tetanus toxoid.
- IV fluids, blood transfusion and plasma.
- Antibiotics.
- Urine output measurement.
- Monitoring by regular checking of blood urea, serum creatinine and bleeding and clotting time.
- In cobra bite, there is neuromuscular blockade and paralysis occurs. So *neostigmine* should be given 0.5 mg IV every half hourly and later repeated as required. It is given along with 0.6 mg of atropine.
- In viper bite DIC is common. So heparin is given as 10,000 to 15,000 units loading dose and later 5,000 units as maintenance dose 8th hourly.
- Human fibrinogen, whenever required.

Complications of Snake Bite

- Cellulitis and gangrene of the part.
- Deep venous thrombosis [DVT].
- Pancytopenia.
- DIC and haemorrhage.
- Neurological complications.
- Septicaemia.
- Renal failure.
- Marjolin's ulcer.

SPIDER BITE

Types

1. *Black Widow Spider Bite*
    - It causes neurotoxicity.
    - It causes muscle spasms, pain and abdominal cramp and rigidity.
    - Hypertension, tachycardia and diaphoresis are the other features.
    - Its effects last for 2-3 days.
    - Cleaning the wound, antibiotics, antihistamines, specific antivenins are the line of treatment.
2. *Brown Spider Bite*
    - It releases sphingomyelinase-D which causes necrosis of the skin and haemolysis.
    - Local effects include skin rash, blister formation, necrosis of the skin and extensive ulceration.
    - Systemic effects are anaphylaxis, arthralgia, thrombocytopenia, haemolysis and renal failure.
    - Often it can be life-threatening especially in children and elderly.
    - The effects last for 2-3 weeks.
    - Wound debridement, antibiotics, antihistamines, steroid therapy, antivenins and management of systemic complication.

BEE BITE

Honey bee has got barbed stinger with two lancets. These lancets get attached to human skin to release the venom. Bee dies after bite.

Wasps: Yellow jacket wasps are more aggressive.

Bee venom contains dopamine, histamine, neurotoxin and toxic peptides.

Clinical Features and Management

- Allergic reactions.
- Anaphylaxis.
- Pain in the local region, oedema, pruritus, flushing.
- Hypotension, laryngeal oedema, bronchospasm.
- Muscle spasm, convulsions.
- Renal failure in severe cases.
- Soda bicarbonate is used to neutralise the bee venom.
- Antibiotics and antihistamines.

MAMMALIAN BITE

- It includes human bites also.
- Infection rate is more in mammalian bites.
- Proper wound toileting is very important.
- Within 12 hours, incised wound is closed primarily.
- All lacerated wounds and wound which is seen after 12 hours is left open. Wound is closed secondarily.
- Antibiotics are must in all mammalian bites.
- Human bite is very dangerous bite.

Self-assessment Questions

- Treatment of snake bite.
- Complications of snake bite.
- Spider bite.

Awareness of change is important and equally acceptance of it also.

Pain

Pain is a subjective one and is difficult to assess and quantify. Pain perception varies from person-to-person and from time-to-time.

- It can be physical or mental
- It can be localised or diffused
- It can be acute or chronic
- It can be intermittent or persistent
- It can be mild or severe

Pain Pathway

Pain receptors in the skin
↓
Neurotransmitters of pain like substance P or peptides are activated
↓
Sensory nerves
↓
Posterior horn of spinal cord
↓
Spino thalamic tract
↓
Thalamus
↓
Cerebrum
↓
Pain perception

GATE CONTROL THEORY

Gate control system is located at the junction of first and second neuron. Large diameter 'A' fibre is stimulated by temperature and touch. Fine 'C ' fibre is stimulated by pain. If 'A' fibre once gets stimulated, blocks the gate mechanism, then pain from 'C' fibre cannot pass through the gate to reach the brain for perception.

Pain modulators like endorphins and opioid peptides in brain and spinal cord inhibit the release of substance 'P'.

Causes of Pain

- Inflammatory causes due to any infection or infestations.
- Hypoxia due to poor blood supply like in myocardial infarction, peripheral vascular disease.
- Trauma.
- Obstruction like intestinal obstruction.
- Colicky pain like ureteric, biliary, intestinal.
- Compression over nerve roots like in inter vertebral disc prolapse.
- Advanced malignancies cause severe distressing pain, which requires proper pain control.
- Ulcers, perforation, peritonitis, abscess formation are all other causes.

Clinical Assessment of Pain

- Its severity, nature, cause should be assessed.
- Cause should be thoroughly analysed by doing all investigations like haematocrit, sinology, CT scan, culture of the fluid like pus, blood.

Reasons to control postoperative pain/acute pain

- Uncontrolled pain causes tachycardia, hypertension and vasoconstriction
- Abdominal (upper abdominal mainly) and thoracic wound pain restricts the respiration causing tachypnoea, altered respiration, coughing, chest infection, pneumonia
- Persisting pain causes restricted movements, deep venous thrombosis and its problems, bed sores
- Pain delays the recovery and also causes psychological trauma to the patient

Management of Pain

- Correct the cause like removal of renal stone, cholecystectomy for gallstones.
- Analgesics.
- Surgical removal of tumour.
- Injection of phenol or alcohol.
- Electric stimulation, massaging, infrared therapy, wax bath.
- Proper physiotherapy.
- Hormone therapy.
- Injection to ganglion like in trigeminal neuralgia.
- Chemotherapy for malignancies.
- Radiotherapy.
- Sympathectomy for vascular diseases, causalgia.
- Cordotomy for severe pain in case of advanced tumours.
- Mental relaxation.
- Attending pain clinic.
- Continuous epidural anaesthesia/analgesia using opioids.
- *Patient controlled analgesia* (PCA) is injecting opioids through epidural route or intravenous route by patient himself after training him.
- Intravenous infusions of the analgesia.

Pain may be –

- Acute pain.
- Chronic pain due to malignancy.
- Chronic pain due to benign disease.

Acute pain	*Drugs/opioids/epidural anaesthesia/drug infusion*
Chronic pain due to malignancy	First level – simple analgesics (aspirin, paracetamol, NSAIDs, tricyclic antidepressants) Second level – intermediate opioids codeine, tramadol, dextropropoxyphene Third level – strong opioids like oral morphine, intravenous morphine, subcutaneous diamorphine, epidural diamorphine. Analgesic infusion is also useful. Neurolytics are used whenever there is limited life expectancy. Other methods are - Subcostal phenol injection for rib secondaries/celiac plexus block using alcohol/intrathecal hyperbaric phenol/percutaneous anterolateral cordotomy/pituitary ablation/hormone ablation/palliative radiotherapy/steroids/flecainide therapy
Chronic pain in benign disease	Local anaesthetics/steroid injections/nerve stimulation like acupuncture/nerve decompression/pain due to sympathetic overactivity is corrected by – IV pentolamine (alpha adrenergic block), stellate ganglion block, block using guanethidine, percutaneous chemical lumbar sympathectomy using phenol. Other methods for chronic pain are - paracetamol/NSAIDs/antidepressants/opioids/carbamazepine/ neuroablative surgeries

Drugs for Pain

Drugs can be given orally, intramuscularly, few intravenously, intrathecally, per rectally as suppositories, sublingually.

Narcotic Analgesics

- Morphine 10-15 mg. Very useful in intractable pain. It can cause nausea, constipation, and respiratory depression. Its action is neutralised by naloxone.
- Pethidine 50-100 mg IM.
- Diamorphine 5-10 mg. It is used only in intractable pain.
- Pentazocine 30-60 mg.
- Dihydrocodeine.
- Codeine phosphate is commonly used after intracranial surgery. It should not be given intravenously as it may precipitate severe hypotension. Codeine also causes constipation.
- Bupremorphine.

Non-narcotic Drugs

- Aspirin.
- Ibuprofen.
- Naproxen.
- All these NSAID's cause gastric irritation and may risk the gastric bleeding. NSAIDs are non-specific cyclo-oxygenase inhibitors. So gastric protection and platelet function are lost. Rectal diclofenac as suppository is good analgesic.
- Paracetamol is effective analgesic and antipyretic agent. It is relatively less common to cause gastric bleeding.

Note: Specific COX2 inhibitors are contraindicated in ischaemic heart disease.

Other Drugs

- Anticonvulsants.
- Antidepressants, anxiolytics.
- Carbamazepine for neuralgia.

Success is dependent upon the glands—sweat glands.

2

Faciomaxillary Diseases

Diseases of the palate
Orthopantomogram (OPG)
Cleft lip and cleft palate
Maxillofacial injuries
Zygomatic complex fracture
Fracture of the mandible
Preauricular sinus
Jaw tumours
Epulis
Ameloblastoma
Dentigerous cyst
Dental cyst
Alveolar abscess
Cherubism

DISEASES OF THE PALATE

- Cleft palate.
- *Torus palatinus*—a bony hard swelling in the centre of the hard palate.
- Nasopalatine cysts.
- *Epstein's pearls*—at the junction of soft and hard palates, in the midline, in infants due to retained developmental cell rests.
- Apical cyst or abscess.
- Minor salivary gland tumour—commonest site is palate.
- Maxillary tumour extending into the palate.
- Squamous cell carcinoma of the palate.
- Gummatous perforation in the middle of the palate seen in congenital syphilis.
- Perforation of the palate anywhere in carcinoma palate.

ORTHOPANTOMOGRAM (OPG)

It is a plain X-ray of the mandible which shows the whole of mandible in a single plane. It is better than X-ray mandible lateral view as it highlights proper dentition, inner and outer plates of mandible and joints. It is like a rotational tomogram.



Figs 2.1A and B: Orthopantomogram is being taken and also picture showing OPG X-ray.

Indications

a. Jaw tumours—Adamantinoma, dental cyst, dentigerous cyst, osteoclastoma.

b. Osteomyelitis of the mandible.
c. Fracture mandible.

CLEFT LIP AND CLEFT PALATE

Development of Face

Face develops from median nasal process, lateral nasal process, maxillary process, mandibular arch, globular arch, olfactory pit and eye. Any change in the development or fusion of these arches leads to formation of different types of cleft lip or cleft palate.

Aetiology

- Familial—more common in cleft lip or combined cleft lip and palate. (Risk is 1:25 live births).
- Protein and vitamin deficiency.
- Rubella infection.
- Radiation.
- Chromosomal abnormalities.
- Maternal epilepsy and drug intake during pregnancy (steroids/eptoin/diazepam).

Classification

I. *Cleft lip alone*: Unilateral.
Bilateral.
Median.

II. *Cleft of primary palate (in front of incisive foramen) only:*
  a. Complete - means absence of pre-maxilla.
  b. Incomplete - means rudimentary pre-maxilla.
    i. Unilateral.
    ii. Bilateral.
    iii. Median.

III. *Cleft of secondary palate (behind the incisive foramen) only:*
  a. Complete – nasal septum and vomer are separated from palatine process.
  b. Incomplete.
  c. Submucous.
  It can be - Cleft with soft palate involvement.
  - Cleft without soft palate involvement.

IV. *Cleft of both primary and secondary palates.*

V. *Cleft lip and cleft palate together.*

Defect is often associated with other congenital anomalies of cardiac, gastrointestinal, neurological system, *Pierre-Robin syndrome* (most commonly associated syndrome with features of isolated cleft palate, retrognathia, posteriorly displaced tongue), *Klippel-Feil syndrome*, *Stickler's syndrome* (eye, skeletal, muscular, cleft), *Shprintzen's syndrome* (cardiac and cleft), *Down's syndrome*, *Treacher-Collin's syndrome*, *Apert's syndrome* and trisomy.

Cleft lip

- *Central*—rare. In upper lip. Between two median nasal processes. (*Hare lip)*
- *Lateral*—maxillary and median nasal process, *commonest*; can be unilateral or bilateral
- *Incomplete* cleft lip does not extend into nose
- *Complete* cleft lip extends into nasal floor
- *Simple* cleft lip is only cleft in the lip
- *Compound* cleft lip is cleft lip with cleft of alveolus



Fig. 2.2: Central cleft lip (Hare lip, Type I cleft lip-It is rare)



Fig. 2.3: Lateral type of cleft lip (Type II variety- it is commonest). It is due to imperfect fusion of maxillary process and median nasal process. It can be unilateral or bilateral.

LAHS classification of cleft disorders

- 'L' for lip, 'A' for alveolus, 'H' for hard palate, 'S' for soft palate
- *Capital* 'LAHS' for 'complete' type
- *Small letters* 'lahs' for 'incomplete type'
- *Asterisks* 'lahs' for microclefts
- 'LAHSHAL' for bilateral clefts

Surgery is a science as well as an art.



Fig. 2.4: Wide cleft palate and lip – complete type in a child.



Fig. 2.6: Unilateral cleft lip, lateral type which is commonest.

Incidence

- Common in Caucasians.
- In 75% of cases it is unilateral. Commonly occurs on the left side (60%).
- In 50% of cases it is combined cleft lip and palate. Incidence is 1:600 live births. Common in boys.
- In 15-25% of cases it is cleft lip alone.
- In 25-40% of cases it is cleft palate alone. Incidence is 1:1000 live births. More common in girls.



Fig. 2.7: Bilateral cleft lip involving palate.



Fig. 2.5: Bilateral cleft lip.



Fig. 2.8A



Fig. 2.8B

Figs 2.8A and B: Cleft lip and cleft palate in an adult.



Figs 2.9A and B: Cleft palate only. Lip is normal. Pre-maxilla is not involved.

Problems in Cleft Disorders

- Difficulty in sucking and swallowing. This is commonly observed in cleft palate than in cleft lip.
- Speech is defective especially in cleft palate, mainly to phonate B, D, K, P, T and G.
- Altered dentition or supernumerary teeth.
- Recurrent upper respiratory tract infection.
- Respiratory obstruction (in Pierre Robin syndrome)
- Chronic otitis media, middle ear problems.
- Cosmetic problems.
- Hypoplasia of the maxilla.
- Problems due to other associated disorders.

Treatment for Cleft Lip

Millard criteria is used to undertake surgery for cleft lip.

Millard criteria (Rule of ‘10’)

- 10 pound in weight
- 10 weeks old
- 10 gm % haemoglobin

a. *Millard cleft lip repair* by rotating the local nasolabial flaps.
b. Management of associated primary or secondary cleft palate deformity.
c. Proper postoperative management like control of infection, training for sucking, swallowing and speech.
d. Tenninson’s ‘Z’ plasty (Tenninson-Randall triangular flap).



Fig. 2.10: Steps of cleft lip repair.

Principles of cleft lip repair

- “Rule of 10’ should be fulfilled
- Before 6 months it should be operated
- Infection should not be present
- Millard advancement flap is commonly used for unilateral cleft lip repair
- Bilateral cleft lip repair can be done either in single or two stages (with 6 months gap between each stage)
- One stage bilateral cleft lip repair is done using Veau III method/Millard’s single stage/Black method
- Proper markings are made prior to surgery and incision should be over full thickness lip
- Often 1 : 2,00,000 adrenaline injection is used to achieve haemostasis
- Three layer lip repair should be done (mucosa, muscle and skin)
- Cupid’s bow should be horizontal
- Continuity of white line should be maintained
- Vermilion notching should not be there

> *Bleeding gums in uraemia are not so spongy as in scurvy: in fact they may look nearly normal.*
> —Frederic J Wright

Note: *Delaire timing of the cleft surgery* – Unilateral/bilateral cleft lip alone, in one stage operation done in 4-6 months. For Cleft palate alone involving only soft palate, in one stage surgery is done in 6 months. Cleft palate alone but involving both soft and hard palates – soft palate in 6 months; hard palate in 18 months. In combined cleft lip and palate, unilateral or bilateral, in two stages – cleft lip and soft palate in 6 months; hard palate in 18 months.

Cleft Palate



Fig. 2.11: Cleft palate with cleft lip in a child. Child also is suffering from congenital cardiac defects.

- It is due to failure of fusion of the two palatine processes.
- Defect in fusion of lines between premaxilla (developed from median nasal process) and palatine processes of maxilla one on each side.
- When premaxilla and both palatine processes do not fuse, it leads into complete cleft palate (Type I cleft palate).
- Incomplete fusion of these three components can cause incomplete cleft palate beginning from uvula towards posteriorly at various lengths. So it could be Type II a–bifid uvula, Type II b–bifid soft palate (entire length) or Type II c –bifid soft palate and posterior part of hard palate (but anterior part of hard palate is normal).
- Small maxilla with crowded teeth, absent/poorly developed upper lateral incisors.
- Bacterial contamination of upper respiratory tract with recurrent infection is common.
- Chronic otitis media with deafness may occur.
- Swallowing difficulties to certain extent and speech problems can occur.
- Cosmetic problems can occur.



Fig. 2.12: Complete cleft palate Type I.



Fig. 2.13: Cleft palate Type II a—bifid uvula.



Fig. 2.14: Cleft palate Type II b—bifid soft palate (entire soft palate).



Fig. 2.15: Cleft palate Type II c—bifid soft palate entire length with cleft of posterior hard palate (anterior palate is normal).

Treatment for Cleft Palate

Criteria for surgery

- 10 kg weight
- 10 months of age (10—18 months)
- 10 gm % haemoglobin

- Cleft palate is usually repaired in 12—18 months. Early repair causes retarded maxillary growth (probably due to trauma to growth center and periosteum of the maxilla during surgery if done early). Late repair causes speech defect.
- Both soft and hard palates are repaired.
- Abnormal insertion of tensor palati is released. *Mucoperiosteal flaps* are raised in the palate which is sewed together. If maxillary hypoplasia is present, then *osteotomy of the maxilla* is done. With *orthodontic help teeth extraction and alignment* of dentition is done.
- Regular examination of ear, nose and throat during follow up period.
- Postoperative speech therapy.
- Whenever complicated problems are present, staged surgical procedure is done.
- *Wardill- Kilner push back operation*—by raising mucoperiosteum flaps based on greater palatine vessels.
- *Secondary management* –
  - Hearing support is given using hearing aids if defect is present; control of otitis media.
  - Speech problems occur due to velopharyngeal incompetence; articulation problems also can occur – speech therapy is given. It is corrected by pharyngoplasty, veloplasty, speech devices.
  - Dental problems like uneruption, unalignments are common. They should be corrected by proper dentist opinion, and reconstructive surgery.
  - Orthodontic management with alveolar bone graft, maxillary osteotomy – done in 8-11 years of age.
  - Veloplasty, dental implants, rhinoplasty, orthognathic surgeries, etc.

Principles of palatoplasty

- Timing is between 10—18 months
- Mucoperiosteum flap is raised
- Palatal defect is closed using 3 layers—nasal, muscle and oral layers
- Hook of pterygoid hamulus is fractured to relax tensor palate muscle to relieve tension on suture line


Cleft palate with palatine artery
Cleft palate repair V-Y palatoplasty

Fig. 2.16: V-Y palatoplasty

MAXILLOFACIAL INJURIES

It may be due to road accidents, assaults, bullet injuries or sport injuries.

Classification

Fracture in maxillofacial region can be grouped as—

- Fracture lower third that comprises mandible.
- Fracture middle third that comprises maxilla, zygoma and nose.
- Fracture upper third of the face involving part of the orbit, frontal bones.

Maxillofacial fracture also can be grouped as—

- Fractures of the face which do not involve the dental occlusion – fractures of zygoma and nose.
- Fracture which involves the dental occlusion – fracture mandible and maxilla.

> *Preauricular ulcer is a late stage of an abscess due to a congenital preauricular sinus. It refuses to heal for infection is maintained from the sinus.*
> — Francis AR Stammers



Fig. 2.17: Relation between middle third and cranium in 45° plane.



Fig. 2.18: Posterior gagging of occlusion due to backward displacement of fracture segment in middle third fracture.

Soft-tissue Injuries

- Lacerations, contusions, cut wounds etc.
- Eye-lid injuries with black eyes.
- *Facial nerve injury*: Primary repair is required.
- *Parotid duct injury*: Here primary anastomosis of the injured duct is done, with a fine polythene cannula as a stent kept inside the duct which will be removed in 14 days.
- *Lacrimal apparatus injury*: Here the duct is sutured with a fine nylon thread in the canaliculus which is kept for 3 months.

Injuries to the Facial Bones

- *Fracture nose*: Nasal bones are most commonly injured bones in face. Patient presents with pain and swelling in the nose with deviation and displacement. Here reduction of the fractured nasal bones and nasal septum under general anaesthesia is done. Later position is maintained by nasal packs from inside (which is removed in 7 days) and by a nasal plaster from outside (which will be kept for 14 days). Procedure is done using Walsham's and Asch's forceps.



Fig. 2.19: Soft tissue injury face involving upper lip.

- Injuries to the *maxilla.*
- *Zygomatic* bone injuries.
- *Mandibular* bone fracture and mandibular dislocation.
- *Orbital bone fracture*: Presents with diplopia, enophthalmous, infra-orbital nerve sensory loss.
- Infraorbital echymosis of the orbit is called as *Panda sign*.

Clinical Features

- Localised swelling due to haematoma.
- Facial oedema.
- Bleeding with open wounds.
- Asymmetry which is clinically confirmed by observing supraorbital ridges, nasal bridge.
- Localised tenderness.
- Step deformity.
- Trismus.
- Diplopia.
- Features of associated injuries like intracranial, abdominal or thoracic injuries.

Investigations

- X-ray face.
- CT scan of head.

General treatment for facio-maxillary injuries:

- Suturing of soft tissues
- Airway maintenance
- Control of bleeding
- Pain relief
- Control of infection
- Treating the individual fractures

PRIMARY CARE (EARLY CARE) IN MAXILLOFACIAL INJURIES

Injury can be isolated single bone fracture or multiple bone fractures. Real primary care is usually not required except when there is mechanical respiratory block causing air-way obstruction.

Respiratory Obstruction

Causes

- Oro-nasal airway block can occur by blood, clot, vomitus, foreign body, dentures, teeth, saliva, bone pieces etc.
- Backwards falling of tongue can cause obstruction of the nasopharynx and oropharynx. It is common in bilateral mandibular fracture.
- Occlusion of the nasopharynx and oropharynx can occur in fracture maxilla with posterior and inferior displacement.
- Haematoma in floor of the mouth or posterior oral cavity can cause airway block.
- Oedema of larynx/tongue/posterior third of oral cavity/pharynx.
- Surgical emphysema.

Treatment

- Cleaning of the oral and nasal cavities to remove obstructing agents like clot, dentures, teeth or bone. Gauze swabbing and suction.
- Fallen tongue should be placed forward using finger and often temporary alignment of the occlusion may be needed.
- Maxillary disimpaction is done when needed in fracture maxilla.
- Positioning of the patient is important. Prone/semiprone position with head towards one side is the safest position. If this is not possible, then patient may be placed in sitting position which also improves the breathing. Placing the patient flat on his back in supine position should be avoided as much as possible.
- Tracheostomy should be done when needed without delay as it will be life saving by facilitating the easy airway and breathing.

Control of Pain

Analgesics like NSAIDs are used to control pain. Morphine and analogues are not used as they may suppress the respiration. They may mask the pain of alarming severe injury in chest, abdomen or other areas, or they may interfere with pupillary reaction and neurological signs in the presence of intracranial injuries.

Control of Infection

Antibiotics are needed. Tetanus toxoid and often antitetanus globulin (ATG 3000 units IM) are required.

Haemorrhage in Maxillofacial Injuries

Haemorrhage in maxillofacial injuries is usually not life threatening. But it should be identified and controlled properly. In association with other internal injury, such haemorrhage may be important to cause the circulatory failure.

Haemorrhage may be due to—

- Soft tissue bleeding.
- Bleeding from inferior alveolar artery, palatine vessels.
- Nasal bleeding.

Control of Bleeding

- Blood transfusion, IV fluids, resuscitation.
- Nasal packs.
- Fracture correction.
- Ligation of the bleeder.
- Cauterisation.
- Packing the area.
- Under running the bleeding field.
- Embolisation.
- External carotid artery ligation above the level of the origin of the superior thyroid artery.

Associated Injuries

All associated injuries should be assessed properly and individually. On priority basis it should be treated.

- Soft tissue injuries.
- Cranial injuries.
- Orbital injuries.
- Intra-abdominal/thoracic/pelvic injuries.

FRACTURE MIDDLE THIRD AREA

It includes-

- Maxillae, zygomatic bones, palatine bones, nasal bones, lacrimal bones, inferior conchae (one on each side).
- The vomer, ethmoid and its attached conchae, pterygoid plates of sphenoid.

> *Ankylosis of mandible joint causes receding of chin giving a characteristic shrew mouse profile.*
>
> —Leon Dufourmentel

Fracture middle third includes fracture maxilla, zygoma and nasal bones.

Fractures not involving occlusion	*Fracture involving occlusion*
Central • Fracture nasal bones and/or nasal septum • Fracture of frontal process of maxilla • Fractures of above two extending into ethmoid-nasoethmoid • Fractures above three which extends into frontal bone – fronto-orbito-nasal dislocation	*Dentoalveolar* *Subzygomatic* • Le Fort-I-low level either unilateral or bilateral • Le Fort II-pyramidal either unilateral or bilateral
Lateral • Fractures involving zygomatic bone, arch and maxilla excluding the dentoalveolar component	*Suprazygomatic* • Le Fort III – high level • Craniofacial disjunction–unilateral or bilateral

Le Fort classification

(*Rene Le Fort* – French surgeon classified these fractures by dropping rocks on the face of the cadavers and later dissected the area for study and research and published paper in 1911)

Types	*Features*
Le Fort I (Guerin's fracture-low level) (floating fracture, horizontal fracture of maxilla) • It runs horizontally above the floor of the nasal cavity involving lower third septum, palate, alveolar process of maxilla and lower third of pterygoid plates of maxilla	• Bleeding from nose • Posterior gagging of occlusion • Upper lip swelling • Palatal ecchymosis • Occlusion derangement • Floating maxilla
Le Fort II (pyramidal fracture) • From the nasal bones at topmost, fracture runs laterally towards lacrimal bones, medial wall of orbit, infraorbital margin, through or medial to infraorbital foramen and backwards below the zygomatico maxillary area through lateral wall of maxillary sinus and pterygoid plates. Zygoma is intact with skull base	• Oedema of middle third face • Both sides circumorbital and subconjunctival ecchymoses • Nasal bleeding/obstruction/deformity • Deformity of face (dish face), diplopia • Retroposition of maxilla with posterior gagging • Limitation of ocular movements, CSF rhinorrhoea • Tenderness and separation of infraorbital margin
Le Fort III (craniofacial disjunction, high level) • Here fracture runs parallel to skull base. It passes through the nasal bone, lacrimal bone, ethmoid bone, optic foramen, inferior orbital fissure, pterygomaxillary fissure and lateral orbital wall with frontozygomatic suture with zygomatic arch	• Lengthening of face • Enophthalmos, ocular level depression • Hooding of eyes, occlusal plane tilting • Entire facial skeleton moves as a single block • Tenderness and separation of suture line • Diplopia • Trismus, teeth mal-alignment *Guerin sign*: Haematoma at greater palatine foramen

Contd...

Contd...



Dentoalveolar
Le Fort I
Le Fort II
Le Fort III

Figs 2.20A to D: Le Fort classification–different types and also dentoalveolar fracture. (*Refer table for details*).



Fig. 2.21: Fixation of the splint to skull. It is often used with gunning splints to fix it to skull.

Clinical Features

- Oedema face, subconjuctival haemorrhage, ocular ecchymosis.
- Bleeding from the nose.
- Diplopia due to trapping of the extra-ocular muscles in the fracture segments.
- Anaesthesia of the cheek.
- Trismus and malalignment of teeth.
- *Guerin's sign*: Haematoma at greater palatine foramen.
- Always patient should be examined and observed for CSF leak and intracranial injuries.



Fig. 2.22: Photo showing bilateral maxillary fracture

Investigations

- CT scan head.
- X-ray skull.

Treatment

- It should be managed in a center for maxillo-facial injuries.
- Antibiotics.
- Tracheostomy.
- Associated zygoma and nasal fractures are reduced first.
- Direct wire suturing of the zygomatico-frontal region.
- Fixation of teeth in occlusion using eyelet wires, bars or cap splints.
- Once reduced, fracture bones are immobilised using extra-oral rods called as *Mount-vernon box frame.*
- Initially intravenous fluids and blood transfusions are required. Later Ryle's tube feeding is done.
- Proper ophthalmic consultation is necessary when there are orbital injuries.

ZYGOMATIC COMPLEX FRACTURE

Classification

- *Simple fracture which is stable and undisplaced*— here fracture line passes across the infraorbital foramen downwards over anterior wall of the antrum.
- *Simple fracture which is displaced medially*. It may be associated with rotation / tilt in vertical axis, either medial tilt or lateral tilt. Infraorbital nerve may get compressed or branches of superior dental nerve may get torn.
- *Unstable fracture with rotation around horizontal axis* with medial tilt or lateral tilt.
- *Comminuted fracture* extending into the floor of the orbit.
- *Fracture of the zygomatic arch* causes a localised depression of the arch which displaces medially and tends to impinge on the coronoid process of the mandible.
- *'Blow-out' fracture* of the orbit is due to direct blunt trauma on the eye-ball causing depressed comminuted fracture of the orbital floor with herniation of the orbital fat into the antrum.
- *Enbloc dislocation of zygomatic bone* medially/ inferiorly/postero-laterally.

The first two letters of goals are go.....



Figs 2.23A and C: Diagrams showing different types of zygomatic fractures.

Clinical Features

- Swelling and bruising in the cheek with sub-conjuctival haemorrhage.
- Flattening of the cheek prominence.
- Step in the margin of the bony orbit at the infraorbital foramen.
- Sensory loss over the supply of the branches of the superior orbital nerve— teeth on the affected area are anaesthetic on percussion.
- Sensory loss over the supply of the infraorbital nerve usually over infraorbital region, upper lip and alar region of the nose-common.
- Enophthalmos is due to herniation of the orbital fat across the fracture floor of the orbit into the antrum
- Diplopia is due to entrapment of the inferior rectus muscle preventing upward rotation of the eye-ball while looking up.
- Trismus with marked restriction of the lateral movements.
- Epistaxis, lowering of pupil level.
- Infraorbital ecchymosis of the orbit is called as *Panda sign.*

Investigations

- 30° occipitomental X ray is used commonly but often obliquity of X-ray may be increased to 60°. In X-ray, findings observed are—
  - Fracture line near infraorbital foramen, zygomatic arch and lateral wall of the antrum.
  - Orbital floor line for fracture.
  - Opacity in the antrum due to blood.
- CT scan is done to see orbital depression and herniation of orbital fat.

Treatment

- *Every patient with zygoma fracture need not require surgical correction.*
- Need for surgery is decided based on clinical features.

Indications for surgery are—

- Infraorbital anaesthesia, trismus
- Diplopia, enophthalmos
- Flattening of the cheek
- Undisplaced fracture with infraorbital anaesthesia

Surgical Approaches

1. *Closed reduction of the zygomatic arch through Gillies temporal approach—*

An oblique skin incision of 2 cm length temporal is made between the two branches of the superficial temporal artery. Care is taken to avoid injury to artery. Whitish glistening temporal fascia is identified and incised. Zygoma elevator is introduced beneath the zygoma and fracture fragments are manipulated and elevated into proper position. An audible snap is heard when fracture gets reduced into position. Reduced, dis-impacted fracture is always stable. Additional corrections in other parts can be done by different leverage actions of the elevator. Orbital rim, zygomatic arch are palpated for completion of correction. Skin wound is closed with sutures.

Elevators used are Bristow's periosteal elevator, Rowe's zygomatic elevator.



Fig. 2.24: Technique showing method of temporal reduction using disimpaction forceps.



Figs 2.25A and B: Disimpaction of maxilla using Rowe's disimpaction forceps by downward leverage action.

2. *Internal fixation by open reduction and fixation is needed*

- When fracture is unstable or
- Comminuted or
- Zygoma fracture with middle third fractures.

By proper incisions infraorbital and zygomatico frontal fracture sites are exposed; after open reduction they are fixed using wires/plates and screws.



Fig. 2.26: Fracture zygoma showing open reduction and fixation using wires directly. Two types of incisions are shown depending on the site of the fracture.

3. *Exploration of the orbital floor is necessary whenever there is*

- Comminuted fracture in orbital floor.
- Orbital fat herniation.
- Diplopia with entrapment of the inferior rectus muscle.

FRACTURE OF THE MANDIBLE

Types

I. At the *neck of the condyle* (35%), as it is the weakest point. The condyle is displaced in front and medially often with dislocation. Painful jaw movement is the clinical features. It may be unilateral or bilateral.



Fig. 2.27: Types of mandibular fractures.

II. At the *angle of the mandible*: If fracture is upwards and inwards, it is impacted and undisplaced. So it is a favourable fracture. If fracture is downwards and outwards, it gets displaced and so it is an unfavourable fracture. It needs open reduction using wires.

Many receive advice, only wise profit from it.

III. Fracture *near the mental foramen through the canine fossa*. This fracture causes displacement. Such bilateral fractures can cause pull on digastric and geniohyoid muscles precipitating fall of *tongue backwards which will block the air-way.*

Other Classifications

Classification of the fracture mandible	
Depends on the type	*Depending on the anatomical site*
• Simple • Compound • Comminuted • Pathological • Green stick fracture in children	• Dentoalveolar fracture • Condylar fracture • Coronoid fracture • Fracture ramus of the mandible • Fracture angle of the mandible • Fracture in the body of the mandible • Symphyseal region fracture

Dentoalveolar fracture	
Features	*Management*
• Horizontal fracture below the alveolar margin • Dentoalveolar segment will be freely mobile • Tooth may get split vertically/horizontally • Derangement in occlusion and alignment • Gingival laceration • Bleeding • Infection and late osteomyelitis of mandible	• Look for other injuries in face • X-ray face to see injuries • Dentoalveolar segment reduction and placing jaws in central occlusion position • Stabilisation using inter-dental wires or arch bars • Liquid diet for 3-4 weeks

Guardsman fracture is direct fracture of symphysis and indirect fractures of both the condyles of the mandible. In olden days guards of queen who are in attention position used to faint and fall forward to get these fractures.

Clinical Features

- Pain and tenderness in the lower jaw with bruising over the surface.
- Haematoma in the floor of the mouth is called as *Coleman's sign.*
- Difficulty in opening the mouth, speech and swallowing.


Temporalis
Medial pterygoid
Masster mylohyoid
Digastric
Fracture site
Fracture site

Fig. 2.28: Muscle actions in mandible fracture causing different displacements.


Fracture unreduced
Fracture reduced
Teeth not occluded
Teeth well occluded

Fig. 2.29: Unreduced and reduced fracture mandible.


Fracture coronoid
Dentoalveolar fracture
Condyle fracture
Ramus fracture
Symphyseal fracture
Body fracture
Angle fracture

Fig. 2.30: Different sites of fracture mandible.


Simple Arch Bar Fixation
Cleats
Erich Arch Bar Fixation with cleats

Fig. 2.31: Arch bar wiring. Figure shows both simple and Erich arch bar wiring with cleats to pass wire.

- Anaesthesia of the lower lip due to compression of inferior dental nerve.
- Deranged dental occlusion.
- Step deformity.

Investigations

- X-ray of the mandible.
- Orthopantomogram (OPG).

Treatment

- Antibiotics to prevent formation of osteomyelitis of the mandible.
- Open fixation of the fracture segments using silver wires for 4-6 weeks.
- Fixation by—
  - Interdental wiring.
  - Using arch bars.
  - Silver alloy or plastic caps.
- Only fluid diet for 6 weeks.
- Irrigation wash to the oral cavity to maintain the hygiene.



Fig. 2.32: Circummandibular wiring used in gunning splints.



Fig. 2.33: Interdental wiring. It is commonly used and accepted method of wiring.


Upper border wiring
Fracture site
Lower border wiring
Fracture site

Fig. 2.34: Upper and lower border wiring. It is used to fix the mandibular fractures and is often done together with other fracture fixations in the face.

Rudeness is a weak imitation of strength.



Figs 2.35A and B: Compression plating of a mandibular fracture. Note the different methods.

Complications of fracture mandible

- Obstruction of the airway
- Osteomyelitis of the mandible
- Trismus
- Speech disturbances

DISLOCATION OF THE MANDIBLE

- It occurs at *temporo-mandibular joint.*
- Unilateral dislocation after trauma is common.
- Bilateral dislocation occurs during yawning and it is recurrent.

Clinical features are difficulty in opening the mouth with pain and tenderness over the joint.

Treatment

- Reduction of dislocation under general anaesthesia.
- If there is associated fracture mandible it should be dealt accordingly.

PREAURICULAR SINUS

- It is due to failure of fusion of anterior tubercles of the auricle creating a sinus.
- Often sinus opening gets sealed forming a preauricular cyst which gets infected forming an abscess.
- Sinus can get infected repeatedly, discharging pus through its opening.
- It is often multiple.

Investigations

- Sinusogram.
- Discharge study.

Differential Diagnosis

- Cold abscess.
- Sebaceous cyst.



Fig. 2.36: Preauricular sinus. During excision, methylene blue is injected into the track initially and later it is excised using elliptical incision.

Treatment

Complete excision of the sinus with entire track.

TREACHER-COLLINS SYNDROME

- Mandibulo-facial dystosis
- Hypoplasia of the zygomatic bone and mandible
- Antimangoloid slant to the palpebral fissure
- Coloboma of lower eyelid
- Low ear lobule with deficient middle ears
- Familial—3rd arch syndrome (Mandibulo-facial dysostosis)

JAW TUMOURS



Fig. 2.37A: Jaw tumour (right sided).



Fig. 2.37B: Left sided upper jaw tumour.

Classification

I. ***Swelling arising from the gums:*** (*Epulis*)
  - Congenital epulis.
  - Fibrous epulis.
  - Pregnancy epulis.
  - Giant cell epulis.
  - Myelomatous epulis.
  - Sarcomatous epulis.
  - Carcinomatous epulis.

II. ***Swelling arising from the dental epithelium*** (*Odontomes*)***:***
  - Ameloblastoma.
  - Compound odontome.
  - Enameloma.
  - Cementoma.
  - Dentinoma.
  - Odontogenic fibroma and myxoma.
  - Radicular odontome.
  - Composite odontome.

Cysts arising in relation to dental epithelium:
- Dental cyst.
- Dentigerous cyst.

III. ***Swelling arising from the mandible or maxilla:***
  - Osteoma and osteoblastoma.
  - Torus palatinus and mandibularis.
  - Fibrous dysplasia.
  - Osteoclastoma (Common in mandible).
  - Osteosarcoma.
  - Secondaries.
  - Giant cell reparative granuloma.

IV. ***Surface tumours:***
  - Tumours from the surface which extend into the jaw.
  - Ossifying fibroma.
  - Osteofibrosis of maxilla.
  - Ivory osteoma of jaw.
  - Leontiasis ossea (diffuse osteitis).
  - Carcinoma extending in to the jaw.

EPULIS

Swelling arising from the mucoperiosteum of gums.

Congenital Epulis

- It is a benign condition seen in a *newborn* arising from gum pads.
- It is a variant of granular cell myoblastoma originating from gums.
- It is more common in *girls.* It is more common in *upper jaw*, common in canine or premolar area.
- It is not a malignant condition.

Clinical Feature

Well localised swelling from the gum which is firm and bleeds on touch.

Treatment

Excision.

Fibrous Epulis

- It is a benign condition, can occur in any individual with caries tooth.

> *Open confession is good for the soul.*

- It is seen in the gum, adjacent to the caries tooth.
- It is commonest type.
- It is fibroma arising from periodontal membrane.

Clinical Features

- Painless, well localised, hard, non-tender swelling in the gum which bleeds on touch.
- Caries tooth adjacent to the lesion.

Differential Diagnosis

Squamous cell carcinoma from the gum.

Investigations

- X-ray jaw.
- Orthopantomogram
- Biopsy from the lesion.

Treatment

Excision with extraction of the adjacent tooth.

Pregnancy Epulis

- It occurs in *pregnant women* due to *inflammatory gingivitis*
- Usually during 3rd month of pregnancy.
- *Clinically* it resembles fibrous epulis or pyogenic granuloma.
- It usually resolves after delivery. Otherwise it should be excised.

Myelomatous Epulis

- It is seen in *leukaemic* patients.

Investigated for leukaemia by peripheral smear, bone marrow biopsy.

Treatment: For leukaemia.

Granulomatous Epulis

It is a mass of granulation tissue in the gum around a caries tooth. It forms a localised soft/firm/fleshy mass in the gum which bleeds on touch.

Giant Cell Epulis

Osteoclastoma causing ulceration and haemorrhage of gum

Carcinomatous Epulis

Squamous cell carcinoma of the alveolus and gum presenting as localised, hard, indurated swelling with ulceration.

Fibrosarcomatous Epulis

Fibrosarcoma arising from fibrous tissue of the gum.

Epulis

- Congenital
- Fibrous-commonest
- Granulomatous
- Pregnancy
- Carcinomatous
- Myelomatous
- Fibrosarcomatous

Odontogenic tumours

Epithelial tumours

- Ameloblastoma
- Calcifying odontogenic tumour
- Odontogenic adenomatoid tumour
- Composite odontoma, which may be either complex or compound. It is odontogenic hamartoma contains all 4 layers, dentin, enamel, cementum and pulp

Mesodermal tumours

- Odontogenic fibroma, myxoma
- Cementoma, dentinoma

Malignant odontogenic tumours

- Malignant ameloblastoma
- Fibrosarcoma



Fig. 2.38: Large jaw tumour – could be adamantinoma/osteoclastoma.



Fig. 2.39: Orthopantomogram (OPG) X-ray showing unilocular odontogenic tumour in lower jaw.

AMELOBLASTOMA (Adamantinoma, Eve's disease, Multilocular cystic disease of the jaw)

- It arises from the dental epithelium probably from the *enamel/dental* lamina.
- It occurs commonly in *mandible* or maxilla.
- Occasionally it is seen in the base of the skull in relation to Rathke's pouch or in tibia.
- Histologically it is a variant of *basal cell carcinoma*.
- It is a *locally malignant tumour.*
- It neither spreads through lymph node nor through blood. Hence it is *curable.*
- It is usually unilateral.
- It can occur in a pre-existing dentigerous cyst.
- It is usually multilocular cystic spaces but can be unilocular also.
- Histologically cords of odontogenic epithelium, connective tissue, stellate reticulum like cells with columnar ameloblast like cells.

Clinical Features

- Swelling in the jaw usually in the mandible near the angle which attains a large size, extending to vertical ramus—*Eggshell crackling.*
- It is a gradually progressive, painless swelling which is smooth and hard with intact inner table (enlarges externally).
- Lymph nodes are not enlarged.
- Outer table expansion.
- It is common in males, common in 4th to 5th decades.

Differential Diagnosis

- Osteoclastoma of the mandible: Here inner table is not intact.
- Dentigerous cyst.
- Dental abscess.
- *Giant cell reparative granuloma (Jaffe's tumour)* – It is a swelling which occurs due to haemorrhage within the bone marrow. It contains vascular stroma, collagen and connective tissue cells. It is common in women. It causes painless enlargement of jaw. It can be treated by calcitonin (100 units / 0.5 mg subcutaneously daily for 12 months) or surgical curettage.

Investigations

- Orthopantomogram (OPG) shows multiloculated lesion—*Honey coomb* appearance.
- Biopsy from the swelling.



Figs 2.40A and B: X-ray (two different X-rays) showing typical honeycomb/multiloculated features of adamantinoma. (*Courtesy by Dr Veena Jagadish MDS*).

Treatment

- Segmental resection of the mandible. OR
- *Hemimandibulectomy with reconstruction of the mandible*.

Note: Curettage and bone grafting should not be done. It is a curable condition.

Recurrent adamantinoma can spread through blood into lungs.

Attitudes are more important than facts.

DENTIGEROUS CYST
(Follicular odontome)

- It is a unilocular cystic swelling arising in relation to the dental epithelium from an unerupted tooth.
- Common in lower jaw, but can also occur in upper jaw.
- It occurs over the crown of unerupted tooth. Commonly seen in relation to premolars or molars.
- It causes expansion of outer table of the mandible.

Clinical Feature

Painless swelling in the jaw which is smooth and hard.

Differential Diagnosis

- Adamantinoma.
- Dental cyst.
- Osteoclastoma.



Fig. 2.41: Dentigerous cyst.

Complication

It can turn into *adamantinoma.*



Fig. 2.42: Orthopantomogram showing dentigerous cyst.

Investigation

Orthopantomogram. Tooth within the cyst, which is well-defined.

Treatment

- If it is small, excision of the cyst is done.
- If it is large, initial marsupialisation and later excision is done.
- *Unerupted tooth should be extracted.*

DENTAL CYST
(Radicular cyst, Periapical cyst)

- It occurs under the root of the chronically infected dead erupted tooth.
- It is lined by squamous epithelium derived from epithelial debris of *Mallassez.*

Clinical Feature

As a smooth, tender swelling in the jaw in relation to caries tooth which causes expansion of the jaw bone.



Fig. 2.43: Dental cyst.

Complication

It can cause osteomyelitis of the jaw.

Differential Diagnosis

Dentigerous cyst.

Investigation

Orthopantomogram.

Treatment

- Antibiotics.
- Drainage or excision of the cyst with extraction of the infected tooth is done.

Differences between dental cyst and dentigerous cyst

	Dental cyst	*Dentigerous cyst*
a. Site of occurrence	Erupted tooth under the root	Over the crown of an unerupted tooth
b. Infection	Common	Not common
c. Complication	Osteomyelitis	Adamantinoma
d. Treatment	Excision and extraction of tooth	Marsupialisation, excision and then extraction of tooth

Curable malignancies
- Adamantinoma
- Basal cell carcinoma
- Verrucous carcinoma
- Papillary carcinoma thyroid
- Marjolin's ulcer
- Carcinoma colon

ALVEOLAR ABSCESS (Dental abscess)

It is due to spread of infection from root of the tooth into the periapical tissue. Initially, it forms periapical abscess which later spreads through the cortical part of the bone into the soft tissues around forming an alveolar abscess.

Bacteria: Staphylococci, streptococci, anaerobic-bacteria and gram-negative organisms.

Clinical Features

- Deep, throbbing pain in the jaw and adjacent oral cavity with diffuse swelling over the cheek.
- Tender soft tissue swelling in the jaw which eventually bursts spontaneously leading to sinus formation.
- Oedema, pain and tenderness in the floor of the mouth.
- Trismus and dysphagia.
- Fever and features of toxaemia.
- Tender palpable lymph nodes in the neck.



Fig. 2.44: Tooth infection causing large dental abscess. It needs antibiotics, proper drainage and tooth extraction. Patient may develop trismus/retropharyngeal infection/ chronic osteomyelitis of the mandible.

Investigations

- X-ray of the mandible or maxilla.
- Discharging pus for culture study.

Complications

- Septicaemia.
- Spread of infection into other spaces like parapharyngeal spaces.
- Chronic osteomyelitis of the jaw with discharging sinuses. It is common in mandible, horizontal process near the mentum. Presents with pain, swelling, discharging sinuses, bone thickening, loose tooth and trismus.
- Sequestrum is commonly seen.

Treatment: Antibiotics, sequestrectomy, mandibulectomy.

Treatment

- Antibiotics.
- Drainage of the abscess under general anaesthesia.
- Extraction of the tooth at a later period.
- Excision of the sinus whenever required.

CHERUBISM

It is an autosomal dominant condition occurs in first year of life.

Pathology

- Giant cell granuloma with fibrous tissues in the jaw.
- It is commonly *bilateral.*
- Commonly seen in *angles of the mandible* and also in maxilla.

Clinical Features

- Diffuse enlargement of maxilla and both sides of the mandible.
- Bulging of the cheek causes pull of the lower eyelid. Hence, child appears like, as if looking upwards.
- Interference of the development and eruption of the teeth.

Treatment

It is a self-limiting disease. Often requires dental care and treatment for proper dentition.

Life is an echo; give the best and get a great deal back.

Pierre-Robin syndrome

- Congenital condition
- Cleft palate alone
- Mandibular hypoplasia
- Cyanotic episodes
- Deficiency in transforming growth factor
- Defective sucking and tongue falling backwards in infants
- Cryptorchidism

Self-assessment Questions

- Cleft lip.
- Cleft palate.
- Treatment for cleft disorders.
- Adamantinoma.
- Fracture mandible.
- Maxillary fracture.
- Treatment of maxillo-facial injuries.
- Dentigerous cyst.
- Dental cyst.
- Follicular odontome.
- Classification of jaw tumours.
- Epulis.

3

Oral Cavity

- Ranula
- Sublingual dermoids
- Cancrum oris (Noma)
- Leukoplakia
- Erythroplakia
- Oral submucosal fibrosis
- Premalignant conditions of oral cavity
- Anatomy of cheek
- Carcinoma cheek
- Carcinoma lip
- Anatomy of tongue
- Carcinoma tongue
- Nasopharyngeal carcinoma
- Maxillary tumours
- Carcinoma hard palate
- Palatal tumours
- Laryngeal tumours

RANULA

(***Rana* = *Frog*,** Ranula looks like belly of frog, hence the name.)

- Ranula is an *extravasation cyst arising from sublingual gland* or *mucus glands of Nuhn* or *glands of Blandin* in the floor of the mouth. Occasionally it can occur in submandibular salivary gland also.
- Initially there is blockage of the duct (of sublingual gland) causing retention cyst, which causes rupture of the acini due to increased pressure leading into extravasation cyst.

Clinical Features

- Presents as a bluish smooth, soft, fluctuant, brilliantly transilluminant swelling in the lateral aspect of the floor of the mouth.



Figs 3.1A to C: Ranula. Note the bluish discolouration, brilliantly transilluminant and the location.

- It often extends into the submandibular region through the deeper part of the posterior margin of mylohyoid muscle and is called as *plunging ranula*. It is intraoral ranula with cervical extension. It is cross fluctuant across mylohyoid.

> *Leukoplakia tongue looks as though it has been covered with white paint that had hardened, dried and cracked.*
>
> —Sir Henry T Buutlin

Clinical features of ranula

- Bluish swelling in the floor of the mouth
- Laterally placed
- Nontender
- Fluctuant and cross fluctuant (plunging ranula)
- Brilliantly transilluminant

- Ranula has a delicate fibrous capsule and is lined by a layer of macrophages. It contains clear fluid.
- It may damage the Wharton's duct.
- It may rupture; it may get infected.
- It may interfere with speech and swallowing occasionally.

Treatment

- *Marsupialisation* can be done initially, and later once the wall of the ranula is thickened it is excised. (*Marsupial* means pouch where baby is kept, carried and sucked on the mother's belly, like in Kangaroo).
- If ranula is small it can be excised without marsupialisation.
- Excision of sublingual salivary gland is often needed.

Differential Diagnosis

Lymph cyst.
Sublingual dermoid.

SUBLINGUAL DERMOIDS

They are *sequestration dermoids* lined by squamous epithelium containing keratin.





Figs 3.2A and B: Sublingual dermoid. It is usually midline. It is not transilluminant. Note the extension into the neck in submental region. Excised specimen is also shown.

Types

1. ***Median sublingual dermoid***: It is derived from epithelial cell rests at the level of fusion of *two mandibular arches*. It may be supramylohyoid or inframylohyoid. It is located between two genial muscles, in relation to mylohyoid muscle. It is a midline swelling which is smooth, soft, cystic, nontender, nontransilluminant.
   Treatment is excision through oral approach.
   Complication is abscess formation.
2. ***Lateral sublingual dermoid***: It develops in relation to submandibular duct, lingual nerve and stylohyoid ligament. It is derived from *first branchial arch*. It forms a swelling in the lateral aspect of the floor of the mouth.
   Treatment: Small one is removed per orally. Larger one, through submandibular incision.

CANCRUM ORIS (NOMA)

- It is an infective gangrene, a severe form of Vincent's acute ulcerative gingivitis and stomatitis.
- Seen in poorly nourished, ill-child due to Borrelia vincentii and Fusiformis bacteria.
- It starts in gums, spreads into cheek, bone, soft tissues and skin causing extensive tissue loss with severe toxaemia.
- Extensive necrosis of the mucus membrane of the oral cavity with destruction of deeper soft tissue and often bone.

- Excessive salivation, fetid odour with destruction, discharge and toxic features.
- Borrelia vincentii can be cultured.
- X-ray part shows bone destruction.
- Condition has got high mortality.
- Secondary infections may also coexist.

Note: **Phagedena** is a destructive ulceration with gangrene seen in cancrum oris, chancroid. (Phagedena is destruction without proliferation but malignancy is destruction with proliferation).

Treatment

1. Systemic antibiotics, high dose penicillins, metronidazole,
2. High protein and vitamin rich diet, through nasogastric tube.
3. Wound irrigation and liberal excision of the dead tissue.
4. Blood transfusion, TPN.
5. Later patient requires flaps to cover the defect.

LEUKOPLAKIA

It is a white patch in the mucosa of the oral cavity that cannot be characterised clinically or pathologically to any other disease. It is a premalignant condition.



Fig. 3.3: Leukoplakia right cheek.

Types

1. *Homogenous.*
2. *Nodular*—more potentially malignant.
3. *Speckled*—more potentially malignant–highest.

Clinically the lesion appears as white or greyish coloured, well-localised patch in the cheek, tongue, palate or other areas of the oral cavity.

Common causes

- Smoking
- Spirit
- Sepsis
- Superficial glossitis
- Syphilis
- Spices
- Sharp tooth
- Susceptibility
- Pan chewing using areca, tobacco, slaked lime
- Chronic hypertrophic candidiasis (long-standing candida infection)

- **Incidence of** leukoplakia in those who smoke or chew pan is 20%, whereas incidence in non-smokers is 1%.
- **Incidence of** its turning into malignancy is 2-4%. It increases with age, duration of the pan chewing, smoking.
- Buccal mucosa and oral commissures are most common sites. Common in males (3:1).
- Leukoplakia of long duration; leukoplakia in elderly; leukoplakia in younger females; leukoplakia in floor of the mouth and tongue; leukoplakia with induration, cracks and fissures are more likely to turn into malignancy.
- **Histology:** *Parakeratosis with widening of rete pegs*.

Histological staging

- Acanthosis – elongation of rete pegs – smooth, white, dry patch
- Parakeratosis
- Widening of rete pegs
- Dyskeratosis – keratin cell layer formation deep to epidermis
- Dysplasia
- Carcinoma *in situ*

- Biopsy confirms the diagnosis as well as rules out the carcinoma.

Treatment

- Pan chewing and smoking has to be stopped.
- Excision, if required skin grafting has to be done.
- Regular follow-up is necessary.
- Isoretinoin is helpful. Beta-carotene, tocoferol are also used.
- CO_2 laser excision.

> *In the case of malignancy of upper jaw, depression of the angle of the mouth on the affected side is also a typical sign.*
> — Charles P Wilson

ERYTHROPLAKIA

- It is red velvety appearance of the mucosa which cannot characterise any recognised condition.
- It is 17-20 times more potentially malignant than leukoplakia.
- Histologically *parakeratosis with severe epithelial dysplasia* is the typical feature.
- Red color is due to decreased keratin causing shining and prominence of submucosal red vascularised connective tissue.
- It is equal in both sexes.
- It is common in lower alveolar mucosa, gingivo buccal sulcus and floor of the mouth.
- It can be homogenous/speckled/granular or erythroplakia interspersed with leukoplakia.
- Diagnosis is done by biopsy.
- *Treatment:* Biopsy and surgical excision.

ORAL SUBMUCOSAL FIBROSIS



Fig. 3.4: Submucosal fibrosis of right cheek. Note the stiff fibrotic bands and scarring.

- It is a progressive fibrosis deep to the mucosa of the oral cavity which causes *trismus* and *ankyloglossia.*
- The mucosa of cheek, gingivae, palate and tongue shows a *mottled/marbled pallor.*
- It is common among Asians and Indians.
- *Aetiology:* Hypersensitivity to chilli, betelnut, tobacco and vitamin deficiencies probably alter the collagen metabolism leading to juxtaepithelial fibrosis, epithelial atrophy and dysplasia.
- 4.5 – 7.6% of oral submucosal fibrosis turns into malignancy (Paymaster -1956 study shows 30-33% incidence – very high).
- *Treatment:* Precipitating factors has to be avoided.
- Surgical excision when required, followed by skin grafting, has to be done.

Submucosal Fibrosis

- Due to
  - Prolonged local irritation by chilies, tobacco (pan/quid), areca due to arecoline
  - Dietary causes— deficiencies of vitamin A, B complex (riboflavin) and iron
  - Localised collagen disorder
- Racial – It is common among Indians / Asians and people of Indian origin
- Prevalence in India is 5 per 1000
- Incidence is 4-7 %
- Common in middle age; equal in both sexes
- Soreness and burning in mouth which is more during meals; vesicular eruptions; trismus; difficulty in protruding the tongue. Initial red area turns into superficial ulcers which later forms *stiff, fibrotic bands* and scarring.
- Common in soft palate, faucial pillars; buccal mucosa
- Disease is progressive
- It shows epithelial atrophy, hyperplasia, dysplasia and fibrosis
- *Treatment* – local injection of dexamethasone (4 mg) with hyalase (1500 units) biweekly for 10 weeks; avoidance of irritants; vitamin supplements; correction of anaemia; surgical wide excision and skin grafting

PREMALIGNANT CONDITIONS OF ORAL CAVITY

High risks – Lesions definite risk of malignant change

- Leukoplakia.
- Erythroplakia.
- Chronic hyperplastic candidiasis – It is common in commissures of the mouth and tongue. It is treated by topical or systemic antifungal drugs/surgical excision or laser therapy.

Medium risks – premalignant but not associated with higher incidence of carcinoma

- Oral submucosal fibrosis.
- Syhilitic glossitis.
- *Sideropenic dysphagia* (*Sideropenia* is iron deficiency without anaemia); or Plummer – Vinson syndrome. Sideropenia is common in Scandinavian females. It causes atrophy of epithelium and becomes potentially malignant. Proper iron therapy controls the disease and reduces the risk.

Equivocal risk lesions

- Oral lichen planus.

- Dyskeratosis congenital.
- Discoid lupus erythematosus.

Note:
- Oropharyngeal cancer is the most common cancer – 40% in Indian subcontinent. In western countries, it accounts for 4 % only.
- *Risk factors* – tobacco and related products; alcohol; areca nut; human papilloma virus; Epstein Barr virus; *Paterson Kelly syndrome;* nutritional deficiency.
- Patient may develop a second primary (15%) in the oropharynx in different site at same time or within 6 months of the existing primary (*synchronous* - 4% prevalence; 20% of second primaries) or after 6 months of first primary (*metachronous* – 80% of second primaries). Metachronous second primary is more common than synchronous second primary and it usually occurs in 2 years.

Premalignant conditions of oral cavity

1. Leukoplakia
2. Erythroplakia
3. Chronic hyperplastic candidiasis
4. Oral submucosal fibrosis
5. Syphilitic glossitis
6. Sideropenic dysphagia
7. Oral lichen planus
8. Discoid lupus erythematosus
9. Dyskeratosis congenita

CHEEK

ANATOMY OF CHEEK

- They are fleshy flaps on either side of the face. The demarcation between the lips and cheek is nasolabial fold.
- It is composed of skin, superficial fascia with parotid duct, buccinator muscle, submucosa with buccal glands and mucous membrane.
- Lymphatics: Submandibular and pre-auricular nodes.
- **RETROMOLAR TRIGONE** is the mucosa on the anterior surface of the ascending ramus of the mandible. It is triangular in shape with the base being superior and apex inferiorly behind the third molar tooth.

CARCINOMA CHEEK

Squamous cell carcinoma is the most common type of carcinoma of the cheek.



Figs 3.5A to D: Carcinoma cheek in different patients. Note the usage of tongue depressor for proper visualisation of the lesion.



Fig. 3.6: Trismus in a patient with advanced carcinoma cheek (T4 lesion). Patient is on chemotherapy and so developed alopecia.

- Occasionally it can be adenocarcinoma arising from the minor salivary glands or mucus glands. Rarely it can also be melanoma.

We are weaving the future on the loom of today.

Malignancies of the oral cavity

- *Squamous cell carcinoma—commonest*
- Minor salivary gland tumours
- Melanomas
- Adenocarcinomas—rare
- Sarcomas—rare

Sites of carcinoma in oral cavity in order

In India	*In Western countries*
Cheek—commonest	Tongue
Tongue	Floor of the mouth
Floor of the mouth	Lip
Palate	Cheek
Lips	

Precipitating Factors

All **'S'**—*Smoking, spirit, syphilis, sharp tooth, sepsis, spices.*

Incidence of oral cancer is six times more in smokers than non-smokers.

Premalignant conditions

a. Leukoplakia
b. Erythroplakia
c. Submucosal fibrosis
d. Hyperplastic candidiasis

Betel nut chewing (*Pan*, with *pan quid* kept in cheek pouch for a long time) is an important causative factor of carcinoma cheek.

Types

1. Ulcerative
2. Proliferative (exophytic)
3. *Verrucous*

Verrucous Carcinoma

- It occurs as a superficial proliferative exophytic lesion with minimal deep invasion, often multiple.
- Lesion has white, dry, velvety or warty, keratinised surface. It is common in females.
- It is of low grade, very well-differentiated squamous cell carcinoma, which is locally malignant without any lymphatic spread.
- It is a curable malignancy.
- After biopsy treatment is *wide excision. Radiotherapy* is not given as it may lead to poorly differentiated carcinoma.

Biological Behaviour of Carcinoma Cheek

- Carcinoma is common in posterior half of cheek than anterior.
- It spreads into the deeper plane to involve buccinator, pterygoids; into the retromolar trigone, base of the skull, pharynx.
- It spreads outwards to involve the skin causing fungation, ulceration, orocutaneous fistula formation.
- Mandible is commonly involved either by direct extension or through subperiosteal lymphatic plexus which communicates freely with oral lymphatics.
- Lymph nodes commonly involved are submental, submandibular, deep cervical and often lateral pharyngeal groups. Nodal spread is seen in 50% of cases.
- Infection of the tumour area and soft tissues around is common, causing fever, foul smelling ulcer, halitosis.
- Respiratory infection is common in these patients.
- Once tumour extends into the retromolar region, soft palate and pharynx, dysphagia will occur.
- Lesion will later spread to involve alveolus.



Fig. 3.7: Recurrent carcinoma cheek in an operated case.

Clinical Features

1. *Ulcer* in the cheek which gradually increases in size in a patient with history of chewing pan and smoking is the commonest presentation and initially it is painless.



Fig. 3.8A



Fig. 3.8B

Figs 3.8A and B: Advanced carcinoma cheeks presenting as swelling outside. There is an ulcer inside over the mucosa.

2. *Pain* occurs when it involves the skin, bone or if secondarily infected. Referred pain to the ear signifies involvement of lingual nerve. Lingual and auriculotemporal nerves arise from mandibular division of trigeminal nerve.
3. *Involvement of retromolar trigone* indicates that it is an advanced disease, as the lymphatics here communicate freely with the pharyngeal lymphatics.
4. *Everted edge, induration* are the typical features of the ulcer.
5. Mandible is examined bidigitally, for thickening, tenderness, irregularity and sites of fracture.
6. *Trismus and dysphagia* signify involvement of pterygoids or posterior extension.
7. Occasionally it may extend into the *upper alveolus and to the maxilla* causing swelling, pain and tenderness.
8. Submandibular lymph nodes and upper deep cervical lymph nodes are involved which are hard and nodular; initially mobile and later get fixed to each other and then to deeper structure.
   - Once lymph nodes get fixed it may infiltrate into hypoglossal nerve (tongue will deviate towards the same side), spinal accessory nerve (defective shrugging of shoulder) and cervical sympathetic chain (*Horner's syndrome*).
   - Compression over external carotid artery leads to absence of superficial temporal artery pulsation.
   - Eventually it causes fungation and bleeding from major vessels—-***carotid blow out.***

Note: *Node involvement may be due to infection. So often trial antibiotic is given initially.*



Figs 3.9A to C: Carcinoma cheek fungating outside extensively. Note the pigmentation in one of the pictures.



Fig. 3.10A

All surgeries are major; there is no minor surgery.



Fig. 3.10B

Figs 3.10A and B: Advanced carcinoma cheek with fungation and oro-cutaneous fistula.



Fig. 3.11: Oral cavity carcinoma with mandibular involvement, with T4 lesion.

Staging (For all oral cancers)

TNM Staging

T_1	Tumour size < 2 cm – greatest dimension
T_2	Tumour size 2-4 cm
T_3	Tumour > 4 cm
T_4	Tumour is of any size involving bone, soft tissues, muscles
N_1	Lymph node size < 3 cm, same side
N_2	Lymph node size 3-6 cm and single ***(N2a);*** multiple lymph nodes 3-6 cm size on same side ***(N2b);*** bilateral or opposite side nodes up to 6 cm size ***(N2c)***
N_3	Lymph node spread, more than 6 cm size

Features of advanced carcinoma cheek

1. Involvement of retromolar trigone
2. Extension into the base of skull and pharynx
3. Fixed neck lymph nodes
4. Extension to the opposite side

Problems with oral carcinomas

- Upper airway obstruction and bronchopneumonia
- Feeding difficulties and severe malnutrition
- Immunosuppression
- Secondary sepsis, uncontrollable bleeding
- Fixity of secondaries, fungation and disability
- Psychological trauma

Investigations

1. *Edge biopsy*, usually taken from two sites. Biopsy has to be taken from the edge as it contains active cells; not from the centre as it is the area of necrosis. Malignant *squamous cells with epithelial pearls (Keratin pearls*) are the histological features.
   Note: Biopsy from the centre is taken only from post-radiotherapy ulcer and ulcerated minor salivary gland tumours.

Broder's histological grading:
1. Well-differentiated: > 75% epithelial pearls
2. Moderately differentiated: 50-75% epithelial pearls
3. Poorly differentiated: 25-50% epithelial pearls
4. Very poorly differentiated: < 25% epithelial pearls

2 FNAC from lymph nodes.
3. CT scan—to assess the extension of tumour and its secondaries.
4. Orthopantomogram to look for the involvement of mandible—destruction and fracture sites.



Fig. 3.12: Normal Orthopantomogram. OPG is a must in all oral carcinomas to stage the disease and to plan the treatment.



Fig. 3.13: Orthopantomogram showing secondaries in mandible.

Open biopsy should be avoided in case of secondaries in lymph nodes as it may aggravate the spread to further level of lymph nodes.

Treatment

Treatment may be ***curative*** or ***palliative***.

Treatment strategy:

- ***Surgery***. Wide excision, hemimandibulectomy, neck lymph nodes block dissection.



Fig. 3.14: Patient who has undergone hemimandibulectomy with primary closure. Note the defect.



Fig. 3.15: Hemimandibulectomy, resected specimen (*Courtesy by Dr. Jagadish Chandra MDS*).

- ***Radiotherapy:*** Curative or palliative; external or brachytherapy.
- ***Chemotherapy***: Intraarterial, IV or orally.

a. ***Early growth without bone involvement*:**
   1. *Curative radiotherapy* using ^{137}Caesium needles or ^{192}Iridium wires, i.e. brachytherapy.

      Advantages:
      - i. Surgery is avoided,
      - ii. No surgical mutilation,
      - iii. Parts are retained,
      - iv. As it is a squamous cell carcinoma, primary is radiosensitive—90% cure rate.
   2. Other option is *wide excision with 1-2 cm clearance*. Often, the approach to the tumour is by raising the cheek flap (outside). After the wide excision, the flap is placed back (***Patterson operation***).



Fig. 3.16: Patterson incision to approach carcinoma cheek by raising skin flaps from lower part of face adjacent to lower margin of the mandible.

   3. Presently advanced technology in radiotherapy, facilitates the use of external radiotherapy also. The incidence of dreaded complication like *osteoradionecrosis of mandible* has been reduced due to better RT methods.

b. ***Growth with mandible involvement*:** Here along with wide excision of the primary tumour, hemimandibulectomy or segmental resection of the mandible or marginal mandibulectomy (using rotary electric saw) is done.

c. ***Operable growth with mandible involvement and mobile lymph nodes on the same side*** (confirmed by FNAC): Along with wide excision of the primary, hemimandibulectomy and radical neck lymph node dissection is done (like commondo operation).

Faith and strength…….help you go through tough times.


Tumour-
intraorally
Lip-split incision
A
B
C

Figs 3.17A to C: Lip split incision approach for carcinoma cheek. It gives adequate exposure of the cheek. Lower extension is for neck block dissection.



Fig. 3.18: Defect in the cheek after wide excision for carcinoma cheek. Defect needs coverage using PMMF with skin graft inside. (*Courtesy by Professor Kishore Chandraprasad ENT surgeon and head of the department and Dr Sampath ENT Surgeon KMC Mangalore*)


Primary
tumor
Mandible
Node secondaries

Fig. 3.19: Specimen showing primary tumour in cheek with mandible (hemimandibulectomy) and block dissection nodes.


Part resected

Fig. 3.20: Segmental resection of the mandible (angle of mandible to mental foramen).



Fig. 3.21: Hemimandibulectomy.



Fig. 3.22: Visor approach for oral malignancy. Visor approach for anterior mandible, floor of the mouth and tongue. Here skin over the anterior curved margin of the mandible is incised to approach the floor of the mouth for needed procedure.

d. ***Operable growth with mandible involvement; mobile lymph nodes on same side and opposite side*:** Along with wide excision of the tumour, hemimandibulectomy, radical neck lymph node dissection on same side and functional block dissection on opposite side are done, retaining the internal jugular vein, sternomastoid, spinal accessory nerve.



Fig. 3.23: Partial mandibulectomy is removal of mandible one side from mental foramen to coronoid process line including coronoid process but leaving condylar process.

e. *Operable primary tumour with mobile lymph nodes on same side but without mandibular involvement:* Wide excision of primary tumour and radical neck lymph node dissection on same side are done. Mandible is not removed.



Fig. 3.24: Carcinoma cheek operated with radical neck dissection of same side lymph nodes. Reconstruction done using pectoralis major myocutaneous flap.

> *Fissuring of tongue due to ariboflavinosis is longitudinal and the bottom of fissure is beefy red.*
> —Dimitri Afonsky



Figs 3.25A and B: Pectoralis major myocutaneous flap to cover the defect in the cheek after wide excision. (*Courtesy by Professor Kishore Chandra Prasad ENT surgeon and head of the department and Dr Sampath ENT surgeon KMC Mangalore*).

f. ***Fixed primary tumour or advanced neck lymph node secondaries*****:** Only palliative *external radiotherapy* is given to palliate pain, fungation and to prevent anticipated torrential haemorrhage.

g. ***Preoperative radiotherapy is often used in fixed lymph nodes to downstage*** the disease so as to make it operable.

h. ***Postoperative radiotherapy is given in T_3 and T_4 tumours:*** N_2 and N_3 nodal status to reduce the recurrence and to improve the prognosis (in multiple nodes and nodes with extracapsular spread).

i. ***Prophylactic block dissection has become popular*** **in N_0 diseases.** Reasons are—even though clinically, lymph nodes are negative there may be microscopic involvement of lymph nodes (25-65%). Clinically detectable disease in lymph nodes of the patient signifies extracapsular spread which has got poor prognosis. Recurrence rate is less after prophylactic block compared to block dissection with clinically positive nodes because there is no extracapsular spread in the former even if there is microscopic spread of tumour in many cases. Block dissection is an acceptable surgery as there is negligible mortality and less morbidity.



Fig. 3.26: Marginal mandibulectomy.



Fig. 3.27: Rim resection of mandible done for carcinoma floor of the mouth.

j. ***If growth is extending to upper alveolus*****:** Partial maxillectomy or total maxillectomy may be required.

k. ***Role of chemotherapy*****:** Drugs used are methotrexate, cisplatin, vincristine, bleomycin, adriamycin. Often it is given intraarterially through external carotid artery using arterial pump or by increasing the height of the drip more than 13 feet, so as to attain a pressure more than systolic pressure. Chemotherapy can also be given IV or orally - postoperatively.

l. Initial chemotherapy to downstage the tumour followed by surgery and later again end with chemotherapy.

m. Chemoradiotherapy is used in unresectable tumours – as consecutive therapies.

Reconstruction after Surgery



Figs 3.28A and B: Reconstruction of the mandible after hemi-mandibulectomy using plate and opposite rib fixation (*Courtesy by Jagadish Chandra MDS*).

Flaps used for reconstruction after oral surgery:

- Forehead flap based on superficial temporal artery
- Delto-pectoral flap based on 1, 2 and 3 perforating vessels from internal mammary vessels
- Pectoralis major myocutaneous flap (PMMF) based on thoraco-acromial artery
- Free microvascular flaps may be from radial artery forearm flap
- For small defects – tongue flap, buccal flap, palatal mucoperiosteal flap

- Split skin graft.
- Deltopectoral cutaneous flap.
- Forehead flap, radial artery forearm flap.
- Pectoralis major myocutaneous flap.
- Mandible reconstruction by cortical bone graft or rib, fibula or synthetic material like titanium, stainless steel plate.

Approaches to Carcinoma Cheek

- Transoral/intraoral approach.
- Lip split incision.
- Patterson approach.
- *Visor approach* for anterior mandible, floor of the mouth and tongue. Here skin over the anterior curved margin of the mandible is incised to approach the floor of the mouth for needed procedure. (Visor is French derived word which means mobile lower part of the helmet which covers the chin).

Different mandibular resections

- Marginal mandibulectomy
- Partial mandibulectomy
- Segmental resection
- Hemimandibulectomy
- Rim resection of mandible
- Resection of the anterior mandible through visor approach

Problems with surgery

- Mutilation (surgical)
- Anaesthesia complications
- Bleeding
- Infection
- Flap necrosis
- Requirement for reconstruction
- Mortality
- Morbidity – stiffness; contracture; cosmetic problem; cutaneous anaesthesia; speech and swallowing problems

Aphthous ulcer is rare after the age of 50. —Wilfred Sircus



Fig. 3.29: Carcinoma cheek, on table wide excision. It requires pectoralis major myocutaneous flap for reconstruction.



Fig. 3.30: Radical neck dissection for secondaries in neck through Mac fee incision.

Problems with radiotherapy

- When mandible is irradiated, chances of the dreaded problem, osteoradionecrosis is high which requires the removal of mandible
- Loss of taste sensation and dryness
- Infection, mucositis
- Skin excoriation
- Trismus may get aggravated
- Can itself cause dysphagia, laryngeal oedema
- Hypothyroidism if neck is irradiated
- Radiation neuritis causing severe pain
- Carotid artery atherosclerosis
- Visual impairment
- Shoulder and neck dysfunction



Fig. 3.31: Forehead flap is used after wide excision of carcinoma cheek. It is based on superficial temporal artery-anterior branch.



Figs 3.32A and B: Forehead flap used to cover the defect after wide excision for carcinoma cheek. (*Courtesy by Professor Kishore Chandra Prasad ENT surgeon and head of the department and Dr Sampath ENT surgeon KMC Mangalore*).



Fig. 3.33: Delto-pectoral flap used to cover defect after surgical clearance in carcinoma cheek. It is based on 2nd perforator, a branch of internal mammary artery (*Bakamjian – 1965*).

Problems with chemotherapy

- Bone marrow suppression
- Megaloblastic anaemia
- GIT symptoms
- Hepatotoxicity and renal toxicity
- Alopecia
- Nausea, vomiting and severe stomatitis



Figs 3.34A and B: Mucositis in cheek and lip in a patient who is receiving chemotherapy for carcinoma.

Prognostic factors in oral carcinomas

- Stage of the disease
  - Stage I and II has got 80% 5 years survival
  - Stage III and IV has got less than 20 % 5 year survival rate
- T3 and T4 lesions has got poor survival rate
- Carcinoma lip has got best prognosis.
- Carcinoma posterior 1/3rd tongue has got worst prognosis
- Cheek, floor of the mouth and palate has got intermediate prognosis
- Perineural invasion and angioinvasion carries poor prognosis
- Histologically positive nodes decrease the survival rate by 50%
- Level III and IV, node > 3 cm, bilateral nodes extracapsular nodal spread are poor prognostic factors
- Grading (differentiation) of the tumour
- Tumour thickness > 6 mm has got poor prognosis
- Exophytic tumour is better than infiltrating type

LIP



Fig. 3.35: Mucous cyst upper lip. It requires simple excision. It is a retention cyst.



Fig. 3.36: Mucus cyst seen in lower lip. It is bluish, localised, smooth, nontender, soft, fluctuant swelling, arising as a retention cyst from mucus glands of lip. It needs excision.

Halitosis is better breath than no breath at all !!!



Fig. 3.37: Lip haemangioma causing macrocheilia.



Fig. 3.38: Aphthous ulcer lower lip. It is painful, self limiting ulcer. It can occur in tongue, lip, cheek and other parts of the oral mucosa.

NEOPLASM OF LIP

> ***One may…cure cancers of the lip without applying caustics or any similar thing…. Pass a threaded needle through the cancer so the thread held in the left hand can lift and control the cancer without any of its escaping. One can then cut to good flesh with scissors in the right hand; and so cut that a layer of good flesh of the lip remains to serve as a base and foundation for regeneration of flesh in place of the portion amputated, supposing the cancer has not taken root and spread from top to bottom.***
>
> —**Ambroise Paré**, 1585

Minor salivary gland tumours are common in *upper lip*. They are usually *pleomorphic adenomas*.

CARCINOMA LIP



Figs 3.39A to C: Carcinoma of lip involving extensively.



Fig. 3.40: Carcinoma lip

- It is common in men. Common in *lower lip* (90%); upper lip 5-10%.
- Commonly due to exposure to sunlight (ultraviolet rays). Common in pipe smokers.
- Initially starts as a red, granular dry lesion which eventually gets ulcerated and forms an ulcero-proliferative lesion. Occasionally it occurs at the angle of mouth.
- It spreads to submental nodes and later to other neck nodes on both sides.
- Usually it is a *well-differentiated squamous cell carcinoma*.

Clinical features of carcinoma lip

- Non-healing progressive ulcer, painless to begin with
- Everted edge with indurations
- Growth moves with the lip
- Submental, submandibular and upper deep neck nodes may get enlarged
- In half of the cases lymph nodes are enlarged due to infection or as reactive process
- Fungation, bleeding

Predisposing Factors

- Cheilitis.
- Solar keratosis.
- Papilloma.
- Leukoplakia.
- Smoking, U-V rays.
- Tobacco chewing, Khaini chewers (tobacco+lime).
- Agriculturists who are commonly exposed to sunlight get carcinoma lip and is called as *countryman's lip*.

Differential Diagnosis

- Keratoacanthoma.



Figs 3.41A to C: Carcinoma lip involving different parts. Commonly they are squamous cell carcinomas.

In great attempts, it is glorious even to fail.

- Basal cell carcinoma.
- Minor salivary gland tumours.
- Often carcinoma of lip is an extension from carcinoma of cheek.
- Pyogenic granuloma in early cases only.

Diagnosis

Edge biopsy, FNAC of lymph nodes.



Fig. 3.42: Carcinoma lip extending into the floor of the mouth.

Treatment

- If lesion is less than 2 cm, then curative *radiotherapy*, either brachytherapy or external beam radiotherapy. It gives a good cure.
- If tumour is more than 2 cm, *wide excision* is done. Excision of lower lip up to one-third can be sutured primarily, in layers keeping vermilion border in proper apposition without causing any microstomia.
- Excision of more than one-third of the lip requires reconstruction using different flaps.



Fig. 3.43: Primary repair of lip after wide excision of small tumour. One-third of the lip can be sacrificed. Lip is sutured in layers. First layer, muco-muscular layer is with absorbable suture. Second layer is skin with non-absorbable monofilament sutures like polypropylene.



Fig. 3.44: Lower lip tumour after excision when primary suturing is not possible, then upper lip flap based on upper labial artery can be used – Estlander flap.

Methods

1. *Estlander's rotating flap* from the upper lip based on upper labial artery. It is used when defect is less than ½ of the lip.
2. *Fries' modified Bernard facial flap*—reconstruction using lateral facial flaps. It is used when defect is more than ½ of lip and midline.
3. Microvascular flaps.
4. *Nasolabial flap*–It is used when defect is more than ½ of lip laterally or defect is in the floor of the mouth.
5. Cheek flap.
6. Free radial artery flap.
7. *Abbe flap* is used in upper lip lesion-defect. It is taken from lower lip with inferior labial artery as base.
8. *"W' flap plasty* – It is done for lower lip middle tumour which is less than 1/3 of the lip.
9. *Gillies fan flap* – It is a cheek flap usually bilateral but can be unilateral. Incision is full thickness around commissures extending into nasolabial fold and upper lip upto upper lip vermilion border. Flap which is based on labial vessels is advanced towards the defect. Vermilion is reconstructed with tongue mucosal flap which is divided in 3 weeks.
10. *Karapandzic flap* – It is modified version of the Gillies flap used for lower lip defect with less angulation towards upper lip. Reverse Karapandzic flap is used for upper lip defect.


Tumour
Abbe flap
A
Excised bed
Rotated flap
Donor flap area
B
Rotated flap
Excised bed
Donor flap area
C
Rotated flap
D
Suture lines
E

Figs 3.45A to E: For upper lip tumour when primary repair is not possible, then lower lip flap based on inferior labial artery can be rotated to upper lip – Abbe flap.


Burrow's triangle
Tumour removed -defect

Fig. 3.46: It is used for central lip tumours. Angles of the lower part of the defect and upper part of the angles of the mouth are rotated inwards with burrow's triangles at the site of rotation – Bernard flap


Tumour
'W' flap

Fig. 3.47: It is done for lower lip middle tumour which is less than 1/3 of the lip – 'W' flap.

Knowledge is the only treasure that increases on sharing.


Tumour removed
Gillies fan flap
A
B

Figs 3.48A and B: Gilles fan flap.


Inferiorly based nasolabial flap bilateral
Tumour in the floor of the mouth removed defect
Flap rotated into the defect in the floor of the mouth
A
B

Figs 3.49A and B: Nasolabial flap used in extensive lower lip defect or over the defect after wide excision of a tumour in the floor of the mouth.

11. *Johansen 'stepladder'* procedure is used for extensive carcinoma of lower lip.
12. Other regular flaps like forehead flap, deltopectoral flap also can be used.

- Lymph nodes are dealt with by radical neck dissection on one side and functional block or supraomohyoid block dissection on other side. For central tumour N_0 disease, bilateral elective (prophylactic) supraomohyoid dissection is done. For lateral tumour N_0 disease, elective ipsilateral supraomohyoid dissection is done.
- Postoperative radiotherapy is given if tumour is large or if lymph nodes are involved.
- When mandible is involved, segmental resection is done.

Prognosis

Prognosis is good, 5 year survival is 70%. Lip has best prognosis.

TONGUE

ANATOMY OF TONGUE

Tongue is a muscular organ located in the floor of the mouth.


Epiglottis
Median G E fold
Vallecula
Lateral G E fold
Lymphoid nodules
Sulcus terminalis
Circumvallate
Foliate
Fungiform
Filiform

Fig. 3.50: Anatomy of the tongue showing parts and papillae.

Parts

1. *Tip*: Anterior free end lies behind the upper incisor teeth.
2. *Root:* Attached to the mandible above and hyoid bone below.
3. *Body:* Dorsal surface is rough due to papillae; and is divided into anterior 2/3 (oral part) and posterior 1/3 (pharyngeal part) by *sulcus terminalis*. Ventral surface is smooth, has a median fold, *'frenulum linguae'* and deep lingual vein on either side.

Papillae

1. *Vallate*—large, located in front of sulcus terminalis.
2. *Fungiform*—lies over the tip and margin of the tongue.
3. *Filiform*—lies over the dorsum of tongue, gives the velvety appearance—commonest.

Muscles of Tongue

a. Intrinsic muscle: Superior and inferior longitudinal, transverse and vertical.

b. Extrinsic muscle: Genioglossus, hyoglossus, styloglossus, palatoglossus.

Blood supply is from lingual artery, a branch of external carotid artery. Venous drainage by deep lingual vein which drains into fascial vein or internal jugular vein.

Movements of the tongue

- Forward protrusion – genioglossus – most commonly affected by carcinoma
- Backward movement – styloglossus
- Elevation of tongue – palatoglossus
- Depression of tongue – hyoglossus

LYMPHATIC DRAINAGE OF THE TONGUE

- Tip of tongue drains into submental lymph nodes.
- Lateral margin drains to submandibular lymph nodes and into upper deep cervical lymph nodes. Many lymphatic vessels pass as subperiosteal lymphatics of mandible. So carcinoma can involve the bone through this route.
- Lymphatics in the midline of tongue freely cross communicate with each other and so spread of malignancy can occur to both side neck lymph nodes.
- Lymphatics from posterior third of tongue drain into pharyngeal group of lymph nodes, as well as to the upper deep cervical lymph nodes. Early spread to the pharyngeal lymph nodes from carcinoma of posterior third of tongue has a poor prognosis.

Lymphatic vessels are named as

1. Apical vessels.
2. Central vessels.
3. Marginal vessels.
4. Basal vessels.



Fig. 3.51: Severe superficial glossitis.

Development and Nerve Supply of the Tongue

- *Anterior 2/3* develop from first branchial arch through two lingual swellings and one tuberculum impar. It is supplied by lingual nerve for general sensation and by chorda tympani for taste sensation.
- *Posterior 1/3* develops from third arch from cranial half of hypobranchial eminence. It is supplied by glossopharyngeal nerve for both general and taste sensations.
- *Posteriormost part* develops from the fourth arch. It is supplied by vagus nerve (internal laryngeal nerve).
- *Muscles of the tongue* are derived from occipital myotomes and are supplied by hypoglossal nerve except palatoglossus, which is supplied by cranial part of accessory nerve.

Differential diagnosis for tongue ulcers

1. Dental ulcers—Painful
2. Aphthous ulcers—Painful
3. Ulcers in lichen planus—Painless
4. Syphilitic ulcers—Painless
5. Tuberculous ulcers—Painful
6. Malignant ulcers—Painless

Macroglossia

It is painless diffuse enlargement of tongue

Causes

1. *Lymphangioma*—soft, painless enlarged tongue with ulcers
2. *Haemangioma*—soft, fluctuant, compressible, bleeding, red/blue lesion
    i. Both are treated by sclerotherapy (ethonalamine oleate)/partial excision
    ii. Angiogram/MR angiogram is a must in haemagioma
    iii. Ligation of lingual artery/ECA on both sides may be needed in large lesions
3. *Neurofibroma*—partial excision is done
4. *Tongue muscular hypertrophy:* Partial excision is done

Attitude is a small thing that makes a big difference.



Fig. 3.52: Macroglossia in Down's syndrome patient. (*Courtesy by Professor Kishore Chandra Prasad ENT surgeon and head of the department and Dr Sampath ENT surgeon KMC Mangalore*)

Benign tumours of the tongue

1. Papilloma
2. Fibroepithelial polyp
3. Haemangioma and lymphangioma
4. Neurofibroma
5. Lipoma
6. Granular cell myoblastoma



Fig. 3.53: Papilloma tongue. It is a premalignant condition. It requires surgical excision.

CARCINOMA TONGUE

Incidence is equal in both sexes. Presently its incidence is increasing in females due to increase in number of female smokers.



Fig. 3.54: Tongue showing fissuring. Fissuring is one of the presentations of carcinoma tongue.

Aetiology

- Leukoplakia.
- Erythroplakia.
- All 'S's (as mentioned in leukoplakia).
- Premalignant conditions mentioned earlier.



Tonsillar pillar
Posterior 1/3rd
Anterior 2/3rd
1. Submental group
2. Submandibular group
3. Upper deep cervical group
4. Pharyngeal group
4
3
2
1

Fig. 3.55: Anatomy and lymphatic drainage of tongue.

Types

Gross

1. Papillary.
2. Ulcerative or ulceroproliferative.
3. Fissure with induration.
4. Lobulated, indurated mass.

Histologically

1. Squamous cell carcinoma—commonest.
2. Adenocarcinoma, may arise from minor salivary glands or mucus glands.
3. Melanomas.

Sites

1. Lateral margin—Commonest—47-50%.
2. Posterior third—20%.
3. Dorsum—6.5%.
4. Ventral surface—9%.

Clinical Features

1. *Pain* in the tongue due to infection or ulceration or due to the involvement of lingual nerve (pain is referred to ear). Pain on swallowing, in case of carcinoma of posterior third of tongue.



Figs 3.56A and B: Carcinoma tongue lateral margin *(commonest site)*.



Fig. 3.57: Carcinoma tongue.

2. *Excessive salivation.* Saliva is often blood stained.
3. *Dysphagia* either due to fixed tongue or due to the involvement of genioglossus or growth in the posterior third of the tongue.
4. *Visible ulcer* in anterior two-thirds of tongue. Ulcer can bleed on touch; edge, base and surrounding areas are indurated. Often indurated area is much more extensive than the primary tumour (it is also common in carcinoma penis). Edge is everted commonly. Ulcer may cross the midline; may extend into the floor of the mouth/alveolus/mandible. Growth or ulcer in posterior third, is usually not visible.
5. *Ankyloglossia* – involvement of muscles of the tongue.
6. *Inability to articulate.*
7. *Foetor* (Halitosis). Due to infection and necrosis in the oral cavity.
8. *Change in voice*. Occurs in posterior third tumours. Tumour in posterior third area is more aggressive.
9. Palpable *lymph nodes* in the neck which are hard, nodular and get fixed to underlying tissues in advanced stages.
10. Features of bronchopneumonia.

Spread of Carcinoma Tongue

*Local spread***:** In case of anterior two-thirds of tongue, the spread occurs to genioglossus muscle, floor of the mouth, opposite side and mandible. In case of posterior third of tongue it spreads locally to tonsil, side of pharynx, soft palate, epiglottis, larynx and cervical spine.

Faith makes all things possible; hope makes all things bright.

Lymphatic spread: From tip of tongue it spreads to submental nodes. From lateral margin it spreads to submandibular lymph nodes and later to deep cervical lymph nodes. Lymphatics in the tongue are freely communicating, and so involvement of bilateral neck lymph nodes is common. From posterior third it spreads to pharyngeal nodes and upper deep cervical lymph nodes.



Fig. 3.58: Carcinoma left lateral margin of the tongue – ulcerative lesion. Note the proliferation. Induration extends for beyond the visible lesion.

Investigations

1. Edge biopsy.
2. FNAC of lymph nodes.
3. Indirect and direct laryngoscopy to see posterior third growth.
4. CT scan to see the extension of posterior third growth, or to see the status of advanced secondaries.
5. Chest X-ray to see bronchopneumonia.
6. Orthopantomogram.

Staging is same as carcinoma cheek.


Epiglottis
Median GE fold
Vallecula
Lateral GE fold
Lymphoid nodules
Sulcus terminalis
Circumvallate
Foliate
Tumour (1cm)
1cm
Fungiform
Filiform

Fig. 3.59: Wide excision is done in small lateral margin tumour of 1 cm size with 1 cm clearance.


Epiglottis
Median G E fold
Vallecula
Lateral GE fold
Lymphoid nodules
Sulcus terminalis
Circumvallate
Foliate
Fungiform
Tumour > 2 cm
Filiform
2 cm

Fig. 3.60: Tumour between 1-2 cm size is treated by partial glossectomy with 2 cm clearance.


Epiglottis
Median GE fold
Vallecula
Lateral GE fold
Lymphoid nodules
Sulcus terminalis
Circumvallate
Foliate
Tumour > 2 cm
Fungiform
Line of clearance
Filiform

Fig. 3.61: Tumour larger than 2 cm requires hemiglossectomy.

Treatment

Surgery, radiotherapy, chemotherapy.

Surgery:

1. Wide excision is done in early growth < 2 cm in size and hemiglossectomy in growth > 2 cm in size.
2. Larger primary tumour can be given preoperative radiotherapy, then later hemiglossectomy is done.
3. Same side palpable, mobile lymph nodes are removed by *radical neck block dissection*.
4. *Bilateral mobile lymph nodes* are dealt with *one side radical block and other side functional block dissection with essentially retaining internal jugular vein* (on opposite side) to maintain the cerebral venous blood flow. Other option is doing same side radical neck dissection and on opposite side supraomohyoid block dissection.

5. *Wide excision* is done when growth is in *the tip* of the tongue.
6. Posterior third growth can be approached by lip split and mandible resection, so as to have *total glossectomy.*
7. When mandible is involved *hemimandibulectomy* is done.
8. The procedure that involves wide excision or hemiglossectomy, hemimandibulectomy and radical neck dissection together is called as *Commando Operation*.
9. Reconstruction of tongue and other area after surgery: By deltopectoral flap, forehead flap, pectoralis major muscle flap, skin grafting.
10. Prophylactic block dissection is becoming popular at present.

Postoperative management
- Control of infection and oedema
- Regular mouth wash
- Maintaining the airway
- Prevention of aspiration
- Nutrition (through nasogastric tube commonly/ TPN often)

Radiotherapy:
1. In small primary tumour — Curative radiotherapy (Brachytherapy using caesium or iridium^{192} needles).
2. Large primary tumour — Initial radiotherapy is given to reduce the tumour size so that the resection will be better later.
3. Advanced primary as well as secondaries in the neck can be controlled by palliative external radiotherapy.
4. Postoperative radiotherapy is given in large tumours to reduce the chances of relapse.
5. In case of growths in the posterior third of tongue, radiotherapy is of curative as well as palliative mode.

Complications of radiotherapy
1. Loss of sensation like taste
2. Trismus and ankyloglossia
3. Infection
4. Pharyngeal and laryngeal oedema
5. Dermatitis and skin infection

Chemotherapy: *Given in postoperative period and also for palliation.*

Price-Hill regimen is commonly used. Drugs are methotrexate, vincristine, adriamycin, bleomycin and mercaptopurine.

It is either given intraarterially, as regional chemotherapy through external carotid artery using arterial pump or through IV. It can also be given orally.

Complications of chemotherapy
- Megaloblastic anaemia
- Bone marrow suppression
- Alopecia
- Sepsis

For Melanoma, Melphalan and DTIC are used.

Anterior chemotherapy (preoperative) is becoming popular to downstage the tumour.

Terminal events
1. Inhalational bronchopneumonia
2. Haemorrhage from erosion of lingual artery. In posterior third of the tongue, erosion of internal carotid artery can occur
3. Cancer cachexia
4. Asphyxia due to pressure on air passages or due to oedema glottis

Prognosis

Five year survival for females is 50%, for males is 25%.

Nodal prognostic factors
- Positive histology in node reduces the survival
- Level III and IV has poor prognosis
- Bilateral/ contralateral nodes carry poor prognosis
- Extracapsular spread/size > 3 cm carry poor survival
- > 3 in number of nodes involved is poor sign

Prognostic factors:
- Size of the tumour > 4 cm caries poor prognosis.
- Site of tumour (posterior third has got poor prognosis).
- Tumour crossing the midline.
- Lymph nodes status.
- Differentiation.
- Bone involvement.

CARCINOMA OF POSTERIOR ONE THIRD / BASE OF THE TONGUE

- Lesion may remain asymptomatic for long time.
- Clinically may be missed easily.
- Earlier symptoms are features mimicking sore-throat and throat discomfort.
- Dysphagia and change in voice (*hot potato voice*) occurs later.

Anything the mind of man can conceive and believe, it can achieve.

- Referred pain in the ear, bleeding from mouth, visible mass in posterior third of tongue is late local features.
- Induration on palpation in posterior third tongue is diagnostic of the carcinoma.
- As posterior third tongue has got abundant lymphatics which cross communicates on either side, lymph node spread is common (70%). Bilateral nodal spread is common. Massive nodes and involvement of jugulodigastric node are also common.
- Infiltration into the tongue muscles like genioglossus, epiglottis, pre-epiglottic space, tonsillar pillars and hypopharynx are common.
- Carcinoma posterior third of the tongue is often poorly differentiated and so caries poor prognosis.
- Blood spread can occur into bones, liver and lungs in posterior third cancers.
- Palpation under anaesthesia gives better idea about the tumour, its spread and also allows the biopsy.
- CT scan is always needed to plan the staging and therapy.
- T_1, T_2, N_0 and N_1 diseases are treated by surgical wide excision or often by total glossectomy using midline mandibulotomy incision (mandible split) with neck dissection on both sides (MRND one side). Post surgery radiotherapy is needed if it is a poorly differentiated type or nodal status is more than N_1.
- Advanced lesions need palliative radiotherapy or chemotherapy.
- T_4 lesions are often treated by total glossectomy with laryngectomy and neck dissection but overall outcome is not good.
- In many centers primary curative radiotherapy is used.
- Lymphoepithelioma and transitional cell carcinoma can occur in posterior third tongue (rarely).

Carcinoma floor of the mouth

- It is usually aggressive tumour
- It is rare in India
- It is 2nd common site of oral carcinoma (SCC) in western countries
- It invades hyoglossus, mylohyoid, genioglossus and anterior mandible early
- Bilateral neck nodes are commonly involved
- Rim resection of mandible with wide excision of tumour with muscles and soft tissues and bilateral neck dissection is necessary
- Often visor anterior approach with anterior mandible resection followed by proper reconstruction with bone graft and plates is needed
- Postoperative radiotherapy and later chemotherapy is used to prevent recurrence
- Prognosis is poor and also has poor cosmetic results

Carcinoma alveolus

- It is squamous cell carcinoma arising from gums
- It is common in males
- It is common in India
- It is commonly due to tobacco/pan chewing
- Features and precipitating factors are similar to other oral carcinomas
- There will be invariable bone involvement by direct extension
- Nodal spread is also common
- Wide excision with mandibulectomy and block dissection of neck is the treatment



Fig. 3.62: Carcinoma of floor of the mouth. It has got poor prognosis.

NASOPHARYNGEAL CARCINOMA

- Nasopharynx lies above the level of the soft palate which divides it from oropharynx below.
- It is also called as post-nasal space or epipharynx. Eustachian tube opens on its antero-lateral wall. Fossa of Rosenmuller is located above and behind the opening of the Eustachian tube as a small depression.
- Nasopharyngeal carcinoma is common in China and Mongolia. In India it is common in North-east region. It is commonly squamous cell carcinoma (85%). Lymphoma, minor salivary tumours and sarcoma are other malignancies that can occur rarely in nasopharynx. It can be of proliferative, ulcerative, and infiltrative types. Commonest site is fossa of Rosenmuller in lateral wall of pharynx. It is three times common in males. *HO's triangle* in supraclavicular fossa (bounded by medial and lateral ends of clavicle and point where neck meets the shoulder) is the site

where metastatic nodes commonly exist in nasopharyngeal carcinoma. In 50% of cases nodal involvement is bilateral. Often cervical lymphadenopathy may be the first presentation. Clinical features may be nasal, otogenic, ophthalmoneurogenic (involving most of the cranial nerves with facial pain, squint, diplopia, exophthalmos, and ophthalmoplegia), jugular foramen syndrome (cranial nerves IX, X, XI spread), nodal spread and distant spread to bones, lungs and liver. Unilateral serous otitis media may be the only presentation.

Clinical Features

1. Epistaxis, nasal speech, post-nasal discharge and nasal obstruction.
2. Pain in the ear with unilateral deafness due to compression of Eustachian tube with fluid collection in the middle ear.
3. Elevation and immobility of soft palate on the same side.
4. Pain in the area of distribution of trigeminal nerve due to direct infiltration of the nerve at foramen lacerum.
5. Palpable secondaries in upper deep cervical lymph nodes (70%).

Trotter's triad
- Unilateral deafness
- Immobile elevated soft palate
- Pain in the distribution of trigeminal nerve

Differential Diagnosis

- Lymphoma.
- Lympho-epithelioma.
- Minor salivary gland tumour.

Investigations

- Biopsy from the primary site.
- FNAC from the neck lymph nodes.
- X-ray of the skull to visualise erosions.
- CT scan skull.

Histological Type

Squamous cell carcinoma.

Treatment

- External irradiation for primary. RT is the main modality of treatment.
- Radical block dissection of cervical lymph nodes.
- In N2a, N2b and N2c contralateral neck dissection is needed. Spinal accessory nerve is never preserved while doing block dissection in nasopharyngeal carcinoma.
- Chemotherapy: Methotrexate, Vincristine.
- Skull base surgeries are useful.

MAXILLARY TUMOURS

They are rare.

- Maxillary sinus is the commonest site for malignancy of paranasal sinuses. Ethmoids, frontal and sphenoids are next in order.
- It is common in people working in furniture industries, mustard gas industries, and leather industries. It is common in Bantus in South Africa where snuff with nickel and chromium is commonly used.

Types

1. Squamous cell carcinoma 80%.
2. Adenocarcinoma.
3. Transitional cell carcinoma.
4. Salivary gland tumours.
5. Sarcomas and melanoma.
6. Burkitt's lymphoma.



Fig. 3.63: Carcinoma maxillary sinus in a boy. Note the extension into the palate.

He who believes, is strong; he who doubts, is weak.



Fig. 3.64: CT picture of carcinoma of maxillary sinus (left-sided).

Behaviour and Presentation

1. Initially may be symptomless or may present with *epistaxis* or *features of chronic sinusitis*.
2. When it spreads to the floor, loosening of the teeth, necrosis, antro-oral fistula can occur.
3. Extension medially causes nasal block, fungation, nasal discharge, blockage of nasolacrimal duct *(epiphora*).
4. Extension anteriorly causes pain, anaesthesia and swelling in the cheek, ulceration and fungation in the skin of cheek.
5. Spread above into the orbit causes epiphora, diplopia, proptosis.
6. *Posterior spread is most dangerous* as it is not revealed easily. It causes postnasal discharge, pain, trismus, limitation of temporo-mandibular joint movement.
7. Involvement of upper deep cervical lymph nodes in later stage is common.

Differential Diagnosis

Chronic sinusitis.

Classification

1. *Ohngren's classification*

An imaginary plane is drawn extending between medial canthus of eye and the angle of mandible. Growth situated above this plane is called as *suprastructural* which has got poor prognosis. Growth below this plane is called as *infrastructural* and has got better prognosis.



Fig. 3.65: An imaginary plane is drawn extending between medial canthus of eye and the angle of mandible and line in this plane is called as Ohngren's line.

2. *Lederman's classification*

Two horizontal lines are used, one passes through the floor of the orbit, another passes through the floor of the antra. These lines are called as *line of Sebileau*.

- *Suprastructure type*: In this type olfactory area of nose, ethmoidal, sphenoid, and frontal sinuses are involved.
- *Mesostructural type*: This involves maxillary sinus and nasal respiratory part.
- *Infrastructural type*: This type involves alveolar process.

Lederman's classification is further divided by two vertical lines over medial walls of the orbit to separate ethmoid sinuses and nasal fossa from maxillary sinuses.



Fig. 3.66: Diagrammatic representation of Lederman's classification.

TNM staging	*Staging*
- T_1 *Tumour* limited to antral mucosa - T_2 *Tumour* causing bone erosion/destruction including extension into hard palate or middle meatus of nose. - T_3 *Tumour* invading bone of posterior wall of maxillary sinus/skin of cheek/medial wall of orbit/infratemporal fossa/pterygoid plates / ethmoid sinuses. - T_4 *Tumour* invading orbital contents beyond the floor or medial wall including orbital apex/cribriform plate / base of skull/nasopharynx/sphenoid or ethmoidal sinuses	Stage I T_1 N_0 M_0 Stage II T_2 N_0 M_0 Stage III T_3 N_0 M_0, $T_1/T_2/T_3$ N_1 M_0 Stage IVA T_4 N_0 M_0, T_4 N_1 M_0 Stage IV B Any T N_2 M_0, Any T N_3 M_0 Stage IVC Any T Any N M_1

Diagnosis

- X-ray of the part-opacity of the involved sinus with destruction of bony walls is seen.
- CT scan – ideal method.
- Biopsy is done through nasal / oral or on early stage through Caldwell-Luc operation.
- Sinus endoscopy for detailed examination of sinus and for biopsy.



Fig. 3.67: Incision for Caldwell-Luc operation which is used for taking biopsy from maxillary tumour. Incision is not used for definitive therapy for carcinoma maxilla. Incision also used in benign conditions to approach maxillary sinus. Gingivo buccal mucosa is incised and mucoperiosteum is raised. Bone of canine fossa is cut to reach the maxillary antrum.



Figs 3.68A to D: Carcinoma maxilla extending into the nose with X-ray and CT pictures. It is a fairly advanced growth.

Hope sees the invisible, feels the intangible and achieves the impossible.



Fig. 3.69: Carcinoma maxillary antrum extending outwards on to all walls. An advanced malignancy.

Treatment

- *Preoperative megavoltage radiotherapy* is given. After six weeks, *total maxillectomy* is done. Reconstruction of maxilla along with dental reconstruction is required.



Fig. 3.70: Weber-Fergusson's incision used for total maxillectomy.

- When lymph nodes are involved radical neck lymph nodes dissection is done.
- Postoperative radiotherapy and chemotherapy is given as an adjuvant therapy.
- Overall prognosis is 30-40%.

MALIGNANT TUMOURS OF TONSIL

- **Carcinoma of tonsil**: It is squamous cell carcinoma, similar to carcinoma cheek, but more aggressive with poor prognosis.
- **Carcino-sarcoma** of tonsil.
- **Lymphoma**—NHL type.

CARCINOMA HARD PALATE

- Minor salivary gland tumours are more common in palate.



Fig. 3.71: Minor salivary gland tumour in posterior half of the palate. Note the nodular lesion with ulceration over the summit. (*Courtesy by Professor Kishore Chandra Prasad ENT surgeon and head of the department and Dr Sampath ENT Surgeon KMC Mangalore*)

- In males, *in reverse smokers* (*Churat* is rolled tobacco leaf) squamous cell carcinoma is seen in palate due to repeated thermal injury.
- Malignant tumours may spread to periosteum, bone, maxilla, sinus, or nose.
- Salivary gland tumours are commonly malignant and are of adenoid cystic type. Other types also can occur. It presents as a single, solid, smooth swelling with ulcer over the summit.
- Squamous cell carcinoma is ulcerative with raised and everted edge.
- Upper deep cervical lymph nodes are involved in 25% of patients.
- Investigations are edge biopsy, FNAC lymph node and CT scan to see extensions.
- *Treatment* is wide excision with removal of the underlying palatal bone. Often partial or total maxillectomy (*Weber—Fergusson* incision) may be required. Myocutaneous flap with dental prosthesis is essential to reconstruct after surgery. Postoperative radiotherapy and neck block dissection are often required.



Fig. 3.72: Carcinoma hard palate extending laterally.

LARYNGEAL TUMOURS

BENIGN

- *Epithelial* can be papilloma, vocal nodule or vocal polyp.
  Papilloma is usually single in adult, multiple in children.
- *Connective tissue tumours* like fibroma, myxoma, angioma.

Indirect laryngoscopy (ILS) or direct laryngoscopy confirms the diagnosis.

Childhood papilloma	*Adult papilloma*
Multiple, of viral origin (Papova)	Single, of neoplastic origin
Can occur in glottic, supra and infraglottic	Glottic only
Not premalignant	Premalignant
Recurrence common	Not common after complete excision
Excision is difficult	Easier removal
Causes more dyspnoea, *stridor*, cough	Hoarseness only
May require tracheostomy	

Note: Stridor can be inspiratory, expiratory or biphasic.

Treatment

- Endoscopic removal. Application of podophyllum
- Cryosurgery, Laser surgery.

MALIGNANT TUMOURS OF LARYNX

Aetiology

- Smoking, tobacco.
- Alcohol intake.



Fig. 3.73: Anatomy of larynx showing supraglottic, glottic and subglottic regions.

- Occupational / industrial exposure to chemicals like mustard gas, asbestos, benzopyrones, petroleum products.
- Previous radiation.
- Genetic- Russians develop familial laryngeal cancers.
- Papilloma, virus, keratosis, malnutrition.

Incidence

- Squamous cell carcinoma is commonest (95%).
- Common in males (10 : 1).
- Common in 5th/6th decade.

Types

- Ulcerative.
- Proliferative.

Anatomical Types

- **Supraglottic (25%):** It arises from infrahyoid part of epiglottis, ventricles, and arytenoids. It spreads to neck lymph nodes early (40%) due to rich lymphatics in this area. Throat pain, dysphagia, palpable neck nodes and referred pain are common features. Hoarseness of voice, loss of weight, respiratory

Efforts and energies should be consistent, constructive and compassionate.

obstruction, and halitosis are late features. Carcinoma in epiglottis causes bilateral nodal spread. Local spread occurs to vallecula, base of tongue and pyriform fossa.

- **Glottic (65%):** It is the commonest type. It begins from upper part or free edge of vocal cords (mid or anterior) often extending 10 mm below. Lymphatic spread is slow (only 4%) as this area has got least lymphatics. Opposite vocal cord can involve as *kiss cancer*. Vocal cord mobility is unaffected in early cases. Vocal cord fixation signifies spread to thyroarytenoid which is a poor prognostic sign. It presents very early due to hoarseness of voice. Eventual cord fixation causes stridor. Locally it spreads anteriorly to anterior commissure, posteriorly to vocal process and arytenoids, above to ventricle and false vocal cords, below to subglottis.
- **Subglottic (2%)** is less common involving undersurface of true vocal cords and subglottic space. It spreads to deep cervical and paratracheal nodes (20%). Upward spread is rather late and so hoarseness is not an early symptom in this type. It can spread through cricothyroid membrane or thyroid gland.

Note:

- *In Indian subcontinent supraglottic tumours are more common than glottic. Glottic type is common in Western countries.*
- *Fixation of cords is due to involvement of thyroarytenoid muscle or cricoarytenoid joint.*

Clinical features	*Investigations*
• Hoarseness of voice • Pain and discomfort • Cough. dyspnoea, stridor, dysphagia in late cases • Bloody sputum • Palpable neck nodes, which eventually get fixed • Absence of laryngeal crepitus • Common in males- 10:1	• ILS (Indirect laryngoscopy Direct laryngoscopy and biopsy • CT neck-*very useful investigation* • Chest X ray • FNAC of lymph node • Microlaryngoscopy in small lesions to identify and to have proper biopsy • Toluidine blue staining to stain early superficial cancers which facilitate the accurate biopsy • Hopkin's endoscopy • Flexible, fibreoptic laryngoscopy



Fig. 3.74: Laryngeal carcinoma types. Note the typical sites. Glottic is the commonest site. Next is supraglottic. Subglottic is rare.


Median GE fold
Vallecula
Epiglottis
Tubercle
Vestibular fold
Vocal fold
Pyriform fossa
Lateral GE fold
Aryepiglottic fold
Tracheal rings
Cuneiform
Corniculate

Fig. 3.75: View of larynx as seen through a laryngoscope.


ILS Mirror
Tongue
Larynx

Fig. 3.77: Indirect laryngoscopy to visualise larynx and its parts.



Fig. 3.76: Endoscopic view of vocal cords, pyriform fossa and aryepiglottic fold.

Staging

Tumour

T1 Tumour confined to one anatomical site in larynx with normal cord mobility.
T2 Tumour confined to one anatomical region within larynx.
T3 Tumour spreads beyond one anatomical region within larynx with cord fixation.
T4 Tumour spreads beyond larynx.

Nodal staging is similar to any other oral carcinomas.



Figs 3.78A and B: Carcinoma larynx—Patients underwent total laryngectomy with permanent tracheostomy.

He who believes, is strong; he who doubts, is weak.

Treatment

- *Supraglottic*—Stage I—Curative radiotherapy is the choice. In stage II and III total laryngectomy and block dissection of neck nodes.
- *Glottic*: Radiotherapy is the choice as nodes are commonly not involved. Endoscopic laser surgery or open partial laryngectomy can be done.
- *Subglottic*: Total laryngectomy is the treatment of choice with nodal block when needed.
- *In advanced stage IV* carcinomas surgery and radiotherapy both are not possible. Here chemotherapy is given using cyclophosphamide, cis platin and methotrexate.
- *In advanced resectable tumours, induction chemotherapy for 3 cycles with methotrexate and cisplatin 100 m/sq metre BSA (at 0, 22. 43 days) and total laryngectomy is under trial. Concurrent chemotherapy and radiotherapy are also under trial in these cases.*

Role of Radiotherapy in Laryngeal Cancer

- In early growth with no impairment in motility curative RT is very useful with 90% cure rate with preservation of voice
- It is commonly used in superficial exophytic lesions, growth in tip of epiglottis and aryepiglottic folds.
- In subglottic extension, fixed growths, and in presence of nodes, radiotherapy is less effective.

Conservative laryngeal surgery

Indications	*Advantages*
• Early growth without fixation especially glottic type	• Permanent tracheostomy is avoided • Voice is retained
Types	*Disadvantages*
• Cordectomy through laryngofissure–excision of vocal cord after splitting of larynx • Partial frontolateral laryngectomy–excision of vocal cord and anterior commissure • Partial horizontal laryngectomy–excision of supraglottis (epiglottis, aryepiglottic folds, false vocal cords and ventricle)	• Inadequate clearance • Recurrence of the disease



Fig. 3.79: Gluck-Sorenson's laryngectomy incision. Extension lines sideward can be used for adding radical neck dissection.

Total laryngectomy

Indications	*Technique*
• T_3 lesions with cord fixation • All T_4 lesions • Bilateral arytenoids spread • Thyroid/cricoid spread • Transglottic cancers involving ventricle with fixation of the cord • Posterior commissure disease • Failure of conservative surgery or RT *Problems* • Mortality of surgery • No speech • Having permanent tracheostomy and its problems	• Entire larynx with hyoid bone, pre-epiglottic space, strap muscles, one or more rings of trachea are removed • Pharyngeal wall is repaired • Lower tracheal stump is sutured to the skin as permanent tracheostomy • Often laryngo-oesophagectomy is done when pharyngeal spread is present. Gastric pull-up is done to maintain GI continuity • Technique may be combined with neck nodal dissection both sides

Care after total laryngectomy

- Speech therapy by pseudoglottis creation, battery operated artificial larynx or Singer-Blom prosthesis or Panje's prothesis. Tracheo-oesophageal prosthesis (TOP) is ideal
- Social and job rehabilitation
- Care of permanent tracheostomy by avoiding immersion in the water, care during bath, shower use and swimming. Shower covers are available for this purpose

- Often along with total laryngectomy, total thyroidectomy and removal of parathyroid glands are required. Patient then needs supplementation of thyroxine and calcium for life time

Self-assessment Questions

- Discuss the aetiology, clinical features and management of carcinoma cheek.
- Erythroplakia.
- Leukoplakia.
- Submucosal fibrosis.
- Premalignant conditions of cheek.
- Ranula.
- Sublingual dermoid.
- Management of carcinoma tongue.
- Price-Hill regime.
- Staging of carcinoma cheek.
- Carcinoma maxillary antrum.
- Carcinoma lip.
- Minor salivary gland tumour.
- Clinical features of carcinoma tongue.
- Lymphatic drainage of tongue. Causes for ulcer tongue.

The road to success is paved with good intentions.

4

Salivary Glands

> ***(Three weeks after arriving at the anatomy laboratory of Gerhard Blasius in Amsterdam) fortune so favoured me that in the first sheep's head, which I…was dissecting alone in my room, I found a duct which, so far as I knew, had been described by no one before.***
>
> ***—Niels Stensen***, 1661

Anatomy
Sialography
Salivary calculus
Sialosis
Sialectasis
Recurrent childhood parotitis
Parotid abscess
Parotid fistula
Sjögren's syndrome
Mikulicz disease
Salivary neoplasms
Minor salivary gland tumours
Parotid lymphoma
Frey's syndrome
Parotidectomy
Facial nerve injury

ANATOMY

Parotid Gland *(Para—around, otis—ear)*

It is the largest of the salivary gland, situated below the acoustic meatus between the ramus of mandible and sternomastoid muscle. The deep cervical fascia splits to form a capsule (parotid capsule) to enclose the gland. The superficial layer is thickened and adherent to the gland.

Parts of the Parotid Gland

- Superficial part (80%)—lies over the posterior part of the ramus of mandible.
- Deep part (20%)—lies behind the mandible and medial pterygoid muscle; in relation to mastoid and styloid process.



Fig. 4.1: Superficial lobe (80%) and deep lobe (20%) are separated by external carotid artery, retromandibular vein and facial nerve from deep to superficial.

Accessory parotid is prolongation of the gland along the parotid duct.

Parotid (*Stensen's*) duct is 2-3 mm in diameter, 5 cm in length, begins behind the angle of the mandible, runs over the surface of the masseter muscle, passes through the buccinator muscle, and opens into the oral mucosa opposite to the crown of upper second molar tooth.

Facial nerve emerges from the stylomastoid foramen lying between external auditory meatus and mastoid process. It passes around the neck of the condyle of mandible and becomes superficial, later dividing into *temporofacial and cervicofacial branches* which in turn divides into many branches. Some of these may be interconnected *as pes anserinus* (goose foot). *Branches are*


Facial nerve
Masseter
Parotid gland
Posterior belly of digastric

Fig. 4.2: Anatomical relations of the parotid gland.

– temporal (auricularis anterior and superior part of frontalis), zygomatic (frontalis and orbicularis oculi), upper buccal and lower buccal (buccinator, orbicularis oris, elevators of the lip) mandibular (lower lip muscles) and cervical (platysma).

Blood supply is from external carotid artery; and venous drainage is by external jugular vein.

Nerve supply is from autonomic nervous system, parasympathetic is secretomotor from auriculotemporal nerve, sympathetic is vasomotor from plexus around the external carotid artery.

Facio-venous plane of Patey is of surgical importance.


Temporal branch
Upper branch
Zygomatic branch
buccal branch
Parotid
Mandibular branch
Lower branch
Cervical branch

Fig. 4.3: Pes anserinus.


Superficial temporal vein
Superficial temporal artery
Maxillary vein
Maxillary artery
Transverse facial artery
Parotid duct
Retromandibular vein
Maxillary vein
Posterior auricular vein
Parotid gland
Posterior auricular artery
Facial vein
External jugular vein
External carotid artery

Fig. 4.4: Vascular plane of parotid.

Structures within the parotid gland from deep to superficial –

- External carotid artery, maxillary artery, superficial temporal artery, posterior auricular artery
- Retromandibular vein (by maxillary and superficial temporal veins)
- Facial nerve with its branches

Great auricular nerve (cutaneous sensory around angle and lower part of the ear lobule) and auriculotemporal nerve which is from mandibular division of trigeminal nerve (secretomotor to parotid gland) are other nerves present in relation to parotid gland.

Submandibular Salivary Gland

It is a 'J' shaped salivary gland situated in the anterior part of the digastric triangle.

Parts

- *Superficial part*: Lies in submandibular triangle, superficial to mylohyoid and hyoglossus muscles, between the two bellies of digastric muscle.
- *Deep part* is in the floor of the mouth and deep to the mylohyoid.

Submandibular (*Wharton's*) duct (5 cm), emerges from the anterior end of the deep part of the gland, enters the floor of the mouth, on the summit of papilla beside the frenulum of the tongue.

Both over-salivation and under-salivation is not advised. Only optimum salivation is accepted and ideal.


Lingual nerve
Nerve to mylohyoid
Medial pterygoids
Posterior belly of digastric
Hypoglossal nerve
Facial artery
Submandibular salivary gland

Fig. 4.5: Anatomical relations of the submandibular salivary gland.

A


Styloglossus
Deep lobe SMSG
Digastric
Mid constrictor
Hyoglossus
Mylohyoid
Hyoid bone

B


Submandibular ganglion
Digastric muscle
Sublingual gland
Lingual nerve
SMSG duct
Lingual artery and vein
Hypoglossal nerve (12)
Deep submandibular gland

Figs 4.6A and B: Relations of the submandibular salivary gland and its deep lobe.

Lingual nerve and submandibular ganglion are attached to upper pole of the gland. Hypoglossal nerve is deep to the gland.

Facial artery emerges from under surface of the stylohyoid muscle, enters the gland from posterior and deep surface, reaching its lateral surface crossing the lower border of mandible to enter the face.

Venous drainage is to anterior facial vein.

Nerve supply: Branches from the submandibular ganglion.

Resting salivary flow usually arises from the submandibular salivary gland. *Sialorrhoea* is increased salivary flow often seen due to drugs, in cerebral palsy, physically handicapped person, children, and psychiatry patients. Intractable sialorrhoea can be corrected by different surgeries to submandibular salivary gland like duct repositioning to excision of the gland.

Xerostomia is decreased salivary flow. It is seen in post menopausal women, depression, dehydration, use of antidepressant drugs; anticholinergic drugs, Sjogren's syndrome, radiotherapy to head and neck region.

Minor Salivary Glands

There are around 450 minor salivary glands which are distributed in lips, cheeks, palate and floor of the mouth. Glands also may be present in oropharynx, larynx, trachea and paranasal sinuses. They contribute to 10% of total salivary volume. *Sublingual glands* are minor salivary glands one on each side; located in the anterior aspect of the floor of the mouth in relation to mucosa, mylohyoid muscle, body of the mandible near mental symphysis. Gland drains directly into mucosa or through a duct which drains into submandibular duct. This duct is called as *Bartholin duct*. Minor salivary glands are not present in gingivae and anterior portion of the hard palate.

Ectopic Salivary Gland

Ectopic salivary gland also called as aberrant salivary gland is nothing but ectopic lobe of the juxtaposed salivary gland. It is commonly seen in relation to submandibular salivary gland. Commonest ectopic salivary tissue is *Stafne bone cyst*. It is invagination of the juxtaposed submandibular salivary gland into the mandible bone on its lingual aspect. X ray shows radiolucent area due to the cyst below the angle of the mandible, lower to inferior dental vessels and nerve.

SIALOGRAPHY



Fig. 4.7: Sialogram X-ray done to visualise the ductal pattern in parotid.

Indications

1. Salivary fistulas.
2. Sialectasis.
3. Congenital conditions.
4. Extraglandular masses.
5. Parotid duct stones.

Dye used is lipiodol or sodium diatrizoate (Hypaque).

24-gauge cannula is passed into either Stensen's duct or Wharton's duct and one ml of the dye is injected into the duct and X-ray is taken.





Figs 4.8A and B: Submandibular gland sialogram pictures. (*Courtesy by Professor Kishore Chandra Prasad, ENT surgeon and HOD KMC Mangalore; Dr Sampath MS ENT KMC Mangalore*).

Findings
- Narrowing (Stricture)
- Grape like cluster appearance (Sialectasis)
- Dilatations
- Communications (Fistulas)
- Mass lesions

Precautions

1. *Sialography should never be performed in acute inflammation.*
2. Only one ml of dye should be injected, if more dye is injected it causes *extravasation and chemical sialadenitis.*

SALIVARY CALCULUS AND SIALADENITIS

- 80% Submandibular.
- 80% Radio-opaque.
- It is commonly calcium phosphate and calcium carbonate stones.
- Calculi are more common in submandibular gland, because the gland secretion is viscous, contains more calcium and also, its drainage is nondependent, causing stasis.
- Secretion from parotid is serous, contains less calcium and so stones are not common.

How a person masters his fate is more important than what his fate is.



Fig. 4.9: Submandibular sialadenitis in a young boy who required excision of gland.



Fig. 4.10: Stone in the submandibular salivary gland as seen in X-ray (*By Dr Jagdish, Mangalore*).

Salivary calculi

Submandibular gland	*Parotid gland*
80% *common*	20% incidence (*Rare*).
80% Radiopaque	Radiolucent
Seen in plain X-ray (intra-oral)	Not seen in plain X-ray
Sialogram is not needed	Identified by sialogram

Calculi are common in submandibular salivary gland, because—

- Viscous nature and mucin content
- Calcium content
- Nondependent drainage
- Stasis

Causes for submandibular sialadenitis	*Types of sialadenitis*
• Bacterial – more common. It is usually due to obstruction and stasis • Trauma over duct causing oedema/stricture and stasis • Viral – mumps – rare	• *Acute* – Bacterial – occurs in submandibular salivary ductal obstruction (Wharton's) or in parotid gland. In parotid, suppuration can occur leading into parotid abscess – Viral – common in parotid • *Chronic* – common after partial obstruction of submandibular gland duct or due to stones in submandibular gland or hilum proximal to the level of crossing of the lingual nerve over the duct

Presentation

Acute features:

- Pain, swelling, tenderness is seen in submandibular region and floor of the mouth.
- Duct is inflamed and swollen.

Features in chronic cases (chronic sialadenitis):

- Pain is more during mastication due to stimulation. (*Salivary colic* which can be induced by meals, lemon juice, etc).
- Salivary secretion is more during mastication causing increase in gland size.
- Firm, tender swelling is palpable bidigitally.
- When stone is in the duct, it is palpable in the floor of the mouth as a tender swelling with features of inflammation in the duct. Pus exudes through the duct orifice. (Irritation of the lingual nerve, which is in very close proximity to submandibular salivary duct, causes referred pain tongue – *lingual colic*).
- In submandibular salivary gland, often the stones are multiple, with chronic inflammation of gland (***sialadenitis***).

Differential Diagnosis

- Submandibular lymphadenitis.
- Salivary neoplasm.

Investigations

- Intra oral X-ray (dental occlusion films) to see radiopaque stones.
- FNAC of the gland to rule out other pathology.
- Total count and ESR in acute phase.



Fig. 4.11: Stone in the duct of submandibular salivary gland (Wharton's duct).



Fig. 4.12: Excised specimen of submandibular salivary gland with stone in the gland.



Fig. 4.13: X-ray (OPG) showing left sided submandibular salivary stone.

Treatment

- If the stone is in the duct, removal of the stone is done intraorally, by making an incision in the duct. Incised duct is not sutured as it may result in stricture.
- If stone is in the gland, *excision of submandibular* gland is done.



Fig. 4.14: Incision for removal of the submandibular salivary gland.



Fig. 4.15: Incision for excision of submandibular salivary gland. It should be 2-4 cm below the margin of the mandible to avoid injury to marginal mandibular nerve.

> *Diagnosis means finding the cause of the disorder, not just giving its name.*—Sydney Walker

Approach is from submandibular region (outside). An incision is made on the skin in submandibular region, about 5-8 cm length, parallel to and 2-4 cm below the mandible. Incision is deepened through the deep fascia until the gland is visualised without raising the flaps (so as to avoid injury to marginal mandibular nerve, branch of facial nerve). Facial artery is ligated twice. Lingual nerve and hypoglossal nerves are taken care of. Mylohyoid is retracted so as to remove the deep portion of the gland. Drain is placed after removal of the gland.

Antibiotic coverage is a must.

Complications of Surgery

1. Haemorrhage.
2. Infection.
3. Injury to marginal mandibular nerve, lingual nerve, hypoglossal nerve.
4. Injury to nerve to mylohyoid causing anaesthesia over submental skin.

Note: *Stone in parotid duct* can be removed by opening the duct longitudinally. *Stone in the gland* or in collecting duct is treated by parotidectomy.

Indications for submandibular salivary gland excision	*Steps in submandibular salivary gland excision*
• Chronic sialadenitis • Submandibular salivary tumours *Pathway of secretomotor fibres of the submandibular and sublingual salivary glands* Superior salivary nucleus ↓ Preganglionic fibres ↓ Facial nerve, Chorda tympani nerve ↓ Lingual nerve ↓ Submandibular ganglion - post ganglionic fibres ↓ Submandibular and sublingual salivary glands	• Anaesthesia – general • Position – neck extension with chin to opposite side • Incision – 2-4 cm (3 cm) below and parallel to the margin of the mandible 5-8 cm in length (6 cm) • Mobilisation of the gland – intracapsular in sialadenitis; extracapsular in tumours with ligation of anterior facial vein • Facial artery ligation proximally and distally as artery is in the groove posteriorly • Dissection of deeper lobe from mylohyoid muscle • Identification of lingual and hypoglossal nerves • Duct identification and ligation • Wound closure with a suction drain

Rule of 2 in submandibular salivary gland

- 2 parts divided by mylohyoid muscle
- 2 condition affect it—tumour and stone
- 2 superficial nerves—cervical and mandibular branch of facial nerves
- 2 deep nerves—lingual and hypoglossal nerves
- Incision—2-4 cm below the mandible
- Ligate facial artery at 2 places

SIALOSIS

It is enlargement of the salivary gland due to fatty infiltration, as a result of various metabolic causes like diabetes, acromegaly, obesity, liver disease, alcoholism, bulimia, idiopathic, drug induced (sympathomimetics, carbimazole, thiouracil).

Clinical features: Bilateral diffuse enlargement of parotids, which is smooth, firm, nontender.

Treatment: The cause is treated.

SIALECTASIS

- It is an aseptic dilatation of salivary ductules causing grape like (cluster like) dilatations.
- It is a disease of unknown aetiology with destruction of parenchyma of gland accompanied by stenosis and cyst formation in the ductules.
- It is common in parotids; often bilateral.
- Presents as a smooth, soft, fluctuant, nontransilluminating swelling which increases in size during mastication. It is tender initially. It lasts for many days with a long symptom-free period of the disease.
- Sialogram is diagnostic (grape-cluster like dilatations).
- Treatment is conservative (nonsurgical).

RECURRENT CHILDHOOD PAROTITIS

It is a recurrent, rapid enlargement of one or both parotids with fever and malaise in children of age group between 3-6 years without any known aetiology. Recurrent episodes with a quiescent period in between are typical. Sialogram shows snowstorm punctate sialectasis. Low dose antibiotics for long period may be required. Occasionally patient may need total conservative parotidectomy especially if it occurs late in adolescent period.

PAROTID ABSCESS (SUPPURATIVE PAROTITIS)

- It is a result of an *acute bacterial sialadenitis* of the parotid gland.

- It is an ascending bacterial parotitis, due to reduced salivary flow, dehydration, starvation, sepsis, after major surgery, radiotherapy for oral malignancies and poor oral hygiene.
- Parotid fascia is densely thick and tough and so parotid abscess does not show any fluctuation until very late stage.
- Causative organism are *Staphylococcus aureus* (commonest), *Streptococcus viridans* and often others like gram-negative and anaerobic organisms.

Causes of acute parotitis (Differential diagnosis of suppurative parotitis)

- Viral—Mumps, Coxsackie virus A and B, parainfluenza 1 and 3, Echo and lymphocytic choriomeningitis
- Bacterial—*Staphylococcus aureus*
- Allergic
- HIV infection
- Radiotherapy, postoperative period
- Specific infections like syphilis
- Sjogren's syndrome often causes bilateral parotitis

Clinical Features

- Pyrexia, malaise, pain and trismus.
- Red, tender, warm, well-localised, firm swelling is seen in the parotid region (brawny induration).
- Tender lymph nodes are palpable in the neck.
- Features of bacteraemia are present in severe cases.
- Pus or cloudy turbid saliva may be expressed from the parotid duct opening.

Investigations

- U/S of the parotid region.
- Pus collected from duct orifice is sent for culture and sensitivity.
- Needle aspiration from the abscess is done to confirm the formation of pus.

Sialogram is contraindicated in acute phase, as it will cause retrograde infection leading into bacteraemia.

Note: In suppurative parotitis patient may develop severe laryngeal or pharyngeal oedema and may require steroids, tracheostomy and critical care.

Complications of suppurative parotitis and parotid abscess

- Septicaemia
- Severe trismus
- Rupture into the external auditory canal

Treatment

1. Antibiotics are started depending on culture report.
2. When it is severely tender and localised, incision and drainage is done under G/A.

Areas where one should not wait for the abscess to form:

- Parotid
- Breast
- Ischiorectal fossa
- Thigh

Skin is incised in front of the tragus vertically and then parotid sheath is (pyogenic membrane) opened horizontally. Pus is drained using sinus forceps and sent for C/S. Antibiotics are continued (***Blair's incision***).



Fig. 4.16: Blair's incision used to drain the parotid abscess.

3. Proper hydration, mouth wash using povidone iodine/potassium permanganate solutions, nutrition. Often patient with parotid infection needs admission and treatment.

PAROTID FISTULA

Parotid fistula may arise from *parotid gland* or *duct* or *ductules*. It may open inside the mouth as internal fistula; or open outside onto the skin as external fistula. Fistula from the duct has profuse discharge. Fistula from the gland often shows only minimal discharge.

Causes

- After superficial parotidectomy.
- After drainage of parotid abscess, ruptured abscess.

By perseverance the snail reached the ark.—Charles Haddon Spurgeon



Fig. 4.17: Parotid fistula with discharging saliva and pus.

- After biopsy.
- Trauma.
- Recurrence of malignant tumour.

Clinical Features

- Discharging fistula in the parotid region of the face, and discharge is more during eating.
- Tenderness and induration.
- Trismus.

Diagnosis

- Sialography to find out the origin of the fistula whether from parotid gland or duct or ductules.
- Fistulogram or CT fistulogram.
- Discharge study.
- MRI.

Treatment

- Anticholinergics - hyoscine bromide (probanthine).
- Radiotherapy.
- Often exploration of fistula is required.
- Repair or reinsertion of the duct into the mucosa.
- *Newman Seabrock's operation* – A probe is passed into the parotid duct through the opening in the mouth. Another probe is passed through the fistula. Duct and fistula are dissected over the probe. After removal of the fistula track severed duct ends are identified; and ends are trimmed. Probes are removed. A tantalum wire is passed into the duct across the severed ends and duct is sutured over it using 4 zero vicryl. Tantalum stent is removed after 3 weeks.
- If still persists, auriculotemporal nerve which supplies secretomotor component of parotid is cut.
- If there is stenosis at the orifice of the Stenson's duct, papillotomy at the orifice may help.
- Total conservative parotidectomy is done in failed cases.

Remember about salivary fistula

- Commonly from the parotid
- It can be *internal* draining in to the mouth or can be *external* draining outside
- It is *acquired commonly* but rarely can be congenital
- It can be due to surgery, trauma or due to sepsis
- Fistula arising from the *gland parenchyma* drains through suture line but usually closes spontaneously. Leakage will be more during meals Saliva is confirmed by its high amylase content compared to seroma/serous fluid
- Fistula due to *ductal disruption* leaks profusely and invariably needs surgery to close it
- Submandibular gland fistula commonly closes spontaneously, rarely if not requires complete removal of the gland
- Anticholinergics, irradiation, denervation of the gland, duct ligation are done to reduce saliva production
- Excision of fistula, repair of the duct, diversion of the duct in to the mouth are other options
- In severe intractable cases, removal of the gland/ total conservative parotidectomy is needed

SJÖGREN'S SYNDROME

It is an autoimmune disease causing progressive destruction of salivary and lacrimal glands, leading to *keratoconjuctivitis sicca (dry eyes), and xerostomia (dry mouth).*

Types

1. Primary.
2. Secondary.

Primary Sjogren's Syndrome:
- Severe dry mouth.
- Severe dry eyes.
- Widespread dysfunction of exocrine glands.
- Incidence of developing lymphomas is high.
- There is no association of connective tissue disorders.

Secondary Sjogren's Syndrome:
- Dry mouth.
- Dry eyes.
- With association of connective tissue disorders like – Primary biliary cirrhosis (near 100%).

  - SLE (30%).
  - Rheumatoid arthritis (RA) (15%).
- Female to male ratio is 10 : 1.

Clinical Features

- It is common in middle aged females who present with dry eyes, dry mouth, enlarged parotids and enlarged lacrimal glands.
- Often they are tender.
- Superadded infections of the mouth, Candida albicans is common.

Investigations

1. Autoantibody estimation—rheumatoid factor, anti-nuclear factor, salivary duct antibody.
2. Sialography.
3. Estimation of salivary flow.
4. Slit lamp test of eyes.
5. Schirmer test – to detect lack of lacrimal secretion.
6. FNAC of parotids and lacrimal glands.
7. ^{99}Technetium pertechnetate scan for gland function.

Treatment: It is conservative.

1. Artificial tears.
2. Artificial saliva.
3. Frequent drinking of water.
4. Treat the cause.

MIKULICZ DISEASE

- It is a clinical variant of Sjogren's syndrome
- It is an autoimmune disorder of salivary and lacrimal glands, resulting in infiltration of the glands with round cells.

Triad

1. Symmetrical and progressive enlargement of all salivary glands
2. Narrowing of palpebral fissures due to enlargement of the lacrimal glands
3. Parchment like dryness of the mouth

SALIVARY NEOPLASMS

Classification

a. ***Epithelial*** (90%):
  1. *Adenomas*
     - Pleomorphic adenoma.
     - Monomorphic adenomas.



Fig. 4.18: Partoid enlargement in a boy of 11 year old.

       - Adenolymphoma (Warthin's tumour).
       - Oxyphil adenomas.
       - Oncocytoma (oxyphil adenoma) seen in elderly; seen in parotid gland.
       - Basal cell adenoma – It is a rare benign tumour.
  2. *Carcinomas*
     - Mucoepidermoid carcinoma—Most common malignancy.
     - Acinic cell carcinoma—1%.
     - Adenoid cystic carcinoma—very aggressive.
     - Adenocarcinoma.
     - Squamous cell carcinoma—2%.
     - Carcinoma in ex. pleomorphic adenoma.
     - Undifferentiated carcinoma.

b. ***Nonepithelial:***
  - Haemangioma—commonly seen in infants, usually in parotids. Spontaneous regression is common. Most common benign salivary gland tumour in paediatric age group.
  - Lymphangioma.
  - Neurofibromas and neurilemmomas.

c. ***Malignant lymphomas—NHL type*:**
  - Common in parotids.
  - Common with HIV, Sjogren's syndrome (44 times more chances than normal people).

d. Secondary tumours from head and neck region; bronchus and skin.

Tumours of ectopic salivary glands are of low grade malignancy (cylindroma) may ultimately metastasize to regional lymph nodes, the viscera and the skeleton. —Kenneth Harrison



Figs 4.19A and B: Neoplasm of parotid gland.

e. Lymphoepithelial tumours–
   Benign – It is 5% of all benign salivary tumours (*Godwin's tumour*). It is common in females; can be bilateral.
   Malignant – It is rare tumour occurs in parotid and submandibular glands (ESKIMOMA).

Incidence

- Eighty per cent salivary neoplasms are in the parotids of which 80% are benign. 80% of these are pleomorphic adenomas.
- Fifteen per cent of salivary tumours are in the submandibular salivary gland, of which 50% are benign. 95% of these are pleomorphic adenomas.
- Ten percent of salivary neoplasms are in the minor salivary glands—palate, lips, cheeks, and sublingual glands. Of these only 10% are benign.

Note: Parotid tumours are common but only 20% are malignant. Submandibular tumours are uncommon but 50% of them are malignant. Minor salivary gland tumours (other than sublingual glands) are rare and 90% of them are malignant. Sublingual salivary tumours are very rare but almost all sublingual salivary tumours are malignant.

PLEOMORPHIC ADENOMA (Mixed salivary tumour)

- Commonest of the salivary gland tumour.
- It is 80% common.
- More common in parotids (80%).
- It is mesenchymal, myoepithelial and duct reserve cell origin.

Grossly it contains cartilages, cystic spaces, solid tissues.

Histologically it shows:
- Epithelial cells
- Myoepithelial cells
- Mucoid material with myxomatous changes
- Cartilages/pseudocartilages



Fig. 4.20: Pleomorphic adenoma.

- Even though it is capsulated, tumour may come out as pseudopods and may extend beyond the main limit of the tumour tissue.
- When disease occurs in parotid, commonly it involves superficial lobe or superficial and deep lobe together.
- But sometimes only deep lobe is involved and then it presents as swelling in the lateral wall of the pharynx, soft palate and posterior pillar of the fauces. There may not be any visible swelling in the preauricular region. It is called as *dumb bell tumour***.** This tumour is in relation to styloid process, mandible, stylohyoid, styloglossus, stylopharyngeus muscles.

Clinical Features

Clinical features of parotid tumour

- Raised ear lobule
- Cannot be moved above the zygomatic bone—curtain sign
- Deviation of uvula and pharyngeal wall towards midline in case of deep lobe tumour
- Facial nerve, masseter, skin, lymph node and bone involvement eventually occurs in case of malignancy

- 80% common.
- 1:1 male to female ratio.
- Occurs in any age group.
- Usually unilateral.
- Present as a single painless, smooth, firm lobulated, mobile swelling in front of the parotid with *positive curtain sign* (As the deep fascia is attached above to the zygomatic bone, it acts as a curtain, not allowing the parotid swelling to move above that level. Any swelling superficial to the deep fascia will move above the zygomatic bone.).
- Obliteration of retromandibular groove is common.

- The ear lobule is lifted.
- When deep lobe is involved, swelling is commonly located in the lateral wall of pharynx, posterior pillar and over the soft palate—10%.
- Facial nerve is not involved.



Figs 4.21A and B: Typical parotid swelling with ear lobe raised. Facial nerve should be tested by clenching the teeth.

Long-standing pleomorphic adenoma may turn into carcinoma (carcinoma in ex. pleomorphic adenoma). Its features are:

- Recent increase in size
- Pain and nodularity
- Involvement of skin, ulceration
- Involvement of masseter
- Involvement of facial nerve—Lower facial nerve palsy—(Difficulty in closing eyelid, difficulty in blowing and clenching teeth)
- Involvement of neck lymph node



Fig. 4.22: Typical parotid tumour—a pleomorphic adenoma.



Fig. 4.23: Parotid tumour showing typical raise in ear lobe.

Complications

- Recurrence—5-50%.
- Malignancy.
  —3-5% in early tumours.
  —10% in long duration (15 or more years) tumours.

Investigations

- FNAC is very important and diagnostic.
- CT scan to know the status of deep lobe, local extension and spread.
- MRI is better method.

Note: Incision biopsy of parotid tumour is contraindicated as chances of seedling and recurrence are high and also

Remember that the faith to move a mountain always carries a pick. — Anonymous



Fig. 4.24: CT picture of pleomorphic adenoma.

there is a chance of injuring the facial nerve while doing the biopsy.

Treatment

- Surgery—First line treatment.
- If only superficial lobe is involved, then superficial parotidectomy is done wherein parotid superficial to facial nerve is removed.
- If both lobes are involved, then total conservative parotidectomy is done by retaining facial nerve.

Note: Enucleation is avoided as the recurrence rate is high.



Figs 4.25A to C: Recurrent parotid tumour which has attained large size. Note facial nerve is intact. Duct orifice should be inspected using retractor.

ADENOLYMPHOMA (Warthin's Tumour, Papillary Cystadenolymphomatosum)

- It is a misnomer. It is not malignant, it is not lymphoma.
- It is a benign tumour that occurs only in parotid, usually in the lower pole.
- It is said to be due to trapping of jugular lymph sacs in parotid during developmental period.

- It composed of *double layer of columnar epithelium*, with papillary projections into cystic spaces with lymphoid tissues in the stroma.
- It usually involves only superficial lobe of parotid gland. It may also be multicentric.

Clinical Features

- It presents as a slow growing, smooth, soft, cystic, fluctuant swelling, in the lower pole, often bilateral and is nontender.
- It is common in males – 4:1.
- Common in old people – 60 years.
- Its incidence is 10%.
- It is often bilateral – 10%.

Investigations

- Adenolymphoma produces a *"hot spot"* in ^{99}Technetium pertechnetate scan—*it is diagnostic* (Due to high mitochondrial content).
- FNAC.

  Adenolymphoma does not turn into malignancy.



Fig. 4.26: Warthin's tumour. It is seen in parotid gland usually in superficial lobe, in lower pole.

Treatment

Superficial parotidectomy.

MUCOEPIDERMOID TUMOUR

- It is the commonest malignant salivary gland tumour (in major salivary glands).
- It is slowly progressive, often attains a large size and spreads to neck lymph nodes.
- It contains malignant epidermoid and mucus secreting cells.

Types

- Low grade—*mucus cells* mainly.
- High grade—*epidermoid cells* mainly.

Facial nerve involvement is late in mucoepidermoid carcinoma of parotid.



Fig. 4.27: Mucoepidermoid tumour.

Clinical Features

- Swelling in the salivary (parotid or submandibular) region, slowly increasing in size, eventually attaining a large size, which is hard, nodular, often with involvement of skin and lymph nodes.

ADENOID CYSTIC CARCINOMA
(10% of salivary tumours)

- It is common in submandibular and minor salivary glands.
- It consists of myoepithelial cells and duct epithelial cells with cribriform or lace like appearance.
- It involves facial nerve very early, spreads through the perineural sheath and infiltrates into the perineural tissues over a long distance, more proximally.
- It also invades periosteum and bone medulla early and spreads extensively.
- Prognosis is poor.
- Radical parotidectomy and radical radiotherapy is the treatment of choice.

Anything the mind of man can conceive and believe, it can achieve.

ACINIC CELL TUMOUR

- It is a rare, slow growing tumour that occurs almost always in parotid and is composed of cells alike serous acini. It is more common in women. It occurs in adult and elderly.
- It can involve facial nerve or neck lymph nodes.
- Clinically it is of variable consistency with soft and cystic areas.
- It is low grade malignant tumour.

SUBMANDIBULAR SALIVARY GLAND TUMOURS

Benign tumours: They are commonly pleomorphic adenomas, are smooth, firm or hard, bidigitally palpable, without involving adjacent muscles or hypoglossal nerve or mandible bone.



Fig. 4.28: Submandibular salivary gland tumour which is malignant. Patient underwent wide excision.

- Diagnosis is by FNAC, Orthopantomogram (OPG) and CT scan.
- Excision of both superficial and deep lobes of the gland is done.

***Malignant tumours of submandibular salivary gland*:**

- They are hard, nodular, often get fixed to skin, muscles, hypoglossal nerve and mandible.
- Diagnosis is by FNAC of primary tumour and of lymph nodes when involved, CT scan and OPG.

Treatment: Wide excision, with removal of adjacent muscle, soft tissues and mandible. If lymph nodes are involved, block dissection of neck (Classical neck dissection) is done.

GENERAL FEATURES OF MALIGNANT SALIVARY TUMOURS

1. Fixation
2. Resorption of adjacent bone
3. Pain and anaesthesia in the skin and mucosa
4. Muscle paralysis
5. Skin involvement and nodularity
6. Involvement of jaw and masticatory muscle
7. Nerve involvement (facial nerve in parotid or hypoglossal nerve in submandibular salivary gland)
8. Blood spread when occurs, commonly to lungs
9. Mandibular branch of 5th cranial nerve may be involved when tumour tracks along the auriculotemporal nerve to the base of the skull causing severe pain in the distribution area.

MANAGEMENT OF MALIGNANT SALIVARY TUMOURS

TNM Staging of Malignant Salivary Tumours

T—Tumour

Tx —Tumour cannot be assessed.
T0 —No evidence of primary tumour.
T1 —Tumour < 2cm without extraparenchymal spread.
T2 —Tumour 2-4 cm.
T3 —Tumour 4-6 cm.
—or with extraparenchymal spread.
—but no facial nerve spread.
T4 —Tumour > 6 cm.
—or spread to facial nerve, skin, mandible, ear canal —T_{4a}.
—or spread to base of skull, pterygoid plates, encased external carotid artery – T_{4b}.

N—Lymph node

Nx —Nodes not assessed.
N0 —Regional nodes not involved.
N1 —Single ipsilateral node < 3 cm.
N2a —Single ipsilateral node 3-6 cm.
N2b —Multiple ipsilateral nodes < 6 cm.
N2c —Bilateral or contralateral nodes < 6 cm.
N3 —Single node spread > 6 cm.

M—Metastases

M0 —No blood spread.
M1 —Blood spread present.



Fig. 4.29: Submandibular salivary gland tumour in old female.

Specific Investigations

1. FNAC.
2. CT scan to see the deep lobe of the parotid: the involvement of bone, extension into the base of the skull; relation of tumour to internal carotid artery, styloid process.
3. OPG.
4. Blood grouping and cross matching; required amount of blood is kept ready.
5. FNAC of lymph node.
6. MRI shows better soft tissue definition than CT scan. *Sialogram is not useful in assessment of tumour.*





Figs 4.30A and B: CT scan pictures of salivary tumours.

Treatment

In parotid:

- ***Surgery***
  - *Radical parotidectomy* is done which includes removal of both lobes of parotid, soft tissues, part of the mandible with facial nerve.
  - Facial nerve is reconstructed using greater auricular nerve, or sural nerve.
  - Often lateral tarsorrhaphy or temporal sling reconstruction is done.

Complications of surgery:
1. Haemorrhage
2. Infection, flap necrosis
3. Fistula
4. Frey's syndrome
5. Facial nerve palsy
6. Facial numbness
7. Numbness in ear lobule due to injury to great auricular nerve
8. Sialocele

- ***Postoperative radiotherapy*** is quiet useful to reduce the chances of relapse. Usually, external radiotherapy is given. It is given in all carcinomas, but more useful in adenoid cystic and squamous cell carcinomas.
- ***Chemotherpy*** is also given. Drugs given here depends on tumour type. Intra-arterial chemotherapy is beneficial.
- ***Preoperative radiotherapy*** is given in large tumours to reduce the size and make it better operable, i.e. to down stage the disease.

It's your imagination that can take you anywhere.

- ***If lymph nodes are involved***, which is confirmed by FNAC, radical neck dissection is done. It is also done in N0 with high-grade tumour or T3/T4 tumours.

In submandibular salivary gland:
Wide excision is done, with removal of mandible, and soft tissues around. If lymph nodes are involved, then block dissection of the neck is done.

Indications for radiotherapy in malignant salivary gland tumours:

1. All adenoid cystic and adenocarcinomas
2. T3 and T4 tumours
3. Recurrent tumours
4. Poorly differentiated tumours – high grade
5. Tumours with lymph node involvement
6. As preoperative radiotherapy
7. Recurrent benign pleomorphic adenomas
8. Spillage during surgery in case of pleomorphic adenomas
9. Residual tumours, refractory tumour or nerve involvement
10. When clearance margin is inadequate

Note: Radiotherapy is delayed for 6 weeks after surgery if nerve grafting is done.

Problems with radiotherapy–

- Xerostomia
- Trismus due to fibrosis of masseter, pterygoids and temporomandibular joint
- Otitis media
- Localised hair loss
- Osteoradionecrosis – is rare now

MINOR SALIVARY GLAND TUMOURS

- It is 10% of salivary tumours.
- It is common in
  — *palate* (40%).
  — *lip.*
  — *cheek.*
  — *sublingual glands***.**
- *Palate* is the commonest site.
- 10% are benign—*commonly pleomorphic adenomas***.**
- 90% are malignant—*commonly adenoid cystic carcinomas.*
- They present as swelling with ulcer over the summit.
- If it is malignant, then extension into the palate, maxilla, pterygoids can occur often with involvement of the lymph node.



Fig. 4.31: Minor salivary gland tumour in the palate. Palate is the common site of minor salivary gland tumour.

Differential Diagnosis

Squamous cell carcinoma of oral cavity.

Investigations

1. Incision biopsy.
2. CT Scan.
3. X-ray maxilla.
4. FNAC of lymph node.

Treatment

- Wide excision often with palatal excision or maxillectomy is done - for malignancy.
- Reconstruction by dental plates, skin grafting, or flaps are done.
- Lymph node block dissection of the neck is done if involved.
- Excision with primary closure is done for benign tumours.

Points to be remembered

- Salivary gland tumours are usually benign in an adult.
- It is rare in children but when it occurs, it is commonly malignant.
- Clinical and FNAC are diagnostic methods.
- *Open biopsy is contraindicated***.**
- *Sialogram is not useful in salivary tumours.*
- CT scan or MRI are often needed.
- Nerve should be preserved in benign lesions.
- Nerve can be sacrificed to achieve clearance in malignancies.

PAROTID LYMPHOMA

- Parotid lymphoma can occur from the lymph nodes in the gland or from parotid parenchyma.
- It can occur in HIV patients; lymphoepithelial diseases and in Sjogren's syndrome.
- Common in elderly.
- Disease may be confined to parotid gland or may involve other nodes in neck, mediastinum.
- When it is confined to parotid total parotidectomy with radiotherapy and later chemotherapy is the treatment.
- When many other nodes are involved chemotherapy is the choice therapy.

Note: Lymphoma occasionally can occur in other salivary glands also (10% of all salivary lymphomas).

FREY'S SYNDROME (Auriculo-temporal syndrome) (Gustatory sweating)

- Occurs in 10% of cases.
- It is due to injury to the auriculo temporal nerve, wherein post-ganglionic parasympathetic fibres from the otic ganglion become united to sympathetic nerves from the superior cervical ganglion (*Pseudosynapsis*). Auriculotemporal nerve has got two branches. Auricular branch supplies external acoustic meatus, surface of tympanic membrane, skin of auricle above external acoustic meatus. Temporal branch supplies hairy skin of the temple. Sweating and hyperaesthesia occurs in this area of skin.

Causes

1. Surgeries or accidental injuries to the parotid.
2. Surgeries or accidental injuries to temporomandibular joint.

Clinical Features

- Flushing, sweating, pain and hyperaesthesia in the skin over the face innervated by the auriculotemporal nerve, whenever salivation is stimulated (i.e. during mastication).
- Condition causes real inconvenience to the patient.
- Involved skin is painted with iodine and dried. Dry starch applied over this area will become blue due to more sweat in the area in Frey's syndrome—***Starch iodine test.***

Treatment

- Initially conservative and reassurance. Most often they recover without any active treatment in 6 months.
- Occasionally (10%) they require surgical division of the tympanic branch of the glossopharyngeal nerve below the round window of middle ear, (i.e. intratympanic parasympathetic (Jacobsen nerve) neurectomy).

Treatment of Frey's syndrome

- Reassurance
- Jacobsen neurectomy (tympanic)
- Injection of botulinum toxin to the affected skin
- Antiperspirants like aluminium chloride
- Syndrome can be prevented on table by placing muscle (sternomastoid) or fascial(temporalis) flaps or artificial membranes over parotid bed



Fig. 4.32: Parasympathetic and sympathetic supply of the parotid gland. Otic ganglion located just below the foramen ovale close to mandibular nerve relays the parasympathetic supply from glossopharyngeal nerve through tympanic branch, tympanic plexus in middle ear and then lesser superficial petrosal nerve. Post-ganglionic fibres run in auriculotemporal nerve along with unrelayed sympathetic fibres from middle meningeal plexus.

PAROTIDECTOMY

Types

1. *Superficial parotidectomy*: It is the removal of superficial lobe of the parotid (superficial to facial nerve). Done in case of benign diseases of superficial lobe of the parotid.

In time of test, family is best.



Fig. 4.33: Incision for parotidectomy. Typical lazy 'S'.



Fig. 4.34: 'S' shaped incision for parotidectomy



Fig. 4.35: On table exposure of facial nerve branches after superficial parotidectomy for a benign tumour.

Steps in parotidectomy

- Lazy 'S' incision and raising the skin flaps
- Mobilisation of the gland
- Identification of facial nerve trunk
- Dissection of the gland off the facial nerve using bipolar cautery
- Removal of parotid – superficial / both
- Distilled water (hypertonic) irrigation to kill spilled tumour cells
- Haemostasis and closure with a suction drain

2. *Total conservative parotidectomy***:** It is done in benign diseases of parotid involving either only deep lobe or both superficial and deep lobes. Here both lobes are removed with preservation of facial nerve. Here initially superficial parotidectomy is done and facial nerve and its branches are retracted gently and deep lobe is removed.
3. *Radical parotidectomy***:** Both lobes of parotid are removed along with facial nerve, fat, fascia, muscles, (masseter, pterygoids and buccinator) lymph nodes. It is done in case of carcinoma parotid. Later facial nerve reconstruction is done using great auricular nerve graft.

   Conservative surgeries are becoming popular for malignancy but they are not universally accepted.
4. *Suprafacial parotidectomy* is done in lower pole parotid tumours wherein all branches of the facial nerve need not be dissected.

Identification of facial nerve

- Facial nerve is 1 cm deep and below the tip of the inferior portion of the cartilaginous canal – *Conley's point*
- By nerve stimulator
- It is inferomedial to tragal point
- Deep to digastric muscle and tympanic plate
- Nerve is just lateral to the styloid process
- Tracing branch from distal to proximal (Hamilton-Bailey technique)

Complications of parotidectomy

1. Facial nerve injury
2. Haemorrhage
3. Salivary fistulas
4. Infection—Flap necrosis is common
5. Frey's syndrome
6. Sialocele
7. Numbness over the face and ear - due to injury to great auricular nerve. Female patients find difficult to wear ear rings. Spontaneous recovery may occur in 1½ to 2 years.







Figs 4.36A to D: Steps in parotidectomy and demonstration of facial nerve. Note the placement of drain after surgery. (*Courtesy by Professor Kishore Chandra Prasad, ENT surgeon and HOD KMC Mangalore; Dr Sampath MS ENT KMC Mangalore*).

FACIAL NERVE INJURY (Lower motor nerve lesion, surgically related)

Causes

- Trauma
- Surgery—parotidectomy, drainage of parotid abscess
- Compression of facial nerve—Bell's palsy.
- Incidence of temporary/transient facial nerve palsy after parotidectomy is 30%. Recovery occurs usually in 12 weeks.

Clinical Features

- Inability to close the eye-lid.
- Difficulty in blowing and clenching.
- Drooping of the angle of the mouth.
- Obliteration of naso-labial fold.
- Loss of forehead wrinkles.
- Wide palpebral fissure.
- Epiphora.

Treatment

- Nerve grafting using greater auricular nerve, sural nerve, lateral cutaneous nerve of thigh or hypoglossal nerve.
- Suspension of angle of mouth to zygomatic bone using temporal fascia sling.
- Lateral tarsorrhaphy—to prevent corneal ulceration.

You will soon break the bow if you keep it always stretched.

- Medial canthus reconstruction—to reduce epiphora.
- Cross facial nerve transplantation from opposite side using its insignificant branches.
- Dynamic neuro-vascular muscle graft.
- Upper lid gold weights to protect cornea.

Surgeries for facial nerve palsy

- *Static*
  - — Suspension surgeries using temporal fascia
  - — Correction of medial canthus
  - — Lateral tarsorrhaphy – to prevent exposure keratitis due to widened palpebral fissure.
  - — Upper lid weights
- *Dynamic*
  - — Muscle transfer-temporal to masseter
  - — Free muscle graft. Gracilis muscle neuro-vascular transfer
  - — Cross facial nerve transplant from opposite facial nerve to injured facial nerve using sural nerve.
  - — Nerve grafts.

Heerfordt's syndrome is sarcoidosis of parotid swelling; anterior uveitis; facial palsy and fever.

Self-assessment Questions

- Mixed parotid tumour.
- Pleomorphic adenoma.
- Classification of salivary tumours.
- Warthin's tumour.
- Adenolymphoma.
- Malignant parotid tumour.
- Malignant salivary tumours.
- Parotid fistula.
- Salivary calculus.
- Sialadenitis.
- Parotid abscess.
- Minor salivary gland tumours.
- Sialolithiasis.
- Frey's syndrome.
- Parotidectomy.
- Complications of parotidectomy.
- Mucoepidermoid carcinoma.
- Sialectasis.
- Sialography.



Fig. 4.37: Features of post parotidectomy facial nerve palsy.

5

Neck

Anatomy of lymphatics of head and neck
Cervical rib
Branchial cyst
Branchial fistula
Pharyngeal pouch
Laryngocele
Cystic hygroma
Ludwig's angina
Parapharyngeal abscess
Retropharyngeal abscess
Subhyoid bursitis
Carotid body tumour
Torticollis
Sternomastoid tumour
Tuberculous lymphadenitis
Secondaries in neck lymph node
Chemotherapy for head and neck cancers

ANATOMY OF LYMPHATICS OF HEAD AND NECK

Waldeyer's Lymphatic Ring (Inner)

It consists of adenoids above, lingual tonsils below and two palatine tonsils laterally one on each side.



Fig. 5.1: Inner and outer Waldeyer's ring anatomy.

Outer Circular Chain of Nodes (Outer Waldeyer's Ring)

Occipital, post-auricular, pre-auricular, parotid, facial, submandibular, submental, superficial cervical and anterior cervical.

Facial nodes are:

a. Superficial
   - Upper–infra-orbital.
   - Middle–buccinator.
   - Lower–supramandibular.

b. Deep groups–in relation to pterygoids.

Submandibular lymph nodes drain

- The side of the nose.
- The cheek.
- Angle of the mouth.
- Entire upper lip.
- Outer part of the lower lip.
- The gums.
- Side of the tongue.

Submental lymph nodes. Drain from the central part of the lower lip, floor of the mouth and apex of the tongue.

Superficial cervical nodes. They lie on outer surface of the sternomastoid around the external jugular vein. They drain the parotid region and lower part of the ear.

Deep Cervical Lymph Nodes

Upper deep cervical lymph nodes—jugulo-digastric nodes—Below the digastric and in front of IJV.
Lower deep cervical lymph nodes—jugulo-omohyoid nodes—Above the omohyoid and behind the IJV.

They drain the ipsilateral half of head and neck, finally form a jugular lymph trunk from lower deep cervical nodes to join thoracic duct on the left side, and the junction of right subclavian and right jugular vein on right side.

Do not worry and hurry so much rather walk this earth lightly and leave your mark.—Dr Saroj Kanna

Rule of 7 in the neck

- 7 days—inflammation
- 7 months—neoplasm
- 7 years—congenital defect

Note: The Rule of 7 provides a probable diagnosis of the neck mass based on the average duration of the patient's symptoms


Submandibular
Submental
Carotid
Omohyoid
Trapezius
Muscular
Suboccipital
Supraclavicular

Fig. 5.2: Triangles of the neck.


Preauricular
Submental
Submandibular
Mid deep cervical
Sternomastoid
Lower deep cervical
Supraclavicular

Fig. 5.3: Lymphatic drainage of the neck.

THORACIC OUTLET SYNDROME (TOS)

It is syndrome complex due to neurovascular bundle compression in the thoracic outlet.

Thoracic outlet has got two main spaces:

- Scalene triangle is bound by scalenus anterior, scalenus medius and first rib. It contains subclavian artery and brachial plexus.
- Costoclavicular space is bound by clavicle, first rib, costoclavicular ligament and scalenus medius. It contains subclavian artery and vein and brachial plexus.

Causes

- Cervical rib.
- Long C7 transverse process.
- Anomalous insertion of scalene muscles.
- Scalene muscle hypertrophy.
- Scalene minimus.
- Abnormal bands and ligaments.
- Fracture clavicle or first rib.
- Exostosis.
- Tumours in the region.
- Brachial plexus trauma and diseases.

Differential Diagnosis of TOS

- Carpal tunnel syndrome.
- Cervical spondylosis.
- Spinal canal tumours.
- Shoulder myositis.
- Angina.
- Raynaud's disease.
- Spinal stenosis.
- Ulnar nerve compression, epicondylitis.

Clinical Features

Neurological

- Paraesthesia.
- Pain in shoulder, arm, forearm and fingers.
- Occipital headache as referred pain from tight scalene muscles.
- Weakness in forearm, hand.

Vascular

- Claudication, ischaemic ulcers, gangrene.

Signs

- Scalene muscle tenderness.
- Pulsatile swelling in supraclavicular region with thrill and bruit (25%).
- Bony mass above clavicle.
- Adson's test.
- Roos test.
- Elevated arm stress test.

- Costoclavicular compression maneuver.
- Hyperabduction maneuver.
- Poor capillary refilling.
- Absence or feeble pulse.

(Please refer Chapter on Arterial Diseases for details of tests).

Investigations

- X-ray neck and cervical spine.
- Doppler.
- Subclavian angiogram, CT angiogram, CT neck.
- Nerve conduction studies, electromyography.

Treatment

- *Conservative.*
- *Surgical.*

Conservative treatment for TOS

- Exercises—neck stretching, postural and breathing exercises
- Drugs—analgesics, muscle relaxants, antidepressants
- Avoid weight lifting
- Physiotherapy

Surgical treatment of TOS

- Transaxillary *(ROOS)*—mainly for first rib excision and also cervical rib
- Supraclavicular approach for cervical rib and soft tissue excision, scalenotomy, neurolysis, arterial reconstruction
- Cervical sympathectomy may be needed

CERVICAL RIB

Definition

- It is an extension of costal element (anterior part) of transverse process of C_7 vertebra more than 2.5 cm (normal).
- Syndrome caused by it is called as *cervical rib syndrome, thoracic-inlet syndrome, thoracic-outlet syndrome, scalene syndrome.*
- It is 0.46% common; common in females; more frequent on right side.
- It can be *unilateral* or *bilateral (50%)* can be *asymptomatic* or *symptomatic*.



Fig. 5.4: Cervical rib types.

Types (Refer Fig. 5.4)

1. *Complete bony*: Cervical rib is radio-opaque, anteriorly ends over the first rib or manubrium.
2. *Complete fibrous*: Cannot be demonstrated radiologically.
3. *Combined*: Partly bony partly fibrous.
4. *Partial bony*: With free end expanding as *bony mass, which is felt in the neck.*

Pathology

- Cervical rib narrows the scalene triangle (bounded by scalenus anterior, scalenus medius and first thoracic rib below).

Compression of subclavian artery; C_8 and T_1 nerve roots due to cervical rib.
↓
Angulation of subclavian artery occurs.
↓
Causes constriction of artery at the site where artery crosses the cervical rib.
↓
'Eddie's current' created in the blood flow causes sudden release of pressure distal to the narrowing.
↓
Poststenotic dilatation → *Venturi phenomenon.*
(due to vessel wall ischaemia)↓
Stasis of blood occur.
↓
Thrombosis → *Embolus.*
↓ ↓
Features of ischaemia in the hand and forearm. Later digital gangrene occurs.

Nothing dies quicker than a new idea in a closed mind.

- Rarely thrombus may extend proximally into the subclavian artery causing vertebrobasilar insufficiency.
- Compression of C_8 and T_1 causes tingling and numbness along its distribution, i.e. in the little finger, medial side of hand and forearm.
- ***Paget-Schrotter syndrome*** is subclavian vein compression by cervical rib. It is rare.

Clinical Features

Majority of patients are asymptomatic—(80%).

1. ***Vascular manifestations***:
   - ***Pain*** is due to ischaemia in the muscle. It is more during work, exercise and is relieved by rest.



Figs 5.5A to C: Anatomy of cervical rib and its relation to subclavian artery and vein and brachial plexus. Note the Eddie's current, post-stenotic dilatation due to arterial compression by cervical rib. X-ray picture shows left sided complete cervical rib.

   - *Roos test* is raising the arm above the shoulder. The side where cervical rib is present, patient cannot continue and so drops the hand down.
   - *EAST—Elevated Arm Stress Test* (*Modified Roos test*): Arm is elevated above the shoulder, with elbow stretched fully. Rapid movements of fingers will cause fatigue on the side where cervical rib is present.
   - *Adson's test*: The hand is raised above after feeling the radial pulse. The patient is asked to take a deep breath and turn the head to the same side. Any change in pulse, i.e. either becoming feeble or absent is noted.
   - *Modified Adson's test* is same as Adson's, but neck is turned towards the opposite side.
   - ***Wasting*** of thenar, hypothenar and forearm muscles.
   - Often ***digital gangrene.***
   - Limb is ***colder*** and ***paler*** than the opposite side.
2. ***Neurological features*** is due to compression of T_1 and C_8 causing tingling and numbness in the little finger, medial side of hand and forearm.
3. ***Features in the neck***:
   a. Hard, fixed, bony mass in the supraclavicular region.
   b. *Palpable thrill* above the clavicle in the subclavian artery.
   c. *Bruit* on auscultation.

Note:

- Most common presentation is neurological.
- Most problematic presentation is vascular which requires surgery.

Differential Diagnosis

1. Cervical spondylosis—to differentiate, X-ray neck-lateral view should be taken.
2. Carpal tunnel syndrome.
3. Tumours or swellings compressing over the vessel or nerves in the neck.
4. Other causes of digital gangrene like atherosclerosis, Raynaud's syndrome, collagen diseases, diabetes mellitus, and embolism.
5. Syringomyelia, motor neuron disease.
6. Pancoast tumour.

Investigations

- Chest X-ray PA view and lateral view including neck—only (radiopaque) bony rib can be identified.

- Nerve conduction studies to confirm neurological compression and also to rule out carpal tunnel syndrome or cervical spondylosis.
- Arterial Doppler of subclavian artery and of the upper limb.
- Subclavian angiogram.
- Other relevant investigations like blood sugar, lipid profile, cardiac assessment.

Treatment

Note: For ***conservative treatment*** refer TOS above.

Surgical

1. In symptomatic cervical rib without arterial compression (subclavian artery), along with scalenotomy (cutting scalenus anterior muscle), extraperiosteal resection of cervical rib and often resection of first rib is done to increase the thoracoaxillary channel and so as to reduce arterial compression.
2. In symptomatic cervical rib with significant subclavian artery compression along with scalenotomy, extraperiosteal resection of cervical rib, resection of first rib, subclavian artery reconstruction with or without a graft is done.
3. Along with scalenotomy, extraperiosteal resection of cervical rib, resection of first rib, reconstruction of subclavian artery, cervical sympathectomy is also done to improve the circulation to the ischaemic upper limb.
4. Amputation of the gangrenous toe.

Approaches

1. Supraclavicular approach—mainly when there is need for vascular reconstruction
2. Transaxillary approach—through axillary crease, rib is approached and removed
3. Thoracotomy approach

BRANCHIAL CYST

It arises from the remnants of second branchial cleft. Normally 2nd, 3rd, 4th clefts disappear to form a smooth neck. Persistent 2nd cleft is called as *cervical sinus* which eventually gets sequestered to form *branchial cyst*.

Features

- Swelling in the neck beneath the anterior border of upper third of the sternomastoid muscle. It is smooth, soft, fluctuant, often transilluminant with a sensation of 'Half-filled double hot water bottle'.
- It contains *cholesterol crystals* which is from the lining of mucous membrane which contains sebaceous gland.
- Histologically, it is lined by *squamous epithelium*.
- It may get infected to form an abscess.
- FNAC shows *cholesterol crystals.*

Differential Diagnosis

1. Cold abscess.
2. Lymph cyst.

Treatment: *Excision* under G/A.

Cyst is in relation to carotids, hypoglossal nerve, glossopharyngeal nerve, spinal accessory nerve, posterior belly of digastric and pharyngeal wall. Medially it is close to the posterior pillar of tonsils. During dissection, all these structures should be taken care of.

Complications of Surgery

- Injury to major structures.
- Infection.
- Recurrence/fistula formation due to incomplete removal of the track.



Fig. 5.6: Branchial cyst.



Fig. 5.7: Positions of branchial cyst and fistula.

Everything big starts with something little.

BRANCHIAL FISTULA



Figs 5.8A and B: Branchial fistula in two different patients. Note the location and discharge. (*Courtesy by Professor Kishore Chandra Prasad ENT surgeon and Head of the department and Dr Sampath ENT surgeon KMC Mangalore*)

- It is a persistent second branchial cleft with a communication outside to the exterior. It is commonly a congenital fistula. Occasionally, the condition is secondary to incised, infected branchial cyst.
- Often it is bilateral.
- *External orifice* of the fistula is situated in *the lower third of the neck* near the anterior border of the sternomastoid muscle.
- *Internal orifice* is located on the anterior aspect of the posterior pillar of the fauces, just behind the tonsils.
- Sometimes fistula ends internally as blind end.
- Track is lined by *ciliated columnar epithelium* with patches of lymphoid tissues beneath it, causing recurrent inflammation.
- *Discharge* is mucoid or mucopurulent.
- *Investigations:* Discharge study, fistulogram.
- *Treatment: Always surgery*.

Under general anaesthesia, methylene blue is injected into the track. Probe is passed into the fistulous track. Through circumferential/elliptical incision around the fistula opening, entire length of the track is dissected until the internal orifice. Care should be taken to safeguard carotids, jugular vein, hypoglossal nerve, glosso-pharyngeal nerve and spinal accessory nerve. *Entire track should be excised.*

PHARYNGEAL POUCH

- It is a protrusion of mucosa through *Killian's dehiscence*, a weak area of the posterior pharyngeal wall between *thyropharyngeus (oblique fibres*) and *cricopharyngeus (transverse fibres*) of the *inferior constrictor muscle* of the pharynx.
- Thyropharyngeus is supplied by pharyngeal plexus from cranial accessory nerve. Cricopharyngeus is supplied by external laryngeal nerve.
- Pharyngeal pouch is a pulsion diverticulum. It starts in the midline of posterior pharyngeal wall. Once it expands and reaches the vertebra, it deviates towards left side of the neck because of resistance of vertebra.



Fig. 5.9: Pharyngeal pouch (Zenker's diverticulum).

- Imperfect relaxation of the cricopharyngeus increases the pressure in the pharynx, mainly during swallowing which leads to protrusion of mucosa through the Killian's dehiscence causing pharyngeal pouch.
- *The potrusion is usually towards left*.

Stages

1. Small diverticulum pointing towards vertebra. It is asymptomatic and incidentally diagnosed by barium

meal X-ray. Foreign body sensation in pharynx may be present.

2. Large, globular diverticulum with vertical mouth / opening causing regurgitation, violent cough, dysphagia, respiratory infection. Regurgitation is more after meals and while turning the neck.

- Large pouch which is visible in the neck as a globular swelling often tender, smooth and soft. Swelling is below the level of the thyroid cartilage and behind sternocleidomastoid muscle and can be emptied on pressure. Opening of the pouch is not vertical but horizontal. They present with dysphagia, features of respiratory infection like pneumonia and lung abscess, weight loss and cachexia. Pouch may itself get infected and may form an abscess. Often the pouch may descend downward and enter the superior mediastinum. Gurgling sound in the neck is observed.

Differential Diagnosis

- Branchial cyst.
- Cold abscess in the neck.
- Lymph cyst.
- Haemangioma neck.

Clinical Features

Pain, dysphagia, recurrent respiratory infection, swelling in the neck on the left side which is smooth, soft and tender.

Investigations

- *Barium swallow* - lateral view shows pharyngeal pouch.
- Chest X-ray shows pneumonia.
- CT neck is very useful.

Note: Oesophagoscopy should be gentle or avoided as scope may enter the friable pharyngeal pouch and can cause perforation and life threatening mediastinitis.

Treatment

- Antibiotic is started to control infection.
- *Pharyngeal pouch is excised* by an oblique neck incision (approach from neck). As there is cricopharyngeal spasm, *cricopharyngeal myotomy* (i.e. cutting of cricopharyngeal circular muscle fibres without opening mucosa) is done to prevent the recurrence.

Technique

Under anaesthesia endoscope is passed to identify the opening of the pouch. It is packed with acriflavine soaked gauze for identification of the pouch. Under anaesthesia nasogastric tube is passed into the oesophagus under visualisation. Pouch is approached through neck incision for proper removal. Myotomy of cricopharyngeus and upper circular muscle of the oesophagus is done to relieve the spasm. Progressive symptoms, respiratory distress and dysphagia are definitive indications for surgery.

- *Dohlman's operation* is endoscopic excision of the pharyngeal pouch.

Complications of surgery

1. Infection, either *mediastinitis* or *lung infection* (Pneumonia or lung abscess)
2. Pharyngeal fistula
3. Abscess in the neck
4. Oesophageal stenosis and recurrence

LARYNGOCELE

- It is an unilateral narrow necked, air containing diverticulum resulting from herniation of laryngeal mucosa.
- It occurs in professional *trumpet players, glass blowers and in people with chronic cough*.

Types

a. **External:** It is situated in the anterior third of the laryngeal ventricle, between the false cords and thyroid cartilage, herniates through the *thyrohyoid membrane* where it is pierced by superior laryngeal nerve.

b. **Internal:** Confined within the larynx, presents as a distention of false cords.

c. **Combined.**



Fig. 5.10: Laryngocele.

There is only one degree difference between hotwater and steam.



Figs 5.11A to C: Typical laryngocele in the neck which becomes prominent after blowing. X-ray (AP and lateral) shows radiolucent air in the neck.

Clinical Features

- Swelling in the neck in relation to larynx, adjacent to thyrohyoid membrane which is smooth, soft, resonant and is more prominent while blowing, coughing and Valsalva manoeuvre.
- Infection is quite common in the sac of laryngocele, leading to the blockade of opening of the sac causing an abscess.
- Pus often may be discharged into the pharynx repeatedly.
- Hoarseness and cough.
- If large, causes obstruction to larynx.

Diagnosis

Clinical features, X-ray neck, laryngoscopy, CT scan.

Treatment

External laryngocele—Excision through neck incision. Neck of the sac should be ligated.

Internal laryngocele—Marsupialisation, with the help of laryngoscope.

CYSTIC HYGROMA (Cavernous lymphangioma)

- It is a cystic swelling due to sequestration of a portion of jugular lymph sac from the lymphatic system, during the developmental period *in utero.*
- Present at birth and so may cause obstructed labour. Occasionally present in early infancy.
- It is also called as ***hydrocele of the neck.***

Sites

1. *Posterior triangle of the neck* – commonest site Eventually may extend upwards in the neck
2. Cheek
3. Axilla
4. Tongue—lymphangiogenetic macroglossia
5. Groin
6. Mediastinum
7. Often multiple sites

Pathology

- It contains aggregation of cysts looking like *soap bubbles*. Cysts have *mosaic appearance* with larger cysts near the surface and smaller cysts in the deeper planes. Each cyst contains clear lymph with endothelial lining.

Clinical Features

1. Swelling is *present at birth* in the *posterior triangle of neck* causing obstructed labour.
2. Swelling is smooth, soft, fluctuant (cystic)**,** *compressible, brilliantly transilluminant*.

3. Swelling may rapidly increase in size causing *respiratory obstruction*—dangerous sign.
4. It may get infected forming an *abscess* which is a tender, warm, soft swelling. It may cause septicaemia which may be life threatening.



Fig. 5.12: Cystic hygroma.

Treatment

1. Aspiration of the contents. Later once the sac or capsule gets thickened by fibrous tissue, it is excised.
2. When it causes respiratory obstruction, *aspiration* and *tracheostomy* is done.
3. Under proper antibiotics coverage, drainage of abscess is done. Later sac is excised.
4. Preoperative injection of sclerosants (OK 432, PICIBANIL recently used) and later once fibrosis develops excision of entire aggregation of cysts.

Complications

1. Respiratory distress
2. Infection → Abscess → Septicaemia
3. Surgery itself may cause torrential haemorrhage

LUDWIG'S ANGINA

- It is an inflammatory oedema of submandibular region and floor of the mouth, commonly due to streptococcal infection.
- It causes diffuse swelling and brawny oedema of the submandibular region. It is common in severely ill and in advanced malignancy, causing *trismus, laryngeal oedema*. Extension of infection into *para-pharyngeal space* may lead to dreaded *internal jugular vein thrombosis.*
- As the infection is deep to the deep fascia in a closed fascial plane, it spreads very fast causing dangerous complications.

Precipitating factors

- Caries teeth
- Oral or other malignancy
- Submandibular salivary infection/calculi
- Chemotherapy
- Chronic diseases like diabetes mellitus
- Cachexia of any cause

Special features

- Brawny oedema/diffuse swelling of submandibular and submental region
- Intraoral oedema in floor of the mouth
- Putrid halitosis
- Severe toxicity
- Dyspnoea, dysphagia
- May cause laryngeal oedema, septicaemia, extension of sepsis into other spaces in the neck

Clinical Features

- Fever, toxicity, diffuse swelling, dysphagia, dyspnoea, trismus.
- Intraoral oedema is common.
- Brawny swelling in submandibular region.
- Putrid halitosis.

Treatment

- Antibiotics.
- IV fluids.



Fig. 5.13: Incision for draining Ludwig's angina.

> *One-third of congenital torticollis is due to sternomastoid tumour and two-third due to abnormal position in utero which recovers spontaneously in a few weeks.* — Kenneth F Hulbert

- *Decompression of the submandibular region is done*, by making a deep incision extending into the deep fascia and also *cutting both the mylohyoid muscles***.** Either it is left open and *delayed suturing is done* (better option) or it is loosely sutured.

Complications

1. Laryngeal oedema and respiratory distress, may require tracheostomy
2. Septicaemia
3. Extension of infection into parapharyngeal space



Fig. 5.14: Abscess in submandibular region. Note the redness and swelling. It needs incision and drainage under general anaesthesia.

PARAPHARYNGEAL ABSCESS

- It is *infection of pharyngo-maxillary space*.
- This is a cone-shaped space; base is formed by the base of skull; apex is formed by the greater cornu of hyoid bone; medial wall by the superior constrictor; lateral wall is formed by the internal pterygoid, angle of mandible and submandibular salivary gland.
- Usually, infection arises from the tonsils, after tonsillectomy and from the submandibular space.

Clinical Features

- It causes diffuse swelling in the upper neck, trismus, fever, toxicity.
- Swelling lies behind the posterior pillar with oedema of soft palate.

Complications

1. Thrombosis of internal jugular vein.
2. Erosion into the internal carotid artery causing torrential bleeding.
3. Septicaemia.

Treatment

- Under G/A, drainage is done by making incision (deep incision) between angle of the mandible and hyoid bone. Early drainage is needed.
- Antibiotics are given.

RETROPHARYNGEAL ABSCESS

Surgical Anatomy

The wall of the pharynx has got 5 layers. Mucosa, submucosa, pharyngobasilar fascia, muscular layer (contains 3 constrictors and stylo, salpingo, palato-pharyngeus muscles) and buccopharyngeal fascia covers outer part of constrictors and extends over buccinator. Buccopharyngeal fascia is adherent to prevertebral fascia posteriorly in the midline. Retropharyngeal lymph nodes are located between buccopharyngeal fascia and prevertebral fascia in paramedian (eccentric) position. (not midline).

Types

- Acute.
- Chronic.


1
2
3
4
5
6
Normal anatomy
Acute abscess
1
2
3
4
5
6
Acute retropharyngeal abscess
Chronic abscess
1
2
3
4
5
6
Chronic retropharyngeal abscess
1. Pharyngeal wall 2. Buccopharyngeal fascia 3. RetophAryngeal LN 4. Prevertebral fascia 5. Median septum 6. Vertebra

Fig. 5.15: Note acute and chronic retropharyngeal abscess. Normal anatomy is also shown. Acute is eccentric and is due to suppuration of retropharyngeal lymph nodes. Chronic is central, midline and is due to tuberculosis of the cervical vertebra.

Acute Retropharyngeal Abscess

- It is infection and suppuration of retropharyngeal lymph nodes due to staphylococci or streptococci organisms.
- Commonly from tonsils or pharynx.
- Common in infants and children.

Clinical Features

- It presents as ***lateral (paramedian, eccentric) smooth, tender swelling*** in the pharynx with dysphagia, dyspnoea, cough, toxic features and neck rigidity.
- Diagnosis is obvious on proper clinical examination.

Treatment

- Antibiotics intravenously.
- Drainage is done usually *through per oral incision* under careful anaesthesia. Only occasionally drainage may be required through a neck incision. Pus should be sent for culture.

Chronic Retropharyngeal Abscess

- It is invariably due to tuberculosis of cervical spine.
- Abscess is in the ***midline behind the prevertebral fascia***.
- There is destruction of the body of the vertebra due to tuberculosis.



Fig. 5.16: X ray neck showing retropharyngeal abscess with tuberculosus lesion involving the C_2 cervical spine. (*Courtesy by Dr Navin Chandra Shetty MD Radiologist, Professor and Head, Department of radiodiagnosis KMC Mangalore*).

Clinical Features

- It is ***midline swelling in the posterior pharyngeal wall***, which is smooth and nontender.
- Features of tuberculosis of cervical spine will be observed.
- Often abscess may point in the neck in relation to sternomastoid.
- Neurological manifestations may occur in severe disease.

Investigations

X-ray spine, chest X-ray, ESR, MRI of cervical spine are essential investigations.

Treatment

- Antitubercular drugs.
- Drainage of the abscess should be done *through neck approach (never intraoral approach)*.
- Decompression of the vertebra and stabilisation is also often required.

SUBHYOID BURSITIS

- Subhyoid bursa is space between posterior surface of the body of hyoid bone and thyrohyoid membrane. It lessens friction between these two structures during swallowing.
- Due to constant friction inflammatory fluid collects in the bursa leading to bursitis, which presents like a ***horizontally placed*** midline swelling between lower part of the hyoid bone and thyrohyoid membrane.

Features

- Smooth, soft, cystic, fluctuant, non-transilluminating swelling which moves upwards with deglutition but ***not while protruding the tongue out***.
- It should be differentiated from thyroglossal cyst and pretracheal lymph nodes.
- It contains turbid fluid often may get infected to make the swelling tender or to form an abscess.



Fig. 5.17: Sagittal and front view showing location and relation of subhyoid bursa.

It is better to aim at good things and miss it , than to aim at a bad thing and hit it.

Treatment

- Excision under general anaesthesia.

CAROTID BODY TUMOUR (Potato tumour, Chemodectoma, Non-chromaffin para-ganglioma)

- It arises from the carotid body, which is located at the bifurcation of the common carotid artery.
- The tumour is situated in the adventitia of the artery.
- They are benign or locally malignant tumours, but in 20% cases spread can occur to the regional lymph nodes and lungs.
- Blood supply to the tumour is from *external carotid artery*. Tumour does not secrete epinephrine or any endocrine substances.
- They can be *familial.*
- Common in high altitude area, common in females.
- Pathologically, it is well-encapsulated, hard creamy yellowish tumour with dense fibrous tissue. Carotid body tumour cells are not hormonally active.

Carotid body–

- Normal carotid body is 3-5 mm sized flat brownish nodule in the adventitious of common carotid artery
- It consists of chief cells (contains catecholamine granules) and supportive cells
- It gets its nerve supply from glossopharyngeal nerve
- These chemoreceptors are sensitive to changes in pH and temperature in the body especially in hypoxia, help in autoregulation of respiration and circulation
- Carotid body hyperplasia can occur in people residing in high altitudes who are exposed to chronic hypoxia.
- Other chemoreceptors in the body are – aortic bodies in the arch of aorta; glomus jugular in the bulb of the internal jugular vein; glomus intravagale in relation to ganglion nodosum of the vagus nerve and others like pulmonary (near pulmonary artery) and myocardial (near coronary artery origin) receptors

Clinical Features (0.5%–Incidence)

1. Usually unilateral.
2. More common in middle age.
3. Swelling in the carotid region of the neck which is smooth, firm, pulsatile (transmitted pulsation—due to pulsatile carotid vessel overlying its surface) and moves only side to side but not in vertical direction.
4. Features of transient ischaemic attacks due to compression over the carotids, *"carotid body syncope."*
5. Thrill may be felt and bruit may be heard.
6. It is located at the level of hyoid bone deep to anterior edge of the sternomastoid muscle in anterior triangle, vertically placed, round, firm 'potato' like swelling.

Often tumour may extend into the cranial cavity along the internal carotid artery as *dumbbell tumour*.

Sites where dumb-bell tumours are seen:

- Parotid tumour
- Spinal cord tumour
- Carotid body tumour

Shamblin classification of carotid body tumor

- Type I– Localised, easily resectable (26%)
- Type II– Adherent, partially surrounding the carotids (46%)
- Type III– Adherent, encased carotids completely (27%)

Investigations

- Doppler.
- Angiogram to see the '*tumour blush*'—DSA. Widening/splaying of the carotid artery with tumour blush in an angiogram is called as **Lyre sign**.
- CT scan, MRI.

No FNAC: No partial excision.

Differential Diagnosis

- Carotid artery aneurysm.
- Soft tissue tumour (Sarcoma).
- Lymph node enlargement.
- Neurofibroma of the vagus nerve presents as swelling in the carotid triangle in the region of thyroid as vertically placed, oval, hard swelling. On palpation of the swelling, patient often develops bradycardia and dry cough. It does not move with deglutition and has only transverse mobility. As the tumour lies behind the carotid it can stretch the carotid in front causing transmitted pulsation.

Treatment

- If it is small, it can be excised easily as the tumour is situated in the adventitia.
- When it is large, as commonly observed, *complete excision has to be done followed by placing a vascular graft.*
- Carotid body tumour is not *radiosensitive* (controversial).



Fig. 5.18: Note the site and location of carotid body tumour. Splaying of the carotid is common.

Complications of the Surgery

- Bleeding.
- Blockage of common carotid artery, leading to contralateral side hemiplegia. This can be prevented by *stenting the common carotid artery* towards internal carotid artery and is done *during surgical excision* of the tumour.

Cystic swellings in the neck

- Cold abscess
- Cystic hygroma
- Branchial cyst
- Thyroglossal cyst
- Laryngocele
- Pharyngeal pouch
- Subhyoid bursa

TORTICOLLIS (Wry Neck)

It is turning of the neck to one side with chin pointing towards opposite side.

Causes

- Sternomastoid tumour.
- Trauma—spinal injury, disc prolapse, spondylosis.
- Inflammatory: Lymphadenitis either tuberculous or suppurative; tuberculosis of cervical spine.
- Spasmodic—due to spasm of sternomastoid muscle of same side or spasm of posterior cervical muscles of opposite side.
- Reflex.
- Rheumatic—after exposure to cold/draught.
- Burns—causing contracture.
- Ocular causes.
- Compensatory due to scoliosis.



Fig. 5.19: Boy having right-sided torticollis.

Clinical Features

- Restricted neck movements.
- Chin pointing towards opposite side.
- Squint.
- Features relevant of the causes.

Treatment

The cause is treated.



Fig. 5.20: Torticollis (right-sided) with chin towards opposite side.

Happiness is a direction not a destination.

STERNOMASTOID TUMOUR

It is due to birth injury to the sternomastoid muscle. It is a *misnomer.* It is not a tumour.



Fig. 5.21: Sternomastoid tumour – typical location.

Pathogenesis

- During child birth, injury to the sternomastoid muscle causes *haematoma* in the muscle which gets organised to form sternomastoid tumour.
- Common in breech delivery.

Clinical Features

- It is seen in infants of 3-4 weeks age.
- Swelling of about 2 cm size, in the sternomastoid muscle which is smooth, hard, nontender and adherent to the muscle – in the middle part.
- Chin pointing towards opposite side. Head towards same side (*Scoliosis capitis).*
- In later age groups it causes *hemifacial atrophy* due to less blood supply as a result of compression of the external carotid artery by sternomastoid tumour and due to kinking by position of neck. Distance between the outer canthus of eye to angle of mouth is reduced, with less arched eyebrow, flat or less filled cheek and flat nose compared to opposite side.
- Compensatory cervical scoliosis.
- Compensatory squint.

Differential Diagnosis

Other causes for torticollis.

Treatment

- Division of the lower end of the sternomastoid muscle or excision of the muscle.
- Exercise and active stimulation of muscles in early cases.

DIFFERENTIAL DIAGNOSIS FOR NECK LYMPH NODE ENLARGEMENT	
• Tuberculous lymphadenitis	• Secondaries in lymph nodes
• HIV infection	• Lymphomas
• Chronic lymphatic leukaemia	• Nonspecific lymphadenitis
• Infectious mononucleosis	• Sarcoidosis
• Actinomycosis	• Brucellosis
• Toxoplasmosis	



Figs 5.22A and B: Lymphoma neck involving both sides. Lymphomas are smooth, nontender, firm/India rubber consistency.



Fig. 5.23: Swelling in the neck well-localised. Note the scar of previous biopsy/excision. It could be lymph node enlargement due to lymphoma or tuberculosis.

TUBERCULOUS LYMPHADENITIS

Causative organism: Mycobacterium tuberculosis (not *M. bovis*).

Site

- Common in neck lymph nodes.
- Common in *upper deep cervical (jugulodigastric—54%) lymph nodes.*
- Next common is posterior triangle lymph nodes. (22%).
- Disease can also occur in other lymph nodes like, axillary lymph nodes, para-aortic lymph nodes, mesenteric lymph nodes, inguinal lymph nodes.
- Disease may be associated with HIV infection, lymphomas.



Fig. 5.24: Cold abscess in the neck which has formed collar stud abscess. It eventually leads in to sinus formation.

Mode of Infection

- Usually through the *tonsils,* occasionally through blood from lungs.
- It may be associated with pulmonary tuberculosis or renal tuberculosis.
- Rarely spread can occur from tuberculous lesion of the apex of lung through suprapleural Sibson's fascia/membrane to supraclavicular nodes.

Stages of tuberculous lymphadenitis

1. Stage of *infection, and lymphadenitis*
2. Stage of *periadenitis with matting*
3. Stage of *caseating necrosis and cold abscess* formation
4. Stage of formation of *collar stud abscess*
5. Stage of formation of *sinus* which discharges yellowish caseating material

- Often fibrosis and calcification can occur with or without treatment.



Figs 5.25A to C: Cold abscess due to caseating tuberculous lymphadenitis in neck. Collar stud abscess in the neck. Tuberculous sinus formation after drainage.

Direction is a matter of fact; ideas are matter of opinion.

Gross Pathology

- Firm, matted, lymph node, with cut section showing yellowish caseating material.



Fig. 5.26: Tuberculous lymphadenitis – cut section of the specimen. Note the yellowish caseating material with periadenitis (matting). Caseating type is more common than hyperplastic type.

Microscopic

- Epithelioid cells with caseating material are seen along with Langhan's type of giant cells.

Clinical Features

- Swelling in the neck which is firm, matted.
- Cold abscess is soft, smooth, nontender, fluctuant, without involvement of the skin. It is not warm.
- As a result of increased pressure, cold abscess ruptures out of the deep fascia to form *collar-stud abscess* which is adherent to the overlying skin.
- Once collar-stud abscess bursts open, discharging sinus is formed. It can be multiple, wide-opened/mouthed, often undermined, non mobile with bluish color around the edge. It is usually not indurated.
- *Tonsils may be studded with tubercles* and so clinically should always be examined.
- Associated pulmonary tuberculosis should also be looked for.
- Cervical spine is examined for tuberculosis.

Differential Diagnosis

1. Nonspecific lymphadenitis.
2. Lymphomas, and chronic lymphatic leukaemia.


Stage 1: Lymphadenitis
(Discrete nodes, nontender, firm/hard mobile)
Stage 2: Matting
(Firm, nontender, move together en mass – due to periadenitis)
Stage 3: Cold abscess
(Deep to deep fascia)
Stage 4: Collar-stud abscess
(Rupture through deep fascia under the skin, cross fluctuant, adherent to skin)
Stage 5: Sinus formation

Fig. 5.27: Stages of tuberculous lymphadenitis.

Types		
1. *Hyperplastic*		2. *Caseating*
a. 20% common	——	a. 80% Common
b. *Discrete*, firm or hard	——	b. *Matted* due to periadenitis
c. Occurs in the cortex of lymph node	——	c. Involves medulla with periadenitis
d. Host immunity is good	——	d. Body resistance is not adequate
e. Drugs act better	——	e. Drugs do not reach in proper concentration and may not be effective
f. Drug resistance is uncommon	——	f. Drug resistance is common
g. No cold abscess or sinus formation	——	g. Cold abscess or sinus are common
h. Blood spread	——	h. Spread from tonsils

3. Secondaries in the neck.
4. Branchial cyst mimics cold abscess.
5. Lymph cyst mimics cold abscess.
6. HIV with lymph node involvement.
7. When there is discharging sinus-actinomycosis.

Cold abscess –

- Deep to deep fascia
- No evidence of signs of inflammation
- Not warm, nontender, smooth, soft and fluctuant, non-transilluminating
- Not adherent to skin (skin is free); no redness
- Contains cheesy caseating material
- It is seen in caseating tuberculous lymphadenitis due to caseation necrosis
- It may form collar stud abscess and later sinus
- FNAC, AFB, culture are useful investigations
- Differential diagnosis are branchial cyst, lymph cyst
- Treated by
  - Antituberculous drugs
  - 'Zig - zag' aspiration by wide bore needle in non-dependent area to prevent sinus formation
  - Drainage using nondependent incision; later closure of the wound without placing a drain

Investigations

1. Haematocrit, ESR.
2. FNAC of lymph node and smear for AFB and culture.
3. HIV test (ELISA and western blot).
4. Open biopsy when FNAC is inconclusive.
5. Chest X-ray to look for pulmonary tuberculosis.
6. Polymerase chain reaction (PCR) is very useful method.

Treatment

- *Drugs*

Antitubercular drugs has to be started**:**

1. Rifampicin 450 mg OD on empty stomach. It is bactericidal. It discolours urine red. It is also hepatotoxic.
2. INH: 300 mg OD. It is bactericidal. It causes intolerance of GIT, Neuritis, Hepatitis (INH).
3. Ethambutol 800 mg OD. It is bacteriostatic. It causes GIT intolerance, retrobulbar neuritis (green colour blindness).
4. Pyrazinamide 1500 mg OD (or 750 mg BD). It is bactericidal. It is hepatotoxic, also causes hyperuricaemia and increases psychosis.

Duration of treatment is usually 6-9 months.

- *Aspiration*

When there is cold abscess, initially it is aspirated. (Wide bore needle is introduced into the cold abscess in a nondependent site along a *"Z" track* (in zigzag pathway) so as to prevent sinus formation.)

- *Incision and drainage*

If it recurs, then it should be drained. Drainage is done through a *nondependent incision***.** After draining the caseating material, *wound is closed without placing a drain***.**

- *Surgical removal*

Surgical removal of tubercular lymph nodes are indicated when

1. There is no local response to drugs or
2. When sinus persists.



Figs 5.28A to C: Typical cold abscess in the neck in which pus is aspirated. Pus should be sent for cytology (for epithelioid cells), staining (Ziehl Neelsen - AFB) and culture.

It takes 5 years to learn when to operate, and 20 years to learn when not to.



Fig. 5.29: Cold abscess with impending rupture.

It is done by raising skin flaps and removing all caseating material and lymph nodes. Care is taken not to injure major structures.

- *Excision of the sinus track* is often essential when sinus develops.

SECONDARIES IN NECK LYMPH NODES

Levels in Neck Nodes (Memorial Sloan—Kettering Cancer centre levelling of neck nodes)

Level I—Submental (Ia) and submandibular (Ib) lymph nodes.

Level II—Lymph nodes in upper deep cervical region. (It extends from base of skull to hyoid bone and from lateral margin of sternothyroid to posterior margin of sternomastoid muscle.)

Level III—Lymph nodes in middle cervical region (from hyoid bone to omohyoid muscle or cricothyroid membrane).

Level IV—Lymph nodes in lower cervical region (from omohyoid muscle to clavicle).

Level V—Lymph nodes in posterior triangle including supraclavicular region.

Level VI—Lymph nodes in the midline neck—pretracheal and prelaryngeal.

Level VII—Lymph nodes in the mediastinum.

Note: Level II and V are now subdivided into level IIa/level IIb and level Va/level Vb depending on nodes in this levels above the level (level IIb/level Vb) of the spinal accessory nerve or below (level IIa/level Va).



Fig. 5.30: Levels of neck nodes.

Common sites of primary

1. Oral cavity, tongue, tonsils
2. Salivary glands
3. Pharynx – nasopharynx
4. Larynx
5. Oesophagus
6. Lungs
7. GIT
8. Thyroid



Figs 5.31A to D: Typical secondaries in the neck. Note the different levels involved in different patients. Note the skin involvement and sinus formation in few photos.

- It is commonly from squamous cell carcinoma, but can also be from adenocarcinoma or melanoma.
- Squamous cell carcinoma is mainly from oral cavity, pharynx.
- Adenocarcinoma is usually from GIT, commonly involving left supraclavicular lymph nodes.

Note: Branchiogenic carcinoma:

It is a primary squamous cell carcinoma arising from remnants of branchial cleft or arch. It is a differential diagnosis for secondaries in neck.

Treatment: Wide excision.

Features of Secondaries in Neck

- Common in adult/elderly male, presents as painless rapidly increasing localised swelling in the neck.
- Nodular surface and hard in consistency, often fixed when it is advanced.
- Secondaries from *papillary carcinoma of thyroid* can be soft, cystic with brownish black fluid.
- Secondaries can infiltrate into carotids, sternomastoid, posterior vertebral muscles, spinal accessory nerve (shrugging of shoulder is affected), hypoglossal nerve (tongue will deviate towards the same side), cervical sympathetic chain (*Horner's syndrome*).
- Secondaries spread into adjacent soft tissues and also to the skin causing fungation and ulceration. Often because of tumour necrosis, softer area develops in the hard node. Skin fold prominence due to infiltration of the platysma is typical.
- In advanced cases tumour may infiltrate into the major vessels like carotids, or branches of external carotid artery causing torrential haemorrhage.
- Dysphagia, dyspnoea, haemoptysis, hoarseness of voice, ear pain, deafness are other features depending on the primary site.

- *Hoarseness*—carcinoma larynx, thyroid
- *Dysphagia*—carcinoma posterior 1/3rd of the tongue, pharynx, oesophagus
- *Haemoptysis, cough, dyspnoea*—carcinoma lung
- *Ear pain, deafness*—nasopharyngeal carcinoma
- *Spinal accessory nerve*—Shrugging of shoulder is difficult
- *Hypoglossal nerve*—Tongue deviates to same side with wasting
- *Sympathetic chain*—Horner's syndrome with miosis, anhidrosis, upper eyelid droop (pseudoptosis), enophthalmos, loss of spino-ciliary reflex



Fig. 5.32: Secondaries in the neck nodes from laryngeal carcinoma.

Types of Secondaries in the Neck

1. *Secondaries in the neck with known primary*

- Here secondaries are present and primary has been identified clinically in the oral cavity, pharynx, larynx, thyroid or other areas.
- Biopsy from the primary and FNAC from the secondaries are done.
- Primary is treated accordingly either by curative radiotherapy or by surgery (wide excision).
- Secondaries, when mobile are treated by radical lymph node block dissection in the neck.

2. *Secondaries in the neck with clinically unidentified primary*

- Hard, neck lymph nodes are the secondaries, but primary has not been identified clinically.
- FNAC of the neck node is done and secondaries is confirmed. Then search for the primary is done by various investigations.

They are

a. Nasopharyngoscopy.
b. Laryngoscopy.
c. Oesophagoscopy.
d. Bronchoscopy.
e. Blind biopsies from the fossa of Rosenmuller, lateral wall of pharynx, pyriform fossa, larynx.
f. FNAC of thyroid and suspected areas.
g. CT scan.

Happiness is when what you think, what you say, and what you do are in harmony—Mahatma Gandhi.



Figs 5.33A and B: Advanced secondary carcinoma neck with ulceration and fungation.



Figs 5.34A and B: Large secondaries in neck with extensive fungation.

Once the biopsy confirms the primary, it is treated either by *surgery* or by *curative radiotherapy*.

Secondaries in the neck is treated by *radical neck dissection*.

3. *Secondaries in the neck with an occult primary*

Occult primary sites which can cause secondaries in neck

- Fossa of Rosenmuller
- Lateral wall of pharynx
- Posterior third of the tongue
- Thyroid
- Paranasal sinuses
- Bronchus
- Oesophagus

Histologically secondaries in neck with occult primary may be of squamous cell carcinoma or of non-squamous cell carcinoma, i.e. adenocarcinoma /poorly differentiated tumours (lymphoma/sarcoma/melanoma). In upper and mid cervical region 80% are due to squamous cell carcinomas. In lower cervical and supraclavicular region 40 % can be adenocarcinomas. Common sites of primary here (for adenocarcinoma) are thyroid, breast, gastrointestinal tract, salivary glands, lungs, prostate and kidney.

- Here secondaries in the neck lymph nodes are confirmed by FNAC, *but primary has not been revealed clinically and by any available investigations.*



Figs 5.35A and B: Large secondaries in neck with nodularity, with involvement of platysma below. In second photo bilateral secondaries are observed. **Skin fold prominence is obvious.**



Fig. 5.36: Secondaries in neck with nodules and ulceration. Note the deviation of tongue towards same side due to hypoglossal nerve involvement.

- When all the investigations mentioned above are done, do not show any evidence of primary, only then it is called as *occult primary.*
- Primary tumor is not identified at the time when definitive therapy has started.
- 70% of occult nodes occur in jugulodigastric group.
- Differential diagnosis for secondary with occult primary is lymphoma and *primary branchiogenic carcinoma.*
- Reasons for primary lesion being occult – Too small a primary to detect; possibility of immunological spontaneous regression of primary and inability of the present diagnostic tools to detect the primary.
- FNAC is the tool to confirm the occult secondary. If FNAC is inconclusive, only then open biopsy (incision/excision) is done to confirm. Open biopsy helps in high suspects of lymphomas or poorly differentiated carcinomas. It facilitates tissue study, immunohistochemistry, and special stains. Many studies prove that risk of seedling, survival and prognosis will not alter by open biopsy. But at present it is proposed only when FNAC fails or special methods are mandatory to type the disease.

- Immunoperoxidase staining can be done in FNAC specimen or formalin fixed paraffin tissue using monoclonal or polyclonal antibodies. Immunoperoxidase is the most commonly used tool. It is mainly useful in lymphomas/neuroendocrine tumours. Electron microscopy is superior to immunohistochemistry as ultrastructure details can be assessed. But it is costly. Chromosomal analysis for tumour specific genes is used in B, T and germ cell lymphomas.
- Initially the secondaries in the neck are treated by *radical neck dissection*, then *regular follow-up* is done (at three monthly intervals) until the primary reveals.
- Once primary is revealed it is *confirmed by biopsy* and treated accordingly, either by *curative radiotherapy* or by *wide excision* depending on location of revealed primary.
- This type is usually less aggressive and has got better prognosis.

Nodal staging in secondaries

N_0—nodes not detected
N_1—single node same side < 3 cm
N_{2a}—single node same side 3-6 cm
N_{2b}—multiple nodes same side < 6 cm
N_{2c}—bilateral/contralateral nodes < 6 cm
N_3—node > 6 cm

Investigations for Secondaries in Neck

1. FNAC of secondary.
2. Biopsy from primary.
3. Blind biopsies from suspected areas.
4. Nasopharyngoscopy, laryngoscopy, bronchoscopy, oesophagoscopy.
5. CT scan is to see the base of skull, paranasal sinuses, nasopharynx, extension of primary tumour/secondary deposits; CT scan of chest and abdomen.
6. Chest X-ray to visualise primary or secondaries in case melanomas or mediastinal nodes.
7. MRI scan or PET scan in conjunction with CT scan or MRI.

Open incision biopsy is avoided in lymph node secondaries.

***Triple endoscopy** includes direct/indirect laryngoscopy, oesophagoscopy and bronchoscopy.*



Fig. 5.37: CT neck showing secondaries.

Differential Diagnosis

1. Lymphomas.
2. Tuberculous lymphadenitis.
3. Non-specific lymphadenitis.
4. HIV.
5. Chronic lymphatic leukaemia.



Figs 5.38A to C: Secondaries in neck but no skin involvement in first photo. In second and third photos, secondaries with skin involvement is obvious.

Example isn't the best way to teach, it's the only way.

In secondaries neck with occult primary –

- FNAC of node/open biopsy to confirm
- Proper clinical methods to identify the location of primary
- CECT is the investigation of choice to look for primary
- Other methods are – MRI, triple endoscopy, examination under anaesthesia, blind biopsies from fossa of Rosenmuller, pyriform fossa, base of tongue, subglottic area and tonsils, FNAC of thyroid, ipsilateral tonsillectomy if surveillance biopsy and other methods are negative
- Once occult primary is confirmed and if node is less than 3 cm in size, it is treated as N_1 disease with RND/MRND
- Post operative RT is essential if disease is N_{2a}; N_{2b} (more than 2 nodes are positive); if 2 or more levels are involved; if extracapsular spread is present
- In fixed lymph node/nodes, initially radiotherapy is given followed by surgery (RND) if nodes become mobile and later adjuvant chemotherapy
- In N_{2c} bilateral neck dissection (one side IJV preservation) with bilateral RT is given
- N_3 stage has got poor prognosis. RND and RT with later chemotherapy are used. In fixed nodes, RT and then chemotherapy is used
- Proper follow up at regular intervals is essential with all diagnostic tools to identify the possible site of primary which may get revealed during follow up period

Treatment

- Primary is treated depending on the site, either by *wide excision (surgery)* or by *curative radiotherapy*. Then the secondaries are treated.
- Secondaries when *mobile*, are treated by *radical neck dissection*.



Figs 5.39A and B: Secondaries in neck with ulcer over the summit.

- When *fixed* it is *inoperable*. *Palliative external radiotherapy* is given to palliate pain and to prevent the anticipated bleeding.
- Sometimes *initially*, *external radiotherapy* is given to *downstage* the disease so that it becomes operable and later classical block dissection can be done.

Types of Block Dissection:

1. *Classic radical neck dissection*



Fig. 5.40: Mac fee incision for radical neck dissection. Upper incision is from mastoid process along the line of digastric to hyoid bone point then upwards to chin. Lower incision is parallel to clavicle 2 cm above from anterior margin of trapezius to midline.



Fig. 5.41: FNAC of neck lymph node. It is very useful method in secondaries in neck node and tuberculosis. Its use is equivocal in lymphoma where open biopsy of the node is preferred method. (*Courtesy by Dr Krishna Upadhya Pathologist, Nandikoor Laboratory, Mangalore*)

It is resection of lymph nodes (level I to V), fat, fascia, sternomastoid muscle, omohyoid muscle, internal jugular vein, external jugular vein, accessory nerve, submandibular salivary gland, lower part of parotid, prevertebral fascia—*"en-block"(Criles' operation).*

Incision that is commonly made is *Mc'Fee* incision which are two parallel incisions, one at submandibular region, another at supraclavicular region. Blood supply of the flap remains intact and so healing will be better without flap necrosis.



Figs 5.42A and B: Incisions/different approaches for radical (RND/MRND) neck dissections. There are many incisions mentioned. Few of them are shown in diagram.

2. *Conservative functional block dissection (After BOCCA surgeon): (Modified radical neck dissection—MRND)*

It is done only in selected cases where tumour is very well-differentiated and less aggressive like in papillary carcinoma of thyroid with lymph node secondaries. Structures preserved here are sternomastoid muscle, internal jugular vein and spinal accessory nerve.



Fig. 5.43: Radical neck dissection on table photo. Note the internal jugular vein, digastric muscle, strap muscles, lower margin of the mandible.

- Only spinal accessory nerve is preserved —MRND type I (most important).
- Accessory nerve and sternocleidomastoid are preserved—-MRND type II.
- Accessory nerve, sternomastoid and internal jugular veins are preserved—MRND type III.

3. *Supraomohyoid block*

Removal of only fat, fascia, lymph nodes, muscles, submandibular salivary gland, with dissection above the omohyoid muscle is done. Done only in selected individuals with well-differentiated tumour and involvement of few submandibular lymph nodes. (*Levels I, II, III are removed*). Done in N0 lesions.

4. *Bilateral neck dissection*

Here internal jugular vein is preserved on one side. *Always the side where the vein is preserved, is operated first.* (If both the jugulars are ligated, cerebral congestion occurs leading to cerebral oedema which is dangerous. Jugular veins are ligated as an inevitable procedure during surgery, the patient is kept in propped-up position; antibiotics, diuretics, steroids are given, repeated CSF taps are done to control the cerebral oedema).

Listen to the faintest sound; for opportunities knock only once.

5. *Commando operation: (Combined mandibular dissection and neck dissection)*

It is *en-block removal*, which includes wide excision of primary tumour with hemimandibulectomy and neck block dissection, e.g. in tongue.

6. *Lateral neck dissection (anterolateral/jugular/ALND)*

It is done in laryngeal and pharyngeal primaries with clinically negative nodes. Levels II, III, IV are removed bilaterally.

7. *Anterior (central) dissection*

Level VI (pre, paratracheal) nodes are removed.

8. *Postero-lateral dissection*

Levels II, III, IV, V are removed for cutaneous malignancies, with suboccipital nodes.

9. *Extended radical dissection*

Additional nodes in the mediastinum are cleared (level VII). Nodes like level VI or parapharyngeal, retropharyngeal, external carotid artery, hypoglossal nerve, parotid gland, mastoid tip—are addressed.

Complications of block dissection

1. Haemorrhage
2. Infection
3. Lymph ooze
4. Carotid blow out
5. Seroma and flap necrosis
6. Frozen shoulder is common
7. Rarely pneumothorax and chylous fistula
8. Drooping of shoulder due to paralysis of trapezius in radical neck dissection

Note: *To control haemorrhage* in head and neck cancers and during head and neck surgeries (like radical parotidectomy, commando operation, maxillectomy) often ligation of external carotid artery is required. ***Ligation should be done distal to the origin of the superior thyroid artery***. It should never be ligated below the origin of the superior thyroid artery as this will lead to formation eddy current and thrombus at the carotid bifurcation and intracranial embolism. Ligation of ECA to control bleeding is usually done in continuity.



Fig. 5.44: Ligation of external carotid artery should be done when needed distal to the origin of the superior thyroid artery.

Carotid blow out is most dangerous complication. It is due to sepsis, wound breakdown, stripping of arterial adventitia, necrosis and drying of the artery. Ligation of the carotid is done to save the life of the patient but procedure itself has got 20% mortality and 50% morbidity (hemiplegia).

Type of neck dissection	*Nodes removed*	*Structures preserved*
Comprehensive –		
Radical neck dissection (RND)	Level I-V	None
MRND type I	Level I-V	Spinal accessory nerve
MRND type II	Level I-V	Spinal accessory nerve; sternomastoid muscle
MRND type III	Level I-V	Spinal accessory nerve; sternomastoid muscle; IJV
Selective node dissection –		
Supraomohyoid neck dissection (N_0)	Level I-III	Spinal accessory nerve; sternomastoid muscle; IJV
Extended supraomohyoid dissection (N_0)	Level I-IV	Spinal accessory nerve; sternomastoid muscle; IJV
Anterolateral neck dissection (N_0)	Level II-IV	Spinal accessory nerve; sternomastoid muscle; IJV
Posterolateral neck dissection (N_0)	Level II-V with suboccipital, retroauricular nodes	Spinal accessory nerve; sternomastoid muscle; IJV
Anterior / central dissection	Level VI	Spinal accessory nerve; sternomastoid muscle; IJV

CHEMOTHERAPY FOR HEAD AND NECK CANCERS

It may be used alone or as multimodality therapy.

Types

- *Adjuvant chemotherapy*: Chemotherapy is used before, during or after main therapeutic modality (surgery or radiotherapy). When used before it is called as anterior /*induction* chemotherapy. It reduces the burden, downstages the tumour, reduces the chance of micrometastasis that may occur during surgery. When used with radiotherapy (concurrent) it is used as radio sensitiser. When used after surgery/radiotherapy it is called as *posterior* chemotherapy.
- *Palliative chemotherapy*: It is used in advanced/ recurrent/metastatic cancers to relieve symptoms like pain/dysphagia/dyspnoea or to prevent chances of bleeding or fungation.

It may be single drug therapy like methotrexate/ bleomycin/cisplatin/5-fluorouracil or multidrug combination chemotherapy. Combination chemotherapy is more beneficial which increases efficacy.

- Methotrexate – 40 mg/m^2 IV weekly. It causes mucositis, bone marrow suppression with liver and kidney toxicity. Hydration and alkalisation of urine before and after therapy is beneficial to reduce toxicity.
- 5 - Fluorouracil – 10-15 mg/m^2 IV daily for 5 days. Complications are bone marrow suppression and gastrointestinal symptoms.
- Bleomycin – 10-20 mg/m^2 IV weekly. Pneumonitis and *pulmonary fibrosis* are the complications.
- Vincristine – 1-2 mg/m^2 IV monthly. *Neurotoxicity* (sensory and motor neuropathy), constipation and alopecia are the side effects.
- Cisplatin – 80-120 mg/m^2 IV infusion once in 3 weeks. Complications are neurotoxicity, bone marrow suppression, renal toxicity, ototoxicity. Adequate hydration and mannitol diuresis may be needed.
- Cyclophosphamide – 60-120 mg/m^2 IV for 5 days at regular 3 weeks cycles. Alopecia, bone marrow suppression and *cystitis* (haemorrhagic) are the toxicities (ABC). Barbiturates should be avoided during therapy.
- Adriamycin – 60-90 mg/m^2 IV. It is *cardiotoxic* and hence cardiac monitoring is needed while infusion.
- Paclitaxel and carboplatin as empiric chemotherapy are used in neck secondaries with occult primary.

Mode of Administration

- It can be given by *intra-arterial route, through external carotid artery* (Never through internal carotid as it will cause cerebral damage). Site of arterial catheter should be confirmed by Doppler or angiogram. Drug is usually administered through an arterial pump. Other method is to increase the height of the drip stand to get a pressure above the level of the systolic pressure of the patient. (i.e. more than 13 ft).
- Drugs can also be given intravenously or orally (methotrexate).

General toxicity of chemotherapeutic agents: Mucositis, alopecia, stomatitis, nausea and vomiting, diarrhoea, bone marrow suppression.

Often transfusions of blood/FFP/platelet are needed before or after chemotherapy depending on parameters.

Monitoring the Patient on Chemotherapy

- Clinical assessment – pulse, blood pressure, alopecia, urine output, jaundice, skin changes like rashes, fever, palor.
- Biochemical parameters – total count, platelet count, blood urea and serum creatinine, liver function tests.
- Specific relevant tests – chest X-ray, endoscopy, CT scan, tumour marker if specific in some types of carcinomas.

RULE OF 80 IN THE NECK

- 80% of nonthyroid neck masses are neoplastic
- 80% of neoplastic neck masses are seen in males
- 80% of neoplastic neck masses are malignant
- 80% of malignant neck masses are metastatic
- 80% of metastatic neck masses are from primary sites above the clavicle

Note: For carotid artery aneurysm—refer Chapter on Arterial Diseases.

'Excellence' is an outcome, of good intentions and the right ways to do a work.

Self-assessment Questions

- Branchial cyst.
- Branchial fistula.
- Thyroglossal cyst.
- Cystic hygroma.
- Thyroglossal fistula.
- Sistrunk operation.
- Sternomastoid tumour.
- Cervical rib.
- Collar-stud abscess.
- Adson test.
- Secondaries in the neck.
- Cold abscess.
- Tuberculous lymphadenitis.
- Differential diagnosis for neck lymph node enlargement.
- Torticollis.
- Wry neck.
- Sternomastoid tumour.
- Secondaries in the neck.
- Secondaries in the neck with occult primary.
- Commando operation.

6

Thyroid

> ***(The thyroid gland) has no very evident mechanical or local office to fulfill…. Yet we may one day be able to show, that a particular material principle is slowly formed, and partially kept in reserve; and that this principle (serves) important subsequent functions in the course of the circulation…. Something analogous to a reservoir function obtains in this part.***
>
> —**Thomas Wilkinson King**, 1836

Development
Anatomy
Physiology
Congenital anomalies
Thyroid function tests
Classification of goitre
Nodular goitre
Solitary thyroid nodule
Retrosternal goitre
Thyrotoxicosis
Thyroid neoplasms
Hashimoto's thyroiditis
de Quervain's subacute granulomatous thyroiditis
Riedel's thyroiditis
Thyroid incidentaloma
Thyroidectomy
Emil Theodor Kocher
Kocher's test
Hypothyroidism
Recurrent laryngeal nerve palsy

DEVELOPMENT

The thyroid gland develops from a median down growth of a column of cells from the pharyngeal floor between the first and second pharyngeal pouches (subsequently marked by the foramen caecum of the tongue).

The canalised column becomes the *thyroglossal duct* which is displaced forward by the developing hyoid bone and then below the hyoid, lies slightly to one side, more commonly to the left. The duct bifurcates to form the thyroid lobes and a portion of the duct forms the pyramidal lobe.


Recurrent laryngeal nerve
Oesophagus
Carotid sheath
Parathyroid
Carotid artery
Vagus
Sympathetic chain
Int jugular vein
Trachea
Thyroid
Int jugular vein
Thyroid cartilage
Superior thyroid vein
Middle thyroid vein
Thyroid
Inferior thyroid vein
CCA
Lt brachiocephalic vein

Fig. 6.1: Relations of the thyroid.

ANATOMY

It is located in the anterior triangle of the neck. It weighs about 20 grams.

Parts

- *Right and left lateral lobes* located in a space (thyroid fossa) between trachea and oesophagus medially and

The art of medicine consists in amusing the patient while nature cures the disease.

carotid sheath laterally. Each lobe is 5 × 3 × 1.5 cm in size, extends from the middle of thyroid cartilage to 6th tracheal ring.

- *Isthmus* is the connecting part between two lateral lobes in midline extending from 2nd to 4th tracheal rings.
- *Pyramidal lobe* is upward extension as fibrous strands or muscular strands from the junction of the isthmus and left lateral lobe.
- Gland is invested by *pretracheal fascia*.
- *Berry's ligament* is a strong condensed vascular connective tissue between the lateral lobe and cricoid cartilage on each side.

Blood Supply

- *Superior thyroid artery* is first anterior branch of external carotid artery enters the gland near superior pole as a larger anterior superficial branch and a smaller posterior branch.
- *Inferior thyroid artery*, a branch of thyrocervical trunk of subclavian artery passes behind the carotid sheath running medially reaching the posterolateral aspect of the gland.
- *Thyroidea ima artery*, a branch of aorta or brachiocephalic artery enters the isthmus or lower pole of one of the lateral lobes (10%).
- Tracheal and oesophageal branches serve blood supply to retained thyroid gland after thyroidectomy.

Venous Drainage

- *Superior thyroid vein.*
- *Middle thyroid vein* is short and drains into the internal jugular vein. It is first to be ligated in thyroidectomy.
- *Inferior thyroid veins* are many in number.
- *Kocher's vein* may be present which drains lower or middle thyroid.

Lymphatic Drainage

- *Primary*:
  Tracheo-oesophageal nodes.
  Prelaryngeal nodes (Delphian nodes).
  Mediastinal nodes.
- *Secondary*:
  Deep cervical nodes.
  Supraclavicular nodes.
  Occipital nodes.

Important Relations of Thyroid gland

- Recurrent laryngeal nerve lies in the tracheo-oesophageal groove, in relation to Berry's ligament.
- Superior laryngeal nerve which gives a branch, external laryngeal nerve supplies cricothyroid muscle. It accompanies superior thyroid artery.



Fig. 6.2: Lymphatic drainage of thyroid.

- Parathyroid glands—four in number, two on each side embedded in thyroid.

PHYSIOLOGY

Thyroid gland has two secretory cells:

1. *Follicular cells*—secretes thyroid hormones (Thyroxine (T_4), Tri-iodothyronine (T_3).
2. *Parafollicular cells* ('C' cells)—secretes calcitonin.

I_2 Metabolism

Ninety per cent of body iodide uptake is in the thyroid gland, whose uptake into the follicular cells is regulated by TSH and follicular iodide content.

Thyroid Hormone Synthesis

Iodothyronins (MIT, DIT) are formed in follicular cells by the coupling of inorganic iodide with tyrosine. These are biologically inert molecules. T_4 (Thyroxine) is formed by coupling of 2 DIT molecules and T_3 (Tri-iodothyronine) is formed by coupling of 1 MIT and 1 DIT molecules. Both are bound to thyroglobin which is the primary component of colloid matrix.

The hypothalamus–pituitary-thyroid axis regulates thyroid hormone production and releases in a classic feedback system. TRH is a regulatory hormone from hypothalamus and TSH is a regulatory hormone from anterior pituitary.


Tongue
Foramen caecum
Hyoid bone
Thyroglossal duct
Thyroid cartilage
Parathyroid (superior)
Thyroid
Pyramidal lobe
Parathyroid (inferior)
Trachea
Thyro-thymic ligament
Thymus

Fig. 6.3: Anatomy of thyroglossal duct showing its pathway.

CONGENITAL ANOMALIES

ECTOPIC THYROID

Ectopic thyroid tissue may lie anywhere along the line of descent. Whole of the thyroid gland or residual thyroid lies in an abnormal position either in the posterior part of the tongue, or in the upper part of the neck in midline, or intrathoracic region. Radioisotope scan, CT scan for intrathoracic thyroid will confirm the diagnosis.

LINGUAL THYROID

It is a thyroid swelling in the posterior third of tongue, at the foramen caecum, presenting as rounded swelling. It may be the only existing thyroid tissue which may cause—

a. Dysphagia.
b. Speech impairment.
c. Respiratory obstruction.
d. Haemorrhage.

Any diseases which can occur in normal thyroid can also occur in lingual thyroid, i.e., nodularity, toxicity, malignancy.

Diagnosis

- *Radioisotope study* shows the uptake of iodine by the lingual thyroid and also shows the status of the thyroid in normal fossa.
- U/S neck has to be done to see the absence of thyroid in normal location.


Foramen caecum
Tongue
1/3
2/3
1
2
3
Hyoid bone
4
1. Ectopic lingual thyroid
2. Intralingual thyroid
3. Sublingual thyroid
4. Thyroglossal cyst
5. Retrosternal thyroid
Pyramidal lobe
Lateral lobe of thyroid
5

Fig. 6.4: Ectopic sites of thyroid.

Treatment

- L-Thyroxine is given daily orally.
- Often requires surgical excision and is technically easier.
- Radioisotope therapy for ablation is also often used.

THYROGLOSSAL CYST

- Thyroglossal cyst is a swelling occurring in the neck in any part along the line of thyroglossal tract.

Possible sites for thyroglossal cyst:

a. Beneath the foramen caecum
b. In the floor of mouth
c. Suprahyoid
d. Subhyoid—commonest site
e. On the thyroid cartilage

- It is usually congenital wherein there will be degeneration of a part of the tract causing cystic swelling. Normal thyroid may be present in the normal location (fossa). Sometimes, thyroid may not be present in the normal site but may be present in the wall of the thyroglossal cyst.
- It is a tubulodermoid type of cyst.
- It is lined by pseudostratified, ciliated columnar epithelium.

Clinical Features

a. Swelling in the midline, towards the left.
b. Moves with deglutition as well as with the protrusion of tongue. Patient is asked to open the mouth and keep

The person who really wants to do something finds a way: the other finds an excuse.



Figs 6.5A and B: Thyroglossal cyst.



Fig. 6.6: Thyroglossal cyst in a boy. It is a midline swelling with a 'TUG' feeling while protruding the tongue out.

the lower jaw still. Examiner holds the cyst between the thumb and forefinger. When the patient is asked to protrude the tongue, a "*tugging sensation*" can be felt.

c. Swelling is smooth, soft, fluctuant (cystic), nontender, mobile, often transilluminant.
d. Thyroid fossa is empty, if there is no thyroid in normal location.
e. Thyroglossal cyst can get infected and may form an abscess.
f. Malignancy can develop in thyroglossal cyst (papillary carcinoma).
g. Incidence is equal in both sexes.

Investigations

a. Radioisotope study.
b. U/S neck.
c. FNAC from the cyst.

Differential diagnosis for thyroglossal cyst

- Subhyoid bursa
- Pre tracheal lymph node
- Dermoid cyst
- Solitary nodule of thyroid – isthmus

Treatment

a. *Sistrunk operation:* Excision of cyst and also full tract upto the foramen caecum is done along with removal of central part of the hyoid bone, as the tract passes through it.

Technique

Through transverse neck incision placed over the cyst, skin flap is raised above along with platysma. Care should be taken not to open the cyst. Cyst with surrounding tissues is dissected up to the hyoid bone. Sternohyoid and thyrohyoid muscles are divided. Central part of the hyoid bone is resected along with intact track within it. Geniohyoid and mylohyoid muscles are divided off from the hyoid. Track with adjacent tissues is dissected above upto the foramen caecum. Adjacent tissues also should be removed because of possibility of multiple tracks which otherwise lead to recurrence or fistula formation. Often anaesthetist is asked to apply digital pressure over the base of tongue near foramen caecum to facilitate the dissection and to confirm the reach up to the foramen caecum. Track is ligated at foramen caecum and removed. Recurrence rate by removal of only track without central hyoid is 25%. Removal of track with central hyoid reduces the recurrence rate to 5%. Complications are recurrence, thyroglossal fistula formation, haemorrahage/haematoma formation and infection.

b. If there is no normal thyroid gland after the surgery, maintenance dose of L-thyroxine 0.1 mg OD is given life long.

Note: If tract is not completely excised, it will result in thyroglossal fistula.

THYROGLOSSAL FISTULA

- *It is not a congenital condition*.
- It either follows infection of thyroglossal cyst which bursts open or after inadequate removal of the cyst.
- It is lined by columnar epithelium, discharges mucus and is a seat of recurrent inflammation. "Hood sign" is characteristic. Opening of fistula is indrawn and been overlaid by a fold of skin as 'hood'.



Fig. 6.7: Thyroglossal fistula in a patient who has undergone surgery for thyroglossal cyst. Note the scar above the fistula.



Fig. 6.8: Thyroglossal fistula.

- **Investigations:** Radioisotope study and fistulogram.
- **Treatment:** Sistrunk operation.

(*Note:* One more sistrunk operation is done in case of lymphoedema.)

LATERAL ABERRANT THYROID

- It is at present considered as a misnomer.
- It is the metastasis into cervical lymph node from a papillary carcinoma of thyroid.
- FNAC has to be done and treated as papillary carcinoma of thyroid.

AGENESIS

Total agenesis of one thyroid lobe may occur. This is rare but can be clinically important. It leads to confusion in diagnosis, especially in the toxic gland, where it could be diagnosed as a secreting nodule.

DYSHORMONOGENESIS

- It is an autosomal recessive condition wherein there is either deficiency of thyroid enzymes (either peroxidase or dehalogenase) or inability to concentrate or to bind or to retain iodine.
- It may be familial and patient presents with large diffuse vascular goitre involving both lobes.
- They respond very well to L-thyroxine and may not require surgery at any time.
- Condition may be associated with congenital deafness which is being called as *Pendred's syndrome*.

THYROID FUNCTION TESTS

1. T_3 (Serum tri-iodothyronine): 1.2-3.1 nmol/litre.
2. T_4 (Serum thyroxin): 55-150 nmol/litre.
3. TSH 0-5 I.U/ml of plasma.
4. PBI (Protein bound iodide)—8 mg%.
5. Free T_3 is 0.3% (3-9 pmol/litre). It is the best single test in assessing hyperthyroidism.
6. Free T_4 is 0.03% (8-26 pmol/litre).
7. RA I^{123} scan can show either cold nodule, hot nodule, or warm nodule.
8. TRH (Thyrotrophin releasing hormone test). After IV TRH (200 mg), TSH level is estimated. TSH level is below 2.5 m units/L in hyper thyroidism and it is exaggerated in hypothyroid patient (more than 20 m units/L).
9. Serum creatinine is increased in hyperthyroidism; decreased in hypothyroidism.
10. Serum cholesterol is increased in hypothyroidism and decreased in hyperthyroidism.
11. BMR is increased in hyperthyroidism.
12. Thyroid autoantibodies are also useful to evaluate the function (LATS).
13. T_3 suppression test.
14. Thyroglubulin estimation. Normal value is 0.5 – 50 μ g/L. It is used during follow up period especially in follicular carcinoma of thyroid. But if thyroglobulin antibodies are raised in patient, then it is of no use.

CLASSIFICATION OF GOITRE

Goitre is enlargement of thyroid gland.

> *In the case of retrosternal goitre, hemoptysis unmixed with sputum is due to rupture of an engorged tracheal vein.*
> —Peter Burgess



Fig. 6.9: Examination of the thyroid gland from behind for any nodules. Thyroid enlargement in male is rare. Nodule in a male could be malignant.



Fig. 6.10: Thyroid swelling moves on deglutition because of attachment of pretracheal fascia through Berry's ligament to cricoid cartilage and to constrictor muscles.

1. *Simple nontoxic*
   a. Diffuse hyperplastic—
      i. Physiological
         - Puberty.
         - Pregnancy.
      ii. Primary iodine deficiency (Endemic; dietary iodine intake less than 100 μg/day).
      iii. Secondary iodine deficiency—
         - Goitrogens of Brassica family, e.g. cabbage, soya bean. Common in hill stations.
         - Excess dietary fluoride.
         - Drugs: PAS, lithium, phenylbutazone, thiocyanates, potassium perchlorate, antithyroid drugs, radioactive iodine.
         - Dyshormonogenetic goitre.
   b. Colloid goitre.
   c. Nodular goitre (Multinodular).
   d. Solitary nontoxic nodule.
   e. Recurrent nontoxic nodule.
2. *Toxic*
   a. Diffuse (Primary)—*Graves' disease.*
   b. Multinodular (Secondary)—*Plummer's disease*.
   c. Toxic nodule (solitary) (Tertiary).
   d. Recurrent toxicosis.
3. *Neoplastic*
   a. Benign—Adenomas: Follicular, Hurthle cell.
   b. Malignant:
      i. Carcinomas: Papillary, follicular, medullary, anaplastic.
      ii. Lymphomas.



Figs 6.11A and B: Note the goitres in (A) male and (B) female patient.

4. *Thyroiditis*
   Hashimoto's autoimmune thyroiditis.
   de-Quervain's autoimmune thyroiditis.
   Riedel's thyroiditis.
5. *Rare causes:* Bacterial (suppurative), amyloid.



Fig. 6.12: Familial goitre. Goitres in brother and sister.

In a case of thyroid disease following things should be made very clear—

- Functional status – hyperthyroid/euthyroid/hypothyroid
- Compression on trachea/recurrent nerve
- Neck lymph nodal status
- Tracheal deviation
- Carotid infiltration
- Retrosternal extension
- Systemic features like toxicity or malignant spread to different organs like bone/liver/lungs

DIFFUSE HYPERPLASTIC GOITRE

Initial persistent increase in TSH level causes diffuse active lobules. In late stages of diffuse hyperplasia, TSH stimulation decreases and many follicles become inactive, get filled with colloid and it is called *as colloid goitre*.

As diffuse hyperplastic goitre is a reversible stage, L-thyroxine is beneficial.



Fig. 6.13: Pizzillos method to make the thyroid more prominent while examining the thyroid.

NODULAR GOITRE

Pathogenesis



Fig. 6.14: Postsurgical specimen of multinodular goitre.

Persistent TSH stimulation.

↓

Diffuse hyperplasia of gland (all active lobules).

↓

Later with fluctuation of TSH level.

↓

Mixed areas of active and inactive lobules develop.

↓

Active lobules become more vascular and hyperplastic.

↓

Haemorrhages occur with necrosis in the centre.

↓

Nodule formation.

↓

Centre of the nodule is inactive and only margin is active, i.e. internodular tissue is active.

↓

Formation of many nodules.

↓

Multi-nodular goitre (MNG).

Other factors involved are growth stimulating immunoglobulins and growth prone cell clones.

Stages of multinodular goiter formation

- Stage of hyperplasia and hypertrophy
- Stage of fluctuation in TSH
- Stage of formation of nodules (inactive); (internodular tissues are active)

Colloid goiter is a goiter due to long standing iodine deficiency with localized accumulation of significant colloid in the gland.

Some people speak from experience; others, from experience, don't speak.



Fig. 6.15: Multinodular goitre.



Fig. 6.16: Recurrent nodule thyroid. Note scar of previous surgery.

Clinical Features

- More common in middle aged females (10:1).
- It is a slowly progressive disease with many years of history.
- Multiple nodules of different sizes are formed in both lobes, also in isthmus, which is firm, nodular, nontender, moves with deglutition.
- Recent increase in size signifies malignant transformation or haemorrhage.
- Positive Kocher's test is due to compression over trachea (tracheomalacia/scabbard trachea) in a long standing MNG.
- Nodule when calcified becomes harder; necrosis softens the nodule.



Fig. 6.17: Multinodular goitre.



Fig. 6.18: Goitre neck, left sided.

Complications of MNG

1. Secondary thyrotoxicosis (30%)
2. Follicular carcinoma of thyroid (10%)
3. Haemorrhage in a nodule
4. Tracheal obstruction, calcification
5. Cosmetic problem



Fig. 6.19: Multinodular goitre. Note the nodules marked.



Fig. 6.21: Nodular thyroid involving both lobes in a female.

Investigations

- T_3, T_4, TSH, U/S neck, FNAC.
- X-ray neck shows ring or rim calcification; also reveals the position and compression of trachea.
- Indirect laryngoscopy to see vocal cords prior to surgery (This is mainly for documentation and legal purpose as even in individual with normal voice, one of the vocal cords may have been paralyzed by viral infection like mumps, probably during childhood and have compensated).
- Radioisotope iodine scan – in selected patients when indicated only.
- Routine blood investigations.



Fig. 6.20: Large multinodular goitre.



Fig. 6.22: X-ray neck showing calcification in thyroid. Fine calcification is seen in papillary carcinoma. Coarse calcification is seen in Multinodular goitre.

Treatment

Usually surgery is preferred. Reason for doing surgery in nodular goiter is – it is an irreversible stage and chances of complications like development of toxicity, haemorrhage and follicular carcinoma is high and also for cosmetic reason.

- When entire gland is diseased *total thyroidectomy* is a better option.
- *Subtotal thyroidectomy* is done depending on the amount of gland involved, amount of normal gland existing and location of nodules – commonly done procedure in multinodular goitre.

A genius is someone who shoots at a target which no one else sees and hits it.

- Often partial thyroidectomy or Hartley Dunhill operation (isthmus + one entire lateral lobe and opposite side subtotal or partial) is also done depending on the amount of diseased gland and normal tissues behind. Partial thyroidectomy is not well approved now.
- Postoperative L thyroxine is often given to prevent any fluctuation in TSH level which may cause recurrent nodule formation.
- Prevention of multinodular goiter is possible by supplementing with L-thyroxine (0.1-0.2 mg) when patient develops goiter in puberty. Formation of nodular goiter can be prevented by correcting iodine deficiency by using iodine rich diet like eggs/seafood/milk or iodized salts and also avoiding goitrogenic drugs and diet.

SOLITARY THYROID NODULE

It is a single palpable nodule in thyroid on *clinical examination*, in an otherwise normal gland.

Causes

1. Thyroid adenomas
   a. Follicular – colloid (commonest); embryonal; fetal.
   b. Hurthle cell.
   (*Note*: Papillary adenoma earlier called is actually papillary carcinoma).
2. Papillary carcinoma of thyroid.
3. Only one nodule may be clinically palpable in an underlying multinodular goitre.
4. Thyroid cyst.





Figs 6.23A and B: Solitary nodule thyroid in one lateral lobe and isthmus.



Fig. 6.24: Solitary nodule thyroid involving isthmus.

Types

1. Toxic solitary nodule.
2. Nontoxic solitary nodule.

Based on radioisotope study:
- *Hot*—Means autonomous toxic nodule.
- *Warm*—Normally functioning nodule.
- *Cold*—Nonfunctioning nodule; may be malignant (need not be always).

Features

- Single nodule palpable in one or other lobes of the thyroid which is usually smooth and firm.

- Lahey's test does not show any other nodules in posterior part of the gland.
- *Hot or warm in 99m technetium scan but cold in I*^{123} *scan-* commonly they are malignant.
- Thyroid nodule in children and elderly can be malignant.
- Rapid enlargement of thyroid nodule can be malignant.
- Tracheal deviation towards opposite side is common–confirmed by *trail sign*, three-finger test, auscultation and X-ray neck.
- 30% of solitary nodules are cystic.
- 20% of cold nodules are malignant. Cold nodule may be due to malignancy, thyroiditis, thyroid cyst or haemorrhage.
- Commonest site of a nodule is at the junction of isthmus with one of the lateral lobes.



Fig. 6.25: Solitary nodule thyroid, left-sided.



Fig. 6.26: Solitary nodule thyroid.



Figs 6.27A and B: Trachea should be clinically examined to find out whether it is central or deviated. In goiter involving both lobes, it is central. One lateral lobe enlargement usually causes deviation of trachea towards opposite side. Tracheal compression should be checked by Kocher's test. It confirms the scabbard trachea.

Possible features of suspected malignancy in solitary nodule thyroid

- Any nodule can be malignant whether it is hard/firm/cystic/small/large/asymptomatic
- Rapid onset/rapid recent increase in size
- Hoarseness of voice/dysphagia/stridor/dyspnoea
- Fixity of the nodule
- Palpable significant neck nodes

Success consists of a series of little daily efforts.

Investigations

- U/S neck (very useful).
- FNAC.
- T_3, T_4, TSH.
- Radioisotope study. ($I^{123}/I^{131}/^{99m}Tc$).
- CT scan or MRI neck is not done routinely, but only in selected cases. Large swelling/to see vascularity/retrosternal extension are the indications.
- X-ray neck to see tracheal deviation.



Figs 6.28A and B: Ultrasound picture of thyroid. It is often used to see nodules, content-solid/fluid, size and extent.



Fig. 6.29: FNAC of thyroid (*Courtesy by Dr Krishna Upadhya Pathologist, Nandikoor Laboratory, Mangalore*).



Fig. 6.30: Patient earlier operated for nodular goitre. Note recurrent nodule and scar of previous surgery.

Treatment

Indications for surgery in solitary nodule thyroid

- Malignant nodule
- Follicular neoplasm
- Toxic nodule in young
- Nodules with obstruction
- Recurrent cystic nodule
- Complex cyst (both solid and cystic components)
- Cosmetic reason

- If it is a *nontoxic nodule due to any cause, hemithyroidectomy* with complete removal of lateral lobe and whole of the isthmus is done.
- If it is *papillary carcinoma thyroid*, then *near total thyroidectomy* is done along with suppressive dose of L-thyroxine given 0.3 mg OD daily.
- If it is a *toxic nodule, radioiodine therapy*, I^{131} – 5 milli curie is given orally, if the age of the patient is more than 45 years.
- If age is less than 45 years, then initially toxicity has to be controlled by antithyroid drugs, always followed by *surgery—Hemithyroidectomy*.
- If FNAC report says follicular adenoma, then hemithyroidectomy is done. If histology report says follicular carcinoma (capsular and vascular invasion) then completion total thyroidectomy is done. *Completion thyroidectomy* is done usually within 7 days or after 3 weeks. If frozen section biopsy proves carcinoma then total thyroidectomy is done.
- If there is a nodule in the isthmus, isthmectomy is done with excision of part of adjacent lateral lobes.
- If FNAC report says medullary carcinoma of thyroid, then total thyroidectomy with bilateral neck nodal dissection including central compartment is done.

- Colloid nodule may respond for conservative drug treatment using thyroxine orally in 50% cases. If nodule reappears/enlarges progressively and significantly/causing cosmetic problem then hemithyroidectomy is indicated in colloid nodule.

DOMINANT NODULE

It is a palpable nodule in an *enlarged thyroid gland*.

THYROID CYST

- It is thyroid swelling which is cystic in nature eliciting positive fluctuation
- But tensely cystic swelling can be hard (*thyroid paradox*—with cellular tumor of thyroid can be soft also)
- Common cause is colloid degeneration – 50%. There will be absence of epithelial lining
- 30% of solitary nodules are cystic
- 15% cystic swellings in thyroid are malignant
- Cyst formation is common in papillary carcinoma of thyroid
- A cyst if contains both solid and cystic areas is called as complex cyst which is more likely to be malignant
- FNAC may cause regression of simple cyst. Even after three repeated aspirations if recurrence occurs, surgery is needed
- Surgery is indicated in complex cyst and if cyst is more than 4 cm in size

RETROSTERNAL GOITRE

Retrosternal goitre is defined as having > 50% goitre below the suprasternal notch.

- *Primary* is rare—1%. Primary retrosternal goitre arises from ectopic thyroid tissue from mediastinum. It gets its blood supply from mediastinum itself, not from the neck. And also it is not related to the existing thyroid in the neck.
- *Secondary* is common. It is extension from the enlarged thyroid from the neck. Usually arises from the lower pole of a nodular goitre. Commonly seen in short neck or obese individuals. Due to negative intrathoracic pressure, nodule gets drawn into the superior mediastinum.

Types

1. *Substernal type*: Part of the nodule is palpable in the lower neck.
2. *Plunging goitre*: An intrathoracic goitre is occasionally forced into the neck by increased intrathoracic pressure.
3. *Intrathoracic goitre* itself. Neck is normal.



Fig. 6.31: Lower border should be checked to confirm retrosternal extension whether present or not.



Fig. 6.32: Superior vena cava obstruction due to thyroid extending into the retrosternal area. Note the dilated veins over neck, chest wall and arm.

Men take only their needs into consideration, never their abilities.



Figs 6.33A to C: X-ray PA view and lateral view showing retrosternal goitre. Diagrammatic representation of the retrosternal goitre.

Clinical Features

- Dyspnoea at night during lying down or neck extended.
- Cough and *stridor* (stridor is harsh sound on inspiration).
- Dysphagia.
- Engorgement of neck veins and superficial veins on the chest wall.
- Lower border is not seen on inspection and not felt on palpation.
- *Pemberton's sign* is positive. The patient is asked to raise the arm above the shoulder level. Dilated veins are seen over neck and upper part of chest wall. Stridor and rarely dysphagia may occur. (When patient raises the arm above the shoulder level, retrosternal goitre compresses over the easily compressible structures like SVC and trachea causing dilated veins and dyspnoea respectively).
- Dull note over the sternum on percussion.
- Retrosternal goitre can be either nodular, toxic or malignant.
- Rarely recurrent nerve palsy can occur.

Differential Diagnosis

- Mediastinal tumours.

Investigations

- Chest X-ray shows soft tissue shadow under the sternum.
- Radioactive iodine study is diagnostic.
- CT scan is useful.

Treatment

- Surgical removal of retrosternal thyroid is done. Commonly it can be removed through an incision in neck (as blood supply of retrosternal goitre is from neck), but in case of large retrosternal extension or in malignant type median sternotomy is required (rarely).

Note:

- *Radioiodine therapy is not accepted in retrosternal goitre.*
- Stridor due to compression of tracheo-bronchial tree by retrosternal goitre is very dangerous because it is often not possible to clear the airway either by intubation or by tracheostomy.
- Surgical removal should be complete because recurrent retrosternal goitre is very difficult to re-operate.

Breathing difficulties in thyroid swelling

- Retrosternal goitre – positive Pembertone's sign
- Multinodular goitre of long duration – positive Kocher's test – compressive stridor
- Secondary toxic goitre – congestive cardiac failure
- Carcinoma infiltrating the trachea – stridor on rest – without compression with fingers.

THYROTOXICOSIS AND HYPERTHYROIDISM

> ***I have lately seen three cases of violent and long-continued palpitations in females, in each of which the sample peculiarity presented itself—viz., enlargement of the thyroid gland…. A lady, aged twenty, became affected with some symptoms which were supposed to be hysterical…. It was now observed that the eyes assumed a singular appearance, for the eyeballs were apparently enlarged, so that when she slept, or tried to shut her eyes, the lids were incapable of closing.***
>
> **—Robert James Graves,** 1835

It is *symptoms complex due to raised levels of thyroid hormones***.**

Types

1. Diffuse toxic goitre—(Graves' disease, *Basedow's disease*. Primary thyrotoxicosis).
2. Toxic multinodular goitre (Secondary thyrotoxicosis) (*Plummer disease*).
3. Toxic nodule.
4. Hyperthyroidism due to rarer causes:
   a. *Thyrotoxicosis factitia*—drug induced. Due to intake of L-thyroxine more than normal.
   b. *Jod Basedow thyrotoxicosis*—because of large doses of iodides given to a hyperplastic endemic goitre.
   c. *Autoimmune thyroiditis or de Quervain's thyroiditis*.
   d. Occasionally *carcinoma thyroid.*
   e. *Neonatal thyrotoxicosis*. It subsides in 3-4 weeks as TsAb titres fall in the baby's serum.
   f. Struma ovarii.
   g. Drugs like amiodarone – an antiarrhythmic agent.

[*Wolf-Chaikoff effect*—Iodides inhibit the further release of hormone causing hypothyroidism *(Hokkaido goitre).*]

Grave's disease is an autoimmune disease with increased levels of specific antibodies in the blood (TSH receptor antibodies). It is often associated with vitiligo. It is often familial. Thyroid stimulating immunoglobulins (TSI)/thyroid stimulating antibodies (Ts Ab) and long acting thyroid stimulator (LATS) cause pathological changes in the thyroid. Histologically there is acinar cell hypertrophy and hyperplasia with absence of normal colloid in the tall columnar epithelium (normal is flat epithelium with colloid). As cells are empty, they look vacuolated. Tissues are highly vascular. Exophthalmos producing substance (EPS) causes Grave's ophthalmopathy.

Clinical Features

- It is eight times more common in females.
- Occurs in any age group.
- Primary type is seen commonly in younger age group.
- Secondary is common in older age group.
- Grave's disease often presents without any obvious thyroid swelling in the neck. Whenever there is unexplained behavioural problem, insomnia, myopathy, unexplained diarrhoea or loss of weight, tachycardia, Grave's diseases should be suspected and evaluated.

Symptoms of Hyperthyroidism

Gastrointestinal system

- Weight loss in spite of increased appetite.
- Diarrhoea (due to increased activity at ganglionic level).

Cardiovascular system

- Palpitations.
- Shortness of breath at rest or on minimal exertion.
- Angina.
- Cardiac irregularity.
- Cardiac failure in the elderly (CCF).

Neuromuscular system

- Undue fatigue and muscle weakness.
- Tremor.

Skeletal system

- Increase in linear growth in children.

Genitourinary system

- Oligo- or amenorrhoea.
- Occasional urinary frequency.

Integument

- Hair loss.
- Pruritus.
- Palmar erythema.

Hope sees the invisible, feels the intangible and achieves the impossible.



Fig. 6.34: Diffuse toxic goitre (primary) involves both lobes with hyper functioning acini.



Fig. 6.35: Primary thyrotoxicosis. Note the exophthalmos.



Figs 6.36A and B: Note the dilated veins in a vascular enlarged thyroid gland. Auscultation is important to hear a bruit.

Psychiatry

- Irritability.
- Nervousness.
- Insomnia.

Sympathetic overactivity causes dyspnoea, palpitation, tiredness, heat intolerance, sweating, nervousness, increased appetite and decrease in weight. Because of the *increased catabolism* they have increased appetite, decreased weight and so also increased creatinine level which signifies *myopathy* (due to more muscle catabolism).

Fine tremor is due to diffuse irritability of grey matter.

Thrill is felt in the upper pole of the thyroid and also bruit on auscultation. It is because in upper pole, superior thyroid artery enters the gland superficially and so thrill and bruit can easily be felt. In lower pole inferior thyroid artery enters the gland from deeper plane and so thrill cannot be felt.

Signs of Hyperthyroidism

1. *Eye signs in toxic goitre*

Eye signs are common in primary thyrotoxicosis. Lid lag, lid spasm can occur in secondary thyrotoxicosis also.

1. *von Graefe's sign*: (Lid Lag's sign): It is inability of the upper eyelid to keep pace with the eyeball when it looks downwards to follow the examiners finger.
2. *Dalrymple's sign*: Upper eye lid retraction, so visibility of upper sclera.
3. *Stellwag's sign*: Absence of normal blinking—so *starring look.* First sign to appear.
4. *Joffroy's sign*: Absence of wrinkling on forehead when patient looks up (frowns).
5. *Moebius sign*: Lack of convergence of eye ball. Defective convergence is due to lymphocytic infiltration of inferior oblique and rectus muscles in case of primary thyrotoxicosis. There will be diplopia. It may be an early sign of eventual ophthalmoplegia.
6. *Jellinek's sign*: Increased pigmentation of eyelid margins.
7. *Enroth sign*: Oedema of eyelids and conjunctiva.
8. *Rosenbach's sign*: Tremor of closed eyelids.
9. *Gifford's sign*: Difficulty in everting upper eyelid in primary toxic thyroid. Differentiates from exophthalmos of other causes.
10. *Loewi's sign*: Dilatation of pupil with weak adrenaline solution.
11. *Knie's sign*: Unequal pupillary dilatation.
12. *Cowen's sign*: Jerky pupillary contraction to consensual light.
13. *Kocher's sign*: When clinician places his hands on patient's eyes and lifts it higher, patient's upper lid springs up more quickly than eyebrows.
14. *Naffziger's sign*: With patient in sitting position and neck fully extended, protruded eye ball can be visualized when observed from behind.

Order of appearance of signs

1. Stellwag's sign — Mild; first sign to appear
2. von Graefe's sign — Mild
3. Joffroy's sign — Moderate
4. Moebius sign — Severe

WAYNE'S DIAGNOSTIC INDICES (CLINICAL)

Symptoms	*Present*	*Absent*
1. Dyspnoea on effort	+1	
2. Palpitation	+2	
3. Tiredness	+2	
4. Preference to heat		–5
5. Preference to cold (Heat intolerance)	+5	
6. Excessive sweating	+3	
7. Nervousness	+2	
8. Appetite increased	+3	
9. Weight decreased	+3	
Signs	*Present*	*Absent*
1. Bruit over thyroid	+2	
2. Exophthalmos	+2	
3. Lid retraction	+2	
4. Lid lag	+1	
5. Hyperkinetic movements	+4	–2
6. Fine finger tremors	+1	
7. Hands hot	+2	–2
Moist	+1	–1
8. Atrial fibrillation	+4	–3
9. Pulse rate 80/minute	0	
80-90/minute	+3	
More than 90/minute	+3	
10. Palpable thyroid		
< 11 points—nontoxic goitre	11-19 equivocal	> 19 points—toxic

EXOPHTHALMOS

- It is proptosis of the eye, caused by infiltration of the retrobulbar tissues with fluid and round cells, with *lid spasm* of upper eyelid. (Lid spasm is spasm of levator palpebrae superioris muscle which is partly innervated by sympathetic fibers).
- Sclera can be seen clearly below the limbus of the eye.
- Proptosis can be measured by *exophthalmometer.*
- Exophthalmos is often self limiting, but not always. Sleeping in propped up position and lateral tarsorrhaphy will help to protect the eye.

Severe exophthalmos

- Eyelid oedema, chemosis, conjunctival injection.
- Diplopia, ophthalmoplegia (complete weakness of all extraocular muscles and so no movements possible).
- Corneal ulceration.
- Papilloedema soon develops.
- Finally it may also cause loss of vision.


Normal
Upper eyelid between upper limbus and pupil
Lid retraction
Upper eyelid raised lower eyelid normal
Exophthalmos
Both upper and lower eyelids away from the center with visible sclera all around mainly below

Fig. 6.37: Diagram showing normal relation of eyelid and pupil in lid retraction and exophthalmos.

It is called as ***malignant exophthalmos.*** (It is misnomer even though it is not malignant nor related to any malignancy).

One person with passion is greater than ninety-nine who have only an interest.

Differentiating Points between Primary and Secondary Hyperthyroidism

Primary thyrotoxicosis	*Secondary thyrotoxicosis*
1. Symptoms appear first, then thyroid swelling	1. Thyroid swelling appears first
2. Goitre is diffuse, smooth, firm or soft, both lobes are involved with thrill and bruit	2. Swelling is large nodular, obvious
3. Features are much more severe compared to that of secondary toxicosis	3. Symptoms appear after long time, which is less severe and slowly progressive compared to primary toxicosis
4. Eye signs and exophthalmos are common	4. Eye signs are not common
5. As it is an autoimmune disease, there may be hepatosplenomegaly	5. Cardiac features are more common
Histologically, there is hyperplasia of acini, lined by columnar epithelium, often containing vacuolated colloid	



Fig. 6.38: Malignant exophthalmos.

Treatment in emergency, i.e. large doses of systemic steroids (Prednisolone) are given along with *orbital decompression*, systemic antibiotics, steroid drops, antibiotic drops.

Treatment of severe exophthalmos

- Steroids intravenously
- IV antibiotics
- Guanethidine, steroid, antibiotic drops
- Lateral tarsorrhaphy
- Orbital decompression
- Diuretics
- Dark spectacles, protective eye patches
- Eyelid surgeries, extraocular muscle surgeries
- Local radiation therapy

Remember—*Antithyroid drugs may worsen exophthalmos and the patient should be observed once antithyroid drugs are started as steroid supplementation may be required.*

- **Lid retraction** is higher upper eyelid with normal lower eyelid with visible sclera adjacent to upper eyelid
- **Lid lag** is inability of the upper eyelid to keep pace with the eyeball when it looks downwards to follow the examiners finger
- **Exophthalmos** is visible sclera *first below* (lower part) the lower edge of the iris and later eventually upper part of sclera will be visible. It is due to pushing of the eyeball forwards due to fat, oedema fluid, cells like macrophages in retrobulbar space

Important signs to be remembered

- *Visible **lower sclera**- sign of exophthalmos*
- Naffziger's sign
- von Graefe's sign-upper lid lag- contraction / overactivity of the involuntary part of the levator palpebrae superioris muscle – Muller's muscle.
- Joffroy's sign
- Moebius sign- *most important- early sign of ophthalmoplegia*

Thyroid ophthalmopathy in Grave's disease-Werner's abridged classification of ocular changes with van Dyke's modification

Class-grade	*Definition*
0	No signs and symptoms
1	Eye signs only—refer table below for eye signs
2	Soft tissue involvement
3	Proptosis more than 22 mm
4	Extraocular muscle involvement
5	Corneal involvement- ulceration
6	Loss of sight / vision due to optic nerve and corneal involvement

Eye signs only

- Resistance to retro displacement of eye
- Edema of conjunctiva and caruncle
- Lacrimal gland enlargement
- Injection of conjunctiva
- Oedema and fullness of lids

Grading of exophthalmos

- **Mild:** Widening of palpebral fissure due to lid retraction
- **Moderate:** Orbital deposition of fat causing bulging with positive Joffroy's sign.
- **Severe:** Congestion with intraorbital oedema, raised intra-ocular pressure, diplopia and ophthalmoplegia
- **Progressive:** In spite of proper treatment progression of eye signs is seen with chemosis, corneal ulceration and ophthalmoplegia.

Causes of exophthalmos	Causes of pulsating exophthalmos
Endocrinal • Thyrotoxicosis – common • Cushing's syndrome, acromegaly-rare *Congenital deformities of skull* • Craniostenosis, oxycephaly, hypertelorism *Primary tumours* • Periorbital meningioma • Optic nerve glioma • Orbital haemangioma • Lymphoma • Osteoma • Pseudo tumour- granuloma *Secondary tumours* • Antral carcinoma, neuroblastoma *Inflammatory* • Orbital cellulites, frontal sinusitis *Vascular causes* • Cavernous sinus thrombosis/A-V fistula • Ophthalmic artery aneurysm *Other eye causes* • Severe myopia • Severe glaucoma-buphthalmos	• Carotid-cavernous sinus A-V fistula • Cavernous sinus thrombosis • Orbital vascular neoplasm • Orbital haemangioma • Ophthalmic artery aneurysm

2. *Cardiac manifestations*

1. Tachycardia is common.
   As per **Crile's grading**
   Sleeping pulse rate is usually checked for three consecutive nights and average is taken as the value.

Pulse rate
Grade I — < 90/mt
Grade II — 90-110/mt
Grade III— >110/mt

2. Ectopic.
3. Pulsus paradoxus.
4. Wide pulse pressure.
5. Multiple extrasystoles.
6. Paroxysmal atrial tachycardia.
7. Paroxysmal atrial fibrillation.
8. Persistent atrial fibrillation (not responsive to digoxin).

3. *Myopathy*

1. Weakness of proximal muscles occurs, i.e. the front thigh muscles, arm muscles.
2. Weakness is more when muscle contracts isometrically either while getting down steps, or lifting a full bucket.
3. Often when it is severe it resembles myasthenia gravis. Once hyperthyroidism is controlled recovery occurs.

4. *Pretibial myxoedema*

It is a misnomer. *Pretibial myxoedema* is often a feature of primary thyrotoxicosis:

- Is usually bilateral, symmetrical, shiny, red thickened dry, skin, with coarse hair in the feet and ankles.
- In severe cases skin of entire leg below the knee with involvement of foot and ankle can occur.
- It is due to deposition of myxomatous tissues (mucin like deposits) in skin and subcutaneous plane.
- It might or might not regress completely after treatment for toxicity.
- It is associated with exophthalmos with high levels of thyroid stimulating antibodies.
- Skin becomes cyanotic when cold.

5. *Thyroid Acropachy*

Thyroid Acropachy is clubbing of fingers and toes in primary thyrotoxicosis. Hypertrophic pulmonary osteoarthropathy can develop.

> *You don't drown by falling in the water; you drown by staying there.*—Edwin Louis Cole

TOXIC NODULE:

- Is a solitary overactive nodule.
- There is an autonomous hypertrophy and hyperplasia of a part of the gland where there is a nodule. (It is not due to Thyroid stimulating antibody (Ts Ab).)
- Here high levels of circulating thyroid hormones suppress TSH secretion and so, normal thyroid tissue surrounding the nodule is itself suppressed and inactive.
- Once patient becomes euthyroid by drugs, surgery (hemithyroidectomy) or radioactive iodine therapy I^{131} in a therapeutic dose of 5 m curie is given orally.
- Because normal gland is inactive, radioactive iodine affects only the autonomous nodule, allowing the normal gland to remain intact which later gets activated and functions normally.
- Drugs are used initially, only for a temporary period to make the patient euthyroid.
- Before the age of 45, surgery is preferred.
- After 45 years age, radioiodine therapy is used.

INVESTIGATIONS

- Thyroid function tests

Type of disease	T_4	T_3	TSH
Conventional hyperthyroidism	Increased	Increased	Undetectable
T3 hyperthyroidism	→	Increased	Undetectable
Subclinical hyperthyroidism	→	→	Undetectable

Serum T_3 and T_4 levels are very high. TSH is very low or undetectable. Sometimes, only T_3 level is increased and is called as *T_3 toxicosis*. Here in T_3 toxicosis, *free T_3 estimation is important*.

- Radioisotope study by I^{131} (Diagnostic dose -5 microcurie is used) shows more uptake, i.e. *hot nodules* or hot areas. This is very useful in autonomous solitary toxic nodule.
- TRH estimation.
- ECG—To look for cardiac involvement; if required opinion from cardiologists is taken and cardiac problems are managed.
- Total count and neutrophil count are very essential base line investigations before starting antithyroid drugs (as it may cause agranulocytosis).
- Thyroid antibodies estimation.

TREATMENT

1. Antithyroid drugs
2. Surgery
3. Radio-iodine therapy

1. *ANTITHYROID DRUGS:*

Indications for antithyroid drugs:

1. Toxicity in pregnant women—Propylthiouracil is preferred
2. Toxicity in children and young adults
3. Before subtotal thyroidectomy, to make the patient euthyroid
4. Soon after starting radioactive I^{131} therapy for 6 to 12 weeks (Effects of radiotherapy start only in 6 to 12 weeks)

a. Carbimazole:

- Is the commonest drug used.
- Dose is 5-10 mg, exactly 8th hourly, (as T1/2 of carbimazole is 8 hours).
- Usually given for 12-18 months.
- Peak plasma level should be maintained in optimum concentration to have a proper benefit.
- Often tri-iodo-thyronine 20 microgram 4 times daily or Thyroxine 0.1 mg daily are given in combination with antithyroid drugs, to prevent iatrogenic thyroid insufficiency or to prevent the increase in size of goitre.
- It acts by blocking thyroid hormone synthesis. Carbimazole also suppresses the autoimmune process in thyroid in Grave's disease.

b. Methimazole: Alike carbimazole. Dose is 5 to 20 mg daily.

c. Propyl thiouracil:

- It acts by blocking thyroid hormone synthesis as well as by blocking peripheral conversion of T_4 to T_3.
- It also decreases the thyroid autoantibody levels.
- It can be given for hyperthyroidism in children and in pregnancy.
- Dose is 200 mg 8th hourly.

Antithyroid drugs are continued during and after surgery, for 7-10 days. It has to be given after starting radioactive iodine therapy for 6 weeks to 12 weeks.

Response to treatment and possibility of relapse in primary thyrotoxicosis can be assessed by studying HLA status and TsAb level.

d. Propranolol:

- It is a beta blocker, which is used as an antithyroid drug.
- Dose is 40 mg tid.
- It reduces the cardiac problems and also blocks the peripheral conversion of T_4 to T_3, as it is the T_3 which is the principle active agent in periphery.
- Contraindications are bronchial Asthma, heart Block, Cardiac failure.
- Long acting nadolol 160 mg OD can also be used.

e. Lugol's iodine (5% iodine + 10% potassium iodide):

It decreases the vascularity of the gland and makes it more firm and easier to handle during surgery. Dose is 10-30 drops/day (minims) for 10 days prior to surgery. Potassium iodide tablets 60 mg tid also can be given instead of Lugol's iodine. But its use at present is disqualified.

(One minim = one drop. One ml = 16 drops).

f. Block and replacement therapy:

It is giving high dose of carbimazole to inhibit T_3 and T_4 production compeltely with a maintenance dose of 0.1 mg of L thyroxine. It reduces the iatrogenic thyroid insufficiency.

Advantages of antithyroid drugs

1. Avoids surgery and its complications.
2. Avoids radioiodine therapy.

Clinical improvement occurs in 2 weeks. Biochemical improvement occurs in 6 weeks.

Remission is confirmed by TsAb assessment, which will be low.

Disadvantages:

1. Prolonged course of treatment for 18 months, and in spite of this cannot predict the remission or relapse. Relapse rate is 40%. Large gland/severe disease/abnormal TSH receptor antibodies (TSH-RAbs) are likely to lead into high recurrence.
2. Size of swelling may not regress.
3. It may lead to *agranulocytosis and thrombocytopenia*, liver damage, hair loss (except propranolol).

Sore throat is the earliest presentation of agranulocytosis. If it is so, drug is stopped, total count is done. If it is less, agranulocytosis is confirmed. High doses of injection benzyl penicillin 10-20 lac, 6th hourly, IV is started to prevent infection. If required, blood transfusion is done. Patient usually recovers by this. To control toxicity, Tab. Propranolol 40 mg tid is started. Rarely they need bone marrow transplantation.

2. *SURGERY:*

Indications:

1. Failure of drug treatment in primary thyrotoxicosis in young patients
2. Autonomous toxic nodule
3. Nodular toxic goitre
4. When malignancy cannot be ruled out

Surgery done is *subtotal thyroidectomy*—Both lobes with isthmus are removed and a tissue equivalent to pulp of finger is retained at lower pole of the gland on both sides (5-8 grams).

In autonomous nodule, *hemithyroidectomy* is done. Here entire lateral lobe with whole of isthmus is removed.

Advantages: Rapid cure and high cure rate.

Patient should be made euthyroid before doing surgery. (It should be confirmed by repeated estimation of serum T_3, T_4 and TSH levels).

Disadvantages:

1. Recurrent thyrotoxicosis (5%).
2. Thyroid insufficiency (20-45%). It is revealed in 6 months to 2 years and is confirmed by estimating T_3, T_4 and TSH levels. Hypothyroidism is better than recurrent thyrotoxicosis. It is treated by tab. L-thyroxine 0.1 mg daily (OD) for life-long.
3. Complications of thyroid surgery itself.

CHOICE OF THERAPIES

Condition	*Age*	*Treatment*
1. *Diffuse toxic goitre*: a. Small goitre b. Large goitre	Over 45 years	Antithyroid drugs for 18 months Radioiodine therapy
	Under 45 years	Surgery (*Subtotal thyroidectomy*)
2. *Toxic nodular goitre*		Surgery (Subtotal thyroidectomy) Initially antithyroid drugs are given to make the patient euthyroid before surgery
3. *Toxic solitary nodule*	Over 45 years	Radioiodine
	Under 45 years	Surgery: (Hemithyroidectomy)
4. *Recurrent thyrotoxicosis after surgery*	Under 45 years	Antithyroid drugs
	Over 45 years	Radioiodine therapy
5. *Failure of antithyroid drugs or radio iodine therapy*		Surgery

Dissatisfaction and discouragement are not caused by the absence of things but the absence of vision.

3. *RADIOIODINE THERAPY:*

Indications:
1. Primary thyrotoxicosis after 45 years of age
2. In autonomous toxic nodule
3. In recurrent thyrotoxicosis

- Radioiodine destroys the cells and causes the complete ablation of thyroid gland. It is given only after the age of 45 years, as the chances of genetic mutation (damage), leukaemia, carcinomas are high in younger individual.
- *Usual dose is 5 to 10 millicurie, or 160 microcurie/gm of thyroid.*
- It takes 3 months to get full response and so until then, the patient has to take antithyroid drugs. Often additional one or two doses of radioiodine are required to have complete ablation. Eventually they go for hypothyroidism and so require maintenance dose of L-thyroxine 0.1 mg daily.
- To give therapeutic dose, patient should be admitted and isolated for 7 days (Half life) to prevent irradiation. It is given orally soon after getting from the manufacturer without much delay to have optimal efficacy.

Advantages:
1. No surgery.
2. No prolonged drug therapy.

Disadvantages:
1. Availability of facilities.
2. Proper follow-up is essential.

TOXIC THYROID IN PREGNANCY

- *Radioiodine therapy is absolutely contraindicated* in pregnancy (High-risk to foetus).
- Antithyroid drugs can be administered carefully.
- But, the problem here is that both TSH and antithyroid drugs cross the placental barrier and baby born may be hypothyroid and goitrous.
- Propylthiouracil is preferred in pregnancy.
- Subtotal thyroidectomy can be done in second trimester.

TOXIC THYROID IN CHILDREN

Radioiodine therapy is *absolutely contraindicated* in children because of the high-risk of developing thyroid carcinoma. Recurrence rate is also very high after surgery. So proposed treatment is, initially antithyroid drugs are given until adolescent period and then subtotal thyroidectomy is done.

THYROCARDIAC

Severe cardiac damage (partly or wholly) resulting from hyperthyroidism, usually secondary type, requires proper opinion from cardiologists and treatment with propranolol. Subtotal thyroidectomy is the treatment.

IN A PATIENT WITH THYROTOXICOSIS, WITH RECENT ONSET OF PROPTOSIS, early thyroidectomy has to be avoided, because early surgery may precipitate malignant exophthalmous. Here the patient has to be treated initially with antithyroid drugs and if required with steroids, until the proptosis has remained static for six months. Then subtotal thyroidectomy is done.

Since half-life of L-thyroxine is 7 days, propranolol and antithyroid drugs has to be continued for 7 days after thyroidectomy.

T_3 THYROTOXICOSIS should be suspected if the clinical picture is suggestive of toxicosis, but routine tests for thyroid function are within normal range.

RADIOACTIVE IODINE

It is used both as a diagnostic as well as a therapeutic agent.

1. **I^{131}**—*is used for radioactive iodine therapy* (β-rays are used).
2. **I^{123}**—*is used for diagnostic studies* (γ-rays are used).

For diagnostic purpose I^{123} is given orally in empty stomach on previous day *(dose—5 micro curie; $T_{1/2}$ (half life) of I^{123} is 13 hours* and so it is suitable for diagnostic purpose). Patient should not take L-thyroxine for 6 weeks prior to radioisotope study.

Note: If patient is on T_3 (60 µg/day) medication, the drug is stopped 10 days before radioisotope scan.

Injection TRH, if given, radioisotope scan can be done in 24 hours.

Thyroid treats this I^{123} similar to inorganic I^{127}. This I^{123} enters the thyroid from the circulation and gets incorporated into T_3, T_4 and later released into circulation as protein bound iodide (PBI). *Normal value of PBI is 8mg%.*

Using *Gieger Muller's gamma ray counter*, scanning of thyroid gland is done to visualize the gland.

- *Hot* area suggests more uptake,
- *Warm* area suggests normal uptake,
- *Cold* area suggests no uptake.

I^{123} radioisotope can be safely used in children and pregnancy for diagnostic purpose only (5 microcurie) as the dose is low.

Note: Presently I^{131} is also becoming popular as a diagnostic tool. For treating malignancy β-rays are more used than γ-rays.

Indications for diagnostic radioactive iodine study

a. Doubtful toxicity
b. Ectopic thyroid
c. Autonomous toxic nodule
d. After total thyroidectomy, to look for secondaries in follicular carcinoma thyroid
e. Retrosternal thyroid

Radioisotope study is done to look for secondaries by doing whole body scanning (total body scintygraphy). For diagnostic radioactive study Technetium 99 pertechnetate can also be used.

Therapeutic Uses

1. In primary thyrotoxicosis after 45 years.
2. In autonomous toxic nodule after 45 years, it is useful as remaining gland still will function adequately after radiotherapy. (As during radiotherapy radioisotope will not be taken up by this retained normal gland as it is suppressed in the presence of toxic nodule which will function later adequately).
3. In follicular carcinoma of thyroid, after total thyroidectomy, if there are secondaries elsewhere in the body, as in bones or lungs, then radioiodine therapy is given. I^{131} is given as its half-life is 8 days. Patient should be isolated for this period and careful disposal of urine has to be done during this period. It is given orally in a dose of 5 milli curies (160 micro-curie/gm of thyroid).

Radioactive isotopes used in thyroid

Isotopes	*Route of administration*	*Half life*	*Type of rays*
I^{123}	Oral	13 hr	γ rays
I^{125}	Oral	60 days	γ rays
I^{131}	Oral	8 days	β, γ rays
I^{132}	Oral	2.3 hr	
Tc 99 scan*	IV	6 hr	

* Used mainly for malignancy in thyroid itself. It is sensitive, convenient, low radiation exposure, inexpensive, with good images but nonspecific and not used for therapy.

Lithium is also used as isotope for diagnosis in thyroid diseases. Technetium is better to identify non-functioning secondaries.

Note

- High dose of retinoic acid will make I^{131} to concentrate in tumour cells (70 mg/daily for 2 weeks)
- Fertility should be avoided for 1 year after I^{131} therapy
- Avoid contrast CT in thyroid diseases as much as possible because I^{131} study in later period will be difficult
- MRI is ideal when radioiodine therapy is needed

Dose of radioactive iodine

Diagnostic	*Therapeutic*
• For thyroid- 5-50 micro curie • For whole body iodine scan – 5- 10 milli curie in 72 hours	• Residual thyroid ablation - 50 m curie • Bone secondaries from FCT- 100-120 m curie • Lung secondaries from FCT- 180 m curie

THYROID NEOPLASMS

A. ***Benign***
   a. Follicular adenoma – colloid, embryonal, fetal.
   b. Hurthle cell adenoma.

   Colloid adenoma (commonest adenoma).
   Papillary adenoma – Its existence is doubtful. It is invariably low-grade papillary carcinoma.

B. ***Malignant*** *(Dunhill classification).*
   a. *Differentiated.*
      1. Papillary carcinoma (60%).
      2. Follicular carcinoma (17%).
      3. Papillofollicular carcinoma behaves like papillary carcinoma of thyroid.
      4. Hurthle cell carcinoma behaves like follicular carcinoma.

   b. *Undifferentiated.*
      Anaplastic carcinoma (13%).

   c. *Medullary carcinoma* (6%).
   d. *Malignant lymphoma* (4%)
   e. *Secondaries* in thyroid (rare) – From colon, kidney, melanoma.

Annual incidence of thyroid cancers is 3.7 per 1,00,000 population. It is common in females (3:1).

Aetiology of Thyroid Malignancy

1. Radiation either external or radioiodine can cause papillary carcinoma thyroid. There is increased incidence of thyroid carcinoma among children following exposure to ionising radiation after the *Chernobyl nuclear disaster* in Ukraine in 1986.

   Earlier irradiation was practised to head and neck region to treat benign conditions like tonsillitis, adenoids, thymus enlargement, acne vulgaris, haemangiomas during first two decades of life. As a consequence papillary carcinoma of thyroid became common in these individuals. Radiotherapy received in adolescent period for Hodgkin's lymphoma may predispose to papillary carcinoma.
2. Pre-existing multinodular goitre. It turns into follicular carcinoma of thyroid.

Don't spend a dollars' worth of time for ten cents worth of results.

3. Medullary carcinoma thyroid is often familial.
4. Hashimoto's thyroiditis may predispose to NHL/ papillary carcinoma of thyroid.
5. Familial.
6. Elevated TSH is observed in papillary carcinoma of thyroid.

PAPILLARY CARCINOMA

- It is 60% common.
- Common in females and younger age group.



Fig. 6.39: Papillary carcinoma of thyroid with nodal infiltration – diagrammatic representation.

Aetiology

- Radiation either external or radioactive iodine therapy.

TSH levels in the blood of these patients are high and so it is called as *hormone dependent tumour*.

Woolner Classification

Types

i. Occult primary (< 1.5 cm).
ii. Intrathyroidal.
iii. Extrathyroidal.

Micropapillary carcinoma is a tumour, clinically not detectable or less than 1 cm.

Gross

It can be soft, firm, hard, cystic. It can be solitary or multinodular. It contains brownish black fluid.

Microscopy

It shows cystic spaces, papillary projections with *psammoma* bodies, malignant cells with *'Orphan Annie eye'* nuclei (intranuclear cytoplasmic inclusions). *Orphan Annie eye nuclei* are identified in histology (paraffin section of formalin tissue). It is not seen in FNAC. Orphan Annie is strip cartoon character with empty circled eyes.

Spread

- It is a slowly progressive and less aggressive tumour.
- It is commonly multicentric.
- It spreads within the gland through intrathyroidal lymphatics to other lobe, comes out of the capsule and spreads to cervical lymph nodes.
- Usually there is no blood spread. Extrathyroidal disease – invasion into thyroid capsule can cause blood born secondaries occasionally.



Fig. 6.40: Papillary carcinoma thyroid, operated specimen.

Clinical Features

- Soft or hard or firm, solid or cystic, solitary or multinodular thyroid swelling.
- Compression features are uncommon in papillary carcinoma thyroid.
- Often discrete lymph nodes in the neck (40%) are palpable.
- May present with secondaries in neck lymph nodes with occult primary.

Diagnosis

- *FNAC* of thyroid nodule and lymph node.
- Radioisotope scan shows cold nodule.
- TSH level in the blood is higher.



Fig. 6.41: FNAC of thyroid. (*Courtesy by Dr Krishna Upadhya Pathologist, Nandikoor Laboratory, Mangalore*)

- Plain X-ray neck shows fine calcification whereas nodular goitre shows coarse – ring/rim calcification.
- U/S neck or CT scan neck (better) to identify non-palpable nodes in neck.

Treatment

- *Total or near total thyroidectomy*.
- *Suppressive dose* of L-Thyroxine 0.3 mg OD life long. TSH level should be < 0.1 m U/L.
- *MRND (modified radical neck dissection)* type III is required if lymph nodes are involved.
- Occasionally if small lymph nodes are present, '*Berry picking*' may be done (universally not accepted). (Not done now).
- Present concept is extrathyroidal type also responds well to radioactive I^{131} therapy.

Note: If tumour is < 1.0 cm, solitary, low grade, probably unicentric, hemithyroidectomy is done with proper follow up at regular intervals.

Note: Suppressive dose of L-thyroxine can cause osteoporosis and so often needs calcium and Vitamin D supplementation.

Prognosis

Prognosis is good and it is one of the curable malignancies.

AMES scoring

A : Age. Age less than 40 years has got better prognosis
M : Distant metastasis
E : Extent of the primary tumour
S: Size of the tumour. Size less than 4 cm has got better prognosis

AGES scoring

A: Age less than 40 years has got better prognosis
G: Pathologic grade of the tumour
E: Extent of the primary tumour
S: Size of the primary tumour. Size less than 4 cm has got better prognosis

Note:

- Lymph node status does not alter the prognosis of papillary carcinoma of thyroid.
- MACIS scoring system is metastases, age, and completeness of excision, invasion, and size.
- All scoring systems categorise the patients as high risk for death – 40% in 20 years; low risk for death – 1% in 20 years. 80% of patients are in low risk for death. Low death risk is achieved by complete clearance of macroscopic tumour without any possible retaining of the disease during first surgery.
- *Follow-up:* Regular estimation of TSH levels, helps to monitor recurrence.

Psammoma bodies are seen in

- Papillary carcinoma thyroid
- Meningioma
- Serous cystadenoma of ovary

Berry's in thyroid

- Berry ligament
- Berry sign
- Berry picking

***Thyroid paradox**—Cellular tumours are soft, and cystic tumours are firm or hard (tensely cystic). It is observed in papillary carcinoma of thyroid.*

Role of ultrasound (U/S) in thyroid diseases

- To detect number, size, nature of the nodules (cystic /solid/complex) (complex means cystic and solid together- more suspicious of carcinoma). Size upto 2 mm can be detected
- U/S guided FNAC is very useful
- U/S at regular intervals is advisable to observe a small nodule in thyroid
- To detect recurrent nodule
- To find out the invasion/spread/vascularity/status of carotid artery and internal jugular vein
- To find out enlarged lymph nodes in neck

Happiness is always an inside job.

Role of FNAC in thyroid swelling

- Highly sensitive in papillary carcinoma of thyroid and also its nodal spread
- Useful to differentiate between benign and malignant
- Should be done in all thyroid diseases especially when there is a nodule or multiple nodules
- Useful in lymphoma/anaplastic carcinoma/medullary carcinoma thyroid/Hashimotos thyroiditis
- It is not very useful in follicular carcinoma as it is difficult to differentiate it from follicular adenoma as main feature in follicular carcinoma is capsular invasion/vascular invasion which are not made out in FNAC

FOLLICULAR CARCINOMA

- It is 17% common.
- It is common in females.
- It can occur either *de novo* or in a pre-existing multinodular goitre.

Types

a. Noninvasive—Blood spread not common.
b. Invasive—Blood spread common.

Typical features: Capsular invasion and angioinvasion.



Fig. 6.42: Total thyroidectomy specimen—done for carcinoma thyroid.

Spread

- It is a more aggressive tumour.
- It spreads mainly through blood into the bones, lungs, liver.
- Bone secondaries are typically vascular, warm, pulsatile, localised, commonly in *skull*, long bones, ribs.
- It can also spread to lymph nodes in the neck occasionally (10%).



Figs 6.43A and B: Thyroid swelling which is highly vascular and malignant in two different patients (male and female).



Fig. 6.44: Secondaries in the skull in a patient who underwent thyroidectomy earlier for follicular carcinoma thyroid.



Fig. 6.45: Secondaries in the skull from thyroid primary. Note well-localised, warm, pulsatile, vascular tumour with underlying bone erosion. It is common in flat bone like skull/ribs/sternum/scapula. Most common in frontoparietal part of skull.

Clinical Features

1. Swelling in the neck, firm or hard and nodular.
2. Tracheal compression and stridor.
3. Dyspnoea, haemoptysis, chest pain when there are lung secondaries.
4. Recurrent laryngeal nerve involvement causes hoarseness of voice, +ve *'Berry's sign'* signifies advanced malignancy (infiltration into the carotid sheath and so absence of carotid pulsation).
5. Pulsatile secondaries in the skull and long bones.



Fig. 6.46: X-ray skull showing secondaries in the skull.

Investigations

- Most often FNAC is inconclusive, because capsular and angioinvasion, which are the main features in follicular carcinoma, cannot be detected by FNAC.



Fig. 6.47: CT skull showing secondaries from follicular carcinoma thyroid.

- Frozen section biopsy is very useful. In 15% cases frozen section biopsy may be inconclusive or facility for frozen section biopsy may not be available in many places, then initial hemithyroidectomy is done.
- U/S abdomen, chest X-ray, X-ray bones are the other investigations required.
- *Trucut biopsy* gives tissue diagnosis, but danger of haemorrhage and injury to vital structures like trachea, recurrent laryngeal nerve, vessels are likely.



Fig. 6.48: X-ray skull showing secondaries with lytic lesions form follicular carcinoma of thyroid as primary.

Take time to think—It is the source of power.



Fig. 6.49: Follicular carcinoma of thyroid in a male patient. It involved mainly left lobe but it is extensive and spreading to soft tissues adjacent to it.

Treatment

- *Total thyroidectomy is done, along with block dissection* whenever lymph nodes are enlarged.
- Maintenance dose of L-Thyroxine 0.1 mg O.D or T_3 80 μg/day is given lifelong.
- *On table frozen section biopsy* is useful in negative FNAC but doubtful cases. Definitive procedure is undertaken once frozen section report comes on table. But in frozen section biopsy itself, 15% of follicular carcinoma report may be inconclusive or negative which causes difficulty in taking decision. In such occasion hemithyroidectomy is done and once histology report of follicular carcinoma is obtained completion thyroidectomy is done usually immediately within a week. If biopsy report is delayed then completion thyroidectomy is done after 6 weeks.

Follow-up

- It is by radioisotope I^{123} scan done at regular intervals (6 months) to look for secondaries.
- ***Thyroglobulin estimation*** is a good follow-up method to decide for Radioisotope study. Normal value (0.5 – 50 μg/L). TG > 50 μg/L is abnormal. It should be done once in 3 months. Its raise signifies recurrent/metastatic disease.
- U/S neck or MRI neck to identify early relapse. MRI neck is better.

Further treatment:

- If secondaries are detected *therapeutic dose* Ra I^{131} is given orally. L-thyroxin has to be stopped 6 weeks prior to RT, then required dose of Ra I^{131} is given (50-150 m curie.)
- Secondaries in bone are treated by *external radiotherapy.* Internal fixation should be done whenever there is pathological fracture.
- There is *no role* of chemotherapy for follicular carcinoma thyroid.

Hurthle cell carcinoma is a variant of follicular carcinoma of thyroid which contains abundant oxyphill cells. It spreads more commonly to regional lymph nodes than follicular carcinoma of thyroid.

Note:
- Hurthle cell carcinoma does not take up I^{131}
- It secretes thyroglobulin
- It has got poorer prognosis than follicular cell carcinoma
- *99mTc sestamibi scan* is very useful for Hurthle cell carcinoma
- Regional nodes are commonly involved than follicular carcinoma
- Abundant oxyphill cells are specific
- Total thyroidectomy, MRND and TSH suppression is the treatment

ANAPLASTIC CARCINOMA



Fig. 6.50: Carcinoma of thyroid gland. It is anaplastic carcinoma. It carries a poor prognosis.



Fig. 6.51: Anaplastic carcinoma of thyroid with infiltration through the capsule. It commonly encases the carotid artery causing Berry's sign positive.

- It occurs in elderly.
- It is a very aggressive tumour of short duration, presents with a swelling in thyroid region which is rapidly progressive causing—
  i. Stridor and hoarseness of voice due to tracheal obstruction.
  ii. Dysphagia.
  iii. Fixity to the skin.
  iv. *Positive Berry's sign*—involvement of carotid sheath leads to absence of carotid pulsation.



Fig. 6.52: Anaplastic carcinoma of thyroid.



Fig. 6.53: Anaplastic carcinoma thyroid in a female patient.



Fig. 6.54: Anaplastic carcinoma thyroid, an aggressive tumour with poor prognosis.

- Swelling is hard, with involvement of isthmus and lateral lobes.
- FNAC is diagnostic.
- Tracheostomy and isthmectomy has got a role to relieve respiratory obstruction temporarily.
- Treatment is *external radiotherapy*, as usually thyroidectomy is not possible.
- Adriamycin as chemotherapy.
- However prognosis is poor.

Follow up in differentiated thyroid carcinoma

- Proper clinical examination in the neck for residual /nodal disease and for distant spread
- Whole body radioisotope scan after one week of surgery to see residual tumour in the neck or metastases
- Estimation of thyroglobulin at regular intervals is very important
- Follow up whole body radioisotope scan at 3-6 months intervals. Thyroxine should be stopped for 6 weeks. But it is commonly done if thyroglobulin level in the blood is significantly high

TNM staging for thyroid cancer

Tumour

Tx—Primary not assessed
T0—No primary
T1—< 1 cm limited to thyroid
T2—1-4 cm limited to thyroid
T3—> 4 cm limited to thyroid
T4—Any size extending beyond capsule

Nodes

Nx—Nodes cannot be assessed
N0—No regional nodes
N1—Regional nodes present
N1a—Same side neck nodes
N1b—Bilateral, midline, mediastinal nodes

Metastases

Mx—Cannot be assessed
M0—No metastases
M1—Metastases present

Under the age of 45 years only Stage I [any T/N and M0] and II [any T/N and M1]. After the age 45 years, Stage I, II, III and IV. Anaplastic carcinoma is always stage IV (Not commonly used).

Voice can say both: What you have done and what you would not have done also !!

Features of thyroid carcinoma

Any thyroid can be malignant of any size, of any texture- solid / cystic, of any number- single / multiple, in any age group.

Features of infiltration

- Infiltration of strap muscles often with sternomastoid muscle
- Infiltration of laryngotracheal complex causing stridor and often haemoptysis
- Infiltration of recurrent laryngeal nerve causes hoarseness of voice
- Infiltration of oesophagus causes dysphagia/ odynophagia (painful swallowing)
- Infiltration into carotid sheath causing absence of carotid pulsation- *Berry's sign*
- Infiltration of cervical sympathetic chain causing Horner's syndrome
- Rarely infiltration into cranial nerves or brachial plexus can occur

Features of lymph nodal spread

- Discrete neck node involvement can occur commonly in papillary carcinoma of thyroid, often in medullary carcinoma and occasionally in follicular carcinoma. Lymph node is often cystic (20%) and contains brownish – black material in papillary carcinoma
- Central neck (level VI) and mediastinal nodes often gets involved in thyroid malignancy. Primary nodes may be involved but clinically may not be palpable. Superior mediastinal nodes (level VII) can cause compression of SVC, recurrent laryngeal nerve with often dullness on percussion over the sternum. These nodes can get involved without palpable neck nodes
- In the neck commonly palpable nodes are levels – II, III, IV and occasionally level V. Secondary nodes – clinically palpable
- Only palpable neck node may be the presentation without clinically palpable thyroid – occult secondary with primary (papillary) thyroid carcinoma. FNAC of the node concludes the diagnosis
- Central node dissection is the common practice while doing total thyroidectomy in carcinoma thyroid especially in medullary carcinoma of thyroid

Features of blood spread

- Follicular carcinoma commonly spreads through blood to bone, lungs, and liver. Bone secondary is typical. It is well-localised, smooth, soft/hard, warm, nonmobile, vascular and pulsatile. It is common in the skull bone—frontal/parietal bone. It can occur in other bones also
- Lung secondaries present with chest pain, dyspnoea and haemoptysis
- Liver secondaries cause hepatomegaly and jaundice
- Blood spread also can occur in medullary carcinoma of thyroid

MEDULLARY CARCINOMA OF THYROID (MCT)

- It is uncommon (5%) type of thyroid malignancy.
- It arises from the *parafollicular 'C' cells* which is derived from the ultimobronchial body (neural crest). C cells are more in upper pole of the thyroid gland.



Fig. 6.55: Note the parafollicular cells. Cell of origin of medullary carcinoma thyroid

- It contains characteristic *'amyloid stroma'* wherein malignant cells are dispersed. Immunohistochemistry reveals calcitonin in amyloid.
- In these patients blood levels of *calcitonin* both basal as well as that following calcium or pentagastrin stimulation is high, a very useful tumour marker.
- Tumour also secretes 5-H.T. (serotonin), prostaglandin, ACTH and vasoactive intestinal polypeptide (VIP).
- It spreads mainly to lymph nodes (60%).
- It may be associated with MEN II syndrome and pheochromocytoma with hypertension. MCT associated with MEN type II B with phaeochromocytoma (Sipple's disease) is most aggressive.
- There may be mucosal neuromas in lips, oral cavity, tongue, eyelids with marfanoid features.
- MCT is not TSH dependent and does not take up radioactive iodine.

Clinical Features

- Thyroid swelling often with enlargement of neck lymph node.

- Diarrhoea, flushing (30%).
- Hypertension, phaeochromocytomas and mucosal neuromas when associated with MEN II syndrome.
- Sporadic and familial types occur in adulthood whereas cases associated with MEN syndrome II occur in younger age groups.

Types

1. Sporadic. Usualy solitary – 70%.
2. MCT with MEN II syndrome.
3. Familial MCT (20%). Commonly multicentric, autosomal dominant in chromosome no. 10.

Investigations

- FNAC: shows amyloid deposition with dispersed malignant cells and "C" cell hyperplasia.
- Tumour marker: Calcitonin level will be higher. Increased levels of calcitonin after injection of calcium 2 mg/kg or pentagastrin 0.5 µg/kg.
  Note: Calcitonin is undetectable in the serum of normal individuals (< 0.08 ng/L).
- U/S abdomen.
- U/S neck to see neck nodes. CT neck and chest is preferred method to identify neck and mediastinal nodes.
- Urinary VMA, urinary catecholamines, urinary metanephrine, serum calcium, serum parathormone estimation.
- 111 Indium octreotide scanning is useful in detecting medullary carcinoma thyroid (70% sensitivity). It is also useful in postoperative follow up to find out residual/metastatic disease.

Treatment

Surgery is the main therapeutic modality.

- *Total thyroidectomy with central node dissection* (level 6) in all patients even if there are no nodes in the neck. + maintenance dose of L-thyroxin.
- Neck lymph nodes block dissection if lymph nodes are involved (bilateral modified radical dissection of neck nodes should include levels – II, III, IV, V and VI). Later regular U/S neck is done to detect early neck nodes.
- No role of suppressive hormone therapy or radioactive iodine therapy.
- External beam radiotherapy for residual tumour disease.
- Somatostatin/octreotide for diarrhoea.
- Adriamycin is the drug used as chemotherapy with limited results.
- If there is associated phaeochromocytoma it should be treated surgically by adrenalectomy first and later only total thyroidectomy is done.
- *All family members of the patient should be evaluated for serum calcitonin and if it is high they should undergo prophylactic total thyroidectomy* (Can also be assessed by genetic evaluation). If there is positive RET proto-oncogene in MCT with MEN II A and familial MCT types, prophylactic total thyroidectomy is done at the age of ***5 years***. In positive RET proto-oncogene in MCT with MEN II B, prophylactic total thyroidectomy is done at the age of ***one year***.
- MCT with associated parathyroid hyperplasia (30%) in MEN IIA, total thyroidectomy with central nodal dissection with total parathyroidectomy and autotransplantation of half of gland in sternomastoid or non-dominant forearm brachioradialis muscle is done.

Prognosis

- Sporadic MCT and MCT with MEN II are aggressive.
- Familial MCT not associated with MEN II has got better prognosis.

Calcitonin

- It is a polypeptide of 32 amino acids. It is derived from ultimobranchial body. It is secreted from C cells of thyroid (parafollicular cells).
- It lowers the plasma calcium and phosphorus levels. It blocks the PTH induced bone resorption. Calcium from the circulation is shunted into the bone. It increases the excretion of calcium, phosphorus, sodium and potassium. It rapidly lowers the serum calcium.
- Normally it is less than 0.08 ng/L (undetectable).
- It is increased in medullary carcinoma of thyroid. It is very good tumour marker for MCT. It confirms the relapse/metastases/residual disease. Increased levels in family members confirm the genetic relation and such relatives should undergo prophylactic total thyroidectomy.
- Calcitonin level will further increase after injection of calcium 2 mg/kg or pentagastrin 0.5 µg/kg.
- In disease free individual, after therapy for MCT calcitonin level decreases.
- Calcitonin as a therapeutic agent is used in hypercalcaemia, Paget's disease, bone pain of neoplastic diseases, menopausal osteoporosis. Calcitonin (pork), 4 units/kg is given SC or IM three times a week.

> *Only in advanced cases of hypothyroidism there is a substantial loss of hair.*—Richard A J Asher

- Salmon calcitonin SC/IM/nasal spray – 50-400 units can be given three times a week or daily depending on need.

MALIGNANT LYMPHOMA

- It is NHL type. Occurs in a pre-existing Hashimoto's thyroiditis (Not proved well).
- FNAC is useful to diagnose the condition (Often trucut biopsy).
- Chemotherapy is the main treatment.
- Rarely total thyroidectomy is done to enhance the results.

Degroot's staging of carcinoma thyroid*

Stage 1: Malignancy is intrathyroidal
Stage 2: Malignancy is intrathyroidal with mobile lymph nodes
Stage 3: Malignancy is intrathyroidal with fixed lymph nodes
Stage 4: Distant metastasis

*This staging is applicable to all thyroid malignancy but mainly used in follicular carcinoma of thyroid.

Differential diagnosis for carcinoma thyroid

- Multinodular goitre
- Solitary nodule of other causes
- Riedel's thyroiditis

HASHIMOTO'S THYROIDITIS (Struma lymphomatosa)

- Also called as diffuse non-goitrous thyroiditis.
- It is an autoimmune thyroiditis—common in women (15 times more common).
- There is hyperplasia initially, then fibrosis, eventually infiltration with plasma cells and lymphocytic cells.
- Askanazy cells are typical (like Hurthle cells).
- The river struma arises in Bulgaria and flows into Aegean Sea. Struma means goitre. Banks of this river are endemic area for goitre.

Features

- Painful, diffuse, enlargement of usually both lobes of thyroid which is firm, rubbery, tender and smooth (occasionally one lobe is involved).
- Initially they present with toxic features but later, they manifest with features of hypothyroidism.

  Hyperplasia → Hyperthyroid – *Hashitoxicosis*
  → Euthyroid.
  Fibrosis → Hypothyroid.
- There may be hepatosplenomegaly,
- It is often associated with other autoimmune diseases.
- In 85% cases significant rise in the thyroid antibodies (microsomal, thyroglobulin, or colloid antibodies) is observed.
- Often condition may be associated with or may predispose to *malignant lymphoma*. It is at present not well-proved.
- Common in perimenopausal females.
- Occasionally it can predispose to papillary carcinoma of thyroid also.

Investigations

FNAC, T_3, T_4, TSH. Thyroid antibodies assay. Usually ESR is very high (over 90 mm/hour).

Treatment

1. L-thyroxine therapy.
2. Steroid therapy often is helpful.
3. If goitre is large and causing discomfort, then subtotal thyroidectomy is done.

DE-QUERVAIN'S SUBACUTE GRANULOMATOUS THYROIDITIS

It is due to viral aetiology either mumps or coxsackie viruses causing inflammatory response with infiltration of lymphocytes, neutrophils, multinucleated giant cells.

Clinical Features

- Painful diffuse, swelling in thyroid which is tender
- Commonly seen in females.
- Initially there is transient hyperthyroidism with high T_3 and T_4 but poor radioiodine uptake.
- FNAC is done.
- It is usually a self limiting disease.
- Prednisolone 20 mg for 7 days helps.

RIEDEL'S THYROIDITIS (0.5% common)

- A very rare benign entity wherein thyroid tissue is replaced by fibrous tissue which interestingly infiltrates the capsule into surrounding muscles, paratracheal tissues, carotid sheath. (*'Woody Thyroiditis', 'Ligneus Thyroiditis'*).
- It is often associated with retroperitoneal and mediastinal fibrosis and sclerosing cholangitis.
- There is both intrathyroidal as well as extrathyroidal fibrosis.

Clinical Features

- Hard, fixed, swelling with stridor, often Berry's sign may be positive, i.e. absence of carotid pulsation.

Differential Diagnosis

- Anaplastic carcinoma of thyroid.

Investigations

- T_3, T_4 may be low due to hypothyroidism.
- Radioisotope scan will not show any uptake.
- FNAC to rule out carcinoma.

Treatment

Isthmectomy is done to relieve compression on the airway. They require L-thyroxine replacement later, as hypothyroidism is common.

- High dose of steroid often used.
- Thyroidectomy is not necessary.

Causes of dyspnoea/stridor in thyroid diseases

- Carcinoma thyroid infiltrating recurrent laryngeal nerve/trachea
- Large, long standing goitre causing tracheomalacia
- Retrosternal goitre
- Congestive cardiac failure in thyrotoxicosis

Recent rapid increase in thyroid swelling is due to

- Previous MNG undergoing malignant transformation
- Haemorrhage into a nodule
- Anaplastic carcinoma of thyroid

Remember

- *Goitre* is enlargement of the thyroid gland
- *Solitary nodule* is single palpable nodule on clinical examination without palpable rest of the gland
- *Dominant nodule* is single nodule with palpable enlargement of the remaining thyroid gland
- *Thyroid swelling* is confirmed by its *movement with deglutition* due to attachment of enclosed pretracheal fascia to inferior constrictor muscle which is attached to trachea and cricoid cartilage and so moves with deglutition
- *Berry's ligament* is condensed vascularised pretracheal fascia postero-supero-medially. It is important as it is close to recurrent laryngeal nerve
- Any thyroid swelling *can be malignant* unless proved otherwise
- U/S neck, FNAC, estimation of T3, T4, TSH are essential investigations
- CT scan neck is needed in large goitre and fixed or malignant thyroid
- Radioisotope study I^{123} is done only in selected cases like borderline toxicity, ectopic thyroid, retrosternal goitre and after thyroidectomy in follicular carcinoma thyroid to see secondaries during follow up period
- Normal thyroid gland is usually not palpable
- A rare entity called as *black thyroid* shows lipofuscin deposition in thyroid in a patient who is on long standing tetracycline therapy which may interfere with thyroid function

Occasions wherein thyroid swelling may not move upwards with deglutition

- Anaplastic carcinoma thyroid – often
- Carcinoma thyroid with extensive local infiltration into soft tissues, trachea/larynx and posterior muscles
- Intrathoracic retrosternal extension with infiltration/impaction
- Riedel's thyroiditis with encasement of trachea
- Massive thyroid wherein upward movement is difficult to observe and appreciate

THYROID INCIDENTALOMA

Clinically unsuspected and impalpable thyroid swelling which is identified while doing imaging of head and neck for nonthyroid head and neck diseases is called as thyroid incidentaloma. It is usually left alone with yearly review both clinically and sonologically.

THYROIDECTOMY

Types

1. *Hemithyroidectomy*: Along with removal of one lobe, entire isthmus is removed. It is done in benign diseases of only one lobe.
2. *Subtotal thyroidectomy* commonly done in toxic thyroid either primary or secondary and also often for nontoxic multinodular goitre. Here about 8 grams, or a tissue, size of pulp of finger is retained on lower pole, on both sides and rest of the thyroid gland is removed. It is also done in MNG.
3. *Partial thyroidectomy* (By Thomas) is removal of the gland in front of trachea after mobilisation. It is done in nontoxic multinodular goitre. Its role is controversial.
4. *Near total thyroidectomy*: Here both lobes except the lower pole (one or both sides) which is very close to recurrent laryngeal nerve and parathyroid is removed

Everything has its beauty but not everyone sees it.

(To retain blood supply to parathyroids). It is done in case of papillary carcinoma of thyroid.

5. *Total thyroidectomy*: Entire gland is removed. It is done in case of follicular carcinoma of thyroid, medullary carcinoma of thyroid.
6. *Hartley Dunhill operation* is removal of one entire lateral lobe with isthmus and partial/subtotal removal of opposite lateral lobe. It is done in non toxic multinodular goitre.

Preoperative preparation

- Blood grouping and cross matching. Keep the required blood ready
- Indirect laryngoscopy. Patient is asked to tell' E' to check the abduction of vocal cord
- Serum calcium estimation
- T3, T4, TSH
- Thyroid antibodies
- ECG and cardiac fitness especially in toxic goitre

Procedure

Position: Under general anaesthesia patient is put in supine position with neck hyperextended by placing a sand bag under shoulder – with table tilt of 15 degree head up to reduce venous congestion.

Incision: Horizontal crease incision is done, two finger breadth above the sternal notch, from one sternomastoid to the other (Kocher's thyroid incision) (Posterior margin of sternomastoid).

Skin and platysma are incised—upper flap raised upto thyroid cartilage, lower flap up to sternoclavicular joint. Deep fascia is opened vertically in the midline. Strap muscles are retracted or cut in between two Kocher's forceps. Pretracheal fascia is opened to mobilise the thyroid. First, short stout middle thyroid vein is ligated, then superior thyroid pedicle is ligated close to the gland so as to avoid injury to external laryngeal nerve. Inferior thyroid artery is ligated away from the gland so as to avoid injury to recurrent laryngeal nerve. Mobilised gland is removed. Bed is sutured with catgut so as to prevent bleeding. Drain is placed. The wound is closed in layers.

Thyroid steal: In thyrotoxicosis, patient is taken to operation theatre daily for few days before doing surgery, so as to reduce the anxiety of the patient.

MIVAI—Minimally Invasive Video-Assisted Thyroidectomy is becoming popular for small nodules and gland without thyroiditis. But it is costly.



Fig. 6.56: Note the incision for thyroid surgery.



Fig. 6.57: Hemithyroidectomy: Entire one lateral lobe and entire isthmus are removed retaining entire opposite lateral lobe. It is done in solitary nodule/toxic or nontoxic adenoma in one lobe.


Part removed
Part retained
Sternomastoid
Muscle
Pulp of the finger or 4-8 gm thyroid in lower pole both sides

Fig. 6.58: Subtotal thyroidectomy – It is done in toxic/nontoxic multinodular goitre. Most of the gland except lower pole (4-8 gram) on both sides is removed.


(Thyroid tissue in tracheo-oesophageal groove)
Part retained
Part removed
Part of both lateral lobes and entire isthmus
Sternomastoid
Muscle

Fig. 6.59: Partial thyroidectomy– It is done in nontoxic nodular goitre if there is adequate normal gland posteriorly. Tissue in the tracheo oesophageal groove is retained. Isthmus and gland with nodules in front is removed. It is not commonly done now.


Except small tissue in lower
Pole near rec nerve and parathyroids (one or both sides-1 g/1 cm)
(Both sides)
Part removed
Both lateral lobes and isthmus
Rec L nerve
Part retained
Sternomastoid
Parathyroid

Fig. 6.60: Near total thyroidectomy is done in papillary carcinoma of thyroid. Here most of the gland except lower small tissue of 1 gram is retained to safeguard recurrent laryngeal nerve and parathyroid gland. Tissue is retained either in one or both sides.


Part removed
Both lateral –lobes and isthmus
Sternomastoid
Muscle

Fig. 6.61: Total thyroidectomy is done for follicular carcinoma and medullary carcinoma of thyroid.


(One side partial–in tracheo –oesophageal groove)
Part removed
Part retained
Isthmus, one entire lateral lobe and other side-partial / subtotal (4 grams retained)
Sternomastoid

Fig. 6.62: Hartley Dunhill procedure: Here one entire lateral lobe, isthmus, and most part of the opposite lateral lobe except small quantity of tissue in the lower pole/tracheo-oesophageal groove—subtotal/partial/one gram is retained.



Fig. 6.63: Skin flaps raised in thyroidectomy. Thyroid covered with pretracheal fascia is seen.


Thyroidectomy specimen

Fig. 6.64: Total thyroidectomy specimen done for follicular carcinoma of thyroid.

You never get the second chance to make the first impression.

Complications of Thyroidectomy

1. *Haemorrhage:* May be due to slipping of ligatures either of superior thyroid artery or other pedicles or small veins. It causes tachycardia, hypotension, breathlessness and compression over the trachea may cause severe stridor, respiratory obstruction due to tension haematoma under strap muscles. As a first aid, immediate release of sutures including that of deep fascia has to be done and pressure over the trachea is released. Then patient is shifted to operation theatre and under general anaesthesia exploration is done and bleeders are ligated. Blood transfusion may be required.
2. *Respiratory obstruction*: It may be due to haematoma (if it is so, the haematoma has to be evacuated), or due to laryngeal oedema, or due to tracheomalacia or bilateral RLN palsy *(emergency endotracheal intubation* is done along with steroid injections). Often emergency tracheostomy may be required as a life-saving procedure.
3. *Recurrent laryngeal nerve palsy:* It can be transient or permanent. Transient is 3% common. They usually recover in 3 weeks to 3 months. Often they require steroid supplement and speech therapy. Permanent paralysis is rare.


Thyroid cartilage
Thyroid
Trachea
Rec laryngeal nerve

Fig. 6.65: Note the relation of recurrent laryngeal nerve.



Fig. 6.67: Patient under anaesthesia with proper position for thyroidectomy surgery.



Fig. 6.68: Position of neck in thyroid surgery.


1. Head end elevated 15 degrees
2. Sand bag under the shoulder
3. Head rest under the occiput
4. Hands tugged under the buttocks

Fig. 6.66: Position of the patient for thyroid surgery. Head end elevated, sand bag under the shoulder.



Fig. 6.69: Kocher's thyroid incision for thyroidectomy.



Fig. 6.70: Suction drain kept after thyroidectomy.

4. *Hypoparathyroidism* is rare 0.5% common. Mostly it is temporary due to vascular spasm of parathyroid glands, occurs in 2nd-5th postoperative day. Present with weakness, +ve Chvostek's sign, carpopedal spasm, convulsions. Serum calcium estimation is done and then 10 ml of 10% calcium gluconate is given IV 8th hourly. Later supplemented by oral calcium 500 mg 8th hourly. After 3-6 weeks, patient is admitted, drug is stopped and serum calcium level is repeated.

Note: Earliest symptom of hypocalcaemia is muscle weakness.



Fig. 6.71: Note the location of parathyroid glands.

5. **Thyrotoxic crisis (Thyroid storm):** Occurs in a thyrotoxic patient inadequately prepared for thyroidectomy and often a thyrotoxic patient presents in a crisis following an unrelated operation or stress. They present in 12-24 hours with severe dehydration, circulatory collapse, hypotension, hyperpyrexia, and often cardiac failure.

   Treatment is injection hydrocortisone, oral antithyroid drugs, tepid sponging of whole body, beta blocker injection, oral iodides, large amount of IV fluids for rehydration, digitoxin, cardiac monitor, often ventilator support, with close observation. It has got high mortality rate with critical period of 72 hours. Fluid and electrolyte management, cardiac management are the important aspects to be monitored and treated.

Treatment of thyrotoxic crisis

- Injection hydrocortisone high dose—500-1000 mg IV
- Rehydration with adequate IV fluids to control circulatory collapse
- Injection sodium iodide IV – 1 gram
- Injection propranolol – 2 mg
- Oral iodides - Lugol's iodine
- Oral antithyroid drugs
- Tepid sponging
- Digitoxin
- Fluid and electrolyte management
- ICU care, ventilator support and cardiac monitor

6. *Injury to external laryngeal nerve* causes weakness of cricothyroid muscle leading to alteration in pitch of voice.
7. *Hypothyroidism.* Revealed clinically after 6 months.
8. Wound infection, stitch granuloma formation.
9. Keloid formation.

Remember in thyroidectomy

- Middle thyroid vein is present only in 30% of cases
- Bipolar cautery or harmonic scalpel (harmonic wave) are better to control bleeding and to prevent injury to RLN
- RLN should be identified in both sides. Variations should be remembered
- Parathyroids should be retained and also their blood supply
- Parathyroid autotransplantation may be needed if their blood supply is compromised
- Rapid influx of serum calcium into bones in immediate postoperative period may cause severe hypocalcaemia – ***hungry bone syndrome*** which is

Anything the mind of man can conceive and believe, it can achieve.

initially corrected by IV calcium gluconate – 10 ml of 10%. It is more commonly observed in patients with beta blockers. It is due to sudden drop in PTH level after surgery
- Tension haematoma under strap muscles is very dangerous and should be relieved by removing sutures from the skin and strap muscles
- Permanent hypoparathyroidism is rare (0.5-1%) whereas temporary hypoparathyroidism and hypocalcaemia is common (25%) which is corrected well with calcium for certain period of 3-6 months.
- External laryngeal nerve injury is more common than of RLN. There is loss of tension of vocal cords causing reduced power and range in voice (pitch).
- Thyroid insufficiency develops in 25-45% cases. It is confirmed by doing serum T3, T4 and TSH after 6 months.

EMIL THEODOR KOCHER

> ***We have arrived at the point where we generally recommend the radical operation for goitre as the surest and simplest method of treatment…. Surgeons have simply assumed that the thyroid gland has no function whatever…. Patients with total excision…all show more or less severe disturbances in their general condition…. We cannot fail to recognise (the) relation to idiocy and cretinism…. We see no objection for the time being, to the use of the name cachexia strumipriva.***
>
> —**Emil Theodor Kocher**, 1883

He is the first surgeon to get Nobel prize. He did extensive work on thyroid surgeries and designed present technique of thyroid surgeries.

He was from Switzerland. He was the founder of:
- Kocher's vein.
- Kocher's forceps (has got tooth in the tip).
- Kocherisation (Duodenal mobilisation).
- Kocher's incision (Right subcostal for cholecystectomy).
- Kocher's thyroid incision.
- Kocher's test.
- Kocher's method for reduction of shoulder dislocation.

He died in 1917. *He is the father of thyroid surgery.*

Other surgeons who got Nobel prizes are—Alexis Carrell, for his work on vascular anastomosis; Christian Bernard, for heart transplantation, Charles Huggins, urologist, for management of carcinoma prostate.

KOCHER'S TEST

In case of a huge or long-standing thyroid enlargement, both lateral lobes of thyroid are pushed postero-medially with fingers. The test is positive, if it produces **stridor.** This signifies weakened tracheal (rings) cartilage because of constant pressure by the thyroid gland. But then trachea is kept patent by the thyroid itself. Once the gland is removed there is no support to trachea and so it collapses causing stridor (*scabbard trachea*). Such patient *requires temporary tracheostomy for 2-3 weeks*. By then trachea regains its strength back.

HYPOTHYROIDISM

Causes

1. Agenesis or dysgenesis
2. Enzyme deficiency
3. Iodine deficiency
4. Hashimoto's thyroiditis
5. Antithyroid drugs
6. Radioiodine
7. *Drugs:* Lithium, Amiodarone
8. After thyroidectomy

Clinical Features

- *General:* Tiredeness, weight gain, cold intolerance, goitre, hyperlipidaemia.
- *Cardiovascular*: Bradycardia, angina, cardiac failure, pericardial effusion.
- *Haematological*: Anaemia.
- *Dermatological*: Dry skin, vitiligo, Alopecia, erythema.
- *Reproductive:* Infertility, menorrhagia, galactorrhoea.
- *Gastrointestinal*: Constipation, ileus.
- *Developmental*: Growth and mental retardation, delayed puberty.
- *Other features*: Carpal tunnel syndrome, myalgia, hoarseness, deafness, ataxia, depression, psychosis (Myxoedema madness).

Investigations

- T_3, T_4 estimation.
- TSH level estimation which is higher.

Treatment

Replacement with L-thyroxine 100 to 150 μg/day. In old patients with ischaemic heart disease initial therapy is with 25–50 μg/day and then gradually increased upto the required dose.

Myxoedema Coma		
Characteristic features	*Precipitated by*	*Treatment*
Hypothermia	Cold	Drug of choice - T_3, 10 µg given IV
Hypotension	Infection trauma	Levothyroxine - 300 µg IV/1000 µg orally (large dose)
Hyponatraemia		Glucocorticoids
Hypoventilation		Antibiotics
Hypoglycaemia		Slow warming
Bradycardia		Electrolyte management.
Coma		

RECURRENT LARYNGEAL NERVE PALSY

Anatomy and Relations of Nerves with Thyroid Gland

- *External laryngeal nerve* is a branch of superior laryngeal nerve. Vagus gives superior laryngeal nerve branch at inferior ganglion of vagus which is at the level of greater cornu of hyoid bone, which in turn divides into internal laryngeal and external laryngeal nerves. Internal laryngeal nerve pierces the thyrohyoid membrane and gives sensory supply to larynx above the vocal cord and hypopharynx. External laryngeal nerve runs close to superior thyroid vessels to supply cricothyroid muscle which is tensor of vocal cord. It may get injured while ligating superior pedicle causing defective pitch of the voice. So upper pedicle of thyroid should be ligated close to gland.


Sup vagal ganglion
Jugular foramen
Sup L N
Inf vagal ganglion
Int L N
Ext L N
Cricoid
CCA
Vagus
Thyroid
Rt SA
Inf T A
Lt RLN
Rt RLN
L Subclavian artery
A
Trachea
Arch of aorta


Carotid artery
Inferior thyroid artery
– 50%
Thyroid
Rec laryngeal nerve
– 25%
Thyroid
Rec laryngeal nerve
– 20%
Thyroid
Rec laryngeal nerve
– 1.5%
Thyroid
Rec laryngeal nerve
– 0.25%
Thyroid
Vagus
B
Non–recurrent–Rec laryngeal nerve

Figs 6.72A and B: Anatomy of superior and recurrent laryngeal nerve. Superior laryngeal nerve divides into internal and external laryngeal nerves. Right recurrent winds round subclavian artery and left winds around arch of aorta.

- *Recurrent laryngeal nerve* is a branch of vagus which hooks around ligamentum arteriosum with arch of aorta on the left and right subclavian artery on the right side. It runs in the tracheo-oesophageal groove near the posteromedial surface close to thyroid gland. Nerve lies in between branches of inferior thyroid artery. So inferior thyroid artery should be ligated away from the gland. Anomalies of the nerve should be remembered. In 5% of cases nerve passes through the gland. Nerve may be much more away from the

Everyone should be quick to listen and slow to speak.

gland. Nerve may be closely adherent to gland posteriorly. Nerve may lie within the ligament of Berry (25%). Non recurrent laryngeal nerve may be present in 1 in 1,000 cases with a horizontal course. RLN supplies all muscles (abductors, adductors) of the larynx except cricothyroid and also gives sensory supply of larynx below the vocal cords.

Muscles of the Larynx

- Cricothyroid – It is the only muscle which is located on the external aspect of the larynx. It is supplied by external laryngeal nerve. It is tensor and mild adductor of the vocal cord.
- Abductors of the vocal cord – Posterior crico-arytenoids.
- Adductors of the vocal cord – Lateral cricoarytenoids, transverse arytenoid, thyroarytenoids and cricothyroids.
- Relaxant of vocal cords – Thyroarytenoids and vocalis.
- Muscles which close the laryngeal inlet – Oblique arytenoids and aryepiglottic.
- Muscles which open the laryngeal inlet – Thyroepiglotticus.

Positions of Vocal Cord

Median; paramedian (1.5 mm); normal; cadaveric / neutral (3.5 mm); gentle abduction (7 mm); completely abducted (9.5 mm).

Assessment of voice change

- Pitch of the voice – whether raised / lowered or pitch locked
- Breath support during speaking is adequate or not
- Ability to alter the rapidity of speech – slow/fast/medium
- Altered laryngeal and neck muscle tension
- *Indirect laryngoscopy* – with tongue pulled out using gauze, warmed ILS is placed into the oral cavity to see vocal cords. Patient is asked to say 'e' to see the vocal cord movements

Types

1. Unilateral recurrent laryngeal nerve palsy.
2. Bilateral recurrent laryngeal palsy.
3. Unilateral, combined recurrent laryngeal and superior laryngeal nerve palsy.
4. Bilateral, combined recurrent laryngeal and superior laryngeal nerve palsy.

1. *Unilateral recurrent laryngeal nerve palsy*

All intrinsic muscles of the larynx except cricothyroid are paralysed. Vocal cord becomes median or paramedian position.

Reasons are –

a. Only retained cricothyroid is a weak adductor of vocal cord causing median or paramedian position of vocal cords (*Wagner-Grossman hypothesis*).
b. Abductor fibres which are phylogenetically newer (to posterior cricoarytenoid) of the recurrent laryngeal nerve is more susceptible and paralysed than adductor fibres (*Semon's law).*



Fig. 6.73: Vocal cord in recurrent laryngeal nerve palsies

Causes for unilateral recurrent laryngeal nerve paralysis

- Infiltration from carcinoma thyroid
- Infiltration from carcinoma oesophagus
- Infiltration from carcinoma bronchus (left-sided)
- Mediastinal tumours (left-sided)
- Aortic aneurysms
- Trauma
- Idiopathic
- Thyroidectomy
- Neck or mediastinal lymph node mass

Clinical Features

- Asymptomatic in 33% cases.
- Some change in voice, which gradually becomes normal with speech therapy.
- Aspiration never occurs.
- Airway obstruction never occurs.

Treatment

No specific treatment is required.

2. *Bilateral recurrent laryngeal nerve palsy*

Both side intrinsic muscles are paralysed. So both vocal cords lie in median or paramedian position due to unopposed actions of the both side cricothyroid.

Clinical Features

- Change in voice.
- Severe dyspnoea and stridor (more during exertion) leading to airway block and respiratory arrest.

Treatment

- Emergency tracheostomy.
- Lateralisation of the cord by—
  - Arytenoidectomy by open surgery or through an endoscope.
  - Vocal cord lateralisation through endoscope.
- Excision of vocal cord through an endoscope or laser–-cordectomy.
- Implantation of sternohyoid.
- Thyroplasty.

3. *Unilateral, combined recurrent laryngeal nerve and superior laryngeal nerve palsy*

All the muscles on one side are paralysed. Vocal cord is in cadaveric position, 3.5 mm from the midline.

Clinical Features

- Hoarseness of voice.
- Aspiration through ineffective glottis.
- Ineffective cough.

Treatment

- Speech therapy. (Commonly healthy opposite cord moves to opposite side of the midline so as to compensate for the paralysis of the opposite side.)
- Injection of Teflon to the paralysed cord.
- Muscle or cartilage implant to the paralysed cord.
- Arthrodesis of cricoarytenoid joint.

4. *Bilateral, combined recurrent laryngeal nerve and superior laryngeal nerve palsy*

Causes

- All (total) paralysis of intrinsic muscles of larynx
- Total laryngeal anaesthesia

Clinical Features

- Aphonia (no voice).
- Aspiration due to severe glottis incompetence and laryngeal anaesthesia.
- Absence of cough.
- Retention of secretions in the chest.
- Respiratory arrest.

Treatment

- Emergency tracheostomy.
- Fixing epiglottis over the arytenoids to prevent aspiration.
- Plication of vocal cords to prevent aspiration.
- Total laryngectomy.

Unilateral recurrent laryngeal nerve palsy - Not dangerous
Bilateral recurrent laryngeal nerve palsy - Most dangerous
Unilateral combined palsy - Not dangerous
Bilateral combined palsy - Dangerous

Self-assessment Questions

- Discuss thyrotoxicosis.
- Primary thyrotoxicosis.
- Secondary thyrotoxicosis.
- Toxic nodule.
- Solitary nodule.
- Colloid goitre.
- Thyroid function tests.
- Thyroidectomy.
- Complications of thyroidectomy.
- Multinodular goitre.
- Classification of thyroid neoplasms.
- Antithyroid drugs.
- Carbimazole.
- Lingual thyroid.
- Thyroglossal cyst.
- Thyroglossal fistula.
- Kocher's test.
- Papillary carcinoma thyroid.
- Malignant exophthalmos.
- Lateral aberrant thyroid.
- Follicular carcinoma thyroid.
- Anaplastic carcinoma.
- Riedel's thyroiditis.
- Hashimoto's thyroiditis.
- Medullary carcinoma thyroid.
- Recurrent laryngeal nerve palsy.
- Wayne's indices.
- Radioactive iodine.
- Lugol's iodine.
- Retrosternal goitre.
- Theodor Kocher.

The same beam of light can illuminate two objects and produce two different effects.

7

Parathyroids and Adrenals

> ***About three years ago I found on the thyroid gland…a small organ, hardly as big as a hemp seed, which was enclosed in the same connective tissue capsule as the thyroid, but could be distinguished therefrom by a lighter color. A superficial examination revealed an organ of a totally different structure from that of the thyroid, and with a very rich vascularity…. (I) suggest the use of the name Glandulae parathyreoideae; a name in which the characteristic of being bye-glands to the thyroid is expressed.***
>
> **— Ivar Victor Sandström**, 1879

Anatomy
Hyperparathyroidism
MEN syndrome
Tetany
Adrenal cortical tumours
Adrenal cortical carcinoma
Neuroblastoma
Phaeochromocytoma

ANATOMY

- Parathyroids are endocrine glands situated behind the thyroid gland. They are four in number two on each side.
- Two upper glands are constant in position. Superior is behind recurrent laryngeal nerve. They develop from 4th pharyngeal pouch hence called as parathyroid IV.
- Two lower glands are variable in position. They develop from endoderm of 3rd pharyngeal pouch hence called as parathyroid III. It is usually in front of the recurrent laryngeal nerve, lower part.
- Each gland weighs 50 gm. It is brownish (khaki coloured) firm gland, which sinks in the fluid unlike fat which floats. It is usually adjacent to the anastomosis between superior and inferior thyroid arteries posteriorly.

PTH

- Increases absorption of the calcium from the gut
- Mobilizes calcium from the bone
- Increases the calcium reabsorption from the renal tubules



Fig. 7.1: Anatomical location of parathyroids.

- Glands (chief cells) secrete parathormone (PTH) which controls the calcium metabolism.

HYPERPARATHYROIDISM (HPT)

Types

1. Primary.
2. Secondary.
3. Tertiary.

Primary is unstimulated inappropriate high PTH secretion due to hyperplasia or adenoma causing hypercalcaemia.

Secondary is due to chronic renal failure or due to malabsorption, vitamin D deficiency rickets, i.e. due to chronic hypocalcaemia.

Tertiary is due to autonomous reactive hyperplasia of parathyroids often seen like after renal transplantation.

PRIMARY HYPERPARATHYROIDISM

- Adenoma 75-90%
- Hyperplasia 20-24%
- Carcinoma, rare 1%

Carcinoma of parathyroid is rare – 1%. It is aggressive. It presents as nodule, palpable neck lymph nodes along with HPT. Often blood spread can occur. It needs wide tumor excision, hemithyroidectomy, neck node dissection and later radiotherapy to neck and mediastinum. With therapy 5 year survival rate is 85%.

Clinical Features

Clinical vignette of hyperparathyroidism—***"Bones, stones, abdominal groans, and psychic moans."***

1. Hyperparathyroidism is common in middle aged women.
2. Presentation may be *asymptomatic*—> 50% cases.
3. *Nonspecific symptoms and psychiatric symptoms*: They are most often named as neurotics.
4. Behavioural problems.
5. In the bone there will be *osteitis fibrosa cystica* **(*von Recklinghausen disease*)**, which shows single or multiple cysts or pseudotumour in the jaw, skull or middle phalanges.

   Lamina dura of tooth is the first bone to show changes.
6. In the kidney, there may be bilateral, multiple *renal stones* or *nephrocalcinosis* (may go for renal failure).
7. It may be associated with the *peptic ulcer, pancreatitis, MEN I syndrome*.
8. They are more prone for skin necrosis, band keratopathy, pseudogout, myalgia, arthralgia, polyuria, glycosuria, hypertension.

- Primary HPT is commonly sporadic than familial
- Histological difference between adenoma and hyperplasia is difficult to assess
- On table gross look is preferred method
- Adenoma is usually single. Multiple adenomas occur in elderly
- Hyperplasia involves all four parathyroids
- Parathyroid cyst may be developmental/secondary to degeneration of nodule or adenoma. Cyst aspiration shows clear fluid with high PTH level in the content fluid

- Preoperative IV methylene blue 5 mg/kg in 500 ml dextrose saline which stains parathyroids is used often to localise glands
- 50 gram of one gland is sufficient to maintain function
- Persistent HPT is one in which HPT persists immediately even after initial surgery
- Recurrent HPT (initially after first surgery HPT is corrected but recurs 12 months after surgery) is due parathyromatosis, development of new adenoma, and hyperplasia of transplanted parathyroid. *Parathyromatosis* is due to rupture and spillage of parathyroid tissue in neck, mediastinum forming functioning nodules
- Re-exploration and removal in persistent/recurrent HPT needs on table PTH assay. On table PTH level drop more than 50% of preoperative value indicates the success of surgical removal
- CT, MRI, PET scan and selective angiography are usually done only for recurrent diseases

Acute Hyperparathyroidism (Crisis)

Acute hyperparathyroidism is rare but dangerous presentation (crisis) wherein patient presents with abdominal pain, vomiting, dehydration, oliguria , muscular weakness and death.

Serum Ca^{++} is very high > 12 mg% (3.5 mmol/L).

Treatment of crisis:

- Forced diuresis using 3-5 litres of saline with frusemide.
- Rehydration.
- Steroids.
- Clodranate Na^+, Pamidronate (90 mg IV slowly in 4 hours).
- Drugs to reduce Ca^{++} level, i.e. *mithramycin, calcitonin, prednisolone, biphosphonates. Cinacalcet* is calcium receptor agonist which reduces the serum calcium level.

  Condition has high mortality rate.

  Patient develops hyperchloraemic metabolic acidosis.

Investigations

- High serum Ca^{++} — > 10 mg/100 ml.

  Note: Serum albumin should also be assessed to get accurate calcium level.
- Decreased serum phosphorus.
- Increased urinary Ca^{++} — > 250 mg/24 hr.
- Increased serum alkaline phosphatase.
- Increased PTH level in the serum is diagnostic— > 0.5 mg/L.
- X-ray skull shows *salt-pepper appearance*.

Any adrenal tumour more than 50 gm is usually malignant.



Fig. 7.2: Plain X-ray skull. Note the characteristic Salt-pepper appearance of the skull bone.

X-ray features in hyperparathyroidism

- Pepper lesions in the skull
- Sub-periosteal erosion of radial side of middle phalanx
- Calcification in bones

- X-ray phalanges and jaw are specific.
- U/S abdomen to find out problems in kidney, pancreas.
- U/S neck and CT scan neck and mediastinum.
- Selective venous sampling for PTH is also very useful.
- Thallium-Technetium scan shows *hot spots* which is diagnostic of parathyroid adenoma.
- *Technetium-99m labelled Sestamibi isotope* scan is better and sensitive (80%) than Thallium-Tc scan. As it is very expensive it is used in parathyroid re-exploration. It is often combined with single photon emission computerised tomography (SPECT).
- Urinary cAMP level increases in 90% cases.

Differential Diagnosis

- Secondaries in the bone—due to secretion of PTH related polypeptide by tumour. Actual PTH is suppressed.
- Multiple myeloma.
- Vit D intoxication.
- Sarcoidosis.
- Functioning carcinoma.
- *Familial hypocalciuric hypercalcaemia* is an autosomal dominant disease with mild raise in serum calcium and PTH levels secondary to mutation in the cell membrane calcium receptor. Urinary calcium excretion is low. It does not require parathyroidectomy.



Figs 7.3A and B: X-ray of humerus bone and hand bones showing bone features—**brown tumour**—osteitis fibrosa cystica.

Indications for parathyroidectomy

- Severe symptoms
- Young age group
- Markedly reduced bone density
- Serum calcium more than 11 mg%
- Urinary calculi
- Neuromuscular presentations
- Urinary calcium more than 400 mg /24 hours

Problems in parathyroidectomy

- Permanent hypoparathyroidism
- Persistent hyperparathyroidism—5%
- Recurrent hyperparathyroidism—hypercalcaemia recurs 12 months after first parathyroid surgery
- Recurrent laryngeal nerve injury—1%
- Often needs additional thyroidectomy
- Variations in positions of the gland especially lower-may be in mediastinum
- Sudden drop in calcium level after surgery due to increased absorption of calcium by bones—***hungry bone syndrome***

Treatment

- Surgical removal of the glands and implantation of fragments of the gland in forearm muscle mass (brachioradialis) or neck (sternomastoid). Marker

stitch is placed at the transplantation site. 1/3rd of one gland or 100 mg of parathyroid gland is autotransplanted—subtotal parathyroidectomy.
- If it is carcinoma, additional hemithyroidectomy with postoperative radiotherapy is required.
- Adenoma when occurs in one gland with normal other glands, removal of that gland with adenoma may be sufficient.
- When all four glands are diseased, transcervical thymectomy is also added along with total parathyroidectomy to reduce persistent and recurrent disease.
- In familial and MEN syndromes, total parathyroidectomy is better.
- If it is mediastinal parathyroid adenoma, after proper localization thoracoscopic removal may be sufficient.
- *Medical treatment of primary hyperparathyroidism* is usually ineffective and not popular. However occasionally as initial therapy and acute crisis it is being advocated. Estrogens, progestogens, raloxifene (estrogen receptor modulator), mithramycin, calicitonin are the few drugs used. Mithramycin is used once a week but it is hepatotoxic and causes thrombocytopenia.

MEN SYNDROME (MEA SYNDROME)

- Commonly inherited as an *autosomal dominant*.
- Cells involved has got common features of *APUD cells (APUDomas*).

Note: APUD—**A**mine **P**recursor **U**ptake **D**ecarboxylation.

Types

- ***Type—I*:** Parathyroid hyperplasia or adenomas; pituitary tumour; pancreatic tumour [Endocrine—Insulinoma, gastrinoma, glucagonoma, vipoma]. It is also called as *Werner's syndrome*. Here the defect is in chromosome 11.
- ***Type—II***: Also called as *Sipple's disease.*
  1. II a includes medullary carcinoma of thyroid+ phaeochromocytoma + parathyroid hyperplasia (50%). Here the defect is in chromosome 10.
  2. II b includes medullary carcinoma of thyroid + phaeochromocytoma mucosal neuromas in lips and eyelids with bumpy-lumpy lesions, with marfanoid face, megacolon.

TETANY

Decreased level of calcium in blood causing its effects.

Causes

- After thyroidectomy (It is decreased level of parathormone in the blood causing hypocalcaemia). It is usually temporary, lasts for 4-6 weeks. It is the commonest cause of hypoparathyroidism.
- Other causes of hypoparathyroidism are neck dissection, haemochromatosis, Wilson's disease, DiGeorge's syndrome.
- Severe vomiting, hyperventilation associated with respiratory alkalosis.
- Metabolic alkalosis.
- Rickets, osteomalacia.
- Chronic renal failure.
- Acute pancreatitis.

Decreased PTH causes decrease in calcium level in the blood leading to:
- *Circumoral paraesthesia*, paraesthesia of neck, fingers and toes.
- Twitching and weakness of tongue muscles, muscles of forearm, hand, foot and digits—*carpopedal spasm.*
- *Chvostek's sign*—Tapping above the angle of the jaw to stimulate branches of facial nerve causes the twitching of the angle of mouth and eyelids.
- Applying the sphygmomanometer to the arm and inflating the pressure more than systolic pressure of the patient for three minutes can demonstrate carpal spasm *(Trousseau's sign).*
- *Stridor* and difficulty in breathing due to paralysis of respiratory muscles.
- Generalized weakness and twitching all over the body in severe cases mimicking *convulsions.*
- Prolonged QT interval and QRS complex in ECG.

Management

- Serum calcium estimation is done. It will be less than 7 mg%.
- IV calcium gluconate 10% 10 ml sixth to eighth hourly is given.
- Later oral calcium (1 gram three times daily) with vitamin D supplementation (1-3 μ g daily).
- Follow up at regular intervals by doing serum calcium level.
- Magnesium sulphate supportive therapy is also often needed – 10 ml 10% magnesium sulphate intravenously.

> *The fact which Addison has published seem to lead to the conclusion that these little organ are essential to life.*
> —Charles Edward Brown-Sequard

DiGeorge's syndrome

- Absence parathroids
- Thymic aplasia with immunodeficiency
- Cardiac defects

ADRENALS

> ***The facts which Addison has published seem to lead to the conclusion that these little organs are essential to life.***
> **—Charles Edouard Brown-Séquard**, 1856

Adrenal cortex contains three layers:

1. Zona glomerulosa secretes mineralocorticoids.
2. Zona fasciculata secretes glucocorticoids.
3. Zona reticularis secretes sex hormones.



Fig. 7.4: Anatomy of adrenal gland

ADRENAL CORTICAL TUMOURS

- Are usually adenomas.
- Any tumour measuring 6 cm or more are likely to be malignant, or have high risk of turning into malignancy. So requires surgical resection.
- *Adenocarcinoma* is the commonest adrenal cortical malignancy (1%). It is very aggressive tumour.
- Cortical tumours may be functioning or nonfunctioning.
- Functioning tumours secrete mineralocorticoids, glucocorticoids or sex hormones or combinations of these.

Investigations

- U/S abdomen.
- CT scan.
- Hormone evaluation.

Treatment

Adrenalectomy.

Incidentalomas (3-5%)

- Incidentalomas are adrenal tumours incidentally identified either through U/S; CT scan; MRI; or any other methods done for other reasons.
- When incidentalomas are identified a proper biochemical work up for hormones is essential. Overnight dexamethasone suppression test; 24 hour urinary cortisol excretion assay; 24 hour urinary excretion of catecholamines; serum potassium, renin and aldosterone analysis are done in these patients. MRI in suspected malignancy is better.
- If secondaries are suspected adrenal mass biopsy is done. Otherwise it should not be done. Non functioning adenomas (commonest – 78%), Cushing's adenoma, adrenocortical carcinoma, phaeochromocytoma, secondaries, Conn's adenoma are different causes of adrenal incidentalomas. Adenoma with Cushing's syndrome is better than adenoma with Conn's syndrome. Tumour with adrenogenital syndrome is commonly malignant.
- Non functioning adrenal tumour more than 4 cm should be operated. Smaller tumors that increase in size over specified period should be removed. All functioning tumours should be operated.
- Non functioning tumour less than 4 cm should be followed up at regular intervals by hormone tests and CT/MRI.

ADRENO CORTICAL CARCINOMA

- It is a rare malignancy with 1 case in 1000000 population. It is common in females with bimodal presentation.
- Features are – tumour size; necrosis; haemorrhage; capsular invasion; vascular invasion. Immunohistochemistry is specific.
- Presentations are – abdominal pain; back pain; Cushing's syndrome (60%); hyperaldosteronism; virilization.
- Diagnosis is by – hormone evaluation, CT/MRI; MR angiography to identify IVC tumour thrombus.
- Secondaries occur commonly in lungs. So HRCT of lungs is done usually.
- *Mc Falane staging* – Stage I – Tumour < 5 cm; Stage II – Tumour > 5 cm; Stage III – Tumour with local invasion; Stage IV – distant spread. In stage I and II, 5 year survival is 25%; in stage III and IV, 5 year survival is 5%.
- Treatment is en block adrenalectomy; removal of tumour thrombus from vena cava if present; chemotherapy using mitotane – Op-DDD (choice) with cis platin, etoposide and doxorubicin. Adjuvant radiotherapy may be used to prevent recurrence.

- Laparoscopic adrenalectomy is not advisable in adrenocortical carcinoma.

Secondaries in adrenal gland

- Common entity
- Commonly from breast, lungs, kidney, melanoma
- 1/3rd of above primaries show secondaries in adrenal gland
- Commonly bilateral
- In unilateral secondaries adrenalectomy can be done
- Bilateral secondaries are treated by chemotherapy depending on type of primary

Approches for adrenals (surgical)

1. Posterior lumbotomy
2. Anterior transabdominal
3. Abdominothoracic
4. Laparoscopic
5. Retroperitoneoscopic

NEUROBLASTOMA

- Commonest childhood tumour.
- It is a tumour of adrenal medulla.
- An aggressive malignant tumour in childhood usually below the age of 5 years.
- Incidence is equal in both sexes.



Fig. 7.5: Left-sided adrenal neuroblastoma with secondaries in orbit. Note scar of left sided adrenalectomy.

- A reddish-grey tumour gets invaded early into kidney, pancreas and adjacent tissues. Can also cause distant spread to liver, bones (skull), orbit.

It can occur anywhere in sympathetic chain but common in adrenal gland (40%).

Types

1. *Pepper type is right side* adrenal neuroblastoma with *liver secondaries.* Common in infants.
2. *Hutchinson's type is left side* adrenal neuroblastoma with *secondaries in orbit and skull.* Common in late childhood.

Secondaries in the skull mimics spicular osteogenic sarcomas.

Risk Groups

- Low risk groups – Stage I disease; Stage II disease with single N myc value; Stage II with favourable Shimada histology.
- Intermediate risk groups – Stage III without N myc amplification; Stage III with favourable Shimada's histology.
- High risk groups – All patients with N myc amplification; stage IV neuroblastoma.

Pathology

- *Gross*—Tumour with vascularity, necrosis, haemorrhage and often calcifications.
- *Histologically* it contains uniform round cells with hyperchromatic speckled nucleus with Homer – Wright rosettes with central fibrillar core. PAS stain is negative and NSE stain is positive. Often histochemistry is needed to differentiate from other tumours.
- *Shimada's histological classification –*
  - Stroma rich tumour – Presence of Schwannian spindle cell stroma.
  - Stroma poor tumour – Absence of Schwannian spindle cell stroma.

Clinical Features

- Child presents as a huge mass per abdomen, in the loin which is non-mobile. Not moving with respiration. Knobby (nodular) surface, crosses the midline
- ***Dancing eye syndrome and opsomyoclonus***
- *Racoon's eye sign* is infraorbital ecchymosis due to secondaries in retroorbital region.

Great man is the one who treats the little in a great way.



Figs 7.6A and B: Figure shows typical secondaries in skull and orbit with primary in adrenal gland. Such patients carry poor prognosis. *Racoon's eye sign* is infraorbital ecchymosis due to secondaries in retroorbital region. Dancing eye syndrome and opsomyoclonus are other eye features. CT picture of the same patient shows obvious secondaries.

- Hypertension, fever, weight loss, anaemia, flushing (due to catecholamine release) and sweating.
- Diarrhoea, hypokalaemia due to release of Vasoactive Intestinal Polypeptide (VIP). Other hormones like ACTH are also released.

Staging of neuroblastoma

Stage I - Localised tumour with gross complete excision. Same side representative nodes are negative on microscopy

Stage II A – Localised tumour with incomplete gross excision. Same side representative nodes are negative on microscopy

Stage II B - Localised tumour with or without complete gross excision. Same side nonadherent representative nodes are positive but contralateral nodes are (may be enlarged) negative on microscopy

Stage III – Unresectable unilateral tumour infiltrating across midline/localised tumour with opposite side node spread/bilateral nodal spread/midline tumour with bilateral infiltration

Stage IV – Any primary tumour with spread to distant nodes, bone, bone marrow, liver, skin and other organs

Stage IV S – Localised primary tumour (stage I, IIA, IIB) with spread to skin, liver or bone marrow – limited to infants younger than one year

Differential Diagnosis

Wilm's tumour, which is mobile, with smooth surface, moves with respiration, does not cross the midline.

Diagnosis

- U/S, CT to assess the mass and secondaries in liver. MRI is better than CT.
- Plain X-ray abdomen shows stippled calcification.
- Urinary VMA and Homovanillic acid (HVA) estimation in 90% cases.
- MIBG scan.
- Bone marrow biopsy may be positive in 60% cases.

Treatment

- Adrenalectomy (Complete surgical excision).
- In inoperable cases debulking is beneficial.
- Post surgical radiotherapy and folic acid supplements are useful.
- Chemotherapy is useful adjuvant. Drugs used are carboplatin, doxorubicin, cyclophosphamide and etoposide.
- Rarely spontaneous regression of tumour is known to occur.
- Low risk groups are treated by surgery. Intermediate risk groups are treated by surgery and multidrug chemotherapy. High risk groups are treated by high dose multidrug chemotherapy and later surgery.

Prognosis

- It depends on staging of the neuroblastoma – 1, 2A, 2B, 3, 4, 4S.
- Low risk has got 3 years survival – 90%; intermediate risk – 70% and high risk group has got 30%.
- Factors are – age of the child; stage of the disease; Shimada's histology; N myc amplification status (more means high risk); DNA ploidy; neurotrophin receptor Trk A (increased favourable); neutrophin receptor Trk B (increased unfavourable).

PHAEOCHROMOCYTOMA

- It is a tumour arising from chromaffin cells, commonly from the adrenal medulla but occasionally can arise from extraadrenal chromaffin tissues (Organ of Zuckerkandl).
- It is a soft, brownish grey pink tumour, mainly *secretes noradrenaline* or other catecholamines.
- It may also secrete calcitonin, ACTH, VIP (vasoactive intestinal polypeptide), PTH related polypeptide.
- Prevalence of phaeochromocytoma is 0.05%. In patients with hypertension it is up to 0.6%. 4% of incidentalomas are phaeochromocytoma.
- Often it is difficult to differentiate between benign and malignant types. Necrosis, haemorrhage, high ki – 67 positive cells, size of the tumour, increased phaeochromocytoma of adrenal gland scale score

(PASS), capsular invasion and vascular invasion, nuclear DNA ploidy and increased neuron specific enolase (NSE) level are possible features of malignant phaeochromocytoma.

- Commonly benign (90%).

- *Tumour is*
    - *10% malignant*
    - *10% extraadrenal*
    - *10% bilateral*
    - *10% familial*
    - *10% childhood*
    - *10% multiple*
    - *10% not associated with hypertension*
    - *10% calcified*

Clinical Features

- Commonest presentation is severe *headache.*
- Palpitation, dyspnoea, weakness, pallor, blurred vision and other symptoms of sympathetic overactivity.
- They may present as persistent or paroxysmal hypertension (90%).
- As an abdominal mass which is nonmobile, smooth, does not move with respiration, crossing the midline, palpitation may cause fluctuation in BP.
- It may precipitate hypertensive encephalopathy, cardiac arrhythmias or cerebral haemorrhage.
- It may be associated with ***MEN -IIa*** or ***MEN - IIb*** syndromes which includes medullary carcinoma of thyroid and mucosal neuromas.
- It may be associated with familial multiple neurofibromatosis with cafe au lait spots in the skin ***(von Recklinghausen disease***). Or with ***von-Hippel-Lindau syndrome*** (cystic lesion of pancreas, non-functioning islet cell tumour, phaeochromocytoma), RCC, CNS and Retinal haemangioblastoma.
- *Familial paraganglioma syndrome* may be an association with carotid body and extraadrenal paraganglioma.

Differential diagnosis

- Hyperthyroidism
- Anxiety status
- Cardiac conditions
- Carcinoids (functioning)

Investigations

- *VMA excretion* in urine in 24 hours will be >7 mg/24 hrs in phaeochromocytoma.
- IVU.
- U/S abdomen.
- CT scan.
- MRI is preferred to CT as contrast used for CT scan can precipitate paroxysms.
- *Urinary normetadrenaline* or other catecholamines estimation.
- Arteriography.
- Iodine labelled metaiodobenzylguanidine *(I, MIBG*). MIBG is useful to find out extraadrenal involvement —SPECT scan is very useful. I^{131} MIBG scan is safe, noninvasive with 100% sensitivity and 95% specificity.
- Assessment of plasma free metanephrine and normetanephrine level is highly sensitive.

Treatment

Adrenalectomy

- Before surgery, BP is controlled initially by α-blocking agent, phenoxybenzamine or doxazosin; then by β-blocking agent, propranolol. Then during surgery, sodium nitroprusside IV infusion is used.
- Careful anaesthetic management with a good postoperative care is very essential. In case of bilateral presentation opposite side can be operated in later period.

Specimen should be sent for *bichromate staining which stains the specimen brown.*

Remember

- Phaeochromocytoma is rarely malignant in MEN II
- Phaeochromocytoma under 40 years of age suspect MEN 2A, VHL
- Beta-blocker is given only after patient is fully alpha blocked with phenoxybenzamine or doxazocin
- Alpha-blocker is given 4 weeks prior to surgery to control hypetension and beta-blocker is given one week before surgery to control tachycardia and arrhythmias
- Tumours, those secrete dopamine exclusively has got high malignant chances
- 5-year survival for malignant phaechromocytoma is 50%. It needs additional chemotherapy using vincristine, dacarbazine and cyclophosphamide.
- Phaeochromocytoma in pregnancy has got 50% maternal mortality
- Vaginal delivery is contraindicated in pregnancy with phaeochromocytoma

Laughter is the music of the soul.

- Adrenal vein should be ligated first
- Avoid breach in the capsule of tumour during surgery
- Careful handling and haemodynamic monitoring is a must
- Sodium nitroprusside may be required on table to control the hypertension—10 µg/kg/minute

Malignant phaeochromocytoma is 10% common. It is more common in extraadrenal site. It commonly spreads to lymph nodes, bone and liver. Adrenalectomy in early tumour and debulking in advanced cases with α blockers, mitotane and I^{131}MIBG therapy and combination chemotherapy are the therapeutic choices. Overall prognosis is not good with 5 year survival being < 50%.

Self-assessment Questions

1. Hyperparathyroidism.
2. MEN syndrome.
3. Neuroblastoma.
4. Phaeochromocytoma.
5. Incidentalomas.

8

Breast

Anatomy
Mammography
ANDI
Fibroadenoma
Fibrocystadenosis
Sclerosing adenosis
Phylloides tumour
Traumatic fat necrosis
Galactocele
Mastitis
Antibioma
Duct ectasia
Mondor's disease
Tuberculosis of breast
Mastalgia
Galactorrhoea
Gynaecomastia
Duct papilloma
Carcinoma breast
Carcinoma of male breast
Breast reconstruction
Mammary fistulas of ATKINS
Nipple retraction

ANATOMY

Breast is a modified sweat gland derived from ectoderm, as branching epithelial cords which form lactiferous ducts. About 15-20 lobes develop during puberty, each of which drains into a single lactiferous duct. True secretory alveoli develop during pregnancy and lactation under the influence of oestrogen, progesterone and prolactin.



Fig. 8.1: Secretory apparatus of the breast.

Secretory Apparatus of Breast

The breast is composed of acini which make up lobules, aggregation of which form the lobes of the gland. The lobes are arranged in a radiating fashion like the spoke of a wheel and converge on the nipple, each lobe is drained by a lactiferous duct.

Different portions of the duct system are associated with different diseases.

1. Larger ducts are sites of *duct papilloma and duct ectasia*.
2. The distal smaller ducts are the sites of *fibroadenoma* during development of the breast; and *cyst formation and sclerosing adenosis* during the involution period.

- *Estrogen* – ductal proliferation
- *Progesterone* – glandular proliferation
- *Prolactin* – milk secretion

Topography

Vertically It extends from the second to the sixth rib in the mid-clavicular line and lies over pectoralis major, serratus anterior and external oblique muscles.

Horizontally from the side of sternum to the mid-axillary line.

2/3 of the breast rests upon pectoralis major.
1/3 rest upon serratus anterior.

God made you an original; not a copy.

At its lower medial quadrant the gland rests on the external oblique aponeurosis, which separates it from the rectus abdominis.

Axillary Tail of Spence

This is a prolongation from the outer part of the gland which passes up to the level of the 3rd rib in the axilla through a defect in the deep fascia (*Foramen of Langer*) where it is in direct contact with the main lymph node of the breasts (anterior axillary nodes).



Fig. 8.2: Axillary tail of Spence.



Fig. 8.3: Hypertrophy of the axillary tail.



Fig. 8.4: Accessory nipple.



Fig. 8.5: Accessory nipple is not an uncommon condition. Often it can be bilateral.



Fig. 8.6: Pedunculated lipoma over the breast.

This process of the breast gets into axilla through an opening in the deep fascia, known as *foramen of Langer*. When it enlarges it is ofen mistaken for a lipoma. Axillary tail of Spence is deep to deep fascia.

Ligament of Cooper

The breast is anchored to the overlying skin and to the underlying pectoral fascia by bands of connective tissue called *ligament of Cooper*.

1. In cancer, the malignant cells may invade these ligaments and consequent contraction of these strands may cause dimpling of the skin or attachment of the growth to the skin, which in turn cannot be pinched off from the lump.
2. If the cancer grows along the ligament of Cooper binding the breast to the pectoral fascia, the breast gets fixed to the pectoralis major. It then cannot be moved along the long axis of the muscle.

Polands syndrome

- Absence of breast—Amazia
- Absence of sternal portion of pectoralis major
- Common in males



Fig. 8.7: Anatomy of the breast.

Blood Supply to the Breast

- The lateral thoracic artery, from the 2nd part of the axillary artery.
- The perforating cutaneous branches of internal mammary artery to the 2nd, 3rd and 4th intercostal spaces.
- The lateral branch of the 2nd, 3rd and 4th intercostal arteries.
- Pectoral branches of acromiothoracic artery.

Venous Drainage

- The superficial veins from the breast characterised by their proximity to the skin drain to the axillary, internal mammary, and intercostal vessels.
- Phlebitis of one of these superficial veins feel like a cord immediately beneath the skin—***'Mondor's disease'.***
- Through posterior intercostal veins, venous drainage communicates with paravertebral venous plexus. So secondaries in vertebrae, is common in carcinoma of breast.

Lymphatic Drainage of the Breast

Commonly into the axillary lymph nodes.

1. Anterior group (pectoral) — along lateral thoracic vessels. Main drainage node.
2. Medial group (central) — next common node.
3. Posterior group (subscapular) — rare to involve in carcinoma.
4. Lateral group — along axillary vein; rare to involve in carcinoma.
5. Interpectoral node *(Rotter's node)*—signifies the retrograde spread of tumour. It lies between pectoralis major and minor.
6. Apical.



Fig. 8.8: Surgical levels of lymph nodes in the axilla draining the breast.

Later they drain into supraclavicular lymph nodes. 25% drains mainly from medial half of the breast into 2nd, 3rd and 4th intercostal space internal mammary lymph nodes.

Drainage into contralateral axilla and opposite lymph nodes also occur.

The concept of Sappey's subareolar drainage of lymph centripetally is not well accepted now.

Levels of the axillary nodes

Level I : Below and lateral to the pectoralis minor muscle—anterior, lateral, posterior

Level II : Behind the pectoralis minor muscle—central

Level III: Above and medial to pectoralis minor muscle— apical

Note in carcinoma breast

- Spread restricted to level I nodes carries better prognosis
- Spread to level II has poor prognosis
- Spread to level III indicates worst prognosis

MAMMOGRAPHY

It is a plain X-ray of soft tissue of breast using low voltage and high ampearage X-rays. Two films are taken.

1. *Craniocaudal* from above downward.
2. *Mediolateral* from side to side.

Dose of radiation is 0.1 Gy, a low dose. So it is a safe and effective procedure.

Its what you learn after you know it all that counts. — John Wooden

Findings

- Microcalcifications signify malignancy.
- Soft tissue shadow may be smooth and regular in benign conditions or irregular in carcinomas.
- Size and location of mass lesion.
- Spiculations, duct distortion.



Fig. 8.9: Different mammography pictures showing mass lesion, microcalcification, craniocaudal and mediolateral pictures *(By Dr Ganesh, MDRD, Mangalore).*

Grading in mammography

Grade I — Negative
Grade II — Benign lesion
Grade III — Probably benign lesion
Grade IV — Suspicious of breast carcinoma
Grade V — Highly suggestive of carcinoma
Grade VI — Known carcinoma

Indications

- For screening purpose it is done after 40 years. Early screening is indicated when there is family history of carcinoma breast or histological risk factor. Mammography before 35 years of age is usually not done unless there is a suspicious lump or a strong family history.
- In obese patients.
- Whenever conservative breast surgeries are planned.
- To find out spread or de novo tumour in the opposite breast.
- Mammography guided biopsy can be done.
- Evaluation and follow up in benign breast disease with malignant potential.
- Follow up mammography after conservative breast surgery (of operated side and opposite side when needed.
- Mastalgias.

***Note*:**

- 5% of breast cancers are missed in total mammograhic screening.
- Breast Imaging Reporting and Data System (BI-RADS) have got its own categories, assessment (0-6) and recommendations.
- Digital mammography is computerised electronic image of the breast with enhanced magnified pictures.
- Digital spot-view mammography allows faster and more accurate stereotactic biopsy.
- The condition when lump is clinically not palpable but mammogram shows identifiable carcinoma is ideal for breast conservative surgery like quadrantectomy / QUART therapy.

Xeromammography is same as above, but here a photoconductor is used to produce a final image on a Selenium paper rather than on X-ray film.

Advantages: Edge enhancement effect, therefore useful in dense breasts.

Disadvantage: Exposure to high radiation dose and selenium plates are needed.

ABERRATION OF NORMAL DEVELOPMENT AND INVOLUTION (ANDI) OF THE BREAST

ANDI includes variety of benign breast disorders occurring at different periods of reproductive periods in females—early, matured and involution phase of reproductive age group. It was first coined at Cardiff breast clinic in 1987 by LE Hughes. All conditions under ANDI should be carefully clinically examined and often mammography and FNAC/core cut biopsy should be done to rule out malignancy. ANDI includes different aberrations and diseases.

In early reproductive age group (15-25 years):

- Normal lobule formation may cause aberration as *fibroadenoma*. If it is more than 5 cm it is called *as giant fibroadenoma* as a diseased status. It is AND of a lobule.
- Normal stroma may develop juvenile hypertrophy as aberration and multiple fibroadenoma as diseased status.

In mature reproductive age group (25-40 years):

- Normal cyclical hormonal effects on glands and stroma get exaggerated by aberration causing generalized enlargement. Its diseased status is cyclical mastalgia with nodularity also called as *fibro-cystadenosis.*

Involution age group (40-55 years):

- Lobular involution with microcysts, fibrosis, adenosis, apocrine metaplasia and eventual aberrations as macrocysts and cystic disease of breast. Macrocyst is an aberration of normal involution (ANI). Sclerosing adenosis is also a type of aberration.
- Ductal involution may cause ductal dilatation and nipple discharge as aberration. Later disease status develops with periductal mastitis, bacterial infection, non-lactational breast abscess and mammary duct fistula. Periductal fibrosis may cause partial nipple retraction.
- Epithelial changes leads into epithelial hyperplasia and atypia.

FIBROADENOMA

- It is a benign encapsulated tumour occurring commonly in young females of 15-25 years age group.
- Presently it is considered as hyperplasia of a single lobule of the breast (classified under ***ANDI***).
- It is the most common benign tumour of the breast.
- It is aberration in normal development (AND) of a lobule.

Types

Gross:

1. Soft.
2. Hard.
3. Giant (> 5 cm in size)—Common in Africa.

Microscopy:

1. Intracanalicular—mainly fibrous tissue (small and hard). Stroma with distorted duct.
2. Pericanalicular—mainly cellular (large and soft). Stroma with normal duct.

Clinical Features

- It presents as a painless swelling in one of the quadrants, which is *smooth, firm, nontender, well-localized and moves freely* within the breast tissue (mouse in the breast).
- Axillary lymph nodes are not enlarged.



Fig. 8.10: US picture showing fibroadenoma left breast.



Fig. 8.11: Large fibroadenoma left breast in a 14-year old female.

Investigations

- Mammography (well-localised smooth regular shadow).
- FNAC.
- Ultrasound (to confirm solid nature).

Treatment

Excision through a circumareolar incision (*Webster's*) or submammary incision (*Galliard Thomas incision*) is done.

Points to be remembered

- *Size of giant duodenal ulcer is > 2 cm*
- *Size of giant gastric ulcer is > 3 cm*
- *Size of giant fibroadenoma is > 5 cm*
- *Diameter of transverse colon in toxic megacolon is > 6 cm*
- *Size of giant naevus is > 20 cm*

Clothe yourselves with compassion, kindness, humility, meekness and patience.



Fig. 8.12: Diagram showing circumareolar and submammary (Galliard Thomas) incisions.

FIBROCYSTADENOSIS (FIBROCYSTIC DISEASE OF THE BREAST/MAMMARY DYSPLASIA)

- It is due to **A**berration of **N**ormal **D**evelopment and **I**nvolution (***ANDI***) of breast causing.
- It is presently called as *cyclical mastalgia with nodularity.*

Microscopic changes
- Stromal fibrosis
- Microcyst formation
- Glandular proliferation (Adenosis)
- Hyperplasia (Epitheliosis)—in ducts and acini
- Papillomatosis—within the ducts, often with apocrine metaplasia

- It is an estrogen dependent condition. One of the cysts may get enlarged to become a clinically palpable, well-localised swelling—*bluedome cyst of Bloodgood.* It is fluctuant, transilluminant, nontender, often tensely cystic swelling (macrocyst) with thin bluish capsule. It should be aspirated initially. Surgical excision is done if it persists or recurs even after two aspirations; if it is blood stained; if there is residual lump after aspiration.
- When diffuse small, multiple cysts are the main component, it is called as *Schimmelbusch's disease.*
- *It is the commonest breast disease.*
- It is common in upper and outer quadrant.

Clinical Features

- Presentation is during menstruating age group as a *bilateral, painful, diffuse, granular, tender, swelling* which is better felt with palpating fingers (poorly felt with palm).
- Pain and tenderness are more just prior to menstruation *(cyclical mastalgia).*
- It subsides during pregnancy, lactation and after menopause.
- Discharge from the nipple when present will be serous or occasionally greenish.
- Occasionally shotty enlargement of axillary lymph nodes can occur.
- Not fixed to skin, muscle or chest wall.

Investigations

- FNAC (Epitheliosis, when florid is undoubtedly premalignant).
- Ultrasound.
- Mammography.

Treatment

I. Conservative line of management is preferred.
  1. Reassurance.
  2. *Oil of evening primrose (capsules):* Contains gamolenic acid which reverses the saturated fatty acids to unsaturated fatty acids. 320-500 mg/day for 4 months.
  3. Gamolenic acid—120 mg.
  4. Bromocriptine—1.25-2.5 mg BD for 3 months.
  5. Vit E and B_6.
  6. LHRH agonist.
  7. Danazol—200 mg BD for 3 months.
  8. NSAIDs.
  9. Tamoxifen—antioestrogen.
  10. Diuretics.

II. Surgery:
  - Subcutaneous mastectomy with prosthesis placement—only in severe, persistent disease.
  - Excision of the cyst or localised excision of the diseased tissue.

Indications for surgery
1. Intractable pain
2. Florid epitheliosis—on FNAC
3. Blood good cyst

***Note*:**

Subcutaneous mastectomy is removal of entire breast with retaining skin over the breast, areola and nipple. It is done through a submammary Galliard Thomas incision. Adequate skin flap containing subcutaneous fat is raised which maintains the blood supply of the flap and prevents flap necrosis. After haemostasis drain is placed. Breast implant can be placed in subcutaneous/submuscular plane either immediately or as delayed reconstruction. Indications for subcutaneous mastectomy are–fibrocystadenosis with epitheliosis, sclerosing adenosis, persistent nodules, gynaecomastia and DCIS.

SCLEROSING ADENOSIS

Known cause of breast lump.

Features

- Occurs in 30-50 years of age.
- Patient may present as breast lump or mastalgia.
- On palpation—It is smooth, relatively mobile mass.
- It can mimic carcinoma clinically, radiologically and histologically.
- No risk of malignancy.
- It is included under ANDI.
- Treatment is like ANDI.

Histology

- Lobular enlargement and distortion.
- Fibrous stromal proliferation.

PHYLLOIDES TUMOUR (CYSTOSARCOMA PHYLLOIDES/ SEROCYSTIC DISEASE OF BRODIE)

- They are not simply giant fibroadenoma.
- They show a wide spectrum of activity, varying from almost a benign condition (85%) to a locally aggressive and sometimes metastatic tumour (15%).
- Depending on mitotic index and degree of pleomorphism they are graded as low grade to high grade tumours.
- When malignant (sarcoma) spreads to lungs or bone.

Gross: Large capsulated area with cystic spaces and cut surface shows soft, brownish, cystic areas.



Fig. 8.13: Cystosarcoma phylloides of right breast. Note the dilated veins. Tumour occupies the entire breast.

Microscopy:

- It contains cystic spaces with leaf like projections, hence the name (Phylloides—Greek—leaf-like).
- Cells show hypercellularity and pleomorphism.
- It may be a variant of intracanalicular fibroadenoma of breast (Giant type).

Clinical Features

- They occur in premenopausal women (30-50 yrs).
- It is usually unilateral, grows rapidly to attain a large size with bosselated surface.
- Swelling is *smooth, nontender, soft, fluctuant with necrosis of skin* over the summit due to pressure.
- Skin over the breast is stretched, red and with dilated veins over it. Tumor is warmer, not fixed to skin or deeper muscles or chest wall. Nipple retraction is absent. Lymph nodes are usually not involved.
- Tumor grows rapidly; undergoes necrosis at various places; causes cystic areas.
- Recurrence is common.

Investigations

- U/S.
- FNAC.
- Mammography.
- Chest X-ray CT chest in malignancy to see secondaries.



Fig. 8.14: Phylloides tumour of left breast (Cystosarcoma phylloides of left breast).

ANDI was coined by Cardiff breast clinic.



Fig. 8.15: Operated specimen of cystosarcoma phylloides.

Treatment

- Excision or subcutaneous mastectomy is done.
- If malignant (sarcoma), total mastectomy is indicated.

TRAUMATIC FAT NECROSIS

It may be due to either direct or indirect trauma (trauma may not be noticed many times).

Pathogenesis

Capillary ooze causes triglyceride in the fat to dissociate into fatty acids. It combines with calcium from the blood resulting in *saponification* which causes inflammatory reaction and later presents as a nonprogressive swelling in the breast.

Clinical Features

- Painless swelling in the breast which is *smooth, hard, nontender and adherent* to breast tissue.
- It is nonprogressive, nonregressive.

Investigations

- FNAC shows chalky fluid with fat globules.
- Mammography to rule out malignancy.

Differential Diagnosis

- Carcinoma breast.

Treatment

- Excision.

GALACTOCELE

- Seen in lactating women.
- It is due to the blockage of lactiferous duct resulting in enormous dilatation of lactiferous sinus.
- It contains milk within.
- It is a retention cyst in subareolar region attaining large size.

Clinical Features

- Lump in the lower quadrant of the breast which is usually *unilateral, large, soft, fluctuant, with smooth surface.*
- It is usually nontender.
- It may get *precipitated, inspissated* or get *calcified*. When it is calcified it mimics carcinoma breast. If it gets infected it will form an abscess.



Fig. 8.17: Galactocele.



Fig. 8.16: Recurrent cystosarcoma phylloides.

Investigations

- U/S.
- FNAC.

Treatment

- Excision (submammary incision).
- Abscess when formed should be drained under general anaesthesia under cover of antibiotics.

MASTITIS

Types



Fig. 8.18: Diagram showing subareolar, intramammary and retromammary abscess.

1. Subareolar.
2. Intramammary.
3. Retromammary (submammary).



Fig. 8.19: Severe infection caused sloughing of the skin and breast tissue, eventually granulating and is ready for graft.

1. *Subareolar mastitis*

- It is the infection under the areola due to cracks in the nipple or areola. It results from an infected gland of Montgomery or a furuncle of the areola.
- Often it is associated with duct ectasia – causing formation of abscess, sinus and fistula.

Clinical Features

- Red, inflamed, edematous areola with a tender swelling underneath.

Differential Diagnosis

Paget's disease of the nipple.

Treatment

- Under cover of antibiotics pus is drained by making a subareolar incision.

2. *Intramammary mastitis (Breast abscess)*

a. ***Lactational abscess of the breast***:
Commonly seen in lactating women.

Precipitating factors

- Cracked nipple
- Retracted nipple
- Improper cleaning of the nipple
- Inadequate milk sucking by baby or milk expression causing stasis
- Infection from the mouth of the baby
- Haematoma getting infected

Mode of infection:
Bacteria (*Staph. aureus*—commenest) enters the breast during sucking through the cracked nipple. Occasionally it can be from haematogenous spread. Gram negative and other bacterial infections can supervene later.

Staphylococcus aureus causes clotting of milk in the blocked duct and multiply. Duct initially gets blocked by epithelial debris or by retracted nipple. Initially it begins in one quadrant but later involves entire breast.

Clinical features:

- Continuous throbbing pain in the breast and fever.
- Diffuse redness, tenderness and brawny induration in the breast.
- Purulent discharge from the nipple.
- Entire breast may get involved eventually.
- It is difficult to differentiate initial *stage of mastitis* (stage of cellulitis) from *stage of breast abscess* formation. When it is treated by antibiotics without

Saying 'no' to something is actually much more powerful than saying 'yes'. — Tom Hanks incision and drainage eventually it may get organised to form a nontender, hard breast lump with sterile pus inside – *stage of antibioma* formation.

Differential diagnosis:

Inflammatory carcinoma of breast.









Figs 8.20A to D: Typical breast abscess with features of acute inflammation. Drain should be placed after incision and drainage in such abscesses. Often gauze drain can be used.



Fig. 8.21: Breast abscess in a male patient. Breast abscess is uncommon in male eventhough it can occur during puberty..

Treatment:

- Antibiotics—Cephalosporins, flucloxacillin and amoxicillin.
- Repeated US guided aspirations can be tried which avoids surgery and scar.
- Drainage under general anaesthesia, a counter incision may be needed.

  It is not advisable to wait till the formation of abscess.

Indications for drainage in mastitis/breast abscess–

- Mastitis not resolving with antibiotics in 48 hours
- Persistent fever and progression of mastitis
- Brawny induration

Do not wait for abscess to form (fluctuation to develop)

Complications:
- Antibioma formation.
- Sinus formation, skin necrosis, fistula formation.
- Recurrent infection, bacteraemia, septicaemia.

Suppression of lactation is often required by giving Bromocryptine 2.5 mg BD for 2 weeks.

b. ***Non-lactational abscess of the breast:***

It commonly occurs in duct ectasia and periareolar infections. Common organisms are bacteroides, anaerobic streptococci, enterococci and gram negative organisms. It is commonly recurrent with tender swelling under the areola.



Fig. 8.22: Incision and counter-incision for breast abscess.



Fig. 8.23: Photo showing placement of drain in breast abscess.

Treatment:
- Antibiotics.
- Repeated aspirations.
- Drainage and later cone excision of the duct is done.

3. *Retromammary mastitis*

- It is due to tuberculosis of the intercostal lymph nodes or ribs beneath or suppuration of the intercostal lymph nodes.
- Breast is normal.

Causes
- Tuberculosis of intercostal lymph nodes
- Tuberculosis of ribs beneath
- Suppuration of intercostal lymph nodes
- Empyema necessitans
- Infected haematoma.

Investigations:
- Chest X-ray.
- FNAC.
- ESR.
- Peripheral smear.
- U/S of breast and chest wall.
- Often CT scan chest may be needed.

Treatment:
- Cause has to be treated.
- Drainage through submammary/retromammary incision.

Note:
- Mastitis of infancy (*Witch's milk*) is due to maternal hormone in infant blood. It usually subsides but may cause suppuration.
- Mastitis of infancy affects both sexes equally.
- Mastitis of puberty is common in boys, is invariably unilateral with tender, swollen and inflamed breast.
- Mastitis of mumps is usually unilateral and can occur in both sexes.
- Bacterial mastitis is seen in adult women, commonly lactating and is due to staphylococci infection.
- Subareolar mastitis is due to infection of gland of Montgomery or due to areolar furuncle.

ANTIBIOMA

If intramammary mastitis is not drained but only treated by antibiotics, pus localises and becomes sterile (flaques) with a thick fibrous tissue cover and it is called as antibioma.

When arms are raised fully above the head, visible signs of breast carcinoma frequently becomes more apparent.
—Hugh Auchincloss

Clinical Features

- Previous history of mastitis treated with antibiotics.
- Swelling which is painless, smooth, nontender, hard, fixed to breast tissue without involving the pectorals and chest wall.

Differential Diagnosis

Carcinoma breast (Scirrhous carcinoma breast).

Investigations

- FNAC
- Mammography
- U/S breast

Treatment

Excision (Submammary incision). Later antibiotics are given. It should be sent for histology.

DUCT ECTASIA

It is dilatation of lactiferous ducts due to muscular relaxation of duct wall with *periductal mastitis*.

It is also called 'plasma cell mastitis' as periductal inflammation contains plasma cells.

Commonly many ducts are involved.

Clinical Features

- Greenish discharge from the nipple.
- Indurated mass under the areola which is often tender.
- Retraction of nipple which occurs at later stage of the disease. Slit like retraction of nipple due to fibrosis occurs.
- Eventually it forms an *abscess* and *fistula*.
- Often they are bilateral and multifocal.
- More common in smokers – in relation to arterial pathology.
- Secondary bacterial infection is common.

Differential Diagnosis

Carcinoma breast.

Investigations

- Discharge study.
- Mammography.

Treatment

- It is important to stop smoking.
- Cone excision of involved major ducts (*Hadfield operation*).
- Antibiotics.

MONDOR'S DISEASE

- Mondor's disease is thrombophlebitis of the superficial veins of the breast and anterior chest wall.
- Cause is not known. History suggestive of injury or infection is not observed.
- Presents as a thrombosed subcutaneous cord which is attached to the skin.
- On raising the arm above, a narrow, shallow subcutaneous groove appears alongside the cord like thrombosed vein.
- It is often a self-limiting disease without any recurrence, complication or deformity.
- It often mimics the lymphatic permeation of carcinoma breast.
- Restriction of arm movements and anti-inflammatory drugs may be needed.

TUBERCULOSIS OF THE BREAST

- It is relatively rare.
- Usually associated with active pulmonary tuberculosis.
- Presents as a swelling in the breast with cold abscess, sinuses and a typical bluish appearance of surrounding skin with matted lymph nodes in the ipsilateral axilla.



Fig. 8.24: Tuberculosis of breast showing undermined lesion.

Differential Diagnosis

Carcinoma breast.

Investigations

- FNAC.
- Frozen section biopsy is useful to differentiate from carcinoma.
- Excision biopsy.

Treatment

- Antituberculous drugs—INH, Rifampicin, Ethambutol, Pyrazinamide.
- Drainage of cold abscess.
- Mastectomy is not done.

CYSTIC SWELLINGS OF THE BREAST

- Blood good cyst
- Breast abscess
- Hydatid cyst
- Galactocele
- Serocystic disease of Brodie
- Cystic necrosis in carcinoma breast
- Lymph cyst
- Haematoma in breast

MASTALGIA ("Pain in the breast")

Types

- Cyclical.
- Noncyclical.

Cyclical
- Pain related to menstrual cycles.
- Usually seen in ANDI like fibrocystadenosis.
- Present in women of menstruating age group.
- Pain is more during menstruation.
- It is bilateral, diffuse with "heavy feeling".

Treatment:
- Evening primrose oil 325 mg BD.
- Gamolenic acid 120 mg BD.
- Danazol (100-200 mg BD) - antigonadotrophin agent.
- Bromocriptine (2.5 mg BD) - prolactin inhibitor.
- Tamoxifen (20 mg daily).
- GnRH analogue 3.6 mg injection depot-monthly.
- Testosterone undecanoate 40 mg BD.
- Vit B_6, B_{12}.
- Analgesics.

Noncyclical
- Other causes of breast pain are periductal mastitis, malignancy, cervical root pain, musculoskeletal pain, previous surgery, Tietze's syndrome.
- It is unilateral, chronic, burning or dragging in nature, occurs both in pre- and post-menopausal age group.
- 5% of breast cancers present as pain during first presentation.

Treatment
- Cause has to be identified.
- Malignancy has to be ruled out.
- Avoid coffee and stress.
- Proper support to breasts.

Tietze's syndrome: Costochondritis of second costal cartilage, commonly seen in females, mimics mastalgia.

GALACTORRHOEA

It is secretion of milk not related to pregnancy or lactation.

Primary galactorrhoea is due to stress and other factors. Reassurance is the treatment.

Secondary galactorrhoea is due to enhanced dopamine activity
— by drugs (haloperidol, methyldopa, chlorpromazine, metoclopramide),
— hyperprolactinaemia due to tumours.

Treatment

- Bromocriptine.
- Cause has to be treated.

Note: ***Witch's milk*** is secretion of milk in both male and female infants due to maternal hormonal effects in foetus. It lasts upto 3 weeks after child birth.



Fig. 8.25: Mammography showing calcified lactiferous duct with a benign lesion.

Transillumination in a case of duct papilloma may reveal an opacity in the line of the duct due to pent-up blood. —William J Moore

GYNAECOMASTIA

- It is hypertrophy of male breast more than usual due to increase in ductal and connective tissue elements often attaining features of female breast.
- It can be unilateral or bilateral.



Fig. 8.26A: Gynaecomastia – right side breast. Compare to opposite side to note the difference in size.



Fig. 8.26B: Right-sided gynaecomastia.

Presentations

- Diffuse enlargement of breast occupying all quadrants.
- Often well-localised, small, firm or hard nodule under the areola which is often painful and tender.

Causes

- Idiopathic
- Teratoma testis
- Ectopic hormonal production in bronchial carcinoma
- Anorchism, after castration
- Adrenal and pituitary disease
- Leprosy, because of bilateral testicular atrophy
- Drugs: Stilbestrol, digitalis, cimetidine, spironolactone, INH, phenothiazides
- Liver diseases and liver failure
- Klinefelter's syndrome (XXY Trisomy)

Investigations

Relevant to the cause, e.g. liver function tests, DNA study, hormone assay.

Treatment

- When symptomatic or large or of long-standing, excision through circumareolar incision is done.
- Otherwise subcutaneous mastectomy has to be done.

Note: Often gynaecomastia may turn into carcinoma.

DUCT PAPILLOMA

- Commonest cause of bloody discharge from nipple
- It is usually single, from a single lactiferous duct
- It blocks the duct causing ductal dilatation

Clinical Features

- Papilliferous swelling (projection), usually seen near the nipple orifice.
- Blood stained discharge from the nipple is common.
- But serous or serosanguinous discharge can also occur.
- Single papilloma is not premalignant.
- But multiple papillomas in many ducts can be premalignant.



Fig. 8.27: Breast duct papilloma is commonest cause of bloody discharge.



Fig. 8.28: Breast papilloma. It usually arises from single duct. It projects near the nipple orifice.

Investigations

- Discharge study.
- Injection of contrast into the duct (Ductogram).

Treatment

Microdochectomy: Probed lactiferous duct is opened, and the papilloma is excised using *tennis racquet* incision.

CARCINOMA BREAST

> ***When cancer occurs in the breast of women under forty, it is more rapid in its progress than when the patient is older, and also more extensive; remote sympathy likewise takes place more readily in them than in the old, so that the operation succeeds better in the latter on this account.***
>
> **—John Hunter**, 1728-1793

Aetiology

- Carcinoma breast is more common in developed, western countries.
- In African-American women, it is more aggressive. It is less common in Japan.
- It is second most common carcinoma in females. Incidence is 19-34%. Median age is 47 years.
- Carcinoma in one breast increases the risk of developing carcinoma on opposite breast by 3-4 times. Incidence of bilateral carcinoma is 2%.
- It is more common after middle age, but can occur at any age group, after 20 years.
- It can be familial in 2-5% cases.
- Mutation of tumour suppressor genes BRCA1/ BRCA2 is thought to be involved with high risk of breast carcinoma. BRCA1 mutation is having more risk (35-45%) than BRCA2 mutation. It is located in long arm of chromosome 17, whereas BRCA2 is located in long arm of chromosome 13.
- Occasionally mutation of BRCA3 and p53 suppressor gene is also involved.
- *Li-Fraumen's syndrome* (LFS) is autosomal dominant condition with breast cancer inheritance (90%) along with sarcoma, leukemia, brain tumours, adreno-cortical tumours.
- Diet low with phytoestrogens and high alcohol intake have high risk of breast cancer.
- It is more common in nulliparous woman.
- Attaining early menarche and late menopause have high risk of breast malignancy.
- Early child bearing and breast feeding reduces the chances of malignancy.
- It is more common in obese individuals.
- Breast cancer relative risk is qualified as relative risk (RR). If RR is 2.0 means, risk is twice the normal population. If RR is 0.5 means, risk is 50% less than normal population.
- Risk is 3-5 times more if 1st degree relative is having breast cancer.
- In males, occasionally gynaecomastia turns into carcinoma.
- Benign breast diseases with atypia, hyperplasia and epitheliosis has got higher risk in a patient with family history.
- *Cowden's syndrome*—It is an autosomal dominant condition, with cutaneous facial lesion (100%), bilateral breast lesion (50%), GI polyps, brain, thyroid tumours.
- It is often associated with ataxia telangiectasia.
- It is more common in individuals who are on oral contraceptive pills and hormone replacement therapy (HRT) for more than 5 years.
- Presently carcinoma breast is considered as a systemic disease. ***Halsted concept*** of spread is *sequential spread*. Breast—axillary lymph node—systemic spread. ***Fischer concept*** is early to begin with itself, there is distant blood spread because of *micro metastasis* without nodal disease. Only tumour lesser than 1 cm size can be sequential. ***Spectrum concept*** is new one where disease spreads loco regionally as well as systemically which makes it to aim at both loco regional disease control as well as systemic disease control.
- Prior diagnosis of uterine / ovarian / colonic cancers.

In the presence of troubles some people grow wings; others buy crutches.

Incidences in carcinoma breast

- 30% of all female cancers
- 20% of cancer related deaths in females
- 2-4% bilateral
- 2-5% hereditary
- Lump in the breast-commonest presentation (75%)
- 10% presents with pain
- 35-45% with mutation of BRCA1 gene
- 70% blood spread occurs to bones

Pathology

- Breast carcinoma arising from lactiferous ducts is called as ***ductal carcinoma.***
- Breast carcinoma arising from lobules is called as ***lobular carcinoma.*** It is 10% common.

Risk factors for breast carcinoma

- Breast carcinoma in 1st degree relative
- Breast carcinoma in contralateral breast
- BRCA1/BRCA2 gene mutation
- Obesity and alcohol intake
- Gynaecomastia in male breast
- Nulliparity
- Early menarche and late menopause

- ***In-situ carcinoma*** is preinvasive carcinoma which has not breached the epithelial basement membrane.
  It may be
  - *Ductal in situ carcinoma (Ductal Carcinoma In Situ, DCIS)* or
  - *Lobular in situ carcinoma (Lobular Carcinoma In Situ, LCIS*).
- ***Invasive carcinoma*** can occur eventually.



Fig. 8.29: Carcinoma right breast in an elderly—an atrophic scirrhous carcinoma.

Classifications

I. Ductal carcinoma.
Lobular carcinoma.



Fig. 8.30: Examination with both arms raised above the shoulder.

II. (a) In situ carcinoma
  - ***DCIS (Ductal carcinoma in situ).***
  - ***LCIS (Lobular carcinoma in situ).***

(b) Invasive.
  - Invasive ductal carcinoma.
  - Invasive lobular carcinoma. It is commonly multifocal and often bilateral.

III. Unilateral.
Bilateral—2-5% common.

IV. Unifocal.
Multifocal.
Multifocal—tumour tissues within the same quadrant at multiple foci.
Multicentric—tumour tissues within the same breast but in different quadrant.

DCIS (Duct carcinoma *in situ*)

- It is intraductal carcinoma (proliferation of malignant mammary ducal epithelial cells) without any invasion into the basement membrane.
- It is 5%-20% common.
- It can be—
  - Solid.
  - Comedo with necrosis is high grade with increased chances of microinvasion.
  - Cribriform.
  - Papillary.
  - Micropapillary.
- It is associated with high expression of C – erb2 gene (80%).
- It can be high grade DCIS or low grade DCIS.
- It can be comedo DCIS (more malignant and more likely to be invasive later) or non-comedo DCIS (less malignant).

- Nipple discharge and often small swelling are main presentations.
- U/S assisted FNAC and mammography are the needed investigations.

Van Nuy's prognostic index for DCIS

Score	*1*	*2*	*3*
Size in mm	< 15 mm	15-40 mm	> 40 mm
Clearance in mm	> 10 mm	1- 10 mm	< 1 mm
Grade and necrosis	not high grade No necrosis	not high grade necrosis present	high grade necrosis present

Total score is 9

Score 3-4 conservative breast surgery (wide local excision)

Score 5-7 conservative surgery + Radiotherapy

Score 8-9 total mastectomy

- Risk of lymph node spread in DCIS is less than 4%. So axillary dissection is not necessary.
- *Sentinel Lymph Node Biopsy* and proceed is the preferred method.

Nottingham Prognostic Index (NPI)- (0.2 X Tumour size in cm) + Lymph node stage + Tumour grade

NPI score - < 3.4	Good prognosis with 80% survival (15 years)
NPI score - 3.4 –5.4	Moderate prognosis with 40% survival
NPI score > 5.4	Poor prognosis with 15% survival

Management of DCIS

- FNAC confirms the disease but will not differentiate from DCIS and invasive carcinoma
- Mammography, U/S breast, MRI breast
- Routine metastatic work up
- *Breast conservative surgery with RT* to breast and axillary dissection after SLNB
- *Hormone therapy* (tamoxifen) prevents both local recurrence and development of new primary breast carcinoma
- *Total mastectomy* is done in DCIS when – positive margin after wide local excision; two or more primary tumour; when radiation to breast is not possible; tumour/breast size ratio is not appro-priate for conservative surgery and DCIS in pregnancy. *Skin sparing mastectomy* (SSM) may be ideal in such occasions

Types

1. *Scirrhous carcinoma*: It is 60% common. It is hard, whitish, or whitish yellow, noncapsulated, irregular, with *cartilaginous* consistency. It contains malignant cells with fibrous stroma.



Fig. 8.31: Specimen of carcinoma breast. Cut section showing tumour tissue of scirrhous type (commonest type).

2. *Medullary carcinoma:* Also called as 'encephaloid type' because of its brain like consistency. It contains malignant cells with dispersed lymphocytes.
3. *Inflammatory carcinoma/Lactating carcinoma/Mastitis carcinomatosis:*
   - Most malignant type of carcinoma breast.
   - It is 2% common.
   - It is common in lactating women or pregnancy.
   - It mimics acute mastitis because of its short duration, pain, warmth and tenderness.
   - Clinically, it is a rapidly progressive tumour of short duration, often involving whole of breast tissue with occurrence of Peau d' orange, often extending to the skin of chest wall also.
   - It rapidly metastasises to chest wall, bone and lungs.
   - *It is always stage IV carcinoma* (T_{4d}). FNAC confirms the diagnosis—It contains undifferentiated cells.
   - Total count is normal.

   Treatment
   - External radiotherapy and chemotherapy.
   - It has got *worst prognosis*.

   Differential diagnosis

   Acute mastitis—Total count is increased.
4. *Colloid carcinoma:* It produces abundant mucin.

A man is not the best because he works hard, he works hard because he is the best.

5. *Paget's disease of the nipple*

> ***I believe it has not yet been published that certain chronic affections of the skin of the nipple and areola are very often succeeded by the formation of scirrhous cancer in the mammary gland…. In the majority (the affection) had the appearance of a florid, intensely red, raw surface…like the surface of very acute diffuse eczema.***
>
> **—James Paget,** 1874

— It is superficial manifestation of an intraductal carcinoma. The malignancy spreads within the duct up to the skin of the nipple and down into the substance of the breast. It mimics eczema of nipple and areola.

Differences between Paget's disease and eczema of nipple

Paget's disease	*Eczema*
1. Unilateral	1. Bilateral
2. Edges are distinct	2. Edges are indistinct
3. Itching absent	3. Itching present
4. Seen in menopausal women	4. Occurs during the time of lactation
5. Vesicles absent	5. Vesicles present
6. Nipple is usually destroyed	6. Nipple is usually intact
7. Underlying lump is usually present	7. No underlying lump

— In Paget's disease, there is a hard nodule just underneath the areola, which later ulcerates and causes destruction of nipple. Histologically, it contains large, ovoid, clear *Paget's cells* with malignant features.

6. *Tubular, papillary, cribriform* are other types of duct carcinomas.
7. *Atrophic scirrhous carcinoma*:
   - Seen in elderly females. It is a slow growing tumour which has got better prognosis.
   - FNAC is diagnostic.
   - Mastectomy or curative brachytherapy (using breast moulds) is the treatment of choice.
   - It is curable.
8. *Lobular carcinoma in situ*
   - Predominantly premenopausal.
   - Need not be detected by mammography, as it does not provoke calcification.
   - It is an incidental pathological entity.
   - Multifocal and bilateral.
   - Clinically, it do not form a lump.
   - Does predispose to invasive cancer.
   - 50% cancers can develop in the contralateral breast.
   - Immunohistochemistry using e-cadherin antibody shows positive reaction in lobular carcinoma.



Figs 8.32A and B: Paget's disease of the breast.



Fig. 8.33: Carcinoma breast involving axillary tail of Spence.



Fig. 8.34: Subareolar carcinoma with destruction of nipple-areolar complex.



Fig. 8.35: Carcinoma breast over the commonest site—upper outer quadrant—more visible on raising the arm.



Fig. 8.36: Mass in the upper outer quadrant—is the commonest site of the carcinoma breast.

- It has poor prognosis due to bilateral, multifocal nature and difficulty in identifying it.



Fig. 8.37: Carcinoma right breast with ulceration in the primary (P) with axillary lymph node secondaries (S).



Fig. 8.38: Quadrants of breast. Carcinoma is more common in upper outer quadrant as more breast tissue is located in this quadrant.

9. *Disease of Reclus*: It is a rare intracystic papilliferous carcinoma of breast presenting as a cystic swelling with bloody discharge from the nipple.

Grading of the Tumour

- It is based on nuclear pleomorphism; tubule formation; mitotic rate.
- It can be – well-differentiated (grade 1); moderately differentiated (grade 2) and poorly differentiated (grade 3).

To strengthen your heart, forgive yourself and others.



Fig. 8.39: Ca breast with rib secondaries.



Fig. 8.40: Carcinoma breast with extensive skin involvement.

Biological Behaviour and Clinical Features of Carcinoma Breast

Most common site is *upper outer quadrant (60%) because breast tissue is more in this quadrant.*

Cutaneous Manifestations of Carcinoma Breast

- *Peau d'orange*: Due to obstruction of dermal lymphatics, openings of the sebaceous glands and hair follicles get buried in the oedema giving rise to orange peel appearance.
- *Dimpling of skin* due to infiltration of ligament of Cooper.
- *Retraction of nipple* due to infiltration of lactiferous duct.
- *Ulceration, discharge* from the nipple and areola.
- Skin ulceration and fungation.
- *Cancer-en-cuirasse*: Skin over the chest wall and breast is studded with cancer nodules appearing like an armour coat.
- *Tethering* to skin.

Spread into the Deeper Plane

- Into pectoralis major muscle (is confirmed by observing the restricted mobility of the swelling while contracting the PM muscle).
- Into latissimus dorsi muscle (extending the shoulder against resistance).
- Into serratus anterior (by pushing the wall with hands without flexing the elbow).
- Into the chest wall (breast will not fall forward when leaning forward, and while raising the arm above the shoulder, breast will not move upwards as it is fixed to the chest wall).



Fig. 8.41: Peau d'orange appearance of skin.



Fig. 8.42: Ulcerated carcinoma breast with peau d'orange. Note the lymph node enlargement.

Lymphatic Spread

- Occurs through
  - subareolar Sappey's lymphatic plexus (presently its significance is discounted).



Fig. 8.43: Carcinoma breast on chemotherapy having alopecia.



Fig. 8.45: Patient underwent mastectomy earlier for carcinoma breast presenting with fungating lymph node secondaries in axilla.



Fig. 8.44: Advanced carcinoma left breast involving entire breast with nodularity.

- cutaneous lymphatics.
- intramammary lymphatics.

- Lymphatic drainage of the breast is predominantly through axillary (75%) and internal mammary lymph nodes.

  Axillary group of nodes are:

1. *Anterior* along lateral thoracic vessels (Pectoral).
2. *Central* (medial) embedded in fat in the centre of the axilla.
3. *Posterior* along subscapular vessels.
4. *Lateral* along axillary vein.
5. *Apical* lies above pectoralis minor tendon in continuity with the lateral nodes and receive efferents from all the groups.

Spread to these lymph nodes occur by ***lymphatic permeation.***

- *Interpectoral,* lies between pectoralis major and minor muscle (***Rotter's nodes***). Presently involvement of these lymph nodes are considered due to retrograde spread.

  These lymph nodes are cleared during *Patey's mastectomy.*

  Groups 1st and 2nd are commonly involved.
  Groups 3rd and 4th are rarely involved.
  Finally Group 5th is involved.
- From axillary lymph nodes spread occurs to supraclavicular lymph nodes by ***lymphatic embolisation.***
- Through dermal lymphatics, it may spread to opposite breast or to opposite axillary lymph nodes.
- Spread restricted to level I nodes carries better prognosis.
  Spread to level II has poor prognosis.
  Spread to level III indicates worst prognosis.
- Spread may occur into internal mammary lymph nodes of same side and then to mediastinal lymph nodes.
- Contralateral internal mammary lymph nodes can also get involved by retrograde spread.
- *Fixed enlarged axillary nodes* can cause lymphoedema due to lymphatic block; venous thrombosis and venous oedema due to venous block; and severe excruciating pain along the distribution of the median

Accountable, dependable, reliable are qualities that make a person responsible.

and ulnar nerves (rare in radial nerve) with often significant sensory and motor deficits due to tumour infiltration of the cords of brachial plexus (medial cord often lateral cord).

Once axillary lymph nodes get fixed, it can result in ***lymphoedema of the upper limb.*** It develops gradually.

Compression of nodes on axillary vein can cause sudden onset of ***venous oedema of upper limb*** (Venous edema develops faster, and is more proximal with bluish discolouration of the skin of the upper limb. It may lead to venous gangrene and so the compression has to be relieved early by radiotherapy).

Causes of lymphatic block in carcinoma breast	*Treatment of lymphoedema of arm*
• Involvement and fixation of the axillary nodes level I, II and III • After levels I, II and III dissection • After radiotherapy to axilla • Inoperable fixed nodes in axilla • Recurrent axillary disease • May be associated with *cancer-en-cuirasse* • Secondary infection *Effects of lymphatic obstruction* • Peau d' orange • Brawny oedema of arm – indurated, painful, non pitting – occurs in fixed nodes in axilla • Elephantiasis chirurgens – after radical mastectomy or radiotherapy to axilla • *Cancer-en-cuirasse*– seen in locally advanced carcinoma of breast. Skin of chest wall is studded with hard fixed nodules like armour coat (of soldiers) • Lymphangiosarcoma after radical mastectomy or MRM (Stewart – Treve's)	• Elevation of limb • Elastic stockings • Pneumatic compression • Drugs like diuretics and benzopyrones

Breast is in subcutaneous plane, but its extension, ***axillary tail of Spence*** passes through an opening in the deep fascia (***foramen of Langer***). Often it is difficult to differentiate between lymph node in pectoral region and tumour invasion of axillary tail. Mobility will be independent if it is a lymph node, but if it is an axillary tail tumour, it is along with the primary tumour in the breast.

Haematogenous Spread

- ***Bone (Commonest)*** **(70%)—**Lumbar vertebrae, femur, ends of long bones, thoracic vertebrae, ribs, skull, in order. They are *osteolytic* lesion often with pathological fracture. Present with painful, tender, hard, non-mobile swelling, with disability.

70% of secondaries in bone in a women is due to carcinoma breast.

Spine secondaries can cause paraplegia.



Fig. 8.46: Carcinoma breast operated, with upper limb oedema postoperatively



Fig. 8.47: Cancer-en-cuirasse with malignant nodules in the chest wall and skin.



Fig. 8.48: Pathological fracture of the humerus due to metastatic secondaries from the carcinoma breast.



Fig. 8.49: Intramedullary nailing as a treatment for pathological fracture.

Features of bone secondaries

- Pain
- Swelling
- Pathological fractures

- Liver—either through blood, occasionally through transcoelomic spread.
- Lung—causes malignant pleural effusion and cannon ball secondaries.
- Brain—causes increased intracranial pressure, coning.
- Adrenals and ovaries.



Fig. 8.50: Osteolytic secondaries involving ischium and pubic bones.

Common sites of distant spread in carcinoma breast

- Bones—70% - (lumbar vertebrae, pelvic bones, long bones)
- Lungs and pleura—20-30%
- Soft tissues—5-15%
- Liver—10-12%
- Brain—2-5%
- Adrenals—2-5%

Transcoelomic Spread

Through mediastinal lymph nodes, it may spread into peritoneal cavity causing secondaries in liver, peritoneum, ovary (*Krukenberg secondaries*—occurs in menstruating age groups. During ovulation, cells get attached over the ovarian capsule).

Note: Present concept of Krukenberg tumour is haematogenous and lymphatic modes of spread. Older concept of transcoelomic spread is no longer well-accepted.

Presentation of carcinoma breast

- Lump in the breast which is hard, painless (commonest)
- Nipple discharge is the second common presentation
- Ulceration and fungation
- Axillary lymph node enlargement; Supraclavicular lymph node enlargement
- Chest pain and haemoptysis
- Bone pain, tenderness, and pathological fracture
- Pleural effusion, ascites
- Liver secondaries, secondary ovarian tumour
- Pain in the lump in 10% cases



Fig. 8.51: Recurrent carcinoma breast.

Breast self-examination (BSE) plays a major role in early detection and intervention of breast carcinoma.

Have a heart that never hardens and a temper that never tires and a touch that never hurts.

This underlines the importance of advocating *self-examination of the breast.*

Ideally done once a month just after the menstruation, as during this time breasts are less engorged. In postmenopausal age group it is done at monthly regular intervals.

- Examine both breasts.
- Remind the patient that 90% of breast lumps are not cancer.
- Better way is in lying down position with arm raised with a mattress support behind.
- Palpation should be using the fingers over all quadrants of the breast.
- If any doubtful swelling is palpable, consult the surgeon.
- American Cancer Society recommends monthly BSE after 20 years of age.
- Nursing mother should perform BSE just after feeding the baby.



Fig. 8.52: Self-examination of breast is done in lying down position.

Staging of Carcinoma Breast (Manchester and TNM Staging)

Manchester Staging

1. Tumour in the breast, not involving pectoral or deeper plane. Skin involvement if present, it is lesser than the size of tumour. Lymph nodes are not palpable.
2. Same as stage I but with *mobile, discrete lymph nodes* palpable in the ipsilateral axilla.
3. Tumour fixed to pectoral muscle, or skin involvement more than the tumour size or ipsilateral axillary lymph nodes adherent to each other or fixed.
4. Tumour fixed to the chest wall, 'cancer-en-cuirasse', skin involvement wider than that of the breast, involvement of ipsilateral or contralateral supraclavicular lymph nodes or opposite breast or opposite axillary lymph nodes, spread to bone, lung, liver or inflammatory carcinoma of breast.

TNM Staging

Tumour:

1. T_1—Tumour size < 2 cm in greatest diameter. (T_{1a}—0.1-0.5 cm; T_{1b}—0.5-1 cm; T_{1c}—1-2 cm).
2. T_2—Size 2-5 cm.
3. T_3—Size >5 cm.
4. T_4—Tumour fixed to chest wall or skin. (T_{4a}—Fixed to chest wall; T_{4b}—Fixed to skin; T_{4c}—$T_{4a} + T_{4b}$; T_{4d}—inflammatory carcinoma of breast).

Node:

N_0— No nodes.

N_1— Axillary nodes mobile (ipsilateral).

N_2— Axillary nodes fixed to one another and other structures (or only internal mammary lymph nodes are involved but not axillary nodes).

N_3— Supraclavicular nodes. Oedema of arm and internal mammary lymph nodes (ipsilaterally) (or–internal mammary lymph nodes and also axillary lymph nodes are involved).

Metastasis:

M_0 No metastasis.

M_1 Distant Metastases.

	T0	T1	T2	T3	T4
N_0		I			
N_1		II			
N_2		IIIA			
N_3		IIIB			
M_1		IV			

Differential diagnosis for carcinoma breast

- Fibroadenosis
- Traumatic fat necrosis
- Tuberculosis of breast
- Blood good cyst
- Filariasis breast
- Mastitis
- Antibioma
- Galactocele
- Mondor's disease
- Cystosarcoma phylloides



Fig. 8.53: Carcinoma breast presenting as lump in the breast. It is the commonest presentation.

Investigations in Carcinoma Breast

- ***Mammography***.

Findings
- Size and location of mass lesion
- Microcalcifications signify malignancy
- Soft tissue shadow is irregular
- Spiculations

- ***Ultrasound of breast:*** To find out whether the lesion is solid or cystic.

Ultrasound of breast

- To look for whether the lesion is solid or cystic, margin of the lesion, internal echoes, retro-tumor acoustic shadowing, compressibility, dimensions
- *Irregular margin, irregular internal echoes, irregular posterior shadowing, non-compressibility, ratio between antero-posterior to width (lateral/horizontal) dimensions more than 1 are the features of carcinoma.* Doppler will show high frequency signals with continuous flow
- Benign lesions are smooth, rounded with well defined margins with weak internal echoes and compressibility
- Disadvantage is lesions less than 1 cm may not be identified
- FNAC can be done under U/S guidance.
- It is cheaper, easily available and there is no risk of radiation
- It is preferred method of screening in young females where mammography is not done and in pregnancy and early lactation
- US of axilla also can be done to assess axilla and to do guided FNAC of node

- ***FNAC:*** It is very useful in diagnosing the carcinoma breast. U/S guided FNAC is also used. But negative results are difficult to interpret because it may be due to sampling errors and so requires further

The Columbia Classification (Haagsen, Cooley and Stout)

GRAVE SIGNS:
- Oedema of skin
- Skin ulceration
- Fixity to chest wall
- Axillary lymph nodes >2.5 cm
- Fixed axillary lymph nodes

Stage A—only tumour. No Grave signs
Stage B—tumour + axillary lymph nodes < 2.5 cm
Stage C—tumour + anyone of five grave signs
Stage D—two or more Grave signs
Supraclavicular lymph node involvement
Distant metastasis

Stage A— No skin oedema, ulceration, or fixation to chest wall.
Axillary nodes are not clinically involved.
Stage B— Clinically involved axillary nodes less than 2.5 cm in diameter.
Not fixed.
Stage C— Grave signs of comparatively advanced carcinoma.
Oedema of skin, skin ulceration, fixation to chest wall.
Massive axillary involvement with nodes >2.5 cm in diameter.
Axillary fixation.
Stage D— Advanced carcinoma including two or more signs in stage C.
In addition satellite nodules, supraclavicular nodes.
Inflammatory cancer, arm oedema or distant metastasis.

> *Mammary fistula presents as a recurrent abscess that points and discharges on to the areola and continues to discharge for weeks at a time.*
> —Sir Headly Atkins

diagnostic methods. FNAC of opposite breast, lymph nodes, opposite axillary lymph nodes are also often required.

It is done with 23 gauge needle using FNAC aspiration special syringe. With the lump held firmly, the needle is passed into the lump and with negative pressure continuous aspiration is done until adequate material comes through the needle. Needle with syringe is removed without negative pressure. Material is collected on a slide; a smear is made using 100% alcohol. Cytology is studied after staining it under microscopy.

Advantages–

FNAC is least painful, can be done on OP basis, reliable and cheaper. Malignant deposits will not occur along FNAC track (only contraindication for FNAC is testicular tumour).

Note: **FNNAC** is **F**ine **N**eedle **N**on-**A**spirating **C**ytology.



Fig. 8.54: FNAC of breast lump.

Reliability of FNAC and mammography

	FNAC	*Mammography*
Sensitivity (true positivity)	90-98%	90%
Specificity (without false positive)	98-100%	90%
False negative	2-10%	10%
False positive	Near 1-5%	10%

FNAC Scoring

C_0 : No epithelial cells
C_1 : Scanty epithelial cells, benign
C_2 : Benign cells
C_3 : Atypical cells
C_4 : Suspicious cells
C_5 : Malignant cells

- ***Frozen section biopsy***: If FNAC fails even after two trials or in cases of negative FNAC, then on table frozen section biopsy is done for diagnosis. Frozen section biopsy also has got drawbacks. It has got 20% false negative results. So its use at present is under debate eventhough it is practiced in most oncocenters.
- *Corecut/Trucut biopsy* is done under local anaesthesia. It gives clear histological evidence and also confirms DCIS (FNAC can not confirm DCIS). This allows proper neoadjuvant/primary chemotherapy, receptor status of the tumour. Wide bore needle biopsy with vacuum is also used.
- *Excision biopsy* is done only when FNAC is inconclusive and a facility for frozen section is not available. Incision should be planned in such a way that it will be included in eventual mastectomy.
- ***Chest X-ray***: To look for pleural effusion, cannon ball secondaries in lungs, mediastinal lymph nodes, secondaries in rib.
- *CT chest* is more reliable method to see lung secondaries.



Fig. 8.55: US picture of right breast showing breast mass.

- ***Ultrasound abdomen:*** To look for liver secondaries, ascites, 'Krukenberg' tumour.
- ***X-ray spine*** shows osteolytic secondaries.
- ***Oestrogen receptor study*:**
  - They are oestrogen sensitive receptors, which are cytosolic, glycoprotein present in the breast and tumour tissue. It is an important indicator of prognosis of carcinoma breast.
  - Tissue for receptor study is sent at low temperature in ice flasks. It is assessed by quantitative analysis (Frozen –70°).

- If value is more than 10 units (f/mols) per n gram of tissue it is called as *ER +ve status*. ER positivity is common in post-menopausal women (60%) compared to pre-menopausal women (30%). If value is less than 10 units per gram of tissue it is called as *ER –ve status*.

  In ER +ve status
  - Prognosis is good.
  - Hormone therapy including Tamoxifen is more beneficial.
  - Response to treatment is better.

  In ER –ve status
  - Prognosis is poor.
  - Hormone therapy is not very beneficial (but used) as compared to ER +ve patients.
  - Response to treatment is not good.
- ***Progesterone receptor (PR status)*** study or *Her 2 Neu receptor status* or *cErb B2* (growth factor receptor study) are other studies done at present to plan the therapy and assess the prognosis.
- ***Study of discharge*** from the nipple. Nipple discharge is usually unilateral in carcinoma breast. *Ductal lavage* may be useful in some patients. Microcatheter of 1 cm length is introduced gently into the ductal opening. 10 ml saline is infused through the catheter. Fluid is withdrawn into the syringe and cytological analysis is done.
- ***MRI of breast***:
  - To differentiate scar from recurrence.
  - To image breasts of women with implants.
  - To evaluate the management of axilla and recurrent disease.
- It is useful in screening females with high risk group.
- T1 and T2 weighed images are taken.
- Irregular mass with spiculations, changes in skin and nipple, lymphoedema are the findings in carcinoma breast.

  MRI breast is not accurate if done within 9 months of the radiotherapy in carcinoma of breast.

  Both precontrast and postcontrast MRI are done.
- ***Edge biopsy:*** Done only when there is ulceration and fungation. Diathermy should be avoided in incision biopsy as it may distort the histology of tumor and study of hormone receptor status may not be possible.
- ***Tumour markers:*** CA 15/3 (normal value < 40 U/ml of serum) are used mainly during follow-up period.
- ***MRI spine/pelvis*** show osteolytic secondaries in the bone like vertebra and pelvic bones.
- ***Radioisotope bone scan*** to look for secondaries in bone in advanced cases. It is not done routinely in early carcinoma of breast.

Indications for whole body bone scan in carcinoma breast

- T3, T4 advanced disease
- Advanced nodal disease
- Bone pain, bone swelling, pathological fracture
- Chest/liver secondaries

- ***Sentinel lymph node biopsy (SLNB)***: The first axillary (SLN) node draining the breast (by direct drainage) is designated as the *sentinel node*. SLN is first node involved by tumour cells and presence or absence of its histological involvement, when assessed will give a predictive idea about the further spread of tumour to other nodes. Involvement of other nodes without SLN is less than 3% and so if SLNB is negative nodal dissection can be avoided but regular follow up is needed. SLNB is done in all cases of early breast cancers, T1 and T2 *without clinically palpable node.* It is not done in clinically palpable axillary node as there is already distortion of lymphatic flow due to tumour. It is also not done in multifocal and multicentric tumours, as there is involvement of many lymphatic trunks from different places of breast, and chances of false negative is high. Sentinel node is localized by pre-operative (within 12 hours) or per-operative injection of patent blue (Isosulfan vital blue dye) or 99m TC radio isotope labelled colloid albumin near the tumour (peritumour area) or over subdermal plexus around the nipple. Marker will pass through the sentinel node which can be detected visually as blue staining or with a hand held gamma camera; and is biopsied with a small incision directly over it. Frozen section biopsy or touch imprint cytology is done for presence of malignant cells. If there is no involvement of sentinel node by tumour then further axillary dissection is not required as *skip lesions* (skipping sentinel node) occur only in less than 3% cases.

  Note: Facility for SLNB is not available in many centres.

SLNB is done in—

- Carcinoma breast
- Carcinoma penis
- Malignant melanoma

Wise man has got the art of knowing what to overlook.



Fig. 8.56: Sentinel Lymph Node Biopsy (SLNB) of breast. Note: Spread by skipping the sentinel node is less than 3%.

- ***Axillary sampling*:** It is often done with an adequate axillary incision. 10-15 nodes are removed for sampling. It is not commonly practiced now. (Minimum 10 nodes should be removed- level I nodes).
- ***CT scan of chest, abdomen and brain*** whenever needed. CT is said to be more useful to detect secondaries in these regions.
- ***Ductography*:** It is contrast study of ducts of breast in case of unilateral nipple discharge. Fine cannula is passed under vision carefully through the duct opening into the duct and 0.2 ml of dilute water-soluble contrast media is injected into the duct. Craniocaudal and mediolateral X-ray films are taken. Contrast irregular filling defect may be observed.
- ***Thermography*:** It is not very sensitive test (50%). Malignant tumours are hypervascular and so transmitted temperature is detected through different thermographic methods.
- ***Blood count, complete liver function tests*** are needed.

Triple assessment includes

1. Clinical assessment
2. Radiological imaging
3. Cytological or histological analysis

Newer investigation modalities for carcinoma breast

1. Stereotactic core biopsy using computer mammography
2. Vacuum-assisted biopsy using 11-guage biopsy probe (becoming popular)
3. Needle localised biopsy under mammographic guidance
4. I^{125} – seed localisation biopsy

Treatment of carcinoma breast:

It is usually through a combined approach.

- *Surgery*
- *Radiotherapy*
- *Hormone therapy*
- *Chemotherapy*



Fig. 8.57: Horizontal incision for total mastectomy.



Fig. 8.58: Oblique incision extending into the anterior axillary fold for radical mastectomy.

A. **Surgeries for carcinoma breast**

- ***Total (simple) mastectomy*:** Along with the tumour, entire breast, areola, nipple, skin over the breast, including axillary tail are removed. There is no axillary dissection. Often the patient is subjected to radiotherapy later (External) to axilla.


A
1-2 cm
Tumour
Incision
B

Figs 8.59A and B: Stewart incision for mastectomy.


Tumour
Incision

Fig. 8.60: Gray incision for mastectomy in carcinoma breast which extends to opposite side.


Incision
Tumour

Fig. 8.61: Greenough incision for mastectomy.


Incision
Tumour

Fig. 8.62: Kocher's incision for mastectomy.


Incision
Tumour

Fig. 8.63: Orr incision for mastectomy


Tumour
Incision

Fig. 8.64: Rodman incision for mastectomy.

If you don't know where you're going, you may miss it when you get there.

- *Total mastectomy with axillary clearance*: Commonly used procedure. Total mastectomy is done along with removal of axillary fat, fascia and lymph nodes.
- *Modified radical mastectomy–*
  - *Patey's operation*: It is total mastectomy along with clearance of all levels of axillary nodes and removal of pectoralis minor muscle. It is enblock dissection of breast and axilla. An elliptical incision is made from medial aspect of the second and third intercostal space enclosing the nipple, areola and tumour extending laterally into the axilla along the anterior axillary fold. Upper and lower skin flaps are raised. Breast with tumour is raised from the medial aspect of the pectoral major muscle. Dissection is proceeded laterally with ligating pectoral vessels. Once dissection reaches axilla, lateral border of pectoralis major muscle is cleared with level I nodes. Pectoralis minor is divided from coracoid process to clear level II nodes. Medial and lateral pectoral nerves should be preserved (otherwise atrophy of pectoralis minor muscle occurs). Later from the apex of axilla level III nodes are cleared. Nerve to serratus anterior, nerve to latissimus dorsi, intercostobrachial nerve, axillary vein, cephalic vein and pectoralis major muscle are preserved. Wound is closed with a suction drain.











Figs 8.65A to E: Different steps of Patey's mastectomy with incision, flap raise, dissection in breast and axilla and specimen after surgery.

Mastectomy specimen should be carefully inspected and sent to pathology department

- Specimen is sent in formalin for histology.
- It is sent in saline in low temperature for ER/PR/Her 2 neu status study (histochemistry).

- Tumour grading, tumour clearance, nodal involvement - its number and capsular breach are assessed histopathologially.
- ***Scanlon's operation:*** Is a modified Patey's operation wherein instead of removing pectoralis minor, it is incised to approach the affected Level III lymph nodes.
- ***Auchincloss modified radical mastectomy***: Here pectoralis minor muscle is left intact and level III lymph nodes are not removed.

- ***Halsted Radical Mastectomy***.* (*Complete Halsted*) (***R M***):

  Structures removed are:
  - Tumour.
  - Entire breast, nipple, areola, skin over the tumour with margin.
  - Pectoralis major and minor muscles.
  - Fat, fascia, lymph nodes of axilla.
  - Few digitations of serratus anterior.

  Structures retained are (ABC)
  - **A**xillary vein
  - **B**ells nerve (nerve to serratus anterior)
  - **C**ephalic vein

  Complications are lymphoedema and eventual lymphangiosarcoma (after 3 to many years later) of the limb.

- ***Conservative breast surgeries:*** Tumour is removed with a rim of 1 cm of normal tissue. It may be
  a. Wide excision.
  b. Quadrantectomy as part of *therapy* — *QUART (VERONESI):* Entire segment of the involved breast



Fig. 8.66: Note the original Halsted and modified Halsted incision.



Fig. 8.67: Complete Halsted operation—Radical mastectomy with removal of fat, lymph nodes, pectoralis major, pectoralis minor, entire breast with tumour and skin over the breast, nipple and arcola.

---

* **Not commonly done at present**. If at all, it is done in early stage I carcinoma breast.

It is better to light a small candle than to curse the darkness.

is removed along with *axillary dissection* (done through a separate incision in the axilla, level I and II removal) and *radiotherapy.* There is a higher rate of local recurrence after conservative QUART therapy especially in younger patient and in high grade tumours.

- ***Toilet mastectomy*:** In locally advanced tumour, tumour with breast tissue and whatever possible is removed to prevent further fungation. But its use and significance is under question. It is often done after giving chemotherapy.
- ***Extended radical mastectomies*:** It includes radical mastectomy + removal of internal mammary lymph nodes of same side with or without opposite side. **It is not done at present.**
- ***Skin sparing mastectomy*** (SSM/Key hole mastectomy) is becoming popular with different approaches.
- ***Lumpectomy*** word is presently used only for removal of benign diseases of breast; *not for* malignant disease.

Complications of MRM/mastectomy

- Injury/thrombosis of axillary vein
- Seroma—50-70%
- Shoulder dysfunction 10%
- Pain (30%) and numbness (70%)
- Flap necrosis/infection
- Lymphoedema (15%) and its problems
- Axillary hyperaesthesia (0.5-1%)
- Winged scapula

LYMPHANGIOSARCOMA (Stewart-Treve's syndrome) of upper limb can develop in patients who have developed lymphoedema after mastectomy with axillary clearance. Usually it occurs *3-5 years* after development of lymphoedema. Such patient may require fore-quarter amputation. It has got poor prognosis. It presents as multiple subcutaneous nodules.

B. Radiotherapy in carcinoma breast

Indications:

- Patient who undergo conservative breast surgery, breast is irradiated after surgery.



Figs 8.68A to D: Mastectomy specimen with dissected axillary nodes. Last photo is Patey's operation specimens. Note the pectoralis minor axillary area and tumour with breast tissue.

Radiotherapy in carcinoma breast

To chest wall—

- T3 tumour > 5 cm
- Residual disease-LABC
- Positive margin/close surgical margin of < 2 cm
- After conservative surgery
- Higher risk group
- Inflammatory carcinoma

To axilla—

- 4 or more nodes positive
- Extranodal spread
- Axillary status not known/not assessed

- *RT is a must* after conservation of breast
- Local as well as to axilla
- Tangential fields 50 Gy/25 fractions/5 weeks
- Another 10 Gy to tumour bed
- Internal mammary and supraclavicular area may be included in radiation field



Fig. 8.69: Postmastectomy lymphoedema. Note the mastectomy scar.

- After total mastectomy, external irradiation is given to axilla.
- Patients with higher risk of local relapse after surgery:
  a. Invasive carcinoma.
  b. Extensive *in situ* carcinoma.
  c. Patients under 35 years.
  d. With multifocal disease.
- In bone secondaries, to palliate pain and swelling. If there is pathological fracture in the bone, internal fixation has to be done along with external irradiation.
- Inflammatory carcinoma of breast.
- In atrophic scirrhous carcinoma of breast, as a curative radiotherapy.
- As preoperative radiotherapy, to reduce the tumour size and downstage the tumour, so that the operability is better.
- More than 4 positive lymph nodes in the axilla, pectoral fascia involvement, positive surgical margins, extranodal spread or in patients with axillary status not known/not assessed.

External radiotherapy is given over the breast area, axilla (in selected patients like if axillary dissection is not done or more than 4 positive axillary nodes), internal mammary and supraclavicular area

- Total dosage 5000 cGY units
- 200-cGY units daily 5 days a week for 6 weeks

C. Hormone therapy in carcinoma breast

Principles

- It is used in ER/PR positive patients in all age groups (earlier it is used in perimenopausal age groups).
- It is relatively safe, easy to administer.
- It gives prophylaxis against carcinoma of opposite breast.
- It is useful in metastatic breast carcinoma.
- Hormone therapy (tamoxifen) is useful in breast cancer in elderly (positive ER) after wide local excision or occasionally as tamoxifen alone.
- It is now not used in ER negative patients.
- Menopausal status; nodal status; chemotherapy used are not factors to defer the use of hormone therapy.
- Hormone therapy reduces the recurrence rate and so probably improves the life span and quality of life.

Includes

- Oestrogen receptor antagonists—*Tamoxifen.*
- Ovarian ablation by surgery (Bilateral oophorectomy) or by radiation.
- LHRH agonists (Medical oophorectomy).
- Oral aromatase inhibitors for postmenopausal women.
- Adrenalectomy or pituitary ablation.
- Progesterone receptor antagonist.
- Androgens—Inj Testosterone propionate 100 mg IM three times a week.
- Aminoglutethimide—blocks the synthesis of steroids by inhibiting conversion of cholesterol to pregnenolone—*Medical adrenalectomy*.
- Progestogens, e.g. Medroxyprogesterone acetate.

TAMOXIFEN

- It is an antioestrogen. It blocks oestrogen receptors.
- Dose is 10 mg BID for 5 years.

Adverse Effects

- *Tamoxifen flare*—flushing, tachycardia, sweating.
- Occasionally it causes bone pain which should be differentiated from pain due to bone metastasis.
- It increases the incidence of endometrial cancer.

Advantages

- It reduces the recurrence rate by 25%.
- It improves the prognosis.
- It is used presently in all age group, ER +ve patients.
- Cheap, easily available, less toxic effects, very effective.
- It is equally effective in carcinoma male breast.
- It is presently also **under trial** for certain benign diseases of breast (*ANDI, Cyclical mastalgia*).

The place to improve this world is first in one's own heart, head and hands.

Selective Oestrogen Antagonists

- Do not cause endometrial hyperplasia or endometrial carcinoma.
- Drugs include Droloxifen, Toremifen.

Tamoxifen used in-

- Carcinoma breast
- Benign diseases of the breast like fibroadenosis
- Infertility in males
- Desmoid tumour

LETROZOLE

- It is a non-steroidal competitive inhibitor of the enzyme 'aromatase'. This enzyme converts adrenal androgens to oestrogen (aromatization). So it is an aromatase inhibitor.
- Other aromatase inhibitors are *anastrozole and exemestane*.
- Letrozole is used as an adjuvant endocrine therapy in post-menopausal women with hormone sensitive breast cancer. (In pre-menopausal women this will cause rise in gonadotrophins and ovarian aromatase is not well suppressed). It can also be used in metastatic and recurrent cases. It slows down and stops the growth of oestrogen sensitive breast tumours. It reduces oestrogen level by 98%. Its half life is 45 hours. It decreases the bone density.
- Dosage of letrozole is 2.5 mg once daily.
- It is given for 5 years or for 2 years following 3 years of tamoxifen.
- Side effects of letrozole are vaginal dryness, night sweats, hot flushes, vaginal bleeding, cardiovascular problems and osteoporosis.

TRANSTUZUMAB (Herceptin)

- It is a monoclonal antibody that blocks HER-2/neu receptors thereby preventing growth of cancer cells. It is a new drug. It is presently marketed as herceptin. It is c-ErbB2 (growth factor receptor) inhibitor. It is a newer biological agent.
- It has very little effect on HER-2/neu negative cancers.
- It is useful only in HER-2/neu positive cancers. It is currently approved by FDA for use only in metastatic disease. It is given as intravenous infusion.
- Studies have shown substantiate improvement in disease free and overall survival rate.
- It has got cardiac side effects.

Note

- *Tamoxifen* interferes with oestrogen receptors
- *Letrozole* interferes with oestrogen production
- *Transtuzumab* (Herceptin) interferes with HER-2 neu receptors

- *Bevacizumab* – vascular growth factor receptor inhibitor – newer agent
- *Lapitinab* – combined growth factor receptor inhibitor – newer agent

Hormone therapy for carcinoma breast

In pre-menopausal women

- Tamoxifen – antioestrogen
- Ovarian ablation by surgery/by Goserelin/by radiation
- Progestogens – Medroxyprogesterone 400 mg
- Androgens – Fluoxymestrone

In post-menopausal women

- Tamoxifen
- Aromatase inhibitor like letrozole 2.5 mg OD
- Progestogens
- Androgens
- Medical adrenalectomy using aminoglutethemide (Mitotane) – as major source of oestrogen after menopause is adrenal gland. Cortisone supplement is also needed to prevent feedback rise of ACTH which may block the effect of aminoglutethemide

Surgical endocrine ablations

- Bilateral oophorectomy (Beatson—1896)
- Bilateral adrenalectomy
- Pituitary ablation

D. Chemotherapy in Carcinoma Breast

Indications

- In advanced carcinoma breast as a palliative procedure.
- In postoperative period after simple mastectomy in stage III carcinoma breast with fixed axillary nodes.
- In inflammatory carcinoma of breast.
- In stage IV carcinoma breast with secondaries in bone, lungs, liver.
- In premenopausal age group with poorly differentiated tumours.

Toxic effects are: Alopecia, bone marrow suppression, cystitis, megaloblastic anaemia, GIT disturbances, nephritis.

Drugs Used

CMF regime	*CAF regime*	*MMM regime*
Cyclophosphamide Methothrexate 5-Fluorouracil	Cyclophosphamide Adriamycin 5-Fluorouracil	Methotrexate Mitomycin-C Mitozantrone

Drug	*Mechanism of action*	*Dose*	*Adverse effects*
Tamoxifen	Antioestrogen	20 mg	Nausea, weight gain, hot flushes, vaginal bleeding, bone pain, amenorrhoea
Medroxyprogesterone	Progestogen	400 mg	Nausea, flushing, vaginal bleeding
Amino glutethimide	Aromatase inhibitor	250 mg - QID	Rash, dizziness, lethargy, Cushing facies
Arimidex	Aromatase inhibitors	1 mg	Lethargy, GI upset
Zoladex (Goserelin)	LHRH agonist	3.6 mg monthly	Amenorrhoea, nausea. It is expensive
Diethyl stilboestrol	Oestrogen	15 mg daily	Fluid retention, vomiting, thrombosis, hypercalcaemia
Fluoxymestrone	Androgen	30 mg daily	Masculinization, nausea

It is more beneficial in ER +ve patient; perimenopausal patient with node +ve; postmenopausal patient.
Presently ***Tamoxifen and Oophorectomy*** are the commonly used methods.

- ***CMF and CAF*** are commonly used with monthly/ 3 weeks cycles for 6 months.
- Other anthracyclines like doxorubicin or epirubicin should be used often for better result.
- ***Taxanes*** - They are newer chemotherapeutic drugs which act by G2/M phase of cell cycle. It is commonly used in metastatic carcinoma of breast. Drugs are **paclitaxel and docetaxel**. Taxanes have no cross resistance with anthracyclines and so can be used sequentially or concurrently with anthracyclines.
- Gemcitabine is also used often in selected cases for better results.

Indications for chemotherapy

- All node positive patients
- Node negative patients but with other poor prognostic factors like tumour grade

Note:

- Neoadjuvant (primary) chemotherapy is useful in large operable primary tumour to make it amenable for conservative breast surgeries. Post operative radiotherapy and chemotherapy is a must in this situation.
- High dose chemotherapy with stem cell rescue is not found to be beneficial by trials in patients with heavy large nodal spread.
- Hormone therapy is given after completion of chemotherapy for additive effect. Concurrent therapy of both (together) is not used at present. It is sequential – chemotherapy then hormone therapy. Chemotherapy gives quicker and better response initially and so it is used early and later only hormone therapy is continued.
- Chemotherapy and radiotherapy can be given concurrently or as sandwich therapy.
- Presently one day dose of all drugs of the regimen used as a *standard* at 3 weekly cycles for 6 cycles for stage III CAF. For metastatic paclitaxel single day dose cycles or etoposide and cisplatin 3 days cycle – 6 cycles.

MANAGEMENT OF EARLY CARCINOMA BREAST

- Early breast cancer is the one diagnosed by mammography or Stage I carcinoma breast.
- Usually chest X-ray, blood count and liver functions are sufficient to screen the early breast cancer patients.

Aims of Treatment

- To achieve possible '*cure*'.
- Control of local disease in breast and axilla.
- Breast conservation, i.e. breast form and function.
- Prevention of distant metastasis.
- To prevent local recurrence.

Modalities of Treatment

- *QUART therapy*.
- *Patey's operation* or simple mastectomy with axillary clearance.
- Postoperative radiotherapy in high risk patients.
- Hormone therapy, i.e. tamoxifen 10 mg BID.
- Sentinel node biopsy when required.
- Regular follow-up often with radioisotope bone scan and CEA tumour marker.

In early breast cancer, breast conservative surgery like quadrantectomy, axillary dissection (level I and II) and post-operative radiotherapy (to the breast) is used which prevents the disfigurement and psychological trauma of

Failure is the only opportunity to begin again more intelligently.

Breast conservative surgery

Indications

- Lump < 4 cm
- Clinically negative axillary nodes
- Mammographically detected lesion
- Well differentiated tumour with low S phase
- Adequate sized breast to allow proper RT to breast
- Breast of adequate size and volume
- Feasibility of axillary dissection and radiotherapy to intact breast

Contraindications

- Tumour > 4 cm
- Positive axillary nodes > N1
- Tumour margin is not free of tumour after breast conservative surgery
- Poorly differentiated tumour
- Multicentric tumour
- Earlier breast irradiation
- Tumour/breast size ratio is more
- Tumour beneath the nipple
- Extensive intraductal carcinoma

mastectomy to the patient. Tumour is removed with a rim of 1 cm normal tissue. Wide excision and QUART therapy are different procedures. (Use of word lumpectomy is a debate and not well-accepted).

Principles of Conservative Breast Surgery

- Curvilinear non-radial incisions (radial incisions should not be placed, because if there is a need to convert into total mastectomy, then incision plan may be difficult).
- Separate incision for axillary dissection.
- Undermining of the skin flap must be avoided.
- Confirm tumour clearance by frozen section. It may be often difficult and so tumour is cut and only margin which is close and doubtful is advocated for frozen section.




Radial and directly axillary extended incisions should not be used in conservative breast surgery
Wrong incisions
B

Figs 8.70A and B: Curvilinear incision should be placed in conservative breast surgeries. Never place wrong radial incisions because if conversion to total mastectomy is needed then placement of incision will be difficult. In conservative breast surgery for axillary dissection separate incision in the axilla should be placed.

- Radiotherapy is a must to breast and chest wall region (locally).

QUART Therapy

It is quadrantectomy, axillary dissection of level I and II nodes with separate axillary incision and post-operative radiotherapy to breast (5000cGy) and axilla (1000cGy). First it was started by *Umberto Veronesi* from Milan.

Skin Sparing Mastectomy (SSM)

- It is like a key-hole surgery of breast.
- Skin sparing/limited skin excision (5-10%) will not alter/affect the recurrence rate.

- *Indications are*- central tumour/multicentral/extensive intraductal/T1/not feasible for conservation.
- Excision of nipple-areola complex with very limited skin removal.
- Marginal skin excision over the tumour/biopsy site.
- Total glandular mastectomy.
- Axillary dissection using either same (extension of SSM incision) or separate incision in the axilla.

Indications for Total Mastectomy in early Breast Cancer

- When tumour is more than 4 cm.
- Multicentric tumour.
- Poorly differentiated tumour.
- Tumour margin is not clear of tumour after breast conservative surgery.


Incision for axillary dissection
Deep tumour (retained after biopsy)
Incision scar of excision biopsy
Re-excision incision with 1 cm - margin after excision biopsy
Nipple-areolar incision
A
Tumour
Skin sparing -mastectomy (SSM) incision
Re-excision incision with -1cm margin
Tumour
Incision scar of -previous biopsy
SSM incision
B
Incision for axillary dissection
Re-excision incision with -1 cm margin
Tumour
Skin sparing -mastectomy (SSM) incision (1 cm margin)
Tumour
C

Figs 8.71A to C: Skin sparing mastectomy for carcinoma breast- different approaches. Skin sparing mastectomy (SSM) does not affect the recurrence rate.

> *He who is afraid of doing too much always does too little.*



Figs 8.72A to C: Skin sparing mastectomy incision with prosthesis implant for placement.

Management of Axillary Nodes when clinically not palpable

- Sentinel Lymph Node Biopsy (SLNB) is done. If node is positive for tumour then axillary dissection is done. But facility for SLNB is not available in most of the centres and so axillary dissection is done as a routine. Usually level I and II nodes - below the axillary vein are dissected.
- Axillary sampling is done by separate curved incision between the outer border of pectoralis major and latissimus dorsi 6 cm below the apex of axilla. About 10-15 nodes (level I) are sampled. Axillary sampling is not advocated now.

Principles of Axillary Dissection/axillary Clearance

It is removal of axillary nodes with fat, fascia of the axilla. Different levels of nodes are removed.

Adjuvant therapy after surgery in early breast cancer

- Radiotherapy
- Chemotherapy—CMF, CAF regime commonly used. Taxanes are also used.
- Endocrine manipulation-
  - Ablation
  - Tamoxifen (receptor antagonist)- 20 mg/day for 5 years
  - Aromatase inhibitors- blocks oestrogen production. –Letrozole 2.5 mg OD
  - LHRH agonists- Goserelin 3.6 mg/28 day's cycle for 2 years.

ADVANCED CARCINOMA BREAST

Refers to -

- Locally inoperable (adherent to chest wall) tumour.
- Inflammatory carcinoma of breast.
- Fixed axillary lymph nodes, or supraclavicular lymph nodes, or opposite axillary nodes.

Principles of axillary dissection/axillary clearance

It is removal of different levels of axillary nodes; with fat and axillary fascia

Why axillary dissection is done?	*Which levels?*	*Technical principles*
• For staging • To assess the prognosis- number of nodes/size of the node • As a treatment- regional control of	• Level I-60% • Level I, II- 20-25% • Level I, II, III- 15-20%	• Any incision but caudal hair-line incision is preferred • Nerve to serratus anterior/thoracodorsal nerve should be safeguarded • Medial and lateral pectoral nerves should be retained when the disease done with the mastectomy
• To plan adjuvant therapy irradiation/chemo/hormone	• Level I and II dissection Low axillary dissection- less chances of lymphoedema	• Drain should be kept to the area • After surgery specimen should be properly dissected for all lymph nodes, labelled and sent for histological study. Usual number of nodes in axilla are 20-32. So minimum of 10 nodes should be dissected, identified and sent for study. Nodes can be easily identified if fat dissolving agents are used over them.

- Bilateral carcinoma breast.
- Metastatic carcinoma of breast, i.e. spread to bones, liver, lungs, brain.

Locally Advanced Carcinoma of Breast (LABC)

- It means locally advanced tumour with muscle/chest wall involvement, extensive skin involvement or fixed axillary nodes. It will be T3, T4a, T4b, T4c or T4d or N2 or N3.
- It is investigated by FNAC of tumor, mammography of opposite breast, chest CT, CT abdomen or whole body bone scan. Biopsy is needed to assess receptor status.
- Treatment of LACB is always palliative by simple mastectomy, toilet mastectomy, chemotherapy and hormone therapy using tamoxifen.
- Initial neoadjuvant chemotherapy; surgery; radiotherapy; adjuvant chemotherapy are other therapeutic plan.
- Palliation is to control pain, to prevent fungation or bleeding.
- In inoperable fixed tumour chemotherapy is given initially. Later, after 3-4 cycles of chemotherapy, when tumour size reduces and becomes operable, total mastectomy is done.
- Postoperative radiotherapy is given to breast field and axilla.
- Usually axillary dissection is not necessary in LACB.
- Only chemotherapy and radiotherapy to breast and axilla (without palliative mastectomy) also can be done in LACB.
- There is no role of breast conservative surgery for LACB.
- 5 year survival is 40% and 10 year survival is less than 25%.
- *Inflammatory carcinoma* is T4d LACB. It is also called as mastitis carcinomatosis or lactating carcinoma of breast. It is 2% common. It is observed in younger age group usually in pregnancy or lactating period. There will be extensive skin involvement with pain. It often mimics mastitis of lactation. FNAC or incision biopsy concludes diagnosis. It is initially treated by chemotherapy or radiotherapy and later if tumour reduces in size total mastectomy with axillary clearance can be done. But most often it is inoperable. After surgery, chemotherapy and tamoxifen is given. 5 year survival for inflammatory carcinoma of breast is 25-30%.

Metastatic Carcinoma of Breast

It is blood spread into different places like bone, lungs and pleura, liver, soft tissues, brain and adrenals. It is evaluated by FNAC/incision biopsy, chest CT, LFT, U/S abdomen, CT abdomen, whole body bone scanning, CT brain, tissue study for ER/PR/HER-2 neu receptor status.

Treatment concept in metastatic carcinoma of breast

- To improve quality of life.
- To relieve pain of secondaries like bone, lungs.
- To relieve neurological problems like convulsions, space occupying cranial problems.
- Other symptomatic relief.

Treatment strategy in metastatic carcinoma of breast

- Chemotherapy- CMF, CAF, Taxanes in combination.
- High dose of chemotherapy using cyclophosphamide, cisplatin, carmustine, melphalan is tried in view to get high response rate of 55-70% along with bone marrow transplant. But toxic effects are often life threatening. Its advantages are now doubtful when compared to toxic effects.
- Haemopoietic growth factor also used along with chemotherapy to enhance the cell kill with less bone marrow toxicity. It may also allow multiple high dose chemotherapy to increase the response rate.
- Radiotherapy is used in bone metastasis, brain secondaries, to prevent paraplegia in spine involvement, and advanced axillary nodes. It is also used in painful bone secondaries.
- Hormone therapy has got important role. Tamoxifen, oophorectomy, adrenalectomy, androgens, progestogens, aminoglutethimide are used.
- Blockage of over expression of epidermal growth factor (EGF) /transforming growth factor alpha (TGF-alpha) which are related to ErbB1/ErbB2 receptors in relation to aggressive carcinoma factor is tried.
- Palliative surgeries done are total/toilet mastectomy, fixation of bones in case of pathological fractures, spinal cord decompression to prevent paraplegia, lung resection in case of localized secondaries, bilateral oophorectomy.
- Trastuzumab (herceptin) is monoclonal antibody used in cancers with good results. It blocks the



Fig. 8.73: Carcinoma of breast operated earlier with skull secondaries. It is metastatic carcinoma of breast. Skull secondaries are not common. Common site of bone secondaries are lumbar vertebrae, pelvis, upper part of femur, ribs etc.

Her-2/neu and ErbB2 receptors. Bevacizumab and Lapitinab are other newer biological agents of different actions.

Bone secondaries in carcinoma breast-

- Commonest site of blood spread (70%)
- Lumbar vertebrae, femur, pelvis
- Pathological fracture can occur
- Spinal compression and paraplegia
- Radiotherapy, internal fixation, spinal decompression is required
- Biphosphonates 1600 mg/day.

Malignant pleural effusion as secondaries from Ca breast-

- It signifies terminal event
- It has got poor prognosis
- Respiratory distress and failure is the main feature
- HRCT is ideal diagnostic tool
- *Treated by*
  - Intercostal tube drainage
  - Pleurodesis using talc/tetracycline
  - Chemotherapy

Causes of death in carcinoma breast

1. Secondaries in lung—Haemoptysis, respiratory failure
2. Spine involvement—Quadriplegia
3. Secondaries in brain
4. Cancer cachexia

PROGNOSTIC FACTORS IN CARCINOMA BREAST

Stage	*5 yr survival*
I	90%
II	70%
III	40%
IV	20%

- **Spread to axillary nodes** is the most important prognostic indicator.
- **Age:** Younger the age worser the prognosis.
- **Sex:** Carcinoma male breast has got worser prognosis compared to female breast. Because of early spread in carcinoma male breast.

Lymph Node—as a Prognostic Factor

- Number of nodes: > 2 carries poor prognosis
- Location of nodes
- Capsular invasion
- Extranodal status
- Size of the node: >2.5 cm has poor prognosis
- More than 4 nodes/level III (apical nodes) involvement has got worst prognosis (5 year survival is 30%) and also decides for radiotherapy to axilla.

- **Stage I and II** has got better prognosis.
- **Atrophic scirrhous** has got best prognosis.
- **Medullary carcinoma** has got better prognosis than scirrhous carcinoma because of lymphocytic infiltration.
- **Invasive carcinoma** has got worser prognosis.
- **Inflammatory carcinoma** breast has worst prognosis.
- **ER +ve** tumours has got better prognosis.
- **Differentiation** also decides prognosis.
- **Presence of elastic fibres** in histology has got better prognosis.
- Tumour proliferation stages, growth factor and oncogene factors.
- Tubular, colloid, papillary types has got better prognosis.
- **Tumour grade**, growth factor and oncogene factors. ErbB2 –Her-2/neu positive has got poor prognosis. ErbB1 with over expression of epidermal growth factor (EGF), TGF alpha and cathepsin D has got poor prognosis.
- **DNA flow aneuploid** status has got poor prognosis. Low S phase fraction (< 5%) has got good prognosis.

Breast cancer group	*Features*	*Prognosis – 5 year survival*
• Very low risk primary	• DCIS; tubular	> 90%
• Low risk primary	• Node negative; favorable microscopy	70-90%
• High risk primary	• Node positive; unfavourable microscopy	< 70%
• Locally advanced	• Inflammatory ca/large primary (T4)	< 30%
• Metastatic	• Blood spread	Poor

Prognostic factors are classified as –

- Host factors – Age; sex; menopausal status; family history; previous breast cancer; immunosuppression; nutrition.
- Tumor factors – Tumour size; nuclear grade; staging; receptor status; DNA nature; spread etc.

CARCINOMA OF MALE BREAST

- It is less than 1% of cases of breast cancers.
- Gynaecomastia and excess oestrogen are said to be the aetiological factors. Commonly associated with BRCA2 gene mutation.
- Commonly it is *infiltrating duct carcinoma*.
- Presentation, spread, behaviour are same as carcinoma of female breast. Investigations and treatment are same as carcinoma female breast.
- *Tamoxifen* is very useful in carcinoma male breast.
- Carcinoma male breast has poorer prognosis when compared to carcinoma breast in females.



Fig. 8.74: Carcinoma male breast in a pre-existing gynaecomastia. Note Gynaecomastia on opposite side.



Fig. 8.75: Carcinoma male breast showing mass under the areola, puckering and nipple retraction.

- 80% cases are ER positive.
- LHRH agonists are also often used. It works at hypothalamo-pituitary axis level via tachyphylaxis. It produces reversible *"chemical castration"*. Goserelin 3.6 mg/28 days for 2 years is the current recommendation.
- Bilateral orchidectomy which was earlier used is no longer commonly advocated.

Carcinoma breast in pregnancy

- Incidence is 3%
- Treatment is modified radical mastectomy (MRM)
- Chemotherapy can be given in 2nd trimester with care
- Radiotherapy has no role
- As commonly ER negative, hormone therapy is not used
- When distressing secondaries are present termination of pregnancy may be required
- *Women with breast cancer can become pregnant 2 years after the completion of therapy, as recurrence is more common in 2 years*

> *He who reigns within himself and rules his passions, desires and fears is more than a king.*

FOLLOW UP AFTER THERAPY

- Clinical examination in detail at regular intervals.
- Yearly/two yearly mammography of treated and contralateral breast is a must.
- Bone scan/CT chest, abdomen/tumour marker are done only if there is clinical suspicion of spread/metastases. It is not a regular routine follow up method at present.

BREAST RECONSTRUCTION

- Immediate reconstruction.
- In early stages of malignancies as well as in selected more advanced stages where the response to neo adjuvant chemo therapy has been good. Not advised in locally advanced disease.
- Delayed reconstruction (3-9 months after surgery).

Indications

- Locally advanced disease.
- Radiation needed in postoperative period.
- Patient unfit for prolonged surgical procedure.

Advantages

- Allows for post op radiation without prosthesis exposure.
- Avoids fibrosis and fat necrosis where TRAM flap is used.

Factors deciding the reconstruction

- Amount of skin retained
- Stage of the carcinoma
- Earlier radiotherapy
- Type of flap used

Methods of Reconstruction

- Oncoplastic techniques.
- Insertion of breast implants or expanders. They are best for small breasts. Healthy non irradiated overlying skin is the requirement.
- Flap with implant or expanders.
- Flap reconstruction—
  - Pedicled flap – TRAM flap.
  - Free flap – free TRAM flap into internal mammary artery.

Types

- Silicon gel implant under pectoralis major muscle.
- Expandible saline prosthesis with prior tissue expansion.
- If there is less skin or after radiotherapy—Latissimus dorsi musculocutaneous flap (*LD flap*) or contra-


Skin
Implant
Pectoral muscle intact (submuscular)
Skin
Ribs
Implant
Pectoral muscle removed (subcutaneous)

Fig. 8.76: Breast implant.



Figs 8.77A and B: LD flap (A) Donor area (B) Recipient area.



Fig. 8.78: Latissimus dorsi flap (LD FLAP) placed after mastectomy. It is based on thoracodorsal artery.

LD flap	*TRAM flap*
• Myocutaneous flap based on subscapular artery • Easy to perform • Reliable flap, well vascularised • Can be placed over prosthesis • Low complication rate • But causes unsightly donor area on the back	• Transverse rectus abdominis myocutaneous flap based on superior epigastric artery. Contralateral TRAM flap is used • It gives the bulk needed for reconstruction and so implant is not needed • Donor site morbidity and fat necrosis can occur • Free TRAM flap into internal mammary/thoraco dorsal axis can be done • Limitations to position, shape and rotate; needs mesh placement in the abdomen wound to prevent development of incisional hernia



Fig. 8.79: Transverse rectus abdominis myocutaneous flap (TRAM). Note the blood supply of the flap.









Figs 8.80A to D: Different operative steps in TRAM flap.

In time of test, family is best.

lateral transversus abdominis muscle flap *(TRAM flap)* is used.
- Superior gluteal flap based on superior gluteal vessels
- *Ruben's flap* using soft tissue pad overlying the iliac crest based on deep circumflex iliac vessels.

External breast prosthesis which fits within the bra is a simpler cosmetic method.

Note:
- Breast reconstruction is done in young patients with early stage disease.
- Skin sparing mastectomy with removal of nipple areola complex may be better for reconstruction.
- Symmetry is the most important factor in breast reconstruction.

Nipple is created using—
- Local breast flaps 3 months after breast reconstruction.
- Nipple sharing from contralateral nipple using composite graft.
- *Skate flap*: Local flap with deepithelialised donor site around the periphery over which a full thickness graft is applied.
- Nipple prosthesis can be fitted.

Areola pigmentation is created using *(it is done 3 weeks after nipple creation)—*
- Full thickness skin graft from non hairy skin lateral to labia majora, as the pigmentation of this graft matches that of the areola.
- From contralateral areola if reduction mammoplasty is done on that side.
- Tattooing – Colour tends to fade with time and may need to be repeated.
- SSG from retroauricular area or from thigh.

BREAST IMPLANTS

Fig. 8.81: Typical breast implant and its placement. It can be placed in subcutaneous or sub muscular plane.

- Technically simple.
- Achieve symmetry easily.
- Implant in *submuscular plane* is better whenever muscle is not removed during surgery.
- If muscle is removed as in radical mastectomy, then *subcutaneous implant* is placed.
- Silicon gel implants are used.

Complications of breast implants

- Pain, exposure of implant and rupture
- Displacement, extrusion
- Infection
- Capsular contraction

Causes of massive enlargement of breast

- Benign hypertrophy—usually bilateral
- Giant fibroadenoma
- Serocystic disease of Brodie
- Sarcoma
- Colloid carcinoma
- Filariasis of breast

Changes that can occur in nipple

- Destruction
- Depression - retraction
- Discolouration
- Displacement
- Deviation
- Discharge
- Duplication

Causes of hard swellings in the breast

- Carcinoma breast
- Antibioma breast
- Traumatic fat necrosis
- Calcified haematoma
- Fibroadenoma—hard variety

MAMMARY FISTULA OF *ATKINS*

- It is a fistula of lactiferous duct which opens on to the areola.
- It causes recurrent abscess that points on to the areola which discharges and continues to discharge for a week.
- It is a differential diagnosis for carcinoma breast.

Treatment

- Antibiotics.
- Excision of fistula along with lactiferous duct.

NIPPLE RETRACTION



Fig. 8.82: Typical nipple retraction in carcinoma breast. It is circumferential retraction in carcinoma and slit like partial in duct ectasia.

- 25% of retractions are bilateral.
- Congenital nipple retraction is simple nipple inversion. It causes problems in breastfeeding, recurrent infection, collection of secretions.
- Slit like retraction is due to duct ectasia and periductal mastitis.
- Circumferential retraction is usually due to carcinoma.
- Any nipple retraction of recent onset should be evaluated.

DISCHARGES FROM THE NIPPLE

Blood
- Papilloma—commonest
- Carcinoma
- Ectasia

Serous
- Fibrocystic disease – common
- Ectasia

Greenish
- Ectasia – common
- Fibrocystic disease – rare

Purulent
- Infection
- Sometimes malignancy

Milk
- Lactation (Physiological discharge)
- Galactorrhoea – pituitary tumour, hypothyroidism

Serosanguinous
- Carcinoma
- Infection

Self-assessment Questions

- Discuss aetiology, clinical features and management of carcinoma breast.
- Differential diagnosis of lump in the breast.
- Advanced carcinoma breast.
- Metastatic carcinoma of breast.
- Tamoxifen.
- ER receptor.
- Benign diseases of the breast.
- Cystic swellings of the breast.
- Galactocele.
- Fibroadenoma.
- Cystosarcoma phylloides.
- Stage I carcinoma of breast.
- Traumatic fat necrosis.
- Breast abscess.
- Mastitis.
- Antibioma.
- Causes of nipple discharge.
- Fibrocystadenosis.
- ANDI.
- Duct papilloma.
- Bloodgood cyst.
- Paget's disease of the breast.
- Radiotherapy for carcinoma breast.
- Lymphatic drainage of breast.
- Carcinoma male breast.
- Gynaecomastia.
- Krukenberg tumour.
- Mammography.
- Mammary fistulas.

Hope sees the invisible, feels the intangible and achieves the impossible.

9

Peritoneum

> ***Among the inflammations of the abdominal region, I have given a place in our Nosology to the Peritonitis, comprehending under that title, not only the inflammations affecting the peritoneum lining the cavity of the abdomen, but also those affecting the extensions of this membrane in the omentum and mesentery.***
>
> **—William Gullen,** 1792

Anatomy
Physiology
Acute peritonitis
Sclerosing peritonitis
Biliary peritonitis
Postoperative peritonitis
Other forms of peritonitis
Pelvic abscess
Subphrenic spaces and subphrenic abscess
Mesenteric cysts

ANATOMY

PERITONEUM

It is a serous membrane lining the abdominal cavity. It is composed of outer fibrous tissue layer (which gives strength) and inner mesothelial cell layer (secretes fluid giving lubricating function to the peritoneum).

Parts of Peritoneum

1. *Parietal peritoneum*: It lines the inner surface of the abdominal wall, under surface of diaphragm and pelvic wall. It is loosely attached to the overlying walls and can be easily stripped off. It is innervated by the somatic nerves, so pain sensitive. Anterior peritoneum is most sensitive when compared to pelvic peritoneum.
2. *Visceral peritoneum*: It lines the outer surface of the abdominal viscera, firmly adherent, cannot be stripped off. It is innervated by autonomic nervous system; hence not pain sensitive.

PERITONEAL CAVITY

It is the potential space between the parietal and visceral peritoneum. Normally it contains 100 ml of clear, straw coloured fluid secreted by the mesothelial cells. Its quantity and quality varies in pathological conditions. It has got lubricating function, allowing frictionless movements of adjacent peritoneal surfaces.

PHYSIOLOGY

Surface area of peritoneum is 2 m^2 - equal to surface area of skin. It has property of bidirectional transfer of substances. It can absorb from or transfer to peritoneal cavity, fluid and electrolytes. This property is used in peritoneal dialysis. The mesothelial cells facilitate rapid healing following any injury, which takes place very fast in matter of hours. Adhesions occur due to delayed or incomplete peritoneal healing.

ACUTE PERITONITIS

Types

- *Primary*
- *Secondary*
- *Tertiary*

PRIMARY PERITONITIS

- It is commonly due to pneumococci, and can occasionally be due to streptococci, haemophilus, gonococcus (rare now) and other gram-negative (*Escherichia coli*) organisms. It is common in young girls between 3-9 years of age group and also in women.
- Here there is no documented source of infection. Infection usually spreads from lower genitals through

fallopian tubes, from upper respiratory tract infection or from middle ear in males.

- It is uncommon after 10 years of age. It is common in malnourished child and child with nephritis. Child is toxic, severely ill and develops septicaemia very early.
- TC is very high, > 30,000/mm^3.

Treatment

- Diagnostic tapping, tube peritoneal drainage and laparoscopic drainage and wash are useful methods.
- Laparotomy and peritoneal toilet**.**
- Broad spectrum antibiotics including combination of aminoglycosides, cephalosporins and metronidazole.
- Local instillation of antibiotics, into the peritoneal cavity to achieve quick and effective results.

Mortality is high.

SECONDARY PERITONITIS

It is secondary to any bowel or other visceral pathology, e.g. perforation, appendicitis. *Escherichia coli* (70%) is the commonest organism involved. Other bacteria are – aerobic and anaerobic streptococci, Clostridium welchii, bacteroides, staphylococci, klebsiella, Salmonella typhi.

TERTIARY PERITONITIS

- It occurs after any abdominal surgeries, which is usually severe and the patient may go in for SIRS or MODS early.
- Tertiary peritonitis is defined as persistent or recurrent intra-abdominal infection after an adequate treatment for primary or secondary peritonitis – usually after 48 hours.

Bacteria Causing Peritonitis

a. *Bacteria from GIT—E. coli,* aerobic streptococci, streptococcus faecalis, staphylococcus, anaerobic streptococci, anaerobes (bacteroides), klebsiellla, Cl. welchii.
b. *Bacteria not from GIT*—Gonococcus, pneumococcus, are from fallopian tubes, commonly occurs in young females. Chlamydia, β-haemolytic streptococci, mycobacterium are few other bacteria which can cause peritonitis.

a. *Primary*	Monomicrobial, extraperitoneal source, blood spread
b. *Secondary*	Most common, polymicrobial, intra-peritoneal source
c. *Tertiary peritonitis*	Due to superadded infection following treatment of secondary/ primary

Most common bacteria during the phase of peritonitis is *E. coli* and during abscess formation is *B. fragilis. Mortality for diffuse peritonitis is 10%.*



Fig. 9.1: On table finding in a case of peritonitis with pus filled peritoneal cavity.

Mode of Infection

- Perforation of the GIT – duodenal/gastric/enteric/ colonic ulcers; Meckel's diverticulitis perforation.
- Penetrating or blunt trauma.
- Surgery.
- Drains.
- Dialysis.
- Foreign body.
- Appendicitis, cholecystitis, diverticulitis.
- Intestinal obstruction with strangulation.
- Via fallopian tubes.
- Through blood spread—in septicaemia.
- Transmural spread.
- Following uterine perforation/injury during abortion or termination of pregnancy.



Fig. 9.2: Duodenal ulcer perforation causing peritonitis.

Attack the problem, not the person.



Fig. 9.3: Jejunal perforation due to trauma. Trauma is the common cause for jejunal perforation. It is commonly blunt abdominal injury due to shearing force (traction injury) causing jejunal tear near duodeno-jejunal junction.



Figs 9.4A and B: Ileal perforation with severe peritonitis. Note the closure done horizontally. It could be typhoid perforation.

Factors affecting the spread of the infection in peritonitis:

a. Rapidity by which the pus is gushed into the peritoneal cavity, e.g. burst appendix, perforations
b. Amount of peristalsis (more the peristalsis more the spread)
c. Virulence of the organism
d. Localising action of the omentum (in children localisation is poor as omentum is small)
e. Immunosuppression—HIV, steroids
f. Anatomical nature of the peritoneal cavity
g. Age, associated diseases like malignancy, malnutrition, anaemia

Pathogenesis

- Lot of fluid is secreted into the peritoneal cavity which is infected, containing bacteria and toxins causing shock, toxaemia and its subsequent effects. Fibrinogen forms fibrin which tries to localise the infection. Bowel gets adhered to each other with fluid collecting between the loops. Thick flakes are formed adhering to the surface of the bowel. Peritoneum is thick, oedematous, becomes velvety and reddish with loss of its glistening appearance. Omentum is thickened, adherent. Often site of perforation may be identified by the location of the end of the omentum. Dilated bowel loops with site of obstruction/gangrene may be found. Pus, often with pockets may be present in subphrenic, paracolic and pelvic spaces.
- Peritoneal contents are initially sterile but eventually become infected in certain situations, as in acute pancreatitis, in haemoperitoneum, and in ruptured urinary bladder. It is due to transmural migration of bacteria.
- In perforated duodenal or gastric ulcers, contents in the peritoneal cavity are initially sterile but later get infected to form bacterial peritonitis.
- *Localized peritonitis* – Initially localisation of peritonitis occurs based on the anatomical factors like supracolic/infracolic compartments; greater omentum; paracolic gutters; dilated small bowel, etc. Pathological factors are thickened peritoneum, fibrin deposition, omental adhesions, reduced bowel peristalsis. Localised peritonitis may resolve by proper therapy. It may form abscess – pelvic/subphrenic. If it progresses it may form generalised peritonitis.

- *Diffuse peritonitis* sets in due to poor localisation, rapid peritoneal contamination, violent peristalsis, virulent organisms, immunodeficiency status, and small omentum in children (not properly developed in children). Diffuse peritonitis may occasionally get localized to form abscess. Mortality in diffuse peritonitis is 10%.

Clinical Features

- Sudden onset of pain.
- Fever, vomiting.
- Tenderness—initially localised later becomes diffused.
- Rebound tenderness—*Blumberg sign.*
- Guarding and rigidity, dull flanks on percussion.
- Tachycardia, tachypnoea.
- Tenderness on P/R examination.
- Distension with silent abdomen.
- Eventually leading to Hippocrates facies, septicaemic shock and loss of consciousness.
- Bowel sounds are absent due to paralytic ileus.
- Fever may be absent in severe peritonitis due to loss of pyrogenic reaction. Total count also may be very low in severe peritonitis.

Investigations

- Plain X-ray abdomen (in erect posture)—will show *ground-glass appearance* along with gas under diaphragm in the presence of perforation.
- Total count is increased.
- U/S abdomen—shows fluid in the abdominal cavity. Also clinches the other causes like haemoperitoneum, pancreatitis.
- Electrolyte study.
- Blood urea and serum creatinine.
- Four quadrant abdominal tap—reveals pus or infected fluid. In suspected pancreatitis fluid should be analyzed for amylase level (which will be high). Often US guided aspiration is better and more accurate.
- ***Diagnostic laparoscopy. It can also be used as therapeutic for duodenal ulcer perforation or primary peritonitis to give peritoneal wash.***
- CT scan is often useful to confirm the cause or to rule out conditions like pancreatitis.



Fig. 9.5: Plain X-ray abdomen showing gas under diaphragm. Perforation is the commonest cause of peritonitis.



Fig. 9.6: Multiple air fluid levels in plain X-ray abdomen—feature of intestinal obstruction.

Differential Diagnosis

- *Pancreatitis* – In pancreatitis back pain is common. But it is often difficult to differentiate clinically from acute peritonitis. Serum amylase is increased. CT abdomen may help in differentiating from peritonitis.
- *Intestinal obstruction* – There will be distension, vomiting and pain. Plain X-ray shows dilated bowel loops. CT scan confirms intestinal obstruction and its cause.

> *Better three hours too soon, than one minute too later.*

- *Ruptured ectopic pregnancy* – Urine pregnancy test will be positive. History of amenorrhoea is significant. Palor, tachycardia, lower abdominal pain and distension are common presentations. US abdomen and pelvis confirms the diagnosis.
- *Acute pyelonephritis* – Often clinically acute pyelonephritis mimics acute peritonitis. Guarding, tenderness, rigidity may be present in pyelonephritis also. Urinary symptoms, tender renal angle, urine microscopy revealing pus cells, US abdomen may confirm the diagnosis.
- *Acute mesenteric ischaemia* – Bloody diarrhoea, colicky pain, tender abdomen, toxicity are the features of mesenteric ischaemia. CT abdomen and angiogram are useful investigations.
- *Diabetic acute abdomen* –Patient with diabetes mellitus may present as acute abdomen. Free fluid in the flank may not be present. Patient may be ketotic also.



Fig. 9.7: Plain X-ray abdomen showing ground glass appearance—a feature of peritonitis.

Treatment

- Intravenous fluids for resuscitation are essential. It improves the tissue perfusion, corrects the hypotension and also improves the urine output. Normal saline, Ringer's lactate are usually used. Usual requirement is 2 ml/kg/hour.
- Nasogastric tube aspiration—to decompress bowel; to reduce toxic fluid; to prevent aspiration.
- Total parenteral nutrition, CVP line to perfuse and to monitor.
- Blood transfusion.
- Catheterisation with maintenance of adequate urine output (30 ml/hour) (0.5 ml/hour/kg).
- Antibiotics—Ampicillin, gentamicin, metronidazole, ceftazidime, cefoperazone, cefotaxime, tazobactum, piperacillin, meropenem, linezolid, etc.
- Nasogastric aspiration.
- Surgical correction of underlying cause.
- Use of dopamine, steroids, and management of shock.
- Often ICU and ventilator support is required during postoperative period.
- Monitoring the patient using PO_2, PCO_2, electrolytes, and pulse oximeter.



Figs 9.8A and B: X-ray showing gas under diaphragm due to perforation. Ground glass appearance of peritonitis is seen in another X-ray.

Laparotomy and proceed

On laparotomy, the cause for peritonitis is identified and corrected.

- In bowel perforation—perforation closure.
- In intestinal obstruction—resection and anastomosis.
- In appendicitis—appendicectomy.
  - Proper peritoneal toilet (wash with 10 litres of saline) is given. A drain is placed (tube).

  - Pus should be sent for culture and sensitivity.
  - Tension sutures are placed when required to prevent burst abdomen.
- *Laparostomy* may be *open or closed method*. In *open method,* (Ettapan's lavage) abdominal wall / fascia and peritoneum are not sutured but kept open. It will reduce the chances of abdominal compartment syndrome and also allows easier and faster drainage of the infected fluid from the peritoneal cavity. But disadvantages are it causes lot of fluid loss and electrolyte imbalance and open area itself may allow infection to get into the peritoneal cavity. In *closed method,* abdominal fascial wound is closed using a zip. It facilitates the regular washing of the peritoneal cavity with normal saline without contaminating the cavity from outside and reduces the unnecessary fluid loss. But it may cause abdominal compartment syndrome.

Technique of emergency laparotomy

Abdomen is opened with midline incision (with wide exposure), often extending both above and below the umbilicus, with incision inclined towards the left side at umbilicus. Once peritoneum is opened gushing pus is removed using suction. Pus is collected for culture. Abdominal cavity is inspected thoroughly for site of origin of sepsis – appendicitis/perforation/gangrene, etc. Definitive procedure is done depending on the cause. Proper wash is given using normal saline (10 litres). Drain should be placed. Wound is closed with tension sutures using non-absorbable monofilament sutures (zero or one number).



Fig. 9.9: Vertical midline incision is used for emergency laparotomy in peritonitis. Lengthy incision with wide exposure of the peritoneal cavity is advisible.



Figs 9.10A and B: Severe peritonitis showing pus in the peritoneal cavity.

Postoperative management

- Proper critical care (ICU) postoperatively.
- Ventilatory support; monitoring with urine output, temperature, breathing, pulse rate, blood pressure, arterial blood gas analysis, total count estimation (both very high and very low counts signify severe sepsis/septicaemia), neutrophil count estimation, platelet count, prothrombin time analysis, blood urea and serum creatinine, liver function tests (altered liver function signifies septicaemia). These investigations need to be repeated as and when required.
- Proper fluid and electrolyte management.
- Total parenteral nutrition (TPN).
- Prevention of deep vein thrombosis by leg exercises, low molecular weight heparin.
- Prevention/identification of ARDS and its management.
- Prevention of bedsore.

Eyes are more accurate witness than ears.—Hiraclitus.



Fig. 9.11: Abdomen is closed with tension sutures in case of peritonitis using monofilament non-absorbable sutures to prevent postoperative burst abdomen. Drain also should be placed into the peritoneal cavity.



Fig. 9.12: Postoperative patient with tension sutures with fistula and leak. Patient has undergone resection and anastomosis for gangrene bowel.

Terminal Features in Peritonitis

a. *Hippocratic facies*—bright, hollow eyes; pale, pinched face; cold perspiration in eye brows; dry, fissured tongue; blue lips. Patient will be in severe shock. It signifies terminal status with high mortality rate. It is a typical facial sign of *severe end stage peritonitis.*
b. Septic shock (cold stage).
c. Systemic Inflammatory Response Syndrome (SIRS).
d. Multi-organ Dysfunction Syndrome (MODS).

Complications and Sequelae of Peritonitis

- Septicaemia.
- Paralytic ileus, adhesions, intestinal obstruction.
- Respiratory infection.
- ARDS, bronchopneumonia.
- Electrolyte imbalance, DVT.
- Renal failure.
- MODS.
- DIC.
- Formation of subphrenic abscess, pelvic abscess and other intra-peritoneal abscess.
- Burst abdomen; biliary/gastric/enteric/faecal fistula formation; later incisional hernia.

SPONTANEOUS BACTERIAL PERITONITIS (SBP)

It is seen in –

- Infants and children commonly.
- In nephritic syndrome.
- In adults, with cirrhosis.
- In patients who has undergone splenectomy.
- Patients with ascites due to any cause.
- Malnutrition and malignancy.

Causative Organisms

- Gram-negative bacilli (70%)—E.coli, Klebsiella.
- Gram-positive cocci (20%)—Pneumococci, streptococci and enterococci.
- Anaerobes (10%).
- In girls it is commonly through fallopian tubes. In males it is always blood born from respiratory tract infection or otitis media.

Features

- Features of peritonitis but initially with dull aching pain.
- Features of shock.
- Common in girls.
- High fever with neutrophilia is characteristic.
- Profuse diarrhoea is common.
- Features relevant of cause.
- Total count, LFT, U/S is useful tool.

Note:
Scoring of the severity of the peritonitis is done based on age, sex, duration, cause, origin, content, general condition, haematocrit, electrolytes, O_2 saturation, blood urea, serum creatinine.

1. Mannheim peritonitis index.
2. Acute physiology and chronic health evaluation score (APACHE score).

Management

- Usually conservative with proper higher generation antibiotics.
- Tapping of the purulent fluid from the peritoneal cavity.
- Laparoscopy is useful method.
- Often peritoneal purulent fluid tube drainage may be beneficial.
- Laparotomy and peritoneal wash.
- Condition has got high mortality.

Note:

- Exudate in pneumococcal peritonitis is odourless, turbid and sticky.
- Exudate in streptococcal peritonitis, is odourless, thin, blood stained with flecks of fibrin. Greenish watery diarrhoea is common. It is common in infants and children. Upper respiratory tract infections, tonsillitis, pharyngitis are the causes. It is treated with penicillins, amoxycillins, cephalosporins.
- Staphylococcus aureus peritonitis is common in those who use intravaginal tampons causing toxic shock syndrome and DIC.

SCLEROSING PERITONITIS

It is usually Practolol (β blocker) induced peritonitis. It is fibrinous peritonitis causing thickening of bowel and other contents of abdomen. It leads to intestinal obstruction and malnutrition.

BILIARY PERITONITIS

Causes

- Trauma.
- Postoperative leak after surgery for gallbladder, CBD, duodenum, ERCP, pyloroplasty.
- Perforation of gallbladder or CBD.
- Gangrenous cholecystitis and rupture.
- Idiopathic.
- Leakage from accessory bile duct after surgery; leakage from displaced T tube or displaced percutaneous stent.

Clinical Features

- Features of peritonitis—abdominal distension, guarding and rigidity.
- Jaundice.
- Toxicity.
- Features of shock.

Investigations

- X-ray abdomen.
- Diagnostic peritoneal lavage.

Treatment

- Laparotomy, wash, drainage.
- Cause to be treated.
- It has got high mortality.
- It may get localise and form abscess or may lead in to biliary fistula.

POSTOPERATIVE PERITONITIS

- It is the development of peritonitis in postoperative period, either due to anastomotic leak, or biliary leak; and there is collection of pus in the peritoneal cavity including interloop areas.
- It is often difficult to differentiate it from postoperative urinary infection, respiratory infection like bronchopneumonia, cardiac causes in old people, and infection in other areas like intravenous cannula site (thrombophlebitis). Symptoms may mask if patient is on steroid therapy.
- In all abdominal surgeries patient initially develops paralytic ileus which lasts for 3-5 days. If it persists or progresses one should suspect postoperative peritonitis. Other suspicious features are – persisting toxaemia in spite of antibiotics, oliguria, pyrexia, altered liver functions, altered total WBC count (very high as well as very low and neutrophil count is more specific) and increasing leak from drain site either fecal/intestinal/biliary, increase in abdominal distension, pain and tenderness. Leak may be due to sepsis, hypotension in pre/per and postoperative period, hypoxia, blood loss, ischaemia of bowel and friability of bowel wall, and specific causes like tuberculosis, malignancy or Crohn's disease. Often multiple areas of the bowel become necrotic which eventually causes leak. Leak from multiple sites is difficult to manage and has got poor prognosis.

Management

- Immediate US or CT abdomen to find out the abdominal cause, total count, assessment of urinary parameters like blood urea and serum creatinine, liver function tests.
- Immediate exploration is the only way to save the life of the patient. Proper exploration with wide exposure of the abdomen, is done to identify the cause for

A friend should be a second identity.

infection is done. Resuturing of the anastomotic site can be done but chances of releak are more likely. It can be done, if leak site is small and less friable. Otherwise either ileostomy or colostomy is the better choice. Often continuous tube irrigation and drainage is needed to clear the infective material. Laparostomy using zip technique is also beneficial. Multiple cavities with multiple abscesses are often found which should be drained and irrigated adequately with normal saline. Extensive bowel necrosis is the finding often observed which needs massive bowel resection that leads to short bowel syndrome which is difficult to manage on long-term basis. Higher antibiotics like piperacillin, meropenem are required. Ventilator support, total parenteral nutrition (TPN) haemodialysis support and critical care management is required. Postoperative peritonitis has got high mortality and morbidity.

OTHER FORMS OF PERITONITIS

1. Meconium peritonitis.
2. Chronic bacterial peritonitis—tuberculous.
3. Chronic nonbacterial peritonitis—granulomatous peritonitis due to talc or starch (from surgical gloves)—starch peritonitis.
4. Gonococcal peritonitis with perihepatitis—*Curtis—Fitz-Hugh syndrome.*
5. *Familial periodic peritonitis* (Familial mediterranean fever). A rare entity gets recurrent pain abdomen often after appendicectomy. It is familial, common in Arabs, Americans and Jewish populations. Specific gene produces a protein – pyrin from neutrophils in these patients. Peritoneum adjacent to spleen and gallbladder are inflamed. But these two organs are normal. It is common in children and common in girls/females. Pain is usually in upper quadrant, left side. There is localised peritoneal inflammation. It is treated conservatively using colchicines.
6. *Parturition/abortion peritonitis* – It occurs after delivery and abortion conducted without asepsis and instrumentation, incomplete instrumental abortion, uterine perforation with or without bowel injury. It causes pelvic peritonitis commonly, generalized peritonitis often. It is due to anaerobic bacteria, anaerobic streptococci, and gram-negative bacteria like Escherichia coli. It is often rapidly progressive causing septic shock. It needs emergency surgery. Complications are ARDS, intestinal obstruction, faecal fistula and intraperitoneal abscess formation.



Fig. 9.13: Perforation in the fundus of the uterus due to attempted abortion. It caused severe peritonitis.

PELVIC ABSCESS

- It is the most common intraperitoneal abscess (50-60%).
- It is the collection of pus in rectovesical or rectouterine pouch (Pouch of Douglas).



Fig. 9.14: Pelvic abscess.

Causes

- Appendicitis.
- Pelvic infections.
- Sequelae of diffuse peritonitis.
- Postoperative and other abdominal causes.

Bacteria: Bacteroides fragilis, *E. coli*, anaerobic streptococci.

Waltman-Walters syndrome: It is postcholecystectomy fluid collection in subphrenic space causing compression over IVC. It mimics coronary thrombosis.

Clinical Features

- Diarrhoea.
- Mucus discharge per rectum.
- High temperature with chills and rigors.
- Lower abdominal pain and distension.
- Frequency and burning micturition.
- P/R shows a soft, boggy, and tender swelling in the anterior wall of the rectum.

Investigations

- TC is raised.
- U/S is diagnostic—shows pus in rectovesical or pouch of Douglas.
- CT scan to find out the size and extent.



Fig. 9.15: CT pelvis showing pelvic abscess.

Treatment

- After starting antibiotics, under G/A, abscess is drained **per rectally**, through the boggy area. Catheter is passed to the bladder before draining the pus.
- In females, *posterior colpotomy* is done to drain the *pus*.
- Occasionally spontaneous rupture of the abscess into the rectum occurs leading to natural regression.
- When abscess is very large, when it is progressing into the general peritoneal cavity or when in doubt, laparotomy through lower abdomen incision is done to drain the pus and to correct the cause. Often in such cases, drainage tube can be placed through the abdomen under U/S guidance.
- But most often laparotomy is not necessary.

SUBPHRENIC SPACES AND SUBPHRENIC ABSCESS

Surgical Anatomy (Fig. 9.17)

There are four intraperitoneal and three extraperitoneal spaces.


Intestine
Pelvic abscess
Rectum
Urinary bladder
Drainage through anterior wall of the rectum
In male patient
A
Urinary bladder
Uterine cavity
Intestine
Pelvic abscess
Rectum
In female patient
Posterior colpotomy to drain pelvic abscess
B

Figs 9.16A and B: In male, pelvic abscess is drained through an incision over the anterior aspect of the rectum. In female, it is drained through posterior colpotomy.


1
7
2
3
GB
4
5
6
1.Rt anterior space
2. Lt anterior space
3. Lt posterior space
4. Rt posterior space
5. Rt perinephric space
6. Lt perinephric space
7. Bare area of the liver

Fig. 9.17: Subphrenic spaces.

The mother's heart is child's schoolroom.—Henry Ward Beecher.

Intraperitoneal Spaces

Right anterior intraperitoneal space (Right subphrenic space): It is bounded by right lobe of the liver and diaphragm, posteriorly by anterior layer of coronary and right triangular ligament, and to the left by falciform ligament.

Causes: Abscess here occurs due to cholecystitis, perforated duodenal ulcer, postoperative, appendicitis, duodenal cap blow out.

Right posterior intraperitoneal space (Right subhepatic space): (*Rutherford Morison's kidney pouch*) is bounded in front by the liver and gallbladder, above by the liver, behind by the right kidney and diaphragm, below by the transverse colon and hepatic flexure, to the left by foramen of Winslow and duodenum. It is large and deepest space of all. *It is the commonest site of subphrenic abscess.*

Causes: Appendicitis, cholecystitis, postoperative, perforated duodenal ulcer, intestinal obstruction.

Left anterior intraperitoneal space (Left subphrenic space): It is bounded above by the diaphragm, behind by left lobe of liver and left triangular ligament, gastrohepatic ligament and anterior surface of the stomach, to the right is the falciform ligament.

Causes for abscess here are surgeries of the stomach, tail of the pancreas, spleen, colon (splenic flexure), diverticulitis.

Left posterior intraperitoneal space: It is bounded by stomach, pancreas, greater omentum, liver, transverse colon (Lesser sac).

Most common *cause* here is pseudo-cyst of pancreas. Rarely perforated gastric ulcer.



Fig. 9.18: Common causes of subphrenic abscess both right and left. Subphrenic abscess is common on right side.

Extraperitoneal Spaces

Right extraperitoneal space is right perinephric space **and left extraperitoneal space** is left perinephric space.

Causes: Abscess here are due to tuberculosis, trauma, haematoma.

Midline extraperitoneal is *bare area* of the liver. Pus collects here commonly due to ruptured amoebic liver abscess and pyogenic abscess of the liver.

Pathology of Subphrenic Abscess

- During inspiration, intraabdominal pressure (especially in subphrenic area) is reduced and so this with capillary action and upward movement of the diaphragm make the peritoneal fluid to move upwards towards the diaphragm. This is the reason why there is higher incidence of subphrenic abscess and *subphrenic abscess is the second most common type of intra-abdominal abscess,* first one being the pelvic abscess.
- Subphrenic abscess is more common on the right side than on left (left anterior) because infective conditions are more common on the right side (like appendicitis /perforation/liver abscess/cholecystitis); and right paracolic gutter is wide and deep without any barrier (unlike left side paracolic gutter which is narrow and limited above by colophrenic ligament). Left posterior space is lesser sac in which infected fluid commonly collects following pancreatitis. Right subphrenic abscess causes elevation of the diaphragm. Pus collects in front or posterior aspect of the liver (right anterior or right posterior spaces) or often in both. Pus may be in a single cavity or may be multiloculated. Occasionally pus may get thickened to form a thick fibrous wall around leading into a chronic stage which causes generalized ill health. Pus gets well localized with a thick pyogenic membrane pushing pleura away and above and peritoneum away and below making subphrenic abscess essentially *extraserosal*. Because of the congestion/hyperaemia of the pleura and elevation of the diaphragm, there will be *sympathetic pleural effusion* on the side of the abscess. In severe acute subphrenic abscess, empyema thorax can also occur.
- If infective organism is gas forming one, abscess will contain pus with gas. So it is resonant above the liver dullness; dull above it due to collapsed lung/ atelectasis; then again resonant on topmost due to normal lung. (From below upwards – dull liver – resonant gas in abscess cavity- dull collapsed lung – resonant normal lung topmost). But it is rare presently.
- *Postoperative surgeries*–mainly of gastric/biliary/ colonic and emergency surgeries (peritonitis) are becoming commonest cause of the subphrenic abscess.

Clinical Features

Barnard's aphorism (Harold Barnard)—
"Pus somewhere, pus nowhere else, pus under diaphragm".
History relevant of the specific causes; history of any previous surgery:

- Fever with chills and rigors.
- Pain in right hypochondrium, epigastrium or lower thorax.
- Tenderness in right hypochondrium.
- Sympathetic right sided pleural effusion due to congestion and hyperaemia of the diaphragm.
- Collapse of the lung/basal atelectasis – right side may be evident. Tachypnoea and respiratory distress can be observed.
- Pain in the right shoulder due to irritation of phrenic nerve.
- Hiccough, tachycardia.
- ***Hoover's sign***: Scoliosis towards same side in subphrenic abscess.
- Wasting and anorexia is common.
- Occasionally tender mass in the right hypochondrium may be palpable.
- Tenderness over 11th intercostal space may be evident in right subhepatic space abscess.

Bacteria causing:

- *E. coli.*
- Klebsiella.
- Streptococci.
- Anaerobic organisms.

Differential diagnosis

a. Amoebic liver abscess
b. Pylephlebitis
c. Empyema
d. Pulmonary collapse

Investigations

- Plain X-ray chest and abdomen shows soft tissue shadow, pleural effusion, tenting of diaphragm, collapse of the lung. Fluoroscopy shows elevated right diaphragm with reduced right sided diaphragmatic movement.
- U/S abdomen confirms the diagnosis.
- TC is high. There is raise in 'C' reactive protein.
- CT scan is very useful to find out the extent and relation. CT shows 'rind' sharp outer margin; septations; size, shape, extent, diaphragmatic position, pleural changes, displaced bowel and other organs and communications.
- Gallium 67 or Iridium 111 isotope imaging.



Fig. 9.19: CT scan of abdomen showing subphrenic abscess.

Treatment

- **Antibiotics:** Ampicillin, Metronidazole, Gentamicin, Cephalosporins.
- **Percutaneous drainage:** Initially ultrasound guided aspiration is useful. Here, under ultrasound or CT guidance, a catheter is placed and pus is drained. Catheters used are pigtail catheter, 16 French trocar catheter or sump catheter. 90% of subphrenic abscess are drained percutaneously.
- **Open drainage is indicated** (Required in 10-20% of cases) in—
  - When symptoms persist
  - When abscess increases in size
  - When aspiration fails, because of thick pus or multiloculated abscess
  - Failure of/contraindications for catheter drainage
  - Multiple abscesses
  - Presence of foreign body/necrosis/haematoma/obstruction/fistula
- Under G/A through anterior or posterior subcostal incision, abscess is approached extraperitoneally and extrapleurally (extraserosally), so as to prevent serosal contamination. Pyogenic membrane is opened, pus is collected for culture sensitivity. Pus is drained by breaking all loculi. Malecot's catheter is placed in situ.
- Both *anterior and posterior extraperitoneal approaches* are used. Posterior approach allows dependent drainage; anterior approach (Clairmont approach for left side) is technically easier and allows proper assess.
- *Transperitoneal approach* is needed whenever definitive procedure has to be undertaken like managing the existing fistula, treating the cause, removal of foreign body, etc.

A superior man is modest in his speech, but exceeds in his actions.

- Antibiotics are continued. Malecot's catheter is removed once pus stops draining, usually after 14 days, which can also be confirmed by U/S abdomen or by X-ray with injection of dye.
- Good nutritional supplement, respiratory physiotherapy are additional support required.

Catheters used for drainage are:

- Malecot's catheter/wide Foley's catheter when open drainage is done
- Pigtail catheter
- Catheter placement through trocar under guidance (16 French trocar catheter)
- Sump catheter (double lumen tube which allows irrigation as well as suction drainage)

Note: Catheter is removed when pus drainage from the tube is <10 ml/day, normal total count, improvement in symptoms, U/S shows clearance of abscess cavity.

Complications

- Empyema.
- Respiratory arrest.
- Septicaemia.
- Sinus formation.
- Recurrence.
- Peritonitis.



Fig. 9.20: Subphrenic abscess open drainage. Incision must be extraserosal. Malecot's tube is placed in the abscess cavity.

MESENTERIC CYSTS

Causes

1. Chylolymphatic.
2. Enterogenous.
3. Cysts of urogenital remnant.
4. Teratomatous dermoid cysts.
5. Other causes:
    - Traumatic haematoma and cyst formation.
    - Tuberculous cold abscess of mesentery.
    - Hydatid cyst of mesentery.

Chylolymphatic cysts are the commonest one.

- It arises from congenitally misplaced lymphatic system.
- Common in ileum, is a thin walled cyst with flat endothelium occasionally containing lymph or chyle, which is either milky or cream coloured.
- It is solitary and commonly unilocular, with loop of the bowel in front.
- It has got independent blood supply, i.e. not from the adjacent bowel loop. So enucleation can be done without resecting bowel.

Enterogenous type arises as a diverticulum or duplication from the adjacent bowel.

Hence it is a thick walled cyst (contains all layers of the bowel) and receives its blood supply from the adjacent bowel (not independent). So resection of the adjacent bowel along with the cyst is essential. Enucleation is contraindicated.



Fig. 9.21: Mesenteric cyst.

Clinical Features

- It presents as a painless abdominal swelling in umbilical region, smooth, fluctuant, not moving with respiration.



Fig. 9.22: Mesenteric cyst.

- It is common in 2nd decade, often in childhood.
- It is freely mobile, mobile in the direction perpendicular to the line of mesentery.
- There is a band of resonance in front of the cyst.
- Presentation as complications.

Tillaux's triad

1. Soft, smooth swelling in the umbilical region
2. Freely mobile in a direction perpendicular to mesentery
3. Zone of resonance in front



Fig. 9.23: Mobility of mesenteric cyst.

Complications of mesenteric cysts

1. *Torsion of cyst* can lead to volvulus of the adjacent bowel
2. *Rupture of the cyst*
3. *Haemorrhage* into the cyst
4. *Infection*—Patient presents with acute painful swelling in umbilical region

Investigations

- U/S abdomen.
- Barium meal X-ray.
- Plain X-ray abdomen.
- CT scan of the abdomen is diagnostic.

Differential Diagnosis

- Hydronephrosis.
- Omental cysts.
- Tuberculosis.

Treatment

- In chylolymphatic cyst—*enucleation.*
- In enterogenous type, removal of the cyst with resection of adjacent bowel is done, because blood supply is from adjacent bowel.

PERITONEAL CARCINOMATOSIS (Carcinoma peritonei)

- Entire peritoneal cavity is studded with carcinomatous nodules—both parietal and visceral peritoneum
- Haemorrhagic ascites, interloop bowel adhesions, hard studded nodules in the omentum are common. Intestinal obstruction can occur
- It may be primary peritoneal carcinomatosis (mesothelial) or secondary from GIT, ovary, breast, pancreas
- Liver secondaries are often present
- It mimics peritoneal tuberculosis, acute pancreatitis, and multiple lymphomatous nodules, multiple peritoneal hydatids
- As malignant ascitic fluid contains high immunoglobulin, peritonitis is not common
- Instillation of radioactive gold and chemotherapy are the treatment
- It has got poor prognosis

Self-assessment Questions

1. Discuss subphrenic space anatomy and subphrenic abscess.
2. Etiology, clinical features and management of peritonitis.
3. Primary peritonitis.
4. Peritoneal lavage.
5. Mesenteric cyst.
6. Tillaux triad.
7. Pelvic abscess.

Clothe yourselves with compassion, kindness, humility, meekness and patience.

10

Abdominal Tuberculosis

> ***In man the balance between immunity and susceptibility to tuberculosis is delicately adjusted: There is a small factor of safety.***
>
> ***—Milton Rosenau, 1927***

It is common in India and developing countries.
It is the 6th most common type of extra pulmonary tuberculosis. Its incidence is high in HIV infected patients.

Types

1. *Intestinal*
   Ileocaecal region
   - Ulcerative—60%.
   - Hyperplastic.
   - Ulcero-hyperplastic.

   Ileal region, commonly—
   - Stricture type.
2. *Peritoneal tuberculosis*
   a. Acute.
   b. Chronic.
      1. Ascitic type.
      2. Encysted (loculated) type.
      3. Plastic (Fibrous/adhesive) type.
      4. Purulent type.
3. *Tuberculosis of mesentery and its lymph nodes.*
4. *Ano-recto-sigmoidal*—Present as fistula, fissure, abscess, mass.
5. *Involvement of liver, spleen and other organs as a part of miliary tuberculosis.*
6. *Tuberculosis of the omentum.*
7. *Rare types:* Oesophageal (0.2% of abdominal tuberculosis)/gastroduodenal (1% of abdominal tuberculosis)/retroperitoneal tuberculosis. Because of hydrochloric acid (acid media) gastric tuberculosis is rare.

Note:
- Chronic peritoneal tuberculosis may be associated with pleural effusion and pericardial effusion.
- Tuberculosis is not common in stomach, duodenum and jejunum.
- *Diffuse tuberculous colitis* is less commonly seen (4%), mimics ulcerative colitis in every respect even in colonoscopy. Patient recovers well with antitubercular drugs.
- *Intestinal tuberculosis is called as **Koenig's syndrome** (1892).*

Modes of Spread of Abdominal Tuberculosis

- By ingestion
  – Ingestion of food contaminated with tubercle bacilli causing *primary intestinal tuberculosis*.
  – Ingestion of sputum containing tuberculous bacteria from primary pulmonary focus causing *secondary intestinal tuberculosis.*
- Haematogenous spread from tuberculosis of lungs.
- From neck lymph nodes (tuberculous cervical lymphadenitis – 5-10%) through lymphatics.
- From fallopian tubes by retrograde spread to involve peritoneum (10%).

ILEOCAECAL TUBERCULOSIS

Most common site of abdominal tuberculosis due to presence of Peyer's patches; and stasis of luminal contents favoured by ileocaecal valve.



Figs 10.1A and B: Ileocaecal tuberculosis. Note the multiple transverse undermined ulcers in one photo. In another photo note ileocaecal tuberculosis with stricture.

Causative organism

Mycobacterium tuberculosis

- Acid fast 20% H_2SO_4
- Alcohol fast
- Gram neutral

Histology

- Epithelioid cells diagnostic
- Langhan's giant cells
- Features of granuloma
- Caseating necrosis



Fig. 10.2: Obtuse ileocaecal angle—Ileocaecal tuberculosis.

It is presently due to Mycobacterium tuberculosis, earlier used to be due to *Mycobacterium bovis.* Mode of infection may be direct or blood spread, usually from lungs.

Types (Refer Table on Page No. 518)

- *Ulcerative—commonest 60%. Circumferential transverse often multiple 'girdle' ulcers* - with skip lesions. It is common in old, malnourished people. Long standing ulcers cause fibrosis and later stricture formation. Stricture (*Napkin ring stricture*) is common in ileal part. Often related intestinal nodes are also involved with caseation, abscess (cold) formation. Bowel adhesions are common. Patient mainly presents with diarrhoea, blood in stool, loss of appetite and reduced weight.
- *Hyperplastic*—Fibroblast reaction in submucosa and subserosa causing thickening of bowel wall and lymph node enlargement, leading to nodular mass (tumour-like) formation. It is 10% common, less virulent, with adequate host resistance, seen in young well nourished individuals. It is common in caecal part. It causes extensive chronic inflammation, fibrosis, bowel adhesions, nodal enlargement, often presents with mass in the right iliac fossa. Caseation necrosis is not common. When present as a mass, it can cause subacute intestinal obstruction. It is commonly primary intestinal tuberculosis. There is no primary focus in the lungs.
- *Ulcero-hyperplastic* – 30%.

Clinical Features

- Abdominal pain is the most common symptom (90%). It is dull in mesenteric type; colicky in intestinal type.
- Common in 25-50 years age group. Equal in both sexes.
- Anaemia, loss of weight and appetite (80%).
- Diarrhoea—10-20%.
- Fever—50-70%.

> *Phthisis is an ulcer of the lung that consumes the whole body.*—Bernard de Gordan, 1495

- *Mass in right iliac fossa*, (35%) which is hard, nodular, nonmobile, nontender with impaired resonance, which may mimic carcinoma caecum. Subacute obstruction can occur.
- Ileocaecal tuberculosis can be associated with adenocarcinoma of caecum, or large bowel lymphoma or HIV.
- Often ileocaecal TB can cause intestinal obstruction (20%).

Ileocaecal region is common site due to

- Stasis
- Abundant Peyer's patches - organisms get trapped in Peyer's patches
- Bacteria contact time with mucosa is more
- M cells in Peyer's patches phagocytose bacilli and transfer to host cells
- Liquid content in the region
- Increased rate of fluid and electrolyte absorption
- Minimal digestive activity

Differential diagnosis

- Carcinoma caecum
- Ameboma
- Appendicular mass
- Ectopic kidney
- Retroperitoneal tumour
- Lymph node mass
- Psoas abscess
- Crohn's disease

Investigations

- Chest X-ray to find out primary focus.
- Mantoux test, ELISA (90%), SAFA (soluble antigen fluorescent antibody – 80%), serum IgG.
- ESR is raised.
- U/S abdomen to see ascites, caecal thickening, nodal status and other organs.
- Plain X-ray abdomen, if presentation is of intestinal obstruction. It often shows calcification. It shows calcified lesion in the bowel; in the lymph node; in the liver (calcified granuloma). Perforation when it occurs (rare) shows gas under diaphragm.

Barium study X-ray (Enteroclysis followed by barium enema or barium meal follow through X-ray)

- Pulled up caecum
- Obtuse ileocaecal angle
- Hurrying of barium due to rapid flow and lack of barium in inflamed segment (*Steirlin sign*)
- Narrow ileum with thickened ileocaecal valve *(Fleischner sign) (Inverted umbrella sign)*
- Calcifications
- Incompetent ileocaecal valve
- Ulcers and strictures in the terminal ileum and caecum—*Napkin lesions*
- Earliest signs are – increased transit time; hypersegmentation (chicken intestine); flocculation of barium
- Other signs are – persistent narrow stream (string sign); multiple strictures with enormous dilatation of proximal ileum (mega ileum); straightening of ileo caecal junction with 'goose neck' deformity



Fig. 10.3: Ileocaecal tuberculosis or tuberculous mesenteric lymphadenitis can present as mass in the right iliac fossa which is usually nontender, nonmobile, hard/firm resonant/impaired resonant.

- Colonoscopy is of value to rule out carcinoma. It is easiest and most direct method in establishing the diagnosis. Colonoscopy shows mucosal nodules or ulcers; caecal and ileal strictures; deformed ileo caecal valve; mucosal oedema and pseudopolyps and occasionally diffuse colitis. Biopsy can be taken to confirm the diagnosis.
- Capsule endoscopy is also useful to see small intestinal (tuberculous) pathology in difficult cases.
- FNAC of palpable mass.
- Laparoscopy is very useful method of investigation. Transabdominal peritoneoscopy is visualization of the peritoneal cavity using endoscope through a small incision in the abdomen. It aids in visualization, to collect ascitic fluid for analysis and to take biopsy. Biopsy can be taken from omentum, peritoneum, nodes and suspected areas. Ascitic fluid can be collected for analysis.
- Abdominal CT scan is better and more reliable.
- PCR assay of endoscopically biopsied tissue or of ascitic fluid. DNA – PCR can detect 1-2 organism or 8fg of mycobacterial DNA. Positive PCR signifies infection but need not be active disease.

- Stool culture for AFB - not useful. Presence of tuberculous bacteia in stool does not signify disease.
- Blind percutaneous needle peritoneal biopsy using *Cope's/Abraham's needle* is also practiced.
- Ascitic tap fluid analysis.
- Anticord factor antibody to differentiate it from Crohn's disease.
- Biochemical assay – proteins, ADA (Adenosine Deaminase Activity) and interleukins. ADA is specific and sensitive marker with 95-98% sensitivity and specificity. Its value more than 33 IU/litre in ascitic fluid and more than 42 IU/litre in serum is significant. Gamma interleukin is two times more expensive than ADA.



Figs 10.4A and B: Pulled-up caecum, obtuse ileocaecal angle—ileocaecal tuberculosis barium study X-ray.

Ascitic fluid in abdominal tuberculosis

- Exudate with protein level > 2.5 g/dl
- Serum-ascitic fluid albumin gradient is < 1.1
- Lymphocyte predominant cells with count as high as 4000/mm^3 > 250/cumm
- AFB in ascitic fluid is seen only < 3% cases
- ADA (Adenosine deaminase activity) in ascitic fluid (95% specificity and 98% sensitivity)
- Specific gravity >1.016
- Glucose < 30 mg
- Decreased pH
- LDH more than 90 units/litre

Ultrasound features observed in abdominal tuberculosis

- Thickened bowel wall, mesentery, omentum, peritoneum
- Loculated ascites with fine septae
- Interloop ascites with alternate echogenic and echofree areas—Club-sandwich appearance
- Bowel loop radiates from its mesenteric root—*stellate sign*
- Mesenteric thickness *more than 15 mm*
- Hepatosplenomegaly
- Lymph nodal enlargement matted
- Pulled up caecum presenting with a mass in subhepatic region and also sonologically visible - "pseudokidney sign"
- Concentric uniform mural thickening

CT scan in abdominal tuberculosis

- It is very useful and reliable investigation
- It is done with oral contrast – CT enteroclysis
- Findings are –
  - Thickened bowel wall, thickened peritoneum
  - Ileocaecal valve thickening
  - Enlarged/necrosed/matted mesenteric nodes often with cold abscess
  - Adhesions
  - Mesenteric thickening and nodules
  - Nodules in the peritoneum/solid organs like liver
  - Adhesions in the bowel/stricture/dilatations of the bowel/features of obstruction
  - Loculated ascites
- CT guided FNAC/biopsy/aspiration of fluid can be done

Complications of abdominal tuberculosis

a. Obstruction - 20%
b. Malabsorption, blind loop syndrome
c. Dissemination of tuberculosis to other areas of abdomen as well as extra-abdominal sites
d. Faecal fistula
e. Cold abscess formation
f. Haemorrhage, perforation (rare)

Note: Perforation is **rare** in GIT tuberculosis **but can occur**.

> *Whilst meagre Pthisis gives a silent bow, her strokes are sure, but her advances slow. No loud alarms, nor fierce assaults are shown. She starves the fortess first, then takes the town.* —Samuel Garth



Figs 10.5A and B: CT scan of abdomen showing features of abdominal tuberculosis.

Treatment

Drugs

- INH; Rifampicin; Pyrazinamide; Ethambutol – *first line drugs*. In drug resistance cases second line drugs are needed. WHO recommends 6-9 months course. Commonly patient presents with complications and late presentations are also common in many. So, more often treatment for one year may be required in these patients. Recurrent abdominal tuberculosis has got high mortality and difficult to manage.
- As they are malnourished supportive therapy in the form of TPN, blood transfusion in preoperative as well as postoperative period is required. Often steroid is used to prevent adhesions along with antituberculous drugs.

Surgery

Indications for surgery

- Intestinal obstruction.
- Severe haemorrhage.
- Acute abdominal presentation like perforation.
- Intraabdominal abscess formation or fistula formation.
- Uncertain diagnosis.

Surgeries are –

- *Limited ileocaecal resection* (with 5 cm margin) is the surgical therapy of choice for ileocaecal tuberculosis. This may be done in initial period depending on the obstructive and other presentations. Often during therapeutic period, healing with fibrosis causes stricture and obstruction in 3-6 weeks after drug therapy. Patient during this time needs limited ileo caecal resection.
- In single ileal stricture – stricturoplasty may be done. But if bowel wall is oedematous and friable then resection would be the ideal choice.
- In multiple strictures resection of ileum and anastomosis is done (ideal). Multiple strictures with long segment gaps between each can be treated by multiple stricturoplasty. But viability of the sutured area should be ensured. Resection is better option for stricture within 10 cm of ileocaecal valve.
- In perforation of ileal bowel, resection and anastomosis is done. Biopsy from perforation site and closure can be done in early perforations but chances of leak and fecal fistula formation is high (due to closure of perforation over a diseased bowel) and so resection is better option. In severely contaminated peritoneum, resection and exteriorization is done. Bowel continuity is maintained after proper antituberculous chemotherapy and proper nutritional improvement.
- During therapy, if patient develops ileocaecal obstruction, ileo-transverse colon anastomosis (bypass) can be done. But this is not a good procedure as it causes blind loop and tuberculous focus is retained. Now this bypass is used only in patient presenting with acute intestinal obstruction with poor general condition and in high risk group patients as a life saving procedure. A definitive second stage right hemicolectomy is needed in these patients at a later period.
- Adhesive obstruction may be released through laparoscopic adhesiolysis. It is often technically difficult to release dense adhesions even by open method.
- Drainage of intraabdominal abscess, perianal abscess and treatment for tuberculous fistula in ano is done when necessary.


Colon
Line of resection
Ileocaecal TB
Ileum
A
B



Figs 10.6A to C: Ileocaecal limited resection with 5 cm bowel margin is the treatment of choice for ileocaecal tuberculosis.


Stomach
Colon
Rolled up omentum
Ileocaecal TB
Ulcerative
Hyperplastic
Incompetent ileocaecal valve
Stricture

Fig. 10.7: Ileocaecal tuberculosis with rolled up omentum. Note: The sites and tubercles in ileocaecal valve, which will be incompetent due to fibrosis.



Fig. 10.8: Barium enema X-ray showing stricture in ileocaecal region due to ileo caecal tuberculosis.

A man carries success or his failure with him; it does not depend on outside conditions.

Differences between ulcerative and hyperplastic types of ileocaecal tuberculosis

Ulcerative type (60%)	*Hyperplastic type (10%)*
1. Secondary to pulmonary tuberculosis	1. Primary GIT tuberculosis, could be due to bovine bacilli
2. Virulent organism	2. Less virulent organism
3. Poor body resistance, old people	3. Good body resistance, young individual
4. Multiple transverse ulcers commonly in the ileum, often in the caecum	4. Chronic granulomatous lesion in the ileocaecal region
5. Clinically presents with diarrhoea, bleeding P/R, loss of appetite and reduced weight	5. Presents as a mass in right iliac fossa
6. Complications: Stricture, intestinal obstruction	6. Complication: Subacute intestinal obstruction
7. Chest X-ray shows primary lesion	7. No primary lesion in chest X-ray
8. Barium study shows ileal strictures with hypermotility	8. Barium study—Pulled up caecum, obtuse ileocaecal angle

ILEAL TUBERCULOSIS

- It is usually *stricture* type.
- It may be multiple.
- It presents usually with intestinal obstruction.
- Bowel adhesion, localization, fibrosis, secondary infections are quiet common.
- Perforation (5%) though rare culminates in peritonitis.
- Plain X-ray shows multiple air fluid levels.
- Treatment *is resection and anastomosis and to continue anti-TB drugs*.
  Often *stricturoplasty* is beneficial.

PERITONEAL TUBERCULOSIS

Peritoneal tuberculosis

- Post-primary
- Becoming more common
- Activation of long-standing latent focus
- Blood spread
- Can develop from diseased mesenteric lymph node, intestine or fallopian tubes

Pathology in Peritoneal Tuberculosis

- Enormous thickening of the parietal peritoneum with multiple tiny yellowish tubercles.
- Dense adhesions in peritoneum and omentum with content inside as small bowel looking like ***abdominal cocoon***. It may precipitate intestinal obstruction.
- Multiple dense adhesions between bowel loops and between bowel and peritoneum and omentum.
- Thickening of bowel wall with adhesions.

Types

1. Acute type—Mimics acute abdomen

Exploratory laparotomy reveals straw-coloured fluid with tubercles in the peritoneum, greater omentum and bowel wall. It is an on-table diagnosis. Fluid is evacuated and collected for AFB study and culture. Omental biopsy is taken. Abdomen is closed (without a drain) with tension sutures to prevent burst abdomen. ATD is started.

Acute peritoneal tuberculosis

- Rare
- On-table diagnosis
- Features of peritonitis
- Due to perforation or rupture of mesenteric tuberculous lymph nodes

2. Chronic tuberculous peritonitis

- Present as abdominal pain, fever, ascites, loss of weight and appetite, abdominal mass, ***doughy abdomen (10%).***
- Peritoneum is thickened with multiple tubercles. Omentum is thick, ***fibrosed, rolled up***.
- Infection is usually from mesenteric lymph nodes, ileocaecal tuberculosis, from fallopian tubes rarely blood born (from lungs).
- *Laparoscopy is very useful in this type to diagnose.*

Ascitic form

- **Ascitic form** shows enormous distension of abdomen with dilated veins.
- It presents with congenital hydrocele in male with patent processus vaginalis, umbilical hernia, rolled

up omentum, shifting dullness, fluid thrill, and mass abdomen.

- *Ascitic tap* reveals straw coloured fluid from which AFB can be isolated. Fluid is pale yellow, clear, rich in lymphocytes, with high specific gravity.
- Chest X-ray, Mantoux test are other required investigations.
- ATD's for one year is required. Repeat tapping may be required initially as part of the treatment.



Figs 10.9A to C: On-table findings in intestinal tuberculosis, of extensive involvement with multiple tiny tubercles, thickening, adhesions and involvement of mesenteric lymph nodes.



Fig. 10.10: Abdominal distension with ascites due to abdominal tuberculosis.



Figs 10.11A and B: US picture showing ascites. Straw coloured ascitic fluid done under US guidance.

Great things are done by a series of small things brought together.



Fig. 10.12: CT scan abdomen showing ascites due to tuberculosis.



Figs 10.13A and B: Laparoscopic picture of loculated ascites due to abdominal tuberculosis. Fluid is getting aspirated using a needle under laparoscopic vision.

Encysted (Loculated) ascites

- Ascites gets loculated because of the fibrinous deposition.
- Dullness, which is not shifting, is the typical feature.
- They may present as intra-abdominal mass, which may mimic ovarian cyst, retroperitoneal cyst or mesenteric cyst.
- Treatment is U/S guided aspiration along with ATD's.

Plastic type

- Here there are wide spread adhesions between the coils of the intestine (ileum commonly), abdominal wall, omentum, with distension of the small bowel, leading to blind loop, ileus, intestinal obstruction (subacute, acute), thickened parietal peritoneum.
- They get recurrent colicky abdominal pain, diarrhoea, wasting, and loss of weight, mass abdomen, and *doughy abdomen*.
- *Differential diagnosis*: Peritoneal carcinomatosis. Open/laparoscopic peritoneal biopsy is very useful tool to diagnose.
- They respond well for drug treatment. Surgery is indicated if obstruction occurs.



Fig. 10.14A



Fig. 10.14B



Fig. 10.14C

Figs 10.14A to C: Laparoscopy showing plastic type of abdominal tuberculosis and multiple tubercles over parietal and visceral surface of the peritoneum.



Figs 10.15A and B: Laparoscopy showing adhesions between bowel and abdominal wall due to tuberculosis.

Purulent form

- It is invariably due to tuberculous salpingitis, presenting as a mass in the lower abdomen containing pus, omentum, fallopian tubes, small and large bowel.
- Cold abscess gets adherent to the abdominal wall, umbilicus and may form an umbilical fistula.
- Patient commonly has got genitourinary tuberculosis.
- U/S, discharge study, X-ray abdomen and other investigations are useful.
- *Treatment:* ATD's are started exploration of umbilicus, exploration of fistula and bowel by pass is done.
- Prognosis is poor in this type.

Ascitic form	*Loculated form*
• Insidious onset • Fatigue, weight loss, fever, anorexia • Abdominal pain usually absent • Abdominal distension usually without pedal oedema • *Rolled up omentum* is common association as mass	• Loculated abdominal swelling • Ascites which is not shifting • Diagnosis – US guided aspiration • Antituberculous drugs
Fibrous form	*Purulent form*
• Widespread adhesion of bowel loops • Adhesions, matting and dilatation • Act as blind loop – malabsorption • Abdominal pain, loss of weight, *doughy abdomen* due to thickened parietal peritoneum, diarrhoea, often mass abdomen – are usual features	• Due to tuberculous salpingitis • Presenting as lower abdominal mass • Umbilical fistula, abdominal wall abscess can occur • Cold abscess adherent to abdominal wall

TUBERCULOUS MESENTERIC LYMPHADENITIS

- Infection is usually through the Peyer's patches of the intestine (i.e. through oral cavity). Usually several lymph nodes are involved often causing massive lymph node enlargement. Commonly right-sided lymph nodes are involved, but left sided nodes can also get involved.
- It presents with general symptoms (fever, malaise, weight loss).

Example isn't the best way to teach, it's the only way.



Figs 10.16A to C: Mesenteric tuberculous lymphadenitis on table findings.

- Pain in umbilical region and right iliac fossa, mass in right iliac fossa, which is matted, nonmobile.
- It may present with features of *acute appendicitis*.
- Often coils of intestine get adherent to the caseated mesenteric lymph nodes leading to intestinal obstruction.
- Most often caseating material may collect between the layers of the mesentery, forming a cold abscess, mimicking a mesenteric cyst (***Pseudo-mesenteric cyst).***
- *Massive enlargement of mesenteric lymph nodes due to tuberculosis is called as* ***tabes mesenterica****.*
- Mesenteric tuberculous adenitis is more common in children. Present with anaemia, fever, loss of appetite and reduced weight, failure to thrive, palpable mass in right iliac fossa which is firm and nodular.

Presentations of mesenteric tuberculous lymphadenitis

- Mesenteric tuberculous adenitis—acute/chronic in right iliac fossa—mass
- Pseudomesenteric cyst
- Cold abscess within the mesentery
- Tabes mesenterica

Differential Diagnosis

- Carcinoma caecum.
- Lymphoma.
- Retroperitoneal tumour.
- Non specific lymphadenitis.

(Acute nonspecific mesenteric lymphadenitis is called as **nurses' syndrome**).

Investigations

- X-ray abdomen shows calcification.
- U/S may confirm the diagnosis.
- Mantoux test may be positive.
- *Diagnostic laparoscopy*—is very useful in TB lymphadenitis. Mesenteric cold abscess can be drained safely through laparoscopy.

Treatment: ATD's; Laparoscopy and proceed. Prognosis is good.

ANO-RECTO-SIGMOIDAL TUBERCULOSIS

- It mimics carcinoma rectum.
- It presents as tenesmus, diarrhoea, and discharge from the fistula and occasionally as mass per abdomen. Rectal tuberculosis occurs usually within 10 cm of anal verge.



Figs 10.17A and B: Note the location of mesenteric tuberculous lymphadenitis in the rigth iliac fossa. But it can occur anywhere in the line of mesentery. On-table caseating tuberculosis lymphadenitis is also shown.

- Fistulas are *painful and characteristically not indurated.* Tuberculous fistulas are commonly multiple.
- Tuberculous anal ulcers when occur are shallow, bluish, with undermined edges.
- Sigmoidoscopy, U/S, discharge study, fistulectomy and biopsy confirms the diagnosis.
- Treatment is ATD's, fistulectomy, often *sigmoid resection.*

TUBERCULOSIS OF THE OMENTUM

- It usually occurs as a part of the other types of abdominal tuberculosis.
- *Rolled up omentum* with thickening is characteristic.
- Often cold abscess can develop per se in the omentum.
- If it is so it can be dealt with laparoscopy safely under the cover of ATD's.

In all abdominal tuberculosis, drug treatment is for one year
In adrenal tuberculosis and severe adhesions steroids may be beneficial

Indications for steroids in tuberculosis

- Miliary tuberculosis
- Tuberculous meningitis
- Adrenal tuberculosis
- Tuberculous pericarditis
- Pleural and endobronchial tuberculosis
- In abdominal tuberculosis to prevent adhesions
- Tuberculosis of the mediastinal lymph nodes (Rapidly progressive)
- Genitourinary tuberculosis
- Ocular tuberculosis

Remember

- AFB staining of fixed tissue in abdominal tuberculosis is possible only in 5% cases. *Ziehl – Neelsen* staining is done. (Carbol fuchsin – steam heat for 7 minutes – water wash – decoloraisation with 20% H_2SO_4 – 95% ethanol wash – counterstain with Loeffer's methylene blue/1% picric acid/0.2% malachite green. Tuberculous bacilli are bright red rods seen under oil immersion lens).
- Culture takes 8 weeks to get the result. 35% of abdominal tuberculosis shows positive in culture. *Lowensten Jenson media* is used. Guinea pig inoculation is also useful method.
- *WHO now recommends* antituberculous drugs for 6 months. Uncomplicated cases – 4 drugs for 2 months and 2 drugs for 4 months. Complicated cases – 4 drugs for 2 months and 2 drugs for 7 months. But many patients need one year treatment. Because of complications and difficulty in managing recurrent cases of abdominal tuberculosis one year therapy is commonly used in developing countries.
- *First line drugs* are - Isoniazid – 5 mg/kg; Rifampicin – 10 mg/kg; Ethambutol – 15 mg/kg; Pyrazinamide – 25 mg/kg.

The same beam of light can illuminate two objects and produce two different effects.

- *Second line drugs* are – Amikacin; Kanamycin; PAS (Para Amino Sulphuric acid); Ciprofloxacin; Ofloxacin; Clarithromycin; Azithromycin; Rifabutin.
- Follow up and prognosis is monitored by – regular weight check to see for gain; improvement in appetite; reduction of abdominal pain and distension; absence of fever; normal bowel habits; normal haemoglobin; ESR becoming normal; and US abdomen shows improvement in sonological features.
- Patients who are not responding in 6 weeks should be reassessed again for – drug resistance; associated other diseases like malignancy (carcinomas or lymphoma), Crohn's disease, eosinophilic enteritis
- During therapy patient who is responding for drug therapy can also go for intestinal obstruction due to fibrosis during healing stage. It needs surgical intervention.
- Repeated surgery in abdominal tuberculosis is difficult and dangerous as chances of developing faecal fistula, further adhesions are more likely.

Self-assessment Questions

- Ileocaecal tuberculosis.
- Differences between ulcerative and hyperplastic types of ileocaecal tuberculosis.
- Barium enema features of ileocaecal tuberculosis.
- Classify abdominal tuberculosis.
- Loculated ascites.
- Tuberculous ascites.
- Pseudomesenteric cyst.
- Tabes mesenterica.
- Peritoneal tuberculosis.
- Abdominal cocoon.

11

Liver

> ***The liver…that great maroon snail…. No wave of emotion sweeps it. Neither music nor mathematics gives it pause in its appointed tasks.***
>
> **—Richard Selzer,** 1976

Surgical anatomy of liver
Functions of the liver
Liver function tests
Alfa-feto protein
Liver biopsy
Liver injury
Infections of liver: *Amoebic liver abscess, Hydatid cyst of liver, Actinomycosis of liver, Pyogenic liver abscess, Portal pyaemia.*
Liver tumours: *Benign tumours of the liver, Primary malignant tumours of the liver, Secondaries in the liver*
Portal hypertension: *Oesophageal varices, Ascites*
Portal hypertensive gastropathy
Budd-Chiari syndrome
Hepatic failure: *Hepatic encephalopathy*
Hepato-renal syndrome
Hepatic resection

SURGICAL ANATOMY OF LIVER

Liver has four lobes—*right lobe, left lobe, quadrate lobe and caudate lobe.*

Supporting structures are *right triangular ligament, left triangular ligament and falciform ligament*.

Blood Supply

It is a unique organ with dual blood supply. Hepatic blood flow is around 1500 ml/minute of which *portal vein* contributes 80% and *hepatic artery* 20%.

Hepatic artery commonly originates from coeliac axis. There are many variations of hepatic artery, both in its origin and its pathway and is considered surgically important. Hepatic artery ligation is one of the surgical palliation for advanced hepatocellular carcinoma and secondaries in liver as tumour tissue is supplied exclusively by hepatic artery but normal tissue is also supplied by portal vein.

Superior mesenteric vein and splenic vein join dorsal to the neck of pancreas to form portal vein.

Hepatic artery, portal vein and bile duct are located in the free edge of the lesser omentum until it enters the liver.

Venous drainage is usually through the three major hepatic veins, right, left, and middle which drain into the IVC. Often inferior hepatic vein may be present.

The liver parenchyma is entirely covered by a thin capsule called '*Glissons capsule*' and by visceral peritoneum in all but the posterior surface of liver termed 'bare area'.



Figs 11.1A and B: Anatomical location of liver and its lobes.

> *I prefer to learn and to teach anatomy, not from books but from dissections; not from the positions of philosophers but from the fabric of nature.*
>
> —William Harvey



Fig. 11.2: Segmental anatomy of the liver.

Segmental Anatomy of Liver

Liver is divided into functional right and left lobes by a line passing from the left of the gallbladder fossa to the left of IVC—*Couinaud's line.* There are *eight segments*:

Segments I, II, III, and IV are of left lobe.

Segments V, VI, VII, VIII are of right lobe.

Segment I is the caudate lobe of the liver and has independent supply of portal and hepatic veins. This hepatic vein directly joins IVC.

Right lobe is having right hepatic artery, right branch of portal vein, and right hepatic duct.

Left lobe is having left hepatic artery, left portal vein, left branch of bile duct.

Functional unit is called as hepatic lobule and it contains central hepatic vein and portal triad (hepatic arteriole, portal venule, bile ductule).

FUNCTIONS OF THE LIVER

1. Removal of gut endotoxins and foreign antigens—liver acts as the first filter
2. Drug and hormone metabolism
3. Formation of bilirubin and its metabolism
4. Formation of urea from protein catabolism
5. Glucose metabolism, glycolysis, and gluconeogenesis
6. Clotting factors synthesis
7. pH balance and correction of lactic acidosis
8. Maintaining body temperature
9. Storage of vit. B12, vit. A, Cu, Fe

LIVER FUNCTION TESTS (LFT)

1. Serum bilirubin which includes both direct and indirect. Test is known as *van den Bergh's test*.
2. Serum albumin, globulin and A : G ratio; serum albumin is the indicator of chronic liver disease.
3. Prothrombin time: Normal value is *12-16 seconds*. Difference between control and test more than 4 seconds or test being more than 1½ times the control is significant. When it is altered it is corrected by injecting vitamin K, 10 mg IM for 5 days or by fresh frozen plasma (FFP)—*For cell synthesis.*
4. Alkaline phosphatase—*Secretary function.*
5. Aspartate amino transaminase *5-40 IU/litre* (AST, SGOT)—*signifies inflammation.*
6. Alanine transaminase *5-40 IU/litre* (ALT, SGPT).
7. 5 nucleotidase.
8. Gamma glutamyl transpeptidase (GGT) 10-48 IU/L.
9. Immunological tests: Antimitochondrial or antinuclear antibodies.
10. AFP.
11. Specific tests: (a) For haemochromatosis-serum iron, total iron binding capacity, serum ferritin. (b) Wilson's disease: Serum copper, urinary copper, serum ceruloplasmin.
12. Flurodeoxy glucose—positron emission tomography (FDG-PET): It is to find out the uptake of labelled glucose which varies in different diseases of liver, i.e., benign, malignant and inflammatory.
13. Technetium-99 m labelled radioisotope scan shows the uptake and excretion of bile.
14. A sulphur colloid liver scan shows specifically Kupffer cell activity. Sulphur colloid will not show uptake in adenoma and haemangioma as Kupffer cells are absent in these lesions.
15. Urine for bile salts (*Hay's test*), for bile pigments (*Fouchet's test*) and for urobilinogen (*Ehrlich's aldehyde test*).

Other investigations for liver diseases

1. U/S abdomen
2. Angiography
3. CT Scan
4. PTC
5. ERCP
6. MRI
7. Laparoscopy and laparoscopic U/S
8. Liver biopsy

ALFA-FETO PROTEIN (AFP)

- It is a normal component of plasma protein of the human foetus secreted by embryonal hepatocytes which disappears 2-3 weeks after birth.
- Normal value is up to 10 ng/ml of plasma.
- It is an important tumour *marker for HCC and more often HCC with cirrhosis* (between 100-1000 ng/ml).
- It also increases in *hepatoblastoma, testicular tumours and ovarian tumours.*
- It is a prognostic indicator.
- It also increases slightly in benign conditions of the liver (only upto 100 ng/ml if at all).

- It increases significantly in non-seminomatous testicular tumours and ovarian tumours (yolk sac tumour).
- AFP is an useful marker to suspect, relapse or residual tumour.

LIVER BIOPSY

Prerequisites:

- Prothrombin time should be normal before doing liver biopsy, otherwise severe bleeding can occur.
- Normal value of prothrombin time is 12-16 seconds. (It is compared to control and difference should be less than 4 sec between test and control.) It is corrected by giving inj. vit K 10 mg IM, for 5 days. After that if repeat PT is still high then fresh frozen plasma (FFP) is required to correct it.

Indications

1. Cirrhosis, chronic hepatitis, haemochromatosis, Wilson's disease.
2. Hepatoma, secondaries in liver.

Complications

- Haemorrhage.
- Bile leak and biliary peritonitis.
- Infection.

Contraindications

- Hydatid disease, where it will precipitate anaphylaxis.
- Haemangioma, bleeding disorders.
- Ascites.

Procedure

Needle used here is either *Vim-Silvermann needle* or *Menghini needle* (better option).


a
a. Stilette b. Biflanged needle
b
A
a
b
c
a. Needle b. Locking pin c. Stilette
B

Fig. 11.3: Liver biopsy needles. A. Vim-Silvermann, B. Menghini.

Needle is usually punctured through right mid-axillary line in 9th intercostal space or under U/S guidance into any place as required.

Presently, guided liver biopsy is commonly recommended and popular, i.e., U/S guided, CT scan guided, laparoscopy guided.

LIVER INJURY

Causes

It can be due to blunt injury, stab, gun shot injury.

Types

It can be contusion, laceration, avulsion, extension into thorax and biliary tree may be associated with other organ injuries (spleen, kidney, duodenum, bowel, IVC) and with fracture ribs.

Clinical Features

- Features of shock due to severe torrential bleeding (pallor, hypotension, tachycardia, sweating).
- Distension of abdomen with dull flank, guarding, tenderness and rigidity.
- Oliguria.
- Tachypnoea, respiratory distress and often cyanosis.
- Rupture of right lobe is more common than left lobe leading to *haemoperitoneum.*
- Occasionally can cause localized haematoma which may form an abscess.
- Bile leak from the injured site can lead to *biliary peritonitis*.

Investigations

- Chest X-ray to look for rib fractures.
- U/S abdomen, CT scan of chest and abdomen (CT is ideal).
- Diagnostic peritoneal lavage.
- Hb%, PCV, blood grouping and crossmatching. Adequate amount of blood (5-10-15 bottles of blood) must be kept ready for transfusion, i.e. requires massive transfusion.
- Arterial blood gas analysis.
- Coagulation profile.
- Thromboelastography is dynamic form of assessing the coagulation status.

Treatment

General measures

1. IV fluids, blood transfusion (massive), FFP.

Regeneration of liver after resection is complete in 4-6 months. 80% of liver can be resected without compromising its function.

2. Have both central venous access, and peripheral venous access.
3. Bladder catheterisation has to be done to measure the urine output.

Specific treatment

- *Push (direct compression); plug* (plugging the deep track injuries using silicone tube or SB tube); *Pringles'* maneuver; *pack* (liver wound is directly packed with mop).
- Laparotomy is done through a large *bucket handle* abdominal incision or thoracoabdominal incision, and extent of liver injury and also other associated injuries are looked for.
- Small liver tear is sutured with *vicryl* or *PDS* mattress sutures with placing of gel foam to control bleeding.
- To control bleeding on table, from hepatic artery and portal vein, both are temporarily occluded using fingers, compressing at foramen of Winslow —*Pringle manoeuvre*. Often bull-dog clamp or vascular clamps can be used.
- In deep severe injuries, following methods are used:
  - Hepatic artery ligation.
  - Segmental resection.
  - Hemihepatectomy.
  - Packing the liver temporarily with mops and closing the abdomen.
- Cholecystectomy and placement of 'T' tube in CBD.
- In associated IVC injuries it is very difficult to manage (has high mortality). A *veno-venous bypass* between femoral vein and SVC is done and then repair of IVC is carried out.
- ICT placement to thorax and repair of diaphragmatic injury.
- Management of other organ injuries accordingly.
- *Kous Netzoff aluminium needle* is used to suture liver tear.
- Postoperatively patient requires ventilator support, blood transfusion, electrolyte management, antibiotics like third generation cephalosporins, ceftazidime, cefoperazone.
- FFP, cryoprecipitate are also required.

Complications and sequelae of liver injury

1. Shock and haemorrhage
2. Liver abscess or septicaemia
3. Bile leak, biliary peritonitis, biliary fistulas
4. Disseminated intravascular coagulation
5. Hepatic artery aneurysm, arterio-venous and arterio-biliary fistulas—Haemobilia
6. Complications of massive blood transfusion
7. Electrolyte imbalance
8. Respiratory complications
9. Liver failure
10. **Late sequelae** of liver trauma is *CBD stricture* causing obstructive jaundice. It can be managed by endoscopic stenting or by open Roux-en-Y hepatico-jejunostomy

INFECTIONS OF LIVER

AMOEBIC LIVER ABSCESS

- It is common in India and other tropical countries and it is caused by a parasite entamoeba histolytica.
- It is more common in *alcoholics and cirrhotic* patients**.**
- It is the commonest extra intestinal presentation of amoebiasis. It is often called *as tropical abscess*.
- Infection commonly occurs from the caecum after an attack of amebic typhlitis (inflammation of the caecum) through the superior mesenteric vein and portal vein. Infection from sigmoid (rectosigmoid) colon spreads through the inferior mesenteric vein and portal vein to liver. Right lobe is commonly involved over postero-superior surface (because of streamline effect and larger size of the right lobe). Trophozoites destroy the hepatocytes by releasing *histiolysin*, a cytolytic agent. It causes amebic hepatitis with multiple micro abscess formation. It leads into liquefaction necrosis, thrombosis of blood vessels, release and, breaking of red cells. It causes formation of *"Anchovy sauce'* pus which is chocolate brown coloured and odourless (Anchovy sauce is sauce prepared from a type of fish). Pus may be green coloured if mixed with bile. Secondary infection is common (30%).
- In western countries pyogenic abscess is much more common. Amebic abscess is much more common than pyogenic abscess in endemic areas like Indian subcontinent, and Africa.
- Amebic abscess is usually sterile unless infected. Trophozoites are found in the wall of the abscess not in the content.

Pathology

- Initially from infected recto-sigmoid or ileocaecal region, amoebic trophozoites reach the liver through portal veins causing amoebic hepatitis, may be in the form of micro-abscesses all over the liver. This might resolve on its own or with antiamoebic drugs, but often leads to a localized *amoebic liver abscess.*



Fig. 11.4: Commonest location of amoebic liver abscess – right posterosuperior part of the liver.



Fig. 11.5: Spread of trophozoites occurs from ileocaecal region and sigmoid through mesenteric vessels.

- In 70% of cases it is *single large abscess,* in 30% it is multiple, may involve both lobes. Problems and difficulties in treating, in addition to poor prognosis are more common in *multiple abscesses*.
- Amoebic liver abscess is more common in *right posterior-superior* region (80%) because of streamline effect, i.e., the portal vein is in direct continuation with the right branch. It can be *multiloculated* also.



Fig. 11.6: Anchovy sauce pus seen in amoebic liver abscess.

- Pus is *chocolate coloured,* classically called as **anchovy—sauce,** contains dead liver cells, RBC's, necrotic material. Pus may be green due to bile admixture.
- Often secondary infection by *E. coli*, staph, strepto may occur (30%) and so may present with features of pyogenic liver abscess. Because of perihepatitis, liver is fixed to diaphragm or abdominal wall, hyperaemia in the diaphragm causes sympathetic *pleural effusion on right side*.
- Commonly amoebic abscess presents as an *acute entity*, but it can also be present as *chronic type* where it is covered by a capsule, that remains dormant for a long period.
- Sometimes it can get calcified also**.**

Course and Sequelae of Amoebic Liver Abscess

- It can *rupture into lungs* leading to expectoration of chocolate-coloured sputum resulting in natural regression of abscess—commonest site of rupture.
- It can rupture into the peritoneum causing *peritonitis* which requires emergency laparotomy.
- It can rupture into pleural cavity leading to *empyema*.
- Rupture into bronchus can cause bronchopleural fistula leading into coughing out of Anchovy sauce pus.
- Rupture into bare-area of liver causing *retro-peritoneal abscess*.
- Rupture into the intestines, or to the skin (*Amoebiasis cutis).*

> *Amoebic liver abscess may be present as bulge in the right lower intercostal spaces and may exhibit pitting edema.*
>
> —Ajit K Basu



Fig. 11.7: Complications of amoebic liver abscess.

- Most dangerous complication is rupture into pericardial cavity (*cardiac tamponade*) which has very *high mortality* requiring emergency thoracotomy and pericardial decompression.
- *Septicaemia and liver failure* can occur in a patient with amoebic liver abscess with *cirrhosis.*

Clinical Features

- It is common in males (20:1), may be after an attack of amoebic dysentery or many months after the attack or history of dysentery may not be there at all.
- They present with fever, loss of weight, chills and rigors, non productive cough, shoulder pain.
- Pain in the right hypochondrium.
- Soft, tender, smooth, liver with increased liver span.
- **Intercostal tenderness** is elicited which is a useful clinical sign.
- Right sided pleural effusion may be evident.
- Mild jaundice is not uncommon especially in cirrhotics and multiple abscesses which may signify poor prognosis.
- Tenderness, rigidity and skin oedema in right hypochondrium may be present in acute cases.
- In chronic amoebic liver abscess, smooth, firm/hard, nontender liver may be palpable.

Amoebic liver abscess may be –

- *Acute* – present with high fever, chills, rigors, tender, soft palpable liver, with intercostal tenderness.
- *Chronic* – present with firm/hard, smooth, non-tender palpable liver without acute features.

Features may be of –

- *Systemic* – present with fever, chills and rigors, loss of appetite, reduced weight, and jaundice.
- *Abdominal* – present with pain and tenderness, localized guarding and rigidity, mass in right upper abdomen (tender, soft liver), ascites, splenomegaly, abdominal wall oedema.
- *Thoracic* – present with dry cough, chest pain in right lower part, right shoulder pain, pleural effusion, and intercostal tenderness.
- *Features of complications* – rupture/infection/septicaemia/liver failure.

Differential diagnosis

For Acute type

1. Acute cholecystitis
2. Acute presentation of hepato-cellular carcinoma (HCC) due to haemorrhage or necrosis.
3. Subphrenic abscess.

Chronic amoebic liver abscess mimics hepatoma in every respect

Investigations

- Total count may be increased.
- Liver function tests may show altered bilirubin and albumin level.
- Prothrombin time may be widened and if it is so Inj. vit K 10 mg IM for 5 days should be given. Even with this if P.T. remains widened then fresh frozen plasma (FFP) is needed to rectify the P.T.
- Serum alkaline phosphatase, SGPT, SGOT levels are altered.
- U/S abdomen shows altered echogenicity, (anechogenic, hypoechogenic) size, location, number of abscess, nature of the liver.
- Chest X-ray findings:
  - Raised fixed diaphragm (tenting)
  - Pleural effusion
  - Soft tissue shadow
- Indirect haemagglutination test (95% positive rate), ELISA and gel diffusion precipitative test are reliable serological tests. Serological tests are reliable in non-endemic areas than endemic areas. Counter immuno-electrophoresis is more useful in active disease.
- CT scan-contrast study. CT scan shows raised diaphragm; abscess cavity (low density area) – its size, location, number; presence of effusion; changes in the lung.
- Sigmoidoscopy/colonoscopy are used to identify the active ulcers. Scrapings of the ulcer show trophozoites.


LIVER
LIVER
ABSCESS
ABSCESS
TRA SEC
LONG SEC.

Fig. 11.8: US picture of amoebic liver abscess. US guided aspiration is very useful.



Figs 11.9A and B: CT scan pictures showing single, large and multiple liver abscesses.

Treatment

Drugs

- Tab. Metronidazole 800 mg tid or inj. metronidazole 500 mg IV tid for 10 days.
- Tinidazole 600 mg BD dose for 5 days.
- IV or oral antibiotics are essential to control secondary infection (cefotaxime, ciprofloxacin, amoxycillin). (Small abscesses < 3 cm respond to drugs).
- *Other drugs:*
  1. Injection dihydroemetine 1.5 mg/kg/day IM for 5 days should be given under cardiac monitoring.
  2. Chloroquine 250 mg BD given for 10-14 days.

Drugs used for amebic infection

- Metronidazole, Tinidazole, Secnidazole, Ornidazole
- Dihydroemetine injection
- Chloroquine, tetracycline
- Diloxanate furoate, iodoquinol, paromonycin—as *cyst eradicators*

Note: Metronidazole is not given in 1st trimester of pregnancy.

Aspiration

- In case of large abscess and infected abscess aspiration with a wide bore needle is done under U/S guidance after correcting the P.T.
- Previously without U/S, aspiration used to be done by passing needle in right 6th intercostal space in mid-axillary line.


Aspiration through intercostal space 8th
US guided aspiration from front ideal
Mid axillary line
Amoebic abscess
Liver

Fig. 11.10: Aspiration of the amoebic liver abscess under US guidance or through right 8th intercostal space in mid-clavicular line.

PIVKA II: Protein induced in the absence of vitamin K or antagonists-II.



Figs 11.11A to E: Operative findings of amebic liver abscess. Note the exposed abscess in the liver, its aspiration and drainage. Placement of Malecot's catheter in the abscess cavity and drain placed into the peritoneal cavity is also seen.

Percutaneous Drainage

- Under U/S guidance pigtail catheter is placed into the abscess cavity percutaneously to drain the pus. Catheter tube and abscess cavity has to be washed and irrigated at regular intervals with normal saline. It may fail if there is thick pus, multiloculated abscess, and multiple abscesses. Procedure may cause bleeding and infection.

Note: Aspirated fluid is sent for C/S, cytology and for study of trophozoites (last part of the aspirated fluid should be sent for this).

Surgery

Indications for surgery

1. Even after repeated aspirations if abscess cavity fills again
2. Thick pus
3. Multiloculated abscess
4. Left lobe abscess, because of danger of rupture into pericardial cavity
5. Ruptured abscess
6. Caudate lobe abscess
7. Multiple abscesses



Fig. 11.12: Drainage of amoebic liver abscess transperitoneally and placing Malecot's catheter into the abscess cavity.

Procedure

- Through transperitoneal approach, abscess area is opened, pus is evacuated. Malecot's catheter is placed and brought out through a separate stab incision. The catheter is kept in situ until drainage stops completely. Complete drainage of pus will be confirmed by repeat U/S. During discharge, advice is given to avoid alcohol, Chloroquine 250 mg BD for 10 days and Diloxanide furaote 500 mg tid is given for 10-14 days.
- *Complications of surgery* – anesthetic problems; bleeding; liver failure (in cirrhotic patients); intraperitoneal abscess formation; bile leak – bile peritonitis and fistula.

Follow up

At regular intervals is important. Measures taken are proper counseling to avoid alcohol; repeat LFT; repeat ultrasound to confirm the complete resolution of the abscess cavity.

HYDATID CYST OF LIVER

Word meaning is '*dew drop*' (Latin). In Greek it means 'watery vesicle'.

Caused by **Echinococcus granulosus (EG),**
dog tape worm, a parasite.

Life-cycle: Infected offal of sheep
↓
Eaten by the dog (definitive host)
↓
EG released, develops in the dog's intestine into a parasite of 1 cm long with a head and three segments, last of which contains about 500 ova.
↓
Ova expelled from the dog's intestine to grass and vegetables
↓
Eggs are ingested by sheep, cattle or human beings *(intermediate host)*
↓
Through portal vein—liver—larva form
↓
Hydatid cysts (70% in liver).

It takes few years to evolve into a complete hydatid cyst.

Most commonly involved segment is segment VII – 27%. Commonly right lobe – 66%; both lobes in 16% and only left lobe is involved in 17%.

Pathology

It has got 3 layers

1. *Adventitia (pseudocyst)* is an inseparable fibrous tissue due to reaction of the liver to the parasite.
2. *Laminated membrane (ectocyst)*, formed of the parasite itself is whitish, elastic, containing hydatid fluid, which can be peeled off readily from the adventitia.



Fig. 11.13: Anatomy of hydatid cyst.

3. *Germinal epithelium* is the only living part, lining the cyst (*endocyst).*

This layer secretes *hydatid fluid*, *brood capsules with scolices* (heads of future worms).

Features of hydatid fluid
- Clear
- High specific gravity (1.005-1.009)
- Shows hooklets and scolices

Once brood capsules disintegrate, it grows into daughter cysts.

Course of the Disease

- The parasite may die and cyst eventually may get *calcified.*

Anything the mind of man can conceive and believe, it can achieve.

- Commonly cyst *enlarges* and is palpable per abdomen.
- It may cause complications like *jaundice* due to pressure over biliary tree.
- *Rupture into the peritoneal cavity* causes anaphylactic reaction which may cause life-threatening shock, requiring proper management with steroids.
- *Rupture into biliary channels is commonest (60%).* Rupture into bowel, pleural cavity can occur.
- *Secondary infection* causing suppuration and septicaemia.
- *Secondary cysts* in the lung, spleen, mesentery, retroperitoneum and other organs can occur.
- *Hepatic dysfunction.*
- *Disseminated abdominal hydatidosis* can occur after silent rupture.

Clinical Features

- Asymptomatic palpable liver with *classical thrill (hydatid thrill)* elicited by *three-finger test.*
- Jaundice and pain.
- Features of anaphylaxis.
- Discomfort in right upper quadrant area; dyspepsia; hydatid cachexia in children; weight loss; fatigue; vomiting.
- Occasionally splenomegaly, pleural effusion, cholangitis, allergic asthma, fever.
- *Camellotte sign*: Following intrabiliary rupture, gas enters into cyst causing partial collapse of the cyst wall.



Fig. 11.14: Multiple scolices removed from hydatid liver (*Courtesy by Dr Yogesh Kumar, Mangalore*).

Differential Diagnosis

- Hepatoma.
- Amoebic liver abscess.
- Cystic disease of the liver.

Complications of hydatid

- Anaphylaxis
- Rupture
- Obstructive jaundice— ERCP sphincterotomy may be needed
- Infection
- Calcification
- Liver failure

Investigations

- U/S is diagnostic. It reveals rosettes of daughter cysts, double contoured membrane of the cyst due to detachment of the cyst membranes, and calcification of cyst wall. Intraoperative ultrasound (IOUS) is very useful tool.
- X-ray often shows calcification.
- CT scan abdomen is more accurate in identifying cyst characteristics – *cart wheel* like – multivesicular rosette like.
- *Primary serological tests* —ELISA; indirect haemagglutination test; latex agglutination test; immunofluorescence antibody test; immunoelectrophoresis. 80-95% sensitivity for liver hydatid.
- *Secondary laboratory tests* –Detection of precipitation line – arc 5; immunoblotting; polymerase chain reaction (PCR). More specific, very useful in extra hepatic hydatid disease and calcified non-fertile liver hydatid.
- Liver function tests.
- Casoni's test (intradermal test – 75% sensitive); complement fixation test – historical interest.
- MRI when there is jaundice to visualise biliary tree and its relation to hydatid cyst; to find out cysto-biliary communication; biliary hydatids in bile duct and hepatic ducts. ERCP can also be done to find out the communications. Other method to find out the cysto-biliary communications is intraoperative cholangiogram.
- ERCP to find out biliary communications but not as useful as MRI. .

Aspiration of the cyst should not be done due to risk of anaphylaxis but presently PAIR (Puncture – Aspiration – Injection – Reaspiration) is done effectively.

Hassen Gharbi's ultrasound based classification of liver hydatid cysts (1981)

Type 1 – Pure fluid collection
Type 2 – Fluid collection with split wall
Type 3 – Fluid collection with septa
Type 4 – Heterogeneous appearance
Type 5 – Reflecting thick walls

WHO classification of liver hydatid cyst

Type – CL – Active; unilocular; no cyst wall; early stage; not fertile
Type – CE 1 – Active; cyst wall present; hydatid sand present; fertile
Type – CE 2 - Active; multivesicular rosette like cyst wall; fertile
Type – CE 3 – Transitional; detaching laminated membrane; *water-lily* sign; beginning of degeneration
Type – CE 4 – Inactive; degenerative contents; no daughter cysts; not fertile
Type – CE 5 – Inactive; thick calcified wall; not fertile







Figs 11.15A to C: Hydatid cyst of the liver – typical look.



Fig. 11.16: CT scan of hydatid disease of the liver.

Treatment

Drugs

- *Indications for drug therapy*
  - 4 days prior to intervention and to continue it for 1 month (albendazole) to 3 months (mebendazole) after the intervention.
  - Inoperable cysts.
  - Multiple or multiorgan cysts.
  - Recurrent hydatids.
  - Surgically unfit patients.
  - Cysts in lungs, bone, brain, eyes.
- *Contraindications*
  - Large cysts.
  - Honeycomb cysts (with septae).
  - Infected cysts.

Today's impossibilities are tomorrow's miracle.

  - Calcified cysts.
  - Pregnancy.
- *Drugs used are:*
  - Albendazole 4-week cycles with 2 weeks drug free interval. It is ovicidal/larvicidal/*vermicidal*. Commonly used.
  - Praziquantel – 60 mg/kg along with albendazole for 2 weeks.
  - Mebendazole—600 mg daily for 4 weeks.

PAIR – (Puncture – Aspiration – Injection – Reaspiration) – percutaneously done [1980]

<table>
<tr><th>Indications for PAIR</th><th>Results and problems of PAIR</th></tr>
<tr><td>• Inoperable patients
• Patients who refuse surgery
• CL, CE 1, CE 2 and CE 3 types / Gharbi type 1 and 2
• Relapse cysts
• Infected cysts
• In pregnant women; children less than 3 years
• Cysts more than 5 cm in different liver segments</td><td>• Complication rate – 10–40%
• Mortality rate – 0.9 – 2.5%
• Fever – 35% - disappears in 72 hours
• Anaphylaxis – 0.1 – 0.2% - Same as open surgery – but drugs should be kept ready for anaphylaxis
• Infection – 10% well controlled by antibiotics
• Local recurrences – 4% - repeat PAIR can be done</td></tr>
<tr><td colspan="2">Contraindications for PAIR
• Inaccessible cysts
• Cysts with multiple septae – honeycomb cysts
• Hyperechogenic cysts
• Communicating cysts to bile duct
• Calcified cysts
• Cysts in the lung</td></tr>
</table>

Technique of PAIR

- Done under US / CT guidance.
- Under local anaesthesia cyst is punctured using a cholangiography 22 gauge needle through thickest route/part of cyst wall.
- Cyst is entered through non-dependent wall and 50% of fluid is aspirated. All multiple/daughter cysts are aspirated. Radiopaque dye is injected to see if any communications are present. Scolicidal agents—15 - 20% hypertonic saline is injected into the cyst. After 20 minutes re aspiration is done. A sclerosant – alcohol is injected. If cyst is 6 cm or more, a drainage catheter is placed for 24 hours for complete drainage and later alcohol sclerosant is injected.
- Double – puncture aspiration and injection (D-PAI) or modified PAIR/PEVAC (Percutaneous EV Acuation of Cyst) are other procedures done.
- PAIR has gained wide acceptance as it is safe, less invasive, and easier to do, with low morbidity and mortality. Complications and results are same as open surgery.

Surgery

- Surgery is still the choice and *gold standard* therapy for hydatid disease. The abdomen is opened, and the peritoneal cavity is packed with mops [black or coloured mops are used to identify white scolices clearly so as to pick up all and prevent any spillage]. Fluid from the cyst is aspirated and scolicidal agents (cetrimide, chlorohexidine, alcohol, hypertonic saline (15%-20%), 10% povidone iodine or H_2O_2) are injected into the cyst cavity (formalin should not be used)**.** Hypertonic saline should be left within the cavity for 15-20 minutes to have effective scolicidal effect.
- Detection of *cystobiliary communications* is very crucial as it may cause caustic sclerosing cholangitis when scolicidal agent like formalin is used. Communicating openings may be single or multiple. Cyst more than 10 cm is likely to have cysto-biliary communications. Often clinically features of communications may not be present. Preoperatively there may be recurrent cholangitis; dilated bile duct. Factors important are – its size; number; site; involvement of hepatic/bile ducts; liver dysfunction. Finding of bile stained cyst on table during aspiration is highly suggestive of communication. White mops soaked with hypertonic saline are kept in the cyst cavity and gallbladder is gently squeezed to see for the bile staining of the mop in the cavity which confirms communication.
- *Laparoscopic pericystectomy* is becoming more popular. Contraindications are deeply situated cyst, densely adherent cyst, and inaccessible cysts; more than 3 cysts; calcified cysts and cysts in other organs. Main problem with laparoscopic pericystectomy is spillage and difficulty in preventing it.
- Liver resection – only occasionally segmental or hemihepatectomy is done.

Scolicidal agents

- Cetrimide – can cause acidosis
- Alcohol 80% - can cause cholangitis
- Hypertonic saline – hypernatraemia
- Sodium hypochlorite – hypernataraemia
- Hydrogen peroxide

In cases with biliary communication only hypertonic saline (15-20%) is used (not other agents)

Procedures used to correct the cysto-biliary communications and to obliterate the cavity are -

- Suturing of the communication – simple suture using vicryl/PDS suture with T tube drain of bile duct.
- Pericystectomy (*Pericystectomy* is done by peeling off the cyst wall and abdomen is closed with or without a drain); marsupialization.
- Tube drainage of the cavity; *capitonnage* – spiral suturing of the bottom of the cavity upward from base of cavity to the edge of the cyst wall; *introflexion* – inverting the rim of the cyst edge without apposition; *omentoplasty.*
- Internal drainage procedures like choledochojejunostomy; transduodenal sphincteroplasty; Roux – en Y cysto/intracystic hepatico jejunostomy; Roux – en – Y hepaticojejunostomy.
- In cysto biliary communication (fistula), cystobiliary disconnection is achieved anatomically between cyst and fistula and a multiperforated transparenchymal drain is placed into the fistula through the cyst and another multiperforated drain is placed into the cyst cavity. A 'T' tube drain is placed into the bile duct (*perdomo procedure*) to achieve complete external drainage with facilitation of closure of the communication.
- Bipolar drainage – a drain is placed to cyst cavity and a T tube is placed into common bile duct. .
- Reconstructive procedure like *pericysto jejunostomy*; bile duct repair.
- ERCP sphincterotomy.

Malignant hydatid disease

- It is a misnomer as it is a benign condition
- It is caused by *Echinococcus multilocularis (Alveolaris*) It presents with multiple small cysts in both lobes of the liver, all over
- It is difficult to treat, and mimics clinically and prognosis-wise to malignancy, hence the name
- They die of liver failure

ACTINOMYCOSIS OF LIVER

- *Actinomyces israelii* reaches the liver—via portal vein from ceacum (60%) or via hepatic artery from distant focus—from facio cervical region—30%.
- Disease progresses gradually and slowly to destroy the liver tissue causing multiple actinomycotic abscesses which produce a typical *'honey comb liver.'*

Complications

- Secondary infection.
- Liver failure.

Investigations

- Liver function tests.
- Ultrasound guided aspiration and staining of pus shows *'sun-rays'* appearance.

Treatment

Penicillins for 3-6 months.

PYOGENIC LIVER ABSCESS

Aetiology

1. *Biliary sepsis:*
    a. Empyema gallbladder.
    b. Cholangitis.
    c. After biliary tract surgery.
    d. Instrumentation.
2. *Portal vein sepsis:*
    a. Appendicitis.
    b. Diverticulitis.
3. *Distant infections:*
    a. Pneumonia.
    b. Upper U.T.I.
    c. Endocarditis.
4. *Super added infections:*
    a. Amoebic liver abscess.
    b. Hydatid cyst.
5. *Cryptogenic liver abscess*—No identified primary infection.
6. *Trauma* becoming common cause.

Causative bacteria

- *E. coli*—commonest
- *Klebsiella*
- *Proteus*
- *Pseudomonas*
- Clostridia

Clinical Features

- Pain in the right hypochondrium.
- High fever, with rigors.
- Weight loss.
- Jaundice—occasionally.
- Inter-costal tenderness.
- Tender, soft liver.
- Features of toxicity.

Venous hum, which is heard louder on inspiration in epigastrium, in portal hypertension is called as Kenawy's sign

Diagnosis

- Ultrasound abdomen, CT scan.
- LFT, total count.
- Ultrasound guided aspiration of pus after controlling PT.

Treatment

- Systemic antibiotics—combination of third generation cephalosporins and metronidazole.
- Ultrasound guided aspiration/pigtail catheter.
- Occasionally open drainage is required.
- Treating the primary causes is very essential.

Complications

- Septicaemia, liver failure.

PORTAL PYAEMIA (PYLEPHLEBITIS)

It usually follows after severe infection of areas drained by portal vein.

Causes

- Appendicitis.
- Diverticulitis.
- Any severe abdominal sepsis.

Presently it is becoming *rare* because of availability of good effective antibiotics.

Infective thrombus in the vein (draining
the infective area)
↓
It dislodges as infective emboli
↓
Reaches the liver
↓
Causes multiple abscesses in liver parenchyma
↓
Pylephlebitis.

E. coli is the most common organism. Often staphylococci, anaerobes, or combined infections may be involved.

Note: Gas and thrombus in portal vein is diagnostic of portal pyaemia.

Clinical features

- High fever with rigors
- Toxicity
- Drowsiness, jaundice
- Tender soft liver
- Ascites

Blood culture is a useful investigation.

Treatment

- *Antibiotics*: Combination of third generation cephalosporin + aminoglycoside, ceftriaxone sodium, cefoperazone, ceftazidime, amikacin, tobramycin, metronidazole.
- IV fluids, blood transfusion, FFP.
- Ventilator support.
- Mortality is very high and usually patients die of hepatic failure, septicaemia, MODS.
- It is better to prevent portal pyaemia by prior good antibiotics in suspected cases.
- Treatment of primary cause is very important.

LIVER TUMOURS

BENIGN TUMOURS OF THE LIVER

Benign tumors of the liver

- It is two times common than malignant liver tumor.
- It is seen in 20% of population.
- Haemangioma is the most common benign tumor.
- CT and MRI are the essential investigations.
- MRI shows 95% accuracy.
- Diagnostic accuracy of liver biopsy is low – 40%.
- Hepatic adenoma is potentially malignant.
- FNH and haemangiomas are not premalignant.



Fig. 11.17: Solitary benign cyst of the liver. It is a rare entity. Polycystic liver also can occur. Polycystic liver is associated with polycystic kidney disease. Condition is a rare differential diagnosis for hydatid cyst, hepatoma, and solitary secondary.

1. **Haemangiomas**
    - They are the *commonest benign* tumour of the liver.
    - It is usually solitary but can be multicentric.
    - *Compressibility of tumour is diagnostic*.

Complications
- Bleeding rupture
- Thrombosis
- DIC
- Infection

- Complication usually occurs if haemangioma is *more than 8 cm* in size.
- ***Needle aspiration and biopsy are contraindicated.***
- U/S and CT scan are confirmative.
- Angiogram may be needed if surgical intervention is planned.
- MRI is diagnostic.
- Giant haemangioma is of size > 4 cm.

Treatment: Prior radiotherapy is given to reduce the size and then hemihepatectomy is done.
Note: It has got very little or no malignant potential.

2. Hepatic Adenomas
- They are common in females. They present as a solitary nodular lesions in the liver.
- It is said to be due to use of oral contraceptive pills (OCP's).
- It is uncommon in males.
- They might turn into malignancy, hence resection is advised.
- U/S, CT scan are diagnostic but angiography is needed prior to resection, as it is vascular.
- MRI is ideal tool.
- Haemorrhage is more common.
- Hepatic adenoma cells are larger, contain glycogen and lipids. They are devoid of bile ducts whereas FNH contains bile duct components.
- AFP may be raised if it has turned into malignancy.
- Surgical resection is the needed treatment.
- OCP should be stopped.

Indications for surgical resection:
- Rupture of adenomas – 50%
- If there is possibility of turning into malignancy (large adenomas)

Note: Kupffer cells are not present in hepatic adenomas.

3. Focal Nodular Hyperplasia (FNH)
- It is a benign condition of unknown etiology, seen in females showing focal overgrowth of functioning liver tissue with fibrous stroma support.
- It contains hepatic cells as well as Kupffer cells which is characteristic.
- It is 2nd most common benign tumour.
- Usually it presents as solitary nodule.
- A sulphur colloid liver scan is diagnostic, shows 'hot spot'.
- It is a harmless condition.
- CT scan shows central scar with stellate distribution of the blood vessels.
- Histologically it can be typical (with central scar) or atypical (without central scar).
- Usually it does not require any treatment. OCP should be stopped.

PRIMARY MALIGNANT TUMOURS OF THE LIVER

1. Hepato-cellular carcinoma/Hepatoma/HCC (80%).
2. Cholangiocarcinoma (20%).
3. Hepatoblastoma in infants and children.

Hepatoblastoma occurs within 2 years of life. *It is most common primary malignant tumour of liver in children*. It is common in male child. CT scan shows vascular mass with speckled calcification. It is highly sensitive to chemotherapy (vincristine, doxorubicin, 5FU). If it is resectable, it is the initial choice of therapy. Liver transplantation is also beneficial.

HEPATOCELLULAR CARCINOMA (HCC / HEPATOMA)

- Its incidence is rising.
- It is common in cirrhotics and hepatitis B and hepatitis C virus infection.
- It is common in Mozambique.
- Male to female ratio is 4:1.
- It is usually unicentric but occasionally can be multicentric.
- Right lobe is commonly involved.



Fig: 11.18: Hepatocellular carcinoma (HCC/hepatoma) is usually solitary, common in right lobe, attains large size.

Every job is self portrait of the person who did it.

Aetiology

- Aflatoxin B_1, a product of fungus aspergillus.
- Hepatitis B and hepatitis C virus infection.
- Alcoholic cirrhosis.
- Clonarchis sinensis infestation.
- Smoking.
- Haemochromatosis.
- Hepatic adenoma – potentially malignant.
- Environment related chemicals like DDT, nitrite and nitrate related food products; trichloroethylene (dry cleaning solvents), biphenyls, carbon tetrachloride, herbicides, solvents like dioxane.
- Tannins, griseofulvin, bush tea (pyrrolizidine), rice toxins.
- Anabolic steroids, polyvinyl chloride.

Pathology

Gross

It is highly vascular with indistinct margin. Often it is well demarcated by fibrous tissue. Haemorrhage and necrosis are common.

- *Hanging type of tumour* – tumour attached to normal liver by a small vascular stalk – always very well resectable.
- *Pushing type of tumour* – large, well demarcated, displaces normal vasculature – resectable.
- *Infiltrative type of tumour* – indistinct, infiltrative – often difficult to resect.

Histology

- Well/moderate/poorly differentiated tumour.

Okudas classification – multifocal; indeterminate; spreading; expanding.

Fibrolamellar Variant of HCC (FL HCC)

- FL HCC occurs in younger age group.
- Incidence is equal in both sexes.
- It does not show any elevated levels of serum AFP.
- *Tumour marker for FL HCC type is increase in serum vitaminB_{12} binding protein and increase in neurotensin levels.*
- It is not related to viral hepatitis or cirrhosis.
- Left lobe is commonly involved.
- It involves lymph nodes more commonly than HCC.
- CT scan shows characteristic central scarring.
- Fibrous stromas with thin hyaline bands are typical. Sheets of well differentiated hepatocytes are seen which are sandwiched between collagen and fibroblasts.
- It is fairly resectable (50-75%) with better prognosis than HCC.

Okuda staging system (1984) for HCC

Parameter		*Points*	*Stage*
Tumor size	< 50 %	0	Stage one – 0 points
	> 50 %	1	Stage two – 1-2 points
Ascites	Absent	0	Stage three – 3-4 points
	Present	1	
Serum albumin	< 3 mg %	0	
	> 3 mg %	1	
Serum bilirubin	< 3 mg %	0	
	> 3 mg %	1	

Staging of HCC (AJCC)

T_0 – No tumour
T_1 – Solitary tumour without vascular invasion
T_2 – Solitary tumour with vascular invasion / multiple tumours equal or less than 5 cm
T_3 – Multiple tumours, more than 5 cm/tumour invading major branch of portal or hepatic veins
T_4 – Tumour with direct invasion of adjacent organs other than gallbladder or to visceral peritoneum

N_0 – No regional nodes are involved
N_1 – Regional nodes are involved

M_0 – No distant spread
M_1 – Distant spread is present

Clinical Features

- Painless mass in right hypochondriac region with loss of appetite and weight. Liver is hard, smooth / irregular and often massively enlarged. Cirrhotic liver may be nodular.
- Acute presentation is not uncommon, when the tumour undergoes necrosis and haemorrhage. Both types of presentations mimic amebic liver abscess. (Haemo-peritoneum is also known).
- Jaundice when present is commonly due to hepatic dysfunction, but occasionally due to compression of bile ducts.
- Ascites (40%) often it is massive, splenomegaly and features of portal hypertension may be present.
- Hepatic thrill and bruit - 25%.
- Fever (10-20%) may be present due to tumour necrosis.
- Dull aching pain in right upper quadrant is common.
- Features of chronic liver disease – jaundice, dilated veins, palmar erythema, gynaecomastia, testicular atrophy, etc.
- Liver failure sets in once tumour replaces the functioning liver parenchyma or portal vein gets occluded by tumour thrombus.
- Gastrointestinal bleeding may be the presentation in 10% of cases due to portal hypertension or portal vein invasion by tumour.
- Occasionally may present with para-neoplastic syndromes.

Spread of Tumour

- *Lymphatic spread*: It can spread to other part of liver through lymphatics within the liver, to the lymph nodes in the porta hepatis and other abdominal lymph nodes later. Often spread occurs directly to cisterna chyli.
- *Blood spread*: To lungs, bones and adrenals often can occur.
- *Direct infiltration*: To diaphragm and neighbouring structures.

Differential diagnosis

- Secondaries in liver
- Polycystic disease of liver
- Amebic liver abscess
- Hydatid cyst of the liver



Figs 11.19A and B: CT picture of hepatoma. In right lobe and left lobe.

Investigations

- U/S abdomen – very useful method. It shows hyper echoic mass; mosaic pattern with thin halo and lateral shadows. Extent, tumour thrombi extension can be made out.
- CT scan abdomen (CECT) more reliable and ideal (hypo dense, mosaic, vascular lesion with irregular margin).
  - – reveals the size, location and extent, vascularity, portal vein invasion, nodal status, portal vein thrombosis.
  - – helps to assess operability.
- *Tumour markers - α feto protein (AFP).* AFP will be raised more than 100 IU; as high as 1000 IU is possible in HCC. PIVKA II is des γ carboxy prothrombin protein induced by vitamin K abnormality/antagonists 2. It is increased in 80% of HCC patients. AFP is usually more than 400 IU in 70% of HCC patients.
- Celiac angiography/CT angiography – It shows the vascularity of the tumour, tumour blush, arterial pattern of the liver and tumour; venous phase can show portal vein invasion or thrombosis and invasion/spread to IVC. Angiogram is essential while planning for hepatic resection.
- Liver function tests like serum bilirubin, albumin, enzymes (alkaline phosphatase, transaminase, 5′ nucleotidase) including prothrombin time.
- Liver biopsy is done after controlling prothrombin time if it is elevated (by Inj vitamin K IM 10 mg for 5 days; FFP transfusion). US / CT guided core liver biopsy is useful and mandatory before clinical trials. It is better than FNAC as it reveals tissue architecture. Problems with the core liver biopsy are spillage of tumour and bleeding (due to hypervascularity, associated thrombocytopenia and reduced liver dependent clotting factors like prothrombin). Such problems may be minimal in FNAC. Patients with high suspicious of HCC by clinical and imaging methods and who are appropriate for surgery may be taken up for surgery without a preoperative biopsy. In case of portal vein infiltration by tumour a portal vein biopsy may be done to exclude the patient for surgery or transplantation.
- Contrast MRI/CT scan 1-2 weeks following intrahepatic infusion of lipiodol (ethiodized oil emulsion 5-15 ml) with contrast agent through hepatic artery is very useful.
- MRI – T_2 weighted studies are useful for small HCC. MR angiography is also done to see tumour thrombus in portal vein, hepatic vein and IVC.

In time of test, family is best.

- Ascitic tap when ascites is present for cytology.
- Laparoscopic evaluation and laparoscopic US is useful for proper assessment of the tumour.
- Investigations in relation to hepatitis B and hepatitis C virus infections.
- Metastatic work up – HRCT of chest is essential.

Treatment

Definitive Treatment

- When limited to one lobe, *hemihepatectomy* is done. (Removal of 80% liver is compatible with life). Laparoscopic resection is becoming popular. It is done only to Child's grade A and favourable Child's B group patients. It is the treatment of choice for operable HCC in noncirrhotic patients. There is no regenerative capacity in cirrhotic patients with poor coagulation status, portal hypertension, varices, and ascites.
- In cirrhotic patients with HCC, *total hepatectomy* with *orthotopic liver transplantation* is required. Now it is found that even resection candidates will do better by transplantation than resection. But waiting period for transplantation is long. To bridge this waiting period for transplantation radiofrequency ablation, transarterial embolisation, ethanol/acetic acid injections are used.

Note: Liver mass which is confirmed by CT/MRI and serum AFP is > 500 ng/dl is almost diagnostic and resection treatment can be started without tissue diagnosis.

Indications for transplantation in HCC are –

- Patient who is not a candidate for resection
- Tumour less or equal to 5 cm
- Tumour less than 3 in number
- Tumour without portal/hepatic vein invasion
- Tumour without extra hepatic spread

Palliative Treatment

- *Radiofrequency ablation (RFA)*: It is thermal ablation of the tumour by passing 18 G needle into the middle of the tumour and passing electric current of 500 kHz. This creates frictional heat causing sphere of necrosis. Maximum zone of necrosis which can be created is 7 cm for a 5 cm tumour. This causes adequate cyto destruction of the tumour. Tumour close to vessels and biliary tree, tumour more than 3-5 cm and multicentric tumours are difficult to manage by radiofrequency ablation. One course ablation takes around 20 minutes. It can be done percutaneously under US or CT guidance or through laparoscopy. Percutaneously it can be done on outpatient basis. It can be repeated several times. Tumour less than 3 cm, tumour deep in parenchyma, tumour away from hilum is ideal for radio ablation.
- *Per-cutaneous ethanol or acetic acid injection:* (*Rule of 3* is used here- indicated in HCC not >3cm and not > 3 nodules). Ethanol injection is minimally invasive, can be injected using fine needle, and is cheaper. Local recurrence is lower with acetic acid injection than ethanol. But radiofrequency ablation has got better result than ethanol / acetic acid injection. RFA is costly and not available in many centers.
- *Intra-arterial chemotherapy* using Adriamycin / cisplatin/mitomycin through gastroduodenal artery. It is often given along with lipiodol to make drugs to stay longer time in the liver tissue so that better results are achieved. This regional chemotherapy is much more successful in HCC.
- *Intra-arterial embolisation* using gelfoam, microspheres, gelatin sponge, or chemoembolisation.
- *Microwave or cryo ablations* similar to RFA.
- As it is considered that tumour tissue exclusively gets its blood supply from hepatic artery, *ligation of hepatic artery* can be a good palliation (to achieve tumour necrosis) for HCC. Normal tissue will still have its blood supply from portal vein.
- Transarterial I^{131} lipiodol, Yttrium 90 microspheres.

Adjuvant Therapy

- Systemic chemotherapy using intravenous adriamycin (doxorubicin), cisplatin, carboplatin, mitomycin C, 5 fluorouracil.
- Octreotide is used along with other chemotherapeutic agents. It decreases the size of the tumour.
- Neoadjuvant (preoperative) chemotherapy also practiced to increase the operability/resectability of the tumour.
- Newer treatments are tried using tamoxifen, interferons, EGFR antibody, interleukins, I^{131} lipiodol, Yttrium^{90} microspheres, etc.

Treatment strategies for HCC

- Surgical resection
- Liver transplantation
- Radiofrequency ablation
- Percutaneous ethanol/acetic acid injection
- Transarterial embolisation/chemoembolisation
- Microwave/cryoablation
- Transarterial radiotherapy
- Transarterial Yttrium^{90} microspheres/I^{131} lipiodol
- Hepatic artery ligation
- Adjuvant systemic chemotherapy
- Immunotherapy/hormone therapy/growth factors

Hepatoma/hepatocellular Carcinoma/HCC

- Common etiologies are aflatoxins, hepatitis B and hepatitis C virus infection, alcoholic cirrhosis, haemochromatosis, smoking, hepatic adenoma, clonorchis sinensis, polyvinyl chloride
- Unicentric and right lobe involvement is more common
- Fibrolamellar variant is common in left lobe, not related to hepatitis or cirrhosis without AFP level raise. There are increased serum vitamin B_{12} binding capacity and neurotensin levels
- Invasion to portal veins is common and it has got negative prognosis with lesser chances of resection or transplantation. It may cause portal vein thrombosis and so splenomegaly
- It can be multifocal/indeterminate/spreading/expanding – *Okuda classification*
- Presents as large, smooth, hard liver mass – later jaundice, fever, pain and tenderness, ascites and bruit over mass
- Spreads by lymphatics, blood and direct extension.
- Mimics amebic liver abscess, secondaries, hydatid cyst, poly cystic liver disease
- LFT, CT scan, raised AFP, liver biopsy are the investigations
- *Liver mass, confirmed by CT/MRI and serum AFP > 500 ng/dl is almost diagnostic* and treatment can be started without tissue diagnosis
- Liver biopsy is done (FNAC) only in patients with non-diagnostic level of AFP and not a candidate for curative surgery but only for palliation
- Hemi hepatectomy is the treatment in early operable growth
- Liver transplantation is the good surgical option
- Hepatic artery ligation/intra-arterial chemotherapy/chemo embolisation/percutaneous ethanol or acetic acid injection/radiofrequency ablation/chemotherapy using adriamycin, carboplatin, gemcitabine – are palliative procedures

SECONDARIES IN THE LIVER

It is the commonest malignant tumour in liver. The incidence of primary : secondary : : 1 : 20.

Secondaries are common malignant tumours

- In bone
- In liver
- In brain

Causes

***Abdominal*:** Carcinoma in stomach, colon, pancreas, small bowel, kidney, abdominal oesophagus, rectum, carcinoids.

***Extra-abdominal*:**

- Melanoma.
- Carcinoma breast, lung, thoracic oesophagus, bladder, prostate.
- Testicular and adrenal tumours.
- Follicular carcinoma thyroid (FCT).

Commonly secondaries in liver are multiple, multiple in one lobe or in both lobes. It can be solitary (rare).

Route of Spread

a. *Direct spread*: Stomach, colon, gallbladder, bile ducts.
b. *Hepatic artery*: Melanoma.
c. *Portal vein*: Carcinoid tumours, other GIT malignancies.
d. *Lymphatic spread*: Breast, lung.

Clinical Features

- They are multiple, hard, nodular, with nodule showing umbilication due to *central necrosis.*
- Patient may have jaundice depending on the extent of liver involvement.
- Loss of appetite and weight.
- Ascites.
- Pain in liver secondaries is due to stretching of liver capsule/tumour necrosis. Often pain may be of primary tumour.
- Recto-vesical secondaries—'Blumer shelf'.
- Supra-clavicular lymph node enlargement.



Fig. 11.20: Secondaries in liver. Note the multiple lesions (nodules) in both lobes of the liver.

The best bridge between despair and hope is a good night's sleep.—E. Joseph Cossman

- Clinical features of primary tumour, e.g. stomach, colon—
  - Stomach – Vomiting; visible gastric peristalsis; palpable stomach mass.
  - Colon – Constipation/diarrhoea; palpable mass; features of obstruction.
  - Pancreas – Jaundice; steatorrhoea; itching; palpable gallbladder.
  - History of earlier surgery – Like mastectomy/wide excision of the melanoma.
  - Testis – Fullness; hard mass; loss of testicular sensation.

Clinical features of secondaries in the liver

- Poor general condition
- Palpable liver which is hard, multinodular with umbilication
- Clinical features of primary
- Ascites ±
- Jaundice ±







Figs 11.21A to C: Secondaries in liver are multiple and often with umbilication. CT picture shows multiple secondaries with ascites. On table photo of multiple liver secondaries with umbilication.

Differential Diagnosis

- Multicentric hepatoma.
- Macronodular cirrhosis.
- Polycystic liver disease, hydatid cyst of liver.

Investigations

- Primary is identified by—Gastroscopy, colonoscopy, contrast X-rays, CT scan.
- Liver function tests.
- U/S abdomen – multiple hypo or hyper echoic lesions; site of possible primary; nodal status; ascites.
- Liver biopsy is done, only if primary is not identified by any of these methods.
- Tumour marker: CEA.
- MRI/CT scan whenever resection is indicated.
- Laparoscopy often with laparoscopic US is very useful to detect small secondaries.

Treatment

- Chemotherapy is the treatment of choice.
- *Surgery has a definitive role if primary is from the colon, kidney.*
- If the primary growth is in the colon, then a palliative hemicolectomy is done. Along with that if a solitary secondary in the liver is present, it can be resected. If secondaries are in single lobe, hemihepatectomy is done.

Criteria for selection for liver resection in secondaries in liver, when primary is in colon are-
- Stage of the primary
- Type of primary resection
- Size of the largest liver secondary
- Number of secondaries
- Segments involved
- Associated liver disease like cirrhosis

- Palliative procedures for other primaries like – for carcinoma stomach – palliative partial gastrectomy/ anterior gastrojejunostomy; for carcinoma pancreas – triple anastomosis/ERCP stenting.
- Depending on the site of primary, drugs vary.
  - For carcinoma stomach, mitomycin and 5FU are given.
  - For carcinoma colon, 5-FU, oraloplatinum/VEGF or EGFR antibodies used with folinic acid.
- Hepatic artery ligation or therapeutic embolization with clot/gel foam can be tried to relieve pain.
- Intra-arterial chemotherapy is tried with little success.

Methods other than resection available to ablate the tumour locally in secondaries in liver
- Microwave therapy
- Radiofrequency ablation
- Laser hyperthermia
- Ultrasound or electrolyte therapy

Overall outcome is poor in liver secondaries.

They die of malignant cachexia, infection, liver failure.

Note: Secondaries are said to be *precocious*, wherein liver secondary is first identified, later the primary site is detected (carcinoid tumour/colorectal carcinoma). When primary and liver secondaries are identified at the same time it is called as *synchronous* secondaries (carcinoma stomach). When liver secondaries appear much later after the treatment of primary it is called as *metachronous* secondaries (treated melanoma causing late liver secondaries, carcinoma breast causing late liver secondaries).

Causes of massive enlargement of liver
- Hepatoma
- Secondaries in liver when primary is from melanoma, carcinoid tumour
- Syphilitic enlargement of liver (hepar lobatum)

PORTAL HYPERTENSION

- *Definition*: Sustained elevation of portal pressure more than 12 mm Hg (normal 8-12 mmHg).



Fig. 11.22: Anatomy of the portal system.

- Left sided portal hypertension (***sinistral***) can be caused by isolated splenic vein thrombosis, which is often caused by adjacent pancreatitis.
- A rise in portal pressure stimulates porta-systemic circulation.
- Portal vein carries 75% of blood flow to liver with all nutrients to maintain its integrity and gives 50% oxygen supply to liver. 25% hepatic blood flow gives remaining 50% of oxygen supply to liver.
- Portal hypertension causes compensatory porto systemic venous collateral formation, altered intrahepatic circulation and increased splanchnic blood flow. High pressure portal blood is diverted via coronary (left gastric vein), short gastric and esophageal veins into azygos venous system.
- There is increased portal resistance and increased portal blood flow. Increased resistance may be presinusoidal, sinusoidal and postsinusoidal.
  - *Presinusoidal*
    - Extrahepatic – portal vein/splenic vein thrombosis.
    - Intrahepatic – schistosomiasis, sarcoidosis.
  - *Sinusoidal* – cirrhosis, haemochromatosis, Wilson's disease, congenital hepatic fibrosis.
  - *Postsinusoidal* – Budd - Chiari syndrome, congestive heart failure, veno occlusive disease.
- 30% of varices patients will bleed; 30% of them will die of bleed; 30% of patients with cirrhosis will develop portal hypertension; 30% of them have variceal bleed in 2 years; 70% of patients who had bleeding once, will rebleed later.
- Variceal bleed accounts for 7% of upper GI bleed.
- In western country more than 90% cases cirrhosis is the cause. In India extrahepatic portal vein obstruction (33%) and extrahepatic periportal fibrosis (33%) is

A superior man is modest in his speech, but exceeds in his actions.

becoming more common. As liver is normal in these two conditions, patients get better cure rate by shunt surgery.

Sites of Porta-systemic Collateralization (Refer Fig. 11.23)

1. *Lower end of oesophagus*, between left gastric and short gastric veins with azygos vein resulting in *oesophageal varices*—commonest.
2. *Umbilicus,* between paraumbilical vein and anterior abdominal vein resulting in *caput medusae.*
3. *Lower end of rectum,* between superior haemorrhoidal vein and inferior, middle haemorrhoidal vein resulting in *piles.*
4. *Retroperitoneum* (vein of Retzius).
5. *Bare area of the liver.*



Fig. 11.23: Porta-systemic collaterals.



Fig. 11.24: Photo showing caput medusae.

Presentations

- *Triad of portal hypertension*
  i. Oesophageal varices.
  ii. Splenomegaly.
  iii. Ascites.
- Jaundice.
- Features of encephalopathy.
- Recurrent infection.
- Coagulopathy.
- Hepatorenal syndrome.

Investigations

- Liver function tests.
- Ultrasound.
- Alfa-feto protein.
- MELD scoring is Model for End stage Liver Disease, is assessed by specific equation using creatinine and bilirubin.
- Child – Pugh score system.

Causes of portal hypertension

Prehepatic	*Hepatic (80%)*	*Posthepatic*
Portal vein or splenic vein thrombosis Hypercoagulable status Periportal inflammation Trauma Extrinsic compression from pancreas, stomach Neonatal umbilicus sepsis	Portal pyaemia Alcoholic cirrhosis Idiopathic portal hypertension Primary biliary cirrhosis Schistosomiasis Hepatitis Nodular regenerative hyperplasia Wilson's disease Haemochromatosis Congenital hepatic fibrosis	Budd-Chiari syndrome Constrictive pericarditis Congestive cardiac failure Veno-occlusive disease

Note: Commonest prehepatic cause of portal hypertension is portal vein thrombosis.



Fig. 11.25: Patient with portal hypertension showing massive ascites with oedema of limb and scrotum – end stage liver disease.

- Serological assessment – AFP, iron studies, α_1-antitrypsin, ceruloplasmin, autoantibodies, investigations for hepatitis.
- Doppler imaging to see vascular pattern, direction of blood flow, size of the vein.
- CT/MRI to look for cause, see collaterals and liver nodules.
- Hepatic venous pressure gradient (HVPG) – It is done using a balloon catheter. Difference between free hepatic vein pressure and wedged hepatic vein pressure is HVPG. Normal HVPG is 8 mm Hg. It is more than 10 mm Hg in cirrhosis.
- *Splenoportography –*
  - Bleeding/clotting time and prothrombin time should be normal prior to the procedure.
  - Antibiotic prophylaxis is a must.
  - A fine lumbar puncture needle is passed into the spleen through left 9th intercostal space in mid axillary line. It is placed into the pulp of the spleen.
  - Splenic pressure is assessed by connecting to a manometer.
  - Water soluble iodine dye is injected under C arm guidance. Flow, anatomy of portal system, size of the splenic/portal vein, site of the obstruction, communications are assessed.
  - Complications are – bleeding, infection, left shoulder pain.
  - Its use is replaced by MR angiogram/celiac angiogram.
- GI scopy.
- Liver biopsy.
- Splenoportography.
- Endosonography.



Fig. 11.26: Laparoscopic view of cirrhosis with nodules on the surface.



Figs 11.27A and B: CT scan pictures showing ascites, splenomegaly.

Venous hum in epigastrium observed in portal HT is called as Kenawy's sign.

Management of Portal Hypertension

a. *General measures:*
   - Anemia to be corrected.
   - Nutrition supplementation.
   - Inj. vit. K – 10 mg IM for 5 days.

b. *Specific measures:*
   - *Treatment of oesophageal varices*
   - *Prevention of hepatic encephalopathy.*
   - *Treatment of ascites.*
   - *Measures to reduce portal pressure —*
     - Surgeries—Porta-systemic shunt.
       - Non-selective.
       - Selective.
     - TIPSS.
     - Drugs to reduce the portal pressure like propranolol, nadolol, isosorbide-5-mononitrate.
   - *Liver transplantation.*

OESOPHAGEAL VARICES

- May be asymptomatic.
- May present with *haematemesis* or *melaena* or as *recurrent bleeding*. Varices begin to bleed when portal pressure exceeds 12 mmHg.
- When present with severe haematemesis, patient shows features of *shock*.
- Mortality in bleeding varices is 25-30%.
- Factors related to variceal bleed are – portal venous pressure; gastro oesophageal reflux causing ulceration; variceal size; variceal wall tension.

Types of Varices

1. *Oesophageal* which is in the lower 1/3rd of the oesophagus, usually 3 or more in number, graded as I, II, III, IV (based on gastroscopic findings) (80%).
2. *Gastric* which is fundal or in upper part of the stomach (20%).
   For differential diagnosis refer Table in page 555.

Gastric Varices

Classification

A. Extension of oesophageal varices
   I. In to lesser curve
   II. Into fundus
B. Isolated gastric varices
   I. In fundus common
   II. In other parts—stomach, duodenum—rare



Fig. 11.28: Picture showing variceal bleed.

Gastric varices are *treated by endoscopic N butyl cyanacrylate glueing, sclerotherapy*. Banding is usually not done.

Investigations

- Hb%, liver function tests, packed cell volume, blood grouping and crossmatching, prothrombin time, platelet count, blood urea, serum creatinine.
- Endoscopy—*Grading of varices:*

I. Minimal varices without luminal prolapse
II. Moderate varices, with luminal prolapse and with minimal obscuring of O-G junction
III. Large varices, with luminal prolapse and with moderate obscuring of O-G junction
IV. Very large varices, with luminal prolapse and with complete obscuring of O-G junction

"Cherry red spots" may be sign of impending rupture.

Endoscopic sclerotherapy or variceal band ligation should be tried in acute bleed also, while doing initial endoscopy to confirm the variceal bleed. If facility for sclerotherapy is not available or sclerotherapy/banding fails or not possible due to massive bleed, then balloon tamponade should be used.

Occasionally patient may be having varices, but bleeding (upper GI bleed) is due to other causes like duodenal or gastric ulcer.

- Once acute bleed stops patient is investigated further by splenoportography, liver biopsy, and superior mesenteric or celiac angiography, MR angiogram.

Note: **Cruvielhier-Baumgarten syndrome** is loud venous hum heard at umbilicus in case of portal hypertension.



Figs 11.29A to C: Different grades of oesophageal varices—endoscopic views.



Fig. 11.29D: Active spurting variceal vessel. Endoscopic variceal banding is gold standard for oesophageal varices. It is not very useful for gastric varix.



Fig. 11.29E: Typical tortuous gastric varix and cyanacrylate glue injection to the same.

- U/S abdomen to see status of the liver and portal vein (size *more than 13 mm* is significant).

Treatment of Oesophageal Varices

- Treatment of varices prior to bleed (no history of earlier variceal bleed) – *primary prophylaxis.*
  - Drugs – propranolol (reduces the portal pressure by 20% with pulse rate below 55/minute or 25% of resting pulse); nadolol (long acting, less lipophilic, not metabolized by liver); isosorbide mononitrate. Drugs reduce bleeding by 40%.
  - Endotherapy.

  Note: No prophylactic shunt surgeries.
- Treatment of varices after one or more episodes of bleeding – *secondary prophylaxis.*
  - Endotherapy.
  - Shunt surgeries.
  - Drugs like propranolol. Drugs may prevent rebleed by 40%.

Treatment of varices is considered under two headings –

- Emergency management of bleeding varices.
- Definitive management of varices.

Glyceryl trinitrate should be given along with vasopressin to prevent coronary vasospasm.

EMERGENCY MANAGEMENT IN SEVERE HAEMORRHAGE

Control of acute bleed

- Initial important measures
  - Volume and electrolyte corrections; volume replacement using crystalloids with central line (CVP line placement with CVP maintained at 5 cm of water, sudden overload should be avoided which may precipitate pulmonary oedema/ascites/hyponatraemia)
  - Blood (massive transfusion of 5,10, 15 bottles) and blood products (FFP, platelets) replacement endotracheal intubation, ventilator, critical care/ICU management
  - Antibiotics, nutrition (TPN)/Vitamin K injection
  - Catheterization and hourly urine output monitoring
  - Prevention of encephalopathy
  - Rest/sedation only if needed with care
- Pharmacotherapy
- Endoscopic banding/sclerotherapy
- Balloon tamponade
- TIPSS
- Devascularisation surgical procedures

Pharmacotherapy (Drugs)

- Inj. Vasopressin 0.4 units / min for 24 hours is commonly used. 20 units in 100 ml 5% dextrose IV in 20 minutes also can be given. Vasopressin infusion is combined with glyceryl trinitrate tablets sublingually (to reduce cardiac side effects and increase the efficacy). Vasopressin is contraindicated in ischemic heart disease as it causes coronary vasoconstriction. Nitroglycerin prevents the coronary vasoconstriction and also reduces the portal pressure. Vasopressin can cause fluid retention and hyponatraemia.
- Glypressin (terlipressin), desmopressin. Glypressin 2 mg IV bolus 5th hourly is better than vasopressin. It has got longer half life with fewer side effects.
- Somatostatin—half life 2 minutes. Somatostatin does not cause systemic vasoconstriction like vasopressin but reduces the splanchnic and hepatic blood flow. It is given as continuous IV infusion 250 µg/hour after an initial bolus of 250 µg.
- Octreotide—half life 2 hours. 50 µg IV bolus and 50 µg/hour for 5 days.
- Propranolol decreases the portal pressure. It is used at later period as prophylaxis to prevent bleeding. Nadolol is also used which has got a longer half life.
- Metoclopramide (20 mg IV, it causes lower oesophageal sphincter constriction); isosorbide 5 mononitrate which is not metabolized in liver can be safely used in patients in liver failure.
- Acid inhibiting drugs (ranitidine IV, pantoprazole IV); and antifibrinolysins (tranexamic acid) are also used.

Endoscopic Therapy

Endotherapy – banding/sclerotherapy/glueing is used to control acute bleed as well as to prevent further bleeding. Pharmacotherapy is often combined with endotherapy.

1. *Endoscopic variceal banding (EVB)*
   - It is done for oesophageal varices. Banding/band ligation has become *gold standard and ideal* for oesophageal varices.
   - Multishoot banding device is used.
   - It is not commonly done for gastric varix as banding is difficult in retroflexed position.
   - Banded varices thrombose and slough off leaving small discrete ulcers.
   - It controls the bleeding in 90% cases. It is technically easier; chances of rebleeding are less; complications like perforation or stricture are less.
   - Earlier single band application device was used. It should be passed through an oesophageal overtube as it requires repeated endoscopy for shooting many bands. Multishoot banding device/applicator carries 5/6/8/10 bands. It does not require repeated removal and insertion of endoscope and so overtube can be avoided.
2. *Endoscopic sclerotherapy (EVS)*
   - Endoscopic sclerotherapy is also commonly used. It is technically easier, and cheaper.
   - Both intravariceal and paravariceal or only intravariceal injections are given.
   - In large varix lower part and upper part of the varix is sclerosed. Around 6 ml of sclerosant to lower part and 2-3 ml to upper part is injected. In small varix, injection is sufficient to only lower part.
   - In combined para and intravariceal injection, first paravariceal injection is done into submucosal plane followed by intravariceal injection.
   - Sclerosants used are – ethanolamine oleate (5%); sodium morrhuate (2-5%); sodium tetradecyl sulphate; polidocanol (3%).
   - Varices should not be injected blindly.
   - In acute bleed it is better to insert an endotracheal tube to the patient and give 45° elevation to the head end of the table.

- Complications— Fever, retrosternal pain, massive bleed, perforation, mediastinitis, stricture oesophagus.
- Sclerotherapy is done weekly for 6-8 sessions until varices are obliterated. Later follow up endoscopy is done once in 3 months for 6 months; and once in 6 months for 2 years; then yearly for life time.
- Sclerotherapy causes 70- 80% control of bleeding but rate of re-bleed is higher than banding.

3. *Endoscopic gluing using tissue adhesives*
   - It is commonly used for gastric varices.
   - Butyl cyanoacrylate is used. It hardens in 20 minutes. If properly injected into the varix it controls the bleeding immediately with 90% success rate.
   - Risk of equipment damage is high if it spills into the working channel and blocks it. Lipiodol is used along with cyanoacrylate to delay premature hardening. Silicone oil is applied to the tip of the instrument to prevent the damage.
   - Needle tip is correctly placed into the gastric varix and 0.5 – 1 ml of adhesive is injected. Instrument should be removed immediately.
4. *Endoscopic thrombin / dilute adrenaline injection into the varices.*



Fig. 11.30: Child with Sengstaken – Blakemore tube for haematemesis showing three channels.



Fig. 11.31: Sengstaken-Blakemore tube showing how it controls the bleeding varices. Oesophageal balloon is inflated with 40 mm Hg pressure of air, Gastric balloon with 400 ml of air.

Balloon Tamponade

- Four lumen Minnesota tube/Sengstaken - Blakemore tube/Linton's tube / modified 4 lumen Pitcher tube are used for the procedure. If bleeding does not stop by banding/sclerotherapy/gluing, balloon tamponade should be tried. Most of the time bleeding comes under control by balloon tamponade.
- Initially gastric balloon is inflated with 300 – 400 ml of *air*, later the oesophageal balloon is inflated with air at 30 – 40 mm Hg pressure. This should be deflated for a short period in 12 – 24 hours so as to prevent necrosis of oesophageal mucosa. Inflation of gastric balloon is most important. Oesophageal balloon inflation is done if needed only.
- X-ray should be taken to confirm the position of balloons.

Sclerotherapy

Sclerosants used	*Method of injection*	*Problems with sclerotherapy*
Ethanolamine oleate (5%) Sodium tetradecyl sulphate (1-3%) Sodium morrhuate 2 – 5% Polidocanol 3% Absolute alcohol	Both intravariceally (6 ml) as well as para variceally (2-3 ml) to create thrombosis as well as fibrosis Repeated sessions in 2-3 weeks Total 15 ml in one session	Oesophageal ulceration Oesophageal perforation Worsening of bleeding Aspiration pneumonitis Difficult to inject gastric varices Chest pain and dysphagia are common

Everyone should be quick to listen and slow to speak.

- Usually within 24 - 72 hours bleeding comes under control and in mean time resuscitative measures has to be undertaken. Success rate is very good but only temporary. It should be followed by definitive procedures like banding/sclerotherapy. Otherwise rebleed rate is 60%. Balloon tamponade is only a rescue procedure and emergency bridging method for more definitive procedures.



Fig. 11.32: Types of sclerotherapy.



Fig. 11.33: Endoscopioc view of variceal banding. Endoscopic variceal banding (EVB) is done for oesophageal varices. Not commonly used for gastric varices.

TIPSS (Transjugular Intrahepatic Porta Systemic Shunt / Stenting)

It is used if all other earlier methods mentioned have failed, in less than 10% of acute bleed patients. It commonly controls the uncontrolled acute bleeding and prevents further bleed and also acts as *a bridge* for future transplantation.

- **Surgeries for acute bleeding varices:**
  - *Open oesophageal stapler transection and oesophago-gastric anastomosis* (Jhonston)**.**
  - *Borema—Crile operation*: The oesophagus is opened. Oesophageal varices are under-run using vicryl**.**
  - *Sugiura—Futagawa* operation: Oesophago-gastric transection and devascularization, vagotomy, pyloroplasty and splenectomy.
  - *Milnes –Walker* thoracic oesophageal transection
  - *Tanner's* abdominal oesophago gastric resection.
  - *Hassab* operation.

  Shunt surgeries are not commonly used to control bleeding in acute stage.

  Note: Once a bleed, there will be always a rebleed without treatment and rebleed is much more severe than earlier bleed. Time gap between each rebleed shortens.
- **Other measures**
  - *Liver biopsy* to confirm the cause for the portal hypertension.(after controlling PT).
  - *Correction of clotting mechanisms* by Vit. K, blood, plasma or platelet concentrate.
  - *Control of encephalopathy*
    - Purgatives
    - Protein free diet
    - Lactulose syrup 30 ml tid
    - Lactitol
    - Neomycin orally—1.5 g 6th hourly
    - Parenteral nutrition

DEFINITIVE MANAGEMENT OF VARICES

- ***Sclerotherapy.***
- ***Shunt surgery.***

  Prophylactic shunt surgery should not be done.

  Shunt surgeries should not be done if the varices have not bled before.

Indications

Child's Grades A and B.

(Child's grading is used for selecting patients for surgery and predicting prognosis.)

Surgery is contraindicated in Child C.

1. **Non-selective shunts**:
   - ***Porta-caval shunt*** (end-side, side-to-side).
   - Mesenterico-caval shunt with or without graft.
   - Mesenterico—renal shunt.
   - *Proximal splenorenal shunt—Linton's shunt.*

   Non-selective shunts control and prevent further bleeding as well as reduce the ascites. But since it diverts the blood from liver *there is high incidence of encephalopathy.*

   Note: End to side porta caval shunt is called as ECK fistula.
2. **Selective shunts:**
   1. ***Distal spleno-renal shunt—Warren's shunt.*** End of splenic vein is shunted to the side of the left renal vein. Splenic vein should be more than 10 mm in size (diameter). It selectively decompresses the portal bed near oesophago-gastric area (so that it

prevents bleeding). Liver is also perfused adequately and so possibility of encephalopathy is less.

2. ***Inokuchi shunt*** is a selective shunt between IVC and left gastric vein (using a graft).

- ***Splenectomy***

Left sided portal hypertension also called as *segmental portal hypertension* (sinistral portal hypertension) is due to splenic vein thrombosis. (If partial channels are present within it, it is called as *splenic vein cavernoma*.) Here liver is normal and *splenectomy* alone will correct the condition.

- ***TIPSS (Transjugular Intrahepatic Porta Systemic Stenting/Shunt)***

– Size of stent must be 10 mm. It is a nonsurgical, interventional radiological method wherein a stent is placed in the liver between hepatic venule and portal venule through a guide wire following dilatation.

– It is a simple and easier method to reduce portal pressure.

– It can cause hepatic encephalopathy, bleeding, bile leak and infection.

– It is contraindicated in encephalopathy, tumours and liver cysts.

– It is quite useful as a temporary measure to reduce portal bed pressure, before doing orthotopic liver transplantation in cirrhotic patients.


Guidewire
Liver
Spleen
Liver
Spleen
Stent

Fig. 11.34: TIPSS.

Child's grading of the severity of liver disease			
Clinical and biochemical measurement	**Points scored**		
	1	2	3
Bilirubin (mg/dl)	< 2.0	2.0-3.0	> 3.0
Albumin (gm/dl)	> 3.5	3.0-3.5	< 3.0
Ascites	None	Controlled	Uncontrolled
Mental status	Normal	Disoriented	Coma
Nutrition	Very good	Good	Poor
Total Score	**< 6** *Child's 'A' disease*	**7-9** *Child's 'B' disease*	**10-15** *Child's 'C' disease*
(Pugh's modification) Prothrombin time seconds prolonged	Increase upto 3	Between 3-6	> 6


Portocaval shunt
Portal vein
Splenic vein
Spleen
Inferior mes vein
Kidney
Kidney
IVC
Superior mesenteric vein

Fig. 11.35: End to side portocaval shunt (ECK fistula).


Portocaval shunt
Portal vein
Splenic vein
Spleen
Inferior mes vein
Kidney
Kidney
IVC
Superior mesenteric vein

Fig. 11.36: Side to side portocaval shunt.

SAAG means Serum, Ascites, Albumin, Gradient.


Portal vein
Splenic vein
Spleen
Inferior mes vein
Kidney
Kidney
IVC
Mesentericocaval shunt
SMV
CIV
CIV

Fig. 11.37: Side to end mesenterico caval shunt.


Portal vein
Splenic vein
Spleen
Inferior mes vein
Kidney
Kidney
Superior mesenteric vein
IVC
Mesentericocaval shunt (graft)

Fig. 11.38: Side to side mesentericocaval shunt using a graft.


Splenic vein
Spleen (removed)
Inferior mes vein
Portal vein
Proximal splenorenal shunt
Kidney
Kidney
IVC
SMV

Fig. 11.39: Proximal splenorenal shunt (Linton's).


Left renal vein
Spleen
Splenic vein
Portal vein
IMV
Kidney
Kidney
Distal spleno-renal shunt
IVC
SMV

Fig. 11.40: Distal splenorenal shunt (Warren's, DSRS)—selective.


Oesophagus
Stomach
Gastrotomy
Stapler (end to end)
Duodenum

Fig. 11.41: Oesophageal open stapler transection.

Problems with TIPSS

- Post stent encephalopathy—40%
- Stenosis (50%) and recurrent varices
- Bleeding
- Bile leak
- Sepsis

Surgeries for portal hypertension

- Devascularisation surgeries
- Decompression surgeries
- Orthotopic liver transplant (OLT)

Surgeries for oesophageal varices and portal hypertension

Nonselective shunts

- End to side porta caval shunt (ECK fistula)
- Side to side porta caval shunt
- Mesenterico caval shunt
- Mesenterico caval shunt with graft
- Proximal splenorenal shunt—Linton's shunt
- TIPSS

Selective shunts

- Distal spleno renal shunt—Warren's shunt
- Inokuchi shunt between left gastric vein and IVC through a graft.

Porta azygos disconnection

- Oesophageal stapler transection of Johnston
- Boerema—Crile operation—thoracic approach
- Milnes—Walker thoracic oesophageal transection
- Tanner's abdominal oesophago gastric transection
- Hassab operation. Devascularisation and splenectomy.
- Sugiura—Futagawa operation—vagotomy, pyloroplasty, devascularisation, splenectomy.
- Splenectomy

Liver transplant

- ***Liver transplant (orthotopic)***

Liver transplant is becoming popular for cirrhosis with varices. It is ideal, final and best. But donor availability and cost is the problem. If patient is for orthotopic liver transplantation (OLT), open shunt surgeries should not be done as liver hilum should be kept virgin for effective transplantation. TIPSS can be done as a bridge in such patients.

PORTAL HYPERTENSIVE GASTROPATHY

- Portal hypertension causes vascular dilatation and ectasia in the stomach which appears pink, speckled, with red mosaic pattern in the gastric mucosa. It occasionally causes upper GI bleed (5% of total; 20% of portal hypertension bleed). Endoscopy is diagnostic.
- Mucosal changes are diffuse and so not amenable for endotherapy.
- Portal gastropathy is more common in cirrhotic patients.
- Commonly presents with chronic bleed causing anaemia; but acute bleed with haematemesis and melaena also can occur.
- Treatment is mainly to reduce the portal pressure using propranolol.

ASCITES

It is the collection of fluid in the peritoneal cavity.

Types

- Mild — up to 150 ml.
- Moderate — 1500-2000 ml.
- Severe — > 2000 ml.

Management of oesophageal varices

Emergency management in acute bleed	*Definitive management*	
1. Balloon tamponade	1. Sclerotherapy, Banding, Glueing	
2. Pharmacotherapy	2. Nonselective shunts:	Porta caval
3. Oesophagogastric transection		Mesentericocaval
4. Borema—Crile operation		Mesentericorenal
5. Sugiura—Futagawa operation	3. Selective shunts:	Distal-splenorenal shunt
6. Sclerotherapy		Inokuchi shunt
	4. Splenectomy	
	5. TIPSS	
	6. Liver transplant	

Differential diagnosis for oesophageal varices (Other causes for haematemesis)

Bleeding peptic ulcer
Mallory-Weiss syndrome
Bleeding disorders
Gastric polyps
Gastric lymphoma
Carcinoma stomach
Acute erosive gastritis
Dieulafoy's syndrome
Gastric leiomyoma

During infancy until about the end of the third year the normal liver extends one to two finger breadth below the costal margin. During inspiration at this period of life, the extreme edge of normal spleen is also palpable.

Classification

- *Transudate* (Protein < 2.5 gm/ dl).
  - CCF—Commonest (SAAG > 1.1).
  - Hypoproteinaemia.
  - Anaemia.
  - Beri-beri.
  - Nephrotic syndrome.
  - Portal hypertension.
  - Polyserositis.
- *Exudate* (Protein > 2.5 gm/dl) (SAAG < 1.1).
  - Peritoneal diseases.
    - Tuberculosis.
    - Bacterial, fungal and parasitic infection.
    - Neoplasm.
  - Collagen disorder.
  - Eosinophilic gastroenteritis.
  - Granulomatous peritonitis.

Clinical Features

Symptoms

- Gradual distention of abdomen
- Severe cases of ascites may lead to respiratory embarrassment.
- Specific features related to the cause may be evident.
- Risk of spontaneous bacterial peritonitis.

Signs
Mild—

- *Puddle sign*—Tapping around the umbilicus in knee-elbow position elicits dullness.

Moderate—

- Positive shifting dullness in the abdomen.

Severe—

- Positive fluid thrill.
- *Tanyol sign*: Umbilicus is shifted upward in pelvic mass (ovarian cyst) downwards in ascites.

Investigations

- U/S abdomen.
- Ascitic tap –Always should be done after emptying the bladder by placing the needle below the umbilicus lateral to the rectus muscle. It may be *Diagnostic* or *Therapeutic tap*. Fluid is sent for analysis.

Treatment

- The cause is treated.
- Therapeutic tap—It should be slow and gradual or staged tapping. Up to 5 litres can be tapped in 90 minutes.
- Ascitic shunt surgeries.
- Spironolactone, salt restriction.

ASCITES IN PORTAL HYPERTENSION

Causes

- Hypoproteinaemia.
- Increased hydrostatic pressure.
- Decreased colloidal osmotic pressure.
- Lymphatic blockage.
- Altered aldosterone mechanism.

Complications of ascites

- Umbilical hernia with erosion, ulceration and leak
- Respiratory embarrassment
- Spontaneous bacterial peritonitis

Treatment of ascites in portal hypertension

- Medical – spironolactone, salt restriction
- Abdominal paracentesis
- TIPS as a bridge to liver transplant
- Liver transplantation

ABDOMINAL FLUID

- *Straw Coloured Fluid*
  - Cirrhosis
  - Tuberculosis
  - Hypoproteinaemia
  - Nephrotic syndrome
  - Budd-Chiari syndrome (Hepatic vein thrombosis)
  - Constrictive pericarditis
  - Chronic pancreatitis
  - Ovarian tumour (Meig's syndrome)
  - Malignancy
- *Haemorrhagic fluid*
  - Traumatic tap
  - Tumour
  - Acute haemorrhagic pancreatitis
  - Bleeding disorder
- *Chylous fluid*
  - Parasitic infestation—Filariasis
  - Tuberculosis
  - Malignancy of thoracic duct
  - Trauma to thoracic duct
  - Thrombosis of subclavian vein
- *Purulent fluid*
  - Abdominal infections.
  - Penetrating wounds or infections
  - Pyaemia and septicaemia
  - Rupture/perforation of an organ



Fig. 11.42: Ascites. Observe the dilated abdominal veins.

Investigations

Liver function tests, U/S, CT scan, MRI, gastroscopy.



Fig. 11.43: Massive ascites in severe portal hypertension.

Treatment

- Correction of serum proteins, salt restriction**.**
- *Ascitic tap*—Site of tap is below the umbilicus, lateral to the rectus muscle. Bladder should be empty before tapping. Slow gradual tapping is important, otherwise patient goes in for fluid and electrolyte imbalance. Up to 5 litres can be tapped at a time.
- *Spironolactone* 25 mg orally BD and other diuretics are often used.
- ***Le Veen shunt*** is a one way valve *peritoneo-venous shunt* done in order to drain ascitic fluid from peritoneal cavity to internal jugular vein**.**
- ***Denver* shunt** is similar to Le Veen type with additional facility of having a chamber to evacuate the debris by digital pressure.
- *Liver transplantation* may be beneficial for ascites in liver diseases.
- The cause is treated.
- TIPSS.

Ascitic shunts are not used when there is

- Hepatorenal syndrome
- Bacterial peritonitis

Complications of Ascitic Shunt Procedure

- Bleeding.
- Infection.
- Displacement.
- Blockage.
- Thrombosis of the vein.
- Volume overload.

BUDD-CHIARI'S SYNDROME

It is a syndrome due to obstruction of the hepatic veins.

Causes

1. Spontaneous thrombosis of hepatic veins (due to myeloproliferative diseases (50%) commonly seen in adults and IVC webs commonly seen in children).
2. Neoplastic encroachment of hepatic veins.

} Majority of cases

3. Polycythaemia.
4. Contraceptive pills.
5. A membranous web in supra hepatic portion of IVC—a curable type of Budd-Chiari syndrome.
6. Plant extracts of Senecio and Crotalaria used in herbal tea in Jamaica causes acute Budd Chiari syndrome.

Clinical Features

1. *In acute form:* Nausea, vomiting, severe pain in right hypochondrium, rapid enlargement of liver, hypotension and often death.
2. *In less sudden onset type:* Rapid development of ascites, hepatic insufficiency, oedema feet, features of IVC obstruction, hepatic coma can occur.
3. *Chronic type:* Present with hepatic cirrhosis, ascites, oesophageal varices, infection, which gradually leads to hepatic failure.

Treatment

- In membrane obstructing IVC, it can be cut by trans-atrial meatotomy, i.e. under guidance, a catheter is passed, via right atrium to IVC and the web is cut. It is curable.
- In other types of porta caval or mesocaval shunts are tried but results are equivocal.
- Meso atrial shunt between right atrium and SMV using Gortex graft.

Efforts and energies should be consistent, constructive and compassionate.

HEPATIC FAILURE

Etiology

- Cirrhosis.
- Congenital diseases.
- Terminal liver diseases.
- Drug induced.
- Fulminant hepatitis.

Precipitating Causes

- Infection.
- GIT bleeding.
- Surgery.
- General anaesthesia.
- Drugs—narcotics, analgesics.
- Old age.
- Electrolyte abnormality—hypokalaemia.

Clinical Features

- Weakness and jaundice.
- Cyanosis.
- Fever, fetor hepaticus.
- Features of hyperdynamic circulation: Bounding pulse, flushed extremities, fresh crops of spider naevi, palmar erythemas.
- Loss of axillary and pubic hairs.
- In male, gynaecomastia and testicular atrophy.

Fulminant Hepatic Failure

It occurs as a result of massive liver cell death due to:

1. Acute viral hepatitis.
2. Drugs like carbon tetrachloride, halothane, cytotoxic drugs.

Presentation

- Sudden onset of the disease
- Personality changes
- Delirium
- Altered behaviour
- Oliguria and kidney failure

Treatment

- Correction of precipitating factors, e.g. GIT bleed, infection, hypokalaemia.
- High carbohydrate diet.
- IV fluids or nasogastric feeding.
- Diuretics and morphine is avoided as it may precipitate coma.
- Correction of hypoglycaemia and electrolytes.
- Management of renal failure by haemodialysis.
- Correction of clotting factors.
- Temporary hepatic support like—
  - Exchange blood transfusion
  - Cross circulation between donor and patient
  - Extracorporeal perfusion of patient's blood through pigs liver.
  - Perfusion through columns of activated charcoal.

HEPATIC ENCEPHALOPATHY

It is a chronic neuropsychiatric disorder wherein blood bypasses the liver, as a result of which, detoxification of *toxic products* do not occur, which, in turn enters the brain to cause toxicity.

Toxic Products

1. Ammonia.
2. Amino-butyric acid.
3. Mercaptan.
4. Methionine.
5. Short chain fatty acids.

Collaterals developed in chronic liver disease like cirrhosis or after shunt surgeries, allow the blood with toxic products to enter the brain causing toxic effects (As toxic products of bacterial degradation, and nitrogenous material from the bowel is normally metabolized in the liver, these toxic products bypass the liver through collaterals to enter the cerebral circulation.).

Encephalopathy is precipitated by—

- Large protein meal.
- GIT bleed.
- Hypokalaemia.
- Drug induced diuresis.
- Uraemia.
- Narcotics.
- Infection.
- Dehydration.
- Constipation.

Clinical Features

- Disorientation, flapping tremor.
- Cogwheel rigidity of limbs, ankle clonus.
- Slurred speech, intellectual deterioration.
- Personality changes.

Grading of hepatic encephalopathy

- Decreased skills—Subclinical
- Confusion—Grade 1
- Drowsiness—Grade 2
- Somnolence, hyperreflexia—Grade 3
- Coma—Grade 4

Treatment

To reduce the entry of nitrogenous products and toxic products from the gut into the circulation.

- Restriction of dietary protein.

- Removal of blood from bowel by purgation or enemas.
- Antibiotics administration.
  Oral neomycin to reduce bacterial load inside the bowel lumen. 1 gm 4-6 hours or metronidazole 250 mg every 8 hours.
- Oral lactulose 30-50 ml 4 times a day.
- Sedatives like benzodiazepines and opioids are avoided.
- Correction of vitamin and electrolyte deficiencies.
- Lactulose enema: 300 ml of lactulose in 700 ml of water can be given.

HEPATO-RENAL SYNDROME

- It is development of acute renal failure due to severe hepatic or biliary disease with jaundice.
- Patient develops oliguria, azotaemia and hyponatraemia.

Causes

- Bile salt sludging in the tubules.
- Absorption of toxins.
- Increased ADH release.
- Hypoperfusion and renal ischaemia.
- It may be precipitated by surgery, stress.

Treatment

- Mannitol infusion.
- Diuretics.
- The cause is treated.
- Dialysis.
- Liver transplantation.

HEPATIC RESECTION

Indications

- Parasitic and non-parasitic cysts.
- Benign and primary malignant tumours of the liver.
- Secondary tumour that involves by direct extension like from carcinoma of gallbladder or limited secondaries from carcinoma colon/carcinoids.
- Trauma to liver.

Contraindication

- Advanced cirrhosis.

Anatomy and Types of Resections

- Right hepatic artery divides into anterior and posterior segmental arteries. Left hepatic artery divides into medial and lateral segmental arteries.
- Portal vein divides at porta hepatis as right and left branches and these branches enter the respective lobes of the liver.
- Hepatic veins originate as central vein of the liver which is formed by liver sinusoids. Middle hepatic vein is located in main lobar fissure. Left hepatic vein is in left segmental fissure – upper portion; right hepatic vein is in right segmental fissure. Inferior part of middle and anterior segments are drained by middle hepatic vein. In 60% of cases middle and left hepatic veins join to form single trunk to enter IVC.
- Main portal fissure divides liver into two lobes by Cantlie's line from anteroinferior part of gallbladder fossa to left of the IVC with 75° angle with horizontal plane. It divides into right/left paramedian sectors/segments.
- Liver is divided into 8 segments (Couinaud segments). Right lobe is formed by segments V, VI, VII, VIII from front to behind. Left lobe formed by segments II, III and IV. Segment I (Spigel lobe) is caudate lobe which has got independent blood supply.
- Resection along the main portal fissure (Cantlie's line) and removal on right side is *right hemihepatectomy* and removal on left side is *left hemihepatectomy*.
- Resection on right of the ligamentum teres is called as *right trisegmentectomy* (older – right lobectomy); and left of the ligamentum teres is called as *left lateral segmentectomy*- segment II and III (older left lobectomy).
- Removal of single segment is called as *unisegmentectomy*.
- *Plurisegmentectomy* is removal of two or more segments. Segments IV and V are removed in carcinoma of gallbladder.
- Removal of small portion of liver either within the segment or traversing segments is called as *wedge resection* of the liver.

Procedure

- Proper preoperative preparation is essential. LFT, prothrombin time is done. Adequate blood, FFP, along with central line is kept ready.
- Subcostal or thoracoabdominal incision is needed.
- Proper mobilization, identification and dissection of portal areas is essential; dissection of hepatic veins, usage of vascular clamp secured ligation of branches of portal vessels and major hepatic veins are essential steps.
- Liver is dissected by finger dissection, back of scalpel, Cavitron ultrasonic surgical aspirator (CUSA), laser ligation of biliary radicles and vascular branches individually using non absorbable sutures are other methods.

Understanding is part of learning and needed before teaching.

- Control of bleeding is done by on table Pringle maneuver, gel foam, cautery, laser and vessel ligation.
- Proper antibiotic coverage is needed to prevent sepsis.
- Post operative ICU care is needed.

Complications

- Bleeding.
- DIC.
- Infection – septicaemia.
- Subphrenic abscess formation.
- Pleural effusion/empyema.
- Liver failure.
- Biliary leak.
- Haemobilia.

DIFFERENTIAL DIAGNOSIS OF SPACE OCCUPYING LESIONS IN THE LIVER

- Hepatoma
- Amoebic liver abscess
- Secondaries in the liver
- Cysts of the liver
- Haemangioma

Self-assessment Questions

- Causes of portal hypertension and management.
- Clinical features and management of bleeding oesophageal varices.
- Child's grading.
- Amoebic liver abscess.
- Secondaries in the liver.
- Hepato-renal syndrome.
- Hepatoma.
- Differential diagnosis for enlarged liver.
- Causes for haematemesis.
- Sengstaken-Blakemore tube.
- Liver function tests.
- Sclerotherapy.
- Space occupying lesions in the liver.
- Liver biopsy.
- Selective shunts.
- Warren's shunt.
- Portal pyaemia.

12

Gallbladder

> ***If the passages which convey the bile to the intestine, be obstructed from inflammation or scirrhous, the bladder gets over-distended, and the bile regurgitates; it therefore becomes mixed with the blood, and the blood, passing over the whole system, carries the bile to every part of the body, which acquires the appearance of bile. But the hardened faeces are white and clayey, as not being tinged with bile, because the bowels are deprived of this secretion.***
>
> **—Aretaeus the Cappadocian,** (81-138?)

Surgical anatomy
Oral cholecystogram
IV cholangiogram
Endoscopic retrograde cholangiopancreatography
Percutaneous transhepatic cholangiography
Peroperative cholangiogram
Postoperative T-tube cholangiogram
Choledochal cysts
Caroli's disease
Biliary atresia
Gallstones: *Acute cholecystitis; Acute acalculous cholecystitis; Empyema gallbladder; Mucocele of the gallbladder; Chronic cholecystitis; Cholecystoses; Dissolution therapy for gallstones.*
Choledocholithiasis
Courvoisier's law
Surgical jaundice
CBD strictures
Sclerosing cholangitis
Carcinoma gallbladder
Cholangiocarcinoma
Biliary fistulas
Gallstone ileus
Hemobilia
White bile
Cholecystectomy
Bile duct injuries
Post-cholecystectomy syndrome
Sump syndrome

SURGICAL ANATOMY

Gallbladder

It is a pear-shaped (size is 5-12 cm) reservoir, located in a fossa on the inferior surface of the liver.

Parts

- Fundus, body, infundibulum and neck. *Hartmann's pouch* is pathological one located in the infundibular region created by gallstones.
- Gallbladder drains through cystic duct into common hepatic duct to form common bile duct.
- It is supplied by cystic artery, a branch of right hepatic artery.



Fig. 12.1: Anatomy of gallbladder.

Your mind will give back exactly, what you put into it.



Fig. 12.2: On table finding of empyema gallbladder with inflamed areas near Calot's triangle.

- *Calot's triangle* is formed by common hepatic duct to the left, cystic duct below, and inferior surface of liver above. Cystic artery originating from right hepatic artery passes behind the common hepatic artery, enters the Calot's triangle to reach the gallbladder. It contains lymph node of *'Lund' (Fred Bates Lund).*
- Often cystic artery, hepatic artery, cystic duct have anomalous positions and anomalous origins. Both gallbladder neck and cystic duct contain mucosal fold called *valves of Heister.*

Extra-hepatic biliary tree:

- The left hepatic duct is formed by the ducts draining II, III, IV segments of the liver. The right hepatic duct is formed by the ducts draining V, VI ,VII, VIII segments of the liver. Both join to form the *common hepatic duct*, which joins with the cystic duct to form the *common bile duct*.
- Common bile duct is normally 10-12 cm in length and 6-8 mm in diameter. It joins the major pancreatic duct in the wall of the 2nd part of duodenum to form the *ampulla of Vater*. Intraduodenal part of CBD is surrounded by smooth muscle fibres called as *sphincter of Oddi.*

Blood supply: From gastroduodenal, retroduodenal, postero-superior pancreatico duodenal arteries.

Bile

- Daily up to 1000 ml of bile is secreted from the liver which contains water (98%), bile salts, bile pigments, fatty acids, lecithin, cholesterol, and electrolytes (sodium, potassium, chloride, bicarbonate, calcium, magnesium) with a pH more than 7.0.
- Main function of gallbladder is to concentrate and store the bile. Capacity of gallbladder is 40-50 ml.
- Bile salts form micelle which makes cholesterol soluble. Bile salts (i.e. salts of cholic and chenodeoxycholic acids) with formed deoxycholic acid (in the bowel) enters the enterohepatic circulation to get resecreted in the bile.
- Bilirubin conjugated in the liver is secreted into the bile, which in the bowel is converted into urobilinogen by bacteria. Urobilinogen gets absorbed in the bowel, enters the liver for resecretion again and part of it is excreted in the urine. Absence of urobilinogen in the urine signifies obstructive jaundice.
- In the absence of gallstones or any other disease, bile is sterile. Symptomatic gallstone disease shows positive culture for bacteria, commonest being *E. coli* and Klebsiella.



Fig. 12.3: CBD parts.

ORAL CHOLECYSTOGRAM (OCG; GRAHAM-COLE TEST)

This test is done to study function of the gallbladder.

Patient is advised to have fat free diet for 3 days. Previous night 6 tablets of *iopanoic acid* (Telepaque), is given orally. On the day of OCG, plain X-ray abdomen in erect posture is taken to visualise the gallbladder.

Later, fatty meal is given and one more X-ray is taken to see the change in the size of the gallbladder, (which should be less in size compared to the earlier film, as



Fig. 12.4: Oral cholecystogram with smooth filling defect (Cystic Duct Stone).

the gallbladder contracts on stimulation with fat rich meal if it is functioning normally). Smooth filling defect signifies nonopaque stone.

Note: One tablet of Iopanoic acid is 500 mg.

Contraindications
1. Patients with serum bilirubin > 3 mg%
2. Acute cholecystitis
3. Vomiting

IV CHOLANGIOGRAM

It is to visualise bile ducts and biliary tree, by injecting IV *Meglumine ioglycamate* (Biligram) and taking X-ray abdomen. It can be combined with OCG.

Problems with this method are poor visualisation, drug reaction. It is not very useful if serum bilirubin is >3 mg%.



Fig. 12.5: Cholecystocholangiogram. Note the dilated CBD, complete block in lower CBD, dilated biliary radicles.

ENDOSCOPIC RETROGRADE CHOLANGIO-PANCREATOGRAPHY (ERCP)

Through a side viewing gastro duodenoscope, sphincter of Oddi is cannulated, and dye is injected. Biliary and



Fig. 12.6A



Fig. 12.6B



Fig. 12.6C



Fig. 12.6D

> *There is little if any restriction to respiratory movements of the abdominal wall in pleuropneumonia.*
> —C Allan Birch



Fig. 12.6E

Figs 12.6A to E: ERCP being done. Note the gastroduodenoscope with injection of dye. (A) shows filling defect in the CBD. (B) shows dilatation of biliary radicles. (C) shows radiolucent stone (smooth filling defect) in distal CBD which can be removed through ERCP. Antibiotics should be given to prevent cholangitis.

pancreatic trees are visualised. It is done under C - ARM guidance and sedation like midazolam or propofol anaesthesia. Patient is placed in prone position with the head turned towards right. After passing gastroduodenoscope, sphincter is identified and cannulated. Under visualisation 3 ml of water soluble iodine contrast is injected into the bile duct and pancreatic duct. When cannula goes upwards beside vertebra, it signifies that it is in bile duct; and if cannula goes across the vertebra it is in pancreatic duct.

Indications

- Malignancy—irregular filling defect.
- Chronic pancreatitis—'*chain-of-lakes*' appearance.
- Congenital anomalies.
- Stones.
- Stricture of biliary tree.
- Choledochal cyst.
- For sampling of biliary and pancreatic juices for analysis and cytology.
- Brush biopsy from tumour site.

Therapeutic uses

1. Extraction of stone from biliary duct
2. Nasobiliary drainage
3. Stenting of tumour in the CBD or in the pancreas
4. Dilatation of the biliary stricture
5. Endoscopic papillotomy

Complications

- Pancreatitis.
- Duodenal injury.
- Cholangitis.
- Bleeding.

Relative Contraindications

1. Acute pancreatitis.
2. Previous gastrectomy.

PERCUTANEOUS TRANSHEPATIC CHOLANGIOGRAPHY (PTC)

- It is done in case of severe obstructive jaundice under cover of antibiotics and after control of any bleeding tendency - by giving injection vitamin K or FFP transfusion.
- With the help of fluoroscopy (C-ARM), *Chiba* or *Okuda needle* which is long, flexible, thin, blunt, without a bevelled end, (15 cm long and 0.7 mm in diameter) is passed into the liver through right 8th intercostal space in mid-axillary line. Once needle is in the dilated biliary radicle, bile is aspirated (sent for culture, cytology, analysis) and then water soluble iodine dye is injected into the same so as to visualise the dilated biliary radicles, also the site and extent of the obstruction, i.e. tumour, stricture.
- Procedure can be used for therapeutic stenting across the biliary tree through the obstruction either in the hepatic ducts or in the CBD into the duodenum.
- It is used whenever ERCP fails, in high strictures (in CHD), in Klatskin tumour, in catheter drainage (external) in high blocks, in stenting high tumours.

Note:

- Chiba is an university in Japan. Okuda is the name of person.
- **PTBD** is percutaneous transhepatic biliary drainage. It can be *external or internal*. It is done through PTC.

Complications

1. Bleeding
2. Biliary leak and biliary peritonitis
3. Septicaemia

MAGNETIC RESONANCE CHOLANGIO PANCREATOGRAPHY (MRCP)

- It is a noncontrast imaging method, better than ERCP as diagnostic tool in biliary and pancreatic diseases.

RADIOISOTOPE SCAN STUDY

- *I^{131} Rose Bengal and Tc^{99} labelled imino diacetic acid (HIDA, PIPIDA)* is very useful in diagnosing acute cholecystitis and other biliary disorders, like biliary atresia.

Note: HIDA is Hippuran Immuno Diacetic Acid.

PEROPERATIVE CHOLANGIOGRAM

- It is done during CBD exploration for stricture, residual CBD stones, atresia, choledochal cyst, cholangitis.
- Fine polythene catheter is passed into the CBD through cystic duct and dye is injected. *Under C-ARM image-intensifier*, any block or stricture can be identified and completion of the procedure can be confirmed.



Fig. 12.7: Preoperative cholangiogram. Fine catheter is passed through cystic duct into the CBD. Care should be taken to avoid air getting into the CBD (it will mimic stone). Dye is injected under C ARM guidance.

Complications

- Infection.
- Bile leak.

Precaution

Air should not be present in the syringe, as it may mimic like stones.

POSTOPERATIVE T-TUBE CHOLANGIOGRAM

After choledochotomy, *Kehr's T- tube* is *placed in CBD for 14 days* and then water soluble dye is injected into the tube and X-ray is taken. Complete free flow of dye into the duodenum indicates that there is no blockage. T-tube can then be removed safely. Block indicates residual CBD stones.

Residual CBD stones are removed by:
- Dormia basket
- Fogarty's catheter
- Choledochoscope
- ERCP



Fig. 12.8: T-tube cholangiogram.

CONGENITAL ANOMALIES OF GALLBLADDER

- *Absence of gall bladder* – rare
- *Phrygian cap* – Cap like projection and bend over the fundus of the gall bladder (*Phrygia* is an ancient Asian country – Mongolia) (Liberte cap of French revolution). It is identified in cholecystogram. It is 6% common
- *Double/triple gallbladder* – additional one may be intrahepatic. Cystic ducts may join to form a common cystic duct which joins the CBD or cystic duct of each gall bladder may join separately into the CBD
- *Mobile / floating / mesenteric gall bladder* – gall bladder has a long mesentery attached. It may cause torsion. It can cause recurrent abdominal pain. Its removal is easier through laparoscopic or open method
- *Long cystic duct* with low insertion of the cystic duct into CBD near the ampulla. This is important in all pancreatic/biliary/laparoscopic biliary surgeries
- *Absence of cystic duct* with gall bladder directly entering the CBD through a wide opening near infundibulum
- *Accessory cholecystohepatic duct* (*duct of Luschka*) may be present(10%) which if not identified and ligated during cholecystectomy will cause biliary fistula/ peritonitis due to continuous leak
- *Cystic artery may originate anteriorly* (15%) from right hepatic artery/from common hepatic artery
- Very tortuous hepatic artery in front of the origin of the cystic duct is called as *Moynihan's caterpillar hump*. It is important cause of bleeding in cholecystectomy
- There may be *double cystic duct* or cystic duct may insert high into the common hepatic duct or right hepatic duct

If vomiting or distinct nausea preceeds pain, the case is not one of appendicitis.— John B Murphy



Fig. 12.9: Cystic duct is absent with wide communication into CBD. There is higher chance of CBD injury here.



Fig. 12.12: Long cystic duct joining the CBD very low.


Accessory
cholecysto
hepatic duct
(duct of
Luschka) 10%

Fig. 12.10: Accessory cholecystohepatic duct (Duct of Luschka – 10%). It may cause bile leak postoperatively if it is not ligated during cholecystectomy.



Fig. 12.13: Cystic duct joining the right hepatic duct – a variation.



Fig. 12.11: Double cystic ducts from the gallbladder joining the CBD.



Fig. 12.14: Phrygian gallbladder.



Fig. 12.15: Gallbladder diverticulum.



Fig. 12.17: Cystic artery originates from right hepatic artery which is anterior to common bile duct.





Figs 12.16A and B: Double gallbladder. One may be intrahepatic. It may have separate cystic ducts joining CBD or two cystic ducts join to form single duct to join the CBD.



Fig. 12.18: Moynihan's caterpillar turn/hump is bend of right hepatic artery in front of/close to cystic duct. It may get injured during cholecystectomy causing torrential haemorrhage.

CHOLEDOCHAL CYSTS

- It is cystic enlargement of CBD. More common in females.
- It is congenital cyst with partial or complete weakness of the CBD wall.
- It may be single/multiple or extrahepatic or intrahepatic.
- It is more common in Asia. It is common in Japan. Its incidence is 1 in 1000.
- It is often associated with pancreatico biliary maljunction. There is long common channel more

Gangrenous cholecystitis is associated with thrombosis of cystic artery.

than 2 cm. It causes reflux of pancreatic juice into the bile duct, enzymatic destruction of the bile duct wall, ductal wall weakening and dilatation – *Babbit theory*.

- During embryogenesis there is abnormal early canalisation of bile duct with distal obstruction causing increased proximal pressure, weakening and ductal dilatation.
- Reduced post ganglionic autonomous neurons in the distal portion of the cyst causing its poor function distally.
- Chronic inflammation, sparse mucin glands and metaplasia are the histological features. Histologically it is either glandular with normal cuboidal epithelium with cavities in the mucosa. Or fibrotic type with fibrous cyst wall with thickened bile duct.



Fig. 12.19: US picture of choledochal cyst.

Types (Todani classification) (Ref. Fig. 12.21)

1. Type I: *Fusiform* dilatation of CBD—Commonest (60%).
2. Type II: A lateral *saccular* diverticulum of the CBD (5%).
3. Type III: Dilatation of the intraduodenal segment of CBD (*choledochocele*) (5%).
4. Type IV: Dilatation of *CBD + intrahepatic* biliary dilatation (30%).
5. Type V: *Multiple intrahepatic* cysts.

Presentations

- Common in females 4:1.
- Present in infants, children and even in adults.
- Obstructive jaundice (80%), pain in right hypochondrium, cholangitis.



Fig. 12.20: Pancreatico biliary maljunction. Here pancreatic duct joins CBD more proximally than normal causing reflux of pancreatic enzymes into the CBD. It leads into weakening, dilatation and choledochal cyst.

- Mass per abdomen—mass is to the right and above the umbilicus, smooth, soft, not moving with respiration, not mobile and resonant (30%).
- Failure to thrive.

Triad of choledochal cyst

- Right upper quadrant pain
- Jaundice
- Palpable abdominal mass

Swellings which appear and disappear

- Hydronephrosis
- Intussusception
- Pseudo pancreatic cyst
- Choledochal cyst

Complications

- Pancreatitis, mainly in type III.
- Suppurative cholangitis.
- Gallstone and CBD stone formation.
- Biliary cirrhosis—secondary.
- Rupture of cyst and peritonitis.
- Cholangio carcinoma in CBD (30% of cases). Incidence of malignancy increases with age and is more common in type I and V. Reflux, stasis, super infection, pancreaticobiliary maljunction are the causes for malignant transformation. Malignancy can develop even in residual cyst or at anastomotic site.

Diagnosis

- U/S abdomen—unilocular cyst mainly in infants.
- CT scan—mainly to see intrahepatic biliary system.

- Hepatobiliary nuclide scanning.
- ERCP, Cholangiography.
- MRCP—to see status of pancreatic and biliary system and pancreaticobiliary maljunction.
- Liver function tests.

Treatment

- In Type I—excision of cyst with its mucosa and reconstruction by Roux-en-Y hepatico-jejunostomy
- In Type II—excision of the diverticulum and suturing of the CBD wall is done.



Fig. 12.21: Different types of choledochal cysts—(1) Fusiform type, (2) Saccular type, (3) Choledochocele, (4) Fusiform + Intrahepatic type, (5) Intrahepatic type.

- In type III—endoscopic sphincterotomy is done. Excision is also often needed.
- Intrahepatic dilatation is difficult to treat. If it is localised, hepatectomy is sufficient, but if it is diffuse, liver transplantation may be required.
- In type IV if cyst is adherent to portal vein posteriorly, that part of the cyst wall over the portal vein is left behind. But mucosa of the part should be removed (*Lily's operation*).
- Cholecystectomy is a must in all these types. Incidence of gall bladder carcinoma is also high in these patients.
- If cyst has already turned into malignancy – adenocarcinoma, then radical surgery and chemotherapy is given.

CAROLI'S DISEASE

- It is congenital, nonfamilial, multiple, irregular, dilatations of the intrahepatic ducts with stenotic segments in between. It is associated with *congenital hepatic fibrosis* and *medullary sponge kidney*.
- It can also be included under type V choledochal cyst.

Investigations

- CT scan
- ERCP
- LFT
- MRCP

Complications

- Recurrent cholangitis.
- Stones in biliary tree.
- Portal hypertension.
- Cholangiocarcinoma (7%).

Treatment

1. Liver transplantation.
2. Hepatectomy.

BILIARY ATRESIA

- It may be either due to viral infection or defective embryogenesis resulting in fibrosis of extra- and intrahepatic biliary tree.
- Incidence is 1 in 10,000.

Porcelain gallbladder is radiopaque gallbladder, due to calcification of the gallbladder wall following chronic cholecystitis which has got high malignant potential.



Fig. 12.22: Types of biliary atresia

- It is obstructive cholangiopathy with inflammation, destruction and obliteration predominantly involving the extrahepatic biliary tree. There is bile duct proliferation, cellular and canalicular bile stasis, bile plugs in portal tract bile system, periportal inflammation and fibrosis.

Aetiology of biliary atresia

- Infections – cytomegalovirus, reovirus, rotavirus and human papilloma virus
- Immune and autoimmune diseases
- Abnormal development of the biliary system
- Toxins
- Vascular defects of the hepatic artery

Classification

- *Correctable—10%.*
- *Non correctable—90%.*

Biliary atresia

Type I: Atretic CBD—10%
Type II: Atretic CBD and common hepatic duct
Type III: Atretic CBD, common hepatic duct and right and left hepatic ducts—88%

Biliary atresia can be–

- *Perinatal acquired* (70%), not associated with congenital anomalies.
- *Fetal/embryonic* (30%) is associated with congenital anomalies.

It may be associated with other congenital anomalies (20%) of the GIT—(malrotation, annular pancreas duodenal atresia) and congenital heart diseases, polysplenia, situs inversus, absent vena cava, preduodenal portal vein.

Clinical Features

- Progressive jaundice in a new born.
- Steatorrhoea (Pale stool is common).
- Hepatomegaly.
- Splenomegaly with portal hypertension.
- Osteomalacia.
- Biliary rickets.
- Severe pruritus.
- Clubbing, skin xanthomas.

Differential Diagnosis

- Neonatal hepatitis.
- Choledochal cyst.
- Cholestatic jaundice.
- Sclerosing cholangitis.
- Metabolic diseases.
- Storage disorders.
- Alagille syndrome – hypoplastic biliary ducts.

Diagnosis

- Liver function test – conjugated hyperbilirubinaemia.
- US abdomen shows triangular cord, tubular echogenisity extending above the bifurcation of the portal vein which is more than 4 mm thick – diagnostic.
- MRCP - 100% accuracy.
- Radioisotope study (HIDA or PIPIDA scan).
- On table cholangiogram.
- Liver biopsy (Percutaneous)—is usually first test obtained.
- Rose Bengal I^{131} study, if shows < 10% secretion it is biliary atresia. If secretion is > 10% it is more likely to be hepatitis.

Treatment

- *In correctable cases*: Roux-en-Y jejunal anastomosis.
- In noncorrectable cases, hepaticoportojejunostomy (*Kasai's operation*).
- Liver transplantation is becoming more popular in biliary atresia – Ideal.
- Presently *Kasai (1974) porto enterostomy* is done (in 8 weeks) as a preliminary procedure followed by liver transplantation eventually. After opening the abdomen, gall bladder is cannulated and on table cholangiogram is done to confirm atretic segment. Liver biopsy should also be done at the same time. If biliary patency is found procedure is abandoned. In atretic biliary tree, gallbladder is dissected off the liver and by applying traction to it, fibrotic atretic biliary tree is felt and dissected upto intrahepatic segment (upto the segmental branches of portal vein). Portal plate is anastomosed to Roux-en-Y part of the small bowel. Postoperatively, antibiotics, intravenous corticosteroids initially, later orally (for 6-12 weeks), ursodeoxycholic acid (for 1 year), nutrition, medium chain and essential fatty acids, essential elements supplementation is given. Success of procedure depends on age of the patient; presence of cholangitis; ductule size (more than 200 µm is better); bridging fibrosis; type of atresia; bilirubin level. Eventually cholangitis, portal hypertension, variceal bleeding will develop.

GALLSTONES

> ***Thus with stone obstruction of the common duct, dilatation of the gallbladder is rarely observed; the organ has already undergone contraction; with obstruction from other causes, dilatation is to be expected.***
>
> **—Ludwig Courvoisier, 1890**

Types

1. *Cholesterol stones* (Cholesterol solitaire – radiating crystalline appearance) are 6% common, often solitary.
2. *Mixed stones* are 90% common. It contains cholesterol, calcium salts of phosphate, carbonate, palmitate, proteins, and are multiple, faceted.



Figs 12.23A and B: Multiple gallstones in a plain X-ray. Only 10% gallstones are radio-opaque. Often they are faceted because of compactness and equal pressure exerted by each stone. Center of the gallstone is often found radiolucent and is called as *Mercedes Benz sign/Seagull sign.*



Fig. 12.24 Lateral X-ray of spine showing radio-opaque shadow in front of the vertebrae – could be radio-opaque gallstone. Note also the fused intervertebral disc spaces.

It frequently happens that gallstones are found in the gallbladder after death. Where there was not the least suspicion of existence during life.
— Mathew Baillie

3. *Pigment stones* are small, black or greenish black, multiple. Often they can be sludge like.

Common in *"Fat, Fertile, Forty, Flatulent, Female"*. Common in western countries and in north India.


Altered GB function
- Stasis
- Poor emptying
- Poor absorption
- Infection
Supersaturated bile
- Female
- Fertile
- Fat
- Forty
- High calorie
Gallstones
Spleen
Haemolytic diseases
Cholesterol nucleation factors
Altered enterohepatic circulation
- Ileal resection
- Ileal diseases
- Altered bowel transit time
- Altered bowel flora
- Cholestyramine
- Deoxycholate

Fig. 12.25: Diagram showing different causes of gallstone formation.

Pathogenesis

I. ***Metabolic:***

- Cholesterol is synthesised in liver. Its solubility is determined by relative concentration of cholesterol, bile salts and lecithin. Altered levels of cholesterol, lecithin, and bile salts in bile reduces the micelle concentration in the bile leading to precipitation of insoluble cholesterol, hence the stone formation *(Lithogenic bile).*
- Normal ratio of bile salt and lecithin to cholesterol is 25:1. Ratio Below 13:1 leads to, precipitation of cholesterol. Insoluble cholesterol is within the soluble micelle which is formed by lecithin and bile salts. If cholesterol component increases bile gets supersaturated and inadequate micelle makes insoluble cholesterol to undergo crystallisation and cholesterol monohydrate stone formation. (*Admiron's triangular hypothesis*).
- Some cholesterol remains as bilayered lipid vesicles which are soluble. A specific heat labile glycoprotein in bile induces cholesterol monohydrate crystal formation in the vesicle and causes their aggregation. It is called as *nucleation*.
- Eventual precipitation and stone formation occurs by infection/infestation; pancreatic fluid reflux into CBD causing conversion of toxic lecithin to lysolecithin which is also toxic (causes supersaturated bile); bile stasis or altered enterohepatic circulation.
- Any condition which either increases the cholesterol secretion in the bile or reduces the bile salt concentration causes cholesterol stone formation. Old age; OCP; obesity; clofibrate may increase cholesterol secretion. Estrogen, ileal resection and cholestyramine reduce the bile salt concentration.
- Chenodeoxycholic acid and ursodeoxycholic acid prevent cholesterol stone formation by maintaining bile acid pool; reducing cholesterol synthesis and secretion; converting supersaturated bile into normal bile.

Factors altering the cholesterol to bile salt ratio:

1. Obesity
2. Drugs
    - Oral contraceptive pills
    - Clofibrate
    - Cholestyramine
3. Ileal disease
4. Ileal resection
5. Altered enterohepatic circulation

II. ***Infections and Infestations*:**
Bacteria like *E. coli, Salmonella*
Parasites like *Clonarchis sinensis* and *Ascaris lumbricoides* are often associated.
Moynihan's aphorism: "A gallstone is a tomb stone erected to the memory of the organism within it."

III. ***Bile stasis*:** Occurs due to estrogen therapy, pregnancy, vagotomy and in patients who are on long term intravenous fluids or TPN.

IV. ***Increased bilirubin production*** due to any of the causes of *haemolysis* as in hereditary spherocytosis, sickle cell anaemia, thalassaemia, malaria, cirrhosis. Here pigment stones are common.

Saint's triad
- Gallstones
- Diverticulosis of the colon
- Hiatus hernia

- Rarely centre of the stone contains radiolucent gas which is either triradiate (*Mercedes Benz sign*) or biradiate (*Seagull sign*).

- Sometimes gallbladder may be filled by 'toothpaste like' material which is a mixture of calcium carbonate and phosphate, which on plain X-ray looks like an opacified gallbladder, so called *as limey gallbladder*.
- Only 10% of gallstones are radio-opaque, 90% are radiolucent.

Note:

- Black pigment stones are common in gallbladder. It is usually calcium bilirubinate, calcium phosphate and bicarbonate stone with a matrix. It is common in haemolytic disorders. They are usually multiple, small black and hard in consistency. Mucin A and mucin C5 secreted by biliary glands may be the aetiology. Cholesterol component here is less than 30%. It is often seen in cirrhosis.
- Brown pigment stones are formed in biliary tree as primary biliary stones. It is commonly due to infection like *Escherichia coli* and bacteroides (98%) with bacterial nidus at the centre (often *Ascaris lumbricoides* or *Clonorchis sinensis* infestation or foreign body or stents). They secrete β glucuronidase to cause hydrolysis of soluble conjugated bilirubin to insoluble calcium bilirubinate. It also contains calcium palmitate, calcium stearate and cholesterol.



Fig. 12.27: Gallstones removed on cutting showing central nidus.



Fig. 12.28: Thickened gallbladder due to chronic cholecystitis with single cholesterol stone.



Fig. 12.26: Multiple gallstones collected during cholecystectomy.



Fig. 12.29: Gallbladder with stone removed from Hartmann's pouch.

Life is endless until it ends.

Effects of the Gallstones

a. *In the gallbladder*

  i. Silent asymptomatic stones occurs in 10% of males and 20% of females.
 ii. *Biliary colic with periodicity*, severe within hours after meal (commonest presentation). Biliary colic is spasmodic pain often severe, in right upper quadrant and epigastrium radiating to chest, upper back and shoulder. It is self-limiting, recurs unpredictably, often precipitated by a fatty/heavy meal. Fever and increased WBC count may be observed.











Figs 12.30A to E: Different types of gallstones. Note the faceted stones; black stones; brown stones; green stones. Thickening of gallbladder is seen. Hartmann's pouch is obvious in one of the photos (with cholesteroses).



Figs 12.31A and B: Plain X-ray showing (A) Mercedes Benz sign (B) Multiple faceted stones

iii. Acute cholecystitis.
iv. Chronic cholecystitis.
v. Empyema gallbladder.
vi. Perforation causing biliary peritonitis or peri cholecystitic abscess.
vii. Mucocele of gallbladder.
viii. Limey gallbladder.
ix. Carcinoma gallbladder.

b. *In the CBD*

x. Secondary CBD stones (occurs in 10% of gallstones).
xi. Cholangitis.

xii. Pancreatitis.

xiii. *Mirizzi Syndrome* (compression of CBD by stone from cystic duct or cholecysto-choledochal fistula).


Perforation
(Hartmann's)
Mirizzi syndrome
CBD stone
Pancreatitis
Carcinoma
Abscess
Perforation
(fundus)
Gallstone ileus

Fig. 12.32: Diagram showing complications of gallstones.

c. ***In the intestine***

xiv. Cholecystoduodenal fistula causing *gallstone ileus* and so intestinal obstruction.

Flatulent Dyspepsia

- It is discomfort in the abdomen, belching, heartburn, fat intolerance, sensation of fullness in the abdomen usually observed in *fatty, fertile, flatulent female.*

Gallstone Colic

- It is sudden, severe colicky abdominal pain in right upper quadrant which radiates to back and shoulder. This pain is due to sudden spasm of gallbladder wall when gall stone moves towards the neck of the gallbladder or cystic duct and gets impacted. Tachycardia and restlessness are common. Right hypochondrium is tender.
- It is precipitated by supine position while sleeping at night. It lasts for few hours and is episodic. It may precipitate acute cholecystitis or empyema gallbladder.
- There is reflex pylorospasm causing vomiting.

Mirizzi Syndrome

- In Mirizzi syndrome, gallstone impacts in the gallbladder wall and compresses it causing pressure necrosis which further gets adherent to CBD wall. It eventually causes compression and later occasionally leads into cholecystocholedochal fistula. It occurs either from Hartmann's pouch into CBD (common) or from fundus of gallbladder into the CBD.
- Mirizzi syndrome is suspected on CT scan, but usually identified on table. It needs cholecystectomy; on table cholangiogram; and exploration of CBD. It often needs choledochojejunostomy.

Mirizzi Syndrome

Type I: Compression of CBD without lumen narrowing
Type II: Compression causing CBD lumen narrowing
Type III: Compression causing CBD wall necrosis.
Type IV: Cholecysto-choledochal fistula


Mirizzi syndrome
type II (compression)
Gallstone
GB
A
Mirizzi syndrome
type IV (fistula)
Gallstone
GB
B

Figs 12.33A and B: Mirizzi syndrome type II and IV.

Surgery is to be done, not to have.

Silent gallstone

- *Asymptomatic stone in the gall bladder*
- Usually it is cholesterol stone, often single
- It is accidentally discovered by U/S
- It need not be treated unless –
  - Patient is diabetic/immunosuppressed
  - High chances of developing gallbladder carcinoma
  - Stone more than 2.5 cm/multiple stones
  - If gallbladder wall is thickened
  - If there is high risk for carcinoma GB

Management of Gallstones

- U/S abdomen (gallstones are seen with posterior acoustic shadowing); plain X-ray abdomen; LFT; total WBC count.
- Laparoscopic cholecystectomy.
- Open cholecystectomy through right subcostal Kocher's incision.

Differential diagnosis of radio-opaque shadow in X-ray

- Kidney stone
- Gall stone
- Calcified 12th rib tip
- Phlebolith
- Pancreatic stone
- Radio-opaque foreign body
- Faecolith
- Calcified lymph node
- Calcified renal tuberculosis
- Renal cell carcinoma – calcifications
- Adrenal tumour – calcification
- Teratomatous dermoid
- Calcification of atheroma in aorta
- Calcified lesion in liver – amoebic liver abscess/calcified hydatid cyst

ACUTE CHOLECYSTITIS

- Commonly it occurs in a patient with pre-existing chronic cholecystitis but often also can occur as a first presentation.
- Usual cause is impacted gallstone in the Hartmann's pouch, obstructing cystic duct.

Causative bacteria are—

E. coli - commonest
Klebsiella, pseudomonas, proteus
Strep. faecalis
Salmonella
Clostridium welchii.

Classification

1. Acute calculous cholecystitis.
2. Acute acalculous cholecystitis.

Mode of Infection

- Haematogenous through hepatic artery – cystic artery.
- Portal vein.
- Through bile after filtering in the liver via portal circulation.

Pathogenesis of Acute Cholecystitis

- Stone causes obstruction at Hartmann's pouch or in cystic duct. Obstruction causes stasis, oedema of the wall, bacterial infection, acute cholecystitis and its effects.
- Impacted stone also causes mucosal erosion allowing bile salts to act over the submucosal tissues as bile is toxic to these tissues. It leads into necrosis, further infection and often perforation of the gallbladder usually at Hartmann's pouch.

Pathology of Acute Cholecystitis

- Gallbladder will be distended with oedematous friable wall. Wall contains dilated vessels.
- Areas of necrosis and patchy gangrene may occur in severe cases.
- Mucosa shows ulceration and necrosis.
- Lumen contains infected fluid/infected bile or frank pus.
- Histology shows features of acute inflammation with neutrophils, oedema, and areas of necrosis and cell death.

Complications of Acute Cholecystitis

Acute cholecystitis can lead to

1. *Perforation*, which usually occurs in the fundus or in the neck (Hartmann's). It can cause cholecysto-duodenal, cholecysto-intestinal or cholecysto-biliary fistula.
2. *Peritonitis*

Emphysematous cholecystitis

- Seen in elderly male patients
- Common in diabetic and immunosuppressed individuals
- *Clostridium welchii* is the causative organism
- Gas is seen in the gallbladder
- Results in life-threatening septicaemia
- It causes severe fulminant cholecystitis
- Gangrene, perforation and peritonitis are common
- Emergency cholecystectomy is needed

3. Pericholecystitic abscess, empyema GB.
4. Cholangitis and septicaemia.
5. Empyema gallbladder, gangrenous gall bladder.



Fig. 12.34: On table look of gallbladder with acute cholecystitis.

Clinical Features

- Sudden onset of pain in the right hypochondrium, with tenderness, guarding, and rigidity.
- Palpable, tender, smooth, soft gallbladder.
- Area of hyperaesthesia between 9th and 11th ribs posteriorly on the right side (*Boas's sign*).
- Jaundice may be present.
- Fever, nausea, palpable tender mass in GB region (25%).
- Tachycardia and toxic features.

Investigations

- Ultrasound abdomen—very useful, reveals presence or absence of gallstones; and thickening of gallbladder wall.
- Plain X-ray abdomen—10% of gallstones are radio-opaque; also rules out other causes of acute pain abdomen. Gas is seen in emphysematous GB.
- Total count shows neutrophilia.
- HIDA/PIPIDA radioisotope study—very useful. Non-visualisation of gallbladder is diagnostic.
- LFT is important. Increased serum bilirubin often signifies cholangitis or stone in the CBD.
- Plain X-ray abdomen is not very relevant but is often important to rule out duodenal ulcer perforation, peritonitis. Only 10% of gallstones are radio-opaque. In emphysematous cholecystitis gas shadow may be seen in the region of gallbladder. Porcelain gallbladder may be seen as opacified area in gallbladder region.



Fig. 12.35: Ultrasound picture of visualisation of multiple gallstones.



Fig. 12.36: Ultrasound showing roundworm in gallbladder.

Differential diagnosis

- Duodenal ulcer perforation
- Acute pancreatitis
- Acute appendicitis
- Acute pyelonephritis
- Lobar pneumonia, myocardial infarction
- Ruptured ectopic pregnancy

Success is the ability to go from failure to failure without losing enthusiasm.



Fig. 12.37: CT scan showing stone in the neck of the gallbladder.

Treatment

- Advised hospitalisation.
- Initially *(non-operative) conservative treatment (95%)*:
  - Nasogastric aspiration.
  - IV fluids.
  - Analgesics and antispasmodics.
  - Broad spectrum antibiotics (cefoperazone, ceftazidime, ceftriaxone, cefotaxime + amikacin, tobramycin + metronidazole {antimicrobial}).
  - Observation.
  - Follow-up U/S scan.
- *Later after 3-6 weeks, elective cholecystectomy*, either by open method through right subcostal (Kocher's) incision or through laparoscopy is done.

Cholecystostomy is done immediately if patient is having:

1. Empyema gallbladder
2. Persisting symptoms
3. Progressing symptoms.

Here the gallbladder is opened and all stones and pus are removed. Either a Foley's or Malecot's catheter is placed in the gallbladder and is exteriorised.

After 3 weeks, elective cholecystectomy is done.

Indications for cholecystostomy or emergency cholecystectomy (5%) —

- Empyema GB
- Persisting symptoms/failure of medication
- Emphysematous cholecystitis
- Perforation/peritonitis
- Elderly



Figs 12.38A and B: On table photo of distended gallbladder. Note the Calot's triangle, liver and CBD.

Note:
Cholecystostomy is better option than *emergency cholecystectomy* as chances of injuring adjacent structures is higher in emergency cholecystectomy. Other option is *partial/subtotal cholecystectomy* with removal of part of GB distal to the Calot's triangle.

ACUTE ACALCULOUS CHOLECYSTITIS (5%)

- It is not an uncommon entity, but can be commonly missed.
- It is common in patients who have undergone major surgeries, trauma, burns, or any other stress or in cases of *cholecystoses.*
- Common in ICU patients.
- Exact cause is not known. Gall bladder distension, release of activation factor VII may be the causes.
- Pathology is oedema and necrosis of the gall bladder wall with features of acute inflammation.
- Presentation is usually acute.



Fig. 12.39: A Foley's or Malecot's catheter is placed in severely ill-patient with acute cholecystitis to drain pus initially, and later elective cholecystectomy is done. Procedure is done in elderly, severely ill, empyema GB, emphysematous GB, perforation of GB. (Cholecystostomy)

- *Investigations:* Isotope study (HIDA), U/S abdomen.
- Treatment: Cholecystectomy.

EMPYEMA GALLBLADDER

- It is a type of acute cholecystitis wherein the gallbladder is filled with pus. In 30% cases pus may be sterile.
- It also can occur in a pre-existing mucocele of the gallbladder where it gets infected.



Fig. 12.40: Gallstone obstructing the neck of the gallbladder in Hartmann's pouch, may lead into empyema or mucocele of the GB.

- It is commonly observed in impacted stone, diabetic individual, immunosuppressed people like HIV, long time steroid therapy.
- It can perforate; can form abscess or can cause peritonitis – biliary and bacterial.
- Condition has got high mortality.

Clinical Features

- Fever, toxicity.
- Pain and tenderness in right hypochondrium.
- Tender, smooth, globular, gallbladder is palpable in right hypochondrium to the right of the right rectus muscle.



Fig. 12.41: Empyema gallbladder. Note the pus and stone.

Complications

- Septicaemia.
- Rupture and peritonitis.

Investigations

- U/S abdomen.
- Total count is raised.
- Radio isotope scan.

Treatment

- Antibiotics: Cefotaxime, quinolones, ceftriaxone.
- Cholecystectomy - an emergency procedure.
- Often initially cholecystostomy is done, with either Foley's or Malecot's catheter kept *in situ.*

  Later after 3-6 weeks, cholecystectomy is done.

Ability may get you to the top, but it takes character to keep you there.



Fig. 12.42: Gangrenous gallbladder.

MUCOCELE OF THE GALLBLADDER

- It is due to obstruction of the cystic duct by a stone in the neck (Hartmann's pouch) of the gallbladder, without any infection or inflammation in the gallbladder. This causes absorption of all bile and secretion of mucus into the gallbladder allowing gallbladder to distend causing mucocele of the gallbladder.
- Rarely cholangiocarcinoma occluding cystic duct may cause mucocele of gallbladder.
- Content is usually sterile.

Clinical Features

- Painless swelling in the right hypochondrium.
- Nontender, smooth, soft, globular, palpable gallbladder (content is sterile).
- Features of dyspepsia.



Fig. 12.43: Mucocele of gallbladder.

Complications

- If infected, can cause empyema gallbladder.
- Rupture can cause pseudomyxoma peritonei (but rare).

Investigations

- U/S abdomen.
- Liver function tests.

Treatment

Cholecystectomy, either laparoscopic or open method.

CHRONIC CHOLECYSTITIS

It is chronically inflamed, thickened gallbladder, which is nonfunctioning and nondistending.

Causes

- Gallstones.
- Cholecystoses.
- Chronic acalculous cholecystitis.

Organisms

- *Klebsiella.*
- *Streptococci.*
- *Salmonella.*

Pathology

- Gallbladder is shrunken, contracted, small, nonfunctioning and fibrotic with thickened gall bladder wall. Mucosa proliferates into the lumen creating deep clefts in the wall projecting into the muscular wall of the gall bladder being lined by epithelium. It is called as *Rokitansky – Ashchoff's sinuses.*
- Muscular wall is atrophied and is often replaced by fibrous tissue.
- Histologically it shows dense chronic inflammation with fibrous tissue.



Fig. 12.44: Specimen of gallbladder showing thickened gallbladder with multiple gallstones. Faceting of stones is due to equal pressure.

Clinical Features

- Pain in right hypochondrium, may be colicky, or persistent.
- Positive *Murphy's sign*, where in sitting position during deep inspiration, while palpating in right hypochondrium, patient winces with pain at the summit of the inspiration. Same sign elicited in lying down position is called as *Moynihan's sign*.
- Flatulent dyspepsia.
- Intolerance to fatty meals.
- Biliary dyspepsia.

Complications

- CBD stone.
- Cholangitis.
- Pancreatitis.
- Mirizzi's syndrome.

Differential Diagnosis

- Peptic ulcer.
- Pancreatitis.
- Hiatus hernia.

Investigations

- U/S abdomen may show stone with posterior acoustic shadowing. Gallbladder wall will be thickened.



Figs 12.45A and B: Thickened GB due to chronic cholecystitis with multiple stones.



Fig. 12.46: Thick GB with single large stone.

- Isotope study may help to confirm the infection.
- LFT.
- Total count may be raised if there is an acute recurrent infection.

Treatment

Cholecystectomy (Laparoscopic or open method).

CHOLECYSTOSES

- Cholecystoses are chronic inflammatory conditions of gallbladder with cholesterol deposits.
- It is due to defective transport of the absorbed cholesterol which accumulates in mucosa. There is also increased absorption of cholesterol by gallbladder epithelium.
- Cholecystoses gallbladder is more prone for infection.
- It may precipitate stone formation.
- It is a premalignant condition.

Types

I. Aggregations of cholesterol crystals in the mucosa or submucosa—*cholesterosis* (*Strawberry gallbladder*). Lipoid contents are present in large foamy cells which has phagocytosed cholesterol. Here cystic duct is normal. Disease occurs only in gallbladder. It is a premalignant condition.

II. Cholesterol laden polypoid projections in the mucosa—*cholesterol polyposis* (Gallbladder polyp).

III. Granulomatous thickening and hyperplasia of the gallbladder—*cholecystitis glandularis proliferans.*

> ***Typhoid Mary:*** *Salmonella typhi infection with chronic cholecystitis acting as a carrier. Mary was a cook who spread typhoid to many people.*

IV. Diverticula formation in the wall of the gallbladder—*diverticulosis of gallbladder*.
V. Gallbladder wall fistula.

Clinical Features

- Features of acalculous cholecystitis like dyspepsia, positive Murphy's sign.



Fig. 12.47: Types of Cholecystoses. (I) Cholesterosis (II) Cholesterol polyposis, (III) Cholecystitis glandularis proliferans, (IV) Diverticulosis of gallbladder, (V) Fistula

Investigations

- U/S abdomen.
- OCG.
- Isotope study.

Treatment

Cholecystectomy - always should be done whether it is symptomatic or not as it is potentially malignant.

DISSOLUTION THERAPY FOR GALLSTONES

Indications

- Functioning gallbladder with cholesterol stone
- Single stone less than 1.5 cm.
- Radiolucent stone
- Old age
- Patients who are not fit for surgery.

Contraindications

- Nonfunctioning gallbladder
- Stone more than 1.5 cm
- Radio-opaque stone
- Multiple stones

Drugs used

- Cheno-deoxy cholic acid (for 2 years).
- Urso-deoxy cholic acid (15 mg/kg/day).

They inhibit absorption of cholesterol from the gut and synthesis of cholesterol in the liver. They inhibit HMG Co A – a rate limiting step in cholesterol synthesis. Ursodeoxycholic acid also inhibits absorption of cholesterol in GIT.

Other methods used

- Citrate
- Monoterpenes
- Percutaneous infusion of methyl-tert- butyl-ether (MTBE) into the gallbladder using a catheter
- Shock waves (ESWL)—Not popular

Problems with Dissolution Therapy

- Drugs should be given for a long time.
- Results are not good.
- Expensive.
- Causes side effects like diarrhoea, pruritus.
- Hepatic dysfunction.

Overall results are not good by dissolution therapy.

CHOLEDOCHOLITHIASIS

It is stones in the CBD and biliary tree.

Classification

i. Primary—Rare-brown pigment stones.
ii. Secondary—Common–black pigment stones/cholesterol stones.



Fig. 12.48: Diagram showing stone in CBD causing the block and subsequent dilatation of the proximal CBD and biliary tree with cholangitis.

Primary stones

They are formed in CBD and biliary tree itself, and are multiple, often sludge like, commonly pigment or mixed type, extends into hepatic ducts (Brown pigment stones).

Causes:

I. Defective pathophysiology of biliary tree causing stasis.
II. Congenital conditions like Caroli's disease, choledochal cyst.
III. Infections and infestations like clonorchiasis, ascariasis.

Secondary biliary stones

- They are from gallbladder (gallstones) passes through cystic duct to CBD. Here CBD and biliary tree are otherwise normal.
- *Secondary stones are better and easier to manage than primary stones.*
- Commonly gallstones get impacted in supraduodenal portion of CBD.



Fig. 12.49: Multiple stones removed from common bile duct and hepatic ducts. They cause cholangitis. After stone removal patient needs choledochoduodenostomy/sphinc-teroplasty/choledochojejunostomy.

Clinical Features

- Pain.
- Jaundice—commonest clinical manifestation.
- Fever with chills and rigors.

Charcot's triad of ascending cholangitis:
Intermittent pain (may be colicky)
Intermittent fever
Intermittent jaundice


Stone in CBD due to impaction
Causes obstruction
Stasis
Jaundice
Pain
Infection, bacteraemia and fever

Stone moves proximally and floats, obstruction is relieved and symptoms subside (**Intermittent features**).

- ***Reynold's pentad** of acute obstructive cholangitis (suppurative cholangitis)*.

Sometimes obstruction persists causing
- Persistent pain
- Persistent fever
- Persistent jaundice
- Shock (toxicity) and
- Altered mental status

Here biliary tree contains pus.

- Pain and tenderness in epigastrium and right hypochondrium.
- Steatorrhoea and darkening of urine.
- Pruritus.

Complications

- Liver dysfunction and biliary cirrhosis.
- White bile formation and liver failure.
- Suppurative cholangitis.
- Liver abscess.
- Septicaemia.
- Pancreatitis.

Differential diagnosis

Obstructive jaundice due to other causes:
- Carcinoma of head of pancreas
- Carcinoma of periampullary region
- Carcinoma of biliary tree
- Biliary stricture
- Viral hepatitis

Investigations

- U/S abdomen; CBD diameter > 1 cm indicates biliary obstruction.
- ERCP, gold standard for diagnosis.
- MRCP.
- Liver function tests.

Treatment

- Injection Vit. K 10 mg IM once a day for 5 days or FFP infusion to correct the prothrombin time.

Commitment is what transforms a promise into reality.

- IV antibiotics (cefoperazone, cefotaxime).
- *Correction of dehydration.*
- IV Mannitol daily 200 ml BD to prevent *hepatorenal syndrome*.
- **ERCP—Therapeutic,** i.e. Endoscopic papillotomy (sphincterotomy) and stone extraction through Dormia basket or balloon catheter; or fragmenting the stone and extraction; or removal through baby endoscope. CBD stent is placed *in situ*.



Fig. 12.50A: Plain X-ray showing stents in CBD and pancreatic ducts. It was placed in a patient who presented with recurrent pancreatitis with block/stricture in both terminal CBD and pancreatic duct. Later patient underwent choledocho-jejunostomy and pancreaticojejunostomy.



Fig. 12.50B: ERCP showing CBD stones. Endoscopic view of stenting is also seen.

Complications of sphincterotomy

- *Bleeding*
- *Sepsis*
- *Perforation*
- *Pancreatitis.*

Once CBD stones are extracted through ERCP, laparoscopic cholecystectomy is done.

- In open cholecystectomy
  - After the removal of gall bladder, on table cholangiogram is done through cystic duct using water soluble iodine dye to see any stones in CBD. Using stay sutures choledochotomy is done (opened longitudinally) to remove stones in CBD.



Fig. 12.51: Placing T-tube in CBD after choledocholithotomy. It is kept for 10-14 days.



Fig. 12.52: Diagram showing placement of T-tube in CBD after choledocholithotomy. Note the separate drain placed in the cholecystectomy bed to drain fluid, blood, bile.

  - After choledochotomy, stones are removed using Des jardin's choledocholithotomy forceps. Bake's CBD dilator is used to confirm the CBD patency.
  - T-tube (Kehr's) is then placed in the CBD and kept for 14 days.
  - After 14 days a post-operative T–tube cholangiogram is done to see for free flow of dye into the duodenum, so that T-tube can be removed.

– If T-tube cholangiogram shows persistent stone, it can be extracted after 6 weeks, through a basket (Dormia) or catheter (Fogarty) through the track or through a choledochoscope. Retained stones can also be removed through ERCP.

Indications for choledochotomy
(After open cholecystectomy)

1. U/S shows stone in CBD
2. Palpable stone in CBD
3. CBD diameter >10 mm
4. Recent H/O jaundice, and with raised serum alkaline phosphatase level
5. On table cholangiogram shows stone (done using C-arm image machine)
6. When in doubt



Fig. 12.53: T-tube cholangiogram showing retained stone in the CBD. (*Courtesy Dr Navin Chandra Shetty, HOD department of Radiodiagnosis KMC Mangalore*)

Methods to confirm the removal of T-tube—

- Clamp the T-tube, after 10-14 days and observe 48 hours for development of pain, jaundice and fever
- Confirm free flow of dye in T-tube cholangiogram

Management of retained CBD stones—

- Small stones may *spontaneously* pass down.
- Heparinised saline or bile acid *flushing* through the T-tube. (Wash 250 ml of normal saline with 25,000 IV heparin for 5 days)
- ***Burhenne technique***—After 6 weeks once T-tube track gets matured, track if needed is dilated using graduated dilators. Either using Dormia basket or Fogarty catheter or choledochoscope, stone is removed through T-tube track under fluoroscopic guidance (C-ARM)
- *ERCP* and stone removal in 3 weeks
- *Reoperation* if everything fails, either transduodenal sphincteroplasty or choledochojejunostomy
- ESWL with endoscopic sphincterotomy/extraction/lavage/stenting
- Through percutaneous transhepatic route, cholangioscope is passed and CBD is visualised, stone is identified and removed using Dormia basket or Fogarty catheter
- Laparoscopic choledocholithotomy
- Open choledocholithotomy often with choledochojejunostomy

Treatment of primary CBD stones:

- *Difficult and is associated with more complications*.



Fig. 12.54: T-tube cholangiogram showing dye in the duodenum and visualisation of normal biliary tree without any obstruction.

Preferred procedures:

- *Transduodenal sphincteroplasty*, or
- *Open choledochoduodenostomy*, side to side or
- *Open choledochojejunostomy*.

These procedures attain complete drainage of bile. Postoperatively they require long-term antibiotics.

Advantages of choledochoduodenostomy are–

- Bile leak is minimal/not there.
- Beneficial as a permanent remedy in multiple stones /sludge/stenosis/strictures/intrahepatic stones.

You are the sole master of your thought processes.

Problem with choledochoduodenostomy–

- Sump syndrome.

Note: Roux-en-Y choledochojejunostomy is equally good as choledochoduodenostomy.



Fig. 12.55: Technique of choledochoduodenostomy for CBD stones. Note the site of possible occurrence of sump syndrome.

Remember

- Gall stones are commonly radiolucent (90%).
- Multiple stones are usually faceted because of exertion of equal pressure in a compact gallbladder.
- Plain X-ray shows radio-opaque lesion to the right side of the vertebra below rib cage. It should be differentiated from kidney stones. In lateral view X-ray, gallstone will be in front of the vertebra whereas kidney stone overlaps the vertebra. Often gallstone has got central radiolucent area – *sea gull sign/Mercedes Benz sign*.
- *Silent/asymptomatic gallstone* is one which is identified on routine investigation where there are no specific relevant symptoms related to gallstones. Chances of developing symptoms in a silent gallstone is 5% in 5 years and 20% in 15 years.
- Presently ultrasound is ideal investigation for gallstones.
- To see gallbladder function or confirm cholecystitis radioisotope HIDA/PIPIDA scan is ideal.
- Cholecystitis can cause jaundice due to cholangitis. But other causes of jaundice should be ruled out – CBD stones/Mirizzi syndrome.
- *Limey gallbladder* is gallbladder filled with toothpaste like mixture of calcium carbonate and calcium phosphate. Plain X-ray shows dense radio-opaque gallbladder shadow (*opacified gallbladder*).
- *Porcelain gallbladder* is one where gallbladder wall is calcified because of chronic cholecystitis. It is potentially malignant. It should be removed either by open or laparoscopic method.
- Cholesterol stone occurs when there is alteration in levels of cholesterol, lecithin and bile salts. This altered bile has got more cholesterol than adequate micelle and is called as *lithogenic bile*. Here bile is in supramicellar zone. Cholesterol stone is radiolucent but causes acoustic shadow in U/S
- Mixed stones are commonest – 90%.
- '*Gallstone is a tomb stone erected to the memory of the organism within it*' – Moynihan's aphorism.
- *Saint's triad*: Gallstones – Colonic diverticulosis – Hiatus hernia.
- *Complications of gallstones*: Acute cholecystitis, chronic cholecystitis, empyema gallbladder, mucocele of gallbladder, perforation and peritonitis, secondary CBD stones, cholangitis, pancreatitis, Mirizzi syndrome, gallstone ileus, pericholecystitic abscess and carcinoma of gallbladder.
- Black pigment stones are more common in gallbladder; brown pigment stones are common in CBD.
- Cholesterol stones are common in Western countries; pigment/mixed stones are common in Asian countries.
- *Acute acalculous cholecystitis* is 5% common. It occurs after stress, major surgeries or in cholecystoses.
- *Xanthogranulomatous cholecystitis* is a rare pathological condition. Gall bladder is thickened with chronic inflammation. It is yellow xathogranulomatous in nature. It often extends to adjacent organs. It is due to reaction to penetrated bile.
- *Residual/retained bile duct stones* are one which is present in CBD within 2 years of initial surgery – cholecystectomy. They are usually missed secondary bile duct stones.
- *Recurrent bile duct stones* are one which is present 2 years after the initial surgery – cholecystectomy and CBD exploration. They are primary biliary stones.
- *Salmonella cholecystitis* (Typhoid Mary – a cook in New York transmitted typhoid through her infected faeces and urine) causes typhoid gallbladder. It can cause acute or chronic cholecystitis. Salmonella itself may predispose stone formation. Patient may be silent typhoid carrier.

COURVOISIER'S LAW

- '**In a patient with jaundice if there is palpable gallbladder, it is not due to stones**'.


Gallstones
Fibrotic gallbladder
CBD stone

Fig. 12.56: Courvoisier's law – "In a patient with jaundice if there is palpable gallbladder it is not due to stones". In stone disease gallbladder is contracted and fibrotic and so non-distensible.

- In obstruction due to CBD stone, gallbladder does not distend because it is chronically inflamed, thickened, fibrotic and contracted.
- In malignancy, like carcinoma of head of the pancreas or periampullary carcinoma, gallbladder will be distended and palpable to the right of rectus muscle in the right hypochondrium, as nontender, globular, smooth, soft, dull mass which moves with respiration and with horizontal mobility.

Rule may not be useful in—

- Absence of gallbladder
- Intra-hepatic gallbladder
- Previous cholecystectomy

Exceptions to the rule are—

- Double impacted stone - one in CBD one in cystic duct.
- Large stone in Hartmann's pouch.

SURGICAL JAUNDICE (Obstructive jaundice)

Causes

1. Biliary atresia.
2. Choledochal cyst.
3. CBD stones.
4. Ascending cholangitis.
5. Biliary strictures.


Choledochal cyst
CBD stricture
LN mass
Roundworm in CBD
Liver
Stomach
Klatskin tumour
CBD stone
Ca head of pancreas
Perampullary Ca
Chronic pancreatitis
Pancreatic stone

Fig. 12.57: Different causes of obstructive jaundice (surgical jaundice).

6. Sclerosing cholangitis.
7. Carcinoma of head and periampullary region of the pancreas.
8. Cholangiocarcinoma.
9. *Klatskin tumour* (Carcinoma at the confluence of hepatic ducts above the level of the cystic duct and so will cause hydrohepatosis without GB enlargement).



Fig. 12.58: CT scan showing hydrohepatosis due to obstruction below, in a patient with obstructive jaundice.

10. Extrinsic compression of CBD by lymph nodes or tumours.
11. Parasitic infestations.

Accountable, dependable, reliable are qualities that make a person responsible.

Clinical Features

- Severe jaundice.
- Pruritus, more on the back and forearms.
- Fever, may or may not be present.
- Loss of weight.
- Loss of appetite.



Fig. 12.59: Sclera of the patient with obstructive jaundice is greenish yellow in colour.

Classification of Causes of Obstructive Jaundice

1. *Congenital*: Biliary atresia, choledochal cyst.
2. *Inflammatory*: Ascending cholangitis, sclerosing cholangitis.
3. *Obstructive:* CBD stones, biliary stricture, parasitic infestation.
4. *Neoplastic*: Carcinoma of head or periampullary region of pancreas, cholangiocarcinomas, Klatskin tumour.
5. *Extrinsic compression* of CBD by lymph nodes or tumours.

Investigations for Obstructive Jaundice

1. Serum bilirubin. Normal value is less than 1.0 mg%. Both direct and indirect bilirubin are assessed. Direct is increased in obstructive jaundice, i.e. conjugated hyperbilirubinaemia. van den Bergh's test is done.
2. Serum albumin, globulin and A : G ratio. Normal S. albumin is more than 3.5 gm%.
3. Prothrombin time. Normal value is 12-16 seconds. It is significant if it is more than 4 from the control or more than one and half times the control. It is corrected by injection vitamin K, 10 mg IM OD for 5 days or by FFP—5-10 units.
4. Serum alkaline phosphatase, SGPT, SGOT, 5′ nucleotidase.
5. U/S abdomen.
6. ERCP to visualise the site of obstruction, brush biopsy, bile sample for analysis.
7. MRCP—Non-invasive diagnostic tool.
8. CT scan in case of tumours to assess operability.
9. Urine tests: Fouchet's test for bile pigments, Hay's test for bile salts and test for urobilinogen in urine.

Fouchet's test: 10 ml of urine + 5 ml of $BaCl_2$ + pinch of $MgSO_4$ causes formation of $BaSO_4$ which is filtered over a filter paper and few drops of Fouchet's reagent is added. Green or blue colour signifies presence of bile pigments in the urine.

***Hay's test for bile salt*:** Sprinkle sulphur to 2 ml of urine. In presence of bile salts sulphur sinks to the bottom.

***Ehrlich's test*:** 5 ml of freshly voided urine + 1 ml of Ehrlich reagent (p-dimethyl amino benzaldehyde) and wait for 5 minutes. Formation of red colour signifies presence of urobilinogen in urine. Normally it is present in traces, in obstructive jaundice it is absent and in haemolytic jaundice it is in excess.

Preoperative preparation of patient with obstructive jaundice

- Proper diagnosis and assessment
- Injection vitamin K IM 10 mg for 5 days
- Fresh Frozen plasma—often requires 6 bottles or more
- *Adequate hydration* is most important
- Blood transfusion in case of anaemia
- Oral neomycin, lactulose
- Mannitol 100—200 ml BD IV to prevent hepato renal syndrome
- Repeated monitoring by doing prothrombin time, electrolytes
- Antibiotics like third generation cephalosporins.
- Calcium supplements as calcium chloride IV

Treatment of Obstructive Jaundice

- CBD stones—ERCP stone removal, choledocholithotomy, transduodenal sphincteroplasty, choledocho jejunostomy or choledochoduodenostomy
- Carcinoma periampullary or head of pancreas—Whipple's operation or triple bypass or ERCP stenting.
- Biliary stricture—Stenting, choledochojejunostomy, Roux-en-Y hepatico jejunostomy.
- Klatskin tumour—Radical resection or palliative stenting.
- Biliary atresia—Kasai's operation or liver transplantation.
- Choledochal cyst—Excision, hepaticojejunostomy, mucosal resection.

Postoperative Management

- Monitoring with prothrombin time, bilirubin, albumin, creatinine, electrolyte estimation.
- FFP or blood transfusion.
- Antibiotics.
- Observation for septicaemia, haemorrhage, pneumonia, pleural effusion, bile leak.
- Care of T-tube and drains.
- T-tube cholangiogram in 10-14 days.
- TPN, CVP line, nasogastric tube, urinary catheter.

CBD STRICTURES (BILIARY STRICTURES)

Causes

1. *Postoperative (80% common)*
    - After cholecystectomy [open or laparoscopic, more common following laparoscopic (0.8%) than open method (0.35%)].
    - Biliary surgery.
    - Gastrectomy.
    - Liver surgery.
    - Duodenal and pancreatic surgery.
2. *Inflammatory:* Stricture following recurrent attacks of cholangitis due to—
    - CBD stones.
    - Parasites—*Ascaris Lumbricoids, Clonorchis Sinensis.*
    - Primary sclerosing cholangitis.
3. *Malignant:* Due to cholangiocarcinoma.
4. *Traumatic.*

Bismuth classification of biliary stricture

I. Low CBD stricture with stump (proximal to stricture) > 2 cm
II. Middle CBD stricture with proximal stump < 2 cm
III. Hilar. Confluence of right and left hepatic ducts is intact
IV. Separated right and left hepatic ducts
V. Stricture involving intrahepatric ducts

Clinical Features

- Obstructive jaundice.
- Pain.
- Features of ascending cholangitis.
- Profuse persistent bile leak.

A



Fig. 12.60A

B



Fig. 12.60B

C



Fig. 12.60C

The mother's heart is child's schoolroom.—Henry Ward Beecher.



Fig. 12.60D



Fig. 12.60E

Figs 12.60A to E: Bismuth classification of stricture CBD.

Causes of postoperative stricture—
- Too much traction to the GB during ' Fundus first cholecystectomy'
- Blind applying of artery forceps in Calot's to control bleeding
- Anomalies of biliary tree
- Inflammatory adhesions at Calot's triangle
- Injury during other surgery like gastrectomy

Note: ***Hogarth Pringle's manoeuvre*** is ideal to control bleeding on table by applying pressure using thumb and fingers over the Foramen Winslow.

Investigations

- U/S abdomen.
- Liver function tests.
- ERCP.
- On table cholangiography.
- MRCP.

Treatment

- ERCP stenting.
- Choledochoduodenostomy or jejunostomy.
- Roux-en-Y hepaticojejunostomy.

SCLEROSING CHOLANGITIS

- It is fibrous thickening of the CBD and biliary ductular wall, associated with multiple strictures with dilatation in between the strictures. Both extra- and intrahepatic ducts are involved.
- They have increased risk of developing cholangiocarcinoma.

Types

1. *Primary* sclerosing cholangitis is one wherein no cause is found and is associated with ulcerative colitis, Sjogren's syndrome, Crohn's disease, Grave's disease. It eventually leads to biliary cirrhosis. *Primary sclerosing cholangitis* (PSC) is an idiopathic, progressive, chronic, cholestatic pathology with diffuse inflammation, sclerosis, and obliteration of intra and extra hepatic biliary systems. There will be multiple areas of strictures and dilatations. It has high risk for cholangiocarcinoma. It could be an autoimmune disease.
2. *Secondary* sclerosing cholangitis is due to stones, trauma, congenital lesions. AIDS, chemotherapy (5FU), transplantation, collagen diseases, sarcoidosis, histiocytosis.

Features

- Common in young men – 70%.
- Intermittent jaundice.
- Abnormal liver functions.
- Weight loss, pain, fever, pruritus.
- Features of ulcerative colitis in case of PSC.
- PSC may be associated with retroperitoneal fibrosis, mediastinal fibrosis, Riedel's thyroiditis, orbital pseudo tumour.

Investigation

- ERCP shows *beaded appearance* of biliary tree.
- LFT is altered.

Treatment

- Stenting.
- T-tube drainage.
- Large dose steroids.

- Immunosuppression therapy – methotrexate, azathioprine, tacrolimus, cyclosporine.
- Ursodeoxycholic acid is beneficial.
- Liver transplantation.

CARCINOMA GALLBLADDER

- It is more common in *India (Patna)* and Asian countries.
- It is common in *females* and elderly. Male : Female :: 1 : 3.

Aetiologies for Carcinoma of Gallbladder

- 3% of gallstones with cholecystitis will develop carcinoma of gallbladder.
- 90% of carcinoma of gallbladder is associated with gallstones. Risk of developing carcinoma in gallstone disease is 7-10 times more than general population. Relative risk is less if stone size is less than 2 cm; if stone size is 2-3 cm in size it is 2.5; it is 10 or more if stone size is more than 3 cm.
- Choledochal cyst, anomalous pancreaticobiliary duct junction (20%), cholesteroses of gallbladder, gallbladder polyp more than 1 cm in size or more than 3 in number or adenomatous polyp.
- Chronic typhoid carriers, carcinogens, inflammatory bowel disease, hepatitis B and hepatitis C virus infection.
- Porcelain gallbladder is more prone for malignant transformation (25%) and 90% of them are inoperable tumours.
- Nitrosamines.

Gross Types of Carcinoma Gallbladder

- Polypoid.
- Scirrhous.
- Proliferative.

Microscopy

Commonly it is adenocarcinoma; occasionally squamous cell carcinoma, adenosquamous or carcinoid tumour can occur.

Spread of Carcinoma Gallbladder

- Direct spread to liver (segment IV and V), bile duct, duodenum, colon and kidney.
- Lymphatic – lymph node of Lund, periportal nodes, peripancreatic and periduodenal nodes.
- Blood spread – to liver, lungs and bones.
- Perineural spread is also known to occur.

Staging of carcinoma gallbladder

Nevin's staging –
Stage I – Intramural
Stage II – Spread to muscularis propria
Stage III – Spread to serosa
Stage IV – Spread to cystic lymph node of Lund
Stage V – Direct spread to adjacent organs / metastases

TNM staging

Tumour	*Nodal spread*
Tis – Carcinoma *in situ*	N0 – No nodes
T1 – Spread to mucosa or muscle layer	N1 – Spread to cystic/nodes in porta/hepatoduodenal ligament
T1a – Only mucosal involvement	
T1b – Spread to muscle layer	N2 – Spread to peripancreatic/celiac/periduodenal/superior mesenteric nodes
T2 – Spread to subserosa but not beyond serosa	
T3 – Spread beyond serosa or one adjacent organ or < 2 cm to liver	*Metastases* –
T4 – Spread > 2 cm to liver, 2 or more adjacent organs-CBD, stomach, duodenum, colon, omentum	M0 – No distant spread M1 – Presence of distant spread

Features of Carcinoma of Gallbladder

- Pain in right hypochondrium, mass in right upper abdomen which is hard and nontender.
- Jaundice is common.
- Significant weight loss in short duration.
- Acute presentation of cholecystitis.
- Palpable nodular liver secondaries, ascites.
- It is common in places where there is more prevalence of gallstone disease – Patna – Bihar
- It is common in females.
- Incidentally confirmed as carcinoma gallbladder histologically after cholecystectomy for chronic cholecystitis.

Investigations

- Ultrasound abdomen.
- CT abdomen to see operability.
- U/S guided FNAC.
- Liver function tests.
- MRCP.
- Laparoscopy.
- CA 19-9 is elevated in 80% of cases.

Treatment

- Cholecystectomy with resection of liver segments IV and V – extended cholecystectomy with perihepatic nodal clearance.

You are the sole master of your thought processes.

- Hemihepatectomy with cholecystectomy with nodal clearance.
- Chemotherapy either systemic or intraarterial, and adjuvant radiotherapy but with poor success rate.

Prognosis

- Overall prognosis for carcinoma gallbladder is poor due to early spread and aggressive nature of the tumour.
- 5 year survival is only 5%.



Fig. 12.61: Gallbladder showing proliferative carcinomatous lesion.



Fig. 12.62: Gallbladder showing scirrhous carcinoma with preexisting gallstones and cholesteroses.

CHOLANGIOCARCINOMA (Bile duct carcinoma)

- It is associated with sclerosing cholangitis, clonorchiasis infestation, Caroli's disease or choledochal cyst.
- It is an aggressive adenocarcinoma which presents as obstructive jaundice.
- It commonly occurs at the hepatic duct confluence.

Classification

- Intrahepatic – 10%.
- Perihilar – 65%.
- Distal – 25%.

Features

- Main presentation is painless obstructive jaundice of short duration.
- Palpable liver either smooth and soft (hydrohepatotic) or hard nodular (secondaries).
- Weight loss is typical and significant.

Classification of Perihilar Cholangiocarcinoma (Bismuth)

- Type I – below the confluence of RHD and LHD
- Type II – reaching the confluence of RHD and LHD
- Type III – involving CHD and RHD/LHD
- Type IV – involving confluence and both RHD and LHD or multicentric tumour

Investigations

- ERCP and choledochoscope.
- Liver function tests.
- PTC.
- U/S abdomen.
- MR scan—Best investigation.

Treatment

- When operable, portal region clearance with hemihepatectomy can be done.
- Most often it is inoperable. Stenting can be done to relieve jaundice.
- Chemotherapy – 5 FU; Gemcitabine.

KLATSKIN TUMOUR

- It is cholangio carcinoma at the confluence of the hepatic ducts and common hepatic duct above the level of the cystic duct.
- *It causes obstructive jaundice with hydrohepatosis without enlargement of gallbladder.*
- Management is like cholangiocarcinoma.



Fig. 12.63: Klatskin tumour.

Cholangiocarcinoma

- It is an uncommon tumour of elderly. 1 in 1,00,000 is the incidence
- Primary sclerosing cholangitis is the commonest association. 20 fold increased risk
- Choledochal cyst, Caroli's disease, pyogenic cholangiohepatitis, Clonorchis sinensis, opisthorchis viverrini infestation, hepatolithiasis, hepatitis C, Lynch syndrome II, bile duct adenoma and papillomatosis are other causes
- Chemical carcinogens like thorium, nitrosamines, diosmin also can cause
- Intrahepatic cholangiocarcinoma is 10%
- 60% cases are proximal to cystic duct CBD junction
- Features are jaundice, pain, hepatomegaly, cachexia, early satiety and weight loss
- It is adenocarcinoma type
- Lymph node spread is common
- Resection along with liver/resection along with pancreas are surgical options
- But surgical resection is possible only in 5% of cases
- Stenting/bypass are palliative options
- Doxorubicin, cis platin and I_{131} anti CEA antibodies are adjuvant therapies
- Condition has got 90% mortality in one year

BILIARY FISTULAS

Types

a. *External:* Usually occurs as a complication of surgery following—
  - Gastrectomy.
  - Cholecystectomy open or laparoscopic.
  - CBD surgery.
  - Pancreatic surgery.

b. *Internal:*
  - Cholecysto-duodenal fistula causing gallstone ileus.
  - Cholecysto-enteric fistula.
  - Cholecysto-choledochal fistula.

External biliary fistulas are difficult to manage, often dangerous, but many a times resolve spontaneously.

Investigations

- Fistulogram.
- ERCP.
- Electrolyte estimation.
- Liver function tests.

Treatment

- Total parenteral nutrition (TPN).
- Antibiotics.
- Blood transfusion.
- Electrolyte management.
- Care of the fistula wound with regular dressing, using zinc oxide cream has to be done to protect the skin.
- Later continuity of biliary system has to be restored by open surgery or through ERCP and stenting.

GALLSTONE ILEUS

It is a type of acute intestinal obstruction, often seen in elderly and is due to blockage by a bolus or mass of gallstones which commonly enter the intestine through cholecystoduodenal fistula or rarely through cholecysto-intestinal or –gastric fistulas.



Fig. 12.64: Gallstone ileus

Every day is little life. Live it to its fullest.

Gallstones in the gallbladder
↓
Cholecystitis
↓
Suppuration and adhesion over the duodenal wall
↓
Communication of gallbladder into the duodenum
↓
Gallstones pass into the duodenum forms a *bolus* *('Rolling stone gather mass')*
↓
Blocks narrow part in the ileum.
↓
Gallstone ileus

Clinical Features

- Pain abdomen and features of intestinal obstruction.
- Stones may perforate the ileum to cause peritonitis.

Investigations

- Plain X-ray abdomen in erect posture shows *air in the biliary tract* (branching gas pattern) and multiple air fluid levels.
- U/S abdomen.
- CT is diagnostic.

Treatment

- Laparotomy, enterotomy, removal of gallstones and closure of enterotomy. Laparotomy and crushing the stones with finger to relieve the obstruction is often useful.
- Cholecystectomy is done at a later period (after 6 - 12 weeks).

Causes for gas in the biliary tree–

- Cholecystoduodenal fistula
- Choledochoduodenostomy
- Choledochojejunostomy
- Transduodenal sphincteroplasty
- Emphysematous cholecystitis

HEMOBILIA

- It is bleeding commonly from the liver or occasionally from the gallbladder into the biliary tract.
- There is communication between a blood vessel and a bile duct or any part of the biliary tree.

Causes

- Accidental trauma.
- Percutaneous diagnostic and therapeutic procedures.
- Vascular diseases of the hepatic artery.
- Malignant liver diseases.
- Portal hypertension.
- Parasitic liver diseases like hydatid disease.
- Gallstones rarely erode into hepatic artery causing life-threatening hemobilia.

Blood and necrotic material drains into the biliary tree causing gastrointestinal bleeding. As bile interferes with coagulation a fatal haemorrhage can occur.

Clinical Features

- Pain which is colicky in nature.
- Obstructive jaundice.
- Haematemesis and melaena.

Triad of sandblom in hemobilia

- Jaundice – 60%
- Pain – 70%
- Melaena – 90%

Investigations

- LFT.
- U/S abdomen.
- Selective arteriography.
- Upper GI scopy.

Treatment

- *Aim: To stop bleeding and to relieve biliary obstruction.*
- Antibiotics.
- Blood transfusions.
- Selective arterial embolisation.

Hemobilia is often a fatal condition.

WHITE BILE

- It is double misnomer.
- It is *neither white nor bile.*
- It is opalescent.
- It is *mucus secreted by the lining of biliary tree.*
- It signifies severe obstruction due to stone (impacted in the CBD), or carcinoma head of pancreas or periampullary region.
- It is on table finding during surgery.
- It means liver is unable to secret bile and so can anticipate hepatic failure.
- Indicates a poor prognosis


Liver
GB
SINGLE USE ONLY
White bile

Fig. 12.65: Demonstration of white bile on table. It is not white but opalescent. It is not bile but it is mucus.

CHOLECYSTECTOMY

It is the surgical removal of gallbladder.

Prophylactic cholecystectomy is done in–

- Diabetic patients
- Congenital haemolytic anaemia
- Patients who has underwent bariatric surgery

Indications

- Gallstones—symptomatic.
- Cholecystitis—acute, chronic.
- Acalculous cholecystitis.
- Empyema gallbladder.
- Mucocele gallbladder.

Approach

- *Open*
  - Right subcostal incision (Kocher's).
  - Right paramedian.
  - Horizontal incision.
  - Mayo-Robson incision.
- *Laparoscopic approach.*


Kocher's incision (open method)
10 mm port
5 mm port
Mayo-Robson incision
5 mm port
10 mm port (Laparoscope to pass)

Fig. 12.66: Incisions for open cholecystectomy and laparoscopic cholecystectomy.

Technique

After opening the abdomen, colon is pushed downwards and stomach medially.

Duct—first method: Here *Calot's triangle* is dissected. Cystic artery is identified and ligated. Cystic duct is ligated close to the gallbladder. Gallbladder is separated from gallbladder fossa and removed. Haemostasis is maintained.

Fundus—first method: It is done in difficult gallbladder due to dense adhesions. Fundus is separated from the liver bed. Dissection is carried proximally until cystic duct and cystic artery are identified, which are then ligated.

Drain is placed, which is removed after 72 hours.

On table cholangiogram is a must after cholecystectomy.

Complications of Cholecystectomy

- Complications can occur either in open method or in laparoscopic method.
- Open method is done through either right paramedian incision or Kocher's incision (right subcostal).


Right hepatic
Cystic A
GB
Cystic duct
Common hepatic A
Stomach

Fig. 12.67: Ligation of cystic duct and cystic artery while doing cholecystectomy.

The same beam of light can illuminate two objects and produce two different effects.



Fig. 12.68: Diagram showing the partial cholecystectomy wherein GB is removed at Hartmann's pouch, distal to Calot's triangle. It is done when there is dense adhesions,with difficult surgical plane.

Complications which can occur in both:
- Infection and subphrenic abscess.
- Bleeding from cystic artery, and from liver bed.
- Injury to CBD or hepatic duct.
- Bile leak and biliary fistula formation.
- Biliary stricture formation.
- Injuries to colon, duodenum, mesentery.

Laparoscopic Cholecystectomy

It is the most popular method to remove gallbladder. It is the gold standard treatment for gallstone.

Position

- Supine, head end up and right side up.

Anaesthesia – general.

Ports

- 10 mm port in umbilicus to pass 10 mm telescope.
- 10 mm port in midline epigastrium as working channel.
- Two 5 mm ports at midclavicular and anterior axillary line in subcostal region.

Procedure

After creation of pneumoperitoneum with 12-14 mm pressure, 10 mm umbilical port is inserted. Telescope is passed. Under vision remaining ports are passed. With lateral 5 mm port, gallbladder grasper forceps is passed and fundus of gallbladder is held and pushed up towards the diaphragm. With middle 5 mm port grasper is passed to hold Hartmann's pouch. With 10 mm port dissector is passed using reducer. Calot's triangle is dissected. Cystic duct is identified. Adhesions are released. First posterior dissection is completed. Cystic artery is above and deep to cystic duct. Cystic duct is clipped or ligated. Cystic artery is also clipped. Gallbladder is dissected off the liver bed using cautery (hook /spatula)/harmonic scalpel. Gallbladder is removed through 10 mm working port with reducer or using a sterile bag. Any bleeding points are coagulated. If needed saline wash is given to the bed. If infected, if gallbladder is opened, if there are adhesions, if there is oozing from gallbladder bed, a tube drain is placed through lateral 5 mm port. All ports are removed. Umbilical port is sutured in layers. Other ports are sutured. Patient is asked to take oral food in 24 hours and can be discharged in 24-48 hours.



Fig. 12.69A



Fig. 12.69B



Fig. 12.69C

Figs 12.69A to C: Photos of laparoscopic cholecystectomy showing cystic duct, gallbladder, Calot's triangle and clipped cystic duct.

Problems

- Difficult Calot's triangle.
- Dense adhesions.
- Bleeding.
- Anomalies of cystic duct, cystic artery.

Complications

- Bile duct injury – 0.05 %.
- Bleeding.
- Bile leak.
- Infection, cholangitis, septicaemia.
- Subphrenic abscess formation.
- Injury to colon, duodenum, mesentery.

Note: *Waltman-Walter syndrome*: It is compression of IVC due to collection of fluid in subphrenic space during post cholecystectomy period. It mimics coronary thrombosis.



Figs 12.70: ERCP picture showing stricture and passing stent into CBD.

BILE DUCT INJURIES

Causes

- Cholecystectomy—open or laparoscopic.
- Trauma.
- Instrumentation—ERCP, baby endoscope, choledochoscope.
- Other surgeries—pancreatic, duodenal, gastric. Anomalous biliary system increases the risk of injury.

Types (Strasberg's classification)

A — Cystic duct leak or leak from small ducts in the liver bed
B — Aberrant right hepatic duct with occlusion
C — Aberrant right hepatic duct with open drainage
D — Lateral injuries to the extrahepatic duct with open drainage
E — Circumferential injuries of CBD at various levels

Presentations

- Fever.
- Pain.
- Bile stasis.
- Jaundice.

Complications

- Septicaemia.
- Biliary fistulas.
- Biliary peritonitis.
- Subphrenic abscess.

Investigations

- Ultrasound.
- Fistulogram.
- ERCP, PTC, MR scan.
- Hepatobiliary scintigraphy.
- LFT.

Treatment

- ERCP, sphincterotomy and stenting.
- TPN.
- Antibiotics.
- Management of electrolyte imbalance.
- Open repair – Roux-en-Y hepaticojejunostomy.

POST-CHOLECYSTECTOMY SYNDROME (15%)

Recurrent, new or persistent symptoms after cholecystectomy in patients who have no demonstrable abnormality is called as post-cholecystectomy syndrome. However importance lies in ruling out the other causes of the

Faith makes all things possible; hope makes all things bright.

symptoms like peptic ulcer, hiatus hernia, pancreatic diseases, residual CBD stone, cystic duct remnant, papillary stenosis. True post cholecystectomy syndrome is treated with proper counseling, psychiatric evaluation and drug therapy. It should be evaluated thoroughly.

SUMP SYNDROME (Fig. 12.55)

It is commonly observed after choledochoduodenostomy rarely after choledochojejunostomy. CBD distal to the choledochoduodenostomy acts as a reservoir with stasis for food particles, bile, stones and sludge. Often it causes cholangitis and narrowing of the stoma of choledochoduodenostomy. Conversion to end-to-end Roux-en-Y choledochojejunostomy is required.

Self-assessment Questions

1. Discuss aetiology, bacteriology, clinical features and management of acute cholecystitis.
2. Enumerate causes for obstructive jaundice and investigations.
3. Causes of surgical jaundice.
4. Aetiology, types, clinical features, complications and management of gallstones.
5. Biliary atresia.
6. Choledochal cyst.
7. PTC.
8. OCG.
9. ERCP.
10. T-tube cholangiogram.
11. Chronic cholecystitis.
12. Acalculous cholecystitis.
13. Gallbladder polyp (Cholecystoses).
14. Mucocele of gallbladder.
15. Empyema of gallbladder.
16. Murphy's sign.
17. Charcot's triad.
18. Klatskin tumour.
19. Gallstone ileus.
20. Complications of cholecystectomy.
21. Laparoscopic cholecystectomy.
22. Liver function tests.
23. Classify choledochal stones and discuss clinical features and management of choledochal stones.
24. Biliary fistula.
25. Stricture CBD.

13

Spleen

Surgical anatomy
Functions of the spleen
Splenunculi
Splenic injury
Splenomegaly
Hereditary spherocytosis
Immune haemolytic anemia
Thalassaemia
Sickle cell disease
Idiopathic thrombocytopenic purpura
Thrombotic thrombocytopenic purpura (TTP)
Splenectomy
Overwhelming postsplenectomy infection
Splenic artery aneurysm
Splenic abscess

SURGICAL ANATOMY

- It is a wedge shaped organ lying mainly in left hypochondrium, along the long axis of 10th rib.
- Hilum of spleen transmits splenic vessels and nerves. The visceral surface is related to stomach, splenic flexure of colon, kidney.

Ligaments of Spleen

Spleen is suspended by two ligaments *(a) lienorenal ligament, (b) gastrosplenic ligament.*

- Lienorenal ligament transmits blood vessels to spleen. The tail of pancreas lies in this ligament, which can be damaged during splenectomy.
- The gastrosplenic ligament contains short gastric vessels which supply the left half of greater curvature of stomach.
- Phrenicocolic ligament comes in contact with lower pole of spleen, which may be damaged during mobilization of splenic flexure of colon.

Blood Supply

Splenic artery is the branch of coeliac artery but may arise from aorta or superior mesenteric artery, blood flow is 300 ml/mt. *Splenic vein* joins the superior mesenteric vein at right angle behind the neck of pancreas to form the portal vein.

Splenic parenchyma contains *white pulp* and *red pulp*. *White pulp* lies in centre surrounding the central artery, which is a branch of trabecular artery. It is made up of lymphatic nodules with germinal centres and periarterial lymphatic sheaths with a network containing lymphocytes and macrophages. White pulp is surrounded by marginal zone which contains end arteries from central and peripheral penicilliary arteries. Marginal zone contains marginal sinus which filters the materials from the white pulp. Immunoglobulins secreted by white pulp enter marginal zone and into main blood stream.

Red pulp is located outer to marginal zone. Red pulp contains cords and sinuses. Central artery gives reticular branches which open into these sinuses and cords wherein particles are phagocytosed. Commonly central artery eventually ends in these cords and sinuses. Few end branches of the central artery directly enters the pulp vein. Cords and sinuses eventually drain into pulp vein. Blood circulating through these cords and sinuses are called as *'open'* circulation (90%). Blood passing through white pulp but not entering these cords and sinuses are called as *'closed'* circulation (10%).

Spleen is palpated under left costal margin during inspiration. It has to enlarge 2-3 times its normal size to become palpable.

FUNCTIONS OF THE SPLEEN

Spleen has got two groups of functions –

1. *Cellular function.*

If you don't know where you're going, you may miss it when you get there.



Fig. 13.1: Architecture of spleen showing red pulp (peripheral); white pulp (central); open and closed circulation; marginal zone and sinuses and trabecular artery and vein.

- Removal of non deformable intracellular substances from deformable cells is called as "*pitting*". *Heinz bodies/Howell – Jolly bodies, Pappenheimer siderotic bodies* are removed by this method from RBC's. Post splenectomy patients will show these bodies in the RBCs in peripheral smear. In splenunculi, these bodies will be absent even after splenectomy.
- Removal of aged/abnormal red cells is done by a process of "*culling*". RBC's which loose osmotic balance and membrane integrity is called as non-deformable and they are removed by this method.
- Half life of platelets is 10 days. In splenomegaly 80% of platelets may be sequestered in spleen causing thrombocytopenia. Normally spleen is reservoir for platelets. 1/3rd of total platelet mass is present in spleen. In pathological status like immune diseases phagocytosis of platelets in spleen is accelerated by many folds.
- Splenomegaly and hypersplenism can cause neutropenia. Neutrophil half life is 6 hours.
- Bacterial clearance also occurs in spleen by phagocytosis. After splenectomy, patients are more prone for OPSI.

2. *Immunologic functions* like synthesis of antibody IgM; formation of lymphocytes; production of tuftsin, opsonins, properdin and interferons.

Functions of spleen are -

- Response to antigenic challenge—by secreting antibodies like Ig M, tuftin, opsonins, properdin, interferons. These agents make bacteria and other organisms more vulnerable to phagocytosis. All bacteria including the capsulated types, virus and fungi are destroyed efficiently.
- Destruction or correction of abnormal cells like old RBC's, target cells, siderocytes, spherocytes or removal of inclusion bodies or parasites from the RBC's by culling and pitting.
- Phagocytosis of foreign substances.
- As platelet reservoir.
- Erythrocyte production: In fetal life, it is an important site of RBC production till 5th month of gestation. In adults erythropoiesis in spleen occurs only if marrow production is inadequate, e.g. in myelofibrosis.
- Iron reutilization.

SPLENUNCULI (30%)



Fig. 13.2: On table photo of splenunculi with splenomegaly. Splenunculi should be removed otherwise disease will recur.

- These are single or multiple **accessory spleens**.

Sites

- Hilum of spleen (50%)
- Near splenic vessels
- Tail of the pancreas (30%)
- Splenic ligaments - gastrosplenic/splenorenal
- Mesocolon
- Greater omentum

- After splenectomy, they undergo hyperplasia and lead to recurrence of the disorder for which spleen was removed.
- Blood peripheral smear, in these patients with splenunculi *will not show* Howell—Jolly bodies. Pappenheimer siderotic bodies.
- Accessary spleen can also be occasionally present adjacent to left ovary or adjacent to left testis.

SPLENIC INJURY (Rupture spleen)

Causes

- Splenic injury occurs commonly following road traffic accidents, other blunt injury or penetrating/stab injuries.

- Most often associated with fracture of left lower ribs, haemothorax, injury of liver (left lobe commonly, occasionally both lobes), bowel, tail of pancreas, left kidney.
- Injury is more common and severe in *enlarged spleen*, i.e. in malaria, tropical splenomegaly, infectious mononucleosis.
- Spontaneous rupture of spleen can occur in malaria and infectious mononucleosis.
- *Larang* was used to kill by the murderers in far east where malaria was endemic leading to splenomegaly, which ruptured more easily.

Types of Injury

1. *Splenic subcapsular haematoma:* After initial injury patient remains asymptomatic for a short period. But this haematoma ruptures later, may be after few days causing torrential haemorrhage.
2. *Clean incised wound over the surface*: This can be treated by splenorrhaphy.
3. *Lacerated wound*
4. *Splenic hilar injury* causes torrential haemorrhage, may even cause death. So immediate surgical intervention and splenectomy is done.
5. Splenic injury associated with other injuries (left kidney, left colon, small bowel, pancreas, diaphragm, left lung).

Associated injuries

- Left lobe liver injury
- Tail of pancreas injury
- Left kidney, left colonic injury
- Small bowel injury
- Diaphragm and left lung injury
- Fracture lower ribs—left sided (30%)
- Left sided haemothorax

Presentation

Hilar injury presents with rapid development of *shock and deteriorates fast.* Even death can occur sometimes. Here *emergency surgery and splenectomy is mandatory*.

- In other types, features of shock (pallor, tachycardia, restlessness, hypotension), pain, tenderness and abdominal rigidity in left upper quadrant is seen.
- Later there will be abdominal distension due to haemoperitoneum.
- Dullness in the left flank which does not shift, as the collected blood gets clotted. *Dullness without shifting*—***Ballance's sign***.



Fig. 13.3: Types of Splenic Injury. (A) Subcapsular hematoma, (B) Incised wound, (C) Lacerated wound and (D) Hilar injury

- Clot collected under the left side of the diaphragm irritates it and the phrenic nerve causing *refered pain in the left shoulder*—***Kehr's sign***. There may be left sided haemothorax with fracture of ribs.

  Delayed presentation is also possible due to formation of subcapsular haematoma which later gives way. Initially gets temporarily localized by greater omentum, later giving way leading to torrential bleeding. Blood clot temporarily seals off the bleeding which later gets dislodged causing severe bleeding. This time period in between is called ***'latent period of Bandet'.***
- Pseudo-aneurysm and traumatic splenic arterio-venous fistula formation can also occasionally cause delayed life threatening haemorrhage.
- Features of other abdominal organ injuries may be present.

Signs in splenic rupture

- *Kehr's sign*—pain in left shoulder 15 minutes after foot end elevation
- *Ballance's sign*—left sided abdominal dullness which will not shift
- *Saegesser's tender point* between left sternomastoid and scalenus medius
- Latent period of Bandet—Refer above

Splenosis: Autotransplantation of fragments of splenic tissue may occur within the peritoneal cavity following rupture of spleen

A smile is the shortest distance between two people.



Figs 13.4A to C: Splenic injury with splenic haematoma.

Investigations

- U/S abdomen is the investigation of choice, as it is quicker, cheaper and non-invasive.
- Hb%, PCV, blood grouping and cross matching. *Adequate amount of blood must be kept ready for transfusion.*
- CT scan will show type of splenic injury and its class.

Plain X-ray abdomen. Findings are—

1. Obliteration of splenic outline
2. Obliterarion of psoas shadow (most important feature)
3. Indentation of fundic gas shadow
4. Fracture of lower ribs
5. Elevation of left side of diaphragm
6. Free fluid in the abdomen between coils of intestine

- ***Diagnostic peritoneal lavage (DPL):*** By subumbilical incision the peritoneal lavage catheter is introduced into the peritoneal cavity. One litre of crystalloid (normal saline) is introduced into the cavity. Patient is turned to both left and right side and fluid is collected back. It is sent for cytology, culture, microscopy and biochemical analysis.
  It is significant when the aspirated fluid contains–
  - Gross blood of 10 ml.
  - >100000/mm^3 of RBC.
  - >500/mm^3 of WBC.
  - Bile, bacteria or food fibres.
  - Amylase > 175 units/dl.



Fig. 13.5: Lacerated injury over the spleen. Patient underwent splenectomy.

- Angiogram, for diagnosis and often for angiographic embolisation to reduce the bleeding and to manage splenic injury non-operatively is also becoming routine in many centres.

Complications of Splenic Rupture/Trauma

- Blood loss.
- DIC.
- Sepsis.
- Splenic artery pseudoaneurysm.
- Splenic arteriovenous fistula.
- Problems of associated injuries like of pancreas.

Splenic organ injury scale

Grade I	Non expanding subcapsular haematoma <10% surface area. Non-bleeding capsular laceration with <1 cm depth
Grade II	Non expanding subcapsular haematoma 10-50% surface area. Nonexpanding intraparenchymal haematoma <2 cm
Grade III	Expanding subcapsular or intraparenchymal haematoma. Bleeding subcapsular haematoma or subcapsular haematoma > 50% area or intraparenchymal haematoma >2 cm or parenchymal laceration >3 cm depth
Grade IV	Ruptured intraparenchymal haematoma with active bleed; laceration involving segmental or hilar vessels with > 25% devascularisation
Grade V	Shattered or avulsed spleen; hilar disconnection with entire spleen devascularisation

Treatment

Initial Management

- Central venous line for perfusion and monitoring.
- Transfusion of blood as needed.
- Antibiotics coverage.
- Urinary catheterization.
- Nasogastric tube aspiration.

Surgical Management

Emergency splenectomy

- It is done through midline/left subcostal incision. Thoracoabdominal extension of incision may be needed for rapid control of bleeding for injury to a large tropical spleen with severe bleeding. Other associated injuries should be looked for and dealt with (injury to left lobe liver/pancreas/intestine/colon).

Partial splenectomy (upper/lower)

- It can be done by retaining either of the upper or lower polar branches of the splenic artery.

Splenorrhaphy

- In especially clean incised wound, spleen can be salvaged by suturing the wound carefully with placement of gel foam, topical thrombin, absorbable mesh wrap over the wound.
- But in class IV or V injuries splenorrhaphy is not possible.

Advantages of splenorrhaphy

- It avoids OPSI
- It avoids dead space and so prevents potential space for subphrenic abscess
- Cellular components of blood are better maintained

Salutary effect

- In traumatic rupture of spleen, spleen is cut into pieces of 0.5 cm and placed in omental pockets.

Non Operative Management

- When facilities are available, splenic injury can be managed conservatively by non-operative management.
- Clinically close observation, serial haematocrit evaluation, serial CT abdomen/U/S abdomen at regular intervals to assess the progress or regress of the bleeding spleen has to be done.
- Absolute bed rest, sedation, antibiotic coverage and proper monitoring are needed.
- It is often supported by angiographic embolisation to improve the splenic salvage rate. But it may cause pain, splenic abscess or infarction.
- *Indications for non operative treatment*
  - Only splenic injury - no other associated injuries.
  - Grade I, II and III injuries.

Complications of splenectomy

1. Haemorrhage and shock
2. Haematemesis
3. Pancreatitis
4. Pancreatic fistula
5. Gastric dilatation
6. Left sided pleural effusion
7. Left sided colonic injury
8. Severe sepsis
9. Changes in cellular component of blood
10. DIC

> *The best bridge between despair and hope is a good nights sleep*—E. Joseph Cossman



Fig. 13.6: Splenorrhaphy is done in incised wound.



Fig. 13.7: Partial splenectomy is done when one of the branches of the splenic artery is ligated and other part is retained.



Fig. 13.8: Splenectomy is done in large wounds, lacerations, hilar injuries.

SPLENOMEGALY

Causes

1. *Infective:* Tuberculosis, splenic abscess, infectious mononucleosis, malaria, typhoid, kala azar.
2. *Blood diseases:* Chronic myeloid leukaemia, myelofibrosis, polycythaemia, hereditary spherocytosis, haemolytic anaemia, idiopathic thrombocytopenic purpura (I T P).
3. *Metabolic:* Gaucher's disease, amyloidosis, porphyrias,
4. *Portal hypertension.*
5. *Collagen diseases.*
6. *Malignancy*: Hodgkin's lymphoma, splenic sarcomas.

Masses which mimic enlarged spleen

- Kidney mass (Left sided)
- Retroperitoneal mass
- Left colonic mass
- Left adrenal mass

Clinical features of enlarged spleen

- Mass in the left hypochondrium
- Notch is felt
- Moves with respiration
- Dull to percuss
- Directed towards right iliac fossa
- Hook sign: Inability to hook under left costal margin
- Can not insinuate finger under left costal margin

HEREDITARY SPHEROCYTOSIS

It is an autosomal dominant disease effecting males and females equally.

Pathology

- Here there is an increase in red cell wall permeability to sodium. So sodium leaks into the red cells and it becomes spherical and more fragile. This leads to greater loss of membrane phospholipid resulting in weakening of the membrane with increase in energy and oxygen requirement. So these RBC's are destroyed in spleen causing haemolytic anaemia, haemolytic jaundice, unconjugated hyperbilirubinaemia, pigmented gall-stones, cholangitis.
- Defect in components of red cell membrane like *spectrin (mainly)*, ankyrin, band 3, or protein 4-2 causes weakness of red cell wall. This promotes the influx of sodium into the cell.
- Condition is common in North America.

Clinical Features

- Pallor, jaundice, recurrent fever, pain abdomen, splenomegaly, hepatomegaly, chronic leg ulcer. Gallstones are seen in 60% of cases.

- Spontaneous remission is uncommon.
- Patients are more prone for several infections.
- *Acute haemolytic crisis* precipitated by infection and stress; with features of acute pain abdomen, fever, vomiting and anaemia. It often mimics other acute abdominal conditions.

Investigations

- *Fragility test:* Here increased fragility of the erythrocytes is the typical feature. Haemolysis occurs in 0.6% or in even stronger solutions.
- LFT-↑ serum bilirubin.
- Reticulocyte count is increased significantly (25% increased).
- Faecal urobilinogen is increased.
- Labelled radioactive chromium shows faster red cell destruction.
- U/S abdomen is done to look for gallstones, spleen, liver, CBD.
- Peripheral smear shows spherocytes, haematocrit.
- Direct Coomb's test—negative.
- Radioactive chromium 51 labelled patients' red cells shows rate of sequestration of red cells in spleen.

Problems with hereditary spherocytosis

- Haemolytic anaemia
- Haemolytic jaundice
- Pigmented CBD stones
- Cholangitis with Charcot's triad
- Gallstones (30%)
- Chronic leg ulcers



Fig. 13.9: Specimen of gall bladder and spleen (post surgical) in case of Hereditary spherocytosis.

Treatment

- Blood transfusion to improve the Hb status. Later splenectomy is done—Optimum age for splenectomy is 7 years.
- Accessory spleen should be removed.
- Splenectomy prevents early RBC destruction thereby controlling anaemia, jaundice and also prevents further formation of leg ulcers.
- Pneumococcal vaccine should be given to all these patients before elective splenectomy – 3 weeks prior to surgery; 3 weeks after surgery and later once in 5-6 years.
- If there are gallstones, cholecystectomy is done.
- Both splenectomy and cholecystectomy can be done through *laparoscopy*.
- Splenectomy for hereditary spherocytosis is not done before the age of 6 years.

Note:

- *Hereditary elliptocytosis* is an autosomal dominant condition where 90% of RBC's are elliptical. Mostly they are asymptomatic, if symptomatic splenectomy cures the condition.

IMMUNE HAEMOLYTIC ANAEMIA

Here Ig G or Ig M antibodies bind to erythrocyte antigens causing red cell destruction through complement and RE systems.

It can be –

- *Alloimmune haemolytic anaemia*: It occurs after exposure to allogenic erythrocytes during transfusion, pregnancy or transplantation.
- *Drug induced immune haemolytic anaemia*: It is drug induced antibody reaction for drugs like α methyl dopa, penicillins or 2nd generation cephalosporins. It occurs via new antigen formation with positive Coomb's test. Cessation of causative drug and steroid therapy will cure the disease.
- *Autoimmune haemolytic anaemia (AIHA)*: Here there is Development of Ig G and Ig M antibodies that bind to RBC's which are identified by Fc receptors of macrophages and RE cells causing phagocytosis and destruction of red cells.

  Two types of antibodies are—
  - *Common warm antibodies*: They react at 98.6°F. Often it is associated with CLL. In classical type, platelets are normal. Evan's syndrome is combination of AIHA and ITP. Coomb's test is positive (95% cases). Clinical features are of any haemolytic anaemias like palor, jaundice, splenomegaly

Autosplenectomy can occur in sickle cell anaemia.

(50%), and gall stones (25%). Long-term prednisolone is the treatment of choice. Failure to respond after long-term treatment is an indication for splenectomy. 80% of patients benefit with splenectomy.

- *Less common cold antibodies (Cold agglutinin syndrome)*: It is treated by avoiding exposure to cold; folic acid; chlorambucil; cyclophosphamide and plasmapheresis. Splenectomy is not beneficial in this condition.

THALASSAEMIA (Mediterranean anaemia/Cooley's anaemia/Erythroblastic target cell anaemia)

- It can be α, β and γ thalassaemia depending on defect in the synthesis of particular peptide.
- *Beta thalassaemia* is commonest. There is decrease in Hb – A and persistence of Hb – F. Homozygous, thalassaemia major is commonest type. Heterozygous, thalassaemia minor also can occur.
- Intracellular *Heinz bodies are typical*.
- Chronic anaemia, jaundice and splenomegaly are the features. Major type presents in first year of life with retarded growth, frontal bossing and prominent malar bones. Leg ulcers, recurrent infections, splenic infarction, pleural effusion, crisis, gall stones (25%) are other features.
- *Complications* are haemosiderosis, diabetes mellitus, pancreatitis, cirrhosis of liver, intractable sepsis and aplastic crisis.
- Haemoglobin electrophoresis, peripheral smear, LFT, bone marrow study and U/S abdomen are the investigations required.
- Regular blood transfusions, splenectomy are the treatment options.

SICKLE CELL DISEASE

- It is hereditary haemolytric anaemia seen commonly in blacks wherein Hb A is replaced by *Hb S* leading to formation of *crescent shaped* red cells which is deformed and more prone for trapping in spleen and destruction. Under low oxygen tension, Hb S undergoes crystallisation causing elongated and deformed red cells. It increases the blood viscosity and causes stasis in circulation. Splenic micro infarcts are common causing initial splenomegaly and later autosplenectomy and calcification.
- Because of autosplenectomy patient is more prone for infection by pneumococcus and other organisms due to reduced production of antibodies.
- Patients are commonly asymptomatic.
- It is common in Africa. Patients in India have high HbF which protects them from developing symptoms.
- Anaemia, pain abdomen, leg ulcers are the usual features.
- Cerebral, pulmonary and mesenteric infarctions can occur which may be often life threatening.
- Peripheral smear and electrophoresis are diagnostic. U/S abdomen is needed to see spleen and for gall stones.
- *Treatment* is sodium cyanate (prevents sickling of Hb S); hydration; partial exchange transfusion, antibiotics, symptomatic therapy by folic acid. Splenectomy has only limited role in initial sequestration stage.

IDIOPATHIC THROMBOCYTOPENIC PURPURA (ITP)

It is development of *antiplatelet antibodies*, (IgG) which damage patient's own platelets. These platelets get sequestered earlier and faster in the spleen than normal causing thrombocytopenia. Spleen is the source of antiplatelet antibody production and destruction of formed platelet – antiplatelet antibody complex (by macrophage phagocytosis).

Types

1. Acute ITP:
   - Initiated after viral infection.
   - Common in children (90%).
   - Spontaneous remission is common.
2. Chronic ITP:
   - Common in adults (90%).
   - Gradual, may be present for years.

Clinical features

- Common in young women (3:1 ratio)
- Purpuric patches in skin and mucous membrane (most common presenting sign)
- Epistaxis
- Menorrhagia
- Haematuria, haemarthrosis (rare)
- GIT bleeding
- Intracranial haemorrhage - 2%; dangerous
- Tourniquet test is *positive* (*Hess test*)

- Purpuric and petechial patches are common in buttocks and limbs as these areas are more dependent having more vascular pressure. These patches and petechiae are mild or moderate.
- Splenomegaly is present in 25% of cases.
- After applying sphygmomanometer cuff and inflation, cubital fossa is observed for petechial haemorrhagic spots. More than 20 numbered petechial spots in 3 cm circled area are significant – Hess Test.

Differential Diagnosis

- Other causes for purpura.
- Increased capillary fragility.
- Bone marrow suppression due to aplastic anaemia.
- Chemotherapy.
- DIC.
- Autoimmune diseases.



Figs 13.10A and B: Purpura legs in case of ITP.

Investigations

- Bleeding time is increased.
- Clotting and prothrombin time are normal.
- Platelet count is decreased.
- Bone marrow biopsy reveals increased megakaryocytes.
- Usually anaemia and neutropenia is not observed.
- U/S shows splenomegaly only in 25% cases.

Note: *Positive Hess test is formation of > 20 purpuric patches in an area of 3 cm diameter.*

Treatment

Drugs

- In children, spontaneous regression occurs in 75% of cases after one attack.
- Short courses of *steroids* or *azathioprine* hastens the recovery.
- In adults, treatment is indicated when platelet count is < 30000/mm^3.
- Glucocorticoid—1 mg/kg is given. Response to treatment is seen within a week. Prednisolone 10 mg/day for 6 weeks is given.
- Danazol 200 mg TID decreases IgG receptor on phagocytes causing lesser degradation of platelets.
- Vincristine 2 mg per week for 6 weeks.
- IV immunoglobulin 0.4-1.0g/kg × 5 days (action like danazol)
- Anti-Rh D antibodies.

Indications for splenectomy:

1. Relapsed severe cases after treatment with steroids - for 6 weeks
2. Girls attaining menarche
3. ITP persisting even after 6-9 months refractory to treatment
4. In 2nd trimester pregnancy, with platelet count <10000/mm^3 and severe bleeding problems
5. Recurrence after stopping/tapering steroids
6. Profound GI bleed and intracranial bleed

Surgery

- *During surgery and in emergency,* fresh blood transfusions or platelet transfusions are required. Sometimes anti-platelet immune response is temporarily blocked by Ig G transfusion so to allow the platelet count to rise at the time of surgery or in cases of severe bleeding or in pregnancy.
- Accessory spleen should be identified and removed.
- In 7 days platelet count raises to more than 100000/cu mm.
- Laparoscopic approach is ideal in elective splenectomy for ITP.

Treatment for ITP

- Methylprednisolone IV for 3-5 days only
- Oral prednisolone tablets—drug of choice for 6-12 weeks
- IV immunoglobulin 0.4-1.0 g/kg/day for 5 days only. It competes with antibodies

For every minute you are angry you lose sixty seconds of happiness.

- Vincristine 2 mg/week for 6 weeks
- Danazol 200 mg tid
- Anti-Rh D antibodies
- Azathioprine
- Splenectomy
- FFP, platelet concentrate, fresh blood transfusions.

THROMBOTIC THROMBOCYTOPENIC PURPURA (TTP)

It is an idiopathic disease associated with bone marrow transplantation, drugs like penicillin, mitomycin, cyclosporine.

Main features are (*pentad*)-

1. Microangiopathy haemolytic anaemia.
2. Thrombocytopenia.
3. Fever.
4. Neurological disturbances.
5. Renal dysfunction.

Features and management

- Here only arterioles and capillaries of microcirculation are involved. Venules are not involved. Platelet micro thrombi, endothelial proliferation are the pathological features.
- Anaemia, platelet trapping in the spleen and thrombocytopenia are typical.
- Altered mental status, neurological deficits and renal failure are common.
- Plasmapheresis improves the survival which is the main treatment.
- Laparoscopic splenectomy is done only to reserved patients.

FELTY'S SYNDROME is chronic rheumatoid arthritis, mild leukopenia and splenomegaly.

SPLENECTOMY

Indications for Splenectomy

1. Trauma.
2. In radical gastrectomy—removed *"en bloc"* with stomach.
3. Staging laparotomy in case of Hodgkin's lymphoma.
4. Hereditary spherocytosis and other haemolytic anaemias.
5. Idiopathic thrombocytopenic purpura (ITP).
6. Portal hypertension with variceal bleeding.
7. Tuberculosis of spleen.
8. Others:
    - Gaucher's disease.
    - Chronic myeloid leukaemia.
    - Felty's syndrome.
    - Carcinoma of tail of the pancreas during distal pancreatectomy.
    - Schistosomiasis.
    - Splenic artery aneurysm.
    - Splenic infarction.
    - Cystic disease of spleen.
    - Splenic tumours.

Procedure

- Incision—left paramedian or left subcostal or in case of large adherent spleen left thoraco-abdominal approach.
- Lieno-renal ligament and short gastric vessels are ligated. Splenic vessels are ligated at the hilum of spleen. Spleen is removed. Abdomen is closed after placing a drain *in situ*.
- *Presently laparoscopic splenectomy is becoming popular.*
- Preoperative splenic artery embolisation is beneficial in massive spleens.

Complications of Splenectomy

- Haemorrhage - mainly from short gastric vessels. Re-exploration and control of bleeding is needed.
- Gastric dilatation.
- Haematemesis due to mucosal congestion following ligation of short gastric vessels.

INDICATIONS FOR SPLENECTOMY

Benefit is maximum/very good	*Benefit is equivocal*	*Benefit may be there/low*
• Splenic injury • Hereditary spherocytosis • ITP • Splenic cysts • Splenic tumours • Hypersplenism • Segmental left sided portal hypertension	• AIHA (autoimmune haemolytic anaemia) • Tropical splenomegaly • Felty's syndrome	• Thalassaemia • CML • Gaucher's disease • Hodgkin's lymphoma for staging laparotomy • Sickle cell anaemia

- Left sided pleural effusion and left basal atelectasis (left lobe atelectasis is the commonest complication) (30%).
- Left subphrenic abscess.
- Pancreatitis following damage to tail of the pancreas and pancreatic fistula (3%).
- Haematologic changes: Rise in WBC and platelet count, rise in abnormal RBC's and RBC bodies.
- Gastric fistulas.
- Left sided colonic injury.
- Infection—Postsplenectomy septicaemia, OPSI-most dangerous.
- Portal vein thrombosis can occur.

OVERWHELMING POSTSPLENECTOMY INFECTION (OPSI)

- As there is reduced IgM, tuftin, properdin and other antibodies, phagocytosis of encapsulated bacteria is defective. So the postsplenectomised patient is more prone for *Pneumococcal septicaemia*, (commonest), *N. meningitides, H. influenzae, Babesia microti* infections. Risk is more in patients on chemotherapy, radiotherapy and haemolytic diseases.
- Incidence is 4%.
- Common in first two years after splenectomy. But it can occur any time. Risk persists for lifetime.

Clinical Features

- Prodromal phase—fever, chills, sore throat.
- Hypotension, shock.
- DIC.
- Respiratory distress, coma, death.

Mortality for fully developed OPSI—50-70%

Prevention

- *Pneumococcal vaccine* should be given to all splenectomised patients. Polyvalent pneumo-vac is given 3 weeks prior to surgery and it is repeated once in 6 years. (Given to patients older than 2 years).
- Other vaccines advised are meningococcal vaccine (only to those who travel with high risk), *H. influenza* 'B' vaccine (to all whatever the age).
- In malaria endemic areas, antimalarial prophylaxis is given for patients after splenectomy.

Treatment of OPSI

- Antibiotics like Cefoperazone, Ceftazidime, Amikacin
- Ventilatory support - ICU care
- Blood transfusion
- Immunoglobulin transfusion
- Nutrition (TPN) and maintaining of urine output

Prevention of OPSI

- Life long prophylaxis using benzathine penicillin 12-24 lac units
- Pneumococcal vaccine given 3 weeks prior to splenectomy - 70% protection
- *H. influenza* B type vaccine
- Meningococcal vaccine is given only to high-risk groups, as its effects are short term. So it is not routinely given
- *Note: Protection by vaccine is not completely guaranteed*

SPLENIC ARTERY ANEURYSM

- Most common intraabdominal site for aneurysm after abdominal aorta.
- Most common in women, due to atherosclerosis.
- Congenital splenic artery aneurysm can occur.
- Splenic artery pseudoaneurysm (10%) can occur after an attack of acute pancreatitis which may cause life threatening rupture.
- Rupture of splenic artery may be intraperitoneal or into the stomach, colon and intestine. Calcified aneurysm rarely ruptures.
- Plain X-ray shows calcified lesion in 70% of cases.
- Contrast CT, angiogram are needed.
- Indication for surgery:
  1. >2 cm diameter.
  2. Symptomatic aneurysm.
  3. Anticipating pregnancy.
  4. Aneurysm identified during pregnancy should be operated before 3rd trimester.

Treatment

- Splenectomy with ligation of artery proximal to aneurysm.
- Splenic artery embolisation under radiological guidance is also beneficial.

Efforts and energies should be consistent, constructive and compassionate.

SPLENIC ABSCESS

- It is uncommon but potentially fatal.
- Incidence is 0.7%.
- **Precipitating factors**.
  - Endocarditis is commonest focus.
  - AIDS.
  - Polycythaemia.
  - Malignancy.
  - Sickle cell disease.
  - Splenic vein thrombosis.
  - Trauma.
  - Drug abuse.
  - Typhoid, osteomyelitis, puerperal sepsis, pancreatitis, otitis media.

Organisms responsible: *Staphylococcus*, *Streptococcus*, *Enterobacter*, *E Coli*, *proteus*, *Klebsiella*, *Candida albicans*, *Mycobacterium tuberculosis* in developing countries.

Clinical features

- Fever
- Pain in left hypochondrium
- Pain in left side of chest
- Left sided pleural effusion
- Spleen when palpable is tender
- Single or multiple abscesses
- Need not move with respiration



Fig. 13.11: Splenic abscess due to tuberculosis.

Investigation

Ultrasound, ESR, chest X-ray, CT scan, blood culture.

Treatment

- High dose antibiotics has to be started.
- ATT in case of tuberculosis.



Fig. 13.12: CT scan showing abscess in the spleen.

- Ultrasound/CT scan guided aspiration of abscess is done.
- Splenectomy.

Note: Splenic abscess can rupture causing peritonitis and left subphrenic abscess.

HYPERSPLENISM

It is overactivity of spleen causing pancytopenia with more of hypercellular bone marrow.

Causes

- Primary hypersplenism.
- Portal hypertension.
- Malaria, Kala azar.
- Schistosomiasis.
- Tuberculosis.
- Myeloproliferative disorders.

Hypersplenism often requires splenectomy.

Note:

- Commonest primary splenic neoplasm is haemangioma
- *Littoral cell angioma* is rare splenic tumour
- Lymphangioma, inflammatory pseudotumours are rare splenic tumours
- Hodgkin's lymphoma commonly involves spleen
- Secondaries in spleen are rare. Occasionally spread can occur from lungs, stomach, pancreas, breast, melanoma
- Primary malignant splenic tumours are exceedingly rare. Angiosarcoma is the most common primary tumour

- *Splenic cysts can be non-parasitic* (simple congenital cysts, epidermoid cysts (75% of non parasitic cysts)); *parasitic* (hydatid)and *pseudocyst / secondary cysts* due to malaria, tuberculosis, infectious mononucleosis, old parenchymal haematoma and syphilis. 80% of splenic cysts are pseudocysts

Self-assessment Questions

- Indications for splenectomy.
- Splenorrhaphy.
- Complications of splenectomy.
- Splenic injury.
- Ballance's sign.
- Causes for splenomegaly.
- OPSI.
- Clinical features, and management of splenic injury.
- Splenunculi.
- Hereditary spherocytosis.
- Idiopathic thrombocytopenic purpura.
- Kehr's sign.

If you don't know where you're going, you may miss it when you get there.

14

Pancreas

Anatomy
Serum amylase
MRCP
Pancreatitis: *Acute pancreatitis, Pseudocyst of pancreas, Chronic pancreatitis.*
Pancreatic tumours: *Exocrine pancreatic tumours, Endocrine pancreatic tumours (Insulinomas, gastrinomas, glucagonomas, Zollinger-Ellison's syndrome).*
Cystic fibrosis
Annular pancreas
Ectopic pancreatic tissue
Pancreatic divisum
Pancreatic calculus
Pancreatic ascites
Pancreatic fistulae
Pancreatic abscess
Pancreatic necrosis
Pancreatic trauma
Cystic lesions of pancreas
Exocrine pancreatic disease

Pancreas is also called as *abdominal tiger.*

ANATOMY

Pancreas is an elongated retroperitoneal organ; 15-20 cm in length; lies against L_1–L_2 vertebra. It lies posterior to stomach, separated by lesser sac.

Parts

It is divided into head, neck, body, tail.

- The head lies in the concavity of duodenum and tail reaches the hilum of the spleen.
- The posterior surface of the neck of pancreas is related to terminal part of superior mesenteric vein and beginning of portal vein.

Ducts of Pancreas

1. Main duct of pancreas (*Duct of Wirsung*): It begins in the tail of pancreas and runs on the posterior surface of the body and head of pancreas, receives numerous tributaries at right angle along its length (*'Herring bone pattern'*).

   It joins the bile duct in the wall of the second part of duodenum to form hepatopancreatic ampulla *(of Vater)* and opens on the summit of major duodenal papilla (8-10 cm from pylorus).
2. Accessory pancreatic duct *(Duct of Santorini):* It begins in the lower part of the head and opens into the duodenum at minor duodenal papilla (6-8 cm from the pylorus).


Duct of Santorini
Minor papilla
CBD
Duct of wirsung
Major duodenal papilla

Fig. 14.1: Ducts of pancreas.


Hepatic artery
Coeliac artery
Splenic artery
Gastro-duodenal artery
Superior pancreatico-duodenal artery
Superior mesenteric artery
Arteria pancreatica magna
Inferior pancreaticoduodenal artery

Fig. 14.2: Arterial supply of pancreas.

Blood Supply of Pancreas

1. Pancreatic branches of splenic artery
2. Superior pancreaticoduodenal artery
3. Inferior pancreaticoduodenal artery.
   Venous drainage is into portal vein.


Sup. pancreatico-duodenal vein
Portal vein
Splenic vein
Inf. mes. vein
Inf. pancreatico-duodenal vein
Sup. mes. vein

Fig. 14.3: Venous drainage of pancreas.

Nerve Supply

Parasympathetic supply is from vagus and sympathetic innervation is from splanchnic nerves.

Functions

- *Exocrine* part secretes pancreatic juice which helps in digestion of proteins, carbohydrates and fats.
- *Endocrine* part constitutes islets of pancreas which is distributed more numerous in tail of pancreas.
  β cells of islets secrete insulin.
  α cells secrete glucagon.

SERUM AMYLASE

- Normal value is up to 200-250 Somogyi units.
- It increases more than 1000 units or a rising titre is very significant in acute pancreatitis.
- Its half life is 24 hours.
- It is not very sensitive because it also increases in other conditions:
  - Salivary gland diseases.
  - Mesenteric ischaemia.
  - Ruptured aortic aneurysm.
  - Intestinal obstruction.
  - Ectopic gestation.
  - Salpingitis.
  - Perforated duodenal ulcer.

Types

- ***Amylase isoenzyme-P*** is specifically increased in pancreatitis.
- In other conditions, ***Amylase-S*** is commonly increased.
- It can be analysed with other proteolytic enzymes like lipase, elastase which are more relevant.
- In peritoneal tap, if amylase level of peritoneal fluid is more than serum amylase it is significant.

Note: Amylase level in pseudocyst fluid is very high.

MAGNETIC RESONANCE CHOLANGIO PANCREATOGRAPHY (MRCP)

It is a non-invasive diagnostic method using magnetic field and energy as resonance.

T_1 weighted images are used for pancreas.

T_2 weighted images are used for biliary tree.

Both images are used to see invasion and adjacent structures.

Advantages

- It is non-invasive.
- It gives equal or better imaging than ERCP.
- Pancreatic divisum or annular pancreas are identified easily by MRCP.
- Ductal dilatation in chronic pancreatitis and visualization of duct beyond stricture is possible.
- Islet tumours are better visualized and diagnosed by MRCP.

Disadvantages

- Availability.
- It is only diagnostic. Not therapeutic (ERCP is both diagnostic as well as therapeutic).
- Costly.

PANCREATITIS

> ***We learn that pain was an early symptom in nearly one-half of the cases; that it was usually severe, and might be intense, and was to be found in the abdomen or lower chest…. The appearances found after death are conspicuously the hemorrhage within and near the pancreas…. It is evident that all treatment, at the onset, can be nothing but palliative.***
>
> —**Reginald Heber Fitz,** 1889

Surgery is a painful procedure to relieve the pain.

Classification

I. *Marseilles' classification*:
  1. Acute pancreatitis.
  2. Acute relapsing pancreatitis.
  3. Chronic relapsing pancreatitis.
  4. Chronic pancreatitis.

Acute means acute inflammatory changes which are reversible.

Chronic means chronic continuous inflammatory changes which are morphologically irreversible.

II. *Trapnell's aetiological classification*:

Major causes

- Biliary tract disease 50% – stones – common cause
- Alcoholism 25%

Other causes

- Trauma
- After biliary, gastric, splenic surgery, ERCP
- Hyperparathyroidism
- Hypercalcaemia, hyperlipidaemia
- Diabetes
- Porphyria
- Drugs: Steroids, INH, diuretics (thiazides), septran, azathioprine – 5%
- Viral infections (mumps, coxsackie)
- Autoimmune diseases
- Vascular diseases
- Idiopathic
- Scorpion venom
- Biliary ascariasis
- Mycoplasma pneumoniae
- Infectious mononucleosis
- Pancreatic divisum

ACUTE PANCREATITIS

Pathogenesis

Alcohol causes direct toxicity, hypersecretion of gastric and pancreatic juices, reflux, plugging of pancreatic proteins, injury by release of free radicals like superoxide and hydroxyl, spasm of sphincter of Oddi and stimulates trypsinogen.

All these etiological factors

↓

Either cause spasm of sphincter of Oddi and lead to reflux of bile into pancreatic duct and into the pancreatic parenchyma OR
Causes increased secretion of pancreatic enzymes or directly acts as toxins to pancreas.

↓

Trypsinogen gets activated forming trypsin which activates other enzymes.



Figs 14.4A and B: Features of acute pancreatitis with necrosis in the omentum and over pancreas; with haemorrhage.

↓ ↓

Proelastase to elastase — *Prolipase to lipase*

↓ ↓

Causes capillary rupture — Metabolises triglycerides to glycerol + fatty acids and fatty acids combine with calcium forming saponified fat.

↓ ↓

Sequestered fluid, saponified fat, blood, toxins all together forms a ***chicken broth fluid.***

↓

Lecithinase and amylase and factors like lysolecithinase, prostaglandins, bradykinins, kallikrein, myocardial depressant factor, free radicals, cytokins, tumour necrosis factor, and platelet activation factor are also released to have local and systemic effects.

↓

Infection occurs causing bacteraemia, septicaemia.

↓

Large volume of fluid sequestration causes *hypovolaemic shock.*

- Toxins released may lead to *acute tubular necrosis and so acute renal failure.*
- Left sided diaphragm gets elevated and *left sided pleural effusion* occurs.
- Lecithinase reduces the surfactant in the alveoli of lung, and infection leads to pulmonary insufficiency, *ARDS and respiratory failure.*
- Because calcium is utilized for saponification, *hypocalcaemia* sets in.
- Diffuse oozing in pancreatic bed occurs which utilizes platelets and causes *disseminated intravascular coagulation (DIC).*
- In severe cases, extensive necrosis with haemorrhage occurs causing *acute haemorrhagic necrotising pancreatitis (Fulminant pancreatitis), which has got a high mortality.*
- Here enzymes seep across the retroperitoneum causing haemorrhagic spots and ecchymosis in the flanks ***(Grey Turner's sign)***, or through falciform ligament causing discolouration around the umbilicus ***(Cullen's sign)***, umbilical black eye or below the inguinal ligament ***(Fox sign).***
- SIRS and later MODS set in.
- *Sequence of events -*

Acute oedematous pancreatitis →→→→→→Severe acute pancreatitis → Acute sterile necrosis → Acute infected necrosis

↓ ↓ ↓ ↓

Resolution/recovery /complications (rare) Less mortality

Local or systemic complications with high mortality. (pseudocyst/abscess/ ARDS/MODS/haemorrhage etc.)

- **Moynihan described acute pancreatitis as** "*The most terrible of all the calamities that occur in connection with abdominal viscera*".



Fig. 14.5: Grey turner's sign in a patient with acute pancreatitis.

ATLANTA CLASSIFICATION
1. Acute oedematous pancreatitis (80%): Milder form, mortality is <1%
2. Acute necrotising pancreatitis (20%): Characterized by pancreatic and peripancreatic necrosis. Mortality is ≈ 15% - 30%

Present Classification of Acute Pancreatitis

- *Interstitial acute pancreatitis* with mortality less than 1%.
- *Necrotizing pancreatitis.*
  - Sterile necrosis with mortality 10%.
  - Infected necrosis with mortality 30-40%. It is confirmed by CT guided aspiration and Gram's stain. When confirmed, needs pancreatic necrosectomy.

Note: In *Ulm classification* pancreatic abscess and pseudocysts are also included.

Organisms Involved

Infection is commonly polymicrobial (60%). It may be from gall bladder, colon or small bowel via transmural migration or by haematogenous spread. Infection rate in one week is 24% and in 3 weeks it is 70%.

- E. coli (35%).
- Klebsiella (25%).
- Enterococcus (25%).
- Others – staphylococci, pseudomonas, proteus, enterobacter, anaerobes, candida (10%).

Clinical Features

- Sudden onset of upper abdominal pain which is referred to back. Pain is severe, agonizing and refractory. Pain may be relieved or reduced by leaning forward.
- Vomiting and high fever, tachypnoea with cyanosis.
- Tenderness, rebound tenderness, guarding, rigidity and abdominal distension, severe illness.
- Often mild jaundice (due to cholangitis).
- Features of shock and dehydration.
- Oliguria, hypoxia and acidosis.
- Grey turner's sign, Cullen's sign, Fox sign.
- Haematemesis/malaena due to duodenal necrosis, gastric erosions, decreased coagulability/DIC.
- Hiccough when present is refractory.
- Ascites may be present. Paralytic ileus is common.
- Pleural effusion (20%), pulmonary oedema, consolidation, features of rapid onset ARDS is often observed.

Working together is essential for success; even freckles would make a nice tan if they would get together.

- Neurological derangements due to toxaemia, fat embolism, hypoxia, respiratory distress can occur. It may be mild psychosis to coma.
- Occasionally haematemesis or melaena can occur.

Clinical features are classified as

- Mild attack
- Severe attack
- Fulminant attack

Differential diagnosis

- Perforated duodenal ulcer
- Cholecystitis
- Mesenteric ischaemia
- Ruptured aortic aneurysm
- Ectopic pregnancy
- Salpingitis
- Intestinal obstruction
- Diabetic ketoacidosis

Investigations

- *Serum amylase* is very high (>1000 Somogyi units) or shows rising titre.
- *Amylase creatinine clearance* ratio is increased. It is - urine amylase/serum amylase X serum creatinine/ urinary creatinine X 100. Normal value is 1-4%. More than 6% signifies acute pancreatitis.
- *Serum lipase* more specific than amylase.
- *Serum lactescence* (related to triglyceride metabolism)—Most specific.
- Serum trypsin is the most accurate indicator but it is not commonly used.
- Trypsinogen activation polypeptide (TAP) assay in serum and urine reveals the severity of the acute pancreatitis. CRP (>150 mg/L) is also useful. Phospholipase A2, LDH levels are also often assessed.
- Liver function tests: Serum bilirubin, albumin, prothrombin time, alkaline phosphatase.
- Blood urea, serum creatinine.
- Blood glucose (hyperglycaemia is seen).
- Serum calcium level, (hypocalcaemia occurs).
- Arterial PO_2 and PCO_2 level to assess pulmonary insufficiency (or ARDS).
- Urinary lipase estimation.
- Total count, haematocrit, platelet count, coagulation profile.
- Peritoneal tap fluid shows *high amylase* and protein level (very useful method). Lipase level in ascitic fluid is also useful.
- Plain X-ray shows
  1. *'Sentinel loop'* of dilated proximal small bowel.
  2. Distension of transverse colon with collapse of descending colon (*colon cut off sign).*
  3. Air-fluid level in the duodenum.
  4. Renal halo sign.
  5. Obliteration of psoas shadow.
  6. Localized ground glass appearance.
- U/S abdomen.
- *Spiral CT is* better - gold standard. To look for oedema, altered fat and fascial planes, fluid collections, necrosis (non enhancement area > 30% or 3 cm), bowel distension, mesenteric oedema and haemorrhage. CT guided aspiration (fluid should be sent for Gram's stain and bacterial culture); pigtail catheter insertion can also be done. If fluid culture shows bacterial growth with CT showing necrosis, it means it is infected necrosis and needs early pancreatic necrosectomy. CT guided aspiration and Gram's staining may need to be repeated.
- MRI, MRCP.
- ERCP is usually not done in acute phase.
- Chest X-ray for effusion and ARDS.

Balthazar CT Scoring System

CT grade—

- A—Normal pancreas—0
- B—Oedematous pancreatitis—1
- C—B+ mild extra pancreatic changes—2
- Severe extra pancreatic changes with one fluid collection—3
- Extensive/multiple extra pancreatic collections—4

Necrosis score—

- None—0
- < 1/3rd—2
- More than 1/3rd less than half—4
- More than half—6

CT severity index— CT grade + necrosis score
0—3, 4—6, 7—10.

Treatment

Treatment of acute pancreatitis

- Conservative, 70-90%
- Surgical treatment when indicated, 10-30%
- Management of complications like acute pseudocyst, abscess, fistula, haemorrhage; systemic complications like ARDS, renal failure, MODS



Fig. 14.6: CT picture showing features of acute pancreatitis.

Mainly conservative treatment

1) (P) : **P**ain relief [pethidine, meperidine (no morphine)]
Protease inhibitors (aprotinin, antisnake venom, EACA etc.), **P**lasma
2) (A) : **A**ntibiotics (ceftazidime, cefoperazone, cefotaxime) imipenum
Anticholinergics (to reduce sphincter pressure)
3) (N) : **N**asogastric aspiration, **N**asal O_2
Nutritional support (TPN)
4) (C) : **C**alcium gluconate 10 ml 10% 8th hourly
Calcitonin
CVP line
5) (R) : **R**edydration by IV fluids, plasma, blood
Ranitidine IV 50 mg 8th hourly
Respiratory support (ventilator)
Resuscitation when required
6) (E) : **E**ndotracheal intubation
Electrolyte management
7) (A) : **A**ntacids
8) (S) : **S**wan-Ganz catheter for CVP and TPN
Somatostatin and its analogue (*Octreotide*)

Mainly conservative

- Rehydration is essential as there is lot of fluid sequestration and 3rd space fluid loss. It is done by using ringer lactate, normal saline, dextrose saline, plasma and fresh blood transfusion.
- Pain relief by pethidine and other analgesics.
- In severe haemorrhagic episodes, fresh frozen plasma and platelet concentrate may be required in anticipation of DIC and haemorrhage.
- Nasogastric aspiration, urinary catheterization to maintain and monitor urine output 50 ml hourly.
- Antibiotics like third generation cephalosporins, imipenem, meropenem, cefuroxime are used even though its role is not clear but it is commonly used to reduce the anticipated sepsis.
- Calcium gluconate 10 ml 10% IV 8th hourly is given as patient will be hypocalcaemic.
- CVP line is essential to monitor, for rapid fluid therapy and for Total Parenteral Nutrition (TPN) using carbohydrate, aminoacids, vitamins, essential elements.
- IV Ranitidine 50 mg 6th hourly or IV omeprazole 40 mg BD or IV pantoprazole 80 mg BD to prevent stress ulcers and erosive bleeding.
- Proper electrolyte management with monitoring is needed.
- It is always better to manage the patient in an ***intensive care*** set up so that when needed endotracheal intubation, ventilatory support, tracheostomy can be done as an emergency basis.
- In case of renal failure haemodialysis is required.
- Somatostatin/octreotide is often used to reduce pancreatic secretion.
- Anticholinergics, protease inhibitors and calcitonin are other agents used. Their efficacy is not sure.
- Steroid injection in initial phase of shock is beneficial. It is also useful in respiratory distress and ARDS.
- Nebulisation, bronchodilators are also tried.
- During recovery period nasogastric feeding or jejunostomy feeding can be undertaken. *Nasojejunal tube placement and feeding* should be started as early as possible once ileus subsides so that it reduces the infection rate by transmucosal migration of bacteria and it also improves nutritional status.
- Repeated calcium estimation, U/S examination to see the response is useful.
- Dopamine or low molecular weight dextran (to improve renal perfusion), somatostatin/octreotide (to reduce pancreatic secretion) are also often used.

Other measures:

Continuous monitoring, observation, maintaining good urine output 30 ml/hr. The required investigations are repeated to find out the response to treatment like serum calcium, total count, blood urea, creatinine, PaO2, haematocrit, ECG.

> *Each case has its lesson—a lesson that may be, but is not always, learnt for clinical wisdom is not the equivalent of experience.*
> —William Osler

Uses of octreotide

- Acute pancreatitis
- Variceal bleeding
- Endocrine pancreatic tumours
- GI fistulas, pancreatic fistulas
- Dumping syndrome
- Carcinoid tumour, acromegaly
- Pancreatic surgeries

Dose:
50 μg as loading dose IV
50 μg 1 hour in 5% dextrose as maintenance dose.

Surgery

Indications for Surgical Intervention (10% cases)

1. If condition of patient deteriorates in spite of good conservative treatment.
2. If there is formation of pancreatic abscess, or infected necrosis.
3. When diagnosis is in doubt.
4. In severe necrotising pancreatitis as a trial to save the life of the patient which has got very high mortality.

Surgical Management of Acute Pancreatitis

Surgery removes intra and extra pancreatic necrotic materials, pancreatic fluid, and toxins. It permits preservation of viable pancreatic tissue. *Open surgery is the gold standard for infected pancreatic necrosis.*

- After opening the abdomen, all necrotic tissue, pus, infected fluid and toxins are removed. 10-12 litres of normal saline wash is given. Drainage tubes are placed liberally. Abdomen is closed in layers - *Conventional closed method* (necrosectomy, wide debridement, adequate drainage, closure). Re-laparotomy is done only on demand later.
- Laparotomy – necrosectomy – wide debridement – wash – wide packing. Wound is left open. Repeated wash and packings are done until healthy granulation develops – *open method*.
- Laparotomy – necrosectomy and closure with drain and re-laparotomy later—*semi-open* method.
- *Zip technique* can be used to give repeated wash to remove toxins and necrotic tissues until healthy granulation tissue develops in the pancreatic bed – *Bradley's repeated laparotomies and wash.*
- Continuous closed peritoneal lavage of the pancreatic bed and lesser sac is done with 10-12 litres of normal saline or hyperosmolar, potassium free dialysate fluid 2 litres/hour using multiple tubes to remove toxic material in the peritoneal cavity/retroperitoneal area until return fluid becomes clear - *Beger's lavage*. Procedure is done after initial surgical debridement.
- Extra peritoneal lavage through bilateral flank incisions is also used. But being a blind procedure it is technically difficult and one may not be sure about the adequacy of the procedure.
- Under laparoscopic visualisation, necrosectomy, wash and drainage can be done. But often it is difficult to create pneumo-peritoneum in acutely ill patient. But it is increasingly becoming popular.
- A jejunostomy is often done along with these procedures to have early enteral nutrition.
- *Further management* is important to prevent recurrence. Gall stones should be dealt by laparoscopic cholecystectomy in 2 weeks after acute attack. Endoscopic sphincterotomy (ERCP) and often stenting may be needed if there are CBD stones.

Note: GI fistula either enteric or pancreatic and incisional hernia are the late complications of these surgeries.

Complications of acute pancreatitis

- Shock-hypovolaemic and septic
- Respiratory failure and ARDS—Common in 7 days
- Septicaemia—Common after 7 days
- Hypocalcaemia
- Disseminated intravascular coagulation (DIC)
- Acute renal failure
- Pancreatic pleural—effusion (left sided 20%)
- Pancreatic pseudo aneurysm
- Pancreatic ascites
- Colonic stricture
- Pseudocyst of pancreas
- Chronic pancreatitis
- Splenic vein thrombosis
- Pancreatic abscess

- *Acute fluid collection* is collection of fluid in or near the pancreas during an attack of acute pancreatitis with an ill-defined or lacking fibrin wall or granulation tissue.
- *Acute pseudocyst* is collection of fluid with pancreatic juice in or near the pancreas localised by fibrin wall or granulation tissue. Fluid can be removed percutaneously under guidance or through an endoscope.
- *Pancreatic necrosis* is focal/diffuse area of non viable pancreatic parenchyma with peripancreatic fat



Figs 14.7A and B: On table photos of acute pancreatitis. Note the typical saponification in the omentum and mesentery.

necrosis. It is initially sterile but eventually gets infected.

- *Pancreatic abscess* is collection of pus in lesser sac (intraabdominal) in relation to pancreatic surface which contains mainly pus with only less or no necrotic pancreas. It may slough off the pancreatic/ splenic vessel wall to cause torrential haemorrhage. Abscess may be single or multiple (60%). It is commonly in head/body or tail. But often entire gland may be involved (25%). Abscess may rupture into viscera or extend into other part of the abdomen. Features of sepsis, tender palpable mass in the epigastrium with leukocytosis are observed. It is treated by antibiotics, percutaneous U/S or CT guided aspiration or drainage or open drainage.
- *Respiratory complications* are often severe and life threatening. It is due to distension of abdomen, diaphragmatic elevation, pleural effusion, reduced surfactant (lecithin) activity in alveoli due to lecithinase, severe pain, pleural effusion (left), intravascular coagulation in lungs and ARDS. Arterial blood gas analysis should be done. Often it needs ventilator support.
- *Pancreatic pseudoaneurysm* is due to enzymatic digestion (elastase) of the wall and weakening and aneurysmal dilatation of the splenic (50%) or gastroduodenal vessels (15%) or inferior and superior pancreaticoduodenal arteries (10%). It may rupture and cause life threatening haemorrhage or may rupture into stomach or duodenum to cause massive upper GI bleed or may rupture into pancreatic duct causing *haemosuccus pancreatitis*. It is diagnosed by CT angiogram. It is treated by critical care, blood transfusion, emergency angiographic embolisation or by open surgery and ligation of the involved vessel. It carries high mortality.
- *Pancreatic fistula* can occur due to ductal wall disruption and necrosis or after surgical intervention for acute pancreatitis (necrosectomy). It may be internal into bowel or external to skin. Fistula may be low (< 200 ml) or high (> 200 ml) out put. It can be straight or curved. It is confirmed by biochemical analysis, ERCP, CT fistulogram. If fistula persists for



Fig. 14.8: Beger's lavage to pancreatic bed. Tubes are placed post operatively. Continuous saline irrigation through the tube is done until irrigation fluid becomes clear.

> *In case of chronic pancreatitis jaundice supervenes in only fifteen percent of cases, but diabetes is present on thirty percent.*
> — Richard B Cattell

6 months then sphincterotomy, resection of fistula with pancreatic resection, pancreaticojejunostomy is done.

- *Emphysematous pancreatitis* with gas in pancreatic parenchyma is dangerous type and can be diagnosed by CT scan.

Ranson's prognostic criteria

On admission:

- Old age >55 years
- Blood sugar >200 mg%
- TC >16,000/mm^3
- Serum LDH > 350 IU/L
- Serum SGOT > 250 IU/L

In 48 hrs:

- Base deficit > 4 mEq/L
- Serum calcium < 8 mEq/L
- Haematocrit : altered by 10%
- Arterial O_2 (PO_2) < 60 mm Hg
- Extravascular space fluid loss: > 6 L
- Blood urea (BUN) altered > 5 mg% of the normal

Total score is 11

Scores up to 5 — better prognosis
5-7 — equivocal—but dangerous
>7 — is highly dangerous

Glasgow criteria

- Age > 55 years
- PO_2 < 8 KPa
- Total count >15000 cells/mm^3
- Serum calcium < 2 mmoles/L
- Blood urea > 16 mmol/L
- Blood glucose > 10 mmols/L (200 mg%, no H/O diabetes)
- SGPT > 200 IU/L
- LDH > 600 U/L
- Serum albumin < 3.2 gm/dl

Note:

- Decrease serum calcium level is *worst prognostic indicator* of pancreatitis.
- These scoring systems differ for non gall stone pancreatitis and gall stone pancreatitis.
- Other scoring systems which are often used are APACHE II (Acute Physiology And Chronic Health Evaluation II) and SAP (simplified acute physiology) scoring systems. Twelve variables are used to assess in APACHE II scoring.

Criteria to find out Systemic Failure in Acute Pancreatitis

- *Cardiac* – hypotension; pulse > 130/minute; arrhythmias, ECG changes.
- *Pulmonary* – PaO_2 > 60 mm Hg; ARDS
- *Renal* – urine output < 40 ml/hour; increase in blood urea and serum creatinine.
- *Metabolic* – Falling serum calcium; magnesium and albumin.
- *Haematologic* – Fall in haematocrit; DIC.
- *Gastrointestinal* – Severe ileus; sequestration of fluid.
- *Neurologic* – Irritability; confusion; localizing features.

PSEUDOCYST OF PANCREAS

- It is localized collection of sequestered pancreatic fluid, usually 3 weeks after an attack of acute pancreatitis.
- It can occur after trauma and recurrent chronic pancreatitis.
- Collection usually occurs in the lesser sac in relation to stomach, but can occur in relation with duodenum, jejunum, colon, splenic hilum.
- About 50% of acute pancreatitis leads to pseudocyst formation, but among that 20-40% will resolve spontaneously.

Sites of pseudocyst

- Lesser sac—commonest, i.e. between colon and stomach

In relation to:

- Duodenum
- Jejunum
- Colon
- Splenic hilum



Fig. 14.9: Pseudocyst of pancreas.

Types

Depending on whether it communicates with pancreatic duct or not it is classified as:

1. *Communicating pseudocyst.*
2. *Noncommunicating pseudocyst.*

It can be

- *Acute pseudocyst.*
- *Chronic pseudocyst.*

D'Egidio Classification of Pseudocyst

- *Type I* - After an attack of acute pancreatitis. Normal duct anatomy; no fistula/communication.
- *Type II* – After an attack of acute on chronic pancreatitis. Abnormal duct anatomy without stricture; 50% chances of fistula.
- *Type III* – After an attack of chronic pancreatitis, abnormal anatomy with stricture; always communicating. It appears like retention cyst.

- Initially cyst wall is thin *(unformed),* but later it gets fibrosed and thickened *(formed)* (matured).
- It is lined by fibrin layer but no endothelium, hence called as pseudocyst.
- It contains typically brownish fluid with sludge like necrotic material. It can get infected to form *infected pseudocyst* or *pancreatic abscess.*
- Amylase level in the cyst fluid is very high (> 5000 units/ml).

Note: It is not a true cyst as there is no epithelial lining.

Clinical Features

- A swelling in the epigastric region which is hemispherical, smooth, soft, not moving with respiration, not mobile, upper margin is diffuse but lower margin well defined, resonant or impaired resonant on percussion, with transmitted pulsation confirmed by knee-elbow position.
- If it is infected, it will be tender mass and patient will be toxic with fever and chills.
- Because stomach is stretched towards the abdominal wall, Ryle's tube passed will be felt per abdominally *(Baid test)***.**

Differential Diagnosis

- Aortic aneurysm.
- Retro-peritoneal cyst or tumour.
- Cystadeno carcinoma of pancreas.



Fig. 14.10: Pseudocyst mass.

- Cyst of the liver.
- Mesenteric cyst.
- Hydatid cyst.

Investigations

- U/S abdomen (commonly done procedure), U/S reveals the size and thickness of the pseudocyst. Size less than 6 cm indicates that one can wait for spontaneous resolution. Endosonography (EUS) is very useful.
- CT scan is ideal and study of choice. It is two times more sensitive than U/S. It demonstrates size, shape, number, wall thickness, contents, pancreatic duct size, and extent of necrosis in pancreas, calcification and atrophy in chronic pancreatitis, regional vessels, pseudoaneurysm, splenic/portal vein thrombosis.
- MRCP delineates the ductal anatomy and its abnormality.
- ERCP can be done to find out the communication.
- Barium meal (lateral view) shows widened vertebrogastric angle with displaced stomach (Not usually done now).
- LFT, serum amylase.

Indications for surgery/intervention

- Size more than 6 cm
- Formed pseudocyst
- Infected pseudocyst
- Cyst persisting after 6 weeks/progressive cyst
- Multiple cysts/cyst due to trauma
- Communicating cysts/cyst with severe pain
- Thick walled pseudocyst

Doing the surgery may be easier, but it is managing the patient which counts finally.



Fig. 14.11: Vertebro-gastric angle.





Figs 14.12A and B: CT scan showing typical pseudocyst of pancreas.





Figs 14.13A and B: CT scan showing pseudocyst of pancreas both single and multiple. Note cyst cavity and thick cyst wall. Patient needs drainage procedure either cystogastrostomy or cystojejunostomy.

Surgery

- *Cysto-gastrostomy:* At laparotomy, anterior wall and posterior wall of the stomach is opened. *Brownish fluid* is aspirated. The thick capsule of pseudocyst is opened. All fluid with necrotic material are sucked. Fluid should be sent for cytology, culture and sensitivity and amylase estimation. Cyst wall always should be biopsied. Cyst cavity should be washed with normal saline after breaking septae. Pseudocapsule is anastomosed to posterior wall of the stomach—*Jurasz operation.*
  Note: **Roux-en-Y cystojejunostomy is better with lesser recurrence rate than cystogastrostomy.**



Fig. 14.14: Pseudocyst of the pancreas aspiration on table. Note the brownish-black colour of the fluid aspirated.

Other procedures

- Cysto-duodenostomy.
- Cystojejunostomy is done in large cyst, recurrent cyst.
- If infected, cystogastrostomy with external drainage is done using Malecot's catheter (*Smith operation*).
- Endoscopic cysto-gastric stenting.
- Laparoscopic cystogastrostomy is becoming popular, effective and less invasive.
- U/S guided aspiration is useful in initial phases.



Fig. 14.15: Cystogastrostomy for pseudocyst of the pancreas.



Fig. 14.16: Cystogastrostomy procedure, on table.

- Along with cystojejunostomy, pancreaticojejunostomy should be done if there is ductal stricture and dilatation and communication with pseudocyst.
- Distal pancreatectomy with pseudocyst removal if cyst is in distal part.

Complications of pseudocyst

- Rupture—3% - into bowel or peritoneum
- Infection, commonest—20%
- Bleeding from the splenic vessels—7%
- Cholangitis
- Duodenal obstruction
- Portal/splenic vein thrombosis and segmental portal hypertension
- Cholestasis due to CBD block

Pseudo-pseudopancreatic Cyst

It is a mass in epigastric region due to pancreatitis formed by bowel, omentum which clinically mimics a pseudo cyst of pancreas. But fluid collection is absent.

Note:

- Small cyst can be drained through endoscopy. But debridement is not possible. Bleeding and cyst leakage are other problems.
- CT guided percutaneous catheter placement is done in critically ill patients, infected pseudocyst, unfit patients, cyst in pelvis/mediastinum. Improper drainage, recurrence and fistula formation are the problems.
- External drainage is done when cyst is infected, haemorrhagic or ruptured. Problem with external drainage is formation of fistula (20%).
- Therapy is decided based on thickness of the wall of pseudocyst; location of pseudocyst; contents of pseudocyst and ductal status.

> *Carcinoma pancreas should be suspected when an elderly person develops diabetes and in spite of adequate treatment, continues to loose weight.*
> — Robert D Lawrence


Stomach
Oesophagus
Pseudocyst
Liver
Cystogastrostomy
Spleen
Pancreas
Duodenum

Fig. 14.17: Roux-en-Y cystojejunostomy for pseudocyst of the pancreas.

CHRONIC PANCREATITIS

- It is persistent progressive irreversible damage of the pancreas due to chronic inflammation.


It can be
Chronic relapsing pancreatitis
Chronic pancreatitis (persistent)
Chronic non-calcifying pancreatitis
Calcifying pancreatitis
In the duct (Stone in the pancreatic duct)
In the parenchyma

- Chronic pancreatitis is more common in males, common in Kerala (induced by diet, rich in Tapioca).



Fig. 14.18: Calcifications in the parenchyma of the pancreas.



Fig. 14.19: Pancreatic ductal stone removed—specimen. Patient underwent pancreatico-jejunostomy.

Aetiology

- Alcohol - 80%
- Stones in biliary tree – rare cause
- Malnutrition, diet
- Hyperparathyroidism
- Hereditary (familial hereditary pancreatitis)
- Idiopathic - 20% – as mutation
- Trauma
- Congenital anomaly (Pancreatic divisum)
- Cystic fibrosis
- Autoimmune pancreatitis
- Hyperlipidaemia

- Alcohol reduces pancreatic blood flow, alters cell viability, releases the free radicals, creates pancreatic ischaemia, and activates the pancrearic stellate cells which produce abundant extracellular matrix and collagen.
- Genetic predisposition may be the cause of idiopathic pancreatitis. Mutation in pancreatic secretory trypsin inhibitor causes activation of trypsin causing pancreatitis.
- Hereditary pancreatitis is an autosomal disorder with mutation in trypsinogen gene in chromosome 7.

Pathology

- It shows atrophy of acini, hyperplasia of duct epithelium, inter-lobular fibrosis, calcifications, ductal dilatation, with strictures in the duct, focal necrosis.
- There is loss of exocrine function initially and endocrine functions eventually.
- Ductular metaplasia and acinar atrophy along with fibrosis and cyst formation develops.

Pathology of chronic pancreatitis

- Focal necrosis
- Segmental or diffuse fibrosis
- Parenchymal calcification or ductal stones
- Stricture or dilatation of the duct

Spectrum of Chronic Pancreatitis

- *Early* – pancreatic oedema – chronic inflammation – normal secretary function.
- *Moderate* – early fibrosis; only few acinar cells – exocrine dysfunction.
- *Late* – fibrosis – loss of secretary function – diabetes mellitus.
- *Complications* develop secondary to healing and fibrosis; deposition of inspissated proteinaceous material in the duct; over expression of CTGF and TGF-B1 that stimulate extracellular matrix.
- *Pain hypothesis include:*
  - Acute and chronic inflammation of the pancreas.
  - Increased pressure within the pancreatic ductal system and parenchyma, ductal dilatation, stasis.
  - Ischaemia of the parenchyma secondary to increased interstitial pressure.
  - Over expression of a particular protein in pancreatic nerve fibres.
  - Pancreatic nerve growth factor released by degenerating acinar cells and its high affinity receptor that promotes nerve growth and repair.
  - Pain may be due to perineural sheath destruction by toxins, ischaemia and also due to tissue acidosis.



Fig. 14.20: Patient will occupy leaning forward position to relieve severe pain of pancreatitis.

Clinical Features

- *Pain in epigastric region*, persistent and severe, which radiates to back. This pain is due to irritation of retropancreatic nerves, or due to ductal dilatation and stasis, or due to chronic inflammation itself.
- *Exocrine dysfunction*: Diarrhoea, asthenia, loss of weight and appetite, steatorrhoea (signifies severe pancreatic insufficiency), malabsorption.
- *Endocrine dysfunction*: Diabetes mellitus.
- *Mild jaundice* is due to narrowing of retropancreatic bile duct and cholangitis.
- *Mass per abdomen*, just above the umbilicus, tender, nodular, hard, felt on deep palpation, not moving with respiration, not mobile, resonant on percussion.

Mallet-Guys sign: In right knee-chest position, if left hypochondrium is palpated tenderness can be evoked in case of chronic-relapsing pancreatitis. In this position, bowel loops are being shifted to right so as to have a direct palpation of pancreas.

Chronic pancreatitis can lead to carcinoma pancreas.

Complications of chronic pancreatitis

- Pseudocyst of pancreas
- Pancreatic ascites
- CBD stricture due to oedema or inflammation
- Duodenal stenosis
- Portal thrombosis—Segmental portal hypertension
- Peptic ulcer
- Carcinoma pancreas
- Pancreatic pleural effusion
- Pancreatic fistula
- Splenic vein thrombosis
- Pancreatico enteric fistula

Differential Diagnosis

- Carcinoma of head of the pancreas.
- Retroperitoneal tumour.

Investigations

- Serum amylase - not very useful
- Blood sugar
- Liver function tests and prothrombin time
- U/S abdomen to see duct dilatation, stones, parenchyma, liver status, CBD (normally, diameter of pancreatic duct is < 3 mm)
- Endosonography
- CT scan—CT guided FNAC
- ERCP—*Chain of lake appearance*. Duct is dilated

A goal is a dream with a deadline.

- MRCP
- Plain X-ray shows calcification in 65% of patients.
- Pancreatic secretory juice analysis
- *Pancreolauryl test*—Pancreatic esterase cleaves fluorescein dilaurate after oral intake. Fluorescein is absorbed and quantified in urine after 2 days.
- Oral glucose tolerance test
- Faecal chymotrypsin and elastase analysis.

Investigations presently used are –

- *CT scan abdomen* – It is 95% reliable; to see pseudocyst, calcification, ductal stones, duct stricture and dilatation, vasculature, fibrosis, surrounding structures, CBD status.
- *ERCP* is useful in chronic pancreatitis to see dilatations, strictures and altered ductal anatomy. It is mainly to assess *structural pathology* of the pancreas.
- *MRCP* is noninvasive method to see ductal anatomy.
- *Endosonography (EUS)* to see possible malignant site and to take FNAC. Site, duct status, stricture, stones, parenchyma, pseudocyst, CBD status, nodes are identified in EUS. Positive five parameters suggest chronic pancreatitis. It also helps in assessing operability.
- *Secretin cholecystokinin test* is the gold standard for assessing pancreatic function. After over night fasting, double lumen tube is placed into the duodenum at the level of ligament of Treitz under C ARM guidance. Gastric and duodenal juices are aspirated. Continuous IV secretin 1 u/kg/hour and CCK are infused in 90 minutes. Sampling of duodenal juice is done in every 10 minutes for one hour for analysis of *volume, HCO3*, amylase, lipase and proteases. It is to assess *functional deficiency*. In chronic pancreatitis volume is normal - > 2 ml/kg but less bicarbonate content - < 80 m Eq/L. In malignancy volume is reduced due to obstruction - < 2 ml/kg; bicarbonate level is normal - > 80 m Eq/L; enzyme levels are normal.
- *Pancreolauryl test* – After overnight fasting, blood sample is taken. IV secretin is injected 1 u/kg in 3 minutes. Test meal containing bread, butter, tea and fluorescein dilaurate is given to eat. IV metoclopramide 10 mg is injected. Blood samples are taken at 2, 2½, 3 and 4 hours to assess serum fluorescein concentration. It is also quantified in urine after 2 days.
- *LFT, prothrombin time* is needed to manage the patient.



Figs 14.21A and B: Multiple stones in pancreatic duct with ductal dilatation. It needs removal of stones with pancreaticojejunostomy.

Treatment

Conservative

- Avoid alcohol.
- Low fat, high protein, high carbohydrate diet; small and more frequent meals.
- Pancreatic enzyme supplements, vitamins and minerals, medium chain fatty acids.
- For pain—analgesics, splanchnic nerve or coeliac plexus block.
- Control of diabetes by oral hypoglycaemics or insulin.
- Somatostatin and its analogues. Its role is not clear.
- Repeated ascitic taps for pancreatic ascites.

Surgery

Indications for Surgery

- Persisting pain - main indication
- Severe malabsorption



Figs 14.22A to C: CT scan abdomen showing features of chronic pancreatitis – calcification, ductal changes, and cyst formation.

- Suspicion of malignant transformation
- Multiple relapses
- Complications like pseudocyst, segmental portal hypertension
- Biliary obstruction (*Wadsworth syndrome*)
- Pseudocyst
- Pancreatic ductal dilatation > 7 mm
- Pancreatic ascites/fistula
- Pancreatic ductal stenosis

Principles of Surgery

- *Pancreatic duct decompression* (drainage) reduces the pain and retains the existing exocrine and endocrine functions. But chances of malignant transformation are still high. In significant number of patients recurrence of symptoms (50% recurrence of pain in 5 years) and progression of the disease pathology occurs and it does not give a complete cure. Normal diameter of pancreatic duct 4 mm in head; 3 mm in body; 2 mm in tail of the pancreas. *Pancreatic duct diameter more than 7 mm is an indication for surgery (pancreaticojejunostomy).*
- *Pancreatic resection* (total pancreatectomy) is the actually ideal technique which relieves pain, removes entire diseased tissue. But technical difficulty; high surgical mortality (21%); and severe exocrine and endocrine deficiency (brittle diabetes) are the drawbacks. Head of pancreas is considered as pacemaker of the pancreatitis disease and so pancreaticoduodenectomy (*Whipple's*) is the other option to give adequate relief. It is preferred in patients who are having relatively normal body and tail of the pancreas. Occasionally when disease is limited to tail and body then *distal pancreatectomy* with or without splenectomy often with distal pancreatico jejunostomy may be done. But it is not beneficial if disease is extensive and diffuse. Resection is the main method of treatment if ductal dilatation is not adequate.
- A combined resection and drainage procedures are also done. Head is decored at various levels and decompressed duct is anastomosed to jejunum.

Surgeries

- 95% *subtotal pancreatectomy.*
- *Distal pancreatectomy*—Spleen, body and tail of the pancreas are removed—*Child's operation.*
- *Puestow's operation*—As the duct is dilated more than 8 mm, duct can easily be opened longitudinally. After removing all stones from the duct, it is anastomosed

Knowledge is the only treasure that increases on sharing.

to the jejunum as *Roux-en-Y anastomosis.* In Puestow's operation spleen is removed.

- *Partington – Rochelle operation*: Here longitudinal pancreaticojejunostomy is done using almost entire laid open pancreatic duct. Spleen is retained in this procedure. This is now commonly done procedure.


Oesophagus
Puestow's operation
Stomach
Spleen removed
Duct
Pancreas
Duodenum
Jejunal loop is telescoped into the entirely mobilised body and tail of pancreas and fixed
Jejunum

Fig. 14.23: Puestow's pancreaticojejunostomy. Here spleen is removed. Entire length of dilated duct is opened. Distal pancreas is mobilised upto superior mesenteric vessels. Pancreas with opened duct is telescoped into the Roux loop of jejunum and anastomosed.


Oesophagus
Spleen retained
Liver
Stomach
Pancreas
Duct
Duodenum
Jejunum
Partington-Rochelle operation

Fig. 14.24: Partington-Rochelle operation. Here spleen is retained and longitudinal pancreaticojejunostomy is done to the opened duct from front.


Oesophagus
Liver
Stomach
Pancreas
Duct
Duodenum
Jejunum
Decoring of head also done
Frey and Smith procedure

Fig. 14.25: Frey's procedure. Here head of pancreas is decored and opened duct with decored head is anastomosed to Roux loop of jejunum.


Oesophagus
Liver
Stomach
Pancreas
SV
PV
SMV
Duodenum
Jejunum
Beger's procedure
Decoring upto portal vein, neck transected to anastomose

Fig. 14.26: Beger's procedure. Here head is decored upto the visible portal vein. Neck is transected. Distal end of the pancreas with retained part is anastomosed to Roux loop of jejunum.

- *Total pancreatectomy* is indicated when entire gland is diseased. It relieves the pain and also prevents the diseased pancreas from turning into malignancy. Patient has to take insulin and oral pancreatic enzymes permanently (*brittle diabetes*).
- The cause is treated like cholecystectomy for gall stones.


CDJ – Choledochojejunostomy
JJ – Jejunojejunostomy
Liver
CBD
CDJ
Stomach
Pancreas
Biliary stricture
JJ
Jejunum
A
Oesophagus
Liver
CDJ
CBD
Roux-en-Y loop
GJ
Spleen
PJ
JJ
Pancreas
B
JJ
CDJ – Choledochojejunostomy
PJ – Pancreaticojejunostomy
JJ – Jejunojejunostomy
GJ – Gastrojejunostomy

Figs 14.27A and B: *Choledochojejunostomy*. It is Roux-en-Y anastomosis. It is done whenever there is complication of biliary stricture after pancreatitis. Often triple anastomosis may be required – pancreatico jejunostomy, choledochojejunostomy and gastrojejunostomy. It is done whenever there is duodenal obstruction, biliary block and pancreatic duct dilatation (drainage procedure).


Oesophagus
Liver
Stomach
Pancreas
Duodenum
Jejunum

Fig. 14.28: Retrograde pancreatico jejunostomy after resection of the tail of the pancreas (Duval).

- Therapeutic ERCP is useful in removal of stones in dilated duct.
- If disease mainly involves head of the pancreas, then pancreatico-duodenectomy can be done—*Whipple's procedure.*
- Duodenal preserving resection of head of pancreas in front of portal vein with jejunal loop anastomosis to transected neck of pancreas—*Beger procedure.* Here extensive resection of head (than Frey's) is done.
- Longitudinal pancreatico-jejunostomy after excision of peripancreatic duct tissue—here superficial part of the head of pancreas is removed to achieve improved drainage—*Frey procedure*. It is done when ductal dilatation is not adequate; head is more than 4 cm thick. Head coring is done with retaining 5 mm thick tissue in front of veins, close to duodenum. It shows 75% pain relief in 3 years.
- Resection of tail of pancreas with retrograde pancreatico-jejunostomy—*Duval procedure*.
- When duodenal, biliary and pancreatic obstruction is present- choledocho jejunal- pancreatico-jejunal and gastrojejunal anastomosis may be needed – *triple anastomosis*. Only biliary stricture which can not be managed by ERCP needs choledochojejunostomy.
- *Complications of surgery:* Pancreatic leak/fistula (10%); infection; bleeding; recurrence; brittle diabetes.

Listen to the faintest sound; for opportunities knock only once.

- *Pain relief* in chronic pancreatitis is achieved by drugs; decompression/drainage surgeries, resection surgeries, epidural analgesia, coeliac ganglion block, operative chemical splanchnicectomy, extra/intra peritoneal right and left splanchnicectomy, transhiatal bilateral splanchnicectomy, thoracoscopic splanchnicectomy.

Post Operative Care

- Nutrition – TPN/jejunostomy feed.
- Fluid and electrolyte management.
- Prevention/control of sepsis.
- Proper monitoring.
- Octreotide on table and post-operatively – regular intervals or slow infusion – 5 days.

Surgery for chronic pancreatitis

Drainage	*Resection*
• Technically easier • Less mortality < 2-5% • Adequate pain relief • Recurrence of pain in 5 years – 50% • Diseased tissue is left behind • Disease progression • Fear of existing occult carcinoma (17%) or later onset	• Technically demanding • Mortality 8-21% - very high • Used when carcinoma is suspected or localised disease • Head is the pacemaker of the disease • WHIPLLES is preferred • Total pancreatectomy causes high mortality, brittle diabetes; though ideal it is not done commonly

PANCREATIC TUMOURS

Classification

A. ***Exocrine tumours***

Benign: Benign cystadenoma. It is rare.

Malignant:

1. Adenocarcinoma in ampulla or periampullary region or head of pancreas. Periampullary carcinoma may arise from any of the component—duodenal mucosa or CBD or pancreatic duct component or all. Occasionally squamous cell carcinoma, or combination of adeno squamous can occur.
2. Cystadenocarcinoma of pancreas occurs commonly in body and tail of the pancreas, which usually attains a large size (5%).

B. ***Endocrine tumours***

1. Insulinoma (β cells)	Whipple's triad
2. Gastrinoma (G cells)	Peptic ulcer.
3. Glucagonoma (α cells)	Diabetes, necrolytic migratory erythema.
4. Vipoma—Pancreatic cholera (Verner-Morrison syndrome)	Watery diarrhoea, hypokalaemia achlorhydria. (WDHA syndrome)
5. Somatostatinoma. (S cells) δ cells	Diabetes, steatorrhoea, gallstones.

C. ***Lymphomas***

EXOCRINE PANCREATIC TUMOURS

Carcinoma pancreas is higher in men. It is common in African American males. 80% of pancreatic cancers are metastatic at the time of first diagnosis. It is common in Jewish heritage and native Hawaiians. Its incidence is 9 new cases per 100000 people. Mean age is 60-65 years.

Etiology

- Smoking.
- High energy diet rich in fat.
- Chronic pancreatitis.
- Familial pancreatitis.
- Diabetes mellitus.
- Carcinogens like benzidine.
- Hemochromatosis with pancreatic calcification.
- Cirrhosis, obesity.
- Occupational exposure to carcinogens like DDT, benzidine.
- *Peutz – Jegher syndrome*, *HNCC* (Hereditary Non polyposis Colonic Cancer - Lynch II type), ataxia telangiectasia, *hereditary breast and ovarian cancers*, *hereditary atypical multiple mole melanoma syndrome*.

Sites

- Head and neck region
- Ampullary and periampullary region } 70%
- Body and tail—30%

Periampullary Carcinoma is Tumour Arising at or Near the Ampulla

It could be –

- Adenocarcinoma from head of pancreas close to the ampulla – 50%.
- Tumour from ampulla of Vater – 30%.
- Distal bile duct carcinoma – 10%.
- Duodenal carcinoma adjacent to ampulla – 10%.

Pathology

Exocrine pancreatic tumours can be solid (75%) or cystic.

Solid neoplasm–

- *Infiltrating ductal adenocarcinoma* (85%), is common in head (yellowish white mass), neck and ampulla. There is evidence of ductal/glandular differentiation; with intense non neoplastic desmoplastic stromal reaction; haphazard infiltrative growth pattern; growth along the nerve roots; and lymphovascular invasion. Early non invasive epithelial proliferation is called as *pancreatic intraepithelial neoplasia* (PanIN). Immunohistochemistry shows CA 19-9; mucins (MUC1, 3, 4, 5); CEA; cytokeratins 9, 19. 5 year survival is < 5%. After surgery it may be 20%. Signet ring, colloid, anaplastic types are variants.
- *Acinar cell carcinoma* shows sheets of acinar structures with often metastatic fat necrosis, eosinophilia, polyarthralgia. Presence of zymogen granules; antibodies against trypsin/chymotrypsin and lipase are typical.
- *Pancreatoblastoma* are malignant tumour seen commonly in children.

Cystic neoplasms—

- *Mucinous cystic neoplasms* are more common. They are common in females (90%). They are common in tail and body. They do not communicate with main pancreatic duct. Mucus secreting columnar epithelium with dense ovarian like stroma is typical histology. It can be mucinous cystadenoma; borderline; *in situ*; mucinous cystadenocarcinoma. Mucinous tumours may show high levels of CEA but low levels of amylase. Presentations may be mass abdomen (large epigastric mass, non mobile, not moving with respiration), abdominal pain, back pain. Survival rate for mucinous cystadenocarcinoma is 50%.
- *Serous cystic neoplasms* are almost always benign and are common in females. It can be microcystic adenomas (90%) or oligocystic adenomas (10%). Central or distal pancreatectomy is the treatment to these patients.
- *Intraductal papillary mucinous neoplasms* (IPMN) are common in males. It is commonly malignant with 40% 5 year survival rate. ERCP shows thick mucus extruding from ampulla.

Clinical Features

Presentations –

a. Ampullary tumours mainly present with *jaundice and weight loss.*



Figs 14.29A to C: CT scan picture of cystadenocarcinoma of pancreas.



Fig. 14.30: On table finding of cystadenocarcinoma of pancreas

Many receive advice, only wise profit from it.



Fig. 14.31: Carcinoma head of the pancreas.

b. Carcinoma of head and neck region present with weight loss and jaundice.
c. Cystadenocarcinoma of pancreas present with pain, weight loss and mass.



Fig. 14.32: Obstructive jaundice due to periampullary carcinoma in male and female patients.

Features are–

- *Jaundice is of obstructive nature* which is of short duration, severe, progressive, associated with pruritus (due to deposition of bile salts in the skin which releases histamine). Painless jaundice is seen in ampullary malignancies.
- In periampullary carcinoma sometimes necrosis of tumour occurs, as a result of which jaundice may reduce temporarily thus being *intermittent.*
- Pain in the right hypochondrium, epigastrium, or left hypochondrium depending on location of the tumour.
- Back pain, when present, is due to involvement of retropancreatic nerves, or pancreatic duct obstruction or stasis, disruption of nerve sheath by tumour.
- Diarrhoea, steatorrhoea, acholic stools, tea colored urine.
- Silvery stool (due to mixing of undigested fat with metabolised blood derived from the ooze of periampullary growth).
- Loss of appetite and weight.
- Scratch marks on the back.
- *Migratory superficial thrombophlebitis—Trousseau's sign* (10%) is due to release of platelet aggregating factors from the tumour or its necrotic material. (Trousseau himself died of carcinoma pancreas who had migrating thrombophlebitis.)
- Ascites.
- Left supraclavicular palpable lymph node.
- Secondaries in rectovesical pouch (Blumer's shelf).
- Gall bladder may be palpable which is nontender, soft, globular, smooth, moving with respiration, mobile horizontally, dull on percussion. (30% in carcinoma head of pancreas; 50% in periampullary carcinoma). *Courvoisier law* favours gall bladder enlargement.
- Liver is enlarged, smooth, firm, nontender, due to dilated bile filled biliary radicles—*Hydrohepatosis*. Liver can show multiple hard nodules due to secondaries.
- Cystadenocarcinoma of pancreas can present with mass in epigastric region, which is nonmobile, not moving with respiration, smooth, soft, nontender.
- Splenic vein thrombosis with splenomegaly (10%) can occur.

Cystadenocarcinoma of the pancreas

- Common in body and tail of the pancreas
- Epigastric pain which is radiating to back is common
- Mass in epigastrium which is nonmobile, smooth, soft/hard but not moving with respiration. It is resonant, does not fall forward
- Jaundice is not observed
- May mimic pseudocyst of pancreas or retroperitoneal tumours
- 1% of pancreatic malignant tumours
- Papillary cytadenocarcinoma is common
- Mucinous cystic tumours show high levels of CEA
- CT scan is diagnostic
- Distal pancreatectomy is the procedure of choice. In large tumours total pancreatectomy is required
- It has got better prognosis

Differential diagnosis

- Retroperitoneal mass/tumour/lymph nodes
- Advanced adherent carcinoma of stomach
- Advanced carcinoma of transverse colon
- CBD stone
- Bile duct stricture
- Lymph node compressing CBD
- Cholangiocarcinoma of CBD
- Chronic pancreatitis



Fig. 14.33: Ultrasound showing mass lesion in the pancreas.



Fig. 14.34: CT picture of carcinoma pancreas showing dilated CBD due to obstruction.

Investigations

- Liver function tests: Serum bilirubin, direct component (conjugated) is increased (van den Bergh's test). Serum albumin is decreased with altered A : G ratio.
  Prothrombin time is widened. Serum alkaline phosphatase is increased.



Fig. 14.35: CT picture showing cystadenocarcinoma of pancreas.



Fig. 14.36: ERCP showing growth in the distal CBD.

Differences between presenting features of carcinoma of head of pancreas and periampullary carcinoma of pancreas

		Carcinoma of head of pancreas	*Periampullary carcinoma*
1.	Pain and weight loss	Early features	Late features
2.	Jaundice	Persistent and progressive	Intermittent
3.	Occult blood in stool	Absent	Present; stools are silvery
4.	Endoscopic examination	Growth not visible	Growth visible
5.	Prognosis	Not good	Good

Surgical Triad: *Measure thrice, think twice, cut once.*

- U/S abdomen to see gall bladder, liver, growth, CBD size (normal diameter is < 10 mm), lymph node status, portal vein, ascites.
- Barium meal shows widened duodenal *"C" loop—pad sign*. *Reverse 3 sign* is seen in carcinoma—periampullary region.
- Spiral CT scan (ideal) shows portal vein infiltration, retroperitoneal lymph nodes, size of the tumour.
- ERCP with pancreatic juice cytology or brush biopsy is useful. MRCP to see biliary tree.
- CA 19-9 (carbohydrate antigen) is a useful tumour marker.
- *Coeliac* and superior mesenteric angiogram can be done to reveal tumour circulation and invasion.
- Gastroduodenoscopy reveals ampullary tumour and biopsy can also be taken.
- *Endosonography* is useful to see the invasion and size, to stage and to do EUS guided FNAC.
- Urine for bile salts (*Hay's test*), bile pigments (*Fouchet's test*), urobilinogen.

Trucut biopsy and other biopsies are not advisable as it may cause bleeding, infection, leak and negative biopsy will not rule out malignancy.

- Laparoscopy to assess.
- CT angiogram to see the vascularity. It also provides idea about resectability of the tumour in 70% cases.



Fig. 14.37: CT scan abdomen showing features of carcinoma of pancreas.

ERCP signs	*Important investigations*
• Abrupt block of pancreatic duct with irregular stricture • Pancreatic duct encasement • *Double duct sign* – cut off of both pancreatic and bile duct • Parenchymal filling • Scrambled egg appearance	• Spiral CT/3D CT is ideal – to detect operability, portal vein invasion, size, extent, pancreatic and biliary tree and nodal status • ERCP to take biopsy/brush cytology, stenting, to see the luminal extent of the tumour • MRCP is non invasive – entire biliary tree is visualised properly • Endosonography (EUS) – to assess size of primary properly; to take endosonographic FNAC • PTC often with PBD if ERCP fails
Barium meal X-ray	*Investigations to stage the disease*
• Is rarely done in periampullary carcinoma • *Rose thorn* appearance in hypotonic duodenography • *Reverse 3 sign* in periampullary carcinoma • *Pad sign* – widened C loop of duodenum in carcinoma head of pancreas • Features of Gastric outlet obstruction	• 3D/spiral CT scan • EUS • Laparoscopy • ERCP

TNM Staging of carcinoma of pancreas (UICC – Union International Center for Cancer)

Tis — *In situ* carcinoma and PanIN
T_1 — Growth limited to pancreas T1a - < 2cm; T1b > 2 cm)
T_2 — Extension occurs to duodenum, bile duct, peripancreatic tissues
T_3 — Extension to stomach, spleen, colon, large vessels
N_0 — No lymph nodes
N_1 — +ve lymph nodes
M_0 — No metastasis
M_1 — +ve metastasis

Resection status –

R0 – No residual tumour found after resection
R1 – Microscopic residual tumour after resection
R2 – Macroscopic residual tumour after resection

Pre Operative Preparation in Carcinoma Pancreas –

- Adequate hydration is important in prevention of dehydration post operatively. Dehydration is common in obstructive jaundice.

- Glycogen reserve in liver will be inadequate which should be replenished by giving preoperative glucose orally or intravenously.
- Patient is prone to develop hepatorenal syndrome post operatively, leading into renal failure due to sludging of the bile salts, due to toxins and sepsis; and so mannitol should be given intravenously for 3 days prior to surgery to flush the kidney (200 ml IV twice a day).
- Injection vitamin K 10 mg IM for 5 days.
- ERCP stenting is done to drain bile if serum bilirubin is high (> 30 mg %). Surgery is done after 2-3 weeks once bilirubin level drops down adequately. If ERCP is not possible then percutaneous transbiliary drainage (PTBD) or *cholecystostomy* using Foley's or Malecot's catheter is done. Surgical resection (Whipple's) is done after 3 weeks. Present indications for ERCP stenting are severe albumin deficit and cholangitis.
- Antibiotics one day prior to surgery – cephalosporins/aminoglycosides.
- Often TPN may be required preoperatively which is also continued post operatively.
- Pulmonary function study and respiratory physiotherapy to have adequate post operative pulmonary function.

Note:

- In obstructive jaundice, serum bilirubin level will not go beyond 40 mg%. At this point raised intrabiliary pressure (Normal is 12-22 cm of H_2O) to 25 cm of H_2O, blocks the formation of bilirubin and secretion of cholesterol and bile acids completely. Maximum production of bilirubin per day possible is 250 mg%. Normal maximum excretion of bilirubin by kidney per day is 210 mg%. So maximum possible raise of serum bilirubin is 40 mg% in obstructive jaundice.
- Cholangitis in malignant obstruction is rare; but when it occurs it is rather severe form.
- Preoperative albumin therapy is usually *not done.*

Treatment

Only 10-15% of pancreatic carcinomas (head) are operable. 40-50% are locally advanced. Another 40-50% will have distant spread to liver or lungs.

Criteria for resection –

- Tumour size less than 3 cm
- Peri ampullary tumours
- Growth not adherent to portal system

In operable cases –

- *Whipple's operation* is done by removing tumour with head and neck of pancreas, C loop of duodenum, 40% distal stomach, 10 cm proximal jejunum, lower end of the common bile duct, gallbladder, peripancreatic, pericholedochal, paraduodenal and perihepatic nodes. Continuity is maintained by choledochojejunostomy, pancreaticojejunostomy and gastrojejunostomy. Few advocate pancreaticogastrostomy into posterior wall of the stomach. Mortality in Whipple's operation is 2-8%. Original Whipple's operation (1935) was two staged procedure– initial by pass and a second stage resection with closure of pancreatic stump. In 1941, Trimble performed one stage pancreaticojejunostomy. *Complications* are delayed gastric emptying (19%); pancreatic fistula (14%); infection (intraabdominal abscess, wound infection, cholangitis, pancreatitis, pneumonia); bile leak. Mortality is 3%.
- *Traverso – Longmire pylorus preserving pancreaticoduodenectomy* (1978) – Here duodenum is cut 2 cm distal to the pylorus and continuity is maintained by anastomosing with jejunum.



Fig. 14.38: Whipples operation.

> *To overcome rigidity of abdomen in refractory cases, with the base of the left hand pressing upon the lower part of the sternum, thoracic respiration is impeded and the abdominal muscles relax.*
>
> —Neville J Nicholson



Fig. 14.39: Specimen of pancreaticoduodenectomy with tumour in the head of pancreas.



Fig. 14.40A: Resected specimen (after Whipple's operation) of periampullary carcinoma of pancreas.



Fig. 14.40B: On table finding in periampullary tumour showing dilated gallbladder and CBD.

- *Fortner's regional pancreatectomy* (extended Whipple's) includes resection like Whipple's along with removal of segment of superior mesenteric vein and clearance of all regional nodes; and portal vein continuity is maintained by a synthetic vascular graft. Even though technically it gives adequate clearance, results are only equivocal.
- *Total pancreatectomy is presently said to be better*. It is done along with nodal clearance. Reasons are – possibility of multicentric nature of the disease, higher chance of recurrence after Whipple's operation, malignant cells may be present in pancreatic duct, morbidity by pancreatic fistula or pancreatitis after Whipple's operation is not seen here. Mortality in total pancreatectomy is higher 10-20%. Severe, resistant brittle diabetes mellitus may be seen after total pancreatectomy.



Fig. 14.41: Specimen of total pancreatectomy with C loop, head, body and tail of pancreas with spleen. Total pancreatectomy is done in refractory severe chronic pancreatitis and carcinoma pancreas.

- Distal pancreatectomy or central pancreatectomy or total pancreatectomy for cystadenocarcinoma of pancreas depending on the extent and size of the tumour.



Fig. 14.42: Photo showing specimen of distal pancreatectomy.

In inoperable cases –

Here mainly to *palliate* obstructive jaundice, duodenal obstruction and pain.

- Roux en Y choledochojejunostomy is ideal palliative procedure along with gastrojejunostomy after doing cholecystectomy. Choledochojejunostomy is better than cholecystojejunostomy as CCJ may get blocked either by tumour infiltration or by bile sludge or by inflammation. 30% of periampullary carcinoma/ carcinoma of head of pancreas eventually develop gastric (duodenal) outlet obstruction and so gastrojejunostomy is undertaken.
- ERCP and stenting is done to drain bile. Problem here are recurrent cholangitis, stent blockage and displacement, requirement of repeated stenting procedure. Duodenal stenting for duodenal obstruction is tried.
- Chemotherapy; neoadjuvant chemotherapy.
- Steatorrhoea is treated by enzymes. Control of diabetes is important.

Adjuvant therapy

- Adjuvant chemotherapy using gemcitabine – better but costly; dose is 1000 mg/m^2 surface area; 5-fluorouracil; mitomycin; vincristine, cisplatin, docetaxel, oxaliplatin are used along with gemcitabine.



Fig. 14.43: Choledochojejunostomy (CDJ) with gastrojejunostomy (GJ) and jejunojejunostomy (JJ). It is a Roux-en-Y anastomosis. CDJ should be 70 cm from the JJ.



Fig. 14.44: Cholecystojejunostomy – is not a preferred method.



Fig. 14.45: It is neither white nor bile. It is opalescent; and is mucus. It suggests complete obstruction. It is usually observed in carcinoma pancreas. It is per operative finding.

- Radioactive iodine seeds I^{125} to the field are on trial. External radiotherapy 4000 cGy units to relieve pain and to reduce the tumour size.
- *Immunotherapy* – specific type to increase the effectiveness of chemotherapy and to improve the cure rate (allogenic tumour cell vaccine).

Postoperative Management in Carcinoma Pancreas

- Maintenance of proper fluid and electrolyte balance.
- Observation for bleeding and its control by transfusion of blood, fresh frozen plasma (FFP), and prevention of DIC at initial period.
- Injection vitamin K 10 mg IM for 5 days.
- Respiratory care – ideally post operative ICU care is better. Often ventilator is needed for 24 hours

Have a heart that never hardens and a temper that never tires and a touch that never hurts.

- Maintaining adequate urine output – mannitol should be continued.
- Injection octreotide infusion for 5 days to suppress pancreatic secretion so as to prevent leak.
- Antibiotics, nasogastric aspiration.
- Continuous monitoring the patient with pulse/blood pressure/oxygen saturation/hourly urine output/inspection of drain site/abdomen distension/by doing HB%, LFT, serum creatinine, bilirubin, arterial blood gas analysis if needed, platelet count, prothrombin time.

Pain Control in Carcinoma Pancreas

- CT guided 50% of 20 ml ethanol injection into coeliac ganglion.
- Epidural anaesthesia.
- Opioids administration.
- Transthoracic splanchnicectomy – greater splanchnic nerve.
- Palliative radiotherapy – 4000 cGy units.

Prognostic factors in carcinoma pancreas – poor prognosis

- Mean survival rate 6-9 months
- Growth more than 3 cm
- Nodal involvement
- Resection status – R0/R1/R2
- Portal vein infiltration
- Liver/lung secondaries
- Ascites/Trousseau's sign/left supraclavicular lymph nodal spread
- *White bile* on table carries poor prognosis
- Associated problems like pancreatitis, diabetes mellitus
- Liver dysfunction

ENDOCRINE PANCREATIC TUMOURS

- Most common is insulinoma.
  Others are gastrinoma, glucagonoma, vipoma, pancreatic polypeptidoma.
- They belong to group of tumours called "APUDOMAS".
- Endocrine tumours are associated with MEN syndrome (Type I Werner's syndrome).
- They are associated with–
  - Parathyroid adenoma.
  - Pituitary adenoma.
  - Peptic ulcer.
- They are usually multiple, small, 35-50% are malignant and presents with features of endocrine lesion. Commonly occurs in body and tail (except gastrinomas).
- Requires special method to identify.
- MRI, angiogram, hormone assay are the diagnostic methods required.
- Normal islet cells are < 2% of pancreatic mass. They contain α, β, δ, G, D2 and PP cells (pancreatic polypeptide).
- Incidence is 5 per 100000 per year.
- 20% are non functional.
- Insulinomas are commonly benign; glucagonomas are almost always malignant.

INSULINOMAS

- Insulinomas are commonest endocrine pancreatic tumour (60%) arising from B cells (β cells) of pancreas.
- They are commonly solitary but 10% can be multicentric and secrete insulin in excess causing profound hypoglycaemic features.
- Equal in both sexes.
- 90% of insulinomas are < 2 cm in size.
- 15% are malignant. 85% are benign.

Clinical Features

- Abdominal discomfort, trembling, sweating, hunger, dizziness, diplopia, hallucinations. Later epilepsy and unconsciousness. They are usually over weight.
- Weight gain is common due to overeating.
- Permanent neurological deficits can occur with behavioural changes.

Whipple's triad:

- An attack of hypoglycaemia in fasting state
- Blood sugar below 45 mg% during the attack
- Symptoms relieved by glucose

Diagnosis

- Insulin radioimmunoassay. An insulin level > 7 μU/ml; insulin/glucose ratio > 0.3 signifies insulinoma. Proinsulin level more than 24% of total insulin signifies insulinoma. Proinsulin level more than 40% of total insulin signifies malignant insulinoma. C peptide level > 1.2 μg/ml with glucose level < 40 mg% suggests insulinoma.
- MRI to localize the tumour.
- Angiogram (coeliac).
- Endosonography.
- On table U/S.
- Blood sugar estimation.
- Insulin provocation test using calcium gluconate or tolbutamide.

Radioimmunoassay in insulinoma–

- Increase in insulin levels of plasma
- Increased ratio of proinsulin to insulin > 20%
- Increased circulating C-peptide
- Plasma insulin to glucose ratio > 0.3 is diagnostic

Differential Diagnosis

- Nesidioblastosis.
- Noninsulinoma pancreatogenous hypoglycaemia.

Treatment

Treatment of insulinoma–

- Enucleation commonly, often distal pancreatectomy
- Diazoxide, beta blockers, phenytoin, verapamil, steroids, growth hormone to control hypoglycaemia
- Octreotide decreases the insulin secretion
- Calcium channel blockers
- Streptozotocin whenever secondaries are present in liver or elsewhere

- Enucleation of all tumours.
- Often distal pancreatectomy is required (spleen; tail and body of the pancreas are removed) 90% are curable.

GASTRINOMAS

- They arise from non-beta cells (G cells) of the pancreas, which secretes high levels of gastrin.
- It is 2nd most common endocrine pancreatic tumour.
- It is the commonest endocrine pancreatic tumour seen in MEN I syndrome. In MEN II syndrome lesion is often seen in duodenum (30%).
- It is common in males.
- Common in gastrinoma triangle (*Passaros triangle*).

Three points forming Passaros triangle:

1. Junction between the head and neck of the pancreas
2. Junction of cystic duct with CBD
3. Junction between the 2nd and 3rd parts of the duodenum

- Half of them are multiple and malignant (50%).
- It causes severe, multiple peptic ulcers in the stomach, duodenum and jejunum.
- It is due to hypergastrinaemia causing high levels of acid secretion.
- Other features are diarrhoea, steatorrhoea, hypokalaemia.
- It causes ZES type II.
- When malignant commonly present with secondaries in liver (80%)/lymph nodes/lungs or bones.

Salient features of ulcers in gastrinomas:

- Multiple ulcer
- Resistant ulcer/refractory ulcer
- Jejunal ulcer
- Recurrent ulcer
- Ulcer which is more prone for bleeding and perforation

Investigations

- Gastrin assay (normal level < 200 pg/ml).
- Gastroscopy.
- U/S, Endosonography.
- MRI (more sensitive) or CT scan to detect the site of the tumour.
- Angiogram.
- Increased gastrin level by calcium (injection IV) provocation test.
- Pentagastrin test (both shows very high basal and peak levels).
- Secretin provocation test.
- Somatostatin receptor scintigraphy (SRS) with radiolabeled octreotide is used to locate the site of tumour.

Note:

Normal level of gastrin is 100-150pg/ml. It is more than 200 pg/ml in gastrinoma patients. It usually reaches upto or greater than 1000 pg/ml in gastrinoma. Other causes of hypergastrinaemia like G cell hyperplasia, incomplete antrectomy, low gastric acid level, achlorohydria, pernicious anaemia, acid controlling drugs like H2 receptor block or proton pump inhibitors and atrophic gastritis should be ruled out. Basal acid output in gastrinoma is > 15 mEq/hour which is specific of gastrinoma (ZES II). Gastric pH more than 3 rules out gastrinoma. *Secretin stimulation test* by injecting 2 units/kg secretin IV and assessing blood samples before and every 5 minutes after injection of secretin for 30 minutes will show rise in gastrin level more than 50% of baseline.

Treatment

60% are curable.

- Enucleation of tumours.
- Distal pancreatectomy.
- Pancreaticoduodenectomy.

A goal is a dream with a deadline.

- Subtotal pancreatectomy.
- Often total gastrectomy may be required.



Fig. 14.46: Passaros triangle.

Remember

- Gastrinomas are often associated with MEN syndrome and are multiple
- Sporadic gastrinomas are often solitary and then are malignant
- Gastrinoma often secretes ACTH
- Most common malignant endocrine pancreatic tumour is gastrinoma
- Gastrinoma causes ulcer of unusual nature (refractory/resistant); unusual recurrence (repeated and multiple); unusual number (multiple); unusual sites (2nd/3rd part duodenum/jejunum); unusual age (young and aged)

Triad of somatostatinoma-

- Diabetes mellitus
- Steatorrhoea
- Cholecystolithiasis

GLUCAGONOMAS

- Arise from α cells of pancreas.
- Common in body and tail of pancreas.
- It is common in females.
- It attains large size of 5-10 cm.
- It is commonly sporadic. 17% associated with MEN type II syndrome.
- It is commonly malignant (80%). 80% spreads to liver.

Clinical Features

- Necrolytic migratory erythema (65%).
- Diabetes (90%).
- Diarrhoea and weight loss.
- Stomatitis.
- Anaemia and features of amino acid deficiency.
- Vulvovaginitis is common.

Investigations

- MRI, CT scan.
- Endosonography.
- Angiogram.
- Increased serum glucagon level. Fasting glucagon level more than 50 p mol/litre is diagnostic.

Treatment

- Correction of anaemia, protein and amino acid deficiency by enteral/parenteral nutrition.
- Intravenous amino acid infusion to control necrolytic dermatitis.
- Prevention of DVT.
- Distal pancreatectomy.
- Occasionally Whipple's/total pancreatectomy is needed.
- Enucleation is rarely sufficient for glucagonoma.
- Dacarbazine is specifically effective in glucagonoma.

Vipoma

- Arising from D2 cells of pancreas
- Watery diarrhoea, hypokalaemia, achlorohydria (WDHA syndrome)
- Also called as *pancreatic cholera or Verner- Morrison syndrome, weak – tea syndrome*
- Usually malignant
- Secretes vasointestinal polypeptide > 150 pg/ml
- Common in body and tail - solitary
- Distal pancreatectomy is the treatment of choice
- Prednisolone controls the diarrhoea
- Octreotide is useful

ZOLLINGER–ELLISON'S SYNDROME

Type I: "G" cell hyperplasia with hypergastrinaemia and chronic peptic ulceration.

Treatment is partial gastrectomy with removal of "G" cell area.

TYPE II: Gastrinomas (see above).

Note:

- Somatostatinoma arises from δ cells of pancreas. It is exceedingly rare. Usually larger than 2 cm and single. It is common in head of pancreas and duodenum. Its association with MEN II syndrome is rare. It is often associated with neurofibromatosis type I and phaeochromocytoma. Presentations are steatorrhoea; diabetes mellitus; gall stones; hypochlorohydria and occasional jaundice. Tumour is commonly malignant and commonly present with nodal and liver spread. Elevated fasting somatostatin level is diagnostic. Treatment is pancreaticoduodenectomy.
- 20% of pancreatic endocrine tumours are non functional. Nonfunctional means these tumours do

not produce hormones or produced hormones will not produce any symptoms.

- Pancreatic polypeptide tumour (PP tumour) is classified under the non functioning endocrine tumour as it does not cause any symptoms even though there is high pancreatic polypeptide. It is commonly malignant, often with spread. PPoma occurs predominantly in head of pancreas. Pancreaticoduodenectomy is the treatment.

CYSTIC FIBROSIS

It is inherited as an autosomal recessive disease. It causes—

1. *Severe exocrine dysfunction*—due to blockage of pancreatic ducts as a result of precipitation of pancreatic enzymes leading to duct ectasia.
2. *Chronic pulmonary disease* due to blockage of bronchi and bronchioles.
3. *Elevated sodium and chloride*—in the sweat more than 90 mmol/L.
4. It is common in Caucasians. It is inherited as mutation in cystic fibrosis transmembrane conductance regulator gene in chromosome 7.

Presentations

- Chronic pulmonary disease with emphysema, bronchiectasis.
- Steatorrhoea.
- Meconium ileus with intestinal obstruction.
- Salty sweat (while kissing the baby).
- Poor growth due to malabsorption.
- Cirrhosis of liver due to bile plugging.
- Pancreatitis is common.
- Sialadenitis, choroiditis can occur.
- Absence of vas deferens in men.

Diagnosis

- DNA study.
- Vomitus when put on a exposed X-ray film will not digest the gelatin in half an hour (wherein in normal individual vomitus contains trypsin which will digest the gelatin of X-ray film and turns white).
- U/S abdomen.
- Sweat test for sodium and chloride.
- Pulmonary function tests.

Treatment

- Low fat and salt rich diet.
- Correction of malabsorption.
- Pancreatic enzyme supplements.
- Antibiotics.
- Respiratory physiotherapy.
- If meconium ileus is present, it might require surgery, i.e. Bishop-Koop operation.

Prognosis is poor.

Problems in cystic fibrosis-

- Meconium ileus
- Recurrent respiratory infection and complications
- Sodium deficit
- Severe malnutrition
- Sialadenitis, choroiditis
- Cirrhosis of liver
- Usually die in childhood or early age group

ANNULAR PANCREAS

It is due to failure of complete rotation of ventral bud of pancreas, so that ring of pancreatic tissue encircles the 2nd part of the duodenum causing obstruction.



Fig. 14.47: Annular pancreas.

Clinical Features

- Distension of upper abdomen.
- Bilious vomiting.
- Visible gastric peristalsis.
- It is often associated with the Down's syndrome, and other congenital gut abnormalities.

Types

- *Neonatal type* – produces symptoms of intestinal obstruction.
- *Adult type* – presents after the age of 20. Presents with features of duodenal ulcer and bilious vomiting.

Those who wish to sing always finds a song.

Differential Diagnosis

- Duodenal atresia.
- Wilkies syndrome.

Investigations

- Plain X-ray abdomen shows double-bubble appearance.
- ERCP and Radioisotope study.
- Barium meal shows obstruction at 2nd part of duodenum.

Treatment

- Duodeno-duodenostomy—Ideal.
- Duodeno-jejunostomy.
- **Do not resect the ring.** Attempt at resection will lead to pancreatic fistula.
- G-J is not done.

ECTOPIC (ACCESSORY) PANCREATIC TISSUE

Sites

- Stomach wall.
- Small intestine.
- Meckel's diverticulum.
- Greater omentum.
- Splenic hilum.
  - In the bowel it may be in the submucus or intramuscular plane. It may precipitate intussusception.
  - About 30-33% contain islet of Langerhan cells. Often endocrine pancreatic tumour can arise from ectopic pancreas.
  - It may cause upper GI bleed.

PANCREATIC DIVISUM

It is failure of fusion of ventral pancreatic duct (Wirsung's duct is opening distally) with dorsal pancreatic duct (Santorini's duct is opening proximally).

PANCREATIC CALCULUS

Causes

- Chronic pancreatitis commonly due to dietary factors, familial, hyperparathyroidism.
- Commonly they are multiple and associated with or due to chronic pancreatitis.

Pathogenesis

Stricture of pancreatic duct and stasis of pancreatic secretion.

Types

a. **Calculi in the duct**:
  - Here parenchyma is still functioning and less severely affected.
  - Duct is dilated significantly (more than 3 mm) with multiple large stones in the duct along with multiple strictures.
  - Duct is having dilatation alternating with strictures—*chain of lake appearance.*
    - Plain X-ray abdomen shows stones placed horizontally at L_1-L_2 level.
    - U/S, ERCP. MRCP are other useful investigations.
    - Blood sugar should be checked.



Figs 14.48A and B: CT scan picture showing pancreatic ductal stones. Stones that are removed from the same patient are also shown. Patient underwent longitudinal pancreatico-jejunostomy.

Treatment

The duct is opened longitudinally and after removing all stones, side to side pancreatico-jejunostomy is done.

b. **Calculi in the Parenchyma**
  - Here multiple calcifications occur in the pancreatic parenchyma with pre-existing chronic pancreatitis. Gland is fibrosed and severely affected with less functioning capacity.
  - Plain X-ray, U/S, ERCP, MRCP are the diagnostic methods.

Treatment

- *Total pancreatectomy.*
- It is more likely to turn into carcinoma pancreas.

PANCREATIC ASCITES

- It can occur in chronic pancreatitis or as a complication of acute pancreatitis or in ruptured pseudocyst of pancreas or after pancreatic trauma (10%, in children trauma is the cause).
- It may be associated with pleural effusion which can be both sided but commonly on left side. Often pleural effusion and ascites may be massive. It is due *to internal pancreatic fistula*.
- Incidence is 1%. If not treated mortality is 30%.
- It is due to leakage from disrupted pancreatic duct or ruptured pseudocyst. Anterior disruption causes pancreatic ascites. Posterior disruption causes fluid to travel along oesophageal and aortic hiatus resulting in pleural effusion.
- Pancreatic ascites and fistula are common in pancreatitis due to alcohol intake. It is less common in pancreatitis due to biliary tract disease.
- U/S, very high amylase and protein levels in ascites fluid, ERCP to identify leak, CT scan are the essential investigations.
- Repeated ascitic tap; pleural tap; TPN; somatostatin or octreotide to reduce pancreatic secretion are tried as conservative therapy for 3 weeks. 50% respond to this therapy.
- If there is no improvement beyond 3 weeks, ERCP stenting of pancreatic duct is done initially. Then resection (better option) or drainage (jejunal loop Roux en Y anastomosis directly over disrupted duct) surgery is done. Pancreatic pleural effusion disappears once abdominal cause or ascites is corrected.

PANCREATIC FISTULAE

Types

External and internal fistulae.

***External fistulae*:**

Types

a. Low output fistulae < 200 ml.
b. High output fistulae >200 ml.
(*Note:* For other GI fistulae it is 500 ml)

Causes

- Whipple's operation.
- Pancreaticojejunostomy.
- Splenectomy.
- Colonic surgeries
- Trauma.
- After external drainage of the infected pseudocyst of pancreas.
- After percutaneous drainage of the pseudocyst.

Clinical features

- Patient is in a catabolic state.
- Skin excoriation.
- Electrolyte imbalance.
- Malnutrition.
- Sepsis.

Investigations

- CT scan.
- ERCP.
- Fistulogram.
- Amylase estimation of the discharge.

Treatment

Conservative treatment:

- Total parenteral nutrition.
- Zinc oxide cream for skin excoriation.
- Correction of electrolyte imbalance.
- Antibiotics.
- Octreotide.

Surgery

- Roux-en-Y anastomosis.
- Resection of fistula with pancreas.
- Endoscopic stenting of the pancreatic duct.

Internal fistulae

- Communicating pseudocyst.
- Pancreatic ascites.
- Pancreatic pleural effusion.
- Pancreatic-enteric fistulae.

Complications of pancreatic fistulae

- Septicaemia
- Malnutrition
- Bleeding due to erosion of vessels
- Electrolyte imbalance
- Severe skin excoriation

PANCREATIC ABSCESS

- 5% common.
- It can occur immediately after an attack of acute pancreatitis or in an existing pseudo cyst.
- Common in alcoholics and gallstone diseases.
- Mortality is 25%.

It is better to aim at good things and miss it, than to aim at a bad thing and hit it.

- *Pancreatic abscess* is collection of pus in lesser sac (intraabdominal) in relation to pancreatic surface which contains mainly pus with only less or no necrotic pancreas. It may slough off the pancreatic/splenic vessel wall to cause torrential haemorrhage. Abscess may be single or multiple (60%). It is commonly in head/body or tail. But often entire gland may be involved (25%). Abscess may rupture into viscera or extend into other part of the abdomen.

Clinical Features

- Persistent pain abdomen.
- Tender epigastric mass.

Commonest organism involved is *E. coli.*

Investigation

- Ultrasound and CT scan are diagnostic.
- CT guided FNA and Gram's staining and culture.

Treatment

- Antibiotics.
- Open surgical drainage with cysto-gastrostomy.
- U/S guided aspiration.
- *CT guided insertion of polythene catheter.*

Complications

- Septicaemia.
- Haemorrhage due to erosion of splenic vessels.
- Recurrent abscess formation.

PANCREATIC NECROSIS

It is diffuse or focal area of non viable parenchyma of pancreas, occurs during an attack of severe pancreatitis that is associated with peripancreatic fat necrosis. It occurs in 20% of acute pancreatitis.

Types

- Sterile necrosis is 60% of total pancreatic necrosis. Mortality here is 10%.
- Infected necrosis is 40% of total necrosis. Mortality here is 30-40%, very high. Risk of infection is 25% in one week of acute attack; 35% at the end of 2nd week; and 70% at the end of 3rd week.
- Necrosis extends to retroperitoneal fat, mesentery, retrocolic and perinephric areas.

Pathogenesis

- Premature activation of proteolytic enzymes.
- Intrapancreatic vessel thrombosis.
- Pancreatic microcirculation failure.
- Release of inflammatory mediators.

Mode of Infection

- Haematogenous.
- Reflux through ampulla.
- Mucosal translocation of bacteria.
- From the biliary tree.
- Lymphatic route.
- Transperitoneal spread.

Bacteria

- 65% are poly microbial.
- *E. Coli* is commonest.
- Others are – proteus, pseudomonas, klebsiella, staphylococci, streptococcus faecalis, enterococci, anaerobes, Clostridium welchii.

Diagnosis

- Clinical features.
- CT scan abdomen and CT guided FNA for Gram's staining and culture.
- CRP value - > 120 mg/litre; interleukin level; elastase level; urinary TAP assessment.

Treatment

- Antibiotics – imipenem, cefuroxime, ofloxacin, meropenem.
- Percutaneous drainage.
- Laparotomy, necrosectomy, debridement, saline wash, closure with tube irrigations/lavage.

Complications

- Septicaemia, ARDS, renal failure, MODS.
- Pancreatic fistula after surgery.
- Intra-abdominal abscess.
- Abdominal dehiscence, incisional hernia after surgery.

PANCREATIC TRAUMA

- It is rare because of its anatomical location - retroperitoneum.
- Its injury is usually associated with injuries to liver/duodenum/spleen/portal system/biliary system/kidney.
- Deep force in epigastrium may cause crushing of body of pancreas against vertebra – closed injury.
- Penetrating injury may cause direct sharp injury of pancreas.

Types

- Parenchymal contusion/laceration without duct disruption.

- Parenchymal injury with duct disruption.
- Complete transection of pancreas.
- Massive destruction of pancreatic head.

Classification

Pancreatic injury

Class I Capsular damage; minor parenchymal injury
Class II Transection of duct in body or tail – partial or complete
Class III Major duct injury in pancreatic head or intrapancreatic CBD injury

Duodenal injury

Class I Contusion, hematoma, partial thickness injury
Class II Full thickness duodenal injury
Class III Full thickness duodenal injury with
1. More than 75% circumference injury
2. Extrapancreatic CBD injury

Combined pancreatico duodenal injury

Type I Class I injury to both organs/class I injury of one organ with class II injury to other
Type II Class II injuries of both organs
Type III Class III injury to one organ with less severe injury to other
Type IV Class III injury to both organs

Features

- Pain in epigastrium.
- Features of associated injuries.
- Features of shock.
- Rise in serum amylase level is common.

Investigations

- CT scan is diagnostic.
- ERCP to confirm duct disruption.
- Assessment of blood loss and other injuries.

Treatment

- Commonly conservative with fluid management; blood transfusions; antibiotics; pain relief.
- Surgery is needed when there is –
  - Major ductal disruption.
  - Vascular injury.
  - Extensive injury to head.
  - Other organ injury.

Surgeries are

- Proper exploration and haemostasis.
- In neck transection, distal pancreatectomy with splenectomy.
- In injury to head, haemostasis and external drainage is done.
- Pancreaticoduodenectomy is done if there is major injury.
- Choledochojejunostomy is done if there is CBD injury.
- Different pancreatic drainage procedures are done to prevent sepsis and fistula.
- Portal system injury carries poor prognosis. It needs repair or intervening graft placement to control and maintain the continuity.

Prognosis

- Depends on type and class of injury and other associated injuries.

Complications

- Haemorrhage.
- Septicaemia.
- Pancreatitis – acute/recurrent.
- Pseudocyst formation.
- Pancreatic fistula.
- Pancreatic abscess.

CYSTIC LESIONS OF PANCREAS

Types

1. True pancreatic cysts:
   - Congenital.
   - Not premalignant.
   - Asymptomatic.
   - May be associated with cystic diseases of liver, kidney.
2. Pseudocyst of pancreas.
3. Cystic tumours of pancreas.
   a. Serous cystadenoma.
   b. Mucinous cystadenoma.
   c. Cystadenocarcinoma.
   d. Angioma.
   e. Cystic teratomas.
4. Hydatid cyst of the pancreas.

EXOCRINE PANCREATIC DISEASE

Causes

- Pancreatitis.
- Cystic fibrosis.
- Pancreatic resections.

No problem can stand the assault of sustained thinking.

Investigations

- *72 hours faecal collection* for estimation of daily faecal fat: In a person ingesting 100 gm of fat/day, if faecal excretion of fat is more than 7 gm/day, it signifies pancreatic insufficiency. It is the most sensitive and specific test. (Presence of neutral fat suggests pancreatic disease whereas split fat suggests small bowel disease.)
- *Secretin-cholecystokinin stimulation test* shows duodenal fluid normally contain more than 80 m Eq/L HCO_3^- and HCO_3^- greater than 15 mEq/30 minutes.
- *PABA excretion in the urine* after ingestion of bentinomide, if less than 50% it signifies pancreatic insufficiency.
- Serum trypsin level is low in pancreatic insufficiency.
- Pancreolauryl test.
- Triolin breath test.
- *Lundh test*—duodenal juice collected 2 hours after meal shows trypsin level > 8 mEq/ml. It is very low in chronic pancreatitis (Goran Lundh).
- Glucose tolerance test.

Treatment of Pancreatic Insufficiency

- Low fat diet.
- Pancreatin enteric coated tablets during meals.
- Cause is treated.

Self-assessment Questions

- Pathogenesis, clinical features and management of acute pancreatitis.
- Etiology of acute pancreatitis.
- Treatment of acute pancreatitis.
- Complications of acute pancreatitis.
- Ranson's prognostic criteria.
- Etiology, clinical presentations and management of chronic pancreatitis.
- Puestow's operation.
- Pancreatic calculi.
- Pseudocyst of pancreas.
- Courvoisier's law.
- Zollinger-Ellison syndrome.
- Gastrinomas.
- Serum amylase.
- Insulinomas.
- MRCP.
- ERCP.
- Grey Turner's sign.
- Carcinoma pancreas—clinical features and its management.
- Surgical jaundice.
- Obstructive jaundice.
- Hydro-hepatosis.
- Hepatorenal syndrome.

15

Retroperitoneal Space

Anatomy of retroperitoneum
Retroperitoneal fibrosis
Retroperitoneal swellings
Retroperitoneal tumours
Psoas abscess

ANATOMY OF RETROPERITONEUM

This is the space between the peritoneal cavity and posterior abdominal wall. It is bounded anteriorly by posterior parietal peritoneum; posteriorly by vertebral column, psoas muscles, quadratus lumborum muscle and tendinous portion of transversus abdominis muscles; superiorly by diaphragm; inferiorly by pelvic levator muscles.

Diseases of retroperitoneal spaces:
Retroperitoneal fibrosis
Retroperitoneal cysts
Retroperitoneal tumours
Retroperitoneal lymphomas
Retroperitoneal vascular diseases, e.g. aneurysms
Retroperitoneal trauma and haematoma
Retroperitoneal infection, e.g. psoas abscess, pyogenic abscess

Diseases of the specific retroperitoneal organs, e.g. adrenals, kidney.

RETROPERITONEAL FIBROSIS

- *Idiopathic type is called as* ***Ormond's disease*** which is associated with mediastinal fibrosis, Dupuytren's contracture, plantar fasciitis, Peyronie's disease, Riedel's thyroiditis, sclerosing cholangitis, mesenteric panniculitis, pseudotumour of the orbit and other fibromatosis. It is nonspecific inflammation of fibrofatty tissue in the retroperitoneum.



Fig. 15.1: Anatomy of retroperitoneal space.

- Patient presents with severe and persistent *back pain.*
- Diffuse fibrosis in retroperitoneum can compress both ureters leading to bilateral hydronephrosis and renal failure.
- Extravasation of urine, ascending lymphangitis, and autoimmune cause are the aetiologies.
- In 30% cases it is bilateral.
- It is like woody fibrous tissue which narrows ureters, vessels and nerves. Ureteric obstruction commonly in lower 1/3 causing dysuria, frequency, oliguria, renal failure. Venous and lymphatic oedema of limbs can occur.
- It may be localised or generalised. Generalised type may extend into duodenum, CBD and pancreas. It is not encapsulated but margin is well-demarcated.

The lesser the indication, the greater the complication.

- It can also cause vascular compression, both venous and arterial.
- Disease is progressive one.

Investigation

- U/S
- IVU - diagnostic:

Triad

1. Deviation of middle 1/3rd of ureter medially
2. Hydroureteronephrosis
3. Extrinsic ureteral compression

- Blood urea and serum creatinine.
- CT scan.

Treatment

- Steroid/tamoxifen therapy.
- Cystoscopic stenting of the ureters to prevent renal failure.
- Symptomatic treatment: If stenting fails, bilateral nephrostomy is done.
- Ureterolysis.
- Lateral repositioning of ureters.
- Omental wrap after ureterolysis.
- Vascular bypass graft for vascular encasement.

Other causes for retroperitoneal fibrosis

- Methysergide and beta blocker drugs
- Urine leak and collection in the space
- Haematoma, blood collection
- Advanced malignancy.

RETROPERITONEAL SWELLINGS

Types of retroperitoneal tumours (0.3 to 3%)

Benign:

- Retroperitoneal lipoma
- Retroperitoneal neurofibroma
- Benign tumours arising from the specific organs (like kidney, adrenals)

Malignant:

- Retroperitoneal liposarcoma, Leiomyosarcoma
- Retroperitoneal lymphoma (commonly NHL)
- Malignant tumours from specific organs
- RPLN secondaries with hard nodules

Features of the Retroperitoneal Mass

- It is usually large.
- Not moving with respiration.
- Nonmobile.
- Does not fall forward (confirmed by knee-elbow position).
- Deeply placed.
- Resonant on percussion (because of the bowel in front).



Fig. 15.2: Retroperitoneal tumour can attain very large size often. It causes deviation of ureter laterally often may invade the ureter. (In retroperitoneal fibrosis ureter is deviated medially). It may invade or encase the IVC also causing IVC obstruction with features of bilateral oedema feet, dilated lateral abdominal wall vein with upward direction flow of blood.

– In retroperitoneal cyst and sarcoma the swelling is smooth.
– In lymphoma it is nodular and firm.
– In aneurysm it is pulsatile (expansile pulsation) which will persist even in knee-elbow position.
– Confirmation is by U/S, CT scan, MRI.
– Most common retroperitoneal benign tumour is lipoma.
– Sarcoma (*commonest is liposarcoma 40%*) which attains a very large size, goes for myxomatous degeneration very early and is aggressive.

RETROPERITONEAL TUMOURS

- Retroperitoneal tumours may be associated with radiation; chemical exposure like vinyl chloride/thorium dioxide, familial Gardner's syndrome, familial retinoblastoma or familial neurofibromatosis. Tumour arises from fat, areolar tissue, vessels, nerves, muscle, fascia, lymph node and lymphatic systems. Sarcomas are commonly solid, can be cystic or mixed. Usually tumour develops a pseudocapsule. Spread mainly occurs through blood to lungs and often to liver. Nodal spread occurs rarely.

- Most patients have initial asymptomatic course with eventual presentation as *mass per abdomen*.
- *Rare presentations* are – GI bleeding; intestinal/urinary obstruction; neurological manifestations by compression or invasion of neurological systems by tumour. Iliac vein or IVC compression can cause lower limb varicosities and oedema.
- Commonly it is *mesenchymal origin – liposarcoma* (40%), leiomyosarcoma (25%), malignant nerve sheath tumour, fibrosarcoma. 55-60% of liposarcomas are low grade and well-differentiated.
- It can be germ cell tumour, lymphoma or primary adrenal tumour in young people.



Fig. 15.3: Retroperitoneal leiomyosarcoma, CT picture.

- CT abdomen (best and ideal) and pelvis and CT chest are essential investigations.
- *CT guided biopsy*; laparoscopic biopsy are needed. FNAC has got limited role.
- IVU shows laterally deviated ureter. Plain X-ray may show soft tissue shadow, obliterated psoas shadow, and often calcification.
- Histochemistry is essential in many suspicious types.
- *Surgery is the main modality* of therapy with wide excision; limited resection; debulking (controversial). Often it needs extensive surgical dissection; resection of adjacent bowel. Wide exposure is the key for successful surgery. Limiting factors are encasement of major vessels; invasion of ureters; extension into duodenum or pancreas; extensive involvement of mesentery and spread. *Complications are* – injury to major structures, bleeding, sepsis and leak.
- Post operative chemotherapy and radiotherapy are used as adjuvant method.



Fig. 15.4: Retroperitoneal tumour, on table finding. It was large and inoperable.

- Radiotherapy may be external beam RT.
- Intraoperative radiotherapy during surgical resection is possible alternate mode of therapy. Problems with retroperitoneal tumour are injury to kidney, bowel, liver and spinal cord.
- Preoperative intensity modulated RT (IMRT) is tried.
- Recurrent disease needs re-exploration but often difficult to do complete clearance.
- Mesna, adriamycin, ifosamide and dacarbazine (MAID) are the chemotherapeutic agents used.
- Germ cell tumour, lymphoma (NHL), adrenal tumours are treated accordingly.



Fig. 15.5A

Time neither subtracts nor divides, but adds to such a pace it seems like multiplication.



Fig. 15.5B



Fig. 15.5C

Figs 15.5A to C: Retroperitoneal tumour presenting as large mass abdomen with all features. CT pictures of the same patient.



Fig. 15.6: Retroperitoneal tumour showing encasement of major vessels. It becomes inoperable. Ureter, duodenum, intestines, kidney are other structures which may get infiltrated by tumour.



Figs 15.7A and B: Retroperitoneal lymph node mass. It could be tuberculosis/lymphoma / secondaries / autoimmune lymph node enlargement.

- *Prognosis* depends on –
  - Tumour grade – low or high;
  - Resectability;
  - Invasion into organs, veins, nerves;
  - Size of tumour < 5 cm or > 5 cm or > 10 cm;
  - Deep location;
  - Nonliposarcoma in histology – poor prognosis;
  - Recurrent disease;
  - Distant spread.
  - Tumour grade and completeness of resection without distant spread are important prognostic factors.
  - RP tumours has got overall 40% recurrence rate. Overall survival is 1½ - 2 years.

Features of retroperitoneal sarcomas

- Mass per abdomen
- Pain in the back and compressive features.

- GIT obstruction especially by leiomyosarcoma
- Compression over the ureter causing hydronephrosis
- Compression over the major veins causing varicose veins
- Arterial compression features are not common
- Liver and lung secondaries can occur
- CT guided biopsy is ideal method of investigations

Treatment of retroperitoneal tumours

- *Wide local excision*. Often requires removal of adjacent structures like colon, kidney, and spleen
- *Debulking operation* as a palliative
- *Enucleation* through pseudocapsule. It has got high recurrence rate
- *Radiotherapy* either brachytherapy or external beam radiotherapy or intraoperative RT
- *Chemotherapy* using adriamycin
- Retroperitoneal NHL is treated by *chemotherapy*



Fig. 15.8: Large pelvic retroperitoneal tumour.

PSOAS ABSCESS

- Abscess in the psoas region in the iliac fossa, is commonly due to tuberculosis of spine (T 10) and lymph nodes, retroperitoneal structures, lower intercostal region.
- It can also be a pyogenic abscess.

Clinical Features

- Back pain, fever, spinal tenderness, para spinal spasm and restricted spine movement.
- Swelling in iliac fossa which is smooth, nontender, nonmobile, not moving with respiration.
- When it extends across the groin and below the inguinal ligament, it is ***cross fluctuant*** across the inguinal ligament.
- Patient has typical *psoas muscle spasm* in which patient is able to flex his hip but finds it difficult to extend.

Swellings which are cross fluctuant

Psoas abscess
Ranula
Compound palmar ganglion
Bilocular hydrocele



Fig. 15.9: Psoas abscess.

Differential Diagnosis

a. Iliac artery aneurysm.
b. Ovarian cyst in females.
c. Soft tissue tumours and cysts in the iliac region.
d. Hernia.



Fig. 15.10: CT picture of large psoas abscess.

> *A man carries success or his failure with him; it does not depend on outside conditions.*



Fig. 15.11: On table finding of psoas abscess.







Figs 15.12A to C: Bilateral large psoas abscess – CT picture. Drainage and placement of Malecot catheters for the same. Note the location of incisions. It is obliquely placed incision above the lateral aspect of groin with extraperitoneal approach.

Investigations

- X-ray spine and chest.
- Mantoux test.
- U/S abdomen.
- ESR.
- Peripheral smear.
- CT scan.

Treatment

- Antituberculous drugs are started—INH, ethambutol, rifampicin, pyrazinamide.
- Under G/A through lateral loin incision, the psoas region is reached extraperitoneally. The pus is drained and collected for culture and sensitivity, AFB, culture. The wound is closed. All caseating material and diseased parts of vertebra should be removed.
- Only lateral approach is advised. In thoracic region —*anterolateral decompression* with *costo- transversectomy* with *bone grafting* is the treatment.

Note: Posterior approach, i.e. laminectomy—**not advised.**

Self-assessment Questions

- Psoas abscess.
- Retroperitoneal mass—features and differential diagnosis.
- Retroperitoneal fibrosis.
- Ormond's disease.

16

Differential Diagnosis of Mass Abdomen

In a patient presenting with mass abdomen, generally following clinical features should be assessed carefully.

- *Pain:* Site, nature, aggravating or relieving factors, duration of pain, referred pain.
- *Vomiting*: Type, content, haematemesis, relation to food, frequency.
- *Jaundice*: It is an important factor in relation to liver, gallbladder or pancreatic masses.



Fig. 16.1: Obstructive jaundice in a patient with carcinoma head of pancreas. Note the sclera for discolouration. Severe itching is common in these patients.

- *Bowel habits*: Constipation, diarrhoea, bloody diarrhoea, furious diarrhoea, tenesmus.
- Decreased *appetite* and *weight*.
- *Inspection of the mass*: Anatomical location, margin, surface, movement with respiration.



Fig. 16.2: Abdomen should be inspected by exposing from nipple level to knee level. Inspection is done from foot end and from right side.



Fig. 16.3: Superior venacaval obstruction causing dilated veins in the neck, chest wall and shoulder. Note the neck swelling extending into the mediastinum.

> *Diagnosis of diseases is often easy; often difficult and often impossible.*— Peter Mere Latham





Figs 16.4A to C: Inferior vena caval obstruction causing dilated veins over the lateral aspect of the flank with flow of blood upwards.



Fig. 16.5: Abdomen mass should be palpated clinically properly.

- *Palpation of the mass:* Site, extent, surface, tenderness, consistency, movement with respiration, mobility, borders, plane of the swelling (by leg raising test), presence of other masses.
- *Percussion* is an important aspect of examination in case of an abdominal mass. Percussion over the mass is important to predict the anatomical location of the mass. If mass is dull, then it is in the anterior abdominal wall or in front of the bowel intraabdominally like liver, spleen, gallbladder. If the mass is with a impaired resonant note, then the mass is arising from the bowel like stomach, colon, small bowel. If the mass is resonant on percussion, then the mass is probably in the retroperitoneal region. Other than this, liver dullness, free fluid in the abdomen should be elicited during percussion.



Fig. 16.6: Percussion over the mass is absolute need to find out the plane of the mass. Anterior masses are dull on percussion; posterior masses are resonant and mass from bowel has impaired resonance.



Fig. 16.7: Digital examination of rectum is a must in patients with mass abdomen to look for secondaries, possible primary and often to assess the mass itself.

- *Per rectal examination*: It is done to look for any secondaries in recto-vesical pouch, primary tumour or relation of lower abdomen masses (pelvic masses).
- *Pervaginal examination* is done to assess pelvic masses.



Fig. 16.8: Different quadrants in the abdomen. They are four in number formed by two lines – one is vertical midline through the umbilicus; another is horizontal line passing through the umbilicus. Quadrants are – right upper, right lower, left upper and left lower.



Fig. 16.9: Regions in the abdomen.

Regions in the abdomen

1. Right hypochondrium
2. Epigastric region
3. Left hypochondrium
4. Right lumbar region
5. Umbilical region
6. Left lumbar region
7. Right iliac fossa
8. Hypogastrium
9. Left iliac fossa

Abdomen is divided into nine regions by four lines.

1. Upper horizontal or *transpyloric line* is mid-way between the umbilicus and xiphisternum.
2. Lower horizontal line is *transtubercular line* at the level of two tubercles on the iliac crest.
3. Right vertical line is the line through the midpoint of right anterior superior iliac spine and pubic symphysis.
4. Left vertical line is the line through the midpoint of left anterior superior iliac spine and pubic symphysis.

MASS IN THE RIGHT HYPOCHONDRIUM

Liver Palpable as Mass in Right Hypochondrium

- It is horizontally placed.
- It usually moves with respiration.
- Upper border is not felt.
- It is dull on percussion. (This dullness continues over liver dullness above.)
- Fingers can not be insinuated under right costal margin.

> *As beds and couches vary in height, the examiner to palpate the abdomen, if need be, must sit on a suitable chair or even kneel upon the floor, no matter how undignified this may appear.* — Charles P


Pancreatic mass
Aortic aneurysm
Kidney mass
Intussusception
Mass in R.I.F
Pelvic mass
Left lobe liver mass
G/B mass
Pyloric mass
Pseudocyst of pancreas

Fig. 16.10: Mass abdomen.


12
10
1
2
3
11
3
5
4
8
6
7
9
1. Stomach mass.
2. Pancreas body mass.
3. Colonic mass.
4. Mesenteric cyst.
5. Omental mass.
6. Carcinoma caecum.
7. Appendicular mass.
8. Ileocaecal tuberculosis
9. Pelvic mass.
10. Gallbladder.
11. Umbilicus.
12. Liver.

Fig. 16.11: Different causes of mass abdomen.

Conditions where liver gets enlarged:

1. *Soft, smooth, nontender liver:*
   - *Hydrohepatosis*—It is due to obstruction of CBD causing dilatation of intrahepatic biliary radicles.
   - Congestive cardiac failure.
   - Hydatid cyst of the liver—Here mass is well-localised in the liver with typical hydatid thrill. *Three finger test:* Three fingers are placed over the mass widely. When central finger is tapped fluid movement is elicited in lateral two fingers.
2. *Soft, smooth, tender liver:*
   - *Amoebic liver abscess:* Here liver often gets adherent to the anterior abdominal wall and will not move with respiration. Intercostal tenderness, right sided pleural effusion are common.

Amebic liver abscess

- It is due to Entameba histolytica infestation
- It is more common in alcoholics and cirrhotics
- Single abscess is common – 70%; common in right posterosuperior lobe- 80%
- Chocolate colored Anchovy sauce pus is classical
- Secondary infection can occur – 30% - life threatening due to septicaemia
- It can be acute or chronic; both mimics hepatoma
- Rupture into lungs – commonest site of rupture
- Most dangerous rupture is into pericardium – left lobe abscess
- Liver failure can develop in cirrhotic patient

Features

- Common in males (20:1), fever, pain, intercostal tenderness, tender liver
- Mimics cholecystitis, subphrenic abscess, hepatoma
- Total count, LFT, prothrombin time, US abdomen are relevant investigations
- Chest X-ray may show left sided sympathetic pleural effusion
- CT scan to differentiate from hepatoma
- *Treatment* – drugs like metronidazole, injection dihydroemetine, chloroquin tablets, diloxanate furoate; U/S guided aspiration after controlling prothrombin time using inj vitamin K or FFP; if recurs percutaneous guided drainage using pigtail catheter, or open laparotomy and drainage with placement of Malecot's catheter

3. *Hard, smooth liver:*
   - *Hepatoma* (HCC): Here a large, single, hard nodule is palpable in the liver. But occasionally there can be multiple nodules when it is multicentric. Rapidly growing tumour can be soft also. Hepatoma often can also be tender due to tumour necrosis or stretching of the liver capsule. Vascular



Fig. 16.12: Hepatocellular carcinoma/hepatoma. It is common in right lobe, unicentric, attains large size.

bruit may be heard over the liver during auscultation. It mimics amoebic liver abscess in every respect.

- Solitary secondary in liver.

Hepatoma/hepatocellular carcinoma/HCC

- Common aetiologies are aflatoxins, hepatitis B and hepatitis C virus infection, alcoholic cirrhosis, haemochromatosis, smoking, hepatic adenoma, clonorchis sinensis, polyvinyl chloride
- Unicentric and right lobe involvement is more common
- Fibrolamellar variant is common in left lobe, not related to hepatitis or cirrhosis without AFP level raise. There are increased serum vitamin B_{12} binding capacity and neurotensin levels.
- It can be multifocal/indeterminate/spreading/expanding – *Okuda classification*
- Presents as large smooth hard liver mass – later jaundice, fever, pain and tenderness, ascites and bruit over mass
- Spreads to lymphatics, blood and direct spread
- Mimics amebic liver abscess, secondaries, hydatid cyst, polycystic liver disease
- LFT, CT scan, raised AFP, liver biopsy (only needed) are the investigations
- Hemihepatectomy in early operable growth is the treatment
- Hepatic artery ligation/intraarterial chemotherapy/chemoembolisation/percutaneous ethanol or acetic acid injection/radiofrequency ablation/chemotherapy using adriamycin, carboplatin, gemcitabine – are palliative procedures

4. *Hard, multinodular liver:*
   - Multiple secondaries in liver: Here hard nodules show umbilication which is due to central necrosis.
   - Macronodular cirrhotic liver.



Figs 16.13A and B: Multiple secondaries in liver with umbilication. It is due to central necrosis. Secondaries are the commonest malignant tumour of the liver. It could be from GIT or extra-gastrointestinal sites like from breast, lungs, melanoma, thyroid, prostate, kidneys, etc. Patient with liver secondaries has got poor general condition. It should be differentiated from multicentric hepatoma. It is usually treated by palliative chemotherapy. Solitary secondary from carcinoma colon can be removed by segmentectomy. It has got poor prognosis.

Palpable Gallbladder in Right Hypochondrium

- It is smooth and soft (except in carcinoma gallbladder).

After every end is a new beginning and every beginning has an end.

- It is mobile horizontally (side-to-side).
- It moves with respiration.
- It is located right of the right rectus muscle, below the right costal margin or below the lower margin of the palpable liver.
- It is dull on percussion.

Conditions where gallbladder is palpable:

1. *Soft, nontender gallbladder*:
   - Mucocele of the gallbladder.
   - Enlarged gallbladder in obstructive jaundice due to carcinoma head of the pancreas or periampullary carcinoma or growth in the CBD.
2. *Hard gallbladder:*
   - Carcinoma gallbladder.
3. Tender gallbladder—Empyema GB.

Other Masses in the Right Hypochondrium

- *Peri cholecystic inflammatory mass*: It is tender, smooth, firm or soft, nonmobile, intraabdominal mass often with guarding.
- *Kidney mass arising from upper pole of the kidney*: It may be due to renal cell carcinoma or hydronephrosis.



Fig. 16.14: Large upper abdomen mass – could be liver mass, pancreatic mass, retroperitoneal mass.

MASS IN THE EPIGASTRIUM

Palpable Left Lobe of the Liver

- It is in the epigastric region.
- Its upper border cannot be felt.
- It moves with respiration.
- It extends towards left hypochondrium.
- It is dull on percussion.

Conditions where left lobe of the liver is palpable:
- Hepatoma
- Amoebic liver abscess in left lobe
- Left lobe secondaries
- Hydatid cyst of the left lobe

Features of Stomach Mass



Figs 16.15A to E: Carcinoma pylorus causes gastric outlet obstruction with palpable mass above the umbilicus. Carcinoma body of stomach mainly presents as loss of appetite and decreased weight with horizontally placed stomach mass. Carcinoma from fundus of the stomach presents as mass abdomen with loss of appetite and weight. Carcinoma OG junction presents as dysphagia. Carcinoma stomach is one of the common causes of secondaries in liver.

- It is located in the epigastric region.
- It moves with respiration. It is intraabdominal.
- It is resonant or impaired resonant on percussion.
- Mass may be better felt on standing or on walking.
- Mass is often mobile, unless it gets adherent posteriorly.
- In pylorus mass, all margins are well felt which is mobile with features of gastric outlet obstruction.
- Mass from the body of the stomach is horizontally placed without any features of obstruction.
- Mass from the upper part of the stomach near the O-G junction causes dysphagia.
- Mass from the fundus of the stomach is in the upper part of the epigastric region towards left side.
- Carcinoma stomach is nodular and hard. It is commonest cause for stomach mass.
- Leiomyoma of stomach is smooth and firm.

Management of gastric carcinoma

- Early growth – pylorus – lower radical gastrectomy with removal of tumour, proximal 5 cm clearance, nodal clearance, greater and lesser omentum, distal pancreas and spleen (now not regularly removed; it is removed to clear splenic nodes – one of the node stations) and Billroth II anastomosis or Roux –en – Y anastomosis is done. Postoperatively adjuvant chemotherapy should be given – 5 fluorouracil, mitomycin, epirubacin, cisplatin
- Growth in body, proximal growth, diffuse carcinoma and generalized linitis plastica are the indications for total radical gastrectomy with oesophagojejunal anastomosis.
- Neoadjuvant chemotherapy in advanced gastric cancer prior to surgery and later gastrectomy
- Instillation of mitomycin C impregnated charcoal intraperitoneally to control lymphatic disease (Japan)
- Palliative procedures like palliative partial gastrectomy, anterior gastrojejunostomy, Devine's exclusion gastrectomy, luminal stenting in proximal inoperable growths, chemotherapy are used in inoperable cases
- In early carcinoma proper lymph nodal clearance is important.

Pseudocyst of the Pancreas

- Mass in the epigastric region. It is smooth, soft. It can be tender if it is infected.
- It does not move with respiration.
- It is not mobile.
- It has got transmitted pulsation. It is confirmed by placing the patient in knee-elbow position.
- Lower border is well felt. Upper border is not clear.
- It is resonant on percussion.
- *Baid test*: As the stomach is pushed in front, Ryle's tube when passed, can be felt per abdomen on palpation.



Fig. 16.16: Pseudocyst of pancreas – CT scan picture.

Investigations for pseudocyst of pancreas–	Indications for intervention–
• Ultrasound – commonly done procedure • CT scan, ideal and choice • LFT, serum amylase, prothrombin time • ERCP to find out communications • Barium meal – not done now – shows widened vertebro gastric angle	• Size more than 6 cm • Formed thick-walled pseudocyst • Infected pseudocyst
Interventions	**Complications**
• Roux – en Y cysto jejunostomy is ideal • Cystogastrostomy – Jurasz procedure – commonly done • Cystoduodenostomy • Cystogastrostomy with external drainage if infected – Smith operation • Endoscopic stenting • Laparoscopic cystogastrostomy – popular – safer • Guided aspiration helps but high recurrence rate of 70%	• Rupture – 3% • Infection – 20% • Bleeding – torrential 7% • Cholangitis

The same beam of light can illuminate two objects and produce two different effects.

- Acute fluid collection – just fluid collection
- Acute pseudocyst with thin wall
- Chronic pseudocyst – thick walled
- Pseudopseudocyst – inflammatory mass of bowel, omentum, etc after acute pancreatitis mimics pseudocyst

Cystadenocarcinoma of the Pancreas

Mass is smooth, firm, does not move with respiration, nonmobile, resonant on percussion. Patient complaints of back pain.

Colonic Mass

- It is due to carcinoma of transverse colon.
- It is mobile, horizontally placed, nodular, hard mass which does not move with respiration. Caecum will be dilated and palpable.
- It is resonant or impaired resonant on percussion.
- Patient will be having bowel symptoms, loss of appetite and decreased weight.

Para-aortic Lymph Node Mass

- Mass in the epigastric region which is deeply placed, nonmobile, not moving with respiration.
- It is vertically placed, above the level of the umbilicus and resonant on percussion.
- Causes for enlargement are: *Secondaries, lymphomas* or *tuberculosis.*

Aortic Aneurysm

It is smooth, soft, pulsatile (expansile pulsation which is confirmed by placing the patient in knee-elbow position).

It is vertically placed above the level of the umbilicus, nonmobile, not moving with respiration and resonant on percussion.

MASS IN THE LEFT HYPOCHONDRIUM

Enlarged Spleen

- Spleen has to enlarge three times to be palpable clinically.
- It enlarges towards the right iliac fossa from left costal margin.
- It moves with respiration, mobile, obliquely placed, smooth, soft or firm, with a notch on the anterior edge which is directed downwards and inwards.
- Fingers can not be insinuated over the upper border.
- *"Hook sign" is positive*, i.e. one can not insinuate the fingers under the left costal margin.
- It is dull on percussion.



Fig. 16.17: Method of palpating spleen.



Fig. 16.18: Hepatosplenomegaly is the common condition (clinical entity). It is due to macronodular cirrhosis with portal hypertension, lymphoma, autoimmune diseases, congestive cardiac failure, hepatoma with portal hypertension, haemolytic diseases, etc. There may be ascites, supraclavicular palpable lymph node and pleural effusion (right-sided).

Left Sided Colonic Mass

- It is mobile, nodular, resonant.
- It does not move with respiration.
- It is commonly due to carcinoma colon.

Left Renal Mass from Upper Pole of any Cause

It has got features of renal mass.

Left Sided Adrenal Mass

- It does not move with respiration. It is not mobile.
- It is deeply placed mass. Often it crosses the midline.
- It is resonant on percussion. It mimics kidney mass.

Mass Arising from the Tail of the Pancreas

Clinical features are same as other pancreatic masses. Causes are pseudocyst in tail of the pancreas and cystadenomas.

MASS IN THE LUMBAR REGION



Fig. 16.19: Kidney should be palpated bimanually with two hands. Ballotability also should be checked.





Figs 16.20A and B: Renal (Kidney) punch. Renal angle should be palpated for tenderness. Renal angle is junction of 12th rib and erector spinae. It is on percussion normally resonant as it is occupied by colon. It is replaced by kidney in kidney enlargement. Renal angle should be inspected, palpated and percussed in sitting position from behind.

Palpable Kidney Mass

- There is fullness in the loin which is better observed in sitting position.
- Mass moves with respiration. It is vertically placed.
- It is bimanually palpable. It is ballotable.
- Renal angle is dull on percussion (normally it is resonant due to colon).
- There is a band of resonance in front due to reflected colon.
- It does not cross the midline.

Conditions Where Kidney gets Enlarged

Hydronephrosis:

- It is smooth, soft, lobulated, nontender mass, non-mobile.

Pyonephrosis:

- History of throbbing pain in the loin, pyuria and fever with chills.
- It is smooth, soft and tender kidney mass, nonmobile.

Polycystic kidney:

- History of loin pain and haematuria.
- Hypertension, anaemia and features of renal failure.
- Usually bilateral. But one side can present early than on the other side.
- Lobulated smooth surface.

Renal cell carcinoma:

- History of mass in the loin, haematuria, fever and dull pain.
- Mass is nodular and hard.
- It does not cross the midline.
- Initially mobile; eventually it infiltrates gets fixed and becomes nonmobile.

Mass from the Ascending Colon on Right Side or Descending Colon on Left Side

- History of altered bowel habits with decreased appetite and weight.
- Mass is nodular, hard which does not move with respiration and is not ballotable.
- It is resonant or there is impaired resonance on percussion.
- Renal angle is resonant.
- Proximal dilated bowel may be palpable.

Adrenal Mass

- It is nodular and hard.
- It does not move with respiration.

Life is an echo; give the best and get a great deal back.

- It is not mobile and often crosses the midline.
- It is felt on deep palpation.
- It is resonant in front.
- It is not ballotable.

Retroperitoneal Tumours

- They are not mobile, resonant and do not fall forward in knee-elbow position.
- They are deeply placed mass which are usually smooth and hard.
- They may be retroperitoneal sarcomas or teratomas or lymph node mass.



Fig. 16.21: Palpation of mass in knee elbow position. Mobility and falling forward should be confirmed in knee elbow position.



Fig. 16.22: Retroperitoneal tumour.

Retroperitoneal Cysts

They are *smooth and soft* with the same features as retroperitoneal tumours.

Cystic lesions in the abdomen

- Mucocele/empyema of gallbladder
- Pseudo-cyst of pancreas
- Hydatid cyst of liver
- Congenital nonparasitic cyst of liver
- Hydronephrosis
- Mesenteric cyst
- Ovarian cyst
- Omental cyst
- Aneurysm
- Retroperitoneal cyst
- Cystadeno carcinoma of ovary
- Loculated ascites

MASS IN THE UMBILICAL REGION

Usual masses are:

- Mesenteric cyst
- Omental cyst
- Ovarian cyst (pedunculated)
- Small bowel tumours
- Extension of masses from other region
- Transverse colon mass
- Mass in the body of pancreas
- Mesentery mass
- Lymph node mass – secondaries (primary from GIT, testis, ovary, melanoma)/lymphoma/tuberculosis
- Retroperitoneal tumour

Mesenteric Cyst

- *Tillaux triad:*
  1. Soft intraabdominal umbilical mass.
  2. Mobile in the direction perpendicular to the attachment of the mesentery.
  3. Resonant mass.
- May precipitate intestinal obstruction, volvulus.

Omental Cyst

- It is smooth, soft and nontender.
- It moves with respiration. It is mobile in all directions.
- It is dull on percussion.

Small Bowel Swellings

- Small bowel lymphomas.
- Small bowel carcinomas.
- Intussusception.

Intussusception

- Mass in umbilical region usually towards left and above the umbilicus.
- Occasionally towards right side.
- Mass is intraabdominal which is *sausage shaped*, with concavity towards umbilicus, well-defined, smooth, firm and mobile.
- Mass does not move with respiration.
- Mass contracts under palpating fingers.
- Often mass disappears and reappears.
- Mass is resonant or there is impaired resonance on percussion.
- *"Red currant gelly"* stool with features of intestinal obstruction may be present.

MASS IN THE RIGHT ILIAC FOSSA



Fig. 16.23: Mass in right iliac fossa. All possible differential diagnosis should be considered and clinically analyzed. Common masses are appendicular mass; carcinoma caecum; ileocaecal tuberculosis; lymph node mass; ameboma.

- Appendicular mass or abscess
- Carcinoma caecum
- Ileocaecal tuberculosis
- Amoeboma
- Psoas abscess
- Lymph node mass either mesenteric or external Iliac lymph nodes
- Bony swellings
- Ectopic kidney
- Undescended testis (Abdominal)
- Actinomycosis
- Crohn's disease
- Iliac artery aneurysm
- Ovarian swelling-ovarian cyst
- Tubo-ovarian mass
- Uterine mass like pedunculated fibroid

Appendicular Mass

- It is *smooth, firm, tender mass* in the right iliac fossa.
- It is not mobile. It does not move with respiration.
- It is *resonant on percussion*. It is well-localized mass with distinct borders.

Appendicular Abscess

It is *smooth, soft, tender and dull mass* in the right iliac fossa with indistinct borders.

Carcinoma Caecum

- It is nodular, hard, mass in the right iliac fossa.
- It does not move with respiration.
- It is mobile but mobility may be restricted once it gets adherent to psoas muscle.
- Mass is resonant or there is impaired resonance on percussion.
- Often features of intestinal obstruction may be present.

Ileocaecal Tuberculosis

- Mass in the right iliac fossa which is smooth, hard, resonant and nontender.
- It does not move with respiration and has restricted mobility.
- Caecum may be *pulled up* to lumbar region due to fibrosis.

Amoeboma

- History of dysentery with pain in the right iliac fossa.
- Smooth, hard, well-defined mass in the right iliac fossa which is nonmobile.
- It may or may not be tender.

Psoas Abscess

- It is localized, smooth, soft, nonmobile mass in the right iliac fossa.
- *Psoas spasm* (flexion of the hip joint) is typical.
- Spine may show *gibbus, tenderness, para spinal spasm*. Spinal movements will be restricted.

MASS IN THE LEFT ILIAC FOSSA

Carcinoma sigmoid or descending colon
Bony masses
Ovarian/uterine masses
Psoas abscess
Ectopic kidney
Lymph node mass
Undescended testis

It's your attitude, not your aptitude which determines your altitude in life.

MASS IN THE HYPOGASTRIUM

Bladder Mass

- It is in the midline. It is dull on percussion. Lower border is not felt.
- It can be mobile in horizontal direction. Mass reduces in size after emptying the bladder. It can be felt on per-rectal examination.
- It is either carcinoma bladder (common) or leiomyoma or sarcoma bladder.

Uterine Mass

- It is midline mass which is smooth, hard.
- Lower border is not felt which extends in to the pelvis.
- It is felt on pervaginal examination.

Ovarian Mass

Pelvic soft tissue mass.

In all lower abdomen masses P/R and or P/V is a must.

*In all regions **parietal masses** can occur:*

- Benign and malignant soft tissue tumours.
- Common, is lipoma.
- Fatty hernia of linea alba.
- Desmoid tumour.
- Parietal wall abscess.

Carnett's Test

The patient, in lying down position, is asked to lift both legs off the bed with knee extended. This puts the abdominal muscles into contraction. Intra-abdominal mass becomes less prominent, parietal mass persists as same, but becomes less mobile.



Fig. 16.24: Looking for minimal ascites in knee elbow position – Puddle sign.

Investigations for Mass Abdomen

- Haematocrit, liver function tests, renal function tests, stool/urine examination.
- Ultrasound abdomen.
- Endoscopies-gastroscopy-colonoscopy-ERCP-MRCP.
- Barium studies-Barium meal-Barium enema- Barium meal follow through.
- CT scan-MRI.
- Endosonography.
- Ascitic tap.
- Diagnostic laparoscopy.
- U/S guided/CT guided biopsy.
- IVU/RGP/Cystoscopy/Isotope renogram.
- Exploratory laparotomy.

Note:

- Hard mass in the abdomen is commonly malignant
- Firm mass may be tuberculous, lymphoma or many benign conditions
- Soft masses are hydronephrosis, pseudocyst, mesenteric cyst, omental cyst, and loculated ascites
- In tuberculosis abdomen may be doughy due to thickened parietal peritoneum or omentum
- It is difficult to elicit fluctuation in the abdomen as mass can not be fixed properly
- Plane of the swelling should be checked by leg raising/head raising test/Valsalva maneuver/knee elbow test
- Bimanual palpation, ballotability, renal angle inspection, palpation and percussion should be done in case of renal mass
- Intrinsic mobility should be checked. Different mobilities/movements are — gallbladder shows side to side; stomach lateral; ovarian mass – all over; mesenteric cyst – right angle to line of mesentery; transverse colon mass – vertical; small bowel mass all over; appendicular mass/pancreatic mass/nodal mass (para-aortic)/retroperitoneal mass do not show any mobility; cystadenocarcinoma of pancreas may show false mobility (*tree top mobility*)
- Percussion is very important method of examination to find out the anatomical plane of the mass. Mass in front of the bowel like liver/spleen/gallbladder/parietal mass are dull on percussion. Mass from the bowel is resonant on percussion like from stomach, small bowel and colon. Retroperitoneal masses like cyst, sarcoma, nodal mass, aneurysm, pancreatic mass are resonant on percussion

- Succussion splash and auscultopercussion tests are done for gastric outlet obstruction in pyloric stenosis
- Digital examination of rectum (P/R) and left supraclavicular examination for nodes is a must. PR is done to see Blumer shelf secondaries in recto vesical pouch. Pervaginal examination should be done in pelvic mass in females
- Bladder should be emptied while examining pelvic mass
- Bimanual examination is done often under general anaesthesia in case of pelvic mass
- Auscultation for bruit depends on condition and location of mass – over epigastrium, over liver
- Other relevant systemic examination is a must in examination of mass abdomen – respiratory system, skeletal and neurological systems

Mass that appears and disappears

- Pseudocyst of pancreas (communicating)
- Hydronephrosis (intermittent)
- Choledochal cyst
- Intussusception

Open confession is good for the soul.

17

Abdominal Wall and Umbilicus

> ***Why do they meet this most unfortunate and lamentable fate? Have these vessels committed some great crime, that you, O Nature, a just and provident mother to all other parts of the body, have become a step-mother to these alone, so that they deserve to be visited with an affliction so dire, a punishment so severe as wasting and death? Did not the vein continuously supply blood to the fetus? Did not the arteries give life to it? Were they not the means of bestowing increase and nutrition upon the fetus?***
>
> **—Girolamo Fabrizio (Fabricius ab Aquapendente),** 1649

Diseases of the umbilicus
Omphalitis
Umbilical granuloma
Anomalies of vitello-intestinal duct
Umbilical sinus
Umbilical adenoma
Umbilical fistula
Patent urachus
Burst abdomen
Abdominal wall tumours
Desmoid tumour
Exomphalos
Gastroschisis
Rectus sheath haematoma
Abdominal wall abscess
Meleney's progressive synergistic bacterial gangrene of abdominal wall

DISEASES OF THE UMBILICUS

1. **Inflammations:**
   - Omphalitis.
   - Umbilical granuloma.
   - Pilonidal sinus.
2. **Fistulas:**
   a. *Faecal*
      - Patent vitello-intestinal duct.
      - Neoplastic ulceration.
      - Tuberculosis of peritoneum.

   b. *Urinary*—Patent urachus.
3. **Neoplasms:**
   a. *Benign*
      - Adenoma (Raspberry tumour).
      - Endometrioma.

   b. *Malignant*
      - Primary (rare).
      - Secondary carcinoma—Sister Joseph's nodule through lymphatics of the round ligament, primary being in the stomach, colon, ovary, uterus, breast (often blood spread).
4. **Umbilical hernias.**
5. **Umbilical calculus (Umbolith**).



Fig. 17.1: Periumbilical pigmented lesion—could be melanoma.

OMPHALITIS

It is inflammation of the umbilical cord.



Fig. 17.2: Omphalitis (Umbilical infection).

Causes

- Ligation of the umbilical cord without aseptic precautions.
- Poor asepsis and umbilical hygiene during delivery and after birth.

Bacteria

- Staphylococci, streptococci.
- Gram-negative organisms.
- *Clostridium tetani* causing neonatal tetanus.

Features

- Infection may spread along the hypogastric vessels into the abdominal wall causing abdominal wall abscess.
- Infection may spread into the peritoneum causing peritonitis.
- In severe cases, septicaemia can occur.
- Umbilical granuloma can occur once infection gets localized.
- Purulent discharge with red, swollen umbilicus.



Fig. 17.3: Umbilical sepsis with foul smelling discharge.

Investigations

- Culture study of discharge.

Treatment

- Antibiotics.
- Drainage of the abscess.
- Aseptic precautions while ligating the cord will prevent the chances of umbilical sepsis.
- Excessive granulation tissue must be removed surgically or by cautery (commonly) using trichloroacetic acid or silver nitrate or copper sulphate in small quantity.

Complications

- Abdominal wall abscess
- Septicaemia
- Peritonitis
- Umbilical granuloma, umbilical hernia
- Neonatal tetanus
- Portal vein thrombosis and portal hypertension
- Neonatal jaundice due to cholangitis

UMBILICAL GRANULOMA

- It is due to chronic infection of the umbilical cicatrix, causing the granulation tissue to pout, leading to the formation of umbilical granuloma.
- It occurs in any age group, but common in infants and children. Presents as umbilical discharge with tender, red, swelling protruding from the umbilicus which bleeds on touch.
- It has to be differentiated from the anomalies of vitello-intestinal duct. It also mimics umbilical adenoma.

Treatment

- Antibiotics, application of silver nitrate and dry dressings.
- Occasionally might require excision of granuloma or umbilectomy (rarely).

ANOMALIES OF VITELLO-INTESTINAL DUCT

1. May remain completely patent, forming a *intestinal fistula*.
2. Only a small portion near the umbilicus may remain patent forming discharging *umbilical sinus*. Often the mucosa of this retained portion (epithelial lining) protrudes or evertes to form *umbilical adenoma*.
3. Duct is closed on either side, but the intervening portion may remain as a *intra-abdominal cyst*.

Umbilical black eye is Cullen's sign seen in acute pancreatitis and ruptured ectopic pregnancy.

4. Vitello-intestinal duct which is obliterated can retain *as a band* which may be a seat for intestinal obstruction, volvulus, internal herniation.
5. Intestinal end may remain patent forming Meckel's diverticulum, which may be attached to umbilicus with a fibrous band. *Meckel's diverticulum* itself can cause diverticulitis, obstruction.



Fig. 17.4: Anomalies of vitello-intestinal duct. (a) Intestinal fistula, (b) Umbilical sinus, (c) Intra-abdominal cyst, (d) Band, (e) Meckels diverticulum with band.



Fig. 17.5: Patent vitello-intestinal duct.

Anomalies of vitello-intestinal duct

1. Intestinal fistula
2. Umbilical sinus
3. Umbilical adenoma
4. Intra-abdominal cyst
5. Meckel's diverticulum
6. Intra-abdominal band

Investigations

- Fistulogram.
- U/S abdomen.
- Radio isotope study.
- If obstruction is present, plain X-ray abdomen in erect posture is useful to visualise the multiple air-fluid levels.

Treatment

Excision of vitello-intestinal duct is done, along with resection of bowel segment containing Meckel's diverticulum.

UMBILICAL SINUS

Causes

- Persistent vitello-intestinal tract partially towards umbilical side.
- Persistent urachus.
- Tuberculosis.
- Umbilical infection.
- Umbolith.
- Pilonidal sinus of the umbilicus.
- Malignancy in the urachus.

Clinical Features

- Pain, swelling, discharge and tenderness in the umbilicus.
- Features of the specific causes.

Investigations

- Study of the discharge-culture and sensitivity, cytology for malignant cells, AFB study.
- Sinusogram.
- U/S abdomen, CT abdomen.
- Chest X-ray, ESR.

Treatment

- Treat the cause.
- Antibiotics.
- Antitubercular drugs in case of tuberculosis.
- Umbilectomy.

UMBILICAL ADENOMA (Raspberry Tumour)

- It is commonly seen in infants. It is due to partially obliterated vitello-intestinal duct towards umbilical end, causing *prolapse of the mucosa* giving rise to *umbilical adenoma* also called *as Raspberry tumour*.
- It protrudes out as a red swelling, which is moist with mucus and tends to bleed on touch. It often gets infected, discharging pus through the umbilicus.
- Histologically, it consists of columnar epithelium rich in *goblet cells*.



Fig. 17.6: Umbilical adenoma (Raspberry tumour).

Differential Diagnosis

- Umbilical granuloma.

Treatment

- If the tumour is pedunculated, a firm ligature is tied round it, so that tumour will fall off in few days. If it reappears, umbilectomy is done.
- Sometimes there may be a patent vitello-intestinal duct or a Meckel's diverticulum, which may require resection along with the bowel segment.

UMBILICAL FISTULA

Causes

- Patent vitello-intestinal duct.
- Patent urachus.
- Post surgical.
- Tuberculosis.

Clinical Features

- Faecal discharge or urinary discharge, mucoid discharge.
- Recurrent infection.
- Pain, tenderness and excoriation in and around the umbilicus.

Investigations

- Fistulogram, CT fistulogram.
- Discharge study. C/S, AFB and cytology.
- U/S abdomen.

Treatment

- Fistulectomy, along with resection of bowel segment, patent vitello-intestinal tract, and anastomosis of the bowel.
- Fistulectomy and excision of vitelline duct up to the antimesentric surface of the ileum. Opening in the ileum is closed transversely using vicryl or silk sutures.

PATENT URACHUS

Allantoic duct/stalk which is remnant of cranial part of ventral urogenital sinus forms urachus. It gets fibrosed and forms median umbilical ligament.

When urachus is patent it can form—

- *Patent urachus (Urachal fistula)* between umbilicus and dome of the urinary bladder. (It is persistent median umbilical ligament).
- *Urachal sinus* if only umbilical side of the urachus is patent.
- *Urachal cyst* if only middle portion of the urachus is patent with lining and fluid content.
- *Urachal diverticulum* when bladder side of the urachus is patent.



Fig. 17.7: Different types of urachal anomalies.

Features

- Persistent discharge from the umbilicus often stained with urine if it is fistula.
- Recurrent infection and bleeding.
- Pain in the umbilicus and below.
- Recurrent urinary infection.

Tanyol's sign: Umbilicus is equidistant from xiphoid process and symphysis pubis. It is displaced downwards in ascites and upwards in pelvic masses.



Fig. 17.8: Tuberculosis of urachus which is excised.

Investigations

- Fistulogram to see the extent.
- U/S abdomen.
- Discharge analysis and culture.
- Urine analysis.

Treatment

- Surgical excision of the tract.
- Often umbilical excision may be required.

Note: Malignancy (adenocarcinoma) or tuberculosis can occur in patent urachus.

BURST ABDOMEN (Abdominal Dehiscence)

- It is disruption of a laparotomy wound, occurring usually between 5th and 8th postoperative day.
- Usually sutures opposing the deep layers, i.e. peritoneum and rectus sheath tear through, causing burst abdomen.

Clinical Features (2%)

- A sudden feeling of giving way from the wound – on 5th to 8th postoperative day often precipitated by bouts of severe cough.



Figs 17.9A and B: Burst abdomen wound exposing intestines outside. It is covered with a mesh later.



Fig. 17.10: Abdominal faecal fistula. Note the tension sutures and faecal discharge.



Fig. 17.11: Ulcer over the postoperative wound.

Factors related to burst abdomen

1. Choice of suture materials used
2. Method of closure; continuous closure is more likely to disrupt than interrupted sutures
3. Upper midline and vertical wounds are more likely to disrupt than transverse
4. Surgical wounds of peritonitis, acute abdomen, major surgeries like pancreatic, hepatic, gastric, surgeries for malignancies have a high incidence of disruption
5. Severe cough, vomiting and distension in post-operative period
6. Poor general condition of the patient—Anaemia, jaundice, hypoproteinaemia, obesity, uraemia and diabetes mellitus.

- *Pinkish serosanguineous discharge* from the wound.
- Often omentum or coils of intestine are forced out of the wound.
- *Clinically burst abdomen can be diagnosed without fail*.



Fig. 17.12: Incisional hernia which was repaired earlier has gaped exposing the mesh.



Fig. 17.13: Horizontal tension sutures.

Treatment

- Nasogastric aspiration.
- IV fluids.
- *Emergency surgery*, i.e. Under anaesthesia, wound is opened up properly.



Figs 17.14A and B: Vertical tension sutures. Second photo shows tension sutures with multiple drains.

Truth is what is actually should be. Reality is what is happening. Every reality need not be truthfully right.

Coils of intestines are replaced into the abdominal cavity. Thorough wash is given. Wound is closed by *all layer sutures*, passing a non-absorbable suture material through the red rubber or plastic collar — *tension sutures*. (which is kept for 14 days).
- Antibiotics and IV fluids are continued.
- Wound usually heals well without much second dehiscence. Late problem, may be development of incisional hernia.

ABDOMINAL WALL TUMOURS

- They are not uncommon but often present late as they are usually asymptomatic.
- Common tumours are lipoma, fibroma, neurofibroma, and fibromatosis.
- Malignant tumours occasionally when occurs, are either from skin or soft tissues. They may be desmoid tumour, soft tissue sarcoma like fibrosarcoma, dermatofibrosarcoma, liposarcoma, umbilical secondaries (Sister Joseph Mary tumour).
- Presents usually as painless progressive swelling. Often ulceration can occur. Attaining large size is also known. It is dull to percuss. On contracting the abdominal wall muscles, swelling becomes prominent and less mobile.
- Differential diagnoses are – abdominal wall abscess, haematoma, intraabdominal tumours (adherent to abdominal wall).
- U/S abdomen, CT abdomen is diagnostic. Biopsy is essential.
- *Treatment* is wide excision with adequate clearance with removal of adjacent skin and musculoaponeurotic layer. Defect is covered with a large mesh.





Figs 17.15A and B: Abdominal wall proliferative ulcer in one photo and large tumour in other. Second one may be Fibromatosis arising from abdominal wall.

DESMOID TUMOUR

- It is a tumour arising from the musculo-aponeurotic layer of abdomen, below the level of the umbilicus.
- It is unencapsulated, hard, fibroma, presently classified under ***aggressive fibromatosis.***
- 80% of cases occur in women, commonly after deliveries. It is common over old abdominal operation scars (lower abdomen), may be due to old haematomas.
- It is often associated with the familial polyposis colon (FAP), osteomas, odontomes epidermal cysts—***Gardner's syndrome.***
- It is a slow growing tumour involving muscle and soft tissue of the abdominal wall, locally spreading, often undergoes myxomatous changes.
- Unlike fibromas, it never turns into sarcoma.

Histologically it contains multinucleated plasmodial giant cells.

Gardner's syndrome

1. Familial polyposis colon
2. Osteomas
3. Odontomes
4. Epidermal cyst – 20%

Management

- The possible association of Gardner's syndrome is looked for and Barium enema, X-ray, U/S abdomen are done.

- *Wide excision* of the tumour with a margin of 2.5 cm is done along with *placement of a mesh to* the abdominal defect.
- It is moderately radiosensitive.
- Drugs like sulindac and tamoxifen are also used.
- Recurrence rate is high – 20%.



Fig. 17.16: Recurrent abdominal wall tumour. It may be Fibromatosis or recurrent dermatofibroma.

EXOMPHALOS (Omphalocele)

- It is the failure of all or a part of the gut to return to the coelomic cavity during early foetal life, as coelomic cavity has not developed properly.
- Sac covering the content is very thin, consists of three layers—outer amniotic membrane, middle Wharton's jelly and inner peritoneal layer. Sac may get ruptured during birth.



Fig. 17.17: Exomphalos.



Fig. 17.18: Exomphalos major. Note the liver, small and large bowel.

- *Omphalocele is often associated with congenital anomalies of cardiac and genitourinary system - 70%.*
- Vitello-intestinal anomaly, diaphragmatic hernia, malrotation can co-exist, Exomphalos, Macroglossia, Gigantism (EMG) can co-exist in 2/3 of such babies—is called as ***Beckwith-Weidman syndrome.***
- Chromosomal trisomies – 13, 15, 18 and 21, bladder extrophy, imperforate anus, sacral vertebral anomaly, meningo-myelocele.
- Abdominal wall defect can be confirmed *in utero* by U/S. Amniocentesis and chromosomal analysis can be done. This will allow deciding the possible need for termination of pregnancy, or management plan immediately after delivery.
- Abdominal wall muscle is normally developed but peritoneal layer is hypoplastic.

Types

Two types–

Differences between exomphalos minor and exomphalos major

Exomphalos minor	*Exomphalos major*
Small sac	Large sac
Defect < 5 cm	Defect >5 cm
Content is small bowel only	Liver, small and large bowel
Primary closure is possible	Primary closure is not possible
Good prognosis	Poor prognosis

Difficulties come not to obstruct, but to instruct.

Exomphalos minor:

- Here the sac is small and *umbilical cord is attached to the summit*, with small bowel as the content. Treatment for E. minor is relatively easier. The sac has to be twisted so as to reduce the content to the peritoneal cavity through the umbilical defect and the abdomen is strapped. Later the defect is closed (Defect is < 5 cm).

Exomphalos major:

- A large defect (> 5 cm) is present with contents lying completely outside. *Umbilical cord is attached to the inferior aspect of the sac.* Contents being small bowel, large bowel and liver.
- Often the sac ruptures during delivery, which in turn leads to severe infection and high mortality. Here immediate surgery (within hours) is the only hope to save the child.



Fig. 17.19: Diagram showing differences between Exomphalos minor and Exomphalos major.

- As there is hardly any properly developed abdominal cavity, it is not possible to reduce the contents to the peritoneal cavity. So initially, relaxing incisions are placed over the lateral abdominal wall and also the subcutaneous layer has to be undermined so as to accommodate whatever possible contents in the cavity. The contents are not to be forced into the cavity, which in turn may cause intestinal obstruction, respiratory distress, venous engorgement.
- Often a sterile polythene bag *(Silastic silo)* can be wrapped over the content carefully. Gradual twisting of the bag over the summit at regular intervals over two to three weeks will stimulate the peritoneal cavity to increase in capacity and eventually the contents get reduced. Later the defect is closed properly.
- Antibiotics, IV fluids, nutritional support are required during this period.
- *Mortality is higher* in spite of all these—due to sepsis, dehydration, hypothermia and respiratory failure.
- Late ventral hernia should be corrected at later period.

Management of exomphalos

- Vitamin K injection, TPN
- Sepsis control with antibiotics
- Evaluation for other anomalies
- In E major when sac is intact application of 0.5% mercurochrome with 65% alcohol to promote granulation tissue formation
- Prevention of aspiration
- Prevention of hypothermia
- Wrapping the content with sterile bag/wrapper
- Correction of dehydration
- Definitive surgical procedures like release incisions and closure

GASTROSCHISIS (Belly Cleft)

- It is a defect of the anterior abdominal wall just lateral to the umbilicus. It is common in premature babies.



Fig. 17.20: Gastroschisis.

- Umbilicus is normal. The defect is almost always to the right of an intact umbilical cord. Evisceration of the bowel occurs through the defect during intra-uterine life. There is no peritoneal sac and the irritating effect of amniotic fluid causes chemical peritonitis with formation of a thick, oedematous membrane.
- *Non-rotation and intestinal atresia are common associations.* Cardiac anomaly is not common as in omphalocele.
- After delivery, these infants are more prone for fluid loss, hypothermia, hypovolaemia, sepsis, metabolic acidosis.
- Necrotising enterocolitis is also common in such infants (20%). They are also more prone for paralytic ileus.

Treatment

General:

- Fluid management.
- TPN.
- Antibiotics.
- R-T aspiration.
- Calorie supplement.

Specific:

- Later under G/A, intestines are pushed into the abdomen through the defect and defect is closed with interrupted non-absorbable sutures. Often when bowel is not accommodating in the abdominal cavity, bowel is initially placed in sterile silastic silo bag. In later period, it is pushed into the abdomen gradually. Often a part of the bowel may not be viable, then resection and anastomosis has to be done.
- With proper surgery, nutrition, resuscitation, survival rate is 90% which is better than omphalocele.

Exomphalos	*Gastroschisis*
1. Defect through umbilicus	1. Defect lateral to umbilicus
2. Covered by sac which has 3 layers	2. No peritoneal sac
3. Associated with anomalies	3. Not associated (except malrotation)

RECTUS SHEATH HAEMATOMA

- Rectus abdominis muscle is supplied by superior and inferior epigastric arteries. Injury to one of these vessels will cause bleeding and haematoma in rectus sheath.
- Commonly it is *due to bleeding from inferior epigastric artery* in the lower abdomen.

Causes

- Trauma.
- Surgery.
- Spontaneous haematoma, typhoid fever.
- Blood dyscrasias, haemophila, anticoagulant therapy.
- Severe straining and exercises.
- Tetanus and other convulsions.
- Patients on anticoagulants.
- Puerperium.

Features

- Common in females.
- Sudden onset of swelling in lower abdomen, which is tender, warm, firm on one side of the abdomen. Swelling does not cross the midline.
- Bluish discoloration over the swelling.
- U/S and aspiration confirms the diagnosis.
- Should be differentiated from other masses and parietal hernias.

Treatment

- Usually conservative with analgesics and antibiotics
- Occasionally requires drainage of haematoma and ligation of inferior epigastric artery.

ABDOMINAL WALL ABSCESS

Causes

- Infected haematoma.
- Umbilical sepsis spreading in to the abdominal layers causing the abscess.
- Blood spread from distant focus.



Fig. 17.21: Abdominal wall infection with a wound.

Features

- Tender, soft/firm swelling which is well localised, adherent to skin and abdominal muscles underneath and not mobile.
- Aspiration will show pus.
- Should be ruled out from intraabdominal mass, cold abscess, parietal hernia.
- U/S and needle aspiration is confirmative.

Treatment is antibiotics and drainage under general anaesthesia.

A deaf husband and a blind wife are always a happy couple.



Fig. 17.22: Abdominal wall abscess.



Fig. 17.23: Postoperative abdominal wall abscess.

MELENEY'S PROGRESSIVE SYNERGISTIC BACTERIAL GANGRENE OF ABDOMINAL WALL

- It is due to infection by microaerophilic streptococci, staphylococci and other anaerobes of the post operative abdominal or thoracic wounds.
- It is common in HIV, diabetic and immunosuppressed people.



Fig. 17.24: Severe abdominal wall sepsis in a postoperative patient.

- Sudden pain, redness, blackening and gangrene of the skin of the abdomen with abdominal wall necrosis.
- Toxicity, septicaemia, renal failure can occur.

Treatment

- Antibiotics like penicillins and metronidazole
- Excision of necrotic and gangrenous tissue until it bleeds.
- Blood transfusion, nutrition supplement.
- Maintaining adequate urine output.
- Management of toxaemia, hyperbaric oxygen and critical care.
- Skin grafting and coverage, when it granulates well.

Self-assessment Questions

1. Management of burst abdomen.
2. Raspberry tumour.
3. Desmoid tumour.
4. Aetiology and management of incisional hernia.
5. Exomphalos.
6. Umbilical granuloma.
7. Vitello-intestinal duct.

18

Hernia

Hernia—*Aetiology, Parts of hernia, Classification of hernia*
Herniography
Inguinal hernia—*Surgical anatomy of inguinal canal, Classification of inguinal hernia, Indirect/oblique inguinal hernia, Direct hernia, Recurrent hernia, Hernioplasty, Malgaigne bulging, Incarcerated hernia*
Strangulated hernia
Sliding hernia
Pantaloon/Saddle hernia
Infantile hernia
Femoral hernia
Ventral hernia
Incisional hernia
Umbilical hernia
Paraumbilical hernia
Epigastric hernia
Spigelian hernia
Obturator hernia
Richter's hernia
Lumbar hernia
Phantom hernia
Sciatic hernia
Different types of hernia

HERNIA

Hernia means—*'To bud' or 'to protrude', 'off shoot' (Greek) 'rupture' (Latin).*

- *A hernia is defined* as an area of weakness or disruption of the fibromuscular tissues of the body wall. Often hernia is also defined as an actual anatomical weakness or defect. 75% of abdominal wall hernias are groin hernias. 15% of males and 5% of females will develop groin hernia. Presently all hernias in groin are grouped as groin hernias. But in this chapter discussion of the indirect/direct/femoral hernias are given, in detail as it is still practiced and followed in most of the centers and still it is important when surgical technical aspects are considered.
- Hernia is defined as an abnormal protrusion of a viscous or a part of a viscous through an opening, artificial or natural with a sac, covering it.
- *Inguinal hernia is the commonest hernia* (73%) because the muscular anatomy in the inguinal region is weak and also due to the presence of natural weakness like deep ring and cord structures.
- Femoral is 17%; Umbilical is 8.5%; Others are 1.5% (Excluding incisional hernia).
- In general, incisional hernia is next to inguinal hernia in occurrence.



Fig. 18.1: Common and rare sites of hernias.

> *In order to achieve a radical cure of inguinal hernia it is absolutely essential to restore those conditions in the area of hernial orifice which exist under normal circumstances.*
> —Edoardo Bassini

AETIOLOGY

- Straining.
- Lifting of heavy weight.
- Chronic cough (tuberculosis, chronic bronchitis, bronchial asthma, emphysema).
- Chronic constipation (habitual, rectal stricture).
- Urinary causes
  - Old age: BPH, carcinoma prostate.
  - Young age: stricture urethra.
  - Very young age: phimosis, meatal stenosis.
- Obesity.
- Pregnancy and pelvic anatomy (especially in femoral hernia in females).
- Smoking.
- Ascites.
- Appendicectomy through McBurney's incision may injure the ilioinguinal nerve causing right sided *direct* inguinal hernia.
- An indirect inguinal hernia occurs in a congenital, preformed sac, i.e. the remains of processus vaginalis. Chances of presence of bilateral preformed sac is 60%.
- Familial-collagen disorder—*Prune Belly syndrome*.



Fig. 18.2: Inguinal hernia in a patient who is having benign prostatic hyperplasia (BPH) with Foley's urinary catheter. He is having paraphimosis probably for not replacing back the retracted prepuce after catheterisation.

PARTS OF HERNIA

Hernia comprises of:

- *Covering.*
- *Sac.*
- *Content.*

Sac is a diverticulum of peritoneum with mouth, neck, body and fundus. Neck is *narrow in indirect sac but wide in direct sac*. Body of the sac is thin in infants, children and in indirect sac but is thick in direct and long standing hernia.

- Hernia without neck: Those hernias with larger mouth lack neck, e.g. direct hernia, incisional hernia.
- Hernia without sac: Epigastric hernia—it is protrusion of extra-peritoneal pad of fat.

Coverings of the sac are the layers of the abdominal wall through which the sac passes.

Contents of Sac

- Omentum—*Omentocele* (Epiplocele). Difficult to reduce the sac later, initially it can be reduced easily.
- Intestine—*Enterocele*— commonly small bowel, but sometimes even large bowel.
  Difficult to reduce the sac initially.
- *Richter's hernia*: A portion of circumference of bowel is the content.
- Urinary bladder may be the content or part of the posterial wall of the sac—*cystocele*.
- Ovary, often with fallopian tube.
- Meckel's diverticulum—*Littre's hernia*.



Fig. 18.3: Littre's hernia with Meckel's diverticulum as content.

- *Fluid:* Fluid is secreted from congested bowel or omentum. It may be an infected fluid or ascitic fluid or blood from the strangulated sac.



Fig. 18.4: Parts of hernia. Note the fundus, body and neck of the hernia.

CLASSIFICATION OF HERNIA

Classification I (Clinical)

1. *Reducible hernia:* Hernia gets reduced on its own or by the patient or by the surgeon. Intestine reduces with gurgling and it is difficult to reduce the first portion. Omentum is doughy, and it is difficult to reduce the last portion. Expansile impulse on coughing present.



Fig. 18.5: Diagram showing the differences between indirect and direct sacs.



Fig. 18.6: Inferior epigastric artery on table. It is very important landmark during surgery whether open or laparoscopic approach.

2. *Irreducible hernia:* Here contents cannot be returned to the abdomen due to narrow neck, adhesions, overcrowding. Irreducibility predisposes to strangulation.
3. *Obstructed hernia*: It is an irreducible hernia with obstruction, but blood supply to the bowel is not interfered. It eventually leads to strangulation.

   Garrey's stricture: Constriction that occurs due to ischaemic narrowing of small bowel which has reduced from an obstructed hernia.



Fig. 18.7: Garrey's stricture on table. Due to ischaemia, a stricture is formed in the bowel at the constriction ring after reduction.

4. *Inflamed hernia:* It is due to inflammation of the contents of the sac e.g. appendicitis, salpingitis. Here hernia is tender but not tense; overlying skin is red and oedematous.
5. *Strangulated hernia.* It is an irreversible hernia with obstruction to blood flow. The swelling is tense, tender, with no impulse on coughing and with features of intestinal obstruction.

   Features of intestinal obstruction may be absent in case of omentocele, Richter's hernia, Littre's hernia.

Classification II

Congenital.
Acquired.

Classification III: According to the contents.

Omentocele—omentum.
Enterocele—intestine.
Cystocele—urinary bladder.
Littre's hernia—Meckel's diverticulum.
Note: Littre described Meckel's diverticulum in a hernial sac 81 years before Meckel was born.
Maydl's hernia.
Sliding hernia.
Richter's hernia—part of the bowel wall.

Classification IV: Based on sites

- Inguinal hernia—occurring in inguinal canal.
- Femoral hernia—occurring in femoral canal.
- Obturator hernia.

> *Anything the mind of man can conceive and believe, it can achieve.*

- Diaphragmatic hernia.
- Lumbar hernia.
- Spigelian hernia.
- Umbilical hernia.
- Epigastric hernia.



Fig. 18.8: Inguinal hernia on right side in a child. It needs only herniotomy.

Herniography (By Gullmo)

Injection of contrast material into the peritoneal cavity and taking films in supine and prone positions to diagnose small protrusions of peritoneal sac is called as herniography.

It was earlier also used for diagnosing undescended testis.

INGUINAL HERNIA

SURGICAL ANATOMY OF INGUINAL CANAL

Superficial inguinal ring is a triangular opening in the external oblique aponeurosis and is 1.25 cm above the pubic tubercle. The ring is bounded by a superomedial and inferolateral crus. Normally the ring does not admit the tip of little finger.

Deep inguinal ring is a U-shaped condensation of the transversalis fascia, lies 1.25 cm above the inguinal ligament midway between the symphysis pubis and the anterior superior iliac spine.

***Inguinal (Poupart's) ligament*:** It is formed by the lower border of the external oblique aponeurosis which is thickened and folded backwards on itself, extending from anterior superior iliac spine to pubic tubercle.

Inguinal canal: It is an oblique passage in lower part of abdominal wall, 4 cm long, situated above the medial ½ of inguinal ligament, extending from deep inguinal ring to superficial inguinal ring.

In infants both superficial and deep rings are superimposed without any obliquity of the inguinal canal.

Contents of inguinal canal

- Spermatic cord in males
- Round ligament in females
- Ilio-inguinal nerve

Contents of spermatic cord

- Vas deferens
- Artery to vas
- Testicular and cremasteric artery
- Genital branch of genitofemoral nerve
- Pampiniform plexus of veins
- Remains of processus vaginalis
- Sympathetic plexus around the artery to vas

Inguinal canal in female is called as **'canal of Nuck.'**

Coverings of Spermatic Cord

- Internal spermatic fascia from fascia transversalis
- Cremasteric fascia.
- External spermatic fascia from external oblique aponeurosis.



Fig. 18.9: Surgical anatomy of inguinal canal.

Boundaries

In front: External oblique aponeurosis and conjoined muscle laterally.

Behind: Inferior epigastric artery, fascia transversalis and conjoined tendon medially.

Above: Conjoined muscle. (Arched fibres of internal oblique).

Below: Inguinal ligament.

Defence mechanism of inguinal canal

- Obliquity of inguinal canal
- Arching of conjoint tendon
- *'Shutter mechanism'* of internal oblique
- *'Ball valve mechanism'* due to contraction of cremaster muscle which plugs to superficial ring
- When external oblique muscle contracts , intercrural fibres of superficial ring appose causing *'slit valve mechanism'*
- Hormones

Fruchaud's Myopectineal Orifice

It is an osseo-myo-aponeurotic tunnel. *It is through this tunnel all groin hernias occur.*

It is bounded-

- Medially by lateral border of rectus sheath.
- Above by the arched fibres of internal oblique and transverse abdominis muscle.
- Laterally by the iliopsoas muscle.
- Below by the pectin pubis and fascia covering it.

CLASSIFICATION OF INGUINAL HERNIA

I. Classification

Anatomical classification: (in inguinal hernia)

Indirect hernia. It comes out through internal ring along with the cord. It is lateral to the inferior epigastric artery.

Direct hernia. It occurs through the posterior wall of the inguinal canal through 'Hesselbach's triangle' (bounded medially by lateral border of rectus muscle, laterally by inferior epigastric artery, below by inguinal ligament). Sac is medial to the inferior epigastric artery.



Fig. 18.10: Location of direct and indirect inguinal hernia and femoral hernia.

II. Classification

According to the extent.

- *Incomplete*:
  - **Bubonocele:** Here sac is confined to the inguinal canal**.**



Fig. 18.11: Bubonocele.

  - **Funicular:** Here sac crosses the superficial inguinal ring, but does not reach the bottom of the scrotum.



Fig. 18.12: Irreducible left side inguinal hernia. It is above the upper part of the testis (funicular). Taxis is the method used to reduce it.

- *Complete:* Here sac descends to the bottom of the scrotum.

Saddle-bag or pantaloon hernial sac has got both medial and lateral component.

> *When spermatic cord is rolled transversely beneath the gentle pressure of index finger. Thickening of the cord denotes presence of a hernia.*
> — William E Ladd



Fig. 18.13: Bilateral complete inguinal hernia. Here hernia descends up to the bottom of the scrotum.

Note: Inguinal hernia is above and medial to the pubic tubercle . Femoral hernia is below and lateral to pubic tubercle.

Newer Classification of Hernia

III. Gilbert classification

Type I: Hernia has got snug internal ring through which a peritoneal sac passes out as indirect sac.

Type II: Hernia has a moderately enlarged internal ring which admits one finger but lesser than two finger breadth. Once reduced it protrude during coughing or straining.

Type III: Hernia has got large internal ring with defect more than two finger breadth. Hernia descends into the scrotum or with sliding hernia. Once reduced it immediately protrudes out without any straining.

Type IV: It is direct hernia with large full blow out of the posterior wall of the inguinal canal. The internal ring is intact.

Type V: It is a direct hernia protruding out through punched out hole/defect in the transversalis fascia. The internal ring is intact.

Type VI: Pantaloon/double hernia.

Type VII: Femoral hernia.

Type VI and VII are Robbin's modifications.

IV. NYHUS classification

Type I: Indirect hernia with normal deep ring.
Type II: Indirect hernia with dilated deep ring.
Type III: Posterior wall defect.
  a. Direct.
  b. Pantaloon hernia.
  c. Femoral hernia.

Type IV: Recurrent hernia.

V. BENDAVID Classification (Type, Staging, Diameter (TSD) classification)

Type I: Antero-lateral defect (indirect).
Type II: Antero-medial (direct).
Type III: Postero-medial (femoral).
Type IV: Posterior-prevascular hernia.
Type V: Antero-posterior defect: Inguino-femoral hernia.

Male to female ratio of inguinal hernia is 10:1. Prevalence of inguinal hernia: 25% in males; 2% in females.

INDIRECT (OBLIQUE) INGUINAL HERNIA

- This is the most common type of hernia (65%).
- It is more common in younger age group as compared to direct inguinal hernia which is more common in elderly.
- It is more common on right side in 1st decade but in 2nd decade the incidence is equal on both sides.
- Hernia is bilateral in 30% of cases.
- Sac is thin in indirect type. Neck is narrow and lies lateral to inferior epigastric vessels.



Fig. 18.14: Complete indirect hernia.

Coverings of indirect hernia (from inside out)

- Extraperitoneal tissue
- Internal spermatic fascia
- Cremasteric fascia
- External spermatic fascia
- Skin



Figs 18.15A and B: Giant inguinal hernias in different sides. (Right side in one photo and left side in another).

Precipitating causes for inguinal hernia

- Smoking
- Obesity
- Respiratory causes like bronchial asthma, tuberculosis, bronchitis
- Ascites
- Previous surgery like appendicectomy which can cause direct inguinal hernia.
- Chronic constipation due to anorectal strictures. Rectal stricture may be due to chronic proctitis (amoebic), tuberculosis of anorectum, previous anorectal surgery, rectal carcinoma or stricture due to lymphogranuloma venereum
- Urinary problems like benign prostatic hyperplasia (BPH), urethral stricture
- Straining
- Multiple pregnancies

Types

Three types

1. *Bubonocele*: Where the hernia is limited to inguinal canal.



Fig. 18.16: Surgical anatomy of indirect hernia.

2. *Funicular:* Processus vaginalis is closed just above the epididymis. Contents of the sac can be felt separately from testis, which lies below the hernia.
3. *Complete (Scrotal)*: Testis appears to lie within the lower part of hernia. It can occur in any age group. It occurs in a congenital preformed sac (processus vaginalis). More commonly contents descend into the pre-existing sac, only when there are precipitating causes which force the content down.



Fig. 18.17: Types of indirect inguinal hernia.

Expansile impulse on coughing

- Hernia
- Laryngocele
- Meningocele
- Empyema necessitans
- Swellings with intracavitary communications like thorax, cranium, and abdomen like dermoid.

Clinical Features

- It is more common in males (20 : 1 :: Male : Female).
- Patient presents with dragging pain and swelling in the groin which is better seen while coughing and standing; and felt together with an expansile impulse.
- In *complete* type, the content descends down to the scrotum completely.
- Contents are either small bowel, large bowel, omentum or combination of all these. In females, sometimes ovary and tubes may be the content. In infants, swelling appears when the child cries and is often translucent.
- It is usually reducible, but can go for irreducibility, inflammation, obstruction, strangulation.
- ***Internal ring occlusion test***: Internal ring is located half inch above the mid-inguinal point (center point between anterior superior iliac spine and pubic symphysis). After reducing the contents, in lying down position, internal ring is occluded using the thumb.

Great minds have purposes, others have wishes.

Patient is asked to cough. If a swelling appears medial to the thumb, then it is a direct hernia. If swelling does not appear and on releasing the thumb swelling appears during coughing, then it is an indirect hernia confirmed in standing position

- ***Ring invagination test***: After reduction of hernia, the little finger/index finger of the examiner is invaginated from the bottom of the scrotum, gradually pushed up and rotated to enter the superficial inguinal ring. The impulse on coughing is felt at the tip of the invaginated finger. This test is done only in males.
- ***Zieman's test***: The examiner places his index finger on the deep inguinal ring and middle finger on the superficial inguinal ring, ring finger over saphenous opening. The patient is asked to cough or to hold the nose and blow. If the impulse is felt on the index finger, it is indirect hernia.



Fig. 18.18: Zieman's test. Index finger on deep ring; middle finger on superficial ring and ring finger over saphenous opening – are placed after reducing the content. Patient is asked to cough and impulse is felt in finger corresponding to the existing hernia.

- ***Head*** or ***leg rising test*** is done to look for abdominal wall muscle tone and Malgaigne bulgings.
  Valsalva manoeuver is also used to check the tone of abdominal wall muscles.
- Abdominal, respiratory, urological examination is done to look for any precipitating factors like chronic bronchitis, ascites, stricture urethra, BPH.



Fig. 18.19: Head or leg rising or valsalva maneuver is important to elicit abdominal muscle tone.

- ***Per rectal*** examination is a must.
- ***Inguinal hernia in females:*** Increased thickness of labium majus on palpation, when compared to contralateral side.
- ***Silk glove sign:*** Index finger is invaginated across scrotum towards the external ring. When patient coughs, inguinal hernia is felt like a slit like sensation.
- Palpation of bulbar urethra for stricture (thickening/crescent like feel/button like depression).



Fig. 18.20: Left side inguinal hernia in a female.

Use five fingers of the hand to complete all tests for hernia
- Thumb—for deep ring occlusion test
- Index, middle and ring fingers for Zieman's test
- Little finger for superficial ring invagination test

Rules of hernia examination
- Never forget to examine opposite side
- Never forget to do per rectal examination
- Never forget to examine urethra
- Never forget to check abdominal muscle tone

Differential diagnosis

- Hydrocele – infantile/encysted/large vaginal/bilocular
- Undescended testis
- Femoral hernia
- Lipoma of the cord
- Hydrocele of the canal of nuck (in females)
- Inguinal lymph node enlargement
- Groin abscess



Fig. 18.21: Differential diagnosis for groin swellings.

Indirect inguinal hernia	*Direct inguinal hernia*
Can occur in any age from childhood to adult	Common in elderly
Occurs in a pre-existing sac	Always acquired
Protrusion through the deep ring; herniation occurs later	Herniation through posterior wall of the inguinal canal
Pyriform/oval in shape; descends obliquely and downwards	Globular/round in shape; descends directly forward bulge
Can become complete by descending down into the scrotum	Descent down into the scrotum is rare
Neck of the sac is narrow and lateral to inferior epigastric artery	Neck of the sac is wide and medial to inferior epigastric artery
Sac is antero-lateral to the cord	Sac is posterior to the cord
Ring occlusion test does not show any impulse after occluding the deep ring	Test shows impulse even after occluding the deep ring
Invagination test shows impulse on the tip of the little finger	Impulse is felt over the pulp of the little finger
Zieman's test shows impulse on the index finger	Test shows impulse on the middle finger
Commonly unilateral but can be bilateral	Commonly bilateral
Obstruction/strangulation are common	Rare but can occur
Sac should be opened during surgery	Sac is not necessarily opened unless obstruction is present

In enterocele	*In omentocele (epiploecele)*
First part is difficult to reduce but last part is easier. There will be gurgling sound on reduction	First part is easier to reduce but last part is difficult. Has a doughy feeling
Resonant on percussion	Dull on percussion
Peristalsis is seen	No peristalsis seen
Bowel sounds may be heard	Bowel sounds not heard

Investigations

- Chest X-ray to rule out chronic bronchitis.
- Ultrasound of abdomen.
- Tests relevant for precipitating causes.



Figs 18.22A and B: Indirect inguinal hernial sac on table and opening the sac over fundus.

Hydrocele of canal of Nuck is the most common differential diagnosis for inguinal hernia in females.



Fig. 18.23: On table direct sac which is medial to inferior epigastric artery. Direct sac is usually not opened. Inverting sutures may be placed if needed.

Treatment

> ***This method reconstructs the inguinal canal as it is physiologically, with two rings, one abdominal, the other subcutaneous; and with two walls, one posterior and the other anterior, between which the spermatic cord passes obliquely.***
>
> **—Edoardo Bassini,** 1887

Always surgery:.

In infants:

- Whether it is hernia or hydrocele,only *herniotomy* is done through inguinal approach (*Michaelis plank operation*).



Fig. 18.24: Inguinal hernia in 4-year-old child. Here just herniotomy is required. Repair is not done.

In adults:

- It includes *herniotomy*, i.e. excision of hernial sac and ***herniorrhaphy*** (strengthening of the posterior wall of inguinal canal either by repair or mesh). Precipitating causes should be treated first, like TURP for BPH, dilatation of stricture urethra, treatment of chronic bronchitis. Patient is advised to avoid smoking.
- Hernioplasty is the present choice (ideal) for all inguinal and groin hernias. Mesh is placed either onlay (over conjoint tendon to inguinal ligament) or inlay (in preperitoneal space). Polypropylene mesh is used. Herniotomy is done prior to mesh placement. TEP (Totally extraperitoneal laparoscopic preperitoneal mesh repair) is preferred method. (For detail refer hernioplasty in later part of this chapter).

Repair may be

- *Pure tissue repair*–Shouldice, Mac Vay (Still very useful repairs) and Modified Bassini (not very useful – high recurrence rate as it is repair with tension and nonphysiological)
- *Prosthetic repair*–Lichtenstein, Rives, Gilbert, Stoppa, TEP, TAPP

Herniotomy

Anaesthesia: Spinal or G/A

Procedure: After cleaning and draping, skin is incised—1.25 cm above and parallel to the medial two/third of inguinal ligament. Two layers of superficial fascia (outer Camper's fascia and inner Scarpa's fascia) are incised.



Fig. 18.25: Large hernia with Foley's catheter. Patient had retention of urine due to benign prostatic hyperplasia. He underwent Transurethral resection of prostate [TURP] first and later hernioplasty.



Fig. 18.26: Incision for inguinal hernia. It is 1.25 cm above and parallel to medial third of inguinal ligament.

External oblique aponeurosis is incised. Upper leaf is reflected above and lower leaf is reflected downwards to visualise and expose the inguinal ligament. Ilioinguinal nerve is safeguarded. Cremasteric muscle is opened. Cord structures are dissected. Sac which is anterior and lateral to cord is identified and is pearly white in colour. Dissection is usually started from the fundus and extended towards the neck which is identified by extraperitoneal fat. The neck is narrow and is lateral to inferior epigastric artery. Sac is opened at the fundus. Finger is passed to release any adhesions. Sac is twisted so as to prevent the content from coming back. It is transfixed using absorbable suture material (chromic catgut 2-0 or vicryl) and is excised distally.



Fig. 18.27: Opened indirect sac in herniotomy.



Fig. 18.28: Hernia with enterocele as content.



Twisting and transfixing

Fig. 18.29: Sac should be twisted before transfixing to prevent contents to get in.

Modified Bassini's Herniorrhaphy

- Conjoint tendon and inguinal ligament are approximated using interrupted non-absorbable monofilament sutures {polypropylene (prolene, blue in colour)}. Medial most stitch is taken from the periosteum of pubic tubercle (*called as key or Bassini's stitch*). External oblique is closed and other layers are also closed.

Usually saphena varix feels softer than a femoral hernia.— Robert Milnes Walker

- It is strengthening of the posterior wall of the inguinal canal by approximation of the conjoint tendon to inguinal ligament using monofilament non-absorbable suture material. Absorbable suture material like catgut should not be used as 50% of its tensile strength will be lost in 7 days. It takes 6 months to achieve more than 80% of tensile strength in repaired hernial wound; and so non-absorbable suture material has to be used here to maintain the same adequate tensile strength in this period. Multifilament suture material like silk may precipitate infection because of the crevices in the suture material and tensile strength is not as good as monofilament suture material. Commonly used suture material is either *polypropylene* [*prolene* (blue in colour)] or *polyethylene* [*ethylon* (black in colour)]. Continuous sutures compromises the blood supply and interferes with proper healing; and strength will not be as adequate as interrupted sutures. So always interrupted sutures are used. Earlier, commonest surgery done for groin inguinal hernia was modified Bassini's repair. But now hernioplasty is the commonly done procedure for both direct and indirect sac. In direct hernia, sac is usually not opened but in indirect hernia, sac is always opened.

Anaesthesia used for Inguinal Hernia Repair

General/spinal/epidural or local anaesthesia can be used to do inguinal hernia repair. Local anaesthesia is becoming popular for open approach. General anaesthesia is needed in children and for TAPP and TEP procedures.

Technique of Local Anaesthesia

Around 50-60 ml of xylocaine 0.5% is used. Plain xylocaine 0.5% or xylocaine 0.5% with adrenaline can be used. Plain xylocaine—dose is 2 mg / kg body weight. Xylocaine with adrenaline—dose is 7 mg / kg body weight.

Two methods are used—

1. *Nerve block method (point block)*
   - 10 ml of xylocaine is infiltrated 2 cm above and medial to anterior superior iliac spine to block the iliohypogastric nerve.
   - Midinguinal point is infiltrated with 10 ml xylocaine.
   - Pubic tubercle point is infiltrated with 10 ml xylocaine.
   - 10 ml of xylocaine is infiltrated just below the inguinal ligament lateral to femoral artery to block the genital branch of genitofemoral artery.
   - Line of skin incision is infiltrated with 10 ml of xylocaine.
   - Later neck of the hernial sac is infiltrated with 10 ml of xylocaine.
2. *Field block method (Shouldice method)*
   - Skin of around 4 cm wide area is infiltrated into the subcutaneous plane as first layer from anterior superior iliac spine to pubic symphysis. Skin, subcutaneous and two layers of superficial fascia (Camper and Scarpa's) are incised.
   - Area deep to external oblique aponeurosis is infiltrated with 10 ml of xylocaine. External oblique aponeurosis is incised.
   - Exposed inguinal canal and hernial sac is infiltrated with 10 ml of xylocaine to continue with the dissection.



Figs 18.30A and B: Inguinal hernia with mesh placement. Prolene mesh is white in colour. It is sutured to conjoint tendon and inguinal ligament by interrupted sutures using non-absorbable monofilament suture material.


Internal ring
Inguinal ligament
Conjoint tendon
External oblique aponeurosis
Sutures (interrupet)
Cord
Testes

Fig. 18.31: Modified Bassini's repair. It is approximation of inguinal ligament to conjoined tendon using interrupted nonabsorbable monofilament sutures.



Fig. 18.32: On table inguinal hernia surgery with cord holding forceps.

Complications of herniorrhaphy:
- Haemorrhage
- Haematoma
- Infection–1-5%
- Haematocele
- Post-herniorrhaphy hydrocele, lymphocele
- Hyperaesthesia over the medial side of inguinal canal due to injury to ilioinguinal nerve - neuralgia
- Recurrence
- Osteitis pubis
- Injury to urinary bladder/bowel
- Testicular atrophy, penile oedema rarely can occur


Right side clean wound
Infected hernia wound left side

Fig. 18.33: Left side inguinal hernia wound infected. Right side hernia wound is clean.



Fig. 18.34: Inguinal hernia after hernioplasty, mesh is infected. It needs removal of mesh.

Lytle's Repair

Often internal ring is narrowed by placing interrupted sutures over the medial side of the ring to the transversalis fascia using either thread or silk. (To narrow the ring and push the cord laterally).


Lytle's repair
Cord
Conjoint tendon
Internal ring
External oblique
Testes

Fig. 18.35: Lytle's repair. It is narrowing of the widened internal ring.

> *In exomphalos, the protruding abdominal contents being covered only by a diphanous membrane, through which viscera are exposed to view, as if exhibited in a show case.* — William E Ladd

Shouldice Repair

Even though transversalis fascia is thin, it is a tough layer and so double breasting of this fascia using continuous sutures (with nonabsorbable material) strengthens the posterior wall of the inguinal wall.

It is a multilayered repair. It was originated at *Shouldice hernia clinic in Toronto* where it was usually done under local anaesthesia. After doing herniotomy as in any other inguinal hernia, transversalis fascia is incised along the line of the wound from deep ring to pubic tubercle. Lower flap of fascia is sutured to posterior part of the upper flap. Upper flap is sutured to the inguinal ligament. It causes double-breasting of the transversalis fascia. Then conjoint tendon and inguinal ligament is further approximated by two layers of continuous sutures. External oblique aponeurosis is sutured in two layers (double-breasting) in front of the cord. Hence the original Shouldice repair is 6 layered procedure. First two layers of transversalis fascia, next two layers of conjoint tendon and last two layers of external oblique aponeurosis. Suture material used here is fine steel wire of 34 gauge (in original Shouldice repair) or polypropylene or polyethylene. Recurrence rate is 1%.

Berliner modified Shouldice repair—It involves double-breasting of the transversalis fascia like in Shouldice repair and single layer closure of the external oblique aponeurosis without any additional two-layered repair of conjoint tendon to inguinal ligament.

Tanner Slide Operation

To reduce the tension in the repair area, relaxing incision is placed over the lower rectus sheath so that conjoined tendon is allowed to slide downward.



Fig. 18.36: Tanner slide operation—relaxing incision placed over the lower medial rectus sheath to reduce the tension after modified Bassini's repair.

Darning (Abrahamson nylon darning)

Continuous intervening network of nonabsorbable sutures are placed between conjoint tendon and inguinal ligament to give good support to posterior wall of inguinal hernia.



Fig. 18.37: Darning between inguinal ligament and conjoined tendon to act as a support to posterior wall of the inguinal canal.

Kuntz' Operation

In old people after taking consent, orchidectomy is done along with removal of entire cord, testis and total closure of posterior inguinal wall by repair so as to reduce the recurrence.

Removal of Cord at Inguinal Region (Hamilton-Bailey operation)

Cord is removed from the inguinal canal by ligating both at external and internal ring. But testis is retained (for psychological reason) and closure of inguinal canal by repair is done.

Andrew's Operation

It involves overlapping of the external oblique aponeurosis.

Mc Vay Operation – 1940 - (Cooper's ligament repair)

It is repair by placing interrupted sutures between transversalis fascia to Copper's ligament starting from pubic tubercle medially towards femoral sheath and later continued as suture repair between transversalis fascia and iliopubic tract laterally up to the entrance of cord is reached. It is a pure tissue repair. It requires relaxing vertical incision at the lateral border of the anterior rectus sheath, from pubic tubercle point extending superiorly for 4 cm. It covers all three groin defects – indirect, direct and femoral.

Nyhus (Original) Iliopubic Repair

Here with a transverse incision and suprainguinal approach, lateral part of lower end of the rectus is retracted medially after opening anterior rectus sheath. Posterior rectus sheath is opened. Sac is dissected proximally and often ligated. Transaponeurotic arch (transverse abdominis muscle and transversalis fascia) is sutured below to Copper's ligament and iliopubic tract.

Hernioplasty

Mesh repair—Prolene mesh (white in colour) is used, which is placed extraperitoneally.



Fig. 18.38: Hernioplasty-Mesh repair-Lichtenstein's method (done under local anaesthesia)

Conservative treatment:

1. ***Taxis***: Patient is placed in supine position with hip and knee flexed and hip internally rotated. Contents are pushed with one hand directing with other hand
2. ***Use of Truss***: Rat-tailed sprung truss is used. Measurement is taken from the tip of greater trochanter to third piece of sacrum circumferentially
   - Complications are discomfort, ulceration, strangulation, inflammation
   - It may be used in elderly people, who are not fit for anaesthesia and surgery
   - Conservative treatment should be avoided in hernia as much as possible
   - Truss is absolutely contraindicated in femoral and sliding hernia

DIRECT HERNIA

- 10-15% of the hernias are direct.
- 50% of direct hernias occur bilateral.
- 35% of inguinal hernias are direct.
- It is uncommon in females.
- It is always acquired, due to weakening of posterior wall of inguinal canal.
- Hernia is medial to the inferior epigastric artery with wide neck. Sac is thick and often the medial wall or content may be bladder.



Figs 18.39A and B: *Hernia truss*. It is used only when patient is not fit for surgery. It may precipitate strangulation. Before placing truss, contents of the hernia should be reduced completely.

- Direct hernia occurs through *Hesselbach's* triangle which is bounded by inferior epigastric artery laterally, lateral border of rectus medially, inguinal ligament below. It is divided into medial and lateral halves by obliterated umbilical artery (lateral umbilical ligament). So direct hernia is classified as *medial or lateral depending on which part of the Hesselbach's triangle, it is arising from.*



Fig. 18.40: Surgical anatomy of direct inguinal hernia.

Language is the dress of thought.



Fig. 18.41: Surgical anatomy of Hesselbach's triangle.

Coverings of direct hernia (from inside out)

- Extraperitoneal tissue
- Fascia transversalis
- Conjoined tendon
- External spermatic fascia
- Skin

Predisposing factors

- Chronic cough, smoking
- Straining
- Constipation
- Heavy work
- Previous appendicectomy



Fig. 18.42: Bilateral direct inguinal hernia.

- *Malgaigne bulgings* are often seen in these patients on examination,more often than in indirect hernia. They are protrusion of abdominal wall muscle during leg raising test as weak, soft, supple, swellings which signifies poor abdominal muscle tone.
- Direct hernia rarely descends into the scrotum and strangulation is not as common as in indirect hernia. But in long-standing cases, it can descend down to the scrotum and strangulation can occur.



Fig. 18.43: Large bilateral direct hernia. Occasionally direct hernia descends down and becomes complete and then may cause obstruction. Descent is not as common as indirect hernia.

Treatment

Surgery:

- Usually direct sac is not opened.
- Care should be taken at the medial aspect due to the presence of bladder (bladder should be emptied before surgery).



Fig. 18.44: Bilateral direct hernia. Note the medial location of the direct hernias.

- Ideally *hernioplasty (mesh repair)* is done. In case of bilateral hernia, mesh repair can be done on both sides together.

FUNICULAR DIRECT HERNIA (Prevesical hernia)

- It is a type of direct hernia which is prone for strangulation.
- It is a narrow necked hernia with prevesical fat and a portion of bladder, and or intestine that herniates through a small defect in the medial part of the conjoined tendon just above the pubic tubercle.
- It occurs in elderly males.

Giant Inguinal Hernia: Hernia reaches below the mid-level of thigh when patient stands.

RECURRENT HERNIA (Inguinal)

Incidence is 10%.

Predisposing Factors

Preoperative:
- Smoking.
- Chronic cough.
- Constipation.
- Old age.
- Anaemia.
- Hypoproteinaemia.
- Straining.
- Increased intra-abdominal pressure of any cause (BPH, carcinoma prostate, stricture urethra)
- Ascites.

Operative:
- Tension in the sutures.
- Weak anterior abdominal wall.

Postoperative:
- Infection (50%).
- Haematoma formation during earlier surgery.
- Retained sac in pantaloon hernia.
- Straining.

Recurrence Rate

- Bassini's repair—10%.
- Shouldice repair—1%.
- Hernioplasty—1 to 3%.
- Other methods—1 to 5%.

True or false recurrences are the types of recurrence. If hernia occurs in inguinal region after inguinal hernia repair it is called as *true recurrence*. If other groin hernia occurs after inguinal hernia repair like femoral hernia or obturator or other rare types, it is called as *false recurrence*. But presently hernia is classified grossly as groin hernias and so all recurrences are true recurrences.

Clinical Features

- Same as for inguinal hernia. Defect is usually narrow and so more likely to go in for strangulation.
- It can be *medial recurrence* or *lateral recurrence* depending on the location of the sac. Medial recurrence is common.

Treatment

After thorough investigations, the cause of recurrence has to be treated and later *hernioplasty* is done.



Fig. 18.45: Recurrent inguinal hernia is 10% common. It is commonly medial recurrence. It is treated by mesh repair.

RERECURRENT HERNIA

1% common.

Causes

Infection, earlier mesh extrusion, failure of treating the precipitating causes.

Treatment

- The cause is treated and *mesh repair is done*.
- GPRVS (Giant prosthesis reinforcement of the visceral sac) or TEP through laparoscopy is ideal.

HERNIOPLASTY

It is strengthening of posterior inguinal wall in case of indirect hernia or in any large hernia with weak abdominal wall using a supportive material. This allows and supports good fibroblast proliferation which in turn strengthens the weak posterior wall of inguinal canal or abdominal wall.

Femoral hernia is never congenital.

Material Used

- *Synthetic:* Prolene mesh (white in colour) Dacron mesh, Morlex mesh, Mersilene sheath
- *Biological:* Tensor fascia lata, temporal fascia and skin. (presently biological materials are not well accepted as infection is common and its efficacy is not proved).

Prolene mesh is commonly used at present. Non-absorbable interspersed absorbed mesh (Vipro/Ultrapro) are also used nowadays.

Indications

- Direct hernia.
- Recurrent hernia.
- Re-recurrent hernia.
- Incisional hernia.
- Old age.
- Hernia with weak abdominal muscle tone.
- Sliding hernia.

Complications

- Infection.
- Mesh extrusion.
- Foreign body reaction.

Principle

- Size of the mesh should be bigger than the size of the defect.
- Mesh should be fixed above and below to the conjoint tendon and inguinal ligament or abdominal wall using interrupted, non-absorbable sutures.
- Absolute haemostasis and control (prevention) of infection is important.

Types of mesh repair

1. In lay mesh
2. On lay mesh
3. Nyhus preperitoneal mesh repair
4. Stoppa procedure
5. Gilbert mesh repair
6. Lichtenstein's method
7. TAPP
8. TEP

Hernioplasty is becoming the prime treatment for inguinal hernia.

Different types are—

- *Onlay mesh* repair by placing mesh in front. It is sutured above to conjoint tendon and below to inguinal ligament using monofilament non absorbable suture material.
- *Inlay mesh* repair by placing mesh deep to conjoint tendon.
- *Lichtenstein tension free mesh repair* (1993) where the cord is encircled with mesh which is often done under local anaesthesia. Suturing of mesh is done similar to onlay mesh repair. It has got less recurrence rate.
- *Nyhus preperitoneal mesh repair:* It is done through *suprainguinal* horizontal incision above the pubic symphysis and internal ring. Preperitoneum is approached through lateral border of the lower part of rectus muscle by making an opening in the posterior rectus sheath. Mesh is placed in the preperitoneal space deep to the cord, conjoint tendon, and transversalis fascia. Below, it is folded deep to the iliopectineal ligament of Cooper and sutured to it using two or three interrupted nonabsorbable sutures. It is sutured to transverse abdominis above and transversalis fascia from deep.
- *Modified Rives pre-peritoneal mesh repair (Read – Rives)* is preperitoneal mesh repair through *transinguinal approach*. Direct sac is inverted with sutures. For indirect sac a high ligation is done. Here mesh is placed in preperitoneal space, folded and sutured below to iliopectineal ligament, above to the transverse abdominis in deeper plane. Often transversalis fascia opened earlier is sutured back using non-absorbable suture material in front of the placed mesh.
- *Stoppa's giant prosthesis reinforcement of visceral sac (GPRVS):* It is done in large hernias, hernias in elderly, bilateral hernias, recurrent and re-recurrent hernias, hernia with very lax abdomen, and hernia with collagen diseases like Marfan's syndrome. Horizontal length (size) of the mesh is 2 cm less than distance between two anterior superior iliac spines and vertical length (size) is distance between the umbilicus and pubic symphysis. Large mesh is placed between peritoneum and lateral, inferior, anterior abdominal wall which stretches in the lower abdomen and pelvis. It is done through lower midline or Pfannensteil incision. Usually such large mesh is placed without any anchorage.
- *Gilbert mesh repair (patch and plug):* After herniotomy, internal ring is plugged by cone-shaped (umbrella plug) piece of prolene mesh. Later onlay / inlay mesh repair of posterior wall of the inguinal canal is done.
- *Transabdominal preperitoneal laparoscopic mesh repair (TAPP repair):* It is mainly used in irreducible and large hernias.
- *Totally extraperitoneal laparoscopic mesh repair (TEP)* - becoming popular.

Transabdominal Pre Peritoneal Mesh Repair (TAPP) using Laparoscope

This is used in large indirect hernia or irreducible inguinal hernia. 10 mm umbilical port is used for laparoscope. 5 mm ports are placed one on each side on pararectal point at the or above the level of umbilicus so as to achieve adequate triangulation. Contents of the hernia are reduced. Hernial sac is dissected in preperitoneal plane after making horizontal incision at the upper part of the sac opening. Vas, gonadal vessels, pubic bone, inferior epigastric vessels are identified. Once sac is dissected and excised, a prolene/vipro/ultrapro mesh of 15 × 10 cm sized or smaller is placed in preperitoneal space. It is fixed to pubic bone using tacks. Peritoneum is closed with continuous prolene sutures.



Fig. 18.46: Mesh placement in TAPP procedure.

Totally Extra Peritoneal Repair (TEP Repair) using Laparoscope

- This technique is gaining more popularity than TAPP. Through sub-umbilical incision (10 mm) extra peritoneal space is reached. After CO_2 insufflation, another 5 mm port is inserted 4 cm below the first port in the midline. Third 5 mm port is inserted in the same line 4 cm below or in the right iliac fossa. Dissection is carried out downwards carefully, then medially up to the pubic tubercle, iliopectineal ligament, laterally to iliac vessels, and inferior epigastric vessels. Once adequate space is dissected 15 × 15 cm mesh is placed and spread. Care should be taken not to have any folding in the mesh. Mesh may be sutured to iliopectineal ligament. Displacement of mesh is not common. Other side also can be done together.

Anatomical Considerations

- Preperitoneal space is a potential space in front of the peritoneum, behind the transversalis fascia and anterior rectus muscle. Below in front of the urinary bladder it is called as *space of Retzius* (medially), laterally it is called as *space of Bogros*. Median umbilical fold is formed by urachus in the midline. Medial umbilical ligament is formed by obliterated umbilical arteries, lateral umbilical fold by inferior epigastric vessels. Three fossae are lying in relation to these folds- supravesical and medial fossae are medial to lateral umbilical fold which are sites of direct hernia whereas lateral fossa is lateral to lateral umbilical fold and is site of indirect hernia.
- In 1956 *Fruchaud* described his *myopectineal orifice* bounded medially by the lateral border of rectus abdominis, laterally by iliopsoas, superiorly by conjoint tendon and inferiorly by pectin pubis. This area is the site of groin hernia which should be covered by mesh of adequate size to strengthen the defect and to prevent the recurrence. Iliopubic tract is analogue of the inguinal ligament, extends from Cooper's ligament to anterior superior iliac spine which divides endoscopic view of preperitoneal space into *superior compartment* (contains inferior epigastric artery, Hesselbach's triangle, cord structures and is site of indirect inguinal hernia) and *inferior compartment* (contains femoral canal, iliac vessels, iliopsoas muscle, genitofemoral nerve, lateral femoral cutaneous nerve). External iliac vessels lie in a triangle formed by gonadal vessels laterally, vas deferens medially and peritoneal reflection inferiorly (*triangle of doom*).
- Aberrant obturator artery is an occasional branch of inferior epigastric artery replacing its pubic branch travels across Cooper's ligament, which during fixation of mesh can cause torrential haemorrhage-*circle of death*. *Triangle of pain* is formed by gonadal vessels medially, iliopubic tract laterally and peritoneal reflection below. Genitofemoral nerve and lateral cutaneous nerve of thigh traverse this triangle. Injury to these nerves either by dissection or by tacks cause postoperative pain. Tacks / staplers should not be placed in this triangle.

Spigelian line: Runs along the lateral border of rectus sheath and extends from the pubic tubercle to the tip of the 9th costal cartilage.

Spigelian fascia: Is the fascia between the aponeurosis of external and internal oblique, transversus abdominis and recuts sheath.


(TAPP)
10 mm port
5 mm(TAPP)
-5 mm(TAPP)
-10 mm(TEP)
-5 mm(TEP)
-5 mm(TEP)

Fig. 18.47: Ports used for TEP and for TAPP.


10 mm camera port
5 mm working port
5 mm working port

Fig. 18.49: Port incisions in TEP.


Skin
Abdominal muscles (external/internal/transverse)
Rectus muscle
Transversalis fascia
Preperitoneal space
Peritoneum
Intestines
Normal anatomy of abdominal wall
Skin
Abdominal muscles (external/internal/transverse)
Rectus muscle
Transversalis fascia
Preperitoneal space
Peritoneum
Intestines
Preperitoneal approach (for TEP)
Skin
Abdominal muscles (external/internal/transverse)
Rectus muscle
Transversalis fascia
Preperitoneal space
Peritoneum
Intestines
Transabdominal preperitoneal approach (TAPP)

Fig. 18.48: Diagrammatic representations of TEP and TAPP.


Direct defect
IEA
Pubic symhpysis
Cord
Cooper's ligament

Fig. 18.50: TEP after dissection prior to placement of mesh. Direct defect, inferior epigastric artery, pubic symphysis and Cooper's ligament are clearly seen.


IE Vessels
Cooper's ligament
Indirect sac

Fig. 18.51: TEP after dissection showing indirect sac, inferior epigastric vessels, Cooper's ligament.



Fig. 18.52: TEP mesh placement in preperitoneal space.

Indications for TEP	*Contraindications for TEP*
• Recurrent hernia • Bilateral hernia • Indirect/direct/femoral hernia	• Obstructed/strangulated inguinal hernias • Ascites • Bleeding disorders
Landmarks to be identified in TEP	*Principles in TEP*
• Pubic bone midline • Inferior epigastric artery • Copper's ligament • Iliopubic tract • Cord and vas deferens • Psoas muscle and nerves in relation	• Head-down supine position • Surgeon standing on opposite side of hernia • Camera person placed on opposite side of hernia • Monitor at foot end • Catheterise/empty the bladder properly prior to TEP • Adequate wide space creation • Careful dissection of cord and sac • Ligate indirect sac • Mesh should not be fixed laterally • Size of mesh is 15 × 15 cm • Two point fixation- one at pubic bone other at Cooper's ligament by tacks /staplers

Difficulties and complications in TEP repair

- Difficulty in dissecting indirect sac. Cord/vas injury
- Inadvertent opening of the sac/peritoneum and creation of pneumoperitoneum.
- Injuries to major structures like iliac vessels- 0.5- 1.0%
- Displacement of mesh or erosion into structures like urinary bladder—rarely may occur.
- Nerve injury
- Formation of seroma/haematoma
- Infection
- Recurrence

Advantages of TEP repair

- Approach is totally extraperitoneal
- Small incision
- Proper placement of mesh in right space that is preperitoneal space
- Peritoneal cavity is intact and not opened

MALGAIGNE BULGING

- It is protrusion of abdominal wall muscles during leg rising test as weak, soft, supple, swelling, which signifies poor abdominal muscle tone. It also concludes that particular hernia requires mesh repair (***hernioplasty***) as surgical treatment.
- It is common in old age, obese patient.

INCARCERATED HERNIA

- Here the lumen of the portion of colon occupying a hernial sac is blocked with *faeces*. Here scybalous content of the bowel should be capable of being indented with the finger, like putty.
- In incarcerated hernia, sac and contents are densely adherent to each other (contents are fixed to sac). It is always irreducible; often obstructed but may not be strangulated.

STRANGULATED HERNIA

Pathology

It occurs when blood supply of the contents of hernia is seriously impaired leading to formation of gangrene.

Common bacteria in strangulated hernia

- *E. coli*
- Anaerobic streptococci
- Anaerobic bacteria
- Klebsiella

Smile is the curve which puts everything straight.

Obstruction
↓
Initially venous return is impaired
↓
Congestion of the bowel
↓
Further dilatation of the bowel which becomes purple coloured
↓
Fluid collects in the sac
↓
Eventually arterial blood supply is impaired
↓
Bowel becomes dark, brownish black coloured with flabby and friable wall
↓
Bacteria migrate transerosally and multiply in fluid of the sac
↓
Perforation occurs at the site of constriction ring
↓
Peritonitis occurs.

- Strangulation commonly occurs in the small bowel and also in large bowel. Occasionally strangulated omentocele also can occur without any intestinal obstruction.
- Strangulation can occur in inguinal, femoral, obturator, umbilical or any hernias.
- Indirect inguinal hernia is more prone for strangulation than direct inguinal hernia. It is due to narrow neck, adhesions, narrow external ring in children.



Fig. 18.53: Picture showing strangulated hernia with toxic fluid and site of constriction.



Fig. 18.54: Strangulated inguinal hernia will be tender and irreducible without impulse on coughing.



Fig. 18.55: Hernia with gangrenous omentum. Note the colour of the gangrenous omentum.

- Part of circumference of the bowel when strangulated, is called as ***Richter's hernia*** wherein the patient presents with diarrhoea, toxicity mimicking *gastroenteritis*. Richter's hernia is more common with femoral, obturator hernias.

Causes of strangulation

- Narrow neck
- Adhesions
- Irreducibility
- Long-time, large hernia with adhesions

Maydl's Hernia (Hernia-in-W): Here a loop of bowel in the form of 'W' lies in the hernial sac and the centre portion of the 'W' loop is strangulated and lies within the abdominal cavity**.** Thus local tenderness over the hernia is not marked and hernia gets reduced with the strangulated loop in the centre of the ***"W"***. Strangulation in this case is often missed during surgery and may lead to peritonitis due to retained gangrenous loop.



Fig. 18.56: Maydl's Hernia (Hernia-in-W).

Clinical Features of Strangulated Hernia

- Sudden severe pain, initially over a pre-existing hernia which later becomes generalised over the abdomen.
- Persistent vomiting, constipation and distension of the abdomen.
- *Hernia is tense, severely tender, irreducible and without any expansile impulse on coughing. Rebound tenderness is diagnostic.*
- Features of toxicity and dehydration.
- Electrolyte imbalance.
- Abdominal distension with guarding and rigidity.
- Oliguria.

Features of strangulated hernia

- Tense, tender, irreducible
- No impulse on coughing
- Shock, toxicity
- Features of obstruction when there is enterocele
- Abdominal distension, vomiting
- Rebound tenderness

Strangulation during Infancy

Incidence is 4%. Female to male ratio is 5:1

In female infants, the content may be ovary with or without fallopian tube

Taxis

- Often in irreducible hernia, *reduction* of hernia is *tried* by elevation, sedation and ***taxis*** (i.e. with flexion and medial rotation of the hip, reduction of hernia is tried).
- *In obstructed hernia, taxis may be dangerous* as during taxis, contusion and rupture of the intestinal wall can occur. Reduction-en-masse may mask the gangrenous bowel existing in the sac. Inner gangrenous loop of Maydl's hernia may be missed. Rupture of the sac extraperitoneally is also a possibility.
- *Taxis has no role in femoral hernia and strangulated hernia.* If tried, contusion, reduction-en-masse and rupture of the sac can occur.

Taxis

- Used in irreducible or partially reducible hernia
- *Trial reduction by flexing and medially rotating the hip*
- It is dangerous in-
  - Obstructed hernia
  - Maydl's hernia

  (As rupture can occur leading to peritonitis)
- No role in femoral and strangulated hernia



Fig. 18.57: In an obstructed hernia, if reduction is forced it may get reduced with the sac and ring with the obstructed/strangulated bowel.

- ***In strangulated omentum*** features of obstruction are not present (i.e. vomiting, constipation). Omentum becomes congested, oedematous and black in colour which secretes toxic fluid with secondary bacterial infection. But here, initially the sepsis is slower than that of strangulated intestinal obstruction.

The most important thing that you wear is the expression on your face.

- Eventually the infection spreads causing diffuse peritonitis. Downward spread of infection can cause scrotal abscess.

Investigations

- Plain X-ray abdomen in erect posture shows multiple air-fluid levels.
- Serum electrolytes.
- Blood urea and serum creatinine.
- Total count is increased.
- U/S abdomen.

Strangulation without obstruction

- Richter's hernia
- Omentocele

Treatment of Strangulated Hernia

- The patient is admitted.
- Ryle's tube aspiration.
- Intravenous fluids to correct dehydration and electrolyte imbalance.
- Antibiotics.
- Catheterisation to maintain adequate urine output.
- *Emergency surgery* —



Fig. 18.58: Incision for strangulated hernia is obliquely placed extending to the scrotum.

Groin incision is made with incision extending into the most prominent area of the swelling.

↓

Sac is exposed.

↓

Constriction ring and superficial ring is released(cut).

↓

Sac is opened carefully **without allowing the spillage of fluid** (Usually spillage occurs extraperitoneally)

↓

Fluid is sucked with a suction apparatus.

↓

The bowel is held with fingers so as to prevent it from getting reduced.

↓

The viability of the bowel is checked by **colour, peristalsis, pulsation, bleeding.**

↓

When gangrenous, resection and anastomosis is done and drain is placed.



Fig. 18.59A



Fig. 18.59B



Fig. 18.59C



Fig. 18.59D



Fig. 18.59E



Fig. 18.59F

Figs 18.59A to F: Strangulated hernia – lift side. It is tense, tender, without any impulse on coughing. Note the incision, discoloured sac, content (gangrenous bowel) and proximal viable bowel.

Bassini's repair is done by placing interrupted non-absorbable sutures. Antibiotics, IV fluids are continued. Drain is removed in 4-5 days. Once the bowel movement begins, oral diet is started (in 5 days).

- **Postoperative problems**
  Infection, leak with fistula, septicaemia.
- *Note: During surgery for strangulated hernia mesh is usually not used, only repair is done.*

SLIDING HERNIA (HERNIA-EN-GLISSADE)

- Here posterior wall of the sac is not only formed by the parietal peritoneum, but also by sigmoid colon on left side; caecum on right side and often with portion of the bladder (Both sides).
- Rarely small bowel sliding hernia or sacless sliding hernia can occur.
- Content of the sac is usually small bowel or omentum.
- *Sliding hernia occurs exclusively in males. Mainly on the left side.*
- Bilaterality is extremely rare.
- It is seen commonly in adults and elderly.
- Huge hernia can occur which extends into the scrotum and do not get reduced totally.



Fig. 18.60: Sliding hernia with urinary bladder as posterior wall of the sac.

Clinical Features (2%)

Large globular swelling in the inguinal region descending into the scrotum, often irreducible.

It takes 26 muscles to smile, and 62 muscles to frown.


Posterior wall of sac
Sac
Content

Fig. 18.61: Sliding hernia (Hernia-en-Glissade).

Small bowel as the content of sliding hernia can lead to strangulation.

Treatment: Always surgery

- *Posterior wall of the sac should not be separated from large bowel or bladder*. If tried, injury may result to these organs leading to faecal or urinary fistulas.
- Partially excised sac is pushed into the peritoneal cavity with posterior wall and repair is done usually using *prolene mesh* (Hernioplasty).
    - Truss should not be used in sliding hernia.

PANTALOON HERNIA (DOUBLE HERNIA, SADDLE HERNIA, ROMBERG HERNIA)

- Here both direct and indirect inguinal sacs are present and clinically present *as direct hernia.*
- During surgery, indirect sac may be missed and so leads to *recurrent hernia* through retained (or unidentified) indirect sac.


Inf epigastric artery
Direct sac
Indirect sac

Fig. 18.62: Saddle/Pantaloon hernia. It is on either side of the inferior epigastric artery having both direct and indirect sacs.

- Here both medial and lateral sacs *straddle* the inferior epigastric artery.
- It is one of the causes for recurrent hernia.

INFANTILE HERNIA

- Clinically difficult to diagnose.
- Often it is diagnosed on table.
- Processus vaginalis is closed at internal ring and hernial sac either invaginates processus vaginalis as "inverted umbrella' or comes behind processus vaginalis.

FEMORAL HERNIA

Surgical Anatomy of Femoral Canal

It is the medial, most compartment of the femoral sheath, which extends from femoral ring above to saphenous opening below. It contains fat, lymphatics, lymph node of Cloquet. It is 1.25 cm long and 1.25 cm wide at the base. Below it is closed by cribriform fascia.

Femoral ring is bounded anteriorly by inguinal ligament; posteriorly by ilio pectineal ligament of Cooper, pubic bone and fascia covering the pectineus muscle; medially by concave, sharp lacunar (Gimbernat's) ligament; laterally by a thin septum separating from femoral vein.


ASIS
IL
F N
F A
F V
Lacunar ligament
Pubic bone
Sac
Femoral hernia

Fig. 18.63: Surgical anatomy of femoral hernia.


Asis
Lateral cut nerve of thigh
FN
FA
FV
Adductor longus
Lateral cut nerve of thigh
PT
Profunda femoris arterey
Sartorius

Fig. 18.64: Femoral triangle.



Fig. 18.65: Hernia; Inguinal hernia is above and medial to tubercle, and femoral hernia is below and lateral.

Aetiology

- Wide femoral canal.
- Multiple pregnancies.

Pathology in Femoral Hernia

Through femoral canal, hernial sac descends down vertically upto saphenous opening and then escapes out into the loose areolar tissue to expand out like a ***retort.*** Because of its irregular pathway and narrow neck, it is more prone for obstruction and strangulation. During surgery, precaution should be taken about the femoral vein and pubic branch of obturator artery (or accessory obturator artery) which often may get injured leading to torrential haemorrhage.

Clinical Features

- Common in females (2:1 ratio), common in multipara.
- Rare before puberty. 20% occurs bilateral, however more common on right side.
- Presents as a swelling in the groin *below and lateral* to the pubic tubercle. (Inguinal hernia is *above and medial* to the pubic tubercle).
- Swelling, impulse on coughing, reducibility, gurgling sound during reduction, dragging pain, are the usual features.
- When obstruction and strangulation occurs which is more common, presents with features of intestinal obstruction—painful, tender, inflamed, irreducible swelling without any impulse. They also present with abdominal distension, vomiting and features of toxicity.
- Often femoral hernia can be associated with inguinal hernia also.
- 40% of femoral hernias present as emergency hernia with obstruction/strangulation.

Gaur's sign: In femoral hernia, distension of superficial epigastric and/or circumflex iliac veins occurs due to the pressure by the hernial sac.

Differential diagnosis

1. Inguinal hernia
2. An enlarged Cloquet lymph node of any cause
3. Psoas abscess—Psoas spasm with flexed hip but difficulty in extension
4. Lipoma
5. Femoral aneurysm
6. Distended psoas bursa (Disappears on hip flexion)
7. *Saphena varix*—It is enlarged terminal portion of long saphenous vein. It is soft, disappears on lying down, fluid thrill, impulse on coughing and venous hum on auscultation are present. There is associated varicose veins on leg
8. Haematoma in the region

Hydrocele of femoral hernia occurs when adherent omentum which is the content secretes fluid into the sac.

Herniation through a gap in the lacunar ligament (medial) is always strangulated and is called as *Laugier's femoral hernia (L for L).*

In congenital dislocation of hip, femoral hernia occurs *behind* the femoral vessels—*Narath's femoral hernia.*

If sac lies under the pectineal fascia, is called as *Cloquet's hernia.*

Strangulation and Richter's hernia are common in femoral hernia.

Often on medial side, a portion of bladder forms the wall of the femoral hernial sac—*sliding-femoral hernia***.**

Femoral hernia—occurs medial to femoral vein
Narath's hernia—occurs behind femoral artery, in congenital dislocation of hip
Hesselbach's hernia—occurs lateral to femoral artery
Serofini's hernia—occurs behind femoral vessels
Laugier's hernia—through lacunar ligament
Teale's hernia—in front femoral vessels
Callison-Cloquet hernia—through pectineal fascia



Fig. 18.66: Femoral hernia on right side. Note the location below the inguinal ligament. Femoral hernia is common on right side. It is common in females.


Inguinal hernia
Inguinal hernia
Femoral hernia

Fig. 18.67: Right side femoral hernia in a male patient. Patient is also having bilateral inguinal hernia. Femoral hernia is rare in males.



Fig. 18.68: Right side femoral hernia in a female patient. Femoral hernia is common in females. In females commonest hernia is inguinal hernia.

Treatment

Approaches:


Mc'Evedy -high
Lotheissen-inguinal
Lockwood- low
4
3
2
1
5
1. Femoral hernia
2. Femoral vein
3. Femoral artery
4. Femoral nerve
5. Lacunar/Cooper's ligament

Fig. 18.69: Different surgical approaches for femoral hernia.

1. ***Lockwood low operation***: Here sac is approached below the inguinal ligament through groin crease incision (or over the swelling) so that fundus of sac is dissected by direct vision and repair is done from below.


Lacunar ligament
Inguinal ligament
Repair
FN
FA
FV
Cooper's ligament

Fig. 18.70: Femoral hernia repair. Inguinal ligament is approximated to Cooper's [Iliopectineal line] ligament. In Lotheissen's repair conjoined tendon is sutured to ilio pectineal line.

Here inguinal ligament is sutured to Cooper's ligament.

2. ***Mc'Evedy-High operation:*** A incision is made over the femoral canal extending vertically above the inguinal ligament. Sac is dissected from below, neck from above and repair is done from above. It gives a very good exposure of both neck, fundus of sac and repair is also easier. It is done in strangulated femoral hernia.

3. ***Lotheissen's operation*:** It is through inguinal canal approach (like for inguinal hernia). Transversalis fascia is opened and neck of the sac is identified in the femoral ring. Sac is dissected from above, neck is ligated and repair is done.

   Lotheissen's repair: After herniotomy, *conjoined tendon is sutured to ilio-pectineal line* (ligament) by interrupted sutures (2 or 3), using non-absorbable monofilament sutures. Care should be taken to avoid injury to femoral vein, pubic branch of obturator artery, bladder.

   Complications: Bleeding haematoma, abscess formation.
4. ***AK Henry's approach***: Repair of bilateral femoral hernia through lower abdominal incision.
5. Polypropylene mesh can be buttressed over the femoral canal to close the defect.

VENTRAL HERNIA

Any protrusion through abdominal wall with the exception of hernia through the inguinofemoral region is defined as *ventral hernia*. Incisional hernia (80%) and primary defects in abdominal fascia which can cause umbilical hernia, epigastric hernia, paraumbilical hernia or Spigelian hernia are grouped under ventral hernia.

Ventral hernia can be –
- Reducible.
- Irreducible.
- Obstructed.
- Strangulated.
- Single.
- Multiple small defects (*Swiss cheese hernia*).





Figs 18.71A and B: Large ventral hernias. It needs proper mesh repair.

Causes
- Congenital defect.
- Obesity.
- Smoking.
- Chronic cough.

Preoperative preparation
- Proper skin hygiene.
- Respiratory care.
- Control of obesity.
- Antibiotics.

Management
- Relevant investigations
- Open mesh repair – inlay; onlay
- Laparoscopic mesh placement – underlay (directly in front of the contents) using duval mesh or four layered mesh.



Fig. 18.72: Port placement for laparoscopic ventral hernia repair. Left subcostal point is *palmer point*.

A friend is your second identity.



Fig. 18.73: Laparoscopic view of ventral hernia with omentum as irreducible content. Content is released and duval or four-layered mesh is fixed with tackers or sutures.

INCISIONAL HERNIA

- It is herniation through a weak abdominal scar (scar of previous surgery).
- It is common in old age and obese individuals.



Fig. 18.74: Incisional hernia adherent to skin. Note the ulceration over the summit. Patient underwent resection and anastomosis with removal of the ulcerated skin with mesh placement.

Additional History to be Collected in Incisional Hernia

- Details of surgery that patient has undergone earlier. Duration after how long incisional hernia has occurred is important.
- History of wound infection, wound dehiscence, whether surgery done was an emergency or elective, and tension sutures placed or not.
- History of pain, irreducibility and details of precipitating factors to be asked.
- Other precipitating factors are similar to inguinal hernia like smoking, urinary/respiratory/abdominal symptoms.

Predisposing Factors

- Vertical scar, midline scar, lower abdominal scar—may injure the nerves of the abdominal muscles.
- Scar of major surgeries (biliary, pancreatic).
- Scar of emergency surgeries (peritonitis, acute abdomen).
- Faulty technique of closure.
- Poor nutritional status of the patient.
- Presence of cough, tuberculosis, jaundice, anaemia, hypoproteinaemia.
- Malignancy, immunosuppression.
- Smoking in postoperative period.
- Causes which increases the intra-abdominal pressure (BPH, straining, stricture urethra or rectum, ascites).

Factors responsible for development of incisional hernia

- Vertical incision has got higher chances of incisional hernia than horizontal incision
- Layered closure of the abdomen has got higher chance than single layer
- Continuous closure has got higher chances than interrupted closure
- Using absorbable suture material has got higher chances of hernia than non-absorbable sutures
- Emergency surgical wound has higher chances than elective surgical wound
- Laparotomy for peritonitis, acute abdomen, and trauma can commonly cause incisional hernia
- Drainage through the main laparotomy wound may precipitate formation of incisional hernia
- Chronic cough, smoking, obstructive uropathy, constipation can precipitate incisional hernia
- Diabetes, old age, malnutrition, malignancy, anaemia, hypoproteinaemia, jaundice, ascites, liver disease, uraemia, steroid therapy, immunosuppressive diseases are other precipitating factors

Clinical Features

- Swelling in the scar region.
- Pain.
- Impulse on coughing.
- Gurgling sound.
- Often bowel peristalsis may be visible under the skin.
- Eventually features of irreducibility, obstruction, strangulation is seen.



Figs 18.75A and C: Incisional hernia in a patient during straining and during relaxing.



Fig. 18.76: Incisional hernia which is irreducible with visible bowel beneath.

Defect is felt and assessed during head rising, by placing fingers over the scar horizontally
Size of the defect is very important

- Hernia is common in lower abdomen.
- It may be *small or large; huge or massive (diffuse).*
- Scar, its extent and location, whether healed primarily or secondarily, skin over the scar and swelling is noted. Details of the swelling with expansile impulse on coughing and *examination both in lying down and standing are done.*
- *Gap cannot be assessed in an irreducible hernia.*

Type of defects in incisional hernia

- Small defect
- Large and wide defect
- Very large defect
- Massive / diffuse
- Multiple defects

Note:

- Size of the defect is important to decide the type of surgical closure in incisional hernia.
- Midline hernia expels the content more outwards due to contraction of rectus muscles on both sides.

Investigations: Always the precipitating factors must be looked for:

- Chest X-ray.
- U/S abdomen.
- Tests relevant for causes.

Complications of incisional hernia: Irreducibility, obstruction, strangulation, incarceration.

Luck is when opportunity knocks and you answer.



Fig. 18.77: CT scan abdomen showing incisional hernia.

Preoperative Preparations for Incisional Hernia Surgery

- Reduction in weight and control of obesity.
- Nutrition, control of anaemia.
- Treatment for diabetes, hypertension, cardiac diseases, respiratory problems.
- Treating the precipitating causes.
- Chest X-ray, U/ S abdomen to be done.
- Massive incisional hernia after reduction might cause IVC compression, paralytic ileus and diaphragmatic elevation with respiratory embarrassment (*abdominal compartment syndrome*). It is prevented by prior increasing the capacity of peritoneal cavity by creating pneumoperitoneum using CO_2 so as to increase the peritoneal pressure by 12-15 cm of H_2O, daily for 3-6 weeks. Later definitive surgery is done.



Fig. 18.78: (A) Keel operation and (B) Nuttall's operation.

Treatment Strategy for Incisional Hernia

- **Cattell's operation**: When the defect is less than 3 cm, and if the patient is having adequate abdominal muscle tone, *layer by layer anatomical repair* is done using monofilament nonabsorbable suture material like *polypropylene/polyethylene*, ideally with interrupted sutures. Sac should be dissected, ligated and excised prior to repair. Peritoneum and posterior rectus sheath is apposed as first layer and anterior rectus sheath as second layer.
- **Double breasting of the rectus sheath** using interrupted non-absorbable sutures using monofilament suture material. It is overlapping the rectus sheath in two layers with two rows of sutures.
- **Mesh repair of the incisional hernia** defect is always better and ideal with less chances of recurrence. Adequate sized mesh is placed either outer to peritoneum (*inlay*), or outer to musculoaponeurotic abdominal layer (*onlay / overlay*), or occasionally combined inlay and onlay mesh placement, both deep to peritoneum and outer to musculoaponeurotic layer. *Rive's Stoppa's mesh placement* for incisional hernia is placing mesh between posterior rectus sheath and rectus muscle. Commonly polypropylene mesh is used. Other materials used are Dacron, polytetrafluroethylene (PTFE) mesh, polyglycolic mesh (vicryl mesh) or combined polypropylene and polyglycolic acid mesh (vipro mesh). Drain (suction drain) must be placed after surgery. Mesh repair is ideal approach for incisional hernia. Prevention of infection / haemostasis and drainage are important.
- **Laparoscopic mesh repair is done for incisional hernia** by placing a mesh under the defect laparoscopically in intraperitoneal plane. The only problem of this underlay placement is chances of adhesion and GI fistula formation, but still it is found to be safer. Laparoscopic preperitoneal mesh placement is also done for smaller defects. Now dual mesh (PTFE) or four layered mesh are available. Here mesh is placed under the peritoneum deep to the defect after reducing the contents. Mesh is fixed with sutures and tacks. In four-layered mesh, deepest 1st layer is absorbable cellulose which allows new peritoneum to creep underneath. 2nd layer is PDS / PTFE mesh 3rd layer is polypropylene mesh and the last 4th layer is again PDS / PTFE mesh. It is ideal but costly.
- **Keel operation** is done in large defect. Scar is excised and is dissected beyond the margin of the defect. Sac is never opened unless there is obstruction of the content. Sac in inverted using continuous/interrupted inverting non-absorbable sutures, layer by layer until

the defect margins are apposed together which is then again sutured with interrupted sutures. Keel is inverted beam of the ship.

- **Nuttall's operation** is done for lower midline incisional hernia. Recti attachments are detached from the pubic bones and are crossed over to fix to opposite pubic bones so as to create a firm abdominal wall support by crossed recti muscles.

Different Types of Mesh Repair for Incisional Hernia

- *Outer to peritoneum is ideal method (inlay):* Large sized mesh is placed in pre-peritoneum. It need not be fixed as abdominal pressure keeps it in position.
- *Under the peritoneum, directly over the content (underlay):* Now it is accepted but there are chances of adhesions/fistula formation. It is used in laparoscopic repair. Duval mesh/four-layered mesh is used.
- *Overlay* mesh placed outer to musculoaponeurotic layer.
- *Combined inlay and overlay* with two layers of mesh.
- *Rive's Stoppa's method* of placing mesh between posterior rectus sheath and rectus muscle widely.

Surgeries for incisional hernia

- Mesh repair—commonly done and ideal
- Layer by layer closure—Cattell's operation
- Double breasting of the rectus sheath
- Keel operation—not commonly used now
- Nuttall's operation—not commonly used now

Postoperative Care

- Antibiotics.
- Analgesics.
- Nasogastric aspiration.
- Abdominal binder for support.
- Prevention of paralytic ileus.
- Control of obesity and other precipitating factors.
- Stop smoking and treat other associated causes.
- Early ambulation.
- Fluid management, catheterisation.
- Drain should be kept until drainage becomes minimal.
- Abdominal binder is used to support abdominal wall during recovery period.

Additional Problems in Large Incisional Hernia

- While reducing the bulky contents like bowel and omentum, inadequate intraabdominal capacity leads to increased intraabdominal pressure causing IVC compression, mesenteric oedema followed by stasis of splanchnic bed, paralytic ileus, diaphragmatic elevation and respiratory distress (*abdominal compartment syndrome*), urinary and bowel disturbances. Abdominal capacity can be raised by creating regular pneumoperitoneum over the period of 3-6 weeks.
- Lordosis and back pain may be presenting feature.
- Sac and contents may get adherent to the thin skin over the summit of the hernia leading to skin ulceration and occasionally fistula formation.
- Often might need resection of the adherent bowel segment.
- Large mesh placement is required.

UMBILICAL HERNIA

- It is herniation through a weak umbilical scar (cicatrix).
- It is common in infants and children, occurs commonly due to neonatal sepsis.
- Male : female :: 2:1.
- It is seen in 20% of newborn infants.

Clinical Features

- Presents with a swelling in the umbilical region within first few months after birth, the size increases during crying. It is hemispherical in shape.
- Defect can be felt with finger during crying.
- Occasionally it can go for irreducibility and obstruction which presents with pain, distension, vomiting.



Fig. 18.79: Umbilical hernia.

Those who can't hear the music think the dancer's mad.



Fig. 18.80A and B: Umbilical hernia. Often it can attain large size.

Treatment

Initially conservative. In 93 to 95% of cases, it disappear spontaneously in few months after birth. (masterly inactivity). It can be hastened by adhesive strapping across the abdomen.



Fig. 18.81: Incision for umbilical hernia.

Indications for surgery:

- If persists even after the age of two years.
- If the defect is more than 2 cm in size.

Surgery is through an infraumbilical curvilinear incision. Sac is identified and ligated by transfixation. Defect is closed with interrupted nonabsorbable sutures.



Fig. 18.82: Umbilical hernia. It needs surgical intervention.

PARAUMBILICAL HERNIA (Supra- and Infraumbilical Hernia)

- It occurs commonly in adults. It is a protrusion or herniation through linea alba, just above or below the umbilicus.



Figs 18.83A and B: Large ventral hernia front and side views. It needs preperitoneal mesh repair.

- It enlarges ovally, often attains a large size and sags downwards.
- Neck of the sac is relatively narrow. Contents are usually omentum, small bowel, sometimes large bowel.
- It has got tendency to go for adhesion, irreducibility and obstruction.

Predisposing factors

- Obesity
- Multiple pregnancies
- Flabby abdominal wall

Clinical Features

- Common in females (5:1 ratio).
- It presents as a swelling which has smooth surface, distinct edges, soft, resonant with dragging pain and impulse on coughing. Large hernias can present with intestinal colic due to subacute intestinal obstruction. Eventually strangulation can occur**.**

Treatment

Is always surgery

- ***Mayo's operation*****:** Through a transverse elliptical incision, sac is identified and dissected. Herniotomy is done. *Double breasting of the defect* in the rectus is done by interrupted nonabsorbable sutures.
- Often *umbilectomy* is required and also *mesh placement is beneficial* (when defect is > 4 cm in size).
- If there is strangulation, resection of bowel segment and anastomosis is done followed by repair of the hernia.
- Additional lipectomy (panniculectomy) may be done in case of pendulous abdomen.
- Postoperative weight reduction, use of abdominal binder is required for these patients.

Mayo's operation

- It is done for umbilical and paraumbilical hernia
- Once lower flap or umbilicus is raised above, sac is identified, dissected and opened
- After reducing the contents sac is transfixed using vicryl
- Rectus sheath is repaired by double breasting using nonabsorbable sutures
- Skin flap is closed with a drain. Infection, recurrences are known complications

EPIGASTRIC HERNIA (Fatty hernia of linea alba)

- It is 10% common.
- 20% of epigastric hernias are multiple—Swiss-*cheese like*.
- It occurs usually through a defect in the decussation of the fibres of linea alba, any where between xiphoid process and umbilicus.
- Extraperitoneal fat protrudes through the defect as fatty hernia of the linea alba presenting like a swelling in the upper midline with an impulse on coughing.
- *It is sacless hernia.* Later protrusion enlarges and drags a pouch of peritoneum, presenting as a *true epigastric hernia*.



Fig. 18.84: Epigastric hernia.

- Content of true epigastric hernia is usually omentum, sometimes it may be small bowel.
- Common in muscular men; manual labourers.



Fig. 18.85: Epigastric hernia. Note the location of epigastric hernia above the umbilicus. Initially it is sacless but later sac with content develops.

Clinical Features

- *Often symptomless.*
- Swelling in the epigastric region which is tender.
- Pain in epigastric region. It is often associated with peptic ulcer and so pain may be due to peptic ulcer. So gastroscopy is done to rule out acid peptic disease.
- Impulse on coughing; defect in the epigastric region are also found.
- Irreducibility, obstruction, strangulation as seen in any other hernia can also occur in epigastric hernia.

We do not remember days, we remember moments.

Treatment



Figs 18.86A to D: Epigastric hernia – incision, sac and defect.

- Through a vertical incision, sac is dealt with. Defect is closed with non-absorbable interrupted sutures.
- Large defect is supported with preperitoneal mesh.

Interparietal hernias/interstitial hernias

- Herniation through parietal peritoneum into various layers of the abdominal wall
- Common in Down's syndrome, Prune Belly syndrome
- Often it can attain large size
- May mimic abdominal wall lipoma; haematoma
- As neck of the sac is often narrow, can present with irreducibility or obstruction
- Commonly it is deep to external oblique aponeurosis
- *Types* –
  - Preperitoneal - between peritoneum and transversus abdominis muscle – 20%
  - Interparietal / intermuscular-between external oblique and internal oblique; commonest – 60%. It is commonly associated with inguinal hernia
  - Extraparietal (inguino superficial) – herniates through external oblique aponeurosis into subcutaneous plane – 20%
- U/S; X-ray abdomen; often CT confirms the diagnosis
- Through a transverse incision, surgical ligation of sac, repair or mesh placement is the treatment.

SPIGELIAN HERNIA

- It is a type of interparietal hernia occurring at the level of arcuate line through spigelian point.

Hernial sac lies either deep to the internal oblique or between external and internal oblique muscles.

- Semilunar line runs from 9th costal cartilage above to pubic tubercle below.
- It is common between arcuate line to umbilicus (in wider and weaker area).

Clinical Features

- Presents as a soft, reducible mass lateral to the rectus muscle and below the umbilicus, with impulse on coughing. Strangulation is common in spigelian hernia.
- Presence of precipitating factors like obesity, chronic cough, old age, multiple pregnancies.
- Equal in both sexes.

Differential Diagnosis

- Abdominal wall lipoma.
- Soft tissue sarcoma.
- Abdominal wall haematoma.



Fig. 18.87: Spigelian hernia.

Investigation

- Ultrasound abdomen.

Treatment

- Through a lengthy transverse incision herniotomy and later closure of the defect layer by layer using non-absorbable interrupted sutures.
- But often mesh is required to cover the defect properly.



Figs 18.88A and B: Spigelian hernia. On table finding and placement of mesh in same patient.

OBTURATOR HERNIA

- It is hernia occurring through obturator canal between superior ramus of pubis and obturator membrane. It is a rare entity, seen in elderly females (6::1 ratio female to male).

Clinical Features

- Usually presents with features of intestinal obstruction and more often confirmed only on laparotomy.

The wind of anger blows out the lamp of intelligence.

- Rarely seen as a swelling in Scarpa's triangle, deep to the pectineus muscle, with limb in flexed and abducted position. Movement of limb is painful.
- Referred pain in knee joint through geniculate branch of obturator nerve signifies not only obturator hernia but also strangulation—*Howship-Romberg sign.*
- On per vaginal examination, tender swelling is felt over the obturator foramen.
- Here strangulation is usually of Richter's type.

Treatment

- Laparotomy is done and the sac is identified. It is dissected and ligated. If strangulation is present (common), resection and anastomosis is done. Broad ligament is stitched over the opening to prevent recurrence.
- Mesh placement is the ideal way of repairing the obturator defect.



Fig. 18.89: Obturator hernia through obturator canal in obturator foramen. Note also the locations of inguinal and femoral hernias.

RICHTER'S HERNIA

It is a hernia in which the sac contains only a portion of the circumference of the intestine (small bowel). It is usually *seen in femoral and obturator hernia.*

Clinical Features

- It *mimics gastroenteritis* with pain abdomen, diarrhoea, toxicity, vomiting.
- There are no features of intestinal obstruction.
- Constipation does not occur in Richter's hernia.
- Gangrene (strangulation) of a part of bowel occurs, eventually leading to peritonitis.



Fig. 18.90: Strangulated femoral hernia, Richter's type with perforation. Patient underwent resection and anastomosis.



Fig. 18.91: Richter's hernia

Treatment

Resection and anastomosis is done.
The type of hernia is treated.
Mortality increases with delay in surgical intervention.

LUMBAR HERNIA

- It is herniation either through superior or inferior lumbar triangle.
- Superior lumbar triangle *(Grynfelt's/Lesgaft's triangle)* is bounded by sacrospinalis, 12th rib and posterior border of internal oblique.
- Inferior lumbar triangle is bounded by latissimus dorsi, external oblique and iliac crest *(triangle of Petit).*
- Lumbar hernia is common through inferior lumbar triangle.
- It can be—
  - **Primary.**
  - **Secondary,** which is due to previous renal surgery, more common.



Fig. 18.92: Lumbar triangles.

Differential diagnosis

- Lipoma.
- Cold abscess.
- Lumbar phantom hernia.

Treatment

Repair using fascial flaps or mesh.

PHANTOM HERNIA

- It is a muscular bulge as a result of local muscular paralysis due to interference with nerve supply of the affected muscles, like poliomyelitis. It is common in lumbar region. It is often seen in lower abdomen.

Phantom hernia is muscular bulge due muscle paralysis in lumbar region
Phantom limb is feeling of pain in amputated toe or limb
Phantom tumour is tumour like lesion in lung like interlobar pleural effusion



Fig. 18.93: Lumbar incisional hernia – large. Previous lumbar incision scar is visible.

SCIATIC HERNIA

- It is a rare hernia.
- It is the protrusion of the peritoneal sac through the greater or lesser sciatic foramen.

Types

Classified based on their relationship to the pyriformis muscle and ischial spine.

1. Suprapyriformis.
2. Infrapyriformis.
3. Subpyriformis.

Sac lies deep to gluteus maximus. Large hernias protrude below the buttock crease.

Diagnosis

Usually on laparotomy for intestinal obstruction.

Treatment

Defect is covered by fascia mobilised from pyriformis muscle after reducing the sac contents.

DIFFERENT TYPES OF HERNIA

1. Gibbon's hernia—It is hernia with hydrocele.
2. Berger's hernia—Hernia in pouch of Douglas.
3. Romberg hernia—Saddle hernia.
4. Obturator hernia—Hernia through obturator foramen (canal).
5. Grynfelt's hernia—Upper lumbar triangle hernia.
6. Petit's hernia—Lower lumbar triangle hernia.
7. Femoral hernia—Hernia medial to femoral vein.
8. Cloquet's hernia—Hernia through pectineal fascia.
9. Narath's hernia—Behind femoral artery, in congenital dislocation of hip.
10. Hesselbach's hernia—Lateral to femoral artery.
11. Serofini's hernia—Behind femoral vessels.
12. Laugier's hernia—Through lacunar ligament.
13. Teale's hernia—In front of femoral vessels.
14. Richter's hernia—Part of circumference of bowel wall is gangrenous.
15. Littre's hernia—Hernia with Meckel's diverticulum as the content.
16. Sliding hernia—Posterior wall of the sac is formed by colon or bladder.
17. Maydl's hernia—'W' hernia.
18. Phantom hernia—Localised muscle bulge following muscular paralysis.
19. Spigelian hernia—Hernia through spigelian fascia.
20. Mery's hernia—Perineal hernia.

Dream as if you'll live forever, live as if you'll die today.

21. Sciatic hernia—Hernia through greater or lesser sciatic foramen.
22. Little's hernia—Appendix in hernial sac.
23. Beclard's hernia—Femoral hernia through the saphenous opening.
24. Barth's hernia—Hernia between abdominal wall and persistent vitello-intestinal duct.
25. Holthouse's hernia—Inguinal hernia that has turned outwards into the groin.

Self-asessment Questions

- Discuss clinical features and management of strangulated hernia.
- Classification of hernia.
- Sliding hernia.
- Pantaloon hernia.
- Bubonocele.
- Omentocele.
- Oblique inguinal hernia.
- Surgical anatomy of inguinal canal.
- Herniorrhaphy.
- Hernioplasty.
- Direct hernia.
- Hesselbach's triangle.
- Recurrent hernia.
- Malgaigne bulging.
- Surgical anatomy of femoral canal.
- Clinical features and management of femoral hernia.
- Differential diagnosis of femoral hernia.
- Umbilical hernia.
- Exomphalous.
- Gastroschisis.
- Spigelian hernia.
- Obturator hernia.
- Epigastric hernia.
- Richter's hernia.
- Phantom hernia.

19

Oesophagus

Anatomy
Dysphagia
Contrast study of oesophagus
Oesophagoscopy
GORD
Hiatus hernia
Reflux oesophagitis
Barrett's oesophagus
Barret's ulcer
Achalasia cardia
Nut cracker oesophagus
Plummer-Vinson syndrome
Corrosive stricture of oesophagus
Schatzki's rings
Boerhaave's syndrome
Mallory-Weiss syndrome
Tracheo-oesophageal fistula
Oesophageal diverticulum
Carcinoma oesophagus
Benign tumours of the oesophagus
Oesophageal perforation
Foreign body oesophagus

ANATOMY

Oesophagus is a hollow muscular tube which begins at the lower edge of the cricoid cartilage (C_6 vertebra) and ends at oesophagogastric junction (T_{12} vertebra). Upper end is closed by cricopharyngeus muscle which is 18 cm from upper incisors. Lower end is 40 cm from the upper incisors (Upper jaw is fixed and so is used as the land mark to measure, but not the lower jaw which is mobile).

It lies anterior to vertebral column and posterior to the trachea. It lacks serosal layer but is surrounded by a layer of loose fibroareolar adventitia.

Anatomical specialities

1. Lacks serosa (other structure without serosa is rectum).
2. Contains 2 different types of muscles (striated and smooth at proximal 1/3 and distal 2/3 respectively)
3. Contains 2 different types of epithelium.
4. Segmental blood supply.
5. Only part of GIT which do not have Meissner's plexus.
6. Longitudinal arrangement of veins and lymphatics.

It is lined by squamous epithelium throughout the length except the last 3 cm (OG junction) which is lined by columnar epithelium. Submucosa of the oesophagus is thick and strongest part.

Parts

1. ***Cervical oesophagus***: It extends from cricopharyngeus which is the horizontal part of inferior constrictor muscle. Upper oblique part is called as thyropharyngeus. Gap between the two is called as *Killian's dehiscence* which is a *site of occurrence of pharyngeal pouch*. Cervical oesophagus is related to trachea and recurrent laryngeal nerve.
2. ***Thoracic oesophagus:*** Lies initially towards the right side. In lower third it deviates towards the left and continues as abdominal oesophagus. It is related to azygos vein, thoracic duct (which crosses the oesophagus posteriorly from right to left), aorta, pleura and pericardium.
3. ***Abdominal oesophagus*** is 2.5 cm long and grooves behind the left lobe of the liver.

Three areas of anatomic narrowing:

1. Cervical constriction — Occurs at the level of cricopharyngeal sphincter—*Narrowest point of GIT* - 15 cm from upper incisor – site of F/B impaction

Don't go through life, but grow through life.


Oesophagus
Trachea
Thoracic duct
Rt pulm A.
Aorta
Rt bronchus
Lt pulm A.
Lt bronchus
Pulm trunk
Heart border
Diaphragm
Crus
Stomach

Fig. 19.1: Anatomical relations of the oesophagus.

2. Bronchoaortic constriction—Located at the level of T_4 – 25 cm from upper incisor – site of endoscopic perforation
3. Diaphragmatic constriction—Occurs where oesophagus traverses the diaphragm (Level of T_{10}) – 40 cm from upper incisor

Arterial supply of oesophagus

By inferior thyroid artery, oesophageal branches of the aorta, gastric arteries and inferior phrenic arteries.

Venous drainage of oesophagus

By inferior thyroid vein, brachiocephalic vein, left hemiazygos vein, azygos vein, coronary vein, splenic vein and inferior phrenic vein. Veins are longitudinal and they lie in submucosal plane in lower third and in muscular plane above.

Lymphatic drainage

Lymphatic arrangement in oesophagus is longitudinal and so spread of carcinoma to distant lymph nodes occurs early.

Lymph nodes are:

- *Paraoesophageal groups* located in the wall of the oesophagus and are cervical, thoracic, paraoesophageal and paracardial nodes.
- *Perioesophageal groups* located immediately adjacent to oesophageal wall. They are deep cervical, scalene, paratracheal, mediastinal, diaphragmatic, gastric and coeliac lymph nodes.


Descending artery
Clavicle
Horizontal artery
Ascending artery
A
SVC
Azygos vein
Oesophageal venous plexus
Left gastric vein
Portal vein
Splenic vein
B

Figs 19.2A and B: (A) Arterial supply and (B) Venous drainage of oesophagus.


1. Cervical group
2. Lateral cervical group
3. Deep cervical group
4. Upper thoracic group
5. Para tracheal group
6. Subcarinal group
7. Hilar group
8. Middle thoracic group
9. Lower thoracic group
10. Posterior mediastinal (para-aortic) group
11. Diphragmatic group
12. Paracardial group
13. Lesser curvature group
14. Coeliac left gastric group
15. Common hepatic group
16. Greater curvature group
17. Suprapyloric group
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17

Fig. 19.3: Lymphatic drainage of the oesophagus.

Lateral oesophageal groups receive lymph from para and perioesophageal lymph nodes.

- Upper oesophagus drains into supraclavicular nodes.
- Thoracic oesophagus drains into paraoesophageal and tracheo-bronchial nodes in thorax.
- Abdominal oesophagus drains into coeliac nodes.
- However due to longitudinal arrangement of lymphatic plexus in the wall of oesophagus, any group

of (neck/thorax/coeliac) lymph nodes can get involved in diseases at any level.

Nerve Supply

- Oesophagus is innervated by vagus.
- It has got both sympathetic and parasympathetic innervation.
- It has got only *Auerbach's plexus* between longitudinal and circular muscle layers.

Leugart's pouch is prolapse of the wall of the oesophagus like a diverticulum over a band *(Leugart's band)* between the left bronchus and adjacent vertebra.

Physiology

Three types of contractions in the oesophagus:

1. *Primary* — Progressive, triggered by swallowing.
2. *Secondary* — Progressive, generated by distension or irritation.
3. *Tertiary* — Non-progressive.

Presbyoesophagus is less efficient oesophageal peristalsis.

LOWER OESOPHAGEAL SPHINCTER (LOS)

- It is a high physiological pressure zone located in the lower end of the oesophagus in terminal 4 cm, with a pressure of 10-25 mmHg.
- LOS prevents reflux of gastric and duodenal contents.
- It is influenced by food, gastric distension, gastric pathology, smoking, GI hormones, alcohol.
- Normally there is a *transient relaxation period* wherein reflux (*physiological*) occurs but then immediately gets cleared by oesophageal clearance mechanism.
- So *pathological reflux or GORD* can occur due to decreased LOS tone, altered relaxation time, reduced oesophageal clearance mechanism, or other altered mechanical factors.
- Oesophageal clearance mechanism is due to primary oesophageal peristalsis which carries saliva with high bicarbonate content which neutralizes and clears the transient physiological reflux. Manometry with special microtransducers are used to measure the LOS pressure.

DYSPHAGIA

- *Dysphagia* is difficulty in swallowing. Painful swallowing is *odynophagia*.
- It can be *acute* – due to foreign body impaction or acute infection or *chronic* due to causes like stricture or carcinoma, etc.
- Associated hoarseness of voice may be present in advanced pharyngeal or post cricoid carcinomas. At late stage laryngeal carcinoma also can cause dysphagia along with hoarseness of voice.
- Dysphagia can be *oropharyngeal* or *oesophageal* depending on the cause.
- Dysphagia may be due to pathology in *voluntary/pharyngeal phase* of the swallowing wherein patient also develops cough while swallowing. Dysphagia due to problem in *oesophageal involuntary phase* of swallowing is specified by food getting stuck in the pathway. But site of "*food getting stuck*" feeling is not relevant.
- Dysphagia can be *progressive or intermittent*.

Causes of Dysphagia

Common causes–

- Gastro oesophageal reflux diseases (GORD/GERD/Hiatus hernia).

Causes of dysphagia

Extraluminal causes	*Causes in the wall of oesophagus or other area*	*Causes in the lumen*
• Mediastinal nodes – secondaries/lymphoma/tuberculosis • Aortic aneurysm • Rolling hiatus hernia • Thyroid enlargement – malignant • Dysphagia lusoria • Congenital anomalies • Mediastinitis/mass	• Carcinoma oesophagus • Corrosive/tuberculous/inflammatory/congenital stricture oesophagus • GERD • Achalasia cardia • Plummer – Vinson syndrome • Oesophageal diverticulum • Carcinoma posterior 1/3 of tongue/pharynx • Diffuse oesophageal spasm • Congenital anomalies • Retropharyngeal abscess/peritonsillar abscess (Quinsy)/acute tonsillitis/pharyngitis	• Foreign body in the oesophagus – coin/dentures/fish or meat bone *Other causes* Cranial causes (neurological)– • Bulbar palsy/infarction/hemiplegia • Vertebro basilar insufficiency

Instrumentation is the most common cause of oesophageal rupture.

- *Carcinoma oesophagus*: Here dysphagia is of short duration and progressive. 2/3 of the lumen should be blocked by tumour to develop dysphagia.
- *Foreign body in oesophagus*: It may be coin/bone piece/denture. It is common in children. It causes acute dysphagia. It may be often life threatening.
- Carcinoma of pharynx or posterior 1/3 of the tongue.
- *Corrosive strictures*: It is usually alkali stricture. Squamous mucosa is resistant to acid effect to certain extent.
- *Oesophageal candidial infection*: It is becoming common due to immunosuppression in association with HIV infection; steroid therapy; cancer chemotherapy; post transplant period, etc. Presentation is dysphagia and odynophagia. Oral candidiasis (thrush) is obvious. Endoscopy shows whitish curd like plaques in the oesophageal mucosa which can not be moved (whereas food particles can be moved). Barium swallow shows mucosal ulceration and irregular areas. Biopsy confirms the diagnosis. Treatment is oral antifungal as well as topical antifungal therapy.



Figs 19.4A and B: Endoscopic view of the oesophageal candidiasis infection. Note the whitish curd like plaques.

- Plummer – Vinson syndrome.
- Mediastinal swellings – Primary tumours/nodal mass either lymphoma or secondaries or tuberculosis.

Rare causes–

- *Diffuse oesophageal spasm*: They are incoordinated contractions of oesophagus causing chest pain or dysphagia. It is common in distal 2/3 of the oesophagus. Hypertrophy of circular muscle fibres with very high persistent pressure of 400-500 mm Hg is specific. Treatment is calcium channel blockers, vasodilators, endoscopic dilatation and extended oesophageal surgical myotomy up to the aortic arch (very useful especially for dysphagia; not much for chest pain).
- Oesophageal diverticula, Chaga's disease.
- *Dysphagia lusoria:* It is a congenital vascular anomaly of aortic root. *Aortic arch anomalies* are – double arch (40%), right arch and left ligamentum arteriosum (25%), anomalous innominate or common carotid artery or aberrant right subclavian artery (10%). It is due to disappearance of proximal right 4th aortic arch instead of distal portion. All patients having this anomaly (*dysphagia lusoria*) have got an *aberrant right subclavian artery* in a transposed position arising from descending aorta that courses posterior to oesophagus. Often there will be a complete *vascular ring* around trachea and oesophagus. It is categorised based on their specific subclavian anomaly – depends on presence of aneurysm, occlusive disease and compression. Commonly they are asymptomatic. Presentations may be dysphagia, chest pain, stridor, wheeze, recurrent respiratory infection (usually presents after the age of 40).

  Investigations: CT chest, MRI, chest X-ray, barium swallow (T4 level diagonal impression) and endoscopy (Shows pulsating extraluminal compressive mass).

  Treatment is reconstruction or ligation of aberrant right subclavian artery by sternotomy/by neck approach.
- *Thyroid swelling*: It is uncommon to develop dysphagia in a thyroid swelling. There will be always dyspnoea when dysphasia develops. Large malignant thyroid or anaplastic thyroid can cause dysphagia with dyspnoea or stridor.
- *Boerhaave's syndrome*: It is vertical full thickness tear of lower oesophagus due to vomiting with closed glottis. It is often life threatening and emergency.
- Neurological causes like stroke, bulbar palsy, motor neuron disease, Parkinson's disease, etc.
- Congenital anomalies of oesophagus.
- *Drug induced dysphagia*: Drugs like KCl, quinine, NSAID can cause dysphagia.
- Mediastinal fibrosis.

Evaluation of a Patient with Dysphagia

- Proper history.
- Haematocrit.
- Chest X-ray often shows mediastinal mass lesion/foreign body.
- *Oesophagoscopy*: Once lesion is detected, it is treated accordingly. Biopsy from lesions, endotherapy if needed should be carried out (like F/B removal; stricture dilatation; sclerotherapy).
- Barium swallow may show irregular filling defect or extrinsic compression.
- CT scan chest is very useful method to identify the anatomical location of the cause (nodes/tumour/aorta/cardiac cause/congenital). Extent, spread, nodal status, size and operability of tumour also well-assessed.

- Oesophageal manometry in achalasia cardia/GERD.
- 24 hours pH monitoring is ideal and most accurate for GERD. Small pH probe (transnasal catheter) is passed into the distal oesophagus 5 cm proximal to upper margin of LOS under manometry guidance. Probe is connected to a digital recorder worn by the patient for 24 hours. Record is analysed using a computer. A pH less than 4 for more than 4% of total 24 hours period (more than near to one hour in toto in 24 hours) is pathological reflux. It is often assessed by scoring system. Radio telemetry pH probes are used now without any nasal tube. It is passed and placed on the oesophageal wall using endoscope.
- Endosonography is very useful in many conditions causing dysphagia. It can assess site, layers of the oesophagus, nodes, spread, etc. properly. Different layers are seen as alternating hyper echoic and hypo echoic bands.
- Ultrasound abdomen to see abdominal nodes/liver/ascites.
- MRI study.

Treatment for Dysphagia

Depends on cause – Modified Heller's myotomy; oesophageal resection; dilatation; F/B removal, etc.

CONTRAST STUDY OF OESOPHAGUS

Types

1. Barium swallow using barium sulphate (thick paste).
2. Using water soluble contrast like 'Gastrograffin'.



Figs 19.5A and B: Barium swallow X-rays showing narrowing and irregularity in carcinoma oesophagus

Indications

1. *Barium swallow*
   - Dysphagia due to motility disorder like achalasia cardia, diffuse oesophageal spasm.
   - Dysphagia due to mechanical causes like carcinoma, benign strictures and neoplasms, external compression.
   - Pharyngeal pouch and other diverticula.
   - GORD.
2. *Water soluble contrast radiograph*
   - In suspected oesophageal perforation.
   - Leaking oesophageal anastomosis.

Important Findings in Barium Swallow

- Achalasia cardia—*'Bird beak'* appearance, as the oesophagus is grossly dilated above an apparent narrowing at the cardia. In long standing cases—'sigmoid oesophagus.'
- Diffuse oesophageal spasm—*Cork screw* appearance.
- GORD—shows reflux when done in Trendelenburg's position.
- Oesophageal carcinoma—Irregular stenosing lesion with shouldering (*'Rat tail'* is a fluoroscopic finding).
- Pharyngeal pouch—Demonstration of the pouch.
- External compression—Indentation of barium column by superior or posterior mediastinal mass, enlarged left atria as in mitral stenosis.

OESOPHAGOSCOPY

Indications

Diagnostic

- To identify the lesion and to take biopsy in carcinoma oesophagus.
- For diagnosing other oesophageal conditions.

Therapeutic

- To remove foreign body
- To dilate structure
- To place endostents for inoperable carcinoma oesophagus
- To inject sclerosants for varices

Types

1. ***Rigid oesophagoscope (Negus type)***
   - It is done under general anaesthesia. Head is extended and head end of the table is tilted upwards, scope is passed behind the epiglottis and cricoid through the cricopharyngeal opening. This is the most difficult part in oesophagoscopy.

Reflux is precipitated by flexion of the trunk—Boot lacing sign.



Fig. 19.6: Oesophageal candidiasis—note the multiple-curd-like lesions.

After that, negotiating through the oesophagus is easier. The lesion is identified and biopsy is taken if required.
- *Complications* are perforation (most common site of perforation is at the level of cricopharyngeus), bleeding.

2. ***Fibreoptic flexible oesophagoscope***
   - It can be done under local anaesthesia. Reflux and hiatus are well identified. Stomach also can be visualised. Easy to pass and perforation is unlikely.
   - But tissue taken for biopsy is smaller and removal of foreign body is also difficult.

OESOPHAGEAL ENDOSONOGRAPHY

- It is an useful method of finding and assessing involvement or pathology of different layers of oesophagus especially in carcinoma oesophagus. It shows all layers clearly and distinctly and so invasion can be better made out and operability can be decided.
- **Endoscopic oesophageal staining** using labelled iodine is used to identify early carcinoma in oesophagus. Normal mucosal cells contain glycogen which takes up iodine and so stains brown, where as carcinoma cells will not take up iodine and so mucosa appears pale (not stained).

GASTRO-OESOPHAGEAL REFLUX DISEASE (GORD/GERD)

- It is a pathological reflux from the stomach into the lower oesophagus.
- Symptoms may be due to peptic oesophagitis, LOS dysfunction, aspiration due to reflux, due to late effects like stricture and obstruction.
- It is due to varied *anatomical and physiological factors.*

Anatomical Factors

- Obesity.
- Altered length of intra-abdominal oesophagus.
- Alteration of phreno-oesophageal ligament.
- Altered obliquity of O-G junction (alteration in angle of '*His*').
- Reduced pinching action of right crus of diaphragm.
- Alteration in normal mucosal rosette at O-G junction.

Physiological Factors

- Reduced LOS pressure.
- Altered transient relaxation period in LOS.
- Reduced oesophageal clearance mechanism.
- Delayed gastric emptying due to diabetes, neuromuscular block, gastroparesis, medications.
- Increased gastric distension and gastric acid hypersecretion.

Other Factors

- Alcohol, smoking, stress, lifestyle.
- It is seen in infants and children and also in pregnant women.

Types

Classification I
- *Symptomatic uncomplicated GORD* (NERD—*Non-Erosive Reflux Disease*).
- *Symptomatic, complicated GORD*.

Classification II
- *Primary*: Incompetent LOS.
- *Secondary*: Due to surgery/disease.

Classification III
- *GORD with sliding hernia.*
- *GORD without sliding hernia.*

Clinical Features

- Fatty dyspepsia.
- Chest pain and heart-burn **(pyrosis)**—main symptom. Pain is more in lying down position and at night. It may mimic cardiac pain/angina. It often begins in the epigastrium and becomes substernal.
- Odynophagia (painful swallowing).
- Appearance of symptoms within seconds of ingestion of food is typical.
- Regurgitation - It is return of oesophageal content.
- Laryngeal symptoms.
- Dysphagia will occur once complications begin.
- Symptoms are more with change of position.
- Chronic cough, shortness of breath and hoarseness—Nocturnal reflux - Reflux is return of gastric content.
- Haematemesis.

Triad

- Heart burn
- Epigastric pain with dysphagia
- Regurgitation

Complications

- Reflux oesophagitis.
- Sliding hiatus hernia.
- Stricture lower end oesophagus.
- Oesophageal shortening.
- Barrett's oesophagus.
- Carcinoma (adeno) oesophagus (10% of GERD).

Oesophageal	*Extraoesophageal*
• Oesophagitis	• Laryngitis
• Stricture	• Recurrent pneumonia
• Barrett's oesophagus	• Progressive pulmonary fibrosis
• Oesophageal shortening	
• Carcinoma (adeno)	

Investigations

- Barium study in head down position.
- Endoscopy to exclude other disease and to assess any mucosal injury - red inflamed mucosa often with ulceration. Sliding hernia can be identified through endoscopy. When patient retches, gastric mucosa will enter the OG junction and ascends upwards to variable distance.



Figs 19.7A and D: Gastro-oesophageal reflux disease (GERD) endoscopic views.

- Mucosal biopsy to confirm metaplastic transformation.
- Oesophageal manometry to assess the function of LES. Length and pressure of LOS is important. Transient relaxation period which is increased is most important.
- 24 hours oesophageal pH monitoring - gold standard. PPI should be stopped for 3 weeks prior to pH monitoring.
- ***Bernstein test:*** Instillation of 1:10 HCl into stomach of patient with reflux will reproduce the symptoms; and pH in the lower end of the oesophagus decreases. Later pain disappears with saline infusion.
- Dual probe pH monitoring (one in distal oesophagus and one in proximal oesophagus/trachea) is used to confirm the respiratory complications of GERD.

Differential Diagnosis

- Achalasia cardia.
- Carcinoma oesophagus.
- Peptic ulcer.
- Gallstones.
- Pancreatic diseases.
- Gastritis.
- Cardiac angina.

Treatment of Uncomplicated GORD

A. ***General measure***
  - Control of obesity.
  - Stop smoking and alcohol.
  - Avoid tea, coffee.
  - Propped up position.
  - Small frequent meals.

B. ***Drugs***
  - **H_2 antagonists; antacids.**
  - **Proton pump inhibitors (PPIs) - (very effective)**
    - Omeprazole 20 mg - BD for 3-6 months.
    - Lansoprazole 30 mg.
    - Pantoprazole 40 mg.
    - Esomeprazole 20 mg.
    - Rabeprazole 20 mg.
  - **Prokinetic drugs**
    - Metoclopramide.
    - Domperidone 30 mg.
    - Cisapride.
    - Mosapride.
    - Itopride 50 mg—does not cause cardiac arrhythmias.

C. ***Endoluminal therapies for GORD***

- Endoluminal *suturing* (Wilson cook)
- *Plexiglass microspheres* (PMMA). Microsphere suspended in gelatin is injected through endoscopic needle. Gelatin gets absorbed and spheres cause a tissue bulking
- *Gatekeeper reflux* repair system. Endoscopic delivery of preformed radiopaque hydrogel into submucosa
- *Stretta catheter*. Flexible, soft, 6 mm sized, 65 cm length tube with balloon/basket and 5.5 mm NITI electrode, irrigation and suction
- *Enteryx* injection technique (estrinyl vinyl alcohol)
- *Endocinch* technique
- Endoscopic full thickness *plication.*

D. ***Surgery***

Indications for surgical treatment

- Failure of drug treatment
- Sliding hernia
- Barrett's ulcer
- Severe pain
- Presence of complications like bleeding/stricture/shortening

Surgeries

Antireflux surgery is the only effective long-term beneficial therapy ideally available and considered now. *Laparoscopic fundoplication* (most popular), Collis – Nissen vertical gastroplasty and fundoplication, resection of OG junction when metaplasia is present, Belsey Mark 4 operation (technically difficult) are the procedures used now.

- *Total (Nissen's) or partial (Toupet) fundoplication* wherein after narrowing the crus of the diaphragm, mobilised fundus is wrapped around the area of O-G junction either totally or partially.

  Fundus is mobilised by ligating short gastric arteries. Crus of the diaphragm is repaired by interrupted polypropylene sutures. Mobilised fundus is wrapped around the lower oesophagus to maintain adequate length (2 cm) of the intraabdominal oesophagus. Wrapped fundus is sutured at various angles to get the effect. Interrupted suturing is done with polypropylene suture materials. Mortality of the procedure is very less. *Gas bloat syndrome*/dysphagia/haemorrhage/perforation/mediastinitis are the known *complications*. Gas bloat syndrome will not resolve. Floppy Nissen's fundoplication reduces the incidence of gas bloat syndrome.
- *Laparoscopic fundoplication* is safe and a popular alternate approach.

Fundoplications

- *Nissen's*—total 360°
- *Toupet's*—partial 180°—posterolateral
- *Watson's*—partial 120°—anterolateral
- *Dor*—anterior fundoplication
- Partial fundoplication with *mesh wrap* around

Gas bloat syndrome (inability to belch) can occur after Nissen's procedure.

- *Hill's operation*—Fixing O-G junction posteriorly to preaortic fascia—to arcuate ligament.
- *Boerema operation*—Fixing O-G junction anteriorly to abdominal wall.
- *Belsey-Mark-4 operation* is plication of oesophagus to the diaphragm through many sutures and so as to push the lower end of oesophagus downwards and make it intra-abdominal—*thoracic approach.*
- Placement of *Angelchik prosthesis* in lower end of oesophagus also prevents the reflux.
- *Highly Selective Vagotomy (HSV*) can be done.
- *Collis' vertical gastroplasty* is done using fundus of stomach (by giving vertical cut and suturing fundus) for oesophageal shortening (a complication of GORD).
- *Oesophago-gastrectomy* may be required in severe cases (Lower end of oesophagus and part of stomach is removed)—whenever *metaplasia is present*/failed antireflux procedure/nondilatable stricture.
- Partial gastrectomy with a Roux-en-Y diversion reduces reflux.
- *Thal's patch procedure* is done in stricture and short oesophagus using fundus of the stomach.
- Fundoplication using mesh wrap around.



Fig. 19.8: Nissen's fundoplication.


Oesophagus
Diaphragm
Gastroplasty incision
Stomach

Fig. 19.9: Vertical gastroplasty is done to lengthen the intra-abdominal oesophagus.



Fig. 19.10: Thal's patch done for oesophageal stricture due to reflux oesophagitis.


Dor anterior fundoplicaton
I row
II row
First row behind
Second row front, also to right crus

Fig. 19.11: Dor anterior fundoplication. Right margin of the fundus is sutured to left margin of the oesophagus. Front aspect of the fundus is sutured to right margin of the oesophagus. Second row is also sutured to right crus.


Oesophagus
Fundus
Sutures to restore the angle
Diaphragm
Stomach
Fundal wrap ant 2/3
Plication O-G Junction
Stomach
Stomach

Fig. 19.12: Belsey mark 4 operation for sliding hiatus hernia. It is done through thoracic approach. Here angle of oesophagus is restored with sutures and partial anterior fundal wrap is done. Then oesophagus is pushed down by oesophago-diaphragmatic plication sutures.


Diaphragm
Oesophagus
CRUS
Partial plication
Fundus wrapped
Stomach

Fig. 19.13: Toupet's partial fundoplication.

Principles of antireflux surgeries

- Operation should restore the LES pressure twice the resting gastric pressure
- The adequate length of the intraabdominal oesophagus should be maintained
- Apposition of diaphragmatic crurae, reduction of hiatus hernia when present
- Repaired OG junction should relax adequately during swallowing
- Tension free fundoplication should be done

Note: Stricture oesophagus due to GERD is treated by regular dilatations and long-term PPI therapy.

Kindness is a language which the dumb can speak, the deaf can understand

Complications of Surgery

- Oesophageal/gastric perforation.
- Haemorrhage.
- Pneumothorax/pyothorax.
- Vagus nerve injury.
- Cardiac arrhythmias.
- Sepsis – mediastinitis or septicaemia.
- Disruption/failure of fundoplication.
- Gas bloat syndrome.

HIATUS HERNIA

It is the most common type of diaphragmatic hernia.

Types of hiatus hernia – classification

- *Type I* hiatus hernia – It is the cephalad displacement of the gastrooesophageal junction through the hiatus into the mediastinum. It is usually small, asymptomatic and reducible. It is commonest type
- *Type II* hiatus hernia – It is superior migration of the fundus of the stomach along side the GE junction and oesophagus into the mediastinum with GE junction in normal intraabdominal location. It is rolling hernia
- *Type III* hiatus hernia – It is combination of type I and type II
- *Type IV* hiatus hernia – It is the hernia containing other abdominal viscera as content like transverse colon and omentum

Types

- Sliding hernia (85%).
- Rolling hernia (10-12%).
- Combined.



Figs 19.14A and B: Endoscopic view of oesophageal hiatus hernia.

Sliding hernia is commonly associated with GORD (Should be discussed like GORD).

Here the cardia migrates back and forth between the posterior mediastinum and peritoneal cavity.

Saint's triad

- Haitus hernia
- Diverticulosis
- Gallstones



Fig. 19.15: Types of hiatus hernia.

ROLLING HERNIA (PARAOESOPHAGEAL HERNIA)

It is herniation of stomach fundus or rarely other abdominal contents colon/spleen through a hiatus, usually towards left side.

Clinical Features

- Common in elderly.
- Abdominal pain and chest pain.
- Hiccough, early satiety.
- Regurgitation, post prandial bloating.
- Cardiac abnormality (arrhythmia).
- Dysphagia dyspnoea.
- 40% presents as acute features with perforation/gangrene/bleeding.

Complications

- Gangrene of stomach.
- Perforation into the mediastinum.
- Perforation into the peritoneum.
- Gastric volvulus.

Investigations

- Plain X-ray - lateral and PA erect view showing retrocardiac air-fluid level.
- Barium meal study very useful.
- ECG.
- 3D CT scan is useful.



Fig. 19.16: Different types of hiatus hernia—sliding, rolling and combined.

Treatment

- Treatment is always *surgical*.
  - Excision of sac and repair of the defect.
  - If it is gangrenous, gastrectomy is required.
  - Either abdominal or thoracic or laparoscopic approach can be used in treating rolling hernia surgically.
  - Mesh reinforcement to hiatus to close the defect may be needed.

OESOPHAGEAL MOTILITY DISORDERS

- Neurological – stroke, bulbar palsy, motor neuron disease, multiple sclerosis, Parkinson's disease
- Muscular – myasthenia, muscular dystrophy
- Pharyngeal pouch
- Diffuse oesophageal spasm
- Nutcracker oesophagus
- Autoimmune disorders like systemic sclerosis, polymyositis and CREST syndrome
- Reflux associated
- Idiopathic
- Eosinophilic allergic oesophagitis
- Achalasia cardia
- GERD
- Alcoholic neuropathy

REFLUX OESOPHAGITIS

Types

1. ***Acute:*** Following *burns, trauma, infection, peptic ulcer.*
2. ***Chronic*:** Reflux of acid in sliding hernia, after gastric surgery.
   Reflux is quite common in pregnancy.
   Site is always in lower oesophagus.

Pathology

There is bleeding granulation tissue in lower oesophageal mucosa with spasm of longitudinal muscle which pulls the adjacent gastric area upwards into the oesophagus causing sliding hernia.

Grading

1. Mucosal erythema
2. Mucosal erythema + superficial ulceration
3. Mucosal erythema + superficial ulceration + submucosal fibrosis
4. Mucosal erythema + extensive ulceration + paramural fibrosis

Savary-Miller classification of reflux oesophagitis—grading

1. Single or isolated erosive lesion(s), oval or linear but affecting only one longitudinal folds
2. Multiple erosive lesions, non-circumferential affecting more than one longitudinal fold with or without confluence
3. Circumferential erosive lesions
4. Chronic lesion: Ulcers, strictures and or short oesophagus alone or in association with grade 1-3 lesions
5. Columnar epithelium in continuity with the Z line, non-circular, star shaped or circumferential, alone or in association with grade 1-4 lesions

Los-Angeles classification of reflux oesophagitis—grading

A. One or more mucosal break *no longer than 5 mm* that does not extend between the tops of two mucosal folds

B. One or more mucosal break *more than 5 mm* long that does not extend between the tops of two mucosal folds

C. One or more mucosal break that continues between the tops of two or more mucosal folds but which involves *less than 75%* of the circumference

D. One or more mucosal break, which involves *at least 75%* of the oesophageal circumference

Clinical Features

- It is a part of GORD.
- Pain and burning sensation in retrosternal area often referred to shoulder, neck, arm.
- Heart burn is common.
- Dysphagia.
- Anaemia.

Diagnosis

- Barium meal X-ray.
- Gastroscopy and biopsy.

Barrett's ulcer is an ulcer with gastric (columnar) metaplasia in lower oesophagus.

Treatment

- *Antacids*
- *H_2 blockers*: Ranitidine, famotidine.

Never forget that only dead fish swims with the stream.

- ***Proton pump inhibitors****—Main method and more effective.*
  - Omeprazole 20 mg BD one hour before food. (Morning) for 6 months
  - Lansoprazole 30 mg
  - Pantoprazole 40 mg
  - Esomeprazole 20 mg
  - Rabeprazole 20 mg - (can be given with food).
- ***Prokinetic drugs*** like metochlopramide, domperidone, cisapride, mosapride.
- *Treating GORD and associated causes.* By fundoplication and other surgeries.
- *Resection in severe cases***.**

Note: Erythromycin is a prokinetic drug (motilin agonist), which acts by binding with motilin receptor on GI smooth muscle cells.

BARRETT'S OESOPHAGUS

- It is the metaplastic changes in the mucosa of the oesophagus as the result of GORD.
- Squamous epithelium of lower end of the oesophagus is replaced by diseased columnar epithelium (columnar metaplasia).
- There is macroscopic visible length of columnar mucosa with microscopic features of intestinal metaplasia.
- It affects lower oesophagus commonly often middle oesophagus also.

Types (based on length)

a. If the length of metaplasia is more than 3 cm, it is called as *long segment Barrett's oesophagus* – classic Barrett type.

b. If the length is less than 3 cm, it is called as *short segment Barrett's oesophagus*.

Histological Types

a. *Gastric type:* Contains chief and parietal cells.

b. *Intestinal type:* Contains goblet cells.

c. *Junctional type:* Contains mucus glands alike of gastric cardia.

Cardia metaplasia is metaplasia at OG junction without any macroscopic change in gastroscopy.

This diseased columnar epithelium is more prone for malignant transformation, i.e. when there is intestinal metaplasia, risk of malignant transformation increases. More the amount of dysplasia more is the risk of malignant transformation. *Dysplasia may be indefinite; low grade or high grade.*

Clinical Features

- Features of GORD.
- Haematemesis.

Complications of Barrett's oesophagus

- Ulcerations and stricture
- Dysphagia
- Bleeding
- Perforation
- Adeno carcinoma of O-G junction (25 times more common)

Management

- Regular endoscopic biopsy and surveillance for low grade dysplasia.
- Ablation of Barrett's oesophagus by laser.
- Photodynamic therapy - through endoscopy.
- Argon beam coagulation.
- Proton pump inhibitors - high dose for 3-6 months.
- Antireflux treatment by surgery.
- Resection—-***Always better choice -*** for high grade dysplasia.
- Endoscopic mucosal resection.

BARRETT'S ULCER

It is an ulcer in columnar epithelium lined Barrett's oesophagus at or just above the squamo-columnar junction.

It is more prone for

- — *Bleeding.*
- — *Perforation.*
- — *Adenocarcinoma of oesophagus.*

Treatment for Barrett's ulcer is endoscopic biopsy and resection.

ACHALASIA CARDIA (Cardiospasm)

> ***The symptom-complex in cardiospasm (the term by which oesophageal achalasia was formerly known) is as a rule almost pathognomonic. It may be divided into the three stages—first, cardiospasm without food regurgitation; second, cardiospasm with immediate food regurgitation; third, cardiospasm with dilated oesophagus, the retention of food in the dilated portion and its regurgitation at irregular intervals after taking.***
>
> **— Henry Stanley Plummer,** 1908

It is failure of relaxation of cardia (oesophago gastric junction) due to disorganised oesophageal peristalsis, as a result of failure of integration of parasympathetic impulses causing *functional obstruction.*

Aetiology

- There is absence or less numbered ganglions in myenteric plexus.
  - Stress.
  - Vit B_1 deficiency.
  - Chaga's disease.
  - Diffuse oesophageal spasm *(Cork-screw oesophagus).*
  - Most commonly it is idiopathic.
- There is pencil shaped narrowing of cardia (O-G junction) with enormous dilatation of proximal oesophagus, which contains foul smelling fluid and is more prone for aspiration pneumonia.
- Achalasia cardia *is a precancerous* condition—seven times chances of getting squamous cell carcinoma (2-8%, after 15 years).

Pathology

- Thickening of circular muscle fibres in distal oesophagus.
- Myenteric inflammation; depletion of ganglion cells; neural fibrosis, reduced nitric oxide and VIP (mediators of LES relaxation).

Clinical Features

- Common in females between 20 and 40 years age group.
- Chest pain occurs in early stage.
- Achalasia with diffuse oesophageal spasm is called as *'vigorous achalasia'.*
- Presents with progressive dysphagia, which is more for liquid than to solid food.
- Regurgitation and recurrent pneumonia are common (10%).
- Malnutrition and general ill health.
- Lung abscess formation.
- Odynophagia and weight loss.

Triad
- Dysphagia
- Regurgitation
- Weight loss

Staging

I - Proximal dilatation < 4 cm
II - Dilatation between 4-7 cm
III - Dilatation > 7 cm

Investigations

- *Barium swallow is diagnostic*—shows



Fig. 19.17: Barium swallow X-ray showing features of achalasia cardia.

1. Pencil like smooth narrowing of lower oesophagus—*Bird beak appearance*
2. Dilatation of proximal oesophagus
3. Absence of fundic gas bubble
4. Sigmoid oesophagus or megaoesophagus

- Chest X-ray shows patches of pneumonia.
- Oesophageal manometry shows unrelaxed lower oesophageal sphincter with high resting pressure - very useful and gold standard. Failure of LES to relax completely during swallowing and complete absence of peristalsis.
- Oesophagoscopy is done to confirm the diagnosis and to rule out carcinoma oesophagus. It shows totally closed LES with atonic, dilated proximal oesophagus. Biopsy of mucosa at LES should be done.



Fig. 19.18: Endoscopic view of achalasia.

Self-respect — that a corner stone of all virtue.

Differential Diagnosis

- Carcinoma oesophagus.
- Stricture oesophagus.
- Scleroderma.



Fig. 19.19: Diagrammatic representation of achalasia cardia.



Fig. 20.20: X-ray picture of achalasia cardia.

Treatment

Surgery

- *Modified Heller's operation*: Oesophagocardiomyotomy. Success rate is 85%.
  - Either through thoracic or through abdominal approach, thickened circular muscle fibres are cut longitudinally for about 8-10 cm, 2 cm proximal to the thickened muscle to 1 cm distal to O-G junction. Care should be taken not to open the mucosa. (Anterior myotomy is done now. Original Heller's is both anterior and posterior myotomies).



Fig. 19.21: Heller's cardiomyotomy for achalasia cardia. Only circular muscle layer is cut longitudinally in O-G junction until mucosa protrudes out without perforating the mucosa.

  - *Nissen's or Toupet's fundoplication* is done along with the above procedure to prevent reflux.
- Rarely *Negus hydrostatic dilatation* is done to dilate O-G junction. It is not very well accepted method as chances of perforation is high. Success rate is 65%. 30 mm diameter balloon is inflated for 3 minutes.
- Laparoscopic/thoracoscopic cardiomyotomy.
- Resection is done only when failure of myotomy occurs or when megaoesophagus or metaplasia is present.

Drugs

a. Endoscopic injection of botulinum toxin to sphincter—High recurrence rate.
b. Calcium channel blocker, nitroglycerin sublingually.



Fig. 19.22: Negus hydrostatic dilator used for achalasia cardia. It has got only 65% success rate.

Note: *Pseudoachalasia* shows features like of achalasia cardia with dysphagia and weight loss, seen in an elderly due to carcinoma. Amylnitrate inhalation causes sphincter relaxation in Achalasia cardia but not in pseudoachalasia.

NUT CRACKER OESOPHAGUS

It is characterised manometrically by prolonged high amplitude peristaltic waves in oesophagus. Presentation mimics cardiac symptoms. (> 180 mm Hg; > 6 seconds).

Treatment

- Calcium channel blocker.
- Nitrates, isosorbide dinitrate.

PLUMMER-VINSON SYNDROME (Paterson-Kelly syndrome)



Fig. 19.23: Oesophageal web, endoscopic view.

- Here *oesophageal webs* are seen in uppermost portion of the oesophagus with spasm of circular muscle fibres.
- Common in patients with long standing *iron deficiency anaemia*.
- Common in females.
- *Superficial glossitis, cheilitis, koilonychia commonly seen.*
- Splenomegaly may be present.
- In oesophageal webs, mucosa is hyperkeratotic, friable, desquamated.
- It is a *premalignant condition* and presents with severe dysphagia.
- Oesophagoscopy and biopsy is required to rule out malignancy.

Treatment

- Oral iron—Ferrous sulphate 300 mg TDS with vitamins.
- Blood transfusion is given when there is severe anaemia (Transfusion of packed cells).
- IV or IM iron therapy.
- Once anaemia comes under control, webs will clear and patient can swallow.
  Follow-up endoscopy is a must.
- Dilatation of web may be required.

CORROSIVE STRICTURE OF OESOPHAGUS

Features of oesophageal corrosive lesion

- *Acute/immediate*
    - Severe pain, shock, laryngeal oedema
    - Mediastinitis, septicaemia, haemorrhage, perforation
- *Late/chronic*
    - Dysphagia
    - Stricture – 50%
    - Severe malnutrition
    - Recurrent respiratory infection
    - Oesophageal shortening
    - Malignant changes
    - Tracheo-oesophageal fistula formation

Corrosive strictures can be multiple. Damage is more in lower 1/3 oesophagus

- Corrosives are commonest cause of oesophageal stricture.
- Mainly due to ingestion of alkali (*Lye stricture* - Lye is strong alkali sodium hydroxide) sodium hydroxide, occasionally due to acid (sulphuric acid, nitric acid). Acid commonly damages the stomach.
- It causes extensive inflammation of the mucosa with perioesophagitis which, if not treated leads to multiple strictures in oesophagus.
- Sometimes it causes severe life-threatening necrotising lesion which requires immediate surgical intervention.
- Acute phase lasts for 3 weeks.
- Damage is more in lower 1/3 oesophagus.
- Alkali is odourless and tasteless and so large volume is ingested. Alkali causes liquefaction, saponification and thrombosis of vessels and later leading to fibrosis and stricture. Acid causes intense pylorospasm, antral pooling of acid, coagulation necrosis and eschar formation.
- Severity depends on type of agent, its concentration and volume.

Hope sees the invisible, feels the intangible and achieves the impossible.



Figs 19.24A and B: Endoscopic view of corrosive injury. Endoscopy should be done very gently in corrosive injury

Treatment

- Careful early gentle repeated endoscopy is mandatory.
- Though advocated often for 2-3 weeks, use of steroids is controversial and under debate.
- Antibiotics if there are chances of aspiration or perforation.
- *Regular oesophageal dilatation* is done for stricture. Stricture is dilated endoscopically using guide wire. Dilators are solid type with gradual increase in diameters. Often radiologic C-ARM guidance is needed to pass the guide wire into the stomach. Dilatation should be done upto minimum 16 mm diameter. Pneumatic or balloon dilatation is also practiced. Gum elastic dilators, mercury weighted dilators, Eder – Puestow dilators, Savary – Gilliard dilators, balloon dilators are other dilators used. Earlier, blind dilatation using oesophageal bougies of increased diameters was the practice, which is followed even now in many places, but chances of perforation is more.
- Oesophageal resection in corrosive strictures is technically difficult and may be hazardous. Oesophageal bypass is better and easier, and following later by regular endoscopic surveillance for malignant transformation (5%). Colon is used as replacing conduit as stomach itself may be diseased in corrosive pathology.
- In multiple strictures oesophageal resection and colonic transposition may be advocated if risk of malignancy is considered.

Note: Malignancy can develop in corrosive strictures — 5%.

Causes of stricture oesophagus

- Peptic stricture (oesophagitis induced)
- Corrosives—commonest cause
- Foreign body
- Post-surgical, radiotherapy
- Congenital
- Infection like tuberculosis
- Drugs like tetracycline, vitamin C



Fig. 19.25: Endoscopic view of oesophageal stricture.



Fig. 19.26: Oesophageal dilatation is being done endoscopically.



Fig. 19.27: Barium swallolw showing stricture at lower oesophagus. It may be due to oesophagitis, congenital, tuberculosis, malignancy, drug induced, etc.



Fig. 19.28: Patient underwent total oesophagectomy with colonic transposition. Colon placed in subcutaneous plane.

SCHATZKI'S RINGS

They are semicircular protrusion of lower oesophageal mucosa located at or just above the oesophago-gastric junction (squamo-columnar junction). Its under-surface is lined by columnar gastric epithelium.

- They involve only the mucosa and submucosa of the oesophagus, not the muscle.
- They present with dysphagia and reflux.



Fig. 19.29: Barium swallow X-ray showing Schatzki ring X-ray also shows features of hiatus hernia.



Fig. 19.30: Schatzki's ring – endoscopic view.

Treatment

- Intermittent oesophageal bougienage.
- Antireflux drugs.

BOERHAAVE'S SYNDROME

It is a tear in the lower third of the oesophagus which occurs when a person vomits *against a closed glottis*, causing leak into the mediastinum, pleural cavity and peritoneum.

All are equal in their ignorance.

Features of Boerhaave's syndrome

Presentations	*Differential diagnosis*	*Complications*
Sudden onset of symptoms	Myocardial infarction	Mediastinitis
Severe chest pain	Pancreatitis	Septicaemia
Pain abdomen		Peritonitis
Subcutaneous emphysema		Emphysema
Shock		

'Crunching effect in the chest' is called as *Hamman's sign*.
Mackler's triad: (1) vomiting, (2) chest pain, (3) subcutaneous emphysema.

Site

2-10 cm of posterolateral part of lower oesophagus.

Investigations

- Chest X-ray—shows pneumomediastinum (*'V' sign of Nacleiro*).
- MRI/CT chest.
- Total count.

Treatment

- Nil by mouth.
- Antibiotics.
- IV fluids.
- TPN.
- Feeding by jejunostomy.
- Most often surgery with resection may be required (thoracotomy and repair).
- *When severe mediastinitis occurs, condition has high mortality.*


Superficial tear with bleed in stomach near O-G junction
Deep tear with perforation in oesophagus lower 1/3
Mallory- weiss syndrome
Boerhaave's syndrome

Fig. 19.31: Diagrams showing Mallory-Weiss syndrome and Boerhaave's syndrome.

MALLORY-WEISS SYNDROME

- It is seen in adults with severe prolonged vomiting, causing longitudinal tear in the mucosa of stomach at and just below the cardia, *leading to severe haematemesis*.
- Violent vomiting often may be due to migraine or vertigo or following a bout of alcohol.
- Presents with severe *vomiting* and later *haematemesis*, with features of *shock.*
- It is common in one O'clock position.
- Only 10% of cases involve lower oesophageal mucosa.

Investigations

- Gastroscopy, Hb%, PCV, blood grouping.
- During gastroscopy, if stomach is not inflated properly, 50% cases may be missed.

Differential diagnosis

- Bleeding peptic ulcer
- Oesophageal varices
- Erosive gastritis
- Carcinoma stomach

Treatment

- Conservative, as it is only a mucosal tear.
- Blood transfusion.
- IV fluids.
- Sedation.
- Haemostatic agents like vasopressin.
- Endoscopic injection therapy is used if required.
- Surgery is rarely required.

TRACHEO-OESOPHAGEAL FISTULA

Types

- In **85% cases,** it is a blind upper end with lower end communicating with trachea.
- It may be associated with **VACTER** anomalies.

V — Vertebral defects
A — Anal atresia
C — Cardiac defect (PDA/VSD)
TE — Tracheo-oesophageal fistula
R — Radial hypoplasia and renal agenesis

Clinical Features

- TOF should be recognised within 24 hours of birth.
- Newborn baby regurgitates all feeds and there is continuous pouring of saliva from the mouth which is a *diagnostic feature.*
- *Cough and cyanosis.*
- It is commonly associated with maternal *hydramnios (50%).*

Investigations

- Obstruction is revealed while passing nasogastric tube.
- Contrast study will reveal fistula and obstruction (Dionosil 1 ml).
- Other anomalies are looked for.
- Chest X-ray.
- Echocardiography.

Treatment

Surgery

- Child requires feeding gastrostomy commonly.
- Often the procedure is staged one.
- Through right sided thoracotomy (opposite to the side of aortic arch), fistula is identified and resected. Lower segment is anastomosed to the blind upper segment. Occasionally if the length is inadequate or the atretic segment is long one then, colonic or gastric transposition is required.



Figs 19.32A to D: Types of tracheo-oesophageal fistula. (A) H type, (B) Lower end blind, upper end connected to trachea, (C) Both ends blind, (D) Upper end blind, lower end connected to trachea (85%).

Complications of surgery

- Pneumonia
- Leak from the anastomotic site
- Reflux
- Dysphagia

OESOPHAGEAL DIVERTICULUM

Types

1. ***Pulsion diverticulum*:**
   a. Pharyngeal pouch through Zenker's or Killian's dehiscence.
   b. Epiphrenic pulsion diverticulum occurs in lower oesophagus, usually towards right side, due to obstruction in the distal oesophagus or due to incoordinated LOS relaxation.
2. ***Traction diverticulum:*** Occurs in mid-oesophagus or in parabronchial region, is due to mediastinal granulomatous disease like tuberculosis.

Investigations

- Barium swallow is typical.
- Oesophagoscopy and endosonography.
- CT Chest as final evaluation.

Treatment

- Treat the cause.
- Excision of the diverticulum – epiphrenic diverticulectomy.
- Cricopharyngeal myotomy or lower oesophageal myotomy with antireflux procedure is usually required.

CARCINOMA OESOPHAGUS

- Carcinoma oesophagus is common in China, South Africa and Asian countries.
- It is 6th most common cancer in the world.
- It is less than 1% of all cancers. It is 7% of all GI malignancies.
- It is less common in America and European countries.
- In India, it is common in Karnataka and Orissa.
- When patient presents with dysphagia, often it is fairly advanced and inoperable and only palliation is the possibility. But then surgery is the treatment of choice in early growths.

Aetiology

Diet, deficiencies (vit. A, C, Riboflavin)
Mycotoxin
Alcohol and tobacco
Fungal contamination of food
Achalasia cardia
Oesophageal webs
Barrett's oesophagus
Plummer –Vinson's syndrome
Corrosive strictures
Tylosis*
Nitrosamines

5% common
Common after 45 years
Common in men
Common in ***China*** – ***Henan*** province
In India, common in Orissa and Karnataka

* *Tylosis* is an inherited disease with thickening of skin of palm and sole

All things must change to something new and strange.

Tylosis

- Autosomal dominant condition seen from childhood
- Soles and palms are involved called as palmoplantar keratoderma
- Waxy, yellow lesions, which does not itch
- 60% of members of families develop carcinoma oesophagus after the age of 60
- Systemic retinoids are the drugs used for tylosis

Pathology

- Common in–
  Middle third—50%.
  Lower third—33%.
  Upper third—17%.
- Lower 3 cm of oesophagus is lined by columnar epithelium, and so adenocarcinoma is common here. Barrett's columnar metaplasia which occurs in lower third of oesophagus is also more prone for adenocarcinoma.
- Squamous cell carcinoma is commonest type in India and Asian countries.



Figs 19.33A and B: Carcinoma oesophagus middle third—pathology specimen, gross and cut section.

Note:
- *In India 90% are squamous cell carcinomas.*
- *In western countries, adenocarcinoma is becoming more common.*

Gross Types

- Annular (15%).
- Ulcerative (20%).
- Fungating – cauliflower like (60%).
- Polypoid.
- Varicoid – diffuse submucosal type.



Figs 19.34A to D: Gross outer look and cut section of proliferative and indurated lesions of carcinoma oesophagus.

Spread

- *Direct*
  - Lack of serosal layer in oesophagus favours local extension. In upper third it spreads through muscular layer and get adherent to left main bronchus, trachea, and left recurrent laryngeal nerve (causes hoarseness), aorta or its branches (causes fatal haemorrhage, but rare).
  - It may perforate and cause mediastinitis.
  - It may get adherent to pleura also.
- *Lymphatic spread*
  - It spreads both by lymphatic permeation and lymphatic embolisation.
  - It can cause satellite nodules elsewhere in the oesophagus, away from the main tumour.
  - Above in the neck, it spreads to supraclavicular lymph nodes.
  - In thorax, it spreads to paraoesophageal, tracheo-bronchial lymph nodes to subdiaphragmatic lymph nodes.
  - In abdomen, it spreads to coeliac lymph nodes.
- *Blood spread occurs* to liver, lungs, brain and bones.

Clinical Features

- *Recent onset of dysphagia* is the commonest feature. *For the dysphagia to develop, two third of the lumen should be occluded.*
- Regurgitation.
- Anorexia and loss of weight (severe), cachexia.
- Pain-substernal or in the abdomen.
- Liver secondaries, ascites.
- Bronchopneumonia, melaena.
- Features of broncho-oesophageal fistula in carcinoma of upper third oesophagus (30%).
- Left supraclavicular lymph nodes may be palpable.
- Hoarseness of voice due to involvement of recurrent laryngeal nerve.
- Hiccough, due to phrenic nerve involvement.
- Back pain - due to nodal spread (paraoesophageal/ *coeliac* nodes).
- Male to female ratio is 3:1.

Investigations

- *Barium swallow*: Shouldering sign and irregular filling defect.
- Oesophagoscopy to see the lesion, extent and type.
- Biopsy for histological type and confirmation.
- Chest X-ray to look for aspiration pneumonia.
- Bronchoscopy, to see invasion in upper third growth.
- Oesophageal endosonography, to look for the involvement of layers of oesophagus, nodes, cardia and left lobe of the liver. Nodes smaller than 5 mm can be very well visualised by EUS which may be missed in CT scan. EUS guided transmucosal nodal needle aspiration cytology can also be done.
- CT scan, (95% accuracy) to look for local extension, nodal status, perioesophageal/diaphragmatic/ pericardial (1%)/vascular infiltration, obliteration of mediastinal fat and status of tracheo-bronchial tree in case of upper third growth.
- U/S abdomen, to look for liver and lymph nodes status in abdomen.
- Endoscopic oesophageal staining with labelled iodine results in normal mucosa being stained brown, but remains pale in carcinoma (as mucosa in carcinoma will not take up iodine).
- Blood tests: Haematocrit; ESR; Liver function tests.
- Laparoscopy: It is useful to see peritoneal spread, liver spread and nodal spread. It is the only reliable method to detect peritoneal seedlings. Biopsy from different places can also be taken. It will prevent unnecessary laparotomy for anticipated surgical resection.
- PET scan using 18 F – fluorodeoxyglucose (FDG): 18 FDG is given to the patient. FDG enters highly active cells and gets phosphorylated to FDG 6 phosphate. It stays in the cell as end product and get polarised there. PET with CT scan is used to see response for therapy.
- Video assisted thoracoscopic approach to stage oesophageal carcinoma.

Treatment

Gastrostomy should not be done as a palliative procedure.

Tolerance is another word for indifference.



Fig. 19.35: Endoscopic views of oesophageal carcinomas – at different levels and different gross types.

Principles

- Only 20% of oesophageal cancers present early and becomes *curable*. In such early growths confirmed with absence of nodal spread, curative surgery is the main approach – *radical oesophagectomy*. Proximal extent of resection should be 10 cm above the macroscopic tumour and distal extent of resection is 5 cm from macroscopic distal end of tumour. Proximal stomach has to be removed commonly especially in lower 1/3 tumour. Sufficient removal of contiguous structures may be needed in curative resection.
- If nodes are present, then multimodal approach should be used like - curative resection; radiotherapy and chemotherapy. Outcome of surgery depends on location of tumour; number, location and size of nodes; tumour grading.
- Neoadjuvant therapy by chemotherapy and or radiotherapy prior to surgery may improve the survival.
- Aggressive chemo radiation also may be used as curative therapy in some patients especially upper 1/3 growths and in patients who are unfit for surgery.
- In remaining patients (80%) *palliation* is the main modality of treatment. Palliation therapy is done if patient is not fit for major surgery; if there is blood spread; if there is spread to adjacent organ; if there is peritoneal/liver spread. It is to relieve pain and dysphagia and also to prevent aspiration and bleeding.

Indications for Curative Treatment

1. Early growth when patient is fit.
2. When there is no involvement of adjacent perio-esophageal structures, bronchus, liver or distant organs.



Fig. 19.36: Carcinoma in upper oesophagus (Endoscopic view).

Indications for palliative therapy

- Relieve pain
- Relieve dyspahgia
- Prevent bleeding
- Prevent aspiration



Fig. 19.37: Carcinoma oesophagus (Endoscopic view).



Fig. 19.38: Endoscopic view of carcinoma oesophagus in lower third.



Fig. 19.39: Barium swallow showing irregular filling defect and shouldering sign in middle third oesophagus.



Figs 19.40A to C: Barium swallow X-rays showing irregular filling defect at different levels – feature of carcinoma of oesophagus.

Hope sees the invisible, feels the intangible and achieves the impossible.

Staging of carcinoma oesophagus

T_0: No primary tumour
Tis: Carcinoma *in situ*
T_1: Tumour involving submucosa
T_2: Tumour involving muscularis propria
T_3: Tumour with perioesophageal spread
T_4: Involvement of recurrent laryngeal nerve, phrenic nerve, sympathetic chain, azygos vein; malignant effusion, (adjacent structure)
N_0: No lymph nodes
N_1: Mobile regional lymph nodes
M_0: No distant metastasis
M_{1a}: Upper thoracic oesophageal carcinoma with spread to neck nodes or lower oesophageal carcinoma with spread to coeliac nodes
M_{1b}: Upper thoracic oesophageal carcinoma with spread to other non regional nodes or distant spread. Middle thoracic oesophageal carcinoma with spread to neck nodes/coeliac nodes or other non regional nodes. Lower thoracic oesophageal carcinoma with spread to other non regional nodes or distant spread

Approaches for Different Level Tumours

Post cricoid tumour (Squamous cell carcinoma):

- Treated mainly by radiotherapy. Radical radiotherapy—5000-6000 rads.
- Often pharyngolaryngectomy is done along with gastric or colonic transposition. But complications are more in this procedure.

Upper third growth (Squamous cell carcinoma):

- Treated mainly by radiotherapy.
- Commonly it is advanced with left recurrent laryngeal nerve palsy and bronchial invasion.
- If it is early and operable, *Mc Keown three phased oesophagectomy* and anastomosis is done in the neck. Initially laparotomy is done to mobilise the stomach. Then thoracotomy through right 5th space is done and oesophagus is mobilised. Through right side neck approach, oesophagus with growth is removed. Anastomosis between pharynx and stomach is done in the neck.

Middle third growth (Squamous cell carcinoma):

Ivor Lewis operation (Lewis-Tanner two-phased oesophagectomy): After laparotomy stomach is mobilised. Pyloroplasty is done. Through right 5th space thoracotomy is done and growth with tumour is mobilised. Partial oesophagectomy and oesophagogastric anastomosis is done in the thorax. Intercostal tube drainage is placed during closure. Right gastroepiploic vessels should be retained safely (essential). Azygos vein should be ligated securely. Mediastinal nodes should be dissected. Thoracic duct should be ligated if needed. Feeding jejunostomy is better to maintain nutrition.

If the growth is inoperable, palliative radiotherapy is given.

Lower third growth (Squamous cell carcinoma + adenocarcinoma):

- Here through left thoracoabdominal approach, partial oesophago-gastrectomy is done with oesophagogastric anastomosis.
  Often jejunal Roux-en-Y loop anastomosis is done.
- *Orringer approach*, i.e. *Trans hiatal blind total oesophagectomy* with anastomosis in the left side of the neck. Through laparotomy, stomach and lower part of the oesophagus are mobilised. Through left sided neck approach, upper part of the oesophagus is mobilised using finger. Blind dissection is completed by meeting both fingers above and below in the thorax. Later oesophagus is pulled up out above through the neck wound and removed. Continuity is maintained in the neck. It is a *palliative* surgery.



Fig. 19.41: Transhiatal blind oesophagectomy—on table surgical specimen.

Other Approaches

- *Thoracoscopic – laparoscopic oesophagectomy* and lymphadenectomy is becoming popular, safer and effective.
- *Radical oesophagectomy with 3 field clearance* of abdominal/thoracic and cervical nodes is also practiced in many centers. 3 – Field clearance (coeliac, thoracic and neck) is done for mainly squamous cell carcinoma as spread in SCC is upwards. In adenocarcinoma 2 field clearance is sufficient (abdominal – coeliac and thoracic) as spread is downwards.

Note

When oesophagus is removed totally or sub totally an interposition is required between cervical oesophagus/pharynx and distal stomach. Different parts of GI is used for the same –

- Stomach as a tube from greater curvature (reverse gastric tube based on left gastroepiploic artery) or entire stomach without a tube.
- Jejunum.
- Colon – left sided with left colic artery as pedicle.

These pedicled tubes can be pulled upwards and placed in either in posterior mediastinum or transpleural or in substernal space or in subcutaneous plane.

Surgical approaches

- Ivor – Lewis 2 phase oesophagectomy
- Mc keown 3 phase oesophagectomy
- Left abdominothoracic approach for lower oesophagus
- Thoracoscopic – laparoscopic
- Transhiatal blind approach - Orringer's

Postoperative Management

- Fluid and electrolyte management.
- Antibiotics and proper analgesia.
- Respiratory care; ICT care; physiotherapy.
- Prevention of DVT – elevation, exercises, heparin.
- Monitoring for bleeding, sepsis, leak, oxygen saturation.
- TPN only during initial post operative period and *early jejunostomy feeding* for nutrition.

Palliative Treatment

80% of patients with carcinoma oesophagus, when present first, have fairly advanced tumour and so they are amenable for only palliative treatment. It is to *relieve pain, dysphagia and to prevent aspiration and bleeding*. Palliation therapy is done –

- If patient is not fit for major surgery.
- If there is blood spread.
- If there is adjacent organ spread.
- If there is peritoneal/liver spread.

Different methods are

- *Palliative external radiotherapy* – 3000 Rads. Severe mucositis, stricture and fistula formation are the complications.
- *Intraluminal RT* – brachytherapy (radiation intraluminally).



Fig. 19.42: Stricture oesophagus after radiotherapy given for carcinoma oesophagus.

- *Chemotherapy* – Cisplatin; methotrexate; 5 FU; ***palcitaxel***, etoposide, bleomycin.
- *Intubation* – They are traction tubes or pulsion tubes.
  - Atkinson tube.
  - Celestin tube – ideal, commonly used tube.
  - Souttar tube – made of coiled silver wire.
  - Mousseau – Barbin tube – cheaper but needs laparotomy. After laparotomy, anterior wall of the stomach is opened. MB tube is passed from mouth with the help of anesthetist by stitching its tip to nasogastric tube and pulled down into the stomach. Tip is cut near the cone part. It is sutured to anterior wall of the stomach. Gastrotomy is closed.
- *Endoscopic therapy* –



Fig. 19.43: Oesophageal stent *in situ* – a look endoscopically.

Truth, like surgery, may hurt, but it cures.

- *Self-expanding metal stents* are passed through endoscope under C-ARM guidance. It is the *ideal method of palliation*. Stent is collapsed during insertion and released once it is placed in proper position. There is no need to dilate oesophagus more than 8 mm to pass this expanding stent and so chances of perforation is minimal.
  Problems are – displacement and erosion.
- *Endoscopic laser* is used to core a channel through the tumour to improve dysphagia (Nd YAG laser; Diode laser). It causes thermal destruction of tumour. It improves dysphagia but needs repeated laser ablation. It may be used more effectively to remove tumour block in previously placed stents.
- *Endoscopic bipolar diathermy* using a olive tip; argon beam plasma coagulation; endoscopic alcohol injection into the tumour.
- *Endoscopic photodynamic therapy* (PDT) is used to destruct tumor and to relieve dysphagia. It is often used as a therapy in early cancer. Photosensitive haematoporphyrin agent is injected intravenously. It is activated over tumour using laser. Sunburn, fever, perforation, pleural effusions are complications.

- Platinum based chemotherapy is beneficial especially in advanced adenocarcinoma of oesophagus.
- *Surgery* – Transhiatal Orringer's blind oesophagectomy is a palliative surgical procedure.

Palliative procedures

- External or intraluminal RT (Brachytherapy)
- *Traction tubes* like Celestin or MB tubes through open surgery
- *Pulsion tubes* like self-expandable metal stents through endoscopes using C arm
- Endoscopic Laser
- Chemotherapy
- Transhiatal oesophagectomy - Orringer



Fig. 19.44: Mousseau—Barbin tube placed as a palliative method for carcinoma oesophagus.



Fig. 19.45: Mousseau-Barbin tube.

Complications of oesophagectomy

- 5-10% mortality
- Haemorrhage
- Respiratory infection, often severe
- Septicaemia
- Chylothorax, injury to thoracic duct
- Anastomotic leak—thoracic leak is most dangerous (5-10%)
- Hoarseness due to recurrent laryngeal nerve palsy
- Stricture formation

Terminal Events in Carcinoma Oesophagus

- Cancer cachexia.
- Sepsis, mediastinitis.
- Immunosuppression.
- Malignant tracheo-oesophageal fistula (causes severe respiratory infection and death. Here expansile (self – expandable) *endoluminal stents* are used at the site of fistula to have temporary benefit).
- Erosion into major blood vessel—bleeding.

Prognosis

- Not good because of early spread, longitudinal lymphatics, aggressiveness, difficult approach, late presentation.
- Nodal involvement carries bad prognosis.
- 5 year survival rate is only 10%.

BENIGN TUMOURS OF THE OESOPHAGUS

- *Benign tumours* of the oesophagus are rare (0.5–1% of all oesophageal tumours).
- It grows slowly like a balloon by expansion, compressing surrounding structures. It never infiltrates or spreads.
- It is usually in submucosal plane.
- It can cause obstruction/regurgitation/aspiration/mediastinal compression.

- It can be squamous papilloma/polyp/inflammatory pseudo tumour/*leiomyoma (commonest benign tumour of oesophagus – 65%)*/neurofibroma/rhabdomyoma/lipoma. True adenoma in oesophagus is very rare.
- Features may be asymptomatic (85% – identified incidentally during contrast X-ray/endoscopy); dysphagia/air way obstruction/pneumonia/spluttering during swallowing; stridor/regurgitation.
- *Leiomyoma* (commonest – 65%) is smooth, sessile, lobulated, firm, with grey white whorled appearance. Only when leiomyoma reaches 5 cm in size it causes obstruction. Multiple localised leiomyomas can occur which can be enucleated independently. *True diffuse leiomyomas* can occur occasionally in females (4%) in lower oesophagus, as diffuse hyperplasia and thickening of both muscular layers; often as part of the Alport's syndrome which needs total oesophagectomy with gastric pull up, even though benign. Benign leiomyoma of oesophagus rarely turns into leiomyosarcoma. 90% of oesophageal leiomyomas occur in *lower third of the oesophagus.*
- *Investigations*—Barium swallow X-ray (smooth circular outline/eccentric filling defect)/oesophagoscopy/endosonography/CT scan.



Figs 19.46A and B: Oesophageal submucosal tumour – endoscopic view – leiomyoma.

- *Treatment*—If tumour is more than 5 cm/symptomatic tumour/intraluminal tumour/when diagnosis is doubtful surgical enucleation is indicated. Enucleation is the therapy of choice. Ideally it should be done through right-sided thoracotomy. Occasionally oesophageal resection is needed if tumour is very large/tumour with mucosal ulceration/if tumour is near OG junction. Thoracoscopic resection can be done. Leak, empyema, sepsis and stricture are the occasional complications.

***Note*:** Unlike in the stomach and intestine (gastric leiomyoma more than 6 cm/intestinal leiomyoma more than 4 cm are potentially malignant) increased size of the oesophageal leiomyoma does not predispose the malignant transformation.

OESOPHAGEAL PERFORATION

Causes

- Instrumental injuries—commonest cause, 75% commonest site is just above the level of cricopharyngeus.
- Foreign bodies.
- Alkali injuries.
- Carcinoma oesophagus 1%.
- Boerhaave's syndrome 15%.
- Trauma 9%.
- Surgical trauma (Vagotomy, thyroidectomy, Heller's operation, pneumonectomy, spine surgery).

Clinical Features

Chest pain, vomiting, shock, subcutaneous emphysema.

Investigations

- Chest X-ray—shows pneumo-mediastinum.
- CT scan.

Complications

- Mediastinitis.
- Septicaemia.
- Empyema. ARDS.

Treatment

- *Conservative treatment*: It is advocated in small perforations due to instrument where there is minimal air leak and contamination of mediastinum with less septic load. Crepitus should be absent; pleura should be clear and without any obstruction. Treatment is - antibiotics, nutrition (TPN/enteral through tube), fluid management, proper observation and monitoring the patient by repeated blood counts, and imaging. Biodegradable removable self expanding stents also can be used. It may also act as a bridge therapy for eventual major surgical exploration. Stents which are used for carcinomas can not be used as they can not be removed.
- *Thoracotomy*, proper saline wash to pleura, mediastinum and repair with buttressing the area using *pedicled intercostal musculo pleural flap is done*. Nasogastric tube for long duration, jejunostomy tube for feeding, ICT for drainage is essential. Often in

One joy scatters a hundred grieves.

late cases decortication of lung is needed to achieve full expansion of the lung.
- Repair over T tube so as to create a controlled fistula along with feeding jejunostomy and ICT on both sides.
- Intraluminal stents/mediastinal irrigation and drainage.
- Resection of oesophagus with gastric pull up. As condition is an emergency situation and with sepsis it carries high mortality.
- Oesophageal exclusion with cervical oesophagostomy above and feeding jejunostomy below.
- Diversion surgeries using colon/stomach/jejunum.

FOREIGN BODY OESOPHAGUS

Common Foreign Bodies

- Coins, metals, plastics.
- Dentures.
- Pins, toothpicks, batteries.
- Fish or meat bones—dangerous – 40%.
- Food (meat – common/vegetables) impaction – 45%.

Sites of Impaction in Oesophagus

- Cervical constriction—C6.
- Broncho aortic constriction—T4.
- Diaphragmatic constriction—T10.
- Pre-existing malignancy or inflammatory stricture site.



Fig. 19.47: Foreign body in the oesophagus.

Features

- Sudden dysphagia with chest pain and breathlessness.
- Later features of shock, sepsis, mediastinitis, empyema.

Management

- X-ray shows site and level of the F/B.
- Endoscopic removal can be tried.
- Impacted large F/B should be removed by thoracotomy.
- Antibiotics, jejunostomy, TPN, ICT are also required.



Fig. 19.48: Foreign body (COIN) in the lower oesophagus. Usually it can be removed by endoscope.

Self-assessment Questions

- Causes for dysphagia.
- Barium swallow.
- Carcinoma oesophagus.
- Management of carcinoma oesophagus.
- Causes for haematemesis.
- Gastro-oesophageal reflux disease.
- Hiatus hernia.
- Plummer-Vinson disease.
- Mallory-Weiss syndrome.
- Oesophagoscopy.
- Sliding hernia.
- Rolling hernia.
- Palliative treatment for carcinoma oesophagus.
- Cardiospasm.
- Achalasia cardia.
- Reflux oesophagitis.
- Barrett's oesophagus (Barrett's ulcer).
- Dyspepsia.
- Causes of upper GI bleeding.
- Tracheo-oesophageal fistula.
- Boerhaave's syndrome.
- Schatzki rings.

20

Stomach

Anatomy
Gastric function tests
Gastrin
Barium meal study
Gastroscopy
Helicobacter pylori
Congenital hypertrophic pyloric stenosis
Gastritis
Acute peptic ulcer
Pyloric stenosis due to chronic duodenal ulcer
Perforated peptic ulcer—*Perforated duodenal ulcer, Perforated gastric ulcer, Perforated stomal ulcer, Dry perforation*
Bleeding peptic ulcer—*Bleeding duodenal ulcer, Bleeding gastric ulcer*
Causes for haematemesis.
Complications of gastric surgery—Stomal ulcer, *Dumping syndrome, Gastrojejunocolic fistula*
Trichobezoar
Chronic duodenal ileus
Acute gastric dilatation
Gastric volvulus
Gastric polyp
Menetrier's disease
Duodenal diverticula
Carcinoma stomach
Gastric lymphoma
Gastric sarcomas
Gastrointestinal stromal tumor (GIST)
Pyloroplasty
Gastrostomy
Gastrectomy
Gastrojejunostomy
Vagotomy

ANATOMY

The stomach contains four anatomic regions:

1. Fundus.
2. Cardia.
3. Body.
4. Antrum.

The *duodenum* is 20-30 cm in length. It extends from pyloric sphincter to ligament of Treitz . It is divided into 4 parts.

90% of duodenal ulcer occurs in the 1st part of duodenum (duodenal bulb/cap).

CBD and pancreatic duct merges to form *ampulla of Vater* and enter the 2nd part of duodenum. The 3rd part of duodenum is wedged between aorta and superior mesenteric artery.



Fig. 20.1: Parts of stomach.

BLOOD SUPPLY OF STOMACH

Arterial Supply

- Left gastric artery, a branch of coeliac artery (Smallest branch of coeliac axis).

Goals and actions must meet.



Fig. 20.2: Blood supply of the stomach.

- Right gastric artery, a branch of hepatic artery.
- Gastroduodenal artery, a (largest) branch of hepatic artery.
- Right gastroepiploic artery, a branch of gastroduodenal artery.
- Left gastroepiploic artery, a branch of splenic artery.
- Short gastric arteries, branches of splenic artery.

Venous Drainage

- Right and left gastric veins drain into portal vein.
- Right gastroepiploic vein drains into superior mesenteric vein.
- Left gastroepiploic vein and short gastric veins drain into splenic vein.
- Prepyloric vein of *Mayo* distinguishes pyloric canal from the first part of duodenum.

NERVE SUPPLY OF STOMACH

- Intrinsic innervation occurs through myenteric plexus of *Auerbach* and submucous plexus of *Meissner.*
- Right vagus is posterior and left vagus is anterior.
- Posterior vagus gives *criminal nerves of Grassi*, which supply lower oesophagus and fundus of stomach, which, if not cut properly during vagotomy, may lead to recurrent ulcer.
- Vagus also gives splanchnic branches (*hepatic and coeliac branches),* ends as *nerve of Latarjet* which supplies the antrum and maintains the antral pump.
- Parietal branches help in HCl secretion, which is an important concept in vagotomy that is done as a treatment in duodenal ulcer.
- *Truncal vagotomy* with posterior gastrojejunostomy is done for chronic duodenal ulcer with pyloric stenosis.
- *Highly selective vagotomy* **(***HSV)* is done in case of uncomplicated chronic duodenal ulcer which is not responding to available medical line of treatment. In HSV, nerve of Latarjet is retained so as to retain antral pump and no drainage is required. Here only the fibres entering the stomach are ligated close to the lesser curve to reduce the acid secretion.
- In *selective vagotomy* splanchnic branches are retained but it is presently not done.
- Gastroduodenal pain is sensed via sympathetic fibres (T_5-T_{10}).



Fig. 20.3: Anatomy of nerve supply of stomach.

HISTOLOGY

- The fundus and body contains parietal and chief cells.
- Parietal cells secrete acid and intrinsic factor.
- Chief cells produce pepsinogen. There are two types of pepsinogen secreted by chief cells – I and II. Pepsinogen I is produced only in stomach. In gastric atrophy pepsinogen I is decreased.
- In the antrum, endocrine cells produce gastrin (G cells) and somatostatin (D cells).
- Pyloric sphincter is a thick circumferential layer of smooth muscle.
- Submucosa is strongest, collagen rich layer of gastric mucosa.
- Gastric mucus is a mucosal barrier containing mucopolysaccharides which maintains the integrity of gastric mucosa.

LYMPHATIC DRAINAGE OF STOMACH

- Lymphatics of proximal half of stomach drain into left gastric, splenic, and superior pancreatic lymph nodes. From antrum, it drains into right gastric, right gastroepiploic, and subpyloric lymph nodes. From pylorus, it drains into right gastric and subpyloric lymph nodes.

- Efferent lymphatics from suprapyloric region drain into para-aortic lymph nodes and so into left supraclavicular lymph nodes. Efferent lymphatics from subpyloric lymph nodes drain into superior mesenteric lymph nodes. Lymphatics near *oesophago-gastric* (O-G) junction communicate with oesophageal lymphatics.
- In carcinoma stomach if upper lymphatics are blocked, retrograde spread through lower lymphatics can occur.



Fig. 20.4: Lymphatic drainage of stomach.

- Presently in carcinoma stomach different resections are classified as R0, R1, R2, R3, or D1, D2 (dissection) based on levels of lymph nodes in the abdomen in relation to the stomach. R0 is *no residual disease*; R1 is microscopic residual disease; R2 is macroscopic residual disease; R3 is inoperable.

DUODENUM

Arterial Supply

It is mainly supplied by superior and inferior pancreaticoduodenal arteries. First part also gets supply from right gastric artery, supraduodenal artery, a branch of hepatic artery.

Venous Drainage

Drains into the splenic, superior mesenteric and portal veins.



Fig. 20.5: After passing the Ryle's tube to the stomach, air from the syringe should be infused through the tube. When auscultated gush of air into the stomach can be heard which confirms that tube tip is in the stomach.

Nerve Supply

Sympathetic from spinal segments T_8 and T_{10}.
Parasympathetic from vagus.

Lymphatic Drainage

Drains mainly to pancreaticoduodenal nodes present along the inside of the curve of duodenum.

GASTRIC FUNCTION TESTS

- Pentagastrin test.
- Hollander's insulin test.
- Radio isotope labelled gastric emptying study.
- 24 hours intragastric pH monitoring
- Gastrin level estimation.
- Fractional test meal (FTM).
- Kay's augmented histamine test.

Pentagastrin Test (Peak acid output test)

Basal acid level of aspirated stomach content (aspiration is done for 1 hour on empty stomach) is analysed. Pentagastrin - 6 microgm/kg body wt. is injected SC/IM, and 15 minutes samples for subsequent hours are collected and analysed. Peak acid output level is calculated. Test is useful in Zollinger-Ellison syndrome, duodenal ulcer and gastric ulcer.

	Basal	*Peak*
Normal	5 mmols	25-27
Gastric ulcer	2	15
Duodenal ulcer	6	35-38
Z-E syndrome	Very high	> than 60

Excellence is rarely found, more rarely valued.

Achlorhydria is defined as a condition in which stomach cannot produce secretions with a pH of less than 7.0 even after maximal stimulation. It is seen in 20% of carcinoma stomach.

Note: Achylia means—no pepsin in the gastric juice.

Insulin Test (*Hollander*)

- This test is useful postoperatively to confirm the completeness of vagotomy. 0.2 units/kg body wt. of insulin is injected intravenously to a fasting patient so as to create hypoglycaemia of below 35 mg%, which in turn stimulates the parietal cells through hypothalamus and through vagus to cause increased acid secretion. Patient who had undergone complete vagotomy does not show increase in acid secretion.
- *Early response* signifies incomplete vagotomy wherein there is increase in acid concentration in first hour of > 20 mmols/L.
- *Delayed response* signifies an increase in acid concentration in between first and second hours, and is probably due to vagal gastrin release.

GASTRIN

- Gastrin is secreted by the G-cells from gastric antrum.
- Number of G-cells are increased in duodenal ulcer, G-cell hyperplasia, but not in gastric ulcer. Normal plasma value is 50 ng/L of plasma (fasting). It is analysed by radioimmunoassay.
- It increases to many 1000's in gastrinomas.
- It also increases in hypochlorhydria due to gastric atrophy and in pernicious anaemia due to negative feedback mechanism.



Fig. 20.6: Foreign body in the stomach. It usually does not harm and commonly passes down.

Investigations for gastroduodenal diseases

- Gastroduodenoscopy is ideal and commonest investigation used to visualise mucosa. Lesions if any biopsy is taken for *H. pylori* and carcinoma. Also often used for endotherapy.
- Endosonography (EUS) is very sensitive method to assess tumors, visualize stomach layers (90% accuracy), lymph nodes (80%), and to detect early liver metastasis which may not be identified by CT especially from left lobe.
- CT scan is good imaging method to detect the stage, spread, nodal status, liver secondaries, and status of lungs.
- CT and PET scan (together) using FDG is better to assess early spread.
- Laparoscopy is very good investigating tool to identify peritoneal secondaries, and to stage the disease. Laparoscopic US is very sensitive to detect the liver secondaries.
- Barium meal studies are used to detect hiatus hernia.
- Celiac angiography is useful in bleeding ulcers, both for diagnostic and therapeutic purpose (therapeutic embolisation).

BARIUM MEAL STUDY

Indications

1. Gastric ulcer—shows a *niche* which is the ulcer crater, a *notch* which is due to spasm of circular muscle on the greater curvature.
2. Chronic duodenal ulcer—shows absence or deformed duodenal cap (due to spasm of 1st part of duodenum, barium will not stay and so cap will not be formed).
3. Gastric outlet obstruction—The cause may be chronic duodenal ulcer with pyloric stenosis or carcinoma pylorus. Features are—
    - Enormous dilatation of stomach.
    - Greater curvature below the level of iliac crest.
    - Absence of duodenal cap.
    - No filling of dye in 2nd part of duodenum.
    - Mottled appearance of stomach because of retained food particles.
    - Evidence of gastritis.
4. Carcinoma stomach—irregular filling defect.
5. Pseudocyst of pancreas—widened vertebro gastric angle.
6. Stomal ulcer in previous gastrojejunostomy.
7. In chronic duodenal ileus (*Wilkie's syndrome)*—shows dilatation of stomach, 1st and 2nd part of duodenum, proximal portion of 3rd part of duodenum.

8. Others—Gastric volvulus, duodenal diverticula, trichobezoar, gastric fistulas, diaphragmatic hernias when stomach is the content.
9. Carcinoma of head of pancreas shows *"pad sign"*; in periampullary carcinoma—*reverse "3'* sign.
   Frostberg's reverse '3' sign (inverted '3' sign).
   Rose thorn duodenum in carcinoma head of pancreas.
10. Hiatus hernia.



Figs 20.7A and B: Barium meal X-rays showing normal picture in one and dilated stomach with features of gastric outlet obstruction in another

Procedure

- Barium sulphate solution is used (Barium is neurotoxic, but in sulphate media it will not get absorbed and so barium sulphate is used (Barium phosphate is not used)).
- About 300 ml solution is given to the patient to drink and its flow down to the stomach is observed under fluoroscopic guidance. Films are taken as required. Commonly oblique views are taken.
- Microcrystalised barium sulphate (*Microbar solution*) is better as it does not get precipitated.

Complication

It may precipitate intestinal obstruction.

GASTROSCOPY

It is visualisation of interior of stomach, duodenum, oesophagus. It can be done as OP procedure.



Fig. 20.8: Technique of doing gastroscopy using videoendoscope.

Uses

1. *For diagnosing any pathology*, e.g.
   - Gastric ulcer.
   - Duodenal ulcer.
   - Gastritis.
   - Stomal ulcer.
   - Carcinoma stomach.
   - Oesophagitis.
   - Varices.
   - Biopsies from the suspected cases of malignancy or for *Helicobacter pylori* can be taken.
     - ***Endosonography*** can be done to assess the staging, operability of carcinoma stomach or oesophagus.
     - Presently fibreoptic, flexible, gastroduodenoscopy is used.

The stomach you can hear, the stomach you can see, the stomach you can feel.—Sir James Walton

2. *Therapeutic*
   - ***Videoendoscopy*** is used not only for diagnosis but also mainly for therapeutic procedures.
   - Both end viewing and side viewing gastroscopes are available.
   - For therapeutic procedures and ERCP, side viewing gastroscope is required.

Therapeutic procedures done are:

- Variceal injection or ligation or glueing or banding.
- Stenting of pseudocyst of pancreas through gastroscopy.
- Polyp removal.
- Submucosal resection.
- For ERCP diagnostic and therapeutic procedures.
- Percutaneous gastrostomy (PEG).

Procedure

Gastroscopy is done following eight hours of fasting. After lignocaine spray into the oral cavity, gastroscope is passed gently down the oesophagus when the patient does the swallowing action. Once the scope is inside the stomach, air is inflated and different parts of the stomach is visualised. Fundus is visualised by retropulsion. Scope is passed through the pylorus to see the 1st and 2nd parts of duodenum and looked for any pathology. If required biopsy is taken.

Often sedation with midazolam is beneficial to have an easy passage.

- *Buscopan is used to relax stomach wall.*
- *Z-line signifies squamo—columnar junction.*
- *Multi-byte biopsy forceps is used.*

Complications

- Bleeding.
- Aspiration.
- Perforation (rarely). Perforation occurs mainly in therapeutic procedures like oesophageal dilatation, endoscopic mucosal resection (EMR). It is common in proximal and middle oesophagus but can occur anywhere. Patient presents with hypotension, tachycardia, sudden severe pain in chest, abdomen, neck and surgical emphysema.



Fig. 20.10: Endosonography of stomach showing different layers with echogenicity.



Fig. 20.9: Gastroscopic views of different parts – vocal cords; pyriform fossa; oesophagus; OG junction; body, fundus and pylorus of stomach duodenum with clearly visible duodenal papilla (*Courtesy by Dr Tantry and Dr Sandeep Gopal, Gastroenterologists, KMC Mangalore*).

Control of *H. pylori* Infection

It is treated with antibiotics and other drugs with different combinations

Clarithromycin 500 mg BD OR Amoxycillin 500-750 mg BD OR Tetracyclines, or Bismuth.	Metronidazole 400 mg BD OR Tinidazole 600 mg BD	Omeprazole 20 mg BD OR Lansoprazole 30 mg BD OR Pantoprazole 40 mg BD

The above regime is given for 7-14 days and then only proton pump inhibitors are continued.

HELICOBACTER PYLORI

- It is gram –ve spiral like flagellated organism, first studied by Warren and Marshall, (both got Nobel prize) which is commonly present in stomach. It is involved in pathogenesis of duodenal ulcer, gastric ulcer, gastritis (type B) and gastric cancer.

H. pylori

- Duodenal ulcer—95%
- Gastric ulcer—70%
- Gastritis—70%
- Gastric cancer—No. 1 carcinogen

Pathogenesis

- It hydrolyses urea so as to release ammonia which through negative feedback mechanism increases the gastrin release from G-cells.
- Infection occurs in stomach, i.e. body, fundus, antrum, which in turn disrupts the mucosal barrier and causes chronic inflammatory response which leads to gastritis, gastric ulcer.
- It also secretes ***cytotoxins*** (cagA and vacA) which may also be involved in inflammatory reaction or malignancy.
- Even though normal duodenum cannot harbour the *Helicobacter*, duodenum with gastric metaplasia can very well get infected by Helicobacter which explains why *Helicobacter* is involved in duodenal ulcer.
- *Helicobacter* is normally not found in saliva.
- Infection is transmitted through faecooral route, with a infection rate of 80-90% in a population (common and high).
- It is more common in lower socioeconomic group.
- It is considered to be a ***carcinogen for stomach.***

  It is identified by:

  a. *Rapid urease test* (cod liver oil test/CLO test)
  b. C13-C14 breath tests (labelled urea breath test)
  c. Biopsy from the different parts of the stomach and staining to identify the organism.

For *H. pylori* three biopsies are taken one each from antrum, body and fundus.

Tests for *H. pylori*—

- Rapid urease test—90% sensitivity, 98% specificity
- C13/ C14 breath tests—95% sensitivity and specificity
  - C13 requires spectrometry and costly
  - C14 uses radioactivity
- Serology to identify Ig G antibody—Elisa test with 90% sensitivity and specificity
- Biopsy and culture—very costly

CONGENITAL HYPERTROPHIC PYLORIC STENOSIS

It is hypertrophy of musculature of pyloric antrum, especially the circular muscle fibres, causing primary failure of pylorus to relax. Duodenum is normal.

Clinical Features

- Common in first born *males* (4:1).
- Incidence is 4 in 1000 births.
- It is familial**.**
- It is seen between 3rd and 6th weeks of age of an infant, the time taken by the hypertrophied muscle to cause complete obstruction.
- Vomiting—forcible, projectile and non-bilious.
- Visible gastric peristalsis (VGP).
- Palpable lump of hypertrophied pylorus which is better felt from left side, as a mobile, smooth, firm mass, with all borders well made out, moves with respiration, with impaired resonance on percussion. It is the most important clinical feature (95%).
- Constipation.
- Dehydration and loss of weight.
- Electrolyte imbalance – hypokalaemic metabolic alkalosis.

Pleasure in the job puts perfection in the work.



Fig. 20.11: Visible gastric peristalsis.

Clinical features of congenital pyloric stenosis

1. Vomiting
2. VGP
3. Palpable mass
4. Constipation and dehydration

In premature infants –

- VGP and mass is better seen and felt.
- Vomiting is regurgitant.
- Anorexia is common.

Diagnosis is established by

— Clinical examination.

— U/S abdomen (very useful)—*Doughnut sign.*
  - Pyloric muscle 4 mm or more in thickness.
  - Length of pyloric canal > 1.8 cm.

— Barium meal shows obstruction.

Differential Diagnosis

- Duodenal atresia (Bilious vomiting is present).
- High intestinal obstruction (e.g. volvulus neonatorum).
- Intracranial haemorrhage.

Treatment

1. Correction of dehydration and electrolyte imbalance.
2. ***Surgery***: *Ramstedt's operation*—After laparotomy, hypertrophied muscle is cut along the whole length adequately until the mucosa bulges out. Mucosa should not be opened (pyloromyotomy). If mucosa is injured, it should be sutured horizontally using interrupted vicryl or silk sutures.



Fig. 20.12: Ramstedt operation for congenital hypertrophic pyloric stenosis. Note that here muscular layer is cut but not mucosal layer.

Complications of surgery:
1. Postoperative pyrexia (Hyperthermia).
2. Gastroenteritis.
3. Electrolyte imbalance.

3. ***Medical treatment***: Not advisable as cure is not guaranteed. Atropine methyl nitrate orally is tried to relax the pylorus muscle.



Figs 20.13 A to C: Ramstedt pyloromyotomy for congenital hypertrophic pyloric stenosis. Only muscular layer is cut to allow mucosa to bulge out.

GASTRITIS

Types

1. Type A gastritis.
2. Type B gastritis.
3. Reflux gastritis.
4. Erosive gastritis.
5. *Others*: Stress gastritis, lymphocytic gastritis, granulomatous gastritis, phlegmonous gastritis.

Type A Gastritis

- Auto-immune disease.
- There is formation of antiparietal cell antibodies.
- Parietal cell dysfunction occurs causing achlorhydria and vitamin B_{12} deficiency.
- Antrum is not affected.
- 'G' cell hyperplasia occurs with raised serum gastrin level.
- There is formation of microadenoma of enterochromaffin like cells (ECL cells) with predisposition to gastric carcinoma.

Type B Gastritis

- Occurs due to *Helicobacter pylori* infection.
- Antrum is affected.
- Peptic ulcer is common.
- Helicobacter related pangastritis commonly occurs which may turn into gastric cancer.

Reflux Gastritis

- Usually occurs after gastric surgeries.
- Prokinetic drugs are useful—metochlopramide, domperidone, cisapride, mozapride.

Erosive Gastritis

- *Occurs due to disturbed gastric mucosal barrier.*
- Induced by NSAIDs/alcohol.
- Due to inhibition of cyclo-oxygenase type 1 (COX-1) receptor enzyme, resulting in decreased prostaglandin production (Prostaglandin is cytoprotective).
- COX-2 mediated NSAIDs will not cause erosive gastritis.

Stress Gastritis

Treatment:
- IV Ranitidine 50 mg 8th hourly.
- IV Omeprazole/pantoprazole.
- Sucralfate orally.



Fig. 20.14: Endoscopic view of erosive gastritis.

Lymphocytic Gastritis

It is associated with *H. pylori* infection.

Granulomatous Gastritis

It is seen in Crohn's disease and tuberculosis.

Phlegmonous Gastritis

It is due to severe bacterial infection of stomach. It is rare but dangerous.

NON-ULCER DYSPEPSIA

- Symptom complex with pain and discomfort in the upper abdomen.
- It occurs in 25% of population – large number.
- Anatomical or biochemical abnormalities are not discovered in this condition.
- *H. pylori* is not associated with this condition.
- Often it lasts for long time decreasing the quality of life.
- Differential diagnosis – GERD/acid peptic diseases/gall stones/pancreatitis/carcinoma.
- *H. pylori* eradication is not required and there is no surgical role.

Troubles waste the stomach like rust waste iron.—Croatian proverb

ACUTE PEPTIC ULCER (DUODENAL OR GASTRIC ULCER)

They are usually multiple erosions due to disruption of the mucosal barrier.

Causes

Stress, drugs like analgesics, steroids, surgeries.

Clinical Features

- Sudden onset of acute pain and tenderness in epigastric region.
- Vomiting with or without haematemesis.
- Often acute peptic ulcers can lead to perforations.

Acute ulcers after cerebral trauma or neurosurgeries are called *as Cushing's ulcers*.

Acute ulcers after major burns are called *as Curling's ulcers*.

Diagnosis is by gastroscopy.

Treatment

- Intravenous ranitidine 50 mg, 8th hourly.
- IV fluids.
- Blood transfusions if there is bleeding.

Most of the time surgery is not required for acute ulcers. During follow-up patients are advised to take antiulcer drugs for 4-6 weeks—ranitidine, omeprazole or lansoprazole.

Curling's ulcers

They are acute ulcers which develop after major burns, presenting as pain in epigastric region, vomiting or haematemesis. Treatment is conservative- IV ranitidine. IV pantoprazole 80 mg in 100 ml DNS—slow, later 40 mg IV maintenance.

Note: Curling's ulcer occurs when burn injury is more than 35%. It is observed in the body and fundus not in antrum and duodenum.

Cushing's ulcers

They are acute ulcers which develop after cerebral trauma or after neurosurgical operations. Treatment is conservative by IV Ranitidine.

GASTRIC ULCER

Aetiology

It occurs due to imbalance between protective and damaging factors of gastric mucosa.

- Atrophic gastritis.
- Smoking, alcohol.
- *Helicobacter pylori* infection (70%).
- There is either normochlorhydria or hypochlorhydria.
- Altered mucosal barrier mechanism.
- Lower socioeconomic group.

Factors Involved in Gastric Ulcer Formation

- Duodeno gastric reflux – reflux containing bile salts and lysolecithin break the mucosal barrier making it more vulnerable for injury, action of drugs and pepsin injury.
- Gastric stasis.
- Ischaemia of the gastric mucosa.

Pathology



Fig. 20.15: Specimen of stomach (identified by the mucosal pattern and rugae) showing deep ulcer near lesser curvature. Margin of the ulcer is clear, not everted with gastric mucosal folds converging towards the base of the ulcer. 95% of benign gastric ulcer occurs towards lesser curve. Benign gastric ulcer is more common in lesser curvature, as it takes more burden of passage of food and so more of wear and tear. Benign gastric ulcer is rare in greater curvature, fundus and cardia. Histologically it shows destruction of epithelial lining; proliferation of margin; destruction of the part of the muscle layer; granulation tissue in the floor; infiltration with chronic inflammatory cells; endarteritis and fibrosis in the base.

- Gastric ulcer is large in size, usually lies in the lesser curvature, its floor being formed by the muscular layer.
- Posteriorly it may penetrate into the pancreas; it may cause torrential bleeding by eroding left gastric (commonly) vessles or splenic vessels or vessels in the gastric ulcer wall.
- Anteriorly it may perforate or penetrate into the liver. It may lead into *hour glass contracture, or tea-pot deformity*.
- Microscopically, it shows ulcer crater with chronic inflammatory cells and granulation tissue, end arteritis obliterans and epithelial proliferation.

  (Ulcer to the right of the incisura is malignant unless proved otherwise).
- Gastric ulcer > 3 cm is called as giant gastric ulcer. It has got 6-23% chances to turn in to malignancy.

Types of Gastric Ulcer (Daintree Johnson)

Type	*Location*	*Incidence*	*Acid level*
Type I	In the antrum, near the lesser curve	55%	Normal
Type II	Combined gastric ulcer (in the body) with duodenal ulcer	25%	High
Type III	Prepyloric ulcer	15%	High
Type IV	Gastric ulcer in the proximal stomach or cardia	5%	Normal

Note: Often in lesser curve, saddle shaped ulcer can occur.

- Grossly, margin of the benign gastric ulcer is clear; deep; near lesser curve; edge is not everted with gastric mucosal folds *converging* towards the base of the ulcer.
- 95% of benign gastric ulcer occurs towards lesser curve, as it takes more burden of passage of food and so more of wear and tear. Benign gastric ulcer is rare in greater curvature, fundus and cardia.

Clinical Features

- Equal in both sexes.
- *Pain* in epigastric region after taking food, lasting up to two hours. Pain is uncommon during night. It is relieved by vomiting or by inducing vomiting.



Fig. 20.16: Types of gastric ulcer.

- *Periodicity*: Symptom free interval may be 2-6 months. Often with seasonal variation.
- *Vomiting* relieves pain and often it is induced by the patient for relief of pain.
- *Haematemesis and melaena*: Haematemesis is more common.
- Appetite is good but hesitant to eat, because eating induces pain and that results in loss of weight. But once complications occur, appetite decreases. Aversion to spicy, fried foods occurs.
- On deep palpation, tenderness is felt in epigastric region.

Differential Diagnosis

- Hiatus hernia.
- Cholecystitis.
- Chronic pancreatitis.
- Chronic gastritis.
- Dyspepsia.
- Carcinoma stomach.



Fig. 20.17: Barium meal showing NICHE in the lesser curve as benign gastric ulcer.

It is consequences which are more important than rewards or punishments.

Investigations



Fig. 20.18: Benign gastric ulcer endoscopic view. Biopsy is a must. Ideally 10 biopsies should be taken from the edge.

- Barium meal X-ray to see *niche and notch.*

Barium meal X ray features of benign gastric ulcer

- *Niche* on the lesser curve with *notch* on the greater curvature
- Ulcer crater projects beyond the lumen of the ulcer
- Regular / round margin of the ulcer crater – *stomach spoke wheel pattern*
- Overhanging mucosa at the margins of a benign gastric ulcer – projects inwards towards the ulcer – *Hamptom's line*
- Converging mucosal folds towards the base of the ulcer
- Symmetrical normal gastric mucosal folds

- Gastroscopy is done to see the location, type of ulcer and also to take biopsy (10 biopsies).
- US abdomen mainly to rule out other diseases and to confirm associated diseases.



Fig. 20.19: Gastric ulcer in prepyloric region.



Fig. 20.20: Multiple ulcers visualised in the gastroscopy.



Fig. 20.21: Multiple gastric ulcers on endoscopy.



Fig. 20.22: Gastric ulcer in the body of the stomach.



Fig. 20.23: Barium meal study showing niche and notch—gastric ulcer.

Treatment

- Drugs like H_2 blockers, proton pump inhibitors, carbenexolone (Biogastrone, Sucralfate, prostaglandins which coats the ulcer and so creates a mucosal barrier) helps in reducing or eliminating the symptoms.
- But asymptomatic ulcer may exist silently and may turn into malignancy.
- ***So surgery is the preferred line of treatment. Partial gastrectomy and Billroth I gastroduodenal anastomosis is done.***
- Type IV proximal gastric ulcer is difficult to manage. It is treated by subtotal gastrectomy. Often distal gastrectomy with selective sleeve like extension cut along the lesser curve to remove the ulcer is done–Pauchet's procedure.

Complications of Gastric Ulcer

1. ***Hour glass contracture***: It occurs exclusively in ***women***, is due to cicatricial contracture of lesser curve ulcer.
   - Here stomach is divided into two compartments.



Fig. 20.24: Hour glass contracture.

   - *Clinical features*
     - Loss of periodicity.
     - Persistent pain.
     - Vomiting.
     - Loss of appetite and weight.
   - *Diagnosis*
     - *Barium meal*: It shows filling only in the proximal stomach or double pouched stomach.
     - Gastroscopy.
   - *Treatment*

     Partial gastrectomy wherein gastric ulcer with lower compartment of the stomach is removed and Billroth-I anastomosis is done.
2. ***Tea-pot deformity*: (Hand-Bag stomach**) is due to cicatrisation and shortening of the lesser curvature.
   - They present with features of pyloric stenosis.
   - Treatment is partial gastrectomy with Billroth-I anastomosis.



Fig. 20.25: Tea-pot deformity.

3. ***Perforation.***
4. ***Bleeding*** *by erosion into the left gastric and rarely splenic vessels or to vessels in the wall of ulcer.*
5. ***Penetration*** *posteriorly into pancreas, anteriorly into liver.*
6. ***Malignant*** *transformation usually into* ***adenocarcinoma of stomach (2-5%)****.*

DUODENAL ULCER

Aetiology

- Common in people with blood group O +ve.
- Stress, anxiety—'*hurry, worry, curry*'.
- *Helicobacter pylori* infection is an important aetiology for duodenal ulcer (90%).
- NSAIDs, steroids.

Every man is the master of his own fortune.

	Benign gastric ulcer	*Malignant gastric ulcer*
Mucosal folds	Converging mucosal folds upto the margin	Effacing mucosal folds
Site	95% lesser curve	Greater curvature
Margin	Regular margin	Irregular margin
Floor	Granulation tissue in floor	Necrotic slough in floor
Edge	Not everted; punched or sloping	Everted edge
Surrounding area	Surrounding area and rugae are normal	Surrounding area shows nodules, ulcers and irregulaties
Size and extent	Small, deep up to part of muscle layer	Large and deep



Fig. 20.26: Anatomical location of chronic duodenal ulcer.

- Endocrine causes: Zollinger–Ellison syndrome, MEN syndrome, hyperparathyroidism.
- Other causes: Alcohol, smoking, vitamin deficiency.

Pathology

- Ulcer occurs in the first part of duodenum, usually with in the first inch,involving the muscular layer. *Sites:*
  a. In the bulb (bulbar)—95%.
  b. Post bulbar (5%).
- Eventually it shows cicatrisation causing pyloric stenosis. Serosa overlying the site of duodenal ulcer shows petechial haemorrhages with speckled red dots, appearing like sprinkled *cayenne pepper*.



Fig. 20.27: Serosal surface in a chronic duodenal ulcer. It appears like cayenne pepper.

- Microscopically, ulcer with chronic inflammation with granulation tissue, gastric metaplasia of duodenal mucosa, endarteritis obliterans are visualised.
- Sometimes two opposing ulcers, i.e. over anterior and posterior surfaces of duodenum are present and are called as *kissing ulcers.*
- An anterior ulcer *perforates* commonly, posterior ulcer *bleeds or penetrates* commonly.

Clinical Features

- In India, ratio of duodenal ulcer to gastric ulcer is 30 : 1. A very high incidence.
- It is common in all socio-economic group, more with stressed professionals (Type A personality).
- *Pain* is more before food, in early morning and decreases after taking food. It is classically called as ***hunger pain*** as it is relieved by taking food. Night pains are common.
- Common in males.
- *Periodicity* is more common than in chronic gastric ulcer with seasonal variation.
- *Water-brash, heart burn, vomiting* may be present.
- *Melaena* is more common, *haematemesis* also can occur.
- Appetite is good and there is gain in weight. It decreases once stenosis develops.
- Eats more frequently without any restriction.
- Chronic duodenal ulcer can ***be uncomplicated or complicated.***

Differences between clinical features of gastric ulcer and duodenal ulcer

Gastric ulcer	*Duodenal ulcer*
Pain after food intake	Pain before food intake
Periodicity less common	Periodicity more common
Haematemesis more common	Malaena more common
Weight loss occurs	Weight gain occurs
Equal in both sexes	Common in males

Complications of Duodenal Ulcer

1. Pyloric stenosis: Due to scarring and cicatrisation of first part of the duodenum.
2. Bleeding (10%).

3. Perforation (5%). Both acute and chronic ulcers can perforate. Anterior ulcers perforate.
4. Residual abscess.
5. Penetration to pancreas.

Note: Chronic duodenal ulcer *will not turn into* malignancy.

Investigations

- Barium meal X-ray shows deformed or absence of *duodenal cap* (because of spasm). Appearance of *'trifoliate'* duodenum is due to secondary duodenal diverticula which occurs as a result of scarring of ulcer.



Fig. 20.28: Absence of duodenal cap—chronic duodenal ulcer.

- Gastroscopy reveals the type, location of ulcer, narrowing if any. Biopsy also can be taken to look for the presence of *Helicobacter pylori*. Usually biopsies are taken from duodenum, pylorus, antrum, body, fundus, and confirmed by rapid urease test or C13 or C14 breath tests.
- Estimation of serum gastrin level, serum calcium level.



Fig. 20.29: Endoscopic view of duodenal ulcer



Fig. 20.30: Chronic duodenal ulcer, gastroscopy view.

Differential diagnosis

- Carcinoma stomach (pylorus)
- Dyspepsia due to other causes
  - Hiatus hernia
  - Oesophagitis
  - Cholecystitis
  - Chronic pancreatitis

Treatment

I. ***General measures:*** Avoid alcohol, NSAIDs, smoking, spicy foods. Have more frequent food.

II. ***Specific measures*:**

Drugs

1. *H_2 Blockers:* Promotes ulcer healing in 4-8 weeks, by reducing acid secretion.
   - Tab cimetidine.
   - Tab ranitidine (300 mg HS or 150 mg BID), (IV preparation is available).
   - Tab famotidine (IV is available) *Most potent H_2 blocker*. Dose is 20-40 mg/day.
   - Tab roxatidine.
   - Tab nizatidine.
2. *Proton pump inhibitors*: Inhibit parietal cell H^+, K^+ ATPase enzyme responsible for acid secretion. They are used for 6-12 weeks. They stop acid secretion completely.
   - Omeprazole 20 mg OD 1 hour before food—IV preparation is available.
   - Esomeprazole 40 mg.
   - Lansoprazole 30 mg.
   - Pantoprazole 40 mg—IV preparation available.
   - Rabeprazole 20 mg—IV preparation available.

> *Patients with peptic ulcer were regularly "milked" for acid, which was used for patients suffering from hypochlorhydria.*
> — Albert E Coates

Anti-Helicobacter regime (Triple regime)		
Clarithromycin 500 mg BD OR Amoxycillin 500-750 mg BD OR Tetracyclines, or Bismuth, etc.	Metronidazole 400 mg BD OR Tinidazole 600 mg BD	Omeprazole 20 mg BD OR Lansoprazole 30 mg BD OR Pantoprazole 40 mg BD

3. *Antacids*: Neutralises the HCl to form water and salt and also inhibits peptic activity. Aluminium hydroxide and magnesium trisilicate are commonly used.
4. *Sucralfate* is an aluminium salt of sulfated sucrose which provides a protective coat to ulcer crater thereby promotes healing. It inhibits peptic activity. Dose is 1 g qid for 6 weeks (Before food). It is an effective drug.
5. *Anti-Helicobacter pylori regime*: It is very useful, given for 7-14 days—later the proton pump inhibitors are continued.
6. *Colloid bismuth sulphate* is a good drug for ulcer, but it stains the oral cavity and mucosa.
7. Misoprostol is the only prostaglandin agonist accepted. Follow-up gastroscopy is a must, to confirm that ulcer has healed.

Note: Antacids and H_2 blockers should not be used along with PPI as these drugs will reduce the action of PPIs by creating alkaline media.

Indications for surgical intervention for chronic DU (Uncomplicated DU):

1. Uncomplicated DU, not responding to drug therapy of 8-12 weeks-**intractable duodenal ulcer**
2. Repeated recurrences

Presently most of the uncomplicated DU does not require surgery

Surgery for Uncomplicated DU

- Highly Selective Vagotomy (HSV).
- Selective vagotomy with pyloroplasty (SV + P).
- Truncal vagotomy with gastrojejunostomy (TV + GJ).

In HSV, only fibres supplying the parietal cells are ligated. Nerve of Latarjet which supplies the antrum pump is retained and so no drainage procedure is required in HSV. HSV is also called as *parietal cell vagotomy or superselective vagotomy.* Here nerve fibres in last 6 cm of stomach, just proximal to pylorus are preserved (Crow's foot). Vagotomy reduces acid secretion, hence ulcer heals. No acid, No ucler.

- Posterior truncal vagotomy with anterior seromyotomy—*Taylor's operation*. It can be done through laparoscopy.

Note: Presently, there is *no role of gastrectomy or gastrojejunostomy (Just GJ) for uncomplicated DU.*

PYLORIC STENOSIS DUE TO CHRONIC DUODENAL ULCER

Pathology

Chronic DU after many years undergoes scarring and cicatrisation causing total obstruction of the pylorus, leading to enormous dilatation of stomach.

Clinical Features

- Pain is severe, persistent, in epigastric region, and also with feeling of fullness.
- Vomiting–large quantity, foul smelling and frothy, vomitus contains food consumed on previous day (partially digested or undigested food).
- Loss of periodicity.
- Loss of appetite and weight.
- *Visible gastric peristalsis* (VGP)—may be elicited by asking the patient to drink a cup of water.
- *Positive succussion* splash which is done with 4 hours empty stomach, by placing a stethoscope over the epigastric region and shaking the patient adequately.
- *Ausculto percussion test* shows dilated stomach.
  Test is done by placing a stethoscope over the epigastric region. Skin is scratched from left side downwards, at several points away from the epigastrium (towards left side) using finger and these points are joined. Normally greater curvature of stomach is above the level of umbilicus (midway between the umbilicus and epigastrium). In gastric outlet obstruction it lies below the level of the umbilicus (Stomach we see; stomach we feel; stomach we hear).
- Confused status because of alkalosis and electrolyte changes.
- ***Electrolyte changes***: Because of vomiting, *hypochloraemic, hyponatraemic, hypokalaemic, hypocalcaemic, hypomagnesaemic alkalosis occurs. It causes **paradoxical aciduria**.*
- Mass is never palpable.

Investigations

1. Barium meal study:
   - Absence of duodenal cap.

   - Dilated stomach where greater curvature is below the level of iliac crest.
   - Mottled stomach.
   - Barium will not pass into duodenum.
2. Gastroscopy to rule out carcinoma stomach and to visualise the stenosed area.
3. Electrolyte study for correction of electrolyte imbalance
4. ECG to check for hypokalaemia.



Fig. 20.31: Pyloric stenosis with gastric dilatation.



Figs 20.32A and B: Barium meal pictures showing gastric outlet obstruction.

Differential Diagnosis

Carcinoma pylorus—here mass may be palpable.

Pyloric stenosis—causes

- Congenital
- Chronic DU—fibrosed/cicatrised
- Carcinoma pylorus
- Adult pyloric stenosis – it is treated by pyloroplasty (not by pyloromyotomy)
- Pyloric mucosal diaphragm – it should be excised surgically or endoscopically

Treatment

- Correction of dehydration and electrolytes by IV fluids—normal saline or double strength saline, calcium, potassium, magnesium.
- Blood transfusion is given if there is anaemia.
- TPN support.
- Stomach wash to clean the stomach contents (using normal saline) is given using stomach tube like Eswald's. It also reduces the oedema of stomach wall and improves gastric emptying time by increasing the gastric muscle tone.
- Surgery
  - Truncal vagotomy along with gastrojejunostomy of *Mayo (posterior, vertical, short loop, retrocolic, iso-peristalsis) is done – Ideal.*
  - Vagotomy, antrectomy (acid secreting area) with Billorth I anastomosis along with feeding jejunostomy for nutrition is the other option.

Note:

- Often gastric emptying may be delayed for 2-4 weeks after surgery in pyloric stenosis. It usually recovers in 7 days.
- After recovery eradication of *H. pylori* infection is routinely done even though infection may not be evident in many of patients with outlet obstruction.
- *No role of pyloroplasty or HSV in a scarred duodenum – as it can cause disruption and bile leak.*
- Gastrectomy and other procedures are usually not necessary in pyloric stenosis.
- Endoscopic balloon dilatation of the stenosed area benefits only temporarily with high recurrence rate.



Fig. 20.33: Truncal vagotomy and gastrojejunostomy. It is posterior, vertical, short loop, retrocolic, isoperistaltic GJ of Mayo.

> *An inn has one entrance and three exist—to hospital, to asylum and to prison.* —Croatian Proverb



Fig. 20.34: Gastrojejunostomy stoma view on endoscopy.



Fig. 20.35: Vagotomy and antrectomy. It is used for intractable resistant duodenal ulcer or chronic duodenal ulcer with obstruction. HSV is commonly used in intractable cases. GJ with vagotomy is commonly used in pyloric stenosis due to chronic duodenal ulcer.

ELECTROLYTE CHANGES IN PYLORIC STENOSIS

- Hyponatraemia.
- Hypokalaemia.
- Hypomagnesaemia.
- Hypochloraemia.
- Metabolic alkalosis.
- Paradoxical aciduria.

Because of severe vomiting which contains acid as well as undigested retained food, sodium, chloride, potassium, magnesium levels drop, causing metabolic alkalosis. Alkalosis can lead to hypocalcaemia causing tetany. It is called as ***'gastric tetany'.***

To control alkalosis, kidney secretes excess bicarbonate. (In alkalosis without hyponatraemia, bicarbonate is secreted along with sodium). Here, due to hyponatraemia, body conserves sodium and so bicarbonate is secreted along with hydrogen ion. So urine becomes *acidic*. It is called as ***paradoxical aciduria.***

Clinical Features

- Irritability, confused status, dehydration.
- Often convulsions can occur.
- Features of alkalosis like rapid breathing—Cheyne-Stokes breathing and tetany.

Investigations

- Serum electrolytes.
- Arterial blood gas analysis.
- Serum calcium level estimation.

Treatment

- Double strength normal saline.
- IV potassium given slowly under ECG monitoring
- The cause is treated.
- IV magnesium.

Note: Metabolic changes are not severe in carcinoma pylorus as it is seen in pyloric stenosis due to chronic duodenal ulcer because in carcinoma stomach often there is hypochlorohydria or achlorohydria.

PERFORATED PEPTIC ULCER

- It is the terminology used for *perforation of duodenal ulcer or gastric ulcer or stomal ulcer.* Otherwise all clinical features and management are similar.
- Perforation is common in duodenal ulcer (75% of perforated peptic ulcers). Mortality is more in gastric ulcer perforation and perforation in elderly.

A. PERFORATED DUODENAL ULCER

- It is common in males (8:1) between 35-45 years of age group, but can occur in any age group.
- ***Anterior ulcer*** perforates, commonly
  - In 80% of cases, there is a history of chronic DU.
  - In 20% cases, it is silent perforation.
- Perforation can occur in acute ulcers or in acute presentation of a pre-existing chronic ulcer.
- Perforation may be precipitated by steroids, analgesics (NSAIDs), alcohol, antimalarials.
- Overall incidence is 5%.
- Active ulcers perforate commonly.

Stages of Perforation

- *Stage of chemical peritonitis:* Once perforation occurs, stomach contents escape into the peritoneal cavity. The acid from the stomach causes chemical peritonitis leading to severe pain in epigastric region, vomiting, tenderness, guarding, rigidity, tachycardia, sweating.

- *Stage of reaction (Stage of illusion):* Peritoneum secretes lot of fluid to neutralise the escaped content and so temporarily the pain reduces, and the patient feels better. This phase lasts for about 6 hours.
- *Stage of diffuse bacterial peritonitis:* After about six hours, bacteria from GIT (escape) migrate from the site of perforation causing diffuse peritonitis.

Clinical Features

- Presents with *severe persistent pain* in the epigastrium initially, later in the right side abdomen (as the inflammatory fluid spills along the right paracolic gutter) and finally becomes generalised. Pain is of sudden in onset, is due to contact of expelled gastric contents with the parietal peritoneum. Pain often radiates to right scapular region. Pain becomes more on movements.
- Tenderness and rebound tenderness is seen (*Blumberg sign*) all over the abdomen.
- Fever, vomiting, dehydration, oliguria occurs.
- Patient is toxic, with tachycardia, hypotension, tachypnoea.
- Abdominal distension occurs.
- Guarding and rigidity, initially in the epigastrium but later all over the abdomen.
- Dullness over the flank because of fluid.
- *Obliteration of liver dullness*—as a result of collection of escaped gas under the diaphragm.
- Silent abdomen with absence of bowel sounds.
- Tenderness felt on per rectal examination.
- Sometimes fluid from supracolic region slowly trickles down along the right paracolic gutter and collects in right iliac region causing pain and tenderness in RIF mimicking appendicitis.
- Often slow, small perforation presents with subacute features, but diffuse peritonitis eventually sets in 24-48 hours.



Fig. 20.36: Spread of DU perforation.

Terminal stage: Patient may have oliguria, septicaemia, shock, *Hippocratic facies* (sunken eyes, cold periphery and shallow rapid breathing, ill look), with MODS (Multi-organ dysfunction syndrome).

Investigations

- Plain X-ray abdomen (erect posture): Shows gas under diaphragm in 70% of cases. In 30% of cases, there is no gas under diaphragm. It may be due to, either the gas leak is less than 1 ml or due to previous surgery causing adhesions between liver and diaphragm, or sealed peptic ulcer.



Fig. 20.37: Note the site of the DU perforation, on table.



Fig. 20.38: Plain X-ray abdomen in erect position with ground-glass appearance and gas under diaphragm—perforation.

> *Things turn out best for people who make best of the way things turn out.*



Fig. 20.39: Lateral decubitus X-ray showing air under diaphragm. This is done when patient is critically ill and can not make the patient stand in erect posture.


5 mm port
Perforation
Midline incision
5 mm
5 mm
10 mm (camera)

Fig. 20.40: Approaches to manage duodenal ulcer perforation can be either open(upper midline incision) laparotomy incision or laparoscopic.


DU perforation
Omental patch
1
3
2
Sutures
1
3
2
Colon

Fig. 20.41: Duodenal ulcer perforation closed horizontally using interrupted silk/vicryl sutures with omental patch over it.

(*Chilaiditi*'s syndrome is the interposition of the colon in front and above the liver. It is common in children and elderly. It may be mistaken for gas under diaphragm in plain X-ray abdomen).

- U/S abdomen shows free fluid and often gas.
- Blood urea, serum creatinine, total count, electrolytes, are helpful.


Perforation
A
Closure of perforation
B
C
Omental patch
C

Figs 20.42A to C: Duodenal ulcer perforation and its closure using omental patch.

- CT is very sensitive investigation whenever there is absence of gas under diaphragm. It rules out other conditions like pancreatitis. Gastrograffin upper GI study also confirms the perforation.

Differential diagnosis

- Acute appendicitis
- Acute pancreatitis
- Acute cholecystitis
- Ruptured aortic aneurysm
- Myocardial infarction
- Mesenteric ischaemia
- Pneumonia

Treatment

- Patient is advised admission.
- IV fluids—Ringer lactate, normal saline, dextrose saline.
- Antibiotics—Cefotaxime, metronidazole, amikacin.
- Catheterisation.
- Ryle's tube aspiration.
- *Surgery:*
  - Emergency laparotomy through upper midline incision is done.
  - All infected fluid is sucked out.
  - Perforation is identified and closed with interrupted, horizontal sutures using *either silk or vicryl*. Omental patch is placed and fixed with loose sutures—It is called as ***Rosoe-Graham Operation.***
  - Peritoneal wash (toilet) using 5-10 litres of saline is given.
  - Drain is placed and abdomen is closed, often if required with *tension sutures*. Drain is removed in 3-5 days. During discharge, patient is advised to avoid alcohol and to take H_2 blockers or proton pump inhibitors for 6-12 weeks.
  - After 12 weeks ***follow up gastroscopy must be done.***

Note:

- Very rarely, in elderly people or in cases of subacute perforation which gets sealed on its own, *conservative treatment is* tried with careful observation, i.e. by giving IV fluids, antibiotics, Ryle's tube aspiration, maintenance of urine output and electrolytes. It is called as *Hermen-Taylor regime.* But it should not be a standard treatment.
- Laparoscopy is beneficial for both diagnoses, as well as for therapy for perforation closure using omental patch. It is proposed and widely used for early duodenal perforation. It can be useful for most of the duodenal ulcer perforations. If it is problematic, conversion options should always be kept in mind.
- Once perforation is closed, either by open or laparoscopic method, after recovery patient should be advised, *anti-Helicobacter pylori* therapy (triple regime for 14 days) with PPI for 3 months. It reduces rate of reperforation and ulcer recurrence in duodenal ulcer.
- In patients with severe peritonitis and critically ill, after perforation closure it is better to insert a nasojejunal tube or feeding jejunostomy for nutrition in postoperative recovery period. Even if patient develops a temporary duodenal leak, this supports nutrition well until the leak stops.
- Occasional large perforated duodenal ulcer with oedema which can not be closed is managed by serosal patch/duodenal drainage and pyloric exclusion/gastrostomy, duodenostomy and jejunostomy/Roux-en-Y jejunal patch over the perforation.
- *Manheim peritonitis index* or *APACHE II* scoring system is used to assess the patient properly.
- Doing concomitant acid reducing surgical procedure like HSV is under debate and not used routinely (not advised) even though some centers advocate. HSV may be done if there is not much contamination of the peritoneal cavity or in early perforation of a chronic duodenal ulcer.

B. PERFORATED GASTRIC ULCER

- Commonly ulcer in the lesser curve near the antrum perforates. Amount of gas escaped is more than the perforated DU. Malignancy should always be suspected and so *biopsy from the edge is a must.*
- Mortality in gastric ulcer perforation is high (20%).
- Commonly they are prepyloric in position.
- Primary closure with an edge biopsy is commonly used. Distal gastrectomy including ulcer area is better option if patient's general condition is favourable.
- Posterior gastric ulcer perforation is often difficult to diagnose both clinically and radiologically.

65% of haematemesis is due to bleeding peptic ulcer. Among peptic ulcer, duodenal ulcer (35%) is the most common cause.



Fig. 20.43: Gastric perforation on table finding.

C. PERFORATED STOMAL ULCER

***In perforation of stomal ulcer**, often undoing of GJ or partial gastrectomy may be required.*

D. DRY PERFORATION (Perforated duodenal ulcer sealed by omentum)

- Patient is ambulatory.
- Vomiting is absent.
- Rigidity confined to epigastrium and right hypochondrium.

Different signs in X-ray in perforation

- *Cupola sign* – crescent shaped radiolucency under the diaphragm
- *Riglers sign* – visualisation of both aspects of the bowel wall being outlined by gas on either side
- *Inverted V sign* – gas on either sides of the falciform ligament
- *Football sign* – collection of gas in the center of the abdomen like a foot ball
- *Triangle sign* – gas between bowel loops

Conditions which mimic pneumoperitoneum - pseudopneumoperitoneum

- Subpulmonary pneumothorax
- Chilladiti syndrome
- Subphrenic abscess due to infections by gas forming organism like *Clostridium Welchii*
- Subdiaphramatic fat or omental fat under the diaphragm may rarely mimic gas under the diaphragm

BLEEDING PEPTIC ULCER

- It is **bleeding either from duodenal ulcer, or gastric ulcer or stomal ulcer**.
- In bleeding from stomal ulcer, partial gastrectomy is required (Fig. 20.44).
- Mortality in bleeding peptic ulcer is high (20-30%). Elderly age, associated systemic diseases increase the mortality.
- NSAID's and *H. pylori* infection, coagulopathy, and anticoagulant drugs are common precipitating factors. Concomitant use of NSAID and steroids increase risk by 10 fold.


Left. gastric artery
Coeliac artery
Right gastric artery
Gastroduodenal artery
DU
GU
Splenic artery
Left gastroepiploic artery
Right gastroepiploic artery

Fig. 20.44: Sites of gastric ulcer and duodenal ulcer bleeding. Note GU can erode into the left gastric artery. DU can erode into the gastroduodenal artery.


Endoscope
Inflated stomach
Ulcer
Air
Ulcer
Non-inflated stomach
Pooled blood

Fig. 20.45: In bleeding ulcer during endoscopy stomach should be inflated with air adequately so that bleeding ulcer is visualised well.

A. BLEEDING DUODENAL ULCER

- 10% common.
- Risk of bleeding in chronic duodenal ulcer increases to 35% if patient has not taken specific antihelicobacter pylori therapy and PPI.
- Bleeding from DU is either from the small vessels in the wall of ulcer crater or due to erosion into the gastroduodenal artery.

- Usually posterior duodenal ulcer bleeds.
- Bleeding from small vessels in the wall of ulcer is due to sloughing of the ulcer. It is less severe, gradual and most often well-controlled by conservative treatment.
- Bleeding from erosion of gastroduodenal artery is severe, torrential and almost always needs early surgical intervention.

Precipitating causes

- Alcohol
- NSAIDs, steroids
- Excessive fibrosis
- Atherosclerotic disease

Forrest classification of bleeding or bled ulcer

Ia Spurting and bleeding
Ib Non-spurting but active bleeding
IIa Visible vessel with red or blue protrusion or pulsatile pseudoaneurysm
IIb Non-bleeding ulcer with clot overlying
IIc Ulcer with haematin base
III Clean ulcer—no clot, no vessel

Clinical Features

- *Haematemesis and melaena.*
- Features of shock: Pallor, tachycardia, sweating, hypotension, tachypnoea, dry tongue, cold periphery.
- Past history of chronic DU may be present. But it is not always necessary in every patient, as some may have a silent ulcer which may present as bleeding and haematemesis to begin with.
- History of pain and tenderness in epigastric region which has increased in intensity recently.



Fig. 20.46: Melaena – typical black, tarry coloured foul smelling stool. It signifies upper GI bleed. At least 50 ml bleeding should be there to cause melaena.

Differential diagnosis

- Erosive gastritis
- Oesophageal varices
- Carcinoma stomach
- Bleeding gastric ulcer
- Mallory-Weiss syndrome
- Gastric polyps
- Bleeding disorders

Investigations

To look for in endoscopy, in bleeding ulcer—

- Spurter
- Clot
- Visible vessel
- Aneurysmal dilatation of the arteriole in the wall of ulcer.
- Ooze



Fig. 20.47: Bleeding duodenal ulcer endoscopic view.

- Gastroscopy is confirmative—it is a must. It identifies ulcer bleed in 90% of cases clearly. Possibility of rebleed is also assessed by endoscopy. A flat clear based ulcer is less likely to rebleed. Active ulcer/fresh clot/visible vessel/pseudoaneurysm/large ulcer are more likely to rebleed. *Rockall scoring system* is used to predict rebleed.
- Coeliac angiogram to identify the bleeder may be helpful.
- Hb% and PCV—should be repeated at regular intervals (once in 2-3 hours).
- Blood group and cross matching.
- Estimation of serum electrolytes, blood urea, serum creatinine, platelet count.

Choice, not chance, determines destiny.

Treatment

Seventy percent of bleeding duodenal ulcers are treated conservatively.

- The shock is corrected initially by:
    - Foot end elevation.
    - IV fluids, plasma expanders (haemaccel, dextran, crystalloids). CVP line is better in these patients.
    - Sedation.
    - Catheterisation – to assess urine output.
    - Blood transfusion to replace the lost blood.
- Stomach wash is given—1 : 2,00,000 adrenaline in saline wash is given to the stomach through Ryle's tube.
- IV ranitidine 50 mg 6th or 8th hourly. IV famotidine.
- IV pantoprazole 80 mg in 100 ml dextrose saline is given slow IV as starting dose and later 40 mg in dextrose saline IV OD/BD. Slow continuous infusion of pantoprazole 40 mg in dextrose saline, 500 ml IV can also be given.
- Endoscopic cauterisation of small vessel with either gastroscopic bipolar cautery or through Laser or through heater probe or through haemoclips can be tried to stop the bleeding.
- Sclerotherapy—Ethanolamine oleate, distilled water. *Epinephrine injection* is also used *commonly.* Other agents used are absolute alcohol, polidocanol.
- Observation
    - Patients with bleeding from small vessels in the wall of DU will commonly respond to conservative treatment.
- Angiographic embolisation of gastroduodenal artery.


Ulcer crater
Endoscopic injection needle
-Vasoconstriction
-Tamponade
-Sclerosis
Visible vessel
Submucosa
Serosa

Fig. 20.48: Sclerosants like Ethanolamine oleate or distilled water are used through endoscopy to control bleeding ulcer. It causes tamponade, vasoconstriction, sclerosis. It is the best method to control the bleeding.

Indications for surgical treatment

- Inspite of conservative treatment condition of patient deteriorates
- Bleeding from gastroduodenal artery
- Recurrent bleeding
- Elderly patient
- If more than 4 units of blood required immediately

- *Surgery*
    - After laparotomy, pyloric channel and first part of the duodenum (gastroduodenum) is opened longitudinally, bleeder is identified. *Underruning of* the bleeding area with vicryl is done.
    - If the bleed is from gastroduodenal artery, then it has to be *ligated* to stop the bleeding. Opened gastroduodenum is closed by ***Finney's pyloroplasty.***
    - Truncal vagotomy may be done together, if the general condition of the patient is good.


Coeliac artery
Left. gastric artery
Right gastric artery
Gastroduodenal artery
Ligation
Bleeding DU
Underrunning

Fig. 20.49: Gastroduodenal artery ligation is required in case of severe massive upper GI duodenal ulcer bleed.


Gastroduodenal artery
Suture ligation
Ulcer
Stomach
Duodenum

Fig. 20.50: Underrunning of the bleeding duodenal ulcer at ulcer bed is done to control haemorrhage. After that duodenum is closed with Finney's pyloroplasty.

- *Further treatment*
  - During discharge, patient is advised to take antihelicobacter pylori (triple) therapy, proton pump inhibitors for 6-12 weeks (Omeprazole, or Lanzoprazole).
  - Healing of ulcer can be confirmed by doing a gastroscopy after 6-12 weeks.

Treatment schedule for bleeding duodenal ulcer-

- Treatment of shock
- Blood transfusion
- Stomach wash with—1 : 2,00,000 adrenaline saline
- IV ranitidine, famotidine, pantoprazole, omeprazole
- Endoscopic sclerotherapy using ethanolamine oleate or distilled water
- Endoscopic bipolar cauterisation, laser therapy, heater probe, haemoclips
- Angiographic embolisation of gastroduodenal artery
- Open surgery and underrunning of the bleeding ulcer bed
- Ligation of gastroduodenal artery and then Finney's pyloroplasty
- Proton pump inhibitors during discharge
- Follow up gastroscopy after 3 months

Sclerotherapy is the most popular endoscopic method used at present

BLEEDING GASTRIC ULCER

- It is similar to bleeding DU. Bleeding may be either from the ulcer bed or from the erosion of gastric vessels commonly but occasionally splenic vessels. They commonly present with severe haematemesis and shock.
- Bleeding is much more severe than bleeding DU.
- Surgery is the main treatment:
  After initial resuscitation, blood transfusion and a trial of conservative management, laparotomy is done. On laparotomy one of the following procedures is done.

  Underrunning of the ulcer bed.

  OR ligation of splenic vessels with splenectomy with or without partial gastrectomy and gastroduodenostomy.

  Postoperative management and follow-up is same like bleeding DU.

Treatment for bleeding gastric ulcer–

- Underrunning of the ulcer bed
- Partial gastrectomy with Billroth I anastomosis
- Vagotomy with antrectomy
- Occasionally splenic vessel ligation with splenectomy may be required

CAUSES FOR HAEMATEMESIS



Fig. 20.51: Gastroscopy showing carcinoma stomach which is bleeding. Note the slough and everted edge.



Fig. 20.52: Various causes of haematemesis.

- Chronic peptic ulcer (duodenal + gastric) (65%).
- Acute peptic ulcer.
- Acute erosive gastritis (Steroids, NSAIDs).
- Oesophageal varices.
- Mallory-Weiss syndrome (5-15%)
- Carcinoma stomach (5%)

Dream things that never were and make it true.

- Gastric polyps, lymphomas, leiomyomas.
- Portal gastropathy.
- Bleeding disorders.
- Pernicious anaemia.
- Thrombocytopenia.
- *Gastric antral vascular ectasia* is a rare endoscopically confirmed condition which shows segmented dilated vessel meshes in the antral mucosa (*water-melon/ tiger stripe stomach*). It is often associated with achlorohydria and hypergastrinaemia.
- Osler-Weber Rendu syndrome, aortoduodenal fistula, Crest syndrome are rare causes.
- ***Dieulafoy's disease*** (A gastricarterio venous malformation which is covered by apparently normal mucosa). It occurs in proximal stomach near OG junction (within 6 cm) along lesser curve (80% of cases). Bleeding often may be severe and torrential. Vasculitis or atheroma are absent in the vessel. Endoscopy and endoscopic therapy or excision of the lesion is required.

Management of Haematemesis

- *Evaluation of patient* by measuring BP, pulse, respiration looking for features of shock, oxygen saturation, investigating for Hb%, blood grouping, blood urea, serum creatinine, LFT, prothrombin time, platelet count, arterial blood gas analysis, gastroscopy.
- *Initial treatment* is central line insertion, fluid and blood replacement; catheterisation; IV PPI; nasogastric tube placement (controversial but now universally accepted); FFP, platelet transfusion if needed; gastroscopic sclerotherapy, banding, laser, haemoclip application; SB tube for varices; pharmacotherapy.
- *Further treatment* – critical care (ICU); antibiotics; treatment of complications like sepsis, DIC, ARDS.
- *Specific treatment* – open surgery for uncontrolled bleeding, ligation of gastroduodenal artery and under running of ulcer bed with pyloroplasty, gastrectomy, ligation of varices with devascularisation.
- *Definitive surgery* for underlying cause – shunt surgery; vagotomy and GJ; gastrectomy; TIPSS; splenectomy, etc.

COMPLICATIONS OF GASTRIC SURGERY

- Haemorrhage.
- Stomal obstruction.
- Biliary fistula.
- Injury to CBD.
- Duodenal blow out—on 4th postoperative day.
- Pancreatitis.
- Recurrent ulcer stomal ulcer.
- Gastrojejunocolic fistula.
- Dumping syndrome (Postcibal syndrome).
- Nutritional disturbances, diarrhoea.
- Pulmonary tuberculosis.
- Carcinoma in gastric remnant (after 10-15 years).
- Gallstone formation.
- Alkaline gastritis.
- Afferent and efferent loop syndrome.
- Afferent loop obstruction—*common.*
- Efferent loop obstruction.

Stomal obstruction after gastric surgeries is due to–

- Mucosal oedema—usually subsides eventually
- Retrograde jejuno-gastric intussusception
- Hypertrophied stomal mucosa causing ball-valve mechanism
- Efferent loop obstruction
- Gastric atony eventhough there is wide patent stoma causing apparent stomal obstruction

Nutritional deficiencies following gastrectomy

Iron deficiency anaemia	40%
Megaloblastic anaemia (after 5 years)	25%
(100µg B_{12} is given IM weekly, later monthly)	
Vit. B deficiency	10%
Calcium deficiency	40%
Calcium deficiency with bone changes (after 5 years)	5%

DUODENAL BLOW OUT

- It is a very serious complication of Billroth II gastrectomy, occurs usually on 4-5th day after surgery.
- Here contents in the afferent loop are not having free flow which in turn increases the pressure in the duodenal 'C' loop leading to giving way of the closed duodenal stump.
- It is due to improper closure of duodenal stump, oedematous inflamed duodenum, afferent loop block, distal obstruction, ischaemia of least vascular duodenum and sepsis.

Features

- Sudden, severe pain abdomen postoperatively with features of shock.
- Forming a duodenal fistula through the drain placed.
- May cause peritonitis.
- Severe electrolyte imbalance.
- Features of biliary peritonitis, septicaemia.
- Skin excoriation and its problems.



Fig. 20.53: Duodenal blow out after Billroth II anastomosis usually occurs 4 days after the surgery. It is often life threatening condition.

Treatment

- *Conservative therapy* with nasogastric aspiration, IV fluids, TPN, antibiotics. Usually, patient will recover in 40-60 days.
- *Surgery is indicated* when there is peritonitis, fistula not responding, when there is distal obstruction.
- *Surgeries are*—-afferent and efferent loop connection, relieving the obstruction distally, serosal patch over the duodenal stump after excision of the fistula, creating a controlled fistula after placing a tube in to the duodenum.

Duodenal fistula

Causes
- Due to duodenal blow out – ischaemia, afferent loop obstruction, sepsis
- After closure of perforated DU
- Injury to duodenum by trauma, surgeries like hemicolectomy, renal surgeries, pancreatic surgeries, etc

Types
- High > 500 ml / 24 hours
- Low < 500 ml

Features
- Pain abdomen
- Bile leak through the drain site or fistula track
- Skin excoriation
- Electrolyte imbalance
- Malnutrition, anaemia
- Recurrent infection

Investigations
- Electrolyte estimation, haematocrit
- CT fistulogram

Treatment
- TPN, feeding through jejunostomy
- Management of anaemia, electrolytes
- Blood transfusion
- Antibiotics whenever sepsis is suspected
- Care of skin – zinc oxide cream application, controlled fistula by placing a Foley's catheter into the fistula track
- Usually responds well by conservative therapy in 8-12 weeks
- If not improved then surgery is needed – anastomosis between afferent and efferent loops (jejuno jejunostomy); serosal patch techniques; surgical closure of fistula, Roux-en-Y patch over fistula

RECURRENT ULCER

It is a wide terminology which includes stomal ulcers, recurrence of ulcer in the original ulcer site or different parts of stomach/duodenum or jejunum after a therapeutic surgical procedure. Stomal ulcer can occur in gastrojejunostomy stoma or in gastroduodenostomy stoma. GJ stomal ulcer per se can occur after only gastrojejunostomy or after partial gastrectomy with Billroth II anastomosis. Recurrent ulcer at the original site is commonly referred to ulcer recurrence after HSV.

Recurrent ulcer is 3-7%. It may be after–
- Gastrojejunostomy.
- Billroth I or Billroth II anastomosis.

It may be –
- Gastrojejunostomy stomal ulcer
- Gastroduodenostomy stomal ulcer
- Jejunal ulcer
- Gastric ulcer
- Recurrent ulcer—10%

Causes

- Incomplete vagotomy.
- Zollinger-Ellison syndrome, gastrinomas.
- Alcohol, smoking.
- Hyperparathyroidism.

What we need is cup of understanding, barrel of love and an ocean of patience.



Fig. 20.54: Stomal ulcer after GJ may be due to incomplete vagotomy, Zollinger-Ellison syndrome.

- Gastrojejunostomy when done without vagotomy—40%.
- After HSV—10%.

Clinical Features

- Pain in the umbilical and left hypochondrium (severe, persistent).
- Back pain.
- Haematemesis.
- Anaemia, loss of weight.
- Features of obstruction – 10%.

Note: Stomal ulcer may complicate to gastrojejunocolic fistula, perforation, bleeding, obstruction, penetration.

Investigations

- Barium meal.
- Gastroscopy.
- Hollander's insulin test.
- Pentagastrin test.
- Gastrin level estimation.
- Serum calcium to rule hyperparathyroidism.
- *Visick grading* is used to assess the response to therapy to various procedures. (Grade 1, 2, 3, 4 and 5).

Treatment

- Complete the vagotomy.
- Undoing of G-J.
- Conversion into another procedure, Roux-en-Y procedure.
- Treat hypergastrinaemia, hyperparathyroidism.
- Eradication of *H. pylori* infection using triple regime for 2 weeks and then continuation of therapy using PPI for 3 months.
- Subtotal gastrectomy in resistant recurrent ulcer cases.

STOMAL ULCER

- It is the ulcer in anastomotic site of GJ / GD
- Overall incidence is 10% in 10 years after surgery
- It is common on jejunal side but can occur on gastric side or both sides or at junction

Causes

- After only gastrojejunostomy procedure – 40%
- After vagotomy and GJ – 5-7%
- After partial gastrectomy and gastroduodenostomy – Billroth I – 3%
- After partial gastrectomy and GJ – Billroth II – 3%
- Other causes like gastrinomas, hyperparathyroidism, incomplete vagotomy, smoking, alcohol

Features

- Pain and haematemesis/melaena is the main presentations
- Pain is persistent, severe over left upper abdomen often radiating to back
- Pain may be in the chest if it is ante-colic anastomosis
- Weight loss and features of obstruction can occur

Investigations

- Acid tests (Hollander's), gastroscopy, tests specific for the cause
- Serum gastrin/calcium assay

Complications

- Bleeding· Stomal obstruction
- Perforation
- Gastrojejunocolic fistula
- Nutritional deficiency

Treatment

- Completion vagotomy
- Subtotal gastrectomy / revision gastrectomy
- Roux-en-Y anastomosis
- Treat the cause

DUMPING SYNDROME (Post-cibal Syndrome)

It is common in *females*, seen after Billroth II surgery.

Types

1. *EARLY DUMPING SYNDROME:*
    - It is common and more severe type
    - Incidence is 10%
    - Vasomotor symptoms appear immediately after food, lasts for 30-40 minutes, aggravated by bulky food. It is relieved by lying down, aggravated by more food

Clinical features:

- Sweating, tachycardia, colicky pain and diarrhoea
- Hypotension and features of hypovolaemia

***Pathogenesis*:** It is a *primary disorder of carbohydrate metabolism* wherein initial transient hyperglycaemia prevents further absorption of glucose, which in turn draws fluid from the bowel wall by high osmolarity resulting in increased intestinal activity, resulting in diarrhoea and fall in blood volume

Treatment: Small, dry, more frequent food, with avoidance of carbohydrates. Octreotide 100 µg given subcutaneously before meals is found to be beneficial

Surgical treatment:

1. Conversion of Billroth II to Billroth I
2. Interposition of reversed jejunal loop

Early dumping syndrome can last for long time (many years)

2. *LATE DUMPING SYNDROME*
   - It is of less severe type
   - Incidence is 5%
   - It usually occurs 2 hours after meal
   - It is relieved by glucose and aggravated by exercise

Pathogenesis: Due to initial hyperglycaemia insulin secretion is stimulated which inturn leads to hypoglycaemia

Clinical features:

- Tremor, fainting, nausea
- Features of hypoglycaemia

Treatment: Symptoms are less severe and so treated conservatively, by giving glucose and food

GASTROJEJUNOCOLIC FISTULA

It is a complication of gastrojejunal ulcer (stomal ulcer), wherein ulcer penetrates and erodes into the transverse colon leading to gastrojejunocolic fistula, a dreaded complication.

Clinical Features

- *Sudden onset of severe diarrhoea* after every meal with past history of GJ done and past history of gastrojejunal ulcer.
- Foul gas eructation.
- Dehydration.
- Rapid loss of weight, anaemia, cachexia, hypoproteinaemia (bacteria from colon enters the jejunum disrupting the absorptive mechanism).
- Steatorrhoea.
- Rarely faecal vomiting.



Fig. 20.55: Gastrojejunocolic fistula.

Investigation

Barium enema (not barium meal).

Treatment

- IV fluids.
- Total parenteral nutrition (TPN).
- Blood transfusions.
- Antibiotics.
- Rehydration, electrolyte management.
- Surgery: Resection of involved *stomach, jejunum, colon* has to be done and continuity has to be maintained (*Triple Resection*). Surgery is the only treatment. ***It has got high mortality***.



Fig. 20.56: Resection of the Gastrojejunocolic fistula (removal of involved parts olf the stomach, jejunum and colon – triple resection) with maintaining the continuity.

TRICHOBEZOAR

- It is a hair-ball commonly seen in stomach of *females with psychiatric illness,* who swallow hair regularly.
- It forms a ball like mass occupying the full stomach.

Carcinoma stomach is the commonest cause of Krukenberg's tumour.



Fig. 20.57: CT scan showing bezoar.

Clinical Features

- Epigastric pain, early satiety.
- Haematemesis.
- Features of gastritis.
- Loss of appetite.
- Perforation.

Investigation

- Barium meal and endoscopy is confirmative.
- CT scan is very useful.

Treatment

- Gastrotomy and removal of hair ball.
- Psychiatric counselling.
- Enzymatic digestion and endoscopic breaking of the bezoars also tried.
- It can also be removed by laparoscopy.

Phytobezoar is due to solid ball formation in the stomach comprising plant fibres and seeds.

CHRONIC DUODENAL ILEUS (WILKIE'S SYNDROME)

- It is also called as *superior mesenteric artery (SMA) syndrome.*
- It is due to obstruction of the 3rd part of the duodenum due to decreased angle between SMA and aorta.
- It can be aggravated by plaster casts, lordosis, pancreatic tumour, enlarged lymph node in the 3rd part of duodenum (*Cast syndrome*).

Clinical Features

- Bilious vomiting.
- Upper abdominal fullness.
- Visible peristalsis.
- Dehydration.



Fig. 20.58: Wilkie's syndrome.

Differential Diagnosis

- Pyloric stenosis with gastric outlet obstruction.
- Annular pancreas.

Investigation

- Barium meal is diagnostic.
- CT scan abdomen.

Treatment

- Duodenojejunostomy.

Note: Gastrojejunostomy—Not done.



Fig. 20.59: Duodenojejunostomy, in case of chronic duodenal ileus.

ACUTE GASTRIC DILATATION

- It is an enormous acute dilatation of stomach with atonic gastric wall without peristalsis.
- Stomach distends enormously occupying most of the abdomen and pelvis causing sequestration of lot of fluid resulting in hypovolaemia.

Causes

- After major surgery (abdomen, neurosurgery).
- Trauma, burns.
- Retroperitoneal haematoma.
- Electrolyte imbalance.

Clinical Features

- Features of hypovolaemia and shock.



Fig. 20.60: Acute gastric dilatation showing dilated stomach occupying entire abdomen and also pelvis.

- Vomiting, hiccough. Vomits large quantity of brownish black fluid like *"the storm water of a peat-laden stream."* Vomitus when placed in a test tube and held in a strong light, myriads of small particles may be suspended in the fluid.
- Dilated stomach confirmed by ausculto percussion test.
- Positive succussion splash.
- Electrolyte imbalance is seen.

Investigations

Plain X-ray abdomen, serum electrolytes, U/S abdomen.

Treatment

- Conservative treatment is given initially.
  - Large amount of intravenous fluids.
  - Ryle's tube aspiration.
  - Electrolyte management, blood transfusion.
- The cause is treated.
- Rarely surgical decompression is required. Condition has got high mortality.

Complications

- Aspiration pneumonia *(Mendelson syndrome).*
- Severe hypovolaemia and electrolyte imbalance.

GASTRIC VOLVULUS

It is twist in the axis of the stomach.
Twist may be
- ***Organo-axial***—Common in elderly – horizontal.
- ***Mesenterico-axial***—Common in children – vertical.



Fig. 20.61: Types of gastric volvulus.

Pathology

- Here stomach twists upwards between oesophagogastric junction and pyloro-duodenal junction. Colon along with omentum also moves upwards initially.
- It is often associated with rolling hiatus hernia or diaphragmatic eventration.

Clinical Features

Borchardt's triad:
1. Acute epigastric pain
2. Violent ineffective vomiting
3. Inability to pass a nasogastric tube

Types

- Acute.
- Chronic-recurrent. It is common type.

Complications

- Perforation.
- Gangrene of the stomach.
- Bleeding.

Many very skillful operators are not good surgeons.— William J Mayo

Investigations

- Plain X-ray abdomen in erect posture.
- Barium meal X-ray.
- CT scan abdomen.

Treatment

- Untwisting of the volvulus and gastropexy by fixing the anterior wall of the stomach to anterior abdominal wall.
- Gastrojejunal fixation (gastrojejunostomy without a stoma).
- Gastrectomy when stomach is gangrenous.
- Treating hiatus hernia or eventration.
- Displacing colon downwards by dividing gastrocolic omentum—*Tanner's operation.*

GASTRIC POLYP

Types

1. Hyperplastic polyp – 75% common, minimal risk of malignancy.
2. Adenomatous polyp – Neoplastic in origin. Size > 2 cm is potentially malignant (25% chance).

Features

- *Hyperplastic polyp* is randomly distributed throughout the stomach. They are usually less than 2 cm in size, often multiple. Spontaneous regression can occur. Often it is associated with *H. pylori* infection.
- *Adenomatous polyp* is usually single. It is common in antrum. It can be sessile (common) or pedunculated. It is usually 2 cm or more (80%). It has got hyper chromatic nuclei arranged in a picker fence pattern. Size more than 2 cm has got high malignant potential.
- Inflammatory, hamartomatous and heterotrophic are other gastric polyps of negligible malignant potential.
- 50% are asymptomatic.
- Fundal polyps are associated with PPI therapy and familial polyposis.
- Gastric carcinoids arise from enterochromaffin like cells (ECL). They usually present as small polyps with pernicious anaemia.
- It may present with pain, haematemesis and gastric outlet obstruction. Gastroscopy is diagnostic.
- Endoscopy and resection is needed. If not possible open resection is done.
- Small polyp can be under regular surveillance by endoscopy.

MENETRIER'S DISEASE

- It is a condition with giant gastric mucosal folds (hypertrophic gastropathy) in the fundus and body of the stomach.
- Histologically, it shows hyperplasia, mucosal thickening and gastric gland atrophy.
- Hypoalbuminaemia, anaemia and hypochlorhydria is common.
- Antrum is not involved.
- There is over expression of transforming growth factor alpha (TGFα) peptide which binds to epidermal growth factor (EGF).

Clinical Features

- Epigastric pain, anaemia and weight loss.



Fig. 20.62: Gastric polyp in prepyloric region.



Fig. 20.63: Polyp in the duodenum first part.

Investigations

- Serum total proteins, albumin.
- Gastric function tests.
- Barium meal studies.

Menetrier's disease

- Giant folds in fundus and body
- Gastric gland atrophy
- Hypochlorhydria
- Hypoalbuminaemia
- It may turn into malignancy
- Antral sparing

Treatment

- Partial gastrectomy.

Menetrier's disease may turn into malignancy.

DUODENAL DIVERTICULA

Types

1. **Primary:**
   - Occurs in the 2nd or 3rd part of duodenum.
   - Are congenital in origin, with all the three layers of duodenum.
   - Are usually asymptomatic.
   - Diagnosed by endoscopy.
   - Treated if required – excision by endoscope or open method.
2. **Secondary:**
   - Commonest type.
   - Always of acquired type.
   - Occurs in the 1st part of duodenum.
   - Due to cicatrised chronic duodenal ulcer.
   - Barium meal X-ray shows *'tri-foliate duodenum'*.
   - Treatment of chronic duodenal ulcer with pyloric stenosis—Truncal vagotomy with posterior GJ.



Fig. 20.64: Primary and secondary diverticula of the duodenum.



Figs 20.65A and B: Barium meal picture showing trifoliate duodenum as secondary diverticulum due to chronic duodenal ulcer.

CARCINOMA STOMACH

> ***My kinsman, Antonio Bruno, retained the food he had eaten for too short a time, and then threw it up undigested…. His body wasted away through lack of nourishment till little more than skin and bone remained. At last he was brought to his death. The body was cut open for reasons of public welfare. It was found that the opening of his stomach had closed up and it had hardened…with the result that nothing could pass through to the organs beyond, and death inevitably followed.***
>
> —**Antonio Benivieni,** 1507

- *'It is the captain of men of death'*.
- It is more common *in Japan* – 70 per 1,00,000 population.
- It is more common in males.
- Decrease incidence in western world (Western Europe and US) – last four decades. But this decrease is confined to distal gastric cancers. Incidence of proximal gastric cancer is increasing. Carcinoma proximal stomach is not associated with *H. pylori* infection unlike cancers of body and distal stomach.

Risk Factors (Aetiology)

- Familial—10%. Napolean and many members of his family died of carcinoma stomach. *Familial gastric cancer* in associated with mutation of *e-cadherin gene* (90% risk). It causes hereditary diffuse gastric cancer. Relatives of such family show mutation of this gene. Whether prophylactic total gastrectomy is needed or not in these high risk individuals is a debate.
- HNPCC, Li-Fraumen syndrome.

Charm strikes the sight, but merit wins the soul.

- Gastric mucosa of people with blood group 'A' is more susceptible for carcinogens—diffuse type.
- Gastric polyps, adenomatous polyp > 2 cm.
- Pernicious anaemia—high risk 6 times.
- Gastric remnant—15 years after gastrectomy and GJ.



Fig. 20.66: Gastrectomy specimen showing ulcerative gastric carcinoma.

- Diet—High salt diet, food with more nitrosamines increases the risk. Smoked salmon fish increases the risk.
- Fruits and vegetables rich in vitamin 'C' protect from carcinoma stomach.
- Chronic gastritis (atrophic, autoimmune), intestinal metaplasia. Type A causes proximal gastric cancer. Type B causes distal gastric cancer.
- Gastric dysplasia.
- Smoking, alcohol.
- *Helicobacter pylori infection*—high risk (Cag A strain) 6 fold increase in incidence. It causes intestinal type of gastric cancer.
- Agammaglobulinaemia—high risk (2–5%).
- Chronic benign gastric ulcer.
- Giant hyperplasia of gastric mucosal folds (*Menetrier's disease).*
- Carcinoma in proximal stomach is common in young and upper socioeconomic group.
- Carcinoma in distal stomach is common in old and lower socioeconomic groups.
- In western countries, carcinoma stomach is more common in proximal, near O—G junction. Obesity, young individual, white people, smoking, alcohol intake, gastrooesophageal reflux, higher social status, high calorie diet and probably genetic factors are the causes for proximal gastric cancers. It is more aggressive, spreads early due to thin muscularis mucosa. It is often diagnosed late. Signet ring type is common. It carries poor prognosis. It needs oesophageal resection.
- In Asian countries, it is still common in distal stomach.
- In India, it is common in south India (4 times than North India).
- Epstein Barr virus, radiation exposure.
- Occupational - Rubber workers, coal workers.

Precursor Lesions of Carcinoma Stomach

- *Chronic atrophic gastritis* – It is the commonest precursor lesion mainly intestinal subtype. In Japan 95% of atrophic gastritis develop early gastric cancer. Incidence is higher in elderly and in those associated with *H. pylori* infection.
- *Adenomatous gastric polyps.*
- *Intestinal metaplasia* – Risk of carcinoma depends on extent of metaplasia in mucosa. *H. pylori* eradication is important here.

  Based on histological and biochemical nature, two types are found –
  - *Complete* – Glands are completely lined with goblet cells and intestinal absorptive cells indistinguishable histologically and biochemi-cally from their small bowel counterparts.
  - *Incomplete* – It contains columnar cells, goblet cells but without intestinal absorptive cells.

  It also can be –
  - *Type I* – Mature; goblet cells secret sialomucin.
  - *Type II* – Cells in different levels of dedifferentiation. Cells secrete sialomucin and an abnormal sialomucin (sulphomucin) – a small quantity.
  - *Type III* – Marked dedifferentiation of cells, secreting mainly sulphomucin.
- *Menetrier's disease.*
- *Benign gastric ulcer* – Here risk is 2–5%. But it is related to the size, extent and duration of the benign gastric ulcer. Giant gastric ulcer has got as high as 6–23% risk. Cancer developing in a preexisting benign gastric ulcer is called as *ulcer cancer.*
- *Stomach remnant (stump carcinoma)* – It can occur after Billroth II gastrojejunostomy (common) or vagotomy GJ. It takes around 15 years or more to develop cancer. Common site is close to the stoma. Atrophic gastritis – metaplasia – dysplasia and carcinoma develops. Altered acid level, duodenogastric bile refluxes are the pathogenesis which increases the peptic activity causing mucosal metaplasia and dysplasia. Earlier history of gastric surgery, recent history of loss of

appetite and decreased weight with often a palpable mass are the features. Liver secondaries, ascites may develop in late cases. Gastroscopy with biopsy and CT scan confirms the diagnosis. Treatment is gastrectomy with nodal clearance.

Aetiology for Gastric Cancer

Environmental/occupational /diet/habits

- Smoking/alcohol/obesity
- Low vegetables, diet with low vitamin A and C
- Consuming red meat, smoked salmon fish, cabbage, diet rich in nitrosamines, lead
- Viral infections like E B virus
- Occupational – rubber/coal workers
- Lower social status – distal cancers
- Higher social status – proximal cancers

Precancerous lesions –

- *H. pylori* infection, chronic gastritis
- Pernicious anaemia
- Intestinal metaplasia
- Adenomatous polyps more than 2 cm
- Agammaglobulinaemia
- Benign gastric ulcer
- Previous gastric surgery
- Menetrier's disease

Genetic and familial

- *E cadherin* gene mutation in diffuse cancers
- Mutation in APC gene for β-catenin in intestinal cancers – 50%
- Inactivation tumour suppressor gene p53 in 30% cases
- Loss of heterozygosity in the BCL2 gene, an inhibitor of apoptosis (intestinal type)
- Amplification/over expression of different growth factor receptors
- HNPCC - Carries 5-10% risk of gastric cancer
- Li Fraumen syndrome
- Blood group A
- First degree relative carries 3-6 folds increased risk of gastric cancer.
- Monozygotic twins carry more risk than dizygotic
- When both parents have gastric cancer, the siblings are at risk of diffuse proximal gastric cancer
- FAP – 10 folds more risk of gastric cancer
- Mutation of H-ras oncogene and over expression of c-erb B2 gene

Pathology

I. ***Gross types***:

Cauliflower type
Ulcerative type
Leather-bottle (Linitis-plastica)



Fig. 20.67: Endoscopic view of carcinoma of stomach.

II. ***Lauren's classification*** (DIO classification):

a. *Intestinal type (53%)*—Has got favourable prognosis. Polypoid and superficial types are intestinal varieties—Common in *H. pylori* induced. Gland formation and definite cellular architecture are the features. Synchronous/polypoid/superficial types are common.

b. *Diffuse type (33%)*—It has got poor prognosis. Common in blood group A, familial type, young people and females. It is usually poorly differentiated/signet type with early gastric wall penetration and both submucosal and subserosal lymphatic spread. Linitis plastica, ulcerative growth without glandular formation is common in this type.

c. *Others*—Unclassified (14%).

III. ***Depending on the depth of invasion***:

a. *Early gastric cancer* is defined as involvement of *mucosa and/or submucosa* only with or without involvement of lymph nodes – T1 + any N.

It is being classified as — ***(Japanese's classification)***

1. Protruded.
2. Superficial.
3. Excavated.

Hasty judgements are generally faulty ones.



Fig. 20.68: Borrmann's classification of the advanced gastric cancer.



Fig. 20.69: Japanese's classification for early gastric cancer.

It is –

- More common in Japan – 50% of gastric cancers treated are early gastric cancers. In USA – 20%.
- 10% of early gastric cancers will have nodal metastases. 3% in only mucosal lesions. 20% in submucosal lesions.
- Nodal spread in early gastric cancer depends on tumour size (> 2 cm) and differentiation.
- About 70 % are well-differentiated.
- Endoscopic mucosal resection (EMR) is possible in cancer of only mucosal lesions.
- Overall cure rate with adequate gastric resection and lymphadenectomy – 95%.

b. *Advanced gastric cancer* is defined as involvement of *muscularis and/or serosa* with or without involvement of lymph nodes.

It is classified as— ***(Borrmann's classification):***

I Single, polypoid carcinoma
II Ulcerated carcinoma with clear cut margin
III Ulcerated carcinoma without clear cut margin
IV Diffuse carcinoma—Linitis plastica.
V Unclassified. (See Fig. 20.68)

IV. ***Ming's classification***:
- Expanding.
- Infiltrative.

V. ***WHO histological classification of gastric cancer (microscopic)***
- Adenocarcinoma – commonest.
  - Papillary adenocarcinoma.
  - Tubular adenocarcinoma.
  - Mucinous adenocarcinoma.
  - Signet-ring carcinoma
- Adenosaquamous carcinoma.
- Squamous cell carcinoma – rare, when occurs it is common near OG junction.
- Small cell carcinoma.
- Undifferentiated carcinoma.
- Others.

VI. ***Proximal gastric adenocarcinoma (Siewert classification)***

Type 1: Carcinoma in Barrett's carcinoma esophagus/ true esophageal carcinoma extending to GE junction. Here total oesophagectomy with gastric pull through to neck is needed.

Type 2: Tumour within 2 cm of squamocolumnar junction. Here total gastrectomy with Roux-en-Y oesophagojejunostomy is needed.

Type 3: Tumour in subcardial region. Here total gastrectomy with Roux-en-Y oesophagojejunal anastomosis is done.



Figs 20.70A and B: Specimen of stomach showing thickening of wall of part of the stomach with loss of rugosity. Omentum, proximal parts are also seen. Thickening is extending into serosa.



Fig. 20.71: Outer look of carcinoma stomach extensively involving including serosa.



Fig. 20.72: Specimen of stomach showing large ulcerative deep lesion in the stomach with raised and everted edge. Loss of rugosity also observed.



Fig. 20.73: Specimen of stomach showing thickening of pylorus – feature of carcinoma stomach. In Asian countries, pylorus is the commonest site. In Western countries proximal stomach is the commonest site.

Common Site of Occurrence

- Prepyloric and pyloric region (65%). (commonest site)
- Body (25%).
- Fundus, O-G junction.

But now the incidence of growth in the upper part, near oesophago-gastric (O-G) junction is increasing.

Fire proves gold, adversity proves men.



Fig. 20.74: Ulcerative lesion with everted edge in the gastrojejunostomy stoma. It usually occurs only after 15 years of gastrojejunostomy surgery.

Spread (Biological behaviour)

- *Direct spread*:
  - To adjacent structures like pancreas, mesocolon, colon, liver can occur.



Figs 20.75A to C: Common sites of Ca stomach, (A) Pylorus, (B) Body, (C) Fundus.

- *Lymphatic spread:*
  - Spread occurs by permeation and embolisation through lymphatics to subpyloric, gastric, pancreati-coduodenal, splenic, coeliac, aortic, and later to left supraclavicular lymph nodes (Virchow's lymph node—*Troisier's sign).*
  - Retrograde spread to mesenteric nodes of small and large bowel can occur which signifies poor prognosis.

Zones of lymphatic drainage in stomach: Four zones.

Zone 1 lies in gastrocolic omentum along the right gastroepiploic vessels, draining pyloric portion of the greater curve to pyloric, coeliac and aortic lymph nodes.

Zone 2 lies in gastrocolic and gastrosplenic omentum along the left gastroepiploic vessels draining from upper half of greater curve to pancreaticosplenic and aortic lymph nodes.

Zone 3 is drainage from proximal two thirds of the stomach and the upper lesser curve along the left gastric artery. Zone 3 drains into perioesophageal lymph nodes.

Zone 4 is from distal portion of lesser curve and pylorus along hepatic artery into para-aortic nodes.

Lymph node groups

Group I Perigastric nodes
Group II Along the root of major vessels
Group III At the root of superior mesenteric artery and hepatoduodenal ligament
Group IV Distant lymph nodes

- *Blood spread*
  - It occurs to liver(commonest) causing multiple liver secondaries presenting as multiple, hard, nodules with umbilications due to central necrosis.
  - Later lungs and bones can get involved.
- *Transperitoneal spread*
  - It can cause peritoneal seedlings (leading to ascites) and also can cause *Krukenberg's tumours in ovary* in menstruating age group. (Commonly seen in colloid carcinoma of stomach).
  - Krukenberg's tumour can often occur without ascites. This is explained by possible spread through *retrograde lymphatic spread* from stomach to ovary. This is favoured by absence of ascites, no denudation/implantation/adhesions on the ovarian surface. Through lymphatic spread, even early gastric cancer can cause Krukenberg's tumour. In Japan, 17% of ovarian tumours is Krukenberg's secondaries from carcinoma of stomach. Occasionally Krukenberg's tumour can arise from carcinoma breast (lobular), other abdominal organs also.
  - Rectal secondaries (Blumer shelf), sister Mary Joseph umbilical secondaries are through transperitoneal spread.
  - Transperitoneal spread is best identified through laparoscopy and confirmed by laparoscopic biopsy.



Fig. 20.76: Krukenberg's tumour involving both ovaries from carcinoma of stomach. It is due to transcelomic spreador through peritoneal lymphatics or blood spread. It usually occurs during ovulation period.

TNM Staging of Carcinoma Stomach

T: Primary tumour
T_0: No evidence of primary tumour
Tis: Carcinoma *in situ*
T_1: Invasion of lamina propria or submucosa
T_2: Invasion of muscularis propria or subserosa
T_3: Penetration of serosa
T_4: Invasion of adjacent structures

N: Lymph Nodes
N_0: No regional lymph nodes
N_1: Involvement of perigastric nodes within 3 cm of tumour (1-6 nodes)
N_2: Involvement of perigastric nodes more than 3 cm or involvement of left gastric, splenic, coeliac or hepatic nodes (7-15 nodes)
N_3: > 15 nodes

M: Metastasis
M_0: No distant metastasis
M_1: Distant metastasis present

Leather-Bottle Stomach (Linitis Plastica) (7-10%)

It is an aggressive diffuse type of carcinoma stomach wherein there is enormous proliferation of fibrous tissue involving submucosa of stomach which is thickened, (*Mother of pearl appearance*) but mucosa looks and feels normal. It is type IV gastric carcinoma.

- *Clinical features:*
  - Loss of appetite and weight. Later mass may be palpable from the body of the stomach.



Fig. 20.77: Linitis plastica.



Fig. 20.78: Specimen showing features of linitis plastica – a diffuse type of carcinoma stomach mainly involving submucosa and deeper layer (mother of pearl appearance). It carries poor prognosis. It is type IV gastric carcinoma. It may be generalised or localised. It is also called as leather – bottle stomach.

- *Investigation:*
  - Small sized stomach in barium meal study.
  - Endosonography is also diagnostic.
- *Treatment:*
  - Total gastrectomy with oesophagojejunal anastomosis.
  - Prognosis is poor.
  - It may be occasionally localised linitis plastica in pyloric antrum which is better operable.

His heart cannot be pure whose tongue is not clean.

Colloid carcinoma of stomach:
- It is 6% common among all gastric cancers, wherein tumour cells contain *colloid* which is histologically typical
- It also signifies *poorer prognosis*.
- Common in women.

Presentations

- *Asymptomatic* in early gastric cancer or often in cancer of body of stomach.
- *Nonspecific symptoms*—indigestion/vague epi-gastric discomfort, constant nonradiating pain which is not related to food intake.
- *Specific* symptoms depend on the site of tumour—obstruction, dysphagia, mass etc.
- *Metastatic disease*—liver secondaries, ascites, secondaries in ovary, recto vesical pouch, umbilicus, supraclavicular nodes, lung and bone secondaries.
- *Unusual presentations*—Acanthosis nigricans, Irish nodes in the axilla.

Clinical Features

- Recent onset of loss of appetite and weight, early satiety, fatigue. Microcytic, hypochromic anaemia (iron deficiency) is common.
- Upper abdominal pain.
- Vomiting with features of gastric outlet obstruction i.e. (VGP +ve, +ve ausculto-percussion test, +ve succussion splash (to be checked with 4-6 hours empty stomach)).
- *Mass abdomen:* Mass in pylorus lies above the umbilicus, nodular, hard, with impaired resonance, mobile, moves with respiration, all border well made out.
- Dysphagia with mass in upper epigastrium.
- When it arises from the body of stomach, it may present as only mass abdomen.
- Along with jaundice, liver may be palpable with secondaries which are hard, nodular (50%) with umbilication.
- Ascites.
- +ve Troisier's sign.
- +ve recto vesical secondaries.(Blumer shelf) on per rectal examination.
- +ve Trousseau sign—migrating thrombophlebitis, also seen in carcinoma pancreas.
- Anaemia, cachexia.
- Haematemesis, melaena.
- Occasionally carcinoma stomach can present as *perforation* to begin with (4%).
- Rarely as secondaries in the liver with silent primary in stomach.
- Secondaries in umbilicus, as sister Joseph's nodules (spread through ligamentum teres).
- Cutaneous secondaries.
- Krukenberg tumours.

Differential Diagnosis

- Acid peptic disease; pyloric stenosis with gastric outlet obstruction.
- Gastritis.
- Pancreatic mass - carcinoma.
- Transverse colon mass – carcinoma.
- Advanced fixed stomach mass may mimic retroperitoneal or nodal mass.



Fig. 20.79: Barium meal showing irregular filling defect in the body of the stomach suggestive of carcinoma stomach.



Fig. 20.80: Barium meal showing irregular filling defect in the pylorus suggestive of carcinoma pylorus.



Fig. 20.81: Barium meal showing irregular filling defect in the body of the stomach due to carcinoma.



Figs 20.82A and B: Polypoid carcinoma stomach seen in barium meal picture and also through endoscopy.



Fig. 20.83: Ulcero-proliferative growth in the antrum—an endoscopic view.

Investigations

- Hb%, haematocrit.
- Barium meal (Irregular filling defect).
- Single contrast barium studies – sensitivity is 75%.
- Double contrast barium studies – sensitivity is 90-95% in the detection of gastric cancer, comparable to endoscopy.

Barium meal findings in carcinoma stomach:
- Irregular filling defect
- Loss of rugosity
- Delayed emptying
- Dilatation of stomach in carcinoma pylorus
- Decreased stomach capacity in linitis plastica
- Margin of the lesion projects outward from the ulcer / lesion into the gastric lumen – *Carmanns meniscus sign*

- Gastroscopy with biopsy–10 targeted biopsies.
- Endosonography: EUS is useful to detect the involvement of layers of the stomach, nodal status and to define whether tumour is early or advanced. All 5 layers are visualised as alternate hypo and hyperechogenic areas. It gives 90% accuracy for T staging and 80% of nodal staging.
- US abdomen to see liver secondaries, ascites, nodes, ovaries. It is not as sensitive as EUS and CT scan.
- Liver function tests and prothrombin time. Secondaries in liver can cause hepatic dysfunction and liver cell failure. Enlarged hepatic nodes can compress CBD and cause obstructive jaundice also.



Fig. 20.84: Endoscopic view of the growth in the pylorus.

Without human being this world would have been heaven. Production of noble human being was the Perfect Tragedy to this world !!



Fig. 20.85: Carcinoma stomach endoscopic view showing irregular tumour.



Fig. 20.86: Carcinoma stomach as seen through gastroscopy.

- Often FNAC from left supraclavicular lymph node when it is significantly palpable.
- Laparoscopy to stage disease.
- CT scan abdomen and CT thorax in proximal tumours to see size, extent, infiltration, LN status, secondaries and operability.



Fig. 20.87: CT scan showing carcinoma pylorus with luminal obstruction.



Fig. 20.88: CT scan showing primary tumour in the stomach with secondaries in the right lobe of the liver. Secondaries are commonly multiple; only occasionally it will be solitary.



Fig. 20.89: CT scan showing multiple secondaries in liver with primary in the stomach.

- *Tetracycline fluorescence test*—Gastric cancer cells take up tetracycline given orally which becomes yellow in colour. Under UV light it shows yellow fluorescence.
- CA 72—4 is important tumour marker to evaluate the relapse. CEA, CA 19-9, CA 12-5 are other markers.
- *Laparoscopy* to see peritoneal seedlings and to take peritoneal biopsy. Laparoscopy US is very sensitive to see nodes, liver metastases. It identifies unresectable/missed lesions. It allows nodal/peritoneal biopsy. It is more accurate than CT.
- Combined *PET*—CT scan is useful. It is to evaluate metabolic, physiologic and functional activity. It is mainly useful to identify recurrent gastric cancer.
- *Sentinel node biopsy*—99mTc colloid peritumoral injection during gastrectomy. It has got sensitivity-80%, specificity-100% but not widely used.

Treatment

Surgery is the treatment of choice for carcinoma stomach

1. If it is an early growth, as in case of pylorus, *lower radical gastrectomy* with proximal 5 cm clearance is done, along with removal of greater omentum, lesser omentum, all lymph nodes, spleen (to clear splenic lymph nodes), tail of pancreas (when required); and later Billroth II anastomosis.
2. In case of growth in the O-G junction or upper part of the stomach, *upper radical gastrectomy* is done along with removal of spleen, both omentum, lymph nodes; and later *oesophagogastric* anastomosis.
3. In case of growth in the body or *linitis plastica, total gastrectomy (radical) with* oesophagojejunal anastomosis is done.



Figs 20.90A to C: Gastrectomies for Ca stomach (A) Lower radical gastrectomy (B) upper radical gastrectomy (C) total radical gastrectomy.

Presently newer staging for dissection is practiced in Japan – D1, D2, D3, D4 depending on levels of lymph nodes cleared ('D' for dissection). D1 or D2 dissections are commonly done.

- **D1** is done when nodes are N_0. It is removal of nodes along the lesser and greater curves and pylorus. (Group I: stations 3-6).
- **D2** is done when nodes are N_1. Here nodes like left gastric/common hepatic/splenic/retropancreatic are removed. Splenic nodes can be cleared with or without splenectomy along with removal of tail of pancreas. Here node stations 1-11 are removed. Stations 12-18 are not removed. Average 27 nodes are removed.
- **D3** is done when nodes are N_2. Nodes removed for clearance are para-aortic, hepatoduodenal, nodes along mesentery, middle colic (1-16 stations). Average 43 nodes are removed.
- **D4** is *not commonly advocated*. It is removal of stations 1-18.

D1—Involvement of group I lymph nodes
D2—Involvement of group I and II lymph nodes
D3—Involvement of group I, II and III lymph nodes
D4—Involvement of group I, II, III and para-aortic nodes

Note: All lymph nodes are numbered differently as 'stations' or 'echelons'.

Lymph node stations in gastric carcinoma (Japan) – 18 stations are there

1. Right cardiac
2. Left cardiac
3. Nodes along the lesser curvature
4. Nodes along the greater curvature
    a. Along short gastric vessels – 4sa
    b. Along left gastroepiploic vessels – 4sb
    c. Along right gastroepiploic vessels – 4sd
5. Suprapyloric nodes
6. Subpyloric nodes
7. Along left gastric artery
8. Along common hepatic artery
9. Along celiac axis
10. At splenic hilum
11. Along splenic artery
12. At hepatoduodenal ligament
13. Retroduodenal lymph nodes
14. At root of mesentery
15. Around middle colic artery
16. Paraaortic nodes
17. Around lower oesophagus
18. Supradiaphragmatic

First tier nodes – Nodes within 3 cm from primary tumour (stations 1-6)

Second tier nodes – Nodes in main and intermediate arterial trunk (stations 7-11).

Third tier nodes – Nodes at stations 12-18 (para-aortic and above)

Note: 15 lymph nodes must be removed for adequate staging of nodes

Most intelligent animal is human being, but he happened to be the most cruel animal also.

4. *Endoscopic mucosal resection (EMR)* is practiced in Japan in early gastric cancer. Tumour less than 2 cm, elevated, well-differentiated tumours without nodal disease is the ideal selection for EMR. Proper regular endoscopic surveillance is essential in these patients after EMR.

Adjuvant Therapy

Chemotherapy:

- Mitomycin 10 mg IV single dose in monthly cycles.
- 5 Fluorouracil, 250 to 500 mg IV in 5% dextrose daily for 5 days.
- Cisplatin and epirubicin, adriamycin, oxalilatin, capecitabine are other drugs used at present. (*FAM regime* is 5-fluorouracil, adriamycin, mitomycin C).
- Chemotherapy is also used as palliation in inoperable cases / metastatic cases whether surgical palliation (if obstruction or bleeding is present) is needed or not
- Neoadjuvant chemotherapy to downstage the tumour is also used to make it operable later.
- Instillation of mitomycin C impregnated charcoal intraperitoneally is done to control lymphatic disease (Japan). It specifically kills the malignant cells in lymphatics and lymph nodes in the abdomen.

Note: *No role for radiotherapy at present.* Many radiosensitive structures in the gastric bed prevents tumour to have effective RT. RT is used as palliative method for painful bone secondaries.



Fig. 20.91: Devine's exclusion procedure. Here inoperable pyloric tumour is left and excluded. Proximal stomach is transected and used for Billroth II like gastrojejunostomy.

Signs of inoperability

- *Adherent to pancreas or colon or mesocolon*
- *Ascites*
- *Para-aortic lymph nodes*
- *Secondaries in liver*
- ***Palpable mass is incurable but can be resectable surgically***
- Blumer shelf
- Left supraclavicular nodes
- Sister Mary Joseph nodule
- Irish node (Left axillary lymph node secondaries)



Fig. 20.92: Carcinoma stomach resected specimen.

Management of gastric carcinoma

- *Early growth in pylorus* – Lower radical gastrectomy with removal of tumour, proximal 5 cm clearance, nodal clearance, greater and lesser omentum, distal pancreas and spleen (now not regularly removed; it is removed to clear splenic nodes – one of the node stations) and Billroth II anastomosis or Roux-en-Y anastomosis is done. Postoperatively adjuvant chemotherapy should be given – 5 fluorouracil, mitomycin, epirubicin, cisplatin, oxalilatin, capecitabine.
- *D1 or D2 nodal dissection* should be done for adequate clearance in curative surgery.
- *Growth in body, proximal growth, diffuse carcinoma and generalised linitis plastica* are the indications for total radical gastrectomy with oesophagojejunal anastomosis.
- Neoadjuvant chemotherapy in advanced gastric cancer prior to surgery and later gastrectomy.

- Instillation of mitomycin C impregnated charcoal intraperitoneally to control lymphatic disease (Japan).
- Palliative procedures like *palliative partial gastrectomy*, anterior gastrojejunostomy, Devine's exclusion procedure, luminal stenting in proximal inoperable growths, chemotherapy are used in inoperable cases.
- In early carcinoma proper lymph nodal clearance is important.

Palliative Treatment

- To palliate pain
- To palliate vomiting
- When there is bleeding
- To improve appetite

Partial gastrectomy(palliative) is the best method

Other Palliative Procedures

- Palliative anterior gastrojejunostomy with jejuno-jejunostomy.
- *Devine's exclusion procedure* wherein instead of removal of tumour, it is excluded with Billroth II anastomosis.
- For unresectable growth in upper part of the stomach, palliation can be attained by inserting tubes through the oesophagus to the stomach like Mousseau-Barbin tube, Celestin tube (like in carcinoma oesophagus). Endoscopic stenting can also be tried.
- Palliative chemotherapy is used in advanced stage.
- RT and analgesia like morphine is used to relieve pain.
- Surgery / endotherapy is used to relieve obstruction. Palliative partial gastrectomy (limited local resection), anterior GJ, laser, stenting are different options.
- Surgery (partial gastrectomy) or endotherapy is required in bleeding.
- Palliation for ascites is difficult even though repeated tapping and chemotherapy is done.

Palliative procedures for carcinoma stomach–

- *Palliative partial gastrectomy is the best palliation*
- Palliative anterior gastrojejunostomy with jejuno-jejunostomy
- Devine's exclusion procedure
- M-B tube/Celestin tube insertion for proximal stomach growths
- Endoscopic stenting/dilatation
- Laser recanalisation
- Palliative chemotherapy—FAM regime



Fig. 20.93: Anterior gastrojejunostomy is one of the palliative procedures used in case of inoperable carcinoma stomach. It is anterior, antecolic GJ.

Prognosis

- In early gastric cancer which has undergone good surgical resection, 5 year survival rate is 70-90% in Japan. In India, 5 year survival rate is 20%.
- In advanced gastric cancer it reduces to 20-25% in Japan. In other countries it is still worser.
- Overall prognosis is worse in carcinoma stomach.
- When serosa is not involved 5 year survival is 50%. When serosa is involved it is 20%.
- Nodal spread is a bad prognostic factor.
- Involvement of more than 4 nodes carry poor prognosis.
- In Japan, prognosis is better due to early diagnosis and better technical and staging approach.
- Early gastric cancer has got better prognosis.
- Intestinal type has better prognosis than diffuse type.
- Size of the tumour (2 cm); tumour depth; and histological type and grading.

Prognostic factors

- Early or advanced
- Histological grading
- Staging
- Gross types
- Lymph node status
- Liver secondaries
- Serosal involvement—an important factor.

Goodness is the permanent investment.

- Intestinal type—got better prognosis than diffuse type
- Ascites.
- Response to treatment

Note:

- Recurrence rate is very high in first 3 years after therapy.
- If primary tumour can be removed surgically, it is called as *resectable tumour*. Resectability can be for palliation or along with radical surgery for cure.
- *Operable tumour* means radical gastrectomy with (amenable for) nodal clearance.
- *Inoperable tumour* means not amenable for radical surgery.
- Inoperable tumour can be resectable for palliation.
- **R_0** is resection with complete clearance – no *residual disease*. **R_1** is resection but with microscopic residual tumour. **R_2** is resection with macroscopic residual tumour, **R_3** is unresectable.
- D1 and D2 dissections are different for proximal and distal tumours.
- In early gastric cancers, laparoscopic endoluminal transgastric mucosal resection of the lesion is under trial now.
- Adjuvant chemoradiation (RT with 5FU as radiosensitiser) is also under trial for proximal tumour, undifferentiated high grade tumour.
- Antrectomy is also called as *hemigastrectomy*. Removal of 60-75% stomach is called as *partial gastrectomy*. Removal of more than 80% of stomach is called as *subtotal gastrectomy*.
- Perforation in gastric cancer has got high mortality.

GASTRIC LYMPHOMA

There are two types of gastric lymphomas.

- Primary.
- Secondary.

PRIMARY GASTRIC LYMPHOMA

- Primary gastric lymphoma is commonest one among GI primary lymphomas.
- It is second common malignant neoplasm of the stomach (5% of gastric malignancies).
- It is common in elderly men and common in the antrum of the stomach.
- It can be infiltrative, ulcerative, nodular, polypoid or combined.
- Gastric lymphomas are commonly of non-Hodgkin's type (NHL—B cell type 98%).
- It is arising from B cells – derived from mucosal associated lymphoid tissue (MALT). So often called as MALTOMA
- Diffuse mucosal thickening which eventually ulcerates – is the pathology.
- Disease remains in the stomach for long time and later spreads to liver and other lymph nodes.
- Association of primary gastric lymphoma with *H. pylori* is well-established. Normal gastric mucosa does not contain lymphocytes but mucosa with *H. pylori* infection contains lymphocytes.
- Usually disease is localised to stomach without any other lymph nodes in the abdomen or mediastinum with normal liver, spleen, bone marrow and total count.
- It is basically a localised disease of stomach to begin with but later to have systemic spread.

Clinical Features

- Pain abdomen, melaena and mass abdomen which is smooth and firm.
- Loss of weight, loss of appetite.

Gastric lymphoma is associated with–

- Wiskott Aldrich syndrome
- Klinfelter syndrome
- HIV, *H. Pylori* (75%)
- Ataxia Telangiectasia
- SLE
- Chronic gastritis
- MALT

Complications

- Obstruction.
- Perforation.
- Bleeding.
- Spread to other lymph nodes and liver—only late event.

Investigations



Fig. 20.94: Gastric lymphoma, endoscopic view. It can be primary or secondary. Secondary is common. Primary occurs in stomach and other lymphatic system is involved very late. Gastrectomy is the treatment with chemotherapy.

- Gastroscopy and biopsy.
- Endosonography.
- Peripheral smear, bone marrow aspiration.
- CT abdomen and CT chest and mediastinum.

Treatment

- Radical subtotal gastrectomy is done in primary gastric lymphoma at antrum. Radical totals gastrectomy is done in primary lymphoma of proximal stomach.
- *Antihelicobacter pylori* therapy. Early primary gastric lymphoma may regress by triple regime.
- Chemotherapy as adjuvant. Drugs are same as used for NHL.

SECONDARY GASTRIC LYMPHOMA

- It is commonest type of lymphoma occurring in stomach. It differs from primary in many aspects.
- Here mainly systemic lymph nodes are involved first and the disease begins in lymph nodes at different regions, later to occur in stomach.
- Peripheral smear shows lymphocytosis; bone marrow shows changes; CT abdomen and chest shows multiple nodal enlargement.
- It is basically a systemic disease extending to stomach.
- Perforation and bleeding are the complications.
- Treatment is mainly chemotherapy – CHOP/ABVD/MOPP/BACOP and other regimes.
- Surgery is not done unless any local complications occur.

GASTRIC SARCOMAS

Note: Previously named leiomyoma and leiomyosarcomas are now classified as GIST. This older terminology is discussed here. Presently it should be considered as GIST.

- Stomach is the commonest site of GI sarcoma.
- Leiomyosarcoma is the commonest type of gastric sarcoma. Other type is malignant leiomyoblastoma.
- Leiomyosarcoma is common in proximal stomach.
- It attains enormous size with rubbery consistency.
- Mainly spreads through the blood to the liver.

Clinical Features

- Pain, vomiting, anorexia.
- Mass in upper abdomen.

Complication

- GI bleeding.

Investigations

- U/S abdomen and CT scan.
- Gastroscopy is useful in less than 50% of cases.

Treatment

- Subtotal gastrectomy.
- Chemotherapy.

Leiomyosarcoma has got better prognosis compared to adenocarcinoma and lymphoma of stomach.



Fig. 20.95: Gastric sarcomas.

Note: Previously named leiomyoma and leiomyosarcomas are now classified as GIST. This older terminology is discussed here. Presently it should be considered as GIST.

GASTROINTESTINAL STROMAL TUMOURS (GIST)

- It is a rare tumour of GI tract – 0.2% of all GI tumours.
- But it is the most common nonepithelial tumour of the gastrointestinal tract. *Stomach is the commonest site* of all GISTs – 50%; 25% of all GISTS are from small bowel; rectum – 15%; colon – 10%.
- Equal in both sexes and common in 50-70 years age group.
- GIST arises from interstitial cell of Cajal (pacemaker cell which intercalates between smooth muscle cells and intramural neurons). Mutation of tyrosine kinase and platelet derived growth factor alpha (PDGFα) are the newer pathogenetic theories.
- GIST is classified as very low risk (2 cm); low risk (2-5 cm); intermediate risk (5-10 cm) and high risk (> 10 cm) based on *tumour size* and *mitotic activity* of cells.
- 95% of GISTS express c-kit – CD117 mutations – a specific molecular marker.

Success is the better way of dealing with failures.



Figs 20.96A and B: Barium meal X-ray showing Gastric teratoma presenting as a large mass lesion compressing gastric lumen. Inset shows CT picture also. Operated specimen is also shown.



Fig. 20.97: Gastric leiomyosarcoma near the fundus – endoscopic view. It is now classified under GIST.

- Abdominal pain; weight loss; *GI bleed* (commonest presentation) and large mass abdomen are typical. Mass is extraluminal as it is of submucosal origin but expands and compresses the mucosa. 50% of GIST can present as metastatic disease to liver and peritoneum (ascites).
- GIST's almost *never* metastasise to regional lymph nodes.
- ***Investigation***:
  - Mainly CT scan.
  - Tumour / molecular marker to differentiate it from sarcomas (immunohistochemistry).
  - Endosonography guided biopsy/guided FNAC are important to get histological confirmation.
  - 18 FDG PET scan is very useful adjunct to CT but reserved for difficult/equivocal cases.
- ***Treatment***:
  - Surgical resection of the tumour with part of the adjacent bowel.
  - *Imatinib mesylate* – a specific *oral* drug (year 2000) that inactivates tyrosine kinase kit and so prevents phosphorylation of the receptor and proliferation of tumour is very much beneficial in advanced cases. Now it is also used if tumour size is more than 10 cm; in intraperitoneal rupture/ spillage; haemorrhage in GIST; multifocal occurrence. Duration of Imatinib is usually one year.
  - Newer drug – *SU11248* inhibits tyrosine kinase receptor as well as blocks PDGFRA. Another newer derivative – *sunitinib* is used in imatinib refractory cases.
- ***Prognostic factors***:
  - Size of GIST more than 5 cm.
  - High mitotic activity (> 10 mitoses per high power field).
  - Liver spread.
  - KIT exon 9 mutation which is more aggressive than KIT exon 11 mutations – carries poor prognosis.

PYLOROPLASTY

Indications

- Bleeding duodenal ulcer.
- As a drainage procedure after vagotomy in uncomplicated DU which is not responding to medical line of treatment.
- As a part of procedure like Ivor-Lewis operation and Siguira—Futagawa operation.

Contraindications

- Duodenal ulcer with cicatrisation and scarring.

Types

- ***Finney's pyloroplasty.***
- ***Heineke-Mikulicz pyloroplasty.***

Complications

Duodenal leak—very dangerous one.
Later reflux.



Figs 20.98A and B: Types of pyloroplasty. (A) Finney's pyloroplasty, (B) Heineke-Mikulicz pyloroplasty.

GASTROSTOMY

- It is the procedure wherein a tube is passed into the stomach per abdominally for the purpose of enteral feeding.
- It can be *temporary or permanent.*

Types

A. *Serous lined*—for temporary gastrostomy.
B. *Mucosa lined*—for permanent one.



Figs 20.99A and B: Types of gastrostomy. (A) Temporary gastrostomy, and (B) Permanent gastrostomy.

After minilaparotomy, gastrotomy is done. Foley's or Malecot's catheter is placed in the stomach. It is fixed to parietal peritoneum through two circular purse string sutures.

Other Types

- Stamm's temporary gastrostomy.
- Kader-senn temporary gastrostomy.
- Janeway's permanent gastrostomy.
- *Endoscopic percutaneous gastrostomy*—becoming popular (PEG).



Figs 20.100A to C: Percutaneous endoscopic gastrostomy (PEG). It is easier and acceptable method and less invasive.

> *The remedy for injuries is not to remember them.*

Indications

- Oesophageal strictures.
- Any conditions where tube feeding is required for more than 4 weeks (e.g., burns, severe sepsis).
- Major neck surgeries.

Contraindications

- Previous gastrectomy.
- Gastric diseases with impaired gastric emptying.
- Intestinal obstruction.

Complications

- Infection.
- Trauma to other organ, e.g. colon.
- Leak from gastrostomy site.
- Aspiration pneumonia.
- Blockage.

GASTRECTOMY

Types

1. *Billroth I* is done for benign condition. Here along with partial gastrectomy, gastroduodenostomy is done.
2. *Billroth II* is done for carcinoma stomach. After partial gastrectomy, gastrojejunostomy is done and duodenal stump is closed.
3. *Lower radical gastrectomy* is done in early carcinoma pylorus. Here along with the growth and proximal 5 cm of stomach, omentum, lymph nodes, spleen with tail of pancreas are removed and Billroth II anastomosis is done.
4. In growth of upper part or O-G junction, *upper radical gastrectomy* is done along with *oesophago-gastric anastomosis*.
5. In some cases like linitis plastica, *total gastrectomy* along with *oesophagojejunal anastomosis is* done.



Figs 20.101A and B: Types of gastrectomy. (A) Billroth I anastomosis and (B) Billroth II anastomosis.

Indications

- Chronic benign gastric ulcer.
- Benign tumours of stomach (Leiomyoma).
- Carcinoma stomach.
- Stomal ulcer.
- Bleeding ulcer.
- Leimyosarcoma, gastric lymphoma.
- Menetrier's disease.


Subtotal gastrectomy (80% or above removed)
Partial gastrectomy (65-75% removed)
Antrectomy (hemigastrectomy)

Fig. 20.102: Different types of gastrectomy. Subtotal – more than 80% of stomach is removed; partial – 60-75% removed.

Complications

- Bleeding.
- Bile leak.
- Duodenal blow out.
- Gastric fistula.
- Dumping syndrome.
- Anaemia.

GASTROJEJUNOSTOMY (GJ)

Types

1. Anterior GJ.
2. Posterior GJ.

Anterior gastrojejunostomy is done as a palliative procedure in case of advanced inoperable (adherent posteriorly) carcinoma pylorus to palliate vomiting. It is anastomosis between jejunum and anterior surface of stomach, in front of transverse colon (antecolic).

Posterior GJ is done along with truncal vagotomy, in pyloric stenosis due to chronic duodenal ulcer. *It is posterior, vertical, retrocolic, short loop, isoperistaltic. (of Mayo*).

GJ is also done as part of the Billroth II gastrectomy.



Fig. 20.103: Gastrojejunostomy stoma veiw on endoscopy.

Problems with GJ

- Stomal obstruction.
- Afferent or efferent loop obstruction.
- Dumping syndrome.
- Duodenal blow out.
- Retrograde intussusception.
- Reflux gastritis.

RETROGRADE JEJUNO GASTRIC INTUSSUSCEPTION

- It is a rare entity occurs after gastrojejunostomy.
- It can occur immediately, in weeks or in months.
- Presents with *pain* above and left of the umbilicus, *haematemesis,* firm, tender *mass* above and towards the left side. Patient becomes better in erect posture.
- Condition causes stomal obstruction.
- It is treated by open reduction of the intussusception with anchoring stitch to the bowel or enteroanastomosis.

VAGOTOMY

> ***In an inquiry which I had formerly instituted, respecting the functions of the stomach, I divided these nerves (the vagi) in the neck of a dog, for the purpose of ascertaining the influence which they possess on the secretion of the gastric juice…. We may conclude that the suppression of the secretions…sufficiently demonstrate, that the secretions of the stomach and intestines are very much under the control of the nervous system.***
>
> **—Benjamin Collins Brodie,** 1814

Types

1. ***Truncal vagotomy*** along with GJ as drainage procedure, is done in case of pyloric stenosis due to chronic DU.

   In uncomplicated DU, with failure of medical treatment and when HSV can not be done, then truncal vagotomy with pyloroplasty is done.
2. ***HSV (Highly selective vagotomy)*** or ***Parietal cell vagotomy or Super selective vagotomy*** is done in case of uncomplicated DU where medical treatment fails. Here only fibres entering the stomach is divided both anteriorly as well as posteriorly. Nerve of Latarjet is retained to supply antrum and so *no drainage procedure is required* (Amdrup). *It has got 10% recurrence rate.*
3. ***Selective vagotomy*** is at present not done often. Here along with a drainage procedure, either GJ or pyloroplasty,vagotomy is done with retaining of coeliac and hepatic branches. It has got 10% recurrence rate.



Figs 20.104A to C: Types of Vagotomy. (A) Highly selective vagotomy, (B) Selective vagotomy with pyloroplasty, (C) Truncal vagotomy with gastrojejunostomy.

Complications of vagotomy

Intraoperative

Injury to spleen/oesophagus/liver/pancreas/thoracic duct/stomach

Bleeding from phrenic veins/gastric vessels/perioesophageal vessels

Pneumothorax

Oesophago gastric disconnection

Early postoperative

Gastric atony

Lesser curve necrosis in HSV

Transient dysphagia

Late complications

- Vagotomy diarrhoea - 20%
  - – Commonest complication of vagotomy
  - – Gastric stasis
  - – Hypoacidity with fermentation with bacterial overgrowth causing enteritis
  - – Alteration in intestinal villi and enzyme content, altered small bowel motility due denervation
  - – Altered biliary and pancreatic exocrine function
  - – Cholestyramine 4 gram tid/reverse jejunal loop is the treatment for intractable case
- Reflux oesophagitis
- Oesophageal stricture
- Gallstones – due to bile stasis and gastric atony – 15%

Pleasure in the job puts perfection in the work.

Self-asssessment Questions

- Lymphatic drainage of the stomach.
- Insulin test.
- Gastrin.
- Barium meal.
- Gastroscopy.
- *Helicobacter pylori.*
- Congenital pyloric stenosis.
- Ramstedt's operation.
- Complications of duodenal ulcer.
- Proton pump inhibitors.
- Ranitidine.
- Complications of duodenal ulcer.
- Perforated duodenal ulcer.
- Perforated gastric ulcer.
- Curling's ulcer.
- Cushing's ulcer.
- Management of gastric ulcer.
- Complications of gastric ulcer.
- Tea-pot deformity.
- Hour glass deformity.
- Pyloric stenosis.
- Gastric outlet obstruction.
- Radiological features in gastric outlet obstruction.
- Stomal ulcer.
- Bleeding duodenal ulcer.
- Bleeding gastric ulcer.
- Causes for haematemesis.
- Complications of gastric surgery.
- Dumping syndrome.
- Gastrojejunocolic fistula.
- Trichobezoar.
- Pathology of carcinoma stomach.
- Early gastric cancer.
- Advanced gastric cancer.
- Spread of gastric cancer.
- Linitis plastica.
- Management of carcinoma stomach.
- Carcinoma pylorus.
- Palliative treatment for carcinoma stomach.
- Gastrectomy.
- Vagotomy.
- Gastrojejunostomy.
- Pyloroplasty.
- Gastrostomy.

21

Small Intestine

Anatomy
Meckel's diverticulum
Regional enteritis (Crohn's disease)
Surgical complications of typhoid
Surgical complications of roundworm
Pneumatosis cystoides intestinalis
Mesenteric vessel ischaemia
Necrotising enterocolitis
Small bowel tumours
Carcinoid tumour
Short bowel syndrome
Small bowel enema
Capsule endoscopy
Small bowel enteroscopy

ANATOMY

The small intestine is 6 m in length. This includes upper fixed (duodenum, 25 cm), lower mobile part (proximal 2/5th is jejunum and distal 3/5th is ileum).

Differences between the features of jejunum and ileum

Jejunum	*Ileum*
1. Long and few vasa rectae	Short and numerous vasa rectae
2. Long plicae	Small plicae
3. Thick wall	Thin wall
4. Mesentery transparent	Mesentery contains fat
5. Peyer's patches are scanty	Peyer's patches are abundant, located in the antimesenteric border
6. Villi, leaf like and more abundant.	Villi, finger like and less abundant.

Mesentery attaches the small intestine to the posterior abdominal wall, contains blood vessels, lymphatics, fat.

Nerve Supply

Sympathetic supply is from T_9-T_{11} and parasympathetic supply is from vagus. Both pass through coeliac and superior mesenteric plexus.


Long vasa recta
Short vasa recta
Vascular arcades
A Jejunum
B Ileum

Figs 21.1A and B: Vascular pattern in (A) jejunum, (B) ileum.


Aorta
Coeliac artery
Duodenum
Jejunum
Ileum
Appendicular artery
Superior mesenteric artery

Fig. 21.2: Blood supply of the small bowel.

Normal GIT secretions

Saliva	1000 ml
Gastric	1500 ml
Intestinal	4000 ml
Bile	1000 ml
Pancreas	1500 ml

One cannot love what he cannot respect, whether it be himself or another.

Bowel wall contains the myenteric plexus of Auerbach which lies between the circular and longitudinal muscle coats; and submucous plexus of Meissner.

Sympathetic nerves are motor to sphincter, inhibitory to peristalsis; parasympathetic nerves are inhibitory to sphincter and stimulates peristalsis.

Cell type	*Function*
Goblet cells	Mucus
Paneth cells	Lysozyme, tumour necrosis factor, cryptidins
Enterocytes	Absorption
Entero-endocrine cells	Different hormones

Investigations for small bowel diseases

- Barium meal follow through
- Small bowel enema (*Enteroclysis*)
- Plain X-ray abdomen to see intestinal obstruction.
- Selective splanchnic angiography to see vascular bleed or malformation (DSA)
- Isotope scintigraphy to see Meckel's diverticulum.
- Estimation of faecal fat in 24 hours—normal is less than 7 gram
- *Schilling test* to find out the absorption of vitamin B_{12} from terminal ileum
- SeHCAT bile acid absorption test (selenium labelled) to find out the absorption of bile acids from the terminal ileum
- Many different breath tests are used to find out malabsorption, bacterial overgrowth and transit time
- Jejunal biopsy
- CT scans to see fistula, tumour, and spread
- Capsule endoscopy is very useful



Fig. 21.3: Gas under diaphragm in an infant. It could be congenital cause, trauma, etc.

MECKEL'S DIVERTICULUM

> ***It appears at a specific site in the ileum and the wall contains each of the several layers of the intestinal tract…. The proof that the diverticulum is a residuum of the communication between the intestinal canal and the umbilical stalk rests in the findings which I have observed in three stillborn, full-term fetuses.***
>
> **—Johann Friedrich Meckel,** 1809

It is a congenital diverticulum arising from the terminal ileum and is part of the unobliterated proximal portion of the vitello intestinal duct.

It is–

- 2% common.
- 2 feet from the ileo-caecal valve.
- 2 inch in length.
- It is congenital, results from incomplete closure of vitello-intestinal duct.
- It is the most common congenital anomaly of small intestine.
- Arises from the antimesenteric border of the ileum, containing all three layers of the bowel with independent blood supply.
- In 20% of cases mucosa contains heterotopic epithelium like gastric (commonest), colonic and pancreatic tissues.
- It may be connected to or communicated with the umbilicus through a band or fistula.
- It may be associated with oesophageal atresia, exomphalos, and anorectal malformations.



Fig. 21.4: Anatomy of Meckel's diverticulum.

Presentations in Meckel's Diverticulum

- Asymptomatic – in majority cases.
- Severe haemorrhage most common, seen in children aged 2 years or younger (*Maroon coloured blood*).

- Intestinal obstruction due to bands/adhesions/intussusception.
- Perforation.
- Intussusception, volvulus of small bowel.
- Peptic ulceration.
- Diverticulitis—features mimic acute appendicitis.
- Littre's hernia—It is presence of Meckel's diverticulum in hernial sac as content. It is observed in inguinal/femoral hernia.
- Silent Meckel's diverticulum found during laparotomy or laparoscopy or by radioisotope study.
- Carcinoid or GIST can occur in Meckel's diverticulum.



Fig. 21.5: Meckel's diverticulum.

Diagnosis

- Technetium (Tc^{99}) radioisotope scan is very useful (90-95% accuracy). Ninety per cent of heterotrophic gastric mucosa can be identified in Meckel's diverticulum by radioisotope study. It can detect Meckel's diverti-culum with minimal bleeding also (0.1 ml/minute). So it is very useful investigation in children presenting with bleeding.
- X-ray abdomen to see complications like obstruction, perforation.
- *Laparoscopy is very useful.*
- Enteroclysis/small bowel enema under fluoroscopy may show the Meckel's diverticulum. It is probably the most accurate investigation.


Appendix
Meckel's diverticulum

Fig. 21.6: Laparoscopic view of Meckel's diverticulum. Patient presented with features of acute appendicitis. On laparoscopy, Meckel's diverticulum which was adherent to umbilicus by a cord was found. Appendix was identified separately. Appendicectomy and Mecklian diverticulectomy was done.

Treatment


Colon
Meckel's diverticulum
Ileum
Meckel's diverticulum
Meckel's diverticulum
Ileum
Resected Meckel's diverticulum
End-end anastomosis
Resected Meckel's diverticulum with ileum
Meckelian diverticulectomy linear staplar can be used
Note:
Care of clearing heterotopic gastric epithelium should be taken. Should avoid stricture formation later.

Fig. 21.7: Meckel's diverticulum – surgical treatment. Meckelian diverticulectomy is done by obliquely clamping beyond the base of the Meckel's diverticulum. Care should be taken not to retain heterotopic gastric (or other) epithelium which can be felt like indurated area. Enough precaution should be taken so that stricture will not form later. When heterotopic tissues extend beyond the Meckel's diverticulum into the ileum, then resection of ileum with Meckel's and anastomosis is done. Clamping distal to the base of the Meckel's diverticulum like appendicectomy should not be done. It will cause stricture, leak or retaining heterotopic tissues in the part.

The successful man is the average man, but focused.

- Asymptomatic Meckel's diverticulum can be left alone when identified during laparotomy.
- *Resection of a short segment of ileum containing Meckel's diverticulum and end to end anastomosis is done.*
- *Meckelian diverticulectomy* with closure of enterotomy also can be done, but chances of retaining heterotopic tissues and stenosis are higher.

Indications for Surgery

– Surgery is done whenever the base is narrow, and in lengthy diverticulum.
– Presence of adhesions or band which may precipitate obstruction, intussusception or volvulus.
– Symptomatic patients or presence of complications.
– If it is found in children below 2 years.

"Meckel's diverticulum frequently suspected; often sought; seldom found" – Charles Mayo.



Fig. 21.8: Jejunal diverticula are rare. Often can cause obstruction, haemorrhage. It needs surgical resection.

REGIONAL ENTERITIS (Crohn's Disease)

> ***We propose to describe, in its pathologic and clinical details, a disease of the terminal ileum, affecting mainly young adults, characterised by a subcutate or chronic necrotising and cicatrising inflammation. The ulceration of the mucosa is accomplished by a disproportionate connective tissue reaction…a process which frequently leads to stenosis of the lumen of the intestine, associated with the formation of multiple fistulas.***
>
> **—Burrill Bernard Crohn, Leon Ginzburg, Gordon D. Oppenheimer,** 1932

- It is a *granulomatous, noncaseating inflammatory condition of the ileum commonly and of the colon often.*
- It is independent of age, sex, socioeconomic status and geographic areas.

Aetiology

- Unknown, but a familial and infective nature is thought of.
- Increased autoantibodies.
- Diet and food allergy.
- It is slightly more common in females.
- DNA of Mycobacterium paratuberculosis was found in intestines of 60% of patient's with Crohn's disease but antituberculous drug therapy has not helped them.
- Focal ischaemia as a vasculitis may be the cause.
- 10% of first degree relatives; 50% of monozygotic twins develop Crohn's disease. Genes NOD2 / CARD15 in chromosome 16q12 has got strong association with Crohn's disease. CARD15 is expressed in Paneth cells of the ileum.
- Smoking is related to Crohn's disease as aetiology, as for relapse and for exacerbations.

Pathology

Transmural inflammation
↓
Granuloma formation with linear snake like ulcers
↓
Cicatrisation
↓
Thickening of the bowel wall *(Hose pipe pattern)*
↓
Adhesions
↓
Fistula formation

- There is increased mucus membrane permeability → antigen induced cell mediated inflammatory response → release of cytokines like TNF, interleukin 2 → defect in suppressor T cell → granuloma and other pathology.
- Fibrosis, stricture formation, deep ulcers, oedema of mucosa between ulcer areas which looks like '*cobble stone*', skipped normal areas in between, serosal opacity, mesen-teric fat stranding, enlarged mesenteric lymph nodes, abscesses in the mesentery, fistula are the pathology. Small mucosal aphthous ulcers are earliest gross feature.
- Disease may be *inflammatory, stricturing or perforating types*.
- Noncaseating giant cell granuloma with chronic inflammation of all layers; focal arterial blocks in muscularis propria are the microscopic features.

Main features of Crohn's disease

- Ileum—most common site of occurrence—60%
- Rectal sparing is usual and common
- Skip lesion
- Hose-pipe pattern
- Linear ulcers and cobble stone appearance of mucosa
- Transmural

- Mesentery is thickened, oedematous, with enlarged lymph glands which will neither break nor calcify.
- Rarely jejunum, stomach and other parts of GIT like oral cavity, oesophagus are involved.
- In colon (30%), it is commonly observed in caecum and ascending colon.
- Toxic megacolon with acute colitis even though rare, can occur in Crohn's disease.

Note: **Anal fissure is most common anal problem in Crohn's disease. It may lead into perianal abscess and fistula.**



Fig. 21.9: Crohn's disease in small bowel. It is transmural full thickness disease. In 30% cases colon is involved. Skip lesion, stricture, fistula are common. It can involve any part of GIT occasionally.

Clinical Features

a. ***Acute presentations* (5%):**
It mimics acute appendicitis with severe diarrhoea. Often there will be localised or diffuse peritonitis.

b. ***Chronic Crohn's:***

First stage—Mild diarrhoea, colicky pain, fever, anaemia, mass in right iliac fossa which is tender, firm, nonmobile along with recurrent perianal abscess.

Second stage is either acute or chronic intestinal obstruction due to cicatrisation with narrowing.

Third stage—Fistula formation—enterocolic, entero-enteric, entero-vesical, entero-cutaneous, etc.

It is *pre-cancerous condition but not as much as ulcerative colitis*.

Extraintestinal manifestations of Crohn's disease

- Skin: Erythema nodosum, pyoderma gangrenosum
- Eyes: Iritis, uveitis
- Joints: Arthritis, ankylosing spondylitis
- Sclerosing cholangitis
- Nephrotic syndrome
- Pancreatitis
- Amyloidosis

Investigations

Plain X-ray abdomen, ultrasound abdomen.

Barium meal follow through or small bowel enema shows—

- Straightening of valvulae conniventes.
- Multiple defects (*cobble-stone* appearance).
- Cicatrisation of ileum (*string sign of Kantor*).
- *Rose thorn appearance of the bowel wall.*
  Radiologically Crohn's disease is classified as ***non-stenosing type or stenosing type.***
- CT scan and CT fistulogram is useful method.
- Colonoscopy usually shows normal rectum; with colon showing aphthoid like ulcers and reddened mucosal margin. Deep ulcers, stricture and fistula will be evident in late cases.
- Blood tests for anaemia, protein loss, mineral and trace element loss like magnesium, zinc, and selenium. There will be raised C *reactive protein and orosomucoid* in active disease.
- Capsule endoscopy is useful investigation.
- MRI to diagnose anal disease.

Treatment

Medical

- Bed rest, protein and vitamin supplementations. Often nasogastric tube nutrition or TPN is required.
- Steroids are mainly used to induce remission of the disease in initial phase. It is less useful for maintenance. Dose is 20-40 mg/day (0.5 mg/kg/day) for

When you get to the end of your rope, tie a knot and hang on.

3-6 weeks. Methylprednisolone infusion IV 60 mg / day for 5-7 days can be given initially.
- Azathioprine is used for maintenance therapy. It inhibits the cell mediated immunity. 6-mercaptopurine and cyclosporine are also used.
- Antibiotics are given to control sepsis. Salazopyrines are mainly used in acute ileitis and colitis. It is not useful in inducing remission. 5-aminosalicylic acid (5-ASA) and sulfasalazine are also used. 5-ASA inhibits leokotriene, TNF, interleukin production. It acts mainly on colonic and partly on small bowel mucosa.
- Metronidazole is useful in reducing the anal and colonic pathology by suppressing the cell mediated immunity and also as antibacterial. It is not beneficial for small bowel disease.
- Monoclonal antibody like infliximab is used in severe refractory cases which act against tumour necrosis factor alpha (TNFα). Single dose is used for induction. Later given after 2nd week, 6th week and then once in 8 weeks at a dose of 5 mg/kg. It is also useful in promoting closure of fistula in 60 - 80% cases. But its long term side effects are not confirmed.

Medical therapy
- To induce remission – steroids
- For maintenance – immunomodulating drugs like azathioprine
- Antibiotics, metronidazole (as immunomodulator)
- Monoclonal antibody – infliximab
- Nutritional support

Note: Patients with Crohn's disease should avoid NSAIDs

Surgery

Indications
- Failure of medical treatment.
- If patient can not be weaned off systemic steroid after 6 months.
- Intestinal obstruction.
- Fistula formation, bleeding, malignant change.
- Perforation, fulminant colitis.
- Perianal problems.

Note: Surgery is not to cure the disease, but to correct complications. Recurrence of complications and relapse of disease can occur even after surgery. Patient should be on postoperative azathioprine/6 MP/5ASA.

Surgeries
- Ileo-caecal resection (common procedure done because commonly ileocaecal region is involved).
- Segmental resection—conservative resection is better.
- Total colectomy and ileorectal anastomosis.
- Stricturoplasty.
- Temporary ileostomy.
- **Per-se appendicectomy should not be done in Crohn's, as it may lead to external fistula.**
- Right hemicolectomy is done occasionally.
- Emergency colectomy may be needed in 8% of patients with extensive severe colitis but with rectal sparing.
- Laparoscopic resection is good alternative.
- Occasionally if rectum is diseased or anal disease is severe then total proctocolectomy with ileostomy is done.
- Corrective surgery for anal diseases like fissure, abscess and fistula.
- Definitive procedures for internal fistulas like ileovesical, ileocolic with faecal and urinary diversions.



Fig. 21.10: Stricturoplasty can be done in Crohn's disease in case of short strictures in the absence of active inflammation.

Complications of Crohn's
- Intestinal obstruction
- Stricture
- Bleeding
- Fistula formation
- Carcinoma
- Perianal abscess
- Peritonitis
- Pericolic abscess

Differential Diagnosis

- Radiation enteritis and Yersinia enteritis.
- Ulcerative colitis.

- Intestinal tuberculosis.
- Carcinoma ileum or caecum.
- Differential diagnosis for mass in the right iliac fossa (carcinoma caecum, actinomycosis, appendicular mass, ileo-caecal TB, ectopic kidney, mesenteric lymphadenitis).

SURGICAL COMPLICATIONS OF TYPHOID

- Typhoid (Enteric fever) is caused by organism—*Salmonella typhi.*
- Mode of transmission is faecooral route.
- Presents initially with fever, chills, abdominal pain.

Typhoid

- *S typhi, S paratyphi* A, B and C
- Gram-negative flagellated bacilli
- Faecooral route is commonest mode of spread
- Asymptomatic human carriers are most important reservoirs (*Typhoid Mary*)
- Peyer's patches, mesenteric lymph nodes, gallbladder, spleen, liver and bone marrow are commonly involved

1. Paralytic ileus is the *commonest* complication.
2. Intestinal haemorrhage—as the Peyer's patches in terminal ileum are enlarged and ulcerated - 10%.
3. ***Perforation usually occurs in 3rd week of the infection.*** Ulcers are multiple, arranged in parallel and in anti-mesenteric border of the ileum.
   One or more ulcers might perforate and many ulcers may be on impending perforation.
   Patient is toxic, presents with—

   - *Severe diarrhoea*
   - *Relative bradycardia*
   - *Soft abdomen*
   - *Obliterated liver dullness*
   - *Abdomen without guarding and rigidity (because of Zenker's degeneration)*
   - *Initial history of fever for few days then pain abdomen and tenderness, which is progressive*

   Associated Features—
   1. Splenomegaly
   2. Fever, headache
   3. Rose spots in the skin

   Investigations
   - Possibility of missing typhoid perforation is very high.
   - X-ray in erect posture shows gas under diaphragm.
   - Widal test is positive.
   - Neutropenia is seen in blood.
   - Blood culture and stool cultures are often required. Marrow culture is useful.
   - Identification of specific and sensitive markers (to detect Ig G/Ig M). These tests are positive even when blood culture is negative.

Note:
- Single ulcer perforation occurs in 80% of cases.
- In paratyphoid B fever colon perforation can occur.
- CT scan abdomen is ideal investigation to detect early pneumoperitoneum and fluid collection.



Fig. 21.11: Enteric perforation is often severe causing faecal peritonitis. Resection/exteriorisation may be needed in severe cases.

Treatment
- Antityphoid drugs (Quinolones, chloramphenicol, ceftriaxone sodium) are started.
- Later laparotomy is done to close the perforation.
- Ulcers which are on impending perforation should be sutured with serosa.
- Presently, resection and anastomosis is also accepted as treatment when multiple perforated ulcers are present.
- ZIP technique (laparostomy) to reopen the abdomen whenever required is also beneficial.
- Exteriorisation of ileum is ideal in a critically ill-patient. Once patient recovers properly after 6-12 weeks closure and continuity is maintained.
- Closure of perforation with ileotransverse anastomosis is the other option.
- ICU care, TPN/enteral feeding/monitoring/blood transfusion/fluid and electrolyte management/prevention or management of other complications like DVT/DIC/ARDS/septicaemia.

Courage is grace under pressure.

4. Cholecystitis and carrier stage.
5. Venous thrombosis particularly of common iliac vein is known.
6. Typhoid cystitis, bacilluria, epididymoorchitis.
7. Arthritis.
8. Typhoid osteomyelitis (granular sequestrum).
9. Typhoid perichondritis and laryngitis leading to air way obstruction.
10. Typhoid abscess in liver, spleen, brain and parotid.
11. Myositis, myocarditis, meningitis.

SURGICAL COMPLICATIONS OF ROUNDWORM (*Ascaris lumbricoides)*

Life Cycle

Eggs → faecooral route → larvae → portal circulation → liver → hepatic veins → IVC, heart, pulmonary artery → lungs → maturation of larvae (8 weeks) → alveoli, trachebronchial tree → coughed out or swallowed to intestine → adult roundworms → male + female worms union → release of eggs → stool → reinfection.



Fig. 21.12: Roundworm removed from peritoneal cavity. Note the faecal contamination.



Fig. 21.13: Specimen of ileum showing roundworm *bolus*. Bolus causes intestinal obstruction, commonly near terminal ileum.



Figs 21.14A and B: Gastroduodenoscopy view of roundworm. It was removed through endoscopy. Roundworm in proximal bowel can cause pancreatitis, cholangitis. Vomiting of roundworms signifies intestinal obstruction. It need not be due to roundworm obstruction. Because of the obstruction and proximal bowel irritation, worms move proximally into stomach and come out through the mouth. (*Courtesy by Dr Tantry, Dr Sandeep Gopal, Gastroenterologists, KMC Mangalore*).



Fig. 21.15: Plain X-ray abdomen in a child showing features of intestinal obstruction due to roundworms in the bowel.

Features

- Worm colic.
- Toxicity—fever, tachycardia.
- Subacute intestinal obstruction.
- Acute intestinal obstruction with palpable round worm bolus per abdomen.
- Perforation—common in the ileum.
  Note: *Perforation usually occurs at the site of pre-existing disease like nonspecific ileal ulcer, amoebic ulcer, typhoid ulcer, and suture line.*
- Intraperitoneal abscess.
- Dyspepsia, malabsorption, iron deficiency anaemia.

- Due to migration of worm into the CBD/pancreatic duct causes ascending cholangitis with fever, jaundice and upper abdominal pain or features of pancreatitis.
- *Loeffler's syndrome* is due to larvae in the alveoli causing fever, dry cough, chest pain, dyspnoea.



Fig. 21.16: Roundworm obstruction. Worms removed through an enterotomy.

Investigations

- Small bowel enema/barium meal follow through may show roundworms in the ileum.
- US can demonstrate the worms/worm bolus/worm in CBD or pancreatic duct.
- Blood may show eosinophilia, anaemia, hypoalbuminaemia. LFT for worm in CBD.
- Chest X-ray may show bronchitis.
- Sputum or bronchial wash may show larvae or Charcot – Leyden crystals.
- Stool examination may show ova.
- CT / MRI will show worms/obstruction/worm in CBD or pancreatic duct.

Treatment

- Antihelminthic drugs like piperazine citrate 60 ml is given immediately if there are features of obstruction, otherwise at night time. Albendazole, mebendazole are other drugs used. Proper nutrition is important.
- Nasogastric aspiration; IV fluids; observation is sufficient in most of the situations. In 48 hours, obstruction will be relieved and child passes worm bolus per anally.
- Occasionally laparotomy and milking of the worm bolus into the caecum without enterotomy is needed. Once worms are in the colon, hypertonic saline wash per anum makes them to disperse and pass outside.
- Removal of worms by enterotomy is rarely done. Enterotomy should be securely sutured using silk otherwise reperforation from sutured site can occur by worm toxins or by worm activity and migration.
- If there is perforation (common site is ileum) or gangrene with peritonitis, peritoneal worms should be essentially removed. Ideally ileum should be exteriorised to prevent suture line breakdown after closure due to worms. Once patient recovers bowel ends are sutured to maintain the continuity and abdomen is closed. Even though it is *ideal method*, it is not commonly performed.
- ERCP, worm extraction and stenting is done for worm in CBD/pancreatic duct.

Treatment of roundworm obstruction

- Drugs—Piperazine citrate, mebendazole, albendazole
- Most often by conservative treatment, worms get dispersed and passed per anally. But patient requires nasogastric aspiration, IV fluids, antibiotics, and observation
- If patient is not responding then laparotomy is done. *Worm bolus* in the distal ileum is milked in to the caecum. Often enterotomy and removal of worms is required
- Perforation due to worm requires immediate laparotomy, removal of worms and closure of perforation
- Only rarely, resection and exteriorisation is required

PNEUMATOSIS CYSTOIDES INTESTINALIS

- It is transient, thin cysts containing nitrogen in submucosa and subserosa of ileum.
- It is due to increased intraluminal pressure, which forces N_2 through the layers of the bowel due to hyper-peristalsis.
- It is associated with chronic duodenal ulcer, chronic pulmonary disease, bowel obstruction.

Treatment

- O_2 support.
- Metronidazole.
- Cause is treated

A man who does nothing never has time to do any thing.



Fig. 21.17: Pneumatosis cystoides intestinalis.

SMALL BOWEL STRICTURES

Causes

- Tuberculosis of ileum/jejunum.
- Crohn's disease.
- Radiation enteritis.
- Ischaemic strictures – after bowel ischaemia, necrotising enterocolitis.
- Nonspecific causes.
- *Garrey's stricture* following long standing irreducible hernia occurs after reduction and surgery (due to constriction band causing ischaemia at the site).

Management

- Small bowel enema/capsule endoscopy/CT scan – investigations.
- *Treatment*: Treating the cause; resection and anastomosis.

MESENTERIC VESSEL ISCHAEMIA

Superior mesenteric artery is commonly involved than inferior mesenteric artery. Often superior mesenteric vein can also get involved.

Causes

- ***Embolism*** (50%)—*Sources*
  - From left auricle, as seen in atrial fibrillation.
  - A mural infarct.
  - Atheroma from aorta or aneurysm.
  - Endocarditis vegetations.
  - Left atrial myxoma.
- ***Thrombosis***—may block the origin of the superior mesenteric artery and can cause ischaemia of full length of small bowel. It is life threatening.
- ***Non-occlusive***—due to hypotension/hypoperfusion.



Figs 21.18A and B: Ischaemic bowel necrosis. It will lead to perforation and peritonitis. So always requires surgical resection.



Fig. 21.19A



Fig. 21.19B



Fig. 21.19C

Figs 21.19A to C: Acute extensive mesenteric ischaemia causing small bowel gangrene. Patient will develop short gut syndrome.

- Superior mesenteric vein thrombosis occurs in patients with portal hypertension, portal pyaemia, sickle cell disease, women with contraceptive pills (OCP).
- Thrombosis of superior mesenteric artery may be due to atherosclerosis or due to TAO. Embolism can involve branches of the SMA, i.e. middle colic or ileo-colic artery.



Fig. 21.20: Gangrene of small bowel due to mesenteric vascular ischaemia.

Pathology

- Bowel and mesentery will be oedematous, friable, discoloured, and collected with fluid and blood.
- Once gangrene sets in, perforation can occur leading to peritonitis.

Clinical features

- Pain initially around the umbilicus and later diffuse.
- Persistent vomiting
- Bloody diarrhoea, dehydration, shock and *toxicity*
- Guarding and rigidity, rebound tenderness

Types

- Acute.
- Chronic.
- It can be extensive gangrene or focal ischaemia.

Specific Features of Mesenteric Ischaemia

- It is often considered as intestinal failure.
- It can be *thrombotic; embolic; and non-occlusive* (low flow status – is due to reduced SMA perfusion by underlying causes like cardiogenic shock, mesenteric vasoconstriction or part of systemic disease. There is no documented thrombosis or embolus).
- It is rapidly progressive causing early mortality.
- Clostridium, anaerobic and streptococci infections are evident.
- Gas bubble in the mesenteric vein is pathognomonic sign of irreversible mesenteric ischaemia.
- CT / CT angiogram is very useful. An occlusion at the ostium of SMA signifies thrombosis. Embolic occlusion is smooth filling defect, usually distal to origin of middle colic artery sparing proximal small bowel, right side colon and transverse colon. Emboli can be fragments causing multiple patchy necrosis of bowel at different sites.
- Decreased blood volume; poor tissue perfusion; metabolic acidosis; myocardial depression by depressant factor; endotoxaemia; ARDS; renal failure; septicaemia and MODS are the pathological events.
- On laparotomy – *musty smell and dusky look of extensive gangrenous bowel is typical*. When in doubt, ischaemia should be confirmed by oxygen support; warming; on table Doppler.

Investigations

- Plain X-ray abdomen.
- Ultrasound abdomen.

A fault once denied is twice committed.

- Angiogram—On-table angiogram
- Doppler study—(On table).
- *Blood tests*: Total count is raised with drop in haemoglobin. Raise in blood urea and serum creatinine is common. Serum phosphate level is increased very early in 4 hours as small bowel is rich in phosphate. Arterial blood gas analysis is often essential. Blood culture may be needed.

Treatment

- *Emergency laparotomy* is done. With the help of Doppler the block is identified and the vessel is opened. The block is removed and the bowel is reperfused.
- If patient has presented after 24-48 hours, gangrene might have already occurred, then resection and anastomosis is done.
- If patient presents within 6 hours, it is possible to prevent gangrene and to salvage the bowel. Emergency SMA angiography is done. Papaverine is injected for vasodilatation (by many studies its benefit is not confirmed). Often heparin (20,000 units loading dose and then maintenance dose of 5000-10000 units 6th hourly) or thrombolytics are injected. Immediate laparotomy is done. SMA is opened (arteriotomy) over the obstruction and thrombus/embolus is removed using Fogarty catheter. Perfusion is maintained. Close monitoring is essential for possibility of formation of bowel gangrene and if it is so relaparotomy should be done for bowel resection.
- Steroids are given to reduce lysosomal membrane destruction and effects of endotoxins; to maintain arterial resistance and complement activity. High dose hydrocortisone is used.
- Higher generation antibiotics; critical care; ventilator, fluid, electrolytes and nutritional support (TPN) are essential.

Note:

- – Minimum bowel length required is 1.2 meters, otherwise the patient will have high mortality (due to short bowel syndrome).
- – Small bowel transplantation is under trail for the same.
- – Mesenteric bowel ischaemia has got very high mortality.
- – Development of septicaemia, ARDS, DIC, post-operative leak are common.

NECROTISING ENTEROCOLITIS

- Necrotising enterocolitis is an acquired inflammatory disease commonly seen in infants and newborn but occasionally can occur in children and adults. It is more commonly seen in premature babies. It is more common in formula fed babies than breast bed babies. Reduced gut flora make virulent pathogens to act and cause sepsis.
- Common site is terminal ileum, caecum and ascending colon. Often it can involve entire small bowel.
- Gas in the bowel wall and often in portal vein is typical.

Incidence

- Often associated with low birth weight babies.
- Preterm babies 90%.
- Term babies 10%.

Pathogenesis

Hypoxia
Hypothermia
Hypotension
Hyperviscosity
Acidosis

Umbilical artery cannulation
Exchange transfusion
Hyperosmolar feeds
Packed cell transfusion
Over dosage with calcium antagonists

↘ ↙

Mesenteric ischaemia.
↓
Bacterial invasion of mucosa and bowel wall.
↓
Necrosis—Skip lesions are common.
↓
Necrotising enterocolitis.

Sites

- Common in small bowel.
- Terminal ileum and caecum.



Fig. 21.21: Necrotising enteritis. Note the segmental involvement of the disease.

Clinical Features

Most babies present with:

- Bilious vomiting.
- Abdominal distension, guarding and rigidity.
- Bradycardia.



Figs 21.22A and B: Necrotising enterocolitis. Skin necrotic lesions are typical. It is common in infants and children but can be seen in adolescents occasionally. (*Courtesy by Dr Rupen MS, KMC Mangalore*).

- Apnoea, lethargy.
- Gross or occult blood in stool (75%).
- Erythema and oedema of anterior abdominal wall—late feature.
- DIC.
- Mortality is 20%.

Investigations

a. Plain X-ray abdomen—
  - Linear gas shadow in bowel wall.
  - Free intraperitoneal air implies perforation.

b. Blood examination—leukocytosis, anaemia, hyperkalemia, metabolic acidosis.

Complications

- Stricture – small bowel.
- Perforation-peritonitis.
- Colonic stricture can develop lately after healing of ischaemic area. It is seen in 10% of cases.

Management

I. ***Medical therapy***
  - Nasogastric aspiration.
  - Broad spectrum IV antibiotics.
  - TPN for 10-14 days.
  - Oxygen supplement is required.

II. ***Surgery***

Indications

1. Pneumoperitoneum.
2. An abdominal mass.
3. Dilated intestinal loops.

Procedures done

- Bowel necrosis and perforation—resection with stoma.
- Localised disease—resection and primary anastomosis.

Complication: Extensive bowel resection—short bowel syndrome.

SMALL BOWEL TUMOURS

- They are rare neoplasms – 3% of all GI tumours.
- Common in elderly men.
- Common in New Zealand and Hawaii.
- It can be benign or malignant.
- Early diagnosis is difficult.
- Presentations are vague initially.



Fig. 21.23: Jejunal haemangioma. Surgical resection cured the condition.



Fig. 21.24: Jejunal tumour.

Man is a creation of desire; not a creation of need to this world.



Fig. 21.25: Gross look of small bowel lymphoma.

Reasons why malignancy is uncommon in the small bowel (even though it comprises 75% of length and 90% of GI mucosa)—

- Rapid transit time, 30 minute – 2 hours. So exposure of mucosa to toxins and metabolites is less.
- Alkaline mucus rich luminal content is protective.
- Cells of small bowel produce the enzyme benzopyrene hydroxylase which detoxifies the carcinogen – benzopyrone.
- High levels luminal IgA provides immunity.
- Plenty of lymphoid tissue in the wall provides immunity.
- Healthy small bowel has got less bacterial load and so their toxic metabolites (as compared to colon).

Risk causes implicated are—

- Bile acids and their metabolites.
- Post cholecystectomy status.
- Familial adenomatous polyposis (FAP) especially with duodenal adenomas has got very high chance of developing adenocarcinoma.
- Crohn's disease has got 100 times increase in incidence of adenocarcinoma.
- Celiac disease increases the risk of lymphoma.
- Peutz-Jegher's syndrome has got increased risk of small bowel adenocarcinoma.
- Patients with chronic immunosuppression have very high risk of developing NHL (PTLD – Post transplant lymphoproliferative disorder, HIV) or sarcoma.
- Patient with von Recklinghausen's disease of neurofibromatosis is prone to develop GI neurofibroma or neurofibrosarcoma.

Presentations

- Asymptomatic initially.
- Features of obstruction/intussusception/bleeding.
- Vague abdominal discomfort.

Investigations

- Often it is very difficult to assess small bowel. It may be on table finding during surgery, while presenting as complication like obstruction.
- Small bowel enteroclysis.
- CT abdomen is better investigation to assess bowel/nodes/organs.
- Video capsule endoscopy enables to visualise small bowel mucosa properly.
- Enteroscopes (push type or Sonde pull enteroscopes) are technically difficult.
- Intraoperative enteroscopes are useful.

BENIGN TUMOURS OF SMALL BOWEL

Benign tumours of small bowel are 50% of primary small bowel tumours. Adenoma can be potentially malignant.

Types

- *Brunner gland adenoma* occurs in duodenal submucosa which secretes alkaline bicarbonate rich fluid. Bleeding is the usual problem. It is treated by endoscopic resection. It rarely turns into malignancy. It is usually hyperplastic.
- *Adenoma* – it can be tubular/villous/tubulo villous. It can occur anywhere in small bowel but commonly seen in periampullary region presenting as obstructive jaundice. It is treated by ERCP to relieve obstruction with biopsy. Size more than 2 cm can lead into adenocarcinoma. EUS is ideal tool to assess size and depth. Transduodenal excision/pancreaticoduodenectomy are the surgical options.
- Lipoma (submucosal) – mainly causes intussusception.
- Puetz-Jegher's syndrome.
- Haemangioma – It presents as small bowel bleed. It can be diagnosed by capsule endoscopy. Endoscopic sclerotherapy or angiographic embolisation is the therapy.
- Others like leiomyoma.

Features

- They cause haemorrhage, colicky pain, and intussusception.

- Diagnosis is by suspicion. Small bowel enema, capsule endoscopy, radioisotope study, CT scan or MRI may help in identifying the disease. Laparoscopy and proceed may be useful.
- Commonly it is on table finding during exploration for acute presentations.
- Adenomas are potentially malignant depending on the size (> 2 cm).

Treatment

- Resection and anastomosis cures the condition.
- Surgery is not done for Peutz-Jegher's syndrome unless it presents with complications.

MALIGNANT TUMOURS OF THE SMALL BOWEL

1. Adenocarcinoma



Fig. 21.26: Resected small bowel specimen showing small bowel adenocarcinoma.

- Its incidence is 40% of small bowel tumours.
- It is most common primary malignant small bowel tumour.
- In 80% cases it is in the duodenum and jejunum.
- FAP, adenoma, Crohn's, coeliac diseases are the causes.
- Nonspecific features, anorexia, crampy pain abdomen, bleeding and diarrhoea, obstruction or features of metastases (liver).
- CT scan, capsule endoscopy are the investigations.
- TNM system is used for staging.
- Nodal spread is the important prognostic factor.
- Surgical resection is the choice of therapy.
- RT and chemotherapy are less beneficial.
- It carries a poor prognosis.



Fig. 21.27: Carcinoma ileum near ileocaecal junction. It (adenocarcinoma of ileum) carries poor prognosis. It is often on table diagnosis.



Fig. 21.28: Jejunal adenocarcinoma presenting as stricture with features proximal small bowel obstruction.

2. Non-Hodgkin's lymphoma (NHL) – 25%

- GI is the commonest extranodal site of NHL (20%), with small bowel (primary intestinal NHL) as second common site (30%) for extranodal site of NHL. (First common site is stomach – 60%).
- Lymphadenopathy/mediastinal lymph node enlargement are absent. Normal spleen, liver, blood peripheral smear are observed.

Love means making the other happy, even from a distance.

- B cell type is the commonest type 75%.
- T cell type (25%) carries poor prognosis.
- Presentations are malabsorption, obstruction, perforation, haemorrhage or palpable mass.
- CT scan with CT guided biopsy or laparoscopic biopsy is needed.
- Surgical resection and chemotherapy are the treatment.
- Prognosis is poor.

3. Carcinoid tumour - 30%.

4. GIST (Gastrointestinal stromal tumour)

- It is rare but most common non epithelial small bowel tumours.
- 25% of GIST occurs in small bowel (stomach – 50 to 60%). It is 0.2% of all GI tumours.
- It is equal in both sexes.
- It arises from interstitial cell of Cajal.
- More than 95% show c-kit (transmembrane receptor tyrosine kinase) mutation.
- Many mesenchymal tumours of small bowel are now classified as GIST. GIST attains massive size when presenting clinically.
- Palpable mass, compression, haemorrhage are the features.
- CT is diagnostic. Histochemistry and tumour markers are needed.
- GIST can be low risk or high risk group based on tumour size and mitotic index.
- Surgical wide resection is the treatment.
- Imatinib mesylate a KIT kinase inhibitor is used successfully. SU11248 with similar effect is also used.



Fig. 21.29: Leiomyoma of jejunum. It is now classified under gastrointestinal stromal tumour (GIST).

5. Liposarcoma, myxoliposarcoma.

6. Secondaries in small bowel

They are very rare – if it is present, primary being commonly melanoma.

Malignant tumours of small bowel

- Adenocarcinoma is commonest – 40%. Order of occurrence – duodenum, jejunum and ileum
- GIST is new entity comprising smooth muscle tumors also
- Carcinoid and lymphoma has got better prognosis
- Adenocarcinoma and GIST has got poor prognosis
- Presentations are pain, diarrhoea, weight loss, anaemia, melaena, palpable mass, intestinal obstruction and metastatic features
- Bleeding and perforation are common in lymphoma and sarcoma
- Enteroclysis/capsule endoscopy/CT scan/histochemistry are needed to diagnose
- Surgery is the main therapy
- Imatinib is used in GIST with favourable results

CARCINOID TUMOUR

It commonly occurs in *appendix* (65%), ileum (25%), other parts of GIT and rarely bronchus, testis, ovary.

In the small intestine, carcinoids are most often seen within the terminal 2 feet of the ileum.

- They arise from the enterochromaffin cells (Kulchitsky cells) found in the crypts of Lieberkuhn.
- These cells are capable of APUD (Amine precursor uptake and Decarboxylation) and can secrete vasoactive peptides.
- Carcinoid syndrome is seen in 40% of patients.
- Carcinoid in appendix is usually single. But commonly it causes luminal obstruction and so presents with features of appendicitis. Common site is at tip/distal 2/3.
- Small bowel carcinoids are multiple in 40% cases. In 50% of cases other primary malignancy is observed like of breast and colon.
- Small bowel carcinoids (jejuno-ileal) < 1 cm incidence, of nodal and liver spread is 20-30%. If it is 1-2 cm, nodal spread is 60-80% and spread to liver is 20%. If it is > 2 cm, nodal spread is more than 80% and spread to liver is 50%.

Types of Small Bowel Carcinoids

1. *Foregut carcinoids* (Bronchial, thymic, gastroduodenal, pancreatic): Produce low levels of serotonin.
2. *Midgut carcinoids* (Jejunal, ileal, appendiceal, right colic.): Secretes high levels of serotonin.
3. *Hindgut carcinoids* (Distal colon, rectum): Rarely produce serotonin, but produce somatostatin and peptide YY. They present as submucosal nodules without ulcer. Hormonally inactive.

Foregut carcinoids—argyrophillic (cells can be stained with metallic silver only in the presence of reducing agent)
Midgut carcinoids—argentaffin (stained with metallic silver without a reducing agent) and argyrophillic both.
Hindgut carcinoids—do not stain with silver



Fig. 21.30: Carcinoid of ileum. It often presents when liver secondaries develop as carcinoid syndrome. Resection and anastomosis is the treatment.

Features of Small Bowel Carcinoids

- Primary tumour is usually small < 1 cm.
- Age: Seen in 50-60 years.
- May be multicentric in small bowel – 40%.
- May coexist with synchronous adenocarcinoma of small or large bowel (10%).
- Highest propensity to metastasise to liver to produce carcinoid syndrome.

Clinical Features

- Most often asymptomatic—an incidental finding.
- May present with abdominal pain, features of intestinal obstruction.
- Hind gut carcinoids present with constipation, bleeding per rectum, rectal tenesmus.
- Once secondaries develop in the liver (which is yellowish) ***Carcinoid syndrome*** develops (40%), which is due to release of 5-HT, kinins, prostaglandins, histamine and indoles causing flushing, diarrhoea, cyanosis, asthmatic attacks, hepatomegaly, cardiac lesion on right side.
- *Attacks can be induced by alcohol.*

Investigations

- *Urine shows increased 5-hydroxyindoleacetic acid (5HIAA) levels. (Normal value—2-8 mg/24 hrs).*
- ^{111}In-octreotide scintigraphy to detect the tumour.
- CT scan is very useful for evaluation.
- I_{131} MIBG scan is also done.

Treatment

- If it is in the tip of the appendix (*tip is common*), appendicectomy and regular follow up with urine 5HIAA is sufficient.
- If it is in the base of appendix or appendicular lesion > 2 cm size or terminal ileum, right hemicolectomy is required.
- In small bowel, if the primary tumour is < 1 cm, with no lymph nodes, then segmental intestinal resection and anastomosis is sufficient. Radical resection of bowel is necessary in case of large, multiple carcinoids, with involvement of lymph nodes.
- In liver secondaries, along with surgical debulking hepatic resection, hepatic artery ligation or embolisation is tried.

Medical treatment

- Mainly symptomatic
- Long acting somatostatin analogue – octreotide can be given – 90% symptom palliation is achieved
- Others: Serotonin antagonists, antihistamines, alpha methyl dopa, 5-fluorouracil
- Bromocryptine, streptozocin, doxorubicin, dacarbazine, 5 FU, methylsergide, diphenoxylate hydrochloride, interferon α
- Radio-labelled somatostatin analogue
- Indium 111 labelled pentetreotide is also effective

Carcinoid Syndrome

- Occurs in 40% of carcinoid patients.
- Presentations are vasomotor, gastrointestinal, cardiac manifestations.
- It is due to release of vasoactive peptides like 5 HT, histamine, kallikrein, bradykinin, prostaglandins.
- Signifies advanced carcinoid or hepatic metastasis (tumour > 2 cm has 30% risk of metastasis).
- Presents with flushing, diarrhoea, bronchospasm, right valvular fibrosis.
- Flushing with erythema of face and trunk is 80% common.
- Symptoms are precipitated by intake of alcohol, cheese, chocolate, red wine.
- Severe bronchospasm, circulatory collapse, when not diagnosed can lead to ***'carcinoid crisis'*** for which octreotide 100 μg IV is the drug of choice.
- Treatment of hepatic secondaries by embolisation, chemotherapy, hepatic artery ligation or radiofrequency ablation.

Our senses don't deceive us; our judgement does.

Prognosis

- Prognosis is very good for carcinoid of appendix. 5 year survival is 90% and commonly appendiceal carcinoid is identified incidentally; they are commonly in the tip or distal 2/3 of the appendix; nodal spread and liver spread is rare; 75% are less than 1 cm. Two histological types of carcinoid *appendix are goblet cell and classical type*. Goblet cell type carries poor prognosis.
- Small bowel carcinoid has got poorer prognosis compared to carcinoid of appendix. Prognosis depends on size of primary tumour; nodal spread; multicentricity; hepatic spread. Carcinoid has better prognosis than adenocarcinoma of small bowel.

SHORT BOWEL SYNDROME

- It is the symptom complex after massive small bowel resection, i.e. resection ***more than 70% of the bowel.*** Minimum bowel required is 1.2 meters.
- Proximal jejunal resection is better tolerated than distal ileal resection.
- Ileum is more adaptive and has got capacity to increase the absorption capacity more efficiently. So in massive resections, patients with retained ileum will do better. Adaptation is better if ileum and caecum is preserved.

Causes

- Massive small bowel resection as in superior mesenteric artery ischaemia.
- Multiple sequential resections.
- Recurrent Crohn's disease—common cause.
- Necrotising enterocolitis in neonates and children.
- Intestinal atresia.
- Midgut volvulus.
- Radiation enteritis.

Adaptive changes in the retained small bowel

- Villous hypertrophy and hyperplasia
- Increased absorptive surface
- Increased capacity of small bowel
- Lower transit time of bowel content

Factors Deciding the Outcome in Short Gut Syndrome

- Age – Infants tolerate massive resection better.
- Retaining ileocaecal valve shows better outcome. Ileocaecal resection interrupts the enterohepatic circulation of bile salts which in colon get metabolised into secondary bile salts. Secondary bile salts block the absorption of water and electrolytes.
- Delayed clearance of gastrin causes hyperacidity and peptic ulcer.
- Adaptability of the small bowel. Adaptation is better if ileum and caecum are preserved.
- Additional colectomy increases the morbidity. In such occasion retained jejunum will function as either of two ways. *'Net absorbers'* have adequate absorption of water and sodium and usually will have more than 100 cm of retained jejunum. *'Net secretors'* have less than 100 cm of jejunum and lot of sodium and water are secreted into the lumen from plasma. These patients should avoid hypotonic solutions like water/tea; instead should take hypertonic saline with glucose containing 90 mmol sodium/L. WHO cholera fluid is ideal (contains 90 mmol sodium/L).

Clinical features

- Diarrhoea
- Fluid and electrolyte deficiency
- Severe malnutrition
- Recurrent bacterial enteritis

Outcome of Short Bowel Syndrome

- Severe malabsorption.
- Severe dehydration.
- Gallstone formation due to altered bile metabolism.
- Urinary calculi due to increased oxalate level.
- Water and electrolyte imbalance.
- Diarrhoea is common.
- Recurrent bacterial enteritis.
- Fulminant hepatic failure often can occur.

Treatment

Early phase

- Total parenteral nutrition.
- Fat and fibre free but protein rich liquid diet with essential fatty acids.
- Diarrhoea is controlled by loperamide/codeine phosphate.
- Oral cholestyramine to bind bile salts is needed in massive resection which includes ileum.
- Parenteral vitamin B_{12} injection regularly.
- H_2 antagonists/PPIs/somatostatin (to reduce secretions from stomach, liver and pancreas).
- Octreotide reduces the secretion and reduces GI motility.
- Fluid and electrolyte management.
- Control of diarrhoea.

Late phase

- Enteral nutrition to stimulate intestinal adaptation.
- TPN supplement—often permanently required.

Home parenteral nutrition is universally used method in western countries. But in Asian countries it is yet not practicable.

- Hormones and glutamine administration are under trial.
- Surgical techniques to delay the intestinal transit time or small bowel transplantation are under trial but with less success.
  - — *Reversal of 10 cm intestinal segment* to delay transit time.
  - — *Intestinal lengthening* to delay transit time and increase the absorption surface.
  - — *Small bowel transplantation.*

SMALL BOWEL ENEMA (Enteroclysis)

It is the contrast study of the small bowel by infusing contrast agent either high density micro-bar solution with methyl cellulose or water soluble iodine dye through Nolan intestinal tube.



Fig. 21.31: Enteroclysis X-ray film showing entire small bowel. It is still commonly used investigation to assess small bowel pathology.

Indications

- Small bowel tumours.
- Stricture small bowel.
- Congenital anomalies.
- Crohn's disease, intestinal tuberculosis.

Findings to Look for–

- Narrowing.
- Filling defects, irregular or regular.
- Mass lesions.

Problems

- Poor patient acceptance.
- Technically difficult.

CAPSULE ENDOSCOPY


Radiofrequency tag with polyimide coating
26 mm
×
11 mm
4 grams
Lactose body with 10% barium

Fig. 21.32: Capsule endoscopy – diagrammatic look.

- It is a type of endoscopy wherein highly sensitive miniature video-camera which after activation is swallowed by the patient. It is 26 mm × 11 mm in size. It weighs 4 grams.
- It contains single use video-camera, with 6 light emitting diodes, a lens, a colour camera chip, two batteries, radiofrequency transmitter with an antenna. Capsule takes 2 pictures per second which is transmitted to a worn recording device through radiofrequency. From the recording device data is downloaded to special computer.
- It is swallowed with 12 hours fasting.
- After activation it functions for 8 hours. It is mainly used to study small bowel diseases like vascular malformations, narrowing, tuberculoses, ulcers and tumours.
- This capsule camera sends signals and endopictures at regular intervals to the receiver (digital recorder) tied over the patient's waist.
- This receiver is later attached to specialised computer software to get different level pictures for study.
- Capsule gets deactivated in 8 hours and is passed out in the stool.
- It is available only at few centers and is costly.
- Capsule retention is the complication in 5% cases.
- It may not give proper evaluation in obstructive pathology and motility disorders of small bowel.

> *A man who does nothing never has time to do any thing.*

SMALL BOWEL ENTEROSCOPY

It is a difficult technique done to visualise the small bowel.

Indications

- Occult or obscure GI bleed. 5% of GI bleed is not diagnosed by any methods like gastroduodenoscopy, colonoscopy, contrast imaging. Angiodysplasia and ectasias are common causes for such type.
- Small bowel tumours.
- Crohn's disease.
- Celiac disease.
- Refractory sprue.
- HIV related small bowel diseases.
- Intraoperative enteroscopes to assess lumen on table.

Technique

Push Enteroscopy–

- It is easier and faster. It reaches 60 cm beyond the ligament of Treitz.
- Flexible enteroscopes or paediatric colonoscopes are used.
- Simethicone is given prior to enteroscopy.
- BT, CT, LFT and prothrombin time should be checked. Aspirin should be stopped 5 days prior if patient is taking it.
- Oesophageal overtube is used to pass the enteroscopes through upper GI.
- Enteroscopes is passed through overtube into stomach, duodenum, and jejunum. Proper evaluation of the mucosa is done during withdrawal. If there is a bleeder point, it is fulgurated.

Sonde Enteroscopy

- It is a 5 mm diameter, 275 cm enteroscope passed through nose by a piggyback technique with a paediatric colonoscope. Its two internal channels are for air inflation and for balloon inflation. Biopsy or working channel is not there.
- Scope is passed through pylorus and further it is moved with subsequent inflation of balloon and distal progression by peristalsis. Distal position is confirmed by fluoroscopy. It takes 6 hours to pass through the entire small bowel.
- Once it is in the terminal part of the small bowel, small bowel is inflated with air and mucosa is inspected.

Intraoperative Enteroscopy

- Abdomen is opened. By a small enterotomy scope is passed into the lumen. It is guided manually by compression and release to visualise entire mucosa of small bowel.

Complications and Problems

- Epistaxis due to nasal irritation.
- Perforation.
- Pancreatitis.
- Failure to pass enteroscopes as needed.
- Time consuming and not acceptable by the patient.

Self-assessment Questions

- Meckel's diverticulum.
- Surgical complications of typhoid.
- Regional enteritis.
- Carcinoid tumour.
- Short bowel syndrome.
- Small bowel tumours.
- Capsule endoscopy.
- Mesenteric ischaemia.

22

Large Intestine

Anatomy
Hirschsprung's disease
Diverticular disease of the colon
Ulcerative colitis
Ischaemic colitis
Pseudomembranous colitis
Surgical complications of intestinal amoebiasis
Tumours of colon: *Benign tumours of colon, carcinoma colon*
Angiodysplasia of colon
Ogilvie's syndrome
Colostomy
Stoma care
Faecal fistula
Preparation of large bowel for surgery
Barium enema

ANATOMY

- The colon (large intestine) is 135 cm long, and is divided into caecum, ascending colon, transverse colon, descending colon and sigmoid colon.
- The wall of the colon is composed of mucosa, submucosa, innercircular muscle layer and outer longitudinal muscle layer which, in turn, is concentrated into 3 separate longitudinal strips–*taeniae coli.*
- Small pockets of fat filled peritoneum—*appendices epiploicae* is scattered all over the colon except appendix, caecum and rectum.
- *Haustra* are sacculations between the taeniae.
- All the 3 above are important features of colon.
- *Ileocecal valve* serves as a sphincter to prevent the back reflux to terminal ileum.

Blood Supply

- Iliocolic, right colic, and middle colic arteries which are branches of superior mesenteric artery supply the colon from caecum to splenic flexure.
- Left colic, sigmoid, superior rectal arteries which are branches of inferior mesenteric artery supply the descending and sigmoid colon.
- The anastamotic arcade formed between the branches of superior and inferior mesenteric arteries is called *'arc of Riolan'*.


Marginal artery of Drummonds (Sudeck's)
Middle colic artery
Arc of Riolan
SMA
Principal LN
Intermediate LN
Epicolic LN
Right colic artery
Paracolic LN
Sudeck's critical point
Ileocolic artery
Superior rectal artery
Inferior mes. artery

Fig. 22.1: Arterial supply and lymphatic drainage of colon.

Once you learn to quit, it becomes a habit.

- Venous drainage occurs into superior mesenteric vein (which joins the splenic vein to form the portal vein) and inferior mesenteric vein (drains into the splenic vein).

Lymphatic Drainage

- Mucosa contains no lymph channels, so mucosal cancers rarely metastasize.
- Nodes are *epicolic* (located in the colonic wall), *paracolic* (located along the inner margin), *intermediate* (located near mesenteric vessels), *principal* (located near main mesenteric vessles).

Nerve Supply

- Colonic motility is under control of autonomic nervous system; parasympathetic via vagi and pelvic nerves, sympathetic via superior and inferior mesenteric ganglia.
- The effect of meal on colonic activity is termed as *gastrocolic reflex.*

HIRSCHSPRUNG'S DISEASE (CONGENITAL MEGACOLON)

> ***(My first specimen) is a colon, but a colon of such a size that it will no doubt surprise you to learn that it comes from a child only 11 months old when it died…. Only (the) rectum was not dilated, nor indeed subject to any obstruction.***
>
> **—Harald Hirschsprung,** 1888

- It is a congenital, familial condition, occurring in newborn due to the *absence of ganglion cells—Auerbach's* and *Meissner's plexus in anorectum*, which may extend proximally either a part or full length of the colon.
- It always involves the anus, internal sphincter and rectum (partly or entirely).
- There is narrow, spasmodic, non relaxing pathological segment.
- Transitional zone proximal to it contains only few ganglion cells with formation of cone.
- Still proximal to it, colon is dilated enormously with hyperaemia, multiple ulcers and hypertrophied circular muscle fibers.
- It is one of the causes of neonatal intestinal obstruction.
- Severe enterocolitis can occur which may be fatal. Perforation, peritonitis and septicaemia can occur.
- Often there will be a chronic course of the disease with malnutrition, abdominal distension.

Types

1. *Ultrashort segment HD*—Only anal canal and terminal rectum is aganglionic.



Fig. 22.2: Types of Hirschsprung's disease.

2. *Short-segment HD*—Anal canal and rectum is completely involved (80%).
3. *Long-segment HD*—Anal canal, rectum and part of the colon is involved (10%).
4. *Total colonic HD*—Anal canal, rectum and full length of the colon is involved - 10%.



Fig. 22.3: Zones in Hirschsprung's disease.



Fig. 22.4: Congenital megacolon showing spasmodic aganglionic segment, Coning (transitional zone), and proximal dilated normal ganglionic segment.



Fig. 22.5: Newborn with Hirschsprung's disease with intestinal obstruction (by Dr Vivek Prabhu MCh, Mangalore).



Fig. 22.6: Barium enema X-ray showing parts of congenital megacolon—spasmodic area, cone, proximal dilated segment.

It has got ***three zones***

I. *Distal immobile spastic segment,* i.e. aganglionic zone.
II. Proximal, *middle transitional zone* of about 1-5 cm length with less, sparse number of ganglions (*cone).*
III. A still more proximal, *hypertrophied dilated* segment is actually the normal ganglionic area.

Clinical Features

Presentations: Acute, recurrent, chronic.

- It is common in males (80%).
- Its incidence is 1 in 5000 live births.
- It is common in infants and children, occasionally it occurs in adults also.
- Often it is associated with Down's syndrome (10%). (Commonest association).
- In 90% of cases, symptoms appear in early neonatal period, i.e within three days of birth. *The child fails to pass meconium.* After introducing finger into the rectum, child passes *toothpaste like stool*, with evidence of straining. Distension of the abdomen with features of intestinal obstruction is seen.
- In children, there is passage of *goat pellet* like stools, malnutrition, abdominal distention - chronic type. Constipation, with history of passing stools once in 3-4 days with straining is seen throughout the childhood and also in adolescent period. Occasionally condition can cause intestinal obstruction.
- 10% familial.
- Gene mutation can occur in chromosome no. 10 commonly; occasionally in chromosome no. 13.
- ***Rectal examination*** shows tight sphincter with empty rectum. Child passes lot of gas and meconium.

Diagnosis

- History of failure of passing meconium.
- Plain X-ray abdomen—shows intestinal obstruction. Useful in case of perforation.
- Biopsy from all three zones to study the *ganglions and hypertrophic nerve terminals* in spasmodic segment. Starting from 2 cm above the dentate line, a full thickness rectal biopsy is ideal.
- ***Barium enema*** is done to look for the extent of disease and three zones. *Foley's catheter should not be used while doing barium enema in case of Hirschsprung's disease.*



Fig. 22.7: Barium enema X-ray showing features of Hirschsprung's disease in a newborn.

- ***Anorectal manometry***—shows the absence of recto-anal reflex in Hirschsprung's disease, which is diagnostic.
- *Acetylcholine esterase staining shows hypertrophied nerve bundles.*

Complications

- Colitis (Intramucosal gas in plain X-ray). Enterocolitis may be fulminant and fatal.
- Intestinal obstruction.
- Growth retardation.
- Constipation.
- Perforation.
- Peritonitis.
- Septicaemia.

Much wisdom often goes with fewer words.

Differential Diagnosis

- Total neuronal dysplasia
- Acquired megacolon - rectum is loaded with stool
- Ano-rectal malformations (ARM)
- Hypothyroidism
- Meconium plug syndrome

Treatment

- Initially, colostomy is done either transverse or transitional, so to have normal bowel function.
- Nutritional supplementation.
- Once the child attains 10 kg of weight, definitive procedure is done, i.e.
  a. Excision of aganglionic segment (spasmodic segment).
  b. Maintenance of continuity by doing coloanal anastomosis.
  c. Closure of colostomy later.

  Common procedures done are:
- *Modified Duhamel Operation*—resection of upper part of the rectum and a part of colon; anastomosis of colon to posterior part of the lower rectum and crushing the spurs to create the rectal pouch. It is *technically easier and a retro-rectal pull through*. New pouch is created by anterior part of the aganglionic rectum and by ganglionic proximal pulled down colon. Biopsy should be taken from proximal pulled down colon to look for evidence of ganglions. Pulled down proximal colon is sutured to full thickness posterior anal canal just above the dentate line. Spur between these two segments is crushed by Kocher's forceps or specialized instrument to create a single pouch.
- Soave's mucosectomy and pull through operation.
- Coloanal anastomosis after proctocolectomy.
- Total proctocolectomy with ileo-anal anastomosis in case of total colonic HD.
- *Swenson's operation*—through abdomino-anal approach, aganglionic segment is resected and colo-anal anastomosis is done.
- *Anorectal myectomy* is found to be very useful for ultra short segment and short segment Hirschsprung's disease. Mucosa in incised horizontally 1 cm proximal to mucocutaneous junction. A strip of muscularis with part of internal sphincter is excised with both muscle layers of the rectum for about 6-10 cm length. Mucosa is sutured back. Complications are abscess formation and failure.



Fig. 22.8: Modified Duhamel operation. Normal colon is brought behind the aganglionic rectum and anastomosed just above the dentate line.

Complications of surgery

a. Severe colitis
b. Faecal fistula
c. Stenosis
d. Stunted growth

Acquired megacolon

- No contracted segment in rectum
- Seen in children with faulty toilet training
- Rectum and sigmoid colon are dilated
- Normal ganglions in all levels
- Improper bowel habit causing chronic bowel dilatation
- Repeated enemas, manual evacuation, toilet training, educating the parents are required
- Should be differentiated from Hirschsprung's disease.

DIVERTICULAR DISEASE OF THE COLON

- They are acquired herniations of colonic mucosa through circular muscles at the points where blood vessels penetrate (points of least resistance).
- It is more commonly localised to *sigmoid colon (90%)* but occasionally seen in full length of the colon. *Rectum is not affected*.

Saint's triad (5%)

Diverticulitis
Hiatus hernia
Gallstones

- It is rare in Asian and African countries because of the high fibre diet. It is common in western countries.
- Colonic diverticulosis is usually of false type with only mucosal herniation.



Fig. 22.9: Diverticular disease of colon.

Aetiology

- Diet - It is the main factor. Less fibre diet increases the stool transit time, reduces the stool weight, reduces the bulkiness of stool which increases the intraluminal pressure and muscle hypertrophy. High fibre diet prevents this.
- Disease is more common in females. It is more common in aged.
- It is more common in non vegetarian than in vegetarian.
- NSAID intake by inhibiting prostaglandin synthesis may cause diverticular disease. It is more common in individuals with steroid therapy or immuno-compromised people.
- Smoking and alcohol.
- Long standing constipation increases the stool transit time and causes diverticulosis.



Fig. 22.10: Diagram showing the formation of diverticula. Note the difference between congenital and acquired diverticula.

Types

- ***Diverticulosis*** is the initial primary stage of the disease, wherein there is hypertrophy, muscular incoordination leading to increased segmentation and increased intraluminal pressure. At this stage they are asymptomatic, but often get severe spasmodic pain due to colonic segmentation called as *painful diverticular disease*.
- ***Diverticulitis*** is the second stage due to inflammation of one or more diverticula with pericolitis.It presents with persistent pain in left iliac fossa, fever, loose stool, recurrent constipation, tenderness in right iliac fossa, palpable and thickened sigmoid colon. P/R may reveal a tender mass.

Pathology

There is hypertrophy and thickening of the muscle layer with progressive colonic narrowing and segmentation with raised intraluminal pressure causing pulsion diverticula of only mucosa adjacent to taenia in antimesentric region. Pathology is common in sigmoid colon.

Features of Diverticular Disease

- In western countries 50% risk to develop diverticular disease for an individual is at the age of 60 yrs. Only 15% of patients with diverticulosis develop diverticulitis. 75% of patients with diverticulitis have uncomplicated course with features of only diverticulitis. 25% of patients with diverticulitis develop complications like abscess, perforation, stenosis and fistula. Abscess can be commonly pericolic and pelvic, rarely in buttock and ischiorectal fossa.
- Features of diverticulosis – Fullness of abdomen, bloating, flatulence, vague discomfort.
- Features of diverticulitis – Pain in left iliac fossa which is constant radiates to back and groin, tenderness, bloody stool, often massive haemorrhage, fever, rigidity and mass in left iliac fossa. Mass is usually tender, firm, resonant, nonmobile.
- Features of fistula – Colo vesical is the commonest type of fistula. It causes passage of gas in the urine (*pneumaturia*) commonly and occasionally feces.

Complications of diverticulitis

- Perforation and pericolic abscess or peritonitis
- Progressive stenosis and intestinal obstruction
- Profuse colonic haemorrhage (17-20%)
- Fistula formation (5%)—vesicocolic, vaginocolic, enterocolic, colocutaneous

The eyes sees only what the mind is prepared to comprehend.



Fig. 22.11: Sigmoid diverticula causing pericolic abscess as a known complication.



Fig. 22.12: Diverticular disease causing colo-vesical fistula. Patient will have urine stained with faecal matter and severe urinary infection. Contrast dye study, CT scan is required. Initial colostomy and ureterostomy as diversion is required before definitive procedure.

Note: Diverticulitis is not a precancerous condition.

It may co-exist with malignancy, irritable bowel syndrome, Crohn's disease.

Hinchey's classification of diverticulitis

Stage I: Pericolic or mesenteric abscess
Stage II: Walled off pelvic abscess
Stage III: Generalised purulent peritonitis
Stage IV: Generalised faecal peritonitis

Investigations

- Barium enema (best method to diagnose) shows *'saw-teeth'* appearance. *Champagne glass sign*—Partial filling of diverticula by barium with stercolith inside—seen in sigmoid diverticula.
- *Sigmoidoscopy* is useful but should not be done in acute stage. Once acute stage subsides, barium enema, sigmoidoscopy, colonoscopy can be done (To rule out associated malignancy).



Fig. 22.13: Colonoscopic view of sigmoid diverticula.

- CT scan in acute phase to see pericolic abscess. CT scan shows thickening of muscle layer, abscess, perforation, fistula, involvement of organs like urinary bladder and associated pathology. CT is the ideal investigation.

Differential Diagnosis

- Carcinoma sigmoid colon.
- Amoebic colitis, ulcerative colitis, ischaemic colitis and Crohn's disease.
- Tuberculosis.

Coexistence of carcinoma and diverticulitis can occur in 12% of cases.

Treatment

Medical treatment

- High fibre diet
- Antibiotics
- Bulk purgatives
- Avoid constipation
- Regular follow-up of the progress of disease and onset of complications
- Abscess can be drained by CT guided aspiration or percutaneous drainage tube

- In acute stages, conservative treatment like bowel rest, antispasmodics, antibiotics are advised.
- Later, surgery is required. *Resection of sigmoid colon and anastomosis (colorectal) is done.*


Resection and primary anastomosis
Part resected

Fig. 22.14: Resection and primary anastomosis can be done in sigmoid diverticula after proper bowel preparation electively.

- If colon is loaded wth faecal matter, initially a transverse colostomy is done. Then resection and anastomosis; later colostomy closure is done as a staged procedure.


Diversion loop colostomy
Resection
Primary anastomosis
Part resected

Fig. 22.15: Resection of sigmoid colon for sigmoid diverticula with primary anastomosis and defunctioning diversion colostomy.

- In case of perforation, proximal colostomy and exteriorisation of the affected bowel with later resection and anastomosis is done as it has high mortality.


Resection
End colostomy
Mucus fistula
Part resected

Fig. 22.16: Resection and formation of end colostomy and mucus fistula for acute sigmoid diverticulitis.

- Occasionally, Hartmann's procedure (combination of sigmoidectomy, end colostomy and closure of rectal stump) is better and life saving.


Sigmoidectomy end colostomy
Closure of rectal stump
Part resected

Fig. 22.17: Hartmanns operation for acute diverticulitis with sepsis/perforation/peritonitis. Here after resection proximal colon is exteriorised as end colostomy. Distal rectal stump is closed.

- Fistulas are treated by resection of the diseased bowel and closure of the fistula along with diversion procedures like colostomy, cystostomy, ureterostomy.
- In certain cases of diverticulosis, a longitudinal incision through the taenia and muscular layer without opening the mucosa is sufficient (like Heller's/Ramstedt's myotomy)—*Reilly's sigmoid myotomy*.

The best doctors in the world are—Doctor Diet, Doctor Quiet and Doctor Merryman.—Jonathan Swift

Note:

- It is basically **a benign condition**, therefore the prognosis is good. High fibre diet is advised.
- Complications like *perforations, fistulas are dangerous and life threatening*.
- Right sided diverticulum in the caecum and ascending colon is usually solitary and congenital.

Myotomy

- Heller's myotomy—Achalasia cardia
- Ramstedt's myotomy—Congenital pyloric stenosis
- Reilly's myotomy—Diverticulosis

ULCERATIVE COLITIS

- It is an inflammatory condition of rectum and colon of unknown aetiology perhaps related to stress, westernized diet, autoimmune factor, familial tendency, allergic factor.
- Disease commonly starts in the *rectum*, spreads proximally to the colon and often into the ileum as ***back wash ileitis*** (5%).

Aetiological Factors

- Westernized diet, red meat; less common in vegetarians.
- Defective mucin production in the colonic mucosa and mucosal immunological reaction.
- Autoimmune factors - Cytotoxic T lymphocytes against colonic epithelial cells and presence of anticolon antibodies. Association with HLA DR2 is observed in ulcerative colitis.
- Appendicectomy and smoking protects ulcerative colitis especially from extraintestinal features and from postoperative complications.
- Familial in nature.
- Allergy to milk (cow milk) and other dietary factors.
- Excess reactive oxidative metabolism in ulcerative colitis.
- Psychological aspects, stress, life style, personality disorders.

Pathology

To begin with, multiple minute ulcers (*pin point ulcers*) occur with proctitis and colitis

↓

These ulcers extend into the deeper layer

↓

Spasm of the bowel

↓

Stricture of the colon

↓

Permanently contracted colon (*pipe stem colon*)

↓

In between ulcers, epithelial thickening occurs which appears like polyps

↓

Pseudopolyposis.

- It is a disease confined to mucosa and submucosa.
- There is no bowel wall thickening and no granuloma formation.
- There are no skip lesions. Rectum is always involved. Distal bowel is involved to begin with, then spreads proximally. Distal involvement is more severe. Entire colon including caecum and appendix may be involved.
- Only rectum involvement, as proctitis occurs in 25% cases. Such patients will have 5% risk of developing rectal cancer. In 15% cases it is left sided ulcerative colitis presenting with severe recurrent diarrhoea. In 25% patients, total proctocolitis is the presentation. Bloody diarrhoea, malnutrition, complications like toxic megacolon, perforation (steroid may mask the features) and carcinoma are common here.
- Pseudopolyps are of inflammatory in nature. Absence of normal mucosa between these pseudopolyps is important to differentiate it from neoplastic polyps.
- Intense inflammation in the ***mucosa and submucosa*** with typical feature like –
  - *Multiple crypt abscesses*
  - *Sparing of the deeper layers* of the colonic wall
  - Inflammatory *pseudopolyps*
  - Multiple *pin point ulcers*
  - Increase in *substance p containing nerve fibres*
  - *Lymphoid hyperplasia* in mucosa and submucosa (25%)
  - Presence of *anti neutrophil cytoplasmic antibodies* with a perinuclear staining pattern (86%)
  - Decreased goblet cell mucin
- Only in **toxic megacolon** (1.5 – 2.5%) there is acute inflammation extending to entire thickness of the colonic wall including the serosa. It is not the colon that is toxic but it is the patient who is toxic hence the name. It is precipitated by non specific causes, during barium enema study, due to drugs like opiates, antidiarrhoeal drugs and anticholinergics. Toxic megacolon commonly affects the *transverse colon* which will be more than 6 cm in diameter. Left colon or entire colon also may be involved. Caecum when rarely involved; becomes more than 10 cm in diameter. Colon will be like *wet blotting paper*. It is prone for perforation, peritonitis which carries high mortality (25-50%). C reactive protein will be increased. It needs emergency laparotomy with total

colectomy/proctocolectomy with ileostomy. Occasionally toxic megacolon can occur in pseudomembranous colitis, amoebic colitis or typhoid colitis.
- **Carcinoma in ulcerative colitis** is more prevalent than in Crohn's disease.

Factors involved are –
- *Extent* of involvement (more in total colonic).
- *Duration* of the disease; *continuous active disease* than intermittent disease.
- Incidence is 5% when duration is 15 years; 25% in 25 years; 35% in 30 years; 45% in 35 years; 65% in 40 years.
- Incidence of developing cancer in left sided colitis is 10 years later than universal ulcerative colitis.
- Incidence of carcinoma developing in ulcerative colitis is *equal* in both sexes.
- Carcinoma in ulcerative colitis is commonly *aggressive and poorly differentiated, multicentric, synchronous, infiltrative and scirrhous;* half the patients will have colloid carcinoma (signet ring), more advanced at the time of presentation, *dysplasia* developing into cancer is common.
- Ulcerative colitis with primary sclerosing cholangitis has still increased risk of developing cancer.
- In ulcerative colitis, dysplasia is very important factor to transform into carcinoma. It may be mild, moderate or marked. It is often called as *dysplasia associated lesion or mass* (DALM).



Fig. 22.18: Multiple pseudopolyposis involving entire colon in ulcerative colitis. Disease involves only mucosa and submucosa.

Clinical Features

Disease usually begins in rectum as **proctitis** later becomes **left sided colitis** and eventually causes severe **total proctocolitis.**

- More common in females (2:1), begins in 3rd decade.
- Watery diarrhoea, mucus or blood stained discharge per rectum.
- Colicky pain, spasms.
- Decreased appetite and loss of weight.
- Relapses and remissions at regular intervals.

Clinical grading of ulcerative colitis

	Mild	*Moderate*	*Severe*
Stool frequency	< 4	4-6	> 6
Pulse	< 90	90-100	>100
Haematocrit	Normal	30-40	< 30
Weight loss in %	None	1-10%	> 10%
Temperature	Normal	99-100	> 100
ESR	< 20	20-30	> 30
Albumin	Normal	3-3.5	< 3.5

Two types of *presentations*

a. ***Fulminant type,*** 5% common
   - It is a severe form, with continuous diarrhoea with passage of blood, mucus and pus.
   - Patient is ill and dehydrated.
   - Mimics fulminant amoebic colitis; severe typhoid and dysentery.
   - Fever, hypokalaemia, acidosis, dehydration and shock.
   - Abdominal distension occurs.
   - *Acute toxic dilatation* (1.5%) of *transverse colon* may occur where in the diameter of transverse colon > 6 cm. It has high mortality and requires *emergency surgery,* i.e. either colostomy or resection with ileostomy and later ileo-anal anastomosis. Here colon is like *wet blotting paper*.

b. ***Chronic type*** (95%):
   - Lasts for months to years with diarrhoea, blood loss, anaemia, invalidism, abdominal discomfort and pain.
   - Severe malnutrition and hypoproteinaemia.

Investigations

- *Barium enema*—shows loss of haustrations, narrow contracted colon *(hose pipe colon)*, mucosal changes, pseudo polyps. *It is avoided in fulminant cases.*
- *Sigmoidoscopy and biopsy.*
- *Colonoscopy* is also required.

Hard work doesn't guarentee success, but improves its chances.



Figs 22.19A and B: Colonoscopic view of ulcerative colitis and multiple ulcers.

Due to very high incidence of malignant transformation in ulcerative colitis (10-20%), multiple biopsies should be taken from suspected areas of the colon. Risk increases with age of the patient and duration of the disease (20%).

Sigmoidoscopic grading of ulcerative colitis

0—Normal mucosa
1—Loss of vascular pattern
2—Granular, non-friable mucosa
3—Friability on rubbing
4—Spontaneous bleeding, ulcerations

- Plain X-ray abdomen is useful in obstruction, toxic megacolon, perforation.
- C reactive protein will be very high in acute phase.

Differential diagnosis

- Crohn's disease
- Ischaemic colitis
- Irritable bowel syndrome
- Amoebic colitis
- Bacillary dysentery
- Carcinoma colon

Differences between Crohn‘s disease and ulcerative colitis

Crohn‘s disease	*Ulcerative colitis*
• It affects ileum and often colon but can involve any part of GIT – rectal sparing is common	• It affects rectum and colon from distal to proximal
• Full thickness – transmural disease	• It affects mucosa and submucosa – not deeper
• Skip lesions are typical	• Skip lesions are not observed
• Granulomatous lesion on histology – deep ulcers; pseudopolyps are not found	• Not a granulomatous lesion – superficial ulcers, pseudopolyps are present
• Stricture and fistula are common	• Narrowing can occur but not very common
• Anal fissure and perianal abscess are more common	• Fissure and perianal disease can occur but not as common as in Crohn's disease
• May mimic appendicitis	• Will not mimic appendicitis
• Bleeding is not common	• Bleeding is common
• Fever is common	• Fever is uncommon
• Mass in RIF is common	• Mass is not a common feature
• Anal pathology very common	• Anal pathology is rare
• Discontinuous segmental asymmetrical colitis	• Continuous mucosal disease – colitis
• Toxic megacolon is rare	• Toxic megacolon is common
• Normal vascular pattern	• Distorted vascular pattern
• Fistula is very common	• Fistula in uncommon
• Recurrence is common after resection	• Total proctocolectomy cures the disease

Complications

GIT

- Pseudopolyposis
- Turning into malignancy
- Stricture formation, commonly in recto sigmoid and anal canal – 10%
- Toxic megacolon in transverse colon
- Massive haemorrhage 1%
- Fistula in ano – 20%
- Perforation – 10-20%

Extraintestinal

- Severe malnutrition
- Liver cirrhosis (50%)
- Skin lesions - pyoderma, erythema nodosum
- Arthritis, iritis, ankylosing spondylitis - common
- Sclerosing cholangitis, carcinoma of bile duct

Treatment

General:

- Correction of anaemia.
- Fluid and electrolyte supplimentation.
- Nutrition (high protein, carbohydrate, vitamin, but low fat diet), TPN.
- Sedatives and tranquillisers.
- Psychological counselling.

Drugs:

In active disease drugs are used to *induce remission*. Later drugs also should be given for *maintenance* of remission and to prevent relapses.

- Salazopyrine/sulfasalazine splits into 5 amino-salicylic acid and sulphapyridine in colon. It is used as *first line therapy*. Its dose is 2 - 4 gm/day. It is mainly used to induce remission. It suppresses PG E1 and PG E2 to reduce the inflammation, inhibits proteolytic enzymes and also causes immuno-suppression. 5 ASA is the most active ingredient. Side effects are skin rashes, bone marrow suppression, folic acid deficiency, haemolysis in glucose 6 phosphate dehydrogenase deficiency patients, temporary fertility problems in men.
- 5 ASA (Mesalamine) is also used in active disease as *first line therapy*. It is used with an azo bond to prevent its absorption in small bowel. Its induction of remission is same as sulfasalazine. Idiosyncrasy and temporary infertility is not present in mesalamine. Its *oral* dose is 2-4 gm/day. It is also used as *retention enema* which is better than steroid enema in left sided ulcerative colitis/proctitis. But mesalamine enema (4 gm in 100 ml saline) is costly. Enema is combined with oral mesalamine or oral steroid in acute cases. Mesalamine 500 mg *suppository* is also used in BID doses. Daily oral (1.6 gm) and topical 4 gm enema, twice weekly is often used for maintenance therapy. Headache, dyspepsia and myocarditis are the complications.
- Steroids are used in cases where salazopyrine fail to induce remission. It is a drug for *refractory cases*. Oral Prednisolone 60 mg/day tapering in 4 weeks is the dose. Intravenous hydrocortisone 100 mg 8th hourly is used in acute cases. 100 mg hydrocortisone enema/ 40 mg methylprednisolone enema (steroid retention enema) are used for 2 weeks in acute active diseases. Most patients with moderate to severe disease need steroid therapy.
- Immunomodulators are used often to induce remission and for maintenance. Azathioprine and 6-mercaptopurine are used. They act at DNA level (purine ribonucleotide) and inhibit lymphocyte function (of T cells). But this action is slow.
- Cyclosporin is used in refractory, fulminant severe ulcerative colitis as a reserve drug. Dose is 4 mg/kg/ day IV.
- Mebeverine HCl and Tegaserod (6 mg) are the other drugs used in ulcerative colitis. Other measures are using sucralfate, short chain fatty acids, probiotics, antidiarrhoeal drugs (diphenoxylate, loperamide, codeine), avoiding milk products, fibre, fruits.
- Antitumour necrosis factor alpha – Infliximab is also used selectively (in some studies).
- Newer drugs with a targeted delivery into the colon is used nowadays. *E.g.*: Olsalazine (azobond); Balsalazine (4 aminobenzoyl carrier).



Fig. 22.20: Different pouches are used after restorative proctocolectomy and during ileoanal anastomosis. Pouch acts as reservoir and reduces the frequency of stool. It avoids ileostomy with natural stool passage with continence. Pouchitis can occur with diarrhoea, blood in stool, perianal pain. Occasionally redoing or conversion may be required. J type is commonly used.

Management of severe ulcerative colitis

- It is more than 6 stools per day, with cramping pain, toxicity, fever, raised ESR, anaemia, tachycardia, more than 10% weight loss, hypoalbuminaemia less than 3.5 gm%
- It always needs hospitalisation
- IV corticosteroids [hydrocortisone] 300 mg/day/ oral Prednisolone/5 ASA orally or as enema
- IV cyclosporine with azathioprine or 6 mercapto-purine
- Fluid and electrolyte management
- TPN/enteral nutrition
- Proper monitoring of the patient for complications
- Surgery

Indications for Surgery—30% cases

- Intractability – commonest indication
- Toxic dilatation
- Perforation

God gives every bird its food, but he does not throw it into the nest.

- Haemorrhage
- Risk of malignant transformation, dysplasia (DALM)
- Onset at early age
- Chronic invalidism
- Progressive disease with stricture, abscess, fistulae
- Steroid dependency, persistent active disease
- Malignancy
- Severe extraintestinal manifestations
- Growth retardation in children

Toxic megacolon

- 1.5% incidence
- Common in transverse colon
- Colon is more than 6 cm in diameter
- Colon is like wet blotting paper
- Commonly seen in ulcerative colitis
- Can occur in bacterial colitis, pseudomembranous colitis, fulminant amoebic colitis
- May be precipitated by antidiarrhoeal drugs
- Emergency surgery, colectomy, colostomy/ileostomy may be required
- IV fluids, blood transfusion, antibiotics, steroids are also needed
- Can be life threatening
- Plain X-ray is very useful



Figs 22.21A and B: Diagrammatic representation of ileostomy after total proctocolectomy.

Surgeries

1. *Total proctocolectomy with ileo-anal anastomosis with pouches as reservoir* ("J', 'S', or "W' pouches).
2 Total proctocolectomy with ileostomy (permanent, continent Kock's ileostomy, with one way valve is done).
3. *Total colectomy* with colorectal anastomosis. Proper follow-up at regular intervals by regular sigmoidoscopy evaluation should be done as rectum is also diseased and vulnerable for complications.
4. Total colectomy with rectal mucosectomy and anastomosis above the dentate line on posterior aspect is also occasionally used.

ILEOSTOMY

It is usually end ileostomy. But often loop ileostomy is also done

Indications

- After total proctocolectomy for ulcerative colitis, total colonic Hirschsprung's diseases, Crohn's disease (occasionally), and total colectomy for carcinomas
- Loop ileostomy is done in critically ill patient with acute ileal conditions like multiple ileal perforations, ileal gangrene or distal fistulas or sepsis. It is temporary ileostomy.
- **Ileostomy** is placed in right iliac fossa lateral to right rectus muscle.
- Ileostomy may be temporary (loop) or permanent (end)
- Brooke's classic end non continent ileostomy or Koch's continent ileostomy (with continent intra abdominal pouch) are used
- Ileum should project as a spout at least 4 cm above the skin surface, which facilitates the effluent to pass directly into the bag
- Ileostomy usually acts in 48 hours
- Ileostomy bag, ileostomy care, nutrition and electrolyte management are important.
- **Complications** like prolapse, stenosis, haemorrhage, retraction can occur

Complications of Surgery for Ulcerative Colitis

- Pouchitis (20%) with pain, diarrhoea, fever, bleeding, toxicity, pouch – vaginal fistula, foecal incontinence (5%). Pouchitis disease activity scoring index is at present used which is based on clinical, endoscopic and histological inflammatory features.
- Stenosis, pelvic abscess formation.
- Leak, fistula formation.
- Problems with ileostomy – psychological trauma, skin excoriation, retraction, stenosis (25%), prolapse, bleeding, enteritis, ileal necrosis, ileal volvulus, paraileostomy hernia, paraileostomy abscess.

- Sexual dysfunction following proctocolectomy by nerve injury.
- Persistent perineal sinus after total proctocolectomy.
- Risk of cancer persists if only total colectomy is done.

ISCHAEMIC COLITIS

It occurs in **splenic flexure** where blood supply is precarious. Splenic flexure is the *water shed* area of colon, receiving blood supply from terminal branches of superior and inferior mesenteric arteries.

- Ischaemic colitis is common in females; common in aged.
- It is related to atherosclerosis, emboli, vasculitis, diabetes, chronic renal failure, autoimmune diseases, polycythaemia, haemodialysis, etc.
- *Water shed point* – Griffith's point in artery of Riolan gets poor perfusion by arterial disease/low perfusion pressure/altered viscosity causing ischaemic colitis.

Types (Marston's Classification)

1. Gangrenous type.
2. Stricture type.
3. Transient type.

Clinical Features

- Pain in left iliac fossa and left hypochondrium.
- Vomiting.
- Passing blood in the stool.

Differential Diagnosis

- CA colon.
- Ulcerative colitis.
- Crohn's disease.
- Tuberculosis.



Fig. 22.22: Ischaemic colitis in splenic flexure.

Investigation

- Barium enema is diagnostic (*Thumb-print sign*).
- Colonoscopy is done in all, other than gangrenous type (which needs emergency laparotomy).

Treatment

- Laparotomy and resection of splenic flexure and anastomosis.

PSEUDOMEMBRANOUS COLITIS

- It is an acute diarrhoea due to toxins produced by the overgrowth of *Clostridium difficile* after antibiotic therapy (usually after clindamycin).
- *Clostridium difficile* is a Gram positive, anaerobic, spore forming bacillus. It produces toxin A (enterotoxin) and toxin B (cytotoxin, more potent).
- It is also often seen in immunocompromised patients and patients who are on cancer chemotherapy.
- Incidence is 2%. Mortality is 30%.
- Stool cytotoxin assay is highly sensitive and specific. ELISA test for toxins is also useful.
- Colonoscopy is ideal as right side involvement is more common.
- It can occur up to 6 weeks after stopping the drug.
- Diarrhoea, toxaemia, perforation, haemorrhage also can occur.

Treatment

- IV Vancomycin 500 mg 8th hourly.
- IV Metronidazole 8th hourly.

SURGICAL COMPLICATIONS OF INTESTINAL AMOEBIASIS

Trophozoites of *Entamoeba histolytica* by digesting mucosa, submucosa of *rectosigmoid* (75%) region commonly or *ileocaecal* region of the colon, causes *retort shaped amoebic ulcers* which exudes blood, pus and necrotic material.

- Cyst is the infective agent. It enters through faeco oral route. It forms trophozoite which multiplies and causes inflammation and *flask shaped ulcers* in the rectosigmoid, caecal and often in the terminal ileal region.
- It causes blood with mucus diarrhoea, toxaemia, secondary bacterial infection, fulminant colitis, perforation and peritonitis, rarely toxic megacolon, extraintestinal amoebiasis.

Children, like animals use all their senses to discover the world.

- Amoebic liver abscess is the *commonest form* of extraintestinal amoebiasis. Others are cutaneous amoebiasis, amoebic empyema, and very rarely amoebic brain abscess, amoebic pericarditis.
- *Chronic amoebiasis* causes vague abdominal pain, decreased appetite, intestinal colic and psychological trauma to the patient.



Fig. 22.23: Amoebic ulcer is common in left side (sigmoid colon). Amoeboma can occur in caecal region where it forms granuloma in pericolic area presenting as mass abdomen. Amoebic ulcers are classically flask/retort shaped.

Presentations

1. *Amoebic dysentery* with diarrhoea, colicky pain, tenderness in left iliac fossa (in" *Sir Philip Manson-Bahr amoebic point*').
2. *Amoebic typhlitis* (inflammation of caecum) presentation with pain and tenderness in right iliac fossa and often also as a *mass in the right iliac fossa mimicking carcinoma caecum* called as ***amoeboma*** (amoebic granuloma) (1.5%).

Differential diagnosis for amoeboma

- Appendicular mass
- Ileocaecal tuberculosis
- Carcinoma colon
- Retroperitoneal tumour
- Lymph node mass.

- Perforation can occur in recto sigmoid or caecal area leading to peritonitis.
- Stricture in the rectum and colon.
- Intestinal obstruction.
- Paracolic abscess.
- Pericolic abscess.
- Ischiorectal abscess and fistula formation.
- Massive bleeding per anum, but rare.
- Amoebic liver abscess formation.

3. *Acute fulminant amoebic colitis* is a severe type with sloughing of colonic and rectal mucosa causing torrential bleeding, toxicity which can be life-threatening.

Investigations for intestinal amoebiasis

- Saline wet mount of fresh stool—trophozoites in 90% cases
- Serology—indirect haemagglutination test
- PCR
- P/R and proctoscopy

Complications of amoebic colitis

- *Amoeboma*—right side common
- Perforation, bleeding, peritonitis
- Stricture rectum and colon
- Obstruction
- Pericolic, ischiorectal abscess and fistula formation
- Amoebic typhlitis, amoebic liver abscess

Treatment

- In acute cases, hospitalization and proper rehydration is done.
- Antispasmodics to alleviate pain is given.
- Metronidazole IV or metronidazole retention enema is given. It is very effective in both intestinal and extraintestinal amoebiasis.
- In less severe disease, tab metronidazole (400 mg – 800 mg) 3 times daily is given for 10 days or tab tinidazole 2 gm daily for 3 days.
- Diloxanide furoate is very effective in chronic amoebiasis and cyst passers. Dose is 500 mg, 3 times daily for 10 days.
- Other drugs used are – paromomycin, iodoquinol.

TUMOURS OF COLON

BENIGN TUMOURS/POLYP OF THE COLON

Polyp is a tumour/swelling arising from mucosal surface with a pedicle/stalk. '*Poly*' means many; '*pous*' means foot in Greek.

POLYPS

Inflammatory	*Hyperplastic*	*Hamartomatous*	*Neoplastic*
• Ulcerative colitis • Segmental colitis • Dysenteric colitis • Crohn's disease • Diverticulitis	(Metaplastic)	• Peutz-Jegher syndrome • Juvenile polyp • Cronkhite – Canada syndrome	Adenomatous — Tubular — Tubulovillous — Villous Malignant (Carcinomatous)

Classification

Inflammatory

- Ulcerative colitis.
- Segmental colitis.
- Crohn's disease.
- Diverticulitis.
- Dysenteric colitis.

Hyperplastic (Metaplastic)

- Also called as metaplastic mucosal polyps.

Hamartomatous

- Peutz-Jegher's syndrome.
- Juvenile polyp.
- Cronkhite – Canada syndrome.

Neoplastic

- Tubular-pedunculated.
- Villous – sessile.
- Tubulo-villous.
- FAP- familial adenomatous polyposis.

Others

- Lipoma, haemangioma, leiomyoma.

Juvenile Polyps

- *Commonest* polyp of colorectum in *infants and children.*
- Can cause intussusception, prolapse through rectum, bleeding.
- Colonoscopic polypectomy is done.
- Not a pre-malignant condition.

Metaplastic/hyperplastic Polyp

- Metaplastic- indicates a difference in appearance from normal mucosa.
- Very minute in size- 1-2 mm. Multiple.
- Common in rectum. Also occurs in other parts of colon.
- Contains columnar epithelium, cystic dilatation, goblet cells, and lymphocytes.
- Not a pre-malignant entity.

PEUTZ-JEGHER'S POLYP

- It is common in *small intestine* (jejunum) but can also occur in large intestine.
- ***Features*** are multiple, familial, hamartomatous intestinal polyps.
- Asssociated with melaenosis of the oral mucosa, lips (lower lip) and occasionally digits (not in tongue).
- Microscopically it contains tree like branching filaments of mucosa with smooth muscle wall.
- It can occasionally turn into malignancy.

Complications

Bleeding or intussusception, when occurs requires surgery either resection—anastomosis or colonoscopic removal.

ADENOMA OF COLON

- It can be *tubular, villous, tubulovillous* (Histologically). Tubular is the commonest—70%.
- It also can be *solitary or multiple*, sessile or pedunculated.
- Tubular is commonly 1-2 mm sized and sessile is 3-4 mm sized.
- ***It has malignant potential***.

  Potentiality increase with
  - *Size, is an important factor* in causing carcinoma. If size of adenoma is > 2 cm –30 - 50% chances of developing carcinoma; 1-2 cm —10% chances of carcinoma; < 1 cm —1% chances of carcinoma.

Self-respect — that a corner stone of all virtue.



Fig. 22.24: Colonoscopic view of colonic polyp.

  - Sessile nature.
  - Villous architecture.
  - Dysplasia.

Grading of adenoma

I- Minimal hyperplasia, no cellular atypia
II- Mild hyperplasia, cellular atypia
III- Moderate hyperplasia, cellular atypia
IV- Severe hyperplasia, cellular atypia
V- Carcinoma- *in situ*

Features of Adenoma

- Can be asymptomatic.
- Bleeding per anum is usually chronic but rarely can be acute.
- Anaemia.
- Prolapse—common in tubular type.
- Diarrhoea common in villous type; mucus discharge.
- Tenesmus, colicky abdominal pain.
- Spurious diarrhoea.
- Poor general health.
- Electrolyte imbalance – *hypokalaemia.*
- Per-rectal examination should be done to feel the adenoma/polyp.
- Carcinomatous changes.

Investigations

- Serum electrolytes.
- *Barium enema* study-shows filling defect – usually multiple.
- *Colonoscopy – biopsy is a must.*
  - Size should be noted.
  - Texture- harder tumour more likely to be malignant.
  - Colour of the lesion -pale is benign, pink, red and active – could be carcinoma.
  - Ulceration on the surface if it has turned into malignancy.

Treatment

- Colonoscopic polypectomy using snare. Any adenoma more than 5 mm in size should be removed colonoscopically.
- Diathermy excision/coagulation with sigmoidoscope.
- Per-anal polypectomy.
- Per-anal excision with clear margin of the rectal sessile adenoma.
- Open-abdominal colotomy and polypectomy in case of huge adenoma.
- Segmental resection of the colon if polyps/adenomas are limited to one segment of the colon confirmed by colonoscopy.
- Total colectomy/proctocolectomy if multiple polyps present all over colorectum and if associated with FAP.
- Blood transfusions, correction of electrolytes, protein supplements.

Problems in therapeutic colonoscopy

- Perforation due to necrosis
- Haemorrhage- secondary
- Intracolonic explosions
- Sepsis

FAMILIAL ADENOMATOUS POLYP (FAP)

- It is inherited as an autosomal dominant neoplastic condition (chromosome no. 5).
- It presents in younger age group—15-20 years.
- Incidence is equal in both sex, involving commonly the large intestine but can also occur in stomach, duodenum and small intestine.
- It is familial with a *high potential for malignant transformation*. If there is no adenoma at the age of 30 years, then it is not FAP of colon.
- It can be associated with duodenal or ampullary carcinomas , *Gardner's syndrome* (Desmoid tumour in the abdomen, osteomas (75%) and epidermoid cysts) and also *Turcot"s syndrome* (FAP + brain tumour (medulloblastoma or gliomas)) or sarcoma of bone.
- Usually multiple (over 100).
- Presents with lower abdominal pain, loose stools with blood and mucus, weight loss.



Figs 22.25A to C: Multiple polyps extensively involving the colon.

Investigations

- Double contrast barium enema.
- Colonoscopic biopsy.



Fig. 22.26: Colonoscopic view of polyp colon in two different patients.

- Screening of *all the members of the family is a must*.

  Pigment spots in retina (CHIRPES) and DNA tests for FAP are good screening methods, but cost and availability limits its use.

Treatment

1. *Proctocolectomy with ileoanal anastomosis with ileal pouch* is commonly done.
2. Alternatively a conservative *total colectomy* with ileo rectal anastamosis can be done, but with a regular follow-up with sigmoidoscopy for any *rectal polyps*. If present *snaring of polyps* should be done.

Sulindac (NSAID) 300 mg BD/*aspirin* 325 mg OD is given to these patients, causes disappearance of polyps in the rectum.

GARDNER'S SYNDROME

- It is commonly associated with FAP – 10%.
- Presents with bone, skin, soft tissue and dental abnormalities. Jaw osteomas are very common. Other features are epidermoid cysts (50%), exostoses, fibromas, lipomas.

- Associated with desmoid tumours seen in the scar, abdomen, intraabdominal region and mesenteric fibromatosis.
- Congenital hypertrophy of pigment layer of retina (seen as pigment spots)—commonly seen.
- Often associated with MEN IIb syndrome.

TURCOT'S SYNDROME

- Autosomal recessive disorder
- Colonic polyps + brain tumours like medulloblastoma or gliomas
- Often associated with FAP

Cronkite – Canada Syndrome

- Polyps in stomach, duodenum and colorectum. No polyps in oesophagus
- Intractable diarrhoea, pigmentation, cachexia, alopecia, onychodystrophy
- In females
- 15% will have malignancy

Cowden Syndrome (multiple hamartoma – neoplasia syndrome)

- Autosomal dominant
- Penetrance at age 20 with PTEN suppressor gene mutation
- Benign ectodermal tumour—tricholemmoma – 80%
- Macrocephaly—40%
- GI polyposis—35% end no risk of GI malignancy
- 10% risk of thyroid cancer
- 30-50% risk of breast cancer

Bannayan –Riley – Ruvalacaba Syndrome (Ruvalacaba Myhre Smith)

- Autosomal dominant
- GI hamartomatous polyp
- Macrocephaly, mental retardation
- Delayed psychomotor development
- Lipid storage myopathy
- Hashimoto's thyroiditis
- Hyperpigmentation of penile skin
- No risk for GI or extra GI malignancy

CARCINOMA COLON

- It is commonly *adenocarcinoma*.
- Very rarely adenosquamous, squamous carcinoma can occur.

Adenocarcinoma

- Sigmoid colon (21%) is the most common site of malignancy after rectum (38%).
- In caecum it is 12% common.

Aetiology

- ***Diet***:
  - Red meat and saturated fat increases the incidence of colonic cancer.
  - Cholesterol increases the bile acid concentration in the intestinal lumen which acts as co-carcinogen.
  - High fibre diet protects the colon against cancer.
  - Calcium in diet prevents colonic cancer by combining with bile salts and reducing bile salt concentration in the colon. It directly acts on the colonic mucosal cells to reduce their proliferative potential.
  - Diet with lack of fibre increases the risk. Diet with high fat increases the risk.
  - Dietary vitamins A,C, E and zinc reduces the risk.
- ***Genetic***:
  - Carcinoma colon is more common in individuals with *adenoma colon* or with *familial adenomatous polyposis (FAP*), Gardner's syndrome, Turcot's syndrome.
  - Relatives of colonic cancer patient have got 2-4 times increased risk of developing carcinoma of colon.
- Long standing *ulcerative colitis, Crohn's disease* has high risk of colonic cancer. Crohn's disease is a premalignant condition but not as much as ulcerative colitis.
- *Alcohol and cigarette smoking increases the risk.*
- *Hereditary nonpolyposis colonic cancer (HNCC)* has got high incidence (25%) of synchronous and metachronous growth, so total colectomy is needed.
- After cholecystectomy and ileal resection there is increased bile salts and so more prone for carcinoma colon.
- Radiation increases the risk (mucinous type).
- Ureterosigmoidostomy increases the risk by 100-500 times.

Note: Aspirin, calcium and other NSAIDs protect against colonic cancer.

Colonic cancer may be

Non hereditary colon cancer

- It can be sporadic colon cancer – 60%.
- It can be familial colon cancer – 30%. Common in Ashkenazi – Jewish population.

Hereditary colon cancer

- FAP.
- HNCC.
- Peutz Jeghers syndrome – 2-3% risk of cancer colon.
- Cronkite – Canada syndrome.
- *Juvenile polyposis syndrome* – It differs from isolated juvenile polyps discussed earlier. It is an autosomal

dominant condition, occurs in children and adolescent. Germ line mutation of SMAD-4 gene is observed. In increases the risk of colonic cancer.

HNCC (hereditary nonpolyposis colonic cancer)

- No polyps. Autosomal dominant
- Three members of the family have colonic cancers
- Two first degree relatives will have same cancer
- Two consecutive generations observed
- One relative with less than 50 years age will have colonic cancer
- *Lynch syndrome* I is site specific - commonly right sided, occurs in early age group, 40% are metachronous
- *Lynch syndrome* II has other malignancy in, stomach, breast, ovary, endometrium and urinary bladder. It is cancer family syndrome
- Microsatellite instability (MSI) at DNA level occurs in HNCC
- Accounts for 3-5% of colonic cancers
- Amsterdam criteria I (1990); Amsterdam criteria II (1999) and revised Bethesda guidelines (2002) are used to diagnose HNCC

Types

Patient can have *de novo multiple primary* carcinomas in different parts of the colon at the same time, i.e. ***synchronous* (5-10%),** or can present with growth in different parts of the colon in different periods, i.e. ***metachronous* (10-20%).**

Gross types: *Annular, tubular, ulcerative, cauliflower like.*



Fig. 22.27: Gross types of carcinoma colon. Annular and tubular types are common in left side, ulcerative and proliferative are common in right side.

Annular (stenosing) type:

- It is more common on left side.
- Here the growth spreads round the internal wall and so it often presents with intestinal obstruction.

Ulcerative type:

- It is common on right side.

Proliferative type:

- Common in right side. It is fleshy, bulky and polypoid. It is less malignant.



Figs 22.28A and B: Carcinoma caecum showing proliferative lesion in one photo. Thickening of the wall is seen in another photo.



Fig. 22.29: Carcinoma ascending colon. Note the growth, caecum and ileum. It is proliferative type.

Let us not look back in anger or forward in fear but look around for awareness.



Fig. 22.30: Carcinoma transverse colon. It is ulcero-proliferative lesion.



Fig. 22.31: Carcinoma descending colon. Note the proliferative tumour. Commonly it is stricture type/annular type on left side.



Fig. 22.32: Annular type of growth observed in left sided/sigmoid colon.



Fig. 22.33: Ulceroproliferative lesion in the colon. Note the everted edge.

Histology (WHO)

- Adenocarcinoma – 90%.
- Mucinous adenocarcinoma – 5-10%.
- Signet ring cell carcinoma.
- Small cell/oat cell carcinoma – rare – extremely poor prognosis.
- Squamous cell carcinoma.
- Undifferentiated carcinoma.

Duke's histological grading of carcinoma colon (Now modified Morson-Dawson)

- Grade I- low grade.
- Grade II- average grade.
- Grade III- high grade.
- Grade IV- anaplastic.

Haggitt's Invasion of Malignant Polyp

In pedunculated polyp

Level 0 – non invasive carcinoma over the summit.
Level 1 – invasion to head of the pedunculated polyp.
Level 2 – invasion to neck of the pedunculated polyp.
Level 3 – invasion to stalk of the pedunculated polyp.
Level 4 – invasion to base of the pedunculated polyp.
In sessile polyp – all lesions are level 4.

Sessile Malignant Polyp Invasion

Sm 1 – Submucosal invasion into upper 1/3 (superficial/inner).
Sm 2 – Submucosal invasion into middle 1/3 (inner 2/3).
Sm 3 – Submucosal invasion lower 1/3 (deep).

STAGING OF CARCINOMA COLON

DUKE'S

A. Confined to bowel wall, mucosa and submucosa
B. Extends across the bowel wall to the muscularis propria with no lymph nodes involved
C. Lymph nodes are involved

MODIFIED DUKE'S

A. Growth limited to rectal wall
B. Growth extending in to extrarectal tissues but no lymph node spread
    B1: Invading muscularis mucosa
    B2: Invading in to or through the serosa
C. Lymph node secondaries
D. Distant spread to liver, lungs, bone, brain

ASTLER-COLLER'S

A. Intramucosal
B1 Involvement up to muscularis propria
B2 Spread through the wall in to peritoneum
C1 B1 + Involvement of lymph nodes
C2 B2 + Involvement of lymph nodes
D Distant spread

Spread

Direct spread:

- Locally it can invade the bladder, obstruct ureter and so cause hydronephrosis.
- Can perforate and cause peritonitis/pericolic abscess/faecal fistula.
- Growth may get adherent to psoas muscle posteriorly.
- Carcinoma sigmoid colon can infiltrate and cause colovesical or colovaginal fistula. It can infiltrate ureter, ovary, uterus etc. It can cause pericolic abscess or abscess in lateral abdominal wall.

Lymphatic spread:

- Growth through lymphatics spreads to pericolic, epicolic, intermediate and principal group of lymph nodes.

Groups of Lymph Nodes Draining Colon

- N1: Nodes immediately adjacent to bowel wall.
- N2: Nodes along ileocolic/right colic/middle colic/ left colic/sigmoid arteries.
- N3: Nodes near the origin of SMA and IMA.
- Nodal spread in carcinoma colon is sequential from N1 → N2 → N3.

Blood spread:

- 40% of carcinoma colon spreads to *liver via portal veins.*
- *Secondaries* may be either *solitary* or *multiple*, present as liver with hard, umbilicated nodules.
    - Rarely it spreads to *bone, lung, skin.*



Fig. 22.34: Carcinoma colon—types.

TNM Staging

Tis—Carcinoma *in situ*.
T1—Invasion into submucosa.
T2—Into muscularis.
T3—Into pericolic fat.
T4—Breaches out of serosa and may involve adjacent organ.

N0—No nodes.
N1—Up to 3 nodes.
N2—4 or more nodes.

M0—No metastasis.
M1—Metastasis present.

L0 – No lymphatic vessel invasion;
L1 – Presence of lymphatic invasion.

V0 – No venous invasion;
V1 – Presence of venous invasion.

R0 – No residual tumour after resection;
R1 – Microscopic residual tumour after resection;
R2 – Macroscopic residual tumour.

Clinical Features

- Occurs usually after 50 years. Familial type can present in younger age group. Common in males (M : F :: 3 : 2).
- Commonly present with loss of appetite and weight, anaemia, abdominal discomfort and mass per abdomen.

Little discipline multiplies rewards.


FEATURES OF CARCINOMA COLON
Multiple liver nodules (Secondaries)
Pleural effusion
Ascites
Enlarged nodes
Tumour
Right side
- Anaemia
- Mass RIF
- Like appendicitis
- Intussusception
- Pericolic abscess
- Altered bowel habits
Tumour
- Loss of appetite
- Decreased weight
- Jaundice
- Lt Supraclavicular LN (Troisier sign)
Perforation peritonitis
Tumour left side
Obstructive symptoms
Pericolic abscess
- Tenesmus
- Diarrhoea
- Mucus
- Mass LIF
- Back pain
Bleeding per anum
- Urinary symptoms
- Fistula into bladder/vagina
- Hydronephrosis by ureter infiltration
- Blumer shelf (rectovesical secondaries)

Fig. 22.35: Clinical features of carcinoma of colon – diagrammatic representation.

- 20% of cases present as an acute intestinal obstruction.
- 20% of colonic/colorectal cancer has stage IV disease at the time of first presentation.
- ***Right sided growth*** commonly presents with *anaemia, palpable mass* in the right iliac fossa, which is not moving with respiration, mobile, nontender, hard, well localized with impaired resonant note.

Differential diagnosis for mass in the right iliac fossa

Ileocaecal tuberculosis
Appendicular mass
Actinomycosis
Ectopic kidney
Mesenteric lymph nodes
Ovarian tumour in females
Retroperitoneal tumour
Amoeboma

Carcinoma caecum occasionally presents like acute appendicitis or intussusception with intestinal obstruction.

- ***Left sided growth*** presents with *colicky pain, altered bowel habits (alternating constipation and diarrhoea)*, palpable lump, distension of abdomen due *subacute/chronic obstruction*. Later may present like complete colonic obstruction. Tenesmus, with passage of blood and mucus, with alternate constipation and diarrhoea, is common. Bladder symptoms may warn colovesical fistula.
- Features of pericolic abscess/obstruction/perforation/peritonitis may be the first presentation.
- *Closed loop obstruction* can occur in transverse colon growth (stricture type causing block) with competent ileocaecal valve. Enormously dilated right sided colon is prone for *stercoral ulcer*, perforation and faecal peritonitis.
- Enlarged liver with multiple umbilicated hard secondaries, ascites, rectovesical secondaries, palpable left supraclavicular lymph nodes are other presentations.
- Faecal strength of *Streptococcus bovis* bacteria increases many fold in patients with colonic cancer compared to individuals without colonic cancer.


Adbominal wall
Carcinoma colon
Pericolic abscess

Fig. 22.36: Carcinoma with pericolic abscess right sided. Mass here will be tender and localized. Patient may be having fever, tachycardia. Associated obstruction may be there occasionally.



Fig. 22.37: Dilated colon in colonic growth with obstruction.


Tumour causing complete block
Dilated ascending colon and caecum (closed loop obstruction)
1.
Ileum
Competent ileo-caecal valve
2.
Stercoral ulcer in the caecum
1 and 2 are sites of perforation

Fig. 22.38: Carcinoma transverse colon or near hepatic flexure can cause complete block, leading into the enormous dilatation of caecum. If ileocaecal valve is competent, then there will be closed loop obstruction of right-sided colon causing *Stercoral ulcer* due to pressure ischaemia over the summit of the caecum. Perforation can occur in Stercoral ulcer or in growth site itself. It is treated by emergency surgery with resection and temporary ileostomy.

Local complications of carcinoma colon

- Intestinal obstruction
- Closed loop obstruction
- Perforation and peritonitis
- Vesicocolic fistula
- Invasion of ureter
- Pericolic abscesss.

Investigations

- *Barium enema*: Shows irregular filling defect and *'apple core' lesion* (in left sided carcinoma). It also helps in finding colonic polyps (*Air-contrast barium enema*).
- *Colonoscopy and biopsy* confirms the diagnosis.
- Virtual colonoscopy (CT colonography) is also useful to visualize entire colon.



Fig. 22.39: Carcinoma colon—colonoscopic view.

- U/S, to see secondaries in liver, peritoneum, lymph node status, rectovesical secondaries.
- **CEA (*Carcinoembryonic antigen*):**
  - It is a *cell surface glycoprotein* discovered by Gold and Freedman.
  - It is normally produced by colonic epithelium.
  - Its serum ½ life is up to 10 days and is cleared by liver through Kupffer cells. So its ½ life prolongs in cholestasis and hepatocellular dysfunction.
  - Normal level is < 2.5 ng/ml. Level > 5 ng/ml is significant.
  - Even though it is a widely used tumour marker, it has got low sensitivity.



Figs 22.40A and B: Carcinoma colon. (A) Barium enema study, (B) Air-contrast study.



Figs 22.41A and B: X-rays with barium enema showing narrowing in sigmoid region in one and irregularity in another.

  - CEA is primarily associated with colorectal cancers, but it can also increase significantly in pancreatic, gastric, lung, breast carcinomas. Often its level also increases in nonmalignant

Art is long, life short, judgement difficult, opportunity transient.



Fig. 22.42: Barium enema X-ray showing irregular filling defect in caecum—feature of carcinoma colon.

conditions like pancreatitis, hepatitis, obstructive jaundice, BPH.

– *Uses in colorectal cancers are*:

a. Preoperative levels >7.5 ng/ml signifies poor prognosis.

b. If postoperative level does not fall, it indicates either incomplete resection, or occult metastasis elsewhere.

c. Increase CEA during follow-up indicates recurrence or secondaries.

– A slow rise indicates loco regional disease.

– A rapid rise signifies metastasis.

– It is not useful in assessing follow-up in poorly differentiated adenocarcinoma as such tumour will not produce CEA.

- Left supraclavicular lymph node if palpable, its FNAC may clinch the histological diagnosis.
- Hb%, PCV, haematocrit, ESR.
- CT scan abdomen and pelvis - to see local spread, invasion, size and extent, stage, nodal status and liver secondaries.
- LFT—mainly enzyme studies like alkaline phosphatase, SGPT.



Fig. 22.43: CT scan picture showing growth in the right side colon.



Fig. 22.44: Colonoscopic view of carcinoma colon.

Treatment


Area of resection in right sided growth
Area of resection in left sided growth
Growth in colon
Line of resection

Fig. 22.45: Levels of resection in growths in different portions of the colon.


Ileo-transverse by pass anastomosis in inoperable right side growth
Colo-colic by pass anastomosis in inoperable left side growth

Fig. 22.46: Colo sigmoid bypass in case of inoperable growth in splenic flexure. Ileo transverse anastomosis in case of inoperable hepatic flexure growth.

Mainly surgical

a. *Right sided early growth*:
   - Right radical hemicolectomy with ileo transverse anastomosis is done. Structures removed are terminal 30 cm of ileum, caecum and appendix, ascending colon, 1/3 of transverse colon, lymph nodes (epicolic, paracolic, intermediate).



Fig. 22.47: Specimen of hemicolectomy done for carcinoma caecum. Note the different parts – terminal ileum, ascending colon, hepatic flexure and omentum.

   - In inoperable right sided growth, *ileo-transverse anastomosis* is done as a by-pass procedure.

b. *Left sided early growth*:
   - Left radical hemicolectomy is done, where in left ½ of transverse colon and descending colon is removed along with lymph nodes.
   - Left sided stenosing type of growth can present with acute intestinal obstruction, in which case initially colostomy is done. Later, after 3-6 weeks, following proper preparation, required formal procedure is done, followed by colostomy closure after 8 weeks (*3 stage operation*).
   - Often growth in the transverse or left sided colon, which is stenosing or obstructive type, can cause *closed loop obstruction* because of the competent ileocaecal valve. As a result, pressure increases in the caecum eventually leading to its perforation. Perforation can also occur occasionally at the site of tumour. They need *emergency intervention*—caecostomy or colostomy, with resection and anastomosis of the tumour. If severe peritonitis sets in, it may be life-threatening.
   - During exploration, presence of any synchronous growths has to be looked for. Now it is found that carcinoma colon can be *associated with tuberculosis or lymphoma of colon*. So this association is also looked for.
   - In acute left sided growths, *trans anal self expanding metal stents* can be used instead of defunctioning colostomy.
   - *Turnball's 'No touch technique'*: Here the vessels are ligated at its origin, at the beginning, in order to prevent the tumour spread - due to tumour handling.

c. *In solitary liver secondary*, segmental hepatic resection is useful. In case of multiple secondaries confined to one lobe of the liver, hemihepatectomy can be tried.
   - *Metastasectomy*—It is done in one secondary/one lobe secondaries/less than 3 metastases in both lobes/without any extrahepatic spread.

d. *'A second look operation'* is most often helpful in carcinoma of colon, to resect the residual or recurrent tumours (*Owen Wangensteen's Second look surgery).*

e. If there are synchronous growths or growth with other area having multiple potential polyps, then total colectomy with colorectal anastomosis is done.

f. Recurrent tumour should be treated by re-exploration and resection with adjuvant chemotherapy of different regime.

g. Laparoscopic evaluation and resection is becoming popular. Laparoscopic assisted colonic resection is also done (*Hand Assisted Laparoscopic Surgery*).

Note:
- Blood transfusion before or during surgery for colonic cancer may alter the immunological aspect of the colonic cancer and may increase the recurrence rate and so may alter the prognosis. It is presently not very well-proved.
- Proper preoperative bowel preparation by mannitol/polyethylene glycol/hypertonic saline/bowel wash/bowel antiseptics (neomycin or gentamycin or streptomycin and metronidazole orally).
- Antibiotic prophylaxis; DVT prophylaxis by bandage, heparin or low molecular weight heparin.
- Pulmonary function tests and pulmonary exercise preoperatively as well as postoperatively.
- Urinary catheterisation, nasogastric tube placement.

The most vital test of a man's character is not how he behaves after success, but how he sustains defeat.

- Postoperative proper care with fluid, electrolyte, drain care, early mobilization, monitoring.
- Complications of surgery are leak (fecal fistula), bleeding, infection like intraperitoneal/pelvic abscess, respiratory problems, DVT, wound infection, burst abdomen.

Adjuvant Therapy

Chemotherapy

Indications for chemotherapy

- Positive nodes.
- T4 lesions.
- Venous (microscopic) spread.
- Signet cell type.
- Poorly differentiated tumour/aneuploidy.
- Changes in CEA level.

Postoperative chemotherapy is used commonly. Occasionally also given preoperatively.

Regimes are -

- 5 Fluorouracil (5 FU) with folinic acid (leucoverin/LV) is the most commonly used regime for 6 months as monthly cycles. Folinic acid potentiates the action of 5 FU.
- Levamisole 150 mg/day for 3 days given once in 15 days for one year with intravenous 5 FU monthly for one year.
- Irinotecan/5 FU/LV – IFL regime is also used.
- Folinic acid (LV)/5 FU/oxaliplatin – FOLFOX regime is also used. It is becoming treatment of choice.
- Irinotecan/oxaliplatin – IROX regime is used in previously untreated metastatic colonic cancer.
- Capecitabine (xeloda) an oral drug which generates 5 FU at tumour tissue, shows significantly greater response than 5 FU/LV regime.
- Phase II trials are going on for capecitabine/oxaliplatin and capecitabine/irinotecan combination regimes.
- 5 FU infusions into the portal vein during and immediately after surgery have shown benefits in terms of outcome and recurrence.

EGFR and VEGF blockers (EGFR is epithelial growth factor receptor; VEGF is vascular endothelial growth factor)—

- They are used as single agent and also in combination with chemotherapy drugs in phase II and III trial.
- Drugs are monoclonal antibody, cetuximab which blocks EGFR, bevacizumab which binds VEGF.

Radiotherapy

- Usually of no role for RT as tumour is radioresistant.
- It is often used in locally advanced tumour, infiltrating the psoas major muscle or lateral abdominal wall.
- It is also used in inoperable recurrent tumour.

Follow-up

- For 3 years at regular intervals, once in 6 months.

This is by:

- Regular CEA analysis
- Ultrasound abdomen
- Barium enema X-ray
- Colonoscopy
  Rise in CEA is a definite indicator of recurrence or secondaries
  In patients with raised CEA, radioistotope antibody study will show the site of recurrence or secondaries
- Serum alkaline phosphatase

Prognosis

Depends on

- *Site*—Left sided tumours has got better prognosis as they present early.
- *Type*—Colloid carcinoma has got poorer prognosis.
- *Size* of the tumour.
- *Lymph nodes status: Number of lymph nodes* involved decides the prognosis.
- *Liver secondaries has poor prognosis.*
- *Age of the patient.*
- Associated diseases like *HIV.*
- *Stage of* the tumour.
- Presence of complications, perforation, peritonitis.

On the whole it is a curable malignancy with proper surgery and adjuvant therapy.

ANGIODYSPLASIA OF COLON

- It is a vascular ectasia.
- It is uncommon in healthy individual.
- It is commonly seen in elderly of 70 years age. It is acquired malformation of aging.
- It is not common in left side colon. It is often associated with calcified aortic stenosis; and ectasia bleeding if present, stops once aortic stenosis is corrected.
- Common cause of rectal bleed in adults and elderly.
- An acquired condition seen in caecum and ascending colon due to degeneration of the mucosal and submucosal vessels of the colon.
- Diagnosis is by mesenteric angiography.
- Colonoscopic fulguration or resection is the treatment.
- Therapeutic embolisation is useful in 85% of cases.
- Acquired malformation with aging.

OGILVIE'S SYNDROME

- Also called as colonic pseudo-obstruction.
- Severe colonic ileus occurs without any mechanical obstruction.

- Occurs in critically ill patients.
- Due to sacral parasympathetic nerve dysfunction.
- Commonly seen in splenic flexure.
- Due to sacral parasympathetic malfunctioning, there is atony of descending colon causing functional obstruction. Splenic flexure will be the junction of dilated and collapsed parts of the colon wherein parasympathetic supply of vagus ends and of sacral parasympathetic begins. Increased sympathetic activity causes colonic dilatation
- It is seen in –
  – Scleroderma, SLE, dermatomyositis.
  – Chaga's disease.
  – Myotonic dystrophy, multiple sclerosis.
  – Neuropathies.
  – Myopathies.
  – Hypothyroidism, diabetes mellitus.
  – CRF, renal transplantation.
  – Poisoning, sepsis, hypoxia.
  – Radiotherapy, orthopedic procedures.
  – Psychiatric disorders, drug abuse.

Treatment

- Mainly conservative.
- Motility enhancing drugs like neostigmine and erythromycin are used.
- Prokinetic drugs like cisapride/mosapride are used.
- Ceruletide decapeptide 0.3 µg/kg IM is used to stimulate intestinal motility.
- Ryle's tube aspiration.
- Flatus tube insertion.
- Correction of electrolyte imbalance.
- Sodium enema.

Caecal diameter more than 12 cm (critical) on X-ray indicates surgical exploration.

- Tube caecostomy; resection and exteriorisation.

COLOSTOMY

It is an artificial opening made in the colon to the exterior (skin) to divert faeces and flatus.

Types

1. ***Temporary:*** Is done in conditions wherein diversion is required to facilitate healing distally in the rectum or distal colon. And this is closed once the purpose is over.

   Site of temporary colostomy is usually right hypochondrium and left iliac fossa.
2. It can be ***loop colostomy*** or ***Devine's double-barrel colostomy*** (wherein there is a gap between the two openings of colostomy which prevents spillage into the distal loop).
3. ***Permanent*** colostomy is always *end colostomy* placed in left iliac fossa, 6 cm above and medial to the anterior superior iliac spine.

Indications

Temporary	*Permanent*
Congenital megacolon	AP-Resection.
Anorectal malformations	Carcinoma anal canal.
Sigmoid volvulus	After Hartmann's operation
Perforation of left sided colon	
Left sided colonic growth	
High anal fistula	
Trauma to left sided growth	



Fig. 22.48: Types of Colostomy. (A) Temporary colostomy, (B) Loop colostomy, (C) Devine's double barrel colostomy, (D) Permanent colostomy.



Fig. 22.49: Different types of stomas used in colostomy.

Complications of colostomy

1. Prolapse of mucosa (prolapse of distal loop mucosa is common) - commonest complication
2. Retraction
3. Necrosis
4. Stenosis
5. Herniation
6. Bleeding
7. Diarrhoea
8. Enteritis
9. Skin excoriation

Better alone than in bad company.



Figs 22.50A and B: Diagram of colostomy in a patient with colostomy bag.

Educating the patient regarding the proper usage of colostomy bags and proper care of the colostomy is very essential.

Colostomy Care

- Similar to stoma care.
- Initially stoma bag should be transparent as content is liquid stool but later it can be opaque.
- Regular consultation with stoma therapist.
- Care of the skin.
- Training for managing colostomy, its care to prevent leak, odour, and discomfort.

Closure of Colostomy

- When temporary colostomy is done, it is closed usually after 3 months.
- *Two types of closure are present*. Extraperitoneal and intraperitoneal type. *Now intraperitoneal closure is done.* Earlier extraperitoneal closure was done in loop colostomy by placing a spur in between and closing the antimesentric part of the colon. It prevents the peritoneal contamination. But inadequate closure, leak, adhesions are the problems. *Intraperitoneal closure* – commonly advocated technique now is done by placing a circumferential incision over the margin with skin edge. Incision is deepened to enter the peritoneum and pull out the colostomy stoma. Part adjacent to the skin is resected and anastomosed using silk/vicryl. Sutured bowel is placed into the peritoneal cavity. Drain is placed into the peritoneal cavity. Abdomen closed in layers.
- Closure of colostomy is done after proper bowel preparation, under general anaesthesia.
- Proper postoperative care is important.
- Patient should perform anal sphincter exercises to prevent sphincter atrophy and to maintain sphincter tone.



Fig. 22.51: Patient with colostomy bag. He has undergone abdominoperineal resection (APR) for carcinoma rectum.

STOMA CARE

Definition of Stoma

Stoma is an artificial opening or 'mouth like' to the exterior, the abdominal wall so as to drain the content from the tubular structures inside, like bowel or ureter. It is done for diversion of urine or faecal matter in case of malignancy, trauma, and sepsis or after surgery.

Types

- ***Ileostomy***- Terminal 5 cm ileum is projected out, on to the skin of abdominal wall to drain semi-liquid, faecal matter.
- ***Colostomy*** - Colon at different levels, can be brought out to the skin as required as colostomy, to divert faecal matter.
- ***Cutaneous ureterostomy*** - Cut ends of one or both ureters are apposed to the skin of abdominal wall.

- ***Ileal urinary conduit*** - Segment of isolated ileum can be used to drain urine from the ureter as urinary ileal conduit. Ureters are anastomosed to a closed ileal conduit. Ileal stoma is brought out as stoma. Different types of continent ileostomies are in use to prevent leak, soakage and discomfort.
- ***Vesicostomy*** **-** It is done in children. Here anterior wall of bladder is brought out and bladder mucosa is sutured to the skin of abdominal wall.

Stoma created may be *round* [commonly] or *square* in shape.

Preparation and Counselling of the Patient for Stoma

- To certain extent stoma of any type causes psychological and physical trauma to the patient, as it is nonphysiological, distressing and socially not acceptable.
- Patient should be explained about the procedure and should be convinced and consoled about the stoma.
- Detailed meaning, explanation and after care of the stoma should be discussed.
- Indication for the stoma and consent for the same should be taken.
- Reassurance about the stoma, its care, and its position should be diagrammatically explained to the patient and his close relative.
- In case of obstructive disease, stoma is done as an inevitable procedure to relieve the obstruction, often it may be temporary.
- Proper bowel preparation by bowel wash, gut irrigation is required before surgery.
- *The surgeon selects the site of the stoma.*
  - Stoma is usually sited midway between anterior superior iliac spine and umbilicus.
  - It should be away from the belt line.
  - It should be away from the scar, creases, and bony points.
  - Patient should be assessed for proper size, adequacy for stoma in lying down, sitting, and standing positions.
  - Proper stoma appliances should be decided after thorough check-up and discussion with patient and patient's relative.
  - Stoma site should be marked properly before surgery.
  - Ileostomy is usually sited in the right iliac fossa, colostomy in left iliac fossa.
  - Allergy for the particular appliances should be checked for.
  - The patient should consult stoma therapist.

Postoperative Care for the Stoma

- Stitches are removed in 6-10 days.
- Dressing should be done first over the stoma and after placement of appliance, laparotomy wound is dressed otherwise stoma appliance will not sit properly.
- Patient should be observed for any complications.
- Once wound has healed patient can take bath by removing the appliances. After bath skin is dried up and stoma appliances can be fit again.
- Patient should be taught about the stoma care and its appliances.
- Care and prevention of skin excoriation due to leak is also looked into.
- Psychotherapy is given for the patient.
- Skin should be *absolutely dry* prior to placing the stoma appliances.



Fig. 22.52: Right sided temporary loop colostomy. Note the tube kept in between.

Complications of Stoma

- Skin excoriation.
- Mucosal prolapse – common complication.



Fig. 22.53: Colostomy prolapse is the common complication.

Liberty means responsibility; that is why most men dread it.

- Stenosis and block.
- Infection either bacterial or candidial.
- Diarrhoea due to irritation.
- Leak due to improper fitting of the appliances, scar, irregularity of stoma, prolapse.
- Bleeding from the stoma edge.
- Herniation of the abdominal contents adjacent to stoma.

Skin Excoriation

It is a major problem in stoma patients. It is basically due to leak adjacent to appliances.

Causes for Excoriation

- Leak due to improper appliances.
- Wet skin before placing the appliance.
- Inadequate stoma hole.
- Improper and inadequate adhesive sheet usage.
- Allergy.
- Infection like of bacteria and candida.
- Altered weight of the patient.
- Stoma bag is overfilled or kinked or air in the stoma bag.

Treatment of Excoriation

- Control of infection by antibiotics and control of moniliasis.
- Allergy has to be confirmed, and if it is the cause, the agent is found out and treated as required.
- Zinc oxide cream application.
- Change of the type of appliance.
- Refashioning of the stoma.

STOMA APPLIANCES

Stoma appliances are devices, which are used to collect and dispose the effluent materials which come out of the stoma.

Ideal stoma appliance is —
- Leak proof
- Should not damage the stoma and surrounding skin
- Should prevent odour
- Should be available
- Easier to use

Types of Appliances

It can be—
- *Closed type* is discarded when full and is used in patients with well-formed stool.
- *Drainable type* is used in patients with loose liquid stool. It can be emptied and retained and re used. Immediately after colostomy, drainable appliance is used. Later it can be changed over to closed type.

It can also be-
- *One-piece stoma* appliance as a bag with adhesive system attached which adheres to skin around the stoma.
- *Two-piece stoma* appliance has got a flange with adhesive system and a bag over it, which can be removed and replaced with a new one without disturbing the flange underneath.

Bag can be-
- *Transparent,* in which fluid can be visualised. It is used in initial period of the stoma.
- *Opaque,* in which fluid cannot be visualised. It is used eventually later.

General Care and Advice to Patients with Stoma

- Patient can have normal diet. Diet, which regulates the bowel action, is better. Plenty of water is advisable.
- Patient can go for normal work, exercise like sports, swimming, tennis. Stoma appliances suitable for these works are available.
- Antidepressants, anticholinergics might cause constipation. So these drugs should be taken carefully.
- Using irritant solutions near stoma should be avoided. It may lead to dangerous complications.
- Patient can have normal sexual activity.
- Patient should have additional stoma bags in hand so as to use if required urgently.
- Patient should be aware of different appliances available and should be well versed with its use. He can take the help of the stoma societies.

FAECAL FISTULA

- This is a dangerous entity.
- It commonly occurs after appendicectomy (gangrenous), ileal resection, colonic surgery, malignancy, ileocaecal TB, actinomycosis and Crohn's disease.
- It may be from the ileum or the colon.
- It may be single or multiple openings.
- More proximal the fistula, more is the severity in fluid and electrolyte imbalance.
- It may be from the main incision wound or from the drain wound.





Figs 22.54A and B: Prolapse of colostomy is a common complication.

- If there is no distal obstruction, the fistula will heal spontaneously, but may take a longer time.
- *Fistulogram* often delineates the track.
- CT fistulogram with CT scan abdomen is essential.
- Often gastrograffin study is also useful to study the fistulous track in detail.

Factors preventing closure (FRIENDS)

F Foreing body in fistula tract
R Radiation enteritis
I Inflammatory bowel disease
E Epithelialisation of tract
N Neoplasm
D Distal obstruction
S Sepsis



Fig. 22.55: Caecostomy is often done in acute colonic conditions as diversion procedure after surgery distally like perforation closure and resection. But it is not as popular as colostomy because it may not function adequately, may get displaced or blocked. But it is technically easier and usually done by doing appendicectomy and passing Malecot's tube through appendicular stump. Removal is easier without any surgical intervention.

Factors preventing spontaneous closure of faecal fistulas

- High output > 500 ml/24 hr
- Distal bowel obstruction
- Sepsis, inflammatory bowel disease
- Tuberculosis
- Cancer
- Radiation enteritis
- Foreign body in fistula tract
- Epithelialisation of tract.

An essential aspect of creativity is not being afraid to fail.



Fig. 22.56: Multiple faecal fistulous openings in the abdominal wall. Patient has undergone laparotomy for acute peritonitis.

Investigations for faecal fistula

- Fistulogram using gastrograffin
- CT scan and CT fistulogram
- Barium enema study



Figs 22.57A and B: Gastrointestinal faecal fistula after an emergency surgery for ileal perforation with severe peritonitis. Patient recovered after long-term stay in the hospital.

Treatment

- TPN and blood transfusion may be required to improve the nutritional status of the patient.
- Sepsis is controlled with proper antibiotics.
- Management of fluid and electrolyte loss.
- Skin is protected from excoriation by using zinc oxide cream.
- If it persists, later exploration and resection is done.
- The cause is treated.
- By pass may be required. (*Most of the time the decision is taken on table during surgery*).

PREPARATION OF LARGE BOWEL FOR SURGERY

1. *Bowel wash* for 2-3 days before surgery using normal saline (not water as it will cause water intoxication). Full length of large bowel is cleaned. Usually about 1-2 litres of saline is used.
2. *Bowel antiseptics*: Oral neomycin for 3 days or oral gentamycin or streptomycin are used, as these drugs will not get *absorbed and acts only locally*. Metronidazole orally for 3 days is given.
3. *Total gut irrigation by oral mannitol*—200 ml for 2-3 days or by single dose of oral polyethyleneglycol (**Peglec, Coloclean)** powder dissolved in 2 litres of water given one day prior to the surgery—acts by drawing fluid from the bowel wall by hygroscopic action and so cleans the bowel including the small bowel.

Other than this oral clear fluids, IV Fluids, IV antibiotics are given.

Indications for Large Bowel Preparation

- Carcinoma colon (especially left sided).
- Anorectal malformations.
- Megacolon.
- Carcinoma rectum.
- Surgery for ulcerative colitis.
- FAP.
- Diverticulitis.
- High pelvirectal fistulas.
- Before colonoscopy.

BARIUM ENEMA

- It is the contrast X-ray done to visualise large bowel.
- Therapeutic barium enema is done in intussusception in children.

Barium enema

Indications	*Finding*
Carcinoma colon	Irregular filling defect
Ileocaecal tuberculosis	Pulled up caecum, obtuse ileocaecal angle Filling defect, incompetent ileocaecal valve
Ulcerative colitis	Loss of haustrations, lead pipe appearance
Colonic polyps	Smooth, regular filling defect
Congenital mega colon	Narrow zone, zone of cone, dilated proximal segment
Diaphragmatic hernia	Colonic shadow in the left thoracic cavity
Gastrojejunocolic fistula	Leak in to the stomach from colon



Fig. 22.58: Barium enema showing normal peristaltic movement.

Procedure

Laxative is given previous evening. Enema is given on same day before doing the procedure. About one litre of barium sulphate solution is infused into the colo-rectum per anally through enema tube. In children 12F Foley's catheter is used. Once complete filling occurs, X-ray is taken. Patient is asked to evacuate the barium and post-evacuation film is taken. After that, air is inflated into the colon which gives a better contrast to visualise thin mucosa of the colon (**air-contrast barium enema).**

Contraindications

Acute colonic conditions.



Figs 22.59A to C: Barium enema X-ray in different indications should be taken with complete filling, postevacuation and after air-contrast.

Arrogance is the obstruction of wisdom.

Self-assessment Questions

- Colostomy.
- Carcinoma caecum—clinical features, investigations and management.
- Differential diagnosis for mass in the right iliac fossa.
- Amoeboma.
- Carcinoma colon pathology, presentations and management.
- Preparation of large bowel for surgery.
- Familial adenomatous polyposis.
- Anterior resection.
- Abdomino-perineal resection (APR).
- Peutz-Jegher syndrome.
- Colonic polyps.
- Gardner's syndrome.

23

Intestinal Obstruction

Intestinal obstruction
Duodenal atresia
Small intestine atresia
Malrotation
Meconium ileus
Intussusception
Volvulus—*Sigmoid volvulus*
Paralytic ileus
Adhesions and bands
Internal hernias

INTESTINAL OBSTRUCTION

TYPES

Classification I: Depending on aetiopathology

A. Dynamic.
B. Adynamic.

Dynamic			*Adynamic*
Outside the wall	In the wall	In the lumen	
Hernia – 25% Adhesions – 40% Volvulus Intussusception	Tuberculous stricture Crohn's disease Malignancy	Gallstones Round worm Inspissated faeces Meconium ileus	Cessation of peristalsis Postoperative period Electrolyte imbalance Spinal injuries Uraemia Diabetes mellitus Retroperitoneal—haematomas and surgeries Renal surgeries Mesenteric ischaemia Pseudo-obstruction

Classification II: Depending on Type of Obstruction

1. Acute: Common in small bowel.
2. Chronic.
3. Acute on chronic: Common in large bowel.
4. Closed loop obstruction.

Classification III: Depending on Site of Obstruction

	Proximal small bowel	*Distal small bowel*	*Large bowel*
Site of obstruction	Duodenum and jejunum	Ileum	Any where in large intestine.
Causes:	Congenital Lipomas Leiomyomas Malignancy Bands and adhesions	TB strictures Malignancy Crohn's Gallstones Hernias—common cause Roundworm Congenital	Malignancy TB stricture Anorectal malformation Volvulus Congenital megacolon Bands

Note: Adhesions and hernias are most common causes of intestinal obstruction.

Today's friction is tomorrow's destruction.

Clinical features:	Severe vomiting, dehydration, no or less distension, colicky pain	Central distension, vomiting, dehydration central abdominal pain	Constipation, distension — early; Late vomiting less pain
Special features: Plain X-ray	Valvulae conniventes	Characterless Central fluid level	Dilatation and haustration

Classification IV

A. Congenital.
B. Acquired.

Congenital	*Acquired*
Anorectal malformations	Hernia (commonest)
Congenital megacolon	Postoperative
Adhesions	Intussusception
Duodenal atresia	Roundworm
Intestinal atresia (ileal)	Gallstones
Bands and adhesions	Tuberculosis
Malrotation	Malignancy
Volvulus neonatorum	Internal hernias

Bolus obstruction

- Worms
- Gallstones
- Trichobezoars
- Phytobezoars
- Meconium pellets
- Foreign body
- Food bulus
- Stercoliths

Dynamic Obstruction

- It is mechanical blockage of normal propulsion and passage of intestinal contents.
- Obstruction may be external/internal; partial (incomplete or subacute)/complete; acute/acute on chronic/or chronic; simple/closed loop/strangulation; congenital/acquired; proximal/distal.
- Earlier, hernia was the commonest cause of intestinal obstruction. Now adhesions (40%) are the commonest cause especially in developed countries and hernia being 15-25% common. In developing countries both adhesions and hernia are the common causes of intestinal obstruction.
- Adhesions commonly cause small bowel obstruction than large bowel.
- Eighty percent of intestinal obstruction occurs in small bowel; 20% in colon. 70% of colonic obstruction is due to malignancy. Other 30% is due to volvulus; diverti-culitis, inflammatory cause like tuberculosis, etc.
- Mortality is 3% in obstruction without strangulation; 30% in obstruction with strangulation.
- Recurrent obstruction is more common in adhesions.

Pathology and Pathogenesis

- ***Changes proximal to the bowel obstruction:***

Intestinal obstruction
↓
Increased peristalsis.
↓
Becomes vigorous
↓
Obstruction not relieved
↓
Peristalsis ceases.
↓
Flaccid, paralysed, dilated bowel

– Fluid collects just proximal to the obstruction which is derived from saliva, stomach, pancreas and intestine. Because of oedema and inflammation absorption decreases, sequestration of fluid from the circulation into the lumen occurs and bacteria (*E. coli*, *Klebsiella*, anaerobes, bacteroides and



Fig. 23.1: Intestinal obstruction due to band. Note the ischaemic bowel under the band.



Fig. 23.2: Postoperative internal hernia with obstruction.

other organisms) multiply, toxins are released—*toxaemia* occurs. This leads to severe dehydration, electrolyte imbalance.

- Proximal to the collected fluid, air accumulates (derived from swallowed air (70%), diffusion from blood into the lumen (20%), from digested product and bacterial action (10%)), in which, main component is nitrogen (90%) and also hydrogen sulphide. During vigorous peristalsis air enters the distal fluid, results in *churning,* is the reason to cause *multiple air-fluid levels in plain X-ray abdomen.*
- *Defective absorption*, decreased fluid intake, loss of fluid by vomiting, sequestration of fluid into the bowel lumen – leads into severe dehydration, fluid and electrolyte imbalance.
- Inflammatory response in the bowel wall (*intramural inflammation*) causes accumulation of activated neutrophils and macrophages in the muscle wall which release reactive enzymes and cytokines. These substances damage secretory and motor process of muscle leading into dilatation of the bowel. Increased release of *nitric oxide* in muscle wall and production of intramural reactive oxygen metabolites alter gut motility and permeability.
- *Intestinal wall hypoxia* is also the cause for dilatation.
- In first 12 hours of obstruction, there is *only decreased absorption* which causes accumulation of fluid and electrolytes in the lumen.
- After 12 hours, there is also *increased intestinal secretion* causing further accumulation of the fluid.
- Accumulation of bacterial toxins, bile salts, prostaglandins, and mucosa derived free radicals, VIP – all increases the luminal secretion of fluid in obstructed bowel.
- Dilatation of bowel wall increases *intraluminal pressure* which exceeds the bowel wall *venous pressure* causing ischaemia which causes further dilatation and *ischaemic injury*. This leads into eventual blockage of arterial perfusion causing bowel wall necrosis/ gangrene.
- *Increased bacterial colony* in the bowel (Normal flora is less than 10^6 colonies/ml in jejunum and 10^8 colonies /ml in the ileum) due to altered luminal content and environment → multiplication → toxins → further mucosa damage → disrupted mucosal defense/ barrier/integrity → *translocation of bacteria across mucosa* into submucosa and also absorption of bacterial and other toxins into the circulation → bacteraemia/toxaemia/septicaemia/SIRS/MODS.

Factors causing systemic problems in intestinal obstruction

- Dilatation of the bowel
- Decreased absorption across mucosa
- Increased secretion into the lumen
- Intramural inflammation and hypoxia
- Increased intraluminal pressure
- Venous congestion and increased venous pressure
- Disrupted mucosal barrier → bacterial translocation

- ***Changes at the site of the obstruction:***

Initially venous return is impaired.
↓
Congestion, oedema of bowel wall occurs which turns purple.
↓
Later this jeopardizes the arterial supply.
↓
Loss of shineness, blackish discolouration, loss of peristalsis.
↓
GANGRENE.
↓
Perforation occurs.
↓
Bacteria and toxins migrate into the peritoneum.
↓
PERITONITIS.

> *The coexistence of intestinal colic and borborygmi, establishes the diagnosis of obstruction of the small intestine in more than 9 out of 10 cases.*
> —Clarence Dennis



Fig. 23.3: Intestinal obstruction showing dilated bowel loops.


Obstructed gangrenous bowel
Proximal dilated bowel
Distal collapsed bowel

Fig. 23.4: Gangrenous bowel with proximal dilated and distal collapsed bowel segments.

Note:

- Causes for strangulation are – external like hernia (by constriction ring of the sac), adhesions, bands; compression in the wall causing mechanical block and compromised blood supply like in volvulus, intussusception; increased intraluminal pressure like closed loop obstruction; mesenteric ischaemia.
- Morbidity, poor outcome and mortality are more common in intraperitoneal strangulation than in strangulation of hernia as it is localised with less fluid loss.
- Outcome also depends on age of the patient, extent of the disease and time at which patient reaches for therapy.

- ***Closed loop obstruction*:**
  - When there is obstruction in the large bowel, with ileocaecal valve competence (40%), pressure increases in the caecum.

↓

Stercoral ulcer in the caecum.

↓

Gangrene.

↓

Perforation.

↓

Peritonitis (Faecal).

- Perforation also can occur at the site of obstruction due to the malignant growth.
- Closed loop obstruction also can occur when bowel get obstructed at both proximal and distal parts of the loop of the bowel. It can occur in external or internal hernias, volvulus, etc. Necrosis and perforation are both common at obstructed site and over the convex summit of the bowel content.


(Closed loop)
Dilated loop
Proximal bowel loop
Distal bowel loop
Constriction ring

Fig. 23.5: Closed loop obstruction. Here loop of the bowel is obstructed at its point of entry and exit creating closed loop.


Growth
b
a,b Sites of perforation
a
Stercoral ulcer
Competent
Ileo-caecal valve

Fig. 23.6: Closed loop obstruction.

- ***Bowel distal to the obstruction** is inactive and collapsed.*

Clinical Features



Fig. 23.7: Step ladder peristalsis seen in small bowel obstruction. Note the previous laparotomy scar signifies obstruction is due to adhesions. Laparoscopy and proceed – is the needed management.

- ***Abdominal pain*:**
  - Initially colicky and intermittent: later continuous and severe.
  - Pain is the first symptom to develop which is sudden and severe. Initial colicky pain suggests obstruction and eventual diffuse persistent pain suggests strangulation. Pain begins usually around umbilicus in small bowel obstruction.
  - In small bowel obstruction, it is crampy, recurrent paroxysms occurring as short crescendo/decrescendo episodes (of 30 seconds).
  - In large bowel obstruction, it is of longer episodes of minutes. (In paralytic/adynamic ileus, pain is diffuse and mild).
- ***Vomiting*:**
  - In *jejunal* obstruction, it is early and persistent.
  - In *ileal* obstruction, it is recurrent occurring at an interval; initially bilious later faeculent.
  - In *large bowel* obstruction, vomiting is a late feature.
- ***Distension*:**
  - It is absent or minimal in case of *jejunal* obstruction
  - Obvious with visible intestinal peristalsis (VIP) and borborygmi sounds in case of *ileal* obstruction—*Step ladder peristalsis*.
  - It is enormous in case of *large bowel* obstruction.
- ***Constipation*:**
  - It is *absolute*, i.e. neither faeces nor flatus is passed.

Exceptions:
- Richter's hernia obstruction
- Gallstone obstruction
- Mesenteric vascular occlusion
- Intestinal obstruction with a pelvic abscess

- ***Dehydration*:**
  - Leads to oliguria → renal failure.
- ***Features of toxaemia and septicaemia*:**
  - Tachycardia, tachypnoea, fever, sunken eyes, cold periphery.
- ***Abdominal tenderness*:**
  - It is initially localised but later becomes diffuse – is a feature of intestinal obstruction. Rebound tenderness and guarding will not be present in simple obstructions which are features of strangulation.
- ***Features of strangulation*:**
  - Continuous severe pain, shock, tenderness, rebound tenderness *(Blumberg's sign).*
  - Guarding and rigidity, absence of bowel sounds.
  - In case of strangulated hernia, a swelling which is tense, tender, rigid, irreducible, no expansile impulse on coughing and history of recent increase in size is seen.
- ***Temperature*:**
  - Fever signifies inflammation in the bowel wall/ischaemia/perforation.
  - Hypothermia can occur when septicemia develops due to lack of pyrogenic response. It suggests poor prognosis.
- ***Bowel sounds*:**
  They are increased – high pitched metallic (rushes and groans) sounds followed by metallic tinkling sounds of dilated bowel. Eventually once fatigue occurs or gangrene develops, bowel sounds are not heard – silent abdomen of peritonitis develops. (In paralytic ileus, there are only continuous metallic sounds of dilated bowel).
- ***Per-rectal examination*:**
  - Shows *empty, dilated rectum*, often with tenderness. If rectal growth is the cause for obstruction, it may be palpable.

Investigations

- ***Plain X-ray abdomen***: (initially supine abdominal X-ray is taken; later if needed X-ray in erect posture is taken if perforation is suspected).
  - *Multiple air-fluid levels.*
  - Proximal the obstruction → Lesser the air fluid level.
  - Distal the obstruction → More the air fluid level.

Fire proves gold, adversity proves men.



Fig. 23.8: Plain X-ray abdomen in erect posture showing dilated bowel and colon—a feature of intestinal obstruction.



Fig. 23.9: Multiple air fluid levels in intestinal obstruction.



Fig. 23.10: Plain X-ray abdomen showing multiple air fluid levels due to bowel obstruction.

Normally, *three fluid levels can be seen* in plain X-ray film—at fundus of stomach, at duodenum and often at caecum.

- *Jejunum* shows *concertina effect* due to *valvulae conniventes (Herring bone pattern).*
- *Ileum is smooth and characterless* (by Wangensteen).
- *Large* bowel shows *haustration.*
- *Pneumobilia* (gas in biliary tree) may be due to gallstone ileus.
- Distended caecum is shown as round gas shadow in the right iliac fossa. Dilated caecum signifies large bowel obstruction.
- Small bowel > 3 cm diameter; proximal large bowel > 9 cm; transverse colon > 5.5 cm; sigmoid colon > 5 cm are suggestive of intestinal dilatation. But this increased diameter need not suggest intestinal obstruction everytime.

- *Barium (micro bar solution) enema or gastrograffin contrast enema X-ray* is useful in intussusception. (*Barium meal is usually contraindicated in acute intestinal obstruction*. However dilute (micro bar) barium meal/gastrograffin meal follow through x ray may be done with caution in suspected subacute/partial intestinal obstruction under fluoroscopy, otherwise it may precipitate complete obstruction or may cause perforation and barium peritonitis which is very dangerous).
- Haematocrit, blood urea and serum creatinine; arterial blood gas analysis (acidosis is common), LFT, platelet count. (In severe sepsis there will be altered LFT with thrombocytopenia).
- Serum electrolytes estimation. Hypokalaemia is common.
- Total count is increased. But can be significantly low in severe stage of sepsis.
- ***US abdomen*** is useful to see dilated bowel and fluid in the peritoneal cavity. It is better than X-ray but not as good as CT scan. It has got 95% sensitivity; 80% specificity; 80% accuracy. Doppler US is useful in detecting strangulation.
- ***CT scan*** is very reliable investigation for intestinal obstruction. It has got 93% sensitivity; 94% accuracy and 100% specificity. In CT scan small bowel loop > 2.5 cm suggests dilatation. It can show dilated loop, transition zone and collapsed part which are definitive features of intestinal obstruction. It can also give idea of changes in the bowel wall, ischaemia, strangulation, mesenteric oedema and thickening.

Complications of intestinal obstruction

- Peritonitis
- Hypovolaemic and septic shock
- Renal failure

- ARDS
- Intra-abdominal abscess formation
- Moribund status

Differential diagnosis

- Paralytic obstruction
- Pseudo obstruction
- Ascites

Treatment

- *Nasogastric aspiration*: To reduce toxic effects, to reduce bowel distension which indirectly improves pulmonary ventilation and to reduce possibility of aspiration pneumonia.
- *Replacement of fluid and electrolytes***.**
- *Antibiotics:* Ampicillin, gentamycin, metronidazole, cephalosporins.
- *Blood transfusion*: FFP or platelet transfusions are often needed in critical patient.
- *ICU critical care*: systemic management of complications like ARDS, DIC, SIRS are important. If there is hypotension, dopamine/dobutamine are also needed.
- *CVP for fluid and monitoring*: PCWP (pulmonary capillary wedge pressure) monitoring are often needed in haemodynamically unstable patient.
- *Surgery***:**
  - ***Immediate laparotomy*** is done and the site (by finding the junction of dilated proximal and collapsed distal bowel) and cause of the obstruction is identified. The obstruction is relieved.

To check for viability of bowel, look for

- Peristalsis
- Pulsations
- Bleeding in mesentery and bowel wall
- Friability—friable, flabby muscle is seen in ischaemia
- Colour (black/pink)—dull and lusterless serosa is seen in ischaemia
- Serosal shining

  - If bowel is not viable *resection and anastomosis is done.* A good peritoneal wash is given and the abdominal cavity is drained.



Fig. 23.11: Bowel resection and anastomosis for gangrene in case of intestinal obstruction. Cheatle's cut on the antimesentric margin of the collapsed distal segment is often needed to avoid discrepancy in luminal width. Single layer interrupted (silk/vicryl) or two layered continuous sutures can be used. Single layer is better in acute conditions.

  - Abdomen is closed in layers using nonabsorbable sutures (polyethylene, polypropylene, nylon). Often tension sutures are required.
  - Small bowel can be decompressed using *Savage's decompressor.*
  - In case of *right-sided colonic* obstruction, *right hemicolectomy with ileocolic* anastomosis is done.
  - In case of *left-sided colonic* obstruction, *left hemicolectomy* (resection) and *colo-colic* anastomosis is done with a *defunctioning colostomy* (right-sided transverse) which is closed after 6 weeks.
  - Obstruction due to *rectosigmoid* growth with patient being severely ill—*Hartmann's operation* can be done to save the life of the patient wherein distal stump after removal of the growth is closed, proximal colon is brought out as *end colostomy.*

Postsurgery Complications

- Pelvic abscess.
- Subphrenic abscess.
- Biliary or faecal fistulas.
- Burst abdomen.
- Bands and adhesions.
- Incisional hernias.

An unspoken word never does harm.

DUODENAL ATRESIA

- It is the commonest site of intestinal atresia.
- It is usually a complete stenosis of the second part of duodenum at the level of ampulla of vater.
- It is defective fusion of foregut and midgut with failure of recanalisation
- Incidence is one in 10,000 live births.

Types



Fig. 23.12: Types of duodenal atresia – complete; fibrous cord; duodenal stenosis and Wind-sock deformity.

- Type 1 – Duodenal complete atresia: It is the commonest type (50%). It is usually complete separation with intact wall. In 25% cases complete separation with wall also occurs.
- Type 2 – Fibrous cord.
- Type 3 – Incomplete or partial obstruction. It can be stenosis or web with an aperture.
- Duodenal diaphragm/web can present as complete; incomplete with a fenestra; incomplete diaphragm with central aperture which causes *'wind-sock' deformity* due to proximal dilatation. Here actual diaphragm will be proximal to the site of obstruction.
- Duodenal atresia may be *preampullary* (nonbilious vomiting) or *postampullary* (bilious vomiting). Post-ampullary is common (80-90%).

Associations

- Duodenal stenosis is often associated with annular pancreas.
- It can be isolated duodenal atresia or in association with Down's syndrome (30%)/incomplete rotation of gut (20%)/congenital heart diseases (30%)/trisomy (30%)/anorectal malformations (10%), etc.
- It is commonly associated with maternal polyhydramnios (50%). Antenatal US can confirm it. 50% infants are premature.

Features

- Jaundice.
- Bilious/nonbilious vomiting immediately after birth.
- Features of gastric outlet obstruction.
- Dehydration. Electrolyte changes are common.
- Growth retardation of new born due deprived nutrition (by swallowed amniotic fluid in fetus).

Investigations

- Plain X-ray shows classic *double – bubble sign with absence of air in the distal part*.



Fig. 23.13: Double bubble sign in duodenal atresia.

- In partial obstruction, air may be present in distal loop and so contrast study has to be done. Risk of aspiration in new born infant should be remembered.
- U/S will show distended stomach and proximal duodenum, *rail road track* duodenum and features of associated anomalies. Maternal and fetal ultrasound in pregnancy may identify the pathology and also maternal polyhydramnios.

Treatment

- Proper preoperative preparation like correction of fluid and electrolytes; gastric decompression; TPN;

injection vitamin K; evaluation for associated anomalies.

- *Duodenoduodenostomy* is done. Associated malrotation should be corrected in these patients (Ladd's operation). Side-side duodenoduodenostomy may cause dilated duodenum (megaduodenum – 30%); anastomotic dysfunction; and delayed transit of the content.
- *Kimura's diamond shaped anastomosis* between transversely opened proximal pouch and longitudinally opened distal pouch reduces the problems of anastomosis. Presence of bile in the duodenum and proximal and distal patency should be confirmed by saline irrigation.



Fig. 23.14: Duodenoduodenostomy is ideal in duodenal atresia. Kimura's modification has got lesser chance of developing side effects like gastroparesis.

- Transanastomotic nasojejunal or gastrostomy tube for feeding purpose is needed as prolonged postoperative ileus is the usual problem.
- Duodenojejunostomy may cause blind loop problems. Gastrojejunostomy should not be done due to high incidence of marginal ulceration and bleeding.

SMALL INTESTINE ATRESIA (INTESTINAL ATRESIA)

- It is jejunoileal atresia.
- It is due intrauterine mesenteric vascular accidents (occlusion) of the segments affected. V-shaped mesentery; presence of bile pigments in the distal segments suggesting earlier period of patency – are supportive for the above theory.
- It is often associated with malrotation, gastroschisis, volvulus – 20%.
- Common site is proximal jejunum; next common is distal ileum.
- Maternal polyhydramnios occurs in 35% of jejunal atresia.
- Proximal bowel wall is dilated with hypertrophy but villi are normal. Distal bowel is collapsed but with hypertrophied villi. Narrow collapsed large intestine (microcolon) is seen in proximal atresia.



Fig. 23.15: Typical intestinal atresia.

Griesfield Modification of Martin's Classification of Intestinal Atresia

- Type I – Membranous/mucosal with normal mesentery – 20%.
- Type II – The lumen is atretic – fibrous cord between proximal and distal parts of the segment involved (only one atretic segment) but mesentery is normal – 40%.
- Type III (a) – Atresia with complete separation of proximal and distal ends and V-shaped defect of mesentery – 35%.
- Type III (b) – Atresia with christmas tree-shaped defect in mesentery with distal bowel being supplied by single artery – right colic/ileocolic/superior mesenteric – *apple peel atresia*.
- Type IV – Multiple atresias – 5%.

> *If the hand is kept flat upon the abdomen the underlying coil may be felt to harden and soften alternately much like in a pregnant uterus, in a case of intestinal obstruction.* — Arthur H Burgess


Type I muscosal atresia
Type II fibrous atresia
SMA
Jejunum
Type III a complete single atresia - V mesentery
Type III b- complete jejunal atresia with colied ileum- christmas tree deformity
Type IV multiple atresias

Fig. 23.16: Types of intestinal atresias.

Clinical Features

- Equal in both sexes.
- Commonly infant is of low birth weight.
- Bilious vomiting with features of intestinal obstruction like distension.
- Features of associated anomalies.
- Respiratory distress.
- Jaundice.

Investigations

- Plain X-ray abdomen shows – *triple-bubble appearance* in jejunal atresia; multiple air fluid levels in ileal atresia.
- Barium enema may show narrow microcolon. Calcification suggests antenatal fetal bowel perforation.
- US abdomen to confirm associated anomalies.

Differential Diagnosis

- Other causes of neonatal intestinal obstruction like duodenal atresia, malrotation, volvulus of midgut.



Fig. 23.17: X-ray abdomen of a patient with intestinal obstruction in a new born as neonatal intestinal obstruction.

Treatment

- Resection and anastomosis is the choice of therapy.
- Treatment of associated anomalies.
- Tapering proximal jejunoplasty is done if extensive length of jejunum is involved.
- Prognosis depends on length of atretic bowel; multiple atresias; associated anomalies.

MALROTATION

It is interference in the process of normal rotation of midgut in fetus and its mesenteric fixation.

Stages of Normal Rotation of Midgut

- *Stage 1*: In 4th-8th week of intrauterine period, midgut supplied by superior mesenteric artery (SMA) grows rapidly. As coelomic cavity can not accommo-date growing midgut during that period, it protrudes into the umbilical cord as *physiological hernia*.
- *Stage 2*: In 10th-12th week, midgut migrates into coelomic cavity. First, small bowel returns towards the left side of the abdomen. Then caecocolic loop returns to left lower abdomen. It rapidly rotates 270° counterclockwise to reach right iliac fossa. Then duodeno-jejunal segment rotates 270° counterclockwise to reach left of SMA and behind the colon.
- *Stage 3*: Fusion of different parts of mesentery and posterior peritoneum.

Different Errors of Rotation

- *Stage 1* – Exomphalos major/minor or gastroschisis.
- *Stage 2* – Errors of rotation in this stage is important and is usually considered under malrotation.
  - *Nonrotation* – Causing small bowel in right side; colon in left side; caecum in midline as suspension.
  - *Incomplete rotation* – It is the *commonest type* of malrotation. Caecum is located in subhepatic right hypochondrium. *Ladd's peritoneal band* connects from caecocolic loop to posterior abdominal wall compressing the 2nd part of the duodenum. Entire midgut is hanging down along with SMA with a narrow based mesentery causing midgut volvulus.



Fig. 23.18: Incomplete gut rotation with diagram showing small bowel volvulus.

  - *Reverse rotation* – Final 180° rotation occur clockwise bringing colon posterior to duodenum and SMA.
  - *Hyper rotation* – Rotation up to 360° or 450° causing caecum on left side of the abdomen.
  - Encapsulated small bowel occurs while fetal midgut returns into coelomic cavity.
- *Stage 3* – Final defect in fixation causes mobile caecum and ascending colon leading into caecal volvulus.

Associated Anomalies (20%)

- Congenital diaphragmatic hernia of Bochdalek.
- Prune belly syndrome.
- Duodenal atresia.
- Oesophageal atresia.

Presentations

- Acute/recurrent/subacute intestinal obstruction.
- Midgut volvulus (30%), (usually clockwise rotation) with features of strangulation, perforation, peritonitis.
- Shock, septicaemia, passage of dark blood per rectum, oedema and erythema of anterior abdominal wall.
- In children – failure to thrive, recurrent abdominal pain, cyclical vomiting, constipation and diarrhoea.

Investigations

- Plain X-ray abdomen shows air fluid levels.
- Barium meal (dilute/microbarium) and follow through X-ray is the investigation of choice.
- US abdomen/CT abdomen, if needed.
- Haematocrit, serum electrolytes estimation.

Treatment

- Resuscitation, antibiotics, fluid and electrolytes, blood transfusion.



Fig. 23.19: Ladd's operation for incomplete gut rotation. Ladd's band is released. Duodenum is straightened. Appendicectomy is done.

- *Laparotomy* through horizontal incision is done. Clockwise rotated midgut which is congested and cyanotic is identified. Untwisting of the midgut in counterclockwise direction is done. Viability of bowel is confirmed (colour, vessels in mesentery, peristalsis, on table Doppler). *Ladd's band* is divided *large bowel is repositioned in left side.* The entire duodenum is *Kocherised* and the ligament of Treitz is divided so that *duodenum becomes straight towards right* iliac fossa. This achieves *wide root of the mesentery* and places the *small bowel in the right* side of the abdomen thus preventing further volvulus. A *complementary appendicectomy* is done – *Ladd's operation*.
- After laparotomy, if bowel is gangrenous, it is resected and remaining parts of the bowel are exteriorised as enterostomies. A second look operation is done to look for viability of remaining bowel and also to maintain the continuity. Often it will be extensive bowel resection leading into poor prognosis.

The remedy for injuries is not to remember them.

MECONIUM ILEUS

- It is neonatal manifestation of fibrocystic disease of the pancreas, wherein thick meconium which is viscid and paste like, gets collected in the terminal ileum. Because of inspissation it forms a firm bolus leading to obstruction of the ileum.
- Neonates present with features of ileal obstruction as well as respiratory dysfunction, exocrine pancreatic insufficiency, and high salt in the sweat (Na^+ and Cl^- more than 90 mmol/L).
- Meconium ileus occurs in 15% of patients with cystic fibrosis. Cystic fibrosis is an autosomal recessive disease involving bronchioles, exocrine pancreas and sweat glands. Condition is common in Caucasians. Exocrine pancreatic insufficiency and malabsorption is seen in 90% of patients with cystic fibrosis.
- There is hypertrophy and dilatation of the proximal ileum containing thick, viscid, tenacious dark green meconium. Distal ileum and colon are narrow and contracted having grayish meconium pellets. Meconium gets calcified very rapidly. Gangrene, perforation, volvulus can occur in 50% of cases.
- Intrauterine perforation causes fetal meconium peritonitis which leads to dense adhesions and calcification in peritoneum. Fetal meconium peritonitis is sterile.



Fig. 23.20: Pathology of meconium ileus. Note the meconium pellets in the distal ileum and colon; thick viscid meconium in proximal ileum.

- Plain X-ray shows calcified meconium pellets with multiple air fluid levels which appear as 'soap-bubbles' (*Neuhauser sign*).
- Vomitus of the patient which does not contain trypsin, when poured on the exposed X-ray film will not digest the gelatin of the film whereas the vomitus of individual with normal pancreas will digest the gelatin of X-ray film—*very useful test.*
- Pilocarpine, a cholinergic drug is injected into skin to stimulate the sweating and collected sweat (100 μg sweat) is analysed for sodium and chloride.
- Elevated albumin level in meconium, sodium level assay in nail clipping, serum immune active trypsin assay are other investigations.

Meconium ileus-

- Commonly associated with cystic disease of pancreas but not necessarily always
- Respiratory dysfunction
- Exocrine pancreatic insufficiency
- High salt in the sweat > 90 mmol/L
- Ileal obstruction
- Soap bubble appearance in X-ray
- Gelatin in X-ray film will not get digested by patient's vomitus
- Bishop-Koop operation, ileostomy, dissolving ileal meconium pellets are required

Complications of meconium ileus

- Intestinal bolus obstruction
- Perforation and peritonitis
- Gangrene, volvulus formation

Treatment

Nonoperative measures

- Dissolution through enema can be tried using *gastrograffin* which is hyperosmolar and contains Tween 80 as dissolving agent. *Gastrograffin* is diatrizoate meglamine with Tween 80 (polysorbate 80) as dissolving agent. Acetyl choline (2-4%) also can be used for irrigation per-anally.
- Acetyl choline wash through nasogastric tube also can be used – 5-10 ml 6th hourly.
- Treatment for cystic fibrosis.

Operative measures

- When patient's condition is critical with obstruction, *Bishop-Koop operation* is done. Proximal dilated segment is resected and resected end is anastomosed to side of the distal collapsed ileum. End of the distal ileum is brought out as ileostomy. Through the ileostomy gastrograffin or acetyl cystine wash is given regularly to dissolve meconium pellets. This ileostomy can be kept for long time. Continuity is maintained at later period.
- *Santulli operation* is done where proximal ileum is brought as ileostomy for irrigation using a fine tube and distal ileum is sutured to proximal ileum as end to side anastomosis.
- *Resection and anastomosis* is ideal if patient is fit and if proximal bowel is suitable for anastomosis.

Management of meconium ileus

- *Nonoperative wash per rectally* using acetyl cystine or gastrograffin through Foley's catheter passed per anally. Acetyl cystine can be passed for irrigation per orally through a Ryle's tube as 10 ml 6th hourly.
- *Bishop-Koop and Santulli operations* done in very sick neonates.
- *Resection and anastomosis* is ideal when child is adequately fit.



Fig. 23.21: Bishop-Koop operation. Here distal ileum is brought as ileostomy and proximal part sutured to distal bowel.



Fig. 23.22: Santulli operation done for meconium ileus wherein proximal ileum is brought out as ileostomy. Distal ileum is sutured to proximal.

Causes neonatal intestinal obstruction

- Hirschsprung's disease
- Duodenal atresia
- Intestinal atresia
- Malrotation
- Midgut volvulus/volvulus neonatorum
- Meconium ileus
- Anorectal malformation

INTUSSUSCEPTION (ISS)

Definition

It is telescoping or invagination of one portion (segment) of bowel into the adjacent segment.

Types

1. ***Antegrade***—Most common.
2. ***Retrograde***—Rare (jejunogastric in gastrojejunostomy stoma).

In elderly intussusception:

- Colocolic is most common type
- Apex is formed usually by growth
- No role of hydrostatic reduction

- It can be single or multiple (rare).
- It can be *ileo-colic (most common type, 75%)*, colocolic, ileoileocolic, colocolic.
- It is common in weaning period of a child (common in male), between the period of 6-9 months.

Aetiology

- Idiopathic ISS is common in children, occurs in terminal 50 cm of ileum.
- During weaning, change in diet causes inflammation and oedema of Peyer's patches—may stimulate ISS.
- Upper respiratory tract viral infection which causes oedema of Peyer's patches is also thought as an aetiology for intussusception in children.
- Other causes in adolescents and adults are submucus lipoma, leiomyoma, polyps in jejunum (Peutz-Jegher syndrome), other polyps and carcinomas with papillary projections.

In the field of observation, chance favours only the prepared mind.





Figs 23.23A to C: Intussusception in different patients. Different parts and apex point is also clearly seen.

Causes

- Change in diet during weaning
- Upper respiratory tract viral infection
- Intestinal polyps
- Submucus lipoma
- Leiomyoma of intestine
- Meckel's diverticulum
- Carcinoma
- Purpuric submucosal haemorrhages

Pathology

- ***Apex*** is the one which advances;
- ***Intussuscipiens*** is the one which receives (outer sheath);
- ***Intussusceptum*** are the tubes which advances (middle and inner sheath).
  – Apex and inner tubes will have compromised blood supply which lead to gangrene.
  – Because of ischaemia, apex sloughs off and bleeds, which mixes with the mucus to produce the classic *red-currant jelly* that is passed per anum.
  – Gangrene which sets in leads to perforation and peritonitis.
  – Red currant jelly is not commonly observed in ISS in adult, but it can occur.



Fig. 23.24: Parts of intussusception.

Clinical Features

- Common in males (3:2).
- Common in 6-9 months. But can also occur at later age grouped children.
- Common in spring and winter, coinciding with the gastroenteritis and respiratory infections in respective periods.
- Commonest cause of intestinal obstruction in infancy.
- Initial colicky abdominal pain (75%) which eventually becomes severe and persistent.
- Sudden onset of pain in a male child, with progressive distension of the abdomen, vomiting, with passage of *"red-currant-jelly' stool.*

- Often ISS is recurrent, when it gets reduced, child automatically becomes asymptomatic. (Mother often complains "Bachha rotha he, Bachha sotha he". It means child cries during an episode and sleeps peacefully once it gets reduced.)



Fig. 23.25: Sausage-shaped mass of Intussusception.

- *On examination*, a mass is felt either on the left or right of the umbilicus which is sausage shaped with concavity towards umbilicus, smooth, firm, resonant, not moving with respiration, mobile, *contracts under the palpating fingers.* Often mass appears and disappears.
- Right iliac fossa is empty *(Sign of Dance).*
- After 24-48 hours, abdominal distension appears and increases progressively with features of intestinal obstruction.
- Features of intestinal obstruction with *step-ladder peristalsis.*
- Blood stained stool is often obvious on digital examination of the rectum. Occasionally ISS can be seen per anally and felt with a long mesentery.
- Eventually, gangrene and perforation occurs with features of the peritonitis.

Abdominal palpatory findings in ISS

- Palpable mass (85%)
  - Sausage shaped smooth, firm mass
  - Mass does not move with respiration
  - Mobile in all directions
  - Resonant
  - Mass contracts under the palpating fingers
  - Mass appears and disappears
- Empty right iliac fossa
- Features of intestinal obstruction/peritonitis – later



Fig. 23.26: A rare condition where colonic intussusception has occurred through rectum, coming out per anally. Part is already gangrenous.

Complications

- Intestinal obstruction
- Perforation
- Peritonitis

Differential Diagnosis

In children:	Acute gastroenteritis. Purpura with intestinal symptoms.
In adults:	Carcinoma colon. Mesenteric mass.

Investigations

- Barium enema shows typical *claw sign or coiled spring* sign (Pincer end).
- Ultrasound shows *target sign or pseudokidney sign or bull's eye sign, which is diagnostic***.**
- Plain X-ray abdomen shows *multiple air fluid levels*.

Treatment

Initial management

- Ryle's tube aspiration.
- IV fluids.
- Antibiotics.
- Catheterisation.

Later management

Non operative management

- *Reduction by hydrostatic pressure* using either *saline or microbarium sulphate solution or air* (popular in ***China*).** Barium or saline is infused into the rectum through

Nine-tenths of wisdom consist of being wise in time.



Fig. 23.27. Barium enema showing the typical 'Claw sign' of intussusception.



Fig. 23.28. Barium enema X-ray showing claw sign in intussusception.

a catheter (Foley's catheter). Under fluoroscopy, reduction can be observed. Child will pass large quantity of air and faeces; distension reduces; child shows recovery and stops crying. Air or contrast enters the proximal bowel freely. *Palpable abdominal mass disappears*. Rare complication is perforation of colon. It is done in early stage within 24 hours of presentation. 70% cases of ISS will respond to non-operative method. It is contraindicated in complete obstruction; perforation and peritonitis.

Indications for surgery in ISS

- ISS more than 48 hours
- Features of perforation, strangulation, peritonitis
- Recurrent ISS
- In adult commonly resection is required

Surgery

- *Cope's method:* If reduction does not occur, *laparotomy* is done under G/A. By gently *milking out* the intussusception with warm packs, it is reduced. After reduction, viability of the bowel is checked carefully. If manual reduction is not possible, it is understood that the bowel is likely to be gangrenous which requires resection and anastomosis. In case of viable bowel, often terminal ileum is anchored to the ascending colon and *Jackson veil band is* cut. Patient also requires nasogastric tube aspiration, IV fluids, antibiotics.
- Laparoscopic approach may be used to reduce the intussusception.
- If intussusception persists for more than 48 hours or intussusception in adult requires resection.
  - Ileocolic resection is sufficient.

Recurrence rate

- In hydrostatic reduction – 10%.
- In open manual reduction – 2%.
- In resection – very less < 1%.

VOLVULUS

Definition

It is the *twist (rotation)* in the axis of the loop of the bowel either clockwise or anticlockwise.

- 15% of large bowel obstruction is due to volvulus.
- Sigmoid colon is the commonest site (anticlockwise)—65%.
- Caecum is the second common site (clockwise) (C for C)—30%. It is common in females, present as intestinal obstruction. Resection and anastomosis is the treatment.
- Caecal volvulus is the commonest cause of large bowel obstruction in pregnancy. X-ray shows *round gas shadow* in right iliac region. CT scan is very useful. Barium enema is also helpful.
- Volvulus of small intestine (midgut), volvulus neonatorum, gastric volvulus are other volvulus which can occur.

SIGMOID VOLVULUS (Volvulus of pelvic colon)

- It is common in Asia, common in India (7% of intestinal obstruction) and especially South India because of high fibre diet.

- It is very common cause of large bowel obstruction in Peru and Bolivia due to high altitude.
- More common in males and old age.
- It is common in patients with chronic constipation with laxative abuse.

It is common in –
- Ogilvie's syndrome
- Mentally retarded individuals
- Chaga's disease
- Hypothyroidism
- Anticholinergic drugs
- Multiple sclerosis
- Scleroderma
- Parkinson's disease



Fig. 23.29: Causes of sigmoid volvulus.

Predisposing factors
- Adhesions
- Peridiverticulitis
- Overloaded redundant pelvic colon
- Long pelvic mesocolon
- Narrow attachment of sigmoid mesocolon

- Always rotation is *anticlockwise.*
- It requires *one and half turn* of rotation to cause vascular obstruction and gangrene which eventually leads into perforation either at the root or at the summit of the sigmoid loop.
- Enormous distension of the colon occurs. Sometimes ileum comes to the root of the sigmoid volvulus and encircles it causing ***compound volvulus*** in which case knotted small bowel also becomes gangrenous. ***–ileo-sigmoid knotting.***



Fig. 23.30: Sigmoid volvulus. Note the dilated sigmoid colon.

Types

1. Acute.
2. Recurrent.

Clinical Features

- Pain in the abdomen—Initially left sided, eventually all over.
- Absolute constipation (*obstipation*—no faeces, no flatus).
- Enormous distension of abdomen, starting from left iliac fossa extending to the whole of the abdomen (Tympanic abdomen).
- Late vomiting, and eventually dehydration.
- Features of peritonitis.
- Hiccough and retching can occur.
- *Tyre like feel* of the abdomen is diagnostic.



Fig. 23.31: Dilated sigmoid in early volvulus.

A little may save a deal of friction.

Differential Diagnosis

- *Ogilvies's syndrome* – It is acute colonic pseudo obstruction. It is due to malfunctioning sacral parasympathetic nerves. Splenic flexure is the junction of collapsed and dilated large bowel. Descending colon is atonic causing acute functional obstruction. It may be due to trauma, retroperitoneal irritation, antidepressants, uraemia, diabetes, myxoedema, hypokalaemia, etc. Prokinetic drugs, colonoscopic decompression, tube caecostomy are the treatment.
- Faecal impaction.
- Carcinoma rectosigmoid region.
- Idiopathic megacolon.

Investigations

1. ***Plain X-ray***:(diagnostic in 70-80%)
    - Ω *sign (omega sign)*—single, grossly distended loop of colon arising out of the pelvis and extending towards the diaphragm.
    - *Coffee-bean sign* or Bent-inner tube sign.



Fig. 23.32: X-ray abdomen showing sigmoid volvulus.

2. ***Contrast enema:*** (dilute barium/water soluble contrast media is used)—
    Birds beak sign (ace of spades appearance)—Upper end of barium column tapers into the spirally twisted distal sigmoid colon.
3. ***CT scan*** (for difficult cases)—
    Shows characteristic whirl pattern.

Treatment

- The patient is admitted.
- RT aspiration.
- IV fluids.
- Catheterisation.
- Antibiotics.
- *A flatus tube or Sigmoidoscope* is passed in operation theatre (proper care is taken otherwise it leads to perforation). If it derotates, patient will pass flatus and faeces; and distension reduces.
- If derotation does not occur, laparotomy through midline incision should be done. Dilated sigmoid colon is derotated manually and checked for viability. If viable, it can be fixed to the lateral wall of abdomen or pelvis—***Sigmoidopexy***.
- If sigmoid colon is gangrenous, it is resected and proximal cut end is brought out as colostomy and distal end is brought out as mucus fistula, from the rectum *(Paul-Mikulicz Operation***).** Later after 6 weeks, continuity is maintained after proper preparation.
- Resection of the gangrenous sigmoid done; proximal cut is brought out as end colostomy: distal end closed – *Hartmann's operation*. Later in 6-12 weeks colorectal anastomosis is maintained.
- Primary resection and anastomosis is not advisable because of the contamination and anastomotic leak.

Mortality in sigmoid volvulus is due to *perforation, peritonitis and septicaemia*.



Fig. 23.33: Paul-Mikulicz operation.

PARALYTIC ILEUS (Adynamic intestinal obstruction)

- It is a state in which intestines fail to transmit peristalsis due to failure of neuromuscular mechanism, i.e. Auerbach's and Meissner's plexus.
- It may be localised or generalised.

Causes

- Postoperative
- Infective – pus, blood, bile, toxins, enteritis
- Uraemia
- Hypokalaemia
- Spinal injury
- Retroperitoneal haemorrhage
- Spinal surgery
- Plaster jacket

Clinical Features

- No passage of flatus.
- No bowel sounds.
- Marked abdominal distension.
- Vomiting of large volume of fluid.
- Tachycardia.
- Respiratory distress due to pressure over the diaphragm.
- High pitched tinkling note '*like bells at evening pealing*'.
- Dull abdominal pain (not colicky).
- Features of fluid/protein/electrolyte imbalance.

Investigations

- Serum electrolyte estimation: Especially serum potassium.
- ECG.
- X-ray abdomen.
- Ultrasound abdomen to find out the possible cause of ileus, e.g. sepsis.

Treatment

- Nasogastric aspiration.
- The primary cause is treated.
- IV fluids.
- Electrolyte management.
- Catheterisation and urine output measurement.
- *Do not stimulate the peristalsis ("Don't flog a tired horse").*
  - **Measurement of abdominal girth** is necessary to see whether patient is recovering or not.
  - Decompression of the large bowel can be tried by inserting a flatus tube per anally into the rectum and keeping in place for few hours.
  - Most often, patient recovers in 3-6 days by conservative treatment.
  - In prolonged, life threatening paralytic ileus, laparotomy is done and bowel is decompressed with *Savage's decompressor* and closed with tesion sutures.
- *Catchpole regime*: Adrenergic blocking agent along with cholinergic stimulant (neostigmine) is used rarely only in resistant cases as medical therapy.

ADHESIONS AND BANDS

Adhesions and bands are the commonest causes of intestinal obstruction in Western countries. In India, hernia and then adhesions are the two common causes of intestinal obstruction.



Figs 23.34A and B: Adhesions causing intestinal obstruction.



Figs 23.35A and B: Congenital band causing intestinal obstruction. These bands are often vascular.

Causes

- Infection due to peritonitis, appendicitis, postlaparotomy, and other acute infective abdominal conditions.

It is never too late to give up your prejudices.

- Materials used during surgery can cause dense inflammatory reactions—suture materials like silk, thread, and foreign body, mop, and gauze, talc powder, drugs like sulphonamides and penicillins.
- Ischaemia of bowel due to poor blood supply, sepsis.
- Gynaecological conditions, bowel injury, radiation-induced enteritis, Crohn's disease, other inflammatory bowel diseases.
- Specific conditions like tuberculosis, malignancy.

Types

Type I—Fibrinous adhesions occur during 5-10th post-surgical period. It usually gets resolved completely. It is avascular and flimsy.

Type II—Fibrous adhesions. Due to lack/poor blood supply, bowel gets attached to part of peritoneum or omentum or other parts of the bowel with dense vascular adhesions to maintain blood supply. It will persist and precipitate intestinal obstruction, often-subacute and recurrent type.

Adhesions due to tuberculosis are severe, dense and difficult to separate.

Clinical features

- Pain abdomen—colicky type and recurrent and episodic
- Distension, vomiting
- Constipation
- Reduced bowel sounds on auscultation
- Previous surgical scars commonly observed
- Dehydration, tachycardia, hypotension

Investigations



Fig. 23.36: X-ray showing intestinal obstruction with dilated colon – colonic obstruction.



Figs 23.37A and B: X-ray showing small bowel obstruction with multiple air fluid levels.

- *Plain X-ray abdomen shows dilated bowel loops.*
- *Oral contrast with CT scan is very useful.*
- *In partial obstruction only enteroclysis with water-soluble iodine dyes can be done.*



Fig. 23.38: Methods used to prevent recurrent adhesions and so to reduce the chances of intestinal obstruction. Nobles plication is plication of intestines.

Treatment

Initial Treatment

- IV fluids.
- Nasogastric aspiration.
- Antibiotics.
- Often per anal flatus tube insertion.
- Commonly patient responds in 4-5 days of therapy.

Later Treatment

- Open surgical adhesiolysis using fingers gently.
- *Laparoscopic adhesiolysis* is becoming popular, safer, ideal with less recurrent adhesion rate and gives good results.



Fig. 23.39: Laparoscopic view of dense adhesions – postoperative cause.



Fig. 23.40: Childs-Phillips operation done to prevent adhesive obstruction by plicating mesentery.

- *Noble's plication* of intestines—wherein adjacent coils of small bowel are sutured to prevent in going for further recurrent adhesions.
- *Childs-Phillips mesenteric plication* is similar way of plication of intestinal mesentery, which will prevent crumpling of bowel and adhesion formation.
- Passing long stiff tube from exterior through an opening in the proximal bowel up to the entry in to the large bowel, which acts as intraluminal splinting.



Fig. 23.41: Intestinal intubation via a jejunostomy tube used for adhesions.

- Expandable PTFE membrane barriers or hyaluronic acid and carboxymethyl cellulose membrane barriers are also used.

Prevention of adhesions

- Instilling drugs like hyaluronidase, steroids, dextrans, dextrins, polyvinyls, silicone, fibrinolysins, chondroitins, streptomycins
- Gentle handling of the bowel
- Prevention of spillage of contents like bile, faeces
- Ideal peritoneal wash using 8-10 liters of saline before closing the abdomen
- Careful placing of the drains
- *Laparoscopic procedures has got lesser chance of getting adhesions than open method*

Obstruction due to Bands

- These are *dense fibrous strings* attached from one portion of the abdomen to another area or bowel causing entrapment of intestines leading into obstruction and often dangerous *strangulation.*
- Common causes are vitellointestinal duct, Ladd's band, omental band, postsurgical fibrous band, tuberculous band.
- Clinical features are like of intestinal obstruction.
- Management is release of the band either through laparoscopy or through laparotomy.

The greatest truths are the simplest; and so are the greatest men.

INTERNAL HERNIAS

- It is rare entity.
- A portion of small bowel gets entrapped in one of the retroperitoneal fossae or congenital internal defects (e.g., mesenteric defect).

Sites

- Mesenteric defect; defect in transverse mesocolon.
- Foramen Winslow.
- Diaphragmatic hernia.
- Hernia through duodenal/caecal/appendiceal/intersigmoid retroperitoneal fossae.
- Hernia through broad ligament.

Features

- Herniation occurs in these sites whenever there are adhesions.
- Features of intestinal obstruction – acute/subacute/recurrent.
- Diagnosis is usually on table. But enteroclysis, contrast CT scan are useful.

Treatment

- Release of adhesion, reduction of hernia, if bowel not viable resection and anastomosis.
- Often major vessels may be present adjacent to the constriction ring which may get injured while releasing causing torrential haemorrhage. Decompression is first done prior to reduction.

Self-assessment Questions

- Aetiology pathogenesis, types, management of intestinal obstruction.
- Meconium ileus.
- Sigmoid volvulus.
- Paralytic ileus.
- Intussusception.
- Duodenal atresia.
- Incomplete rotation.
- Ladd's operation.

24

Appendix

Surgical anatomy
Acute appendicitis
Appendicular mass
Appendicular abscess
Faecal fistula after appendicectomy
Mucocele of appendix
Pseudomyxoma peritonei
Neoplasms of the appendix
Laparoscopic appendicoctomy

SURGICAL ANATOMY

It is located at the terminal end of the caecum where three taeniae join, about 2 cm below the ileocaecal orifice. Usually, around 5-10 cm in size but can be varible. Size of its lumen is that of matchstick. Diameter of appendix is 3-8 mm; diameter of lumen is 1-3 mm (matchstick).

Mesoappendix is extension of the mesentery contains appendicular artery, a branch of ileocolic artery. Often an accessory appendicular artery (*of Seshachalam*) may be present. Thrombosis of these vessels leads to gangrenous appendicitis.



Fig. 24.1: On table demonstration of mesoappendix with appendicular artery. Note the appendix (A); mesoappendix (B); caecum (C); ileum (D); taenia (E).



Fig. 24.2: Different anatomical positions of the appendix.

DUPLICATION OF APPENDIX (Wallbridge classification) (Fig. 24.3)

Type A—Partial duplication in a single caecum.
Type B—Two separate appendices in a single caecum.
Type C—Double caecum with each one having one appendix.

- **Most common position** *is retrocaecal (75%). Next common is pelvic (21%).*

Other sites are:

- Preileal—rarest (1%)
- Postileal
- Paracaecal
- Subcaecal
- Subhepatic

Charm strikes the sight, but merit wins the soul.



Fig. 24.3: Duplication of appendix.



Fig. 24.4: Laparoscopic view of subhepatic appendix.

- Often it may be in sub serosal plane leading to difficult dissection during appendicectomy.
- In *situs inversus* appendix is on *the left side.*
- Mucosa of appendix is lined by columnar cells with crypts.
- Submucosa contains numerous lymphatic aggregations (follicles) *('abdominal Tonsil').*
- Opening of the appendix into caecum is guarded by *'valve of Geralch'*.

ACUTE APPENDICITIS

> ***The partial inflammation of the peritoneum, in the Iliac fossa, is sometimes set up by disease in the Appendix caeci…. The appendix having been perforated by ulcerations, occasioned by the lodgement of the faecal concretions in its cavity, extravasation takes place, and inflammation of a more severe and serious kind is originated…. Nature sometimes succeeds in limiting the inflammation to a part of the right side; but it is at other times diffused over the whole abdomen …and quickly proves fatal.***
>
> **—Thomas Hodgkin,** 1836

Aetiology

- It is common in young males.
- It is common in white races.
- Fibre rich diet prevents appendicitis. Less fibre diet increases chance of appendicitis.
- It is common in May and August – seasonal variation – often called as *epidemic appendicitis*.
- Viral infection may cause mucosal oedema and inflammation which later gets infected by bacteria causing appendicitis.
- Family history may be relevant in 30% of appendicitis in children with appendicitis occurring in first degree relatives.
- Obstruction of the lumen of appendix causing obstructive appendicitis.
  - Blockage occurs due to—Faecoliths, stricture, foreign body, round worm or threadworm.
  - Adhesions and kinking—Carcinoma caecum near the base, ileocaecal Crohn's disease.
- Distal colonic obstruction.
- Abuse of purgatives.
- Faecolith is the commonest cause.

Organisms:

E. coli (85%), enterococci, (30%), streptococci, *Anaerobic streptococci, Cl. welchii*, bacteroides.

Pseudoappendicitis is appendicitis due to acute ileitis following Yersinia infection. It is often due to Crohn's disease.



Fig. 24.5: Removed appendix with its mesoappendix.



Fig. 24.6: Severely infected appendix with faecolith inside. Faecolith is one of the causes of obstructive appendicitis.

Pathogenesis

- Acute inflammation of the mucus membrane with secondary infection without obstruction causes *acute non obstructive appendicitis*. It may lead into resolution, fibrosis, recurrent appendicitis or eventual obstructive appendicitis.
- Luminal obstruction by faecolith, lymphoid hyperplasia, pinworm (oxyuris vermicularis), other worms, foreign body, carcinoma/Crohn's disease → mucus and inflammatory fluid collects inside the lumen → increases intraluminal pressure → leads to blockage of lymphatic and venous drainage → resulting in increased oedema of mucosa and wall → causes mucosal ulceration and ischaemia → bacterial translocation → bacterial spread through submucosa and muscularis propria → *acute obstructive appendicitis* → thrombosis of appendicular artery → ischaemic necrosis of full thickness of the wall of the appendix → gangrene of the appendix → perforation at the tip or at the base → peritonitis.



Fig. 24.7: Laparotomy showing perforated appendix with peritonitis.

- After perforation → localisation by greater omentum and dilated ileum occurs → with suppuration and pus inside forming *appendicular abscess*.
- In severe acute appendicitis → localisation can occur by omentum and dilated ileum without pus inside → forming *appendicular mass*.
- Acute appendicitis with blockage at the opening of the lumen → inflammation rarely subsides → mucus collects inside the lumen of the appendix resulting in its enlargement → *Mucocele of the appendix*.

Types

1. ***Acute non obstructive appendicitis (catarrhal):*** Inflammation of mucous membrane occurs with redness, oedema and haemorrhages which may go for following courses:
   - Resolution.
   - Ulceration.
   - Fibrosis.
   - Suppuration.
   - Recurrent appendicitis.
   - Gangrene—Rare initially in non obstructive type but later can occur.
   - Peritonitis.
2. ***Acute obstructive appendicitis*:** Here pus collects in the blocked lumen of appendix which is blackish, gangrenous, oedematous and rapidly progresses leading to perforation either at the tip or at the base of appendix. This leads to peritonitis, formation of appendicular abscess or pelvic abscess. Most often, there will be thrombosis of the appendicular artery.
3. ***Recurrent appendicitis:*** Repeated attacks of non-obstructive appendicitis leads to fibrosis, adhesions causing recurrent appendicitis.
4. ***Subacute appendicitis*** is milder form of acute appendicitis.



Fig. 24.8A

Appendices epiploicae are absent in rectum, appendix and caecum.



Fig. 24.8B

Figs 24.8A and B: Gangrenous obstructive appendicitis – on table.

Clinical Features



Fig. 24.9: McBurney's point is junction of lateral 1/3 and medial 2/3 of spino-umbilical line. McBurney's/Gridiron's/McArthur's incision is perpendicular to this line in this point.

- It is rare before the age of two, common in children and other age groups.
- *Pain*: It is the earliest symptom. Visceral pain starts around the umbilicus due to distension of appendix, later after few hours, somatic pain occurs in right iliac fossa due to irritation of parietal peritoneum due to inflamed appendix. Pain eventually becomes severe and diffuse which signifies spread of infection into the general peritoneal cavity.
- *Vomiting:*due to reflex pylorospasm.

Murphy's triad

- Pain
- Vomiting
- Temperature

- *Constipatio*n is the usual feature *but diarrhoea* can occur if appendix is in postileal or pelvic positions.
- *Fever, tachycardia, foetor oris* are other features.
- *Urinary frequency***:** Inflamed appendix may come in contact with bladder and can cause bladder irritation.
- Tenderness and rebound tenderness at *McBurney's point* in right iliac fossa *(release sign—Blumberg's sign)* are typical.
- *Rovsing's sign***:** On pressing left iliac fossa, pain occurs in right iliac fossa which is due to shift of bowel loops which irritates the parietal peritoneum.
- Hyperextension (in case of retrocaecal appendix — *Cope's psoas test*) or internal rotation (in case of pelvic appendix—*obturator test*) of right hip causes pain in right iliac fossa due to irritation of psoas muscle and obturator internus muscle respectively.
- *Baldwing's test* is positive in retrocaecal appendix—when legs are lifted off the bed with knee extended, the patient complains of pain while pressing over the flanks.
- P/R examination shows tenderness in right side of the rectum.
- Hyperaesthesia in '*Sherren's triangle*'. This triangle is formed by anterior superior iliac spine, umbilicus, pubic symphysis.



Fig. 24.10: Sherren's triangle. It is area of hyperesthesia found in acute appendicitis between anterior superior iliac spine; umbilicus and pubic symphysis.

Often infection gets localised by omentum, dilated ileum and parietal peritoneum leading to *appendicular* *mass.* Often suppuration occurs in the localised area resulting in *appendicular abscess.*

Clinical signs in appendicitis

1. Rovsing's sign
2. Blumberg's sign (Release sign)
3. Cope's psoas test
4. Obturator test
5. Baldwing's test
6. Bastede sign

(Refer fascinating signs for detail)

Acute appendicitis in infancy: Eventhough it is rare, when it occurs, it has got 80% chances of perforation with high mortality (50%).

Acute appendicitis in children: Here localisation is not present, and so peritonitis occurs early. It *requires early surgery.* Dehydration, septicaemia are common.

In elderly: Gangrene and perforation are common. Because of lax abdominal wall, localisation is poor and so peritonitis sets in early.

In pregnancy: Appendix shifts to upper abdomen. So pain is higher and more lateral. After 6 months, maternal mortality increases by 10 times than usual and also leads to premature labour. Appendicitis is the most common non-gynaecologic surgical emergency during pregnancy. Incidence of perforation is highest in 3rd trimester. Surgery is the treatment. Foetal death rate is 5%.



Fig. 24.11: Radiopaque appendix in a plain X-ray. It could be calcified or have calcified content.

Differential Diagnosis for Acute Appendicitis

Many conditions mimic acute appendicitis. It differs in children, adult, elderly and females.

- *Perforated duodenal ulcer*: In duodenal ulcer perforation, fluid trickles down along right paracolic gutter and mimics appendicitis. Upper abdominal pain, obliterated liver dullness, gas under diaphragm in X-ray and CT scan differentiate it from acute appendicitis.
- *Acute cholecystitis*: Pain in right upper abdomen, fever, jaundice, upper abdominal guarding are the features of acute cholecystitis. US; HIDA scan, LFT will differentiate it from acute appendicitis.
- *Acute pancreatitis*: Pain in epigastrium, radiating to back, raised serum amylase and lipase, CT abdomen with a history of alcohol intake often are diagnostic.
- *Right ureteric colic*: Pain is colicky in nature which often refers to genitalia. Haematuria, urinary symptoms are common. It mimics retrocaecal/pelvic acute appendicitis. Often in ureteric stone, abdomen is soft and nontender. CT is the important way to differentiate.
- *Acute typhlitis*: Inflammation of caecum is called as typhlitis. Often it is difficult to differentiate it from acute appendicitis. Intravenous/oral metronidazole completely controls the disease.
- *Acute bacterial enterocolitis*: It presents with pain abdomen, diarrhoea, toxaemia, dehydration. Often it is difficult to differentiate from acute appendicitis.
- *Acute mesenteric lymphadenitis* is difficult to differentiate from acute appendicitis. It is treated conservatively. CT may be helpful to identify it. Laparoscopic evaluation is ideal.
- *Right sided acute pyelonephritis*: Here there will be pain and tenderness in loin. Urine analysis, US are diagnostic. Often DTPA scan may be needed.
- *Crohn's disease* presenting with acute symptoms will have similar features of acute appendicitis.
- *Pelvic inflammatory disease* like salpingo-oophoritis mimics acute appendicitis. Twisted/haemorrhagic/ruptured ovarian cyst/ruptured ectopic gestation/endometriosis/tuboovarian abscess mimics acute appendicitis. US, laparoscopy helps to differentiate it from others. *Mittelschmerz* is lower abdominal pain due to rupture of follicular cyst during midcycle. It subsides on its own. There are no systemic features.
- *Meckel's diverticulitis* presents clinically like acute appendicitis. It is not possible to differentiate between two clinically.
- *Intussusception* mimics acute appendicitis in children. ISS is common before the age of 2 years. Acute appendicitis is rare before the age of 2 years. Palpable mass, features of intestinal obstruction, barium enema X-ray, US are useful methods to differentiate.
- *Worm infestation (round worm bolus/ball):* It often presents as pain in right iliac fossa. Features of intestinal obstruction are common here.

Perforated appendix rarely causes pneumoperitoneum.

- *Right-sided lobar pneumonia* and pleurisy are often not easy to differentiate from acute appendicitis. Pleural rub, change in breath sounds, chest X-ray can identify pneumonia.
- *Testicular torsion/acute severe orchitis* often look like acute appendicitis. Referred pain in iliac fossa, and if scrotum is not palpated clinically these conditions are mistaken for acute appendicitis. These problems are much more obvious if *testis is undescended* one.
- *Sigmoid diverticulitis* in elderly with loop lying towards right side may present as pain in the right iliac fossa.
- *Carcinoma caecum* may present with features of acute appendicitis without any earlier typical features.
- *Ruptured aortic aneurysm, acute intestinal obstruction, mesenteric ischaemia* may present like acute appendicitis.
- Rare conditions like pre herpetic pain of the right 10th and 11th dorsal nerves may mimic acute appendicitis. Guarding and rigidity will not be present. There will be significant hyperaesthesia.
- Tabetic crisis, tuberculosis of spine, secondaries in spine, multiple myeloma, osteoporotic pain often can mimic acute appendicitis.
- Acute crisis of porphyria and diabetes mellitus mimic acute appendicitis with severe abdominal pain.

Differential diagnosis

- Perforated peptic ulcer
- Ruptured or twisted ovarian cyst
- Acute cholecystitis
- Right ureteric colic
- Enterocolitis
- Right acute pyelonephritis
- Mesenteric lymphadenitis
- Lobar pneumonia
- Crohn's disease
- Acute pancreatitis
- Meckel's diverticulitis
- Acute crisis of porphyria
- Salpingitis
- Diabetic abdomen
- Ectopic gestation-ruptured
- Typhlitis

Differential diagnosis in children

- Meckel's diverticulitis
- Acute colitis
- Acute iliac lymphadenitis
- Intussusception
- Roundworm colic
- Lobar pneumonia

Differential diagnosis in females

- Ruptured ectopic gestation
- Mittelschmerz rupture of ovarian follicle during mid menstrual period
- Ovarian cyst torsion
- Salpingo-oophoritis

Differential diagnosis in elderly

- Acute diverticulitis
- Carcinoma caecum – acute features
- Mesenteric ischaemia
- Intestinal obstruction
- Aortic aneurysm leak
- Crohn's disease

Sequelae of acute appendicitis

- Resorption
- Relapse and recurrent appendicitis
- Appendicular mass
- Appendicular abscess
- Perforation - has got 20% mortality
- Peritonitis
- Portal pyaemia

Investigations

- Total leucocyte count is increased.
- U/S is done to rule out other conditions like ureteric stone, pancreatitis, ovarian cyst, ectopic pregnancy and also to confirm appendicular mass or abscess.
- Laparoscopy is the most useful method.

Sonographic Criterias for Appendicitis (85% specificity)

- Noncompressible appendix of size > 6 mm AP diameter.
- Appendicolith.
- Interruption of submucosal continuity.
- Periappendicular fluid.



Fig. 24.12: Ultrasound visualisation of appendix.

- Contrast CT scan is very much useful when diagnosis is difficult especially in old people. Dilated appendix; dilated lumen; thickened wall; non filling of the lumen by contrast or air; periappendicular fluid collection; presence of mass/abscess/associated pathology like carcinoma can be identified. It has 95% sensitivity and specificity with 95% accuracy.

***Alvarado scoring** for appendicitis:*	*Score*
***M**igrating pain*	1
***A**norexia*	1
***N**ausea and vomiting*	1
***T**enderness in right iliac fossa*	2
***R**ebound tenderness*	1
***E**levated temperature*	1
***L**eucocytosis with count more than 10,000*	2
***S**hift to left with neutrophilia in peripheral smear*	1
Total score	10
Score less than 5: Not sure. Score between 5-6: Compatible. Score between 6-9: Probable. Score more than 9: Confirmed.	

Treatment

Surgery-Appendicectomy:

Approaches:

1. ***Gridiron's incision*** (*McBurney's incision*): Incision is placed perpendicular to the right spino-umbilical line at the McBurney's point (i.e. at the junction of lateral one-third and medial two-third of spino-umbilical line). (Gridiron is a frame of cross beams to support a ship during repairs. This incision was first described by *McArthur*).



Fig. 24.13: Approaches for appendicectomy.

2. ***Rutherford Morison's muscle*** cutting incision (*Muscles are cut upwards and laterally*).
3. ***Lanz crease incision*** centering at McBurney's point—cosmetically better.
4. ***Right lower paramedian incision/lower midline incision***—when in doubt or when there is diffuse peritonitis.
5. ***Laparoscopic approach:*** Becoming popular and better.
6. ***Fowler-Weir approach*** by cutting muscle medially over the rectus.



Fig. 24.14: Appendix, on table during appendicectomy.

Procedure

- Under general anaesthesia, skin is incised. Two layers of superficial fascia are cut. External oblique aponeurosis is opened in the line of incision. Internal oblique and transverse muscles are split in the line of fibres. Peritoneum is opened in the line of incision. Caecum is identified by taeniae, and ileocaecal junction. Omentum when adherent is separated. Appendix is held with Babcock's forceps. Meso-appendix with appendicular artery is ligated. Using thread or silk, a purse—string suture is placed around the base of the appendix. Base of the appendix is crushed with artery forceps and transfixed using vicryl (absorbable). Appendix is cut distal to the suture ligature and removed. Stump is cleaned with antiseptics. Purse string suture is tightened so as to bury the stump.
- In difficult cases—*Retrograde appendicectomy* can be done. In presence of pus or burst appendix, the peritoneal cavity is drained.

Poverty knows how extremely expensive it is to be poor.


Incision
Mesoappendix
Appendicular artery
Transfixation
Transfixation
Ligation
Cutting appendix
Appendix stump
Closure

Fig. 24.15: Steps in open appendicectomy. Note the base of appendix, mesoappendix; its ligation; transfixation of the base using 2 zero vicryl; cutting of appendix and closure of the wound. Burying is not essential; it is optional. Burying is done using silk/vicryl using purse string suture.

- Postoperatively, IV fluids, antibiotics are given. Once bowel sounds are heard, oral diet is started.



Fig. 24.16: Gangrenous appendix. It is gently ligated at the base using 2 zero vicryl. It is not buried as stump will be friable. (Burying is not necessary to any appendicectomy).



Fig. 24.17: Transfixation of the base of appendix using 2 zero vicryl is an important step after secured ligation of appendicular artery.

Complications after appendicectomy

- Paralytic ileus
- Reactionary haemorrhage due to slipping of ligature of the appendicular artery



Fig. 24.18: Faecal fistula after appendicectomy. Most of the time faecal fistula subsides by conservative treatment unless there is distal obstruction or specific causes like Crohn's, tuberculosis or malignancy.



Fig. 24.19: Wound infection after appendicectomy in patient with burst appendicitis.

- Residual abscess (pelvic, paracolic, local, subdiaphragmatic)
- Pylephlebitis (Portal pyaemia)
- Adhesions, kinking and intestinal obstruction
- Right inguinal hernia *(direct)*—due to injury to ilioinguinal nerve
- Wound sepsis 10%
- Faecal fistula
- Respiratory problems and DVT

Troubles in Appendicectomy

- During surgery if appendix is found normal, other cause for symptoms should always be looked for like Meckel's diverticulum, Crohn's disease, ovarian/pelvic causes in females, malignancy, etc.
- Appendicular tumour may be found. If it is in the tip, appendicectomy is sufficient. It could be carcinoid tumour. If it is in the base right hemicolectomy is done.
- Absence of appendix – a rare occasion can occur. Caecum and taeniae should be traced properly before finalising it.
- Appendicular abscess/pelvic abscess formation.
- Malignancy in the caecum is identified on table - right hemicolectomy should be done.
- If Crohn's disease is identified during surgery, appendicectomy can be done with care, if base of the appendix is normal. But in rare occasion where appendix is involved by Crohn's disease, appendicectomy should not be done but treated only with antibiotics and steroids, otherwise fistula can develop.

Portal pyaemia

- It is rare nowadays
- It is septic portal system thrombosis
- Commonly seen in immunosuppressed individuals
- Infection spreads to liver through portal vein causing rapid multiplication of virulent organisms leading into septicaemia (toxaemia with hypotension, tachycardia), jaundice, tender palpable liver. Patient will be drowsy
- Treatment – antibiotics like cefoperazone, amikacin, metronidazole, meropenem; fluid management; ventilator support
- It carries poor prognosis

INCIDENTAL APPENDICECTOMY

- Here removal of normal appendix is done at laparotomy for other conditions, e.g. hysterectomy.
- It is done in vague lower abdominal pain of doubtful severity.
- It is a useful procedure to tackle *'Munchausen syndrome,* i.e. the patient is always worried of pain abdomen and gets relieved after the procedure (psychological benefit).
- It is done along with Ladd's procedure for malrotation.
- It is also done during on table colonic lavage *(Doodleys lavage)*.

Remember

- Appendicitis is common in white races, young males and in those who are on westernised diet
- It most commonly affects individuals of age group 10-20yrs. 2/3rd will develop perforation due to rapid progression and poor localisation
- Gangrene, perforation and peritonitis are rare in non obstructive type; but recurrent appendicitis of non obstructive origin can cause perforation
- Pneumoperitoneum is not common in appendicular perforation
- Appendicular artery which is an end artery can undergo infective thrombosis and can cause gangrene and perforation
- In retrocaecal appendicitis rigidity is not common; psoas spasm is known to occur
- Pelvic and post ileal appendicitis can cause diarrhoea. Post ileal appendicitis is difficult to diagnose
- It is difficult to remove sub hepatic appendix through McBurney's incision
- Pain will be above and lateral in appendicitis in pregnant women. Appendicitis is the commonest acute abdominal condition in pregnancy (1:1500 pregnancies). Incidence of foetal loss is 5% without perforation and it becomes 20% if there is perforation. It is better to do laparotomy to remove the appendix in pregnancy
- In elderly atypical features are more common and so diagnosis is often missed. Gangrene and perforation are common in elderly. Often it mimics subacute obstruction
- In obese patients diagnosis is often difficult
- Appendicitis is rare before 2 years. But when it occurs perforation and peritonitis are common carrying poor prognosis

Those who can't hear the music think the dancer's mad.

- In children with appendicitis, there is poor localisation and so peritonitis is common. So conservative therapy should be avoided. Surgery is the only choice of treatment otherwise early peritonitis is the danger.
- Appendicular mass is initially treated with *Ochsner Sherren* regime. After 6 weeks, *interval appendicectomy* is done.
- Children, old age, faecolith, laxative abuse, diabetes mellitus, immunosuppression and pelvic appendix are high risk factors for perforation in appendicitis
- In pelvic and retrocaecal appendicitis, adjacent ureteral inflammation can occur in which urine on analysis shows blood cells and pus cells
- Incidence of removal of normal appendix is 30%
- *Stump appendicitis* is inflammation and infection in the remaining portion of the appendix in the stump after appendicectomy. It is a rare entity

APPENDICULAR MASS (Periappendicular Phlegmon)

- It is the localisation of infection occurring 3 to 5 days after an attack of acute appendicitis.



Fig. 24.20: Appendicular mass—a well localised mass.

- Inflamed appendix, greater omentum, oedematous caecum, parietal peritoneum and dilated ileum (Ileus) forms a mass in the right iliac fossa.
- This mass is tender, smooth, firm, well localised, not moving with respiration, not mobile, all borders well made out (well localized) and resonant on percussion. Patient may have fever and features of toxicity.



Fig. 24.21: Appendicular mass is formed by dilated ileum; greater omentum; inflamed appendix and caecum. It is resonant, smooth, firm, and tender with well defined borders which does not move with respiration and does not have mobility.

Differential diagnosis

Carcinoma caecum	Actinomycosis
Crohn's disease	Mesenteric lymphadenitis
Ovarian disease	Ruptured ectopic pregnancy
Twisted ovarian cyst	Ileocaecal tuberculosis

Investigations

- TC is increased.
- U/S confirms the mass.

Treatment

Conservative (***Ochsner-Sherren Regimen***), as nature has already localised the infection, if now disturbed will cause faecal fistula.

Includes observation–
- Temp, BP, Pulse chart.
- *Marking the mass to identify the progression/regression*.
- Antibiotics (Ampicillin, metronidazole, gentamycin, or other drugs given depending on severity and requirement).
- IV fluids.
- Analgesics.
- Initial nasogastric aspiration.
  - Patient usually shows response by 48 to 72 hours and mass reduces in size, temperature and pulse becomes normal. Appetite is regained. 90% of patients respond to conservative therapy.
  - Patient is discharged and advised to come *for* ***interval appendicectomy*** after 6 weeks.

Criteria to discontinue *Ochsner-Sherren* regimen:
1. Patient becomes more toxic (tachycardia, high fever)
2. Persistent vomiting
3. Increase or spread of pain abdomen (means onset of diffuse peritonitis)
4. Increased size of the mass
5. Suppuration (abscess formation) in the mass

In these patients the regimen is discontinued. The patient is taken for immediate surgery, either through laparotomy or through classic approaches

Contraindications for Ochsner-Sherren Regimen
1. When diagnosis is in doubt.
2. In acute appendicitis in children and elderly.
3. In burst, gangrenous appendicitis.
4. In patients in whom diffuse peritonitis sets in.

APPENDICULAR ABSCESS

- It occurs due to suppuration in an acute appendicitis or suppuration in an already formed appendicular mass.
- Abscess commonly *occurs in retrocaecal* region but often can occur in subcaecal, preileal lumbar or postileal regions.
- *Pelvic abscess is also common after an attack of acute appendicitis*.



Fig. 24.22: Appendicular abscess. Swelling with ill-defined lower border.

Clinical Features

- High fever, features of toxicity, tender, smooth, dull (to percuss), soft swelling in right iliac fossa which lies towards right lateral and lower side with clear upper margin but indistinct lower margin.
- U/S confirms the diagnosis.



Fig. 24.23: Different sites where abscess can occur after appendicitis – retrocaecal, appendicular; pelvic; subphrenic; preileal and lumbar. Portal pyaemia can occur with multiple pyaemic abscesses in the liver.

Treatment

- Antibiotics are started.
- Under G/A, incision is made in the lower lateral aspect of the swelling above the inguinal ligament. Skin, external oblique muscle is cut. Abscess cavity is opened and pus is drained *extraperitoneally*, which is sent for culture and sensitivity. Wound is closed. A drain is placed through a separate incision. Antibiotics are continued.
- *Interval appendicectomy is done after 3 months.*

Pelvic abscess is drained per-rectally or through posterior colpotomy (in females).

FAECAL FISTULA AFTER APPENDICECTOMY

Causes

- It can occur when appendicectomy is done in gangrenous/perforated/friable base appendix.
- It can occur after drainage of appendicular abscess.
- It can occur if appendicectomy is done/attempted in appendicular mass.
- If there is underlying additional pathology like Crohn's disease/carcinoma/ileocaecal tuberculosis/actinomycosis during appendicectomy, fistula can occur.

Features

- Faeculent, foul smelling discharge from either main wound or drain site.
- Features of infection.

An essential aspect of creativity is not being afraid to fail.



Fig. 24.24: After appendicectomy fistula can occur. Note the faecal discharge.

- Skin excoriation.
- Features suggestive of cause.

Investigations

- CT fistulogram to delineate the track.
- CT scan abdomen to find out the other pathology.
- Other relevant investigations, Hb%, albumin level, etc.

Treatment

- Conservative – antibiotics, IV fluids, dressing, zinc oxide cream over the skin, observation.
- Most of the time fistula subsides provided there is no distal obstruction by adhesions or kinking or specific causes like carcinoma or tuberculosis.
- If persists even after 6 weeks, resection of ileocaecal segment and anastomosis is done.

MUCOCELE OF APPENDIX

- It can be neoplastic or non neoplastic.
- It occurs when proximal end of the lumen of appendix gets slowly and completely occluded, usually by a fibrous stricture causing collection of sterile fluid (mucus) in the lumen. It is a retention cyst.
- Appendix is grossly enlarged with features of subacute appendicitis.
- Mucocele can get infected leading to *empyema* of appendix.
- Rupture of mucocele can lead to *pseudomyxoma-peritonei*. Neoplastic type causes generalised pseudomyxoma peritonei; non neoplastic type causes localised pseudomyxoma peritonei.
  (Other cause for pseudomyxoma-peritonei is ruptured mucinous carcinoma of ovary).
- Often mucocele of appendix is also caused by a mucus secreting adenocarcinoma and if it is so right hemicolectomy is done.

Clinical Features

- Colicky pain in right iliac fossa.
- Tenderness in the right iliac fossa.

Investigations

- U/S abdomen.

PSEUDOMYXOMA PERITONEI

- Jelly like mucoid yellowish-brown substance accumulates in peritoneal cavity
- Due to ruptured adenocarcinoma appendix/ mucocele or mucinous carcinoma of ovary
- Common in females
- Painless progressive distension of abdomen with intestinal obstruction occurs eventually
- Shifting dullness is absent
- Surgical debulking, oophorectomy, appendicectomy, omentectomy are often done
- Chemotherapy is useful—Cisplatin
- Carries poor prognosis

Treatment

- Appendicectomy.

Note: Pseudomyxoma peritonei is presently considered to be due to neoplastic adenocarcinoma of appendix with gelatinous fluid collection in the peritoneal cavity. It is also seen in cystadeno carcinoma of ovary. Treatment is surgery and chemotherapy.

NEOPLASMS OF THE APPENDIX

- It is rare.
- It is often post appendicectomy histological diagnosis.
- ***Cystic neoplasms of appendix*** – Simple cyst (non neoplastic mucocele); mucinous cystadenoma; mucinous cystadenocarcinoma (commonest form of cystic neoplasms); pseudomyxoma peritonei. Simple cyst is non neoplastic obstruction of the lumen and is less than 2 cm in size which contains mucin. Mucinous cystadenoma attains progressively large size of up to 8 cm with CT showing calcification of the wall. Laparoscopic appendicectomy is not used in mucinous cystadenoma. Hemicolectomy is done in mucinous cystadenocarcinoma and cystadenoma of large size and if base is involved.
- ***Carcinoid tumour*** is the commonest type. It is less aggressive. It is often incidentally found. It is arising from Kulchitsky cells in crypts of Lieberkuhn (argentaffin tissue). It is ten times more common than other types. (One in 400 appendices). Commonly its location is in the tip. 75% are less than 1 cm; 15% are 1-2 cm; 10% are > 2 cm in size. It stains chromograninB immuno-histo chemically. Distant and nodal spread occurs if tumour is more than 2 cm.

Carcinoid of appendix may be goblet cell type or classical type histologically. Goblet cell has got more mortality than classic type. Treatment is appendicectomy. Right hemicolectomy is done if base is involved or size is more than 2 cm or nodes are involved. 5 year survival is 90%.

- ***Primary adenocarcinoma of the appendix*** is rare. It can be mucinous (common) or colonic (less common) type. Acute presentation as appendicitis is common in colonic type. It is staged as Duke's staging A, B, C and D. 5 year survival rate for each is 100%; 65%; 50% and 5% respectively. Mucinous type has got better prognosis. 5 year survival for mucinous type is 70% and colonic type is 40%. Mucinous type can rupture into the peritoneal cavity and can cause pseudomyxoma peritonei.



Figs 24.25A and B: Carcinoid tumour in two different patients. If it is in the tip or away from the base, then appendicectomy is sufficient. If it is in the base or extending into the caecum then right hemicolectomy is needed.

Tumours of the appendix

- Carcinoid tumour—commonest site is appendix
- Primary adenocarcinoma of appendix
- Mucocele of appendix leading in to pseudomyxoma peritonei

LAPAROSCOPIC APPENDICECTOMY

This is newer, popular and ideal method of appendicectomy.

Advantages

- Diagnosis is confirmed.
- Other parts of the abdomen are visualised.
- In females pelvic structures are assessed properly.
- Trauma of access is less.
- Faster recovery.
- Laparoscopic appendicectomy is definitely better whenever there is vague abdominal pain; atypical pain; situs inversus; in women; subhepatic appendix and as interval appendicectomy.

Disadvantages

- Technical difficulties especially in burst appendix.
- Cost factor and availability.

Note: Consent for conversion should be taken.

Technique

- Procedure is done under general anaesthesia. Head down position with right tilt is needed. Surgeon and camera man stands on the left side. Scrub nurse on the right side. Monitor is kept on the foot end right side.
- 10 mm camera port is placed at the umbilicus. Working ports are two 5 mm, one on each side of lower abdomen or one on left side and another on the lower midline. One of the working ports can be 10 mm in difficult appendectomies.



Fig. 24.26: Different possible port placements for appendicectomy.

Art is long, life short, judgement difficult, opportunity transient.



Figs 24.27A and B: Laparoscopic appendicectomy. Note the mesoappendix is being cauterised. Ligation of the appendix is done using vicryl. (*Courtesy by Dr Keshava Prasad MS, KMC Mangalore*).

- Pneumoperitoneum is created using CO2.
- Appendix is held with grasper or *Babcock's forceps*. Mesoappendix is cauterised by bipolar or unipolar cautery.
- Appendix is dissected upto the base of the appendix.
- Base of the appendix is ligated with loop ligature. Intracorporeal ligature also can be placed using vicryl 2 zero suture material. Appendix is removed through 10 mm working port along with reducer. Often retrieval bag can be used to remove the appendix.
- Umbilical port is closed in two layers. Other ports are closed by skin sutures. If gangrenous or burst appendix drain can be placed through one of the ports.
- Oral food is started in 12 hours.

Laparoscopic assisted appendicectomy can be done if caecum is mobile without much adhesions and mobilised appendix can be delivered through the 10 mm umbilical port. As in regular laparoscopic procedure, appendix is identified and mobilised. Appendix which is not friable and not turgid can be delivered through umbilical port gently. During this procedure gas flow should be stopped so that all gas in the cavity will be empty. Mesoappendix is ligated. Appendix is transfixed like in open method and removed. Stump is pushed back into the place. Telescope is passed again to confirm the position and security of the stump. Advantage is that it is faster.

Complications

- Injury to bowel, vessels while passing the ports.
- Complications of pneumoperitoneum.
- Accidental cautery injury to bowel, vessels and other vital structures.
- Bleeding.
- Bowel perforation, peritonitis.



Fig. 24.28: Laparoscopic assisted appendicectomy.

- Ligature slipping, leak, peritonitis, fistula formation.

Self-assessment Questions

- Acute appendicitis –causes, clinical features, and management.
- Appendicular mass.
- Appendicular abscess.
- Differential diagnosis for acute appendicitis.
- Mucocele of appendix.
- Ochsner-Sherren regime.
- Appendicectomy.
- McBurney's incision.
- Complications of appendicectomy.
- Differential diagnosis of mass in the right iliac fossa.
- Carcinoid tumour.
- Laparoscopic appendicectomy.

The lie you tell today will force you to lie again tomorrow also.

25

Rectum and Anal Canal

Anatomy
Per-rectal examination
Proctoscopy
Sigmoidoscopy
Colonoscopy
Carcinoma rectum
Solitary ulcer syndrome
Rectal prolapse
Anorectal malformations
Pilonidal sinus
Haemorrhoids (Piles)
Anal fissure: *Sentinel pile*
Anorectal abscess
Fistula-in-ano
Anorectal strictures
Malignant tumours of anal canal
Condyloma acuminata
Anal intraepithelial neoplasia (AIN)
Anal margin tumours
Sacrococcygeal teratoma
Anal incontinence
Descending perineal syndrome
Proctitis
Proctalgia fugax
Hidradenitis suppurativa of anal region
Pruritus ani
Gastrointestinal haemorrhage

ANATOMY

Rectum

- It is the distal portion of the large gut, placed between the sigmoid colon above and anal canal below; in front of last three pieces of sacrum and coccyx (From S3).
- The three cardinal features of large intestine (sacculation, appendices epiploicae and taeniae) are absent.
- The upper third of rectum is covered by peritoneum on front and sides, mid third only on the front, lower third is infraperitoneal.
- The rectum is pulled forward by the puborectalis muscle forming the anorectal sling which is primarily responsible for rectal continence.
- It has got three lateral flexions left, right and left from below upwards (*Valves of Houston*).

Rectosigmoid Junction

- Implies a segment of bowel comprising the last seven centimetre of sigmoid colon and upper five centimetre of rectum.


Ano-rectal junction
Anal column
Anal valve
Pectinate line
Pecten
White line of Hilton

Fig. 25.1: Interior of the anal canal.


Circular muscle
Puborectalis
Longitudinal muscle
External sphincter
Fibro-elastic septa
Skin

Fig. 25.2: Sphincters of anal canal.

- On sigmoidoscopic examination it is taken as a point 15 cm from the anal verge.

Supports of Rectum

- Pelvic floor.
- *Fascia of Waldeyer*: It is the condensation of pelvic fascia behind rectum, contains superior rectal vessels and lymphatics.
- *Lateral ligaments of rectum*: It is the condensation of pelvic fascia, attaches rectum to the postero-lateral wall of lesser pelvis.
- *Denonvillier's fascia:* It is the fascial condensation which separates rectum from prostate in males and vagina in females.
  - Rectum is supplied by rich network of vessels that originates from superior and middle rectal arteries and median sacral artery.
  - Lymphatic drainage from upper half of rectum is to inferior mesenteric nodes; from lower half to internal iliac nodes.

It is innervated by autonomic nervous system; sympathetic (L_1, L_2) is motor to sphincter and inhibitory to musculature; parasympathetic (S_{234}) is motor to musculature and inhibitory to sphincter. Sensation of distension is carried through parasympathetic; pain sensation is carried by both.

Anal Canal

- It is 4 cm long, extends from levator ani muscle to anal verge.
- The *dentate line* represents the former site of the embryonic anal membrane.
- The lining of the canal above this line is columnar epithelium and below is skin.
- The mucosa above this line has an autonomic nerve supply, below is by pudendal nerve.
- The venous drainage above this line is by inferior mesenteric and portal circulation, whereas below to systemic venous circulation.
- Internal haemorrhoids develop above this line.

Sphincters of Anal Canal

Internal sphincter: Downward extension of circular muscle of rectum, under control of autonomic nervous system.

External sphincter: Surrounds the internal and continuous with the levator muscle.

Blood supply is from inferior rectal artery.

Venous drainage: Internal rectal venous plexus lies in the submucosa of the anal canal. It drains mainly into the superior rectal vein but communicates freely with external plexus. It is an important site of porta- systemic communication. They are situated in anal column at 3,7,11 o' clock. Their saccular dilatation forms *'primary internal piles'*.



Fig. 25.3: Blood supply of rectum.

PER-RECTAL EXAMINATION (Digital examination of the rectum)

> ***We had almost come to the conclusion that the case (of vasovesiculitis) was one of acute appendicitis, but decided to make a rectal examination for the sake of completeness.***
> **— Ulysses Grant Dailey, W.S. Grant,** 1924

No abdominal examination is complete without a per rectal examination

a. It is done to palpate—
   1. Carcinoma rectum.
   2. Stricture rectum.
   3. Polyps.
   4. Thrombosed piles.
   5. BPH and carcinoma prostate.
   6. Secondaries in the recto-vesical pouch (Blumer shelf).
   7. Sphincter tone.
   8. Pelvic abscess (is felt as boggy swelling).

b. To feel the internal opening of anal fistulas.

c. In bimanual palpation of the bladder or pelvic tumours.

d. In acute abdominal conditions—it reveals dilated empty rectum with tenderness.

In the case of acute abdomen, it is more important to insert the finger into the lower end than to put the thermometer into the upper end of the alimentary tract. — Sir Zachary Cope

Positions for P/R Examination

- Right lateral position.
- Left lateral position.
- Dorsal position in ill-patients.
- Lithotomy position.
- Knee-elbow position.
- Picker position: Patient in standing position leans forward by grasping a chair or stool. This method is used to palpate seminal vesicles which is involved by tuberculous seminal vesiculitis (as craggy feeling) or in trichomonas vaginalis infestation of seminal vesicle.

Per-rectal examination is contraindicated in acute fissure in-ano.

PROCTOSCOPY (Kelly's)

Indications

a. *Diagnostic*—Piles, fissure in ano, polyps, stricture, etc.
b. *Therapeutic*—Injection therapy for partial prolapse or piles, cryotherapy for piles, polypectomy, biopsy for carcinoma rectum or anorectum.



Figs 25.4A and B: Types of proctoscopes: (A) Non-illuminating, (B) Illuminating.

Types

a. Illuminating.
b. Nonilluminating.

Parts (10 cm)

Proctoscope is conical shape, with proximal diameter more than the distal, so as to illuminate the light at the required site properly. *Obturator* is the inner part which allows the easy insertion of the proctoscope.

Positions for Proctoscopy

- Left lateral position (common).
- Right lateral.
- Lithotomy.
- Knee-elbow position.

Technique of Proctoscopy

After doing digital examination, proctoscope with the obturator is introduced inside, through the anal canal in the direction towards the umbilicus. The obturator is removed. Proctoscope is withdrawn and during the course of withdrawal, any pathology has to be looked for.

Acute anal fissure is contraindication for proctoscopy.

SIGMOIDOSCOPY

> ***Annual sigmoidoscopy for all, after their fortieth birthday: something to look forward to.***
> **— Henry George Miller,** 1968



Fig. 25.5: Rigid sigmoidoscope with inflation balloon and biopsy forceps.

- It is used to visualize rectum and sigmoid colon, take biopsies from suspected lesions and do therapeutic procedures (polypectomy, control of bleeding, etc).
- There are *two* types:
  1. ***Rigid***—25 cm long, with illumination.
  2. ***Flexible***— 60 cm long.
- In lateral position as in P/R examination or proctoscopy, sigmoidoscope with obturator is passed into the rectum and obturator is removed. Rectosigmoid is inflated with air and scope is negotiated into the sigmoid through *Alpha* (α) *manoeuvre*. Looked for any disease, biopsies are taken and also any required procedure is done.

Precaution: Care should be taken in acutely inflamed sigmoid colon, because chance of perforation is high.

COLONOSCOPY

- It is 160 cm long, flexible.
- Technique is same as sigmoidoscopy, but is passed up to the caecum.

Technique

It is often done under GA using propofol or with laryngeal mask airway (LMA). It can be also done under high sedation. But patient finds difficult to tolerate pain and distension. Passage by *elongation; looping with a maneuver; dither-torquing* (clockwise–anticlockwise rotations) methods are used. Difficulty is encountered while passing through sigmoid colon, splenic flexure, and hepatic flexures. Continuous air inflation is important. It is better to visualize the lumen and then pass the colonoscope. Often it can also be negotiated into the terminal ileum. Changing position, abdominal pressure is required for better negotiation of the colonoscope. Technique differs in patients after hemicolectomy or through colostomy.

Indication

- Bleeding per rectum, resistant anaemia.
- To take biopsies from different parts of the bowel.
- To identify synchronous growths, ulcerative colitis.
- To remove polyps.
- When barium enema shows irregularity.
- For therapy—colonoscopic polypectomy, dilatation of stricture colon, fulgaration.

Contraindication

Acute ulcerative colitis.

Advantage

It helps to visualise full length of the colon. GA is not used, except in children.

Disadvantage

Takes a long time and requires expertise to do the same.

Hazards

- Perforation of bowel, splenic flexure is the commonest site.
- Trauma to anorectum.
- Sepsis.
- Haemorrhage.
- Problems of incomplete therapeutic procedures.

CARCINOMA RECTUM

> ***Bubo is an apostem breeding within the anus in the rectum with great hardness but little aching. This I say, before it ulcerates, is nothing else than a hidden cancer…. Out of bubo (cancer) goes hard excretions and sometime they may not pass, because of the constriction caused by the bubo, and they are retained firmly within the rectum…. I never saw nor heard of any man that was cured…but I have known many that died of the foresaid sickness.***
>
> **—John of Arderne,** 1414

- It is common in females.
- Usually originates from a pre-existing adenoma or papilloma (tubular polyp).
- In 3% of cases, it occurs in multiple sites (synchronous).

Aetiology

- Red meat and saturated fatty acids increase the risk.
- High fibre diet reduces the risk.
- Alcohol and smoking increases the risk.
- FAP and adenomas are more prone to carcinomas.
- Villous adenoma has 40% chance of turning malignancy, size more than 2 cm is at high risk.
- Ulcerative colitis; Crohn's disease; HNPCC carries higher incidence of carcinoma of rectum.
- Family history of rectal cancer – any first degree relative of a person with rectal cancer will show two times increased risk of carcinoma rectum.
- Risk of developing other cancers like of endometrium (40%); stomach (20%); biliary tree (20%); ovary (10%) in the same patient also increases.
- *'Adenoma – carcinoma sequence'* like in carcinoma of colon is known common method of occurrence.



Fig. 25.6: Polyps of colon. It is important premalignant condition for colorectal cancers.

Never insult the vagina by examining the rectum first—An old axiom



Fig. 25.7: Large rectal polyp which has come out of the anal canal. It is potentially malignant.



Fig. 25.8: Pathological specimens of anal canal, rectum and sigmoid colon after abdomino perineal resection for low rectal carcinoma and midrectal carcinoma.

Gross: It can be—

- *Ulcerative.*
- *Papilliferous.*
- *Infiltrative.*
- *Annular*: It is common in recto-sigmoid junction.
- *Diffuse type:* Often observed in patients with ulcerative colitis which carries poor prognosis.

Histologically: It is *adenocarcinoma* which may be—

- *Well differentiated – 10%*
- *Moderately differentiated – 65%*
- *Undifferentiated – 25%*

Spread

- *Local spread*: Initially, it spreads, locally circumferentially (takes 12-18 months to complete the circumference of the bowel). Later spreads out to the muscular coat and peri-rectal tissue. Then to prostate, bladder, seminal vesicles in males, and uterus and vagina in females. Posteriorly into the sacrum and sacral plexus, laterally into the ureters.
- *Lymphatic spread:* Above the peritoneal reflection, spread occurs upwards along the colonic lymph nodes. In mid-rectum, into the para rectal and mid-rectal lymph nodes. Downward spread is rare, occurs when growth is close to the anal canal, into the inguinal lymph nodes. Obturator nodes may be involved in 8% of lower rectal growths.
- *Venous spread* occurs to the *liver 35%, lungs 20%, adrenals 10%* and other areas.
- *Perineural spread* carries poor prognosis.

Haggitt's Invasion of Malignant Polyp (Similar to Carcinoma Colon)

In pedunculated polyp

Level 0 – non invasive carcinoma over the summit
Level 1 – invasion to head of pedunculated polyp
Level 2 – invasion to neck of the pedunculated polyp
Level 3 – invasion to stalk of the pedunculated polyp
Level 4 – invasion to base of pedunculated polyp
In sessile polyp – all lesions are level 4

DUKE'S STAGING OF CARCINOMA RECTUM

A. Confined to bowel wall, mucosa and submucosa
B. Extends across the bowel wall to the muscularis propria with no lymph nodes involved
C. Lymph nodes are involved

MODIFIED DUKE'S STAGING

A. Growth limited to rectal wall (15%)
B. Growth extending in to extra rectal tissues but no lymph node spread (35%)
B1: Invading muscularis mucosa
B2: Invading in to or through the serosa
C. Lymph node secondaries (50%)
D. Distant spread to liver, lungs, bone, brain

Colloid carcinoma of the rectum

It is 12% common. Common in young people

Types

- Primary and secondary
- *Secondary* colloid carcinoma is common type and is due to mucoid degeneration of adenocarcinoma itself.

Primary is mucus within the cell with displaced nucleus *(signet ring)*

Primary type has got poorer prognosis compared to secondary

TNM Staging of Rectal Cancers

Tx - Primary not assessed.
T_0 – No primary tumour.
Tis – Carcinoma *in situ*.
T_1 - Invasion to submucosa.
T_2 – Invasion to muscularis propria.
T_3 – Invasion of subserosa or non-peritonealized perirectal tissues.
T_4 – Involvement of visceral peritoneum, other organs or structures.
N_0 – No nodal spread.
N_1 – 1-3 nodal spread.
N_2 – 4 or more nodal spread.
M_0 – No distant spread.
M_1 - Distant spread present.

Clinical Features

- Bleeding per rectum/anum (may mimic haemorrhoids)—earliest symptom.
- *Spurious diarrhoea*: It occurs in *early morning* due to overnight mucus accumulation in the rectum causing urgency for defecation, but results in spurious diarrhoea with incomplete evacuation.
- *Tenesmus*: It is painful incomplete defecation with bleeding.
- *Bloody slime*: Mucus with blood in stool.
- Sense of incomplete evacuation, constipation.
- Presenting as piles due to proximal venous congestion by tumour or as fistula in perianal region (which itself is tumour extension into the anal canal).
- Anaemia, malnutrition, loss of appetite and weight.
- Altered bowel habits.
- Urinary symptoms are due to infiltration of bladder or prostate.
- Back pain, due to invasion of sacral plexus.
- Ascites, liver secondaries, urinary symptoms.

90% of rectal growths can be felt by per–rectal examination.

Investigations

- Proctoscopy.
- Sigmoidoscopy.
- Biopsy using *Yeoman's* forceps.
- Barium enema in case of FAP and synchronous growths.
- Colonoscopy is ideal to rule out presence of any synchronous growths proximally (5%) or polyps.
- U/S abdomen—to look for secondaries in liver, ascites.



Fig. 25.9: Air contrast CT of colon and rectum showing significant narrowing in recto-sigmoid junction.



Fig. 25.10: CT picture of carcinoma rectum. CT is useful in evaluating the extent, nodal status and operability.



Fig. 25.11: CT scan showing carcinoma of rectum

Diseases of the soul are more dangerous than those of the body.

- CT scan to see operability, local extension, size, nodal status, ureteral involvement, presence of perforation or fistula. CT is very useful to assess *nodal status*. Local extension is better assessed by TRUS. Any mesorectal node detected in CT is considered as malignant spread. Liver secondaries are well identified in CT. Ureteral involvement in CT scan signifies requirement of stenting prior to surgery. Chest CT is essential to look for secondaries.
- *Endorectal ultrasonography*—very useful to assess the local extent of the tumour. *Transrectal ultrasound (TRUS)*/endorectal ultrasound gives more accurate picture of primary tumour, layers, perirectal tissues and nodes. TRUS is superior in T staging of rectal cancers. Its accuracy is 95% compared to MRI (85%); and CT (75%). Endorectal US based T staging and N staging used now depends on layers involved and presence of nodes. TRUS detects nodes more or equal to 5 mm size.
- *Endorectal coil MRI (ec MRI)* is very useful as it gives larger field of view compared to TRUS; extent, adjacent organ spread are better assessed by MRI. Recurrent tumour is better assessed by MRI.



Figs 25.12A and B: MRI showing carcinoma of rectum and adjacent structures. MRI is good method to evaluate the spread and staging.

- *Fluorine – 18 fluorodeoxyflucose PET scan* is useful to detect recurrent local tumours; metastatic disease; to detect pathologic response in preoperative chemo-radiation. PET is not accurate for nodal spread.
- Blood tests like haematocrit; CEA; blood urea and serum creatinine; serum electrolytes and proteins for management purpose.

Differential Diagnosis

- Inflammatory stricture
- Amoebic granuloma
- Tuberculosis
- Carcinoid
- Solitary ulcer syndrome

Treatment

- Surgery is the main method of treatment. Preoperative chemoradiotherapy is often used if growth is invading into adjacent tissues (T4). Adjuvant chemotherapy and radiotherapy is a must.
- *Abdomino perineal resection (APR)* is the gold standard. But if tumour is well differentiated and if there is adequate margin above the anal canal, a sphincter saving *anterior resection (AR)* can be done. *Low anterior resection (LAR)* is possible if EEA stapler is used for anastomosis. But anterior resection should not be done by compromising the adequacy of tumour clearance. Tumour clearance is still the priority in rectal cancer as it decides the eventual outcome.
- *Total mesorectal excision (TME) should be the goal* in all procedures as mesorectum contains nodes and lymphatics, clearance of which gives better result.
  - It is a *sharp dissection* (not blunt) in avascular areolar plane between fascia of rectum which encroach the mesorectum and parietal pelvic wall fascia.
  - Mesorectum should not be breached.
  - Absolute haemostasis, *preservation of autonomic nerves* and dissection under vision are the essential principles.
  - Both layers of membranous anterior Denonvillier's facia should be dissected off the prostate and seminal vesicles in male to have proper clearance.
  - In TME for middle and lower rectum, entire mesorectum should be removed.
  - For upper rectal tumors, TME is done 5-6 cm below the lower margin of the tumour.
  - TME improves the quality of life in relation to *impotence, retrograde ejaculation and urinary incontinence*. These complications are around 50% or more in APR whereas in TME it is less than 20%.
- Recommended *distal rectal margin clearance is 5 cm*, however 2 cm distal margin is an *acceptable* clearance.
- *Circumferential resected margin - CRM* (radial margin) is more important than proximal and distal margin. A 5 cm clearance of mesorectum from the primary tumour is essential as tumour implants can occur only for up to 4 cm from primary tumour margin.
- *Principles to be followed*—Adequate lymphatic and vascular clearance; en bloc resection of primary tumour; no / less touch technique; avoiding spillage; adequate radical surgery.
- *Ultra low anterior resection or intersphincteric* resection can be considered in low rectal tumours.
- After resection (on table*) irrigation of rectal bed* with cetrimide or hypertonic solution like distilled water is often practiced as they are tumoricidal.

- Selection of the procedure AR or APR is decided by proper staging using TRUS and MRI.
- Neoadjuvant chemotherapy or neo-adjuvant chemoradiotherapy is often used in T3 lesions which also may avoid APR; and AR may be sufficient.
- Local wide excision approaches are often used when tumour is < 4 cm; < 40% circumference involved; T1 N0/T2 N0 tumour— *transanal approach* is used in small tumours that is 3-5 cm above the dentate line but within 10 cm from the anal verge; *transcoccygeal Kraske's approach* for posterior wall rectal tumours (dangerous posterior faecal fistula can occur); *transanal endoscopic microsurgery* (Buess) using operating microscope and videoscope can also be done.
- In females, partial vaginectomy with or without hysterectomy and bilateral oophorectomy may be needed in T4 lesions to achieve surgical resection. Removal of uterus and ovaries prevents patient from developing possible associated cancers of these organs. Carcinoma rectum also spreads to ovaries commonly which can be prevented by oophorectomy.
- Often resection of liver secondaries can be undertaken in selected patients when one lobe is involved or solitary secondaries are present.
- *Laparoscopic APR/AR* is becoming popular. Dissection will be more meticulous.

Features are –

- Less blood loss, less postoperative pain.
- Early bowel function.
- Clearance is same as open method in relation to primary tumour and nodes.
- Short hospital stay, mortality and morbidity are similar to open method.
- Port site recurrence chances are 0.5 – 2%. (Earlier it was higher; now it has reduced due to proper technique, careful handling of the specimen, specimen isolation prior to extraction, trocar site irrigation with cytotoxic agents and povidone iodine).

- For carcinoma rectum presenting with obstruction, an initial proximal colostomy is done. Neoadjuvant chemoradiation is given. Patient is reassessed for operability. Then APR is done with permanent colostomy.
- Incidence *of local recurrent rectal cancer* is 30%.
  - 80% of local recurrence occurs within 2 years of surgery.
  - Common site of recurrence is in the pelvic wall. It also can occur at distal anastomotic margin.
  - Intractable pelvic pain, urinary symptoms, sepsis, bleeding, perineal sinus, swelling and induration, bowel disturbances are the features.
  - It is evaluated by CEA, biopsy, CT abdomen, MRI of pelvis and PET scan.
  - It is often difficult to manage.
  - Incidence of recurrence will come down to 5% in proper TME.
  - Palliative chemoradiation, end colostomy, ureteral stenting are the palliation. RT controls pain and bleeding.
  - Extensive radical surgery like removal of tumour with pelvic structures can be undertaken with diversions but with a high mortality rate and failure rate.
- Proper preoperative bowel preparation is a must in all rectal cancers which reduces the postoperative problems like sepsis, leak and increases the early chance of recovery.
  - Bowel preparation by polyethylene glycol; electrolytes *orally*; bowel wash *per anally*; bowel antiseptics like neomycin 1 gram tid previous day/erythromycin 1 g tid/metronidazole tid *orally*.
  - Systemic antibiotics like cefazolin, metronidazole, gentamycin.
  - Prophylactic heparin or low molecular weight heparin.
  - Foley's catheterisation and nasogastric tube should be passed.
  - Preoperative adequate hydration using IV fluids.
  - Blood grouping and cross matching and required bottles of blood should be reserved if needed to transfuse during the procedure.

1. ***Abdomino-Perineal Resection*** (AP–resection) where in sigmoid, descending colon and upper rectum is mobilised per abdominally. Anal canal with perianal and perirectal tissues are dissected per anally. Retained colon is brought out as *end colostomy* in *left iliac fossa*.

APR—Types

- *Miles*—Abdomen first, perineum later
- *Gabriel*—Perineum first, abdomen later
- *Lioyd—Davis*—Synchronised (together), (Combined)

- APR is done through lower midline incision in lithotomy position. Left-sided colon and entire rectum is mobilised from above. Rectum is mobilised posteriorly in avascular plane in front of nerve plane (hypogastric nerve) between mesorectum and sacrum. Inferior mesenteric artery is ligated high proximal (as lymphovascular ligation) at its origin or just beyond its first branch. Colon is transected and proximal cut

'Knowledge' is proud that she knows so much, 'wisdom' is humble that she knows no more.

end is fashioned for end colostomy in *left iliac fossa*. Through perineum, a purse string suture is placed around anal margin. Circumferential incision is placed around the anus. Dissection is deepened using scissor and cautery into the perineal body, coccyx, ischial tuberosity, ischiorectal fossa. First posterior and lateral dissections are undertaken until it reaches above. Lastly anterior dissection is done to reach above and specimen is removed through perineal wound. Perineal wound is closed in layers often with a drain. Abdomen drain is placed. Colostomy is created by suturing skin to mucosa using silk.



Fig. 25.13: Laparoscopic view of mobilised rectum in APR.



Figs 25.14A and B: Colostomy done in left iliac fossa after APR. Colostomy care is important.

- *Complications of APR* are –
  - Bleeding.
  - Infection of perineal wound.
  - Complications of colostomy like prolapse, stenosis, and infection.
  - Injury to urinary system, ureter, impotence, urinary incontinence.
  - Operative mortality is less than 2%.

APR is the treatment of choice when mesorectum is involved or when it is poorly differentiated tumour or when nodes are involved. It gives adequate clearance.

2. ***Anterior Resection*** (Abdominal radical restorative operation) is done in growths located in the mid and upper part of the rectum, which is well-differentiated, small sized and with a clear adequate length for anastomosis after resection.

Criteria for anterior resection- (Low anterior resection) (LAR)

- Upper and middle third rectal growth
- Above peritoneal reflection
- Well-differentiated tumour
- < 4 cm size tumour
- In females, growth 7 cm above the anal verge
- T1 N0/T2 N0 tumour
- Tumour without lymphatic or venous spread

Advantages:

- Avoids permanent colostomy.
- Sphincter is retained.
- Patient's acceptance.

It is done through laparotomy. Recto-sigmoid region is resected with the tumour with adequate clearance and *colo-anal anastomosis is d*one either by hand suturing or by staplers.



Fig. 25.15: Anterior resection for carcinoma upper rectum using stapler device.

Disadvantages:
- Uncertainity of clearance which is very important in cancer surgeries and so chances of **local recurrence** is high.
- Anastomotic leak, infection; stenosis.

3. ***Hartmann's operation*** is an excellent palliative procedure -done in elderly people who are not fit for major surgery like AP resection and also in locally advanced tumours. Here rectal growth is resected and upper end of the rectum is closed completely. Proximal colon is brought out as *end colostomy*.
4. ***Pelvic evisceration (Brunschwig's operation):*** It is removal of rectum with the tumour, all the lymph nodes, urinary bladder, fat, fascia, uterus, vagina, with colostomy and urinary diversion. It is neither favourable nor popular.


A
Growth
Carcinoma rectum (lower)
After A-P resection
B
Carcinoma upper rectum-anterior resection
C
Resected
Advanced carcinoma rectum-Hartmann's resection

Fig. 25.16: Surgeries for Ca rectum (A) AP resection, (B) Anterior resection, (C) Hartmann's resection.

5. ***Palliative colostomy*** is done in advanced unresectable growth which presents with intestinal obstruction.
6. ***Radiotherapy*** is beneficial in carcinoma rectum showing increased survival rate. It is useful when growth is below the level of peritoneal reflection.

Radiotherapy in carcinoma rectum

- Only rectal adenocarcinoma in GIT responds well for RT
- Preoperative RT can be given to down stage the tumour so as to make it amenable for APR or make it for anterior resection
- Postoperative RT is commonly used
- In small well-differentiated growths intracavitary curative RT can be tried with proper follow-up
- Palliative RT
- IORT (Intraoperative RT) is used in pelvic wall disease. It can cause peripheral neuropathy and ureteral stenosis
- As a component of chemoradiation
- Short course 25 Gy in 5 fractions in 5 days
- Long course 5040 Gy in 28 fractions in 6 weeks
- RT sterilises field; causes down staging of tumour; preserves sphincter

7. ***Chemotherapy*** has been tried using endoxan, 5 FU, semustine also with leucoverin (Folinic acid) or Levamisole.
   - Capecitabine, oxaliplatin are newer drugs used (refer chapter large intestine for detail). Indications are positive nodes; T2 stage; blood spread; for chemoradiation; recurrent tumour; advanced/metastatic disease.
   - Biologic agents.
     - Bevacizumab VEGF receptor antagonist.
     - Cetuximab EGFR antagonist.
8. Electrocoagulation and decoring of the tumour, as a palliative procedure.
9. Laser photocoagulation.

Chemoradiation in Carcinoma Rectum

- It is very useful adjuvant therapy.
- To prevent recurrence after anterior resection
- Neoadjuvant (preoperative) chemoradiation can be used in tumour like T3 to downstage the disease and make it possible for AR
- Postoperative chemoradiation.
- Palliative chemoradiation in locally advanced disease or metastatic disease also.
- Recurrent local carcinoma of rectum.
- In carcinoma of rectum presenting with obstruction, chemoradiation is given after loop colostomy.

Prognosis in carcinoma rectum

5 year survival is	*Prognostic factors are*	*Follow-up*
• Stage I 90%	• Size of the tumour	• Regular colonoscopy
• Stage II 75%	• Differentiation	• CEA assessment
• Stage III 40%	• Mesorectal involvement	• PET scan
• Stage IV 5%	• Stage of the disease	• CT/MRI
	• Nodal status, perineural spread	• Colostomy care in APR
	• Distant spread	
	• Circumferential resected margin	
	• Adjuvant therapy used	

The palce to improve this world is first in one's own heart, head and hands.

SOLITARY ULCER SYNDROME

- It is mainly thickening and disorganisation of muscularis mucosa with superficial ulceration.
- It is usually 4-12 cm from the anal verge in the anterior wall of the rectum. But often can occur in sigmoid colon.
- In 30% cases, there are multiple ulcers.
- Often there will be inflammation and induration of the area without an ulcer.
- Condition is commonly associated with rectal prolapse.
- ***Differential diagnosis*** are carcinoma, tuberculosis, ulcerative colitis.
- ***Investigations*** are colonoscopy and biopsy.
- ***Treatment:***
  - High fibre diet.
  - Treatment for rectal prolapse.
  - Avoid surgical excision in solitary ulcer syndrome as much as possible.

RECTAL PROLAPSE

- It is circumferential descent of bowel through the anal canal.
- It is commonly seen in infants, children and elderly individual.
- It is common in females (6 : 1).

Aetiology

- Decreased sacral curvature and decreased anal canal tone are the probable causes in infants.
- Diarrhoea, cough, malnutrition are the additional factors in children.
- It may be due to reduced ischiorectal fossa fat, neurological causes, fibrocystic disease of pancreas or poorly developed pelvis.
- In adults, it is common in females, common in multipara—repeated birth injuries to perineum results in damage to the perineal nerve supply.



Fig. 25.17: Partial rectal prolapse is less than 3.75 cm and only mucosal.

- It is due to weakening of supporting tissue and levator ani muscle, atony of the sphincter, increased intra-abdominal pressure due to any cause like chronic cough, stricture urethra.

Types

Partial Prolapse

Here only mucosa and submucosa of the rectum descends, not more than 3.75 cm. There is no descent of the muscular layer. It is the *commonest type of rectal prolapse.*

Clinical Features

- History of mass per anum, which can be observed when child is allowed to strain in squatting position.
- It is *pink in colour and circumferential.*



Figs 25.18A to C: Complete rectal prolapse. It is more than 3.75 cm and mucosa with muscular layer.



Fig. 25.19: Rectal prolapse.

- It differs from *piles* (differential diagnosis), the piles are not circumferential and *are plum or blue coloured (not pink).*

Treatment for partial prolapse:

1. The nutrition of the child is improved and digital repositioning is tried.
2. Submucosal injections of 10 ml of 5% phenol in almond oil or ethanolamine oleate is given into the apex of the prolapse under. G/A so as to create an aseptic inflammation leading to tethering of mucosa to the underlying muscular coat. Injection can also be given at the base or both at the apex and base.
   – Alternatively 30 ml of tetracycline or oxytetracycline or hypertonic saline injection can also be used. Initial injection is supported by *Thiersch wiring* using (temporary) chromic catgut until adhesion occurs between the mucosa and muscular layer (in 3 weeks).
   – In adults, injection therapy is tried for partial prolapse, results are not as good as in children.
3. Thiersch wiring alone is tried with good success rate in children.
4. *Goodsall's operation* is excision of the prolapsed mucosa at its base, usually in three positions.



Fig. 25.20: Goodsall's ligature for partial prolapse. Prolapsed mucosa is ligated at different positions using nonabsorbable suture material often with double needled. Usually it is done for one side in three portions.

Complete Prolapse

- Also called as *procidentia,* is *less common than partial prolapse.*
- It is common in females (6 : 1 :: female : male).
- It is due to weakened levator ani and supporting pelvic tissues.



Fig. 25.21: Complete rectal prolapse.



Figs 25.22A and B: Complete rectal prolapse. It should be confirmed by observing the patient during straining in squatting position.

He who is angry is seldom at ease.

- The descent is always more than 3.75 cm, contains all layers of the rectum (i.e. including muscular layer). Often descends down up to 10-15 cm.
- It is often associated with the uterine descent *(uterine prolapse*).
- It is also thought to be as an intussusception of the rectum.
- Once complete prolapse is more than 5 cm, anteriorly it drags peritoneum as pouch which often contains small intestine. On digital pushing it reduces with gurgling.
- Patulous anal sphincter is typical with mucus discharge and faecal incontinence.

Aetiological factors

- Weak anus, external sphincter and pelvic muscle
- Lax, mobile rectum
- Obliterated ano-rectal angle
- Abnormally mobile rectum with descent

Clinical Features

- Complete descent of the rectum which is red in colour and often painful, as mass per anum.
- Faecal incontinence is very common. It is due to disruption of the anal sphincter and prolapsed rectal mucosal discharge.
- Pain per anum.
- Bleeding can occur because of the congestion.
- Sepsis, discharge, fever, anaemia are other features.
- P/R examination shows lax sphincter. Anteriorly, peritoneal sac comes down as a pouch which may contain small bowel.

Differential Diagnosis

Rectosigmoid intussusception, third degree piles, large rectal polyp.

Investigations

- Defecography reveals increased mobility of the rectum from sacral fixation point with redundant mesorectum and funnel formation. It is fluoroscopic and spot filming in lateral projection after instilling radio-opaque material into the rectum done in sitting posture over a radiolucent commode.
  - Cinedefecography, triple contrast cinedefecography, dynamic MRI defecography, colpocystodefecography are helpful to delineate complex pelvic floor problems.
  - *Defecography abnormalities* – megarectum, incontinence, nonrelaxing puborectalis, abnormal perineal descent (2.5 cm), mucosal prolapse, solitary ulcer rectocoele, enterocele.
  - *Preprolapse* [in defecography]: Rectum is funnel shaped, lack of fixation to sacrum, excessive rectosigmoid mobility, ring pocket formation, intussusception.
  - *Rectal prolapse* [in defecography]**:** Redundant sigmoid colon, wide deep pouch of Douglas

Defecographic grading of rectal prolapse

N – Normal rectal fixation and sphincter relaxation and rectal emptying.
1 – Nonrelaxed puborectalis.
2 – Mild intussusception.
3 – Moderate intussusception.
4 – Severe intussusception.
5 – Prolapse.
R – Rectocele.

- Sigmoidoscopy.
- Anal manometry.
- Pudendal nerve latency study.

Treatment for Complete Prolapse

*Aim of treatment***:**

- To *control* the prolapse; to *restore* continence; to *prevent* constipation.
- *In young males, abdominal repair should be avoided as it injures pelvic nerves leading to sexual impotency*. So perineal approach is better.
- Rectopexy is fixing the rectum to sacrum by sutures or mesh after complete mobilisation of the rectum. Laparoscopic rectopexy using polypropylene mesh and sutures gives good result and has become very popular.
- *Delorome's operation* is better option in young individual with complete prolapse.
- In elderly perineal proctectomy with anterior and posterior reefing of the sphincter muscle is accepted method now. It is similar to Altemeier technique (It is perineal rectosigmoidectomy). Here entire prolapsed rectum and redundant sigmoid is resected through perineum prior to reefing of the sphincter.
- Anal encircling surgeries using synthetic wires/mesh/suture materials are limited to extremely ill patients and elderly who will not withstand perineal proctectomy.
- *Choice of procedure* depends on age, sex, operative risk, pelvic floor defect, degree of incontinence, history of constipation.

Surgeries are:

- *Delorme's operation* is done in young males with complete prolapse, wherein mucosa of the prolapsed rectum is excised and muscular layer is plicated with vicryl and mucosa is sutured to the anal margin through perineal approach.

- Laparoscopic rectopexy is very good approach to fix the rectum to sacrum. Adequate mobilisation of the rectum is an essential step prior to fixing.
- Strengthening of puborectalis and external anal sphincter through perineum—*Post anal repair*.
- *Thiersch operation* done in elderly is simple, effective, avoids major surgery, can be done under L/A wherein thin steel wire or monofilament non-absorbable (No : 1 or No : 2) suture material is circumferentially placed deep to the anal skin to prevent descent of rectum.
- *Wells's operation*—Through abdominal approach, rectum is mobilised from the sacral curve. Polyvinyl alcohol sponge or mesh is wrapped around the rectum partially and fixed into the sacrum which in turn creates extensive fibrosis and prevents prolapse.
- Through perabdominal approach, after rectal mobilisation, rectosigmoid junction is hitched up to the sacrum below the sacral promontory using a *teflon sling—Ripstein operation*.
- *Lahaut's operation* is mobilisation of the recto-sigmoid and extraperitonealisation through the rectus sheath.
- Rectosigmoidectomy—only done in severe cases. It has got high recurrence rate (*Altmeir's*).
- Encircling gracilis muscle around anal opening.

Procedures for repair of rectal prolapse

Perineal operations	*Abdominal operations: Open/laparoscopic*
• Mucosal sleeve resection (Delorme) • Perineal rectosigmoidectomy (Altemeier) • Anal encircling (Theirsch)	• Suture rectopexy • Prosthetic or mesh rectopexy – Anterior/posterior • Resection rectopexy • Anterior resection • Lahaut's operation

Complications of Surgery

- Injury to hypogastric nerve causing impotence.
- Bladder dysfunction.
- Bleeding from sacral venous plexus.
- Injury to rectum and colon causing faceal fistula.
- Constipation after rectopexy is a known complication.
- Recurrence of prolapse.
- Improper correction of continence occurs in 50% cases.
- Infection – proctitis/pelvic abscess, etc.

ANORECTAL MALFORMATIONS (ARM)

- It is due to imperfect fusion of the post-allantoic gut with the proctodaeum.
- Incidence is one in 4500 new borns.



Figs 25.23A and B: Ano-rectal malformation with fistula in (A) Females and (B) Males.

Clinical Features

- New born presents with inability to pass meconium, abdominal distension, features of intestinal obstruction, improper anal dimple, sometimes with complaints of passing meconium per urethra.
- It can be associated with—cardiac anomaly, tracheo-oesophageal fistula, renal anomalies, spinal anomalies. VATER/VACTERL anomaly.

Wingspread classification of anorectal malformations
('Wingspread'—name of the place where the conference was held)

Low	*Intermediate*	*High*
It is below the level of pelvic floor, (Puborectalis). Easy to diagnose and treat with good outcome. It may be— — Covered anus — Anovestibular fistula — Anal stenosis — Anal membrane.	It occurs at the level of puborectalis, with or without fistula	It can be with or without a fistula into the bladder urethra, uterus, vagina It may be— — Anorectal agenesis — Rectal atresia — Cloaca (only in females, with confluence of rectum, vagina, bladder and urogenital sinus)

Patience is the companion of the wisdom.

- Most common ARM in boys is *rectobulbar fistula* with fistula beginning distal to puborectalis from distal rectum to bulbar urethra.
- Most common ARM in females is *rectovestibular fistula*.



Fig. 25.24: Anal stenosis.



Fig. 25.25: Anorectal malformation Cloaca type.

Investigations

1. *Wangenstein's invertogram:* Usually done 6-12 hours after birth, so as to allow air to reach the rectal pouch. A metal coin (marker) is strapped at the presumed site of anus and X-ray is taken. Length between the rectal pouch and anal dimple marker is more than 2.5 cm in high anal fistula.
   a. In *low fistula*, rectal pouch is distal to the *Stephen's line (Pubococcygeal line).*
   b. In *intermediate*, pouch is at the level of ischial spine (*Kelly's point*).
   c. In *high fistula*, rectal pouch is proximal to the Stephen's line.
2. *Murugassu's technique:* Through visible anal dimple, meconium is aspirated by passing a needle into the rectal pouch in sitting propped up position. Watersoluble iodine dye is injected. Lateral X-ray is taken to study the level through Stephen line and Kelly's point.



Fig. 25.26: Stephen's line.

3. U/S abdomen.
4. Evaluation of cardiac function is also important.
5. MRI spine.

Treatment

1. In ***low fistula***, single stage reconstruction is done under G/A with very good results.
   i. Anoplasty.
   ii. Anovestibuloplasty.
   iii. Anal dilatation.
   iv. Incision of anal membrane.
2. In ***high fistula***, initial colostomy is done. Later definitive procedure, i.e. *Pull through operation* through puborectalis and anastomosis of rectal pouch to create the anal canal is done. Closure of colostomy is done later.
   – *Posterior sagittal anorectoplasty* is commonly done procedure.
   – *Note:* Level of rectal pouch and normal/abnormal sacrum are the deciding factors for good results.

Complications

- Infection
- Faecal fistula
- Stenosis
- Colitis
- Malnutrition
- Faecal incontinence

PILONIDAL SINUS (Jeep bottom; Driver's bottom)

Pilus—hair; Nidus—nest

- It is of infective origin and occurs in sacral region between the buttocks, umbilicus, axilla.
- It is common in hair dressers (seen in interdigital clefts), jeep drivers.
- It is common in 20-30 years of age. It is common in males and mostly affects hairy men.



Fig. 25.27: Site and types of pilonidal sinus.



Fig. 25.28: Typical site of pilonidal sinus in the sacral region. Note the primary and secondary sinuses.



Fig. 25.29: Recurrent pilonidal sinus. 25-40% of pilonidal sinuses can recur.

Commonest site: Interbuttock sacral region.

Pathology



Fig. 25.30: Specimen of typical excised pilonidal sinus. Note the tuft of hair.

Hair penetrates the skin
↓
Dermatitis
↓
Infection
↓
Pustule formation
↓
Sinus formation
↓
Hair gets sucked into the sinus by negative pressure in the area
↓
Further irritation and granulation tissue formation
↓
Pus forms
↓
Multiple discharging sinus

Primary sinus occurs in the midline.

Secondary sinus occurs laterally (paramedian).

Remember about pilonidal sinus

- Congenital theory is no longer considered; it is an acquired entity
- Hair follicles have never been demonstrated in the wall of the sinus (only hairs have found)
- Number, sharpness, nature, shape of hairs; depth and narrowness of the natal cleft; friction movements; nature of the skin, moisture and sweating are the factors predisposing pilonidal sinus
- Hair need not be local, tract always traverses cephalad
- Male preponderance – 74%, Male sex hormone effect, hairy body, more sweat and maceration
- Occurs in young – 20-29 year, who are having active pilosebaceous glands

We make a living by what we get; we make a life by what we give.

- Dark haired – Stiff hairs, rare in Negroes
- Obese and overweight– deep natal cleft
- Prolonged sitting
- Many procedures for treatment are available with each one having their own advantages and disadvantages



Fig. 25.31: Pilonidal sinus – primary and secondary sinuses are clearly seen.

Clinical Features

- *Discharge*—either sero sanguinous or purulent.
- *Pain*—throbbing and persistent type.
- *A tender swelling* seen just above the coccyx in the midline (*primary sinus*); and on either sides of the midline (*secondary sinus*).
- Tuft of hairs may be seen in the opening of the sinus.
- Presentation may be *as an acute* exacerbation (abscess), or as a *chronic one.*
- It causes recurrent infection, abscess formation which bursts open forming recurrent sinus with pain, discharge and discomfort.

Complications

- Chronic pilonidal sinus can cause occasionally sacral osteomyelitis, necrotising fasciitis and rarely meningitis.
- It is not a life threatening condition but often it can be a morbid disease because of high recurrence rate.

Treatment

In acute phase initially—

Drainage of the abscess and antibiotics; later definitive treatment is undertaken

Definitive treatment -



Figs 25.32A and B: Pilonidal sinus – operative jack knife position.

- In prone position (*jack knife* position, i.e. prone with buttocks elevated) excision and primary closure is done under general anaesthesia or local anaesthesia. All sinus tracks, unhealthy granulation tissues with hairs are removed completely. Methylene blue is injected to demonstrate the multiple tracks properly.
- Excision and skin grafting – has got high recurrence rate.
- Excision with Z plasty – good result.
- Excision with multiple Z plasty.
- Karydakis excision through a semilateral incision and lateralised suturing of the wound away from the midline gives good result.
- Excision with closure using Limberg (Rhomboid) buttock flap (single or double rhomboid flaps) – good result.
- V-Y gluteal advancement flap.
- *Bascom technique* of excision through lateral approach is a good method. Through small lateral incision or multiple small lateral incisions 2-4 mm sized sinus is approached and pus is drained; hairs are removed with only minimal excision of sinus done. Cavity walls are not excised. Lateral small wounds are either sutured or left open for spontaneous healing.



Figs 25.33A to G: Rhomboid Limberg flap for pilonidal sinus. It gives good result.



Fig. 25.34: 'Z' plasty is done for pilonidal sinus. It gives good result. Multiple Z plasties are also used.

Non-operative treatment/prevention of recurrence after surgery

- Regular shaving of natal cleft to have meticulous hair control.
- Proper perineal hygiene.
- Only drainage of abscess if occurs and antibiotics.

Causes for high recurrence rate–

- Improper removal
- Overlooking of existing diverticulum
- Entry of new tuft of hairs
- Breakage of scar

Note: Condition has got high recurrence rate (20%)

PILES/HAEMORRHOIDS/FIGS

> ***If bile or phlegm be determined to the veins in the rectum, it heats the blood in the veins: and these veins becoming heated attract blood from the nearest veins, and being gorged the inside of the gut swells outwardly, and the heads of the veins are raised up, and being at the same time bruised by the faeces passing out, and injured by the blood collected in them, they squirt blood, most frequently along with the faeces, but sometimes without faeces.***
>
> **—Hippocrates,** (460-375 BC)

Piles = a ball or mass, Haemorrhoids = blood to ooze, Figs = a fruit (Anjoora).

It is sliding downwards of anal cushions abnormally due to straining or other causes.

Types

Internal—above the dentate line, covered with mucous membrane.

External—below the dentate line, covered with skin.

Interno-external—together occurs.



Fig. 25.35: Anatomical locations of internal and external piles.

Trust your hopes, not your fear.



Fig. 25.36: Parts of piles—plum coloured internal part and black cutaneous external component.

Classification I

Primary haemorrhoids: Located at 3, 7, 11 o'clock positions, related to the branches of the superior haemorrhoidal vessel which divides on the right side into two; left side it continues as one.



Fig. 25.37: Positions of haemorrhoids.

Secondary haemorrhoids: One which occurs between the primary sites.

Classification II

First degree haemorrhoids
Piles within that may bleed but does not come out.
Second degree haemorrhoids
Piles that prolapse during defecation, but returns back spontaneously.
Third degree haemorrhoids
Piles prolapsed during defecation, can be replaced back only by manual help.
Fourth degree haemorrhoids
Piles that are permanently prolapsed.

Piles begin as pedicle and it is located at the origin of the internal pile, i.e. at the level of anorectum.



Fig. 25.38: Degrees of haemorrhoids.



Fig. 25.39A



Fig. 25.39B



Fig. 25.39C



Fig. 25.39D



Fig. 25.39E



Fig. 25.39F

Figs 25.39A to F: Different types of prolapsed piles.



Fig. 25.40: Thrombosed prolapsed pile. Note the colour of the thrombosed pile. It is very painful and tender.

Aetiology

- Hereditary.
- Morphological—weight of the blood column without valves causes high pressure. Veins in the lower rectum are in loose submucosal plane, but the veins above enter the muscular layer, which on contraction increases the venous congestion below (more prevalent in patients with constipation). Superior rectal veins have no valves (as they are tributaries of portal vein) and so more congestion.
- Other causes are straining, diarrhoea, constipation, overpurgation, carcinoma rectum, pregnancy, portal hypertension (rare cause).

An arterial pile is haemangiomatous condition of superior rectal artery entering the pedicle of internal haemorrhoid which will bleed profusely.

Clinical Features

- *Bleeding*—1st symptom—'Splash in the pan'-'bright red and fresh'—occurs during defecation.
- Mass per anum.
- Discharge—a mucoid discharge.
- Pruritus.
- Pain—may be due to prolapse, infection or spasm.
- Anaemia—secondary.
- On inspection, prolapsed piles will be visualized.
- On P/R examination, only thrombosed piles can be felt.
- Through *proctoscopy*, exact position can be made out as a bulge into the proctoscope.



Fig. 25.41: Proctoscopic view of the internal pile.

To different minds, the same world is a hell, and a heaven.



Figs 25.42A to C: Different positions of piles and parts.

- Sigmoidoscopy or colonoscopy or barium enema should be done if there is any suspicion of associated malignancy.

Causes for bleeding per anum

Piles	Carcinoma rectum
Fissure in ano	Carcinoma colon
Polyps	Diverticulitis
Ulcerative colitis	Intussusception
Amoebic colitis	Vascular anomaly of the colorectum
Fistula in ano	Mesenteric ischaemia

Differential Diagnosis

- Carcinoma.
- Rectal prolapse.
- Perianal warts.

Investigations

- Haematocrit.
- Colonoscopy to evaluate proximally for any cause.
- Barium enema X-ray.

Complications

- Profuse haemorrhage which may require blood transfusion.
- Strangulation—piles is being gripped by anal sphincter.
- Thrombosis—piles appear dark purple/black, feels solid and tender.
- Ulceration.
- Gangrene.



Fig. 25.43: Prolapsed, strangulated piles.

- Fibrosis.
- Stenosis.
- Suppuration, leads to perianal or submucosal abscess.
- Pylephlebitis (Portal pyaemia) is rare, but can occur in 3rd degree piles after surgery.

Treatment

1. ***Nonoperative:***
   a. *Sitz bath*—means the patient has to sit in warm water with the anal region dipped in water for 20 minutes, 2-3 times a day. This reduces the oedema, pain and promotes healing.
   b. *Local applications* to reduce pain and oedema can be used.
   c. Antibiotics, laxatives, anti-inflammatory drugs are beneficial.
   d. Fiber diet 35 gram/day, plenty of water.

2. In case of inflamed, permanently prolapsed, oedematous piles, initially, manual stretching of the anal canal sphincter is tried. This prevents congestion of anal cushions and relaxes the anal sphincter, as a result of which the prolapsed piles gets reduced—*Lord's dilatation*. Once oedema subsides, in 1-2 weeks, formal procedure is done.

Complications of anal dilatation (3-4 fingers dilatation)

- Incontinence—rectal—usually temporary
- Infection
- Haemorrhage/haematoma
- Prolapse rectum

3. ***Injection-Sclerosant therapy*:**
   - It is done in 1st degree and early 2nd degree piles (internal) - outpatient procedure.
   - Using proctoscope and Gabriel syringe, 3-5 ml of 5% phenol in almond oil is injected into the submucosal plane just above the anorectal ring to the pedicle. All three piles can be injected separately—3-5 ml to each site in single sitting. Technique can be repeated after 6 weeks. This technique is not done in the presence of sepsis or prolapse.

     Inadvertent deep injection can precipitate pelvic abscess, prostatitis, impotence, rectovaginal fistula.



Fig. 25.44: *Gabriel syringe*–It is used for injection sclerotherapy for internal piles using 5% phenol in almond/olive oil (almond/vegetable oil acts as a vehicle which holds phenol for long period of action). It is a stainless steel syringe with two metallic finger brims near the proximal end. One more metallic finger brim is present on the proximal end of the piston to place thumb while injecting.



Fig. 25.45: Barron's band instrument for 1st and early 2nd degree piles.



Fig. 25.46: Cryosurgery instrument set up for cryohaemorrhoidectomy.



Fig. 25.47: Cryosurgery for piles. Note the probe, grooved proctoscope, freezing the internal pile mass.

4. ***Barron's banding:***
   - It is done for 2nd degree piles. It causes ischaemic necrosis and piles fall off.
   - At one time only two piles can be banded. Repeat banding can be done only after 3 weeks.
   - Band should be placed 2 cm above the dentate line.

Note: Suction banding is also used presently. Suction is used to suck the internal pile into the banding gun.

Complications are – discomfort, pain and bleeding.

5. ***Cryosurgery:*** Using nitrous oxide (–98°) or liquid nitrogen (–196°), extreme cold temperature is used to coagulate and cause necrosis of piles which gets separated and falls off subsequently. It is relatively painless and can be done on OP basis.

We do not see things as they are, we see them as we are.

6. ***Infra-red coagulation:*** Here heat is used to burn the piles so as to allow it to fall off.
7. ***Laser therapy for piles*** - for 3rd degree piles.
8. ***Stapled haemorrhoidopexy (Antonio Longo)*** is circumferential excision of the mucosa and submucosa 4 cm above the dentate line using circular haemorrhoidal stapler passed per anally (MIPH – Minimally Invasive Procedure for Haemorrhoids). *Advantages* are—It is less painful; less blood loss; faster recovery; short hospital stay and equally efficacious. It is done only for prolapsed piles. Improper purse string can cause incomplete doughnut leading to severe haemorrhage.



Figs 25.48A and B: Stapler haemorrhoidopexy. It is minimally invasive procedure for haemorrhoids. It is high mucosal rim excision including vascular pedicles using circular (single use) staplers. It is done for prolapsed piles.

9. ***Open operative methods:***

Indications:
a. 3rd degree piles
b. Failure of nonoperative methods
c. Fibrosed piles

Methods are:

- *Ligation and excision of piles*—commonly done procedures (Milligan—Morgan) (Open method).
  - Under anaesthesia, in lithotomy position, initially the sphincter should be dilated to reduce the postoperative pain. Later skin is held with Allis forceps, internal pile is held with artery forceps. Skin is cut in "V' shaped manner and internal sphincter is separated and pushed up. Pedicle is transfixed with vicryl or catgut and distal part is excised. All the three piles can be dealt in a single sitting.
  - Postoperatively, *sitz bath*, antibiotics, laxatives, analgesics, local applications are given. Often few finger dilatation of the anal canal is required to prevent stenosis.



Fig. 25.49: During haemorrhoidectomy, skin part is held with Allis forceps; internal pedicle is held with artery forceps. A 'V' cut is placed over the outer skin upto mucocutaneous junction. Dissection is deepened to visualise the internal sphincter. Once pedicle is dissected, it is transfixed using vicryl suture material. Distal tissue is excised. Technique is repeated on other sites also.

Postoperative complications

Pain
Retention of urine—commonest
Reactionary or secondary haemorrhage
Anal stricture
Anal fissure
Recurrence

- *Submucosal haemorrhoidectomy of 'Parks'*—Approach is above the skin through submucosal plane.

- *Hill—Ferguson closed* method wherein cut mucosa and skin is approximated using catgut suture.

10. ***Management of strangulated/thrombosed/gangrenous piles*:** Here initially conservative treatment is done using warm water sitz bath; antibiotics; elevation; bed rest; saline compression dressing; analgesics. This reduces the oedema and piles shrink. Later in 4-5 days haemorrhoidectomy is done. Doing haemorrhoidectomy immediately may precipitate portal pyaemia and also increases risk of developing anal stricture.

EXTERNAL PILES

Causes

- As a part of internal piles.
- Sentinel pile associated with anal fissure.
- Anal skin tags.



Fig. 25.50: Typical external pile. It causes haematoma, abscess, pain, itching.

Treatment

- The cause is treated.
- Sitz bath.
- Excision.

Problems

- Pruritus ani.
- Perianal haematoma.
- Perianal abscess formation.

ANAL FISSURE (FISSURE IN ANO)

- It is an ulcer in the longitudinal axis of the lower anal canal.
- Commonly it occurs in the *midline, posteriorly (more common in males),* but can also occur in the midline anteriorly (more common in females)**.**
- 95% of anal fissures in men are posterior; 5% are anterior. 80% of anal fissures in females are posterior; 20% are anterior. Anterior anal fissure is common in females.
- It is superficial, small but distressing lesion.
- Fissure ends above at the *dentate line***.**



Fig. 25.51: Anatomy of anal canal with fissure in ano. It is commonly posterior.

Causes

- Because of the curvature of the sacrum and rectum, hard faecal matter while passing down causes a tear in the anal valve leading to posterior anal fissure.
- Anterior anal fissure is common in females due to lack of support to pelvic floor.
- Hard stool; diarrhoea; increased sphincter tone; local ischaemia; trauma; sexually transmitted diseases.
- *Other causes*—Haemorrhoidectomy, Crohn's disease, venereal disease, ulcerative colitis, tuberculosis.

Types

- Anal fissure can be *acute or chronic*.

Acute Anal Fissure

- It is a deep tear in the lower anal skin with severe sphincter spasm without oedema or inflammation.
- It presents with *severe pain and constipation*.

Chronic Anal Fissure

- It has got inflamed, indurated margin with scar tissue.
- Ulcer at its inferior margin is having a skin tag which is oedematous, acts like a guard—*Sentinel pile.*

Life is ten percent, to make it and ninty percent, how you take it.

- Proximally *hypertrophied anal papilla* is observed.
- It can cause repeated infection—fibrosis—abscess formation—fistula formation.
- Chronic fissure is less painful than acute one.



Figs 25.52A and B: Fissure in ano (posterior). Note the ulcer with skin tag.



Fig. 25.53: Parts of chronic fissure in ano. Ulcer in the lower anal canal; sentinel pile below and hypertrophied papilla above.



Fig. 25.54: Fissure in ano with sentinel pile.



Fig. 25.55: Lateral fissure in ano.

Clinical Features

- Common in middle aged women, not in elderly.
- Pain is severe in nature in acute type, whereas less severe in chronic.
- Constipation, bleeding and discharge.
- P/R examination and proctoscopy is not possible in acute fissure in ano. General anaesthesia is required for examination.
- In chronic fissure, ulcer is felt with button like depression, induration and often sentinel pile.

Differential Diagnosis

- Carcinoma anal canal.
- Inflammatory bowel disease.
- Venereal diseases.
- Anal chancre (painful).
- Tuberculous ulcer.
- Proctalgia fugax.

Treatment

General measures for anal fissure

- Adequate fluid intake (6-8 glasses of liquids)
- Fiber rich diet (vegetables, fruits, brown rice)
- Bulk forming agents (psyllium husk, bran)
- Stool softeners (Lactulose)
- Local anaesthetic agents (Lignocaine 5%)
- Sitz bath
- Avoid constipation
- Once recovers, regular anal dilatation

*In an **acute*** **case**

- *Lord's dilatation* is done under G/A to relax the sphincter.
- Later, use of laxatives, xylocaine surface anaesthetic application, and anal dilatation with finger can be carried out for certain period**.**
- Bed rest; 2% nifedepine ointment.

For chronic fissure

- *Dorsal fissurectomy with sphincterotomy* is done under anaesthesia. Specimen should be sent for biopsy to rule out carcinoma, tuberculosis, etc. Here transverse fibres of internal sphincter is divided in the floor of the fissure.
- *Lateral anal sphincterotomy*
  - Here internal sphincter is divided partially away from the fissure either in right or left lateral positions (also gives a good result).
  - Here *closed or open methods* (Notaras) are used. Sphincterotomy is done below the dentate line. In *closed method* no 11 blade is inserted into the intersphincteric groove to pass upwards. Blade is moved medially to cut lower 1/3 or 1/2 of the internal sphincter. In *open method* skin is incised laterally, external to anal verge. Hypertrophied band of lower part of internal sphincter is dissected and divided. Wound is left open.
  - Haematoma, perianal abscess, bruising, fistula, incontinence are the complications of lateral sphincterotomy.
- Topical nitroglycerine 0.2% is also used to relax the sphincter. It causes severe headache.
- Botulinum toxin 25 units injected into the internal sphincter.
- Diltiazem (2%), L arginine are the other agents used.
- Regular anal dilatation is also often important to prevent recurrence.

SENTINEL PILE ('sentinel' means guard)

- It is commonly associated with *Fissure in ano* of chronic type wherein, in the lower part of fissure, skin enlarges and appears like guarding the fissure.
- The chronic fissure is treated along with excision of the sentinel pile.

ANORECTAL ABSCESS

- Most common causative organism is *E. coli.* Others are *Staphylococcus, Bacteroides, Streptococcus, B. proteus.* Commonly occurs due to infection of anal gland in perianal region.
- Common in diabetics and immunosuppressed.



Fig. 25.56: Lithotomy position used for all perineal surgeries like for fissure, piles, fistula, and APR.



Fig. 25.57: Sitz bath is used after perineal surgeries like for piles, fissure, and fistula. Patient sits in warm water bath with perineum dipped in the water. Often small quantity of antiseptics or $KMNO_4$ is added.



Fig. 25.58: Anatomy of anorectal abscess.

One cannot love what he cannot respect, whether it be himself or another.

- **Other causes:**
  - Injury to anorectum.
  - Cutaneous infection (e.g. Boil).
  - Blood born infections.
  - Many anorectal abscesses are associated with anal fistulas.
  - Fissure in ano.
  - Perianal haematoma.
  - Post anorectal surgery.
  - Crohn's disease.
  - Tuberculosis.

Differential diagnosis of anorectal abscess

- Periurethral abscess
- Bartholin abscess
- Tuberculous abscess

Classification

1. Perianal.
2. Ischiorectal.
3. Submucous.
4. Pelvirectal.
5. *Fissure abscess* (in relation to fissure in ano).

Perianal Abscess (60%)

- This usually results due to suppuration of anal gland or suppuration of thrombosed external pile or any infected perianal condition.
- It lies in the region of subcutaneous portion of external sphincter.



Fig. 25.59: Perianal abscess. Note the swelling and inflammation.

Clinical features

- Severe pain in perianal region with difficulty to sit.
- Tender, smooth, soft swelling in the region.



Fig. 25.60: Sites of anorectal abscess.

Treatment

- Sitz bath, antibiotics, analgesics, local application of anaesthetic agents and laxatives.
- Drainage under G/A.

Ischiorectal Abscess (30%)

Surgical anatomy

Ischiorectal fossa (pyramidal shape 5 cm depth and 2 cm width) lies between anal skin and levator ani. Right and left communicates with each other. Laterally it is related to fascia covering obturator internus; medially to levator ani and external sphincter; posteriorly sacrotubercous ligament and gluteus maximus; anteriorly urogenital diaphragm; below, the floor by skin. Above it is related to lunate fascia and pudendal neurovascular bundle in pudendal canal (Alcock's canal).



Fig. 25.61: Anatomy of ischiorectal fossa. Note the boundaries and Alcock's canal.

- Commonly it is due to extension of low intermuscular anal abscess, laterally through external sphincter.
- But often it can be blood or lymphatic born.
- Fat in the fossa is more prone for infection because it is least vascularised.

- Fossa communicates with that of opposite side through postsphincteric space and so *horse-shoe like* abscess can occur.
- It presents with tender, indurated, brawny swelling in the skin over the ischiorectal fossa with high fever.
- *Swelling is not well-localised and fluctuation is absent in ischiorectal abscess.*

Treatment

Under G/A in lithotomy position, through a cruciate incision a portion of skin is excised (de roofing) and pus is drained. Pus is sent for C/S and presence of any internal opening to rectum should be looked for (for possibility of an existing fistula).



Fig. 25.62: Cruciate incision is used for drainage of ischiorectal abscess.

Submucous Abscess (5%)

- It occurs above the dentate line, which can be drained with sinus forceps, through a proctoscope.
- Aching pain in the anorectum with significant perineal discomfort. .
- On digital examination (P/R), tender, soft, smooth swelling in the lower rectum and anal canal.
- It may be missed clinically as there is no obvious swelling externally.
- *Treatment* is proper antibiotics; incision and drainage under general anaesthesia.

Pelvirectal Abscess

- It is situated between the upper surface of levator ani and pelvic peritoneum. It is almost like a pelvic abscess, occurs secondary to appendicitis, salpingitis, diverticulitis, Crohn's.
- U/S abdomen is done to rule out the above factors.
- Treated accordingly, after thorough investigations for diabetes, Crohn's and other conditions.

Problems with anorectal abscess

- Recurrent abscess formation
- Fistula formation

FISTULA IN ANO

- It is a track lined by granulation tissue which connects perianal skin superficially to anal canal; anorectum or rectum deeply.
- It usually occurs in a pre-existing anorectal abscess which burst spontaneously.

Other causes are:

- Tuberculosis
- Carcinoma
- Crohn's disease
- Ulcerative colitis
- Lymphogranuloma venereum
- Hydradenitis suppurativa
- Traumatic



Figs 25.63A to C: Ischiorectal abscess drainage done under general anaesthesia. Note the cruciate incision placed and pus gushing out.

Success is never final and failure is never fatal.


Rectum
Dentate line
Anal valves

Fig. 25.64: Anatomy of fistula in ano.

Classifications

1. ***Low level fistulas—****these open into the anal canal below the internal ring.*
2. ***High level fistulas****—these open into the anal canal at or above the internal ring.*

Standard classification	*Park's classification*
Subcutaneous (Most comon)	Intersphincteric
Submucuous	Transphincteric
Low anal	Supralevator
High anal	Anal
Pelvirectal	


1
4
5
2
3
A
1. Pelvi-rectal fistula
2. Submucosal fistula
3. Subcutaneous fistula
4. High-anal fistula
5. Low-anal fistula
1
3
2
B
1. Supralevator fistula
2. Intersphincteric fistula
3. Transphincteric fistula

Fig. 25.65: Classifications of fistula in ano. (A) Standard classification and (B) Park's classification.

LOW-LEVEL FISTULAS

Clinical Features

- It presents with seropurulent discharge, along with skin irritation and one or more external opening may be present with induration of the surrounding skin.



Figs 25.66A to C: Fistula in ano—typical look and site.

- Often it may heal superficially but pus may collect beneath forming an abscess which again discharges through same or new opening.
- Ischiorectal fossa on each side, most often communicates with each other behind the anus causing *horse-shoe* fistula.

Goodsall's Rule

- Fistulas with an external opening in relation to the anterior half of the anus is of *direct type.*



Fig. 25.67: Goodsall's rule. Anterior fistulas are having straight track. Posterior fistulas are having curved track with internal opening in the posterior midline.

- Fistulas with external openings in relation to posterior half of the anus, has a curved track may be of horse-shoe type, opens in the midline posteriorly and may present with multiple external opening all connected to a single internal opening.
- ***P/R examination shows indurated internal opening usually in the midline posteriorly***.
- Most of the fistulas are on posterior half of anus.
- ***Probing in the ward and fistulogram*** in the ward before surgery using Lipiodol is not advisable as it may cause recrudescence of inflammation. It can be done with adequate precaution.

Investigations

- Chest X-ray, ESR and barium enema X-ray.
- *If required Fistulogram is done only under anaesthesia.*
- MRI/MRI fistulogram.
- Endorectal U/S is useful to assess deeper plane.



Fig. 25.68: Anterior fistula in ano with probe in place. Anterior low fistula has got straight track. Both internal and external openings are seen.



Fig. 25.69: Multiple fistulas in ano. It may be Crohn's disease; carcinoma or HIV. Biopsy should be done prior to formal therapy. MRI of perineum is of great help in such patients to anatomically evaluate the fistula in ano.

Tuberculous fistulas do not have induration, will have pale granulation tissue with watery discharge and they are most often multiple. Here the infection occurs in lymphoid tissue over the lower part of anal canal, around anal gland opening.

Our senses don't deceive us; our judgement does.



Fig. 25.70: Probing of the fistula track during surgery to find out its inner opening.

Treatment

- *Fistulectomy*
  - Under G/A or spinal anaesthesia, probe is passed through external opening up to the internal opening which is felt as an induration. Fistula is opened along the probe using a knife. Fibrous track along with unhealthy granulation tissue and additional external openings are excised. Specimen is always sent for histopathology.
  - Postoperatively—Sitz bath, antibiotics, analgesics, laxatives are given.
  - *Fistulectomy for low level fistulas do not cause rectal incontinence.*
  - Proper curetting of the infected anal gland area is essential.
- *Fistulotomy*

  It is done in low anal fistula. It is technically easier. After passing the probe through the entire fistulous track, incision is made over the probe to cut and lay open the fistulous track. It is allowed to granulate and heal from the floor/surface. Technique is safer, easier and can be done on outpatient basis.
- *Advancement flaps* are used occasionally to get better result.
- *Gluing of the fistula* track is tried but success rate is not good.

HIGH LEVEL FISTULAS

- Its upper opening is at or above the anorectal ring. It is difficult to treat.

Common causes are
Crohn's disease
Ulcerative colitis
Trauma
Carcinomas
Foreign body

- Incontinence may follow after lay opening of these fistulas.

Investigations

- Barium enema X-ray, colonoscopy, chest X-ray, biopsy.

Treatment

- Requires staged procedure—*Initial colostomy* is done followed by definitive procedure. This prevents sepsis and promotes faster healing.
- Later closure of colostomy is done.

Seton Technique

- A *silk or linen ligature* is passed across the fistula and left in place with a tie.
- This allows the fistula to granulate and heal from above and to close completely. Usually takes longer duration to heal.
- It is done for intermediate and intersphincteric fistula. It is used prior to definitive procedures like fistulectomy or advancement flap.
- Seton can be kept for 3 months. It can be regularly replaced by new silk or any material by rail road technique without anaesthesia.
- *Two types of setons are present*.
  - Loose setons are used mainly to drain for long period in recurrent/postoperative fistulas and due to specific causes like Crohn's. There is no tension in seton.
  - Cutting setons are used when enclosed muscle is needed to cut (cheese wiring through ice effect). It is placed tight.



Fig. 25.71: Seton technique for intersphincteric fistula in ano. It is kept for 3 months. It can be tight or loose seton depending on the indications. It promotes formation of granulation tissue, healing by fibrosis and track recedes downwards.

ANORECTAL STRICTURES

Causes

Congenital	LGV (in females)
Fibrotic anal fissure	Ulcerative colitis
Irradiation	Crohn's disease
Senility	Carcinomas
Postoperative (surgery for piles, coloanal anastomosis)	

Clinical Features

- Progressive constipation.
- On P/R examination, stricture can be felt as a tight ring.
- Features relevant of specific cause.

Investigations

- Barium enema X-ray, biopsy, colonoscopy

Treatment

- The cause is treated.
- Dilatation of the anal canal under general anaesthesia.
- Resection in severe recurrent cases.

CONDYLOMA ACUMINATA

- It is most common sexually transmitted anal disease. It is common in homosexual men.
- Penile warts or female genital warts may be present.



Fig. 25.72: Anal papilloma. It often attains very large size. It could be of viral origin. It can turn into squamous cell carcinoma.

- It is caused by Human Papilloma Virus (HPV).
- Pruritus, discharge, pain and bleeding are the features.
- Pinkish white warts in anal canal, often attaining large size causing *Buschke Lowenstein tumour*.
- Large wart may block the anal canal orifice.
- Whitening occurs on applying acetic acid on it.
- Biopsy confirms the diagnosis.
- Treatment is local application of 25% podophyllin cream; surgical excision of the wart; intralesional injection of interferon α 2b.
- Malignancy should be ruled out by histology.

ANAL INTRAEPITHELIAL NEOPLASIA (AIN)

- It is dysplasia of anal or perianal epidermis.
- It is seen in individuals with HIV infection; HPV infection; individual who do anorectal intercourse.

Classification–

AIN I – absence of keratocyte maturation and cellular atypia observed in outer 1/3 of epithelium – low grade.

AIN II – cellular atypia observed in middle 1/3 – low grade squamous intraepithelial neoplasia.

AIN III – cellular atypia full thickness – high grade squamous intraepithelial neoplasia.

- 30% of anal warts will show AIN.
- It is raised scaly white/pigmented/cracked lesion.
- Biopsy confirms the disease.
- Treatment: Excision; topical imiquimod and oral retinoids.

MALIGNANT TUMOURS OF ANAL CANAL

- *Anal malignant tumours* are < 2% of large bowel tumors. It can be below the dentate line (SCC, 80% of anal tumors); above the dentate line (Basaloid/transitional/cloacogenic).
- Causes may be HPV infection; HIV infection; AIN (Anal intraepithelial neoplasia); organ transplant recipients; immunosuppression.

Classification

It can be -

- Benign
- Malignant

It also can be -

- Tumour of the anus
- Tumour of the anal canal
- Anal marginal tumour

Two types of mankind are there; Hosts and Guests; on either way you are in trouble.



Figs 25.73A to C: Anal canal carcinoma. Squamous cell carcinoma is commonest type – 80%.

Types

1. *Squamous cell carcinoma* is the commonest type. Predisposing causes: Papilloma, irradiation, dermatitis, long standing fistula in ano.
2. Basaloid carcinoma—It is rare, non keratinising squamous cell carcinoma. Highly malignant.
3. Muco-epidermoid carcinoma—arises near squamo–columnar junction.
4. Basal cell carcinoma.
5. Melanoma—blue/black in colour mistaken for thrombosed pile—poor prognosis.
6. Adenocarcinoma from the anal glands in a pre-existing fistula in ano.

Features	*Investigations*
• Ulceration • Bleeding • Pain, pruritus and discharge • Irregular indurated mass • Anovaginal fistula in females • Faecal incontinence in late cases • Inguinal node- hard, nontender • Iliac nodes • Later- late constipation – obstruction	• Biopsy from anal region • FNAC of inguinal node • U/S abdomen • MRI perineum is very useful • *P/R is a MUST to assess upper extent of the growth* *AJCC staging* Tis – Carcinoma *in situ* T1 – Tumour < 2 cm T2 – Tumor 2-5 cm T3 – Tumor > 5 cm T4 – Invasion into adjacent organs like vagina/urethra N1 – Perirectal nodes + N2 – Unilateral internal iliac /inguinal nodes N3 – Perirectal + inguinal/ iliac or bilateral nodes M 0 – No distant spread M1 – Distant spread present

- ***Squamous cell carcinoma of anal canal,*** usually present as a fungating or ulcerative growth, which spreads to inguinal lymph nodes.
  - Biopsy and FNAC of lymph nodes are the essential investigations.
  - *Treatment:* Wide excision of the lesion with 3 to 5 cm clearance and ilioinguinal block dissection for lymph nodes are done. Follow up radiotherapy is also often given.
  - NIGRO regime

NIGRO Regime

NIGRO Regime for Anal Carcinoma
(Norman Nigro et al 1974)

- Initial radiotherapy for 3 weeks 3000 rads (30 Gy total) to perineum and pelvis

- Then chemotherapy – 5 FU, for 4 – 5 days; is a radiosensitizer, started on 1st day of RT as 1000 mg/m^2 continuous infusion. Mitomycin C is 15 mg/m^2 as single dose on 1st day of RT
- Later after 3 weeks Abdomino-perineal resection (APR)

  – ***Chemoradiation*** is becoming popular for carcinoma of anal canal.
  – Drugs used for chemotherapy are 5 FU, bleomycin, vincristine, adriamycin.
  – In advanced growths radiotherapy is the only treatment.
- ***All other tumours***: *Abdomino-Perineal-Resection with* permanent colostomy is done.

Paget's

- Paget's disease of breast
- Paget's disease of anal margin
- Paget's disease of penis
- Paget's test.
- Paget's disease of bone

ANAL MARGIN TUMOURS

1. Bowen's disease.
2. Paget's disease.
3. Basal cell carcinoma.
4. Squamous cell carcinoma.
5. Verrucous carcinoma (Giant condyloma acuminatum or Buschke-Lowenstein tumour).

SACROCOCCYGEAL TERATOMA

- It is an uncommon tumour, but most common of the large tumours in first 3 months of life.
- More common in females.
- Retention of large amount of primitive toti-potential cell in this region may be the reason for this tumour.
- It occurs between coccyx and rectum
- It is attached to coccyx, extends commonly downwards as a huge mass, occasionally upwards into the pelvis.
- It is a congenital condition arising from totipotent cells.
- X-ray and CT scan are must.

Complications	*Differential diagnosis*
Ulceration	Sacral meningocele
Infection	Sacral chordoma
Urinary obstruction	Postanal dermoid
Malignant changes	



Figs 25.74A and B: Sacrococcygeal teratoma, typical site (*by Dr Suresh Kamath, Mangalore*).



Fig. 25.75: X-ray of a patient with sacrococcygeal tumour.

Treatment

Excision soon after birth.

You never get the second chance to make the first impression.



Fig. 25.76: Recurrent chordoma of sacrum.

ANAL INCONTINENCE

Continence of anal canal is maintained by two factors.
- Normal rectal and colonic pressure and activity.
- Normal pelvic floor function.

Types

- *Urge incontinence*-Here rectal and colonic pressure and activity is increased but normal pelvic floor.
- *True incontinence*—Here rectal and colonic pressure and activity is normal but defective pelvic floor function.
- *Full incontinence*—Here rectal and colonic pressure and activity is reduced and also defective pelvic floor function.
- *Temporary*—Treated by reassurance. Often seen after Lord's dilatation.
- *Permanent*—Needs definitive therapy.

Causes

- Irritable bowel syndrome, severe diarrhoea.
- Prolapsed piles, rectal prolapse.
- Old age, malnutrition, debilitating illness.
- Congenital anomalies.
- Trauma, surgeries, injury during childbirth in females.
- Spina bifida, spinal tumours, spinal injuries and surgeries.
- Malignancy, postirradiation.
- Psychological causes.

Evaluation of the patient
- For specific causes
- Anorectal manometry
- Per-rectal examination
- Sigmoidoscopy

Treatment

- Suturing of the torn sphincter.
- Repair of puborectalis muscle and plication of external sphincter.
- Encircling operations around anal canal to give support using gracilis sling or mersiline sutures.
- Electrical stimulation of the puborectalis.
- *Secca therapy*: Temperature controlled radiofrequency energy in the anal canal and distal rectum to create scarring and fibrosis of internal sphincter and adjacent tissues.

DESCENDING PERINEAL SYNDROME

- When a healthy person increases the intraabdominal pressure and relaxes the pelvic floor muscles, there will not be any changes in the concavity of the perineum.
- In chronic ill-patients, malnourished, and people with preprolapse, perineal descent can occur with obliteration of the normal concavity of the perineum. It is called as *descending perineal syndrome*.
- Levators got injured directly or indirectly causing weakening of pelvic floor.
- Anal canal is situated many centimeters below the pubo coccygeal line. Usually 3-4 cm low during straining.
- *Defecography* is ideal to evaluate such patients. Perineometer is also used.
- Presentations are tenesmus; incomplete evacuation; incontinence.
- *Treatment* is diet, laxatives, avoiding straining, and suppositories.
- Restoration of pelvic floor by various surgical methods may be needed often with rectal resection and suspension.
- Total pelvic marlex mesh repair; transcoccygeal posterior hitching of the rectum (Kraske); correction of cystocele, rectocele and enterocele.
- Results are *not very good* as recurrence or residual problems may persist.

PROCTITIS

It is inflammation of rectal mucosa often with the inflammation of colon and anal canal.

Types

- Acute.
- Chronic.
- Nonspecific—common.
- Ulcerative proctocolitis as part of ulcerative colitis.

- Specific
  - Bacillary dysentery.
  - Amebic proctitis—common.
  - Combined amoebic and bacillary.
  - Gonococcal proctitis.
  - Lymphogranuloma inguinale (LGV).
  - Tuberculous proctitis.
  - Bilharzial proctitis due to Schistosoma Haematobium.
  - Enema induced proctitis especially of herbal enemas.

Clinical features

- Pain per rectum and anum
- Tenesmus
- Passage of mucus and blood
- Frequent urge to pass stool
- Fever, loss of appetite
- Pain and tenderness in left lower abdomen
- P/R is tender

Investigations

- Sigmoidoscopy is more relevant than just proctoscopy.
- Stool study, stool culture.
- Mucosal biopsy.
- Serological tests.
- Relevant investigations like ESR, blood smear, and chest X-ray.

Treatment

- Antibiotics, antiamoebic drugs like metronidazole.
- In severe cases, retention enema using metronidazole, prednisolone, salazopyrin.
- IV fluids, IV antibiotics and IV metronidazole are often required.
- Treating the specific causes like tuberculosis, gonococcal infection and bilharzial infection.

PROCTALGIA FUGAX

- It is sudden severe recurring pain in the rectum of unknown cause with segmental pubo coccygeal spasm.

Features

- It is common in young people may be due to stress, straining.
- Common at night, starts suddenly, lasts for few minutes and then subsides spontaneously.
- Pain is unbearable and severe with often constipation.
- Gradually subsides on its own.
- Occasionally only cutting of puborectalis muscle is required but with danger of developing incontinence.

HIDRADENITIS SUPPURATIVA OF ANAL REGION

- It is a chronic suppurativa condition of apocrine glands of the skin in axilla/perineum/mons pubis/thighs/scrotum etc.
- Apocrine gland duct obstruction → bacterial infection → multiple glands involvement → secondary infection (Staphylococcus aureus, streptococci) → skin oedema, multiple raised pustules → multiple communicating fistulae formation.
- Disease does not extend above dentate line or into sphincter.
- It is common in young obese females.
- Sinus; scarred areas; discharge; skin changes; pain and tenderness; foul smelling fluid are the presentations.
- *Differential diagnosis* are – Crohn's disease; fistula in ano; pilonidal sinus; tuberculosis; actinomycosis; LGV.
- *Treatment* -
  - Weight reduction; proper hygiene.
  - Antibiotics; analgesics.
  - Incision and drainage of abscess.
  - Laying open of all communicating tracks and regular dressing.
  - Radical local excision of entire apocrine bearing perineal skin with reconstruction using flap.
  - Recurrence is known to occur.

PRURITUS ANI

- It is intractable itching in and around anal canal.
- Skin is reddened, hyperkeratotic, cracked and moist.

Causes

- Poor hygiene.
- Anal discharge due to fissure/fistula/piles/warts/polyp.
- Trichomonas vaginalis infection of vagina in females.
- Parasites.
- Epidermophytosis.
- Allergic cause.
- Dermatitis/psoriasis.
- Intertrigo/erythrasma (Corynebacterium minutissimum).
- Diabetes mellitus; psychological cause.

His heart cannot be pure whose tongue is not clean.

Treatment: Proper cause should be assessed and treated. Good hygiene; local steroid application; topical xylocaine; strapping of the buttocks are needed.

GASTROINTESTINAL HAEMORRHAGE (GI BLEED)

GI bleed is classified as upper GI and lower GI bleed.

- ***Upper GI bleed*** is bleeding above the level of ligament of Treitz.
- ***Lower GI bleed*** is bleeding below the level of ligament of Treitz.

  Ligament of Treitz is a fibromuscular band, which extends from right crus of diaphragm to duodenojejunal flexure with upper part made up of striped muscle fibres, lower part smooth muscle fibres and middle part with elastic fibres.



Fig. 25.77: Anatomy of ligament of Treitz.

UPPER GI BLEED

Causes

- Peptic ulcer 65%. Ulcer bleeding is precipitated by NSAIDs, steroids, alcohol. Ulcer bleeding is overall common in men. But NSAID induced ulcer bleeding is common in females.
- Gastroduodenal erosions.
- Oesophageal varices.
- Gastric ulcer.
- Oesophagitis and erosions.
- Carcinoma stomach – 5%
- Mallory-Weiss syndrome – 5-15%.
- Vascular anomalies—Dieulafoy's syndrome (A-V malformation in the fundus of the stomach), Osler-Weber-Rendau syndrome, Ehlers-Danlos syndrome.
- Aortoduodenal fistula.
- Bleeding disorders.

Factors which aggravate the bleeding:

- Gastric acid which inhibits the platelet aggregation
- Pepsin, by its proteolytic action causes erosion of the ulcer into the vessel. It also digests the clot, so as to aggravate the bleeding
- Mucosal blood supply pattern
- Gastric motility
- Alcohol, drugs

  Major haemorrhage occurs when erosion of gastroduodenal artery or left gastric artery or splenic artery occurs or when bleeding occurs from varices

Clinical Features

Acute bleed

- Features of shock.
- Haematemesis.
- Melaena.

Chronic bleed

- Hypochromic microcytic anaemia, glossitis, koilonychia, congestive cardiac failure.
- Mortality in upper GI bleed is 10%.

Investigations



Fig. 25.78A



Fig. 25.78B

Figs 25.78A and B: Bleeding peptic ulcer (duodenal ulcer) is the commonest cause of upper GI bleed. Oesophageal varix causes dangerous severe life threatening bleed.

- Gastroscopy to see the spurting vessel, oozing, clot in the ulcer, collected blood in the lumen of the stomach.
- Angiography of superior mosenteria artery.
- Hb%, packed cell volume, CVP measurement, blood grouping and cross matching.
- LFT; prothrombin time; platelet count; blood urea and serum creatinine; serum electrolytes.
- U/S abdomen.

Treatment

- General: IV fluids, catheterisation, Ryle's tube aspiration, blood transfusion.
- Injection ranitidine IV 50 mg 8th hourly, or famotidine IV, omeprazole IV, pantoprazole IV.
- Antifibrinolytics like tranexamic acid, EACA.
- Somatostatin or octreotide.
- For varices, vasopressin, propranolol, isosorbide dinitrate, Sengstaken tube tamponade, sclerotherapy, Boerema-crile operation, Hasaab operation (devascularisation with splenectomy), oesophageal transection, Siguira-Futagawa operation or TIPSS.
- For peptic ulcer, saline wash with 1 : 2,00,000 adrenaline, Nd: YAG laser therapy, cautery coagulation, thrombin injection, Finney's pyloroplasty, partial gastrectomy, ligation of gastroduodenal or left gastriartery, cytoprotectant Mesoprostil injection.
- The cause is treated, once acute episode is under control.

Prognosis

- Varices and gastric ulcer bleed has higher mortality.
- Bleeding duodenal ulcer has got better prognosis.

LOWER GI BLEED

- Bleeding in the GIT below the level of the ligament of Treitz.
- Normal faecal blood loss is 1.2 ml/day. A loss more than 10 ml/day is significant.

Causes



Fig. 25.79: Causes of lower GI bleed.

- Angiodysplasia.
- Diverticular disease – commonest cause in Western countries.
- Tumours of colon or small bowel.
- Anorectal diseases—Haemorrhoids, fissure in ano.
- Ulcerative colitis, Crohn's disease.
- Colorectal polyps; rectal carcinomas.
- Intussusception.
- Tumours, either benign or malignant of colon or small bowel.
- Meckel's diverticulum.
- Ischaemic colitis.
- Stercoral ulcer.
- Infectious colitis.
- Mesenteric artery occlusion.

God gives every bird its food, but he does not throw it into the nest.

Lower GI bleed can be:
- Occult bleed: > 10 ml/day but not revealed
- Overt bleed: Bleeding which is revealed
  - Overt acute
  - Overt acute massive (bleed > 1.5 litre/day)
  - Overt chronic

Common causes
- Internal piles
- Diverticular disease
- Neoplasia
- Inflammatory bowel diseases
- Angiodysplasia

I. Bleeding may be:

Small bowel bleed: Polyp', Meckel's diverticulum, mesenteric ischaemia, intussusception; small bowel tumor.

Large bowel bleed: Angiodysplasia, carcinoma, colitis, diverticulitis, carcinoma.

Anorectal diseases: Piles, fissure in ano, carcinomas.

II. Bleeding may be:

Congenital: Polyp's, Meckel's diverticulum.

Inflammatory: Ulcerative colitis, infective, amoebic, Crohn's disease.

Neoplastic: Adenomas, carcinomas, polyps.

Vascular: Angiodysplasia, mesenteric artery ischaemia, colitis.

Others: Piles, fissure in ano.

Angiodysplasia is common in caecum and ascending colon.

Bleeding more than 1.5 litres per day is called as *acute massive GI bleed.*

***Acute bleed occurs* in:**
- Mesenteric ischaemia
- Angiodysplasia
- Ischaemic colitis
- Meckel's diverticulum
- Intussusception
- Acute episodes of ulcerative colitis
  80% of acute bleed regress spontaneously
  20% will become either massive or recurrent

Presentations

- Acute bleeding presents with features of shock.
- Chronic blood loss occurs in piles, fissures, colitis. Presents with hypochromic, microcytic anaemia.
- Tenesmus, subacute obstruction, loss of appetite, decreased weight, bloody diarrhoea is seen in carcinoma distal, large bowel.
- Per-rectal examination is a must which may reveal polyp, growth, ulcerations.
- Haematochezia.
- Mass palpable per abdomen in left or right iliac fossa or mass of intussusception.

- *Blood with mucus*—colitis, carcinoma
- *Fresh blood as splashes in the pan*—piles
- *Maroon coloured stool*—Meckel's diverticulum
- *Red currant jelly in stool*—intussusception
- *Bright red blood in stool*—polyps

Investigations

- Hb%, packed cell volume, ESR.
- Bleeding time; clotting time; prothrombin time; platelet count; blood urea and serum electrolytes.
- Occult blood in the stool—positive faecal blood test using Guaiac reagent.
- Barium enema.
- Proctoscopy for piles and sigmoidoscopy for rectosigmoid diseases.
- Colonoscopy for colitis, carcinomas, polyps.
- Small bowel enema (enteroclysis).



Fig. 25.80: Sigmoid diverticula on colonoscopy. It is the common cause of lower GI bleed in Western countries.

- U/S abdomen.
- Mesenteric angiogram is very useful investigation in acute bleed, especially in angiodysplasia.
- Technetium scan for Meckel's diverticulum.
- Capsule endoscopy.

Treatment

- Endoscopic fulguration or therapeutic embolisation or right hemicolectomy (for angiodysplasia).
- Endoscopic polypectomy for polyps.
- Treatment for ulcerative colitis with mesacol enema or drugs or total proctocolectomy with ileo-anal anastomosis.
- Surgical resection of colonic carcinoma.
- Massive resection of small bowel in mesenteric ischaemia.
- Sigmoid colectomy in sigmoid diverticula.
- Cause is treated.
- Proper exploration through a lengthy midline incision is essential.

Self-assessment Questions

- Rectal prolapse.
- Carcinoma rectum.
- Anterior resection.
- AP resection.
- Rectal stricture.
- Haemorrhoids.
- Treatment for piles.
- Anorectal malformations.
- Fissure-in-ano.
- Fistula-in-ano.
- Goodsall's rule.
- Complications of haemorrhoids.
- Partial rectal prolapse.
- Complete rectal prolapse.
- Pilonidal sinus.
- Lord's dilatation.
- Proctoscopy.
- Sigmoidoscopy.
- Per-rectal examination.
- Differential diagnosis for bleeding per anum.
- Preparation of large bowel for surgery.
- Staging of rectal carcinoma.
- Sentinel pile.

Diseases of the soul are more dangerous than those of the body.

26

Urology

Kidney

> *It is no exaggeration to say that the composition of the blood is determined not by what the mouth ingests but by what the kidneys keep; they are the master chemists of our internal environment, which, so to speak, they synthesize in reverse.*
>
> —**Homer William Smith,** 1939

Anatomy of kidney and ureter
Plain X-ray—KUB
IVU
RGP
Renal angiogram
MCU
Ascending urethrogram
Isotope renography
Cystoscopy
Catheters—*Foley's catheter, Malecot's catheter, Red rubber catheter*
Nephrostomy
SPC
Haematuria
Horseshoe kidney
Cystic diseases of the kidney—*Polycystic kidney disease, Solitary renal cyst*
Duplication of renal pelvis and ureter
Retrocaval ureter
Ureterocele
Injuries to kidney
Renal tuberculosis
Hydronephrosis
Pyonephrosis
Carbuncle of kidney (Renal carbuncle)
Perinephric abscess
Renal calculus
Ureteric calculi
Staghorn calculus
Wilms' tumour
Renal cell carcinoma
Approaches to kidney

ANATOMY OF KIDNEY AND URETER

KIDNEY—ANATOMY

- They are a pair of excretory organs situated retroperitoneally, on the posterior abdominal wall; one on each side of vertebral column.
- Vertically it extends from the upper border of T_{12} vertebra to the centre of the body of L_3 vertebra. The right kidney is slightly lower than the left, left kidney is slightly nearer to the median plane.
- Each kidney is about 11 cm long, 6 cm broad, 3 cm thick. Lateral border is convex. Medial border is concave with a hilum. Structures seen in the hilum are (from anterior to posterior)—(1) renal vein, (2) renal artery, (3) renal pelvis.
- Upper pole is related to suprarenal gland; lower pole lies 1 inch above the iliac crest.
- Capacity of renal pelvis is 10 ml.
- The angle between the 12th rib and the outer border of the sacrospinalis is the kidney angle. Kidney pain is usually referred here and pressure over this point elicit pain in kidney lesions.
- Hepato-renal pouch is a peritoneum lined deep recess, related to the upper pole of kidney. It is the lowest site when the body is in horizontal position,

excluding the pelvis. Collection of extravasated fluid is likely to occur in this pouch following surgeries to liver and biliary tract.

Capsules of Kidney

1. Proper capsule—Fibrous membrane which can easily be stripped off from the organ.
2. Perirenal fat is in the space of Gerota.
3. Renal fascia of Gerota—Has got anterior layer *(Fascia of Toldt)* and posterior layer *(Fascia of Zuckerkandl).*
4. Pararenal body of fat.

Structure of Kidney

Gross

Coronal section shows outer brownish cortex, inner pale medulla, renal sinus.

Renal sinus is a space that extends into the kidney from hilus. It contains (1) branches of renal artery, (2) branches of renal vein, (3) renal pelvis.

The pelvis divides into 2-3 major calyces which in turn divides into 7-13 minor calyces.

Histology

Each kidney is composed of 1-3 millions of uriniferous tubules; each of which has a collecting part *(collecting tubules)* and secretory part *(nephron).*

Blood supply

It is from renal artery, which arises from the aorta at right angles, at the level of intervertebral discs between L_1 and L_2 vertebrae. About 95% of abdominal aortic aneurysm arises below the level of origin of renal artery.



Fig. 26.1: Segments of kidney.

The kidney is divided into anatomic segments based on blood supply. In the hilum, the main artery, divides into anterior and posterior divisions. The anterior division supplies the apical, upper, middle and lower segments; posterior segment is supplied by the posterior division. The knowledge of this is important in the operation of anatrophic nephrolithotomy, where a functionally *avascular plane* (*Brodel*) between the posterior segment and the upper and middle segments exist on the posterior half of the kidney, about two-thirds of the way from the hilum to the lateral margin of the kidney.

Nerve supply

$T_{10,11,12}$ through the lesser and lower splanchnic nerves.

Lymphatics

They are drained into para-aortic nodes. Perinephric fat is removed during nephrectomy (for malignancies), as intrarenal lymphatics freely communicates with the plexus in the perinephric fat.

URETER—ANATOMY

- Each ureter is 25-30 cm long. It begins within the renal sinus as a funnel shaped dilatation called renal pelvis.
- It enters the bladder wall obliquely to open at the lateral angle of the trigone.
- It lies in the retroperitoneal space not attached to any fixed structures, so can be displaced or obstructed by retroperitoneal masses like tumours or aneurysms.
- Abdominal portion of ureter lies on the medial portion of psoas major muscle near the tips of transverse processes of lumbar vertebra (which is very well seen in IVP).
- The ureter enters the pelvis crossing the end of common iliac or beginning of external iliac artery.
- In females, uterine artery crosses the ureter from lateral to medial side, about 2 cm lateral to the cervix (this has to be remembered while ligating the uterine arteries in hysterectomy).

***Normal sites of constrictions*:** (1) PUJ, (2) At the brim of lesser pelvis, (3) Along its passage through the bladder wall

- ***Arterial supply:*** Upper segment of ureter receives blood supply from branches of renal and adrenal arteries; the middle portion from the branches of arteries of posterior abdominal wall; the pelvic portion from the branches of internal iliac arteries.
  - Vessels reach the abdominal portion of ureter on the medial side; whereas the pelvic portion receives on the lateral side. (This has to be remembered while mobilising the ureter.) The vessels form an anastomotic plexus in the adventitia of the ureter, which is found to be deficient in 10-15% of individuals leading to necrosis of cut ends of ureter following extensive mobilisation.

The remedy for injuries is not to remember them.

PLAIN X-RAY—KIDNEY, URETER, BLADDER (KUB)

- Preparation of the patient – Enema/bowel wash/laxative is given on the previous day and the patient is asked to fast in order to reduce the bowel gas shadows in X-ray.
- High penetration X-ray is taken in supine position which covers *pubic symphysis and lower two ribs*.
- Interpreting the film:
  a. First bony parts are looked for, i.e. the hip, pelvis, lumbar vertebrae for fractures, scoliosis, spina bifida, secondaries in the spine.
  b. ***Kidney shadow***—Kidney shadows are visualised in plain X-ray KUB due to difference in the density between kidney (high vascularity) and perinephric fat (low vascularity). Findings noted are size, location, calcification and stones. In children, perinephric fat is absent and so kidney shadows are not visualised.
  c. ***Psoas shadow***—It is visualised well in normal KUB.

Psoas shadow is obliterated in:
- In enlarged kidney
- In scoliosis due to inflammatory or infiltrative causes
- In malignancy
- Tuberculous spine with cold abscess (psoas abscess)
- Splenic injury—In left sided shadow
- Retroperitoneal tumours

  d. ***Ureteric line***—It is looked for any radiopaque shadow (ureteric stone). It runs along the tips of the *transverse processes of the lumbar vertebrae*, crosses the *sacroiliac joints* and reaches upto a point medial to the *ischial spine.*
  e. Bladder, prostate and urethral areas are visualised for any lesion.



Fig. 26.2: Plain X-ray KUB AP-view. Note the psoas shadow.

INTRAVENOUS UROGRAM (IVU)



Figs 26.3A to C: IVU showing hydronephrosis with clubbing of calyces and dilatation. Delayed post-lasix film often should be taken whenever there is poor secretion in initial films. Film can be taken as late as 72 hrs. This delayed film shows dilatation. (*Courtesy by Dr Navinchandra Shetty MD, HOD of radiology, KMC Mangalore*).

Procedure

Renal function must be normal.

- Overnight fasting for 8 hours is advised. Laxatives are given to reduce bowel shadow and get a good quality film.
- First, a plain X-ray KUB is taken (IVU should not be read without doing KUB)

- Then 1 ml test dose of **sodium diatrizoate** (*Urograffin)* or **meglumine iothalamate** is injected IV and waited for 5-10 minutes for any reaction. If no adverse reaction occurs, then full dose 1 ml/kg body weight, IV urograffin is given (40-50 ml).
- X-ray is taken in 1-5 minutes, which shows the nephrographic and secretory function of the kidneys.
- Later 15 minute and then 20-30 minute films are taken.
- Further films are taken depending on the need.
- Film can be taken as late as 72 hours. Late films show bladder pathology as well as residual urine.
- In case of *renal failure* with high blood urea, dose of dye is increased to 2 ml/kg body weight to get a better film—***Infusion IVU***. Often diuretics are used in these patients to have better secretion.



Fig. 26.4: IVU showing hydronephrosis.

- Lower abdominal compression is done for 10 minutes to have better definition of calyces, but not done in children and patients with abdominal aortic aneurysm.
- ***Minute IVU***—In case of renal artery stenosis, within first minute many films are taken to see nephrographic shadow (where a small, concentrated kidney is seen).
- ***Nonvisualization of kidney:*** No contrast is seen in the film even after 12 hours.



Fig. 26.5: IVU showing hydronephrosis on right side; normal secretion on left side; with bladder filling.

IVU (INTRAVENOUS UROGRAM)

Indications	*Findings*
1. Hydronephrosis	Clubbing of calyces
2. Congenital anomalies	
a. Horse shoe kidney	Flower vase appearance
b. Duplex kidney and double ureter	
c. Ureterocele	Adder (cobra) head appearance
d. Polycystic kidney disease	Spider leg appearance
e. Retrocaval ureter	Reverse 'J' sign with hydronephrosis
3. Renal cell carcinoma	Irregular filling defect; spider leg appearance
4. To see the function of the kidneys in bilateral diseases	Bilateral stones, obstructive uropathy
5. After surgery for urinary diseases	To see the function of kidneys and outcome of the surgery
6. Renal injury	To see the function of other kidney (a very specific investigation)

Contraindications:

1. Iodine sensitivity—may go for anaphylaxis. Hence, all precautions must be taken and essential drugs should be available while doing IVU
2. Multiple myeloma and hypergammaglobulinaemias (Acute renal failure may be precipitated due to dehydration.)
3. Toxic thyroid

If someone is greedy, bribe him, if someone is foolish, advise him; if someone is wise, listen to him.

RETROGRADE PYELOGRAPHY (RGP)

Indications

- Failure of showing any secretions in an IVU as late as 72 hours film
- Urinary tuberculosis
- Urothelial tumours from the renal pelvis

Procedure

- Under G/A, cystoscope is passed. Ureteric orifice is visualised.
- Ureteric catheter is passed. Dye, sodium diatrizoate is injected.
- Patient is put in 15° head down position to allow the dye to reach upper urinary system.
- X-ray is taken.

Advantages

a. Prior to dye injection selective urine sample can be taken from each ureter.
b. Brush biopsy from suspected urothelial tumours of upper urinary tract can be taken.
c. Better-delineation of anatomy (due to more concentration of dye).



Fig. 26.6: Left RGP—Normal study.

Disadvantage

Anaesthesia is required and is laborious.

RENAL ANGIOGRAM

Indications

- Renal artery stenosis
- Renal artery atheroma
- Renal artery aneurysm
- Occasionally renal cell carcinoma
- Arterial anomalies

Procedure

Retrograde Seldinger technique:

- Through femoral artery, using Seldinger's needle selective angiogram is done to visualise tumour vascularity, narrowing, anomalies. Dye used is Hypaque. Dose: 6-7 ml.
- Therapeutic embolisation, transluminal balloon angioplasty for renal artery stenosis can also be done by this approach.
- Translumbar approach for angiogram (through aortogram) is also used. Hypaque used is 30 ml.

Complications

- Paraplegia
- Embolism
- Dissecting aneurysm
- Bleeding
- Renal tubular necrosis

Renal pharmacoangiogram:

- Noradrenaline is injected along with the dye. Normal vessels will constrict in response to noradrenaline. But since tumour is autonomous, vessels in renal cell carcinoma do not respond to noradrenaline and so *tumour blush* is seen.

MICTURATING CYSTOURETHROGRAPHY (MCU)

Indications

a. Vesicoureteric reflux.
b. Posterior urethral valve.

Procedure

Catheter is passed into the bladder. Dilute iodine dye is infused. X-ray is taken during micturition. *Free reflux* is looked for. Applying pressure over the suprapubic region, X-ray is taken. *Pressure reflux* is studied.

Vesicoureteric reflux is graded depending on the severity of the reflux—as:

I — Ureters seen
II — Ureters and pelvis are seen
III — Ureters, pelvis, calyces are seen
IV — With grossly distended calyces
V — Tortuous elongated serpentine ureters

It can be unilateral or bilateral. Often it is associated with posterior urethral valve. It is often complicated by infection, pyonephrosis and renal failure

Investigations: MCU, IVU, U/S, blood urea and serum creatinine

Treatment: Tailoring of ureter with reimplantation



Fig. 26.7: Micturating cystourethrogram showing concomitant existence of posterior urethral valve (causing dilatation of proximal urethra) and vesicoureteric reflux (left side).

ASCENDING URETHROGRAM

- It is the investigation of choice for *stricture urethra*.
- Red rubber catheter is passed into the external meatus.
- Water soluble iodine dye is injected through the catheter.
- Oblique X-ray films are taken to visualise the urethra.
- Site, size, extent of stricture and extravasation can be found out in urethrogram.



Figs 26.8A and B: Ascending urethrogram showing stricture urethra.

ISOTOPE RENOGRAPHY

- A measure of individual kidney function is obtained by this method using a gamma camera.
- Radio labelled Technetium 99m **DMSA** (Dimercapto-succinic acid) **or DTPA** (Diethylenetriamine-penta acetic acid) is given intravenously.

DTPA – renal function.

DMSA – renal parenchymal changes.

It shows:

a. *Early* vascular phase.
b. *Then* secretory phase.
c. *Later* excretory phase.

- This allows the assessment of renal plasma flow to each kidney and the efficiency and effectiveness of pelvi calyceal excretion also.
- Secretion < 20% is precarious.



Fig. 26.9A

> *The skilful doctors know what is wrong by observing alone, the middling doctor by listening and the inferior doctor by feeling the pulse.*
> —Chang Chung-Ching



Fig. 26.9B

Figs 26.9A and B: Isotope renogram showing reduced secretion on right side.

Problems

1. Positioning of counters.
2. Often difficult to differentiate from muscle mass. It is only a supportive investigation.



Figs 26.10A to C: Renography showing (A) Normal study, (B) Hydronephrosis and (C) Renal failure.

CYSTOSCOPY

Uses

a. To examine urethra, bladder, ureteric orifice for any pathology (tumour, infection)
b. To visualise any bladder fistulas



Fig. 26.11: Isotope renogram showing kidney function.

c. To treat
- Urethrotomy (in stricture urethra)
- TURP for BPH and carcinoma prostate
- Bladder tumour resection
- Bladder stone removal (cystolithotripsy, cystolitholapaxy)
- Ureteric catheterisation
- Fulguration of posterior urethral valve

Contraindication: Acute cystitis and prostatitis

Types

- ***Rigid.***
- ***Flexible.***

Procedure

- Patient is placed in lithotomy position.
- Under G/A or spinal anaesthesia after cleaning and draping, through urethra, cystoscope is passed using continuous *glycine irrigation* (to avoid TURP syndrome).
- The parts of the urethra are visualised while passing the cystoscope.
- Once bladder is reached, it is looked for diverticula, hypertrophy and other pathologies.
- Ureteric orifices are visualized.



Fig. 26.12: Cystoscope.

Complications

- Urethral injury.
- Bleeding.
- Water intoxication.

Fig. 26.13: Cystoscopy is being done for different procedures like TURP; diagnostic, etc. (*Courtesy by Dr. Ashok Pandit MCh Urologist, Mangalore*)

CATHETERS

They are hollow tubes used to relieve urinary retention, obtain urine for analysis, irrigate bladder and to instill drugs into bladder.



Figs 26.14: Photo showing red rubber catheter; Malecot's catheter and Foley's catheters.

Types

a. Nonself-retaining catheter: Simple red rubber catheter.

b. Self-retaining catheter: Foley's catheter, Malecot's catheter, Gibbon's catheter, De-pezzer catheter.

Types of Catheterisation

a. ***Indwelling catheterisation*:** When a catheter is left behind in bladder and remains so it is called an indwelling catheter.

It is achieved by:

— Ballon tip of catheter—Foley's catheter.

— Flower tip of catheter—Malecot's catheter, De-Pezzers.

— Straping catheter externally—Gibbon's catheter.



Figs 26.15A to C: Gibbon's catheter. Note the look and method of fixing in male and female. It is a self-retaining catheter made up of plastic with a stillete in it which makes its passage easier through urethra. Sizes differ for males and females because of the difference in length of the urethra in male and female. Catheter has two ribbons attached which can be used to fix to the genitalia by adhesive plaster. Gibbon's catheter is least irritant to urethra.

> *When the patient dies the kidneys may go to the pathologist, but while he lives the urine is ours. It can provide us a serial story of the major events going on within the kidney.* —Thomas Addis

b. ***Intermittent catheterisation*:** A sterile catheter is introduced intermittently by the patient or by others.

FOLEY'S CATHETER (Fredrick Eugene Basil Foley—American Urologist)

It is a *self-retaining* urinary catheter made of *latex*. It has got a balloon near the tip into which distilled water is infused to make it *self-retainable*. Usually, Foley's catheter is kept for 7 days.

Sterilized by γ-radiation.

Size: Adults—16 F.
Children—8 F or 10 F.

(F—French unit, Charriere unit, where each unit equals 0.33 mm). 16 F means circumference of the catheter is 16 mm. Diameter is one-third of circumference).



Figs 26.16A and B: Foley's catheter. Two way/three way Foley's catheters are available.

Uses

1. To pass per urethrally in retention of urine of any cause (BPH, stricture, trauma).
2. To measure the urine output in renal failure, postoperative patients, terminally ill patients.
3. Percutaneous cystostomy.
4. Cholecystostomy.
5. To drain fistulas.

Types

1. Two-way Foley's.
2. Three-way Foley's—To give bladder irrigation, e.g. following TURP.
3. Silicon coated Foley's—To reduce reaction and so as to keep for longer period (3 months).

Procedure

- After cleaning under strict asepsis, lignocaine gel is lubricated onto the urethral meatus. Catheter is passed into the urethra.
- Sometimes *Maryfield introducer* is used to pass Foley's catheter.
- Once catheter is in the bladder, urine flows out. It is now connected to a *urosac bag*.
- Balloon is inflated with 20-30 ml (amount is written on the catheter) of distilled water to make it self-retainable.
- During removal of the catheter same amount of water should be removed from the balloon before pulling out the catheter.

Complications

- Infection
- Encrustation
- Bleeding
- Stone formation
- Blockage
- Stricture
- Difficulty in removal of the catheter due to blockage of the balloon channel. Here bulb of Foley's can be punctured either from above under U/S guidance or injecting ether into the balloon so as to burst it but may cause chemical cystitis or passing a stilette into the channel

MALECOT'S CATHETER

- Self-retaining urinary catheter with an umbrella or flower at the tip. It is made of red rubber, contains sulphur and so it is radio-opaque.

- It is never introduced per urethrally.
- It is sterilised by boiling.



Fig. 26.17: Malecot's catheter – photo.



Fig. 26.18: Malecot's catheter – diagram

Uses

1. Suprapubic cystostomy (SPC)
   a. In case of urinary retention when Foley's catheterisation fails (after two trials)
   b. For diversion of urine following bladder, prostate or urethral surgeries
2. Perinephric abscess
3. Pyonephrosis
4. Cabot's nephrostomy
5. Subphrenic abscess
6. Cholecystostomy
7. Infected pseudocyst of the pancreas
8. Amoebic liver abscess
9. Gastrostomy

Advantages

- Malecot's catheter can be kept for a longer duration (3 months).
- It drains fluid adequately.
- Less infection rate.
- Removal is easier.

Disadvantage

- Surgery (open method) is required to insert the catheter.

RED RUBBER CATHETER

- It is a non self-retaining urinary catheter.
- Its tip is blunt. It has got only side opening.

Uses



– Only opening in the side wall near the tip
– No opening at the tip
– Nonself-retaining
– Rounded tip

Fig. 26.19: Simple red rubber catheter. It has got only side opening. No opening in the tip (Flatus tube has got opening on both sides as well as at the tip).

1. Used to drain urine from the bladder temporarily.
2. To find out residual urine. After passing urine, catheter is introduced into the bladder. The amount of retained urine is measured. If it is more than 30-50 ml it signifies obstruction. It often increases up to 200-300 ml in conditions like BPH.
3. Other uses
   - To administer nasal oxygen.
   - For throat suction.
   - As a tourniquet for venesection and surgeries of fingers and toes.

NEPHROSTOMY

Nephrostomy is diversion of urine by passing a tube through the kidney into the calyces**.**

Indications

- Pyonephrosis
- Severe hydronephrosis
- Postoperative—Following renal surgeries
- Obstruction in ureters

Good health is a serious business: like life itself, it has to be worked at and it takes on added meaning with effort.
—Normour Cousins



Figs 26.20A to C: Nephrostomy types: (A) Cabot's nephrostomy, (B) Tresidder's nephrostomy and (C) Percutaneous nephrostomy.

Types

1. ***Cabot's nephrostomy***—Malecot's catheter is placed into the calyces.
2. ***Tresidder's through and through loop nephrostomy***—Loop tube is placed with central part in the kidney and ends outside percutaneously to drain urine. This achieves double drainage. New tube can be placed using rail road technique.
3. ***Percutaneous nephrostomy***—Done under U/S guidance using guide wire and dilators.

Complications of nephrostomy
- Bleeding
- Sepsis
- Blockage

SUPRAPUBIC CYSTOSTOMY (SPC)

- It is placing of Malecot's catheter into the bladder above the pubis by open method, or percutaneously under the guidance using Foley's catheter.
- It is a temporary opening through the abdominal wall into the bladder.

Prerequisite

- Bladder must be full and is confirmed by dullness below the umbilicus or by U/S.

Indication

- Retention of urine, when urethral catheterisation fails.



Fig. 26.21: Suprapubic cystostomy (SPC). Malecot's or Foley's catheter can be used.



Fig. 26.22: X-ray showing radio-opaque Malecot's catheter.

Procedure

- Under local anaesthesia (Xylocaine 2% above the pubis, in the midline) or G/A, a vertical midline incision of 3 cm in length is placed through linea alba. Skin, fascia, anterior rectus sheath are incised. Recti are retracted. In extraperitoneal space, peritoneum with pad of fat is reflected upward.
- Bladder is identified by the pattern of detrusor muscle and vesical venous plexus and is also confirmed by aspirating urine through a syringe.
- The bladder is opened near the fundus. Urine is aspirated. Bladder wall is inspected for any pathology.

- Malecot's catheter is straightened using artery forceps and placed in the bladder. Sutures are placed around the Malecot's catheter. Wound is closed in layers.
- In percutaneous SPC, Foley's catheter is passed into the bladder using trocar and cannula.

Complications

- Injury to bowel, peritoneum.
- Infection.



Figs 26.23: Ectopic kidney right sided IVU picture. It is un-ascended kidney. It often presents as mass in the right iliac fossa. CT scan is diagnostic. Differential diagnoses for masses in right iliac fossa are nodal mass; carcinoma caecum; tuberculosis; psoas abscess; retroperitoneal tumour. Sepsis; stones; tumour; can occur in ectopic kidney. Management of whatever problems arise is done through open method. Bilateral ectopic kidney may lead into eventual renal failure. Isotope scan is diagnostic.

HAEMATURIA

Types

a. *Gross* (visible to unaided eye).
b. *Microscopic* (> 5 RBC's/HPF).

Early (initial) haematuria: Urethral origin, distal to external sphincter

Terminal haematuria: Bladder neck or prostate origin

Diffuse (total) haematuria: Source is in the bladder or upper urinary tract

False haematuria: Discolouration of urine from pigments such as food colouring and myoglobin.

Silent haematuria is due to tumours of kidney or bladder unless proved otherwise.

Causes

- Renal injury
- Urinary stones
- Wilm's tumour
- Tuberculosis
- Renal cell carcinoma
- Cystitis
- Bladder tumour
- Urinary bilharziasis
- BPH, carcinoma prostate
- Renal infarct
- Glomerulonephritis
- Blood dyscrasias


Benign
Malignant
Glomerulonephritis
Infarct
Renal stone
Tuberculosis
Trauma
Ureteric stone
Bleeding disorders
Renal tumour
Papillary carcinoma
Ureteric tumour
Cystitis
Tuberculosis
Bladder stone
Endemic haematuria
Benign prostatic hyperplasia
Urethral injury
Bladder tumours
Carcinoma prostate
Urethral tumours

Fig. 26.24: Causes of haematuria.

Investigations

- Urine culture and sensitivity (urine test for haematuria—*Benzidine test).*
- Ultrasound to look for the stone, tumour in the urinary tract.
- Cystourethroscopy to look for bladder or urethral pathology.
- IVU look for function of the kidneys.

The value of experience is not in seeing much but in seeing wisely—William Osler

- Urinary cytology for diagnosing urothelial malignancy.
- Bleeding time; clotting time; prothrombin time; platelet count.
- CT abdomen.
- Renal function tests—blood urea, serum creatinine.

Management

- Cause should be identified and treated.
- Blood transfusion.
- Antibiotics.
- Nephro-ureterectomy for RCC; removal of stone from kidney, ureter, urinary bladder.
- Treatment of bladder tumour by cystoscopic resection; intravesical chemotherapy using BCG; radiotherapy; systemic chemotherapy.
- Treatment of medical causes like glomerulonephritis.
- Correction of BPH.
- Correction of bleeding diathesis.

HORSESHOE KIDNEY

- It is a developmental anomaly where there is failure of complete ascent of kidneys with the fusion of lower or upper poles. It is due to fusion of subdivisions of mesonephric duct, when the embryo is as early as 30-40 days old.
- This condition is common in males.
- Fusion of lower pole is common (rarely upper poles).
- Commonest site is in front of 4th lumbar vertebrae. The part in front of the vertebra is called as *isthmus*. It has blood supply which freely communicates one kidney to other. Isthmus usually lies in front of aorta.



Figs 26.25A and B: (A) Horseshoe kidney and (B) Plain X-ray KUB showing horseshoe kidney with renal stones.

Clinical Features

- Presents as a fixed, nonmobile, firm mass in the midline at the level of 4th lumbar vertebra which is resonant on percussion.
- It is more prone for infection, stone formation, hydronephrosis, tuberculosis.

Diagnosis

- IVU—Medialisation of lower calyces and curving of ureter like a ***'flower vase'*****.**



Fig. 26.26: IVU showing flower vase appearance of horseshoe kidney.

- U/S abdomen.
- Urine analysis, blood urea and serum creatinine are supportive investigations.
- CT abdomen.

Treatment

- Whatever the complication occurs in horseshoe kidney, it is treated accordingly.
- Per se separation of isthmus is not indicated, unless to approach aorta for aortic diseases.

CYSTIC DISEASES OF THE KIDNEY

Types

a. *Genetic*
   - Adult polycystic kidney disease (Autosomal dominant).
   - Infantile polycystic kidney disease (Autosomal recessive).

b. *Nongenetic*—Simple cyst, multicystic kidney, medullary sponge kidney.

c. *Acquired renal cystic disease* may develop in patient on long-term dialysis.

POLYCYSTIC KIDNEY DISEASE (PCKD)

- Adult PCKD is inherited as autosomal dominant disease.
- It is bilateral and presents in third decade. One side presents little earlier than other side.
- *Aassociations*
  - Polycystic diseases of liver (18%), pancreas and lungs.
  - Berry aneurysm in the circle of Willis.
- Cyst formation occurs at the junction of the distal tubule and the collecting duct.
- Grossly it contains multiple cysts with a clear or brownish fluid (due to haemorrhage).



Figs 26.27A and B: Polycystic kidney disease, picture and CT scan. It is bilateral, multiple.

Clinical features

- Bilateral palpable renal mass
- Loin pain
- Haematuria
- Infection
- Hypertension
- Uraemia

- Renal mass, which is lobular, firm, mobile, moves with respiration, ballotable, with dull renal angle and resonant band in front.
- Pain, which is due to stretch of renal capsule or haemorrhage into a cyst.
- Haematuria, (25%) due to overdistended cyst rupturing into the renal pelvis.
- Infection is due to stasis.
- Hypertension (75%).
- Uraemia occurs in late stage due to renal failure.

Differential diagnosis

- Renal cell carcinoma
- Hydronephrosis
- Solitary renal cyst

Investigations

- U/S confirms the presence of cysts.
- IVU—*Spider leg pattern* with an elongated compressed renal pelvis, narrowed and stretched calyces.
- Blood urea and serum creatinine.
- Urine shows low specific gravity.

Treatment

- Wait and watch policy.
- If one of the cysts overdistends causing pain, haemorrhage, infection, then surgical intervention is required.
- ***Rovsing operation***—The kidney is exposed. The cyst is opened. The fluid is evacuated. The cut edge is marsupialised.
- Presently U/S guided aspiration is done as a simpler approach.
- Laparoscopic / retro-peritoneoscopic aspiration / de-roofing of the renal cyst.
- Once renal failure sets in, then initial haemodialysis followed by bilateral nephrectomy, is done and later renal transplantation should be planned for.

SOLITARY RENAL CYST

- Solitary renal cyst is never congenital.
- It is due to an earlier trauma or infection resulting in blockage of tubule, leading to cyst formation.
- It is usually unilateral, presents as a renal mass which is smooth, often tender if infected or haemorrhagic.

Differential Diagnosis

- Renal neoplasm.
- Hydronephrosis.
- Polycystic disease.
- Hydatid cyst.

Always make a total effort even when the odds are against you.



Fig. 26.28: Solitary renal cyst. It is acquired, unilateral.

Investigation

- U/S and IVU confirms the diagnosis.
- CT scan.



Fig. 26.29: Left side renal cyst – CT picture. It could be solitary renal cyst. It can be aspirated or de-roofed by laparoscopy/retroperitoneoscopy.

Treatment

- Kidney is exposed. The cyst is aspirated and a portion of the cyst wall is removed ***(Kirwin's operation)*** and cavity is filled with perinephric fat.
- Occasionally if the cyst is in one of the pole, partial nephrectomy is done.
- Laparoscopic approach.

DUPLICATION OF RENAL PELVIS AND URETER

- It is most common congenital anomaly of the upper urinary tract (4%).
- Usually unilateral. Common on the left side.
- In 3% of cases it is associated with duplication of ureter.
- Upper renal pelvis is small, drains the upper calyces. Lower renal pelvis is larger, drains the middle and lower calyces.
- Double ureter when associated, may be *partial* where two ureters join in lower third or *complete* where upper ureter opens into the bladder at a lower level and lower ureter opens into the bladder at the upper, normal ureteric orifice. This is called as "*Weigert Meyer Law*".
- In partial duplex, there is reno-renal reflux resulting in infection, stone formation and hydronephrosis.

Investigations

- IVU—Diagnostic.
- U/S to look for complications.





Figs 26.30A and B: (A) Duplex renal system and (B) X-ray showing bilateral duplex system.



Fig. 26.31: IVU showing bilateral duplex kidney.

- Cystoscopy shows **double ureteric orifices** on the same side.
- DTPA scan to see the function.

Treatment

- Ureteric meatotomy is done if there is narrowing of the orifice.
- The co-existing complications are treated.
- Often heminephrectomy including removal of corresponding ureter may be essential as treatment.
- In females with complete duplication, lower ureteric orifice is ectopic, causing urinary incontinence which needs partial nephrectomy or ureteric reimplantation.

RETROCAVAL URETER (FIG. 26.33)

- It is due to developmental defect of IVC, as a result of which right ureter passes behind the IVC, causing right sided hydronephrosis with upper third hydroureter.
- IVU shows hydronephrosis with *'reverse J sign'*.
- *Treatment:* Anderson Hynes' operation.



Figs 26.32A and B: Retrocaval ureter – IVU picture showing reverse J sign. On table finding of retrocaval ureter. It is treated by Anderson's Hynes operation. It causes hydronephrosis. It is due to anomalous development of IVC.

URETEROCELE

- It is a *cystic enlargement of the intramural portion of ureter* due to congenital atresia of the ureteric orifice. Its wall contains mucous membrane only.
- It is common in females, often bilateral (10%).

Complications

- Stone formation
- Recurrent infection
- Hydronephrosis

> *Variability is the law of life, and so no two faces are the same, so no two bodies are alike, and no two individuals react alike and behave alike under the abnormal conditions which we know as disease.*
>
> —William Osler



Fig. 26.33: Retrocaval ureter. It is due to developmental problem of IVC.

Stephen classification:
Stenotic, sphincteric, sphincterostenotic.



Fig. 26.34: IVU reveals left sided ureterocele with duplex kidney. Note the characteristic Cobra (Adder) head pattern of left ureterocele.

Investigations

- IVU—Shows *Adder-head* appearance or *cobra head* appearance.
- Cystoscopy—Shows translucent cyst which is thin walled surrounding the ureteric orifice.

Treatment

- *Cystoscopic ureteric meatotomy* with the removal of cyst wall.



Fig. 26.35: U/S picture of ureterocele—Adder head appearance.

- In addition to that co-existing complications should be treated.
- Often ureteric reimplantation is needed.

INJURIES TO KIDNEY

- Commonly it is due to a blunt injury.
- Often it is associated with other abdominal injuries—of liver, spleen, bowel, mesentery, etc.
- *Per se renal injury is extraperitoneal*.



Fig. 26.36: Renal trauma causing extensive laceration. Patient underwent nephrectomy. (*Courtesy by Dr Ashfaque Mohammed DNB; KMC Mangalore*).

Types

1. Small subcapsular.
2. Large subcapsular.
3. Cortical laceration.
4. Laceration with perinephric haematoma.

5. Medullary laceration with bleeding into the renal pelvis.
6. Corticomedullary complete rupture.
7. Hilar injury (most dangerous).

Grading of renal injury

1 – Subcapsular non-expanding haematoma without parenchymal laceration
2 – Cortical laceration < 1 cm of parenchymal depth, no extravasation; perirenal haematoma
3 – Cortical laceration > 1 cm depth; no urine extravasation
4 – Parenchymal laceration extending through cortex and medulla with collecting system; with extravasation of urine
5 – Renal pedicle avulsion; shattered kidney

Clinical Features

- Features of *shock.*
- *Haematuria*—may be mild to profuse depending on the type of injury.
- *Clot colic*.
- Bruising, swelling and tenderness in the loin.
- Paralytic ileus with abdominal distension occurs due to retroperitoneal haematoma implicating splanchnic nerves.

Investigations

- ***IVU (high dose)***—It is the investigation of choice. Here function of not only the injured kidney but also of the contralateral kidney can be seen. It is observed that often opposite renal artery undergoes a reflex spasm, temporarily ceasing the function of the contralateral kidney.
- ***U/S abdomen***—Done to see the type of injury, amount of haematoma and other associated injuries in the abdomen. U/S is repeated at regular intervals to see the progress (at 12-24 hourly).
- Blood urea and serum creatinine should be repeated at regular intervals.
- Blood grouping and cross-matching for blood transfusion.
- Emergency CT scan is very useful.



Figs 26.37A to G: (A) Small subcapsular, (B) Large subcapsular, (C) Cortical laceration, (D) Laceration with perinephric haematoma, (E) Medullary laceration with bleeding into the renal pelvis, (F) Corticomedullary complete rupture, (G) Hilar injury (most dangerous).

Treatment

I. *Initially always conservative:*
   - Catheterise and watch the urine colour and output.
   - Blood transfusion.
   - Strict observation with regular monitoring of the pulse, BP, temperature, *U/S follow-up daily.*
   - Sedation, analgesic and antibiotics.
   - 75% of patients respond to conservative management.
   - While treating conservatively, regular monitoring of blood urea and serum creatinine is a must.
   - If the patient goes in for renal failure, haemodialysis should be done for 6-8 weeks. Meanwhile, other kidney starts functioning again and patient recovers without any further problem.

II. *Indications for surgical intervention:*
   - When there are signs of progressive blood loss with the condition of the patient deteriorating.

Difficulties are like mirror on the wall, that show a person what they are in reality.

- Formation of progressive perinephric haematoma.
- When there are associated other injuries.
- Hilar injury.

Surgery

Options:

- Gentle suturing of the laceration. Often kidney is friable, this is not possible.
- Then nephrostomy (Cabot's) is done.
- When the injury is in the poles partial nephrectomy is done.
- In *hilar injury and severe laceration, nephrectomy is the only choice*.

	Types	*Treatment*
I	Only bruise/contusion	Conservative
II	Breach in calyceal system rupture of one of the small branches of renal artery	Conservative/ nephrectomy
III	Rupture of pelvi-calyceal system/renal substance	Nephrectomy

Complications

- Clot retention in the bladder and may go for renal failure
- Pararenal pseudohydronephrosis
- Infection
- Perinephric abscess
- Aneurysm of the renal artery
- Renal failure
- Hypertension occurs 3 months later

RENAL TUBERCULOSIS

- Commonly it is *secondary*. Primary may be in the lung.
- Tuberculous bacilluria occurs with an early lesion in the renal cortex, and the disease spreads along the ureter causing tuberculous ureteritis and stricture ureter.
- Tuberculous kidney results in any of the following pathological types.

Pathological Types

Through blood, bacteria reach the glomeruli causing caseating granuloma with Langhan's type of giant cells and epithelioid cells. These granulomas coalesce to form a papillary ulcer and other consecutive different forms.

- *Tuberculous papillary ulcer.*
- *Cavernous form.*
- *Hydronephrosis.*



Figs 26.38A to C: Specimen of kidney showing dilatation and caseous material as content. It is tuberculous pyonephrosis. Ureter is visualised in the specimen. Often there may be ureteric stricture due to tuberculosis.

- *Pyonephrosis* [due to (secondary) superadded infection by *E. coli*, *Klebsiella*].
- *Tuberculous perinephric abscess*.
- *Calcified tuberculous area* (mimics calculi, hence called as pseudocalculi).
- *Caseous kidney*—often called as *putty kidney* or *cement kidney* (it goes for autonephrectomy).
- *Miliary tuberculosis*.
- Tuberculous bacilluria occurs from an early stage of the disease which causes tuberculous ureteritis and stricture ureter. Commonest site is *ureterovesical junction*; second common site is pelvi uretric junction.
  - Tuberculous cystitis eventually results in *golf hole ureter and thimble bladder* (cystoscopic findings). This is due to fibrosis causing rigid withdrawn dilated ureteric orifice looking like *golf hole*. Entire urinary bladder gets fibrosed, stiff and unable to dilate and accommodate urine causing *thimble systolic bladder*.
  - Tuberculous prostatitis, seminal vesiculitis (P/R—palpable seminal vesicle), tuberculous epididymitis and funiculitis are other associations. Thickened epididymis with ulcer on the posterior aspect of the scrotum may be often found. Tuberculous funiculitis with beaded, thickened vas deferens.



Fig. 26.39: Mode of spread in urinary tuberculosis.

Clinical Features

- Common in males.
- Common on right side.
- Frequency—Both day and night.
- Polyuria.
- ***Sterile pyuria***—Urine is pale and opalescent with presence of pus cells without organisms in an acid urine—*abacterial aciduria*. (Other causes: Interstitial cystitis, chlamydia).
- ***Painful micturition with often haematuria.*** Haematuria may be overt or microscopic (50%).
- Renal pain and suprapubic pain. Suprapubic pain is more common due to cystitis.
- ***Tuberculous kidney is rarely palpable*** unless there is hydronephrosis or perinephric abscess.
- Enlarged prostate and seminal vesicle, thickened beaded vas, thickened epididymis, impotence, infertility are other features.
- Presentation like acute pyelonephritis.
- Features of urinary stones; recurrent urinary tract infection; renal failure if both kidneys are diseased; hypertension.
- Haemospermia; pelvic pain.
- Dyspaerunia; menstrual dysfunction; vaginal discharge; infertility in females.
- Fever and weight loss.
- Often cough with expectoration and haemoptysis may be present.

Investigations

- ↓Hb%.
- ↑ESR. Mantoux skin test is usually positive.
- Chest X-ray.
- U/S abdomen.
- *Three consecutive early morning samples of urine* **(EMSU)** are collected and sent for microscopy, (Ziehl-Neelsen staining), culture (L-J media) or guinea pig inoculation.
- Plain X-ray KUB—shows calcification**.**
- CT scan of abdomen and pelvis to see hydronephrosis, shrunken kidney, stricture, necrosis.

Roots of education are bitter, but the fruit is sweet.



Fig. 26.40: Renal tuberculosis types.

- IVU—Hydrocalyx, narrowing of calyx, stricture ureter which are often multiple with dilatations in between.



Fig. 26.41: Stricture of left ureter lower part – IVU picture. Common cause is tuberculosis of ureter.

- Often RGP is very useful, as better definition of ureter, pelvis, calyces and selective sampling of urine are possible.
- Cystoscopy reveals multiple tubercles, bladder spasm, oedema of ureteric orifice eventually forming *"golf hole ureter"*, scarring, ulceration, bleeding, stone formation.
- Polymerase chain reaction (PCR) for tuberculosis. Radioisometric culture.
- Voiding cystourethrography (MCU) to see ureteric stricture and reflux.

Treatment

- Antitubercular therapy is started. INH, Rifampicin, Ethambutol and pyrazinamide. Duration of treatment is *one year*.
- After 6-12 weeks of drug therapy, surgical treatment is planned. Kidney is exposed. Pyocalyx is drained. Cut edge of the capsule is sutured—*Hanley's renal cavernostomy.*
- Hydronephrosis—*Anderson Hynes* operation or nephrostomy or stenting ("J" stent) of ureter is done.
- Renal tuberculous abscess not resolving for 2 weeks should be drained.
- Ureteral stricture—Stenting/reimplantation of the ureter into the bladder/psoas hitch/Boari's flap/ ileal conduit (*Koch's ileal conduit*).
- Thimble bladder—Hydraulic dilatation/ileocystoplasty/caecocystoplasty/sigmoid colocystoplasty is done.
- In unilateral lesion, with gross impairment of renal function– *nephro ureterectomy* is done.

Indications for nephroureterectomy

- Nonfunctioning kidney
- Disease extensively involving the kidney
- Disease causing hypertension and severe obstruction
- Tuberculous pyonephrosis
- Coexisting renal cell carcinoma

HYDRONEPHROSIS (HN)

It is an aseptic dilatation of pelvicalyceal system due to *partial* or *intermittent obstruction* to the outflow of urine.

Aetiology

It can be unilateral or bilateral.

Unilateral

A. *Extramural*:
   1. Aberrant renal vessels (vein or artery).
   2. Compression by growth (carcinoma cervix, carcinoma rectum).
   3. Retroperitoneal fibrosis.
   4. Retrocaval ureter.

B. *Intramural:*
   1. Congenital PUJ obstruction.
   2. Ureterocele.
   3. Neoplasm of ureter.
   4. Narrow ureteric orifice.
   5. Stricture ureter following removal of stone, pelvic surgeries or tuberculosis of ureter.

C. *Intraluminal:*
   1. Stone in the renal pelvis or ureter.
   2. Sloughed papilla in papillary necrosis.

Bilateral

A. *Congenital:*
- Congenital stricture of external urethral meatus, pin-hole meatus.
- Congenital posterior urethral valve.

B. *Acquired:*
- BPH.
- Carcinoma prostate.
- Postoperative bladder neck scarring.
- Inflammatory/traumatic urethral stricture.
- Phimosis.
- Carcinoma cervix.
- Bladder carcinoma.

- *Congenital PUJ is the commonest cause of HN***.**
- Often it is bilateral and presentation on one side is earlier than the other side.
- *Aberrant renal artery* or *vein* in the lower pole of kidney can compress the PUJ causing HN. Renal angiogram confirms the diagnosis.



Fig. 26.42: Aberrant renal vessels are one of the known causes of hydronephrosis.



Figs 26.43A and B: Aberrant renal vessels causing obstruction and hydronephrosis. As this often supplies lower pole of kidney exclusively, it need to be retained.

Treatment of aberrant renal vessels
- If it is a vein it can be ligated safely. But if it is an artery, it exclusively supplies the lower pole of the kidney and so cannot be ligated. So kidney is mobilised; upper and lower poles are approximated together so that artery is made to slip away from the site of compression—*Hamilton Stewart operation***.**
- In *pregnancy* dilatation of ureters and both pelvis occur due to atony of ureteric musculature by progesterone. It starts as early as in the first few weeks of pregnancy and lasts until few weeks after delivery. Involution occurs 2-12 weeks after delivery.

Classifications

Classification I
- Unilateral HN
- Bilateral HN without renal failure
- Bilateral HN with renal failure

Classification II
- Intermittent HN: Obstruction occurs, swelling and pain appear in the loin. After sometime patient passes large amount of urine following

In the case of perinephric abscess bending the trunk away from the side of the abscess may produce pain, whereas the patient can bend his body towards the lesion without much discomfort.—George S

which swelling and pain disappear—*Dietl's crisis*
- *Persistent HN*: It is due to persistent partial obstruction

Classification III
- HN only
- HN with hydroureter

Classification IV
- Extrarenal pelvic HN (80%)
- Intrarenal pelvic HN (20%). Destruction of kidney is earlier and severe here, as compared to extrarenal pelvic HN

Pathology

- Initially pressure burden is taken up by the pelvis; later calyces and renal parenchyma. Gradually, parenchyma thins out due to destruction and it dilates. Eventually leading to compromised secretory function. Parenchymal thickness of less than 2 mm is unlikely to function. In bilateral cases such patients will go for renal failure.


HN kidney
Dilated pelvis
Obstructed cong PUJ

Fig. 26.44: Hydronephrosis due to congenital PUJ obstruction. It is the common cause of hydronephrosis.

Clinical Features

A. *In unilateral cases:*
- Congenital PUJ obstruction and calculus are the most common causes.
- M : F : : 2 : 1.


Parenchyma
Calyces
Renal pelvis
A
Renal parenchyma
Dilated calyces
Renal pelvis (dilated)
PUJ
Ureter
B

Figs 26.45A and B: Specimens showing hydronephrosis.


Cup
Flat
Club
Broadened

Fig. 26.46: Stages of HN.



Figs 26.47A and B: Types of renal pelvis (A) Intrarenal and (B) Extrarenal.

- Right side kidney is affected more commonly.
- Dull aching loin pain with dragging sensation or heaviness.
- Mass in the loin which is smooth, mobile, ballotable, moves with respiration with dullness in renal angle and a band of colonic resonance in front.
- Attacks of acute renal colic.
- Often patient may be having ***Dietl's crisis***—After an acute attack of renal colic, swelling in the loin is seen which disappears after sometime following passage of large volume of urine.
- Dysuria, haematuria, if infected fever and tenderness in renal angle.
- Occasionally hypertension.

B. *In bilateral cases:*

- From lower urinary tract obstruction.
  - Loin pain
  - Features of bladder outlet obstruction—frequency, hesitancy, poor stream
  - Kidneys are often not palpable if renal failure develops early



Fig. 26.48: IVU showing bilateral hydronephrosis and hydroureter.

- From bilateral upper urinary tract obstruction.
  - Loin pain, mass in the loin, attacks of renal colic
  - In bilateral cases, when it is severe, features of renal failure like oliguria, oedema, hiccough may be present

Complications

1. Pyonephrosis.
2. Perinephric abscess.
3. Renal failure in bilateral cases.

Investigations

- Blood urea and serum creatinine.
- Urine for microscopy.
- U/S abdomen: Investigation of choice.



Fig. 26.49: Hydronephrosis as seen in CT scan.

Efficiency is, doing better what is already done.

Type of pelvis, thickness of parenchyma, site of obstruction and cause of obstruction, e.g. stones, can be made out (Refer Fig. 26.53).

- IVU: To find out the function of diseased as well as opposite kidney. Normal calyx is *cup* shaped. It gets *flattened* and later *club shaped* which eventually becomes *broadened* in hydronephrosis (Refer Fig. 26.46).
- ***Whitaker test*:** A fine needle is passed into the renal pelvis through loin. Pelvis is perfused with saline at a rate of 10 ml/minute. Normally, initially the pressure increases and later it will remain constant. Persistent increase in pressure suggests HN.
- CT scan is diagnostic.



Fig. 26.50: Retroperitoneal tumour causing ureteral obstruction with hydronephrosis.



Fig. 26.51: CT scan showing bilateral hydronephrosis. One side large (left side); another side early hydronephrosis.



Fig. 26.52: IVP showing right hydronephrosis. Note the dilated right renal pelvis and delay in the excretion of the dye from the affected kidney.

- *Isotope renography* is also useful to study the function of the kidney before and after the surgical treatment and also to see the efficacy of surgery as far as function is considered—DTPA scan.



Fig. 26.53: U/S picture of hydronephrosis showing dilated pelvis.

Treatment

- Always conservative surgeries which are aimed at conserving the kidneys are done. Nephrectomy is not done unless indicated.



Fig. 26.54: Isotope scan showing hydronephrosis on the left side.

1. The cause is treated—Stone, congenital anomaly, aberrant renal vessels, stricture urethra (dilatation, urethrotomy, urethroplasty); phimosis (circumcision); BPH (TURP); posterior urethral valve (cystoscopic fulguration of valve).
2. ***Anderson—Hyne's operation*** (Dismembered pyeloplasty):

   In congenital PUJ obstruction, the spasmodic segment and redundant pelvis are excised. A new pelvis is created and the cut end of pelvis is anastomosed to the ureter in the *dependent* position.
3. *Davis T-tube ureterostomy:* Placement of T tube in the ureter by making longitudinal incision.
4. Non-dismembered pyeloplasties: Here PUJ is not transected. Reconstruction is done without PUJ transection by different methods, e.g. **Foley's Y-V plasty.**



Fig. 26.55: Anderson-Hyne's operation.

5. In bilateral HN, without renal failure, *kidney which is functioning better should be operated first*. Three months later, otherside kidney is dealt with.
6. In bilateral HN with renal failure, *bilateral nephrostomy and haemodialysis* support is required initially. After 3-6 weeks IVU is done and the functions of both kidneys are looked for. If they function, then treated accordingly by Anderson Hyne's operation.

   If kidneys are still not functioning (renal function < 20% on isotope study) then nephrectomy and renal transplantation is the only option left.
7. *Laparoscopic* or *retroperitoneoscopic pyeloplasty* is becoming popular but is expensive and time consuming. It gives good result as well.
8. *Endoscopic pyelolysis*, even though technically easier results are not assured.

PYONEPHROSIS

It is collection of pus in pelvicalyceal system, which is converted into a multiloculated sac. Occurs due to—

a. Infection of preexisting hydronephrosis.
b. Following acute pyelonephritis.
c. As a complication of renal calculus—either stone in the renal pelvis or staghorn calculus.

Clinical Features

- Usually unilateral.

Triad:
- Anaemia
- Fever
- Loin swelling

- Tender mass in the loin which is smooth, soft, not mobile, not moving with respiration.
- Patient may also have cystitis, pyuria, burning micturition.
- Features of toxicity such as fever with chills and rigors.

Investigations

- Plain X-ray, KUB, may show renal calculus.
- IVU shows HN poor secretion.
- *Cystoscopy* reveals cystitis with *efflux of purulent pus* through the ureteric orifice.
- U/S shows dilatation.
- DTPA scan later.

Enthusiasm is the greatest asset in the world. It beats money, power and influence.

Treatment

- After starting antibiotics, pus is immediately drained from the kidney through a loin incision and *nephrostomy* tube (Cabot's nephrostomy) (Malecot's catheter) is placed.
- If kidney is totally destroyed, *subcapsular nephrectomy* is done. This also prevents other kidney from getting infected through perirenal lymphatic connections.
- In bilateral pyonephrosis, *bilateral nephrostomy* is the only choice. '*J*' *stenting* is done often to keep the ureters patent.

CARBUNCLE OF KIDNEY (RENAL CARBUNCLE)



Fig. 26.56: Cut section of specimen of kidney showing pus, necrotic area, and multiple infected abscesses – renal carbuncle with multiple abscesses. Condition is common in diabetics.

- A localised inflammatory necrotic mass of tissue involving renal parenchyma, caused by *Staphylococcus aureus* and coliform organisms, source of which is cutaneous infections like boil and carbuncle.
- It presents as ill-defined tender swelling in the loin, with pyrexia and leucocytosis.
- Staphylococci can be isolated from the urine.
- IVU shows obliteration of group of calyces, ***mimics renal cell carcinoma***.
- **Treatment**: Antibiotics, drainage of carbuncle, with placement of Malecot's catheter.
- Often, in severe type nephrectomy may be needed.
- Severe septicaemia may occur in renal carbuncle.

Renal abscess/renal carbuncle

- A localised inflammatory necrotic mass of tissue involving renal parenchyma, caused by *Staphylococcus aureus* and coliform organisms, source of which is cutaneous infections like boil and carbuncle. Eventually infection may spread to entire kidney causing multiple abscesses
- It presents as ill defined tender swelling in the loin, with pyrexia and leucocytosis
- Staphylococci can be isolated from the urine
- IVU shows obliteration of group of calyces, *mimics renal cell carcinoma*
- Treatment: Antibiotics, drainage of carbuncle with Malecot catheter placement
- Often, nephrectomy may be needed in severe type
- Life threatening septicaemia can occur which often needs not only nephrectomy but also higher antibiotics like mereponem, linezolid, and intensive critical care, ventilator support

PERINEPHRIC ABSCESS

Causes

- Infection of a perinephric haematoma.
- Perforation through renal capsule from pyonephrosis or renal carbuncle.
- Tuberculous perinephric abscess.
- Extension of cortical abscess.
- Haematogenous spread.
- Extension of appendicular abscess.
- Periureteral lymphatic spread.



Fig. 26.57: Perinephric abscess.

Clinical features

- High fever
- Fullness in the loin
- Tenderness and rigidity
- Scoliosis with concavity towards the side of abscess

Investigations

- Total count is increased.
- Plain X-ray KUB—Obliteration of psoas shadow, scoliosis, elevation of hemidiaphragm.
- IVU—Two films taken one in lying down position and another in erect posture.

  Normally in erect posture, downward displacement of the kidney is seen. Downward displacement is not seen in case of perinephric abscess—*Mathe's sign.*
- U/S abdomen.
- CT scan is diagnostic.

Treatment

1. Antibiotics are started.
2. Under G/A through loin approach (lumbar incision), pus is drained adequately. Pus is sent for culture and sensitivity. Collection in the cortex of the kidney should also be drained. A Malecot's catheter is kept in place.

RENAL CALCULUS

> ***The Times whereat you often in a day have the Urinary Excretion performed with Ease, are times which invite you very frequently to lift up your Hearts unto God with such an Acknowledgment as This; 'O, My most merciful God, I bless thee, that the grinding Torments of the Stone, are not now grinding of me'***
>
> **—Cotton Mather,** 1724

It is more common in males; 90% are radiopaque (gallstones are more common in females; 90% are radiolucent).

Aetiology

- *Diet:* Vitamin A deficiency—It causes desquamation of epithelium which acts as a nidus for stone formation.
- *Climate*: In hot climate urinary solutes will increase with decrease in colloids, which leads to chelation of solute with calcium forming a nidus for stone.
- *Citrate level* in urine (300-900 mg/24 hours) maintains the calcium phosphate and carbonate in soluble state and any decrease in citrate level in urine causes stone formation.
- *Infection* in kidney: Urea splitting organisms commonly cause stone formation, i.e. *E. coli*, *Staphylococcus, Streptococcus, Proteus.*
- *Prolonged immobilization* causes decalcification of bones and so hypercalciuria leading to stone formation.
- *Hyperparathyroidism* causes hypercalciuria causing multiple bilateral stones or often bilateral nephrocalcinosis.
- *Hyperoxaluria*, as a result of altered glycine metabolism.
- *Cystinuria* (Autosomal recessive).
- *Stasis* due to obstruction to urine flow.
- *Medullary sponge kidney*.
- *Randall's plaque theory* is erosion and deposition of urinary salts as Randall's plaque at the apex of renal papillae.
- *Carr's postulates* states that minute concretions called as microliths normally develop in the subendothelial part of the tubule which will be carried away as particles by renal lymphatic network vessels. If these lymphatics are blocked, microliths enlarge and act as nidus for stone formation.
- *Others:* Sarcoidosis, myelomatosis, gout, idiopathic hypercalciuria, hypervitaminosis D, neoplasms on treatment, hypomagnesuria (Mg^{++} in urine acts as a complexing agent and prevents nucleation normally).
- *Renal tubular acidosis*: Commonly causes calcium phosphate stone (10%).

Stages of stone formation

I. Supersaturation
II. Nucleus formation
III. Crystallisation
IV. Aggregation
V. Matrix formation
VI. Stone

Epitaxy: Growth of one type of stone on another type.

You may be disappointed if you fail, but you are doomed if you don't try.



Fig. 26.58: Plain X-ray KUB showing bilateral large renal stones and right ureteral stone.

Types

1. *Oxalate stones (75%):* Also called as *mulberry stone* as it is brown in colour, with sharp projections. It is invariably calcium oxalate stone, shows *envelope crystals in urine.*
2. *Phosphate stones (10-15%):* It is either calcium phosphate or calcium, magnesium, ammonium phosphate stone usually occurring in an infected urine. It is smooth and white in colour. In an alkaline urine it enlarges rapidly, filling renal calyces taking their shape called as *staghorn calculus*. It is radiopaque and attains a large size.
3. *Uric acid stones* are smooth, hard, yellowish, multiple and radioluscent. They are seen in gout, hyperuricosuria, altered purine metabolism.
4. *Urate stones.*
5. *Cystine stones* occur in *cystinuria* where there is defective absorption of cystine from the renal tubules (autosomal recessive condition).
   It is seen in young girls, occurs only in *acidic urine.* It is multiple, soft, yellow in colour and the colour changes to *greenish hue* on exposure. It attains large size. It is radiopaque because it contains sulphur.
6. *Xanthine stones* are very rare, smooth, brick red in colour, due to altered xanthine metabolism.
   Here there is deficiency in xanthine oxidase enzyme.
7. *Indigo stones*: Very rare. Blue in colour.
8. *Struvite stone*: It is compound of magnesium, ammoniumphosphate mixed with carbonate. It occurs in presence of ammonia and urea splitting organisms in urine, e.g. *Proteus; Klebsiella.*

Shapes of Stone Crystals in Urine

Type of crystal	*Shape of the crystal*
a. Calcium oxalate monohydrate	Dumbell shaped
b. Calcium oxalate dihydrate	Envelope shaped
c. Uric acid	Yellowish of varying size and shape
d. Cystine	Hexagonal, very soft stones
e. Triple stone	Coffin lid shaped

Clinical Features

- Pain—Renal pain is located over renal angle, hypochondrium and lumbar region. Often severe radiating to groin and testis in male, with vomiting due to pylorospasm. Pain worsens on movements.
- Haematuria is common.
- Pyuria.
- Fever.
- Tenderness in renal angle, with often a mass in the loin due to hydronephrosis which moves with respiration and is bimanually palpable, ballotable, smooth, soft.
- As urinary tract infection.
- Incidental finding.
- Often hypertension.

Note: Food rich in oxalates are, spinach, tea, cola, alcohol, citrus fruits.

Investigations

- Blood: ESR, serum calcium, phosphate, creatinine, blood urea, uric acid, PTH level.
- Urine: Calcium, urate, cystine if suspected only, pH, specific gravity.
- Plain X-ray, KUB: To see kidney shadow, stones (90%—*radiopaque*).



Fig. 26.59: Plain X-ray, KUB, showing multiple stones in the right kidney.

- IVU to see renal functions and HN.
- RGP if required.
- U/S abdomen—can detect even radioluscent stones and gives information about the changes in renal parenchyma.
- Urine analysis and C/S to identify bacteria.

Treatment

1. ***PCNL (Percutaneous Nephrolithotomy).***

Indications:
1. Stones more than 2.5 cm in size
2. Multiple stones
3. Stones not responding for ESWL

Procedure: Under the guidance of C-ARM or U/S, needle puncture is made in the loin percutaneously. Through kidney, calyx and pelvis are approached. Guidewire is passed. Graduated dilators are passed and so track is widened. Then through that, a nephroscope is passed. After fragmentation, stone is removed using different methods [Laser (Holmium), pneumatic, ultrasonic or electro hydraulic].



Fig. 26.60: Plain X-ray KUB showing phosphate stone in the kidney and oxalate stone in urinary bladder.



Figs 26.61A to C: Stages in PCNL.

Complications of PCNL

- Haemorrhage
- Perforation of collecting duct
- Injury of collecting duct

2. ***ESWL (Extracorporeal Shock Wave Lithotripsy):***



Fig. 26.62: ESWL table and machine used for renal stones. It needs C-ARM to guide the exact point of stone to be fragmented.

- *Piezo-Ceramic* or *Electromagnetic* shock waves are passed to the stone through water bath or water cushion which acts as a media. Shocks are produced at 2/sec. 1000-4000 shocks are required for each stone.
- *Dornier Lithotripter* is used for fragmenting stones.
- Stone is located and observed through fluoroscope (C-ARM) or ultrasound. Shock waves are triggered to create *compressive waves* over the stone, to *fragment* it. These fragments are flushed out later.

Faith is like electricity, you can't see it, but you can see the light.

Advantages:
- No anaesthesia is required
- Can be done as an OP procedure
- Less than 2.5 cm sized stones are well fragmented
- Hard stones, oxalate stones are better eliminated by ESWL
- ESWL can be done repeatedly in different sittings
- If it is not successful one can switch over to PCNL

Complications:
- Renal haematoma
- Severe haematuria
- Injury to adjacent structures
- Fragmented stone retains in the ureter

Contraindications:
- Pregnancy
- Bleeding disorders
- Patients with abdominal aneurysms
- Sepsis and renal failure (Serum creatinine more than 3 mg%)

3. ***Conservative treatment:***
   - Flush therapy—Mainly *used for lower ureteric stones.*
   - IV Fluids.
   - Inj. frusemide 60-80 mg IV.
   - Anti-inflammatory and antispasmodic agents are given to relieve the pain.
4. ***Surgery for renal stones*:** Presently most of the renal stones can be removed without open surgery (PCNL, ESWL, URS). But limiting factors are cost and availability.

Surgeries

1. *Pyelolithotomy.*
   – Suitable for stones in extrarenal pelvis.



Fig. 26.63: Plain X-ray showing right-sided renal stone with 'J' stent on left side.

   – By loin (posterior subcostal) incision, kidney is approached.
   – Renal pelvis is opened, the stone is removed and the pelvis is closed. A drain is placed and wound is closed.
2. *Extended Pyelolithotomy (Gil—Vernet)*: In case of intrarenal pelvis, incision is done on the hilum between the pelvis and kidney over the renal sinus, dissection is carried out so as to remove the stones from pelvis as well as calyces.
3. *Nephrolithotomy*: By placing incision just behind the most convex surface (Brodel's line), stone is removed.
4. *Nephropyelolithotomy*: By making incisions both over the kidney and pelvis, stone/stones are removed. It is often done in *staghorn calculus.*



Figs 26.64A to F: Surgeries for renal stones. (A) Pyelolithotomy, (B) Extended pyelolithotomy, (C) Nephropyelolithotomy, (D) Nephrolithotomy, (E) Partial nephrectomy, (F) Coagulum pyelolithotomy.

5. *Partial nephrectomy:* Done when there are multiple stones occupying a pole, usually lower pole of the kidney or when there is damage to the calyx, if not removed may encourage further stone formation.
6. *Bench surgery:* Kidney is removed out temporarily, cooled by ice packs or inosine or liquid nitrogen. Stones are searched and removed completely. Later kidney is replaced in right iliac fossa.
7. *Coagulum pyelolithotomy*: Coagulum solution which contains fibrinogen is poured into the renal pelvis. It is activated so that it solidifies, meanwhile entangling the stones in renal pelvis. This entangled mass is removed en masse.
8. *Anatrophic pyelolithotomy*: After exposing the kidney, it is cooled with ice packs for 20 minutes and posterior branch of the renal artery is clamped temporarily using bull-dog clamp. The most avascular plane

behind the Brodel's line is thus visualised properly. Kidney is opened through this line and stone/stones are removed (anatrophic means "to prevent atrophy").

URETERIC CALCULI

- Always of renal origin.
- Nature of stones are same as that of renal stones.
- They are commonly of elongated shape.
- They can get impacted at various narrow junctions.



Fig. 26.65: Sites of ureteric narrowing.

Sites

- PUJ.
- Where ureter crosses the iliac vessels.
- Where ureter crosses vas deferens/broad ligament.
- Where ureter penetrates outer layer of bladder muscle.
- In the intramural portion of ureter near the ureteric orifice.

Stones less than 5-8 mm size may pass spontaneously.

Problems with ureteric stones

- Obstruction
- Hydronephrosis
- Infection
- Impaction
- Ureteral stricture

Clinical features

1. *Pain*—It is of colicky type and radiates from loin to groin often to the tip of the genitalia, testis in males, labia majora in female (referred along the genitofemoral nerve).

   It is severe in intensity, increases with exercise. It mimics *appendicitis, cholecystitis, ovarian* or *tubal pathology*.
2. Nausea, vomiting, sweating due to pain and reflex pylorospasm.
3. Haematuria, dysuria, frequency, strangury.
4. Tenderness in iliac fossa and renal angle (no rebound tenderness).

Investigations

- Urine-microscopy, C/S.
- Plain X-ray, KUB—Radiopaque stones are visible in 90% of cases—in the line of ureter (near the tips of transverse processes of lumbar vertebrae, sacroiliac joint and medial to ischial spine).

  Lateral or oblique films are required to differentiate from other opacities which mimic stone.



Fig. 26.66: A plain X-ray, KUB, showing left ureteric calculi.

- IVU shows hydronephrosis and hydroureter. Function may be accurately assessed by isotope renogram.
- Blood urea, serum creatinine, serum calcium, uric acid level.
- U/S is useful.
- CT scan is diagnostic.

Differential diagnosis

- Appendicitis
- Cholecystitis
- Ovarian cyst
- Tubo-ovarian disease
- Mesenteric adenitis
- Ruptured ectopic gestation

Treatment

1. Plenty of water orally.
2. Diuretic—Oral frusemide to flush the stone.
3. Suitable antibiotics to control sepsis; antispasmodics to relieve pain.

Fire proves gold, adversity proves men.

4. IV fluids—Fast infusion of about 1.5 to 2 litres and injection frusemide 60 to 80 mg. Usually given for 3 to 5 days.
5. Surgical intervention for ureteric stones:

Indications:
- Size of the stone more than 5 to 8 mm
- IVU showing deterioration of function
- Co-existing infection
- If stone is impacted in the ureter with persistent symptoms

Procedures

Upper Third Stone:
- ESWL for stone in upper third ureter.
- The stone is pushed into the renal pelvis and then PCNL is done.
- URS—*Uretero-Renoscopic Stone removal*—
  - Through ureteroscope, stone is visualized and often fragmented using pneumatic bombarder. It is then extracted by ureteroscope.
  - Complications are perforation of ureter and extraperitoneal leakage of urine, bleeding.



Fig. 26.67: 'J` stent right side – used after URS (uretero renoscopy) in ureteric stone extraction.

- Open *ureterolithotomy* through loin incision.

Stone in middle third ureter:
- URS.
- Open ureterolithotomy.

Stone in lower third ureter:
- URS.
- *Dormia Basketing*:


Ureter
Stone
Basket
Opened basket with stone

Fig. 26.68: Dormia basket is used to remove the stone in the lower ureter. Single stone less than 1 cm can be removed.

Indications for Dormia basketing
- Stone in lower third ureter.
- Stone below pelvic brim.
- Stone less than 10 mm size.
- Single stone.

Basket is passed into the proximal ureter beyond the stone and opened. The stone is then pulled out.

Complications of Dormia Basket
- Stone dislodgement
- Urethral injury
- Avulsion of ureter
- Stricture ureter

- Open ureterolithotomy.
- Using cystoscope under general anaesthesia, *ureteric meatotomy* is done for stones impacted at the ureteric


Upper third
Flush
ESWL
PCNL
URS
Open ureterolithotomy
Middle third
Flush
URS
Open ureterolithotomy
Lower third
Flush
URS
Dormia-basket
Ureteric meatotomy
Open ureterolithotomy

Fig. 26.69: Approaches for removal of ureteric stones.

orifice. It is released by cutting the orifice at upper and lateral aspects.

Note: All ureteric stones can be removed through laparoscopy or retroperitoneoscopy.

PREVENTION OF RECURRENCE OF STONES

Types of recurrence:

a. False recurrence—During intervention, tiny fragments may be left behind.
b. True recurrence—Recurred again once all stones are cleared by intervention.

Causes for recurrence:

Existing causes like hyperparathyroidism, hypercalciuria, hyperuricaemia, gout, cystinuria.

Advice

- Hydration is the main method of prevention. Per day 3 to 4 litres of fluid should be taken.
- Diet:
  - Avoid diets rich in calcium, oxalate, sodium (natriuresis causes hypercalciuria) and vit. C (gets converted into oxalate).
  - Increased intake of dietary fibre—Binds with intestinal calcium and decreases the calcium absorption. *Sodium cellulose phosphate is used* for the same.
- *Allopurinol* reduces the uric acid level and so uric acid stone. It also reduces the oxalate level.
- Diet rich in *magnesium* makes calcium oxalate less soluble.
- *Aluminium gel* or *ammonium chloride* prevents the excessive alkalinity and so prevents the recurrence of phosphate stones.
- *Penicillamine* or *alpha mercapto propinyl glycine* may reduce the recurrence rate of cystine stones.
- In idiopathic hypercalciuria, strict low calcium diet along with 5 mg bendrofluzide which reduces loss of calcium in urine or indomethacin 25 mg tds which reduces the calcium secretion or sodium phytate can be given.
- Acetohydroximic acid due to structural similarity to urea is a potent inhibitor of urease and so reduces the bacterial originated stone.

STAGHORN CALCULUS

- It is the stone occupying the renal pelvis and calyces.
- It is usually phosphate or ammonium, magnesium phosphate (*Triple phosphate*) stone.
- It is white in colour, soft, smooth, occurs in pre-existing infection (commonly *E. coli*).
- It can be *unilateral* or *bilateral*. Patient with *bilateral* stones may go in for *renal failure.*



Fig. 26.70: Staghorn calculus.



Fig. 26.71: Staghorn calculus.

Presentation

- Pain in loin
- Fever
- Burning micturition
- Haematuria
- In bilateral cases, symptoms are bilateral and often with features of renal failure (hiccough, oedema feet, oliguria, anaemia)



Fig. 26.72: Bilateral staghorn calculi.

Imagination is the highest kite one can fly.

Investigations

- U/S, abdomen.
- Plain X-ray, KUB.
- IVU to see the renal function.
- Blood urea and serum creatinine.
- Urine microscopy and urine C/S.
- Isotope renogram–DTPA.



Fig. 26.73: A plain X-ray, KUB, revealing staghorn calculus on right side.

Treatment

Antibiotic is started.

1. *Unilateral stone* is removed by *nephropyelolithotomy*. Multiple incisions are made over the Brodel's line (avascular plane) and assisted by pelvic incision. Stone is removed. Blood transfusion may be necessary as bleeding can occur.

   After that, nephrotomy and pyelotomy incisions are sutured with chromic catgut or vicryl.
2. In *bilateral cases* IVU is very essential. The kidney which is functioning better should be treated first. After 3 months, the other side kidney should be operated upon.
3. If there are *bilateral staghorn calculi with pyonephrosis*, then initially bilateral nephrostomy is done using Malecot's catheter (*Cabot's nephrostomy*). IVU is done later to see the renal function. If function is present, then both kidneys are operated one after the other in a gap of 3 months. They often need *haemodialysis.*
4. Sometimes in case of severe infection *nephrectomy* is required.

Presently, PCNL is becoming a popular procedure for unilateral or bilateral staghorn calculi.

But when required, *conversion to open nephropyelolithotomy* should be considered.



Fig. 26.74: Nephropyelolithotomy. Note the incisions placed.

Complications of staghorn calculus

- Pyelonephritis
- Pyonephrosis
- Perinephric abscess
- Renal failure

DIFFERENTIAL DIAGNOSIS FOR RADIOPAQUE SHADOW WHICH MIMICS RENAL STONE

- Calcified lumbar or mesenteric lymph node
- Gallstone (10% are radio-opaque)
- Concretion in appendix
- Phleboliths
- Ossified tip of 12th rib
- Chip fracture of transverse process of vertebra
- Calcified renal tuberculosis
- Calcified suprarenal gland
- Drugs or foreign body in the alimentary canal

WILM'S TUMOUR (NEPHROBLASTOMA)

> ***The patient was a 3-year old girl with a kidney tumour which had grown to immense proportions in a short time. The child, anemic and emaciated, was admitted with an enormous mass in the right abdomen and with definite ascites. After nephrectomy, the little child recovered uneventfully. A few months later, however, a recurring abdominal mass was again palpable and shortly afterward the child died.***
>
> **—Max Wilms,** 1899

- It arises from embryonic connective tissue containing epithelial and connective tissue elements.
- It is located in one of the poles of the kidney.
- It is bilateral in 5% cases. It is common in first 4 years of life.

Pathology

Gross

It is smooth, soft, fleshy, pinkish white in colour, often with haemorrhagic areas.

Microscopically

Malignant primitive glomeruli and primitive tubules, with epithelial and connective tissue cells exist side by side, one of the types is usually prominent.

Types

A. *Favourable histology—FH—Wilms'—means without anaplastic features*
B. *Unfavourable histology—Un FH—Wilms'—means with anaplastic features*

Histological types

- Cystic nephroma.
- Mesoblastic nephroma.
- Nephroblastoma.

Spread

Mainly through blood into the lungs, liver and rarely to bones.



Fig. 26.75: X-ray showing mass lesion in right abdomen. It could be Wilm's tumour.

Clinical features

- Incidence is equal in both sexes.



Fig. 26.76: Renal tumour.

Triad

Mass, fever, haematuria

- *Mass abdomen is commonest presentation*. Mass is smooth, mobile, firm or hard, lobular, located in the loin, moves with respiration, bimanually palpable, ballotable, with dullness in renal angle and with resonant band in front. It does not cross the midline. (Differential diagnosis is adrenal neuroblastoma which is knobby and nodular, does not move with respiration and crosses the midline).
- *Fever*—May be due to tumour necrosis.
- *Haematuria* is a grave sign as it signifies rupture of tumour into the renal pelvis.
- *Hypertension*—In 25% cases.
- 12% of cases are associated with congenital anomalies and syndromes (Glaucoma, Aniridia, Beckwith syndrome).

Staging of Wilm's

I. Disease confined to kidney and completely resectable
II. Tumour extends beyond kidney, but can be excised completely
III. Residual disease after resection with positive lymph nodes and massive spillage
IV. Blood born metastasis
V. Bilateral disease

Investigations

- U/S abdomen, CT scan abdomen.
- IVU.
- Renal angiography.
- X-ray, abdomen—*egg shell* peripheral calcification is diagnostic.
- MRI.

The men who make history have no time to write it.

Differential diagnosis

- Adrenal tumour
- Retroperitoneal tumour
- Renal cyst
- Polycystic kidney disease

Treatment

- *Nephrectomy and postoperative radiotherapy in case of unilateral tumours.*
- In bilateral cases, either bilateral partial nephrectomy or nephrectomy on one side with partial nephrectomy on the other side is done (*Nephron sparing surgery*).



Fig. 26.77: Partial nephrectomy.

- *Chemotherapy:* Actinomycin D, vincristine, doxorubicin.
- Preoperative RT in locally inoperable cases – later surgery and then chemotherapy is given.

Prognosis

Five years survival rate is 80% under the age of one year. Recurrence rate is high within one year.

Prognostic factors

Age, bilaterality, size of the tumour, presence of haematuria, spread of tumour, histology type.

RENAL CELL CARCINOMA (RCC)

Also known as *Hypernephroma—(it is a misnomer), Grawitz tumour, clear cell carcinoma, Internist tumour.*

- It is an adenocarcinoma arising from renal tubular cells, most common site is proximal renal tubule. More common in males; more common in 5th-6th decade of life.
- It is 3% of all adult malignancies.

Aetiology

- It is associated with von Hippel-Lindau disease (cerebellar haemangioblastoma, retinal angiomatosis, tumour or cysts of pancreas). Here RCC is commonly bilateral
- Diet high in animal fat
- Environmental factors like asbestos, lead, cadmium and tobacco
- Cigarette smoking
- Chromosomal aberration, tuberous sclerosis
- Acquired cystic kidney disease after long-term dialysis
- *Birt-Hogg-Dube' syndrome* with hereditary chromophobe RCC and oncocytoma
- Cortical renal adenoma could be RCC by itself
- Analgesic nephropathy

Pathology



Fig. 26.78A



Fig. 26.78B



Fig. 26.78C

Figs 26.78A to C: Renal cell carcinoma in upper pole of kidney–resected specimen. It is from two different patients.

Gross

It attains a large size. Commonly located in *upper pole*, sometimes in lower pole but rare in the middle. Cut section is *yellowish* due to lipoid content with areas of haemorrhage and necrosis. This noncapsulated tumour is very vascular.

Microscopy

Malignant cells which are cubical or polyhedral containing lipid, cholesterol and glycogen.

Histological types—Clear (75%), granular, spindle, sarcomatoid, papillary (15%)

Spread

1. *Local*: Into the perinephric pad of fat, calyces and renal pelvis.
2. *Blood spread*: RCC enters the renal vein as *proliferating tumour thrombus*, which extends into the IVC and later gets detached causing "*cannon ball secondaries*" in the lung, which are often calcified. Once primary tumour is removed, secondaries may regress due to tumour immunity. Occasionally, secondaries occur in bone, liver and brain. Left testicular vein which drains into left renal vein may gets blocked by proliferating tumour thrombus resulting in *irreducible left sided varicocele.*
3. *Lymphatic spread*: To hilar lymph nodes, para-aortic lymph nodes.

AJCC (American Joint Committee on Cancer) Staging: TNM Staging

Tx: Primary tumour cannot be assessed
T0: No primary tumour
T1: Tumour less than 7.0 cm size, limited to kidney
T1a is tumour 4 cm or less; T1b is tumour 4-7 cm in size
T2: Tumour more than 7.0 cm size, limited to kidney
T3: Tumour extends into major veins, adrenals, perinephric fat but not into the Gerota's fascia
  T3a : Into adrenal or perinephric tissue
  T3b : Into renal vein or IVC below diaphragm
  T3c : Tumour extends into IVC above the diaphragm
T4: Tumour invades Gerota's fascia and extends beyond

N0: No lymph nodes
N1: Spread to single regional lymph nodes
N2: Spread to more than one regional lymph nodes

M0: No blood spread
M1: Distant spread to – lungs (75%); soft tissues (25%); bones (20%); liver (15%); CNS (8%); skin (8%)

Robson-Flocks and Kadesky Staging

Stage 1	Tumour confined to renal parenchyma
Stage 2	Tumour invasion to perinephric fat but confined within Gerota's fascia
Stage 3	a. Tumour invasion to renal vein or IVC b. Invasion to regional lymph nodes c. Both a + b
Stage 4	Invasion to adjacent organs other than adrenal Distant metastasis

Note: 45% present as early disease; 25% as locally advanced disease; 30% as metastatic disease.

Clinical Features

- M : F :: 2 : 1.
- Haematuria – 30%.
- Clot colic.
- Dragging discomfort in the loin.
- Mass in the loin which moves with respiration, mobile, nodular, hard, with dull renal angle and resonant band in front.
- Left-sided *varicocele* which is *irreducible* in left-sided RCC.

A drop of INK may make a million THINK.

Triad of RCC

1. Pain
2. Haematuria
3. Palpable renal mass

Atypical presentations: 25%

- Due to secondaries:
  1. Pathological fractures.
  2. Persistent cough and haemoptysis.
- *Persistent pyrexia* with no evidence of infection (***P***yrexia of ***U***nknown ***O***rigin) – 20%
- *Constitutional symptoms:* Malaise, lethargy and severe anaemia.
- *Polycythemia:* 4% – due to increased secretion of erythropoietin.
- Hypercalcaemia, hypertension. Hypercalcaemia due to PTH like hormone secretion, hypertension is due to increased secretion of renin from kidney tissue adjacent to tumour.

Surgical renal conditions associated with hypertension

- Polycystic kidney disease
- Renal cell carcinoma
- Renal artery stenosis

- *Nephrotic syndrome:* Very rare.
- *Stauffer's syndrome:* Non-metastatic reversible liver dysfunction which gets corrected after nephrectomy. It is 7% common. It carries poor prognosis.
- Cushing's syndrome.
- Leukaemoid reaction due to bone marrow stimulation.
- Secondary amyloidosis 5%.

Investigations

- Urine microscopy for RBCs.
- IVU—shows mass lesion and irregular filling defect.
- U/S, abdomen—to know the size, extension, lymph node involvement, spread to the liver, status of renal vein and IVC.
- CT scan: It is confirmatory and also helps to know the status of renal vein and IVC. Multi-detector CT and CECT (contrast enhancement CT) are very useful in detecting early lesion / function / spread / venous status. Lymph node status, tumour extension are well made out with CT. Contrast enhancement CT scan helps to find out function of opposite kidney and tumour thrombus in renal nein or IVC.



Figs 26.79A and B: CT scan showing features of renal cell carcinoma.

- Renal angiogram through Seldinger technique via transfemoral route, to see the vascularity. *Pharmacoangiogram* (Inject noradrenaline along with dye while doing angiogram). As tumour vessels are autonomous they will not constrict whereas adjacent normal vessels will constrict, so *tumour blush* is visualised. Through angiogram therapeutic embolisation of tumour can be done to reduce the vascularity of tumour.
- Chest X-ray shows *cannon ball* secondaries. Often it is *calcified.*
- *CT chest is ideal and more reliable.*
- Bone scan to see bone secondaries.
- Peripheral smear, serum calcium, haematocrit and ESR.

- MRI is diagnostic to assess the tumour thrombus in IVC. MRI/MR angiogram is unique in identifying the spread in to IVC especially in the thorax. In such occasion oesophageal endosonography is also useful to visualise thoracic extension of the tumour thrombus.

Differential diagnosis

- Polycystic kidney disease
- Solitary cyst of kidney
- Adrenal tumour
- Retroperitoneal tumour
- Carcinoma colon



Fig. 26.80: CT scan of carcinoma right kidney.

Treatment

Surgery is the treatment of choice.

- *Radical nephrectomy*:

Structures removed are—

- Entire kidney along with tumour
- Perinephric tissue
- Ipsilateral adrenal gland
- Proximal 2/3rd ureter/as low as possible
- Lymph nodes from crus of diaphragm to aorta bifurcation with renal hilar nodes

  - Transperitoneal approach is often used. Retroperitoneal/Nagamatsu (resection of 11th ribs) approach/thoraco abdominal approach/posterior vertical are other approaches used. Patient will be in lateral position. After laparotomy, colon is mobilised medially. Vessels are identified and dissected and ligated securely (transfixation and three ligatures proximally using nonabsorbable silk / polypropylene sutures).
  - Preoperative renal artery embolisation can be done to decrease vascularity and to facilitate the removal of entire tumour.
  - Always renal vein is ligated early so as to prevent tumour dislodgement. (But early ligation of renal vein may cause congestion and torrential bleeding). In case of IVC extension, after applying an oblique vascular clamp, IVC is opened, tumour thrombus is removed and IVC is sutured. In supradiaphragmatic venacaval extension of thrombus, cardio-pulmonary bypass is necessary. First renal vessels (artery and vein) should be ligated to prevent tumour dissemination and bleeding.



Fig. 26.81: Renal cell carcinoma, on table after nephrectomy. Note the vascular pedicels.

- Even in large fixed tumour, palliative nephrectomy or debulking is advised as it may cause regression of secondaries.
- *Nephron sparing surgeries* is done in bilateral RCC (Bilateral partial nephrectomy). Renal artery is temporarily occluded using vascular clamps and kidney is cooled to have proper control of bleeding and adequate visualisation of the line of resection. Partially resected specimen is assessed by frozen section biopsy. Retained partial capsule is sutured after haemostasis. Renal arterial clamp is released.
- *No role for radiotherapy*.
- *Chemotherapy:* Vinblastine and progesterone can be tried. RCC is a remarkably refractory solid tumour.

Be a good listener, your ears will never get you in trouble.

- Interferons and interleukins have shown beneficial effects.
- Preoperative renal artery embolisation can be done to decrease the vascularity of the tumour (Using clot, gelfoam, spheres).
- Antiangiogenic drugs like endostatin and angiostatin are under trial. RCC is highly vascular and there is highly angiogenic environment to give possible benefit by anti-angiogenesis.
- Patient with solitary lung metastasis may get benefited by wide resection of the secondary.
- Humanised monoclonal antibodies like bevacizumab which neutralises VEFG are under trial.

Note: Laparoscopic approach is becoming popular. Here renal artery is ligated first.

Prognosis

- Five year survival rate is 40%.
- In early localised disease, it is 70-90%. In advanced and metastatic disease it is 10-15%
- 5 year survival is 65% for stage I and II; 40% for stage III; 10% for stage IV

Prognostic factors are

- Tumour size more than 4 cm carries poor prognosis
- Extension into the renal vein
- Presence of secondaries
- Differentiation
- Local extension
- Hypercalcaemia and Stauffer's syndrome carry poor prognosis

Note:

- Commonest type of renal pelvis and ureteric tumours is transitional cell carcinoma (90%).
- Renal pelvic tumours account for 5% of renal tumours. It is common in Taiwan.
- It is more aggressive.
- Treatment is radical nephro-ureterectomy with removal of cuff of bladder adjacent to ureteric orifice.

APPROACHES TO KIDNEY (SURGICAL)

- Posterior subcostal (oblique lumbar incision).
- Laparotomy approach (anterior approach).
- Thoraco abdominal approach.
- Nagamatsu approach (approach following excision of 11th rib in case of upper pole tumour).
- Posterior vertical lumbotomy approach (Gilvernet's approach).
- Laparoscopic approach.
- Retroperitoneoscopic approach.



Fig. 26.82: On table position to approach kidney surgically.

Self-assessment Questions

- Enumerate causes of haematuria.
- What is microscopic haematuria.
- Discuss Hydronephrosis with – definition, causes, presentations and management.
- Whitaker test.
- Renal stones' causes, clinical features, investigations and treatment.
- Staghorn calculus.
- Ureteric stones.
- ESWL.
- PCNL.
- Prevention of recurrence of renal stones.
- IVU.
- Renal mass-differential diagnosis.
- Polycystic kidney.
- Ureterocele.
- Horseshoe kidney.
- PUJ obstruction.
- Dormia basket.
- Stone in the lower third of ureter.
- Renal cell carcinoma.
- Pharmacoangiogram.
- Hypernephroma.
- Wilm's tumour.
- Rovsing's operation.
- Retroperitoneal fibrosis.
- Renal tuberculosis.
- Retrograde pyelogram.
- Malecot's catheter.
- Injuries to the kidney.
- Foley's catheter.
- Perinephric abscess.
- Pyonephrosis.
- Autonephrectomy.
- Renal trasnsplantation.

Urinary Bladder

Anatomy
Ectopia vesicae
Urachal anomalies
Vesical calculus
Cystitis
Recurrent cystitis
Interstitial cystitis
Schistosoma haematobium
Thimble or systolic bladder
Bladder tumours
Uretero sigmoidostomy
Rupture bladder
Malakoplakia
Neurogenic bladder
Vesico-ureteric reflux
Bladder diverticula
Urinary diversion
Urinary fistulas

ANATOMY

- It is a muscular reservoir of urine situated in the pelvis, posterior to the pubic bone from which it is separated by the retro-pubic space.
- The size, shape, position of bladder depends on the amount of urine it contains.
- In females, the peritoneum is reflected from the superior surface of the bladder onto the anterior wall of the uterus close to the junction of the body of the uterus and cervix.
- In males, the peritoneum is reflected from the superior surface of the bladder over the superior surface of the ductus deference and seminal vesicles.
- The neck of the bladder is the most fixed part, lies 3-4 cm behind the pubic symphysis. In males it lies on the prostate and in females it rests on the anterior vaginal wall which is also supported by the levator ani-muscle.

Structure of the Bladder

- The bladder wall consists of interlacing fibres of smooth muscle. The urothelium consists of transitional epithelium which is loosely attached and easily separated from the bladder wall except over the *trigone*.
- *Trigone* is a triangular area over the lower part of the base of the bladder. The ureters opens into the postero-lateral angles of the trigone. The internal urethral orifice opens at the inferior angle of trigone.

Sphincters

- *Internal sphincter*—Smooth muscle, situated at the neck of the bladder, micturition follows its relaxation. It is innervated by autonomic nervous system.
- *External sphincter*—It consists of striated muscle, innervated by the perineal branch of pudendal nerve (S_2,S_3).

Blood Supply

- Superior vesical artery, a branch of internal iliac artery.
- Inferior vesical artery.
  - – Venous drainage is by the vesical plexus of veins, which drains into the internal iliac veins. These veins connect directly to veins of hip bones, the



Fig. 26.83: Anatomy of urinary bladder—posterior aspect.



Fig. 26.84: Urinary bladder—Inner anatomy.

Retrograde cystogram is the most reliable investigation in case of bladder rupture.

heads of femoral and vertebral bodies. This accounts for the site of occurrence of bony metastasis in carcinoma of the bladder and prostate.

Lymphatic Drainage

Lymphatics drain into internal iliac and external iliac nodes.

ECTOPIA VESICAE (Extrophy of the bladder)

- It is incomplete development of the infraumbilical part of the anterior abdominal wall and anterior wall of the bladder. It is of embryological origin.
- It is often associated with the spina bifida and other congenital anomalies.
- It is more common in males (4 : 1).
- Red mucus membrane of posterior bladder wall protrudes out with visible urine efflux from ureteric orifice.
- Umbilicus is absent.
- There is separation of pubic bones.
- In males, *epispadias* is commonly present with rudimentary prostate and seminal vesicle.
- Testes are normal.
- Bilateral inguinal hernias are common.
- In females defective external genitalia is common.



Fig. 26.85: Child showing extrophy bladder.

Problems

- Repeated soakage
- Ulceration
- Pain
- Recurrent pyelonephritis
- Renal failure
- Metaplastic changes in mucosa can lead into *adenocarcinoma*
- 50% of patients die of renal failure

Treatment

- Staged procedure.
- Initial diversion of urine to colon/rectum.
- Iliac osteotomy and closure of the abdominal wall.
- Correction of epispadias.
- Sometimes cystectomy and permanent uretero-sigmoid diversion is required.
- Condition has got high mortality due to infection and renal failure.

URACHAL ANOMALIES

- *Patent urachus with urine leak*: It signifies obstruction distal to bladder.
- *Urachal sinus with discharge.*
- *Urachal cyst*—Present as immobile, fluctuant swelling in the abdominal wall.

Sepsis, tuberculosis, adenocarcinoma, can occur in patent urachus.

VESICAL CALCULUS

> ***The signs of a stone in the bladder are, great and frequent irritations to make water, a stoppage in the middle of making it, and a pain with heat just after it is made; a tenesmus, pain in the extremity of the urethra, incontinence or suppression of urine, together with a quiet pulse, and the health in no bad state.***
>
> **—William Heberden,** 1802



Fig. 26.86: Ectopia vesicae in a man of 25 years old.

Types



Fig. 26.87: Bladder stones – oxalate and phosphate. Phosphate stone has occurred in an indwelling J ureteric stent.

- ***Primary vesical calculus*:** Occurs in sterile urine.
  - Usually comes down from kidney through ureter into the bladder and it gets enlarged here. It is usually *oxalate* stone (Jack stone).
  - Oxalate stone is usually single, primary stone, brownish black in colour (due to deposited blood pigment over the surface), hard and with spikes over the surface which irritates bladder mucosa causing haematuria *(mullberry stone).*
- ***Secondary vesical calculus***: Occurs in the presence of infection. Commonest bladder stone.
  - It is usually *phosphate stone*, occurs in bladder only.
  - Phosphate stone is smooth, soft, ivory-white in colour. It is either calcium phosphate or ammonium, calcium and magnesium phosphate *(Triple phosphate stone).*
  - *E coli* is the common organism.
- ***Uric acid and urate stones*** are single or multiple, primary, nonradiopaque, smooth, pale yellow in colour.
- ***Cystine calculus**:* Occurs in cystinuria and is radiopaque due to high sulphur content.

Aetiology

- Infection
- Hypercalciuria of any cause
- Hyperoxaluria
- Cystinuria
- Bed ridden and paraplegic patients
- Gout and other hyperuricaemic patients
- Diverticula bladder
- Obstruction to urine flow by BPH, urethral stricture, bladder neck obstruction
- Neurogenic bladder
- Schistosomiasis
- Foreign body in bladder

Fig. 26.88: Large bladder stone removed by open suprapubic extraperitoneal cystolithotomy.



Fig. 26.89: Plain X-ray KUB showing large bladder stone.

Clinical Features

- Common in males. Often occurs in children.
- *Frequency* is more during day than night, because during day, due to ambulation stone comes in contact

It is better to have an idea than to have thousand opinion.

with the trigone of the bladder and irritates, whereas during night, stone slips towards the fundus, away from the trigone and so less frequency and pain.
- *Pain*: More during day which is referred to the tip of penis or labia. Also increases during jolting movements. Suprapubic pain and tenderness may be present.
- *Haematuria*: Often terminal.
- Interruption of urinary stream and often acute urinary retention.
- Features of cystitis: Burning micturition, fever, pain.
- P/R or P/V: Large stone may be palpable.
- Stone may be identified incidentally in plain X-ray, KUB or U/S, abdomen.



Fig. 26.90: Plain X-ray showing dermoid cyst of ovary with calcification. It is teratoma of ovary.

Investigations

- Urine microscopy
  - Envelope crystals in oxalate stone,
  - Hexagonal type in cystine stone.
- Urine C/S.
- Blood urea, serum creatinine, serum calcium, inorganic phosphate, uric acid.
- Plain X-ray, KUB shows radio-opaque stones—90% are radio-opaque.



Figs 26.91A and B: A plain X-ray, pelvis showing (A) Phosphate stone. Note the laminations. (B) Oxalate stone. Note the spiculated margins.

Radiological D/Ds for vesical calculi in females—
- Calcified fibroid uterus
- Dermoid cyst ovary



Fig. 26.92: Plain X-ray revealing multiple bladder calculi.



Fig. 26.93: Dermoid cyst ovary. Note the radiopaque teeth.

- IVU to see function of the kidney.
- U/S abdomen is diagnostic.
- Cystoscopy to see radioluscent stone.



Figs 26.94A and B: X-ray showing vesical calculus. Note the laminated appearance.

Treatment

1. **Cystoscopic litholapaxy**
   Under GA, cystoscope is passed and the stone is visualized. It is fragmented by pneumatic, laser, electromagnetic waves or mechano-hydraulic lithotripsy. The bladder is flushed using an irrigator (Freyer's evacuator or irrigator or Ellik's evacuator).

Contraindications

- Too large stone
- Too small stone. Too soft stone. Too many stones
- Stone in bladder diverticula
- Bladder tumour
- Contracted bladder
- Patient's age below 10 years
- When patients general condition is poor, as the procedure takes a longer duration it is avoided and open removal is advised

2. **Suprapubic open cystolithotomy**
   Through pfannenstiel incision, bladder is approached extra-peritoneally. Bladder is identified by its detrusor muscle pattern, which is criss-cross and also its venous pattern. Bladder is opened near the fundus and stone is removed. Bladder is closed often with SPC using Malecot's catheter and Foley's catheter is passed per urethera. Wound is closed in layers with a drain.
3. **Suprapubic percutaneous litholapaxy**
   This procedure is becoming popular. When cystoscope can not be passed per urethra, bladder is approached suprapubically. Through a needle, guidewire and dilators, a track is created through which a nephroscope is passed to remove the stone after fragmenting.

   The cause is treated.



Fig. 26.95: Asepto syringe used for bladder wash in patients with urinary catheter which has been blocked; or when haematuria is noticed in the catheter. It is also used to fill the bladder with saline.

CYSTITIS

Inflammation of the bladder mucosa due to different causes.

Causes

- Acute bacterial cystitis
- Chronic cystitis due to tuberculosis, syphilis
- Interstitial cystitis
- Radiation cystitis
- Cystitis due to schistosomiasis
- Post menopausal atrophic cystitis

Predisposing Factors

Congenital Urinary Anomalies

- Short urethra in females may cause ascending infection and cystitis.
- Initial period of sexual contact in females can cause cystitis—Honeymoon cystitis.
- Catheters, instrumentation.
- Bladder stone.
- BPH, carcinoma prostate.

Men take only their needs into consideration, never their abilities.

- Cystocele, bladder diverticulum.
- Stricture urethra, bladder neck obstruction.
- Bladder tumours.
- Pregnancy.
- CNS diseases, spinal injury.

Organisms

- *E.coli, Klebsiella, Pseudomonas, Staph aureus, Staph albus, Proteus.*
- *Candida albicans*, fungal infection.

Features

- Painful urination, frequency, strangury, incomplete emptying, with often retention.
- Occasionally haematuria can occur.
- Burning urine, discolored foul smelling urine.
- Fever, chills, rigors, suprapubic pain and tenderness and often loin pain.
- Septicaemia can develop in severe cystitis.

Investigations

- Total count will be raised.
- Urine will show pus cells and culture will reveal the organisms.
- X-ray may show a stone. IVU, cystogram are also helpful.
- U/S abdomen will show thickening of bladder mucosa, stone, tumour.
- Cystoscopy reveals bladder inflammation, mucosal changes.

Treatment

- Appropriate antibiotics like quinolones, aminoglycosides, cephalosporins.
- Plenty of water intake to flush the bacteria from the bladder.
- Often admission and parenteral antibiotics may be needed.
- Evaluation and therapy for cause should be done.
- Strict aseptic precaution is used while catheterization, cystoscopy.
- Often long term antibiotics are needed to prevent recurrent infection.

RECURRENT CYSTITIS

Causes

- Failure of early treatment for acute cystitis
- Reinfection by same or different organisms.

Types

- Chronic cystitis
- Phosphate deposition in the ulcerated mucosa causing encrusted cystitis
- Proliferation of mucosa and submucosa causing proliferative cystitis. It may be cystitis follicularis, cystitis polyposa, cystitis glandularis, cystitis cystica
- Gas filed cysts in the submucosa causing cystitis emphysematosa
- Necrosis of bladder wall can occur leading to gangrenous cystitis.

Management

- Urine microscopy and culture.
- Antibiotic and urinary antiseptics like hippuric acid, mandelic acid.
- Proper hygiene.
- Plenty of oral fluid intake and frequent emptying of the urine.

INTERSTITIAL CYSTITIS (Hunner's ulcer, Elusive ulcer)

- It is common in females
- Common in western countries
- Common in psychic females

Pathology

There is pancystitis with fibrosis of the vesical musculature along with linear ulcers in the bladder mucosa. Microscopically, severe inflammation of all layers of bladder with fibrosis is observed. Bladder eventually becomes **thimble (systolic) bladder** with decreased bladder capacity up to 30-60 ml (less than 100 ml).

Clinical Features

- Pain.
- Decreased bladder capacity.
- Pain increases with bladder distension.
- Frequency and often haematuria.

Investigation

Cystography and cystoscopy are diagnostic.

Treatment

- Hydrostatic dilatation.
- Instillation of dimethyl sulphoxide (Rimso 50).
- Ranitidine instillation.
- Ileo-cystoplasty or caecocystoplasty, to increase the bladder capacity.
- Urinary diversion.

Differential Diagnosis

Other causes for thimble bladder.

SCHISTOSOMA HAEMATOBIUM (Endemic haematuria, Urinary bilharziasis) (Swimmer's itch)

Life Cycle

Fresh water snail—(Intermediate host)
↓
Bifid tailed embryos (cercariae) in infected water
↓
Penetrate the skin
↓
Through circulation enters the liver
↓
Male and female worms formed
↓
Sexual fusion and maturity occurs
↓
Flows through the portal vein in retrograde direction along the inferior mesenteric vein
↓
Vesical venous plexus
↓
Bladder wall and submucosa
↓
Ova are released
↓
Enters the bladder through the mucosa
↓
Ova are released into the urine and to water
↓
Ciliated miracidium
↓
Fresh water snail
↓
Death of snail releases thousands of cercariae.

Pathology in the Bladder

- Bilharzial pseudotubercles—earliest sign.
- Nodules.
- Sandy patches—calcified dead ova with degeneration of overlying epithelium.
- Granulomas.
- Ulceration and papilloma.
- Fibrosis and thimble bladder formation.
- In due course of time, development of *squamous cell carcinoma*.
- Other pathologies: Ureteral and urethral stricture, recurrent UTI, bladder calculi, urinary fistula.

Clinical Features

- Initially cutaneous lesions like utricaria develops lasting for few days.
- Then after a period of 4-8 weeks, fever, along with features of eosinophilia develops.
- Eventually, after many months it causes intermittent, painless, *terminal haematuria*.

Investigations

- Cystoscopy and biopsy.
- IVU.
- Cystography.
- Urine microscopy: Last few ml. of early morning urine sample is collected to see for ova and RBCs.

Differential diagnosis

- Tuberculosis
- Recurrent cystitis
- Malignancy

Treatment

- Long term *Praziquantel* or metrifonate.
- Surgery for thimble bladder—ileo or caecocystoplasty.
- Cystoscopic diathermy fulgaration of papillomas.
- Radical cystectomy, if it is squamous cell carcinoma of the bladder.

THIMBLE OR SYSTOLIC BLADDER

It is inability of the bladder to relax and distend and so inability to retain the urine as required.

Causes

- Tuberculous cystitis
- Schistosoma haematobium
- Interstitial cystitis
- Radiotherapy
- Malignancy
- Previous bladder surgery

- Bladder is fibrotic and contracted, with difficulty in dilating and accommodating urine as needed.
- Bladder capacity is less than 100 ml (60 ml).

Clinical features

1. Decreased bladder capacity
2. Frequency
3. Features of recurrent cystitis

Time won't stand with us; we have to stand with time.

Investigations

- Cystoscopy.
- Cystography.
- IVU.
- Urine C/S.
- Specific diagnostic tests.

Treatment

- The cause is treated.
- Hydrostatic dilatation.
- Augmentation of bladder by doing ileocystoplasty or *caeco cystoplasty* or *sigmoidocystoplasty*.
- Steroids are also tried.

BLADDER TUMOURS

They are urothelial tumors. They are commonly malignant. Benign tumors are rare. Transitional cell carcinoma (TCC) is the commonest.

1. Primary

a. ***Epithelial***
  - *Transitional cell carcinoma* (90%).
  - *Adenocarcinoma*, arising from urachal remnant or in exstrophy bladder or from glandular metaplasia (2%).
  - *Squamous cell carcinoma* originates from bilharzial infection (5%) or calculus.

b. ***Connective tissue tumour:***
  - Myoma, angioma, fibromas, sarcomas.
  - Extra-adrenal phaeochromocytoma.

2. Secondary

From adjacent organs like sigmoid colon, rectum, uterus, ovary, prostate.

TRANSITIONAL CELL CARCINOMA (TCC)

It is the commonest type of bladder tumour.

Aetiology

3C's
- Chemical carcinogens.
- Cigarette smoking.
- Cyclophosphamide.

- Chemical carcinogens are the main factor. 2-Naphthylamine, aminobiphenyl, benzidine, chloro-O-toluidine, chloro-aniline, other dyes.
- Occupation wise it is common in textile, dye, cable, tyre, petrol, leather workers, painters, chemical workers, sewage workers.
- Abnormal tryptophan metabolism can cause bladder cancer.
- Schistosoma haematobium; chronic irritation etc.

Classification I

1. ***Nonmuscle invasive tumour without involving lamina propria*:** Has got excellent prognosis (70%).
2. ***Nonmuscle invasive tumour with involvement of lamina propria.***
3. ***Muscle invasive type*** (25%): Carries poor prognosis.
4. ***Carcinoma in situ*** (*flat noninvasive–5%*):
   - Contains irregularly arranged cells with large nuclei, with high mitotic index, replacing normal urothelium.
   - This may occur alone—*Primary carcinoma in situ*.
   - It may occur in association with a new tumour—*Concomitant carcinoma in situ.*
   - It can occur in a patient who had a previous tumour—*Secondary carcinoma in situ.*
   - It has got high malignant potential with 50% mortality rate.
   - It was called earlier as 'malignant cystitis' as it causes severe dysuria, suprapubic pain and frequency (terminology not used presently).

Classification II

a. ***Superficial bladder tumour***:
  - It may be *papillary*, pedunculated with narrow stalk, which is often multiple.
  - It may be *sessile* with a wide base, can be single or multiple, and has got tendency to invade the muscle earlier.
  - Mucosa in and around the tumour is oedematous, red, with dilated vessels, often with encrustations. It is 70% common. Less than 5% of superficial TCC develop metastatic carcinoma.

b. ***Muscle invasive TCC***:
  - Almost always they are solid, sessile, with a broad base and with irregular ulcerated surface.



Fig. 26.96: Staging of bladder tumour.

  - It may spread through lymphatics to pelvic lymph nodes or through blood to the lung, liver and bones.
  - It has got poor prognosis.

c. ***Carcinoma in situ:***
  - Bladder tumor can be papillary or villous type. It can be low grade or high grade.

Sites

- *Lateral wall—Most common (35%).*
- Trigone—Next common (32%).

Staging (Refer Fig. 26.96)

Jewett – Strong – Marshall staging

I Tumour confined to subepithelial connective tissue
II Muscle infiltration superficially
III Full thickness muscle and perivesical tissue infiltrated, but mobile
IV Fixed to adjacent organs
  IVa (prostate)
  IVb (pelvic wall)

Staging is done by bimanual palpation under G/A.

TNM staging (AJCC)

Tis – Carcinoma *in situ*
Ta – Noninvasive papillary tumour
T1 – Invading only lamina propria
T2 – Tumor invades muscularis propria
  - p T2a – Invading the inner half of the muscle
  - p T2b – Invading the outer half of the muscle
T3 – Invading the perivesical tissues
  - p T3a – Microscopic invasion
  - p T3b – Macroscopic invasion
T4 – Invasion into prostate/uterus/vagina/pelvic wall/abdominal wall
  - T4a – Into prostate/uterus/vagina
  - T4b- Into pelvic/abdominal wall

N0 – No nodes
N1 – Single regional nodal spread upto 2 cm in size
N2 – Spread to single node 2 - 5 cm in size or multiple nodes less than 5 cm

M0 – No distant spread
M1 – Distant spread present

Clinical Features

- Painless haematuria anaemia.
- Features of cystitis, with suprapubic pain, frequency, dysuria.
- Hydronephrosis can occur when tumour obstructs the ureteric orifice.
- Pain in groin, back, perineum, when tumour invades the pelvic wall.
- Common in males – 3:1.

Investigations

- Urine microscopy: For RBC's and malignant cells.
- Blood: Hb%, blood urea, serum creatinine.
- IVU: Shows filling defect with distortion and often hydronephrosis.
- *Cystoscopy* and biopsy/resection.
- *Bimanual examination under G/A*—To stage the tumour.
- U/S abdomen to see bladder wall, pelvis, liver, lymph nodes.
- CT scan to evaluate the extension.
- MRI to see invasion and pelvic wall status.



Figs 26.97A to C: CT scan picture showing irregularity in bladder mucosa – carcinoma urinary bladder.

Many receive advice, only wise profit from it.



Fig. 26.98: Bimanual palpation is done for bladder tumour under general anaesthesia to evaluate the tumour.



Fig. 26.99: Carcinoma urinary bladder—U/S picture.

Treatment

a. ***Noninvasive tumour***:
- *Endoscopic resection* of tumour.
- *Intravesical chemotherapy* using BCG (Dose: 120 mg in 150 ml of normal saline weekly for six weeks), mitomycin C, epirubacin, adriamycin, thiotepa, methotrexate can be given especially for carcinoma *in situ*.
  - BCG is very useful. Very rarely BCG provocation can occur. Fever, joint pain, granulomatous prostatitis, sinus formation, disseminated tuberculosis are the features. Dysuria, frequency and urinary irritation can occur. Mitomycin C causes skin desquamation and rash.
- *Systemic chemotherapy*: Using cisplatin, 5 FU, adriamycin, mitomycin.
- *Helmstein balloon degeneration* for large papillary tumour. Balloon is passed into the bladder and inflated so as to cause pressure necrosis of the summit of the tumour. Later remaining part of the tumour can be resected easily through cystoscopy.

b. ***Invasive bladder tumour***:
- *Curative interstitial radiotherapy* using implantation of radioactive gold grains (Au 198) (half life is two and half days), or radioactive tantalum wires (Ta 182) (half life is 4 months).
- *Radical deep external beam radiotherapy* (45 Gy) using cobalt 60 is useful, as bladder is retained and so normal act of micturition and potency can be maintained. Complication is that it may eventually lead to formation of thimble bladder.
- ***Surgery***:

Indications for surgery
- Multiple bladder tumours
- Sessile tumours
- Recurrent tumours
- Poorly differentiated tumours
- In situ carcinomas
- Squamous cell carcinoma
- Adenocarcinomas

  - *Partial cystectomy* done when tumour is confined to fundus of the bladder and is single, with a margin of clearance of 2.5 cm. External beam RT and chemotherapy should be given.
  - *Radical cystectomy*: CT scan is a must before doing radical cystectomy to see the pelvis and lymph node status. Here urinary bladder, urethra, paravesical tissues, lymph nodes (pelvic) are removed. In females hysterectomy with removal of part of the vagina is done. After surgery urinary diversion is done either by doing continent ileal conduit, or ureterosigmoidostomy or by creating rectal urinary pouch.
- *Intravesical chemotherapy* by BCG, mitomycin C, adriamycin and interferons.
- *Systemic chemotherapy* by cisplatin, adriamycin, mitomycin, vinblastin - adjuvant therapy. Neoadjuvant cisplatin based chemotherapy is beneficial improving survival by 7%. MVAC regime is Methotrexate; Vinblastin; Adriamycin and Cisplatin.

Prognosis

- Depends on type, differentiation, location, stage, invasion, number, lymph node status, pelvis involvement and response to treatment.
- TCC alone – 85%; TCC with SCC or adenocarcinoma – 6%; SCC/adenocarcinoma alone – 3%; spindle cell carcinoma – 2%.

URETEROSIGMOIDOSTOMY

- It is a procedure done for urinary diversion after radical cystectomy or as a permanent diversion for many other causes, e.g. bladder dystrophy.
- *Left ureter is implanted to the sigmoid colon, right one to the upper rectum or rectosigmoid junction.*

Complications

- Because the pressure in sigmoid colon is more, it causes *pyelonephritis* and recurrent upper urinary tract infection.
- Because of diarrhoea it causes *hypokalaemia.*
- Because of reabsorption of chloride**,** *hyperchloraemic acidosis* occurs.

Treatment

- IV sodium bicarbonate (8.4%) with slow IV potassium.



Fig. 26.100: Ureterosigmoidostomy.

- IV antibiotics.
- Patient is advised to take potassium citrate and sodium bicarbonate and to **avoid salt.**
- In many cases conversion to *ileal conduit* may be required.

RUPTURE BLADDER (BLADDER INJURY)

Causes

- Blow, kick or fall
- Road traffic accidents
- Stabs, gunshot injuries
- Endoscopic trauma
- Diathermy
- Instrumentations



Fig. 26.101: Rupture urinary bladder causing extravasation and lower abdominal swelling. It needed surgical intervention, repair of bladder; suprapubic cystostomy.

Types

I. *Intraperitoneal rupture*—20% common.
Occurs in fully distended bladder due to blow, kick, or fall.

II. *Extraperitoneal rupture*—80% common.
Due to road traffic accidents, golf playing, fall over the manhole.
Its features and management are same as rupture of posterior (membranous) urethra.



Figs 26.102A and B: (A) Intraperitoneal rupture. (B) Extraperitoneal rupture.

Conduct has the loudest tongue.

I. *Intraperitoneal Rupture*

- It is 20% common.
- It occurs in full bladder.

Clinical Features

- Sudden pain in suprapubic region.
- Shock and syncope.
- Diffuse abdominal pain.
- Urine leaks into the abdominal cavity causing distension of abdomen.
- Later it causes features of peritonitis, with guarding, rigidity, tenderness and rebound tenderness, dull flank.
- *Patient does not have the desire to micturate.*

Investigations

- Plain X-ray shows ground glass appearance.
- Peritoneal tap is done to confirm urine.
- Cystogram: After passing a small catheter gently per urethra, water soluble iodine dye is passed to visualize the tear in the bladder and entry of the dye into the free peritoneal cavity. This can be done now through C-ARM image intensifier easily.
- U/S abdomen to look for other injuries in the abdomen.
- CT scan abdomen.

Treatment

- *Surgery is the only treatment for intraperitoneal rupture of the bladder*. Emergency laparotomy is done.
- Bladder tear is sutured in two layers using **vicryl**. Peritoneal wash is given.
- Malecot's catheter is placed from above as SPC.
- Prevesical space and peritoneal cavity are drained separately.
- Foley's catheter from below is also passed.
- Adequate specific antibiotics are given to prevent sepsis.

Complications of rupture bladder

- Cystitis and pyelonephritis
- Peritonitis
- Pelvic abscess
- Fistula formation (vesico vaginal or recto vesical)
- Paralytic ileus
- Haemorrhage

Without surgery mortality is 100%

II. *Extraperitoneal Rupture of the Bladder*

- It is 80% common.
- Occurs in road traffic accidents, in a non-distended bladder.

Clinical Features

- There is collection of urine and blood in the extraperitoneal space in front, with fullness, diffuse pain and tenderness in lower abdomen.
- Swelling in the scrotum or labia, and abdominal wall.
- Strangury and inability to pass urine.
- Often blood in the external meatus is noted.
- Features of shock and of other associated injuries may be noted.

Investigations

- Plain X-ray pelvis shows fracture pelvis.
- Cystogram shows leak from the bladder.

During cystoscopy

- Bladder can not be distended
- Endoscopy light may be shining through the abdominal wall
- Irrigating fluid cannot be retrieved back Associated urethral injury is looked for

Treatment

- The bladder is exposed extraperitoneally, the tear is identified and sutured. The extraperitoneal space is irrigated with saline. Bladder is closed with a SPC using Malecot's catheter and a drain is placed in prevesical space (cave of Retzius).
- If there is urethral injury it should be treated accordingly.

Note:

- **Bladder injury can also occur** during hystrectomy, (both abdominal and vaginal), surgery of colon or rectum, repair of direct inguinal or femoral hernias.

RESIDUAL URINE

- It is the amount of urine retained in the bladder after voiding (at the end of completion of the act of micturition).
- Normal value is 30 ml.
- Amount more than 50 ml is significant. It signifies obstruction in the urethra like BPH.
- Residual urine more than 200 ml in BPH indicates the need for surgical intervention.
- High residual urine is also seen in different types of neurogenic bladder.
- Residual urine precipitates infection because of stasis.

Residual urine is assessed by the following methods:

- The patient is asked to pass urine and then a red rubber catheter is passed to empty the retained urine which is measured to quantify.
- U/S for evaluation of the bladder after voiding urine.
- Intravenous urogram (IVU)—Post micturition film.

MALAKOPLAKIA

- It is usually associated with chronic cystitis of unknown aetiology causing greyish raised patches in the bladder mucosa.
- Microscopically it shows infiltration of submucosa with lymphocytes, plasma cells and large multinucleated malakoplakia giant cells with concretions, called as ***Michaelis Gutmann bodies*** present both inside the giant cell as well as outside.
- It does not turn into malignancy.
- It presents as cystitis.
- Management is urine analysis; culture; antibiotics; urinary antiseptics like pyridium; cystoscopic evaluation and biopsy to rule out other causes.

NEUROGENIC BLADDER

It is the altered bladder function due to defects anywhere in the pathway of micturition reflex.

Causes

Spinal cord trauma
Disc prolapse
Spina bifida
Spinal cord root lesions
Tabes dorsalis
Diabetes mellitus
Cerebral diseases
Poliomyelitis

Types

Uninhibited Neurogenic Bladder

- It occurs in CNS diseases due to block in the corticospinal tract.
- There is increased frequency, urgency and incontinence.
- There is early desire to micturate with inability to hold urine.
- Bladder capacity is decreased.
- Awareness of filling and distension, and voiding pressure is normal.
- No residual urine.

Reflex Neurogenic Bladder (Automatic bladder)

- Lesion here is above the level of micturition centre S_2, S_3 and S_4.
- There is no desire to micturate.
- No awareness of filling or distension.
- Bladder capacity is normal or increased.
- Voiding pressure varies.
- Residual urine present.
- Infection is common.

Autonomous Bladder

- Here micturition centre is destroyed (S_2, S_3, S_4). Both sensory and motor parts are destroyed.
- There is no awareness of filling.
- Bladder is incapable of contraction and so bladder capacity is increased.
- No voiding pressure.
- High residual urine and infection.
- Stress incontinence is present.
- Patient empties the urine by manual pressure.

Sensory Paralytic Bladder

- Here sensation from the bladder to micturition centre is selectively affected.
- It is common in tabes dorsalis and pernicious anaemia.
- There is complete loss of awareness of filling.
- Varying voiding pressure.
- Increased bladder capacity and residual urine.
- Infection is common.

Motor Paralytic Bladder

- It is due to selective destruction of motor pathway from the micturition centre to the bladder.
- It is seen commonly in polio, tumours, trauma.
- There is normal awareness of filling and painful distension.
- Voiding pressure is zero. It is atonic bladder.
- There is residual urine with normal bladder capacity.

Investigations

- Spine X-ray.
- Micturating cystogram.
- Urodynamic studies.
- U/S abdomen to find out residual urine.
- Urine culture and microscopy.

Treatment

- The cause is treated.
- Condom drainage.
- Intermittent catheterization.
- Drugs like carbachol, distigmine can be given.
- Alpha adrenergic agents.
- Physiotherapy and pelvic exercises.
- Electrical stimulation of perineal muscles.
- Treating the stress incontinence surgically.
- Antibiotics whenever there is infection.

Aging is "immobility, incontinence, instability and intellectual deterioration.

VESICOURETERIC REFLUX

- Normal flow of urine is always from ureter to bladder through ureteric orifice. It is called as efflux.
- If urine enters the ureter from the bladder through ureteric orifice, it is called as reflux. It is always *pathological*.



Fig. 26.103: Micturating cystourethrogram (MCU) showing gross vesicoureteric reflux on both sides.

Causes

- *Congenital:* It is commonly associated with posterior urethral valve.
- *Acquired:* Trauma, after surgery or intervention.
  - Reflux has got **5 grades** depending on the amount of reflux (for grades refer back—MCU).
  - Reflux can be unilateral or bilateral.

Clinical Features

- Features of recurrent urinary tract infection.
- Renal failure in bilateral cases.
- Palpable kidney mass in the loin.

Investigations

- Urine microscopy and C/S.
- Blood urea and serum creatinine.
- IVU.
- Micturating cystourethrogram (MCU).

Treatment

- Tailoring of the ureter with ureteric re-implantation.
- Antibiotics.
- In severe cases nephrectomy, renal transplantation are required.

BLADDER DIVERTICULA

Normal intravesical pressure is 30-50 cm of water. Pressure reaches as high as 150 cm of water in obstruction. This causes hypertrophy of bladder mucosa → saccule formation → diverticulum.

Diverticula can be –

- *Acquired* – common
  - Pulsion diverticulum occurs due to increased intravesical pressure
  - Traction diverticula occurs due to traction into a hernial sac in the groin – often as a sliding hernia
- *Congenital* – due to remnant urachus in midline



Figs 26.104A and B: Diverticula bladder. In acquired type only mucosal protrusion is seen in paraureteric orifice region. In congenital type it is full thickness protrusion, commonly over the dome of the bladder.

1. *Congenital diverticula:*
    - It occurs over the dome of the bladder.
    - It is due to unobliterated end of the urachus.
    - As it contains muscle in the wall and it contracts during micturition.
    - Rare type.
2. *Acquired diverticula*:



Fig. 26.105: X ray showing bladder diverticula. It can be pulsion or traction diverticula. It can be congenital or acquired. Acquired occurs in paraureteric region. Congenital occurs in midline over the dome of the urinary bladder.

- They are more common.
- It occurs as a result of chronic urinary obstruction like BPH.
- It occurs adjacent to ureteric orifice and contains only mucosa (above and outer to ureteric orifice).
- It is prone for stasis, sepsis, stone formation, metaplasia and malignancy.
- Common in males (95%). Common in adults of 50 years.
- Haematuria (30%); fever; pyelonephritis.
- Micturition twice in rapid succession to empty the diverticular urine – is often typical.

Complications of bladder diverticula

- Recurrent infection
- Bladder stone formation
- Obstructive uropathy
- Malignant transformation – less than 5%

Investigation

- Urine C/S, cystoscopy, cystogram, IVU, U/S abdomen.
- CT scan abdomen.

Treatment

- Removal of the diverticula through open surgery.
- Approach is combined intravesical and extravesical. Through cystoscopy, ureteric stent is placed. Suprapubic transverse extra-peritoneal open approach is used. Anterior wall of bladder is vertically opened in midline. Diverticulum is packed with gauze. Junction between urinary bladder and, diverticulum is dissected from outside; transected and diverticulum is excised. Bladder surface is closed with vicryl 2 zero single layer sutures. Midline vesicotomy is closed with a Malecot's catheter. Retropubic space is drained. Indwelling urinary catheter is kept in situ for 7-10 days.

URINARY DIVERSION

- It is diversion of urine temporarily or permanently, proximal to the site of obstruction.
    - Temporary type is done in benign conditions and distal obstructions, to promote healing.
    - Permanent type is done in advanced malignancies which block the urine flow distally, after radical cystectomy, after radiotherapy with frozen pelvis etc.



Fig. 26.106: Perineal urethrostomy after total amputation of penis.

A man who does nothing never has time to do any thing.



Fig. 26.107: Types of urinary diversions.



Fig. 26.108: Ileal conduit as urinary diversion.

Temporary diversions are –

- Suprapubic cystostomy (SPC).
- Vesicostomy in children in ectopiae vesicae, epispadias, urethral anomalies
- Ureteric J stent – pigtail stents kept for 3 months.
- Urethrostomies.
- Nephrostomies in pyonephrosis and high obstructive uropathies.
- Pyelostomy.

Permanent Diversions

External Diversions

- *Non continent ileal conduit*

Here 20 cm of vascularised distal ileum (30 cm from IC valve) is prepared. Ureters are re-implanted over the ileum. Other end of ileum is brought out as a 3 cm stoma in right iliac fossa. Patient has to wear a bag over it.

- *Continent ileal conduit* is similar conduit with creation of specialised valve (Koch's continent) within, using ileal mucosa or appendix. Patient has to empty the conduit by passing self catheters once in 6 hours.
- Cutaneous ureterostomy/cutaneous ring ureterostomy.

Internal Diversions

- Uretero-sigmoidostomy (Leadbetter – pallitono).
- Rectal bladder creation.
- Ileo-cystoplasty.
- Caecocystoplasty/sigmoidocystoplasty.
- Creation of neo-bladder using ileum/caecum/sigmoid colon which is sutured to urethra.

Types of urinary diversions

- Nephrostomy
- Pyelostomy
- Cutaneous ureterostomy
- Cutaneous ring ureterostomy
- Supra-pubic cystostomy
- Vesicostomy in children
- Urethrostomy
- Uretero-sigmoidostomy
- Rectal bladder
- Urinary ileal conduit (Koch's conduit)

Complications of Diversions

- Urine leak, faecal leak, intestinal obstruction, sepsis.
- Hyperchloraemic hypokalaemic metabolic acidosis.
- Pyelonephritis.
- Osteomalacia, growth retardation.
- Calculi formation – 4%.
- Continent failure, blockage of diversion stoma (stenosis).
- Reflux of urine.
- Vitamin B_{12} and folate deficiency due to absence of ileum.

- Complications of stoma.
- Renal failure.
- Metaplasia and adenocarcinoma especially at uretero sigmoidostomy junction.

URINARY FISTULAS

It is the leak of urine at abnormal sites.

Causes

Congenital

- Patent urachus.
- Ectopiae vesicae.
- In association with anorectal malformation – rectovesical fistula.

Acquired

- Trauma to perineum.
- Pelvic surgery.
- *Vesicovaginal fistula* – due to obstructed labour; after hysterectomy, bladder may get injured while pushing it down; anterior colporrhaphy in elderly after vaginal hysterectomy; radiation induced; infiltrating carcinoma cervix. Usually it takes one week to cause necrosis and present as fistula. Features are – passage of urine per vagina, dribbling of urine in vagina on per speculum examination, swab test is positive (Methylene blue is injected through urethra after placing a swab in the vagina. Swab turns blue if there is fistula. Treatment is difficult. Surgical exploration – transvaginal repair in low fistula. Suprapubic repair if fistula is high. Often urinary diversion is needed.
- Specific causes like tuberculosis.
- Staghorn calculi can cause fistula after nephrostomy.
- Fistula can develop after surgery of renal pelvis, ureter, bladder. It will persist if there is distal obstruction like stricture urethra, otherwise it will subside spontaneously.
- Renal pelvis involved by Crohn's disease.

Investigations

- Discharge study for creatinine level.
- Urine C/S; leaking fluid for C/S.
- U/S abdomen; CT scan.
- MR fistulogram.

Treatment

- Correction of cause.
- Urinary diversion in initial period.
- Excision of fistula track and repair.
- Fistula can recur based on cause, nutrition, local blood supply, specific causes.

Self-assessment Questions

- Discuss bladder stone—types, presentations and management.
- Write notes on-
  - Oxalate stone.
  - Phosphate stone.
  - Triple phosphate stone.
  - Ectopia vesicae.
  - Thimble bladder.
  - Neurogenic bladder.
  - Rupture bladder.
- Bladder tumours—classification, clinical features and management.
- Transitional cell carcinoma (TCC).
- Endemic haematuria.
- Residual urine.
- Intravesical therapy for bladder tumour.
- Malakoplakia.
- BCG as immunomodulator.

> *Very occasionally the prostatic calculi are comparatively free and they impart to the palpating finger an impression of beads in a bag.*
> — Sir John E Erichson

Prostate

Anatomy
Acid phosphatase
Prostate specific antigen (PSA)
Benign prostatic hyperplasia
Prostatitis
Bladder outlet obstruction (BOO)
Carcinoma prostate

ANATOMY

It is an accessory gland of male reproductive system. It is composed of glandular tissue embedded in fibromuscular stroma. It surrounds the first 3 cm of the urethra.

Lobes

- It is composed of 5 lobes—Anterior, posterior, 2 lateral, 1 middle/median lobe.
- Primary carcinoma is said to begin in posterior lobe. Middle lobe produces an elevation in the lower part of the trigone of bladder *(uvula vesicae)*. Adenoma is more common here due to more amount of glandular tissue.

Capsules

1. *True capsule*: Formed by the condensation of the peripheral part of the gland; continues with the stroma of the gland.
2. *False capsule*: Derived from the pelvic fascia. On each side prostatic venous plexus are embedded in it.

McNeal Divided Prostate into Three Zones

- *Peripheral zone* – prone for carcinoma.
- *Periurethral transition zone* where BPH arises.
- *Central zone*.

Note:
- Prostate carcinoma develops in prostatic gland proper.
- BPH develops in submucosal glands.

ACID PHOSPHATASE

- It is the enzyme that splits organic phosphates.
- It is found in many human tissues, but more concentrated in prostate.
- It is active at pH 5.
- Acid phosphatase secreted by prostate drains into the urethra through prostatic ducts and so blood levels of this enzyme remain low.



Fig. 26.109: Parts of prostate.

- Serum acid phosphatase estimation should be done ***on empty stomach*** because heavy meals alter the level of the acid phosphatase.
- Normal value is *0-5 King Armstrong units per 100 ml of serum*.
- It is raised significantly in carcinoma prostate with metastases.
- *It does not increase in BPH.*
- Slight increase in acid phosphatase level occurs in acute prostatitis, Paget's disease of bone and hepatic cirrhosis.
- Prostatic fraction of acid phosphatase is more relevant in carcinoma prostate.

PROSTATE SPECIFIC ANTIGEN (PSA)

- It is a protease, produced from the prostatic epithelium secreted in the semen to cleave and liquefy the seminal coagulum formed after ejaculation.
- PSA is organ specific. *Normal value is 4 ng/ml of plasma. More than 10 ng/ml is significant*.
- PSA elevation occurs not only in carcinoma but also in prostatic hyperplasia and prostatitis.
- But the increase is much more in carcinoma than in benign conditions.
- PSA is in two forms: *Major,* bound form and *minor,* free form.
- Major, bound form increases in carcinoma. Minor, free form is increased in benign conditions.
- PSA density, i.e. PSA level per gram of prostate tissue is more relevant.
- Serial estimation of PSA is very useful to suspect spread and recurrence after treatment.

- 25% of men with PSA 4-10 mg% show prostate carcinoma.
- 20% of men with normal PSA (1-4 mg %) will show prostate carcinoma.
- PSA more than 10 mg % is suggestive of carcinoma prostate.
- PSA more than 35 mg % is almost diagnostic of advanced carcinoma of prostate.
- Decrease in PSA after therapy suggests adequate ablation.

Prostatic calculi: It is the calcification of corpora amylaceae which contains calcium phosphate, protein and fat.

BENIGN PROSTATIC HYPERPLASIA (BPH)

> ***He was very often, both in the Day and the Night, forced to make Water, seldom in any Quantity, because he could not retain it long enough.***
> **—Edward Hyde (first Earl of Clarendon),** 1759

It is benign enlargement of prostate which occurs after 50 years, usually between 60 and 70 years.

Theories

- It is involuntary hyperplasia due to disturbance of the ratio and quantity of circulating androgens and estrogens.
- BPH is a benign neoplasm, also called as ***fibro-myoadenoma.***
- Hypothalamus → pulsatile release of LHRH → release of luteinising hormone (LH) from anterior pituitary → stimulates Leydig cells of testes → releases testosterone (TS) → reaches prostate → releases 5α reductase type II of prostate → converts TS to DHT (dihydroteststerone) for its effects. DHT is five times more potent than TS. 90% TS is from testes. Remaining 10% TS is from adrenal cortex.
- With age TS level drops slowly. But fall of oestrogen level is not equal. So prostate enlarges through intermediate peptide growth factor.
- BPH arises from submucosal glands of periurethral transitional zone with stromal proliferation and adenosis. It eventually compresses the peripheral zone and enlarges as lateral lobe.
- BPH arising from subcervical glands of central zone enlarges as middle lobe projecting up into the bladder.

Pathology

- BPH usually involves median and lateral lobes or one of them.
- It involves adenomatous zone of prostate, i.e. submucosal glands.



Fig. 26.110: Prostate anatomy.

- Median lobe enlarges into the bladder.
- Lateral lobes narrow the urethra causing obstruction.
- *Urethra above* the verumontanum gets elongated and narrowed.
- *Bladder* initially takes the pressure burden causing *trabeculations, sacculations* and later *diverticula* formation.
- Enlarged prostate compresses the prostatic venous plexus causing congestion, called as *vesical piles leading to haematuria.*
- Incrimination of BPH as the source of haematuria before excluding other causes is termed as ***"Decoy prostate"***.
- *Kidney and ureter*: Backpressure causes *hydroureter and hydronephrosis*.
- Secondary ascending infection can cause *acute* or *chronic pyelonephritis*.
- Often severe obstruction can lead to obstructive uropathy with *renal failure.*
- BPH causes *impotence.*

Clinical Features

- Frequency occurs due to introversion of sensitive urethral mucosa into the bladder or due to cystitis and urethritis.

The formula to be complete happy is to be very busy.



Fig. 26.111: Retention of urine in bladder due to BPH.

- Urgency, hesitancy, nocturia.
- Overflow and terminal dribbling.
- Difficulty in micturition with weak stream and dribble.
- Pain in suprapubic region and in loin due to cystitis and hydronephrosis respectively.
- Acute retention of urine.
- Retention with overflow. High pressure chronic retention with functional obstruction.
- Impaired bladder emptying with its problems like cystitis, urethritis, stone formation and residual urine.
- Haematuria.
- Renal failure.
- Prostatism is a combination of symptoms like frequency both at day and night, poor stream, delay in starting and difficulty in micturition.
- Tenderness in suprapubic region, with palpable enlarged bladder due to chronic retention. Hydronephrotic kidney may be palpable.
- **Per rectal examination shows enlarged prostate. It should be done when bladder is empty.**
- Features of urinary infection like fever, chills, burning micturition.
- International prostate symptom score is available now.

Lower urinary tract symptoms (LUTS)	
Symptoms of voiding	*Symptoms of storage*
• Hesitancy	• Frequency
• Poor flow not improving by straining	• Nocturia
• Dribbling even after micturition	• Urgency
• Intermittent stream – stops and starts	• Urge incontinence
• Poor bladder emptying	• Nocturnal incontinence
• Episodes of near retention	

Differential Diagnosis

- Stricture urethra.
- Bladder tumour, carcinoma prostate.
- Neurological causes of retention of urine like diabetes, tabes, disseminated sclerosis, Parkinson's disease.
- Idiopathic detrusor activity.
- Bladder neck stenosis; bladder neck hypertrophy.

Investigations

- Urine for microscopy and C/S.
- Blood urea and serum creatinine.
- U/S abdomen—Look for presence of residual urine.
- Urodynamics.
  - Urine flow rate > 15 ml / sec is normal. 10-15 ml is equivocal; < 10 ml is low.
  - Voiding pressure < 60 cm of water is normal; 60-80 is equivocal; > 80 is high.
- Cystoscopy.
- Trans-rectal US (TRUS) is useful to find out nodules/possibility of carcinoma prostate. It is not done routinely.
- Acid phosphatase.
- Prostate specific antigen (PSA).
- IVU - to see kidney function.
- Serum electrolytes.

Note: Normal peak urine flow rate is 20 ml/sec. In obstruction it is less than 10 ml/sec.



Fig. 26.112: IVU showing bladder with enlarged median lobe of prostate.

Management

- Patient with ***acute retention*** of urine requires *urethral catheterization.*

- If urethral catheterization fails, then *supra pubic cystostomy (SPC)* is done.
- If patient presents with ***uraemia***, then urethral catheterization is a must. That allows the kidney to function adequately and further obstructive damage is prevented.
- Serum electrolytes should be corrected properly in these patients.

Indications for Surgery

- Prostatism (frequency, dysuria, urgency).
- Acute retention of urine.
- Chronic retention of urine with residual urine more than 200 ml.
- Complications like hydroureter, hydronephrosis, stone formation, recurrent infection, bladder changes.
- Haematuria.

Surgeries

1. *Transurethral resection of prostate (TURP)*:
    - Using cystoscope with fluid like glycine irrigating continuously, enlarged prostate is identified and resected using a loop with a hand control. Resection is done using high frequency diathermy current, above the level of verumontanum.
    - After surgery, continuous bladder irrigation using normal saline is done using three way Foley's catheter. Antibiotics should be given. Catheter is removed within 72 hours.

    Postoperative complications are:
    - Water intoxication with congestive cardiac failure—TURP syndrome.
    - Hyponatraemia
    - Haemorrhage
    - Infection
    - Incontinence
    - Perforation of the bladder or prostatic capsule
    - Stricture urethra
    - Retrograde ejaculation and impotence
    - Recurrence.

TURP

- No supra pubic incision
- Most common and popular method
- Done using resectoscope
- Recurrence may occur in large prostate
- TURP syndrome can develop
- Continuous postoperative irrigation using glycine solution is needed for 72 hours.
- Faster recovery and early discharge is possible.

2. *Freyer's suprapubic transvesical prostatectomy*. Before TURP, it was a popular and was the procedure of choice for enlarged prostate.

    Complications are haemorrhage, infection, stricture urethra, incontinence, impotence, bladder neck contracture.
3. *Millin's retropubic prostatectomy*. It is done without opening the bladder. (It is not commonly practiced).
4. *Young's perineal prostatectomy* through perineal approach.
5. Microwave hyperthermia treatment with temperature of 45–50 degree.
6. Laser treatment is becoming popular, using holmium laser.
7. High energy electromagnetic treatment.
8. Placement of intraurethral stents at prostatic urethra.
9. Placement of extrauretheral stents which are inert.
10. Transurethral balloon dilatation of the prostate.
11. If patient presents with acute retention of urine, initial urethral catheterization is done. If not possible then *suprapubic trocal cystostomy* ideally or formal open SPC is done. Once patient's obstructive uropathy is under control, TURP is done after 7-14 days after evaluation.

Specific Problems after Surgical Intervention of Prostate

- Retrograde ejaculation – 65%.
- Erectile dysfunction – 5%.
- Failure, recurrence of symptoms and enlargement – 10%.
- Need for re TURP/surgery in 10 years – 15%.
- Severe sepsis – 6%.
- Recurrent late urinary infection – 20%.
- Postoperative haematuria – 3% - needs transfusion.
- Mortality in TURP is 0.5%.

Other Methods used for BPH

- Transurethral incision of prostate – TUIP
- Laser ablation
- Transurethral microwave therapy – TUMT
- Transurethral needle ablation using high frequency radiowaves – TUNA
- High intensity US energy
- Water induced thermotherapy – through a balloon placed in prostatic urethra
- Prosthetic stents
- Balloon dilatation

> *In cases of complete intrapelvic rupture of the urethra, the tip of the catheter can be felt per rectum protruding from the urethral tear as a longitudinal cord lying beneath the anal canal.* —Wallace

Drugs used for BPH

- *Alpha 1 adrenergic blocking agents*—which inhibit smooth muscle contraction of prostate. They reduce the bladder neck resistance so as to improve the urine flow.
  - Short acting drugs are *prazosin* and *indoramin.*
  - Long acting drugs are *terazocin* and *doxazosin*.
  - Selective alpha$_{1A}$ – adrenoceptor blocking agent: *Tamsulosin* 0.2 to 0.4 mg OD for 12 weeks.
- *5-alpha reductase inhibitor* inhibits conversion of testosterone to dihydrotestosterone.
  - It is effective in palpably enlarged prostate.
  - Drug used is *finasteride* 5 mg daily. Duration of treatment is about 6-8 months.
  - It is contraindicated in obstructive uropathy or carcinoma prostate.

PROSTATITIS

Types

Acute or chronic.

Acute prostatitis

Causes:
- Due to instrumentation.
- Ascending infection from below.
- Haematogenous.
- Descending infection from above.

Bacteria involved:
- *E. coli, Klebsiella, Proteus.*
- *Staphylococcus.*
- *Streptococcus faecalis.*
- *Gonococcus.*

Clinical features:
- Pain, frequency, fever with chills and rigors.
- Retention of urine.
- **Perineal heaviness, pain on defaecation.**
- Tender prostate on per rectal examination.
- Initial fraction of urine is turbid which is sent for culture and sensitivity.

Investigations:
- Urine C/S.
- U/S abdomen.

Treatment:
- Prolonged rigorous antibiotics—for 2 months.
- Avoidance of alcohol and sexual intercourse for 6 weeks.

Complications:
- Formation of single or multiple abscess. It is common in diabetics.
- Chronic prostatitis
- Retention of urine.

Prostatic abscess has to be drained—through perineal approach under U/S guidance.

Chronic Prostatitis

Caused by *E. coli*, *Staphylococcus*, *Streptococcus*, *Trichomonas*, *Chlamydia*.
- There is always associated posterior urethritis.
- Epididymitis.
- Pain in the perineum, rectum, low back pain, leg pain.
- Fever.
- Sexual dysfunction.
- Per rectal examination shows tender prostate.
- Prostatic fluid obtained by prostatic massage shows 15 or more pus cells/HPF.
- In three glass urine test—first glass contains prostatic threads.

Treatment: Antibiotics—Co-trimethoxazole, trimethoprim, doxycycline.

Prostatic Abscess

- It is infection, suppuration and pus formation in the prostate gland.
- Presentation is fever, rigors, perineal pain, urinary disturbances, and tender soft fluctuant swelling in the prostate on rectal examination.
- Often presentation may be retention of urine.
- Total count will be increased.
- Urine will show pus cells.
- US is diagnostic. US is often done over perineum also.
- Treatment is antibiotics; US guided aspiration transperineally in lithotomy position or transperineal incision and drainage.
- Suprapubic cystostomy is better in case of retention of urine.
- After drainage antibiotics are needed for longer period of 6 weeks to prevent recurrent infection.

BLADDER OUTLET OBSTRUCTION (BOO)

- It is low urinary flow rate with the presence of high voiding pressure. It is an urodynamically confirmed entity.
- It is diagnosed by urodynamic pressure flow study.
- Flow rate will be les than 10 ml / second with voiding pressure more than 80 cm of water.
- Eventually detrusor inefficiency occurs causing significant residual urine.

- *Causes of BOO* – BPH; bladder neck hypertrophy or stenosis; carcinoma of prostate; urethral stricture; functional bladder neck obstruction.
- *Effects of BOO* – acute retention of urine; chronic retention of urine; impaired bladder emptying; uraemia; infection; stone formation, haematuria.
- US; renal function tests; IVU; PSA are the investigations.
- *Management* is by treating the cause by cystoscopic bladder neck incision, urethrotomy; TURP etc.

CARCINOMA PROSTATE

> ***During the last six months, (I.B.) had suffered …excruciating pain in the region of the kidneys and bladder, attended with almost constant desire to void urine, which was effected with the greatest difficulty…. An examination per rectum proved that there existed an enlarged…prostate gland, and slight pressure occasioned great pain…. The bladder was found (at autopsy) to contain a tumour as big as a large orange…discovered to derive its origin from the prostate gland…. The fungus …plugged up both ureters…. In the liver there were several tumours (and) several…in the lungs.***
>
> —**George Langstaff,** 1817

- It is the *most common malignant tumour* in men over 65 years.
- Carcinoma prostate occurs in peripheral zone in prostatic gland proper, i.e. *commonly in posterior lobe*. So prostatectomy for BPH does not confer protection against development of carcinoma prostate.
- Incidence of prostate cancer in men over 80 years is 70%.

Types of carcinoma prostate

- Microscopically latent
- Tumours incidentally found either by TURP or by PSA estimation
- Early localised carcinoma
- Advanced local prostatic carcinoma
- Metastatic carcinoma either into the bone commonly or other organs

Histology: It is an *adenocarcinoma,* wherein there is loss of myoepithelial cell layer which normally surrounds the prostatic glands (Gleason). Glands here appear in confluence. *Grading of carcinoma* is based on dedifferentiation as proposed by Gleason.

Staging of carcinoma prostate

Occult—Diagnosed after investigation due to suspicion

Stage I—Tumour confined to prostate/local nodule

Stage II—Tumour involving capsule or diffuse type

Stage III—Tumour involving seminal vesicle

Stage IV—Extension into adjacent tissue



Fig. 26.113: Staging of Ca prostate (a) Occult, (b) Stage I, (c) Stage II, (d) Stage III, (e) Stage IV.

TNM staging of carcinoma prostate

T1 – Incidentally confirmed carcinoma after prostatectomy
- T1a – Tumour occupying less than 5% of specimen
- T1b – Tumour occupying more than 5% of specimen
- T1c – Tumour impalpable but suspected by high PSA

T2 – Tumor nodule palpable on rectal examination
- T2a – Single nodule palpable on digital examination within prostate capsule
- T2b – Nodule involving both lobes

T3 – Tumor extends through the capsule
- T3a – Extension through capsule one or both
- T3b – Extension to seminal vesicles

T4 – Tumor which is fixed or spread to adjacent structures like pelvic wall and rectum other than seminal vesicles

Note:
For T1a progress rate is slow – 15-20% in 8 years
For T1b and T2 it is 35%
For T3/T4 M0 it is 50% in 5 years with bone spread
For M1 average survival is 3 years

Do all the good you can, by all the means you can, in all the ways you can, in all the places you can, at all the times you can, to all the people you can, as long as ever you can—

Spread

Local spread:

- Upward into seminal vesicles, bladder neck, trigone, later into both ureters causing anuria. Downward into distal sphincter.

Blood spread:

- Into the bones commonly—pelvic bones, lumbar vertebrae, femoral head, ribs, skull—in that order.
  - Pathological fractures can occur in long bones and vertebrae.
  - Paraplegia may occur if spine is involved.
  - Rarely spread to liver and lung can occur.

Lymphatic spread:

- Into the obturator lymph nodes, then to internal iliac lymph nodes.
  - Through seminal vesicles, into external iliac and retroperitoneal lymph nodes.
  - Eventually mediastinal, left supraclavicular lymph nodes get involved.



Fig. 26.114: A plain X-ray AP view of lumbar spine in a patient with carcinoma prostate. Note the typical osteosclerotic secondaries.

Clinical features

- Commonly asymptomatic
- Bladder outlet obstruction and so retention of urine
- Haematuria, frequency
- Pelvic pain, back pain, arthritic pain in sacroiliac joint—features of secondaries
- On per rectal examination, prostate feels hard, nodular, irregular often with loss of median groove
- Incidental carcinoma after TURP or after PSA analysis
- Features of renal failure
- Anaemia secondary to extensive bone marrow invasion and also due to renal failure

Differential Diagnosis

- Are other causes of retention of urine and other causes of back pain.

Investigations

- Hb%, peripheral smear. In metastatic disease, there may be leuko-erythroblastic reaction with bone marrow invasion causing anaemia, thrombocytopenia, DIC and increased fibrinogen degradation products (FDP). Anaemia may also be due to renal failure
- Prostate specific antigen (PSA): More than 10 nmol/ml is suggestive.
- Prostatic fraction of acid phosphatase is increased.
- Blood urea, serum creatinine, liver function tests.
- Transrectal ultrasound (TRUS) is very useful.
- Transrectal prostatic biopsy. 10 biopsy cores are taken.
- Plain X-ray, KUB, may show *dense coarse sclerotic* secondaries. Osteolytic or combination of lytic and sclerotic lesions are also often seen.
- Technetium radioisotope bone scan to see secondaries.
- U/S, abdomen, to see the tumour extension into the bladder and to see kidneys for hydronephrosis.
- MRI/CT scan is better for staging the disease. MRI is ideal. It can be combined with TRUS to have an accurate staging.

Note: Osteoblastic secondaries occasionally can be seen in carcinoma breast.



Fig. 26.115: Carcinoma prostate showing skeletal secondaries in bone scan.



Figs 26.116A and B: Osteoblastic secondaries in pelvic bones and lumbar spine.

Treatment

> ***In prostatic cancer with marked elevation of acid phosphatase, castration or injection of large amounts of estrogen caused a sharp reduction of this enzyme to or towards the normal range.... In 3 patients with prostatic cancer, androgen injections caused a sharp rise of serum acid phosphatase.***
> **—Charles Brenton Huggins, Clarence Vernard Hodges,** 1941

- Radical prostatectomy is done in early growth with removal of prostate, seminal vesicle, distal sphincter along with reconstruction of the urethra.
- Radical radiotherapy for early carcinoma prostate can be given using both interstitial and external radiation.
- Pelvic lymph node dissection with I^{125} radiation seeds implantation.
- Bilateral subcapsular orchidectomy is done to reduce the testosterone level. Very useful method. First started by ***Charles Huggins***—Urologist *(Nobel Prize winner).* (Other condition where orchidectomy is done is carcinoma of male breast.)
- ***TURP + Bilateral orchidectomy + External radiotherapy for bone secondaries + Flutamide*** or ***Honvan***—commonly advocated method.
- External radiotherapy for spine and pelvis.
- Strontium isotope radiotherapy.
- Drugs:
  - Phosphorylated diethyl stilbestrol ***(Honvan)***—initially given intravenously and later orally. It is very effective. Complications are cardiac congestion, DVT, gynaecomastia.

Phosphorylated diethyl stilbestrol

- Initially IV 100 mg/daily later orally 100 mg/daily
- Can cause cardiac congestion, DVT, gynaecomastia
- Prior RT to breasts to prevent gynaecomastia often advocated
- Response starts appearing in 48 hours

  - LHRH agonists (Medical castration)—Leuprolide, Goserelin.
  - Androgen receptor blocking agents *like flutamide*, bicalutamide.
  - Cyproterone acetate (also has got progestogenic effect).
    - In elderly people with early carcinoma prostate *inactivity with wait and watch policy* is practised.
    - Sometimes permanent suprapubic cystostomy (SPC) is required in these patients.

Prognosis is good

Remember

- Wait and watch policy is ideal in elderly patient with early carcinoma (P/R; PSA) above 70 years
- TURP if there is obstruction with bilateral subcapsular orchidectomy; LHRH agonists; androgen blockage

Look at happiness and misery the same; Look at success and failure the same. —True way of life it is called as.

- Radical prostatectomy/radical RT in young T1a or T1b – early disease. The criteria for radical prostatectomy—Life expectancy should be more than 10 years; PSA < 20 mmol/ml; bone scan should be negative
- Brachytherapy using guided RI seeds of I^{125} and palladium
- Orchidectomy; LHRH agonists (Leuprolide); androgen receptor blockade (flutamide, bicalutamide); TURP if needed – commonly done procedure
- External RT / IV radiopharmaceutical Strontium 89 (bone seeking isotope) for bone secondaries – used

Self-assessment Questions

Write notes on-

1. Aetiology, clinical features and management of BPH.
2. Decoy prostate.
3. TURP.
4. Treatment of BPH.
5. Clinical features of carcinoma prostate.
6. Treatment of carcinoma prostate.
7. Residual urine.
8. Obstructive uropathy.
9. PSA.
10. Acid phosphatase.

Urethra

Anatomy
Urethral injury
Stricture urethra
Hypospadias
Epispadias
Posterior urethral valve
Urethral calculi
Urethritis
Extravasation of urine
Retention of urine

ANATOMY

Posterior urethra:
Prostatic urethra.
Membranous urethra.

Anterior urethra:
Bulbar urethra.
Penile urethra.



Fig. 26.117: Anatomy of urethra.

URETHRAL INJURY

Classification

I. *Depending on site of rupture:*
   1. Rupture of the membranous urethra.
   2. Rupture of the bulbous urethra.

II. *Depending on circumference of the urethral wall involved:*
   1. Complete.
   2. Incomplete.

III. *Depending on the thickness of the urethra involved:*
   1. Total.
   2. Partial.



Fig. 26.118: Common sites of urethral injuries.

RUPTURE OF MEMBRANOUS URETHRA AND/OR PROSTATIC URETHRA (POSTERIOR URETHRA)

Causes

- It is usually associated with pelvic fracture, commonly due to road traffic accidents
- Injury can also occur during instrumentation
- Calculus passage and catheterisation
- In prolonged labour, due to long-standing pressure on the urethra by foetal head

- Prostate is attached to pubis by puboprostatic ligament and disruption of puboprostatic ligament with complete rupture of urethra can lead to *floating prostate—Vermooten's sign.*
- Injury can lead to incomplete rupture of urethra or may be associated with extraperitoneal rupture of bladder.

Based on ascending urethrogram, posterior urethral injury is classified as (Macculum-cola-pinto classification).

Type I: Elongation of posterior urethra, but intact

Type II: Prostate "plucked off" membranous urethra with extravasation of urine above sphincter only—*Floating prostate—Vermooten's sign*

Type III: Total disruption of urethra with extravasation of urine both above and below the sphincter

Clinical Features

- Blood in external meatus. Failure or difficulty in passing urine.
- Extravasation of urine to scrotum, perineum and abdominal wall.

Silence is not only the absence of sound but also stillness of the mind.

- *Shock* with pallor, tachycardia, hypotension.
- Features of associated injuries like head injury, thorax and or abdominal organs which take priority in initial phases of management.
- On P/R examination, prostate may be felt high or may not be palpable at all. Signifies *floating* prostate.

Investigations

- X-ray pelvis to see for fracture.
- U/S abdomen to see pelvis and other injuries.
- *Urethrogram* is done to see the site and type of tear. (often reserved to do at later stage).

Treatment

The shock and associated injuries are treated.

- In *floating prostate:*
  - *As rupture is complete*, bladder is opened from above. A metal bougie is passed from above through the bladder and one more metal bougie is passed from below through urethra and both are manipulated so as to meet each other.
  - Lower bougie is negotiated along the upper one and so into the bladder. Red rubber catheter is tied to the tip of the lower (urethral) bougie which has already entered into the bladder. When lower bougie is pulled out per urethrally, catheter tied to it will pass through urethra from above, to which Foley's catheter is tied and pulled up, so as to keep it in position.
  - Bladder is closed with a SPC using Malecot's catheter—*Railroad technique*.

In ***incomplete rupture:*** *Two approaches—*

- *First approach proposed by Mitchell*:
  - *Do not pass catheter from below* as it may further damage the urethra and also may damage sphincter mechanism and so may cause incontinence later. Here SPC is done using Malecot's catheter.
  - After three to six weeks, an urethrogram is done. Using endoscope or along with open method Foley's catheter is passed, often after dilatation.
- *Second approach advocated by Blandy*:
  - *Single attempt to pass a small soft catheter per urethrally* gently may lead into the bladder, which will be kept in situ, to maintain the continuity.
  - If this fails SPC is done. On second day, in operation theatre (O T), bladder is opened from above and flexible cystoscope is passed from below and using this, catheter is passed from below.
  - Bladder is closed with a SPC.
- If patient with incomplete rupture presents later, then it is managed once a stricture forms, accordingly as stricture urethra, after 3 months. Until then patient may require SPC.
- Other measures: Antibiotics, blood, fluid replacement, treatment of other injuries.

Complications

- Urinary incontinence
- Impotence
- Stricture urethra
- Infection



Fig. 26.119: Penetrating injury in the perineum causing rectal and urethral injury which is communicating. Note the catheter passed per urethra has gone into the rectum and come out through the anal canal. It needed colostomy and suprapubic cystostomy diversions. (*Courtesy by Dr Ashfaque Mohammad DNB, KMC Mangalore*)

RUPTURE OF BULBOUS URETHRA (Anterior urethra)

- Usually, due to a fall astride a projecting object, like in sailing ships, cycling, over loose manhole cover, gymnasium.

Clinical features: *Triad*

1. Blood in external meatus (Urethral haemorrhage)
2. Perineal haematoma
3. Retention of urine

- Rupture may be *complete* or *incomplete*.
- *Total* or *partial*.

Investigations

X-ray pelvis, and U/S abdomen. Condition is diagnosed clinically.

Treatment

- *Patient should be told not to try to pass urine*, if passed, then extravasation of urine occurs.
- In operation theatre, *one attempt of urethral catheterization is tried gently*. If able to pass a catheter, then it is left in place.
- Often perineal haematoma which occurs, has to be drained.
- Antibiotics should be given to prevent sepsis.
- *If catheter fails to pass*, then under general anaesthesia, in lithotomy position, SPC is done. Bulbous urethra is exposed through perineal midline incision and tear is sutured with an indwelling Foley's catheter. Drain is then placed into the perineum.
- If suturing is not possible (sometimes), then *perineal urethrostomy* is done and at later stages continuity is maintained (usually after 3 months).

Complications

- Infection
- Extravasation of urine
- Stricture urethra

STRICTURE URETHRA

Classification I: Aetiologically.

1. Congenital.
2. Inflammatory:
   a. Post-gonococcal is commonest (70%).
      – Gonococcal stricture occurs one year after infection.
      – Retention develops only 10-15 years later.
      – Common in the bulb of urethra especially in the roof.
      – Here multiple strictures are common, proximal stricture is the narrowest.
   b. Tuberculous.
   c. Other infection (urethritis).
3. Traumatic: Bulbous, membranous.
4. Postinstrumentation: Catheter, dilator, cystoscope.
5. Postoperative: Prostate surgery (4%), urethrostomy.

Classification II:

1. Proximal: Common in *bulbous urethra* (70%).
2. Distal: Congenital (in the external meatus). Often traumatic in children.

Classification III:

1. Permeable: Permits urine to pass.
2. Impermeable.

Classification IV:

1. Passable: Allows catheter to pass.
2. Impassable.

Classification V: It can be single or multiple.

Classification VI: According to the part involved. In the roof (commonest) or in the floor.

Clinical features

- Poor urinary stream
- Forking and spraying of the stream
- Incomplete emptying
- Frequency, dysuria
- Retention and often with overflow
- Pain, burning micturition, suprapubic tenderness
- Thickening and button-like feeling in bulbar urethra. (Bulbous urethra is felt clinically by lifting the scrotum in midline in the perineum.)

Investigations

- Urine microscopy and culture.
- Blood urea and serum creatinine.
- IVU to see hydronephrosis and function of kidney.
- U/S abdomen.
- X-ray of pelvis to see old fracture with history of trauma.
- *Ascending urethrogram* is an essential investigation to see the site, type, extent and false passage.



Fig. 26.120: Ascending urethrogram showing failure of dye to pass due to stricture urethra.

Even though you can't change realise it is time for you to change.



Fig. 26.121: Ascending urethrogram showing stricture urethra.

- The dye is injected through suprapubic needle puncture into the bladder and visualisation is done using C-ARM image intensifier.
- Urodynamic studies.
- Urethroscopy.



Fig. 26.122: Cystoscopic view of urethral stricture.

Treatment

1. **Intermittent dilatation**:

   Gradual dilatation, initially with thin dilators, later with thicker dilators of increasing size. Dilatation should be done in OT under aseptic precaution.

   *Should avoid forcible dilatation or over dilatation***.**

   Dilatation is done "***Once a week for one month, once a month for one year, and later once a year (on his birthday)***"*.*

   Dilators used:

   1. Lister's dilator [has got olive tip (blister)].
   2. Clutton's dilator.
   3. Filiform bougies.



Fig. 26.123: Filiform bougies are used to dilate narrow stricture urethra. One of the bougies will be passed into the urethra.

Complications of dilatation:
- Infection and bleeding due to trauma
- False passage
- Fistula formation

2. **Visual internal cystoscopic urethrotomy or stricturotomy**:
   - Here using cystoscope, stricture is visualized and is cut at 12 o'clock position, until it bleeds (fibrous tissue is cut completely).
   - After that Foley's catheter is passed and kept in position for 48 hours.
3. **External urethrotomy** by open method. Presently not commonly done as cystoscopic urethrotomy is more popular. It is presently done as an initial stage surgery for urethroplasty *(Wheelhouse's operation*).
4. **Urethroplasty:** Stricture is excised and urethra is reconstructed using *prepuceal skin* or scrotal skin. *(Johanson's urethroplasty).*

Problems in urethroplasty

- Staged procedure and so prolonged hospitalization
- Infection
- Necrosis of skin flap
- Leak and fistula formation
- Restenosis

Complications of stricture urethra

- Retention of urine
- Urethral fistula
- Infection-urethritis, cystitis, pyelonephritis
- Urethral diverticula
- Periurethral abscess
- Bilateral hydronephrosis
- Stone formation
- Renal failure
- Due to straining—hernia, haemorrhoids, rectal prolapse

HYPOSPADIAS



Fig. 26.124: Hypospadias.

It is the most common congenital malformation of urethra wherein external meatus is situated *proximal* than normal, over the *ventral* (under) aspect of the penis.



Figs 26.125A and B: Hypospadias in coronal region of glans penis with typical chordee.

Classification

- Glandular: Meatal opening in glans. It is the most common.
- Coronal.
- Penile.
- Peno-scrotal.
- Perineal with split scrotum. This is associated with bilateral undescended testes.



Fig. 26.126: Types of hypospadias

Features

- Absence of urethra and corpus spongiosum distal to abnormal urethral orifice.
- Bowing or bending of penis distal to abnormal urethral opening *(chordee)*, with poorly developed prepuce over inferior aspect.
- Urine soakage over the scrotum with dermatitis and infection.
- Associated congenital anomalies are known to exist.

Treatment: Staged Procedure

I. At the age of one and half years, surgical correction of the chordee is done.

II. At the age of 5-7 years, reconstruction of urethra is done using *prepucial skin* (ideal) or scrotal skin if the patient has been circumcised. Best is prepucial skin.

- *Perineal urethrostomy is done for diversion*.
- Perineal urethrostomy should be there until reconstruction of urethra takes up well *(Denis-Browne procedure).*
- *Magpi repair*: Meatal advancement glandular repair—for glandular hypospadias.

In hypospadias, circumcision is contraindicated as prepucial skin is required for future urethroplasty.

EPISPADIAS

- Here the urethra opens on the dorsum of the penis, proximal to the glans.
- Commonest site is at the abdomino-penile junction.
- It is associated with a dorsal chordee, ectopia vesicae, urinary incontinence, separated pubic bones.
- It is uncommon in females.

The greatest service is to share with others the joys of living.



Figs 26.127A and B: Bladder extrophy. X-ray pelvis showing separation of pubic bones. Epispadias is the common association.

Treatment

- Correction of incontinence of urethra.
- Urinary diversion.

POSTERIOR URETHRAL VALVE

- They are congenital symmetrical valves in the posterior urethra, just below the verumontanum.
- It allows the passage of catheter without obstructing its ingress. But it obstructs the outflow of urine.
- Proximal urethra is enormously dilated with obstructive pathology in the bladder (sacculations and diverticula formation).
- Bladder wall is thickened and hypertrophied so much so that it is palpable in supra pubic region as a firm swelling *(cricket–ball bladder).*
- There is poor urinary stream, with hydronephrosis, often with infection.
- Child finds difficult to pass urine.
- Often it is associated with vesico-ureteral reflux.
- Renal failure and atrophy of kidney occurs due to back pressure.

Investigations

- *Micturating cysto urethrography (MCU)* is diagnostic. It shows dilated proximal urethra.
- U/S abdomen.
- Blood urea and serum creatinine.
- IVU.
- Antenatal US shows fetal urinary tract dilatation.

Differential Diagnosis

- ***Marion's disease***: Bladder neck obstruction due to hypertrophied inter ureteric bar. MCU differentiates it from posterior urethral valve. Treatment is Y-V plasty ***(Bonin's Y-V Plasty).***
- Neurogenic bladder.

Treatment

Initial SPC and later cystoscopic resection of the posterior valves is done usually after several weeks.

URETHRAL CALCULI

Stone from the bladder is commonly passed out through urethra if it is small, but the stone can get impacted due to a *stricture* or *urethral diverticulum*.

Sites of impaction

- Prostatic urethra
- Bulbous urethra
- Fossa navicularis
- External meatus

Clinical Features

- Painful urination with thin stream and forking of urine.
- Retention of urine.
- Lower urinary tract infection.
- Haematuria.
- Pain in the penis and perineum.
- Stone may be palpable when it is in the bulbar or penile urethra.

Investigations

- Plain X-ray, KUBU (kidney, ureter, bladder urethra).
- U/S abdomen.
- Urine examination.



Fig. 26.128: X-ray showing urethral stone.



Fig. 26.129: Plain X-ray KUB showing stone in the bladder; stone in the terminal end of ureter; stone in the prostatic urethra.

Treatment

- If it is impacted in the external meatus or fossa navicularis, meatotomy and extraction of the stone is done. (Meatotomy is cutting and widening of external meatus so as to have an easy stone extraction.)
- If it is impacted in other parts of the urethra, urethroscopy and removal of stone from urethra is done or through a cystoscope the stone is pushed into the bladder and then extracted.
- In case of retention of urine, initial suprapubic cystostomy is required before removal of the stone.
- Diverticulum and stricture urethra should be treated accordingly.

Complications

Bleeding, stricture urethra and infection.

URETHRITIS

Causes

- Gonococcal urethritis.
- Nongonococcal urethritis:
  - Trichomonal urethritis.
  - Lymphogranuloma venereum (LGV).
  - Mycoplasma.
  - Ureoplasma ureolyticum.
  - *Candida*.
- Trauma, catheters, cystoscopes, stones.
- Chemical urethritis.
- *Reiter's disease*: Arthritis, conjunctivitis, urethritis.
- Allergy.

Reiter's syndrome

- Nongonococcal urethritis
- Conjunctivitis
- Arthritis

Clinical Features

- Urethral discharge, dysuria, burning micturition, haematuria and increased frequency.
- Perineal pain, tenderness over the site.
- Suprapubic pain and tenderness.

Investigations

- Urine microscopy and culture.
- U/S abdomen.

Treatment

- Antibiotics given according to culture and sensitivity.
- The cause is treated.

EXTRAVASATION OF URINE

Urine extravasates from the bladder or urethra and collects in the layers of the perineum or in the prevesical space (cave of Retzius).



Fig. 26.130: Extravasation of urine showing the collection of urine in the scrotum and perineum after trauma.

True victory means complete control over sense-organs.

Causes

- Trauma to bladder or urethra.
- Instrumentation like dilatation, catheterisation, cystoscopy.
- Infection like gonococcus *(water can perineum).*

Clinical Features

- Pain, swelling in the perineum.
- Retention of urine.
- Suprapubic pain, tenderness and fullness.

Treatment

- The cause is treated:
    - Antibiotics.
    - Suprapubic cystostomy.

Often multiple incisions may be placed in the perineum to evacuate the extravasated urine.

Complications

Abscess formation, sinus/fistula formation.

RETENTION OF URINE

- Retention can be *acute; chronic; retention with overflow.* Retention differs in male, female and in infants and children.
- Chronic retention is due to BPH, bladder neck contracture, urethral stricture, etc and is painless with suprapubic dullness.
- It is one of the common conditions seen in surgical casualty.

Causes

Urethral injury
Stricture urethra
Stone in the urethra
Phimosis with meatal stenosis
Posterior urethral valve
Prostatic hyperplasia (BPH).
Carcinoma prostate
Bladder tumour near bladder neck
Bladder neck hypertrophy
Prostatitis or urethritis

Neurogenic causes like head and spinal injuries
Postoperative period following pelvic and perineal surgeries
Drug induced retention of urine: Anticholinergics, antihistamine drugs, antidepressants

In males

- BPH in old.
- Stricture urethra in young.
- Trauma – urethral/pelvic.
- Post surgical – perineal surgeries like haemorrhoidectomy; fistulectomy; fissurectomy; pelvic surgeries; surgeries for fracture hip/fracture pelvic bone.
- Bladder outlet obstruction.
- Carcinoma of prostate.

In females

- Uterine prolapse.
- Urethral stricture.
- Uterine/Ovarian surgeries.

In infants and children

- Posterior urethral valve.
- Meatal stenosis.

Clinical Features

- Pain and swelling (fullness) in the suprapubic region.
- Inability to pass urine.
- Smooth, soft, tender swelling in hypogastric region which is dull on percussion.
- Features relevant of specific causes.
    - Per rectal examination to see prostate and other causes. In full bladder often prostate cannot be assessed properly.

Types

- Acute
- Chronic
- Retention with overflow

Investigations

- U/S abdomen.
- Blood urea, serum creatinine.
- Urine microscopy.

Treatment

- Urinary catheterisation using Foley's catheter.
- If it fails then suprapubic cystostomy (SPC) using Malecot's catheter is done.
- The cause is treated.
- Intermittent catheterisation in case of neurogenic bladder.

Management of retention of urine—

- Clinical and sonological assessment of kidney, ureter and bladder
- Evaluation for cause
- Evaluation for obstructive uropathy and renal function
- Urinary catheterization by Foley's catheter/red rubber catheter/metallic catheter.

- SPC with Malecot catheter by open method or using Foley’s catheter by trocal puncture method
- Intermittent catheterisation
- Vesicostomy in children
- Treating the cause
- Postoperative retention is a common cause. It is treated by reassurance, placing hot water bag over suprapubic region, change of position or standing, only occasionally by catheterisation.

Self-assessment Questions

- What type of urethral injury occurs in a man who falls on a manhole? Discuss the features and management.
- Classify urethral injuries.
- Rupture urethra.
- Membranous urethral injury.
- Bulbar urethral injury.
- Stricture urethra.
- Urethral dilatation.
- Urethrotomy.
- Extravasation of urine.
- Urethritis.
- Urethral calculus.
- Hypospadias.
- Posterior urethral valve.
- Causes of retention of urine.

The quality of our thoughts determines our own personal degree of happiness.

Penis

> ***The functioning role of the penis is as well established as that of any other organ in the body. Ironically, there is no organ about which more misinformation has been perpetrated. The penis constantly has been viewed but rarely seen. The organ has been venerated, reviled, and misrepresented with intent in art, literature, and legend through the centuries.***
>
> **—William H. Masters, Virginia E. Johnson,** 1966

Phimosis
Paraphimosis
Circumcision
Balanoposthitis
Chordee
Priapism
Peyronie's disease
Carcinoma penis
Buschke-Lowenstein tumour


Superficial dorsal vein of penis
Deep dorsal vein of penis
Dorsal artery of penis
Albuginea
Corpus cavernosum
Deep artery of penis
Corpus spongiosum
Urethra

Fig. 26.131: Anatomy of penis.



Fig. 26.132: Degloving injury of penis which needed skin grafting later.

PHIMOSIS

It is inability to retract the prepuce over the glans.

Causes

1. Congenital—in which case the child has pinhole meatus and ballooning of prepuce occurs when the child urinates.



Figs 26.133A and B: Pinhole meatus with phimosis. It is an indication for circumcision. Often clinically there will be ballooning of the prepuce during urination.

2. Balanitis (inflammation of glans) and balanoposthitis (inflammation of glans, prepuce and sac). Common in diabetics.



Fig. 26.134: Posthitis and balanoposthitis are common causes of phimosis in adult. It may be common in diabetics. Carcinoma should also be ruled out. Specimen should be sent for histology after circumcision.

Patients with phimosis are more prone for recurrent infection, smegma collection and *carcinoma penis*.

Treatment: *Circumcision.*



Fig. 26.135: Phimosis. It is inability to retract prepuce over glans.

Problems due to phimosis

- Recurrent balanoposthitis.
- Paraphimosis.
- Ballooning of prepuceal skin.
- Retention of urine.
- Prepuceal calculi formation due to smegma collection in prepuceal sac.
- Carcinoma of penis later.

PARAPHIMOSIS

- Inability to place back (cover) the retracted prepucial skin over the glans is called as paraphimosis.
- It causes ring like constriction proximal to the corona and prepuceal skin.
- As a result the glans will be swollen, oedematous with severe pain and tenderness.
- Often glans will undergo necrosis or becomes gangrenous.



Fig. 26.136: Paraphimosis.



Figs 26.137A and B: Paraphimosis showing constricted ring with infection in the groove.



Figs 26.138A to C: Paraphimosis is inability to place back the retracted prepuce.

If you want to advance in life, make sure that your WANTS don't advance.

Paraphimosis is precipitated after sexual intercourse or iatrogenically after urethral catheterisation.



Fig. 26.139: Paraphimosis developed after catheterisation due to failure of replacing back of the prepuce.

Treatment

- Manual reduction of prepuceal skin is to be tried.
- If not possible, *initial dorsal slit* is made to relieve the oedema and compression. Antibiotics and analgesics are given. *Circumcision* is done after 3 weeks.
- Sedation and hyaluronidase injection in 10 ml saline in to the constriction ring or multiple needle punctures over the oedematous part, reduces the oedema and makes the paraphimosis to get reduced. Later circumcision should be done.

CIRCUMCISION

> ***And God said to Abraham, "As for you, you shall keep my covenant, you and your descendants after you throughout their generations. This is my covenant.... Every male among you shall be circumcised. You shall be circumcised in the flesh of your foreskins, and it shall be a sign of the covenant between me and you. He that is eight days old among you shall be circumcised."***
>
> —**The Bible,** date unknown

Indications

- Religious
- Phimosis
- Paraphimosis after doing initial dorsal slit
- Balanitis and balanoposthitis (common in diabetics)
- Early carcinoma of prepuce or glans penis—both diagnostic as well as therapeutic purpose
- Certain sexually transmitted diseases, e.g. Herpes infection

Procedure (Refer Fig. 26.140)

- In children, it is done under G/A. In adults, it is done under local anaesthesia.
- After cleaning and draping, LA (1% lignocaine *(plain)* injected circumferentially near the root of the penis) is given (ring block).
- Dorsal skin is cut up to the corona and later circumferentially and ventrally.
- The skin is cut with inner layer.
- Care is taken to see that optimum (less) skin is cut ventrally to prevent the occurrence of *chordee*.
- Frenular artery is transfixed and ligated ventrally using chromic catgut (2-0 or 3-0). Small bleeders are also ligated.
- Skin is apposed to the cut edge of corona using interrupted chromic catgut sutures.
- Postoperatively, antibiotics and analgesics are given.

Complications

- Reactionary haemorrhage due to slipping of ligature from frenular artery and dorsal vein
- Infection
- Stricture urethra near the external meatus in *children*
- Chordee due to removal of excess skin on the ventral aspect
- Rarely priapism can occur

- *Hollister Bell cap technique* (Plastibel device) – This specially devised plastic cap can be fitted over the glans penis and prepuce is rolled over it. A tight ligature is tied over it near base of the prepuce. In 7 days skin and prepuce sloughs off and sheds with the cap. Bleeding will not occur due to thrombosis of prepuceal vessels. Technique can be used for religious circumcision/balanoposthitis without phimosis. It is contraindicated in phimosis and paraphimosis.

Note:

- Circumcision *by guillotine* is a method done by pulling and stretching the prepuceal skin beyond the glans and cutting the prepuce. It should be condemned and not be done as injury to glans is common. It is practiced in religious circumcision.
- Monopolar cautery should not be used in circumcision.

BALANOPOSTHITIS

It is inflammation of glans and prepuce – (Inflammation of prepuce is posthitis; of the glans is balanitis).



Fig. 26.140: Operative steps of the circumcision.

Causes

- Diabetes mellitus.
- Candidiasis.
- Veneral diseases like syphilis, herpes.

It can cause phimosis, carcinoma penis.

Clinical Features

Pain, swelling, discharge.

Treatment

- Antibiotics.
- Circumcision.
- The diabetes is controlled.

CHORDEE (CORDEE)

It is fixed bending of glans penis, more obvious during erection.



Fig. 26.141: Chordee

Types

a. Ventral.
b. Dorsal.

Causes

- Hypospadias, where urethra opens more proximally than normal *(ventral cordee).*
- After circumcision, if more skin is cut over the ventral aspect (*ventral cordee*).
- In epispadias *dorsal cordee* occurs.

Treatment

- Chordee due to hypospadias is corrected during staged procedure.
- In chordee following circumcision, initially stilbestrol 6 mg daily is given. Later chordee is corrected surgically by excising fibrous tissue and later doing skin grafting. More often they require surgical intervention.

PRIAPISM

- It is persistent, painful erection of penis.
- Corpora cavernosa are filled with blood due to defective venous drainage. Glans and corpus spongiosum are not involved.

Causes

- Idiopathic thrombosis of prostatic venous plexus.
- Sickle cell disease
- Leukaemia
- Secondary deposits in corpora cavernosa
- Spinal injury or diseases

Investigations

Relevant for specific causes.

When you burn with the fire of anger, smoke gets in your eyes.

Treatment

- Anastomosis between corpora cavernosa and saphenous vein.
- Anastomosis between corpora cavernosa and corpus spongiosum.

PEYRONIE'S DISEASE (Induratio-penis plastica)

- It is development of fibrous tissue plaque on the covering of corpus cavernosum and later involving its full extent resulting in induration of corpus.
- It is a slowly progressive disease of uncertain aetiology, may be due to old trauma, often associated with *Dupuytren's contracture, retroperitoneal fibrosis and plantar fasciitis.*
- Initial active phase has painful erection with changing deformity of penis.
- Later quiescent phase has disappearance of painful erection with development of deformity which is painless.
- Later erectile dysfunction; penile shortening occurs.
- Indurated plaque is noticed in the penis.

Treatment

- Some cases resolve spontaneously.
- Drugs
  - Steroids.
  - Vitamin E.
  - Potassium amino benzoate 12 mg / day.
  - Tamoxifen 20 mg daily.
  - Terfenadine and fexafenadine.
  - Colchicine therapy.
  - Intra lesional injection of verapamil 10 mg once in 2 weeks – 12 injections.
- Surgery is needed in many cases
  - Excision and plication to opposite side – *Fitzpatric operation*.
  - Multiple incisions over the fibrous plaque and temporal fascia bridging – *Gelhard's operation*.
  - Excision of fibrous plaque and corporotomy is covered with overlay flap like tunica vaginalis flap (*Lockhart's*)/dermal flap (*Devine and Horton's*).
  - Intracorporeal penile prosthesis placement.

RAM'S HORN PENIS

Filarial involvement of penis where it becomes thick, distorted and resembles horn of a ram.

CARCINOMA PENIS

- It is commonly *squamous cell carcinoma*, but melanoma, adenocarcinoma from Tyson's gland, basal cell carcinoma and secondaries may also occur.



Fig. 26.142: Carcinoma of penis involving glans extensively.



Fig. 26.143: Carcinoma penis earlier operated by total amputation of penis has now developed secondaries in inguinal lymph nodes which has already fungated. Note the perineal urethrostomy done.



Fig. 26.144A



Fig. 26.144B

Figs 26.144A and B: Carcinoma penis in two different patients.



Fig. 26.145: Carcinoma penis – circumferential proliferative exophytic lesion.



Fig. 26.146: Small ulcerated lesion over glans penis – carcinoma.

Aetiology

- Chronic balanoposthitis, phimosis.
- Sexually transmitted diseases.
- Leukoplakia of glans.
- Long-standing genital warts.
- *Paget's disease* of penis (Erythroplasia of Querat is persistent rawness of glans penis).
- Condyloma acuminata (by human papilloma virus), balanitis xerotica obliterans.
- HIV infection – HPV - 16.



Fig. 26.147: Genital warts – in glans penis. It is a pre-malignant condition. Biopsy, excision and podophyllin application is needed.

– *Circumcision during infancy confers total immunity against carcinoma penis.*
– It is common in Asia and Africa.



Figs 26.148A and B: Erythroplasia of glans penis. It is a premalignant condition.

Our senses don't deceive us; our judgement does.



Fig. 26.149: Carcinoma of penis causing destruction of entire penis



Fig. 26.150: Carcinoma penis with proliferative lesion.

Pathology

- *Infiltrating type* occurs in a preexisting leukoplakia. It often presents as indurated area.
- *Papilliferous type* eventually attains a large size forming a fungating foul smelling lesion which often gets infected.
- *Ulcerative type*.

– Glans penis is the commonest site (coronal sulcus for basal cell carcinoma).
– 80% are of low grade tumours.

Spread

- Through lymphatics, it spreads to the horizontal group of inguinal lymph nodes which become nodular and hard. Lymph nodes on both sides can get involved. Later, external iliac group are involved (above and on medial aspect of the inguinal ligament).
- Once inguinal lymph nodes are fixed, it causes severe excruciating pain and lymphoedema. *Fixed lymph node status indicates the advancement of the disease.* It may erode into the femoral vessels causing torrential haemorrhage and death. Fungation can occur.
- From glans, it also spreads to Cloquet lymph node which is located in femoral canal.
- Carcinoma from shaft of penis can spread directly to the external iliac lymph nodes.
- It spreads proximally to the body of penis causing induration.
- Urethral meatus may get involved causing alteration in urinary stream. *It is a locoregional malignant disease.*
- *Blood spread is rare*.

Clinical Features

- In an adult, recent onset of phimosis should raise the suspicion of carcinoma penis.



Figs 26.151A and B: Verrucous carcinoma of penis.

- Lesion is painless initially but later becomes painful due to secondary infection, often accompanied by discharge which is foul smelling, purulent and irritating.
- Altered urinary stream.
- Fungation and induration, often extending into the body of penis.
- Palpable hard, nodular inguinal lymph nodes on both sides may be present. External iliac lymph nodes may be palpable.
- Pain, oedema, tenderness, redness develops once infection occurs.

Investigations

1. *Edge biopsy* from the lesion shows squamous cell carcinoma with epithelial pearls.

Broder's classification: Grading:

- Very well differentiated (75% epithelial pearls)
- Well differentiated (50-75%)
- Moderately differentiated (25-50%)
- Undifferentiated (< 25%)



Fig. 26.152: Carcinoma of penis.

2. *FNAC of lymph nodes.* (No open biopsy for lymph nodes.)
3. U/S abdomen, to look for involvement of external iliac lymph nodes.
4. *SLNB*—**Cabana sentinel node** is located above and medial to the junction of saphenous and femoral vein. It is the first node to get involved in carcinoma penis. So this Sentinel Lymph Node Biopsy (SLNB) after isosulphan blue dye injection in to the primary is done to decide for the necessity for ilio inguinal block dissection.

Staging of Carcinoma of Penis

Jackson's staging of carcinoma penis

Stage I – Tumour involving only glans/prepuce/both	90% five year survival
Stage II – Tumour extending into body of penis	70%
Stage III – Tumour having mobile inguinal nodes	50%
Stage IV – Tumour spreading to adjacent structures/fixed nodes	5%

TNM staging

T_0 – No primary tumour
Tis – Carcinoma *in situ*
T_1 – Tumour < 2 cm without deep invasion
T_2 – Tumour between 2-5 cm with minimal deep invasion
T_3 – Tumour > 5 cm with deep invasion/urethral spread
T_4 – Tumour spread to adjacent tissues

N_0 – No nodal spread
N_1 – Mobile regional nodes – unilateral
N_2 – Mobile regional nodes – bilateral
N_3 – Fixed regional nodes

M_0 – No distant spread
M_1 – Distant spread present

Treatment

- If growth involves the glans without extending into the proximal part of shaft of the penis, then *partial amputation of the penis* is done. A length of 2.5 cm stump is retained. Clearance of 2 cm from the proximal extended part of the tumor is needed. Advantage is proper streaming of the urine is possible.
- Partial amputation of penis with bilateral ilio-inguinal lymph node block dissection is called as *Young's operation.*
- If tumour involves the proximal part of the body of penis or if it is anaplastic/poorly differentiated tumour *total amputation of penis* is done with *perineal urethrostomy*. Problems with perineal urethrostomy are scrotal ammoniacal dermatitis and stricture at urethrostomy site. Dermatitis is prevented by asking the patient to urinate in sitting position lifting the scrotum upwards. Stricture needs dilatation.

Violence at home can lead to blood in the streets.



Fig. 26.153: Specimen of total amputation of penis done for carcinoma of penis.

- Total scrotectomy with orchidectomy is done along with total amputation of the penis – *Sir Piersey Gold operation*. It prevents frequent dermatitis of the scrotal skin because of the perineal urethrostomy and also reduces the sexual desire.
- In case of carcinoma *in situ*, T_1 lesion of glans penis or well differentiated tumor in young individual, circumcision and curative radiotherapy to the penis can be given using radioactive tantalum wire implantation (6000 cGy in 7 days) or by wearing radium penile mould continuously or intermittently (6000 cGy in 7 days) or by linear accelerator external beam radiotherapy (6000 cGy in 5 weeks). Involvement of nodes in these patients is less than 10%.
- When lymph nodes are involved and are mobile, *bilateral ilioinguinal nodal dissection* is done.
  - *Primary inguinal block* is doing block dissection within 4 weeks of surgery for primary tumour.
  - *Secondary inguinal block* is doing block dissection after 4 weeks of surgery for primary disease. Only 50% of palpable inguinal nodes are involved by metastatic spread. So often a course of antibiotic is given and waited for 4-6 weeks. Complications of ilio inguinal block dissection are *flap necrosis*, lymphoedema of lower limb, femoral blow out, infection, lymphorrhoea and haemorrhage.
  - If primary tumour is poorly differentiated, and if tumour is T_2 or above, chances of inguinal nodal spread is more than 50% and so a prophylactic inguinal nodal dissection is done.
  - Often, involvement of inguinal nodes may be due to infection. So a trial of antibiotic therapy is given for 4-6 weeks to reduce the size of the inguinal node.
  - Removal of iliac nodes does not alter the outcome. It is done to confirm the spread, so that further therapy can be planned and prognosis can be predicted.
- Postoperative radiotherapy to inguinal region is often given.
- In advanced fixed inguinal nodes palliative external radiotherapy is given. It is to palliate pain, fungation and anticipated erosion into femoral vessels.
- Topical 5 FU cream or Nd:YAG laser photo-irradiation is useful in carcinoma *in situ*.
- *Chemotherapy* –
  5 FU; Methotrexate, Bleomucin, Cis platin and Vincristine. MBP/VBM combinations are used. Bleomycin is a radiosensitiser and so beneficial if RT is planned later.

Note:

- *Dresslers quadrangle* – upper border is formed by line joining anterior superior iliac spine and pubic tubercle; laterally line joining anterior superior iliac spine and a point 20 cm below it; medially pubic tubercle and a point 15 cm below it. Nodal block dissection for carcinoma penis should cover this area adequately.
- *Elective prophylactic inguinal block* is done in high risk group – invasive carcinoma; T_2 and T_3 tumours; with vascular invasion.
- *Therapeutic inguinal block* is done whenever FNAC of node shows positive tumour.
- *Superficial lymph node block* is dissection superficial to fascia lata in N_0 disease. It should undergo frozen section biopsy.If nodes are positive, then formal block dissection should be done.
- *Standard inguinal lymphadenectomy*–is classical block dissection.
- *Modified inguinal block dissection* (Catalona) – small incision, limited dissection, preservation of saphenous vein.

Role of radiotherapy in carcinoma penis

- Carcinoma *in situ*
- Small lesion less than 2 cm
- Lesion confined to glans
- Small lesion in young individual
- Advanced inoperable disease
- Palliation to inoperable inguinal nodes in groin
- Postoperative RT


A
B
Bladder
Urethra
Foley's catheter
Urosac bag
C

Figs 26.154A to C: Perineal urethrostomy is done for urethral injury, urethral surgeries like urethroplasties as diversion and after total amputation of penis in carcinoma penis.


Carcinoma
Incision
Partially amputated penis
Urethra
Urethra
Retained stump

Fig. 26.155: Partial amputation of penis is done in penile carcinoma in the glans not extending into the body of the penis.

Complications of inguinal block dissection

- Haemorrhage
- Lymphorrhoea
- Lymphoedema
- Infection
- Flap necrosis – *common*



Fig. 26.156: Total penectomy for carcinoma penis. Note the drain placed; sutures; urethrostomy site.

A long life may not be good enough; but a good life is long enough.

BUSCHKE-LOWENSTEIN'S TUMOUR

It is verrucous carcinoma of penis (5-15% common).

- *It is a curable malignancy*.
- It is locally destructive, locally invasive.
- It is often large, exophytic, dry, verrucae-like growth.
- Neither spreads through lymphatics nor blood.
- After biopsy and confirmation, surgical excision or partial amputation is the treatment of choice.
- Radiotherapy should not be given.
- Virus aetiology is proposed—HPV – 6 and 11.
- Systemic interferon α therapy and Nd:YAG laser therapy is successful.

Self-assessment Questions

- Phimosis.
- Circumcision.
- Paraphimosis.
- Carcinoma penis.
- Premalignant lesions for carcinoma penis.
- Treatment for carcinoma penis.
- Peyronie's disease.
- Chordee.

Scrotum

Anatomy
Fournier's gangrene
Hydrocele
Haematocele
Pyocele
Cyst of epididymis
Spermatocele
Varicocele

ANATOMY

It is a cutaneous bag containing the right and left testis, epididymis and lower part of spermatic cord.

Layers (from without inwards):
1. Skin
2. Dartos muscle
3. External spermatic fascia
4. Cremasteric fascia
5. Internal spermatic fascia

Blood Supply

From external pudendal, deep external pudendal and internal pudendal arteries.

Nerve Supply

- Anterior 1/3rd portion by ilioinguinal nerve and genital branch of genitofemoral nerve.
- Posterior 2/3rd portion by posterior scrotal branch of pudendal nerve and perineal branch of posterior cutaneous nerve of thigh.
- Dartos is supplied by sympathetic nerve.

FOURNIER'S GANGRENE

- It is also called as *idiopathic gangrene of the scrotum*.
- It is a vascular gangrene of infective origin, caused by haemolytic streptococci, microaerophilic streptococci, staphylococci, *E. coli*, *Cl.welchii*, *Bacteroides fragilis*.
- There will be fulminant inflammation of the scrotal skin and subcutaneous tissues resulting in *obliterative arteritis* of the arterioles of the scrotal skin leading into cutaneous gangrene.
- It is common in diabetics, old age, malnourished, immunosuppressed individuals.

Clinical Features

- Condition is common in old age.
- Sudden pain in the scrotum, fever, severe toxicity
- Very fast spreading cellulitis of scrotal skin, extending to the groin and often to anterior abdominal wall.
- Extensive skin sloughing occurs *leaving normal testis exposed.*
- Sometimes toxicity is so severe that they may go for renal failure and other complications.
- Sometimes the condition may worsen rapidly leading to death (25% mortality).



Figs 26.157A and B: Fournier's gangrene. Testes are normal. It is an infective gangrene of scrotum, rapidly spreading.

Treatment

- Treated as an in-patient always.
- IV fluids and catheterisation—for maintenance of urine output.

The smallest good deed is better than the grandest intention.

- Antibiotics, blood transfusion.
- Nutritional support (TPN, enteral).
- Liberal excision of all slough.
- Once patient recovers and wound granulates well, *skin grafting is done*.
- ***Orchidectomy is not necessary as testis is normal and viable.***
- Testis can be placed in the pouch in medial aspect of the thigh.

HYDROCELE

It is the collection of fluid between the two layers of tunica vaginalis of testis.



Fig. 26.158: Bilateral hydrocele.

Types

- Congenital
- Acquired
  - Primary
  - Secondary

Aetiology

- Defective absorption of fluid by the tunica vaginalis, probably due to damage to the endothelial wall by low-grade infection.
- Excessive production of fluid as in secondary hydrocele.
- Interference with drainage of fluid by lymphatic vessels of the cord.
- Communication with the peritoneal cavity.

Hydrocele fluid is amber-coloured with specific gravity of 1.022 to 1.024. It contains water, salts, albumin, fibrinogen. Per se, hydrocele fluid does not clot, but if it comes in contact with the blood, fibrinogen gets activated and clots firmly. Often fluid contains cholesterol and tyrosine crystals.



Fig. 26.159: Types of hydrocele.

Cysts which contain cholesterol crystals—
- Vaginal hydrocele
- Branchial cysts
- Dentigerous cyst

PRIMARY VAGINAL HYDROCELE

- Occurs in middle-aged, common in tropical countries.
- Testis is not palpable as it usually attains a large size (unlike secondary hydroceles which are small, except in filarial hydrocele).
- *Fluctuant* (elicited by, fixing the hydrocele with hand and feeling for the fluid movement using fingers placed in *two perpendicular directions*).

  Note: A relaxed muscle can demonstrate fluctuation in one direction even though there is *no fluid* in it.
- *Initially transilluminant*, (elicited in front of the swelling, side to side), but long-standing hydrocele is non-transilluminant (due to thickened dartos, thickened spermatic fascia, thickened hydrocele sac, infected content, chylous fluid, often filarial hydrocele, haematocele).
- Can *get above the swelling* (you can feel only cord structures and nothing else at the root of the scrotum, unlike in hernia).



Fig. 26.160: Hydrocele which is brilliantly transilluminant.



Fig. 26.162: Hydrocele is transilluminant. It may be negative in long-standing hydrocele, thick sac, thick dartos, thick skin and infected fluid or chylocele.



Fig. 26.161: Get above the swelling is possible in case of hydrocele.

- Testicular sensation can be elicited in vaginal hydrocele by transmitting the pressure sensation through the fluid.

Swellings which are brilliantly transilluminant

1. Vaginal hydrocele
2. Epididymal cyst
3. Cystic hygroma
4. Ranula
5. Meningocele



Figs 26.163A and B: Hydrocele in two different patients. One is average sized; another is large and penis is buried into the hydrocele swelling.

A clear conscience can bear any trouble.

Infantile Hydrocele

Here tunica and processus vaginalis (hydrocele) are distended up to internal ring, but sac has no connection with the general peritoneal cavity.

Congenital Hydrocele

- Processus vaginalis communicates with the peritoneal cavity.
- As this communicating orifice is too small, bowel does not descend and so hernia usually will not develop. While lying down, fluid disappears gradually and while standing fluid recollects.
- Hydrocele can not be emptied by digital pressure as it causes "*inverted ink bottle*" effect. Ascites, tuberculous peritonitis are the aetiologies for the same.

Encysted Hydrocele of the Cord

- It is a smooth, oval, swelling associated with the spermatic cord.
- On gentle traction to the testis, the swelling becomes less mobile (*traction test*).
- Differential diagnosis: Epididymal cyst, inguinal hernia, lipoma of cord, varicocele.
- Treatment is excision under local anaesthesia.

Hydrocele-en-bisac (Bilocular hydrocele)

Hydrocele has got two intercommunicating sacs, one above and one below the neck of the scrotum. Upper one lies superficial or in the inguinal canal or may insinuate itself between the muscle layers—*cross fluctuant.*

Other conditions where cross fluctuation is elicited:
1. Plunging ranula
2. Compound palmar ganglion
3. Psoas abscess

Hydrocele of the Canal of the Nuck

It occurs in females, in relation to the round ligament, always in the inguinal canal.

Hydrocele of the Hernial Sac

It is due to adhesions of the content of hernial sac. Fluid secreted collects in the hernial sac and forms hydrocele of the hernial sac.

SECONDARY HYDROCELE

Causes

Infection: Filariasis
Tuberculosis of epididymis - 30% cases have secondary hydrocele
Syphilis
Injury: Trauma, postherniorrhaphy hydrocele
Tumour: Malignancy

Secondary hydrocele rarely attains large size.

It is usually small, lax and testis is usually palpable (unlike primary hydrocele). *Exception is, secondary hydrocele due to filariasis.* It can be very large.

Postherniorrhaphy Hydrocele

It is a secondary hydrocele occurring after the surgery for inguinal hernia. It is due to the damage to lymphatic vessels of the tunica vaginalis and is 0.2% common. It is treated like any hydrocele but usually after about 6 months.

Filarial Hydrocele and Chylocele



Fig. 26.164: Chylocele

- Occurs commonly in coastal region, and in and around the equator.
- Usually occurs after repeated attacks of filarial epididymitis.
- Hydrocele is usually of large size and the sac is thickened.
- Fluid contains fat, rich in cholesterol, and is derived from ruptured lymph varix into the tunica.
- It is often difficult to differentiate from primary hydrocele.



Fig. 26.165: Hernia of hydrocele is a rare complication of hydrocele. Herniation occurs through dartos.

Complications of hydrocele

1. Infection
2. Pyocele
3. Haematocele
4. Atrophy of testis, hernia of hydrocele (rare)
5. Infertility
6. Hernia of hydrocele sac (rare)

Differential diagnosis

- Inguinal hernia
- Epididymal cyst
- Spermatocele
- Testicular tumour
- Scrotal oedema

Treatment for Hydrocele

Surgery

- Sub-total excision
- Partial excision and eversion (Jabouley's operation)
- Evacuation and eversion
- Lord's plication

Procedure

- Under G/A or spinal or L/A, after cleaning and draping, vertical incision of about 6-8 cm in length is made over the scrotum, anteriorly 1 cm lateral to the median raphe.
- Skin, dartos, external spermatic fascia, internal spermatic fascia are incised.

  Bluish hydrocele sac is identified, i.e. parietal layer of the tunica vaginalis of testis.

  Fluid is evacuated using trocar and cannula. Sac is opened.



Fig. 26.166: Trocar and cannula used to evacuate the hydrocele fluid.



Fig. 26.167A



Fig. 26.167B



Fig. 26.167C

> *In early testicular tuberculosis there is often a loss of cutaneous elasticity as shown by smoothening out of rugae consequent upon wasting of the cellular tissue beneath the dermis.* —A Clifford Morson



Fig. 26.167D



26.167E

Figs 26.167A to E: Bluish hydrocele sac and hydrocele fluid in the sac.

- *If the sac is small, thin and contains clear fluid,* either *Lord's plication,* i.e. tunica is bunched into a "ruff" by placing series of multiple interrupted chromic catgut sutures so as to make the sac to form fibrous tissue. (It is relatively avascular and so haematoma will not occur.)
- Or *evacuation and eversion* of the sac behind the testis (after eversion, everted sac is sutured with chromic catgut by continuous sutures) is done.
- *If the sac is thick, in large hydrocele and chylocele*, *subtotal excision of the sac* is done (as tunica vaginalis is reflected on to the cord structures and epididymis posteriorly, total excision leads to orchidectomy with division of cord).
- Often the sac is excised partially and then eversion is done, which is called as *Jabouley's* operation.
- After evacuation, the sac with the testis is placed in a newly created pocket between the fascial layers of the scrotum *(Sharma and Jhawer's technique).*
- *Aspiration must be avoided as much as possible* as it is only a temporary measure (recurrence occurs very early) and chances of haematocele, infection are higher.
- A drain is placed near the root of the scrotum on the lateral aspect because it becomes the most dependent portion, when scrotal support is given. Scrotal support is given to reduce the scrotal oedema.
- Wound is closed in layers.
- Drain is removed in 48 hours.



Fig. 26.168: Transilluminance of hydrocele sac during surgery just prior to placing the trocar for evacuation after exposing the sac.

Surgeries for hydrocele
- Subtotal excision of the sac
- Jabouley's operation
- Evacuation and eversion
- Lord's plication
- Sharma and Jhawer's technique



Fig. 26.169A to D: Hydrocele surgery showing sac; trocar and cannula; its insertion and evacuation of fluid.

Complications of surgery
- Reactionary haemorrhage
- Infection
- Pyocele
- Sinus formation
- Recurrent hydrocele

Conditions which cause loss of testicular sensation
1. Testicular tumour
2. Lepra orchitis
3. Syphilitic orchitis
4. Chronic haematocele

Conditions where orchidectomy is done in hydrocele
- Pyocele with testicular destruction
- Clotted haematocele with testicular destruction

HAEMATOCELE

Types

a. *Recent Haematocele*

- It is due to rupture of one of the vessels in the tunica causing bleeding into the sac.
- Often it may occur following aspiration of a hydrocele.
- It may be precipitated by trauma also.



Figs 26.170A to C: Haematocele in different patients. Orchidectomy is often required in these patients if testis is not viable.

Clinical features:
- Sudden onset of pain and swelling after an history of trauma.
- It is tender, warm, fluctuant, but nontransilluminant.
- Occasionally aggressive testicular tumour mimics the presentation of acute, recent haematocele.
  – U/S of scrotum is done in such suspected cases to rule out neoplasm and also to find out the viability of testis.

Complications
- Chronic (old clotted) haematocele
- Infection
- Pyocele.

Treatment: The scrotum is explored under general anaesthesia. The clot is evacuated and the wound is closed with a drain.

b. *Chronic or Old Clotted Haematocele*

- It is usually due to slow, spontaneous haemorrhage into the tunica vaginalis, without any proper history of trauma.



Fig. 26.171: Low orchidectomy is done in case of haematocele, pyocele. Here incision is in the scrotum. Cord is doubly ligated using thick chromic catgut.

- It is painless, hard, nontender, nonfluctuant, often calcified swelling, with *loss of testicular sensation*.
- Because of the constant pressure, testicular function and so testicular sensation is lost. It mimics testicular tumour in many aspect.
- U/S of the scrotum is done.
- **Treatment is** *orchidectomy*, as testis is functionless (Low orchidectomy through scrotal approach).

In transposition of the viscera (situs inversus) the right testis hangs lower.—C Allan Birch

PYOCELE

- It is collection of pus in the layers of tunica vaginalis.
- It can occur in a previously normal tunica or in a preexisting haematocele or hydrocele (which gets infected).

Features

- Fever, toxicity, tender swelling in the scrotum, with scrotal wall oedema.
- Often in young individuals, it may be difficult to differentiate this from the torsion testis.
- Pus under tension eventually causes infective thrombosis of testicular vessels, leading to nonviability of the underlying testis or testicular gangrene.



Fig. 26.172: Pyocele of scrotum. It is pus collection in the tunica vaginalis testis. It needs immediate exploration; drainage; often orchidectomy.

Treatment

- Antibiotics are started.
- Scrotum is explored immediately and pus is evacuated.
- Viability of the testis is checked.
- If viable, pus is evacuated and sent for C/S, wound is closed with a drain.
- If the testis is not viable, then *orchidectomy* is done (after taking consent).
- When in doubt, always testis is left in place and observed. Often, testis will show signs of viability. If not, then orchidectomy is done at a later stage.

CYST OF EPIDIDYMIS

It is due to the cystic degeneration of—

1. Paradidymis (organ of Geraldes)—is the most common cause
2. Appendix of the epididymis
3. Appendix of the testis
4. The vas aberrans of Haller

- Even though it is of congenital origin, it occurs in middle age.
- It is tensely cystic, contains clear fluid.
- Often bilateral.
- They are aggregation of number of small cysts and so **multiloculated**.
- They feel like ***'bunch of tiny grapes'*** situated behind the body of the testis.
- It is situated behind the body of testis.
- Because of numerous septae they are finely tessellated and so are brilliantly transilluminant, appear like ***'chinese lantern pattern'.***



Fig. 26.173: Epididymal cyst showing multiloculated 'Chinese lantern' pattern. Its location is behind the body of testis.

Differential Diagnosis

- Spermatocele.
- Encysted hydrocele of the cord.

Treatment

- Avoid excision as much as possible as it results in infertility due to blockage.
- In old age, excision can be done.

SPERMATOCELE

It is a *unilocular, acquired retention cyst* derived from blockage of some portion of the sperm conducting mechanism of the epididymis.



Fig. 26.174: Spermatocele occurs behind and above the testis. It is unilocular containing 'barley' like fluid.

- It is situated in the head of the epididymis, above and behind the body of the testis.
- Swelling contains *barley water like fluid*, which contains spermatozoa.
- It is soft, cystic and transilluminant. It is often considered by the patient as having an additional testis.
- Aspiration cytology confirms the diagnosis.

Treatment: It can be left alone. If it is large, excision is done.

Differential Diagnosis

- Epididymal cyst.
- Hydrocele.

Epididymal cyst	*Spermatocele*
• Congenital	• Acquired retention cyst
• Behind the body of the testis	• Behind and above the testis
• Multilocular	• Unilocular
• Bunch of grapes appearance	• Looks like 3rd testis
• Clear fluid as content	• Barley water fluid contains sperms
• Brilliantly transilluminant	• Transilluminant
• Excision should be avoided in young	• Can be excised

VARICOCELE

- It is dilatation and tortuosity of the pampiniform plexus of veins and so also the testicular veins. Normally, there will be numerous plexus of veins (pampiniform) in the scrotum, which all join together to form about 4-8 veins in the inguinal canal. Above, in the abdominal cavity, in the posterior abdominal wall all join to form a single testicular vein. On left side, it drains the left renal vein; on the right side it drains the inferior venacava.
- Varicocele is common in *tall, thin young men*.
- More common on the *left side*, but often can be bilateral.
- Commonly, it is idiopathic in origin, may be due to absence or incompetent valve at the junction of left testicular vein and left renal vein causing inefficient drainage of blood. Other reason is, due to perpendicular (right angle) entry of the left testicular vein into the left renal vein.



Fig. 26.175: Anatomy of testicular veins. Left testicular vein joins into left renal vein in perpendicular fashion. Right vein joins IVC directly.



Fig. 26.176: Scrotal U/S showing varicocele.

- In left sided renal cell carcinoma, tumour proliferates into the left renal vein and blocks the entry of left testicular vein causing varicocele on left side which is *irreducible.*
- Varicocele causes increased temperature in the scrotum which depresses the spermatogenesis and so causes *infertility* (correctable infertility).

> *When the scrotal skin of the affected side is less rugose than the normal side, it is probable that, that half of the scrotum never contained a testis.*
> —Kenneth I Macrosson



Fig. 26.177: Varicocele it is common on left side.



Fig. 26.178: Varicocele, on the table look. Note the tortuous vein. Ligation of these veins is the treatment.

Types of Varicocele

- *Primary/idiopathic*– 95%: No cause is found. There is incompetence of valves of the testicular vein. It is common on left side because left testicular vein joins left renal vein perpendicularly and left side vein is longer and liable to get compressed by loaded sigmoid colon. Left renal vein is often compressed between aorta and SMA.
- *Secondary* – due to specific cause like left-sided renal cell carcinoma with a tumour thrombus in left renal vein causing obstruction to venous flow of left testicular vein.

Subfertility / infertility are observed even in unilateral varicocele. It is a debate whether it really causes subfertility. Possible causes are –

- Altered heat exchange mechanism of the scrotum due to varicocele → hyperthermia → inhibition of spermatogenesis.
- Increased blood flow → increased temperature in the testes → increases the metabolic activity using glycogen storage → depletion of glycogen → injury of parenchyma of testes → oligospermia.
- Hypoxia of testes.
- Same cause leads into Leydig cell dysfunction, decreasing testosterone levels.
- Final effect is maturation arrest → poor spermatogenesis.

Clinical features

- Swelling in the root of the scrotum
- Dragging pain in the groin and scrotum
- *"Bag of worms"* feeling
- Impulse on coughing
- On lying down it gets reduced (except in renal cell carcinoma)

Bow sign: After holding the varicocele between thumb and fingers, patient is asked to bow. Varicocele gets reduced in size. Bowing reduces the blood flow of testicular vein and pampiniform plexus causing reduction in size.

Grading of varicocele:

I. Small
II. Moderate
III. Large
IV. Severely tortuous

Differential Diagnosis

- Hydrocele.
- Inguinal hernia.
- Lymph varix.
- Lipoma of the cord.

Investigations

- Venous Doppler of the scrotum and groin.
- U/S abdomen to look for kidney tumour.
- Semen analysis.

Treatment

- ***Palomo's operation***—Suprainguinal extraperitoneal ligation of the testicular vein.
- ***Inguinal approach***: Easier and safer.



Fig. 26.179: On table varicocele finding.

- *Scrotal approach*: In case of grade IV, veins have to be excised through this approach.
- *Laparoscopic approach* – Presently accepted, good approach.

Indications for surgery

- Pain
- Oligospermia—Usually in 6-12 weeks oligospermia improves very well and also the conception rate

Self-assessment Questions

- Varicocele.
- Hydrocele.
- Bubonocele.
- Haematocele.
- Pyocele.
- Surgeries for hydrocele.
- Epididymal cyst.
- Spermatocele.

Testis

> ***The stones are called in Latin, Testes, that is witness because they witness one to be a man, ask the Pope else, he will tell you I say true…. I need not tell you where they are placed, for every boy that knows his right hand from his left, knows that…. The use of the stones is, 1. To convert blood spirit into seed for the procreation of man…2. They add heat, strength, and courage to the body.***
>
> **—Nicholas Culpeper,** 1660

Anatomy
Undescended testis
Ectopic testis
Retractile testis
Torsion of the testis
Testicular tumours
Orchitis
Epididymitis

(*Testis* = was so-called because, in olden days men were *testifying* by holding the genitalia)



Fig. 26.180: Anatomy of the testis.

ANATOMY

It is the male gonad. It is suspended in the scrotum by the spermatic cord. It lies obliquely such that its upper pole is tilted forwards and laterally.

It is 1½ inches long, 1 inch broad, 3/4 inch thick. Epididymis lies along the lateral part of the posterior border.

Coverings of the Testis

1. Tunica vaginalis—lower persistent portion of processus vaginalis.
2. Tunica albuginea—Dense, white fibrous coat covering the testis; the posterior border of which is thickened to form the mediastinum testis. Numerous septa extend from it into the inner surface.
3. Tunica vascularis.

Structure of Testis

Contains 200-300 lobules, each containing 2-3 seminiferous tubules.

Arterial Supply

Testicular artery, a branch of abdominal aorta.

Venous Drainage

By pampiniform plexus of veins which ultimately fuse to form single vein, which drains into IVC on right side, renal vein on left side.

Lymphatic Drainage

Para-aortic group of nodes at the level of L_2 vertebra.



Fig. 26.181: Stages of testicular descent.

UNDESCENDED TESTIS

- It results from arrest of descent of the testis in some part along its pathway to the scrotum.
- Bilateral undescended testis is called *cryptorchidism* (means hidden testis).

Anorchism: Here there is complete agenesis of testis. These two can be differentiated by HCG test.

Embryology *(Normally kidney ascends, testis descends)*

- Primitive testis develops from the genital fold which is attached to the posterior abdominal wall by mesorchium. It lies below the developing kidneys.
- Wolffian duct develops into epididymis and *vas deferens*. A fold of peritoneum develops at the junction of *vas deferens* and epididymis which can be traced down upto the developing phallus (scrotum) and is called as *gubernaculum.*
- Along with some hormonal factors, the muscular fibres in the gubernaculum assist in the descent of testis.
- During 9th month of gestation, testis reaches deep inguinal ring. Later, just before or after delivery it descends into the scrotum.
- Increased intra-abdominal pressure, differential growth of the abdominal wall are other mechanical factors.
- Mullerian inhibiting substance from fetal sertoli cells; androgens and HCG are hormonal factors.

Aetiology

- Gubernacular dysfunction
- Lack of gonadotrophin (HCG)
- Lack of '*Calcitonin Gene Related Peptide (CGRP)*' produced by genito-femoral nerve responsible for testicular descent
- *Prune-Belly syndrome*—due to weak abdominal wall
- Familial
- Retroperitoneal adhesions
- Short vas deferens/short testicular vessels
- Altered hypothalamo – pituitary – gonadal axis; testosterone (androgen) deficiency; deficiency of Mullerian inhibiting substance which is secreted by fetal sertoli cells which is essential for testicular descent – are other factors

Incidence

- In premature infants—30%.
- In full-term infants—4%.
- In later childhood—2%.
- Right testis alone is involved commonly in 50% cases, left alone in 30% cases, bilateral in 20% cases.

Pathology

Up to the age of six, microscopic changes are uncommon. After that, testis gradually atrophies, reduces its external as well as internal secretory activity. Eventually, grossly immature epithelial elements with irreversible destructive changes of the germinal epithelium occur.

Different Positions

1. In the abdomen just above the internal ring, extraperitoneally.
2. In the inguinal canal.
3. In the superficial inguinal pouch.

Bilateral undescended testes which are clinically impalpable is called as ***cryptorchidism.***

- Scrotum is not fully developed and testis cannot be brought down manually to the bottom of the scrotum in undescended testis.



Figs 26.182A and B: Undescended testis right-sided. Inguinal region is normal without any swelling. Note the poorly developed scrotum on right side. Testis is probably intra-abdominal in this patient.

The smallest good deed is better than the grandest intention.

Differential Diagnosis

Retractile testis.

Complications of Undescended Testis

- Sterility.
- Trauma and pain.
- An associated indirect inguinal hernia (70%).
- Torsion testis.
- Epididymo orchitis (as the pain will be high up it mimics acute appendicitis).
- Testicular atrophy.
- *Malignant transformation in undescended testis is 20 times more common* than normally descended testis.
  - It is higher in abdominal than in inguinally located testis.
  - *Seminoma* is the commonest malignancy in undescended testis.
  - The testis which has normally descended on other side testis (in case of unilateral undescended testis), is also more prone for malignant transformation than normal individual.



Fig. 26.183: Undescended testis which has turned into seminoma testis.

"TESTIS"

- *Torsion*
- *Epididymo orchitis*
- *Sterility*
- *Trauma*
- *Inguinal hernia*
- *Seminoma*

Investigations

- U/S abdomen, intra-abdominal testis is difficult to detect in U/S.
- Assessment of FSH, HCG. If FSH is high in a young boy, that means there is bilateral anorchia.
- CT scan.
- Gonadal venogram.
- Laparoscopy—quiet useful and therapeutic also.
- Blind ending *vas deferens* in laparoscopy is called as *vanishing testis*. It means testis is completely atrophied.

Treatment

Always surgery. Surgery is done between two and four years of age.

Principles*:*

a. *Mobilisation of cord*
b. Repair of associated hernia
c. Adequate scrotal fixation without tension

Mobilisation of spermatic cord:

- Inguinal canal is opened.
- Herniotomy is done as hernia is a common association.
- Inferior epigastric vessels are ligated to lengthen the cord.
- If length is still required, vas and testicular vessels are mobilised retroperitoneally.
- If further length is required then a soft clamp is applied to the testicular artery and the viability of testis is checked. If it is viable that means it is also receiving blood supply from the artery of vas or cremaster vessels. Then testicular artery can be ligated safely so that adequate length can be achieved to bring down the testis to the scrotum—*Stephen-Fowler's technique.*
- **Proper scrotal pouch** is created by finger dissection.
- **Fixation of the testis** into the scrotum is done using nonabsorbable interrupted sutures (prolene). In bilateral cases, testis is passed into the opposite scrotum through an opening in the scrotal septum—*Ombredanne's Operation***.**
- If the testis is totally atrophied*, orchidectomy* should be done after taking consent, because even though this is a nonfunctioning testis, it is highly prone for malignant transformation.
- **Role of hormone therapy: Not much**. Only indications are cryptorchidism associated with hypogenitalism and obesity and doubtful retractile testis. It should be given at or after the age of eight.
  - HCG (Chorionic gonadotrophin) 1000 I/U—twice weekly for maximum of ten weeks (not more than 10 weeks). It stimulates Leydig cells to produce testosterone.
  - GnRH - 1.2 mg/day as nasal spray for one month.



Fig. 26.184A and B: Undescended testis in the inguinal region. Right-sided scrotum is underdeveloped. On table finding seen in the same patient. Hernia is the common association.



Fig. 26.185: Laparoscopic view of undescended testis (abdominal testis). Note the inguinal hernial defect. Laparoscopic approach is becoming popular.

***Note*:**

- In bilateral case surgery is done with an interval of 6 months.
- *Ladd and Gross procedure*: After placing the testis in the scrotal pouch, it is fixed by a polypropylene suture into tunica albuginea, across scrotal skin and into the thigh skin outside. This suture is removed in 14 days.
- *Keetley-Torrek procedure*: Testis is mobilised and is brought into the scrotal pouch first. Then it is brought out through scrotal skin. A pouch is created on the medial aspect of the thigh outer to fascia lata, deep to thigh skin after making skin incision. Testis delivered from scrotal pouch is placed into the thigh pouch. Scrotal and thigh incisions are sutured around the cord inside. After 6 months scrotal sac with cord and testis is separated and placed in the scrotal pouch.
- *Laparoscopic approach*: Orchidopexy has become popular and accepted method.
- Orchidopexy may not alter the chances/risk of developing carcinoma of testis. But it makes easy observation and evaluation by US to detect the possible changes early.
- Orchidectomy is considered if there is atrophy; torsion; inability to bring down abdominal testis.
- Testicular biopsy in infertility to study spermatogenesis is sent in *Buins fluid* – picric acid (not in formalin).

Surgeries in undescended testis

- External anchorage—Ladd and Gross
- Ombredanne's procedure
- Denis-Brownes operation—narrowing of the neck and external anchorage
- Keetley-Torrek procedure into the thigh
- Dartos pouch creation and placing the testes
- Stephen-Fowler's technique
- Silbar procedure—Autotransplantation with micro-vascular anastomoses into inferior epigastric vessels

ECTOPIC TESTIS

- **Lockwood theory:** Even though there are multiple gubernaculum, scrotal tail normally gets activated better and so testis is brought down to the scrotum.
- In ectopic testis, scrotal tail weakens or ruptures and so one of the other accessory tails will act and pulls the testis in direction according to its site.

> *About 1 man in every 14 has an anteverted testis.*—Sidney H Wadley

Different sites

- Superficial inguinal pouch
- Perineum
- Root of the penis
- Femoral triangle (thigh)

- Testis, here is functioning normally and of normal size. It is more prone for trauma and can cause psychological problem.
- *Superficial inguinal pouch* is space between external oblique and Scarpa'a fascia. On raising the legs, ectopic testis in superficial inguinal pouch becomes more prominent but not is case of undescended testis located in inguinal canal.


Tails of Lockwood
Ectopic sites of testis
Superficial inguinal pouch tail
Pubic tail
Penile tail
Gubernaculum
Superficial inguinal pouch
Pubic
Femoral tail
Femoral
Perineal tail
Perineal
Scrotal tail
Penile

Fig. 26.186: Tails of Lockwood and ectopic testes.

Treatment

- Mobilisation and creation of a new scrotal pouch.
- Then placement and fixation.

RETRACTILE TESTIS

- It is due to the overaction of cremaster. Testis is pulled up, to stay near the external ring and often mistaken for undescended testis.
- Here, testis is normally developed, can be pulled down to the bottom of the scrotum properly. Scrotum is also fully developed.

Treatment

- Usually *no treatment* is required. Often hormone therapy is given (HCG).

TORSION OF THE TESTIS

- It is an emergency condition of the testis, wherein the testis twists (rotates) in its axis compromising its blood supply. If not intervened and rectified within 12-24 hours, testicular gangrene may occur.
- Right testis rotates in clockwise direction where as left testis rotates in anticlockwise.

Predisposing factors

- Inversion of the testis
- High investment of the tunica vaginalis which acts like a mesentery through which testis rotates. Here testis hangs like a *clapper in bell*
- Presence of gap between the body of the testis and epididymis, as a result of which testis twists over epididymis
- Heavy straining often precipitates torsion due to vigorous contraction of the cremaster which is attached spirally



Figs 26.187A to D: Clinical look of torsion testis. On table finding showing torsion and gangrene of testis. Patient underwent orchidectomy and fixation of opposite testis.



Figs 26.188A and B: Torsion testis left sided – clinical look. Removed orchidectomy specimen.

Clinical Features

- Occurs in children and adolescents.
- Presents with sudden onset of pain in the scrotum, groin and lower abdomen.
- Vomiting due to pylorospasm.
- Tenderness, redness and oedema of the scrotal skin.
  - *Deming's sign:* Affected testis is positioned high because of twisting of cord and spasm of cremaster muscle.
  - *Angell's sign:* Opposite testis lies horizontally because of the presence of mesorchium.



Fig. 26.189: Torsion testes

Differential Diagnosis

- Acute epididymo-orchitis—elevation of the scrotum relieves the pain of acute epididymo-orchitis but aggravates in case of torsion testis *(Prehn's sign).*
- Strangulated inguinal hernia. Torsion of incompletely descended testis resembles strangulated inguinal hernia but the scrotum on that side is empty.
- Other structure in scrotum which can undergo torsion is '*Appendage of testis*'. If the patient is able to walk to clinician with feature of torsion, then this condition has to be thought of, whereas in torsion testis the pain is so severe that the clinician is summoned to the patient's bed.

Investigations

- Total WBC count.
- Doppler study of scrotum to look for the testicular artery pulsation.
- U/S abdomen.

Treatment

- *Emergency exploration of the scrotum and untwisting of the torsion testis is done*. Then viability of testis is checked. Once confirmed, the testis is fixed to the scrotal sac using 2-3 interrupted nonabsorbable sutures (Prolene).
- If surgery is done within 12-24 hours, viability of the testis may be retained. If delayed, testis becomes gangrenous and *orchidectomy* is done after taking informed consent.
- *When in doubt, testis is retained and orchidectomy can be postponed to later period* so as to give a chance to have a viable testis.
- Here *early exploration is an important aspect.*
- When diagnosis is in doubt, exploration is advised.
- Postoperatively, a repeat doppler study helps to confirm the viability. As often the condition is *bilateral, other side testis should also be fixed to prevent the torsion.*

TESTICULAR TUMOURS

- 1% of all malignant tumours.
- 99% of testicular tumours are malignant.

In torsion testis, affected testis lies higher than its fellow.—Clyde L Deming

Predisposing factors: Undescended testis and testicular atrophy.

Aetiology

- Cryptorchidism.
- Klinefelter's syndrome – testicular atrophy, absence of spermatogenesis, eunuch, gynaecomastia – features. These patients are prone to seminoma testis.
- Testicular atrophy.

Classification

1. Seminoma—40%
2. Teratoma—32%
3. Seminoma + teratoma—14%
4. Interstitial tumours—1.5% (Leydig cell tumour (musculinises), Sertoli cell tumour (feminises))
5. Lymphomas—7%
6. Others

Histological Classification

- *Germ cell tumour.*
  - Seminomatous – classic; spermatocytic; anaplastic.
  - Nonseminomatous type – embryonal carcinoma; teratomas; choriocarcinoma; yolk sac tumour (endodermal sinus tumour contains Schiller Duval bodies).
- *Sex cord stromal tumours* – Leydig cell tumour; Sertoli cell tumour; granulosa cell tumour.
- *Combined germ cell and gonadal stromal tumour* – Gonadoblastoma.
- *Adnexal and paratesticular tumours* – mesothelioma; sarcomas.
- *Others* – carcinoids; lymphomas.
- *Secondaries.*

Seminoma Testis

- Starts in the mediastinum of testis.
- Grossly it is lobulated, fleshy, homogenous, creamy or pinkish in colour and it compresses adjacent testicular tissue.
- Histologically, malignant cells resemble spermatocytes which are cells containing clear cytoplasm with large nucleus, and are arranged in sheets with fibrous stroma in between which is in turn infiltrated by lymphocytes.
- It spreads through testicular lymphatics into the para-aortic lymph nodes and then to left supra-clavicular lymph node. Through blood, it spreads to lungs, bone, brain, liver.

Types of seminoma –

- *Typical/classic form* – it is commonest type; occurs in middle age; syncytiotrophoblastic type (15%) occurs and produces high levels of beta HCG.
- *Spermatocytic seminoma* – occurs in older people with different phases of spermatogonia. Spread in this type is very rare.
- *Anaplastic type* has got high mitotic index/nuclear pleomorphism/anaplasia with high potentiality to spread.
- *Atypical* form of seminoma shows cytoplasmic expression of low molecular weight keratin type 1 precursor to blood group antigen where typical seminoma stains negative.

Teratoma



Figs 26.190A to C: Teratoma testis which is fungating out through scrotal skin. On table during orchidectomy and specimen of the same.

- It arises from totipotent cells, i.e. ecto, meso, endoderms.
- Grossly tumour surface is irregular, cut section shows solid and cystic spaces with areas of haemorrhage. It often contains gelatinous fluid and cartilaginous nodules.
- Teratoma spreads mainly through blood, less commonly through lymphatics.
- Teratoma can be mature; immature; choriocarcinoma or mixed germ cell tumour.

Histologically, there are four types—

1. *Teratoma differentiated*—(1%)
2. *Teratoma intermediate*—(30%) common
   - Two subtypes are A and B. Type A contains matured cells but type B is more malignant consisting of less proper differentiated tissues.
3. *Teratoma anaplastic* (15%)
   - Secretes alpha-feto-protein (AFP)
4. *Teratoma trophoblastic* (1%)

It shows high levels of beta HCG (normal level is 100 IU)



Fig. 26.191: Specimen of testicular tumour. Note the cystic and solid areas of teratoma.

Interstitial Cell Tumour

- *Leydig cell tumour*(2%): Masculinises. Prepubertal tumour shows excessive output of androgens causing sexual precocity, extreme muscular development often mimicking infant hercules. They are relatively benign, spread occurs to lymph nodes and lungs. It is treated by surgery. It is radioresistant and chemoresistant.
- *Sertoli cell tumour* (1%): Feminises. Post pubertal tumour commonly arising from sertoli cells causes feminising effect with gynaecomastia, loss of libido and aspermia. It may be classic/large cell type; calcifying/sclerosing. Surgery is the treatment.

Clinical Features



Fig. 26.192: Testicular tumour.

- Enlargement of testis.
- Fullness and heaviness in the scrotum.
- Pain in the testis (30%).
- Testis is enlarged, firm, heavy, with loss of testicular sensation.
- Secondary hydrocele is common.
- Cremaster is hypertrophied and thickened.
- Vas, prostate and seminal vesicles are normal.
- Often in epigastric region para-aortic lymph nodes may be palpable as hard, nodular, nontender, nonmobile, vertically placed, resonant mass (not moving with respiration).
- Haemoptysis, altered breath sounds and pleural effusion.
- Bone pain and tenderness due to secondaries in bone.
- Nodular secondaries in the liver.
- Occasionally, it may mimic acute epididymo-orchitis or acute haematocele.
- Gynaecomastia may be present in few teratomas.

- ***Hurricane type*** is very aggressive, highly malignant testicular tumour which is more often fatal in few weeks.
- Rarely, if tumour comes out of the tunica albuginea (tunica albuginea is resistant for malignant cell infiltration), then scrotum gets infiltrated and spread can occur to inguinal lymph nodes.

Differential diagnosis

- Acute and chronic haematocele
- Acute epididymo-orchitis
- Syphilitic orchitis
- Lepra orchitis

In torsion testis, testis always twists away from midline.—John P Sparks

Sign of vas: To differentiate tumour from infection—In testicular tumours vas is normal, cord structures may become bulky because of cremasteric hypertrophy whereas in infection vas is thickened, beaded, tender.

Staging of testicular tumours (Fig. 26.194)

I. Lesion confined to testis
II. Nodes involved below the diaphragm
III. Nodes involved above the diaphragm
IV. Distant (blood) spread

TNM staging

T_0 – No evidence of tumour
Tis – Carcinoma *in situ*
T_1 – Tumour limited to testis and epididymis. Vascular/lymphatic invasion not present. Tumour may invade tunica albuginea but not tunica vaginalis.
T_2 – Tumour limited to testis and epididymis with vascular/lymphatic invasion. Or tumour extends through the tunica albuginea with involvement of tunica vaginalis.
T_3 – Tumour invades to spermatic cord with or without vascular/lymphatic invasion.
T_4 – Tumour invades to scrotum with or without vascular/lymphatic invasion.

N_0 – Regional lodes not involved
N_1 – Single/multiple nodes – not more than 2 cm in size
N_2 – Regional nodes – between 2—5 cm
N_3 – Regional nodes > 5 cm

M_0 – Distant spread not present
M_1 – Distant spread present
M_{1a} – Distant spread to non-regional nodes or to lungs
M_{1b} – Distant spread to other than non-regional nodes or lungs

Investigations

No FNAC; No scrotal approach; No incision biopsy.

- Through inguinal approach, cord and testis are exposed. A soft clamp is applied to the cord at or above the level of the deep ring so has to prevent dissemination through blood. Frozen section biopsy is done from the suspected area. If tumour is positive, *high orchidectomy is done (Chevassou maneuver)*.
- Measurement of tumour markers (βHCG, AFP, LDH).
  - AFP and βHCG are elevated in nonseminomatous germ cell tumours (teratomas).
  - Raised AFP always indicates teratomatous tumour. *AFP level increase is not seen in pure seminomas*.
  - βHCG may be elevated in *advanced* cases of seminomas (10%).
  - LDH level depends on growth rate/cellular proliferation/tumour burden. LDH is increased in 80% of advanced seminomas and 60% of nonseminomatous germ cell tumour.
  - βHCG is never found in normal individual. It is secreted by syncytiotrophoblasts. Half life is 18-36 hours. It is increased in choriocarcinoma (100%); embryonal carcinoma (65%); teratoma testis; recurrent or residual disease in testicular tumour after therapy.
  - Placental alkaline phosphatase (PLAP) is increased in seminoma.
- Chest X-ray to look for lung secondaries. HRCT scan is ideal.
- U/S abdomen to see nodal status like para-aortic nodes and liver secondaries. CT abdomen is better.
- U/S scrotum to see echogenicity of testis and tumour within.
- CT scan abdomen and pelvis to look for secondaries, iliac and para-aortic nodes.
- CT chest is needed to confirm lung secondaries.
- Based on presence of AFP; βHCG; LDH; Non-pulmonary visceral secondaries (bone/liver/brain), germ cell tumour risk group classification is done to both seminomatous germ cell tumour (SGCT) and also to nonseminomatous germ cell tumour (NSGCT).
  - Good risk and intermediate risk group for SGCT.
  - Good risk; intermediate risk and poor risk for NSGCT.

Treatment

- Seminomas are radiosensitive. So after high orchidectomy, *radiotherapy* is given to increase the cure rate and also to reduce relapse. It is *the treatment of choice* in stage I seminomas. Opposite testis should be shielded during radiotherapy.



Fig. 26.193: High orchidectomy is done for testicular tumour through inguinal approach. Not through scrotal incision. Cord is ligated at the level of the internal ring.



Fig. 26.194: Staging of testicular tumour.

- Seminomas with high levels of tumour marker are treated as nonseminomatous tumours.
- Chemotherapy is also effective. *Cisplatin* is very useful drug in seminoma.
- In teratoma, *Retroperitoneal Radical Lymph Node Dissection (RPLND)* is beneficial after high orchidectomy. Even in stage I disease, chances of existing retroperitoneal spread is 30%. So RPLND (infra hilar) has a major role especially in teratomas which are relatively radioresistant. It involves removal of precaval, retrocaval, paracaval, interaortocaval, retroaortic, para-aortic, common iliac nodes along with removal of gonadal vein and adjacent fibrofatty tissues from internal ring level to its insertion in to renal vein on left side and inferior vena cava on right side. Commonly bilateral RPLND is done as contralateral nodes also can be involved. Mortality in RPLND is only 1%. RPLND may cause ejaculatory problems. Nerve sparing RPLND is ideal if technically possible. Nerve sparing dissection is done on opposite side of the tumour. Laparoscopic RPLND is also advocated safely.
- *Complications:* Haemorrhage; injury to main structures like major vessels/ureter/bowel; chylous ascites; lymphocele; retrograde ejaculation.
- Radiotherapy is not beneficial in teratoma.
- Chemotherapeutic drugs for teratoma are cisplatin, bleomycin, vinblastine, etoposide, ifsofamide, mesna, paclitaxel.

Follow up

- Measurement of tumour markers at regular intervals for 5 years and yearly after 5 years.
- CT abdomen and chest once a year

Factors Affecting the Prognosis

- Histological appearance of tumour.
- Staging of the tumour.
- Age of the patient, younger the age group poorer the prognosis.
- Seminoma has got better prognosis than teratomas.
- Spermatocytic seminoma has got good prognosis.
- Hurricane type has got worst prognosis.
- Seminoma responds well to RT (melts like snow). Teratoma is less sensitive RT.

PARATESTICULAR TUMOURS

Types

- Adenomatoid.
- Cystadenoma of epididymis.
- Mesenchymal neoplasms.
- Mesotheliomas.
- Metastases.

Features

- Generally sarcomatous.
- Rhabdomyosarcoma occurs in 40% cases. Occurs during first two years of age. It can be localised or with distant spread (lungs).

> *The young patient is asked to sit on a chair and hug his knees to the chest. Pressure then directed on the inguinal canal causes a retractile testis to descend into the scrotum.* — Louis Orr

- US scrotum; CT scan.
- Treatment – radical orchidectomy and chemotherapy.

ORCHITIS

- It is an inflammation of the testis. It is commonly associated with inflammation of the epididymis. Hence, called as epididymo-orchitis.
- Orchitis is due to infection through blood, lymphatics or epididymis.

Causes

- Viral infection—mumps.
- Filarial disease.
- Leprosy.
- Bacterial.
- Brucellosis.
- Infectious mononucleosis.
- It can be precipitated by retrograde spread due to stricture urethra, after prostate or bladder surgery, after instrumentation.
- Syphilis involves testis-causing formation of gummatous ulcer *on front of the scrotum.*

Features

- Pain in the testis often radiates in to groin due to associated funiculitis.
- Fever, tenderness in the testis.
- Secondary hydrocele is common.
- Urinary infection often noticed.

Differential Diagnosis

- Torsion testis.
- Testicular tumour.

Treatment

- Antibiotics, analgesics, DEC.
- Treating the cause.

EPIDIDYMITIS

Inflammation of epididymis is commonly associated with orchitis—*epididymo-orchitis*.



Fig. 26.195: On table operated hydrocele case – showing thickened epididymis.

Causes

- Non specific, viral like mumps.
- Bacterial.
- Filarial.
- *Tuberculosis*: It involves mainly epididymis not testis and so ulcer/sinus occurs over *the posterior aspect of the scrotum not in front.*
- Gonococcal.
- Schistosomiasis.

It can be acute or chronic.

Features

- Pain and tenderness in the epididymis.
- Swollen, tender epididymis.
- Thickened epididymis.
- Often secondary hydrocele may be present.
- Beaded vas with craggy epididymis.

Treatment

- Analgesics, antibiotics, Diethyl carbamazine citrate (DEC) 100 mg for 3 weeks.
- Specific cause should be ruled out.
- Long-term epididymitis causes real psychological disturbance to the patient and so reassurance is required.

Self-assessment Questions

- Testicular tumours, classification, investigation and management.
- Seminoma testis.
- Teratoma testis.
- Torsion testis.
- Ectopic testis.
- Management of testicular tumours.

27

Neurosurgery

Head Injuries
Extradural haematoma
Subdural haematoma
Subarachnoid haemorrhage
Depressed skull fracture
Hydrocephalus
Intracranial abscess
Intracranial aneurysms
Intracranial tumours
Pituitary tumours
Craniopharyngiomas
Spina bifida
Intervertebral disc prolapse
Tuberculosis of spine
Spinal tumours

HEAD INJURIES

> ***Now as soon as thou findest that smash which is in his skull like those corrugations which form on molten copper, (and) something therein throbbing and fluttering under thy fingers like the weak place of an infant's crown before it knits together-when it has happened there is no throbbing and fluttering under thy fingers, until the brain of his (the patient's) skull is rent open-(and) he discharges blood from both his nostrils and both his ears, (and) he suffers stiffness in his neck.***
>
> **— (Anonymous),** circa 2500 BC

Mechanism

1. *Distortion of the brain*: Brain is a soft structure, therefore has a 'mobility' and readily distorts. This distortion and mobility is accentuated by CSF and vascular components. Any impact creates shearing forces in the brain causing damage to neurons, supporting tissues and blood vessels. This leads to loss of consciousness, focal neurological deficits. Such distortive damage may be temporary or permanent.



Fig. 27.1 Exposed skull after trauma with sepsis. It needs multiple burr holes to allow granulation tissue formation from depth. Later skin grafting can be done. Otherwise local rotation flap is needed.

2. *Mobility of the brain in relation to the skull and membranes* causes cerebral damage and bleeding in dural spaces from torn vessels in the dura, commonly the veins. In old age, the brain shrinks, as a result of which 'mobility ' of brain increases favouring rupture of veins which cross the subdural space.
3. *Configuration of interior of skull*: Damage is less severe over the smooth area but is more severe over the rough and sharp areas. So the damage is severe over the

For the resolute and determined, there is time and opportunity.

anterior cranial fossa, over the falx, and over the tentorium.

4. *Deceleration and acceleration injuries: Deceleration injuries* occur when moving head strikes an immovable object (like in road traffic accidents). *Acceleration injuries* occur when stationary skull is struck by a moving object (like in assault).
5. *Cerebral concussion* is slight distortion causing temporary physiological changes leading to transient loss of consciousness with complete recovery.
6. *Cerebral contusion* is more severe degree of damage with bruising and cerebral oedema leading to diffuse or localized changes.
7. *Cerebral laceration* is tearing of brain surface with collection of blood in different spaces and with displacement of dural parts.

Effects of Brain Injuries

1. *Brain oedema* is accumulation of fluid, both intracellular and extracellular. It is due to congestion and dilatation of blood vessels. It may be diffuse or localized.
2. *Brain necrosis* is of severe variety with destruction and is due to haemorrhagic infarction.
3. *Extradural haematoma* occurs usually in temporoparietal region. It is commonly due to tear in middle meningeal veins and often middle meningeal artery. It causes intracranial hypertension, displacement, Kernohan's effect and often death.
4. *Subdural haematoma* is due to tear of veins between cerebrum and dura due to shearing forces. It is diffuse and commonly associated with cerebral injury.
5. *Intracerebral haematoma* can occur in different parts of cerebrum may be in frontal lobe, temporal lobe.
6. *Intraventricular haemorrhage* is very severe type of haemorrhage.
7. *Brain ischaemia* is due to increased pressure. This in turn leads to alteration in the perfusion of brain which itself aggravates the ischaemia and this forms a vicious cycle, causing progressive diffuse ischaemia of brain.
8. *Coup injury* occurs on the side of the blow to the head. *Contre-coup injury* occurs on the side opposite to the blow on the head.
9. *Coning*: It is due to raise in intracranial pressure causing either:
   i. Herniation of contents of supratentorial compartment through *the tentorial hiatus* or
   ii. Herniation of the contents of infratentorial compartment through the *foramen magnum.*

   In supratentorial herniation, there is compression of ipsilateral third cranial nerve and midbrain. Midbrain is displaced away from the mass (haematoma) and midbrain is pressed by the sharp edge of tentorium cerebelli of opposite side leading to dysfunction of corticospinal fibres (which after decussation supplies the opposite side of the body, i.e. same side of the injury).



Fig. 27.2: Coning with Kernohan's notch.

   This leads to:
   a. Deterioration in the level of consciousness.
   b. Dilatation of pupil on the side of compressing mass (haematoma).
   c. Hemiparesis on the same side of the mass lesion (haematoma) due to compression of the contralateral corticospinal tract. This effect is called as ***"Kernohan's notch"***.

   Herniation of infratentorial contents through the foramen magnum causes obstruction of cerebral aqueduct which further damages the brain function.
10. *Respiratory failure* altering PO_2 and PCO_2 levels.
11. *Raised intracranial pressure* causing bradycardia, hypertension, vomiting. Raised intracranial pressure may precipitate coning and thus aggravates brain ischaemia.
12. *Fluid and electrolyte imbalance.*
13. *Hyperpyrexia*.
14. *Convulsions* due to irritation of grey matter.
15. *CSF rhinorrhoea or CSF otorrhoea.*

Pathology of Head Injury

Primary lesions	*Secondary lesions*
• Diffuse neuronal damage • Shearing lesions • Contusions • Lacerations	Brain swelling • Oedema, venous congestion, hypoxia Intracranial haemorrhage • Extradural • Subdural • Intracerebral

	Infections • Open head injury – Generalised meningitis – Subdural empyema • Closed head injury – Pott's puffy tumor
Cerebral concussion • Temporary physiological paralysis of nervous system • Loss of consciousness • Post traumatic amnesia • Full recovery is expected • Residual complications may develop	*Cause of death in head injury* • Brain hypoxia • Coning • Diffuse severe irreversible neuronal injury • Death may be due to other injuries like abdominal/thoracic • Metabolic changes • Aspiration in unconscious patient

Clinical Approach of a Patient with Head Injury

1. Detail history of injury has to be taken and also the process of deterioration—rapid or gradual.
2. History of alcohol intake: Alcohol intake mimics head injury and alcoholism itself may mask the features of head injury.
3. *Neurological assessment*: By
   - Level of consciousness
   - Glasgow coma scale
   - Pupillary reaction to light and size
   - Pulse
   - Temperature
   - Blood pressure
   - Respiratory rate
   - Reflexes
   - Limb movements—normal/mild weakness/severe weakness/spastic flexion/extension/ no response
4. Status and protection of airway.
5. General assessment and other injuries like fractures, abdominal organ injuries, thoracic injuries are looked for.
6. Presence of any scalp haematoma, fractures of skull bone which may be depressed has to be looked for.
7. Any blood from nose or ear, CSF rhinorrhoea or CSF otorrhoea has to be looked for.

ADELAID COMA SCALE

It is used in children

Scores for eye opening and motor responses are same as Glasgow coma scale

But *verbal response score differs*—Oriented-5. Words-4. Vocal sounds-3. Cries-2. Nil-1

Orientation cannot be evaluated below 5 years. For first 6 months, the best verbal response is CRY

Other features

- CSF leak or bleeding from nose
- Blood collection in the orbit
- Black eye
- *Battle's sign*—ecchymosis over the mastoid
- Haematoma of scalp
- *Panda sign*—bilateral black eye



Fig. 27.3: Degloving injury scalp. Note all layers of the scalp stripped off.

GLASGOW COMA SCALE

Eye opening		*Verbal response*		*Motor response*	
Spontaneous	–4	Oriented	–5	Obeys commands	–6.
To speech	–3	Confused	–4	Localises pain	–5.
To pain	–2	Inappropriate words	–3	Flexion to pain	–4.
None	–1	Incomprehensible words	–2	Abnormal flexion	–3.
		None	–1	Extension to pain	–2.
				None	–1.

Total score-15
Mild head injury: score 13-15
Moderate head injury: 9-12
Severe head injury: less than 8 (3-8)

In great attempts, it is glorious even to fail.



Fig. 27.4: Patient with Head injury having black eye.

Indications for Hospitalisation

- Any altered level of consciousness
- Skull fracture
- Focal neurological features
- Persistent headache, vomiting, systolic hypertension, bradycardia
- Alcohol intoxication
- Bleeding from ear or nose
- Associated injuries

Investigations

- X-ray skull: To look for fracture, relative position of the calcified pineal gland, presence of intracranial air.
- Serum electrolyte measurement.
- Blood grouping and cross matching.
- CT scan: Plain (not contrast) to look for cerebral oedema, haematomas, midline shift, fractures, ventricles, brainstem injury.
- Carotid arteriography.
- Investigations for other injuries like ultrasound of abdomen.
- Monitoring of intracranial pressure.



Fig. 27.5: CT scan head showing scalp haematoma on both sides. There is no internal injury.



Fig. 27.6: CT scan head showing intracerebral haematoma.

Treatment

General

- Protection of airway using mouth gag, endotracheal intubation or tracheostomy, whenever required.
- Throat suction, bladder and bowel care and good nursing are very essential.



Figs 27.7A and B: CT scan head showing sharp head injury causing through and through cut across skull and brain. Patient survived and went home.

- Nasal oxygen, or often ventilator support.
- IV fluids initially, later Ryle's tube feeding has to be done.
- Electrolyte maintenance.

Drugs

- Sedation is avoided.
- Analgesics and anticonvulsants like phenytoin or phenobarbitone is started.
- Diuretics are given to reduce cerebral oedema—either mannitol 20%, 200 ml IV 8th hourly or frusemide 40 mg IV 8th hourly. It should not be given in case of intracranial haematoma.
- Antibiotics like penicillins, ampicillins are given to prevent the onset of meningitis.
- Corticosteroids, either dexamethasone or betamethasone is used commonly, but its beneficial effect is not confirmed.

Indications for surgery

- Acute extradural haematoma
- Acute subdural haematoma
- Depressed skull fracture

Procedure

Craniotomy is done and cranial flap is raised. Clot is evacuated followed by applying *hitch stitches* between dural layer and scalp. Postoperative antibiotics, analgesics, anticonvulsants are given.

Complications of Head Injuries

Early

- Brainstem injury—due to coning.
- Compression over cerebellum and medulla.
- ***CSF rhinorrhoea***: Due to communication between intracranial cavity and the nose. There is a tear in the dura following the fracture involving the sinuses—frontal, ethmoid, sphenoid sinuses. Meningitis is the common complication of CSF rhinorrhoea.
  Treatment: Initial management is only conservative, for 10 days—by antibiotics and observations.
  Indications for surgical intervention
  a. Fracture of middle third face
  b. CSF rhinorrhoea persisting for more than 10 days
  c. Fracture of sinuses
  d. An aerocoele
  e. An attack of meningitis
  Surgeries:
  (i) Reduction of fracture of middle third face.
  (ii) Exploration of anterior cranial fossa.
- Meningitis—common.
- Pituitary damage and endocrine failure—requires high dose of hydrocortisone 200 mg, 6th hourly.
- Aerocoele.
- CSF otorrhoea.
- Depressed fractures, often causes injury to dural venous sinuses and may lead to torrential haemorrhage, which may be life threatening. So such depressed fractures should never be elevated.

Late

- Chronic subdural haematoma.
- Early post-traumatic epilepsy—they need anticonvulsants for 3 years.
- Late post-traumatic epilepsy is due to scarring and gliosis of cerebrum.
- Post-traumatic amnesia.
- Post-traumatic hydrocephalus.
- Post-traumatic headache.

EXTRADURAL HAEMATOMA

- It is collection of blood in the extradural space between the dura and skull.
- Most common site is *temporo-parietal* region. It can *be unilateral or bilateral*

Vessels commonly involved

- Middle meningeal veins
- Anterior branch of middle meningeal artery
- Posterior branch of middle meningeal artery

Usually it is associated with fracture of temporo-parietal region.

Pathology

Direct blow, like from cricket ball or road traffic accidents or fall and impact or coup and contre-coup injuries

↓

Fracture of thin temporal bone

↓

Tear of vessels

↓

Bleeding initially outward towards the scalp and under temporalis muscle

↓

Formation of haematoma

↓

Gradual stripping of dura from skull and collection of blood occurs

↓

> *Fourth nerve when paralysed causes diplopia when going downstairs (that is on looking downwards).*
> —Sir Benjamin W Ryeroft

In 6-12 hours extradural haematoma occurs which raises the intracranial pressure

↓

Coning of supratentorial content (uncus of temporal lobe) through tentorial hiatus

↓

Shift of midbrain towards opposite side which gets injured by sharp edge of the tentorial cerebelli

↓

Corticospinal tract before decussation on opposite side gets injured

↓

So hemiparesis, and pupillary changes occur on the same side of haematoma.

↓

This effect is called as ***Kernohan's notch effect***.

- Immediately after injury, there is transient loss of consciousness and the patient soon becomes normal. Later after 6-12 hours, he again falls ill and the condition deteriorates. This is the time taken to develop raised intracranial pressure, coning and its effects. This crucial time gap which is unnoticed and often missed is called as ***"lucid interval."***

Clinical Features

- History of transient loss of consciousness following a H/o blow or fall.
- Patient soon regains consciousness and again after 6-12 hr starts deteriorating ***(Lucid interval)***.
- Later the patient presents with confusion, irritability, drowsiness, hemiparesis on same side of the injury. Initially pupillary constriction and later pupillary dilatation occurs on the same side, finally becomes totally unconscious – *Hutchinsonian pupils*.
- Death can occur if immediate surgical intervention is not done.
- *Features of raised intracranial pressure* like high blood pressure, bradycardia, vomiting is also seen. Occasionally *convulsions* may be present.
- *Wound and haematoma in the temporal region of scalp* may be seen.

Investigations

- X-ray skull may show fracture of temporal bone.
- Electrolyte estimation.
- CT scan head is diagnostic. Extradural haematoma shows *biconvex* lesion.



Fig. 27.8: Extradural haematoma. Note the biconvex configuration of the haematoma.

Treatment

Immediate surgical intervention is a must to save the life of the patient.



Figs 27.9A and B: CT scan head showing extradural haematoma with biconvex lesion.

- Craniotomy is done and cranial flaps are raised. The dura is opened and the clot is evacuated. The dura is fixed to galea using interrupted sutures—*Hitch stitches*.
- Antibiotics and anticonvulsants are given post-operatively.
- Recovery is good after surgery.

Treatment of extradural haematoma

- Earliest surgery and evacuation is the need
- 5 cm vertical incision in parietal region above the zygoma
- Galea is incised. Skull is opened using perforator and burr
- Meninges are kept aside
- *Black currant jelly clot* is evacuated
- Bleeding vessels are cauterized – bipolar cautery
- Dural hitch stitches are placed
- Opposite side if needed should be evacuated
- Antibiotics; anticonvulsants
- Analgesics
- General measures – catheter; fluid therapy
- Prevention post traumatic complications

Complications

- Post-traumatic epilepsy
- Meningitis
- Post-traumatic amnesia

SUBDURAL HAEMATOMA

Types

- *Acute*
- *Chronic*

Acute Subdural Haematoma

- It is a collection of blood between the brain and dura.It is due to injury to the cortical veins and often due to laceration of cortex of brain which bleeds and blood gets collected in the subdural space forming a haematoma.
- Here haematoma is extensive and diffuse. There is no lucid interval. There is severe primary brain damage.
- Haematoma may be of coup and contre-coup type.
- Loss of consciousness occurs immediately after trauma and is progressive.
- Convulsion is common.
- Features of raised intracranial pressure is obviously seen—high BP, bradycardia, vomiting.
- Focal neurological deficits or hemiparesis can occur.
- CT scan shows concavo-convex lesion.

Treatment

- Antibiotics, anticonvulsants.
- *Surgical decompression is done by craniotomy.*

Chronic Subdural Haematoma

- It is due to the rupture of veins between dura and brain (cerebral hemispheres), causing gradual collection of blood in subdural space.
- It is commonly seen in elderly people following any minor trauma like fall, slipping (which might have gone unnoticed).
- In elderly people, brain atrophies and even minor injuries can cause shearing and bleeding from these veins.
- Blood collects gradually over 2-6 weeks. Plasma and cellular components get separated. Eventually cellular part gets absorbed leaving only fluid component. It is called as ***chronic subdural hygroma*.**
- Usual haematoma collection is 60-120 ml. Often in 50% of cases, it is bilateral.

Clinical Features

- Common in old age, with history of minor trauma
- Patient presents with confusion, disorientation, gradually with altered level of consciousness and drowsiness.
- Later convulsions, features of intracranial hypertension, features of coning develops.
- Extensor plantar response and pupillary changes develop eventually.

Investigations

- CT scan (shows *concavo-convex* lesion).
- Serum electrolytes.
- Blood grouping and cross matching.

Differential Diagnosis

- Electrolyte imbalance.
- Intracranial space occupying lesion.

Two black eyes following one injury indicate fracture of the base of skull.—Sir Earnest Finch



Fig. 27.10: Subdural haematoma. Note the concavo-convex configuration of the lesion.



Fig. 27.11: CT scan head showing subdural haematoma with concavo-convex lesion.

Treatment

- Craniotomy and evacuation of clot is done when required on both sides.
- Antibiotics.
- Anticonvulsants for 3 years.

Complications

- Epilepsy
- Meningitis
- Coning
- Neurological deficits

Chronic Subdural Empyema

- It may be primary infection of subdural space from sinusitis focus causing suppuration and pus formation.
- It can be complication of the chronic subdural haematoma.
- It is due to secondary bacterial infection of collected clot/fluid.
- Infection is from sinusitis scalp (common)/through earlier trauma wound/Haematogenous.
- Commonly Gram positive organisms cause empyema like streptococci (viridans/milleri) but other virulent organisms like Gram negative bacteria occasionally can cause.
- There is cortical venous thrombophlebitis and cortical infarction.
- Headache, fever, meningism and convulsions are the features.
- MRI is ideal than CT to diagnose.
- *Treatment*: Antibiotics, craniotomy and drainage; anticonvulsants, ICU care, proper monitoring, regular follow up.
- Condition has got 10% mortality.

SUBARACHNOID HAEMORRHAGE (SAH)

> ***The Abbot by chance wished to decide with him the fate of the servants, found (him) prostrate upon the ground, insensible to shouts, to shaking and pinching of the body…senseless…. I saw him livid from pallor, deprived of all sensation and animate motion…. The first hour after midday of the same day he ceased to live…. By the indulgence of the Most Reverend Lord Abbot… I opened the head…. Much blood flowed from the space…. The (blood) covered (the brain) all over…. The ventricles laid open I found them all filled up with blood.***
>
> **—Johann Jakob Wepfer,** 1658

It is a type of intracranial haemorrhage into the subarachnoid space usually from basal cisterns.

It may be spontaneous or following trauma.

Causes

- Intracranial aneurysms.Commonest cause (50%)
- Hypertension
- A-V malformations
- Blood dyscrasias
- Anticoagulant drugs
- Brain tumours (malignant)

Clinical Features

- Sudden onset of severe headache with vomiting.
- Features of raised intracranial pressure.
- Photophobia.
- Neck stiffness.
- Focal neurological deficits: hemiplegia, dysphasia.

- Eye changes: ptosis, dilated pupil, changes in the eye ball movements.
- Sudden loss of consciousness.
- Features of brain oedema and cerebral ischaemia.

In 40% of recovered patients, rebleeding occurs in 6-8 weeks which is commonly fatal.

Hunt and Hess grading for subarachnoid haemorrhage:
Grade 1: Asymptomatic
Grade 2: Severe headache and neck stiffness
Grade 3: Drowsy, confused or mild focal deficit
Grade 4: Stupor, hemiparesis
Grade 5: Decerebrate rigidity, coma

Fischer grading of SAH

I—minimal < 8 mm size
II—moderate 8-15 mm size
III—severe > 15 mm size

Differential Diagnosis

- Meningitis.
- Coning due to any cause.

Investigations

- Lumbar puncture should be done to differentiate from meningitis.
  It has to be done carefully as it may precipitate coning.
  In subarachnoid haemorrhage, blood stained CSF is collected.
- CT scan.
- Carotid and vertebral angiogram.

Treatment

- Clipping, or wrapping the aneurysm.
- Craniotomy and proceed.
- Ligation of common carotid artery—there is risk of hemiplegia.
- Therapeutic embolisation.
- Excision of vascular malformations.
- Coiling of aneurysm with instruments.

DEPRESSED SKULL FRACTURE

- It is a common neurosurgical problem among the head injuries.
- It means fracture depression is more than the depth of inner table of the skull.

Problems in depressed fracture

- Tear in the dura beneath
- Haematoma in the deeper plane
- Injury to the cerebrum
- Injury to the venous sinuses—may cause life threatening haemorrhage. *Fracture should not be elevated* in such occasion, as it itself can precipitate bleeding
- Convulsions
- Meningitis

Investigations

- CT scan.



Fig. 27.12: Depressed skull fracture.

Treatment

- Antibiotics, anticonvulsants.
- *Elevation of the depressed fracture*: Burr holes are made in the adjacent normal skull. Fracture is elevated. Bony fragments and necrotic materials are removed. Dural tear is closed with interrupted sutures.

HYDROCEPHALUS

> ***The heads of children sometimes grow enormously large, the sutures give way, and the membranes of the brain are pushed up with the water within, and make a soft tumour rising above the edges of the sutures.... They daily become more and more stupid, with a pulse not above seventy-two.***
>
> **—William Heberden,** 1802

The blessing of health is realised on the sick bed.—Mr Tut-Tut

It is dilatation of ventricles due to blockage of cerebrospinal fluid flow (CSF) or due to increased secretion or due to defective absorption of CSF.

Classification I

- **Communicating type:** Ventricles communicate freely into the subarachnoid space.

  Here there is defective absorption of CSF following any inflammation, subarachnoid haemorrhage or trauma.
- **Noncommunicating type**: Obstruction is in the ventricle or its exit, due to any tumours or any inflammatory process.

Clinical Features

Bulging of anterior fontanelle, engorged scalp veins, separation of suture lines, *sun-setting sign* (decreased upward gaze), increasing head circumference, papilloedema, lethargy, ataxia.

Investigations

CT scan, ventriculography, air encephalography, MRI.

Treatment

- Tapping of lateral ventricles.
- Ventriculo-cysternostomy using polythene catheters—*Torkildsen operation.*
- Ventriculoatrial (VA) shunt.
- Ventriculoperitoneal (VP) shunt.



Figs 27.13A and B: Hydrocephalus child. CT scan head picture in hydrocephalus.

Classification II

Congenital	*Acquired*
Associated with spina-bifida and myelomeningocele. It is due to— • Failure of formation of CSF pathways • Arnold-Chiari malformation • Congenital stenosis of aqueduct of Sylvius • Presents with widening of sutures, tense fontanelles and decreased cortical thickness Enlargement of head occurs, either prenatal (can cause obstructed labour) or post natal	May be unilateral or bilateral (midline obstruction), due to— • Chronic meningitis • Trauma • Subarachnoid haemorrhage • Brain tumours—(pineal/cerebellar/craniopharyngiomas) • Colloid cyst of 3rd ventricle • Arachnoid cysts

INTRACRANIAL ABSCESS

Types

- ***Extradural abscess***: Caused by—
  - Osteomyelitis of skull.
  - Middle ear infection.
  - Frontal sinusitis.

  Pott's puffy tumour is subperiosteal swelling with infection and inflammation of the scalp. There is acute localized headache and tenderness in the skull, localized pitting oedema of the scalp usually in the frontal region.
- ***Subdural abscess***: is caused by septic thrombophlebitis from the frontal sinusitis or other infections. It is often very severe with extension into the venous sinuses.
- ***Intracerebral abscess***: is caused by
  - Extension from middle ear or sinuses.
  - Blood-born infection.
  - After intracranial injuries.

Common sites: Temporal lobe, cerebellum, frontal lobe.

It can be:

a. *Acute*—There is acute septic encephalitis without pus formation. It may cause ventriculitis or localized abscess formation

b. *Subacute*—Occurs in 3 weeks, by the formation of a glial wall, i.e. thickness is more near the cortex and less towards ventricle

c. *Chronic*—Occurs in 6 weeks with thick wall which may persist or may get enlarged behaving like a space occupying lesion

d. *Metastastic*—Abscess in brain occurs either in cerebrum (parietal or temporal lobes) or in ventricles (Ventriculitis is more dangerous and often fatal)

Clinical Features

- Evidence of focus of infections are seen, i.e. middle ear (CSOM), sinusitis.
- Focal neurological features are seen, depending on the location of abscess. In temporal lobe abscess features of dysphasia, contralateral hemiparesis are seen; in cerebellar abscess, all cerebellar symptoms are seen.
- Epilepsy.
- Features of raised intracranial pressure: a) slow pulse, b) rising BP, c) headache and vomiting, d) papilloedema, e) deterioration in level of consciousness, f) visual disturbances.

Differential Diagnosis

- Intracranial tumour.
- Tuberculoma.
- Meningitis.

Investigations

- CT scan.
- MRI.
- Carotid angiogram.
- Ventriculography.
- EEG.
- Isotope brain scan.
- Total count, ESR.
- Investigation specific for focus of infection.

Lumbar puncture should be avoided in acute abscess as coning can occur.



Fig. 27.14: Intracranial abscess. It needs drainage. It could be tuberculosis. It is a space occupying intracranial lesion, mimics malignancy often.

Treatment

- Antibiotics—high dose penicillins, benzyl penicillins are given.
- Burr hole exploration is done and Dandy's brain cannula is placed. Pus is aspirated and sent for culture and cytology.
- In case of chronic abscess, exploration of cranial cavity and excision of brain abscess is done.

Complications

- Intracranial hypertension
- Coning
- Neurological deficits

> *Disease is no absolute physical entity but a complete intellectual construction, an amalgam of biological state and social definitions.*
> —Charles E Rosenberg

INTRACRANIAL ANEURYSMS

Types

- ***Subclinoid type*** occurs in the internal carotid artery within the cavernous sinus. It causes ptosis, defective external ocular movements, 5th nerve palsy. It can cause carotid-cavernous fistula.
- ***Supraclinoid type*** is commonest type.
  - *Berry aneurysms: A congenital type* occurs in circle of Willis in relation to internal carotid artery [40% (most commonly at the origin of posterior communicating artery)], anterior communicating artery, middle cerebral artery, vertebro-basilar artery. It occurs due to weakness in the media of major arteries.
  - *Acquired aneurysms* due to atheromas, hypertension.
  - *Mycotic aneurysms* occurs due to infection in the wall of cerebral vessels, as a result of any bacteraemia.

Common sites are peripheral branches of middle cerebral artery.

Presentations

i. Subarachnoid haemorrhage
ii. Pressure effects
iii. Convulsions
iv. Eye and pupillary signs

Investigations

- CT scan.
- Carotid and vertebral angiogram.

Treatment

- Clipping or wrapping of aneurysms.
- Therapeutic embolization.
- Open neurosurgical approaches.

INTRACRANIAL TUMOURS

> ***There was discovered on (the corpus callosum) of the brain a remarkable round fleshy tumour like an acorn. It was hard and full of holes and was as large as a medium-sized apple. It was covered with its own membrane and was entwined with veins.... We perceived that this ball by compressing the brain and its ducts with its mass and by flooding them, had been the occasion of the lethargy and listlessness and finally of death.***
>
> **—Felix Platter,** 1614

Secondaries are the commonest malignant tumour in the brain. ***Metastasis occurs usually from lung (commonest), nasopharynx or from any other organ in the body.***

Secondaries in brain

- Commonest malignant brain tumor
- Primary are – Lungs (40%), breast (30%), melanoma (15%), others (15%)
- Usually multiple
- Headache, focal lesions, convulsions, hypertension, altered level of consciousness are the features
- CT scan, CT chest or evaluation of primary – needed
- Radiotherapy chemotherapy of particular primary is treatment
- Solitary metastasis can be removed surgically
- Steroids reduce the cerebral oedema and so symptoms



Fig. 27.15: Orbital secondaries from adrenal neuroblastoma.



Fig. 27.16: CT scan head showing brain secondaries.

Primary Brain Tumours

1. ***Gliomas* (43%).**
   - **a.** ***Astrocytomas*** are the commonest type. They are usually malignant. They can occur anywhere in the cerebral hemispheres, medulla, brainstem. Peak incidence is in 4th decade.

     They can be *diffuse, solid or cystic*. They contain star-shaped cells resembling adult neuroglial cells. Astrocytic gliomas are graded as *Grades I, II, III, IV based on the quantity of adult and primitive cells*.
   - **b.** ***Oligodendrogliomas***.
   - **c.** ***Spongioblastoma polare*** arises from the primitive spongioblasts, affects optic chiasma, third ventricle, hypothalamus. They are irremovable but are radiosensitive.
   - **d.** ***Medulloblastoma*** occurs in children, affecting vermis of the cerebellum which grows rapidly with seedling elsewhere in the brain.
   - **e.** ***Ependymomas***:Cells here resemble ependymal cells. It can occur through out the cerebral hemespheres.
2. ***Meningiomas* (18%):** They are usually globular, arising from the arachnoids. Tumour gets attached to the dura. It gets blood supply from dural arteries and veins, from emissary veins and veins of diploe and scalp. Along these veins tumour cells invade the bone, causing bone destruction and reactive hyperostosis.

   Meningiomas are *classified as fibroblastic, endothelial and angioblastic*.

   Sites:
   - Parasagittal
   - Frontobasal
   - Posterior fossa
   - Choroid plexus

   Microscopic: It contains whorls of spindle cells, with central hyaline material, with *psammoma bodies*.

Meningioma
- 18% common
- Arising from arachnoids
- Gets blood supply from dural vessels
- Invades the skull bone through emissary and diploe veins.
- Destruction and reactive hyperostosis of bone is common
- *Psammoma bodies* are often seen histologically
- CT/MRI diagnostic
- Surgery is the choice therapy
- It has got good prognosis

3. ***Schwannoma* (8%):** Common in auditory nerve, also called as *acoustic neuroma*.

   Occurs in the internal auditory meatus which projects into the cerebello pontine angle (C- P angle), compressing 5, 6, 7, 8th nerves. It presents with compressive features like unilateral deafness, trigeminal neuralgia, squint, cerebellar compression syndrome.
4. ***Pituitary tumours* (12%)**.
5. ***Craniopharyngiomas* (5%)**.
6. ***Blood vessel tumours* (2%)**.

Clinical Features

- Initial period of silent growth.
- Focal syndromes with epilepsy.
- Raised intracranial pressure with headache, vomiting, deterioration of level of consciousness, altered vision, slow pulse, high BP, papilloedema.
- Brain displacement and stage of coning.

Note: First sign in acoustic neuroma is loss of corneal reflex.

Specific Features

- Frontal lobe tumours: Personality and emotional changes, epilepsy of generalised type, contralateral facial weakness.
- Parietal lobe tumours: Jacksonian epilepsy, progressive hemiparesis, astereognosis, acalculia.
- Occipital lobe tumours: Aura of flashing of light in contralateral field, homonymous hemianopia.
- Temporal lobe tumours: Progressive aphasia, visual, auditory, smell and taste hallucinations, hemiparesis, superior quandrantic hemianopia.
- Midline tumours: Produces bilateral hydrocephalus.
- Tumours of the third ventricle (colloid cyst is common): Causes bilateral hydrocephalus, progressive cerebral atrophy, dementia, sexual precocity, endocrine disturbances.
- Pineal tumours: Causes precocious puberty.
- Cerebellar vermis tumours: Usually medulloblastomas, occur in young children, presents with progressive hydrocephalus and features of herniation of cerebellar tonsils through foramen magnum.
- Cerebellar hemisphere tumours: Commonly are astrocytomas, produce cerebellar syndromes, nystagmus.

A very bold surgeon is the one who realise that, his patient takes all the risks.



Fig. 27.17: CT scan head showing large meningioma frontal region.





Figs 27.18A and B: MRI brain showing glioma brain.



Fig. 27.19: MRI brain showing glioblastoma multiforma. It is very aggressive malignant tumour.



Fig. 27.20: Skull X-ray showing mass calcified lesion. It could be meningioma, dermoid extending intracranially.

Investigations

- X-ray skull.
  - Calcifications like in meningiomas, craniopharyngiomas.
  - Separation of sutures.
  - A beaten silver appearance.
  - Lateral displacement of pineal body.
  - Hyperostosis, expansion, destruction in skull bones.



Fig. 27.21: MRI brain showing pontine tumour.

- Isotope scan.
- CT scan.
- MRI.
- Positron Emission Tomography (PET).
- Carotid angiogram (Introduced by Egas Moniz).
- Ventriculography.
- EEG.



Figs 27.22A and B: Craniopharyngioma from sellar region.

Treatment

- Relief of raised intracranial pressure:
  a. Ventricular tap and drainage through a posterior parietal burr hole.
  b. Tapping of cystic tumours and abscesses.
  c. Administration of mannitol.
  d. Emergency decompression by partial removal of tumour.
  e. Steroid therapy—dexamethasone.
- Establishment of pathological diagnosis:
  a. Burr-hole and biopsy.
  b. Craniotomy and biopsy using brain cannula.
  c. Frozen section biopsy.
  d. CT guided stereotactic biopsy.
- Removal of benign tumours—by different craniotomy approaches.
- Decompressive surgeries for malignant tumours.
- Shunt surgeries to drain CSF—ventriculo-peritoneal shunt or ventriculo-atrial shunt.
- Radiotherapy—External radiotherapy is used as primary treatment or as a adjuvant therapy after surgery.
- Chemotherapy is occasionally used.

Prognosis

Tumour which is benign and surgically accessible has better prognosis.

PITUITARY TUMOURS

> ***A young student…suddenly (sleepy and lethargic) died in convulsions within two weeks. In his brain the ventricles were found swollen with blood… which had gone down to the base of the skull…. The olfactory bulbs were not swollen at all. The pituitary gland…was completely blocked by a…viscous and gelatinous mass about the size of a small bean… Hence a dropsy of the brain ensued.***
>
> **—Richard Lower,** 1672

Classifications I

1. *Eosinophil (Acidophil) adenomas*: Tumour is usually small. Rarely it causes compressive features.

   It secretes excess growth hormone causing acromegaly in adults and gigantism in children.

Truth always exists; only lies are invented.



Figs 27.23A and B: Acromegaly due to pituitary tumours. Note the operated scar in the frontal region.

2. ***Chromophobe adenomas***:are common in females and in the age group (20-50 years).

   Initially it is *intrasellar* and after sometime becomes *suprasellar*. Later, it extends *intracranially* often massively, causing features of intracranial space occupying lesion. It presents with myxoedema, amenorrhoea, infertility, headache, visual disturbances, bitemporal hemianopia, blindness, intracranial hypertension, epilepsy.

   Differential diagnosis: Meningiomas, aneurysms.

   CT scan, angiogram, X-ray skull are diagnostic.

   Treatment is surgical decompression by craniotomy through subfrontal approach or transphenoidal approach. Deep external radiotherapy and steroids are also used.
3. ***Basophil adenomas***: are usually small. They secrete ACTH and presents as Cushing's disease with all its features.
4. ***Prolactin-secreting adenomas***: causes infertility, amenorrhoea and galactorrhoea.

Classification II

- Hypersecreting
- Hyposecreting by compression and atrophy

Classification III

- Micronodular:Tumour size less than 10 mm
- Macronodular: Tumour size more than 10 mm

Stages

- Stage of intrasellar development
- Stage of suprasellar extension
- Stage of massive intracranial extension

Investigations

- X-ray skull: shows calcifications, destruction of sella turcica, mass lesion, enlarged pituitary fossa.
- CT scan.
- MRI.
- Hormone assay—like serum prolactin, growth hormone, ACTH, steroids, sex hormones, etc.

Treatment

- Surgery: By subfrontal craniotomy approach or transphenoidal approach.

  Care should be taken not to injure optic chiasma, arteries, cavernous sinus.
- External radiotherapy.

CRANIOPHARYNGIOMAS

They are large masses with cystic cavities, lined by ciliated epithelium containing cholesterol crystals. Areas of calcifications may be present and coral like masses may be formed. They are adherent to the basal arteries and adjacent nerves. They are *irremovable.* They are tumours of sellar region.

Clinical Features

- *Intrasellar craniopharyngiomas* inhibits sexual maturation causing obese, impotent dwarf with bitemporal hemianopia (due to compression of optic chiasma)—***Frolich's syndrome.***
- *Suprasellar craniopharyngiomas* produces Frolich's syndrome; pressure on hypothalamus which controls sleep and water metabolism (causes somnolence and diabetes insipidus).

- *Massive intracranial extension* causes intracranial hypertension and also hydrocephalus by obstructing CSF flow.

Investigations

- Skull X-ray shows calcification.
- CT scan is diagnostic.

Treatment

- Through craniotomy or through transphenoidal approach cystic tumours are evacuated.
- Ventriculoatrial shunt has to be done to drain CSF in case of hydrocephalus.
- Ventriculo cisternostomy—*Torkildsen's operation is done in cases of large masses blocking the 3rd ventricle obstructing the CSF outflow.*
- Radiotherapy.

MENINGOCELE

It is the herniation of meninges through a weak point of spine where bony fusion has not taken place effectively.

Swelling is covered with pia mater and arachnoid mater without dural covering and contains CSF.

Clinical Features

- Present since birth.
- Soft, cystic, fluctuant with transillumination.
- Signs of compressibility.
- Expansile impulse when asked to cough or when child cries.

Location

- Lumbosacral – commonest.
- Occipito cervical – 2nd most common.

Investigations

- CT scan head to look for hydrocephalus.
- MRI spine.

Treatment

Excision as early as possible. Transverse elliptical incision. Closure of defect by plication. Approximation of muscles.

Early closure prevents infection.

Complications

- Ulceration.
- Haemorrhage.
- Closure may cause hydrocephalous which needs shunting of CSF.

Meningocele	*Meningomyelocele*
• Membranes content • Soft, cystic • Brilliantly transilluminant • Longitudinal furrow absent • No neurological defect • Good prognosis after repair	• Membranes with nerve roots • Soft to firm • Non transilluminant • Longitudinal furrow is seen due to adherence of nerve roots • Trophic ulcer, bowel/urine incontinence, motor problems • Neurological deficit present • Not good results

SPINA BIFIDA

- It is failure of enfolding of nerve elements within the spinal canal during developmental period.
- It is usually seen in lumbo-sacral region. There is failure of fusion of one or more posterior vertebral arches.
- It is often associated with other anomalies.

Sites

- Lumbo-sacral
- Thoraco-lumbar

Types

a. ***Spina bifida occulta***—commonest type
   - There is dimpling of skin with dermoids, lipomas in the site. Impulse on coughing can be seen.
   - Initially there is no neurological deficit but later due to tethering, traction on dura, infection, can lead neurological deficits.

b. ***Spina bifida aperta***
   - Here neurological deficit is present. It may be *myelomeningocele* wherein spinal cord and nerve roots are in the sac. It may be *meningocele* wherein sac consists of meninges and fluid only.
   - Meningocoele is brilliantly transilluminant. Myelomeningocoele is not transilluminant.

> *The first sign of Pott's disease is deepened midline spinal sulcus at about T10 level due to increased muscular tonicity of sacrospinalis muscle. It is a NATURE'S PLASTER CAST.* —Francis E Jardine



Fig. 27.24: Spina bifida occulta. Note the dimple and tuft of hair.



Figs 27.25A and B: Spina bifida with protruding dermoid through the defect.

Clinical features

- Motor paralysis
- Sensory paralysis
- Visceral paralysis with incontinence of urine and faeces
- Swelling in the spine at the site of the lesion, may be lipoma or dermoid, with impulse on coughing
- Bony defect at the site
- Hydrocephalus.

Investigations

- Plain X-ray of the spine.
- CT scan/MRI of spine and head.

Treatment

- Correction of deformity.
- Maintaining the visceral function.
- Development of limb function.
- Ventriculo-peritoneal shunt or ventriculo-atrial shunt surgery for hydrocephalous.



Fig. 27.26: Infant with encephalocele. It is non-transilluminant whereas meningocele is brilliantly transilluminant.

INTERVERTEBRAL DISC PROLAPSE (IVDP)

- Herniation of part of the gelatinous nucleus pulposus through a rent in the annulus fibrosus, commonly at postero-lateral part which is a weak point.
- ***In cervical spine*** discs between C_5 and C_6; C_6 and C_7 are commonly affected impinging 6th and 7th nerves respectively.
- ***In lumbosacral region,*** discs between L_5 and S_1; L_4 and L_5 are commonly affected impinging first sacral nerve and 5th lumbar nerve respectively.
- Initially protrusion bulges through the pain sensitive posterior longitudinal ligament causing back pain.
- Later it herniates through the posterior ligament compressing the nerve causing typical root pain.

Types

- Postero-lateral is common.
- Central-posterior is not common. It is due to trauma. It is severe type, even though rare.

Secondary changes: Osteoarthritis of joints.


Intervertebral disc prolapse
Vertebra with nucleus pulposus and annulus fibrosis

Fig. 27.27: Intervertebral disc prolapse.

Clinical Features

- Pain in the distribution of the root which gets aggravated by straining, coughing, twisting, stooping.
- Pain radiates along the distribution of the nerve with tingling and numbness.
- Lumbar scoliosis is significant.
- Restricted forward flexion but free lateral flexion.
- Positive straight leg raising on the affected side with positive Lassegue's maneuver.
- Wasting in the muscles with blunting of sensation, with absence knee and ankle jerks.
- Loss of bladder sensibility and retention of urine.



Fig. 27.28: Intervertebral disc prolapse.

Differential Diagnosis

- Spinal cord tumours.
- Tuberculosis of the spine.
- Osteoarthritis.
- Ankylosing spondylitis.
- Spondylolisthesis.
- Vascular problems.
- Retroperitoneal and pelvic tumours.

Investigations

- X-ray spine both AP and lateral. It is not useful in acute prolapse.
- Myelography or Radiculography.
- CT scan.
- MRI is very useful method.

Treatment

- Rest in bed.
- Spinal jacket.
- Continuous or intermittent traction.
- Analgesics and relaxants.
- Intradiscal injection of the chymopapain enzyme which dissolves the fibrocartilaginous tissue and nucleus pulposus.
- Surgical treatment:
  Indications—
  - Persistent pain for 12 weeks which is not relieved by drugs.
  - Severe neurological disturbances like involvement of bladder, bowel or sexual functions.

  Surgery: Discectomy.



Fig. 27.29: Compression fracture spine – traumatic, pathological.

Great minds must be ready not only to take opportunities, but also to make them.

TUBERCULOSIS OF SPINE (CARIES SPINE)

- It is commonly of *secondary* type.
- Primary focus is in the lungs or lymph nodes.
- Commonly involved vertebra is dorsilumbar vertebra T_{10}.

Mode of infection: Mainly haematogenous.



Fig. 27.30: Tuberculosis of spine.

A. Tuberculosis of Cervical Vertebra

Common in C_6 and C_7 vertebra.

Clinical Features

- Pain in the neck, often referred to occipital region through suboccipital or posterior auricular nerves.
- Pain, when referred through anterior cervical primary rami causes *brachial neuralgia.*
- Rigidity in the neck.
- Patient supports the chin on the palm of his hand (*Rust sign*).
- Tenderness and paraspinal spasm with rigidity of the skull muscles.
- All passive and active movements of spine are painful and restricted.
- Cold abscess may be present in the neck, posterior to sternomastoid muscle or in the retropharyngeal region or in the axilla.
- Chronic tuberculous retropharyngeal abscess in midline, situated behind the prevertebral fascia. It is painless, soft, often causing dysphagia and dyspnoea.

Differential diagnosis

- Cervical spondylosis
- Congenital torticollis
- Secondaries
- Spinal cord tumours

Investigations

- X-ray cervical spine, chest X-ray.
- MRI is ideal.

Treatment

- Antitubercular drugs.
- Antero-lateral decompression of vertebra.
- Drainage of cold abscess.

B. Tuberculosis of thoraco-lumbar vertebra (Pott's disease, caries dorsilumbar spine)

Commonest site is dorsilumbar region —T_{10}

Reasons

- It is the junction of fixed (thoracic) and mobile (lumbar) segments of spine
- It bears the maximum stress
- It has got large amount of cancellous bone
- Bulky nucleus pulposus
- Relative avascularity of the body of dorsilumbar vertebra
- Close proximity to the thoracic duct through which infection can occur
- Adjacent prevertebral veins

Types

- ***Tuberculosis of the body of vertebra***
  - *Tuberculous metaphysitis*—Here contiguous surfaces of the vertebra are involved. It is the most common type in children.
  - *Tuberculous osteomyelitis* (central type—through central artery of the vertebra)—It occurs in the center of the body of vertebra.
  - *Tuberculous periostitis* (peripheral or periosteal)—It is seen in adults. It is situated deep to the anterior longitudinal ligament.
- ***Tuberculosis of the appendages***
  - Spinous process.
  - Pedicle.
  - Transverse process.
  - Lamina.

Features

- Contiguous surfaces of paired vertebra are involved.
- Lower half of one vertebra and upper half of adjacent vertebra below, with intervertebral joints are involved as they share a common blood supply.
- Destruction of the vertebra and intervertebral disc; collection of caseous material behind the anterior longitudinal ligament.



Fig. 27.31: Tuberculosis of spine. Note the area of involvement.

Pathology

- Tuberculous endarteritis
- Decreased blood supply
- Formation of tubercles with caseation
- Destruction of bone
- Failure of subperiosteal new bone formation

Effects

1. Deformity—*Kyphosis (Gibbus*) is excessive posterior curvature of the spine. It is due to complete anterior collapse of the vertebra.
2. *Cold abscess* formation—
   a. Close to the midline, when caseating material passes through the medial dorsal cutaneous nerves.
   b. Away from the midline, when caseating material passes through the lateral cutaneous nerve.
   c. Cold abscess may form in relation to psoas muscle (in dorsilumbar or lumbar).

      It passes through psoas sheath. It causes psoas spasm causing flexion of hip with inability to extend. If abscess extends below the inguinal ligament, then it is cross-fluctuant.
3. Spinal cord involvement—causes *paraplegia* (10%). This is common in thoracic spine, as the spine is narrow.
   a. *Early paraplegia ('Paraplegia in flexion' , 'paraplegia with active disease'*).

      It is due to –
      - Pressure by caseating material, granulation tissue and sequestrum.
      - Tuberculous meningitis.
      - Spinal cord oedema.
      - End arteritis of segmental spinal artery.
      - Pressure from distended disc.
   b. *Late paraplegia* (*'Paraplegia with a healed disease', 'paraplegia with extension').*

      It is due to –
      - 'Gibbus' causing stretching of the spinal cord.
      - Longitudinal shrinkage of the spinal cord due to gliosis.

Clinical Features

- Pain in the back, often with tingling sensation along the distribution of nerve roots.
- In upper thoracic tuberculosis, typical *'military attitude'* with raised shoulder which is drawn backwards is seen.
- Kyphosis (*gibbus)* is the commonest deformity. It can be angular but also can be rounded.
- Tenderness in the spine with paraspinal spasm.
- All active and passive movements of spine are restricted.
- *'Coin test'*—inability to pick up a coin is positive.
- Weakness and decreased power in the limb muscles, with altered sensation.

Investigations

- X-ray spine shows—
  - Narrowing of the disc space.
  - Wedging of the vertebra.
  - Rarefaction of the adjacent vertebra.
  - Soft tissue shadow of cold abscess.
- Chest X-ray PA view.
- ESR.
- Radio-isotope bone scan.
- CT scan or MRI of spine.

> *No head injury is so slight that it should be neglected, or so severe that life should be despaired of.*
> —Hippocrates, Father of Medicine



Figs 27.32A and B: Typical tuberculosis of spine involving L4 and L5 spine X-ray features.

Differential Diagnosis

- Secondaries in the spine.
- Spinal tumours.
- Scheuermann's disease (osteochondritis).
- Old compression fracture of the vertebra.
- Ankylosing spondylitis.

Complications of pott's spine

- Kyphosis
- Cold abscess
- Paraplegia
- Sinus formation
- Dissemination

Treatment

- Antituberculous drugs for one year.
- Rest with plaster jacket (SPICA).

Patient gains weight, X-ray shows re-calcification and healing. ESR becomes normal. Pain and spasm disappears.

Indication for surgery

- When the disease is progressive
- When there is neurological manifestation
- Cold abscess formation

Surgeries

Note: **No posterior approach, no laminectomy for TB spine.**

- Antero-lateral approach and costo-transversectomy with removal of all caseating material with bone grafting.
- Drainage of cold abscess.
- Posterior spinal fusion using bone graft. Bone graft is taken from the iliac crest.

SPINAL TUMOURS

Classification

A. *Extradural tumours*

- Commonest is secondaries.
  - They lie between the dura, bone and ligamentum flavum.
  - Primary sites are bronchus, breast, prostate, kidney. Rare extradural tumours are sarcomas, osteoclastoma, chondroma, lipoma.



Fig. 27.33: MRI spinal cord showing spinal cord tumour—ependymoma.

B. *Intradural tumours*

1. *Extramedullary* (75% of intradural)
   - Neurofibromas are the commonest, more common in males.
     - Arises from the posterior nerve root. It can be 'dumb-bell' tumours.
   - Spinal meningiomas are seen exclusively in females.
2. *Intramedullary* (25% of intradural)
   - Commonest is diffuse gliomas (50%).Others are ependymomas, vascular malformations.
   - Common in cervical cord.

Clinical Features

- Weakness of limbs, often with paraplegia.
- Tingling and numbness.

- Disturbance in micturition.
- Changes in tendon reflexes.
- Pain in the back.

Spinal cord or cauda equina compression is a surgical emergency.

Investigations

- X-ray shows widening of space and destruction.
- Myelography.
- Lumbar puncture *per se* has no role, as it is dangerous.
- CSF below the block may be yellow and proteinaceous and is called as *'Frolin's syndrome'.*
- Protein levels in lumbar CSF is usually raised in the presence of lumbar tumours, commonly 'Schwannomas'.
- CT scan.
- MRI.

Surgery

- Surgery is the main treatment—*Decompression of spinal cord and removal of tumour* by doing laminectomy.
- Adjuvant therapy: Radiotherapy and chemotherapy.
- Intrathecal methotrexate is also beneficial.

Self-assessment Questions

- Discuss a case of severe head injury brought to casualty.
- How will you assess a case of head injury? Discuss the management.
- Lucid interval.
- Brain oedema.
- Effects of head injury.
- Late effects of head injury.
- Subdural haematoma.
- Chronic subdural haematoma.
- Extradural haematoma.
- Raised intracranial pressure.
- Subarachnoid haemorrhage.
- Cerebral abscess.
- Tuberculosis of brain.
- Hydrocephalus.
- Glasgow coma scale.
- Depressed skull fracture.
- Pott's puffy tumour.
- Meningioma.
- Subdural hygroma.
- Spinal headache.
- Kernohan's effect (notch).
- Berry aneurysms.

Always look at what you have left; never look at what you have lost.

28

Thorax

Chest injuries
Pleural tap
Bronchoscopy
Flail chest
Pneumothorax
Tension pneumothorax
Haemothorax
Empyema thoracis—*Empyema necessitans*
Lung abscess
Intercostal tube drainage
Shock lung
Pulmonary embolism
Lung cysts—*hydatid cyst*
Mediastinal tumours—*Thymomas*
Pancoast tumour
Chest wall tumours
Pericarditis
Pericardial tap
Cardiac tamponade
Diaphragmatic hernia
Pulmonary complications during postoperative period
Surgical management of pulmonary tuberculosis

CHEST INJURIES

Types

- Crush injuries involving lung, pleura, ribs.
- Single rib fracture.
- Two or more rib fractures.
- *Steering wheel injury*—causes multiple rib fractures, bilaterally often with flail chest, with fracture dislocation of upper end of sternum.
- Stove in chest or flail chest.
- Traumatic pneumothorax.
- Haemothorax, haemopneumothorax, with fracture ribs.
- Tension pneumothorax.
- Pericardial, cardiac injuries and rupture of bronchus.
- Associated injuries in liver, spleen, diaphragm, major vessels.

Causes

- Road traffic accidents.
- Industrial accidents.
- Blast injuries.
- Crush injuries.
- Stab injuries.
    - In children, ribs are malleable and so fracture ribs are rare.
    - In elderly because of rigid ribs fracture is common.
    - First and second ribs are protected by clavicle and so their fracture is uncommon.
    - 11th and 12th ribs are floating ribs and so their fracture is rare.

Classification of Chest Injuries

As per the *American College of Surgeons Committee on Trauma* chest injuries are classified as—

1. Immediately life-threatening injuries.
2. Potentially life-threatening injuries.

Immediately life threatening injuries	*Potentially life-threatening injuries*
1. Air-way obstruction	1. Tracheo-bronchial disruption
2. Tension pneumothorax	2. Aortic disruption
3. Open pneumothorax	3. Diaphragmatic disruption
4. Massive pneumothorax	4. Esophageal disruption
5. Cardiac tamponade	5. Cardiac contusion
6. Flial chest	6. Pulmonary contusion

Pathological Effects of Chest Injuries

Immediate	*Late*
Hypoxia	Empyema, fibrothorax
Hypercarbia	Lung abscess
Acidosis	Mediastinitis
Hypovolemic shock	Cardiac arrhythmias
Bronchospasm	

Clinical Features of Thoracic Injuries

- History of trauma, painful breathing, cough, haemoptysis, pain in the chest wall, sometimes external wound may be present (in communicating wounds).
- Features of shock when major vessels are involved, i.e. tachycardia, hypotension, cold periphery.
- Respiratory distress—tachypnoea, cyanosis, respiratory difficulties.
- Tenderness over the fracture site.
- Dullness on percussion with decreased breath sounds signifies haemothorax. Resonant with decreased breath sound confirms pneumothorax.
- Surgical emphysema with palpable crepitus may be present.

Investigations

- Chest X-ray shows haemothorax, pneumothorax, fracture ribs.
- Hb%, PCV to assess blood loss.
- Blood grouping and cross matching.
- Blood gas analysis, i.e. PO_2 and PCO_2.
- U/S abdomen to look for associated abdominal injuries.

Treatment

Initial First Aid

- *Airway:* Prevention of aspiration, plastic airway, intubation, tracheostomy.
- *Breathing*: ICT placement, supportive measures.
- *Circulation:* Fluid therapy, CVP line, blood transfusion.
- Look for disability.
- Expose the patient properly for proper breathing and assisting.
- Assess the patient properly.
- Examine the patient thoroughly.
- Evaluate the patient for associated injuries like of head, abdomen, fracture limbs, spine.

Further Treatment

- Fracture rib without complication is treated with analgesics and rest.
- Haemothorax, pneumothorax should be treated with ***intercostal tube drainage*** (ICT) with under-water seal.
- Flail segment should be treated accordingly.
- Blood transfusion is done whenever required.
- Antibiotics like penicillin, cefotaxime, etc. to prevent infection.
- Nasal oxygen, throat suction.
- Ventilator support with IPPV (Intermittent positive pressure ventilation), with regular monitoring of blood gas.
- Tracheostomy/endotracheal intubation is done whenever required.
- Antibiotics, bronchodilators, often steroids are other supportive measures required.

Indications for thoracotomy

- Haemothorax more than 1500 ml found when ICT is placed or hourly collection in ICT is 200-300 ml
- ICT placed shows persistent drainage of blood
- Diaphragmatic injury
- When associated with liver and spleen injuries
- Bronchus and major vessel injuries
- Haemopericardium
- Oesophageal and thoracic duct injuries

Principles of Management of Chest Injuries

- Pulmonary physiotherapy.
- Aspiration of secretions—trachea, nasotracheal, oral, pharyngeal.
- Pain relief—oral narcotics, intercostal nerve block, epidural anaesthesia.
- Respiratory supports—encourage coughing, chest percussion, deep inspiration efforts, humidification, mobilisation.
- ICT placement for haemo/pneumothorax.
- Management of shock.
- Focused abdominal sonography on trauma (FAST).
- Surgery when indicated—thoracotomy and proceed.
- Management of complications—DVT and embolism, tracheostomy problems, ICT problems, sepsis, ARDS, empyema treatment, bronchopleural fistula, bronchial stenosis, chylothorax, clotted haemothorax, atelectasis.

There are no disease of aged but diseases among the aged.—Leonard Larson

Complications

- Infections—empyema, lung abscess, pneumonia, septicaemia.
- Respiratory failure.
- Traumatic asphyxia.
- Traumatic shock lung.
- Disseminated intravascular coagulation (DIC).
- ARDS (Adult Respiratory Distress Syndrome).

PLEURAL TAP

Indications

- Pleural effusion—both for diagnostic as well as therapeutic purpose. The fluid is sent for culture, cytology, microscopy, specific gravity, biochemical analysis of proteins for diagnosis of tuberculosis, malignancy.
- In empyema thoracis, for diagnostic purpose before placing an ICT.



Fig. 28.1: Sites of pleural tap.

Position

In sitting position, leaning forward over a wooden support.

Site

Tip of scapula at 7th intercostal space (posteriorly).
Under local anaesthesia wide bore needle (Abraham needle) is passed to tap the fluid.

Complications

- Infection
- Dry tap or bloody tap
- Sudden vagal shock
- Pain and respiratory distress



Fig. 28.2: Position for pleural tap is sitting and leaning forward over a support. Site is below the scapula, posteriorly through the seventh intercostal space.

BRONCHOSCOPY

Indications

Diagnostic: To take biopsy in conditions like carcinoma lung, lung abscess, pulmonary tuberculosis.

Therapeutic: To remove foreign body, to suck out the bronchial secretions.



Fig. 28.3: Foreign body in trachea. This can be removed using a bronchoscope. Patient may develop collapse of lung, pneumonia, respiratory failure and ARDS.



Fig. 28.4: Bronchoscope.

Types

- *Rigid bronchoscopy*—It is used for removal of foreign body and bronchial wash. It reaches up to third generation bronchioles. It is used to take biopsy from carcinoma of proximal divisions but not from carcinoma of peripheral lung. Rigid scope has got multiple holes to allow ventilation during the procedure (Oesophagoscope does not have side holes). It is done under general anaesthesia.
- *Flexible bronchoscopy*—It reaches up to 5th generation bronchioles. It can be done under local anaesthesia. It is mainly used for diagnosis and biopsy.

Complications

- Bleeding
- Infection
- Perforation
- Bronchospasm

FLAIL CHEST AND STOVE IN CHEST

- It is fracture *of two or more consecutive ribs*, with each rib having *two or more* fracture sites. Such segment is called as ***flail segment.***
- **Stove in chest** is depression of a portion of chest wall due to severe chest injury, otherwise features and management are like flail chest.

Pathophysiology

Flail segment moves independent of the adjacent thoracic cage. During inspiration flail segment moves inwards (unlike normal thoracic cage which moves outward), and during expiration the segment moves outwards (unlike normal cage which moves inward) causing pathophysiological derangements.

- This *paradoxical respiration* causes reduction in ventilatory lung surface and so respiratory dysfunction.
- *Mediastinal flutter*: Movement of mediastinum during different phases of respiration occurs, often causing kinking of great vessels and sudden cardiac arrest.
- *Pendular movement of air* from one lung to other occurs, and thus preventing atmospheric air to get into both injured and otherside normal lung leading to respiratory failure.
- All these derangements gets aggravated by *haemothorax, pneumothorax* and other associated injuries.
- There is *hypoventilation:* carbon dioxide retention and respiratory failure.

First Aid

The paradoxical movement of flail segment is prevented by applying pressure over it using hand or clothes (It is often life saving.) It makes other lung function adequately.

Investigations

- Chest X-ray—to identify the fracture segment.
- Blood grouping.
- Arterial PO_2 and PCO_2 and serum electrolytes.

Treatment

- Intercostal tube drainage.
- Applying clips to fracture ribs and fixing above and below to normal ribs.
- Antibiotics like penicillins, cefotaxime.
- Blood transfusion, IV fluids.
- Bronchodilators, steroids.

Flail chest

Derangements	*Types*	*Problems*
• Paradoxical respiration • Mediastinal flutter • Pendular movement of air • Pulmonary contusion	• Anterior—near costochondral junction • Lateral—in rib shafts • Posterior—safer, due to support of scapula	• Cardiac arrest • Respiratory failure • Haemothorax • Infection • ARDS

Experience teaches slowly at the cost of mistake.

- Ventilator support with IPPV—IPPV is treatment of choice. Assisted ventilation is required for several days until the chest wall stabilises. If ventilator support is required for more than 10 days, then tracheostomy is done to prevent laryngeal stenosis which can occur due to prolonged endotracheal intubation.
- Thoracotomy—when required only.

Non-traumatic rib fracture
- Stress fracture
- Metastatic fracture
- Metabolic cause like hyperparathyroidism
- Osteogenesis imperfecta
- Child abuse
- Old age—osteoporosis

PNEUMOTHORAX

> ***The means we possess of reducing (a diseased lung) to a state of collapse, or of divesting it for a time of its peculiar functions, are equally simple and safe. In those cases in which the disease is placed in one of the lungs only, the remedy (i.e. induced pneumothorax) would appear to be simple, safe, and complete***
>
> —**James Carson,** 1820

It is the presence of air between the layers of pleura.

Classification I

a. Pneumothorax.
b. Hydropneumothorax.
c. Pyopneumothorax.
d. Haemopneumothorax.
e. Artificial pneumothorax.
f. Tension pneumothorax.

Classification II

a. Open pneumothorax
b. Closed pneumothorax
    - Simple
    - Tension

Causes

- Traumatic.
- Spontaneous.
    1. Tuberculous.
    2. Non-tuberculous:
        a. Rupture of emphysematous bullae.
        b. Rupture of solitary lung cyst.
        c. Honeycomb or cystic lung.
        d. Idiopathic.



Fig. 28.5: Plain X-ray chest PA-view showing air-fluid level and collapsed lung margin (Hydropneumothorax).

Spontaneous pneumothorax can be acute, chronic, recurrent.

Clinical Features

Hyperresonant, absence of breath sounds, tracheal deviation.

Chest X-ray reveals
- Radiolucency on the affected side
- Absence of lung markings
- Collapsed lung margin

Treatment

- In tension pneumothorax, emergency needle aspiration is done followed by ICT placement.
- ICT placement.
- The cause is treated.
- Often thoracotomy is required, if there is persistent broncho-pleural fistula or ruptured cyst or bullae.

TENSION PNEUMOTHORAX

- During inspiration, air is pumped into the pleural cavity through a valvular opening in the visceral pleura and underlying injured lung.
- Lung collapses first, and as air continuously collects in the pleural cavity, mediastinum shifts towards the opposite side, further decreasing the volume of the functioning lung.

- Further increase in the pleural pressure, reduces the venous return, atrial filling, and ventricular filling and so cardiac output and cardiac function.



Fig. 28.6: Emergency decompression through 2nd intercostal space.

It causes sudden death and hence emergency treatment is required.

Clinical features

- Tachypnoea and tachycardia
- Decreased/absent breath sounds
- Resonant on percussion with severe mediastinal/tracheal shift
- Cyanosis and hypotension
- Chest pain

Management

- *Once clinically diagnosed, a wide bore needle is immediately placed in the second intercostal space in midclavicular line*, and a sterile glove is kept on the hub (blunt) end of the needle to create a valve so as to prevent inward sucking of air from outside.
- Nasal oxygen is used.
- Once patient is better, chest X-ray is done.
- Later an intercostal tube is passed.
- Antibiotic, analgesics are given.
- In severe cases ventilator support with IPPV is required.

HAEMOTHORAX

It is blood in pleural cavity. It causes pain, shock, as it is very irritant to pleural cavity.

It is a good culture media for bacteria and so infection is quite common.

Causes

- Trauma.
- Postoperative: pulmonary, cardiac, oesophageal surgeries, cervical sympathectomy, leak from CVP monitor line.
- Tumours of lung, mediastinum, pleura.
- Leaking aneurysms.
- Spontaneous.

There may be rib fractures in traumatic haemothorax.

Clinical features

- Pain in the chest, tenderness
- Difficulty in breathing, dullness on percusion diminished breath sounds
- Features of shock

Investigations

- Chest X-ray.
- Aspiration (pleural tap).
- Chest CT scan.

Treatment

1. ICT placement in the mid-axillary line in the 6th intercostal space.
2. Antibiotics, bronchodilators.
3. Thoracotomy—

Indications of thoracotomy:

1. Initial chest tube output of 1500 ml of blood or persistent drainage of 200-300 ml/hr.
2. Clotted haemothorax is difficult to manage. It requires thoracotomy, evacuation and decortication of lung. Initially liquefaction of the clot is tried by infusing of streptokinase and trypsin into the pleural cavity

Complications

- Infection and empyema.
- ARDS: respiratory failure.

EMPYEMA THORACIS

The pleurisie is an inflammation of the membrane, investing the ribs, caused by subtile and cholerick blood…. If it tend to suppuration, it commonly infers a pricking pain, a fever and difficulty of breathing…. If nature being too weak…the disease is turned into an empyema, wherefore the Chirurgeon must then be called, who…may make a vent between the third

For all the happiness mankind can gain, is not in pleasure but in rest from pain.—Dryden

> ***and fourth true and legitimate ribs…. The pus or matter must be evacuated by little and little at several times; and the capacity of the chest cleansed from the purulent matter.***
>
> **—Ambroise Paré,** 1575

It is collection of pus in pleural cavity.



Fig. 28.7: Causes of empyema.

Causes

An empyema is never primary.

Secondary causes are:

- From chest wall: Wounds, osteomyelitis of ribs.
- From lung: Pneumonia, abscess, bronchiectasis, tuberculosis, growth.
- Postoperative: After thoracotomy.
- From oesophagus: Perforations, carcinoma.
- From below diaphragm: Subphrenic abscess.

Tuberculosis and pneumonia are common causes in developing countries.

Pathology

Stages of empyema

1. Acute empyema
2. Subacute empyema
3. Chronic empyema

Initially serous fluid collects, which eventually becomes purulent. Intrapleural clotting of pus occurs with thickening of pleura and later fibrinous adhesion forms resulting in matured empyema.

Chest is withdrawn inwards and is immobile, mediastinum is drawn inwards, diaphragm gets elevated.

It leads to rigid contracted immobile chest with functionless lung underneath—*frozen chest*. Often pus perforates through intercostal space and forms *empyema necessitans*.

Organisms: Initially staphylococci, streptococci, pneumococci, and later *E. coli*, *Pseudomonas*, drug-resistant staphylococci.

Clinical types

- Acute empyema
- Acute fulminant toxic empyema
- Subacute empyema
- Chronic empyema
- Latent empyema
- Persistent empyema
- Empyema necessitans
- Chronic empyema with sinus
- Interlobar empyema

Pathological types

- Exudative
- Fibrinopurulent
- Organising

Anatomical types (Depending on the anatomical location)

- Apical
- Mediastinal
- Interlobar
- Diaphragmatic
- Lateral

Clinical Features

- Pain in the chest, tenderness, fever.
- Difficulty in breathing.
- Features of toxicity in acute type of empyema.
- Dullness on percussion, absence of breath sounds.
- Decreased chest wall movement.

Complications

- Frozen chest(functionless lung)
- Empyema necessitans
- Osteomyelitis/chondritis of ribs or vertebra
- Pericarditis
- Mediastinitis
- Bronchopleural fistula
- Dissemination of infection

Investigations

- Chest X-ray, ESR.
- Peripheral smear.
- Diagnostic aspiration.
- Pus C/S, AFB.
- Bronchoscopy.
- CT scan and MRI for carcinoma bronchus.

Treatment

Stage 1
- Antibiotics.
- Repeated aspirations.
- Intercostal tube drainage.
- Antituberculous drugs.

Stage 2
- ICT drainage.
- Rib resection *(Eloiser's method)*.
- Antibiotics, antituberculous drugs.
- Respiratory physiotherapy.

Stage 3
- ***Decortication*** *is very* useful and favourable method. Here, thickened pleural sac is stripped off from the lung through thoracotomy approach.
- Often ***lobectomy*** may be required, rarely pneumonectomy is done.
- Physiotherapy, antibiotics, ATD'S are also essential.

EMPYEMA NECESSITANS



Fig. 28.8: Empyema necessitans.

It is a complication of empyema thoracis, *wherein empyema* which is not drained perforates through the chest wall presenting as subcutaneous collection of pus communicating directly or often with a tortuous route with the pleural cavity.

Causes

- Neglected empyema either of tuberculous or non-tuberculous aetiology.
- Following incomplete aspiration of pus of empyema through a thin needle—needle track itself allows pus to form a track and leads to *empyema necessitans*.

Clinical Features

A diffuse, tender, smooth, soft, fluctuant, swelling in the intercostal space having *impulse on coughing*.

Features of empyema necessitans
- Bulge in the intercostal space
- Restricted movement of chest wall
- Tenderness
- Dullness on percussion without breath sounds
- Impulse on coughing

Investigations

- Chest X-ray.
- Total count is increased.
- ESR.

Treatment

- Antibiotics.
- Empyema is drained by placing an ICT. Pus is sent for C/S and AFB.
- If it is tuberculous, antitubercular drugs are started.
- Empyema necessitans subsides on its own when empyema is treated.
- But often may require separate incision and drainage when track is tortuous.

LUNG ABSCESS

- It is localised suppuration in the lung with tissue necrosis.
- It is end-stage of suppurative pneumonitis with thrombosis of associated artery.

Aetiology

- Pneumonias due to *Streptococcus, Pneumococcus, Haemophilus, Staphylococcus,* anaerobic and other bacteria.
- Bronchial obstruction due to tumours or foreign body.
- Chronic upper respiratory infection due to sinusitis, tonsillitis and dental infection (anaerobic infection).
- Septicaemia.
- Aspiration.

As pus accumulates, tension increases inside the abscess cavity causing spread into other areas of the lung or may rupture into the bronchus.

Note: Lung abscess secondary to aspiration is commonly seen in apical lower lobe.

> *Clubbing is frequently present in those with a chronic discharging empyema sinus.*
> —Hippocrates, Father of Medicine

Clinical features

- Acute onset of fever, but often it is recurrent in nature
- Cough with expectoration
- Haemoptysis with foul smelling sputum.
- Chronic illness with debilitation
- Pleuritic pain

Complications

- Spread into other areas of the lung.
- *Metastatic cerebral abscess*—Lung abscess is the *commonest* focus for metastatic cerebral abscess. Occurs as a result of pyaemic emboli through paravertebral veins.
- Haemorrage, may be torrential due to erosion of the vessel in the abscess wall.
- Empyema thoracis.

Differential Diagnosis

- Pulmonary tuberculosis.
- Carcinoma lung.
- Fungal infections like aspergillosis.
- Pneumoconiosis.
- Lung cysts.

Investigations

- Chest X-ray shows localised opacity with smooth margin and fluid level.
- Bronchoscopy and biopsy is done to rule out carcinoma.
- Sputum for culture, AFB and cytology.
- CT scan.



Fig. 28.9: CT scan of lung showing right-sided lung abscess with fluid level.



Figs 28.10A and B: Lung abscess X-ray picture and CT of the same patient.

Treatment

Medical

1. Appropriate *high dose antibiotics* are started depending on sputum culture like penicillins, third generation cephalosporins like cefoperazone, ceftriaxone *for 3-6 weeks.*
2. *Postural drainage* for 2-3 hours, 3 times daily.
3. *Periodic culture* of sputum is done to study the response of treatment.
4. 80-90% of acute abscesses resolve by medical therapy.

Surgical

1. External surgical drainage with rib resection is done in severe acute lung abscess only. Not commonly used procedure.
2. *Lobectomy* is done when medical treatment fails.

INTERCOSTAL TUBE DRAINAGE

It is the method of draining fluid collected in the pleural cavity safely, so as to allow the underlying lung to expand.

Indications

- Haemothorax
- Pneumothorax
- Haemopneumothorax
- Empyema thoracis
- Traumatic lung contusion
- After thoracotomy, to drain pleural cavity

Procedure

- **Sites:** An ICT is placed in 6th intercostal space in midaxillary line for haemothorax and pyothorax; in 3rd or 4th space in midaxillary line for pneumothorax.



Fig. 28.11: Intercostal tube drainage under water seal.

- Under local anaesthesia, a small incision is made in midaxillary line (as the muscle bulk is less here and so passage of ICT is easier), parallel to intercostal space (above the rib, i.e. in lower part of intercostal space so to avoid injury to neurovascular bundle which are located in the groove in the lower part of rib). Tube with side openings is pushed into the pleural cavity.
- Other end is connected *to under water seal. Air-water column moving* with respiration can be observed. Tube is fixed with skin sutures.
- Usually for pneumothorax, ICT is kept for 2-3 days (till lung expands—confirmed by—repeat chest X-ray). For haemothorax and pyothorax it is kept for 4-6 days or until it stops draining and lung expansion is confirmed by repeat chest X-ray.
- To have proper expansion of lungs, patient is asked to blow football bladder (balloon) and do breathing exercise. If there is bronchopleural fistula, ICT should be placed for a longer time, until the fistula heals.



Fig. 28.12: Intercostal tube drainage showing haemothorax.

Complications

- Infection.
- Displacement and inadequate functioning.
- Injury to intercostal vessels and bleeding.
- Pain at the site of ICT placement.

SHOCK LUNG (Stiff lung)

Causes

- Major chest trauma.
- Septicaemia.
- Massive blood transfusions.
- DIC.

> *The patient dyspnoeic due to pulmonary embolism prefers to lie flat.*—Ronald Gibson

Pathogenesis

Development of microthromboembolism in small lung vessels following extensive intravascular coagulation, leading to pulmonary consolidation, which reduces the lung compliance markedly, causing severe depression of gas exchange in the lung —***a stiff lung****.*

It has got high mortality as lung cannot expand at all. Outcome is fatal if emergency treatment is not given.

Treatment

- Endotracheal intubation.
- Ventilator support with IPPV.
- Antibiotics.
- High dose of steroids.
- Monitoring the patient with PCWP and cardiac monitor.
- Bronchodilators.
- The cause is treated.

PULMONARY EMBOLISM (PE)

> ***From my Stanford days… I had known that excessive bed rest gave rise to thromboembolic complications…. The death rate from thromboembolism was always much less at the County Hospital than it was at Stanford Hospital…. When (the County Hospital patients) got up to go to the bathroom, (they) dislodged only tiny clots from their veins and these did not harm them when they got to the lungs and were dissolved, while the wealthier patients (at Stanford) who remained in bed and formed large clots in their legs and pelvises suffered the major consequences of large pulmonary emboli.***
>
> —**William Dock,** 1984

- It is due to deep venous thrombosis (DVT) which gets detached to cause pulmonary embolism.
- It may be from femoropopliteal or ileo-femoral region.

  The thrombi most commonly develop in the leg veins due to stasis and hypercoagulable state. They subsequently enlarge and propagate proximally, dislodge to form emboli.

Types

- **Small emboli**: Causes pulmonary hypertension of features of bronchopneumonia.
- **Medium emboli** lodges in branches of pulmonary artery causing chest pain, haemoptysis, dyspnoea.
- **Large (massive) emboli** causes block at bifurcation of pulmonary artery trunk or right/left pulmonary artery leading to sudden chest pain, severe dyspnoea, shock, raised venous pressure and ***sudden death.***

Effects of pulmonary embolism

- Decreased cardiac output
- Pulmonary vasospasm and pulmonary hypertention
- Bronchospasm
- Defective oxygenation of blood

Risk Factors

- Postoperative and trauma patients who are bed ridden.
- Pregnant women.
- Old age.
- Obesity and heart disease.
- Varicose veins.
- All aetiologies which cause DVT.
- Carcinoma.

Clinical features

- Dyspnoea, chest pain and haemoptysis
- Tachycardia, tachypnoea and cyanosis
- Pleural rub and cardiac gallop

Investigations

- Chest X-ray PA view—hyperlucency in an area of oligaemia—*Westermark sign.*



Fig. 28.13A: Chest X-ray showing wedge shaped pulmonary infarct.

- CT scan and MRI—can detect PE.
- Pulmonary angiography: It is diagnostic (100%).
- Arterial blood gas analysis.
- Isotope radionuclide ventilation—Perfusion (V/Q) Lung scanning:While normal scan rules out PE, evidence of V/Q mismatch is highly suggestive of pulmonary embolism.
- Doppler study and venogaphy—To rule out DVT.

Management

- Thrombolytics: Streptokinase, 6 lakhs units to begin with and later one lakh units hourly.
- Pulmonary embolectomy with or without bypass by immediate thoracotomy.
- Venous thrombectomy using Fogarty catheter.
- Ventilator support.
- To prevent further embolisation of embolus into the lungs, IVC filters can be placed.
- Treatment of DVT.

Note: Heparin should not be combined with thrombolytics.

SURGICAL EMPHYSEMA

It is collection of gas/air in the subcutaneous or and fascial planes.

Causes

- Lung injury.
- Tracheal injury.
- Chest wall injury.
- After laparoscopic procedure.



Fig. 28.13B: Chest X-ray PA and lateral views showing surgical emphysema.

Types

- Localised.
- Generalised—extensive in the neck, face, eyelids, chest wall, etc.

Features

- Pain, diffuse swelling of the subcutaneous region.
- Palpable *crepitus* is diagnostic.
- X-ray chest and neck is confirmatory.

Treatment

- Conservative treatment—treat the cause.
- In severe cases—ICT one side or both sides placement.

LUNG CYSTS

Types

- Epithelial cyst
- Emphysematous cyst
- Parasitic cyst (Hydatid cyst)
- Pseudocyst of the lung

Pseudocyst of the lung: It occurs in a cavity due to tuberculosis, lung abscess or *Staphylococcus* pneumonia.

Epithelial Cyst

- It is of d*evelopmental* origin.
- It can be large single cyst or small, multiple cysts.
- It is lined by *respiratory epithelium.*
- It is often associated with cervical rib or cardiac anomalies.
- It is common in *infants and children.*
  - Usual *clinical features* are dyspnoea and chest pain. When infected, presents with fever, cough and haemoptysis.
  - *Treatment* is excision of the cyst. Antibiotics are given when infected.
  - *Here spontaneous pneumothorax is uncommon. Infection and haemorrhage are common.*

Emphysematous Cyst

- *It is a progressive disease of lung with rupture of alveolar wall and distension with air.*
- It is an *acquired* condition.
- Cyst *does not have epithelial lining.*
- Compression of adjacent lung tissue with poor gaseous exchange is common.

Usual *clinical features* are dyspnoea and severe, persistent cough.

Complications

- Spontaneous pneumothorax.
- Severe chronic bronchitis.



Figs 28.14A and B: (A) Hydatid cyst in lung (B) Ruptured hydatid cyst with water-lily sign.

Endurance is not just the ability to bear hard things but to turn it into glory.

Treatment

- Localised cyst is excised.
- Generalised cysts are treated conservatively.
- Pleurodesis is often required.

Here spontaneous pneumothorax is very common. Infection and haemorrhage are uncommon.

Hydatid Cyst of the Lung

- It is caused by the parasite, *Echinococcus granulosus.*
- It is often associated with hydatid cysts of the liver.
- Incidence is 15%.
- It is usually single. But multiple hydatids can occur.

Presentations

- Dyspnoea, chest pain and haemoptysis.
- Rupture into bronchial tree causes anaphylaxis.
- Rupture also causes expectoration of fluid and grape skins (vesicles).
- Fever, cough and expectoration due to secondary infection.
- Asymptomatic hydatid, identified during chest X-ray.

Investigations

- Chest X-ray:
  1. Dense homogenous opacity.
  2. Collapsed laminated membrane produces an irregular projections in a fluid level due to rupture of the cyst—*Water-lily* appearance.
  3. *Crescentic cap of air,* when it communicates into bronchial tree.
- Positive Casoni's test.
- Blood shows eosinophilia.
- Complement fixation test.
- Indirect haemagglutination test.
- CT scan—diagnostic.

Complications

- Rupture of the cyst
- Anaphylaxis
- Secondary infection
- Collapse of lung
- Pleural effusion
- Secondary pleural hydatid formation
- Hepatobronchial fistula formation (produces bilious sputum)

Differential diagnosis

- Lung abscess
- Epithelial lung cysts
- Aspergillosis

Treatment

- Thoracotomy and *enucleation of the cyst:* It is achieved by taking a good anaesthetist's help by creating positive pressure ventilation. Cyst extrudes intact. It should not be held with forceps to avoid rupture.
- *Lobectomy* is done in cases with difficulty and complications.
- Drugs like *praziquantel* or *albendazole* is given for a long period.

MEDIASTINAL TUMOURS

- It occurs at any age group, in both sexes.
- It is often identified on a routine chest X-ray, as about 50% are symptomless.



Fig. 28.15: Superior mediastinal tumour—could be thymoma, nodal mass.

Presentations

- Chest pain and back pain.
- Respiratory distress.
- Venous congestion (SVC syndrome).
- Hoarseness of voice (due to compression over recurrent laryngeal nerve).
- Dysphagia, due to oesophageal compression.
- Horner's syndrome, due to compression over sympathetic chain.
- Scabbard trachea.
- Later diaphragmatic paralysis may occur.
- Pleural effusion.
- Haemorrhage, due to erosion of major vessels by malignant tumour.


I
1
2
3
4
2
VI
5
2
X
I. Retrosternal goitre
2. Neural tumours (neurofibroma) meningocele, meningomyelocele
3. Lymphoma, foregut, duplication
4. Teratoma thymoma lymphoma
5. Pleuropericardial cyst

Fig. 28.16: Sites of mediastinal tumours.

Classification

Superior mediastinal tumour: Retrosternal goitre.

Anterior mediastinal tumours:

- Retrosternal goitre, aortic arch aneurysm lymph node enlargement.
- Thymic tumours—thymomas are commonly associated with myasthenia gravis.
- Teratomas and dermoids.
- Pleuro-pericardial cyst (spring *water cyst*).

Midmediastinal tumours

- Lymphadenopathies of all causes—secondaries, lymphomas, tuberculosis—common.
- Foregut duplication cysts.
- Lipomas.

Posterior mediastinal tumours

- Neurofibromas—commonest, 75%.
- Ganglioneuromas.
- Aneurysm of descending aorta.
- Lymph node mass.



Figs 28.17A and B: Chest X-ray showing mediastinal tumour.

Investigations

- Chest X-ray, both PA view and lateral view.
- CT scan.
- MRI.
- Mediastinoscopy and biopsy.

Treatment

- Thoracotomy and removal of tumour.
- If malignant, adjuvant therapy like radiotherapy and chemotherapy are given.



Figs 28.18A and B: CT scan showing mediastinal tumour.



Figs 28.19A and B: Plain X-ray chest showing posterior mediastinal mass.

Comedy is the Tragedy that happens to other people.

- Sternotomy for superior and anterior mediastinal tumours.
- Thoracoscopic and mediastinoscopic approaches.



Fig. 28.20: Malignant effusion—right-sided.

THYMOMAS

- Thymomas are the most common tumours of the anterosuperior mediastinum in the adult.
- They are most common in the fifth and sixth decades of life. Both sexes are equally affected.

Histological types

- Epithelial cell—has poor prognosis
- Lymphocytic
- Mixed
- Spindle—has better prognosis

50% of thymomas are malignant

Staging

I — Confined to the capsule
II — Tumour spread to periglandular fat
III — Tumour spread to adjacent tissue

Clinical Features

- Asymptomatic—50%.
- 30-40% of thymomas have associated myasthenia gravis.
- Chest pain.
- Dysphagia and dyspnoea.
- Superior vena caval obstruction.

Investigations

- *Tensilan diagnostic test:* By injecting 10 mg IV to symptomatic myasthenia will be relieved in one minute temporarily.
- Chest X-ray, lateral view shows opacity in the mediastinum.
- CT scan.

Treatment

- *For myasthenia*—Tab. neostigmine bromide 15 mg tds, daily.
- *Thymectomy* is very useful.
  - When the disease is less than 5 years.
  - Myasthenia gravis without thymoma.
  - In young, females.

Features of myasthenia gravis

- An autoimmune disease
- Presence of antibodies to acetylcholine receptors in NMJ resulting in reduced muscular contraction
- Weakness of muscle on exertion
- Ptosis, diplopia, dysarthria, dysphagia
- Drooping of jaw
- Paralysis of respiratory muscle
- Periodic remission



Fig. 28.21A: Bronchogenic carcinoma—X-ray picture.

PANCOAST TUMOURS (Superior sulcus tumour)

> ***When the tumour extends its feet from all sides of its body into the veins, the sickness produces the picture of a crab.***
>
> **—Galen** (130-200)

- It is a type of peripheral lung carcinoma arising from the apex of the lung (5% of lung cancers).

Features

- It invades brachial plexus, sympathetic chain, upper ribs and vertebrae.

Presentations

Pancoast's syndrome
- Lower brachial plexus palsy
- Horner's syndrome
- Rib erosion
- Apical shadow



Fig. 28.21B: X-ray showing right sided Pancoast's tumour.

Horner's syndrome
- Miosis
- Enophthalmos
- Anhydrosis
- Ptosis
- Loss of spino-ciliary reflex

- Intractable pain in upper chest, arm and also weakness in the arm.

Investigations

- Chest X-ray.
- CT scan.
- Bronchoscopy and biopsy.
- CT guided biopsy.
- MRI is better than CT in Pancoast tumor as brachial plexus and sympathetic chain is involved which better visualised in MRI.

Treatment

- Lobectomy/pneumonectomy.
- Radiotherapy—External tele cobalt.
- Chemotherapy—Methotrexate.

Prognosis: Poor.

CHEST WALL TUMOURS

- Tumours arising from the chest wall components like muscles or ribs. They can be benign or malignant.
- Commonest benign tumour is chondroma arising from ribs.
- Malignant tumours are *secondaries (commonest)*, chondrosarcoma arising from ribs (common among primary malignant tumours), rhabdomyosarcoma from muscles, fibrosarcoma from ribs/muscles/other soft tissues, Ewing's sarcoma and invasion from other tumours like from pleura or lungs or breast.



Fig. 28.22: Chest wall tumour. Benign tumours are usually chondromas.



Fig. 28.23: Fungating tumour invading chest wall.

Benign Tumours

- *They are slow growing, nonmobile, painless and usually from the rib cartilage, near costochondral junction.*
- X-ray is diagnostic, shows rib expansion with intact cortex.
- One or more ribs can be involved. Treatment is rib resection.

Don't let the skin stand between you and the diagnosis.

Primary Malignant Tumour

- *It has got all features of sarcoma—progressive rapid enlargement, attaining large size, warm, vascular, nonmobile, often extends into the thoracic cavity or with skin ulceration.*
- *Secondaries in* lung/*brain/liver can occur.*
- Chest X-ray, CT chest, US abdomen should be done to see secondaries.
- CT scan can also give idea about the tumour extension and operability.
- Open incision/trucut biopsy is essential for histological confirmation.
- Treatment *is wide excision with chest wall reconstruction using different osteomyocutaneous flaps, rib grafts, mesh or acrylic plates.*
- Postoperative adjuvant chemotherapy is always needed to prevent relapse. In advanced cases radiotherapy to chest wall is advised.



Fig. 28.24: Multiple cannon ball secondaries in lung. Primary sites are—breast, kidney, sarcomas, testis, prostate, thyroid.

PERICARDITIS

> ***Water contained in the sac of the heart, likewise if the sac contain within either a fluid putrid and smelling badly, or stones, it causes throbbing…. Adhesions of the pericardium to the body of the heart itself…was observed in two dropsical patients.***
>
> **—Guillaume de Baillou (Ballonius),** 1735

Types

1. Acute pericarditis
2. Chronic pericarditis
3. Chronic constrictive pericarditis

ACUTE PERICARDITIS

Usually by bacteria like *Staph. aureus, H. influenzae, Streptococci, Neisseria.* It is uncommon at present, because of availability of good antibiotics.

Other causes

- Viral infection
- Uraemia
- Trauma
- Malignancy
- Connective tissue disorders

- Here pus collects in the pericardial space causing decreased cardiac function and toxicity.

Treatment

- Antibiotics.
- Pericardial aspiration.
- Drainage of purulent fluid by open pericardiotomy.

CHRONIC CONSTRICTIVE PERICARDITIS (PICK'S DISEASE)

- Here pericardium is thickened, fibrosed and calcified. Heart is encased in a rigid cavity which decreases the cardiac function as well as the venous return.

Causes

- *Tuberculous pericarditis* is the commonest cause.
- Trauma.
- Viral pericarditis.
- After cardiac surgery.

Clinical Features

- Decreased cardiac output and tachycardia.
- Dyspnoea on exertion, easy fatigability.
- Raised jugular veins, hepatomegaly, ascites and oedema feet.

Investigations

- ECG.
- Echocardiography.
- Chest X-ray.
- CT scan.

Treatment

- Pericardiotomy with biopsy.
- Pericardiectomy.
- Antitubercular drugs is started when tuberculosis is the cause.

PERICARDIAL TAP

Indications

- Pericardial effusion due to any cause—viral, tubercular
- Haemopericardium
- Purulent pericardium

Procedure

A 16 or 18-gauge needle is passed into the pericardium just below the Xiphoid process, directing upwards and backwards, towards left side with an angle of 45° to the surface.


Heart border
Pericardial border
Pericardial fluid
Aspirating syringe with needle
Xiphoid process

Fig. 28.25: Pericardial tap for pericardial effusion/tamponade.

This site is used because—
- Most dependent aspiration
- Unlikely to traumatise heart
- Pleura is not punctured
- Coronary vessels are not interfered

Presently U/S guided aspiration is commonly done.

Complications

- Injury to heart.
- Infection.

CARDIAC TAMPONADE

Rapid accumulation of fluid or blood in the pericardial space causing increase in the ***intrapericardial pressure*** is called as cardiac tamponade.

This results in compression of cardiac chambers.
↓
↓ venous return
↓
↓ cardiac output

Causes

- Trauma
- Progressive pericardial effusion due to tuberculosis, viral, bacterial infections
- Often, uraemia can cause significant pericardial effusion

Clinical Features

- Hypotension.
- Widened cardiac dullness.
- Muffled or decreased heart sounds.
- Increased venous pressure with raised jugular veins.
- Pulsus paradoxus (pulse becomes weaker on inspiration than expiration).
- In severe cases, heart is unable to expand causing *shock and often sudden death*.

Beck's triad
- Hypotension
- Muffled heart sounds
- Raised jugular venous pressure

Investigation

Chest X-ray and U/S confirms the diagnosis.

Treatment

- ***Pericardial tap***, as early as possible to allow heart to expand adequately.
- Occasionally ***open pericardiotomy*** is required.

DIAPHRAGMATIC HERNIA

It is herniation of abdominal content through diaphragm into the chest.


Congenital
Acquired
Traumatic
Oesophageal hiatus. (Commonest type of diaphragmatic hernia)
May be associated with malrotation with Ladd's band.
Eventration
Hernia through foramen Bochdalek
Hernia through foramen Morgagni
Congenital oesophageal hernia (rare)

Eventration

- It is weakening of diaphragm due to atrophy and loss of muscle of a part or all of one leaf of the diaphragm, with thin fibrous tissue formation, covered with pleura and peritoneum on either side.

Words that enlighten are more precious than jewels.

- This thin diaphragm is raised higher and immobile. It is actually not a true herniation. But features mimic hernia.
- Differential diagnosis are diaphragmatic hernia through foramen Bochdalek.
- Condition causes respiratory embarrassment.



Fig. 28.26: Chest X-ray showing left sided diaphragmatic hernia. Note the bowel shadows in the left side thorax.



Fig. 28.27: Anatomy of diaphragm showing different sites where hernia can occur.

Types



Fig. 28.28: Diaphragmatic hernia.

Treatment is plication of diaphragm through laparotomy.

Hernia through foramen Bochdalek (through pleuroperitoneal canal) (95% left sided, only 5% right sided)

- It is commonest congenital diaphragmatic hernia.
- This is a developmental defective condition, due to failure of fusion of pleuroperitoneal canal leaving a direct communication between pleura and peritoneum on left side. This allows herniation of contents of abdomen into the left side thorax.
- Common content is *colon*. Occasionally small bowel, stomach are the contents.
- 80% cases do not have hernial sac. Only 20% cases has got sac.



Fig. 28.29: Postmortem look of a newborn baby with classical diaphragmatic hernia. (*Courtesy by Dr Subramanya Bhat K Sonologist Kanhangad*). Note the entire bowel occupying the left side thorax.

Clinical features:
- Respiratory embarrassment
- Scaphoid abdomen
- Bowel sounds in left side of chest
- Mediastinal shift towards right side
- Occasionally features of intestinal obstruction

Investigations: Chest X-ray, *Barium enema (common)* or barium meal.

Treatment

- Laparotomy and dissection of the sac (when present) and closure of the defect in the diaphragm (using nonabsorbable suture material).

Note: Persistent fetal circulation is the major problem in these newborns. It aggravates the postsurgical mortality.

Triad of congenital diaphragmatic hernia (CDH)
- Respiratory distress
- Scaphoid abdomen
- Mediastinal shift (Pseudodextrocardia)

Association of CDH

- Pulmonary hypoplasia with persistent fetal circulation—is the actual cause for hernia
- Respiratory acidosis

Hernia through Foramen of Morgagni

- The defect lies between the sternal and costal attachments of diaphragm and is situated in front, towards right. Colon is commonest content. Usually it is symptom free.

Oesophageal Hiatus Hernia

- Oesophageal hiatus hernia can be congenital or acquired (common).

Traumatic Diaphragmatic Hernia

- Either on right or left side, resulting from road traffic accidents, crush injuries, penetrating injuries, or blunt injuries.
- Patient is under shock.
- On right side along with the liver, the intestines may also get herniated.
- Patient is pale, presents with respiratory distress, guarding and rigidity over the abdomen.

Investigations

X-ray chest and abdomen.
U/S abdomen.
Often CT scan of abdomen and chest is done.



Figs 28.30A and B: (A) Plain X-ray chest, (B) Barium enema, showing bowel loops within thoracic cavity on the right side (diaphragmatic hernia).

Treatment

- Immediate laparotomy and exploration is done. Tear in the diaphragm is sutured.
- Associated injuries in liver or spleen or bowel are treated accordingly.
- Adequate blood transfusion and antibiotics is required.
- Ventilator support is often necessary.

PULMONARY COMPLICATIONS DURING POSTOPERATIVE PERIOD

Precipitating Factors

- Age: Common in infants and elderly.
- Sex: Common in males.
- Common in *smokers.*
- Common in people with chronic bronchitis, asthma, tuberculosis or COPD.
- Postoperative pain.
- Deep venous thrombosis and pulmonary embolism.
- Type of surgery: Common in thoracic or upper abdomen surgeries.
- Septicaemia.
- Paralytic ileus.
- Anaesthetic complications.
- Aspiration and its problems.
- Obesity.

Complications

- Bronchopneumonia.
- Lung collapse.
- Bronchitis.
- Lung abscess.
- *Adult respiratory distress syndrome (ARDS).*
- *Respiratory failure.*
- Alkalosis.
- Pleural effusion or empyema.

Investigations

- Chest X-ray.
- Arterial blood gas analysis.

Management

- Suction—aspiration of tracheobronchial tree.
- Respiratory physiotherapy.
- Analgesics to control pain.
- Ventilator support with endotracheal intubation.
- Tracheostomy.
- Control of sepsis by proper antibiotics.

An error gracefully acknowledged is a victory.

SURGICAL MANAGEMENT OF PULMONARY TUBERCULOSIS

Indications for Surgery

- Failure of medical therapy.
- Tuberculoma.
- Tuberculous bronchiectasis.
- Destruction of lobe.
- Persistent foci, persistent cavity.
- Empyema thoracis.
- Presence of neoplasm with tuberculosis.

Surgeries Done

- Pleural tap.
- Intercostal tube drainage for empyema.
- Rib resection and Eloisier's drainage.
- Lung resection is undertaken when medical treatment fails or when there is tuberculoma. It is commonly used method.
- Lobectomy or pneumonectomy.
- Decortication.
- Thoracoplasty collapse therapy—it causes elastic relaxation of lung around the lesion leading to closure of cavity.
- Creation of artificial pneumothorax (nitrogen is used).
- Temporary phrenic nerve palsy.
- Extrapleural pneumothorax.
- ***Plombage:*** It is extrapleural pneumolysis using lucite spheres.

VIDEO ASSISTED THORACOSCOPIC SURGERY (VATS)

It is visualisation and doing surgical procedures through video thoracoscopy.

It can be—

- Diagnostic—lung cyst, pleural pathology, malignancy, tuberculosis, lung abscess, emphysematous bullae.
- Therapeutic—cervical sympathectomy, oesophageal mobilisation for carcinoma of oesophagus, lung resection, excision of lung cysts, etc.

Requirements

- Expert skilled personal.
- Double lumen endotracheal tube for one lung anaesthesia.
- Instruments.

Advantages

- Open thoracotomy and its complications are avoided.
- Less painful, fast recovery.
- Magnification and precise dissection.

Disadvantages

- Injury to major structures.
- Longer duration of surgery.
- Learning curve.

Self-assessment Questions

- Classify thoracic injuries and their management.
- Stove in chest.
- Flail chest.
- Tension pneumothorax.
- Pneumothorax.
- Haemothorax.
- Empyema necessitans.
- Empyema.
- Fracture ribs.
- Lung cysts.
- Hydatid cyst of the lung.
- Lung abscess.
- Intercostal tube drainage.
- Bronchoscopy.
- Pancoast tumour.
- Pancoast syndrome.
- ARDS.
- Mediastinal tumours.
- Cardiac tamponade.

Cardiac Surgery

Anatomy
Preoperative assessment
Cardiopulmonary bypass
Congenital heart diseases
PDA
Coarctation of aorta
ASD
VSD
Pulmonary stenosis
Transposition of great vessels
Tetralogy of Fallot
Acquired heart disease—*Mitral stenosis*
Mitral regurgitation
Aortic stenosis
Aortic regurgitation
Valve replacement surgery
Ischaemic heart disease
Cardiac pacemakers
Postoperative care

ANATOMY

Heart consists of right and left atrium, right and left ventricle with mitral (bicuspid) valve between left atrium and left ventricle and tricuspid valve between right atrium and right ventricle. Aorta begins from the left ventricle to have systemic circulation. Superior vena cava (SVC) and inferior vena cava (IVC) enters the right atrium to return venous blood. From right ventricle pulmonary artery begins which transport the unoxygenated venous blood in to the lungs. From lungs four pulmonary veins collect the oxygenated blood to reach right atrium and to complete the cycle.

Pressure in the right ventricle is low. Pressure in the left ventricle is high.

Chordae tendinae act as guy ropes which connect valves (mitral and tricuspid) to heart through papillary muscles.

Aortic and pulmonary valves are semilunar valves.

First heart sound is produced by closure of atrio ventricular valves. ***Second heart sound*** is produced by closure of semilunar valves. Valvular heart disease may be congenital or acquired. Rheumatic heart disease is the commonest acquired cause for valvular disease. Mitral stenosis is the commonest type.

Right and left ventricles are separated by interventricular septum. Right ventricle is thinner than left ventricle. SVC and IVC opens in to right atrium.



Fig. 28.31: Normal heart anatomy.

Heart derives its blood supply from two ***coronary arteries—right and left***. Left coronary artery once origins at ostium runs for 2 cm, divides in to ***anterior descending and circumflex artery***. Anterior descending artery runs in the anterior interventricular groove to reach apex and ascends short distance in posterior interventricular groove. ***The circumflex artery*** runs around the base of left ventricle. Right coronary artery through atrioventricular groove reaches the posterior interventricular groove and runs along it.

Right coronary artery supplies right atrium, entire right ventricle except anterior part, posterior part of the interventricular septum, conducting system except left branch.

Left coronary artery supplies left atrium, entire left ventricle except posterior part, anterior part of the interventricular septum.

There are collaterals within the heart and extracardiac but is not sufficient enough to maintain the adequate perfusion in case of coronary block to the dynamic heart leading into myocardial infarction.

Venous drainage of heart is through superficial and deep veins. Superficial veins (great cardiac, middle cardiac, small cardiac, oblique and posterior veins) form

Have a heart that never hardens and a temper that never tires and a touch that never hurts.

coronary sinus ending at right atrium. Deep veins directly enter the heart called as ***Thebesian veins.***

First blood passes to the elastic vessels then resistant vessels and capillaries later to veins and then back to heart. In capillary because of great cross-sectional area, rapid transfer of substances across tissues occur.

Flow of blood from left side heart through aorta and its branches to capillaries and return to right heart is called as ***systemic circulation.***

Blood from right heart through pulmonary artery to lungs and from lungs through pulmonary veins to left heart is called as ***pulmonary circulation***.

Conduction system of heart consists of ***SA node*** (Sinu atrial node) which is pacemaker of the heart, ***AV node*** (Atrio ventricular node) located in lower part of the atrial septum, ***AV Bundle*** (Atrio ventricular bundle) with right and left branches and terminal ***Purkinje fibres*** in subendocardial region.



Fig. 28.32: Conduction system of heart.

Surface marking of the heart: Upper border is between 2nd and 3rd costal cartilage at the level of sternum. Lower border is from 2 cm to the right of sternal margin at 6th costal cartilage to the apex of heart at 5th intercostal space 9 cm from the midline.

PREOPERATIVE ASSESSMENT AND PREPARATION OF THE CARDIAC PATIENT

- Since cardiac surgery is a major surgery, proper evaluation is essential. Consent, explanation, discussion in initial phases is absolute need.
- Patient will be anxious. He needs proper consolation, moral support.



Fig. 28.33: Surface marking of the heart.

- Proper history related to smoking, alcohol intake, diabetes, previous cardiac surgery, drug intake is essential.
- ECG, chest X-ray, haemoglobin, haematocrit, blood urea, serum creatinine, blood sugar, lipid profile, blood grouping are essential basic investigations.
- ***Echocardiography*** is ultrasound examination of heart. Heart chambers, pericardium, pumping capacity, valves and their structure, ejection fraction are found through this. Usually cardiologists do this test and give opinion about it.
- **Treadmill stress test** *to find out the response of heart to work.*
- ***Coronary angiogram*** is done to find out the amount of coronary function or its block. Special coronary artery catheter is passed through the brachial or femoral artery like in seldinger angiogram. This catheter is negotiated into the coronary arteries both right and left. Radio-opaque water soluble dye is injected into the catheter and coronaries. X-ray film will confirm the status of the coronaries. Procedure is done under guidance using C-arm. Amount of block is assessed and categorised.
- ***Cardiography*** is the procedure wherein dye is injected into the heart chambers using specialised catheters and size, shape, presence of clot in the chambers, valvular incompetence are studied.
- ***Cardiac catheterisation*** is done to get cardiac ***oximetry and pressures*** in different chambers of the heart. Cardiac catheter is flexible 100 cm long tube passed to the heart under guidance. Right and left sides are assessed separately. Catheter is infused with heparinised solution to prevent intravascular clotting during procedure.

- ***Catheter to the right side*** of the heart is passed through the cubital vein, subclavian vein, SVC. Pressures at systole and diastole are studied in right atrium, right ventricle, pulmonary artery. Blood samples are collected from these three levels to study ***oxygen saturation (oximetry).***
- ***Left side of the heart*** is approached by two approaches—one is through the right atrium penetrating the atrial septum, catheter reaches the left atrium, and so to left ventricle and aorta. Pressure is recorded in each chambers. Blood samples are colleted for oxygen saturation.
- ***Pressure*** will alter in valvular diseases like stenosis or regurgitation.
- ***Oxygen saturation*** is altered in shunts between right and left sided. Shunt occurs between systemic and pulmonary circulation.
- *Cardiac isotope scanning.*

Pressure in atrium is low 0-10 mmHg. Right atrium is little lower than left
Pressure in the right ventricle is 15-30 mmHg systolic and 0-8 diastolic
Pressure in pulmonary artery is 15-30 mmHg systolic and 3-12 diastolic
Pressure in left ventricle is 100-140 systolic and 3-12 mmHg diastolic
Pressure in aorta is 100-140 systolic and 10-80 mmHg diastolic

- Pulmonary function study is done by chest X-ray, spirometry, blood gas analysis.
- Focus of infection should be looked for like dental infection, throat infection, skin infection.

CARDIOPULMONARY BYPASS

Here functions of the heart and lungs are temporarily replaced by heart—lung machine which acts as a pump and oxygenator to the body.

Heart is exposed through a midline sternotomy incision.

Venous blood from the SVC and IVC is diverted to the heart lung machine by placing tubes to them.

From the heart lung machine oxygenated blood is pumped through a tube which is passed to the ascending aorta so as to bypass the heart and lungs with retaining the function so tissues will have adequate required perfusion. Blood should be heparinised to prevent clotting. Often venous tube is placed in the right atrium.

Temperature is lowered over the heart by poring cold saline. Ventilation is discontinued.

Once procedure in the heart is over, air in the chambers of the heart is cleared. Coronary artery perfusion is restored and heart is made to beat spontaneously or using DC shock. Acidosis and hypokalaemia is corrected. Patient is warmed.

Heart is allowed to fill gradually and slowly heart lung machine blood flow is reduced. Cannulas are removed from the veins (SVC and IVC) and also from the aorta. Protamine sulphate is given to reverse the effect of heparin.



Fig. 28.34: Figure showing cardiopulmonary bypass.

Myocardial protection is achieved by—
- Infusion of solution with 20 mmol/litre of potassium in to the coronaries
- Cooling cardioplegic infusate to 6°C
- Surface of the heart is sprayed with 4°C Hartmann's solution
- Body temperature is reduced to 20-27°C

Heart can be kept arrested for 2 hours.

CONGENITAL HEART DISEASES

Left to right shunt—It leads into overloading of the pulmonary circulation. Usually it is acyanotic.
PDA—Patent ductus arteriosus
ASD—Atrial septal defect
VSD—Ventricular septal defect.

You never get the second chance to make the first impression.

Right to Left shunt—Blood from the systemic veins enter the systemic arteries bypassing the lungs allowing severe hypoxic blood to enter the systemic circulation. It will cause cyanosis. Examples are tetralogy of Fallot and transposition of great vessels.

Conditions without shunts—Coarctation of aorta, aortic stenosis, pulmonary stenosis.

Also classified as ***cyanotic and acyanotic heart diseases.***

PATENT DUCTUS ARTERIOSUS (PDA)—10%

Ductus arteriosus is essential in fetal life wherein blood from pulmonary artery reaches the aorta through this ductus arteriosus by passing the lung. Once child is born, this ductus closes because of the beginning of the lung function. Prostaglandin prevents closure. Indomethacin promotes closure. If it persists in child it is called as PDA.

In PDA, part of the blood from aorta flows back to pulmonary artery because of high pressure in aorta (left to right shunt). This causes pulmonary hypertension.

Occasionally pressure is so severe that flow may reverse and deoxygenated blood from pulmonary artery may flow towards aorta causing reversal of left to right shunt converting acyanotic shunt to a cyanotic one. It is called as ***Eisenmenger's syndrome***. It can occur in other left to right shunt also (ASD, VSD).

Child presents with dyspnoea, chest pain, machinery murmur.

Aortogram and echocardiography are diagnostic.



Fig. 28.35: Patent ductus arteriosus.

Treatment—Closure of the PDA either through interventional cardiology or more conveniently through open surgery.

Complications of PDA—Congestive cardiac failure, bacterial endocarditis.

COARCTATION OF AORTA—5%

Narrowing of the aorta just distal to the origin of left subclavian artery. It is often associated with PDA, VSD.



Fig. 28.36: Coarctation of aorta.

There is increased perfusion of upper limb, cranium, face. But less blood supply occurs to lower limb, kidneys.

Types

- It can be preductal or postductal depending on relation to the ligamentum/ductus arteriosus.

Features

- It causes left ventricular hypertrophy, differential blood pressure (pressure upper limb is higher but pressure in lower limb is lower). Often there is differential cyanosis.
- Visible dilated intercostal vessels through collateral perfusion is more obvious when patient leans forwards.
- X-ray will show dilated proximal aorta, notching of ribs due to erosion of the intercostals vessels.
- Aortogram is diagnostic.

Treatment *is widening of the narrowed segment of aorta with Dacron patch graft, or removal of stenosed segment and arterial graft.*

Complications

- Congestive cardiac failure, bacterial endocarditis, aortic rupture.



Fig. 28.37: Collaterals development in intercostal vessels in coarctation of aorta.

ATRIAL SEPTAL DEFECT (ASD)—7%

- An ASD is the hole in the atrial septum thus causing communication between left and right atrium.

Types

- *Secundum type* is the commonest one. It is elliptical, in the middle of the atrial septum and is due to defect in the site of foramen ovale
- *Primum type* is lower part. It is rare
- *Sinus venosus type* is near SVC opening

Features

- There is shunting of blood from left atrium to right atrium. It causes left ventricular hypertrophy, pulmonary hypertension, eventually occasionally reversal of shunt as right to left leading in to cyanosis
- Dyspnoea, fixed split of second heart sound, systolic murmur due to increased blood flow through the pulmonary valve are the clinical features
- It is diagnosed by echocardiography, cardiac catheterisation and angiocardiogram.



Fig. 28.38: Atrial septal defect.

Treatment

- Closure of the defect by direct suturing or using patch either pericardium or Dacron.

VENTRICULAR SEPTAL DEFECT (VSD)—15%

- VSD is defect in the ventricular septum causing left to right shunt. There is pulmonary hypertension, ventricular hypertrophy.

Types

- Four types of VSD are present depending on location of the defect. Defect can be small or large.
- It may be associated with tetralogy of Fallot.
- *Severe cases of shunt become reversal causing* **Eisenmenger's** *syndrome.*

Clinical Features

- Pansystolic murmur, palpable thrill, split second sound with pulmonary accentuation, recurrent respiratory infections.



Fig. 28.39: Ventricular septal defect.

He who believes, is strong; he who doubts, is weak.

- 40-50% of defects especially when they are small, will close spontaneously. Spontaneous closure will not occur after the age of 6.

Investigations

Echocardiography, cardiac catheterisation.

Treatment

Closure of the defect using pericardial patch or Dacron. While suturing care should be taken not to inure atrioventricular conduction system.

Complications of VSD

Recurrent respiratory infection, pulmonary hypertension, cardiac failure.

PULMONARY STENOSIS

It is narrowing of the pulmonary valves due to fusion of cusps. Narrowing may be as less as 2-4 mm. Patient develops right ventricular hypertrophy and later right ventricular failure. Pressure in the right ventricle is higher, in pulmonary artery is lower. Treatment is pulmonary valvotomy.

TRANSPOSITION OF GREAT VESSELS

Here aorta begins from right ventricle and pulmonary artery begins from left ventricle. So venous blood enters the aorta and causes hypoxia and cyanosis. It is usually not compatible with life but often through bronchial collaterals communication may develops and become compatible. When it is often associated with ASD or VSD or PDA mixing occurs and is compatible.

It is cyanotic heart disease.

It is diagnosed by an emergency echocardiography and aortocardiogram.



Fig. 28.40: Transposition of great vessels.

Treatment

- Immediate palliative method is ***Rashkind balloon septostomy***. A balloon is passed in to the right atrium and through the septum in to the left atrium. Balloon is inflated and rapidly pulled out through the atrial septum causing widening of the defect in the septum. It allows flow of oxygenated blood from pulmonary veins through the septum and so to the right ventricle and aorta.
- ***Albert-Mustard atrial redirection of flow of blood:*** Atrial septum is excised and using either pericardial or Dacron patch left atrial blood is directed to the right ventricle and right atrial blood is directed to the left ventricle.
- Later definitive correction is done either at atrial level or at great arterial level.

TETRALOGY OF FALLOT

It is a cyanotic congenital heart disease.

Components

- Ventricular septal defect
- Infundibular and pulmonary stenosis causing right ventricular outflow obstruction
- Right ventricular hypertrophy
- Dextroposition of aorta



Fig. 28.41: Tetralogy of Fallot.

Because of right ventricular outflow obstruction venous blood gets diverted through the existing VSD in to the left ventricle and so to the aorta. So systemic circulation is provided with unoxygenated venous blood causing cyanosis.

Features

- Cyanosis with dyspnoea. Ejection systolic murmur which diminishes during cyanotic attack.
- Echocardiography, cardiac catheterization are the essential investigations.

Treatment

- ***Blalock-Taussig operation***—It is done as initial treatment in newborn baby with Fallot's tetralogy. Left subclavian artery and pulmonary artery is connected using a graft which allows the pulmonary arterial perfusion.
- ***Second stage definitive correction*** by relieving the right ventricular outflow obstruction completely and closure of VSD using Dacron patch.

ACQUIRED HEART DISEASE

MITRAL STENOSIS

Commonest acquired heart disease. Valve here cannot open completely during left atrial contraction.

It is scarring and thickening of the mitral valves due to inflammation of valves with valve area less than 2.5 cm^2 (normal is 4-6 cm^2). It will later lead into fusion of chordae tendinae, calcification of the valve cusps. It is commonly due to rheumatic fever with streptococcal pharyngitis.

Features

Mitral stenosis
↓
Hypertrophy of the left atrium
↓
Sluggish blood flow, left atrial hypertrophy
↓
Atrial fibrillation → atrial thrombus → emboli
↓
Pressure in pulmonary vein increases
↓
Lung congestion, oedema
↓
Pulmonary artery hypertension
↓
Right ventricular failure and tricuspid regurgitation (CCF).

Mitral stenosis—clinical features and investigations

- Dyspnoea, orthopnoea
- Cough, haemoptysis
- Mid-diastolic murmur, with loud heart sound
- Features of atrial fibrillation
- Chest X-ray shows straightening of the left border of the heart
- ECG and echocardiography will demonstrate mitral stenosis, clot
- Cardiac catheterisation shows increased right atrial pressure
- Pulmonary capillary wedge pressure (PCWP) shows increased left atrial pressure

Indications for surgery

- Severe stenosis
- Calcification of cusps
- Clot in the left atrium
- Right ventricular hypertrophy

Surgeries for mitral stenosis

- *Closed mitral valvotomy*—Through left thoracotomy incision, heart is exposed. Left atrium is opened with purse string suture so as to allow the finger to pass inside. Left ventricular tip is incised with a purse string suture and Tubb's valve dilator is passed. Under finger guidance through left atrial purse string wound, valve and cusps are separated using ***Tubb's dilator.***



Fig. 28.42: Mitral valvotomy using Tubb's dilator.

Perfection is the best excuse.

- *Open mitral commissurotomy*—It is done with cardiopulmonary bypass, left atrium is opened, valve and commissures are separated, valve is dilated using finger, clot in the left atrium is removed.
- Open valvuloplasty by doing repair of the valve.
- Percutaneous balloon valvotomy.
- Valve replacement surgery.

MITRAL REGURGITATION

Mitral valve here cannot close completely during left ventricular contraction. It can be associated with mitral stenosis also.

Causes

- Rheumatic heart disease causing fibrosis, rigidity and shortening of chordae tendinae leading to inability to close the mitral valve.
- Myxomatous degeneration of the valve.
- Marfan's syndrome.
- Connective tissue disease.
- Sarcoidosis.

Mitral regurgitation
↓
Left ventricular hypertrophy but reduced cardiac output
↓
Left atrial enlargement with increased pressure
↓
Pulmonary venous pressure increases
↓
Lung congestion, oedema (CCF).

Features

- Cough, haemoptysis, chest pain, dyspnoea
- Pansystolic murmur
- Features of failure
- Often associated features of mitral stenosis
- Features of associated diseases
- Echocardiography, cardiac catheterization and PCWP are the investigations

Treatment

Valve replacement surgery.

AORTIC STENOSIS

Narrowing of the aperture of aorta is due to rheumatic heart disease, bicuspid stenosis, calcification. Valve is thickened, fibrosed, calcified and narrowed.

Features

- There is left ventricular hypertrophy with reduced left ventricular capacity
- Because of the narrowing of the valve, cardiac output decreases
- Systolic murmur is better heard over aortic area
- Later may lead in to failure
- Echocardiography is diagnostic.

Treatment

Valve replacement surgery.

AORTIC REGURGITATION

There is incompetence of aortic valve.

Causes

- Rheumatic disease.
- Connective tissue disorder.
- Marfan's syndrome.
- Tertiary syphilis.
- Endocarditis.
- Aortic dissection.

Features

- There is left ventricular hypertrophy, and cardiac failure later
- Early diastolic murmur is characteristic
- Collapsing pulse
- Dyspnoea, chest pain
- Echocardiography is diagnostic
- It may be associated with ischaemic heart disease.

Treatment

Valve replacement surgery.

VALVE REPLACEMENT SURGERY

Indications

- Severe valvular disease with fixity, stenosis
- Valve disease with thrombosis like in mitral stenosis
- Multivalvular disease

Types

1. ***Biological valves***—Capentier's glutaraldehyde preserved porcine valve with a sewing ring and frame is used. It is not thrombogenic. So it is used in child bearing age and in whom warfarin is contraindicated. But its life span is less. So it is useful in elderly.
2. ***Mechanical valves***
    - Starr-Edwards ball- valve prosthesis
    - Bjork-Shiley tilting disc valve prosthesis.

Mechanical valves are long lasting but they are thrombogenic. Embolic phenomenon can occur. Patient requires oral anticoagulant to keep prothrombin time twice normal. If anticoagulants cannot be used, then aspirin, dipyridamole can be used.

Problems with mechanical valves
- Thrombogenic
- Require warfarin anticoagulant therapy
- Prone for severe epistaxis, intracranial haemorrhage while on warfarin therapy
- Prone for infections by bacteria, fungi, yeasts
- Mechanical haemolysis and anaemia
- Valve malfunction may occur



Fig. 28.43: Different types of valve prosthesis.

3. ***Free homograft valve.***

ISCHAEMIC HEART DISEASE (IHD)

Main major arteries of the heart are right coronary, left coronary and circumflex artery. Blockage can occur in one or two or all three vessels. Involvement of all three vessels is called as triple vessel disease.

IHD presents as ***asymptomatic*** with sudden massive cardiac ischaemia with sudden death.

Or ***symptomatic angina,*** is progressive if not treated and eventually may lead in to severe MI.

Atherosclerosis is the commonest cause.

Risk factors are—
- Hypercholesterolaemia
- Cigarette
- Diabetes mellitus
- Hypertension
- Family history and age

Atheroma plaques deposits in the coronary artery and narrows it. Block above 70% is called as critical block. Angina is initially treated with calcium antagonists, beta blockers, nitrates.

Investigations

- ECG.
- Coronary angiography is diagnostic.
- Echocardiography.
- Lipid profile (done on empty stomach).



Fig. 28.44: Coronary artery: Anatomy and sites of CABG.

Treatment

1. *Coronary balloon angioplasty* is done in case of angina, only one or two vessels are involved. It is done by interventional radiologists in presence of cardiologists. Balloon tip catheter is passed through femoral or radial artery to reach proximal aorta and entered into the coronary artery opening. Coronary angiogram is done after injecting the dye. Balloon tip of the catheter is passed across the site of the block. Balloon is inflated to crush the atheroma.

Problems with angioplasty
- Restenosis
- May precipitate block

2. Coronary artery stenting after balloon angioplasty.
3. Coronary artery bypass graft (CABG).

Indications
- Triple vessel stenosis
- Left main stem stenosis
- Chronic stable angina
- Angina with persistent chest pain
- Block more than 70%

Grafts Used

- Patient's own long saphenous vein—*Commonly used graft*

Strong convictions precede great actions.

- Patient's own internal mammary artery—*Choice graft* as it is reliable, less occlusion, long-term patency. Usually 3-4 grafts are used.

Technique—It is done under cardiopulmonary bypass. Aortic cross clamps are used to help proper graft anastomosis.

Complications of CABG

- Graft thrombosis
- Narrowing
- Atherosclerosis in the graft
- Respiratory infection.

CARDIAC PACEMAKERS

Cardiac rate is made regular using specialized device which stimulates the heart and acts as pacemaker.

Temporary Pacing

It is done in myocardial infarction, arrhythmias, and cardiac surgery.

Permanent Pacing

It is done in congenital and acquired atrioventricular block, sick sinus syndrome (SA node dysfunction), atrial fibrillation, certain tachycardia.

Routes of Pacing

Transvenous route is commonly used. A needle is passed into the subclavian vein and guide wire is passed through the needle into SVC. Dilators are passed through the guide wire. Then sheath is passed. Electrode is passed into the atrium or ventricle. It is endocardial pacing.

Transthoracic pacing—It is not commonly used. It requires open thoracotomy. One lead is placed to the atrium and two other to ventricle.

Pacemaker may be ***external*** usually used as temporary.

Internal pacemaker is placed in the upper chest wall below the middle of the clavicle in subfacial plane under local anaesthesia (pacemaker pocket).

Complications of pacing

- Arrhythmias
- Infection
- Phlebitis, haematoma, thrombosis, bleeding
- Failure of battery, electrode
- Electrode displacement

Types of electrode activity

- Fixed rate—ventricular pace—no sensing
- Demand release—ventricular pace—sensing-triggered mode
- Inhibited rate—ventricular pace—sensing-inhibited mode

Pacemakers are sensitive to electromagnetic interference.

POSTOPERATIVE CARE

- Proper monitoring and ICU care is essential.
- ECG, temperature, BP, CVP, cardiac monitor, urine output has to be assessed regular intervals.
- Serum electrolytes, blood gas analysis, assessment of isoenzymes, haematocrit, blood urea, creatinine.
- Acidosis and hypercalcaemia to be corrected early.
- Drains from pericardium, mediastinum should be assessed carefully.
- Hypovolaemia, cardiac tamponade, myocardial infarction, hypoxia, acid-base imbalance has to be corrected.
- Dopamine, dobutamine, isoproterenol are the drugs used when there is low cardiac output.
- Digoxin, pacing, cadioversion may be required if there is cardiac arrhythmias.
- Management of respiratory system—when the patient is alert and having adequate cough reflux, endotracheal tube is removed. Breathing exercises, physiotherapy, observation for respiratory distress, prevention of pneumonia to set in are important care required.
- Care of the endotracheal tube, suctioning, checking the parameters in intermittent positive pressure ventilation (IPPV).
- Neurological system should be observed—alertness, speech, level of consciousness, any deficits are looked for.
- Strict asepsis is undertaken in cardiac postoperative period by avoiding unnecessary visitors, separate dress in postoperative ward, wearing gloves, cap, masks while attending the patient.

Self-assessment Questions

- Cardio-pulmonary bypass.
- USO.
- ASD.
- PDA.
- Mitral valvotomy.
- Fallot's tetralogy.

29

Adjuvant Therapy

Radiotherapy
Chemotherapy
Hormone therapy in cancer
Immunosuppression
Immunotherapy
Hybridoma
Gene therapy

RADIOTHERAPY

> ***The effect of radiations on living cells is the more intense: (1) the greater their reproductive activity, (2) the longer their mitotic phase lasts, and (3) the less their morphology and function are differentiated.***
>
> **—Jean Alban Bergonié, Louis Mathieu Frédéric Adrien Tribondeau,** 1906

- It is use of ionizing radiation as therapy, mainly in malignant conditions.
- Megavoltage X-rays or gamma rays which generates energy greater than 1 × 10^6 V are used.

Principles and Factors in Radiotherapy

- Penetration of the beam into the deep seated tumour.
- Building of the radiation dose under the skin over the tumour tissue so as to minimize the skin reactions.
- Precise targeting of radiation towards the tumour.
- Radiosensitivity, tumour volume and tumour size are the factors which determine the radiation efficacy.

Physicochemical Effects of the Radiation

- Direct action on the target tissues.
- Indirect action, by releasing free radicals which cause cell destruction.
- It acts on the different phases of cell cycle to destroy the cell.

Changes in the Tumour Cells after Irradiation

1. Repair of the damaged but retained cells.
2. Repopulation is by proliferation and reproduction of the retained cells.
3. Redistribution of the cells. Cells in the 'S' phase of the cell cycle (where DNA is being synthesised) are radioresistant. These cells after radiotherapy will go to 'G_2' or 'M' phase.
4. Reoxygenation of the cells which were hypoxic at the time of radiotherapy. Hypoxic tumour cells are radioresistant. About 10% of tumour cells are in hypoxic state.

Thus fractionation of the radiotherapy allow retained cells to go for active and sensitised phase making radiotherapy more effective.

Oxygen is a good radiosensitiser. So hyperbaric oxygen is used many times as radiosensitiser.

Radiation Unit

It is called as gray unit. It is defined as the absorption of 1 J of radiation energy by 1 kg of tissue.

Types of Radiotherapy (Therapeutic)

1. ***Curative (radical) radiotherapy:*** It is given in early malignancies as a curative or primary method to tumours which are radiosensitive.
2. ***Palliative radiotherapy:*** It is used to alleviate the symptoms when the tumour is beyond cure.

Symptoms are:

- ***Pain*** in secondaries in the bone
  - Myeloma.
  - Carcinoma breast.
  - Advanced lymph node metastasis.
- ***Bleeding***
  - Carcinoma oral cavity, cervix.
  - Carcinoma bladder, rectum.
  - Advanced secondaries in the lymph nodes.

"Cancer" word itself is lethal many times than cancer.

Common tumours are:

- Seminoma testis
- Hodgkin's lymphoma
- Squamous cell carcinoma
- Ewing's sarcoma
- Carcinoma lung
- Gliomas
- Bladder tumours
- Carcinoma cervix, vagina, nasopharynx, head and neck, oesophagus
- Basal cell carcinoma

Dose is 60 Gy in 30 fractions over 6 weeks.

- ***Fungation***
  - Breast carcinoma
  - Rectal carcinoma.
- ***Obstruction***
  - Bronchogenic carcinoma obstructing inferior vena cava
  - Carcinoma cervix causing obstruction to the ureter.
- ***Pathological fracture*** due to secondaries.
- ***Spinal cord compression*** due to secondaries.

Dose is 10-25 Gy in 1 to 5 fractions.

Principle

Radiation is used to kill actively proliferating malignant cells at their mitotic level.

Common malignancies which are *Radiosensitive* are:

- Squamous cell carcinoma
- Basal cell carcinoma
- Bladder tumours
- Carcinoma cervix
- Seminoma testis
- Hodgkin's lymphoma

Other areas where radiotherapy is used commonly -

- In carcinoma breast during postoperative period, for secondaries in bone, sometimes as preoperative radiotherapy, as part of *QUART Regime.*
- In follicular carcinoma of thyroid: For secondaries radio active I^{131} 5 m curies is given orally. External radiotherapy is also given for bone secondaries along with internal fixation if there is pathological fracture.
- Malignant brain tumours like astrocytomas.
- Many sarcomas.
- Carcinoma prostate.
- Carcinoma oesophagus.
- Carcinoma lung.
- Fixed secondaries in neck as palliation to palliate pain, fungation and erosion into major vessels.
- Multiple myelomas.

Radoresistant Tumours Include

- All GI malignancies.
- Melanoma.
- Medullary carcinoma of the thyroid.

Source of Radiotherapy

- Cobalt 60 machine – most commonly used.
- Kilovoltage machines.
- Linear accelerator.
- Betatron/microton.
- Radioactive materials like Cesium 137 (pellets), Iridium 192 (wire), Gold 198 (seeds), iodine 125 (seeds).

Measurement of Ionizing Radiation

Roentgen unit is a measure of ionizations produced per unit volume of air by X-rays and gamma rays but it is not used for photon energies above 3MeV. SI unit for exposure is Coulomb per kg.

Radiation Absorbed Dose (RAD)

Absorbed dose is De/dm. It is mean energy imparted by the ionizing radiation to material of mass dm.

Old unit is *rad* which is equivalent to 100 ergs of energy per gram.

Newer International Unit is Presently Used

One Gray *(Gy)* is one joule of energy deposited per kilogram of material. One Gy = 100 rads = 100 cGy. 1 cGy = 1 rad.

Radiotherapy sources	*Classification*	*Efficacy depends on–*
• X-rays, electrons-from high energy X-ray machine, i.e. Linear accelerator • Gamma and beta rays from radioactive isotopes like Cobalt-60, Caesium 137, Iridium 197 • Protons, neutrons and heavy ion nuclei from cyclotrons	• *Low LET* (Low Energy Transfer) radiation- X-rays, gamma rays, electron • *High ET* radiation – Neutrons, protons, alpha particles and negative ions. It has heavier mass with dense localisation and hence biologically more effective	• Cell cycle phase • Oxygen content of cells *Methods of delivery* • External beam radiation (Teletherapy) • Brachytherapy • Systemic irradiation using radioisotopes like I^{131}

Pre-operative radiotherapy advantages	*Post operative radiotherapy*	*Radiotherapy and chemotherapy combined*
• Down-stage the tumour and reduces the tumour bulk • No change in oxygenation of tissues • Blockage of lymphatics by RT prevents tumour spread during surgical dissection • Reduces the chances of microscopic spread *Disadvantages* • Delayed healing due to reduced vascularity • Flap necrosis, fistula formation • Carotid blow-out	• More effective and extent of RT is well defined • Flap necrosis, fistula complications are less *Indications* • When resected margin is positive for tumour • When bone/cartilage are involved • Extracapsular nodal spread • Multiple neck nodes/node more than 3 cm in case of neck disease • Poorly differentiated tumour	• Commonly used before or during RT • Chemotherapy after RT is not commonly followed • Chemotherapy before RT is called *as induction chemotherapy* which reduces the bulk of tumour without altering the vascularity • Chemotherapy with RT is called as *concomitant RT* which improves the effect of RT. Methotrexate and bleomycin are radio sensitisers

Radiotherapy Plan

Type and doses of radiotherapy is decided by following factors -

- Site of tumour.
- Lymphatic field.
- Tumour size and extent.
- Histological type and grading.

Types of radiotherapy (Technical)

- Superficial X-ray therapy (100 KV)
- Orthovoltage X-ray therapy (200/300 KV)
- Caesium (^{137}Cs) or cobalt (^{60}Co) teletherapy
- Intracavitary or intralesional radiotherapy (Brachytherapy)
- Radioactive I^{131} therapy for follicular carcinoma thyroid

Brachytherapy

- It is radiation given with source close to the tumour.
- It is given using iridium^{192} caesium^{137}.
- It is curative radiotherapy.
- It is used in carcinoma oral cavity, penis, breast, cervix and bladder.
- Radiation material placed in the cavity is called, *intracavitory* RT.
- Radiation material is inserted into the tissues — *interstitial* RT.
- Implants can be kept permanently or temporarily.
- Radioactive material is placed into the cavity/tissue through applicators under general anaesthesia.
- Intraoperative radiotherapy is also becoming popular.
- It has only localised effect with adjacent tissue being spared.

Brachytherapy

Type	*Advantages*	*Disadvantages*
• *Intracavitary* like in uterus, urinary bladder, maxillary antrum, bronchial or esophageal tree • *Interstitial* wherein radioactive needles/wires/ribbons/seeds are inserted into the tumour area like in bladder or oral cavity • *Surface brachytherapy* using moulds like in tumours of skin/eye/breast Radionuclides used are Caesium 137 (Cs^{137}), Iridium 192 (Ir^{192}), Gold 198 (Au^{198}) and Iodine 125 (I^{125}) Brachytherapy is often combined with external beam radiotherapy	• High, localised, single continuous dose of RT • Deeper and adjacent tissues are spared • High dose rate with short time • Less side effects • Curative and effective in early cancers • After loading devices are available which reduces personal exposure • Surgery is avoided and part is retained	• Technically difficult • Availability of the facility • Local complications like displacement/erosion

The miserable have no other medicine but only hope.—William Shakespheare

External beam radiation:
Given using cobalt 60 teletherapy or X-ray source.

Advantages—Deep penetration, skin sparing, better dose distribution.

Internal radiation:
Used for diagnostic and therapeutic purpose, e.g. in carcinoma thyroid for treatment of secondaries.

Complications of Radiotherapy

- Oral mucosal oedema, ulceration, dysphagia, dyspnoea, loss of taste, oral thrush.
- Bone marrow suppression.
- Oophoritis in women and oligospermia in men.
- Effecting lens, eyelashes and lacrymal glands causing dryness, cataract.
- Mucosa in GIT is very sensitive causing nausea, vomiting and diarrhoea.
- Radiation dermatitis, pigmentation in skin.
- Radiation myelitis of the spinal cord—causing hemiplegia, paraplegia.
- Radiation pneumonitis and pulmonary fibrosis.
- Radiation nephritis and renal failure.
- Radiation osteomyelitis.
- Radiation-induced malignancies.
- Radiation-induced thimble bladder.
- Radiation-induced frozen pelvis.
- Infection—bacterial, viral, candidial *(oral thrush).*

CHEMOTHERAPY

- Chemotherapy, today is an important modality of treatment in managing a case of cancer.
- It is the main modality of treatment in most of the advanced malignancies.
- It is used preoperatively to downstage the tumour so as to increase the possibilities of surgical resection.
- When used postoperatively it reduces the rate of recurrence.
- It is the primary treatment for NHL, leukemia.
- These drugs mainly act by blocking the mitotic activity in the nucleus in different phases of the cell cycle.
- It is given either oral, intravenous (*systemic*), intra-arterial, intrathecal and intravesical (*regional*) or as isolated limb perfusion.
- Intra-arterial chemotherapy is used in head and neck cancers and hepatic cancers.
- *Isolated limb perfusion* is used in melanoma.

CELL CYCLE

The cell cycle is composed of —

1. ‘G_0’—resting phase or nonproliferative phase.
2. Presynthetic phase (G_1)—Resting cells that are not preparing for cell division are said to be in this subphase G.
3. ‘S’ phase—DNA synthesis takes place during this phase.
4. ‘M’ phase—formation of mitotic spindle, i.e. period of mitosis.
5. Postsynthetic phase (G_2)—premitotic interval, which follows the termination of DNA synthesis.



Fig. 29.1: Cell cycle.

Most potent cytotoxic agents act by damaging DNA. Their toxicity is high during the DNA synthetic phase, ‘S’ phase of the cell. Some agents block the formation of mitotic spindle in M phase (vinka alkaloids and taxanes). So the agents have activity only against cells that are in the process of division. Hence tumour with high fraction of actively dividing cells are more susceptible to chemotherapeutic agents.

When chemotherapy is given with interferons and interleukins, it is called as **biochemotherapy**.

ANTIMALIGNANCY DRUGS

I. Classification

1. *Alkylating agents*—
    a. Nitrogen mustards: Mechlorethamine (mustine hydrochloride), cyclophosphamide, chlorambucil, melphalan.
    b. Ethylenimines.
    c. Alkylsulfonates—Busulfan.
2. *Antimetabolites*—
    a. Folic acid antagonists—methotrexate.
    b. Purine antagonists—azathioprine, 6-mercaptopurine.
    c. Pyrimidine antagonists—5-fluorouracil,

	Drugs	*Used in*	*Adverse effects*
1.	Mustine hydrochloride	Hodgkin's lymphoma	Alopecia, bone marrow suppression
2.	Cyclophosphamide: Dose: 3 mg/kg IV daily for 5 days in dextrose, as monthly cycle for 6 months Orally as 50 mg tablets.	Ovarian carcinoma, lymphomas, colonic and bronchogenic carcinoma	Alopecia, bone marrow suppression, haemorrhagic cystitis
3.	Melphalan Dose:10 mg daily × 3 weeks. Available as 2 mg tablets	Multiple myeloma and melanoma	
4.	Busulfan: 10 mg for 3 weeks	Chronic myeloid leukaemia	Pulmonary fibrosis
5.	Chlorambucil: 10 mg for 3 weeks	Chronic lymphatic leukaemia	
6.	Methotrexate: 2.5-5 mg/d orally;10 mg intrathecally 1-2 times a week	Choriocarcinoma, ALL, soft tissue sarcoma, breast cancer	Oral and GIT ulceration, bone marrow suppression, hepatic damage
7.	6-Mercaptopurine Dose: 2.5 mg/kg/d orally	Leukaemias and choriocarcinoma	Hyperuricaemia
8.	5-Fluorouracil Dose:15 mg/kg/d IV	Adenocarcinomas of GIT, breast cancers and cancer cervix	Neurotoxicity, stomatitis, bone marrow suppression
9.	Vinca Alkaloids.		
	Vincristine: Dose:1.5 mg/sq.m	Leukaemia	Neurotoxic
	Vinblastine: Dose: 0.1mg/kg body weight	Hodgkin's lymphoma	Bone marrow toxicity
10.	Rubidomycin: Dose: 40 mg/m/ day IV	Acute myeloblastic leukaemia	Myocardial depressant
11.	Adriamycin: 60 mg/m^2 IV	NHL, hepatoma, medullary carcinoma thyroid, osteosarcoma and soft-tissue sarcomas	Cardiotoxic
12.	0'-p DDD(Mitotane): Dose: 10 gm orally for 8 weeks	Carcinoma adrenal cortex	
13.	Bleomycin: 20 units IV or IM	Squamous cell carcinoma of skin and other regions and lymphomas	Pulmonary fibrosis
14.	Cytosine arabinoside Dose: 4 mg/Kg IV	Leukaemias and lymphomas	Leukopenia and thrombocytopenia
15.	Lomustine (CCNU) and Carmustine (BCNU)	Brain tumours and lymphomas	
16.	Procarbazine:	Hodgkin's lymphoma and Oat cell carcinoma lung	Bone marrow and CNS depression
17.	Cisplatin: Dose:20 mg/m^2/d	Testicular and ovarian tumours	Nephrotoxicity
18.	Etoposide: Dose: 100 mg/sq.m	Testicular tumour, bladder tumour, lymphomas	
19.	Hydroxyureas:	Myeloma, leukaemias	

> *Life so short, the craft so long to learn.*—Hippocrates

3. *Antibiotics:* Actinomycin-D, mitomycin, doxorubicin, bleomycin.
4. *Vinca alkaloids:* Vincristine, vinblastin.
5. *Miscellaneous:* Cisplatin, procarbazine.

II. Classification of antimalignancy drugs based on the action on cell cycle

S-phase specific agents: Cytosine arabinoside, hydroxyurea, 6-mercaptopurine.

M-phase specific agents: Vincristine, vinblastine, palcitaxel.

Phase nonspecific agents: Alkylating agents, nitrosoureas, antitumour drugs, procarbazine, cis-platin, dacarbazine.

Mode of Action

These drugs damage the active cells by affecting the process of cell division. Hence, they also affect haemopoiesis, cellular activity, epithelial tissues and gonads. They also suppress the immune system.

Adverse Effects in General

Bone marrow suppression, alopecia, hepatotoxicity, nephrotoxicity, damage to gonads, damage to GI mucosa and ulceration.

HORMONE THERAPY IN CANCER

Ablative Procedures

- Oophorectomy and adrenalectomy in carcinoma breast.
- Orchidectomy in carcinoma prostate.

Added Hormone

- Prednisolone, progestogens, estrogens and androgens.

Hormone Antagonists

- Tamoxifen is estrogen receptor antagonist. Estrogen receptor level is assayed. If it is more than 10 units/ gm of tissue, it is called as ER positive and if less than 10 units, it is called as ER negative.
- Cyproterone acetate, competes with testosterone for binding receptors.
- LHRH analogue—Goserelin (Zoladex) acts as an antagonist to carcinoma breast.
- Phosphorylated diethylstilbestrol (Honavan) is used in carcinoma prostate.

Drugs that Interfere with Hormone Synthesis or Release

- Aminoglutethimide is an adrenal inhibitor. It is also an aromatase inhibitor inhibiting the peripheral conversion of androstenedione to estrogen.
- *Papillary carcinoma of thyroid is (TSH) hormone dependent.* TSH can be very well-suppressed by giving L-thyroxine, suppressive dose, daily 0.3 mg for life long.

Steroids (corticosteroids) are used as component of chemotherapy regime. They also improve the anorexia and also control hypercalcaemia seen in patients with malignancies on treatment. They reduce cerebral oedema in intracranial malignant neoplasms.

IMMUNOSUPPRESSION

- It is mainly used in transplantation to prevent graft rejection, e.g. in transplantation of kidney, liver, heart, small bowel, pancreas.

Drugs used are—

- *Azathioprine* (Imuran, Purine analogue)—Inhibits purine synthesis.
- *Cyclosporine:* It is a very good immunosuppressant, derived from fungus. It causes inhibition of lymphocytic activity, delayed hypersensitivity, interleukins, memory cells, etc. It binds to cyclophilin, decreases IL-2 and other cytokine release from T cells. It is initially given intravenously and later given orally. It is given usually for long duration, for 12-24 months. It is *nephrotoxic* as well as *bone marrow suppressant*. So, constant monitoring by blood urea, serum creatinine, blood count, Hb% at regular intervals is required. Dose should be adjusted depending on these parameters. Cyclosporine is very effective immunosuppressant in transplantation.
- Antilymphocytic globulin—Antibodies against T-cell receptors (CD_2, CD_3, CD_4, CD_8), B-cells and macrophages.
- Steroids (methylprednisolone)—Alters transcription and translation, affects T-cells and macrophages.
- Cytosine arabinoside—anti-inflammatory and immunosuppressive effect.
- Tacrolimus (FK506)—Bind to FK binding proteins, effects are similar to cyclosporine.
- OKT3—Acts against CD3 and T-cells.
- Mycophenolate Mofetil—Inhibits inosine monophoshate, affects lymphocytes.

Types of Immunosuppression

1. *Induction regimens* — Mainly aims to avoid rejection and to establish a good graft function during the immediate post-transplant weeks (2 weeks). Anti-lymphocytic sera, along with either cyclosporine or azathioprine or steroids are used here.

2. *Antirejection regimens*—It aims at reversing the acute rejections. High dose steroids and antilymphocytic sera are used here.
3. *Maintenance therapy*—Using cyclosporine or FK506 along with steroids and azathioprine.

Complications

- Infection—Commonest
- Malignancy—Squamous cell carcinoma, lymphoma, Kaposi's sarcoma
- Nephrotoxicity
- Bone marrow toxicity
- GIT toxicity
- Neurotoxicity

IMMUNOTHERAPY

It is enhancing the host response of patient whenever required, commonly against malignant cells. Often it is used in other conditions also, where there is severe immunosuppression due to any reason like bone marrow suppression or in specific conditions like severe hepatitis.

Immunotherapy can be

- Active
- Passive
- Restorative
- Adaptive

Immunotherapy agents

- Monoclonal antibodies.
- Bone marrow transplantation.
- Cell transfer.
- Lymphokines.
- Thymic hormones.
- Levamisole and BCG (as immuno modulators).
- Prostaglandins.
- Interferons, Interleukins.
- Immunoglobulins.
- Antibody derived specific to certain tumour like melanoma.

Tumours where immunotherapy is used

- Melanoma
- Bladder tumour
- Carcinoma colon
- Renal cell carcinoma
- In many tumours it is under trial

Disadvantages

- Very costly.
- Nonavailability.
- Effect is not 100%.

HYBRIDOMA

- It is a biotechnological process wherein *multiplication* property of *Myeloma cells* is combined with *synthetic* property of some other required cells, *to achieve rapid* and large quantity manufacturing of required chemical.
- Myeloma cells with only retained multiplication activity is fused with human cells or lymphocytes or other cells (of nature to produce the required product) by ***hybridisation***. The resulting cell has got the capacity to multiply rapidly and to produce required product in large quantity. It is called as ***hybridoma***.
- It is used to generate monoclonal antibodies, insulin and many other antibodies, immunoglobulins, etc.

Monoclonal antibodies are used for

- Immunodiagnosis—For radioimmunoassay, radio nuclide scan
- Antibody for detection of tumour antigen
- For cancer therapy
- For serotherapy
- As conjugates (with drugs, toxins, isotopes)
- For production of other chemicals and as a *research tool*

GENE THERAPY

The ability to alter specific genes of interest is, nowadays an exciting and powerful tool in the potential management of a wide range of diseases. Instead of giving a patient a drug to treat or control the symptoms of the genetic disorder, physicians may be capable of treating the basic problem by altering the genetic makeup of the patient's cell.

Typically two methods have been considered : Germ line and somatic cell gene therapy.

- *Germ cell therapy* involves insertion of a gene into fertilised egg for the correction of a genetic disease. Because these genes are dispersed throughout the tissues of the egg, they end up in the germ cells of the foetus, and hence are passed on to the future generations.
- *Somatic cell therapy* involves the insertion of genes or otherwise manipulating the gene machinery of a cell to treat a disease. In this case the cells are restricted to the population that has been treated and any genetic change remains restricted to these cells and is not passed onto the germ cell line.

It is better to light a small candle than to curse the darkness.

The goals of human somatic therapy are usually one of the following:

- To repair or compensate for a defective gene.
- To enhance the immune response directed at a tumour or pathogen.
- To protect vulnerable cell populations against treatments such as chemotherapy.
- To kill tumour cells directly.

Several single gene disorders are candidates for gene therapy and in addition, current thinking has expanded to include treatment of AIDS and atherosclersis using gene therapy techniques.

Vectors used for gene therapy fall into ***two main classes***—*Viral and non-viral.*

- **Viral:** Initially retroviruses were used as vectors. Other potential vectors include Adenovirus, Herpes virus and Vaccinia virus.
- **Non-viral systems**
  - Liposome mediated DNA transfer.
  - DNA protein conjugates.

However exciting and appealing the prospects of gene therapy may appear, this technique is still in the experimental stages.

Self-assessment Questions

- Hybridoma.
- Brachytherapy.
- Hormone therapy.
- Cyclosporine.
- Cell cycle.
- Immunosuppressants.
- Immunotherapy.
- Gene therapy.
- Monoclonal antibodies.

30

Anaesthesia

> ***It has long been an important problem in medical science to devise some method of mitigating the pain of surgical operations. An efficient agent for this purpose has at length been discovered. A patient has been rendered completely insensible during an amputation of the thigh, regaining consciousness after a short interval.***
>
> **— Henry Jacob Bigelow,** 1846

Preoperative assessment
General anaesthesia
Regional anaesthesia
Spinal anaesthesia
Epidural anaesthesia

PREOPERATIVE ASSESSMENT

History

1. Chronic cough, smoking, alcohol, drug intake, drug allergy.
2. Any previous diseases like hypertension, diabetes mellitus, epilepsy, bronchial asthma, tuberculosis, hepatitis, cardiac diseases.
3. Drug therapy: Steroids, antihypertensives, sedatives, antibiotics, antiepileptics.

Examination

General: Posture, teeth, mouth opening, dilated veins, neck movements, tremor, airway.

Anaemia, oedema, jaundice, cyanosis.

Respiratory system: To look for asthma, tuberculosis, emphysema, COPD.

Airway: Mouth opening, Mallampati scoring, thyromental distance, temporomandibular joint assessment.

Thyromental distance: It is the distance between mentum and thyroid cartilage, measured externally. If it is more than 6.5 cm (i.e. more than 4 fingers breadth) intubation is easier, if it is less than 6.5 cm intubation is difficult.

Cardiovascular system: Hypertension, ischaemic heart disease, arrhythmias, cardiac failure, valvular diseases.

Spine: Curvature, intervertebral space, skin over the area for any infection.

Other systems: Abdomen, skeletal system.

Scoring to assess intubation

Mallampati scoring:
Class I — Faucial pillar, soft palate, uvula are seen
Class II — Faucial pillar, soft palate are seen
Class III — Only soft palate is seen

Samsons Young modification:
Class IV — Only hard palate seen
Class I, II: Easy intubation
Class III, IV: Difficult intubation

Preoperative Investigations

Haematocrit, blood sugar, blood urea, serum creatinine, electrolytes, chest-X ray, ECG, blood grouping, blood-gas analysis, cardiac assessment.

Preoperative Treatment

- Control of respiratory and cardiac diseases.
- Improvement of Hb% status, if anaemia is present.

> *When giving mouth-to-mouth resuscitation, the important thing to remember is to remove your denture first.*
>
> —W.U. McClenahan

- Preoperative antibiotics are given.
- Blood should be kept ready for major cases.
- *Starvation for 4 hours for liquids and six hours for solids.*
- Bladder and bowel should be emptied to prevent soiling on the operation table. Urinary catheter may be passed and enema may be given.
- Dentures, contact lenses, jewellery must be removed.
- Surgical area should be cleaned and properly prepared.

GENERAL ANAESTHESIA

It means abolition of all sensations, i.e. touch, pain, posture and temperature with a state of reversible loss of consciousness.

It has got three components:

1) Analgesia. 2) Hypnosis. 3) Muscle relaxation.

ANAESTHETIC AGENTS

- ***Volatile anaesthetics*:** They vaporise in room air.
  - Agents used are: Ether, trichloroethylene, halothane, enflurane, isoflurane, sevoflurane.
  - *Ether* which is irritant, unpleasant, flammable, is commonly used agent in developing countries.
  - Enflurane and isoflurane are non-inflammable, non-explosive, non irritant, stable. Here anaesthesia is rapid with faster recovery.
- ***Gaseous anaesthetics*:**
  - *Nitrous oxide*: It is non inflammable, non irritant, good analgesic but weak anaesthetic agent. It is given along with 30-50% oxygen for balanced anaesthesia (blue coloured cylinder in India).
  - Cyclopropane is highly flammable.
- ***Intravenous anaesthetics*:**
  - *Thiopentone*: It is ultra short acting barbiturate which causes hypnosis during induction of anaesthesia. It does not have analgesic effect. It causes hypotension, respiratory depression, laryngeal and bronchospasm. Recovery is rapid. Extravasation of drug can cause skin ulceration. Intra-arterial injection causes vasospasm and gangrene. Dose: 4-7 mg/kg.
    Methohexitone sodium.
    Propanidid. 4-7 mg/kg. It can cause anaphylaxis.
  - *Ketamine:* Dose: 2 mg/kg IV. It is a good analgesic. It causes dissociative anaesthesia. It can lead to hypertension, apnoea, laryngospasm. In children it can be given IM-5 mg/kg. It does not require intubation for small procedures.
  - *Propofol*: It is widely used induction agent which has got predictable onset and recovery. It has got least side effects on CVS and respiratory system. It is also used for total IV anaesthesia. Dose: 1-2.5 mg/kg.
  - Fentanyl is neuroleptanalgesic. It causes sedation, catatonia, dissociation, hypotension and preferred in asthmatics.

OXYGEN

- Oxygen is given through Boyles apparatus (33.3%).
- Oxygen in high concentration is respiratory depressant and also affects eyes.
- A 5% CO_2 mixture in oxygen is called as carbogen.
- Oxygen is available in black and white coloured cylinder.

MUSCLE RELAXANTS

Depolarising Muscle Relaxants

They act at the level of acetylcholine receptors which widens the refractory period after depolarisation causing paralysis. It is short acting muscle relaxant.

a. *Suxamethonium chloride (scoline)*:
  - It lasts for 2-4 minutes.
  - It causes muscle twitching—fasciculations—paralysis.
  - It is metabolised by plasma pseudocholinesterase. Atypical or deficiency of this enzyme prolongs the action of the scoline.
  - *Side effects* are hyperkalaemia, myotonia, apnoea and cardiac arrest.

b. *Suxthonium bromide.*

Non-Depolarising Muscle Relaxants

They block the channels of entry of acetylcholine. They are long acting relaxants.

1. *Tubocurarine*: It lasts for 45 minutes. 30 mg is the dose.
2. *Gallamine. (Flaxedil*): Dose is 1-2 mg/kg. It is cheaper. It is contraindicated in renal diseases.
3. *Pancuronium bromide (Pavulon*): It is synthetic steroid muscle relaxant. It's action lasts for 45 minutes. Dose is 0.08-0.1 mg/kg.
4. *Vecuronium bromide*: It is a steroid muscle relaxant, given at a dose of 0.05-0.1 mg/kg.
5. *Rocuronium is* short acting steroid muscle relaxant. It starts its action in one minute.
6. *Atracurium*: It lasts for 20-30 minutes. Dose is 0.6 mg/kg.
7. *Mivacurium*: Dose is 0.15-0.25 mg/kg.

REVERSAL AGENTS

They are anticholinesterase drugs which increase the acetylcholine and thus act as antagonising agents for non depolarising muscle relaxants. They cause bradycardia.

Neostigmine (2.5 mg) is used commonly along with atropine (1.2 mg).

Edrophonium (short acting) and pyridostigmine (long acting) are other drugs.

INSTRUMENTS IN ANAESTHESIA



Fig. 30.1: Different sized airways have different colours.



Fig. 30.2: Different sized masks used during anaesthesia.



Fig. 30.3: Boyle's apparatus used for anaesthesia.



Fig. 30.4: Direct laryngoscope with endotracheal tube and tongue depressor.

1. ***Boyle's apparatus***—
   It consists of—
   a. Cylinders for N_2O and O_2.
   b. Pressure guage – to know the amount of gas remaining.
   c. Pressure regulator – to regulate the pressure of gas used.
   d. Rotameter – to know the flow of gas.
   e Vaporiser.

   Note: Pin index code: It is safety mechanism to fix gas cylinder onto the Boyle's machine. Different gases have different pin index codes, so that interchanging of cylinders does not take place.
   Pin index code for N_2O is 3, 5.
   Pin index code for O_2 is 2, 5.
   Pin index code for air is 1, 5.
2. ***Endotracheal tube*****:** These are tubes inserted into the trachea and is used to conduct gases and vapours to and from the lungs. Depending on the diameter, it is available in various sizes. It has a cuff at one end which, when inflated stabilises the tube in position and also prevents regurgitation. Non cuffed tubes are also available. The other end near the mouth is connected to the breathing circuit through which anaesthetic gases are delivered. The tube is inserted using a direct laryngoscope. The proper placement in the airway is confirmed by auscultating for the breath sounds over the chest when the gases are delivered.

Complication
- Postoperative sore throat
- Hoarseness after intubation
- Upper airway oedema

3. Magill's forceps.
4. Mouth gag.

The future belongs to those who believe in the beauty of their dreams.



Fig. 30.5: Magill's forceps.

5. Laryngoscope.
6. Connectors.
7. ***Laryngeal mask airway (LMA):***
    - Laryngeal mask consists of a wide bore tube whose proximal end connects to breathing circuit and distal end is attached to an elliptical cuff which can be inflated.
    - These come in various sizes for various age groups. It is made up of silicon rubber.
    - The deflated cuff is lubricated and inserted into the hypopharynx, so that once inflated, the cuff forms a low pressure seal around the entrance into the larynx.



Figs 30.6A and B: Laryngeal Mask Airway and curved endotracheal tube. LMA is used in small procedures where a short period anaesthesia is needed. Mask which is inflatable is intubated so as to snugly fit into the opening of larynx once inflated.

Advantages

- Does not require laryngoscope for insertion
- Does not cause irritation of airway
- Less incidence of laryngospasm
- In case of inability to intubate can save the life of the patient

Contraindications

- Pharyngeal pathology
- Full stomach as it can cause aspiration
- Bronchospasm

Components of general anaesthesia

- Premedication
- Induction
- Maintenance
- Recovery

Premedication

It is given one hour before surgery:

- *For sedation and relief of anxiety.* Pethidine 50 mg/ morphine 10 mg/diazepam 10 mg, midazolam 1-2.5 mg.
- To suppress vagal activity. Atropine 0.6 mg IM.
- *To reduce vomiting.* Promethazine (phenargan) 12.5 mg.

Induction: Patient is preoxygenated with 100% oxygen for 3 minutes then induced with IV thiopentone, given 4-5 mg/kg. Patient *loses consciousness*. Induction is maintained by 67% nitrous oxide and 33% oxygen.

Scoline is given IV to relax muscles so as to facilitate *endotracheal intubation*.

Once intubated, *ventilation* can be either *controlled* using muscle relaxants or *spontaneous* using a volatile anaesthetic agent.

Reversal is done using neostigmine and atropine or glycopyrrolate.

COMPLICATIONS OF GENERAL ANAESTHESIA

- Intra-arterial injection of the drug.
- Myocardial depression and cardiac arrest.
- Hypertension.
- Laryngeal and bronchial spasm.
- Cardiac arrhythmias.
- Respiratory failure.
- ARDS.
- ***Mendelson's syndrome***: It is due to regurgitation of the acid from the stomach causing aspiration of acid leading into bronchospasm, pulmonary oedema and circulatory failure. This is treated with oxygen, suction, hydrocortisone, aminophylline, antibiotics, Ryle's tube aspiration and ventilator support.

- Hypoxia.
- Pneumothorax.
- Anaphylaxis.
- ***Malignant hyperthermia***: It is an inherited myopathic disorder occurs under anaesthesia due to drugs like halothane, scoline. There is marked increase in metabolic rate, with rise of temperature. There is high levels of CPK enzyme. Condition will cause metabolic acidosis and hyperkalaemia. It has got high mortality. Treatment is IV dantrolene, cooling, oxygen and cold IV fluids.
- Hypothermia.

POSTOPERATIVE CARE

Immediate postoperative period is important and critical, because patient may not be fully conscious. Patient should be kept in recovery room until he/she recovers from anaesthesia.

1. Care of respiratory system: Adequate breathing is important, otherwise hypoxia sets in, which gradually leads to cardiac arrest.
   Respiratory problems may be:
   - Laryngeal spasm
   - Falling of tongue backwards blocking the air way
   - Aspiration
   - Bronchospasm
   - ARDS
   - Respiratory failure

   Oxygen supplement through mask, observation, proper positioning are the treatment.
2. Hypercarbia.
3. Circulatory problems:
   - Hypotension
   - Arrhythmias
   - Hypertension
   - Cardiac arrest
4. GIT:
   - Vomiting
   - Regurgitation
   - Mendelson's syndrome
5. Renal problems: Oliguria, i.e urine output is less than 30 ml/hour. It may be due hypovolaemia, hypotension, acidosis, sepsis, transfusion reaction, toxins.

   The ratio of urine/plasma osmolality of 2:1 signifies pre-renal failure. Ratio of 1.7:1 indicates renal failure.

   Blood urea and serum creatinine is done at regular intervals.

   Fluid and electrolyte imbalance, if any is corrected.

   100 ml 20 % mannitol or frusemide 40-80 mg are often required.
6. Other problems:
   Restlessness, shivering, pain.

MONITORING THE POSTOPERATIVE PATIENT

- Pulse, temperature, BP chart.
- Breathing type.
- Level of consciousness.
- Urine output.
- Oxygen saturation and heart rate using pulse oximeter.
- Checking and encouraging limb movements.
- Skin colour, tongue colour for adequacy of oxygenation.
- Tongue for hydration.
- Cardiac monitor.
- Blood gas analysis in case of patient on ventilator.
- Serum electrolytes assessment.

REGIONAL ANAESTHESIA

Carl Koller, an ophthalmologist introduced cocaine as local anaesthetic in ophthalmic practice.

Mode of action: It causes temporary conduction block of the nerve, thus preventing the propagation of nerve impulse.

Advantages of local anaesthetic agent:

- Technically simpler.
- General anaesthesia is avoided.
- Consciousness is retained.
- Patient can have food earlier after surgery.

Drugs used:

- Cocaine, procaine, cinchocaine—amino esters.
- Lignocaine, prilocaine, bupivacaine, ropivacaine—amino amides.

Lignocaine/lidocaine/xylocaine: It is the commonest local anaesthetic agent used. It is available as 0.25 – 5% concentrations.

It is metabolized in the liver and excreted in the kidney as xylidines. It is also an antiarrhythmic drug and so commonly used in cardiology and cardiac surgery.

Side effects: Giddiness, headache, postural hypotension, tinnitus, circumoral anaesthesia.

Dose: 4 mg/kg effect lasts for 90 minutes.

Greater the obstacle more the glory in overcoming it.

Uses

- Topical-4%.
- Infiltration block: 0.25%.
- Field block 0.5%.
- Nerve block 1.0 %.
- Epidural 1.5, 2.0%.
- Spinal 5%.

It can be used with or without adrenaline.

Xylocaine with adrenaline has got longer duration of action. It creates relatively bloodless field.

But it should not be used in places where end arteries are present like glans penis, ear lobule, tip of the nose, lip, fingers and toes.

Bupivacaine (Marcaine): It has got prolonged action. It is a vasodilator also.

Dose: 3 mg/kg.
Epidural block: 0.5%
Spinal 0.5% 3 ml.

TOPICAL ANAESTHESIA

- It is used for minor surgeries of eye, laryngoscopy, bronchoscopy, cystoscopy, gastroscopy.
- It is available as instillation, spray, viscous, ointment, gel, EMLA (Eutectic mixture of local anaesthetic).

INFILTRATION BLOCK

Direct injection of local anaesthetic under the skin for small procedures.

FIELD BLOCK

It is achieved by blocking the entire field of excision where lesion is located.

NERVE BLOCK

- Block of inferior dental nerve and lingual nerves in the region of the mental foramen for extraction of teeth.
- Finger block of digital nerves. Here plain xylocaine is used (without adrenaline).
- Intercostal block.
- Ankle block.
- Median and ulnar nerve block.
- Brachial plexus block *(Winnie's block):*
  It can be given through–
  - Interscalene,
  - Axillary,
  - Supraclavicular approaches.

Supraclavicular approach is commonly used. 1 cm above the mid-point of the clavicle, needle is passed downwards, backwards and medially towards first rib. Once needle hits the first rib, 15-20 ml of 1.5% xylocaine is injected (with walking or stepping over the first rib). Complications are pneumothorax and injury to the great vessels.

Other blocks:

Cervical plexus block.
Sciatic nerve block.
Femoral nerve block.

INTRAVENOUS REGIONAL ANAESTHESIA (BIER'S BLOCK)

Limb is exsanguinated and occluded with tourniquet. Pressure in the tourniquet must be 30 mmHg more than the systolic pressure of the patient. Needle is placed in the selected vein. 40 ml of 0.5% xylocaine for upper limb and 80 ml of 0.25% of xylocaine for lower limb is injected into the vein. *Xylocaine with adrenaline should not be used***.** It gives very good analgesia for 2 hours.

Side effects: Sudden release of drug into the circulation can cause hypotension, convulsions and often death.

Bupivacaine should not be used.

Indications

For upper and lower limb surgeries, it can be used without G/A or S/A.

SPINAL ANAESTHESIA

It is the injection of local anaesthetic into the subarachnoid space causing loss of sympathetic tone, sensation and motor function. The sympathetic block is 3 segments higher than sensory block, motor block is 3 segments lower than sensory block.

Position: Lateral decubitus position with head, hips and knees being fully flexed so as to open the inter-laminar spaces. Highest point of iliac crest corresponds to 4th lumbar vertebra.

Drugs used:

Lignocaine 5% in 6% dextrose, 2 ml.
Bupivacaine 0.5% in 5% dextrose, 3 ml.
Cinchocaine 0.5% in 6% dextrose, 2 ml.

Technique: 24-26 gauge needle with stillette is used. Needle is passed through the interspinous space and ligamentum flavum to reach the subarachnoid space to get clear fluid (0.5 ml/ sec). Needle is rotated 360 degrees and drug is injected slowly. Patient is repositioned to supine. Drug takes 15 minutes to act.

Types

1. Caudal (up to L_5)
2. Low spinal (up to L_1)
3. Mid-spinal (up to T_{10})
4. High spinal (up to T_6)
5. Unilateral spinal.

Advantages

- Economical
- Hypotension reduces the bleeding
- Adequate relaxation is achieved
- Respiratory complications are less



Fig. 30.7: Spinal anaesthesia being given. Note the position of the patient.

Disadvantages and Complications

- CSF leak and aseptic inflammation of meninges causing headache.
- Meningism.
- Infection.
- Paraplegia. It is very rare.
- Occasionally it can become total spinal which requires intubation and ventilator support.

Contraindications

- Cardiac patient
- Allergy
- Increased intracranial pressure. It may precipitate coning
- Sepsis
- Spinal tumours
- Back pain and spinal diseases
- Neurological conditions like syringomyelia
- Kyphosis, scoliosis

SADDLE BLOCK

- It is used for surgeries in perineal and anorectal region.
- It is spinal anaesthesia using xylocaine or bupivacaine given in sitting position.

EPIDURAL ANAESTHESIA

- It is a potential space between dura anteriorly and ligamentum flavum posteriorly which has got negative pressure inside. It extends from foramen magnum to sacral haitus.
- ***Touhy needle*** **is** used for epidural anaesthesia. Once the needle is in the space there will be sudden indrawing of air or saline drop.
- An epidural catheter is placed in the space and fixed. 2% xylocaine with adrenaline or 0.5% bupivacaine is injected into the space to achieve anaesthesia up to the desired level.



Fig. 30.8: Epidural anaesthesia with epidural catheter placed.

Advantages

- It can be used for continuous repeated prolonged anaesthesia.
- It can be used for postoperative analgesia.
- It can be kept for several days.

CAUDAL ANAESTHESIA

Caudal space is the sacral component of epidural space and access is through the sacral hiatus.

We should have a good heart to pity; a good hand to bless.

Indications

- Haemorrhoidal surgery
- Circumcision
- Small procedures in the perineum like cystoscopy

Procedure

It is given in lateral position. Needle is inserted through the sacral hiatus to enter the caudal epidural space. Drug is then injected into the space.

Complications

- Trauma to anal canal
- Intravascular injection
- Failure of caudal block

Self-assessment Questions

- Epidural anaesthesia.
- Spinal anaesthesia.
- Xylocaine.
- Bupivacaine.
- Caudal anaesthesia.
- Complications of general anaesthesia.
- Saddle block.
- Field anaesthesia.
- Bier's block.

31

Advanced Imaging Methods

> ***What would it be like in a radiologist's shoes? To spend most of my day dealing with images of people: plain black-and-white X-ray images, or speckled images caused by sound waves bouncing off organs, or images caused by dyes outlining arteries and veins, or contrast medium filling loops of bowel, or images reconstructed by computers into cross sections of the body-all without speaking to a patient.***
>
> **—Abraham Verghese,** 1994

Ultrasound
Doppler
CT scan
MRI
Radionuclide imaging
PET scan

ULTRASOUND

Ultrasound contains waves with a frequency of more than 20,000 cycles/second which the human ears cannot hear.

In medical sonography, frequencies used are commonly 2-10 MHz. The transducer or the probe works as both transmitter of ***sound waves*** and receiver of ***echoes.*** The piezoelectric crystal is the producer of ultrasound waves. Received signals from the patient are fed into the computer which forms the image.

There are three types of ultrasound image display.

1. **A-mode**: Only one dimensional static display as spikes are obtained. It is used only in eye scan.
2. **B-mode**: Two dimensional real time images in the form of grains. It is most widely used type. Using this mode *Transverse, Longitudinal or Oblique* sections can be taken.
3. **M-mode**: Here images are recorded as dots. It is mainly used in moving parts like echocardiography. M-mode is also called as TM mode, i.e. *Time Motion Mode.*

Uses

1. Used in all abdominal and pelvic conditions, often in thoracic conditions.
2. ***Ultrasound of thyroid*** is very useful method to differentiate between solid and cystic lesions.
3. Ultrasound is used in testicular tumours, epididymo-orchitis, trauma to testis, erectile dysfunction etc.
4. Ultrasound breast is used to differentiate solid from cystic tumours.
5. Soft tissue and musculoskeletal ultrasound.
6. Ocular ultrasound is ideal method to image eye and intraocular structures.

Advantages

- No radiation
- Non-invasive
- Effective with efficiency
- Painless
- Low cost
- Available even as portable machines
- Stones are well visualised with *acoustic shadow*

Disadvantages

- Interpretation can be inadequate
- Bowel shadow may prevent proper visualisation
- In obese patient image will be inadequate
- **Interpretation** is based on echogenicity either *hyperechogenic* or *hypoechogenic*

It's your imagination that can take you anywhere.


ANEURYSM OF ABD. AORTA
LONG
TRANS

Fig. 31.1: US showing abdominal aortic aneurysm.



Fig. 31.2: US showing appendix—appendicitis.


LIVER
LIVER

Fig. 31.3: US showing liver mass.


CRANIAL SONOGRAPHY
LV
3
4

Fig. 31.4: Cranial sonography is done to see intracranial problems through suture lines—usually done in infants and children.


THYROID
TRACHEA
RT. LOBE
LT. LOBE
A
RT. LOBE-THYROID
B

Figs 31.5A and B: US thyroid showing thyroid both lobes in one; solid and cystic components in another.



Fig. 31.6: US picture of a pelvic mass.

Advanced ultrasound techniques

1. Endosonography (EUS) is used in visualisation of walls of oesophagus or stomach through gastroscopy
2. Transvaginal ultrasound
3. Transrectal ultrasound to see prostate
4. Doppler ultrasound to study arterial and venous diseases

Ultrasound as therapeutic use

- To guide aspiration of amoebic liver abscess, pericardial tap
- On table ultrasound can be done to assess the operability of tumour. (During laparotomy to assess the extent of tumour, lymph node status etc.)

DOPPLER

Doppler effect is a change in the perceived frequency of sound emitted by a ***moving source***. So it measures blood flow. Spectral Doppler wave form and ultrasound image are combined in **Duplex scanning**.

Types

1. Continuous waves.
2. Pulsed waves.

Doppler will provide both audio and video signals. ***Colour Doppler imaging displays*** flowing blood as ***red*** when direction of flow is towards the transducer. Image will be ***blue*** if flow is away from transducer.

Uses

- To study cardiovascular system.
- To study vascularity of tumours.
- To study blood flow and velocity in arterial diseases so as to assess stenosis (its extent, cause etc.) like in atherosclerosis, TAO, cervical rib, aneurysm, A-V fistulas.
- To find out deep venous thrombosis (DVT), varicose veins, perforator incompetence.
- To study grade of varicocele in males.

Advantages

- It has replaced venogram and angiogram in many places as a diagnostic tool.
- It is reliable and non-invasive.

CT SCAN

Computerised tomography scan was invented by ***Godfrey Hounsfield*** in 1963. He was a physicist. He received **Nobel prize** (1972) for the same. The first CAT scan is in the London museum.

Narrow X-ray beams are passed from rotating X-ray generator through **the gantry** where patient is placed. When X-rays pass through the tissues, some of the X-rays get absorbed and some pass through, depending on the tissue density. The different grades of absorption in different tissues are detected through sensitive detectors which are translated to a Gray scale image by a computer.

Density of tissues is numbered as **Hounsfield Number (HN)**

- Water—Zero HN
- Air—Minus 1,000
- Bone—Plus 1,000

The density of other tissues come in between air and bone with different HNs

Presently spiral CT scan has become popular. They are faster and in a single breath holding time, whole CT scan can be taken.

Both plain and contrast CTs are done whenever required.

Contrast Agents

- **Ionic**: Water soluble iodide dyes like *Sodium diatrizoate, Meglumine iothalamate (Conray, Urograffin, Angiograffin).* They are cheaper but often toxic and cause anaphylaxis.
- **Non-ionic are** safer but expensive, like *Iohexol (Omnipaque), Iopamiro.*

Ultrasound and CT scan are conveyors of morphological information.

In abdominal CT, contrast agents can be given orally to delineate bowel properly.



Fig. 31.7: CT scan picture showing liver secondaries.



Fig. 31.8: CT scan showing ascites (gross).



Fig. 31.9: CT scan abdomen showing right renal mass (RCC).

Indications

- **Trauma** like head injury, chest injury, abdomen trauma. In trauma *only plain CT scan* is taken.
- **Neoplasms:** To see the exact location, size, vascularity, extent and operability.
  For example, brain, abdominal, retroperitoneal, thoracic and spinal tumours.
- **Inflammatory conditions,** in various sites.
  For example, psoas abscess, pseudocyst of pancreas.



Fig. 31.10: CT scan showing retroperitoneal tumour.



Fig. 31.11: CT scan showing brain secondaries. Secondaries are the commonest malignant tumours of brain. Breast is the common site of primary.

Advantages of CT scan

- One to 2 mm sized sections are possible
- Amount of exposure to radiation is less
- More accurate, sensitive, and specific
- Small lesions are also detected
- CT guided biopsies are done at present, safely



Fig. 31.12: CT picture showing astrocytoma.

Disadvantages

- **Interpretation** by an experienced radiologist is important
- **Artefacts** can be present
- **Cost factor** and **availability**

Findings

- Extradural haematoma—*Biconvex lesion.*
- Subdural haematoma—*Concavoconvex lesion*.
- Smooth margin in benign condition.
- Irregular margin in malignant condition.

Advantages of spiral CT scan

- Reduced scan time. Useful in children and critically ill-patients
- Imaging in both arterial and venous phases is possible
- Improved lesion detection. Missing a lesion is uncommon
- Multiplanar and 3-dimensional analysis like CT angiography, complex joint imaging, facial bone imaging is possible

High resolution CT *(HRCT)* is a CT technique used in chest scan where thin sections are taken to have better quality images.

MAGNETIC RESONANCE IMAGING (MRI)

Earlier, named as *Nuclear magnetic imaging*, the term is not used now.

It can be **Plain MRI** or **Contrast MRI**. Contrast agent is *Gadolinium,* given intravenously**.**

Principle

When patient is placed in an *external high magnetic field*, protons of hydrogen atoms rotate in phase with each other and gradually return to their original position releasing small amounts of energy which is detected by sensitive coils. Proton density and relaxation time are assessed by radiofrequency pulse and the computer generates a Gray scale image from this data.

T1 relaxation time is the time taken to return to original axis. *T1 images* are used to find out *normal anatomical details.* It has got high soft tissue discrimination. Here fluid (CSF) looks black.

T2 relaxation time is the time taken by the proton to diphase. It is used to assess *pathological processes. In T2 images* fluid looks white.

In proton density images fluid looks in between black and white.



Fig. 31.13: MRI showing spine tuberculosis. Note the lesion and vertebral collapse.

Radioisotope studies are indicators of physiological processes



Fig. 31.14: MRI showing AV malformation.



Fig. 31.15: MRI picture, which shows extra-dural schwannoma.

Uses of MRI

- It is very useful in intracranial, spinal and musculoskeletal lesions including *joint pathologies.*
- It gives direct anatomical sections of the area, with lesions at a high resolution.
- **MR angiogram** is done without injecting IV contrast agents.
- **Cardiac MRI is** very useful.
- **Breast MRI** is used in multifocal recurrent cancers.
- **Magnetic resonance cholangiopancreatography** (*MRCP*) is a very useful noncontrast diagnostic tool which may replace diagnostic ERCP.
- **MR spectroscopy** is chemical analysis of elements in a tissue to differentiate between tumour, inflammation, and degeneration.

Advantages

- Artefacts are not common.
- More sensitive and specific than CT scan.

Contraindications

Patients with ***prosthesis in the body, metallic foreign bodies, pacemakers, cochlear implants, cranial aneurysm clips should never*** undergo MRI

Precaution

Before entering the MRI room, the patient and other personnel should remove all magnetically attractive materials

Disadvantages

- ***Availability*** and ***cost factor.***
- It is time consuming.
- Patient compliance is poor.
- It is not feasible in patients suffering from ***Claustrophobia***.
- It is not ideal in emergencies and critically ill patients.
- It is not useful in lung pathology and subarachnoid haemorrhage.

RADIONUCLIDE IMAGING

- It represents function of an organ than morphology.

Rays:

- α-particles are emitted by the natural radionuclides like radium, which are no longer used in medicine.
- β-particles are useful for therapy but not for diagnosis.
- γ-rays pass out of the body and so used for the diagnostic purpose.
- Mapping is done using sophisticated gamma camera

Technetium 99^m

- It is commonest radionuclide used (99- is mass number; m- metastable.)

- It is administered IV.
- Pure γ-rays emitter.
- Short half life.
- Widely used gamma ray detectors are specified to Tc99^{m}.

Uses

Tc99^{m}	labelled serum albumin is used to detect pulmonary emboli
Tc99^{m}	labelled phosphate is used to image bone
Tc99^{m}	labelled sulphur colloid is used to detect the functions of liver, spleen, bone marrow
Tc99^{m}	labelled HIDA (Hippuric immuno diacetic acid) or PIPIDA is used to study the functions of hepatocytes and biliary tract
Tc99^{m}	labelled DMSA (Dimercapto succinic acid) which is taken up by the renal cortical cells, is used in renal function tests
Tc99^{m}	labelled DTPA (Diphenyl triamine penta acetic acid) measures G.F.R
Tc99^{m}	labelled HMPAO (Hydroxy methyl propylamine oxime) is used in Alzheimer's disease and schizophrenia as it crosses the blood brain barrier

Other radionuclides used:

- Thallium 201 chloride for cardiac imaging
- Gallium 67 nitrate to detect tumours and inflammation
- I^{123}

Advantages	*Disadvantages*
Safer	Availability
Easier	Cost factor
No side effects	Not specific
	Fast half life

POSITRON–EMISSION TOMOGRAPHY (PET scan)

It is a non-invasive diagnostic method to assess the biochemical and physiological status of a tissue.

It is used in complimentary with CT scan and MRI. Two protons are used, they are positive electrons (*positrons*).

Most clinically used positron emitting radionuclides is fluoro-deoxyglucose (FDG), others are ^{82}Rb,^{15}O,^{13}N.

Detectors used are Bismuth germanate (BGO) crystals or sodium iodide crystals.

Principle of *electronic collimation* is used to produce images from the radiation emitted from positron emitting tracers.

Uses

- To assess myocardial perfusion (^{82}Rb)and viability (FDG) study.
- Epilepsy—To localize temporal lobe epilepsy (FDG)
- Cancer imaging—Lung cancer (detection and staging).
- Colorectal cancer.
- Melanoma.
- Head and neck cancer and breast cancer.
- Musculoskeletal tumours.
- Thyroid cancer (I^{131}).

Advantage

Very specific

Disadvantage

Very expensive and limited availability.

Note: **Most of the U/S pictures, CT and MRI pictures in this book are from Balmatta Scan Center, Mangalore, I am thankful to consultants Dr Raghavendra Bhat and Dr Ravichandra there.**

Self-assessment Questions

- CT scan.
- MRI.
- Doppler.

It is better to aim at good things and miss it, than to aim at a bad thing and hit it.

32

Operative Surgery

Asepsis and Sterilisation

> ***Bearing in mind that it is from the vitality of the atmospheric particles that all the mischief arises, it appears that all that is requisite is to dress the wound with some material capable of killing these septic germs, provided that any substance can be found reliable for this purpose, yet not too potent as a caustic.***
>
> **—Joseph Lister,** 1867

STERILISATION

- It is freeing an article by removing or killing all bacteria, spores, fungi and viruses.

DISINFECTION

- It is killing of all bacteria, fungi and viruses but not spores.

ANTISEPSIS

- It is inhibition of growth of microorganisms.

ASEPSIS

- Asepsis means-organisms are prevented to access the patient or individual.

DIFFERENT METHODS OF DISINFECTION/ STERILISATION

Physical Agents

- ***Burning*** or ***incineration*** is used to disinfect contaminated articles like dressings.
- ***Hot-air oven:*** Here temperature used is 160 to 180 degree for one hour.
- ***Boiling:*** It kills bacteria but not spores and viruses. Temperature is between 90 to 99 degree. It is used to disinfect syringes, utensils. It is not useful for gloves, rubber materials.
- ***Autoclave***: It is steam under pressure. Temperature attained is between 120-135 degree. It is sterilised for 20 minutes with 15 pounds/sq. inch pressure. It kills all organisms including spores. Completeness of sterilisation is confirmed by using specific gelatin protein which precipitates only in steam under pressure for 20 minutes. Green coloured strip turns to black if autoclave is complete *(signaloc).* Surgical gloves, linen, cotton, dressings, surgical instruments are sterilised by this method. Sharp and plastic instruments cannot be sterilised by this method. Bacillus thermophilus spores are used to assess the completeness of the sterilisation in mass scale. Double autoclaving is done for instruments of orthopaedic or ophthalmic surgeries.
- *The Bowie-Dick* method is also used to check the completeness of sterilisation.



Fig. 32.1: Autoclave machine for sterilisation.

- ***Radiation:*** *Ionising type of radiation:* Atomic gamma radiation is used as commercial method to sterilise suture materials, disposable materials in packets. It is viable, safe and cheaper.
- *Non-ionizing radiation* either infra-red radiation or ultraviolet radiation is used to reduce the bacteria in air, water. Bacteria and virus are vulnerable to ultraviolet rays below 3000Å. Exposure to eyes and skin can cause burn injury.

Chemical Agents

- ***Phenol:*** It is used as standard to compare the efficacy of other agents.
- ***Cresol*** is more powerful and nontoxic. 5% solution is used.
- ***Lysol*** is emulsified cresol with soap. 2% solution is effective.
- ***Chlorhexidine (hibitane)*** is useful antiseptic.
- ***Hexachlorophane***. It is not used in infants and children because it can get absorbed through intact skin in this age group causing severe neurotoxicity.
- ***Dettol (chloroxylenol)*** 5% solution is used.
- ***Cetrimide*** is cationic surfactant (cetavlon) 2% solution is used.
- ***Savlon*** is combination of cetrimide and hibitane. It is very commonly used antiseptic in operation theatres, wards.

Halogens

- Bleaching powder.
- Sodium hypochlorite.
- ***EUSOL: Edinburg University Solution*** contains sodium hypochlorite, boric acid and calcium hydroxide.
  Eusol bath is dipping the ulcer bearing part in dilute eusol solution for 30 minutes 2-3 times a day.
- Iodine
- ***Iodophors:*** These are antiseptics and also sporicidals. They are non-irritant and do not stain skin. ***Povidone-iodine*** is a good example which is commonly used.
- ***Alcohols***: Ethyl or isopropyl alcohols are used.
- ***Formaldehyde:*** It is useful to disinfect the rooms like operation theatre. It is effective at a high temperature and humidity of 80-90%. It is commonly used to fumigate the room. 500 ml of formalin with one litre of water is boiled to get formaldehyde vapour.

All theatre appliances	Autoclave
Sharp instruments (scissors, needles, blades) plastic materials	Glutaraldehyde 2%, Lysol
Endoscopes	Glutaraldehyde
Rubber equipments	Glutaraldehyde
Syringes	Autoclave, hot air oven, gamma radiation
Heart-lung machine	Ethylene oxide
Disposable articles	Gamma radiation
Operation theatre and rooms	Ideally by U-V radiation or by formaldehyde
Sera and biological materials	Filtration
Lab glassware	Hot-air oven
Ward, sick room, furniture	Formaldehyde, iodophor spray, glutaraldehyde
Clothes, bed sheets especially for burns patients	Autoclaving
Soiled dressings, materials, animal carcasses	Incineration, Lysol, iodophors
Excreta	Lysol, iodophors
Cleaning of skin before surgery	Iodophors 2%, savlon, spirit
For cleaning infected wounds	Iodophors, acriflavine, savlon, H_2O_2
To remove slough from the wounds	EUSOL, H_2O_2
Before injection	Spirit is used to clean the skin
Cleaning the ward	Phenol, cresol, Lysol
Hand wash	Chloroxylenol, savlon, spirit, iodophors
Bladder wash	0.1% potassium permanganate solution (Condy‘s -lotion), solution of acetic acid and silver nitrate
Water	Chlorination, potassium permanganate
Fruits, vegetables	Potassium permanganate

Treat the patient as a whole, “Half a sheep is mutton”.



Figs 32.2A and B: Operation theatre mop rack to keep 'used mops' during surgery after use.

Formaldehyde vapour can be created by adding potassium permanganate to the same solution. Room is kept closed for 12 hours.

- ***Glutaraldehyde (cidex 2%)*:** It is used to sterilise sharp instruments. Instrument should be dipped for 10 hours to achieve complete sterilisation. It is potent bactericide, sporicide, fungicide and viricide.

***Hydrogen peroxide (H_2O_2)*:** It is used as topical oxygen therapy. Because of its effervescence and release of nascent oxygen it removes the tissue debris. It is used to clean wounds, cavities, ulcers, as mouth wash and as ear drops to clear ear wax.

Acriflavine and proflavine are orange-red coloured dyes used as antiseptics. It is effective against gram-positive and few gram-negative organisms. It retains its activity in pus and body fluids.

Instruments

CHEATLE'S FORCEPS

It is used to pick sterilised articles like instruments and drapes so that touching of the instruments is avoided while transferring them. It is kept dipped in antiseptic solutions. It does not have lock.



Fig. 32.3: Cheatle's forceps.

SPONGE HOLDING FORCEPS (RAMPLEY'S)

It has got fenestrated, serrated, flat distal end. It is used to clean the operative field, to swab the cavities, to mop the oozing area, to hold gallbladder and cervix during surgeries, for blunt dissections, as ovum forceps.



Fig. 32.4: Sponge holding forceps.

MAYO'S TOWEL CLIP (Fig. 32.5)

It is used to fix drapes in operative field.

It is used to fix suction tubes, diathermy wires, laparoscopic cables in operative table.

It is used to fix ribs in flail chest.

ARTERY FORCEPS (HAEMOSTAT)

Types:

Based on size—

a. Small or mosquito artery forceps.



Fig. 32.5: Mayo's towel clip.



Fig. 32.6: Artery forceps (A) Straight (B) Curved (C) Mosquito.

b. Medium sized artery forceps.

c. Large artery forceps.

Based on shape—

a. Straight artery forceps.

b. Curved artery forceps.

Features of Artery Forceps

Distal blades have transverse serrations which are well apposed.

Lock in the proximal part.

Anger is a short madness which often creates life-long tragedy.

Uses

- To catch bleeding points
- To open the fascial planes in different surgeries
- To pass a ligature
- To hold fascia, peritoneum, aponeurosis
- To hold sutures
- To drain an abscess like a sinus forceps
- To hold gauze as peanut

RIGHT ANGLE FORCEPS

It is used to dissect pedicles and to pass ligatures.

KOCHER'S FORCEPS

It has got serrations in the distal blades and apposing tooth in the tip.

It is used to hold pedicles, tough structures, cut ends of the muscles.

It is used to hold gauze for blunt dissection, to hold resected bowel, to hold ribs during rib resection.



Fig. 32.7: Kocher's forceps.

ALLIS' TISSUE HOLDING FORCEPS

Here distal blades are not apposing each other.

Tip has got teeth in each blade which are apposing.

It has got a lock on the proximal part.

It is used to hold skin flaps, fasciae, aponeurosis, bladder wall.



Fig. 32.8: Allis' tissue holding forceps.

BABCOCK'S FORCEPS

Its distal part of distal blades are curved with a triangular fenestra in it which allow soft tissues to bulge out. Tip is non-traumatic with transverse serrations on it. It has got a lock in the proximal part.



Fig. 32.9: Babcock's forceps.

It is used to hold any part of the bowel, fallopian tubes, appendix, ureter, cord, etc.

LANE'S TISSUE HOLDING FORCEPS

It has got thick, stout distal blades with oval fenestra in each blade. It has got apposing tooth in the tip. It has got a lock in the proximal part.



Fig. 32.10: Lane's tissue holding forceps.

It is used to hold bulky and tough structures, to hold lymph nodes. It is also used as towel clip, as sponge holding forceps.

MORANT-BAKER'S APPENDIX HOLDING FORCEPS

It is like Lane's forceps but with apposing serrations proximal to the tooth. These serrations give a good grip in mesoappendix while holding appendix in appendicectomy. Its use is replaced by Babcock's forceps (Fig. 32.11).

VOLKMANN'S RETRACTOR

It is used to retract fasciae in soles and palms.



Fig. 32.11: Morant-Baker's appendix holding forceps.



Fig. 32.12: Volkmann's retractor.

Retractors

- Superficial retractors
- Deep retractors
- Self-retaining retractors

LANGENBECK'S RETRACTOR

It has got a long handle and a small solid blade. It is used in hernia surgery or any superficial surgeries to retract skin, fascia and aponeurosis, etc.



Fig. 32.13: Langenbeck's retractor.

CZERNY'S RETRACTOR (HERNIA RETRACTOR)

This retractor has got thick, small blade on one side and biflanged hook on the other side in opposite directions. It is used in surgeries like hernia, laparotomy especially during closure.



Fig. 32.14: Czerny's retractor.

MORRIS' RETRACTOR

It may be single blade type or double blade type.

It is used to retract abdominal wall.



Fig. 32.15: Morris retractor.

DEAVER'S RETRACTOR



Fig. 32.16: Deaver's retractor.

- It is a retractor with a broad, gently curved blade.
- It is used to retract liver, spleen and other abdominal viscera.
- It is atraumatic and gives adequate exposure of the surgical field.

DOYEN'S RETRACTOR

It is used in pelvic surgeries.



Fig. 32.17: Doyen's retractor.

SELF-RETAINING RETRACTOR

It has got different adjustable blades so as to retract abdominal wall and tissues during surgery (Balfour's retractor).



Fig. 32.18: Self-retaining retractor.

Surgery is easy to watch, difficult to do.

SINGLE HOOK RETRACTOR

It is used to retract skin.



Fig. 32.19: Single hook retractor.

PLAIN NON-TOOTHED DISSECTING FORCEPS

It is used to hold delicate structures like peritoneum, vessels, bowel, nerves, tendons (Fig. 32.20).

TOOTHED-DISSECTING FORCEPS

It is used to hold skin and tough structures.



Fig. 32.20: Dissecting forceps (A) Non-toothed (B) and (C) Toothed.

SURGICAL NEEDLES

Types

Based on the edge

a. Round body needle
b. Cutting needle
c. Reverse cutting needle
d. Taper cut needle
e. Side-to-side flat—Hagedron needle

Based on curvature

a. Straight needle
b. Curved needle. Half circle; 5/8 circle, etc

Based on existence of the eye

Atraumatic needle is eyeless. Here suture material is attached to the needle by swaging. Size of the suture material and that of needle is same and so tissue trauma is less. Needle once used is disposed of (not reusable).

Traumatic needle: It is eyed needle. Needle in the eye area is wider than the body of the needle and so tissue trauma is more. These needles are re-usable.


Traumatic cutting type needle
Reverse cutting needle with eye
Round-bodied needle
Atraumatic needle
Straight needle

Fig. 32.21: Needles.

Round body needles are used in soft structures like peritoneum, muscle, vessel, nerves, tendons, bowel, soft tissues.

Cutting needles are used to suture skin, aponeurosis and tough structures.

Reverse cutting needle is used to suture muco-periosteum.

NEEDLE HOLDER

Smaller distal blades with criss-cross serrations often with a groove in the middle are the features of a needle holder.



Fig. 32.22: Needle holder.

It may be straight or curved. It may be available with different sizes. While holding a needle in a needle holder one should get a good control and good grip. This is achieved by placing the needle at the junction of proximal 2/3 and distal 1/3. Needle holder should be held between thumb and ring finger.

JOLL'S THYROID RETRACTOR

It is a self-retaining retractor specifically used for thyroid surgeries.



Fig. 32.23: Joll's thyroid retractor.

MOYNIHAN'S OCCLUSION CLAMP

- It has got long distal blades with longitudinal serrations.
- It may be straight or curved.
- It is non-traumatic, non-crushing type.
- It occludes lumen of the bowel/stomach and so prevents spillage of the content of the bowel.
- It also occludes the vessels in the wall of the bowel and so prevents bleeding during surgery.
- It is used during anastomosis of the stomach and other parts of the bowel.



Fig. 32.24: Moynihan's occlusion clamp.

PAYR'S CRUSHING CLAMP (GASTRIC)

It is stout and heavy instrument with double lever in the handle.



Fig. 32.25: Payr's crushing clamp.

It crushes the bowel once applied. So before applying it, line of resection of stomach/bowel should be assessed properly. It is applied to the part which is removed. Viability of the bowel is lost once it is applied.

It is used in gastrectomy and resection and anastomosis of the bowel.

DESJARDIN'S CHOLEDOCHOLITHOTOMY FORCEPS

It has got long distal blades with smooth serrations and fenestra in the tip. It does not have lock and so accidental damage of CBD mucosa or crushing of the CBD stone are avoided.



Fig. 32.26: Desjardin's choledocholithotomy forceps.

It is used for choledocholithotomy (removal of CBD stones).

BAKE'S DILATOR

It is long malleable metallic instrument with club at the terminal end.

It is used to assess the CBD, duodenal papilla for patency or block.



Fig. 32.27: Bake's dilator.

SINUS FORCEPS (Lister's)

- It has got straight, long blades with serrations in the tip. It does not have a lock.
- It is used to drain pus from abscess cavity (Hilton's method). It is called as sinus forceps because it was initially originated to pack the sinus cavities. It is less traumatic.
- Sinus forceps has no lock; no serrations; broad tip; blunt.

> *Surgery is always second best; if you can do something else, its' better.*—John Kirklin



Fig. 32.28: Lister's sinus forceps.

SCISSORS



Fig. 32.29: Scissors.

VOLKMANN'S SCOOP

To scoop cavities, ulcer bed, granulation tissues.

On either side different sized scoops are present.



Fig. 32.30: Volkmann's scoop.

TRACHEOSTOMY TUBE

- ***Fuller's bivalved tracheostomy tube***: It has got outer tube and inner tube. Outer tube is biflanged and so insertion is easier. Inner tube is longer with an opening on its posterior aspect. Inner tube can be removed and re-inserted easily whenever required.
- ***Jackson's tracheostomy tube***: It has got outer tube, inner tube and an obturator.
- Red-rubber tracheostomy tube.
- PVC tracheostomy tube.

Modern tracheostomy tubes are made of plastic. They are soft, least irritant and disposable. They have inflatable cuff which makes it easier to give assisted ventilation. Cuff should be deflated at regular intervals to prevent tracheal pressure necrosis (For assisted ventilation, endotracheal, tube can be kept for 7 days. Beyond that period, patient needs tracheostomy for further ventilation).



Fig. 32.31: Tracheostomy tube (A Fuller's (B) Jackson's tracheostomy tube.

Indications for tracheostomy

- In head, neck and facial injuries
- Tetanus
- Tracheomalacia after thyroidectomy
- Laryngeal oedema/spasm
- Major head and neck surgeries like commando's operation, block dissection, etc.

DRAINS

A drain is a created channel which allows any fluid collected, to come out after closure of the main wound.

Types

- *Corrugated rubber drain:* It drains by capillary action and gravity. It is cheaper and technically easier. But it allows soakage of dressings and causes discomfort to the patient.
- *Tube drains:*
  - Malecot catheter can be used as a tube drain.
  - Penrose soft latex rubber tube.
  - Multiple perforated tubes.



Fig. 32.32: Drains (A) Corrugated rubber drains, (B) Multiple perforated drains, (C) Tube drain.

Advantages of tube drains

- Quantity of fluid like bile, pus can be measured
- It can be kept for longer time
- Skin excoriation will not occur
- Patient remains more comfortable
- Infection rate is less
- Removal is easier
- Dye can be injected and cavity or communication can be assessed using 'C-ARM'

- *Closed suction tube drain system.*
- *Glove drain.*
- *Wick drain* is a gauze drain to drain pus, discharge, etc.
- *Sump drain:* This is a type of drain where parallel air vent prevents the adjacent soft tissues from being sucked into the drain when negative pressure is applied.

Advantages of sump drain

- No drain blockade
- Resists collapse of the structure when suction is applied.

Uses of sump drain

- Collection of irritant discharges (enterocutaneous fistula)
- Collection of secretions having activated enzymes (high small bowel, pancreatic fistula)
- Draining proximal stump in TEF with esophageal atresia to prevent aspiration



Fig. 32.33: Suction drain used in thyroid surgery.



Fig. 32.34: Romovac suction drain. Here suction is created by pressing the suction corrugation. There is a sharp metallic introducer to pass the tube into the required area after puncturing the skin. It is used for thyroidectomy, mastectomy, radical dissection, wide excisions, flap surgeries, etc.

Classification of Drain Systems

- ***Open (static) drain:*** For example, corrugated drain, penrose drain. Infection rate is higher.
- ***Closed siphon drain:*** Here drain is connected to a sterile bag with or without one-way valve. It reduces the infection.
- ***Closed suction drain:*** Here negative pressure of –100 to –500 mmHg is used to create vacuum to drain the secretions.
- ***Sump suction drain:*** Here negative suction with a parallel air-vent is used to prevent the adjacent soft tissues being sucked into the lumen of the drain.
- ***Under water seal drain*** to drain pleural space.

Indications for drains

- In drainage of an abscess
- In bleeding surgical conditions like trauma, peroperative bleed

> *The postoperative treatment is as essential as the operation and the surgeon is as much responsible for the postoperative treatment as for the operation.* — Roscoe C Giles

- In haemo, pyo or pneumothorax
- In acute abdominal conditions like peritonitis, haemoperitoneum
- In major abdominal surgeries like of pancreas, biliary tree, stomach, etc.
- In thyroid surgery
- In hydrocele surgery

Problems in Drains

- Infection can occur through the drain.
- Displacement.
- It may not drain adequately and can give a false information.
- It may interfere with healing process inside.

Presently keeping a drain itself is a questioned debate and controversy all over.

Older dictum was 'when in doubt keep a drain and the surgeon can sleep happily'—is questioned at present.

DRAINS IF NOT USED PROPERLY MAY BE COUNTERPRODUCTIVE.

FOLEY'S CATHETER: Refer Urology



Fig. 32.35: Foley's catheter (Refer Urology).

MALECOT'S CATHETER: Refer Urology



Fig. 32.36: Malecot's catheter (Refer Urology).

SIMPLE RED RUBBER CATHETER: Refer Urology



Fig. 32.37: Red Rubber catheter (Refer Urology).

LISTER'S URETHRAL DILATOR

It has got olive tip and it is used to dilate stricture urethra. Other dilators are Clutton's dilator and filiform bougies.



Fig. 32.38: Lister's urethral dilator.

RYLE'S TUBE

It is one meter long and is made of red rubber or plastic.

It has got *three lead shots* in the tip which makes it radiopaque. It also facilitates easy passage of the tube through the oesophagus.

It has got markings at different levels:

- At 40 cm distance, at the level of gastro-oesophageal junction.
- At 50 cm distance, at the level of body of the stomach.



Fig. 32.39: Ryle's tube.

- At 60 cm distance, at the level of the pylorus.
- At 65 cm distance, at the level of the duodenum.

Indications

Diagnostic:

- For gastric function tests—To assess free acid and total acid
- Hollander's test for completion of vagotomy
- To diagnose tracheo-oesophageal fistula
- Baid test for pseudocyst of the pancreas

Therapeutic:

- In acute abdominal conditions like peritonitis/obstruction
- In abdominal trauma
- After abdominal surgeries
- In pyloric stenosis
- In upper GIT bleeding
- In paralytic ileus
- For feeding purpose in conditions like comatose patients, faciomaxillary injuries, major head and neck surgeries

INFANT FEEDING TUBE (Fig. 32.40)

- There are *no lead shots* and markings on the tube.
- It is used for feeding purpose in infants who is under coma, with facio-maxillary injuries and anorexia.

KEHR'S 'T' TUBE (Fig. 32.41)

- It is used after opening CBD (choledochotomy). CBD is closed with 'T" tube placed in the CBD.
- It is made up of latex or red rubber.



Fig. 32.40: Infant feeding tube.



Fig. 32.41: Kehr's 'T' tube.

- 'T' tube has got horizontal part which is placed in the CBD and vertical part which is allowed to come out, to drain bile. Amount of bile draining daily is measured.

Before removal of the "T" tube, patency of CBD should be confirmed.

It is done by following methods:

- The vertical limb is clamped (done in 12-14 days) and the patient is observed for development of pain, fever and jaundice in 24 hours. If normal, then one can presume that there is no obstruction in the CBD.
- Water soluble iodine dye is injected through the tube to visualize biliary tree and free flow of dye into the duodenum. (postoperative 'T' tube cholangiogram). It is done in 14 days which is the time required to develop fibrous track. Once there is free flow, tube is removed and track gets closed on its own.

PROCTOSCOPE (Refer Rectum and Anal Canal)



Fig. 32.42: Proctoscope.

Surgery is an art of learning not only when to cut but also when not to cut.

FLATUS TUBE



Fig. 32.43: Flatus tube

It is made up of India rubber, 45 cm in length. There is one opening in the tip and another on the side proximal to the tip. (Urinary catheter like red rubber catheter has no opening in the tip, only side opening is present). It is used in sigmoid volvulus to decompress and derotate; in paralytic ileus; in subacute intestinal obstruction. It is passed per anal into the recto-sigmoid area. Proximal end is connected to water container to observe the quantity of air bubble which signifies the amount of gas getting deflated.

Suture Materials

Features of ideal suture material

- Adequate tensile strength
- Good knot holding property
- Should be least reactive
- Easy handling property
- Should have *less memory*
- Should be easily available and cost effective

CLASSIFICATION I

ABSORBABLE SUTURE MATERIALS

- **Plain catgut** is derived from submucosa of jejunum of sheep.
  - It is yellowish white in colour.
  - It is absorbed by inflammatory reaction and phagocytosis—absorption time is 7 days.
  - It is used for subcutaneous tissue, muscle, circumcision in children.
- **Chromic catgut** is catgut with chromic acid salt.
  - It is brown in colour.
  - Its absorption time is 21 days.
  - It is used for suturing muscle, fascia, external oblique aponeurosis, ligating pedicles, etc.
- **Vicryl** (Polyglactic acid):
  - It is synthetic absorbable suture material.
  - It gets absorbed in 90 days.
  - Absorption is by hydrolysis.
  - It is violet in colour (braided).
  - It is multifilament and braided.
  - It is very good suture material for bowel anastomosis, suturing muscles, closure of peritoneum.
- **Dexon** (Polyglycolic acid) is synthetic absorbable suture material like vicryl. It is creamy yellow in colour (braided).
- **Maxon** (Polyglyconate) monofilament.
- **PDS** (**P**oly **D**ioxanone **S**uture material) is absorbable suture material. It is creamy in colour with properties like vicryl. It is costly but better suture material than vicryl.
- **Monocryl** (Polyglecaprone) monofilament.
- **Biosyn** (Glycomer) monofilament.

Uses of absorbable suture materials:

- In bowel anastomosis like gastrojejunostomy, resection and anastomosis. Vicryl is used
- In cholecystojejunostomy (CCJ), choledocho-jejunostomy (CDJ), pancreaticojejunostomy. Vicryl is used.
- In suturing muscle, fascia, peritoneum, subcutaneous tissue, mucosa
- In ligating pedicles. 1–zero chromic catgut or vicryl are used, e.g. ligation of pedicles during hysterectomy
- In circumcision, usually 3-zero plain or chromic catgut are used

Absorbable suture materials should not be used for suturing tendon, nerves, vessels (vascular anastomosis).

NONABSORBABLE SUTURE MATERIALS

- ***Silk*** is natural, multifilament, braided, non-absorbable suture material derived from cocoon of silkworm larva. It is black in colour. It is coated suture material to reduce capillary action.
- ***Polypropylene*** (Prolene) is synthetic, monofilament suture material. It is blue in colour. It has got high memory. (*Memory of suture material* is recoiling tendency after removal from the packet. Ideally suture material should have low memory.) (Prolene mesh used for hernioplasty is white in colour).
- ***Polyethylene*** (Ethylene) is synthetic monofilament nonabsorbable suture material. It is black in colour.
- ***Cotton*** is twisted multifilament natural nonabsorbable suture material. It is white in colour.
- ***Linen*** is derived from bark of cotton tree.
- ***Steel, Polyester, Polyamide, Nylon*** are other nonabsorbable suture materials.

Uses of nonabsorbable suture materials:

- In herniorrhaphy for repair
- For closure of abdomen after laparotomy
- For vascular anastomosis (6-zero), nerve suturing, tendon suturing
- For tension suturing in the abdomen
- For suturing the skin

CLASSIFICATION II

Natural

- Catgut.
- Silk.
- Cotton.
- Linen.

Sadness is a form of fatigue.

Synthetic

- Vicryl, dexon, PDS, maxon.
- Polypropylene, polyethylene, polyester, polyamide.

CLASSIFICATION III

- **Braided:** Polyester, polyamide, vicryl, dexon, silk.
- **Twisted:** Cotton, linen.

CLASSIFICATION IV

- **Monofilament**: Polypropylene, polyethylene, PDS, catgut, steel.
- **Multifilament**: Polyester, polyamide, vicryl, dexon, silk, cotton.

CLASSIFICATION V

- Coated.
- Uncoated.

Numbering of Suture Material

2-Thick. For pedicle ligation.
1-
0-zero.
1-zero.
2-zero. For bowel suturing.
3-zero.
4-zero.
5-zero. For vascular anastomosis.
6-zero.
7-zero.
8-zero.
9-zero. For ophthalmic surgery. Requires operating microscope.

Fig. 32.44: Photo showing different types of suture materials (with pack).

Types of suturing

- Continuous suturing
- Interrupted simple suturing
- Interrupted mattress suturing
- Subcuticular suturing
- Horizontal tension suturing
- Vertical tension suturing



Fig. 32.45: Types of suturing.

Types of knots

- Reef knot
- Granny knot
- Surgeon's knot



Fig. 32.46: Types of knots.

Diathermy (Electrocautery)

It is the method to control bleeding or to cut the tissues during surgery.

Types

Based on type of current used:

- Unipolar cautery.
- Bipolar cautery. It is safer because its effect is seen only in between electrode points. Adjacent tissues will never get damaged.

Based on type of action:

- ***Coagulation cautery*** which causes haemostasis by tissue coagulation. Here temperature is 100 degree (blue switch).
- ***Cutting cautery***: Here temperature is 1,000 degree which disintegrate the tissues. It is not haemostatic (yellow switch).
- ***Blended current*** is combination of both coagulation and cutting.

Differences between unipolar and bipolar cautery

Unipolar cautery	*Bipolar cautery*
1. Can be used for both coagulation and cutting	1. Only for coagulation
2. Conducting plate should be kept	2. No need
3. Cannot be used in patient with artificial valves	3. Can be used
4. Cannot directly touch structures to be coagulated	4. Directly touch structures to be coagulated.
5. Should be careful about adjacent tissues	5. Adjacent tissues will never get damaged

Uses

- For coagulation of bleeders during surgery to achieve haemostasis.
- To cut muscles, fascia, etc.
- It is essential for laparoscopic surgical procedures. Bipolar is commonly used.
- It is used to remove small cutaneous lesions, to control bleeding duodenal ulcer.

Disadvantages

- Infection.
- Cauterisation of normal tissues.
- Problem of explosion.
- Diathermy burn to the patient at the site where diathermy plate is kept.
- Burn injury or electrical shock to surgeon and assisting personnel.

Precautions

- Proper earthing.
- Avoid loose contact of electrodes.
- It should be kept off when not in use during procedure.



Fig. 32.47: Diathermy machine with plate, foot switch for use.

Self-assessment Questions

- Sterilisation.
- EUSOL.
- Vicryl.
- Catgut.
- Absorbable suture material.
- Diathermy.
- Drains in surgery.

Surgery is—once act is done cannot be reversed.

Operative Procedures

Abdominal Incisions
Vasectomy
Circumcision
Hydrocele
Inguinal hernia
Appendicectomy
Thyroidectomy
Tracheostomy
Cryosurgery
LASER in surgery
Staplers in surgery

ABDOMINAL INCISIONS

Principles

- Incision should be long enough for a good exposure.
- Splitting the muscle is better than cutting, except rectus muscle.
- Avoid cutting nerves and vessels in the abdominal wall.
- Retract muscle, abdominal organs towards the neurovascular supply.
- Insert a drainage tube through a separate incision.
- Transverse incisions are better than vertical incisions.
- Close the wound layer by layer.

Requirements

- Accessibility
- Extensibility
- Security

Factors affecting the strength of the scar

- Type of surgery (acute abdomen, surgery for malignancy, major surgery)
- Obesity
- Pregnancy
- Straining
- Cough
- Ascites
- Nutrition
- Diabetes
- Immunosuppression
- Type of incision

Complications of Abdominal Incision

- Wound infection.
- Burst abdomen.
- Fistula formation.
- Wound pain.
- Incisional hernia.
- Adhesion and its complication.


1
2
3
4
5
6
7
1. Rt subcostal incision
2. Lt subcostal incision
3. Upper midline
4. Rt upper paramedian
5. Subumbilical
6. Lt lower paramedian
7. Lower midline
8
9
10
11
12
13
14
15
16
8. Lt thoraco-abdominal
9. Roof-top-(Chevron) incision
10. Upper horizontal
11. Lt lumbar sympathectomy incision
12. Lower horizontal
13. Lanz incision
14. McBurney's incision
15. Pfannensteil incision
16. Incision for inguinal hernia

Fig. 32.48: Different incisions in the abdomen.

Different abdominal incisions are:

- Upper midline.
- Upper right paramedian.
- Upper left paramedian.
- Kocher's incision (right subcostal).
- Left subcostal.
- Bucket handle.
- Upper horizontal.
- Thoraco-abdominal.
- Sub-umbilical.
- Incision for lumbar sympathectomy.
- Lower midline.
- Lower right or left paramedian.
- Incisions for appendicectomy—McBurney's, Rutherfold Morrison's, Lanz, laparoscopic.
- Pfannensteil incision.
- Lower horizontal.
  – Upper incisions are always better.
  – Horizontal incisions are better.
  – Paramedian is better than midline.

VASECTOMY

Indications

- Family planning (parents should have two healthy children, consent should be obtained).
- After prostatectomy, vasectomy is done to prevent retrograde infection of testes.

Procedure

After cleaning and draping, 2 ml of 1% Inj Xylocaine (local anaesthetic) is injected to the root of the scrotum on the antero-lateral aspect.

Skin, external and internal spermatic fasciae are incised, cord is held with Allis forceps. Thick, firm, vas is dissected, two artery forceps are applied. A small piece of vas is excised and cut ends are ligated with silk or thread (nonabsorbable). Skin is sutured. Procedure is repeated on the other side.

Advice

To avoid sexual contact or to use contraception for 3 months.

Complications

- Haematoma
- Haematocele
- Infection
- Pyocele
- Sperm granuloma
- Recanalisation occurs rarely but dangerous

- When there is hernia or hydrocele, vasectomy is done along with specific procedures for hernia or hydrocele.
- ***No scalpel vasectomy,*** using specialised instruments is becoming popular. Procedure does not require any suturing.



Figs 32.49A and B: No scalpel vasectomy instruments and technique.

CIRCUMCISION

Indications

- Religious.
- Phimosis.
- Paraphimosis after doing initial dorsal slit.
- Balanitis and balanoposthitis (common in diabetics).
- Early carcinoma of prepuce or glans penis—both diagnostic as well as therapeutic purpose.
- Certain sexually transmitted diseases, e.g. Herpes infection.

Procedure

In children, it is done under G/A. In adults, it is done under local anaesthesia.

After cleaning and draping, LA (1% lignocaine *(plain)* is injected circumferentially near the root of the penis) is given (ring block). Dorsal skin is cut up to the corona and later circumferentially and ventrally. The skin is cut with inner layer. Care is taken to see that optimum (less) skin is cut ventrally to prevent the occurrence of *chordee*. Frenular artery as well as dorsal vein is transfixed and

Surgery is an irreversible repair but often it can be irreversible damage also !!!

ligated ventrally using chromic catgut (2-0 or 3-0). Small bleeders are also ligated. Skin is apposed to the cut edge of corona using interrupted chromic catgut sutures.

Postoperatively, antibiotics and analgesics are given.

Complications

- Reactionary haemorrhage due to slipping of ligature from frenular artery and dorsal vein.
- Infection.
- Stricture urethra near the external meatus in *children*.
- Chordee due to removal of excess skin on the ventral aspect.
- Rarely priapism can occur.

HYDROCELE

Types of Surgery

- Subtotal excision.
- Partial excision and eversion (Jabouley's operation).
- Evacuation and eversion.
- Lord's plication.
- Sharma and Jhawers technique.

Procedure

- Under G/A or spinal or L/A, after cleaning and draping, vertical incision of about 6-8 cm in length is made over the scrotum, anteriorly 1 cm lateral to the median raphe.
- Skin, dartos, external spermatic fascia, internal spermatic fascia are incised.

  Bluish hydrocele sac is identified, i.e. parietal layer of the tunica vaginalis of testis.

  Fluid is evacuated using trocar and cannula. Sac is opened.
- *If the sac is small, thin and contains clear fluid,* either *Lord's plication,* i.e. tunica is bunched into a "ruff" by placing series of multiple interrupted chromic catgut sutures so as to make the sac form a fibrous tissue which is relatively avasular and so haematoma will not occur, or *Evacuation and eversion* of the sac behind the testis (after eversion, everted sac is sutured with chromic catgut by continuous sutures) is done.
- *If the sac is thick, in large hydrocele and chylocele, subtotal excision of the sac* is done (as tunica vaginalis is reflected on to the cord structures and epididymis posteriorly, total excision of the sac leads to orchidectomy with division of cord).
- Often the sac is excised partially and eversion is done, which is called as *Jabouley's* operation.
- After evacuation, the sac with the testis is placed in a newly created pocket between the fascial layers of the scrotum *(Sharma and Jhawer's technique).*
- *Aspiration must be avoided as much as possible* as it is only a temporary measure (recurrence occurs very early) and chances of haematocele, infection are higher.
- A drain is placed near the root of the scrotum on the lateral aspect because, it becomes the most dependent portion once scrotal support is given. Scrotal support is given to reduce the scrotal oedema.
- Wound is closed in layers.
- Drain is removed in 48 hours.



Fig. 32.50: Trocar and cannula used for tapping hydrocele. It prevents spillage of fluid.

Surgeries for hydrocele

- Subtotal excision of the sac
- Jabouley's operation
- Evacuation and eversion
- Lord's plication
- Sharma and Jhawer's technique

Complications of surgery

- Reactionary haemorrhage
- Infection
- Pyocele
- Sinus formation
- Recurrent hydrocele

Conditions where orchidectomy is done in hydrocele

1. Pyocele with testicular destruction
2. Clotted haematocele with testicular destruction

INGUINAL HERNIA

Surgery is the treatment of choice for inguinal hernia.

In infants, whether it is hernia or hydrocele, only *herniotomy* is done through inguinal approach *(Michaelis plank operation*).

In adults: It includes *herniotomy*, i.e. excision of hernial sac and *herniorrhaphy* (strengthening of the posterior wall of inguinal canal either by repair or mesh).

1. Herniotomy

Anaesthesia: Spinal or G/A

Procedure: After cleaning and draping, skin is incised 1.25 cm above and parallel to the medial two-third of inguinal ligament. Two layers of superficial fascia (outer Camper's fascia and inner Scarpa's fascia) are incised. External oblique aponeurosis is incised. Upper leaf is reflected above and lower leaf is reflected downwards to visualize and expose the inguinal ligament. Ilioinguinal nerve is safeguarded. Cremasteric muscle is opened. Cord structures are dissected. Sac which is anterior and lateral to cord is identified and is pearly white in colour. Dissection is usually started from the fundus and extended towards the neck which is identified by extra peritoneal fat. The neck is narrow and is lateral to inferior epigastric artery. Sac is opened at the fundus. Finger is passed to release any adhesions. Sac is twisted so as to prevent the contents from coming back. It is transfixed using absorbable suture material (chromic catgut 2-0) and is excised distally.

2. Modified Bassini's Herniorrhaphy

Conjoined tendon and inguinal ligament are approximated using interrupted nonabsorbable monofilament sutures [polypropylene (prolene, blue in colour)]; medial most stitch is taken from the periosteum of pubic tubercle *(called as key or Bassini's stitch)*; external oblique is closed and other layers are closed.

Complications of herniorrhaphy

- Haemorrhage
- Haematoma
- Infection
- Haematocele
- Postherniorrhaphy hydrocele
- Hyperaesthesia over the medial side of inguinal canal due to injury to ilioinguinal nerve
- Recurrence
- Osteitis pubis

Hernioplasty

Prolene mesh is used for hernioplasty (white in colour). Other materials which can be used are Dacron, tensor fascia lata, skin.

Relation of sac to the cord:
Indirect inguinal hernia—Anterolateral
Direct inguinal hernia—Posteromedial

APPENDICECTOMY

Approaches –

- ***Grid-iron incision*** (*McBurney's incision*): Incision is placed perpendicular to the right spino-umbilical line at the McBurney's point, i.e. at the junction of lateral one-third and medial two-third of spino-umbilical line.
- ***Rutherford Morison muscle*** cutting incision *(Cut upwards and laterally)*.
- ***Lanz crease incision*** centering at McBurney's point-cosmetically better.
- ***Right lower paramedian*** incision—when in doubt or when there is diffuse peritonitis.
- ***Laparoscopic approach:*** Becoming popular.
- ***Fowler-Weir approach:*** Medial muscle cutting incision.

Procedure

Under general anaesthesia, skin is incised. Two layers of superficial fascia are cut. External oblique aponeurosis is opened in the line of incision. Internal oblique and transverse muscles are split in the line of fibres. Peritoneum is opened in the line of incision. Caecum is identified by taeniae, and ileo-caecal junction. Omentum when adherent is separated. Appendix is held with Babcock's forceps. Mesoappendix with appendicular artery is ligated. Using thread or silk, a purse-string suture is placed around the base of the appendix. Base of the appendix is crushed with artery forceps and transfixed using vicryl (absorbable). Appendix is cut distal to the suture ligature and removed. Stump is cleaned with antiseptics. Purse-string suture is tightened so as to bury the stump.

In difficult cases *Retrograde appendicectomy* can be done. In presence of pus or burst appendix, the peritoneal cavity is drained.

Postoperatively, IV fluids, antibiotics are given. Once bowel sounds are heard, oral diet is started.

Complications after Appendicectomy

- Paralytic ileus.
- Reactionary haemorrhage due to slipping of ligature of the appendicular artery.
- Residual abscess (pelvic, paracolic, local, subdiaphragmatic).
- Pylephlebitis (Portal pyaemia).
- Adhesions, kinking and intestinal obstruction.

A surgeon should have a heart of lion, eyes of a hawk and hands of a woman.—John Halle

- Right inguinal hernia *(direct)* due to injury to ilio inguinal nerve.
- Wound sepsis.
- Faecal fistula.

THYROIDECTOMY

Types

- ***Hemithyroidectomy*:** Along with removal of one lobe, entire isthmus is removed. It is done in benign diseases of only one lobe.
- ***Subtotal thyroidectomy:*** Commonly done in toxic thyroid either primary or secondary and also often for nontoxic multinodular goitre. Here about 8 grams or a tissue, size of pulp of the finger is retained at the lower pole, on both sides and rest of the thyroid gland is removed.
- ***Partial thyroidectomy*** is removal of the gland in front of trachea after mobilization. It is commonly done in nontoxic multinodular goitre.
- ***Near total thyroidectomy*:** Here both lobes, except the lower pole which is very close to recurrent laryngeal nerve and parathyroid is removed. It is done in case of papillary carcinoma of thyroid.
- ***Total thyroidectomy*:** Entire gland is removed. It is done in case of follicular carcinoma of thyroid, medullary carcinoma of thyroid.

Procedure

Position: Under general anaesthesia patient is put in supine position, with neck hyperextended by placing a sand bag under shoulder—with table tilt of 15 degree head up to reduce venous congestion.

Incision: Horizontal crease incision is done, two finger breadth above the sternal notch, extending from sterno-mastoid of one side to the other.

Skin and platysma are incised – upper flap raised up to thyroid cartilage, lower flap up to sternoclavicular joint. Deep fascia is opened vertically in the midline. Strap muscles are retracted or cut in between two Kocher's forceps. Pretracheal fascia is opened to mobilize the thyroid. First, short stout middle thyroid vein is ligated, then superior thyroid pedicle is ligated close to the gland so as to avoid injury to external laryngeal nerve. Inferior thyroid artery is ligated away from the gland so as to avoid injury to recurrent laryngeal nerve. Mobilized gland is removed. Bed is sutured with catgut so as to prevent bleeding. Drain is placed. The wound is close in layers.

Thyroid steal: Patient with thyrotoxicosis is taken to operation theatre daily for few days before doing surgery so as to reduce the anxiety of the patient.

Complications of Thyroidectomy

1. ***Haemorrhage*:** May be due to slipping of ligatures, either of superior thyroid artery or other pedicles. It causes tachycardia, hypotension, breathlessness and compression over the trachea which inturn may cause severe stridor, respiratory obstruction. As a first aid, immediate release of sutures including that of deep fascia has to be done and pressure over the trachea is released. Then patient is shifted to operation theatre and under general anaesthesia exploration is done and bleeders are ligated. Blood transfusion may be required.
2. ***Respiratory obstruction.*** It may be due to haematoma (if it is so, the haematoma has to be evacuated), or due to laryngeal oedema. For laryngeal oedema, *immediate emergency endotracheal intubation* is done along with steroid injections. Often emergency tracheostomy may be required as a life-saving procedure.
3. ***Recurrent laryngeal nerve palsy*:** It can be transient or permanent. Transient is 3% common. They usually recover in 3 weeks to 3 months. Often they require steroid supplement and speech therapy. Permanent paralysis is rare.
4. ***Hypoparathyroidism*** is rare (0.5%)/ Mostly it is temporary due to vascular spasm of parathyroid glands, occurs in 2nd-5th postoperative day. Presents with weakness, +ve Chvostek's sign, carpopedal spasm, convulsions. Serum calcium estimation is done and then 10 ml of 10% calcium gluconate—is given IV 8th hourly. Later supplemented by oral calcium 500 mg 8th hourly. After 3-6 weeks, patient is admitted, drug is stopped and serum calcium level is repeated.
5. ***Thyrotoxic crisis*** **(Thyroid storm):** Occurs in a thyrotoxic patient inadequately prepared for thyroidectomy and rarely a thyrotoxic patient presents in a crisis following an unrelated operation or stress. They present in 12-24 hours with severe dehydration, circulatory collapse, hypotension, hyperpyrexia and often cardiac failure.
   Treatment is injection hydrocortisone, oral antithyroid drugs, tepid sponging of whole body, beta blocker injection, oral iodides, large amount of IV fluids for rehydration, digitoxin. Cardiac monitor, often ventilator support with close observation is necessary. It has got high rate of mortality with critical period of 72 hours. Correction of fluid and electrolyte imbalance and cardiac monitoring are the important aspects of management.
6. ***Injury to external laryngeal nerve*** causes weakness of cricothyroid muscle leading to alteration in pitch of voice.

7. ***Hypothyroidism:*** Revealed clinically after 6 months.
8. Wound infection, stitch granuloma formation.
9. Keloid formation.

TRACHEOSTOMY

Types

- Emergency tracheostomy.
- Elective tracheostomy.

Tracheostomy Tube

- ***Fuller's bivalved tracheostomy tube***: It has got outer tube and inner tube. Outer tube is biflanged and so insertion is easier. Inner tube is longer with an opening on its posterior aspect. Inner tube can be removed and re-inserted easily whenever required.
- ***Jackson's tracheostomy tube***: It has got outer tube, inner tube and an obturator.
- Red-rubber tracheostomy tube.
- PVC tracheostomy tube.

Modern tracheostomy tubes are made of plastic. They are soft, least irritant and disposable. They have inflatable cuff which makes it easier to give assisted ventilation. Cuff should be deflated at regular intervals to prevent tracheal pressure necrosis. (For assisted ventilation endotracheal tube can be kept for 7 days. Beyond that period patient needs tracheostomy for further ventilation.)

Indications for tracheostomy

- In head, neck and facial injuries
- Tetanus
- Tracheomalacia after thyroidectomy
- Laryngeal oedema/spasm/surgeries
- Major head and neck surgeries like commando's operation, block dissection, etc.
- ICU ventilation after 7 days



Fig. 32.51: Tracheostomy tube with inflation part and syringe (Inflated with air).



Fig. 32.52: Figure showing the position of tracheostomy tube.



Fig. 32.53: Vertical midline or transverse incisions are used for tracheostomy. ***Vertical midline*** extends from cricoid cartilage to sternal notch. It is used both in emergency and elective tracheostomy and commonly used incision. It gives rapid access with less dissection but leads into poor scar. ***Transverse incision*** can be used in elective tracheostomy. It is placed two finger breadths above the sternal notch with a length of about 5 cm transversely. It has got a better cosmetic scar.

Technique of Tracheostomy

Neck of the patient is hyperextended by placing sand bags under the shoulder. Vertical (midline) or horizontal incision is made. Deep fascia is opened. Strap muscles are retracted laterally. Isthmus is divided or retracted

Surgery is not just cutting, but it is an art; it is not only an art but also a merciful art.



Fig. 32.54: Advanced secondaries in neck with tracheostomy tube to control respiratory stridor.

below. 2nd and 3rd tracheal rings are opened and circular opening is made. Tracheostomy tube is placed. It is tied around the neck.

Note: Endotracheal tube can be kept *in situ* only for 7 days.

Tracheostomy Care

- Regular suctioning of the tube.
- Cleaning of tracheostomy tube.
- Humidification of the inspired air.

Complications of tracheostomy

- Tracheal stenosis
- Bleeding
- Aspiration
- Pneumothorax
- Surgical emphysema in the neck
- Mediastinal emphysema
- Tracheostomy dependency

CRYOSURGERY

- It is the destruction of tissues by ***controlled cooling.***
- System contains an automatic defrosting device with a cryoprobe.

Gases used are

- Nitrous oxide—minus 98°C temperature.
- CO_2—minus 60°C.
- Liquid N_2—minus 180°C.
- Freon—minus 190°C.

Commonly nitrous oxide is used as it is easily available, cheaper and achieves optimum temperature required for different procedures.

Mode of Action

- It produces intracellular crystallization, dehydration and denaturation of proteins and cell death.
- It causes the obliteration of microcirculation and so cell death.

Indications

- To remove warts and lesions in the skin.
- Cryotherapy for piles.
- For chronic cervicitis.

Advantages

- Relatively bloodless and painless.
- Adequate control of extent and depth in freezing.
- Equally effective.

Disadvantages

- Infection.
- Discharge from the site.

LASERS IN SURGERY (Light Amplification Stimulated Emission of Radiation)

Molecules are placed in a compact area and power is passed through this so as to activate the molecules. Molecules get activated at different periods and move in different directions, which they hit to each other releasing energy. This energy is allowed to act through optical system to the area wherever required.

It is named depending on the molecules used as—

- Argon Laser.
- **N**eo-**d**ynium-**Y**ttrium **A**luminium **G**arnet Laser (Nd-YAG Laser).
- CO_2 Laser.
- Neon Laser.
- Holmium Laser.
- Erbium Laser.

Uses of Laser

- In *cranial surgery* in children.
- In *ENT* it is used to treat vocal cord lesions, laryngeal lesions.
- In *ophthalmology* it is very useful in retinal surgery—
  - Detachment.
  - Iridotomy.
  - Dacryocystitis.
  - Capsulotomy.
  - To liquefy human lens.
  - Glaucomas.

- In *general surgery*:
  - In bleeding duodenal ulcer.
  - For palliative decoring of tumours in carcinoma oesophagus.
  - In Ca rectum.
  - In treatment of haemorrhoides (1st and 2nd degree).
  - In resection of bladder tumour.
  - In cervical cancer.
  - To achieve bloodless field.
  - Often in making incisions in abdomen and other places.

Advantages of laser

- Bloodless field
- Faster
- Small lesions can be removed easily and completely

Precautions

- All reflecting instruments should be avoided otherwise laser gets reflected and injure normal tissues or the working team in the OT.
- All should wear protective spectacles to their eyes.

Disadvantage

Availability and cost factors.

STAPLERS IN SURGERY

Staplers are used for apposition of tissues. Used in skin, bowel, lungs, etc.

Types

- **Cutaneous staplers** give clean apposition. It is faster and technically easier. Problem is removal requires specific instrument and costlier than sutures.
- **Linear staplers** are used to close the bowel either completely or partially.
- **Circular staplers** also called as E.E.A. stapler—**E**nd to **E**nd **A**nastomosis. It is commonly used for colorectal anastomosis in anterior resection for carcinoma rectum, oesophago-gastric anastomosis after oesophago-gastric resection in case of carcinoma at O-G Junction.



Fig. 32.55: Circular stapler for colorectal anastomosis.

  Parts: *Stapler gun*, and *cartridge* with two rows of stapler pins for apposition. Loaded cartridge is detachable. Cut ends of bowel are placed over *gun* and *cartridge*. Once gun is shot, cartridge moves to the gun and creates anastomosis.
- **GIA stapler** (Gastrointestinal anastomosis stapler) for *side to side* anastomosis, like small bowel or ileo-colic anastomosis.
- **Stapler for lung apposition.**
- **Endostaplers:** These are used during laparoscopic surgeries. It is commonly used for bowel anostomosis. ***Endovascular staplers*** are used to ligate vascular pedicles like renal pedicles during laparoscopic nephrectomy.
- Stapled haemorrhoidopexy – costly.



Fig. 32.56: X-ray showing nasojejunal tube for enteral nutrition purpose. It is useful and effective method of enteral nutrition. Its passage needs expertise, C ARM guidance. It can be kept for long time for 3 months. Its position is often confirmed by X-ray.

> *Remember, the most important person in an operation theatre is the patient.*
> —Berkehy George Andrew Moynihan

Disposable staplers are available but are costly.

Advantages: Technically easier and faster.

Disadvantages: Cost factor, availability.

Problems with staplers:
- It is not completely haemostatic and so bleeding can occur.
- Leak from anastomosis, improper apposition.
- Intestinal obstruction.

Self-assessment Questions

- Lasers in surgery
- Staplers in surgery
- Appendicectomy
- Circumcision
- Abdominal incisions
- Cryosurgery
- Thyroid crisis
- Vasectomy.

Laparoscopic Surgery

History

First laparoscopic cholecystectomy was done by Muhe of Germany in 1985 and by Mouret in Lyon in 1987.

McKeran and Saye performed the first laparoscopic cholecystectomy in USA in 1988.

First laparoscopic appendicectomy was done by Semm as prophylaxis.

First laparoscopic appendicectomy for acute appendicitis was done by Schreiber in 1987.

Semm changed 75% open gynaecological surgeries into laparoscopic surgeries.

Prof TE Udwadia, Mumbai did first laparoscopic cholecystectomy in India.

ADVANTAGES OF LAPAROSCOPIC SURGERY

- Relatively less painful compared to open surgery. Trauma of access is very less.
- Shorter hospital stay and early return to work.
- Faster postoperative recovery.
- Better visualisation of the anatomy, i.e. better approach for dissection and visualisation of other parts of abdomen for any other pathology.
- Instrumental access to different abdominal locations is many times better compared to open method.
- Minimal scar on the abdomen.

Instruments Used

- Zero degree laparoscope is commonly used. Side viewing scopes are also used to have better visualisation.
- Cold light source either Halogen lamp or Xenon lamp is used. Halogen lamp is used commonly and is cheaper. Xenon lamp gives high visualisation.
- Camera: 3 chip camera is commonly used with high resolution.
- Video-monitor to display images.
- CO_2 insufflator.
- Long fine dissectors like in open surgical techniques.
- Hooks and spatulas are used along with cautery for dissection.
- Clip applicators.

Figs 32.57A and B: Laparoscopic set showing trolley, telescope and monitor instruments

- Needle holders.
- Endostaplers.
- Veress needle.
- Suction-irrigation apparatus.
- Trocars of different sizes – 10 mm, 5 mm.
- Reducers to negotiate smaller instruments through larger ports.

Preparation

Always general anaesthesia. Other preparations are same as for open method.

Technique

Pressure bandages are applied to both legs to improve the venous return and to decrease the stasis.

Head end of the table is lowered to have easier insertion of veress needle and scope.

Ryle's tube and Foley's catheter are essential before insertion of the trocars.

Pneumoperitoneum is created using veress needle through umbilical incision. Access can be achieved by open method through an umbilical incision.

Everyone should be quick to listen and slow to speak.

CO_2 is commonly used to create pneumoperitoneum as
- It is readily available
- It is cheaper
- It suppresses the combustion
- It is easily absorbed by tissues
- It has a high diffusion coefficient
- It is quickly released via respiration

Other gases used are: Air, nitrous oxide, helium, argon.

Pneumoperitoneum is created up to a pressure of 15 mmHg which distends the abdominal cavity adequately to have proper visualisation of the abdominal contents.

Laparoscope is inserted through the umbilical port (10 mm). Abdomen is evaluated for any pathology. Liver, gallbladder, pelvic organs are visualised.

Additional ports (3-4) through trocars are placed depending on the procedure to be done. It may be either 5 mm port or 10 mm port. These ports are placed in such a way to have a proper triangulation of instruments for dissection.

To use clip applicator 10 mm port is required.

PHYSIOLOGIC CHANGES DUE TO PNEUMOPERITONEUM

- CO_2 causes hypercarbia, acidosis and hypoxia.
- Pneumoperitoneum exerts pressure on the IVC, decreases the venous return and so the cardiac output.
- It increases the arterial pressure also.
- It compromises the respiratory function by compressing over the diaphragm impairing the pulmonary compliance.

Complications

- CO_2 narcosis and hypoxia.
- Sepsis—Subphrenic abscess, pelvic abscess, septicaemia.
- IVC compression.
- Bleeding.
- Leak from the site, e.g. bile leak.
- Organ injury during insertion of ports, e.g. major vessels, bowel, mesentery, liver.
- Subcutaneous emphysema and pneumomediastinum.
- Gas emboli, though is rare but fatal.
- Postoperative shoulder pain due to irritation of diaphragm.
- Cardiac dysfunction due to decreased venous return.
- Injury to the abdominal wall vessels and nerves.
- Cautery burn to abdominal structures.
- Abdominal wall hernias.
- Wound infection.
- Mortality – 0.5%.

Relative Contraindications

- Patients with compromised cardiac status.
- Peritonitis.
- Previous abdominal surgeries.
- Bleeding disorders.
- Morbid obesity.
- Third trimester pregnancy.
- Portal hypertension.

Basic Laparoscopic Surgeries

- Laparoscopic cholecystectomy.
- Laparoscopic appendicectomy.

LAPAROSCOPIC CHOLECYSTECTOMY

It is becoming popular method of treatment.

Indications
- Gallstones—symptomatic
- Cholecystitis
- Biliary colic



Fig. 32.58: Portals for laparoscopic cholecystectomy.

Relative Contraindications

- End stage cirrhosis, ascites or portal hypertension.
- Cholangitis: Cholecystectomy should be done after the control of cholangitis.
- CBD stones: Here, initially ERCP and stone extraction is done from CBD, then laparoscopic cholecystectomy is done.

Technique

After pneumoperitoneum, patient is placed in head up and slight left tilt position so as to make bowels to fall below and towards the left side. One 10 mm trocar is placed at umbilicus and through this umbilical port, laparoscope is passed. One 10 mm port in the epigastric region and two 5 mm ports in the right subcostal line are placed for grasping the gallbladder and for dissection. Initially, through the working channel gallbladder is held and Calot's triangle is dissected. Cystic duct and cystic artery are clipped.

An intraoperative cholangiogram is done with C-arm. Through the epigastric port, clips or ligatures are applied to the cystic duct and cystic artery, close to the gallbladder. Care should be taken to avoid bleeding and not to injure or clip the CBD or hepatic ducts. Gallbladder is separated from its bed using cautery and spatula and removed through the epigastric port. Abdomen may be drained. Patient is discharged after 48-72 hours.



Fig. 32.59: Laparoscopic cholecystectomy. Applying clip to cystic duct is shown.

Complications

- CBD injury
- Bile leak
- Haemorrhage
- Postoperative jaundice
- Subphrenic and other intra-abdominal abscess
- Septicaemia

When problem arises, one should be ready to convert into open cholecystectomy. Conversion rate to open cholecystectomy is 2-10%. It is indicated when there is uncontrolled bleeding, dense adhesions, suspected CBD injury, when anatomy is indistinct.

When required one should not be hesitant to do conversion.

LAPAROSCOPIC APPENDICECTOMY



Fig. 32.60: Ports for laparoscopic appendicectomy.

Indications

Acute appendicitis. Here main advantage is confirmation of the diagnosis. Other parts of the abdomen are also visualised.

Relative Contraindications

Appendicular mass and abscess.

Technique: Laparoscope is passed through the umbilical port. Two additional ports are placed, one in lower midline (5 mm), another at right lumbar region. Mesoappendix is clipped or cauterized, using bipolar cautery. Appendix base is clipped or ligated using Roeder knot and ligature.

Complications

- Appendicular stump leak.
- Pelvic abscess.
- Bleeding.
- Injury to caecum, ileum.

ADVANCED LAPAROSCOPIC SURGERIES

- Presently most of the abdominal surgeries can be done through laparoscopy.

> *When light pressure is exerted over area of surgical emphysema, a sensation similar to that of like wise pulpating a horse hair mattress is experienced.* —Denis Dooley

- It requires advanced technology and skill. Surgeon should be expert in doing intracorporeal and extracorporeal knotting.

Procedures done are:

- Laparoscopic hernia repair.
- Laparoscopic splenectomy.
- Laparoscopic fundoplication.
- Laparoscopic vagotomy and gastrojejunostomy.
- Laparoscopic Nissen's fundoplication.
- Laparoscopic colectomy.
- Laparoscopic hysterectomy. It is becoming very popular.
- Laparoscopic urologic surgeries.
- Laparoscopic paediatric surgeries.

Laparoscopic Inguinal Hernia Repair

It is becoming popular method, lately. It is a skilled laparoscopic surgery.

1. *Transabdominal preperitoneal repair (TAPP repair)*: Through abdomen, using laparoscope Hesselbach's triangle is exposed and mesh is placed in the preperitoneal space. Peritoneum is sutured back or stapled.
2. *Totally extraperitoneal repair (TEP repair)*: Through subumbilical incision, pre-peritoneal space is created with the help of a balloon. Laparoscope is passed to this space. Inguinal canal is dissected and mesh is placed.

Triangle of 'Doom': It is bounded by ductus deference medially, testicular vessels laterally, with apex at internal ring. This is dangerous area in laparoscopic hernia repair as dissection may injure iliac vessels and cause torrential haemorrhage.

Complications

- Subcutaneous emphysema.
- Abdominal wall haematoma.
- Injury to major vessels.
- Recurrence.

DIAGNOSTIC LAPAROSCOPY

Indications

- Acute pelvic conditions.
- Tubal pregnancy.
- Ovarian diseases.
- Infertility.
- Staging of the malignancy.



Figs 32.61A and B: Diagnostic laparoscopy showing ectopic pregnancy in right fallopian tube. It is removed by salphingectomy through laparoscopy.

- Biopsy from the tumours.
- In chronic pain abdomen where ultrasound, endoscopies, barium studies are negative, then diagnostic laparoscopy is useful.

Needle laparoscopy of 2 mm sized becoming popular (especially for diagnostic purpose).

Advantages

- Laparotomy is avoided.
- Once diagnosis is made, therapeutic procedure also can be carried out in the same sitting.

RETROPERITONEOSCOPY

- It is becoming popular in urology to assess kidney, ureter, adrenals for various urologic procedures.

- Through a small loin approach, retroperitoneum is expanded by inflating balloon in the space. Once space is created, different ports are placed to do dissections.

Procedures done through retroperitoneoscopy are:
- Nephrectomy
- Pyeloplasty
- Adrenalectomy
- Pyelolithotomy
- Uretero-lithotomy
- Retroperitoneal lymph node dissection (RPLND)

Complications

- Injury to vessels.
- Paralytic ileus.
- Bowel (colon) injury.

Advantage

- Complications of pneumoperitoneum is not present and so respiratory reserve is well maintained.



Fig. 32.62: Port positions for retroperitoneoscopy.

Self-assessment Questions

- Diagnostic laparoscopy
- Pneumoperitoneum
- Laparoscopic cholecystectomy
- Complications of laparoscopic surgeries.

Duty makes us do things well, but love makes us do them beautifully.

Dressings and Bandages

DRESSINGS

They are the materials used to cover wounds, ulcers to provide support and to encourage healing.

Advantages

- It covers the wound and so prevents further contamination.
- It gives comfort to the patient.

Disadvantages

- It may get soaked.
- It may delay the epithelial layer formation.

Types

- *Dry dressings.* It is used in clean, sutured operated wound. It is not changed at regular intervals.
- *Wet dressings:* It is used in ulcers and wounds. Dressings are made wet by using jelly or sofra tulle sheets.

Components of Dressing

- *Inner contact layer.* It is non-absorbent and only allows secretion to pass into the absorbent layer. It does not allow penetration of granulation tissue. It is usually kept wet. Either mesh gauze or sofra tulle is used.
- *Intermediate absorbent layer* made up of cotton which absorbs the secretions.
- *Outer layer as supportive* is made up of gauze.

Dressings are fixed to the place by
- Bandages
- Plasters
- Dynoplast
- Crepe bandages.

Depending on the condition and amount of discharge from the wound/ulcer it is changed as required —twice a day/once a day/once in two days.

Small dressings are done without anaesthesia.

Large areas like burn wounds or dressing in children require general anaesthesia.

BANDAGES

Technique of bandaging is called as ***Dysmergia***.

Indications

- To reduce the swelling like in lymphoedema
- To keep dressings in position
- To support splints
- To stop bleeding/oozing

Types of Bandages

a. *Roller bandages:*
   - It is a continuous roll of material, which is rolled over the part to cover the area.
   - It is used in limbs.
   - It is available in different lengths and widths—1 inch, 2 inches, 4 inches or 6 inches.
   - It is used in different ways.
     - *Circular turns:* Continuous rolls placed over the same place.
     - *Spiral turns:* After the initial turn of the bandage, it ascends proximally overlapping the distal 2/3 of the previous turn.
     - *Reverse spiral turn.* Here each spiral turn is reversed in opposite direction so as to attain uniform pressure. It is used in limbs and areas which end as cones.
     - *Figure eight turn:* It is used in knee, elbow, wrist, ankle and for clavicle.
     - *Recurrent turn:* It is used in head, amputation stump. Here initially circular rolls are made and over that half turns are made to cover other parts of the area required.
     - *Spica bandage.* It has got ascending and descending turns, with each turn overlap and cross each other. It is used in hip, groin, shoulder, breast or thumb. *Spica means eye of a bean.*

b. *'T' bandages:* It is used in perineum and groin.

c. *Tailed bandages*: It may be four tailed bandages or many tailed bandages. It is used to support dressings on a wide area like in burns dressing, over abdomen or chest wall.

d. *Tubular bandages:* These are stockings which are unrolled over the limb to give pressure effects. It is used in lymphoedema, varicose veins and in the postoperative period following surgeries of the limb (Tubifix, Tubipress).

e. *Triangular bandage:* These are used for supporting the elbow or forearm. Here a wide gauze is used to cover the arm, forearm and elbow, which again winds around the neck.

f. *Cravat bandages:* It is a folded type of triangular bandage, which is used as sling around the neck, when elbow requires to be rested

Principles of Bandaging

- Bandage is applied to the part from distal to proximal end.
- Proper positioning of the limb is a must before bandaging.
- After initial few circular turns, the required type of bandaging is then done.
- Bandage is unrolled outwards.
- During bandaging, latter turn should overlap 2/3rd of earlier turn.
- Firm, adequate pressure should be used during bandaging.
- After completing the procedure, the knot should not lie over the area or over the bony points or over the back.
- It should not cause venous or arterial compression.
- Digits should be left open and circulation in the digits should be observed for

Finger/toe	One inch.
Arm	Two and half inches
Leg	Four inches
Thigh	Six inches
Trunk	Six inches
Head	Four inches.

Genius is one percent inspiration 99% perspiration.

Day Care Surgery

DAY CARE SURGERY

- *Day care surgery* is discharge within 23 hours (USA); surgery done without night stay (UK).
- *Day care surgery* is an upcoming field in surgical practice. It is an unique method wherein general practitioner, nurse at day care ward and theatre, surgeon, anaesthetist work in hand so that hospital stay and so the cost is reduced.
- Patient comes to hospital at morning for surgery and leaves the hospital on same day evening.

Procedures done in day care surgery—

- Excision of cysts, lipomas, bursae, neurofibromas.
- Lymph node biopsy, haemorrhoid surgery, endoscopies, circumcision, hydrocele
- Wound suturing, toe amputation

Advantages

- Minimal hospital stay
- Becomes cheaper
- Patient acceptance

- *Contraindications* for day care surgery are – age > 70 years; high risk cardiac and respiratory patients; patients with bleeding disorders.

Precautions

- Patient should be assessed properly before sending to day care surgery.
- The nurse should give proper instruction to the patient as patient stays in the hospital for a short period.
- Patient should be warned about possible problems like bleeding, vomiting, pain, discomfort, and sedation.
- Before discharging, patient should be seen by the doctor for the fitness.
- All records should be carefully documented.
- Patient should be advised to rush to hospital if any problems arise or to communicate immediately.
- Now hernia; small gynaecology procedures; ENT, cataract surgeries are done as day care procedures.

Nurses hold an important role in day care surgery.

33

Miscellaneous

Fascinating Signs in Surgery

> ***"If it is a question of doubt in diagnosis, you may often observe that one man solves the doubt when the others could not, and the way in which one man happened to solve it is this: he applied to the diagnosis of the case some method of examination which others had not applied."***
>
> **—Charles Barrett Lockwood,** 1856-1914

SIGN: Sign is an indication of existence of an objective evidence of a disease, i.e. such evidence as is perceptible to the examining physician, as opposed to the subjective sensation (symptoms) of the patient.

PATHOGNOMONIC SIGN (patho = disease, gnoma = signature, pathognomonic = signature of the disease): Specially distinctive or characteristic sign of a disease or pathological condition on which a diagnosis can be made.

ACCESSORY SIGN (Assident sign): Any nonpathognomonic sign of disease, which adds on to the surety of the diagnosis when present.

ANTECEDENT SIGN: Any precursory indication of an attack of disease. These signs are to be identified at the earliest.

1. **Aaron's sign:** A sensation of pain and/or distress in the epigastric or precordial region on pressure over McBurney's point in appendicitis.
2. **Abadie's sign:**
   Charles Abadie—Spasm of levator palpebrae superioris muscle—A sign of Graves' disease.
   Jean Abadie—Insensibility of Achilles tendon to pressure, seen in tabes dorsalis.
3. **Air cushion sign** (Syn: Klemm's sign): In the radiograph of chronic appendicitis, there is often an indication of tympanitis in the right lower quadrant.
4. **Alder's sign** of shifting tenderness: This sign is useful to diagnose acute appendicitis in pregnancy.
   Locate the most tender spot and mark it on the skin. Now request the patient to turn on the left side and wait for a full minute. If the tenderness is of uterine origin it will shift with the uterus while the position remain constant in case of appendicular origin.
5. **Angell's sign:** Helpful in diagnosing *"Torsion testis"* due to developmental anomaly—The presence of mesentery between the testis and the epididymis is invariably bilateral.

   The sign is usually obscured on the affected side and can be made out by examining the patient in the standing position wherein the opposite testis will be found to lie horizontally instead of in the normal vertical position.
6. **Anghelescus' sign:** Seen in Pott's disease of spine (TB spine) wherein the victim is unable to bend the spine while lying on the back so as to rest on the head and heel alone.

Everything is funny as long as it is happening to somebody else.

7. **Argyll Robertson pupil sign:** Typically described for neurosyphilis wherein light reflex is lost while accommodation reflex is retained. Such an eye responds poorly to mydriatics. This is due to destruction of fibres between pretectal nucleus and Edinger-Westphal nucleus. Other conditions where this sign may be seen—encephalitis, vascular and traumatic lesions, cerebral tumours, diabetes mellitus and chronic alcoholism.
8. **Auenbrugger's sign:** Bulging of the epigastrium due to massive pericardial effusion. This sign highlights the importance of examining thorax in patients with abdominal symptoms.
9. **Babinski's sign** (Not syn with Babinski's reflex):
   a. Loss or weakening of the Achilles tendon reflex in sciatica. This sign helps distinguish true sciatica from hysterical sciatica.
   b. In hemiplegia the contraction of platysma muscle in the healthy side is more pronounced than on the affected side. It can be elicited by asking the patient to open the mouth, whistling, blowing, etc.
   c. When a hemiplegic patient is lying with arms crossed upon the chest and makes an effort to sit up, the thigh on the paralyzed side is flexed upon the pelvis and the heel lifted from the floor while limb on the healthier side does not move.
   d. When the paralyzed forearm is placed in supination it turns over to pronation. It is seen in organic paralysis and is also called 'Pronation sign'.
10. **Baid sign:** Described for pseudocyst of pancreas and is well appreciated in thin individuals. When Ryle's tube is passed into the stomach, it may be palpated over the swelling because the stomach is displaced anteriorly by the pseudocyst pancreas.
11. **Ballances' sign:** Seen in about 25% of ruptured spleen. There is a dull note in both the flanks due to haemoperitoneum. The dullness on the right side can be made to shift, but that on the left side remains constant/fixed because the blood in the vicinity of the ruptured spleen gets coagulated soon.
12. **Ballet's sign:** This sign is helpful in Graves' disease and hysteria wherein there will be persistence of involuntary pupillary and reflex eye movements with loss of all voluntary eye movements (external ophthalmoplegia).
13. **Bamberger's sign:** A sign described in pericardial effusion—Presence of signs of consolidation at the angle of scapula which disappears when the patient leans forwards.
14. **Banana sign:** An ultrasonographic sign described for *Arnold-Chiari deformity*—a cause for congenital hydrocephalus. Sonography of the fetal skull reveals flattened and curved (banana like) shape of the cerebellar hemisphere.
15. **Bastede's sign:** A sign described in a case of appendicitis—*Mentioned to be condemned*—when colon is inflated with air through a rectal tube, pain and tenderness can be elicited in the right iliac fossa in a suspected case of appendicitis. Such maneuver carries risk of perforation and hence should not be entertained.
16. **Battle's sign:** It is relevant in middle cranial fossa fracture—bruising/ecchymosis over the mastoid process in the line of posterior auricular artery is a tell-tale sign of underlying middle cranial fossa fracture (temporal bone fracture).
17. **Bergman's sign:** A urologic radiographic sign:
   a. The ureter is dilated immediately below an obstructing neoplasm rather than collapsed as seen in cases of obstructing stones.
   b. The ureteral catheter passed in such cases tends to coil in this dilated portion of the ureter.
18. **Berry's sign:** Indicated by the absence of carotid artery pulsation in a patient presenting with goitrous swelling, is an ominous sign of thyroid malignancy (due to carotid sheath infiltration by the malignant tissue).
19. **Bezold's sign:** Described in a case of mastoiditis—An inflammatory swelling seen below the apex of the mastoid process.
20. **Biederman's sign:** A dark colour instead of normal pink colour of the anterior pillar of the throat is seen in some patients with syphilis.
21. **Bird's sign:** Described for hydatid disease of lung wherein a definite zone of dullness with absence of the respiratory sounds may be appreciated.
22. **Biernacki's sign:** Analgesia of ulnar nerve in general paresis and tabes dorsalis.
23. **Blatin's sign** (Syn: Hydatid thrill): A sign elicited in cases of hydatid cystic disease. It is due to displacement of daughter cysts in the fluid of the mother cyst.

24. **Boas sign:** An area of hyperaesthesia, posteriorly extending 2.5 cm lateral to the spinous process of vertebrae to the posterior axillary line and vertically from the level of the 11th dorsal to the 1st lumbar spine—A definitive sign of the presence of cholecystitis.
25. **Blumberg sign** (Syn: Rebound tenderness; Release sign): It is a sign of peritonitis due to presence of an inflamed organ underneath it.
26. **Bonnet's sign:** Pain on thigh adduction in sciatica.
27. **Boston's sign** (Syn: von Graefe's sign): It constitutes the lid lag elicited in cases of thyrotoxicosis.
28. **Bowler's hat sign** (Syn: Double ring sign): A radiological sign which describes the appearance of a gastric polyp seen on end-on position in a double contrast barium meal study. There will be a central lucency with two rims of barium around. May also be seen in cases of sessile intestinal polyp or a diverticulum.
29. **Boyce's sign:** A gurgling sound heard on pressure by the hand on the side of neck, in cases of oesophageal diverticulum.
30. **Bozzolo's sign:** A visible pulsation of the arteries in the nostrils. A sign believed to indicate the presence of aneurysm of the thoracic aorta.
31. **Branham sign** (Syn: Nicoladoni sign): This sign is elicited when arterio-venous fistula is suspected. A pressure on the artery proximal to the fistula will cause—
    a. Reduction in size of the swelling.
    b. Disappearance of bruit.
    c. Fall in pulse rate.
    d. Pulse pressure returns to normal.
32. **Brodie's sign:** A black spot on the glans penis—a sign of gangrene due to urinary extravasation into the corpus spongiosum.
33. **Bald fundus sign:** A radiological sign described for atrophic gastritis. The fundus of the stomach looks like a small dome with absence of mucosal pattern indicated by a very thin smooth appearing gastric wall.
34. **Bent inner tube sign:** A radiological sign described for sigmoid volvulus—an important diagnostic sign. A plain X-ray abdomen taken in the supine position reveals a massively distended ahaustral sigmoid colon arising from the pelvic loop.
35. **Bird of prey sign:** A radiological (Barium enema) sign which helps in confirming the diagnosis in doubtful cases of sigmoid volvulus. Barium enema reveals a smooth tapered narrowing at the point of tortion of the colon. Mucosal folds show a screw pattern around the point of twist.
36. **Border sign:** Describes the appearance of ventral hernia in barium study follow through done in suspected cases, in the postoperative period. Lateral and inferior border of the hernia are sharply outlined while the medial and upper border blends with the abdominal shadows.
37. **Cardarelli's sign:** Transverse pulsations in the laryngotracheal tube in suspected cases of aneurysms and dilatation of the aortic arch.
38. **Chvostek's sign** (Syn: Chvostek Weiss sign; Schultze's sign): A clinical sign typically described for hypocalcaemic tetany. The sign is elicited by tapping over the muscles and/or superficial nerves to induce the muscle spasm. It may be:
    a. **Facial sign**: A light tap over the facial nerve branches in front of the ear lobe causes muscular twitching over the whole of that side of the face.
    b. **Peroneal sign:** Tapping the peroneal nerve near the fibular neck will cause dorsiflexion and abduction of the foot.
39. **Cobra head sign** (Adder head appearance): A radiological sign seen in cases of ureterocele—congenital dilation of lower end of ureter. Urography done in suspected cases produces a characteristic appearance which resembles a cobra head and hence the name.
40. **Crescent sign:** A radiological sign described in relation to two different conditions affecting the lungs and the kidneys—
    a. In plain chest X-ray taken in a patient suspected of hydatid disease or aspergilloma (fungus ball) of the lung reveals a crescent of air in the shadow of partially ruptured hydatid cyst or in the cavity containing fungus ball.
    b. On IVP, the nephrogram reveals a crescent sign in cases of congenital hydronephrosis.

> *Many look but only few see.*—Maxwell M Wintrobe

41. **Cullen's sign** (Syn: Cullen Hofstatter sign): A clinical sign which was typically and initially described for ruptured ectopic pregnancy wherein there is discolouration (ecchymosis) of the umbilicus and the surrounding skin (aptly referred to as umbilical black eye). It is due to haemoperitoneum and may be seen in conditions like ruptured ectopic pregnancy (a bluish tinge), acute haemorrhagic pancreatitis (a yellowish tinge).
42. **Carman's sign** (Syn : Carman-Kirklin meniscus sign): A radiographic sign helpful in the analysis of gastric ulcers in barium meal study. It is a reliable indicator of malignancy. Nonprojecting ulcers lying intraluminal in all projections surrounded by an elevated rim of tumour produces a curval interface resembling a meniscus and is called Carman's meniscus sign. Whether the meniscus is convex or concave towards the lumen is mainly dependent upon the site of ulcer in relation to incisura angularis. Meniscus is concave towards the lumen in cases of ulcer being proximal to the incisura while it is convex when the ulcer is distal to the incisura.
43. **Carnett's sign:** A clinical sign which helps differentiate the plane of abdominal swelling. The abdominal wall muscle is made tense by asking the patient to raise both the legs with knee extended. If the lump is intraperitoneal it disappears or becomes less prominent, while it becomes prominent or persists when the lump arises from the abdominal wall.
44. **Chilaiditi's sign** (Syn: Chilaiditi's syndrome; Hepatoptosis): A radiological sign seen in plain X-ray abdomen which is helpful in the diagnosis of this syndrome wherein there is interposition of colon between liver and diaphragm. It needs to be differentiated from the conditions causing gas under the diaphragm. The presence of haustrations in the gas shadow in a plain X-ray abdomen tilts the favour in the diagnosis of Chilaiditi's syndrome.
45. **Coiled spring sign:** A radiological sign (Barium enema) classically described for intussusception. The passage of barium beyond the apex of the intussusception into the intussuscipien gives a coiled spring appearance. The sign may also be seen in cases of—
    a. Post-traumatic haematoma of duodenum.
    b. Acute appendicitis.
    c. Mucocele of appendix.
    d. Endometriosis of appendix.
    e. Intestinal carcinomas.
46. **Coles' sign:** A radiological sign. Barium meal follow through study reveals deformity of the duodenal contour in the presence of duodenal ulcer.
47. **Colon cut off sign:** A radiographic sign of appendicular perforation or colonic spasm. Absence of gas and feces in the right lower quadrant, reflex dilatation of transverse colon and sharp cut-off of gas at the hepatic flexure. This sign is also seen in acute pancreatitis
48. **Coopernail's sign:** Ecchymosis on the perineum and scrotum/labia. A sign of fracture pelvis.
49. **Cope's sign** (Syn: Psoas sign): Clinical signs which are relevant in cases of acute appendicitis. This has two tests—
    a. **Cope's psoas test:** In acute appendicitis there is psoas muscle spasm secondary to the inflamed organ and hence the patient keeps the thigh in a flexed position. This pain can be aggravated by passively hyper-extending the hip joint which stretches the psoas muscle.
    b. **Cope's obturator test:** Principles are same as above except the muscle involved is obturator internus which is passively stretched by internally rotating the right leg which is flexed at the hip and knee.
50. **Cupola sign:** A radiological sign helpful in the diagnosis of pneumoperitoneum. A plain X-ray abdomen (erect position) reveals gas under the diaphragm when there is relatively large amount of air in the peritoneal cavity—Cupola sign.
51. **Crow foot sign** (Syn: Mercedes Benz sign; Seagull's sign): A radiological sign described in relation to cholelithiasis (Gallstones). Nearly 80-90% of the gallstones are radiolucent with only 10-20% being radio-opaque. However rarely a non-opaque gallstone can be diagnosed in plain radiography by the presence of gas containing crevices within the stone. These radiolucent crevices give the appearance of the crow foot; Hence the name crow foot sign, Mercedes Benz sign or the Seagull's sign.
52. **Courvoisier's sign** (Syn; Courvoiser's law): In a patient with obstructive jaundice, if the gallbladder is palpable it is not due to gallstones.
53. **Cowen's sign:** A clinical sign elicited in cases of Graves' disease. In response to a light shone on one eye there is jerky constriction of the contralateral pupil.

54. **Crowe's sign:** Refers to axillary freckling seen in neurofibromatosis.
55. **Cruveilhier's sign** of the saphena varix: A clinical sign elicited in cases of varicose viens (Saphena varix). A thrill is felt over the saphena varix when the patient is asked to perform a Valsalva manoeuvre/cough in an erect position and is due to a jet of blood entering and filling the pouch.
56. **Coleman's sign:** Helps in the clinical evaluation of fracture mandible. There is obvious swelling and bruising over the bony injury and a haematoma in the floor of the mouth if the body of the mandible is fractured.
57. **Claw sign:** A radiological sign (Barium study) diagnostic of ileo-colic intussusception. The barium in the intussuscipien is seen as a claw around the negative shadow of the intussusceptum.
58. **Coffee bud sign:** It is a radiological sign seen in volvulus of sigmoid colon.
59. **Dalrymple's sign:** It is one of the manifestations of Graves' ophthalmopathy. It consists of retraction of the upper eyelid so that the palpebral opening is abnormally wide and upper sclera is visible.
60. **Delbet's sign:** An prognostic indicator in cases of aneurysm of the main artery of the limb. If the nutrition of the part distal to the aneurysm is maintained then the collateral circulation is said to be sufficient even though the distal pulse is not felt.
61. **de Musset's sign:** Rhythmical jerking movement of the head with each heart beat and is seen in cases of aortic insufficiency and aortic aneurysm.
62. **Dance sign** (Syn: Signe de Dance): A feeling of emptiness in the right iliac fossa—A sign of intussusception.
63. **Demarouay's sign:** Fixation or lowering of larynx during phonation and deglutition. A sign of syphilis of trachea.
64. **Dew's sign:** A clinical sign described in relation to the diaphragmatic hydatid abscess beneath the right cupola of the diaphragm. The area of resonance moves caudally with the patient in knee-elbow position.
65. **Dixon Mann's sign** (Syn: Mann's sign): In case of Graves' orbitopathy the two eyes appear not to be on the same level.
66. **Dorendorf's sign:** The sign identifies the fullness in the supraclavicular groove on one side in aneurysm of aortic arch.
67. **Double bubble sign:** A radiological sign described in cases of duodenal obstruction. A plain X-ray abdomen reveals two foci of gas, one in the stomach and the other in the duodenum—a sign of duodenal atresia. A similar feature is observed in the foetus in ultrasonography done in the antenatal period.
68. **Drummond's sign:** A whiff sound heard over the open mouth during respiration in cases of aortic aneurysm.
69. **DTP sign** (Syn: Distal tingling on percussion; Tinel's sign; Formication sign): A prognostic indicator which is helpful in the evaluation of nerve recovery following nerve injury. If percussion over the site of nerve injury causes tingling sensation in the distal end of the limb it suggests that the nerve injury was a partial one or it heralds the recovery from the nerve injury—a good prognostic sign.
70. **Dubois sign:** Shortness of the little finger in congenital syphilis.
71. **Duchenne's sign:** This clinical sign identifies the sinking of the epigastrium during inspiration (a paradox). It is classically seen in cases of paralysis of the diaphragm and in certain cases of hydropericardium (Pericardial effusion).
72. **Dupuytren's sign:** It is described in two conditions—
    a. A crackling sensation on pressure over a sarcomatous bone.
    b. In congenital hip dislocation, it refers to free up and down movement of the head of the femur.
73. **Dott's sign:** It is helpful in differentiating pain due to acute appendicitis and basal pneumonia with pleuritis. Compression of lower thorax from side to side elicits obvious distress when the lesion is above the diaphragm whereas in appendicitis it has no effect.
74. **Dock sign:** A radiological sign described in relation to coarctation of aorta. A chest X-ray PA view reveals rib notching on the inferior margins of 3rd-9th ribs while sparing the first two ribs and is indicative of collateral circulation developed in coarctation of aorta.
75. **De Weese sign:** A clinical sign helpful in cases presenting with history suggestive of intermittent claudications with palpable peripheral pulses. The patient is asked to exercise by walking or running sufficiently to bring on the pain. If prompt re-examination reveals absence of peripheral pulses it suggests that the pain was truly due to intermittent claudication.

Learn to see, learn to hear, learn to feel, learn to smell—that is clinical method.

76. **Echo sign:** A percussion sound resembling an echo which is heard over a hydatid cyst.
77. **Elliot's sign:** Refers to presence of indurated edge of a syphilitic skin lesion.
78. **Enroth's sign:** Identifies the abnormal fullness of the eyelids—a manifestation of Graves' orbitopathy.
79. **Escherich's sign** (Syn: Escherich's reflex): Described in relation to tetany, where percussion of the inner surface of the lips or tongue produces contraction of lips, tongue and masseter muscles.
80. **Ewart's sign:** It is said to be positive in cases of pericardial effusion if there is bronchial breathing and dullness on percussion at the lower angle of the left scapula and is due to pressure and collapse of the lingular lobe due to enlarged pericardial sac.
81. **E- sign** (Syn: Reverse 3 sign): A radiological sign seen on barium swallow radiograph in patient suspected of coarctation of aorta and is due to indentation produced on the barium filled oesophagus by the aorta.
82. **Figure of three sign:** A radiological sign seen in the plain chest X-ray PA view in patient with coarctation of aorta. A pair of bulges is seen in the wall of the aortic arch one above and one below the aortic knuckle and is due to pre- and post-stenotic dilatation of the aorta.
83. **Frostberg's sign:** A radiological sign seen in barium study in carcinoma of the head of pancreas involving the duodenum. In carcinoma of the head of the pancreas, there is widening of the 'C' loop of the duodenum and with the involvement of the ampulla of Vater, the expanded loop assumes a reversed 3 configuration—Frostberg's sign. Once the carcinoma of the head affects the duodenum the surgical cure is remote.
84. **Fox sign:** Discolouration near the inguinal ligament—seen in few cases of haemorrhagic pancreatitis.
85. **Fuchsig's sign** (Syn: Crossed leg test): This sign is more relevant when popliteal artery is not clinically palpable along with absent distal pulses. The patient is made to sit with his legs crossed. Normally, oscillatory movements of the foot occur synchronously with the pulse if the popliteal artery is patent while a negative result is more suggestive of popliteal artery block in a patient with absent distal pulses.
86. **Federici's sign:** An interesting sign described in relation to pneumoperitoneum (due to intestinal perforation) wherein on auscultation of the abdomen, the cardiac sounds can be heard.
87. **Flush tank sign:** A clinical sign described in relation to hydronephrosis. The patients classically present with features suggestive of Dietle's crisis, i.e. passage of a large amount of urine with consequent disappearance of a lumbar swelling—Flush tank sign.
88. **Flare sign:** The precursor of varicose ulcer is a splay of fine venules that courses from the medial (sometime the lateral) malleolus, and spreads out to be lost beneath the thick skin of the heel and is known as the "Flare sign."
89. **Gifford's sign:** A clinical sign which helps in differentiating unilateral exophthalmos and proptosis due to intraorbital tumours. If the upper eyelids cannot be easily everted on the affected side, the exophthalmos is more likely to be due to thyrotoxicosis, whereas if the lid is easily everted it is more likely due to an intra-orbital mass.
90. **Grey Turner sign:** Skin discolouration (bruising) in the left flank (left costo-vertebal angle) in cases of acute haemorrhagic pancreatitis.
91. **Gilbert's sign:** Opsiuria indicative of hepatic cirrhosis (opsiuria means excretion of urine more rapidly during fasting than after a meal).
92. **Glasgow's sign:** A clinical sign—presence of systolic murmur over the brachial artery is found in latent aortic aneurysm.
93. **Griffith sign:** It is one of the clinical signs of Graves' orbitopathy wherein there is lower lid lag on upward gaze.
94. **Guyon's sign:** Ballottement and palpation of a floating kidney.
95. **Gaur sign:** A clinical sign seen in femoral hernia. Distension of superficial epigastric and/or circumflex iliac veins on the affected side due to pressure on these vessels by the hernial sac.
96. **Guerin's sign:** Haematoma at greater palatine foramen seen in maxillary fracture.
97. **Homan's sign:** Pain on sudden dorsiflexion of the foot—a sign of deep vein thrombosis of calf veins.
98. **Hamilton Bailey sign:** A clinical sign described for intussusception. A sausage shaped mass with concavity towards the umbilicus which is felt to harden as a wave of peristalsis commences.
99. **Hall's sign:** This sign identifies a tracheal diastolic shock felt in the aneurysm of aorta.
100. **Hatchcock's sign:** Refers to the tenderness towards the angle of the jaw in mumps.

101. **Haudek's sign (Haudek's niche):** A radiological sign identified in barium meal X-ray done in patient suffering from gastric ulcer. It describes a projecting shadow (niche) in radiographs due to settlement of barium in pathological niches of stomach wall.
102. **Hitzelberger's sign:** A clinical sign described in case of acoustic neuroma wherein there is anaesthesia of medial, posterior or superior areas of the external auditory canal because of the tumour tissue compressing on the facial nerve.
103. **Hook sign:** This clinical sign identifies flexion of fingers in a case of acute suppurative tenosynovitis.
104. **Horn's sign:** This sign identifies the pain produced by traction on the right spermatic cord in acute appendicitis.
105. **Howship Romberg sign:** A sign described in the patients suffering from obturator hernia. The patient complains of pain passing down the inner side of the knee due to pressure on the obturator nerve by the hernial sac.
106. **Harvey's sign:** Two index fingers are placed by the side on a vein. The fingers are now pressed firmly and the finger near the heart is moved proximally keeping the steady pressure on the vein so as to empty the short length of vein between the two fingers. The distal finger is now released. This will allow venous refilling to be observed which will be poor in ischemic limb and increased in arteriovenous fistula.
107. **Hamman's sign** (Syn: Hamman's mediastinal crunch or murmur): A clinical sign—precordial crunching, clicking or knocking sound synchronous with each heart-beat heard on auscultation in conditions such as—
    - Acute mediastinitis
    - Pneumomediastinitis
    - Pneumothorax.
108. **Inflammatory signs** (Syn: Cardinal signs in inflammation):
    - Rubor—Redness
    - Calor—Temperature
    - Dolor—Pain
    - Tumour—Oedema/swelling
    - Functio lesa—Loss of function
109. **Jendrassik's sign:** Paralysis of extraocular muscles—A manifestation of Graves' orbitopathy.
110. **Jugular sign** (Syn: Quekenstedt's sign; Tobey Ayer test): On spinal canal block (e.g. spinal tumour) when pressure is applied over jugular veins, in the manometer connected to LP needle, either pressure will not raise or if raises falls slowly.
111. **Joffroy's sign:** Absence of wrinkling of the forehead when the head is bent down and the patient is asked to look upwards—A sign of Graves' ophthalmopathy.
112. **Kernig's sign:** A sign which is positive in meningitis. With the hip flexed, the knee is extended, normally it can be done upto 175°. In meningitis it is restricted due to spasm of the hamstrings.
113. **Kaposi Stemmer sign:** Failure to pick up or to pinch a fold of skin at the base the second toe. It is characteristic of lymph oedema.
114. **Kocher sign** (Syn: Mean's sign): A sign of Graves' orbitopathy. The examiner places one hand on a level with the patient's eye and then lifts it higher. The upper eyelid springs up more quickly than the eyeball.
115. **Kanavel sign:** This sign is useful in the diagnosis of ulnar bursitis. In case of ulnar bursitis the site of maximum tenderness is over that part of the ulnar bursa lying between the transverse palmar creases.
116. **Kantor's sign** (String sign of Kantor): A radiological sign described in barium enema follow through in patients suffering from Crohn's disease. A string like configuration of contrast material through a filling defect is seen in the radiography.
117. **Kehr sign:** This sign identifies the pain elicited in the left shoulder in patients with suspected splenic rupture. The pain (referred pain) experienced by the patient is due to blood in the peritoneal cavity irritating the diaphragm.
118. **Klemm's sign:** It is the radiological sign found in chronic appendicitis where there is often an indication of tympanitis in the right lower quadrant.
119. **Knie's sign:** Unequal dilatation of the pupils—a sign of Graves' orbitopathy.
120. **Krisowski's sign:** Cicatricial lines radiating from the mouth in congenital syphilis.

> *Absolute diagnosis are unsafe and are made at the expense of the conscience.*—William Osler

121. **Kenawy's sign:** A clinical sign usually associated with bilharzial fibrosis of liver (Egyptian splenomegaly) but may be present in any type of portal hypertension. Auscultation over the xiphoid process reveals a venous hum (splenic vein engorgement) which becomes prominent on inspiration.
122. **Klein's sign** (of shifting tenderness): A clinical sign useful in acute nonspecific mesenteric lymphadenitis. When patient is shifted to left lateral position, point of maximum tenderness also gets shifted to the left side in contrast to acute appendicitis. It may also be positive in Meckel's diverticulitis.
123. **Lemon sign:** A radiological sign of Arnold-Chiari deformity. There is scalloping of the frontal bones giving the skull a lemon shaped configuration in sonography of the fetal skull during second trimester of pregnancy.
124. **Lennhoff's sign:** A furrow appearing on deep inspiration below the lower rib and above an echinococcal cyst of liver.
125. **Sign of Leser Trelat:** Sudden appearance and rapid increase in size and number of seborrhoeic keratoses, a sign of internal malignancy of the GIT.
126. **Lloyd's sign:** A clinical sign elicited in a patient with renal calculus. Pain elicited in the loin on deep percussion over the kidney even when there is no pain on applying deep pressure.
127. **London's sign:** It is useful in ruptured intestine suspected in an accident case. The presence of pattern of bruising of the skin (i.e. an imprint of the clothing is noted on the skin) indicates that a crushing force has been applied sufficient to rupture the bowel against the vertebral column. This sign is a strong indication to carry a laparotomy.
128. **Mallet Guy's sign:** A clinical sign identified in chronic relapsing pancreatitis. It is elicited by placing the patient in the right lateral position with the patient's hip and knee flexed and deeply palpating the abdomen in the epigastric and the left subcostal region. This will evoke tenderness in chronic relapsing pancreatitis.
129. **McBurney's sign:** Finger tip pressure is made over the McBurney point elicits severe tenderness in patients with appendicitis.
130. **Murphy's sign** (Moynihan's method): This clinical sign is classically described in patients suffering from cholecystitis. It is elicited by asking the patient to breath deeply while exerting moderate pressure with the left hand such that thumb lies over the fundus of the gallbladder. The patient catches his breath as the inflamed gallbladder which is pushed down by the diaphragm gets imposed against the thumb.
131. **McEwen's sign:** A clinical sign elicited in children with hydrocephalus. On percussion of skull behind the junction of frontal, parietal and temporal bones and auscultation over opposite mastoid bone there is a more resonant note than normal, seen in internal hydrocephalus and cerebral abscess in children (syn: cracked pot sign, cranial cracked pot sound).
132. **Meniscus sign:** Refer No. 57.
133. **Moebius sign:** Inability to keep the eyeballs converged due to insufficiency of medial rectus muscle— A clinical sign of Graves' ophthalmopathy.
134. **Milian's ear sign:** A clinical sign which is useful to differentiate facial erysipelas from cellulitis. Erysipelas being a cuticular lymphangitis spreads from the face to the pinna while the cellulitis which is spreading inflammation of the subcutaneous tissue stops short of pinna because of close adherence of the skin to cartilage.
135. **Mahler's sign:** A steady increase of pulse rate without corresponding increase of temperature seen in thrombosis.
136. **Mann's sign** (Syn: Dixon Mann's sign): In Graves' disease the two eye appears not to be on the same level.
137. **Marie's sign:** Tremors of body extremities in Graves' disease and other types of hyperthyroidism.
138. **Mean's sign** (Syn: Kocher's sign): Refer No. 114.
139. **Medusa Lock sign:** A radiological sign described in patients with intestinal obstruction due to round worm infestation. A plain X-ray erect film of the abdomen reveals trapped intestinal gas within the worm mass giving a characteristic appearance of coiled locks of hair—Medusa Lock sign.
140. **Meitzer's sign:** Loss of normal second heart sound on auscultation of the heart after swallowing. Seen in occlusion or contraction of lower part of oesophagus.
141. **Mercedes Benz sign** (Syn: Crow foot sign): Refer No. 51.
142. **Mexican hat sign:** A radiological sign described in barium enema (filling defect) done in patients with pedunculated polyp of the inferior wall of the colon.
143. **Maulage sign:** Waxy cast appearance of bowel segments—A radiographic sign of coeliac disease.
144. **Mose's sign:** A clinical sign suggestive of deep vein thrombosis. It is elicited by squeezing the relaxed calf muscles from side to side which is painful in case of deep vein thrombosis.

145. **Niche sign** (Syn: Haudek's sign): Refer No. 101.
146. **Nicoladoni's sign** (Syn: Branham's sign): Refer No 31.
147. **Oliver's sign** (Syn: Porter's sign; Tracheal tug): Tracheal tug is seen in—
    - Aneurysm of the aorta.
    - Neoplasm which fixes bronchus to aorta.
148. **Omega sign:** A radiological sign observed in patient suspected of sigmoid volvulus on the X-ray. A plain X-ray abdomen taken in the supine position shows a massively distended sigmoid colon with haustrations arising from the pelvis resembling Greek letter 'omega' (ω).
149. **Payr's sign:** Pressure over the sole of the foot elicits severe pain in cases of thrombophlebitis.
150. **Peroneal sign:** Tapping the peroneal nerve near the fibular neck causes dorsiflexion and abduction of foot in hypocalcaemic tetany.
151. **Perez's sign:** A friction sound heard over the sternum when the patient raises and drops his arms. A sign of mediastinal tumour or aneurysm of arch of aorta.
152. **Parrot's sign** (Syn: Parrot's nodes, hot cross bun skull, Natiform skull): Bony nodes on the outer table of the skull of infants with congenital syphilis, so that it has a hot cross bun or buttock shape.
153. **Pfuhl sign:** A clinical sign which helps in differentiating between subphrenic abscess and pyopneumothorax. Inspiration increases the force of flow in paracentesis in subphrenic abscess, but lessens in case of pyopneumothorax. This distinction is however lost in cases where diaphragm is paralyzed.
154. **Pitre's sign:** Hypoaesthesia of scrotum and testes in tabes dorsalis.
155. **Plummer's sign** (Syn: Quadriceps sign): Inability to step up onto the chair or to walk up steps seen in Graves' disease and other forms of hyperthyroidism.
156. **Pool Schlesinger's sign:** In tetany if patients leg is held at the knee joint and flexed strongly at the hip joint, within a short time there will be an extensor spasm at the knee joint with extreme supination of foot.
157. **Porter's sign:** Tracheal tugging in aneurysm of aortic arch and neoplasms which fix the left bronchus to aorta.
158. **Potain's sign:** Extension of percussion dullness over the arch of the aorta from the manubrium to the third costal cartilage on the right side—seen in cases of dilatation of the aorta.
159. **Prehn's sign:** Elevation and support of the scrotum will relieve the pain in epididymo-orchitis but not in torsion testis.
160. **Psoas sign** (Syn: Cope's test): Refer No. 49.
161. **Puddle sign:** Describes a clinical method to detect small amount of ascites (150-500 ml.) Patient lies prone for 5 minutes and then goes for knee-elbow position. In this position dullness is elicited in the umbilicus in case of minimal ascites.
162. **Pemberton's sign:** This sign refers to symptoms of faintness with evidence of facial congestion and external jugular vein distension when the arms are raised above the head touching the ears. This manoeuvre reduces the thoracic inlet thereby hampering venous drainage of the face in the presence of retrosternal thyroid.
163. **Pointing sign:** Ask the patient to point to the site of maximum pain. If this proves to be the site of localized tenderness it is also certainly the site of diseased organ, e.g. appendicitis.
164. **Patel's sign:** It is important in paralytic ileus. Apply the stethoscope firmly to the skin just below and right of the umbilicus for full 3 minutes. In paralytic ileus there will be omnious silence, broken by patient's own heart sounds believed to be transmitted via the over distended coils of the intestine with added succussion splashes if the patient moves and very occasionally by faint tinkles.
165. **Pad sign:** A radiological sign identified in patients with carcinoma of the head of pancreas wherein the 'C' loop of barium filled duodenum may be widened.
166. **Panda sign** (Raccoon sign, Spectacle haematoma, Black eye): Haemorrhages in soft tissues around the eye and in the eye lids is known as Panda sign as it resembles panda eyes. It is caused by:
    1. Direct trauma, such as punch to the eye.
    2. Blunt impact to the forehead, the blood gravitating downwards over the supraorbital ridge.
    3. Fracture of the floor of the anterior fossa of the skull.
167. **Queckenstedt's sign** (Jugular sign; Tobey Ayer test): Refer No. 110.

> *Observe, record, tabulate, communicate. Use your five senses.*—William Osler

168. **Quenu Muret sign:** A prognostic indicator. In aneurysm, when the main artery of the limb is compressed and a puncture is made at the periphery, if the blood flows, then the collateral circulation is probably established.
169. **Rat-tail sign:** A radiological sign described in relation to oesophageal carcinoma.
170. **Ridge sign:** A clinical sign of dehydration. In considerable dehydration if the skin is picked up in between the thumb and fingers and then released, instead of it springing back with normal elasticity, a ridge is formed that subsides slowly.
171. **Rovsing sign:** In acute appendicitis, when left iliac fossa is pressed; pain is felt in right iliac fossa.
172. **Release sign** (Syn: Rebound tenderness; Blumberg's sign): Refer No. 25.
173. **Reversed 3-sign:** Refer No. 81.
174. **Reisman sign** (Syn: Snellen's sign): The bruit heard over the closed eye in Graves' disease.
175. **Rocher's sign:** A clinical sign which helps in the differentiation of epididymitis from torsion of the testes. In torsion testes, the epididymis cannot be distinguished from the body the testes, whereas in epididymitis the body of the testes can be felt in the enlarged crescent of epididymis.
176. **Rommelaere's sign:** An abnormally small proportion of normal phosphates and of sodium chloride in urine in cancerous cachexia.
177. **Rotch sign:** A clinical sign identified in case of pericardial effusion. Dullness is felt on percussion on the right 5th intercostal space.
178. **Rovighi's sign:** A fremitus felt on percussion and palpation of the superficial hepatic hydatid cyst.
179. **Racoon sign** (Syn: Panda sign, Spectacle Haematoma, Black Eye): Refer No. 166.
180. **Sign of splashing** (Syn: Succussion splash): Seen in gastric outlet obstruction.
181. **Saegesser's sign:** A clinical sign identified in patients with splenic rupture. An excruciating tenderness is elicited in the Saegesser's point or splenic point (seen in the lower part of the posterior triangle of the neck between the left sternomastoid and scalenus medius muscle above the clavicle).
182. **Sternomastoid sign** (Syn: Trail's sign): The sternal head of the sternomastoid muscle will become more prominent on the side to which trachea is deviated.
183. **Saenger's sign:** Refers to the light reflex of the pupil that has ceased, returns after a short stay in the dark. Observed in cerebral syphilis but not in tabes dorsalis.
184. **Sansom's sign:** Described in two separate context—
    - Marked increase in the area of dullness in the second and third intercostal space – Due to pericardial effusion.
    - A rhythmical murmur heard with a stethoscope applied to the lips in aneurysms of the thoracic aorta.
185. **Schlesinger's sign** (Syn: Pool's phenomenon): Refer No. 156.
186. **Schultze sign** (Syn: Schultze Chvostek sign): Refer No. 38.
187. **Silex's sign:** Furrows radiating from the mouth in congenital syphilis.
188. **Sisto's sign:** Constant crying in infancy—a sign of congenital syphilis.
189. **Setting sun sign:** A clinical sign described in patients suffering from raised intracranial tension. There is downwards deviation of the eyes so that each iris appears to set beneath the lower eyelid with white sclera exposed between it and the upper lid. This sign is observed in cases—
    - Hydrocephalus
    - Intracranial haemorrhage
    - Brain tumours
190. **Snellen's sign** (Syn: Reisman sign): Refer No. 174.
191. **Sumner's sign:** This sign is said to be positive when there is increase in the tone of the abdominal muscle on gentle palpation of the right iliac fossa. It may indicate—
    - Appendicitis
    - Right ureteric or renal stones
    - Torsion ovarian cyst.
192. **Simon's sign:** Identifies absence of usual co-relation between the movements of diaphragm and thorax, seen in early cases of meningitis.
193. **Stierlin's sign:** A radiological sign observed in barium enema study of the colon where there is absence of normal shadow due to an indurating or ulcerative process such as tuberculosis of caecum or colon.
194. **String sign** (Syn: Kantor's sign): Refer No. 116.
195. **Suker's sign:** Deficient complementary fixation in lateral eye rotation—a manifestation of Graves' orbitopathy.

196. **String of beads sign:** A series of round shadows resembling a string of beads or pearls, seen on a radiograph of small intestine, indicating of trapped gas surrounded by the fluid of obstructed and distended bowel.
197. **Stellwag's sign:** Identifies the widening of palpebral fissures (staring look) due to retraction of upper eyelids, an early sign of Graves disease.
198. **Stemmer sign** (Kaposi Stemmer sign): Refer No. 113.
199. **Slip sign:** A clinical sign which helps in differentiating a solid swelling, e.g. lipoma, from a cystic swelling. Here, when the edge of the swelling is palpated, the margin of the solid swelling does not yield but slips away from it unlike a cystic swelling which yields to the pressure of the palpating finger and does not slip away.
200. **Solius sign:** A radiological finding observed in a chest X-ray lateral view in patient's with enlarged thymus. An enlarged thymus being a firm swelling does not get flattened against sternum by the pressure of heart and great vessels.
201. **Shrinkage sign:** A radiological sign of thymus enlargement. In a chest X-ray there is a paradoxical alteration of the shape of the chest with respiration (Decrease in transverse diameter with deep inspiratory film than the expiratory film).
202. **Seagull sign:** Refer No. 51.
203. **Suzmann's sign:** A clinical sign described in patient with coarctation of aorta. The collaterals which develop display visible and palpable pulsations together with thrills and murmurs which are most obvious in the interscapular and infra-scapular regions of the back. The Dock sign is the radiological counterpart of this sign.
204. **Trail's sign** (Syn: Sternomastoid sign): Refer No. 182.
205. **Tap sign** (Syn: The percussion sign; Chevrier's sign): If the valves are incompetent an impulse will be felt by the fingers overlying the long saphenous vein when the varicosities are percussed below.
206. **Thornton's sign:** Refers to the severe pain complained by the patient in the region of the flanks in nephrolithiasis.
207. **Tinel's sign** (Syn: DTP sign; Formication sign): Refer No. 69.
208. **Tresilian sign:** This sign identifies reddish appearance (congestion) in opening of Stensen's duct in cases of mumps.
209. **Trimadeau's sign:** A radiological sign identified in barium swallow X-ray done in patient's with dysphagia. If the dilatation above an oesophageal stricture is conical, the stricture is fibrous; while it is cup shaped (shouldering) it is likely to be malignant.
210. **Tanyol's sign:** In ascites umbilicus shifts downwards and in mass arising from pelvis it shifts upwards.
211. **Troisier's sign:** Identifies enlargement of left supraclavicular lymph node (Virchow's node). Seen in—
    - Ca stomach
    - Ca testes
    - Ca bronchus
    - Malignancy of any other abdominal organ.
212. **Trousseau's sign:** This sign is described under two different context—
    - The blood pressure cuff is applied to the arm and inflated to pressure above systolic pressure for 3-5 minutes. This will elicits typical carpo-pedal spasm (obstetrician's hand) in cases of hypoparathyroidism and other conditions associated with hypocalcaemia.
    - Migrating superficial thrombophlebitis—a sign of visceral carcinomas especially of pancreas or the stomach.
213. **Tracheal fluctuation sign:** A unique sign elicited in patients suffering from achalasia cardia.
214. **von Graefe's sign** (Syn: Graefe's sign): Persistent lagging of upper lid behind the corneoscleral limbus when patient is asked to follow the finger moved up and down several times. Seen in Graves' disease.
215. **Vermooten's sign:** A clinical sign helpful in the intrapelvic rupture of urethra. On per rectal examination, the prostate cannot be felt but in its position a doughy swelling (blood and urine) is felt. If prostat is felt, it is displaced upwards.
216. **Vas sign:** This sign is helpful in differentiating testicular neoplasm and an inflammatory lesion of the testes. Inflammatory lesions causes vas deferens to become considerably thickened which remains normal in cases of neoplasm.

> *Probability is the rule of life, especially under the skin. Never make a positive diagnosis.*—William Osler

217. **Vein sign:** A bluish cord along the mid-axillary line formed by the swollen junction of the thoracic and superficial epigastric vein. Seen in—
    - Tuberculosis involving the bronchial glands
    - Superior vena cava obstruction.
218. **Wegner's sign:** A postmortem finding—A broadened discoloured appearance of the epiphyseal line in infants who have died from congenital syphilis.
219. **Wilder's sign:** An early clinical sign of Graves' disease consisting of slight twitch of the eyeball when it changes its movement from adduction to abduction or vice versa.
220. **Wimberger's sign:** Symmetrical erosions of the proximal tibia seen radiographically in infants with congenital syphilis.
221. **Water lily sign** (Syn: Lily pad sign): A radiological sign identified in cases of hydatid cyst of the lung. When the hydatid cyst ruptures, the daughter cyst floating within the cavity appear like a water lily hence the name water lily sign.
222. **Smith's sign:** Murmur heard in cases of enlarged bronchial lymph nodes on auscultation over the manubrium with the patients head thrown backwards.
223. **'H' Bomb sign:** A radiological sign seen in cases of atrophic gastritis. The gastric folds within fundus and the body of stomach are very thin and the thin walled fundus becomes distended with air (in erect posture) or with barium contrast.

Triads in Surgery

1. **Saint's triad:**
    - Diverticulosis of colon
    - Gallstones
    - Hiatus hernia.
2. **Whipples' triad:** Seen in insulinoma.
    - Features of hypoglycaemia
    - Blood sugar less than 45 mg%
    - Symptoms are relieved by glucose.
3. **Charcot's triad:** Seen in ascending cholangitis.
    - Intermittent fever
    - Intermittent pain
    - Intermittent jaundice.
4. **Virchow's triad:**
    - Change in the vessel wall
    - Diminished rate of blood flow
    - Increased blood coagulability.
5. **Murphy's triad:** Seen in acute appendicitis.
    - Pain in right iliac fossa
    - Vomiting
    - Temperature
6. **Hutchinson's triad:** Seen in late congenital syphilis
    - Interstitial keratitis
    - 8th nerve deafness
    - Hutchinson's teeth.
7. **Trotter's triad:** Seen in nasopharyngeal carcinoma.
    - Conductive deafness
    - Elevation and immobility of same side soft palate
    - Pain in the side of the head.
8. **Tillaux's triad:** Seen in mesenteric cyst.
    - Soft fluctuant swelling in the umbilical region
    - Freely mobile in the direction perpendicular to mesentery
    - Zone of resonance all around.
9. **Triad of portal hypertension:**
    - Varices
    - Splenomegaly
    - Ascites.
10. **Cushing's triad:** In intracranial hypertension.
    - Increased blood pressure
    - Decreased pulse rate
    - Decreased respiratory rate.
11. **Triad of renal cell carcinoma:**
    - Anaemia
    - Haematuria
    - Mass in the loin.

> *Reason of life is destiny of unknown; and desire of life.*

12. **Borchardt's triad:** Seen in gastric volvulus
    Acute epigastric pain.
    Violent vomiting.
    Inability to pass nasogastric tube.
13. **Beck's triad:** Seen in cardiac tamponade.
    Muffled heart sounds.
    Distended neck veins.
    Hypotension.
14. **Pancoast's triad:** Seen in Pancoast tumour.
    Excruciating pain in the arm.
    Horner's syndrome.
    Erosion of ribs.
15. **Prune-Belly triad:** Seen in Prune-Belly syndrome.
    Cryptorchidism
    Abdominal wall defects.
    Genitourinary defects.
16. **Mackler's triad:** Seen in Boerhaave's syndrome.
    Vomiting.
    Chest pain.
    Sub-cutaneous emphysema.
17. **Triad of Sandblom:** Seen in haemobilia
    Jaundice.
    Pain.
    Melaena
18. **Galezia triad:**
    Dupuytren's contracture.
    Retroperitoneal fibrosis.
    Peyronie's disease of penis.
19. **Dieulafoy's triad: Seen in appendicitis**
    Hypersensitiveness of skin
    Reflex muscular contraction
    Mac Burney's tenderness
20. **Triad of congenital diaphragmatic hernia**
    Respiratory distress.
    Apparent dextrocardia.
    Scaphoid abdomen
21. **Carney's triad**
    Functioning adrenal para ganglioma—nonfamilial.
    Gastric leiomyosarcoma.
    Pulmonary chondroma.

Misnomers in Surgery

1. *White bile*: It is neither white nor bile. It is opalescent. It contains mucus. It signifies severe obstructive jaundice due to which secretion of bile from liver is stopped. Mucus is derived from biliary tree lining.
2. *Mycotic aneurysm*: It is not due to fungal infection. It is due to bacterial infection.
3. *Lateral aberrant thyroid*: It is not an aberrant thyroid. It is secondaries in neck lymph node from occult primary in the thyroid, i.e. papillary carcinoma thyroid.
4. *Adenolymphoma of parotid gland*: It is not lymphoma. It is a benign tumour of the parotid. It never turns into malignancy.
5. *Pretibial myxoedema*: It is not seen in myxoedema. It is seen in thyrotoxicosis.
6. *Sternomastoid tumour:* It is not a tumour. It is due to birth trauma which causes organised haematoma in sternomastoid muscle.
7. *Dissecting aneurysm:* It is aortic dissection, not dissecting aneurysm.
8. *Malignant hydatid:* It is not malignant. It is due to Echinococcus alveolaris. It behaves like a malignant condition.
9. *Malignant exophthalmos:* It is due to primary thyrotoxicosis. It is not a malignant condition.
10. *Spina ventosa*: It is tuberculous dactylitis. It is not related to spine.
11. *Mycosis fungoides:* It is cutaneous "T" cell lymphoma. It is not due to fungal infection.
12. *Hypernephroma*: It is renal cell carcinoma. It is not above the kidney.
13. *Hepatoma:* It is hepatocellular carcinoma. It is not benign tumour.
14. *Melanoma:* It is melanocarcinoma. It is not benign.
15. *Surgical ganglion:* It is arising from the synovial sheath. It is not from nerve ganglion.
16. *Brain fungus*: It is not a fungal infection. It is seen in cranial injury wherein due to injury brain protrudes out of the wound as fungus.
17. *Cock's peculiar tumour*: It is not a tumour. It is ulcerated sebaceous cyst. It mimics SCC of skin.
18. *Pott's puffy tumour:* It is not a tumour. It is osteomyelitis of the frontal bone with cellulitis of the frontal region of the scalp. It may spread intracranially through emissary veins which endangers the life of the patient.
19. *Tumour alba*: It is tuberculosis of synovial sheath of knee joint.
20. *Umbilical adenoma*: It is not a tumour. It is prolapse of mucosa of cutaneous end of vitello-intestinal duct
21. *Madelung's deformity*: It is not associated with any of the conditions in the lung. It is a congenital subluxation or dislocation of the lower end of the ulna, from malformation of the bones.
22. *Ray fungus:* Actinomycoses, a bacteria infection.
23. *Malignant pustule:* Anthrax infection.
24. *Malignant oedema:* Gas gangrene.
25. *Juvenile melanoma:* It is not a melanoma. It is benign SPITZ naevus.
26. *Hydrocele of the neck*: It is cystic hygroma
27. *Kuttner tumour*: It is chronic sclerosing sialadenitis of submandibular salivary gland.

Finding remedy is better than finding fault.

Triangles in Surgery

1. *Hesselbach's triangle:* The medial border of the triangle is formed by the rectus sheath, superolateral border by the inferior epigastric artery, inferior border by the inguinal ligament.

   Importance: Helps in differentiating direct from indirect hernias.

2. *Bryant's triangle:* Patient lies in supine position, three lines are drawn, one from the anterior superior iliac spine vertically down to the bed; another from the tip of the greater tronchanter to join the first line at the right angles; third line from anterior superior iliac spine to the tip of the greater tronchanter—this forms a triangle.

   Importance: Diminution in the length of the second line indicates upward displacement of the greater trochanter. Third (oblique) helps determine the antero-posterior displacement of the greater tronchanter.

3. *Triangle of Doom:* Bounded by the ductus deferens medially, spermatic vessels laterally in the male and the apex of the triangle is at the level of internal inguinal ring.

   Importance: External iliac artery and vein, femoral nerve are located in the triangle and so stapling is avoided in this triangle while doing laparoscopic preperitoneal repair for hernia.

4. *Calot's triangle:* Formed medially by the common hepatic artery, laterally by the cystic duct and the apex is formed by the junction of the cystic and the hepatic ducts. Base is formed by the cystic artery.

   Importance: Cystic lymph node of 'Lund' is present in the fork created by the junction of the cystic and common hepatic artery.

5. *Anal triangle and urogenital triangle:* A transverse line joining the anterior parts of the ischial tuberosities and passing immediately anterior to the anus divides the perineum into two triangles, anal and urogenital triangle. Anal triangle contains the termination of the anal canal in the median plane and an ischiorectal fossa on each side.

   Importance: Both the perineal and ischiorectal spaces in the anal triangle are common sites of abscess.

6. *Femoral triangle:* It is triangular depression on the front of the upper one-third of the thigh below the inguinal ligament, bounded medially by the medial border of adductor longus, laterally by the medial border of sartorius, apex is formed by the meeting point of the medial and lateral boundaries.

   Importance: Femoral vein in this site is most suitable for intravenous injection in the infants; femoral artery pulsations are an important aid for clinicians (in diagnosing peripheral vascular disease).

7. *Lumbar triangle:*
   a. *Inferior lumbar triangle of Petit*—bounded by the crest of ilium below, external oblique laterally and medially by the latissimus dorsi.
   Importance: Most primary lumbar hernia occur through this triangle.

   b. *Superior lumbar triangle of Grynfelt*—bounded by the 12th rib above, medially by the sacrospinalis and laterally by the posterior border of the inferior oblique.
   Importance: Grynfelt hernia appears through superior lumbar triangle.

8. *Triangle of auscultation*: This is a small triangular interval bounded medially by the lateral border of the trapezius, laterally by the medial border of the scapula and inferiorly by the upper border of latissimus dorsi. Floor of the triangle is formed by the 7th rib, 6th and 7th intercostal spaces and *rhomboids minor*.

   Importance: This is the only part of the back which is not covered with muscles. Respiratory sounds are better heard with a stethoscope here than that heard elsewhere in the back.

   On the left side, the cardiac end of the stomach lies deep to this triangle and in days before X-rays were discovered, sounds of swallowed liquids were auscultated over this triangle.

9. *Simon's triangle:* Bounded anteriorly by the recurrent laryngeal nerve, posteriorly by the common carotid artery and base is formed by the inferior thyroid artery.

   Importance: Aids in identification of the recurrent laryngeal nerve.

10. *Lumbosacral triangle of Marcille:* It is a triangular interval on each side of the body of the 5th lumbar vertebra, bounded medially by the body of the 5th lumbar vertebra, laterally by the medial border of the psoas muscle, apex by the junction of the psoas major muscle and the body of the 5th lumbar vertebra. Base is formed by the upper surface of the ala of the sacrum and floor by the transverse process of the 5th lumbar vertebra and the iliolumbar ligament.

    Importance: Ureter crosses the common iliac vessels at the lateral angle of the triangle.

11. *Retromolar trigone:* Base overlies the ascending ramus of the mandible from the last molar, apex terminates at the maxillary tuberosity, laterally continuous with the buccal mucosa and medially blends with the anterior tonsillar pillar.

    Importance: Common site for oral malignancy.

12. *Sherren's triangle:* Bounded by the umbilicus, symphysis pubis and the anterior superior iliac spine.

    Importance: Indicates the area of hyperaesthesia in an acute episode of appendicitis.

13. *Scalene triangle:* Bounded by scalenus anticus anteriorly, scalenus medius posteriorly and first rib inferiorly.

    Importance: Subclavian artery and trunks of the brachial plexus pass through the scalene triangle where they may be compressed causing thoracic outlet syndrome.

Dead men are always good men !!

Drugs at a Glance

> ***Remember how much you do not know. Do not pour strange medicines into your patients.***
> **—William Osler,** 1903

ANTIBACTERIALS

> ***It seems likely that in the next few years a combination of antibiotics with different antibacterial spectra will furnish a "cribrum therapeuticum" from which fewer and fewer infecting bacteria will escape.***
> **—Alexander Fleming,** 1946

SULFONAMIDES

They act by inhibiting folic acid synthetase which converts PABA to folic acid.

Side effects: Intolerance, crystalluria, agranulocytosis, goitre, neuritis, jaundice.

Drugs

Sulfadiazine: 1 gm 6th hourly.
Sulfamethizole: 200 mg 6th hourly.
Sulfadimidine: 1 gm 6th hourly.
Sulphamethoxazole:
Sulfaguanidine: 3 gm 6th hourly.
Sulfamethoxale: 1 gm 6th hourly.
Used in meninigitis, UTI, chancroid, trachoma, ulcerative colitis, toxoplasma, B. dysentery.
Silver sulphadiazine cream 1% for burns.
Sulphacetamide as ophthalmic solution.

Cotrimoxazole: Combination of trimethoprim and sulfamethoxazole in a ratio of 1 : 5 in different strengths

Trimethoprim inhibits dihydrofolate reductase enzyme which converts dihydrofolate into tetrahydrofolate. It has got synergistic action with sulphamethoxazole.

It is used as BID dose in typhoid, plague, UTI, prostatitis.

Side effects: Severe skin reactions, megaloblastic anaemia.

QUINOLONES

They act by interfering with the synthesis of DNA.

They are useful against gram-negative organisms, enteric fever, respiratory infections, gastroenteritis, urinary infections, tuberculosis.

Side effects: Allergic reactions, CNS manifestations, hallucinations, nephritis, arrhythmias.

Drugs

Nalidixic acid 1 gm 6th hourly.
Norfloxacin 400 mg BD for 10 days.
Ciprofloxacin 500 mg BD for 10-14 days.
Pefloxacin 400 mg BD.
Ofloxacin 200 mg OD or BD for 10-14 days.
Lomefloxacin 400 mg OD.
Sparfloxacin 200 mg BD.
Levofloxacin 500 mg OD for 7-14 days.
Gatifloxacin 200 mg OD.

PENICILLIN

It acts by interfering with the cell wall synthesis of bacteria.

Used in *Streptococcus, Pneumococcus, Meningococcus* and gonococcal infections, syphilis, tetanus, gas gangrene, acitnomycosis, plague. It is also used as prophylaxis in rheumatic fever. It is used in pelvic infections, lymphoedema.

Side-effects: Anaphylaxis, serum sickness, Jerisch-Herxheimer reaction.

Drugs:

Benzyl penicillin. 4-10 lakhs 4th or 6th hourly intravenously after test dose.
Procaine-penicillin 4-10 lakhs IM after test dose OD for 7-14 days.
Benzathine penicillin 12-24 lakhs deep IM into the buttocks after test dose once in 3 weeks.

AMPICILLIN/AMOXYCILLIN/TALAMPICILLIN/PIVAMPICILLIN

Used in respiratory infections, meningitis, endocarditis, cutaneous infections.
It is not useful in penicillin-resistant staphylococci infections.
Dose: 500 mg 6th hourly.

METHICILLIN

It is a penicillin group of antibiotic which is used in penicillin resistant staphylococcal infections.
Dose: 1-2 gm. IM 6th hourly.
1 gm in 5-10 ml normal saline can be used as intrapleural or intra-articular therapy.

CLOXACILLIN/DICLOXACILLIN/FLUCLOXACILLIN

These drugs are used in penicillin resistant staphylococcal infections.
Dose: 500 mg 6th hourly.

CARBENICILLIN/TICARCILLIN

It is used in septicaemias, urinary tract infections mainly due to *Pseudomonas* and *Proteus* infections.
Dose: 1 gm 6th hourly IV.

PIPERACILLIN/AZOCILLIN/MEZLOCILLIN

It is active against *Pseudomonas.*
Dose: 2 gm 4th–6th hourly.

CLAVULANIC ACID

It is a beta lactamase inhibitor used against beta lactamase producing bacteria.
It is used along with amoxycillin/ticarcillin/ampicillin.

SULBACTUM

It is a beta lactamase inhibitor.
It is combined with ampicillin.

TAZOBACTUM

It is a beta lactamase inhibitor combined with piperacillin.

CARBAPENEM/IMIPENEM/MEROPENEM

These are bactericidal beta lactam antibiotic.
They are used in septicaemia, *Pseudomonas, Klebsiella* and *Proteus* infections.

> *He is the best physician who knows the worthlessness of many medicines.*—Benjamin Frunklin

LINCOMYCIN/CLINDAMYCIN

They act on bacterial ribosomal RNA.
Side effect: Pseudomembranous colitis.
Dose: 500 mg tds.

VANCOMYCIN/TEICOPLANIN

It inhibits cell wall synthesis.
Side effects: Nephritis, ototoxicity.
Used in pseudomembranous colitis.
Dose: 500 mg 6th hourly IV.

CEPHALOSPORINS

They are bactericidal. They inhibit bacterial cell wall synthesis.
Useful in most of the bacterial infections.
Side effects: Anaphylaxis, Hepatotoxicity, Nephrotoxicity.

Ist Generation	*IInd Generation*
Cephalexin 500 mg TDS oral.	Cefuroxime 500 mg BD oral.
Cephadroxyl 500 mg BD oral.	Cefaclor 500 mg 8th hourly.
Cephadrine 250 mg QID oral.	Cefamandone 2 gm 6th hourly.
Cephazolin 1 g BD IV.	Cefoxitin 2 gm 8th hourly.
Cephalothin 2 gm 6th hourly.	Cefonicid 2 gm 6th hourly.
Cepharin 2 gm 6th hourly.	Ceforanide 2 gm 12th hourly.
IIIrd Generation	*IVth Generation*
Cefetoxime 1 gm 6th or 8th hourly.	Cefepime 200 mg BD orally.
Ceftriaxone 1 gm 12th hourly.	Cefpodoxime 200 mg BD orally.
Ceftizoxime 2 gm 8th hourly.	
Ceftazidime 2 gm 8th hourly.	
Cefaperazone 2 gm 12th hourly.	
Cefixime 200 mg BD orally.	

MACROLIDES

They act by inhibiting protein synthesis and also by blocking ribosomal activity.
Side effects: Allergic reactions, gastric irritation, cholestasis.
Uses: Respiratory infections, skin infections.

Drugs:
Erythromycin: 500 mg QID.
Roxithromycin: 150 mg BD.
Azhithromycin 500 mg OD before food for 3 days.
Clarithromycin 500 mg BD. It is also used as anti-*Helicobacter pylori* in treating duodenal ulcer.
Spiramycin 1-5 millions BD.

AMINOGLYCOSIDES

They block the RNA-ribosome combination and also inhibits the enzymes involved in Krebs' cycle.
Side effects: Ototoxicity (vestibular), nephrotoxicity.

Aminoglycoside will not get absorbed through the GIT because of high pH. So they are given either IM or IV. As bowel antiseptic they can be given orally.

Drugs:

1. Streptomycin: 0.75 gm IM OD for 3 months. Used in tuberculosis, plague, chancroid, granuloma inguinale, brucellosis, respiratory infections, gut sterilisation during large bowel preparation.

2. Kanamycin: 1.5 gm/day. It is more cochlear toxic.
3. Gentamicin: 80 mg BD IM or IV. 1 mg/kg body weight. Antipseudomonal drug.
4. Tobramycin 5 mg/kg body weight. More effective against *Pseudomonas* than gentamicin.
5. Amikacin 250 mg BD IM/IV. 15 mg/kg body weight.
6. Netilmycin: 3-6 mg/kg body weight.
7. Neomycin 1 gm 6th hourly. Mainly used in hepatic failure and in gut sterilisation.
8. Framycetin as 0.5% ointment.
9. Paromomycin: 2 gm QID. Used in amoebic dysentery.

TETRACYCLINES

They are bacteriostatic.

They act by inhibiting enzyme system, protein synthesis and ribosomal activity.

Side effects: Hepatic dysfunction, gastric irritation, permanent yellow staining of teeth, suppresses the bone growth.

Uses: Plague, cholera, sexually transmitted diseases like syphilis, gonorrhoea, chancroid, actinomycosis.

It is also used to identify malignant cells as brilliant yellow fluorescence under UV light after giving tetracycline for 5 days.

Dose: 500 mg QID.

Doxycycline: 100 mg OD/BD for 10-14 days.

CHLORAMPHENICOL / THIAMPHENICOL

It interferes with protein synthesis.

Side effects: Bone marrow suppression, Grey-baby syndrome, liver damage.

Uses: Typhoid fever, meningitis, plague.

Dose: 2 gm/day.

DRUGS FOR TUBERCULOSIS

RIFAMPICIN:

It inhibits DNA-dependent RNA polymerase. It is bactericidal.

Side effects: Hepatotoxicity, orange-red coloured urine, flu like syndrome.

Uses: Tuberculosis.

Other uses: Leprosy, Meningococcal carrier, brucellosis, mycetoma, Q-fever, *Legionella, Chlamydia.*

Dose: 450-600 mg/day (OD) before food.

RIFABUTIN: 150 mg/day.

ISONICOTINIC ACID HYDRAZINE (INH):

It inhibits the synthesis of phospholipid synthesis of cell wall of bacteria. It is bactericidal.

Side effects: **I**ntolerance, **N**euritis, **H**epatitis.

It crosses the blood brain barrier and placenta.

Dose: 300 mg orally OD.

ETHAMBUTOL: It is bacteriostatic.

Side effects: Gastric intolerance, retrobulbar neuritis (green colour vision is defective).

It crosses the blood-brain barrier and concentrates in CSF.

Dose: 25 mg/kg body weight. 800 mg OD after food.

PYRAZINAMIDE: It is bactericidal.

It acts on dormant bacteria, bacteria inside the macrophages and caseating material.

Side effects: Hepatotoxicity, hyperuricaemia, photosensitivity.

Dose: 1.5 gm OD after food or 750 mg BD after food for 2 months.

MORPHAZINAMIDE: 3 gm/day.

STREPTOMYCIN.

CYCLOSERINE: 2 gm daily. It is a reserve drug.

Abilities not used are abilities wasted.

VIOMYCIN: 1 gm twice a week. IM. It is used in multi-drug-resistant tuberculosis.
AMIKACIN/KANAMYCIN.
CAPREOMYCIN.
PAS: Para-amino salicylic acid: It interferes with PABA metabolism of the bacteria.
Side effects: GIT intolerance, hepatotoxicity, blood abnormalities.
ETHIONAMIDE and PROTHIONAMIDE.
CLARITHROMYCIN.
AZHITHROMYCIN.

ANTIAMOEBIC DRUGS

DEHYDROEMETINE:
It acts on the trophozoite. But not on the cyst.
It is used for extra-intestinal amoebiasis.
Side effects: Myocarditis, myalgia.
Dose: 60 mg deep IM OD for 10 days given under monitor.
DIIDOHYDROXYQUINOLINE: 2 gm/day. It is more useful against trophozoites.
IDOCHLOROHYDROXYQUINOLINE: 0.75 gm/day. It is more useful in cyst passers.
CHLOROQUINE: Used for only extra-intestinal amoebiasis.
500 mg BD for 2 days.
250 mg BD up to 3 weeks.
METRONIDAZOLE:
400-800 mg tds for 10 days. Or 500 mg (1 mg/ml) tid IV.
It is used for intestinal and extra-intestinal amoebiasis.
TINIDAZOLE:
300-600 mg tid for 3-5 days.
SECNIDAZOLE:
2 gm single dose after food for intestinal amoebiasis.
2 gm OD for 5 days.
ORNIDAZOLE:
DILOXANIDE FUROATE:
500 mg tid for 10 days.
Used in cyst passers and chronic carriers.
TETRACYCLINES:
2 gm/day for 10 days.
It is used only as an adjuvant drug.

IMPORTANT ANTIHELMINTHICS

PIPERAZINE CITRATE:
Dose: 5 gm single dose. 1 ml = 150 mg.
Used for Ascariasis.
Side effects: Cerebellar ataxia, vertigo, convulsion.
TETRAMISOLE: 150 mg for adult, 50 mg for children. Used in ascariasis and ankylostomiasis.
MEBENDAZOLE: 100 mg BD for 3 days. 600 mg tid for 21 days.
Used in Ascariasis, Ankylostomiasis, Trichuris trichura, hydatid cyst.
ALBENDAZOLE: 400 mg single dose.
PRAZIQUANTEL: 500 mg tid for 15 days.
THIABENDAZOLE: 25 mg/kg for 3 days.
PYRANTEL PALMOATE: 11 mg/kg. 15 ml. (1 ml = 50 mg).
LUCANTHONE 1 gm tid for 3 days. **HYCANTHONE** 4 mg/kg orally for 4 days.
Used in S. haematobium, S. mansoni.
METRIFONATE: 7.5 mg/kg for 3 days.

NIRIDAZOLE: 25 mg/kg. Used in schistosomiasis.
ANTIMONY COMPOUNDS: Given intramuscularly.
Used in S. haematobium and leishmaniasis.
DIETHYL CARBAMAZINE CITRATE (DEC): 100 mg tid for 21 days.
Used in Filariasis, tropical eosinophilia, larva migrans.
LEVAMISOLE: 150 mg OD.
Used in ascariasis, hookworms, strongyloidosis, as immunomodulator in cancer.

ANTICOAGULANTS

HEPARIN: 10,000 units IV and later 5,000 subcutaneously 8th hourly.
Uses: DVT, pulmonary embolism, DVT prophylaxis.
Heparin therapy should be monitored by partial thromboplastin time (PTT).
Side effects: Haemorrhage, alopecia.
Protamine sulphate neutralizes the action of heparin. It is given IV slowly. Dose should not exceed 50 mg.
LOW MOLECULAR WEIGHT HEPARINS:
It has got longer duration of action. Monitoring is not required. Given as once a day regime.
Dalteparin 2500-10, 000 IV- SC/IV.
Enoxaparin: 40 mg SC.
Parnaparin.
Fraxiparin.
WARFARIN SODIUM:
It is an oral anticoagulant. It is monitored using prothrombin time.
Available as 5 mg tablets.
Dose: 10 mg OD.
It causes haemorrhage and drug interactions.

OTHER DRUGS

- **VITAMIN K:** 10 mg OD IM for 3-5 days. It is used in bleeding disorders, Vitamin K deficiencies in children, liver disorders.
- **ERYTHROPOIETIN**: 500 IU/kg thrice a week. It is used in chronic renal failure.
- **BROMOCRIPTINE**: *Dose:* 20 mg/day.
  It is used to suppress lactation, galactorrhoea, hyperprolactinaemia, parkinsonism, acromegaly.
- **CLOMIPHENE CITRATE**: Used in infertility.
  Dose: 50 mg for 5 days from 5th day of menstruation.
- **OCTREOTIDE:** 0.1 mg BD. Used after pancreatic surgeries in haematemesis, gut endocrine tumours.
- **VASOPRESSIN:** 20 IU IV/SC. Used in bleeding oesophageal varices.
  DESMOPRESSIN 4 microgram/day-SC-IV-NASAL SPRY.
  TERLIPRESSIN: 2 mg IV.
- **L-THYROXINE**: 25, 50, 100, 200 microgram tablets.
  Uses: Myxoedema, cretinism for maintenance therapy after total thyroidectomy, as suppressive therapy in papillary carcinoma thyroid (300 µgm) in physiological goitre, in dyshormonogenesis.
- **ANTITHYROID DRUGS:** *Side effects:* Agranulocytosis and alopecia.
  CARBIMAZOLE: 5-20 mg daily exactly 8th hourly.
  METHIMAZOLE: 5-20 mg daily.
  PROPYLTHIOURACIL: 600 mg tid. Used in pregnancy and children.
- **DANAZOL**: It is used in fibrocystic disease of breast, gynaecomastia, mastalgia, infertility, precocious puberty.
  Dose: 800 mg OD.

> *It seems likely that in the next few years a combination of antibiotics with different antibacterial spectra will fernish a "cribrum therapeuticum" from which fewer and fewer infecting bacteria will escape.*
> —Alexander Fleming

- **ANTACIDS**: Aluminium hydroxide, magnesium trisilicate, sodium bicarbonate.
  Dose is variable.
- **CARBENOXOLONE:** 100 mg tid. It is used in peptic ulcer.
  It causes water and sodium retention, hypokalaemia.
- **H_2 RECEPTOR BLOCKERS**: Used in peptic ulcer.
  Cimetidine 1000 mg/day.
  Ranitidine 150 mg BD or 300 mg at bed time. Injection ranitidine 50 mg IV 6th-8th hourly.
  Famotidine: 40 mg OD.
  Roxatidine 75 mg OD.
  Nizatidine.
- **PROTON PUMP INHIBITORS:** Used in peptic ulcer.
  Omeprazole: 20 mg OD/BD 1 hour before food.
  Lanzoprazole: 30 mg OD before food.
  Esomeprazole 40 mg OD.
  Pantoprazole 40 mg OD before food.
- **PIRENZEPINE**: 50 mg BD. Used in peptic ulcer.
- **BISMUTH COLLOIDS**: Used in peptic ulcer. It is also anti-*Helicobacter pylori.*
  It stains the oral mucosa.
- **SUCRALFATE:** Used in peptic ulcer.
  Dose: 1 gm tid.
- **ONDANSETRON**: 8 mg BD. Orally or IV. It is used to prevent vomiting before starting chemotherapy.
- **LAXATIVES:**
  Castor oil: 16 ml HS.
  Phenolphthalein 300 mg HS.
  Bisacodyl 5 mg orally. HS or 100 mg as rectal suppositories.
  Isabgol as bulk laxative. 15 mg HS.
  Liquid paraffin: 30 ml HS.

- **ANTIDIARRHOEAL:**
  Bismuth kaolin.
  Diphenoxylate, atropine.
  Loperamide 2-4 mg 8th hourly or as required up to maximum of 16 mg/day dose.
- **PROKINETIC DRUGS:**
  Metoclopramide: Used in vomiting, dyspepsia, hiccough. It causes extra-pyramidal reactions.
  Domperidone: *Dose:* 10 mg tid before food. It does not cause extra-pyramidal reaction as it does not cross the blood-brain barrier.
  Cisapride: 10-40 mg/day before food. It can cause cardiac arrhythmias.
  Mosapride.
- **POTASSIUM:** It should be given only in IV drip slowly. IV *Bolus should not be given*. 2 mEq/ml.
  Dose: 20-40 m equivalents. IV should be given under ECG monitoring.
- **SODIUM BICARBONATE**: 7.5% w/v in correction of acidosis.

Appendix

Important Laboratory Values

URINE

Specific gravity:
Normal: 1.010 to 1.025. Low: less than 1.010. High: more than 1.025.
Fixed: 1.010 to 1.014.
Reaction: Acidic with a pH of 6.0.
Colour: Clear and amber coloured.

Parameter	Values
Aldosterone	2-10 µg/day
Nitrogen	0.4-1.0 gm/day
Amylase	30-250 Somogyi units/hour
Calcium	< 3.8 mmol/day
Catecholamines	< 100 U/day
Copper	< 25 µg/day
Creatinine	1.0-1.6 gm/day
Creatinine clearance	140-150 ml/min in males 105-130 ml/min in females
Estrogens	4-25 µg/day in males 5-100 µg/day in females. Very high in pregnancy
17-hydroxy corticosteroids	2-10 mg/day
5-HIAA	2-9 mg/day
17-ketosteroids	7-25 mg/day in men 4-15 mg/day in women
Magnesium	6.0-8.5 mEq/24 hours
Metanephrines	1.3 mg/day
Urine osmolarity	38-1400 mOsm/kg water
Phosphorus	0.9-1.3/day
Porphyrins	
Coprophyrin	50-250 µg/day
Uroporphyrin	10-30 µg/day
Potassium	25-100 mmol/day
Protein	< 150 mg/day
Sodium	100-250 mEq/day

Humor is hazardous to your illness; but not for you.

Urobilinogen	1-3.5 mg/day
VMA	< 8 mg/day
BLOOD:	
Acetoacetic acid	< 0.3 mmol/litre
Acid phosphatase	1.0-5.0 King-Armstrong units
Alkaline phosphatase	20-90 IU/litre
Amino nitrogen	3.5-5.5 mg/dl
Amylase	60-180 Somogyi units
Ascorbic acid	0.4-1.0 mg/dl
Bicarbonate	23-29 mmol/litre
Bilirubin	Total 0.3-1.0 mg/dl. Direct 0.1-0.3 mg/dl Indirect 0.2-0.7 mg/dl
Calcium	9-11 mg/dl
Ionised	4.5-5.6 mg/dl
CO_2 in plasma	20–30 mmol/L. (50-70 volume %)
CO_2 tension in artery	35-45 mmHg
Ceruloplasmin	27-37 mg/dl
Chlorides	98-106 mmol/L
Cholesterol—total	150-250 mg%
Copper	115 + or –15 µg/dl
Cortisol	5-20 µg/dl
Creatine phosphokinase (CPK).	25-90 units/ml in males. 10 m-70 units/ml in females
Creatinine	< 1.5 mg/dl
Free fatty acids	0.7 mmol/litre
Gastrin	40-200 mg/dl
Glucose	70-110 mg/dl
17-OH corticosteroids	2-10 mg/day
IgG	800-1500 mg/dl
IgM	40-150 mg/dl
IgA	90-320 mg/dl
Insulin	6-26 µU/ml
17-keto steroids	7-25 mg/day in males. 4-15 mg/day in females
Lipase	1.5 units
Magnesium	0.8-1.3 mmol/litre
5′ nucleotidase	0.3-2.6 Bodansky units/dl
Osmolality	280-300 mOsm/kg of water
Oxygen.	17-21 volume % in arterial blood 10-16 volume % in venous blood
Oxygen saturation	97% in arterial blood. 60-85% in venous blood
pH of blood	7.36-7.44
Phosphorus, inorganic	1-1.4 mmol/litre
Potassium	3.5-5.0 mmol/litre
Protein—total.	5.5-8.0 gm/dl
Albumin	3.5-5.5 gm/dl
Globulin	2.0-3.5 gm/dl
Sodium	136-145 mmol/litre
Sulphate inorganic	0.8-1.2 mg/litre
Testosterone	< 100 ng/dl in females. 300–1000 ng/dl in males
TSH	0-5 IU/ml plasma
Thyroxine (T4)	5-12 µg/dl
Triiodo thyronine (T3)	80-200 ng/dl

SGOT/AST	6-18 units/litre
SGPT/ALT	3-26 units/litre
Uric acid	2.5-8.0 mg/dl in males
	1.5-6.9 mg/dl in females
Urea nitrogen (BUN)	10-20 mg/dl

RBC count	4.6-6.2 millions/mm^3 in males
	4.2-5.4 millions/mm^3 in females
	4.5-5.1 millions/mm^3 in children
Reticulocyte count	25,000-75,000/mm^3
WBC count	4,300-10,000/mm^3
Platelet count	1,50,000-4,40,000/cu mm
Bleeding time	1-4 minutes
Haematocrit	40-54 ml/100 ml
Clotting time	2-15 minutes
Clot retraction time	Apparent in 60 minutes, complete in 24 hours
	Usually < 6 hours
Plasma fibrinogen	160-400 mg/dl
Partial thromboplastin time	68-82 seconds
	Activated is 32-46 seconds
Prothrombin time	11-15 seconds
Haemoglobin	14-18 gm/dl males
	12-16 gm/dl females
	11-16 gm/dl children
	16-19 mg/dl newborn
Fetal haemoglobin	< 2%
HaemoglobinA2	1.5-3.5%
Osmotic fragility	Begins in 0.45-0.39% NaCl and completes in 0.33-0.30%
Sedimentation rate (ESR)	< 10 mm in one hour in males
	< 20 mm in one hour in females

STOOL EXAMINATION:

Bulk	100-200 gm
Water	75%
Osmolarity	250 mOsm/L
Colour	Brown
pH	7.0-7.5
Fat	< 7 gm/day
Stercobilinogen	50-280 mg/day
Urobilinogen	30-200 mg/100 gm
Nitrogen	< 2.5 gm/day
Calcium	0.6 gm/24 hours
Trypsin	20-90 units/gram

There are two things that unite people, either fear or interest.

Further Reading

- Sabiston Text Book of Surgery.
- Oxford Textbook of Surgery.
- Short Practice of Surgery—Bailey and Love.
- Essential Surgical Practice—Cuschieri.
- Demonstration of Physical Signs in Clinical Surgery—Hamilton Bailey.
- A Little Book of Doctors' Rules—Clafton.
- Clinical Methods in Surgery—Das.
- Rob and Smith Operative Procedures.
- Synopsis of Surgical Anatomy—Lee McGregor.
- Abdominal Operations—Maingot.
- Textbook of Operative Surgery—Farquharson.
- Basic and Clinical Pharmacology—Bertram G Katzung.

Life ends always as "Incomplete".

Index

A

Abdomen quadrants 655
Abdominal cocoon 518
Abdominal dehiscence 670
Abdominal fluid 556
Abdominal incisions 1130
Abdominal tonsil 874
Abdominal trauma 123
Abdominal wall abscess 675
Abdominal wall tumours 672
Abdominal wall, Meleney's bacterial gangrene 676
Abdomino-perineal resection 894, 895
Aberrant renal artery 949, 951
Abrasion 2
Abscess 33
Abscess drainage, Hilton's method 36
Abscess, alveolar 319
Abscess, anorectal 913
Abscess, appendicular 663
Abscess, breast 461
Abscess, cold 37, 391, 393
Abscess, collar stud 133, 392
Abscess, dental 319
Abscess, extradural 1047
Abscess, intracerebral 1047
Abscess, intracranial 1047
Abscess, ischiorectal 914
Abscess, lung 1067
Abscess, metastatic 42
Abscess, parapharyngeal 386
Abscess, parotid 362
Abscess, pelvic 506
Abscess, pelvirectal 915
Abscess, perianal 914
Abscess, perinephric 954
Abscess, psoas 651, 663
Abscess, pyaemic 42
Abscess, pyogenic 33
Abscess, retropharyngeal 386
Abscess, splenic 610
Abscess, subdural 1047
Abscess, submucous 915
Abscess, subphrenic 507
Acanthosis 323
Achalasia cardia 728
Achalasia cardia, Negus hydrostatic dilatation 730
Acid phosphatase 986
Acid-base balance 84
Acidosis, metabolic 84
Acidosis, respiratory 85
Acriflavene 1116
Acrocyanosis 172
Actinomyces israelii 537
Actinomycosis 49
Acute pyomyositis 59
Acute suppurative tenosynovitis 135
Adamantinoma 317
Adelaid coma scale 1039
Adenoma colon 831
Adenoma colon grading 832
Adhesiolysis, laparoscopic 871
Adhesions and bands 869
Adhesions, Child's-Phillips plication 871
Adhesions, Noble's plication 871
Adiposis dolorosa 61
Admiron's triangular hypothesis 572
Adrenal gland secondaries 449
Adrenal incidentalomas 448
Adrenal mass 661
Adrenocortical carcinoma 448
Adrenocortical carcinoma, McFalane staging 448
Adrenocortical tumours, 448
Aggressive fibromatosis 71, 672
AIDS 54
Ainhum 176
Alfa-feto protein 526
Alkalosis, metabolic 84
Alkalosis, respiratory 84
Allograft 279
Ambulatory venous pressure 197
Ameloblastoma 317
Amoebiasis cutis 529
Amoebic colitis, complications 830
Amoebic typhlitis 830
Amoeboma 663, 830
Amputation of penis, partial 1011
Amputation of penis, total 1011
Amputation stump, conical bearing 272
Amputation, 'Peg-leg' 275
Amputation, above knee 174, 275
Amputation, below-knee 174, 274
Amputation, Buerger's 174, 274
Amputation, Chopart's 273
Amputation, forequarter 276
Amputation, Gritti-Stokes 275
Amputation, Guillotine 276
Amputation, hindquarter 275
Amputation, ideal stump 271
Amputation, incisions 272
Amputation, interscapulo thoracic 276
Amputation, Krukenberg 276
Amputation, Lisfranc's 273
Amputation, modified Syme's 274
Amputation, Pirogaff's 274
Amputation, prothesis 277
Amputation, RAY 273
Amputation, Syme's 273
Amputation, transmetatarsal (Gillies') 273
Amputations 271
Amputations, types 271
Anaemia, alloimmune hemolytic 605
Anaemia, autoimmune hemolytic 605
Anaemia, Cooley's 606
Anaemia, erythroblastic target cell 606
Anaemia, immune hemolytic 605
Anaemia, mediterranean 606
Anaesthesia, caudal 1105
Anaesthesia, epidural 1105
Anaesthesia, general 1100
Anaesthesia, instruments 1101
Anaesthesia, intravenous regional 1104
Anaesthesia, postoperative care 1103
Anaesthesia, premedication 1102
Anaesthesia, preoperative assessment 1099
Anaesthesia, regional 1103
Anaesthesia, spinal 1104
Anaesthesia, topical 1104
Anaesthetic agents 1100
Anaesthetic, gaseous 1100
Anaesthetic, intravenous 1100
Anaesthetics, volatile 1100
Anal canal, anatomy 889
Anal canal, malignant tumours 919

Anal canal, malignant tumours, AJCC staging 920
Anal canal, sphincters 889
Anal carcinoma, NIGRO regime 920
Anal dilatation 909
Anal fissure, acute 911
Anal fissure, chronic 911
Anal incontinence 922
Anal intraepithelial neoplasia (AIN) 919
Anal margin tumours 921
Anaplasia 233
Anarchism 1027
Anchovy sauce 528, 529
Aneurysm 37
Aneurysm, Berry 1048
Aneurysm, carotid artery 170
Aneurysm, cirsoid 182
Aneurysm, dissecting 171
Aneurysm, intracranial 1048
Aneurysm, mycotic 167, 1048
Aneurysm, popliteal 170
Aneurysm, ruptured aortic 169
Aneurysm, splenic artery 609
Aneurysms 166
Aneurysms, abdominal 168
Aneurysms, endoluminal stent 169
Angelchik prosthesis 724
Angiodysplasia, colon 842
Angiogram, coronary 1082
Angiogram, renal 932
Angiogram, transbrachial 154
Angiography 150
Angiography, digital substraction DSA 150
Angiography, indication 150
Angiography, retrograde transfemoral Seldinger 150, 154
Angiomyoneuroma 70
Angioplasty, balloon 177
Angioplasty, coronary balloon 1089
Angioplasty, percutaneous transluminal balloon 157
Angioscope 159, 177
Anion gap 85
Anorectal malformation 901
Anorectal myectomy 820
Anorectal strictures 919
Anterior resection 896
Anthrax 53
Anti tetanus globulin 44
Anti tetanus serum 44
Antibioma 35, 463
Anticoagulants 206
Anticoagulants, *in vitro* 208
Anticoagulants, oral 207
Anti-Helicobacter regime 760
Antimalignancy drugs 1094
Antiplatelet drugs 208
Antirabies vaccines, indication 51
Antisepsis 1114
Antithyroid drugs 422
Aortic aneurysm 660
Ape thumb deformity 227
Appendicectomy 879, 1133
Appendicectomy, complications 880, 1133
Appendicectomy, incidental 881
Appendicectomy, interval 882
Appendicectomy, laparoscopic 885, 1141
Appendicectomy, laparoscopic assisted 886
Appendicectomy, retrograde 870, 1133
Appendicectomy, troubles 881
Appendicitis sequelae 878
Appendicitis, acute non-obstructive 875
Appendicitis, acute obstructive 875
Appendicitis, Alvarado scoring 879
Appendicitis, children 877
Appendicitis, differential diagnosis 877
Appendicitis, elderly 877
Appendicitis, infancy 877
Appendicitis, pregnancy 877
Appendicitis, recurrent 875
Appendicitis, sonographic criterias 878
Appendicitis, subacute 875
Appendicular abscess 875, 883
Appendicular mass 663, 875, 882
Appendix, carcinoid tumour 884
Appendix, cystic neoplasms 884
Appendix, duplication 873
Appendix, mucocele 875, 884
Appendix, neoplasms 884
Appendix, primary adenocarcinoma 885
Appendix, surgical anatomy 873
APUDOMAS 638
Arc of Riolan 817
Arterial diseases 145
Arterial occlusion, acute 162
Arterial occlusion, traumatic 162
Arterial pile 907
Arteries, lower limb 145
Arteries, upper limb 144
Arterio venous fistula, acquired 185
Arterio venous fistula, congenital 183
Artificial blood 104
Ascending urethrogram 933
Ascites 555
Ascites in portal hypertension 556
Ascites, encysted 520
Ascites, loculated 520
Ascitic tap 556, 557
Asepsis 1114
Asepsis, wound scoring 30
Astrocytomas 1049
Astrup formula 85
Atherectomy 157
Athlete's foot 143
Atresia, apple peel 859
Atresia, duodenal 858
Atresia, intestinal [small intestine] 859
Atresia, intestinal, Griesfield modification of Martin's classification 859
Atrophic blanche 194
Autoclave 1114
Autograft 279
Axillary tail of Spence 454
Axonotmesis 224

B

Back wash ileitis 824
Bacteraemia 41
Balanoposthitis 1007
Balloon tamponade 551
Bandage, spica 1144
Bandages 1144
Bandages, cravat 1145
Bandages, roller 1144
Bandages, T' 1144
Bandages, tailed 1144
Bandages, triangular 1145
Bandages, tubular 1144
Bandaging, principles 1145
Barium enema 848
Barium enema, air contrast 849
Barium meal study 748
Barium swallow 383, 721
Barrett's ulcer 727, 728
Barron's banding, haemorrhoids 909
Basal cell papilloma 247
Bascom technique 904
Base ball finger 140
Bassini's repair 701
Bassini's stitch 687, 1133
Bazin's disease 23
Beck's triad 1077
Bednar's tumour 245
Bedsore 19, 176
Beger procedure 628, 629
Beger's lavage 618
Belly cleft 674
Bench surgery 958
Benign prostatic hyperplasia 987
Benign prostatic hyperplasia, drugs in 990
Benign prostatic hyperplasia, surgical management 989
Berry's ligament 404, 435
Bile duct carcinoma 592
Bile duct injuries 597
Bile duct injuries, Strasberg's classification 597

Biliary atresia 569
Biliary colic 574
Biliary fistulas 593
Biliary strictures 589
Biochemotherapy 1096
Biopsy 237
Biopsy, excision 239
Biopsy, frozen section 240
Biopsy, incision 239
Biopsy, trucut 239, 478
Bisgaard method 204
Bite, bee 297
Bite, mammalian 297
Bite, snake 296
Bite, spider 297
Bladder carcinoma, transitional cell 976
Bladder carcinoma, treatment 978
Bladder diverticula 982
Bladder mass 664
Bladder outlet obstruction 990
Bladder systolic, 947, 974, 975
Bladder tumours 976
Bladder tumours, Jewett- Strong-Marshall staging 977
Bladder tumours, TNM staging (AJCC) 977
Bladder, autonomous 981
Bladder, cricket ball 1000
Bladder, extraperitoneal rupture 979
Bladder, intraperitoneal rupture 979
Bladder, motor paralytic 981
Bladder, neurogenic 981
Bladder, reflux neurogenic 981
Bladder, sensory paralytic 981
Bladder, thimble 947, 974, 975
Bladder, uninhibited neurogenic 981
Blair's incision 363
Block dissection, ilioinguinal 1012
Block, Bier's 1104
Block, field 1104
Block, infiltration 1104
Block, nerve 1104
Block, saddle 1105
Blood fractions 103
Blood loss, measurement 101
Blood substitutes 104
Blood transfusion 102
Blood transfusion, autologus 104
Blood transfusion, complication 103
Blood transfusion, donor criteria 102
Blood transfusion, massive 104
Blood vessels, palpation 149
Bloodgood cyst 458
Blumer's shelf 632
Body mass index 86, 89
Boil 38
Bolus obstruction 852
Bonin's Y-V plasty 1000
Borchardt's triad 775
Bottle nose 247
Bowen's disease 248
Boyle's apparatus 1101
Brachytherapy 1093
Brachytherapy, interstitial 1093
Brachytherapy, intracavitory 1093
Brachytherapy, surface 1093
Brain, secondaries 1048
Breast implants 496
Breast reconstruction 493
Breast self examination 475
Breast, anatomy 453
Breast, ANDI 456
Breast, atrophic scirrhous 470
Breast, blood supply 455
Breast, ductal carcinoma 468
Breast, fibrocystic disease 458
Breast, FNAC scoring 478
Breast, inflammatory carcinoma 469, 491
Breast, lactational abscess 461
Breast, lobular carcinoma 468
Breast, lobular carcinoma *in situ* 470
Breast, lymphatic drainage 455
Breast, massive enlargement 496
Breast, medullary carcinoma 469
Breast, nipple discharge 497
Breast, nipple retraction 497
Breast, non-lactational abscess 463
Breast, scirrhous carcinoma 469
Breast, transcoelomic spread 475
Breast, ultrasound 477
Brittle diabetes 628
Bronchoscopy 1062
Bruising and contusion 2
Buerger's angle of vascular insufficiency 148
Buerger's disease 152
Buerger's, exercise 155
Buerger's, position 155
Bunion 73, 143
Burhenne technique 585
Burns 106
Burns, acid 116
Burns, alkali 116
Burns, assessment 107
Burns, chemical 116
Burns, classification 106
Burns, effects 109
Burns, electric 115
Burns, fluid resuscitation 111
Burns, inhalation 116
Burns, local management 111
Burns, management 110
Burns, medico legal aspects 117
Burns, metabolic changes 109
Burns, pathophysiology 108
Burns, topical agents 112
Bursa anserina 73
Bursa bicipito radial 72
Bursa, adventitious 73
Bursa, infrapatellar 72
Bursa, olecranon 72
Bursa, prepatellar 72
Bursa, psoas 72
Bursa, radial 135
Bursa, retrocalcaneum 73
Bursa, semimembranosus 72, 73
Bursa, subacromial 72
Bursa, subhyoid 72
Bursa, tailor's 73
Bursa, ulnar 135
Bursa, weaver's 73
Bursae 71
Bursae, types 72
Bursitis 72
Bursitis, retro achilis 73
Bursitis, subhyoid 387
Burst abdomen 670

C

Café au lait spots 76
Calcinosis cutis 74
Calcitonin 433
Calculus, renal 955
Calculus, staghorn 961
Calculus, uerteric 959
Calculus, urethral 1000
Calculus, vesical 970
Calf musculovenous pump 188
Callosity 140
Calot's triangle 562
Campbell de Morgan spots 186
Cancer, Chimney sweep 248, 249
Cancer, Kang 248, 249
Cancer, Khangri 248, 249
Cancer, management strategy 241
Cancer, tear 252
Cancer-en-cuirasse 472
Cancrum oris 322
Capitonage 537
Capsule endoscopy 815
Carbimazole 422
Carbuncle 39
Carbuncle, renal 39
Carcinoembryonic antigen 839
Carcinogens, chemical 234
Carcinogens, microbial 234
Carcinoid crisis 813
Carcinoid syndrome 813
Carcinoid tumour 812
Carcinoma 232
Carcinoma alveolus 346

Carcinoma breast 467
Carcinoma breast, advanced 490
Carcinoma breast, axillary dissection 490
Carcinoma breast, biological behaviour 472
Carcinoma breast, chemotherapy 486
Carcinoma breast, Columbia classification 477
Carcinoma breast, conservative surgeries 483, 488
Carcinoma breast, ductography 480
Carcinoma breast, early management 487
Carcinoma breast, frozen section biopsy 478
Carcinoma breast, hormone therapy 485, 486
Carcinoma breast, locally advanced 491
Carcinoma breast, lymphatic spread 472
Carcinoma breast, male 493
Carcinoma breast, Manchester staging 476
Carcinoma breast, metastatic 491
Carcinoma breast, metastatic, treatment 491
Carcinoma breast, Oestrogen receptor study 478
Carcinoma breast, pregnancy 493
Carcinoma breast, progesterone receptor study 479
Carcinoma breast, prognostic factors 492
Carcinoma breast, radiotherapy 484
Carcinoma breast, sentinel node biopsy 479
Carcinoma breast, TNM staging 476
Carcinoma breast, triple assessment 480
Carcinoma cheek 325
Carcinoma cheek, advanced 328
Carcinoma cheek, approaches 333
Carcinoma cheek, biological behaviour 326
Carcinoma cheek, Broder's classification 328
Carcinoma cheek, clinical features 326
Carcinoma cheek, reconstruction after surgery 333
Carcinoma cheek, staging 328
Carcinoma cheek, TNM staging 328
Carcinoma cheek, treatment 329
Carcinoma cheek, verrucous 326
Carcinoma colon 834
Carcinoma colon, adjuvant therapy 842
Carcinoma colon, Astler-Coller's staging 837
Carcinoma colon, Duke's histological grading 836
Carcinoma colon, Duke's staging 836
Carcinoma colon, follow up 842
Carcinoma colon, modified Duke's staging 837
Carcinoma colon, radical hemicolectomy 841
Carcinoma colon, second look operation 841
Carcinoma colon, TNM staging 837
Carcinoma colon, treatment 840
Carcinoma floor of the mouth 346
Carcinoma gallbladder 591
Carcinoma gallbladder TNM staging 591
Carcinoma gallbladder, Nevin's staging 591
Carcinoma hard palate 350
Carcinoma *in situ* 233
Carcinoma lip 336
Carcinoma lip, treatment 338
Carcinoma oesophagus 735
Carcinoma of penis, Broder's classification 1011
Carcinoma parathyroid 445
Carcinoma penis 1008
Carcinoma penis, Jackson's staging 1011
Carcinoma penis, radiotherapy 1012
Carcinoma penis, TNM staging 1011
Carcinoma penis, treatment 1012
Carcinoma peritonei 511
Carcinoma prostate 991
Carcinoma prostate, grading, Gleason's 991
Carcinoma prostate, staging 991
Carcinoma prostate, TNM staging 991
Carcinoma rectum 891
Carcinoma rectum, chemoradiation 897
Carcinoma rectum, Duke's staging 892
Carcinoma rectum, modified Duke's staging 892
Carcinoma rectum, radiotherapy 897
Carcinoma rectum, TNM staging 893
Carcinoma stomach 777
Carcinoma stomach, adjuvant therapy 788
Carcinoma stomach, aetiology 779
Carcinoma stomach, barium meal finding 785
Carcinoma stomach, biological behaviour 782
Carcinoma stomach, Borrmann's classification 780
Carcinoma stomach, colloid 784
Carcinoma stomach, Japanese classification 780
Carcinoma stomach, Lauren's classification 779
Carcinoma stomach, lymph node stations 787
Carcinoma stomach, lymphatic spread 782
Carcinoma stomach, Ming's classification 780
Carcinoma stomach, palliative procedures 789
Carcinoma stomach, precursor lesions 778
Carcinoma stomach, sentinel node biopsy 786
Carcinoma stomach, Siewert classification 780
Carcinoma stomach, TNM staging 783
Carcinoma stomach, transperitoneal spread 782
Carcinoma stomach, treatment 787
Carcinoma stomach, WHO histological classification 780
Carcinoma tongue 342
Carcinoma tongue, chemotherapy 345
Carcinoma tongue, Commando operation 345
Carcinoma tongue, posterior one third/base 345
Carcinoma tongue, Price- Hill regimen 345
Carcinoma tongue, radiotherapy 345
Carcinoma tongue, spread 343
Carcinoma tongue, terminal events 345
Carcinoma tongue, treatment 344
Carcinoma, basal cell 252
Carcinoma, basisquamous 253
Carcinoma, branchiogenic 395, 397
Carcinoma, caecum 663
Carcinoma, cuniculatum 250
Carcinoma, Merkel cell 245
Carcinoma, nasopharyngeal 346
Carcinoma, Verrucous 249, 250
Cardiac arrest 98
Cardiac catheterization 1082
Cardiac massage, external 98
Cardiac massage, internal open 99
Cardiac paceing, postoperative management 1090
Cardiac pacemakers 1090
Cardiac patient, preoperative assessment 1082
Cardiac tamponade 1077
Cardiography 1082
Cardiopulmonary bypass 1083
Caries spine 1056
Carotid blow out 400
Carotid body 388
Carotid body tumour, Shamblin's classification 388

Carotid body, syncope 388
Carr's postulates 955
Catchpole regime 869
Catgut, chromic 1127
Catgut, plain 1127
Catheter, Fogarty 163
Catheter, Foley's 936, 1124
Catheter, Malecot's 936, 1124
Catheter, red rubber 937, 1124
Catheterisation, indwelling 935
Catheterisation, intermittent 936
Catheters 935
Causalgia 226
Cautery, bipolar 1129
Cautery, blended 1129
Cautery, coagulation 1129
Cautery, cutting 1129
Cautery, unipolar 1129
CBD strictures 589
CBD strictures, Bismuth's classification 589
Celestin tube 741
Cellcycle 1094
Cellulitis 30
Central venous pressure 96
Cerebral concussion 1038
Cerebral contusion 1038
Cerebral laceration 1038
Cervical rib 379
Cetrimide 1115
Charcot's triad 583
Chassaigne tubercle 147
Cheek, anatomy 325
Chemodectoma 388
Chemotherapy 1094
Chemotherapy, head and neck cancers 401
Chernobyl nuclear disaster 425
Cherubism 319
Child's grading 553
Child's grading, Pugh's modification 553
Chiropady 155
Chlorhexidine 1115
Cholangiocarcinoma 592
Cholangiocarcinoma, perihilar, Bismuth classification 592
Cholangiogram IV 563
Cholangiogram, peroperative 565
Cholangiogram, postoperative T tube 565
Cholangitis, sclerosing 590
Cholecystectomy, laparoscopic 596
Cholecystectomy, open 595
Cholecystitis acute, complications 576
Cholecystitis glandularis proliferans 581
Cholecystitis, acute 576
Cholecystitis, acute acalculous 578, 586
Cholecystitis, chronic 580
Cholecystitis, emphysematous 576
Cholecystitis, salmonella 586
Cholecystitis, xanthogranulomatous 586
Cholecystoses 581
Cholecystostomy 578
Choledochal cyst, Todani classification 568
Choledochal cysts 567
Choledochojejunostomy 629
Choledocholithiasis 582
Choledochotomy 584
Chondrosarcoma 268
Chordee 999, 1007
Chordoma 79
Chronic duodenal ileus 748
Chylocele 1018
Chylothorax 222
Chylous ascites 222
Chyluria 223
Cidex 1116
Circulatory failure 101
Circumcision 1006, 1131
Clamp, Moynihan's occlusion 1121
Clamp, Payr's crushing 1121
Classification, deBakey's 171
Classification, Stanford 171
Claw hand 228
Claw hand, median 229
Claw hand, ulnar 229
Cleft disorder, LAHS classification 301
Cleft disorder, problems 302
Cleft lip 301
Cleft lip, Millard criteria 303
Cleft palate 301, 304
Cleft palate, treatment 305
Cleft surgery, Delaire timing 304
Clergyman's knee 72
Closed loop obstruction 838, 841, 854
Clostridium tetani 42
Clostridium welchii 45
Coarctation of aorta 1084
Coin test 1057
Colitis, ischaemic 829
Colitis, pseudomembranous 829
Colitis, ulcerative 824
Collis' vertical gastroplasty 724
Colloid carcinoma rectum 892
Colon, benign tumours/polyp 830
Colon, diverticular disease 820
Colon, juvenile polyps 831
Colon, metaplastic/hyperplastic polyp 831
Colonic mass 660
Colonic mass, left side 660
Colonoscopy 890
Colostomy 843
Colostomy care 844
Colostomy, closure 844
Colostomy, complications 843
Colostomy, Devine's double barrel 843
Colostomy, permanent 843
Colostomy, temporary 843
Compartment excision 80
Compartment syndrome 7
Compartment syndrome, problems 7
Compound palmar ganglion 135
Condyloma acuminata 919
Congenital heart diseases 1083
Coning 1038, 1042
Contracture, burns 112
Contracture, Dupuytren's 138
Contracture, hour-glass 754, 757
Contracture, treatment 114
Contracture, Volkmann's ischaemic 138
Corn 141
Coronary balloon angioplasty 1089
Countryman's lip 336
Courvoisier's law 586, 632
Craniopharyngiomas 1052
Cresol 1115
Criminal nerve of Grassi 746
Crohn's disease 800
Crurum puellarum frigidum 172
Crush injury 2, 8
Crush syndrome 8
Crush syndrome, treatment 8
Crutch palsy 229
Cryoprecipitate 103
Cryosurgery 1136
Cryosurgery, haemorrhoids 909
Cryptorchidism 1026, 1027
CSF rhinorrhoea 1041
CT Scan 1109
CT scan advantages 1110
CT scan, contrast agents 1109
CT scan, high resolution 1111
CTscan, spiral 1109, 1111
CUSA 559
Cutaneous ureterostomy 844
CVP 96
Cyclosporine 292, 1096
Cylindroma 254
Cyst, acquired 64
Cyst, apoplectic 63
Cyst, branchial 381
Cyst, Chylolymphatic 510
Cyst, classification 64
Cyst, clinical features 64
Cyst, congenital 64
Cyst, dental 318
Cyst, dentigerous 318
Cyst, distention 64
Cyst, effects 64
Cyst, enterogenous 510
Cyst, epidermoid 66

Cyst, epididymis 1022
Cyst, false 63
Cyst, lymph 74
Cyst, mesenteric 662
Cyst, Morrant Baker's 74
Cyst, omental 662
Cyst, parasitic 64
Cyst, periapical 318
Cyst, pseudo mesenteric 522
Cyst, pseudo-pseudopancreatic 623
Cyst, radicular 318
Cyst, retention 64
Cyst, retroperitoneum 662
Cyst, sebaceous 66
Cyst, solitary renal 941
Cyst, thyroglossal 405
Cyst, traumatic 64
Cyst, true 63
Cystectomy, partial 978
Cystectomy, radical 978
Cystic fibrosis 641
Cystic hygroma 384
Cystic lesion, abdomen 662
Cystitis 973
Cystitis, interstitial 974
Cystitis, recurrent 974
Cystocele 678
Cysto-gastrostomy 622
Cystosarcoma phylloides 459
Cystoscopic litholapaxy 973
Cystoscopy 934
Cysts 63
Cysts, lung 1071
Cysts, mesenteric 510
Cysts, splenic 611

D

Danaparoid 207
Darning 690
Day care surgery 1146
DCIS 468
DCIS, Nottingham prognostic index 469
DCIS, Van Nuy's prognostic index 469
Decoy prostate 987
Deep veins 187
Defibrillation 99
Degloving injuries 8
Delphian nodes 404
Demodex folliculorum 66
Denis-Browne procedure 999
Dermal flares 191
Dermal histicytoma 245
Dermatofibroma 245
Dermatofibrosarcoma protuberans 245
Dermoid, external angular 65
Dermoid, implantation 66
Dermoid, internal angular 65
Dermoid, sublingual 322
Dermoid, teratomatous 66
Dermoid, tubulo 66
Dermoids, sequestration 64
Dermoids, sequestration, complication 65
Dermoids, submental 66
Dermoids, types 64
Dettol 1115
Devine's exclusion procedure 789
Dexon 1127
Dextrans 104
Diabetic foot, Meggitt's classification 174
Diagnostic peritoneal lavage (DPL) 124, 602
Dialysis 294
Dialysis, peritoneal 294
Diathermy, types 1129
Dietl's crisis 950, 951
Dieulafoy's disease 770
Dilator, Bake's 1121
Dilator, Lister's urethral 1124
Disease, Basedow's 417
Disease, Caisson's 166
Disease, Caroli's 569
Disease, decompression 166
Disease, Dercum's 61
Disease, Grave's 408, 417
Disease, Hide porter's 53
Disease, Marion's 1000
Disease, Menetrier's 777
Disease, Mondor's 455
Disease, Nonne-Milroy's 210
Disease, Ormond's 647
Disease, Parry-Romberg 186
Disease, Peyronie's 1008
Disease, Pick's 1076
Disease, Plummer's 408
Disease, Reclus 470
Disease, Reiter's 1001
Disease, Schimmelbusch's 458
Disease, Sipple's 447
Disease, von Ricklinghausen 445, 451
Disease, Wool sorter's 53
Diseases, arteries 151
Disinfection 1114
Disinfection, methods 1114
Dislocation, mandible 314
Distal run off 154
Diverticular disease, colon 820
Diverticulitis 821
Diverticulitis, Hinchey's classification 822
Diverticulosis 821
DMSA 933
Doppler 1109
Drain system, classification 1123
Drain, closed siphon 1123
Drain, closed suction 1123
Drain, corrugated rubber 1122
Drain, indications 1123
Drain, sump 1123
Drain, sump suction 1123
Drain, tube 1122
Drain, under water seal 1123
Drain, wick 1123
Drains 1122
Drains, problems 1124
Dressings 1144
Dressings, components 1144
Dressings, dry 1144
Dressings, wet 1144
Dressler's quadrangle 1012
Dry perforation 766
DTPA 933
Duct carcinoma *in situ* 468
Duct ectasia 464
Duct papilloma 466
Duct, Bartholin 358
Duct, Santorini 612
Duct, Stenson's 356
Duct, Wharton's 357
Duct, Wirsung 612
Duodenal atersia, 'Wind sock' deformity 858
Duodenal blow out 770
Duodenal diverticula 777
Duodenal ulcer 757
Duodenal ulcer, bleeding 766
Duodenal ulcer, bleeding, Forrest classification 767
Duodenal ulcer, bleeding, treatment 768
Duodenal ulcer, perforated 762
Duodenal ulcer, surgeries 760
Duodenal ulcer, treatment 759
Duodenoduodenostomy 859
Duodenum, anatomy 747
Duplex scan 147, 196, 1109
Duval procedure 629
Dynamic obstruction 852
Dyskeratosis 323
Dysmergia 1144
Dysphagia 343, 719
Dysphagia lusoria 720
Dysplasia 233

E

EAST 147, 380
ECF excess 82
ECF loss 82
Echinococcus granulosus, life cycle 533
Echocardiography 1082
Echosclerotherapy 198
Ectopia vesicae 970

EGFR and VEGF blockers 842
Electron microscopy 241
Elephant boot 273, 277
Elephantiasis, endemic 212
Elephantiatic neurofibromatosis 77
Embolectomy 163, 164
Emboli, paradoxical 163
Embolisation, therapeutic 166
Embolism 163
Embolism, air 165
Embolism, arterial 163
Embolism, fat 165
Embolism, pulmonary 1070
Embolus, saddle 164
Emphysematous cyst, lung 1071
Emprosthotonus 44
Empyema necessitans 1066, 1067
Empyema thoracis 1065
Empyema thoracis, decortication 1067
Empyema, chronic subdural 1044
Endarterectomy 157
Endoscopic retrograde cholangio-pancreatography (ERCP) 563
Endotracheal tube 1101
Enlarged spleen 660
Enteral feeding 86
Enteritis, regional 800
Enterocele 678, 685
Enteroclysis 815
Enucleation 79
Ependymomas 1049
Epididymitis 1035
Epignathus 79
Epineurorrhaphy 225
Epi-perineurorrhaphy 225
Epispadias 999
Epitaxy 955
Epithelioma 248
Epstein pearls 300
Epulis 315
Epulis, carcinomatous 316
Epulis, congenital 315
Epulis, fibrous 315
Epulis, giant cell 316
Epulis, granulomatous 316
Epulis, myelomatous 316
Epulis, pregnancy 316
ERCP, therapeutic 584
Erysipelas 32
Erysipeloid disease 33
Erythema induratum 23
Erythrocyanosis frigida 23
Erythroplakia 324
Erythropoietin 104
Eschar 112
Escharotomy 112
Eschmann blade 279
Eskimoma 366
Ether 1100
Ethrombosis 188
Ethylene 1127
Ettappan's lavage 503
EUSOL 205, 1115
Eusol bath 1115
Evan's formula 111
Eve's disease 317
Eventration 1077
Exocrine pancreatic disease 645
Exomphalos 673
Exomphalos, major 674
Exomphalos, minor 674
Exophthalmos 419
Exophthalmos, grading 420
Exophthalmos, malignant 419
Exophthalmos, pulsating 421
External piles 911
Extra corporeal shock wave lithotripsy (ESWL) 957
Extrahepatic biliary tree 562

F

Facial nerve 356
Facio maxillary diseases 300
Facio venous plane of Patey 357
Faecal fistula after appendicectomy 883
Familial adenomatous polyp 832
Fasciotomy 7
Fatty hernia of linea Alba 711
Felon 133
Femoral canal, anatomy 702
Femoral hernia 702
Femoral hernia, AK Henry's approach 705
Femoral hernia, hydrocele 703
Femoral hernia, Laugier's 703
Femoral hernia, Lotheissen's repair 705
Femoral hernia, Narath's 703
Femoral hernia, sliding 703
FFP 103
Fibrin cuff theory 192
Fibrinogen 103
Fibrinolysins 190
Fibroadenoma 456, 457
Fibrocystadenosis 458
Fibrolipoma 61
Fibroma 71
Fibroma, classification 71
Fibrosarcoma 267
Fine needle aspiration cytology (FNAC) 239
Fine needle non aspirating cytology (FNNAC) 240
First heart sound 1081
Fish handler's disease 33
Fissure in ano 911
Fistula 25
Fistula in ano 915
Fistula in ano, high level 918
Fistula in ano, low level 916
Fistula in ano, Park's classification 916
Fistula in ano, standard classification 916
Fistula, branchial 382
Fistula, cimino 185, 295
Fistula, duodenal 771
Fistula, ECK 552
Fistula, external 25
Fistula, faecal 846
Fistula, gastrojejunocolic 773
Fistula, internal 25
Fistula, parotid 363
Fistula, rectobulbar 902
Fistula, rectovestibular 902
Fistula, thyroglossal 406
Fistula, tracheo- oesophageal 734
Fistula, types 25
Fistula, umbilical 667, 669
Fistula, urinary 985
Fistula, vesicovaginal 984
Fistulectomy 918
Fistulotomy 918
Flail chest 1063
Flail segment 1063
Flap, cross leg 288
Flap, deltopectoral 286
Flap, Estlander's rotating 338
Flap, Fries modified Bernard 338
Flap, gastrocnemius muscle 287
Flap, Gillies fan 338
Flap, groin 287
Flap, island 285
Flap, Karapandzic 338
Flap, latissimus dorsi muscle/myo-cutaneous 287
Flap, LD 495
Flap, Limberg 288
Flap, local rotation 284
Flap, radial forearm 288
Flap, salutatory 286
Flap, TRAM 495
Flap, transverse rectus abdominis muscle (TRAM flap) 287
Flaps 283
Flatulent dyspepsia 575
Flexar retinaculum 128
Fluid therapy 85
Fluids, colloids 85, 111
Fluids, crystalloid 85, 111
Foaming liver 45
Foley's Y-V plasty 953
Follicular odontome 318

Foot drop 230
Foramen of Langer 454
Forceps, Allis'tissue holding 1118
Forceps, artery 1117
Forceps, Babcock's 1118
Forceps, Cheatle's 1117
Forceps, Desjardin's choledocholithotomy 1121
Forceps, Kocher's 1118
Forceps, Lane's tissue holding 1118
Forceps, Lister's sinus 1121
Forceps, Moran-Baker's appendix holding 1118
Forceps, non-toothed dissecting 1120
Forceps, Rampley's 1117
Forceps, right angle 1118
Forceps, sinus (Lister's) 1121
Forceps, sponge holding 1117
Forceps, toothed dissecting 1120
Fordyce's disease 68
Formaldehyde 1115
Fracture middle third area 307
Fracture nose 306
Fracture, depressed skull 1045
Fracture, Guardsman 312
Fracture, Guerin 307, 308
Fracture, mandible 311
Fracture, pyramidal 308
Fracture, zygomatic bone and arch 309
Fracture, zygomatic complex 309
Fractures, Le Fort 308
Frey's procedure 628, 629
Frog hand 134
Frostbite 20, 176
Frozen chest 1066
Fruchaud's myopectineal orifice 681
Fundoplication Toupet's 724
Fundoplication, laparoscopic 724
Fundoplication, Nissen's 724
Furuncle 38

G

Gaiter's zone 204
Galactocele 460
Galactorrhoea 465
Galactorrhoea, primary 465
Galactorrhoea, secondary 465
Galezia triad 138
Gallbladder, congenital anomalies 565
Gallbladder, diverticulosis 582
Gallbladder, empyema 579
Gallbladder, limey 586
Gallbladder, mucocele 580
Gallbladder, polyp 581
Gallbladder, porcelain 586
Gallbladder, strawberry 581
Gallbladder, surgical anatomy 561
Galliard Thomas incision 457
Gallstone colic 575
Gallstone ileus 593
Gallstone, silent 576
Gallstones 571
Gallstones, dissolution therapy 582
Galveston regime 111
Ganglion 78
Ganglioneuroma 75
Gangrene 147, 172
Gangrene, diabetic 174
Gangrene, dry 147, 172
Gangrene, Fournier's 1015
Gangrene, wet 147, 172
Garrey's stricture 679
Garrod's pads 138
Gas gangrene 45
Gas gangrene, prevention 46
Gas gangrene, treatment 46
Gas gangrene, types 46
Gastrectomy, 794
Gastrectomy, Billroth I 794
Gastrectomy, Billroth II 794, 787
Gastrectomy, lower radical 787
Gastrectomy, total 787
Gastrectomy, upper radical 787
Gastric antral vascular ectasia 770
Gastric cancer, familial 777
Gastric carcinoma 659
Gastric dilatation, acute 775
Gastric function test 747
Gastric lymphoma 790
Gastric lymphoma, primary 790
Gastric lymphoma, secondary 791
Gastric polyp 776
Gastric sarcomas 791
Gastric surgery, complications 770
Gastric tetany 762
Gastric ulcer 754
Gastric ulcer, bleeding 769
Gastric ulcer, perforated 765
Gastric ulcer, types 755
Gastric varices 548
Gastrin 748
Gastrinoma triangle 639
Gastrinomas 639
Gastritis, 753
Gastritis, erosive 753
Gastritis, granulomatous 753
Gastritis, lymphocytic 753
Gastritis, phlegmonous 753
Gastritis, reflux 753
Gastritis, stress 753
Gastritis, Type A 753
Gastritis, Type B 753
Gastrocolic reflux 818
Gastrograffin wash 862
Gastrointestinal stromal tumour (GIST) 791, 812
Gastrojejunostomy 794
Gastro-oesophageal reflux disease (GORD) 722
Gastro-oesophageal reflux disease, endoluminal therapies 724
Gastroschisis 674
Gastroscopy 749
Gastrostomy 88, 793
Gastrostomy, Janeway's 88
Gastrostomy, Kader-Senn 88
Gastrostomy, percutaneous endoscopic 88
Gastrostomy, Stamm temporary 88
Gate control theory 298
Gelatin 104
General anaesthesia, complications 1102
Genetherapy 1097
Germ cell therapy 1097
Giant cell reparative granuloma 317
Gibbus 1057
Glasgow coma scale 1039
Gliomas 1049
Glomangioma 70
Glucagonomas 640
Glutaraldehyde 1115, 1116
Goitre, classification 407
Goitre, collod 409
Goitre, diffuse hyperplastic 409
Goitre, Hokkaido 417
Goitre, multi nodular 409
Goitre, plunging 415
Goitre, retrosternal 415
Goldner method 289
Goodsall's rule 917
Goose's foot 73
Graft 279
Graft contracture 281
Graft rejection 293
Graft, endovascular 177
Graft, full thickness 282
Graft, partial thickness 279
Graft, saphenous vein 158
Graft, skin 279
Graft, split thickness 279
Graft, Thiersch 279
Graft, Wolfe 282
Grafts, arterial 158
Granulation tissue 15
Granulation tissue, exuberant 16
Granulation tissue, healthy 16
Granulation tissue, unhealthy 16
Granuloma pyogenicum 40
Grawitz tumour 964

Gray 1092
Great pox 48
Grynfelt's triangle 714
Gustatory, sweating 373
Guyon's canal 228
Gynaecomastia 466

H

H_2 blockers 757
Haemaccel 104
Haemangioma 179
Haemangioma, acquired lobular capillary 179
Haemangioma, capillary 179
Haemangioma, cavernous 181
Haemangioma, strawberry 179
Haemangiosarcoma 268
Haematemesis, causes 769
Haematemesis, management 770
Haematocele 1021
Haematoma, acute subdural 1043
Haematoma, chronic subdural 1043
Haematoma, extradural 1038, 1041
Haematoma, rectus sheath 675
Haematoma, subarachnoid 1044
Haematoma, subdural 1038, 1043
Haematuria 939
Haematuria, diffuse 939
Haematuria, early 939
Haematuria, endemic 975
Haematuria, false 939
Haematuria, microscopic 939
Haematuria, terminal 939
Haemodialysis 294
Haemorrhage 100
Haemorrhage, acute 100
Haemorrhage, chronic 100
Haemorrhage, classification 100
Haemorrhage, gastrointestinal 924
Haemorrhage, non-surgical 100
Haemorrhage, pathophysiology 101
Haemorrhage, primary 100
Haemorrhage, reactionary 100
Haemorrhage, secondary 100
Haemorrhage, subarachnoid, Fischer grading 1045
Haemorrhage, subarachnoid, Hunt and Hess grading 1045
Haemorrhage, surgical 100
Haemorrhage, treatment 102
Haemorrhagic shock, classification 101
Haemorrhoidectomy 910
Haemorrhoids 905
Haemorrhoids, classification 906
Haemostat 1117
Haemothorax 1065
Haggitt's invasion of malignant polyp (Colon) 836
Haggitt's invasion of malignant polyp (rectum) 892
Hallux valgus 143
Halogens 1115
Hamartoma 179
Hamptom's line 756
Hand infections 129
Hand infections, complications 131
Hand infections, general features 129
Hand infections, management 131
Hand, blood supply 128
Hand, modified Verdan zones 128
Hand, muscles 128
Hand, nerve supply 128
Hand, surgical anatomy 28
Hand-Bag stomach 757
Hard corn 141
Hare lip 301
Hartmann's pouch 561
Hassab operation 552
Heart, anatomy 1081
Heberdon's nodes 140
Helicobacter pylori 751
Hemipelvictomy 276
Hemobilia 594
Heparin 207
Heparin, low molecular weight 207
Hepatectomy, hemi 542
Hepatic adenomas 539
Hepatic encephalopathy 558
Hepatic failure 558
Hepatic resection 559
Hepatoblastoma 539
Hepatocellular carcinoma 539
Hepatoma 539, 656, 657
Hepatoma Okuda staging system 540
Hepatoma, AJCC staging 540
Hepatoma, fibrolamellar varient 540
Hepatoma, Okuda classification 540
Hepatoma, palliative treatment 542
Hepatoma, treatment 542
Hepato-renal syndrome 559
Hereditary elliptocytosis 605
Hereditary nonpolyposis colonic cancer 834
Hereditary spherocytosis 604
Hermen-Taylor regime 765
Hernia 677
Hernia repair, anaesthesia 688
Hernia through foramen Bochdalek 1078
Hernia through foramen of Morgagni 1079
Hernia, aetiology 678
Hernia, classification 679
Hernia, Cloquet's 703
Hernia, diaphragmatic 1077
Hernia, different types 715
Hernia, double 702
Hernia, epigastric 711
Hernia, funicular direct 693
Hernia, giant inguinal 693
Hernia, Hesselbach's 703
Hernia, hiatus 726, 1079
Hernia, hiatus, classification 726
Hernia, incarcerated 697
Hernia, incisional 706
Hernia, infantile 702
Hernia, inflamed 679
Hernia, inguinal 680
Hernia, irreducible 679
Hernia, Littre's 678, 679
Hernia, lumbar 714
Hernia, Maydl's 698
Hernia, mesh repair, laparoscopic repair 694
Hernia, mesh repair, material used 694
Hernia, obstructed 679
Hernia, obturator 713
Hernia, pantaloon 702
Hernia, paraoesophageal 726
Hernia, para-umbilical 710
Hernia, parts 678
Hernia, prevesical 693
Hernia, recurrent 693
Hernia, reducible 679
Hernia, re-recurrent 693
Hernia, Rhomberg 702
Hernia, Richter's 679, 698, 714
Hernia, rolling 726
Hernia, saddle 701
Hernia, sciatic 715
Hernia, Serofini's 703
Hernia, sliding 701
Hernia, Spigelian 712
Hernia, strangulated 679, 697
Hernia, strangulated, infancy 699
Hernia, Teale's 703
Hernia, truss 691
Hernia, umbilical 709
Hernia, ventral 705
Hernia-en-glissade 701
Hernia-en-W 698
Hernias interparietal/interstitial 712
Herniography 680
Hernioplasty 691, 693
Herniorrhaphy, complications 689
Herniorrhaphy, modified Bassini's 687, 1133
Herniotomy 686, 1133
Hesselbach's triangle 691

Hexachlorophane 1115
Hibernoma 61
Hibitane 1115
HIDA scan 564
Hidradenitis suppurativa 38
Hidradenitis suppurativa, anal region 923
Hip disarticulation 275
Hippocrates facies 501,504, 763
Hirschsprung's disease 818
Hitch stitches 1043
HIV, GIT problems 56
HIV, hospital and surgeon 57
HIV, modes of transmission 55
HIV, neurological problems 56
HIV, pulmonary problems 56
HIV, tests 55
HIV, treatment 57
HIV, tumours 56
HIV, universal precautions 57
HO's triangle 346
Hogarth Pringle's manoeuvre 590
Hollister bell cap technique 1006
Honey comb liver 49
Hormone therapy, cancer 1096
Horse antirabies serum 52
Hot-air oven 1114
Hounsfield number 1109
Housemaid's knee 72
Human albumin 4.5% 104
Human rabies immunoglobulin 52
Humby's knife 279
Hunger pain 758
Hunterian chancre 48
Hutchinson's freckle 255
Hutchinson's melanotic freckle 258
Hutchinson's teeth 49
Hutchinson's triad 49
Hybridoma 1097
Hydatid cyst, liver 533
Hydatid cyst, liver, Hassen Gharbi's ultrasound based classification 535
Hydatid cyst, liver, WHO classification 535
Hydatid cyst, lung 1071
Hydatid disease, malignant 537
Hydatid fluid 533
Hydatids thrill 534
Hydrocele 1016
Hydrocele, canal of Nuck 1018
Hydrocele, congenital 1018
Hydrocele, encysted 1018
Hydrocele, filarial 1018
Hydrocele, hernia sac 1018
Hydrocele, infantile 1018
Hydrocele, postherniorrhaphy 1018
Hydrocele, primary vaginal 1016
Hydrocele, secondary 1018
Hydrocele, surgeries 1020
Hydrocele, tapping 1132
Hydrocele, types of surgery 1132
Hydrocele-en-bisac 1018
Hydrocephalus 1045
Hydrogen peroxide 1116
Hydrohepatosis 592, 632, 656
Hydronephrosis 948
Hydrophobia 51
Hydrotherapy 116
Hygroma, chronic subdural 1043
Hyperbaric oxygen 97
Hyperkalaemia 83
Hypermagnaesemia 83
Hypernatraemia 82
Hypernephroma 964
Hyperparathyroidism 444
Hyperparathyroidism crisis 445
Hyperparathyroidism, acute 445
Hyperparathyroidism, primary 445
Hyperparathyroidism, secondary 444
Hyperparathyroidism, tertiary 445
Hypersplenism 610
Hyperthyroidism 417
Hyperthyroidism, signs 418
Hypertrophic scar 10
Hypokalaemia 82
Hypokalaemic alkalosis 83
Hypomagnaesemia 83
Hyponatraemia 82
Hypoparathyroidism 1134
Hypospadias 999
Hypothyroidism 440
Hypovolaemia, types 93

I

Ileal urinary conduit 845
Ileostomy 828, 844
Immunohistochemistry 241
Immunosuppression 1096
Immunosuppression, types 1096
Immunotherapy 1097
Immunotherapy agents 1097
Impetigo 41
In situ hybridisation 241
In situ hybridisation, fluorescence (FISH) 241
Incision, Gridiron's 879, 1133
Incision, Lanz crease 879, 1133
Incision, McBurney 879, 1133
Incision, Rutherford Morrison 879, 1133
Incisional hernia, laparoscopic mesh repair 708
Incisional hernia, large 709
Incisional hernia, mesh repair 708, 709
Index, ankle-brachial pressure 148
Index, pack year 152
Index, smoking 152
Induratio-penis plastica 1008
Infection, apical subungual 132
Infection, deep palmar space 134
Infection, HIV 54
Infection, hospital acquired 53
Infection, nosocomial 53
Infection, opportunistic 53, 54
Infection, terminal pulp space 133
Infection, web space 134
Infusion IVU 931
Ingrowing toe nail 142
Inguinal block dissection, elective 1012
Inguinal block dissection, modified 1012
Inguinal block dissection, therapeutic 1012
Inguinal canal, anatomy 680
Inguinal canal, contents 680
Inguinal canal, defence mechanism 681
Inguinal hernia, Bendavid classification 682
Inguinal hernia, classification 681
Inguinal hernia, direct 691
Inguinal hernia, direct, coverings 692
Inguinal hernia, Gilbert classification 682
Inguinal hernia, indirect 682
Inguinal hernia, indirect, bubonocele 683
Inguinal hernia, indirect, complete 683
Inguinal hernia, indirect, coverings 682
Inguinal hernia, indirect, funicular 683
Inguinal hernia, NYHUS classification 682
Inguinal hernia, precipitating causes 683
Inguinal ligament 680
Inguinal ring, deep 680
Inguinal ring, superficial 680
Injuries, blast 122
Injuries, bullet 122
Injuries, chest 1060
Injuries, hand 136
Injuries, hand, classification 136
Injuries, hand, treatment 137
Injuries, head 1037
Injuries, kidney 944
Injuries, maxillofacial 305
Injuries, neck 121
Injuries, penetrating 123
Injury, axillary nerve 230
Injury, brachial plexus 225
Injury, colon 126
Injury, common peroneal nerve 230
Injury, contre-coup 1038
Injury, coup 1038
Injury, duodenal 124
Injury, facial nerve 375
Injury, liver 126
Injury, long thoracic nerve 231

Injury, medial popliteal nerve 230
Injury, median nerve 227
Injury, pancreatic 125
Injury, radial nerve 229
Injury, renal 126
Injury, reperfusion 166
Injury, small bowel 125
Injury, spinal 120
Injury, splenic 126, 600
Injury, steering wheel 1060
Injury, ulnar nerve 228
Injury, urethral 995
Injury, urinary bladder 126, 979
Insulinomas 638
Intercostal tube drainage 1069
Intermittent claudication 145
Intermittent claudication, Boyd's classi-fication 145
Internal hernias 872
Internist tumour 964
Intervertebral disc prolapse 1054
Intestinal amoebiasis, surgical complications, 830
Intestinal obstruction, adynamic 868
Intestinal obstruction, complications 856
Intestinal obstruction, CT scans 856
Intestinal obstruction, plain X-ray abdomen 855
Intestinal obstruction, treatment 857
Intestinal obstruction, types 851
Intestinal obstruction, ultrasound 856
Intra-abdominal pressure grading (Burch) 126
Intravenous urogram 930
Intrinsic minus deformity 228
Intrinsic plus deformity 228
Intussusception 663, 863
Intussusception, Cope's method 866
Intussusception, retrograde jejuno gastric 795
Intussusceptum 864
Intussuscipiens 864
Inverted ink bottle effect 1018
Iodophors 1115
Ischaemia, features 148
Ischaemia, upper limb 177
Ischaemic colitis, Marston's classification 829
Ischaemic heart disease 1088
Isograft 279
Isotope lymphoscintigraphy 209
Isotope renography 933

J

Jack-knife position 904
Jaffe's tumour 317
Jarich- Herxheimer reaction 49
Jaundice, obstructive 587
Jaundice, surgical 587
Jejunostomy 88
Jejunostomy, needle 88
Jejunostomy, Witzel 88
Johansen 'stepladder' procedure 340

K

Kaposis's sarcoma 269
Kasai porto enterostomy 571
Keetly-Torrek procedure 1029
Keloid 8
Keratoacanthoma 246
Kernohan's notch 1038, 1042
Kessler method 289
Ketamine 1100
Kidney shadow 930
Kidney, anatomy 928
Kidney, approaches 968
Kidney, avascular plane 929
Kidney, capsule 929
Kidney, carbuncle 954
Kidney, cystic disease 940
Kidney, horseshoe 940
Kidney, palpable mass 661
Kidney, polycystic disease 941
Kistner's valvuloplasty 205
Klatskin tumour 587, 592
Kous Netzoff aluminium needle 528
Krukenberg's tumour 235, 782
Kuntz nerve 160

L

Ladd and Gross procedure 1029
Laparoscopic surgery, advanced 1141
Laparoscopic surgery, advantages 1139
Laparoscopic surgery, complications 1140
Laparoscopic surgery, instruments 1139
Laparoscopy, diagnostic 1142
Laparostomy 503
Large bowel, preparation for surgery 848
Large intestine, anatomy 817
Laryngeal cancer, radiotherapy in 354
Laryngeal mask airway 1102
Laryngeal nerve, external 441
Laryngeal nerve, recurrent 441
Laryngeal surgery, conservative 354
Laryngocele 383
Larynx, muscles 442
Lasers in surgery 1136
Latent period of Bandet 601
Leiomyosarcoma 268
Leprosy, surgical complications 48
Leprosy, types 47
Lesgafts' triangle 714
Letrozole 486
Leugart's pouch 719
Leukoplakia 323
Ligament of Cooper 454
Ligation, Hunter's 186
Ligation, quadruple 185
Lignocaine 1103
Limb ischaemia 146
Limb ischaemia, critical 146
Limb ischaemia, Fontaine classification 146
Limey gallbladder 573
Line of demarcation 147
Linitis plastica 783
Lipodermatosclerosis 192, 194, 204
Lipoedema 212
Lipoma 61
Lipoma arborigens 61
Liposarcoma 63, 266
Lithogenic bile 572, 586
Littoral cell angioma 610
Liver 525
Liver biopsy 527
Liver function tests 526
Liver injury 527
Liver transplantation, orthotopic 542, 555
Liver tumours 538
Liver tumours, benign 538
Liver, actinomycosis 537
Liver, amoebic abscess 528, 656
Liver, focal nodular hyperplasia 539
Liver, functions 526
Liver, haemangioma 538
Liver, honey comb 537
Liver, pyogenic abscess 537
Liver, secondaries 543
Liver, surgical anatomy 525
Lord's anal dilatation 909
Lord's plication 1020
Lower GI bleed 924
Lower oesophageal sphincter 719
Lucid interval 1042
Ludwig's angina 32, 385
Lugol's iodine 423
Lupus vulgaris 22
Lymphangiography 209
Lymphangioma, cavernous 384
Lymphangiosarcoma 269, 484
Lymphatics 209
Lymphatics of head and neck, anatomy 377

Lymphodema, Browse classification 209
Lymphoedema 209
Lymphoedema, Brunner's grading 212
Lymphoedema, complex decongestive therapy 214
Lymphoedema, filarial 211
Lymphoedema, Kinmoth classification 209
Lymphoedema, primary 211
Lymphoedema, secondary 211
Lymphoma, Ann-Arbor staging 218
Lymphoma, Burkitt's 221
Lymphoma, cutaneous T cell 222
Lymphoma, Hodgkin's 217
Lymphoma, malignant of Africa 221
Lymphoma, non-Hodgkin's, Rappaport classification 221
Lymphoma, non-Hodgkin's, working classification 221
Lymphoma, REAL classification 217
Lymphoma, Rye's classification 217
Lymphoma, staging laparotomy 219
Lymphomas 216
Lysol 1115
Lytle's repair 689

M

Mackler's triad 734
Macroglossia 341
Madura foot 50
Magnetic resonance cholangiopancreatography [MRCP] 564, 613
Magnetic resonance imaging 1111
Magpi repair 999
Major Histocompatibility Complex 290
Malakoplakia 981
Malgaigne bulging 692, 697
Malignant histiocytoma 267
Malignant hyperthermia 1103
Malignant neurilemmoma 269
Malignant oedema 45
Malignant pustule 53
Mallampati scoring 1099
Mallet finger 140
Malrotation 860
Mammary dysplasia 458
Mammary fistula of ATKINS 496
Mammography 455
Mandibular resections 333
Maneuver, costoclavicular compression 149
Maneuver, hyperadduction 149
Maneuver, scalene 148
Marsupialisation 322
Mass abdomen, differential diagnosis 653
Mass abdomen, investigations 664
Mass, epigastrium 658
Mass, hypogastrium 664
Mass, left hypochondrium 660
Mass, left iliac fossa 663
Mass, lumbar region 661
Mass, right hypochondrium 655
Mass, right iliac fossa 663
Mass, umbilical region 662
MAST 95
Mastalgia 465
Mastalgia, cyclical 458
Mastectomy, Auchincloss modified radical 483
Mastectomy, extended radical 484
Mastectomy, Halsted radical 483
Mastectomy, simple 480
Mastectomy, skin sparing 484, 488
Mastectomy, subcutaneous 458
Mastectomy, toilet 484
Mastectomy, total 480
Mastitis 461
Mastitis carcinomatosis 469
Mastitis, intramammary 461
Mastitis, periductal 464
Mastitis, retromammary 463
Mastitis, subareolar 461
Maxillary tumours 347
Maxillary tumours, behaviour 348
Maxillary tumours, Lederman's classification 348
Maxillary tumours, Ohngren's classification 348
Maxillary tumours, TNM staging 349
Maxillofacial injuries, classification 305
Maxillofacial injuries, primary care 307
MCR feet wear 174
Mechanical valves 1089
Meckel's diverticulectomy 799
Meckel's diverticulum 668, 798
Meconium ileus 862
Median nerve palsy 227
Mediastinal flutter 1063
Mediastinal tumours 1072
Medusa head 53
Megacolon, acquired 820
Megacolon, congenital 818
Melanoblast 256
Melanocyte 256
Melanoma 256
Melanoma, acral lentiginous 258
Melanoma, AJCC classification 257
Melanoma, amelanotic 258
Melanoma, Breslow's Classification 257
Melanoma, Clark's concept 259
Melanoma, Clark's level 257
Melanoma, clinical types 257
Melanoma, desmoplastic 258
Melanoma, endolymphatic therapy 262
Melanoma, immunotherapy 262
Melanoma, isolated limb perfusion 261
Melanoma, lentigo maligna 258
Melanoma, newer TNM staging 260
Melanoma, nodular 257
Melanoma, occult 259
Melanoma, sentinal lymph node biopsy 260
Melanoma, subungual 258
Melanoma, superficial spreading 257
Melanoma, treatment 260
Melanoma, tumour markers 260
Melanophages 256
Melanophores 256
Melon seed bodies 135
Melphalan 261
MEN syndrome type II 77
Menghini needle 527
Meningiomas 1049
Meningocele 1053
Meningomyelocele 1053
Mesalamine 827
Mesenteric vessel ischaemia 806
Mesh repair, Gilbert 694
Mesh repair, inlay 694
Mesh repair, Lichtenstein tension free 694
Mesh repair, modified Rives preperitoneal 694
Mesh repair, Nyhus pre-peritoneal 694
Mesh repair, onlay 694
Mesh repair, totally extraperitoneal laparoscopic [TEP] 694, 695, 1142
Mesh repair, trans abdominal preperitoneal laparoscopic [TAPP] 694, 695, 1142
Mesher 281
Methimazole 423
Michaelis Gutmann bodies 981
Microdochectomy 467
Micturating cystourethrography 932
Mikulicz disease 365
Military antishock trouser 95
Milker' nodes 136
Miller procedure 216
Mill-wheel murmur 166
Milnes-Walker thoracic oesophageal transaction 552
Miner's elbow 72
Minnesota tube 551
Minute IVU 931
Mitral commissurotomy, open 1088
Mitral volvotomy, closed 1087
Modified Brooke formula 111
MODS 42, 92
MOHS 254
Mole, hairy 254

Mole, nonhairy 255
Molluscum sebaceum 246
Monoclonal antibodies 1097
Mousseau-Barbin tube 741
Moynihan's aphorism 572
Muir and Burclay regime 111
Murphy's triad 876
Murugassu's technique 902
Muscle relaxant, depolarising 1100
Muscle relaxant, nondepolarising 1100
Myasthenia gravis 1074
Mycetoma pedis 50
Myelinic neuroma 75
Myotomy 824
Myotomy, Heller's 824
Myotomy, Ramstedt's 824
Myotomy, Reilly's 823
Myxoedema madness 440
Myxoedema, pretibial 421

N

Naevi 254
Naevolipoma 61
Naevus flammeus 180
Naevus of Ota 255
Naevus spilus 255
Naevus, blue 255
Naevus, compound 255
Naevus, giant 256
Naevus, halo 255
Naevus, intradermal 255
Naevus, Ito 255
Naevus, junctional 255
Naevus, juvenile 255
Naevus, spindle cell 255
Naevus, Spitz 255
Nail, floating 132
Nail, hang 132
Narcotic analgesics 299
Neck dissection, bilateral 399
Neck dissection, extended radical 400
Neck dissection, modified radical 399
Neck dissection, radical 398
Neck dissection, supraomohyoid block 399
Neck dissection, types 398
Neck lymph nodes, memorial Sloan-Kettering cancer centre levels 394
Neck lymph nodes, secondaries 394
Neck lymph nodes, secondaries with occult primary 396, 398
Neck lymph nodes, secondaries, features 395
Necrotising enterocolitis 808
Necrotising fasciitis 57
Needle holder 1120
Needles, atraumatic 1120
Needles, cutting 1120
Needles, round body 1120
Needles, surgical 1120
Needles, traumatic 1120
Negri bodies 51
Neoplasia, aetiological factors 233
Neoplasm 232
Nephrectomy, partial 958
Nephrectomy, radical 967
Nephrectomy, subcapsular 954
Nephrolithotomy 958
Nephropyelolithotomy 958, 962
Nephrostomy 937
Nephrostomy, bilateral 954, 953
Nephrostomy, Cabot's 938, 962
Nephrostomy, percutaneous 938
Nephrostomy, Tresidder's loop 938
Nephroureterectomy 948
Nerve of Latarget 746
Nerve suturing 225
Neurilemmoma 77
Neuroblastoma 75, 449
Neuroblastoma, Hutchinson's type 449
Neuroblastoma, Pepper type 449
Neuroblastoma, *Shimada* histological classification 449
Neurofibroma 75
Neurofibroma, complications 77
Neurofibroma, nodular 75
Neurofibroma, plexiform 75, 77
Neurofibroma, vagus nerve 388
Neurolipoma 61
Neuroma 224
Neuroma, end 75
Neuroma, false 75
Neuroma, lateral 75
Neuroma, true 75
Neuroma, types 74
Neuropraxia 224
Neurotmesis 224
Nitrous oxide 1100
No scalpel vasectomy 1131
Nonchromaffin paraganglioma 388
Nonnarcotic drugs 299
Nonulcer dyspepsia 753
Normal rotation of midgut, errors 861
Normal rotation of midgut, stages 860
Nutrition 86

O

Obesity 89
Obstipation 867
Ochsner-Sherren regimen 883
Octreotide 618
Odontomes 316
Odynophagia 719
Oesophageal carcinoma, endoscopic therapy 741
Oesophageal carcinoma, staging 740
Oesophageal diverticulum 735
Oesophageal endosonography 722
Oesophageal intubation 741
Oesophageal motility disorders 727
Oesophageal perforation 743
Oesophageal varices 548
Oesophageal varices, balloon tamponade 551
Oesophageal varices, endoscopic gluing 551
Oesophageal varices, endoscopic sclerotherapy 550
Oesophageal varices, endoscopic variceal banding 550
Oesophageal varices, pharmacotherapy 550
Oesophagectomy, complications 742
Oesophagectomy, McKeown 740
Oesophagectomy, Orrhinger approach 740
Oesophagectomy, radical 738
Oesophagoscopy 721
Oesophagus, abdominal 717
Oesophagus, anatomy 717
Oesophagus, Barrett's 728
Oesophagus, benign tumours 742
Oesophagus, cervical 717
Oesophagus, corrosive stricture 731
Oesophagus, foreign body 744
Oesophagus, nut cracker 731
Oesophagus, thoracic 717
Oil of evening primrose 458
Omentocele 678, 685
Omentoplasty 155, 161
Omphalitis 667
Omphalocele 673
Onychocryptosis 142
Onychogryphosis 143
Onychomycosis 143
Operation Kuntz' 690
Operation, Anderson-Hyne's 948, 953
Operation, Andrew's 690
Operation, Belsey Mark 4 724
Operation, Bishop-Koop's 862
Operation, Blalock-Taussig 1087
Operation, BOCCA 399
Operation, Boerema 724
Operation, Boerema-Crile 552
Operation, Brunschwig's 897
Operation, Cattell's 708
Operation, Charle's 215, 216
Operation, Child 627
Operation, Commando 345, 400
Operation, Delorme's 900

Operation, Fitzpatric 1008
Operation, Fowler's 143, 229
Operation, Gelhard's 1008
Operation, Goodsall's 899
Operation, Hadfield 464
Operation, Hamilton-Baily 690
Operation, Hamilton-Stewart 949
Operation, Hartley Dunhill 412, 436
Operation, Hartmann's 857, 868, 897
Operation, Hill's 724
Operation, Homan's 215
Operation, Ivor Lewis 740
Operation, Jabouley's 1020, 1132
Operation, Jurasz 622
Operation, Keel 708
Operation, Kondolean's 215
Operation, Ladd's 861
Operation, Lahaut's 901
Operation, Lily's 569
Operation, Lockwood low 704
Operation, Lotheissen's 705
Operation, Macey's 216
Operation, Max-Page 139
Operation, May-Husni 191
Operation, Mayo's 711
Operation, Mc'Evedy-High 704
Operation, McVay 690
Operation, Michaelis Plank 686, 1133
Operation, modified Duhamel 820
Operation, modified Heller's 730
Operation, Newman-Seabrock's 364
Operation, Nielubowicz 215
Operation, Nuttall's 709
Operation, O'Brien's 215
Operation, Ombredanne's 1028
Operation, Palma 190
Operation, Palomo's 1024
Operation, Parington- Rochelle 628
Operation, Patey's 482
Operation, Paul Brand's 229
Operation, Paul-Mickulicz 868
Operation, Puestow's 627
Operation, Ramstedt's 752
Operation, Riordan 229
Operation, Ripstein 901
Operation, Rosoe-Graham 765
Operation, Rovsing 941
Operation, Santulli 862
Operation, Scanlon's 483
Operation, Sir Piersey Gold 1012
Operation, Sistrunk 215, 406
Operation, Smith 623
Operation, Stye Bunnell's 229
Operation, Sugiura-Futagawa 552
Operation, Swenson's 820
Operation, Tanner slide 690
Operation, Tanner's 776
Operation, Taylor's 760
Operation, Thiersch 901
Operation, Thompson's 215
Operation, Trendelenburg 199
Operation, Well's 901
Operation, Wheelhouse's 998
Operation, Young's 1011
Operation, Zadik's 143
Operative surgery 1114
Opisthotonus 44
OPSI 609
Oral carcinoma, prognostic factors 335
Oral cavity, premalignant condition 324
Oral cholecystogram 562
Oral submucosal fibrosis 324
Orbital cellulitis 31
Orchitis 1035
Orf 136
Orphan Annie eye nuclei 426
Orthopantomogram 300
Orthotonus 44
Orthroses 277
Ovarian mass 664
Oxygen 1100
Oxygen therapy 97

P

Pachydermatocele 76
Packed cells 103
Paget's disease of nipple 470
Paget's disease penis 1009
Paget's, recurrent fibroid of 71
Pain 298
PAIR (Puncture – Aspiration – Injection – Reaspiration) 536
Palate, diseases 300
Palatoplasty 305
Palmar aponeurosis 128
Palpable gallbladder 657
Palpable liver, left lobe 658
Panarteritis 152
Pancoast tumours 1074
Pancreas pseudocyst 618, 620, 659
Pancreas pseudocyst, complication 623
Pancreas pseudocyst, D'Egidio classification 621
Pancreas, acinar cell carcinoma 631
Pancreas, anatomy 612
Pancreas, annular 641
Pancreas, cystic lesions 645
Pancreas, ectopic 642
Pancreas, periampullary carcinoma 630
Pancreatectomy, distal 627, 636
Pancreatectomy, Fortner's regional 636
Pancreatectomy, total 628, 636
Pancreatic ascites 643
Pancreatic calculus 642
Pancreatic carcinoma, pain control 638
Pancreatic carcinoma, prognostic factors 638
Pancreatic carcinoma, TNM staging 634
Pancreatic cholera 640
Pancreatic divisum 642
Pancreatic fistula 619, 643
Pancreatic intraepithelial neoplasia (PanIN) 631
Pancreatic necrosis 618, 644
Pancreatic polypeptide tumour 641
Pancreatic pseudoaneurysm 619
Pancreatic resection 627
Pancreatic trauma 644
Pancreatic tumours 630
Pancreatic tumours, acinar cell carcinoma 631
Pancreatic tumours, cystadenocarcinoma 631, 632
Pancreatic tumours, endocrine 638
Pancreatic tumours, endosonography 634
Pancreatic tumours, ERCP sign 634
Pancreatic tumours, exocrine 630
Pancreatic tumours, infiltrating ductal carcinoma 631
Pancreatic, abscess 619, 621, 643
Pancreaticoduodenectomy, Traverso-Longmire pylorus preserving 635
Pancreatitis, 613
Pancreatitis, acute 614
Pancreatitis, acute, APACHI II scoring 620
Pancreatitis, acute, Atlanta classification 615
Pancreatitis, acute, complications 618
Pancreatitis, acute, Glasgow criteria 620
Pancreatitis, acute, Ranson's prognostic criteria 620
Pancreatitis, acute, surgical management 618
Pancreatitis, acute, treatment 616
Pancreatitis, Balthazar CT scoring system 616
Pancreatitis, chronic 624
Pancreatitis, chronic, endosonography 626
Pancreatitis, emphysematous 620
Pancreatitis, fulminant 615
Pancreatitis, Marseille's classification 614
Pancreatitis, Trapnell's classification 614
Pancreatoblastoma 631
Papilloma 70
Papilloma, complications 71
Papilloma, duct 71
Papilloma, fibroepithelial 71
Papilloma, infective 70

Papilloma, true 70
Paraaortic lymph node mass 660
Paradoxical aciduria 762
Paradoxical respiration 1063
Paralysis, Erb-Duchenne 226
Paralysis, Klumpke's 226
Paralytic ileus 868
Paraneoplastic syndromes 236
Paraphimosis 1004
Paratesticular tumours 1035
Parathyroid anatomy 444
Parathyroidectomy 446
Parathyromatosis 445
Parenteral nutrition, home 88
Parenteral nutrition, peripheral 88
Parenteral nutrition, total 88
Parkland regime 111
Paronychia, acute 132
Paronychia, chronic 132
Parotid gland, accessory 356
Parotid gland, anatomy 356
Parotid lymphoma 373
Parotidectomy 373
Parotidectomy, complications 374
Parotidectomy, radical 374
Parotidectomy, superficial 373
Parotidectomy, suprafacial 374
Parotidectomy, total conservative 374
Parotitis, suppurative 362
Passaros triangle 639
Patent ductus arteriosus 1084
Patent urachus 669
Patterson operation 329
PCWP 96
PDS 1127
Peau d' orange 471
Pelvic evisceration 897
Penis, Ram's horn 1008
Peptic ulcer, acute 754
Peptic ulcer, bleeding 766
Peptic ulcer, perforated 762
Percarditis, chronic constrictive 1076
Percutaneous nephrolithotomy (PCNL) 957
Percutaneous transhepatic cholangiography (PTC) 564
Perdomo procedure 537
Perforator veins 188
Pericardial tap 1076
Pericarditis 1076
Pericarditis, acute 1076
Pericystectomy 537
Pericystectomy, laparoscopic 537
Periodicity 755, 758
Peripheral nerve injuries, Seddon's classification 224
Peripheral nerve injuries, Sunderland's classification 225
Peripheral nerves 224
Peritoneum, anatomy 498
Peritoneum, physiology 498
Peritonitis, acute 498
Peritonitis, biliary 505
Peritonitis, Familial periodic 506
Peritonitis, primary 498
Peritonitis, sclerosing 505
Peritonitis, secondary 499
Peritonitis, spontaneous bacterial 504
Peritonitis, tertiary 499
Perniosis 20
Per-rectal examination 889
Peutz-Jegher's polyp 831
Phaeochromocytoma 450
Phaeochromocytoma, malignant 452
Phagedena 323
Phantom hernia 715
Phantom limb 277, 715
Phantom tumour 715
Pharyngeal pouch 382
Phenol 1115
Phimosis 1004
Phlebectomy, ambulatory 203
Phlebectomy, transilluminated 203
Phlebography 197
Phlegmasia alba dolens 189
Phlegmasia caerulea dolens 189
Phosphorylated diethyl stilbestrol 993
Piles 905
Pin index code 1101
PIPIDA scan 564
Plain X-ray (KUB) 930
Plantar fasciitis 141
Plasma 103
Platelets concentrate 103
Plethysmography 197
Plethysmography, air 197
Plethysmography, photo 197
Pleural tap 1062
Pleurosthotonus 44
Plombage 1080
Pneomothorax, tension 1064
Pneumatosis cystoides intestinalis 805
Pneumaturia 821
Pneumobilia 856
Pneumothorax 1064
Podoconiosis 212
Policeman's heel 141
Polvalent snake venom 296
Polymerase chain reaction (PCR) 241
Port wine stain 180
Portal hypertension 545
Portal hypertension, segmental 553
Portal hypertension, sinistral 553
Portal hypertensive gastropathy 555
Portal pyaemia 538, 881
Porta-systemic collateralisation 546
Positron emission tomography 1113
Posterior urethral valve 1000
Postoperative synergestic gangrene 22
Postphlebitic limb 205
Potato nose 247
Pott's puffy tumour 39, 1047
Pott's spine 1056
Pregangrene 146
Presbyo-oesophagus 719
Pressure sore 18, 176
Pressure sore, factors causing 19
Pressure sore, staging 19
Priapism 1007
Pringle manoeuvre 126, 528
Proctalgia fugax 923
Proctitis 922
Proctoscope 890, 1125
Profundaplasty 155,157
Prolene 1127
Propofol 1100
Propranolol 422
Propyl thiouracil 422
Prostate specific antigen 986
Prostate, anatomy 986
Prostate, floating 995, 996
Prostate, specific problems after surgical intervention 989
Prostatectomy, Freyer's suprapubic transvesical 989
Prostatectomy, Millin's retropubic 989
Prostatic abscess 990
Prostatitis 990
Prostatitis, acute 990
Prostatitis, chronic 990
Prosthesis 277
Protamine sulphate 207
Prothrombin complex concentrate 103
Proton pump inhibitors 759
Pruritus ani 923
Psammoma bodies 427, 1049
Pseudoachalasia 731
Pseudoappendicitis 874
Pseudocyst, lung 1071
Pseudoeschar 112
Pseudomyxoma-peritonei 884
Pseudopneumoperitoneum 766
Psoas shadow 930
PTB 277
Pulmonary capillary wedge pressure 96
Pulmonary circulation 1082
Pulmonary complications, post-operative period 1079
Pulseless disease 155

Purpura, idiopathic thrombocytopenic (ITP) 606
Purpura, thrombotic thrombocytopenic (TTP) 608
Pyaemia 42
Pyelolithotomy 958
Pyelolithotomy, anatrophic 958
Pyelolithotomy, coagulum 958
Pyelolithotomy, extended 958
Pylephlebitis 538
Pyloric stenosis, chronic duodenal ulcer 760
Pyloric stenosis, congenital hypertrophic 751
Pyloric stenosis, electrolyte changes 760
Pyloroplasty 792
Pyloroplasty, Finney's 768
Pyloroplasty, Heineke-Mikulicz 792
Pyocele 1022
Pyogenic granuloma 16, 40
Pyonephrosis 953
Pyrosis 722

Q

QUART therapy 483, 488

R

Rabies 51
Rabies, dogs 52
Rabies, Human diploid cell vaccine 52
Rabies, passive immunity 52
Rabies, prophylaxis 51
Rabies, vaccines 51
Radiation 1115
Radiation absorbed dose 1092
Radiation unit 1091
Radiation, physicochemical effects 1091
Radical excision 80
Radioactive iodine 424
Radioiodine therapy 424
Radionuclide imaging 1112
Radioresistant malignancies 1092
Radiosensitive malignancies 1092
Radiotherapy 1091
Radiotherapy, complications 1094
Radiotherapy, concomitant 1093
Radiotherapy, curative 1091
Radiotherapy, induction 1093
Radiotherapy, palliative 1091
Radiotherapy, postoperative 1093
Radiotherapy, preoperative 1093
Radiotherapy, types 1091
Railroad technique 996
Rains factor 101
Ram's horn nail 143
Ram's horn penis 212
Randall's plaque theory 955
Ranula 321
Ranula, plunging 321
Rashkind balloon septostomy 1086
Ray fungus 49
Raynaud's disease 156
Raynaud's phenomenon 155
Raynaud's syndrome 156
Raynaud's syndrome, Coffman criteria 156
Reconstruction 279
Rectal prolapse 898
Rectal prolapse, defecographic grading 900
Rectal prolapse, partial 898
Rectal proplapse, complete 899
Rectosigmoid junction 888
Rectum, anatomy 888
Rectum, supports 889
Recurrent childhood parotitis 362
Recurrent laryngeal nerve palsy 438, 441, 1134
Recurrent laryngeal nerve palsy, bilateral 443
Recurrent laryngeal nerve palsy, unilateral 442
Recycled blood 104
Red-currant jelly stool 864
Reed-Sternberg cells 217
Refeeding syndrome 89
Reflux oesophagitis, Los Angeles classification 727
Reflux oesophagitis, Savey-Miller classification 727
Regurgitation, aortic 1088
Regurgitation, mitral 1088
Renal abscess 954
Renal cavernostomy, Hanley's 948
Renal cell carcinoma 964
Renal cell carcinoma, AJCC staging 965
Renal cell carcinoma, Robson-Flocks and Kadeskey staging 965
Renal cell carcinoma, triad 966
Renal injury, grading 945
Renal pelvis, duplication 942
Renal pharmacoangiogram, 932, 966
Renal stones, conservative management 958
Renal stones, cystine 956
Renal stones, oxalate 956
Renal stones, phosphate 956
Renal stones, prevention of recurrence 961
Renal stones, struvite 956
Renal stones, xanthine 956
Residual urine 980
Rest pain 146
Resting salivary flow 358
Retractor, Czerny's [hernia] 1119
Retractor, Deaver's 1119
Retractor, Doyen's 1119
Retractor, Joll's thyroid 1121
Retractor, Langenbeck's 1119
Retractor, Morris 1119
Retractor, self-retaining 1119
Retractor, single hook 1120
Retractor, Volkmann's 1118
Retrograde pyelography 932
Retrograde Seldinger technique 932
Retromolar trigone 325
Retroperitoneal cyst 662
Retroperitoneal fibrosis 647
Retroperitoneal mass 648
Retroperitoneal radical lymph node dissection (RPLND) 1035
Retroperitoneal space, anatomy 647
Retroperitoneoscopy 1142
Retroperitoneul swellings 648
Retroperitoneul tumours 648, 662
Reversal agents 1100
Reynold's pentad 583
Rhabdomyosarcoma 268
Rhinophyma 247
Ringer's lactate 85
Risus sardonicus 43
Roentgen unit 1092
Rotter's nodes 455,473
Round worm obstruction 805
Roux- en-Y procedure 636
Rupture bladder 979
Rupture, bulbous urethra 996
Rupture, bulbous urethra, treatment 997
Rupture, membranous urethra 995
Rupture, membranous urethra, Maccullum-cola- pinto classification 995
Rupture, membranous urethra, treatment 996
Rutherford Morison's kidney pouch 508

S

SACH 277
Sacrococcygeal teratoma 921
SAG-M blood 103
Saint's triad 572, 726, 820
Salazopyrine 827
Salivary calculus 359
Salivary colic 360
Salivary gland excision, submandibular 361, 362

Salivary gland, sublingual 358
Salivary glands, ectopic 358
Salivary glands, minor 358
Salivary neoplasm 365
Salivary tumour, acinic cell 370
Salivary tumour, adenoid cystic carcinoma 369
Salivary tumour, adenolymphoma 368
Salivary tumour, malignant, general features 370
Salivary tumour, management 370
Salivary tumour, mucoepidermoid 369
Salivary tumour, papillary cystadeno lymphomatosum 368
Salivary tumour, pleomorphic adenoma 366
Salmon patch 179
Sandblom triad 594
Saphena varix 194
Saphenous vein, long 187
Saphenous vein, short 187
Sarcoidosis 223
Sarcoma 232
Sarcomas 263
Sarcomas, features 263
Saturday night palsy 229
Savlon 1115
Scalene triangle 144
Schatzki's rings 733
Schistosoma haematobium 975
Schwannoma 77, 1049
Scissors 1122
Sclerosant therapy, haemorrhoids 909
Sclerosing adenosis 459
Sclerosing angioma 245
Sclerotherapy, foam 198
Sclerotherapy, micro 198
Sclerotherapy, varicose veins 198
Scolicidal agents 536
Scoline 1100
Scoliosis capitis 390
Scoop, Volkmann's 1122
Scrotum, anatomy 1015
Scrum pox 41
Sebaceous horn 68
Seborrhoeic keratosis 247
Seborrhoeic wart 247
Second heart sound 1081
Seminoma testis 1032
Semon's law 442
Sengstaken-Blakemore tube 551
Senile keratosis 248
Sentinel node, Cabana 1011
Sentinel pile 913
SEPS 202
Septal defect, atrial 1085
Septal defect, ventricular 1085
Septicaemia 41
Septicaemia, complications 42
Sequestrum 28
Serocystic disease of Brodie 459
Serum amylase 613
Seton technique 918
Sharma and Jhawer's technique 1020, 1132
Shianoya's criteria 152
Shock 91
Shock index 94
Shock lung 1069
Shock, anaphylactic 91, 94
Shock, cardiogenic 93
Shock, causes 91
Shock, distributive 97
Shock, effects 92
Shock, endotoxic 93
Shock, hypovolaemic 91, 93
Shock, neurogenic 91, 93
Shock, pathophysiology 91
Shock, septic 91, 93
Shock, septic, pathophysiology 93
Shock, septic, stages 93
Shock, septic, treatment 94
Shock, stages 92
Shock, types 93
Shock, vasovagal 93
Shouldice repair 690
Shunt, Denver 557
Shunt, Inokuchi 553
Shunt, Le Veen 557
Shunt, Linton's 552
Shunt, porta-caval 552
Shunt, Warren's 552
Shunts, selective 552
Sialadenitis 359, 360
Sialectasis 362
Sialography 359
Sialorrhoea 358
Sialosis 362
Sick cell syndrome 92, 101
Sickle cell disease 606
Sideropenia 324
Sideropenic dysphagia 324
Sigmoidopexy 868
Sigmoidoscopy 890
Sign 'V' 134
Sign of Dance 865
Sign of vas 1034
Sign, 'C' loop pad 634
Sign, Angell's 1031
Sign, Balance's 601
Sign, battle's 1039
Sign, Berry's 428, 432
Sign, birds beak 868
Sign, Blumberg's 501, 763, 855, 876
Sign, Boas's 577
Sign, Bow 1024
Sign, Branham's 185
Sign, bull's eye 865
Sign, Camellotte 534
Sign, Champagne glass 822
Sign, Chvostek's sign 447
Sign, claw 865
Sign, coffee bean 868
Sign, coiled spring 865
Sign, Coleman's 312
Sign, colon cut off 616
Sign, Cowen's 418
Sign, Cullen's 615
Sign, Cupola 766
Sign, Curtain 366
Sign, Dalrymple's 418
Sign, Deming's 1031
Sign, double duct 634
Sign, Enroth 418
Sign, Fleischner 514
Sign, football 766
Sign, Fox 615
Sign, Froment's 228
Sign, Frostberg's reverse '3', 749
Sign, Gaur's 703
Sign, Giffrod's 418
Sign, Grey Turner's 615
Sign, Guerin 308, 309
Sign, Harvey's 148
Sign, Homan's 189
Sign, Hook 135, 660
Sign, Hoover's 509
Sign, Howship-Romgberg 714
Sign, Hutchinson 258
Sign, inverted umbrella 514
Sign, inverted V 766
Sign, Jellinek's 418
Sign, Joffroy's 418
Sign, Kanavel 135
Sign, Kehr's 601
Sign, Kenway's 547
Sign, Knie's 418
Sign, Kocher's 418
Sign, Loewi's 418
Sign, London's 125
Sign, Lyre 388
Sign, Mallet-Guys 625
Sign, Mathe's 955
Sign, Mercedes Benz 572
Sign, Milian's ear 33
Sign, Moebius 418
Sign, Mose's 189
Sign, Moynihan's 581
Sign, Murphy's 581
Sign, Naffziger 418
Sign, Neuhauser 862
Sign, Neuhof's 189
Sign, Nicoladoni's 185
Sign, Omega (Ω) 868

Sign, Panda 306, 310, 1039
Sign, Pemberton's 416
Sign, Prehns 1031
Sign, pseudokidney 865
Sign, puddle 556
Sign, Racoon's eye 449
Sign, reverse '3' 634
Sign, reverse 'J' 931
Sign, Riglers 766
Sign, Rosenbach's 418
Sign, Rovsing's 876
Sign, rust 1056
Sign, Seagull 572
Sign, silk glove 684
Sign, slip 62
Sign, Steirlien's 514
Sign, stellate 515
Sign, Stellwag's 418
Sign, Stemmer's 212
Sign, sun-setting 1046
Sign, Tanyol 556
Sign, target 865
Sign, Tinel's 225
Sign, triangle 766
Sign, Trousseau's 84, 206, 447, 632
Sign, Vermooten 995
Sign, Von Graefe 418
Sign, Wester mark 1070
Silastic silo 674
Silk 1127
Sinus 25
Sinus forceps 37
Sinus, median mental 27
Sinus, pilonidal 903
Sinus, preauricular 314
SIRS 92, 97
Sister-Joseph nodule 244
Sitz bath 908
Skin adnexal tumours 244
Skin tumours, classification 243, 244
Skin, anatomy 243
Skin, eccrine gland tumours 244
Skin, hair tumours 244
Skin, premalignant conditions 248
Skin, squamous cell carcinoma 248
Small bowel carcinoids 812
Small bowel enema 815
Small bowel enteroscopy 816
Small bowel strictures 806
Small bowel swellings 662
Small bowel tumours 809
Small bowel, benign tumours 810
Small bowel, malignant tumours 811
Small intestine, anatomy 797
Soft corn 141
Soft tissue sarcoma 263
Soft tissue sarcomas, amputation in 266
Soft tissue sarcomas, compartment resection 265
Soft tissue sarcomas, grading 265
Soft tissue sarcomas, GTNM staging 265
Soft tissue sarcomas, incision biopsy 264
Solar keratosis 248
Solitary ulcer syndrome 898
Somatic cell therapy 1097
Somatostatinoma, triad 640
Southampton wound grading system 30
Souttar tube 741
Space, midpalmar 134
Space, thenar 134
Spermatic cord, contents 680
Spermatic cord, coverings 680
Spermatocele 1022
Spina bifida 1053
Spina bifida aperta 1053
Spina bifida occulta 1053
Spina ventosa 140
Spleen, blood supply 599
Spleen, function 599
Spleen, ligaments 599
Spleen, salutary effect 603
Spleen, surgical anatomy 599
Splenectomy 603, 608
Splenectomy, complication 126, 608
Splenectomy, emergency 603
Splenectomy, indications 608
Splenectomy, partial 603
Splenectomy, portal hypertension 553
Splenic organ injury scale 603
Splenic rupture 600
Splenic vein cavernoma 553
Splenomegaly 604
Splenoportography 547
Splenorrhaphy 603
Splenosis 601
Splenunculi 600
Spongioblastoma polare 1049
Spread of malignant tumours 234
Spurious diarrhoea 893
Squamous cell carcinoma, Broder's classification 249
Stafne bone cyst 358
Staghorn calculus 956
Stapler haemorrhoidectomy 910
Staplers in surgery 1137
Stenosis, aortic 1088
Stenosis, mitral 1087
Stenosis, pulmonary 1086
Stephen-Fowler's technique 1028
Sterile pyuria 947
Sterilisation 1114
Stiff lung 1069
Stings and bites 296
Stoma appliances 846
Stoma care 844
Stoma, complications 845
Stoma, types 844
Stomach mass 659
Stomach, anatomy 745
Stomach, blood supply 745
Stomach, leather-bottle 783
Stomach, lymphatic drainage 746
Stomach, nerve supply 746
Stomal obstruction 770
Stomal ulcer, perforated 766
Stoppa's giant prosthesis reinforcement of visceral sac 694
Stork bite 179
Stove in chest 1063
Stricture urethra 997
Stricture urethra, classification 997
Stricture urethra, complications 999
Stricture urethra, intermittent dilatation 998
Stripper, Myer's 199
Stripping, Vein 199
Struma lymphomatosa 434
Student's elbow 72
Stump carcinoma 778
Sub-epithelial benign nodular fibrosis 245
Sublingual salivary gland, anatomy 357
Subphrenic spaces 507
Suprapubic cystolithotomy 973
Suprapubic percutaneous litholapaxy 973
Surapubic cystostomy 938
Surgeries, endovascular 177
Surgical complications, pulmonary tuberculosis 1080
Surgical complications, roundworm 804
Surgical complications, typhoid 803
Surgical emphysema 1071
Surgical infection 30
Surgical wounds, classification 2
Suture knots 1128
Suture materials, absorbable 1127
Suture materials, classification 1127, 1128
Suture materials, memory 1127
Suture materials, nonabsorbable 1127
Suture materials, numbering 1128
Suturing types 1128
Suturing, delayed primary 6
Suturing, primary 6
Suturing, secondary 6
Suxamethonium chloride 1100
Swimmer's itch 975
Sympathectomy, cervical 157, 160
Sympathectomy, cervico-thoracic preganglionic 159
Sympathectomy, chemical 161

Sympathectomy, lumbar 160
Syndactyly 139
Syndrome Cronkite-Canada 834
Syndrome Mendelson's 1102
Syndrome, abdominal compartment (ACS) 127, 709
Syndrome, auroculo-temporal 373
Syndrome, Bannayan-Riley-Ruvalacaba (Ruvalacaba Myhre Smith) 834
Syndrome, Beckwith-Weidman 673
Syndrome, Birt-Hogg-Dube 964
Syndrome, Boerhaave's 733
Syndrome, Brown-Sequard 120
Syndrome, Budd-Chiari 557
Syndrome, carpal tunnel 227
Syndrome, cast 774
Syndrome, central cord 120
Syndrome, Chilaiditi's 764
Syndrome, compartment 163, 172
Syndrome, Cowden (multiple hamartoma – neoplasia syndrome) 467, 834
Syndrome, Cruvielhier-Baumgarten 548
Syndrome, Curtis-Fitz-Hugh 506
Syndrome, dancing eye 449
Syndrome, descending perineal 922
Syndrome, diGeorge's 448
Syndrome, disappearing pulse 148
Syndrome, dumping 772
Syndrome, Eisenmenger's 1084
Syndrome, familial paraganglioma 451
Syndrome, Felty's 608
Syndrome, Frey's 373
Syndrome, Frolich's 1052
Syndrome, Frolin's 1059
Syndrome, Gardner's 672, 833
Syndrome, Heerfordt's 376
Syndrome, Horner's 159, 325, 395, 1075
Syndrome, hungry bone 439
Syndrome, juvenile polyposis 834
Syndrome, Kasabach Merritt 181
Syndrome, Klippel Trenauny Weber 180
Syndrome, Koenig's 513
Syndrome, Leriche's 148, 164
Syndrome, Letessier-Meige's 210
Syndrome, Li-Fraumen's 467
Syndrome, Maffuccis 181
Syndrome, Mallory-Weiss 734
Syndrome, MEA 447
Syndrome, MEN 61, 447
Syndrome, MEN II 432
Syndrome, Mirizzi 574, 575
Syndrome, Munchausen 881
Syndrome, Nurses' 522
Syndrome, Ogilvie's 842, 868
Syndrome, Osler-Rendu-Weber 181
Syndrome, Paget-Schrotter 380
Syndrome, pancoast 1075
Syndrome, Parkes-Weber 180
Syndrome, Paterson-Kelly 325, 731
Syndrome, Pierre-Robin 320
Syndrome, Plummer-vinson 731
Syndrome, Polands 454
Syndrome, post cholecystectomy 597
Syndrome, post-cibal 772
Syndrome, Proteus 181
Syndrome, Reiter's 1001
Syndrome, Sezzary 222
Syndrome, short bowel 814
Syndrome, Sjogren's 364
Syndrome, Stauffer's 966
Syndrome, Stewart-Treve 264, 484
Syndrome, Sturge Weber 181
Syndrome, subclavian steal 162
Syndrome, sump 598
Syndrome, superior mesenteric artery 774
Syndrome, thoracic outlet 144, 378
Syndrome, Tietze's 465
Syndrome, Torre-Muir 244
Syndrome, Treacher-Collins 314
Syndrome, Turcot's 834
Syndrome, Verner-Morrison 640
Syndrome, von-Hippel-Lindau 451
Syndrome, Waltman-Walter 506, 597
Syndrome, Wermer's 447
Syndrome, Wilkie's 748
Syndrome, Zollinger-Ellison 640
Synovial sarcoma, 269
Syphilis 48
Syphilis, congenital 49
Syphilis, early 48
Syphilis, late 48
Syphilis, latent 48
Syphilis, secondary 48
Syphilis, types 48
Systemic circulation 1082

T

T tube 585
Tabes mesenterica 522
Takayasu's arteritis 155
Tamoxifen 485
Tangential excision 111
Tanner's resection 552
Taxis 691, 699
Tea-pot deformity 754, 757
Technetium 99m 1113
Tendon graft 289
Tendon healing 288
Tendon repair 289
Tendon suturing 289
Tendon transfer 289
Tenesmus 893
Teratoma testis 1032
Tessari technique 198
Test, Adson's 148, 380
Test, Allen's 149
Test, auscultopercussion 760
Test, Baid 621
Test, Baldwing's 876
Test, Bernstein 723
Test, Brodie-Trendelenburg 195
Test, Buerger's postural 148
Test, card 228
Test, Carnett's 664
Test, Casoni's 534
Test, Cope's psoas 876
Test, EAST-Elevated Arm Stress 380
Test, Ehrlich's 588
Test, Falconer 149
Test, Fegan's 196
Test, Fouchet's 588
Test, Fragility 605
Test, Fuchsig's 148
Test, Graham-Cole 562
Test, Halsted 149
Test, Hay's 588
Test, Hess 606
Test, Hollander 748
Test, Ian-Arid 196
Test, insulin 748
Test, internal ring occlusion 683
Test, Javid 162
Test, Kocher 440
Test, leg rising 684
Test, Lundh 646
Test, modified Adson's 380
Test, modified Perthes' 195
Test, modified Roos 149, 380
Test, Morrissey's cough impulse 196
Test, Pancreolauryl 626
Test, peak acid output 747
Test, pen 227
Test, pentagastrin 747
Test, Perthes' 195
Test, Phalen's 228
Test, Pratt's 195
Test, ring invagination 684
Test, Schwartz 195
Test, Secretin cholecystokinin 626
Test, Secretin cholecystokinin stimulation 646
Test, Secritin stimulation 639
Test, Starch-iodine 373
Test, tensilan diagnostic 1074
Test, three tourniquets 195
Test, three-fingers 534, 656
Test, Triolin breath 646
Test, Whitaker 952
Test, Zieman's 684

Testicular descent, embryology 1027
Testicular tumours 1031
Testicular tumours, interstitial cell 1033
Testicular tumours, leydig cell 1033
Testicular tumours, sertoli cell 1033
Testicular tumours, staging 1034
Testicular tumours, TNM staging 1034
Testicular tumours, treatment 1034
Testis, anatomy 1026
Testis, ectopic 1029
Testis, ectopic, Lockwood theory 1029
Testis, retractile 1030
Testis, torsion 1030
Testis, undescended 1026
Testis, undescended, complications 1028
Tetanus 42
Tetanus, ascending 43
Tetanus, bulbar 43
Tetanus, cephalic 43
Tetanus, complications 44
Tetanus, descending 43
Tetanus, early 43
Tetanus, late 43
Tetanus, latent 43
Tetanus, neonatorum 43
Tetanus, postoperative 43
Tetanus, postures 44
Tetanus, prophylaxis 45
Tetanus, staging 44
Tetanus, toxoid 44
Tetanus, treatment 44
Tetanus, types 43
Tetany 84, 447
Tetracycline fluorescene test 786
Tetralogy of Fallot 1086
Thal's patch procedure 724
Thalassaemia 606
Theodor Kocher 440
Thiopentone 1100
Thoracic outlet, surgical anatomy 144
Thoracotomy, indication 1061, 1065
Thrombectomy 157
Thrombin inhibitors 208
Thromboangiitis obliterans, TAO 152
Thrombolysis 164
Thrombolytic agents 208
Thrombophlebitis 206
Thrombophlebitis migrans 206
Thrombosis, deep vein 188
Thrombosis, spontaneous 188
Thrombosis, traveller's 188
Thrombus, fixed 190
Thrombus, free 190
Thymomas 1074
Thyrocardiac 424
Thyroid acropachy 421
Thyroid cancer, Degroot's staging 434
Thyroid cancer, TNM staging 431
Thyroid cyst 415
Thyroid function tests 407
Thyroid gland, anatomy 403
Thyroid gland, blood supply 404
Thyroid gland, congenital anomalies 405
Thyroid gland, development 403
Thyroid gland, ectopic 405
Thyroid gland, physiology 404
Thyroid hormone synthesis 404
Thyroid incidentaloma 435
Thyroid neoplasms 425
Thyroid neoplasms, Dunhill
    classification 425
Thyroid ophthalmopathy-Werner'
    abridged classification 420
Thyroid paradox 427
Thyroid steal 436, 1134
Thyroid storm 439
Thyroid, agenesis 407
Thyroid, anaplastic carcinoma 430
Thyroid, dominant nodule 415
Thyroid, dyshormonogenesis 407
Thyroid, follicular carcinoma 428
Thyroid, Hurthle cell carcinoma 430
Thyroid, lateral aberrant 407
Thyroid, lingual 405
Thyroid, malignant lymphoma 434
Thyroid, medullary carcinoma 432
Thyroid, papillary carcinoma 426
Thyroid, papillary carcinoma, AGES
    scoring 427
Thyroid, papillary carcinoma, AMES
    scoring 427
Thyroid, papillary carcinoma,
    Woolner classification 426
Thyroid, pyramidal lobe 404
Thyroid, solitary nodule 412
Thyroid, toxic nodule 422
Thyroidectomy 435
Thyroidectomy, complications 438, 1134
Thyroidectomy, hemi 435, 1134
Thyroidectomy, minimally invasive
    video assisted (MIVAI) 436
Thyroidectomy, near total 435, 1134
Thyroidectomy, partial 435, 1134
Thyroidectomy, subtotal 435, 1134
Thyroidectomy, total 436, 1134
Thyroiditis, De-Quervain's 434
Thyroiditis, Hashimoto's 434
Thyroiditis, Ligneus 434
Thyroiditis, Reidel's 434
Thyroiditis, Woody's 434
Thyrotoxic crisis 439, 1134
Thyrotoxicosis 417
Thyrotoxicosis factitia 417
Thyrotoxicosis, cardiac manifestation,
    Crile's grading 421
Thyrotoxicosis, Jod Basedow 417
Thyrotoxicosis, primary 420
Thyrotoxicosis, secondary 420
Thyrotoxicosis, T3 424
Tillaux's triad 511
Tinea pedis 143
Tongue muscles 341
Tongue, anatomy 340
Tongue, benign tumour 342
Tongue, development and nerve
    supply 341
Tongue, lymphatic drainage 341
Tongue, movements 341
Topical O_2 therapy 98
Torticollis 389
Torus palatinus 300
Total laryngectomy 354
Total laryngectomy, after care 354
Total mesorectal excision 894
Touhy needle 1105
Tourniquet palsy 229
Tourniquets, complications 105
Tourniquets, types 105
Towel clip, Mayo's 1117
Toxic megacolon 824
Toxic thyroid, children 424
Toxic thyroid, pregnancy 424
TPN 88
Tracheostomy tube 1122, 1135
Tracheostomy tube, Fuller's bivalved
    1122, 1135
Tracheostomy tube, Jackson's 1122,
    1135
Tracheostomy, care 1136
Tracheostomy, complications 1136
Tracheostomy, indications 1135
Tracheostomy, technique 1135
Trans-duodenal band of Ladd 861, 871
Transjugular Intrahepatic Porta
    Systemic Shunt (TIPSS) 552
Transplantation, bone marrow 292
Transplantation, liver 292
Transplantation, organ procurement
    290
Transplantation, orthotopic liver 292
Transplantation, pancreatic 293
Transplantation, preoperative
    evaluation 290
Transplantation, renal 291
Transplantation, small bowel 293
Transposition of great vessels 1086
Transrectal ultrasound 894
Transtuzumab (Herceptin) 486
Transurethral resection of prostate
    (TURP) 989
Trauma 118
Trauma, management 118
Trauma, mechanism 120
Traumatic fat necrosis 460

Triad of CDH 1078
Triad, Tillaux 662
Triage 118
Triage algorithm 118
Triage, types 118
Triangle of Doom 695, 1142
Triangle of pain 695
Triangle of Petit 714
Trichobezoar 773
Triple anastomosis 629
Triple endoscopy 397
TRIVEX 202
Trotter's triad 347
Tubb's dilator 1087
Tube, flatus 1126
Tube, infant feeding 1125
Tube, Kehr's T' 1125
Tube, Ryle's 1124
Tuberculosis 46
Tuberculosis abdomen, ascitic fluid 515
Tuberculosis abdomen, complications 515
Tuberculosis abdomen, CT scan 515
Tuberculosis abdomen, plastic type 520
Tuberculosis abdomen, ultrasound features 515
Tuberculosis spine 1056
Tuberculosis, abdomen 512
Tuberculosis, breast 464
Tuberculosis, ileal 518
Tuberculosis, ileocaecal 513, 663
Tuberculosis, peritoneal 518
Tuberculosis, renal 946
Tuberculous dactylitis 140
Tuberculous lymphadenitis 390
Tuberculous mesenteric lymphadenitis 521
Tuberculous, ano-recto-sigmoidal 522
Tuberculous, omentum 523
Tuberculous, role of steroids 523
Tumour markers 240, 241
Tumour suppressor gene p53 234
Tumour, Broder's grading 235
Tumour, Buschke-Lowenstein 1014
Tumour, carotid body 388
Tumour, Cock's peculiar 68
Tumour, desmoid 71, 672
Tumour, dumb-bell 366, 388
Tumour, glomus 70
Tumour, Klatskin 587
Tumour, minor salivary gland 372
Tumour, mixed salivary 366
Tumour, phylliodes 459
Tumour, potato 388
Tumour, Raspberry 668
Tumour, staging 236
Tumour, sternomastoid 390
Tumour, submandibular salivary 370
Tumour, turban 254
Tumour, ubiquitous 61
Tumour, universal 61
Tumour, Warthin's 368
Tumours, chest wall 1075
Tumours, colon 830
Tumours, intracranial 1048
Tumours, jaw 315
Tumours, laryngeal 351
Tumours, laryngeal, glottic 352
Tumours, laryngeal, subglottic 352
Tumours, laryngeal, supraglottic 351
Tumours, maxillary 347
Tumours, odontogenic 316
Tumours, pituitary 1051
Tumours, retroperitoneum 662
Tumours, spinal 1058
Tumours, tonsil 350
Tylosis 735
Typhoid Mary 586, 803

U

Ulcer 12
Ulcer, assessment 17
Ulcer, Bairnsdale 20
Ulcer, base 12
Ulcer, Buruli 20
Ulcer, callous 12
Ulcer, chillblains 20
Ulcer, chronic 18
Ulcer, classification 12
Ulcer, cleaning 17
Ulcer, clinical examination 23
Ulcer, cortisol 15
Ulcer, Curling's 109, 754
Ulcer, Cushing's 754
Ulcer, debridement 17
Ulcer, decubitus 176
Ulcer, definition 12
Ulcer, diabetic 21
Ulcer, diabetic, problems 22
Ulcer, discharge 16
Ulcer, dressing 17, 18
Ulcer, duodenal 757
Ulcer, edge 12
Ulcer, elusive 974
Ulcer, floor 12
Ulcer, frostbite 20
Ulcer, gravitational 204
Ulcer, healing 12
Ulcer, Hunner's 974
Ulcer, induration 12
Ulcer, investigation 17
Ulcer, kissing 758
Ulcer, malignant 13
Ulcer, management 17
Ulcer, margin 12
Ulcer, Marjolin's 11, 113, 249, 250
Ulcer, Martorelle's 20
Ulcer, Meleney's 22
Ulcer, neurogenic 19
Ulcer, neuropathic 19
Ulcer, nonspecific 13
Ulcer, parts 12
Ulcer, penetrating 19
Ulcer, perforating 19
Ulcer, recurrent 771
Ulcer, rodent 252
Ulcer, spreading 12
Ulcer, stercoral 838, 854
Ulcer, stomal 772
Ulcer, syphilitic 13
Ulcer, trophic 18, 175
Ulcer, tropical 15, 23
Ulcer, venous 204
Ulcer, Wagener's grading 15
Ulcerative colitis, surgeries 828
Ulcerative colitis, treatment 827
Ulnar paradox 228, 229
Ultrasound 1107
Umbilical adenoma 667, 668
Umbilical granuloma 667
Umbilical sinus 667, 668
Umbilicus, diseases 666
Unna boots 198, 206
Upper GI bleed 924
Urachal anomalies 970
Urachal cyst 669
Urachal diverticulum 669
Urachal fistula 669
Ureter, anatomy 929
Ureter, golf hole 947, 948
Ureter, retrocaval 943
Ureter, sites of constrictions 929
Ureteric calculus, Dormia basket 960
Ureterocele 943
Ureterocele, Stephen's classification 944
Uretero-sigmoidostomy 979
Ureterostomy, Davis-T-tube 953
Urethra, anatomy 995
Urethritis 1001
Urethroplasty, Johanson's 998
Urethroplasty, problems 998
Urinary bilharziasis 975
Urinary bladder, anatomy 969
Urinary bladder, sphincters 969
Urinary bladder, trigone 969
Urinary diversion 983
Urinary diversion, complication 984
Urine, extravasation 1001
Urine, retention 1002
Urine, retention, management 1002

Urograffin 931
Uterine mass 664

V

VACTER anomalies 734
Vacuum assisted closure 20
Vagotomy, complications 795
Vagotomy, highly selective 746, 795
Vagotomy, parietal selective 795
Vagotomy, selective 746, 795
Vagotomy, super selective 795
Vagotomy, truncal 746, 795
Valve of Geralch 874
Valve replacement surgery 1088
Varicocele 1023
Varicocele, subfertility 1024
Varicography 197
Varicose vein, stripping 199
Varicose vein, subfascial ligation of Cockett and Dodd 201
Varicose veins 191
Varicose veins surgery, problems 204
Varicose veins, complications 204
Varicose veins, compression bandages 206
Varicose veins, compression therapy 205
Varicose veins, endo venous laser ablation 202
Varicose veins, Linton's approach 202
Varicose veins, radiofrequency ablation 202
Vasectomy 1131
Veins of lower limb, anatomy 187
Venography 197
Venous disabilty scoring system 196
Venous diseases 187
Venous diseases, CEAP classification 193
Venous Doppler 196
Verocay bodies 78
VERONESSI QUART therapy 483
Verrucous carcinoma, cheek 326
Vesicostomy 845
Vesicoureteric reflux 932, 982
Vicryl 1127
Video assisted thoracoscopic surgery (VATS) 1080
Vigorous achalasia 729
Vim-silvermann needle 527
Vin rose patch 182
Vipoma 640
Virchow's triad 188
Visor approach for oral malignancy 333
Vitello-intestinal duct, anomalies 667
VNUS closure 202
Volkmann's sign 139
Volvulus 866
Volvulus, compound 866
Volvulus, gastric 775
Volvulus, pelvic colon 866
Volvulus, sigmoid 866
Von Recklinghausen's disease 76
Von-Hippel- Lindau disease 964

W

W' flap plasty 338
Wagner-Grossman hypothesis 442
Waldeyer's lymphatic ring 377
Wallace's rule of nine 106
Waltzing 286
Wangenstein's invertogram 902
Warfarin 208
Water can perineum 1002
Water intoxication 81
Water loss 81
Water shed point 829
Wayne's diagnostic indices 419
Webster's incision 457
Weigert Meyer Law 942
Wen 66
Whipple's procedure 627, 629, 635
Whipple's triad 638
White bile 594
White cell trapping theory 192
Wide excision 80
Wilm's tumour 450, 962
Wilm's tumour, staging 963
Winging of scapula 231
Witch's milk 463, 465
Wolf-Chaikoff effect 417
Wound classifications 3
Wound healing 4
Wound healing, factors affecting 5
Wound healing, phases 5
Wound healing, primary 4
Wound healing, secondary 4
Wound healing, stages 4
Wound healing, types 4
Wound, clean 2
Wound, clean contaminated 2
Wound, contaminated 3
Wound, debridement 6, 7
Wound, dirty infected 3
Wound, excision 7
Wound, radical excision 7
Wound, toilet 7
Wounds 1
Wounds suturing, principle 7
Wounds, clean incised 1
Wounds, closed 3
Wounds, definition 1
Wounds, lacerated 1
Wounds, management 6
Wounds, open 3
Wounds, penetrating 2
Wounds, Rank and Wakefield classification 1
Wounds, tidy 1
Wounds, untidy 1
Wrist drop 230
Wry neck 389

X

Xenograft 279
Xeroderma pigmentosa 248
Xeromammography 456
Xerostomia 358
Xylocaine 1103

Z

Z' plasty 284
Zip technique 503, 618

Latha Ganti
Editor

Atlas of Emergency Medicine Procedures



Springer

Atlas of Emergency Medicine Procedures

Latha Ganti
Editor

Atlas of Emergency Medicine Procedures

Springer

Editor
Latha Ganti
Professor of Emergency Medicine
University of Central Florida
Director, SE Specialty Care Centers of Innovation
Orlando Veterans Affairs Medical Center
Orlando, FL
USA

ISBN 978-1-4939-2506-3 ISBN 978-1-4939-2507-0 (eBook)
DOI 10.1007/978-1-4939-2507-0

Library of Congress Control Number: 2016930028

Springer New York Heidelberg Dordrecht London
© Springer Science+Business Media New York 2016
This work is subject to copyright. All rights are reserved by the Publisher, whether the whole or part of the material is concerned, specifically the rights of translation, reprinting, reuse of illustrations, recitation, broadcasting, reproduction on microfilms or in any other physical way, and transmission or information storage and retrieval, electronic adaptation, computer software, or by similar or dissimilar methodology now known or hereafter developed.
The use of general descriptive names, registered names, trademarks, service marks, etc. in this publication does not imply, even in the absence of a specific statement, that such names are exempt from the relevant protective laws and regulations and therefore free for general use.
The publisher, the authors and the editors are safe to assume that the advice and information in this book are believed to be true and accurate at the date of publication. Neither the publisher nor the authors or the editors give a warranty, express or implied, with respect to the material contained herein or for any errors or omissions that may have been made.

Printed on acid-free paper

Springer Science+Business Media LLC New York is part of Springer Science+Business Media (www.springer.com)

To my father, my role model and career coach –

Dr. Ganti L. Rao

Dad, I wouldn't have had the career I do were it
not for you. Your unconditional belief in me, your confidence in
my success, your never ending patience and generosity – you
lead a life of great achievements with utmost humility.
It is my privilege to be your daughter.

Preface

The *Atlas of Emergency Medicine Procedures* is presented in the spirit of "see one, do one, teach one" and "a picture is worth a thousand words." It can be used at the bedside, both by novice practitioners and seasoned clinicians as a teaching aid. For ease of reference, the most common procedures are grouped by organ systems. Each procedure follows a standardized format, beginning with keywords, a definition if appropriate, indications, and contraindications. These are followed by materials and medications, often accompanied by a photograph of the specific equipment or setup. The procedure itself is numbered rather than bulleted, highlighting the sequence of steps. Photographs are placed where the relevant information is encountered in the text rather than at the end. Every procedure also lists complications. Finally, there is a section on pearls and pitfalls, gleaned from the collective experience of the contributors in addition to traditional teachings.

Emergency medicine, by nature, is a field best suited to a visually appealing, concise text able to deliver the information required. Much effort therefore has been dedicated to images. These are either actual photographs taken of the procedure steps or specially commissioned drawings by Springer's professional illustration team. A work of this magnitude could not have been accomplished without the expertise of my dedicated Springer team. A huge thank you to Shelly Reinhardt, Megan Ruzomberka, and Lee Klein. It is hoped that readers will find this atlas useful and practical. Feedback and suggestions for future editions are welcomed and can be sent to AtlasEMprocedures@gmail.com.

Orlando, FL, USA Latha Ganti

Contents

Part I Vascular Procedures 1

1 Arterial Cannulation (Radial and Femoral) 3
Jeffrey Kile, Katrina John, and Amish Aghera
1.1 Indications 3
1.2 Contraindications 3
1.3 Materials and Medications 3
1.4 Complications 10
1.5 Pearls and Pitfalls 10
Selected Reading 11

2 Ultrasound-Guided Peripheral Intravenous Access 13
Coben Thorn and L. Connor Nickels
2.1 Indications 13
2.2 Contraindications 13
2.3 Materials and Medications 13
2.4 Procedure 14
2.5 Complications 15
2.6 Pearls and Pitfalls 15
Selected Reading 15

3 Central Venous Line Placement: Internal Jugular Vein, Subclavian Vein, and Femoral Vein 17
Kevin D. Ergle, Zachary B. Kramer, Jason Jones, and Rohit Pravin Patel
3.1 Indications 17
3.2 Contraindications 17
3.3 Materials and Medications 17
3.4 Procedures 18
3.5 Complications 25
3.6 Ultrasound Guided Cannulation: Tips for Each Approach 26
3.7 Removing a Central Line 26
Selected Reading 26

4 Pulmonary Artery Catheter 29
Rohit Pravin Patel and Marie-Carmelle Elie
4.1 Indications 29
4.2 Contraindications 29
4.3 Materials 29
4.4 Procedure 30
4.5 Complications 33
4.6 Pearls and Pitfalls 33
Selected Reading 33

5 Noninvasive Cardiac Monitoring: The Edwards Vigileo System . . . 35
Dawood G. Dalaly and Rohit Pravin Patel
5.1 Indications . . . 35
5.2 Contraindications . . . 37
5.3 Definitions and Values . . . 37
5.4 Materials . . . 38
5.5 Procedure . . . 38
5.6 Pearls and Pitfalls . . . 38
Selected Reading . . . 38

6 Peripheral Venous Cutdown . . . 39
Jeffrey Kile, Katrina John, and Amish Aghera
6.1 Indications . . . 39
6.2 Contraindications . . . 39
6.3 Materials and Medications . . . 39
6.4 Choice of Vessel for Cutdown . . . 41
6.5 Procedure . . . 41
6.6 Complications . . . 44
6.7 Pearls and Pitfalls . . . 44
Selected Reading . . . 44

Part II Airway and Vascular Procedures . . . 45

7 Bag-Valve-Mask Ventilation . . . 47
Braden Hexom and Tatiana Havryliuk
7.1 Indications . . . 47
7.2 Contraindications . . . 47
7.3 Materials . . . 47
7.4 Procedure . . . 48
7.5 Complications . . . 50
7.6 Pearls and Pitfalls . . . 50
Selected Reading . . . 51

8 Awake Orotracheal Intubation . . . 53
Benjamin M. Mahon, Justin Bennett, and Lars K. Beattie
8.1 Indications . . . 53
8.2 Contraindications . . . 53
8.3 Materials and Medications . . . 53
8.4 Procedure . . . 53
8.5 Pearls and Pitfalls . . . 56
Selected Reading . . . 56

9 Rapid-Sequence Intubation . . . 57
Ram A. Parekh
9.1 Indications . . . 57
9.2 Contraindications . . . 57
9.3 Materials and Medications . . . 57
9.4 Procedure . . . 60
9.5 Complications . . . 65
9.6 Pearls and Pitfalls . . . 65
Selected Reading . . . 65

10 Direct Laryngoscopy . . . 67
Bharath Chakravarthy and Weston Seipp
10.1 Indications . . . 67
10.2 Contraindications . . . 67

10.3 Materials and Medications . . . 68
10.4 Procedure . . . 69
10.5 Complications . . . 74
10.6 Pearls and Pitfalls . . . 74
References . . . 74

11 Laryngeal Mask Airway . . . 75
Sohan Parekh
11.1 Indications . . . 75
11.2 Contraindications . . . 75
11.3 Types . . . 76
11.4 Materials and Medications . . . 77
11.5 Procedure . . . 77
11.6 Complications . . . 83
11.7 Pearls and Pitfalls . . . 83
Selected Reading . . . 83

12 Combitube . . . 85
Clint Masterson
12.1 Indications . . . 85
12.2 Contraindications . . . 85
12.3 Materials . . . 85
12.4 Procedure . . . 86
12.5 Pearls and Pitfalls . . . 87
Selected Reading . . . 87

13 Assessment of the Difficult Airway . . . 89
Melinda W. Fernandez and Lars K. Beattie
13.1 Indications . . . 89
13.2 Materials and Medications . . . 89
13.3 Procedure . . . 89
13.4 Pearls and Pitfalls . . . 92
References . . . 92
Selected Reading . . . 92

14 GlideScope . . . 93
Sohan Parekh
14.1 Indications . . . 93
14.2 Contraindications . . . 93
14.3 Materials and Medications . . . 93
14.4 Procedure . . . 95
14.5 Complications . . . 96
14.6 Pearls and Pitfalls . . . 96
Selected Reading . . . 97

15 Endotracheal Tube Introducer (Bougie) . . . 99
Joseph Rabinovich
15.1 Indications . . . 99
15.2 Contraindications . . . 99
15.3 Materials and Medications . . . 99
15.4 Procedure . . . 100
15.5 Complications . . . 101
15.6 Pearls and Pitfalls . . . 101
References . . . 101

16 Lighted Stylet Intubation 103
Benjamin M. Mahon and Lars K. Beattie
- 16.1 Indications 103
- 16.2 Contraindications 103
- 16.3 Materials and Medications 103
- 16.4 Procedure 104
- 16.5 Pearls and Pitfalls 107
- References 107
- Selected Reading 107

17 Fiber-Optic Stylet Intubation (Rigid and Semirigid) 109
Joseph Rabinovich
- 17.1 Indications 109
- 17.2 Contraindications 109
- 17.3 Relative Contraindications 109
- 17.4 Materials and Medications 109
- 17.5 Procedure 110
- 17.6 Pearls and Pitfalls 113
- References 113

18 Storz Video Laryngoscope 115
Joseph Rabinovich
- 18.1 Indications 115
- 18.2 Contraindications 115
- 18.3 Materials and Medications 116
- 18.4 Procedure 116
- 18.5 Complications (As with any Direct Laryngoscopy) 118
- 18.6 Pearls and Pitfalls 118
- References 118
- Selected Reading 118

19 Cricothyroidotomy 119
Henry Young II, Shannon Toohey, Bharath Chakravarthy, and Lars K. Beattie
- 19.1 Indications 119
- 19.2 Contraindications 119
- 19.3 Techniques 119
- 19.4 Complications 126
- 19.5 Pearls 126
- References 126
- Selected Reading 126

20 Tracheostomy Tube Malfunction 127
Deena Bengiamin and Bharath Chakravarthy
- 20.1 Indications 127
- 20.2 Materials and Medications 127
- 20.3 Procedure 127
- 20.4 Pearls and Pitfalls 131
- Selected Reading 132

21 Percutaneous Transtracheal Jet Ventilation 133
Clint Masterson
- 21.1 Indications 133
- 21.2 Contraindications 133
- 21.3 Materials and Medications 133

21.4 Procedure 135
21.5 Complications 139
21.6 Pearls and Pitfalls 139
Selected Reading 139

Part III Thoracic Procedures 141

22 Needle Thoracostomy 143
Lucas McArthur and Christian Fromm
22.1 Indications 143
22.2 Contraindications 143
22.3 Materials 143
22.4 Procedure 144
22.5 Complications 147
22.6 Pearls and Pitfalls 147
Selected Reading 147

23 Chest Tube Thoracostomy 149
Brandon R. Allen and Latha Ganti
23.1 Indications 149
23.2 Contraindications 149
23.3 Materials and Medications 149
23.4 Procedure 151
23.5 Complications 153
23.6 Pearls and Pitfalls 153
Selected Reading 153

24 Thoracentesis 155
Lee Richard Donner and Michael Anana
24.1 Indications 155
24.2 Contraindications 155
24.3 Materials and Medications 155
24.4 Procedure 156
24.5 Complications 158
24.6 Considerations 158
24.7 Pearls and Pitfalls 158
Selected Reading 158

25 Open Chest Wounds and Flail Chest 159
Jacob J. Glaser and Carlos J. Rodriguez
25.1 Background 159
25.2 Initial Evaluation of Thoracic Trauma 161
25.3 Open Pneumothorax (“Sucking Chest Wound”) 161
25.4 Flail Chest 162
References 162

26 Emergent Resuscitative Thoracotomy, Open Cardiac Massage, and Aortic Occlusion 163
Kevin M. Jones and Jay Menaker
26.1 Indications 163
26.2 Contraindications 163
26.3 Materials and Medications 163
26.4 Procedure 165
26.5 Complications 169
Selected Reading 169

27 Lung Ultrasonography 171
Ali H. Dabaja, L. Connor Nickels, and Rohit Pravin Patel
27.1 Indications 171
27.2 Contraindications 171
27.3 Materials 171
27.4 Preparations 171
27.5 Procedure 172
Selected Reading 176

Part IV Cardiac Procedures 177

28 Repair of Cardiac Injuries 179
Ronald Tesoriero
28.1 Indications 179
28.2 Contraindications 179
28.3 Materials and Medications 179
28.4 Procedure 181
28.5 Complications 183
28.6 Pearls and Pitfalls 183
Selected Reading 183

29 Synchronized Electrical Cardioversion 185
Jason Jones, Ann Tsung, and Marie-Carmelle Elie
29.1 Indications 185
29.2 Contraindications 185
29.3 Materials and Medications 185
29.4 Procedure 185
29.5 Complications 188
29.6 Pearls and Pitfalls 188
Selected Reading 188

30 Unsynchronized Cardioversion (Defibrillation) 189
Matthew R. Tice, Zachary B. Kramer, and Marie-Carmelle Elie
30.1 Indications 189
30.2 Contraindications 189
30.3 Materials and Medications 189
30.4 Procedure 190
30.5 Complications 192
30.6 Pearls and Pitfalls 192
Selected Reading 192

31 Transcutaneous Pacing 193
Nour Rifai and Christian Coletti
31.1 Indications 193
31.2 Contraindications 193
31.3 Materials and Medications 193
31.4 Procedure 194
31.5 Pearls and Pitfalls 196
Selected Reading 196

32 Transvenous Cardiac Pacing 197
Katrina John, Jeffrey Kile, and Amish Aghera
32.1 Indications 197
32.2 Contraindications 197
32.3 Materials and Medications 198
32.4 Procedure 199

32.5 Complications 202
32.6 Pearls and Pitfalls. 202
Selected Reading. 202

33 Pericardiocentesis (Optional: Ultrasound Guidance) 203
Katrina Skoog Nguyen, L. Connor Nickels, and Rohit Pravin Patel
33.1 Indications 203
33.2 Contraindications 203
33.3 Materials and Medications. 203
33.4 Procedure 203
33.5 Complications 205
33.6 Pearls and Pitfalls. 205
References. 205

34 Ultrasound Evaluation of Pulmonary Embolism and Heart Strain. 207
Giuliano De Portu, L. Connor Nickels, and Marie-Carmelle Elie
34.1 Indications 207
34.2 Contraindications 207
34.3 Materials and Medications. 207
34.4 Procedure 207
34.5 Findings 209
34.6 Complications 209
34.7 Pearls and Pitfalls. 209
Selected Reading. 209

35 Pacemaker Evaluation in the Emergency Department 211
Joseph D. Romano and Christian Coletti
35.1 Pacemaker Function. 211
35.2 Common Pacemaker Codes 213
35.3 Pacemaker Malfunction 213
35.4 Initial Evaluation of the Patient with a Pacemaker 214
35.5 Interpreting the Type of Malfunction Based on ECG 214
35.6 Management of Pacemaker-Mediated Tachycardia 214
References. 215

Part V Spine Evaluation 217

36 Cervical Collar Placement 219
Justin Bennett and Lars K. Beattie
36.1 Indications 219
36.2 Contraindications 219
36.3 Materials and Medications. 219
36.4 Procedure (Aspen Collar) 220
36.5 Pearls and Pitfalls. 222
Selected Reading. 222

37 Cervical Spine Clearance 223
Braden Hexom and Tatiana Havryliuk
37.1 Indications 223
37.2 Contraindications 223
37.3 National Emergency X-Radiography Utilization Study (NEXUS) and Canadian C-Spine Rules (CCR) to Assess the Need for Imaging 223
37.4 Type of Imaging 224
37.5 Materials 224
37.6 Procedure 225

37.7 Complications 227
37.8 Pearls and Pitfalls. 227
Reference 227
Selected Reading. 227

38 Log Roll 229
Justin Bennett and Lars K. Beattie
38.1 Indications 229
38.2 Contraindications 229
38.3 Materials and Medications. 229
38.4 Procedure 229
38.5 Pearls and Pitfalls. 232
Selected Reading. 232

Part VI Neurologic and Neurosurgical Procedures 233

39 Burr Hole Craniotomy 235
Latha Ganti
39.1 Indications 235
39.2 Contraindications 235
39.3 Materials and Medications. 235
39.4 Procedure 236
39.5 Complications 240
39.6 Pearls and Pitfalls. 240
References. 240
Selected Reading. 240

40 External Ventricular Drain Placement 241
Latha Ganti
40.1 Indications 241
40.2 Contraindications 241
40.3 Materials and Medications. 241
40.4 Procedure 241
40.5 Complications 244
40.6 Pearls and Pitfalls. 244
References. 245

41 Lumbar Puncture in Adults. 247
Kevin Tench, L. Connor Nickels, and Rohit Pravin Patel
41.1 Indications 247
41.2 Contraindications 247
41.3 Materials and Medications. 247
41.4 Procedure 248
41.5 Complications 250
41.6 Pearls and Pitfalls. 250
Selected Reading. 250

42 Reflex Eye Movements (Doll's Eyes and Caloric Testing). 251
Thomas T. Nguyen, Tina Dulani, and Saadia Akhtar
42.1 Doll's Eyes (Oculocephalic Reflex Testing) 251
42.2 Caloric Reflex Testing (Vestibuloocular Reflex) 253
Selected Reading. 255

43 Dix-Hallpike Maneuver 257
Rui Domingues and Muhammad Waseem
43.1 Indications 257
43.2 Contraindications 257
43.3 Materials 257

43.4 Procedure 257
43.5 Complications 258
43.6 Pearls and Pitfalls. 258
Selected Reading. 258

44 Epley Maneuver for Vertigo (Particle Repositioning or Canalith Repositioning Procedure) 259
Rui Domingues and Muhammad Waseem
44.1 Indications 259
44.2 Contraindications 259
44.3 Materials 259
44.4 Procedure 259
44.5 Complications 260
44.6 Pearls and Pitfalls. 260
Selected Reading. 260

45 Clinical Brain Death Examination in Adults 261
Eric S. Papierniak, Hassan M. Alnuaimat, Tracy Timmons, and Deborah M. Stein
45.1 Indications 261
45.2 Contraindications 261
45.3 Materials and Medications. 261
45.4 Procedure 261
45.5 Pearls and Pitfalls. 267
45.6 Controversies 267
Selected Reading. 268

Part VII Ophthalmic Procedures 269

46 Slit Lamp Examination. 271
Bobby K. Desai
46.1 Indications 271
46.2 Contraindications 272
46.3 Materials 273
46.4 Procedure 274
46.5 Complications 276
46.6 Pitfalls 276
46.7 Fluorescein Testing 276
Selected Reading. 277

47 Eye Irrigation 279
Bobby K. Desai
47.1 Indications 279
47.2 Contraindications 279
47.3 Materials and Medications. 279
47.4 Procedure 281
47.5 Complications 282
47.6 Pearls and Pitfalls. 282
Selected Reading. 282

48 Corneal Foreign Body Removal. 283
Bobby K. Desai
48.1 Indications 283
48.2 Contraindications 283
48.3 Materials and Medications. 284
48.4 Procedure 285
48.5 Complications 285
Selected Reading. 285

49 Ultrasound Evaluation of Retinal Detachment 287
Shalu S. Patel, L. Connor Nickels, and Rohit Pravin Patel
49.1 Indications 287
49.2 Contraindications 287
49.3 Materials and Medications 287
49.4 Procedure 287
49.5 Complications 289
49.6 Pearls and Pitfalls 289
Selected Reading 289

50 Ultrasonography in the Evaluation of Intraocular Pathology 291
Benjamin M. Mahon, Marie-Carmelle Elie, L. Connor Nickels, and Rohit Pravin Patel
50.1 Indications 291
50.2 Contraindications 291
50.3 Materials 291
50.4 Procedure 291
50.5 Complications 291
50.6 Pearls and Pitfalls 291
50.7 Specific Disease Processes/Pathology 292
References 295
Selected Reading 295

51 Tonometry 297
Bobby K. Desai
51.1 Indications 297
51.2 Contraindications 297
51.3 Overview 297
51.4 Schiøtz Tonometry 299
51.5 Tono-Pen Tonometry 300
51.6 Complications 303
Selected Reading 303

52 Lateral Canthotomy 305
Benjamin M. Mahon and Bobby K. Desai
52.1 Indications 305
52.2 Contraindications 306
52.3 Materials and Medications 306
52.4 Procedure 306
52.5 Complications 308
52.6 Pearls and Pitfalls 308
Selected Reading 308

Part VIII Otorhinolaryngologic Procedures 309

53 Epistaxis Control 311
Benjamin M. Mahon and Bobby K. Desai
53.1 Etiology 311
53.2 Indications 313
53.3 Contraindications 313
53.4 Materials and Medications 313
53.5 Procedure: Anterior Epistaxis 313
53.6 Procedure: Posterior Epistaxis 317
Selected Reading 319

54 Treatment of Septal Hematoma 321
Bobby K. Desai
54.1 Indications 321
54.2 Contraindications 322
54.3 Materials and Medications 322
54.4 Procedure 322
54.5 Pitfalls and Complications 324
Selected Reading 324

55 Nasal Foreign Body Removal 325
Bobby K. Desai
55.1 Indications 325
55.2 Contraindications: Need Urgent Referral 325
55.3 Materials and Medications 326
55.4 Procedures (Based on the Method Chosen) 328
Selected Reading 329

56 Cerumen Removal 331
Bobby K. Desai
56.1 Indications 331
56.2 Contraindications 331
56.3 Materials and Medications 331
56.4 Procedure 334
56.5 Pitfalls and Complications 334
Selected Reading 334

57 Ear Foreign Body Removal 335
Bobby K. Desai
57.1 Indications 335
57.2 Contraindications: Need Urgent Referral 335
57.3 Materials and Medications 335
57.4 Procedures (Based on the Method Chosen) 337
Selected Reading 338

58 Treatment of Auricular Hematoma 339
Bobby K. Desai
58.1 Indications 339
58.2 Contraindications 340
58.3 Materials and Medications 340
58.4 Procedure (Needle Aspiration) 340
58.5 Pitfalls and Complications 346
Selected Reading 346

59 Incision and Drainage of Peritonsillar Abscess 347
Melinda W. Fernandez and Bobby K. Desai
59.1 Indications 347
59.2 Contraindications 347
59.3 Materials and Medications 347
59.4 Procedure: Aspiration 347
59.5 Procedure: Incision and Drainage 349
59.6 Complications 350
59.7 Pearls and Pitfalls 350
Selected Reading 350

60 Incision and Drainage of Sublingual Abscess 351
Melinda W. Fernandez and Bobby K. Desai
60.1 Indications 351
60.2 Contraindications 352
60.3 Materials and Medications 352
60.4 Procedure: Incision and Drainage 353
60.5 Complications (Generally Minimal) 354
60.6 Pearls and Pitfalls 354
Selected Reading 354

61 Incision and Drainage of Parotid Duct Abscess 355
Melinda W. Fernandez and Bobby K. Desai
61.1 Indications 355
61.2 Contraindications 355
61.3 Materials and Medications 355
61.4 Procedure 357
61.5 Complications 358
61.6 Pearls and Pitfalls 358
Selected Reading 358

Part IX Dental Procedures 359

62 Techniques of Mandibular Anesthesia 361
Susana Perry, Joshua Perry, and Rosalia Rey
62.1 Inferior Alveolar Nerve Block 361
62.2 Buccal Nerve Block 365
62.3 Mental Nerve Block 366
Selected Reading 368

63 Reduction of Dislocated Temporomandibular Joint 369
Christopher J. Spencer and Geraldine Weinstein
63.1 Indications 369
63.2 Contraindications for Closed Reduction 369
63.3 Materials and Medications 369
63.4 Procedure 370
63.5 Complications 372
63.6 Pearls 372
Selected Reading 372

64 Dry Socket (Alveolar Osteitis, Fibrinolytic Osteitis) 373
Michael A. Abraham, Amir Azari, Jennifer Westcott, and Franci Stavropoulos
64.1 Indications 373
64.2 Contraindications 374
64.3 Materials and Medications 374
64.4 Procedure 374
64.5 Complications 374
64.6 Pearls and Pitfalls 374
Selected Reading 374

65 Postextraction Hemorrhage 375
Michael A. Abraham, Amir Azari, Jennifer Westcott, and Franci Stavropoulos
65.1 Indications 375
65.2 Contraindications 375
65.3 Materials and Medications 375
65.4 Procedure 375
65.5 Complications 376

65.6 Pearls and Pitfalls . . . 376
Selected Reading . . . 376

66 Fractured Tooth . . . 377
Geraldine Weinstein
66.1 Indications . . . 377
66.2 Methods of Sustaining Dental Fracture . . . 377
66.3 Four Types of Fractured Tooth . . . 378
66.4 Contraindications . . . 379
66.5 Materials and Medications . . . 379
66.6 Procedure . . . 379
66.7 Complications . . . 380
66.8 Pearls . . . 380

67 Dental Avulsion Management . . . 381
Laura Tucker and Abimbola O. Adewumi
67.1 Indications . . . 381
67.2 Contraindications . . . 382
67.3 Materials and Medications . . . 382
67.4 Procedure . . . 383
67.5 Complications . . . 384
67.6 Pearls and Pitfalls . . . 384
Selected Reading . . . 385

Part X Gastrointestinal Procedures . . . 387

68 Excision of Thrombosed External Hemorrhoid . . . 389
Latha Ganti
68.1 Indications . . . 389
68.2 Contraindications . . . 389
68.3 Materials and Medications . . . 389
68.4 Procedure . . . 390
68.5 Complications . . . 392
68.6 Pearls and Pitfalls . . . 392
References . . . 392
Selected Reading . . . 392

69 Diagnostic Peritoneal Lavage . . . 393
Latha Ganti
69.1 Indications . . . 393
69.2 Contraindications . . . 394
69.3 Materials and Medications . . . 394
69.4 Procedure . . . 394
69.5 Complications . . . 397
69.6 Pearls and Pitfalls . . . 397
References . . . 397
Selected Reading . . . 397

70 Manual Reduction of Abdominal Hernia . . . 399
Latha Ganti
70.1 Indications . . . 401
70.2 Contraindications . . . 401
70.3 Materials and Medications . . . 401
70.4 Procedure . . . 401
70.5 Complications . . . 402
70.6 Pearls and Pitfalls . . . 402
Selected Reading . . . 402

71 Extended Focused Assessment with Sonography for Trauma . . . 403
Coben Thorn and L. Connor Nickels
71.1 Indications . . . 403
71.2 Contraindications . . . 403
71.3 Materials and Medications . . . 403
71.4 Procedure . . . 404
71.5 Complications . . . 409
71.6 Pearls and Pitfalls . . . 409
Selected Reading . . . 410

72 Nasogastric Tube Placement . . . 411
David P. Nguyen, L. Connor Nickels, and Giuliano De Portu
72.1 Indications . . . 411
72.2 Contraindications . . . 411
72.3 Materials and Medications . . . 411
72.4 Procedure . . . 412
72.5 Complications . . . 413
72.6 Pearls . . . 413
Selected Reading . . . 413

73 Esophageal Foreign Body Removal . . . 415
David P. Nguyen, L. Connor Nickels, and Rohit Pravin Patel
73.1 Indications . . . 415
73.2 Contraindications . . . 415
73.3 Materials . . . 415
73.4 Procedure . . . 416
73.5 Complications . . . 416
73.6 Pearls . . . 416
Selected Reading . . . 417

74 Activated Charcoal . . . 419
Deylin I. Negron Smida and Judith K. Lucas
74.1 Indications . . . 419
74.2 Contraindications . . . 420
74.3 Materials and Medications . . . 420
74.4 Procedure . . . 421
74.5 Complications . . . 421
74.6 Pearls and Pitfalls . . . 421
Selected Reading . . . 422

75 Gastric Lavage . . . 423
Deylin I. Negron Smida and Judith K. Lucas
75.1 Indications . . . 423
75.2 Contraindications . . . 423
75.3 Materials and Medications . . . 423
75.4 Procedure . . . 424
75.5 Complications . . . 425
75.6 Pearls and Pitfalls . . . 425
Selected Reading . . . 426

76 Whole-Bowel Irrigation . . . 427
Judith K. Lucas
76.1 Indications . . . 427
76.2 Contraindications . . . 427
76.3 Materials and Medications . . . 427

76.4 Procedure 429
76.5 Complications 429
76.6 Pearls 429
Selected Reading. 430

77 Sengstaken-Blakemore Tube 431
Thomas T. Nguyen, Etan Eitches, and Stephanie Wetmore-Nguyen
77.1 Indications 431
77.2 Contraindications. 431
77.3 Materials and Medications. 431
77.4 Procedure 434
77.5 Complications 437
77.6 Pearls and Pitfalls. 437
Selected Reading. 437

78 Gastrostomy Tube Placement 439
Nathaniel Lisenbee and Latha Ganti
78.1 Indications 443
78.2 Contraindications. 443
78.3 Materials and Medications. 443
78.4 Procedure (PEG Tube Replacement) 444
78.5 Pearls and Pitfalls. 446
78.6 Complications 446
Selected Reading. 446

79 Paracentesis 447
Shalu S. Patel and Bobby K. Desai
79.1 Indications 447
79.2 Contraindications. 447
79.3 Materials and Medications. 447
79.4 Procedure 447
79.5 Complications 449
79.6 Pearls and Pitfalls. 449
Selected Reading. 449

80 Anal Fissure Management 451
David P. Nguyen, L. Connor Nickels, and Giuliano De Portu
80.1 Indications 451
80.2 Contraindications. 453
80.3 Materials and Medications. 453
80.4 Procedure 453
80.5 Complications 453
80.6 Pearls and Pitfalls. 453
Selected Reading. 453

Part XI Genitourinary Procedures. 455

81 Bladder Catheterization 457
Maritza A. Plaza-Verduin and Judith K. Lucas
81.1 Indications 457
81.2 Contraindications. 457
81.3 Materials and Medications. 457
81.4 Procedure 458
81.5 Complications 461
81.6 Pearls and Pitfalls. 461
Selected Reading. 461

82 Pelvic Examination and Wet Preparation 463
Nauman W. Rashid, Elaine B. Josephson, and Muhammad Waseem
82.1 Indications 463
82.2 Contraindications 463
82.3 Materials and Medications 463
82.4 Procedure 463
82.5 Complications 466
82.6 Pearls and Pitfalls 466
Selected Reading 467

83 Bartholin Gland Abscess/Cysts Drainage 469
Holly H. Charleton, Marylin Otero, Diane F. Giorgi, and Joseph A. Tyndall
83.1 Indications 469
83.2 Contraindications 469
83.3 Procedure Types 469
83.4 Materials 470
83.5 Procedures 470
83.6 Iodoform Packing 472
83.7 Aftercare 474
Selected Reading 474

84 Sexual Assault Forensic Examination 475
Rajnish Jaiswal, Mary T. Ryan, and Muhammad Waseem
84.1 Indications 475
84.2 Contraindications 475
84.3 Materials and Medications 475
84.4 Procedure “Prepare the Patient, Prepare the Room” 476
84.5 Pearls and Pitfalls 481
References 481

85 Treatment of Priapism 483
Jeffrey Kile, Katrina John, and Amish Aghera
85.1 Indications 483
85.2 Contraindications 483
85.3 Materials and Medications 483
85.4 Noninvasive Therapy Preprocedure 485
85.5 Procedures 485
85.6 Complications 491
85.7 Pearls and Pitfalls 491
85.8 Considerations 492
Selected Reading 493

86 Reduction of Phimosis/Paraphimosis 495
Justin Chen and Muhammad Waseem
86.1 Indications 495
86.2 Contraindications 495
86.3 Materials and Medications 495
86.4 Procedure: Manual Reduction for Paraphimosis 496
86.5 Complications 499
86.6 Pearls and Pitfalls 499
Selected Reading 499

87 Manual Testicular Detorsion 501
Brandon R. Allen and L. Connor Nickels
87.1 Indications 501

87.2 Contraindications 503
87.3 Materials and Medications 503
87.4 Procedure 503
87.5 Pearls and Pitfalls 504
References 504

Part XII Skin and Soft Tissue Procedures 505

88 Local Anesthesia 507
Derek Ailes and Muhammad Waseem
88.1 Indications 507
88.2 Contraindications 507
88.3 Materials and Medications 508
88.4 Procedure 509
88.5 Complications 510
88.6 Pearls 510
References 510

89 Regional Anesthesia (Nerve Blocks) 511
Derek Ailes and Muhammad Waseem
89.1 Indications 511
89.2 Contraindications 511
89.3 Materials and Medications 512
89.4 Procedure: General Block 513
89.5 Complications 513
89.6 Pearls and Pitfalls 513
89.7 Selected Specific Blocks 514
References 523

90 Wound Management and Hemostasis 525
Rich Teitell and Muhammad Waseem
90.1 Indications for Primary Wound Repair 525
90.2 Contraindications for Primary Wound Repair 525
90.3 Procedure for Wound Closure and Hemostasis 525
90.4 Complications 528
90.5 Pearls and Pitfalls 528
Selected Reading 528

91 Burn Care 529
Thomas Parry and Jeffrey Pepin
91.1 Burn Description 529
91.2 Indications 530
91.3 Materials and Medications 530
91.4 Sizing 530
91.5 Fluid Resuscitation 532
91.6 Procedure 532
91.7 Complications 532
91.8 Pearls and Pitfalls 532
91.9 Admission Criteria 532
Selected Reading 533

92 Wound Closure 535
Oliver Michael Berrett, Jeffrey Joseph Harroch, Karlene Hosford, and Muhammad Waseem
92.1 Indications 535
92.2 Contraindications 535

92.3 Methods 535
92.4 Preparation 535
92.5 Suture Repair 536
92.6 Alternative Methods of Wound Closure. 541
92.7 Pearls and Pitfalls. 542
Selected Reading. 542

93 Wound Closure with Tissue Adhesive 543
Pratik S. Patel and Latha Ganti
93.1 Indications 543
93.2 Contraindications 543
93.3 Materials and Medications 543
93.4 Optional Materials 543
93.5 Procedure 544
93.6 Complications 545
93.7 Pearls and Pitfalls. 545
Selected Reading. 545

94 Fishhook Removal 547
Judith K. Lucas
94.1 Indications 547
94.2 Contraindications 547
94.3 Materials and Medications 547
94.4 Procedures 548
94.5 Postremoval Wound Care 551
94.6 Complications 551
94.7 Pearls and Pitfalls. 551
Selected Reading. 551

95 Tick Removal 553
David N. Smith and Judith K. Lucas
95.1 Indications 553
95.2 Contraindications 553
95.3 Materials and Medications 553
95.4 Procedure 553
95.5 Complications 554
95.6 Pearls and Pitfalls. 554
Selected Reading. 555

96 Subungal Hematoma Drainage 557
Pratik S. Patel and Latha Ganti
96.1 Causes 557
96.2 Indications 557
96.3 Contraindications 557
96.4 Materials and Medications 557
96.5 Procedure 558
96.6 Complications (Rare) 559
96.7 Pearls and Pitfalls. 559
Selected Reading. 559

97 Incision and Drainage of Abscess 561
Nicholas D. Caputo, Karlene Hosford, and Muhammad Waseem
97.1 Indications 561
97.2 Contraindications 561
97.3 Materials and Medications 561
97.4 Procedure 563

97.5 Complications . . . 565
97.6 Pearls . . . 565
Selected Reading . . . 565

Part XIII Orthopedic Procedures . . . 567

98 Splinting . . . 569
Christopher H. Stahmer and Muhammad Waseem
98.1 Indications . . . 569
98.2 Contraindications . . . 569
98.3 Materials and Medications . . . 569
98.4 Procedure . . . 570
98.5 Complications . . . 572
Selected Reading . . . 572

99 Ulnar Gutter Splint . . . 573
Jeffrey Kile, Katrina John, and Amish Aghera
99.1 Indications . . . 573
99.2 Contraindications . . . 573
99.3 Materials . . . 573
99.4 Procedure . . . 575
99.5 Complications . . . 579
99.6 Pearls and Pitfalls . . . 579
Selected Reading . . . 579

100 Shoulder Dislocation Reduction Techniques . . . 581
Katrina Skoog Nguyen, L. Connor Nickels, and Rohit Pravin Patel
100.1 Indications . . . 581
100.2 Contraindications . . . 583
100.3 Materials and Medications . . . 583
100.4 Procedure . . . 583
100.5 Complications . . . 588
100.6 Pearls . . . 588
Selected Reading . . . 588

101 Elbow Dislocation Reduction . . . 589
Katrina John, Jeffrey Kile, and Amish Aghera
101.1 Indications . . . 589
101.2 Contraindications . . . 589
101.3 Materials and Medications . . . 590
101.4 Procedure for Posterior Dislocations . . . 590
101.5 Procedure for Anterior Dislocations . . . 592
101.6 Procedure for Radial Head Subluxations . . . 593
101.7 Complications . . . 595
101.8 Pearls and Pitfalls . . . 595
Selected Reading . . . 595

102 Distal Interphalangeal Joint Reduction . . . 597
Justin Chen and Muhammad Waseem
102.1 Indications . . . 597
102.2 Contraindications . . . 597
102.3 Materials and Medications . . . 597
102.4 Procedure . . . 598
102.5 Complications . . . 599
102.6 Pearls and Pitfalls . . . 599
Selected Reading . . . 599

103 Hip Dislocation Reduction 601
Katrina John, Jeffrey Kile, and Amish Aghera
103.1 Indications 601
103.2 Contraindications 601
103.3 Materials and Medications 601
103.4 Procedure 601
103.5 Complications 606
103.6 Pearls and Pitfalls 606
Selected Reading 606

104 Knee Dislocation Reduction 607
Katrina John, Jeffrey Kile, and Amish Aghera
104.1 Indications 607
104.2 Contraindications 607
104.3 Materials and Medications 607
104.4 Procedure 607
104.5 Complications 612
104.6 Pearls and Pitfalls 612
Selected Reading 613

105 Ankle Dislocation Reduction 615
Katrina John, Jeffrey Kile, and Amish Aghera
105.1 Indications 615
105.2 Contraindications 615
105.3 Materials and Medications 615
105.4 Procedure 615
105.5 Complications 618
105.6 Pearls and Pitfalls 618
Selected Reading 618

106 Arthrocentesis 619
Shalu S. Patel and Bobby K. Desai
106.1 Indications 619
106.2 Contraindications 619
106.3 Materials and Medications 619
106.4 Procedure 619
106.5 Complications 621
106.6 Pearls and Pitfalls 621
Selected Reading 621

107 Intra-articular Injection 623
Bharat Kothakota and Muhammad Waseem
107.1 Indications 623
107.2 Contraindications 623
107.3 Materials and Medications 623
107.4 Procedure 624
107.5 Complications 628
107.6 Pearls 628
Selected Reading 629

108 Sugar-Tong Splint 631
Katrina John, Jeffrey Kile, and Amish Aghera
108.1 Indications 631
108.2 Contraindications 631
108.3 Materials 631
108.4 Procedure 633

108.5 Complications 635
108.6 Pearls and Pitfalls 635
Selected Reading 635

Part XIV Obstetric Procedures 637

109 Fetal Heart Rate Monitoring 639
Nathaniel Lisenbee and Joseph A. Tyndall
109.1 Indications 639
109.2 Contraindications 639
109.3 Methods 639
109.4 Equipment and Procedures 640
109.5 Complications 642
References 642
Selected Reading 642

110 Ultrasonography for Ectopic Pregnancy 643
L. Connor Nickels
110.1 Indications 644
110.2 Contraindications 646
110.3 Materials and Medications 646
110.4 Procedure 646
110.5 Complications 646
110.6 Pearls and Pitfalls 646
Reference 647
Selected Reading 647

111 Ultrasonography for Hydatidiform Mole 649
L. Connor Nickels
111.1 Indications 649
111.2 Contraindications 649
111.3 Materials and Medications 649
111.4 Procedure 649
111.5 Complications 651
111.6 Pearls and Pitfalls 651
Selected Reading 651

112 Ultrasonography for Blighted Ovum (Anembryonic Gestation) 653
Katrina Skoog Nguyen and L. Connor Nickels
112.1 Indications 653
112.2 Contraindications 654
112.3 Materials and Medications 654
112.4 Procedure 654
112.5 Complications 654
112.6 Pearls and Pitfalls 654
Selected Reading 654

113 Ultrasonography for Threatened, Incomplete, or Compete Abortion 655
L. Connor Nickels and Giuliano De Portu
113.1 Indications 655
113.2 Contraindications 655
113.3 Materials and Medications 655
113.4 Procedure 655
113.5 Complications 657
113.6 Pearls and Pitfalls 657
Selected Reading 657

114 Ultrasonography for Placenta Previa 659
L. Connor Nickels and Giuliano De Portu
114.1 Indications 660
114.2 Contraindications 660
114.3 Materials and Medications 660
114.4 Procedure 660
114.5 Complications 662
114.6 Pearls and Pitfalls 662
Reference 662
Selected Reading 662

115 Vaginal Delivery 663
Umarfarook Javed Mirza, Christopher Shields, and Muhammad Waseem
115.1 Indications 663
115.2 Contraindications 663
115.3 Materials and Medications 663
115.4 Procedure 665
115.5 Complications 666
115.6 Pearls and Pitfalls 666
Selected Reading 666

116 Shoulder Dystocia Management 667
Irina Fox Brennan and Joseph A. Tyndall
116.1 Indications 667
116.2 Contraindications 667
116.3 Materials and Medications 667
116.4 Procedure 668
116.5 Complications 673
116.6 Pearls and Pitfalls 673
Selected Reading 673

117 Breech Delivery in the Emergency Department 675
Kristin Stegeman, Sapnalaxmi Amin, Anton A. Wray, and Joseph A. Tyndall
117.1 Indications 676
117.2 Contraindications 676
117.3 Materials and Medications 676
117.4 Procedure 676
117.5 Complications 680
117.6 Pearls and Pitfalls 680
Selected Reading 680

118 Management of Primary Postpartum Hemorrhage 681
Megan Kwasniak, Anton A. Wray, and Joseph A. Tyndall
118.1 Indications 681
118.2 Contraindications 681
118.3 Materials and Medications 681
118.4 Procedure 681
118.5 Complications 683
118.6 Pearls and Pitfalls 683
Selected Reading 684

119 Perimortem Cesarean Section 685
Jordana J. Haber, Elaine B. Josephson, and Muhammad Waseem
119.1 Indications 685
119.2 Contraindications 685
119.3 Materials and Medications 685

119.4 Procedure 686
119.5 Complications 688
119.6 Pearls and Pitfalls 688
Selected Reading 688

Part XV Common Pediatric Procedures 689

120 Peripheral Venous Catheterization 691
David N. Smith and Judith K. Lucas
120.1 Indications 691
120.2 Contraindications 691
120.3 Materials and Medications 691
120.4 Procedure 692
120.5 Pearls and Pitfalls 697
Selected Reading 697

121 Umbilical Venous Catheters (Insertion and Removal) 699
Judith K. Lucas
121.1 Indications 699
121.2 Contraindications 699
121.3 Materials and Medications 699
121.4 Procedure (Insertion) 701
121.5 Procedure (Removal) 703
121.6 Complications 703
121.7 Pearls and Pitfalls 704
Selected Reading 704

122 Intraosseous Access 705
Judith K. Lucas
122.1 Indications 705
122.2 Contraindications 705
122.3 Materials and Medications 705
122.4 Procedure 706
122.5 Complications 710
122.6 Pearls and Pitfalls 710
Selected Reading 710

123 Lumbar Puncture in Pediatrics 711
Maritza A. Plaza-Verduin and Judith K. Lucas
123.1 Indications 711
123.2 Contraindications 711
123.3 Materials and Medications 711
123.4 Procedure 713
123.5 Complications 715
123.6 Pearls and Pitfalls 715
Selected Reading 716

124 Suprapubic Bladder Aspiration 717
Maritza A. Plaza-Verduin and Judith K. Lucas
124.1 Indications 717
124.2 Contraindications 717
124.3 Materials and Medications 717
124.4 Procedure 718
124.5 Complications 720
124.6 Pearls and Pitfalls 720
Selected Reading 720

125 Removal of Hair/Thread Tourniquet 721
Judith K. Lucas
125.1 Indications 721
125.2 Contraindications 722
125.3 Materials and Medications 722
125.4 Procedures 722
125.5 Complications 726
125.6 Pearls and Pitfalls 726
Selected Reading 726

126 Use of the Broselow Tape 727
Judith K. Lucas
126.1 Indications 727
126.2 Contraindications 727
126.3 Materials 727
126.4 Procedure 728
126.5 Pearls and Pitfalls 729
Selected Reading 729

127 Nursemaid's Elbow 731
Judith K. Lucas
127.1 Definition 731
127.2 Clinical Diagnosis 732
127.3 Indications 732
127.4 Contraindications 732
127.5 Materials and Medications 732
127.6 Procedure 732
127.7 Evaluation After Procedure 735
127.8 Pearls and Pitfalls 735
Selected Reading 735

Index 737

Associate Editors

Lars K. Beattie, MD
Bobby K. Desai, MD
Marie-Carmelle Elie, MD
Judith K. Lucas, MD
L. Connor Nickels, MD
Department of Emergency Medicine
University of Florida
Gainesville, FL, USA

Sapna Amin, MD
Central Florida Healthcare
Mulberry, FL, USA

Ad-Hoc Reviewers

Linda Sheehan-Foster, PA-C
Jason Williams, RN
Lake City Veterans Affairs Medical Center
Lake City, Florida

Tej Geoffrey Stead
Buccholz High School
Gainesville, Florida

Models

Lars K. Beattie
Eike Flach
Tatiana Havryliuk
Katy Howard
Ben M. Mahon
Pratik S. Patel
Joseph Rabinovich
Thor Shiva Stead
Karthik Dax Stead
Clarence R. Tucker

Contributors

Michael A. Abraham, DMD United States Air Force, Dental Corps, Minot, ND, USA

Abimbola O. Adewumi, BDS, FDSR Department of Pediatric Dentistry, University of Florida College of Dentistry, Gainesville, FL, USA

Amish Aghera, MD Department of Emergency Medicine, Maimonides Medical Center, New York, NY, USA

Derek Ailes, MD Department of Emergency Medicine, Lincoln Medical and Mental Health Center, New York, NY, USA

Saadia Akhtar, MD Department of Emergency Medicine, Mount Sinai Beth Israel, New York, NY, USA

Brandon R. Allen, MD Department of Emergency Medicine, University of Florida, Gainesville, FL, USA

Hassan M. Alnuaimat, MD Department of Medicine, University of Florida, University of Florida Health Shands Hospital, Gainesville, FL, USA

Sapnalaxmi Amin, MD Department of Family Medicine/Urgent Care, Bayside Urgent Care Center, Clearwater, FL, USA

Michael Anana, MD Emergency Department, University Hospital, Rutgers New Jersey Medical School, Newark, NJ, USA

Amir Azari, DMD Department of Oral and Maxillofacial Surgery, Oregon Health and Science University, Portland, OR, USA

Lars K. Beattie, MD, MS Department of Emergency Medicine, University of Florida, Gainesville, FL, USA

Deena Bengiamin, MD Department of Emergency Medicine, University of San Francisco Fresno, Fresno, CA, USA

Justin Bennett, MD Department of Emergency Medicine, Wake Forest University School of Medicine, Winston-Salem, NC, USA

Oliver Michael Berrett, MD Department of Emergency Medicine, Lincoln Medical and Mental Health Center, New York, NY, USA

Irina Fox Brennan, MD Department of Emergency Medicine, University of Florida, Gainesville, FL, USA

Nicholas D. Caputo, MD, MSc Emergency Department Critical Care, Lincoln Medical and Mental Health Center, New York, NY, USA

Bharath Chakravarthy, MD, MPH Department of Emergency Medicine, University of California Irvine, Orange, CA, USA

Holly H. Charleton, MD Emergency Department, The Brooklyn Hospital Center, Brooklyn, NY, USA

Justin Chen, MD, MSc Department of Emergency Medicine, North Shore University Hospital, Manhasset, NY, USA

Christian Coletti, MD Department of Emergency Medicine and Internal Medicine, Christiana Care Health System, Newark, DE, USA

Ali H. Dabaja, DO Division of Critical Care, Department of Anesthesia, University of Florida, Gainesville, FL, USA

Dawood G. Dalaly, DO Department of Surgery, University of Florida, Gainesville, FL, USA

Giuliano De Portu, MD Department of Emergency Medicine, University of Florida, Gainesville, FL, USA

Bobby K. Desai, MD Department of Emergency Medicine, University of Florida, Gainesville, FL, USA

Rui Domingues, MD Department of Emergency Medicine, Lincoln Medical and Mental Health Center, New York, NY, USA

Lee Richard Donner, MD Emergency Medicine Department, Lincoln Medical and Mental Health Center, New York, NY, USA

Tina Dulani, MD Department of Emergency Medicine, New York Methodist Hospital, Brooklyn, NY, USA

Marie-Carmelle Elie, MD, RDMS Department of Emergency Medicine, University of Florida, Gainesville, FL, USA

Etan Eitches, MD Department of Emergency Medicine, Beth Israel Medical Center, New York, NY, USA

Kevin D. Ergle, MD Department of Internal Medicine, University of Florida Health Shands Hospital, Gainesville, FL, USA

Melinda W. Fernandez, MD Department of Emergency Medicine, University of Florida, Gainesville, FL, USA

Christian Fromm, MD Department of Emergency Medicine, Maimonides Medical Center, SUNY Downstate College of Medicine, New York, NY, USA

Latha Ganti, MD, MS, MBA Department of Emergency Medicine, Orlando Veterans Affairs Medical Center and University of Central Florida, Orlando, FL, USA

Diane F. Giorgi, MD Department of Emergency Medicine, Mount Sinai Queens, New York, NY, USA

Jacob J. Glaser, MD Combat Casualty Care Directorate, Naval Medical Research Unit, San Antonio, TX, USA

Jordana J. Haber, MD Department of Emergency Medicine, Maimonides Medical Center, New York, NY, USA

Jeffrey Joseph Harroch, MD Department of Emergency Medicine, University of Miami Miller School of Medicine, University of Miami Hospital, Miami, FL, USA

Tatiana Havryliuk, MD Department of Emergency Medicine, University of Colorado Denver, Denver, CO, USA

Braden Hexom, MD Department of Emergency Medicine, Mount Sinai Hospital, New York, NY, USA

Karlene Hosford, MD Department of Emergency Medicine, Lincoln Medical and Mental Health Center, New York, NY, USA

Rajnish Jaiswal, MD Department of Emergency Medicine, New York Medical College, Metropolitan Hospital Center, New York, NY, USA

Katrina John, MBBS Department of Emergency Medicine, Eisenhower Medical Center, Rancho Mirage, CA, USA

Jason Jones, MD Department of Emergency Medicine, University of Florida, Gainesville, FL, USA

Kevin M. Jones, MD Trauma and Surgical Critical Care, R Adams Cowley Shock Trauma Center, University of Maryland Medical Center, Baltimore, MD, USA

Elaine B. Josephson, MD Department of Emergency Medicine, Weill Cornell Medical College of Cornell University, Lincoln Medical and Mental Health Center, New York, NY, USA

Jeffrey Kile, MBBS, PhD, MPH Department of Emergency Medicine, Eisenhower Medical Center, Rancho Mirage, CA, USA

Bharat Kothakota, MD Department of Emergency Medicine, Lincoln Medical and Mental Health Center, New York, NY, USA

Zachary B. Kramer, MD Department of Emergency Medicine, University of Florida, Gainesville, FL, USA

Megan Kwasniak, MD Emergency Department, The Brooklyn Hospital Center, New York, NY, USA

Nathaniel Lisenbee, MD U. S. Air Force Medical Center Keesler, Biloxi, MI, USA

Judith K. Lucas, MD Department of Emergency Medicine, University of Florida, Gainesville, FL, USA

Benjamin M. Mahon, MD Ponciana Medical Center, Kissimmee, FL, USA

Clint Masterson, MD Department of Emergency Medicine, Mayo Clinic Health System in Fairmont, Fairmont, MN, USA

Lucas McArthur, MD Department of Emergency Medicine, Maimonides Medical Center, New York, NY, USA

Jay Menaker, MD Departments of Surgery and Emergency Medicine, R Adams Cowley Shock Trauma Center, University of Maryland Medical Center, Baltimore, MD, USA

Umarfarook Javed Mirza, DO Department of Emergency Medicine, Baylor University Medical Center, Dallas, TX, USA

David P. Nguyen, DO Department of Emergency Medicine, Rush-Copley Medical Center, Aurora, IL, USA

Katrina Skoog Nguyen, DO Northwest Community Hospital, Arlington Heights, IL, USA

Thomas T. Nguyen, MD Department of Emergency Medicine, Mount Sinai Beth Israel, New York, NY, USA

L. Connor Nickels, MD, RDMS Department of Emergency Medicine, University of Florida Health Shands Hospital, Gainesville, FL, USA

Marylin Otero, MD Department of Emergency Medicine, Franklin Hospital, Valley Stream, NY, USA

Eric S. Papierniak, DO Division of Pulmonary, Critical Care, and Sleep Medicine, University of Florida and Malcom Randall VA Medical Center, Gainesville, FL, USA

Ram A. Parekh, MD Department of Emergency Medicine, Icahn School of Medicine at Mount Sinai, Elmhurst Hospital Center, Elmhurst, NY, USA

Sohan Parekh, MD Department of Emergency Medicine, University of Texas at Austin Dell Medical School, Austin, TX, USA

Department of Emergency Medicine, University Medical Center Brackenridge, Austin, TX, USA

Thomas Parry, MD Department of Emergency Medicine, Lincoln Hospital and Mental Health Center, New York, NY, USA

Pratik S. Patel, MD Department of Emergency Medicine, University of Florida, Gainesville, FL, USA

Rohit Pravin Patel, MD Department of Emergency Medicine, University of Florida, Gainesville, FL, USA

Shalu S. Patel, MD Department of Emergency Medicine, Florida Hospital Tampa, Florida Hospital Carrollwood, Tampa, FL, USA

Jeffrey Pepin, MD Department of Emergency Medicine, University of Minnesota Medical Center Fairview, Minneapolis, MN, USA

Joshua Perry, DMD Department of Prosthodontics, University of Florida College of Dentistry, University of Florida Health Shands Hospital, Gainesville, FL, USA

Susana Perry, DMD Department of Pediatric Dentistry, University of Florida College of Dentistry, University of Florida Health Shands Hospital, Gainesville, FL, USA

Maritza A. Plaza-Verduin, MD Pediatric Division, Department of Emergency Medicine, Arnold Palmer Hospital for Children, Orlando, FL, USA

Joseph Rabinovich, MD Department of Emergency Medicine, Mount Sinai School of Medicine, Elmhurst Hospital Center, Elmhurst, NY, USA

Nauman W. Rashid, MD Department of Emergency Medicine, WellStar Kennestone Hospital, Marietta, GA, USA

Rosalia Rey, DDS Department of Restorative Dental Sciences, University of Florida College of Dentistry, University of Florida Health Shands Hospital, Gainesville, FL, USA

Nour Rifai, MBCHB Department of Emergency Medicine, Christiana Care Health System, Newark, DE, USA

Carlos J. Rodriguez, DO Division of Trauma Surgery, Surgical Critical Care, Walter Reed National Military Medical Center, Bethesda, MD, USA

Joseph D. Romano, MD Departments of Emergency Medicine and Internal Medicine, Christiana Care Health System, Newark, DE, USA

Mary T. Ryan, MD Department of Emergency Medicine, Lincoln Medical and Mental Health Center, New York, NY, USA

Weston Seipp, MD Department of Emergency Medicine, University of California Irvine Medical Center, Orange, CA, USA

Christopher Shields, MD Department of Emergency Medicine, Lincoln Medical and Mental Health Center, New York, NY, USA

Deylin I. Negron Smida, MD Department of Emergency Medicine, University of Pittsburgh Medical Center, Saint Margaret Hospital, Pittsburgh, PA, USA

David N. Smith, MD Department of Pediatrics, University of Alabama at Birmingham, Children's of Alabama, Birmingham, AL, USA

Christopher J. Spencer, DDS Department of Restorative Dental Sciences, University of Florida College of Dentistry, Gainesville, FL, USA

Christopher H. Stahmer, MD Department of Emergency Medicine, Lincoln Medical and Mental Health Center, New York, NY, USA

Franci Stavropoulos, DDS Department of Dental Specialties - Oral and Maxillofacial Surgery, Gundersen Health System, La Crosse, WI, USA

Kristin Stegeman, MD Department of Emergency Medicine, The Brooklyn Hospital Center, New York, NY, USA

Deborah M. Stein, MD, MPH Department of Surgery, University of Maryland School of Medicine, R Adams Cowley Shock Trauma Center, University of Maryland Medical Center, Baltimore, MD, USA

Rich Teitell, MD Department of Emergency Medicine, Waterbury Hospital, Waterbury, CT, USA

Kevin Tench, MD Department of Emergency Medicine, Banner Boswell Medical Center, Sun City, AZ, USA

Ronald Tesoriero, MD Department of Surgical Critical Care, University of Maryland School of Medicine, R Adams Cowley Shock Trauma Center, Baltimore, MD, USA

Coben Thorn, MD Department of Emergency Medicine, Bon Secours St. Francis Health System, Greenville, SC, USA

Matthew R. Tice, MD Department of Emergency Medicine, University of Florida, Gainesville, FL, USA

Tracy Timmons, MD Department of Trauma/Surgical Critical Care, R Adams Cowley Shock Trauma Center, University of Maryland Medical Center, Baltimore, MD, USA

Shannon Toohey, MD Department of Emergency Medicine, University of California Irvine Medical Center, Orange, CA, USA

Ann Tsung, MD Department of Emergency Medicine, University of Florida, Gainesville, FL, USA

Laura Tucker, DDS Department of Pediatric Dentistry, University of Florida Health Shands Hospital, Gainesville, FL, USA

Joseph A. Tyndall, MD, MPH Department of Emergency Medicine, University of Florida, Gainesville, FL, USA

Muhammad Waseem, MD Department of Emergency Medicine, Lincoln Medical and Mental Health Center, New York, NY, USA

Geraldine Weinstein, DDS Department of Restorative Dental Sciences, University of Florida College of Dentistry, Gainesville, FL, USA

Jennifer Westcott, DMD Private Practice, Palm Beach Gardens, FL, USA

Stephanie Wetmore-Nguyen, MD Department of Emergency Medicine, New York-Presbyterian Hospital/Columbia University Medical Center, New York, NY, USA

Anton A. Wray, MD Department of Emergency Medicine, The Brooklyn Hospital Center, New York, NY, USA

Henry Young II, MD Department of Emergency Medicine, University of Florida, Gainesville, FL, USA

Part I

Vascular Procedures

Arterial Cannulation (Radial and Femoral)

1

Jeffrey Kile, Katrina John, and Amish Aghera

Arterial cannulation is frequently performed in the care of critically ill patients for purposes of both serial arterial blood gas sampling and continuous intra-arterial blood pressure monitoring. It also provides arterial access for less common procedures, including thrombolysis, embolization, angiography, and infusion of vasoactive drugs. This chapter discusses cannulation of the radial and femoral arteries—the two most common sites for indwelling arterial catheter placement.

1.1 Indications

- Continuous monitoring of blood pressure in acute illness or major surgery
- Serial sampling of arterial blood during resuscitation
- Inability to use noninvasive blood pressure monitoring (*e.g.*, burns, morbid obesity)
- Continuous infusion of vasoactive inotropes (*e.g.*, phentolamine for reversal of local anesthesia)
- Angiography
- Embolization

1.2 Contraindications

- Absolute
  - Circulatory compromise in the extremity
  - Third-degree burns of the extremity
  - Raynaud's syndrome
  - Thromboangiitis obliterans (Buerger's disease)
- Relative
  - Recent surgery in the extremity
  - Local skin infection
  - Abnormal coagulation
  - Insufficient collateral circulation
  - First- or second-degree burns of the extremity
  - Arteriosclerosis

1.3 Materials and Medications

- Radial artery cannulation: standard over-the-needle catheter assembly (Fig. 1.1)
  - Antimicrobial solution and swabs
  - Sterile gloves
  - Local anesthetic (1–2 % lidocaine without epinephrine)
  - Blunt needle
  - 25- or 27-gauge needle
  - Two 5 mL syringes
  - 4″×4″ gauze sponges
  - Standard over-the-needle catheter assembly
- Additional materials required for radial artery cannulation: over-the-needle catheter assembly with integrated guide wire
  - Over-the-needle catheter assembly with integrated guide wire
- Additional materials required for femoral artery cannulation: The Seldinger Technique
  - Introducer needle
  - Guide wire
  - Scalpel
  - Dilator
  - Arterial catheter

J. Kile, MBBS, PhD, MPH (✉) • K. John, MBBS
Department of Emergency Medicine, Eisenhower Medical Center,
Rancho Mirage, CA, USA
e-mail: jeffrey.kile@gmail.com; trenjohn@me.com

A. Aghera, MD
Department of Emergency Medicine, Maimonides Medical Center,
New York, NY, USA
e-mail: aaghera@maimonidesmed.org

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_1


APLICARE
POVIDONE-IODINE SOLUTION
LIDOCAINE HCl
10 mg/mL
ETHILON
4-0
ETHICON

Fig. 1.1 Materials and medications

1.3.1 Procedure: Radial Artery Cannulation—Standard Over-the-Needle Catheter Assembly

1. Ensure adequate collateral flow in the selected extremity using the Allen test (see details below).
2. Immobilize the extremity by dorsiflexing the wrist to approximately 60° over a small towel roll and taping the base of the fingers to an arm board or other flat, fixed surface (Fig. 1.2).
    - Rotation of the wrist may shift the artery from its normal anatomical position, complicating cannulation.
3. Locate vessel by palpation of arterial pulse using the second and third fingers of the gloved nondominant hand.
4. Sterilize overlying skin with antimicrobial solution.
5. Inject local anesthetic to raise a small (0.5 cm) wheal using 25- or 27-gauge needle, and direct needle through wheal to infiltrate skin superficial to the artery with additional local anesthetic.
    - Infiltration of the subcutaneous tissue with local anesthetic may also reduce vessel spasm during arterial puncture.
    - Injection of local anesthetic into the vessel may precipitate arrhythmia, so draw back on the plunger prior to infiltration to ensure the tip of the needle is not inside the vessel.
    - Injection of excessive anesthetic when raising a wheal may obscure palpation of the pulse.
6. Ensure proper function of needle-cannula assembly by checking that cannula advances smoothly over needle.
7. Connect a 5 mL syringe with the plunger removed to the over-the-needle catheter assembly.
    - Attachment of syringe improves control during cannulation.
8. Hold syringe connected to needle-cannula assembly like a pen with needle bevel facing upward.
9. Directing the needle at a 30° angle to the skin, puncture the skin through the anesthetic wheal immediately overlying the palpated artery, and advance needle slowly until tip enters arterial lumen, which is confirmed by visible arterial blood flow (“flashback”) into the needle hub and syringe.
    - Avoid self-puncture by maintaining adequate distance between needle tip and index finger (Fig. 1.3).
10. Reduce the angle between needle and skin (by lowering the needle) and advance an additional 2 mm to ensure catheter tip (which sits approximately 2 mm behind the needle tip) has entered the lumen.
    - Advancing the needle too far (or failing to reduce angle between needle and skin) once initial flashback is visualized may result in piercing the back side (or “double puncture”) of the artery wall, in which case visible blood flow will cease; if this occurs, slowly withdraw needle several millimeters until pulsatile blood flow reappears.
11. Stabilize position of introducer needle and advance catheter alone into artery over needle until hub of catheter is in contact with the skin; blood flow from catheter hub at this point indicates successful cannulation of the artery.
    - If difficulty is encountered at this step, catheter hub may be rotated slightly to facilitate advancement.
12. Remove the needle without dislodging catheter from artery.
13. Manually apply pressure to proximal aspect of artery to occlude blood flow from the catheter.
14. Attach desired extension tubing, injection cap, and stopcock to the catheter hub.
15. Secure the catheter hub to the skin using silk (2.0) or nylon (4.0) sutures as follows. Take a 0.5 cm bite of skin under the catheter hub with the suture needle, tie several knots in the suture without pinching the skin, then tie a second set of knots around the hub of the catheter firmly. If the catheter assembly contains an integrated suture wing for fixation, take a 0.5 cm bite of skin under suture wing with the suture needle, thread suture through wing perforation, and secure wing against the skin with several knots. If suture wing has two perforations, repeat this process to secure other half of wing to skin (Fig. 1.4).
16. Cover the catheter with an appropriate self-adhesive sterile dressing.
    - A small bead of antibiotic ointment applied to the puncture site prior to dressing reduces the likelihood of cutaneous wound infection.
17. Secure the tubing connected to the catheter with gauze and adhesive tape or other sterile dressing.
18. Ensure all connections extending from catheter are tight and well secured, as accidental disconnection may result in rapid exsanguination.



Fig. 1.2 Correct position of wrist prior to cannulation



Fig. 1.3 Puncture of radial artery with standard over-the-needle catheter assembly



Fig. 1.4 Radial arterial catheter secured to wrist

1.3.2 Procedure: Radial Artery Cannulation—Over-the-Needle Catheter Assembly with Integrated Guide Wire (Arrow and Other Brands)

Perform steps 1–6 from the "Radial Artery Cannulation: Standard Over-the-Needle Catheter Assembly," above, and then proceed with the steps below:

1. Remove protective cap from needle-cannula assembly and ensure proper function by sliding actuation lever along extension tubing to advance and retract guide wire through needle.
2. Retract guide wire as far back as possible using actuation lever to maximize visibility arterial blood flow ("flashback") within introducer hub.

Perform steps 8–10 from the "Radial Artery Cannulation: Standard Over-the-Needle Catheter Assembly," above, and then proceed with the steps below (Fig. 1.5):

1. Hold needle stationery and slowly slide actuating lever forward to feed guide wire as far as possible into artery.
   - If resistance is met while feeding the guide wire, discontinue sliding actuating lever and withdraw entire unit from artery to prevent damage to guide wire or vessel wall
2. Advance entire assembly 1–2 mm further into vessel to ensure catheter tip (which sits approximately 2 mm behind the needle tip) has entered the lumen.
3. Stabilize clear introducer hub in position and advance catheter forward into artery over guide wire until hub of catheter is in contact with the skin.
   - If difficulty is encountered at this step, catheter hub may be rotated slightly to facilitate advancement.
4. Stabilize catheter in position and withdraw introducer needle, guide wire, and feed tube as a single unit; blood flow from catheter hub at this point indicates successful cannulation of the artery.

Perform steps 13–18 from the "Radial Artery Cannulation: Standard Over-the-Needle Catheter Assembly," above.



Fig. 1.5 Puncture of radial artery using over-the-needle catheter assembly with integrated guide wire

1.3.3 Procedure: Radial Artery Cannulation—The Allen Test

1. Occlude both radial and ulnar arteries of one extremity with digital pressure at wrist.
2. Instruct patient to repeatedly clench the fist tightly to exsanguinate the hand while occlusion of the arteries is maintained.
3. Without releasing digital pressure on arteries, instruct patient to extend fingers and observe palmar surface to confirm blanching of skin.
4. Release pressure on ulnar artery only and observe palmar surface for reperfusion (Fig. 1.6).
    - If reperfusion of the hand does not occur within 5–10 s, ulnar arterial blood flow may be compromised and radial artery cannulation should not be attempted. If reperfusion is brisk, repeat the test releasing pressure on radial artery only and observing palmar surface for reperfusion. If the return of rubor takes longer than 5–10 s, radial artery puncture should not be performed.



Fig. 1.6 The Allen Test

1.3.4 Procedure: Femoral Artery Cannulation—The Seldinger Technique

1. Place the patient in the supine position with the inguinal region adequately exposed.
2. Palpate the femoral pulse, located at midpoint between pubic symphysis and anterior superior iliac spine, using the second and third fingers of the gloved nondominant hand.

Perform steps 4 and 5 from the "Radial Artery Cannulation: Standard Over-the-Needle Catheter Assembly," above, and then proceed with the steps below (Fig. 1.7):

1. Attach 5 mL syringe to an introducing needle of bore sufficient to accommodate guide wire.
2. Hold syringe connected to introducing needle like a pen with needle bevel facing upward.
3. Directing the needle at a 45° angle to the skin in a cephalic direction, puncture the skin through the anesthetic wheal immediately overlying the palpated artery just distal to the inguinal ligament and advance needle slowly toward palpated artery until tip enters arterial lumen, which is confirmed by visible arterial blood flow ("flashback") into the needle hub and syringe.
   - Avoid self-puncture by maintaining adequate distance between needle tip and index finger.
   - Care must be taken to avoid trauma to the femoral nerve and vein bordering the femoral artery.
4. Hold needle stationery and remove syringe, taking care not to displace the intraluminal position of the needle tip.
   - Advancing the needle too far once initial flashback is visualized may result in piercing the back side (or "double puncture") of the artery wall, in which case visible blood flow will cease; if this occurs, slowly withdraw needle several millimeters until pulsatile blood flow reappears.
5. Occlude needle hub temporarily with gloved finger to prevent unnecessary blood loss and air embolism.
6. Thread blunt end of flexible guide wire smoothly into needle and gently into artery until at least one-quarter of guide wire is intravascular (Fig. 1.8).
   - If resistance is met while threading guide wire, remove wire from needle, reattach syringe, and aspirate blood to confirm continued intraluminal needle tip placement; if resistance is met while *removing* guide wire from needle, remove guide wire and needle from artery *as a single unit* to prevent shearing the guide wire off inside the vessel.
7. Holding the wire securely in place, remove the introducing needle.
8. Using a scalpel, make a small incision (approximately the width of the catheter to be used) through the dermis at the insertion site of the guide wire.
   - Avoid severing the guide wire by facing the sharp edge of the scalpel *away* from the guide wire.
9. While stabilizing the guide wire at its insertion site, thread the dilator over the free end of the guide wire until it is approximately one inch from the skin.
10. Grasp the free end of the guide wire protruding from the tail end of the dilator.
    - If it does not protrude from the tail end of the dilator, the guide wire must be removed sufficiently from the artery to be securely grasped; it must protrude visibly from the tail end of the dilator throughout the subsequent process of threading the dilator into the artery.
11. Holding the dilator firmly near its tip, thread the dilator over the wire into the skin with a back-and-forth twisting motion until it reaches the artery.
    - Only the skin tract should be dilated; dilation of the artery may result in excessive arterial injury and/or hemorrhage.
12. Holding the wire securely in place, remove the dilator.
13. While stabilizing the guide wire at its insertion site, thread the catheter over the free end of the guide wire until it nears the skin.
14. Grasping the guide wire where it protrudes from the tail end of the catheter, thread the catheter into the skin to its appropriate insertion length.
15. While stabilizing the catheter at its insertion site, slowly remove the guide wire.
    - If resistance is met while removing guide wire, remove guide wire and catheter from artery as a single unit to prevent shearing the guide wire off inside the vessel.
16. Secure the catheter to the skin using silk (2.0) or nylon (4.0) sutures. Take a 0.5 cm bite of skin with the suture needle. If the catheter assembly contains integrated "wings" for fixation, thread suture through the perforated wings and secure catheter against the skin with several knots. If no fixation device is included, tie several knots in the suture without pinching the skin, leaving both ends of the suture long. Using the loose ends of the suture, tie a second set of knots around the hub of the catheter, firmly, but without constricting its lumen.



Fig. 1.7 Anesthetic injection over the femoral artery



Fig. 1.8 Insertion of guide wire into femoral artery

1.4 Complications

- Hemorrhage
- Hematoma (at puncture site)
- Infection (at insertion site or systemic)
- Thrombosis
- Arteriovenous fistula
- Pseudoaneurysm formation
- Exsanguination (secondary to dislodgement of catheter)
- Cerebrovascular accident (CVA; secondary to air embolism)

1.5 Pearls and Pitfalls

- The shorter and stiffer the plastic tubing connected to the arterial cannula for blood pressure monitoring, the higher its frequency response and the accuracy of measurements.
- Use of an ultrasound probe can facilitate artery location and vessel cannulation.
- Puncture of the femoral artery proximal to the inguinal ligament, or distal to its bifurcation into superficial femoral and deep femoral arteries, may cause massive hemorrhage due to poor vessel compressibility in these regions; the artery should therefore be cannulated just distal to the inguinal ligament, where it is easily compressible against the femoral head if necessary.
- If difficulty is encountered when advancing an over-the-needle catheter into the artery, attach a 10 mL syringe containing 5 mL of sterile normal saline to the catheter hub, aspirate 1 or 2 mL of blood to confirm catheter tip placement within the vessel lumen, and then advance the catheter while gently injecting the saline-blood mixture; the jet of fluid momentarily dilates the lumen, aiding advancement of the catheter.
- An alternative approach to the over-the-needle catheter that will not fully advance is the use of a guide wire. After intraluminal placement of the cannula tip is confirmed by blood return, a guide wire is gently inserted through the catheter into the artery. The cannula is then passed along the guide wire until fully advanced. The guide wire employed must have a blunt, flexible tip to minimize the possibility of vessel wall trauma.
- Two potential consequences of arterial cannulation are vessel obstruction secondary to intravascular thrombosis and hemorrhage (the latter being the most common complication). Choice of puncture site is therefore essential. Due in part to their generous collateral blood flow, as well as ease of compressibility, the radial and femoral are the two most commonly cannulated arteries.
- Repeated puncture following unsuccessful cannulation increases the risk of arterial obstruction secondary to vessel wall damage and thrombosis.

- Double puncture of the cannulated artery by inadvertent over-insertion of the needle has not been shown to increase complications despite the additional trauma to the vessel walls.

Selected Reading

Anderson JS. Arterial cannulation: how to do it. Br J Hosp Med. 1997;57:497.

Gilchrist IC. Reducing collateral damage of the radial artery from catheterization. Catheter Cardiovasc Interv. 2010;76:677–8.

Lemaster CH, Agrawal AT, Hou P, Schuur JD. Systematic review of emergency department central venous and arterial catheter infection. Int J Emerg Med. 2010;3:409–23.

Mitchell JD, Welsby IJ. Techniques of arterial access. Surgery. 2004;22:3–4.

Wilson SR, Grunstein I, Hirvela ER, Price DD. Ultrasound-guided radial artery catheterization and the modified Allen’s test. J Emerg Med. 2010;38:354–8.

2

Ultrasound-Guided Peripheral Intravenous Access

Coben Thorn and L. Connor Nickels

2.1 Indications

- Difficulty placing peripheral intravenous (PIV) using traditional methods of direct visualization and palpation
- To reduce needle sticks in a hypercoagulable patient

2.2 Contraindications

- Patient needs emergent central venous access

2.3 Materials and Medications

- Ultrasound machine
- High-frequency (5–8 MHZ) linear probe (Fig. 2.1)
- Ultrasound gel
- Minimum 1.5-in. needle length
- IV setup
- Skilled operator



Fig. 2.1 High-frequency (5–8 MHZ) linear probe

C. Thorn, MD
Department of Emergency Medicine, Bon Secours St. Francis Health System, Greenville, SC, USA
e-mail: cobenthorn@gmail.com

L.C. Nickels, MD, RDMS (✉)
Department of Emergency Medicine, University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: cnickels@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_2

2.4 Procedure

1. Scan the selected area to identify a target vessel for PIV cannulation.
    - Basilic (runs on the medial side of upper arm) (Fig. 2.2) and cephalic (runs on the lateral side of the upper arm) veins are good superficial veins that are generally not seen without ultrasound. The deep brachial vein is also an option; however, this is a deep vein that runs with the brachial artery, and there is higher chance for complications (Fig. 2.3).
2. Now the site should be prepared for IV insertion. It should be cleaned. An appropriate gauge long needle should be selected, and IV setup should be conveniently located for when access is obtained.
3. The ultrasound probe should be placed in the transverse plane (Fig. 2.4) to best visualize surrounding structures and vein. Alternatively, the probe can be placed longitudinally (Fig. 2.5) for better visualization of needle depth and slope.
    - Most practitioners seem to prefer the transverse approach.
4. The concept of the Pythagorean Theorem is used for accuracy. The needle should be inserted at a 45° angle to the skin and at an equal distance back from the probe as the approximate depth of the vessel vertically. The depth is given on the screen, usually at the bottom in centimeters. As soon as the needle has penetrated the skin the needle tip should be located by fanning the probe toward the needle until it is identified. The needle should then be advanced slowly always keeping the needle tip in view. Once directly on top of the vein, it should tent with pressure and then the needle should be inserted into the vein. Follow the needle in the vein as far as possible while keeping the tip of the needle in the center of the vein to make sure the catheter is securely in the vein and does not infiltrate.


2012Dec17 08:22
Gen
S MB
Ven
HFL
56%
MI
0.7
TIS
0.1
104
BV
2.2
Cine

Fig. 2.2 Basilic vein (BV) located medially when scanning proximally from the antecubital fossa


2012Dec17 08:21
Gen
S MB
Ven
HFL
56%
MI
0.7
TIS
0.1
183
BrV
BrA
2.2
Cine

Fig. 2.3 Brachial artery (BrA) and vein (BrV). The less round, slightly compressed, anechoic structure on the left is the vein. The very circular, not compressed, anechoic structure to the right is the artery


2012Jun14 11:01
Res
S MB
Msk
HFL
99%
MI
0.7
TIS
0.1
31
1.5
Cine

Fig. 2.4 Needle tip in vein seen in a transverse orientation


2012Jun14 09:12
Gen
S MB
SmP
HFL
79%
MI
0.7
TIS
0.1
1.5
Gen
0
Guide
MB On
Dual
Page 1/2

Fig. 2.5 Needle tip in vein seen in a longitudinal orientation

2.5 Complications

Inadvertent puncture of artery. Veins should be thin walled, compressible, and have no pulsations.

2.6 Pearls and Pitfalls

- Mistaking the midshaft of the needle for the needle tip. If this occurs, the needle tip is actually deeper than expected. The ultrasound machine will plot a hyperechoic “dot” on the screen for the needle tip, as long as it crosses the ultrasound beam at any point. This same “dot” will appear whether the tip is directly centered under the beam or *any* segment of the needle shaft is intersecting the beam. This can be visually deceiving and makes this procedure difficult to grasp.
- Very slow movements of the needle and the probe are important for keeping the needle tip in view. Once the needle tip is identified, the probe should be fanned forward (away from operator) just slightly and then the needle advanced until the needle tip comes into view again. This is repeated until the needle is securely moved further into the vein.

Selected Reading

Brannam L, Blaivas M, Lyon M, et al. Emergency nurses’ utilization of ultrasound guidance for placement of peripheral intravenous lines in difficult-access patients. Acad Emerg Med. 2004;11:1361–3.

Constantino TG, Parikh AK, Satz WA, et al. Ultrasonography-guided peripheral intravenous access versus traditional approaches in patients with difficult intravenous access. Ann Emerg Med. 2005;46(5):456–61.

Dargin JM, Rebholz CM, Lowenstein RA, et al. Ultrasonography-guided peripheral intravenous catheter survival in ED patients with difficult access. Am J Emerg Med. 2010;28(1):1–7.

Ma JO, Mateer JR, Blaivas M. Emerg ultrasound. 2nd ed. New York: McGraw-Hill Companies, Inc.; 2008.

Saul T, Rivera M, Lewiss R. Ultrasound image quality. ACEP News. 2011;4:24–5.

Central Venous Line Placement: Internal Jugular Vein, Subclavian Vein, and Femoral Vein

3

Kevin D. Ergle, Zachary B. Kramer, Jason Jones,
and Rohit Pravin Patel

3.1 Indications

- Volume replacement
- Emergent venous access
- Administration of caustic medications: vasopressors, calcium chloride, hypertonic saline, high dose of potassium
- Dialysis catheter placement (hemodialysis)
- Nutritional support (total parenteral nutrition)
- Long-term antibiotics
- Chemotherapy
- Plasmapheresis
- Frequent or persistent blood draws or intravenous therapy when unable to establish peripheral access due to edema or other causes
- Jugular and subclavian: Central venous pressure monitoring, transvenous pacing wire introduction, pulmonary artery catheterization

3.2 Contraindications

- Absolute
  - Infection at site of insertion
  - Distorted anatomy/landmarks (prior surgery, radiation, or history of thrombus in the specified vein)
  - Subclavian only: Trauma to the ipsilateral clavicle, anterior proximal rib, subclavian or superior vena cava vessels
- Relative
  - Morbid obesity
  - COPD
  - Children less than 2 years (higher complication rates)
    - Coagulopathy (although ultrasound-guided internal jugular can be done in this situation)
  - Agitated or moving patient
  - Jugular only: Trauma to the ipsilateral clavicle, anterior proximal rib, subclavian or superior vena cava vessels
  - Jugular and subclavian: Inability to tolerate potential pneumothorax of the ipsilateral thoracic cage
    - Pneumothorax or hemothorax of the contralateral thorax
    - Patients receiving ventilatory support with high-end expiratory pressures (temporarily reduce the pressures)
  - Femoral only: Intra-abdominal (or retroperitoneal) hemorrhage

3.3 Materials and Medications

- Central venous catheter tray or bundle: single/double/triple/quadruple lumen, dialysis catheter, large-bore introducer (for transvenous pacing or pulmonary artery catheter kit)
- Sterile gloves
- Sterile drapes or towels
- Sterile gown
- Hat/hair cap and mask with eye protection
- Antiseptic solution with skin swabs (e.g., chlorhexidine)
- Sterile saline flushes (one 30 mL syringe or three 10 mL syringes)
- Lidocaine 1 %

K.D. Ergle, MD
Department of Internal Medicine, University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: kevin.ergle@medicine.ufl.edu

Z.B. Kramer, MD
Emergency Medicine Resident, University of Florida College of Medicine, University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: zkramer@ufl.edu

J. Jones, MD • R.P. Patel, MD (✉)
Department of Emergency Medicine, University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: jasonjones@ufl.edu; rohitpatel@ufl.edu

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_3

- Sterile gauze
- No. 11 blade scalpel
- Dressing (sterile waterproof transparent dressing or sterile 4×4 gauze with tape)
- Sterile biopatch
- Suture material with needle driver if needed
- Transducing line (optional)
- Sterile probe cover (if using ultrasound guidance)

3.4 Procedures

3.4.1 Internal Jugular Vein Access Procedure

1. Obtain informed consent if not emergently indicated procedure.
2. Obtain supplies and prepare the room, ensuring that all supplies are within operator reach prior to placing gown and commencing the procedure. Include a sterile ultrasound sheath on the sterile field if ultrasound is being used.
3. Raise bed to a comfortable height for the operator.
4. Place patient with head facing away from side of central line site (if using ultrasound, other positions may be preferred). Place patient in 15–20° Trendelenburg position to help fill the upper central veins and reduce the risk of air embolism.
5. Identify the anatomy. Palpate triangle made by the clavicle and sternal and clavicular heads of the sternocleidomastoid (SCM) muscle to identify the location of the internal jugular vein (Fig. 3.1). If using ultrasound guidance, identify optimal anatomical arrangement.
6. Wash your hands and wear sterile attire using aseptic technique, including cap, mask, gown, and sterile gloves.
7. Prepare the site from the clavicle to the ear and across the trachea with antiseptic solution. Allow the antiseptic (chlorhexidine or iodine) to fully dry.
8. Drape the site and patient with sterile towels and drapes included in most CVL bundles. Make sure to cover the whole area and bed.
9. Cover the ultrasound probe with a sterile sheath. This can be done solo or by holding the sterile ultrasound sheath and having an unsterile assistant hold the probe so that the probe can be covered by the sheath.
10. Prepare the kit by checking the guide wire and flushing the tubing and lines with saline included in the kit.
11. With a 25-gauge needle, use 1 % lidocaine to anesthetize the skin at the apex of the triangle made by the SCM and clavicle. Aspirate to make sure the operator is not in a vessel and make a superficial wheel for the insertion site.
12. Preferred method is with ultrasound guidance (see steps 13–17 and Sect. 3.6 for description of ultrasound guidance). If performing without ultrasound, palpate the carotid artery and insert needle lateral to the artery at the apex of the triangle formed by the SCM, aiming toward the ipsilateral nipple at an angle 30–45° above the horizontal plane (Fig. 3.1). Once blood returned, go to step 18.
13. Place sterile ultrasound gel over the insertion site. Use the ultrasound to identify vessel anatomy including internal jugular vein and carotid artery. Use the ultrasound probe to compress the vein, which is compressible as opposed to the carotid artery, which is not compressible (Fig. 3.2).
14. Prepare the insertion needle and syringe (if long and short needles are available, a short needle may be used to reduce posterior vein perforation) and prime the syringe by pulling back on the plunger prior to making the puncture.
15. Use the ultrasound probe to re-identify the patient's anatomy.
16. Ultrasound can be used in short axis or long axis (Fig. 3.3). Short axis is easier for novice operators due to increased ability to see the artery and vein but has a higher risk of posterior perforation if the needle tip is not visualized well. Once short axis of the vein is found, turning the probe 90° clockwise allows the operator to see the vein in long axis. The needle is better visualized in this view but technically more difficult and has less chance to penetrate the posterior wall. In patients with short necks, it may be difficult to obtain long-axis view and needle insertion in the limited space.
17. Insert the needle using the ultrasound guidance with dynamic approach preferred (see Sect. 3.6 for specifics). Make sure to aspirate while inserting the needle to identify when the venous access is obtained. The needle tip should be visualized through the whole process.
    - If using the static approach (see Sect. 3.6), insert needle lateral to carotid pulsation as this is where the vein anatomically is located. Standard method is to insert the needle as far back as the depth the vessel is visualized (e.g., if the vein is visualized 2 cm below skin surface, the needle should be inserted 2 cm behind the probe at a 45° angle).
    - If inserting the needle ~3 cm does not achieve access, gently withdraw the needle toward the surface of the skin while aspirating. Avoid withdrawing the needle completely from the skin. If needed, redirect the needle and advance until blood is aspirated. Cannulation of the vein often takes place while withdrawing the needle.
18. Hold the needle steady with your nondominant hand and remove the syringe, careful not to advance or withdraw the needle. You can place the base of your hand on the patient's chest to make your hand more stable during

this part of the procedure. Occlude the hub of the needle to prevent air embolus.

19. You may verify that you are in the vein by transducing pressure with a fluid column. The fluid should flow easily into the vein.
    - If the aspirated blood is pulsatile and moves up the column, withdraw the needle completely and apply pressure for 10–20 min while taking the patient out of Trendelenburg position (if nonemergent procedure).
20. Once it is verified that you are in the vein, insert the J-tip of the guide wire into the needle hub and advance into the vein. The J-tip can be straightened with a pinching motion (Fig. 3.4). Always keep one hand on the guide wire until it is removed from the patient. Monitor for arrhythmias as the guide wire is advanced toward the right atrium.
    - If the guide wire does not flow easily, remove the guide wire and reattach the syringe, checking for blood flow.
    - If arrhythmia occurs, slowly withdraw the guide wire until the patient's native rhythm returns.
    - Alternatively, the catheter/syringe found in most kits can be used as a bridge to guide wire placement. For the author, this has improved success when there is difficulty in wire placement. Use the same steps above with the catheter (Fig. 3.5) and when you have return of blood, advance the angiocath into the vein followed by insertion of the guide wire through the angiocath. This is especially useful in moving/agitated patients, patients who have collapsible veins due to hypovolemia, and patients who have abnormal anatomy and may have veins that take an abnormal angle shortly past the needle tip.
21. Remove the needle over the guide wire, making sure to always keep control of the guide wire.
22. Make an incision contiguous with the guide wire using a straight (No. 11) blade with the scalpel blade facing upward (away from the wire).
23. Advance the dilator over the guide wire in a twisting motion, keeping control of the guide wire.
    - The dilator only needs to go slightly beyond the anticipated depth of the patient's jugular vein. Do not advance the entire length of the dilator.
24. Withdraw the dilator and hold pressure over the wound site.
25. Advance the catheter over the guide wire while keeping control of the guide wire.
26. With the catheter inserted 10–12 in. from the skin insertion site, retract the guide wire until it comes out of the distal port. Maintain control of the guide wire and advance the catheter to the appropriate length. Usually catheters are inserted 15–16 cm from the right side and 18–20 cm from the left side (Fig. 3.6).
27. Flush each port of the catheter and check aspiration. If difficulty with aspiration or flushing, concern is raised for catheter malposition. The operator can change the depth slightly or twist the catheter and recheck.
28. At this time, an antibiotic ointment or biopatch may be applied to skin around the intersection with the lumen of the catheter. This step is based on local institutional guidelines.
29. Suture the line in place.
30. Enclose CVL site with sterile waterproof transparent dressing.
31. Confirm placement using chest X-ray (CXR). The tip of the catheter should be in the lower third of the superior vena cava (SVC) at the insertion of the SVC into the right atrium.



Fig. 3.1 Internal jugular blind approach; this would be the same location for probe placement if doing ultrasound guided


Vasc/Carotid
L8-3/CH7MHz
DR60/M3/P2
G70/E1/100%
MI1.5 TIs0.2
4.0 cm
14 Hz
ZSI 40
Cine
vein
artery
2 cm
mark
Not compressed
compressed vein
artery
Compressed

Fig. 3.2 Ultrasound showing internal jugular vein and artery with and without compression


Long axis
Vasc/Carotid
L8-3/CH7MHz
DR60/M3/P2
G84/E1/100%
MI1.5 TIs0.2
3.5 cm
15/15 Hz
ZSI 60
Image
Short axis
G70/E1/100%
4.0 cm
14 Hz
ZSI 40
Cine
vein
artery
2 cm
mark
Not compressed

Fig. 3.3 Long- and short-axis views of the internal jugular vein



Fig. 3.4 (**a**, **b**) J-tip straightening using pinch/stretch method



Fig. 3.6 Length: marking seen on typical central venous catheters; number indicates distance in centimeters from distal tip



Fig. 3.5 Angiocath that can be used in difficult to cannulate/wire patients

3.4.2 Subclavian Vein Access Procedure

1. Obtain informed consent if not emergently indicated.
2. Raise bed to comfortable height for the operator.
3. Place patient in supine position and position so patient's head is at the top of the bed.
4. Place patient in 15–20° Trendelenburg position (if tolerated) to reduce risk of air embolism. Studies show this will also increase the size of the subclavian vein. Do NOT place towel between shoulder blades (arch shoulder back) as this has been shown to decrease vein diameter and affect reliability of accessibility. Keep shoulders at anatomical location (forward).
5. Prep area chosen from the anterior neck, clavicle, and upper chest (above nipple line) with chlorhexidine prep or iodine.
6. Open kit and place close to operator's dominant hand to allow for easy access. Diameter of catheter/kit used based on clinical situation:
   - Introducer or large bore if requiring large volumes of resuscitation
   - Triple lumen catheters for vasopressors
   - Introducers if anticipating pulmonary artery catheter or venous pacer
7. Operator should prepare with all aseptic techniques (e.g., hand washing) and maximal barrier precautions (e.g., sterile gowns, sterile gloves, caps, masks covering both mouth and nose, eye protection, and full-body patient drapes).
8. Once sterile and able to touch the inside of the CVL kit, the operator may want to retract the curved J-tip wire into the plastic loop sheath for easy directing into the introducer needle. The operator should also uncap all distal lumens and flush all ports with 3–5 cc of the sterile NS syringes to ensure no defects in the lumen of the catheter. Close all ports except the distal tip port (usually marked with words "distal tip") with the slide clamp.
9. Prep area chosen (right or left side) from the anterior neck, clavicle, and upper chest (above nipple line) with sterile chlorhexidine prep (this is the second cleaning).
10. Place full-body drape over patient with opening over selected side where needle will be inserted.
11. Needle insertion site options (Fig. 3.7):
    - One centimeter inferior to the junction of the middle and medial third of the clavicle
    - Just lateral to the midclavicular line, with the needle perpendicular along the inferior lateral clavicle
    - One fingerbreadth lateral to the angle of the clavicle
12. Anesthetize needle insertion site with 5–10 mL of 1 % lidocaine superficially (make sure to pull back on needle syringe to ensure operator is not in the vein or artery).
    - Never place equipment on a patient.
13. Prepare the needle and syringe by placing the long needle on the syringe. Make sure to break seal of syringe by pulling back on the plunger of the syringe prior to making incision with needle.
14. Turn patient's head to opposite of CVL placement and retract ipsilateral shoulder down to improve clavicle-vein relationship. The retraction of the arm can be done a few steps earlier and can be held in position using a person or tape/restraints.
15. Direct the insertion needle toward sternal notch in the coronal plane at an angle no greater than 10–15° while gently withdrawing the plunger of the syringe. Keep bevel of the needle facing up and in line with the numbers on the syringe until operator enters skin, then face bevel caudally to facilitate smooth progression of the guide wire down the vein toward the right atrium.
16. It helps to place nondominant hand (not holding the needle) on the sternal notch so operator can feel where sternal notch is and direct needle in that direction (Fig. 3.7).
17. NEVER increase the angle of the needle greater than 15° as pneumothorax may ensue.
18. Advance the needle under and along the inferior border of the clavicle, making sure the needle is virtually horizontal to the chest wall. Aim medially in the direction of the suprasternal notch, attempting to first aim for the clavicle then "walk" the needle below the clavicle.
19. Once under the clavicle, continue to advance the needle in a plane almost parallel to the skin approximately 2–3 cm until venous blood is freely aspirated into the syringe.
20. When venous blood is freely aspirated, disconnect the syringe from the needle, and immediately occlude the lumen to prevent air embolism and insert the guide wire. If the vein is difficult to locate, remove the introducer needle, flush it clean of clots, and try again. Change insertion sites after three unsuccessful passes with the introducer needle.
21. At this point, the hand holding the needle should be "set in stone." Use the patient's chest wall as a base to keep needle completely still as to not inadvertently advance or retract needle out of the vein.
22. Insert the guide wire through the needle into the vein with the J-tip directed caudally to improve successful placement into the subclavian vein.
    - Beware a return of red pulsatile blood. If this occurs, the wire is in an artery.
    - Beware aspirating air bubbles through the probing introducer needle. This indicates a pneumothorax.
23. Advance the wire until it is mostly in the vein or until arrythmia is seen on the cardiac monitor. Then, retract the wire 3–4 cm.
24. If the wire does not pass easily, remove the wire, reattach the syringe, and confirm that the needle is still in the

lumen of the vein before reattempting. The J-tip can be straightened with a pinching motion (Fig. 3.4).

- Alternatively, the catheter/syringe found in most kits can be used as a bridge to guide wire placement. For the author, this has improved success when there is difficulty in wire placement. Use the same steps above with the catheter (Fig. 3.5) and when you have return of blood, advance the angiocath into the vein followed by insertion of the guide wire through the angiocath. This is especially useful in moving/agitated patients, patients who have collapsible veins due to hypovolemia, and patients who have abnormal anatomy and may have veins that take an abnormal angle shortly past the needle tip.

25. Use the tip of the scalpel to make a small incision just against the needle to enlarge the catheter entry site for the dilator and catheter.
26. Holding the wire in place, withdraw the introducer needle and place in needle holder.
27. Thread the dilator over the wire and into the vein with a firm and gentle twisting motion while maintaining constant control of the wire. If a large-bore introducer is placed, the dilator/introducer goes in one step, after the introducer is inserted, hold the wire in place and remove the dilator.
28. If operator is having difficulty threading the dilator, the skin incision with the scalpel may have been too superficial or small. It may help to enlarge this incision to avoid having the dilator get caught on superficial skin or connective tissue.
29. It is helpful to have sterile gauze handy to apply pressure with the hand not holding the wire as the vein will now bleed profusely from around the wire secondary to dilation.
30. Thread the catheter until it is close to the skin insertion site. Then pull back on the guide wire until it shows outside of the distal port. Grasp the wire outside of the distal port and thread the catheter while holding onto the guide wire. Usually catheters are inserted 15–16 cm from the right side and 18–20 cm from the left side (Fig. 3.6)
31. Hold the catheter in place and remove the wire. After the wire is removed, occlude the open lumen.
32. Attach sterile saline syringe to the hub and aspirate blood. Take needed samples and then flush the line with saline and recap. Repeat this step with all lumens.
33. Place biopatch on skin around the intersection with the lumen of the catheter.
34. Suture the line in place.
35. Enclose CVL site with sterile waterproof transparent dressing.
36. Confirm placement using CXR. Tip of catheter should be in the lower third of the SVC at the insertion of SVC into right atrium (tip at right bronchiotracheal angle or up to 2.5 cm below bronchiotracheal angle).
    - Alternatively, ultrasound can be used for subclavian line access but only a few limited studies have confirmed this as to date so will not describe in detail (see below for typical ultrasound technique used). See references for more information.



Fig. 3.7 Subclavian vein approach: wrong (**a**) and correct (**b**) angles to take when making skin puncture

3.4.2.1 Subclavian Vein Pearls and Pitfalls

- Inadequate landmark identification: operator should always palpate for landmarks and check anatomy prior to starting the procedure.
- Improper insertion position.
- Insertion of needle through periosteum.
  - Operator should NOT increase angle of needle to avoid the clavicle bone (this can cause a pneumothorax).
  - Operator should press on needle with downward pressure on chest wall to allow needle to maneuver under the clavicle without changing the angle of insertions of the needle.
- Taking too shallow a trajectory with needle.
- Aiming the needle too cephalad (aim for sternoclavicular junction).
- Failure to keep needle in place for wire passage: hand holding the needle should be planted on patient's chest for stabilization.

3.4.3 Femoral Vein Access Procedure

1. Palpate the patient's femoral artery below the inguinal ligament. This is usually found halfway between the anterior superior iliac spine (ASIS) and the midline of the symphysis pubis.
2. Trim overlying hair as necessary.
3. If ultrasound-guided approach is desired, use the linear probe (same as internal jugular) to detect the femoral vein at this location. The femoral vein will be easily compressible, while the femoral artery will be less compressible and pulsatile (Fig. 3.2).
4. Wash hands and use sterile technique to apply iodine or chlorhexidine solution (various forms available).
5. Open your femoral CVL kit and don cap, mask, sterile gown, and sterile gloves. Nonsterile assistants should wear a cap, mask, sterile gown, and sterile gloves. Flush all ports of your CVL kit with saline flushes and check for leaks or malfunction of catheter.
6. Under sterile technique, apply the drape over the area of insertion, and have an assistant extend the drape the length of the bed. Reapply sterile iodine or chlorhexidine at the site.
7. Anesthetize the skin overlying the femoral vein with lidocaine.
8. If ultrasound-guided approach is desired, have an assistant hold up the vascular ultrasound probe. Place your gloved hand through a sterile ultrasound sleeve and grasp the top of the ultrasound probe. Without breaking sterile technique, pull and invert the sterile ultrasound sleeve over the probe and cable. See Sect. 3.6 for detailed ultrasound-guided cannulation technique.
9. Insert the needle at a 45° angle, bevel down, directed superiorly, 1 cm medial to the palpable femoral artery pulse. Once the needle has broken the skin, aspirate by applying a small amount of continuous traction on the plunger of the attached syringe.
10. Advance smoothly and slowly until blood appears in the syringe. Stop once blood is aspirated. If femoral vein is not cannulated, withdraw your needle until just beneath the skin and redirect.
11. Hold the hub of the needle with thumb and forefinger to immobilize in place. Remove the syringe carefully. If blood appears arterial or pulsatile, remove the needle and hold pressure for 5–10 min.
    - Use the palm of your hand on the thigh to stabilize your hand. Not having your hand stable is a common mistake leading to needle movement out of the vein.
12. If blood appears venous (dark color, emerges as a continuous trickle, or transduced), cannulate the needle with the guide wire. Maintain a two-finger grip on the guide wire at all times. Advance the guide wire until approximately 15 cm remains.
    - Must keep handle of guide wire at ALL times and can be done through proper technique.
13. If guide wire does not advance easily, remove guide wire and reposition needle until blood aspirates easily. The J-tip can be straightened using a pinching motion if needed (Fig. 3.4)
    - Alternatively, the catheter/syringe found in most kits can be used as a bridge to guide wire placement. For the author, this has improved success when there is difficulty in wire placement. Use the same steps above with the catheter (Fig. 3.5) and when you have return of blood, advance the angiocath into the vein followed by insertion of the guide wire through the angiocath. This is especially useful in moving/agitated patients, patients who have collapsible veins due to hypovolemia, and patients who have abnormal anatomy and may have veins that take an abnormal angle shortly past the needle tip.
14. Using your scalpel, make a single 1/2 cm stab incision at the site of needle insertion to assist with dilator placement.
    - You can do the stab incision with or without the needle in place, but from experience, most novices have difficulty locating the correct stab location due to small amount of blood accumulation when the needle is taken out.
15. Remove your needle, carefully leaving guide wire in place. Apply dilator over guide wire and advance into the body with gentle pressure and a twisting motion in the same plane that you used to direct the needle.
16. Holding pressure at the insertion site with sterile gauze 4×4 pads, remove the dilator from the guide wire,

leaving the guide wire in place. Insert the central venous catheter over the guide wire until it fits snugly against the skin. Use the markings on the catheter to determine proper length placed (usually with femoral site you can "hub" the catheter) (Fig. 3.6).

17. Using a sterile saline flush, ensure that each lumen of the CVL draws blood easily and flushes easily. Carefully note any that do not and consider repositioning as needed. You can attempt moving catheter in or out a few centimeters or rotating the catheter and recheck. Apply caps to each open lumen of the CVL.
    - Remember to cover the introducer port if not using immediately. If you do not, it poses an infection and air embolism risk to the patient.
18. Suture the line in place.
19. Place an antibiotic biopatch or similar antimicrobial dressing.
20. Enclose CVL site with sterile waterproof transparent dressing.

3.4.3.1 Femoral Vein Pearls and Pitfalls

- Femoral central venous lines cannot accurately transduce central venous pressures.
- Asking the patient to perform a Valsalva maneuver has been shown to increase the width of the femoral vein by 1/3.
- The mnemonic NAVEL (Nerve Artery Vein Empty space Lymphatics) assists in remembering the order of femoral structures from lateral to medial.
- Traditionally, femoral venous lines were thought to have higher rates of infection than subclavian or internal jugular lines, but more recent analyses are challenging this belief.
  - Obesity is a more important risk factor for infection in femoral sites.

3.5 Complications

3.5.1 Jugular and Subclavian Complications

- Pneumothroax/Hemothorax
  - Prevention: Remove patient from ventilator before advancing the needle, choose the right side rather than left, and avoid multiple attempts when possible.
  - Management: Check postprocedure x-ray; if pneumothorax, arrange for thoracostomy depending on the size of the hemo-/pneumothorax.
- Catheter embolization
  - Prevention: Never withdraw a catheter past a needle bevel as this might shear off the catheter.
  - Management: X-ray the patient and contact specialist who can remove the embolized catheter.
- Arterial puncture: Hold compression if this occurs.
- Hematoma: Usually requires monitoring only.
- Thrombosis: This complication may lead to pulmonary embolism.
- Local site or systemic infection: Using maximal sterile precautions has been shown to greatly decrease rate of infection.
- Air embolism
  - May be caused by negative intrathoracic pressure when inspiration by the patient drawing air into an open line hub
  - Prevention: Be sure the line hubs are always occluded; placing the patient in the Trendelenburg position lowers the risk.
  - Management: The patient should be placed in Trendelenburg position with a left lateral decubitus tilt, which may prevent the movement of air into the right ventricle and onward into the left side of the heart. One hundred percent oxygen should be administered to speed the resorption of the air. If a catheter is located in the heart, aspiration of the air should be attempted.
- Dysrhythmias: Due to cardiac irritation by the wire or catheter tip. This can usually be terminated by simply withdrawing the line into the superior vena cava. One should always place a central venous catheter with cardiac monitoring.
- Lost guide wire: If the operator is not careful about maintaining control of the guide wire, it may be lost into the vein. This requires retrieval by interventional radiology or surgery and is an emergency.
- Catheter tip too deep: Check the postprocedure chest radiograph and pull the line back if the tip disappears into the cardiac silhouette.
- Catheter in the wrong vessel: Check the postprocedure chest radiograph for this complication; remove catheter and try again.
- Arterial puncture (subclavian only): The subclavian artery cannot be compressed; so, the subclavian approach should be avoided in anticoagulated patients.

3.5.2 Femoral Complications

- Arterial puncture: The femoral artery site can be compressed, so if punctured hold pressure.
- Hematoma: Usually requires monitoring only.
- Thrombosis: This complication may lead to pulmonary embolism.
- Catheter embolization.
  - Prevention: Never withdraw a catheter past a needle bevel which might shear off the catheter.
  - Management: X-ray the patient and contact specialist who can remove the embolized catheter.

- Lost guide wire: If the operator is not careful about maintaining control of the guide wire, it may be lost into the vein. This requires retrieval by interventional radiology or surgery and is an emergency.
- Local site or systemic infection: Using maximal sterile precautions has been shown to greatly decrease rate of infection.

3.6 Ultrasound Guided Cannulation: Tips for Each Approach

- Venous anatomy is best visualized using high-frequency (5–10 MHz) linear probe. Higher frequencies generate less penetration but better resolution.
- You can use the ultrasound to identify the location of the vessel prior to the procedure and utilize external landmarks during the procedure itself (static technique), or you can use the ultrasound to visualize cannulation of the vessel during the procedure (dynamic technique).
- Static view is advantageous in that the ultrasound transducer is not needed during the sterile portion of the procedure, but it does not allow for direct visualization of cannulation and guidance during the procedure.
- Dynamic view (preferred) allows for direct visualization during the procedure but requires more technique and requires use of transducer during the sterile portion of the procedure.
- The dynamic technique can be used in either a short-axis view, where a cross-sectional view of the vessel and needle is used, or a long-axis view, where a longitudinal view of vessel and needle is used (Fig. 3.3).
- The long-axis view allows for full visualization of the needle throughout the procedure and allows for better visualization and adjustment of needle depth. It is more difficult for lateral changes in positioning and tends to be more difficult technically.
  - Key in this view is that once a good section of vein is obtained, do not move probe to visualize the needle; move the needle into the ultrasound view by slightly adjusting trajectory.
- The short-axis view allows for lateral changes in position but is not as good at visualizing depth throughout the procedure, as visualization of the needle is in cross-sectional imaging. Perforation of the posterior wall is more common in this view.
- When using the short-axis view, remember to position the ultrasound probe such that the field of the ultrasound intersects the vessel (internal jugular, subclavian, femoral) at the anticipated site of insertion of the needle into the vein. Remember that the needle is only visualized as it intersects the plane of the ultrasound.
- When using the long-axis view, make sure to visualize the vessel with the ultrasound such that you can see the greatest diameter of the vessel along the entire length of the ultrasound probe. Keep the ultrasound steady during the procedure, and insert the needle at an angle at the lateral edge of the ultrasound probe. Using this technique, one can visualize the entire length of the needle.

3.7 Removing a Central Line

1. Place patient in supine or Trendelenburg position (for femoral removal can help decrease bleeding).
2. Remove suturing and dressing.
3. Jugular and subclavian: Have patient exhale and pull the line during the exhalation.
   - Exhalation increases intrathoracic pressure as compared to atmospheric pressure, thereby reducing the risk of air thromboembolism.
4. Hold pressure for approximately 1 min to stop bleeding.
5. Dress with a sterile dressing.
6. If central line-related infection is suspected, cut off the tip with sterile scissors and send for culture.

Selected Reading

Internal Jugular Vein Access

McGee DC, Gould MK. Preventing complications of central venous catheterization. N Engl J Med. 2003a;348(12):1123–33.

Mimoz O, et al. Chlorhexidine-based antiseptic solution vs alcohol-based providone-iodine for central venous catheter care. Arch Intern Med. 2007;167(19):2066–72.

Noble V, et al. Manual of emergency and critical care ultrasound. Cambridge: Cambridge University Press; 2007. p. 196–204.

Parry G. Trendelenburg position, head elevation and a midline position optimize right internal jugular vein diameter. Can J Anaesth. 2004;51(4):379.

Vesely T. Central venous catheter tip position: a continuing controversy. J Vasc Interv Radiol. 2003;14(5):527.

Subclavian Vein Access

Elliott TS, Faroqui MH, Armstrong RF, Hanson GC. Guidelines for good practice in central venous catheterization. Hospital Infection Society and the Research Unit of the Royal College of Physicians. J Hosp Infect. 1994;28(3):163–76.

Fortune JB, Feustel P. Effect of patient position on size and location of the subclavian vein for percutaneous puncture. Arch Surg. 2003;138(9):996–1000; discussion 1001.

Fragou M, et al. Real time ultrasound-guided subclavian vein cannulation versus the landmark method in critical care patients: a prospective randomized study. Crit Care Med. 2011;39(7):1–6.

Kilbourne MJ, Bochicchio GV, Scalea T, Xiao Y. Avoiding common technical errors in subclavian central venous catheter placement. J Am Coll Surg. 2009;208(1):104–9.

McGee DC, Gould MK. Preventing complications of central venous catheterization. N Engl J Med. 2003b;348(12):1123–33.

Femoral Vein Access

Dailey RH. Femoral vein cannulation: a review. J Emerg Med. 1985;2:367–72.

Lim T, Ryu H-G, et al. Effect of the bevel direction of puncture needle on success rate and complications during internal jugular vein catheterization. Crit Care Med. 2012;40(2):491–4.

McGee DC, Gould MK. Preventing complications of central venous catheterization. N Engl J Med. 2003c;348:1123–33.

Marik PE, Flemmer M, Harrison W. The risk of catheter-related bloodstream infection with femoral venous catheters as compared to subclavian and internal jugular venous catheters: a systemic review of the literature and meta-analysis. Crit Care Med. 2012;40:2479–85.

Swanson RS, Uhlig PN, Gross PL, et al. Emergency intravenous access through the femoral vein. Ann Emerg Med. 1984;13:244–7.

4 Pulmonary Artery Catheter

Rohit Pravin Patel and Marie-Carmelle Elie

4.1 Indications

- Prevention or treatment of multiorgan failure in high-risk patients
- Preoperative and postoperative management in high-risk patients with cardiac, pulmonary, or renal dysfunction
- Patients with anticipated large fluid shifts (sepsis, bleeding, burns, cirrhosis)
- Oliguria or hypotension not relieved by fluids
- Suspected cardiac event leading to shock
- For continuous SVO2 (central venous oxygenation) monitoring in shock
- To differentiate shock states
- For monitoring cardiac output in patients requiring high-positive end-expiratory pressure (>14 cm H20)
- Monitoring and management of complicated myocardial dysfunction or cardiogenic shock
- Congestive heart failure with poor response to afterload reduction and diuretic therapy
- Suspected tamponade or contusion from blunt chest injury
- Pulmonary hypertension with myocardial dysfunction
- Diagnosis of primary pulmonary hypertension
- Aspiration of air emboli
- Direct pulmonary artery administration of thrombolytic therapy

4.2 Contraindications

- Tricuspid or pulmonary valve mechanical prosthesis
- Right heart mass (thrombus or tumor)
- Tricuspid or pulmonary valve endocarditis
- Recurrent sepsis (catheter could serve as nidus for infection)
- Hypercoagulopathy (catheter could serve as site for thrombus formation)
- Patient known sensitivity to heparin (catheters with heparin coating)
- Electrocardiographic (ECG) monitoring encouraged in conditions of complete left bundle branch block (risk of complete heart block increased), Wolfe–Parkinson–White syndrome, and Ebstein's malformation (risk of tachyarrhythmias)

4.3 Materials

- Pulmonary artery or Swan–Ganz catheter
- Percutaneous sheath introducer and contamination shield
- Compatible cardiac output computer for measuring cardiac output by the bolus thermodilution method
- Injectate temperature sensing probe (bolus thermodilution method)
- Connecting cables
- Sterile flush system and pressure transducers
- Bedside ECG and pressure monitor system
- Appropriate ECG "slave" cables

4.3.1 Catheter Preparation

- Avoid forceful wiping or stretching of catheter to avoid injury to the thermistor wire circuitry; wiping the heparin coat may cause removal of the coating.
- In vivo calibration is required if in vitro calibration is not done; refer to the monitor operator's manual for detailed calibration instructions.
- Connect catheter's injectate and pressure-monitoring lumens to the flush system and pressure transducers; ensure all lines are free of air.
- Connect the thermistor to the monitor and confirm no fault messages appear.

R.P. Patel, MD • M.-C. Elie, MD, RDMS (✉)
Department of Emergency Medicine, University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: rohitpatel@ufl.edu; elie@ufl.edu

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_4

4.4 Procedure

1. Maintain sterile precautions including sterile cap, mask, gown, gloves.
2. Place a central venous line introducer and verify placement of introducer with chest radiograph; it is also acceptable to obtain the chest radiograph after the insertion of the pulmonary artery catheter if no complication was suspected with the central venous line introducer.
3. Cleanse the skin and introducer thoroughly with chlorhexidine.
4. Have assistant open pulmonary artery catheter kit in sterile fashion.
5. Remove pulmonary artery catheter from kit and have assistant hook up all the ports to the transducers and make sure readings are accurate as the catheter is being manipulated.
6. Gently lift the distal portion of the catheter up from the silicone gripper; do not pull the balloon through the gripper to avoid damage.
7. Have assistant check the proximal and distal ports for patency by flushing with sterile saline. Also have the assistant check the patency of the balloon with the syringe provided in the kit (Fig. 4.1). Check for major asymmetry and for leaks (optional) by submerging in sterile saline or water. Deflate balloon prior to insertion. Carefully wave the distal catheter segment up and down to confirm electrical continuity by observing a pressure tracing on monitor. Ensure proper readings, no information is sometimes better than wrong information. Make sure each port transduces appropriately *prior to* insertion.
8. Familiarize yourself with the catheter line markings. Each thin line indicates 10 cm from the tip and thick line indicates 50 cm from the tip. These are used in combination to indicate length from tip (Fig. 4.2).
9. Place the sterile plastic sleeve (lock side toward patient, Fig. 4.3) over the catheter after flushing all ports to further protect the catheter during manipulation.
10. The distal end of the catheter is inserted into the introducer hub of the central venous line and threaded to the superior vena cava. The catheter must be placed at least 30 cm into the introducer for the balloon to clear the distal end of the introducer prior to inflation. At *no point* should the catheter be withdrawn with the balloon inflated; ensure the assistant has deflated the balloon prior to withdrawal. The balloon assists in directing the catheter through the vascular system using the directional blood flow.
11. At 20 cm, the balloon should be inflated and catheter advanced through right atrium, past the tricuspid valve into the right ventricle, then past the pulmonary valve to the pulmonary artery. The waveform and pressure readings can guide you through the various locations (Fig. 4.4).
12. Once in the pulmonary artery, the catheter should be carefully and slowly advanced to wedge position. The balloon can be deflated and pulmonary artery tracings should reappear. If a wedge is obtained with less than the maximum recommended volume, the catheter should be withdrawn to a position where full inflation volume produces a wedge tracing. Avoid prolonged times when obtaining wedge pressure (2 respiratory cycles or 10–15 s), especially in patients with pulmonary hypertension.
13. General guidelines for distance necessary at various points include: right atrium 20–25 cm, right ventricle 30–35 cm, and pulmonary artery 40–45 cm; catheter usually wedges at 50–55 cm. These are dependent on the starting location you are using to advance the catheter (subclavian, internal jugular, femoral).
14. Once the catheter is in correct position, it should be locked into place with the plastic sleeve tip onto the hub of the introducer.
15. Correct placement is confirmed with chest radiograph (Fig. 4.5).



Fig. 4.1 Balloon inflation prior to insertion for evaluation of patency or leaks



Fig. 4.2 Thick and thin markings found on the catheter representing length from distal tip



Fig. 4.3 Lock position on catheter for stabilization of catheter



Fig. 4.4 Typical waveform seen at specific locations in the heart with associated estimated distances from catheter tip



Fig. 4.5 Chest radiograph demonstrating correct (**a**) and incorrect (**b**) positioning of pulmonary artery catheter (*arrows*) (**a** Reproduced with permission from McGraw-Hill: Stead LG, et al. *First Aid for the Radiology Clerkship*. New York: McGraw-Hill; 2009; **b** Reproduced with permission from Wolters Kluwer: Jain SN. A pictorial essay: radiology of lines and tubes in the intensive care unit. *Indian J Radiol Imaging*. 2011;21(3):182–190)

4.5 Complications

- Arrhythmias: most are premature ventricular contractions that are self-limiting and resolve with advancement into pulmonary artery or withdrawal into atrium.
- Right bundle branch block: usually transient after positioning catheter into the pulmonary artery; if has already left bundle branch block may lead to complete heart block; should have temporary pacing equipment on standby.
- Knotting in the right ventricle (RV): risk increased in those with dilated cardiac chambers; a persistent RV tracing (15 cm beyond the point where initial RV tracing was observed) should alert you to this possibility.
- Pulmonary artery rupture: age >60 year, anticoagulation therapy, and presence of pulmonary hypertension increase risk of rupture; hemoptysis shortly after placement is indicative and management includes lateral decubitus positioning (bleeding side down), intubation with double lumen tube, and increasing positive end-expiratory pressure (PEEP).
- Infection.
- Pulmonary infarction: due to unintentional migration of distal tip.

4.6 Pearls and Pitfalls

- If the catheter requires stiffening during insertion, slowly perfuse the catheter with 5–10 mL of cold sterile solution as the catheter is advanced through a peripheral vessel.
- The incidence of complications increases significantly with periods of use longer than 72 h, so assess the need for the catheter on daily basis.
- Anticipate spontaneous catheter tip migration toward periphery of pulmonary bed; if a wedge tracing is observed when balloon is deflated, pull the catheter back.

Selected Reading

1. Edward Lifesciences. Pulmonary artery catheter Instruction manual. 2009. http://ht.edwards.com/resourcegallery/products/swanganz/pdfs/invasivehdmphysprincbook.pdf.
2. Edward Lifesciences. Pulmonary artery catheter Instruction manual. 2009. http://www.edwards.com/products/pacatheters/Pages/ThermodilutionCatheter.aspx.
3. Leatherman JW, Marini JJ. Clinical use of the pulmonary artery catheter. In: Hall JB, Schmidt GA, Wook LDH, editors. Principles of critical care. 3rd ed. New York: McGraw-Hill; 2005. p. 146–50.
4. Moran SE, Pei KY, Yu M. Hemodynamic monitoring: arterial and pulmonary artery catheters. In: Gabrielli A, Layon AJ, Yu M, editors. Civetta, Taylor, and Kirby's critical care. 4th ed. Philadelphia: Lippincott Williams & Wilkins; 2009.

Noninvasive Cardiac Monitoring: The Edwards Vigileo System

5

Dawood G. Dalaly and Rohit Pravin Patel

5.1 Indications

Cardiac output monitoring is indicated when trying to determine fluid responsiveness in patients. It assists in directing and assessing results of resuscitative efforts to ensure appropriate tissue perfusion. Although most catheters are systemically invasive, tools like the Vigileo (Edwards Lifesciences; Irvine, CA) are excellent noninvasive devices for determining values such as the stroke volume, stroke volume variation, stroke volume index, cardiac output, and cardiac index (Fig. 5.1).

D.G. Dalaly, DO
Department of Surgery,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: ddalaly@ufl.edu

R.P. Patel, MD (✉)
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: drpratik@gmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_5


a
Power
Trend Screen
Print
Move across trend screen up to 24 hours
Help
Alarm
Enter and Scroll knob, *You can turn this knob and press it to confirm a function you want*
Edwards Lifesciences
Vigileo
CO 4.3 ScvO2
CI 2.0
SV 45
SVR 1096
SVV 7
SVI 21
SVRI 2325
Alert SVR: Slaved-In Pressure Signal Loss
b
Press
CO2
SICU
PRESS
Press
Zero
BIS
c
Edwards Lifescience
Vigileo
CO 4.1 ScvO2
CI 1.9
SV 43
SVR 631
SVV 11
SVI 20
d

Fig. 5.1 Typical monitoring devices and connecting devices from monitor to patient: (**a**) FloTrac monitor, (**b**) FloTrac red port connects to the heart monitor, (**c**) the FloTrac system connects to the arterial line on one end and the pressure bag/monitors on the other; monitor connections are color coded, (**d**) the green port connects to the green port from the FloTrac

5.2 Contraindications

There are no contraindications to noninvasive monitoring of the heart, although most systems will need to be connected to an arterial line catheter, therefore contraindications to arterial line placement must be determined. Current literature supports the use of noninvasive monitoring to those who are 100 % supported ventilation with tidal volumes ≥8 mL/kg. There is no support for use in those with spontaneous breaths or arrhythmia. Patients with significant variation in respiratory pattern may have results that are unreliable.

5.3 Definitions and Values (Table 5.1)

Table 5.1 Cardiac output monitoring definitions

Term	Reference range	Definition
Cardiac output	4–8 L/min	Volume of blood being pumped by the heart in 1 min
Cardiac index	2.5–4 L/min/m^2	Compares the amount of fluid being pumped by the heart with an individual's body surface area
Stroke volume	40–80 mL/beat	Volume of blood being pumped by the ventricle per beat
Stroke volume variation	10–15 %	Represents percentage of change between minimum and maximum stroke volumes and predictor of fluid responsiveness
Stroke volume index	33–47 mL/m^2/beat	Quantity of blood ejected from the heart per beat
Mixed venous saturation (SvO$_2$)	60–80 %	Percentage of oxygen bound to hemoglobin in blood returning to the right side of the heart; represents oxygen delivery and consumption at the tissue level. Usually obtained from pulmonary artery catheter
Central venous oxygen saturation (ScvO$_2$)	70 %	Surrogate marker for SvO$_2$, usually obtained from internal jugular or subclavian catheters

5.4 Materials

- FloTrac (Edwards Lifesciences, Irvine, CA, USA)
- Vigileo monitor
- Pressure bag

5.5 Procedure

1. Connect FloTrac to arterial line and distal FloTrac port to pressure bag. Inflate bag to 300 mmHg.
2. Connect green FloTrac cord to green Vigileo cord and red FloTrac cord to arterial line port on heart monitor.
3. Turn the port on the FloTrac off to the patient and zero on your heart monitor as you would with an arterial line. At the same time, you should have pressed the "Enter" knob on the Vigileo system, scrolled it to "zero arterial pressure," and pressed the knob again for that function.
4. You should now have an arterial waveform on your heart monitor and your cardiac values on the Vigileo system.

5.6 Pearls and Pitfalls

- Some components of the values obtained are not reliable on spontaneously breathing patients and it is critical to check the ventilator waveforms for these breaths.
- Patients without adequate tidal volumes (at least 8 mL/kg) will also have unreliable values.
- Stroke volume variation usually is more reliable when greater than 13 % and indicates fluid responsiveness rather than when it is less than 13 % (similar to a low central venous pressure (CVP) being more informative than normal or high CVP levels).

Selected Reading

1. Alarcon LH, Fink MP. Chapter 13. Physiologic monitoring of the surgical patient. In: Brunicardi FC, Andersen DK, Billiar TR, et al., editors. Schwartz's principles of surgery. 9th ed. New York: McGraw-Hill; 2010.
2. Holcroft JW, Anderson JT, Sena MJ. Chapter 12. Shock and acute pulmonary failure in surgical patients. In: Doherty GM, editor. CURRENT diagnosis & treatment: surgery. 13th ed. New York: McGraw-Hill; 2009. Available at http://www.accesssurgery.com/content.aspx?aID=5212482. Accessed 22 Aug 2012.
3. Edwards Critical Care Education. Available at http://www.edwards.com/education/Pages/cceducationmap.aspx. Accessed 11 Dec 2012.

6

Peripheral Venous Cutdown

Jeffrey Kile, Katrina John, and Amish Aghera

6.1 Indications

- Distorted anatomy of peripheral venous access sites
- Unavailability of cannulable veins (e.g., in hypovolemia, burn victim, traumatic anatomy, sclerosed veins, etc.)
- Emergency venous access for infusion/transfusion
- Unavailability of central venous access or less invasive means peripherally

6.2 Contraindications

- Absolute
  - Availability of less invasive or less time-consuming means of vascular access
  - Overlying infection, traumatic tissue, burn, etc., at cutdown site
  - Traumatic injury proximal to cutdown site
- Relative
  - Coagulation disorders

6.3 Materials and Medications (Fig. 6.1)

- Sterile gloves
- Antimicrobial solution and swabs
- 4″×4″ gauze sponges
- Local anesthetic (1 % lidocaine 5 mL)
- 5-mL syringe
- Blunt needle
- 25- or 27-gauge needle
- Scalpel
- Vein dilator/lifter
- Peripheral intravenous catheter
- Curved hemostat
- 0-0 silk sutures or 4.0 nylon sutures
- Iris scissors
- Intravenous infusion tubing
- Adhesive tape

J. Kile, MBBS, PhD, MPH (✉) • K. John, MBBS
Department of Emergency Medicine, Eisenhower Medical Center,
Rancho Mirage, CA, USA
e-mail: jeffrey.kile@gmail.com; trenjohn@me.com

A. Aghera, MD
Department of Emergency Medicine, Maimonides Medical Center,
New York, NY, USA
e-mail: aaghera@maimonidesmed.org

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_6


APLICARE
POVIDONE-IODINE SOLUTION
LIDOCAINE HCl
10 mg/ml
ETHILON
4-0

Fig. 6.1 Materials and medications

6.4 Choice of Vessel for Cutdown

- Greater saphenous vein: this vessel is the longest vein in the body, is predominantly subcutaneous, and is exposed with minimal blunt dissection just anterior to the medial malleolus at the ankle.
- Basilic vein: this vessel is reliably located 1–2 cm lateral to the medial epicondyle on the anterior aspect of the humeral region, typically catheterized just superior to the antecubital fossa approximately, and its diameter permits its localization relatively easily even in the hypotensive patient.
- Cephalic vein: this vessel runs anteromedially from the radial aspect of the wrist to the antecubital fossa, is superficial and large in diameter, and is most easily cannulated at the distal flexor crease in the antecubital fossa.

6.5 Procedure

6.5.1 Standard Venous Cutdown Technique

1. Apply antimicrobial solution liberally to the skin surrounding the incisional area.
2. Establish a sterile field by placing drapes around the incisional area.
3. Apply a tourniquet proximal to the planned cutdown site to maximize visualization of vein to be cannulated.
4. Inject local anesthetic to raise a small (0.5 cm) wheal using 25- or 27-gauge needle and then insert the tip of the needle through wheal to infiltrate skin superficial to the artery with approximately 4 mL of anesthetic.
   - Injection of local anesthetic into the vessel may precipitate arrhythmia, so draw back on the plunger prior to infiltration to ensure the tip of the needle is not inside the vessel.
5. Incise the skin with scalpel perpendicular to the course of the vein through all cutaneous layers until subcutaneous fat is visualized (Fig. 6.2).
   - Some practitioners prefer using a longitudinal incision to reduce the risk of transecting neurovascular structures, but this may not produce sufficient exposure of vein.
6. Using a curved hemostat or gloved finger, bluntly dissect the subcutaneous tissue to isolate and mobilize approximately 2–3 cm of the vein (Fig. 6.3).
   - A small self-retaining retractor or tissue spreader can be used in this step to improve visualization of vein if desired
7. Pass suture under the vein distal to the planned venous puncture site using hemostat to stabilize the vein and tie the suture over the vein (Fig. 6.4).
8. Pass a second suture under the vein proximal to the planned venous puncture site using hemostat (Fig. 6.5).
   - This step enables increased visualization, vessel control, and hemostasis during incision.
   - Leave the ends of both sutures long to facilitate maneuvering the vein.
9. Incise one-half to one-third of the diameter of the vein using a scalpel or iris scissors held at a 45° angle to the vessel (Fig. 6.6).
10. Grasping the proximal edge of the incision with a hemostat to apply counter traction (in a distal direction), insert the tip of the catheter into the venous incision (Fig. 6.7).
    - Do not force the catheter if it does not easily advance.
    - Catheter can be introduced directly through the skin incision or via skin puncture adjacent to the skin incision.
    - If the catheter lacks a tapered tip, cut the distal end of the cannula at a 45° angle to fashion a beveled tip.
11. Thread catheter into vein (Fig. 6.8).
12. Aspirate any air which may have entered the cannula during insertion.
13. Connect hub of catheter to intravenous tubing.
14. Tie the proximal suture around the vein just proximal to the venous incision, encircling both the vein and the intraluminal cannula with the suture.
15. Remove tourniquet.
16. Secure the catheter hub to the skin using nylon (4.0) sutures as follows. Take a 0.5 cm bite of skin under the catheter hub with the suture needle, tie several knots in the suture without pinching the skin, then tie a second set of knots around the hub of the catheter firmly.
17. Close the incision using nylon (4.0) sutures.
18. Dress the wound with appropriate self-adhesive sterile dressing or sterile gauze pads and adhesive tape.



Fig. 6.2 Incision of skin



Fig. 6.3 Mobilization of vein



Fig. 6.4 Distal ligature tied around vein



Fig. 6.5 Distal and proximal ligatures in place



Fig. 6.6 Incision of vein



Fig. 6.7 Catheterization of vein



Fig. 6.8 Catheter threaded into vein

6.5.2 "Mini-Cutdown" Technique

(Perform steps 1–6 from the "Standard Venous Cutdown Technique," above, and then proceed with the steps below.)

1. Puncture the vein using a standard over-the-needle venous catheter.
   - Catheter can be introduced directly through the skin incision or via skin puncture adjacent to the skin incision.
2. Thread catheter into the vein over the needle.
3. Remove and discard the needle.
4. Aspirate any air which may have entered the catheter during insertion.
5. Connect catheter to intravenous tubing.

(Continue with steps 15–18 from the "Standard Venous Cutdown Technique," above.)

6.5.3 Modified/Guide Wire Technique

(Perform steps 1–6 from the "Standard Venous Cutdown Technique," above, and then proceed with the steps below.)

1. Insert the blunt end of the guide wire into the incised vein.
2. While stabilizing the guide wire at its insertion site, thread the dilator and sheath assembly over the free end of the guide wire until it is approximately one inch from the skin.
3. Grasp the free end of the guide wire protruding from the tail end of the assembly.
   - If it does not protrude from the tail end of the assembly, the guide wire must be removed sufficiently from the artery to be securely grasped. It must protrude visibly from the tail end of the dilator throughout the subsequent process of threading the dilator into the vein.
   - Never let go of the guide wire during this step, as insertion of the dilator and sheath assembly can otherwise push the guide wire completely into the vein.
4. Holding it firmly near its tip, thread the assembly over the wire into vessel with a gentle back-and-forth twisting motion.
5. Holding the sheath securely in the vein, remove and discard the dilator and guide wire.
6. Aspirate any air which may have entered the sheath during insertion.
7. Connect sheath to intravenous tubing.
8. Remove tourniquet.
9. Secure the sheath to the skin.
10. Close the incision using nylon (4.0) sutures.
11. Dress the wound with appropriate self-adhesive sterile dressing or sterile gauze pads and adhesive tape.

6.6 Complications

- Hematoma
- Infection
- Sepsis
- Phlebitis
- Embolization
- Wound dehiscence

6.7 Pearls and Pitfalls

- Fluids are infused most quickly via short, large-bore catheters.
- If the line is inserted for slow infusion of intravenous drugs, catheter lumen size is relatively insignificant.
- In larger children and adults, intravenous plastic tubing, small-bore pediatric feeding tubes, and Silastic catheters may be used as infusion catheters.
- Threading a 10-gauge intravenous catheter or intravenous tubing directly into the incised vein achieves excellent flow rates.
- If difficulty is encountered while threading the catheter into the incised vein, ensure an appropriately sized catheter has been used and that the vessel lumen has been correctly identified and that no false passage has been created in the adventitia.
- As compared to the standard venous cutdown technique, the mini-cutdown technique is easier and also preserves the vein, permitting repeated catheterization if necessary.
- As compared to the standard venous cutdown technique, the modified/guide wire technique reduces procedure time and increases the likelihood of vein salvage in the event of vessel transection.

Selected Reading

1. Chappell S, Vilke GM, Chan TC, et al. Peripheral venous cutdown. J Emerg Med. 2006;31:411–6.
2. Klofas E. A quicker saphenous vein cutdown and a better way to teach it. J Trauma. 1997;43:985–7.
3. McIntosh BB, Dulchavsky SA. Peripheral vascular cutdown. Crit Care Clin. 1992;8:807–18.
4. Nocito A, Wildi S, Rufibach K, et al. Randomized clinical trial comparing venous cutdown with the Seldinger technique for placement of implantable venous access ports. Br J Surg. 2009;96:1129–34.
5. Shockley LW, Butzier DJ. A modified wire-guided technique for venous cutdown access. Ann Emerg Med. 1990;19:393–5.

Part II

Airway and Vascular Procedures

Bag-Valve-Mask Ventilation

7

Braden Hexom and Tatiana Havryliuk

7.1 Indications

- Hypoxia
- Hypoventilation/apnea
- Rescue maneuver if failed intubation

7.2 Contraindications

- Absolute
  - Inability to ventilate due to lack of seal (thick beard, deforming facial trauma)
  - Inability to ventilate secondary to complete upper airway obstruction
  - Active, adequate spontaneous ventilation
- Relative
  - Full stomach (aspiration risk)
  - After induction and paralysis during rapid sequence intubation (aspiration risk)

7.3 **Materials** (Fig. 7.1)

- Bag valve mask (BVM) with reservoir
- Oxygen connector tubing
- Nasal pharyngeal airway/oral pharyngeal airway
- Lubricant jelly



Fig. 7.1 BVM supplies: bag, mask, oral airways, nasopharyngeal airways, lubricant

---

B. Hexom, MD (✉)
Department of Emergency Medicine, Mount Sinai Hospital,
New York, NY, USA
e-mail: braden.hexom@mssm.edu

T. Havryliuk, MD
Department of Emergency Medicine, University of Colorado
Denver, Denver, CO, USA
e-mail: tatiana.havryliuk@ucdenver.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_7

7.4 Procedure

1. Position patient in "sniffing" position.
2. Open the airway with chin-lift/head-tilt or jaw thrust maneuvers.
3. Place airway adjuncts to maintain airway patency. Use oral airway (Fig. 7.2) in unconscious patients. Use nasal airway (Fig. 7.3) in semiresponsive patients.
4. Attach oxygen tubing to high-flow oxygen (15 L/min).
5. Place appropriately sized mask on patient's face covering the nose and mouth.
    - For one-handed technique (Fig. 7.4), use nondominant hand to make a "C" with index finger and thumb on top of the mask and form an "E" with the rest of the fingers using them to pull up on the mandible (E–C technique). Use the dominant hand to provide bag ventilations.
    - For two-handed (Fig. 7.5), two-person technique (preferred), make two semicircles with index fingers and thumbs of both hands on top of the mask and use the rest of the fingers to pull up on the mandible.
6. Consider the Sellick maneuver (cricoid pressure) to compress the esophagus against the cervical vertebrae, preventing gastric insufflation.
7. Ventilate patient providing reduced tidal volume breaths (500 mL) at a rate of 10–12 breaths per minute.
8. Give each breath gently over 1–1.5 s to avoid high peak pressures, avoiding gastric insufflation.
9. Prepare for definitive airway as dictated by the clinical scenario.



Fig. 7.2 (**a**–**c**) Oral airway insertion



Fig. 7.3 (**a**, **b**) Nasal airway insertion



Fig. 7.4 (**a**–**c**) One-handed seal technique



Fig. 7.5 Two-handed seal technique: (**a**) two semicircles, (**b**) alternative thumbs method

7.5 Complications

- Stomach inflation may lead to vomiting and aspiration.
- Increased positive thoracic pressure may cause decreased preload, worsening cardiac output, and/or hypotension.
- Hypoventilation (inadequate O_2 tidal volume, airway patency, or mask seal).

7.6 Pearls and Pitfalls

- Pearls
  - Use jaw thrust to open mouth for patients with possible cervical spine injury.
  - Use airway adjuncts whenever available, especially if prolonged BVM ventilation is anticipated.
  - Use lubricant jelly to insert nasal airway; do not insert in patients with severe facial trauma.
  - Mask should be placed on patient's face prior to attaching to bag.
  - Apply pressure to the bony part of the mandible only to avoid soft-tissue injury.
  - Provide just enough tidal volume to see a chest rise and deliver each breath gently over 1–1.5 s to prevent gastric insufflation.
  - Ensure good seal:
    - Select appropriate mask size.
    - Choose two-handed technique over one-handed, if possible.
    - Keep well-fitting dentures in place if present (and remove before intubation).
    - Lift the mandible toward the mask (as opposed to pushing the mask onto the face).
    - Rock the mask on face until no leak is present.
    - Apply K–Y jelly to beard to improve the seal.
- Pitfalls
  - Overcompression during the Sellick maneuver can compress the cricoid ring, preventing ventilation.
  - Cricoid pressure (Sellick maneuver) is not recommended during cardiac arrest resuscitation.
  - Difficult BVM ventilation: MOANS
    - *M*ask seal
    - *O*besity/obstruction
    - *A*ge
    - *N*o teeth
    - *S*tiff

Selected Reading

ECC Committee, Subcommittees and Task Forces of the American Heart Association. American heart association guidelines for cardiopulmonary resuscitation and emergency cardiovascular care. Circulation. 2010;122:S685–705.

Joffe AM, Hetzel S, Liew EC. A two-handed jaw-thrust technique is superior to the one-handed "EC-clamp" technique for mask ventilation in the apneic unconscious person. Anesthesiology. 2010;113:873–9.

Roberts JR, Hedges JR. Clinical procedures in emergency medicine. Philadelphia: Saunders Elsevier; 2010.

Walls RM, Murphy MF. Manual of emergency airway management. 3rd ed. Philadelphia: Lippincott Williams & Wilkins; 2008.

Awake Orotracheal Intubation

8

Benjamin M. Mahon, Justin Bennett, and Lars K. Beattie

8.1 Indications

- Urgent but not emergent endotracheal intubation is required in a patient who:
  - Is awake
  - Is currently protecting his airway
  - Is not a candidate for a supraglottic airway (LMA)
  - The patient
    - Is predicted to have a difficult airway
    - Has structural abnormalities of the airway
    - Will not tolerate a period of apnea
    - May lose his airway (anaphylaxis, angioedema, traumatic airway)
- Patients requiring urgent but not emergent intubation in whom paralytics are contraindicated (i.e., allergies, myasthenic crisis)

8.2 Contraindications

- Absolute
  - Surgical airway indicated
  - Emergent crash airway needed
  - Obtunded patient
  - Allergies to medications needed (lidocaine, glycopyrrolate)
- Relative
  - Inability to maintain airway or tolerate secretions

8.3 Materials and Medications

- Suctioning equipment
- Intravenous access equipment, cardiac monitor, pulse oximetry, blood pressure cuff
- 4 % lidocaine solution
- 2 % viscous lidocaine jelly
- Nebulizer
- Mucosal atomization device
- 4×4 gauze
- Tongue depressor
- Glycopyrrolate/atropine
- Sedation: ketamine, propofol, Versed, and/or fentanyl
- Intubation equipment
- Backup emergency airway adjuncts
- Bag valve mask
- Laryngoscope, fiber optics, oral airway, etc.

8.4 Procedure

1. Preparation
   (a) Establish IV access.
   (b) Place the patient on a cardiac monitor with continuous pulse oximetry.
   (c) Keep backup RSI emergency airway medication and equipment at the bedside.
2. Administer 0.2–0.4 mg of intravenous glycopyrrolate (or a small dose (0.5–1 mg) of atropine to decrease secretions) 15 min prior to procedure.
3. Nebulize 2 mL of 4 % lidocaine with oxygen at 5 l O2 per minute to anesthetize the pharynx (Fig. 8.1).

B.M. Mahon, MD
Ponciana Medical Center,
Kissimmee, FL, USA
e-mail: drfaust2k9@aol.com

J. Bennett, MD
Department of Emergency Medicine, Wake Forest University
School of Medicine, Winston-Salem, NC, USA
e-mail: jubennet@wakehealth.edu

L.K. Beattie, MD, MS (✉)
Department of Emergency Medicine, University of Florida,
Gainesville, FL, USA
e-mail: lars.beattie@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_8

4. Use Yankauer suction (with the patient's assistance) to dry out the mouth as much as possible. Dabbing the tongue with gauze can assist in this step.
5. Continue preoxygenation.
6. Immediately after the nebulized solution is applied, give the patient a "lidocaine lollipop" (Fig. 8.2).
    - (a) A 2 ml dollop of 2 % viscous lidocaine is to be placed on the end of a tongue depressor and is given to the patient to place in his mouth (like a lollipop).
    - (b) Have the patient copiously gargle, then swallow the viscous lidocaine.
7. Using a mucosal atomizer, spray 2 ml of 4 % lidocaine in the posterior oropharynx and as far down toward the glottis as possible (Figs. 8.3, 8.4, and 8.5).
8. Sedation
    - (a) It is feasible to proceed with the awake intubation in an un-sedated, wide awake but cooperative patient.
    - (b) Sedation can be initiated using institutional preferences, but some options include:
        - (i) Midazolam 2 mg IV
        - (ii) Ketamine 1 mg/kg IV
        - (iii) Propofol 1 mg/kg IV
        - (iv) Ketofol (ketamine and propofol both at concentrations of 10 mg/ml, 5 ml of each mixed in a 10 cc syringe) titrated at 1–3 ml aliquots
    - (c) More atomized lidocaine can be provided prior to endotracheal tube (ETT) passage, but one must be aware of the upper lidocaine dose for your patient.
    - (d) Adequate anesthesia is confirmed by the absence of a gag reflex upon direct palpation (Fig. 8.6).
9. Intubation, induction, and gentle direct laryngoscopy can be performed at this point to place the ETT (Fig. 8.7).
    - (a) Induction (if no prior sedation) and paralytic agents should be available to immediately administer after ETT placement.
    - (b) Thorough discussions on intubation techniques can be found in other chapters in the atlas.



Fig. 8.1 Nebulization of 4 % lidocaine



Fig. 8.2 Lidocaine lollipop



Fig. 8.3 Mucosal atomizer attached to syringe



Fig. 8.4 Pushing syringe plunger atomizes lidocaine



Fig. 8.5 Atomized lidocaine being administered to the posterior pharynx



Fig. 8.6 (**a**, **b**) Adequately anesthetized awake patient with laryngoscopic view of epiglottis



Fig. 8.7 (**a**) Final lidocaine atomization of deep structures and trachea, (**b**) intubation using a lighted stylet

8.5 Pearls and Pitfalls

- Pearls
  - Steps 3–7 should be done successively and as quickly as possible, to capitalize on the short half-life of lidocaine.
  - Simultaneous preoxygenation and anesthetization can be achieved by nebulizing the 4 % lidocaine through a face mask.
  - If the patient has been sedated, soft restraints may help prevent the patient from inadvertently grabbing the tube or your intubating equipment.
  - A nasotracheal intubation can be performed by simply anesthetizing the nares through which the ETT will be placed using lidocaine jelly and/or atomized lidocaine.
- Pitfalls
  - Failure to prepare all equipment beforehand may extend the procedure beyond the lidocaine half-life.
  - The toxic dose of lidocaine is 300 mg or 3–5 mg/kg. The dosages listed are intended for a 70 kg patient and yields a total dose of 280 mg (4 mg/kg). This dose may need to be decreased in smaller individuals.

Selected Reading

Agro F, Hung OR, Cataldo R, Carassiti M, Gherardi S. Lightwand intubation using the Trachlight: a brief review of current knowledge. Can J Anaesth. 2001;48(6):592–9.

Rhee KY, Lee JR, Kim J, Park S, Kwon WK, Han S. A comparison of lighted stylet (Surch-Lite) and direct laryngoscopic intubation in patients with high Mallampati scores. Anesth Analg. 2009;108(4):1215–92.

Walls RM, Murphy MF. Manual of emergency airway management. 3rd ed. Philadelphia: Lippincott Williams and Wilkins, a Wolters Kluwer Business; 2008. Chap 11.

9 Rapid-Sequence Intubation

Ram A. Parekh

9.1 Indications

- Failure to oxygenate
- Failure to ventilate
- Unable to protect airway patency or reflexes
- Projected clinical course deterioration

9.2 Contraindications

- Absolute
  - Complete upper airway obstruction
  - Significant facial and airway trauma with loss of landmarks for orotracheal intubation
- Relative
  - Anticipated difficult intubation
    - Not an absolute contraindication.
    - Patient scenario requires a careful preintubation assessment and plan.
    - Consider an “awake” intubation.
    - Consider alternative airway adjuncts (e.g., extraglottic devices, video laryngoscopy, laryngeal mask airway [LMA]).
  - Induction or paralytic agent-specific contraindications given clinical circumstances
    - Caution: induction agents that lower blood pressure in hypotensive patients
    - Caution: succinylcholine in potentially hyperkalemic patients
  - Crash airway
    - Apneic, arrest, and periarrest situation

9.3 Materials and Medications

- Laryngoscope with appropriate blade (choice based on proceduralist’s preference and patient anatomy) (Fig. 9.1)
- Intubating stylet
- Endotracheal tubes (ETTs)
- Syringe, 10 mL (to inflate ETT cuff)
- Surgilube
- Suction catheter
- Oral and nasal airways (Fig. 9.2)
- Ambu bag and mask attached to oxygen source
- Induction, pretreatment, and paralytic agents
- ETT confirmation device—EZ capnometry, quantitative end-tidal carbon dioxide concentration ($EtCO_2$) detection

---

R.A. Parekh, MD
Department of Emergency Medicine,
Icahn School of Medicine at Mount Sinai,
Elmhurst Hospital Center, Elmhurst, NY, USA
e-mail: ram.parekh@mssm.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_9


Mac blades
Laryngoscope handle
Miller blades

Fig. 9.1 Laryngoscope and blades


Intubating stylet
Endotracheal tube
Yankauer suction catheter
Nasopharyngeal airway
Surgilube
Oropharyngeal airway
Syringe, 10cc

Fig. 9.2 Oral and nasal airways

9.4 Procedure

1. Preparation
    - Thoroughly assess patient for difficulty of intubation (Fig. 9.3).
    - Develop fallback plans for failed intubation attempt.
    - Establish at least one, but preferably two, secure intravenous (IV) lines.
    - Place on cardiac monitor with pulse oximetry, blood pressure monitoring, and continuous capnography.
    - Yankauer suction device attached to suction, suction on.
    - Pharmacological agents, drawn and labeled.
    - Laryngoscope and blades tested to ensure proper functioning of light source.
    - Desired ETT size, prepared for intubation:
        - Intubating stylet in position (tip at eye of ETT)
        - 10-mL syringe attached to ETT
        - ETT configured per proceduralist's preference (e.g., hockey stick, curved)
        - Cuff tested for air leak
2. Preoxygenation
    - Administer high-flow oxygen for 3–5 min (Fig. 9.4).
        - Nitrogen is exchanged for O_2 in the functional residual capacity of the lungs.
        - Establishes oxygen reservoir within lungs (primarily), blood, and body tissue.
        - Also known as nitrogen "washout."
    - This can be done using:
        - Non-rebreather masks—delivers 65–70 %
            - Difficult intubation not anticipated
        - Well-fitting bag-valve-masks (without positive-pressure ventilation)—delivers greater than 90 % oxygen (Fig. 9.5)
        - Noninvasive positive-pressure ventilation (NIPPV)—delivers 100 % oxygen
            - Consider NIPPV in high-risk patients with moderate to severe shunt physiology.
3. Pretreatment
    - Administer pharmacological agents to mitigate adverse physiological effects of intubation, induction, and paralysis, which may be undesirable in certain clinical circumstances (Table 9.1).
4. Induction and paralysis
    - Administer a rapidly acting induction agent to produce rapid loss of consciousness via IV push (Table 9.2).
    - Immediately follow induction agent with a neuromuscular-blocking agent via IV push (Table 9.3).
5. Positioning
    - If no cervical spine injury suspected, place the patient in the "sniff" position (Fig. 9.6):
        - Flex neck
        - Extend head
    - Ideally, the patient's pinna will be at the level of the sternum.
6. Direct laryngoscopy (see Chap. 10)
7. Proof of placement
    - Visualize ETT passing vocal cords
    - Confirm tube placement via $EtCO_2$:
        - Qualitative detection device—EZ Cap
        - Quantitative continuous $EtCO_2$ waveform on monitor (preferred) (Fig. 9.7)
    - Auscultation of breath sounds:
        - Lung fields bilaterally
        - Epigastric region (ensuring no breath sounds in the stomach)
8. Postintubation management
    - Secure ETT (Fig. 9.8)
    - Initiate mechanical ventilation.
    - Postintubation sedation and analgesia.
    - Postintubation chest x-ray.


Difficulty of intubation based on mallampati classification
Class I
Class II
Class III
Class IV

Fig. 9.3 Assess patient for difficulty of intubation



Fig. 9.4 *FaO2* fractional concentration of alveolar oxygen, *SaO2* arterial oxygen saturation, *Ve* expired volume per minute



Fig. 9.5 Preoxygenation materials

Table 9.1 Pretreatment: pharmacological agents used to mitigate adverse physiological effects of intubation, induction, and paralysis

Agent	Dose (IV)	Indication
Lidocaine	1.5 mg/kg Rapid push	Use in tight brain to attenuate ICP increase from laryngoscopy/intubation; use in tight lungs to blunt bronchospastic response
Fentanyl	1–3 mcg/kg Slow push	Use in tight brain, tight heart, and tight vessels to blunt reflex sympathetic response to laryngoscopy

ICP intracranial pressure

Table 9.2 Induction: rapidly acting induction agents used to produce rapid loss of consciousness

Agent	Dose (IV) (mg/kg)	Onset (sec)	Duration (min)
Midazolam	0.2–0.3	60–90	15–30
Etomidate	0.3	15–45	3–12
Thiopental	3	<30	5–10
Ketamine	1.5–2.0	45–60	10–20
Propofol	1.5	15–45	5–10

Table 9.3 Paralysis: neuromuscular-blocking agents administered immediately after induction agent

Agent	Dose (IV)	Onset (sec)	Duration (min)
Succinylcholine	1.5 mg/kg	45	6–10
Rocuronium	1.0 mg/kg	60–75	40–60
Vecuronium	0.01 to prime, then 0.15 mg/kg	75–90	60–75

Fig. 9.6 Patient in the "sniff" position. *OA* oral axis, *LA* laryngeal axis, *PA* pharyngeal axis


Chin lift and jaw thrust
PA
OA
LA
Atlanto-occipital extension
Neck flexion



Fig. 9.7 EtCO$_2$, end-tidal carbon dioxide concentration: *a* Qualitative detection device—EZ Cap, *b* quantitative continuous EtCO$_2$ waveform on monitor


Anchor Fast
Tube Tamer

Fig. 9.8 Equipment used to secure ETT

9.5 Complications

- Esophageal intubation
- Right mainstem intubation
- Pneumothorax from laryngeal trauma
- Aspiration
- Dental trauma
- Vocal cord injury
- Hypotension
  - Induction agent
  - Decreased venous return from positive pressure
  - Pneumothorax
- Hyperkalemia (succinylcholine used in mildly hyperkalemic patient)
- Iatrogenically obstructed airway
- Failure to intubate

9.6 Pearls and Pitfalls

- Utilization of oral and nasal airways will greatly increase the ease of preoxygenation and reoxygenation.
- Inadequate preoxygenation will cause premature desaturation, decreasing time for intubation.
- Suboptimal patient positioning can prevent vocal cord visualization during direct laryngoscopy.
- Consider alternative airway devices before intubation to have a plan in place if a difficult airway is encountered.
- Underdosing induction or paralytic agent will prevent adequate time to perform procedure or create patient discomfort.
- Inappropriately sized McIntosh laryngoscopic blades.
  - Too small—more difficulty in moving tongue and epiglottis out of way for vocal cord visualization
  - Too large—easier to overshoot and go past vocal cords into the esophagus
- Excessive cricoid pressure (Sellick maneuver) may lead to disrupted laryngoscopic view and difficulty passing the ETT.
  - Disrupted view: readjust larynx using dominant hand to allow cord visualization.
  - Difficulty passing ETT: ask for release of some cricoid pressure to allow for ETT passage.
- Inadequate postintubation sedation and analgesia, especially when long-acting paralytics are used.
- Acidic gastric contents can cause CO_2 qualitative capnometry to change to yellow, falsely indicating tracheal placement of the ETT.

Selected Reading

Walls R, Murphy M. Manual of emergency airway management. Philadelphia: Lippincott Williams & Wilkins; 2008.

Weingart SD. Preoxygenation, reoxygenation, and delayed sequence intubation. J Emerg Med. 2011;40:661–7.

Direct Laryngoscopy

10

Bharath Chakravarthy and Weston Seipp

10.1 Indications

- Orotracheal intubation
  - Maintenance of oxygenation/ventilation
  - Airway protection
- Visualization of laryngeal anatomy
- Foreign body retrieval

10.2 Contraindications

- Absolute
  - None
- Relative
  - Presumed difficult airway
    - Anatomical limitations
      - Small oral opening (less than three of the patient's fingers)
      - Small mandible (hyomental distance less than three fingers)
      - Hyoid-thyroid distance (less than two fingers)
    - Clinical limitations
      - Patient with unstable cervical spine
      - Patient with multiple facial or neck trauma
      - Patient with history of tracheal stenosis, irradiation, or history of tracheal mass or surgery

---

B. Chakravarthy, MD, MPH (✉)
Department of Emergency Medicine,
University of California Irvine,
Orange, CA, USA
e-mail: bchakrav@uci.edu

W. Seipp, MD
Department of Emergency Medicine,
University of California Irvine Medical Center,
Orange, CA, USA

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_10

10.3 Materials and Medications (Fig. 10.1)

- Laryngoscope handle
- Laryngoscope blade with light
  - Macintosh blade (“Mac” or “curved blade”)
  - Miller blade (“straight blade”)
- Bag valve mask attached to 100 % O_2 source
- Endotracheal tube (ETT)
- 10-mL syringe
- Yankauer suction
- End-tidal CO_2 ($EtCO_2$) monitor (colorimetric or quantitative)
- McGill forceps (for foreign body retrieval)
- Postintubation chest radiograph



Fig. 10.1 Basic laryngoscopy supplies. *Clockwise from top left*: Yankauer suction, Miller Blades, endotracheal tube, 10-mL syringe, laryngoscope handle, Macintosh blades, and McGill forceps

10.4 Procedure

1. Check the laryngoscope handle and blades to ensure that the light is functioning.
2. Choose the appropriate blade based on patient size.
   (a) The Macintosh or Miller 3 size is appropriate for the majority of adults, and a 4 can be used for a larger body habitus.
   (b) The Macintosh blade is generally preferred in adults owing to increased space for ETT passage [1].
   (c) The Miller blade may be preferable in cases in which the patient has limited mouth opening (owing to its smaller vertical height), or in which the airway is particularly floppy (such as in infants and children) [1].
3. Position the patient (Fig. 10.2).
   (a) Raise the bed so that the patient's oral opening is at the level of the xiphoid process of the laryngoscopist.
   (b) The optimal laryngeal view is obtained in the neck flexion/head extension or "sniffing" position. To achieve this, place towels under the patient's occiput to raise it approximately 6–9 cm [2].
   (c) If patient is in cervical spine precautions, then an assistant must hold the cervical spine in midline immobilization throughout the laryngoscopy; elevation of the occiput is therefore contraindicated.
4. Provide 100 % O_2 via face mask to preoxygenate the patient before laryngoscopy.
5. After ensuring adequate anesthesia and neuromuscular blockade (if performing laryngoscopy for intubation), perform the scissor technique to open the patient's mouth and to lift the tongue base from the glottic opening.
6. Macintosh blade insertion (Fig. 10.3).
   (a) Insert the laryngoscope into the patient's mouth, starting from the right side, and slowly advance into the oropharynx, using the blade's vertical flange to "sweep" the tongue to the left and away from the glottic opening.
   (b) Advance the blade along the tongue toward the tongue base, until the epiglottis and posterior arytenoids are viewed.
   (c) In order to expose the cords, insert the Macintosh blade into the vallecula, which is the potential space anterior to the epiglottis and posterior to the tongue base. This will act as a fulcrum and raise the epiglottis, exposing the vocal cords.
   (d) To further expose the cords and/or expose the vallecula, exert force outward at a 45° angle to the patient. Do not "rock" the laryngoscope because this may cause injury to the teeth.
7. Miller blade insertion (Fig. 10.4).
   (a) Insert the blade into the right side of the mouth and slowly advance along tongue toward the tongue base. The Miller blade does not have a flange for isolating the tongue, and thus the Macintosh may be preferable in patients with large tongues.
   (b) Advance the blade along the right side of the tongue until the epiglottis and posterior arytenoids are visible.
   (c) In contrast to the Macintosh blade, the Miller blade is used to directly isolate the epiglottis and expose the vocal cords. Using the tip of the Miller, move the epiglottis anteriorly to expose the vocal cords.
   (d) As with the Macintosh, exert force outward at a 45° angle to the patient to increase the view of vocal cords. Do not "rock" the laryngoscope because this may cause injury to the teeth.
8. Assessing the glottic view (Fig. 10.5).
   (a) With the epiglottis either directly or indirectly lifted from the glottic opening, assess the Cormack-Lehane laryngeal view grade.
      (i) Grade I—view of entire laryngeal opening, including cords
      (ii) Grade II—view of posterior laryngeal cartilages
      (iii) Grade III—visualization of epiglottis only
      (iv) Grade IV—no structures visualized
   (b) A lower grade (higher quality, better) view is predictive of intubation success [3].
   (c) In the event of a higher grade view, the operator may request airway adjuncts, such as a bougie.
9. Improving the glottic view [4].
   (a) With the laryngoscope in the desired position, it is possible to improve the glottic view by exerting backward pressure on the thyroid cartilage either with the operator's right hand (bimanual laryngoscopy) or with an assistant applying BURP (backward-upward-rightward pressure) (Fig. 10.5a).
   (b) Backward pressure increases the vertical distance between the epiglottis and the posterior cartilages, thereby increasing the likelihood of vocal cord visualization.
10. Passing the ETT (Fig. 10.6).
    (a) With the optimal view of the cords obtained, pass the ETT from the right corner of the mouth through the vocal cords, to a depth of 21 cm at the incisors in females and 23 cm in males.
    (b) Inflate the ETT cuff with approximately 5 cc of air until the pilot balloon is firm to touch.
11. After completing intubation or after completion of laryngoscopy, slowly remove the blade from the mouth, taking care to avoid dental or lip trauma.
12. Attach the capnography device to the ETT tube to ensure $EtCO_2$ return.
    (a) Colorimetric devices will turn from purple to yellow in the presence of $EtCO_2$.
    (b) Quantitative devices will return a CO_2 waveform.
13. Attach the ETT to ventilator or bag-valve-mask connected to an oxygen source.

14. Auscultate breath sounds in both lung fields and ensure absence of breath sounds over the epigastrium (which could signify esophageal intubation).
15. Obtain a postintubation chest x-ray to ensure no right mainstem intubation or pneumothorax.


a
Trachea
∞
Incorrect
b
Tongue
Laryngoscope
Epiglottis
A
B
∞
Pillow
Correct

Fig. 10.2 Visualization axis and sniffing position: (**a**) The patient's occiput is not elevated and the neck is not in flexion, thereby creating a steep visual axis, (**b**) the occiput is correctly elevated 6–9 cm, placing the patient in sniffing position and allowing the visual axis to align with the airway axis



Fig. 10.3 Macintosh blade insertion. The blade is inserted into the vallecula, which raises the epiglottis and exposes the glottic opening


Straight blade placement
Epiglottis

Fig. 10.4 Miller blade insertion. The blade is used to elevate the epiglottis directly, exposing the glottic opening


a
b
Glossoepiglottic folds (median and lateral)
Epiglottis
Vocal chords (true chords)
Ventricular fold (false chords)
Aryepiglottic fold
Piriform fossa
Posterior cartilages
Esophagus
Interarytenoid notch

Fig. 10.5 (**a**) Bimanual laryngoscopy. The force on the neck is opposite the direction of lift by the laryngoscope, (**b**) laryngoscopy view, (**c**) Cormack and Lehane

Fig. 10.5 (continued)


Laryngoscopy view: cormack and lehane
Grade I
Grade II
Grade III
Grade IV



Fig. 10.6 (**a**) Insert the laryngoscope into the mouth, (**b**) sweep the tongue to the left, (**c**) advance the laryngoscope until the epiglottis is visible, and insert the blade into vallecula to expose the cords. When using the Miller blade, insert the blade until the epiglottis is seen. Slide the blade under the epiglottis and lift to expose the cords

10.5 Complications [3, 5]

- Common (1–4 %)
  - Esophageal intubation—*can be fatal if unrecognized*
  - Mainstem bronchus intubation
  - Tachycardia
  - Aspiration
  - Hypotension
- Uncommon (<1 %)
  - Dental/oral trauma
  - Oropharyngeal edema or bleeding
  - Laryngospasm
  - Dysrhythmia
  - Pneumothorax
  - Cardiac arrest

10.6 Pearls and Pitfalls

- Pearls
  - Positioning is of key importance—all patients with a stable cervical spine should be placed in the “sniffing” position to maximize view.
  - Consider the “ramping” position in obese patients with stable cervical spines—elevation of the head and shoulders allows redundant tissue to fall and gives an improved glottic view.
  - Always have suction readily available to remove blood, vomitus, or edema.
  - If structures are not readily visible, withdraw the blade gradually because it is common to insert the blade too deep.
- Pitfalls
  - “Rocking” the laryngoscope instead of lifting outward
  - Failure to recognize esophageal intubation
  - Failure to evaluate postintubation chest x-ray

References

1. Hagberg CA. Benumof’s airway management. Maryland Heights, MO: Mosby; 2007. p. 363–5.
2. Park SH, Park HP, Jeon YT, Hwang JW, Kim JH, Bahk JH. A comparison of direct laryngoscopic views depending on pillow height. J Anesth. 2010;24:526–30.
3. Martin LD, Mhyre JM, Shanks AM, Tremper KK, Kheterpal S. 3,423 emergency tracheal intubations at a university hospital: airway outcomes and complications. Anesthesiology. 2011;114:42–8.
4. Levitan RM, Kinkle WC, Levin WJ, Everett WW. Laryngeal view during laryngoscopy: a randomized trial comparing cricoid pressure, backward-upward-rightward pressure, and bimanual laryngoscopy. Ann Emerg Med. 2006;47:548–55.
5. Walls RM, Brown CA 3rd, Bair AE, Pallin DJ, NEAR II Investigators. Emergency airway management: a multi-center report of 8937 emergency department intubations. J Emerg Med. 2011;41:347–54.

Laryngeal Mask Airway

11

Sohan Parekh

11.1 Indications

- Rescue device in a failed intubation
- Initial device in a predictably difficult airway
- Temporizing airway prior to definitive endotracheal intubation or surgical airway

11.2 Contraindications

- Absolute
  - Inadequate mouth opening
- Relative
  - Neck trauma/injury/radiation
  - High risk of aspiration

S. Parekh, MD
Department of Emergency Medicine,
University of Texas at Austin Dell Medical School,
Austin, TX, USA

Department of Emergency Medicine,
University Medical Center Brackenridge,
Austin, TX, USA
e-mail: sohan.parekh@gmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_11

11.3 Types (Fig. 11.1)



Fig. 11.1 Types of laryngeal mask airway: (**a**) LMA Unique, (**b**) LMA Classic Excel, (**c**) LMA Fastrach

11.4 Materials and Medications

- Appropriately sized laryngeal mask airway (LMA; LMA Unique/LMA Classic Excel/LMA Fastrach) and corresponding syringe (Table 11.1)
- Surgilube
- Bag valve mask
- Continuous end-tidal CO_2 ($EtCO_2$) or colorimetric $EtCO_2$ detector
- 8-mm or smaller endotracheal tube (ETT) (for Fastrach intubating LMA only)

Table 11.1 Laryngeal mask airway sizing

Size	Patient weight (kg)	Maximum cuff inflation volume (mL)	LMA product availability
1	<5	4	Unique
1½	5–10	7	Unique
2	10–20	10	Unique
2½	20–30	14	Unique
3	30–50	20	Unique, Classic Excel, Fastrach
4	50–70	30	Unique, Classic Excel, Fastrach
5	70–100	40	Unique, Classic Excel, Fastrach
6	>100	50	Unique

LMA laryngeal mask airway

11.5 Procedure

11.5.1 LMA Unique or Classic Excel

1. If using a reusable LMA Classic Excel, ensure that it is sterile and inspect it for any damage or wear.
2. Tightly deflate the cuff using a syringe such that it forms a spoon shape (Fig. 11.2).
3. Lubricate the posterior surface of the LMA with sterile lubricating jelly.
4. Stand behind the patient at the head of the bed as in direct laryngoscopy.
5. Place the patient's head in the sniffing position and ensure proper induction and paralysis.
6. Hold the LMA with the index finger of the dominant hand positioned at the juncture of the tube and cuff (Fig. 11.3).
7. Widely open the mouth with the nondominant hand and insert the LMA with the flattened tip flush with the palate.
    - Ensure that the tip of the device does not fold over during insertion.
8. Using the index finger, push the LMA along the curvature of the hard and soft palate (Fig. 11.4).
9. Continue to insert the LMA into the hypopharynx until resistance is felt. (At this point the tip of the LMA is in the esophagus.)
10. Stabilize the tube with the nondominant hand and remove index finger of the dominant hand from the LMA.
11. Inflate the cuff of the LMA to at least half of the maximum value using a syringe.
    - The LMA might move slightly outward during cuff inflation as the LMA positions itself in the hypopharynx.
12. Confirm placement and adequate gas exchange with continuous $EtCO_2$ capnography or colorimetry.

Fig. 11.2 Deflate the laryngeal mask airway (LMA) cuff using a syringe





Fig. 11.3 Hold the LMA with the index finger positioned at the juncture of the tube and the cuff



Fig. 11.4 Use the index finger to guide the LMA along the hard and soft palate

11.5.2 LMA Fastrach

1. If using a reusable LMA Fastrach, ensure that it is sterile and inspect it for any damage or wear.
2. Tightly deflate the cuff using a syringe such that it forms a spoon shape.
3. Lubricate the posterior surface of the LMA with sterile lubricating jelly.
4. The LMA Fastrach may be inserted from any position with respect to the patient's head.
5. Position the patient's head in the neutral position. Do not extend the head.
6. Widely open the mouth with the nondominant hand.
7. Holding the handle of the LMA Fastrach, insert the device into the mouth, placing the deflated cuff flush with the superior palate.
   - Distribute the lubricant over the superior palate using a side-to-side motion to allow for easier insertion.
   - Ensure that the tip of the device does not fold over during insertion.
8. Using the handle, gently advance the LMA Fastrach directly into the oropharynx until the curved portion of tube comes into the contact with the patient's chin (Fig. 11.5).
9. At this point use the handle to rotationally advance the device further into the oropharynx following the natural curvature of the palate and posterior pharynx (Fig. 11.6).
   - Do not initiate any rotation until the tube is in contact with the patient's chin.
10. Once resistance is felt, inflate the cuff of the device to at least half of the maximum value using a syringe.
    - Note that the tube is directed slightly caudally when properly inserted.
    - Confirm placement and adequate gas exchange with $EtCO_2$ capnography or colorimetry.



Fig. 11.5 Using the handle, insert the LMA Fastrach such that the posterior surface is in contact with the superior palate



Fig. 11.6 Once the tube is in contact with the chin, use the handle to rotationally advance the device further into the oropharynx

11.5.3 Endotracheal Intubation through the LMA Fastrach

1. Ensure that the ETT will pass freely in the LMA.
2. Lubricate the cuff of the ETT.
3. Firmly hold the handle of the LMA Fastrach with the nondominant hand and insert the ETT to a depth of 15 cm (Fig. 11.7), which places the ETT tip at the point of emergency from LMA Fastrach.
    - Ensure that the tube does not pass beyond 15 cm at this point.
4. Using the handle of the LMA Fastrach, draw the device outward in order to displace the larynx slightly to accommodate insertion of the ETT (Fig. 11.8).
    - Use a lifting rather than a levering motion.
5. Carefully advance the ETT slightly further. If no resistance is felt, continue with insertion of the ETT (Fig. 11.9).
6. Confirm placement and adequate gas exchange with $EtCO_2$ capnography or colorimetry.
7. Once successful confirmation of intubation is established, deflate the cuff pressure on the LMA Fastrach.



Fig. 11.7 While holding the handle of the LMA, insert the endotracheal tube (*ETT*) to the 15-cm mark



Fig. 11.8 Lift the handle outward to open the glottis for the ETT



Fig. 11.9 If no resistance is felt during further insertion of the ETT, the ETT may be fully advanced

11.5.4 Removing the LMA Fastrach after Successful Intubation

1. The LMA Fastrach need not be removed immediately, but if this is desired, first adequately oxygenate the patient and then disconnect the patient from the circuit.
2. Remove the airway connector from the proximal end of the ETT.
3. Ensure that the cuff of the LMA Fastrach is entirely deflated.
4. Stabilize the ETT with the nondominant hand, and using the dominant hand, gently ease the LMA Fastrach out by rotating the handle caudally (Fig. 11.10).
5. Once the tube of the LMA Fastrach reaches the proximal end of the ETT, use the stabilizer rod to maintain the position of the ETT while continuing to remove the LMA Fastrach using the handle (Fig. 11.11).
6. After the cuff of the LMA Fastrach has been fully removed from the oral cavity, release the stabilizer rod and ensure stability of the ETT by grasping it distally at the mouth with the nondominant hand (Fig. 11.12).
7. Continue to ease the LMA Fastrach out from around the ETT, ensuring that the pilot balloon and inflation line of the ETT cuff pass through the device (Fig. 11.13).
    - Take care not to rupture the pilot balloon or tear the inflation line of the ETT.
8. Replace the airway connector on the proximal end of the ETT and reconnect the patient to the circuit.



Fig. 11.10 Rotate the handle caudally to gently ease the LMA Fastrach out of the pharynx



Fig. 11.11 Use the stabilizer rod to allow for further removal of the LMA Fastrach



Fig. 11.13 Carefully pass the pilot balloon and inflation line of the ETT cuff through the tube of LMA Fastrach as it is removed



Fig. 11.12 Once the cuff of the LMA Fastrach is out of the mouth, grasp the ETT distally and remove the LMA entirely

11.6 Complications

- Aspiration with resulting pneumonitis
- Ineffective seal resulting in insufficient ventilation
- Coughing, bucking, or breath holding
  - Ensure that the patient is adequately sedated.

11.7 Pearls and Pitfalls

- Cricoid pressure can push the tip of the LMA out of the esophagus and prevent optimal placement.

Selected Reading

Barata I. The laryngeal mask airway: prehospital and emergency department use. Emerg Med Clin North Am. 2008;24:1069–83.

LMA classic LMA flexible LMA classic single use LMA flexible single use instruction manual. Victoria: The Laryngeal Mask Company Limited; 2010.

LMA fastrach LMA fastrach single use instruction manual. Victoria: The Laryngeal Mask Company Limited; 2010.

Pollack CV. The laryngeal mask airway: a comprehensive review for the emergency physician. J Emerg Med. 2001;20:53–66.

Walls RW, Murphy MF, editors. Manual of emergency airway management. 3rd ed. Philadelphia: Lippincott Williams & Wilkins; 2008.

12 Combitube

Clint Masterson

12.1 Indications

- Need for ventilation and oxygenation in an unconscious, unresponsive, or paralyzed patient
- Rescue airway needed after failed intubation

12.2 Contraindications

- Absolute
  - Awake, responsive patient
  - Intact gag reflex
  - Known esophageal disease
  - Ingestion of caustic substances
  - Child (no Combitubes are made for children)
- Relative
  - D50 or naloxone about to be given
  - Facial trauma

12.3 Materials

- Combitube sized based upon height (Fig. 12.1)
  - >5 ft—size 41 French (cuff inflation 15 and 100 mL)
  - >4 ft to<5.5 ft—size 37 French (cuff inflation 12 and 85 mL)



Fig. 12.1 (**a**, **b**) Combitube equipment

C. Masterson, MD
Department of Emergency Medicine,
Mayo Clinic Health System in Fairmont,
Fairmont, MN, USA
e-mail: clint@clintm.us

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_12

12.4 Procedure

1. Test both balloons and cuffs for leaks as one would an endotracheal tube (ETT).
2. Open up the airway.
   - (a) Use a laryngoscope to move the tongue and open the oropharynx.

     OR
   - (b) Use the left hand to elevate the chin, elevating the tongue and pharyngeal tissue.
3. Insert Combitube blindly into the oropharynx until the teeth lie between the two black bands on the proximal Combitube (Fig. 12.2).
4. Inflate the proximal blue cuff until air pressure is produced or the manufacturer-recommended pressure is reached.
   - (a) 85 mL for 37 French Combitube
   - (b) 100 mL for 41 French Combitube
5. Identify placement and attach to oxygen.
   - (a) Ventilate through tube #1 (blue).
   - (b) Auscultate the stomach and lungs.
     - (i) If breath sounds are heard, the Combitube is in its more common esophageal location.
     - (ii) Attach tube #1 to bag valve mask and O_2.
   - (c) ONLY IF gurgling is present over the stomach when tube #1 is ventilated:
     - (i) Ventilate through tube #2.
     - (ii) If breath sounds are heard, the Combitube is in the less common tracheal location.
     - (iii) Attach tube #2 to bag valve mask and O_2.
6. If no breath sounds are heard in either location:
   - (a) Consider obstruction—Combitube may be obstructing the glottis or collapsing the trachea owing to deep proximal cuff inflation.
     - (i) Deflate the cuffs.
     - (ii) Withdraw 3 cm.
     - (iii) Reinflate and start from step 4.
   - (b) Consider equipment failure.
     - (i) Check that balloons are maintaining pressure and intact.
   - (c) Consider reinsertion.
7. Confirm placement with capnogram and pulse oximetry.
8. Secure the Combitube in position (Fig. 12.3).



Fig. 12.2 (**a**) Insertion of Combitube. (**b**) Teeth should lie between the two black bands on the proximal Combitube



Fig. 12.3 Secure the Combitube in position

12.5 Pearls and Pitfalls

- Pearls
  - In an esophageal intubation situation, a suction tube may be threaded down using tube #2 to decompress the stomach.
  - The Combitube comes with an L-shaped piece that may also be attached to the end of tube #2 to deflect gastric contents away from practitioners.
- Pitfalls
  - After Combitube placement, a definitive airway should be placed when possible.
    - Gastric contents may aspirate despite placement of the Combitube.
    - Combitube should be considered a bridging airway device.
  - Combitubes are associated with a more pronounced hemodynamic stress response than ETTs or laryngeal mask airways (LMAs).
  - Balloon overinflation can lead to esophageal rupture (albeit rare).
  - Combitubes are associated with an increased incidence of sore throat, dysphagia, and upper airway hematomas than ETTs and LMAs.
  - Piriform sinus perforation.

Selected Reading

Agro F, Frass M, Beunmof JL, Krafft P. Current status of the Combitube: a review of the literature. J Clin Anesth. 2002;14:307–14.

Laurin E, Bair A. Devices for difficult airway management in adults. www.uptodate.com. Accessed 14 Mar 2014.

Liem EB. Combitube insertion. University of Florida Department of Anesthesiology, Center for Simulation, Advanced Learning and Technology, Virtual Anesthesia Machine Web site; 2006. http://vam.anest.ufl.edu/airwaydevice/combitube/index.html. Accessed 14 Mar 2014.

Walls R, Murphy M. Manual of emergency airway management. Philadelphia: Lippincott Williams & Wilkins; 2008.

13 Assessment of the Difficult Airway

Melinda W. Fernandez and Lars K. Beattie

13.1 Indications

- Should be performed on all patients that require airway management, conditions permitting
- Respiratory distress
- Airway protection

13.2 Materials and Medications

- None required

13.3 Procedure

1. Anticipating a difficult airway in emergency department patients is the first step to avoiding an unexpected surgical airway.
2. Two mnemonics can be applied quickly and easily to aid in an airway assessment: MOANS and LEMON.

13.3.1 Predicting Bag-Valve-Mask Difficulty

1. Use the mnemonic *MOANS* to assess for possible bag-valve-mask (BVM) difficulty.
   M—mask seal. Will you be able to get a good seal on the face? Predictors of difficulty include facial hair such as a beard, elderly, or emaciated owing to loss of muscle tone in the face.
   O—obesity. Body mass index (BMI) >30.
   A—age (>55 years). Loss of facial muscle tone can make bagging difficult.
   N—no teeth. Although being edentulous makes for an easier intubation, it makes bagging more difficult.
   S—stiff lungs. Acute or chronic lung disease can make a person difficult to bag. In the setting of Trauma, pulmonary contusion(s) and/or other direct lung injuries may increase BVM difficulty.

13.3.2 Predicting Difficult Laryngoscopy

1. Attempts should be made, if at all possible, to assess for a potentially difficult airway. This does not mean you cannot perform direct laryngoscopy if you are anticipating a difficult airway. It does, however, force you to consider all options and to have a solid backup plan in place with backup equipment readily available in the room.
2. Use the mnemonic *LEMON* to predict difficult direct laryngoscopy.
   L—look. A quick look at the patient will tell you a lot. Are there facial injuries; facial anomalies; obesity; short, thick neck; and small mouth or mandible?
   E—evaluate. Use the 3-3-2 rule to quickly assess for the strongest predictors of difficult laryngoscopy.
   - *3:* Open the patient's mouth and three vertically aligned fingers should fit between the incisors.
   - *3:* Three finger widths should fit along the length of the mandible from the mentum to the hyoid bone. Shorter or longer distances may make for a difficult intubation.
   - *2:* Thyromental distance should ideally be two fingers. Measure this from the hyoid to the thyroid.

M.W. Fernandez, MD
Department of Emergency Medicine, University of Florida Health, Gainesville, FL, USA
e-mail: mindyfernandez@ufl.edu

L.K. Beattie, MD, MS (✉)
Department of Emergency Medicine, University of Florida, Gainesville, FL, USA
e-mail: lars.beattie@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_13

M—Mallampati classification (Fig. 13.1). If patient's condition and situation allow, have the patient open the mouth wide, stick out the tongue, and say "Ahh." Evaluate for visible structures.

- *Class I:* Tonsillar pillars and the entire uvula are visible.
- *Class II:* More than the base of the uvula is visible but no pillars are visible.
- *Class III:* Only the base of the uvula is visible.
- *Class IV:* No uvula or soft palate is visible. Only the hard palate is visible.
- These classifications correlate with the Cormack-Lehane grading system for laryngoscopic views. A Mallampati class I will correlate with a grade 1 view about 99 % of the time, whereas a Mallampati IV will be a grade 3 or 4 view all of the time and a rescue plan with backup equipment immediately available should always be in place [1, 2].

O—obstruction. Observe for anything that can get in the way (e.g., the tongue, dentures, blood, vomit, foreign body, edema, redundant tissue).

N—neck mobility. If patient's condition and situation allow, have the patient flex and extend the neck to evaluate mobility. Many patients in the emergency department have limited neck mobility. Examples include the trauma patient who arrives in cervical collar immobilization or a patient with degenerative or rheumatoid arthritis.

3. The *"6-D"* method is another assessment tool that can be used to predict difficult laryngoscopy and intubation. This method can be remembered by the fact that the word "difficult" begins with the letter "D":

Disproportion

- Increased tongue size in relation to pharyngeal size
- Airway swelling or trauma

Distortion

- Neck mass, hematoma, abscess, previous surgical airway, arthritic neck changes

Decreased thyromental distance

- Anterior larynx and decreased mandibular space.
- Look for a receding chin or greater than three fingerbreadths from the mentum to the hyoid bone.

Decreased inter-incisor gap

- Reduced mouth opening.
- Look for less than two to three fingerbreadths placed vertically in the patient's open mouth.

Decreased range of motion in any joints of the airway

- Limited head extension
- Previous neck radiation and/or surgery
- Neck contractures

Dental overbite

- Oversized, angled teeth disrupt the alignment of airway axes.
- Can decrease the interincisor gap.


Class 1
Class 2
Class 3
Class 4
Grade 1
Grade 2
Grade 3
Grade 4

Fig. 13.1 Mallampati classification

13.3.3 Optimizing Laryngoscopy in the Obese Patient

- It is essential that emergency medicine physicians are able to successfully intubate the obese patient.
- Proper assessment and positioning will increase the success rate:
  - The goal is to ensure alignment of the oropharyngeal-pharyngeal-laryngeal (OA-PA-LA) airways by placing the patient in the head-elevated laryngoscopy position (Fig. 13.2a).
  - Align the external auditory meatus with the sternal notch along a horizontal line by positioning the patient on a “ramp.”
  - The ramp can be created by stacking blankets/towels under the lower back ramping up to the neck and head (Fig. 13.2b).
- While the patient is in position on the ramp, the support is adjusted to minimize head flexion and allow for positioning in the sniffing position.
  - Because of the increased height, a step stool may be required to adequately visualize the airway from the head of the bed.



Fig. 13.2 (**a**, **b**) Ramping the obese patient will align the axes of the airway and allow easier direct laryngoscopy when viewed from the head of bed. (*LA* laryngeal airway, *OA* oropharyngeal airway, *PA* pharyngeal airway)

13.4 Pearls and Pitfalls

- Owing to time-sensitive patient care situations, emergency physicians are often not able to perform a thorough airway evaluation on every patient.
- With every airway that you manage and before pushing any drugs, always ask yourself:
  - Will I be able to ventilate this patient?
  - Will I be able to intubate this patient?
  - What is my difficult airway plan if I encounter trouble?
  - Will I be able to perform a surgical airway, if necessary?
- Be sure you have a solid backup plan A, B, and C before pushing any drugs.

References

1. Lee A, Fan LT, Gin T, Karmakar MK, Ngan Kee WD. A systematic review (meta-analysis) of the accuracy of the Mallampati tests to predict the difficult airway. Anesth Analg. 2006;102:1867–78.
2. Boschert S. Think L-E-M-O-N when assessing a difficult airway. ACEP News. Nov 2007.

Selected Reading

Murphy M. Bringing the larynx into view: a piece of the puzzle. Ann Emerg Med. 2003;41:338–41.

Rick J. Recognition and management of the difficult airway with special emphasis on the intubating LMA-Fastrach/whistle technique: a brief review with case reports. BUMC. 2005;18:220–7.

Roberts J, Hedges J. Clinical procedures in emergency medicine. 5th ed. Philadelphia: WB Saunders; 2009. p. 60–2.

Wilson W. Difficult intubation. In: Atlee J, editor. Complications in anesthesia. Philadelphia: WB Saunders; 1999. p. 138–47.

GlideScope

14

Sohan Parekh

14.1 Indications

- Initial device in a predictably difficult airway
- Rescue device in a failed intubation

14.2 Contraindications

- Absolute
  - Inadequate mouth opening
- Relative
  - Blood, vomit, or other secretions that can coat and obstruct the camera lens

14.3 Materials and Medications

- GlideScope video monitor with video cable (GlideScope Video Laryngoscope [GVL] system) (Fig. 14.1) or appropriate-size video baton (Cobalt System) (Fig. 14.2)
- Appropriate-size reusable video laryngoscope (GVL) or single-use laryngoscope blade (GVL Stat) (Table 14.1).
- Endotracheal tube (ETT)
- Malleable stylet or GlideRite rigid stylet
- 10 mL syringe
- End-tidal CO_2 ($EtCO_2$) capnography or colorimetry

S. Parekh, MD
Department of Emergency Medicine,
University of Texas at Austin Dell Medical School,
Austin, TX, USA

Department of Emergency Medicine,
University Medical Center Brackenridge,
Austin, TX, USA
e-mail: sohan.parekh@gmail.com

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_14



Fig. 14.1 GlideScope GVL system (With kind permission from Springer Science + Business Media: Noppens RR, Werner C, Piepho T. Indirekte Laryngoskopie. *Der Anaesthesist*. 2010;59(2):149–61)



Fig. 14.2 GlideScope Cobalt system (With kind permission from Springer Science + Business Media: Jones PM, Turkstra TP, Armstrong KP, et al. Comparison of a single-use GlideScope® Cobalt videolaryngoscope with a conventional GlideScope® for orotracheal intubation. *Can J Anesthe/Journal canadien d'anesthésie*. 2010;57(1))

Table 14.1 GlideScope sizing

				Video Baton 1–2			Video Baton 3–4	
GVL 1	GVL 2	GVL 3	GVL 4	Stat 0	Stat 1	Stat 2	Stat 3	Stat 4
1.8–10 kg	10 kg—adult	40 kg—morbidly obese	40 kg—morbidly obese	<1.5 kg	1.5–3.6 kg	1.8–10 kg	10 kg—adult	40 kg—morbidly obese

14.4 Procedure

1. Insert the video cable (GVL system) or the video baton (Cobalt system) into the GlideScope video monitor (Fig. 14.3).
2. If using the GVL system, insert the distal end of the video cable into the port on the handle of the reusable video laryngoscope (GVL) (Fig. 14.4).
3. If using the Cobalt system, insert the video baton into the GVL Stat (Fig. 14.5).
   (a) Align the logo on the side of the video baton with the logo on the side of the single-use laryngoscope blade (GVL stat).
   (b) The video baton should slide smoothly and click into the place.
4. Turn on the GlideScope at for at least 30–120 s before use to fully activate the antifog mechanism.
5. Insert a stylet into the ETT. If using a malleable stylet, shape the curvature of the distal end of the tube to conform to the 60° curvature of the laryngoscope blade.
6. Firmly hold the laryngoscope handle in the left hand and ensure that an image can be clearly seen on the video monitor.
7. After ensuring adequate sedation and paralysis, open the mouth wide and insert the laryngoscope blade in the midline underneath the tongue (Fig. 14.6).



Fig. 14.3 Cable insertion into the video monitor



Fig. 14.4 Connect the distal end of the video cable the port on the handle of the GVL (GVL System)



Fig. 14.5 Slide the video baton into the GVL Stat, Cobalt System



Fig. 14.6 Insert the laryngoscope blade in the midline beneath the tongue (with kind permission from Springer Science+Business Media: Osborn IP, Kleinberger AJ, Gurudutt VV. Chapter 8: Airway emergencies and the difficult airway. In: Levine AI, Govindaraj S, DeMaria S, editors. *Anesthesiology and otolaryngology*. 2013)

8. Looking at the video monitor, advance the laryngoscope blade further into the oropharynx in order to obtain a view of the epiglottis.
   (a) Do not look directly into the oropharynx.
   (b) Movements and adjustments should be guided by the image on the video monitor.
9. Place the laryngoscope blade in the vallecula (analogous to a Macintosh blade) and apply a gentle backward tilt to expose the glottis.
10. In the event that a satisfactory glottic view cannot be obtained, the laryngoscope blade may be advanced and used like a Miller blade to lift the epiglottis out of the way.
11. Directing attention back toward the patient, insert the ETT into the mouth adjacent to the laryngoscope blade.
12. Guide the ETT toward the tip of the laryngoscope such that the end of the ETT emerges on the video monitor.
13. Looking at the video monitor, advance the ETT toward the glottis, and maneuver the tip of the tube between the vocal cords by rotating and altering the angle of the ETT.
   (a) If the ETT tip is posterior to the arytenoids:
      (i) Pull the ETT superiorly, rotate it over the left arytenoid, and gently twist the tube over the epiglottic aperture.
      (ii) Apply external laryngeal manipulation.
      (iii) Withdraw the blade to reduce tilting of the laryngeal axis and lessen the angle of introduction.
   (b) If the ETT abuts the false vocal cords, turn the ETT in the clockwise direction while withdrawing the stylet (Fig. 14.7).
14. Using the thumb, partially withdraw the stylet a few centimeters from the ETT.
   (a) The distal end of the tube should be free of the stylet.
   (b) An assistant can perform this task to allow for greater control and stability of the ETT.
15. Insert the ETT to the desired depth.
16. Fully remove the stylet, inflate the cuff of the ETT using a syringe, and confirm placement with $EtCO_2$, capnography, or colorimetry.



Fig. 14.7 Partially withdraw the stylet from the ETT to allow for passage through the vocal cords

14.5 Complications

- Dental injury
- Airway trauma

14.6 Pearls and Pitfalls

- Unlike conventional laryngoscopy, there is no need to displace the tongue.
- The greatest challenge when intubating with the GlideScope is maneuvering the ETT into the glottis aperture. Alternatives to the conventional technique are:
  - Make a 90° bend in the ETT just proximal to the cuff and insert it in the horizontal direction with the tip toward the right cheek. Once the tube is advanced past the flange of the laryngoscope, rotate it counterclockwise, at which point it should be pointed at the glottis. The tube can then be gently rotated into the glottis.
  - Consider inserting the laryngoscope slightly to the left of the midline upon initial insertion to allow greater space for advancement and maneuvering of the ETT.
- Do not overly lever the laryngoscope or use excessive lifting force after insertion into the vallecula. An adequate view of the glottis is generally easily obtained with minimal effort.
- Display settings can be adjusted using the menu button on the video monitor.

Selected Reading

Cho JE, Kil HK. A maneuver to facilitate endotracheal intubation using the GlideScope. Can J Anaesth. 2008;55:56–7.

GlideScope GVL and Cobalt user's manual & quick reference guide. Bothell: Verathon Inc; 2009–2011.

Kramer DC, Osborn IP. More maneuvers to facilitate tracheal intubation with the GlideScope. Can J Anaesth. 2006;53:737.

Lim HC. Utilization of a GlideScope videolaryngoscope for orotracheal intubations in different emergency airway management settings. Eur J Emerg Med. 2009;16:68–73.

Walls RW, Murphy MF, editors. Manual of emergency airway management. 3rd ed. Philadelphia: Lippincott Williams & Wilkins; 2008.

Endotracheal Tube Introducer (Bougie)

15

Joseph Rabinovich

15.1 Indications

- During orotracheal intubation, when only epiglottic visualization or partial glottic view is obtained during laryngoscopy.
- Particularly useful when neck mobility is limited, leading to inadequate visualization of the glottis (as in the case with cervical spine immobilization).
- When the glottic opening is narrowed either from pathological causes (burns, trauma, tumor, or other anatomical variation).
- When the direct view of the airway is very narrow, as with limited mouth opening or large tongue. In these scenarios, the endotracheal tube (ETT) can obstruct one's view of the cords during placement.

15.2 Contraindications

- When a failed airway occurs (three unsuccessful attempts at endotracheal intubation and inability to adequately oxygenate)
- When surgical airway is indicated (i.e., upper airway obstruction that prevents passage of the ETT via the orotracheal route)

15.3 Materials and Medications

- ETT introducer (bougie) (Fig. 15.1)
- Water-based lubricant
- Lubricated ETT 6 mm or larger *without* stylet (pediatric bougies are available that accommodate smaller ETTs)
- Standard orotracheal direct laryngoscopy (Miller or Macintosh blade) or video laryngoscopy setup
- Assistant



Fig. 15.1 Endotracheal tube introducer (bougie)

J. Rabinovich, MD
Department of Emergency Medicine,
Mount Sinai School of Medicine,
Elmhurst Hospital Center, Elmhurst, NY, USA
e-mail: joerab@gmail.com

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_15

15.4 Procedure

1. The operator first optimizes airway visualization (Fig. 15.2). (Bougie use should not be a substitute for poor technique.)
2. Without losing sight of the airway, the operator asks the assistant to hand him or her the bougie with the coudé tip facing up.
3. The operator directs the bougie tip underneath the epiglottis (Fig. 15.3).
4. Confirmation of placement can be done visually or by tactile sensation:
    (a) A ratchet-like sensation may be felt as the bougie tip is advanced into the airway and slides over the tracheal rings.
    (b) As the bougie is further advanced, the operator may feel the bougie rotate as it enters the bronchus and/or will get a "hold up," the most reliable sign that the bougie is in the trachea [1]. (The "hold-up" sign occurs when the Bougie encounters a terminal bronchus [typically at around 35 cm] and stops advancing.) [2]
5. Once placement is confirmed, the bougie needs to be partially withdrawn to about 25 cm at the lip line.
    (a) Some brands will have a thick black indicator line.
    (b) A sufficient amount of the bougie needs to extend out beyond the proximal end of the ETT.
6. While the operator holds the bougie in place, the assistant threads the ETT over the bougie (Fig. 15.4).
7. The operator now grasps the ETT in her or his right hand and advances it over the bougie.
8. Simultaneously, the assistant holds and stabilizes the proximal end of the bougie.
9. The ETT should be advanced to approximately 23 cm in males and 21 cm in females. The assistant removes the bougie as the operator holds the ETT in place (Fig. 15.5).
10. As the operator holds the ETT firmly in position, the assistant inflates the ETT balloon and withdraws the bougie.
11. Confirmation of proper ETT placement is achieved through traditional means (end-tidal CO_2 detection, auscultation of breath sounds).



Fig. 15.2 (**a**) Assistant hands operator bougie with coudé tip directed upward, while operator maintains his focus on the target. (**b**) Bougie being placed, parallel with line of sight, underneath epiglottis



Fig. 15.3 Bougie can be placed into the glottis using direct laryngoscopy or video assistance



Fig. 15.4 (**a**) Assistant places ETT over bougie and operator withdraws bougie until it protrudes out the top of the ETT, (**b**) while assistant stabilizes the protruding portion of the bougie, the operator railroads the ETT into the airway. The operator continues to support the soft tissues with the laryngoscope blade to facilitate placement



Fig. 15.5 The assistant removes the bougie while the operator stabilizes the endotracheal tube

15.5 Complications

- Trauma to the esophagus, larynx, trachea, or bronchus, including perforation [3, 4].
- In general, complications are rare.

15.6 Pearls and Pitfalls

- The line of sight should be as parallel as possible to the axis of the bougie as it is being passed, allowing better eye-hand coordination. This augments more accurate placement of the bougie tip.
- Maintain the view of the airway as the assistant hands the operator the bougie.
- Keep the laryngoscope in place to support the soft tissues, as the endotracheal tube is slid over the bougie, to facilitate placement.
- If resistance is met during passage, withdraw the ETT slightly (~2 cm) and rotate the ETT counterclockwise one-quarter turn (90°) and reattempt passage.
  - This changes the position of the leading edge of the ETT, which may catch on the posterior laryngeal inlet [2].
  - By rotating the ETT, the leading edge now is anterior facing and is less likely to catch on the arytenoid cartilage along with other laryngeal inlet structures.
- If encountering resistance to ETT placement, consider releasing cricoid pressure (if used).
- Measurement markings on the bougie are aligned with the coudé tip. If not sure of orientation and the loose site of the tip, use the markings to properly orient the tip.

References

1. Kidd JF, Dyson A, Latto IP. Successful difficult intubation. Use of the gum elastic bougie. Anaesthesia. 1988;43:437–8.
2. Murphy MF, Hung OR, Law JA. Tracheal intubation: tricks of the trade. Emerg Med Clin North Am. 2008;26:1001–14.
3. Kadry M, Popat M. Pharyngeal wall perforation – an unusual complication of blind intubation with a gum-elastic bougie. Anaesthesia. 1999;54:404–5.
4. Smith BL. Haemopneumothorax following bougie-assisted tracheal intubation. Anaesthesia. 1994;49:91.

Lighted Stylet Intubation

16

Benjamin M. Mahon and Lars K. Beattie

When lighted stylet intubation is done correctly, the procedure can be very safe, with very little difference in outcome from that of primary laryngoscopy. (*Note*: *several lighted stylet devices*, *such as the TrachlightTM and Light WandTM*, *are no longer being manufactured*, *but these devices are still in use*.)

16.1 Indications

- Difficult/impossible direct laryngoscopy [1, 2]
  - Congenital abnormalities of airway
  - High Mallampati grade [3]
  - Dental appliances
- Failed direct laryngoscopy

16.2 Contraindications

- Absolute
  - Morbid obesity
  - Airway foreign body
  - Expanding neck mass
- Relative
  - Abnormal airway anatomy
  - Airway lesions (e.g., abscess, mass, epiglottitis) that change oropharyngeal anatomy
  - Acute care where concomitant resuscitation requires a well-lit room
  - Lack of familiarity or experience with procedure
  - “Can’t oxygenate, can’t ventilate” situation

16.3 Materials and Medications

- Intravenous (IV) access, O_2, and monitor
- Ambu bag with supplemental oxygen
- Suction (Yankauer and tubing)
- Lighted stylet (LS)
- Endotracheal tube (ETT) 2.5-mm larger than LS with 10-cc syringe
- Surgilube
- Intubation medications (this procedure may be performed as an awake or a rapid-sequence intubation)

B.M. Mahon, MD
Ponciana Medical Center,
Kissimmee, FL, USA
e-mail: drfaust2k9@aol.com

L.K. Beattie, MD, MS (✉)
Department of Emergency Medicine, University of Florida,
Gainesville, FL, USA
e-mail: lars.beattie@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_16

16.4 Procedure

1. Preoxygenate.
2. Positioning.
    (a) Sniffing position, pinna at the level of the sternal notch (Fig. 16.1).
    (b) Skip sniffing position if cervical spine injury is suspected.
3. LS-ETT unit preparation.
    (a) Insert the wire stylet into the device.
    (b) Check the LS light.
    (c) Lubricate the LS with K-Y Jelly.
    (d) Position the LS just distal to the Murphy eye.
    (e) Curve the LS to user preference at the line labeled "Bend Here."
4. Administer intubation medications.
5. Have an assistant to apply cricoid pressure.
6. Grasp and elevate the patient's jaw near the corner of the mouth with the operator's thumb, index, and middle fingers, elevating the tongue and epiglottis along with it.
7. Using the free hand, insert the LS-ETT unit into the oropharynx and advance (Fig. 16.2).
8. Use the midline glow in the neck to guide insertion of the LS-ETT (Fig. 16.3).
9. Bright light *below* the thyroid prominence indicates correct placement of the ETT tip.
10. Dim or blurred light or light at the thyroid prominence suggests incorrect positioning (Fig. 16.4).
11. If the transilluminated light is dim, off center, or not seen, esophageal positioning must be considered.
    (a) Withdraw the LS-ETT unit approximately 2–5 cm.
    (b) Reposition the patient's head and neck.
    (c) Reattempt according to steps 5–8.
12. Placement of the ETT (Fig. 16.5).
    (a) Hold the LS-ETT unit steady with one hand.
    (b) Check the depth of the ETT and adjust accordingly.
    (c) Release the LS latch that holds the ETT to the LS.
    (d) While holding the ETT in position, gently slide the LS out from the ETT.
    (e) Inflate the ETT balloon.
13. Confirm ETT placement (continuous end-tidal CO_2 [$EtCO_2$], colorimetric capnometry).
14. Secure the ETT.



Fig. 16.1 Sniffing position, pinna at the level of the sternal notch



Fig. 16.2 Grasp and elevate the patient's jaw near the corner of the mouth with the operator's thumb, index, and middle fingers, elevating the tongue and epiglottis along with it. Using the free hand, insert the LS-ETT unit into the oropharynx and advance



Fig. 16.3 (**a**–**c**) Use the midline glow in the neck to guide insertion of the LS-ETT. (**d**) Bright light *below* the thyroid prominence indicates correct placement of the ETT tip



Fig. 16.4 Dim or blurred light or light at the thyroid prominence suggests incorrect positioning



Fig. 16.5 (**a**) Hold the LS-ETT unit steady with one hand. (**b**) Check the depth of the ETT and adjust accordingly. (**c**) Release the LS latch that holds the ETT to the LS. (**d**) While holding the ETT in position, gently slide the LS out from the ETT

16.5 Pearls and Pitfalls

- Pearls
  - LS-ETT complex—Typically the classic "hockey-stick" shape with the 90° curve just proximal to the cuff is recommended [2].
  - Dimming the room lights will enhance transillumination.
  - Pulling the wire stylet out from the LS-ETT unit will make it more pliable and may facilitate its placement in the trachea and removal of the LS.
  - Some LS devices start to blink after 30 s to prevent bulb overheating.
  - The LS may be used with nasotracheal intubation, intubation through a laryngeal mask airway (LMA), or conventional laryngoscopy to enhance success.
- Pitfalls
  - LS intubation should not be used as an emergency airway alternative by a proceduralist unfamiliar with the technique:
    - It is technically complicated and more challenging than many other airway adjuncts in the standard difficult airway algorithm.
    - One study compared the use of four rescue airway devices in the difficult airway algorithm. A success rate of only 20 % was achieved with the Trachlight™ on the first attempt when in the hands of the novice physician when used as a rescue device in their difficult airway algorithm [4].
  - In very thin patients, transillumination may be visualized quite well even when the LS-ETT unit is in the esophagus:
    - When the unit is in the esophagus, typically the light it will be more diffuse.
    - When the unit is in the trachea, the transilluminated area will be well circumscribed.
  - In obese patients or patients with significant neck tissue, the transilluminated light from the LS-ETT unit may be dim despite correct positioning in the trachea.

References

1. Agro F, Hung OR, Cataldo R, Carassiti M, Gherardi S. Lightwand intubation using the Trachlight: a brief review of current knowledge. Can J Anaesth. 2001;48:592–9.
2. Davis L, Cook-Sather SD, Schreiner MS. Lighted stylet tracheal intubation: a review. Anesth Analg. 2000;90:745–56.
3. Rhee KY, Lee JR, Kim J, Park S, Kwon WK, Han S. A comparison of lighted stylet (Surch-Lite) and direct laryngoscopic intubation in patients with high Mallampati scores. Anesth Analg. 2009;108:1215–9.
4. Aikins NL, Ganesh R, Springmann KE, Lunn JJ, Solis-Keus J. Difficult airway management and the novice physician. J Emerg Trauma Shock. 2010;3:9–12.

Selected Reading

Langeron O, Birenbaum A, Amour J. Airway management in trauma. Minerva Anestesiol. 2009;75:307–11.

Walls RM, Murphy MF. Manual of emergency airway management. 3rd ed. Philadelphia: Lippincott Williams & Wilkins; 2008. Chap. 11.

Fiber-Optic Stylet Intubation (Rigid and Semirigid)

17

Joseph Rabinovich

17.1 Indications

- For use in routine and predicted difficult oral intubations.
- Similar to a flexible fiber-optic scope with the specific advantages of:
  - Less setup time
  - Less time to perform the procedure
  - Appropriate for routine intubations (and easier to accumulate experience)
  - Rigid enough to lift up the epiglottis
  - Easier to navigate through tissue
  - Less susceptible to being obscured by blood and secretions
  - More durable, more portable, easier to clean, and less expensive
- Particularly useful when neck mobility or mouth opening is restricted.
- Advantageous in awake intubations because it can minimize tissue contact, resulting in less stimulation to the patient's airway and better tolerance.
- Certain stylets can be used to intubate through supraglottic airways such as laryngeal mask airways (LMAs).

17.2 Contraindications

- Complete upper airway obstruction where surgical airway is indicated
- Oral pharyngeal swelling requiring a nasotracheal or surgical approach
- Failed airway and unable to adequately maintain oxygenation

17.3 Relative Contraindications

- Large amounts of blood and secretions may obscure visualization of the airway and cords.
- Very distorted airways. Compared with flexible endoscopy, this device is less maneuverable.

17.4 Materials and Medications

- Endotracheal tube (ETT) 5.5 mm or greater (Fig. 17.1) (Pediatric stylets are also available.)
- Water-soluble lubricant
- Defogging agent
- Optional: Swivel adaptor and meconium aspirator

J. Rabinovich, MD
Department of Emergency Medicine,
Mount Sinai School of Medicine, Elmhurst Hospital Center,
Elmhurst, NY, USA
e-mail: joerab@gmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_17



Fig. 17.1 (**a**) Bonfils rigid fiber-optic stylet, Karl Storz endoscopy, (**b**) Levitan FPS malleable fiber-optic stylet

17.5 Procedure

1. Use standard preparation for rapid sequence intubation (RSI) or for awake intubation.
2. Place the ETT over the stylet.
   - (a) The ETT should extend slightly beyond the stylet tip.
   - (b) If using the malleable stylet:
     - (i) Without a laryngoscope: Bend tip to about 70° [1].
     - (ii) With a laryngoscope: Bend tip to 35° [1].
   - (c) Lubricate the tip of the ETT.
3. Depending on specific scope capability, connect oxygen tubing to the port on the scope.
   - (a) This keeps secretions away from the tip while providing an oxygen source.
   - (b) Keep flow less than 6 L/min [2].
4. Lens fogging prevention.
   - (a) Warm the tip of the scope with the hand or immerse the tip in warm saline.
   - (b) Apply the defogging agent.
   - (c) Alternatively, chlorhexidine is an effective defogger.
5. Scope insertion.
   - (a) Use the nondominant hand to pull the jaw forward while holding the tongue.
     - (i) In an awake patient, have the patient protrude the tongue and the operator grasps it with 4×4 gauze. (Alternatively, a Macintosh laryngoscope blade can be used.)
     - (ii) The goal is to move the base of the tongue off the posterior pharyngeal wall.
   - (b) Initially position the scope horizontally and to the right of the patient's mouth.
   - (c) Once the tip is in the oropharynx, reposition the scope vertically (Fig. 17.2a).
   - (d) The scope tip should be in the midline or in the retromolar position (per scope design).
   - (e) Position the scope and the tip of the ETT in front of the uvula.
   - (f) Refer to the eyepiece or video screen to see if there is a clear image of the uvula (Fig. 17.2b).
   - (g) Advance the scope very slowly to maintain a view of landmarks, avoiding tissue contact (Fig. 17.3).
6. Once the epiglottis is visualized:
   - (a) Continue to advance slowly.
   - (b) To get underneath the epiglottis, the tip of the scope may need to be moved posteriorly (by tilting the operator's hand slightly forward) (Fig. 17.4).

7. Once underneath the epiglottis, tilt the scope back, to advance into the more anterior directed airway.
    - (a) Make sure the glottic opening is well centered on the screen to facilitate placement (Fig. 17.5).
    - (b) If resistance is felt, operator may need to rotate the scope clockwise, or tip scope slightly forward, to prevent the ETT from abutting the anterior aspect of the trachea.
    - (c) The ETT may need to be advanced off the rigid stylet to allow further advancement.
8. To remove scope:
    - (a) Twist the proximal end of the ETT clockwise.
    - (b) Stabilize the tube with the nondominant hand.
    - (c) Use the dominant hand to pull the scope forward, following the curvature of the stylet (Fig. 17.6).
    - (d) An assistant may be of use during this step.



Fig. 17.2 (**a**) Initial placement of scope, under direct visualization; (**b**) tip is positioned in from the uvula



Fig. 17.3 (**a**) Using the video monitor, or through an eyepiece, the operator advances to the next landmark, (**b**) the epiglottis



Fig. 17.4 (**a**) Operator tips scope forward to get underneath the epiglottis while advancing; (**b**) once under the epiglottis, the scope may need to be tipped back to advance to the glottic opening; (**c**) operator should try to keep the glottic opening in the center of the screen



Fig. 17.5 (**a**) Operator is advancing the scope, (**b**) through the glottic opening keeping the image centered



Fig. 17.6 To remove scope, operator must pull it forward while stabilizing the endotracheal tube

17.6 Pearls and Pitfalls

- Pearls
  - When the operator loses perspective or a clear view, withdraw the scope back to the point where identifiable structures are visualized and proceed.
  - The operator can suction through the scope by attaching a swivel adaptor and a meconium aspirator (Fig. 17.7) [3].
- Pitfalls
  - If the scope is advanced too quickly, orientation can be lost.
  - Structures that are too close to the scope will become blurred and unidentifiable.
  - If the scope tip abuts pharyngeal tissue, visualization can become blurred.
  - Flow greater than 6 L/min connected to the oxygen port may result in subcutaneous emphysema (single case report) [2].



Fig. 17.7 By placing the stylet through the rubber valve of a swivel adaptor, which is then connected to suction via a neonatal meconium aspirator, the operator can now suction through the endotracheal tube

References

1. Levitan RM. Design rationale and intended use of a short optical stylet for routine fiberoptic augmentation of emergency laryngoscopy. Am J Emerg Med. 2006;24:490–5.
2. Hemmerling TM, Bracco D. Subcutaneous cervical and facial emphysema with the use of the Bonfils fiberscope and high-flow oxygen insufflation. Anesth Analg. 2008;106:260–2.
3. Weingart SD, Bhagwan SD. A novel set-up to allow suctioning during direct endotracheal and fiberscope intubation. J Clin Anesth. 2011;23:518–9.

Storz Video Laryngoscope

18

Joseph Rabinovich

18.1 Indications

- Orotracheal intubation for both routine and predicted difficult airways.
- Teaching traditional direct laryngoscopy to novice intubators.
- Ideal for unanticipated difficult airway with the option of intubating indirectly if an adequate direct view is unobtainable.
- An excellent tool when cervical spine precautions need to be taken: Because the video view of the airway is generated by a camera at the tip of laryngoscope blade, less manipulation is required for optimal glottic views.

18.2 Contraindications

- Absolute
  - When orotracheal intubation is contraindicated, e.g., for massive facial trauma, complete upper airway obstruction precluding orotracheal access to the airway
  - In a failed airway (three unsuccessful attempts with inability to maintain adequate oxygenation)
- Relative
  - Blood or copious secretions may prevent indirect viewing of the airway but does not always preclude the use of this device.

J. Rabinovich, MD
Department of Emergency Medicine,
Mount Sinai School of Medicine,
Elmhurst Hospital Center, Elmhurst, NY, USA
e-mail: joerab@gmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_18

18.3 Materials and Medications (Fig. 18.1)

- Standard materials and medications for endotracheal intubation. Operator should have a backup laryngoscope in case of equipment failure.
- Endotracheal tube (ETT) with or without stylet.
- Water-based lubricant.
- Antifogging agent (not required for C-Mac).



Fig. 18.1 (**a**) Storz video laryngoscope (older version), (**b**) Storz C-Mac (newer version)

18.4 Procedure

1. Standard preparation for orotracheal intubation. If there are no cervical spine precautions, then align the external auditory meatus with the sternal notch [1].
2. Apply antifogging drops to lens at tip of the blade, and/or hold the hand over the blade tip to warm it up to body temperature (older V-Mac model) (Fig. 18.2a).
3. Because blade geometry is the same as in standard laryngoscopes, the insertion technique is identical to that of standard laryngoscopy with a Macintosh blade (Fig. 18.2b).
4. Obtain the best direct view possible.
5. Consider the addition of the backward-upward-rightward pressure (BURP) maneuver [2].
6. Airway maneuvers may be performed by the operator or by the assistant using the video screen as a guide along with operator feedback (Fig. 18.3).
7. The operator has the option of intubating directly with adequate view or indirectly if visualization is improved.
8. Consider using an ETT introducer (bougie—see Chap. 15) if the view is inadequate.
9. Place the ETT, with or without a stylet, into the airway under direct or indirect visualization. If using a stylet, bend the distal end of the tube to approximately 35° as for a standard intubation (Fig. 18.4) [3].
10. Remove the stylet, inflate the cuff of the ETT using a syringe, and confirm placement with end-tidal CO_2, capnography, or colorimetry.



Fig. 18.2 (**a**) Operator warming the blade to prevent fogging, (**b**) laryngoscope blade insertion using the standard direct technique. Operator visually places the blade and optimizes the glottic view



Fig. 18.3 Operator has the choice of using direct visualization (preferred when a novice intubator is learning laryngoscopy) or the indirect video view of the glottis



Fig. 18.4 (**a**) Operator initially places the endotracheal tube (ETT) into the oropharynx using direct visualization to avoid injury; (**b**) the tip of the ETT passing through the cords can be confirmed by direct visualization or by watching the video image

18.5 Complications (As with any Direct Laryngoscopy)

- Dental trauma
- Oropharyngeal trauma
- Vocal cord injury

18.6 Pearls and Pitfalls

- The initial placement of the laryngoscope blade and ETT should be done under direct visualization to avoid trauma to the oropharyngeal structures.
- As with direct laryngoscopy, the ETT should not be placed blindly, and the ETT must be seen to pass through the vocal cords to avoid placement in the esophagus.
- View can be obscured by secretions or fogging. If this occurs, the operator may need to remove the blade, wipe it down, and reinsert. The newer model, the C-Mac, is less likely to fog owing to design improvements.
- Observing the ETT pass through the vocal cords can sometimes be easier using the video image because the camera is angled to provide the most optimal view.
- Placement of the blade into the oropharynx can be awkward because the handle of laryngoscope is bulkier than a standard laryngoscope. Its handle is larger and has cables attached to its base. In patients with large anteroposterior diameter chests, the operator may need to rotate the laryngoscope handle toward the right corner of the mouth in order to introduce the blade into the oral cavity and then rotate it back to the proper position.
- These devices are ideal for teaching laryngoscopy. With same blade geometry, the technique is the same as with standard laryngoscopy. As the operator attempts intubation directly, the instructor can observe on the video screen and guide the student. The instructor will also be able to visually confirm that the ETT is entering the trachea.

References

1. Greenland KB, Edwards MJ, Hutton NJ, Challis VJ, Irwin MG, Sleigh JW. Changes in airway configuration with different head and neck positions using magnetic resonance imaging of normal airways: a new concept with possible clinical applications. Br J Anaesth. 2010;105:683–90.
2. Knill RL. Difficult laryngoscopy made easy with a “BURP.”. Can J Anaesth. 1993;40:798–9.
3. Levitan RM, Heitz JW, Sweeney M, Cooper RM. The complexities of tracheal intubation with direct laryngoscopy and alternative intubation devices. Ann Emerg Med. 2011;57:240–7.

Selected Reading

Brown 3rd CA, Bair AE, Pallin DJ, et al. Improved glottic exposure with the video Macintosh laryngoscope in adult emergency department tracheal intubations. Ann Emerg Med. 2010;56:83–8.

Niforopoulou P, Pantazopoulos I, Demestiha T, Koudouna E, Xanthos T. Video-laryngoscopes in the adult airway management: a topical review of the literature. Acta Anaesthesiol Scand. 2010;54:1050–61.

Cricothyroidotomy

19

Henry Young II, Shannon Toohey, Bharath Chakravarthy, and Lars K. Beattie

Up to seven intubation attempts in 1000 end up in a "can't intubate/can't ventilate" situation in the emergency department. These are considered failed airways that may require a surgical airway to maintain ventilation and oxygenation.

19.1 Indications

- Endotracheal tube (ETT) placement attempts unsuccessful
- Failed bag valve mask, laryngeal mask airway, or Combitube ventilation
- Severe facial trauma affecting the upper airway
- Severe oropharyngeal hemorrhage or profound emesis
- Obstruction (foreign body, mass, mass effect)

19.2 Contraindications

- Airway protection achievable using a less invasive strategy
- Tracheal transaction
- Pediatric patients younger than 8 years

19.3 Techniques

- Scalpel-bougie – minimalist
- Scalpel-Trousseau – standard

19.3.1 Scalpel-Bougie

19.3.1.1 Materials and Medications (Fig. 19.1)

- Betadine or chlorhexidine
- Scalpel #11 blade
- ETT (≥6 cm)
- Bougie
- Surgilube
- Bag valve mask

H. Young II, MD
Department of Emergency Medicine, University of Florida Health,
Gainesville, FL, USA
e-mail: hyoungii@ufl.edu

S. Toohey, MD
Department of Emergency Medicine, University of California
Irvine Medical Center, Orange, CA, USA
e-mail: stoohey@uci.edu

B. Chakravarthy, MD, MPH
Department of Emergency Medicine,
University of California Irvine, Orange, CA, USA
e-mail: bchakrav@uci.edu

L.K. Beattie, MD, MS (✉)
Department of Emergency Medicine, University of Florida,
Gainesville, FL, USA
e-mail: lars.beattie@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_19



Fig. 19.1 *Right to left*, *top to bottom*: ETT (≥6 cm); bag valve mask; trauma shears; scalpel #11 blade; bougie

19.3.1.2 Procedure

1. Apply topical antiseptic.
2. Remove the 15-mm ETT ventilator connector from the ETT end.
3. Place copious Surgilube on the bougie and railroad over the end of the bougie.
4. Palpate the thyroid notch, cricothyroid membrane, and hyoid bone for orientation (Fig. 19.2a).
5. Stabilize the thyroid cartilage between the thumb and the middle finger of the nondominant hand.
6. Make a vertical skin incision (2–3 cm) over the cricothyroid membrane (Fig. 19.2b).
7. Use the index finger to palpate the cricothyroid membrane.
8. Turn the scalpel 90° and make a 1.5-cm horizontal incision through the lower half of the cricothyroid membrane (Fig. 19.3a).
9. With the scalpel still in the incision, turn it 90°, and insert the bougie into the incision, using the blade as a guide (Fig. 19.3b).
10. Advance the bougie caudally 5–6 cm. Stop if resistance is encountered.
11. Slide the ETT over the bougie into the incision (Fig. 19.4a).
12. Inflate the ETT cuff and ventilate the patient (Fig. 19.4b).
13. Verify the position of the ETT via auscultation, end-tidal CO_2 ($EtCO_2$), and chest radiograph.
14. Secure the ETT.



Fig. 19.2 (**a**) Palpate and stabilize the thyroid cartilage, (**b**) make a vertical 2–3 cm incision over the cricothyroid membrane



Fig. 19.3 (**a**) Make a horizontal incision into the cricothyroid membrane, (**b**) insert the bougie into the incision made in the cricothyroid membrane



Fig. 19.4 (**a**) Slide the endotracheal tube (ETT) over the bougie into the trachea, (**b**) ventilate the patient

19.3.2 Scalpel-Trousseau

19.3.2.1 Materials and Medications (Fig. 19.5)

- Scalpel with #11 blade
- Tracheal hook
- Trousseau dilator
- Cuffed tracheostomy tube (TT) (6.5 or 7.0) or ETT (5.0, 5.5, or 6.0)
- Antiseptic preparation



Fig. 19.5 *Top to bottom*, *right to left*: Scalpel with #11 blade; tracheal hook; Trousseau dilator; cuffed tracheostomy tube (TT) (6.5 or 7.0) or ETT (5.0, 5.5, or 6.0); antiseptic preparation

19.3.2.2 Procedure

1. Apply topical antiseptic.
2. Palpate the thyroid notch, cricothyroid membrane, and hyoid bone for orientation.
3. Stabilize the thyroid between the thumb and the middle finger of the nondominant hand (Fig. 19.6a).
4. Make a vertical skin incision (2–3 cm) over the cricothyroid membrane (Fig. 19.6b).
5. Palpate with the index finger to verify the cricothyroid membrane location.
6. Use stabilization of the thyroid and palpation to maintain orientation of the anatomy.
7. Make a 1.5-cm horizontal incision through the lower half of the membrane (Fig. 19.7a).
8. Insert a tracheal hook into the incision, then rotate such that hook faces superiorly (Fig. 19.7b).
9. Withdraw at a 45° angle in a cephalad direction, applying gentle traction to the thyroid cartilage.
10. Place the Trousseau dilator into the incision transversely and open the membrane incision vertically (Fig. 19.8a).
11. Insert a cuffed ETT (5.0–6.0) or TT (6.5–7.0) into the incision between the prongs of the dilator in the horizontal access (Fig. 19.8b).
12. Rotate both the dilator and the ETT toward the head of the patient and then direct the tube downward into the trachea while removing the dilator.
13. Inflate the ETT cuff and ventilate the patient.
14. Verify the position of the ETT via auscultation, $EtCO_2$, and chest x-ray.
15. Once placement of the tube has been verified, the tracheal hook can be removed.
16. Secure the ETT.



Fig. 19.6 (**a**) Stabilize the thyroid cartilage between the thumb and the middle finger of the nondominant hand; (**b**) make a vertical incision over the cricothyroid membrane



Fig. 19.7 (**a**) Make a horizontal incision in the lower half of the cricothyroid membrane. (**b**) Insert a tracheal hook and apply gentle traction superiorly at a 45° angle



Fig. 19.8 (**a**) Insert the Trousseau dilator into the incision, and open the path for placement of the tracheostomy tube (TT) or the ETT. (**b**) Insert the TT or the ETT into the expanded incision between the Trousseau dilator prongs

19.4 Complications

- Bleeding
- ETT misplacement (false passage, through the thyrohyoid membrane, unintentional tracheostomy)
- Hoarseness, dysphonia, or vocal cord paralysis
- Subglottic or laryngeal stenosis
- Damage to thyroid cartilage, cricoid cartilage, or tracheal rings
- Perforated esophagus
- Infection
- Aspiration

19.5 Pearls

- Predictors of difficult cricothyrotomy: "SHORT" [1]
  - Prior *S*urgery or *S*car tissue
  - *H*ematoma
  - *O*bese
  - Prior *R*adiation
  - *T*umor/abscess
- The incision should cut through the skin and subcutaneous tissue down to the cricothyroid membrane and cartilages.
- Vertical incisions allow for extension in either direction if the cricothyroid membrane is above or below initial incision.
- Blood in the field may hinder visualization of the membrane, but the airway should be established before attempts to control any bleeding.
- Cricothyroid arteries are located cephalad to the cricothyroid membrane.
- Either a TT or an ETT can be used for the procedure.
  - ETTs are more ubiquitous.
  - TTs are easier to secure.
- If an ETT is used, a stylet can help direct placement.
- Cricothyroidotomy is preferred in the emergency setting over tracheostomy owing to the increased risks of bleeding, the mobility of the trachea, and the risk of lacerating the underlying thyroid gland [2].
- Ultrasound can be used to visualize landmarks in patients in whom landmarks are difficult to identify.

References

1. Walls RM, Murphy MF, editors. Manual of emergency airway management. 4th ed. Philadelphia: Wolters Kluwer; 2012.
2. Boon JM, Abrahams PH, Meiring JH, et al. Cricothyroidotomy: a clinical anatomy review. Clin Anat. 2004;17:478–86.

Selected Reading

DiGiacomo C, Neshat KK, Angus LD, et al. Emergency cricothyrotomy. Mil Med. 2003;168:541–4.

Hamilton PH, Kang JJ. Emergency airway management. Mt Sinai J Med. 1997;64:292–301.

Helm M, Gries A, Mutzbauer T. Surgical approach in difficult airway management. Best Pract Res Clin Anaesthesiol. 2005;19:623–40.

Sagarin MJ, Barton ED, Chng YM, Walls RM. Airway management by US and Canadian emergency medicine residents: a multicenter analysis of more than 6,000 endotracheal intubation attempts. Ann Emerg Med. 2005;46:328–36.

Walls RM. Cricothyroidotomy. Emerg Med Clin North Am. 1988;6:725–36.

Tracheostomy Tube Malfunction

20

Deena Bengiamin and Bharath Chakravarthy

Tracheostomy tube (TT) malfunction is the source of airway compromise in patients requiring these airway devices. TT malfunction may create an airway emergency, and the timely replacement of TTs is a challenging procedure in the most experienced hands.

20.1 Indications

- Cuff rupture
  - Can lead to dislodgment
- Dislodgment
  - Most common emergency department TT complication
  - Can lead to air passage obstruction
- Obstruction
  - Caused by blood or thick, dry secretions (formed in the absence of nasopharyngeal air humidification).
  - Dried secretions or blood can act as a one-way valve, allowing air in but restricting outward flow.

20.2 Materials and Medications

- Airway suction catheter
- Oxygen humidifier
- Bougie/nasogastric (NG) tube (12 French)
- Saline
- N-Acetyl-cysteine (NAC)
- Appropriately sized endotracheal tube (ETT) or TT

20.3 Procedure

1. Supply high-flow humidified oxygen through a bag valve mask (BVM), or a non-rebreather face mask.
2. Assess clinical indicators to determine TT problem.
   (a) Indicators of cuff rupture: Air leak with BVM and loose TT.
   (b) Indicators of dislodged TT (if TT is still in the stomal opening): Subcutaneous emphysema, crepitus, and diminished or absent breath sounds.
   (c) Indicators of an obstructed TT: ±stridor and diminished or absent breath sounds.
   (d) If time allows, chest radiograph, continuous capnography, and oxygen saturation can be helpful.
3. Obstruction
   (a) Remove the inner cannula and inspect for obstruction—clean if necessary.
   (b) If this fails, 5–10 mL of saline or NAC can be squirted directly down the TT to loosen secretions.
   (c) Suction thoroughly with a suction catheter (Fig. 20.1).
   (d) In refractory cases, the TT will need replacement.
4. Replacement
   (a) Ideally, the replacement tube should be of the same type and size as the original TT.
   (b) A smaller size TT or ETT can be helpful in settings of airway compromise.
   (c) A 6–7.5-cm ETT tube may be used if a TT is unavailable.
   (d) Remove the existing TT.
   (e) Hyperextend the patient's head and neck to maximize visualization of the stoma.

D. Bengiamin, MD
Department of Emergency Medicine, University of San Francisco Fresno, Fresno, CA, USA
e-mail: dbengiamin@fresno.ucsf.edu

B. Chakravarthy, MD, MPH (✉)
Department of Emergency Medicine, University of California Irvine, Orange, CA, USA
e-mail: bchakrav@uci.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_20

- (f) Note: Careful inspection of the area is paramount because the thyroid isthmus may obscure visualization of the tracheal stoma.
- (g) Techniques
  - (i) Direct insertion
    1. As soon as possible, insert the new TT or ETT into the stoma to prevent stomal narrowing (Fig. 20.2).
    2. Inflate the new TT/ETT cuff.
  - (ii) Bougie or NG tube
    1. Lubricate the TT or ETT tube.
    2. Lubricate a bougie or 12-French NG tube.
    3. Insert the lubricated bougie or NG tube into the TT or ETT.
    4. Insert the bougie or NG tube into stoma and advance into the trachea (Fig. 20.3a).
    5. Direct the NG tube or bougie caudad toward the lower tracheobronchial tree.
    6. Do not advance more than 7 cm.
    7. If resistance is noted:
       - (a) Either the operator has reached a terminal bronchiole or is in a false passage.
       - (b) Do not force bougie/NG tube farther at this point.
       - (c) Use clinical judgment (bougie/ETT depth, palpation) to determine likely placement.
    8. Advance TT or NG tube over bougie or NG tube is in trachea (Fig. 20.3b).
    9. After the TT is in place, remove the bougie/NG tube.
  - (iii) The fingertip technique
    1. Insert a gloved forefinger into tracheal stoma (Fig. 20.4a).
    2. Formulate a mental plan as to the direction and path of the stoma.
    3. Then place a TT or an ETT into the stoma as the finger is withdrawn (Fig. 20.4b).

5. If placement of a TT or ETT is not possible through the stoma, consider endotracheal intubation.



Fig. 20.1 (**a**) Insert the suction catheter to the appropriate depth, keeping the suction port open. (**b**) Slowly withdraw the catheter in a circular motion, keeping the suction port closed



Fig. 20.2 Insertion of the endotracheal tube (ETT) directly into the stoma



Fig. 20.3 (**a1, a2**) Insert the tracheostomy tube (TT) over the nasogastric (NG) tube or bougie, which is first inserted into the trachea. (**b1, b2**) Advance the TT over the NG tube or bougie, which serves as a guidewire



Fig. 20.4 (**a**) Insert a gloved finger into the stoma. (**b**) Insert the TT along the path while withdrawing the gloved finger. (**c**) TT in place

20.4 Pearls and Pitfalls

- Stomal closing
  - Stomal constriction begins as soon as the TT is removed or displaced.
  - Forceful attempts to replace a large TT may result in false passages and trauma.
- Tracheal stenosis
  - Constant TT cuff pressure may cause necrosis, ulceration, and granulation tissue formation, leading to tracheal narrowing.
  - Complicates TT replacement in the setting of dislodgment or obstruction.
  - Bougie use can be helpful to place a small(er) ETT until surgical dilation and/or resection can be achieved.
- Creation of a false lumen during recannulation
  - Subcutaneous emphysema will be an early indicator of this.
  - Early confirmation of correct placement of TT by confirming:
    - Continuous end-tidal CO_2 monitoring
    - Equal chest rise
    - Bilateral breath sounds
- Unrecognized trachea–innominate artery fistula (Fig. 20.5)
  - Usually occurs within 3–4 weeks of placement
  - Presentation: Bleeding around the tracheostomy tube (>10 mL) or massive hemoptysis
  - Requires
    - ETT cuff overinflation to compress the fistula.
    - Digital pressure on stoma may be helpful to tamponade the bleeding.
    - Place stomal ETT deep to bleeding fistula to protect airway.
    - Definitive surgical intervention in operating room.
  - Associated with high mortality
- Unrecognized tracheoesophageal fistula
  - Usually iatrogenic injury from TT placement or NG tube erosion
  - Presentation: Dyspnea, copious TT secretions, recurrent food aspiration, and gastric distention
  - Requires
    - Bronchoscopy or swallowing studies to confirm diagnosis
    - Surgical repair or stenting



Fig. 20.5 Anatomical relationship between the trachea and the innominate artery. *TIF* trachea–innominate artery fistula

Selected Reading

De Leyn P, Bedert L, Delcroix M, et al. Tracheotomy: clinical review and guidelines. Eur J Cardiothorac Surg. 2007;32:412–21.

Dobiesx VA, Miller SA, Pitzele MJ. Complications of tracheostomies. In: Wolfson AB, Hendey GW, Ling LJ, Rosen CL, Scheider JJ, Sharieff GQ, editors. Harwood-Nuss' clinical practice of emergency medicine. 5th ed. Philadelphia: Lippincott Williams & Wilkins; 2009.

Epstein SK. Late complications of tracheostomy. Respir Care. 2005;40:542–9.

Friedman M, Ibrahim H. The dislodged tracheostomy tube: "fingertip" technique. Oper Technol Otolaryngol. 2002;13:217–8.

Young JS, Brady WJ, Kesser B, Mullins D. A novel method for replacement of the dislodged tracheostomy tube: the nasogastric tube "guidewire" technique. J Emerg Med. 1996;14:205–8.

Percutaneous Transtracheal Jet Ventilation

21

Clint Masterson

21.1 Indications

- Failure to control the airway by other means
- As a temporary measure while preparing for definitive airway control
- Securing the airway in crash airways in infants and small children

21.2 Contraindications

- Absolute
  - Transection of the trachea below the cricothyroid membrane
- Relative
  - Inability to identify the cricothyroid landmarks
  - Anatomical distortion to the cricothyroid membrane
  - Supraglottic obstruction (preventing gas exhalation)

21.3 Materials and Medications (Fig. 21.1)

- Betadine, chlorhexidine, or similar skin sterilization solution
- 12- to 16-gauge angiocatheter or transtracheal jet ventilation (TTJV) purpose-specific catheter
- 10-mL syringe filled with 4 mL of normal saline, 2 % lidocaine, or viscous lidocaine
- Hand-operated regulator valve
- Attach oxygen supply.
  - Connect kit tubing to wall oxygen OR.
  - Connect 7–0 endotracheal connector to bag valve mask (BVM) attached to oxygen.

C. Masterson, MD
Department of Emergency Medicine, Mayo Clinic Health System
in Fairmont, Fairmont, MN, USA
e-mail: clint@clintm.us

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_21


a
b
c
mL
3
2.5
2
1.5
1
0.5

Fig. 21.1 (**a**) Tubing and regulator valve, (**b**) commercially available catheter, (**c**) 3-mL or 10-mL syringe

21.4 Procedure

1. Attach the tubing and the hand-operated regulator valve to wall oxygen (Fig. 21.2a), and place the distal end of the tubing near the patient in preparation for ventilation.
2. Adjust regulator to maximum pressure, 50 psi if possible (Fig. 21.2b).
3. Palpate the cricothyroid membrane just distal to the thyroid prominence (Fig. 21.3).
   (a) Sterilize the area with a suitable cleansing agent.
   (b) Use the thumb and index finger of the nondominant hand to stabilize the trachea for the procedure.
4. Attach the TTJV catheter (or angiocatheter) to the syringe (Fig. 21.4).
5. Advance the catheter through the cricothyroid membrane at a 30–45° caudal direction while aspirating with the syringe (Fig. 21.5).
6. Return of air confirms entry into the trachea.
7. If lidocaine is utilized, it can then be injected to prevent spasm during the procedure.
8. Fully advance the angiocatheter and secure it while the needle and syringe are withdrawn.
9. Remove the needle, secure it to the skin, and connect it to the regulator hose.
10. Secure the distal end of the oxygen tubing (distal to the hand-operated valve) to the catheter (Fig. 21.6).
11. If a BVM is used as the oxygen source:
    (a) Attach a 3-mL syringe to the angiocatheter.
    (b) Attach the BVM with the 7–0 endotracheal tube (ETT) connector to the end of the plungerless 3-mL syringe (Fig. 21.7).
12. Operate the valve 12–20 times a minute with long periods to allow gas exhalation and exchange (Fig. 21.8).
13. Preparations should be made for a definitive airway as soon as possible—preferably within 15 min.



Fig. 21.2 (**a**) Attach tubing and the hand-operated regulator valve to wall oxygen, and (**b**) adjust regulator to maximum pressure (50 psi if possible)


Hyoid bone
Laryngeal prominence of thyroid cartilage
Cricothyroid membrane
Cricoid cartilage
Tracheal rings
Hyoid bone
Vocal cords
Cricothyroid membrane
Cricoid cartilage
Infant
Superior thyroid artery
Cricothyroid artery and vein
Cricothyroid membrane
Thyroid gland
Infrathyroid vein
Median colli vein

Fig. 21.3 Airway anatomy



Fig. 21.4 Attach the TTJV catheter to the syringe



Fig. 21.5 (**a**) Advance the catheter through the cricothyroid membrane at a 30–45° caudal direction (**b**) while aspirating with the syringe



Fig. 21.6 Secure the distal end of the oxygen tubing to the catheter


Ventilation bag
Standard endotracheal tube connector
3cc syringe barrel
14-gauge IV catheter-over needle
Thyroid cartilage
Cricoid ring
Cricothyroid membrane

Fig. 21.7 Attach the BVM with the 7–0 endotracheal tube (ETT) connector to the end of the plungerless 3-mL syringe



Fig. 21.8 Operate the valve 12–20 times a minute with long periods to allow gas exhalation and exchange

21.5 Complications

- Pneumothorax
- Pneumomediastinum
- Subcutaneous emphysema
- Catheter kink or misplacement
- Hypercarbia and respiratory acidosis
  - Use of TTJV for prolonged periods of time without adequate ventilation will elevate CO_2.
- Barotrauma
- Coughing in conscious patients
- Aspiration
- Persistent stoma

21.6 Pearls and Pitfalls

- If the wall connector does not have a pressure regulator, it can still be used although the risk of barotrauma is greater. Use the endpoint of chest rise to determine the end of each ventilation burst in this case.
- Higher pressures and lack of supraglottic air exchange are risk factors for pneumothorax. If the supraglottic area is obstructed, a Y catheter can be attached to allow gas to escape before the next insufflation.
- TTJV may or may not allow sufficient gas exchange to prevent hypercarbia. Preparations should be made to obtain a definitive airway as soon as possible.
- Endotracheal intubation may be facilitated by the high pressures insufflated in the trachea, and a repeat attempt may be performed after the transtracheal ventilation is achieved.

Selected Reading

Patel R. Percutaneous transtracheal jet ventilation. A safe, quick and temporary way to provide oxygenation and ventilation when conventional methods are unsuccessful. Chest. 1999;116:1689–94.

Roberts JR, Hedges JR. Clinical procedures in emergency medicine. Philadelphia: Saunders Elsevier; 2010.

Tintinalli J. Tintinalli's emergency medicine: a comprehensive study guide. 7th ed. New York: McGraw Hill; 2010.

Walls R. Manual of emergency airway management. 3rd ed. Philadelphia: Lippincott Williams & Wilkins; 2008.

Part III

Thoracic Procedures

Needle Thoracostomy

22

Lucas McArthur and Christian Fromm

22.1 Indications

Needle decompression thoracostomy is a procedure used in the emergent treatment of a tension pneumothorax. Tension pneumothorax is a clinical diagnosis. Decompression treatment should not be delayed in order to obtain radiographic confirmation. The following scenarios illustrate some of the clinical signs that *may* be present in such patients:

- *Awake patient* with suspected or confirmed tension pneumothorax
  - Chest pain
  - Respiratory distress
  - Decreased breath sounds with hyperresonance and/or subcutaneous emphysema
  - Trachea deviated away from the side of the pneumothorax
  - Tachycardia
  - Falling pulse oximetry (SpO_2)
  - Shock
- *Ventilated patient* with suspected or confirmed pneumothorax (often insidious)
  - Increased resistance to ventilation
  - Hypotension
  - Elevated central venous pressure
  - Tachycardia
  - Decreased breath sounds with hyperresonance and/or subcutaneous emphysema
  - Trachea deviated away from the side of the pneumothorax
  - Falling SpO_2
  - Shock
- *Injured patient* (especially with penetrating chest trauma) with suspected or confirmed tension pneumothorax
  - In arrest
  - Unexplained hypotension
  - Apnea
  - Decreased breath sounds with hyperresonance and/or subcutaneous emphysema

22.1.1 Absolute Indications

- Patient in acute respiratory distress with rapid decompensation secondary to suspected or confirmed tension pneumothorax
- Injured patient in extremis with apnea, unexplained hypotension, or arrest

22.2 Contraindications

- No absolute contraindications.

22.3 Materials

- Large-bore needle/angiocatheter (minimum of 16 gauge)
- 10-mL syringe (optional)
- One-way valve (optional)
- Betadine (povidone-iodine) swab/chlorhexidine scrub
- Tape

L. McArthur, MD (✉)
Department of Emergency Medicine, Maimonides Medical Center, New York, NY, USA
e-mail: LMcarthur@jfkhealth.org

C. Fromm, MD
Department of Emergency Medicine, Maimonides Medical Center, SUNY Downstate College of Medicine, New York, NY, USA
e-mail: cfromm@maimonidesmed.org

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_22

22.4 Procedure

1. Expose the anterior chest at the level of the second intercostal space on the affected side (Fig. 22.1). Alternatively, expose the chest wall at the level of the anterior axillary line in the fourth or fifth intercostal space on the affected side.
2. Cleanse the area with a Betadine swab or chlorhexidine scrub (Fig. 22.2).
3. Using a gloved hand, locate the second intercostal space at the midclavicular line.
   (a) The first rib is normally not felt.
   (b) The second rib is felt just below the clavicle.
   (c) The second intercostal space is the area between the second and the third ribs.

   Note: Alternatively, this procedure may also be performed on the midaxillary line in the fourth intercostal space of the affected side. The same general steps listed later are employed in this approach and care is taken to avoid the neurovascular bundles inferior to the fourth rib.
4. Insert the needle/angiocatheter perpendicular to the chest wall into the second intercostal space just above the superior edge of the third rib to avoid the intercostal neurovascular bundle (Fig. 22.3).
   (a) This step may be done with or without a syringe attached.
   (b) Local anesthesia is usually unnecessary but may be used if the patient is not in extremis.
5. Carefully walk the needle over the third rib and advance until the pleural space is entered.
   (a) Entry into the pleural space is accompanied by a "popping" sound or a sensation of "giving way."
6. If you are able to withdraw air with the syringe or hear a "hiss" of air escaping through the angiocatheter during expiration and inspiration, then placement is considered successful.
7. After removing the needle, secure the angiocatheter in place with tape (Fig. 22.4).

   Caution: Do not reinsert needle into the angiocatheter owing to the danger of sheering the angiocatheter.
8. Assess the patient and evaluate the effectiveness of the procedure.
   (a) The patient should exhibit immediate and obvious improvement in respiratory status including improved lung sounds and vital signs.
   (b) The procedure may be repeated if the patient is not improving.
   (c) Excess pleural air may be aspirated through the angiocatheter with a syringe.
9. Obtain a chest radiograph to confirm success.
   (a) Repeat in 6 h.
10. Because needle decompression is only a temporizing measure, tube thoracostomy (see Chap. 23) must be performed for definitive management of the pneumothorax.



Fig. 22.1 The preferred site for needle thoracostomy is the second intercostal space in the midclavicular line



Fig. 22.2 Prepare the skin with povidone-iodine or chlorhexidine


a
3rd
2nd
b
Superior
10–14 g IV catheter
Subcutaneous
2nd rib
3rd rib
90°
Neurovascular bundle
Pleural space
Lung

Fig. 22.3 (**a**) Insert the needle into the second intercostal space just above the superior edge of the third rib and (**b**) avoid the neurovascular bundle by approaching the skin with the needle perpendicular to the chest wall just above the superior edge of the third rib



Fig. 22.4 After removing the needle, secure the angiocatheter in place with tape

22.5 Complications

- Failure to resolve the tension pneumothorax.
  - Obese or muscular patients may require a longer needle and catheter to reach the pleural space or, alternatively, may require proceeding immediately to tube thoracostomy.
- Iatrogenic pneumothorax.
- Laceration of intercostal artery or nerve.
- Rapid re-expansion may result in the development of pulmonary edema.
- Infection.

22.6 Pearls and Pitfalls

- Use the sternum as a landmark to more easily locate the second and third ribs.
- The same procedure may also be done on the midaxillary line in the fourth intercostal space, which is usually landmarked with the nipple.
- Primary pneumothorax is unusual in those older than 40 years. Consider the presence of underlying disease in this population.

Acknowledgments We would like to thank Antonios Likourezos, MA, MPH, and Abraham Lederman for assisting with the photographs.

Selected Reading

Britten S, Palmer SH. Chest wall thickness may limit adequate drainage of tension pneumothorax by needle thoracocentesis. Emerg Med J. 1996;13:426–7.

Custalow CB. Color atlas of emergency department procedures. Philadelphia: Saunders; 2005.

Leigh-Smith S, Harris T. Tension pneumothorax—time for a re-think? Emerg Med J. 2005;22:8–16.

Roberts JR, Hedges JR. Clinical procedures in emergency medicine. 3rd ed. Philadelphia: Saunders; 1998.

Chest Tube Thoracostomy

23

Brandon R. Allen and Latha Ganti

23.1 Indications

- Spontaneous pneumothorax (large and/or symptomatic)
- Tension pneumothorax (or suspected)
- Iatrogenic pneumothorax
- Penetrating chest injuries
- Hemopneumothorax in acute trauma
- Patient in extremis with evidence of thoracic trauma
- Complicated parapneumonic effusions (empyema)
- Chylothorax/hemothorax
- Post-thoracic surgery
- Bronchopleural fistula

23.2 Contraindications

- Absolute
  - Emergent thoracotomy
- Relative
  - Coagulopathy
  - Pulmonary bullae
  - Pulmonary, pleural, or thoracic adhesions
  - Loculated pleural effusion or empyema
  - Skin infection over the chest tube insertion site

23.3 Materials and Medications

- Tube thoracostomy tray
  - #10 scalpel; 18-, 22-, and 25-gauge needles; 10-mL syringes; forceps; clamps; scissors; drape; abdominal pads; 0 or 1–0 silk suture; needle driver; curved clamp (Fig. 23.1a)
- Betadine (povidone-iodine) or other skin antiseptic preparation solution
- Lidocaine (1 % or 2 % with epinephrine)
- Appropriate chest tube size (approximate)
  - Adult male: 28–36 French
  - Adult female: 28 French
  - Child: 12–24 French
  - Infant: 12–16 French
  - Neonate: 10–12 French

Vaseline gauze
Chest drainage system (Fig. 23.1b)

B.R. Allen, MD
Department of Emergency Medicine, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: brandonrallen@ufl.edu

L. Ganti, MD, MS, MBA (✉)
Professor of Emergency Medicine, University of Central Florida,
Orlando, FL, USA

Director, SE Specialty Care Centers of Innovation, Orlando
Veterans Affairs Medical Center, Orlando, FL, USA
e-mail: lathagantimd@gmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_23


a
b
Suction system
Fluid level in collection chamber
Underwater seal bottle
S-1100-08LF
PLEUR-EVAC
SAHARA

Fig. 23.1 (**a**) Tube thoracostomy tray, (**b**) chest drainage system

23.4 **Procedure** (Fig. 23.2)

1. Sterile skin preparation with sterile drape.
2. Anesthetize the appropriate area subcutaneously up to and including the rib periosteum with 5 mL of 1 % lidocaine with epinephrine (Fig. 23.2a).
3. Using a #10 or #11 blade, make an approximately 4-cm skin incision over the desired intercostal level of entry (most often the fourth or fifth intercostal space in the midaxillary line) (Fig. 23.2b, c).

   If the incision is placed *below* the fifth intercostal space, the risk of subdiaphragmatic placement into the abdominal space is increased.
4. Bluntly dissect with a hemostat or Kelly clamp through the subcutaneous tissue to the level of the intercostal muscles with intermittent opening of the dissection instrument during advancement (Fig. 23.2d, e).
5. Digitally palpate the selected intercostal space and the superior margin of the inferior rib (pay careful attention to avoid the neurovascular bundle lying inferiorly) (Fig. 23.2f).
   - If time permits, additional analgesia is recommended at this point of the procedure.
6. Guiding the closed Kelly clamp over the upper margin of the rib, enter the chest wall into the pleural cavity. (This will require some controlled force and a twisting motion.) Once the pleural space is entered, a rush of air or fluid should occur (Fig. 23.2g).

   Uncontrolled force and a lunging motion can result in penetration to the lung, heart, liver, or spleen.
7. Open the Kelly clamp while still inside the pleural space and then withdraw while the clamp is still open to enlarge the dissected tract of entry and allow easier passage of the thoracostomy tube (TT).
8. Explore the dissected tract with a sterile finger to appreciate lung tissue and possible adhesions.
9. To estimate the length the TT is to be inserted, measure the distance between the skin incision and the apex of the lung. If preferred, place a clamp over the tube at the estimated length (Fig. 23.2h).
10. Grasp the proximal end of the TT with the large Kelly clamp and pass the tube through the thoracic cavity along the previously dissected tract.
11. Release the Kelly clamp and continue to advance the tube posteriorly and superiorly.

    Make sure all of the fenestrated holes of the TT are within the thoracic cavity to prevent unnecessary manipulation and/or replacement of the TT.
12. Once the TT is in the desired position, connect the tube to the drainage device (Fig. 42.1b). Once connected, release the cross clamp on the distal end of the TT.
13. Secure the TT to the skin with 0 or 1–0 silk or nylon suture. A simple, interrupted suture above and below the TT with each stitch wrapped tightly around the TT is recommended.

    Incomplete security of the TT leads to dislodging of the tube with routine patient movements.
14. Apply petrolatum gauze over the skin closure surrounding the TT and then apply a support dressing with 4×4 gauze and adhesive tape (4 in.).
15. Obtain a chest radiograph to confirm placement of the TT.



Fig. 23.2 Chest tube thoracostomy procedure

23.5 Complications

- Improper placement for pneumothorax
  - – Reposition if:
    - Horizontal (over diaphragm)
    - Subcutaneous
    - Placed too far into the chest (against apical pleura)
  - – Remove if:
    - Placed into the abdominal space
- Bleeding (local vs. hemothorax)
- Hemoperitoneum (liver or spleen injury)
- Tube dislodgment
- Empyema (TT introduces bacteria into the pleural space)
- Retained pneumothorax (may require second TT)
- Re-expansion pulmonary edema
- Subcutaneous emphysema

23.6 Pearls and Pitfalls

- Water seal acts as a one-way valve; if the system bubbles, there is an air leak.
- In the Pleur-evac® systems, there is an orange floater which, when static, means the desired suction pressure (usually 20 cmH_2O) has been reached.
- The negative pressure in the chest cavity equals the amount of water in water seal plus amount of suction.
- A chest tube can be removed when there is no air loss or blood for 24 h.
- When removing the tube, have the patient exhale and remove as quickly as possible.
- Leave petrolatum gauze in place for 48 h before changing it (allows wound to heal better).

Selected Reading

Ball CG, Lord J, Laupland KB, et al. Chest tube complications: how well are we training our residents? Can J Surg. 2007;50:450.

Collop NA, Kim S, Sahn SA. Analysis of tube thoracostomy performed by pulmonologists at a teaching hospital. Chest. 1997;112:709.

Dalbec DL, Krome RL. Thoracostomy. Emerg Med Clin North Am. 1986;4:441.

Miller KS, Sahn SA. Chest tubes. Indications, technique, management and complications. Chest. 1987;91:258–64.

Millikan JS, Moore EE, Steiner E, et al. Complications of tube thoracostomy for acute trauma. Am J Surg. 1980;140:738.

Thoracentesis

24

Lee Richard Donner and Michael Anana

24.1 Indications

- *Therapeutic thoracentesis* is performed to relieve dyspnea, hypoxia, or otherwise compromised respiratory function due to a large pleural effusion.
- *Diagnostic thoracentesis* is performed to aid in the diagnosis and workup of:
  - Pleural effusions of unknown cause
  - Unilateral pleural effusions
  - Pleural effusions originally determined to be due to heart failure but persisting after 3 days of diuresis

24.2 Contraindications

- Absolute
  - None
- Relative:
  - Coagulopathy, thrombocytopenia.
  - Small or loculated pleural effusion. These will increase the risk of missing the effusion and causing lung injury.
  - Positive-pressure ventilation.
  - Skin infection over the needle insertion site.

24.3 Materials and Medications

- Thoracentesis tray (commercially available kits generally include the items in the following list) (Fig. 24.1)
  - (1) Fenestrated drape
  - (1) 25-gauge × 1-in. needle
  - (1) 21-gauge × 1.5-in. needle
  - (1) 8-French catheter over 18-gauge needle
  - (1) Small plastic syringe, 5 mL
  - (1) Small plastic syringe, 10 mL
  - (1) Large plastic syringe, 50–60 mL
  - (1) Three-way stopcock
  - Specimen vials and caps
  - (1) Collection bag, 1500 mL, or vacuum container
  - (1) Tubing set
  - (1) Hemostat
  - Betadine (povidone-iodine) or other skin antiseptic preparing solution
  - 10-mL lidocaine 1 % without epinephrine



Fig. 24.1 Typical commercial thoracentesis tray

L.R. Donner, MD (✉)
Emergency Medicine Department, Lincoln Medical and Mental Health Center, New York, NY, USA
e-mail: LeeDonnerMD@gmail.com

M. Anana, MD
Emergency Department, University Hospital, Rutgers New Jersey Medical School, Newark, NJ, USA
e-mail: ananami@njms.rutgers.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_24

24.4 Procedure

1. Place patient in seated position with arms at rest on a bedside table (Fig. 24.2).
2. The location and height of the pleural effusion are confirmed by physical examination. Auscultation of decreased or absent breath sounds, dullness to percussion, and decreased tactile fremitus are physical findings to confirm the location and height of the effusion (Fig. 24.3).
3. Determine and mark the site of needle insertion. This will be at the midscapular line one or two intercostal spaces below the maximum height of the effusion as determined by a combination of imaging and physical examination (Fig. 24.4).
    - *Do not* attempt thoracentesis inferior to the eighth intercostal space because respiratory cycle and anatomical variation place the diaphragm and intra-abdominal organs at risk.
4. Prepare the skin with the sterile skin preparation and sterile drape.
5. Anesthetize the appropriate area subcutaneously using a 25-gauge needle on a 10-mL syringe. Create a wheal in the skin and then infiltrate up to and including the periosteum of the rib inferior to the landmarked space with 5 mL of 1 % lidocaine.
    - Remember that the neurovascular bundle is found at the inferior border of each rib. Keep this in mind as you approach the rib and throughout the rest of the procedure to avoid injury to these structures (Fig. 24.5).
6. Using a 22-gauge needle, slowly walk the needle up and over the superior border of the rib. Continue to advance the needle along the superior border of the rib with the syringe withdrawn and infiltrating lidocaine intermittently along the way.
7. Pleural fluid will be aspirated once the pleural space is reached. Do not advance the needle further. Deposit 1–2 mL more lidocaine. A hemostat can be placed on the needle at the level of the skin to mark the depth of the pleural space and the needle can be removed.
8. Some commercial kits may come with an adjustable depth guard to be positioned at the determined depth. On an 18-gauge catheter-over-needle device, position the depth guard to the appropriate depth determined from the prior step. If a depth guard is not available, use the index finger and thumb on the catheter at the appropriate depth. With the 5-mL syringe attached, advance the device over the superior border of the rib while aspirating, expecting pleural fluid to return again at the determined depth (Fig. 24.6).
9. When the pleural space is reached, do not advance the needle further. Advance the catheter over the needle until the hub reaches the skin. Remove the needle during expiration and immediately cover the open hub with a gloved finger to prevent development of pneumothorax. Some kits provide catheters with one-way valves to prevent air entry.
10. Attach the 50–60-mL syringe to the catheter via the three-way stopcock. Pleural fluid can be drained and transferred to appropriate collection vials for diagnostic thoracentesis. A collection bag may be attached with tubing to the third port of a three-way stopcock for larger volume evacuation in the case of a therapeutic thoracentesis. Employ a syringe pump method to drain 50–60 mL of fluid at a time to the collection bag. Fill the syringe by withdrawing the plunger while the stopcock is closed to the bag. Then, close the stopcock to the patient and pump the contents of the syringe to the bag. Next, close the syringe closed to the bag, and repeat the cycle until the desired volume is drained. A vacuum container is an alternative that simply attaches via tubing to the stopcock (Fig. 24.7).
    - If using a three-way stopcock and a device that does not have a one-way valve on the catheter, be sure to always keep the stopcock closed to the patient unless withdrawing fluid in order to decrease the risk of pneumothorax.
11. When the desired amount of pleural fluid is obtained, remove the catheter during expiration and apply an occlusive dressing.



Fig. 24.2 Patient in upright, seated position



Fig. 24.3 Determining the location and height of the pleural effusion



Fig. 24.4 Marked site for needle insertion


Intercostal vein
Intercostal artery
Intercostal nerve
Innermost intercostal muscle
Internal intercostal muscle
Enterior intercostal muscle

Fig. 24.5 The intercostal neurovascular bundle



Fig. 24.6 Needle and catheter insertion, thumb and index finger at desired depth


ARROW
stryker

Fig. 24.7 Pleural fluid collection via syringe pump method

24.5 Complications

- Pneumothorax
- Re-expansion pulmonary edema
- Hemothorax, hematoma
- Intra-abdominal organ injury
- Air embolism
- Empyema

24.6 Considerations

- If available, the use of bedside ultrasound is highly recommended because ultrasound guidance has been shown to substantially reduce the risk of pneumothorax. Before the procedure, the height, width, and depth of the effusion can be appreciated by scanning the chest and viewing the effusion through the intercostal spaces. The use of ultrasound aids in selecting the needle insertion site by:
  - Visualizing the distance the needle must pass to reach the parietal pleura
  - Confirming the thickness of the effusion in the site selected is at least a minimum of 1.5 cm
  - Providing the clinician with a view of the effusion and surrounding structures through the complete respiratory cycle

  With these items in mind, the needle insertion site can be selected with confidence and marked before beginning the procedure.
- In addition, the use of bedside ultrasound in real time will allow the clinician to visualize the needle as it passes toward and enters the pleural space. This use requires sterile probe covers.
- Re-expansion pulmonary edema is a rare but feared complication of thoracentesis. The cause is not fully understood. Historically it was thought that re-expansion pulmonary edema was caused by removing too large a volume of fluid from the pleural space (>1–1.5 L). Another theory is that re-expansion pulmonary edema is caused when great negative intrapleural pressures (<20 cmH_2O) are generated during the procedure. The low incidence of this complication has yielded inconclusive evidence.
  - In light of this, it is prudent to continue to limit the volume of pleural fluid removed to no more than 1–1.5 L. Pleural manometry is not widely available for use in the emergency department, but should also be considered if available to maintain intrapleural pressures from reaching more negative values.

24.7 Pearls and Pitfalls

- Bedside ultrasound reduces the risk of complications.
- Never attempt thoracentesis below the eighth intercostal space.
- Thoracentesis should not be performed on pleural effusions demonstrated to be less than 1–1.5 cm thick by ultrasound or on a lateral decubitus film.
- Positive-pressure ventilation mandates extreme care while performing thoracentesis because the lungs can be punctured during inflation. In addition, ventilated patients will not be able to sit upright and will need to have the procedure performed in lateral decubitus position with the effusion side down and the posterior axillary line as the needle insertion site. Alternatively, the patient can be placed supine with the head of the bed elevated to 45° and the midaxillary line as the needle insertion site.
  - Routine post-procedure radiographs are not necessary to exclude pneumothorax. Indications for post-procedure imaging include onset of chest pain during the procedure, persisting cough or chest discomfort after the procedure, air aspiration along any step of the procedure, or positive-pressure ventilation.
  - Pneumothorax rates are higher for inexperienced providers. Although an effusion compromising respiratory function is considered a clear indication for therapeutic thoracentesis, the performance of nonurgent diagnostic thoracentesis might best be delayed for those more practiced in the procedure.

Selected Reading

Dewitz A, Jones R, Goldstein J. Additional ultrasound-guided procedures. In: Ma OJ, Mateer JR, Blavias M, editors. Emergency ultrasound. 2nd ed. New York: McGraw-Hill; 2008. p. 546–50.

Feller-Kopman D, Berkowitz D, Boiselle P, Ernst A. Large-volume thoracentesis and the risk of reexpansion pulmonary edema. Ann Thorac Surg. 2007;84:1656–61.

Gordon CE, Feller-Kopman D, Balk EM, Smetana GW. Pneumothorax following thoracentesis: a systematic review and meta-analysis. Arch Intern Med. 2010;170:332–9.

Light RW. Pleural effusion. N Engl J Med. 2002;346:1971–7.

Thomsen TW, DeLaPena J, Setnik G. Videos in clinical medicine. Thoracentesis. N Engl J Med. 2006;355, e16.

Open Chest Wounds and Flail Chest

25

Jacob J. Glaser and Carlos J. Rodriguez

25.1 Background

Thoracic injuries are commonly associated with penetrating and blunt abdominal trauma and are implicated in 50–70 % of trauma deaths [1]. Cardiac tamponade, tension pneumothorax, massive hemothorax, airway obstruction, flail chest, and open pneumothorax represent the six immediately life-threatening injuries attributed to chest trauma [2]. Accordingly, they must be accurately identified and dealt with urgently.

Open pneumothorax ("sucking" chest wound) is seen in penetrating chest injuries. If the associated chest wound is greater than 2/3 the diameter of the trachea (generally anything greater than 1.5–2 cm), air can preferentially enter the intrapleural space, via the trachea, with each inspiration [3] (Fig. 25.1). This allows equilibration of pressure between the pleural space and the atmosphere, causing the lung to collapse and leading to profound hypoventilation and hypoxia.

Flail chest results from high-energy blunt, crushing chest trauma causing two or more fractures in two or more contiguous ribs. Classically, the fractures are lateral or sternal. Posterior rib fractures rarely cause flail physiology (Fig. 25.2). Flail chest has been reported to have mortality as high as 16 % [4]. This injury pattern is associated with a high incidence of underlying pneumothorax, hemothorax, pulmonary contusion, and chest wall instability. Mortality from flail chest is thought to be correlated with the degree of underlying pulmonary contusion and attendant hypoxia [2].

Both open pneumothorax and flail chest are immediately life threatening and require early appropriate management.

J.J. Glaser, MD (✉)
Combat Casualty Care Directorate, Naval Medical Research Unit,
San Antonio, TX, USA
e-mail: Jacob.glaser1@gmail.com

C.J. Rodriguez, DO
Division of Trauma Surgery, Surgical Critical Care, Walter Reed
National Military Medical Center, Bethesda, MD, USA
e-mail: Carlos.J.Rodriguez.mil@health.mil

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_25


Wound
Wound

Fig. 25.1 Air preferentially will enter the chest via the wound, collapsing the lung on the affected side


Lateral flail
Sternal flail

Fig. 25.2 Flail chest: two or more rib fractures in two or more segments. Lateral flail (most common) and sternal flail segments represented below

25.2 Initial Evaluation of Thoracic Trauma

- To the best extent possible, obtain good patient handover from the prehospital caregivers.
- Initial physical evaluation.
  - Appropriate attention should be given to the ABCs (airway, breathing, circulation) of ATLS (Advanced Trauma Life Support) management.
  - Evaluation and resuscitation are to be *concurrent* with diagnostic procedures and immediate interventions.
  - Maintain a high degree of suspicion for open chest wound in impalement injury and destructive penetrating trauma (blast injury or shotgun).
  - Maintain a high degree of suspicion for flail chest in high-energy direct impact trauma (motor vehicle crash, fall, crush injury).
- Administer high-flow O_2 with a non-rebreather mask.
  - If patient is in respiratory distress, is unstable, or has an obvious chest wall defect, consider early intubation to secure the airway.
  - Inspect the chest wall for occlusive dressings.
- Decompress the chest if tension physiology is present or suspected.
  - Immediate decompression of a suspected tension pneumothorax can be readily accomplished by removing any existing occlusive dressings *or*
  - Place a large-bore cannula over the rib, second intercostal space, or midclavicular line.
- Specific immediate management appropriate to open chest wound and flail chest (see later).
- Monitor continuous pulse oximetry and electrocardiogram.
- Initiate crystalloid resuscitation via large-bore intravenous (IV) access.
  - Early mobilization of blood products if ongoing hemorrhage or expectation of excessive blood loss.
  - Placement of resuscitative lines concurrent with management of respiratory parameters.
- Early surgical consultation for management of intrathoracic injuries and management of chest wall defect.

25.3 Open Pneumothorax ("Sucking Chest Wound")

- Immediate management requires attention to airway and respirations.
  - If in respiratory distress, *intubate*.
- Close the chest wall defect with an occlusive three-sided dressing.
  - This includes a valve mechanism that allows trapped air to escape, preventing tension (Fig. 25.3).
  - An IV bag cut to fit the wound and then taped on three sides can be useful in an emergent situation.
  - Commercial products are available and appropriate for smaller wounds, including the Asherman Chest Seal and HyFin Vent.
- A completely occlusive dressing may quickly convert an open chest wound into a tension pneumothorax [2, 3, 5] and therefore should *never* be done.
  - The patient and dressing must be serially checked to ensure that trapped air is allowed to escape.
  - If there is any doubt, immediately remove the dressing and replace it with an appropriate dressing.
- These maneuvers are a bridge to definitive care.
- When the timing is appropriate (i.e., time and resources are available), perform a formal tube thoracostomy and convert to a completely occlusive dressing over the wound.
  - Avoid placing the tube through the open wound.
- Once tube thoracostomy, placement of occlusive dressing, and the airway are secured, the pathophysiology of the open pneumothorax becomes inconsequential.
- Immediate consultation with surgery for definitive care of associated intrathoracic injuries is required.
  - The patient may need urgent thoracotomy to treat associated injuries.
  - Irrigation and debridement should take place in the operating room.
  - Depending on injury severity, the patient may need chest wall reconstruction.



Fig. 25.3 Three-sided dressing, allowing a valve to decompress tension in the chest

25.4 Flail Chest

- Diagnosis is made from mechanism and examination, not radiographically.
  - With inspiration, the affected chest will move inward with negative pressure.
  - With expiration, the affected chest will move outward.
  - Patients who are intubated on positive pressure (and not spontaneously breathing) will often not show this paradoxical chest movement.
- Attention *must* be paid to presumed underlying blunt lung injury and contusion.
  - The degree of underlying contusion (not the flail segment itself) is directly related to the degree of hypoxia and associated morbidity and mortality [2, 3].
  - There should be a low threshold for intubation to manage respiratory distress, hypoxemia, or hemodynamic instability.
  - The patient is at high risk for hemothorax and pneumothorax requiring tube thoracostomy.
- Abdominal injuries may be present in up to 15 % of patients [2].
- After initial stabilization, treatment is supportive.
  - Intensive care unit admission for management of underlying pulmonary contusion.
  - Pain control in the form of epidural or regional block for excellent pain control.
  - Close attention to pulmonary toilet and lung re-expansion.
  - Patients require observation and treatment in a monitored setting until ensured that respiratory parameters and oxygenation are improving.
- Surgical stabilization of the chest wall is rarely performed.
  - Early surgical consultation for chest wall fixation in questionable cases is warranted.

References

1. LoCicero J, Mattox KL. Epidemiology of chest trauma. Surg Clin North Am. 1989;69:15–9.
2. Pietzman AB, Schwab CW, Yealy DM, editors. The trauma manual. 2nd ed. Philadelphia: Wolters Kluwer Health; 2000.
3. Weinberg JA, Croce MA. Chapter 33: Chest wall injury. In: Flint L, Meredith JW, Schwab CW, editors. Trauma: contemporary principles and therapy. 1st ed. Philadelphia: Lippincott Williams & Williams; 2007.
4. Clark GC, Schecter WP, Trunkey DD. Variables affecting outcome in blunt chest trauma: flail chest vs. pulmonary contusion. J Trauma. 1988;28:298–304.
5. Borden Institute Walter Reed Army Medical Center. Emergency war surgery. 3rd ed. Washington: Office of the Surgeon General U.S. Army, Borden Institute; 2004.

26 Emergent Resuscitative Thoracotomy, Open Cardiac Massage, and Aortic Occlusion

Kevin M. Jones and Jay Menaker

26.1 Indications

- Penetrating chest trauma with recent or immanent loss of vital signs
- Consider in blunt trauma with pericardial tamponade or exsanguination where aortic occlusion may provide proximal control

26.2 Contraindications

Absolute
  - Prolonged cessation of vital signs
  - Injury profile obviously incompatible with life
  - Absence of surgical services to whom care can be transferred

Relative
  - None

26.3 Materials and Medications (Fig. 26.1)

- Betadine (povidone-iodine) for rapid skin preparation
- #10 Scalpel
- Mayo or long Metzenbaum scissors
- Finochietto retractor (rib spreader)
- Long DeBakey or other tissue forceps (2)
- Satinsky vascular clamp and/or straight vascular clamp
- Long needle holders (2)
- Lebsche knife or sternal osteotome with hammer
- Lap sponges or gauze pads

K.M. Jones, MD (✉)
Trauma and Surgical Critical Care, R Adams Cowley Shock Trauma Center, University of Maryland Medical Center, Baltimore, MD, USA
e-mail: KJones12@umm.edu

J. Menaker, MD
Departments of Surgery and Emergency Medicine, R Adams Cowley Shock Trauma Center, University of Maryland Medical Center, Baltimore, MD, USA
e-mail: jmenaker@umm.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_26


Long-handled needle driver
DeBakey aortic occlusion clamp
Tissue forceps
Statinsky clamp
Metzenbaum scissors
Lebsche knife and mallet
Finochietto retractor

Fig. 26.1 Basic components of an emergency thoracotomy tray: Lebsche knife and mallet for crossing sternum (bone-cutting forceps or sternal osteotome would also suffice), Finochietto retractor, atraumatic vascular clamps (a Satinsky clamp and a DeBakey aortic occlusion clamp), long-handled needle driver, tissue forceps, and Metzenbaum scissors. *Not illustrated* Scalpel with #10 or #20 blade, Mayo scissors

26.4 Procedure

26.4.1 Resuscitative Thoracotomy and Open Cardiac Massage

1. Rapidly prepare the entire anterior and bilateral chest with Betadine.
2. Using a scalpel, incise the skin and subcutaneous tissue from just right of the sternum to the anterior margin of the left latissimus dorsi, following the curvature of the inframammary crease or the fourth or fifth intercostal space (Fig. 26.2).
   - This incision is often made too low on the patient's chest. It should extend across the sternum, not at the level of the xiphoid. Upward retraction of the breast may help provide access to the fourth or fifth intercostal space, where the incision should be located.
3. Bluntly enter the right pleural space through the fourth or fifth intercostal space.
4. Using scissors, cut the intercostal muscles, dividing between the fourth and the fifth ribs from the sternum to the posterior axillary line.
5. If better exposure to the heart is desired, some practitioners advocate extending the incision across the sternum using a Lebsche knife, sternal osteotome, or bone-cutting forceps at this time (Fig. 26.3).
   - If the thoracotomy incision extends to or through the sternum, tie off the internal mammary arteries before closing the chest should the patient be successfully resuscitated, because these will have been divided with the incision.
6. Insert a Finochietto retractor and retract the ribs in order to gain access to the left chest and expose the pericardium (Figs. 26.4 and 26.5).
   - Insert a Finochietto retractor with the rack and pinion bar down and lateral, as in Fig. 26.4, so as not to interfere with extension of the thoracotomy across the sternum into a clamshell maneuver if needed.
7. If massive left pleural hemorrhage is encountered, investigate and control the source at this time.
8. Using tissue forceps, raise a portion of the pericardium anterior to the phrenic nerve, and enter the pericardium using scissors (Fig. 26.6).
9. Widely open the pericardium with scissors, cutting in a cranial-caudal direction anterior to the phrenic nerve and deliver the heart (Fig. 26.7).
10. If hemopericardium is encountered, investigate for and initiate appropriate repair of identified cardiac injuries.
11. Initiate open cardiac massage by cupping the heart between the flattened palmar aspect of the fingers of both hands and rhythmically compressing the heart from apex to base, relaxing completely between compressions to allow filling (Fig. 26.8).

26.4.2 Aortic Occlusion

1. Expose the posterior aspect of the left mediastinum by having an assistant retract the left lung superomedially, dividing the inferior pulmonary ligament if necessary (Fig. 26.9).
2. Bluntly dissect the pleura separating the pleural and mediastinal space just anterior to the vertebral bodies, exposing the aorta (Fig. 26.9).
3. Completely encircle the aorta with the finger of the nondominant hand (Fig. 26.10).
   - Differentiating the aorta from the esophagus when the patient is in a state of profound shock is very difficult. Having an assistant pass an orogastric tube may help distinguish the two. The aorta should be the most posterior structure, lying immediately on the anterior aspect of the vertebral bodies.
4. With the aorta completely encircled, place a vascular clamp across the aorta and verify by sight and feel that the complete vessel is occluded within the clamp (Fig. 26.11).



Fig. 26.2 Raise the left arm above the head. Make an incision along the left fourth intercostal space, just below the nipple in a male or at the inframamillary crease in a female



Fig. 26.3 Use a Lebsche knife to extend the incision across the sternum to improve exposure to the heart



Fig. 26.4 Finochietto retractor placed through the fourth intercostal anterolateral incision. Note the rack and pinion bar placed posterolaterally, where it will not impede access to the midline



Fig. 26.5 Finochietto retractor extended, exposing the left pleural space and the pericardium. In this case the sternum has been divided as above, and the resultant window into the right pleural space is seen anterior to the pericardium. The lung is deflated in this postmortem picture but would be far more an obstacle in the actively ventilated patient. The clamp seen in the upper portion of the picture is reapproximating the pericardium, which has previously been divided, for the sake of illustration



Fig. 26.6 The pericardium is lifted with tissue forceps and opened with a nick using scissors. The phrenic nerve is easily visualized running cranial-caudal just below the scissors in this picture



Fig. 26.7 Open the pericardium widely in the cephalad-caudad plane anterior to the phrenic nerve, taking care not to damage the phrenic nerve



Fig. 26.8 (**a**) Deliver the heart from the pericardium, rapidly assess for cardiac injury requiring damage-control repair; (**b**) initiate open cardiac massage



Fig. 26.9 The heart and lung are retracted superomedially, allowing visualization of the left posterior mediastinal pleura; the aorta lies just anterior to the vertebral bodies and has been previously isolated through the pleural interruptions seen here. The heart and lung are assertively retracted here for the benefit of illustration of the posterior mediastinum. Such retraction would completely occlude venous return



Fig. 26.10 After bluntly dissecting the mediastinal pleura, the aorta is looped using a finger of the nondominant hand



Fig. 26.11 (**a**) A vascular clamp (a Satinsky clamp is used here, although any large atraumatic vascular clamp can be used) is applied across the descending aorta, (**b**) followed by visual and tactile confirmation that the aorta is completely occluded

26.5 Complications

- Injury to care providers, by means of scalpel, needlestick, or sharp foreign body, is the principal concern.
- Post-emergency department thoracotomy infections are rare, even given the less than optimal sterile conditions.
- Damage to lung parenchyma during the initial incision is common and often leads to air leak in survivors.
- Neglect of the mammary arteries, often divided during emergent thoracotomy and not briskly bleeding in the shock state, will result in intrathoracic hemorrhage if not tied off.

Selected Reading

Bartlett RL. Resuscitative thoracotomy. In: Roberts JR, Hedges JR, editors. Clinical procedures in emergency medicine. 3rd ed. Philadelphia: WB Saunders; 1998.

Feliciano DV, Mattox KL. Indications, technique, and pitfalls of emergency center thoracotomy. Surg Rounds. 1981;4:32.

Siemans R, Polk Jr MC. Indications for thoracotomy following penetrating thoracic injury. J Trauma. 1977;17:493.

Wall Jr MJ, Huh J, Mattox KL. Indications and techniques of thoracotomy. In: Feliciano DV, Mattox KL, Moore EE, editors. Trauma. 6th ed. New York: McGraw Hill; 2008.

Lung Ultrasonography

27

Ali H. Dabaja, L. Connor Nickels, and Rohit Pravin Patel

27.1 Indications

- Evaluation of respiratory failure and insufficiency due to pneumothorax, pleural effusion, pulmonary edema, acute respiratory distress syndrome (ARDS), and alveolar consolidation (atelectasis, pneumonia, aspiration)
- Monitoring progress of diseases such as pulmonary edema and pneumothorax
- Procedural guidance during pleural fluid removal or pneumothorax treatment
- Procedural guidance for chest tube placement for complex pleural effusions, hemothorax, pneumothorax, and other pleural diseases

27.2 Contraindications

- None

27.3 Materials

- Ultrasound equipment/machine, ultrasonography gel
- Microconvex or phased-array cardiac probe for sufficient evaluation of lung artifact (use abdominal preset). Linear-array probes, or vascular probes, can be used for more detailed evaluation of the pleura, although this is insufficient for penetration to deeper structures.
- Sterile materials and equipment where appropriate

27.4 Preparations

- Clean ultrasound equipment and use sterile operating procedures and ultrasound conductive gel whenever adequate.
- Ultrasound positioning. Place ultrasound device where it is easily accessible and in adequate view.
- Proper environment. Minimize light interference. Close shades and lights where appropriate.
- Position the patient. This helps optimize and expedite the examination. Supine position should be adequate for critically ill patients. Upright positioning is best for all others, with arms abducted above the head or spaced away from the chest to allow space for the probe. Patients should be moved to the edge of the bed. Uncover appropriate areas, including anterior and lateral chest walls.
- Equipment use. Turn on equipment, enter patient data, and select proper probe (cardiac probe or abdominal probe with abdomen presets). Depth and gain should be adjusted accordingly, where depths in the range of 4–10 cm give proper evaluation of more superficial and deeper structures, respectively.

A.H. Dabaja, DO
Division of Critical Care, Department of Anesthesia, University of Florida Health, Gainesville, FL, USA
e-mail: ali.dabaja@gmail.com

L.C. Nickels, MD, RDMS (✉) • R.P. Patel, MD
Department of Emergency Medicine, University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: cnickels@ufl.edu; rohitpatel@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_27

27.5 Procedure

1. Probe position (Fig. 27.1). Start examination at the midclavicular level at the space between the second and the third ribs. Probe positioning should be perpendicular to the ribs (longitudinal positioning) with the ultrasound marker pointed cephalad. This should place the most superficial structures at the top, with deeper structures at the bottom of the monitor. Upon completion, probe positioning can be mapped to evaluate three or four additional areas, typically between the anterior and the posterior axillary lines. Lateral views with the probe should be most posterior, typically along the posterior axillary line, tracking caudad toward the diaphragm. PLAPS (posterolateral alveolar and/or pleural syndrome) pointed posteriorly should also be evaluated, specifically in supine patients. PLAPS is lateral to the scapula and typically requires that the patient be lifted off the bed from one side.
2. Identify the "bat sign" (Fig. 27.2). The initial view observed should be a window of lung flanked by two rib shadows. This view, termed the "bat sign," should now allow evaluation of the parietal and visceral pleura, seen most superficial as echogenic line (approximately 0.5 cm below start of rib shadows), subsequent lung sliding, and other findings such as "A" and "B" lines, as well as abnormal lung tissue.
3. Identify "A lines" (Fig. 27.3). A lines indicate air. These are multiple echogenic lines appearing horizontally in sequence deep to the pleural line. This artifact represents reverberations of the pleura and can be found in aerated lungs, which can be normal or abnormal (e.g., pulmonary embolism, chronic obstructive pulmonary disease [COPD]). The first true A line, denoted "A1," is found equidistant from the chest wall to the pleural line. Many other A lines might be seen and are denoted "A'" lines. Subsequent equidistant A lines are "A2," "A3," and so on.
4. Identify "B lines" (Fig. 27.4). These artifacts appear in well-aerated lung and are vertical echogenic lines (ray, flashlight, lung rockets) transmitted from the pleura to the deeper parts of the lung on the ultrasound monitor field. They are due to thickened interlobular septa and represent alveolar fluid surrounded by air. True B lines arise from the pleural line and shoot all the way down to the far lung fields, whereas "comet tails" are seen only close to the pleural and are sometimes referred to as "shimmering" or "glimmering" during movement of the pleural line. When multiple B lines are seen in a patient, it is sometimes referred to as "lung rockets" or "flashlights" because many rays are shooting from the pleura. Even though most of the time B lines represent pulmonary edema, they can be seen in other conditions such as aspiration, pulmonary fibrosis, acute respiratory distress syndrome (ARDS), and pneumonia.
5. Identify lung sliding (Fig. 27.5). Lung sliding identifies movement of a normal parietal-visceral interface. Patient breathing causes a rhythmic movement of parietal against the visceral pleura appearing as movement of the hyperechoic line. M-mode can be used to show a timed clip of this through a still image and should only be used as a method of reporting or saving for documentation purposes. A "lung point" is an area adjacent to lung sliding (parietal pleura) that is devoid of movement. This is highly specific for pneumothorax. If one suspects a pneumothorax, quantification of the size can be made by evaluation at the anterior lung points and movement toward the lateral wall of the chest. The more rib spaces found to have absent lung sliding, the larger the pneumothorax. Lung sliding (Fig. 27.5) can be evaluated with M-mode, which can help identify a normal parietal-visceral interface at that level. Obtain an adequate two-dimensional view ("bat sign") and press the "M-mode" option on the equipment. A normal interface appears as multiple hyperechoic lines, the pleura (termed "seashore"; Fig. 27.5a), followed by a sandlike pattern, the lung tissue. This pattern together is termed a "seashore sign." Air that disrupts the parietal-visceral interface, as found within a pneumothorax, is identified as horizontal repeating echogenic lines, similar to a barcode (Fig. 27.5b), and is termed "stratosphere sign." M-mode can be discontinued.
   - Lung sliding can be absent in conditions other than pneumothorax: apnea, right or left bronchial intubation, lung collapse (blebs), pneumonia, and pulmonary fibrosis.
6. Identify lung pulse. This appears as a shimmering of the pleural line due to cardiac activity. This is most apparent on the left side of the chest, closest to the heart. This helps to exclude pneumothorax as well.
7. Move posteriorly. Move the ultrasound probe laterally and posteriorly to the PLAPS point. The transducer can be directed toward the center of the patient's body in supine patients. Pleural effusions and consolidations are found in the dependent areas of the lung.
8. Move caudally. With the marker still pointing cephalad, move along the posterior axillary line in two or three additional rib spaces. Identification of pleural disease and other pathology requires multiple views and will aid in evaluating the extent of the disease. This will also allow for identification of boundaries of the lung, such as the diaphragm. Identification of the diaphragm is most critical to determine location of fluid.

9. Identify the diaphragm and liver and/or spleen (Fig. 27.6). Along the posterior axillary line, or the posterior chest wall, move the probe caudad to identify the diaphragm. This appears as an echogenic curvilinear structure, with the liver or spleen being subdiaphragmatic and typically of different echogenicity than the lung. Many times the diaphragm is very high in the supine critically ill patient. Massive edema and obesity may also degrade image quality in this location.
    - Always identify the diaphragm. Hypoechoic fluid surrounding the liver or spleen can appear as a pleural effusion and must not be mistaken as such. In addition, lung tissue may mimic hepatic tissue in certain diseases such as dense consolidations termed "hepatization" of the lung. Proper probe positioning, clear identification of the diaphragm, subdiaphragmatic structures, and lung are crucial. This is a common error in novice operators owing to the confusion of the hepatorenal or splenorenal recess for the diaphragm.
    - Identifying the diaphragm can be technically difficult depending on patient position, size, and clinical condition. It maybe useful to start below the diaphragm, first identifying the hepatorenal recess (liver and kidney view interface) and then moving cephalad until the lung and diaphragm are visualized. In addition as ribs change their orientation anatomically, the probe may need to be adjusted while still in the longitudinal axis. Moving the probe clockwise and counterclockwise may be of benefit to bring into view the lung, the diaphragm, and the subdiaphragmatic structures.
10. Identify pleural effusions (Fig. 27.6). Confirming the presence of pleural effusions requires identifying anechoic material between the pleura and the lung. This can be seen as lung movement in an undulating pattern, which typically is facilitated by cardiac activity and respirations. This is termed "jellyfish sign," where the lung flaps as it freely floats in the effusion. Floating debris can also confirm effusion, termed "plankton sign." It is also important to identify the depth of the chest wall to the pleural fluid in order to determine the best location/depth of needle insertion when attempting thoracentesis or chest tube insertion. The challenge is to find a safe path for needle insertion. The key when using ultrasound as guidance is that the angle of the needle/syringe assembly must duplicate the angle of the probe. The time between scan and needle insertion must also be minimized. Real-time guidance is not required. In patients who are obese or edematous, skin indentation during probe placement can result in underestimation of depth of needle insertion required and must be taken into account. Safety margin of thoracentesis is thought to be 10 mm of visceral-parietal distance. Dry taps may be due to loculations the blocking needle, needle plugs, patient movement from scan to tap, and poor angle selection.
    - Exudates, empyemas, and hemothoraces may appear more echogenic, unlike, for example, a transudative effusion that could be anechoic. Complex effusions can also appear as heterogeneous and echogenic. The consistency of the effusion can make identification technically difficult because this can limit lung motion. Sometimes the operator may think there is no effusion when there is an echo-dense effusion.
11. Identify consolidations (Fig. 27.7). Compressed lung appears with alveolar consolidation pattern (tissue-like sign). Alveolar consolidations are devoid typically of air and appear as tissue density; these can be atelectasis, pneumonia, aspiration, or other diseased lung. "Hepatization" of the lung is typical, where the images mimic liver tissue. Images may also have hyperechoic foci representing air bronchograms, which would indicate pneumonia. Probe location should be correlated with an anatomical lobular or segmental area.
    - Lung may slide into the effusion during the respiratory cycle and can be problematic during needle insertion, causing pneumothorax or abnormal wire placement during the performance of pigtail chest tube catheters. This is called a "curtain sign."
12. Sinusoid sign (Fig. 27.8). M-mode is placed in the center of the visible lung when a large amount of pleural fluid is seen. A sinusoid sign strengthens the operator's determination that pleural fluid is present and that the pleural fluid is not necessarily compromising lung dynamics. If the sinusoid sign is absent, it may indicate a "trapped" lung dynamic.
13. Assessment and clinical decision making. Upon completion of ultrasonography of bilateral lung fields, clinical decision-making tools may be of benefit, especially in undifferentiated respiratory failure. A protocol has been developed to organize the exam of a respiratory failure patient (on noninvasive or invasive ventilation only). The BLUE protocol assesses patients based on findings (e.g., A lines, B lines, lung sliding) of both lungs and incorporates them into an algorithm. With acceptable sensitivities and specificities, practitioners can diagnose pulmonary edema, pneumonia, pneumothorax, and COPD/asthma with the BLUE protocol.



Fig. 27.1 *Black circles* indicate possible ultrasound view points. These are just guides, and one may view a few interspaces left/right and cephalad/caudad from each point to obtain better views


Abd/General
C4-1/CH4MHz
DR60/M3/P2
G70/E1/100%
MI1.2 TIs0.4
6.0 cm
17 Hz
ZSI 0
Cine

Fig. 27.2 Typical bat sign with rib shadows (*arrowhead*) that surround the pleura (*black arrow*) and lung tissue. Incidentally, A lines (*white arrow*) are seen


Abd/General
C4-1/CH4MHz
DR60/M3/P2
G86/E1/100%
MI1.3 TIs0.4
10.0 cm
14 Hz
ZSI 40
Text

Fig. 27.3 Rib shadows can be seen, with multiple A lines (*arrows*)


LEFT
Abd/General
C4-1/CH4MHz
DR60/M3/P2
G86/E1/100%
MI1.1 TIs0.3
22.0 cm
10 Hz
ZSI -60
Cine

Fig. 27.4 Two B lines can be appreciated (*arrows*)


a
Vasc/Carotid
L8-3/7.0MHz
DR60/M3/P2
G76/E1/100%
MI1.3 TIs0.2
6.0 cm
10 Hz
ZSI 0
Cine
0.0
19.7
G70
Med
M2
DR60
P0
0.0
2.0
4.0
6.0
b
RIGHT
Vasc/Carotid
L8-3/7.0MHz
DR60/M3/P2
G70/E1/100%
MI1.3 TIs0.1
4.0 cm
10 Hz
ZSI 40
Cine
0.0
4.9
G70
Med
M2
DR60
P0
0.0
2.0
4.0

Fig. 27.5 (**a**) M-mode identifies the seashore sign, with the pleura (*arrows*) and the lung parenchyma (*arrowhead*) together producing an image similar to a seashore. (**b**) M-mode shows the stratosphere or barcode sign. *White arrows* indicate the pleura, and the *large triangle* shows an area of artifact from movement. Artifact from movement can be distinguished by a similar pattern change above and below the pleural line. On either side of the bracket is a continued horizontal line pattern typical of absent lung sliding


RIGHT
Abd/General
C4-1/CH4MHz
DR60/M3/P2
G70/E1/100%
MI1.3 TIs0.4
16.0 cm
11 Hz
ZSI 0
Cine

Fig. 27.6 Diaphragm (*white arrow*), liver (*white arrowhead*), lung (*black arrow*), and anechoic fluid, likely an effusion (*open arrowhead*). Incidentally, hyperechoic foci in the lung tissue, likely representing air bronchograms, can be seen


Gen THI
S MB
Abd
P21
97%
MI
1.2
TIS
0.8
255
A
B
10

Fig. 27.7 Lung here appears as tissue density, likely representing the alveolar consolidation pattern seen in pneumonia, and is termed “hepatization” and “tissue-like sign”


LEFT
Abd/General
C4-1/H3.5MHz
DR60/M3/P2
G80/E1/100%
MI1.4 TIs0.4
16.0 cm
10 Hz
ZSI 10
Cine
0.0 12.2
0.0
4.0
8.0
12
16
G70
Med
M2
DR65
P0

Fig. 27.8 In M-mode, identification of pleural effusion becomes evident with the sinusoidal sign (*arrowhead*) and identification of pleural fluid (*arrow*)

Selected Reading

Levitov A, Mayo PH, Slonim AD. Ultrasound evaluation of the lung. In: Critical care ultrasonography. New York: McGraw-Hill; 2009.

Lichtenstein DA, Menu Y. A bedside ultrasound sign ruling out pneumothorax in the critically ill. Lung sliding. Chest. 1995;108: 1345–8.

Lichtenstein DA, Meziere GA. A lung ultrasound sign allowing bedside distinction between pulmonary edema and COPD: the comet-tail artifact. Intensive Care Med. 1998;24:1331–4.

Lichtenstein DA, Meziere GA. Relevance of the lung ultrasound in the diagnosis of acute respiratory failure: the BLUE protocol. Chest. 2008;134:117–25.

Mayo PH, Doelken P. Pleural ultrasonography. Clin Chest Med. 2006;27:215–27.

Mayo PH, Goltz HR, Tafreshi M, Doelken P. Safety of ultrasound-guided thoracentesis in patients receiving mechanical ventilation. Chest. 2004;125:1059–62.

Part IV

Cardiac Procedures

Repair of Cardiac Injuries

28

Ronald Tesoriero

Whether performed by an emergency physician or a surgeon, the majority of cardiac repairs performed at emergency department thoracotomy will be temporary in nature and require further revision in the operating room. This chapter's main focus is the temporary control of cardiac injuries.

28.1 Indications

- Wounds to the heart in patients presenting with pulseless electrical activity (PEA) or asystole with evidence of cardiac tamponade
    - Penetrating wounds: <15 min of prehospital cardiopulmonary resuscitation (CPR)
    - Blunt wounds: <10 min of prehospital cardiopulmonary resuscitation (CPR)

28.2 Contraindications

- Absolute
    - Presenting rhythm of asystole and no evidence of pericardial tamponade on Focused Assessment with Sonography for Trauma (FAST)
- Relative
    - None

28.3 Materials and Medications

- Diagnostic ultrasound
- Emergency department thoracotomy tray (Fig. 28.1)
    - Sterile drapes, #10 scalpel, curved Mayo scissors, Finochietto retractor, Lebsche sternal knife and mallet, forceps, curved Metzenbaum scissors, surgical skin stapler, Foley catheter, clamps, needle driver, 2–0 and 3–0 polypropylene suture on MH or SH (noncutting) needle, Satinsky vascular clamps
- Betadine (povidone-iodine) or other skin antiseptic preparing solution
- Defibrillator and internal cardiac panels
- Epinephrine

R. Tesoriero, MD
Department of Surgical Critical Care,
University of Maryland School of Medicine,
R Adams Cowley Shock Trauma Center,
Baltimore, MD, USA
e-mail: rtesoriero@umm.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_28



Fig. 28.1 Emergency department thoracotomy tray. *Left to right*: Scalpel, curved Mayo scissors, Finochietto rib spreader, DeBakey forceps, Metzenbaum scissors, needle driver, Lebsche knife and mallet, Satinsky vascular clamp, aortic clamp, bone cutter

28.4 Procedure

1. Identify the pericardium anterior to the phrenic nerve, pinch it between the fingers, and enter it by making a nick with the Metzenbaum scissors. Then open the pericardium longitudinally anterior to the phrenic nerve.
2. If the heart is not contracting effectively (PEA, asystole, fibrillation), immediately begin internal cardiac massage.
   - Unless the injury is so large that it cannot be controlled, taking time out at this point to repair the injury may lead to significant acidosis and inability to reestablish a perfusing rhythm.
3. While continuing internal cardiac massage, identify the area of injury and attempt to control it with manual pressure; if a larger wound, use a Foley catheter to prevent continued bleeding.
4. If necessary owing to the location of injury, extend the incision to a bilateral anterolateral thoracotomy and transect the sternum with a Lebsche knife and mallet or heavy shears.
5. If, after several minutes of internal massage and appropriate red blood cell and plasma transfusion, the patient remains in PEA or asystole, irrigate the heart with warmed saline and administer intravenous (IV) or intracardiac epinephrine.
6. If the heart enters ventricular fibrillation or ventricular tachycardia, cardiovert with internal paddles applied directly to the heart with an energy between 10 and 30 J.
7. Once a perfusing rhythm is reestablished, or if on initial evaluation the wound is so large that it cannot be controlled and will require immediate repair before internal massage can be effective, proceed to cardiac repair.
8. Choose the simplest method that will allow control of the injury until definitive repair can be performed in the operating room.
   (a) Injuries to the atrium: The pliable nature of the atria will often allow placement of a Satinsky clamp for control followed by repair with a running 3–0 polypropylene suture (Fig. 28.2).
   (b) Small injuries to the ventricles: Control the injury with direct manual pressure and close with either interrupted 3–0 polypropylene suture or a surgical skin stapler (Figs. 28.3 and 28.4).
   (c) Medium to large injuries to the ventricle: Attempt to control the wound by placing a Foley catheter through it, then blow up the balloon and apply gentle traction. Either staple or suture the wound closed before deflating the balloon and removing the catheter (Fig. 28.5).
      - Place an occluding clamp on the open end of the catheter or blood loss will continue through the catheter
      - Avoid excessive traction on the Foley because it will pull through the ventricle and make the hole larger
   (d) Extensive or inaccessible injury: Perform temporary inflow occlusion to the heart by manually compressing the right atrium against the heart so that it cannot fill. The heart will likely immediately enter PEA, fibrillation, or asystole giving the physician a couple of minutes to gain control of the injury before the patient becomes unrecoverable.
   (e) Injuries in proximity to coronary vessels: To avoid compression of the vessel, perform a horizontal mattress suture that passes beneath the artery. Teflon pledgets may assist in the repair (Fig. 28.6).



Fig. 28.2 Position the Finochietto retractor with the closed end toward the axilla. A Foley catheter may be used for initial control of large cardiac lacerations



Fig. 28.3 Atrial injuries may be quickly controlled with a Satinsky clamp followed by repair with a 3–0 polypropylene suture



Fig. 28.4 Injuries may be controlled with direct manual pressure and closed with interrupted 3–0 polypropylene suture



Fig. 28.6 Lacerations in close proximity to coronary vessels can be controlled with horizontal mattress sutures passed beneath the artery to avoid coronary arterial compression



Fig. 28.5 A surgical skin stapler is a quick way to gain initial control of simple cardiac lacerations with minimal risk to the provider

28.5 Complications

- Cardiac and/or pulmonary laceration during entry into the chest
- Bleeding
- Delayed hemorrhage (failure to control internal mammary artery, disruption of sutures or staples)
- Infections: empyema and sternal infection
- Missed intracardiac valvular or septal injury (echocardiography should be performed after repair is complete)
- Air embolus

28.6 Pearls and Pitfalls

- Pearls
  - There may be more than one wound to the heart (especially with gunshot wounds). Look for them. However, if the wound is posterior and not bleeding with the heart in its natural position, it will be more prudent to leave the injury alone until the patient can be transported to the operating room. Elevating the heart can cause both inflow and outflow obstruction, leading to dysrhythmia that may be difficult to recover from.
  - To avoid sutures pulling through in patients with thin, edematous, or friable myocardium, consider horizontal mattress rather than simple sutures. These may be buttressed with Teflon pledgets for added security.
- Pitfalls
  - The myocardium tears easily. When tying sutures, take care to not tighten them too forcefully.

Selected Reading

Asensio JA, Trunkey DD. Current therapy of trauma and surgical critical care. Philadelphia: Mosby/Elsevier; 2008.

Feliciano DV, Mattox KL, Moore EE. Trauma. 6th ed. New York: McGraw-Hill Medical; 2008.

Hirshberg A, Mattox KL. Top knife: the art & craft of trauma surgery. Castle Hill Barns: TFM; 2005.

Moore EE, Knudson MM, Clay CB, et al. Defining limits of resuscitative emergency department thoracotomy: a contemporary Western Trauma Association perspective. J Trauma. 2011;70:334–9.

Wall MJ, Mattox KL, Chen CD, et al. Acute management of complex cardiac injuries. J Trauma. 1997;42:905–12.

Synchronized Electrical Cardioversion

29

Jason Jones, Ann Tsung, and Marie-Carmelle Elie

Tachycardia is defined as >100 beats per minute

29.1 Indications

- Non-sinus-rhythm tachycardias with a pulse including:
  - Atrial fibrillation
  - Atrial flutter
  - Monomorphic ventricular tachycardia (VT)
  - Refractory or unstable supraventricular tachycardia (SVT)
- Unstable signs and symptoms including acute coronary syndrome, decreased level of consciousness, chest pain, dyspnea, pulmonary edema, and hypotension

29.2 Contraindications

- Absolute
  - Ventricular fibrillation and pulseless or polymorphic (irregular) VT require unsynchronized electrical cardioversion (defibrillation), not synchronized cardioversion.
  - Known atrial thrombus.
  - Sinus tachycardia.
- Relative
  - Digitalis toxicity-related tachycardia
  - Atrial fibrillation of greater than 48 h duration without anticoagulation
  - Multifocal atrial tachycardia
  - Electrolyte abnormalities
  - Left atrial diameter greater than 4.5 cm
  - Patients with low probability of maintaining sinus rhythm and readily return to atrial fibrillation
  - Patients with sick sinus syndrome or sinoatrial blockage who will require a pacemaker for maintenance of stable rhythm

29.3 Materials and Medications

- Airway management equipment (laryngoscopes, endotracheal tubes)
- Cardiac monitoring, pulse oximetry, end-tidal CO_2 monitoring
- Cardioverter/defibrillator
- Sedation and analgesic medications

29.4 Procedure

1. Obtain a 12-lead electrocardiogram (ECG) and intravenous (IV) access.
2. If possible, correct underlying electrolyte abnormalities that may cause or contribute to the patient's arrhythmia.
3. Discuss risks, benefits, and alternatives (including pharmacological cardioversion) with the patient and obtain consent.
4. Prepare airway equipment and Advanced Cardiac Life Support (ACLS) code drugs.
5. Consider IV sedation (e.g., propofol, midazolam).
6. Provide IV analgesia (e.g., fentanyl, morphine).
7. Place defibrillator adhesive pads (8- to 12-cm diameter in adults) or paddles on the patient. Pediatric-sized pads/paddles should be used if the patient is less than 10 kg.

J. Jones, MD • M.-C. Elie, MD, RDMS (✉)
Department of Emergency Medicine, University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: jasonjones@ufl.edu; elie@ufl.edu

A. Tsung, MD
Department of Emergency Medicine, University of Florida Health, Gainesville, FL, USA
e-mail: TSUNGANN@UFL.EDU

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_29

8. The first paddle/pad is placed to the right of the sternum at the second/third intercostal space. The second paddle/pad can be placed in one of two equally efficacious positions:
    (a) Anterolateral position—left fourth/fifth intercostal space in the midaxillary line (Fig. 29.1)
    (b) Anteroposterior position—between the spine and the edge of the left scapula (Fig. 29.2)
9. Turn the defibrillator/cardioverter into synchronized mode—marker above R-waves will be present (Fig. 29.3).
10. Select the energy level to be delivered based on the underlying rhythm
    (a) Regular VT (with pulses)—Adults: 100 J (monophasic or biphasic), 200 J for subsequent shocks
    (b) Atrial fibrillation—120–200 J (biphasic), 200 J (monophasic), 360 J for subsequent shocks
    (c) Atrial flutter and paroxysmal SVT—50–100 J (biphasic), 100 J for subsequent shocks
    (d) Pediatric dosage (regular and pulsed VT or SVT)—0.5–1 J/kg, up to 2 J/kg for subsequent shocks (Fig. 29.4)
11. Announce that you are going to deliver the shock on the count of three, and ensure that everyone is clear of the patient.
12. Deliver the shock by pressing button marked “SHOCK.”
    - If using paddles, apply firm pressure and keep paddles in place until shock is delivered.
13. Reassess the patient’s pulse and cardiac rhythm.
14. Repeat with escalating energy in a stepwise fashion if cardioversion is unsuccessful.



Fig. 29.1 Anterolateral pad placement



Fig. 29.2 Anteroposterior pad placement



Fig. 29.3 Synchronized cardioversion—mark on R wave



Fig. 29.4 Pediatric pad placement

29.5 Complications

- Superficial burns if there is inadequate gel.
- Induced arrhythmias (bradycardia in patients with previous inferior myocardial infarction, atrioventricular block, VT, ventricular fibrillation, asystole).
- Improperly synched cardioversion may rarely induce ventricular fibrillation.
  – Ectopy of the atria or ventricle in first 30 min after cardioversion
  – Atrial clot embolization in patients without adequate anticoagulation
- Apnea, hypoxia, hypercarbia, or hypotension may occur from sedation/analgesia.
- Medical professionals who incidentally touch the patient during shock delivery may be shocked or burned.
- Rarely, fire has occurred as a consequence of poor pad placement and a hyperoxygenated environment.

29.6 Pearls and Pitfalls

- Hirsute males should be shaved at the pad/paddle placement sites.
- Placing the cardioverter in “synchronized” mode avoids delivering a shock during the relative refractory segment, which could induce ventricular fibrillation.
- Cardioversion of pregnant patients is performed as in the general adult population.
- Keep pacemakers and implantable cardioverter-defibrillators at least 10 cm away from contact with paddles.
- If patient has implanted pacemaker, position pads so that they are not directly over the device.

Selected Reading

Gowda SA, Shah A, Steinberg JS. Cardioversion of atrial fibrillation. Progr Cardiovasc Dis. 2005;48:88–107.

Kleinman ME, Chameides L, Schexnayder SM, et al. Part 14: pediatric advanced life support. 2010 American Heart Association Guidelines for Cardiopulmonary Resuscitation and Emergency Cardiovascular Care. Circulation. 2010;122 Suppl 3:S876–908.

Link MS, Atkins DL, Passman RS, et al. Part 6: electrical therapies: automated external defibrillators, defibrillation, cardioversion, and pacing. 2010 American Heart Association Guidelines for Cardiopulmonary Resuscitation and Emergency Cardiovascular Care. Circulation. 2010;122 Suppl 3:S706–19.

Mayeaux EJ. The essentials guide to primary care procedures. Philadelphia: Lippincott Williams & Wilkins; 2012. p. 88–92.

Sirna SJ, Ferguson DW, Charbonnier F, et al. Factors affecting transthoracic impedance during electrical cardioversion. Am J Cardiol. 1988;62:1048–52.

Trohman RG, Parrillo JE. Direct current cardioversion: indications, techniques, and recent advances. Crit Care Med. 2000;28:170–3.

Unsynchronized Cardioversion (Defibrillation)

30

Matthew R. Tice, Zachary B. Kramer, and Marie-Carmelle Elie

Unsynchronized cardioversion or defibrillation is the delivery of a *high-energy* shock as soon as the button is pushed on defibrillator. This means it can be delivered anywhere in the cardiac cycle. By contrast, synchronized cardioversion (see Chap. 29) delivers a low-energy shock at the peak of the R wave in the cardiac (QRS) cycle.

30.1 Indications

- Ventricular fibrillation (VF)
- Pulseless ventricular tachycardia (VT)
- Cardiac arrest due to or resulting from VF

30.2 Contraindications

- Absolute
  - Conscious patient
  - Presence of a pulse
  - Pulseless electrical activity (PEA)
  - Asystole
  - Multifocal atrial tachycardia
  - Defibrillation without knowing the rhythm
  - A second defibrillation before 2 min (or five cycles) of CPR
  - Advanced Directive, Physician Order for Life-Sustaining Treatment (POLST) indicating no cardiopulmonary resuscitation (CPR) or do not resuscitate (DNR)
- Relative
  - Potential electrical catastrophe (explosive environment [i.e., operating rooms])
  - Dysrhythmias due to enhanced automaticity such as in digitalis toxicity and catecholamine-induced arrhythmia (because mechanism of tachycardia remains after the shock)
- Factors that are not contraindications
  - Pregnancy.
  - Chest trauma.
  - Automatic implantable cardiac defibrillators (AICDs).
  - The patient is on a wet or moist surface.
  - Piercings on the chest.

30.3 Materials and Medications

- Electrocardiogram (ECG) monitor/defibrillator.
- Self-adhesive defibrillation pads or defibrillation paddles (paddles may be more successful than self-adhesive pads, but they have more complications and pose more danger to operators).
- Conductive gel for defibrillation paddles (not ultra sound gel).
- ECG electrodes.
- Supplemental oxygen.
- Intubation equipment as needed.

M.R. Tice, MD • Z.B. Kramer, MD • M.-C. Elie, MD, RDMS (✉)
Department of Emergency Medicine,
University of Florida, Gainesville, FL, USA
e-mail: mtice@ufl.edu; kramer@ufl.edu; elie@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_30

30.4 Procedure

Defibrillation is an emergent maneuver and, when necessary, should be promptly performed in conjunction with or before administration of induction or sedative agents to facilitate intubation.

1. Assess the ABCs (airway, breathing, circulation).
    - Open the airway with a head tilt/chin lift (or jaw thrust in a suspected traumatic patient). If the patient is apneic, provide breaths with a bag-valve-mask (BVM) and observe chest rise.
    - Check for pulses. If absent, start CPR.
    - CPR should be initiated before any shock while getting all equipment ready for at least 2 min to provide adequate circulation to the brain and heart.
2. Wipe off the patient's chest if moist or wet.
3. Remove transdermal patches, jewelry, and piercings if possible.
4. Attach ECG electrodes to the patient.
    - The self-adhesive defibrillation pads or defibrillation paddles can be used as ECG electrodes to access the rhythm.
5. Paddles: With conductive gel applied to the metal surface, place one paddle on the patient's right chest, just below the clavicle, near the sternal border. The other should be on the left chest, midaxillary line above the fifth or sixth intercostal space (Fig. 30.1).
    - The long axis of the paddles should be perpendicular to the ribs to allow for better transduction of current through the chest.
    - Pads: Same placement as paddles except that pads can be placed in any orientation as long as they are in full contact with the chest.
    - If a lot of breast tissue is present, push the tissue to one side or lift it away and place the paddles or pads underneath.
    - An error in pad or paddle placement can distort the rhythm into looking like a rhythm that does not require defibrillation.
6. Place the ECG monitor/defibrillator into a mode to acquire a rhythm from the pads or paddles.
    - Steps 1–3 can be done simultaneously.
7. Stop CPR and assess the rhythm and pulse for no longer than 10 s.
8. If VF or pulseless VT is observed, then switch the defibrillator to charge mode.
9. Charge to 200 J.
    - Continue CPR while the defibrillator is being charged.
10. When the defibrillator indicates that it is charged, clearly order that everyone stop touching the patient and observe that there is no physical contact before defibrillating the patient.
    - If using the paddles, apply extra force to the chest through the paddles to deflate the lungs to allow for better defibrillation.
    - The operator should observe a muscle twitch during defibrillation.
11. Restart CPR for 2 min or five cycles.
    - Another operator may charge (but not fire) the defibrillator while CPR is being performed to expedite the time between pulse/rhythm check and the initiation of a shock.
12. After 2 min or five cycles of CPR, assess the rhythm and pulse and repeat steps 6–8 and give appropriate Advanced Cardiac Life Support (ACLS) medications.
13. If successful return of spontaneous circulation (ROSC) occurs, initiate the hypothermia protocol per hospital guidelines.

Fig. 30.1 Proper placement of defibrillation paddles



30.5 Complications

- Skin burns (most common and likely due to improper technique).
- Injury to cardiac tissue (myocardial necrosis secondary to burn).
  - ST segment elevation that lasts longer than 2 min usually indicates myocardial injury unrelated to the shock.
- Abnormal heart rhythms (usually benign like atrial, ventricular, and junctional premature beats).

30.6 Pearls and Pitfalls

- Pearls
  - Post-defibrillation cardiac dysrhythmias are more common following prolonged VF and higher-energy-level countershocks. Early defibrillation at the recommended energy levels minimizes this complication. Follow ACLS protocols to manage the resulting dysrhythmias.
  - The presence of liquid (body fluids, medications, or intravenous fluids) may cause electrical arcing thermal burns to the skin and soft tissue and produce ineffective defibrillation by allowing the current to pass across the trunk rather than transthoracically. To minimize this potential complication, ensure that any body fluids or liquids are wiped away from the skin before defibrillation attempts.
- Pitfalls
  - Myocardial and epicardial injury (not direct thermal injury) may result from the electrical current applied in defibrillation. Use the minimal recommended energy levels to minimize injury.
  - Electrical injuries to health-care providers can result if participants remain in contact with the patient during delivery of a countershock because they can serve as a ground for the current discharged.
    - This can be minimized by wearing gloves and using biphasic machines and electrode pads.
  - Fires that can result from sparks in the presence of nitroglycerin patches or ointment, flammable gases, or an oxygen-rich environment can also be a source of injury to the patient or health-care providers. Ensure "all clear" from the patient before delivery of shock to avoid these complications.

Selected Reading

Advance cardiovascular life support: provider manual. Dallas: American Heart Association; 2011.

Deakin CD, Sado DM, Petley GW, Clewlow F. Is the orientation of the apical defibrillation paddle of importance during manual external defibrillation? Resuscitation. 2003;56:15–8.

Pagan-Carlo LA, Spencer KT, Robertson CE, Dengler A, Birkitt C, Kerber RE. Transthoracic defibrillation: importance of avoiding electrode placement directly on the female breast. J Am Coll Cardiol. 1996;27:449–52.

Walker C, Callies F, Langenfeld H. Adverse effects of direct current cardioversion on cardiac pacemakers and electrodes: is external cardioversion contraindicated in patients with permanent pacing systems? Eur Soc Cardiol. 2004;6:165–8.

Transcutaneous Pacing

31

Nour Rifai and Christian Coletti

31.1 Indications

- Hemodynamically unstable (i.e., hypotension, pulmonary edema, chest pain, shortness of breath, or evidence of decreased cerebral perfusion) bradyarrhythmias refractory to medical therapies
- As a bridge to a transvenous or permanent pacemaker
- As an overdrive pacer in tachyarrhythmias
- Controversially, within the first 10 min of a witnessed asystolic cardiac arrest
- In children only with bradycardia associated with a known congenital cardiac defect or after cardiac surgery

31.2 Contraindications

- Absolute
  - None
- Relative
  - Bradyarrhythmia associated with hypothermia (ventricles are more prone to defibrillation-resistant fibrillation)
  - Prolonged cardiac arrest (>20 min)
  - Bradyarrhythmia in children (usually secondary to hypoxia or a respiratory issue)
  - Patient is unable to tolerate the procedure despite sedation and analgesia

31.3 Materials and Medications

- Pacemaker device (modern units offer combined pacer and defibrillator functions) (Fig. 31.1)
- One set of standard electrocardiogram (ECG) electrodes
- One set of pacer pads
- Code cart and airway equipment (prophylactically)
- Sedation and analgesia (typically a short-acting benzodiazepine and an opioid)
  - Midazolam: 0.2–0.10 mg/kg intravenous (IV) push and may repeat with 25 % of initial dose after 3–5 min. Do not exceed 2.5 mg/dose or a cumulative dose of 5 mg.
  - Fentanyl: 1–2 mcg/kg IV slow push over 1–2 min, may repeat dose in 30 min. (Fentanyl is the opioid of choice because it is less likely to exacerbate any hypotension.)



Fig. 31.1 Pacemaker device

N. Rifai, MBCHB • C. Coletti, MD (✉)
Department of Emergency Medicine,
Christiana Care Health System,
Newark, DE, USA
e-mail: nourifai@gmail.com; chris.coletti@gmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_31

31.4 Procedure

1. Time permitting, clean and dry the skin, and shave any excess hair off the chest.
2. Administer any appropriate sedation and analgesia.
3. Attach the ECG electrodes to both the input port of the pacemaker unit and the patient. On the patient, the white lead is placed just above the right clavicle, the black lead is just above the left clavicle, and the red lead is around the left midaxillary line.
4. Attach the pacer pads either in the anteroposterior or anterolateral positions as pictured (avoid placement over an implanted pacemaker or defibrillator; Fig. 31.2).
5. Turn the machine on and switch it to synchronous (or on-demand) mode.
    - Asynchronous (or fixed) mode fires impulses with no regard to the intrinsic cardiac cycle, increasing the likelihood of an R on T phenomenon, which could result in ventricular tachycardia or fibrillation.
    - Synchronous (or on-demand) mode will not fire an electrical impulse when a QRS complex is sensed; this is the preferred mode for transcutaneous pacing.
6. Set the desired heart rate: typically 60–80 beats/min to achieve adequate perfusion.
7. Select a lead on the pacemaker unit and then press Start.
8. Slowly increase the output current until electrical capture is denoted by a visible pacemaker spike, which will precede every QRS complex on the ECG monitor (Fig. 31.3).
    - Electrical capture is usually achieved between 50 and 100 mA.
    - If a patient is unconscious or truly deteriorating quickly or in cardiac arrest, it may be prudent to set the initial currents at maximum to ensure rapid capture and then decrease the current to just above that at which electrical capture was achieved.
9. After electrical capture is appreciated on the monitor, assess for mechanical capture by palpation of a pulse at a rate that corresponds to that which the machine is set at. An improved blood pressure or resolution of chest pain, shortness of breath, or altered mental status also suggests that the heart rate has improved and perfusion has been restored.
10. When pacing in overdrive for tachyarrhythmias, the pacer rate is set 20–60 beats/min faster than the detected tachycardic rate.
    - Bear in mind that rhythm acceleration or the induction of ventricular fibrillation is a possibility with pacing, hence the recommendation of having a code cart and airway equipment in the room at all times.



Fig. 31.2 Pacer pads attached in the anterolateral (**a**) or anteroposterior positions (**b**)


Lead I
Heart Rate 41

Bradycardia prepacing attempt


Lead I
Heart Rate 43
35 mA

Pacing attempted, note pacing stimulus indicator (arrow) which is below threshold, no capture


Lead I
Heart Rate 71
60 mA

Pacing above threshold (60mA), with capture (QRS complex broad and ventricular, T wave opposite QRS)

Fig. 31.3 A visible pacemaker spike will precede every QRS complex on the ECG monitor

31.5 Pearls and Pitfalls

- Pearls
  - Pacer pads can be prophylactically placed on bradycardic but stable patients in preparation for potential decompensation.
  - It may be prudent to discuss with a stable but bradycardic patient the option of trying the pacemaker not only to ensure that the machine and pads are working but also to gauge an idea of the output current that will be needed to electrically capture for quicker, more efficient, and potentially lifesaving pacing that may prove necessary.
  - When palpating for mechanical capture, the femoral pulse may be easier because carotid palpation may prove difficult with muscular contractions induced by the pacer impulses.
  - If impulses are not capturing, try slightly readjusting the pacer pads, making sure the leads are still on, the settings were not changed, the machine's battery did not die, or that the machine is plugged in.
  - If electrical capture is achieved but mechanical is not, increase the rate until adequate pulses are palpated.
  - Be careful to not miss an underlying ventricular fibrillation if the monitor is not blanked or dampened by an ECG screen.
  - Cardiopulmonary resuscitation (CPR) can be continued even while transcutaneous pacing is taking place because the pacer pads are insulated and the power delivered in each impulse is minimal, making the risk of injury to health-care workers very low.
- Pitfalls
  - Certain factors including a large body habitus, the presence of large pericardial effusions, scarring secondary to intrathoracic surgeries, or large amounts of intrathoracic air associated with obstructive pulmonary diseases may not only increase the threshold for capture but also may even cause a failure to capture, in which case transvenous pacing should immediately be considered.
  - Be aware that long-term pacing and pacing in children increases the likelihood for cutaneous and soft tissue damage.

Selected Reading

Bonow JS, Mann DL, Zipes DF, editors. Braunwald's heart disease: a textbook of cardiovascular medicine. 9th ed. Philadelphia: Saunders Elsevier; 2008.

Pfenninger JL, Fowler GC, editors. Pfenninger and Fowler's procedures for primary care. Philadelphia: Saunders Elsevier; 2010.

Roberts JR, Hedges JR, editors. Clinical procedures in emergency medicine. 5th ed. Philadelphia: Saunders Elsevier; 2010.

Tintinalli JE, Stapczynski JS, Cline DM, Ma OJ, Cydulka RK, Meckler GD, editors. Tintinalli's emergency medicine: a comprehensive study guide. 7th ed. New York: McGraw-Hill Medical; 2011.

Transvenous Cardiac Pacing

32

Katrina John, Jeffrey Kile, and Amish Aghera

32.1 Indications

Hemodynamic compromise in the presence of:

- Sinus node dysfunction
- Second- and third-degree heart block
- Atrial fibrillation with slow ventricular response
- New left bundle branch block (LBBB)
- Right bundle branch block (RBBB)
- Bifascicular block
- Alternating bundle branch block (BBB)
- Implanted pacemaker malfunction

32.2 Contraindications

- Absolute
  - Prosthetic tricuspid valve
- Relative
  - Bradycardia in the presence of severe hypothermia

K. John, MBBS • J. Kile, MBBS, PhD, MPH (✉)
Department of Emergency Medicine, Eisenhower Medical Center,
Rancho Mirage, CA, USA
e-mail: trenjohn@me.com; jeffrey.kile@gmail.com

A. Aghera, MD
Department of Emergency Medicine, Maimonides Medical Center,
New York, NY, USA
e-mail: aaghera@maimonidesmed.org

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_32

32.3 Materials and Medications (Fig. 32.1)

- Sterile gloves
- Sterile gown and drapes
- Face mask and surgical cap
- Two 10-mL syringes
- One 3-mL syringe
- Local anesthetic (1 or 2 % lidocaine without epinephrine)
- 22-gauge needle
- Povidone-iodine or chlorhexidine/isopropyl alcohol
- Several 4 × 4-in. gauze sponges
- Sterile dressing pack
- 4-0 nylon or silk sutures
- Scalpel (#11 blade)
- Needle holder
- Scissors
- Introducer needle
- Guidewire
- Dilator
- Introducer sheath
- Collapsed sterile extension sheath
- Balloon-tipped pacing catheter
- Pacing generator with working battery
- Insulated cable with alligator clamps or other suitable connectors
- Electrocardiogram (ECG)/cardiac monitor



Fig. 32.1 Materials and medications

32.4 Procedure

1. Select appropriate catheterization site.
   - Four sites provide superior access to right atrium: brachial, femoral, internal jugular, and subclavian veins. The right internal jugular and left subclavian veins, respectively, are the most direct routes and, thus, the most commonly used in the emergency department setting.
2. If clinical situation permits, explain the procedure fully to the patient and obtain consent.
3. Sterilize the skin and apply sterile drapes.
4. Anesthetize the intended insertion site with lidocaine.
5. Prepare the pacing wire by inflating and deflating the balloon with 1–1.5 mL of air using a 3-mL syringe, and confirm that locking lever functions correctly to maintain balloon inflation (Fig. 32.2).
6. Using ultrasound guidance by means of a probe covered in a sterile sheath, insert the introducer needle into the vein while applying negative pressure to the attached 10-mL syringe (as with standard central line placement) (Fig. 32.3).
7. When flashback of blood is visualized in the syringe, remove the syringe, stabilizing the introducer needle firmly in place.
8. Pass the guidewire through the needle to a depth of 10–15 cm.
9. Holding the guidewire securely in place, remove the introducing needle.
10. Using a scalpel, make a small incision (approximately the width of the catheter to be used) through the dermis at the insertion site of the guidewire.
    - Avoid severing the guidewire by facing the sharp edge of the scalpel *away* from the guidewire.
11. Pass a dilator over the guidewire to make a tract in the skin and then remove the dilator.
12. Pass the introducer catheter over the guidewire until the hub is in contact with the skin and then remove the guidewire (Fig. 32.4).
13. Attach the collapsible sterile sheath to the hub of the introducer catheter.
14. Attach the positive and negative connectors of the pacing wire to their respective terminals on the cable(s) connected to the generator.
15. Set generator rate at 80 beats/min, output to 5 mA, and sensitivity to 3 mV.
16. Insert the free end of the pacing wire into introducer catheter with the balloon deflated and slowly advance the wire.
17. When the tip of the wire is within the superior vena cava, inflate the balloon, lock the valve to ensure that the balloon remains inflated, and continue to advance the pacing wire.
18. Closely watch the cardiac monitor for signs of capture (i.e., a wide QRS preceded by a pacing spike).
    - Markings on the pacing wire indicate its depth of insertion. At 20 cm, the wire should be in the right ventricle. If there is no capture observed by 25 cm, then the wire should be slowly withdrawn and advanced again.
19. Once capture is achieved, deflate the balloon.
20. Advance the wire a further 1–2 cm.
21. Coil the wire that remains outside the extended sterile sheath and suture it loosely but securely to the skin.
22. Suture the introducer hub to the skin.
23. Reduce generator output to zero and then increase it slowly to determine the minimum pacing threshold (i.e., the minimum voltage at which capture is achieved) and then set the output to twice this value.
24. Set the generator rate.
25. Stabilize the generator near the catheterization site.
    - For example, the generator can be attached to an intravenous (IV) fluid stand to the right of the patient's head if the pacing wire has been placed via the patient's right internal jugular vein.
26. Obtain a chest x-ray to confirm pacing wire position and absence of potential complications (e.g., pneumothorax) (Fig. 32.5).
27. Obtain a 12-lead ECG (Fig. 32.6).



Fig. 32.2 Pacing wire balloon locking lever



Fig. 32.3 Insertion of introducer needle into internal jugular vein with ultrasound guidance



Fig. 32.4 Placement of introducer catheter over guidewire


Portable
R
FSJ
L
5 cm

Fig. 32.5 X-ray displaying correct position of pacing wire in the right ventricle


HR 60 [VPACE] . Ventricular-paced rhythm
PR 212
QRSD 181
QT 482
QTc 482
-- AXIS --
P 0
QRS -37
T 92
- ABNORMAL ECG -
Previous ECG:13-Feb-2011 18:45:25 - Abnormal Confirmed
AD
Order #: SCM1-001149KPM
Enc ID: 501301348
Reason: 427.89
Standard 12
Requested By:
Confirmed for:
16-Feb-2011 15:50:22
I
aVR
V1
V4
II
aVL
V2
V5
III
aVF
V3
V6
II
Device: 1249708
Speed: 25 mm/sec
Limb: 10 mm/mV
Chest: 10 mm/mV
F 60~ 0.5-100 Hz W
PH100B bCL P?

Fig. 32.6 Cardiac monitor displaying wide-complex QRS and pacing spike

32.5 Complications

- Arterial puncture
- Venous thrombosis
- Thrombophlebitis
- Pulmonary embolus
- Pneumothorax
- Fracture of guidewire with embolization
- Hemothorax
- Thoracic duct laceration
- Indwelling line infection (local or systemic)
- Dysrhythmias/premature ventricular contractions (PVCs)
- Insertion of pacing wire into coronary sinus/pulmonary artery
- Left (rather than right) ventricular pacing through atrial septal defect/ventricular septal defect (ASD/VSD)
- Septal perforation
- Ventricular perforation
- Entrapment/twisting of preexisting permanent pacing wires by the temporary pacing wire
- Balloon rupture
- Chordae tendineae rupture
- Pacing wire fractures
- Loss of capture owing to wire displacement or fracture
- Generator failure

32.6 Pearls and Pitfalls

- Confirm all necessary equipment is present and functional before beginning the procedure. If a dedicated transvenous pacing set is unavailable, individual components required (e.g., pacing catheter, connector cables, introducer catheter, guidewire) may need to be "cannibalized" from several different procedure kits in an emergency department.
- Become familiar with the locking valve for the pacing wire balloon before beginning the procedure. This small part is essential for inflating and deflating the balloon but is frequently difficult to adjust owing to stiffness (and all the more so if covered in blood).
- The ideal position for the pacing wire tip is against the diaphragmatic aspect of the right ventricle between its midpoint and its apex. This position is confirmed by development of an LBBB pattern with left axis deviation on the cardiac monitor. If difficulty is encountered achieving this position, the tip of the pacing wire can be moved to the right ventricular outflow tract, where the wire is less stable, but adequate pacing can still be achieved. In this latter position, the threshold will need to be kept relatively high and the monitor should display an LBBB pattern with an inferior axis.
- The use of balloon-tipped catheters enables the catheter tip to be directed with blood flow and its position (and successful capture) to be confirmed with a cardiac monitor. Nonballoon-tipped catheters, however, have typically required insertion with guidance of either constant ECG monitoring or fluoroscopy.

Selected Reading

Aguilera PA, Durham BA, Riley DA. Emergency transvenous cardiac pacing placement using ultrasound guidance. Ann Emerg Med. 2000;36(3):224–7.

Birkhahn RH, Gaeta TJ, Tloczkowski J, Mundy T, Sharma M, Bove J, Briggs WM. Emergency medicine-trained physicians are proficient in the insertion of transvenous pacemakers. Ann Emerg Med. 2004;43(4):469–74.

Dalsey WC, Syverud SA, Hedges JR. Emergency department use of transcutaneous pacing for cardiac arrests. Crit Care Med. 1985;13(5):399–401.

Harrigan RA, Chan TC, Moonblatt S, Vilke GM, Ufberg JW. Temporary transvenous pacemaker placement in the Emergency Department. J Emerg Med. 2007;32(1):105–11.

Silver MD, Goldschlager N. Temporary transvenous cardiac pacing in the critical care setting. Chest. 1988;93(3):607–13.

Pericardiocentesis (Optional: Ultrasound Guidance)

33

Katrina Skoog Nguyen, L. Connor Nickels,
and Rohit Pravin Patel

33.1 Indications

- Treatment of hemodynamic compromise from cardiac tamponade
- To diagnose the cause or presence of a pericardial effusion

33.2 Contraindications

- Absolute
  - Aortic dissection
  - Need for immediate surgery for trauma patients
- Relative
  - Coagulopathy
  - Anticoagulant therapy
  - Thrombocytopenia

33.3 Materials and Medications

- Antiseptic (e.g., Chloraprep)
- 1 % lidocaine
- 25-gauge needle, 5/8-in. long
- 18-gauge catheter-type needle, 1½-nch long
- Syringes (10, 20, and 60 mL)
- Ultrasound (US) machine and cardiac/phased array probe
- Sterile US probe cover
- Cardiac monitor

33.4 Procedure

1. Identify the point of maximal effusion with US. Evaluate for hypoechoic or anechoic (dark) effusion around the heart, between the pericardial sac and the myocardium. A patient with hemodynamic compromise from a pericardial effusion or tamponade will have right ventricular collapse, septal bulging, and dilation of the inferior vena cava. Diastolic collapse of the right ventricular free wall can be absent in elevated right ventricular pressure and right ventricular hypertrophy or in right ventricular infarction.
2. Measure the distance from the skin surface to the effusion border to assess the expected needle depth.
3. Choose the needle trajectory based on the point of maximal effusion in the path with the fewest intervening structures. The most commonly used approaches are left parasternal, apical, and subxiphoid. For complex loculated posterior pericardial effusions, optional techniques such as transatrial and transbronchial may be performed by specialists. These types of loculated effusions can occur in autoimmune diseases, infective pericarditis, after cardiac surgery, and after radiotherapy.
4. Sterile preparation: prepare the skin of the entire lower xiphoid and epigastric area with antiseptic. Prepare the US transducer with a sterile sleeve.
5. Local anesthetic: if the patient is awake, anesthetize the skin and planned route of the needle.
6. Pericardial needle insertion: depends on approach used.

K.S. Nguyen, DO
Northwest Community Hospital, Arlington Heights, IL, USA
e-mail: katrinaskoog@hotmail.com;

L.C. Nickels, MD, RDMS (✉) • R.P. Patel, MD
Department of Emergency Medicine, University of Florida
Health Shands Hospital, Gainesville, FL, USA
e-mail: cnickels@ufl.edu; rohitpatel@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_33

33.4.1 Subxiphoid Approach (Fig. 33.1)

- The US transducer is placed just inferior to the xiphoid process and left costal margin.
- Insert the needle between the xiphoid process and the left costal margin at a 30–45° angle to the skin.
- Aim for the left shoulder.


a
b
Path to fluid
Crd
P21
MI
0.8
TIS
0.7
21

Fig. 33.1 Subcostal approach (**a**) and corresponding ultrasound image (**b**). *Red line* through liver to obtain fluid (no fluid present on ultrasound image)

33.4.2 Apical Approach (Fig. 33.2)

- The US transducer is placed at the patient's point of maximal impulse and aimed at the patient's right shoulder for a four-chamber view of the heart.
- Insert the needle in the fifth intercostal space 1 cm lateral to and below the apical beat, within the area of cardiac dullness.
- Aim for the right shoulder.
- A Mayo Clinic review showed, in 80 % of total effusions, that the distance to the effusion was least and the size was maximal in the apical approach [1].


a
b
THI
2012Oct10 08:58
Crd
P21
MI
0.9
TIS
0.7
Path to fluid
19
Gen
0
Sector
MB Off
On
Page 1/3

Fig. 33.2 Apical approach (**a**) and corresponding ultrasound image (**b**). *Red line* with minimal distance to fluid if present (no fluid present on ultrasound image)

33.4.3 Parasternal Long-Axis Approach

- The US transducer is placed obliquely on the left sternal border between the fourth and fifth ribs with the transducer indicator aimed at the right shoulder.
- Insert the needle perpendicular to the skin in the fifth intercostal space medial to the border of cardiac dullness.
  - Visualize and feel a giving way as the needle penetrates the pericardium. Removal of fluid confirms successful entry. Remove fluid with the goal of restoring hemodynamic stability. Aspiration of fluid should result in improvement in blood pressure and cardiac output.
  - Remove the catheter and apply a dressing. Optional: Place a pigtail catheter using the Seldinger technique for continued drainage.

33.5 Complications

- Blind techniques are associated with 20 % morbidity and 6 % mortality. The complication rate with US-guided approaches is less than 5 % [2].
- Any vital structure within reach of the pericardial needle has the potential for injury: pneumothorax; hemothorax; coronary vessel laceration; hemopericardium; heart chamber lacerations; intercostal vessel injury; dysrhythmias; ventricular tachycardia; puncture of the liver, diaphragm, or gastrointestinal tract; bacteremia; purulent pericarditis; air embolisms; and pleuropericardial fistulas.

33.6 Pearls and Pitfalls

- Pearls
  - A scoring index is available that can be obtained at initial presentation in patients without hemodynamic compromise that identifies those who require pericardial effusion drainage later in the course of treatment. The scoring index uses echocardiographic findings, etiological information, and the size of the effusion at end-diastole [3].
  - Take care to avoid the left internal mammary artery, which travels in a cephalad-to-caudad direction 3–5 cm lateral to the left sternal border [4].
- Pitfalls
  - Tamponade should always be considered in the differential diagnosis of shock or cardiac arrest owing to pulseless electrical activity (PEA). Complications of acute coronary syndrome, aortic dissection, and decompensations in chronic advanced constriction may also need treatment [5].
  - When cardiac compensation mechanisms are exhausted, small increases in pericardial volume can lead to an increase in ventricular diastolic pressure, systemic and pulmonary congestion, and decrease preload and cardiac output.
  - Use US-guidance rather than a blind or an electrocardiogram (ECG)-alone-guided approach for pericardiocentesis to significantly decrease the risk of injury to vital structures [4].
  - Do not delay patient transport to the operating room to perform pericardiocentesis on a traumatically induced effusion unless the patient is hemodynamically unstable and on the verge of cardiac arrest.

References

1. Tsang TS, Enriquez-Serano M, Freeman WK, Barnes ME, Sinak LJ, Gersh BJ, et al. Consecutive 1127 therapeutic echocardiography guided pericardiocentesis: clinical profile, practice patterns, and outcomes spanning 21 years. Mayo Clin Proc. 2002;77:429–36.
2. Guo K, Ding ZP, Tan J. Trans-pleural pericardiocentesis: revisiting an old technique. Catheter Cardiovasc Interv. 2011;78:815–8.
3. Halpern DG, Argulian E, Briasoulis A, Chaudhry F, Aziz EF, Herzog E. A novel pericardial effusion scoring index to guide decision for drainage. Crit Pathw Cardiol. 2012;11:85–9.
4. Seferović PM, Ristić AD, Imazio M, et al. Management strategies in pericardial emergencies. Herz. 2006;31:891–901.
5. Sagristà-Sauleda J, Mercé AS, Soler-Soler J. Diagnosis and management of pericardial effusion. World J Cardiol. 2011;3:135–43.

Ultrasound Evaluation of Pulmonary Embolism and Heart Strain

34

Giuliano De Portu, L. Connor Nickels,
and Marie-Carmelle Elie

34.1 Indications

- Undifferentiated respiratory distress
- Unexplained hypotension
- Evaluation for cardiac tamponade, pericardial effusion

34.2 Contraindications

- Relative
  - Morbidly obese patients
  - Patients with chest wall deformities
  - Patient with subcutaneous emphysema, pneumopericardium
  - Combative or altered patients

34.3 Materials and Medications

- Portable ultrasound machine with appropriate probes (phased array)
- Ultrasonic gel for the probe
- Drapes for the patient (if the condition allows)

34.4 Procedure

1. Begin with the parasternal long-axis view. If possible have the patient turn to the left decubitus side (that helps "move" the heart closer the chest wall).
2. Find the phased array probe, select the "cardiac examination" on the machine, and make sure the orientation marker is pointed toward the right shoulder of the patient.
3. Place the probe along the left side of the sternum over the fourth to sixth intercostal space. This should produce the image shown in Fig. 34.1.
4. Measure the diameter of the ventricle during the end of diastole (normal values, 21 mm ± 1 mm; any measurement >25–30 mm is abnormal).
5. Using the aorta as a landmark, evaluate the structures starting with the pericardium (bright white line around the heart), making sure there is no fluid around it. (Fluid above the aorta indicates a pericardial effusion. Fluid below the aorta indicates a pleural effusion.) If a hypoechoic or anechoic stripe appears in the anterior side of the heart, it is most likely a fat pad. Fluid seen "all around" categorizes it as an effusion.
6. While keeping the probe in the same place, rotate the probe marker 90° clockwise toward the left shoulder to obtain the parasternal short-axis view (Fig. 34.2).



Fig. 34.1 Parasternal long-axis view (PSLA). *1* right ventricle, *2* left ventricle, *3* left atrium, *4* aortic outflow track; *circle* descending aorta (right atrium is not visualized in the PSLA)

G. De Portu, MD • L.C. Nickels, MD, RDMS
M.-C. Elie, MD, RDMS (✉)
Department of Emergency Medicine, University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: gdeportu@ufl.edu; cnickels@ufl.edu; elie@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_34



Fig. 34.2 Parasternal short-axis view (PSSA). *1* right ventricle, *2* left ventricle



Fig. 34.3 Four-chamber view (4C). *1* left ventricle, *2* left atrium, *3* right ventricle, *4* right atrium

7. The parasternal short-axis view will give information on the contractility of the heart. The right ventricle should be anterior and to the left and the left ventricle to the right. The normal position of the septum bows slightly toward the right ventricle.
8. Obtain a four-chamber view. Place the orientation marker to the patient's left.
9. Palpate for the point of maximum impulse (PMI) and place the transducer. All four chambers should appear in one view (Fig. 34.3).
10. Compare the sizes of the ventricles and note any difference. Notice also the interventricular septum. The normal right-to-left ventricular ratio is less than 0.5. (In an unstable patient, this is probably the most useful because both ventricles can be quickly visualized and the ratio compared.)
11. A subxiphoid approach is also possible. Make sure the orientation marker is toward the right side of the patient (Fig. 34.4).



Fig. 34.4 Subcostal/subxiphoid view. *RV* right ventricle, *RA* right atrium, *LV* left ventricle, *LA* left atrium



Fig. 34.5 Inferior vena cava. *L* liver, *2* inferior vena cava, *H* heart

12. Use the liver for orientation. The right side of the heart will be nearest to the liver (think that the liver is on the right of the body); again note for any differences in the size ratio.
13. Next take a look at the inferior vena cava (IVC) by placing the curved array transducer just inferior to the xiphoid in a longitudinal fashion. (Switch from the subxiphoid view to the IVC by rotating the probe counterclockwise until the IVC is seen.) Evaluate the IVC. During normal physiological inspiration, the drop in intrathoracic pressure "pulls" blood into the heart, thus decreasing the relative IVC size. If something is preventing venous return, such as a massive PE, collapse will not be as evident and the suspicion for PE increases (fluid overload and increased central venous pressure [CVP] will also account for this finding). Normal IVC diameter is 1.2–2.3 cm, and total collapse and greater than 50 % collapse are normally visualized. An increase in IVC size and less than 50 % or no change has been correlated with increased right atrial pressures (11 to >20 cm Hg) (Fig. 34.5).

34.5 Findings

A right heart that is “strained” or pumping against a higher resistance owing to a PE will show some or all of these changes:

1. Right ventricular dilation (Fig. 34.6).
2. Right ventricular hypokinesis (especially of the middle segment), McConnell’s sign but normal motion of the apex.
3. Tricuspid regurgitation.
4. Abnormal septal motion: deviated toward the left ventricle (normally it relaxes during diastole toward the right ventricle); as pressure increases, the right ventricle will not empty properly and septal flattening can be seen.
5. Dilated IVC with little or complete loss of changes in diameter with respiration (variability); the IVC collapses less than 50 % during inspiration.



Fig. 34.6 Four-chamber view that shows right ventricular dilatation due to pulmonary embolism. Normally, the LV is greater than the RV during diastole, but in the case of increased pressure, the RV will be enlarged. *RV* right ventricle, *LV* left ventricle

34.6 Complications

- Ultrasound per se has been shown to cause no direct complications with proper use unless it is interfering with advanced airway or life-saving procedures.

34.7 Pearls and Pitfalls

- Pearls
  - Proper interpretation of the images is necessary because some normal anatomy could be confused with a positive finding. Make sure to properly identify the structures because a common mistake is to identify the aorta thinking it is the IVC.
  - Depth: increase to be sure to visualize all structures.
- Pitfalls
  - Ultrasound is user dependent, and the acquisition of images will vary with each user, creating the possibility of false-negatives if images not properly acquired.
  - Reversal of the orientation owing to transducer misplacement could “reverse” the anatomy and allow mistakenly identification of structures.
  - An enlarged right ventricular wall (>5 mm) is considered hypertrophied and would indicate a more chronic etiology of a right ventricular dilation.
  - Gain problems: adjust so the heart chambers are anechoic and the walls are echogenic.

Selected Reading

Kline JA. Thromboembolism In: Tintinalli J, Stapczynski J, Ma OJ, Cline D, Cydulka R, Meckler G, editors. Tintinalli’s emergency medicine. 7th ed. New York: McGraw Hill; 2012.

McConnell MV, Solomon SD, Rayan ME, Come PC, Goldhaber SZ, Lee RT. Regional right ventricular dysfunction detected by echocardiography in acute pulmonary embolism. Am J Cardiol. 1996;78:469–73.

Reardon RF, Joing SA. Cardiac. In: Ma OJ, Mateer J, Blaivas M, editors. Emergency ultrasound. 2nd ed. New York: McGraw Hill Professional; 2007. p. 109–44.

Vanden Hoek TL, Morrison LJ, Shuster M, et al. Part 12: cardiac arrest in special situations: 2010 American Heart Association Guidelines for Cardiopulmonary Resuscitation and Emergency Cardiovascular Care. Circulation. 2010;122(18 Suppl 3):S829–61.

Pacemaker Evaluation in the Emergency Department

35

Joseph D. Romano and Christian Coletti

35.1 Pacemaker Function

There are approximately 500,000 implanted cardiac pacemakers in the USA and another 100,000 are implanted each year [1]. In the emergency department, a physician may be faced with a pacemaker that is not functioning appropriately. To understand the ways in which a pacemaker can malfunction or lead to medical complications, first it is important to understand how pacemakers work when they do so appropriately.

A common pacemaker system is composed of a pulse generator and insulated wire leads that originate in the pulse generator and end within the myocardium. The pulse generator is implanted in the pectoral region. It contains circuitry and the battery and creates the electrical impulses that depolarize the myocardium. The leads leave the pulse generator and are directed to the heart by following the venous system. Leads may terminate in the right atrium, the interventricular septum of the right ventricle, or biventricular pacing; a third lead navigates the coronary sinus to the left ventricular wall (Figs. 35.1 and 35.2).

Early pacemakers produced impulses only at a set rate. Today, however, virtually all pacemakers have sensing leads that detect intrinsic activity and react with electrical impulses when the intrinsic intervals fall outside of a set time threshold. Some pacemakers are programmed to allow for rate changes based on physical activity. To simplify the classification of different pacemaker types, the North American Society of Pacing and Electrophysiology and British Pacing and Electrophysiology Group (NASPE/BPEG) developed a five-letter code to describe each pacemaker (Table 35.1) [2].

J.D. Romano, MD (✉) • C. Coletti, MD
Departments of Emergency Medicine and Internal Medicine,
Christiana Care Health System,
Newark, DE, USA
e-mail: jromano@christianacare.org; chris.coletti@gmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_35


Right atrial lead
Coronary sinus lead
Right ventricular lead

Fig. 35.1 Common pacemaker lead insertion sites



Fig. 35.2 Common generator location and path of pacemaker leads

Table 35.1 NASPE/BPEG five-letter pacemaker code

Paced chamber	Sensed chamber	Response to sensing	Rate modulation	Multisite pacing
A = atrium	A = atrium	T = triggered	R = rate modulation	A = atrium
V = ventricle	V = ventricle	I = inhibited	O = none	V = ventricle
D = dual	D = dual	D = dual		D = dual
O = none	O = none	O = none		O = none

Reproduced with permission from Bernstein et al. [2]

35.2 Common Pacemaker Codes [3]

- VVI: ventricular paced and sensed, inhibited by normal intrinsic pacing; used for patients with a need for pacing if bradycardia occurs
- VVIR: ventricular paced and sensed, inhibited by normal intrinsic pacing; adaptive to changes in intrinsic rate for physically active patients
- DDD: dual-chamber paced and sensed, inhibited by normal intrinsic atrial and ventricular electrical activity; used in third-degree atrioventricular (AV) block to allow for more physiological conduction
- DDDR: dual-chamber paced and sensed, inhibited by normal intrinsic atrial and ventricular electrical activity; adaptive to changes in intrinsic rate; used primarily in sinoatrial (SA) node dysfunction to closely mimic normal, adaptable heart conduction

35.3 Pacemaker Malfunction

Malfunctioning pacemakers can have complicated programming that is best altered after thorough "interrogation" by a trained electrophysiologist. This type of evaluation is beyond the scope of this chapter and, in many clinical settings, subspecialty support is not readily available. In the emergency department, it is vital to stabilize the patient and identify common pacemaker system issues. Pacemaker system malfunctions can be identified as a failure to sense, failure to pace, failure to capture, or pacing at an inappropriate rate [4]. Another common abnormality associated with pacing is the "pacemaker syndrome" [3].

- Failure to sense:
  - Oversensing: The sensor interprets external stimuli as a normal ventricular rate leading to inappropriate inhibition. This may be due to lead fracture, fibrosis of the lead tip, or lead dislodgment. Cross talk is present when the atrial stimulus is sensed on the ventricular lead causing inappropriate inhibition. Oversensing is rarely due to failure of the generator.
  - Undersensing: Present when there is constant pacing despite cardiac activity that has not exceeded threshold. This can be due to low-amplitude intrinsic cardiac activity, lead dislodgment, battery depletion, or metabolic abnormalities.
- Failure to pace:
  - Lack of pacing despite appropriate sensing of the intrinsic electrical activity or activity below the threshold rate.
  - Typically caused by lead fracture, battery depletion, or fibrosis of the lead tip.
  - It is rare for any specific part of the device to fail, but suspicion should be high if the patient had recent radiation therapy, electrocautery, defibrillation, electroshock therapy, magnetic resonance imaging (MRI), lithotripsy, or transcutaneous electrical nerve stimulation (TENS) treatments.
  - Rarely due to battery depletion.
- Failure to capture:
  - A lack of cardiac response despite appropriate sensing and subsequent pacer stimuli.
  - Commonly due to lead dislodgement, but can be due to myocardial perforation, lead fracture, fibrosis of the lead tip, poor lead placement, battery depletion, and antiarrhythmic medications.
  - Functional failure to capture occurs when pacer stimuli fall within the refractory period of previous depolarization.
- Pacing at an inappropriate rate:
  - Likely due to an endless-loop reentry tachycardia known as pacemaker-mediated tachycardia.
    - More common in DDD pacemakers.
    - Initiated by a premature ventricular stimulus, which is carried retrograde through the intrinsic conduction system to the atrioventricular node (AVN) and then the atria. This conduction is sensed by the atrial lead and causes triggering of pacing back in the ventricle. The ventricular depolarization is then sensed again in the atria, forming a loop. The intrinsic conduction system acts as a retrograde limb and the pacer circuit acts as the anterograde limb of a reentry tachycardia.
- The "pacemaker syndrome":
  - Constellation of symptoms found in 20 % of patients with pacemakers.
  - Symptoms include syncope, near-syncope, dizziness, fatigue, weakness, pain, shortness of breath, and cough.
  - Ventricular rates are poorly timed with atrial activity such that atrial contraction occurs against closed mitral and tricuspid valves.
  - Ventricles lose the benefit of the atrial kick, the atria enlarge, and signs and symptoms similar to congestive heart failure ensue.

35.4 Initial Evaluation of the Patient with a Pacemaker [4]

- History:
  - Symptoms of syncope, near-syncope, chest pain, palpitations, and irritation at the generator pocket
  - Brand and NASPE/BPEG code
  - Date of implantation
  - Location of generator pocket and any previous locations
  - Most recent electrophysiological interrogation
  - Medications that interfere with function, such as flecainide or lidocaine
  - Recent procedures, such as MRI, lithotripsy, or defibrillation
- Physical examination:
  - Check vital signs, listen for heart sounds (paradoxically split S2 is normal).
  - Inspect generator pocket; turning of the leads is associated with Twiddler's syndrome, in which a patient compulsively touches the skin around the device.
  - Look for jugular venous distension.
- Laboratory studies and electrocardiogram (ECG):
  - Obtain a chest x-ray to determine effusions, infiltrates, generator placement, and lead placement or fracture.
  - Electrolyte imbalances must be detected and corrected.
  - ECG: The following are examples of appropriate ECG patterns in patients based on type of pacing [3]:
    - VOO (asynchronous pacing): Regular pacer spikes lead to immediate QRS waveforms. Left bundle branch block (LBBB) is a normal finding in a right ventricular lead location.
    - VVI: Pacer spikes and an LBBB waveform should be seen if the intrinsic rate is below the threshold rate.
    - DDD: Various patterns are possible. If the intrinsic rhythm and intervals are normal, then no pacer spikes will be seen. If the atrial rate is slow and AV delay is normal, then an atrial spike will cause a P wave and a normal QRS. If AV delay is prolonged, then two spikes may be observed: a P wave and a QRS with an LBBB waveform.
- If malfunction is suspected:
  - Obtain intravenous (IV) access, place the patient on a heart monitor, and, if possible, consult cardiology for interrogation and reprogramming.
  - Obtain a ring magnet:
    - Positioning over the generator causes the pacing stimuli to revert to an asynchronous ventricular pacing mode at a set rate [5].

35.5 Interpreting the Type of Malfunction Based on ECG

The first step in evaluating the ECG of a malfunctioning pacemaker is to determine the presence of pacing spikes [6]:

- If pacing spikes are noted on the ECG, determine whether capture is present by ensuring that an appropriate waveform follows each pacer spike and that there is an associated pulse.
  - If capture is present, check the rate:
    - If the rate is appropriate, the pacer is functioning normally.
      - If the rate is slow, suspect oversensing.
      - If the rate is rapid, suspect undersensing or pacemaker-mediated tachycardia.
  - If capture is not present, consider metabolic effects or component failure.
- If pacing spikes are not noted on the ECG, determine whether the patient is in an intrinsic rhythm:
  - If the patient is in an intrinsic rhythm and the rate is appropriate, application of a ring magnet will cause pacer spikes to show up at a set rate. This is normal functioning.
    - If application of the magnet does not cause pacing, suspect mechanical failure.
  - If the patient is not in an intrinsic rhythm, place a magnet over the generator.
    - If magnet application causes pacing, consider oversensing.
    - If it does not, consider mechanical failure.
- If a patient is hemodynamically unstable and application of a magnet leads to stability, keep the magnet in place until the patient is able to have the pacemaker interrogated.

35.6 Management of Pacemaker-Mediated Tachycardia

- After ensuring adequate IV access, placing a heart monitor, and interpreting a baseline ECG, put a ring magnet over the generator [5].
  - If a normal rhythm results, keep the magnet on the chest.
  - If it does not change the rate, attempt isometric pectoral exercises by having the patient press the left hand against the right shoulder.
    - This is an attempt to overstimulate the pacemaker sensor and precipitate inhibition of pacer output.
    - If this is unsuccessful, consider transcutaneous pacing.
    - If transcutaneous pacing is unsuccessful, then the leads may require surgical adjustment or removal.

References

1. Ford-Martin PA, Spiwak AJ. Pacemakers. In: Gale encyclopedia of surgery: a guide for patients and caregivers. 2004. Encyclopedia.com: http://www.encyclopedia.com/doc/1G2-3406200337.html. Accessed 01 Apr 2011.
2. Bernstein A, Daubert J, Fletcher R, et al. The revised NASPE/BPEG generic code for antibradycardia, adaptive-rate, and multisite pacing. North American Society of Pacing and Electrophysiology/British Pacing and Electrophysiology Group. Pacing Clin Electrophysiol. 2002;25:260–4.
3. Marx JA, Hockberger RS, Walls RM, Adams J, editors. Rosen's emergency medicine. 7th ed. Philadelphia: Mosby; 2009.
4. Bonow RO, Mann DL, Zipes DP, Libby P, editors. Braunwald's heart disease: a textbook of cardiovascular medicine. 9th ed. Philadelphia: Saunders; 2011.
5. Roberts JR, Hedges JR, editors. Clinical procedures in emergency medicine. 4th ed. Philadelphia: Saunders; 2004.
6. Kaszala K, Huizer JF, Ellenbogen KA. Contemporary pacemakers: what the primary care physician needs to know [review]. Mayo Clin Proc. 2008;83:1170–86.

Part V

Spine Evaluation

Cervical Collar Placement

36

Justin Bennett and Lars K. Beattie

The cervical spine (C-spine) accounts for the majority of all spinal injuries. In the US prehospital setting, patients are often transported using cervical collars (C-collars) and rigid backboards in trauma and when spinal cord injuries are suspected. After airway, breathing, and circulation, every effort must be made to secure the C-spine.

There are two main subcategories of C-collars: the one-piece and the two-piece. One-piece C-collars include the Stifneck and the Ambu Perfit. Two-piece C-collars have posterior and anterior pieces, with the anterior piece usually the larger of the two. Examples of two-piece collars include the Aspen collar, the Philadelphia collar, and the Miami J collar. The basic features of a C-collar include:

- Adjustable circumference with fasteners (usually Velcro straps)
- Adjustable height with a locking device of different sizes
- Hooks for a nasal cannula
- Exposure of the anterior neck for pulse checks and advanced airway procedures
- Posterior access for cervical palpation
- Padding to protect the soft tissues of the neck

36.1 Indications

- Prehospital suspicion for spine trauma:
  - Emergency department patients or trauma patients who fail clinical rule-out criteria such as NEXUS (National Emergency X-Radiography Utilization Study) and Canadian C-spine rules (see Chap. 37)

36.2 Contraindications

- Absolute:
  - Cervical dislocation with fixed angulation
  - Impaled foreign object in the neck
  - Massive soft tissue swelling in the neck
- Relative:
  - Unsecured airway
  - Surgical airway
  - Vomiting
  - Mandible or soft tissue injuries with potential for airway compromise
  - Preexisting anatomical abnormalities

36.3 Materials and Medications

- Properly fitting C-collar
- Consider:
  - Head blocks, if needed for lateral stabilization
  - Towels or backboard pads for custom support
    - Under shoulders – pediatric patients
    - Under occiput – adults with poor C-spine mobility

J. Bennett, MD
Department of Emergency Medicine, Wake Forest University
School of Medicine, Winston-Salem, NC, USA
e-mail: jubennet@wakehealth.edu

L.K. Beattie, MD, MS (✉)
Department of Emergency Medicine, University of Florida,
Gainesville, FL, USA
e-mail: lars.beattie@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_36

36.4 Procedure (Aspen Collar)

1. Address airway, breathing, and circulation while maintaining in-line immobilization, before placing a C-collar.
2. Gather personnel:
   (a) One person is needed to apply the collar to an awake patient.
   (b) Two or more people may be required when a patient has an altered level of consciousness:
      (i) One to maintain in-line immobilization in the neutral position
      (ii) One to place the C-collar
3. While the C-spine is being held in neutral position, assess the airway before placing the C-collar:
   (a) Anticipate and prepare for airway compromise early to avoid a crash intubation.
   (b) Place airway if necessary.
4. Palpate and inspect the C-spine, head, and shoulders for evidence of trauma *before* placing the C-collar.
5. While maintaining the neutral position of the C-spine, place the C-collar:
   (a) Remove loose clothing, jewelry, and earrings that may cause soft tissue pressure wounds.
   (b) Begin with the piece of C-collar that fits under the occiput (Fig. 36.1).
   (c) Fold the Velcro straps behind the C-collar.
   (d) Gently hold back the hair (Fig. 36.2).
   (e) Slide the occipital section or piece of the C-collar behind the occiput (Fig. 36.3). (Use in-line C-spine stabilization in patients with an altered level of consciousness.)
   (f) Wrap (one-piece) or place (two-piece) the anterior section of the C-collar around the circumference of the patient's neck and snugly under the chin (Fig. 36.4).
   (g) Once the Velcro fasteners are in place, ensure that the height is properly adjusted on the C-collar to minimize C-spine mobility.
      (i) Most C-collars have height adjustments that utilize a locking device that requires releasing a locking mechanism by pulling out.



Fig. 36.1 Fold Velcro strap of C-collar posteriorly



Fig. 36.2 Slide occipital section of collar behind occiput flat against stretcher



Fig. 36.3 (**a**) Use of hand to guide C-collar behind occiput; (**b**) unfold Velcro strap and position collar behind cervical spine



Fig. 36.4 (**a**) Correct orientation of anterior portion of C-collar; (**b**) incorrect orientation of anterior portion of C-collar may cause injury



Fig. 36.5 Aspen collar is adjusted with a combination of (**a**) pulling out while (**b**) twisting a round knob at the sternal notch

   (ii) The Aspen collar is adjusted with a combination of pulling out while twisting a round knob at the sternal notch (Fig. 36.5).
   (iii) Pull out (away from patient) and twist for height adjustment of the Aspen two-piece collar.
   (iv) Adjust the height of the Ambu Perfit one-piece collar by simultaneously pulling (away from the patient) the two locking pins out and adjusting the height of the collar before pushing the pins back in (toward the patient) to lock the collar at the desired height (Fig. 36.6).

6. Special cases:
   (a) Depending on the age of the patient, it may be necessary to place towels under the shoulder blades to keep the neck in a neutral position.
   (b) Children:
      (i) Head-to-body ratios are relatively larger than that of adults.
      (ii) Placement on a backboard may cause significant neck flexion because the occiput rests on a flat board.
      (iii) Towels can be placed under a child's shoulders to minimize flexion.



Fig. 36.6 Adjustment the height of the Ambu Perfit one-piece collar by simultaneously pulling (away from the patient) the two locking pins out and adjusting the height of the collar before pushing the pins back in (toward the patient) to lock the collar at the desired height

(c) Adults with excess soft tissue or degenerative changes that prevent C-spine straightening:
    (i) A towel or pad is placed behind the occiput to prevent hyperextension.

36.5 Pearls and Pitfalls

- Pearls
  - Airway, breathing, and circulation should be assessed before placement of the C-collar.
  - A high index of suspicion of C-spine injury is needed in intoxicated or comatose patients and the elderly.
  - Always remember to adjust the height and circumference of a C-collar for a snug fit.
- Pitfalls
  - Spinal immobilization increases the risk of aspiration in vomiting patients.
  - Failure to palpate and inspect the C-spine, head, and shoulders before C-collar placement may delay recognition of an impending airway emergency and conceal signs of critical injury needing rapid assessment and care.
  - Lateral C-spine motion is unsecured unless tape, rubber blocks, or towels are used for support.
  - Overlooking C-spine stabilization during C-collar placement leaves the C-spine at risk of further injury in patients with an altered level of consciousness.
  - C-collars that are too tight may decrease venous return from the head and may increase intracranial pressure.

Selected Reading

American College of Surgeons Committee on Trauma. Advanced trauma life support for doctors. 8th ed. Chicago: American College of Surgeons; 2004.

Hankins DG, Boggust A. Prehospital equipment and adjuncts. In: Tintinalli JE, Stapczynski JS, Cline DM, Ma OJ, Cydulka RK, Meckler GD, editors. Tintinalli's emergency medicine: a comprehensive study guide. 7th ed. New York: McGraw Hill; 2012.

Hoffman JR, Wolfson AB, Todd K, Mower WR. Selective cervical spine radiography in blunt trauma: methodology of the National Emergency X-Radiography Utilization Study (NEXUS). Ann Emerg Med. 1998;32:461–9.

Roberts JR, Hedges JR. Clinical procedures in emergency medicine. 5th ed. Philadelphia: Saunders Elsevier; 2009.

Stiell IG, Clement CM, McKnight RD, et al. The Canadian C-spine rule versus the NEXUS low-risk criteria in patients with trauma. N Engl J Med. 2003;349:2510–8.

Cervical Spine Clearance

37

Braden Hexom and Tatiana Havryliuk

37.1 Indications

- Assessment of the need for radiological imaging in trauma

37.2 Contraindications

- Known unstable cervical spine (C-spine) fracture
- Known unstable ligamentous injury
- Intoxication/altered mental status
- Presence of distracting injury

37.3 National Emergency X-Radiography Utilization Study (NEXUS) and Canadian C-Spine Rules (CCR) to Assess the Need for Imaging

- *The NEXUS clinical criteria*
  1. Tenderness at the posterior midline of the C-spine
  2. Focal neurological deficit
  3. Decreased level of alertness
  4. Evidence of intoxication
  5. Clinically apparent pain that might distract the patient from the pain of a C-spine injury
- The presence of any one of the above findings is considered to be clinical evidence that a patient is at increased risk for C-spine injury and requires radiographic evaluation.
- *CCR*
  For alert (Glasgow Coma Scale [GCS] 15) and stable trauma patients
  1. Any high-risk factor that mandates radiography? *YES → Radiography*
     - Age older than 65 years
     - Dangerous mechanism (Table 37.1)
     - Paresthesias in extremities

     ↓ *NO*
  2. Any low-risk factor that allows safe assessment of range of motion? *NO → Radiography*
     - Simple rear-end motor vehicle crash (MVC)
     - Sitting position in emergency department
     - Ambulatory at any time
     - Delayed onset of neck pain
     - Absence of midline C-spine tenderness

     ↓*YES*
  3. Able to actively rotate neck? *NO → Radiography*
     - 45° left and right

     ↓*ABLE*

     No radiography
- CCR found to have higher sensitivity (99.4 % vs. 90.7 %) and specificity (45.1 % vs. 36.8 %) and a lower rate of imaging (55.9 % vs. 66.6 %) than NEXUS criteria for C-spine clearance of low-risk alert trauma patients.

Table 37.1 Dangerous Mechanism

Fall from elevation ≥3 ft/5 stairs
Axial load to head (e.g., diving)
Motor vehicle crash at high speed (>100 km/h), rollover, ejection
Motorized recreational vehicles
Bicycle crash

B. Hexom, MD (✉)
Department of Emergency Medicine, Mount Sinai Hospital,
New York, NY, USA
e-mail: braden.hexom@mssm.edu

T. Havryliuk, MD
Department of Emergency Medicine, University of Colorado
Denver, Denver, CO, USA
e-mail: tatiana.havryliuk@ucdenver.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_37

37.4 Type of Imaging

- Bones
  - C-spine computed tomography (CT)—the new gold standard.
  - Plain X-rays—less sensitive than CT; in one study X-rays missed 45 % of injuries that were picked up by CT [1].
- Ligaments
  - C-spine magnetic resonance imaging (MRI)—consider for possible ligamentous injuries and for further evaluation of obtunded patients.
  - Flexion-extension X-rays—less sensitive than MRI for detection of ligamentous injuries in the acute phase. Delayed flexion-extension films are more sensitive for ligamentous injury than those done the day of injury, but less sensitive than MRI.

37.5 Materials

- Cervical collar (C-collar) (Fig. 37.1)



Fig. 37.1 Assembly of C-collar: Select appropriate size (**a**). Invert chinstrap and snap into place (**b**). Assembled C-collar (**c**)

37.6 Procedure (Fig. 37.2)

1. Apply C-collar to stabilize spine. Select appropriate size.
2. Perform a brief neurological examination and assess the patient's mental status; proceed only if both are normal.
3. Loosen the collar to palpate the midline while the patient holds his or her head still. If spinal tenderness exists replace the C-collar and proceed to imaging (Fig. 37.3).
4. Instruct the patient to rotate the neck 45° to each side and flex the neck. If the patient is pain free and with no neurological comprise, the C-collar may be removed and no imaging of the C-spine is required (Fig. 37.4).



Fig. 37.2 Proper placement of C-collar: Slide C-collar under the neck while keeping neck immobilized (**a**). Secure the collar (**b**). Correct C-collar placement (**c**)



Fig. 37.3 Assessment of C spine tenderness: Loosen C-collar while keeping neck immobilized (**a**). Palpate midline of C spine (**b**)



Fig. 37.4 C-spine clearance: Instruct patient to rotate neck 45° each way (**a**). Instruct patient to flex neck (**b**)

37.7 Complications

- Missing clinically important C-spine injury
- Pressure ulcer from prolonged use of C-collar

37.8 Pearls and Pitfalls

- *Pearls*
  - Select appropriate size of C-collar.
  - Ensure adequate mental status because further imaging might be required in obtunded/intoxicated patients.
- *Pitfalls*
  - Avoid prolonged use of C-collar because this can lead to a pressure ulcer.

Reference

1. Schenarts PJ, Diaz J, Kaiser C, Carrillo Y, Eddy V, Morris Jr JA. Prospective comparison of admission computed tomographic scan and plain films of the upper cervical spine in trauma patients with altered mental status. J Trauma. 2001;51:663–8; discussion 668–9.

Selected Reading

Hoffman JR, Schriger DL, Mower W, Luo JS, Zucker M. Low-risk criteria for cervical-spine radiography in blunt trauma: a prospective study. Ann Emerg Med. 1992;21:1454–60.

Platzer P, Jaindl M, Thalhammer G, et al. Clearing the cervical spine in critically injured patients: a comprehensive C-spine protocol to avoid unnecessary delays in diagnosis. Eur Spine J. 2006;15:1801–10.

Stiell IG, Clement CM, McKnight RG, et al. The Canadian C-spine rule versus the NEXUS low-risk criteria in patients with trauma. N Engl J Med. 2003;349:2510–8.

Stiell IG, Wells GA, Vandemheen K, et al. The Canadian C-spine rule for radiography in alert and stable trauma patients. JAMA. 2001; 286:1841–8.

Log Roll

38

Justin Bennett and Lars K. Beattie

38.1 Indications

- Any patient arriving on a rigid backboard in the emergency department
- Assessment of posterior traumatic injuries
- Performed as early as possible after arrival to prevent skin breakdown from pressure ulcers

38.2 Contraindications

- Improperly fitted cervical collar (C-collar) or unsecured cervical spine (C-spine) before log roll
- Unsecured endotracheal tube before log-rolling intubated patients

38.3 Materials and Medications

- Personnel: three or four people
  - One to stabilize the C-spine
  - One or two to roll the patient
  - One to palpate the length of the spine
- Properly fitting hard C-collar
- Trauma shears for removing transport straps

38.4 Procedure

1. Ensure that the airway, breathing, and circulation (ABCs) are established before attempting to remove the patient from the backboard.
2. Gather personnel, at least three, but preferably four people. Larger patients will often require additional assistance.
3. For intubated patients an additional person will be needed to secure the endotracheal tube during the log roll.
4. Ensure the height is properly adjusted on the C-collar to minimize C-spine mobility (Fig. 38.1).
5. Position the stretcher at an ergonomic lifting position for the person responsible for stabilizing the C-spine.
6. Clothing and transport straps should be removed before the log roll to improve visualization of injuries.
7. The patient is asked to cross his or her hands over the chest.
8. C-spine stabilization (at head of bed)
   - Grasp the patient's trapezoids at the midclavicular line.
   - Secure the sides of the patient's head between the operator's forearms.
   - Stabilize the patient's head in neutral anatomical position relative to the body using the operator's forearms (Fig. 38.2).

J. Bennett, MD
Department of Emergency Medicine, Wake Forest University
School of Medicine, Winston-Salem, NC, USA
e-mail: jubennet@wakehealth.edu

L.K. Beattie, MD, MS (✉)
Department of Emergency Medicine, University of Florida,
Gainesville, FL, USA
e-mail: lars.beattie@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_38

9. Thoracic and lumbar spine stabilization
    - One or two (preferably two) people should stand next to the patient on the side to which the patient will be rolled.
        - One person: Place hands over the patient's shoulder and hip.
        - Two people
            - First person places hands on the patient's shoulder and hip.
            - Second person places hands on the patient's hip and knees.
    - The decision to roll to the left or right side is determined by injury sites, to minimize injury exacerbation and pain, and to minimize risk of endotracheal tube dislodgment.



Fig. 38.1 (**a**) The height of the Ambu Perfit one-piece collar is adjusted by simultaneously pulling the two locking pins out (away from the patient) and adjusting the height of the collar, (**b**) then pushing the pins back in (toward the patient) to lock the collar at the desired height



Fig. 38.2 (**a**) Incorrect: Single-point stabilization does not keep head and C-spine in line with torso (**b**, **c**). Correct: The two-point stabilization technique keeps the head and C-spine in line with the torso during the log roll

10. The person at the head of the bed signals the initiation of a synchronized log roll when everyone is in position.
11. Attention should be directed at maintaining a neutral axis along the anatomical line of symmetry during the roll (Fig. 38.3).
12. While the patient is on her or his side, the rigid backboard should be removed and secured to prevent injury of caretakers.
13. The patient's entire posterior should be exposed and examined, taking care to note lacerations and obvious deformities.
14. The entire length of the spine is examined by inspection and then by palpation to assessed for tenderness, step-offs, and deformities (Fig. 38.4).
15. Before returning the patient back onto the stretcher, ensure that any debris, glass, lumps of clothing, or blankets are removed.



Fig. 38.3 (**a**) The interlocking hands of operators performing lateral log roll help maintain spine immobilization and minimize twisting. (**b**) Two-point cervical spine stabilization is maintained in neutral axis relative to the anatomical line of symmetry during the roll. Appropriate bed height adjustment will increase the ease of the procedure



Fig. 38.4 (**a**–**c**) After backboard has been removed, the entire length of the of the spine can be appropriately palpated and assessed for injury to the thoracic and lumbar spine

38.5 Pearls and Pitfalls

- Pearls
  - The log roll should be performed in unison to avoid segmental rotation.
  - The ABCs should be established before initiating the log roll, which is part of the secondary survey in the trauma evaluation.
  - A proper log roll begins with stabilization of the C-spine because it is the most freely mobile part of the spine and, therefore, most frequently injured.
  - Take the patient off the backboard as soon as possible to prevent formation of pressure sores.
- Pitfalls
  - Failure to establish a two-point stabilization between the patient's body and the head leaves the C-spine at risk of further injury during the log roll.
  - Patients should not be left on the backboard for spinal precautions.
  - Failure to ensure that the ABCs are established before attempting a log roll.

Selected Reading

American College of Surgeons Committee on Trauma. Advanced trauma life support for doctors. 8th ed. Chicago: American College of Surgeons; 2008. ISBN 1880696312.

Roberts JR, Hedges JR. Clinical procedures in emergency medicine. 5th ed. Philadelphia: Saunders Elsevier; 2009.

Part VI

Neurologic and Neurosurgical Procedures

Burr Hole Craniotomy

39

Latha Ganti

39.1 Indications

- Extradural hematoma (EDH) or subdural hematoma (SDH) with Glasgow Coma Scale (GCS) <8 and unavailability of timely neurosurgical intervention in the face of increased intracranial pressure
- Signs of increased intracranial pressure [1]
  - Deteriorating level of consciousness
  - Slowing of the pulse
  - Dilating pupils
  - Focal seizures
  - Hemiparesis
  - Extensor posturing of the limbs

39.2 Contraindications

- Absolute
  - GCS >8
  - Immediate availability of neurosurgeon
- Relative
  - Lack of imaging (in this case, decision is guided by neurologic findings and signs of increased intracranial pressure or impending herniation)

39.3 Materials and Medications

- Razor to shave area
- 2 % lidocaine with epinephrine to numb scalp
- 10 % povidone-iodine or chlorhexidine prep
- Light, suction, cautery, dressing tray
- Gelfoam
- Penrose drain
- 3-0 silk
- #10 scalpel blade and #3 handle
- Small self-retractors or rakes
- Drill and drill bits: can be manual (Fig. 39.1) or automatic stopping variety (Fig. 39.2)
- Bone wax or electric cautery apparatus
- Suction apparatus
- Saline irrigation (IV tubing connected to a saline bag with clamp set so flow is low, or a saline syringe flush)



Fig. 39.1 Hudson brace, burr, and perforator

L. Ganti, MD, MS, MBA
Professor of Emergency Medicine, University of Central Florida,
Orlando, FL, USA

Director, SE Specialty Care Centers of Innovation, Orlando
Veterans Affairs Medical Center, Orlando, FL, USA
e-mail: lathagantimd@gmail.com

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_39



Fig. 39.2 Automatic stopping craniotomy drill set

39.4 Procedure

Preparation

1. Patient should be supine, intubated, with appropriate C-spine precautions
    - Hypertonic saline and/or mannitol can be considered for medical management of increased ICP if/as directed by neurosurgery
2. Determine location and depth for burr hole placement (Figs. 39.3 and 39.4):
    - Have CT images immediately available for viewing
    - Most common location for EDH or SDH is temporal
        - Temporal burr hole placement: 2 fingerbreadths above the ear, 2 fingerbreadths forward (Fig. 39.5)
        - Parietal burr hole placement: 2 fingerbreadths above the ear, 3 fingerbreadths backward (behind the ear)
        - Frontal burr hole placement: 3 fingerbreadths from midline, 3 fingerbreadths above hairline
    - Estimate depth of hematoma by counting the number of slices the hematoma is as seen on CT scan and multiplying by the slice thickness [2]
3. Shave hair around area of hematoma.
4. Prep skin with betadine and chlorhexidine.
5. Anesthetize scalp skin with lidocaine and epinephrine.

    Accessing hematoma
6. Make a vertical incision approximately 4 cm long down to bone.s
7. Use periosteal elevator or end of scalpel blade to scrape muscle and periosteum away from bone.
8. Place self-retaining retractors (or rakes) to keep field open (Fig. 39.6).
9. Using a drill with a clutch mechanism [2], drill through outer table (resistance), diploic space (no resistance), then inner table.
    - Burr hole needs to be placed over the *center* of the hematoma (Fig. 39.7).
10. Control bone bleeding with bone wax; control bleeding from veins and/or muscle with gelfoam sponge or cautery (diathermy).
    - Wound edges may also be cauterized or tamponaded with manual pressure +/– epinephrine gauze.
11. Once in the inner table, separate dura from bone
12. Enlarge opening by switching to a conical or cylindrical burr or use a rongeur

    Evacuating hematoma
13. EDH blood will be visible at this point and should be gently suctioned out.
14. SDH blood will be seen as a tenting of the dura and may be clotted: lift the dura with a hook or make an incision with a fresh scalpel through it to expose the clot and drain.

15. Irrigate with saline (this can be via a hand syringe or via IV tubing connected to a saline bag at low sped flow).
16. Repeat gentle suction.

Closure

17. For temporal burr holes, ligate middle meningeal artery (if visible) or cauterize.
18. Place Penrose drain (Fig. 39.8) and close the dura first with a 3-0 absorbable suture, ensuring there is no dural leak (will lead to infection if present).
    - A watertight seal of the duraplasty is essential to minimize cerebrospinal fluid leakage.
19. Loosely suture scalp using 3-0 silk.


Parietal burr hole
Frontal burr hole
Temporal burr hole
Middle meningeal artery

Fig. 39.3 Positions of burr hole placement


a
Site of burr hole
Tragus of ear
b
Anterior branch of middle meningeal artery
Blood clot lying between endosteal layer and meningeal layer of dura
Zygomatic arch

Fig. 39.4 (**a**, **b**) Anatomy for temporal burr hole placement (most common location)



Fig. 39.5 Landmark for temporal burr hole above zygoma, make 5 cm incision over site



Fig. 39.6 After incision is made, use retractors (preferably self-retaining) to visualize field



Fig. 39.7 Use penetrator drill to get through outer table. Follow up with a burr to get through the rest of the layers. Can also use an automatic stop craniotomy drill



Fig. 39.8 Suture in Penrose drain and close the wound

39.5 Complications

- Brain laceration/perforation
- Temporal artery laceration
- Wrong location (minimized when viewing images during procedure)
- Facial artery laceration
- Meningitis
- Brain abscess

39.6 Pearls and Pitfalls

- Pearls
  - If brain herniates through the burr hole, there is likely a hematoma at another location.
  - Remember this is only a lifesaving procedure that is to be done when timely neurosurgical intervention is not possible. *Do not delay transfer* of the patient
- Pitfalls
  - Bone in temporal area is quite thin; if not using an automatic stop drill, be very careful not to go too far and perforate the brain.

References

1. Wilkinson DA, Skinner MF. The primary trauma care manual for trauma management in district and remote locations. World Health Organization (WHO). http://www.steinergraphics.com/surgical/006_17.6.html. Accessed 22 May 2014.
2. Wilson MH, Wise D, Davies G, Lockey D. Emergency burr holes: "how to do it.". Scand J Trauma Resusc Emerg Med. 2012;20:24. doi:10.1186/1757-7241-20-24.

Selected Reading

http://www.viewmedica.com/vm/pages/library/L_df8516c9#vm_A_ac54d3a1. Accessed 29 June 2014.

External Ventricular Drain Placement

40

Latha Ganti

An external ventricular drain (EVD; also known as a ventriculostomy tube) is placed via a burr hole in one of the ventricles of the brain (Fig. 40.1) to drain excess cerebrospinal fluid (CSF) that causes elevated intracranial pressure.

40.1 Indications

- Emergent need for intracranial pressure (ICP) monitoring and or management
- Enlarged ventricles on neuroimaging with Glasgow coma scale <12
- Subarachnoid hemorrhage with Hunt-Hess grade ≥3 (Table 40.1)
- Coma
- Obstructive hydrocephalus
- Intraventricular hemorrhage
- Signs of increased intracranial pressure

40.2 Contraindications

- Absolute
  - Immediate availability of a neurosurgeon who can do the procedure
- Relative
  - Coagulopathy
  - Scalp infection

40.3 Materials and Medications

- Intubation equipment and medications for sedation as needed
- Sterile gloves, gown, mask
- Ruler
- Surgical marking pen
- 1–2 % lidocaine with epinephrine to numb scalp
- 5 cc syringe and needles to give anesthetic
- 10 % povidone-iodine solution and swabs
- Razor to shave area
- Fenestrated clear drape
- Scalpel #11 blade (for scalp) and #15 blade (for periosteum) with #3 handle (Fig. 40.2a)
- 4×4 sterile gauze
- Adson forceps
- Mosquito forceps
- Self-retaining eyebrow retractor (Fig. 40.2b)
- 3-0 nylon suture and needle holder and/or skin stapler
- Scissors
- A hand drill with variable chuck
- One or more drill bits with depth guards in 5/32″ (3.97 mm), 13/64″ (5.31 mm), and 1/4″ (6.35 mm) sizes
- A hex wrench for depth guard adjustment
- Ventricular catheter
- Primed ventricular drainage collection system

40.4 Procedure

Patient preparation

1. Patient is intubated and placed supine in neutral position with head of the bed elevated 30–45°.
2. Administer one dose of intravenous antibiotics that covers skin flora.
3. Make precise measurement of where the hole and incision will be made. Most commonly, EVDs are placed in

L. Ganti, MD, MS, MBA
Professor of Emergency Medicine, University of Central Florida, Orlando, FL, USA

Director, SE Specialty Care Centers of Innovation, Orlando Veterans Affairs Medical Center, Orlando, FL, USA
e-mail: lathagantimd@gmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_40


Lateral ventricles
Anterior horn
Interventricular foramen (connects lateral ventricle and 3rd ventricle)
Inferior horn
Third ventricle
Cerebral aqueduct (connects 3rd and 4th ventricle)
Lateral aperture (apertures of 4th ventricle lead to subarachnoid space)
Fourth ventricle
Central canal of spinal cord
Posterior horn
Inferior horn
Median aperture
Lateral aperture
Anterior view
Left lateral view

Fig. 40.1 Ventricles of the brain that contain CSF

Table 40.1 Hunt and Hess scale for subarachnoid hemorrhage [1]

Grade	Signs and symptoms
1	Alert and oriented, mild headache, slight or no nuchal rigidity
2	Alert and oriented, moderate to severe headache, nuchal rigidity, no neurologic deficit
3	Drowsiness, confusion, mild focal neurologic deficit
4	Stupor, moderate-severe hemiparesis
5	Coma, decerebrate posturing

the right frontal scalp, as this is the nondominant hemisphere in >95 % of the population.

4. Using a sterile skin/surgical marker, draw a line 11 cm back from nasion and then a point 3 cm to the right of that, which corresponds to the mid-pupillary line. This is called Kocher's point (Fig. 40.3).
5. Once Kocher's point is marked, shave skin and remove loose hairs so field is wide enough for subcutaneous catheter placement and tunneling.
6. Prep area with povidone-iodine.
7. Place sterile clear drape over field.
8. Prep area of incision once more.
9. Infiltrate scalp with 1–2 % lidocaine with epinephrine (the epinephrine acts as a hemostatic agent, keeping surgical field clean) (Fig. 40.4).
10. Make a 2 cm linear stab incision and extend incision to skull (Fig. 40.5).
11. Use eyebrow self-retaining retractors to hold skin edges back.
12. Drill burr hole with hand drill (Fig. 40.6).
13. Irrigate burr hole with sterile saline.
14. Put on a new pair of sterile gloves (prior to handling ventriculostomy catheter).
15. Remove ventricular tubing from sterile package. It has markings on it that are 1 cm apart.
16. Insert ventriculostomy catheter perpendicular to the skull at the point of insertion. Catheter is aimed at the ipsilateral medial canthus of the eye (anteroposterior plane) and tragus of ear (lateral plane).
17. Advance ventriculostomy tube 5–6 cm with stylet from outer skull table so it sits in the anterior horn of the lateral ventricle (Fig. 40.7).
18. Ensure ventriculostomy catheter is draining CSF.
19. Attach metal trocar to tip of ventriculostomy catheter and tunnel the trocar and catheter under the galea approximately 3–5 cm to the right of the original incision. Bring trocar out through separate stab incision in scalp.
20. Remove trocar, make sure ventriculostomy catheter is still draining CSF.
21. Place temporary cap on ventriculostomy catheter to prevent overdrainage of CSF.

22. Close the original incision with either sutures or staples.
23. Secure catheter to the scalp using staples.


#11 scalpel blade: elongated triangular blade, sharpened along the hypotenuse edge, with a strong pointed tip making it ideal for stab incisions
#15 scalpel blade: small curved cutting edge with flat back, used for making short and precise incisions
a
b

Fig. 40.2 (**a**) Surgical scalpel blades. (**b**) Self-retaining eyebrow retractors

24. Cover incision with sterile transparent dressing.
25. Suture stopcock to ventricular catheter to ensure it does not come off (take care not to make suture too tight or it will occlude ventriculostomy catheter).
26. Remove blind end of stopcock, attach ventricular catheter to ventricular drain system once it is primed.

Priming, setup, and maintenance of ventricular drainage system

27. Prepare drainage system by priming system with sterile, preservative-free saline.
28. Place zero point of drainage system at midbrain (level of patient's ear tragus) or above midbrain at 15–20 cm of H_20 (target ICP set by neurointensivist and will change depending on patient's situation) (Fig. 40.8).
29. Attach drainage tubing.
30. Patients who require an EVD should be closely monitored by nurses trained and competent in assessment and management of the drain and in recognizing signs of increased ICP in the patient.
31. Assessment of the drainage system should be done a minimum of every 4 h, which includes inspecting the EVD from the insertion site along the entire drainage system, checking for cracks in the system or fluid leaking from the insertion site [2].

Post-procedure

32. Obtain CT scan of brain to verify placement (Fig. 40.9).


Mid-pupillary line
(Adults) 11–12 cm behind nasion
3 cm off midline
Aim catheter toward ipsilateral medial canthus and ipsilateral tragus
1 cm anterior to coronal suture

Fig. 40.3 Kocher's point for frontal EVD placement



Fig. 40.4 Anesthetize skin



Fig. 40.5 Make stab incision



Fig. 40.6 Make burr hole



Fig. 40.7 Advance ventriculostomy catheter with stylet

40.5 Complications

- Hemorrhage
- Infection: meningitis, ventriculitis
- Tract hematoma
- Migration/dislodgement

40.6 Pearls and Pitfalls

- Pearls
  - EVD needs to be re-leveled every time the patient moves. Family and all visitors must be informed that any patient movement or change in elevation of head

Fig. 40.8 Zero point of drainage system placed at midbrain (level of patient's ear tragus)


Collection system
Zero-line is placed at the level of the ear
Black arrow on chamber indicates pressure level set by surgeon
Ventricles of the brain
Drain
Collection bag



Fig. 40.9 CT scan demonstrating typical placement of ventriculostomy catheter in ipsilateral anterior horn of lateral ventricle [3] (Reproduced with permission from National Institutes of Health: Jaffe et al. [3])

of bed will require re-leveling of EVD in order to ensure it is a the appropriate level for CSF drainage.
  - CSF collection chamber should remain upright to prevent reflux/leakage.
  - EVD placement in the parieto-occipital scalp or frontotemporal or trans-sylvian locations is generally not done at the bedside due to higher rate of complications. This is performed in the operating room.
- Pitfalls
  - If the drain is leveled too low: CSF will drain too easily, which can lead to re-rupture of an unrepaired ruptured cerebral aneurysm or cause a subdural hematoma due to shearing of bridging veins.
  - If the drain is leveled too high, CSF will not drain or will not drain at desired rate, leading to hydrocephalus. The ICP will need to be higher in order for the CSF to drain.

References

1. Hunt WE, Hess RM. Surgical risk as related to time of intervention in the repair of intracranial aneurysms. J Neurosurg. 1968; 28(1):14–20.
2. Care of the patient undergoing intracranial pressure monitoring/external ventricular drainage or lumbar drainage. AANN clinical practice guideline series. 2011. http://www.aann.org/uploads/AANN11_ICPEVDnew.pdf. Accessed 27 Sept 2014.
3. Jaffe J, Melnychuk E, Muschelli J, et al. Ventricular catheter location and the clearance of intraventricular hemorrhage. Neurosurgery. 2012;70(5):1258–64.

41

Lumbar Puncture in Adults

Kevin Tench, L. Connor Nickels, and Rohit Pravin Patel

41.1 Indications

- Diagnostic
  - Evaluation for the possibility of a central nervous system (CNS) infection: viral, bacterial, and fungal meningitis and encephalitis
  - Evaluation for inflammatory processes: multiple sclerosis, Guillain-Barré syndrome
  - Evaluation for spontaneous subarachnoid hemorrhage (SAH)
  - Suspicion of CNS diseases: oncological and metabolic processes
- Therapeutic
  - Therapeutic reduction of cerebrospinal fluid (CSF) pressure
  - Procedures requiring lower body analgesia or anesthesia
  - Intrathecal antibiotic administration for some types of meningitis
  - Chemotherapy and methotrexate for some forms of leukemia and lymphomas

41.2 Contraindications

- Presence of infection in tissues at or around puncture site.
- Increased intracranial pressure (ICP) from a space-occupying lesion; patients with signs of cerebral herniation or with potential of increased ICP and focal neurological signs.
- Bleeding diathesis (thrombocytopenia, anticoagulant therapy, hemophilia); may increase risk of spinal hematoma, but level of coagulopathy that increases risk is unclear.
- Patients with cardiorespiratory compromise may worsen owing to position.

Patients with prior history of lumbar surgery, osteoarthritis, ankylosing spondylitis, kyphoscoliosis, or degenerative disk disease might have more success if lumbar puncture is performed by an interventional radiologist using imaging techniques and should be considered.

41.3 Materials and Medications (See Fig. 123.1)

- Spinal needle(s) with stylet
  - Adults: 3.5-in. 20-gauge needle; obese may require 5.0-in. 22- to 24-gauge needle
  - Children: 2.5-in. 22-gauge needle
  - Infants: 1.5-in. 22-gauge needle
- Three-way stopcock (optional: drainage catheter)
- Manometer (optional: extension tube for higher opening pressures)
- Specimen tubes (# may vary, but in general labeled 1–4, important to obtain from 1, 2, 3, 4 owing to cell count obtained from tubes 1 and 3)
- Local anesthetic (lidocaine 1 or 2 %), 5- to 10-mL syringe and needle (25-gauge) for local anesthesia
- Sterile drapes and gauze
- Mask, sterile gown, sterile gloves
- Antiseptic solution for skin preparation (Chloroprep or iodine)

K. Tench, MD
Department of Emergency Medicine, Banner Boswell Medical Center, Sun City, AZ, USA

L.C. Nickels, MD, RDMS (✉) • R.P. Patel, MD
Department of Emergency Medicine, University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: cnickels@ufl.edu; rohitpatel@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_41

41.4 Procedure

1. Positioning
    - Determined by practitioner preference or patient capability.
    - Options: lateral recumbent position, upright sitting position (Fig. 41.1).
    - Lateral recumbent position is preferred to obtain accurate opening pressure and to reduce the risk of post-puncture headache.
    - Both positions require the patient to arch the lower back toward the practitioner in order to open up the intervertebral spaces (obtain the "fetal position" or arch "like a cat").
    - Shoulders and hips should remain aligned during process.
2. Landmarks
    - Determined by palpation.
    - Draw a visual line between the superior aspects of the iliac crests that intersects the midline at the L4 interspace. The L3–4 and L4–5 spaces are preferred because these points are below the termination of the spinal cord.
    - Palpate the posterosuperior iliac crests with the midpoint of a visual line that connects the two crests representing the L4 spinous process.
    - Palpate the space between the L3–4 or the L4–5 spinous processes and mark where the needle will be placed.
3. Ultrasound guidance (optional)
    - Helpful in obese patients, patients with previous surgical scarring, or anyone in whom palpation of the spinous processes is not easily done.
    - Sonographic measurement of the dura mater strongly correlates with needle depth needed to obtain CSF.
    - Identify the spinal process in the short and long axis to determine the midline and the interspinous space.
    - Identify the interspinous ligament for estimation of the depth of needle insertion.

      Commonly only the spinous processes are well visualized, and the interspinous ligament, ligamentum flavum, and subarachnoid space are less clearly seen.
    - High-frequency (5–10 MHz) linear probe to best evaluate anatomy.
    - A marking pen can be used to create a cross-hair-type figure (Fig. 41.1).
    - After placing the patient as described, locate the midline at the lumbar spine in transverse and longitudinal orientations.
    - Bright echogenic structures with shadowing posteriorly identify the spinous processes.
    - Transverse probe positioning to identify midline (Fig. 41.2), and then longitudinal probe positioning to identify interspinous space (Fig. 41.3).
4. Sterile preparation
    - After positioning and palpating the appropriate landmarks, the practitioner should then dress in the appropriate protective gear: mask, gown, and sterile gloves.
    - After dressing, the practitioner can then sterilely prepare the patient.
    - – Make sure the patient's back is completely exposed.
    - – Clean the patient's back with an antiseptic solution (Chloroprep should be scrubbed in an up/down and side/side fashion; iodine in a circular motion starting from the center of the anticipated insertion point).
    - – Apply sterile drapes with the puncture site exposed.

      This is an optimal time to make sure all equipment in a standard lumbar puncture tray connects properly and that the stopcock for opening pressure measurement is assembled. Make sure the stopcock is closed away from the patient so that CSF can flow from the patient to the manometer. If the assembly is done, it will decrease the amount of CSF lost after the puncture.

- Local anesthesia
    - – 1 % Lidocaine or anesthetic cream topically before preparing skin
    - – For injection, form a skin wheal over the insertion site.
    - – Inject into the deep tissues below the wheal in all directions while only breaking the skin once.
    - – Systemic sedatives and analgesics may also be used.

5. Needle insertion
    - Needle should be inserted in the midline between the L3–4 or the L4–5 spinous process, and the stylet should be firmly in place.
    - Initially parallel to the bed, but once into the subcutaneous tissue, the needle should be angled toward the umbilicus (slightly cephalad, 15°) with the bevel facing upward (Fig. 41.4). This sagittal plane orientation spreads rather than cuts the fibers of the dural sac, which run parallel to the spinal axis.
    - If properly positioned, the needle passes through the skin; subcutaneous tissue; supraspinous ligament; interspinous ligament between the spinous processes; ligamentum flavum; epidural space including the internal vertebral venous plexus, dura, and arachnoid; into the subarachnoid space and between the nerve roots of the cauda equina.
    - In most cases, a "pop" will be felt when the needle penetrates the ligamentum flavum, entering into the subarachnoid space; then intermittent withdrawal should be done in 2-mm intervals to assess for CSF flow.
    - If bone is encountered during insertion, the needle should be withdrawn partially without exiting the skin and readjusted to a different angle more cephalad.



Fig. 41.1 Sitting position (**a**) left lateral decubitus position, (**b**) with general areas of insertion of needle



Fig. 41.2 Transverse view, *white arrow* indicates spinous process. Place in middle of ultrasound view to locate appropriate midline access point



Fig. 41.3 Longitudinal view of lumbar spine. *Thick white arrows* indicate vertebral shadows; *thin white arrow* indicates supraspinous ligament. *Red arrow* indicates trajectory of needle

- If the tap is traumatic, CSF may be blood tinged but should clear as more is collected. If it does not clear, it may indicate intracranial hemorrhage or subarachnoid blood. Also in traumatic patients, clotting will be seen in the tubes; clotting does not occur in SAH owing to defibrinated blood being present in the CSF. Blood-tinged CSF can also be seen in herpes simplex virus (HSV) encephalitis.
- A dry tap is usually due to incorrect positioning and misdirection of needle, often due to a superior direction of the needle with obstruction by the lamina or spinous process of the superior or inferior vertebra. If the needle is too lateral, an inferior or superior articular process may be hit.

  If flow slows down, rotate the needle 90° because a nerve root may be obstructing the opening.

6. Opening pressure measurement
   - Must be performed in the lateral recumbent position. Although there are some conversion formulas from the sitting position, these are not standard of care.



Fig. 41.4 Angle of insertion of needle, cephalad with bevel up

- Once the needle is in the subarachnoid space and CSF is flowing from the needle, the three-way stopcock should be attached to the needle and the manometer should be attached to the stopcock to take a measurement. Use the flexible tube to connect the manometer to the hub of the needle.
- Note the height of fluid in the manometer after it stops rising (normal opening pressure, <20 cm Hg); it may be possible to see pulsations from cardiac or respiratory motion.
  - Elevated CSF pressure is seen with meningeal inflammation, hydrocephalus, pseudotumor cerebri, SAH, and CHF.
  - Decreased CSF pressure is seen in leakage of CSF and severe dehydration.

7. Collecting CSF fluid
   - Collect at least 1–2 mL of CSF fluid in each tube, going from 1 to 4 and never aspirate because this can cause hemorrhage.
   - After collecting the fluid, replace the stylet and remove the needle, clean the skin, and place a bandage over the puncture site.
   - General recommendations
     - Tube 1: glucose, protein, protein electrophoresis
     - Tube 2: Gram stain, bacterial and viral cultures
     - Tube 3: cell count and differential
   - When ruling out SAH, cell count should be performed in tubes 1 and 3 or 1 and 4 to differentiate between SAH and traumatic tap.
     - Tube 4: Any special tests: myelin basic proteins, lactate, pyruvate, and smear on cell concentrates all depend on suspicion.

41.5 Complications

- Implantation of epidermoid tumors: from introducing skin plug into the subarachnoid space and can be avoided by using stylet when advancing.
- Postlumbar puncture headache: most common, occurring in 36.5 % of patients within 48 h
- CSF leak: causes headache when CSF leak through puncture site exceeds rate of production
- Bleeding: most common in patients with bleeding diathesis; may result in spinal cord compression
- Epidural hematoma
- Infection: local cellulitis, abscess (local or epidural), or meningitis
- Herniation syndromes: high risk can be identified by computed tomography but may not completely identify all patients with increased ICP
- Backache: local or referred pain
- Cardiorespiratory compromise

41.6 Pearls and Pitfalls

- Pearls
  - Positioning the patient is key to a successful procedure.
  - In adults the spinal cord may terminate higher than previously thought and it may be okay to go one interspace higher than recommended; but in infants owing to the differential in longitudinal growth of the spinal canal and cord, the spinal cord usually ends in L3. So in children the tap must go L4–5 or L5–S1.
  - Always keep the stylet in place until after the skin barrier is penetrated because this will avoid introduction of epidermoid tissue.
- Pitfalls
  - Postspinal headaches can be avoided with smaller needles and intravenous (IV) fluids.
    - Having the patient lie on the back for 1 h after the procedure has no change in incidence of headache.
    - Treatment consists of IV fluids initially, then caffeine, and, ultimately, if the headache persists, a blood patch.

Selected Reading

Boon JM, Abrahams PH, Meiring JH, Welch T. Lumbar puncture: anatomical review of a clinical skill. Clin Anat. 2004;17:544–53.

Ellenby MS, Tegtmeyer K, Lai S, Braner DA. Videos in clinical medicine. Lumbar puncture. N Engl J Med. 2006;355:e12.

Ferre RM, Sweeney TW, Strout TD. Ultrasound identification of landmarks preceding lumbar puncture: a pilot study. Emerg Med J. 2009;26:276–7.

Peterson MA, Abele J. Bedside ultrasound for difficult lumbar puncture. J Emerg Med. 2005;28:197–200.

Reflex Eye Movements (Doll's Eyes and Caloric Testing)

42

Thomas T. Nguyen, Tina Dulani, and Saadia Akhtar

42.1 Doll's Eyes (Oculocephalic Reflex Testing)

42.1.1 Indications: Doll's Eyes

- To assess brain stem function of a comatose patient
- To assess cerebral function in a comatose patient if brainstem function is intact

42.1.2 Contraindications: Doll's Eyes

- Absolute
  - Occult cervical spine injury; rule out radiographically and clinically
  - Basilar skull fracture
- Relative
  - Rheumatoid arthritis; increased risk of atlantoaxial subluxation resulting in spinal cord compression
  - Osteoporosis; increased risk of cervical spine injury
  - Cervical spine ankylosis; increased risk of cervical spine injury

42.1.3 Procedure: Doll's Eyes (Fig. 42.1)

1. Stand at the head of bed and grasp the patient's head with both hands.
2. Use the thumbs of both of hands to open the patient's eyelids.
3. Rapidly move the patient's head to one side and hold.
4. Simultaneously observe for the presence or absence of horizontal movements.
   (a) Head movement to one side should result in conjugate eye movement to the opposite side and then in spontaneous return of the eyes to the midline (normal test).
   (b) Normal oculocephalic reflex is the observation of conjugate eye movements to the opposite side of head turning. This indicates a functionally intact brainstem in a comatose patient.
   (c) Abnormal oculocephalic reflex: incomplete or absent horizontal eye movements. The eyes remain in the midline. This indicates impairment of the brainstem; caloric testing should be done if not contraindicated.
   (d) A partially abnormal oculocephalic reflex: conjugate eye movement opposite to head turning but does not return to the midline means the brainstem is intact but cerebrum function is not.
5. Repeat by rotating the head to the opposite side.
6. Vertical oculocephalic response can be tested by moving the patient's head up and down. A compensatory vertical eye movement should be observed.
   (a) This test is useful only if the horizontal oculocephalic reflex is negative. An intact vertical oculocephalic reflex with a negative horizontal oculocephalic reflex suggests a pontine lesion.
7. Document the observations.

42.1.4 Pearls and Pitfalls: Doll's Eyes

- Oculocephalic reflex may not be present in the first 10 days of life and is unreliable until 2 years of age.
- Do not attempt the doll's eye maneuver in patients with cervical spinal injuries.

T.T. Nguyen, MD (✉) • S. Akhtar, MD
Department of Emergency Medicine, Mount Sinai Beth Israel,
New York, NY, USA
e-mail: tnguyen@chpnet.org

T. Dulani, MD
Department of Emergency Medicine, New York Methodist
Hospital, Brooklyn, NY, USA
e-mail: tdulani@gmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_42



Fig. 42.1 The oculocephalic (doll's eyes) reflex in a patient with an intact brainstem. (**a**) Start with the head facing upright and grasp as depicted using both thumbs to keep the eyes open. (**b**) Rotate the head 90° to the right and the eyes deviate to the left (opposite side). (**c**) The eyes will spontaneously return to the midline. (**d**) Then rotate the head 180° to the left and the eyes should deviate to the right (opposite side). (**e**) The eyes will spontaneously return to the midline

- The doll's eye reflex can be absent or partial in patients with ocular muscle nerve palsy (e.g., cranial nerve [CN] 6).
- Make sure the patient does not have a neuromuscular blockade agent or other toxins present.
- A conscious person can suppress the doll's eye or oculocephalic reflex.

42.2 Caloric Reflex Testing (Vestibuloocular Reflex)

42.2.1 Indications: Caloric Reflex Testing

- In any comatose patient with abnormal doll's eye or if it cannot be performed
- To assess brainstem function of a comatose patient
- To assess asymmetrical function in the peripheral vestibular system

42.2.2 Contraindications: Caloric Reflex Testing

- Absolute
  - Perforated tympanic membrane
  - Presence of tympanostomy tubes
  - Basilar skull fracture, petrous bone fracture
  - Suspicion of cerebrospinal fluid (CSF) otorrhea

42.2.3 Materials and Medications: Caloric Reflex Testing

- Otoscope
- 60-mL syringe
- 16- to 18-gauge angiocatheter
- Thermometer
- Ice-cold water (30–33 °C)
- Warm water (44 °C)
- Emesis basin (to collect water)
- Towels or Chux

42.2.4 Procedure: Caloric Reflex Testing (Fig. 42.2)

1. Place the patient supine and elevate the head to 30° to bring the lateral semicircular canal into the upright position.
   (a) Careful otoscopic examination should be done before caloric testing to make sure there are no contraindications.
   (b) Remove any cerumen from the external auditory canal (EAC); the irrigation fluid should be able to reach the tympanic membrane.
2. Get a 60-mL syringe with an 18-gauge angiocatheter. Remove the plastic angiocatheter from the needle and discard the needle.
3. Place the angiocatheter on the 60-mL syringe and fill it with ice water (30 °C).
4. Place the angiocatheter in the EAC and squirt the water in over a period of 30–40 s. The water should freely enter and exit the auditory canal.
   (a) The stimulus depends upon the temperature of the water and not on water pressure.
   (b) Reflex horizontal movements may be delayed for up to 1 min after irrigation of the EAC.
5. Observe: Have an assistant hold the eyelids open with the head still and facing forward.
   (a) Normal test: Cold water induces slight deviation of the eyes to the side being irrigated followed by a latent period of approximately 20 s and then nystagmus to the opposite side (direction of the fast phase).
   (b) Abnormal test: Eyes do not deviate; this implies brainstem problems.
   (c) The quick phase may return in patients in a persistent vegetative state. Search for the slow, full eye deviation in response to caloric stimulation and not nystagmus when assessing a comatose patient.
6. Pause at least 5 min so the auditory canal can warm up.
   (a) The same EAC can be irrigated with warm water if the contralateral side cannot be tested for any reason.
7. Repeat steps 3–5 in the opposite ear.
   (a) Warm water testing can be used if there is no response to cold water testing. Use warm water (44 °C) and repeat testing, starting with one ear and then, after 5 min, with the other ear.
   (b) Warm water induces nystagmus to the same side (direction of the fast phase).
   (c) COWS: Cold opposite, warm same (referring to the compensatory fast phase of eye movement, the nystagmus).
8. Dry the patient off and reexamine the tympanic membranes to assess for testing-related injury.

42.2.5 Complications: Caloric Reflex Testing

- If contraindications are excluded, no significant complications are expected.
- Tympanic membrane injury or EAC injury can occur from the angiocatheter, forceful irrigation, or injury during cerumen removal.
- Potential complications from caloric testing include meningitis, otitis media, and vomiting.

Fig. 42.2 Depiction of the vestibuloocular reflexes with unilateral cold-water irrigation


Unilateral cold water irrigation
Caloric response
Right ear
Left ear
Normal, awake patient
(Fast phase nystagmus
(Slow phase nystagmus
Conjugate deviation
Disconjugate deviation
Unresponsive

42.2.6 Pearls and Pitfalls: Caloric Reflex Testing

- A positive response to caloric testing indicates intact brainstem function.
- In an awake patient, excessive reflex vagal activity may occur (i.e., nausea, vomiting, dizziness).
- Absence of horizontal eye movement means comatose brainstem injury.
- Disconjugate or impaired reflex horizontal eye movements indicate impaired brainstem function at or below the level of the oculomotor nucleus.
- A comatose patient with intact full-reflex horizontal eye movements indicates that the lesion causing coma is in the cerebral hemisphere.

Selected Reading

Gomella LG. Central nervous system. In: Clinician's pocket reference. 11th ed. New York: McGraw-Hill; 2007.

McCann J, et al. Rapid assessment: a flowchart guide to signs and symptoms. Philadelphia: Lippincott William & Wilkins; 2004.

Reeve A, Swensen R. Auditory and vestibular function. In: Disorders of the nervous system: a primer. Hanover, NH: Dartmouth Medical School; On Line; 2009.

Reichman EF, Simon RR. Chapter 103. Reflex eye movements (caloric testing and doll's eyes). In: Emergency medicine procedures. New York: McGraw Hill Education; 2004.

Ropper AH, Samuels MA. Chapter 15. Deafness, dizziness, and disorders of equilibrium. Chapter 17. Coma and related disorders of consciousness. In: Adams and Victor's principles of neurology. 9th ed. New York: McGraw Hill; 2009.

Simon RP, Greenberg DA, Aminoff MJ. Chapter 3. Disorders of equilibrium. In: Clinical neurology. 7th ed. New York: McGraw Hill; 2009. http://www.accessmedicine.com.elibrary.einstein.yu.edu/content.aspx?aID=5146162.

Dix-Hallpike Maneuver

43

Rui Domingues and Muhammad Waseem

The Dix-Hallpike maneuver, also termed the "head-hanging positioning maneuver," is helpful in confirming the clinical suspicion of benign paroxysmal positional vertigo (BPPV). This maneuver provokes abnormal nystagmus, which is a characteristic feature of BPPV.

43.1 Indications

- BPPV is one of the most common types of vertigo.
  - The pathophysiology of BPPV, in brief, is believed to be due to free-moving densities (canaliths/otoliths) in the posterior semicircular canal; with head movement, the particles would alter the flow of the endolymph and cause the stimulation of the ampulla. The particles in the canal cause slow or even reversal of the movement of the cupula and create signals that do not correlate with the actual head movements, therefore causing the sensation of nystagmus.
  - This maneuver locates the cause of vertigo as either the inner ear or the brain; if the problem is in the ear, this maneuver helps localize which ear is affected.
- This maneuver is indicated for patients presenting with vertigo, which is evoked by a change in position and has no symptoms at rest.
- This maneuver is inexpensive, easily done, and part of the physical examination when a patient presents with the complaint of dizziness or vertigo.

43.2 Contraindications

- Severe cervical spine disease.
- Unstable spinal injury.
- High-grade carotid stenosis.
- Unstable heart disease.
- Elderly patients may not tolerate this maneuver.
- There is no need to perform this test in the presence of nystagmus at rest.

43.3 Materials

- Examination table
- Flat cushion
- Frenzel goggles: These high-powered (+20 diopters) magnifying glasses can be placed on a patient during the performance of the maneuver and have shown to increase the sensitivity of the Dix-Hallpike maneuver by preventing the patient from visually fixating on an object, thereby preventing suppression of nystagmus. They are not required to perform the maneuver; they usually are used by specialists.

43.4 Procedure (Fig. 43.1)

1. Have the patient sit at the edge of a bed. The patient is instructed to maintain eye contact with the physician throughout the maneuver.
2. With the patient seated, the examiner will extend the neck, approximately 20°, and turn the head to one side, approximately 30–45°.
3. The examiner then assists the patient by lowering the patient quickly into a supine position, so that the head hangs over the edge of the bed or table, with the neck in a hyperextended position. A flat cushion can be placed

---

R. Domingues, MD • M. Waseem, MD (✉)
Department of Emergency Medicine, Lincoln Medical and Mental Health Center, New York, NY, USA
e-mail: rbdomingues@hotmail.com; waseemm2001@hotmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_43



Fig. 43.1 (**a**) With the patient seated, the doctor will extend the neck, approximately 20°, and turn the head to one side, approximately 30–45°. (**b**) The physician then assists the patient by lowering the patient quickly into a supine position, so that the head hangs over the edge of the bed or table, with the neck in a hyperextended position

beneath the person's back in the shoulder blade area to assist with obtaining head extension.

4. This position is held, and the examiner observes for nystagmus for up to 60 s.
    (a) Nystagmus is a rapid, rhythmic movement of the eyes and usually appears after a brief period and lasts less than 30 s.
    (b) The direction of the nystagmus is usually up and twisted; therefore, the eyes will beat toward the ground.
    (c) If the patient becomes dizzy or the doctor sees nystagmus, the test is positive for the ear that is pointed to the floor.
5. The patient is then returned to the upright position and is again observed for nystagmus for 30 s.
6. If nystagmus is not provoked, the maneuver is repeated with the head turned to the opposite direction.
7. If nystagmus is provoked, the patient should have the maneuver repeated to the same side.
    (a) With each repetition, the intensity and duration of nystagmus should decrease.

43.5 Complications

- Vertigo
- Nausea

43.6 Pearls and Pitfalls

- The maneuver can be uncomfortable to the patient because it can cause vertigo and nausea.

Selected Reading

Brandt T, Steddin S, Daroff RB. Therapy for benign paroxysmal positioning vertigo, revisited. Neurology. 1994;44:796–800.

Buckingham RA. Anatomical and theoretical observations on otolith repositioning for benign paroxysmal positional vertigo. Laryngoscope. 1999;109:717–22.

Fife TD, Iverson DJ, Lempert T, et al. Practice parameter: therapies for benign paroxysmal positional vertigo (evidence-based review): report of the Quality Standards Subcommittee of the American Academy of Neurology. Neurology. 2008;70:69–74.

Halker RB, Barrs DM, Wellik KE, Wingerchuck DM, Demaerschalk BM. Establishing a diagnosis of benign paroxysmal positional vertigo through the Dix-Hallpike and side-lying maneuvers: a critically appraised topic. Neurologist. 2008;14:201–4.

Herdman SJ. Treatment of benign paroxysmal vertigo. Phys Ther. 1990;70:381–8.

Lanska DJ, Remler B. Benign paroxysmal positioning vertigo: classic descriptions, origins of the provocative positioning technique and conceptual developments. Neurology. 1997;48:1167–77.

Li JC, Meyers AD. Benign paroxysmal positional vertigo. http://emedicine.medscape.com/article/884261-overview. Accessed December 20, 2015.

Von Brevern M, Radtke A, Lezius F, et al. Epidemiology of benign paroxysmal positional vertigo: a population based study. J Neurol Neurosurg Psychiatry. 2007;78:710–5.

Epley Maneuver for Vertigo (Particle Repositioning or Canalith Repositioning Procedure)

44

Rui Domingues and Muhammad Waseem

During the Dix-Hallpike test (see Chap. 43), the particles move in the canal and trigger a burst of upbeat-torsional nystagmus. The Epley maneuver causes resolution of positional nystagmus. This maneuver is effective in about 80 % of patients with benign paroxysmal positional vertigo (BPPV).

44.1 Indications

- Performed to alleviate the symptoms of posterior canal BPPV

44.2 Contraindications

- Back or spine injuries or other problems
- Presence of detached retina

44.3 Materials

- Pillow or pad
- Padded table or bed

44.4 Procedure (Fig. 44.1)

1. The patient is positioned on the bed with the head slightly extended and turned 45° to the affected side; hold this position for 60 s.
   - The patient may hold the physician's arm for support.
2. The patient is then assisted by the physician to a supine position, with the head in extension, with a pillow or pad placed at the shoulder level allowing for extension; this position is held for a 60 s. This position will likely provoke transient dizziness and vertigo.
3. The head is then turned 90° to the opposite side; this position is held for 60 s. This position will likely provoke transient dizziness and vertigo.
4. The head is then turned through a further 90° while the patient rolls onto the unaffected side; this position is held for 60 s.
5. The patient then sits up slowly, by rolling up from lying on the unaffected side; this position is held for 60 s.
6. The patient should wait for 10–15 min before discharge.
7. Discharge instructions are then provided. Home instructions:
   - Instruct the patient to sleep in a semi-recumbent position for the next two nights; the patient should sleep at a 45° angle, which is most easily done by sleeping in a recliner or with several pillows arranged on a couch.
   - Sleep on the nonaffected side.
   - During the day, try to keep the head in a vertical position; no sudden head movements to the right, left, up, or down.
   - When men shave under their chins, they should bend their bodies forward in order to keep their heads vertical.
   - Do not go to the hairdresser or dentist because these require head movements.
   - Care should be taken when putting in eye drops because it requires head extension.
   - No vacuuming or mopping the floor.
   - Try not to wear clothing that needs to be pulled over the head. Try to avoid bending down to tie shoes.

R. Domingues, MD • M. Waseem, MD (✉)
Department of Emergency Medicine, Lincoln Medical and Mental Health Center, New York, NY, USA
e-mail: rbdomingues@hotmail.com; waseemm2001@hotmail.com

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_44



Fig. 44.1 (**a**) Patient seated on the table. (**b**) Patient in supine position, with the head turned 45° to the affected side. (**c**) Head then turned to the unaffected side (45°). (**d**) Head turned additional 90° on the unaffected side. *D* direction of view of labyrinth

44.5 Complications

When performing the previous maneuver, caution is advised should neurological symptoms occur. Occasionally such symptoms are caused by compression of the vertebral arteries; if it persists for a long period of time, a stroke can occur.

44.6 Pearls and Pitfalls

- Pearls
  - This maneuver should initially be performed by a trained therapist or medical physician.
  - It is best to perform the Epley maneuver before going to bed at night.
- Pitfalls
  - The patient should not drive herself or himself home after the procedure.
  - Avoid rapid changes in head position that might provoke BPPV.

Selected Reading

Harvey SA, Hain TC, Adamiec LC. Modified liberator maneuver: effective treatment for benign paroxysmal positional vertigo. Laryngoscope. 1994;104:1206–12.

Herdman SJ. Treatment of benign paroxysmal vertigo. Phys Ther. 1990;70:381–8.

Massoud EA, Ireland DJ. Post-treatment instructions in the nonsurgical management of benign paroxysmal positional vertigo. J Otolaryngol. 1996;25:121–5.

Parnes LS, Price-Jones RG. Particle repositioning maneuver for benign paroxysmal positional vertigo. Ann Otol Rhinol Laryngol. 1993;102:325–31.

Radtke A, Neuhausen H, von Brevern M, Lempert T. A modified Epley's procedure for self-treatment of benign paroxysmal positional vertigo. Neurology. 1999;53:1358–60.

Smouha EE. Time course of recovery after Epley maneuvers for benign paroxysmal positional vertigo. Laryngoscope. 1997;107:187–91.

Welling DB, Barnes DE. Particle repositioning maneuver for benign paroxysmal positional vertigo. Laryngoscope. 1994;104:946–9.

Clinical Brain Death Examination in Adults

45

Eric S. Papierniak, Hassan M. Alnuaimat, Tracy Timmons,
and Deborah M. Stein

45.1 Indications

- Deep coma without any identifiable reversible causes
- Suspected brain death in a mechanically ventilated patient

45.2 Contraindications

- Metabolic derangements
- Acid-base disorders
- Electrolyte abnormalities sufficient to cause the coma
- Profound hypotension
- Hypothermia (core body temperature <36°C)
- Drug overdose or toxic exposure
- Locked-in syndrome

45.3 Materials and Medications

- A bright light
- Intravenous (IV) catheter
- 30-mL syringe
- 50-mL of ice water
- Endotracheal suction catheter
- Long swab or tongue depressor
- Gauze 4 × 4 or saline eye drops

45.4 Procedure

1. Evaluate the motor response to pain.
    - Apply pressure to the supraorbital nerve and nail beds. No motor response is consistent with brain death (Figs. 45.1 and 45.2).
2. Test for the absence of brainstem function.
    - Check pupillary response to bright light.
    - Check the oculocephalic reflex. With the eyelids held open, quickly turn the head to the side. The normal response is for the eyes to move in the opposite direction, maintaining the focus forward. Failure of the eyes to deviate during head rotation is consistent with brain death (Fig. 45.3).
    - Check the oculovestibular reflex with cold caloric testing. Elevate the head of the bed to 30°. Attach an IV catheter to the tip of a 30-mL syringe. Inject 50 mL of cold water into the external ear canal. Observe the pupils for 1 min for deviation toward the ear with the cold stimulus. Wait 5 min before testing the other side. No deviation of the pupils is consistent with brain death (Figs. 45.4 and 45.5).
    - Check for bulbar paralysis.
        - Check for a cough response to bronchial suctioning.

E.S. Papierniak (✉)
Division of Pulmonary, Critical Care, and Sleep Medicine, Department of Medicine, University of Florida Health, Gainesville, FL, USA

Malcom Randall VA Medical Center, Gainesville, FL, USA
e-mail: eric.papierniak@medicine.ufl.edu

H.M. Alnuaimat, MD
Department of Medicine, University of Florida, University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: Hassan.Alnuaimat@medicine.ufl.edu

T. Timmons, MD
Department of Trauma/Surgical Critical Care, R Adams Cowley Shock Trauma Center, University of Maryland Medical Center, Baltimore, MD, USA
e-mail: ttimmons1@umm.edu

D.M. Stein, MD, MPH
Department of Surgery, University of Maryland School of Medicine, R Adams Cowley Shock Trauma Center, University of Maryland Medical Center, Baltimore, MD, USA
e-mail: dstein@umm.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_45

  - Stimulate the posterior pharynx with a long swab or tongue depressor and observe for a gag.
  - Check the corneal reflex by lightly touching the cornea with a cotton swab, corner of gauze, or drops of sterile saline and observe for blinking of the eyelids (Fig. 45.6).

3. Check for respiratory effort by performing an apnea test. Before starting the apnea test, the following conditions must be met:
   (a) The patient must not be hypothermic. The core temperature must be greater than 36°C.
   (b) The patient must be hemodynamically stable with a systolic blood pressure greater than 90 mmHg.
   (c) The arterial blood gas (ABG) must demonstrate a normal arterial partial pressure of carbon dioxide ($PaCO_2$). The arterial partial pressure of oxygen (PaO_2) may be elevated with preoxygenation to minimize the risk of hypoxemia prematurely ending the examination.
   - Monitor the patient with a pulse oximeter.
   - Disconnect the ventilator and deliver oxygen at 6 L/min by cannula into the endotracheal tube.
   - Alternately the patient can remain connected to the ventilator with no applied support, which allows for an in-line negative pressure monitor to be attached to the circuit. Note: Most ventilators are too sensitive to be used as the sole method of sensing respiratory effort as they can produce false-negative results.
   - Watch the chest and abdomen for respiratory motion, or monitor for negative inspiratory force on the pressure gauge. Check an ABG every 10 min and when the test ends.
   - If the $PaCO_2$ increases by 20 mmHg or the $PaCO_2$ is greater than 60 mmHg and there was no respiratory effort, the test is consistent with brain death.
   - The test must be aborted and the patient reconnected to mechanical ventilation if the patient becomes hypotensive, desaturates, or develops cardiac arrhythmias.
   - If there is respiratory effort, the patient must be reconnected to mechanical ventilation (Figs. 45.7 and 45.8).



Fig. 45.1 Motor response to pain 1. Temporomandibular joint and supraorbital ridge test supraorbital nerve function



Fig. 45.2 Motor response to pain 2: Firm pressure can be applied to the nail beds with a penlight or similar instrument

a Normal reaction: Eyes move side to side when head is turned



b Abnormal reaction: Eyes remain in fixed position in skull when head is turned



Fig. 45.3 (**a**, **b**) Oculocephalic reflex or "Doll's eyes." Movement of the eyes away from the direction of head turning (i.e., to keep the gaze forward) indicates intact functioning



Fig. 45.4 Preparation of cold saline for testing of the oculovestibular reflex or "cold calorics"



a Normal caloric: Eyes deviate to side of ice water application

b Abnormal caloric: eyes do not deviate

Fig. 45.5 (**a**, **b**) Oculovestibular reflex. Intact functioning is demonstrated by deviation of the gaze toward the side being tested



Fig. 45.6 Use of a cotton ball or unwound tip of a cotton swab for testing of the corneal reflex. A piece of sterile gauze (“4×4”) is also commonly used


P PEAK
P MEAN 6.1
PEEP 1.0
I:E 13:1
f TOT 18
V TE 0.0
V E TOT 0.00
23:40 30 Apr 2011
SPONT
PC
PS
V-TRIG
60 kg
P 12
T 1.00
P 0
V 3.0
O2 40 %
60 %
E 15 %
PEEP 5.0
Alarm Silence in Progress

Fig. 45.8 Ventilator waveform in a patient without spontaneous respirations during the apnea test


A
P PEAK 22
P MEAN 11
PEEP 4.7
I:E 1:1.5
f TOT 16
V TE 435
V E TOT 9.09
Circuit Type Adult
Humidification Type HME
06:52 01 May 2011
PLOT SETUP
FREEZE
A/C
VC+
V-TRIG
70 kg
f 10 1/min
V T 550 mL
T I 1.20
V SENS 3.0 L/min
O2 70 %
50 %
PEEP 5.0 cm H2O

Fig. 45.7 Ventilator waveform before apnea test

45.5 Pearls and Pitfalls

- Pearls
  - The clinical examination should be performed by someone with experience or training in brain death examinations. Local regulations as well as hospital policies should be reviewed in order to determine the requirements for brain death. Some locales require a repeat examination by a different practitioner.
  - A patient with a cervical spine injury causing quadriplegia may not feel nail bed pressure and may be unable to respond to pain with more than facial movements.
- Pitfalls
  - Pupillary constriction less than 3 mm is not consistent with brain death.
  - Do not test oculocephalic reflex (doll's eyes) on patients who may have a cervical spinal cord injury from trauma.
  - Do not test the oculovestibular reflex with cold caloric testing in patients with a ruptured tympanic membrane.
  - A large number of patients may demonstrate spinal reflex movements during brain death. These reflexes may be triggered by touch, noxious stimuli, or removal of the ventilator. These movements can include plantar flexion, upper extremity posturing, eye opening, and the "Lazarus sign" (the arms raise off the bed and cross). Although these movements can be disconcerting to the health care team and family, they do not preclude a diagnosis of brain death.

45.6 Controversies

- Repeat examinations
  - The American Academy of Neurology guidelines recommend repeating the brain death examination at 6 h. The guidelines acknowledge that this is an arbitrary interval. Recent evidence suggests that the second examination may be unnecessary.
- Confirmatory Testing
  - Confirmatory testing is an option if specific elements of the clinical examination cannot be performed. For example, a trauma patient with suspected cervical spinal cord injuries precluding the oculocephalic reflex test would be a candidate for confirmatory testing.
  - Conventional cerebral angiography will demonstrate no filling beyond the carotid bifurcation or within the circle of Willis. Electroencephalography demonstrates no electrical activity. Transcranial Doppler ultrasonography will demonstrate vascular resistance associated with elevated intracranial pressure. Technetium-99m hexamethylpropylene-amine oxime brain scans demonstrate the "hollow skull" sign or no uptake of isotope in the brain (Fig. 45.9).
  - Newer modalities of confirmatory testing include computed tomography (CT) angiography and magnetic resonance imaging/magnetic resonance angiography (MRI/MRA). These tests are being used in some hospitals; however, the recent review by the American Academy of Neurology finds evidence insufficient to recommend using these newer modalities to confirm brain death.



Fig. 45.9 "Empty skull sign" on nuclear medicine flow study confirms brain death

Selected Reading

A definition of irreversible coma: report of the Ad Hoc Committee of the Harvard Medical School to Examine the Definition of Brain Death. JAMA. 1968;205:337–40.

Lustbader D, O'Hara D, Wijdicks EF, et al. Second brain death examination may negatively affect organ donation. Neurology. 2011;76:119–24.

Practice parameters for determining brain death in adults (summary statement). The quality standards subcommittee of the American Academy of Neurology. Neurology. 1995;45:1012–4.

Saposnik G, Maurino J, Saizar R, Bueri JA. Spontaneous and reflex movements in 107 patients with brain death. Am J Med. 2005;118:311–4.

Wijdicks EF. Current concepts: the diagnosis of brain death. N Engl J Med. 2001;344:1215–21.

Wijdicks EF, Varelas PN, Gronseth GS, Greer DM, American Academy of Neurology. Evidence-based guideline update: determining brain death in adults: report of the Quality Standards Subcommittee of the American Academy of Neurology. Neurology. 2010;74:1911–8.

Part VII

Ophthalmic Procedures

Slit Lamp Examination

46

Bobby K. Desai

46.1 Indications

- A slit lamp magnifies structures of the eye (Fig. 46.1).
- Gives the operator a three-dimensional view of the area visualized.
- Used to delineate abnormalities that cannot be visualized by other means.
- Helpful in foreign body removal.

B.K. Desai, MD
Department of Emergency Medicine, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: bdesai@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_46


Magnification
Slit height and intensity
Slit centration or offset
Elevation & joystick for right and left movement and to focus
Slit width and/ or height

Fig. 46.1 A basic slit lamp

46.2 Contraindications

- Not to be used in patients who cannot tolerate an upright posture (e.g., trauma patients).
  - In these cases if a slit lamp examination is required, a portable slit lamp may be beneficial (Fig. 46.2).



Fig. 46.2 A portable slit lamp

46.3 Materials

- The slit lamp is an eye-specific binocular stereoscope specifically designed to examine the eye and its structures and gives the practitioner a three-dimensional assessment of the eye.
- The operator has full movement of the microscope in all directions and the apparatus can be locked in place if required.
- Its light source can be manipulated to change the characteristics of the beam from its intensity to the angle at which it projects (Fig. 46.3).
  - A low-power setting is typically used for normal examination.
  - A higher-intensity beam is used when evaluating the anterior chamber with a narrow slit beam.
- It has colored filters typically built within the slit lamp.
  - Cobalt blue: Used with fluorescein dye to evaluate for corneal abrasions (Fig. 46.4) and avulsions; the dye will collect where the corneal epithelium is absent. It results in a yellow glow or hue visible through the microscope.
  - Green filter: Used to increase contrast of blood vessels. They appear black and the filter is useful for the assessment of hemorrhage.
- The operator is able to adjust the magnification of the microscopic typically through dial controls.
  - Low magnifications are most helpful for general examination.
  - Higher magnifications are used for examination of a particular area in fine detail.



Fig. 46.3 The slit lamp beam and the reflection of the beam



Fig. 46.4 Example of a corneal abrasion seen with a cobalt blue filter (With kind permission from Springer Science+Business Media: Das S, Chohan A, Snibson GR, Taylor HR. Capsicum spray injury of the eye. *International Ophthalmology*. 2005;26(4–5):171–3)

46.4 Procedure

1. As part of a complete eye examination, informed consent is not generally required.
2. An explanation of the procedure and reassurance are helpful.
3. Lock the slit lamp before positioning the patient because unintended movement may inadvertently damage the equipment or cause injury to the operator or patient.
4. The apparatus has a chin and a head rest. Ask the patient to place the chin and forehead in the respective areas (Fig. 46.5).
5. Adjust the height of the apparatus and the patient's chair for optimum comfort (Figs. 46.6 and 46.7). It may be necessary for children to stand during the examination.
6. The patient may place his or her hands on the sides of the table that the lamp is mounted on; this ensures stability of both the lamp and the patient.
7. Adjust the eyepieces of the microscope to fit the operator.
8. Turn on the slit lamp at its lowest setting to avoid a sudden power surge that could potentially damage the bulb.
9. Move the stage forward and narrow the beam and angle it at 45° to the patient. Aim the beam laterally so as not to cause the patient discomfort.
10. Focus the beam by manipulating the joystick to move the apparatus forward and backward so that the beam is clearly visible and its lines are sharp.
11. For each area of the eye to be examined, inspect the area thoroughly using the joystick to slowly manipulate the slit lamp across the eye in all directions, using the height adjustment of the joystick to slightly raise and lower the slit lamp as needed.
    - The operator may find that the slit lamp may move too freely; in that case she or he may find slightly tightening the locking nut of the C-arm may provide better and more precise control.



Fig. 46.5 Appropriate positioning for a slit lamp examination



Fig. 46.6 The slit lamp is too high



Fig. 46.7 The slit lamp is too low

46.5 Complications

There are no complications following routine slit lamp examination.

46.6 Pitfalls

- Ensure a working bulb.
- Appropriately set the microscope's oculars for the operator's pupillary distance.
- Ensure all dials and knobs are firmly set.
- Inadequate focusing
- Patient noncompliance

46.7 Fluorescein Testing

46.7.1 Indications and Uses

- Examination of the cornea under a cobalt blue filter on a slit lamp or Wood's lamp: The chemical fluoresces under blue light and appears green under these circumstances.
- Useful for detecting corneal abrasions, corneal foreign bodies, and infections of the eye.

46.7.2 Procedure

- Fluorescein is typically used after installation of a topical anesthetic, which provides patient comfort especially for those with significant pathology.
- The fluorescein strip comes packaged in single-use wrappers (Fig. 46.8).
- Hold the strip by the white end and wet the orange end *lightly* because heavily moistening the strip may cause a significant amount of dye to be present, obscuring the examination.
  - A dry strip may be used, but it may irritate the patient's eye especially if already sensitive.
- If this occurs, the clinician may use tissue paper to gently blot the excess solution away.
  - The exception to this is the performance of the *Seidel test*, which is used to assess the eye for potential perforation (Fig. 46.9).
  - The clinician will instill a large amount of dye into the eye by wetting the orange strip copiously.
  - The clinician will next examine the eye for a stream of fluid leaking from the ruptured globe.
  - This stream will fluoresce green or blue in distinction to the rest of the globe, which appears orange.
- The choice of solution to wet fluorescein strip is up to the clinician because saline, tap water, or the recently used anesthetic solution may be used safely.
- Place the now-wet orange end on the lower lid of the patient's eye.
- Ask the patient to blink several times to allow the solution to spread evenly.
- The clinician may use a Wood's lamp, penlight, or the cobalt blue filter on the slit lamp to examine the now-stained eye.
  - The slit lamp is preferable owing to the potential for missing small abrasions.


Contents may not be sterile if this package has been damaged or previously opened. See box for complete information.
Manufactured for Akorn, Inc., Lake Forest, IL 60045
FGBLP Rev. 11/10
MSN 015-083
Slowly
NDC 17478-404-01
ONE STERILE STRIP
FUL-GLO® Fluorescein Sodium Sterile Ophthalmic Strips 1.0 mg
To Open, Pull Tab Apart Slowly
Contents may not be sterile if this package has been damaged or

Fig. 46.8 A typical fluorescein strip package



Fig. 46.9 A positive Seidel test (Reproduced with permission from: Lingam V, Panday M, George R, Shantha B. Management of complications in glaucoma surgery. *Indian J Ophthalmol*. 2011;59(Suppl1): S131–40)

46.7.3 Complications

- There is a theoretical risk of the development of superficial punctate keratitis from instillation of topical anesthetic before fluorescein testing.
- Discoloration of soft contact lenses.
- Potential for infection using premixed fluorescein solution.

46.7.4 Pitfalls

- Contact lens wearers should remove their lenses because the fluorescein will permanently stain the lens.
  - The wearer should not put the contacts back in for several hours.

Selected Reading

DuBois L. The slit lamp examination. In: DuBois L, Ledford JK, Daniels K, Campbell R, editors. Clinical skills for the ophthalmic examination: basic procedures. 2nd ed. Thorofare: Slack; 2006. p. 61–70.

Galor A, Jeng BH. Red eye for the internist: when to treat, when to refer. Cleve Clin J Med. 2008;75:137–44.

Lang GK. Ophthalmology: a short textbook. Stuttgart: Thieme; 2000.

Ledford JK, Sanders VN. The slit lamp primer. 2nd ed. Thorofare: Slack; 2006.

Eye Irrigation

47

Bobby K. Desai

47.1 Indications

- Chemical burns to the eye
- Removal of superficial foreign bodies

47.2 Contraindications

- For suspected globe perforation, extreme care must be taken to not exacerbate the injury.

47.3 Materials and Medications

- Irrigating device—the Morgan lens (Fig. 47.1)
- Saline solution or lactated Ringer's (preferably warmed)
- Topical anesthetic drops (Fig. 47.2)
- Basin to secure the extruded solution
- Intravenous (IV) tubing to attach the IV bag to the Morgan lens
- pH paper (Fig. 47.3)

B.K. Desai, MD
Department of Emergency Medicine, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: bdesai@ufl.edu

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_47



Fig. 47.1 The Morgan lens and packaging

Fig. 47.2 Examples of topical anesthetics



Fig. 47.3 (**a**, **b**) Examples of pH paper

47.4 Procedure

1. Informed consent is generally not required, although a thorough explanation to the patient is warranted.
2. Obtain pH of the eye *before* instilling anesthetic drops.
3. Anesthetize the eye(s) with topical anesthetic of choice by instilling drops within the lower lid and then asking the patient to blink several times in order to evenly distribute the solution.
4. Ensure there are no foreign bodies on the inside of the upper lids by inverting the upper lid.
   - Particulate foreign bodies may be removed with moistened cotton tip applicators.
5. After adequate anesthesia is ensured, place one end of the Morgan lens within the fornix of the upper lid (Fig. 47.4).
6. Next, gently retracting the lower lid will ensure smooth placement of the remaining portion of the Morgan lens (Fig. 47.5).
7. Using the end of the Morgan lens, screw in the prepared IV tubing (Fig. 47.6).
8. Attach the end of the IV tubing to the saline bag and place at height to allow for gravity to ensure a smooth flow of solution.
   - Continue to irrigate the eye until desired pH is obtained.
9. To remove the Morgan lens, use the opposite technique for insertion.



Fig. 47.4 Inserting the Morgan lens under the upper lid



Fig. 47.5 Inserting the Morgan lens under lower lid



Fig. 47.6 The Morgan lens in place, ready to be attached to IV tubing for saline irrigation

47.5 Complications

- Corneal abrasions may be caused by the Morgan lens and are treated in the usual fashion.
- Deep corneal injury may occur with inadequate irrigation.

47.6 Pearls and Pitfalls

- Note that alkali burns will require significant irrigation and more topical anesthesia may be required.
- Ophthalmological consultation may be required, especially for alkaline and hydrofluoric acid burns.

Selected Reading

Lang GK. Ophthalmology: a short textbook. Stuttgart: Thieme; 2000.
Rhee DJ, Pyfer MF, Rhee DM, editors. The Wills Eye manual: office and emergency room diagnosis and treatment of eye disease. 3rd ed. Philadelphia: Lippincott Williams & Wilkins; 1999.

Corneal Foreign Body Removal

48

Bobby K. Desai

48.1 Indications

- Presence of a corneal foreign body (Fig. 48.1)



Fig. 48.1 Corneal foreign body (With kind permission from Springer Science+Business Media: Zuberbuhler B, Tuft S, Gartry D, Spokes D. Ocular Surface and Reconstructive Surgery. In: *Corneal Surgery*. 2013. 29–48)

48.2 Contraindications

- An uncooperative patient may require ophthalmological consultation as well as sedation.
- Suspected foreign bodies from high-velocity injuries must be referred to an ophthalmologist subsequent to initial evaluation.
- Any signs of globe penetration (e.g., hyphema) require emergent ophthalmological consultation.
- Overt globe rupture.
- Evidence of an inflammatory process such as iritis requires emergent ophthalmological consultation.
- Foreign bodies associated with corneal burns secondary to chemical exposure such as alkaline corneal burns will require emergent ophthalmological consultation.

B.K. Desai, MD
Department of Emergency Medicine, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: bdesai@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_48

48.3 Materials and Medications

- Eye chart for visual assessment
- Cotton tip applicator
- Slit lamp or other source of magnification
- 27-Gauge needle or ophthalmic foreign body needle (Fig. 48.2)
- Topical ophthalmic anesthetic
- Ophthalmic burr (Fig. 48.3)



Fig. 48.2 Foreign body needle



Fig. 48.3 Ophthalmic burr drill

48.4 Procedure

1. Informed consent may be required.
2. Visual acuity and a formal assessment of the eye should be done and documented.
3. Consider intraocular foreign body.
    - Computed tomography (CT) scan may be used to assess for the presence of an intraocular foreign body.
4. Eversion of the upper lid should be performed to evaluate for retained foreign body under the lid.
    - These usually can be removed by:
        – A moistened cotton tip applicator
        – Irrigation
5. Magnification is preferable, but some foreign bodies may be large enough to see with the naked eye.
6. Anesthetize the eye with topical anesthetic.
7. For multiple loose foreign bodies, removal may be attempted with irrigation after appropriate anesthesia.
8. Removal of the foreign body may be attempted with a moistened cotton swab.
    - Metallic foreign bodies recently embedded within the cornea may be difficult to remove in this fashion.
    - However, during the healing process, some metallic foreign bodies may be pushed closer to the surface during reepithelialization of the cornea. These potentially can be removed with this technique.
        – Care must be taken to avoid leaving a rust ring that could permanently stain the cornea.
9. A 27-gauge needle bent at a 90° angle may be used to remove foreign bodies by gently prying it out.
    - An advantage of using a needle is that any rust ring as well as any metallic foreign body can potentially be removed.
10. Technique: A slit lamp may be used to magnify the area.
    - See slit lamp chapter (Chap. 46) for details.
    - The patient should be informed about the procedure; formal informed consent may not be required.
    - Proper positioning is critical for success.
    - The patient's head should be fully forward and firmly placed against the head rest.
    - The patient's hands may be placed on the sides of the slit lamp stage for stabilization.
    - Apply topical anesthesia to the cornea.
11. Using the patient's cheek as a bolster potentially avoids significant movement of the needle if the patient unexpectedly moves.
    - Other modalities for stabilization include supporting the elbow by placing on a box or using towels.
12. Have the patient gaze at one point in the far distance.
    - Using the needle or burr as a scoop, gently manipulate the foreign body out.
        – Using a burr can allow for the total removal of any rust ring.
13. Once the foreign body is removed, patching is not required.
14. Consider application of topical antibiotics.
15. Tetanus prophylaxis should be given as for open other wounds.
16. Arrange follow-up with a primary care physician or preferably an ophthalmologist.

48.5 Complications

- Forceful attempts to dislodge a foreign body may result in corneal perforation.
- Incomplete removal of a foreign body.

Selected Reading

Lang GK. Ophthalmology: a short textbook. Stuttgart: Thieme; 2000.

Rhee DJ, Pyfer MF, Rhee DM, editors. The Wills eye manual: office and emergency room diagnosis and treatment of eye disease. 3rd ed. Philadelphia: Lippincott Williams & Wilkins; 1999.

Thomas SH, White BA. Foreign bodies. In: Marx J, Hockberger R, Walls R, editors. Rosen's emergency medicine: concepts and clinical practice. 7th ed. Philadelphia: Mosby; 2010. p. 715–32.

Ultrasound Evaluation of Retinal Detachment

49

Shalu S. Patel, L. Connor Nickels, and Rohit Pravin Patel

49.1 Indications

- To aid in the evaluation of vision loss or change in vision

49.2 Contraindications

- Relative: Suspicion of increased intraocular pressure
- Relative: Suspicion of globe rupture (see Chap. 50)

49.3 Materials and Medications

- Bedside ultrasound machine with high-frequency (7.5- to 10-MHz) linear transducer
- Transparent adhesive such as Tegaderm (optional)
- Sterile ultrasound gel
- Sterile gauze

49.4 Procedure

1. Position the patient supine with his or her eyes closed. The eyelid may be taped closed with a transparent adhesive if desired (Fig. 49.1).
2. Place a liberal amount of ultrasound gel over the eyelid.
3. Place the ultrasound probe over the eye in a transverse position.
4. Adjust the depth of the ultrasound so that the whole eye fills the screen.
5. Scan through the eye fully in the transverse and sagittal planes.
6. When viewing the ultrasound image, the normal eye is a circular hypoechoic structure (Fig. 49.2). The structures should be evaluated from anterior to posterior.
7. Identify the cornea. This is the first thin hypoechoic line in the anterior eye.
8. Continuing posteriorly, identify the anterior chamber, which is an anechoic area bordered by the cornea, iris, and lens. The iris is an echogenic linear structure, and the normal lens is anechoic.
9. Identify the vitreous chamber, the large anechoic region posterior to the lens.
10. Carefully evaluate the posterior globe. The normal retina cannot be distinguished from the other choroidal layers on ultrasound.
11. A detached retina will appear as a hyperechoic linear floating membrane in the posterior vitreous chamber (Fig. 49.3).
12. In the retrobulbar region, the optic nerve can be identified as a hypoechoic linear structure perpendicular to the globe (Fig. 49.3).

S.S. Patel, MD
Department of Emergency Medicine, Florida Hospital Tampa,
Florida Hospital Carrollwood, Tampa, FL, USA
e-mail: shalu314@gmail.com

L.C. Nickels, MD, RDMS (✉) • R.P. Patel, MD
Department of Emergency Medicine, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: cnickels@ufl.edu; rohitpatel@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_49



Fig. 49.1 Probe positioning with Tegaderm applied to orbit: (**a**) sagittal view, (**b**) axial view


a
b
2012Oct17 14:35
Sup
L25
MB
MI
0.7
TIS
0.2
181
Cine
Cornea
Ciliary body
Lens
Vitreous
Extraocular muscle
Orbital fat
Anterior chamber
Posterior wall
Optic Nerve Sheath

Fig. 49.2 Ocular ultrasound with normal anatomy findings ((**a**) without labels, (**b**) with anatomy labeled)


Vas
HFL
MI
0.7
TIS
0.1
247
A
B
4.0
A 0.34cm
B 0.26cm

Fig. 49.3 Retinal detachment appears as a hyperechoic linear structure (*white arrow*). *White* bracket shows the optic nerve sheath shadow (see Chap. 50 for more information)

49.5 Complications

- Conjunctival infection
- Increased intraocular pressure (if too much pressure is applied)

49.6 Pearls and Pitfalls

- Pearls
  - Use a transparent adhesive such as Tegaderm to decrease the risk of conjunctival infection.
  - Use a liberal amount of gel to obtain the best images.
  - Use minimal pressure to obtain the best images.
  - False positives on ocular ultrasound may occur with disk edema or vitreous hemorrhage.
- Pitfalls
  - Subacute retinal detachments may be missed on ocular ultrasound.

Selected Reading

Blaivas M. Bedside emergency department ultrasonography in the evaluation of ocular pathology. Acad Emerg Med. 2000;7:947–50.

Blaivas M, Theodoro D, Sierzenski PR. Elevated intracranial pressure detected by bedside emergency ultrasonography of the optic nerve sheath. Acad Emerg Med. 2003;4:376–81.

Shinar Z, Chan L, Orlinksy M. Use of ocular ultrasound for the evaluation of retinal detachment. J Emerg Med. 2011;4:53–7.

Whitcomb MB. How to diagnose ocular abnormalities with ultrasound. AAEP Proc. 2002;48:272–5.

Ultrasonography in the Evaluation of Intraocular Pathology

50

Benjamin M. Mahon, Marie-Carmelle Elie,
L. Connor Nickels, and Rohit Pravin Patel

50.1 Indications

- Eye trauma
- Loss of vision or decreased vision
- Head injury
- Ocular pain
- Suspected foreign body

50.2 Contraindications

- None

50.3 Materials

- Linear probe (7.5–10 MHz)
- Tegaderm or other protective eye covering
- Copious amounts of water-soluble transmission gel

50.4 Procedure

1. Begin by asking the patient to close her or his eye, and then apply the Tegaderm or other suitable eye cover over both eyes.
2. Apply a copious amount of transmission jelly over both eyes.
3. Gently apply the ultrasound probe to the outer eyelid. If the operator has used a sufficient enough amount of jelly, the probe itself should not need to be in actual contact with the eyelid. This becomes of critical importance in suspected globe trauma or intraocular foreign body, when excess manipulation of the intraocular contents could precipitate further damage or worsening of present damage. Ensure the pressure is gentle enough to prevent this, but sufficient to obtain good imaging (see Chap. 49).
4. Image the normal eye first, to become familiar with the patient's anatomy (see Chap. 49), before proceeding to the suspected abnormal eye.
5. Start with low gain.
6. Ask the patient to move the eye slowly from the left to the right. This is called kinetic echography and will provide information elaborated upon later. Have the patient keep her or his eye straight ahead, as the operator phases up and down and side to side, between the transverse and the sagittal planes.
7. Increase gain slowly while the patient is moving the eye. Shifting from low gain to higher gain during the examination will help to prevent overlooking certain disease processes. As a fluid-filled structure, the eye provides its own acoustic window, and imaging is generally easy.

50.5 Complications

- Through excessive pressure applied to the eye, as described previously, further disruption of the intraocular contents and worsening of preexisting injury can occur.

50.6 Pearls and Pitfalls

- Pitfalls
  - Applying too much pressure to the globe and disrupting already damaged intraocular contents
  - Failing to image with full spectrum of gain
  - Using an insufficient amount of gel

B.M. Mahon, MD
Ponciana Medical Center, Kissimmee, FL, USA
e-mail: faust2k9@ufl.edu

M.-C. Elie, MD, RDMS (✉) • L.C. Nickels, MD, RDMS
R.P. Patel, MD
Department of Emergency Medicine, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: elie@ufl.edu; cnickels@ufl.edu; rohitpatel@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_50

50.7 Specific Disease Processes/Pathology [1]

50.7.1 Vitreous Hemorrhage (Fig. 50.1)

- Best seen in high gain.
- Clinical: Very common pathology. Seen as “floaters” on the visual field. Can cause blindness if large.
- Ultrasound: Appearance may vary. Early on in the evolution of a hemorrhage, these can be seen as small dots or mobile linear opacities that float freely in the back of the posterior chamber with eye movement. Has been described as a “snow-storm appearance.” As hemorrhage ages, the blood organizes and membranes form, sometimes layering inferiorly owing to gravity.

50.7.2 Vitreous Detachment

- Best seen with higher gain.
- Clinical: Common in older patients. Presents as “flashers.” Vitreous gel loses its attachment from the internal membrane lining.
- Ultrasound: Seen as “swaying seaweed.” There are layering opacifications. Also seen as “snow-globe appearance.” Concurrent vitreous hemorrhage is also common.
- Note: A small percentage of patients also have a retinal tear, so ophthalmology follow-up is necessary.

50.7.3 Retinal Detachment (Figs. 50.2 and 50.3)

- Best seen with lower gain.
- Clinical: Acute loss of vision, usually painless, often preceded by “flashers” and/or “floaters” as the neurosensory component of the retina pulls away from the retinal pigment epithelium. *An ophthalmological emergency.* Can be caused by ocular trauma or no known precipitant at all.
- Ultrasound: Seen as a taut, hyperechoic, linear opacity that moves with the eye, attached to the optic disc, in the posterior region of the globe.


2012Oct17 14:35
Res
S MB
Sup
L25
97%
MI
0.7
TIS
0.2
181
A
B
Vitreous hemorrhage: mobile, poorly defined, increased echogenicity
3.1
Cine

Fig. 50.1 Vitreous hemorrhage



Fig. 50.2 Retinal detachment ultrasound image


Retinal detachment
Vitreous body
Retina
Cornea
Lens
Iris
Optic nerve

Fig. 50.3 Retinal detachment graphical representation

50.7.4 Intraocular Foreign Body (Fig. 50.4)

- Clinical: Usually a preceding episode of trauma, often from metalworking or landscaping.
- Ultrasound: Foreign bodies are seen as hyperechoic substances in the eye often with distal shadowing. Certain shadow patterns distal to the foreign body, as well as comet tails, can help to differentiate the type of foreign body material.

50.7.5 Globe Rupture (Fig. 50.5)

- Clinical: Usually the result of trauma. Frequently, the mechanism causing the injury has subsequently made the eye examination itself impossible, if edema, blepharospasm, hyphema, or distorted anatomy makes visualization of the posterior chamber too difficult. In these circumstances ultrasound can be immeasurably helpful.
- Ultrasound: Findings include decreased size of the anterior chamber, posterior chamber, or both, often with buckled sclera. Globe rupture should be suspected when the injury mechanism is present and any major distortion of the ocular anatomy is appreciated.


2012Oct17 14:35
Res
S MB
Sup
L25
97%
MI
0.7
TIS
0.2
181
A
B
Foreign bodies show
reverberation artifacts
and shadowing
3.1
Cine

Fig. 50.4 Foreign bodies


2012Oct17 14:35
Res
S MB
Sup
L25
97%
MI
0.7
TIS
0.2
181
A
B
Increased intraocular
pressure leads to
deformed globe
3.1
Cine

Fig. 50.5 Globe rupture

50.7.6 Increased ICP

- Clinical: Increased ICP is encountered in a number of pathological processes, such as closed head injury from trauma, altered mental status, pseudotumor cerebri, space-occupying lesion, or any other process causing intracranial injury. Physical examination may be suggestive of an intracranial process, but often key examination findings such as papilledema are not appreciated, owing to both limitations from the patient and their mental status, as well as limitations in the skill of the ED doctor, or the ability to dilate the eyes sufficiently, to appreciate the finding.
- Ultrasound: The size of the *optic nerve sheath diameter* is an indirect measurement of ICP. It is visualized as a hypoechoic linear strip radiating posteriorly from the edge of the back of the globe. A normal diameter is 5.0 mm or less. This measurement is taken at 3 mm back from the posterior edge of the globe (Fig. 50.6). Take measurements bilaterally to compare. Two or more measurements should be taken and then averaged on each side.
- A diameter greater than 5.0 mm, at 3.0 mm distal from the posterior globe border, is strongly suggestive of increased ICP and warrants further evaluation and imaging [2].



Fig. 50.6 Optic nerve sheath measurement

References

1. Blaivas M, Theodoro D, Sierzenski P. A study of bedside ocular ultrasonography in the emergency department. Acad Emerg Med. 2002;9:791–9.
2. Blaivas M, Theodoro D, Sierzenski P. Elevated intracranial pressure detected by bedside emergency ultrasonography of the optic nerve sheath. Acad Emerg Med. 2003;10:376–81.

Selected Reading

Mustafa M, Montgomery J, Atta H. A novel educational tool for teaching ocular ultrasound. Clin Ophthalmol. 2011;5:857–60.

Qureshi MA, Laghari K. Role of B-scan ultrasonography in preoperative cataract patients. Int J Health Sci (Qassim). 2010;4:31–7.

Shinar Z, Chan IL, Orlinsky M. Use of ocular ultrasound for the evaluation of retinal detachment. J Emerg Med. 2011;40:53–7.

Vodapalli H, Murthy SI, Jalali S, Ali MJ, Rani PK. Comparison of immersion ultrasonography, ultrasound biomicroscopy and anterior segment optical coherence tomography in the evaluation of traumatic phacoceles. Indian J Ophthalmol. 2012;60:63–5.

Whitcomb MB. How to diagnose ocular abnormalities with ultrasound. AAEP Proc. 2002;48:272–5.

Yoonessi R, Hussain A, Jang TB. Bedside ocular ultrasound for the detection of retinal detachment in the emergency department. Acad Emerg Med. 2010;17:913–7.

Tonometry

51

Bobby K. Desai

51.1 Indications

- To measure intraocular pressure (IOP)

51.2 Contraindications

- A relative contraindication is the presence of an active or indolent infection about the cornea or conjunctiva, unless a one-time-use device is used (e.g., a Tono-Pen XL).
- Recent trauma to the eye.
- Uncooperative patients because improper technique may cause damage to the eye.

51.3 Overview

- Tonometry is the measurement of IOP obtained by evaluating the resistance of the eye to indentation by a force applied to it.
- Can be obtained by several methods.
- Two methods are routinely used in an emergency department setting:
  - *Impression tonometry*: measures the indentation made by a plunger carrying a known amount of weight.
  - More weight can be added to the apparatus.
  - The more weight needed to indent the cornea results in a higher IOP reading.
    - The Schiøtz tonometer is the most commonly used apparatus to utilize this method (Fig. 51.1).
- *Electronic indentation tonometry*: does not exert pressure on the eye (Fig. 51.2).

B.K. Desai, MD
Department of Emergency Medicine, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: bdesai@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_51


0
5
10
15
20
Jewel mounted plunger
Weight disc (5.5 g)
Cylinder collar
Cylinder
Foot plate
Plunger

Fig. 51.1 Schiøtz tonometer



Fig. 51.2 Tono-Pen

51.4 Schiøtz Tonometry

51.4.1 Procedure: Schiøtz Tonometry (Fig. 51.3)

1. Carefully clean the apparatus between each patient.
    - Rubbing alcohol may be used.
    - Because it is metal, it can be autoclaved.
2. Calibrate the Schiøtz tonometer with the metal test block provided.
    - Test by placing the apparatus directly on the metal block.
    - The needle should be at "0" at the far end of the scale.
        - If not, loosen the screw at the base of the needle to rezero it.
        - Ensure that the needle is completely straight because any bend will produce an erroneous reading.
3. An explanation of the procedure is helpful because patient cooperation is critical for accurate results.
4. Anesthetize the eye with topical ophthalmic anesthetic of choice.
5. The patient should be in a recumbent position.
    - Have the patient focus on an area of the ceiling.
6. Hold the instrument with the aid of the curved arms at the side of the tonometer.
    - The operator can rest her or his hand on the patient's cheek or forehead to maintain stability.
7. Gently rest the tonometer on the patient's eye such that the instrument is centered on the eye and the instrument is completely vertical; no pressure should be exerted on the eye.
8. Note the scale reading.
9. Lift the Schiøtz directly off the cornea to avoid injury.
10. Using the table provided with the Schiøtz, the operator may convert the scale reading into the IOP.
    - The scale is inversely proportional to the actual IOP.
    - If the scale is low (i.e., high IOP), the additional weights provided with the instrument may be used and the patient retested.

51.4.2 Pitfalls

- Ensure the plunger is clean because it can transmit infection.
- False readings may be obtained without proper calibration.
- Placing pressure on the instrument will cause false readings.



Fig. 51.3 Correct use of Schiøtz tonometer

51.5 Tono-Pen Tonometry

51.5.1 Overview

- Electronically measures IOP
  - Combines applanation and indentation tonometry
- Uses pressure-sensitive electronics to average four successive readings and displays the reading and a reliability factor digitally

51.5.2 Calibration of the Tono-Pen

- Should be performed once daily
- Hold the instrument with the tip down (Fig. 51.4).
- Press the black button twice.
  - The letters "CAL" will appear in the display.
- Press the black button again.
  - After a few seconds the word "UP" will appear.
- Rotate the instrument so that the tip points upward.
  - If "GOOD" appears, the Tono-Pen is ready for use.
  - If "BAD" appears, repeat the process until "GOOD" appears.
    - If "GOOD" does not appear, the device cannot be used.



Fig. 51.4 Tono-Pen calibration position

51.5.3 Procedure: Tono-Pen Tonometry

1. An explanation of the procedure is helpful because patient cooperation is critical for accurate results.
2. Anesthetize the eye with the topical ophthalmic anesthetic of choice.
3. Place a probe cover on the unit.
4. The patient should be in a comfortable position because the unit can be used in any position.
   - Have the patient focus on a specific area.
5. The best way to hold the instrument is similar to that of a pen.
   - Ensure that the digital readout is visible.
6. The operator can rest his or her hand on the patient's cheek or forehead to maintain stability.
7. Hold the unit perpendicular to the patient's cornea.
8. Press the black button only once.
   - If "ICALI" is seen, followed immediately by a single row of dashes [– – – –], it indicates that the Tono-Pen requires calibration before it will measure.
   - If "====" is seen and a "beep" is heard, the unit is ready.
   - Proceed with measurement.
9. Gently touch the Tono-Pen to the cornea and withdraw (Fig. 51.5). Repeat several times.
   - Indentation is not required.
10. The unit will "chirp" and a digital reading will be displayed if a valid reading is obtained.
11. After four valid readings are obtained, the average of these measurements as well as a single bar that signifies statistical reliability will appear on the readout.
    - After the final beep if the liquid crystal display (LCD) readout shows "----,“ not enough valid readings were obtained.
    - In this case, the measurement must be repeated.

51.5.4 Pitfalls

- Unsuccessful calibration mandates a repeat attempt at calibration.
- Loosen the Ocu-Film tip cover and repeat for multiple failed attempts.
- Press the reset button and reattempt calibration.
- Replace the battery if necessary.
- If all else fails, use another device or Schiøtz tonometer.

Fig. 51.5 Proper use of Tono-Pen



Correct



Incorrect

51.6 Complications

- Unusual if proper technique is used.
- If too much force is applied, a corneal abrasion may result.
- Infection when using an improperly sterilized Schiøtz tonometer.

Selected Reading

Lang GK. Ophthalmology: a short textbook. Stuttgart: Thieme; 2000.

Rhee DJ, Pyfer MF, Rhee DM, editors. The Wills eye manual: office and emergency room diagnosis and treatment of eye disease. 3rd ed. Philadelphia: Lippincott Williams & Wilkins; 1999.

Lateral Canthotomy

52

Benjamin M. Mahon and Bobby K. Desai

52.1 Indications

- Absolute indications: In the presence of presumed or confirmed retrobulbar hemorrhage
  - Acute visual loss
  - Intraocular pressure (IOP) greater than 40 mmHg (normal IOP is 10–20 mmHg)
  - Proptosis not amenable to retropulsion
- Relative indications: In the context of presumed or confirmed retrobulbar hemorrhage (Fig. 52.1)
  - Ophthalmoplegia
  - Cherry red macula
  - Profound eye pain
  - Afferent pupillary defect (Marcus Gunn pupil)
    - This defect is seen with the *swinging flashlight test.*
      - Shine a light into both eyes; a normal response is equal constriction of both pupils.
      - In those patients with an afferent papillary defect, when light is swung from an unaffected pupil to an affected pupil, the pupil will seem to paradoxically dilate, rather than constrict. The pupil on the nonaffected side will similarly dilate as light is shown into the affected eye. This results from injury to the afferent fibers of cranial nerve (CN) II on the affected side, while the efferent fibers, innervated by CN III, remain intact.
  - This procedure is most effective if performed as soon as possible because irreversible vision loss can occur secondary to ischemia in as little as 90 min.



Fig. 52.1 Retrobulbar hemorrhage

B.M. Mahon, MD
Ponciana Medical Center, Kissimmee, FL, USA

B.K. Desai, MD (✉)
Department of Emergency Medicine, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: bdesai@ufl.edu

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_52

52.2 Contraindications

- Absolute
  - Globe rupture
- Relative
  - Suspected globe rupture: Heralded by a number of signs including hyphema, irregularly shaped pupil, exposed uveal tissue, or profound restriction of extraocular movement

52.3 Materials and Medications

- Straight hemostat
- Suture or iris scissors
- Forceps
- 1–2 % lidocaine with epinephrine
- Sterile gloves
- Sterile towels/drapes
- 4×4 gauze
- Face shield/mask
- Large-bore needle to withdraw anesthetic, 25-gauge needle to infiltrate
- 10-cc syringe
- Normal saline

52.4 Procedure

1. Position the patient
   - While waiting for the procedure to begin, the patient should initially be upright to produce any decrease in IOP that can be provided.
   - At the start of the procedure, lay the patient supine.
   - A cooperative patient is absolutely necessary because even slight movements can cause devastating iatrogenic injury.
   - If the patient is anxious or conscious, sedation may be required.
   - In extreme cases of altered mental status or combative trauma patients, endotracheal intubation and mechanical ventilation may be required.
2. Gently irrigate the affected eye to remove any debris.
3. Inject approximately 1–2 mL of 1–2 % lidocaine with epinephrine into the lateral canthus of the affected eye (Fig. 52.2).
4. Using a curved hemostat, gently crimp the skin over the lateral corner of the patient’s eye down to the orbital rim for 3 min to establish hemostasis and set the boundaries for the incision.
   - Using forceps, use the hemostats to pick up the skin just crushed.
   - Raise the skin with forceps and then use scissors to make a 1- to 2-cm incision from the lateral corner of the eye extending laterally outward (Fig. 52.3).
     - This incision can often sufficiently decrease IOP.
     - It is feasible to remeasure the IOP at this point, and if it is still greater than 40 mmHg, proceed to the next step.
   - Visualize the lateral canthal tendon by retracting the inferior orbital lid inferiorly.
   - Direct the scissors along the lateral side of the orbital rim away from the globe, and cut the lateral canthal tendon inferiorly (Fig. 52.4).
   - At this point, again measure IOP, and if greater than 40 mmHg, proceed to the next step.
   - Direct the scissors along the lateral side of the orbital rim away from the globe, this time directed superiorly, and cut the superior crux of the lateral canthal tendon.


Lateral canthal tendon
Orbicularis oculi muscle

Fig. 52.2 Lateral canthal tendon



Fig. 52.4 Further cut to reduce intraocular pressure



Fig. 52.3 Initial cut

52.5 Complications

- If one is making a superior incision, caution must be taken during this procedure to avoid injury to the lacrimal gland or artery.
- An additional complication of the procedure is ptosis due to iatrogenic injury to the levator aponeurosis, either partially or completely.
- The most obvious complication involves direct injury to the globe itself due to either operator error or poor patient control and immobility.
- Hemorrhage from inadequate hemostasis.
- Infection.

52.6 Pearls and Pitfalls

- Abrupt decrease in pain, decrease in IOP, and resolution of afferent pupillary defect will herald a successful procedure, assuming it was performed within an early enough time frame.
- Having an assistant present is beneficial.
  - In this case, the role of the assistant is to provide lateral retraction of the tissues to decrease likelihood of globe rupture.
- After cantholysis of the inferior component of the lateral canthal tendon, the lower lid will become lax as its attachment to the lateral wall is separated. This signifies a successful incision.
- Incisions made during this procedure generally heal without the need for suturing.
- Emergent ophthalmological consultation should ideally be sought before beginning this procedure.
- Emergent ophthalmological consultation is mandatory subsequent to the procedure.

Selected Reading

Goodall KL, Brahma A, Bates A, Leatherbarrow B. Lateral canthotomy and inferior cantholysis: an effective method of urgent orbital decompression for sight threatening acute retrobulbar haemorrhage. Injury. 1999;30:485–90.

McInnes G, Howes DW. Lateral canthotomy and cantholysis: a simple vision-saving procedure. CJEM. 2002;4:49–52.

Roberts JR, Hedges JR, editors. Clinical procedures in emergency medicine. 5th ed. Philadelphia: WB Saunders; 2009: Chap. 63.

Vassallo S, Hartstein M, Howard D, Stetz J. Traumatic retrobulbar hemorrhage: emergent decompression by lateral canthotomy and cantholysis. J Emerg Med. 2002;22:251–6.

Part VIII

Otorhinolaryngologic Procedures

Epistaxis Control

53

Benjamin M. Mahon and Bobby K. Desai

53.1 Etiology

- Anterior source: approximately 90 % of nosebleeds, usually Kiesselbach's plexus (Fig. 53.1)
  - Nose picking ("epistaxis digitorum")
  - Trauma
  - Infection
  - Nasal foreign body
  - Dry air
  - Atmospheric pressure alterations (e.g., increased altitude, lower arterial partial pressure of oxygen [PaO_2])
  - Allergies
  - Blood dyscrasias
  - Malignancy (e.g., leukemia, lymphoma)
- Posterior source: approximately 10 % of nosebleeds, usually sphenopalatine artery (Fig. 53.2)
  - Iatrogenic coagulopathy (e.g., warfarin, heparin, high-dose aspirin)
  - Blood dyscrasia
  - Liver failure
  - Renal failure
  - Malignancy
  - Older age

B.M. Mahon, MD
Ponciana Medical Center, Kissimmee, FL, USA

B.K. Desai, MD (✉)
Department of Emergency Medicine, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: bdesai@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_53


Anterior ethmoid artery
Posterior ethmoid artery
Sphenopalatine artery
Kiesselbach's plexus
Superior labial artery
Greater palatine artery

Fig. 53.1 Vascular supply to the nasal septum


Posterior ethmoidal
Anterior ethmoidal
Sphenopalatine
Descending palatine
Greater and lesser palatine

Fig. 53.2 Vascular supply of the lateral wall of the nose

53.2 Indications

- Acute/recurrent epistaxis

53.3 Contraindications

- Resolution of epistaxis episode before arrival
- Massive facial trauma

53.4 Materials and Medications

- Headlight with focused beam
- Gown
- Gloves
- Mask with visor
- Full-body drape or sterile towels
- Nasal packing material (any or all of the following, as needed [see later]): several cotton pledgets, 3–5 feet of ½-inch ribbon gauze (preferably enriched with petroleum jelly and bacitracin), anterior epistaxis balloon nasal pack
- Topical vasoconstrictor (e.g., 1 % pseudoephedrine or 1:1000 epinephrine)
- Topical anesthetic (e.g., 4 % lidocaine solution or 2 % tetracaine)
- Nasal speculum
- Bayonet forceps
- Anterior epistaxis balloon (e.g., Rhino Rocket)
- Any of the following commercial products, as needed (see later): Gelfoam, Surgicel, Crosseal, and FloSeal
- Foley catheter

53.5 Procedure: Anterior Epistaxis

- Initial preparation
  1. Assemble necessary equipment at the bedside.
  2. Have the patient seated upright, with head and neck in the sniffing position.
  3. Universal precautions are mandatory: gown, glove, and mask.
  4. Drape the patient with towels or a large body drape.
  5. If initial evaluation using the headlamp and nasal speculum with gentle spreading in a vertical fashion or a simple visual examination reveals the source (anterior vs posterior), proceed with the appropriate management pathway as determined later.
     - If clot obstructs visualization, it is recommended for the patient to gently blow her or his nose once to remove any easily friable clots, and then proceed with immediate inspection. If anterior nose bleeds, go to the next step.
- Management of anterior epistaxis:
  1. Initial step in the management of anterior nosebleeds involves pinching the patient's nostrils firmly for at least 10–15 min.
     - This can be done by the patient.
     - Simple pressure is very often enough to provide appropriate hemostasis in anterior nosebleeds. If it fails, proceed to the next step.
  2. A topical vasoconstrictor of choice (e.g., cocaine, oxymetazoline, 1 % pseudoephedrine) can be applied to the septum and lateral walls of the nose either topically with cotton-tipped applicators or by using soaked pledgets.
  3. Continue to apply firm pressure to the nares for 10–15 min, and recheck the nose for evidence of bleeding.
  4. If the bleeding site can be easily visualized, chemical cautery may be attempted with silver nitrate (Fig. 53.3).
     - This can be accomplished with the help of a nasal speculum and a headlight.
     - It is advised to cauterize both the site itself and 0.5 cm around the site, by holding the silver nitrate stick to the site for at least 20 s until the bleeding stops.
     - If bleeding then stops, cover the site with an absorbable gelatin foam or an oxidized cellulose such as Gelfoam or Surgicel or simply apply topical antibiotic to the site.
  5. If there is continued bleeding, the clinician may apply either two elongated cotton pledgets or a commercially available substitute (e.g., a Rhino Rocket or similar device [Fig. 53.4]) presoaked in a few milliliters or a 1:1 mixture of a topical vasoconstrictor and an anesthetic. Combinations can include the previously cited two agents, plus 2 % tetracaine or 4 % lidocaine.
  6. Universal instructions for the insertion of a commercially available anterior nasal pack include (Fig. 53.5):
     - Soak the fabric via the manufacturer's recommended solution if required.
     - Insert antibiotic ointment in the nares to facilitate insertion.
     - Insert the entire length of the balloon along the inferior surface of the nasal cavity.
     - The fluid within the nasal cavity should cause it to expand spontaneously while in the nares, after which the remaining exposed string can be taped to the cheek.
     - For those devices that require air instillation, read the manufacturer's instructions on how much air to instill within the device.

7. Another option is to provide an anterior nasal packing using a few feet of ½-inch ribbon gauze (Fig. 53.6).
8. It is preferable if this gauze is impregnated with petroleum jelly and is enriched with bacitracin ointment.
   - If it is not, bacitracin can be applied to the strip before its insertion into the nasal cavity.
9. To facilitate the insertion, bayonet forceps can be used to gently lay each successive strip on top of the one before it.
10. Begin inferiorly, laying each strip on top of the other, about three or four layers at a time, with the end points protruding from the opening of the nasal cavity.
11. Pack the strands firmly.
12. It may take several feet to pack the entire nasal cavity.
13. This may be both uncomfortable for the patient and time consuming for the provider, so ensure adequate time and copious topical anesthetic.
14. Parenteral analgesic or anxiolytics may be required for any of these techniques.
15. If none of these resources is available, another technique requires the use of two cotton pledgets gently inserted into the nostrils after vasoconstrictor/anesthetic topical solution has been sprayed into the nose either manually or with the addition of bayonet forceps, where they will remain for 20 min, supplemented by firm pressure to the nares as described previously.
   - If the bleeding has then stopped, they can be removed at this time. If it does not, it is advised to repeat the previous step a second time, this time with a longer period of pressure, before proceeding to the next step.
16. If all of these techniques fail to control bleeding, the clinician may apply a sealant spray or foam enriched with thrombin to enhance clotting.
   - Commercially available options include Crosseal or FloSeal.
17. Finally, if none of these techniques manage to halt what one is sure is only an anterior, albeit persistent, nosebleed, consult the otolaryngologist for further guidance.
   - Another consideration at this point may be that the uncontrollable anterior nosebleed is really a posterior nosebleed from an undetermined location.
   - It may be prudent to proceed to the algorithm for treatment of posterior epistaxis, even if a posterior bleed is not specifically confirmed.

53.5.1 Complications

- Using an inadequate amount of packing when inserting the ribbon gauze, the entire product may serve as a plug with potential aspiration risk, rather than as a tool for hemostasis.
- Otitis, sinusitis, and toxic shock syndrome.

53.5.2 Pearls and Pitfalls

- Pearls
  - Be sure to perform a reevaluation of both the posterior oropharynx and the posterior nasopharynx after insertion of any of the previously discussed devices, and inspect for continued bleeding/oozing to ensure hemostasis has been accomplished.
  - For those patients with nasal packs in place, consider the use of oral antibiotics to avoid subsequent sinusitis, otitis, or toxic shock syndrome.
    - Appropriate antibiotic choices include cephalexin, clindamycin, or amoxicillin–clavulanic acid.
    - The use of antibiotics for short-term packing has not been proven.
  - Consider admission for elderly patients or for those patients with potential airway complications such as those patients with chronic obstructive pulmonary disease (COPD) and for those at risk for aspiration.
  - Have the patient follow up with otolaryngology within 2–3 days for reevaluation and packing removal.
  - Provide adequate discharge instructions warning the patient against nose blowing, sneezing with the mouth closed, or any movements or actions that cause a Valsalva maneuver.
  - The patient should try to keep his or her head elevated for the next 24–48 h even while sleeping to prevent potential aspiration.
- Pitfalls
  - Discharging a patient without an adequate period of observation.
  - Failing to ensure appropriate follow-up.
  - Providing inadequate discharge instructions.
  - Mistaking an anterior nosebleed for a posterior nosebleed.
  - Leaving silver nitrite on exposed nasal mucosa can lead to iatrogenic nasal septal perforation.
  - Not informing the patient that minimal oozing of blood from the nose can be expected.



Fig. 53.3 Example of silver nitrate stick and packaging



Fig. 53.4 Example of commercial nasal pack



Fig. 53.5 Proper taping of a commercial anterior nasal pack

Fig. 53.6 Gauze method


Layers of petroleum-soaked gauze
Bayonet forceps

53.6 Procedure: Posterior Epistaxis

- Preliminary Steps
  1. Owing to the possibility of extreme exsanguination from a posterior source of epistaxis or airway obstruction from a large clot dislodgment or large volume of blood aspiration, the stability of the patient's airway, breathing, and circulation must be ensured first.
     - Appropriate interventions entirely depend on the presentation of the patient and therefore are not described in this chapter.
     - Patients with posterior epistaxis can lose a large volume of blood quickly, so this needs to be an initial consideration.
  2. Consider establishing intravenous access and placing the patient on a cardiac monitor.
  3. Because patients with posterior epistaxis tend to be either older, on various blood thinners, or to potentially have some type of coagulopathy, consider obtaining a complete blood count, prothrombin time, and partial thromboplastin time as part of the preliminary workup.
  4. Consider a blood type and screen.
- Management of posterior epistaxis:
  1. Inspect the nares as described in the previous section on anterior nosebleeds.
  2. Several of the techniques discussed may be attempted but may not be successful.
  3. Assemble necessary equipment at the bedside.
  4. Have the patient seated upright, with the head and neck in the sniffing position.
  5. Universal precautions including a gown, glove, and mask should be employed.
  6. Drape the patient with towels or a large body drape.
  7. Apply a combination of a topical vasoconstrictor and anesthetic to the nose.
     - An appropriate choice (e.g., 1 % pseudoephedrine or 1:1000 epinephrine in a 1:1 ratio with 4 % lidocaine or 2 % tetracaine)
     - Be aware, however, that there are situations in which the bleeding may be too brisk, and this step may need to be avoided owing to time constraints and the volume of bleeding. So it is not unheard of to be required to intervene in posterior epistaxis without this initial step.
  8. Otolaryngology should be consulted as early as possible in the workup of this condition, both for admission and in case the following techniques fail.
  9. An advised initial step for the treatment of posterior epistaxis is to proceed directly to insertion of a unilateral or, preferably, bilateral posterior nasal pack or balloon.
     - An example of these is the elongated version of the Rhino Rocket as described previously.
     - Insertion and securing of the product proceed essentially the same way, except that it is inserted deeper into the posterior oropharynx.
  10. Consider the use of a dedicated posterior balloon, such as a Nasostat or Epistat (Fig. 53.7).
     - These devices are double-balloon systems that are lubricated preferably with bacitracin (sterile jelly is also appropriate) and inserted into the posterior nasopharynx.
     - The posterior balloon is then inflated with the product-specific quantity of air.
     - The product is then withdrawn slightly to ensure that the posterior balloon is situated firmly in its desired location of the posterior nasal cavity.
     - The anterior balloon is then inflated with the device-specific quantity of normal saline, and the device is secured.
- If the previously discussed resources are not available, a clinician can insert an adult-caliber Foley catheter into the posterior nasopharynx, with inflation of the balloon, and gentle traction anteriorly to ensure the bulb is situated similarly to the Nasostat or Epistat, firmly in the posterior nasal cavity to tamponade off the bleeding (Fig. 53.8).
- If all of these techniques still fail to control bleeding, an otolaryngologist will likely need to intervene, performing techniques outside the scope of practice of the emergency physician, including electrocautery, submucosal lidocaine/epinephrine injections, or other surgical interventions.
- The final step in the management of this patient includes admission to a monitored bed.

53.6.1 Pearls and Pitfalls

- Pearls
  - Consult otolaryngology early in the workup as soon as a posterior bleed is identified.
  - Patients receiving packing will still need to be placed on antibiotics, such as a first-generation cephalosporin, clindamycin, or amoxicillin–clavulanic acid.
  - Perform a good physical examination concomitantly with the management of the bleed specifically geared toward assessing the patient's volume status (orthostatics, capillary refill, heart rate), because the patient may have significant volume loss depending on the duration and quantity of the bleed.
  - Take a good history including prior bleed, prior admission requirements owing to epistaxis, any anticoagulant use, blood dyscrasias, and so on.

- Pitfalls
  - Misidentifying a posterior bleed as an anterior bleed. This can be catastrophic if the patient is discharged. Reference the “Etiology” section earlier.
  - Discharging the patient.
  - Consulting otolaryngology too late.
  - Underestimating the volume of blood loss. It may be helpful to think of these patients as trauma patients in their initial management and to proceed down the standard primary survey/intervention/secondary survey/intervention approach, ensuring that the volume needs are identified early.
  - Infection.
  - Pressure necrosis of the septum.
  - Hypoxia.
  - Aspiration.
  - Arrhythmias.
  - Dysphagia.
  - Dislodgment of the pack.



Fig. 53.7 Example of posterior balloon



Fig. 53.8 Foley catheter in the posterior nasopharynx

Selected Reading

Buttaravoli P. Minor emergencies, splinters to fractures. 2nd ed. Philadelphia: Mosby; 2007.

Kucik CJ, Clenney T. Management of epistaxis. Am Fam Physician. 2005;71(2):305–11.

Marx JA, Hockberger RS, Walls RM, editors. Rosen's emergency medicine: concepts and clinical practice. 6th ed. Philadelphia: Mosby; 2006.

Pope LE, Hobbs CG. Epistaxis: an update on current management. Postgrad Med J. 2005;81(955):309–14.

Singer AJ, Blanda M, Cronin K, et al. Comparison of nasal tampons for the treatment of epistaxis in the emergency department: a randomized controlled trial. Ann Emerg Med. 2005;45:134–9.

Summers SM, Bey T. Chapter 239. Epistaxis, Nasal Fractures, and Rhinosinusitis. In: Tintinalli's Emergency Medicine, 7th ed. New York, NY: McGraw Hill; 2011.

Treatment of Septal Hematoma

54

Bobby K. Desai

54.1 Indications

- Septal hematomas occur after force applied to the nasal cartilage results in leakage of blood from the perichondrium (Figs. 54.1 and 54.2). They may be unilateral or bilateral.
- Untreated, this hematoma can expand and mechanically obstruct the blood vessels that supply the nasal cartilage.



Fig. 54.1 Example of a septal hematoma



Fig. 54.2 Diagram of a septal hematoma

B.K. Desai, MD
Department of Emergency Medicine, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: bdesai@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_54

54.2 Contraindications

- In the setting of massive facial trauma, airway protection and consultation with otolaryngology or oral surgery may be required.

54.3 Materials and Medications

- 5-cc syringe
- 20-gauge needle (may use larger-gauge needle, but smaller ones may not allow for adequate suctioning).
- Topical antiseptic
- Sterile drapes, gown, eye protection, and gloves
- Light source—preferably a head lamp
- If using procedural sedation, specific medications of choice are needed as well as monitoring and resuscitation equipment
- Nasal speculum
- 4 % liquid cocaine or 4 % liquid lidocaine for anesthesia
- Topical vasoconstrictor of choice (oxymetazoline or phenylephrine)
- Scalpel (#15 blade)
- Suction setup
- Saline for irrigation
- Sterile gauze
- Iodoform packing or sterile rubber band
- Anterior nasal pack (Rhino Rocket)
- Intravenous antibiotics to cover *Staphylococcus aureus*, group A β-hemolytic streptococci, *Streptococcus pneumonia,* and *Haemophilus influenzae*

54.4 Procedure

- Preprocedure
  - Explain the procedure to the patient.
  - Informed consent may be required.
- Procedure—unilateral (Fig. 54.3):

1. Place the patient in a seated position if the procedure is to be done without procedural sedation.
    - If performing the procedure under procedural sedation, the patient may be placed in the supine position with appropriate monitoring and resuscitation equipment on standby.
2. Provide local anesthesia by applying the topical anesthetic of choice to cotton pledgets, wringing out the excess before insertion.
    - Remove after 10 min.
    - If using lidocaine, a topical vasoconstrictor may be required that may be mixed with the lidocaine or applied directly on the nasal mucosa before the procedure.
3. Using a nasal speculum, open the affected nares vertically as wide as possible. Horizontal use may obscure the hematoma.
4. Using a #15 blade, make a vertical incision at the hematoma extending the incision posteriorly at its base.
    - Take care not to make too deep an incision because septal perforation may occur.
5. Suction and gauze should be at the ready to remove as much blood as possible.
6. Pack the incision site with iodoform gauze or a sterile rubber band in order to keep the incision open to prevent accumulation of blood.
7. This packing can be held in place with an anterior nasal pack.
    - The pack should be placed in both nares to prevent deformity of the nasal septum.
8. Consider administration of a dose of intravenous antibiotics.
9. Send the patient home with a prescription for oral antibiotics.
10. Arrange follow-up for 24 h.

- Procedure—bilateral (Fig. 54.4):

1. If bilateral hematomas are present, otolaryngology consultation should be sought.
2. One method involves the incision of one side only through the nasal septum so that both may drain through one side.
    - Care must be taken NOT to penetrate the overlying mucosa of the other side.
3. The second option is to repeat the unilateral drainage procedure on the contralateral side.
4. Care must be taken to not have the incision exactly in the same location as the contralateral side owing to the risk of permanent septal perforation.


a
Nasal septum
Septal hematoma
Perichondrium
b
c
d

Fig. 54.3 (**a–d**) Technique for drainage of a unilateral septal hematoma



Fig. 54.4 Technique for drainage of a bilateral septal hematoma

54.5 Pitfalls and Complications

- Bleeding
- Infection: toxic shock syndrome
- Deformity of the nose
- Permanent septal perforation
- Inadequate drainage
- Reaccumulation of blood
- Development of septal abscess

Selected Reading

Ginsburg CG. Consultation with the specialist: nasal septal hematoma. Pediatr Rev. 1998;19:142–3.

Savage RR, Valvich C. Hematoma of the nasal septum. Pediatr Rev. 2006;27:478–9.

Nasal Foreign Body Removal

55

Bobby K. Desai

55.1 Indications

- Visualized foreign body (FB) on inspection
- Continued unilateral nasal discharge of unknown etiology
- Recurrent epistaxis

55.2 Contraindications: Need Urgent Referral

- Those cases in which the emergency physician is not confident of success.
- Combative patients who are not candidates for conscious sedation.
- Embedded FBs.
- Penetrating injuries with an FB.
- Button batteries that cannot be removed.
- Patients with bleeding diathesis.
- Respiratory distress.
- FBs superior and medial to the middle turbinate owing to risk of puncture to the cribriform plate.
- Chronic FBs may be difficult to visualize and these should be referred.

B.K. Desai, MD
Department of Emergency Medicine, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: bdesai@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_55

55.3 Materials and Medications

- 1 % lidocaine without epinephrine (solution) for anesthesia
- 2 % lidocaine jelly
- 0.5 % phenylephrine to vasoconstrict vessels
- Nasal speculum (Fig. 55.1)
- Headlamp or other direct lighting instrument
- Ambu bag (Fig. 55.2)
- Alligator forceps (Fig. 55.3)
- Curved hook (Fig. 55.4)
- Foley catheter
- Suction: schuknecht catheter (Fig. 55.5)
- Eye and biohazard protection for the clinician



Fig. 55.1 (**a**–**c**) Example of nasal speculum



Fig. 55.2 Example of Ambu bags



Fig. 55.4 Example of a curved hook



Fig. 55.5 Example of a schuknecht suction tube



Fig. 55.3 Example of alligator forceps

55.4 Procedures (Based on the Method Chosen)

55.4.1 Alligator Forceps

- Perhaps the easiest method to use for easily visualized FBs.
- Care must be taken for those FBs that are easily broken apart (e.g., peas) to ensure that all of the matter has been removed.
- Using a nasal speculum, spread the nares as much as possible to maximize visualization.
- Stabilize the head with the nondominant hand, or for children, consider a papoose board to secure the patient.
- Attempt to grasp the FB with the forceps.
- After removal, ensure the complete removal of the object and ensure that no other FBs are present.

55.4.1.1 Pitfalls and Complications

- Pushing the object deeper into the nares.
- Inability to totally remove the FB.
- Attempted removal of an embedded FB may cause significant bleeding.

55.4.2 Curved Hook

- Used for nongraspable objects especially in the anterior nares.
- Using a nasal speculum, spread the nares as much as possible to maximize visualization.
- Stabilize the head with the nondominant hand, or for children, consider a papoose board to secure the patient.
- Pass the hook behind the object, or if the object has holes, the hook may be placed inside the hole to facilitate removal.
- Slowly withdraw the hook, thereby removing the FB.
- After removal, ensure the complete removal of the object and ensure that no other FBs are present.

55.4.2.1 Pitfalls and Complications

- This technique cannot be used if the object cannot be directly visualized because significant trauma may arise owing to the misplacement of the hook.
- Attempted removal of an embedded FB may cause significant bleeding.

55.4.3 Foley Catheter Removal

- Use a 5 or 6 French catheter.
- Anesthetize the nares with lidocaine with or without epinephrine and vasoconstrict the nasal vessels with phenylephrine.
- Ensure that the Foley balloon has no leaks.
- Place the patient in a supine position.
  - Consider procedural sedation for children and/or a papoose board.
- Lubricate the Foley tip and balloon with lidocaine jelly.
- Advance the tip past the object.
- Blow up the balloon with 2–3 mL of air and gently withdraw the catheter.
  - The amount of air may need to be adjusted depending on the size of the object to be withdrawn.
  - Pulling too quickly may cause a soft FB to break apart.

55.4.3.1 Pitfalls and Complications

- This technique may be used if the FB is not visible.
- In order for this technique to work, the catheter must be able to slide posterior to the object in order for the balloon to pull out the object.

55.4.4 Suction

- A small metal suction catheter—the schuknecht catheter—may be used.
- The suction is placed against the FB and slowly withdrawn.
- This technique works best for round smooth objects visualized in the anterior nares.

55.4.4.1 Pitfalls and Complications

- May not work for posteriorly displaced FBs.
- May not work for objects too tightly entrenched in the nares.

55.4.5 Nasal Positive Pressure

- This technique works best for round FBs occluding the nares.
- Place the patient in a supine position.
  - Consider a papoose board to secure the patient.
- Apply pressure to the contralateral nares to occlude it.
- Connect an Ambu bag to high-flow oxygen.
  - Use a facemask that covers only the mouth.
- Place the mask on the patient's mouth and allow it to expand by covering the thumbhole.
- If this pressure is insufficient to expel the object, the Ambu bag may be compressed to add pressure to the attempt.
- This may allow the object to be seen and grasped in the anterior nares.

55.4.5.1 Pitfalls and Complications

- Too much pressure could theoretically rupture the tympanic membranes.

Selected Reading

Backlin SA. Positive-pressure technique for nasal foreign body removal in children. Ann Emerg Med. 1995;25:554–5.

Chan TC, Ufberg J, Harrigan RA, et al. Nasal foreign body removal. J Emerg Med. 2004;26:441–5.

Kadish H. Ear and nose foreign bodies: it is all about the tools. Clin Pediatr. 2005;44:665–70.

Cerumen Removal

56

Bobby K. Desai

56.1 Indications

- Hearing loss
- Profound dizziness
- Pain

56.2 Contraindications

- Uncooperative patient
- Potential for foreign bodies
- Prior surgery to ear or mastoid
- History of middle or outer ear disease

56.3 Materials and Medications

- Ear speculum (Fig. 56.1).
- Eye and biohazard protection for the clinician
- Headlamp or other direct lighting instrument
- Cerumen-softening solutions
  - Carbamide peroxide
  - Mineral oil or other oil-based agents including almond or olive oil
  - Liquid docusate sodium
  - Acetic acid
  - Sodium bicarbonate
- Alligator forceps (Fig. 56.2)
- Curved hook or cerumen spoon (Figs. 56.3 and 56.4)
- Suction—Schuknecht catheter
- Irrigation setup
  - Ear syringe (Figs. 56.5 and 56.6)

– 20- to 60-mL syringe with an 18-gauge angiocath attached
  - Commercial ear irrigation setup
  - Water (tap water may be used)
  - Basin or other collection device
  - Towels

B.K. Desai, MD
Department of Emergency Medicine, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: bdesai@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_56



Fig. 56.1 Example of an ear speculum



Fig. 56.2 Example of alligator forceps



Fig. 56.3 Examples of cerumen spoons



Fig. 56.4 Examples of ear curettes



Fig. 56.5 Example of a typical bulb syringe used in irrigation


Tri-Stream tip
Flared design
Exit portals
0
5
10
15
20

Fig. 56.6 Example of a specialized ear syringe

56.4 Procedure

1. Explain the procedure to the patient to facilitate cooperation.
    - Some discomfort may be involved, including a sensation of pressure and the cold, wet feeling from the water used.
    - Nausea, vomiting, or a sensation of vertigo may also be experienced.
        - Consider pretreatment of vertigo with agent of choice.
2. The patient may be seated or supine with the head slightly turned to the affected side to facilitate the collection of fluid.
3. Stabilize the head with the nondominant hand, or for children, consider a papoose board to secure the patient.
4. Pull the ear up and out to straighten the ear canal.
5. Before irrigation, if the cerumen is hard, alligator forceps or a cerumen spoon may be used under direct visualization to remove as much cerumen as possible.
6. Use a cerumen-softening agent before irrigation by instilling and leaving in for 30 min to maximize softening.
7. Place a collection device next to the patient's ear, or alternatively, have the patient hold a basin near the ear to collect any liquid.
8. Attach an angiocath to a 20- or 60-mL syringe, place the tip of the catheter within the ear canal, and aim toward the tympanic membrane.
9. Slowly inject the solution into the ear canal.
    - Care must be taken to limit the force used owing to the potential for tympanic membrane rupture.
    - The fluid can be injected in short bursts or all at once.
10. Direct the stream as much as possible toward the rear of the cerumen to be removed.
11. Continually reassess the ear canal to ensure that all cerumen has been removed.
    - If one large piece remains, use a cerumen hook to facilitate removal.
12. If the patient complains of severe sharp pain, stop the procedure and assess the tympanic membrane for rupture.
    - Consider referral or otolaryngological consultation at this point.
13. After successful removal, dry the ear canal with cotton-tipped applicators to prevent otitis externa.

56.5 Pitfalls and Complications

- Owing to instillation of room temperature water, a caloric response may occur including vertigo, nausea, and vomiting.
- Rupture of the tympanic membrane.
- Unsuccessful irrigation secondary to inadequate time given to softening agents before attempting removal.
- Bleeding of the external auditory canal.
- Otitis externa.
- Hearing loss.

Selected Reading

Blake P, Matthews R, Hornibrook J. When not to syringe an ear. N Z Med J. 1998;111:422.

McCarter D, Courtney AU, Pollart SM. Cerumen impaction. Am Fam Physician. 2007;75:1523–8.

Roland PS, Smith TL, Schwartz SR, et al. Clinical practice guideline: cerumen impaction. Otolaryngol Head Neck Surg. 2008;139:S1–21.

Ear Foreign Body Removal

57

Bobby K. Desai

57.1 Indications

- Visualized foreign body (FB) on inspection.
- Continued unilateral otorrhea of unknown etiology mandates a search.
- Recurrent bleeding.
- History of FB placement by patient.

57.2 Contraindications: Need Urgent Referral

- Those cases in which the emergency physician is not confident of success.
- Combative patients are not candidates for conscious sedation.
- Embedded FBs.
- Penetrating injuries with an FB.
- FBs close to the tympanic membrane.
- Consider referral of spherical FBs because these may be difficult to grasp.
- Chronic FBs may be difficult to visualize; these should be referred.
- Consider referral for those patients who have attempts made at other institutions.

57.3 Materials and Medications

- Ear speculum (Fig. 56.1)
- Eye and biohazard protection for the clinician
- Headlamp or other direct lighting instrument
- Alligator forceps (Fig. 56.2)
- Curved hook (Fig. 57.1) or cerumen spoon (Fig. 56.3)
- Suction—Schuknecht catheter (Fig. 57.2)
- Irrigation setup
  - Ear syringe (Fig. 57.3)
  - 20- to 60-mL syringe with an 18-gauge angiocath attached
  - Water (tap water may be used)
  - Basin or other collection device
  - Towels
- Cyanoacrylate (Fig. 57.4)

B.K. Desai, MD
Department of Emergency Medicine, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: bdesai@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_57



Fig. 57.1 Example of a curved hook


a
b
hydrogen peroxide

Fig. 57.2 (**a**) Example of a Schuknecht suction tube, (**b**) example of ear irrigation setup using a Waterpik system



Fig. 57.3 Example of a typical syringe used in irrigation

ETHICON
DERMABOND
ADVANCED
DERMABOND ADVANCED

Fig. 57.4 Example of cyanoacrylate

57.4 Procedures (Based on the Method Chosen)

57.4.1 Alligator Forceps

- Ideal for easily visualized FBs, especially graspable FBs in the lateral third of the ear canal.
  - May have limited success with rounded objects.
- Care must be taken for those FBs that are easily broken apart (e.g., peas) to ensure that all of the matter has been removed.
  - May need irrigation subsequent to the attempt.
- Explain the procedure to the patient to facilitate cooperation.
- Pull the ear up and out to straighten the ear canal.
- Consider using a specialized otoscope with magnification (an operating otoscope) to maximize visualization.
- The patient may be seated or supine with the unaffected side turned to the gurney or examining chair.
- Stabilize the head with the nondominant hand, or for children, consider a papoose board to secure the patient.
- Attempt to grasp the FB with the forceps.
  - If using an ear speculum, attempt to bring the object as close as possible to the speculum in order to stabilize it and slowly remove both.
- After removal, ensure the complete removal of the object and ensure that no other FBs are present.

57.4.1.1 Pitfalls and Complications

- Pushing the object deeper into the auditory canal.
- Inability to totally remove the FB.
- Attempted removal of an embedded FB may cause significant bleeding.

57.4.2 Curved Hook

- Ideal for spherical objects in the lateral third of the auditory canal.
- Can be used for non-graspable objects especially in the lateral third of the auditory canal.
- Direct visualization is necessary to avoid trauma to the ear canal.
- Consider using a specialized otoscope with magnification (an operating otoscope) to maximize visualization.
- Explain the procedure to the patient to facilitate cooperation.
- The patient may be seated or supine with the unaffected side turned to the gurney or examining chair.
- Stabilize the head with the nondominant hand, or for children, consider a papoose board to secure the patient.
- Pull the ear up and out to straighten the ear canal.
- Pass the hook behind the object, or if the object has holes, place the hook inside the hole to facilitate removal.
  - In order for this technique to succeed, there must be sufficient area near the object to facilitate the hook going behind it.
- Slowly withdraw the hook, thereby removing the FB.
- After removal, ensure the complete removal of the object and ensure that no other FBs are present.

57.4.2.1 Pitfalls and Complications

- Pushing the object deeper into the auditory canal.
- This technique cannot be used if the object cannot be directly visualized because significant trauma may arise owing to the misplacement of the hook.
- Attempted removal of an embedded FB may cause significant bleeding.
- Do not use this technique if the object is close to the tympanic membrane owing to risk of rupture.

57.4.3 Suction

- A small metal suction catheter—the Schuknecht catheter—may be used.
- Ideal for hard rounded objects in the lateral third of the ear canal.
  - Does not work as well for those objects closer to the tympanic membrane owing to lack of suction and the narrow ear canal
- Direct visualization of the object is mandatory.
  - The catheter must be placed directly on the object for this technique to succeed.
- Explain the procedure to the patient to facilitate cooperation.
- The patient may be seated or supine with the unaffected side turned to the gurney or examining chair.
- Stabilize the head with the nondominant hand, or for children, consider a papoose board to secure the patient.
- Pull the ear up and out to straighten the ear canal.
- Place the suction against the FB and slowly withdraw.

57.4.3.1 Pitfalls and Complications

- Pushing the object deeper into the auditory canal
- May not work for objects too tightly entrenched in the ear canal

57.4.4 Irrigation

- Useful for small particulate matter unable to be grasped by forceps or too small for a hook to pull out.
  - Cannot be used for button batteries or vegetable matter.
    - Irrigation may cause an alkaline necrosis with the button battery.
    - Vegetable matter may expand, increasing the difficulty of removal.
- Explain the procedure to the patient to facilitate cooperation.
  - Some discomfort may be involved, including a sensation of pressure and a feeling cold wetness from the water used.
- The patient may be seated or supine with the head slightly turned to the affected side to facilitate collection of fluid.
- Stabilize the head with the nondominant hand, or for children, consider a papoose board to secure the patient.
- Pull the ear up and out to straighten the ear canal.
- Place a collection device next to the patient's ear, or alternatively, have the patient hold a basin.
- Attach an angiocath to a 20- or 60-mL syringe and place the tip of the catheter within the ear canal, or use a Waterpik system.
- Slowly inject the solution into the ear canal.
  - Care must be taken to limit the force used owing to the potential for tympanic membrane rupture.
- Direct the stream as much as possible toward the rear of the object(s) to be removed.
- Continually assess the ear canal to ensure that all foreign matter has been removed.
- If the patient complains of severe sharp pain, stop the procedure and assess the tympanic membrane for rupture.
  - Consider referral or otolaryngological consultation at this point.

57.4.4.1 Pitfalls and Complications

- Owing to instillation of room temperature water, a caloric response may occur including vertigo, nausea, and vomiting.
- Rupture of the tympanic membrane.

57.4.5 Cyanoacrylate

- Useful for objects that can be directly visualized.
- Ideal for hard rounded objects in the lateral third of the ear canal.
  - Does not work as well for those objects closer to the tympanic membrane owing to lack of visualization
- Direct visualization of the object is mandatory.
  - The stick with the cyanoacrylate must be placed directly on the object for this technique to succeed.
- Consider using a specialized otoscope with magnification (an operating otoscope) to maximize visualization.
- Explain the procedure to the patient to facilitate cooperation.
- The patient may be seated or supine with the unaffected side turned to the gurney or examining chair.
- Stabilize the head with the nondominant hand, or for children, consider a papoose board to secure the patient.
- Pull the ear up and out to straighten the ear canal.
- Place a small amount of cyanoacrylate on the end of a cerumen spoon or wooden end of a cotton-tipped swab.
- Using direct visualization, place the stick in the ear canal and touch the FB.
- Leave the stick on the object for approximately 30–60 s to facilitate drying of the glue.
- Remove the stick and the FB.

57.4.5.1 Pitfalls and Complications

- This technique cannot be used if the object cannot be seen.
- The object must be relatively smooth to facilitate placement of the glue.

Selected Reading

Hanson RM, Stephens M. Cyanoacrylate-assisted foreign body removal from the ear and nose in children. J Paediatr Child Health. 1994;30:77–8.

Kadish H. Ear and nose foreign bodies: it is all about the tools. Clin Pediatr. 2005;44:665–70.

Treatment of Auricular Hematoma

58

Bobby K. Desai

58.1 Indications

- Presence of auricular hematoma
  - These occur after significant force is applied to the ear.
  - This type of hematoma will separate the perichondrium from the cartilage.
    - Untreated, this hematoma prevents the development of new cartilage, subsequently deforming the auricle, causing *cauliflower ear* (Figs. 58.1 and 58.2).



Fig. 58.1 Example of a cauliflower ear

B.K. Desai, MD
Department of Emergency Medicine, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: bdesai@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_58



Fig. 58.2 Schematic of auricular hematoma

58.2 Contraindications

- Uncooperative patient.
- Evidence of infection mandates plastic surgery or otolaryngology consultation.
- Significant trauma to area around the ear.

58.3 Materials and Medications

- 5-cc syringe
- 20-gauge needle (may use larger-gauge needle, but smaller ones may not allow for adequate suctioning)
- Topical antiseptic
- Sterile drapes, gown, eye protection, and gloves
- 1 % lidocaine for anesthesia
- Scalpel (#11 or #15 blade)
- Suction setup
- Saline for irrigation
- Hemostat and forceps
- Penrose drain or plain gauze packing
- Xeroform gauze
- Laceration tray setup
  - Needle driver
  - 4–0 Nonabsorbable suture
- Antibiotic ointment
- Gauze bandages

58.4 Procedure (Needle Aspiration)

1. Explain the procedure to the patient.
2. Informed consent may be required.
3. The patient may be seated or supine with the unaffected side turned to the gurney or examining chair.
4. Stabilize the head with the nondominant hand, or for children, consider a papoose board to secure the patient.
   - Consider procedural sedation for children.
5. Carefully clean the area with an antiseptic solution of choice (povidone-iodine [Betadine] or chlorhexidine solution) and allow to dry.
6. Anesthetize the area where the hematoma is of greatest diameter with 1 % lidocaine.
7. Inject the hematoma itself to promote increased anesthesia.
8. The clinician should prepare for the procedure by practicing universal precautions.
9. Drape the patient's ear.
10. Attach a 20-gauge needle to a syringe.
    - A 5-cc syringe should be sufficient.
11. Attempt to aspirate the hematoma contents with the prepared syringe (Fig. 58.3).

12. "Milking" the hematoma may be required to fully remove the clot.
    - If the hematoma has been present for sufficient time for the blood to completely clot, needle aspiration will fail, and an alternative technique, described later, may be necessary to completely evacuate the hematoma.
13. Place antibiotic ointment around the injection site.
14. Loosely dress the area.
15. Refer to an otolaryngologist or a plastic surgeon for follow-up care.

If needle aspiration fails, a larger incision may be required using the following procedure:

1. Perform the previously discussed steps.
2. Consider a local field block of the greater auricular nerve.
3. Make an incision over the hematoma, following the anatomy of the helix (Fig. 58.4).
    - The incision should be 5–6 mm in length and curvilinear, following the concavity of the helix.
    - More than one incision may be required.
4. Remove the hematoma with hemostats or forceps.
    - Suctioning may be used as well.
5. Copiously irrigate the cavity with saline to make certain of complete removal of the hematoma.
6. Insert the Penrose drain or plain packing into the incision.
7. Antibiotic ointment may be applied to the incision site.
8. Place the Xeroform gauze over the incision site.
9. Apply a compression dressing to the ear (Fig. 58.5).
    - Place dry cotton into the ear canal to protect from possible drainage and subsequent infection (Fig. 58.6).
    - Mold Xeroform gauze in and around the contours of the helix (Fig. 58.7).
    - With the aid of an assistant, place gauze behind the pinna and over the Xeroform gauze already molded to the anterior portion of the ear (Fig. 58.8).
    - Place more fluffed gauze over the ear (Fig. 58.9).
    - While the assistant holds the anterior and posterior gauze in place, use a web roll (Kerlix) around the head to keep the gauze in place. Then wrap the head with an ACE wrap or stretchy bandage (Figs. 58.10 and 58.11).
    - These steps are critical to maintain equal compression of the ear, which will help prevent future deformity.
    - Alternatively, dental rolls can be secured with suture to the anterior and posterior site of the drained hematoma (Fig. 58.12).
10. Place the patient on prophylactic antibiotics.
11. Refer to an otolaryngologist or a plastic surgeon for follow-up care.



Fig. 58.3 Aspiration of a hematoma



Fig. 58.4 Incision of an auricular hematoma. (**a**) Incision; (**b**) removal of clot with forceps; (**c**) aspiration of blood with syringe



Fig. 58.5 Materials needed for compression dressing



Fig. 58.6 Place cotton in the ear to prevent drainage into ear



Fig. 58.7 (**a**, **b**) Mold Xeroform gauze around ear helix



Fig. 58.8 (**a**, **b**) Mold sterile gauze on top of Xeroform gauze around ear helix



Fig. 58.9 Pad outside of ear with 4×4 gauze pads



Fig. 58.10 (**a**–**c**) Wrap head with Kerlix (sterile gauze roll)



Fig. 58.11 (**a**–**d**) Wrap head with elastic bandage



Fig. 58.12 Dental rolls secured to the ear

58.5 Pitfalls and Complications

- Bleeding
- Infection—perichondritis
- Deformity of the auricle
- Inadequate clot removal
- Hematomas present for several days warrant a plastic surgery or an otolaryngology consultation

Acknowledgement The authors would like to thank Thor Shiva Stead for serving as the subject in many of the photographs in this chapter.

Selected Reading

O'Donnell BP, Eliezri YD. The surgical treatment of traumatic hematoma of the auricle. Dermatol Surg. 1999;25:803–5.

Starck WJ, Kaltman AI. Current concepts in the surgical management of traumatic auricular hematoma. J Oral Maxillofac Surg. 1992;50:800–2.

Incision and Drainage of Peritonsillar Abscess

59

Melinda W. Fernandez and Bobby K. Desai

59.1 Indications

- Peritonsillar abscess

59.2 Contraindications

- Absolute
  - Malignancy
  - Vascular malformations
- Relative
  - Pediatric patient
  - Severe trismus
  - Uncooperative patient

59.3 Materials and Medications

- #11 or #15 scalpel
- 27-gauge 1.5-inch needle, 18- to 20-gauge 1.5-inch or longer needle
- 5-mL syringe, 10- to 20-mL syringe
- Tape
- Trauma shears
- Viscous lidocaine
- Lidocaine 1 % with epinephrine
- Laryngoscope with MAC 3 or 4 *or* tongue blade(s) and headlamp or other light source
- Suction setup with Frazier or tonsil suction tip

59.4 Procedure: Aspiration

1. Informed consent may be required.
2. Raise head of bed to at least 60° and place a pillow or other support behind the patient's head.
3. Prepare an 18- to 20-gauge 1.5-inch needle on a 10- to 20-mL syringe with a needle guard.
   - This can be accomplished by using trauma shears to cut 1–1.5 cm off the distal plastic needle cover and replacing the cover over the needle.
   - This now creates a guard to prevent deep penetration into vascular structures (Fig. 59.1).
4. Topically anesthetize area with viscous lidocaine (alternatively, can use Cetacaine [benzocaine, tetracaine hydrochloride, and butamben] spray)
5. Using lidocaine 1 % with epinephrine and a 27-gauge 1.5-inch needle on a 5-mL syringe, infiltrate 1–2 mL into the area. Blanching should be apparent.
6. Palpate the oropharynx with the gloved finger to evaluate for fluctuance.
7. Assemble a MAC 3 or 4 intubation blade on a laryngoscope handle and open into the light-on position. Insert the blade into the patient's mouth, and advance the blade as far posteriorly as possible without inducing gagging. Have the patient hold the laryngoscope handle. Alternatively, use a tongue blade and head lamp or other light source, but the laryngoscope technique allows for an unobstructed view of the area and the weight of the handle helps hold the patient's mouth open.
8. Using the previously prepared needle guard on the long 18- to 20-gauge needle on a 12-mL syringe, insert the needle into the most fluctuant area (as determined from the previous examination), aspirating as the needle advances (Fig. 59.2). The most fluctuant area will usually be located in the superior pole of the tonsil.

- It is very important to be careful not to angle the needle laterally toward the carotid artery. Also remember, this is a peritonsillar abscess so do not aspirate the tonsil itself.

M.W. Fernandez, MD
Department of Emergency Medicine, University of Florida Health, Gainesville, FL, USA
e-mail: mindyfernandez@ufl.edu

B.K. Desai, MD (✉)
Department of Emergency Medicine, University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: bdesai@ufl.edu

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_59

9. After aspiration, if there is a pus return, remove as much purulent drainage as possible. Typical drainage is between 2 and 6 mL. If a large amount of pus is obtained (>6 mL), incision and drainage (I&D) may be indicated. (See later for details on I&D.)
10. If the aspirate did not return pus, attempt aspiration again by moving the insertion site 1 cm inferiorly to the middle pole of the peritonsillar space. If there is still no pus aspirated, make a final attempt by moving again 1 cm inferiorly to the lower pole of the peritonsillar space.
11. Suction should be set up, readily available, and turned on. Use suction to prevent the patient from aspirating or swallowing any purulent drainage.
12. Expect a small amount of bleeding when the procedure is complete and the needle is removed.



Fig. 59.1 Guard to prevent deep penetration of vascular structures



Fig. 59.2 Aspiration of a peritonsillar abscess: (**a**) Aspirate superior pole first. If no pus aspirated, move 1 cm inferior to the middle pole. If still no pus, make final attempt by moving 1 more cm inferiorly to the inferior pole. (**b**) Demonstrates use of needle guard

59.5 Procedure: Incision and Drainage

1. Raise the head of the bed and anesthetize the area as described previously.
2. Have suction set up with a Fraser or tonsil tip, available, and turned on.
3. Have the patient hold the laryngoscope handle after the blade has been inserted orally as described previously.
4. Fashion a blade guard on a #11 or #15 blade scalpel by taping over the blade with only 0.5 cm of the blade exposed at the tip. Incise the area that was previously aspirated with a small stab incision. Suction the area.
5. Insert a curved Kelly clamp into the incision and open gently to enter the abscess cavity and break up loculations (Fig. 59.3). Suction as necessary.
6. Have the patient gargle with a saline solution and expectorate.
7. Do not pack the abscess cavity.
8. Observe for 2–4 h for bleeding.



Fig. 59.3 Incision and drainage of peritonsillar abscess: (**a**) Gain access with appropriate lighting. (**b**) Fashion a blade guard on a #11 or #15 blade scalpel by taping over the blade with only 0.5 cm of the blade exposed at the tip. Incise the area that was previously aspirated with a small stab incision. (**c**) Insert a curved Kelly clamp into the incision and open gently to enter the abscess cavity and break up loculations. Do not pack!

59.6 Complications

- Aspiration or incision of the carotid artery
- Excessive bleeding
- Aspiration of purulent material
- Pain

59.7 Pearls and Pitfalls

- Pearls
  - Airway protection should always be considered. Intubation may be necessary for very large abscesses with airway compromise.
  - Bedsides ultrasound is a valuable tool in confirming the diagnosis of peritonsillar abscess. Perform using the intracavitary probe covered with a sterile glove or other appropriate probe cover and insert into the oropharynx. The abscess will appear as any other abscess: an encapsulated, hypoechoic structure. Doppler flow can also be used to locate the carotid artery relative to the abscess.
  - Empirical oral antibiotics after aspiration or I&D are considered usual care and should cover for group A streptococcus and oral anaerobes.
    - Amoxicillin/clavulanate or clindamycin is the most commonly used.
  - A single dose of high-dose steroids may be helpful in relieving symptoms.
  - Patients who cannot tolerate oral fluids, cannot take oral antibiotics, or who appear to have a toxic response should be admitted. Others may be discharged with 24-h follow-up.
- Pitfalls
  - The carotid artery is located approximately 2.5 cm posterolaterally to the tonsils. Take care that the needle is not inserted too far laterally or the risk of aspirating the carotid artery is increased.
  - Incision into the tonsil itself may cause excessive bleeding. Aspiration or incision into the tonsil will likely miss the abscess altogether and may result in misdiagnosis.
  - There is a 1–15 % failure and recurrence rate.

Selected Reading

Afarian H, Lin M. Tricks of the trade—say “ah!”—needle aspiration of peritonsillar abscess. ACEP News. 2008;27(5):38.

Braude DA, Shalit M. A novel approach to enhance visualization during drainage of peritonsillar abscess. J Emerg Med. 2008;35:297–8.

Galioto NJ. Peritonsillar abscess. Am Fam Physician. 2008;77:199–202.

Ozbek C, Aygenc E, Tuna EU, Selcuk A, Ozdem C. Use of steroids in the treatment of peritonsillar abscess. J Laryngol Otol. 2004;118:439–42.

Roberts J, Hedges J, editors. Clinical procedures in emergency medicine. 5th ed. Philadelphia: Saunders; 2009. p. 1184–9.

Vieira F, Allen SM, Stocks RM, Thompson JW. Deep neck infection. Otolaryngol Clin North Am. 2008;41:459–83.

Incision and Drainage of Sublingual Abscess

60

Melinda W. Fernandez and Bobby K. Desai

60.1 Indications

- Sublingual abscess (Fig. 60.1)



Fig. 60.1 Sublingual abscess

M.W. Fernandez, MD
Department of Emergency Medicine, University of Florida Health, Gainesville, FL, USA
e-mail: mindyfernandez@ufl.edu

B.K. Desai, MD (✉)
Department of Emergency Medicine, University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: bdesai@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_60

60.2 Contraindications

- Relative
  - Pediatric patient
  - Severe trismus—may need sedation or drainage in the operating room
  - Uncooperative patient—may need sedation or drainage in the operating room
  - Coagulopathy, patients taking anticoagulants, or patients with a known bleeding disorder

60.3 Materials and Medications (Fig. 60.2)

- #11 scalpel
- Hemostats
- Penrose drain
- 4-0 silk suture
- 25- to 27-gauge 1.5-inch needle for injecting anesthetic
- 18- to 20-gauge needle for drawing up anesthetic
- 5- to 10-mL syringe or control syringe
- Viscous lidocaine (or other topical anesthetic)
- Lidocaine 1 % with epinephrine
- Light source
- Suction setup with tonsil suction tip
- Culture swab



Fig. 60.2 Materials needed: #11 scalpel, hemostats, Penrose drain, 4-0 silk suture, 25–27-gauge 1.5-inch needle for injecting anesthetic, 18- to 20-gauge needle for drawing up anesthetic, 5- to 10-mL syringe or control syringe, viscous lidocaine (or other topical anesthetic), lidocaine 1 % with epinephrine, light source, suction setup with tonsil suction tip, culture swab (optional)

60.4 Procedure: Incision and Drainage

1. After explaining the procedure, risks, and benefits to the patient, put the head of the bed in the most comfortable working position for the clinician and the patient. Alternatively, the clinician may also elect to position the patient in an upright procedure chair that has multiple positions.
2. Apply viscous lidocaine topically with a cotton-tipped swab to the area to be injected with anesthetic. Leave in place for a minute or 2. Alternatively, spray the area with a topical anesthetic spray.
3. Have suction set up with a tonsil tip, available, and turned on.
4. Draw up the appropriate amount of lidocaine with epinephrine into a 5-mL syringe (control syringe if available).
5. Direct light source to area to be worked on. *Adequate lighting is essential.* Options include a headlamp or an overhead adjustable light.
6. Change needle to the 27-gauge needle and inject 1–2 mL of lidocaine with epinephrine using an inferior alveolar block. Alternatively, anesthetize the floor of the mouth around the most fluctuant area. Avoid injecting through infected tissue to avoid possible spread into deeper spaces.
7. Using the scalpel, make an intraoral stab incision superficially at the lowest point of the pus accumulation (Fig. 60.3). This will facilitate evacuation of pus under gravity. Have the suction catheter in the mouth and allow the purulent material to drain into the suction.
8. Obtain a specimen of the purulent fluid for culture and sensitivity.
9. Insert a hemostat into the incision to facilitate drainage, but do not open it up to avoid injury to neurovascular structures. Gently massage the soft tissue surrounding the abscess to assist drainage. Suction as necessary to avoid swallowing or aspirating the pus.
10. Once adequate drainage has been achieved, place a small Penrose drain (or other rubber-type drain) into the cavity, and stabilize on one side with a silk suture that goes through the drain and the mucosa (Fig. 60.4).
11. Have the patient rinse and spit with a half-strength peroxide solution followed by either water or saline.
12. Watch for signs of bleeding or upper airway symptoms.
13. Ensure that the patient can tolerate oral fluids before discharge.



Fig. 60.3 Incise lowest portion of abscess



Fig. 60.4 (**a**) Using hemostats, place small Penrose drain into the abscess cavity. (**b**) Suture Penrose in place with a silk suture that goes through the drain and the mucosa

60.5 Complications (Generally Minimal)

- Excessive bleeding (apply pressure—to avoid potential nerve injury, do not cauterize or ligate unless absolutely necessary)
- Aspiration of purulent material (have the patient sit upright and use suction as the abscess is incised)
- Pain

60.6 Pearls and Pitfalls

- Pearls
  - Airway protection is paramount. Infections in this space can quickly spread to the submandibular region and can compromise the airway owing to swelling (Ludwig's angina).
    - Assess for elevation of the floor of the mouth and tongue, ability to lie supine, drooling, stridor, and restlessness.
    - If these signs are present, emergent surgical airway will be necessary before incision and drainage (I&D).
  - The sublingual space is bounded superiorly by the oral mucosa and inferiorly by the mylohyoid muscle.
  - Infected premolars and first molars drain into this space because the apices of their roots are located superior to the mylohyoid muscle.
  - The source molar should be extracted as soon as possible after I&D.
  - Empirical oral antibiotics after I&D should cover for group A streptococcus and oral anaerobes. Penicillin remains the drug of choice, but clindamycin or amoxicillin–clavulanic acid can be substituted.
- Pitfalls
  - The lingual artery, vein, and nerve are contained in the posterolateral area of the floor of the mouth, and the hypoglossal nerve is nearby. These must be avoided when performing I&D for sublingual abscesses.

Selected Reading

Flynn TR, Shanti RM, Levi MH, Adamo AK, Kraut RA, Trieger N. Severe odontogenic infections, part 1: prospective report. J Oral Maxillofac Surg. 2006;64:1093–103.

Reichman E, Simon R, editors. Emergency medicine procedures. New York: McGraw-Hill Education; 2003. p. 1342–5.

Roberts J, Hedges J, editors. Clinical procedures in emergency medicine. 5th ed. Philadelphia: Saunders; 2009. p. 1184–9.

Vieira F, Allen SM, Stocks RM, Thompson JW. Deep neck infection. Otolaryngol Clin North Am. 2008;41:459–83.

Incision and Drainage of Parotid Duct Abscess

61

Melinda W. Fernandez and Bobby K. Desai

61.1 Indications

- Parotid duct abscess

61.2 Contraindications

- Absolute
  - None
- Relative
  - Pediatric patient
  - Severe trismus—may need sedation or drainage in the operating room
  - Uncooperative patient—may need sedation or drainage in the operating room
  - Coagulopathy, patients taking anticoagulants, or patients with a known bleeding disorder

61.3 Materials and Medications (Fig. 61.1)

- #11 scalpel
- 4×4 gauze
- Hemostat
- Penrose drain or ¼-inch packing gauze
- Light source (headlamp or overhead light)
- Culture swab
- 4-0 silk suture
- 25- to 27-gauge needle, 1.5–2 inches long
- 18-gauge needle to withdraw anesthetic from vial
- 5-mL syringe
- Viscous lidocaine or other topical anesthetic
- Lidocaine with epinephrine
- Suction setup with Frazier or tonsil suction tip

M.W. Fernandez, MD
Department of Emergency Medicine,
University of Florida Health, Gainesville, FL, USA
e-mail: mindyfernandez@ufl.edu

B.K. Desai, MD (✉)
Department of Emergency Medicine, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: bdesai@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_61


MULTIPLE-DOSE
LIDOCAINE VISCOUS
PEEL
10ml
5-0 (1.5 metric)
18" (45 cm)
Conventional Cutting
PC-1
MultiPass
FAST ABSORBING
PLAIN GUT
1915
ETHICON

Fig. 61.1 Materials needed: #11 scalpel, hemostats, Penrose drain, 4-0 silk suture, 25- to 27-gauge 1.5-inch needle for injecting anesthetic, 18- to 20-gauge needle for drawing up anesthetic, 5- to 10-mL syringe or control syringe, viscous lidocaine (or other topical anesthetic), lidocaine 1 % with epinephrine, light source, suction setup with tonsil suction tip, culture swab (optional)

61.4 Procedure (Figs. 61.2 and 61.3)

1. After explaining the procedure, risks, and benefits to the patient, put the head of the bed in the most comfortable working position for the operator and the patient. Alternatively, position the patient in an upright procedure chair that has multiple positions.
2. Find the most fluctuant area. Apply viscous lidocaine topically with a cotton-tipped swab to the area to be injected with anesthetic. Leave in place for a minute or 2. Alternatively, spray the area with a topical anesthetic spray.
3. Have suction setup with a tonsil tip, available, and turned on.
4. Draw up the appropriate amount of lidocaine with epinephrine into a 5-mL syringe (control syringe if available).
5. Direct light source to area to be worked on. *Adequate lighting is essential.* Options include a headlamp or an overhead adjustable light.
6. Change needle to a 25- or 27-gauge needle. Inject 1–2 mL of lidocaine with epinephrine just beneath the mucosal surface. Avoid injecting through infected tissue to avoid possible spread into deeper spaces.
7. Using the scalpel, make an intraoral stab incision superficially into the area of greatest fluctuance (Fig. 61.4). Have the suction catheter in the patient's mouth and allow the purulent material to drain into the suction.
8. Obtain a specimen of the purulent fluid for culture and sensitivity.
9. Insert a hemostat into the incision to facilitate drainage, but do not open it up in order to avoid injury to neurovascular structures. Gently massage the soft tissue surrounding the abscess to assist drainage. Suction as necessary to avoid swallowing or aspirating the pus.
10. Have the patient rinse and spit with a half-strength peroxide solution.
11. Place a small Penrose drain (or other rubber-type drain) into the cavity, and stabilize on one side with a silk suture that goes through the drain and the mucosa. Alternatively, cut a strip of ¼- inch packing gauze and insert into the abscess cavity.
12. Have the patient rinse and spit with a half-strength peroxide solution followed by either water or saline.
13. Watch for signs of bleeding or upper airway symptoms.
14. Ensure that the patient can tolerate oral fluids before discharge.



Fig. 61.2 Anatomy of the salivary glands



Fig. 61.3 Parotid papilla: opening of the parotid gland located adjacent to third upper molar



Fig. 61.4 Parotid abscess; make a superficial stab into most fluctuant area

61.5 Complications

- Complications are generally minimal but may include:
  - Excessive bleeding (apply pressure; to avoid potential nerve injury, do not cauterize or ligate unless absolutely necessary)
  - Aspiration of purulent material (have the patient sit upright and use suction as the abscess is incised)
  - Pain

61.6 Pearls and Pitfalls

- Airway protection should always be considered.
- Empirical oral antibiotics after incision and drainage are considered usual care and should cover for group A streptococcal and oral anaerobes. Penicillin remains the drug of choice, but clindamycin or amoxicillin–clavulanic acid can be substituted.
- Patients who cannot tolerate oral medications, cannot take oral antibiotics, or who appear to have a toxic response should be admitted. Pediatric patients should be admitted. Others may be discharged with 24-h follow-up.

Selected Reading

Reichman E, Simon R, editors. Emergency medicine procedures. New York: McGraw-Hill Education; 2003. p. 1346–9.

Roberts J, Hedges J, editors. Clinical procedures in emergency medicine. 5th ed. Philadelphia: Saunders; 2009. p. 1184–9.

Part IX

Dental Procedures

62

Techniques of Mandibular Anesthesia

Susana Perry, Joshua Perry, and Rosalia Rey

62.1 Inferior Alveolar Nerve Block

62.1.1 Nerves Anesthetized

- Inferior alveolar, branch of the posterior division of the mandibular nerve (V3, branch of the trigeminal nerve)
- Incisive
- Mental
- Lingual (usually)

62.1.2 Areas Anesthetized (Fig. 62.1)

- Mandibular teeth to midline
- Body of the mandible
- Buccal mucoperiosteum, mucous membrane anterior to the mandibular first molar
- Anterior two thirds of the tongue and floor of the mouth (via the lingual nerve)
- Lingual soft tissues and periosteum (via the lingual nerve)

S. Perry, DMD (✉)
Department of Pediatric Dentistry, University of Florida College of Dentistry, University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: sperry@dental.ufl.edu

J. Perry, DMD
Department of Prosthodontics, University of Florida College of Dentistry, University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: jperry@dental.ufl.edu

R. Rey, DDS
Department of Restorative Dental Sciences, University of Florida College of Dentistry, University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: RREY@dental.ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_62



Fig. 62.1 Areas anesthetized with inferior mandibular nerve block

62.1.3 Indications

- When buccal soft tissue anesthesia is necessary
- When lingual soft tissue anesthesia is needed
- When performing procedures on multiple mandibular teeth in one quadrant

62.1.4 Contraindications

- Infection or acute inflammation in the area of injection
- Patients who might bite their lip or tongue (e.g., very young child or physically or mentally handicapped adult or child)
- In relation to local anesthetic use

Absolute

- Local anesthetic allergy
  - Avoid all local anesthetics in the same chemical class (e.g., esters).
- Bisulfite allergy
  - Avoid vasoconstrictor-containing local anesthetics.

Relative

- Atypical plasma cholinesterase
- Methemoglobinemia (idiopathic or congenital)
- Significant liver dysfunction (American Society of Anesthesiologists [ASA] III–IV)
- Significant kidney dysfunction (ASA III–IV)
- Significant cardiovascular disease (ASA III–IV)
  - Avoid high concentrations of vasoconstrictors.
  - Use local anesthetics with epinephrine concentrations of 1:200,000 or 1:100,000 or 3 % mepivacaine or 4 % prilocaine.
- Clinical hyperthyroidism (ASA III–IV)
  - Avoid high concentrations of vasoconstrictors.
  - Use local anesthetics with epinephrine concentrations of 1:200,000 or 1:100,000 or 3 % mepivacaine or 4 % prilocaine.

62.1.5 Materials and Medications

- Local anesthetic carpule (1.7–1.8 mL)
  - Mepivacaine 3 % (+epinephrine 1:100,000)
  - Articaine HCI 4 % (+epinephrine 1:100,000 or 1:200,000)
  - Lidocaine HCI 2 % (+ epinephrine 1:50,000 or 1:100,000) (Fig. 62.2)
  - Bupivacaine HCI 0.5 % + epinephrine 1:200,000
- Aspirating syringe (Fig. 62.3)
- Needle (Fig. 62.4)
  - Gauge refers to the lumen of the needle: The smaller the number, the greater the diameter of the lumen.
  - Needles are color coded by gauge: red = 25 gauge, yellow = 27 gauge, and blue = 30 gauge.
  - *Recommendations: For inferior alveolar nerve (IAN) block, it is best to use a 25-gauge long needle.*
- Mouth props
- Retractors


Plunger indented from rim of glass
Drug-identifying color-coded band
Aluminum cap
Silicon rubber plunger
Neck
Rubber diaphragm

Fig. 62.2 Local anesthetic carpule (1.7–1.8 mL)



Fig. 62.3 Aspirating syringe


Bevel
Shaft
Hub
Syringe adaptor
Cartridge-penetration end

Fig. 62.4 Needle

62.1.6 Procedure

1. Target area: IAN as it passes downward toward the mandibular foramen.
2. Landmarks.
   - (a) Coronoid notch
   - (b) Pterygomandibular raphe
   - (c) Occlusal plane of mandibular posterior teeth
3. Procedure.
   - (a) Correct position for operator.
     - (i) For a right IAN block, a right-handed administrator should sit at the 8 o'clock position facing the patient.
     - (ii) For a left IAN block, a right-handed administrator should sit at the 10 o'clock position facing in the same direction as the patient.
   - (b) Recommended to position the patient supine and with the mouth wide open.
   - (c) Place thumb on the coronoid notch and index finger extraorally on the posterior border of the ramus in order to estimate the distance between these two points (Fig. 62.5).
     - (i) The needle insertion should be three fourths of the anteroposterior distance from the coronoid notch to the deepest part of the pterygomandibular raphe.
   - (d) Place the barrel of the syringe in the corner of the mouth on the contralateral side, usually corresponding to the premolars.
   - (e) Slowly advance the needle until bony resistance is met.
     - (i) For anxious or sensitive patients, a small volume of anesthetic may be deposited as the soft tissue is penetrated.
     - (ii) Average depth of penetration to bony contact will be 20–25 mm, approximately two thirds to three fourths the length of a long needle.
     - (iii) If the bone is contacted too soon (less than half the length of a long needle), the needle tip is usually located too far anteriorly (laterally) on the ramus. To correct:
       - Withdraw it slightly from the tissues and bring the syringe barrel anteriorly toward the lateral incisor or canine; reinsert to the proper depth.
     - (iv) If the bone is not contacted, the needle tip is usually located too far posterior (medial). To correct:
       - Withdraw it slightly in tissue (leaving approximately one fourth its length in tissue), and reposition the syringe barrel more posteriorly (over the mandibular molars).
       - Continue the insertion until contact with the bone is made at an appropriate depth (20–25 mm).
   - (f) Aspirate. If negative, slowly deposit 1.5 mL of anesthesia over 60 s.
   - (g) Wait 3–5 min before commencing the dental procedure.
4. Precaution: *Do not deposit anesthesia if the bone is not contacted*. The needle tip may be resting within the parotid gland near the facial nerve (cranial nerve VII), and a transient paralysis of the facial never may occur if solution is deposited.



Fig. 62.5 Needle orientation for inferior alveolar nerve block

62.2 Buccal Nerve Block

62.2.1 Nerve Anesthetized

- Buccal nerve, a branch of the anterior division of the mandibular nerve

62.2.2 Area Anesthetized (Fig. 62.6)

- Soft tissues and periosteum buccal to the mandibular molars


Lingual soft tissue and bone
Tongue
Alveolar mucous membrane
Mental foramen
Extraoral soft tissue

Fig. 62.6 Areas anesthetized with buccal nerve block

62.2.3 Procedure

1. A 25-gauge long needle is recommended.
2. Landmarks: mandibular molars and mucobuccal fold.
3. Orient the bevel of the needle *toward* the bone during injection.
4. Correct positioning.
    (a) For a right buccal nerve block, a right-handed administrator should sit at the 8 o'clock position directly facing the patient.
    (b) For a left buccal nerve block, a right-handed administrator should sit at the 10 o'clock facing in the same direction as the patient.
5. Procedure.
    (a) With the index finger, pull the buccal soft tissues in the area of injection laterally to allow for better visualization.
    (b) Align the syringe parallel to the occlusal plane of the teeth.
    (c) Penetrate the mucous membrane at the injection site, distal and buccal to the last molar (Fig. 62.7).
6. If tissue at the injection site becomes swollen, stop depositing solution.



Fig. 62.7 Needle orientation for buccal nerve block

62.3 Mental Nerve Block

62.3.1 Nerve Anesthetized

- Mental nerve, a terminal branch of the inferior alveolar nerve

62.3.2 Area Anesthetized (Fig. 62.8)

- Buccal mucous membranes anterior to the foramen (around the second premolar) to the midline and skin of the lower lip


Lingual soft tissue and bone
Tongue
Alveolar mucous membrane
Mental foramen
Extraoral soft tissue

Fig. 62.8 Areas anesthetized with mental nerve block

62.3.3 Indications

- For buccal soft tissue anesthesia in procedures such as:
  - Soft tissue biopsies
  - Suturing of soft tissues

62.3.4 Procedure

1. Area of insertion: mucobuccal fold at or just anterior to the mental foramen.
2. Orientation of bevel should be *toward* the bone during injection.
3. Operator should sit in front of the patient so that the syringe is below the patient's line of sight.
4. Locate the mental foramen.
   (a) Place the index finger in the mucobuccal fold and press against the body of the mandible in the area of the first molar.
   (b) Move the finger anteriorly until the bone beneath the finger feels somewhat concave.
   (c) Mental foramen is usually found around the apex of the second premolar.
   (d) Orient the needle with the bevel directed toward the bone.
   (e) Penetrate the mucous membrane and advance needle slowly; penetration depth is usually 5–6 mm.
   (f) If aspiration is negative, deposit approximately one third of the cartridge over 20 s.
      (i) If the site balloons, stop the deposition of anesthetic and remove the syringe.

Selected Reading

Bennett CR. Monheim's local anesthesia and pain control in dental practice. 6th ed. St. Louis: Mosby; 1978.

Gow-Gates GAE. Mandibular conduction anesthesia: a new technique using extraoral landmarks. Oral Surg. 1973;36:321–8.

Jastak JT, Yagiela JA, Donaldson D. Local anesthesia of the oral cavity. Philadelphia: WB Saunders; 1995.

Malamed SF. The Gow-Gates mandibular block: evaluation after 4275 cases. Oral Surg. 1981;51:463.

Malamed SF. Handbook of local anesthesia. 5th ed. St. Louis: Mosby; 2004.

Reduction of Dislocated Temporomandibular Joint

63

Christopher J. Spencer and Geraldine Weinstein

63.1 Indications

- Open lock: associated with yawning, vomiting, or opening the mouth wide
- Open lock: associated with a dental procedure
- Open lock: associated with endoscopy
- Open lock: associated with oral intubation
- Time duration: acute to 3 weeks or less duration

63.2 Contraindications for Closed Reduction

- Absolute
  - Head trauma with fracture of the skull, maxilla, mandible, or mandibular
    Condyles
- Relative
  - Dislocation of 30 days or longer (will likely be unable to accomplish reduction without general anesthesia and/or open surgical approach)

63.3 Materials and Medications

- Local anesthetic syringe.
- Lidocaine 2 % 1–2 mL.
- 25- to 27-gauge needle (long or approximately 2 inches long).
- Betadine (povidone-iodine) or other skin antiseptic preparation.
- Gauze padding for thumbs.
- Consider a muscle relaxant.
- Consider conscious sedation.

C.J. Spencer, DDS • G. Weinstein, DDS (✉)
Department of Restorative Dental Sciences, University of Florida
College of Dentistry, Gainesville, FL, USA
e-mail: cspencer@dental.ufl.edu; gweinstein@dental.ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_63

63.4 Procedure

63.4.1 Manual Closed Reduction *without* Local Anesthesia (Figs. 63.1)

1. Position the patient in an upright posture with the mandible at the physician's flexed elbow height (physician's comfortable position).
2. Place the thumbs on the mandibular molars with wrapping around the thumbs to protect from possible biting force once the mandible reduces.
3. Apply bilateral firm force in an inferior direction.
4. The mandible will move rapidly in an inferior and then a posterior direction as the condyles slide back over the height of their respective articular eminences.



Fig. 63.1 Reduction in progress: (**a**) In a mandibular dislocation, the condyle will be anterior and superior to the articular eminence. (**b**) Position the thumbs on mandibular molars, and apply firm pressure in an inferior direction to distract the TM joint condyles so that they can reposition themselves into the glenoid fossa so that the TM joint can be reduced. (**c**) Lateral view of the distraction force with direction in an inferior direction to distract the condyle of the TM joint

63.4.2 Manual Closed Reduction *with* Local Anesthesia

- If the mandible will not respond to closed reduction with just thumb pressure, likely the masticatory muscles are contracting with sufficient force to prohibit the condyles from being sufficiently distracted owing to pain.
  1. Reduction of pain in the temporomandibular joint (TMJ) with local anesthesia.
  2. *Auriculotemporal block of V3:*
     - The auriculotemporal nerve that innervates the TMJ may be anesthetized inferior to the TMJ capsule. It can be accessed through the skin just anterior to the tragus.
     - With the patient's mouth wide open (it already is in this case), a triangular-shaped hollow will be evident inferior and posterior to the mandibular condyle. Insert the needle at a 20-degree anterior inclination, in the horizontal plane, at the level of the inferior border of the tragus of the ear (Fig. 63.2). The bevel of the needle should be anterior.
     - The needle should be inserted behind the (posterior) ramus and approximately 2 cm deep (aiming for the medial aspect of the posterior border of the ramus). If the posterior border of the ramus is contacted, the needle will need to be directed in a more posterior direction. Then deposit 1–2 mL of lidocaine 2 %.
  3. Then, as before, place the thumbs in a bilateral position on the patient's mandibular molars, and depress the mandible to distract the condyles in an inferior direction.
  4. Conscious sedation may be utilized if the reduction procedure has been arduous and stressful for the patient.



Fig. 63.2 Infiltration of cranial nerve V, the auriculotemporal branch (V3)

63.5 Complications

- Inability to reduce the condyles manually which may lead to more invasive procedures.
- If the condition is acute (≤24 h) and not associated with trauma, there are few if any significant complications or risks for this procedure.

63.6 Pearls

- The manual pressure required on the mandibular molars needs to be sustained and very firm.
- If both condyles are dislocated, it is likely beneficial to attempt one side at a time.
- The clinician needs to protect the thumbs from the impact of the patient's molars during the sudden successful reduction because the biting forces are significant in the molar region.

Selected Reading

Chan TC, Harrigan RA, Ufberg J, Vilke GM. Mandibular reduction. J Emerg Med. 2008;34:435.

Donlon WC, Truta MP, Eversole LR. A modified auriculotemporal nerve block for regional anesthesia of the temporomandibular joint. J Oral Maxillofac Surg. 1984;42:544.

Huang IY, Chen CM, Kao YH, Chen CM, Wu CW. Management of long-standing mandibular dislocation. Int J Oral Maxillofac Surg. 2011;40:810–4.

Prabhakar V, Singla S. Bilateral antersuperior dislocation of the intact mandibular condyles in the temporal fossa. Int J Oral Maxillofac Surg. 2011;40:640–3.

Thagarajah T, Mcculloch N, Thangarajah S, Stocker J. Bilateral temporomandibular joint dislocation in a 29-year-old man: a case report. J Med Case Rep. 2010;4:263.

Dry Socket (Alveolar Osteitis, Fibrinolytic Osteitis)

64

Michael A. Abraham, Amir Azari, Jennifer Westcott,
and Franci Stavropoulos

64.1 Indications (Fig. 64.1)

- Definition: severe pain occurring 2–3 days after tooth extraction
- Recent tooth extraction, especially of a mandibular tooth or an impacted third molar
- Partially or completely visible bone socket
- Intense radiating pain (often to the ear)
- Fetid odor without suppuration
- Absence of swelling, lymphadenitis, or bacteremia
- Foreign bodies present in the extraction socket



Fig. 64.1 Clinical photograph suggestive of a dry socket. Clinical correlation is necessary

---

M.A. Abraham, DMD (✉)
United States Air Force, Dental Corps, Minot, ND, USA
e-mail: mikeabrahamdmd@gmail.com

A. Azari, DMD
Department of Oral and Maxillofacial Surgery, Oregon Health and Science University, Portland, OR, USA
e-mail: Azari@OHSU.edu

J. Westcott, DMD
Private Practice, Palm Beach Gardens, FL, USA
e-mail: Jwestcott561@gmail.com

F. Stavropoulos, DDS
Department of Dental Specialties – Oral and Maxillofacial Surgery, Gundersen Health System, La Crosse, WI, USA
e-mail: Mfstavro@gundersenhealth.org

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_64

64.2 Contraindications

- Absolute
  - Osteomyelitis
  - Jaw fracture
- Relative
  - Retained roots
  - Infection

64.3 Materials and Medications

- Warm saline or 0.12 % aqueous chlorhexidine solution
- 12-mL syringe with curved tip (Monoject® syringe)
- 25-gauge needle, syringe
- Local anesthetic, 2 % lidocaine 1:100,000 epinephrine
- Suction with small tip or gauze
- Socket dressing
  - Gelfoam or small gauze strips
- Socket medicament
  - Sultan dry socket paste® (guaiacol, balsam of Peru, eugenol, 1.6 % chlorobutanol), iodoform, or eugenol® (zinc oxide eugenol dental cement)
- Curved forceps

64.4 Procedure

1. Administer local anesthesia as necessary.
2. Remove any sutures closing the extraction site.
3. Irrigate the wound gently with warm saline or 0.12 % aqueous chlorhexidine.
4. Carefully suction or gently dry any excess saline; the socket area should be isolated from saliva by using gauze or cotton rolls.
5. Gently place iodoform-soaked gauze, Gelfoam soaked in eugenol, or Sultan dry socket paste in the extraction socket with forceps/Monoject syringe.
6. Rinse with saline and replace the dressing as needed for the first 2–3 days and every 2–3 days thereafter.
7. Remove the dressing, if it does not dissolve, without replacement once the pain has resolved.
8. Pain medication (nonsteroidal anti-inflammatory drugs [NSAIDS] or narcotics) should be prescribed if necessary.
9. Follow-up with dentist.

64.5 Complications

- Delayed healing
- Wound dehiscence

64.6 Pearls and Pitfalls

- *Pearls*
  - Wound irrigation may be so painful at the first visit that administration of a local anesthetic without a vasoconstrictor should be considered.
  - The patient should experience profound pain relief within minutes of placement of the soaked medicated dressing.
  - If a medicated dressing is necessary for more than 2 weeks, reevaluate for development of osteomyelitis.
  - "Dry socket" is not a progressive disease but may persist for 10–14 days whether treated or not; therapy is palliative.
  - Instruct the patient to avoid the following, which can cause changes of pressure in the mouth:
    - Smoking
    - Using a straw
    - Spitting
    - Drinking carbonated beverages (e.g., soda, seltzer water, beer)
- *Pitfalls*
  - Avoid over manipulating the socket because this will increase the amount of exposed bone and pain.

Selected Reading

Bloomquist D, Hooley J, Whitacre R. A self-instructional guide: surgical complications. 3rd ed. Seattle: Stroma; 1983.

Matocha DL. Postsurgical complications. Emerg Med Clin North Am. 2000;18:549–64.

Roberts G, Scully C, Shotts R. Dental emergencies. West J Med. 2001;175:51.

Postextraction Hemorrhage

65

Michael A. Abraham, Amir Azari, Jennifer Westcott, and Franci Stavropoulos

65.1 Indications

- Recent tooth extraction site, presenting with more than a slight oozing of blood
- Full evaluation indicating amount of blood loss, present physical condition, and reason for hemorrhage including coagulopathy or medication use

65.2 Contraindications

- Absolute
  - None
- Relative
  - None

65.3 Materials and Medications

- 2×2 gauze pad
- Saline
- 25-gauge needle, syringe
- Local anesthetic without vasoconstrictor—2 % lidocaine plain
- Gelfoam® (absorbable gelatin-compressed sponge) or oxidized cellulose
- Topical thrombin
- Suture kit with 3-0 chromic gut suture or 3-0 Vicryl® suture (synthetic absorbable sterile surgical suture composed of a copolymer made from 90 % glycolide and 10 % L-lactide)
- Hemostat

65.4 Procedure

1. Use suction and saline irrigation to gently rinse the affected area. If a "liver" clot is present, irrigate and remove it with suction.
2. Determine the source of hemorrhage without local anesthesia, if possible, because the use of local anesthetic with an added vasoconstrictor may obscure bleeding sites.
3. Moisten a folded 2×2 gauze pad with saline and place it directly onto the extraction site.
4. Instruct the patient to apply firm biting pressure, and observe for 1 h, changing gauze as necessary.
5. If bleeding persists, an intraoral nerve block should be performed.
   - Blocks are preferred to infiltrations; anesthetic with epinephrine infiltrated near the bleeding site will produce only temporary local hemostasis from vasoconstriction.
6. Gently curette the tooth extraction socket and remove areas of old blood clot or granulation tissue.
7. Check soft tissue for associated arterial bleeding.
   - If hemorrhage is localized to soft tissue, use pressure or tie off vessels.
8. Fold Gelfoam® into a small cylinder to fit into the extraction socket.
9. Place Gelfoam® with topical thrombin or Surgicel® (absorbable hemostat) into the socket and hold in

---

M.A. Abraham, DMD (✉)
United States Air Force, Dental Corps, Minot, ND, USA
e-mail: mikeabrahamdmd@gmail.com

A. Azari, DMD
Department of Oral and Maxillofacial Surgery, Oregon Health and Science University, Portland, OR, USA
e-mail: Azari@OHSU.edu

J. Westcott, DMD
Private Practice, Palm Beach Gardens, FL, USA
e-mail: Jwestcott561@gmail.com

F. Stavropoulos, DDS
Department of Dental Specialties – Oral and Maxillofacial Surgery, Gundersen Health System, La Crosse, WI, USA
e-mail: Mfstavro@gundersenhealth.org

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_65

position with a figure-of-eight stitch using 3-0 chromic gut suture or 3-0 Vicryl suture (Figs. 65.1 and 65.2).

10. Fold 2×2 gauze, moisten it with saline, and place it over the suture.
11. Instruct the patient to bite down with firm pressure for 30 min; repeat as necessary.
12. Follow-up with dentist.



Fig. 65.1 A resorbable figure-of-eight suture placed over an extraction socket



Fig. 65.2 Gelfoam® (absorbable gelatin-compressed sponge) being placed into the extraction socket (Photograph courtesy of Dr. Michael Abraham)

65.5 Complications

- Continued bleeding due to lack of patient compliance.
- Continued bleeding due to coagulopathy or medication use.
- If bleeding persists and coagulopathy is identified, the administration of intravenous blood replacement products may be necessary.

65.6 Pearls and Pitfalls

- Pearls
  - Minor bleeding concerns may be addressed at home by instructing the patient to bite on the affected area with a tea bag for 30 min (tannic acid in tea is a vasoconstrictor).
  - It is normal for an extraction socket to ooze slight amounts of blood for 12–24 h; it is normal for patients to see some blood on their pillow after waking.
  - The patient should be instructed to avoid the following, which can cause changes of pressure in the mouth:
    - Smoking
    - Using a straw
    - Spitting
    - Drinking carbonated beverages (e.g., soda, seltzer water, beer)
- Pitfalls
  - Small amounts of blood mixed with saliva may deceptively appear as large amounts of blood.

Selected Reading

Bloomquist D, Hooley J, Whitacre R. A self-instructional guide: surgical complications. Seattle: Stroma; 1983. pp. 50–5.

Hupp JR, Ellis III E, Tucker MR, editors. Contemporary oral and maxillofacial surgery. 5th ed. St. Louis: Mosby Elsevier; 2008. p. 195–7.

Fractured Tooth

66

Geraldine Weinstein

66.1 Indications (Fig. 66.1)

- Temporary repair of an acute dental fracture until follow-up by a dentist can be secured.



Fig. 66.1 Examples of fractured teeth

66.2 Methods of Sustaining Dental Fracture

- Traumatic injury to the head/facial area
- Falling down
- Extensive tooth decay that has undermined the integrity of the tooth structure
- Biting down on something hard

G. Weinstein, DDS
Department of Restorative Dental Sciences,
University of Florida College of Dentistry,
Gainesville, FL, USA
e-mail: gweinstein@dental.ufl.edu

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_66

66.3 Four Types of Fractured Tooth (Fig. 66.2)

- *Type 1*: contained to the enamel of the tooth, asymptomatic, and can be treated easily with a composite filling by a dentist.
- *Type 2*: involves a fracture through the dentin layer of the tooth. The patient may experience some sensitivity to temperature changes and chewing. Depending on the severity, treatment may include a root canal and a restoration by a dentist.
- *Type 3*: involves the pulp of the tooth and will require endodontic treatment by a dentist.
- *Type 4*: a root fracture in the tooth that makes it nonrestorable and requiring extraction. It is diagnosed by means of a periapical radiograph taken in a dental office.


Crown
Neck
Roots
Jawbone
Enamel
Pulp (contains nerves and blood vessels)
Gums
Dentin
Cementum
Periodontal ligaments

Fig. 66.2 Anatomy of a tooth

66.4 Contraindications

- *Relative*
  - Patients at high risk of aspiration owing to intoxication and altered mental status

66.5 Materials and Medications

- Warm saline or 0.12 % aqueous chlorhexidine solution for irrigation of tissues and tooth
- Irrigating syringe
- Suction with a small tip
- Gauze to control hemorrhage
- Resorbable sutures and local anesthetic as needed for soft tissue lacerations
- Temporary tooth restoration material like intermediate restorative material (IRM) and glass ionomer (like Fuji)

66.6 Procedure

1. Have the patient rinse the mouth out with warm water to clean out any debris. Apply an ice pack to the affected cheek to reduce swelling.
2. Anesthetize the area, either locally at the tooth apex or with a nerve block (mental or inferior alveolar).
3. Irrigate the area; assess the fracture intraorally and check for soft tissue lacerations. Use the gauze with finger pressure to control bleeding in the soft tissue or the tooth.
4. Check if the tooth or bony segment is mobile. If so, a referral to a dentist or oral surgeon is necessary as soon as possible for proper assessment.
5. Type II fractures (fracture limited to dentin layer): cover the exposed surface with a temporary dental cement. In a pinch, 2-octyl cyanoacrylate (Dermabond) is an acceptable secondary alternative (Fig. 66.3).
6. Type III (pulp involved)
   - Provide immediate dental follow-up and analgesics.
   - Initiate antibiotic coverage with penicillin or clindamycin.

50% MORE
Than Other Brands
12+ REPAIRS
net wt. 2.64 g (0.09 oz)
Repair
Lost Fillings & Loose Caps
DenTek
Temparin Max
One Step
Formula
MAXIMUM STRENGTH
Dentist Recommended
Instant Pain Relief
Easy To Apply
NEW!
Applicator Tip
Spade Tool
DenTek

Fig. 66.3 Example of temporary dental cement (Reproduced with permission from DenTek Oral Care, Inc.)

66.7 Complications

- Loss of a tooth
- Infection or abscess
- Aspiration of a segment or a whole tooth
- Cosmetic deformity

66.8 Pearls

- Be certain to perform a thorough intraoral examination, looking for tooth fragments or lacerations that may be hiding fragments.
- Dental blocks are very useful for pain control.
- If a tooth is not mobile and the *pulp is exposed*, immediate referral (within a few hours) to a dentist is necessary for extraction or endodontic (root canal) treatment of the tooth. Placement of a temporary-type restoration on this tooth is *not* recommended at this time because it may exacerbate symptoms. Prescribe pain medication and possibly antibiotics when the tooth's pulp is exposed and the patient is unable to see the dentist within 24 h.
- If the tooth is not mobile and *the pulp is not exposed*, a temporary restoration can be placed on the tooth and the patient referred to a dentist for treatment. The fractured part of the tooth should be saved in the event that it can be used. If temporary tooth restoration is unavailable in the emergency department, advise the patient that it is readily available at local pharmacies.
- ALL DENTAL FRACTURES, EXCEPT TYPE I, REQUIRE DENTAL FOLLOW-UP WITHIN 24 h.

Dental Avulsion Management

67

Laura Tucker and Abimbola O. Adewumi

67.1 Indications

- The tooth is completely displaced *out* of its socket, leading to severance of the neurovascular pulp supply and separation of the periodontal ligament (Fig. 67.1).
- Diagnosis
  - Clinically, the socket is found empty or filled with coagulum.
  - Imaging (occlusal, periapical, and lateral views of the affected tooth and surrounding area) (Fig. 67.2):
- Confirm vacuous socket.
- Ensure that the missing tooth is not intruded.
- Diagnose root fracture or alveolar fracture.



Fig. 67.1 (**a**, **b**) Empty socket following traumatic dental avulsion

---

L. Tucker, DDS • A.O. Adewumi, BDS, FDSR (✉)
Department of Pediatric Dentistry, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: lauragracesullivan@gmail.com; aadewumi@dental.ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_67



Fig. 67.2 Lower occlusal radiograph shows a complete avulsion of the mandibular right and left central incisors

67.2 Contraindications

- Absolute
  - Avulsed tooth is a primary tooth.
    - DO NOT REPLANT OR REPOSITION AVULSED PRIMARY TEETH.
    - Replantation of primary teeth increases the potential for damage to the developing permanent tooth owing to the increased frequency of pulpal necrosis.
- Relative
  - Fractured root (further intervention required before replantation)
  - Alveolar fracture (further intervention required before replantation)
  - Prolonged extraoral dry time and out of compatible solution (>1 h)
  - Immunocompromised host or congenital heart disease
  - Severe seizure disorder that may put tooth at risk for coming out while the airway is compromised
  - Patient with potential to lose airway reflexes

67.3 Materials and Medications

- Hank's Balanced Salt (Save-A-Tooth) solution or milk in which to preserve tooth until it can be replanted
  - Normal saline if neither of those is available
- Normal saline rinse
- 20- or 18-gauge cannula for gentle irrigation of the socket
- Absorbable suture for gingival lacerations, if present
- Flexible splint materials
  - Round dental wire
  - A flat pliable metal long enough to cover the affected tooth and the two teeth on other side (e.g., the metal nasal bridge from a respirator mask)
- Fixative
  - Dental adhesive
  - Dermabond or some other brand of cyanoacrylate for adhesive skin closures

67.4 Procedure

1. Be certain the tooth is a permanent one and not a primary tooth.
2. If not done by the patient, gently wash the tooth under water for approximately 10 s.
    - Be certain to hold the tooth by the crown, not the root (Fig. 67.3)
3. If the tooth cannot be replanted immediately, place the tooth in Hank's solution or milk.
4. If no such media is available, instruct the patient to hold the tooth inside his or her mouth between the cheek and the gums.
5. Gently replant the tooth, using digital pressure only into as anatomical a position as possible (Fig. 67.4).
    - Assess clinically for alignment.
    - Radiograph for confirmation.
6. Suture any gingival lacerations if present.
7. Apply a flexible splint, securing the affected tooth to the teeth on either side.
    - Consider using skin adhesive both to secure the tooth to its neighbors and, perhaps, to apply a makeshift splint until the patient can be seen by her or his dentist.
        - Towel dry the teeth as best as possible.
        - Apply skin adhesive (using the standard applicator) to the lateral edges of the avulsed tooth where it will make contact with its adjacent teeth.
        - If dental wire is available, apply adhesive to the buccal surfaces of the three teeth (the avulsed tooth central to the other two) and apply length of metal to the Fixodent (Fig. 67.5).
8. Systemic antibiotics with anaerobic coverage is empirical.
9. Ascertain tetanus status for the patient; update if uncertain.



Fig. 67.3 Proper way to hold an avulsed tooth



Fig. 67.4 Gentle replantation using digital pressure



Fig. 67.5 (**a**, **b**) Splint stabilization

67.5 Complications

- Primary teeth
  - Dilaceration (bend) in the permanent tooth crown
  - Enamel defect of the lower permanent incisors as a result of avulsion of the preceding primary tooth
- Permanent teeth
  - Discoloration as a result of loss of vitality of the avulsed tooth.
  - Ankylosis of the alveolar ridge, leading to functional and aesthetic changes.
  - Replacement resorption occurs when the replanted tooth is slowly replaced with bone.
  - External inflammatory resorption is a progressive loss of tooth associated with destruction of adjacent alveolar bone.
  - Infection
  - Aspiration of an inadequately secured replanted tooth.

67.6 Pearls and Pitfalls

- Pearls
  - At the initial examination, make sure that all avulsed teeth are accounted for.
    - If not, a radiographic examination is necessary to ensure that the missing tooth is not completely intruded (pushed into the gum) or has sustained a root fracture with loss of the coronal fragment.
  - In children, always consider the likelihood of nonaccidental trauma (abuse).
  - Short-term and long-term dental follow-up cannot be emphasized enough.
- Pitfalls
  - If the avulsed tooth cannot be accounted for, aspiration is a possibility.
- Prognosis
  - Depends on extraoral dry time (length of time the tooth has been out of the mouth and not stored in an appropriate medium):
    - Ideally, tooth should be implanted within 5 min.
    - Extraoral dry time greater than 60 min has a poor prognosis for periodontal healing.
  - Depends on stage of root development of the avulsed tooth (Fig. 67.6)
- The more advanced the root development, the lower the probability of pulp healing and survival.



Fig. 67.6 The various stages of root development, from the less advanced (*open apex, left*) to the more advanced (*closed apex, right*)

Selected Reading

AAPD Council on Clinical Affairs. Guideline on management of acute dental trauma. AAPD reference manual. Chicago: American Academy of Pediatric Dentistry; 2010–2011. pp. 202–12.

Andreasen FM, Andreasen JO. Avulsions. In: Andreasen JO, Andreasen FM, Andersson L, editors. Textbook and color atlas of traumatic injuries to the teeth. 4th ed. Oxford: Blackwell; 2007. p. 444–88.

Andreasen JO, Jensen SS, Sae-Lim V. The role of antibiotics in preventing healing complications after traumatic dental injuries: a literature review. Endod Topic. 2006;14:80–92.

Finucane D, Kinirons MJ. External inflammatory and replacement resorption of luxated, and avulsed replanted permanent incisors: a review and case presentation. Dent Traumatol. 2003;19:170–4.

Flores MT, Andersson L, Andreasen JO, et al. Guidelines for the management of traumatic dental injuries. II. Avulsion of permanent teeth. Dent Traumatol. 2007;23:130–6.

Hile LM, Linklater DR. Use of 2-octyl cyanoacrylate for the repair of a fractured tooth. Ann Emerg Med. 2006;47:424–6.

The dental trauma guide. Available at: www.dentaltraumaguide.org.

Part X

Gastrointestinal Procedures

Excision of Thrombosed External Hemorrhoid

68

Latha Ganti

68.1 Indications

- Acute pain within 72 h of thrombosis onset
- The thrombosis will be visible as a bluish-purplish painful mass in perianal area (Fig. 68.1).



Fig. 68.1 Bluish-purplish appearance of an external thrombosed hemorrhoid. The *ellipse* denotes the area of the elliptical incision to be made (Reproduced with permission from: Fargo and Latimer [3])

L. Ganti, MD, MS, MBA
Professor of Emergency Medicine, University of Central Florida,
Orlando, FL, USA

Director, SE Specialty Care Centers of Innovation, Orlando
Veterans Affairs Medical Center, Orlando, FL, USA
e-mail: lathagantimd@gmail.com

68.2 Contraindications

- Absolute
  - Severe coagulopathy
  - Hemodynamic instability
  - Concurrent internal hemorrhoid with rectal prolapse
  - Painless rectal mass (external hemorrhoids are almost always painful, so a painless mass is not a thrombosed external hemorrhoid; also, the whole point of doing this procedure is to provide pain relief).
- Relative
  - Allergy to local anesthetics
  - Perianal infection
  - Inflammatory bowel disease
  - Serious systemic illness or comorbidity that could increase risk of procedure

68.3 Materials and Medications

- Sterile gloves and drape
- Alcohol swabs or pads
- 10 % povidone-iodine or chlorhexidine prep
- 2 % lidocaine with epinephrine
- 5 ml syringe with 25 or 27 gauge and 18 gauge needles
- #11 or #15 scalpel blade and handle
- Direct light source
- Forceps
- Iris scissors
- 4×4 gauze pads
- Adhesive tape
- 3-0 absorbable suture
- 1/4 inch iodoform packing
- Silver nitrate sticks
- Sterile dressing

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_68

68.4 Procedure

1. Patient should be in either prone, left lateral decubitus, or jackknife position (Fig. 68.2).
2. Place 2 vertically oriented pieces of tape down each buttock from lower back to upper thigh. Next, place a perpendicular (horizontal) strip spreading buttocks to either side, securing gurney (Fig. 68.3).
3. Place sterile drape over field and center direct lighting over field (Fig. 68.4).
4. Wipe area with alcohol.
5. Inject 1–2 cc of anesthetic into base of hemorrhoid.
6. Clean area with povidone-iodine or chlorhexidine prep.
7. Make an elliptical incision in the roof of the hemorrhoid, being careful to avoid anal sphincter muscle.
8. Remove blood clot(s); multiple clots are often present.
9. If profuse bleeding is a problem, consider cauterization with silver nitrate sticks.
10. Wound can be closed with figure-of-8 absorbable suture OR can be loosely packed with1/4 inch iodoform gauze if not suturing (do not suture wound closed with packing inside).
11. Cover wound with 4×4 gauze folded in half and taped into place (Fig. 68.5).

- Discharge medicines:
  - Antibiotics generally not necessary.
  - Prescribe ibuprofen and/or acetaminophen for analgesia. Avoid opiates, which are constipating.
  - Prescribe stool softeners, to be taken two to three times daily.
- Discharge instructions to patient:
  - Sitz baths 3–4 times daily, for 20 min, warm not hot water.
  - Packing should fall out spontaneously in 2 days.
  - Keep well hydrated.
  - Use gauze to protect underclothing from soilage/blood stains.
  - Return to ED if pain persists beyond 48 h.



Fig. 68.2 Jackknife position



Fig. 68.3 Taping of buttocks to maximize visualization of hemorrhoid



Fig. 68.5 Dress wound with sterile gauze



Fig. 68.4 Direct lighting over field

68.5 Complications

- Common
  - Bleeding: usually self-limited. Can apply cautery or figure-of-8 suture if not previously done
  - Pain: usually controlled with ibuprofen or acetaminophen
  - Perianal skin tag: benign
- Rare
  - Infection rate is 5 % [1].
  - Recurrence rate is 5–19 %, vs. 30 % for simple lancing [2].
  - Stricture and/or incontinence: prevented by avoiding underlying external anal sphincter muscle

68.6 Pearls and Pitfalls

- Pearls
  - Elliptical excision of the hemorrhoid results in much lower recurrence rate than simple lancing.
  - Risk factors for thrombosed external hemorrhoids include constipation, 2nd or 3rd trimester pregnancy, and traumatic vaginal delivery.
- Pitfalls
  - Excision of multiple hemorrhoids in circumferential fashion on all sides of the anal canal can cause anal stenosis.
  - Excision of a painless mass: if it is *painless*, it is *not* a thrombosed external hemorrhoid.

References

1. Lorber BW. Thrombosed external hemorrhoid excision. Medscape.com. www.emedicine.medscape.com/article/81039. Accessed 27 July 2014.
2. Rivadeneira DE. Outpatient and surgical procedures for hemorrhoids. UpToDate.com. http://www.uptodate.com/contents/outpatient-and-surgical-procedures-for-hemorrhoids. Accessed 27 July 2014.
3. Fargo MV, Latimer KM. Evaluation and management of common anorectal conditions. Am Fam Physician. 2012;85(6):624–30.

Selected Reading

Fargo MV, Latimer KM. Evaluation and management of common anorectal conditions. Am Fam Physician. 2012;85(6):624–30.

Jongen J, Bach S, Stübinger SH, Bock JU. Excision of thrombosed external hemorrhoid under local anesthesia: a retrospective evaluation of 340 patients. Dis Colon Rectum. 2003;46(9):1226–31.

Diagnostic Peritoneal Lavage

69

Latha Ganti

69.1 Indications (Table 69.1)

- Inability to perform FAST exam due to lack of equipment or operator
- Hemodynamically unstable patient in whom FAST exam is negative or equivocal

Table 69.1 Comparison parameters for DPL, FAST, and CT [1]

	DPL	FAST	CT
Speed	10–15 min	Fastest: <5 min	Variable
Repeatable	Yes, but rarely done	Yes, and frequently done	Yes, but not done often
Cost	$	$$	$$$
Invasive	Yes	No	No
Mobile	Yes	Yes	No
Advantages	Most sensitive for mesenteric and hollow viscus injuries	Highest specificity	Highly accurate but can be hampered by patient movement
Disadvantages	Misses retroperitoneal and diaphragm injuries	Hampered by subcutaneous or intra-abdominal air, obesity, and pelvic fractures Significant false-negative rate	Misses diaphragm, small bowel, and pancreatic injuries Small but significant risk of radiation-associated malignancy Cannot be done at bedside

---

L. Ganti, MD, MS, MBA
Professor of Emergency Medicine, University of Central Florida,
Orlando, FL, USA

Director, SE Specialty Care Centers of Innovation, Orlando
Veterans Affairs Medical Center, Orlando, FL, USA
e-mail: lathagantimd@gmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_69

69.2 Contraindications

- Absolute
  - Indication for laparotomy already exists.
- Relative
  - 2nd or 3rd trimester pregnancy
  - Previous lower abdominal surgery
  - Inexperienced operator
  - Abdominal wall infection
  - Coagulopathy
  - Cirrhosis
  - Morbid obesity

69.3 Materials and Medications

- 10 % povidone iodine prep
- 1 % lidocaine with epinephrine
- Fenestrated drape
- #10 scalpel blade and scalpel holder
- Skin retractors
- Hemostats
- Diagnostic peritoneal lavage (DPL) catheter (standard peritoneal dialysis catheter)
- 10 cc syringe
- Warmed lactated Ringer's or normal saline solution
- Skin stapler
- Simple suture tray with suture material

69.4 Procedure

69.4.1 Patient Preparation

- Place patient in supine position.
- Ensure nasogastric and urethral catheter (Foley) are in place.
- Prep and drape the area from the umbilicus to the symphysis pubis.
- Anesthetize the skin using 1 % lidocaine with epinephrine in the midline where incision will be made (Fig. 69.1).



Fig. 69.1 Anesthetize skin where incision will be made (supraumbilical incision shown here, can also make infraumbilical incision)

69.4.2 Three DPL Techniques

- Semiopen (Seldinger) technique
  1. Using a #10 scalpel blade, make a 2 cm incision either superior or inferior to the umbilicus.
  2. Dissect subcutaneous fat until linea alba is exposed.
  3. Hold incision open with skin retractors (Fig. 69.2).
  4. Grasp fascia with hemostats on either side of midline.
  5. Insert 18 gauge needle at 45° angle toward pelvis (Fig. 69.3).
  6. First "pop" will be heard once fascia is penetrated.
  7. Second "pop" will be heard once peritoneum is traversed.
  8. Pass guidewire through needle into pelvis (should pass easily without resistance).
  9. Remove needle while keeping wire stable.
  10. Pass dilator over the wire through fascia, and remove (Fig. 69.4).
  11. Slip DPL catheter over guidewire aiming toward pelvis.
  12. Aspirate peritoneal contents with syringe; aspiration of blood is a positive DPL and means immediate laparotomy (can stop DPL procedure here).
  13. If no blood is immediately obvious, then connect the DPL catheter to a liter of warmed lactated Ringer's (LR) or normal saline (NS) solution for lavage (ensure setup has no one-way valves as solution and peritoneal fluid need to be able to freely mix).
  14. Place LR or NS bag on floor once it is almost empty (minimum 300–350 ml for adults or 10–15 ml/kg for children) and allow intra-abdominal fluid to return (Fig. 69.5).
  15. Send fluid for analysis (Table 69.2).
  16. Irrigate wound, and close skin only with staples or sutures.
- Open technique
  1. Make a 5 cm incision inferior to the umbilicus over linea alba and directly visualize peritoneal cavity.
  2. Both fascia (absorbable suture) and skin (nonabsorbable suture) need to be closed.
- Closed technique
  1. Access peritoneal cavity via percutaneous needle access.
  2. No surgical closure required.



Fig. 69.2 Hold incision open with skin retractors



Fig. 69.3 Insert 18 gauge needle at 45° angle toward the pelvis



Fig. 69.4 Pass dilator over the wire through fascia and remove

Table 69.2 Diagnostic peritoneal lavage red blood cell criteria (per mm^3) [2]

	Positive	Indeterminate
Immediate gross return of blood via catheter	Any amount	
Immediate return of food particles/intestinal contents	Any amount	
Aspiration of blood	10 cc	
RBC in blunt trauma	100,000	20,000–100,000
RBC in penetrating trauma	10,000	5000–10,000
RBC in gunshot wound	5000	1000–5000
Amylase level (IU/L)	≥175	
Alkaline phosphatase level (IU/L)	≥3	
WBCs (per mm^3)	>500	250–500



Fig. 69.5 Lavage

69.5 Complications

- Wound infection or dehiscence
- Intraperitoneal injury to organs or vessels (iatrogenic hemoperitoneum)
- Unnecessary laparotomy due to false-positive result from bleeding within rectus sheath or from site of incision
- Potential failure to recover lavage fluid due to:
  - Inadvertent placement of the catheter into the preperitoneal space
  - Compartmentalization of fluid by adhesions
  - Obstruction of fluid outflow (e.g., by omentum)
  - Fluid pooling in the intrathoracic cavity due to diaphragmatic injury
- Incisional hernia

69.6 Pearls and Pitfalls

- Pearls
  - When properly done, complication rate for DPL is low.
  - Prophylactic antibiotics are generally not indicated.
- Pitfalls
  - Inadequate decompression of stomach and urinary bladder increases the chance of injury to these organs; thus, nasogastric and Foley decompression is an important step in patient preparation.

References

1. Jagminas L. Diagnostic peritoneal lavage. Medscape.com. http://emedicine.medscape.com/article/82888-overview#a17. Accessed 28 Aug 2014.
2. Marx JA. Diagnostic peritoneal lavage. In: Ivatury RR, Cayten CG, editors. The textbook of penetrating trauma. Baltimore: Williams & Wilkins; 1996. p. 337.

Selected Reading

Whitehouse JS, Weigelt JA. Diagnostic peritoneal lavage: a review of indications, technique, and interpretation. Scand J Trauma Resusc Emerg Med. 2009;17:13.

Manual Reduction of Abdominal Hernia

70

Latha Ganti

An abdominal wall hernia is a protrusion of the intestine through an opening or area of weakness in the abdominal wall. See Table 70.1 for types of abdominal hernias and Fig. 70.1 for locations along the abdominal anatomy.

Table 70.1 Types of abdominal hernias

Type	Defect	Most commonly seen in	Notes
Inguinal	Intestine or bladder protrudes through abdominal wall or into inguinal canal in the groin	Men because of a natural weakness in this area	96 % of all groin hernias are inguinal; 4 % are femoral
Femoral	Intestine enters canal carrying femoral artery into the upper thigh	Women, especially those who are pregnant or obese	
Incisional	Intestine pushes through abdominal wall at the site of previous abdominal surgery	Elderly or overweight people who are inactive after abdominal surgery	
Umbilical	Part of the small intestine passes through abdominal wall near the navel	Newborns and obese women or those who have had many children	In children, not repaired until age five because often resolve on their own
Hiatal	Upper stomach squeezes through hiatus, an opening in the diaphragm through which the esophagus passes		

L. Ganti, MD, MS, MBA
Professor of Emergency Medicine, University of Central Florida,
Orlando, FL, USA

Director, SE Specialty Care Centers of Innovation, Orlando
Veterans Affairs Medical Center, Orlando, FL, USA
e-mail: lathagantimd@gmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_70

Fig. 70.1 Types of abdominal wall hernias


Ventral hernias
Hiatal
Umbilical
Spigelian
Incisional
Groin hernias
Obturator
Femoral
Inguinal

70.1 Indications

- Incarcerated hernia

70.2 Contraindications

- Absolute
  - Strangulated hernia (could result in placing dead bowel into abdominal cavity)
- Relative
  - Inability to get patient relaxed enough
  - Previous unsuccessful attempts

70.3 Materials and Medications

- Ice or cold compress
- Stretcher or gurney that can tilt to provide Trendelenburg position
- Moderate sedation drugs if providing moderate sedation
- Truss for post-procedure

70.4 Procedure

1. Patient positioning:
   - For abdominal hernia: place patient supine.
   - For groin hernia in adult: place in 20 ° of Trendelenburg.
   - For groin hernias in children: place in unilateral frog leg position (Fig. 70.2).
2. Apply ice or cold compress directly over hernia site to reduce swelling.
3. Administer opiate analgesia or moderate/procedural sedation.
4. Wait up to 30 min as hernia may reduce spontaneously after swelling has gone down and patient is relaxed.
5. Gently apply steady pressure distally on the tissue at the neck of the hernia with one hand and with other hand, guide hernia proximally through fascial defect. Too much pressure distally can cause hernia to balloon further, making manual reduction difficult. Takes up to 15–20 min. Do not rush procedure.
6. Once hernia is reduced, pain will improve.
7. An external support garment or truss (Fig. 70.3) can be helpful to hold reduced hernia in place and serve as a temporizing measure until surgical repair can be done.
8. Advise patient to schedule elective surgical repair.
9. If unable to reduce the hernia, obtain surgical consultation. Do not force repeated attempts.



Fig. 70.2 Frog leg position in child



Fig. 70.3 An example of a truss, or external support, that can be useful as a temporizing measure until definitive hernia repair can be done

70.5 Complications

- Pain.
- Inability to achieve manual reduction, leading to strangulation of the hernia.
- Strangulation can result in peritonitis and sepsis.
- Recurrence.
- Hydrocele.

70.6 Pearls and Pitfalls

- Pearls
  - Definitive treatment for a hernia is surgery (herniorrhaphy). Without surgery, hernias grow larger over time; they do not disappear. Small hernias are easier to fix and result in fewer complications.
  - The only hernia that can resolve on its own is an umbilical hernia in a child.
  - Trusses, bandages, and tape may provide some comfort but do not reduce risk of incarceration or strangulation.
  - Note that if a truss is worn, it should be in place after reduction of the hernia. Also, it can be impractical in hot climates.
- Pitfalls
  - When the constricting neck and the protrusion are both reduced into the abdomen together (known as a reduction *en masse*), without actually reducing the hernia itself, strangulation ensues even though it appears one has reduced the hernia.
  - If there is still considerable pain after the reduction, it is likely the reduction was not successful or that dead bowel has been reduced into the abdominal cavity.
  - Not recognizing strangulation leads to gangrenous bowel, peritonitis, and sepsis.

Selected Reading

Campanelli G, Canziani M, Frattini F, et al. Inguinal hernia: state of the art. Int J Surg. 2008;6 Suppl 1:S26–8.

Jenkins JT, O'Dwyer PJ. Inguinal hernias. BMJ. 2008;336(7638):269–72.

Moses S. Hernia reduction. 2014. http://www.fpnotebook.com/mobile/Surgery/GI/HrnRdctn.htm. Accessed Sept 15, 2014.

Extended Focused Assessment with Sonography for Trauma

71

Coben Thorn and L. Connor Nickels

71.1 Indications

- Blunt abdominal or chest trauma
- Penetrating abdominal or chest trauma
- Undifferentiated hypotension
- The “E” in EFAST refers to the “extended” ability to detect lung pathology such as a pneumothorax or hemothorax during the otherwise standard trauma FAST exam using the same equipment with or without an additional transducer probe.
- Specific findings that can be detected on extended focused assessment with sonography for trauma (EFAST):
  - Pericardial fluid
  - Pleural fluid
  - Free intraperitoneal fluid
  - Pneumothorax
- Free fluid appears as anechoic or black.

71.2 Contraindications

- Need for immediate operative intervention

71.3 Materials and Medications

- Ultrasound machine
- Probe(s): phased array probe (5 to 1 MHz) or curved array probe (5 to 2 MHz)
  - Phased array has a smaller footprint, allowing easier access between intercostal spaces (Fig. 71.1); however, curved array provides better resolution of images



Fig. 71.1 Phased array transducer (P17) with a small footprint that is helpful to fit between the ribs and can be used for focused assessment with sonography for trauma (FAST) examination

---

C. Thorn, MD
Department of Emergency Medicine, Bon Secours St. Francis Health System, Greenville, SC, USA
e-mail: cobenthorn@gmail.com

L.C. Nickels, MD, RDMS (✉)
Department of Emergency Medicine,
University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: cnickels@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_71

(Fig. 71.2). The linear array transducer (L38, 10–5 MHz) is good for lung images.
- Gel
- Skilled ultrasound operator
- ± Laboratory work, cardiac monitor, and two large-bore intravenous (IV) needles
  - All trauma alerts and unstable patients must have all of these.



Fig. 71.2 Curved array transducer (C60) with a larger footprint and better resolution for deeper imaging that can be used for FAST examination as well as lung examination

71.4 Procedure

1. Ultrasound machine in the abdominal preset.
2. Patient in the supine position.
3. Phased array or curved array probe for focused assessment with sonography for trauma (FAST) and linear array for lung.
4. Begin scanning the patient in a systematic fashion.
   - All the views should be scanned by thoroughly sweeping through the area in question in order to maximize the information obtained.
   - All views should be obtained in the same order every time.
   - Obtain all four views, five views if pneumothorax is included.

71.4.1 Subxiphoid Four-Chamber View (Fig. 71.3)

1. Examine for free pericardial fluid.
    - Anechoic (black) stripe seen between the myocardium and the pericardium
2. Probe is placed in the subxiphoid area.
3. Indicator is to the patient's right.
4. Probe is directed toward the patient's left shoulder.
5. Use a shallow angle in the head to feet direction.
6. Should adequately visualize the following:
    - Liver edge superficially
    - Right ventricle
    - Left ventricle
    - Right atrium
    - Left atrium
7. If unable to obtain this view, proceed to *parasternal long-axis view*:
    - Probe is placed perpendicular at the left parasternal border.
    - Third to fourth intercostal space.
    - Indicator is to the patient's right shoulder.
    - Coronal section through the heart's long axis should adequately visualize the following:
        - Right ventricle most superficially
        - Left ventricle
        - Mitral valve
        - Left atrium
        - Aortic valve
        - Aortic outflow tract



Fig. 71.3 (**a**) Image shows how to obtain the subxiphoid four-chamber view of the heart using the curved array transducer (C60) (Photograph courtesy of F. Eike Flach, MD).(**b**) Ultrasound image of four-chamber view of the heart (Used with permission from First aid for the emergency medicine clerkship 3rd Ed, McGraw Hill, 2011.) *RV* right ventricle, *LV* left ventricle, *RA* right atrium, *LA* left atrium

71.4.2 Right Upper Quadrant View (Fig. 71.4)

1. Examine for free fluid in all of the following areas:
    - Right intrathoracic space
        – Anechoic area above the diaphragm
    - Morison’s pouch: hepatorenal space
        – Anechoic stripe between the liver and the kidney
    - Right paracolic gutter
        – Anechoic collection surrounding the inferior tip of the kidney
2. Probe is placed in the midaxillary line on the right.
3. Indicator is directed toward the patient’s head.
4. Probe is in the coronal plane, angle can be aimed obliquely while scanning anterior to posterior.


a
b
Gen S
THI MB
13:10
Abd
C60
92%
MI 0.7
TIS 0.1
75
A
B
15
Cine
c
L
K
Gen S
THI MB
13:10
Abd
C60
92%
MI 0.7
TIS 0.1
255
A
B
15
Cine

Fig. 71.4 (**a**) Image shows how to obtain the right upper quadrant view of the FAST exam using the curved array transducer (C60). The probe is aimed slightly obliquely in the coronal plane to get a better view between the ribs (Photograph courtesy of F. Eike Flach, MD). (**b**) Ultrasonographic view of the liver. (**c**) Ultrasonographic view of the liver–kidney interface (Morrison’s pouch). *L* liver, *K* kidney

71.4.3 **Left Upper Quadrant View** (Fig. 71.5)

1. Examine for free fluid in all of the following areas:
   - Left intrathoracic space
     - Anechoic area above the diaphragm
   - Subphrenic space
     - Anechoic stripe below the diaphragm and above the spleen
   - Splenorenal space
     - Anechoic stripe between the spleen and kidney
   - Left paracolic gutter
     - Anechoic collection surrounding the inferior tip of the kidney
2. Probe is placed in the midaxillary line on the left.
3. Indicator is directed toward the patient's head.
4. Probe in the coronal plane, angle can be aimed obliquely while scanning anterior to posterior.

71.4.4 **Pelvic View** (Figs. 71.6 and 71.7)

1. Examine for intraperitoneal free fluid in the pelvis:
   - Anterior pelvis, above the bladder
     - Anechoic fluid above the bladder
   - Posterior cul-de-sac (pouch of Douglas)
     - Anechoic fluid posterior to the bladder or uterus
2. Probe is placed above the pubic symphysis over the bladder.
3. Scan through in both planes:
   - Transverse plane (Fig. 71.6)
     - Indicator is to the patient's right.
     - Scan through the bladder in the head to feet direction.
   - Sagittal plane (Fig. 71.7)
     - Indicator is aimed to the patient's head.
     - Scan through the bladder in a right to left direction.



Fig. 71.5 (**a**) Image shows how to obtain the left upper quadrant view of the FAST examination using the curved array transducer (C60). Again, the probe is aimed slightly obliquely and is placed more superiorly in the midaxillary line (Photograph courtesy of F. Eike Flach, MD). (**b**) Ultrasonographic view of spleen–kidney interface. *S* spleen, *K* kidney



Fig. 71.6 Transverse pelvic view of the FAST examination using the phased array transducer (P17). With gentle force, the probe is pressed downward in order to look back behind the pubic symphysis and view the bladder (Photograph courtesy of F. Eike Flach, MD)



Fig. 71.7 (**a**) Sagittal pelvic view of the FAST exam using the curved array transducer (C60). With gentle force, the probe is pressed downward in order to look back behind the pubic symphysis and view the bladder (Photograph courtesy of F. Eike Flach, MD). (**b**) Ultrasonographic view of the bladder. *B* bladder

71.4.5 EFAST with Lung Views (Figs. 71.8 and 71.9)

1. Examine for pneumothorax:
    - Lung sliding
        - Absence: pneumothorax
        - Presence: normal lung
    - M mode tracing
        - Stratosphere sign: pneumothorax
        - Seashore sign: normal lung
2. Probe is placed on the anterior chest in the midaxillary line.
3. Level of the second to fourth intercostal spaces.
4. Sagittal position.
5. Center the probe over the pleural line between the ribs.
    - Find the rib and then slide the probe toward the head or feet to center the pleural line.
6. Observe for lung sliding.
7. Press M mode and move the line over the pleural line and press M mode again to get the tracing.
8. Examine multiple other areas anteriorly, moving distally, and in midaxillary line laterally, moving from superior to inferior.



Fig. 71.8 Right lung view of the extended focused assessment with sonography for trauma (EFAST) examination using the linear array transducer (L38). The probe is placed in the sagittal plane on the anterior chest in the midaxillary line approximately at the second intercostal space and centered over the pleural line (Photograph courtesy of F. Eike Flach, MD)



Fig. 71.9 Left lung view of the EFAST examination using the linear array transducer (L38) (Photograph courtesy of F. Eike Flach, MD)

71.5 Complications

- Overreliance on ultrasound to rule out abdominal injury:
  - FAST examinations do not detect retroperitoneal bleeding, solid organ injury, contained subcapsular hematomas, and bowel injuries.
- Not scanning through the object in question could lead to false-negative results.

71.6 Pearls and Pitfalls

- Always follow the ABCs (airway, breathing, circulation) first in any unstable patient.
- Always make sure the depth is set adequately.
  - Recommend starting deeper to make sure positive findings are not missed and then adjustments can be made from there.
- The curved array probe may be used throughout the entire EFAST for convenience if necessary.

71.6.1 Subxiphoid Four-Chamber View

- For larger body habitus, need to parallel the probe with the body in the subxiphoid area and use firm pressure to press the entire probe downward so as to look up under the xiphoid process at the heart.
- Moving the entire probe more to the patient's right in the subxiphoid area while still looking toward the left shoulder may improve visualization by using the liver as a window.
- Fat pad:
  - May be mistaken for pericardial fluid
  - Contains echoes and, therefore, is hypoechoic rather than anechoic
  - Should only be present anteriorly
    - Fluid should be gravity dependent, completely encircling the heart, and seen in multiple views.

71.6.2 Right Upper Quadrant View

- Normal artifacts of mirroring and loss of the spine are obscured when pleural fluid is present and, instead, the anechoic fluid is seen and there is loss of mirroring and continuation of the spine.

71.6.3 Left Upper Quadrant View

- Same as right upper quadrant view
- May be more difficult view to find than in right upper quadrant view for all of the following:
  - Spleen and kidney are more posterior and superior than in right upper quadrant view.
  - Spleen is smaller and less of a window for viewing.

71.6.4 Pelvic View

- Bowel can be mista0ken for free fluid or vice versa, but holding the probe still and observing can sometimes help distinguish the two.
  - Peristalsis will occur with bowel.
  - Internal echoes may be present in bowel.

71.6.5 Lung Views

- Ultrasound is more sensitive than a supine portable chest x-ray.
  - Apex anteriorly in midaxillary line.
- Rib
  - Hyperechoic horizontal line with a dense shadow posteriorly
  - Evenly spaced along the chest
- Pleural line
  - First hyperechoic line deep to the rib.
  - Actually includes the visceral and parietal pleura, but appears as one line.
  - Lung sliding is present in normal lung.
  - Comet tail artifact.
  - M mode tracing will be the same in normal lung and pneumothorax above the pleural line and different below the pleural line.
    - Seashore sign (Fig. 27.5a):
      - Appears as waves washing up on the shore.
      - Granular appearance represents movement.
    - Stratosphere sign (Fig. 27.5b):
      - Appears as straight lines
      - Bar code appearance

Selected Reading

Brunett P, Cameron P. Trauma in adults. In: Tintinalli J, Stapczynski J, Ma OJ, Cline D, Cydulka R, Meckler G, editors. Emergency medicine: a comprehensive study guide. 7th ed. New York: McGraw Hill; 2012. p. 1671–5.

Ma JO, Mateer JR, Blaivas M. Trauma. In: Emergency ultrasound. Course Materials; New York, NY: McGraw Hill; 2008. pp. 7–109.

Saul T, Rivera M, Lewiss R. Ultrasound image quality. ACEP News. 2011;4:24–5.

Nasogastric Tube Placement

72

David P. Nguyen, L. Connor Nickels,
and Giuliano De Portu

72.1 Indications

- Evaluation of upper gastrointestinal (GI) bleeding (history of melena, bright red blood per rectum, or coffee-ground emesis)
  - Only in the cases in which frank blood is obtained, the sensitivity/specificity in detecting upper GI bleeding is poor.
  - It should not be used for diagnostic purposes. It is used to remove blood that is irritating the stomach and to determine whether bleeding is still occurring (lavage does not clear).
- Commonly used in decompression of the GI tract (partial/complete small bowel obstruction)
- Prevents aspiration and gastric dilation in intubated patients
- Used during gastric lavage and/or removal of toxins (activated charcoal) for acute overdose or poisonings

72.2 Contraindications

- Absolute
  - Facial trauma with possible cribriform plate fracture
- Relative
  - Severe coagulopathy (consider orogastric tube placement)
  - Esophageal strictures and alkali ingestions (possible esophageal perforation)
  - Esophageal varices (studies show that it is actually safe)

72.3 Materials and Medications

- For awake patients, consider pretreatment: lidocaine gel (2 % viscous)/nebulized lidocaine (4 or 10 %), vasoconstrictors (e.g., phenylephrine 0.5 %), and antiemetic (e.g., ondansetron 4 mg).
- 16- or 18-French sump tube lubricating jelly
- 50- or 60-mL syringe stethoscope

D.P. Nguyen, DO
Department of Emergency Medicine, Rush-Copley Medical Center, Aurora, IL, USA
e-mail: davidpnguyen@yahoo.com

L.C. Nickels, MD, RDMS (✉) • G. De Portu, MD
Department of Emergency Medicine,
University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: cnickels@ufl.edu; gdeportu@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_72

72.4 Procedure

- Preparation
  1. Awake patients, should receive antiemetics 15 min before procedure.
  2. Anesthetize both nares at least 5 min before placement.
     – Spray vasoconstrictor into both nares.
     – Inject about 5 mL of lidocaine gel along the floor of the nose.
     – Nebulized lidocaine via facemask also reduces both nasal and pharyngeal discomfort.
  3. Elevate the head of the bed to an upright position (when possible).
  4. Estimate tube insertion distance by measuring the tube from the xiphoid to the earlobe and then to the tip of the nose. Add 6 in. to this estimate and note the total distance. This helps with placement in the stomach and prevents esophageal placement or coiling in stomach. Mark the tube with markers or tape at the desired length.
  5. Lubricate the nasogastric (NG) tube.
- Insertion (Fig. 72.1)
  1. Always insert the tube gently into the nares along the floor of the nose under direct visualization. Always point inferiorly (do not point upward).
  2. If resistance is encountered, try to apply a small amount of pressure. STOP if unable to advance. Try the other side. It is necessary to prevent bleeding or dissecting the tissues.
  3. Have the patient flex his or her head forward when the tube is in the nasopharynx. This helps direct the tube toward the correct placement in the esophagus and not the trachea. Have the awake and cooperative patient sip water from a straw and swallow as the tube enters the oropharynx.
  4. Making the tube more rigid by placing it in cold water will help advance it because the "warmer" tube will tend to coil.
  5. Once the tube is in the esophagus, rapidly advance the tube into the stomach, taking into consideration the previously marked depth.
- Confirmation of tube placement
  1. Insufflate air into the end of the NG tube, via a 50- or 60-mL syringe, while auscultating for a rush of air (borborygmi) over the stomach.
  2. Aspiration of gastric contents (pH<4, there is >90 % gastric placement).
  3. The awake and cooperative patient should be able to talk, and if coughing or severe discomfort occurs, consider that esophageal or bronchial placement might have occurred.
  4. Radiographic evaluation:
     – "Gold standard" is to evaluate simple radiograph for position.
     – Consider in comatose patients.
- Secure the tube
  1. Tape the NG tube in place by taping both the tube and the nose. A butterfly bandage is typically used. Some companies produce a specific fixation for the tube.
  2. Secure the tube to where it does not press on the medial or lateral nostril (can lead to bleeding/necrosis).



Fig. 72.1 NG tube placement

72.5 Complications

- Inability to pass the tube
- Bleeding
- Curling of the NG tube in the patient's mouth
- Pulmonary placement
- Nasal necrosis

72.6 Pearls

- Pearls
  - NG tube placement was ranked #1 as the most painful procedure in the emergency department so it is imperative to maintain patient's comfort by using anesthetics and even maybe intravenous anxiolytics.
  - Estimate the proper length of the tube before passage to avoid placing the tip of the tube in the esophagus or excessively coiling it in the stomach.
  - If leaving the tube for a prolonged period of time, make sure that the suction is set "intermittent" or "off" to prevent irritation to the gastric mucosa owing to direct pressure.

Selected Reading

Chun DH, Kim NY, Shin YS, Kim SH. A randomized, clinical trial of frozen versus standard nasogastric tube placement. World J Surg. 2009;33:1789–92.

Goff JS. Gastroesophageal varices: pathogenesis and therapy of acute bleeding. Gastroenterol Clin North Am. 1993;22:779.

Henneman PL. Gastrointestinal bleeding. In: Marx J, Hockberger R, Walls R, editors. Rosen's emergency medicine: concepts and clinical practice. 7th ed. Philadelphia: Mosby; 2010.

Tho PC, Mordiffi S, Ang E, Chen H. Implementation of the evidence review on best practice for confirming correct placement of nasogastric tube in patients in an acute care hospital. Int J Evid Based Healthc. 2011;9:51–60.

Esophageal Foreign Body Removal

73

David P. Nguyen, L. Connor Nickels,
and Rohit Pravin Patel

73.1 Indications

- Patient presenting with any one or combination of the following:
  - Foreign body sensation in throat, neck, substernal chest, or epigastric area
  - Clear history of ingestion
  - Dysphagia
  - Airway compromise
  - Drooling
  - Inability to tolerate fluids
  - Inability to tolerate solids
  - Evidence of perforation
  - Active bleeding
- All unstable patients should have immediate airway management and urgent endoscopy.
- FBs lodged superior to the epiglottis may be retrieved by emergency physicians in an emergent situation, but generally, a consultant should be present, whether ear, nose, and throat, gastroenterology, or general surgery.

73.2 Contraindications

- Absolute
  - None
- Relative
  - Performing rapid sequence intubation (RSI) in a patient with an FB that could compromise the airway.
  - Generally, if the patient is breathing on their own, collaborate with a consultant on the best method to secure the airway (emergency department, intensive care unit, operating room).
  - Treating with glucagon repeatedly if it is inducing vomiting and/or not working.
  - Conservatively managing a patient who should otherwise undergo a procedure for removal.

73.3 Materials

- Esophagoscopy/endoscopy is the definitive diagnostic and therapeutic procedure for impacted esophageal FBs.
  - Generally, should not be performed by an emergency physician.
  - Devices used include forceps, baskets, polypectomy snares, and nets.
  - Endoscopic techniques include push into stomach, push plus fragmentation, pull with retrieval forceps, and pull with various items (basket, snare, nets).
- Foley catheter removal
  - Widely used technique for recently ingested single, smooth, blunt, and radiopaque objects
  - #12 to #16 French Foley catheter
  - Forceps (bayonet and Magill) of various sizes
  - Often done under fluoroscopic guidance
- Bougienage
  - A single, smooth object, such as a coin, lodged less than 24 h in a patient with no respiratory distress or esophageal disease can be advanced successfully into the stomach by using bougienage.
  - Dilator size is selected based on age:
    - 1–2 years: 28 French
    - 2–3 years: 32 French
    - 3–4 years: 36 French
    - 4–5 years: 38 French
    - Longer than 5 years: 40 French
- Relaxation of the lower esophageal sphincter (LES)
  - Some FBs lodged at the LES can be medically managed by relaxation of the LES.

D.P. Nguyen, DO
Department of Emergency Medicine, Rush-Copley Medical Center, Aurora, IL, USA
e-mail: davidpnguyen@yahoo.com

L.C. Nickels, MD, RDMS (✉) • R.P. Patel, MD
Department of Emergency Medicine,
University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: cnickels@ufl.edu; rohitpatel@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_73

  - Most ingested FBs and impacted food boluses eventually pass spontaneously.
    - 1–2 mg of glucagon intravenously
    - 0.4–0.8 mg of nitroglycerin sublingually
    - 5–10 mg of nifedipine sublingually
    - Carbonated beverage

73.4 Procedure

- Push technique and push with fragmentation technique (generally performed by specialists)
  1. First accepted endoscopic method.
  2. Gentle pressure is applied with the tip of the endoscope on the esophageal food bolus after air insufflation.
  3. If pressure does not disimpact the bolus, fragmentation can be attempted but is generally avoided owing to unknown pathology behind the food bolus.
- Foley catheter removal
  1. Moderate sedation and nasopharyngeal topical anesthesia may be used.
  2. Place the patient in a head-down Trendelenburg position.
  3. Check for symmetrical balloon inflation of the Foley catheter.
  4. Under fluoroscopy, visually pass the catheter distal to the FB.
  5. Fill the balloon slowly with 3–5 mL of saline or contrast agent.
  6. Using steady, gentle traction, withdraw the catheter with the balloon inflated distal to the FB.
  7. Grasp the object with fingers, forceps, or clamp once it is visualized in the oropharynx.
- Bougienage
  1. Topical anesthesia is recommended.
  2. Blind esophageal bougienage resembles placement of an orogastric tube.
  3. Place the patient in a sitting position.
  4. Pass a well-lubricated, appropriately sized bougie posteriorly along the roof of the mouth, following the natural curve of the soft palate caudally to the hypopharynx.
  5. Encourage the patient to swallow (to help pass the dilator through the cricopharyngeus muscle).
  6. Ask the patient to phonate to help exclude accidental laryngeal intubation.
  7. Once past the cricopharyngeus muscle, extend the head to aid the bougie in passing distally to the stomach.
  8. Post-procedure radiograph is used to confirm passage into the stomach.
- Relaxation of the LES
  1. Premedicate with an antiemetic, such as ondansetron.
  2. Administer 1–2 mg of glucagon intravenously (0.02–0.03 mg/kg in children, not to exceed 0.5 mg) with the patient in a sitting position over 1–2 min.
  3. Carbonated beverages given after glucagon ingestion have shown to have higher success rates.
  4. An alternative is to use either sublingual nitroglycerin (1–2 0.4 mg tabs) or 5–10 mg of nifedipine to relieve LES tone.
  5. This procedure does not work in patients with structural abnormalities.

73.5 Complications

- Esophageal FBs may cause esophageal pressure leading to edema, necrosis, infection, laceration, and/or perforation.
- Be cognizant of time (risk of complications is higher the longer the FB is left in place) and treatment side effects (i.e., do not continue to give patient water or glucagon if these induce vomiting).
- Aspiration and perforation during procedures listed previously.
- Late complications: esophageal stricture, abscess, mediastinitis, tracheoesophageal fistula, vascular injuries, pneumothorax, pericarditis, aspiration pneumonia, and vocal cord paralysis.

73.6 Pearls

- Esophageal foreign bodies can be lodged in the upper (proximal), middle, or lower (distal) one third:
  - Proximal: cervical web, Zenker's diverticulum
  - Middle: eosinophilic esophagitis, cancer, radiation structure, spastic dysmotility
  - Distal: peptic stricture, eosinophilic esophagitis, cancer, achalasia, esophageal diverticula, spastic dysmotility
- Because food bolus impactions are generally associated with pathology, follow-up evaluation for these abnormalities should be considered.
- Esophagus foreign bodies should not be allowed to remain in the esophagus beyond 24 h from presentation.
- Button/disc batteries in esophagus (emergent removal)
  - Considered an emergency, because liquefaction necrosis and perforation can occur rapidly.
  - Most common ingestions are hearing aid batteries.
  - If in stomach, and patient is a symptomatic, can wait up to 24 h.
- Sharp objects (emergent removal)



Fig. 73.1 (**a**) Anteroposterior (AP) and (**b**) lateral views demonstrating a coin in the esophagus. A coin in the trachea would present in the opposite manner—the coin would be seen on edge in the AP view and flat on the lateral view (Reproduced with permission from McGraw-Hill: Stead LG, et al. *First Aid for the Pediatrics Clerkship*. New York: McGraw-Hill, 2010)

  - Cause the majority of complications (~35 %) with esophageal FBs.
  - Direct visualization with endoscopy is the only appropriate removal technique.
- Magnets (urgent removal)
  - Can cause necrosis and fistula formation due to the way they adhere to the mucosa
- Esophageal coins (remove within 24 h) (Fig. 73.1)
  - Up to 80 % of coins at the LES will pass spontaneously within 24 h without interventions. The watchful waiting approach is used only in patients with single coins and who are asymptomatic.
  - Common complications of these procedures include mild bleeding, lip laceration, bradycardia with Foley catheter insertion, and teeth injuries.
  - Some protocols include RSI as part of the management process and should be considered if lifesaving.

Selected Reading

ASGE Standards of Practice Committee. Management of ingested foreign bodies and food impactions. Gastrointest Endosc. 2011; 73:1085.

Bhargava R, Brown L. Esophageal coin removal by emergency physicians: a continuous quality improvement project incorporating rapid sequence intubation. CJEM. 2011;13:28–33.

Conway WC, Sugawa C, Ono H, Lucas CE. Upper GI foreign body: an adult emergency hospital experience. Surg Endosc. 2007; 21:455–60.

Katsinelos P, Kountouras J, Paroutoglou G, et al. Endoscopic techniques and management of foreign body ingestion and food bolus impaction in the upper gastrointestinal tract: a retrospective analysis of 139 cases. J Clin Gastroenterol. 2006;40:784–9.

Activated Charcoal

74

Deylin I. Negron Smida and Judith K. Lucas

74.1 Indications

- Single-dose activated charcoal (AC) (Fig. 74.1)
  - Does not meet criteria for gastric emptying.
  - Gastric emptying may be too harmful.
  - Ingestion of toxic xenobiotic is known to be adsorbed by AC.
  - Ingestion occurred with a time frame amenable to adsorption by AC, or clinical factors are present that suggest that not all of the xenobiotic had already been systemically absorbed.
  - Ingestion of extended- or sustained-release formulations.
- Multiple-dose activated charcoal therapy (MDAC)
  - Life-threatening ingestion of:
    - Carbamazepine
    - Phenobarbital
    - Quinine
    - Theophylline
    - Dapsone
  - Life-threatening ingestion of another xenobiotic that undergoes enterohepatic recirculation and is adsorbed to AC
  - Ingestion of a significant amount of a slowly released xenobiotic
  - Ingestion of a xenobiotic known to form concretions or bezoars, such as aspirin


Paddock
Laboratories, Inc.
Actidose-Aqua™
ACTIVATED CHARCOAL SUSPENSION
25 grams Activated Charcoal
SHAKE WELL BEFORE USING
CONTENTS: 120 mL (4 Fl Oz)

Fig. 74.1 Activated charcoal (AC)

D.I.N. Smida, MD
Department of Emergency Medicine, University of Pittsburgh Medical Center, Saint Margaret Hospital, Pittsburgh, PA, USA
e-mail: Deylin.negron@gmail.com

J.K. Lucas, MD (✉)
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: judithklucas@ufl.edu

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_74

74.2 Contraindications

- Absolute
  - Gastric perforation
  - Gastrointestinal ileus, obstruction, or diminished peristalsis
  - Nonintubated patients with the potential of losing protective airway reflexes
  - Intestinal obstruction
  - Ingestion of:
    - Corrosives
    - Petroleum distillates
- Relative
  - Altered or decreased level of consciousness unless intubated.
  - Vomiting.
  - Xenobiotic has limited toxicity at almost any dose.
  - Dose ingested is less than the dose expected to produce significant illness.
  - Presentation many hours after ingestion.
  - Minimal signs or symptoms of poisoning.
  - Ingested xenobiotic has a highly efficient antidote.
  - Administration of charcoal may increase the risk of aspiration (i.e., hydrocarbons).

74.3 Materials and Medications

- Nasogastric (NG) tube/orogastric (OG) tube (Fig. 74.2)
- Baby bottle with split nipple (designed for drinking of slurry solutions, such as thickened formulas) or sippy cup without the valve
- Absorbent pad
- Basin
- Water-soluble lubricant
- Tubing connected to suction device
- Flavored syrup



Fig. 74.2 Drinking AC (by cup, sippy cup, or bottle) is effective, but it may also be infused via nasogastric or orogastric tube

74.4 Procedure

- Single-dose administration
  - Adult
    - Can be taken via a cup and straw (drunk) if the patient is cooperative.
    - The optimal dose of AC is unknown.
    - 50–100 g/dose (1 g/kg), administered at a rate no less than 12.5 g/h or its equivalent.
    - If vomiting is anticipated, an intravenous antiemetic is recommended.
  - Children
    - 1 g/kg or 10:1 ratio of AC to drug ingested.
    - After massive ingestion, give 2 g/kg.
    - Many children will drink the suspension from a bottle or sippy cup, especially if it is mixed with juice or flavored syrup (e.g., chocolate or strawberry).
- MDAC
  - Adults: 0.5–1 g/kg every 2–4 h for 24–48 h
  - Children (<12 y old): 0.25–0.5 g/kg every 2–4 h or rate of 0.2 g/kg/h for 24–48 h
- Mixtures
  - Ready to drink
  - Powder form
    - Add eight parts water to the selected powdered form.
    - Gatorade or juices can also be used to help hide the flavor and texture.
    - In children, the AC can be mixed with cold chocolate or some other flavored syrup, which also hides the flavor.
  - Shake liquid suspension well for 1 min.
  - If the patient vomits, the dose should be repeated. Smaller, more frequent, dosing may be better tolerated, and an antiemetic may be needed.

74.5 Complications

- Aspiration pneumonitis
- Transient constipation
- Intestinal bezoars
- Bowel obstruction
- Diarrhea, dehydration, hypermagnesemia, and hypernatremia with coadministered cathartics or MDAC
- Vomiting
- Corneal abrasion if spilled in the eyes

74.6 Pearls and Pitfalls

- Pearls
  - If an OG or NG tube is used, time should be allowed for the last dose to pass through the stomach before the tube is removed. Suctioning the tube before removal may prevent subsequent AC aspiration.
  - With children, the colder and sweeter the solution and if the color is camouflaged (cup with a lid or a sippy cup), there will be increased success at oral administration (vs NG/OG).
- Pitfalls
  - No evidence-based literature supports the assertion that AC changes clinical outcome.
  - Xenobiotics and AC adsorption (Table 74.1).
  - Incorrect application (e.g., into the lungs) results in pulmonary aspiration, which can be fatal if unrecognized.
    - Incorrect placement of NG/OG tube into trachea.
    - Administration of AC to a patient with an ileus (e.g., in anticholinergic overdoses).
  - No specific contraindication for AC in pregnant women; however, diarrhea or hypernatremia in the mother may adversely affect the fetus.

Table 74.1 Absorption of xenobiotics by AC

Good absorption	Poor absorption
Acetaminophen	Alkali
Bupropion	Chlorpropamide
Caffeine	Doxepin
Carbamazepine	Ethanol or other alcohols
Chlordecone	Ethylene glycol
Dapsone	Fluoride
Digitoxin	Heavy metals
Nadolol	Imipramine
Phenobarbital	Inorganic salts
Phenylbutazone	Iron
Phenytoin	Lithium
Salicylate	Methotrexate
Theophylline	Mineral acids
	Potassium
	Tobramycin
	Valproate sodium
	Vancomycin

Selected Reading

American Academy of Clinical Toxicology; European Association of Poisons Centres and Clinical Toxicologists. Position statement and practice guidelines on the use of multi-dose activated charcoal in the treatment of acute poisoning. J Toxicol Clin Toxicol. 1999;37:731–51.

Chyka PA, Seger D. American Academy of Clinical Toxicology; European Association of Poisons Centres and Clinical Toxicologists. Position statement: single-dose activated charcoal. J Toxicol Clin Toxicol. 1997;35:721–41.

Gude A, Hoegberg LCG. Techniques to prevent gastrointestinal absorption. In: Nelson LS, Lewin NA, Howland MA, et al., editors. Goldfrank's toxicologic emergencies. 9th ed. New York: McGraw-Hill; 2011. p. 93–7,431.

Lie D. Use of activated charcoal in drug overdose. Medscape family medicine. 25 Mar 2004. www.medscape.com/viewarticle/471331

Olson KR. Emergency evaluation and treatment. In: Olson KR, Anderson IB, Benowitz NL, et al., editors. Poisoning and drug overdose. 5th ed. New York: McGraw-Hill; 2007. p. 1–56.

Gastric Lavage

75

Deylin I. Negron Smida and Judith K. Lucas

75.1 Indications

- Recent ingestion (<30–60 min).
- Life-threatening exposure where there is a high suspicion that a xenobiotic is still present in the stomach and evacuation is expected to contribute to an improved outcome (e.g., iron, tricyclic antidepressants).
- Ingested agent is not absorbed with activated charcoal (e.g., pesticides, hydrocarbons, iron, alcohols, lithium, and solvents).
- Activated charcoal is unavailable.
- Ingestion exceeds adsorptive capacity of initial activated charcoal dosing (e.g., >100 mg/kg of pills).
- Ingestion of an agent likely to form a durable mass or bezoars after overdose.

75.2 Contraindications

- Vomiting
- Unintubated patients with potential to lose airway protective reflexes
- Ingestion of a xenobiotic with aspiration potential (e.g., hydrocarbon) without intubation
- Ingestion of caustic substances (alkali or acidic)
- Ingestion of sharp metals
- Ingestion of a foreign body (e.g., drug packet)
- Risk for hemorrhagic gastrointestinal perforation
- Ingestion of xenobiotic in a form known to be too large to fit into the lumen of the orogastric tube
- Nontoxic ingestions

75.3 Materials and Medications

- Orogastric tube (Ewald tube or the Tum-E-Vac) (Fig. 75.1)
  - Adults and adolescents: 36–40 French
  - Children: 22–28 French
- Pen or tape to mark the length of the tube
- Water-soluble lubricant
- Suction
- Emesis basin
- Absorbent pad
- Catheter-tip syringe with 2 mL water/saline to check position of the tube
- Room temperature irrigation fluid
- Bite block or oral airway to prevent patients from biting down on the tube



Fig. 75.1 Materials needed for gastric lavage include a large-bore nasogastric tube, a 60-cc non-Luer-Lok syringe, and a solution, typically normal saline, for lavage

---

D.I.N. Smida, MD
Department of Emergency Medicine, University of Pittsburgh Medical Center, Saint Margaret Hospital, Pittsburgh, PA, USA
e-mail: Deylin.negron@gmail.com

J.K. Lucas, MD (✉)
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: judithklucas@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_75

75.4 Procedure

1. If there is potential airway compromise, endotracheal or nasotracheal intubation should precede orogastric lavage.
2. Place an oral airway or a bite block to prevent biting of the endotracheal tube if the patient recovers consciousness or has convulsions during the procedure.
3. Ensure suction apparatus is available and functioning.
4. Place the patient in an upright-seated position if awake and alert.
5. Place patient in the left lateral decubitus position if obtunded.
6. Before insertion, the proper length of tubing to be passed should be measured from the mouth, back to the ear, and down anterior to the chest and abdomen, beyond the point where any side ports on the tube would be beyond the level of the estimated lower esophageal sphincter (Figs. 75.2 and 75.3).
7. If the patient is still awake, insert the gastric tube to the level of the glottis, and encourage the patient to swallow.
8. Pass the tube to the stomach.
   (a) Coughing, airflow, or fog from the tube raises the concern for inadvertent tracheal positioning.
9. After the tube is inserted, it is essential to confirm that the distal end of the tube is in the stomach, by "popping" 5–10 mL of air into the tube while someone is listening with a stethoscope over the stomach.



Fig. 75.3 Measuring correct placement of the tube. Place the distal tip over the stomach and wrap the tube up behind the ear (usually the right ear because the tubes generally pass easier through the right nares) and around the nares. The black line or centimeter mark at the level of the nares is the point of insertion when passage stops



Fig. 75.2 Diagram illustrates appropriate placement of the lavage tube

10. In adults, 250-mL aliquots of a room temperature saline lavage solution are instilled via a funnel or lavage syringe. In children, aliquots should be 10–15 mL/kg to a maximum of 250 mL and suctioned back out of the tube attached to low to moderate continuous wall suction. Instillation of lavage solution and suction is repeated (Fig. 75.4).
11. Orogastric lavage should continue for at least several liters in an adult and/or at least 0.5–1 L in a child if the return is free of debris or until no particulate matter returns and the effluent lavage solution is clear.
12. Those caring for the patient must remain protected at all times, using goggles, mask, gown, and gloves. If the ingested poison is toxic via pulmonary or skin absorption, isolate the ingestant immediately in a self-contained wall suction unit.
13. Any material still in the stomach should be withdrawn, and immediate instillation of the activated charcoal should be considered for large ingestions of xenobiotics known to be adsorbed by activated charcoal.

75.5 Complications

- Vomiting
- Esophageal tears or perforation after orogastric tube insertion
- Inadvertent tracheal intubation and/or airway trauma
- Aspiration pneumonitis

75.6 Pearls and Pitfalls

- Pearls
  - You must use a large-bore orogastric tube for maximal efficacy.
  - The left lateral decubitus position is recommended because the pylorus points upward in this orientation. This position theoretically helps prevent the xenobiotic from passing through the pylorus during the procedure.
- Pitfalls
  - Large drug packets, adherent masses of pills, and plant and mushroom fragments will not pass through a 40-French lavage tube.



Fig. 75.4 Lavage in progress

Selected Reading

Gude A, Hoegberg LCG. Techniques to prevent gastrointestinal absorption. In: Nelson LS, Lewin NA, Howland MA, et al., editors. Goldfrank's toxicologic emergencies. 8th ed. New York: McGraw-Hill; 2006. p. 91–3.

Olson KR. Poisoning & drug overdose. In: Olson KR, Anderson IB, Benowitz NL, et al., editors. Emergency evaluation and treatment. 6th ed. New York: McGraw-Hill; 2012.

Smilktein MJ. Techniques used to prevent gastrointestinal absorption of toxic compounds. In: Nelson LS, Lewin NA, Howland MA, et al., editors. Goldfrank's toxicologic emergencies. 7th ed. New York: McGraw-Hill; 2002. p. 46–8.

Whole-Bowel Irrigation

76

Judith K. Lucas

76.1 Indications

- Whole-bowel irrigation (WBI) should not be used routinely in the management of the poisoned patient (because there is no clinical proof it will change clinical outcome).
- Ingestion of significant amount of medications.
  - Not adsorbed by activated charcoal
    - Lead, lithium, arsenic, and zinc
    - Substantial amounts of iron (high morbidity and no other effective method to gastrointestinal decontamination)
  - Sustained-release medications or enteric-coated drugs
  - Disk batteries distal to the pylorus
  - Whole transdermal patches (fentanyl, clonidine, nicotine)
  - Drug concretions
  - Ingested packets of illicit drugs

76.2 Contraindications

- Absolute
  - Bowel obstruction
  - Bowel perforation
  - Ileus
  - Hemodynamic instability
  - Compromised or unprotected airway
  - Intractable vomiting
- Relative
  - Concurrent or recent administration of activated charcoal (may decrease the effectiveness of activated charcoal)

76.3 Materials and Medications

- Topical anesthesia, although not mandatory, will reduce the pain of nasogastric (NG) tube placement.
  - 10 % lidocaine spray
  - Lidocaine gel
- Small-bore (12-French) NG tube (Fig. 76.1).
- Tape for securing the NG tube.
- Reservoir or feeding bag used for NG tube feedings (Fig. 76.2).
- Intravenous pole.
- Bedside commode or toilet (Fig. 76.3).
- Polyethylene glycol-electrolyte solution (PEG-ES) (Fig. 76.4).
- Antiemetic.
  - No absolute indication for prophylactic use
  - May be helpful if vomiting ensues during infusion
    - Metoclopramide
      - Antiemetic
      - *Increases gastric motility*

J.K. Lucas, MD
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: judithklucas@ufl.edu

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_76



Fig. 76.1 Nasogastric (NG) tube. Typically, the infusion of the lavage solution is too rapid to be taken orally, so an NG tube can be placed. Since the irrigation solution is of low viscosity, a small-bore NG tube should be used for comfort



Fig. 76.2 Bag from which the lavage solution will drain; it is similar to the bags used for gastrostomy tube feeding

Fig. 76.3 Almost always, the patient will need to be seated on or very near a portable commode, as once the irrigation solution starts to move through the bowels, defecation will occur rapidly



Fig. 76.4 Example brands of intestinal irrigation electrolyte solutions

76.4 Procedure

1. An NG tube is required because most patients will not drink the PEG-ES at the necessary rate.
2. Place a small-bore (12-French) NG tube to a sufficient distance that the tip lies in the central portion of the stomach.
3. Confirm NG placement with a radiograph.
4. Attach the tube to the reservoir bag of PEG-ES and hang from an elevated site (an extended intravenous pole).
5. The patient should be seated in an upright position.
   - Promotes settling of the intoxicant in the distal portion of the stomach
   - Decreases the likelihood of vomiting
6. Dosing:
   - Children 9 months to 6 years: 500 mL/h
   - Children 6–12 years: 1,000 mL/h
   - Adolescents/adults: 1,500–2,000 mL/h
7. Collect effluent.
8. Continue infusion.
   - Until the rectal effluent is the same color as the influent (i.e., clear), usually between 4 and 6 h.
   - You may continue beyond clear effluent if clinical evidence indicates ongoing effectiveness:
     – Continued pill fragments or drug packets are present in the effluent.
     – Radiographic evidence that pills, pharmacobezoars, or packets are still present.

76.5 Complications

- Nausea, vomiting, and bloating
- Misplacement of the NG tube
- Esophageal perforation owing to NG tube placement
- Aspiration pneumonitis in the unprotected airway

76.6 Pearls

- Overall, WBI is probably more effective than gastric lavage, but probably less effective than activated charcoal in preventing poison absorption (when the intoxicant can be adsorbed to charcoal).
- Vomiting.
  – Usually secondary to the ingestant (i.e., emetogenic toxins, such as iron)
  – May be due to rate of infusion
    - Slow rate by 50 % for 30–60 min.
    - Then return to original rate.
- If resistance is encountered during NG tube placement, do not force passage. Remove and redirect.

Selected Reading

Bailey B. To decontaminate or not to decontaminate? the balance between potential risks and foreseeable benefits. Clin Pediatr Emerg Med. 2008;9:17–23.

Hanhan UA. The poisoned child in the pediatric intensive care unit. Pediatr Clin North Am. 2008;55:669–86. xi.

Lheureux P, Tenenbein M. Position paper: whole bowel irrigation. American Academy of Clinical Toxicology/European Association of Poison Centres and Clinical Toxicologists. J Toxicol Clin Toxicol. 2004;42:843–54.

Othong R. Whole-bowel irrigation. MedScape Reference: drugs, diseases, and procedures. Updated: Aug 2011

Postuma R. Whole bowel irrigation in pediatric patients. J Pediatr Surg. 1982;17:350–2.

Sengstaken-Blakemore Tube

77

Thomas T. Nguyen, Etan Eitches,
and Stephanie Wetmore-Nguyen

77.1 Indications

- Life-threatening esophageal variceal bleed refractory to endoscopy and medical therapy
- Life-threatening esophageal variceal bleed refractory to medical therapy in the absence of possible endoscopy

77.2 Contraindications

- Absolute
  - Known esophageal rupture
  - Unable to intubate or maintain airway
- Relative
  - History of prior esophageal trauma or strictures
  - Recent surgery of the gastroesophageal junction
  - Resolved or resolving variceal bleeding

77.3 Materials and Medications

- Sengstaken-Blakemore (SB) tube (Fig. 77.1)
- 60-mL syringe with catheter tip (Fig. 77.2)
- Sphygmomanometer (Fig. 77.3) or cuffalator (Fig. 77.4)
- Y-Tube connector (Fig. 77.5) or 3-way stop-valve connector (Fig. 77.6)
- Vacuum suction device and tubing (Fig. 77.7)
- Tube clamps (4) (Fig. 77.8)
- Lubricant (water soluble)
- Lidocaine (Xylocaine) spray or gel
- Anchoring device such as a football helmet or catcher's mask (Fig. 77.9)
- Cup of water and straw if the patient is awake
- Scissors (Fig. 77.10)
- Intubation equipment
- Sterile water

T.T. Nguyen, MD (✉)
Department of Emergency Medicine,
Mount Sinai Beth Israel, New York, NY, USA
e-mail: tnguyen@chpnet.org

E. Eitches, MD
Department of Emergency Medicine,
Beth Israel Medical Center, New York, NY, USA
e-mail: eeitches@gmail.com

S. Wetmore-Nguyen, MD
Department of Emergency Medicine,
New York-Presbyterian Hospital/Columbia University Medical Center,
New York, NY, USA
e-mail: slw9004@nyp.org

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_77



Fig. 77.1 Sengstaken-Blakemore (SB) tube



Fig. 77.2 Syringe


300
280
260
240
220
200
180
160
140
120
100
80
60
40
20
290
270
250
230
210
190
170
150
130
110
90
70
50
30
10

Fig. 77.3 Sphygmomanometer


0
10
20
30
40
50
60
70
80
90
100
110
120

Fig. 77.4 Cuffalator



Fig. 77.5 Y-Tube connector



Fig. 77.6 3-way stop-valve tube connector


3000
2750
2500
2250
2000
1750
1500
1250
1000
750
500
400
300
200
100

Fig. 77.7 Suction device and tubing



Fig. 77.8 Tube clamps



Fig. 77.9 Helmet traction setup

Fig. 77.10 Scissors

77.4 Procedure

1. Sedate and/or intubate the patient for adequate control of the patient during the procedure.
2. Ensure that the SB tube balloons are functional by inflating and deflating the balloons to ensure the absence of leaks.
3. Perform gastric lavage and irrigate the stomach with copious amount of sterile water.
4. Coat the distal and proximal portions of the SB tube with a thin layer of lubricating jelly or lidocaine gel. Spray the nasal passage with lidocaine spray.
5. Pass the SB tube via the nasogastric (NG) or the orogastric route (in intubated patients) to the 50-cm line. You may confirm placement with x-ray.
6. Inflate the gastric balloon to 200 mL of air and clamp the tube.
7. Apply gentle traction of 1–2 lb (0.4–2 kg) of force until it is felt that the gastric balloon has lodged at the gastroesophageal junction (Fig. 77.11).
8. Secure the tube to an anchor (e.g., football helmet or catcher's mask) placed on the patient's head.
9. Aspirate and lavage the gastric aspiration port. If it is clear of blood, do not inflate the esophageal balloon.
10. If it is not clear of blood, connect the esophageal tube of the SB tube to the sphygmomanometer/cuffalator using the 3-way stop-valve device (Fig. 77.12). You may use the Y-Tube connector instead.
11. Inflate the esophageal balloon to the lowest pressure determined to stop bleeding, typically 20–45 mmHg. Clamp the balloon.
12. Place an NG tube until it is felt overlying the top of the esophageal balloon of the SB tube. Check for further proximal esophageal bleed through aspiration and gentle lavage. Attach this NG tube to intermittent section to aid in the clearance of secretions.
13. Obtain a portable radiograph to confirm the position of the SB tube.
14. The esophageal tube should be at the lowest pressure that prevents bleeding and kept inflated for 24 h or until other definitive treatment is obtained.

Fig. 77.11 Proper placement of the balloons


Esophagus balloon
Gastric aspiration
Gastric balloon
Esophageal balloon
Gastric balloon

Fig. 77.12 Connection of the sphygmomanometer to the esophagus balloon port


Esophagus balloon
Gastric aspiration
Gastric balloon

77.5 Complications

- Esophageal rupture occurs owing to esophageal erosion and necrosis owing to a balloon tamponade effect on tissue perfusion or overzealous balloon inflation.
- Airway obstruction owing to gastric tube deflation or failure, allowing esophageal tube to move up and occlude airway. Keep scissors near the patient to cut the SB tube lumens and remove the tube as necessary.
- Regurgitation and aspiration pneumonia from failure to adequately suction oropharyngeal secretions.

77.6 Pearls and Pitfalls

- Pearls
  - The esophageal balloon should not be inflated if the gastric balloon alone stops the bleeding.
  - Never inflate the esophageal balloon without the inflating the gastric balloon first. This will prevent it from slipping proximally into the oropharynx and obstructing the airway.
  - Nausea, vomiting, or aspiration is highly likely to occur. Use antiemetics and lavage the stomach before the procedure.
  - Intubate if there is airway compromise or risk of aspiration into the lungs.
  - Inflate the esophageal balloon only to the minimum pressure necessary to stop the variceal bleeding.
  - Using a catcher's mask may be more practical and comfortable for the recumbent patient.
- Pitfalls
  - The SB tube may induce hiccups.

Selected Reading

Bauer J, Kreel I, Kark A. The use of the Sengstaken-Blakemore tube for immediate control of bleeding esophageal varices. Ann Surg. 1974;179:273–7.

Henneman PL. Gastrointestinal bleeding. In: Rosen P, Barkin RM, editors. Emergency medicine. 6th ed. St. Louis: Mosby; 1998.

Remonda G, Morachioli N, Petruzzelli C. The use of the Sengstaken-Blakemore tube for immediate control of bleeding esophageal varices. Ann Osp Maria Vittoria Torino. 1981;24:115–20.

Sengstaken RW, Blakemore AH. Balloon tamponage for the control of hemorrhage from esophageal varices. Ann Surg. 1950;131:781–9.

Treger R, Graham T, Dea S. Sengstaken-Blakemore tube. Available at http://emedicine.medscape.com/article/81020-overview#a01. Accessed 18 May 2014.

Gastrostomy Tube Placement

78

Nathaniel Lisenbee and Latha Ganti

There are several types of gastrostomy tubes and related procedure variations:

- Procedure variations:
  - Open gastrostomy tube (G tube)
  - Percutaneous endoscopic gastrostomy (PEG) tube
  - Laparoscopic G tube
- Tube types:
  - PEG tube (Fig. 78.1)
  - Malecot tube (Fig. 78.2)
  - Balloon G tube (Fig. 78.3)
  - Low-profile G tube (nonobturated, button) (Fig. 78.4)
  - Low-profile G tube (obturated, button) (Fig. 78.5)

N. Lisenbee, MD
U. S. Air Force Medical Center Keesler, Biloxi, MI, USA
e-mail: nate4085@ufl.edu

L. Ganti, MD (✉)
Professor of Emergency Medicine, University of Central Florida, Orlando, FL, USA

Director, SE Specialty Care Centers of Innovation, Orlando Veterans Affairs Medical Center, Orlando, FL, USA
e-mail: lathagantimd@gmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_78

Fig. 78.1 Percutaneous endoscopic gastrostomy (PEG) tube


Internal retention disc
Feeding set adaptor
Universal funnel adaptor
Clamp
External fixation plate


Internal retention lugs
Universal funnel adaptor

Fig. 78.2 Malecot tube

Fig. 78.3 Balloon gastrostomy tube


Retention balloon
External fixation plate
20
15
10
5
0
Balloon port
Feeding port
Feeding port cover


Feeding port
10
5
0
Feeding port cover
Anti-reflux valve
Balloon port
Retention balloon

Fig. 78.4 Low-profile gastrostomy tube (nonobturated, button)

Fig. 78.5 Low-profile gastrostomy tube (obturated, button)


Spacer
Overnight feeding extension set
Obturator
Obturator
Bolus feeding extension set
Entristar® button

78.1 Indications

- Inability to swallow
  - Neurological deficit
  - Head trauma
  - Facial burns
  - Decreased mental status
- Need for gastric decompression
  - Gastric outflow obstruction
  - Small bowel obstruction (SBO), ileus, or volvulus
  - Intra-abdominal malignancy

78.2 Contraindications

- Absolute
  - Peritonitis
  - Ascites
- Relative
  - Hemodynamic instability
  - Coagulopathy
  - Abdominal wall infection at surgical site
  - History of gastric resection
  - Portal hypertension
  - Gastric varices

78.3 Materials and Medications

- Materials
  - Gloves
  - Lubricant
  - G tube (commercial kit) or Foley catheter
  - Sterile saline
  - External bolster
  - Multiple syringes
  - Suture material
  - Needle driver
  - Scissors
  - Stethoscope
- Medications
  - PEG tube placement
    - Moderate sedation (e.g., propofol, midazolam, fentanyl)
    - Local anesthesia (e.g., lidocaine, bupivacaine)
  - Open or laparoscopic G tube placement (not an emergency department procedure)
    - General anesthesia

78.4 Procedure (PEG Tube Replacement)

1. If the G tube is only partially removed upon patient presentation, the tube must first be removed.
2. Remove the G tube by deflating the balloon and pull gently on the tube while applying pressure to the abdominal wall at the surgical site.
3. The G tube should slide out easily with gentle traction, and the procedure should be discontinued if it does not.
4. Initially, it is important to assess the tract to determine the size and potential need for dilation.
5. If necessary for tube passage, the tract can be dilated with a cotton-tipped applicator or hemostat; however, be sure to dilate gently because it is possible to create a false tract.
6. Once the tract has been assessed, obtain the appropriate tube for replacement.
7. Initially, attempt replacement of the patient's G tube with an identical tube.
8. If an identical tube is not available, attempt placing a small Foley catheter in the tract to ensure that it stays open.
9. To initiate placement, place lubricant on the tube and carefully advance the tube into the tract.
10. Once the tube is in place, secure an air-filled syringe to the tip of the tube and insufflate a small amount of air into the stomach while auscultating to confirm passage of air into the stomach.
11. Secondary procedural confirmation can be performed by aspirating gastric contents from the tube.
12. Once placement is verified, do not forget to inflate the balloon with saline and then pull the tube backward until it abuts the inside of the stomach wall (Fig. 78.6).
13. Finally, it is very important to secure the external portion of the tube to prevent the tube from being lost into the stomach.
14. Commercial G tubes are accompanied by a bolster made specifically for the specific type of G tube in order to provide security of tube placement.



Fig. 78.6 Placement of low-profile gastrostomy tube

15. If a Foley catheter is used to maintain tract patency, an external bolster must be created using the following steps:
    - Trim a 2- to 3-in. portion from the tip of the catheter.
    - Cut two small holes just above each other on the 2- to 3-in. trimmed catheter portion.
    - Slide the external portion of the Foley catheter through both holes of the bolster.
    - Slide the bolster down the Foley catheter to the abdominal wall.
    - Secure the two ends of the bolster to the skin in order to maintain patency of the Foley catheter.
    - An interventional radiologist may also be contacted to advance the tube over a wire under fluoroscopic guidance.
16. Radiographic confirmation.
    - Typically, G tube placement is confirmed by injecting approximately 20 mL of Gastrografin® (diatrizoate meglumine, diatrizoate sodium) water-soluble contrast into the G tube, followed shortly by an abdominal x-ray.
    - Proper placement will result in an abdominal radiograph showing contrast outlining the stomach (Fig. 78.7).



Fig. 78.7 An anteroposterior abdominal radiograph after PEG tube placement and injection of 25 mL of gastrografin. The tube can be seen projecting up the left side of the abdomen, and contrast medium appears to enter the stomach lumen. The balloon is not visualized in the stomach (Reproduced with permission from: Burke DT, El Shami A, Heinle E, and Pina BD. Comparison of gastrostomy tube replacement verification using air insufflation versus gastrografin. Archives of physical medicine and rehabilitation. 2006;87(11): 1530–3.)

78.5 Pearls and Pitfalls

- Pearls
  - Even if a patient's G tube is only partially removed upon presentation to the emergency department, the tube likely needs complete removal and replacement.
  - Most G tubes are easily removed at the bedside; however, some are not able to be safely removed in the emergency department setting. Thus, if the tube does not withdraw easily, attempt to contact the proceduralist who placed the tube in order to inquire about the best method for removal.
- Pitfalls
  - Never use barium contrast when confirming G tube placement radiographically because barium can cause significant intra-abdominal damage if accidentally injected in the intraperitoneal cavity.

78.6 Complications

- Aspiration
- Surgical site infection
- Bleeding
- Pneumoperitoneum
- Accidental perforation of the colon or small bowel
- Tube dislodgment
- Peritonitis

Selected Reading

Arora G. Medscape: percutaneous endoscopic gastrostomy tube placement. Retrieved 3 Jan 2013, from http://emedicine.medscape.com/article/149665-overview#a09.

Gauderer MW, Ponsky JL, Izant Jr RJ. Gastrostomy without laparotomy: a percutaneous endoscopic technique. J Pediatr Surg. 1980; 15:872–5.

Great Ormand street hospital for children website. Retrieved 3 Jan 2013, from www.gosh.nhs.uk/EasySiteWeb/GatewayLink.aspx?alId=102263.

Sarani B. Percutaneous endoscopic gastrostomy tube placement. In: Falter F, editor. Bedside procedures in the ICU. Philadelphia: Springer; 2012. p. 113–22.

Tawa Jr NE, Fischer JE. Metabolism in surgical patients. In: Townsend Jr CM, Beauchamp RD, Evers BM, Mattox KL, editors. Sabiston textbook of surgery. 18th ed. Philadelphia: Elsevier; 2007.

Paracentesis

79

Shalu S. Patel and Bobby K. Desai

79.1 Indications

- Diagnosis of infection in ascites
- Diagnosis of malignant ascites
- Diagnosis of hemoperitoneum in traumas
- Relief of abdominal pressure/pain or respiratory compromise secondary to ascites

79.2 Contraindications

- Severe coagulopathy
  - Prothrombin time (PT) > 21 s
  - International normalized ratio (INR) > 1.6
  - Platelets < 50,000/mm^3
- Skin infection over the needle insertion site
- Acute abdomen that requires surgery
- Pregnancy
- Distended bowel
- Intra-abdominal adhesions

79.3 Materials and Medications

- 18- to 22-gauge 1.5- to 3.5-in. needle or angiocatheter, 25-gauge needle
- Lidocaine 1 or 2 % (10 mL)
- Syringes
  - 10 mL (1), 50 mL (2)
- 1-L vacuum bottle (4) (if therapeutic tap)
- Thoracentesis kit tubing or any high-pressure connection tubing (if therapeutic tap)
- Sterile gloves
- Surgical pen (recommended)
- Povidone-iodine (Betadine) or other skin antiseptic
- Sterile drape
- Sterile gauze (4 × 4)
- Band-Aid
- Bedside ultrasound (recommended)

79.4 Procedure (Fig. 79.1)

1. Position the patient supine. If possible, adjust the head of the bed to make a 45° angle to help the fluid accumulate in the pocket. Sometimes, it may also be beneficial to have the patient lie recumbent toward the site of drainage.
2. Scan the abdomen with an ultrasound to determine whether there is a pocket of fluid that can be drained. This also allows the physician to see how far the needle needs to be inserted and how deep it can be placed without risking injury to the bowel (Fig. 79.2).
3. Mark the optimal needle insertion site with a surgical pen.
4. Prepare the skin and drape in a sterile fashion.
5. Using lidocaine, anesthetize the appropriate area subcutaneously and then continue to insert the needle, and inject anesthetic through the deeper tissues until ascitic fluid can be drawn back.
6. Withdraw the needle.
7. When ready for the paracentesis, stretch the skin caudad and insert the needle or angiocatheter (connected to a syringe) while aspirating. Then, release the skin and continue to insert the needle or angiocatheter through the peritoneal wall until fluid is retrieved. This will create a "Z-track" that will decrease leakage of peritoneal fluid through the skin.

S.S. Patel, MD
Department of Emergency Medicine, Florida Hospital Tampa,
Florida Hospital Carrollwood, Tampa, FL, USA
e-mail: shalu314@gmail.com

B.K. Desai, MD (✉)
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: bdesai@ufl.edu

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_79


30° to 45°
Coronal section
Cranial
Ascitic fluid
Caudal
3
Withdraw ascitic fluid for analysis.
Cranial
Needle tract
Ascitic fluid
Caudal
4
Remove needle and allow cutaneous tissue to retract to original position.
Ascitic fluid
Transverse section
Superior epigastric artery
Rectus abdominis muscle
Inferior epigastric artery
Bladder (empty)
2
Insert needle
Caudal
1
Stretch skin 1–2 cm caudad to insertion site
Possible sites of needle insertion

Fig. 79.1 Paracentesis procedure

8. Once fluid is retrieved, push in the catheter and remove the needle portion (if used) or hold the needle steady.
9. Aspirate from the catheter to ensure that it is in the appropriate location.
10. If fluid easily is aspirated, unscrew the syringe and connect a 50-mL syringe to the needle or catheter and fill it with fluid. This may be done twice. Alternatively, if the procedure is done for therapeutic purposes, attach the tubing that is already connected to the vacuum bottle to the catheter and allow the vacuum to withdraw fluid into the collection bottles.
11. If fluid cannot be aspirated easily, the catheter can be repositioned further in the pocket or turned by 45° sequentially as needed.



Fig. 79.2 Ultrasound to determine whether there is a pocket of fluid that can be drained

12. Once the fluid is aspirated, pull out the needle or angiocatheter and hold pressure with gauze. Bleeding should be minimal.
13. Place a Band-Aid or other dressing over the site.
14. Send the fluid to the laboratory. Generally, laboratory analyses include protein, albumin, specific gravity, glucose, bilirubin, amylase, lipase, triglyceride, lactate dehydrogenase (LDH), cell count and differential, culture and sensitivity (C&S), Gram stain, acid-fast bacillus (AFB), fungal culture, cytology, and pH.

79.5 Complications

- Persistent leakage from the needle insertion site
- Abdominal wall hematoma
- Bowel perforation
- Introduction of infection
- Hypotension (after a large-volume paracentesis)
- Dilutional hyponatremia
- Hepatorenal syndrome
- Bleeding
- Postparacentesis circulatory dysfunction

79.6 Pearls and Pitfalls

- Pearls
  - The preferred site of entry is in the midline of the abdomen, below the umbilicus.
  - The serum-ascites albumin gradient (SAAG) can be used to identify the cause of the ascites. It is calculated by subtracting the albumin concentration in the ascites from the albumin concentration in the serum. A high gradient (>1.1 g/dL) suggests portal hypertension, whereas a low gradient (<1.1 g/dL) suggests other causes.
  - Postparacentesis circulatory dysfunction (PPCD) occurs secondary to hypovolemia after large-volume paracentesis (>4 L) in cirrhotic patients. It is associated with worsening hyponatremia, renal dysfunction, shorter time to ascites recurrence, and increased mortality. Prevention of PPCD has been demonstrated with the administration of 6–8 g of albumin per liter of ascites removed.
- Pitfalls
  - Polymorphonuclear lymphocyte (PMN) count greater than 250/mm^3 is diagnostic of spontaneous bacterial peritonitis.

Selected Reading

Ginès P, Cárdenas A, Arroyo V, Rodés J. Management of cirrhosis and ascites. N Engl J Med. 2004;350:1646–54.

Ginès P, Tito L, Arroyo V, et al. Randomized comparative study of therapeutic paracentesis with and without intravenous albumin in cirrhosis. Gastroenterology. 1988;94:1493–502.

Ruiz del Arbol L, Monescillo A, Jimenéz W, et al. Paracentesis-induced circulatory dysfunction: mechanism and effect on hepatic hemodynamics in cirrhosis. Gastroenterology. 1997;113:579–86.

Runyon BA. Paracentesis of ascitic fluid. A safe procedure. Arch Intern Med. 1986;146:2259–61.

Wong CL, Holroyd-Leduc J, Thorpe KE, Straus SE. Does this patient have bacterial peritonitis or portal hypertension? How do I perform a paracentesis and analyze the results? JAMA. 2008;299:1166–78.

Anal Fissure Management

80

David P. Nguyen, L. Connor Nickels, and
Giuliano De Portu

80.1 Indications

- An anal fissure is a small ulcer of the mucosa at the anal verge (Fig. 80.1).
- It is the most common cause of intense sudden rectal bleeding.
- Posterior midline anal fissures are the most common type (90 %).
  - Mostly found in young adults (30–50 y) but can occur at any age.
  - Usually associated with constipation (firm, large-caliber, painful bowel movements) or chronic diarrhea.
  - Most uncomplicated fissures resolve in 3–4 weeks.
- Can be extremely painful, during and after defecation.
- Classified as acute or chronic.
- Now believed to be caused by reduced anal blood flow in the posterior midline, anal sphincter hypertonia, and thus mucosal ischemia.

D.P. Nguyen, DO
Department of Emergency Medicine, Rush-Copley Medical Center, Aurora, IL, USA
e-mail: davidpnguyen@yahoo.com

L.C. Nickels, MD, RDMS (✉) • G. De Portu, MD
Department of Emergency Medicine, University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: cnickels@ufl.edu; gdeportu@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_80


a
b
Anal fissure
Anal fissure

Fig. 80.1 (**a**, **b**) Anal fissures

80.2 Contraindications

- Digital rectal examination should be avoided unless the diagnosis is in doubt.
- Surgical procedures are generally reserved for when medical management has failed after 1–3 months of treatment.

80.3 Materials and Medications

- Standard precautions barrier protection for the provider.
- Good light source.
- Optional emergency department treatments:
  - Topical anesthetic/preparation (Anusol [pramoxine hydrochloride; zinc oxide] with cortisone).
  - Nitroglycerin (0.2 %) or nifedipine gel (2 %) is second-line therapy (relaxes muscles and promotes blood flow).

80.4 Procedure

1. In a private, calm environment, gently spread the buttocks for complete visual inspection.
   - This may cause an increase in the patient's pain and spasming.
   - If a fissure is clearly identified, stop here.
2. Apply topical anesthetic/preparation for symptomatic relief (optional, as the physician may want to just start with the treatments that follow).
3. Discharge the patient with conservative therapy management.
4. In acute anal fissures (onset of 3–6 weeks), medical management is indicated along with dietary modifications (WASH regimen [warm baths, analgesia, stool softeners, high-fiber diet]):
   - Warm sitz baths.
     - Usually 20 min soaking each time
     - Recommended after every bowel movement
     - At least twice per day if not having regular bowel movements
   - High-fiber diet with fiber supplements.
   - Increase fluid intake.
   - May add stool softeners, if needed.
   - If chronic or the previous regimen has been exhausted, one of the following may be considered:
     - 0.2–0.4 % nitroglycerin cream applied to anal area
       - May cause headache
       - Recommend wearing a glove to prevent absorption through digital skin
     - Calcium channel blockers:
       - Topical nifedipine
       - 2 % diltiazem cream
     - Botulinum toxin A injection:
       - Controversial; may have poorer success rates than surgery
5. Provide surgical referral for nonhealing wounds.
   - Lateral internal sphincterotomy is the surgical procedure of choice.

80.5 Complications

- Infection
- Abscess
- Bleeding
- Chronic fissure formation
- Postsurgical fecal incontinence

80.6 Pearls and Pitfalls

- Pearls
  - Multiple or recurrent fissures are associated with Crohn's disease, tuberculosis, syphilis, human immunodeficiency virus (HIV), and malignancy.
- Pitfalls
  - Suspect child abuse if an anal fissure is found in a child.

Selected Reading

Feldman M, Friedman LS, Brandt LJ, editors. Sleisenger and Fordtran's gastrointestinal and liver disease. 9th ed. Philadelphia: Saunders; 2010.

Marx J, Hockberger R, Walls R, editors. Rosen's emergency medicine. 7th ed. Philadelphia: Mosby; 2010. Chapter 94: Disorders of the anorectum

Oztürk H, Onen A, Dokucu AI, Otçu S, Yağmur Y, Yucesan S. Management of anorectal injuries in children: an eighteen-year experience. Eur J Pediatr Surg. 2003;13:249–55.

Townsend CM Jr, Beauchamp RD, Evers BM, Mattox KL, editors. Sabiston textbook of surgery. 19th ed. Philadelphia: Saunders; 2012. Chapter 53: Anus

Part XI

Genitourinary Procedures

Bladder Catheterization

81

Maritza A. Plaza-Verduin and Judith K. Lucas

81.1 Indications

- Obtaining a sterile urine specimen
- Preventing or relieving urinary retention
- Close monitoring of urine output for fluid balance with an indwelling urinary catheter
- Urgent cystourethrography
- Child with contusion or burns to the perineum and at risk for meatal swelling and obstruction to urine outflow
- Temporary measure to relieve lower urinary tract obstruction
- Neurogenic bladder
- Anesthesia-induced and/or surgery-induced urinary retention has occurred.

81.2 Contraindications

- Absolute
  - Potential urethral injury from trauma
    - Pelvic fractures
    - Known trauma to the urethra
    - Blood at the meatus
- Relative
  - Recent genitourinary surgery (consult with a urologist before placing a catheter)

81.3 Materials and Medications

- Bladder catheterization kit:
  - Sterile gloves
  - Sterile drapes
  - Povidone-iodine (Betadine) solution
  - Cotton sponges or applicators for sterilizing solution
  - Lubricant
  - Specimen collection cup
  - Catheter
    - 5-French feeding tube for neonates
    - 8-French catheters for Infants
    - 10- to 12-French catheters in older children
- Local anesthetic (if desired—2 % lidocaine hydrochloride jelly)
- Absorbent pad

M.A. Plaza-Verduin, MD
Pediatric Division, Department of Emergency Medicine, Arnold Palmer Hospital for Children, Orlando, FL, USA
e-mail: mari.plazav@gmail.com

J.K. Lucas, MD (✉)
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: judithklucas@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_81

81.4 Procedure

1. Inspect the urinary catheterization tray for all the appropriate materials.
2. Place the patient supine with an absorbent pad under the buttocks.
   (a) Girls should be placed in the frog-leg position (Fig. 81.1).
3. Before sterilizing the field, locate the urethral opening.
4. Remove any powder, ointments, or medicated creams the child might have on the perineum.
5. If needed, apply anesthetic to the area.
   (a) Soak a cotton ball with anesthetic (2 % lidocaine hydrochloride jelly) and hold over the urethra opening for 2 min.
   (b) 0.5–2.0 mL of anesthetic can also be injected into the urethra.
6. Sterilize the area and place drapes appropriately, exposing the genitalia.
7. Catheterization of males
   (a) If uncircumcised, gently retract foreskin, *if possible*, for cleaning and visualization of the meatus.
   (b) Hold the penis using the nondominant hand at a 90° angle from the body (Fig. 81.2).
   (c) Lubricate the catheter tip.
   (d) Insert the lubricated catheter into the meatal opening and advance it while applying gentle traction to the penis from the base of the penis.
   (e) If resistance is met, maintain gentle pressure with the catheter.
      - *Do not attempt to force the catheter that could create a false tract or traumatic fistula.*
   (f) Advance the catheter until urine is obtained, approximately inserting the catheter to just beyond the penile length.
   (g) Once completed, gently withdraw the catheter.
   (h) Clean the area, wiping away the Betadine solution.
   (i) If uncircumcised, pull the foreskin over the glans to avoid paraphimosis.
8. Catheterization of females
   (a) Sterilization of the area should occur from anterior to posterior.
   (b) Have an assistant hold the labia majora apart.
      (i) If no assistant is available, use the nondominant hand to hold the labia apart.
         - Holding the labia majora with a gentle outward, lateral, and upward traction will help visualize the meatus (Fig. 81.3).



Fig. 81.1 Infant held in the frog-leg position for catheterization

Fig. 81.2 Bladder catheterization of a male; penis should be held perpendicular to the body




Gentle lateral and
outward traction
of labia majora

Fig. 81.3 Positioning of labia for better visualization of the meatus

- Downward displacement of the cephalad aspect of the vaginal introital fold with a cotton-tipped applicator can help visualize the urethral meatus (Fig. 81.4).

(c) Lubricate the catheter tip.

(d) Insert the lubricated catheter into the meatal opening. Advance slowly until urine is obtained (Fig. 81.5).

(e) Once completed, gently withdraw the catheter.

(f) Clean area, wiping away the Betadine solution.

Fig. 81.4 Better visualization of the meatus is achieved with downward displacement of the introital mucosa





Fig. 81.5 Bladder catheterization of a female

81.5 Complications

- Urethral or bladder injury
- Infection if sterile field not maintained
- Paraphimosis owing to failure to restore a retracted foreskin to its normal position

81.6 Pearls and Pitfalls

- Pearls
  - It is not necessary to fully retract a foreskin. This only causes trauma and increases the likelihood of paraphimosis. As the infant/boy ages, the foreskin will loosen and the naturally occurring adhesions will spontaneously release.
  - The urethral meatus in an infant female is usually tucked just above the redundant hymen (as opposed to the more anteriorly located meatus in the adult woman) and often looks like a dimple or small blind pouch.
  - Using viscous lidocaine in lieu of, or blended with, lubricant anesthetizes the meatus and urethra as the catheter passes.
  - Have the specimen cup at the ready because, at times, once the (usually cold) Betadine or antiseptic solution is applied, the infant often releases the urine and it can be caught, literally, midstream.
  - In the uncircumcised male, be certain to return the foreskin over the glans to avoid paraphimoses.
- Pitfalls
  - If catheterizing a child in search of infection, send a urine culture regardless of the urinalysis results because the younger infants can have false-negative urinalysis and still have positive cultures.

Selected Reading

American Academy of Pediatrics, Subcommittee on urinary tract infection, steering committee on quality improvement and management. Urinary tract infection: clinical practice guideline for the diagnosis and management of the initial UTI in febrile infants and children 2 to 24 months. Pediatrics. 2011;128:595–609.

Beno S, Schwab S. Bladder catheterization. In: King C, Henretig FM, editors. Textbook of pediatric emergency procedures. 2nd ed. New York: Lippincott Williams & Wilkins; 2008.

Cheng YW, Wong SN. Diagnosing symptomatic urinary tract infection in infants by catheter urine culture. J Paediatr Child Health. 2005;41:437–40.

Gerard LL, Cooper CS, Duethman KS, et al. Effectiveness of lidocaine lubricant for discomfort during pediatric urethral catheterization. J Urol. 2003;170:564–7.

Kozer E, Rosenbloom E, Goldman D, et al. Pain in infants who are younger than 2 months during suprapubic aspiration and transurethral bladder catheterization: a randomized, controlled study. Pediatrics. 2006;118:e51–6.

Pelvic Examination and Wet Preparation

82

Nauman W. Rashid, Elaine B. Josephson,
and Muhammad Waseem

82.1 Indications

- Lower abdominal or pelvic pain
- Vaginal bleeding or discharge
- Cancer screening
- Pregnancy
- Exposure to sexually transmitted disease
- Sexual assault

82.2 Contraindications

- Physical or mental disability
- Recent gynecological surgery
- Third-trimester pregnancy with bleeding
- Premenstrual females (may not be indicated in adolescents, who are not sexually active, unless there is discharge, bleeding, suspicion for abuse, or a foreign body)
- If a speculum examination is necessary, examination under general anesthesia should be considered.

82.3 Materials and Medications

- Examination table with stirrups (Fig. 82.1)
- Reliable light source
- Appropriately sized speculum (Fig. 82.2)
- Endocervical brush or spatula
- Culture swab for gonorrhea and chlamydia
- Large cotton swabs for vaginal discharge or bleeding (Fig. 82.2)
- pH paper
- Saline and potassium hydroxide dropper bottles for wet preparations
- Lubricating gel
- Disposable gloves (Fig. 82.2)
- Small stool or chair for examiner

82.4 Procedure

1. Obtain permission from patient before beginning examination.
2. Chaperone should be present (medical staff member).
3. Make sure the examination table is clean and appropriately draped.
4. Have the patient in a loose-fitting gown.
5. Place the patient on the examination table in the lithotomy position with both feet in the stirrups and have the patient's pelvis as close to the edge of the table as possible.
6. Turn on the light source and adjust for optimum illumination. Put on the disposable gloves.
7. Communicate the procedure well to the patient.
8. Begin the examination with inspection and palpation of the abdomen.
9. Examine the external genitalia. Evaluate the skin, labia minora and majora, clitoris, urethral meatus, vaginal

---

N.W. Rashid, MD
Department of Emergency Medicine, WellStar Kennestone
Hospital, Marietta, GA, USA
e-mail: naumanrashid@hotmail.com

E.B. Josephson, MD
Department of Emergency Medicine, Lincoln Medical and Mental
Health Center, Weill Cornell Medical College of Cornell
University, Bronx, NY, New York
e-mail: elaine.Josephson@nychhc.org

M. Waseem, MD (✉)
Department of Emergency Medicine, Lincoln Medical and Mental
Health Center, New York, NY, USA
e-mail: waseemm2001@hotmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_82



06/30/2011 21:11

Fig. 82.1 Examination table with stirrups



06/30/2011 21:13

Fig. 82.2 Gloves, speculum, and swabs

canal, and Bartholin glands (Fig. 82.3). Look for skin abnormalities, lesions, masses, rashes, excoriation, abscesses, discharge, bleeding, or trauma. Palpate for tenderness.

10. Lubricate the appropriate-size speculum (mostly medium size). Insert the speculum through the vaginal opening with gentle downward pressure. The speculum should advance without any resistance until the cervical os is visualized.
11. Inspect the vaginal walls for any lesions or masses (Fig. 82.4). The cervical os is inspected to see if it is open or closed. Cervical cultures for gonorrhea and chlamydia are obtained with a cotton swab and sent for microbiology.
12. A sample of the discharge or bleeding is taken with a large cotton swab. The color, odor, and amount should be noted. The pH of the vaginal discharge can be evaluated. Normal pH is less than 4.5. An elevated pH indicates an infection (Table 82.1).

Fig. 82.3 Female external genitalia


Clitoris
External urethral orifice
Vaginal vestibule
Fossa navicularis
Perineum
Mons veneris
Labium mojus
Labium minue
Vaginal introitus
Hymen
Posterior commissure


Peritoneum
Oviduct
Ovary
Uterus
Ilium
Broad ligament
Obturator internus muscle
Cardinal ligament
Levator ani muscle
Ischiorectal fossa
vagina

Fig. 82.4 Female internal genitalia

Table 82.1 Wet preparation interpretation

Organism	Preparation	pH	Microscope	Cervix	Appearance of discharge
Bacterial vaginosis	Saline	>4.5	Clue cells	Redness	Thin, milky, fishy odor
Trichomoniasis	Saline	>4.5	Motile flagella	Strawberry red	Yellow-green, foamy
Yeast	Potassium hydroxide	3.8–4.5	Budding yeast pseudohyphae	Normal	White, cottage cheese

13. Next, a bimanual examination should be performed (Fig. 82.5). Lubricating gel is applied to the nondominant gloved hand and the index and middle finger are inserted into the vagina until the cervix is felt. The other hand is placed on the abdomen to palpate the uterus and ovaries. Pressure is applied to the abdomen while the vaginal hand is elevated upward.
14. The cervix is palpated to elicit any cervical motion tenderness. The uterus is palpated and the size, position, and mobility are noted. The adnexa are examined for masses and tenderness. If a mass is palpated, the size, mobility, consistency, and tenderness are noted.
15. The final part of the pelvic examination is the rectovaginal examination. Lubricate the index and middle fingers

of the left hand. Place the index finger in the vagina and the middle finger in the rectum. Palpate for any fistulas or masses. With the finger, also palpate the uterosacral ligaments, the broad ligaments, and the pelvic side walls. The finger is then gently removed and any feces are inspected for mucous or occult blood.

16. A wet preparation is made by obtaining a sample of the vaginal discharge and placing it in a vial mixed with saline solution. A drop of the solution is placed on a microscopic slide and examined under high magnification for the presence of clue cells (Fig. 82.6) diagnostic for bacterial vaginosis and trichomonads (Fig. 82.7) diagnostic for trichomoniasis. For yeast, two drops of the solution is mixed with two drops of potassium hydroxide. Presence of hyphae is diagnostic of candida (yeast) species (Fig. 82.8)



Fig. 82.5 Bimanual pelvic examination

82.5 Complications

- Urinary tract infection
- Vaginal bleeding
- Cramping

82.6 Pearls and Pitfalls

- Pearls
  - Good communication is essential to ensure the patient is comfortable and not anxious.
  - The chaperone should be a medical staff member.
  - Do not skip the pelvic examination if the patient is menstruating.
- Pitfalls
  - Do not forget to perform a complete abdominal exam along with the pelvic exam to rule out any GI etiology.
  - In older females (>50), perform the DRE for a stool occult sample as a possible source of bleeding.

Fig. 82.6 Photomicrograph of a vaginal smear specimen depicting two epithelial cells, a normal cell, and an epithelial cell with its exterior covered by bacteria giving the cell a roughened, stippled appearance known as a "clue cell" (From the CDC Public Health Image library)





Fig. 82.7 Photomicrograph of trichomonads in wet mount prepared witvh physiological saline (From the CDC Public Health Image library)



Fig. 82.8 *Candida albicans* from vaginal wet prep (From the CDC Public Health Image library)

Selected Reading

Brown J, Fleming R, Aristzabel J, Gishta R. Does pelvic exam in the emergency department add useful information? West J Emerg Med. 2011;12:208–12.

Butler J, Barton D, Shepherd J, Reynolds K, Kehoe S. Gynaecological examinations. Good not bad medicine. BMJ. 2011;342:d1760.

Carr SE, Carmody D. Outcomes of teaching medical students core skills for women's health: the pelvic examination educational program. Am J Obstet Gynecol. 2004;190:1382.

Katz VL, Lentz G, Lobo RA, Gershenson D, editors. Comprehensive gynecology. 5th ed. Philadelphia: Mosby; 2007.

Tiemstra J, Chico P, Pela E. Genitourinary infections after a routine pelvic exam. J Am Board Fam Med. 2011;24:296–303.

Bartholin Gland Abscess/Cysts Drainage

83

Holly H. Charleton, Marylin Otero, Diane F. Giorgi,
and Joseph A. Tyndall

83.1 Indications

- Bartholin gland cysts larger than 1 cm or painful
- Bartholin gland abscess

83.2 Contraindications

- Absolute
  - None
- Relative
  - Recurrent/complex abscess requiring general anesthesia in operating room
  - Coagulopathy

83.3 Procedure Types

- Incision and drainage (I&D)
- Iodoform packing
- Word catheter
- Jacobi ring catheter
- Silver nitrate stick ablation (after I&D)

H.H. Charleton, MD
Emergency Department, The Brooklyn Hospital Center,
Brooklyn, NY, USA
e-mail: Hcmd08@gmail.com

M. Otero, MD
Department of Emergency Medicine, Franklin Hospital,
Valley Stream, NY, USA
e-mail: momd42@hotmail.com

D.F. Giorgi, MD
Department of Emergency Medicine, Mount Sinai Queens,
New York, NY, USA
e-mail: dgiorgi@earthlink.net

J.A. Tyndall, MD (✉)
Department of Emergency Medicine, University of Florida Health,
Gainesville, FL, USA
e-mail: tyndall@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_83

83.4 Materials

- Sterile gloves
- Sterile skin preparatory solution/swabs and drapes
- Lidocaine 1 % (local anesthesia); may give oral or intravenous sedatives or analgesics
- Needles 25 or 27 gauge with 3-mL syringe for lidocaine injection
- Scalpel #11 for incision
- Culture swab
- Hemostat or suture kit
- Word catheter (if choosing that method) (Fig. 83.1)
- Jacobi ring catheter (if choosing that method) (Fig. 83.2)
- 3-mL syringe with saline for inflation of Word catheter balloon
- Silver nitrate stick (if choosing that method)
- Gauze pads for bleeding and effluents
- Iodoform packing



Fig. 83.1 Word catheter (inflated/deflated)



Fig. 83.2 Jacobi ring catheter

83.5 Procedures

83.5.1 Incision and Drainage

1. Obtain informed consent from the patient.
2. Place the patient in the lithotomy position.
3. Prepare the cyst/abscess and the surrounding area with sterilizing fluid/swabs and drape the area, leaving the cyst/abscess accessible for the procedure (Fig. 83.3)
4. May need to hold traction to the labia to fully expose the cyst/abscess (Fig. 83.4).
5. Inject 1–4 mL of lidocaine at the planned site of incision (Fig. 83.5).
6. Hold one side of the cyst/abscess with a forceps or hemostat to maintain traction while incising.
7. With a #11 scalpel, make an incision approximately 0.5–1 cm and 1.5 cm deep in the introitus or behind the hymnal ring to prevent vulvar scarring. The incision should be made through the fluctuant area of the abscess on the mucosal surface. The incision should be linear and large enough to fit the Word catheter (if using that method).
8. Drain the cyst/abscess completely, using the hemostat to break up the loculations.
9. Culture the abscess with a swab and send to microbiology.
10. All previous steps should be done regardless of the procedure type to follow.



Fig. 83.3 Cyst/abscess accessible for the procedure


Oval incision in vulvar mucosa
Oval incision in cyst wall

Fig. 83.4 May need to hold traction to the labia to fully expose the cyst/abscess



Fig. 83.5 Inject 1–4 mL of lidocaine at the planned site of incision

83.6 Iodoform Packing

1. Pack with iodoform packing, grasping the end of the packing material with a hemostat and inserting deeply within the cavity.
2. The cavity should be filled with the packing material and a small piece left exposed (for ease of retrieval during follow-up).
3. Clean the site and cover with gauze.

83.6.1 Word Catheter

- After culturing the abscess
  1. Place the Word catheter into the incision site as deep as possible (if the incision is too large, the catheter will slip out) (Fig. 83.6).
  2. Inflate the balloon of the Word catheter with 2–3 mL of saline or water injected into the hub with a needle and syringe (Fig. 83.7).
  3. Tuck the end of the Word catheter into the vagina for comfort purposes.
  4. The catheter should remain in place for 4 weeks to allow for epithelialization of the tract.



Fig. 83.6 Place the Word catheter into the incision site as deep as possible



Fig. 83.7 Inflate the balloon of the Word catheter with 2–3 mL of saline or water injected into the hub with a needle and syringe

83.6.2 Jacobi Ring Catheter

1. Grasp one end of the Jacobi ring with a hemostat and pass it through the initial incision site.
2. At this time, use a hemostat to break loculations and culture the material for microbiology.
3. Pull the Jacobi ring through the abscess cavity (be careful not to pull the suture out of the catheter) and make a second incision to pull the catheter out through it.
4. The two ends of the catheter are then tied, forming a ring.

83.6.3 Nitrate Stick

- After sending the culture
    1. Take the silver nitrate stick and place it deep within the cyst/abscess cavity (Fig. 83.8).
    2. The patient is instructed to return in 48 h for removal of the remaining nitrate material and necrotic tissue and wound cleaning.
    3. The patient should be warned of side effects including pain, chemical burns of nearby tissue, edema, discharge, and scarring.



Fig. 83.8 Silver nitrate sticks

83.7 Aftercare

- Follow-up care is required after each of these procedures.
- A high-risk patient (e.g., diabetic) may need to be covered with broad-spectrum antibiotics.
- Pregnant women are also considered high risk and should be given antibiotics and followed closely.
- The patient should be instructed to remain on pelvic rest (nothing in vagina) while the catheter is in place, wear a pad owing to discharge, use sitz baths and analgesics for pain control, and follow up 1–2 days after the procedure.

Although a few other methods are available for draining Bartholin cyst/abscess including marsupialization, carbon dioxide laser vaporization, and excision, these methods are typically done by gynecologists and rarely, if ever, performed by an emergency department physician.

Selected Reading

Chen KT, Robert LB, Falk SJ. Disorders of Bartholin's gland. Available at: WWW.Uptodate.com.
Chen KT, Robert LB, Falk SJ. Word catheter placement for treatment of Bartholin's cysts and abscesses. Available at: WWW.Uptodate.com.
Gennis P, Li SF, Provataris J, et al. Jacobi ring catheter treatment of Bartholin's abscesses. Am J Emerg Med. 2005;23:414–5.
Vitaly KA, Mosquera C. Novel technique for management of Bartholin gland cysts and abscesses. J Emerg Med. 2008;36:388–90.
Wechter ME, Wu JM, Marzano D, Haefner H. Management of Bartholin duct cyst and abscesses: a systematic review. Obstet Gynecol Surv. 2009;64:395–404.

84

Sexual Assault Forensic Examination

Rajnish Jaiswal, Mary T. Ryan, and Muhammad Waseem

When the survivor of a sexual assault seeks medical care, in addition to addressing their medical needs, their forensic needs must also be addressed. This is best achieved by a specialist examiner, who is trained to conduct a Sexual Assault Forensic Examination (SAFE). When the examiner is a nurse, she or he is referred to as a Sexual Assault Nurse Examiner (SANE). In designated centers, the forensic examiner and the nurse, physician, law enforcement officials, social workers, and patient advocates work together as a Sexual Assault Response Team (SART).

The process of caring for survivors of sexual assault continues to evolve and reflects the advances in forensic science, judicial reform and our understanding of assault survivor psychology.

However, when an emergency medical condition exists, it should be addressed by the designated medical team. The role of the SAFE examiner becomes secondary in these situations. Life- or limb-threatening injuries always take priority over forensic evidence collection, although emergency medical care can often be rendered without compromising existing evidence.

84.1 Indications

- Survivors of sexual assault who seek and consent to forensic examination.
- The upper limit of time for evidence collection varies from state to state (e.g., 96 h in New York State [1]).

84.2 Contraindications

- Absolute
  - If the survivor does not consent to evidence collection
- Relative
  - If the upper time limit has been exceeded

84.3 Materials and Medications

- Ideally, a designated SAFE room should be available.
- Standardized sexual assault evidence collection kits.
- Gloves.
- Camera.
- Portable light source.
- Swab dryer.
- Wood's lamp.
- Anoscope.
- Colposcope, ideally with a camera.
- Support material for survivors: information pamphlets, clothing.
- Prophylactic medications: antibiotics, antiretrovirals, contraceptives.

R. Jaiswal, MD
Department of Emergency Medicine, New York Medical College,
Metropolitan Hospital Center, New York, NY, USA
e-mail: Rajnish.Jaiswal@gmail.com

M.T. Ryan, MD • M. Waseem, MD (✉)
Department of Emergency Medicine, Lincoln Medical and Mental
Health Center, New York, NY, USA
e-mail: maryryanmd@aol.com; waseemm2001@hotmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_84

84.4 Procedure: "Prepare the Patient, Prepare the Room"

1. Informed Consent
    - A separate consent is required for the SAFE. Obtaining consent has important psychosocial implications for the survivor and returns "control" and "choice" to him or her at this critical time [2]. If the survivor chooses not to undergo a SAFE, the examiner must respect his or her decision. Consent is not an "all-or-none" phenomenon and survivors can chose to consent to some steps and decline others. The examiner should be respectful of their decision.
    - Consent for the SAFE should include consent for evidence collection, forensic photography, release of evidence to law enforcement, and permission to discuss the findings of the SAFE with investigators.
2. Law Enforcement Involvement
    - State laws vary in terms of reporting requirements for sexual assault. The examiner should be familiar with the requirements in the state in which she or he practices. All survivors should be offered law enforcement involvement and the benefits of doing so should be outlined to them.
3. Evidence Collection
    - Sexual assault evidence collection kits are specialized preassembled kits containing essential materials for collecting and preserving evidence (Fig. 84.1). The kit contains written instructions, swabs, envelopes, body diagrams, and an integrity seal for the examiner's use.
4. Forensic Interview and History Taking
    - The forensic interview is the first step in the SAFE process. It is a therapeutic as well as a forensic exercise, designed to establish rapport with the survivor, offer support, and gather information to help guide the medical care and direct evidence collection. Acquiring information is a continuous process that ends only when the survivor-SAFE interaction ends.
    - The survivor's exact words with quotation marks should be recorded. A simple factual account of events should be documented. Avoid biased or prejudicial language, such as "allegedly" or "claims." Relevant information includes the time of the assault, the type of contact involved (offender-survivor and survivor-offender), the number of people involved, and the survivor's activities since the assault. A basic medical and obstetrical-gynecological history is also relevant. The SAFE interview is not an investigative interview. Investigation of the sexual assault is the role of law enforcement.
5. General Physical Examination
    - The patient should be asked to undress over a paper sheet to allow any trace evidence to fall and be collected. She or he should be given a gown to wear. A systematic head-to-toe examination should be undertaken. Identify any injuries, no matter how minor. Document them in writing, on a body diagram (Fig. 84.2), and, when possible, with photography. Pay attention to areas that can be easily overlooked: in the mouth, behind the ears, under the chin, and the soles of the feet, for example. Take time to palpate the scalp for areas of tenderness.
6. Injury Documentation
    - Always take time during documentation. Describe the type of injury—abrasion, contusion, laceration, or bite mark. Document the size and site of the injury, ideally include a measuring device in the photograph. A commonly used scale is the one provided by the American Board of Forensic Odontology (ABFO) (Fig. 84.3). If an injury appears to have a shape or pattern (e.g., linear, circular, curvilinear, petechial), describe it without drawing specific conclusions.
7. Bite Marks
    - Bite marks require additional evaluation because they may have salivary trace evidence associated with them. In addition to being described and photographed, they should be swabbed and the dried swabs included in the evidence collection kit.
8. Forensic Pelvic Examination
    - The purpose of the genital examination (external and speculum) is to identify injury and collect forensic evidence.
9. Inspection
    - Visually examine the external genitalia. Separate the labia and look in skin folds and at the posterior fourchette for injury. The TEARS mnemonic (T = tear, E = ecchymosis, A = abrasions, R = redness, S = swelling) is a useful tool while inspecting and documenting. External genital injury findings can be photographed using a standard camera (digital or conventional 35 mm) or a colposcope camera for additional magnification.
10. Speculum Examination
    - Insert a moistened speculum under a good light source and inspect the vault and cervix for any injuries or possible trace evidence for collection (pooled secretions, hair, retained condom, debris). A colposcope (Fig. 84.4) is a useful adjunct and allows for magnification and assists in injury identification and photodocumentation.
    - Bimanual pelvic examination may be a part of some protocols but is not mandatory.
11. Rectal Examination
    - Inspect the area looking for fissures, bleeding, or secretions. Anoscopy, if indicated by this history and permitted by the survivor, should be performed and the findings documented and photographed.

12. Evidence Collection
    - The evidence collection kit should be opened and the contents laid out in a systematic way. Once the evidence collection kit has been opened, it cannot be left unattended at any time. Each envelope should be labeled with the survivor's name and the time and date of collection. The required swabs and slides are included in the kit.
13. Collection of Biological Material
    - Evidence collection will include oral, anal, and vaginal swabs. Swabs should be allowed to air dry before being placed back in the envelopes. Trace evidence should be collected and may include nail scrapings, dried secretions, loose hair collection, and possible foreign bodies (e.g., soil, condom). A Wood's lamp may help the examiner to identify dried secretions on skin or clothing. When each step is completed, the envelope will be closed, sealed, and signed by the examiner and returned to the box.
    - When completed, the Sexual Assault Evidence Collection Kit (SAECK) is closed, the provided evidence seal placed on the box, and the seal signed and dated by the examiner. The evidence is then given to law enforcement (if the patient consents) or maintained in a predesignated, secure locked area if law enforcement is not yet involved in the case. Each time evidence is passed from person to person, the transfer must be documented in writing to ensure it is not compromised or tampered with in any way. This is the underlying principle of maintaining a "Chain of Custody." This chain must be maintained for evidence to be admissible in court.
14. Collection of Clothing
    - Clothing may be considered "evidence" and collected in some cases. Depending on the case, this may include underwear and any feminine hygiene products. These may fit in the evidence collection kit itself. Larger items of clothing and/or shoes will need to be collected separately. They should be placed in an appropriately sized paper bag and labeled with the patient's name. The bag should be sealed, signed, and dated by the examiner in the same way as all other evidence. Any additional evidence should remain with the SAECK. The survivor should be provided with replacement clothes and underwear.
15. Forensic Photography
    - Although the examiner is not expected to be a specialized forensic photographer, photodocumentation of injuries is an important part of the SAFE. A separate consent is required. Either a conventional 35-mm camera or a high-resolution digital camera is acceptable.
    - At least one image should include the survivor's face or some form of identifying marks. Near and far images should be taken. The camera should be held at 90° to the surface to avoid distortion of the image. A tape measure should be included when an injury is being photographed. An identifier, like medical record number or case number, should be visible in the image if possible. The examiner should document in the records that photographs were taken.
16. Investigations
    - Baseline complete blood count (CBC), chemistry panel, and liver function tests are generally drawn before initiation of human immunodeficiency virus (HIV) prophylaxis. Serologic tests for syphilis, hepatitis B virus (HBV), hepatitis C virus, and HIV should be obtained. Urine should be sent for analysis and pregnancy testing. Urine for toxicology may be useful in selected cases. Testing for gonorrhea and chlamydia before starting prophylactic antibiotics may be undertaken, but this remains controversial.
17. Prophylaxis
    - Survivors should be offered prophylaxis against pregnancy, common sexually transmitted infections, HBV, and HIV. The current Centers for Disease Control and Prevention (CDC) guidelines recommend the following:

    (a) HBV vaccination should be offered to sexual assault victims at the time of the initial examination if they have not been previously vaccinated. Postexposure HBV vaccination, without hepatitis B immunoglobulin (HBIG), should adequately protect against HBV infection. Follow-up doses of vaccine should be administered 1–2 and 4–6 months after the first dose.

    (b) An empirical antimicrobial regimen for chlamydia, gonorrhea, and trichomonas should be offered.
      - Recommended regimens:
        - *Ceftriaxone* 125 mg intramuscularly in a single dose
        - *PLUS*
        - *Metronidazole* 2 g orally in a single dose
        - *PLUS*
        - *Azithromycin* 1 g orally in a single dose
        - *OR*
        - *Doxycycline* 100 mg orally twice a day for 7 days

    (c) Emergency contraception protocols are state and institution specific. A negative pregnancy test should be documented before evidence collection. Commonly prescribed regimens are "Plan B," "Ovral," and the recently approved "Ella."

    (d) Update tetanus profile if indicated.

    (e) HIV postexposure prophylaxis.
      - All patients with significant exposure should receive pretest counseling and postexposure prophylaxis as per CDC guidelines [3]. The regimens are complex (Table 84.1).


FDLE
SEXUAL ASSAULT EVIDENCE KIT
Integrity Seal
BUCCAL/CHEEK STANDARD
CERVICAL/ANAL/ORAL/MISC.
VAGINAL SWABS
PUBIC HAIR COMBINGS
UNDERWEAR
Drug Facilitated Sexual Assault
BLOOD AND URINE SPECIMEN COLLECTION KIT

Fig. 84.1 Sexual assault evidence collection kit


Male genitalia
Clitoris
Urethral meatus
Labia minora
Fourchette
Perineum
Mons veneris
Vestibule
Labia majora
Hymen
Vaginal introitus
Bartholin gland
duct orifice
Anus
Female genitalia
Oral
Anal
Cervical Observation

Fig. 84.2 Traumagram



Fig. 84.3 American Board of Forensic Odontology (ABFO) scale (Courtesy Bronx SART Program)



Fig. 84.4 Colposcope (Courtesy Bronx SART Program)

Table 84.1 Postexposure prophylaxis as per Centers for Disease Control and Prevention (CDC) guidelines [3]

Regimen	Dosage
Zidovudine (Retrovir, ZDV, AZT)+lamivudine (Epivir®, 3TC); *available as Combivir™*	ZDV: 300 mg twice daily or 200 mg three times daily, with food; total: 600 mg daily 3TC: 300 mg once daily or 150 mg twice daily Combivir: one tablet twice daily
Zidovudine (Retrovir, ZDV, AZT)+emtricitabine (Emtriva, FTC)	300 mg twice daily or 200 mg three times daily, with food; total: 600 mg/day, in 2 or 3 divided doses; FTC: 200 mg (one capsule) once daily
Tenofovir DF (Viread, TDF)+lamivudine (Epivir, 3TC)	300 mg once daily; 3TC: 300 mg once daily or 150 mg twice daily
Tenofovir DF (Viread, TDF)+emtricitabine (Emtriva, FTC)	TDF: 300 mg once daily; FTC: 200 mg once daily Truvada: one tablet daily

AZT azidothymidine, *FTC* emtricitabine, *3TC* lamivudine, *TDF* tenofovir disoproxil fumarate, *ZDV* zidovudine

84.5 Pearls and Pitfalls

- Pearls
  - Survivors will need to have both medical and psychosocial follow-up. Medical referrals should include gynecology and primary care for follow-up of their baseline serology, testing and completion of HBV vaccination regimen, and so on.
  - Referrals for counseling and information with 24-h hotlines should be provided**.** Recovery from a sexual assault is a process and is best achieved by a long-term support network [4].
- Pitfalls
  - It is estimated that survivors are men in fewer than 10 % of cases, although sexual assault in males appears to be greatly underreported. The same principles for evidence and prophylaxis apply for the SAFE.

References

1. Department of Health, State of New York. Acute care of the adult patient reporting sexual assault. 2004.
2. Criminal Victimization in the United States 2010. Washington, DC: US Department of Justice, Office of Justice Programs, Bureau of Justice Statistics; 2010.
3. Varghese B, Maher JE, Peterman TA, et al. Reducing the risk of sexual HIV transmission. Sex Transm Dis. 2002;29:38–43.
4. Parekh V, Brown CB. Follow up of patients who have been recently sexually assaulted. Sex Transm Infect. 2003;79:349.

Treatment of Priapism

85

Jeffrey Kile, Katrina John, and Amish Aghera

85.1 Indications

- Ischemic (“low-flow”) priapism

85.2 Contraindications

- To cavernosal aspiration/irrigation
  - Nonischemic (“high-flow”) priapism
  - Overlying cellulitis
  - Uncontrolled bleeding disorder
  - Skin infection at the site of injection
- To intracavernosal injection of vasoactive agents (α-adrenergic sympathomimetics)
  - Severe hypertension
  - Dysrhythmias
  - Monoamine oxidase inhibitor use

85.3 Materials and Medications (Fig. 85.1)

- Sterile gloves
- Antimicrobial solution and swabs
- 4×4 gauze sponges
- Local anesthetic (1 % lidocaine 5 mL and 0.5 % bupivacaine 5 mL, without epinephrine)
- 10-mL syringe
- 20-mL syringe
- 19- or 21-gauge butterfly or straight needles (2)
- Blunt needle
- 27-gauge needle
- Normal saline, 1000 mL
- Phenylephrine 1 % solution (10 mg/mL), 1 mL

J. Kile, MBBS, PhD, MPH (✉) • K. John, MBBS
Department of Emergency Medicine, Eisenhower Medical Center,
Rancho Mirage, CA, USA
e-mail: jeffrey.kile@gmail.com; trenjohn@me.com

A. Aghera, MD
Department of Emergency Medicine, Maimonides Medical Center,
New York, NY, USA
e-mail: aaghera@maimonidesmed.org

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_85

Fig. 85.1 Materials and medications


APLICARE
POVIDONE-IODINE SOLUTION
16 FL Oz. (473 mL)
Marcaine® 0.5%
LIDOCAINE HCl
10 mg/mL

85.4 Noninvasive Therapy Preprocedure

1. Administer analgesia (e.g., parenteral opiates, benzodiazepines).
2. Administer subcutaneous terbutaline as soon as the diagnosis is suspected (0.25–0.5 mg subcutaneous in quadriceps, deltoid, or gluteus maximus) and repeat after 20 min if necessary.
   - If resolution of priapism does not occur with subcutaneous terbutaline, proceed to cavernosal aspiration.

85.5 Procedures

85.5.1 Dorsal Penile Nerve Block Procedure

1. Position the patient in the supine position.
2. Apply povidone-iodine solution liberally to the penis and scrotum using a 4×4 gauze pad.
3. Clean the glans and shaft of the penis in a circular motion.
4. Establish a sterile field by placing drapes between the scrotum and the shaft, above the shaft, and on either side (Fig. 85.2).
5. Draw up 5 mL 0.5 % bupivacaine and 5 mL 1 % lignocaine (both without epinephrine) into a single syringe.
6. Using a 27-gauge needle, inject local anesthetic superficially to raise skin wheals at the (dorsal) 2 and 10 o'clock positions as proximal to the base of the penis as possible.
7. Insert the needle through the wheal at the 2 o'clock position at the base of the penis until it contacts the pubic symphysis.
8. Withdraw the needle slightly and walk the needle in a caudal fashion down the pubis until the needle passes immediately below the symphysis and advance to a depth of 5 mm deeper than the depth of the pubic symphysis (Fig. 85.3).
   - A transmitted "pop" may be felt as the needle penetrates the superficial penile fascia beneath the symphysis.
9. Aspirate to confirm the tip of the needle is not within the lumen of a vessel.
10. Inject 4 mL of solution.
11. Repeat the injection of local anesthetic as outlined at the 10 o'clock position of the penile base to anesthetize the right dorsal penile nerve (Fig. 85.4).



Fig. 85.2 Priapism in sterile field



Fig. 85.3 Schematic anatomy of dorsal penile nerve block



Fig. 85.4 Injection of local anesthetic

85.5.2 Cavernosal Aspiration Procedure

1. Attach a 19- or 21-gauge needle to a syringe.
2. Puncture the corpus cavernosa at the 2 o'clock or 10 o'clock position (~+60° or −60° from the midline) on the suprapubic aspect of the penis approximately 3 cm from the penile base, directing the needle straight toward the center of the ipsilateral cavernosum.
    - Never use the glans as a puncture site during this procedure.
3. Advance the needle slowly while drawing back on the plunger until blood is visible in the syringe (blood is usually easily aspirated).
4. Once blood is obtained, do not advance further, stabilize the needle, and use one hand to aspirate 20–30 mL of blood while milking the corpus with the free hand (Fig. 85.5).
    - The needle should not be advanced further once blood is visible in the syringe to minimize the risk of injury to the cavernosal artery.
    - Avoid excessive negative pressure on the plunger because this often halts aspiration.
    - If detumescence is not achieved using the above steps, proceed with the following steps.
5. Insert an irrigation needle by puncturing the corpus cavernosum on the same side of the penis punctured with the aspiration needle, approximately 1 cm from the penile base.
6. Irrigate the oxygen-depleted blood in the cavernosa by injecting 20–30 mL of 0.9 % normal saline via the proximal needle in exchange for the blood aspirated (Fig. 85.6).
7. Repeat the cycle of aspiration of 20- to 30-mL volumes of blood from the distal needle followed by irrigation with an equal volume of 0.9 % normal saline via the proximal needle until flow into the syringe of dark red (oxygen-depleted) blood ceases and bright red (oxygen-rich) blood is aspirated or until detumescence is achieved (Fig. 85.7).
    - When removing the needle after cavernosal aspiration, compress the puncture site for approximately 1 min to prevent hematoma formation.
8. Wrap the detumescent penis in gauze or an elastic bandage to prevent return of priapism and to compress the puncture site(s) (Fig. 85.8).



Fig. 85.5 Aspiration of cavernosal blood

Fig. 85.6 Aspiration and irrigation of cavernosal blood





Fig. 85.7 Detumescence



Fig. 85.8 Detumescent penis wrapped in compression dressing

85.5.3 Intracorporeal Injection Procedure

1. Prepare a diluted concentration of 100 μg/mL (1 mg/10 mL) phenylephrine solution by aspirating 0.1 mL of standard 1 % (10 mg/mL) phenylephrine solution into a 10-mL syringe and then adding normal saline to a total volume of 10 mL
2. Attach a 25- or 27-gauge needle to the syringe.
3. Puncture the corpus cavernosum at the 2 o'clock *or* 10 o'clock position (~+60° or −60° from the midline) on the suprapubic aspect of the penis approximately 1 cm from the penile base.
    - Puncture only one side of the penis.
4. Confirm the position of the needle by drawing back on the plunger to aspirate blood from the corpus cavernosa.
5. Inject 1 mL of phenylephrine solution every 3–5 min.
    - Repeat injections of phenylephrine (up to the maximum dose of 1000 μg) should be continued until the erection resolves; only thereafter should this procedure be abandoned in favor of the more invasive approach of surgical shunt.
6. Wrap the detumescent penis in gauze or an elastic bandage to prevent the return of priapism and to compress the puncture site(s).

85.6 Complications

- Of cavernosal aspiration/irrigation
    - Hematoma (at puncture site)
    - Infection (at insertion site or systemic)
    - Thrombosis
    - Arteriovenous fistula
    - Pseudoaneurysm formation
    - Traumatic puncture of dorsal penile or urethra
    - Exsanguination (secondary to dislodgement of catheter)
    - Cerebrovascular accident (secondary to air embolism)
- Of intracavernosal injection of vasoactive agents (α-adrenergic sympathomimetics)
    - Fibrosis of the corpora, pain, penile necrosis, urinary retention
    - Phenylephrine toxicity
    - Acute hypertension, headache, reflex bradycardia, tachycardia, palpitations, cardiac arrhythmia

85.7 Pearls and Pitfalls

- Pearls
    - In ischemic priapism, the penis and corpora cavernosa are rigid and tender to palpation.
    - Ischemic priapism commonly results from an underlying hypercoagulable state, tumor, infection, neurological impairment ("spinal shock"), or vasoactive drug use.
    - During intracorporeal injection, the patient should be monitored for known side effects of sympathomimetics, including hypertension, headache, reflex bradycardia, tachycardia, palpitations, and cardiac arrhythmia. In addition, in patients with elevated cardiovascular risk profiles, blood pressure and electrocardiographic monitoring should be performed.
    - Seek a urological consult as soon as possible for any patient presenting with priapism.
    - Resolution of priapism can be verified by measurement of cavernous blood gases or measurement of blood flow by color duplex ultrasonography.
    - Phenylephrine is the sympathomimetic agent of choice for intracavernosal injection because it is has a lower likelihood of causing adverse cardiovascular side effects than other agents. If this is unavailable, alternatives include epinephrine, norepinephrine, ephedrine, metaraminol, and etilephrine.
    - Intracavernous aspiration/irrigation/injection therapy is unlikely to resolve ischemic priapism lasting for 48 h or longer. In such cases, immediate surgical shunting is first-line treatment.
    - Once detumescence is achieved, any unmetabolized drugs in the corpus cavernosa enter the venous circulation, and thus, dosages of any vasoactive drugs injected must be monitored carefully.
- Pitfalls
    - The most common complication of ischemic priapism is complete erectile dysfunction.

85.8 Considerations

85.8.1 Blood Gas Analysis

This investigation provides a rapid distinction between ischemic and nonischemic priapism. Blood aspirated from the corpus cavernosum in ischemic priapism is dark in color with partial pressure of oxygen (PO_2) less than 30 mmHg, partial pressure of carbon dioxide (PCO_2) greater than 60 mmHg, and pH less than 7.25. In nonischemic priapism, respective values will be PO_2 greater than 90 mmHg, PCO_2 less than 40 mmHg, and pH of 7.4 (Table 85.1).

Table 85.1 Summary of cavernosal blood gas findings

	pH	PO_2 (mm Hg)	PCO_2 (mm Hg)
Ischemic priapism	<7.25	<30	>60
Arterial blood	7.40	>90	<40
Mixed venous blood	7.35	40	50

PCO_2 partial pressure of carbon dioxide, *PO2* partial pressure of oxygen

85.8.2 Sickle Cell Testing

The sickle-solubility test detects any sickle hemoglobin (therefore, it is positive in patients with either sickle cell train or sickle disease). Hemoglobin electrophoresis with 10 % or greater HbS suggests sickle cell disease. Anemia and increased reticulocyte count may also be present in sickle cell disease.

85.8.3 Hemoglobin Electrophoresis

Confirmatory test for sickle status after a positive sickle-solubility test.

85.8.4 Complete Blood Count

White blood cell (WBC) count may suggest infection or blood dyscrasia. Hemoglobin (Hb) and reticulocyte counts may suggest sickle cell disease.

85.8.5 Color Duplex Ultrasonography

Blood flow in cavernosal arteries is absent or minimal in ischemic priapism, whereas flow velocity is normal to high in nonischemic priapism.

85.8.6 Urine Toxicology and Psychoactive Drug Screen

The following drugs have been associated with priapism: antihypertensives, anticoagulants, antidepressants, alcohol, marijuana, cocaine, and other illegal substances. Intracavernous injection therapy using drugs such as alprostadil, papaverine, prostaglandin E1, phentolamine, and others may precipitate priapism.

Selected Reading

Burnett AL, Bivalacqua TJ. Priapism: new concepts in medical and surgical management. Urol Clin North Am. 2011;38:185–94.

Dubin J, Davis JE. Penile emergencies. Emerg Med Clin North Am. 2011;29:485–99.

Montague DK, Jarow J, Broderick GA, et al; Members of the Erectile Dysfunction Guideline Update Panel; American Urological Association. American Urological Association guideline on the management of priapism. J Urol. 2003;170:1318–24.

Shrewsberry A, Weiss A, Ritenour CW. Recent advances in the medical and surgical treatment of priapism. Curr Urol Rep. 2010;11:405–13.

Vilke GM, Harrigan RA, Ufberg JW, Chan TC. Emergency evaluation and treatment of priapism. J Emerg Med. 2004;26:325–9.

Reduction of Phimosis/Paraphimosis

86

Justin Chen and Muhammad Waseem

Phimosis occurs when the distal aspect of the prepuce cannot be retracted over the glans.

Paraphimosis is a true urological emergency; it occurs when retracted paraphimotic foreskin cannot be replaced to its normal position past the coronal sulcus, resulting in venous and lymphatic congestion leading to arterial occlusion, ischemia, and necrosis of the glans.

Both conditions commonly result from chronic infection from poor local hygiene in uncircumcised males; it can also be due to redundant skin.

86.1 Indications

- Phimosis: signs of acute urinary retention
- Paraphimosis: signs of present or impending *arterial* occlusion

86.2 Contraindications

- Absolute
  - Failure to rule out penile swelling and pain due alternative conditions (e.g., posthitis/balanoposthitis, angioedema, insect bite, constricting band)

86.3 Materials and Medications

- Latex-free gloves (sterile)
- Local anesthetic
  - 2 % lidocaine without epinephrine (preferred)
  - 2 % lidocaine gel or eutectic mixture of local anesthetics (EMLA) cream (2.5 % prilocaine and 2.5 % lidocaine)
- 25- to 27-gauge 1.5-in. needles (2)
- Small plastic syringe, 10 mL (1)
- Bag of ice (1)
- 2-inch elastic pressure dressing (1)
- Sterile gauze (1)

J. Chen, MD, MSc
Department of Emergency Medicine, North Shore University Hospital, Manhasset, NY, USA
e-mail: chen.justin@gmail.com

M. Waseem, MD (✉)
Department of Emergency Medicine, Lincoln Medical and Mental Health Center, New York, NY, USA
e-mail: waseemm2001@hotmail.com

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_86

86.4 Procedure: Manual Reduction for Paraphimosis

1. Grasp the swollen foreskin of the penis and apply gentle compression for a few minutes.
2. Grasp the swollen foreskin and elevate upward.
3. Push the glans into the foreskin.
4. Place the patient in the supine position and carefully inspect the penis for constricting bands or foreign bodies (e.g., piercings).
5. Usage of penile block to provide analgesia to the shaft and glans penis depends on urgency, patient age, and cooperativeness (Fig. 86.1).
   (a) Use a 25- to 27-gauge needle to inject lidocaine into the base of the penis, at the junction between the penis and the suprapubic skin, away from the midline to avoid the superficial dorsal vein.
   (b) Inject lidocaine just deep to Buck's fascia (3–5 mm beneath the skin) to form wheals, where a slight "pop" is felt as the needle penetrates the fascial layer.
   (c) Between 1 and 5 mL of local anesthetic should be used, depending on the age of the patient, which can be delivered as follows:
      - Half the volume should be injected at the 10 o'clock position and the remainder at the 2 o'clock position *or*
      - Full volume of local anesthetic is injected midline through Buck's fascia, directed toward each direction, ensuring negative aspiration of blood.
6. Alternatively, use gauze soaked in topical local anesthetic to cover the penis (2 % lidocaine gel or EMLA cream [2.5 % prilocaine and 2.5 % lidocaine]), which has slower onset.
7. For phimosis
   (a) If acute urinary retention occurs, dilate the foreskin under procedural sedation or penile block to allow Foley catheterization.
8. For paraphimosis
   (a) Once penile analgesia is achieved (typically in 5 min with penile block), relieve tissue edema before attempting reduction by using:
      - Bag of ice (3 min at a time), *or*
      - Granulated sugar (*contraindicated* in emergent situations owing to time required), *or*
      - Manual compression (squeezing the glans for 5 min), *or*
      - Pressure dressing (2-in. elastic bandage over the gland for 5 min)
   (b) Place both thumbs over the glans, with both index fingers and long fingers surrounding the trapped foreskin proximal from the paraphimotic tissue.
   (c) Use the thumbs to push the glans back into the foreskin while pulling the trapped foreskin distally, which may require a few minutes of constant pressure (Fig. 86.2).
   (d) Can also attempt using Babcock (once in each quadrant) or Adson (3 and 9 o'clock positions) forceps to grasp the paraphimotic tissue (Fig. 86.3).
   (e) If ineffective owing to extreme tissue edema, seek emergent urological consultation.
   (f) Follow-up with urologist is always recommended; circumcision may be performed once infection and/or edema have resolved to prevent recurrence (Fig. 86.4).

Fig. 86.1 Penile block to provide analgesia to the shaft and glans penis





Fig. 86.2 Use the thumbs to push the glans back into the foreskin while pulling the trapped foreskin distally



Fig. 86.3 (**a**) Babcock forceps. (**b**) Adson forceps



Fig. 86.4 Circumcision may be performed once infection and/or edema have resolved to prevent recurrence

86.5 Complications

- Bleeding/infection of injection site(s).
- Phimosis and scarring due to foreskin manipulation.
- Usage of Adson or Babcock forceps may result in minor bruising and abrasion to the foreskin and glans penis.

86.6 Pearls and Pitfalls

- Pearls
  - Phimosis is a normal occurrence in young males (<5–6 years) and should be treated only in the presence of acute urinary retention.
  - If arterial compromise is imminent in paraphimosis, the emergency physician should attempt reduction if urological consult is unavailable.
- Pitfalls
  - Reduction of phimotic tissue over the coronal sulcus may lead to emergent paraphimosis.

Selected Reading

Doherty GM, editor. Current diagnosis and treatment: surgery. 13th ed. New York: McGraw-Hill Medical; 2010.

King C, Henretig FM, editors. Textbook of pediatric emergency procedures. Philadelphia: Wolters Kluwer Health/Lippincott Williams & Wilkins; 2008.

Knoop KJ, editor. Atlas of emergency medicine. 3rd ed. New York: McGraw-Hill Professional; 2010.

Smith DR, Tanagho EA, McAninch JW, editors. Smith's general urology. New York: Lange Medical Books/McGraw-Hill; 2008.

Manual Testicular Detorsion

87

Brandon R. Allen and L. Connor Nickels

87.1 Indications

- Testicular torsion is a clinical diagnosis (Fig. 87.1).
  - Although no single clinical finding has 100 % sensitivity for the presence of testicular torsion, patients will have one or more of these signs and symptoms: nausea or vomiting, pain for less than 24 h, high position of the testis, and/or abnormal cremasteric reflex [1].
  - If the diagnosis is in question, radionuclide scan or ultrasonography of the testicles may be helpful to assess blood flow and to differentiate torsion from other conditions (Fig. 87.2).


Normal testicle
Spermatic cord
Epididymis
Urethra
Testicle
Testicular torsion
Twisted spermatic cord
Epididymis
Urethra
Testicle

Fig. 87.1 Schematic of normal testicle and testicular torsion

B.R. Allen, MD • L.C. Nickels, MD, RDMS (✉)
Department of Emergency Medicine, University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: brandonrallen@ufl.edu; cnickels@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_87



Fig. 87.2 Doppler ultrasound of bilateral testes shows swollen right testis with hypoechoic areas within and reduced arterial signal suggesting testicular torsion with necrosis (*left panel*). This is compared to the left testis which has normal flow (*right panel*) (Reproduced with permission from: Bhagra et al. [4])

87.2 Contraindications

- Do not attempt if the length of symptoms is greater than 24 h.
- Manual detorsion should not delay scrotal exploration and bilateral orchiopexy in the operating room [2].

87.3 Materials and Medications

- Standard precautions barrier protection for the provider
- Local anesthetic (optional to anesthetize the spermatic cord near the external ring)
- Intravenous sedation (optional)

87.4 Procedure

- The physician stands at the patient's feet and rotates the affected testicle away from the midline (as if opening a book) (Fig. 87.3).
  - For detorsion of the left testicle: the physician will place his or her right thumb and index finger on the affected testicle and rotate the testicle 180° from medial to lateral [2].
  - For detorsion of the right testicle: the physician will place his or her left thumb and index finger on the affected testicle and rotate the testicle 180° from medial to lateral.



Fig. 87.3 (**a**) As if opening a book, rotate the testicle away from the midline. (**b**) Affected testicle should be rotated 180° from medial to lateral

87.5 Pearls and Pitfalls

- Pearls
  - The most common misdiagnosis is epididymitis.
  - Because torsion of greater than 360° degrees is possible, more than one rotation may be needed to fully detorse the affected testis (Fig. 87.4).
  - Only surgical exploration can provide a definitive resolution if testicular torsion is present [2].
- Pitfalls
  - The most common causes of testicular loss after torsion are delay in seeking medical attention (58 %), incorrect initial diagnosis (29 %), and delay in treatment at the referral hospital (13 %) [3]



Fig. 87.4 Because torsion of greater than 360° degrees is possible, more than one rotation may be needed to fully detorse the affected testis

References

1. Beni-Israel T, Goldman M, Bar Chaim S, Kozer E. Clinical predictors for testicular torsion as seen in the pediatric ED. Am J Emerg Med. 2010;28:786–9.
2. Ringdahl E, Teague L. Testicular torsion. Am Fam Physician. 2006;74:1739–43.
3. Jones DJ, Macreadie D, Morgans BT. Testicular torsion in the armed services: twelve year review of 179 cases. Br J Surg. 1986;73:624–6.
4. Bhagra A, Suravaram S, Schears RM. Testicular torsion–a common surgical emergency. Int J Emerg Med. 2008;1(2):147.

Part XII

Skin and Soft Tissue Procedures

Local Anesthesia

88

Derek Ailes and Muhammad Waseem

88.1 Indications

- Laceration repair
- Abscess incision and drainage
- Wound exploration
- Vascular access procedures
- Foreign body removal
- Lumbar puncture

88.2 Contraindications

- History of allergy (usually to the ester class [e.g., procaine, tetracaine]), amide class (e.g., lidocaine [Xylocaine], bupivacaine, mepivacaine) may be safely substituted if true allergy to esters and vice versa. One percent diphenhydramine (4 mL normal saline: 1 mL 5 % intravenous [IV] diphenhydramine [Benadryl] mixture) can be used in patients with true allergy.
- Topical preparations on mucous membranes, burns, abraded/denuded skin, or eyes owing to potential toxicity from increased absorption and corneal injury.
- Common teaching is to avoid epinephrine-containing anesthetic solutions in nose, penis, and digits for concern of ischemia owing to end-artery constriction. Recent studies including prospective trials and comprehensive literature reviews, however, do not validate this concern [1, 2].

D. Ailes, MD • M. Waseem, MD (✉)
Department of Emergency Medicine,
Lincoln Medical and Mental Health Center, New York, NY, USA
e-mail: derekailes@yahoo.com; waseemm2001@hotmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_88

88.3 Materials and Medications (Fig. 88.1)

- 1 % Xylocaine with or without 1:200,000 epinephrine, 0.25 % bupivacaine solution. 8.4 % (1 mL/mL) sodium bicarbonate (optional)
- 18-, 25-, or 27-gauge needles, syringes up to 10 mL
- Sterile and nonsterile gloves, face shield
- Alcohol pads and povidone-iodine swabs



Fig. 88.1 Local anesthesia materials

88.4 Procedure

1. Position the patient in a comfortable position (supine, sitting, anticipating vasovagal response).
2. Draw the anesthetic with an 18-gauge needle into a syringe. Be aware of the maximum dose for the particular local anesthetic to avoid systemic toxicity.
3. Take steps to minimize the pain of infiltration (Table 88.1).
4. Prepare the area with povidone-iodine solution; cover surrounding areas with sterile drapes.
5. Inject subcutaneously by direct infiltration with a 25- to 27-gauge needle noting wheal and blanching. If a clean wound, may inject into wound edges. Usually no aspiration is needed because the infiltration is superficial to major blood vessels.
6. For contaminated wounds or abscess incision and drainage, perform field block by inserting the needle into clean intact skin adjacent to the wound and continuing in a circular manner around the wound, injecting into the previously anesthetized area (Fig. 88.2).
7. Wait several minutes for the local anesthetic to provide the maximum effect.
8. Test the area for sharp sensation with a needle tip or other sharp object.

Table 88.1 Common anesthetics and their characteristics

Medication	Time to onset (min)	Length of action	Maximum dose (mg/kg)	Maximum dose with epinephrine (mg/kg)
Marcaine (bupivacaine)	5–10	>3 h, up to 9 h with epinephrine	2.5	2.5–3.5
Xylocaine (lidocaine)	<2	30–75 min (longer with epinephrine)	3	5–7



Fig. 88.2 Local infiltration should be performed in a circular fashion with each injection performed over the prior anesthetized area

88.5 Complications

- Systemic toxicity
- Allergic reaction
- Infection
- Digital artery vasospasm from accidental injection of epinephrine (can be reversed with topical nitroglycerine or subcutaneous phentolamine)
- Vasovagal response

88.6 Pearls

- Minimize or reduce the pain of infiltration by use of the following:
  - Warm Xylocaine before infiltration (blanket warmer or water bath) [3].
  - Buffer Xylocaine with 1 mL 8.4 % sodium bicarbonate for every 10 mL of Xylocaine. Buffer bupivacaine with 0.05–0.10 mL sodium bicarbonate for every 10 mL of bupivacaine (greater chance of precipitation).
  - Use a small-gauge needle (e.g., 27 gauge) and inject slowly.
  - Use a small syringe (1–3 mL) to reduce the pressure of injection.
  - Withdraw the needle and, just before exiting the skin, redirect and inject.
  - Inject in a circular manner around the wound with each subsequent injection entering a previously anesthetized area, such that the patient feels only one needle stick (Fig. 88.2).
  - Inject into the subcutaneous plane as opposed to the intradermal plane.
  - Consider using a topical anesthetic before infiltration, especially in pediatrics (lidocaine, epinephrine, tetracaine [LET]).
- Beware of toxicity by not exceeding the maximum dose, especially in large or multiple lacerations. Even at standard doses, toxicity can occur with inadvertent vascular injection, injection into highly vascular areas, or onto mucous membranes [4, 5].
  - Convert % mg/mL into mg/kg by moving the decimal one place to the right (e.g., 1 % Xylocaine becomes 10 mg/mL and 0.25 % bupivacaine becomes 2.5 mg/mL).
  - Xylocaine can be safely injected up to 3.5 mg/kg every 30 min, up to 300 mg/dose. If the mixture contains epinephrine, 5–7 mg/kg is safe.
  - Bupivacaine can be injected at 2.5 mg/kg and 3.5 mg/kg with epinephrine and can be injected every 3 h with daily maximum of 400 mg [5].
- When treating a wound, it is important to first anesthetize so debridement, cleansing, and irrigation can adequately be performed.
- Choose appropriate anesthetics. Xylocaine lasts approximately 75 min, and bupivacaine lasts several hours. Adding epinephrine to either increases vascular constriction, thereby decreasing systemic absorption and significantly increasing the duration of effect.
- Topical anesthetics have a role in pediatric populations and in conjunction with or as an alternate to local infiltrative anesthesia. TAC is a mixture of 0.5 % tetracaine, 0.05 % epinephrine, and 11.8 % cocaine. LET is 4 % lidocaine, 0.1 % epinephrine, and 0.5 % tetracaine. LET has been found to be safer and more cost-effective [6].

References

1. Muck AE, Bebarta VS, Borys DJ, Morgan DL. Six years of epinephrine digital injections: absence of significant local or systemic effects. Ann Emerg Med. 2010;56:270–4.
2. Waterbrook AL, Germann AC, Southall JC. Is epinephrine harmful when used with anesthetics for digital blocks? Ann Emerg Med. 2007;50:472–5.
3. Hogan ME, vanderVaart S, Perampalades K, Machado M, Einarson TR, Teddio A. Systematic review and meta-analysis of the effect of warming local anesthetics on injection pain. Ann Emerg Med. 2011;58:86–98.
4. Reichman EF, Simon RR, editors. Emergency medicine procedures. New York: McGraw-Hill Medical; 2004. p. 937.
5. Marx J, Hockberger R, Walls R, editors. Rosen's emergency medicine: concepts and clinical practice. 7th ed. Philadelphia: Mosby; 2010. p. 2425–7.
6. Kravitz ND. The use of compound topical anesthetics. J Am Dent Assoc. 2007;138:1333–9.

Regional Anesthesia (Nerve Blocks)

89

Derek Ailes and Muhammad Waseem

89.1 Indications

- Repair of wounds where preserving anatomical landmarks or having precise anatomical alignment is important (e.g., vermillion border of lip)
- Pain control in dislocation or fracture reductions
- Incision and drainage of abscesses
- Burn and wound care
- Extensive or multiple lacerations (reduces total amount of local anesthetic needed)
- Foreign body removal

89.2 Contraindications

- Allergic to local anesthetic (see Chap. 88)
- History of coagulopathy or bleeding disorder
- Injection through infected tissue

D. Ailes, MD • M. Waseem, MD (✉)
Department of Emergency Medicine, Lincoln Medical and Mental
Health Center, New York, NY, USA
e-mail: derekailes@yahoo.com; waseemm2001@hotmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_89

89.3 Materials and Medications (Fig. 89.1)

- Povidone-iodine, alcohol swabs
- Sterile gloves and drapes
- Local anesthetic solution (e.g., lidocaine, Marcaine with or without epinephrine)
- 18-gauge, 20- to 30-gauge needles 2 in. in length
- 22- to 24-gauge spinal needles
- Syringes up to 60 mL


LEFT
GAUCHE
THREE PVP-I SWABSTICKS
PLUS
THREE POVIDONE IODINE PREP SWABSTICKS
KENDALL
WEBCOL
Alcohol Prep

Fig. 89.1 Materials

89.4 Procedure: General Block

1. Obtain consent after explaining the risks of procedure including temporary paresthesias and expected duration of block. Perform neurological examination before procedure, documenting any preexisting deficits.
2. Position the patient comfortably, preferably supine, anticipating vasovagal response.
3. Identify landmarks for the block. Clean area, prepare with povidone-iodine, and surround with sterile drapes.
4. A small skin wheal of local anesthetic may be placed at the site of needle entry before block.
5. Insert the needle into the site while aspirating to ensure it is not in a vessel.
6. If paresthesia is elicited, withdraw the needle slightly allowing paresthesia to improve and inject.
7. Wait 5–15 min for the block to reach full effect.
8. Test for sharp sensation in the anesthetized area and document.

89.5 Complications

- Infection
- Hemorrhage
- Hematoma
- Allergic reaction
- Systemic toxicity (exceeded maximum dose or inadvertent injection into vasculature)
- Paresthesias, pain
- Intraneural injection causing ischemia
- Intra-arterial injection of epinephrine causing vasospasm and tissue ischemia

89.6 Pearls and Pitfalls

- Pearls
  - It is important to aspirate before injecting anesthesia when performing regional anesthesia because, unlike local techniques, the needle is deeper and in proximity to larger vessels.
  - Shooting pain and/or paresthesias occurs when the needle contacts the nerve. When this happens, withdraw the needle 1 mm and wait for the paresthesia to resolve before injecting.
  - Injury can occur to a limb or digit if the patient manipulates it before the anesthesia wears off. The patient should be cautioned not to use the affected area until motor and sensation return. If an extensive block was done, monitor the patient in the emergency department until return of baseline neurological function.
- Pitfalls
  - It is traditionally taught to avoid epinephrine-containing solutions in blocks in end-artery blocks (e.g., digital blocks). However, evidence for any vascular insufficiency and necrosis as a result is lacking in standard commercially available lidocaine with epinephrine preparations. They should, however, be avoided in patients with peripheral artery disease [1, 2].

89.7 Selected Specific Blocks

- Contraindications and materials are the same as general block.

89.7.1 Facial Blocks: Trigeminal Nerve (Fig. 89.2) [2, 3]


Supraorbital nerve
Supratrochlear nerve
Infraorbital nerve
Mental nerve
Opthalmic
Maxillary
Mandibular

Fig. 89.2 Vertical plane through the midposition of the pupil shows the position of the supraorbital foramen, infraorbital foremen, and mental foramen

89.7.1.1 Supraorbital (Fig. 89.3) and Supratrochlear Nerve Block

- Indications
  - To anesthetize the forehead from the orbital ridge to the vertex of the scalp. The supraorbital nerve emerges from the supraorbital foramen/notch and is a branch of the ophthalmic division of the trigeminal nerve. The supratrochlear nerve also is a branch of the ophthalmic division of the trigeminal nerve and exits through the superior medial aspect of the orbit.
- Procedure
  1. Inject local anesthetic solution over the midline of the forehead at eyebrow level.
  2. Inject a 25- or 27-gauge needle through skin wheal aimed laterally while injecting 3–5 mL local anesthetic subcutaneously. Stop infiltrating when the needle reaches the midline of the orbit.



Fig. 89.3 Supraorbital nerve block

89.7.1.2 Infraorbital Nerve Block

- Indications
  - To anesthetize the medial cheek, upper lip, philtrum, skin between the lips and the nose, and nasal ala. The infraorbital nerve emerges from the infraorbital foramen and is a branch of the maxillary division of the trigeminal nerve. Anesthesia to the infraorbital nerve will also provide anesthesia to its terminus, the superior alveolar nerves.
- Procedure: Extraoral Approach (Fig. 89.4)
  1. Palpate the inferior orbital foramen in its midline position. The infraorbital nerve is often tender on palpation as it exits the foramen.
  2. Inject a 25- or 27-gauge needle just above the infraorbital foramen injecting 1–2 mL of local anesthetic.
  3. Take care not to inject into the foramen because there is an increased risk of intraneural injection.
  4. Hold a finger on the inferior orbital rim to avoid ballooning of the lower eyelid with injection.
  5. Intraoral approach is possible and preferred because it is less painful.



Fig. 89.4 Extraoral approach to the infraorbital nerve block

- Procedure: Intraoral Approach (Fig. 89.5) [3]
  1. Apply topical benzocaine or lidocaine gel to the point of insertion, which is the height of the mucobuccal fold over the first premolar, which is the site of insertion. Wipe off after 1–3 min.
  2. Palpate with the finger of the noninjecting hand over the inferior border of the inferior orbital rim. Retract the lip with the noninjecting hand.
  3. Using a long 25- to 27-gauge needle, with the bevel toward the bone, advance the needle at the insertion site toward the infraorbital foramen. Once the target is reached, aspirate and inject 1 mL of local anesthetic.
  4. Exert pressure on the foramen for 1 min after injection to force the anesthetic through the infraorbital foramen.
  5. If the needle is difficult to advance and the patient experiences pain on insertion, redirect the needle laterally and advance.
  6. If analgesia is attained for the lip but not the eyelid, the analgesia was placed inferior to foramen, and if analgesia is attained for the eyelid but not the lip, placement was superior to the foramen.



Fig. 89.5 Intraoral approach to the infraorbital nerve block

89.7.1.3 Mental Nerve Block

- Indications
  - To anesthetize the lower lip and chin and is especially useful in laceration repair at those sites. The mental nerve emerges from the mental foramen and is a branch of the mandibular division of the trigeminal nerve. Mental foramen lies in the vertical plane with the midpoint of the pupil and sits in the middle of the body of the mandible.
- Procedure: Extraoral Approach (Fig. 89.6)
  1. Inject local anesthetic solution over the identified location of the mental foramen, creating a skin wheal.
  2. Advance a 25- or 27-gauge needle through the skin wheel until the mandible is contacted, injecting 1–2 mL of local anesthetic.
  3. Intraoral approach is possible and preferred because it is less painful.
- Procedure: Intraoral Approach (Fig. 89.7) [3]
  1. Apply topical benzocaine or lidocaine gel to the point of insertion, which is the mucobuccal fold between the apices of the first and the second premolars. Wipe off after 1–3 min.
  2. Insert a 25- to 27-gauge needle, with the bevel toward the mandible, aimed toward the mental foramen.
  3. After advancing one-third the depth of the mandible and contacting the mandible, inject 1–2 mL of local anesthetic.
  4. By pressing firmly on the mental foramen for 2–3 min after the mental foramen has been blocked, an incisive nerve block is also created. This is useful if anesthesia to the lower anterior teeth is also desired.



Fig. 89.6 Extraoral approach to the mental nerve block



Fig. 89.7 Intraoral approach to the mental nerve block

89.7.2 External Ear Block (Fig. 89.8) [4]

- Indications
  - To anesthetize the entire external ear, excluding the external auditory canal and the concha
  - Especially useful in large lacerations of the ear and surrounding skin, hematoma evacuations, or incision and drainage of abscess.
- Procedure: Auricular Ring Block (Fig. 89.9) [4]
  1. Using a 25- to 27-gauge needle, insert the needle just inferior to the earlobe directing it toward the tragus.
  2. Aspirate and advance the needle superiorly subcutaneously injecting 3–4 mL of local anesthetic (Fig. 89.9, #1).
  3. Withdraw the needle without fully removing it and redirect it posterosuperiorly along the inferior posterior auricular sulcus, aspirating and injecting as before (Fig. 89.9, #2).
  4. Remove the needle and insert it just superior to the point of helix insertion into the scalp.
  5. Advance the needle and aspirate and inject in the direction of the tragus. Inject into the subcutaneous tissue while avoiding the ear cartilage (Fig. 89.9, #3).
  6. Withdraw and redirect the needle posteriorly and inferiorly toward the skin behind the ear, injecting as before (Fig. 89.9,#4).
  7. Beware of inadvertent cannulation of the superficial temporal artery, which crosses the zygomatic arch and crosses medial to the ear. If the artery is violated, it requires 20–30 min application of firm pressure.



Fig. 89.8 Auricular block anesthetizes four nerves that innervate the auricle. *1* Great auricular nerve, *2* lesser occipital nerve, *3* auricular branch of vagus nerve, *4* auriculotemporal nerve



Fig. 89.9 Auricular ring block technique

89.7.3 Wrist Block (Fig. 89.10) [3, 5, 6]

- Indications
  - To anesthetize the hand in preparation for laceration repair, fracture or dislocation reduction, or pain relief



Fig. 89.10 Nerve distribution in the hand

89.7.3.1 Wrist Block: Median Nerve (Fig. 89.11)

- Procedure
  1. Position the patient supine with the palmar surface of the hand face up.
  2. Have the patient make a fist and slightly flex the wrist so that the palmaris longus and flexor carpi radialis tendons become prominent.
  3. Create a skin wheal of local anesthetic between the two tendons between the proximal skin crease and the distal skin crease at the wrist. Alternatively, anesthetic can be injected in line with the ulnar styloid process at the proximal skin crease.
  4. The palmaris longus tendon is absent normally in 10–20 % of the population. In this case, inject over the midpoint of the proximal skin crease at the level of the styloid process.



Fig. 89.11 Median nerve block at the wrist: *1* proximal and distal wrist creases radial artery, *2* flexor carpi radialis tendon, *3* palmaris longus tendon, *4* ulnar artery, *5* styloid process

89.7.3.2 Wrist Block: Radial Nerve (Figs. 89.12 and 89.13) [3, 7]

- Procedure
  1. To block the radial nerve, block multiple peripheral branches on the dorsal and the radial aspects of the lateral wrist.
  2. A field block in and around the anatomical snuffbox may be performed, requiring roughly 5–6 mL of local anesthetic. This anesthetizes the terminal branches of the radius arising from the forearm.
  3. Position the patient's palm face up and inject a skin wheal to the area 1 mm lateral to the radial pulse and in line with the proximal wrist crease. Inject 2 mL of local anesthesia with a 25- to 27-gauge needle. This anesthetizes the terminal trunk of the radial nerve.



Fig. 89.12 Radial nerve block at the wrist: *1* radial artery, *2* anatomical snuffbox



Fig. 89.13 Radial nerve block at the wrist: *1* radial artery, *2* flexor carpi radialis tendon, *3* palmaris longus tendon, *4* ulnar artery, *5* proximal and distal wrist creases

89.7.3.3 Wrist Block: Ulnar Nerve (Fig. 89.14)

- Procedure
  1. Position the patient with the hand face up.
  2. Palpate the styloid process of the ulna and pisiform and find the ulnar artery pulse.
  3. Create a skin wheal of local anesthetic between lateral to the ulnar artery and medial to the flexor carpi ulnaris tendon just proximal to the styloid process. This is at the level of the proximal wrist crease.



Fig. 89.14 Ulnar nerve block at the wrist: *1* proximal and distal wrist creases, *2* flexor carpi radialis tendon, *3* palmaris longus tendon, *4* ulnar artery, *5* styloid process, *6* flexor carpi ulnaris

89.7.4 Digital Nerve Blocks: Ring, Web Space, and Tendon Sheath (Fig. 89.15) [3, 8, 9]

- Indications
  - To anesthetize the digits in preparation for laceration repair, nail bed repair, joint reduction, or pain relief


Dorsal surface
Extensor tendon mechanism
Dorsal digital nerve
Bone
Vein
Artery
Nerve
Palmar digital
Superficialis tendon
Palmar surface
Profundus tendon

Fig. 89.15 Cross section of finger

89.7.4.1 **Ring Block** (Fig. 89.16) [3]

- Procedure
  1. Insert a 25-gauge needle on the dorsal surface of the proximal phalanx of the digit to be anesthetized. Inject 1 mL along the dorsal surface and withdraw the needle.
  2. Reinsert the needle again perpendicular to the last injection and running on the lateral surface of the phalanx. Inject 1–1.5 mL of local anesthetic to just past the phalanx base.
  3. Repeat the injection in the same fashion on the medial aspect of the phalanx.
  4. Do not inject more than 5 mL into a digit.
  5. Toe blocks are similar to finger ring blocks, except that the great toe requires plantar surface injection as well, owing to its unique nerve supply.



Fig. 89.16 Dorsal surface injection of digital nerve ring block. Digital nerve block is performed by injecting onto the (**a**) dorsal, (**b**) lateral, and (**c**) medial surfaces of the proximal phalanx

89.7.4.2 **Web Space Digital Block** (Fig. 89.17) [9]

- Procedure
  1. Have the patient abduct the fingers.
  2. Palpate the metacarpophalangeal joint and then insert a 25- to 27-gauge needle into the lateral web space subcutaneously, directing it dorsally. Aspirate then inject 1 mL of local anesthetic.
  3. Withdraw the needle but before the exiting skin, redirect toward the palmar aspect until the tip is next to the metacarpophalangeal joint, and inject 1 mL of local anesthetic.
  4. Repeat the procedure on the medial web space of the digit. Each digit blocked requires injection on both the lateral and the medial web spaces.



Fig. 89.17 Web space approach to the digital block, requiring injection on the medial and lateral web spaces for a blocked digit

89.7.4.3 Intrathecal Digital Block: Flexor Tendon Sheath (Fig. 89.18) [8]

- Procedure
  1. Inject anesthetic directly into the flexor tendon sheath. Palpate on the palmar surface over and proximal to the metacarpophalangeal joint. Gentle flexion of digit may better reveal the sheath. Have the patient abduct the fingers.
  2. Insert a 25-gauge needle at a 45° angle to the skin and along the long axis of the digit directly into the flexor tendon sheath at the level of the distal skin crease.
  3. Inject 2 mL of local anesthetic. The anesthetic should flow freely if it is in the sheath. If it does not, it is likely in the tendon and should be withdrawn slightly.
  4. Contraindications to intrathecal block are local infection and preexisting flexor tendon injury.
  5. Risk of tenosynovitis; sterilize the skin before introducing the needle.
  6. If laceration has involved the tendon, anesthetic may leak from the wound.



Fig. 89.18 Intrathecal/tendon sheath approach to the digital block

Acknowledgment The authors would like to thank Katy Howard for serving as the subject in many of the photographs in this chapter.

References

1. Muck AE, Bebarta VS, Borys DJ, Morgan DL. Six years of epinephrine digital injections: absence of significant local or systemic effects. Ann Emerg Med. 2010;56:270–4.
2. Waterbrook AL, Germann AC, Southall JC. Is epinephrine harmful when used with anesthetics for digital blocks? Ann Emerg Med. 2007;50:472–5.
3. Reichman EF, Simon RR, editors. Emergency medicine procedures. New York: McGraw-Hill Medical; 2004. p. 961–3.
4. Benko K. Fixing faces painlessly: facial anesthesia in emergency medicine. Available at: Emergency Medicine Practice (ebmedicine.net). 2009;11.
5. Rosh AJ. Ear anesthesia. Medscape reference. Available at: http://emedicine.medscape.com/article/82698-overview#a15.
6. Butterworth JF. Atlas of procedures in anesthesia and critical care. Philadelphia: WB Saunders; 1992. p. 160–4.
7. Brown DL. Atlas of regional anesthesia. Philadelphia: WB Saunders; 1992. p. 52.
8. Morrison WG. Transthecal digital block. Arch Emerg Med. 1993;10:35–8.
9. Mueller J, Davenport M. Digital nerve block (web space and tendon sheath). New York: McGraw-Hill's Access Emergency Medicine. Available at: http://www.accessemergencymedicine.com/videosPDF/DigitalNerveBlock.pdf.

90 Wound Management and Hemostasis

Rich Teitell and Muhammad Waseem

90.1 Indications for Primary Wound Repair

- Wounds that have been sustained less than 8 h before presentation may be closed primarily.
- If there is suspicion of broken glass or the presence of a foreign body, the patient should receive an x-ray before primary wound repair. Of note, x-ray has poor sensitivity for radiolucent foreign bodies such as wood and plastic.
- Wounds that are free of foreign bodies or show no gross evidence of infection or dead tissue may be closed primarily.

90.2 Contraindications for Primary Wound Repair

- History must address the factors that predispose a wound to greater risks of infection and not implement primary wound closure in such wounds that have had a duration greater than 8–12 h or contamination with saliva, stool, or foreign matter and a wound that has been sustained by blunt or crush mechanism.
- When wounds are highly contaminated with debris or if devitalized tissue is present, the wound should be left open for 3–4 days and then reevaluated.
- After a proper physical examination has been performed that assesses distal pulse and sensory and motor function of the surrounding region and distal extremity, if any of these are compromised, appropriate orthopedic and/or vascular consultation should be sought before wound closure, especially in the setting of a suspicion for open fracture.
- Consider delayed closure in wounds over joints.
- Wounds that have a significant loss of skin should be left to heal by secondary intention.

90.3 Procedure for Wound Closure and Hemostasis

1. Wound should be thoroughly prepared with Betadine (10 % povidone with 1 % iodine), which has a rapid onset with greatest antimicrobial effect.
2. Skin surrounding the wound should be covered with sterile drapes (Fig. 90.1) so as to reduce additional contamination within the open wound.
3. The most important determinant for preventing wound infection is adequate high-pressure irrigation.
4. Normal saline is the best solution for irrigation. Use pressures above 7 psi and an 18-gauge needle with a syringe of 30 mL or more; this gauge needle will achieve pressure greater than 7 psi.
5. It has been suggested that tap water irrigation may be just as effective. Because this approach will reduce costs, it can be considered.
6. Sharp debridement should be performed when foreign matter is found in an open wound that does not easily rinse out with saline. In this circumstance, consider wound closure by secondary intention or delayed primary closure.
7. At this point, wounds that do not meet criteria for primary closure must be left open, covered with a sterile dressing, and reevaluated in 3–4 days for consideration of delayed primary closure versus healing by secondary intention.
8. Wounds that do meet criteria as previously discussed for primary closure should be closed with either sutures or staples.
9. Staples are the preferred method of closure of scalp wounds and can be used under low wound tension.

R. Teitell, MD
Department of Emergency Medicine, Waterbury Hospital,
Waterbury, CT, USA
e-mail: rjt0013@gmail.com

M. Waseem, MD (✉)
Department of Emergency Medicine, Lincoln Medical and Mental
Health Center, New York, NY, USA
e-mail: waseemm2001@hotmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_90

10. The angle of the stapler is critical and must be positioned perpendicular to the intended area of delivery. A two-person approach can be utilized for optimal placement of the staple, using forceps to approximate the edges of the tissue.
11. Synthetic or monofilament sutures have a lower rate of infection than braided sutures (for closure techniques with sutures, see Chap. 92).
12. Dermabond should be utilized only for the most superficial linear lacerations and confers the benefit of efficiency of time and less discomfort to the patient. However, it should be mentioned that Dermabond does not offer any statistically significant difference in cosmesis when compared with suturing or other adhesives (see Chap. 93).
13. When a wound presents with deep underlying tissue involvement and direct bleeding is evident, direct pressure may be used to achieve hemostasis within a wound. Surgicel may also be applied with pressure to achieve control of small capillary and venous oozing (Fig. 90.2).
14. When a persistent bleed is visible within a wound that does not respond to direct pressure, a figure-of-eight suture (Fig. 90.3) may be used.
15. If a bleeding vessel is visible within a wound, an alternate method of hemostasis may be achieved by utilizing a hemostat to clamp the vessel and then tying an absorbable suture (Fig. 90.4).



Fig. 90.1 (**a**) High-pressure irrigation using an 18-gauge needle (**b**)



Fig. 90.2 Direct pressure with or without Surgicel may be used to achieve hemostasis within a wound and also to achieve control of small capillary and venous oozing



Fig. 90.3 (**a**) The location of the bleeding vessel in the subcutaneous tissue is identified and an absorbable suture is threaded through the region. (**b**) In a diagonal direction, a second suture is placed, which when tied will form the shape of an eight. (**c**) Once tied, the suture forms a figure eight in the tissue and hemostasis is achieved



Fig. 90.4 (**a**) The culprit vessel is identified and clamped with a hemostat. (**b**) An absorbable suture is wrapped around the vessel inferior to the hemostat. (**c**) Once the first tie is placed being driven down with index finger, the hemostat may be removed and the knot can be completed for a total of three or four passes

90.4 Complications

- Hematoma formation
- Infection
- Scar formation

90.5 Pearls and Pitfalls

- Pearls
  - Antibiotic coverage should be employed judiciously depending on the wound and location.
  - Wounds to the face that are not heavily contaminated generally do not require antibiotics because the face and scalp have a significant vascular supply.
  - Patients with diabetes have higher incidences of wound infection, and the physician should consider prophylactic antibiotics in such individuals.
  - Wounds that are clean-contaminated and sutured in the emergency department should have a nonadherent dressing applied for 48 h until epithelialization has occurred. After that, the dressing may be removed, and soap and water gentle washing should commence to keep area clean. Only small amounts of bacitracin should be applied to wound in the interim period before sutures are removed.
- Pitfalls
  - Wounds located on the extremities have greater incidences of infection than those on the trunk or head/face.

Selected Reading

Blankenship RB, Baker T. Imaging modalities in wounds and superficial skin infections. Emerg Med Clin North Am. 2007;25:223–34.

Dimick AR. Delayed wound closure: indications and techniques. Ann Emerg Med. 1988;17:1303–4.

Edlich RF, Rodeheaver GT, Morgan RF, Berman DE, Thacker JG. Principles of emergency wound management. Ann Emerg Med. 1988;17(12):1284–302.

Farion K, Osmond MH, Hartling L, et al. Tissue adhesives for traumatic lacerations in children and adults. Cochrane Database Syst Rev. 2002;(3):CD003326.

Hall S. A review of the effect of tap water versus normal saline on infection rates in acute traumatic wounds. J Wound Care. 2007;16:38–41.

Marx J, Hockberger R, Walls R, editors. Rosen’s emergency medicine: concepts and clinical practice. 6th ed. Philadelphia: Mosby-Elsevier; 2006. p. 702–3.

Ritchie AJ, Rocke LG. Staples versus sutures in the closure of scalp wounds: a prospective, double-blind, randomized trial. Injury. 1989;20:217–8.

Singer AJ, Hollander JE, Quinn JV. Evaluation and management of traumatic lacerations. N Engl J Med. 1997;337:1142–8.

Burn Care

91

Thomas Parry and Jeffrey Pepin

Burns result from exposure to heat, caustic chemicals, electricity, or radiation. Damage to the natural barrier provided by skin results in rapid fluid losses and risk of infection. Permanent scarring is a common long-term complication. They may also be complicated by sensory deficits due to loss of nerve connections and limb loss due to circulatory compromise.

91.1 Burn Description (Fig. 91.1)

- First degree or superficial: burn that remains confined to the epidermis (e.g., sunburn)
- Second degree or partial thickness: burn that extends into the dermis (e.g., blistering scald burns)
- Third degree or full thickness: burn involving the entire depth of the dermis and epidermal appendages



Fig. 91.1 Tea scald over the chest and shoulder of a child showing heterogeneity of burn depth. *D* deep (second or third degree), *I* intermediate (second degree), *S* superficial (first degree) (Reproduced from: Enoch S, Roshan A, Shah M. Emergency and early management of burns and scalds. *BMJ*. 2009;338:b1037, with permission from BMJ Publishing Group Ltd.)

T. Parry, MD (✉)
Department of Emergency Medicine, Lincoln Hospital and Mental Health Center, New York, NY, USA
e-mail: Thomas.parry@nychhc.org

J. Pepin, MD
Department of Emergency Medicine, University of Minnesota Medical Center Fairview, Minneapolis, MN, USA
e-mail: medicone76@hotmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_91

91.2 Indications

- Superficial, deep second degree, and third degree.
- First-degree burns generally need only supportive care.

91.3 Materials and Medications

- Appropriate analgesia
- Antibiotic ointment
- Silver sulfadiazine (avoid on face)
- Sulfamylon for ears
- Alternative agents include bacitracin or polymyxin B ointments
- Cleansing solution such as chlorhexidine prep and water
- Basin
- Petroleum gauze
- Several 4×4 gauze pads
- Rolled gauze
- Tape
- Gloves

Airway, breathing, and circulation and cervical spine should be immediately assessed before any burn wound management. It is important to remember that any patient suspected of an inhalation injury or carbon monoxide poisoning should receive 100 % humidified oxygen until carboxyhemoglobin returns to normal. Inhalation injuries may not present themselves until after fluid resuscitation has already been started, so early intubation is recommended in these cases.

91.4 Sizing

Total body surface area (TBSA) of body parts is estimated by multiples of 9 (Rule of Nines)

- Adults
  - Head and neck: 9
  - Arms: 9 each
  - Legs: 18 each
  - Trunk: 18 front and 18 back
  - Perineum and palms: 1
- Infants/children
  - Head and neck: 18
  - Arms: 9 each
  - Legs: 14 each
  - Trunk: 18 front and 18 back

A second way to estimate TBSA in smaller burns is by using the palm surface area: using the patient's palm as a guide, each palmar surface equals 1 %.

A third way to estimate TBSA is via the use of the Lund and Browder chart (Fig. 91.2).



ADULT FLUID RESUSCITATION

2-4 mls X Body Weight (Kgs) X % TBSA
Give ½ in first 8 hrs, the rest over next 16 hrs

PAEDIATRIC FLUID RESUSCITATION

Resuscitation fluids as per adults PLUS
Dextrose saline as metabolic fluids at a rate:
4 ml/Kg/h for 0-10 Kg, add 2 ml/Kg/h for 11-20
Kg add 1 ml/Kg/h for each Kg over 20 Kg

AREA	Age 10	15	ADULT
A ½ OF HEAD	5.5%	4.25%	3.5%
B ½ OF ONE THIGH	4.25%	4.5%	4.75%
C ½ OF ONE LEG	3%	3.25%	3.5%

Fig. 91.2 Lund Browder chart for estimating total body surface area of burns, with suggested fluid resuscitation guidelines (Reprinted from Malic CC, Karoo RO, Austin O, Phipps A. Resuscitation burn card–a useful tool for burn injury assessment. *Burns*. 2007;33(2)195–9, with permission from Elsevier)

91.5 Fluid Resuscitation

Because fluid resuscitation is absolutely essential in the early aspects of burn care, the Parkland formula has been used to estimate fluid requirements in burn patients. The patient's weight in kilograms is multiplied by the percent body surface area (BSA) involved; this number is multiplied by 4 mL of lactated Ringer's solution. Half of this amount is given during the first 8 h and the remaining amount is given over the next 16 h of resuscitation. The goal is to keep urine output approximately 0.5–1.0 mL/kg/h.

In pediatric cases, the Galveston formula may be used instead: 5000 mL/m^2 BSA burned plus 2000 mL/m^2. TBSA of 5 % dextrose in lactated Ringer's solution intravenously over the first 24 h, half in the first 8 h, and the other half over the next 16 h.

91.6 Procedure

1. Provide appropriate analgesia.
2. Clean the wound with antiseptic solution and water (if it is a dry chemical burn, make sure to brush off as much chemical before using copious amounts of water to clean the wound).
3. Debride any loose skin or foreign debris using a dry 4×4 or rolled gauze.
4. Apply antibiotic ointment or cream to the burn.
5. Apply petroleum gauze in a single layer just over the affected skin.
6. Use loose 4×4 gauzes and "fluff" them to make a thick layer of padding to place over the petroleum gauze.
7. Either wrap the entire area with a rolled gauze or tape a small layer of 4×4 gauze over the "fluffed" layer of 4×4 gauze.

91.7 Complications

- Wound infection
- Nonhealing wound requiring skin graft (deep second-degree and third-degree burns)
- Compartment syndrome (circumferential burns may require escharotomy)
- Rhabdomyolysis

91.8 Pearls and Pitfalls

- Pearls
  - Determination of the depth of burns on initial presentation is difficult (especially when covered with petroleum). A good rule of thumb is if it blanches and/or hurts, it is a partial thickness burn.
  - First-degree burns are not included in burn size estimations for fluid resuscitation calculation.
  - Burn size determines fluid requirements and transfer decision.
  - Burn of greater than 20 % TBSA should receive intravenous fluids.
  - Patients who have inhalation injury, greater than 10 % TBSA, high-voltage electrical injury, or chemical burns should be referred to burn unit.
  - Fluid resuscitation should be adjusted according to physiological response such as urine output (30–50 mL/h in adults and 1 mL/kg/h in children).
  - Assure tetanus is up to date.
- Pitfalls
  - Keep the patient warm in the first few hours. There is no need to apply ice.
  - All jewelry and rings should be removed.
  - Prophylactic antibiotics are not recommended.
  - Silver sulfadiazine should be avoided in facial burns because of the risk of staining of the skin.

Blister care is a very controversial topic. Current research suggests that it may be beneficial to keep the blister intact unless it appears to be tense or over a joint. Most blisters will rupture in 2–4 days. Ruptured blisters should be debrided with all the extra skin removed. Most burn units will scrub everything off once they receive a patient.

Wounds should be kept clean to prevent an environment that will increase the chances of infection. Wrap in saline-soaked sterile gauze prior to transfer.

Dressing changes should be done daily with all previously applied antibiotic ointment removed before a reapplication of new ointment. It is important to provide analgesic 30 min before a dressing change.

91.9 Admission Criteria

- Partial-thickness burns of noncritical areas not including the eyes, ears, face, hands, feet, or perineum that total a BSA of 10–20 % in adults
- Partial-thickness burns of noncritical areas involving 5–10 % of BSA in children younger than 10 years
- Suspicious of non-accidental trauma
- Patients unable to care for wounds in outpatient settings
- Prompt referral to a burn specialist is required in the following cases:
  - Partial-thickness and full-thickness burns greater than 10 % of the TBSA in patients younger than 10 years or older than 50 years of age.
  - Partial-thickness and full-thickness burns greater than 20 % of the TBSA in other age groups.

- Partial-thickness and full-thickness burns involving the face, eyes, ears, hands, feet, genitalia, or perineum or the skin overlying major joints.
- Full-thickness burns greater than 5 % TBSA in any age group.
- Electrical burns, including lightning injury: significant volumes of tissue beneath the surface may be injured and result in acute renal failure and other complications.
- Significant chemical burns.
- Inhalation injury.
- Burn injury in patients with preexisting illness that could complicate management, prolong recovery, or affect mortality.
- Any burn patient in whom concomitant trauma poses an increased risk of morbidity or mortality may be treated initially in a trauma center until stable before transfer to a burn center.
- Children with burns seen in hospitals without qualified personnel or equipment for their care should be transferred to a burn center with these capabilities.
- Burn injury in patients who will require special social and emotional or long-term rehabilitative support, including cases involving suspected child abuse and neglect.

Selected Reading

Bezuhly M, Fish JS. Acute burn care. Plast Reconstr Surg. 2012;130(2):349e–58.

Rex S. Burn injuries. Curr Opin Crit Care. 2012;18(6):671–6.

Wasiak J, Cleland H, Campbell F, Spinks A. Dressings for superficial and partial thickness burns. Cochrane Database Syst Rev. 2013;(3):CD002106.

Wound Closure

92

Oliver Michael Berrett, Jeffrey Joseph Harroch,
Karlene Hosford, and Muhammad Waseem

92.1 Indications

- Open wound of skin or mucosal tissues
- Purpose
  - Preserve function
  - Control bleeding
  - Promote healing
  - Cosmesis

92.2 Contraindications

- Wounds caused by animal or human bites
- Contaminated, infected, or puncture wounds
- Complex wounds (may require operating room)

92.3 Methods

- Suture placement
- Tissue adhesives
- Adhesive tapes
- Staples

92.4 Preparation

- Obtain a complete history of injury
  - Mechanism
  - Time since injury
  - Tetanus status
  - Comorbidities
- Examine the extent of the wound, remove any contaminants, debride devitalized tissue, inspect for foreign bodies. Obtain a radiograph if foreign body is suspected.
- Copious irrigation with normal saline.
- Clean around the wound with a povidone-iodine solution.
- Drape the area in sterile manner.
- Inject the anesthetic agent into the wound edges using a 25- or 27-gauge needle. The most common agent is lidocaine 2 % with or without epinephrine 1 % (maximum dose is 3 mg/kg without epinephrine and 5 mg/kg with epinephrine).
- Close the wound using the appropriate technique (see later).
- Dress the wound.
- Update tetanus and diphtheria vaccination if needed.

O.M. Berrett, MD • K. Hosford, MD • M. Waseem, MD (✉)
Department of Emergency Medicine, Lincoln Medical and Mental Health Center, New York, NY, USA
e-mail: omberrett@gmail.com; krlhos@aol.com; waseemm2001@hotmail.com

J.J. Harroch, MD
Department of Emergency Medicine, University of Miami Miller School of Medicine, University of Miami Hospital,
Miami, FL, USA
e-mail: jharroch@med.miami.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_92

92.5 Suture Repair

92.5.1 Materials and Medications

- Commercial kits commonly contain all the following except the suture material (Fig. 92.1)
  - Povidone-iodine solution
  - Normal saline for irrigation
  - 5- to 12-mL syringe with a 25-gauge needle
  - Anesthetic agent
  - Needle holder
  - Pickups
  - Suture scissors
  - Suturing material
  - Sterile drape or sheet, gloves, gauze


LIDOCAINE HCl
10 mg/mL
APLICARE
THREE
POVIDONE-IODINE
SWABSTICKS
STERILE
Drug Facts

Fig. 92.1 Suture kit

92.5.2 General Guidelines

- Local anesthetic lidocaine 1 % or lidocaine 1 % with epinephrine.
- Minimize direct use of instruments on the tissues.
- Wound edges should be everted to maximize healing and cosmetic effect. This is achieved by inserting the needle at 90° to the skin.
- Sutures should be evenly spaced, placed 1–3 mm apart and 2 mm from the wound edge.
- Optimal tension is achieved by tying the sutures so the edges lightly approximate.

92.5.3 Suture Material

- Nonabsorbable
  - Silk: for specialty use, reactive and weak
  - Nylon (Ethilon), polypropylene (Prolene): good strength, good overall material for cutaneous wounds
  - Polypropylene: good strength, difficult to use
  - Require removal at a specified time
- Absorbable
  - Undergo rapid degradation in tissues, losing their tensile strength within 60 days
  - Indication: buried suture to reduce wound edge tension
  - Vicryl: subcutaneous placement, mucous membranes
  - Chromic: use for intraoral lacerations
  - Removal not required

92.5.4 Suture Size

- 0.0–2.0: thick material for large wounds, trunk
- 0.3–0.4: used on medium-sized wounds, extremities, scalp
- 0.5–0.6: fine sutures, used on facial wounds

92.5.5 Suture Techniques

- Simple interrupted sutures (Fig. 92.2)
  - Most common method
  - Position needle 2 mm from the wound edge at a 90° angle. Enter the needle into the skin and arc through the wound edge and into the opposing edge at the same level, exiting the skin on the opposing side 2 mm from wound edge, tie.
- Deep dermal suture (Fig. 92.3)
  - Also known as buried sutures, used to minimize tension in a wound.
  - Use absorbable suture material.
  - The needle is placed at the base of the wound wall and arched upward, exiting the ipsilateral wall more superficially. The needle is then directed across to the opposing wound wall at the same level and directed downward, exiting deep, tie. Note: The knot will be deep in the wound.
- Simple running suture (Fig. 92.4)
  - This method provides rapid closure of long and relatively linear lacerations.
  - Place the initial suture in the same manner as a simple suture, tie, cut the free strand, and leave the needle attached. Reintroduce the needle into the skin on the opposite side so the suture crosses the wound superficially at a 65° angle. The needle is then inserted perpendicular to the skin, emerging on the opposite side about 3 mm from the wound edge. Repeat without tying until closure is complete, maintaining appropriate tension. When the last stitch is placed, leave a loose loop of suture on one side so that both ends can be tied together.
- Vertical mattress suture (Fig. 92.5)
  - Provides the benefits of both simple and deep techniques. For use on deeper, gaping wounds and wounds over high-tension areas such as joints.
  - Position the needle 1 cm from skin edge, at a 90° angle, drive a deep arc perpendicular through the wound, exiting the skin on the opposing side the same distance from the wound edge. Next, reinsert the needle on the ipsilateral side 2 mm from the edge, emerging on the opposing side and approximate, tie.
- Horizontal mattress suture (Fig. 92.6)
  - For large wounds with tension.
  - Place the initial suture in the same manner as a simple suture, only do not tie. Reposition the needle on the ipsilateral side, horizontally 5 mm to the side of the exit at the same distance from the wound edge and drive through to the other side, tie. Note: The tie lies parallel to the wound.
- Half-buried horizontal mattress suture (Fig. 92.7)
  - Used on wounds with skin flap.
  - On one side, drive the needle percutaneously, and then pass horizontally through the dermal tissue of the tip of flap, finally passing into the dermis of the opposing edge and exiting the skin, tie.

92.5.6 Recommendations

- Face
  - 5.0–6.0 nylon.
  - Remove after 3–5 days.
- Scalp
  - 2.0–3.0 nylon or staple.
  - Remove at 8–10 days.



Fig. 92.2 Simple suture

- Hand
  - 4.0–5.0 nylon, consider vertical or horizontal mattress.
  - 5.0–6.0 Monocryl for nail bed.
  - Remove at 10–14 days, use for a longer time if directly over the joint.
- Extremity
  - Nonmobile skin: 3.0–4.0 nylon, remove at 8–10 days
  - Over joint: 3.0–4.0 nylon, remove at 10–14 days
- Trunk
  - Anterior trunk: 3.0–4.0 nylon, remove at 8–10 days.
  - Posterior trunk: 2.0–3.0 nylon, remove at 10–14 days.
  - Consider staples.
- Oral mucosa
  - Thin mucosa: 4.0 Vicryl will absorb; duration, 5–7 days
  - Tongue: 3.0 Vicryl will absorb; duration, 5–7 days



Fig. 92.3 Deep suture



Fig. 92.4 Running suture



Fig. 92.5 Vertical mattress suture



Fig. 92.6 Horizontal mattress suture



Fig. 92.7 Half-buried horizontal mattress suture

92.6 Alternative Methods of Wound Closure

92.6.1 Cyanoacrylate Tissue Adhesives

See Chap. 93.

92.6.2 Adhesive Tape

- Advantages
  - Rapid and painless application
  - Inexpensive
  - Good cosmetic result
- Disadvantages
  - Minimal strength
- Contraindications
  - Allergy to product
- Precautions
  - For use with wounds under little tension
- Procedure
  - Thoroughly clean the wound as described previously.
  - Approximate the wound edges.
  - Apply adhesive tape directly over the wound with 2–3 mm of space between strips.
  - An adjunct adhesive, such as benzoin, may be used to improve durability.

92.6.3 Staple Closure (Fig. 92.8)

- Advantages
  - Rapid
  - Inexpensive
- Disadvantages
  - Minimal strength
- Contraindications
  - Wounds on face, hands, or feet
- Procedure
  - Thoroughly clean the wound as described previously.
  - Anesthetize the wound edges.
  - Approximate the wound edges (may require an additional set of hands).
  - Apply staples.



Fig. 92.8 Staple

92.7 Pearls and Pitfalls

- Pearls
  - Sutures should not remain in place longer than the recommended period. If the wound is not completely healed, sutures should be removed and an adhesive tape may be used for edge approximation.
  - Remember to verify tetanus status.
  - Antibiotics should be used judiciously.
- Pitfalls
  - Wound infection.
  - Incomplete healing may lead to wound separation.
  - Tissue reaction to suture or adhesive materials.
  - Allergy to anesthetic agent.

Selected Reading

http://apps.med.buffalo.edu/procedures/repairoflacerations.asp?p=17. Accessed 19 May 2014.

Singer AJ, Hollander JE. Methods for wound closure. In: Ma OJ, Cline DH, Tintinalli JE, Kelen GD, Stapczynski JS, editors. Emergency medicine manual. 6th ed. New York: McGraw Hill; 2003: Chap. 13, Fig. 13–14.

Singer AJ, Hollander JE, editors. Laceration and acute wounds: an evidence-based guide. Philadelphia: FA Davis; 2003. p. 122.

University of Connecticut Health Center, suturing 101. fitsweb.uchc.edu/suturing101. Accessed 19 May 2014.

Zuber TJ. The mattress sutures: vertical, horizontal and corner stitch. Am Fam Physician. 2002;66:2231–6.

Wound Closure with Tissue Adhesive

93

Pratik S. Patel and Latha Ganti

93.1 Indications

- Small superficial skin incisions or laceration repairs which require 5.0 or smaller-diameter sutures.

93.2 Contraindications

- Absolute
  - Large irregular/stellate lacerations
  - Infected/contaminated wounds
  - Animal/human bites
  - Puncture wounds
  - Crush wounds
  - Skin ulcers
  - Mucous membranes and mucocutaneous junctions
  - Axillae and perineum (owing to high moisture)
- Relative
  - Wounds on extremities (unless kept dry)
  - Joints (unless kept immobilized with a splint)

93.3 Materials and Medications

- Dermabond (2-octyl cyanoacrylate)
- Betadine (povidone-iodine) solution
- 0.9 % normal saline solution
- 20-mL sterile syringe
- Sterile gloves
- Dry 4×4 gauze

93.4 Optional Materials

- Topical anesthesia
- 1:1000 epinephrine solution
- Forceps
- Bacitracin ointment or sterile petroleum jelly ointment
- Gown and protective eyeglasses
- Splint

P.S. Patel, MD
Department of Emergency Medicine, University of Florida Health,
Gainesville, FL, USA
e-mail: drpratik@gmail.com

L. Ganti, MD, MS, MBA (✉)
Professor of Emergency Medicine, University of Central Florida,
Orlando, FL, USA

Director, SE Specialty Care Centers of Innovation, Orlando
Veterans Affairs Medical Center, Orlando, FL, USA
e-mail: lathagantimd@gmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_93

93.5 Procedure

1. Have the patient rest comfortably on a chair or bed.
2. Use universal precaution measures: sterile gloves (gown and eye-screen, if necessary for wound irrigation).
3. Wash the wound with 0.9 % normal saline irrigation.
4. Use a topical anesthetic such as LET (lidocaine, epinephrine, tetracaine) or EMLA (eutectic mixture of local anesthetics) cream (lidocaine and prilocaine), or a 1:1000 epinephrine solution soaked into gauze can be used to achieve hemostasis in a bleeding wound.
5. Approximate the edges of the wound with fingers. Toothed forceps or other skin approximation devices may be used as an adjunct. Apply bacitracin ointment or Vaseline to the tips of the forceps and wipe off the excess to prevent sticking of Dermabond glue to the forceps.
6. Crush Dermabond vial between the thumb and the finger while in the inverted position until the adhesive is seen at the applicator tip (Fig. 93.1).
7. Squeeze gently until a drop of adhesive forms at the applicator tip.
8. Gently brush the adhesive at the applicator tip over the approximated wound edges (Fig. 93.2). (Do not force or press the applicator tip over the wound.)
9. Cover the entire wound with single coat of adhesive.
10. Hold the wound edges for 30 s to 1 min until it dries.
11. Apply two or three more coats of adhesive over and around the wound in a circular or oval movement to provide extra strength.
12. Wipe off extra adhesive in the surrounding skin with gauze if needed.
13. Apply a splint (optional) to provide wound stability over the joints.
14. Recommend the patient to keep the wound dry for 4–5 days. Patients may shower but should be instructed to pat dry instead of rubbing a towel over the skin.
15. No topical antibiotic ointment is required before or after application of Dermabond.



Fig. 93.1 (**a**) Before the tip has been crushed. (**b**) The purple Dermabond is in the tip



Fig. 93.2 Closing the wound: use tip of Dermabond pen to "paint" over the laceration

93.6 Complications

- Wound dehiscence
- Wound infection

93.7 Pearls and Pitfalls

- Pearls
  - Advantages of tissue adhesives for wound repair compared with sutures include faster repair time, better acceptance by patients (especially children), water-resistant covering, and no need for a second visit to remove sutures (sloughs off in 5–10 days).
- Pitfalls
  - Dermabond is a super adhesive. Take care not to have the glove, finger, drape, gauze, or instrument inadvertently stuck to the wound or the patient by having a bacitracin or petroleum jelly coating around the wound, on gloved fingers, and on forceps as needed.

Selected Reading

Bruns TB, Worthington JM. Using tissue adhesive for wound repair: a practical guide to Dermabond. Am Fam Physician. 2000;61:1383–8.

Farion K, Osmond MH, Hartling L, et al. Tissue adhesives for traumatic lacerations in children and adults. Cochrane Database Syst Rev. 2002;(3):CD003326.

Fishhook Removal

94

Judith K. Lucas

94.1 Indications

- Removal of a fishhook from nonvital structures (Fig. 94.1)



Fig. 94.1 Anatomy of a fishhook

94.2 Contraindications

- Removal of hooks located near/in eyes or eyelids, embedded near or within neurovascular structures, or embedded within vital structures such as peritoneum, testicle, or urethra.
  - Fishhooks in these areas require specialist consultation.

94.3 Materials and Medications

- Antiseptic cleansing solutions
  - Betadine (povidone-iodine)
  - Chloraprep
- Local anesthetic
  - 1 % lidocaine, with or without epinephrine
- Needle drivers or pliers
- 18- or 20-gauge needle
- 3-0 silk suture or umbilical tape
- Wire cutters
- Protective eyewear

J.K. Lucas, MD
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: judithklucas@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_94

94.4 Procedures

- Retrograde technique (Fig. 94.2): simplest, least traumatic, but least successful; good for small to medium hooks, superficially embedded hooks, and hooks with no barbs or a single barb.
    1. Detach extra hooks, line, or foreign materials (e.g., worms, fish, debris).
    2. Cleanse the puncture site and surrounding tissue with antiseptic solution.
    3. Infiltrate the entry site and surrounding area with local anesthetic.
    4. Apply downward pressure on the shank or shaft of the hook, near the eye, thus disengaging the barb from the tissue.
    5. Back the hook out of the skin along the path of entry.
- String and yank technique (Fig. 94.3): Good for small to medium hooks. Often requires no anesthesia. Good for areas of deep soft tissue penetration. Cannot be used on parts of the body that are not fixed, such as earlobes.
    1. Detach extra hooks, line, or foreign materials (e.g., worms, fish, debris).
    2. Cleanse the penetration site and surrounding area with antiseptic wash.
    3. Consider infiltrating the entry site with local anesthetic.
    4. Wrap 3-0 silk suture, fishing line, or umbilical tape several times around the bend of the hook (at the point of greatest curvature).
    5. The loose ends of the string need be held tightly. Sometimes the loose ends can be more firmly held if wrapped around a pencil or tongue depressor.
    6. The skin around the entry site should be well stabilized, while simultaneously depressing the shank, close to the eye of the hook.
    7. While stabilizing the skin and applying downward pressure on the shaft, quickly and firmly yank the string, in a parallel line to the shaft. Be certain downward pressure is applied along the shank.
    8. The hook will “fly” out quickly. Be certain to wear eye protection.
- Needle cover technique (Fig. 94.4): good method to remove large hooks with a single barb, especially if superficially embedded
    1. Detach extra hooks, line, or foreign materials (e.g., worms, fish, debris).
    2. Cleanse the penetration site and surrounding area with antiseptic wash.
    3. Infiltrate the entry site and surrounding area with local anesthetic.
    4. Advance an 18-gauge needle along the entrance wound of the hook. Pass the needle parallel to the shank. The bevel should be pointed downward, toward the barb and point.
    5. The needle is advanced until it disengages the barb, entrapping it within the needle lumen.
    6. The hook and needle are advanced just enough to disengage the barb.
    7. The hook and needle are withdrawn along the track of the wound.
- Advance and cut technique (Fig. 94.5). Almost always successful but does cause additional tissue trauma.
    1. Detach extra hooks, line, or foreign materials (e.g., worms, fish, debris).
    2. Cleanse the penetration site and surrounding area with antiseptic wash.
    3. Infiltrate the entry site and surrounding area with local anesthetic.
    4. If the hook has a single barb:
        - Grip the hook on the shank, near the bend, with either a needle driver or pliers.
        - Push the hook through along its natural trajectory, until the point and barb pass completely through the skin.
        - Clip the point proximal to the barb. Be certain to wear eye protection because the point can fly off in an unpredictable direction.
        - Withdraw the hook out back along its entry path.
    5. If the hook has multiple barbs (Fig. 94.6):
        - Grip the hook on the shank, near the hook’s bend with either a needle driver or pliers.
        - Push the hook through along its natural trajectory, until the point and barb pass completely through the skin.
        - Clip the eye of the hook with wire cutters.
        - Grasp the point and withdraw the hook through the skin forward along its natural course.



Fig. 94.2 Retrograde technique. *1* Push down along whole shank and slightly forward to release the barb. *2* Pull back and out along hook's entry path, applying steady downward pressure


Eye and shank
pressed firmly
downward
3-0 Silk tie wrapped
several times around
bend of hook

Fig. 94.3 String and yank technique


Pass 18-G needle through
hook's entry.
Follow hook's bend,
keeping needle's
bevel downward
along line of bend.
Capture barb in bevel,
then gently pull needle/hook
unit out of skin along path.

Fig. 94.4 Needle technique


Single barb
Clip here

Fig. 94.5 Advance and cut technique


Multi-barb
Clip here

Fig. 94.6 Advance and cut a hook with multiple barbs present

94.5 Postremoval Wound Care

- Immune competent, without peripheral vascular disease:
  1. Explore the wound for possible foreign bodies.
  2. Irrigate or scrub the wound copiously with soapy solution.
  3. Apply antibiotic ointment and sterile dressing.
  4. Tdap (or Dtap) should be given to anyone in whom the last tetanus booster has been longer than 5 years.
  5. Wound check in 24–48 h with care provider.
- Immunocompromised or a patient with peripheral vascular disease:
  1. As previously.
  2. Give strong consideration to treating prophylactically with antibiotics, choosing a fluoroquinolone, third-generation cephalosporin, or aminoglycoside.

94.6 Complications

- Infection
- Retained foreign body
- Injury to neurovascular structures, if method of removal is not carefully selected
- Injury to provider if adequate (eye) protection not used

94.7 Pearls and Pitfalls

- Pearls
  – Begin with either the retrograde method or the string-yank method, because these result in less tissue damage and are the easiest to perform, although they have the lowest rate of success.
  – Eye protection is imperative, especially if utilizing the string-yank method or clipping any portion of the hook (eye or point) because the retraction of the hook, or its parts, is generally at a high velocity and travels an unpredictable path.
  – When trying the advance and cut technique, stop immediately if, when advancing the hook, impasse, or resistance is met because this may indicate bone or neurovascular structures are blocking the natural path of the hook.
  – Fishhooks that embed into or near the eye or lids should be covered with a metal patch or cup and the patient should be sent (immediately) for ophthalmologic consultation.
  – Close follow-up is imperative to watch for signs of infection.
- Pitfalls
  – When utilizing the advance and cut technique, do not cut anything until certain there is another portion of the hook on which to grasp.

Selected Reading

Bothner J. Fish-hook removal techniques. Available at: www.UpToDate.com. Literature review version 19.2, May 2011. Topic last updated: Sep 2010. Accessed 23 June 2014.

Gammons M, Jackson E. Fishhook removal. Am Fam Physician. 2001;63:2231–7.

Wakeman K. Fishhook removal. Available at: www.fishgame.com. Texas Fish and Game, LLC. July 2003. Accessed 23 June 2014.

Tick Removal

95

David N. Smith and Judith K. Lucas

95.1 Indications

- Tick attachment to the skin

95.2 Contraindications

- None

95.3 Materials and Medications

- Gloves
- Skin disinfectant (commercially available product, such as Chloraprep, isopropyl alcohol, or Betadine [povidone-iodine])
- Fine-toothed forceps

95.4 Procedure

1. Comfortably position the patient with the tick site exposed.
2. Grasp the tick as close to the skin surface as possible (e.g., grasp the mouth parts).
3. Gently pull upward with steady, nontwisting, even traction (Figs. 95.1 and 95.2).
4. After removal, clean the bite area and apply antibiotic ointment.



Fig. 95.1 Place the forceps as close to the mouth of the tick as possible, hold firmly, and pull straight up with steady gentle traction



Fig. 95.2 Steady upward traction

D.N. Smith, MD
Department of Pediatrics, University of Alabama at Birmingham,
Children's of Alabama, Birmingham, AL, USA
e-mail: dsmith@peds.uab.edu

J.K. Lucas, MD (✉)
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: judithklucas@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_95

95.5 Complications

- Multiple diseases including:
  - Lyme disease
  - Human granulocytic and monocytic ehrlichiosis
  - Babesiosis
  - Relapsing fever
  - Rocky Mountain spotted fever
  - Colorado tick fever
  - Tularemia
  - Q fever
  - Tick paralysis
- Secondary infection (methicillin-resistant *Staphylococcus aureus* [MRSA] and group A streptococcus).
- Scratching can lead to lichenification.
- Rare cases of alopecia when tick located in the scalp.

95.6 Pearls and Pitfalls

- Pearls
  - Do not twist or jerk the tick out (may cause breakage of mouth parts; they may remain in the skin).
  - Do not squeeze the body of the tick.
  - Do not use a hot match, gasoline, or other noxious stimulus for removal (causes irritation of tick and release of internal contents).
  - Lyme disease transmission increases significantly after 24–48 h of attachment, so early removal is the key.
  - Patients should be monitored for up to 30 days for signs of tick-borne diseases, including erythema migrans (bull's-eye rash) indicating Lyme disease (Fig. 95.3).
- Prophylactic antibiotic treatment, a single dose of doxycycline, is used only in patients with an identified *Ixodes scapularis* tick that has been attached for longer than 36 h and if treatment can start within 72 h of tick removal.
  - Serological testing for Lyme disease is not indicated for a reported tick bite.
- Pitfalls
  - Use of lidocaine subcutaneously can irritate the tick and cause it to regurgitate its stomach contents, increasing the risk of disease transfer.



Fig. 95.3 Erythema migrans (the bull's-eye rash), the rash typically associated with Lyme disease. Often the rash is so pale as to go unnoticed

Selected Reading

Centers for Disease Control and Prevention. Tick removal. In: Ticks. 2014. http://www.cdc.gov/ticks/removing_a_tick.html. Accessed 23 Feb 2014.

Needham GR. Evaluation of five popular methods for tick removal. Pediatrics. 1985;75:997–1002.

Sexton DJ. Evaluation of a tick bite for possible Lyme disease. Up To Date; 2010. http://uptodate.com.

Sloan S. Background. In Tick removal. 2014. http://emedicine.medscape.com/article/1413603-overview. Accessed 23 Feb 2014.

Subungal Hematoma Drainage

96

Pratik S. Patel and Latha Ganti

96.1 Causes

- Crushing injury to the finger or toe
- Ill-fitted shoes/inadequate space for toes

96.2 Indications

- Pain that is not tolerable with nail edges intact

96.3 Contraindications

- Relative
  - Disrupted nail edges
  - Tolerable pain that can be managed conservatively
  - Skin infections around toe/finger
  - Bleeding disorder

96.4 Materials and Medications

- 18-gauge needle
- Betadine (povidone-iodine) solution
- Gloves
- Topical antibiotic

96.4.1 Optional materials

- Electrocautery tool
- Paper clip or sewing needle and sterilizing flame
- Finger splint
- Lidocaine (1 or 2 % with epinephrine)

P.S. Patel, MD
Department of Emergency Medicine, University of Florida Health,
Gainesville, FL, USA
e-mail: drpratik@gmail.com

L. Ganti, MD, MS, MBA (✉)
Professor of Emergency Medicine, University of Central Florida,
Orlando, FL, USA

Director, SE Specialty Care Centers of Innovation, Orlando
Veterans Affairs Medical Center, Orlando, FL, USA
e-mail: lathagantimd@gmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_96

96.5 Procedure

1. Have the patient rest the affected finger comfortably on a flat surface.
2. Use universal precaution measures: gloves, gown, and eye screen.
3. Sterile skin preparation with Betadine.
4. Optional (for complicated subungal hematoma): use 1 or 2 % lidocaine with epinephrine for providing local digital block.
5. Using the thumb and index finger gently twist the 18-gauge needle with light pressure over the base of the nailbed or in the center of the hematoma until no resistance is felt. Do not apply any further pressure in order to avoid nailbed damage. Nail penetration is confirmed by return of dark blood from the hole. This procedure is known as trephination (Figs. 96.1 and 96.2).
6. Apply light pressure around the tip of the finger and hematoma to facilitate drainage. In case of continuous bleeding elevate the digit and apply firm and continuous pressure over the nail with a gauze piece.
7. Apply topical antibiotic ointment (e.g., bacitracin) over the puncture hole.
8. Apply a gauze dressing or a bandage over the wound site/fingernail.
9. Apply a finger splint (optional) to provide additional comfort.
10. Recommend the patient to keep the finger or toe dry (avoid soaking) and elevated for 1–2 days.



Fig. 96.1 Subungal hematoma of right index finger



Fig. 96.2 Positioning of needle to perform subungal hematoma drainage

96.6 Complications (Rare)

- Infection
- Injury to nail bed or underlying bone if too much pressure is applied with puncture
- Onycholysis when there is incomplete drainage in rare cases

96.7 Pearls and Pitfalls

- Pearls
  - Multiple holes may be necessary for appropriate drainage of the hematoma.
  - When using electrocautery for hole puncture, execute high caution with acrylic nails because they are flammable.
  - When using a paper clip or regular needle, make sure to sterilize the tip over a flame.
  - Take a radiograph of the finger whenever necessary to rule out phalangeal fracture.
  - Check for avulsion of the extensor tendon.
  - Inform the patient that the existing nail may fall off and will regenerate in few months if the nailbed is intact.
  - Systemic or oral antibiotics are not recommended.
- Pitfalls
  - Development of a dark color change over the nailbed without any history of trauma should raise suspicion of a tumor and should be evaluated accordingly.
  - Do not remove the nail to evaluate injury to nailbed.

Selected Reading

Brown RE. Acute nail bed injuries. Hand Clin. 2002;18:561–75.

Dean B, Becker G, Little C. The management of the acute traumatic subungual haematoma: a systematic review. Hand Surg. 2012;17:151–4.

Incision and Drainage of Abscess

97

Nicholas D. Caputo, Karlene Hosford,
and Muhammad Waseem

97.1 Indications

- Abscess greater than 5 mm in diameter and in accessible areas (e.g., axilla, extremities, trunk)

97.2 Contraindications

- Absolute
  - Absence of fluctuation
  - Large, deep, and complicated (multiloculated) abscesses
  - Location
    - Perianal
    - Mastoid
- Relative
  - Location
    - Face (e.g., nose, nasolabial fold)
    - Palms
  - Coagulopathy
  - Recurrent pilonidal cysts (may mandate operative excision)
  - Area of cosmetic importance where aspiration may be preferred

97.3 Materials and Medications

- Incision and drainage tray (Fig. 97.1)
  - Drape
  - Betadine (povidone-iodine) swabs
  - 1 % lidocaine
  - 18- and 27-gauge needles
  - 12-mL syringes, gauze pads
  - #11 scalpel, mosquito clamps (hemostat)
  - Iodoform packing of appropriate size
- Ultrasound machine (Fig. 97.2)

N.D. Caputo, MD, MSc
Emergency Department Critical Care, Lincoln Medical and Mental Health Center, New York, NY, USA
e-mail: Ncaputo.md@gmail.com

K. Hosford, MD • M. Waseem, MD (✉)
Department of Emergency Medicine, Lincoln Medical and Mental Health Center, New York, NY, USA
e-mail: krlhos@aol.com; waseemm2001@hotmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_97



Fig. 97.1 Supplies necessary for incision and drainage

Fig. 97.2 Bedside SonoSite ultrasound

97.4 Procedure

1. Ultrasound (optional) may be helpful when abscess is suspected in the absence of fluctuation. Using the vascular probe (7 mHz), confirm the clinical suspicion of abscess and check the depth and width of the abscess (Fig. 97.3).
2. Sterile skin preparation with Betadine swab and sterile drape.
3. Anesthetize the appropriate area subcutaneously with 5 mL of 1 % lidocaine by inserting the 27-gauge needle at an acute angle into the intradermal space (Fig. 97.4a, b).
4. Using a #11 blade, make an approximately 1- to 2-cm skin incision over the desired area parallel to the Langer lines. The incision must approach into the abscess cavity (Fig. 97.4c).
    - Some physicians still advocate the technique of making a cruciate incision. This may leave a larger scar and should be discussed with patient before doing so because of cosmetic consequences.
5. Allow for spontaneous drainage. After resolution of drainage, you may express more pus with gentle downward pressure.
6. Using the hemostat, enter the incision to break any suspected loculations. This should be done with the clamps closed and curved part down. The clamps should then be opened and removed slowly (Fig. 97.4d).
7. After clearing the remaining loculations, the wound should be packed.
    - Evidence suggests that packing the abscesses does not prevent recurrence; however, this is still practiced. If packing the wound, follow the next step.
8. Take the iodoform packing with the hemostat, and place the packing into the incision site until no further packing will fit.
9. Cut the packing leaving a tail out of the incision site (Fig. 97.4e).
10. Apply dressing with 4×4 gauze and adhesive tape (2 in.).



Fig. 97.3 (**a**) Example of an abscess as viewed on bedside ultrasound. (**b**) A multiloculated abscess



Fig. 97.4 (**a**) Abscess with overlying erythema. (**b**) Lidocaine injection in the superficial layer. (**c**) Linear incision with #11 blade. (**d**) Expression of purulent material and breaking of loculations with clamps. (**e**) Optional placement of packing

97.5 Complications

- Recurrence of abscess
- Progression of cellulitis
- Neurovascular injury to adjacent structures

97.6 Pearls

Antibiotic coverage is a controversial topic. Methicillin-resistant *Staphylococcus aureus* (MRSA) is a concern not only in the immunocompromised and diabetic patients. *S. aureus* has been detected in up to 51 % of patients with abscesses. Of these isolates, approximately 75 % were MRSA. Bactrim (trimethoprim/sulfamethoxazole) should be utilized for all prophylactic measures.

Selected Reading

Barnes SM, Milsom PL. Abscess: an open and shut case. Arch Emerg Med. 1988;5:200–5.

Burney RE. Incision and drainage procedures: soft tissue abscesses in the emergency service. Emerg Med Clin North Am. 1986;4:527–42.

Duong M, Markwell S, Peter J, Barenkamp S. Randomized, controlled trial of antibiotics in the management of community-acquired skin abscesses in the pediatric patient. Ann Emerg Med. 2010;55:401–7.

Fitch MT, Manthey DE, McGinnis HD, Nicks BA, Pariyadath M. Abscess incision and drainage. N Engl J Med. 2007;357:e20.

Frazee BW, Lynn J, Charlebois ED, Lambert L, Lowery D, Perdreau-Remington F. High prevalence of methicillin-resistant *Staphylococcus aureus* in emergency department skin and soft tissue infections. Ann Emerg Med. 2005;45:311–20.

Hankin A, Everett WW. Are antibiotics necessary after incision and drainage of a cutaneous abscess? Ann Emerg Med. 2007;50:49–51.

O'Malley GF, Dominici P, Giraldo P, et al. Routine packing of simple cutaneous abscesses is painful and probably unnecessary. Acad Emerg Med. 2009;16:470–3.

Part XIII

Orthopedic Procedures

Splinting

98

Christopher H. Stahmer and Muhammad Waseem

98.1 Indications

- Need for immobilization for fracture, dislocation, or soft tissue injury
- Suspicion for occult injury of an extremity
- Immobilization for pain management

98.2 Contraindications

- Absolute
  - Open fracture (requires operative intervention)
- Relative
  - Infection
  - Compartment syndrome

98.3 Materials and Medications (Fig. 98.1)

- Plaster of Paris
- Fast drying: 5–8 min to set
- Extra fast drying: 2–4 min to set
  - Variety of widths depending upon splint of choice:
  - Splints may take up to 2 days to dry and achieve maximum strength.
- Prefabricated splinting materials
  - Plaster OCL® (Orthopedic Casting Laboratories)
    - 10–20 sheets of plaster with padding and cover
    - Faster setup time but less customizable
  - Fiberglass splints
    - Cure rapidly
    - Less messy
    - Less moldable
    - Stronger and lighter
- Stockinette.
  - Protects the skin.
  - Variety of sizes available.
- Soft wrap (Webril™).
  - Provides padding.
  - Five to six layers depending on anticipated swelling.
    - Too much padding reduces the stability of the splint.
  - Use extra padding over bony prominences.
  - Pad between digits for splinting of digits.
  - Avoid wrinkles, which generate pressure points.
  - Do not wrap circumferentially.
    - Increased risk of ischemia.
- Ace wraps.
  - Variety of sizes depending.
    - Larger widths over legs.
    - Narrow widths around fingers and joints.
      - Avoid bunching by using narrow widths at joints.
- Water
  - Warm water and splint sets more quickly but increases the risk of burns.
    - Splint drying is an exothermic or heat-releasing reaction.
  - Hot water leaves less time to mold the splint.

C.H. Stahmer, MD • M. Waseem, MD (✉)
Department of Emergency Medicine, Lincoln Medical and Mental Health Center, New York, NY, USA
e-mail: stahmer@gmail.com; waseemm2001@hotmail.com

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_98



Fig. 98.1 Posterior splint materials: plaster of Paris, Ace wraps, soft roll. Note there are two layers of soft wrap: the inner layer to face the patient (eight layers) and the outer layer to pad the exterior (two layers)

98.4 Procedure

1. Completely expose and examine the afflicted body part for tissue, vascular, or neurological injury.
   - Address respective injuries before proceeding.
2. Lay out all splinting materials before initiating procedure.
   - Layer plaster of Paris.
     - Upper extremity: 8–10 layers.
     - Lower extremity: 12–15 layers.
     - Up to 20 for a large person.
     - More layers of plaster of Paris increase the risk of burn and the weight of the splint.
3. Administer appropriate anesthesia.
   - Conscious sedation
   - Hematoma block
   - Intra-articular injection
   - Intravenous pain medication
   - Oral pain medication
4. Hang fractures as indicated for improved success of reduction to relax muscles before reduction attempt.
5. Reduce afflicted extremity.
6. While maintaining reduction, apply respective splint.
7. Apply in the following order for plaster of Paris splint.
   - Stockinette (not necessary).
   - Soft wrap.
   - Select appropriate layers of plaster of Paris.
   - Prepare plaster of Paris to create splint:
     - Layer plaster with no overlap.
     - Submerge completely into water.
     - Crumple into ball without letting go of the ends of the splint.
     - Release the lower end of the splint while holding the top tightly together.
     - Run fingers in a “squeegee” manner from top to bottom to smooth the splint (Fig. 98.2).
       - This also removes excess water.
       - Repeat until the splint is smooth and free of dripping water.
     - Apply soft wrap layers to the splint.
       - Apply thicker layer to the patient’s body.
       - Apply two or three layers of soft wrap to the exterior of plaster of Paris for padding and to facilitate drying.
     - Apply Ace wrap to hold the splint and assist in contouring the splint to the patient’s extremity (Fig. 98.3).
       - Applying the Ace wrap too tightly may cause ischemia. Observe the patient after splinting for 30 min for tingling, burning, pain, or discomfort.
     - Mold the splint without making indentations with the fingertips (Fig. 98.4).
       - An indentation may cause a pressure point, which may result in an ulcer.



Fig. 98.2 Hold the top of the saturated plaster securely with one hand while removing excess water with the other hand



Fig. 98.3 Apply Ace wrap to hold the splint and assist in contouring the splint to the patient's extremity



Fig. 98.4 Hold the splint in a neutral anatomical position while taking care not to make indentations with the fingertips

  - Allow the splint to cure while the practitioner maintains the appropriate position. This will take approximately 5 min depending upon water temperature and splint thickness.

98.5 Complications

- Ischemia may result in compartment syndrome.
  - Advise the patient to unwrap the splint for the following indications.
    - Increasing pain.
    - Discoloration of fingers, toes, or the splinted extremity.
    - Loss of sensation of splinted extremity.
- Burns
  - Plaster drying releases heat.
  - Increased risk with limited layers of padding.
  - If pain is troubling the patient, remove the splint and add more padding.
- Pressure sores
  - Apply ample padding.
  - Smooth all wrinkles.
  - Instruct the patient to return for increased discomfort.
- Infection
  - Clean and débride all devitalized tissue before application.
  - Requires close follow-up to reevaluate wounds.

Selected Reading

Fitch MT, Nicks BA, Pariyadath M, McGinnis HD, Manthey DE. Basic splinting techniques. N Engl J Med. 2008;359:e32.

Marx JA, Hockberger R, Walls R, editors. Rosen's emergency medicine: concepts and clinical practice. 7th ed. Philadelphia: Mosby; 2010.

Simon R, Sherman S, Koenigsknecht S. Emergency orthopedics—the extremities. New York: McGraw-Hill; 2007.

99 Ulnar Gutter Splint

Jeffrey Kile, Katrina John, and Amish Aghera

99.1 Indications

- Fractures and soft tissue injuries of the ring or little finger
- Fractures of the neck, shaft, or base of the fourth or fifth metacarpal

99.2 Contraindications

- Relative
  - Evidence of compartment syndrome or any neurovascular compromise

99.3 Materials (Fig. 99.1)

- Splint roll (plaster of Paris, prefabricated foamcore, or fiberglass)
- Stockinette
- Cotton padding, such as simple cotton sheet wadding or a newer alternative such as Webril (Curity), Specialist (Johnson & Johnson), and so on
- Elastic bandages, such as Ace (3M) or similar
- Shears
- Adhesive tape
- Gloves

J. Kile, MBBS, PhD, MPH (✉) • K. John, MBBS
Department of Emergency Medicine, Eisenhower Medical Center,
Rancho Mirage, CA, USA
e-mail: jeffrey.kile@gmail.com; trenjohn@me.com

A. Aghera, MD
Department of Emergency Medicine, Maimonides Medical Center,
New York, NY, USA
e-mail: aaghera@maimonidesmed.org

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_99



Fig. 99.1 Materials and medications

99.4 Procedure

1. Select the appropriate diameter stockinette according to the size of the forearm.
    - Generally, 3-in. diameter stockinette is used for the ulnar gutter splint.
2. Cut the stockinette to a length approximately 20 cm longer than the total length of the desired splint.
3. Apply the stockinette to the injured limb so that the stockinette extends approximately 10 cm beyond the region to be splinted proximally and distally.
4. Cut the distal aspect of the stockinette to free the thumb and also the index and middle finger (Fig. 99.2).
5. Insert cotton padding cut to the appropriate size between the ring and the little fingers to prevent skin degradation (Fig. 99.3).
6. Wrap cotton padding circumferentially around the entire region to be splinted, with each turn overlapping the previous turn by approximately 25 % of its width.
    - Generally, 3-in.-wide padding is used for the ulnar gutter splint.
    - Apply padding to an approximate thickness of 1 cm, with extra padding placed over the bony prominences of the wrist and carpometacarpal joints.
    - Extend the padding at least an inch beyond the desired splint length so that it may later be folded back over the jagged ends of the plaster or fiberglass splint roll (Fig. 99.4).
7. Unwrap and prepare an appropriate length splint.
    - The width of splinting material used should be approximately one-half the circumference of the extremity measured at the wrist, such that it is wide enough to extend approximately halfway around the distal forearm once applied.
    - Layer the splint eight sheets thick if using plaster roll and six sheets thick if using fiberglass roll.
    - It is best to begin with a generous length of splinting material because both plaster and fiberglass splint rolls shrink slightly once moistened. If the wet splint turns out too long, the ends can be either folded back or cut with shears before hardening.
8. Apply the dry splinting material to the ulnar aspect of the extremity from the midforearm to just beyond the distal interphalangeal joint of the little finger and cut the splint to approximately 20 cm longer than the desired length.
9. Submerge the dry splint in water until bubbling stops.
10. Remove the splint from water, place on a hard flat surface, and smooth out the excess water to ensure no wrinkles are present.
11. Apply to the splint to the limb over the cotton padding.
    - If the splint is too long at this stage, the ends may be folded back or cut with shears to the proper length.

12 Once positioned properly, fold the side of the splint up around the ulnar aspect of the forearm and hand to form a gutter (Fig. 99.5).

13. Fold the underlying cotton padding and stockinette back over the ends of the splint, which both protects the skin and holds the splint in place.
14. Secure the loose end(s) of the elastic bandage with adhesive tape.
    - Avoid using the metal clips often packaged with elastic bandages because these can become displaced and embed in the skin.
15. Manipulate the forearm and hand into the “neutral” position: (1) the wrist in slight extension (10–20°), (2) the metacarpophalangeal joints in 50° of flexion, and (3) the proximal and distal interphalangeal joints of the ring and little finger in slight flexion (10–15°) (Fig. 99.6).
    - When splinting a boxer’s (i.e., metacarpal neck) fracture, the metacarpophalangeal joint should be flexed to 90°.
16. Mold the splint to the contour of the extremity (Fig. 99.7).
    - Use only the palms of the hands when molding because the fingertips may cause indentations, resulting in excessive skin pressure.
17. Wrap the extremity with an elastic bandage in a distal-to-proximal direction to secure the splint in place (Fig. 99.8).
18. Ensure the extremity is neurovascularly intact.
19. Instruct the patient to loosen the elastic bandage if it feels too tight.



Fig. 99.2 Stockinette applied to the forearm and hand



Fig. 99.3 Cotton padding applied to the ring and little fingers



Fig. 99.4 Cotton padding applied to the forearm and hand



Fig. 99.5 Splint folded around the ulnar aspect of the forearm and hand



Fig. 99.6 Forearm and hand in the neutral position (without splint)

Fig. 99.7 Splint molded to maintain the forearm and hand in the neutral position





Fig. 99.8 Splint secured in place with an elastic bandage

99.5 Complications

- Neurovascular or other soft tissue compromise (if the splint/bandage is too tight)
- Soft tissue degradation (if the splint is left in place too long)

99.6 Pearls and Pitfalls

- Pearls
  - Simple plaster of Paris splints are inexpensive and allow a thoroughly customizable fit but can be damaged by water and require more time to set and more clean up than prefabricated foamcore or fiberglass splint rolls.
  - Simple fiberglass splints set quickly, are not damaged by water, are stronger and lighter than simple plaster and prefabricated splints, and offer a fully customized fit, but are not applied as quickly as prefabricated splints.
  - Prefabricated fiberglass splints are quickly applied, require virtually no clean up, and are not damaged by water, but are relatively expensive and provide a somewhat less customizable fit than simple splint rolls.
  - Stockinette protects the skin and, when folded back over the ends of the plaster or fiberglass splint roll, holds the wet splint in place before the elastic bandage is placed, and provides a padded rim with a professional appearance.
- Pitfalls
  - Avoid wrinkling the cotton padding applied between the stockinette and the splinting material because, once under the pressure of the elastic bandage, wrinkles can cause unnecessary skin pressure.
  - Avoid using more or fewer layers of splinting material than recommended. Additional layers can result in excessive heat during the setting process and a splint that is too heavy, whereas insufficient layers can result in a splint that is too weak.

Selected Reading

Harrison BP, Hilliard MW. Emergency department evaluation and treatment of hand injuries. Emerg Med Clin North Am. 1999;17:793–822.

Henry MH. Fractures of the proximal phalanx and metacarpals in the hand: preferred methods of stabilization. J Am Acad Orthop Surg. 2008;16:586–95.

Margic K. External fixation of closed metacarpal and phalangeal fractures of digits. A prospective study of one hundred consecutive patients. J Hand Surg Br. 2006;31:30–40.

McMahon PJ, Woods DA, Burge PD. Initial treatment of closed metacarpal fractures. A controlled comparison of compression glove and splintage. J Hand Surg Br. 1994;19:597–600.

Viegas SF, Tencer A, Woodard P, Williams CR. Functional bracing of fractures of the second through fifth metacarpals. J Hand Surg Am. 1987;12:139–43.

Shoulder Dislocation Reduction Techniques

100

Katrina Skoog Nguyen, L. Connor Nickels, and Rohit Pravin Patel

100.1 Indications

- Subjective history of new-onset dislocation or recurrent dislocations combined with clinical assessment consistent with shoulder dislocation
  - Anterior dislocations (96 %)
    - Typical mechanism of injury being indirect, with combination of abduction, extension, and external rotation. Rarely, the etiology is a direct blow to the posterior shoulder.
    - Prominent acromion with a palpable drop off below the acromion and subclavicular region fullness is consistent with anterior shoulder dislocation.
  - Posterior dislocations (4 %)
    - Mechanism of injury is indirect with a combination of internal rotation, adduction, and flexion. Precipitating events include seizure, electrical shock, and falls.
    - More subtle presentation. Patient will maintain arm locked in internal rotation and adduction; he or she cannot externally rotate. Shoulder is flattened anteriorly and rounded posteriorly.
    - Ultrasound can be used to prevent missed or delayed diagnosis (Figs. 100.1 and 100.2 show probe positioning and a diagram of abnormal ultrasound anatomy).
  - Inferior dislocations (luxation erecta)
    - Arm will be held fixed in overhead position.
- Radiographs reveal shoulder dislocation.
- Ultrasound can be used to identify the nature of the dislocation (anterior or posterior) and can be determined by the position of the humeral head relative to the transducer and glenoid. Although at this point, it should not replace radiographs owing to missed fractures. Advantages may include less radiation (decreased need for postreduction x-rays) and re-sedation if reduction is not complete.

K. Skoog Nguyen, DO
Northwest Community Hospital, Arlington Heights, IL, USA
e-mail: katrinaskoog@hotmail.com

L.C. Nickels, MD, RDMS (✉) • R.P. Patel, MD
Department of Emergency Medicine, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: cnickels@ufl.edu; rohitpatel@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_100


a
b
2012Oct17 14:59
Res
S MB
Sup
L25
97%
MI
0.7
TIS
0.2
194
Humeral
head
Tissue/
muscle
Glenoid
Bone shadow
Cine
5.1

Fig. 100.1 (**a**, **b**) Ultrasound image of normal shoulder anatomy. "Dot fits the Dot" means when looking at the ultrasound machine from the sonographer's standpoint, the side of the probe marker corresponds to the side the marker is on the screen. This ensures when doing procedures, the direction of needle correction is the same as the orientation of the probe (Images courtesy of Dr. Rohit Patel)


2012Oct17 14:59
Res
S MB
Sup
L25
97%
MI
0.7
TIS
0.2
194
Anterior
dislocation
Cine
5.1
a
2012Oct17 14:59
Res
S MB
Sup
L25
97%
MI
0.7
TIS
0.2
194
Posterior
dislocation
Cine
5.1
b

Fig. 100.2 Anterior (**a**) and posterior (**b**) dislocations (Images courtesy of Dr. Rohit Patel)

100.2 Contraindications

- Associated fracture
  - This warrants orthopedic evaluation.
- Associated neurovascular deficit
  - May attempt reduction once but avoid multiple attempts.

100.3 Materials and Medications

- 1 % lidocaine, with syringe and needle and povidone-iodine prep if administering local anesthesia
- Moderate sedation medications if administering moderate sedation
- Bed sheet for traction-countertraction method
- Dangling weight for Stimson maneuver

100.4 Procedure

- Physical examination
  - Compare affected with unaffected shoulder.
  - Perform a complete neurovascular examination: test axillary, radial, ulnar, and median nerves for sensory deficit and motor function.
- Radiographs
  - Always obtain before attempting reduction for assessment of possible fracture and type and position of dislocation.
  - Obtain three views: anteroposterior, scapular Y, and axillary lateral views.
  - Anterior dislocations: humeral head appears anterior to the glenoid fossa on lateral or Y views.
  - Posterior dislocations: on anteroposterior view (vacant glenoid sign, 6-mm sign, lightbulb sign; on lateral or Y view: humeral head appears posterior to glenoid fossa).
- Pain management and sedation
  - Decide whether to use intra-articular lidocaine versus procedural sedation and analgesia.
  - For intra-articular lidocaine
    - Use 10–20 mL of 1 % lidocaine.
    - Attach a 1.5-in., 20-gauge needle.
    - Prepare the shoulder with povidone-iodine.
    - Insert the needle lateral to the acromion process and 2 cm inferiorly into the sulcus.
    - After withdrawing to ensure that the needle is not in a vessel, inject 10–20 mL lidocaine into the joint.
- Reduction techniques: it is important for the emergency department physician to be familiar with several different techniques. The following techniques are presented:

100.4.1 Stimson Maneuver (Fig. 100.3)

1. Patient is placed prone with 2.5–5 kg of weight hanging from the wrist.
2. Reduction may be facilitated by traction and external rotation of the arm.
3. A success rate of 96 % has been reported using the combined prone position, hanging weights, intravenous drug therapy, and scapular manipulation.

- Advantage: can be performed by one person only.
- Disadvantages: requires time to gather materials; the danger involved in the patient falling off the stretcher, requiring staff to monitor the patient.



Fig. 100.3 Stimson maneuver

100.4.2 Scapular Manipulation Technique (Fig. 100.4)

1. Place the patient in the prone position with the affected arm hanging downward.
2. Apply traction down on the arm.
3. Locate the inferior tip of the scapula. Simultaneously push the inferior tip of the scapula medially toward the spine and use the other hand push the superior scapula laterally.

- Advantages: high success rate, greater than 90 %; very safe to perform.
- Disadvantages: it requires the patient to assume the prone position; may require another person to perform traction.



Fig. 100.4 Scapular manipulation method

100.4.3 External Rotation Method (Fig. 100.5)

1. Place the patient in the supine position with the affected arm adducted directly next to the patient's side with the elbow flexed to 90°.
2. The operator uses one hand to direct downward traction on the affected arm while maintaining it next to the patient's side.
3. The operator uses the other hand to hold the patient's wrist and guide the arm into slow external rotation.
4. Reduction usually takes place between 70° and 110° of external rotation.

- Advantages: requires no strength by operator; well tolerated by patients.
- Disadvantage: patient may have persistent dislocation during procedure, requiring operator to make adjustments.



Fig. 100.5 (**a**–**d**) Kocher technique: external rotation method

100.4.4 Milch Technique (Fig. 100.6)

1. Technique looks as though one is reaching up to grab an apple from a tree.
2. Abduct the injured arm up to the overhead position.
3. Once in the overhead position, apply gentle vertical traction with external rotation.
4. An adjustment may need to be made if the reduction does not occur easily; push the humeral head upward into the glenoid fossa.

- Advantages: lack of complications; patient tolerance
- Disadvantage: variable success rate reported: 70–90 %



Fig. 100.6 (**a**, **b**) Milch technique

100.4.5 Spaso Technique (Fig. 100.7)

1. Place the patient in the supine position.
2. Operator grasps the affected arm at the wrist and lifts the straight arm directly upward while applying longitudinal traction.
3. Apply external rotation.

- Advantages: single operator, high level of success
- Disadvantage: may require more time to allow the shoulder muscles to relax



Fig. 100.7 (**a**–**c**) Spaso technique (Photographs courtesy of Dr. Pratik S. Patel)

100.4.6 Traction-Countertraction Technique (Fig. 100.8)

1. With the patient is sitting up, have an assistant wrap a sheet around the upper chest and under the axilla of the affected shoulder. Have the assistant wrap the sheet behind her or his back. Now have the patient lay supine.
2. Wrap another sheet around the flexed elbow of the affected arm and behind the operator's back.
3. Both the operator and the assistant lean back, applying gentle traction.

- Advantage: many older physicians are familiar with this method and, therefore, have a high degree of success.
- Disadvantages: requires two people; may cause skin tears on elderly patients.



Fig. 100.8 (**a**, **b**) Hippocrates method/traction-countertraction method

100.4.7 Posterior Shoulder Dislocation Reduction

1. Give adequate premedication.
2. Place the patient supine and apply lateral traction on the proximal humerus.
3. Have an assistant apply anterior pressure to the posteriorly located humeral head.

- Advantage: logical methods for reduction
- Disadvantages: require sufficient premedication because often posterior dislocations present late; may require open reduction

100.4.8 Postreduction

- Obtain postreduction x-rays. There is some literature on using ultrasound to confirm adequate reduction, which allows repetitive assessments throughout procedure, as well as reduce radiation (see Fig. 100.2 for ultrasound of anterior and posterior dislocations).
- Do a postreduction neurovascular examination.
- Sling and swath or shoulder immobilizer for 2–3 weeks.
- Orthopedic follow-up in 1 week.

100.5 Complications

- Fractures
- Adhesive capsulitis, or frozen shoulder; especially a concern in the elderly with prolonged immobilization in sling
- Brachial plexus injury, especially of the axillary nerve
- Vascular laceration, most commonly of the axillary artery
- Rotator cuff tears

100.6 Pearls

- It is imperative to document the pre- and postreduction neurovascular status in the medical record.
- If unsure whether the reduction was successful, attempt to place the palm of the injured extremity on the contralateral shoulder. This is a good sign the reduction was successful.

Acknowledgment The authors would like to thank Karthik Stead for serving as the subject in many of the photographs in this chapter.

Selected Reading

Beck S, Chilstrom M. Point-of-care ultrasound diagnosis and treatment of posterior shoulder dislocation. Am J Emerg Med. 2013;31:449.e3–5.

Blakeley CJ, Spencer O, Newman-Saunders T, Hashemi K. A novel use of portable ultrasound in the management of shoulder dislocation. Emerg Med J. 2009;26:662–3.

Dala-Ali B, Penna M, McConnell J, Vanhegan I, Cobiella C. Management of acute anterior shoulder dislocation. Br J Sports Med. 2014;48(16):1209–15.

Simão MN, Noqueira-Barbosa MH, Muqlia VF, Barbieri CH. Anterior shoulder instability: correlation between magnetic resonance arthrography, ultrasound arthrography, and intraoperative findings. Ultrasound Med Biol. 2012;38:551–60.

Yuen CK, Chung TS, Mok KL, Kan PG, Wong YT. Dynamic ultrasonographic sign for posterior shoulder dislocation. Emerg Radiol. 2011;18:47–51.

Elbow Dislocation Reduction

101

Katrina John, Jeffrey Kile, and Amish Aghera

101.1 Indications

- Any dislocation of the elbow joint. Direction of the dislocation (i.e., anterior, posterior, lateral and divergent radius, and ulnar dislocations) is determined by the position of the ulna relative to the joint space (Fig. 101.1).

101.2 Contraindications

- Relative
  - Compound fracture dislocation

Fig. 101.1 Anatomical depiction



K. John, MBBS • J. Kile, MBBS, PhD, MPH (✉)
Department of Emergency Medicine, Eisenhower Medical Center,
Rancho Mirage, CA, USA
e-mail: trenjohn@me.com; jeffrey.kile@gmail.com

A. Aghera, MD
Department of Emergency Medicine, Maimonides Medical Center,
New York, NY, USA
e-mail: aaghera@maimonidesmed.org

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_101

101.3 Materials and Medications

- Parenteral sedation and analgesia medications
- Local anesthetic for local and intra-articular anesthesia
- Splinting material
- Stockinette
- Padding
- Elastic bandage
- Tape
- Sling

101.4 Procedure for Posterior Dislocations

1. Obtain a true lateral and anteroposterior radiographs of the affected elbow.
2. Ensure adequate sedation and analgesia.
3. Consider intra-articular analgesia.
4. Check the neurovascular status of affected extremity.
5. Follow a selected method for reduction as detailed later.
6. Following successful reduction gently flex the elbow to ensure full range of motion.
7. Place a long-arm posterior splint with the elbow in at least 90° flexion and secure the arm in a regular sling.
8. Check neurovascular status.
9. Obtain a postreduction radiograph of the elbow.

101.4.1 **Method A** (Fig. 101.2)

1. Position the patient on a stretcher in the supine position.
2. Apply steady traction at the supinated distal forearm keeping the elbow slightly flexed, while an assistant applies countertraction to the midhumerus with both hands.

101.4.2 **Method B** (Fig. 101.3)

1. Position the patient on a stretcher in the supine position.
2. Extend the affected extremity over the edge of the stretcher.
3. Apply traction to the supinated forearm slightly flexed at the elbow, while an assistant holds the distal humerus with both hands and uses thumbs to apply pressure to the olecranon as if pushing it away from the humerus.

101.4.3 **Method C** (Fig. 101.4)

1. Position the patient on a stretcher in the prone position.
2. Hang the affected extremity over the side of the stretcher toward the floor.
3. Apply downward traction to the pronated distal forearm and with the other hand just above the patient's antecubital fossa lift the humerus toward you.



Fig. 101.2 Posterior method A



Fig. 101.3 Posterior method B



Fig. 101.4 Posterior method C

101.5 Procedure for Anterior Dislocations (Fig. 101.5)

1. Follow pre- and postprocedure steps as documented for the posterior dislocation.
2. Position the patient on a stretcher in the supine position.
3. With one hand, apply traction to the supinated distal forearm with the elbow extended, while an assistant applies countertraction with both hands around the distal humerus.
4. With the other hand apply downward and backward pressure over the proximal forearm just below the antecubital fossa.



Fig. 101.5 Anterior elbow

101.6 Procedure for Radial Head Subluxations (See Also Chap. 127)

1. This procedure can normally be performed without any sedation or parenteral analgesia.
2. Position the patient, most commonly a child aged 1–3 years, facing forward on the caretaker's lap.
3. Hold the flexed elbow of the affected extremity placing your thumb firmly over the radial head.
4. With the other hand, take the child's hand and wrist, and in one continuous movement, hyperpronate and flex the forearm (Figs. 101.6 and 101.7).
5. Another method is to supinate and flex the forearm instead of hyperpronating it (Fig. 101.8).
6. Leave the room, encourage the caretaker to engage the child with distracting activities and reexamine the child in 10–20 min, at which stage, if reduction was successful, the child should be using the extremity normally again.
7. No postreduction radiograph or immobilization is required.



Fig. 101.6 Subluxation hyperpronated



Fig. 101.7 Subluxation hyperpronated and flexed



Fig. 101.8 Subluxation supinated

101.7 Complications

- Concomitant fractures
- Vascular injury, most commonly to the brachial artery
- Median nerve injury/entrapment
- Recurrent dislocation—rare

101.8 Pearls and Pitfalls

- Pearls
  - A true lateral radiograph is necessary to accurately detect and identify elbow fractures, dislocations, and soft tissue abnormalities (i.e., the fat pad sign). It is obtained with the patient's elbow in 90° flexion, in neutral rotation with the thumb pointing up and the arm and forearm resting on the radiograph cassette and the beam nearly perpendicular to the cassette. On a true lateral, the "hourglass" or "figure-of-eight" formation at the distal humerus should be clearly visible, and the rings of the capitellum and trochlea should be concentric.
  - During nursemaid elbow reduction, provide age appropriate distractions to divert the child's attention and minimize resistance.
- Pitfalls
  - On the pre- and postreduction radiographs, search for commonly associated fractures of the distal humerus, radial head, and coronoid process.
  - Inability to range the elbow after apparent reduction indicates possible trapped fracture fragments and the need for operative intervention.
  - Vascular or open injuries are common with anterior dislocations, and early orthopedic consultation is advised.
  - Ninety percent of simple elbow dislocations are posterior, and this injury is rarely associated with vascular injury. However, it does occur, and vascular evaluation after every reduction is good clinical practice.

Selected Reading

Jain K, Shashi Kumar Y, Mruthyunjaya, Ravishankar R, Nair AV. Posterior dislocation of elbow with brachial artery injury. J Emerg Trauma Shock. 2010;3:308.

Kuhn MA, Ross G. Acute elbow dislocations. Orthop Clin North Am. 2008;39:155–61.

McDonald J, Witelaw C, Goldsmith LJ. Radial head subluxation. Comparing two methods of reduction. Acad Emerg Med. 1999;6:715.

Sheps DM, Hildebrand KA, Boorman RS. Simple dislocations of the elbow: evaluation and treatment. Hand Clin. 2004;20:389–404.

Villarin Jr LA, Belk KE, Freid R. Emergency department evaluation and treatment of elbow and forearm injuries. Emerg Med Clin North Am. 1999;17:843–58.

Distal Interphalangeal Joint Reduction

102

Justin Chen and Muhammad Waseem

Distal interphalangeal (DIP) joint dislocation is rare. It occurs when an axial force is applied to the distal phalanx (Fig. 102.1).



Fig. 102.1 Distal interphalangeal joint dislocation

102.1 Indications

- DIP joint reduction is performed to alleviate functional and anatomical derangements resulting from DIP joint dislocation, commonly dorsal, from axial compression.

102.2 Contraindications

- Absolute
  - Absence of radiographic confirmation (anteroposterior, true lateral, and oblique) of simple DIP joint dislocation, especially in pediatric cases
- Relative
  - Open joint dislocation, associated fracture, or entrapped volar plate
  - Digital neurovascular compromise

102.3 Materials and Medications

- Latex-free gloves
- Local anesthetic: 2 % lidocaine without epinephrine, 1.5 % mepivacaine, 0.5 % ropivacaine, or 0.5 % bupivacaine
- 25-gauge × 1.5-in. needle (can substitute with 27 or 30 gauge)
- Small plastic syringe, 10 mL
- Padded, malleable, aluminum digital splint

J. Chen, MD, MSc
Department of Emergency Medicine, North Shore University Hospital, Manhasset, NY, USA
e-mail: chen.justin@gmail.com

M. Waseem, MD (✉)
Department of Emergency Medicine, Lincoln Medical and Mental Health Center, New York, NY, USA
e-mail: waseemm2001@hotmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_102

102.4 Procedure

1. Place the patient in the seated position with the arms at rest on a bedside table or supported by an assistant.
2. Pronate the patient's hand, remove rings if present, and rest on a flat surface.
3. Insert a 25-gauge needle at the dorsolateral aspect of the base of the finger to form a wheal to reduce patient discomfort.
4. Advance the needle and direct anteriorly toward the phalangeal base.
5. Inject 0.5–1 mL of local anesthetic as the needle is withdrawn 1–2 mm from the point of bone contact.
6. Inject an additional 1 mL of local anesthetic continuously as the needle is withdrawn.
7. The injection should never render the tissue tense nor be circumferential.
8. Hyperextend the DIP joint while applying longitudinal traction, followed by immediate joint flexion at the base of the distal phalanx.
9. Place finger(s) in an aluminum digital dorsal splint in slight flexion for 2 weeks (Fig. 102.2).
10. Postreduction radiograph is recommended for confirmation.



Fig. 102.2 Padded aluminum splint applied to block the DIP joint in flexion but allow further flexion, which encourages active flexion of that joint when the PIP joint flexes (Reproduced with permission from: HandLab Clinical Pearls Feb 2011, No 12. www.handlab.com)

102.5 Complications

- Irreducible dislocations
- Stiffness
- Recurrent dislocation
- Extensor lag in joints with residual subluxation
- Associated with dorsal joint prominences, swan-neck/boutonnière deformity, and degenerative arthritis

102.6 Pearls and Pitfalls

- Pearls
  - Lidocaine without epinephrine is preferred owing to the risk of vasoconstriction of the digital vessels with epinephrine.
  - Regardless of the mechanism of trauma, all joints (DIP, proximal interphalangeal, metacarpophalangeal) should be assessed for instability.
  - Joint dislocations involving volar plate entrapment may require surgical repair (open reduction internal fixation) for successful reduction.
- Pitfalls
  - Irreducible DIP joint dislocations may be due to entrapment of an avulsion fracture, the profundus tendon, or the volar plate.

Selected Reading

Calfee RP, Sommerkamp TG. Fracture-dislocation about the finger joints [review]. J Hand Surg Am. 2009;34:1140–7.

Knoop KJ. Atlas of emergency medicine. 3rd ed. New York: McGraw-Hill Professional; 2010.

Simon RR, Sherman SC, Sharieff GQ. Emergency orthopedics. 6th ed. New York: McGraw-Hill Medical; 2011.

Stone CK, Humphries RL. Current diagnosis & treatment emergency medicine. 6th ed. New York: McGraw-Hill; 2008.

Tintinalli JE, Stapczynski JS, Ma OJ, Cline D, Cydulka R, Meckler G, editors. Tintinalli's emergency medicine: a comprehensive study guide. 7th ed. New York: McGraw-Hill; 2012.

Hip Dislocation Reduction

103

Katrina John, Jeffrey Kile, and Amish Aghera

103.1 Indications

Displacement of the femoral head in relation to the acetabulum without concomitant femoral neck, head, or acetabulum fractures:

- Posterior hip dislocations make up 80–90 % of cases.
- Anterior hip dislocations make up 10–15 % of cases. These are classified into obturator, pubic, iliac, central, or inferior types. Central dislocations are associated with comminuted acetabulum fractures, and inferior dislocations are a rare occurrence normally occurring in children younger than 7 years of age.
- Prosthetic hip dislocations

103.2 Contraindications

- Absolute
  - Femoral neck fracture: attempted reduction may increase the displacement of the fracture and increase the probability of avascular necrosis.
- Relative
  - Fractures in other parts of the affected lower extremity: these may limit the pressure that can be applied necessary for traction during reduction.

103.3 Materials and Medications

- Parenteral sedation and analgesia medications
- Sheet or belt to fix the pelvis to the stretcher
- Knee immobilizer
- Abduction pillow

103.4 Procedure

1. Check the neurovascular status of the affected extremity.
2. Obtain anteroposterior (AP) views of the pelvis and lateral views of the hip.
3. Ensure adequate parenteral sedation and analgesia.
4. Decide upon a technique, as detailed later, and position the patient accordingly.
5. Once the hip has been successfully reduced, test the joint for stability by moving it gently thought its range of motion.
6. Place a knee immobilizer and an abduction pillow between the knees.
7. Check the neurovascular status.
8. Obtain repeat AP films of the pelvis.

K. John, MBBS • J. Kile, MBBS, PhD, MPH (✉)
Department of Emergency Medicine, Eisenhower Medical Center,
Rancho Mirage, CA, USA
e-mail: trenjohn@me.com; jeffrey.kile@gmail.com

A. Aghera, MD
Department of Emergency Medicine, Maimonides Medical Center,
New York, NY, USA
e-mail: aaghera@maimonidesmed.org

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_103

103.4.1 Stimson Maneuver

1. Place the patient prone on the stretcher with the affected extremity hanging over the edge and the hip flexed to 90°.
2. Flex the knee and the foot to 90°.
3. Apply downward pressure to the area just distal to the popliteal fossa with a hand (Fig. 103.1) or knee (Fig. 103.2) while using the opposite hand to internally and externally rotate the hip at the ankle.
4. Have an assistant simultaneously manipulate the displaced femoral head into position with both hands, applying downward pressure over the affected buttock (Fig. 103.3).



Fig. 103.1 Stimson maneuver with hand



Fig. 103.2 Stimson maneuver with knee



Fig. 103.3 Manipulation of the femoral head

103.4.2 Allis Maneuver

1. Position the patient supine on the stretcher.
2. The operator should stand on the stretcher to achieve maximum leverage or have the patient on a backboard on the ground.
3. Have an assistant apply downward pressure to both iliac crests.
4. Apply constant, gentle upward traction in line with the deformity while maneuvering the hip to 90° flexion and through internal and external rotation (Fig. 103.4).
5. Have a second assistant provide lateral traction to the midthigh.
6. Once the femoral head has cleared the outer lip of the acetabulum, continue traction while keeping the hip in external rotation and gently abducting and extending the hip (Fig. 103.5).



Fig. 103.4 Allis flexion



Fig. 103.5 Allis extension

103.4.3 Whistler Technique

1. Position the patient supine on the stretcher with the knee and hip flexed to 45°.
2. Have an assistant stabilize the pelvis with downward pressure on both iliac crests.
3. Stand on the side of the affected extremity and place one arm under the knee, resting the hand on the flexed knee of the unaffected extremity.
4. Secure the ankle of the affected extremity with the other hand and elevate the shoulder of the opposite arm, providing upward traction at the distal thigh and a strong fulcrum to reduce the dislocation (Fig. 103.6).
5. Internal and external rotation can be achieved with the opposite hand at the ipsilateral ankle.



Fig. 103.6 Whistler technique

103.4.4 Captain Morgan Technique

1. Position the patient supine on the stretcher with the knee and hip flexed to 90°.
2. Stabilize and fix the pelvis with a sheet tied securely over the pelvis and under the stretcher.
3. Standing on the side of the affected extremity, the operator's foot should be resting perpendicular on the stretcher with the knee placed under the patient's knee.
4. With the opposite hand, apply downward pressure to the ankle and provide a sustained upward force to the patient's thigh by elevation of the knee through plantar flexion of the toes and upward pressure of the other hand placed behind the patient's knee.
5. Internal and external rotation can be applied simultaneously if necessary by gently twisting the ankle (Fig. 103.7).



Fig. 103.7 Captain Morgan technique

103.5 Complications

- Sciatic nerve injury
- Avascular necrosis of the femoral head due to delay in adequate reduction
- Inability to perform reduction due to occult fractures and fracture fragments, incarceration of the joint capsule, or associated tendons
- Unstable or irreducible dislocations
- Traumatic arthritis and joint instability

103.6 Pearls and Pitfalls

- Pearls
  - On AP radiograph, posterior dislocations can be more easily detected by the presence of a smaller femoral head compared with the unaffected side and poor visualization of the lesser trochanter.
  - On AP radiographs, anterior dislocations can be detected by a larger femoral head and a clear lesser trochanter seen in profile alongside the femoral shaft.
  - Pay close attention to the femoral vessels and the sciatic nerve. Injury to the sciatic nerve most commonly affects the common peroneal branch, therefore causing weakness in great toe extension and foot dorsiflexion. Sensation may also be reduced over the dorsum of the foot.
  - Check the femoral head is intact and clearly in the acetabulum and for intact Shenton lines, symmetrical intra-articular spaces, and clear outlines of the lesser trochanters.
  - For any of the techniques requiring stabilization of the pelvis, an alternative is to fix it to the stretcher using a sheet or belt.
  - To overcome the powerful muscles that oppose successful reduction, it is important to provide adequate muscle relaxation and steady, prolonged traction.
  - An assistant should stand on the floor behind to support the operator if standing on a stretcher.
- Pitfalls
  - Owing to the force necessary to dislocate a native hip, this injury should serve as a red flag to the physician to consider other potentially life- or limb-threatening occult injuries.
  - Hip dislocation is a true orthopedic emergency and must be treated without delay. Delay in reduction, especially greater than 6 h, results in increased incidence of avascular necrosis of the femoral head and sciatic nerve injury.
  - Review imaging carefully because associated fractures of the femoral head, neck, and acetabulum are often present.
  - It is recommended that anterior dislocations be reduced by orthopedic surgeons under general anesthetic in the operating room. These are often more complicated and difficult to reduce, and failure at closed reduction in the operating room can be followed by an open procedure.
  - Multiple attempts at reduction should not be performed in the emergency department because these are unlikely to be successful and will only delay definitive management and lead to an increased risk of complications.

Selected Reading

Hendey GW, Avila A. The captain Morgan technique for the reduction of the dislocated hip. Ann Emerg Med. 2011;58:536–40.

Newton EJ, Love J. Emergency department management of selected orthopedic injuries. Emerg Med Clin North Am. 2007; 25:763–93.

Nordt WE. Maneuvers for reducing dislocated hips. Clin Orthop Relat Res. 1999;360:160–4.

Rupp JD, Schneider LW. Injuries to the hip joint in frontal motor-vehicle crashes: biomechanical and real-world perspectives. Orthop Clin North Am. 2004;35:493–504.

Walden PD, Hamer JR. Whistler technique used to reduce traumatic dislocation of the hip in the emergency department setting. J Emerg Med. 1999;17:441–4.

104

Knee Dislocation Reduction

Katrina John, Jeffrey Kile, and Amish Aghera

104.1 Indications

- Dislocation of the knee/fibular head/patella

104.2 Contraindications

- Absolute
  - None
- Relative
  - Immediate availability of orthopedic consultation

104.3 Materials and Medications

- Parenteral sedation and analgesia medications
- Knee immobilizer or splinting materials

104.4 Procedure

104.4.1 Knee (Femur/Tibia) Dislocation Reduction

1. Assess neurovascular function.
2. Pretreat the patient with sedation or analgesia as appropriate.
3. Position the patient supine with the affected leg fully extended.
4. Instruct an assistant to stand near the patient's hip and, facing the patient's affected knee, grasp the distal femur firmly with both hands to fix it in place.
5. Stand near the patient's foot and, facing the patient's affected knee, grasp the distal tibia and apply straight traction in a distal direction.
   - Longitudinal traction-countertraction alone, as described previously, will usually reduce the dislocation. If reduction does not occur, proceed with the following steps.
6. While applying straight traction in a distal direction to the tibia with the dominant hand, with the nondominant hand:
   (a) Anterior dislocation: push the proximal tibia in a posterior direction (Fig. 104.1)
   (b) Posterior dislocation: lift the proximal tibia in an anterior direction (Fig. 104.2)
   (c) Lateral dislocation: push the proximal tibia in a medial direction (Fig. 104.3)
   (d) Medial dislocation: push the proximal tibia in a lateral direction (Fig. 104.4)
   (e) Rotary dislocation: rotate the proximal tibia into proper linear alignment with the femoral condyles (Fig. 104.5)
      - Reduction may be facilitated by the use of two assistants rather than just one. The second assistant grasps the distal tibia and applies straight traction in a distal direction, freeing the operator to manipulate the proximal tibia as described previously using both hands.
7. After reduction, reassess neurovascular function and, if available, obtain angiography.
8. Immobilize the knee in 15° of flexion in a knee immobilizer or long-leg posterior splint.

K. John, MBBS • J. Kile, MBBS, PhD, MPH (✉)
Department of Emergency Medicine, Eisenhower Medical Center,
Rancho Mirage, CA, USA
e-mail: trenjohn@me.com; jeffrey.kile@gmail.com

A. Aghera, MD
Department of Emergency Medicine, Maimonides Medical Center,
New York, NY, USA
e-mail: aaghera@maimonidesmed.org

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_104

Fig. 104.1 Anterior dislocation of the knee: the proximal tibia is pushed in a posterior direction. The *arrows* indicate the direction in which force should be applied by the operator during reduction of dislocation



Fig. 104.2 Posterior dislocation of the knee: the proximal tibia is pushed in an anterior direction. The *arrows* indicate the direction in which force should be applied by the operator during reduction of dislocation



Fig. 104.3 Lateral dislocation of the knee: the proximal tibia is pushed in a medial direction. The *arrows* indicate the direction in which force should be applied by the operator during reduction of dislocation





Fig. 104.4 Medial dislocation of the knee: the proximal tibia is pushed in a lateral direction. The *arrows* indicate the direction in which force should be applied by the operator during reduvction of dislocation



Fig. 104.5 Rotary dislocation of the knee: the proximal tibia is rotated into proper alignment with the femoral condyles. The *arrows* indicate the direction in which force should be applied by the operator during reduction of dislocation

104.4.2 Fibular Head Dislocation Reduction

1. Assess neurovascular function.
2. Pretreat the patient with sedation or analgesia as appropriate.
3. Position the patient supine.
4. Flex the knee to 90° to relax the biceps femoris tendon.
5. Instruct an assistant to stand near the patient's hip and, facing the patient's affected knee, grasp the distal femur firmly with both hands to fix it in place.
6. Stand near the patient's foot and, facing the patient's affected knee, grasp the distal tibia and apply straight traction in a distal direction with the dominant hand and with the nondominant hand.
   (a) Anterior dislocation: push the fibular head in a posterior direction (Fig. 104.6)
   (b) Posterior dislocation: push the fibular head in an anterior direction (Fig. 104.7)
      - Reduction may be facilitated by the use of two assistants rather than just one. If a second assistant is available, instruct the second assistant to stand near the patient's foot and, facing the patient's affected knee, grasp the distal tibia and apply straight traction in a distal direction. This enables the operator to grasp and move the proximal fibula as described previously using both hands.
      - Reduction is often signified by a palpable and audible click as the fibula snaps back into position.
7. After reduction, reassess neurovascular function and, if available, obtain angiography.
   - After reduction, patients should receive orthopedic referral, avoid weight-bearing for the first 2 weeks, and then gradually increase weight-bearing over the next 6 weeks.
   - Typically, immobilization is not required following reduction of an i.solated fibular head dislocation.



Fig. 104.6 Anterior dislocation of the fibular head: the fibular head is pushed in a posterior direction. The *arrow* indicate the direction in which force should be applied by the operator during reduction of dislocation



Fig. 104.7 Posterior dislocation of the fibular head: the fibular head is pushed in an anterior direction. The *arrow* indicate the direction in which force should be applied by the operator during reduction of dislocation

104.4.3 Lateral Patellar Dislocation Reduction

1. Pretreat the patient with sedation or analgesia as appropriate.
2. Stand at the side of the affected knee and, facing the knee, grasp the distal tibia and slowly extend the knee with one hand, and with the other hand simultaneously apply gentle pressure to the patella in a medial direction.

- The lateral edge of the patella may be lifted slightly to facilitate its travel over the femoral condyle during reduction (Fig. 104.8).
- After reduction, the knee should be immobilized in full extension in a knee immobilizer or long-leg posterior splint, and the patient should receive orthopedic referral, avoid weight-bearing for the first 2 weeks, and then gradually increase weight-bearing over the next 6 weeks.



Fig. 104.8 Lateral dislocation of the patella: the patella is pushed in a medial direction. The *arrow* indicate the direction in which force should be applied by the operator during reduction of dislocation

104.5 Complications

104.5.1 Knee (Femur/Tibia) Dislocations

- Distal ischemia (even requiring amputation)
- Degenerative arthritis
- Joint instability due to ligamentous injury

104.5.2 Fibular Head Dislocations

- Peroneal nerve injury
- Fibular head instability/subluxation
- Degenerative arthritis

104.5.3 Patellar Dislocations

- Failure of reduction
- Degenerative arthritis
- Recurrent dislocation/subluxation

104.6 Pearls and Pitfalls

104.6.1 Knee (Femur/Tibia) Dislocations

- Pearls
  - Dislocations of the knee are described in terms of the tibia's position in relation to the femur.
  - All knee dislocations require orthopedic evaluation at the earliest possible opportunity.
  - Owing to the frequency of associated popliteal artery and peroneal nerve injury, a neurovascular examination should be performed before and after any attempts at reduction or manipulation of the knee.
  - Dislocations of the knee should be reduced as soon as possible, particularly if distal neurovascular compromise exists.
  - Operative ligamentous repair is often required approximately 2 weeks postreduction (once acute swelling has resolved) to achieve the maximum functional recovery.
- Pitfalls
  - If the knee hyperextends more than 30° when the horizontal leg is lifted by the foot, the knee is considered severely unstable. This is likely due to a previous dislocation, and thus, the knee should be evaluated for the neurovascular complications of dislocation.
  - Because the joint capsule is commonly disrupted during knee dislocation, synovial fluid may diffuse into the surrounding tissue, such that an effusion is not always present.
  - A posterolateral dislocation may be irreducible because the medial femoral condyle traps the medial capsule within the joint.

104.6.2 Fibular Head Dislocations

- Pearls
  - Fibular head dislocations are usually anterolateral, but these do not result in neurovascular compromise.
  - A knee joint effusion is usually not seen in a fibular head dislocation because the tibiofibular ligaments are contained within a separate synovium.
  - Anterior dislocations typically result from a fall on the flexed, adducted leg, often combined with ankle inversion.
  - Flexion of the knee relaxes the fibular collateral ligament, reducing the stability of the tibiofibular joint.
  - Superior dislocation is accompanied by interosseus membrane damage and proximal displacement of the lateral malleolus.
- Pitfalls
  - Posterior fibular head dislocations usually result from direct trauma to the flexed knee and may be accompanied by peroneal nerve injury.

104.6.3 Patellar Dislocations

- Pearls
  - Patellar dislocation occurs most frequently among adolescents.
  - Patellar dislocation typically occurs in the setting of external rotation combined with a strong valgus force and quadriceps contraction.
  - Patellar dislocations are described in terms of the patellar relationship to the normal knee joint.
  - The most common patellar dislocations are lateral.
  - If a spontaneous reduction has occurred, a knee effusion and tenderness along the medial aspect of the patella are likely to be present on examination, and the patellar apprehension test will be positive.
  - To perform the patellar apprehension test, flex the knee to 30° and push the patella laterally. If the patient senses an impending redislocation, the test is considered positive.

  - Isolated lateral patellar dislocations do not usually require hospitalization, but orthopedic follow-up is recommended owing to the likelihood of persistent instability.
  - Intracondylar and superior dislocations require surgical reduction.
  - Patients with an isolated patellar dislocation typically present with the knee in 20–30° of flexion and the patella displaced laterally.
- Pitfalls
  - Dislocations tend to be recurrent, particularly in patients with patellofemoral anatomical abnormalities.

Selected Reading

Martinez D, Sweatman K, Thompson EC. Popliteal artery injury associated with knee dislocations. Am Surg. 2001;67:165–7.

Peskun CJ, Levy BA, Fanelli GC, et al. Diagnosis and management of knee dislocations. Phys Sportsmed. 2010;38:101–11.

Rihn JA, Groff YJ, Harner CD, Cha PS. The acutely dislocated knee: evaluation and management. J Am Acad Orthop Surg. 2004;12:334–46.

Roberts DM, Stallard TC. Emergency department evaluation and treatment of knee and leg injuries. Emerg Med Clin North Am. 2000;18:67–84. v–vi.

Wascher DC, Dvirnak PC, DeCoster TA. Knee dislocation: initial assessment and implications for treatment. J Orthop Trauma. 1997;11:525–9.

Ankle Dislocation Reduction

105

Katrina John, Jeffrey Kile, and Amish Aghera

105.1 Indications

- Dislocation of the ankle joint. This is defined by the articulation of the talus with the mortise that is formed by the distal tibia and fibula. Dislocations can be posterior, anterior, superior, or lateral and are classified by the position of the talus in relation to the tibial mortise.

105.2 Contraindications

- Relative
  - Open dislocations where there is no evidence of acute neurovascular compromise are better managed definitively in the operating room to avoid further contamination.

105.3 Materials and Medications

- Parenteral sedation and analgesia medications
- Local anesthetic for local and intra-articular anesthesia
- Splinting material
- Stockinette
- Padding
- Elastic bandage
- Tape
- Sheet

105.4 Procedure

1. Check the neurovascular status of the affected foot and ankle.
2. If there is no evidence of critical neurovascular compromise, obtain a lateral and an anteroposterior radiograph of the affected ankle.
3. Ensure adequate parenteral sedation and analgesia to maximize success and limit pain and suffering.
4. Position the patient on a stretcher with the knee flexed at 90° over a folded pillow or rolled-up sheet or with the lower leg and knee hanging over the edge of the stretcher.

K. John, MBBS • J. Kile, MBBS, PhD, MPH (✉)
Department of Emergency Medicine, Eisenhower Medical Center,
Rancho Mirage, CA, USA
e-mail: trenjohn@me.com; jeffrey.kile@gmail.com

A. Aghera, MD
Department of Emergency Medicine, Maimonides Medical Center,
New York, NY, USA
e-mail: aaghera@maimonidesmed.org

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_105

105.4.1 Posterior Dislocations

1. Hold the heel in one hand and pull with longitudinal traction.
2. With the other hand, hold the top of the foot and gently plantarflex it downward, while an assistant provides countertraction at the back of the midcalf (Fig. 105.1).
3. Continue longitudinal traction at the heel and countertraction at the calf.
4. Dorsiflex the foot while another assistant applies downward pressure to the distal anterior leg (Fig. 105.2).
5. Examine foot for restoration of normal anatomy and for any new lacerations or defects to the skin.
6. Recheck neurovascular integrity.
7. Place the leg in a sugar-tong splint with the foot at 90°.
8. Recheck neurovascular integrity.



Fig. 105.1 Plantarflexion with longitudinal heel traction



Fig. 105.2 Dorsiflexion with longitudinal heel traction

105.4.2 Anterior Dislocations

1. Hold the heel in one hand and pull with longitudinal traction.
2. With the other hand, hold the top of the foot and dorsiflex, while an assistant provides countertraction at the back of the midcalf (Fig. 105.3).
3. Continue longitudinal traction at the heel and countertraction at the calf.
4. Keeping the foot at 90° to the leg, hold the foot firmly and push the foot downward toward the floor while another assistant applies upward pressure to the distal posterior leg (Fig. 105.4).
5. Examine the foot for restoration of normal anatomy and for any new lacerations or defects to the skin.
6. Recheck neurovascular integrity.
7. Place the leg in a sugar-tong splint with the foot at 90°.
8. Recheck neurovascular integrity.



Fig. 105.3 Dorsiflexion with longitudinal heel traction



Fig. 105.4 Downward movement of foot (toward the floor) with longitudinal heel traction

105.5 Complications

- Compound fractures
- Neurovascular injury
- Skin and soft tissue damage
- Compartment syndrome

105.6 Pearls and Pitfalls

- Pearls
  - The ankle rarely dislocates without associated fractures.
- Pitfalls
  - Ankle dislocation is an orthopedic emergency, and reduction should not be delayed by imaging if there is evidence of neurovascular impairment. Complications that are exacerbated by delay in management include concomitant fractures, gross deformity of the ankle, severe stretching and tenting of the skin with resultant skin blisters, skin necrosis, and possible conversion to a compound fracture.
  - Be sure to check the radiograph carefully for commonly associated fractures notably of the malleoli.

Selected Reading

Collins DN, Temple SD. Open joint injuries: classification and treatment. Clin Orthop. 1989;243:48.

Hamilton WC. Injuries of the ankle and foot. Emerg Med Clin North Am. 1984;2:361.

Kelly PJ, Peterson FP. Compound dislocations of the ankle without fractures. Am J Surg. 1986;103:170.

Simon RR, Sherman SC, Koenigsknecht SJ, editors. Emergency orthopedics—the extremities. 5th ed. New York: McGraw-Hill; 2007. p. 264.

Wedmore IS, Charette J. Emergency department evaluation and treatment of ankle and foot injuries. Emerg Med Clin North Am. 2000;18:85.

Arthrocentesis

106

Shalu S. Patel and Bobby K. Desai

106.1 Indications

- Diagnosis of septic joint
- Diagnosis of traumatic effusion
- Diagnosis of inflammatory effusion
- Diagnosis of crystal-induced arthritis
- Therapeutic relief of pain from effusion

106.2 Contraindications

- Severe coagulopathy
- Skin infection over the needle insertion site
- Joint prosthesis
- Patients with bacteremia or sepsis (except to diagnose a septic joint)

106.3 Materials and Medications

- Betadine (povidone-iodine) or other skin antiseptic
- Sterile gloves
- Sterile towels
- Lidocaine 1 % or 2 % (5 mL) or other anesthetic of choice
- 18- to 22-gauge needle, 25-gauge needle
- Syringes (5 mL, 5–50 mL)
- Sterile gauze (4 × 4)
- Band-aid

106.4 Procedure

1. Informed consent may be required.
2. Position the patient appropriately. The joint should be placed in slight flexion.
3. Palpate the joint and identify anatomical landmarks.
    (a) For knee arthrocentesis, the needle should be inserted at the midpoint of either the medial or the lateral side of the patella (Fig. 106.1).
    (b) For acromioclavicular (AC) joint arthrocentesis, the needle should be inserted at the superior surface of the AC joint (Fig. 106.2).
    (c) For glenohumeral joint arthrocentesis, there are two approaches.
        (i) In the anterior approach, the needle is inserted into the groove lateral to the coracoid process (Fig. 106.3).
        (ii) In the posterior approach (preferred), the needle is inserted below the posterior border of the acromion process and lateral to the border of the scapula (Fig. 106.4).
4. Prepare the skin and drape in a sterile fashion.
5. Using lidocaine (drawn up in 5-mL syringe), anesthetize the skin with the 25-gauge needle.
6. Secure the 18- to 22-gauge needle on the 5- to 50-mL syringe (depending on the size of the joint) and insert it into the skin.
7. Advance the needle slowly into the joint space while aspirating until joint fluid can easily be withdrawn. While inserting the needle into the joint space, avoid scraping the needle against the bone.

S.S. Patel, MD
Department of Emergency Medicine, Florida Hospital Tampa,
Florida Hospital Carrollwood, Tampa, FL, USA

B.K. Desai, MD (✉)
Department of Emergency Medicine, University of Florida Health
Shands Hospita, Gainesville, FL, USA
e-mail: bdesai@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_106

8. If fluid cannot be aspirated easily, the catheter can be repositioned further in the joint space or turned by 45° sequentially as needed.
9. Once the joint fluid is aspirated, pull out the needle and hold pressure with gauze. Bleeding should be minimal.
10. Place a band-aid or other dressing over the site.
11. Send the synovial fluid to the laboratory. Generally, laboratory analyses may include crystals, protein, glucose, cell count and differential, culture and sensitivity, and Gram stain.



Fig. 106.1 Knee arthrocentesis



Fig. 106.2 Acromioclavicular joint arthrocentesis



Fig. 106.3 Glenohumeral joint arthrocentesis: anterior approach



Fig. 106.4 Glenohumeral joint arthrocentesis: posterior approach

106.5 Complications

- Introduction of infection
- Bleeding

106.6 Pearls and Pitfalls

- The preferred site of entry is over the extensor surface of the joint. This will reduce the risk of damage to tendons, ligaments, and blood vessels.
- When assessing synovial fluid, the Rule of Twos may be used to differentiate among normal, inflammatory, and septic fluid. Normal synovial fluid has less than 200 white blood cells (WBCs)/mm^3. Noninflammatory synovial fluid has 200–2000 WBCs/mm^3. Inflammatory synovial fluid has greater than 2000 WBCs/mm^3 (but <50,000 WBCs/mm^3). Septic synovial fluid has greater than 75,000 WBCs/mm^3.
- Only septic synovial fluid will have a positive Gram stain and culture.

Selected Reading

Biundo JJ, Roberts N, Deodhar A. Regional musculoskeletal complaints. In: Stone JH, editor. A clinician's pearls and myths in rheumatology. New York: Springer Science; 2009. p. 433–4.

Parrillo SJ, Fisher J. Arthrocentesis. In: Roberts JR, Hedges J, editors. Clinical procedures in emergency medicine. 4th ed. Philadelphia: Saunders; 2004. p. 1042–57.

Self WH, Wang EE, Vozenilek JA, del Castillo J, Pettineo C, Benedict L. Dynamic emergency medicine. Arthrocentesis. Acad Emerg Med. 2008;15:298.

Thomsen TW, Shen S, Shaffer RW, Setnik GS. Arthrocentesis of the knee. N Engl J Med. 2006;354:e19.

Intra-articular Injection

107

Bharat Kothakota and Muhammad Waseem

107.1 Indications

- Aspiration of fluid (arthrocentesis)
  - For diagnosis: to rule out infection
  - To relieve pressure from large, painful joint effusion
- Injection of joints with inflammatory arthritis
  - Tendinitis
  - Bursitis
  - Rheumatoid arthritis (RA)
- Injection of joints with osteoarthritis (OA)
  - Injection of large weight-bearing joints
  - Injection of small joints of hands
- Intra-articular anesthetic
  - Shoulder reduction
  - Ankle impingement syndrome

107.2 Contraindications

- Cellulitis
- Bacteremia
- Fracture

107.3 Materials and Medications

- Glucocorticoid
  - Duration of effect inversely proportional to solubility
    - Less soluble → longer acting
  - Choice of steroid is the personal preference of the physician
  - Methylprednisone (Depo-Medrol) and triamcinolone acetonide (Kenalog)
    - Less likely to induce postinjection flare
  - Kenalog and triamcinolone hexacetonide (Aristospan)
    - Longest-acting agents
- Local anesthetic
  - 1 % Lidocaine
- Needle
  - 18- to 22-gauge used for knee, ankle, hip, elbow, and shoulder
  - 25-gauge or smaller used for smaller joints (interphalangeal)
- Syringe

B. Kothakota, MD • M. Waseem, MD (✉)
Department of Emergency Medicine, Lincoln Medical and Mental Health Center, New York, NY, USA
e-mail: bharatkothakota@yahoo.com; waseemm2001@hotmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_107

107.4 Procedure

1. Selecting an injection approach.
   - Knee
     - Lateral approach: 1 cm inferior to the patella laterally (Fig. 107.1)
     - Medial approach: 1 cm inferior to the patella medially (Fig. 107.2)
   - Ankle
     - Lateral approach: just inferior to the lateral malleolus (Fig. 107.3)
     - Medial approach
       - Plantar flex the foot.
       - Angle the needle cephalad to pass between the medial malleolus and the tibialis anterior tendon (Fig. 107.4).
   - Shoulder
     - Posterior approach
       - Insert the needle 1 cm inferior and 1 cm medial to the posterolateral corner of the acromion.
       - Direct the needle anterior and medial toward the coracoid process (Fig. 107.5).
2. Skin preparation.
   - Make three separate concentric outward spirals with iodine disinfectant
   - Scrub with cyclohexidine preparation
3. Mark the injection site by impressing the skin with a hard object.
   - Sterile end of needle sheath
   - Ball point pen with tip retracted
4. Local anesthesia.
   - 1 % Lidocaine injected into the skin and subcutaneous tissue
   - Short burst of ethyl chloride spray before iodine preparation
   - Mixing lidocaine with glucocorticoid preparation
5. Always aspirate joint fluid before injecting the corticosteroids.
   - Use a 1.5-inch 18-gauge needle for aspiration.
   - Confirm that the needle is in the joint space.
   - Reduced effusion size before injection can improve outcomes.
   - Compress the opposite side of the joint to aid in aspiration (Fig. 107.6).
6. After aspirating, change the syringe.
   - Use a sterile hemostat or hand to stabilize the needle within the joint space (Fig. 107.7).
   - Avoid injecting corticosteroids if the aspirate appears purulent.
7. Injection of medication.
   - Can use the same needle used for aspiration.
   - Insert needle 0.75–1.25 inch in depth for injection.
8. Remove the needle, wipe the iodine solution clean, and apply the bandage.
9. Postinjection care.
   - First 48 h: bedrest versus minimize walking
   - Next 2–3 weeks: crutches or cane

Fig. 107.1 Knee arthrocentesis, lateral approach


Patella
Relaxed quadriceps tendon


Patella
Thumb stabilizing patella

Fig. 107.2 Knee arthrocentesis, medial approach


Lateral malleolus
Talus
Sinus tarsi

Fig. 107.3 Ankle arthrocentesis, lateral approach


Tibialis anterior
tendon
Tibia
Talus

Fig. 107.4 Ankle arthrocentesis, medial approach


Acromion
Head of
humerus
1cm

Fig. 107.5 Shoulder arthrocentesis, posterior approach



Fig. 107.6 Compress opposite side of joint to aid in aspiration



Fig. 107.7 Use hemostat or hand to stabilize needle within joint space

107.5 Complications

- Local postinjection flare
  - Irritation of the synovium by steroid microcrystals
  - Can be confused for infection
  - Occurs and resolves within 48 h after injection
  - Treat with ice and appropriate analgesics.
- Iatrogenic joint infection
  - Suspect if it begins later than, or lasts longer than, flare
  - Increasing pattern of pain
  - Fever, malaise, redness, or drainage around injection site
  - *Staphylococcus aureus* most common
- Subcutaneous atrophy and depigmentation
  - Leakage of corticosteroids into soft tissues
- Aspiration of blood
  - Indicative of trauma or bleeding disorder (hemophilia)
- Systemic absorption
  - Water-soluble preparations
  - Dose dependent
  - Injection into multiple joints
  - Transient hyperglycemia in diabetic patients
  - Avascular necrosis of the femoral head

107.6 Pearls

- Mixing lidocaine with glucocorticoids
  - Reduces pain caused by injection of steroids into joint space
  - Less likely to cause soft tissue atrophy and tendon rupture
  - Immediate relief from anesthetic indicates proper injection
- Limiting intra-articular glucocorticoid injections per joint
  - OA
    - Four injections per lifetime of the joint
    - Injections reduce the rate of accelerated degeneration in joints
  - RA
    - Limit of one injection per month
    - No evidence of glucocorticoid-induced cartilage loss

Selected Reading

Aponte EM, Schraga ED. Joint reduction, shoulder dislocation, anterior. Available at: http://emedicine.medscape.com/article/109130-overview#a08.

Cianflocco AJ. Intra-articular injections of the knee: a step-by-step guide. J Fam Pract. 2011;60(Suppl):S48–9. Available at: http://www.jfponline.com/pages.asp?id=10062.

Lavelle W, Lavelle ED, Lavelle L. Intra-articular injections. Anesthesiol Clin. 2007;25:835–62.

Molis MA, Young CC. Ankle impingement syndrome. Available at: http://emedicine.medscape.com/article/85311-overview.

Neustadt DH. Intra-articular injections for osteoarthritis of the knee. Cleve Clin J Med. 2006;73:897–911.

Roberts WN. Intraarticular and soft tissue injections: what agents(s) to inject and how frequently? Available at: www.uptodate.com.

Roberts WN. Joint aspiration or injection in adults: techniques and indications. Available at: www.uptodate.com.

Sugar-Tong Splint

108

Katrina John, Jeffrey Kile, and Amish Aghera

108.1 Indications

- Fractures to the wrist or forearm
- To prevent motion at the wrist and elbow
- To prevent supination and pronation

108.2 Contraindications

- Relative
  - Evidence of compartment syndrome or any neurovascular compromise

108.3 Materials (Fig. 108.1)

- Stockinette
- Padding
- Splint material: fiberglass/plaster of Paris or prefabricated splint rolls, 2, 3, 4 inches depending on age and body habitus
- Trauma shears/scissors
- Elastic bandage
- Tape
- Container with water
- Gloves, eyemask, sheet
- Sling

K. John, MBBS • J. Kile, MBBS, PhD, MPH (✉)
Department of Emergency Medicine, Eisenhower Medical Center,
Rancho Mirage, CA, USA
e-mail: trenjohn@me.com; jeffrey.kile@gmail.com

A. Aghera, MD
Department of Emergency Medicine, Maimonides Medical Center,
New York, NY, USA
e-mail: aaghera@maimonidesmed.org

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_108



Fig. 108.1 Equipment

108.4 Procedure

1. Ensure the skin of the affected extremity is clean, dry, and intact.
2. Cover the patient with a sheet or gown to protect the patient's clothing and the surrounding area.
3. Position the patient's arm abducted at 90° at the shoulder and internally rotated with the elbow flexed at 90° (Fig. 108.2).
4. Measure the splinting material by running a single layer from the metacarpal heads of the dorsum of the hand along the extensor surface of the forearm over the elbow and humeral condyles and back down the flexor surface of the forearm to the palmar aspect of the hand to the metacarpal heads.
5. If using non-prefabricated splint rolls, lay the measured piece of splinting material out on a flat surface and multiply the layers to the same length, 6–8 layers for fiberglass and 10–12 layers for plaster.
6. Measure the stockinette from the finger tips to the midhumerus and cut a hole for the thumb.
7. Place the stockinette on the arm (Fig. 108.3).
8. Use a 3- to 4-inch padding roll to apply several layers of circumferential padding extending from the metacarpal heads to the midhumerus below the level of the stockinette (Fig. 108.4).
9. Wet the already prepared and measured splinting material and remove the excess water.
10. Ensure the forearm is in the aforementioned position, and apply the splinting material from the metacarpal heads of the dorsum of the hand along the extensor surface of the forearm over the elbow and humeral condyles and back down the flexor surface of the forearm to the palmar aspect of the hand to the metacarpal heads (Fig. 108.5).
11. Fold each end of the stockinette down over the padding and splinting material.
12. An extra layer of padding can be added at this stage.
13. Secure the entire splint with two elastic bandages/ace wrap and apply tape to ensure the bandages stay in place (Fig. 108.6).
14. Place the arm in a sling.



Fig. 108.2 Arm positioning



Fig. 108.3 Fiberglass being measured and stockinette on patient



Fig. 108.4 (**a**) Application of padding over the stockinette (partial), (**b**) Application of padding over the stockinette (complete)



Fig. 108.5 (**a**) Application of splinting material over padding (anteromedial view), (**b**) Application of splinting material over padding (anterolateral view)



Fig. 108.6 Application of elastic bandage over splinting material

108.5 Complications

- Compartment syndrome

108.6 Pearls and Pitfalls

- Pearls
  - This procedure is best done with an assistant to hold the extremity in the desired position and to prevent the splint slipping as it is secured.
  - Having the patient in the illustrated position enables the practitioner to use gravity to hold the splint in the correct position while securing it; especially helpful if an assistant is not available.
- Pitfalls
  - If the splint is too short, it fails to immobilize the wrist.
  - If the splint is too long, it will cause reduced motion and stiffness at the metacarpophalangeal joints and swelling of the fingers due to immobility.

Selected Reading

Bong MR, Egol KA, Leibman M, Koval KJ. A comparison of immediate postreduction splinting constructs for controlling initial displacement of fractures of the distal radius: a prospective randomized study of long-arm versus short-arm splinting. J Hand Surg Am. 2006;31:766–70.

Denes AE, Goding R, Tamborlane J, Schwartz E. Maintenance of reduction of pediatric distal radius fractures with a sugar-tong splint. Am J Orthop (Belle Mead NJ). 2007;36:68–70.

Gartland JJ. The sugar tong splint. Am J Orthop. 1963;5:131.

McGeorge DD, Stilwell JH. The sugar tong splint: a reliable method of arm splintage in the child. J Hand Surg Br. 1989;14:357.

Simon RR, Koenigsknecht SJ, editors. Emergency orthopedics—the extremities. 3rd ed. New York: McGraw Hill; 1995.

Part XIV

Obstetric Procedures

Fetal Heart Rate Monitoring

109

Nathaniel Lisenbee and Joseph A. Tyndall

109.1 Indications

- Fetal heart rate (FHR) monitoring is important because it provides basic patterns that can be correlated to the acid–base status, circulatory volume, and oxygenation status of the fetus through brainstem detection and subsequent cardiac response. It has numerous indications during the antepartum and intrapartum stages [1].
- Antepartum indications include:
  - Nonstress test (consists of monitoring FHR in conjunction with fetal movements)
  - Contraction stress test (consists of monitoring FHR during contractions, which are induced pharmacologically)
  - Biophysical profile (BPP; consists of a nonstress test with an additional ultrasound)
- Intrapartum indications include monitoring FHR during:
  - Uterine contractions
  - Pain medications/anesthetic administration to the mother during labor
  - Procedures performed during labor
  - Second stage of labor
  - High-risk pregnancies, which can be defined by a number of conditions including [2, 3]:
    - Maternal diabetes, asthma, preeclampsia/eclampsia
    - Multiple gestations
    - Intrauterine growth restriction
    - Premature rupture of membranes
    - Lack of prenatal care

109.2 Contraindications

- Contraindications for internal FHR monitoring
  - Presence of placenta previa
  - Lack of ability to identify the portion of the fetal body where device application is being considered
  - Active herpes, active hepatitis, or human immunodeficiency virus (HIV) in the mother
- Contraindications for external FHR monitoring
  - None

109.3 Methods

- Two methods for FHR monitoring:
  - Auscultation monitoring
    - Defined as auscultating FHR every 15 min in the first stage of labor and auscultating every 5 min in the second stage
    - Does not provide strips with information on FHR variability or the shape of FHR accelerations and decelerations
- Electronic FHR monitoring
  - Allows for real-time continuous monitoring of FHR activity
  - Provides strips with information on FHR variability or the shape of FHR accelerations and decelerations
  - Can be performed by Doppler ultrasound or internal fetal electrocardiography (ECG)

When comparing the two methods for electronic FHR monitoring, both are equally as reliable in most settings. Thus, external monitoring is the preferred method because it is noninvasive. However, in instances in which external monitoring becomes difficult owing to poor quality or technical difficulties, invasive monitoring is indicated.

N. Lisenbee, MD
U. S. Air Force Medical Center Keesler,
Biloxi, MI, USA
e-mail: nate4085@ufl.edu

J.A. Tyndall, MD, MPH (✉)
Department of Emergency Medicine, University of Florida Health,
Gainesville, FL, USA
e-mail: tyndall@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_109

109.4 Equipment and Procedures

Multiple methods exist for electronic FHR monitoring [4]. The most commonly used are external monitoring by Doppler ultrasound and internal monitoring by fetal ECG.

109.4.1 Doppler Ultrasound is a Noninvasive Method to Monitor FHR (Fig. 109.1)

- Equipment
  - Electronic FHR monitor
  - Contraction monitor sensor with belt
  - FHR sensor with belt (consists of ultrasound transducer and ultrasound sensor)
  - Ultrasound coupling gel
- Procedure
  1. Place the patient in a supine position.
  2. Palpate the fetal anatomy through the maternal abdomen to find the approximate location of the fetal heart.
  3. Place ultrasound coupling gel on the maternal abdomen at the sight of suspected fetal cardiac activity.
  4. Place the transducer probe on gel and locate the fetal heart tones.
  5. Once the fetal heart tones are located, secure the FHR sensor to the maternal abdomen with the attached belt.
  6. Place the contraction monitor sensor near the fundus in order to monitor uterine contractions.
  7. Attach the FHR sensor and contraction monitor to the electronic FHR monitor to obtain printouts of FHR and uterine contractions.



Fig. 109.1 External fetal heart rate monitoring

109.4.2 Internal Fetal ECG is an Invasive Method to Monitor FHR and is Used Only in the Intrapartum Period (Fig. 109.2)

- Equipment
  - Fetal scalp monitoring electrode
  - Leg plate electrode
  - Sterile vaginal lubricant
  - Electronic FHR monitor
- Procedure (Fig. 109.3)
  1. Place the patient in a dorsal lithotomy position.
  2. Sterilize the perineal area.
  3. Perform a bimanual vaginal examination to identify the presenting fetal head. (Note: rupture of membranes must occur before scalp electrode placement.)
  4. Place the spiral electrode guide tube on the fetal scalp and advance the electrode until it contacts the scalp.
  5. Rotate the drive tube clockwise approximately one rotation while maintaining pressure on the guide tube and drive tube.
  6. Release the electrode locking device by pressing together the arms on the drive tube grip.
  7. Carefully slide the drive and guide tubes off the electrode wires while holding the locking device open.
  8. Attach the leg plate to the inner thigh of the mother as a means to eliminate electrical interference.
  9. Attach the spiral electrode wires to the color-coded leg plate, which is then connected to the electronic fetal monitor.
  10. Do not forget to sterilize the area of electrode placement after delivery is completed and the scalp electrode is removed.

When comparing the two methods, both are equally reliable in most settings. Thus, external monitoring is the preferred method because it is noninvasive. However, in instances in which external monitoring becomes difficult owing to poor quality or technical difficulties, invasive monitoring is indicated.



Fig. 109.2 Internal fetal heart rate monitoring



Fig. 109.3 Internal fetal heart rate monitoring

109.5 Complications

- Complications of external FHR monitoring
  - Confusing maternal aortic pulsations with FHR
  - Inability to locate FHR
- Complications of internal FHR monitoring
  - Fetal or maternal hemorrhage, fetal infection (usually scalp abscess at the site of insertion)
  - Uterine perforation
  - Subsequent fetal infection due to the invasive nature of the procedure

References

1. Hobel CJ. Intrapartum clinical assessment of fetal distress. Am J Obstet Gynecol. 1971;110:336–42.
2. Byrd JE. Intrapartum electronic fetal heart rate monitoring (EFM) and amnioinfusion. In: Advanced life support in obstetrics course syllabus. Kansas City: American Academy of Family Physicians; 1996. p. 97–106.
3. Queenan JT, Hobbins JC, Spong CY. Protocols for high-risk pregnancies. New York: Wiley; 2010. Retrieved 16 Jan 2012, from http://lib.myilibrary.com?ID=268955.
4. External and internal heart rate monitoring of the fetus. New Haven: Yale Medical Group; 2012. Retrieved from http://www.yalemedicalgroup.org/stw/.

Selected Reading

Alfirevic Z, Devane D, Gyte GM. Continuous cardiotocography (CTG) as a form of electronic fetal monitoring (EFM) for fetal assessment during labour. Cochrane Database Syst Rev. 2006;(3):CD006066.

American College of Obstetricians and Gynecologists. Fetal heart rate patterns: monitoring, interpretation, and management, ACOG technical bulletin, vol. 207. Washington, DC: ACOG; 1995.

Cunningham FG, Leveno KJ, Bloom SL, Hauth JC, Rouse DJ, Spong CY. Chapter 18: Intrapartum assessment. In: Williams obstetrics. 23rd ed. New York: McGraw Hill; 2010.

Freeman RK. Problems with intrapartum fetal heart rate monitoring interpretation and patient management. Obstet Gynecol. 2002;100:813.

Gomella LG, Haist SA. Chapter 13: Bedside procedures. In: Clinician's pocket reference. 11th ed. Columbus: McGraw-Hill; 2007.

Sweha A, Hacker TW, Nuovo J. Interpretation of the electronic fetal heart rate during labor. Am Fam Physician. 1999;59:2487–500.

Ultrasonography for Ectopic Pregnancy

110

L. Connor Nickels

An ectopic pregnancy is a pregnancy occurring outside of the uterine cavity (fundus) (Fig. 110.1).



Interstitial
Tubal (isthmus)
Tubal (ampullar)
Infundibular (ostial)
Ovarian
Peritoneal
Cervical
Abdominal

Fig. 110.1 Ectopic pregnancy diagram: pregnancy occurring outside of the uterine cavity

---

L.C. Nickels, MD, RDMS
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: cnickels@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_110

110.1 Indications

- Patient in the first trimester of pregnancy with any combination of the following:
  - Vaginal bleeding.
  - Acute pelvic pain.
  - Hypotension or shock.
  - Dizziness or syncope.
  - Positive pregnancy test.
  - Adnexal mass.
  - Cervical tenderness.
  - Abnormal rise in the serum human chorionic gonadotropin (hCG).
  - No specific sign or symptom is absolute; therefore, the index of suspicion must be high.
- Risk factors for ectopic pregnancy
  - Pelvic inflammatory disease (PID)
  - Previous or current intrauterine device
  - Infertility treatment
  - Previous tubal surgery
  - Tubal ligation
  - Advanced maternal age
  - Previous ectopic pregnancy
- Usually a sonographic diagnosis
- Sonographic signs of an ectopic can include any of the following:
  - Gestational sac seen in one of the following:
    - Adnexa with any of the following:
      - Yolk sac (Figs. 110.2 and 110.3)
      - Fetal pole with or without cardiac activity
      - Both of these
    - Low position in the cervix (cervical ectopic)
    - Seemingly in the uterus, but off to one side and with minimal surrounding myometrium (interstitial ectopic)
    - Within the peritoneal cavity, outside of the tubes (abdominal ectopic)
  - Pseudogestational sac seen in the uterus
    - Uterine enlargement or decidual reaction (single outline only) in the endometrium without a gestational sac
  - Other unidentifiable adnexa mass
  - Free fluid in the pelvis or other gravity-dependent area (i.e., Morison's pouch in the right upper quadrant in a supine or reverse Trendelenburg patient) (Fig. 110.4)
    - Small free fluid: tracks less than one third of the posterior cul-de-sac
    - Moderate free fluid: tracks less than two third of the posterior cul-de-sac
    - Large free fluid: tracks greater than two third of the posterior cul-de-sac
    - Right upper quadrant free fluid: 100 % predictability for ectopic
  - Empty uterus with serum hCG >1000 mIU/mL
- Patient in the first trimester of pregnancy with a serum hCG at or above the discriminatory zone (i.e., 1000 mIU/mL) without a sonographically normal gestational sac visualized within the uterus has an ectopic pregnancy until proven otherwise and should have an obstetrics consult in the emergency department.
  - Discriminatory zone may differ depending on the reference, but typically serum hCG between 1000 and 2000 mIU/mL.
  - For this chapter, we have used serum hCG greater than 1000 mIU/mL [1].
- Yolk sac should be first sign of definitive intrauterine pregnancy for emergency physicians because the decidual reaction and gestational sac are not 100 % accurate.
- May be treated surgically or medically depending on findings.
  - Decision to be made by obstetrics consultant


2011Apr23 22:47
Gen THI
S MB
OB
C60
96%
MI
0.7
TIB
0.1
128
Uterus
15
Cine

Fig. 110.2 Transabdominal transverse image of the uterus shows an ectopic pregnancy in the left adnexa (red circle) with the yolk sac present (Photo courtesy of L. Connor Nickels, MD, RDMS)


Gen
S MB
OB
ICT
100%
MI
0.4
TIB
0.1
169
Uterus
Free
Fluid
YS
Ovary
8.3

Fig. 110.3 Transvaginal sagittal image of an empty uterus with an ectopic pregnancy (in red circle) noted just posterior in the adnexa, adjacent to the ovary. The gestational sac contains a yolk sac and there is free fluid surrounding the ectopic, concerning for rupture (Photo courtesy of L. Connor Nickels, MD, RDMS). YS–yolk sac


Gen
S MB
OB
ICT
31%
MI
0.5
TIB
0.1
20
Uterus
Free
Fluid
6.5
Cine

Fig. 110.4 Transvaginal sagittal image of an empty uterus and large free fluid in the posterior cul-de-sac in a patient with a presumed ectopic pregnancy (Photo courtesy of L. Connor Nickels, MD, RDMS)

110.2 Contraindications

- Treating ectopic pregnancy medically when there is a fetal pole with fetal cardiac activity present
- Failing to consult obstetrics/gynecology when the patient has a serum hCG above the discriminatory zone and no sonographic findings to diagnose intrauterine pregnancy

110.3 Materials and Medications

- Ultrasound machine
- Probes: transabdominal and transvaginal
- Gel
- Skilled ultrasound operator
- Endocavitary probe covers
- Pelvic setup (speculum and cultures)
- Cardiac monitor, two large-bore intravenous needles
- Laboratory work: serum quantitative hCG, hemoglobin, group and Rh, type and screen
  - May add additional laboratory tests depending on the stability and symptoms of the patient

110.4 Procedure

- Ultrasound machine in obstetrics preset
- Transabdominal
  1. Place the patient in the supine position.
  2. Ideally, the bladder will be full for a good acoustic window.
  3. Using a curvilinear probe, 3.5–5.0 MHz.
  4. Begin scanning the patient in a sagittal position to identify the uterus as it lies in position with the bladder. Scan through the uterus completely in this plane, looking for signs of intrauterine pregnancy.
  5. Imaging in the transverse plane should be done in the same fashion.
  6. Any signs of an intrauterine pregnancy should be clearly identified and measured.
     - Gestational sac diameter
     - Yolk sac diameter
     - Fetal pole with crown rump diameter
       - If present, fetal cardiac activity should be recorded by using M mode to obtain a tracing and measure the fetal heart rate.
  7. Although sometimes limited transabdominally, an attempt to identify the adnexa should be performed in both planes bilaterally.
  8. Any abnormalities identified should be noted.
     - Free fluid surrounding the uterus (anterior or posterior cul-de-sac) or ovaries
     - On pelvic imaging or FAST examination
     - Intrauterine contents not consistent with an intrauterine pregnancy and/or not clearly, centrally visualized within the fundus of the uterus
     - Masses or contained fluid collections outside the uterus
     - Yolk sac or fetal pole with or without fetal cardiac activity seen outside the uterus
  9. Transvaginal scanning should be performed if a definitive intrauterine pregnancy is not identified on transabdominal imaging.
- Transvaginal
  1. Place the patient in the lithotomy position.
  2. Bladder is preferably empty.
  3. Use a transvaginal probe, 5–7.5 MHz.
  4. Repeat same steps as transabdominal imaging previously.
- The procedure is the same for all pelvic ultrasounds including transabdominal and transvaginal imaging because this should be performed in a systematic fashion so as to not miss pertinent findings. Therefore, the findings may change, but the examination remains the same.
- Yolk sac should be first sign of definitive intrauterine pregnancy for emergency physicians because the decidual reaction and gestational sac are not 100 % accurate.

110.5 Complications

- Bleeding: internal and/or external
- Maternal death if ectopic ruptures
  - Nine percent of pregnancy-related deaths
  - Leading cause of maternal death in the first trimester
- Sterility if tube(s) are damaged or surgically removed

110.6 Pearls and Pitfalls

- Pearls
  - Following the algorithm despite the patient being asymptomatic can help avoid missed ectopic pregnancies.
  - Cervical ectopic pregnancy can be difficult to distinguish from a spontaneous abortion. If the patient is aborting, the ultrasound findings should change quickly and the patient should have vaginal bleeding.
  - Double decidual reaction versus pseudogestational sac can be a very subtle distinction and should not be made by emergency physicians; hence, the statement made earlier, requiring a yolk sac as the earliest definitive sign of an intrauterine pregnancy.

  - Fibroids, bicornuate uterus, and eccentrically located normal pregnancy can all appear similar to a cornual pregnancy.
  - The majority of times when the patient is pregnant, has an empty uterus on sonographic imaging, and has vaginal bleeding, the final diagnosis is still unknown because it could still be an early normal pregnancy or an ectopic pregnancy.
- Pitfalls
  - Failing to obtain a pregnancy test in all reproductive-age women who have not undergone a hysterectomy
  - Failing to identify subtle signs of ectopic pregnancies

Reference

1. Ma OJ, Mateer JR, Blaivas M, editors. Emergency ultrasound. 2nd ed. New York: McGraw-Hill Professional; 2007.

Selected Reading

Gabbe SG, Niebyl JR, Galan HL, et al., editors. Obstetrics: normal and problem pregnancies. 5th ed. Philadelphia: Churchill Livingstone; 2007.

Marx J, Hockberger R, Walls R, editors. Rosen's emergency medicine: concepts and clinical practice. 7th ed. Philadelphia: Mosby; 2010.

Sanders RC, Winter T, editors. Clinical sonography: a practical guide. 4th ed. Philadelphia: Lippincott Williams & Wilkins; 2007.

Stead LG, Behera SR. Ectopic pregnancy. J Emerg Med. 2007;32(2):205–6.

Ultrasonography for Hydatidiform Mole

111

L. Connor Nickels

Definition: molar pregnancy = hydatidiform mole = anomalous growth of trophoblastic tissue

- Complete: 46,XX or 46,XY
  - Completely paternal in origin
  - Contains no fetal tissue
  - Most recognizable by clinical symptoms
- Incomplete (partial mole): 69,XXX or 69,XXY
  - Maternal and paternal in origin
  - Contains fetal tissue
  - More subtle clinical presentation

111.1 Indications

- Clinical presentation of any combination of the following:
  - Vaginal bleeding
  - With or without vomiting, persistent hyperemesis gravidarum
  - High blood pressure
  - Uterine size large for dates
- Serum human chorionic gonadotropin (hCG) very elevated (more than would be consistent for dates)
  - Usually greater than 100,000 mIU/mL

111.2 Contraindications

- Conservative management

111.3 Materials and Medications

- Ultrasound machine
- Probes: curvilinear (abdominal) and endocavitary (transvaginal)
- Gel
- Skilled ultrasound operator
- Endocavitary probe covers
- Pelvic setup (speculum and cultures)
- Lab work: serum quantitative hCG, hemoglobin, group and Rh
  - May add additional laboratory tests depending on the stability and symptoms of the patient

111.4 Procedure

- Ultrasound machine in obstetrics preset
- Transabdominal imaging
  1. Place the patient in the supine position.
  2. Ideally the bladder will be full for a good acoustic window.
  3. Using a curvilinear probe, 3.5–5.0 MHz, begin scanning the patient in a sagittal position to identify the uterus as it lies in position with the bladder. Scan through the uterus completely in this plane, looking for signs of intrauterine pregnancy.
  4. Rotate the probe to a transverse position (counterclockwise), with the probe indicator toward the patient's right. Scan through the uterus completely in this plane, looking for signs of intrauterine pregnancy.
  5. Any signs of an intrauterine pregnancy should be clearly identified and measured.
  6. Sonographic findings of a molar pregnancy include:
     - Uterus filled with heterogeneous material.
       - Echogenic material interspersed with anechoic areas known as the "snowstorm" is the most common appearance of a mole (Fig. 111.1).

L.C. Nickels, MD, RDMS
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: cnickels@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_111

    - Can be confused with missed abortion or fibroid, underscoring the importance of the serum hCG because this will be markedly elevated, which would make the alternative diagnoses less likely.
  - Theca lutein cysts are present in the adnexa.
    - Multiple cysts that occur with trophoblastic disease, multiple pregnancies (e.g., twins, triplets, quadruplets), and induced ovulation.

7. Although sometimes limited transabdominally, an attempt to identify the adnexa should be performed in both planes bilaterally.
8. Any abnormalities should be noted.
9. Transvaginal scanning should be performed if a definitive intrauterine pregnancy is not identified on transabdominal imaging.

- Transvaginal imaging
  1. Place the patient in the lithotomy position.
  2. Bladder is preferably empty.
  3. Use an endocavitary probe, 5–7.5 MHz.
  4. Repeat the same steps as for transabdominal imaging previously discussed (#2).
  5. After scanning through the uterus in sagittal and transverse planes, the adnexa should be scanned in the same format bilaterally, looking for any abnormalities, as mentioned previously.
  6. Again, any abnormalities should be noted:
     - Free fluid surrounding the uterus (anterior or posterior cul-de-sac) and/or ovaries
     - Masses or contained fluid collections outside the uterus
     - Yolk sac or fetal pole with or without fetal cardiac activity seen outside the uterus
- The procedure is the same for all pelvic ultrasounds, transabdominal and transvaginal imaging, because this should be performed in a systematic fashion so as to not miss pertinent findings. Therefore, the findings may change, but the examination remains the same.
- Yolk sac should be the first sign of definitive intrauterine pregnancy for emergency physicians because the decidual reaction and gestational sac are not 100 % accurate.



Fig. 111.1 Uterus with "cluster of grapes" represents a molar pregnancy (With kind permission from Springer Science+Business Media: Swisher E, Greer B, Montz FJ, Stenchever M. Chapter 14. In: *Atlas of Clinical Gynecology*. Vol. 4. 2002)

111.5 Complications

- Multiple complications can occur and include the following:
  - Invasive mole: when a hydatidiform mole recurs after a dilation and curettage and, subsequently, invades the muscle of the uterus.
    - Molar tissue is extremely vascular and necessitates an ultrasound with color flow to visualize any residual invasive tissue.
  - Choriocarcinoma: molar tissue develops into an aggressive malignancy, metastasizing early throughout the body.
    - In this scenario, the tumor takes on a very cystic appearance with an echogenic rim. When this is seen, one should attempt to view the liver as well for heterogeneous appearance consistent with metastasis or consider other imaging tests (more comprehensive ultrasound, computed tomography, or magnetic resonance imaging) as indicated to further assess concerns for malignancy.
    - Extremely sensitive to chemotherapy, but most favorable results are seen when diagnosed and treated early.

111.6 Pearls and Pitfalls

- Pearls
  - An obstetrics consult must be obtained in the emergency department when this diagnosis is made.
    - Patient must have a dilation and curettage to evacuate the mole.
    - Serum hCG must be followed to less than detectable levels because they have a high rate of recurrence (invasive mole) and potential for malignancy (choriocarcinoma).
  - May occur with intrauterine or ectopic pregnancies or after spontaneous abortions or full-term pregnancies
  - Qualitative and quantitative β-hCG results may be falsely negative in the setting of a molar pregnancy secondary to the "high-dose hook effect" found in sandwich immunoassays in which there is an overabundance of antigen. This error can be corrected by diluting the urine or serum sample and repeating the test.
- Pitfalls
  - Many pitfalls with potentially life-threatening consequences surround this diagnosis. Meticulous observation of the entire picture, including clinical presentation, laboratory results, and ultrasound findings, will help to avoid these outcomes.

Selected Reading

Gabbe SG, Niebyl JR, Galan HL, et al., editors. Obstetrics: normal and problem pregnancies. 5th ed. New York: Churchill Livingstone; 2007.

Hunter CL, Ladde J. Molar pregnancy with false negative â-hCG urine in the emergency department. West J Emerg Med. 2011;12:213–5.

Lentz GM, Lobo RA, Gershenson DM, et al., editors. Comprehensive gynecology. 6th ed. Philadelphia: Mosby; 2012.

Ma OJ, Mateer JR, Blaivas M. Emergency ultrasound. 2nd ed. New York: McGraw Hill Professional; 2008.

Sanders RC, Winter T, editors. Clinical sonography: a practical guide. 4th ed. Philadelphia: Lippincott Williams & Wilkins; 2007.

112

Ultrasonography for Blighted Ovum (Anembryonic Gestation)

Katrina Skoog Nguyen and L. Connor Nickels

112.1 Indications

- A blighted ovum or anembryonic gestation is a pregnancy in which the embryo never develops in the gestational sac (Fig. 112.1).
- Presents as first-trimester vaginal bleeding and/or pelvic pain or cramping
- Criteria for defining an anembryonic pregnancy:
  - Based, in part, on mean gestational diameter (MGD), which is an average of three orthogonal measurements of the gestational sac
    - MGD greater than or equal to 25mm with no embryo
    - 5 MHz or less
      - MGD greater than or equal to 20 mm without a yolk sac
  - May have abnormally low sac position
- References differ in their measurements depending on the approach, transabdominal versus transvaginal, and the frequency of the probe (e.g., 5 MHz vs. 6.5 MHz or greater).



Fig. 112.1 Low-lying empty gestational sac consistent with blighted ovum (Photo courtesy of L. Connor Nickels, MD, RDMS)

K.S. Nguyen, DO • L.C. Nickels, MD, RDMS (✉)
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: katrinaskoog@hotmail.com; cnickels@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_112

112.2 Contraindications

- Misinterpreting images as blighted ovum when any of the following could potentially be present:
  - Early intrauterine pregnancy
  - Pseudogestational sac
  - Molar pregnancy
- Discussions with the patient should always involve an obstetrics consult or referral for definitive decisions and treatment.

112.3 Materials and Medications

- Ultrasound machine
- Probes: transabdominal and transvaginal
- Ultrasound gel
- Endocavitary probe covers
- Skilled ultrasound operator
- Laboratory tests: serum quantitative human chorionic gonadotropin (hCG), hemoglobin, group, and Rh
  - May add additional laboratory tests depending on the stability and symptoms of the patient

112.4 Procedure

- Ultrasound machine in obstetrics preset
- Transabdominal
  1. Place the patient in the supine position.
  2. Ideally the bladder will be full for a good acoustic window.
  3. Use a curvilinear probe, 3.5–5.0 MHz.
  4. Begin scanning the patient in a sagittal position to identify the uterus as it lies in position with the bladder. Scan through the uterus completely in this plane, looking for signs of intrauterine pregnancy.
  5. Imaging in the transverse plane should be done in the same fashion.
  6. Any signs of an intrauterine pregnancy should be clearly identified and measured.
     - In this case, gestational sac and any other intrauterine contents
  7. Although sometimes limited transabdominally, an attempt to identify the adnexa should be performed in both planes bilaterally.
  8. Any abnormalities should be noted.
     - Free fluid surrounding the uterus (anterior or posterior cul-de-sac) or ovaries
     - Masses or contained fluid collections outside the uterus
     - Yolk sac or fetal pole with or without fetal cardiac activity seen outside the uterus
  9. Transvaginal scanning should be performed if a definitive intrauterine pregnancy is not identified on transabdominal imaging.
- Transvaginal
  1. Place the patient in the lithotomy position.
  2. Bladder is preferably empty.
  3. Use a transvaginal probe, 5–7.5 MHz.
  4. Repeat the same steps as for transabdominal imaging previously discussed (#2).
- The procedure is the same for all pelvic ultrasounds including transabdominal and transvaginal imaging because this should be performed in a systematic fashion so as to not miss pertinent findings. Therefore, the findings may change, but the examination remains the same.
- Yolk sac should be first sign of definitive intrauterine pregnancy for emergency physicians because the decidual reaction and gestational sac are not 100 % accurate.

112.5 Complications

- Bleeding
- Retained products of conception

112.6 Pearls and Pitfalls

- Pearls
  - See “Contraindications.” If following an algorithm, a blighted ovum would fall into indeterminate category and obstetrics consult is recommended in the emergency department.
- Pitfalls
  - It is imperative to inform all pregnant patients that obstetrical ultrasonography performed by emergency physicians is limited and not used to detect fetal health and/or anatomy.

Selected Reading

Cosby K, Kendall J, editors. Practical guide to emergency ultrasound. Philadelphia: Lippincott Williams & Wilkins; 2006.

Doubilet PM, Benson CB, Bourne T, Blaivas M. Diagnostic criteria for nonviable pregnancy early in the first trimester. N Engl J Med. 2013;369(15):1443–51.

Ma OJ, Mateer JR, Blaivas M, editors. Emergency ultrasound. 2nd ed. New York: McGraw Hill Professional; 2007.

Morin L, Van den Hof MC. Ultrasound evaluation of first trimester pregnancy complications. J Obstet Gynaecol Can. 2005;161:581–5.

Sanders RC, Winter T, editors. Clinical sonography: a practical guide. 4th ed. Philadelphia: Lippincott Williams & Wilkins; 2007.

Shah K, Mason C, editors. Essential emergency procedures. Philadelphia: Lippincott Williams & Wilkins; 2008.

Ultrasonography for Threatened, Incomplete, or Compete Abortion

113

L. Connor Nickels and Giuliano De Portu

Key Points

Threatened abortion: closed os, no passage of products of conception (POC).

Inevitable abortion: open os, no POC.

Incomplete abortion: open os, passage of POC.

Complete abortion: closed os, empty uterus (all POC passed).

Missed abortion: fetus has died and the uterus has failed to enlarge any further.

113.1 Indications

- Vaginal bleeding in the setting of early intrauterine pregnancy

113.2 Contraindications

- There are no contraindications to ultrasonography.

113.3 Materials and Medications

- Ultrasound machine
- Probes: curvilinear (transabdominal) and endocavitary (transvaginal)
- Gel
- Endocavitary probe covers
- Towels
- Skilled ultrasound operator
- Pelvic setup (speculum and cultures)
- Cardiac monitor and intravenous access if bleeding is significant
- Laboratory tests: serum human chorionic gonadotropin (hCG), hemoglobin, group and Rh, type, and screen

113.4 Procedure

The procedure is the same for all pelvic ultrasounds including transabdominal and transvaginal imaging because this should be performed in a systematic fashion so as to not miss pertinent findings. Therefore, the findings may change, but the examination remains the same.

1. Place the patient in the supine position.
2. Ultrasound machine in obstetrics preset with abdominal probe and gel.
3. Begin scanning the patient in a transabdominal sagittal plane to identify the uterus as it lies in position with the bladder. Scan through the uterus completely in this plane looking for signs of intrauterine pregnancy (gestational sac, yolk sac, fetal pole, fetal cardiac activity).
    - For our purposes as emergency physicians, a yolk sac (at the least) must be seen within the uterus to definitively report an intrauterine pregnancy (Fig. 113.1). The decidual reaction and/or presence of gestational sac is not 100 % accurate.
4. Transabdominal imaging in the transverse plane should be done in the same fashion.
5. If an intrauterine pregnancy is clearly identified on transabdominal scanning, appropriate measurements can be taken to estimate dates:
    - Gestational sac diameter.
    - Yolk sac diameter or crown rump length (CRL).
    - If present, fetal cardiac activity should be recorded by using M mode to obtain a tracing and measure the fetal heart rate (Fig. 113.2).
6. For a complete examination, the adnexa should be scanned in an attempt to identify the ovaries bilaterally.
7. Any abnormalities identified should be noted:
    - Free fluid surrounding the uterus (anterior or posterior cul-de-sac) or ovaries
        - On pelvic imaging or focused assessment with sonography in trauma (FAST) examination

L.C. Nickels, MD, RDMS (✉) • G. De Portu, MD
Department of Emergency Medicine, University of Florida Health Shands Hospital, Gainesville, FL, USA
e-mail: cnickels@ufl.edu; gdeportu@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_113

- Intrauterine contents not consistent with an intrauterine pregnancy and/or not clearly, centrally visualized within the fundus of the uterus
- Any masses or contained fluid collections noted outside the uterus
- Yolk sac or fetal pole with or without fetal cardiac activity seen outside the uterus

8. Transvaginal scanning with the endocavitary probe should be performed if a definitive intrauterine pregnancy is not identified on transabdominal imaging.
9. Transvaginal imaging is performed in the sagittal and transverse planes to identify an intrauterine pregnancy, with bladder preferably empty.
10. Measurements should be taken of any intrauterine findings.
    - Same as #5.
    - CRL >7 mm on transvaginal ultrasound should have fetal cardiac activity.
11. Each adnexa should be scanned in the sagittal and transverse planes.
12. Any abnormalities identified should be noted.
    - Same as #7.
13. The uterus will be empty in the case of a complete abortion (Figs. 113.3 and 113.4).



Fig. 113.1 Yolk sac present within the gestational sac with double decidual reaction (With kind permission from Springer Science+Business Media: Buja LM, Chandrasekhar C. Chapter 7: pathology of the breast and female genital tract. In: Krueger GRF, Buja LM, eds. *Atlas of Anatomic Pathology with Imaging*. 2013)



Fig. 113.2 Fetal cardiac activity recorded using M mode to obtain a tracing and measure the fetal heart rate (With kind permission from Springer Science+Business Media: Hanprasertpong T, Phupong V. First trimester embryonic/fetal heart rate in normal pregnant women. *Archives of Gynecology and Obstetrics*. 2006;274(5))



Fig. 113.3 Transvaginal sagittal image of an empty uterus (Photo courtesy of L. Connor Nickels, MD, RDMS)



Fig. 113.4 Transvaginal transverse image of an empty uterus (Photo courtesy of L. Connor Nickels, MD, RDMS)

113.5 Complications

- Vaginal bleeding
- Miscarriage
- Rh isoimmunization

113.6 Pearls and Pitfalls

- Pearls
  - Threatened abortion:
    - Threatened abortion is not visible sonographically. It is the presumed diagnosis when a patient presents with vaginal bleeding in the first 20 weeks of pregnancy, an intrauterine pregnancy is found with dates corresponding to the patient's dates, and the cervix is closed.
    - Fetal cardiac activity suggests a better prognosis than those without.
    - Fetal heart rate less than 120 bpm suggests impending fetal death (only 6 % survival).
  - Completed abortion:
    - There are only three scenarios in which this diagnosis can confidently be made in the emergency department:
      1. Intact gestation is passed and identified in the emergency room.
      2. Ultrasound shows an empty uterus in the setting of a prior known intrauterine pregnancy.
         - Small internal echoes within the uterus may represent blood rather than retained products of conception, but this determination should be made in consultation with obstetrics.
      3. Negative pregnancy test result in the setting of a prior known intrauterine pregnancy.
    - In all other cases, the quantitative β-hCG must be followed until it is less than 2 mIU/mL.
- Pitfalls
  - Treating threatened abortion as fetal demise or abortion – many of these pregnancies actually go on to completion with a normal fetus.
  - If there is any concern for alternative diagnoses in any of the abortion types (i.e., ectopic gestation), obstetrics consult should be obtained.
  - Failing to order a quantitative serum hCG to rule out other possibilities (e.g., molar pregnancy) and to ensure that it is trending downward (if others to compare).
  - Failing to establish follow-up for an incomplete abortion to ensure appropriate management. The patient may eventually require a dilation and curettage if products do not pass naturally.

Selected Reading

Doubilet PM, Benson CB, Bourne T, Blaivas M. Diagnostic criteria for nonviable pregnancy early in the first trimester. N Engl J Med. 2013;369(15):1443–51.

Gabbe SG, Niebyl JR, Galan HL, et al., editors. Obstetrics: normal and problem pregnancies. 5th ed. Orlando: Churchill Livingstone; 2007.

Ma OJ, Mateer JR, Blaivas M, editors. Emergency ultrasound. 2nd ed. New York: McGraw-Hill Professional; 2007.

Marx J, Hockberger R, Walls R, editors. Rosen's emergency medicine. 7th ed. Philadelphia: Mosby; 2010.

Sanders RC, Winter T, editors. Clinical sonography: a practical guide. 4th ed. Philadelphia: Lippincott Williams & Wilkins; 2007.

Ultrasonography for Placenta Previa

114

L. Connor Nickels and Giuliano De Portu

Placenta previa is a condition in which the placenta covers the internal cervical os. It is the leading cause of antepartum hemorrhage. There are four grades of the condition:

- Complete: Placenta completely covers the internal os.
- Partial: Placenta partially covers the internal os.
- Marginal : Lower margin of placenta reaches the internal os but does not cover it (within 3 cm).
- Low lying: Lower margin of placenta is located in the lower uterine segment but does not reach the internal os (Fig. 114.1).



Fig. 114.1 Varying degrees of placenta previa

L.C. Nickels, MD, RDMS (✉) • G. De Portu, MD
Department of Emergency Medicine, University of Florida Health
Shands Hospital, Gainesville, FL, USA
e-mail: cnickels@ufl.edu; gdeportu@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_114

114.1 Indications

- A patient in the second half of pregnancy who presents to the emergency room with bright red, painless vaginal bleeding OR premature labor should be evaluated for this condition.

114.2 Contraindications

- Absolute:
  - There are no absolute contraindications to transabdominal ultrasonography.
- Relative:
  - Transvaginal ultrasound should be carried out with caution, so as to avoid hemorrhage.

114.3 Materials and Medications

- Ultrasound machine
- Probes: curvilinear or phased array, endocavitary
- Sterile gel
- Endocavitary probe covers
- Towels
- Sterile speculum (see previously)
- Cardiac monitor, two large-bore intravenous needles, laboratory tests

114.4 Procedure

1. Place the patient in the supine position.
2. Ultrasound machine with abdominal probe and gel.
3. Begin scanning the patient in a transabdominal sagittal position (Fig. 114.2) to determine the placental position and whether it is lying in the lower uterine segment.
4. The patient should then be scanned in a transverse fashion to further evaluate the exact position of the placenta.
5. If the placenta appears to lie in the lower uterine segment, the patient should be scanned in the oblique plane as well.
6. The bladder should initially be full for best visualization. However, if the placenta appears to reside low or lie over the internal os, the scanning should be repeated after the patient has voided.
   - An overdistended bladder may create the appearance of a placenta previa. The anterior wall of the uterus is compressed against the posterior wall by the distended bladder, shortening the distance between the placenta and the internal os (Fig. 114.3).
7. The following ultrasonographic findings exclude placenta previa [1]:
   - Direct apposition of the presenting part of the fetus and the cervix without space for interposed tissue
   - Presence of amniotic fluid between the presenting part of the fetus and the cervix, without the presence of placental tissue
   - Distance of greater than 2 cm between the inferior aspect of the placenta
   - Indirect visualization of the internal cervical os
8. If placenta previa cannot be ruled out with transabdominal ultrasound, the patient should then be scanned transvaginally with the endocavitary probe because this is more sensitive for diagnosing placenta previa.
9. A sterile speculum examination should be performed before transvaginal scanning to assess the cervix and ensure there are no presenting parts or bulging membranes. Transvaginal imaging is contraindicated if the patient has ruptured or bulging membranes.
10. The probes should be swapped out and a sterile cover placed on the endocavitary probe with gel inside the cover and sterile gel on the outside of the cover.
11. The endocavitary probe should be inserted into the vaginal canal, ensuring that caution is taken to stay off the cervix and distal to it, keeping the cervix in view on the screen.
12. The patient should be scanned in both the sagittal and the transverse planes to assess the inferior margin of the placenta.



Fig. 114.2 Transabdominal ultrasound of placenta previa. Note loss of the decidual interface between the placenta and the myometrium on the lower part of the uterus and multiple intraplacental lacunae (*arrows*) (Reproduced with permission from *J Korean Med Sci*. 2010; 25(4):651–5)

13. If the inferior margin appears to be located near the internal os, then the distance should be measured.
    - Steps 8 through 13 should only be performed by the emergency physician if he or she feels confident in this ultrasound skill and there is no obstetrics available. If obstetrics is available, these steps should be performed in conjunction with them or by them to ensure the best outcome for the patient.

Fig. 114.3 (**a**) Overdistended bladder creating the appearance of placenta previa, (**b**) empty bladder showing the more accurate position of the placenta



114.5 Complications

- Bleeding:
  - May range from self-limited to life-threatening hemorrhage
- Maternal and/or fetal distress or death

114.6 Pearls and Pitfalls

- Pearls
  - Risk factors include:
    - Multiparity
    - Multiple pregnancy
    - Advanced maternal age
    - Previous placenta previa
    - Cigarette smoking
    - Cocaine abuse
    - Hypertension
    - Previous cesarean delivery/uterine surgeries
  - Myometrium contraction: can mimic placenta previa by temporarily displacing the placenta in the lower uterine segment.
  - If ultrasound capabilities are not available, but the patient is in the second half of pregnancy and having vaginal bleeding, do not perform a digital cervical examination.
- Pitfalls
  - Digital examination should be avoided because this may precipitate life-threatening hemorrhage and/or death.
  - Always consult obstetrics as soon as possible if this is suspected or known and the patient is symptomatic. Not consulting obstetrics could be detrimental to the mother and fetus.
  - Gentle sterile speculum examination should be done only if an obstetrician is not available. This is to ensure the bleeding is coming from the cervix. If placenta previa is suspected or known and obstetrics are available, then abdominal ultrasound evaluation alone should be sufficient for the examination of the patient.

Reference

1. American College of Radiology. Role of imaging in second and third trimester bleeding. In: ACR Appropriateness Criteri. Reston: American College of Radiology; 2001.

Selected Reading

Gabbe SG, Niebyl JR, Galan HL, et al., editors. Obstetrics: normal and problem pregnancies. 5th ed. Orlando: Churchill Livingstone; 2007.

Ma OJ, Mateer J, Blaivas M, editors. Emergency ultrasound. 2nd ed. New York: McGraw Hill Professional; 2007.

Marx J, Hockberger R, Walls R, editors. Rosen’s emergency medicine: concepts and clinical practice. 7th ed. Philadelphia: Mosby; 2010.

Sanders RC, Winter T, editors. Clinical sonography: a practical guide. 4th ed. Philadelphia: Lippincott Williams & Wilkins; 2007.

Vaginal Delivery

115

Umarfarook Javed Mirza, Christopher Shields,
and Muhammad Waseem

115.1 Indications

- Inevitable delivery of the fetus (cervix fully dilated at 10 cm and fully effaced 1 mm with crowning of the head)

115.2 Contraindications

- Absolute:
  - Indications for emergent cesarean section (C-section)
  - Prolapsed cord
  - Prior C-section with classic vertical incision
  - Placenta previa – complete/partial
  - Breech presentation – footling
- Relative:
  - Placenta previa – marginal/low lying
  - Breech presentation – complete/incomplete/frank

115.3 Materials and Medications (Fig. 115.1)

- 4 Crile clamps or Kelly clamps
- 1 Mayo scissor curved and 1 Mayo scissor straight
- 2 sponge forceps
- 2 towel clamps
- 1 Mayo-Hegar needle holder
- 1 mouse-tooth forceps
- Suction bulb
- Betadine (povidone-iodine)
- Umbilical cord clamp (Fig. 115.2)
- Incubator warmer (Fig. 115.3)
- Most importantly, help.

U.J. Mirza, DO
Department of Emergency Medicine,
Baylor University Medical Center, Dallas, TX, USA
e-mail: Umarfarook.Mirza@gmail.com

C. Shields, MD • M. Waseem, MD (✉)
Department of Emergency Medicine,
Lincoln Medical and Mental Health Center, New York, NY, USA
e-mail: cpatrickshields@hotmail.com; waseemm2001@hotmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_115


DELIVERY SET
Contents
2-Sponge Forceps - straight
4-Crile Clamps - curved
1-Mayo-Hegar Needle Holder
1-Mousetooth Forcep
1-Mayo Scissors - curved
1-Mayo Scissors - straight
2-Towel Clamps

Fig. 115.1 Equipment: delivery set



Fig. 115.2 Equipment: umbilical clamp



Fig. 115.3 Equipment: incubator warmer

115.4 Procedure

1. Determine the fetal presentation (breech or cephalic) with Leopold's maneuvers or bedside ultrasound.
2. If breech, follow the breech pathway.
3. Perform a vaginal examination.
4. Check for cord prolapse.
5. Check effacement.
6. Check dilation.
7. Prepare the site.
8. Position the mother in the extreme lithotomy position.
9. Deliver the head in a controlled manner.
10. Check to see if the cord is wrapped around the neck. If present, follow cord presentation pathway.
11. Deliver the anterior shoulder with downward traction of the head.
12. Check for shoulder dystocia. If present, follow the McRobert-Rubin maneuvers (see Chap. 116).
13. Deliver the posterior shoulder by gently pulling the trunk upward.
14. Suction the airway.
15. Clamp the cord 5 cm from the umbilicus in two places and cut.
16. Obtain Apgar score of the baby. Initiate resuscitation if required.
17. Keep the baby warm in the incubator.
18. Clamp the cord again closer to the vaginal opening.
19. Use this clamp to help deliver the placenta. Use gentle controlled traction on the clamp with one hand while placing the other hand suprapubically to push the uterus upward.
20. If the placenta does not deliver easily, stop and wait a few minutes to allow it to come away from the uterine wall naturally and then try again.
21. Placenta must be fully intact. If not, check for retained intrauterine placental products, and manually remove them; retained placenta may cause postpartum hemorrhage.
    - Massage the fundus externally to prevent uterine atony, but only after all products have been removed.
22. Repair any vaginal or cervical lacerations.

115.5 Complications

- Postpartum hemorrhage due to uterine atony or retained products
- Uterine inversion
- Rectal or urethral injuries
- Shoulder dystocia
- Meconium aspiration

115.6 Pearls and Pitfalls

- Pearls
  - Postpartum hemorrhage has a high incidence during the first hour postpartum.
  - Be aware of possible second delivery.
  - Oxytocin or Methergine (methylergonovine maleate) may be used after delivery of the placenta; both help increase uterine contractions and decrease postpartum hemorrhage.
- Pitfalls
  - Rushing delivery of the head/shoulders can lead to trauma to the mother/baby.
  - Rushing delivery of the placenta, when the placenta is not ready to detach, may cause placental or cord tearing or uterine inversion. Remember: it may take up to 20 min for the placenta to detach from the uterus.

Selected Reading

Desai S, Henderson SO, Mallon WK. Labor and delivery and their complications. In: Marx J, Hockberger R, Walls R, editors. Rosen's emergency medicine: concepts and clinical practice. 7th ed. Philadelphia: Mosby; 2010.

Liao JB, Buhimschi CS, Norwitz ER. Normal labor: mechanism and duration. Obstet Gynecol Clin North Am. 2005;32:145–64.

Norwitz ER, Robinson JN, Repke JT. Labor and delivery. In: Gabbe SG, Niebyl JR, Simpson JL, editors. Obstetrics: normal and problem pregnancies. 4th ed. Philadelphia: Saunders; 2001. p. 353–94.

Shoulder Dystocia Management

116

Irina Fox Brennan and Joseph A. Tyndall

116.1 Indications

- Retracting fetal head ("turtle sign")
- Failure of anterior shoulder delivery following gentle downward traction
- Difficult face-chin delivery
- Failure of shoulders to descend

116.2 Contraindications

- Mother with diabetes and fetus larger than 4500 g
- Mother without diabetes and fetus larger than 5000 g
- History of shoulder dystocia with prior birth
- Factors that signal the need for cesarean section:
  - Complete/partial placenta previa
  - Cord prolapse
  - Brow/face presentation
  - Non-reassuring fetal heart rate
  - Extensive uterine surgery and previous classic uterine incision

116.3 Materials and Medications

- No specialized materials/equipment required.
- Team coordination is of utmost importance.

I.F. Brennan, MD • J.A. Tyndall, MD, MPH (✉)
Department of Emergency Medicine, University of Florida Health,
Gainesville, FL, USA
e-mail: ibrennan@ufl.edu; tyndall@ufl.edu

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_116

116.4 Procedure

1. *Accurate documentation*: Designate a team member to document the progress of labor, the position and rotation of the infant's head, the time of delivery for the head and body, the presence of episiotomy, anesthesia requirements, the duration of shoulder dystocia, whether the shoulder is anterior or posterior at the time of delivery, the onset/duration/results of maneuver(s) performed, and Apgar scores.

   The HELPERR mnemonic is commonly employed:
2. *Help recruitment*: Involve anesthesiology, pediatric resuscitation, and obstetric/gynecology colleagues either as part of advance preparations or via activation of protocol during labor.
3. *Episiotomy consideration*: Not required but might be of benefit if more space is needed for rotation maneuvers.
   - Episiotomy alone will not release the impacted shoulder.
4. *Legs positioned for the McRoberts maneuver*: Position the woman's thighs onto her abdomen by abducting and flexing her hips. Have two assistants help her, one on either side. This increases the functional size of the bony pelvis by rotating the pubic symphysis toward the mother's head, hence aiding delivery (Fig. 116.1).

Fig. 116.1 McRoberts maneuver: hyperflexion of the maternal thighs against the abdomen



5. *Pressure suprapubically* (*Rubin I maneuver*): While continuing downward traction, have a colleague place his or her hand suprapubically on the fetal anterior shoulder and apply pressure down and laterally on its posterior aspect in 30-second increments. This allows the fetal shoulders to enter the pelvis in an oblique fashion (pelvic inlet is widest in the transverse plane) (Fig. 116.2).
6. *Enter maneuver* (*internal rotation*): Rotate the anterior shoulder into the oblique plane and under the maternal symphysis.
   - It may be necessary to push the fetus slightly up into the pelvis in order to successfully perform this maneuver.
     (a) *Rubin II maneuver*: Insert one hand vaginally behind the fetal anterior shoulder and rotate the shoulder toward the chest. This will reduce the diameter of the fetal shoulder girdle and facilitate delivery (Fig. 116.3).
     (b) *The Woods corkscrew maneuver*: Place one hand at the front of posterior shoulder and push upward gently. This can be combined with the Rubin II maneuver (Fig. 116.4).
     (c) *The reverse Woods corkscrew maneuver*: Place one hand behind the fetal posterior shoulder and rotate in the direction opposite to that of the Woods corkscrew maneuver to adduct the shoulder.
7. *Remove the posterior arm*: Flex the fetal elbow and deliver the forearm in a sweeping motion over the fetal anterior chest wall. This allows the fetus to drop into the sacral hollow, freeing the anterior shoulder impaction.
   - Avoid grasping and pulling on the fetal arm directly because it may fracture the fetal humerus.
8. *Roll the patient* (*Gaskin maneuver*): Position the patient on all fours (this acts as an upside-down McRoberts maneuver). Continue gentle traction. The turning itself, as well as gravity, will often dislodge the impacted shoulder.

   Last-resort maneuvers:
9. *Deliberate fracture of the fetal clavicle*: Apply direct pressure upward in the middle of the clavicle to reduce the shoulder-to-shoulder distance.



Fig. 116.2 Ruben I maneuver: suprapubic pressure is directed at the anterior shoulder



Fig. 116.3 Ruben II maneuver: pressure is applied to the most accessible part of the fetal shoulder and rotated toward the chest



Fig. 116.4 The Woods corkscrew maneuver: pressure is applied to the clavicle of the posterior arm, enabling rotation and dislodgement of the anterior shoulder

10. *Zavanelli maneuver*: Rotate the fetal head into the direct occiput anterior position, flex, and push back into the birth canal. Continue holding upward pressure until cesarean delivery. Ensure the operating and anesthesiology teams are present (Fig. 116.5).
    - Do not perform this maneuver if the nuchal cord has been clamped or cut.
11. *Symphysiotomy*: Place the patient in the exaggerated lithotomy position, insert a transurethral catheter, displace the urethra laterally, and separate the cephalad portion of fibrous cartilage of the symphysis pubis under local anesthesia with either a scalpel blade or Kelly clamp.
    - This technique is associated with significant maternal morbidity, including bladder neck injury and infection. It is truly the last resort and should be used only when all other methods have failed and cesarean delivery is unavailable.



Fig. 116.5 Zavanelli maneuver: the fetal head is rotated into the direct occiput anterior position, flexed, and pushed back into the birth canal. (**a**) Rotation of the head to the occiput anterior position. (**b**) Replace head with constant firm pressure on occiput with palm of hand flexing head

116.5 Complications

- Maternal:
  - Postpartum hemorrhage
  - Fourth-degree laceration/soft tissue damage to cervix and vagina
  - Uterine rupture
  - Bladder atony
  - Symphyseal separation with or without femoral neuropathy (transient)
  - Sacroiliac dislocation
- Fetal:
  - Brachial plexus palsies (Erb, Klumpke): most resolve within 6–12 months; permanent injury occurs in less than 10 % of patients
  - Clavicular and/or humeral fractures
  - Ischemia/hypoxia/asphyxia due to umbilical cord compression with or without neurological damage
  - Significant fetal acidosis, with pH drop of 0.04 U/min between delivery of the head and trunk
  - Death

116.6 Pearls and Pitfalls

- Pearls
  - Many cases of shoulder dystocia and birth trauma are encountered in the absence of risk factors and in non-macrosomic infants. Shoulder dystocia is largely neither predictable nor preventable.
  - Presence of risk factors for shoulder dystocia should prompt advance preparation in anticipation of a difficult delivery. Risk factors include maternal diabetes, obesity, multiparity, advanced maternal age, prolonged pregnancy, macrosomia (fetal weight >4,500–5,000 g), male fetal gender, and prior birth complicated by shoulder dystocia.
- Pitfalls
  - Do not cut and clamp the nuchal cord if at all possible in order to avoid fetal hypoxia and hypotension should shoulder dystocia arise.
  - Labor induction or prophylactic cesarean delivery of macrosomic fetuses has not decreased rates of shoulder dystocia.
  - Avoid fundal pressure in shoulder dystocia because it has been shown to increase the risk of permanent neurological damage and uterine rupture.

Selected Reading

Acker DB. A shoulder dystocia intervention form. Obstet Gynecol. 1991;78:150–1.

Athukorala C, Middleton P, Crowther CA. Intrapartum interventions for preventing shoulder dystocia. Cochrane Database Syst Rev. 2006;4:CD005543.

Baxley EG, Gobbo RW. Shoulder dystocia. Am Fam Physician. 2004;69:1707–14.

Chauhan SP, Gherman R, Hendrix NW, Bingham JM, Hayes E. Shoulder dystocia: comparison of the ACOG practice bulletin with another national guideline. Am J Perinatol. 2010;27:129–36.

Gherman RB, Chauhan S, Ouzounian JG, Lerner H, Gonik B, Goodwin TM. Shoulder dystocia: the unpreventable obstetric emergency with empiric management guidelines. Am J Obstet Gynecol. 2006;195:657–72.

Gottlieb AG, Galan HL. Shoulder dystocia: an update. Obstet Gynecol Clin North Am. 2007;34:501–31.

Hoffman MK, Bailit JL, Branch DW, et al. Consortium on safe labor. A comparison of obstetric maneuvers for the acute management of shoulder dystocia. Obstet Gynecol. 2011;117:1272–8.

Patterson DA, Winslow M, Matus CD. Spontaneous vaginal delivery. Am Fam Physician. 2008;78:336–41.

Sokol RJ, Blackwell SC, American College of Obstetricians and Gynecologists. Committee on Practice Bulletins–Gynecology. ACOG practice bulletin no. 40: shoulder dystocia. November 2002 (replaces practice pattern no. 7, October 1997). Int J Gynaecol Obstet. 2003;80:87–92.

Breech Delivery in the Emergency Department

117

Kristin Stegeman, Sapnalaxmi Amin, Anton A. Wray,
and Joseph A. Tyndall

Breech presentation: the buttocks enter the pelvis before the head (Fig. 117.1)

- Frank (extended):
  - Hips flexed and knees extended, buttocks presenting
  - Most common
- Incomplete/complete (flexed):
  - One or both hips and knees flexed, buttocks presenting
- Footling:
  - One or both hips and knees extended, foot presenting

The emergent delivery of a breech baby is one of the most challenging situations for an emergency physician.



Fig. 117.1 Variations of the breech presentation

K. Stegeman, MD • A.A. Wray, MD (✉)
Department of Emergency Medicine, The Brooklyn Hospital Center, New York, NY, USA
e-mail: kristin.stegeman@gmail.com; anw9071@nyp.org

S. Amin, MD
Department of Family Medicine/Urgent Care,
Bayside Urgent Care Center, Clearwater, FL, USA
e-mail: sapna_amin59@yahoo.com

J.A. Tyndall, MD, MPH
Department of Emergency Medicine, University of Florida Health,
Gainesville, FL, USA
e-mail: tyndall@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_117

117.1 Indications

- Inevitable delivery of fetus with complete or frank breech presentation
- Absence of vertex presentation

117.2 Contraindications

- Footling presentation (increased risk of cord prolapse and entrapment of the after-coming head).
- There is adequate time to transfer the mother safely to labor and delivery in the knee/chest position (administer subcutaneous terbutaline before transfer).

117.3 Materials and Medications

- Supplemental oxygen for mother
- Ultrasound machine
- Piper forceps
- Sterile towels/gloves
- Betadine (povidone-iodine) or another antiseptic preparing solution
- Sterile lubricant (Surgilube)
- Instruments to cut the umbilical cord/perform episiotomy/resuscitate baby (Kelly clamps/scissors/#10 scalpel/bulb suction)
- Available emergency department staff
- Pediatric, obstetrics, and anesthesia practitioners

117.4 Procedure

1. Assess the health of the mother and the baby (vitals/physical examination/history).
2. Listen to the fetal heart with stethoscope or Doppler ultrasound.
    - Should be 120–160 beats/min.
3. Identify the type of presentation by bedside ultrasound or by digital exam.
4. Perform a sterile digital examination to confirm the position of the baby and the stage of labor.
    - Membranes should not be artificially ruptured. The amniotic sac will help to dilate the cervix, lubricate the canal, and protect the umbilical cord from compression.
5. If footling presentation: await OB/general surgery for emergency C-section.
6. If frank/complete/incomplete: instruct the patient to push when the cervix is completely dilated.
7. When the breech has descended to the perineum, consider performing an episiotomy if more space is needed. Cleanse the perineum with antiseptic and sterile lubricant beforehand.
8. Allow the baby to extrude to the umbilicus with maternal efforts alone. Do not exert traction before this time.
9. If frank: deliver the posterior leg by gently guiding the sacrum anteriorly, grasping the thigh and flexing the leg at the knee.
10. Deliver the anterior leg in a similar manner while guiding the sacrum posteriorly.
11. If incomplete: deliver the extended leg as #8 or #9 as appropriate.
12. Delivery continues as it would for a complete presentation.
13. Wrap the legs/buttocks in a clean towel to decrease trauma (create grip).
14. Grasp the upper legs with the index fingers holding the anterior iliac crests. Place the thumbs on the sacrum (Fig. 117.2).
15. Apply gentle traction as the mother pushes until the scapulae and axillae are visible.
16. If there is difficulty delivering the shoulders, deliver the posterior shoulder by rotating the trunk 90° and applying gentle downward traction to rotate the shoulder anteriorly.
17. Rotate the baby 180° so as to deliver the anterior arm in a similar manner.
18. If the arms do not spontaneously deliver, a finger can be hooked over the shoulders to bring the arm down while rotating the trunk as above (Fig. 117.3).
19. Use the McRoberts position to increase the diameter of the pelvis (Fig. 117.4).



Fig. 117.2 Correct placement of hands on sacrum



Fig. 117.3 Rotation toward maternal symphysis pubis to avoid nuchal arm


Pelvic outlet
Pelvic outlet

Fig. 117.4 The McRoberts maneuver in vertex (head-first) presentation

20. Maintain the baby in the same plane as the vagina (support the body with the forearm) and place the second and fourth fingers over the maxilla of the baby. Place the middle finger in the mouth or on the chin and the other hand on the upper back/occiput (Fig. 117.5).
    - Avoid extreme elevation of the fetus to prevent hyperextension and cervical spine injury. Piper forceps may also be used to promote flexion.
21. Deliver the head in the flexed position.
    - If the baby descends with the neck and abdomen facing anteriorly: Grasp the shoulders posteriorly with two fingers of one hand while the other hand flexes the abdomen and the baby's feet are brought upward (Fig. 117.6).
    - If the baby's neck remains extended: Leave the baby hanging (weight = traction). When the hairline appears under the symphysis, grab the baby by the feet and elevate upward (Fig. 117.7).
22. Clamp and cut the umbilical cord (collect arterial and venous samples for pH).
23. Suction the baby's mouth and nose, and resuscitate as indicated.
24. Deliver the maternal placenta.
25. Repair tears or episiotomy made during delivery.



Fig. 117.5 Delivery of head in flexed position



Fig. 117.6 Correct hand placement if abdomen facing anterior



Fig. 117.7 The Burns-Marshall maneuver. (**a**) Allow baby to hang until you can see the hair at the nape of his neck; (**b**) swing the baby's head clear of the birth canal; (**c**) left hand guards and slips the perineum over fetal mouth; suction baby's air passage to clear mucus; (**d**) hold baby's feet

117.5 Complications

- Umbilical cord prolapse
- Brachial plexus injury (from the nuchal arm)
- Fetal head entrapment
- Cervical spine injury (from hyperextension of the neck)
- Birth asphyxia

117.6 Pearls and Pitfalls

- Pearls
  - Allow the uterine contractions to help deliver the baby.
- Pitfalls
  - Do not rush the delivery or use too much force. This can increase the risk of trauma to the baby and mother.
  - Beware of nuchal arm. To avoid brachial plexus injury: Rotate the face of baby toward the maternal symphysis pubis. This will reduce the tension keeping the arm around the back of the fetal head (Fig. 117.3).

Selected Reading

Auerbach PS. Gynecologic and obstetric emergencies. In: Wilderness medicine. 6th ed. Philadelphia: Elsevier; 2012.

Buckley RG, Knoop KJ. Gynecologic and obstetric conditions. In: Knoop KJ, Stack LB, Storrow AB, Thurman RJ, editors. The atlas of emergency medicine. 3rd ed. New York: McGraw Hill; 2010.

Cunningham FG, Leveno KJ, Bloom SL, Hauth JC, Rouse DJ, Spong CY. Breech presentation and delivery. In: Williams obstetrics. 23rd ed. New York: McGraw Hill; 2010.

Kish K, Collea JV. Chapter 21. Malpresentation & cord prolapse. In: DeCherney AH, Nathan L, editors. Current diagnosis & treatment: obstetrics & gynecology. 10th ed. New York: McGraw Hill; 2007.

Kotaska A, Menticoglou S, Gagnon R. Vaginal delivery of breech presentation. Int J Gynecol Obstet. 2009;107:169–76.

Probst BD. Emergency childbirth. In: Roberts JR, Hedges JR, editors. Clinical procedures in emergency medicine. 5th ed. Philadelphia: Elsevier; 2010.

Management of Primary Postpartum Hemorrhage

118

Megan Kwasniak, Anton A. Wray, and Joseph A. Tyndall

Postpartum hemorrhage (PPH) is defined as ≥500 ml blood loss within 24 h of vaginal delivery or 1000 ml loss within 24 h of cesarean section. It is the leading cause of maternal mortality worldwide.

118.1 Indications

- Excessive vaginal bleeding with or without pain and/or hemodynamic instability within 24 h of delivery

118.2 Contraindications

- There are no absolute contraindications to the management of PPH.

118.3 Materials and Medications

- Sterile technique
- Good lighting
- Sponge forceps
- Gauze
- Towels
- IV fluids
- Type and screen/crossmatch of blood
- Absorbable suture with curved needle
- Needle holder
- Tooth forceps

118.4 Procedure

- Standard resuscitation measures: Place IV, O_2, monitor.
- Assessment and treatment should occur simultaneously.
- All techniques should be performed under strict sterile conditions.

118.4.1 Uterine Exam

1. Assess by placing the hand on the uterine fundus and checking its size and firmness.
2. High, soft, or boggy uterus implicates retained placenta or uterine atony. Start external fundal massage.
3. Non-palpable uterus implicates uterine inversion.

118.4.2 Vaginal Exam

1. Keeping one hand on the abdomen, gently examine the vaginal canal using the other sterilely gloved hand.
2. Gently scoop out any clots/retained placenta that are easily removable.
3. Look for traumatic sources of bleeding from the perineum, vaginal walls, and cervical lacerations.
4. Gauze-wrapped ring forceps can be used to assist direct visualization and clearing of clots.

M. Kwasniak, MD
Emergency Department, The Brooklyn Hospital Center,
New York, NY, USA
e-mail: megan.kwasniak@gmail.com

A.A. Wray, MD (✉)
Department of Emergency Medicine, The Brooklyn Hospital
Center, New York, NY, USA
e-mail: anw9071@nyp.org

J.A. Tyndall, MD, MPH
Department of Emergency Medicine, University of Florida Health,
Gainesville, FL, USA
e-mail: tyndall@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_118

118.4.3 If Uterine Atony Suspected

1. Continue external fundal massage with the abdominal hand. Make a fist with the vaginal hand and start bimanual massage. Raise the uterus from the pelvis and pivot it anteriorly, compressing it between the external hand and the internal fist. This maneuver will result in expression of any clots present and decrease uterine bleeding via direct compression (Fig. 118.1).
2. Administer oxytocin (20–40 units in 1 L of normal saline or lactated Ringer's solution intravenously [IV]; alternatively give 10 units intramyometrially with a spinal needle).
3. Methylergonovine may also be used at this time if oxytocin fails to reduce uterine bleeding (100 or 125 mcg IV or intramyometrially; alternatively 200 or 250 mcg may be given intramuscularly).
4. Continue massage until bleeding slows and the uterus becomes more firm. This can take 15–30 mins.



Fig. 118.1 Intrauterine massage for uterine atony

118.4.4 If Retained Placenta Suspected

1. Manual removal of the placenta or any of its retained tissue should be facilitated with sedation or additional analgesia.
2. Keeping the thumb and fingers together in a teardrop shape and using sterile technique as described previously, insert the hand through the vaginal canal and the cervix into the lower uterine segment.
3. Keep the other hand on the lower abdomen to continue gentle yet firm upward pressure and massage.
4. Find the placental edge within the uterus, grasp it gently, detach it from the uterine wall, and withdraw the hand from the patient.
5. Repeat the maneuver as necessary; remove any additional clots from the uterus and continue bimanual massage until it becomes firm and bleeding decreases.
6. If the entire placenta has been removed this way, an assistant should be available to inspect it for completeness and any torn vessels.
7. If the bleeding is particularly severe and placenta accreta is strongly suspected, pack the uterus with gauze and prepare the patient for urgent surgical intervention.

118.4.5 If Uterine Inversion Suspected

1. Using sterile technique, insert a fist through the vaginal canal and push the inverted fundus back through the cervical canal with pressure directed toward the umbilicus.
2. If the uterus has contracted, tocolytics such as IV magnesium sulfate or terbutaline can be used to aid myometrial relaxation. Alternatively, provided the patient is not overly hypotensive, nitroglycerin 50–100 mcg IV may be administered to relax the myometrium and facilitate return to normal uterine position.
3. If manual replacement is ineffective, hydrostatic reduction may be attempted. Warm fluids are run into the upper vagina under high pressure while occluding the introitus.

118.4.6 Trauma: Genital and Perineal Lacerations

1. For significant cervical lacerations: use absorbable sutures with a continuous interlocking stitch technique to close (Fig. 118.2).
2. For vaginal wound repair: place the initial and final stitch above the apices of the lacerations and grab a good amount of tissue with the needle. Small bites can lead to ongoing bleeding and hematoma formation.
3. Observe the repaired lacerations for any additional bleeding after the torn edges have been sutured.
    - Apply additional pressure to any site that continues to ooze blood; gauze-wrapped ring forceps may be used for this purpose if necessary.

If none of the above causes are apparent, consider underlying coagulopathies and treat appropriately. This may require administration of fresh-frozen plasma, platelets, or clotting factors as indicated.



Fig. 118.2 Continuous interlocking stitch: perineal lacerations repair

118.5 Complications

- Uterine perforation and scarring
- Urinary and genital tract trauma and injury
- Genitourinary and genitointestinal fistula
- Pelvic hematoma
- Genital vascular injury
- Infection and sepsis
- Disseminated intravascular coagulation (DIC)
- Maternal death

118.6 Pearls and Pitfalls

- Pearls
    - Causes of PPH can be divided into the “5 Ts”:
        - Tone: uterine atony, occurring within the first 4 h after delivery.
        - *T*issue: retention of the placenta, especially placenta accreta and its fragments, more common at extreme preterm deliveries.
        - *T*rauma: injury to the uterus, cervix, and perineal structures after delivery of a large fetus, use of forceps and/or vacuum, frequent vaginal manipulation during delivery, and episiotomy procedures.
        - *T*hrombosis: intrinsic or acquired coagulation disorders, including idiopathic thrombocytic purpura (ITP); hemolysis, elevated liver enzymes, and low platelets (HELLP) syndrome; and disseminated intravascular coagulation (DIC), as well as preexisting conditions such as von Willebrand disease.
        - *T*raction: inversion of the uterus during placental delivery secondary to excessive traction on the umbilical cord. The uterine fundus can be within the endometrial cavity, in the cervical canal, or outside the external os and within the vaginal canal.
    - The administration of broad-spectrum antibiotics should be strongly considered following any manual removal, exploration, or instrumentation of the uterus and the genital tract.
    - Bedside ultrasonography can be very helpful for identifying uterine abnormalities, retained placental tissue, free fluid in the pelvis, and/or intrauterine hematoma.
    - Risk factors for PPH include prolonged active phase of labor, previous PPH, multiple pregnancy, and history of a bleeding disorder.
- Pitfalls
    - Failure to recognize and treat PPH early increases morbidity and mortality.
    - Underestimating the potential blood loss of PPH. The gravid uterus at term has a blood flow of 600 ml/min (non-gravid: 60 ml/h).

Selected Reading

Anderson J, Duncan E. Prevention and management of postpartum hemorrhage. Am Fam Physician. 2007;75:875–82.

Druelinger L. Postpartum emergencies. Emerg Med Clin North Am. 1994;12:219–37.

Leduc D, Senikas V, Lalonde AB, et al. Active management of the third stage of labour: prevention and treatment of postpartum hemorrhage. J Obstet Gynaecol Can. 2009;31:980–93.

Miller S, Lester F, Hensleigh P. Prevention and treatment of postpartum hemorrhage: new advances for low-resource settings. J Midwifery Womens Health. 2004;49:283–92.

Sheiner E, Sarid L, Levy A, Seidman DS, Hallak M. Obstetric risk factors and outcome of pregnancies complicated with early postpartum hemorrhage: a population-based study. J Matern Fetal Neonatal Med. 2005;18:149–54.

Tessier V, Pierre F. Risk factors of postpartum hemorrhage during labor and clinical and pharmacological prevention. J Gynecol Obstet Biol Reprod (Paris). 2004;33(8 suppl):4S29–56.

World Health Organization. World health report 2005: make every mother and child count. Available at: http://www.who.int/whr/2005/whr2005_en.pdf.

Perimortem Cesarean Section

119

Jordana J. Haber, Elaine B. Josephson,
and Muhammad Waseem

119.1 Indications

- Maternal arrest with a viable fetus (gestation >24 weeks)

119.2 Contraindications

- Stable mother
- Fetus less than 24 weeks' gestation
- Extreme fetal prematurity
- Maternal hypoxia longer than 15 min

119.3 Materials and Medications

- Cesarean section instrument tray if available
  - #10 or #11 scalpel blade, scissors, bladder retractor, 2 large retractors, gauze sponges, hemostats, suction, forceps, and straight and curved clamps
- Skin antiseptic preparing solution, such as Betadine (povidone-iodine)
- Silk suture with needle driver or skin stapler
- Sterile drapes
- Sterile gloves
- Obstetrical pack (See Chap. 115)
  - Bulb syringe and umbilical cord clamp
- Clean blanket or towels for delivery
- Neonatal resuscitation equipment

Owing to the rarity of this procedure in the emergency department, it is unlikely to have a prepared cesarean section tray available. In this case, a thorocotomy or thorocostomy tray combined with an obstetrical pack would contain all the supplies needed. At a minimum, a scalpel and an obstetrical pack are necessary.

J.J. Haber, MD
Department of Emergency Medicine, Maimonides Medical Center,
New York, NY, USA
e-mail: Jordana.haber@gmail.com

E.B. Josephson, MD
Department of Emergency Medicine, Lincoln Medical and Mental
Health Center, Weill Cornell Medical College of Cornell
University, Bronx, New York, NY, USA
e-mail: elaine.Josephson@nychhc.org

M. Waseem, MD (✉)
Department of Emergency Medicine, Lincoln Medical and Mental
Health Center, New York, NY, USA
e-mail: waseemm2001@hotmail.com

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_119

119.4 Procedure

1. Prepare skin with antiseptic solution and a sterile drape.
2. Insert a Foley catheter to empty the bladder.
3. Continue cardiopulmonary resuscitation until delivery.
4. Obtain emergent obstetrician and neonatologist consult if available, but do not delay procedure.
5. Using a #10 or #11 blade, make a vertical midline incision beginning 4–5 cm below the xiphoid process and extend the incision to the pubic symphysis (Fig. 119.1).
6. Incise through the subcutaneous fat no further than the rectus sheath.
7. Lift the rectus sheath with a toothed forceps and make an incision with scissors to expose the uterus (Fig. 119.2).
8. With forceps and scissors, lift and incise the peritoneal membrane in the midline.
9. Identify and lift the bowel and cover it with saline-soaked gauze.
10. Retract the rectus sheath and bladder with a bladder retractor or, if not available, use saline-soaked gauze or a towel.
11. Create a 2- to 4-cm midline vertical opening in the uterus.
12. Place a finger in the opening directed caudally to protect the fetus while making a superior incision through the uterine wall. Once complete, repeat this step in the inferior direction.
13. Use a clamp to rupture the amniotic membranes. Immediately deliver the fetus and clamp the umbilical cord.
14. Expulse the head by placing a hand between the pubic symphysis landmark and the fetal occiput. Then, gently flex the fetus while simultaneously moving the head superiorly and anteriorly until delivery (Fig. 119.3).
15. Suction the mouth and nose with a bulb syringe immediately.
16. Deliver the shoulders, followed by the torso and extremities. Secure the umbilical cord with a hemostat or umbilical cord clamp 10 cm distal to the fetus and a second clamp 2 cm distal to this clamp. With scissors, incise the umbilical cord between the two clamps.
17. Immediately begin resuscitation of the infant (Fig. 119.4).
18. If the patient is still alive or regains vital signs, prepare to deliver the placenta. Begin with an oxytocin infusion at 20 U in 1 L at 10 mL/h. Apply cautious traction to the umbilical cord until the placenta separates from the uterus (Fig. 119.5).
19. Following delivery, the uterus should be closed using two layers with either 2-0 or 1-0 suture. In the case of maternal death, skin staples or a running stitch is an acceptable method of skin closure.



Fig. 119.1 Vertical incision

Fig. 119.2 Exposing rectus sheath


Rectus
abdominis
Parietal
peritoneum
Cut edge of
rectus fascia





Fig. 119.3 Delivery of the fetus

Fig. 119.4 Suctioning newborn as part of resuscitation



Fig. 119.5 Delivery of the placenta

119.5 Complications

- Maternal sepsis
- Maternal visceral injury
- Maternal hemorrhage
- Maternal death
- Fetal injuries and laceration
- Fetal sepsis

119.6 Pearls and Pitfalls

- Pearls
  - Perimortem cesarean section, although rarely performed, should be considered in any maternal arrest when the fetus is greater than 24 weeks' gestation.
  - In addition to saving the life of the fetus, this procedure may aid in resuscitation of the mother. Emptying of the uterus may improve thoracic compliance and, therefore, improve maternal ventilation.
- Pitfalls
  - The decision to perform an emergency cesarean section must be made early. There is a higher chance of survival if performed no more than 5 min after the onset of maternal cardiac arrest.

Selected Reading

Doan-Wiggins L. Emergency childbirth. In: Roberts JR, Hedges JR, editors. Clinical procedures in emergency medicine. 4th ed. Philadelphia: Saunders; 2004. p. 1117–43.

Flippin A, Hendricks S. Perimortem cesarean section. In: Reichman EF, Simon RS, editors. Emergency medicine procedures. New York: McGraw Hill Medical; 2004. p. 1070–8.

Gianopoulos JG. Emergency complications of labor and delivery. Emerg Med Clin North Am. 1994;12:201–17.

Jeejeebhoy FM, Zelop CM, Windrim R, Carvalho JC, Dorian P, Morrison LJ. Management of cardiac arrest in pregnancy: a systematic review. Resuscitation. 2011;82:801–19.

Whitten M, Irvine LM. Postmortem and perimortem caesarean section: what are the indications? J R Soc Med. 2000;93:6–9.

Part XV

Common Pediatric Procedures

Peripheral Venous Catheterization

120

David N. Smith and Judith K. Lucas

120.1 Indications (See Also Chap. 2)

- Fluid resuscitation
- Medication administration
- Blood draws

120.2 Contraindications

- Relative
  - Avoid catheterizing areas of trauma in which extravasation of fluid is possible (e.g., burns, open wounds, or severe edema in tissue).
  - Avoid catheterizing in an area of local infection for risk of inoculating the circulation with bacteria (e.g., cellulitis).
- Absolute
  - None

120.3 Materials and Medications

- Gloves
- Skin disinfectant (isopropyl alcohol, chlorhexidine, or Betadine [povidone-iodine])
- Appropriate-sized catheter (18- to 24-gauge [IV]) (Fig. 120.1)
  - Large child: 18 to 20 gauge
  - Infant or small child: 22 to 24 gauge
- Tourniquet
- Sterile 2×2 gauze
- Appropriate-sized Tegaderm transparent dressing
- Adhesive tape
- IV bag with solution set (tubing flushed and ready) or saline lock
- Sharps container

D.N. Smith, MD
Department of Pediatrics, University of Alabama at Birmingham,
Children's of Alabama, Birmingham, AL, USA
e-mail: dsmith@peds.uab.edu

J.K. Lucas, MD (✉)
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: judithklucas@ufl.edu

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_120



Fig. 120.1 24-Gauge angiocatheter (*yellow*), 18-gauge angiocatheter (*red*), 20-gauge angiocatheter (*blue*)

120.4 Procedure

1. Comfortably position the patient with the site exposed.
2. Assemble the equipment and don a pair of (nonlatex) examination gloves.
3. Apply the tourniquet to the extremity above the site to be catheterized (Fig. 120.2).
4. Visualize and palpate the vein.
5. Cleanse the site with a disinfectant swab using an expanding circular motion.
6. Prepare and inspect the catheter and flush the tubing; be certain that the stylet and catheter separate easily, then fit again into the notch, aligning the bevel with the hub.
7. Stabilize the vein and apply countertension to the skin, being careful not to touch the cleansed area.
8. Insert the stylet through the skin and then reduce the angle while advancing through the vein (Fig. 120.3).
9. Observe for “flashback” as blood slowly fills the flashback chamber.
10. Advance the needle approximately 1–2 mm further into the vein, depending on the gauge and age of the patient, to ensure that the catheter is within the vein.
11. Slowly advance the catheter into the vein while keeping tension on the vein and skin (Fig. 120.4).
12. While advancing the catheter, be certain to hold the stylet portion with the thumb and forefinger, so as to avoid advancing the needle portion into and through the opposite side of the vessel, thus “blowing” the vein.
13. When the catheter is advanced about halfway, slowly withdraw and remove the stylet while simultaneously continuing to advance the catheter to its hub.
14. Attach a 3-mL non-Luer-Lok syringe to the hub.
15. Remove the tourniquet.
16. Gently attempt to aspirate blood. The blood should be free flowing.
17. Secure the catheter by either placing a transparent occlusive dressing (e.g., Tegaderm) over the lower half of the catheter hub or taping over the catheter hub in a cruciate

fashion, taking care not to cover the IV tubing connection (Fig. 120.5).

18. Remove the cover from the end of the IV tubing and insert the IV tubing into the hub of the catheter (the tubing must have been flushed with IV solution before connecting with the catheter hub: the unit from the solution bag/bottle through the catheter must be air free).
19. Open up the IV roller clamp and observe for drips forming in the drip chamber.
20. Place a piece of tape over the catheter hub then make a small (kink-free) loop in the IV tubing and place a second piece of tape over the first piece to secure the loop (Fig. 120.6).
21. Place a third piece of tape over the IV tubing above the site.
22. Ensure that the IV is properly secured and infusing properly.
23. Ensure that all "sharps" are placed in the sharps container.


Cephalic vein
Basilic vein
Accessory cephalic vein
Median cubital vein
Cephalic vein
Median antebrachial vein

Fig. 120.2 Anatomy of the volar surface antecubital fossa and forearm



Fig. 120.3 (**a**–**d**) After applying the tourniquet, palpate a vein, as straight as possible, and ideally without many "knots" (i.e., valves)



Fig. 120.4 With the tourniquet "up," and the vein distended, apply traction to the skin, pierce the skin, and pass the catheter tip (into the vein) until blood return is noted in the catheter hub



Fig. 120.5 (**a**–**d**) Securing the intravenous line utilizing the cruciate taping style



Fig. 120.5 (continued)



Fig. 120.6 Commercially available hub stabilizer, minimizing the need for excessive tape

120.5 Pearls and Pitfalls

- Pearls
  - Start catheter attempts distal in the extremities and move proximally with each subsequent attempt.
  - The use of ultrasound or a light source in infants can aid in location of the vessel and placement of the line.
  - In an emergent situation, in which fluids or medications are needed quickly, intraosseous access (see Chap. 122) can be obtained if venous catheterization fails.
- Pitfalls
  - The use of lidocaine subcutaneously can improve patient comfort, but it does disrupt anatomical landmarks.

Selected Reading

Bailey P. Vascular (venous) access for pediatric resuscitation and other pediatric emergencies. UpToDate. http://www.uptodate.com/contents/vascular-venous-access-for-pediatric-resuscitation-and-other-pediatric-emergencies. Accessed 23 June 2014.

Department of Emergency Medicine, University of Ottawa. Peripheral intravenous access. 2003. http://www.med.uottawa.ca/procedures/iv/. Accessed 23 June 2014.

Kost S. Ultrasound-guided vascular (venous) access. UpToDate. http://www.uptodate.com/contents/principles-of-ultrasound-guided-venous-access. Accessed 23 June 2014.

Nursing Resource Administration. Medical procedure: insertion of peripheral IV line. http://nursing-resource.com/iv-insertion/. Accessed 23 June 2014.

Umbilical Venous Catheters (Insertion and Removal)

121

Judith K. Lucas

121.1 Indications

- Temporary vascular access for infants up to roughly 10 days of life (between 7 and 14 days) with shock or cardiopulmonary failure
- Emergency vascular access in this age group, when peripheral intravenous (IV) access cannot be rapidly obtained
- Preferred vascular access in infants less than 1000 g

121.2 Contraindications

- Omphalitis
- Omphalocele
- Necrotizing enterocolitis
- Peritonitis

121.3 Materials and Medications

- Anesthetic: not necessary; procedure is painless
- Soft ties to restrain infant's extremities
- Sterile gloves/gowns
- Antiseptic solution
- Sterile towels/drapes
- 3.5- (infants <1500 g) or 5-French (>1500 g) umbilical venous catheter
- 5-French feeding tube
- Three-way stopcock
- 10-mL syringe with heparinized saline flush (1 U/mL)
- Umbilical tape or 3-0 silk on a cutting needle
- Non-toothed forceps
- Small hemostats (2)
- #11 scalpel and blade
- Scissors
- Graph depicting length of catheter insertion, if placing umbilical venous catheter (UVC) above the diaphragm in either very small infants or infants for whom measurement of central venous pressure (CVP) is indicated (Fig. 121.1)

J.K. Lucas, MD
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: judithklucas@ufl.edu

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_121


a
COTTON UMBILICAL TAPE
ETHICON
b
Vessel Catheter
Single Lumen
5 Fr/Ch (1.7 mm) x 15" (38.1 cm)
Cathéter ombilical en polyuréthane
Une lumière
Rx
Polyurethane Umbilical Vessel Catheter
Single Lumen
3.5 Fr/Ch (1.2 mm) x 15" (38.1 cm)
Cathéter ombilical en polyuréthane
Une lumière

Fig. 121.1 (**a**) Instrumentation suggested for umbilical venous catheter placement. (**b**) Umbilical venous catheters (in an emergency, 5 F feeding tube is an acceptable alternative)

121.4 Procedure (Insertion)

1. Place the infant under a radiant warmer.
2. Using soft ties, restrain the infant's extremities.
3. Scrub the umbilicus and surrounding abdomen with antiseptic solution.
4. Drape the umbilicus and area in sterile manner (leave the infant's head exposed).
5. Tie a loose loop with the umbilical tape around the base of the cord OR run the 3-0 silk through the skin *of the cord* in a purse-string fashion.
    - This will be used later to anchor the line after placement and to provide hemostasis should the line accidentally be pulled out and bleeding ensue.
6. Using the scalpel blade, cut the umbilical cord horizontally approximately 2 cm above the junction between the cord and the skin.
7. Identify the umbilical vessels
    - The vein is thinner walled, larger in diameter, and somewhat floppy appearing, relative to the umbilical arteries, and typically located at the 12 o'clock position.
    - The arteries are smaller, thick walled, and paired (a single umbilical artery often signifies the presence of a congenital malformation/syndrome) and located at the 4 and 8 o'clock positions (Fig. 121.2).
8. Place the stopcock on the receiving end of the umbilical catheter or the 5-French feeding tube and flush with heparinized saline solution, and then close the stopcock.
    - It is imperative that there is no air in the catheter.
9. Introduce a closed smooth-surfaced forceps into the lumen of the umbilical vein and allow the forceps to separate, allowing the vein to dilate (Fig. 121.3).
10. Insert the catheter (or feeding tube) into the lumen and gently advance, directing the catheter toward the right shoulder (Fig. 121.4).
11. Advance the catheter only until good blood flow is noted and then another 1 to 2 cm (this should be a total of only 4–5 cm in a term infant).
    - *Do not force the advancement.*
    - At this level the tip of the catheter should still be inferior to the liver (Fig. 121.5).
12. Tighten the umbilical tie or the purse-string suture.
13. Secure the catheter with a tape bridge (Figs. 121.6, 121.7, and 121.8).
14. Although if placed only up to point of blood return, the catheter tip should be below the liver; it is best to get an abdominal x-ray to confirm; many solutions are caustic to the liver and can result in complications.



Fig. 121.2 Anatomy of the umbilical cord when cut transversely approximately 2 cm from abdominal wall



Fig. 121.3 Sterilely draped umbilicus, with umbilical tape loosely tied at base of umbilical cord. This tie will be cinched and secured once the catheter is placed, but meanwhile, can assist with homeostasis should the catheter be inadvertently dislodged during placement. Gently dilate the umbilical vein with a smooth toothed forceps. Insert the distal most couple of mm of a closed forceps into umbilical vein and relax, so the forceps tips smoothly separate



Fig. 121.4 Gently pass the umbilical venous catheter (or 5 F feeding tube) until there is easy blood return



Fig. 121.5 Once there is easy blood return, pass the catheter an additional 1–2 cm. The catheter should still be inferior to the liver at this point



Fig. 121.6 Creating an umbilical catheter tape bridge: the uprights



Fig. 121.7 Umbilical tape catheter bridge: the "cross bar" secures the catheter without applying tape to the umbilical stump



Fig. 121.8 Fold the catheter over to create a "U." Be careful not to kink the catheter, and secure with a second taped cross bar to lend additional security to the catheter and prevent displacement

121.5 Procedure (Removal)

1. The UVC should be removed as soon as adequate peripheral venous access is obtained (unless in an infant estimated to weigh <1000 g).
2. Turn infusions off.
3. Be certain the stopcock is closed to the infant.
4. It is imperative that there be no air in the catheter before withdrawal (if air is present and infant takes inspiration, the negative pressure generated can pull significant amount of air into the central vasculature).
5. Remove the securing tape from the infant.
6. Withdraw the catheter gradually as a single maneuver.

121.6 Complications

- Infection
- Bleeding due to disconnection of tubing (*always use Luer-Lok connections*) or perforation of vessels
- Arterial injury by accidental perforation
- Hepatic injury and necrosis if the catheter sits within a portal vein
- Thrombosis
- Air embolus
- Dysrhythmia or pericardial tamponade or perforation if catheter is advanced too far

121.7 Pearls and Pitfalls

- Pearls
  - The umbilical vein is 2–3 cm long before it widens into the umbilical recess, just before intersecting with the left portal vein and the ductus venosus.
  - Be certain to include the length of the umbilical stump in any calculations for placement.
  - If using the calculating graph, measure from the right shoulder to the umbilicus (Fig. 121.9).
- If choosing the above-diaphragm site for placement, corkscrewing the catheter clockwise while passing the catheter will encourage it to pass through the ductus venosus.
  - A kidney, ureter, and bladder study is mandatory in high UVC placement.
- Pitfalls
  - When preparing with Betadine (povidone-iodine), be certain to wipe away and remove any pooled Betadine along the infant's side because this will cool the infant initially; as the Betadine is warmed, it becomes highly irritating to newborn skin.



Fig. 121.9 Graph for estimation of insertion distance of the catheter; be certain to add the length (cm) of the umbilical stump to the insertion distance

Selected Reading

Sudbury, Jones, Bartlett. Emergency vascular access. In: APLS: the pediatric emergency medicine resource. 5th ed., p. 741.

Magnan JP. Umbilical Vein Catheterization. http://emedicine.medscape.com/article/80469-overview.

Schlesinger AE, Braverman RM, DiPietre MA. Neonates and umbilical venous catheters: normal appearance, anomalous positions, complications, and potential aid to diagnosis. Presented at the 2001 annual meeting of the American Roentgen Ray Society, Seattle, Apr 2001.

Intraosseous Access

122

Judith K. Lucas

122.1 Indications

- During cardiac arrest: Failure to attain vascular access after three peripheral intravenous attempts or 90 s, whichever comes first
- Inability to gain vascular access in pediatric patients presenting in shock due to hemorrhage (trauma), sepsis, profound dehydration, or cardiac failure

122.2 Contraindications

- Absolute
  - Fracture of the long bone considered for intraosseous (IO) access
- Relative
  - Previous IO access attempt in the same long bone
  - Cellulitis over the insertion site
  - Inferior vena cava injury (circulatory access proximal to the injury site is preferred).
  - Osteogenesis imperfecta

122.3 Materials and Medications

- Preparation materials, such as an antiseptic solution and sterile drapes, IF the patient's stability offers the time.
- Lidocaine without epinephrine: If it becomes necessary to place an IO in a conscious patient, use lidocaine to anesthetize the skin to the bony cortex; then once accessed, infiltrate 2–3 mL into the marrow to alleviate some of the pain of medications infusing through the marrow.
- IO needle (a few examples shown) (Figs. 122.1, 122.2, and 122.3).



Fig. 122.1 Jamshidi disposable sternal/iliac aspiration needle (Jamshidi, Cardinal Health Dublin, OH)

J.K. Lucas, MD
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: judithklucas@ufl.edu

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_122



Fig. 122.2 Cook intraosseous needle (Cook Critical Care, Bloomington, IN)



Fig. 122.3 EZ-IO (Vida-Care, San Antonio, TX)

122.4 Procedure

- Most common site: proximal tibia
  1. Patient should be supine, with the intended leg slightly externally rotated and flexed at the hip. Flex the knee about 90°.
  2. Place a towel underneath the knee and the proximal lower leg.
  3. Palpate the tibial tuberosity. Then move fingers 2 cm distal to the tuberosity (1–2 fingerbreadths) and 2 cm medial. This area is consistently flat and is distal to the growth plate (Figs. 122.4 and 122.5).
  4. If the patient is stable, create a sterile field focused on the insertion site.
  5. Insertion site should be cleaned with an antiseptic solution.
  6. Pass the needle through the skin and subcutaneous tissue to the cortex.
  7. Once bone is reached, stabilize the IO with the thumb and first fingers adjacent to where the needle penetrates the skin.
  8. Apply steady and firm pressure downward and with a twisting motion (back and forth) with the palm on the end of the device. Although inserting the needle perpendicularly to the bone is totally acceptable, ideally angling the needle caudally slightly (~15°) will avoid the growth plate (Fig. 122.6).
  9. As the cortex is fully penetrated indicating entrance into the marrow space, one *may* feel an ease in resistance. Do not advance the needle further. The needle should be able to stand up without support.
  10. Remove the inner trocar (Fig. 122.7).
  11. Attempt to aspirate marrow/blood. Not being able to do so DOES NOT mean inadequate or inaccurate placement. Instead, if marrow cannot be aspirated, affix a 10-mL syringe with normal saline and attempt to infiltrate. Resistance to flow should be minimal, and one should not appreciate either extravasation around the insertion site, coolness, or tissue expansion posterior to the site (indicating the fluid is passing through the IO).

12. Once placement is confirmed, connect an intravenous line, using a three-way stop-cock.
13. Secure the needle with tape and gauze (Fig. 122.8).

- Alternative sites
  - – Distal tibia
    - The landmarks are the medial aspect of the tibia (the flat portion), 2 fingerbreadths proximal to the medial malleolus.
    - Again, externally rotate and abduct the hips, with the knee flexed about 60° (as with the proximal tibia).
    - Angle the needle toward the knee (cephalad) about 10–15° to avoid the distal tibia growth plate.
    - The remainder of the IO insertion is identical to the procedure for proximal tibia placement.
  - – Distal femur
    - Slightly flex and externally rotate the hip.
    - Flex the knee enough that the quadriceps muscle group is relaxed.
    - The landmarks for the distal femur are the anterior thigh, midline, about 3 fingerbreadths proximal to the medial and lateral condyles.
    - The IO is inserted perpendicular to the bone (because there is no growth plate in the distal femur other than the condyles).
    - The remainder of the procedure is identical to the procedure for placement in the proximal tibia.
  - – Proximal humerus (Fig. 122.9)
    - The patient should be supine, with the shoulder, upper arm, and elbow as close to the body as possible, yet still on the bed. The elbow should be flexed at 90°, with the forearm and palm resting on the patient's abdomen.
    - The provider slides his or her thumb up the anterior shaft of the humerus toward the shoulder until the greater humerus tubercle is palpated, which identifies the surgical neck of the humerus.
    - The insertion site is perpendicular to the humerus, approximately 1–2 fingerbreadths proximal to the tubercle.
    - The remainder of the insertion is identical to that for the proximal tibia.
  - – Sternum (not usually recommended for small children).
    - Requires a special IO needle and system.
    - Method of placement is specific to the insertion system chosen.
    - Manubrium is the desired site (as opposed to the body of the sternum, which would interfere with cardiopulmonary resuscitation).
    - Risks specific to sternal placement include pneumothorax, mediastinitis, and great vessel injury.



Fig. 122.4 Step 1. Identify the tibial tuberosity



Fig. 122.5 Step 2. One to 2 fingerbreadths below the tuberosity and medially, to the flat aspect of the proximal tibia


09/10/2011 00:36

Fig. 122.6 Step 3. Angle the device slightly caudal to avoid growth plate


09/10/2011 00:37

Fig. 122.7 Step 4. Uncap the top of the device and remove the trocar


09/10/2011 00:40

Fig. 122.8 Step 5. Stabilize the intraosseous cannula



Fig. 122.9 IO insertion into proximal humerus site

122.5 Complications

- Extravasation of fluid.
  - Occurs as a result of a misplaced IO, either not completely in the marrow space anteriorly or through the cortex posteriorly.
  - Tissue necrosis.
- Compartment syndrome if extravasation is not recognized.
- Fracture and growth plate injury.
- Infection and osteomyelitis are rare complications if sterile technique is used.
- Fat embolism, considered rare and only in adult patients.

122.6 Pearls and Pitfalls

- Be certain to avoid placing a hand beneath the IO site during placement in order to prevent possible IO penetration into the provider's tissue.
- Do not rely on the sensation of a "pop" to determine appropriate penetration into the cortex, especially in infants.
- Likewise, one may not be able to aspirate bone marrow or blood, even with an appropriately placed IO. DO NOT pull out the IO if marrow cannot be aspirated. Rather, gently but firmly infiltrate 10 mL normal saline.
- Blood gases, body chemistries, and blood typing can be obtained from IO samples, but the sample CANNOT be used for hematocrit determination.

Selected Reading

Bohn D. Intraosseous vascular access: from archives to the ABC. Crit Care Med. 1999;27:1053.

DeCaen AR, Reis A, Bhutta A. Vascular access and drug therapy in pediatric resuscitation. Pediatr Clin North Am. 2008;55:909–27.

Deitch K. Intraosseous infusion. In: Roberts JR, Hedges JR, editors. Clinical procedures in emergency medicine. 5th ed. Philadelphia: Saunders; 2009. Chap. 25.

EMS World. Intraosseous infusion: not just for kids anymore. Posted Jan. 12, 2011. Updated from Mar 2005. EMSWorld.com. Cygnus Business Media Site.

Halm B, Yamamoto LG. Comparing ease of intraosseous needle placement: Jamshidi versus Cook. Am J Emerg Med. 1998;16:420.

Lumbar Puncture in Pediatrics

123

Maritza A. Plaza-Verduin and Judith K. Lucas

123.1 Indications

- Evaluation of cerebrospinal fluid (CSF) for infection or malignancy
- Measurement of opening pressure
- Treatment of pseudotumor cerebri
- Diagnosis of central nervous system (CNS) metastases
- Instillation of intrathecal chemotherapy
- Injection of radiopaque dye for spinal cord imaging

123.2 Contraindications

- Increased intracranial pressure
- Bleeding diathesis (platelet count <50,000)
- Overlying skin infection near the area of puncture site
- Spinal cord trauma or spinal cord compression
- Signs of progressive cerebral herniation
- Condition of the patient (e.g., unstable airway, potentially dangerous breathing problem, severe circulatory instability) that could cause an abrupt decompensation
- Known spinal cord deformity

123.3 Materials and Medications

- Lumbar puncture (LP) tray (Fig. 123.1)
  - Sterile drapes
  - Betadine (povidone-iodine) swabs or tray to pour Betadine
  - Sterile sponges for preparing the puncture site
  - Sterile 3-mL syringe with needle for lidocaine injection
  - Sterile collecting tubes (4)
  - Sterile spinal needle with stylet (size depending on age of patient)
    - Premature infant: 22 gauge or smaller, 1.5 inch
    - Neonate to 2 years: 22 gauge, 1.5 inch
    - 2–12 years: 22 gauge, 2.5 inch
    - Older than 12 years: 20 or 22 gauge, 3.5 inch
  - Pressure manometer column with a three-way stopcock
- Betadine solution
- Sterile gloves
- Mask
- Lidocaine (1–2 % without epinephrine)
- 4 % Lidocaine cream (LMX-4) or lidocaine and prilocaine mixture (EMLA [eutectic mixture of local anesthetics])

M.A. Plaza-Verduin, MD
Pediatric Division, Department of Emergency Medicine, Arnold Palmer Hospital for Children, Orlando, FL, USA
e-mail: mari.plazav@gmail.com

J.K. Lucas, MD (✉)
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: judithklucas@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_123



Fig. 123.1 Lumbar puncture (LP) tray

123.4 Procedure

1. Position the child (Figs. 123.2 and 123.3).
    (a) Can be positioned in either the sitting or the lateral recumbent position with the hips, knees, and neck flexed.
    (b) For small infants or any patient with any degree of cardiorespiratory compromise, keep close monitoring of heart rate, respirations, and oxygen saturation while in the flexed position.
2. Palpate the top of the iliac crest and draw an imaginary line connecting the two across the back, which should cross the midline just above the fourth lumbar spine (Fig. 123.4).
3. Palpate L3–4 or L4–5 space along this line.
4. Place EMLA or LMX-4 on the area at this time and allow some time for anesthesia to occur (can take up to 30 min to be effective).
5. Prepare the skin in sterile fashion with Betadine solution using enlarging circles that begin at the puncture site.
6. Drape the patient with sterile towels, exposing the puncture site.
    (a) If an infant, do so conservatively to be able to monitor the infant during the procedure.
7. Locate the intervertebral space (L3–4 or L4–5) once again.
    (a) Make a small mark on the chosen intervertebral space with a fingernail depression or the plastic cap of the spinal needle.
8. If desired, or if anesthetic cream was not previously used or more is needed, apply a small wheal of lidocaine at the desired puncture site using a 25-gauge needle.
9. Insert the spinal needle in the intervertebral space.
    (a) Puncture the skin in the midline just caudal to the palpated spinous process.
    (b) Bevel should be positioned so that the dura mater is pierced parallel to its fibers (which will reduce the likelihood of CSF leakage).
        (i) If in the lateral recumbent position, the bevel of the needle should be positioned horizontally.
        (ii) If in the sitting position, the bevel of the needle should be positioned vertically.
        (iii) Angle the needle slightly cephalad toward the umbilicus and parallel to the bed if the patient is in the lateral recumbent position or slightly caudal (perpendicular to the skin) if the patient is in the sitting position.
10. Advance the needle several millimeters at a time and withdraw the stylet frequently to check for CSF flow.
    (a) Advance the needle until a loss of resistance is felt or approximately 1–2 cm.
        (i) In the infants, whose dura are not so thick and a “pop” or give may be unnoticeable, after passing between the spiny processes and approximately 2 cm through the skin, remove the stylet frequently to check for CSF return. This will allow you to avoid passing through the subarachnoid space.
        (ii) After the change in resistance occurs, if resistance is met again, pull back gently on the needle to reposition in the subarachnoid space and remove the stylet to check for CSF fluid.
11. Once CSF is free flowing, attach a pressure manometer to the needle hub via the three-way stopcock (Fig. 123.5).
    (a) Make sure to hold the spinal needle with one hand in place while attaching the manometer to prevent movement of the needle.
    (b) Measure the CSF pressure once the CSF reaches the highest level in the manometer column.
    (c) CSF pressures will be best obtained in the lateral recumbent position with the neck and legs extended.
    (d) Normal CSF pressure is 5–20-cm H_2O with the neck and legs extended, 10–28-cm H_2O with the neck and legs flexed.
    (e) Have an assistant hold the top of the pressure manometer while the spinal needle is supported at the connection of the manometer and stopcock.
12. Remove the manometer and collect the CSF into sterile tubes.
    (a) Make sure to keep the needle in place when removing the manometer.
    (b) Continue to drain fluid into the collecting tubes, approximately 1 mL per tube.
    (c) The tubes should be labeled for specific studies, depending on the order of collection.
        (i) First tube for gram stain and culture.
        (ii) Second tube for quantitative glucose and protein.
        (iii) Third or fourth tube for cell count and differential.
        (iv) Leftover tube for any additional studies that may be needed.
        (v) When the LP is to assess for possible subarachnoid blood, the first and fourth tubes are sent for cell count.
13. Replace the stylet and remove the spinal needle.
14. Cleanse the puncture area to avoid staining with the Betadine solution.
15. Apply a sterile dressing to the puncture site.
16. Patients 4 years and older should remain in the supine position, with the head elevated no more than the height of a pillow (for comfort), for at least an hour to avoid spinal tap headaches.
17. Likewise, after the LP, giving a fluid bolus of normal saline (10–20 mL/kg in children; 1 L in non-volume-sensitive adults) will also assist with avoidance of spinal tap headaches.



Fig. 123.2 Curling up for an LP



Fig. 123.3 Having the LP


Level of posterior superior iliac crests
Puncture site (L4–5 interspace)
L5
L4
L3

Fig. 123.4 Anatomy of the lumbar spine showing the sites for dural puncture



Fig. 123.5 Pressure manometer attached to the needle hub via the three-way stopcock

123.5 Complications

- Minor
  - Localized back pain
  - Transient paresthesia during procedure
  - Post-LP headache
- Major
  - Severe back pain associated with neurological signs (may be subdural or epidural spinal hematoma)
  - LP-induced meningitis
  - Cerebral herniation
  - Acquired epidermoid tumor
  - Damage to adjacent structures (disk herniation, retroperitoneal abscess, spinal cord hematoma)

123.6 Pearls and Pitfalls

- Pearls
  - Success of the LP depends on the positioning of the patient.
    - Goal of positioning is to stretch the ligamentum flavum and increase the interlaminar spaces.
    - In the recumbent position, the shoulder and hips should be perpendicular to the bed, keeping the spinal cord straight, with no rotation.
    - Sitting position is useful with older, cooperative patients or with very young infants who are unlikely to struggle and may have increased respiratory distress in the lateral recumbent position.
  - Administration of an anxiolytic (e.g., midazolam) can be used to facilitate the procedure in an older child. In some cases, procedural sedation may be required.
  - Placing the tip of the thumb on the spinous process just above the space being entered can ensure good alignment of the needle.
  - In older patients a “pop” may often be felt as a change in resistance occurs once the dura is penetrated; however, in infants and neonates, that “pop” may be exceedingly subtle or not palpable.
  - If no CSF returns, attempt the following options:
    - Ensure the needle is in the appropriate position, withdrawing the needle slowly if necessary.
    - Rotate the needle 90°.
    - If an infant, have the assistant massage the anterior fontanel to help facilitate CSF flow.
    - If the procedure continues without CSF, withdraw the needle to just under the skin and redirect it.
    - If the procedure continues without CSF, withdraw the needle and insert a new needle with stylet at an alternate site.

    - If these steps do not yield CSF, the infant may be dehydrated, not allowing for adequate CSF flow.
      - Give the patient a bolus and reattempt later.
      - Attempt putting the infant in a sitting position to increase flow.
- Pitfalls
  - Traumatic LP
    - Bloody CSF fluid, which usually clears as the CSF drains if the needle is in the correct space.
    - Occurs with improper technique (inserting the needle too far to one side into an epidural venous plexus or through the subarachnoid space into or adjacent to the vertebral body).
    - Can occur with proper technique as well.
    - If fluid does not clear and clots form in the tubes, LP should be reattempted at a different site.
  - Failed LP attempts despite proper procedure and positioning
    - Ultrasound can be used to visualize the area and determine the reason for failure or the likelihood of success with future attempts.

Selected Reading

Coley BD, Shiels WE, Hogan MJ. Diagnostic and interventional ultrasonography in neonatal and infant lumbar puncture. Pediatr Radiol. 2001;31:399–402.

Cronan KM, Wiley JF. Lumbar puncture. In: King C, Henretig FM, editors. Textbook of pediatric emergency procedures. 2nd ed. New York: Lippincott Williams & Wilkins; 2008.

Ebinger F, Kosel C, Pietz J, Rating D. Headache and backache after lumbar puncture in children and adolescents: a prospective study. Pediatrics. 2004;113:1588–92.

Friedman AG, Mulhern RK, Fairclough D, et al. Midazolam premedication for pediatric bone marrow aspiration and lumbar puncture. Med Pediatr Oncol. 1991;19:499–504.

Partin WR. Emergency procedures. In: Stone CK, Humphries RL, editors. Current diagnosis & treatment: emergency medicine. 6th ed. New York: McGraw-Hill; 2007.

Suprapubic Bladder Aspiration

124

Maritza A. Plaza-Verduin and Judith K. Lucas

124.1 Indications

- Collection of sterile urine for urinalysis and culture (avoiding urethral contamination)
- Collection of sterile urine in a child with gastroenteritis and frequent diarrheal stools
- Female child with labial adhesions or male child with minimally retractable foreskin
- Urinary retention

124.2 Contraindications

- Empty or nonpalpable bladder
- Urination within 1 h before the procedure
- Anatomical abnormalities of the gut or genitourinary tract
- Bleeding diathesis
- Intestinal obstruction
- Overlying cellulitis on abdominal wall
- Lower abdominal scars or wounds

124.3 Materials and Medications

- Sterile gloves
- Lidocaine (1–2 %) with syringe and needle
- EMLA (eutectic mixture of local anesthetics) cream
- Betadine (povidone-iodine) solution
- Sterile syringe, 5–20 mL
- Sterile needle 22 or 23 gauge, 1.5 inch
- Sterile specimen container
- Sterile towels
- Sterile gauze
- Sterile dressing
- Adhesive bandage

M.A. Plaza-Verduin, MD
Pediatric Division, Department of Emergency Medicine,
Arnold Palmer Hospital for Children, Orlando, FL, USA
e-mail: mari.plazav@gmail.com

J.K. Lucas, MD (✉)
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: judithklucas@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_124

124.4 Procedure

1. Place the infant in the supine, frog-leg position (Fig. 124.1).
2. Localize the bladder.
3. Palpate the midline between the umbilicus and the pubis symphysis to feel for bladder fullness.
    - Use a portable ultrasound device to localize the bladder and allow for approximation of bladder size (see later).
4. Localize the symphysis pubis and the imaginary line midline from the umbilicus to the pubic symphysis (Fig. 124.2).
5. Sterilize the area from the umbilicus to the urethra.
6. Drape the area with sterile towels, keeping the puncture site area exposed.
7. Area of insertion should be midline 1–2 cm above the symphysis pubis on the abdominal wall.
    - The suprapubic crease can usually be used as a guideline to the puncture site.
8. Place a small wheal of anesthetic at the intended puncture site or can apply EMLA cream.
    - For use of EMLA cream, place before sterilization and allow some time for anesthesia to occur.
9. Occlude the urethral opening to avoid spontaneous loss of urine specimen.
    - In males, apply gentle pressure to the base of the penis against the pubic symphysis.
    - In females, directly apply pressure to the urethral meatus.
10. Puncture the skin with the needle (attached to the syringe).
    - Puncture at a 10–20° angle to the perpendicular, aiming slightly cephalad (Fig. 124.3).
11. Apply negative pressure to the syringe as the needle is advanced until urine enters the syringe; do not advance more than 1 inch.
    - If unsuccessful, draw back the needle until it rests in the subcutaneous fat and redirect 10° in either direction.
    - Do not attempt more than three times.
12. Cleanse the area of antiseptic solution and apply an adhesive dressing.



Fig. 124.1 Frog-leg position


Umbilicus
Suprapubic crease and puncture site

Fig. 124.2 Landmarks



Fig. 124.3 Insert the needle 10–20° perpendicular to the skin

124.5 Complications

- Peritoneal perforation with or without bowel perforation
- Infection
- Hematuria
- Inability to aspirate urine

124.6 Pearls and Pitfalls

- If no fluid is obtained:
  - Hydrate the child and reattempt in 1 h.
- Ultrasound can be used to identify bladder size or for ultrasound-guided aspiration:
  - Use a portable ultrasound device with a standoff 7.5-MHz sector probe to allow for superficial scanning and measurement of the diameter of the bladder.
  - Bladder diameter measurement:
    1. Apply approximately 5 mL of ultrasound transmission gel to the infant's suprapubic region.
    2. Apply pressure to the ureteral meatus as previously described.
    3. Gently apply the probe to the suprapubic region in the midline and scan the area in transverse plane, with the probe directed caudad or cephalad as needed to maximize bladder image.
       - Bladder will appear anechoic below the brighter reflections of the rectus muscle and bladder wall.
    4. When maximum bladder size obtained, freeze the image.
       - Measure the anteroposterior and transverse internal bladder diameters.
       - Goal measurement is 2 cm or more of each diameter. If either diameter is less than 2 cm, the bladder is considered to be empty.
  - Ultrasound-guided bladder aspiration:
    1. After preparing the sterile field, place a sterile sheath over the ultrasound probe and proximal cable.
       (a) Gel should be placed within the sheath to eliminate the air interface between the probe and the sheath.
    2. Apply gel to the abdomen above the symphysis pubis.
    3. Locate the bladder and measure the maximum diameter as described previously.
    4. Insert the needle midline at the location where the bladder wall is closest to the probe.
    5. Continue steps for aspiration as described previously.

Selected Reading

Kozer E, Rosenbloom E, Goldman D, et al. Pain in infants who are younger than 2 months during suprapubic aspiration and transurethral bladder catheterization: a randomized, controlled study. Pediatrics. 2006;118:e51–6.

Leong Y, Tang KW. Bladder aspiration for diagnosis of urinary tract infection in infants and young children. J Singapore Paediatr Soc. 1976;18:43–7.

Loiselle JM. Ultrasound-assisted suprapubic bladder aspiration. In: King C, Henretig FM, editors. Textbook of pediatric emergency procedures. 2nd ed. New York: Lippincott Williams & Wilkins; 2008.

Pollack CV, Pollack ES, Andrew ME. Suprapubic bladder aspiration versus urethral catheterization in ill infants: success, efficiency and complication rates. Ann Emerg Med. 1994;23:225–30.

Polnay L, Fraser AM, Lewis JM. Complication of suprapubic bladder aspiration. Arch Dis Child. 1975;50:80–1.

Removal of Hair/Thread Tourniquet

125

Judith K. Lucas

125.1 Indications

- Consider the diagnosis when presented with an appendage that has a well-demarcated, circumferential, painful, edematous distal segment, adjacent to a nonedematous, nonerythematous proximal portion (Fig. 125.1).
- Removal is imperative in all cases of tourniquet syndrome and should be undertaken without delay.
- Method of removal is determined by degree of constriction.
  - Unwrapping: in situations with minimal or no edema and the ability to visualize the offending hair or thread
  - Blunt probe, cutting: mild to moderate edema
  - Incision: severe swelling or inability to visualize the constricting band; epithelialization
  - Depilatory: for areas with mild to moderate edema, but without epithelialization



Fig. 125.1 Hair tourniquet

J.K. Lucas, MD
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: judithklucas@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_125

125.2 Contraindications

- Absolute
  - There are no absolute contraindications; the tourniquet must be removed.
- Relative
  - Based more on the specific approach (e.g., avoid incising the skin of a patient with hemophilia; avoid depilatory creams in a patient with known allergies to such)

125.3 Materials and Medications

- Unraveling technique
  - Fine-tipped, non-rat-tooth forceps or small fine hemostats
- Blunt probe and tourniquet cutting
  - Antiseptic solution of choice
  - Lidocaine 1 % without epinephrine for local or regional anesthesia
  - Scalpel blade #11 or Iris scissors
  - Blunt probe or metal earwax curette
- Incision technique
  - Antiseptic solution of choice
  - Lidocaine 1 % without epinephrine for local or regional anesthesia
  - Scalpel blade #11
  - Fine-tipped, non-rat-tooth forceps or small, fine hemostats
- Depilatory technique
  - Commercial depilatory cream

125.4 Procedures

- Unraveling method (Fig. 125.2)
  1. Place the appendage in an orientation that maximizes exposure.
  2. Apply skin traction such that as much of the tourniquet and base of the constriction can be seen.
  3. Look closely to identify a free end of the hair or thread. If no free end is visible, identify an area of bunching or a knot. Break the knot from the strand and grasp the end with the forceps or hemostat.
  4. Slowly and gently pull and unwind the hair.
  5. This may take several attempts because the hair strand or thread may break repeatedly during removal. Sometimes more than one hair strand may be involved.
- Blunt probe and cutting method (Figs. 125.3 and 125.4)
  1. Apply gentle traction to the skin to maximally expose the involved area and to make the base of the wedge caused by the tourniquet as shallow as possible.
  2. Gently impose a blunt probe or a metal ear curette between the skin and the tourniquet, starting proximally to the band and sliding distally beneath the constriction.
  3. Cut the tourniquet by sliding the scalpel blade along the edge of the probe, placing the blunt edge of the scalpel against the skin and slicing the constricting material in a movement away from the skin, in order to avoid inadvertently cutting the skin.
  4. Once an end of the tourniquet has been created, the remainder of the offending strap can be removed via unraveling.

- Incision technique for digits (Fig. 125.5)
  1. Perform a digital nerve block to anesthetize the extremity proximal to the constriction.
  2. Sterilize the involved area with antiseptic solution of choice and drape in typical protocol to allow as sterile a procedure as is possible outside a surgical suite.
  3. Incise the skin across the demarcation indicating the presence of the tourniquet at the 3 o'clock or 9 o'clock position or the midline dorsal area (12 o'clock), passing the scalpel blade proximally to distally and down to the bone (Fig. 125.6). Incision at these locations will avoid the laterally located neurovascular bundles of the digits.
- Incision technique for severe penile tourniquet
  1. Begin with a dorsal nerve block (Fig. 125.7).
  2. Sterilize the involved area with antiseptic solution of choice and drape in typical protocol to allow as sterile a procedure as is possible outside a surgical suite.
  3. A longitudinal incision is made at either the 4 o'clock or the 8 o'clock position, in order to avoid the penile neurovascular structures located dorsally.
  4. The incision should be made perpendicular to the tourniquet, but shallowly, in order to avoid penetration through the deep fascia. It will be necessary to repeat the incision, staying within the original incision, gently but repeatedly in order to cut through the whole tourniquet. In this way the constriction is relieved, but the integrity of the corpus cavernosum and the corpus spongiosum is maintained (Fig. 125.8).
  5. Once the layers of the tourniquet have been interrupted, grasp an end of the hair/thread and remove the remainder of the tourniquet utilizing the unraveling method.
- Depilatory method
  1. Depilatories work only on hair and will not work on threads.
  2. Apply the depilatory cream directly to the hair tourniquet with a saturated cotton swab, so as to avoid applying this potential irritant to surrounding tissue.
  3. Wait the recommended amount of time, as dictated by whatever brand of depilatory is used.
  4. After the appropriate time has elapsed, wash off the cream thoroughly with soap and water.



Fig. 125.2 A good example for use of the unraveling technique. The edema is minimal and the hair is easily identifiable

Fig. 125.3 Blunt and cut method. Notice the cutting edge of the scalpel blade is away from the skin as it is placed adjacent to the probe and slips beneath the tourniquet


Hair tourniquet
Blunt probe



Fig. 125.4 Blunt and cut method


Dorsal alternate approach
3 o'clock incision extended to bone
9 o'clock

Fig. 125.5 Incision technique for digits


Dorsal alternate approach

Fig. 125.6 Incision at 12 o'clock preferred



Fig. 125.7 Dorsal nerve block


Superficial dorsal veins
Deep dorsal vein, artery, and nerve
Lateral superficial vein
Corpus cavernosum
Corpus spongiosum
Urethra

Fig. 125.8 Penile tourniquet schematic

125.5 Complications

- Necrosis of tissue distal to the tourniquet
- Neurovascular damage secondary to prolonged ischemia
- The incision technique can cut into the tendon insertions or neurovascular bundles of the digits or into the corpus callosum of the penis. Be certain to ascertain function after incision.
- Infection, especially after incision.

125.6 Pearls and Pitfalls

- Pearls
  - All tourniquets must come off.
  - The easiest way to get to the bottom of the tourniquet, regardless of method used, is to identify the knot or bunched area if possible.
  - When using the incision technique, keep the incision in the longitudinal plane of the appendage and perpendicular to the tourniquet.
  - Do not use depilatories on open wounds.
  - 24-h follow-up is mandatory, although if the tourniquet has been present for an extended period of time, it may actually take several days for return of color and blood flow.
  - Be certain to document neurovascular status before and after tourniquet removal.
  - Consider surgical consult in cases of severe tissue edema or distorted anatomy.
  - Tourniquets have been described in the child abuse literature. Consider that possibility in the preverbal child.
- Pitfalls
  - The depilatories will not work on nonorganic tourniquets.

Selected Reading

Bothner J. Hair entrapment removal techniques. UpToDate. Accessed 30 Nov 2010.

Cardriche, D. Hair tourniquet removal. Medscape reference: drugs, diseases, and procedures. Available at: http://emedicine.medscape.com/article/1348969-overview. Accessed 17 May 2009.

Klusmann A. Tourniquet syndrome—accident or abuse? Eur J Pediatr. 2004;163:495–8.

Lundquist ST, Stack LB. Genitourinary emergencies: diseases of the foreskin, penis, and urethra. Emerg Med Clin North Am. 2001;19:529–46.

Peleg D, Steiner A. The Gomco circumcision: common problems and solutions. Am Fam Physician. 1998;58:891–8.

126

Use of the Broselow Tape

Judith K. Lucas

126.1 Indications

- To determine the equipment size and the medication doses during a pediatric resuscitation, without having to take the time to perform calculations

126.2 Contraindications

- Premature infant or newborn whose heel, while the infant is fully extended, does not fall at least into the white area (corresponding to 3, 4, and 5 kg).
- The length of the child exceeds the distal end of the green area (36 kg).

126.3 Materials

- Broselow Pediatric Emergency Tape (Armstrong Medical Industries, Wilshire, IL) (Figs. 126.1 and 126.2)



Fig. 126.1 Broselow tape, proximal end (at patient's head)



RESUSCITATION	
Epinephrine (1:10,000)	0.33 mg (3.3 mL)
pinephrine ET (1:1,000)	3.3 mg (3.3 mL)
tropine (0.1 mg/mL)	0.5 mg (5 mL)
ropine ET (0.4 mg/mL)	1 mg (2.5 mL)
dium Bicarbonate	33 mEq
ocaine	33 mg
caine ET	66-100 mgs
rillation	
/2nd Dose (may repeat)	66J/132J
version	
2nd Dose	33J/66J
ine	
ose	3.3 mg
ose If Needed	6.6 mg
one	165 mg
Chloride	660 mg
Sulfate	1650 mg

RAPID SEQUENCE INTUBATION	
PREMEDICATIONS	
Atropine	0.5 mg
Pan/Vecuronium (Defasiculating Agent)	0.33 mg
Lidocaine	50 mg
Fentanyl	100 mcg
INDUCTION AGENTS	
Etomidate	10 mg
Ketamine	66 mg
Midazolam	10 mg
Propofol	100 mg
PARALYTIC AGENTS	
Succinylcholine	66 mg
Pancuronium	6.6 mg
Vecuronium	6.6 mg
Rocuronium	33 mg
MAINTENANCE	
Pancuronium/Vecuronium	3.3 mg
Lorazepam	1.7 mg

Fig. 126.2 Broselow tape, distal end (the tape will accommodate a 36-kg child, at most)

J.K. Lucas, MD
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: judithklucas@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_126

126.4 Procedure (Figs. 126.3, 126.4, and 126.5)

- Place the infant or child on the bed in the supine position.
- Extend the Broselow Pediatric Emergency Tape next to the patient, placing the red line at the top of the patient's head.
- With the patient fully extended, especially through the hips and knees, align the bottom of the heel, while the ankle is flexed and toes upward, with the color on the tape adjacent to the heel.
- The color on the tape corresponds to the patient's weight.
- The side of the tape with weights noted along the bottom has medication doses for resuscitation, rapid-sequence intubation (RSI), and paralytics (Fig. 126.6).
- The top half of the other side of the tape has the appropriate dosing for managing seizures, overdoses, elevating intracranial pressure, and fluids. The bottom half of this side has the appropriate equipment sizes, such as endotracheal tubes, nasogastric tubes, chest tubes, and other equipment, that correspond to the patient's weight (Fig. 126.7).



Fig. 126.3 Placement of the child on the tape



Fig. 126.5 Placement of the child on the tape



Fig. 126.4 Placement of the child on the tape



BLUE

RESUSCITATION	
Epinephrine (1:10,000)	0.21 mg (2.1 mL)
Epinephrine ET (1:1,000)	2.1 mg (2.1 mL)
Atropine (0.1 mg/mL)	0.42 mg (4.2 mL)
Atropine ET (0.4 mg/mL)	1 mg (2.5 mL)
Sodium Bicarbonate	21 mEq
Lidocaine	20 mg
Lidocaine ET	40-60 mgs
Defibrillation Doses	
2J/kg	40J
4J/kg	80J
4-10J/kg	80J-200J
Cardioversion	
1st/2nd Dose	20J/40J
Adenosine	
1st Dose	2.1 mg
2nd Dose If Needed	4.2 mg
Amiodarone	105 mg
Calcium Chloride	420 mg
Magnesium Sulfate	1050 mg

RAPID SEQUENCE INTUBATION	
PREMEDICATIONS	
Atropine	0.42 mg
Pan/Vecuronium (Defasciculating Agent)	0.2 mg
Lidocaine	32 mg
Fentanyl	63 mcg
INDUCTION AGENTS	
Etomidate	6.3 mg
Ketamine	42 mg
Midazolam	6.3 mg
Propofol	63 mg
PARALYTIC AGENTS	
Succinylcholine	40 mg
Pancuronium	4.2 mg
Vecuronium	4.2 mg
Rocuronium	21 mg
MAINTENANCE	
Pancuronium/Vecuronium	2.1 mg
Lorazepam	1 mg

KG 19 KG 20 KG 22 KG 24 KG

Fig. 126.6 Front of tape. Weight groupings are noted at the bottom. This is the side with resuscitation and RSI medications



BLUE

SEIZURE	
Lorazepam	2 mg
Diazepam IV	4.2 mg
Diazepam – RECTAL	10 mg
Phenobarbital Load	420 mg
Phenytoin Load	420 mg
Fosphenytoin Load	420 mg-PE
OVERDOSE	
Dextrose	10.5 g
Naloxone	2 mg
Flumazenil	0.2 mg
Glucagon	1 mg
Charcoal	21 g
ICP	
Mannitol	21 g
Furosemide	21 mg

FLUIDS	
Volume Expansion	
Crystalloid (NS or LR)	420 mL
Colloid/blood	210 mL
Maintenance	
D5W + 1/2 NS + 20 meq KCl/L	63 mL/HR

Infusion:
Pursuant to JCAHO's
National Patient Safety Goal 3b -
"Rule of 6" for infusions
should be converted to
Standardized Concentrations.

Equipment			
E.T. Tube	5.5 Uncuffed	O_2 Mask	Pediatric NRB
E.T. Insertion Length	16.5 cm	*$ETCO_2$	Adult
Stylet	10 French	*Urinary Catheter	10-12 French
Suction Catheter	10 French	*Chest Tube	24-32 French
Laryngoscope	2 Straight or Curved	NG Tube	12-14 French
BVM	Child	Vascular Access	18-20Ga
Oral Airway	70 mm	Intraosseous	15Ga
*Nasopharyngeal Airway	24 French	BP Cuff	Child
*LMA	2-2.5		

*May not be included in Organizer System(s).

Fig. 126.7 Reverse side of tape. This side has medications for critical interventions aside from the primary survey, as well as equipment sizes

126.5 Pearls and Pitfalls

- Pearls
  - Be certain that the top of the head is at the red line and that the patient's body is fully extended. Infants tend to lay flexed at the hips and knees.
  - Determining the appropriate color code depends on noting the bottom of the heel while the ankle is flexed and the toes are pointing upward.
- Pitfalls
  - Beware of the child who is unusually heavy compared with other children of the same height.

Selected Reading

Luten R. Error and time delay in pediatric trauma resuscitation: addressing the problem with color-coded resuscitation aids. Surg Clin North Am. 2002;82:303–14, vi.

Luten R, Broselow J. Standardization of product concentration in emergency dosing: a response to Fineberg and Arendt. Ann Emerg Med. 2008;52:477–8.

Rosenberg M, Greenberger S, Rawal A, Latimer-Pierson J, Thundiyil J. Comparison of Broselow tape measurements versus estimations of pediatric weights. Am J Emerg Med. 2011;29:482–8.

Nursemaid's Elbow

127

Judith K. Lucas

127.1 Definition

- An injury commonly seen in children between 6 months and late preteens, although generally seen between 1 and 3 years
- A subluxation of the radial head, usually resulting from sudden, longitudinal traction on an extended arm with the wrist pronated
- Often occurs when a parent/caregiver is holding the child by the hand while walking and suddenly pulls the child away from a dangerous situation (Fig. 127.1)



Fig. 127.1 Note that the toddler prefers to hold her right arm pronated and somewhat flexed at the elbow. When asked where it hurts, she may as often point to her wrist as to her elbow. There will be no soft tissue swelling anywhere along the upper extremity

---

J.K. Lucas, MD
Department of Emergency Medicine,
University of Florida Health Shands Hospital,
Gainesville, FL, USA
e-mail: judithklucas@ufl.edu

© Springer Science+Business Media New York 2016
L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0_127

127.2 Clinical Diagnosis

- History of pulling-type injury.
- Child presents with arm held slightly flexed at elbow and pronated.
- Patient may point to elbow or wrist as source of pain, but both areas are without any swelling and are nontender on palpation.
- Elbow can be flexed and extended, but the forearm cannot be supinated.
- Radiography is not helpful.

127.3 Indications

- Clinical presence of subluxed radial head

127.4 Contraindications

- Absolute
  - Radiographic evidence of elbow or forearm fracture
  - Swelling or pain about the elbow, forearm, or wrist
- Relative
  - Unknown history or witnessing of pulling-type injury

127.5 Materials and Medications

- None

127.6 Procedure

127.6.1 Method A: Superpronation (preferred method) (Fig. 127.2)

1. Explain to the caretaker that the reduction will cause the child *very brief* discomfort.
2. Seat the child on the lap of a parent/caregiver or an assistant, facing the operator and holding the child in such a way as to hold the child's humerus against her or his side.
3. The person performing the procedure holds the elbow at approximately 90° and grasps the elbow, with the physician's thumb over the region of the radial head (this is done in order to be able to palpate the reduction "clunk" or "click").
4. The physician then holds the patient's wrist firmly and rapidly hyperpronates the forearm. A palpable or audible "click" signifies successful reduction but may not be appreciable.
5. The child may cry for a few minutes after reduction; however, the provider should leave the bedside for 5–10 min and instruct the parents to allow the child to simply play, without focusing on the affected arm.
6. After approximately 10 min, return to the bedside and reevaluate the child, who should have full use of her or his arm by then.



Fig. 127.2 Pronation: (**a**) The examiner's left hand holds the patient's radial head and medial condyle to better appreciate palpable reduction of the subluxation, (**b**) The examiner's right hand gently, but firmly, hyperpronates the patient's forearm from the level of the wrist. Within this maneuver, the examiner should feel or sense a "pop"

127.6.2 Method B: Supination (Fig. 127.3)

1. Follow the first three steps in Method A.
2. While holding the patient's wrist firmly, the operator steadily supinates the patient's forearm completely, followed by flexing the elbow, bringing the patient's wrist up to the shoulder.
3. Return to the fifth and sixth steps in Method A.



Fig. 127.3 Supination: (**a**) With the examiner's left hand in the same position as for the pronation technique, (**b**) the examiner supinates the forearm, from the level of the wrist, and fully flexes at the elbow. In either of these two maneuvers, the examiner should feel or sense a "pop"

127.7 Evaluation After Procedure

- If the child has complete use of the arm, no further intervention is required.
- If the child is still unable to supinate the forearm after 20–30 min, consider a repeat attempt at reduction.
- If there is still no return to full function after 30 min and/or repeated attempts at reduction, X-rays should be considered.
- In a child who still refuses to use the arm and X-rays are negative, the child should be reevaluated in 24 h.

127.8 Pearls and Pitfalls

- Pearls
  - Once reduced, there is rarely the need for analgesic medications. However, should the need arise, stay with ibuprofen because it is a proven anti-inflammatory.
  - If not seeing improvement within 15 min of reduction, consider this to be a fracture and obtain appropriate views of the elbow and forearm.
- Pitfalls
  - The longer the radial head has been subluxed, the longer it will take the child to return to full use.

Selected Reading

Krul M, van der Wouden JC, Koes BW, Schellevis FG, van Suijlekom-Smit LW. Nursemaid's elbow: its diagnostic clues and preferred means of reduction. J Fam Pract. 2010;59:e5–7.

Krul M, van der Wouden JC, van Suijledom-Smit LW, Koes BW. Manipulative interventions for reducing pulled elbow in young children. Cochrane Database Syst Rev. 2009;4:CD007759. doi: 10.1002/14651858.CD007759.pub2.

Macias CG, Bothner J, Wiebe R. A comparison of supination/flexion to hyperpronation in the reduction of radial head subluxations. Pediatrics. 1998;102:e10–8.

Quan L, Marcuse EK. The epidemiology and treatment of radial head subluxation. Am J Dis Child. 1985;139:1194–7.

Switzer JA, Ellis T, Swiontkowski MF. Wilderness orthopaedics. In: Auerbach PS, editor. Wilderness medicine. 5th ed. Philadelphia: Elsevier; 2007. p. 573.

Index

A
Abdominal hernias
  complications, 404
  contraindications, 403
  definition, 401
  indications, 403
  locations, 401, 402
  materials and medications, 403
  procedure, 403
  types of, 401
ABFO scale. *See* American Board of Forensic Odontology (ABFO) scale
Abortion
  complications, 659
  contraindications, 657
  indications, 657
  materials and medications, 657
  pearls and pitfalls, 659
  procedure
    checking abnormalities, 657–658
    decidual reaction, 657, 658
    fetal cardiac activity, 657, 658
    transvaginal sagittal imaging, 658
    transvaginal transverse imaging, 658
Abscess
  anal fissure, 455
  brain, 239
  difficult cricothyrotomy, 126
  incision and drainage
    Bartholin gland (*see* Bartholin gland abscess/cysts)
    complications, 567
    contraindications, 563
    external ear block, 520
    indications, 563
    local anesthesia, 509
    materials and medications, 563, 564
    parotid duct (*see* Parotid duct abscess)
    pearls, 567
    peritonsillar (*see* Peritonsillar abscess)
    procedure, 565–566
    sublingual (*see* Sublingual abscess)
  retroperitoneal, 717
  septal, 324
Acromioclavicular (AC) joint arthrocentesis, 621, 622
Activated charcoal (AC) adsorption
  complications, 423
  contraindications, 422
  indications
    MDAC therapy, 421
    single-dose activated charcoal, 421
  materials and medications, 422
  pearls, 423
  pitfalls, 423
  procedure, 423
Acute anal fissures, 453, 455
Acute dental fracture, 379
Acute respiratory distress syndrome (ARDS), 171, 172
Adson forceps, 241, 498, 500
Advance and cut technique, 550, 552
  with multiple barbs, 550, 552
  pearls and pitfalls, 553
  with single barb, 550
Airway assessment. *See* Difficult airway
Airway management. *See* Cricothyroidotomy
Allen test, 5, 7
Alligator forceps
  cerumen removal, 331, 332
  foreign body removal
    ear, 335, 336, 338
    nasal, 326–328
Allis maneuver, 605–606
Alveolar osteitis. *See* Dry socket
Ambu bags, 57, 326, 327, 329
Ambu Perfit, 219, 221, 230
American Academy of Neurology, 267
American Board of Forensic Odontology (ABFO) scale, 478, 482
Anal fissures, 454
  complications, 455
  contraindications, 455
  definition, 453
  indications, 453
  materials and medications, 455
  pearls and pitfalls, 455
  procedure, 455
Anembryonic gestation, 655
  complications, 656
  contraindications, 656
  indications
    low-lying empty gestational sac, 655
    mean gestational diameter, 655
  materials and medications, 656
  pearls and pitfalls, 656
  procedure
    transabdominal, 656
    transvaginal, 656
Anesthesia
  local (*see* Local anesthesia)
  mandibular nerve (*see* Mandibular anesthesia)
  over femoral artery, 9, 90
  regional (*see* Regional nerve block)
  for splinting, 572
Ankle arthrocentesis, 626, 629

© Springer Science+Business Media New York 2016

L. Ganti (ed.), *Atlas of Emergency Medicine Procedures*, DOI 10.1007/978-1-4939-2507-0

Ankle dislocation reduction
  complications, 620
  contraindications, 617
  indications, 617
  materials and medications, 617
  pearls and pitfalls, 620
  procedure
    anterior dislocations, 619
    posterior dislocations, 618
Antepartum hemorrhage, 661
Anterior dislocation
  ankle, 619
  elbow, 591, 594
  femur, 609, 610
  fibular head, 612
  shoulder, 583, 584
Anterior epistaxis
  complications, 314
  initial preparation, 313
  management of, 313–314
    commercial nasal pack, 313, 315
    gauze method, 314, 316
    silver nitrate stick and packaging, 313, 315
  pearls and pitfalls, 314
Aortic occlusion, 165, 168
Apnea test, 262, 266
ARDS. *See* Acute respiratory distress syndrome (ARDS)
Arrhythmia, 19, 33, 185, 188, 318
Arterial cannulation
  complications, 10
  contraindications, 3
  critical care, 3
  femoral artery (*see* Femoral artery cannulation)
  indications, 3
  pearls and pitfalls, 10–11
  radial artery (*see* Radial artery cannulation)
Arthritis diagnosis. *See* Arthrocentesis
Arthrocentesis. *See also* Intra-articular injection
  acromioclavicular joint, 621, 622
  ankle, 626, 629
  complications, 623
  contraindications, 621
  fluid aspiration, 625
  glenohumeral joint, 621, 622
  indications, 621
  knee
    lateral approach, 626, 627
    medial approach, 626, 628
    procedure, 621, 622
  materials and medications, 621
  pearls and pitfalls, 623
  procedure, 621–622
  shoulder, 626, 629
Ascites, 445, 449, 451
Aspen collar, 219–222
Atrial fibrillation, 185, 186
Atrial flutter, 185, 186
Atrial injuries, 181
Auricular hematoma
  cauliflower ear, 341
  contraindications, 342
  incision procedure, 342–348
    compression dressing, materials needed for, 343, 345
    elastic bandage, wrap head with, 343, 347
    Kerlix, wrap head with, 343, 346
    mold sterile gauze, 343, 346
    mold Xeroform gauze, 343, 345
    pad outside ear, 343, 346
    place dry cotton, 343
    secure dental rolls, 343, 348
  materials and medications, 342
  needle aspiration, 342–343
  pitfalls and complications, 348
  schematic of, 342
Auricular ring block technique, 520
Auriculotemporal block, 373
Auscultation monitoring, 641
Awake orotracheal intubation
  contraindications, 53
  indications, 53
  materials and medications, 53
  pearls and pitfalls, 56
  procedure, 53–55
    deep structures and trachea, lidocaine atomization of, 54, 55
    lidocaine lollipop, 54
    lighted stylet, 54, 55
    mucosal atomizer, 54
    nebulization of 4 % lidocaine, 53, 54
    posterior pharynx, lidocaine atomization of, 54, 55
    preparation, 53
    sedation, 54, 55

B

Babcock forceps, 498, 500, 501
Babysitter's elbow. *See* Nursemaid's elbow
Bag-valve-mask (BVM) ventilation, 127, 133, 135, 138
  airway, 89
  complications, 50
  contraindications, 47
  indications, 47
  materials, 47
  pearls and pitfalls, 50
  procedure, 48–50
    nasal airway insertion, 48, 49
    one-handed seal technique, 48, 49
    oral airway insertion, 48
    two-handed seal technique, 48, 50
Balloon gastrostomy tube, 441, 443
Balloon tamponade, 439
Bartholin gland abscess/cysts
  contraindications, 471
  follow-up care, 476
  indications, 471
  materials, 472
  procedure, 471
    incision and drainage, 472–473
    iodoform packing, 474
    Jacobi ring catheter, 475
    silver nitrate sticks, 475
    Word catheter, 474
Basilic vein (BV)
  cutdown, 41
  PIV cannulation, scanning for, 14
Benign paroxysmal positional vertigo (BPPV)
  Dix-Hallpike maneuver, 257
  Epley maneuver (*see* Epley maneuver for vertigo)
Bezoars, 421, 425
Bimanual pelvic examination, 467, 468, 478
Bladder catheterization
  complications, 463
  contraindications, 459
  indications, 459
  materials and medications, 459

- pearls and pitfalls, 463
- procedure, 460–462
  - for females, 460–462
  - frog-leg position, 460
  - for males, 460, 461

Bleeding evaluation, gastrointestinal. *See* Nasogastric tube (NT) placement
Blighted ovum. *See* Anembryonic gestation
Blister care, 534
Blood gas analysis, 494
Blunt probe and cutting method, 724, 726
Body surface area (BSA), 534
Bonfils intubation fiberscope, 109, 110
Bougie. *See* Endotracheal tube (ETT) introducer
Bowel obstruction/perforation. *See* Whole-bowel irrigation (WBI)
BPEG. *See* British Pacing and Electrophysiology Group (BPEG)
BPPV. *See* Benign paroxysmal positional vertigo (BPPV)
Brachial artery (BrA), 14
Brachial vein (BrV), 14
Bradycardia
- transcutaneous pacing, 195, 196
- transvenous cardiac pacing, 197

Brain death examination in adults
- confirmatory testing, 267
- contraindications, 261
- indications, 261
- materials and medications, 261
- pearls and pitfalls, 267
- procedure
  - apnea test, 262, 266
  - bulbar paralysis, 262, 266
  - motor response, pain, 261–263
  - oculocephalic reflex, 261, 264
  - oculovestibular reflex, 261, 265
- repeat examination, 267

Breech delivery
- breech presentation, 677
- complications, 682
- contraindications, 678
- indications, 678
- materials and medications, 678
- pearls and pitfalls, 682
- procedure
  - Burns-Marshall maneuver, 680, 681
  - correct hand placement, 680
  - head delivery in flexed position, 680
  - McRoberts maneuver, 678, 679
  - placing thumbs on sacrum, 678, 679
  - rotating towards maternal symphysis pubis, 678, 679

British Pacing and Electrophysiology Group (BPEG), 211, 212
Broselow Pediatric Emergency Tape
- contraindications, 729
- indications, 729
- materials, 729
- pearls and pitfalls, 731
- procedure, 730–731

Buccal nerve block, 367–368
Bulbar paralysis, 262, 266
Burn care
- admission criteria, 534–535
- blister care, 534
- complications, 534
- first degree/superficial burn, 531
- fluid resuscitation, 534
- inhalation injuries, 532
- materials and medications, 532
- pearls and pitfalls, 534
- permanent scarring, 531
- procedure, 534
- second degree/partial thickness burn, 531, 532
- sensory deficits, 531
- TBSA, 532–533
- third degree/full thickness burn, 531, 532

Burns-Marshall maneuver, 680, 681
Burr hole craniotomy
- complications, 240
- contraindications, 235
- indications, 235
- materials and medications, 235–236
- pearls and pitfalls, 240
- procedure
  - anatomy, 236, 238
  - automatic stop craniotomy drill, 236, 239
  - landmark for, 236, 239
  - patient positioning, 236, 237
  - penetrator drill, 236, 239
  - Penrose drain, suture in, 237, 239
  - preparation, 236
  - self-retaining retractors, placement of, 236, 239
  - wound closure, 237, 239

BVM ventilation. *See* Bag-valve-mask (BVM) ventilation

C

Caloric reflex testing
- complications, 253
- contraindications, 253
- indications, 253
- materials and medications, 253
- pearls and pitfalls, 255
- procedure, 253

Canadian C-spine rules (CCR), 223
Canalith repositioning procedure. *See* Epley maneuver for vertigo
Candida albicans, 468, 469
Cannulation
- PIV, 14
- of radial and femoral arteries (*see* Arterial cannulation)
- ultrasound guided, 20, 26

Captain Morgan technique, 607
Cardiac arrest, 193, 194, 205
Cardiac injury
- complications, 183
- contraindications, 179
- indications, 179
- materials and medications, 179–180
- pearls and pitfalls, 183
- procedure, 181–182
  - atrial injuries, 181
  - direct manual pressure, 181, 182
  - Finochietto retractor positioning, 181
  - lacerations, 181, 182
  - patient positioning, 181
  - polypropylene suture, 181, 182
  - surgical skin stapler, 181, 182

Cardiac massage. *See* Resuscitative thoracotomy
Cardiac output monitoring
- definitions, 37
- Edwards Vigileo System, 35, 36
  - contraindications, 37
  - materials, 38
  - pearls and pitfalls, 38
  - procedure, 38

Cardiac pacing, transvenous. *See* Transvenous cardiac pacing
Cardiac tamponade, 159, 179, 203, 207

Cardioversion
  synchronized electrical (*see* Synchronized electrical cardioversion)
  unsynchronized cardioversion
    complications, 192
    contraindications, 189
    high-energy shock, 189
    indications, 189
    materials and medications, 189
    pearls and pitfalls, 192
    procedure, 190–191
Catheterization
  bladder
    complications, 463
    contraindications, 459
    indications, 459
    materials and medications, 459
    pearls and pitfalls, 463
    procedure, 460–462
  peripheral vein
    contraindications, 693
    indications, 693
    materials and medications, 693, 694
    pearls and pitfalls, 699
    procedure, 694–699
  umbilical vein (*see* Umbilical venous catheters (UVC)
Cauliflower ear, 341
Cavernosal aspiration procedure, 490–492
CCR. *See* Canadian C-spine rules (CCR)
Centers for Disease Control and Prevention (CDC) guidelines, 479, 482
Central venous line
  contraindications, 17
  femoral vein access
    complications, 25–26
    pearls and pitfalls, 25
    procedure, 19, 21, 24–25
  indications, 17
  internal jugular vein access (*see* Internal jugular central venous line)
  materials and medications, 17–18
  removal of, 26
  subclavian vein access
    complications, 25–26
    pearls and pitfalls, 24
    procedure, 22–24
  ultrasound guided cannulation, 24, 26
Cephalic vein, 41, 695
Cerumen removal
  contraindications, 331
  indications, 331
  materials and medications
    alligator forceps, 331, 332
    bulb syringe, 331, 333
    cerumen-softening solutions, 331
    cerumen spoons, 331, 332
    ear curettes, 331, 333
    ear speculum, 331, 332
    eye and biohazard protection, 331
    headlamp/direct lighting instrument, 331
    irrigation setup, 331
    Schuknecht suction tube, 331
    specialized ear syringe, 331, 333
  pitfalls and complications, 334
  procedure, 334
Cerumen spoons
  cerumen removal, 331, 332
  ear foreign body removal, 335, 336
Cervical collar (C-collar)
  Aspen collar, 219–222
  cervical spine clearance (*see* Cervical spine clearance)
  contraindications, 219
  features of, 219
  indications, 219
  log roll, 229
  materials and medications, 219
  one-piece C-collars, 219
  pearls and pitfalls, 222
  two-piece C-collars, 219
Cervical ectopic pregnancy, 648
Cervical spine clearance
  CCR, 223
  complications, 227
  computed tomography, 224
  contraindications, 223
  flexion-extension X-rays, 224
  indications, 223
  magnetic resonance imaging, 224
  NEXUS clinical criteria, 223
  pearls and pitfalls, 227
  plain X-rays, 224
  procedure, 355–358
    C-collar placement, 225
    C spine tenderness assessment, 225, 226
Chemical burns, eye, 279
Chest trauma, 159
Chest tube thoracostomy. *See* Tube thoracostomy
Choriocarcinoma, 653
Chronic anal fissures, 453, 455
Clue cell, 458
Cobalt blue, 273
Color-coded pediatric emergency tape. *See* Broselow Pediatric Emergency Tape
Color duplex ultrasonography, 495
Colposcope, 478, 482
Combitube
  contraindications, 85
  indications, 85
  materials, 85
  pearls and pitfalls, 87
  procedure, 86–87
Complete abortion, 657–659
Complete breech, 677
Computed tomography (CT)
  brain death examination, 267
  choriocarcinoma, 653
  C-spine, 224
  EVD, 243, 245
  herniation syndromes, 250
  intraocular foreign body, 285
Cook intraosseous needle, 707, 708
Corneal foreign body removal
  complications, 285
  contraindications, 283
  indications, 283
  materials and medications, 284
  procedure, 285
Cotton tip applicator, 281, 284, 285
Cricothyroidotomy
  complications, 126
  contraindications, 119
  indications, 119
  pearls, 126
  scalpel-bougie techniques
    materials and medications, 119–120
    procedure, 121–122

    - Scalpel-Trousseau technique
        - materials and medications, 123
        - procedure, 124–125
- Cricothyrotomy. *See* Cricothyroidotomy
- Cuffalator, 433, 434
- Curved array transducer (C60)
    - FAST examination
        - with larger footprint, 406
        - left upper quadrant view of, 409
        - right upper quadrant view of, 408
    - heart, subxiphoid four-chamber view of, 407
- Curved hook
    - cerumen removal, 331
    - foreign body removal
        - ear, 335, 336, 338
        - nasal, 326–328
- Cyanoacrylate, 335, 337, 339

D

- Defibrillation. *See* Unsynchronized cardioversion
- Delivery
    - breech birth (*see* Breech delivery)
    - perimortem cesarean (*see* Perimortem cesarean section)
    - shoulder dystocia (*see* Shoulder dystocia management)
    - vaginal, 665–668
- Dental avulsion
    - complications, 386
    - contraindications, 384
    - indications, 383–384
    - materials and medications, 384
    - pearls and pitfalls, 386
    - procedure, 385
    - prognosis, 386
    - root development, stages of, 386
- Dental fracture. *See* Fractured tooth
- Depilatory method, hair tourniquet, 725
- Dermabond, 546–547
- Diagnostic peritoneal lavage (DPL)
    - complications, 399
    - contraindications, 396
    - indications, 395
    - materials and medications, 396
    - pearls and pitfalls, 399
    - procedure
        - closed technique, 397
        - open technique, 397
        - patient preparation, 396
        - semiopen (Seldinger) technique, 397–398
- Difficult airway
    - awake orotracheal intubation, 53
    - indications, 89
    - materials and medications, 89
    - pearls and pitfalls, 92
    - procedure
        - 6-D method, 90
        - LEMON, predict difficult direct laryngoscopy, 89–90
        - MOANS, BVM difficulty, 89
        - obese patient, optimizing laryngoscopy in, 92
- Digital nerve blocks, 523
    - intrathecal/tendon sheath approach, 525
    - ring block, 524
    - web space approach, 524
- DIP joint reduction. *See* Distal interphalangeal (DIP) joint reduction
- Direct laryngoscopy, 118
    - complications, 74
    - contraindications, 67
    - indications, 67
    - materials and medications, 68
    - pearls and pitfalls, 74
    - procedure, 69–74
        - ETT, 69, 74
        - glottic view, 69, 72–73
        - Macintosh blade insertion, 69, 71
        - Miller blade insertion, 69, 71
        - patient positioning, 69, 70
- Dislocation
    - ankle
        - anterior dislocations, 619
        - complications, 620
        - contraindications, 617
        - indications, 617
        - materials and medications, 617
        - pearls and pitfalls, 620
        - posterior dislocations, 618
    - elbow
        - anterior dislocations, 591, 594
        - complications, 597
        - contraindications, 591
        - indications, 591
        - materials and medication, 592
        - pearls and pitfalls, 597
        - posterior dislocations (*see* Posterior dislocation, elbow)
        - radial head subluxations, 595–596
    - finger joint (*see* Distal interphalangeal (DIP) joint reduction)
    - hip (*see* Hip dislocation reduction)
    - knee (*see* Knee dislocation reduction)
    - shoulder (*see* Shoulder, dislocation reduction)
    - temporomandibular joint (*see* Temporomandibular joint (TMJ) dislocation)
- Distal interphalangeal (DIP) joint reduction, 599
    - complications, 601
    - contraindications, 599
    - indications, 599
    - materials and medications, 599
    - pearls and pitfalls, 601
    - procedure, 600
- Dix-Hallpike maneuver
    - complications, 258
    - contraindications, 257
    - indications, 257
    - materials, 257
    - pearls and pitfalls, 258
    - procedure, 257, 258
- Doll's eyes
    - brain death examination in adults, 261, 264
    - contraindications, 251
    - indications, 251
    - pearls and pitfalls, 255
    - procedure, 251, 252
- Doppler ultrasonography
    - fetal heart rate monitoring, 642
    - testicular torsion, 503, 504
- Dorsal penile nerve block, 487–489
- Double-lumen airway. *See* Combitube
- DPL. *See* Diagnostic peritoneal lavage (DPL)
- Dry socket
    - complications, 376
    - contraindications, 376
    - indications, 375
    - materials and medications, 376
    - pearls and pitfalls, 376
    - procedure, 376
- Durable mass, 425

E
Ear canal impaction. *See* Cerumen removal
Ear curettes, 331, 333
Ear foreign body removal
  alligator forceps, 335, 336, 338
  cerumen spoon, 335, 336
  contraindications, 335
  curved hook, 335, 336, 338
  cyanoacrylate, 335, 337, 339
  ear speculum, 335, 336
  ear syringe, 335, 337
  eye and biohazard protection, 335
  headlamp/direct lighting instrument, 335
  indications, 335
  irrigation setup, 335, 337, 339
  Schuknecht catheter, 335, 337, 338
Ear hematoma. *See* Auricular hematoma
Early pregnancy failure. *See* Anembryonic gestation
Ear speculum
  cerumen removal, 331, 332
  foreign body removal, 335, 336
Ear syringe, 335, 337
Ear wax removal. *See* Cerumen removal
Ectopic pregnancy, 645
  complications, 648
  contraindications, 648
  indications
    in first trimester, 646
    free fluid in pelvis, 646, 647
    gestational sac, 646, 647
    hCG level, 646
    pseudogestational sac, 646
    risk factors, 646
    yolk sac, 648
  materials and medications, 648
  pearls and pitfalls, 648–649
  procedure
    transabdominal, 648
    transvaginal, 648
Edwards Vigileo System, 35, 36
  contraindications, 37
  materials, 38
  pearls and pitfalls, 38
  procedure, 38
EFAST. *See* Extended focused assessment with sonography for trauma (EFAST)
Elbow dislocation reduction
  anterior dislocations, 591, 594
  complications, 597
  contraindications, 591
  indications, 591
  materials and medication, 592
  pearls and pitfalls, 597
  posterior dislocations
    anatomical depiction, 591
    method A, 592
    method B, 592, 593
    method C, 592, 593
  radial head subluxations
    subluxation hyperpronated, 595
    subluxation hyperpronated and flexed, 595
    subluxation supinated, 595, 596
Electrocardiography (ECG)
  complete left bundle branch block, 29
  fetal heart rate monitoring, 643
Electronic fetal heart rate monitoring
  vs. auscultation method, 641
  external, 642
  internal, 643
Electronic indentation tonometry. *See* Tono-Pen tonometry
Embolism. *See* Pulmonary embolism
Emergent delivery. *See* Breech delivery
Emergent thoracotomy
  aortic occlusion, 165, 168
  complications, 169
  contraindications, 163
  indications, 163
  materials and medications, 163–164
  resuscitative thoracotomy and open cardiac massage, 165–167
    Finochietto retractor, 165, 166
    Lebsche knife, 165, 166
    pericardium, 165, 167
    skin and subcutaneous tissue incision, 165, 166
Empty skull sign, 267
Encephalitis, 247
Endocardial pacing. *See* Transvenous cardiac pacing
Endotracheal tube (ETT) introducer, 116
  complications, 101
  contraindications, 99
  indications, 99
  materials and medications, 99
  pearls and pitfalls, 101
  procedure, 100–101
    airway visualization, 100
    epiglottis, 100
    placement, 100, 101
    removal, 100, 101
Endotracheal tube (ETT) intubation
  fiber-optic stylet intubation (*see* Fiber-optic stylet intubation)
  lighted stylet intubation (*see* Lighted stylet (LS) intubation)
  LMA Fastrach, 80–81
  Storz video laryngoscope (*see* Storz video laryngoscope)
Episiotomy, 670, 678, 680, 685
Epistat, 317, 318
Epistaxis control
  anterior epistaxis (*see* Anterior epistaxis)
  contraindications, 313
  indications, 313
  materials and medications, 313
  nasal septum, vascular supply to, 311, 312
  nose, lateral wall of, 311, 312
  posterior epistaxis
    management of, 317, 318
    pearls and pitfalls, 317–318
    preliminary steps, 317
Epley maneuver for vertigo
  complications, 260
  contraindications, 259
  indications, 259
  materials, 259
  pearls and pitfalls, 260
  procedure, 259–260
Erythema migrans, 556
Esophageal foreign body removal
  complications, 418
  contraindications, 417
  indications, 417
  materials
    bougienage, 417
    esophagoscopy/endoscopy, 417

    Foley catheter removal, 417
    LES, relaxation of, 417–418
  pearls, 418–419
  procedure
    bougienage, 418
    Foley catheter removal, 418
    LES, relaxation of, 418
    push technique, 418
    push with fragmentation technique, 418
Esophagoscopy, 417
EVD. *See* External ventricular drain (EVD)
Extended focused assessment with sonography for trauma (EFAST), 410–411
External ear block
  auricular ring block, 520
  indications, 520
External fetal heart rate monitoring, 642
External rotation method, 587
External thrombosed hemorrhoid. *See* Thrombosed external hemorrhoid
External ventricular drain (EVD)
  complications, 244
  contraindications, 241
  CSF, 241
  indications, 241
  materials and medications, 241, 243
  pearls and pitfalls, 244, 245
  procedure, 241–245
    advance ventriculostomy catheter with stylet, 242, 244
    anesthetize skin, 242, 244
    brain, CT scan of, 243, 245
    Kocher's point, 242, 243
    level of patient's ear tragus, 243, 245
    make burr hole, 242, 244
    make stab incision, 242, 244
Extradural hematoma (EDH), 235
Extrauterine pregnancy. *See* Ectopic pregnancy
Eye
  corneal foreign body removal (*see* Corneal foreign body removal)
  intraocular pathology (*see* Intraocular pathology)
  irrigation
    complications, 282
    contraindications, 279
    indications, 279
    materials and medications, 279–280
    pearls and pitfalls, 282
    procedure, 281
  lateral canthotomy (*see* Lateral canthotomy)
  retinal detachment (*see* Retinal detachment)
  slit lamp examination
    complications, 276
    contraindications, 272
    corneal foreign body removal, 284
    fluorescein testing (*see* Fluorescein testing)
    indications, 271, 272
    materials, 273
    pitfalls, 276
    procedure, 274–275
  tonometry (*see* Tonometry)

F

Facial nerve block
  infraorbital nerve block, 517–518
  mental nerve block, 519
  suborbital and supratrochlear nerve block, 517
FAST examination. *See* Focused assessment with sonography for trauma (FAST) examination
Feeding tube, 459, 701–704
Femoral artery cannulation. *See also* Arterial cannulation
  materials and medications, 3
  pearls and pitfalls, 10–11
  Seldinger technique, 3, 9–10
Femoral central venous line
  complications, 25–26
  pearls and pitfalls, 25
  procedure, 20, 21, 24–25
Femoral neck fracture, 603
Femur dislocation reduction. *See also* Hip dislocation reduction
  anterior dislocation, 609, 610
  complications, 614
  lateral dislocation, 609, 610
  medial dislocation, 609, 611
  pearls and pitfalls, 614–615
  posterior dislocation, 609, 610
  rotary dislocation, 609, 611
Fetal heart rate (FHR) monitoring
  complications, 644
  contraindications, 641
  electronic method
    vs. auscultation method, 641
    external, 642
    internal, 643
  indications
    antepartum, 641
    intrapartum, 641
Fiber-optic stylet intubation
  contraindications, 109
  indications, 109
  materials and medications, 109–110
  pearls and pitfalls, 113
  procedure
    advancing scope, 111, 112
    endotracheal tube placement, 110
    epiglottis visualization, 110, 112
    lens fogging prevention, 110
    scope insertion, 110, 111
    scope removal, 111, 112
Fibrinolytic osteitis. *See* Dry socket
Fibular head dislocation reduction
  anterior dislocation, 612
  complications, 612
  pearls and pitfalls, 614
  posterior dislocation, 612
Finger dislocation joint reduction. *See* Distal interphalangeal (DIP) joint reduction
Finochietto retractor, 163–166, 179, 181
Fishhook removal
  anatomy, 549
  complications, 553
  contraindications, 549
  materials and medications, 549
  from nonvital structures, 549
  pearls and pitfalls, 553
  postremoval wound care, 553
  procedures
    advance and cut technique (*see* Advance and cut technique)
    needle cover technique, 550, 551
    retrograde technique, 550, 551
    string and yank technique, 550, 551

Fissures. *See* Anal fissures
Flail chest
  abdominal injuries, 162
  blunt lung injury and contusion, 162
  chest wall, surgical stabilization of, 162
  diagnosis, 162
  mortality, 159
  posterior rib fractures, 159, 160
Fluorescein testing
  complications, 277
  indications and uses, 276
  pitfalls, 277
  procedure, 276
Focused assessment with sonography for trauma (FAST) examination, 179
  abdominal/chest trauma, 405
  complications, 411
  contraindications, 405
  vs. DPL, 395
  free fluid, 405
  hypotension, 405
  materials and medications, 405–406
  pearls and pitfalls, 411–412
  pneumothorax/hemothorax, 405
  procedure
    EFAST examination, right and left lung view of, 410, 411
    left upper quadrant view, 409
    right upper quadrant view, 408
    sagittal pelvic view of, 409, 410
    subxiphoid four-chamber view, 407
    transverse pelvic view of, 409
Foley catheter, 417, 498, 688
  foreign body removal
    esophageal, 417, 418
    nasal, 326, 328
  large cardiac lacerations, control of, 181
  in posterior nasopharynx, 317, 318
Forearm fracture. *See* Sugar-tong splint
Foreign body (FB) removal
  corneal
    complications, 285
    contraindications, 283
    indications, 283
    materials and medications, 284
    procedure, 285
  ear (*see* Ear foreign body removal)
  esophageal (*see* Esophageal foreign body removal)
  nasal (*see* Nasal foreign body removal)
Forensic examination, sexual assault. *See* Sexual Assault Forensic Examination (SAFE)
Fracture
  acetabulum, 603
  basilar skull, 251, 253
  concomitant, 597
  cribriform plate, facial trauma with, 413
  DIP joint dislocations, 601
  elbow, 597
  femoral neck, 603
  fetal clavicle, 672
  fetal humerus, 672
  jaw, 376
  long bone, 707
  pelvic, 459
  petrous bone, 253
  posterior rib, flail chest, 159, 160
  splinting (*see* Splinting)
Fractured tooth
  anatomy of tooth, 380
  complications, 382
  contraindications, 381
  indications, 379
  materials and medications, 381
  methods of, 379
  pearls, 382
  procedure, 381
  types of, 380
Frank breech, 677

G
Galveston formula, 534
Gaskin maneuver, 672
Gastric aspiration. *See* Nasogastric tube (NT) placement
Gastric decompression. *See* Nasogastric tube (NT) placement
Gastric irrigation. *See* Gastric lavage
Gastric lavage
  complications, 427
  contraindications, 425
  indications, 425
  materials and medications, 425
  pearls and pitfalls, 427
  procedure, 426–427
Gastrografin®, 447
Gastrostomy tube placement
  balloon G tube, 441, 443
  complications, 448
  contraindications, 445
  general anesthesia, 445
  indications, 445
  laparoscopic G tube, 441
  low-profile G tube
    nonobturated, button, 441, 443
    obturated, button, 441, 444
    placement of, 446
  Malecot tube, 441, 442
  materials, 445
  open gastrostomy tube, 441
  pearls and pitfalls, 448
  PEG tube, 441, 442
    local anesthesia, 445
    moderate sedation, 445
    replacement procedure, 446–447
Gelfoam®, 377, 378
Genital and perineal lacerations, 685
Glenohumeral joint arthrocentesis, 621, 622
GlideScope
  complications, 96
  contraindications, 93
  indications, 93
  materials and medications, 93, 94
  pearls and pitfalls, 96
  procedure, 95–96
    cable insertion, video monitor, 95
    Cobalt system, 95
    distal end, video cable connection, 95
    ETT abuts, 96
GlideScope Video Laryngoscope (GVL) system, 93, 94
Globe rupture, 294
Glucocorticoids, 625, 626, 630
Guillain-Barré syndrome, 247

H
Hair tourniquet
  complications, 728
  contraindications, 724
  indications, 723
  materials and medications, 724
  pearls and pitfalls, 728
  procedure
    blunt probe and cutting method, 724, 726
    depilatory method, 725
    digits, incision technique for, 725, 726
    severe penile tourniquet, incision technique for, 725, 727
    unraveling method, 724, 725
Half-buried horizontal mattress suture, 540, 543
Headache, 248, 250, 493
Head-hanging positioning maneuver. *See* Dix-Hallpike maneuver
Heart failure
  Edwards Vigileo System (*see* Edwards Vigileo System)
  pulmonary artery catheter, 29
Heart strain. *See* Pulmonary embolism
Hematomas
  auricular hematoma
    cauliflower ear, 341
    contraindications, 342
    incision procedure, 342–348
    materials and medications, 342
    needle aspiration, 342, 343
    pitfalls and complications, 348
    schematic of, 342
  septal (*see* Septal hematomas)
  subungal hematoma (*see* Subungal hematoma)
Hemoperitoneum, 153, 449
Hemorrhage
  antepartum, 661
  postextraction (*see* Postextraction hemorrhage)
  postpartum (*see* Postpartum hemorrhage (PPH))
  retrobulbar, 305
  subarachnoid, 241, 242
  vitreous, 292
Hepatitis B virus (HBV), 479
Hernia. *See* Abdominal hernias
High-frequency (5–8 MHZ) linear probe, 13
High-risk pregnancy, 641
Hip dislocation reduction
  Allis maneuver, 605–606
  Captain Morgan technique, 607
  complications, 608
  contraindications, 603
  indications, 603
  materials and medications, 603
  pearls and pitfalls, 608
  Stimson maneuver
    femoral head manipulation, 604, 605
    with hand, 604
    with knee, 604
  Whistler technique, 607
Hippocrates method, 589
Horizontal mattress suture, 540, 542
Human immunodeficiency virus (HIV), 455, 479, 641
Hunt and Hess scale, 242
Hydatidiform mole
  complications, 653
  contraindications, 651
  definition, 651
  indications, 651
  materials and medications, 651
  pearls and pitfalls, 653
  procedure
    transabdominal imaging, 651–652
    transvaginal imaging, 652
Hydrocephalus, 241, 245, 250
Hypotension
  Edwards Vigileo System (*see* Edwards Vigileo System)
  FAST examination, 405
  pulmonary artery catheter, 29
Hypovolemia, 19, 23, 24, 39, 451

I
IAN. *See* Inferior alveolar nerve (IAN) block
ICP. *See* Intracranial pressure (ICP)
Impotency, 493
Incision and drainage (I&D), abscess
  Bartholin gland (*see* Bartholin gland abscess/cysts)
  complications, 567
  contraindications, 563
  external ear block, 520
  indications, 563
  local anesthesia, 509
  materials and medications, 563–564
  parotid duct (*see* Parotid duct abscess)
  pearls, 567
  peritonsillar (*see* Peritonsillar abscess)
  procedure, 565–566
  sublingual (*see* Sublingual abscess)
Incomplete abortion, 657–659
Incomplete breech, 677
Inevitable abortion, 657–659
Infectious arthritis. *See* Arthrocentesis
Inferior alveolar nerve (IAN) block
  anesthetized areas, 363–364
  anesthetized nerves, 363
  contraindications, 364
  indications, 364
  materials and medications
    aspirating syringe, 365
    local anesthetic carpule, 365
    mouth props and retractors, 365
    needle, 365
  procedure, 366
Inferior vena cava (IVC), 208, 209
Infraorbital nerve block
  contraindications, 513
  extraoral approach, 517
  indications, 517
  intraoral approach, 518
  materials and medications, 514
Inhalation injuries, 532
Internal fetal heart rate monitoring, 643
Internal jugular central venous line
  complications, 25–26
  procedure, 18–21
    angiocath, 21, 23
    informed consent, 18
    J-tip straightening, 19, 21
    long-and short-axis views, 18, 20
    marking, 19, 21
    patient positioning, 18

Intra-articular injection. *See also* Arthrocentesis
  complications, 630
  contraindications, 625
  indications, 625
  materials and medications, 625
  pearls, 630
  procedure, 626–630
    ankle arthrocentesis, 626, 629
    joint fluid aspiration, 626, 629
    knee arthrocentesis, 626–628
    shoulder arthrocentesis, 626, 629
    using sterile hemostat, 626, 630
Intracorporeal injection procedure, 493
Intracranial pressure (ICP), 241, 243, 247, 295
Intraocular pathology
  complications, 291
  foreign body, 294
  globe rupture, 294
  increased ICP, 295
  indications, 291
  materials, 291
  optic nerve sheath measurement, 295
  pitfalls, 291
  procedure, 291
  retinal detachment, 292–293
  vitreous detachment, 292
  vitreous hemorrhage, 292
Intraocular pressure (IOP), 289
  lateral canthotomy, 305, 306, 308
  tonometry (*see* Tonometry)
Intraosseous (IO) access
  complications, 712
  contraindications, 707
  indications, 707
  materials and medications
    Cook intraosseous needle, 707, 708
    EZ-IO, 707, 708
    Jamshidi disposable sternal/iliac aspiration needle, 707
  pearls and pitfalls, 712
  procedure
    distal femur, 709
    distal tibia, 709
    proximal humerus, 709, 711
    proximal tibia, 113, 708, 709
    sternum, 709
Intraosseous infusion. *See* Intraosseous access
Intrathecal digital block, 525
Intrauterine pregnancy, 657–659
IOP. *See* Intraocular pressure (IOP)
Ischemic priapism. *See* Priapism
Ixodes scapularis, 556

J
Jacobi ring catheter, 471, 472, 475
Jamshidi disposable sternal/iliac aspiration needle, 707
Joint aspiration. *See* Arthrocentesis
Joint effusion treatment. *See* Arthrocentesis
Joint pain treatment. *See* Arthrocentesis
Joint stabilization, splinting. *See* Splinting

K
Kiesselbach's plexus, 311, 312
Knee arthrocentesis
  lateral approach, 626, 627
  medial approach, 626, 628
  procedure, 621, 622
Knee dislocation reduction
  complications, 614
  contraindications, 609
  femur/tibia
    anterior dislocation, 609, 610
    complications, 614
    lateral dislocation, 609, 610
    medial dislocation, 609, 611
    pearls and pitfalls, 614
    posterior dislocation, 609, 610
    rotary dislocation, 609, 611
  fibular head
    anterior dislocation, 612
    complications, 614
    pearls and pitfalls, 614
    posterior dislocation, 612
  indications, 609
  lateral patellar
    complications, 614
    pearls and pitfalls, 614–615
    procedure, 613
  materials and medications, 609
Kocher technique, 587

L
Laparoscopic gastrostomy tube placement, 441, 445
Laryngeal mask airways (LMAs), 109, 119
  complications, 83
  contraindications, 75
  indications, 75
  LMA Classic Excel, 76–78
  LMA Fastrach, 76
    endotracheal intubation, 80–81
    insertion, 79
    removal of, 81–82
  LMA Unique, 76–78
  pearls and pitfalls, 83
  sizing, 77
Laryngotomy. *See* Cricothyroidotomy
Lateral canthotomy
  complications, 308
  contraindications, 306
  materials and medications, 306
  pearls and pitfalls, 308
  procedure, 306–307
    initial cut, 306, 307
    intraocular pressure, further cut to reduce, 307
    lateral canthal tendon, 306, 307
    patient positioning, 306
  retrobulbar hemorrhage, 305
Lateral patellar dislocation reduction
  complications, 614
  pearls and pitfalls, 614–615
  procedure, 613
LES. *See* Lower esophageal sphincter (LES)
Levitan FPS malleable fiber-optic stylet, 110
Lighted stylet (LS) intubation
  contraindications, 103
  indications, 103
  materials and medications, 103
  pearls and pitfalls, 107
  procedure, 104–106
    dim/blurred light, 104, 105

    - ETT placement, 104, 106
    - LS-ETT unit insertion, 104
    - LS-ETT unit preparation, 104
    - midline glow, use of, 104, 105
    - patient positioning, 104
    - preoxygenate, 104
- Light Wand™, 103
- LMAs. *See* Laryngeal mask airways (LMAs)
- Local anesthesia
  - Bartholin gland abscess/cysts drainage, 472
  - bladder catheterization, 459
  - characteristics, 511
  - complications, 512
  - contraindications, 509
  - dorsal penile nerve block procedure, 487, 488
  - dry socket, 376
  - fishhook removal, 549
  - indications, 509
  - infiltration, 511
  - intra-articular injection, 626
  - lumbar puncture in adults, 248
  - materials and medications, 510
  - needle thoracostomy, 144
  - pearls, 512
  - PEG tube placement, 445
  - phimosis/paraphimosis, 497
  - postextraction hemorrhage, 377
  - procedure, 511
  - septal hematomas, 322
  - TMJ dislocation reduction, 373
- Log roll
  - contraindications, 229
  - indications, 229
  - materials and medications, 229
  - pearls and pitfall, 232
  - procedure, 229–231
    - Ambu Perfit one-piece collar height, 229, 230
    - anatomical line of symmetry, 231
    - backboard removed, 231
    - C-spine stabilization, 229, 230
    - thoracic and lumbar spine stabilization, 230
- Lower esophageal sphincter (LES), 417–418, 426
- Low-profile gastrostomy tube
  - nonobturated, button, 441, 443
  - obturated, button, 441, 444
  - placement of, 446
- Lumbar puncture (LP), in adults
  - complications, 250
  - contraindications, 247
  - indications, 247
  - materials and medications, 247
  - pearls and pitfalls, 250
  - procedure
    - CSF fluid collection, 250
    - landmarks, 248
    - local anesthesia, 248
    - needle insertion, 248–250
    - patient positioning, 248, 249
    - pressure measurement, 249, 250
    - sterile preparation, 248
    - ultrasound guidance, 248, 249
- Lumbar puncture (LP), in pediatrics
  - complications, 717
  - contraindications, 713
  - indications, 713
  - materials and medications, 713–714
  - pearls and pitfalls, 717–718
  - procedure
    - attaching pressure manometer, 715, 717
    - child, positioning of, 715, 716
    - CSF freeflow, checking for, 715
    - iliac crest top, palpation of, 715, 717
    - locating intervertebral space, 715
    - spinal needle insertion, 715
- Lund Browder chart, 532, 533
- Lung ultrasonography
  - contraindications, 171
  - indications, 171
  - materials, 171
  - preparations, 171
  - procedure, 172–175
    - A lines identification, 172, 174
    - assessment and clinical decision making, 173
    - bat sign identification, 172, 174
    - B lines identification, 172, 174
    - consolidations identification, 173, 175
    - diaphragm, liver and spleen identification, 173, 175
    - lung pulse, 172
    - lung sliding identification, 172, 174
    - pleural effusions identification, 173, 175
    - probe position, 172, 174
    - sinusoid sign, 173, 175
- Lyme disease, 556

M

- Malecot tube, 441, 442
- Malfunctioning pacemakers
  - ECG evaluation, 214
  - failure to capture, 213
  - failure to pace, 213
  - failure to sense, 213
  - inappropriate rate, 213
  - pacemaker-mediated tachycardia management, 214
  - pacemaker syndrome, 213
- Mallampati classification, 61, 90, 91
- Mandibular anesthesia
  - buccal nerve block, 367–368
  - inferior alveolar nerve block (*see* Inferior alveolar nerve (IAN) block)
  - mental nerve block, 368–369
- Manual testicular detorsion. *See* Testicular torsion
- McRoberts maneuver
  - breech delivery, 678, 679
  - shoulder dystocia management, 670, 671
- Mean gestational diameter (MGD), 655
- Meningitis, 240, 244, 247
- Mental nerve block, 368–369
  - contraindications, 513
  - extraoral approach, 517
  - indications, 513
  - intraoral approach, 518
  - materials and medications, 514
- Methicillin-resistant *Staphylococcus aureus* (MRSA), 567
- Miami J collar, 219
- Milch technique, 588
- Miscarriage, 657–659
- Missed abortion, 657–659
- Molar pregnancy, 651–653
- Morgan lens, 279–281
- Multiple-dose activated charcoal (MDAC) therapy, 421, 423
- Myocardial infarction, 29
- Myometrium contraction, 664

N

Nailbed injury. *See* Subungal hematoma
Nail trauma. *See* Subungal hematoma
Nasal foreign body removal
    alligator forceps, 326–328
    Ambu bags, 326, 327
    contraindications, 325
    curved hook, 326–328
    eye and biohazard protection, 326
    Foley catheter, 326, 328
    headlamp/direct lighting instrument, 326
    indications, 325
    lidocaine jelly, 326
    lidocaine without epinephrine, 326
    nasal positive pressure, 329
    nasal speculum, 326
    phenylephrine, 326
    schuknecht suction tube, 326, 327
Nasal trauma
    epistaxis control, 311
    septal hematomas (*see* Septal hematomas)
Nasogastric tube (NT) placement
    complications, 415
    contraindications, 413
    indications, 413
    materials and medications, 413
    pearls, 415
    procedure
        insertion, 414
        preparation, 414
        secure tube, 414
        tube placement, confirmation of, 414
Nasopharyngeal airways, 47–49
Nasostat, 317, 318
National Emergency X-Radiography Utilization Study (NEXUS), 223
Needle cover technique, 550, 551
Needle decompression thoracostomy
    complications, 147
    indications
        absolute, 143
        awake patient, 143
        injured patient, 143
        ventilated patient, 143
    materials, 143
    pearls and pitfalls, 147
    procedure
        anterior chest, exposure of, 144
        second intercostal space, needle insertion, 144, 145
        secure angiocatheter, 144, 146
        skin preparation, 144
Noninvasive cardiac monitoring. *See* Cardiac output monitoring
Nonischemic priapism. *See* Priapism
North American Society of Pacing and Electrophysiology (NASPE), 211, 212
Nosebleeds, 311
Nuchal arm. *See* Breech delivery
Nursemaid's elbow, 597
    clinical diagnosis, 734
    contraindications, 734
    definition, 733
    evaluation, 737
    indications, 734
    pearls and pitfalls, 737
    superpronation method, 734–735
    supination method, 736

O

Obstetric complications. *See* Breech delivery
Ocular pathology. *See* Intraocular pathology
Oculocephalic reflex. *See* Doll's eyes
Oculovestibular reflex, 261, 265, 267
One-handed seal technique, BVM ventilation, 48, 49
Open chest wounds
    sucking chest wound, 159–161
    thoracic trauma, 159, 161
Open gastrostomy tube placement, 441, 445
Open pneumothorax, 159, 161
Ophthalmic burr drill, 284
Oral airways, 47, 48
Orogastric (OG) tube
    activated charcoal, 422, 423
    gastric lavage, 425
Orotracheal intubation, 67. *See also* Awake orotracheal intubation
Osteoarthritis (OA), 625, 630

P

Pacemaker evaluation
    electrocardiogram, 214
    impulses, 211
    insulated wire, 211, 212
    laboratory studies, 214
    malfunctioning (*see* Malfunctioning pacemakers)
    NASPE/BPEG code, 211, 212
    pacemaker codes, 213
    pacemaker lead insertion sites, 211, 212
    patient history, 214
    physical examination, 214
    prevalence, 211
    pulse generator, 211, 212
Pacemaker-mediated tachycardia, 213, 214
Pacemaker syndrome, 213
Pacer pads, 194
Paracentesis
    complications, 451
    contraindications, 449
    indications, 449
    materials and medications, 449
    pearls and pitfalls, 451
    procedure, 449–451
Paraphimosis
    complications, 501
    contraindications, 497
    indications, 497
    manual reduction, procedure for, 498–500
        Adson/Babcock forceps, 498, 500
        circumcision, 498, 500
        patient positioning, 498
        penile block, usage of, 498, 499
    materials and medications, 497
    pearls and pitfalls, 501
Parasternal long-axis view (PSLA), 207
Parasternal short-axis view (PSSA), 207, 208
Parkland formula, 534
Parotid duct abscess
    complications, 360
    contraindications, 357
    materials and medications, 357–358
    pearls and pitfalls, 360
    procedure, 359–360
        intraoral stab incision, 355
        lighting, 355

    parotid papilla, 359, 360
    patient positioning, 359
    salivary glands, anatomy of, 359
Parotid papilla, 359, 360
Particle repositioning. *See* Epley maneuver for vertigo
Patellar dislocation reduction
  complications, 614
  pearls and pitfalls, 614–615
  procedure, 613
PEG tube. *See* Percutaneous endoscopic gastrostomy (PEG) tube
Pelvic examination and wet preparation
  complications, 468
  contraindications, 465
  indications, 465
  materials and medications, 465, 466
  pearls and pitfalls, 468
  procedure, 465–468
    bimanual examination, 467, 468
    Candida albicans, 468, 469
    female external and internal genitalia, 466, 467
    normal and clue cell, 458
    rectovaginal examination, 467
    trichomoniasis, 468, 469
    wet preparation interpretation, 466, 467
  SAFE, 478
Pelvic ultrasound, 657–658
Percutaneous endoscopic gastrostomy (PEG) tube, 441, 442
  local anesthesia, 445
  moderate sedation, 445
  replacement procedure, 446–447
Percutaneous TTJV. *See* Transtracheal jet ventilation (TTJV)
Pericardial effusion, 203, 205
Pericardiocentesis
  complications, 205
  contraindications, 203
  indications, 203
  materials and medications, 203
  pearls, 205
  pitfalls, 205
  procedure, 203
    apical approach, 204
    parasternal long-axis approach, 205
    subxiphoid approach, 204
Pericardium. *See* Pericardiocentesis
Perimortem cesarean section
  complications, 690
  contraindications, 687
  indications, 687
  materials and medications, 687
  pearls and pitfalls, 690
  procedure
    exposing rectus sheat, 688, 689
    fetus delivery, 688, 689
    placenta delivery, 688, 690
    resuscitation of infant, 688, 689
    vertical incision, 688
Peripheral intravenous (PIV) access, ultrasound-guided
  complications, 15
  contraindications, 13
  indications, 13
  materials and medications, 13
  pearls and pitfalls, 15
  procedure
    basilic and cephalic veins, 14
    brachial artery and vein, 14
    needle insertion, preparation for, 14
    Pythagorean Theorem, concept of, 14
    transverse and longitudinal orientation, 14
Peripheral vascular disease, 553
Peripheral venous catheterization
  contraindications, 693
  indications, 693
  materials and medications, 693, 694
  pearls and pitfalls, 699
  procedure, 694–699
    applying tourniquet, 694
    hub stabilizer placement, 695, 699
    passing catheter tip, 694, 697
    secure intravenous line, 695, 698
    vein, palpation of, 694, 696
Peripheral venous cutdown
  basilic vein, 41
  cephalic vein, 41
  complications, 44
  contraindications, 39
  indications, 39
  materials and medications, 39–40
  mini-cutdown technique, 43
  modified/guide wire technique, 43
  pearls and pitfalls, 44
  saphenous vein, 41
  standard venous cutdown technique, 41–43
    distal and proximal ligatures, 41, 42
    mobilization of vein, 41, 42
    skin incision, 41, 42
    venous catheter, 41–43
    venous incision, 41, 42
Peritonsillar abscess
  aspiration of, 349–350
  complications, 352
  contraindications, 349
  incision and drainage of, 351
  indications, 349
  materials and medications, 349
  pearls and pitfalls, 352
Phased array transducer (P17), 405
Phenylephrine
  nasal foreign body removal, 326
  priapism, 493
  septal hematoma, 322
Philadelphia collar, 219
Phimosis. *See also* Paraphimosis
  complications, 501
  contraindications, 497
  indications, 497
  materials and medications, 497
  pearls and pitfalls, 501
  procedure, 498–500
pH paper, 279, 280
Piles. *See* Thrombosed external hemorrhoid
Placenta previa
  complications, 664
  contraindications, 662
  grades, 661
  indications, 662
  materials and medications, 662
  pearls and pitfalls, 664
  procedure, 662–663
  varying degrees, 661

Placenta removal, 684
Pleural effusions, 173, 175
Pneumonia, 172, 173, 175
Pneumothorax, 156, 158, 405
Poisoning treatment. *See* Activated charcoal (AC) adsorption
Polyethylene glycol-electrolyte solution, 429, 431
Polymorphonuclear lymphocyte (PMN), 451
Posterior dislocation
  ankle, 618
  elbow
    anatomical depiction, 591
    method A, 592
    method B, 593
    method C, 593
  femur, 609, 610
  fibular head, 612
  shoulder, 583, 584
Posterior epistaxis
  management of, 317
  pearls and pitfalls, 317–318
  preliminary steps, 317
Postextraction hemorrhage
  complications, 378
  contraindications, 377
  indications, 377
  materials and medications, 377
  pearls and pitfalls, 378
  procedure, 377–378
Postparacentesis circulatory dysfunction (PPCD), 451
Postpartum hemorrhage (PPH), 668
  complications, 685
  contraindications, 683
  definition, 683
  indications, 683
  materials and medications, 683
  pearls and pitfalls, 685
  procedure
    continuous interlocking stitch technique, 685
    placenta removal, 684
    uterine atony, intrauterine massage for, 684
    uterine examination, 683
    uterine inversion management, 684
    vaginal examination, 683
  shoulder dystocia management, 675
Pregnancy
  blighted ovum (*see* Anembryonic gestation)
  complications (*see* Placenta previa)
  fetus/embryo, removal of (*see* Abortion)
  high-risk, 641
  hydatidiform mole (*see* Hydatidiform mole)
  tubal (*see* Ectopic pregnancy)
Priapism
  blood gas analysis, 494
  color Duplex ultrasonography, 495
  complete blood count, 495
  complications, 493
  contraindications, 485
  hemoglobin electrophoresis, 495
  indications, 485
  materials and medications, 485–486
  noninvasive therapy preprocedure, 487
  pearls and pitfalls, 493
  procedure
    cavernosal aspiration, 490–492
    dorsal penile nerve block, 487–489
    intracorporeal injection, 493
  psychoactive drug screen, 495
  sickle cell testing, 495
  urine toxicology, 495
Prophylaxis, 479, 482
PSLA. *See* Parasternal long-axis view (PSLA)
PSSA. *See* Parasternal short-axis view (PSSA)
Pulled elbow. *See* Nursemaid's elbow
Pulmonary artery catheter
  catheter preparation, 29
  complications, 33
  contraindications, 29
  indications, 29
  materials, 29
  pearls and pitfalls, 33
  procedure, 30–32
    balloon inflation, 30
    chest radiograph, correct placement, 30, 32
    sterile plastic sleeve, 30, 31
    thick and thin markings, 30, 31
    waveform and pressure readings, 30, 31
Pulmonary embolism
  clinical findings, 209
  complications, 209
  contraindications, 207
  indications, 207
  materials and medications, 207
  pearls and pitfalls, 209
  procedure, 207–208
    four-chamber view, 208
    inferior vena cava, 207–208
    PSLA, 207
    PSSA, 207, 208
    subxiphoid approach, 208
Pulmonary hypertension, 29, 30, 33
Pulseless electrical activity (PEA), 179, 189, 205
Pulseless ventricular tachycardia, 189

R
Radial artery cannulation. *See also* Arterial cannulation
  Allen test, 7–8
  over-the-needle catheter assembly with integrated guide wire, 3, 7
  pearls and pitfalls, 10–11
  standard over-the-needle catheter assembly
    materials and medications, 3, 4
    procedure, 5–6
Radial head subluxations. *See also* Nursemaid's elbow
  subluxation hyperpronated, 595
  subluxation hyperpronated and flexed, 595
  subluxation supinated, 595
Radial nerve block, wrist, 522
Rapid sequence intubation (RSI), 110
  complications, 65
  contraindications, 57
  indications, 57
  materials and medications, 57, 59
  pearls and pitfalls, 65
  procedure

        direct laryngoscopy (*see* Direct laryngoscopy)
        induction, 60, 62
        paralysis, 60, 62
        positioning, 60, 62
        postintubation management, 60, 64
        preoxygenation, 60, 62
        preparation, 60, 61
        pretreatment, 60, 62
        proof of placement, 60, 64
Rectal bleeding, 453
Rectal effluent, 431
Rectal pain, 453
Recurrent epistaxis, 313, 325
Re-expansion pulmonary edema, 153, 158
Regional nerve block
    complications, 515
    contraindications, 513
    digital nerve blocks, 523
        intrathecal/tendon sheath approach, 525
        ring block, 524
        web space approach, 524
    external ear block
        auricular ring block, 520
        indications, 520
    facial blocks, trigeminal nerve
        infraorbital nerve block, 517–518
        mental nerve block, 519
        suborbital and supratrochlear nerve block, 519
    general block, procedure for, 515
    indications, 513
    materials and medications, 514
    pearls and pitfalls, 515
    wrist nerve block
        indications, 521
        median nerve block, 522
        nerve distribution in hand, 521
        radial nerve block, 522
        ulnar nerve block, 523
Respiratory failure, 171, 173
Resuscitative thoracotomy, 165–168
    Finochietto retractor, 165, 166
    Lebsche knife, 165, 166
    open cardiac massage, 165, 167
    pericardium, 165, 167
    skin and subcutaneous tissue incision, 165, 167
Retinal detachment
    complications, 289
    contraindications, 287
    graphical representation, 292, 293
    indications, 287
    materials and medications, 287
    pearls and pitfalls, 289
    procedure, 287–288
        anatomy findings, 287, 288
        hyperechoic linear structure, 287, 288
        patient positioning, 287, 288
    ultrasound image, 292
Retrobulbar hemorrhage, 305
Reverse Woods corkscrew maneuver, 672
Rheumatoid arthritis (RA), 90, 625, 630
RSI. *See* Rapid sequence intubation (RSI)
Rubin II maneuver, 672
Rubin I maneuver, 672
Running suture, 540, 541

S
SAFE. *See* Sexual Assault Forensic Examination (SAFE)
Salivary glands, anatomy of, 359
Saphenous vein cutdown, 41
SB tube. *See* Sengstaken-Blakemore (SB) tube
Scalpel-bougie techniques. *See also* Cricothyroidotomy
    materials and medications, 119
    procedure, 121–122
Scalpel-Trousseau technique. *See also* Cricothyroidotomy
    materials and medications, 123
    procedure, 124–125
Scapular manipulation method, 586
Schiøtz tonometer, 297
    complications, 303
    pitfalls, 299
    procedure, 299
Schuknecht suction tube
    cerumen removal, 331
    foreign body removal
        ear, 336–338
        nasal, 326–328
Seidel test, 276
Seldinger technique
    DPL, 397–398
    femoral artery cannulation, 3, 9–10
Sengstaken-Blakemore (SB) tube
    complications, 439
    contraindications, 433
    materials and medications
        cuffalator, 433, 434
        helmet traction setup, 433, 436
        intubation equipment, 433
        lidocaine, 433
        lubricant (water soluble), 433
        scissors, 433, 436
        sphygmomanometer, 433, 434
        sterile water, 433
        suction device and tubing, 433, 435
        syringe with catheter tip, 433, 434
        3-way stop-valve tube connector, 433, 435
        tube clamps, 433, 435
        water and straw, 433
        Y-Tube connector, 433, 435
    pearls and pitfalls, 439
    procedure, 436–438
        balloons, placement of, 436, 437
        sphygmomanometer, connection of, 436, 438
    variceal GI bleed, 433
Sepsis, 685
    Edwards Vigileo System (*see* Edwards Vigileo System)
    fetal, 690
    maternal, 690
    peripheral venous cutdown, 44
Septal hematomas
    contraindications, 322
    indications, 321
    materials and medications, 322
    pitfalls and complications, 324
    procedure
        bilateral hematomas, drainage of, 322–323
        preprocedure, 322
        unilateral hematoma, drainage of, 322, 323

Serum-ascites albumin gradient (SAAG), 451
Sexual Assault Forensic Examination (SAFE)
  contraindications, 477
  indications, 477
  life/limb-threatening injuries, 477
  materials and medications, 477
  pearls and pitfalls, 483
  procedure
    biological material, collection of, 479
    bite marks, 478
    clothing, collection of, 479
    evidence collection kit, 478–480
    forensic interview and history taking, 478
    forensic pelvic examination, 478
    forensic photography, 479
    general physical examination, 478, 481
    informed consent, 478
    injury documentation, 478, 481
    inspection, 478
    investigations, 479
    law enforcement involvement, 478
    prophylaxis, CDC guidelines, 479, 482
    rectal examination, 478
    speculum examination, 478, 482
  SANE, 477
  SART, 477
  survivors, 477
Sexual Assault Nurse Examiner (SANE), 477
Sexual Assault Response Team (SART), 477
Shoulder arthrocentesis, 626, 629
Shoulder, dislocation reduction
  complications, 590
  contraindications, 585
  indications
    anterior dislocations, 583, 584
    inferior dislocations, 583
    posterior dislocations, 583, 584
  materials and medications, 585
  pearls, 590
  procedure
    external rotation method, 587
    Milch technique, 588
    pain management and sedation, 585
    physical examination, 585
    posterior shoulder, 589
    postreduction, 589
    radiographs, 585
    scapular manipulation method, 586
    Spaso technique, 588
    Stimson maneuver, 585
    traction-countertraction method, 589
Shoulder dystocia management
  complications, 675
  contraindications, 669
  indications, 669
  materials and medications, 669
  pearls and pitfalls, 675
  procedure
    accurate documentation, 670
    episiotomy consideration, 670
    Gaskin maneuver, 672
    help recruitment, 670
    McRoberts maneuver, 670, 671
    reverse Woods corkscrew maneuver, 672
    Rubin II maneuver, 672
    Rubin I maneuver, 672
    symphysiotomy, 674
    Woods corkscrew maneuver, 672, 673
    Zavanelli maneuver, 674
Sickle cell anemia, 495
Sickle-solubility test, 495
Silver nitrate stick ablation, 471, 475
Single-dose activated charcoal, 421
Slit lamp
  complications, 276
  contraindications, 272
  corneal foreign body removal, 284
  fluorescein testing (*see* Fluorescein testing)
  indications, 271, 272
  materials, 273
  pitfalls, 276
  procedure, 274–275
Spaso technique, 588
Sphenopalatine artery, 311, 312
Sphygmomanometer, 433, 434
Spine immobilization, 22, 231
Splinting
  complications, 574
  contraindications, 571
  DIP joint reduction, 600
  indications, 571
  materials and medications, 571–572
  procedure, 572–574
  sugar-tong (*see* Sugar-tong splint)
  ulnar gutter (*see* Ulnar gutter splint)
Spontaneous bacterial peritonitis, 451
Sterile urine aspiration. *See* Suprapubic bladder aspiration
Stifneck, 219
Stimson maneuver, 585
  femoral head manipulation, 604, 605
  with hand, 604
  with knee, 604
Stomach pumping. *See* Gastric lavage
Stomal closing, 131
Storz C-Mac, 116
Storz video laryngoscope
  complications, 118
  contraindications, 115
  indications, 115
  materials and medications, 116
  pearls and pitfalls, 118
  procedure
    blade, warming and insertion of, 116, 117
    ETT, placement of, 116, 117
    glotti, direct and indirect visualization of, 116, 117
String and yank technique, 550, 551
Subarachnoid hemorrhage, 241
Subclavian central venous line
  complications, 25–26
  pearls and pitfalls, 24
  procedure, 22–24
Subdural hematoma (SDH), 235
Sublingual abscess, 353
  complications, 356
  contraindications, 354
  incision and drainage, 355
  materials and medications, 354
  pearls and pitfalls, 356
Suborbital nerve block, 517
Subungal hematoma
  causes, 559

  complications, 561
  contraindications, 559
  indications, 559
  materials and medications, 559
  pearls and pitfalls, 561
  procedure
    positioning of needle, 560
    right index finger, 560
    trephination, 560
Sucking chest wound. *See* Open pneumothorax
Sugar-tong splint
  complications, 637
  contraindications, 633
  indications, 633
  materials, 633–634
  pearls and pitfalls, 637
  procedure, 635–637
    arm positioning, 635
    elastic bandage application, 635, 637
    splinting material application over padding, 635, 636
    stockinette positioning, 635
Superpronation method, nursemaid's elbow, 734
Supination method, nursemaid's elbow, 736
Supraglottic airways, 109
Suprapubic bladder aspiration
  complications, 722
  contraindications, 719
  indications, 719
  materials and medications, 719
  pearls and pitfalls, 722
  procedure
    applying negative pressure to syringe, 720
    landmark identification, 720, 721
    needle insertion, 720, 721
    occluding urethral opening, 720
    placing infant in frog-leg position, 720
Supratrochlear nerve block, 517
Surgical airway management. *See* Cricothyroidotomy
Swinging flashlight test, 305
Synchronized electrical cardioversion
  complications, 188
  contraindications, 185
  indications, 185
  materials and medications, 185
  pearls and pitfalls, 188
  procedure, 185–187
    anterolateral position, 186
    anteroposterior position, 186
    defibrillator/cardioverter, 186, 187
    pediatric pad placement, 186, 187
Synovial fluid aspiration. *See* Arthrocentesis

T

Tachyarrhythmias, 29, 193, 194
Tachycardia, 185
  awake patient, 143
  direct laryngoscopy, 74
  non-sinus-rhythm tachycardias, 185
  pacemaker-mediated, 213, 214
  ventilated patient, 143
TBSA. *See* Total body surface area (TBSA)
Temporary dental cement, 381
Temporary pacemakers, 202
Temporomandibular joint (TMJ) dislocation
  closed reduction
    contraindications for, 371
    with local anesthesia, 373
    without local anesthesia, 372
  complications, 374
  materials and medications, 371
  open lock, 371
  pearls and pitfalls, 374
Tension pneumothorax treatment. *See* Needle decompression thoracostomy; Tube thoracostomy
Testicular torsion
  contraindications, 505
  Doppler ultrasound of, 503, 505
  materials and medications, 505
  and normal testicle, schematic of, 503
  pearls and pitfalls, 512
  procedure, 505
  signs and symptoms, 503
Thoracentesis
  complications, 158
  contraindications, 155
  indications, 155
  materials and medications, 155
  pearls and pitfalls, 158
  procedure, 156–157
    intercostal neurovascular bundle, 156, 157
    needle and catheter insertion, 156, 157
    needle insertion mark, 156, 157
    patient positioning, 156
    pleural effusion location and height, 156
    pleural fluid collection via syringe pump method, 156, 157
  re-expansion pulmonary edema, 158
  ultrasound guidance, 158
Thoracic trauma, 159, 161
Thoracostomy
  needle (*see* Needle decompression thoracostomy)
  pneumothorax, 25, 162
  tube (*see* Tube thoracostomy)
Thoracotomy. *See* Emergent thoracotomy
Thread tourniquet. *See* Hair tourniquet
Threatened abortion, 657–659
Three-way stop clock, 701, 709, 713, 715, 716
Thrombin, 314, 377
Thrombosed external hemorrhoid
  complications, 394
  contraindications, 391
  indications, 391
  materials and medications, 391
  pearls and pitfalls, 394
  procedure, 392–393
    buttocks, taping of, 392, 393
    direct lighting over field, 392, 393
    discharge medicines and instructions, 392
    dressing, 392, 393
    jackknife position, 392, 393
    wound closure, 392
Tibia dislocation reduction. *See* Femur dislocation reduction
Tick removal
  complications, 556
  erythema migrans, 556
  indications, 555
  materials and medications, 555
  pearls and pitfalls, 556
  procedure, 555
TMJ dislocation. *See* Temporomandibular joint (TMJ) dislocation

Tonometry
  complications, 303
  contraindications, 297
  impression tonometry, 297
  indications, 297
  Schiøtz tonometer, 297
    pitfalls, 299
    procedure, 299
  Tono-Pen (*see* Tono-Pen tonometry)
Tono-Pen tonometry, 297, 298
  applanation and indentation tonometry, 300
  calibration position, 300
  pitfalls, 301
  pressure-sensitive electronics, use of, 300
  procedure, 301
Tooth avulsion. *See* Dental avulsion
Total body surface area (TBSA), 532, 534
Tourniquet
  hair/thread (*see* Hair tourniquet)
  peripheral venous catheterization, 694, 696, 697
  peripheral venous cutdown, 41, 43
Toxic ingestion treatment. *See* Activated charcoal (AC) adsorption
Tracheal stenosis, 131
Tracheostomy tube (TT) malfunction
  indications, 127
  materials and medications, 127
  obstruction procedure, 127, 128
  pearls and pitfalls
    false lumen during recannulation, 131
    stomal closing, 131
    tracheal stenosis, 131
    unrecognized trachea, 131
    unrecognized tracheoesophageal fistula, 131
  replacement procedure
    bougie/NG tube, 128, 129
    direct insertion, 127, 129
    fingertip technique, 127, 130
Trachlight™, 103, 107
Traction-countertraction method, 585, 589, 609
Transcranial Doppler ultrasonography, 267
Transcutaneous pacing
  contraindications, 193
  indications, 193
  materials and medications, 193
  pearls and pitfalls, 196
  procedure, 194–195
Transillumination, 107
Transtracheal jet ventilation (TTJV)
  complications, 139
  contraindications, 133
  indications, 133
  materials and medications, 133
  pearls and pitfalls, 139
  procedure
    advancing catheter through cricothyroid membrane, 135, 137
    attaching BVM, 135, 138
    attaching catheter, 135, 136
    attaching tubing and regulator, 135
    operating the valve, 135, 138
    palpating cricothyroid membrane, 135, 136
    secure distal end of oxygen tubing, 135, 137
Transvenous cardiac pacing
  complications, 202
  contraindications, 197
  indications, 197
  materials and medications, 198
  pearls and pitfalls, 202
  procedure, 199–201
    cardiac monitor displaying, 201
    guidewire placement, 199, 200
    pacing wire balloon locking lever, 199, 201
    pacing wire position, 201
    ultrasound guidance, 199, 200
Trauma
  FAST examination (*see* Focused assessment with sonography for trauma (FAST) examination)
  nasal, 311
  thoracic, 159, 161
Traumagram, 478, 481
Traumatic effusion treatment. *See* Arthrocentesis
Trichomoniasis, 468
TTJV. *See* Transtracheal jet ventilation (TTJV)
Tubal pregnancy. *See* Ectopic pregnancy
Tube thoracostomy
  complications, 153
  contraindications, 149
  indications, 149
  materials and medications, 149–150
  open pneumothorax, 161
  pearls and pitfalls, 153
  procedure, 151–152
Two-handed seal technique, BVM ventilation, 48, 50
Two-point stabilization technique, 229, 230

U

Ulna bone fracture. *See* Sugar-tong splint
Ulnar gutter splint
  complications, 581
  contraindications, 575
  indications, 575
  materials and medications, 575
  pearls and pitfalls, 581
  procedure, 577–580
Ulnar nerve block, wrist, 523
Ultrasonography
  abortion (*see* Abortion)
  abscess incision and drainage, 565,
  bladder aspiration, 722
  blighted ovum (*see* Anembryonic gestation)
  ectopic pregnancy (*see* Ectopic pregnancy)
  fluid determination, 449, 451
  hydatidiform mole (*see* Hydatidiform mole)
  intraocular pathology (*see* Intraocular pathology)
  lung (*see* Lung ultrasonography)
  pelvic, 647–648
  pericardiocentesis (*see* Pericardiocentesis)
  peripheral intravenous access (*see* Peripheral intravenous (PIV) access, ultrasound-guided)
  placenta previa (*see* Placenta previa)
  pulmonary embolism and heart strain (*see* Pulmonary embolism)
  retinal detachment (*see* Retinal detachment)
  shoulder anatomy, 583, 584
  thoracentesis, 158
Umbilical cord prolapse. *See* Vaginal delivery
Umbilical tape, 701, 703, 705
Umbilical venous catheters (UVC)
  complications, 705
  contraindications, 701
  indications, 701
  insertion procedure

        catheter insertion, 703, 704
        dilating umbilical vein, 703securing catheter, 703, 705
        umbilical catheter tape bridge, creation of, 703, 704
        umbilical vessels, identification of, 703
    materials and medications, 701–702
    pearls and pitfalls, 706
    removal procedure, 705
Unsynchronized cardioversion
    complications, 192
    contraindications, 189
    high-energy shock, 189
    indications, 189
    materials and medications, 189
    pearls and pitfalls, 192
    procedure, 191–192
Upper gastrointestinal (GI) bleeding evaluation. *See* Nasogastric tube (NT) placement
Urine collection. *See* Suprapubic bladder aspiration
Uterine atony
    delivery, 667
    management, 684
Uterine inversion management, 684
UVC. *See* Umbilical venous catheters (UVC)

V
Vaginal bleeding
    anembryonic gestation, 655
    early intrauterine pregnancy, 657
    ectopic pregnancy, 646, 648
    hydatidiform mole, 651
    pelvic examination and wet preparation, 465, 468
    placenta previa, 662, 664
    postpartum hemorrhage, 683
    threatened abortion, 659
Vaginal delivery
    complications, 668
    contraindications, 665
    indications, 665
    materials and medications, 665–667
    pearls and pitfalls, 668
    procedure, 667
Ventricular fibrillation (VF, 181, 185, 188, 189
Ventriculostomy tube. *See* External ventricular drain (EVD)
Vertical mattress suture, 540, 542
Vestibuloocular reflex. *See* Caloric reflex testing
Vision loss. *See* Retinal detachment
Vitreous detachment, 292
Vitreous hemorrhage, 292

W
Web space digital block, 524
Wet preparation. *See* Pelvic examination and wet preparation
Whistler technique, 607
Whole-bowel irrigation (WBI)
    contraindications, 429
    indications, 429
    materials and medications
        bedside commode, 429, 430
        lavage solution bag, 430
        nasogastric tube, 429
        polyethylene glycol-electrolyte solution, 429, 431
    pearls, 431
    procedure, 431
Woods corkscrew maneuver, 672, 673
Word catheter, 471, 472, 474Wound closure
    adhesive tape, 543
    complications, 530
    contraindications, 537
    with cyanoacrylate tissue adhesive
        complications, 547
        contraindications, 545
        indications, 545
        materials and medications, 545
        pearls and pitfalls, 547
        procedure, 546
    and hemostasis, procedure for, 527–529
        dermabond, 528
        direct pressure, Surgicel, 528
        figure-of-eight suture, 528, 529
        high-pressure irrigation, 527, 528
        staples, 527
        two-person approach, 528
        tying absorbable suture, 528, 529
    indications, 537
    methods, 537
    pearls and pitfalls, 530, 544
    preparation, 537
    primary wound repair
        contraindications, 527
        indications, 527
    staple closure, 544
    suture repair
        deep dermal suture, 540, 541
        general guidelines, 539
        half-buried horizontal mattress suture, 540, 543
        horizontal mattress suture, 540, 542
        materials and medications, 538
        recommendations, 540
        running suture, 540, 541
        simple interrupted sutures, 540
        suture material, 539
        suture size, 539
        vertical mattress suture, 540, 542
Wrist fracture, sugar-tong splint. *See* Sugar-tong splint
Wrist nerve blocks
    indications, 521
    median nerve, 522
    nerve distribution in hand, 521
    radial nerve, 522
    ulnar nerve, 523

Y
Y-Tube connector, 433, 435

Z
Zavanelli maneuver, 674

Get Full Access and More at ExpertConsult.com

ATLAS OF PAIN INJECTION TECHNIQUES

SECOND EDITION

Therese O'Connor & Stephen Abram



CHURCHILL LIVINGSTONE
ELSEVIER

Atlas of Pain Injection Techniques

Content Strategist: *Michael Houston*
Content Development Specialist: *Poppy Garraway*
Content Coordinator: *Samuel Crowe*
Project Managers: *Anne Collett/Julie Taylor*
Design: *Stewart Larking*
Illustration Manager: *Jennifer Rose*
Illustrator: *Antbits*
Marketing Manager: *Debashis Das*

ATLAS OF PAIN INJECTION TECHNIQUES

SECOND EDITION

Therese C. O'Connor MB FFARCSI
Consultant Anesthetist, Pain Specialist
Sligo Regional Hospital
Ireland

Stephen E. Abram MD
Professor, Department of Anesthesiology
Medical College of Wisconsin
Milwaukee, WI, USA

CHURCHILL LIVINGSTONE
ELSEVIER

CHURCHILL
LIVINGSTONE
ELSEVIER
an imprint of Elsevier Limited

© 2014, Elsevier Limited. All rights reserved.

First edition 2003

The rights of Therese C. O'Connor and Stephen E. Abram to be identified as authors of this work has been asserted by them in accordance with the Copyright, Designs and Patents Act 1988.

No part of this publication may be reproduced or transmitted in any form or by any means, electronic or mechanical, including photocopying, recording, or any information storage and retrieval system, without permission in writing from the publisher. Details on how to seek permission, further information about the Publisher's permissions policies and our arrangements with organizations such as the Copyright Clearance Center and the Copyright Licensing Agency, can be found at our website: www.elsevier.com/permissions.

This book and the individual contributions contained in it are protected under copyright by the Publisher (other than as may be noted herein).

Notice

Knowledge and best practice in this field are constantly changing. As new research and experience broaden our understanding, changes in research methods, professional practices, or medical treatment may become necessary.

Practitioners and researchers must always rely on their own experience and knowledge in evaluating and using any information, methods, compounds, or experiments described herein. In using such information or methods they should be mindful of their own safety and the safety of others, including parties for whom they have a professional responsibility.

With respect to any drug or pharmaceutical products identified, readers are advised to check the most current information provided (i) on procedures featured or (ii) by the manufacturer of each product to be administered, to verify the recommended dose or formula, the method and duration of administration, and contraindications. It is the responsibility of practitioners, relying on their own experience and knowledge of their patients, to make diagnoses, to determine dosages and the best treatment for each individual patient, and to take all appropriate safety precautions.

To the fullest extent of the law, neither the Publisher nor the authors, contributors, or editors, assume any liability for any injury and/or damage to persons or property as a matter of products liability, negligence or otherwise, or from any use or operation of any methods, products, instructions, or ideas contained in the material herein.

ISBN: 9780702044717

Ebook ISBN: 9780702050343

British Library Cataloguing in Publication Data

A catalogue record of this book is available from the British Library

ELSEVIER
your source for books,
journals and multimedia
in the health sciences
www.elsevierhealth.com

ELSEVIER
Book Aid
International
Working together
to grow libraries in
developing countries
www.elsevier.com • www.bookaid.org

The
publisher's
policy is to use
paper manufactured
from sustainable forests

Printed in China

Last digit is the print number: 9 8 7 6 5 4 3 2 1

DEDICATION

For my Parents
Therese C. O'Connor
To my teachers, my colleagues, my patients and my family
Stephen Abram

ACKNOWLEDGMENT

I would like to acknowledge Florence Grehan, photographer, and the nursing staff of the Day Services Unit, Sligo Regional Hospital.

Therese C. O'Connor

PREFACE TO THE FIRST EDITION

While the role of anesthesiologists in the management of patients with severe or intractable pain has expanded dramatically in the past few decades, it has traditionally been anesthesiologists' ability to use regional anesthetic techniques both diagnostically and therapeutically that has made their contributions to pain medicine unique. This textbook emphasizes those regional anesthetic techniques that have been included in the anesthesiologist's armamentarium for many years. In recent years, there have been dramatic advances in the technology of pain management interventions. These include implantable drug delivery devices, radiofrequency and cryoanalgesia neuroablation techniques, spinal cord and peripheral nerve stimulators, percutaneous nucleoplasty, annuloplasty and vertebroplasty devices. Despite these innovations, there is still a substantial role in acute, chronic and cancer pain management for many of the older, more conventional regional anesthetic techniques.

Nerve blocks play a variety of roles in the management of pain. For acute postoperative or post-traumatic pain, they may be continued throughout the most painful interval, serving as the sole analgesic technique or as adjunctive measures, reducing the need for opioids and other systemic analgesics. For patients with chronic or cancer pain, they may provide long-term benefit by reducing nociceptive inputs to sensitized regions of the spinal cord or brain. They provide periods of antinociception that facilitate physical therapy and reconditioning. Combined with corticosteroids, they reduce neural inflammation and produce neuronal membrane stabilization. They provide diagnostic information regarding sites and mechanisms of pain. Joint and muscular injections also provide an important contribution to the diagnosis and management of chronic pain. In the cancer patient, neurolytic procedures may provide extended periods of interruption of the most active sources of nociception. Long-term infusions of local anesthetics, often combined with opioids and other analgesic agents, can provide weeks to months of relief when systemic analgesics have failed.

Our aim in embarking on the preparation of this atlas was to provide a description of many of the basic regional anesthetic tools and the common joint and muscular injections that may be of benefit to patients with persistent or severe pain. It is unusual for these procedures to be curative on their own. Their value lies in their rational use in combination with other management techniques, including, but by no means limited to, physical therapy, exercise, psychotherapy, and systemic medication. All chapters in the book have been written to a template taking the reader through each block in a consistent and easy-to-follow way. Step-by-step illustrations accompanied by photographs are used to teach technique within the context of the surrounding anatomical structures and we have also highlighted where injections can go wrong and offered advice on how to avoid problems. It is our hope that this atlas will fulfill our aim of providing a strong foundation of regional anesthetic techniques in the treatment of pain.

MECHANISMS OF PAIN TRANSMISSION—AN OVERVIEW OF ANATOMY AND PHYSIOLOGY

1

The term pain is used to define sensations that hurt or are unpleasant. There are, however, different types of pain. Pain following injury can be considered to have a useful protective function by rendering the injured area hypersensitive to external stimuli. Specific groups of primary sensory neurons carry stimuli defining the quality, duration and intensity of noxious stimuli from injured tissue. Their organized projections to the spinal chord or trigeminal nucleus mean that the origin of the stimuli can be precisely located. This somatic pain is often termed "ouch" pain and is usually associated with acute, direct injury to tissue. It arises from structures that are innervated by somatic nerves, e.g. muscle, skin, synovium, and periosteum. Thus the pain is usually easily localized to the distribution of the nerve supplying the injured area, and is often sharp and intense.

On the other hand, pain arising from visceral organs is poorly localized. It may be appreciated as being deep in the body, often arising from the midline, or may be referred to distant structures. The reason for this is that visceral sympathetic afferents converge on the same dorsal horn neuron as do somatic nociceptive afferents, and both of these stimuli travel to the brain via the spinothalamic pathways. Thus, pain is appreciated in the cutaneous area corresponding to the dorsal horn neuron upon which the visceral afferents converge, accompanied by allodynia and hyperalgesia in this dermatome. As a result, reflex somatic motor activity may result in the spasm of muscles. Consequently, cutaneous nociceptors may be stimulated, which may be partly responsible for referred pain. In addition, there is considerable branching of peripheral visceral afferents with resulting overlap in the territory of individual dorsal roots. Compared with somatic nociceptor fibers, only a small number of visceral afferents converge on dorsal horn neurons. This overlap, combined with convergence of visceral afferents on the dorsal horn over a wide number of segments, means that visceral pain is usually dull, vague, and very often poorly localized.

While damage to cutaneous or deep tissue is usually associated with inflammation of that tissue, neuropathic pain is significantly influenced by pathologic changes in peripheral nerve function. Thus neuropathic pain can persist long after the original injury has healed. Pathologic peripheral nerve changes include generation of spontaneous neural inputs, neuroma formation and regeneration of nerves. An injured nerve may become mechanically sensitive, and mild pressure or traction may produce bursts of rapid firing followed by many minutes of after-discharge, perceived as pain in the affected root. With time, the dorsal horn pain projection cells (wide dynamic range neurons) may attain lower thresholds and expanded receptive fields, adding to the traffic from pain fibers. The character of the pain varies and typically may be throbbing, shooting, lancinating, burning or freezing.

Recently, it has become apparent that the receptive-field properties of dorsal horn neurons are not fixed or hard-wired, but can change. The reason for this is that sensory input from primary sensory fibers and interneurons onto spinal neurons is normally too low in amplitude to generate an action-potential discharge in the postsynaptic cell. A temporal or spatial summation of postsynaptic action potentials is required to exceed the threshold of the cell. The center of the receptive field usually constitutes the firing zone, where an adequate stimulus will generate an action-potential discharge in the cell. Surrounding this firing zone is the subliminal zone; a peripheral stimulus evokes a response that is subthreshold. Changes may occur in the area because an increase in excitability of a neuron can convert a previously subthreshold input into a suprathreshold response, leading to receptive-field plasticity, or central sensitization. Thus, afferent barrages of high-frequency C fiber activity can generate changes in sensory processing in the spinal cord, leading to a hyperalgesic state.

Careful investigation of the likely neurologic basis of each patient's pain may help in its treatment; thus whenever possible the following aspects should be determined: site(s), character, radiation, temporal pattern, factors increasing or decreasing pain, and associated factors. An attempt should be made to determine if the pain is somatic, visceral or neuropathic in origin, so that a rationale for treatment may be planned.

In addition, it should be remembered that there are other factors that determine an individual's level of pain perception. Psychologic factors are as important as sensory factors in determining pain perception and are more important in their contribution to suffering. Various responses to painful conditions exist, but depressive features tend to predominate in patients with chronic pain. Analysis of the patient from a psychologic perspective will provide a more thorough understanding of the patient's pain complaint and the ramifications thereof. Being attuned to psychologic issues will enable the physician to plan and execute a more comprehensive treatment plan. The relationship between depression, anxiety and pain is circular or reciprocal, rather than linear. The existence of pain often has detrimental effects on the patient's mood, increasing feelings of anxiety or depression. The development of depression or anxiety can exacerbate the experience of pain.

There have also been many reports about the perception and communication of pain, and its treatment may be influenced by sociodemographic factors. These include ethnicity and cultural background, as well as gender, age, education, and socioeconomic class.

It is therefore important to approach the management of pain bearing foremost in the mind the varying influences on perception of pain.

On the other hand, repeated blockade of sympathetic activity with local anesthetic has been shown to reduce the severity of sympathetically maintained pain. Visceral pain may also be reduced by local anesthetic blockade of visceral afferent fibers that accompany the sympathetic efferents. However, the result is short-lived if pathology remains that will cause continued stimulation; for example, carcinoma of the head of the pancreas causes pain mediated through the celiac plexus. In these cases it is reasonable to consider neurolytic visceral afferent blockade for pain relief.

It has been demonstrated that locally applied corticosteroids prevent development of ectopic discharge and suppress ongoing discharge of injured nerves. Thus in the patient with chronic nerve pain, it is reasonable to consider injection of corticosteroid at the site of injury to a nerve, e.g. epidural or nerve root injection for nerve injury due to intervertebral disc pathology.

Degeneration and inflammation of joints can produce pain that is usually somatic in character, although this may sometimes be difficult to distinguish from neuropathic pain; for example, facet joint pain may be very similar to radicular pain. Joint arthropathy as a cause of pain can be confirmed by injection of local anesthetic into the joint. Addition of corticosteroid to the local anesthetic has been shown to decrease inflammation in the joint and thereby reduce pain.

The myofascial syndrome is a very common cause of somatic pain. It is associated with marked tenderness of discrete points (trigger points) within affected muscles, and with pain that is often referred to an area some distance away. In addition, the affected areas may have the appearance of tight, ropey bands of muscle with associated autonomic changes such as vasoconstriction. Biopsies of such trigger points can show degenerative changes corresponding to the severity of pain (or can show little or no change at all). The most important aspect of the treatment of myofascial pain is to regain the length and elasticity of affected muscles. This is best achieved by physical maneuvers that stretch muscle. However, these maneuvers are often painful and may worsen muscle contraction. Therapy aimed at reducing pain and sensitivity in muscles is best instituted prior to stretching exercises. Trigger-point injections—injection of local anesthetic directly into the trigger point—can confirm the diagnosis of myofascial pain and a series of injections can markedly reduce muscle sensitivity. These injections, combined with stretching exercises, can produce significant analgesia for myofascial pain.

JOINT INJECTIONS 2

2.1 LUMBAR FACET JOINT INJECTION

Anatomy

The zygopophyseal or facet joints (Fig. 2.1.1) are paired articular surfaces between the posterior aspects of adjacent vertebrae. In the cervical region, rotation and flexion are possible as the joint surfaces lie midway between the coronal and the axial planes. Rotation is prevented in the lumbar region but flexion is possible as the anterior portion of the lumbar facet joints lie in the coronal plane and the posterior portions in the sagittal plane. In the thoracic region, the joints' inferior and superior articular surfaces overlap each other in an almost vertical incline.



Fig. 2.1.1

The facet joints bear most of the shear forces when the spine is flexed. In addition, when the intervertebral discs are degenerated, the facet joints carry increased load and weight, especially when the spine is extended. Innervation of the facet joints is via the medial branches of the dorsal rami of the spinal nerves. These nerves also innervate the muscles and ligaments surrounding the joints. Each medial branch divides into proximal and distal branches (Fig. 2.1.2). The proximal branch innervates the



Fig. 2.1.2 Lumbar spine innervation. Innervation of the lumbar spinal structures in the transverse view. Note the posterior primary ramus (Ppr) leaving the spinal nerve (Sn) and splitting into a lateral branch (Lb) and a medial branch (Mb). The medial branch passes under the mamillo-accessory ligament to innervate the facet joint and capsule, the spinous process and the multifidus muscles. Sensory fibers traveling with the gray rami (Gr) form the sinu-vertebral nerve (SvN) and provide sensory function to the disc annulus. (Reproduced with permission from *Cousins and Bridenbaugh's Neural Blockade in Clinical Anesthesia and Management of Pain*, 4th edition, Wolters Kluwer/Lippincott Williams & Wilkins, 2009.)

adjacent facet joint, and the distal branch innervates the next facet joint below. The medial branch also innervates the interspinous ligaments and the multifidus muscles and the lateral branch innervates other adjacent muscles. Thus, pain from irritation of a joint may cause generalized sensitization of the dorsal rami with secondary hyperactivity and spasm of the innervated muscles and may be difficult to localize.

The facet joints contain vascular, highly innervated intra-articular synovial inclusions, which may become trapped and inflamed when the joint is injured, causing pain.

Equipment

- 2 ml and 10 ml syringes
- 25 G needle
- 22 G spinal needle, end-opening
- Non-ionic radio-opaque contrast medium
- ECG, BP, and SpO_2 monitors
- Resuscitation equipment (*see Appendix 3*)
- C-arm fluoroscopy or ultrasound

Drugs

- Lidocaine (lignocaine) 1% 10 ml (or its equivalent)
- Corticosteroid if indicated, e.g. triamcinolone diacetate 25 mg (or its equivalent)
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Prone.
- Pillow under anterior superior iliac spine to flatten the normal lumbar lordosis (*Fig. 2.1.3*).

Needle puncture and technique

- Intravenous access is inserted.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- The lumbar midline and an area 10 cm × 5 cm laterally is cleaned with antiseptic solution.
- The spinous processes of the vertebrae are marked.
- **The insertion point of the needle lies 2–3 cm lateral to the cephalic end of the spinous process of the vertebra** (*Fig. 2.1.4 a,b*).
- C-arm fluoroscopy is positioned at an angle of about 30°, tilted towards the side of the joint to be injected. The angle is adjusted until the joint is well visualized. A radio-opaque object, e.g. the tip of a hemostat, is positioned over the joint and the skin is marked.
- Thereby, with the aid of fluoroscopy, the insertion point is identified.
- A skin wheal is raised and the area is infiltrated with lidocaine (lignocaine) 1%.
- A spinal needle is introduced in a **vertical direction to the skin,** until the needle is observed to enter the joint space, preferably near the lowest aspect of the joint (inferior recess). Confirmation of intra-articular placement is made by **observation of the needle tip remaining on the joint line as the fluoroscope is rotated laterally** (*Fig. 2.1.5*).
- After negative aspiration, 0.5 ml of non-ionic radio-opaque contrast medium (that is compatible with nerve tissue) is injected.
- The correct placement is indicated by outlining the joint with non-ionic radio-opaque contrast medium, visible on anteroposterior and oblique views (*Fig. 2.1.6 a,b*).



Fig. 2.1.3



Fig. 2.1.4



Fig. 2.1.5

Ultrasound may also be helpful in identifying the facet joint (*Fig. 2.1.7*).

- When the correct placement of the needle is confirmed, lidocaine (lignocaine) 1% 0.5 ml plus corticosteroid, e.g. triamcinolone diacetate 25 mg, may be injected and the needle removed while clearing with lidocaine (lignocaine) 1% 1 ml.

Confirmation of a successful injection

- Relief of pain.

Tips

- Care must be taken to inject only a small amount of volume as described above. A total volume of more than 1 ml may damage the joint. If the joint is disrupted anteriorly, drug may spread to the epidural space.

Potential problems

- Solution may spread to the epidural space via the anteromedial capsule.
- Nerve root injection.



Fig. 2.1.6

Lumbar Facet Nerve Injection

- Facet nerve injection may be carried out by placing a spinal needle at the point where the superior articular and transverse processes join as the median branch passes over the cephalad edge of the transverse process (*Fig. 2.1.8*).
- The direct posterior approach should be avoided as the needle placement may be obstructed by the superior portion of the facet joint.
- Approach to the target site from a **lateral oblique angle 30° to skin** is recommended.
- The needle is advanced towards the target site (the posterior-superior edge of the transverse process) until bone is encountered.
- It is recommended that the transverse process be approached first, to determine depth.
- The needle is then repositioned medially until the lateral edge of the facet joint is reached.
- The needle is then moved superiorly until it just "falls off" the superior edge of the transverse process (*Fig. 2.1.9*).
- The optimum position is obtained by repositioning the needle to the postero-superior edge of the transverse process.
- The patient may now report reproduction of back pain.
- Injection of lidocaine (lignocaine) 1% 0.5 ml plus triamcinolone diacetate 25 mg may be carried out for therapeutic effect. Diagnostic blockade may be unreliable as anesthesia of a facet joint means that both nerves supplying the joint should be blocked. However, this means that the joint above and the joint below will also be partially blocked and therefore diagnosis of pain in a particular joint using nerve block is not feasible.

Potential problems

- The same potential problems may occur as described for lumbar facet joint injection (see above).



Fig. 2.1.7 **A** High-resolution sonogram (15-MHz linear transducer) of vertebral bone L3 immersed in water in the cross-axis view. **B** Corresponding anatomic cross-sectional cadaver preparation. Circles indicate targets. ESM erector spinae muscle; N needle; PM psoas muscle; SAP superior articular process; SC spinal channel; TP transverse process; VB vertebral body. (From Greher M, Scharbert G, Kamolz LP, et al, Ultrasound-guided lumbar facet nerve block: a sonoanatomic study of a new methodologic approach. Anesthesiology 2004; 100:1242–8 © 2004 American Society of Anesthesiologists, Inc. Lippincott Williams & Wilkins, Inc.)



Fig. 2.1.8



Fig. 2.1.9

2.2 CERVICAL FACET JOINT INJECTION

Anatomy

The anatomy relevant to injection of the cervical facet joints is similar to that relevant to the lumbar facet joints. The cervical facet joints below the C2–3 level are innervated by the medial branches of the cervical posterior primary rami. These divide into lateral and medial branches after leaving the posterior spinal canal and the splenius capitis muscles cover the medial branch posteriorly. The medial branches lie in close proximity to the vertebral artery and the epidural space is in close proximity to the anterior joint capsule (**Fig. 2.2.1**). The C2–3 facet joint is innervated by the medial branch of the third occipital nerve, which travels beneath the tendonous origin of the splenius capitis muscle where it may be accessed for local anesthetic blockade (**Fig. 2.2.2**).

Equipment

- 2 ml and 10 ml syringes
- 25 G needle
- 22 G spinal needle, end-opening
- Radio-opaque contrast medium
- ECG, BP, and SpO_2 monitors
- Resuscitation equipment (*see Appendix 3*)
- C-arm fluoroscopy or ultrasound

Drugs

- Lidocaine (lignocaine) 1%, 10 ml (or its equivalent)
- Corticosteroid if indicated, e.g. triamcinolone diacetate 25 mg (or its equivalent)
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Prone.
- Neck slightly flexed (*Fig. 2.2.3*).

Needle puncture and technique

Caution: injection of 0.5–1 ml of lidocaine (lignocaine) 1% into the vertebral artery may result in immediate convulsion and/or loss of consciousness with possible cardiovascular system (CVS) collapse.

- Intravenous access is inserted.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- The cervical midline and an area of 7 cm × 5 cm laterally is cleaned with antiseptic solution.
- The spinous processes are marked.



Fig. 2.2.1



Fig. 2.2.2



Fig. 2.2.3



Fig. 2.2.4



Fig. 2.2.5

- **The insertion point of the needle lies 2–3 cm lateral to the cephalic end of the spinous process of the vertebra** (*Fig. 2.2.4*).
- C-arm fluoroscopy is positioned at an angle of about 30°, tilted towards the side of the joint to be injected. The angle is adjusted until the joint is well visualized. A radio-opaque object, e.g. the tip of a hemostat, is positioned over the joint and the skin is marked.
- Thereby, with the aid of fluoroscopy, the insertion point is identified.
- A skin wheal is raised and the area is infiltrated with lidocaine (lignocaine) 1%.
- A spinal needle is introduced in a vertical direction to the skin, until the needle is observed to enter the joint space (*Fig. 2.2.5*). Confirmation of intra-articular placement is made by observation of the needle tip remaining on the joint line as the fluoroscope is rotated (*Fig. 2.2.6*) or on ultrasound.
- After negative aspiration, 0.5 ml of non-ionic radio-opaque contrast medium (that is compatible with nerve tissue) is injected.
- The correct placement is indicated by outlining the joint with non-ionic radio-opaque contrast medium, visible on anteroposterior and oblique views.
- When the correct placement of the needle is confirmed, lidocaine (lignocaine) 1% 0.5 ml plus corticosteroid, e.g. triamcinolone diacetate 25 mg, may be injected and the needle removed while clearing with lidocaine (lignocaine) 1% 1 ml.

Confirmation of a successful injection

- Relief of pain.



Fig. 2.2.6



Fig. 2.2.7

Tips

- Care must be taken to inject only a small amount of volume, as described above. A total volume of more than 1 ml may damage the joint. If the joint is disrupted anteriorly, a drug may spread to the epidural space.

Potential problems

- Solution may spread to the epidural space via the anteromedial capsule.
- Nerve root injection.
- Intrathecal injection resulting in spinal anesthesia may occur if local anesthetic is inadvertently injected into the nerve root sleeve. Prompt recognition of this complication is vital during cervical procedures, because the patient's breathing may be arrested and there may be immediate convulsion and/or loss of consciousness with CVS collapse requiring immediate resuscitation. In addition, the patient's head should be immediately elevated after the injection to ensure that the lidocaine (lignocaine) flows inferiorly. Some practitioners elevate the head of the table during all cervical injections to help prevent this complication. Intravenous injection may be harmless, but it results in a suboptimal or false-negative result.
- Intra-arterial injection may result in immediate convulsion and/or loss of consciousness with possible CVS collapse. Intrarterial injection can be dangerous if the agent is injected into the vertebral artery or radicular branches that enter the neural foramina at various levels and, rarely, persisting paraplegia or paraparesis have been reported after cervical facet joint injection or nerve root block. These complications may be due to embolism from intra-arterial injection of particulate corticosteroid. However, even when contrast injection prior to steroid infiltration confirms extravascular needle placement, nerve damage may occur, which suggests an alternative cause for the complication, such as vasospasm or direct arterial injury from the needle-tip. Regardless of the cause, contrast injection is recommended to at least potentially reduce the risk of intravascular injection. Ultrasound will have limitations in this regard.
- Hematoma may occur (avoid performing block on patients who have coagulopathy).

CERVICAL FACET NERVE INJECTION

- Facet nerve injection may be carried out by placing a spinal needle at the point where the superior articular and transverse processes join as the median branch passes over the cephalad edge of the transverse process (*Fig. 2.2.7*).
- The direct posterior approach should be avoided as the needle placement may be obstructed by the superior portion of the facet joint.
- Approach to the target site from a **lateral oblique angle 30° to the skin** is recommended.
- The needle is advanced towards the target site (the posterior–superior edge of the transverse process) until bone is encountered.
- It is recommended that the transverse process be approached first, to determine depth.

- The needle is then repositioned medially until the lateral edge of the facet joint is reached.
- The needle is then moved superiorly until it just “falls off” the superior edge of the transverse process.
- The optimum position is obtained by repositioning the needle to the posterosuperior edge of the transverse process.
- The patient may now report reproduction of back pain.
- Injection of lidocaine (lignocaine) 1% 0.5 ml plus triamcinolone diacetate 25 mg may be carried out for therapeutic effect. Diagnostic blockade may be unreliable as anesthesia of a facet joint means that both nerves supplying the joint should be blocked. However, this means that the joint above and the joint below will also be partially blocked and therefore diagnosis of pain in a particular joint using nerve block is not feasible.

2.3 SACRO-ILIAC JOINT INJECTION

Anatomy

The surfaces of the sacrum and ilium form a synovial joint, the sacro-iliac joint. Ligaments and connective tissue surround the joint, conferring stability and preventing excessive movement of the joint (**Figs 2.3.1**, **2.3.2**). The joint is innervated by L4, L5, S1 (the superior gluteal nerve), S2, and L3. Localization of the pain is therefore difficult due to this wide nerve supply to the joint.

Equipment

- 2 ml and 10 ml syringes
- 25 G needle
- 22 G spinal needle, end-opening
- Radio-opaque contrast medium
- ECG, BP, and SpO_2 monitors
- Resuscitation equipment (*see Appendix 3*)
- C-arm fluoroscopy or ultrasound


Disaligned joint with pressure
Posterior sacro-iliac ligament
Sacrospinalis muscle

Fig. 2.3.1

Drugs

- Lidocaine (lignocaine) 1%, 10 ml (or its equivalent)
- Corticosteroid if indicated, e.g. triamcinolone diacetate 25 mg (or its equivalent)
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Prone.
- Pillow under anterior superior iliac spine to flatten the normal lumbar lordosis (*Fig. 2.3.3*).

Needle puncture and technique

- Intravenous access is inserted.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- The sacral area is prepared antiseptically.
- An AP image is obtained, centered over the joint to be injected.
- Two joint lines are observed. The posterior joint line is located more medial in a direct AP view (*Fig. 2.3.4a*). The image intensifier (positioned above the patient) is rotated toward the opposite side until the two joint lines



Fig. 2.3.2



Fig. 2.3.3



Fig. 2.3.4



Fig. 2.3.5



Fig. 2.3.6

are superimposed (usually about 10–20°) (*Fig. 2.3.4b*). The skin is marked and a skin wheal is raised. The area is infiltrated with lidocaine (lignocaine) 1% **over the joint line 1 cm above the most caudal point of the joint.**

- A 22 or 25 G 3½ in spinal needle is advanced no more than 1 cm into the joint. Some resistance is usually felt as the needle contacts the joint.
- A lateral view is then obtained. The needle should traverse no more than half the distance across the sacrum, and should never be advanced beyond the anterior cortex.
- Contrast dye, 0.5 to 1 ml, may be injected to ensure intra-articular spread. Intravascular injection is best detected during "live" fluoroscopy injection. In the AP view, dye should be seen within the joint space. Some extravasation outside the joint is common. If extensive, the needle should be repositioned.
- 1–2 ml lidocaine 1% is injected alone for diagnostic purposes. Reproduction of the patient's pain during needle positioning and injection as well as pain relief following the block will help confirm the sacro-iliac joint as the pain generator (avoid sedation with opioids for diagnostic procedures).
- Corticosteroid, e.g. triamcinolone diacetate 25 mg, plus 1–2 ml 1% lidocaine may be injected for therapeutic effect.
- Ultrasound may also be used to identify the joint (*Fig. 2.3.5*).
- CT scan may also be used to identify the joint but is not usually necessary (*Fig. 2.3.6*).

Confirmation of a successful injection

- Reproduction of pain during injection and relief of pain following injection confirms correct placement.
- Radiologic assessment of the X-ray image after injection of contrast medium may demonstrate tears in the joint capsule.

Tips

- While the joint may be easily entered, injection can be difficult where the joint is heavily invested with connective tissue and ligaments. This is especially true in elderly patients, where the joint is rigid and the joint space cannot expand to accommodate a volume of liquid. In such cases it may be possible to inject only as the needle is being removed from the joint.
- Sometimes, injection into the deep sacro-iliac ligaments around the joint may be helpful for pain relief. Introduction of a spinal needle just above the midline of the upper sacrum and advanced at 45° to the skin, under the rim of the ilium and in the direction of the joint, will access these ligaments. Lidocaine (lignocaine) 1% 4 ml plus triamcinolone diacetate 25 mg may then be injected.

Potential problems

- Discomfort on injection.
- Epidural injection.
- Sacral nerve root blockade.
- Subperiosteal injection (painful in the awake patient).

EPIDURAL INJECTION

3

Intervertebral disc disease may produce inflammation of spinal nerve roots, which may be the cause of radicular pain. The L5 and S1 nerve roots are most commonly affected, probably because they exit the bony canal through a narrow lateral bony recess, therefore increasing the likelihood of nerve compression and irritation. Lumbo-sacral radiculopathy consists of low-back pain that radiates a varying distance into the lower extremity, and which may be associated with motor and sensory loss consistent with damage to the affected nerve root. If bowel and bladder symptoms of dysfunction are present, large midline disc protrusion is suspected and prompt surgical intervention is indicated. Otherwise, if severe pain exists after treatment with immobilization and mild analgesics, epidural steroid injection may be carried out. Similarly, pain of thoracic or cervical disc origin may respond to epidural steroid injection.

Triamcinolone diacetate is the most commonly administered preparation and injection should be carried out as close to the affected nerve root as possible. Injection of a small amount of local anesthetic with the steroid will help to confirm drug placement and provide analgesia. In patients with S1 pathology the drug may not spread to the affected nerve root using the lumbar approach and the caudal approach to the epidural space may be required. Cervical epidural injection accesses the cervical spinal nerve roots, while in the thoracic region a paramedian approach is usually more successful.

3.1 LUMBAR EPIDURAL BLOCK

Anatomy

Structures encountered when inserting an epidural needle include skin, subcutaneous tissue, supraspinous ligament, interspinous ligament, ligamentum flavum (5–6 mm thick in the midline of the lumbar region, 3–5 mm thick in the midline of the thoracic region), prior to reaching the epidural space itself (**Fig. 3.1.1**). Beyond this space lies the dura mater, the arachnoid mater and intrathecal space containing the cerebrospinal fluid. The spinal cord usually ends at the L2 level (**Fig. 3.1.2**).

One should expect a distance of 3.5–6 cm from skin to the epidural space using a midline approach. In the lumbar region the spinous processes are generally perpendicular to the vertebral bodies (**Fig. 3.1.3**). In the thoracic region the spinous processes lie at an angle of 30–45° to the thoracic vertebral body, thus making midline epidural injection a little more difficult, and sometimes necessitating a paravertebral approach. Other relevant anatomy of the vertebral bodies is illustrated in **Fig. 3.1.4**.

Equipment

- 2 ml and 10 ml syringes
- 18 G, 20 G, and 25 G needles
- ECG, BP, and SpO_2 monitors
- 18 G epidural set (*Fig. 3.1.5*)
- Filter aspiration needle
- Resuscitation equipment (*see Appendix 3*)
- Fluoroscopy (optional)
- Ultrasound (optional)



Fig. 3.1.1

Drugs

- Lidocaine (lignocaine) 1%, 10 ml (or its equivalent)
- Corticosteroid if indicated, e.g. triamcinolone diacetate 50 mg (or its equivalent)
- Saline (NaCl) 10 ml
- Resuscitation drugs (*see Appendix 3*)



Fig. 3.1.2


(a) Cervical
(b) Thoracic
(c) Lumbar

Fig. 3.1.3

Position of patient

- Lateral, usually lying on the side of the radiculopathy.
- Shoulders and buttocks parallel to the edge of the bed, perpendicular to the floor, with spine flexed.

Needle puncture and technique

- Intravenous access is inserted.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- The midline and an area 10 cm × 5 cm laterally is cleaned with antiseptic solution and a fenestrated drape is placed over the sterile area.
- Lidocaine (lignocaine) 1% 2 ml is drawn up into three 2 ml syringes.
- Lidocaine (lignocaine) 1% 2 ml, plus corticosteroid, e.g. triamcinolone diacetate 50 mg is drawn up into the 10 ml syringe.
- NaCl 10 ml is drawn up into the 10 ml loss-of-resistance syringe.
- The iliac crest is palpated and the intercrestal line (this corresponds with the inferior aspect of the spinous process of L4 or may lie in the L4–5 interspace) is identified (*Fig. 3.1.6*).
- The spinous processes are palpated, and the level requiring injection is identified.
- This may be confirmed by fluoroscopy or ultrasound.


Superior articular process
Pedicle
Transverse process
Spine
Inferior articular process
Facet
Facet
Superior articular process
Transverse process
Inferior articular process
Lamina
Inferior and superior articular facets
Transverse process
Pedicle
Vertebral foramen

Fig. 3.1.4


FOR LOSS OF RESISTANCE TECHNIQUE

Fig. 3.1.5

MIDLINE APPROACH FOR THE RIGHT-HANDED OPERATOR

With the left hand

- The fore- and middle fingers are placed each side of the interspace.



Fig. 3.1.6

- These fingers are kept in place until the epidural needle is gripped by the interspinous ligament.

With the right hand

- The interspinous ligament is infiltrated with lidocaine (lignocaine) 1% 2 ml.
- **The epidural needle is inserted, bevel facing the side of the radiculopathy, between the fore- and middle fingers of the left hand in a direction 60° cephalad, perpendicular to the spine, parallel to the floor, until it is gripped by the interspinous ligament** (*Fig. 3.1.7 a,b*). In the case of thoracic epidural injection (midline approach), the point of entry of the needle should be as close as possible to the caudal end of the interspinous space and the needle directed 30–45° cephalad to enter between the spinous processes.
- The hub of the needle is gripped with the fore- and middle fingers of the left hand and this hand is steadied by leaning the wrist against the patient's back.
- The stylet is removed and the loss-of-resistance syringe is applied.



Fig. 3.1.7

- The needle is slowly and carefully advanced, while constant pressure is applied to the plunger, the left hand aiding the advance, while at the same time applying a brake if required (*Fig. 3.1.8 a,b*).
- At the point at which the needle enters the ligamentum flavum, absolute resistance to injection is experienced.
- At this point the needle is advanced very slowly until a sudden loss of resistance to the pressure on the plunger is experienced, the point at which the epidural space is entered.
- After negative aspiration for blood or cerebrospinal fluid (CSF), lidocaine (lignocaine) 1% 3 ml is injected.
- After 5 minutes the patient is questioned about any changes in sensation or power, and any changes in heart rate or blood pressure are noted.
- If the injection is for diagnostic purposes only, the needle may be removed at this point.
- If therapeutic effect is required, lidocaine (lignocaine) 1% 2 ml, plus corticosteroid if indicated, e.g. triamcinolone diacetate 50 mg (or its equivalent), may be injected. Alternatively, a catheter may be inserted through the needle if indicated.
- The needle is flushed with NaCl 1 ml and removed.
- The patient is allowed to lie in the lateral position, on the side of the pain.



Fig. 3.1.8

- Monitors should be left attached and i.v. access left in situ for at least 30 minutes.
- The patient is advised to contact the hospital should the anesthesia remain after several hours.

FLUOROSCOPIC GUIDED LUMBAR EPIDURAL INJECTION

- Position the patient prone with a pillow under the lower abdomen to increase lumbar flexion.
- The interlaminar space for the desired segmental level is identified fluoroscopically using a straight AP view. Angling the fluoroscope slightly cephalad may open the space if it appears very narrow.
- Prepare skin with antiseptic and sterile drape.
- Raise a local anesthetic skin wheal just below the interlaminar space, about 0.5 cm from the midline toward the symptomatic side.
- Advance the Tuohy needle, angling slightly toward the midline until resistance of the ligamentum flavum is encountered, keeping the trajectory just lateral to the midline to avoid contacting the spinous process. Repeat imaging periodically to ensure that the needle is approaching the space, not the lamina or spinous process (see *Fig. 3.1.9*). Advance the needle through the ligamentum flavum using a loss of resistance technique with air or saline. Once loss of resistance is achieved, obtain a lateral view to ensure the needle is barely into the bony spinal canal.
- Attach a low volume extension set to the needle, aspirate to ensure there is no blood return, and inject 0.5–1 ml of non-ionic contrast medium during live fluoroscopy. Dye should be seen spreading within the bony canal (see *Fig. 3.1.10*). Prior to injecting local anesthetic or steroid, obtain an AP view to reconfirm epidural spread.



Fig. 3.1.9



Fig. 3.1.10

- Aspirate again, then inject local anesthetic (1–2 ml) and 50 mg triamcinolone diacetate or equivalent.
- Loss of resistance is occasionally encountered with the needle superficial to the epidural space. Dye will be seen dorsal to the epidural space on the lateral view, and spread lateral to the spinal canal will be seen on the AP view. The needle can then be advanced through the ligamentum flavum, again using loss of resistance, followed by dye confirmation.

Confirmation of a successful block

- Relief of pain.
- Anesthesia in the distribution of the blocked nerves.
- For lumbar epidural steroid injection, improvement in straight-leg raising may be evident.

Tips

- Air may be used instead of NaCl to determine loss of resistance. If this technique is used it is advisable to avoid constant pressure on the plunger, as the air is compressible; instead it should be bounced intermittently with the thumb to test for resistance and loss of resistance.
- Advocates claim identification of CSF is easier with this technique.
- Advocates of the use of NaCl point out that absolute resistance to pressure identifies the ligamentum flavum, and that by applying constant pressure to the plunger one can identify loss of resistance earlier, thereby more easily avoiding the possibility of dural tap.
- An epidural catheter may be inserted through the needle and the needle removed, taking care not to withdraw the catheter when removing the needle. However, a test dose of lidocaine (lignocaine) 1% 4 ml with/without epinephrine (adrenaline) 1:200 000 is given after insertion, before any injection through the catheter is carried out.
- Ultrasound may guide the insertion of the needle as spinous proccesses are easily visible on ultrasound (optional) (*Fig. 3.1.11*).



Fig. 3.1.11

- Injection of radio-opaque dye under direct fluoroscopy can confirm epidural placement.
- Insertion of a radio-opaque epidural catheter may be carried out also under fluoroscopy.

Potential problems

IMMEDIATE

- Failure to locate epidural space (sitting position may be successful).
- Intravascular injection (test dose important); addition of epinephrine (adrenaline) to test dose may help identification of intravascular injection.
- Intrathecal injection (test dose important).
- Hypotension due to sympathetic blockade (give i.v. fluid; consider ephedrine).
- Headache (possible dural puncture).
- Allergic reaction.

LATER

- Infection (epidural abscess; bacterial meningitis).
- Aseptic meningitis; usually a result of intrathecal injection (test dose important).
- Cushingoid symptoms; usually as a result of repeated steroid injections.

3.2 THORACIC EPIDURAL BLOCK

Anatomy

In the thoracic region, the spinous processes lie at an angle of 30–45° to the thoracic vertebral body (**Fig. 3.2.1 a,b**) thus making midline epidural injection a little more difficult, and sometimes necessitating a paramedian approach (**Fig. 3.2.2 a–d**).

Equipment

- 2 ml and 10 ml syringes
- 18 G, 20 G, and 25 G needles
- ECG, BP, and SpO_2 monitors
- 18 G epidural set
- Resuscitation equipment (*see Appendix 3*)
- Fluoroscopy or ultrasound (optional)

Drugs

- Lidocaine (lignocaine) 1%, 10 ml (or its equivalent)
- Corticosteroid if indicated, e.g. triamcinolone diacetate 50 mg (or its equivalent)
- Saline (NaCl) 10 ml
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Lateral, usually lying on the side of the radiculopathy.
- Shoulders and buttocks parallel to the edge of the bed, perpendicular to the floor, with spine flexed.

Needle puncture and technique

- Intravenous access is inserted.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- The midline and an area 10 cm × 5 cm laterally is cleaned with antiseptic solution and a fenestrated drape is placed over the sterile area.
- Lidocaine (lignocaine) 1% 2 ml is drawn up into three 2 ml syringes.
- Lidocaine (lignocaine) 1% 2 ml, plus corticosteroid, e.g. triamcinolone diacetate 50 mg, is drawn up into the 10 ml syringe.
- NaCl 10 ml is drawn up into the 10 ml loss-of-resistance syringe.
- The spinous processes are palpated, and the level requiring injection is identified.
- This may be confirmed by fluoroscopy or ultrasound.



Fig. 3.2.1



Fig. 3.2.2

Paramedian approach

FOR THE RIGHT-HANDED OPERATOR

With the left hand

- The fore- and middle fingers are placed each side of the interspace.
- These fingers are kept in place until the epidural needle is gripped by the interspinous ligament.

With the right hand

- The interspinous ligament is infiltrated with lidocaine (lignocaine) 1% 2 ml.
- **The insertion point of the epidural needle in the paravertebral approach lies 1 cm lateral to the midline, at the lower border of the spinous process** (*Fig. 3.2.3 a,b*). The epidural needle is inserted, bevel facing the side of radiculopathy, between the fore- and middle fingers of the left hand, perpendicular to the spine, parallel to the floor, until it is gripped by the interspinous ligament.
- **The direction of the needle is 130° cephalad and 15° medial to the midline.** Care must be taken as the ligamentum flavum is not as thick laterally, and may not be identified as easily. Therefore, it is usually easiest to first identify the lamina and **walk the needle off the lamina in a cephalad direction** until the needle enters the ligamentum flavum. At that point the loss-of-resistance technique may be performed.
- The hub of the needle is gripped with the fore- and middle fingers of the left hand and this hand is steadied by leaning the wrist against the patient's back.
- The stylet is removed and the loss-of-resistance syringe is applied.
- The needle is slowly and carefully advanced until the osseous endpoint of the lamina is encountered.
- It is then walked off the lamina in the cephalad direction until it enters the ligamentum flavum.
- At the point at which the needle enters the ligamentum flavum, absolute resistance to injection is experienced.
- It is then carefully advanced further while constant pressure is applied to the plunger, the left hand aiding the advance, while at the same time applying a brake if required (*Fig. 3.2.4*, viewed from above).
- The needle is advanced very slowly until a sudden loss of resistance to the pressure on the plunger is experienced, the point at which the epidural space is entered.
- After negative aspiration for blood or cerebrospinal fluid, lidocaine (lignocaine) 1% 2 ml is injected.


Transverse process
Facet
Lamina
Spinous process
Paramedian approach (spinal or epidural)
15
Midline approach (spinal or epidural)
A
L3
15
1cm
L4
L5
B

Fig. 3.2.3

- After 5 minutes the patient is questioned about changes in sensation or power, and any changes in heart rate or blood pressure are noted.
- If the injection is for diagnostic purposes only, the needle may be removed at this point.
- If therapeutic effect is required, lidocaine (lignocaine) 1% 2 ml plus corticosteroid, e.g. triamcinolone diacetate 50 mg, may be injected.
- The patient is allowed to lie in the lateral position, on the side of the pain.
- Monitors should be left attached and i.v. access should remain in situ for at least 30 minutes.



Fig. 3.2.4

- The patient is advised to contact the hospital should anesthesia remain after several hours.

Confirmation of a successful block

- Relief of pain.
- Anesthesia in the distribution of blocked nerves.
- For lumbar epidural steroid injection, improvement in straight-leg raising may be evident.

Tips

- Air may be used instead of NaCl to determine loss of resistance. If this technique is used it is advisable to avoid constant pressure on the plunger, as the air is compressible; instead the plunger should be bounced intermittently with the thumb to test for resistance and loss of resistance.
- Advocates claim identification of CSF is easier with this technique.
- Advocates of the use of NaCl point out that absolute resistance to pressure identifies the ligamentum flavum, and that by applying constant pressure to the plunger one can identify loss of resistance more immediately, thereby avoiding the possibility of dural tap more easily.
- An epidural catheter may be inserted through the needle and the needle removed, taking care not to withdraw the catheter when removing the needle. However, a test dose of lidocaine (lignocaine) 1% 4 ml with epinephrine (adrenaline) 1:200 000 is given after insertion, before any injection through the catheter is carried out.
- Identification of the insertion point may be aided by ultrasound (*Fig. 3.2.5*).
- Injection of radio-opaque dye under direct fluoroscopy can confirm epidural placement.
- Insertion of a radio-opaque epidural catheter may be carried out also under fluoroscopy.



Fig. 3.2.5

Potential problems

IMMEDIATE

- Failure to locate epidural space (sitting position may be successful).
- Intravascular injection (test dose important); addition of epinephrine (adrenaline) to test dose may help identification of intravascular injection.
- Intrathecal injection (test dose important).
- Hypotension due to sympathetic blockade (give i.v. fluid, consider ephedrine).
- Headache (possible dural puncture).
- Allergic reaction.
- Spinal cord injury may occur if the epidural space is not recognized. Deep sedation should be avoided during needle insertion and drug injection.

LATER

- Infection (epidural abscess, bacterial meningitis).
- Aseptic meningitis, usually the result of intrathecal injection (test dose important).
- Cushingoid symptoms (usually as a result of repeated injections).
- Epidural hematoma. This complication should be suspected when sensory or motor function loss occurs minutes to hours after the procedure. Immediate diagnostic imaging (CT or MRI) is essential. Prompt surgical decompression may be required.

3.3 CERVICAL EPIDURAL BLOCK

Anatomy

In the cervical region, the spinous processes are almost perpendicular to the vertebral bodies, especially in the lower part. They also widen and become bifid. As a result, insertion of the needle is often easy. However, it must be remembered that the epidural space is relatively narrow in this area (2–4 mm), and that the spinal cord lies very close to it (**Fig. 3.3.1 a,b**). Most workers prefer to use the "hanging drop" technique when accessing the cervical epidural space, as there exists a significant negative pressure in the cervical region in the sitting position.

Equipment

- 2 ml, 5 ml, and 10 ml syringes
- 18 G, 20 G, and 25 G needles
- ECG, BP, and SpO_2 monitors
- 18 G epidural set
- Resuscitation equipment (*see Appendix 3*)
- Fluoroscopy or ultrasound (optional)

Drugs

- Lidocaine (lignocaine) 1%, 10 ml (or its equivalent)
- Corticosteroid if indicated, e.g. triamcinolone diacetate 50 mg (or its equivalent)
- Saline (NaCl) 10 ml
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Sitting.
- Head flexed forward.

Needle puncture and technique

- Intravenous access is inserted.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- The midline and an area 10 cm × 5 cm laterally is cleaned with antiseptic solution and a fenestrated drape is placed over the sterile area.
- Lidocaine (lignocaine) 1% 2 ml is drawn up into two 2 ml syringes.
- Lidocaine (lignocaine) 1% 1 ml plus corticosteroid, e.g. triamcinolone diacetate 50 mg, is drawn up into a 5 ml syringe.
- NaCl 10 ml is drawn up into a 10 ml syringe.
- The patient is allowed to sit up straight for a moment, and the spinous process of T3, which lies opposite the root of the spine of the scapula, is identified and marked. The prominent spinous process of C7 (vertebra prominens) is identified (*Fig. 3.3.2*) and marked (*Fig. 3.3.3 a,b*). Ultrasound can be used to guide needle placement (*Fig. 3.3.3 c,d*). The interspace to be used for epidural injection is also marked.



Fig. 3.3.1



Fig. 3.3.2



Fig. 3.3.3

FOR THE RIGHT-HANDED OPERATOR

With the left hand

- The fore- and middle fingers are placed each side of the interspace.
- These fingers are kept in place until the epidural needle is gripped by the interspinous ligament.

With the right hand

- The interspinous ligament is infiltrated with lidocaine (lignocaine) 1% 2 ml.
- **The epidural needle is inserted, bevel facing caudad, between the fore- and middle fingers of the left hand in a direction 60° cephalad, until it is gripped firmly by the interspinous ligament.**
- The hub of the needle is gripped with the fore- and middle fingers of the left hand and this hand is steadied by leaning the wrist against the patient's spine.
- The stylet is removed.
- The hub of the epidural needle is filled with saline (*Fig. 3.3.4*) such that a "hanging drop" appears (*Fig. 3.3.5*).

With both hands

- The wings of the epidural needle are gripped with each hand, steadying the hands by resting the wrists against the posterior thoracic wall (*Fig. 3.3.6*).
- The needle is slowly and carefully advanced with both hands.
- It is prudent periodically to confirm high resistance of the needle in the ligament by testing with an air-filled syringe, then replace the stylet to make sure there is no tissue blocking the needle before resuming the "hanging drop" technique.



Fig. 3.3.3, cont'd



Fig. 3.3.4



Fig. 3.3.5

- The "hanging drop" at the hub of the needle is watched closely, and the patient is asked periodically about the presence of paresthesia.
- At the point at which the epidural needle enters the epidural space, the drop should appear to be sucked into the needle (*Figs 3.3.7*, *3.3.8*).
- After negative aspiration for blood or CSF, lidocaine (lignocaine) 1% 2 ml is injected.
- After 1–2 minutes the patient is questioned about changes in sensation or power, and any changes in heart rate or blood pressure are noted.
- If the injection is for diagnostic purposes only, the needle may be removed at this point.
- If therapeutic effect is required, lidocaine (lignocaine) 1% 1 ml plus corticosteroid, e.g. triamcinolone diacetate 50 mg, may be injected.
- The patient is allowed to lie in the lateral position, on the side of the pain.
- Monitors should be left attached and i.v. access kept in situ for at least 30 minutes.



Fig. 3.3.6



Fig. 3.3.7

- Ultrasound may aid in identifying the interspinous space as spinous processes are easily visible.

FLUOROSCOPIC GUIDED CERVICAL EPIDURAL INJECTION

- Check MRI to ensure that the spinal cord is not displaced posteriorly. If the posterior epidural space is compromised or the spinal cord is shifted posteriorly, it is safer to enter the upper thoracic epidural space and advance a radio-opaque catheter to the low cervical level.
- Position patient prone, with pillow under shoulders, neck flexed, arms at sides, shoulders as far downward as possible.



Fig. 3.3.8

- Identify targeted interlaminar space (T1–2, C7–T1, or C6–7) in direct AP fluoroscopic view. Adjust angle upward or downward slightly to maximize view of interlaminar space.
- Mark skin over lower border of T1–2, C7–T1 (preferred) or C6–7 interlaminar space just lateral to the midline. Do not perform epidural injection above C6–7 because of absence of midline epidural fat at higher levels.
- Prepare skin with antiseptic and sterile drape.
- Provide only minimal sedation or no sedation. Instruct patient to report any pain or paresthesia during the procedure.
- Infiltrate skin and subcutaneous tissue with lidocaine (lignocaine) 1%.
- Advance the Tuohy needle through the insertion point into the interspinous ligament and check the fluoroscopy image to ensure the needle tip is directed toward the midline (*Fig. 3.3.9*).
- Begin to advance through the ligament using loss of resistance with air or saline. Check lateral view if possible (may be obscured by the shoulders). Proceed with needle advancement. When loss of resistance



Fig. 3.3.9



Fig. 3.3.10

occurs, recheck the lateral view. If unable to visualize the spinal canal, obtain slightly oblique view (*Fig. 3.3.10*).

- Attach a low volume extension set to the needle and inject a small volume (1 ml or less) of non-ionic contrast medium under live fluoroscopy, preferably in lateral view (AP or oblique view is used if this is not possible) (*Fig. 3.3.11*), then observe the AP view to confirm epidural dye spread.
- Aspirate to ensure there is no blood return, then inject 1–2 ml lidocaine (lignocaine) 1% followed by 25–50 mg triamcinolone diacetate or equivalent.

Confirmation of a successful block

- Relief of pain.

Tips

- Loss-of-resistance techniques may also be used to access the cervical epidural space.
- The steroid may be given soon after the test dose, as hypotension may be a problem if the patient remains in the sitting position.

Potential problems

IMMEDIATE

- Failure to locate epidural space (lateral position with loss of resistance technique may be successful).
- Pain on injection (caution: close proximity to spinal cord).
- Intrathecal injection (test dose important).
- Hypotension ± bradycardia due to sympathetic blockade (maximum 3 ml local anesthetic administered in this technique).
- Vasovagal syncope is common in young adult patients.



Fig. 3.3.11

- Intravascular injection; addition of epinephrine (adrenaline) 1:200 000 to the test dose may aid identification of intravascular injection.
- Headache (possible dural puncture).
- Allergic reaction.
- Spinal cord injury may occur if the epidural space is not recognized. Deep sedation should be avoided during needle insertion and drug injection.

LATER

- Infection (epidural abscess, bacterial meningitis).
- Aseptic meningitis, usually the result of intrathecal injection (test dose important).
- Cushingoid symptoms (usually as a result of repeated injections).
- Epidural hematoma. This complication should be suspected when sensory or motor function loss occurs minutes to hours after the procedure. Immediate diagnostic imaging (CT or MRI) is essential. Prompt surgical decompression may be required.

3.4 CAUDAL EPIDURAL BLOCK

Anatomy

Injection of anesthetic through the sacral hiatus allows access to the sacral epidural space or caudal anesthesia. The sacrum is roughly triangular in shape and is made up of five fused sacral vertebrae (**Fig. 3.4.1**). Its dorsal aspect is convex and there is a midline sacral canal that allows passage of the sacral nerves through four pairs of foramen, anteriorly and posteriorly. At the caudal end lies the coccyx, and at the cephalad end lies the fifth lumbar vertebra. The posterior wall of S5, and sometimes S4, is unfused. The thick fibrous sacro-coccygeal membrane or sacral hiatus covers the defect. This may be variable in size as the posterior wall of other sacral vertebrae may also be unfused. Penetration of this membrane allows access to the sacral epidural space.

Equipment

- 2 ml, 5 ml, and 20 ml syringes
- 18 G, 20 G, and 25 G needles
- 22 G, 3–5 cm short-bevel needle, with stylet
- ECG, BP, and SpO_2 monitors
- Resuscitation equipment (*see Appendix 3*)
- Fluoroscopy or ultrasound (optional)

Drugs

- Lidocaine (lignocaine) 1%, 10 ml (or its equivalent)
- Corticosteroid if indicated, e.g. triamcinolone diacetate 50 mg (or its equivalent)
- Saline (NaCl) 10 ml
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Prone.
- Pillow under abdomen and/or operating table broken to allow flexion of the lumbo-sacral spine.
- Lower limbs abducted 15°, toes rotated to point towards the opposite foot (*Fig. 3.4.2*).

Needle puncture and technique (adult)

- Intravenous access is inserted.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- The midline and an area 10 cm × 5 cm laterally is cleaned with antiseptic solution and a fenestrated drape is placed over the sterile area.



Fig. 3.4.1



Fig. 3.4.2

- Lidocaine (lignocaine) 1% 2 ml is drawn up into three 2 ml syringes.
- Lidocaine (lignocaine) 1% 15 ml plus corticosteroid, e.g. triamcinolone diacetate 50 mg, is drawn up into the 20 ml syringe.
- NaCl 10 ml is drawn up into the 10 ml syringe.

FOR THE RIGHT-HANDED OPERATOR

With the left hand

- The posterior superior iliac spines are identified.
- The sacral cornua (the unfused spinous processes of S5) are also identified and marked.
- Between the cornua lies the base of the sacral hiatus, a roughly triangular fibroelastic structure.
- The index and middle fingers of the left hand are placed on each of the sacral cornua (*Fig. 3.4.3*).
- **The insertion point lies between these two fingers.**

With the right hand

- The insertion point is infiltrated with lidocaine (lignocaine) 1% 2 ml.
- The 22 G short-bevel needle with stylet is inserted at an angle of 45° to the skin (*Fig. 3.4.4. a,b*). Ultrasound can be used to guide needle placement (*Fig. 3.4.4c*).
- As the needle passes through the fibroelastic sacral hiatus, a "pop" may be experienced, although this is not always evident in adults, and bone may be contacted.
- After passing through the sacral hiatus, the needle is withdrawn a little, and redirected to an angle to the skin of 15–20° (*Fig. 3.4.5*). This should allow further advancement of 1–2 cm, as the needle enters the long axis of the caudal epidural space.
- After negative aspiration, lidocaine (lignocaine) 1% 2 ml is injected.
- After 5 minutes the patient is questioned about changes in sensation or power of the lower limbs, and any changes in heart rate or blood pressure are noted.
- Then lidocaine (lignocaine) 1% 5–15 ml plus corticosteroid, e.g. triamcinolone diacetate 50 mg, may be injected in order to promote spread to upper sacral and lower lumbar segments (a volume of at least 10 ml should be used if the symptoms are at the level of S1 nerve root or higher) (*Fig. 3.4.6*). The needle is then



Fig. 3.4.3



Fig. 3.4.4



Fig. 3.4.5



Fig. 3.4.6



Fig. 3.4.7

removed while clearing it with lidocaine (lignocaine) 1% 2 ml.

- Monitors should be left attached and i.v. access kept in situ for at least 30 minutes.
- It is prudent to warn the patient about possible loss of sensation and or power of one or both lower limbs.

FLUOROSCOPIC GUIDED CAUDAL EPIDURAL INJECTION

- This approach may be used for treating L5 or S1 radiculopathy. It is a reasonable alternative to the interlaminar approach when surgery has disrupted the posterior spinal anatomy.
- Position the patient prone.
- Locate the sacral hiatus using the sacral cornua as landmarks.
- Prepare skin with antiseptic and sterile drape.
- Place the tip of a sterile blunt instrument over the sacral hiatus and obtain a lateral fluoroscopic view of the sacrum.
- Raise a skin wheal with 1% lidocaine (lignocaine) just below the sacral hiatus and infiltrate with lidocaine down to the sacral hiatus with a small gauge needle.
- Advance a Tuohy needle at a 45° angle to the skin through the sacral hiatus, checking a lateral fluoroscopic view to make sure the needle has entered the spinal canal. Lower the needle angle and advance the needle slightly. Recheck lateral fluoroscopy to ensure the needle is in the spinal canal.
- Aspirate to rule out intravascular placement and inject 0.5–1 ml contrast medium under live fluoroscopy. Check a lateral and AP image to ensure epidural spread.
- If no epidural catheter is used, inject a mixture of local anesthetic and steroid. Inject 10 ml 0.5% lidocaine plus 50 mg triamcinolone diacetate. This volume should be sufficient to reach the L5 or S1 nerve roots.
- Alternatively, a radio-opaque catheter can be inserted through the needle and advanced to the desired level. Check the catheter position in both AP and lateral views (*Fig. 3.4.7*). Attach the injection hub to the catheter and inject 0.5–1 ml contrast medium under live fluoroscopy, rechecking dye spread in both AP and lateral views (*Fig. 3.4.8*). Inject 1–2 ml 1% lidocaine plus 50 mg triamcinolone diacetate or equivalent.



Fig. 3.4.8

Confirmation of a successful block

- Relief of pain.
- Anesthesia or diminished sensation in distribution of blocked nerves.
- Improvement in straight-leg raising (although for sacral nerve root-related pain, this may not have been positive prior to caudal blockade).

Tips

- After location of the caudal epidural space, the left hand may be placed over the sacral hiatus while 10 ml saline is rapidly injected (*Fig. 3.4.6*). Misplacement of the needle in the subcutaneous tissue (*Fig. 3.4.9*) should be evident if the injection is appreciated by the palpating left hand.
- Subperiosteal injection in the awake patient will cause pain (*Fig. 3.4.10*). The needle angle is important as the tip may come to lie anterior to the sacrum (*Fig. 3.4.11*).
- Anatomic variations exist in many patients, making access to the caudal epidural space difficult or impossible. Fluoroscopy using lateral views is useful to confirm the epidural needle position. Ultrasound may also be helpful in identifying the sacro-coccygeal membrane.



Fig. 3.4.9



Fig. 3.4.10



Fig. 3.4.11

Potential problems

IMMEDIATE

- Failure to locate epidural space.
- Intravascular injection (test dose important); addition of epinephrine (adrenaline) to test dose may help identification of intravascular injection.
- Intrathecal injection, rare but possible (test dose important).
- Hypotension due to sympathetic blockade (give i.v. fluid, consider ephedrine).
- Transient exacerbation of radiculopathic pain (caution patient).
- Headache (possible dural puncture, rare).
- Allergic reaction.

LATER

- Infection (epidural abscess, bacterial meningitis).
- Aseptic meningitis, usually the result of intrathecal injection (test dose important).
- Cushingoid symptoms (usually as a result of repeated injections).
- Infection (epidural abscess).
- Epidural hematoma.

3.5 LONG-TERM EPIDURAL CATHETER INSERTION

Anatomy

As described for lumbar epidural block in Section 3.1.

Equipment

- 2 ml and 10 ml syringes
- 18 G, 20 G, and 25 G needles
- ECG, BP, and SpO_2 monitors
- 18 G epidural set
- Epidural catheter passer
- A surgical pack, including small scalpel and suture set
- Resuscitation equipment (*see Appendix 3*)
- Fluoroscopy or ultrasound (optional)

Drugs

- Lidocaine (lignocaine) 1% (preservative free) 20 ml (or its equivalent)
- Lidocaine (lignocaine) 1% (preservative free) 4 ml plus epinephrine (adrenaline) 1:200 000
- Saline (NaCl) 10 ml

Position of patient

- Lateral, lying on side of radiculopathy (*Fig. 3.5.1*).
- Shoulders and buttocks parallel to the edge of the bed, perpendicular to the floor, with spine flexed.

Needle puncture and technique

- Intravenous access is inserted.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- The midline and an area 10 cm × 5 cm laterally is cleaned with antiseptic solution and a fenestrated drape is placed over the sterile area.
- Lidocaine (lignocaine) 1%, 2 ml is drawn up into three 2 ml syringes.
- Lidocaine (lignocaine) 1% 10 ml is drawn up into one 10 ml syringe.
- NaCl 10 ml is drawn up into the 10 ml loss-of-resistance syringe.
- An epidural catheter is inserted through the needle as previously described, 5–6 cm into epidural space (see Section 3.1).
- The needle is withdrawn 1–1.5 cm, but *is not removed.*
- After negative aspiration, a test dose of lidocaine (lignocaine) 1% 4 ml, with epinephrine (adrenaline) 1:200 000, is given. After 5 minutes the patient is questioned about changes in sensation or power, and any changes in heart rate or blood pressure are noted.
- After a negative reaction lidocaine (lignocaine) 1% 10 ml is injected slowly over 10 minutes. Assessment of the level of blockade is carried out after a further 15 minutes.
- Subcutaneous infiltration around the epidural needle with lidocaine (lignocaine) 1% is carried out. Note: a small incision is made to include the epidural needle (*Fig. 3.5.2*).
- A purse string suture is placed around the epidural needle, *but is not tied* (*Fig. 3.5.3*).
- Another small incision in the lateral abdominal wall is made after subcutaneous infiltration with lidocaine (lignocaine) 1% (*Fig. 3.5.4*). A catheter passer is tunneled through the subcutaneous tissue between the two incision sites.
- A catheter is manually bent to a curve and tunneled through the subcutaneous tissue between the two incision sites in the direction from the abdominal site to the epidural needle site (*Fig. 3.5.5*).
- The epidural needle is carefully removed (*Figs 3.5.6, 3.5.7*).
- The catheter is secured to subcutaneous tissue in the midline by tightening the purse string suture (*Fig. 3.5.8*).
- The catheter is further secured using an angle piece and then threaded in a lateral direction through the catheter



Fig. 3.5.1



Fig. 3.5.2



Fig. 3.5.3



Fig. 3.5.6



Fig. 3.5.4



Fig. 3.5.5



Fig. 3.5.7



Fig. 3.5.8



Fig. 3.5.9

passer from the needle site to the abdominal wall site and connections are secured (*Fig. 3.5.9*).

- A pump may be placed in the abdominal wall site and the skin incisions closed.

Confirmation of a successful block

- Relief of pain.
- Anesthesia or diminished sensation in the distribution of affected nerves.

Tips

- Injection of radio-opaque dye under direct fluoroscopy can confirm epidural placement.
- Insertion of a radio-opaque epidural catheter may be carried out also under fluoroscopy.
- Ultrasound may aid insertion

Potential problems

- As described for lumbar epidural block in Section 3.1.
- However, in view of the long-term nature of epidural catheter implantation, any symptoms of infection should be immediately investigated and treated.
- Epidural catheters should not be inserted or removed during anticoagulation. Coagulation and platelet function should be normalized before catheter removal.

SOMATIC NERVE BLOCKADE

4

Mechanical nerve root compression was originally thought to be the cause of pain in discogenic radiculopathy. However, it has been found that many asymptomatic patients demonstrate substantial disc protrusion on magnetic resonance (MR) imaging, myelography and subsequent autopsy examination. In addition, surgical decompression does not result in uniform success in the relief of such pain. Following a period of mechanical nerve-root compression it is likely that an acute inflammatory process ensues, resulting in intraneural accumulation of serum proteins and fluid, raised intraneural pressure, ischemia and axonal degeneration. Degenerating glycoprotein material from the nucleus pulposis may also contribute to the inflammatory process.

There are many situations in which injection of spinal nerve roots with local anesthetic may be helpful in the diagnosis of radicular pain. These include those where investigations including electromyography, computer tomography (CT) or MR imaging are not consistent with the clinical findings, where there are multiple levels of pathology, and after spinal surgery with subsequent scarring in the area of the surgery. In addition, the contribution of the somatic nerve root may be elucidated in pain of uncertain origin, e.g. chest pain or abdominal pain, by specific nerve root local anesthetic injection.

It may be used therefore to determine the level of surgery, if indicated, and the addition of steroid may produce longer-lasting pain relief.

4.1 INTERCOSTAL NERVE BLOCK

Anatomy

The intercostal nerve is made up of several types of nerves: sympathetic white and grey rami communicantes, cutaneous and motor fibers supplied by dorsal rami, sensory fibers to the chest wall, anterior and posterior, via the lateral cutaneous branch, and further sensory fibers to the anterior chest wall via the anterior cutaneous branch. The lateral cutaneous branch exits just distal to the angle of the rib. Just below the inferior edge of the rib, in the intercostal groove, lie the intercostal nerve, artery and vein, the latter lying superior to the nerve. The optimal site to block the intercostal nerve is the most posterior point at which the rib is palpable, usually the angle of the rib (**Fig. 4.1.1 a,b**).



Fig. 4.1.1

Equipment

- 2 ml and 5 ml syringes
- 30 G needle
- 22 G 3–4 cm short-bevel needle
- Extension set (optional)
- ECG, BP, and SpO_2 monitors
- Resuscitation equipment (*see Appendix 3*)
- Ultrasound (optional)

Drugs

- Lidocaine (lignocaine) 1% 2 ml for skin infiltration
- Lidocaine (lignocaine) 1% 5 ml (or its equivalent)
- Corticosteroid if indicated, e.g. triamcinolone diacetate 50 mg (or its equivalent)
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Prone (this allows best access, although a lateral or supine position may also be used).
- Pillow under mid-abdomen to widen the intercostal spaces.
- Arms hanging over sides of table to rotate the scapulae laterally.

Needle puncture and technique

- Intravenous access is inserted.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- Sedation may be administered if multiple blocks are being performed.
- The midline and an area 10 cm × 10 cm laterally is cleaned with antiseptic solution and a fenestrated drape is placed over the sterile area.
- The midline is palpated and marked.
- **The inferior edge of the rib is palpated and marked at the most posterior point at which the rib is palpable; this is the insertion point** (*Fig. 4.1.2*). If multiple blocks are planned these marks will form a line that becomes more medial towards the cephalad end as the scapulae are avoided laterally (*Fig. 4.1.2*).

FOR THE RIGHT-HANDED OPERATOR

With the left hand

- The inferior edge of the rib is palpated with the fore- and middle fingers (*Fig. 4.1.3*).



Fig. 4.1.2



Fig. 4.1.3



Fig. 4.1.4

- The skin is drawn up over the rib itself.
- The fingers of the left hand will grip the needle-hub for controlled advancement of the needle once contact with the rib is made during injection.

With the right hand

- The insertion point is infiltrated with lidocaine (lignocaine) 1% using a 2 ml syringe and a 30 G needle.
- The 22 G short-bevel needle with syringe attached is inserted between fore- and middle finger of the left hand in a direction 15–20° cephalad, until it makes contact with the rib (*Figs 4.1.4, 4.1.5*).
- The needle-hub is gripped with the fingers of the left hand and this hand is steadied by leaning the wrist against the patient's posterior chest wall.
- With the right and left hands acting as one unit, the needle is walked off the edge of the rib until it enters the intercostal space immediately below the rib (*Fig 4.1.6*). Alternatively, a catheter may be inserted between the needle and syringe and injection may then be carried out by a second operator, while the first maintains the needle steady in the correct position (*Fig. 4.1.7*).
- It is then advanced 2 mm.
- After negative aspiration, 3–4 ml of local anesthetic, plus corticosteroid if indicated, is injected and the needle is withdrawn.
- Monitors are left attached and i.v. access left in situ for at least 30 minutes.
- Chest X-ray is performed if pneumothorax is suspected.



Fig. 4.1.5



Fig. 4.1.6



Fig. 4.1.7

Confirmation of a successful block

- Relief of pain.
- Anesthesia in the distribution of the blocked nerve.

Tips

- The approximate depth to the rib may be determined with the left fore- and middle fingers before insertion of the needle.
- Insertion of the needle > 2 mm deeper than the rib when intercostal space is reached is avoided. This will minimize the risk of pneumothorax, as the average distance from the rib to the pleura is 8 mm. If patient coughs on injection, pneumothorax is suspected.
- Neurolytic intercostal nerve block, e.g. with alcohol 50% 3 ml (made up by combining equal parts of alcohol 100% and lidocaine (lignocaine) 1% or its equivalent), or phenol 6%, may be carried out after local anesthetic block confirms accurate placement of the needle as described above. However, it is important to note that injection may result in subarachnoid spread of a neurolytic agent with resultant possible permanent spinal cord damage.
- Ultrasound may aid accurate placement of the needle (*Fig. 4.1.8*). Injection of non-ionic radio-constrast medium may also aid accurate placement of the needle in neurolytic block (*Fig. 4.1.9*).
- Placement of a catheter into the intercostal space can be achieved by threading 3 cm of catheter through an 18 G epidural needle after the intercostal neurovascular bundle has been identified as above.



Fig. 4.1.8



Fig. 4.1.9

Radiofrequency lesioning

- Radiofrequency lesioning of the intercostal nerve is simple and has a low level of side effects. The lesioning is carried out using the same method of placement of the needle as described for intercostal nerve block with local anesthetic.
- However, after placement of the needle and confirmation of accuracy by fluoroscopy (as described above), a trial of stimulation is carried out using 2 V at 50 Hz. If the needle has been placed accurately the patient should experience paresthesiae in the distribution of that intercostal nerve. A pulsed radiofrequency lesion may then be produced at 40–45 °C for 5 minutes or 49–60 °C for 90 seconds.

Potential problems

- Injection within the nerve sheath can result in the spread of anesthetic to the subarachnoid space.
- Intercostal block in patients with severe respiratory problems should be avoided as there is risk of a pneumothorax. Careful observation of a small pneumothorax is usually all that is required but failure to re-expand the lung may require chest tube insertion.
- Because of the vascularity of the intercostal space, there may be rapid absorption of local anesthetic and systemic effects can occur quickly, especially with multiple blocks. However, peak plasma concentration of local anesthetic may occur 15–20 minutes after the block is performed, when systemic toxicity effects may develop. Addition of epinephrine (adrenaline) to the anesthetic solution may decrease the peak plasma concentration of local anesthetic.
- If aspiration of blood occurs, the needle should be removed, keeping the left fore- and middle fingers in place. The needle is cleared, reinserted to contact the rib again, and the block is continued as above.

- Care of the airway must be remembered if sedation is administered to a patient in the prone position.
- Complications of neurolytic intercostal nerve block include pneumothorax, infection (especially in the immunocompromised patient) as well as post-lesioning intercostal nerve neuritis. The frequency of the latter in radiofrequency lesioning increases as higher temperatures are used. Intercostal nerve neuritis usually responds to local injection of lidocaine (lignocaine) 1% 3 ml plus triamcinolone diacetate 20 mg to the lesion site.

4.2 INTERPLEURAL BLOCK

Anatomy

The parietal pleura lines the thoracic wall, the thoracic surface of the diaphragm and the lateral mediastinum. The visceral pleura completely covers the surface of the lung. Both the pleural layers become contiguous at the root of the lung. Between the two pleural layers lies the interpleural space (**Fig. 4.2.1**). Injection of local anesthetic into this space produces an interpleural block by topical contact with free nerve endings within the pleura, and by local diffusion to nerves in the vicinity of the injection site. These include the intercostal nerves, the sympathetic chain, and the inferior part of the brachial plexus. Local anesthetic solution may also track to the epidural and subarachnoid spaces producing blockade.

Equipment

- 2 ml and 10 ml syringes
- 18 G, 20 G, and 25 G needles
- ECG, BP, and SpO_2 monitors
- 18 G epidural set
- Well-lubricated 5 ml glass syringe
- Resuscitation equipment (*see Appendix 3*)

Drugs

- Lidocaine (lignocaine) 1% 10 ml
- Levobupivacaine 0.25%, 20 ml (or its equivalent)
- Saline (NaCl) 10 ml
- Resuscitation drugs (*see Appendix 3*)



Fig. 4.2.1

Position of patient

- The technique described here relies on negative interpleural pressure to identify the interpleural space. Therefore the patient should be breathing spontaneously for this technique.
- Semi-prone.
- Side to be blocked uppermost, supported by a pillow (*Fig. 4.2.2*).
- The arm should be allowed to fall forwards in front of the body to rotate the scapula anterolaterally.

Needle puncture and technique

- Intravenous access is inserted.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- The midline and an area 15 cm × 12 cm laterally is cleaned with antiseptic solution and a fenestrated drape is placed over the sterile area.
- Lidocaine (lignocaine) 2%, 2 ml is drawn up.
- Levobupivacaine 0.25% 20 ml is drawn up.
- Air is drawn up into a well-lubricated 5 ml syringe.
- The seventh and eighth ribs are palpated and marked.



Fig. 4.2.2



Fig. 4.2.3

- **A point approximately 10 cm from the midline, immediately superior to the eighth rib, is marked; this is the insertion point** (*Fig. 4.2.3*).

FOR THE RIGHT-HANDED OPERATOR

With the left hand

- The fore- and middle fingers are placed each side of the insertion point, palpating the superior aspect of the eighth rib.
- These fingers are kept in place until the epidural needle passes through the subcutaneous tissue.

With the right hand

- A skin wheal is raised at the insertion point.
- The epidural needle is inserted between the fore- and middle fingers of the left hand, taking care that the point of entry of the needle is as close as possible to the superior aspect of the eighth rib. This helps to avoid damage to the neurovascular bundle, which lies immediately inferior to the seventh rib.
- After passage through the subcutaneous tissue, the hub of the needle is gripped with the fore- and middle fingers of the left hand and this hand is steadied by leaning the wrist against the patient's posterior chest wall.
- The stylet is removed and the well-lubricated glass syringe containing 3 ml air is applied (*Fig. 4.2.4*).
- The needle is slowly and carefully advanced, with no pressure applied to the plunger, the left hand aiding the advance, while at the same time applying a brake if required.
- Resistance from the tissues prevents the plunger from advancing.
- At the point at which the needle enters the interpleural space a definite click is experienced, negative pressure draws the air in and the barrel drops (*Fig. 4.2.5*).



Fig. 4.2.4

- Taking care not to allow air entry into the interpleural cavity, a catheter is inserted approximately 10 cm into the interpleural space (*Fig. 4.2.6*). **Once the catheter is in position it is best to place the patient supine, tilted slightly, with the side to be blocked upwards** (*Fig. 4.2.7 a,b*). **(If blockade of the upper thoracic segments is required the patient is tilted head-down).**
- After negative aspiration and a test dose, 10–15 ml levobupivacaine 0.25% (or its equivalent) in divided doses of 5 ml is injected.
- Infusion of local anesthetic may be set up for continuous analgesia.
- Monitors should be left attached and i.v. access left in situ while the catheter is in place.
- Chest radiograph may be performed to rule out pneumothorax.

Confirmation of a successful block

- Relief of pain.
- Anesthesia in the distribution of the blocked nerves.


Pleural
reflection
8–10 cm
A
Air
Parietal
pleura
B
Visceral pleura
C
D

Fig. 4.2.5


Epidural
needle
Intercostal
muscle
Skin
Rib
Neurovascular bundle
Parietal pleura
Visceral pleura
Lung
Epidural catheter

Fig. 4.2.6


Supine
Pleural cavity
Pericardial cavity
Lung
Phrenic nerve
A
Local anesthetic
solution
Sympathetic
chain
Splanchnic
nerve
B
Local anesthetic
solution

Fig. 4.2.7

Tips

- As an alternative technique, the barrel of the syringe may be removed and the open syringe filled with NaCl or local anesthetic and advanced until the fluid level begins to fall as the solution is sucked into the interpleural space (*Fig. 4.2.8*).
- Also, a bag containing NaCl 500 ml may be attached to the epidural needle via a giving set, and drops observed on entry to the interpleural space (*Fig. 4.2.9*).
- Ultrasound may aid placement of the needle (*Fig. 4.2.10*).

Potential problems

- Pneumothorax.
- Unpredictable analgesia. The mechanism of action of interpleural block is still unproven and spread of the local anesthetic solution may be unpredictable. The duration of the block may be decreased when a thoracotomy drainage tube is present.



Fig. 4.2.8



Fig. 4.2.9



Fig. 4.2.10

4.3 LUMBAR NERVE ROOT BLOCK

Anatomy

The lumbar nerves are made up of sensory and motor fibers to the trunk and lower limbs, and sympathetic white and grey rami communicantes. Each lumbar nerve exits via the intervertebral foramen which lies just inferior to the caudad edge of the transverse process of the respective vertebral body, and passes anteriorly over the lateral aspect of the transverse process of the vertebral body below (**Fig. 4.3.1**). It then branches into posterior and anterior branches. The posterior branch supplies the paravertebral muscles and cutaneous fibers to the back. The anterior branch passes through the substance of the psoas muscle and branches further, communicating with the other anterior branches to form the lumbar plexus. As a result there is significant overlap of nerve supply. The fascial layers of the psoas muscle prevent spread of local anesthetic to the sympathetic lumbar chain. It may be helpful to consider blockade of a lumbar nerve root to be similar to intercostal nerve block except that the transverse process is present instead of a rib and the insertion site is therefore more medial.

Equipment

- 2 ml and 10 ml syringes
- 25 G needle
- 22 G spinal needle, end-opening
- Radio-opaque contrast medium
- ECG, BP, and SpO_2 monitors
- Resuscitation equipment (*see Appendix 3*)
- Fluoroscopy or ultrasound



Fig. 4.3.1

Drugs

- Lidocaine (lignocaine) 1% 10 ml (or its equivalent)
- Corticosteroid if indicated, e.g. triamcinolone diacetate 25 mg (or its equivalent)
- Resuscitation drugs

Position of patient

- Prone.
- Pillow under the anterior superior iliac spine to flatten the normal lumbar lordosis (*Fig. 4.3.2*).

Needle puncture and technique

- Intravenous access is inserted.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- The lumbar midline and an area 10 cm × 5 cm laterally is cleaned with antiseptic solution and a fenestrated drape is placed over the sterile area.
- The iliac crests are palpated and the intercrestal line is identified. This corresponds with the inferior aspect of the spinous process of L4 or may lie in the L4–5 interspace (*Fig. 4.3.3 a*).
- The spinous processes are counted until the level to be blocked is identified and confirmed with fluoroscopy.
- The spinous processes of the vertebrae are marked (*Fig. 4.3.3 b*).
- **The insertion point of the needle lies 2–3 cm lateral to the cephalic end of the spinous process of the vertebra. The nerve corresponding to each vertebra emerges just below the transverse process of that vertebra at this site** (*see Appendix 6*).
- Therefore, with the aid of fluoroscopy, the insertion point is identified.
- A skin wheal is raised and the area is infiltrated with lidocaine (lignocaine) 1%.
- A spinal needle is introduced in a vertical direction to the skin, until the needle contacts bone at an approximate depth of 3–5 cm, the transverse process of that vertebra (*Fig. 4.3.4 a,b*).



Fig. 4.3.2



Fig. 4.3.3

- The needle is then walked off the transverse process in the caudad direction and advanced 1.5–2 cm, the site of the emerging nerve root (*Fig. 4.3.5*).
- It is useful to confirm the needle tip over the intervertebral foramen with fluoroscopy.
- Paresthesia in the distribution of the nerve may be experienced.
- After aspiration, non-ionic radio-opaque contrast medium 1 ml is injected.
- The correct placement is indicated by outlining the nerve root with non-ionic radio-opaque contrast medium, visible on anteroposterior and lateral fluoroscopic views (*Fig. 4.3.6*).
- After further aspiration, lidocaine (lignocaine) 1% 0.5–1 ml is injected.
- After 5 minutes the patient is questioned about changes in pain, sensation and power of the lower limb.
- For diagnostic nerve root blockade, the needle may be removed when the level causing pain is identified.
- Ultrasound may also aid placement of the needle (*Fig. 4.3.7*).



Fig. 4.3.4

Confirmation of a successful block

- Relief of pain and anesthesia in distribution of the blocked nerve.

Tips

- As in the case of thoracic nerve root block, it has also been recommended that the needle is angled 20° medially after entering the paravertebral space. However care must be taken, with the aid of fluoroscopy, not to inject local anesthetic solution into the nerve sheath allowing tracking of the solution centrally to produce intrathecal blockade.

Potential problems

- Intrathecal injection.
- Epidural blockade usually occurs with this block, but this is not a problem once low volumes are used. However, even small volumes of epidural spread may confound the diagnostic value of the block.
- Sympathetic blockade is unlikely, but it may occur and cause hemodynamic changes.
- Intravascular injection. Injection of particulate steroids into a radicular artery can cause spinal cord infarction. Particulate steroids should never be injected near the foramen unless intravascular placement has been ruled out using live fluoroscopy contrast dye injection, preferably with digital subtraction technique.


1
2
3cm
Sympathetic chain
Lumbar nerve

Fig. 4.3.5



Fig. 4.3.7



Fig. 4.3.6

4.4 THORACIC NERVE ROOT BLOCK

Anatomy

The anatomy relevant to thoracic paravertebral nerve root blockade is very similar to the anatomy relevant to lumbar paravertebral nerve root block, except that:

- ribs are present instead of the rudimentary ribs of the lumbar spine, the transverse processes;
- the lung and pleura are in close proximity to the injection site, therefore the risk of pneumothorax is significant;
- unlike the lumbar region, where the needle passes through the substance of the psoas muscle, the needle passes through connective tissue only in the thoracic region (*Fig. 4.4.1 a,b*);
- the fascial layers of the psoas muscle prevent spread to the sympathetic lumbar chain. However, such layers do not exist in the thoracic region, and paravertebral injection usually results in sympathetic blockade.

Equipment

- 2 ml and 10 ml syringes
- 25 G needle
- 22 G spinal needle, end-opening
- Radio-opaque contrast medium
- ECG, BP, and SpO_2 monitors
- Resuscitation equipment and drugs (*see Appendix 3*)
- Fluoroscopy or ultrasound

Drugs

- Lidocaine (lignocaine) 1% 10 ml (or its equivalent)
- Corticosteroid if indicated, e.g. triamcinolone diacetate 25 mg (or its equivalent)
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Prone (the block requires localization of the transverse process and can be performed in a lateral, sitting or prone position) (*Fig. 4.4.2*).

Needle puncture and technique

- Intravenous access is inserted.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- The thoracic midline and an area 10 cm × 5 cm laterally is cleaned with antiseptic solution.


Anterior costotransverse ligament
A
Pleura
Sympathetic ganglion
Anterior costotransverse ligament
Nerve
Rib
Lamina
B

Fig. 4.4.1



Fig. 4.4.2

- The inferior angle of the scapula is identified; this lies at the level of the spinous process of T7.
- The root of the spine of the scapula is identified; this lies at the level of the spinous process of T3.
- The spinous processes are counted until the level to be blocked is identified, and confirmed with fluoroscopy.
- The spinous processes of vertebrae are then marked.
- **The insertion point of the needle lies 1.5–3 cm lateral to the cephalic end of the spinous process of the vertebra, usually midway between the ribs** (*Fig. 4.4.3 a,b*).
- The nerve corresponding to each vertebra emerges just below the transverse process of that vertebra at this site.
- Therefore, with the aid of fluoroscopy, the insertion point is identified.
- A skin wheal is raised and the area is infiltrated with lidocaine (lignocaine) 1%.
- The transverse process is identified under fluoroscopy and the spinal needle is introduced in a direction perpendicular to the skin until the needle contacts bone.
- A slightly mesiad inclination avoids the pleura and increases the chances of placing the needle tip near the nerve root.
- Care must be taken to avoid the pleura by not advancing the needle any further than is necessary to locate the transverse process, approximately 3 cm. If the needle does not contact the transverse process by 3 cm, it should be withdrawn and re-advanced in a more caudad, and subsequently more cephalic, direction, again taking care not to advance beyond 3 cm.
- The needle is then walked off the caudad edge of the transverse process until it slips off the edge (*Fig. 4.4.4 a,b*). It is then advanced 1 cm, the site of the emerging nerve root at that level.
- It is useful to confirm the needle tip over the intervertebral foramen with fluoroscopy.
- Paresthesia in the distribution of the nerve may be experienced.


A
Anterior costotransverse ligament
Posterior costotransverse ligament
Azygos vein
Lung
Thoracic duct
Esophagus
Aorta
Greater splanchnic nerve
Thoracic sympathetic chain
1.5cm
B
Superior costotransverse ligament

Fig. 4.4.3

- After aspiration, radio-opaque contrast medium 1 ml, is injected.
- The correct placement is indicated by outlining the nerve root with non-ionic radio-opaque contrast medium, visible on anteroposterior and lateral views (as in the description of lumbar somatic nerve injection in Section 4.3).
- Ultrasound may aid placement of needle.



Fig. 4.4.4

- After further aspiration, lidocaine (lignocaine) 1% 0.1–1 ml is injected.
- After 5 minutes the patient is questioned about changes in pain and sensation in the distribution of the nerve root.
- For diagnostic nerve root blockade the needle may be removed when the level causing pain is identified.

Confirmation of a successful block

- Relief of pain and anesthesia in distribution of the blocked nerve.

Tips

- An alternative approach is to advance the needle in a mesiad direction until the lamina is contacted. The needle is inserted more medially, 1.5 cm lateral to the cephalad edge of the spinous process and then walked laterally off the edge of the lamina until it slips into the costovertebral ligament and is advanced 1 cm.
- Some workers advocate applying an air-filled loss-of-resistance syringe to the needle after it has been walked off the transverse process or lamina, and advancing the needle while applying pressure to the plunger. Loss of resistance has been described as the needle pops through the costotransverse ligament to enter the thoracic paravertebral space.
- A catheter may be passed into the paravertebral space via an epidural needle, with the bevel medial, by using this technique.

Potential problems

- Pneumothorax.
- While it has been recommended that the needle be angled 20° medially after entering the paravertebral space, care must be taken with the aid of fluoroscopy that the local anesthetic solution is not injected into the nerve sheath causing the solution to track centrally to produce intrathecal blockade.

- Epidural blockade usually occurs with this block, but this is not a problem once low volumes are used. However, even small volumes of epidural spread may confound the diagnostic value of the block.
- Sympathetic blockade may cause hemodynamic changes.
- Neuritis may occur with catheter placement.
- Intravascular injection. Injection of particulate steroids into a radicular artery can cause spinal cord infarction. Particulate steroids should never be injected near the foramen unless intravascular placement has been ruled out using live fluoroscopy contrast dye injection, preferably with digital subtraction technique.

4.5 SACRAL NERVE ROOT BLOCK

Anatomy

Each of the five sacral nerves is accessible by passing a needle into the sacral foramen via the posterior opening at the level of the nerve. The sacral canal is the caudal extension of the epidural space and nerves of the cauda equina leave via the sacral foramina (**Fig. 4.5.1**). The distal dural sac ends at S2, the level of the posterior superior iliac spines. The epidural space ends at the sacral hiatus (**Fig. 4.5.2**). While variability in the bony anatomy of the sacrum is common, this occurs usually in the midline.


Conus medullaris
Dura matter
Spinous process
Termination of the spinal cord at the level of L1
Transverse process
1
L1
2
L2
3
Cauda equina
L3
4
L4
5
Subarachnoid space (CSF)
L5
Termination of the subarachnoid space at S2
Sacral nerves in the caudal epidural space
S1
S2
S3
S4
Filum terminale
S5
Coccygeal nerve

Fig. 4.5.1

Equipment

- 2 ml and 10 ml syringes
- 25 G needle
- 22 G spinal needle, end-opening
- ECG, BP, and SpO_2 monitors
- Resuscitation equipment (*see Appendix 3*) and drugs
- Fluoroscopy or ultrasound

Drugs

- Lidocaine (lignocaine) 1% 10 ml (or its equivalent)
- Corticosteroid if indicated, e.g. triamcinolone diacetate 50 mg (or its equivalent)
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Prone.
- Pillow under anterior superior iliac spine to flatten the normal lumbar lordosis (*Fig. 4.5.3*).

Needle puncture and technique

- Intravenous access is inserted.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- The sacral midline and an area 10 cm × 5 cm laterally is cleaned with antiseptic solution and a fenestrated drape is placed over the sterile area.


Posterior sacral foramen
Sacral hiatus
Cornu of sacrum
First coccygeal vertebra
Coccygeal cornu

Fig. 4.5.2



Fig. 4.5.3



Fig. 4.5.4

- Iliac crests are palpated and an intercrestal line is identified.
- This corresponds with the inferior aspect of the spinous process of L4 or may lie in the L4–5 interspace.
- For this block, it is almost essential that the posterior opening of the sacral foramina is identified with fluoroscopy. The X-ray beam is used to guide the needle tip into the foramen. It is important to note that when the anteroposterior X-ray view is used, it is usually the anterior opening of the foramen that is the most prominent.
- **The insertion point of the needle lies 2–3 cm lateral to the midline (variable) and approximately 1 cm medial to the posterior iliac spine** (*Figs 4.5.4, 4.5.5 a,b*).
- Therefore, with the aid of fluoroscopy, the insertion point is identified.
- A skin wheal is raised and the area is infiltrated with lidocaine (lignocaine) 1%.



Fig. 4.5.5

- A spinal needle is introduced in a vertical direction to the skin, and aimed slightly cephalad until bone is contacted (*Fig. 4.5.6*).
- The needle is then walked off the sacrum in a caudad direction until it slips into the foramen. After confirmation with the aid of fluoroscopy it is then advanced 1 cm.



Fig. 4.5.6

- Paresthesia may be produced.
- After aspiration, non-ionic radio-opaque contrast medium 0.5 ml is injected.
- The correct placement is indicated by a needle tip flush with the anterior surface of the spinal canal in the lateral fluoroscopic view.
- Injection of 0.5 ml non-ionic contrast should spread diagonally along the S1 spinal nerve (*Fig. 4.5.7*).
- After further aspiration, lidocaine (lignocaine) 1% 0.5 ml is injected.
- After 5 minutes, the patient is questioned about changes in pain, sensation and power of the lower limb.
- For diagnostic nerve root blockade the needle may be removed when the level causing pain is identified.
- Ultrasound may also aid placement.

Confirmation of a successful block

- Relief of pain.
- Anesthesia in the distribution of the blocked nerve.



Fig. 4.5.7

Tips

- Some workers advocate drawing a line from a point 2–3 cm medial to the posterior superior iliac spine to a point 1–2 cm lateral to the sacral cornua. The sacral foramina usually lie along this line.
- It is best to angle the X-ray beam caudally, thereby perpendicular to the sacrum, superimposing the anterior and posterior sacral foramina. Consequently, when the needle is introduced in a direction perpendicular (*Fig. 4.5.8*) to the skin, fluoroscopic guidance is easier. Optimally, the needle makes gentle contact with the spinal nerve in the middle of the canal (*Figs 4.5.9*, *4.5.10*) and produces paresthesia in the distribution of the nerve.
- While all sacral nerve roots are accessible, using this technique for blockade of S5 is achieved by walking the needle caudally off the inferior edge of the bony plate of the sacrum and advancing the needle 1 cm.

Potential problems

- Caudal epidural blockade may occur with this block, but this is not a problem once low volumes are used. However, even small volumes of epidural spread may confound the diagnostic value of the block.
- Intravascular injection. Injection of particulate steroids into a radicular artery can cause spinal cord infarction. Particulate steroids should never be injected near the foramen unless intravascular placement has been ruled out using live fluoroscopy contrast dye injection, preferably with digital subtraction technique.



Fig. 4.5.8


S5
S4
S3
S2
S1

Fig. 4.5.9


S5
S4
S3
S2
S1

Fig. 4.5.10

4.6 OCCIPITAL NERVE BLOCK

Anatomy

The greater occipital nerve arises from the dorsal rami of the second cervical nerve. From here it passes through the muscles of the neck and becomes subcutaneous at the superior nuchal line, where it emerges with the occipital artery (**Fig. 4.6.1**). The superior nuchal line extends from the mastoid process to the greater occipital protuberance bilaterally (**Fig. 4.6.2**).

Equipment

- 10 ml syringe
- 25 G needle
- ECG, BP, and SpO_2 monitors
- Resuscitation equipment (*see Appendix 3*)

Drugs

- Lidocaine (lignocaine) 1% 10 ml (or its equivalent)
- Corticosteroid if indicated, e.g. triamcinolone diacetate 50 mg (or its equivalent)
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Sitting.
- Neck flexed.

Needle puncture and technique

- The superior nuchal line is cleaned with antiseptic solution (no drape is required) (*Fig. 4.6.3*).


Greater occipital protuberance
Mastoid process
Greater occipital nerve
Occipital artery
Lesser occipital nerve
Greater auricular nerve posterior branch

Fig. 4.6.1


Greater occipital nerve
Lesser occipital nerve
Superior nuchal line
Mastoid process
Greater occipital protuberance

Fig. 4.6.2



Fig. 4.6.3

- The occipital artery is palpated 2 cm lateral to the greater occipital protuberance on the superior nuchal line (*Fig. 4.6.4*).
- A 25 G needle is inserted subcutaneously at this point.
- After negative aspiration, 3–5 ml of lidocaine (lignocaine) 1% or its equivalent, plus corticosteroid if indicated, is injected to surround the occipital artery.
- It is often difficult to feel an occipital artery pulse. If this is the case, it is best to pick a point midway between the occipital protuberance and the mastoid bone and fan out the injection in both directions, medially and laterally from that site (*Fig. 4.6.5*).

Confirmation of a successful block

- Relief of pain and anesthesia in distribution of nerve.

Tips

- Bone should be contacted at a depth no greater than 1–2 cm.
- The lesser occipital nerve is blocked by redirecting the needle towards the mastoid process along the greater nuchal line and injecting a further 3 ml of solution.

Potential problems

- Injection into the cerebrospinal fluid (CSF) of the cisterna magna is possible and will produce a total spinal block.



Fig. 4.6.4



Fig. 4.6.5

4.7 TRIGEMINAL GANGLION (GASSERIAN) BLOCK

Anatomy

The trigeminal ganglion gives rise to the fifth cranial nerve and divides into three branches, the ophthalmic, maxillary, and mandibular nerves (**Fig. 4.7.1**). These provide the sensory nerve supply to the ipsilateral face and the anterior two-thirds of the head (**Fig. 4.7.2**). The mandibular nerve also provides motor supply to the muscles of mastication.

The trigeminal ganglion is located at the apex of the petrous temporal bone in a fold of dura mater, "Meckel's cave". This dural invagination covers the posterior two-thirds of the ganglion and contains cerebrospinal fluid (CSF). Posterior to Meckel's cave lies the brainstem, superior to it lies the temporal lobe, and medially lies the cavernous sinus which contains the internal carotid artery and cranial nerves III, IV, and VI. Accordingly, extreme care must be taken when carrying out this block, especially if neurolytic agents are used. Blockade of the ganglion is carried out by passage of a needle through the foramen ovale, which lies immediately below it (**Fig. 4.7.3**).


Ophthalmic
Maxillary
Mandibular

Fig. 4.7.1


Ophthalmic
Maxillary
Mandibular
C2
C3
C4
Posterior primary rami
Anterior primary rami

Fig. 4.7.2

Equipment

- 2 ml and 10 ml syringes
- 25 G needle
- 22 G 8–10 cm needle
- Non-ionic radio-opaque contrast medium
- ECG, BP, and SpO_2 monitors
- Resuscitation equipment (*see Appendix 3*)
- Fluoroscopy

Drugs

- Lidocaine (lignocaine) 2% 10 ml
- Lidocaine (lignocaine) 1% 10 ml (or its equivalent)
- Neurolytic agent, e.g. phenol 6% plus glycerol (or its equivalent)
- Sedative, e.g. midazolam, propofol
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Supine.
- Eyes directed straight ahead.


Meckel's cave
Gasserian ganglion
Zygomatic arch
Foramen ovale

Fig. 4.7.3

Needle puncture and technique

Caution: Injection of 0.25 ml of lidocaine (lignocaine) 1% into the CSF may result in immediate convulsion and/or loss of consciousness with possible cardiovascular system (CVS) collapse.

- The cheek on the side of the block is cleaned with antiseptic solution or saline.
- Mild sedation is induced.
- It is best to stand on the side of the block, just below the shoulder.
- **The insertion point lies 1–3 cm posterior to the lateral margin of the mouth, at the medial edge of the masseter muscle (located by asking the patient to clench the jaw) and is marked.**
- **In edentulous patients the insertion point should be more caudad** as sufficient angle towards the infratemporal surface of the sphenoid bone may not be achieved.
- One finger is placed inside the upper lip to avoid injection into the buccal cavity and possible bacterial contamination, and a skin wheal is raised at this site.
- Viewed from above, a 22 G 8–10 cm needle is advanced towards the ipsilateral pupil (*Figs 4.7.4–4.7.6*), or viewed from the side the needle advances towards the mid-point of the zygomatic arch (see Anatomy above) until bone is contacted; the roof of the infratemporal fossa. This lies just anterior to the foramen ovale and lateral to the base of the pterygoid process. The location of the needle tip is confirmed with fluoroscopy.
- A depth mark is set and the needle is withdrawn to the subcutaneous tissue. With the aid of fluoroscopy the needle is reinserted to walk off the bone and enter the foramen ovale (*Fig. 4.7.7*).
- Paresthesia in the distribution of the mandibular nerve (sometimes the other branches of the trigeminal nerve) or contraction of the muscles of mastication may be experienced at this point.
- The needle is advanced a further 1 cm to bring the tip to lie in the trigeminal ganglion. The correct placement is indicated by a visible outline of Meckel's cave on injection of 0.25 ml non-ionic radio-opaque contrast medium under fluoroscopy (*Figs 4.7.8*, *4.7.9*).
- The patient is allowed to awaken from sedation and is questioned about the presence and distribution of paresthesia and pain.
- A stimulating device may aid placement in patients who are not able to locate the paresthesia with accuracy.
- If necessary, analgesia may be administered, although this may affect accurate assessment of the blockade.
- Adjustment of the needle may be required to place the needle near the appropriate nerve division.



Fig. 4.7.4



Fig. 4.7.5



Fig. 4.7.6



Fig. 4.7.8



Fig. 4.7.9


Roof of infratemporal fossa
Zygomatic arch
Foramen ovale
2
1

Fig. 4.7.7

- After careful negative aspiration for CSF or blood, lidocaine (lignocaine) 1% 0.25 ml is injected (***Caution: injection into CSF may cause loss of consciousness***.) This is followed by further boluses of lidocaine (lignocaine) 1% 0.25 ml until a total of 1 ml is given.
- After 5 minutes the patient is questioned about pain relief and changes in sensation.
- When the desired analgesia has been achieved for diagnostic blockade the needle may be removed.

Confirmation of a successful block

- Relief of pain and anesthesia in the distribution of the trigeminal nerve or its desired branches.

Tips

- Intravenous anesthesia using a short-acting agent, e.g. propofol, may be induced to allow placement of the needle. The patient is then allowed to awaken and a stimulating device may aid accurate placement of the needle.
- The needle is advanced beyond the infratemporal bone by 0.5 cm for location of the mandibular division, 1.0 cm for the maxillary division, and 1.5 cm for the ophthalmic division.
- Gangliolysis using thermocoagulation may be employed for trigeminal-nerve division destruction after location of the ganglion using this technique. Further intravenous anesthesia using a short-acting agent, e.g. propofol, may be induced after placement of the insulated needle to facilitate this painful procedure.
- Injection of glycerol alone may produce pain relief with this injection technique. This involves placement of the needle in the cul-de-sac of CSF, positioning the patient face-down or supine, with the head extended to prevent spill-over into the posterior cranial fossa. After entry into the CSF, and positive aspiration of CSF, 0.1–0.3 ml of glycerol may be injected.

Potential problems

- Injection of 0.25 ml of lidocaine (lignocaine) 1% into the CSF may result in immediate convulsion and/or loss of consciousness with possible CVS collapse.
- Spread of hyperbaric neurolytic solution may immediately affect cranial nerves VI, VIII, IX, X, XI, and XII.
- Spread of hypobaric neurolytic solution may immediately affect the oculomotor and trochlear nerves.
- Neurolytic blocks of the trigeminal ganglion commonly produce corneal and hemifacial anesthesia.

AUTONOMIC BLOCKADE

5

Autonomic blockade is useful in the diagnosis and treatment of pain of autonomic origin. In cases of thoracic, abdominal or pelvic pain, it is often difficult to distinguish between that of visceral origin and that of somatic. Pain of visceral origin, e.g. pancreatic cancer or pelvic cancer, may cause pain that responds to celiac or hypogastric plexus blockade, respectively. A prognostic block may be carried out prior to neurolytic blockade for relief of cancer pain. Pain of the upper abdominal viscera may also be relieved by celiac plexus block, proceeding to neurolytic blockade as appropriate for cancer-related pain. The retrocrural approach to the celiac plexus also targets the splanchnic nerves to produce a splanchnic nerve block if required. Chest pain may be of somatic origin, e.g. intercostal neuralgia and costochondritis, or visceral origin, e.g. pulmonary or cardiac-related pain. Stellate ganglion blockade may be helpful in the diagnosis and management of the latter.

In addition, increased sympathetic activity is thought to contribute to a large number of pain states. These are generally grouped under the term Complex Regional Pain Syndrome Type I and II. In these cases, trophic changes and alterations in blood flow are often obvious but the pathophysiologic origin is not. Blockade of sympathetic innervation may therefore help in diagnosis and management of such pain. This may also indicate other therapies that could be beneficial, e.g. sympathetically active drugs or destructive therapies. Similarly, these therapies would not be indicated if sympathetic blockade failed to relieve the pain. If blockade did succeed in relieving this type of pain, further blocks may effect lasting relief.

There are a number of other conditions in which the diagnosis is clear but there is a possible contribution of sympathetic activity in the pathogenesis of the pain. These conditions include central pain, post-herpetic neuralgia, trigeminal neuralgia, peripheral vascular disease and others. Blockade of sympathetic activity may help to clarify the sympathetic contribution to the pain and therefore help to indicate management options.

5.1 STELLATE GANGLION BLOCK—C6 (CLASSIC) APPROACH

Anatomy

The cervical sympathetic trunk—the superior, middle, and stellate ganglia—supplies the sympathetic innervation of the head, neck, and upper limbs. The stellate ganglion is made up of a combination of the lower cervical and first thoracic ganglia. It lies on the prevertebral fascia of the seventh cervical and first thoracic vertebrae (**Fig. 5.1.1**). However, as the sixth cervical anterior tubercle (Chassaignac's tubercle) is easy to palpate, injection of a large volume of local anesthetic is made at this level and allowed to track caudally along the prevertebral fascia to block the stellate ganglion. The vertebral and carotid arteries, the pleura, and the brachial plexus are in close proximity to the stellate ganglion.

Equipment

- 10 ml syringe
- 22 G short-bevel needle
- Extension set (optional)
- ECG, BP, SpO_2 monitors
- Skin temperature monitor
- Resuscitation equipment (*see Appendix 3*)
- Ultrasound (optional)

Drugs

- Lidocaine (lignocaine) 1%, 10 ml
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Supine.
- Thin pillow under head.
- Roll under neck.
- Eyes directed at ceiling.
- Mouth slightly open.

Needle puncture and technique

Caution: Injection of 0.5–1 ml of lidocaine (lignocaine) 1% into the vertebral artery may result in immediate convulsion and/or loss of consciousness with possible cardiovascular system (CVS) collapse.

- Intravenous access is inserted.
- Monitors are attached, each temperature probe is attached to the palmar aspect of the middle finger of each hand (*Fig. 5.1.2*).
- Resuscitation equipment and drugs are checked and made ready for use.
- The side of the neck is cleaned with antiseptic solution.
- It is best to stand at the same side of the neck as the ganglion to be blocked.

FOR THE RIGHT-HANDED OPERATOR

With the left hand

- The thyroid cartilage is located and marked.
- The cricoid cartilage is identified and marked (*Figs 5.1.3, 5.1.4*).



Fig. 5.1.1



Fig. 5.1.2



Fig. 5.1.3



Fig. 5.1.6



Fig. 5.1.4



Fig. 5.1.7



Fig. 5.1.5

- Chassaignac's tubercle is palpated with the middle finger, just lateral to the cricoid cartilage (*Fig. 5.1.5*).
- The sternocleidomastoid (SCM) muscle is gently pulled laterally and the carotid pulse is palpated (*Fig. 5.1.6*).
- Chassaignac's tubercle is palpated again and positioned between the fore- and middle fingers.

With the right hand

- The needle is inserted between the fore- and middle fingers of the other hand, directly perpendicular to the floor, aiming for Chassaignac's tubercle (*Figs 5.1.7, 5.1.8*).
- When contact with the tubercle is reached, the injecting hand is steadied and the needle is withdrawn 2 mm.
- The hub of the needle is held in place with the other hand.



Fig. 5.1.8



Fig. 5.1.9

- After negative aspiration, lidocaine (lignocaine) 1%, 0.5 ml, is injected.
- The patient is questioned about sensation and any change in level of consciousness is noted.
- If negative, the same procedure is repeated as 0.5 ml boluses are given until 10 ml is injected.
- The needle is withdrawn and the patient is immediately put in the sitting position.
- Monitors should be left attached and i.v. access left in situ for at least 30 minutes. The patient is requested not to eat or drink for 2 hours, as the recurrent laryngeal nerve may be blocked.
- Note: if aspiration of blood occurs during the block the needle is removed and cleared, keeping left fore- and middle fingers in place. It is then reinserted and the block is continued as above.
- If hematoma occurs before the solution is injected it may be worth performing the block at the C7 level.
- If there is pain on injection and/or paresthesia, it is likely that the brachial plexus may have been contacted, the needle is withdrawn and the landmarks are rechecked.

Confirmation of a successful block

- Skin temperature, measured over the palmar aspect of the hand or fingers on the blocked side, should begin to rise within 2–3 minutes. Extensive sympathetic blockade is confirmed by a rise in skin temperature to >33 °C.
- Ptosis of eyelid.
- Miosis of pupil.
- Unilateral blockage of nose on side of block.
- Unilateral flushing of conjunctiva of eye on side of block.
- Blockade of the upper sympathetic chain can occur in the absence of sympathetic denervation of the upper extremity, resulting in Horner's syndrome without a rise in skin temperature in the hand.

Tips

- The external jugular vein usually crosses the SCM muscle at the level of C6.
- Skin infiltration prior to block should be avoided if possible, as this will make landmarks more difficult to locate.
- If palpation is painful or difficult it may be helpful to try to bounce the middle finger off the tubercle during identification.
- An extension set may be inserted between the needle and syringe for better stability of needle (*Fig. 5.1.9*), but an assistant is then required to continue the procedure as described above.
- Consideration should be given to performance of the block under fluoroscopy or CT control if the landmarks are difficult to locate.
- Lidocaine (lignocaine) 1% 15 ml may be given if a previous block failed to relieve sympathetically maintained pain in the presence of correctly placed solution. This may improve tracking of the solution caudally to produce more effective blockade of the stellate ganglion.
- Ultrasound may aid placement of needle (*Fig. 5.1.10 a,b*).

Potential problems

- Intra-arterial injection or intrathecal injection may result in immediate convulsion and/or loss of consciousness with possible CVS collapse.



Fig. 5.1.10 From Gupta Prashant K, Gupta Kumkum, Dwivedi Amit Nandan D, Jain Manish. Potential role of ultrasound in anesthesia and intensive care, Anesthesia Essays and Research, 2011 Volume 5, Issue Number 1, Page: 11-19.

- Hematoma may occur (avoid performing block on patients who have coagulopathy).
- Pneumothorax may occur.
- Recurrent laryngeal nerve block may occur and it is prudent to advise the patient about possible hoarseness post-blockade. Bilateral stellate ganglion blockade should be avoided for the same reason.
- Phrenic nerve block may occur and it is prudent to caution the patient about possible shortness of breath post blockade of the stellate ganglion.

5.2 STELLATE GANGLION BLOCK—C7 APPROACH

Anatomy

As for stellate ganglion block (C6 approach) in Section 5.1 (**Figs 5.2.1 a,b**).

Equipment

- 10 ml syringe
- 22 G short-bevel needle
- Extension set (optional)
- ECG, BP, SpO_2 monitors
- Skin temperature monitor
- Fluoroscopy or CT (optional)
- Resuscitation equipment (*see Appendix 3*)
- Ultrasound (optional)

Drugs

- Lidocaine (lignocaine) 1%, 10 ml
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Supine.
- Thin pillow under head.
- Roll under neck.
- Eyes directed at ceiling.
- Mouth slightly open.

Needle puncture and technique

Caution: injection of 0.5–1 ml of lidocaine (lignocaine) 1% into the vertebral artery may result in immediate convulsion and/or loss of consciousness with possible cardiovascular (CVS) collapse. The risk of pneumothorax is greater with this approach.

- Intravenous access is inserted.
- Monitors are attached.
- Each temperature probe is attached to the palmar aspect of the middle finger of each hand. (*Fig. 5.2.2*).
- Resuscitation equipment and drugs are checked and made ready for use.
- The side of the neck is cleaned with antiseptic solution.


C5
Middle cervical ganglion
C6
Stellate ganglion
Vertebral artery
T1
Common carotid artery
A
Right subclavian artery
Lung
Longus colli
Superior stellate ganglion
C2
C3
C4
C5
C6
C7
T1
Anterior scalenus
Middle ganglion
Medius scalenus
Stellate ganglion
Subclavian artery
Dome of pleura
1st rib
B
Carotid artery

Fig. 5.2.1


Temperature probe

Fig. 5.2.2

- It is best to stand at the same side of the neck as the ganglion to be blocked.

FOR THE RIGHT-HANDED OPERATOR

With the left hand

- The thyroid cartilage is located and marked.
- The cricoid cartilage is identified and marked (*Figs 5.2.3, 5.2.4*).
- The sternoclavicular junction is palpated and marked (*Fig. 5.2.5*).
- The SCM muscle is gently pulled laterally and the carotid pulse is palpated (*Fig. 5.2.6*).
- **The site of insertion of the needle lies 3 cm above the sternoclavicular junction or one to two finger-breadths below the level of the cricoid cartilage.**

With the right hand

- The patient is requested to exhale deeply before needle insertion to minimize the risk of pneumothorax.
- The needle is inserted between the fore- and middle fingers of the other hand, directly perpendicular to the floor.
- When contact with the transverse process of C7 is reached, the injecting hand is steadied and the needle is withdrawn 2 mm.
- The hub of the needle is held in place with the other hand.
- After negative aspiration, lidocaine (lignocaine) 1%, 0.5 ml, is injected.
- The patient is questioned about sensation, and any change in level of consciousness is noted.
- If negative, the same procedure is repeated and 0.5 ml boluses are given until 5–8 ml is injected.
- The needle is withdrawn and the patient is immediately put in the sitting position.



Fig. 5.2.3



Fig. 5.2.4



Fig. 5.2.5



Fig. 5.2.6

- Monitors should be left attached and i.v. access left in situ for at least 30 minutes. Blockade of the recurrent laryngeal nerve is less likely with the C7 approach but it is wise to advise the patient not to eat or drink for 2 hours.
- Note: if aspiration of blood occurs during the block, the needle is removed and cleared, keeping the left fore- and middle fingers in place. It is then reinserted and the block is continued as above.
- If there is pain on injection and/or paresthesia, it is likely that the brachial plexus may have been contacted, the needle is withdrawn and the landmarks are rechecked.
- Ultrasound may aid placement of the needle.

Confirmation of a successful block

- Temperature increase >1° on the side of block. The temperature should begin to rise in the finger of the blocked side within 3 minutes of injection.
- Ptosis of eyelid.
- Miosis of pupil.
- Unilateral blockage of nose on side of block.
- Unilateral flushing of conjunctiva of eye on side of block.
- Relief of sympathetically maintained pain.

Tips

- Some workers advocate targeting the **ventrolateral aspect of the C7 vertebral body instead of its transverse process.** The needle is directed 15–20° medially. With the aid of fluoroscopy, ultrasound or CT, the vertebral body is contacted just medial to the insertion of the longus colli muscle. The needle is then withdrawn 2 mm, stabilized, and 1 ml of non-ionic contrast medium is injected.
- The external jugular vein usually crosses the SCM muscle at the level of C6.
- Skin infiltration prior to block should be avoided if possible, as this will make landmarks more difficult to locate.
- An extension set may be inserted between the needle and syringe for better stability of needle, but an assistant is then required to continue the procedure as described above.
- Lidocaine (lignocaine) 1% 10 ml may be given if a previous block failed to relieve sympathetically maintained pain in the presence of correctly placed solution. This may improve tracking of the solution caudally to produce more effective blockade of the stellate ganglion.

Potential problems

- Intra-arterial injection or intrathecal injection may result in immediate convulsion and/or loss of consciousness with possible CVS collapse.
- Hematoma may occur (avoid performing block on patients who have coagulopathy).
- Pneumothorax may occur (more likely with C7 approach).
- Recurrent laryngeal nerve block may occur and it is prudent to advise the patient about possible hoarseness post blockade. Bilateral stellate ganglion blockade should be avoided for the same reason.
- Phrenic nerve block may occur and it is prudent to caution the patient about possible shortness of breath following blockade of the stellate ganglion.

5.3 LUMBAR SYMPATHETIC BLOCK

Anatomy

The lumbar sympathetic chain is located in the prevertebral fascia, which lies on the anterolateral aspects of the vertebral bodies. The psoas muscle separates the lumbar sympathetic chain from the lumbar somatic nerves. A single injection of local anesthetic at the level of L2 will usually provide a complete block of postganglionic sympathetic efferents to the lower extremity because the lowest preganglionic sympathetic outflow to the chain is at the level of L2.

Equipment

- 2 ml, 5 ml, and 10 ml syringes
- 30 G needle
- Two 15 cm 22 G needles
- Extension set (optional)
- ECG, BP, SpO_2 monitors
- Skin temperature monitor (two probes)
- Resuscitation equipment (*see Appendix 3*)
- Fluoroscopy

Drugs

- Lidocaine (lignocaine) 1%, 5 ml for skin infiltration
- Lidocaine (lignocaine) 1%, 15–20 ml (or its equivalent) for block
- Phenol 6%
- Radio-opaque contrast medium
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Prone.
- Pillow under anterior superior iliac spine to flatten the normal lumbar lordosis (*Fig. 5.3.1*).

Needle puncture and technique

- Intravenous access is inserted.
- Monitors are attached.
- Each temperature probe is attached to the plantar aspect of the big toe (*Fig. 5.3.2*).
- Resuscitation equipment and drugs are checked and made ready for use.
- The thoracolumbar midline and an area 10 cm × 5 cm laterally is cleaned with antiseptic solution and a fenestrated drape is placed over the sterile area.
- The twelfth rib is identified and a line is drawn along its inferior border (*Fig. 5.3.3 a,b*).
- The iliac crests are palpated and the intercrestal line is identified (this corresponds with the inferior aspect of the spinous process of L4 or may lie in the L4–5 interspace).
- The spinous processes are counted until L2 is identified and confirmed with fluoroscopy.
- **The insertion point lies 8 cm lateral to the L2 spinous process and is also marked (*Fig. 5.3.4*).**
- A skin wheal is raised at one of the marked sites and the area is infiltrated with lidocaine (lignocaine) 1%.
- At a 30° angle to the frontal plane, a 22 G 15 cm needle is advanced slightly cephalad towards the lower



Fig. 5.3.1



Fig. 5.3.2

portion of the L2 vertebral body (*Fig. 5.3.5*), until its vertebral body is contacted at a depth of about 7–9 cm and confirmed with fluoroscopy. If the needle contacts bone at a more superficial level, it is probable that it has come into contact with the transverse process and it will need to be repositioned.

- The needle depth is noted.
- The needle is then withdrawn to the subcutaneous tissue and, with the aid of fluoroscopy, it is re-advanced, this time at an angle 45° to the frontal plane, until the previous depth (as noted) is reached. It should slip past the vertebral body at a depth about 1–2 cm deeper than the first depth mark (*Fig. 5.3.6*).
- After negative aspiration, the fluoroscopic image is observed as a small amount of non-ionic radio-contrast medium is injected. The correct placement of the needle is indicated by the presence of a layer of contrast medium in a thin line along the anterior border of the vertebral column (*Figs 5.3.7–5.3.9*).
- After further negative aspirations, 5 ml of lidocaine (lignocaine) 1% is injected. The patient is questioned about pain relief and observations of skin temperature are made. There should be little resistance to injection, similar to resistance felt when injecting through an epidural needle. If resistance is encountered, or if the injection is painful, the needle should be repositioned. A unilateral rise in skin temperature indicates a successful block.
- After 10 minutes the patient is questioned about pain relief and any symptoms of somatic nerve blockade. Sensory and motor functioning of the lower extremities is checked. The procedure should be abandoned if there is evidence of somatic blockade.



Fig. 5.3.3



Fig. 5.3.4



Fig. 5.3.5



Fig. 5.3.6

- Neurolysis may be achieved by leaving the needle in place after block has been confirmed and injecting 5 ml phenol 6%. To avoid leaving alcohol in the needle tract, the needle is then cleared with air or local anesthetic 1 ml, and removed. However, because of the very high incidence of genitofemoral neuralgia that can occur post-neurolytic lumbar sympathetic block, the benefit versus risk should be considered carefully.
- Monitors should be left attached and i.v. access left in situ for at least 30 minutes.

Confirmation of a successful block

- Increase in skin temperature on the plantar surface of the foot to about 35 °C; temperature should begin to rise in the foot on the side of the block within 3 minutes of injection of local anesthetic.
- Relief of sympathetically maintained pain in the lower limb.

Tips

- If fluoroscopy is not available ultrasound may aid placement of the needle. A line 10 cm from the midline is drawn parallel to the midline; the lowest rib is identified and a line is drawn along its inferior border.
- The point of intersection of these lines should be lateral to the L2 vertebral body.
- Consideration should be given to performance of the block under CT control if the block is unsuccessful.
- Repeated blocks may bring about gradual improvement in sympathetically maintained pain.
- Immediate physiotherapy after blockade may improve the outcome.



Fig. 5.3.7



Fig. 5.3.8



Fig. 5.3.9

Potential problems

- If the needle tip is placed too superficially, the tip may come to lie in the intervertebral foramen and injection may result in a subarachnoid block, an epidural block, or a somatic nerve block. Confirmation of needle position using lateral fluoroscopy is therefore recommended.
- Genitofemoral neuralgia may occur in 5–10% of patients post-neurolytic block causing pain in the groin.
- Perforation of the aorta or the inferior vena cava is possible and retroperitoneal hematoma may occur. Consequently the block should be avoided in patients with coagulopathy.
- Intravascular injection may occur.
- Perforation of the kidney or ureter is usually of no clinical significance unless neurolytic agents are used.
- Perforation of the intervertebral disc may occur. This also is usually of no clinical significance but may produce a septic discitis if bacterial contamination occurs.
- Postural hypotension, secondary to sympathetic blockade, may occur.
- Injection of neurolytic solution into the psoas muscle may cause rhabdomyolysis.
- Patients in the prone position should be monitored carefully when intravenous sedation is administered.

5.4 CELIAC PLEXUS BLOCK—RETROCRURAL APPROACH

Anatomy

The celiac plexus is flat and lies against the crus of the diaphragm, surrounding the root of the celiac and mesenteric arteries and anterior to three vertebral bodies centered at L1. Posteriorly on the left side is the aorta, and on the right is the inferior vena cava. The kidneys lie lateral and the pancreas anterior to the celiac plexus (**Fig. 5.4.1 a,b**).

The celiac plexus is made up of pre- and postganglionic sympathetic and parasympathetic nerve fibers. Postganglionic sympathetic fibers are supplied from the paired celiac ganglia. Preganglionic sympathetic efferents from the thoracic sympathetic chain are supplied via the greater and lesser splanchnic nerves. The intra-abdominal viscera are supplied by postganglionic sympathetic fibers that have synapsed in the celiac ganglia (**Fig. 5.4.2**). The vagus nerve also supplies parasympathetic nerve fibers. Via the celiac plexus dorsal root, ganglion cells innervate the whole of the abdominal viscera, including the liver, spleen, kidneys, suprarenal glands, and intestines, with the exception of the pelvic organs, the rectum, and the left half of the colon.

Pain originating from the viscera is often vague and poorly localized as a result of convergence of neurons in the dorsal horn and crossing over the midline of some of the visceral afferents.

There are two main approaches to celiac plexus blockade. One approach places the two needles posterior to the crura of the diaphragm, the retrocrural approach. The retrocrural approach to the celiac plexus also targets the splanchnic nerves to produce a splanchnic nerve block if required. The other approach places a needle anterior to the crus of the diaphragm on the right, the anterocrural approach (**Fig. 5.4.3**), as discussed in Section 5.5.


Celiac artery
Celiac plexus
Liver
Aorta
Inferior vena cava
Splanchnic nerve
Kidney
Kidney
A
L1
Diaphragmatic crus
Aorta
Diaphragm
Retrocrural spread
Celiac plexus
Anterocrural spread
Splanchnic nerves
Diaphragmatic crus
B

Fig. 5.4.1


Sympathetic chain
Dorsal root
Thoracic spinal cord
Somatic nerve
Grey ramus
Ventral root
White ramus
Vagus nerve
Splanchnic nerve
Celiac ganglion
Viscus
Superior mesenteric ganglion
B

Fig. 5.4.2

Equipment

- 2 ml, 5 ml, and 10 ml syringes
- 30 G needle
- Two 15 cm 22 G needles
- Extension set (optional)
- ECG, BP, SpO_2 monitors
- Resuscitation equipment (*see Appendix 3*)
- Fluoroscopy

Drugs

- Mild sedative
- Lidocaine (lignocaine) 1%, 5 ml for skin infiltration
- Lidocaine (lignocaine) 1%, 15–20 ml (or its equivalent) for block
- 6% aqueous phenol or 50–75% alcohol (ethanol). Our suggestion: mix 2 parts absolute alcohol with one part 1% lidocaine. This will help reduce the incidence and severity of pain following injection. In addition, precede all alcohol injections with 3–4 ml 1% lidocaine
- Non-ionic radio-opaque contrast medium
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Prone.
- Pillow under anterior superior iliac spine to flatten the normal lumbar lordosis (*Fig. 5.4.4*).

Needle puncture and technique

- Intravenous access is inserted.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- Mild sedation may be induced.

RETROCRURAL APPROACH

- A 15 cm 22 G spinal needle is selected. A slight curve at the needle tip, away from the bevel direction, may be created, which allows the needle to be redirected during placement.
- An AP view of the upper lumbar/low thoracic spine is obtained and the C-arm is adjusted to superimpose the T12–L1 endplates.
- **A skin wheal is raised at the lower border of the twelfth rib on the right just above the level of the L1 transverse process** (*Fig. 5.4.5 a*). The needle is inserted at this site and advanced at an angle 30° from perpendicular inward until the L1 body is contacted just below the upper endplate (*Fig. 5.4.5*). The curve of the needle is turned laterally and the needle is advanced along the upper portion of the body. Once the needle has slipped a few millimeters past the lateral aspect of the L1 body, a lateral view is obtained. The curve of the needle is directed inward toward the body and advanced until the tip lies at the anterior border of the body, near the upper endplate, in a direct lateral view.
- Using “live” fluoroscopy, 1 ml non-ionic contrast medium is injected. The dye should remain against the anterior aspect of the bodies in the lateral view (*Fig. 5.4.6 a*).
- If dye is seen spreading dorsally toward the neural foramina (*see Fig. 5.4.6 b*), the needle should be withdrawn and repositioned at a higher level.
- An AP view is obtained, which should demonstrate dye spread against the lateral aspect of the bodies (*Fig. 5.4.6 c*).
- Spread more laterally indicates injection within the psoas muscle, in which case the needle should be repositioned more medially and anteriorly. 3 ml 1% lidocaine is then injected. The dye shadow will



Fig. 5.4.3



Fig. 5.4.4


L3
L2
L1
A
R
L
12th Rib
L1
12th Rib
Kidney
Aortic
artery
Kidney
Liver
Pancreas
Inferior
vena cava
B
C

Fig. 5.4.5



Fig. 5.4.6



Fig. 5.4.6, cont'd

be seen to expand superiorly, spreading to the thoracic levels to contact the splanchnic nerves (*see Fig. 5.4.6 d*).

- After confirming negative aspiration for blood, 15–20 ml alcohol or phenol is injected. The needle is cleared with 1 ml lidocaine prior to removal.
- Alternatively, the needle can be advanced more cephalad to a position at the anterior border of T12 preferably near either the lower or upper endplate (*Fig. 5.4.6 e*).
- Injection near the mid-point of the body is more likely to result in dorsal spread of the drug toward the neural foramen. More cephalad placement is a bit more difficult technically, but places the needle closer to the splanchnic nerves.
- The procedure is repeated in an identical manner on the left side.

Confirmation of a successful block

- Relief of upper abdominal pain.

Tips

- After injection of non-ionic radio-contrast medium, a blush will indicate injection into muscle. If visible contrast medium disappears immediately it is likely that intravascular injection has occurred.
- Consideration should be given to performance of the block under CT control if the block is unsuccessful.
- Placement of the needle anterior to the diaphragmatic crus can also be achieved via insertion through the abdominal wall.

Potential problems

- The position of each needle tip should always be confirmed with fluoroscopy before injection of neurolytic agent as it may lie in the peritoneal cavity, within a viscus or intravascularly. If a needle tip is placed too superficially, the tip may come to lie in the intervertebral foramen and injection may result in an epidural block or a somatic nerve block. Injection of neurolytic solution into the psoas muscle may cause rhabdomyolysis.
- Perforation of the aorta or the inferior vena cava is possible and consequently the block should be avoided in patients with coagulopathy. Dissection of the aorta may occur as a result of direct damage during the block. Retroperitoneal hematoma may occur and for this reason also the block should be avoided in patients with coagulopathy.
- Orthostatic hypotension may occur as a result of sympathetic blockade for up to 3 days after a neurolytic block. Diarrhea may occur also and hydration of the patient should be monitored.
- Pneumothorax may occur.
- Transient motor paralysis and paraplegia may occur after the block, probably as a result of spasm of the segmental arteries.
- Perforation of the intervertebral disc may occur, but this also is usually of no clinical significance.
- Perforation of the kidney or ureter is usually of no clinical significance unless neurolytic agent is injected.
- The thoracic duct may be damaged (possibly causing chylothorax, or lymphedema).
- Abdominal and chest discomfort may be experienced for 30 minutes after injection of alcohol.
- There may be a detectable odor from the breath after alcohol injection.
- Patients in the prone position should be monitored carefully when intravenous sedation is administered.

5.5 CELIAC PLEXUS BLOCK—ANTEROCRURAL APPROACH

Anatomy

The anterocrural approach places a needle anterior to each crus of the diaphragm. The needles are inserted more medially and directed at a larger angle towards the midline until they come to lie in the retroperitoneal compartment between the aorta, and the inferior vena cava dorsally, and the pancreas ventrally (**Fig. 5.5.1**). Fluoroscopic imaging is necessary for accurate placement of the anterocrural needles using this approach.

Equipment

- 2 ml, 5 ml, and 10 ml syringes
- 30 G needle
- 15 cm 22 G needle (penetration of the diaphragmatic crus is easier with a large gauge needle)
- Extension set (optional)
- ECG, BP, SpO_2 monitors
- Resuscitation equipment (*see Appendix 3*)
- Fluoroscopy

Drugs

- Mild sedative
- Lidocaine (lignocaine) 1%, 5 ml for skin infiltration
- Lidocaine (lignocaine) 1%, 15–20 ml (or its equivalent) for block
- 6% aqueous phenol or 50–75% alcohol (ethanol). Our suggestion: mix 2 parts absolute alcohol with one part 1% lidocaine. This will help reduce the incidence and severity of pain following injection. In addition, precede all alcohol injections with 3–4 ml 1% lidocaine
- Non-ionic radio-opaque contrast medium
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Prone.
- Pillow under anterior superior iliac spine to flatten the normal lumbar lordosis (*Fig. 5.5.2*).

Needle puncture and technique

- Intravenous access is inserted.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- Mild sedation may be induced.



Fig. 5.5.1



Fig. 5.5.2

- The thoracolumbar midline and area 10 cm × 5 cm laterally is cleaned with antiseptic solution and a fenestrated drape is placed over the sterile area.
- The twelfth rib and L1 are identified and confirmed with fluoroscopy.

ANTEROCRURAL APPROACH

Right side

- A 15 cm 22 G spinal needle is selected. A slight curve at the needle tip, away from the bevel direction, may be created which allows the needle to be redirected during placement.
- An AP view of the upper lumbar/low thoracic spine is obtained and the C-arm is adjusted to superimpose the T12–L1 endplates.
- **A skin wheal is raised at the lower border of the twelfth rib on the right just above the level of the L1 transverse process. The needle is inserted at this site and advanced at an angle 30° from perpendicular inward until the L1 body is contacted just below the upper endplate.**
- The curve of the needle is turned laterally and the needle is advanced along the upper portion of the body.
- Once the needle has slipped a few millimeters past the lateral aspect of the L1 body, a lateral view is obtained.
- The needle is advanced until the tip is 1.5–2 cm anterior to the anterior border of the L1 body. The needle is aspirated and if negative, 1 ml non-ionic contrast is injected. Dye spread should be in an amorphous pattern (*Fig. 5.5.3*).
- If aspiration is negative, 3 ml 1% lidocaine (lignocaine) is injected. If no nerve block is noted after 10 minutes, this is followed by 15–20 ml alcohol. If phenol is used, the lidocaine is not needed.
- 1 ml 1% lidocaine is injected before removing the needle to clear it.

Left side

- **The same procedure is repeated on the left.**
- The needle is positioned 1.5–2 cm anterior to the anterior border of the L1 body. It is then usually within the aorta, and aspiration is positive for arterial blood.
- The needle is advanced forward until aspiration is negative for blood (*Fig. 5.5.3 b*).
- 1 ml contrast is injected. The pattern is generally amorphous anteriorly, but a straight border of dye along the anterior surface of the aorta may be seen (*Fig. 5.4.4*).
- Aspiration is repeated and, if negative, 3 ml 1% lidocaine (lignocaine) is injected. If no nerve block is noted after 10 minutes, this is followed by 15–20 ml alcohol. If phenol is used, the lidocaine is not needed.
- 1 ml 1% lidocaine is injected before removing the needle to clear it.
- Monitors should be left attached and i.v. access left in situ for at least 30 minutes.

Confirmation of a successful block

- Relief of upper abdominal pain.

Tips

- After injection of non-ionic radio-contrast medium, a blush will indicate injection into muscle. If visible contrast medium disappears immediately it is likely that intravascular injection has occurred.
- Consideration should be given to performance of the block under CT control if the block is unsuccessful.


R
L
L3
L2
L1
A
L1
12th Rib
12th Rib
Kidney
Aortic artery
Kidney
Liver
Pancreas
Inferior vena cava
B
Greater splanchnic nerve
Paravertebral sympathetic trunk
Lesser splanchnic nerve
T10
T11
T12
L1
L2
Thoracic duct
Azygos vein
Diaphragm
Celiac plexus
Celiac axis
Superior mesenteric artery
Aorta
Classic celiac block
Prevascular celiac block
C

Fig. 5.5.3

Potential problems

- The position of each needle tip should always be confirmed with fluoroscopy prior to injection of neurolytic agent as it may lie in the peritoneal cavity, within a viscus or intravascularly. If a needle tip is placed too superficially, the tip may come to lie in the intervertebral foramen and injection may result in epidural block or a somatic nerve block. Injection of neurolytic solution into the psoas muscle may cause rhabdomyolysis.
- Perforation of the aorta or the inferior vena cava is possible and consequently the block should be avoided in patients with coagulopathy. Dissection of the aorta may occur as a result of direct damage during the block. Retroperitoneal hematoma may occur and for this reason also the block should be avoided in patients with coagulopathy.
- Orthostatic hypotension may occur as a result of sympathetic blockade for up to three days after a neurolytic block. Diarrhea may occur also and hydration of the patient should be monitored.

- Pneumothorax may occur.
- Transient motor paralysis and paraplegia may occur after the block, probably as a result of spasm of segmental arteries.
- Perforation of the intervertebral disc may occur, but this also is usually of no clinical significance.
- Perforation of the kidney or ureter is usually of no clinical significance unless neurolytic agents are injected.
- The thoracic duct may be damaged (possibly causing chylothorax, or lymphedema).
- Abdominal and chest discomfort may be experienced for 30 minutes after injection of alcohol.
- There may be a detectable odor from the breath after alcohol injection.
- Patients in the prone position should be monitored carefully when intravenous sedation is administered.

5.6 HYPOGASTRIC PLEXUS BLOCK

Anatomy

The superior hypogastric plexus is formed from pelvic sympathetic fibers of the aortic plexus and L2 and L3 splanchnic nerves. These afferent and efferent fibers innervate the pelvic viscera, including the uterus, bladder, vagina, and prostate. The plexus is located between the upper third of the first sacral vertebral body and the lower third of the fifth lumbar vertebral body, at the sacral promontory, in the retroperitoneal space (**Fig. 5.6.1 a,b**). Parasympathetic nerve fibers from S2–S4 pass through the inferior hypogastric plexus.

Equipment

- 2 ml, 5 ml, and 10 ml syringes
- 30 G needle
- Two 15 cm 22 G needles
- Extension set (optional)
- ECG, BP, and SpO_2 monitors
- Resuscitation equipment (*see Appendix 3*)
- Fluoroscopy


A
Inferior vena cava
Aorta
Superior hypogastric plexus
Superior rectal artery
Internal iliac artery and vein
External iliac artery and vein
Psoas major muscle
B

Fig. 5.6.1

Drugs

- Lidocaine (lignocaine) 1%, 5 ml for skin infiltration
- Lidocaine (lignocaine) 1%, 15–20 ml (or its equivalent) for block
- Phenol 6%
- Non-ionic radio-opaque contrast medium
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Prone.
- Pillow under anterior superior iliac spine to flatten the normal lumbar lordosis (*Fig. 5.6.2*).

Needle puncture and technique

- Intravenous access is inserted.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- The lumbosacral midline and area 10 cm × 5 cm laterally is cleaned with antiseptic solution and a fenestrated drape is placed over the sterile area.
- The iliac crests are palpated and the intercrestal line is identified (this corresponds with the inferior aspect of the spinous process of L4 or may lie in the L4–5 interspace).
- The spinous processes are counted until the L5–S1 interspace is identified and confirmed with fluoroscopy.
- **The insertion points lie 2 cm lateral and 2 cm cephalad to the space between the L5 transverse process and the sacrum** (*Fig. 5.6.3 a,b*).
- A skin wheal is raised at one of the marked sites and the area is infiltrated with lidocaine (lignocaine) 1%.
- At a 30° angle to the frontal plane, a 22 G 15 cm needle is advanced, aimed slightly caudad towards the L5–S1 interspace (*Fig. 5.6.3 c*), until the lower part of the L5 vertebral body is contacted at a depth of about 7–9 cm and confirmed with fluoroscopy. If the needle contacts bone at a more superficial level, it is probable that it has come into contact with the L5 transverse process or the sacrum and needs to be repositioned.
- The needle depth is noted.
- The needle is then withdrawn to the subcutaneous tissue and, with the aid of fluoroscopy, it is re-advanced, this time at an angle 45° to the frontal plane (or with slight concavity of the needle) until the previous depth (as noted) is reached. It should slip past the vertebral body at a depth about 1–2 cm deeper than the first depth mark, to lie just anterior to the upper portion of the sacrum (*Fig. 5.6.4*).
- After negative aspiration, the fluoroscopic image is observed as a small amount of non-ionic radio-contrast medium is injected (*Fig. 5.6.5*). The correct placement of the needle is indicated by the presence of a collection of contrast medium just anterior to the upper portion of the sacrum or the L5–S1 interspace (*Fig. 5.6.6*). The contrast medium usually spreads in all directions, not usually along the sacrum.
- The procedure is repeated on the other side in a mirrored fashion (*Figs 5.6.7, 5.6.8*).
- After further negative aspirations, 5 ml of lidocaine (lignocaine) 1% is injected bilaterally and the patient is questioned about pain relief. There should be little resistance to injection, similar to that felt when injecting through an epidural needle. If resistance is encountered, or if the injection is painful, the needle should be repositioned.
- After 10 minutes the patient is questioned about pain relief and any symptoms of somatic nerve blockade. Sensory and motor functioning of the lower extremities is checked. The procedure should be abandoned if there is evidence of somatic blockade.
- After confirmation of pain relief and lack of somatic block, 6 ml phenol 6% is injected through each needle using glass syringes. The needles are then cleared with air or local anesthetic 1 ml, and removed.
- Monitors should be left attached and i.v. access left in situ for at least 30 minutes.
- Ultrasound may help placement of the needle (*Figs 5.6.9–5.6.10*).



Fig. 5.6.2

Confirmation of a successful block

- Relief of lower abdominal pain.

Tips

- After injection of non-ionic radio-contrast medium, a blush will indicate injection into muscle. If this disappears immediately it is likely that intravascular injection has occurred.



Fig. 5.6.3

- Consideration should be given to performance of the block under CT control if the block is unsuccessful (*Fig. 5.6.10*).

Potential problems

- The position of each needle tip should always be confirmed with fluoroscopy prior to injection of neurolytic agents as it may lie in the peritoneal cavity, within a viscus or intravascularly. If a needle tip is placed too superficially, the tip may come to lie in the intervertebral foramen and injection may result in an epidural block or a somatic nerve block. Injection of neurolytic solution into the psoas muscle may cause rhabdomyolysis.
- Perforation of the aorta or the inferior vena cava is possible and consequently the block should be avoided in patients with coagulopathy. Dissection of the aorta may occur as a result of direct damage during the block. Retroperitoneal hematoma may occur and for this reason also the block should be avoided in patients with coagulopathy.



Fig. 5.6.4



Fig. 5.6.6



Fig. 5.6.5



Fig. 5.6.7


Superior
hypogastric
plexus
Bifurcation of
iliac vessels
Psoas
major muscle

Fig. 5.6.8

- Orthostatic hypotension may occur as a result of sympathetic blockade for up to three days after a neurolytic block. Diarrhea may occur also and hydration of the patient should be monitored.
- Transient motor paralysis and paraplegia may occur after the block, probably as a result of spasm of segmental arteries.
- Perforation of the intervertebral disc may occur, but this is usually of no clinical significance.



Fig. 5.6.9


S 2
T 5
V 125
D 115

Fig. 5.6.10

5.7 GANGLION IMPAR BLOCK

Anatomy

The ganglion impar is a retroperitoneal sympathetic ganglion located at the level of the sacrococcygeal junction (**Fig. 5.7.1**). Above the level of this ganglion the sympathetic chains are paired. Sympathetic afferents from the perineum, distal rectum and anus, distal urethra, vulva and the distal third of the vagina converge in the ganglion impar.



Fig. 5.7.1

Equipment

- 2ml, 5 ml, and 10 ml syringes
- 30 G needle
- 22 G spinal needle
- Extension set (optional)
- ECG, BP, and SpO_2 monitors
- Resuscitation equipment (*see Appendix 3*)

Drugs

- Lidocaine (lignocaine) 1%, 5 ml for skin infiltration
- Lidocaine (lignocaine) 1%, 15–20 ml (or its equivalent) for block
- Phenol 6%
- Non-ionic radio-opaque contrast medium
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Prone.
- Pillow under anterior superior iliac spine to flatten the normal lumbar lordosis (*Fig. 5.7.2*).

Needle puncture and technique

- Intravenous access is inserted.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- The midline along the intergluteal groove and an area 10 cm × 5 cm laterally is cleaned with antiseptic



Fig. 5.7.2

solution and a fenestrated drape is placed over the sterile area.

- A skin wheal is raised at the superior aspect of the intergluteal groove, just above the anus, over the anococcygeal ligament (*Fig. 5.7.3*).
- The stylet from the 22 G spinal needle is removed, and the needle is bent with the fingers to form a 30° angle, approximately 2 cm from the hub.
- The needle is inserted through the skin wheal, with the concave curvature facing posteriorly.
- With the aid of fluoroscopy, the needle is advanced deep into the coccyx, closely approximating its anterior surface, until the tip reaches the level of the sacrococcygeal junction (*Fig. 5.7.4*).


Iliac crest
Posterior suprior iliac spine
Sacral cornua
Sacral hiatus
Coccyx
Anococcygeal ligament
Anus

Fig. 5.7.3


Sacrococcygeal junction
Ganglion impar
Retroperitoneal space
Anococcygeal ligament
Sacrum
Anus
Rectum

Fig. 5.7.4

- After negative aspiration, the fluoroscopic image is observed as a small amount of non-ionic radio-contrast medium is injected. The correct placement of the needle is indicated by the presence a small round blob of contrast medium at the anterior border of the vertebral column (*Fig. 5.7.5 a,b*).
- Lidocaine (lignocaine) 1% 5 ml is injected for ganglion blockade.



Fig. 5.7.5

- After 10 minutes the patient is questioned about pain relief and any somatic blockade. Sensory and motor functioning of the lower extremities is checked. The procedure should be abandoned if there is evidence of somatic blockade.
- After confirmation of pain relief and lack of somatic block, 5 ml of phenol 6% is injected using a glass syringe. To avoid leaving alcohol in the needle tract the needle is then cleared with air or local anesthetic 1 ml, and removed.
- Monitors should be left attached and i.v. access left in situ for at least 30 minutes.

Confirmation of a successful block

- Relief of perineal pain.

Tips

- To aid access to the anococcygeal ligament an assistant may be asked to retract the skin of the buttock; after penetration of the skin, this is no longer required.
- Exaggerated anterior curvature of the sacrococcygeal vertebral column may inhibit access and it may be necessary to bend the needle to a more acute angle.

Potential problems

- The position of each needle tip should always be confirmed with fluoroscopy prior to injection of neurolytic agent as it may lie in the peritoneal cavity, within a viscus or intravascularly. Caudal epidural placement of the needle is possible, therefore it is essential that spread of contrast material is observed to be restricted to the retroperitoneum, and that a test dose produces no somatic nerve blockade. Perforation of the rectum or periosteal injection is also possible.
- Local tumor invasion may inhibit spread of solution.
- Retroperitoneal hematoma may occur and the block should be avoided in patients with coagulopathy. Diarrhea may occur also and hydration of the patient should be monitored.
- There may be a detectable odor from the breath after alcohol injection.
- Patients in the prone position should be monitored carefully when intravenous sedation is administered.

5.8 INTRAVENOUS REGIONAL SYMPATHETIC BLOCK—UPPER LIMB

Anatomy

Peripheral sympathetic blockade is achieved by limiting the effect of the sympatholytic agent to the tissues of the affected limb using a tourniquet. Intravenous injection of an agent that releases endogenous norepinephrine (noradrenaline) from sympathetic nerve endings causes depletion of this neurotransmitter, and thereby chemical sympathetic blockade.

Equipment

- 20 ml syringe
- Two i.v. cannulae
- Pneumatic tourniquet
- ECG, BP, and SpO_2 monitors
- Skin temperature monitor
- Resuscitation equipment (*see Appendix 3*)

Drugs

- Lidocaine (lignocaine) 0.5% *without epinephrine/adrenaline*, or its equivalent
- Bretylium 1.5 mg/kg (or its equivalent, e.g. guanethedine 0.25 mg/kg)
- Saline (NaCl) 20 ml
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Supine.

Technique

- Intravenous access is inserted in the contralateral limb.
- Peripheral i.v. access is inserted in the limb to be blocked (*Fig. 5.8.1 a*).
- Monitors are attached.



Fig. 5.8.1



Fig. 5.8.2

- Resuscitation equipment and drugs are checked and made ready for use.
- The limb is raised above the level of the heart for 2 minutes (*Fig. 5.8.1 b*).
- With the limb raised, it is exsanguinated by applying a tight wrap, e.g. Esmarch bandage.
- A thin layer of padding is applied, e.g. Velband, under the tourniquet site.
- The tourniquet is applied and the cuff is inflated to a pressure 100 mmHg higher than the systolic blood pressure (*Fig. 5.8.2*).
- The limb is then lowered. A mixture of lidocaine (lignocaine) 0.5% 15 ml (*without epinephrine/adrenaline*), bretylium 1.5 mg/kg (or guanethidine 0.25 mg/kg), and NaCl to make a total volume of 40 ml (a final lidocaine (lignocaine) solution of 0.25%), is injected through the i.v. cannula in the affected limb.
- The tourniquet is allowed to remain inflated for at least 30 minutes.



Fig. 5.8.3

- It is then deflated in one step, but left in place. Re-inflation may be required if there is a precipitous change in blood pressure.
- Monitors should be left attached and i.v. access left in situ for at least 30 minutes.

Confirmation of a successful block

- Relief of sympathetically maintained pain.
- Measurements of skin temperature of the affected limb before and after the block should demonstrate temperature increase. However, the sympatholytic effect of the drug may not be immediate (*Fig. 5.8.3*).

Tips

- If i.v. access to the affected limb is difficult due to vasoconstriction, a smear of glycerol trinitrate cream on the dorsum of the hand will usually aid i.v. insertion.
- A single or double cuff may be employed for this block but a double tourniquet may make the block more comfortable. The proximal cuff is inflated first. A few minutes after injection the distal cuff is inflated and **when inflation is complete the proximal cuff is released.**
- Retrograde cannulation, i.e. towards the periphery (*Figs 5.8.4, 5.8.5*) rather than proximally (*Figs 5.8.6, 5.8.7*), may help direct the spread of bretylium to the periphery.
- Active or passive movements of the limb may hasten the distribution of bretylium to the periphery.
- If the tourniquet inflation is painful, inhalation of nitrous oxide–oxygen mixture may improve comfort.
- Repeated blocks may bring about gradual improvement in sympathetically maintained pain.



Fig. 5.8.4



Fig. 5.8.6



Fig. 5.8.5



Fig. 5.8.7

- Immediate physiotherapy after block may improve outcome.

Potential problems

- Accidental deflation of the tourniquet early in the procedure may cause a precipitous rise in blood pressure due to the general release of endogenous norepinephrine/noradrenaline when unfixed bretylium enters the circulation. Systemic toxicity of lidocaine (lignocaine) may also occur, possibly causing seizures. Blood pressure may decrease after deflation of the cuff later in the procedure.
- The tourniquet inflation may be painful.
- A sensation of burning may occur after injection due to release of endogenous norepinephrine.
- Neuropraxia may occur (rarely) with a very tight tourniquet.
- Avoid in sickle cell anemia.

5.9 INTRAVENOUS REGIONAL SYMPATHETIC BLOCK—LOWER LIMB

Anatomy

As in the case of the upper limb, peripheral sympathetic blockade is achieved by limiting the effect of the sympatholytic agent to the tissues of the affected limb using a tourniquet. Intravenous injection of an agent releases endogenous norepinephrine (noradrenaline) from sympathetic nerve endings, which causes depletion of this neurotransmitter, and may bring about a chemical sympathetic block.

Equipment

- 50 ml syringe
- Two i.v. cannulae
- Pneumatic tourniquet
- ECG, BP, and SpO_2 monitors
- Skin temperature monitor
- Resuscitation equipment (*see Appendix 3*)

Drugs

- Lidocaine (lignocaine) 0.5% *without epinephrine (adrenaline)*, or its equivalent
- Bretylium 1.5 mg/kg (or its equivalent, e.g. guanethedine 0.5 mg/kg)
- Saline (NaCl) 30 ml
- Resuscitation drugs (*see Appendix 3*)

Position of patient

- Supine.

Technique

- Intravenous access is inserted in the contralateral limb.
- Peripheral i.v. access is inserted in the limb to be blocked.
- Monitors are attached.
- Resuscitation equipment and drugs are checked and made ready for use.
- The limb is raised above the level of the heart for 2 minutes (*Fig. 5.9.1*).
- With the limb raised, it is exsanguinated by applying a tight wrap (*Fig. 5.9.2*).
- A thin layer of padding is applied, e.g. Velband, under the tourniquet site.
- The tourniquet is applied and inflated to a pressure 100 mmHg higher than the systolic blood pressure. A second tourniquet may be applied to the calf of patients with no known predispositions to deep venous thrombosis. Inflation of this second cuff may aid limitation of spread of sympatholytic agent to the periphery (*Fig. 5.9.3*).
- The limb is then lowered and a mixture of lidocaine (lignocaine) 0.5% 25 ml (*without epinephrine*), bretylium 1.5 mg/kg (or its equivalent) and NaCl to make a total volume of 40 ml (a final lidocaine/lignocaine solution of 0.25%) is injected through the i.v. cannula in the affected limb.
- The tourniquet is allowed to remain inflated for at least 30 minutes.
- It is then deflated in one step, but left in place. Re-inflation may be required if there is a precipitous change in blood pressure.



Fig. 5.9.1



Fig. 5.9.2

- Monitors should be left attached and i.v. access left in situ for at least 30 minutes.

Confirmation of a successful block

- Relief of sympathetically maintained pain.
- Measurements of skin temperature of the affected limb before and after the block should demonstrate temperature increase (*Fig. 5.9.4*).

Tips

- If i.v. access to the affected limb is difficult due to vasoconstriction, a smear of glycerol trinitrate cream on the dorsum of the foot will usually aid i.v. insertion.
- A single or double cuff may be employed for this block but a double tourniquet may make the block more comfortable. The proximal cuff is inflated first. A few minutes after injection the distal cuff is inflated and when inflation is complete the proximal cuff is released.
- Retrograde cannulation, i.e. towards the periphery (*Fig. 5.9.5*) rather than proximally (*see Fig. 5.9.3*), may help direct the spread of bretylium to the periphery.
- Active or passive movements of the limb may hasten the distribution of bretylium to the periphery.
- If the tourniquet inflation is painful, inhalation of nitrous oxide–oxygen mixture may improve comfort.
- Repeated blocks may bring about gradual improvement in sympathetically maintained pain.
- Immediate physiotherapy after block may improve outcome.



Fig. 5.9.3



Fig. 5.9.4



Fig. 5.9.5

Potential problems

- Accidental deflation of the tourniquet early in the procedure may cause a precipitous rise in blood pressure due to the general release of endogenous norepinephrine or epinephrine when unfixed bretylium enters the circulation. Systemic toxicity of lidocaine (lignocaine) may also occur in high doses possibly causing seizures. Blood pressure may decrease after deflation of the cuff later in the procedure.
- The tourniquet inflation may be painful.
- A sensation of burning may occur after injection due to release of endogenous norepinephrine.
- Neuropraxia may occur (rarely) with a very tight tourniquet.
- Avoid in sickle cell anemia.

MUSCLE INJECTIONS

6

Myofascial pain occurs commonly in the muscles of the upper and lower back. It is characterized by pain associated with movement of the affected muscles that develop areas of extreme tenderness, termed trigger points. Palpation of these points is usually perceived as a tight band or firm nodule in the muscle and reproduces pain that may be referred some distance from the site of palpation. Involuntary muscular contraction can occur on palpation, and snapping palpation can result in a local twitch response. Electromyography (EMG) is not reliable in diagnosing myofascial pain syndrome and it is worth remembering that this syndrome may occur in association with underlying painful disorders of the spine.

Injection of trigger points with local anesthetic, especially if repeated several times and combined with stretching exercises, may have a beneficial therapeutic effect on the pain of myofascial pain syndrome. Pain reproduction during injection, followed by relief of pain after injection, that lasts at least as long as the expected local anesthetic effect, indicates that these painful points contribute to myofascial pain syndrome.

Fibromyalgia is a pain syndrome characterized by widespread, diffuse and usually symmetrical tender areas of muscles. Bony structures, such as costochondral junctions and lateral epicondyles, produce local pain, but not referred, on palpation of tender points. Injection of these tender areas typically does not improve the pain of fibromyalgia.

Usually a dilute solution of local anesthetic suffices for beneficial effect. Bupivacaine produces more muscle degeneration than any other local anesthetic when injected into a muscle, and consequently it is usually avoided, lidocaine (lignocaine) being the usual local anesthetic of choice.

The optimum number of trigger-point injections required to produce pain relief is variable. The injection sites may themselves be painful after the local anesthetic wears off. This may exacerbate muscle spasm if too many trigger-point injections are performed. Consideration should be given to the severity of the muscle spasm, the number of trigger points, and to the sensitivity of the patient to pain when deciding on the number of injections.

6.1 TRIGGER-POINT INJECTIONS—NECK AND THORAX

Anatomy

The muscles most often involved in myofascial pain syndrome of the neck include the trapezius, rhomboid minor and major, latissimus dorsi, levator scapulae and splenius capitis (**Fig. 6.1.1**; see also Fig. 2.1.2).



Fig. 6.1.1



Fig. 6.1.2

Equipment

- 10 ml syringe
- 25 G needle

Drugs

- Lidocaine (lignocaine) 1% 10 ml

Position of patient

- Prone.
- Pillow under chest to allow the neck to flex.
- The sitting position is also used, but vasovagal response may follow trigger-point injections especially in young adults, and it is probably more prudent to use the prone position.

Needle puncture and technique

- The neck, shoulders, and upper posterior thorax are cleaned with antiseptic solution.
- **Trigger points in the muscles are palpated** (**Fig. 6.1.2**) **and marked** (*Fig. 6.1.3*).
- A 25 G needle with syringe attached is inserted into a trigger point (*Fig. 6.1.4*).
- After negative aspiration, 2–3 ml of lidocaine (lignocaine) 1% is injected into the trigger point while moving the needle back and forth through the muscle.
- After injection, the next trigger point is injected in the same manner (*Fig. 6.1.5 a,b*).

Confirmation of a successful injection

- Pain reproduction when the needle enters the muscle confirms correct placement.



Fig. 6.1.3



Fig. 6.1.4

Tips

- For best results, injection is carried out in a fan-like manner by repeatedly withdrawing the needle slightly and redirecting it.
- Stretching of the involved muscles by physiotherapy within the duration of the local anesthesia improves results.
- Some workers advocate massage of the area immediately after injection.

Potential problems

- Pain on injection.
- Vasovagal response (especially in young adults in the sitting position).
- Pneumothorax (especially in thin patients).


A
B
Skin
Subcutaneous tissue
Muscle
Trapezius
Supraspinatus (under trapezius)
Infraspinatus
Teres minor
Teres major

Fig. 6.1.5

6.2 TRIGGER-POINT INJECTIONS—BACK

Anatomy

The muscles most often involved in myofascial pain syndrome of the back include the erector spinae (the longissimus, iliocostalis, and spinalis columns) and the deep transversospinal (semispinalis, multifidus, and rotatores) muscles (**Fig. 6.2.1 a,b**). In the buttocks, spasm of the gluteus medius muscle may also cause significant pain.

Equipment

- 10 ml syringe
- 25 G needle

Drugs

- Lidocaine (lignocaine) 1% 10 ml

Position of patient

- Prone.
- Pillow under abdomen to straighten the normal lumbar lordosis (*Fig. 6.2.2 a*).
- The sitting position is also used, but vasovagal response may follow trigger-point injections, and it is probably more prudent to use the prone position.
- Alternatively, the semiprone position will also allow access to affected muscles (*Fig. 6.2.2 b*).


External oblique
Latissimus dorsi
Longissimus and iliocostalis
Quadratus lumborum
Internal oblique
A
Psoas major
Quadratus lumborum
Interspinalis
Multifidus
Iliocostalis
Longissimus
B

Fig. 6.2.1



Fig. 6.2.2

Needle puncture and technique

- The midline and the surrounding area are cleaned with antiseptic solution.
- **Trigger points in the muscles are identified by palpation and marked** (*Fig. 6.2.3*).
- A 25 G needle with syringe attached is inserted into a trigger point (*Fig. 6.2.4*).
- After negative aspiration, 2–3 ml of lidocaine (lignocaine) 1% is injected into the trigger point while moving the needle back and forth through the muscle (*Fig. 6.2.5*).



Fig. 6.2.3



Fig. 6.2.4

- After injection, the next trigger point is injected in the same manner.

Confimation of a successful injection

- Pain reproduction when the needle enters the muscle confirms correct placement.

Tips

- For best results, injection is carried out in a fan-like manner by repeatedly withdrawing the needle slightly and redirecting it.
- Stretching of the involved muscles by physiotherapy within the duration of the local anesthetic improves results.
- Some workers advocate massage of the area immediately after injection.

Potential problems

- Pain on injection.
- Vasovagal response (especially young adults in the sitting position).
- Pneumothorax (especially in thin patients) is also a possibility when injecting the upper back.



Fig. 6.2.5

6.3 GLUTEUS MEDIUS INJECTION

Anatomy

When the buttock muscles are relaxed the quadratus femoris, gemelli and gluteus medius muscles can be palpated. Spasm of the gluteus medius muscle (**Fig. 6.3.1**) may be the source of buttock pain and may respond to trigger-point injection. Unlike pirformis muscle spasm, this does not produce symptoms of sciatic nerve irritation but causes localized pain, often referred to the posterior thigh and calf.

Equipment

- 10 ml syringe
- 22 G needle

Drugs

- Lidocaine (lignocaine) 1% 10 ml

Position of patient

- Prone.
- Pillow under abdomen to flatten the normal lumbar lordosis (*Fig. 6.3.2*).

Needle puncture and technique

- The surface of the buttock and hip is cleaned with antiseptic solution.
- The posterior superior iliac spine is palpated and marked.
- The greater trochanter is palpated.
- **The insertion point of the needle lies approximately 2 cm medial and superior to the greater trochanter** (*Figs 6.3.3, 6.3.4*).
- A 22 G needle is introduced in a direction vertical to the skin and advanced until it is felt to be gripped by the tense muscle (*Fig. 6.3.5*).



Fig. 6.3.1



Fig. 6.3.2



Fig. 6.3.3



Fig. 6.3.4



Fig. 6.3.5



Fig. 6.3.6

- After negative aspiration, lidocaine (lignocaine) 1% 3 ml is injected in the substance of the muscle while moving the needle back and forth in the muscle (*Fig. 6.3.6*).
- The procedure is repeated if other trigger points are present in the muscle.

Confirmation of a successful injection

- Pain reproduction when the needle enters the muscle confirms correct placement of the needle.
- Relief of pain on abduction of the hip.

Tips

- For best results injection is carried out in a fan-like manner by repeatedly withdrawing the needle slightly and redirecting it (*see inset in Fig. 6.3.6*).

Potential problems

- Sciatic nerve block: although this is unusual because the injection site is not very close to the sciatic notch, it is prudent to warn the patient of the possibility.
- Infection or abscess formation.

6.4 PIRIFORMIS INJECTION

Anatomy

The piriformis muscle inserts into the pelvic surface of the sacrum from the second to the fourth segments, lateral to the anterior sacral foramina, and passes out of the pelvis through the greater sciatic foramen to insert into the superior aspect of the greater trochanter (**Fig. 6.4.1**). It overlies the sciatic nerve in the greater sciatic foramen. Contraction contributes to abduction of the lower limb. Spasm of the muscle in myofascial pain syndrome often causes pain referred to the posterior thigh and calf.

Equipment

- 2 ml syringe and two 5 ml syringes
- 25 G needle
- 22 G spinal needle, end-opening

Drugs

- Lidocaine (lignocaine) 1% 10 ml (or its equivalent)

Position of patient

- Prone.
- Pillow under abdomen to flatten the normal lumbar lordosis (*Fig. 6.4.2*).



Fig. 6.4.1

Needle puncture and technique

- The surface of the buttock and hip is cleaned with antiseptic solution and a fenestrated drape is placed over the sterile area.
- The posterior superior iliac spine is palpated and marked.
- The greater trochanter is palpated and marked.
- **The insertion points of the needle lie at the points one-third and two-thirds along, and 1–3 cm below the line connecting these two marks** (*Figs 6.4.3 a,b,c*).
- The first insertion point, the medial one, is infiltrated with lidocaine (lignocaine) 1% 2 ml.
- A 22 G spinal needle is introduced in a direction vertical to the skin and advanced until it is felt to be gripped by the tense piriformis muscle, or until bone is contacted (*Figs 6.4.4, 6.4.5*).
- The end-point is a fascial click at a depth of about 4–5 cm, depending on the thickness of adipose tissue.
- The patient is questioned about the presence of pain, paresthesia, and changes in sensation in the distribution of the sciatic nerve, while the needle is being advanced.
- If these symptoms arise, the needle may be in contact with the sciatic nerve and should be repositioned. It is also possible that spasm of the muscle on needle insertion may produce these symptoms and often reproduction of pain occurs with entry into the muscle.
- After negative aspiration, lidocaine (lignocaine) 1% 5 ml is injected.
- Ultrasound may aid placement of the needle (*Fig. 6.4.6 a,b*)

Confirmation of a successful injection

- Relief of pain on abduction of the lower limb against pressure on the lateral knee in the sitting position.

Tips

- If injection is not successful in relieving the pain, it may be repeated at the lateral insertion point. This lies at a



Fig. 6.4.2


Sacral cornua
Sciatic nerve
Posterior superior iliac spine
Piriformis muscle
Gluteus minimus
Greater trochanter
A
Sacral cornu
Sciatic nerve
Posterior superior iliac spine
Piriformis muscle
Greater trochanter
B
PSIS
GT
C

Fig. 6.4.3



Fig. 6.4.4


Piriformis muscle

Fig. 6.4.5

point two-thirds along and 1–3 cm below the line joining the posterior superior iliac spine and the greater trochanter.

Potential problems

- Sciatic nerve block.
- Infection or abscess may occur (rarely).


PSIS
A
PSIS
B

Fig. 6.4.6

TRANSCUTANEOUS ELECTRICAL NERVE STIMULATION (TENS)

7

Transcutaneous electrical nerve stimulation is thought to modify pain appreciation by stimulation of large fibers thereby blocking (or "closing the gate" to) smaller C-fibers carrying nociceptive impulses. There is also evidence that high-frequency stimulation of the skin increases latency and decreases maximum firing rates in small afferent fibers. This can produce conduction blockade in C-fibers as the current is increased, probably via potassium efflux from the axon. It is thought that a combination of these actions is responsible for the analgesia derived from the use of TENS. This is probably not related to opiate-mediated mechanisms when conventional parameters are used.

Not all pain responds to TENS. If the usual parameters do not produce pain relief, low frequency, high intensity stimulation may be tried. This means that the current amplitude is increased to a level that produces mild discomfort and muscle stimulation. Analgesia from this type of stimulation may be due to opiate-mediated mechanisms. Burst stimulation means short bursts of high frequency stimulation delivered at 1–2 Hz and may also relieve pain that is not responsive to conventional TENS.

A TENS trial may be carried out prior to giving the unit to the patient to use at home. This allows the patient to become familiar with the use of TENS, and to ensure that the pain is not aggravated by its use. A minimum of one hour is recommended as the trial period. This will indicate whether the patient is likely to respond to TENS. However, failure to respond within this time period does not necessarily mean that there will be no response if used for longer periods, or with different settings. It is important to allow the patient to use the TENS at home for a period of at least 14 days.

The TENS stimulator is a battery-operated pulse generator which has several controls. These include an on/off switch plus amplitude control, frequency control, mode selector, and width control. In addition, multichannel units have amplitude controls for each channel. The pulse generator connects to leads that then connect to electrodes, which are applied to the skin. Electrodes are applied in pairs, and are positioned so that they lie along the direction of the nerves in the area being treated, e.g. longitudinally in the limbs, but dermatomally in the trunk.

Control settings (*Figs 7.1.1, 7.1.2*)

CONTINUOUS STIMULATION

- Amplitude set to zero.
- Pulse width set to midrange.
- Switch to continuous mode.
- Increase pulse amplitude level gradually to the maximum level for comfort (sensation should be strong but not painful).
- Adjust pulse frequency to maximum level for comfort (amplitude may be reduced as pulse width is increased).
- Adjust pulse width to maximum level for comfort.
- Maintain for 45–60 minutes.



Fig. 7.1.1



Fig. 7.1.2

Modulated settings

BURST STIMULATION

- All controls set to zero.
- Switch to pulsed mode.
- Frequency set to 1–2 Hz.
- Increase amplitude and pulse width as with continuous mode described above.
- Maintain for 45–60 minutes.

LOW-FREQUENCY HIGH-INTENSITY STIMULATION

- All controls set to zero.
- Increase amplitude to level where the muscle underlying the electrodes twitches visibly but not painfully.
- Increase frequency to 2–4 Hz.
- Maintain for short period (5–15 minutes).

All the types of stimulation should be tried for each pain, and the effects on the pain should be compared. The optimum parameters must be found by trial and error. The patient is usually advised to begin by using TENS for at least one hour three times a day. Once the effect of TENS on the pain is known it is recommended that stimulation should be discontinued after 30 minutes if the patient experiences one or more hours of analgesia from a single application. If pain relief is achieved only during stimulation, the unit can be kept on constantly. However, electrode sites should be changed every 24 hours. Occasionally, skin rash under the electrodes may occur and this problem may be minimized by frequent rotation of the electrode sites and with topical steroids. However, very few side effects are associated with the use of TENS. Electrical skin burns may occur if TENS is applied to skin with poor innervation and it is necessary to ensure that there is normal sensation prior to applying the electrodes. Allergic reaction to the electrodes or the adhesive tape has also been described, but is not common.

Use of TENS is contraindicated on areas over the anterior neck (stimulation of carotid sinus, larynx), over the pregnant uterus or in the presence of a cardiac pacemaker.

Note: Description of the insertion technique of a spinal cord stimulator or peripheral nerve stimulator is outside the scope of this text as the techniques are specific to the different types of stimulator.

APPENDIX 1

SUGGESTED CORTICOSTEROIDS

Drug name	Duration of action	Equivalent dosage (mg)	Anti-inflammatory potency (relative)	Mineralocorticoid potency (relative)
Triamcinolone[a]	12–36 h	4	5	0
Methylprednisolone	12–36 h	4	5	0.5
Dexamethasone	48 h	0.75	25	0
Hydrocortisone	12 h	20	1	2

[a] *Triamcinolone diacetate recommended for central neuroaxial injections.*

Corticosteroid injection side effects

LOCAL SIDE EFFECTS

- Atrophy of subcutaneous tissue
- Rupture of injected tendon
- Depigmentation of skin
- Infection

SYSTEMIC SIDE EFFECTS (HIGHER INCIDENCE WITH LARGER DOSES)

- Skin flushing
- Irregularity of the menstrual cycle
- Impaired glucose tolerance
- Osteoporosis
- Muscle wasting and myopathy
- Arthropathy
- Suppression of adrenal function
- Psychologic upset

APPENDIX 2

SUGGESTED NEUROLYTIC AGENTS

- Aqueous phenol 6%.
- Alcohol 100% may be diluted to 50% (pain on injection may be experienced and it is recommended that the nerve is blocked with local anesthetic prior to injection).

APPENDIX 3

RECOMMENDED RESUSCITATION DRUGS AND EQUIPMENT

SUGGESTED RESUSCITATION DRUGS

Drug	Suggested dosage (70 kg adult)	Indication
Atropine	0.2–0.4 mg i.v. increments	Bradycardia from vagal dominance
Ephedrine	5–10 mg i.v. increments	Hypotension from sympathetic block
Lidocaine (lignocaine)	50–100 mg i.v. bolus	Ventricular arrhythmias
Midazolam	1–3 mg i.v. increments	Local anesthetic; seizure activity
Diazepam	2.5–5 mg i.v. increments	Local anesthetic; seizure activity
Thiopental (thiopentone)	50–100 mg i.v. increments	Local anesthetic; seizure activity
Succinylcholine	50–100 mg i.v. bolus	Muscle relaxation; airway control

It is also recommended that the full range of drugs required for advanced cardiac life support (ACLS), including pre-filled syringes, be available in the operating room.

Suggested resuscitation equipment

- Oxygen source
- Bag and masks (full range)
- Breathing system for positive pressure ventilation
- Oro- and nasopharangeal airways (full range)
- Laryngoscopes and blades (full range)
- Endotracheal tube stylets and forceps, e.g. Magill's forceps

APPENDIX 4

DERMATOMES


C2
C3
C4
C5
T2
3
4
5
6
7
8
9
10
11
12
L1
C5
T2
T1
C6
C7
C8
T2
C6
T1
C7
C8
S3
S3
S4
L2
L2
S2
L3
L3
S2
L4
L5
L5
S1
S1

Fig. A.4.1


C2
C3
C3
T1
C4
C4
T2
3
4
5
6
7
8
9
10
11
12
L1
C5
C5
T2
T2
T1
T1
S1
C6
C6
L3
S5
Coc
C7
C8
C7
C8
L2
S3
S4
L2
S2
S2
L3
L4
L5
S1
S1
L5
S1
L5
L4
L4
S1
L5

Fig. A.4.2


L3
L3
L5
L5
S2
S2
L4
L4
L2
L2
S4
L2
S3
S3
L2
S1
S1
L5
S1
Coc
S1
L5
S5

Fig. A.4.3


C2
C3
C4
C6
C5
T2
C5
C6
T1
3
T1
C7
C8
4
5
6
7
8
9
10
11
12
L1
C8
C7
L2
L3
L2
L5
L5
S1
S2
S3
S4
S2
S1
S5
L4
L3
L3
L4
Coc
C2
C3
C6
C5
C4
C4
C5
C6
T1
T2
T2
T2
T1
C7
C8
C7
C8
3
4
5
6
7
8
9
10
11
12
L2
L1
L2
S1
S1
L3
L3
L4
L4
L5
S3
S3
L5

Fig. A.4.4


L3
C3
C4
T2
3
4
5
6
7
8
9
10
11
12
L1
S3
C2
C5
L2
T1
C6
L3
S2
C7
C8
L4
L5
S1

Fig. A.4.5


C2
C3
C4
C4
C5
C5
T2
3
4
5
T2
T2
6
7
8
9
10
11
12
C6
T1
T1
C6
C7
C7
L1
C8
S3
S4
C8
L2
L2
L3
L3
L4
L4
L5
L5
S1
S1

Fig. A.4.6

APPENDIX 5

SPINAL CORD SEGMENTAL MYOTOMES

Each muscle in the body is supplied by a particular level or segment of the spinal cord and by its corresponding spinal nerve.

- C5 also supplies the shoulder muscles and the muscle that we use to bend our elbow.
- C6 is for bending the wrist back.
- C7 is for straightening the elbow.
- C8 bends the fingers.
- T1 spreads the fingers.
- T1–T12 supplies the chest wall and abdominal muscles.
- L2 bends the hip.
- L3 straightens the knee.
- L4 pulls the foot up.
- L5 wiggles the toes.
- S1 pulls the foot down.
- S3, S4 and S5 supply the bladder, bowel and sex organs, and the anal and other pelvic muscles.



Fig. A.5.1

APPENDIX 6

LUMBO-SACRAL SPINE ANATOMY


Spinal cord
Pia mater
Arachnoid
Dura mater
Conus medullaris
Cauda equina
Ligamentum flavum (L3–4)
Epidural space
Internal filum terminale
Sacrum
Distal dural sac
External filum terminale
Coccyx
L1
L2
L3
L4
L5
L1
L2
L3
L4
L5
Sacrum
S1
S2
S3
S4
S5

Fig. A.6.1

INDEX

Page numbers followed by “f” indicate figures, “t” indicate tables, and “b” indicate boxes.

A

- abdominal discomfort, 81, 85
- abdominal viscera, 77
- abscess
  - epidural, 33
  - post-gluteus medius injection, 107
- ACLS (advanced cardiac life support), 117
- action potentials, 1
- adipose tissue, 108
- adrenal function suppression, 113
- adrenaline *see* epinephrine
- advanced cardiac life support (ACLS), 117
- air
  - in interpleural block, 43
  - in lumbar epidural block, 20
  - in thoracic epidural block, 23
  - in thoracic nerve root block, 53
- alcohol, 115
  - in celiac plexus block
    - anterocrural approach, 83, 85
    - retrocrural approach, 80–81
  - in ganglion impar block, 93
- allergic reaction
  - caudal epidural block, 33
  - cervical epidural block, 29
  - lumbar epidural block, 20
  - thoracic epidural block, 24
- allodynia, 1
- analgesia
  - opiate-mediated mechanisms and, 111
  - unpredictable, 46
- analgesics, mild, 15
- anemia, sickle cell, 96, 99
- anesthetics, local *see* local anaesthetics
- anococcygeal ligament, 93
- anterior costotransverse ligament, 51f–52f
- anterior scalenus, 70f
- anterior superior iliac spine
  - in autonomic blockade, 73, 78, 82, 87, 91
  - in joint injections, 4, 12
  - in somatic nerve blockade, 47, 55
- anterocrural spread, 77f, 82f
- anteromedial capsule, 6, 10
- anus, 91–92, 92f
- anxiety, 2
- aorta
  - anatomy, 77
  - dissection, 84, 88
  - perforation, 76, 81, 84, 88
- aortic artery, 79f, 84f
- aortic plexus, 86
- arachnoid mater, 16
- arteries
  - aortic, 79f, 84f
  - carotid, 66, 70f
  - celiac, 77f
  - external iliac, 86f
  - intercostal, 38f
  - internal iliac, 86f
  - mesenteric, 77
  - occipital, 60
  - segmental, 81, 85, 90
  - subclavian, 70f
  - superior mesenteric, 78f, 84f
  - vertebral, 66, 70–71, 70f
- arthropathy, 113
- aseptic meningitis
  - after caudal epidural block, 33
  - after cervical epidural block, 29
  - after lumbar epidural block, 20
  - after thoracic epidural block, 24
- atlas, 25f
- atropine, 117
- autonomic blockade, 65–99
- autopsy, 37
- axis, 25f
- axon, potassium efflux from, 111
- axonal degeneration, 111
- azygos vein, 52f

B

- bacterial contamination, 62, 76
- bilateral stellate ganglion block, 69
- bladder, 15, 86
- blood aspiration
  - intercostal nerve block, 41–42
  - stellate ganglion block
    - C7 approach, 72
    - C6 (classic) approach, 68
- blood pressure changes, 18, 22–23, 27, 31, 34
  - fall, 96, 99
  - rise, 68, 96, 99
  - systolic, 95, 97
- bowel dysfunction, 15
- brachial plexus, 43, 66, 68, 72
- bradycardia, 29, 117
- brainstem, 61
- breath
  - after alcohol injections, 81, 85, 93
  - shortness of, 69, 72
- breathing systems, 117
- bretylium in intravenous regional sympathetic block
  - lower limb, 97–98
  - upper limb, 68, 95
- buccal cavity, 62
- bupivacaine, 44, 101
- burning sensation, 96, 99
- buttock pain, 106

C

- calf, 97, 106, 108
- cancer
  - pain, 65
  - pancreatic, 2, 65
  - pelvic, 65
- cannulation, retrograde *see* retrograde cannulation
- carcinoma of the head of the pancreas, 2
- cardiac pacemaker, 112
- cardiovascular system (CVS) collapse, stellate ganglion block
  - C7 approach, 70–72
  - C6 (classic) approach, 66, 68–69
- carotid arteries, 66, 70f
- carotid pulse, 67, 71
- carotid sinus, 112
- catheter
  - epidural *see* epidural catheter, long-term
  - intercostal, 40–41
  - interpleural, 44
  - passer, 34–36
  - thoracic nerve root block, 53
- cauda equina, 55, 125f
- caudal anesthesia, 30
- caudal epidural block, 30–33
  - anatomy, 30, 30f
  - confirmation of success, 33
  - drugs, 30
  - equipment, 30
  - needle puncture and technique, 31f
    - adult, 30–32
    - fluoroscopic-guided, 32, 32f–33f
    - right-handed operator, 31–32, 31f–32f
  - position of patient, 30, 30f
  - potential problems, 33
  - with sacral nerve root block, 57
  - tips, 33, 33f
- caudal epidural space, 31, 33
- cavernous sinus, 61
- celiac artery, 77f
- celiac axis, 78f, 84f
- celiac block
  - classical, 78f, 84f
  - prevascular, 78f, 84f
- celiac ganglia, 77
- celiac plexus, 77
- celiac plexus block
  - anterocrural approach, 82–85
    - anatomy, 82, 82f
    - confirmation of success, 83
    - drugs, 82
    - equipment, 82
    - needle puncture and technique, 82–83, 84f
    - position of patient, 82, 83f
    - potential problems, 84–85
    - tips, 83

  retrocrural approach, 77–81
    anatomy, 77, 77f–78f
    confirmation of success, 80
    drugs, 78
    equipment, 78
    needle puncture and technique, 78–80, 79f–80f
    position of patient, 78, 78f
    potential problems, 81
    tips, 81
cerebrospinal fluid (CSF), 16, 60, 64
cervical anterior tubercle, sixth, 66–68
cervical disc pain, 15
cervical epidural block, 25–29
  anatomy, 25, 25f
  confirmation of success, 29
  drugs, 25
  equipment, 25
  needle puncture and technique, 25–29, 26f–28f
    fluoroscopic guided, 28–29, 29f
  position of patient, 25
  potential problems, 29
  tips, 29
cervical epidural injection, 15
cervical epidural space, 25, 29
cervical facet joint injection, 8–11
  anatomy, 8, 8f
  confirmation of success, 9
  drugs, 8
  equipment, 8
  needle puncture and technique, 8–9, 9f–10f
  position of patient, 8, 9f
  potential problems, 10
  tips, 10
cervical ganglia, 66
cervical nerve, dorsal rami of second, 59
cervical nerve roots, 15
cervical sympathetic trunk, 66
C-fibers, 111
Chassaignac's tubercle, 66–68
chest discomfort, 81, 85
chest X-ray
  intercostal nerve block, 39
  interpleural block, 44
chylothorax, 85
cisterna magna, 60
coagulopathy
  and celiac plexus block, 81
  and facet joint injections, 10
  and hypogastric plexus block, 88
  and lumbar sympathetic block, 76
coccygeal cornu, 55f
coccygeal nerve, 55f
coccygeal vertebra, 55f
coccyx, 92, 125f
colon, 77
Complex Regional Pain Syndrome Type 1 and II, 65
computed tomography (CT) scan, 37
  in celiac plexus block, 83
  in hypogastric plexus block, 88
  in sacro-iliac joint injection, 13, 13f
  in stellate ganglion block
    C7 approach, 72
    C6 (classic) approach, 68
conjunctiva, unilateral flushing, 68, 72
consciousness, loss of in stellate ganglion block
  C7 approach, 70–72
  C6 (classic) approach, 68–69
contrast medium, non-ionic radio-opaque
  in celiac plexus block
    anterocrural approach, 83
    retrocrural approach, 78, 81
  in cervical epidural block, 29
  in cervical facet joint injection, 9
  in ganglion impar block, 92
  in hypogastric plexus block, 87–88
  in intercostal nerve block, 40, 41f
  in long-term epidural catheter insertion, 36
  in lumbar epidural block, 19
  in lumbar facet joint injection, 4–5
  in lumbar nerve root block, 48
  in lumbar sympathetic block, 74
  in sacral nerve root block, 57
  in sacro-iliac joint injection, 13
  in thoracic epidural block, 23
  in thoracic nerve root block, 52
  in trigeminal ganglion (Gasserian) block, 62
conus medullaris, 55f, 125f
convulsion, 64, 66
corneal anesthesia, 64
corticosteroids, 2
  in caudal epidural block, 31–32
  in cervical epidural block, 27, 29
  in cervical facet joint injection, 9
  in lumbar epidural block, 18
  in lumbar facet joint injection, 5
  in sacro-iliac joint injection, 13
  side effects, 113
  suggested, 113
  in thoracic epidural block, 21, 23
costochondral junctions, 101
costotransverse ligament, 51f–52f, 53
coughing on injection, 40
cranial fossa, 64
cranial nerves, 61, 64
cricoid cartilage, 66–67, 71
CSF (cerebrospinal fluid), 16, 60, 64
CT *see* computed tomography (CT) scan
Cushingoid symptoms
  post-caudal epidural block, 33
  post-cervical epidural block, 29
  post-lumbar epidural block, 20
  post-thoracic epidural block, 24
cutaneous fibers, 47
cutaneous nociceptors, 1
CVS collapse *see* cardiovascular system (CVS) collapse

D

decompression, 37
depression, 2
dermatomes, 119
dexamethasone, 113
diagnostic blockade, 11, 48, 53, 57, 64
diaphragm, 43, 77, 77f, 82, 82f, 84f
diaphragmatic crus, 77f, 82, 82f
diarrhea
  post-celiac plexus block, 81, 84
  post-ganglion impar block, 93
  post-hypogastric plexus block, 90
diazepam, 117
discogenic radiculopathy, 37
discomfort
  abdominal, 81, 85
  chest, 81
distal dural sac, 55, 125f
dorsal horn neurons, 1
dorsal horn pain projection cells, 1
dorsal nerve roots, 1
dural puncture, 20, 24, 29, 33
dural sac, 55, 125f
  distal, 55, 125f
dural tap, 20, 23
dura mater, 16, 125f

E

electromyography (EMG), 37, 101
endotracheal tubes, 117
ephedrine, 117
epidural abscess, 33
epidural block
  in celiac plexus block, 81, 84–85
  in hypogastric plexus block, 88–90
  lumbar, 16–20
  with lumbar nerve root block, 49
  in lumbar sympathetic block, 76
  in thoracic nerve root block, 54
epidural catheter insertion, 20, 23
  long-term, 34–36
    anatomy, 34
    confirmation of success, 36
    drugs, 34
    equipment, 34
    needle puncture and technique, 34–36, 34f–36f
    position of patient, 34, 34f
    potential problems, 36
    tips, 36
epidural injection, 15–36
  caudal, 32
  cervical, 15, 25
  lumbar, 19–20, 19f
epidural needle
  in autonomic blockade, 74, 87
  in epidural block, 16, 18, 22, 26–28, 33–34
  in somatic nerve block, 40–41, 44, 46, 53
epidural space, 16, 24–25, 29, 33, 55, 125f
epidural spread, 19, 32, 49, 54, 57
epidural steroid injection, 15, 20, 23
epinephrine
  in intercostal nerve block, 41
  in intravenous regional sympathetic block, 99
  in long-term epidural catheter insertion, 34
  in lumbar epidural block, 20
  in thoracic epidural block, 23
erector spinae muscles, 104
Esmarch bandage, 95
exsanguination, 95
external filum terminale, 125f
external iliac artery, 86f
external iliac vein, 86f
external oblique muscles, 104f

F

facet joints
  cervical, 8–11
  lumbar, 3–6
  pain, 2
facet nerve injection, 10–11
fibromyalgia, 101
filum terminale, 125f
fluoroscopy
  C-arm, 4, 9
  in caudal epidural block, 32, 32f–33f

  in celiac plexus block
    anterocrural approach, 82
    needle puncture and technique, 78
  in cervical epidural injection, 28–29, 29f
  in ganglion impar block, 92–93
  in hypogastric plexus block, 87
  in lumbar epidural injection, 19–20, 19f
  in lumbar sympathetic block, 73–74
  in stellate ganglion block
    C7 approach, 72
    C6 (classic) approach, 68
foramen ovale, 61
forceps, 117

G

gangliolysis, 64
ganglion blockade *see* stellate ganglion block
ganglion impar, 91
ganglion impar block, 91–93
  anatomy, 91, 91f
  confirmation of success, 93
  drugs, 91
  equipment, 91
  needle puncture and technique, 91–93, 92f
  position of patient, 91, 91f
  potential problems, 93
  tips, 93
Gasserian block *see* trigeminal ganglion (Gasserian) block
Gasserian ganglion, 61f
gemelli muscles, 106
genitofemoral neuralgia, 76
glucose tolerance, impaired, 113
gluteus medius injection, 106–107
  anatomy, 106
  confirmation of success, 107
  drugs, 106
  equipment, 106
  needle puncture and technique, 106–107, 106f–107f
  position of patient, 106, 106f
  potential problems, 107
  tips, 107
gluteus muscles, 104
glycerol injection, 64
glycerol trinitrate cream, 98
greater auricular nerve, 59f
greater occipital nerve, 59
greater occipital protuberance, 59–60, 59f
greater sciatic foramen, 108
greater trochanter
  gluteus medius injection, 106
  piriformis injection, 108
grey rami, 38, 47
guanethedine, 94–95, 97

H

hanging drop technique, 25–27, 27f
headache
  post-caudal epidural block, 33
  post-cervical epidural block, 29
  post-lumbar epidural block, 20
  post-thoracic epidural block, 24
heart rate changes, 18, 22–23, 27, 31, 34
hematoma
  post-caudal epidural block, 33
  post-cervical epidural block, 29
  post-cervical facet joint injection, 10
  post-stellate ganglion block
    C7 approach, 72
    C6 (classic) approach, 68–69
  post-thoracic epidural block, 24
  retroperitoneal, 76, 81, 84, 88, 93
hemifacial anesthesia, 64
hoarseness, 69
hydrocortisone, 113
hyperalgesia, 1
hyperbaric neurolytic solution, 64
hypogastric plexus, 86
hypogastric plexus block, 86–90
  anatomy, 86, 86f
  confirmation of success, 87
  drugs, 87
  equipment, 86
  needle puncture and technique, 87, 88f–90f
  position of patient, 87, 87f
  potential problems, 88–90
  tips, 87–88
hypotension
  orthostatic, 81, 84, 90
  post-caudal epidural block, 33
  post-cervical epidural block, 29
  post-lumbar epidural block, 20
  post-thoracic epidural block, 24

I

iliac crest, 73
  hypogastric plexus block, 87
  lumbar epidural block, 17
  lumbar nerve root block, 47
  sacral nerve root block, 56
iliac vessels, bifurcation of, 90f
iliocostalis muscle, 104
ilium, 12, 13f, 14
infection
  post-caudal epidural block, 33
  post-cervical epidural block, 29
  post-corticosteroid injection, 113
  post-gluteus medius injection, 107
  post-long-term epidural catheter insertion, 36
  post-lumbar epidural block, 20
  post-thoracic epidural block, 24
inferior articular process, 17f
inferior hypogastric plexus, 86
inferior vena cava
  anatomy, 77
  perforation, 76, 81, 84, 88
infraspinatus muscle, 103f
infratemporal bone, 64
infratemporal fossa, 62
injections
  cervical facet joint, 8–11
  epidural, 15–36
  joint, 3–14
  lumbar facet joint, 3–6
  sacro-iliac joint, 12–14
  sacroiliac ligaments, 14
  trigger point, 2
intercostal artery, 38f
intercostal muscle, 38f, 45f
intercostal nerve block, 38–42
  anatomy, 38, 38f
  confirmation of success, 40
  drugs, 38
  equipment, 38
  needle puncture and technique, 38–39, 39f
    right-handed operator, 38–39, 39f–40f
  neurolytic, 40, 41f, 42
  position of patient, 38
  potential problems, 41
  radiofrequency lesioning, 41
  tips, 40–41, 41f
intercostal nerves, 43
intercostal neuralgia, 65
intercostal space, 39–41
intercostal vein, 38f
intercrestal line, 73
  hypogastric plexus block, 87
  lumbar epidural block, 17
  lumbar nerve root block, 47
  sacral nerve root block, 56
intergluteal groove, 91–92
internal carotid artery, 61
internal filum terminale, 125f
internal iliac artery, 86f
internal iliac vein, 86f
internal oblique muscles, 104f
interpleural block, 43–46
  anatomy, 43, 43f
  confirmation of success, 44
  drugs, 43
  equipment, 43
  needle puncture and technique, 43–44, 44f
    right-handed operator, 44, 44f–45f
  position of patient, 43, 43f
  potential problems, 46
  tips, 46, 46f
interpleural space, 43
interspinalis muscle, 104f
interspinous ligament, 16
  in cervical epidural block, 26, 28–29
  in lumbar epidural block, 18–19
  in thoracic epidural block, 22–23
intervertebral disc
  disease, 15
  pain, 15
  perforation, 76, 81, 85, 90
intervertebral foramen, 47, 76
intestines, 77
intra-arterial injection, 10, 68–69, 72
intraneural pressure, raised, 111
intrathecal blockade, 49
intrathecal injection, 10
  in caudal epidural block, 33
  in cervical epidural block, 29
  in lumbar epidural block, 20
  in lumbar nerve root block, 49
  in stellate ganglion block
    C7 approach, 72
    C6 (classic) approach, 68–69
  in thoracic epidural block, 24
intrathecal space, 16
intravascular injection
  in caudal epidural block, 33
  in cervical epidural block, 29
  in lumbar epidural block, 20
  in lumbar nerve root block, 49
  in lumbar sympathetic block, 76
  in sacral nerve root block, 57
  in thoracic epidural block, 24
  in thoracic nerve root block, 54
intravenous injection, 10
intravenous regional sympathetic block
  lower limb, 97–99
    anatomy, 97
    confirmation of success, 98
    drugs, 97
    equipment, 97
    position of patient, 97

    potential problems, 99
    technique, 97–98, 97f–99f
    tips, 98
  upper limb, 94–96
    anatomy, 94
    confirmation of success, 95
    drugs, 94
    equipment, 94
    position of patient, 94
    potential problems, 96
    technique, 94–95, 94f–96f
  tips, 95–96
ipsilateral face, 61
ipsilateral pupil, 62
ischemia, 111

J

joint(s)
  arthropathy, 2
  degeneration, 2
  information, 2
  injections, 3–14
  pain, 2
jugular vein, 68, 72

K

kidneys, 77
  anatomy, 77
  perforation, 76, 81, 85

L

lamina, 22
laryngeal nerve block, recurrent, 69, 72
laryngoscope, 117
lateral epicondyles, 101
latissimus dorsi muscle, 102
lesser occipital nerve, 59f, 60
levator scapulae muscle, 102
levobupivacaine, 43
lidocaine
  caudal epidural block, 31–32
  celiac plexus block
    anterocrural approach, 83
    retrocrural approach, 78–80
  cervical epidural block, 25–29
  cervical facet joint injection, 8–10
  facet nerve injection, 11
  ganglion impar block, 92
  gluteus medius injection, 107
  hypogastric plexus block, 87
  intercostal nerve block, 39–40
  interpleural block, 43
  intravenous regional sympathetic block
    lower limb, 97, 99
    upper limb, 68, 95
  long-term epidural catheter insertion, 34
  lumbar epidural block, 17–19
  lumbar facet joint injection, 4–5
  lumbar nerve root block, 47–48
  lumbar sympathetic block, 74
  occipital nerve block, 60
  piriformis injection, 108
  for resuscitation, 117
  sacral nerve root block, 56–57
  sacro-iliac joint injection, 12–13
  stellate ganglion block
    C7 approach, 70–72
    C6 (classic) approach, 66, 68
  thoracic epidural block, 21–23
  thoracic nerve root block, 52–53
  toxicity, 68, 99
  trigeminal ganglion (Gasserian) block, 62–64
  trigger point injections, 101–102, 105
ligaments
  anococcygeal, 93
  anterior costotransverse, 51f–52f
  costotransverse, 51f–52f, 53
  posterior sacro-iliac, 12f
  sacro-coccygeal, 30f
  sacroiliac, 14
  supraspinous, 16
ligamentum flavum, 16, 125f
  lumbar epidural block, 18–19
  thoracic epidural block, 22–23
lignocaine *see* lidocaine
liver, 77
local anaesthetics, 2
  in lumbar epidural block, 20
  rapid absorption in intercostal nerve block, 41
longissimus muscle, 104
longus colli muscle, 72
loss-of-resistance technique, 22, 29
lumbar epidural block, 16–20
  anatomy, 16, 16f–17f
  confirmation of success, 20
  drugs, 16
  equipment, 16, 17f
  needle puncture and technique, 17–20
    fluoroscopic guided lumbar epidural injection, 19–20, 19f
    midline approach, right-handed operator, 17–19, 18f–19f
  position of patient, 17
  potential problems, 20
  tips, 20, 20f
lumbar epidural steroid injection, 23
lumbar facet joint injections, 3–6
  anatomy, 3–4, 3f
  confirmation of success, 5
  drugs, 4
  equipment, 4
  needle puncture and technique, 4–5, 5f–7f
  position of patient, 4, 4f
  potential problems, 6
  tips, 5
lumbar nerve root block, 47–49
  anatomy, 47, 47f
  confirmation of success, 49
  drugs, 47
  equipment, 47
  needle puncture and technique, 47–48, 48f–50f
  position of patient, 47, 48f
  potential problems, 49
  tips, 49
lumbar nerve roots, 15
lumbar nerves, 47
lumbar plexus, 47
lumbar radiculopathy, 32
lumbar somatic nerves, 73
lumbar spine innervation, 3f
lumbar sympathetic block, 73–76
  anatomy, 73
  confirmation of success, 75
  drugs, 73
  equipment, 73
  needle puncture and technique, 73–75, 73f–76f
  position of patient, 73, 73f
  potential problems, 76
  tips, 75
lumbar sympathetic chain, 73
lumbo-sacral radiculopathy, 15
lumbo-sacral spine anatomy, 125
lungs, 51
lymphedema, 85

M

Magill's forceps, 117
magnetic resonance imaging (MRI), 37
mandibular nerve, 61–62
masseter muscle, 62
mastication muscles, 61–62
mastoid process, 59–60, 59f
maxillary nerve, 61
mechanical nerve root compression, 37
Meckel's cave, 61
medius scalenus muscle, 70f
meningitis, aseptic *see* aseptic meningitis
menstrual cycle irregularity, 113
mesenteric artery, 77
methylprednisolone, 113
midazolam, 117
middle cervical ganglion, 70f
miosis of pupil, 68, 72
MRI (magnetic resonance imaging), 37
multifidus muscle, 104, 104f
muscle contraction, involuntary, 101
muscle injections, 101–110
muscles
  erector spinae, 104
  external oblique, 104f
  gemelli, 106
  gluteus, 104
  iliocostalis, 104
  infraspinatus, 103f
  intercostal, 38f, 45f
  internal oblique, 104f
  interspinalis, 104f
  latissimus dorsi, 102
  levator scapulae, 102
  longissimus, 104
  longus colli, 72
  masseter, 62
  mastication, 61–62
  medius scalenus, 70f
  multifidus, 104, 104f
  paravertebral, 47
  piriformis, 106, 108
  psoas, 47, 51, 73, 78–80, 104f
  quadratus femoris, 106
  quadratus lumborum, 104f
  rhomboid, 102
  rotatores, 104
  sacrospinalis, 12f
  semispinalis, 104
  spinalis, 104
  splenius capitis, 102
  sternocleidomastoid, 67, 71
  supraspinatus, 103f
  teres major, 103f
  teres minor, 103f
  transversospinal, 104
  trapezius, 102, 103f
muscle spasm, 1
muscle wasting, 113

myelography, 37
myofascial pain syndrome, 2, 101, 108
myopathy, 113
myotomes, 123

N

nasopharyngeal airway, 117
neck, 112
nerve fibers
  parasympathetic, 77, 86
  pre- and postganglionic, 77
  sympathetic, 77, 86
nerve roots, mechanical compression, 37
nerve(s)
  injured, 1
  regeneration, 1
nerve sheath, 41–42, 49, 53
neural foramina, 78
neuritis in thoracic nerve root block, 54
neurolysis, 75
neurolytic agents
  in autonomic blockade, 76, 81, 84–85, 88–90, 93
  in somatic nerve blockade, 40, 61, 64
  suggested, 115
neurolytic blocks, 40, 64–65, 76, 81, 84, 90
neuroma formation, 1
neuropraxia, 96, 99
neurotransmitters, 94, 97
neurovascular bundle, 40–41, 44, 45f
norepinephrine, 68, 94, 97, 99
nose blockage, unilateral, 68, 72
nucleus pulposis, 37

O

occipital artery, 60
occipital nerve, 59
occipital nerve block, 59–60
  anatomy, 59, 59f
  confirmation of success, 60
  drugs, 59
  equipment, 59
  needle puncture and technique, 59–60, 59f–60f
  position of patient, 59
  potential problems, 60
  tips, 60
oculomotor nerve, 64
ophthalmic nerve, 61
oropharyngeal airway, 117
orthostatic hypotension, 81, 84, 90
osteoporosis, 113
oxygen bag and masks, 117
oxygen source, 117

P

pacemaker, cardiac, 112
pain
  cervical epidural block, 29
  communication of, 2
  definition, 1
  joint, 2
  management of, 2
  mechanisms, 1–2
  myofascial, 2
  neuropathic, 1–2
  perception, 2
  psychologic factors, 2
  radicular, 2, 15, 33
  referred, 1
  somatic, 1–2
  visceral, 1–2, 77
pancreas
  anatomy, 77
  cancer, 2, 65
paralysis, transient motor *see* transient motor paralysis
paraparesis, 10
paraplegia, 10
  post-celiac plexus block, 81, 85
  post-hypogastric plexus block, 90
parasympathetic nerve fibers, 77, 86
paravertebral injection, 51
paravertebral muscles, 47
paravertebral space, 53
paravertebral sympathetic trunk, 78f, 84f
paresthesia
  in lumbar nerve root block, 48
  in sacral nerve root block, 57
  in stellate ganglion block
    C7 approach, 72
    C6 (classic) approach, 68
  in thoracic nerve root block, 52
  in trigeminal ganglion (Gasserian) block, 62
parietal pleura, 43
pelvic cancer, 65
pelvic organs, 77
pericardial cavity, 45f
perineum, 91
periosteal injection, 93
peripheral nerve changes, 1
peripheral sympathetic blockade, 94f
peripheral vascular disease, 65
peripheral visceral afferents, 1
petrous temporal bone, 61
phenol, 115
  celiac plexus block
    anterocrural approach, 83
    retrocrural approach, 80
  ganglion impar block, 93
  hypogastric plexus block, 87
phrenic nerve block, post-stellate ganglion block
  C7 approach, 72
  C6 (classic) approach, 69
physiotherapy
  post-intravenous regional sympathetic block, 96, 98
  and trigger point injections, 103, 105
pia mater, 125f
piriformis injection, 108–110
  anatomy, 108, 108f
  confirmation of success, 108
  drugs, 108
  equipment, 108
  needle puncture and technique, 108, 109f–110f
  position of patient, 108, 108f
  potential problems, 110
  tips, 108–110
piriformis muscle, 106, 108
pleura, 43, 51, 66
  avoidance in thoracic nerve root block, 52
pleural cavity, 45f
pneumothorax
  in celiac plexus block, 81, 85
  in intercostal nerve block, 39–41
  in interpleural block, 44, 46
  in stellate ganglion block
    C7 approach, 70–72
    C6 (classic) approach, 69
  in thoracic nerve root block, 51, 53–54
  in trigger point injections, 103, 105
posterior sacral foramen, 55f, 57
posterior sacro-iliac ligament, 12f
posterior superior iliac spines, 31, 55
  gluteus medius injection, 106
  piriformis injection, 108
post-herpetic neuralgia, 65
postural hypotension, 76
preganglionic sympathetic efferents, 77
prevertebral fascia, 73
propofol, 64
prostate, 86
psoas muscle, 47, 51, 73, 78–80, 104f
psychologic upset, 113
pterygoid process, 62
ptosis of eyelid, 68, 72

Q

quadratus femoris muscle, 106
quadratus lumborum muscle, 104f

R

radiculopathy
  discogenic, 37
  lumbar, 32
  lumbo-sacral, 15
  sacral, 32
radiofrequency lesioning of the intercostal nerve, 41
radiograph, chest
  intercostal nerve block, 39
  interpleural block, 44
rami
  cervical posterior primary, 8
  dorsal, medial branches, 3–4
  grey, 38, 47
  posterior primary, cervical, 8
  white, 38, 47
rectum, 77
  distal, 91
  perforation, 93
recurrent laryngeal nerve block, stellate ganglion block
  C7 approach, 72
  C6 (classic) approach, 69
resuscitation, recommended drugs and equipment, 117
retrocrural spread, 77f, 82f
retrograde cannulation, intravenous regional sympathetic block
  lower limb, 98
  upper limb, 95
retroperitoneal compartment, 82
retroperitoneal space, 86, 92f
retroperitoneum, 93
rhabdomyolysis, 76, 88–90
rhomboid muscles, 102
ribs
  anatomy, 51
  palpation, 38–39, 43–44
  twelfth, 73, 83
rotatores muscle, 104

S

sacral canal, 55
sacral cornua, 31–32

sacral epidural space, 30
sacral foramen, 55–57
sacral hiatus, 30–32, 55
sacral nerve root block, 55–57
  anatomy, 55, 55f
  confirmation of success, 57
  drugs, 55
  equipment, 55
  needle puncture and technique, 55–57, 56f–58f
  position of patient, 55, 56f
  potential problems, 57
  tips, 57
sacral nerve roots, 15
sacral nerves, 55
sacral promontory, 86
sacral radiculopathy, 32
sacrococcygeal junction, 92
sacrococcygeal ligament, 30f
sacrococcygeal membrane, 30–32, 55
sacrococcygeal vertebral column, 93
sacro-iliac joint injection, 12–14
  anatomy, 12, 12f
  confirmation of success, 14
  drugs, 12
  equipment, 12
  needle puncture and technique, 12–13, 12f–13f
  position of patient, 12, 12f
  potential problems, 14
  tips, 14
sacroiliac ligaments injection, 14
sacrospinalis muscle, 12f
sacrum, 30, 55, 125f
saline
  in caudal epidural block, 31
  in cervical epidural block, 25–26
  in interpleural block, 46
  in intravenous regional sympathetic block
    lower limb, 97
    upper limb, 95
  in long-term epidural catheter insertion, 34
  in lumbar epidural block, 17–18, 20
  in thoracic epidural block, 23
scapula
  inferior angle of, 52
  root of the spine of, 52
sciatic nerve, 108
sciatic nerve block, 107
sciatic notch, 107
sedation
  in autonomic blockade, 76, 78, 81–82, 85, 93
  in epidural injections, 24, 28–29
  in joint injections, 13
  in somatic nerve blockade, 38, 42, 62
segmental arteries spasm, 81, 85, 90
seizures, 96
semispinalis muscle, 104
sensory neurons, 1
septic discitis, 76
sickle cell anemia, 96, 99
sixth cervical anterior tubercle, 66–68
skin
  depigmentation, 113
  flushing, 113
  temperature, 68, 72, 75
somatic nerve blockade, 37–64
  in celiac plexus block, 81, 84–85
  in ganglion impar block, 93
  in hypogastric plexus block, 87–90
  in lumbar sympathetic block, 76
somatic nerves, 1
  lumbar, 73
somatic nociceptive afferents, 1
somatic nociceptor fibers, 1
sphenoid bone, 62
spinal anaesthesia, 10
spinal block, total, 60
spinal cord, 16, 125f
  injury
    cervical epidural block, 29
    thoracic epidural block, 24
  segmental myotomes, 123
spinalis muscle, 104
spinal nerve roots inflammation, 15
spinal nerves, 3–4, 3f
spinothalamic pathways, 1
spinous processes
  cervical, 25
  lumbar, 16–17, 47, 56, 73, 87
  thoracic, 21–22, 25, 52
splanchnic nerves, 77, 86
spleen, 77
splenius capitis muscle, 102
spontaneous neural inputs, 1
stellate ganglion, 66, 70f
stellate ganglion block
  bilateral, 69
  C7 approach, 70–72
    anatomy, 70, 70f
    confirmation of success, 72
    drugs, 70
    equipment, 70
    needle puncture and technique, 70–72, 70f–71f
    position of patient, 70
    potential problems, 72
    tips, 72
  C6 (classic) approach, 66–69
    anatomy, 66, 66f
    confirmation of success, 68
    drugs, 66
    equipment, 66, 66f
    needle puncture and technique, 66–68
      right-handed operator, 66–68, 67f–68f
    position of patient, 66
    potential problems, 68–69
    tips, 68, 69f–70f
sternoclavicular junction, 71
sternocleidomastoid muscle, 67, 71
subarachnoid block, 76
subarachnoid space, 19–20, 25f, 32f
subclavian artery, 70f
subcutaneous tissue atrophy, 113
subperiosteal injection, 33, 33f
succinylcholine, 117
superior articular process, 17f
superior gluteal nerve, 12
superior hypogastric plexus, 86, 86f, 90f
superior mesenteric artery, 77f–78f, 84f
superior mesenteric ganglion, 77f
superior nuchal line, 59–60
superior stellate ganglion, 70f
suprarenal glands, 77
supraspinatus muscle, 103f
supraspinous ligament, 16
sympathetic afferents, 1, 91
sympathetic blockade, 51
  with lumbar nerve root block, 49
  in thoracic nerve root block, 54
sympathetic chain, 43
sympathetic ganglia, 51f, 91
sympathetic lumbar chain, 47, 51
sympathetic nerve endings, 94, 97
sympathetic nerve fibers, 77, 86
sympatholytic agents, 94, 97

T

temperature, skin, 68, 72, 75
temporal lobe, 61
tender points, 101
tendon, rupture of injected, 113
TENS *see* transcutaneous electrical stimulation (TENS)
teres major muscle, 103f
teres minor muscle, 103f
thermocoagulation, 64
thiopental (thiopentone), 117
thoracic disc pain, 15
thoracic duct damage, 81, 85
thoracic epidural block, 21–24
  anatomy, 21, 21f
  confirmation of success, 23
  drugs, 21
  equipment, 21
  needle puncture and technique, 21, 21f–22f
  paramedian approach, right-handed operator, 22–23, 23f
  position of patient, 21
  potential problems, 24
  tips, 23, 24f
thoracic ganglia, 66
thoracic nerve root block, 51–54
  anatomy, 51, 51f
  confirmation of success, 53
  drugs, 51
  equipment, 51
  needle puncture and technique, 51–53, 52f–53f
  position of patient, 51, 52f
  potential problems, 53–54
  tips, 53
thoracic sympathetic chain, 52f, 77
thoracostomy drainage tubes, 46
thyroid cartilage, 66–67, 71
total spinal block, 60
tourniquet, 68, 95, 97–99
transcutaneous electrical stimulation (TENS), 111–112
  burst stimulation, 112
  continuous stimulation, 111
  contraindications, 112
  control settings, 111–112, 111f–112f
  low-frequency high-intensity stimulation, 112
  modulated settings, 112
  trial period, 111
transient motor paralysis
  post-celiac plexus block, 81, 85
  post-hypogastric plexus block, 90
transverse processes, 17f, 52
transversospinal muscles, 104
trapezius muscle, 102, 103f
triamcinolone, 113
  in caudal epidural block, 31–32
  in cervical epidural block, 27, 29
  in cervical facet joint injection, 9
  in epidural injection, 15
  in lumbar epidural block, 18, 20
  in lumbar facet joint injection, 5
  in sacro-iliac joint injection, 13
  in thoracic epidural block, 21, 23
trigeminal ganglion, 61

trigeminal ganglion (Gasserian) block, 61–64
  anatomy, 61, 61f
  confirmation of success, 64
  drugs, 61
  equipment, 61
  needle puncture and technique, 62–64, 62f–63f
  position of patient, 61
  potential problems, 64
  tips, 64
trigeminal nerve, 62, 64
trigeminal neuralgia, 65
trigeminal nucleus, 1
trigger point injections, 2, 101
  back, 104–105
    anatomy, 104, 104f
    confirmation of success, 105
    drugs, 104
    equipment, 104
    needle puncture and technique, 105, 105f
    position of patient, 104, 104f
    potential problems, 105
    tips, 105
  neck and thorax, 102–103
    anatomy, 102, 102f
    confirmation of success, 102
    drugs, 102
    equipment, 102
    needle puncture and technique, 102, 102f–103f
    position of patient, 102
    potential problems, 103
    tips, 103
  number of, 101
trigger points, 2, 101
  palpation, 101
trochlear nerve, 64
twitch, local, 102f

U

ultrasonography
  in caudal epidural block, 31
  in cervical epidural block, 25, 28
  in hypogastric plexus block, 87
  in intercostal nerve block, 40
  in interpleural block, 46
  in long-term epidural catheter insertion, 36
  in lumbar epidural block, 20, 20f
  in lumbar facet joint injection, 4–5, 5f
  in lumbar nerve root block, 48
  in piriformis injection, 108
  in sacral nerve root block, 57
  in sacro-iliac joint injection, 13
  in stellate ganglion block
    C7 approach, 72
    C6 (classic) approach, 68
  in thoracic epidural block, 23, 24f
  in thoracic nerve root block, 52
ureters, perforation, 76, 81, 85
urethra, distal, 91
uterus, 86

V

vagina, 86, 91
vagus nerve, 77
vasovagal response, 103, 105
vasovagal syncope, 29
veins
  azygos, 52f
  external iliac, 86f
  intercostal, 38f
  internal iliac, 86f
  jugular, 68, 72
Velband, 95, 97
vertebral arteries, 66, 70–71, 70f
vertebra prominens, 18f, 25
visceral afferents, 1
visceral organs, 1
visceral pleura, 43
vulva, 91

W

white rami, 38, 47
wide dynamic range neurons, 1

Z

zygapophyseal joints *see* facet joints
zygomatic arch, 62

CONVERSION FACTORS AND UNIT SYMBOLS

SI UNITS (ADOPTED 1960)

A new system of metric measurement, the International System of Units (abbreviated SI), is being implemented throughout the world. This system is a modernized version of the MKSA (meter, kilogram, second, ampere) system, and its details are published and controlled by an international treaty organization (The International Bureau of Weights and Measures).

SI units are divided into three classes:

Base Units

length	meter[†] (m)
mass[‡]	kilogram (kg)
time	second (s)
electric current	ampere (A)
thermodynamic temperature§	kelvin (K)
amount of substance	mole (mol)
luminous intensity	candela (cd)

Supplementary Units

plane angle	radian (rad)
solid angle	steradian (sr)

Derived Units and Other Acceptable Units

These units are formed by combining base units, supplementary units, and other derived units. Those derived units having special names and symbols are marked with an asterisk (*) in the list below:

Quantity	*Unit*	*Symbol*	*Acceptable equivalent*
*absorbed dose	gray	Gy	J/kg
acceleration	meter per second squared	m/s^2	
*activity (of ionizing radiation source)	becquerel	Bq	1/s
area	square kilometer	km^2	
	square hectometer	hm^2	ha (hectare)
	square meter	m^2	

[†] The spellings “metre” and “litre” are preferred by American Society for Testing and Materials (ASTM); however, “−er” will be used in the Encyclopedia.

[‡] “Weight” is the commonly used term for “mass.”

§Wide use is made of “Celsius temperature” (t) defined $t = T - T_0$ where T is the thermodynamic temperature, expressed in kelvins, and $T_0 = 273.15\,\mathrm{K}$ by definition. A temperature interval may be expressed in degrees Celsius as well as in kelvins.

Quantity	*Unit*	*Symbol*	*Acceptable equivalent*
*capacitance	farad	F	C/V
concentration (of amount of substance)	mole per cubic meter	mol/m^3	
*conductance	siemens	S	A/V
current density	ampere per square meter	A/m^2	
density, mass density	kilogram per cubic meter	kg/m^3	g/L; mg/cm^3
dipole moment (quantity)	coulomb meter	C·m	
*electric charge, quantity of electricity	coulomb	C	A·s
electric charge density	coulomb per cubic meter	C/m^3	
electric field strength	volt per meter	V/m	
electric flux density	coulomb per square meter	C/m^2	
*electric potential, potential difference, electromotive force	volt	V	W/A
*electric resistance	ohm	Ω	V/A
*energy, work, quantity of heat	megajoule	MJ	
	kilojoule	kJ	
	joule	J	N·m
	electron volt[†]	eV[†]	
	kilowatt hour[†]	kW·h[†]	
energy density	joule per cubic meter	J/m^3	
*force	kilonewton	kN	
	newton	N	kg·m/s^2
*frequency	megahertz	MHz	
	hertz	Hz	1/s
heat capacity, entropy	joule per kelvin	J/K	
heat capacity (specific), specific entropy	joule per kilogram kelvin	J/(kg·K)	
heat transfer coefficient	watt per square meter kelvin	W/(m^2·K)	
*illuminance	lux	lx	lm/m^2
*inductance	henry	H	Wb/A
linear density	kilogram per meter	kg/m	
luminance	candela per square meter	cd/m^2	
*luminous flux	lumen	lm	cd·sr
magnetic field strength	ampere per meter	A/m	
*magnetic flux	weber	Wb	V·s
*magnetic flux density	tesla	T	Wb/m^2
molar energy	joule per mole	J/mol	
molar entropy, molar heat capacity	joule per mole kelvin	J/(mol·K)	
moment of force, torque	newton meter	N·m	
momentum	kilogram meter per second	kg·m/s	
permeability	henry per meter	H/m	
permittivity	farad per meter	F/m	
*power, heat flow rate, radiant flux	kilowatt	kW	
	watt	W	J/s
power density, heat flux density, irradiance	watt per square meter	W/m^2	
*pressure, stress	megapascal	MPa	
	kilopascal	kPa	
	pascal	Pa	N/m^2
sound level	decibel	dB	
specific energy	joule per kilogram	J/kg	
specific volume	cubic meter per kilogram	m^3/kg	
surface tension	newton per meter	N/m	
thermal conductivity	watt per meter kelvin	W/(m·K)	
velocity	meter per second	m/s	
	kilometer per hour	km/h	
viscosity, dynamic	pascal second	Pa·s	
	millipascal second	mPa·s	

[†] This non-SI unit is recognized as having to be retained because of practical importance or use in specialized fields.

Quantity	*Unit*	*Symbol*	*Acceptable equivalent*
viscosity, kinematic	square meter per second	m^2/s	
	square millimeter per second	mm^2/s	
	cubic meter	m^3	
	cubic decimeter	dm^3	L(liter)
	cubic centimeter	cm^3	mL
wave number	1 per meter	m^{-1}	
	1 per centimeter	cm^{-1}	

In addition, there are 16 prefixes used to indicate order of magnitude, as follows:

Multiplication factor	*Prefix*	*Symbol*	*Note*
10^{18}	exa	E	
10^{15}	peta	P	
10^{12}	tera	T	
10^9	giga	G	
10^8	mega	M	
10^3	kilo	k	
10^2	hecto	h[a]	[a] Although hecto, deka, deci, and centi are SI prefixes, their use should be avoided except for SI unit-multiples for area and volume and nontechnical use of centimeter, as for body and clothing measurement.
10	deka	da[a]	
10^{-1}	deci	d[a]	
10^{-2}	centi	c[a]	
10^{-3}	milli	m	
10^{-6}	micro	μ	
10^{-9}	nano	n	
10^{-12}	pico	p	
10^{-15}	femto	f	
10^{-18}	atto	a	

For a complete description of SI and its use the reader is referred to ASTM E 380.

CONVERSION FACTORS TO SI UNITS

A representative list of conversion factors from non-SI to SI units is presented herewith. Factors are given to four significant figures. Exact relationships are followed by a dagger (†). A more complete list is given in ASTM E 380-76 and ANSI Z210. 1-1976.

To convert from	*To*	*Multiply by*
acre	square meter (m^2)	4.047×10^3
angstrom	meter (m)	$1.0 \times 10^{-10\dagger}$
are	square meter (m^2)	$1.0 \times 10^{2\dagger}$
astronomical unit	meter (m)	1.496×10^{11}
atmosphere	pascal (Pa)	1.013×10^5
bar	pascal (Pa)	$1.0 \times 10^{5\dagger}$
barrel (42 U.S. liquid gallons)	cubic meter (m^3)	0.1590
Btu (International Table)	joule (J)	1.055×10^3
Btu (mean)	joule (J)	1.056×10^3
Bt (thermochemical)	joule (J)	1.054×10^3
bushel	cubic meter (m^3)	3.524×10^{-2}
calorie (International Table)	joule (J)	4.187
calorie (mean)	joule (J)	4.190
calorie (thermochemical)	joule (J)	$4.184^\dagger$
centimeters of water (39.2 °F)	pascal (Pa)	98.07
centipoise	pascal second (Pa·s)	$1.0 \times 10^{-3\dagger}$
centistokes	square millimeter per second (mm^2/s)	$1.0^\dagger$

To convert from	*To*	*Multiply by*
cfm (cubic foot per minute)	cubic meter per second (m^3/s)	4.72×10^{-4}
cubic inch	cubic meter (m^3)	1.639×10^{-4}
cubic foot	cubic meter (m^3)	2.832×10^{-2}
cubic yard	cubic meter (m^3)	0.7646
curie	becquerel (Bq)	$3.70 \times 10^{10\dagger}$
debye	coulomb-meter (C·m)	3.336×10^{-30}
degree (angle)	radian (rad)	1.745×10^{-2}
denier (international)	kilogram per meter (kg/m)	1.111×10^{-7}
	tex	0.1111
dram (apothecaries')	kilogram (kg)	3.888×10^{-3}
dram (avoirdupois)	kilogram (kg)	1.772×10^{-3}
dram (U.S. fluid)	cubic meter (m^3)	3.697×10^{-6}
dyne	newton(N)	$1.0 \times 10^{-6\dagger}$
dyne/cm	newton per meter (N/m)	$1.00 \times 10^{-3\dagger}$
electron volt	joule (J)	1.602×10^{-19}
erg	joule (J)	$1.0 \times 10^{-7\dagger}$
fathom	meter (m)	1.829
fluid ounce (U.S.)	cubic meter (m^3)	2.957×10^{-5}
foot	meter (m)	$0.3048^{\dagger}$
foot-pound force	joule (J)	1.356
foot-pound force	newton meter (N·m)	1.356
foot-pound force per second	watt(W)	1.356
footcandle	lux (lx)	10.76
furlong	meter (m)	2.012×10^{2}
gal	meter per second squared (m/s^2)	$1.0 \times 10^{-2\dagger}$
gallon (U.S. dry)	cubic meter (m^3)	4.405×10^{-3}
gallon (U.S. liquid)	cubic meter (m^3)	3.785×10^{-3}
gilbert	ampere (A)	0.7958
gill (U.S.)	cubic meter (m^3)	1.183×10^{-4}
grad	radian	1.571×10^{-2}
grain	kilogram (kg)	6.480×10^{-5}
gram force per denier	newton per tex (N/tex)	8.826×10^{-2}
hectare	square meter (m^2)	$1.0 \times 10^{4\dagger}$
horsepower (550 ft·lbf/s)	watt(W)	7.457×10^{2}
horsepower (boiler)	watt(W)	9.810×10^{3}
horsepower (electric)	watt(W)	$7.46 \times 10^{2\dagger}$
hundredweight (long)	kilogram (kg)	50.80
hundredweight (short)	kilogram (kg)	45.36
inch	meter (m)	$2.54 \times 10^{-2\dagger}$
inch of mercury (32 °F)	pascal (Pa)	3.386×10^{3}
inch of water (39.2 °F)	pascal (Pa)	2.491×10^{2}
kilogram force	newton (N)	9.807
kilopond	newton (N)	9.807
kilopond-meter	newton-meter (N·m)	9.807
kilopond-meter per second	watt (W)	9.807
kilopond-meter per min	watt(W)	0.1635
kilowatt hour	megajoule (MJ)	$3.6^{\dagger}$
kip	newton (N)	4.448×10^{2}
knot international	meter per second (m/s)	0.5144
lambert	candela per square meter (cd/m^2)	3.183×10^{3}
league (British nautical)	meter (m)	5.559×10^{2}
league (statute)	meter (m)	4.828×10^{3}
light year	meter (m)	9.461×10^{15}
liter (for fluids only)	cubic meter (m^3)	$1.0 \times 10^{-3\dagger}$
maxwell	weber (Wb)	$1.0 \times 10^{-8\dagger}$
micron	meter (m)	$1.0 \times 10^{-6\dagger}$
mil	meter (m)	$2.54 \times 10^{-5\dagger}$
mile (U.S. nautical)	meter (m)	$1.852 \times 10^{3\dagger}$
mile (statute)	meter (m)	1.609×10^{3}
mile per hour	meter per second (m/s)	0.4470

To convert from	*To*	*Multiply by*
millibar	pascal (Pa)	1.0×10^{2}
millimeter of mercury (0 °C)	pascal (Pa)	$1.333 \times 10^{2\dagger}$
millimeter of water (39.2 °F)	pascal (Pa)	9.807
minute (angular)	radian	2.909×10^{-4}
myriagram	kilogram (kg)	10
myriameter	kilometer (km)	10
oersted	ampere per meter (A/m)	79.58
ounce (avoirdupois)	kilogram (kg)	2.835×10^{-2}
ounce (troy)	kilogram (kg)	3.110×10^{-2}
ounce (U.S. fluid)	cubic meter (m^3)	2.957×10^{-5}
ounce-force	newton (N)	0.2780
peck (U.S.)	cubic meter (m^3)	8.810×10^{-3}
pennyweight	kilogram (kg)	1.555×10^{-3}
pint (U.S. dry)	cubic meter (m^3)	5.506×10^{-4}
pint (U.S. liquid)	cubic meter (m^3)	4.732×10^{-4}
poise (absolute viscosity)	pascal second (Pa·s)	$0.10^{\dagger}$
pound (avoirdupois)	kilogram (kg)	0.4536
pound (troy)	kilogram (kg)	0.3732
poundal	newton (N)	0.1383
pound-force	newton (N)	4.448
pound per square inch (psi)	pascal (Pa)	6.895×10^{3}
quart (U.S. dry)	cubic meter (m^3)	1.101×10^{-3}
quart (U.S. liquid)	cubic meter (m^3)	9.464×10^{-4}
quintal	kilogram (kg)	$1.0 \times 10^{2\dagger}$
rad	gray (Gy)	$1.0 \times 10^{-2\dagger}$
rod	meter (m)	5.029
roentgen	coulomb per kilogram (C/kg)	2.58×10^{-4}
second (angle)	radian (rad)	4.848×10^{-6}
section	square meter (m^2)	2.590×10^{6}
slug	kilogram (kg)	14.59
spherical candle power	lumen (lm)	12.57
square inch	square meter (m^2)	6.452×10^{-4}
square foot	square meter (m^2)	9.290×10^{-2}
square mile	square meter (m^2)	2.590×10^{6}
square yard	square meter (m^2)	0.8361
store	cubic meter (m^3)	$1.0^{\dagger}$
stokes (kinematic viscosity)	square meter per second (m^2/s)	$1.0 \times 10^{-4\dagger}$
tex	kilogram per meter (kg/m)	$1.0 \times 10^{-6\dagger}$
ton (long, 2240 pounds)	kilogram (kg)	1.016×10^{3}
ton (metric)	kilogram (kg)	$1.0 \times 10^{3\dagger}$
ton (short, 2000 pounds)	kilogram (kg)	9.072×10^{2}
torr	pascal (Pa)	1.333×10^{2}
unit pole	weber (Wb)	1.257×10^{-7}
yard	meter (m)	$0.9144^{\dagger}$

A

ABLATION. See Tissue ablation.

ABSORBABLE BIOMATERIALS. See Biomaterials, absorbable.

ACRYLIC BONE CEMENT. See Bone cement, acrylic.

ACTINOTHERAPY. See Ultraviolet radiation in medicine.

ADOPTIVE IMMUNOTHERAPY. See Immunotherapy.

AFFINITY CHROMATOGRAPHY. See Chromatography.

ALLOYS, SHAPE MEMORY

Young Kon Kim
Inje University
Kimhae City
Korea

INTRODUCTION

An alloy is defined as a substance with metallic properties that is composed of two or more chemical elements of which at least one is an elemental metal (1). The internal structure of most alloys starts to change only when it is no longer stable. When external influences, such as pressure and temperature, are varied, it will tend to transform spontaneously into a mixture of phases, the structures, compositions, and morphologies of which differ from the initial one. Such microstructural changes are known as phase transformation and may involve considerable atomic rearrangement and compositional change (2,3).

Shape memory alloys (SMAs) exhibit a unique mechanical "memory", or restoration force characteristic, when heated above a certain phase-transformation temperature range (TTR), after having been deformed below the TTR. This thermally activated shape recovering behavior is called the shape memory effect (SME) (3–5). This particular effect is closely related to a martensitic phase transformation accompanied by subatomic shear deformation resulting from the diffusionless, cooperative movement of atoms (6,7). The name martensite was originally used to describe the very fine, hard microstructure found in quenched steels (8). The meaning of this word has been extended gradually to describe the microstructure of nonferrous alloys that have similar characteristics.

SMAs have two stable phases: a high temperature stable phase, called the parent or austenite phase and a low temperature stable martensite phase. Martensite phases can be induced by cooling or stressing and are called thermally induced martensite (TIM) or stress induced martensite (SIM), respectively (8). The TIM forms and grows continuously as the temperature is lowered, and it shrinks and vanishes as the temperature is raised. The SIM is generated continuously with increasing applied stress on the alloy. On removing the applied stress, SIM disappears gradually at a constant temperature. If the temperature is sufficiently low when stressing, however, the SIM cannot return to its initial structure when the stress is removed. When the temperature is increased above the TTR, the residual SIM restores the original structure, resulting in shape recovery (9). Surprisingly, this process can be reliably repeated millions of times, provided that the strain limits are not breached. If dislocations or slips intervene in this process, the shape memory becomes imperfect. When the applied stress on a SMA is too great, irreversible slip occurs, and the SMA cannot recover its original shape even after heating above TTR (10). However, it can remember this hot parent pattern. In the next cooling cycle, the SMA changes slightly and remembers the cool-martensite pattern. A SMA trained with this repeated cyclic treatment is called a two-way SMA (9). A schematic explanation of the SME related to the two-dimensional (2D) crystal structure (11) is shown in Fig. 1. When a SMA is cooled below its TTR, the parent phase begins to form TIM without an external shape change. This TIM can be changed into SIM easily by mechanical deformation below the TTR. When the deformed SMA is heated above its TTR, however, it cannot hold the deformed shape anymore, and the SMA returns to its original shape, resulting in a reverse martensitic phase transformation.

A SMA also shows rubber-like behavior at temperatures above its TTR. When a SMA is deformed isothermally above its TTR, only SIM is produced, until plastic deformation occurs. Then, the SIM disappears immediately after removing the applied load, resulting in a much greater amount of recovering strain, in excess of the elastic limit, compared to the conventional elastic strain of a metal. This rubber-like behavior at a constant temperature above TTR is called superelasticity (12). A schematic explanation of superelasticity is shown in Fig. 2.

These contrasting behaviors of superelasticity and SME are a function of the testing temperature. If a SMA is tested below its TTR, it shows SME, while a SMA that is deformed above its TTR shows superelasticity.

It is convenient to subdivide the superelastic behavior into two categories, "superelasticity" and "rubber-like behavior", depending on the nature of the driving forces and mechanism involved. If it is triggered by SIM formation and subsequent reversion, the terminology superelasticity is used. By contrast, rubber-like behavior does not involve phase transformation, but involves deformation of the martensite itself. It is closely related to the reversible movement of deformed twin boundaries or martensite boundaries (10).

An example of SME in a shape-memory suture needle (13) is shown in Fig. 3. Figure 3a shows a curved needle with the shape preset by a heat-treatment process. When the shape-memory needle is cooled below its TTR, it is readily amenable to a change in shape with forceps (b). On heating it above TTR, thermal energy causes the needle to recover its original curved shape (c).



Figure 1. Schematic illustration of the shape memory effect. The parent phase is cooled below TTR to form a twinned (self-accommodated) martensite without an external shape change. Deformed martensite is produced with twin boundary movement and a change of shape by deformation below the TTR. Heating above the TTR results in reverse transformation and leads to shape recovery.



Figure 2. Schematic illustration of the superelasticity of a SMA above TTR. During the loading process, the applied load changes the parent phase into stress-induced martensite, which disappears instantly on unloading.



Figure 3. Shape-memory effect in a SMA suture needle. (a) Cooling the SMA suture needle below its TTR, (b) straightening the SMA suture needle below its TTR, (c) recovering the original shape of the SMA suture needle above its TTR.

HISTORY OF SHAPE MEMORY ALLOYS

The first observed shape memory phenomenon was pseudoelasticity. In 1932, Oelander observed it in a Au–Cd alloy and called it "rubber-like" behavior (14). Owing to the great amount of reversible strain, this effect is also called "superelasticity". The SME was discovered in 1938 by Greninger and Mooradian (15), while observing the formation and disappearance of martensite with falling and rising temperature in a brass (Cu–Zn alloy) sample. The maximum amount of reversible strain was observed in a Cu–Al–Ni single crystal with a recoverable elastic strain of 24% (16). In 1949, Kurdjumov and Khandros (17), provided a theoretical explanation of the basic mechanism of SME, the thermoelastic behavior of the martensite phase in Au–Cd alloy. Numerous alloy systems have been found to exhibit shape memory behavior. However, the great breakthrough came in 1963, when Buehler et al. (4) at the U.S. Naval Ordnance Laboratory discovered the SME in an equiatomic alloy of Ni–Ti, since then popularized under the name nitinol (Nickel–Titanium Naval Ordnance Laboratory). Partial listings of SMAs include the alloy systems: Ag–Cd, Au–Cd, Au–Cu, Cu–Zn, Cu–Zn–X (X = Si, Sn, Al, Ga), Cu–Al–Ni, Cu–Au–Zn, Cu–Sn, Ni–Al, Ni–Nb, Ni–Ti, Ni–Ti–Cu, Ti–Pd–Ni, In–Tl, In–Cd, Mn–Cd, Fe–Ni, Fe–Mn, Fe–Pt, Fe–Pd, and Fe–Ni–Co–Ti (9). It took several years to understand the microscopic, crystallographic, and thermodynamic properties of these extraordinary metals (18–20). The aeronautical, mechanical, electrical, biomedical, and biological engineering communities, as well as the health professions, are making use of shape memory alloys for a wide range of applications (9). Several commercial applications of Ni–Ti and Cu–Zn–Al SMAs have been developed, such as tube-fitting systems, self-erectable structures, clamps, thermostatic devices, and biomedical applications (5,21–23).

Andreasen suggested the first clinical application of Ni–Ti SMA in 1971. He suggested that nitinol wire was useful for orthodontics by reason of its superelasticity and good corrosion resistance (24). Since then, Ni–Ti alloys have been used in a broad and continually expanding array of biomedical applications, including various prostheses and disposables used in vascular and orthopedic surgery. Medical interventions have themselves been driven toward minimally invasive procedures by the creation of new medical devices, such as guide wires, cardiovascular stents, filters, embolic coils, and endoscopic surgery devices. The Ni–Ti SMA stent was first introduced in 1983 when Dotter (25) and Cragg (26) simultaneously published the results of their experimental studies. However, their studies were unsuccessful because of the unstable introduction system and the intimal hyperplasia in the stent-implanted region (27). In 1990, Rauber et al. renewed the effort to use a Ni–Ti alloy as a stent, significantly reducing intimal hyperplasia by using a transcatheter insertion method (28). In 1992, Josef Rabkin reported successful results in the treatment of obstructions in vascular and nonvascular systems in 268 patients (29). In 1989, Kikuchi reported that a guidewire constructed from kink-resistant titanium–nickel alloy was helpful for angiography and interventional procedures (30). Guidewires are used for needles, endoscopes, or catheters, to gain access to a desired location within the human body. In 1989, the U.S. Food and Drug Administration approved the use of a Mitek anchor constructed of nitinol for shoulder surgery (31). Since then, many devices and items have been developed with nickel–titanium SMAs.

NICKEL–TITANIUM SHAPE MEMORY ALLOY

Physical Properties

Some of the physical properties of 55-Nitinol are listed in Table 1 (32,33). Nitinol has good impact properties, low density, high fatigue strength, and a nonmagnetic nature. The excellent malleability and ductility of nitinol enable it to be manufactured in the form of wires, ribbons, tubes, sheets, or bars. It is particularly useful for very small devices.

Phase Diagram and Crystal Structures

A Ti–Ni equilibrium phase diagram (34) is very useful for understanding phase transformation and alloy design; a modified one is shown in Fig. 4 (35). There is a triangular region designated "TiNi" near the point of equiatomic composition. The left slope (solubility limit) is nearly vertical with temperature. This means that a precipitation-hardening process cannot be used on the Ti-rich side in bulk alloys. By contrast, the right slope is less steep than the left. Therefore, the precipitation-controlling process can adjust transformation temperatures for practical application of SMAs on the Ni-rich side. The crystal structure of the upper part of this triangle, > 1090 °C, is body centered cubic (bcc). The lower part is a CsCl-type ordered structure (B2) from 1090 °C to room temperature. A schematic atomic configuration of the B2 structure is shown in Fig. 5 (36). In 1965, Wang determined the lattice constant of the B2 crystal as $a_0 = 3.01$ Å (6). He proposed that the Ni–Ti crystal structure is not a simple CsCl-type structure, but has a disordered 9 Å superlattice and an ordered 3 Å CsCl-type sublattice. As the temperature is lowered, the ordered CsCl structure is slightly tilted instantaneously and cooperatively into a close-packed structure, called martensite, with a 2D dimensional close-packed plane (basal plane) (6,37). The martensite unit cell is described as a monoclinic (B19′) configuration, as shown in Fig. 6.

Table 1. Some of the Physical and Mechanical Properties of Nominal 55-Nitinol[a]

Density	6.45 g/cm^3
Melting point	1310 °C
Magnetic permeability coefficient	< 1.002
Electrical resistivity	
20 °C	80 $\mu\Omega \cdot$ cm
900 °C	132 $\mu\Omega \cdot$ cm
Thermal expansion	10.4×10^{-6}/ °C
Hardness,	
950 °C furnace cooled	89 R_B
950 °C quenched	89 R_B
Yield strength	103–138 MPa (15–20 $\times 10^3$ psi)
U.T.S.	860 MPa (125 $\times 10^3$ psi)
Elongation	60%
Young's modulus	70 GPa (10.2 $\times 10^6$ psi)
Shear modulus	24.8 GPa (3.6 $\times 10^6$ psi)
Poisson's ratio	0.33
Fatigue (Moore test) stress 10^7 counts	480 MPa (70 $\times 10^3$ psi)
Charpy impact	
Unnotched (RT)[b]	155 ftlb
Unnotched (−80 °C)	160 ftlb
Notched (RT)	24 ftlb
Notched (−80 °C)	17 ftlb

[a] Reproduced with permission from Biocompatibility of Clinical Implant Materials volume I, Ed. By D. F. Williams, 1981, Table 2 on page 136, Castleman L. S. and Motzkin S. M., copyright CRC press, Boca Raton Florida. See Refs. (32) and (33).

[b] Room temperature = RT.



Figure 4. Phase diagram of a Ti–Ni alloy and details of the TiNi and TiNi$_3$ phases (35). (Reproduced with permission from Binary Alloy Phase Diagrams, 2nd ed., Vol. 3, 1990, Phase diagram of a Ti-Ni alloy on page 2874, T. B. Massalski, H. Okamoto, P. R. Subramanian, and L. Kacprzak, ASM International.)



Figure 5. Schematic 3D diagram of the Ni–Ti atomic model in the stable high temperature phase (CsCl-type structure; lattice constant; $a_0 = 3.01$ Å).

The twin-type stacking of the thermally induced martensite structure shown on the left (a) has a readily deformable crystalline arrangement, from the twin structure to the detwinned structure shown on the right (b) (9,38). Diagram (b) of the detwinned structure shows relatively planar atomic stacking layer by layer alternately along the {111} basal plane of the deformed martensite crystal (39). Since martensitic transformation in Ni–Ti SMAs demonstrates an abnormal heat capacity change, it is regarded as a crystallographic distortion instead of a crystallographic transformation. The Ni–Ti martensite transformation is accompanied by a large latent heat of enthalpy ($\Delta H \sim 4{,}150$ J/mol). This extraordinarily latent heat of transformation was considered to be owing to a portion of the electrons undergoing a "covalent-to-metallic" electron-state transformation (11).

Thermomechanical Properties

The mechanical properties of Ni–Ti SMAs are closely dependent on the testing temperature. If a mechanical stress is applied to the SMA below the TTR, then the metastable parent structure of the Ni–Ti alloy is susceptible to transformation into the martensite. However, if the testing temperature exceeds the TTR, then, in the absence of stress, the reverse transformation happens. Figure 7 shows an example of a uniaxial compressive stress-strain curve of a Ni–Ti alloy above its TTR, which shows its superelasticity (40).


(a) (b)

Figure 6. Schematic 3D diagram of the Ni–Ti atomic stacking model of low temperature stable monoclinic structured martensite (a) twin-type stacking of martensite, (b) detwinned-type stacking of martensite).



Figure 7. Compressive stress–strain curve of a heat-treated 6-mm-diameter Ni–Ti rod at 4 °C. Three distinct stages are observed on the stress–strain curve (σM_f: stress-induced martensite finishing stress, σM_s: stress-induced martensite starting stress, σA_s: parent phase starting stress, σA_f: parent phase finishing stress) (40).

With stress below the martensite starting stress (σM_s), the Ni–Ti alloy behaves in a purely elastic way, as shown in section AB. As soon as the critical stress is reached at point B, corresponding to stress level σM_s, forward transformation (parent phase-to-martensite) is initiated and SIM starts to form. The slope of section BC (upper plateau) reflects the ease with which the transformation proceeds to completion, generating large transformational strains. When the applied stress reaches the value of the martensite finishing stress (σM_f), the forward transformation is completed and the SMA is fully in the SIM phase. For further loading above σM_f, the elastic behavior of martensite is observed again until plastic deformation occurs, as represented in section CD. For stress beyond D, the material deforms plastically until fracture occurs. However, if the stress is released before reaching point D, the strain is recovered in several stages. The first stage is elastic unloading of the martensite, as shown in section DE. On arriving at stress σA_s, at E, the reverse martensite transformation starts and the fraction of martensite decreases until the parent phase is completely restored at F. Section FA represents the elastic unloading of the parent phase. If some irreversible deformation has taken place during either loading or unloading, the total strain may not be recovered completely. Owing to the stress differences between σM_f and σA_s and between σM_s and σA_f, a hysteresis loop is obtained in the loading–unloading stress–strain curve. Increasing the test temperature results in an increase in the values of the critical transformation stresses, while the general shape of the hysteresis loop remains the same. The area enclosed by the loading and unloading curves represents the energy dissipated during a stress cycle. As part of the hysteresis loop, both the loading and unloading curves show plateaus, at which point large strains are accommodated on loading, or recovered on unloading, with only a small change in stress (19). This behavior of Ni–Ti SMAs is much like that of natural tissues, such as hair and bone, and results in a "superelastic" ability to withstand and recover from large deforming stresses.



Figure 8. The effect of compressive (a) and tensile (b) loading on martensite formation and disappearance in 20.7% Tl–In alloy (19). (From J. Mat. Sci. Vol. 9, 1974, Figure 2 on page 1537, Krishnan R. V., Delaey L., Tas H. and Warlimont H., Kluwer Academic Publisher. Reproduced with kind permission of Springer Science and Business Media.)

In 1974, Krishnan argued that Burkart and Read had found the effects of compressive and tensile stress on martensite formation and disappearance in Tl–In SMAs (19). The transformation stresses σM_s and σA_s have a linear relation with testing temperature, as shown in Fig. 8 (41). They inferred that σM_s is a linear function of temperature, and the stresses σM_s and σA_s increase with temperature.

Another important thermomechanical property of SMAs is the relationship between the plateau stress of the martensite phase transformation and the enthalpy change of that reaction. As the stress-induced martensitic transformation is a second-order transformation, the amount of transformation depends on its temperature, so the high temperature state has a larger energy barrier of SIM and needs more energy to overcome this larger reverse martensitic transformation barrier. The enthalpy change of the parent phase to martensitic transformation ($\Delta H^{\text{p-m}}$) can be calculated theoretically using the modified Clausius–Clapeyron equation (20), shown in Eq. 1.

$$\frac{\delta\sigma^{\text{p-m}}}{\delta T} = \frac{\rho \Delta H^{\text{p-m}}}{\varepsilon^{\text{p-m}} T_{\text{o}}} \tag{1}$$

Where $\Delta H^{\text{p-m}}$ is the enthalpy change of the parent phase to the martensite phase at T_{o}; $\sigma^{\text{p-m}}$ is the stress at which stress-induced martensite is formed at the testing temperature, T; ρ is the density of the SMA; and $\varepsilon^{\text{p-m}}$ is the strain corresponding to complete transformation. $\delta\sigma^{\text{p-m}}$ and $\varepsilon^{\text{p-m}}$ can be taken from the stress–strain curves. Kim compared the theoretically calculated $\Delta H^{\text{p-m}}$ of a Ni–Ti alloy using stress–strain curves and Eq. 1 with an experimentally acquired value (9). He reported that the theoretical value of $\Delta H^{\text{p-m}}$ for a Ni–Ti alloy calculated from the stress–strain curves was 6.24 cal/g. The experimental value of the enthalpy change ($\Delta H^{\text{p-m}}$) of an 8% prestrained Ni–Ti wire sample from DSC measurement was 6.79 cal·g^{-1}. Based on this result, he inferred that Ni–Ti alloys undergo thermomechanical-phase transformation by exchanging thermal energy into mechanical energy and vice versa (9).

MANUFACTURING METHODS

Alloy Refining

The Ni–Ti SMAs can be refined using either the vacuum-induction melting method or the consumable arc melting technique. In vacuum-induction melting, a prerequisite in working with Ni–Ti is a high purity graphite crucible. To prevent impurities, the crucible should be connected to the pouring lip mechanically to keep the molten Ni–Ti compound from contacting anything, but the high density, low porosity graphite. Elemental carbon is very reactive with Ni or Ti alone and any contact with either will ruin the purity of the desired sample. However, there is very little reaction with the crucible in the consumable arc melting process. This method yields a product that is relatively free of impurities. Once the Ni–Ti alloy is cast using the melting technique, it is ready for hot or cold working into more practical forms and consecutive annealing treatment (42).

Mechanical Processing

When hot working a piece of Ni–Ti alloy, the temperature should be below that where incipient melting of the secondary phase can occur. This temperature should also be held constant for a period of time sufficient for certain nonequilibrium phases to return to solution, which makes the remaining alloy homogeneous. Andreasen suggested that the optimum hot working temperature is 700–800 °C for forging, extrusion, swaging, or rolling. If cold rolling is desired, then the alloy should be annealed before the oxide is removed (42). The most common form of Ni–Ti alloy is a wire. To make a wire, the Ni–Ti alloy ingot must be rolled into a bar at high temperature. Swaging the bar, followed by drawing, and a final annealing, reduce the alloy to wire form. To soften the wire, it should be annealed between 600 and 800 °C for a short period. When the Ni–Ti alloy is drawn down to 0.8 mm through a carbide die, the maximum reduction in area with each pass should be within 10%. Once this diameter is reached, a diamond die is used to draw the alloy with a 20% area reduction per die. The Ni–Ti alloy is annealed again at 700 °C and allowed to cool to room temperature between passes (42). By contrast, the extrusion method is used for the tube-making process, which enables a substantially greater reduction in cross-sectional area as compared to drawing wire. Laser cutting of Ni–Ti tubes has been used to make vascular stents (43). Most Ni–Ti alloys require a surface finishing procedure after the final machining process, such as chemical leaching, cleaning, rinsing, and surface modification.

Shape Memory Programming

There are two steps in the shape memory programming of a Ni–Ti alloy. First, the Ni–Ti alloy sample must be deformed to the desired shape and put into a constraining mold or fixture. The next step is shape memory heat treatment in a furnace at 400–600 °C. The shape recovery efficiency of a Ni–Ti alloy can be controlled by changing the heat treatment conditions or the degree of deformation. In general, there are three different ways to control the TTR of a Ni–Ti SMA: altering the chemical composition, changing the heat treatment conditions, and varying the degree of deformation (13).

Chemical Composition Effect on TTR. The shape memory characteristic is limited to Ni–Ti alloys with near-equiatomic composition, as shown in Fig. 4. A pure stoichiometric (50 at%) Ni–Ti alloy will have a nickel content of ~ 55 wt%. Increasing the nickel concentration lowers the characteristic transformation temperature of the alloy. The limit of the nickel concentration for a SMA is ~ 56.5 wt%, owing to the formation of a detrimental second phase. In addition, the shape memory properties of a Ni–Ti alloy can be readily modified by adding ternary elements that are chemically similar to Ni or Ti. Adding a small amount of a transition metal such as Co, Fe, or Cr, instead of Ni, depresses the TTR, such that the SME occurs at well-below ambient temperature (44). When larger ions are substituted for smaller ions, the transformation temperature increases. Concerning ternary additions to alloys, Murakami et al. (45) proposed that the stability of the parent phase is controlled by ion–core repulsive interactions such that when larger ions are substituted for smaller ions, the transformation temperature increases. Based on this hypothesis, substitutions of Au and Zr should increase the recovery temperature of Ni–Ti alloys, Al and Mn should decrease it, and Co and Fe should cause little change. The effects of Au, Zr, Al, and Mn were predicted correctly, but those of Co and Fe were not. Similarly, Morberly suggested that if $> 7.5\%$ copper is added to a Ni–Ti alloy, up to 30%, the addition of Cu increases and narrows the TTR (46).

Mechanical Deformation Effect on the TTR. Many investigators have reviewed the effect of mechanical deformation on the TTR (5,36,47). They found that the degree of deformation affects the TTR of a SMA, and the stress slope ($d\sigma/dT$) is a very important fundamental descriptor of SMAs. The residual stress from prior cold work can have a major effect on the transformation behavior. As a result, retention of the parent phase is a function of the stress and heat treatment history. Lee et al. reported that bending beyond the yielding point broadened the TTR and increased the stored internal energy (48). Figure 9 shows an example of transition temperature variation with respect to uniaxial prestrain of a Ni–Ti alloy wire (13). When the prestrain $> 8\%$, the shape recovery transition temperature (A_s) and the martensite starting temperature (M_s) are increased with increasing prestrain. However, the enthalpy change of the cooling cycle is almost the same because most stored internal energy in SIM is already liberated during the heating cycle (36).

Heat Treatment Effect on the TTR. The TTR of a Ni–Ti alloy can be controlled by the final annealing temperature and time. Kim insisted that a higher annealing temperature gives a lower transition temperature and a wider TTR (9). Moreover, he showed that a larger grain size has a lower transition temperature because the annealed large grains have much more transformable volume than smaller grains, so they need more energy for second-phase nucleation and growth inside the grain (49).



Figure 9. Transition temperatures of prestrained Ni–Ti alloy wire (13).

Figure 10 shows an example of the heat treatment temperature effect on SME (40). When a Ni–Ti rod is heat treated for 30 min at 600 °C, the rod shows superelasticity at room temperature. This indicates that the TTR is lower than the testing temperature. By contrast, when a Ni–Ti rod is heat treated for 30 min at < 500 °C, the rod shows SME at room temperature, which suggests that the TTR is higher than the testing temperature. These results clearly show that the SME is closely related to the heat treatment temperature (9,50).

Methods of Measuring Transition Temperatures

There are many measurable parameters that accompany the shape memory transformation of a Ni–Ti alloy, for example, hardness, velocity of sound, damping characteristic, elastic modulus, thermal expansion, electrical resistivity, specific heat, latent heat of transformation, thermal conductivity, and lattice spacing. Of these, the electrical resistivity and latent heat of transformation are useful for measuring the TTR of a SMA.



Figure 10. The room temperature compression stress–strain curves of heat-treated ϕ6-mm Ni–Ti rods for 30 min at 350–600 °C. The numbers pointing to the graphs are the annealing temperatures (40).



Figure 11. A cyclic DSC curve of the specific heat versus temperature for a Ni–Ti alloy wire from −70 to 70 °C. The lower and upper parts of the cyclic curve represent heating and cooling processes, respectively. (A_s: shape recovery starting temperature, A_f: shape recovery finishing temperature, M_s: martensitic transformation starting temperature, M_f: martformation starting temperature, R_f: R phase transformation finishing temperature) (40).

DSC Measurement. Differential scanning calorimetry (DSC) is a thermal analysis technique that determines the specific heat, heat of fusion, heat of reaction, or heat of polymerization of materials. It is accomplished by heating or cooling a sample and reference under such conditions that they are always maintained at the same temperature. The additional heat required by the sample to maintain it at the same temperature is a function of the observed chemical or physical change (50). Figure 11 shows a typical DSC curve of the specific heat change of a Ni–Ti alloy (40). The lower curve is the heating curve and the upper one is the cooling curve. Each peak represents a phase transformation during the thermal cycle. The area under the curve represents the enthalpy change (ΔH) during the phase transformation. The arrows on Fig. 11 indicate the transition temperatures. The advantage of DSC measurement is that samples can be small and require minimal preparation. In addition, it can detect the residual strain energy, diffusing DSC peaks (51).

Electrical Resistivity Measurement. The shape memory transition temperature can also be determined from the curve of the electrical resistance versus temperature using a standard four-probe potentiometer within a thermal scanning chamber. In 1968, Wang reported the characteristic correlation between the shape memory phase transformations of a Ni–Ti alloy and the irreversible electrical resistivity curves (52). He proposed that the electrical resistivity curve in the same temperature range has a two-step process on cooling, that is, from the parent phase via R-phase to the final martensite phase, and a one-step process on heating, that is, from the martensite to the parent phase. Figure 12 plots the electrical resistivity versus temperature curves of a ϕ1.89 mm Ni–Ti alloy wire that was heat treated at 550 °C for 30 min. During the heating process, the electrical resistivity increases up to temperature A_s, and then it decreases until temperature A_f is reached. This suggests the restoration of the parent structure accompanying this resistivity change. During the cooling cycle, however, a triangular curve appears. The increasing part of this triangular curve from R_s to R_f represents the formation of an intermediate R phase resulting in a further increase in electrical resistivity. The decreasing part represents the thermal energy absorption of the martensitic phase transformation.



Figure 12. The electrical resistivity versus temperature curve of a ϕ1.89 mm Ni–Ti alloy wire that was heat treated at 550 °C (53).

Corrosion Resistance

The Ni–Ti SMAs are an alloy of nickel, which is not corrosion resistant in saline solutions, such as seawater, and titanium, which has excellent corrosion resistance under the same conditions. The corrosion resistance of Ni–Ti alloys more closely resembles that of titanium than that of nickel. The corrosion resistance of Ni–Ti alloys is based mainly on the formation of a protective oxide layer, which is called passivation (9). If the alloy corrodes, then breakdown of the protective oxide film on the alloy's surface occurs locally or generally, and substantial quantities of metallic ions are released into the surrounding solution. Therefore, corrosion resistance is an important determinant of biocompatibility (54–56). The Pourbaix diagram is a useful means of measuring corrosion. It is a potential versus pH diagram of the redox and acid–base chemistry of an element in water. It is divided into regions where different forms of the metal predominate. The three regions of interest for conservation are corrosion, immunity, and passivity. The diagram may indicate the likelihood of passivation (or corrosion) behavior of a metallic implant *in vivo*, as the pH varies from 7.35 to 7.45 in normal extracellular fluid, but can reach as low as 3.5 around a wound site (57). An immersion test is also used for determining the concentration of released metallic ions, corrosion rates, corrosion types, and passive film thickness in saline, artificial saliva, Hank's solution, physiological fluids, and so on (58).

Some surface modifications have been introduced to improve the corrosion properties of Ni–Ti alloys, and prevent the dissolution of nickel. These include titanium nitride coating of the Ni–Ti surface and chemical modification with coupling agents for improving corrosion resistance. However, when the coating on a Ni–Ti alloy is damaged, corrosion appears to increase in comparison with an uncoated alloy (56). Laser surface treatment of Ni–Ti leads to increases in the superficial titanium concentration and thickness of the oxide layer, improving its cytocompatibility up to the level of pure titanium (9). Electropolishing methods and nitric acid passivation techniques can improve the corrosion resistance of Ni–Ti alloys owing to the increased uniformity of the oxide layer (59).

Biocompatibility

Biocompatibility is the ability of a material or device to remain biologically inactive during the implantation period. The purpose of a biocompatibility test is to determine potential toxicity resulting from contact of the device with the body. The device materials should not produce adverse local or systemic effects, be carcinogenic, or produce adverse reproductive or developmental effects, neither directly nor through the release of their material constituents (60). Therefore, medical devices must be tested for cytotoxicity, toxicity, specific target-organ toxicity, irritation of the skin and mucosal surfaces, sensitization, hemocompatibility, short-term implantation effects, genotoxicity, carcinogenicity, and effects on reproduction.

The biocompatibility of a Ni–Ti alloy must include the biocompatibility of the alloy's constituents. As Ni–Ti alloys corrode, metallic ions are released into the adjacent tissues or fluids by some mechanisms other than corrosion (61). Although Ni–Ti alloys contain more nickel than 316L stainless steel, Ni–Ti alloys show good biocompatibility and high corrosion resistance because of the naturally formed homogeneous TiO_2 coating layer, which has a very low concentration of nickel. Although Ni–Ti alloys have the corrosion resistance of titanium, the passivated oxide film will dissolve at some rate; furthermore, the oxide layer does not provide a completely impervious barrier to the diffusion of nickel and titanium ions (62,63).

Many investigators have reported on the biocompatibility of Ni–Ti alloys. Comparing the corrosion resistance of common biomaterials, the biocompatibility of Ni–Ti ranks between that of 316L stainless steel and Ti6A14V, even after sterilization. Some of these findings are listed here. Thierry found that electropolished Ni–Ti and 316L stainless steel alloys released similar amounts of nickel after a few days of immersion in Hank's solution (64). Trepanier reported that electropolishing improved the corrosion resistance of Ni–Ti stents because of the formation of a new homogeneous oxide layer (59). In a short-term biological safety study, Wever found that a Ni–Ti alloy had no cytotoxic, allergic, or genotoxic activity and was similar to the clinical reference control material AISI 316 LVM stainless steel (65). Motzkin showed that the biocompatibility of nitinol is well within the limits of acceptability in tissue culture studies using human fibroblasts and buffered fetal rat calvaria tissue (66). Ryhanen reported that nitinol is nontoxic, nonirritating, and very similar to stainless steel and Ti–6Al–4V alloy in an *in vivo* soft tissue and inflammatory response study (67). Castleman found no significant histological compatibility differences between nitinol and Vitallium (Co–Cr alloy) (68). However, Shih reported that nitinol wire was toxic to primary cultured rat aortic smooth muscle cells in his cytotoxicity study using a supernatant and precipitate of the corrosion products (69). Moreover, he found that the corrosion products altered cell morphology, induced cell necrosis, and decreased cell numbers.

MEDICAL DEVICES

The Ni–Ti alloys have been used successfully for medical and dental devices because of their unique properties, such as SME, superelasticity, excellent mechanical flexibility, kink resistance, constancy of stress, good elastic deployment, thermal deployment, good corrosion resistance, and biocompatibility. Recently, Ni–Ti alloys have found use in specific devices that have complex and unusual functions, for example, self-locking, self-expanding, or compressing implants that are activated at body temperature (58). Some popular examples of Ni–Ti medical devices have been selected and are reviewed below.

Orthodontic Arch Wires

A commercially available medical application of nitinol is the orthodontic dental arch wire for straightening malpositioned teeth, marketed by Unitek Corporation under the name Nitinol Active-Arch (70). This type of arch wire, which is attached to bands on the teeth, is intended to replace the traditional stainless steel arch wire. Although efforts have been made to use the SME in orthodontic wires (71), the working principle of Nitinol Active-Arch wire is neither the SME nor pseudoelasticity, but the rubber-like behavior and relatively low Young's modulus (30 GPa) of nitinol in the martensitic condition. This modulus is very low in comparison with the modulus of stainless steel (200 GPa). Comparing the bending moment change of nitinol and stainless steel wire undergoing a constant change in deflection (72), stainless steel wire shows a much larger change in moment than the moment change of nitinol wire. Clinically, this means that for any given malocclusion nitinol wire will produce a lower, more constant force on the teeth than would a stainless steel wire of equivalent size. Figure 13 shows a clinical example of orthodontic treatment using a superelastic Ni–Ti arch wire (73). This wire showed faster movement of teeth and shorter chair time than conventional stainless steel wire.

Guidewires

One typical application of superelasticity is the guidewires that are used as guides for the safe introduction of various therapeutic and diagnostic devices. A guidewire is a long, thin metallic wire that is inserted into the body through a natural opening or a small incision. The advantages of using superelastic guide wire are the improvement in kink resistance and steerability. A kink in a guidewire creates a difficult situation when the time comes to remove it from a



Figure 13. Orthodontic treatment using a Ni–Ti superelastic arch wire. (a) Malaligned teeth before treatment and (b) normally aligned teeth after the first stage of treatment (73). (Reprinted with permission from Shape memory materials, Ed. By K. Otsuka and C. M. Wayman, 1998, Figure 12.3 on page 270, S. Miyazaki, Cambridge University Press.)

complex vascular structure. The enhanced twist resistance and flexibility make it easier for the guidewire to pass to the desired location (74). Figure 14 shows the tip of a guidewire. The curved “J” tip of the guidewire makes it easy to select the desired blood vessel.



Figure 14. Photograph of the tip of a commercial Ni–Ti guidewire (FlexMedics, USA) (75).



Figure 15. Commercial Ni–Ti stents (a) Gianturco stent, (b) self-expanding nitinol stent with the Strecker stent design, (c) Wall stent (76).

Stents

A stent is a slender metal mesh tube that is inserted inside a luminal cavity to hold it open during and after surgical anastomosis. Superelastic nitinol stents are very useful for providing sufficient crush resistance and restoring lumen shape after deployment through a small catheter (25–27). Figure 15 shows three examples of commercial self-expandable Ni–Ti superelastic stents: a Gianturco stent for the venous system, a Strecker stent for a dialysis shunt, and a Wall stent for a hepatic vein. Figure 16 shows the moment of expansion of a Ni–Ti self-expandable stent being deployed from the introducer. The driving force of the self-expanding stent is provided by the superelasticity of the Ni–Ti alloy. Some clinical limitations of Ni–Ti stents remain unresolved and require further development; these are the problems of intimal hyperplasic and restenosis (78).

Orthopedic Applications

Dynamic compression bone plates exhibiting the SME are one of the most popular orthopedic applications of nitinol, followed by intramedullary fixation nails. Fracture healing



Figure 16. Deployment of a commercial Ni–Ti self-expandable stent (Taewoong Medical, Korea) (77).

in long bones can be accelerated when bone ends are held in position with compression between the bone fragments. Using this method, the undesirable surface damage and wear of the holes that occur in a conventional dynamic bone plate are avoided, while continuous compression is assured, even if bone resorption occurs at the fracture sites. The effect continues as long as the original shape is not reached (79).

Historically, the first orthopedic application of a SMA was a Nitinol Harrington instrument for scoliosis treatment that was introduced in 1976 by Schmerling (80), which enabled the surgeon to restore any relaxed corrective force postoperatively simply by the external application of heat. In addition, it could be used initially to apply a more appropriate set of corrective forces. Figure 17 shows an example of a Ni–Ti shape memory clamp in small bone surgery (81). Six months after surgery, a non-union was present, although the outcome in this patient was assessed as good.

CONCLUSIONS

A shape memory alloy is a metallic substance that has a memory for shape combined with superelasticity. The mechanisms of a nickel–titanium alloy's shape memory effect and superelasticity are described based on thermally induced or stress induced martensite phase transformations. Some of the physical properties of nickel–titanium alloys and a phase diagram are included for reference. The thermomechanical characteristics, corrosion properties, and biocompatibility of Ni–Ti shape memory alloys are reviewed for the design of shape memory devices. Manufacturing methods, including refining, processing, shape memory programming, and transformation temperature range measuring methods are summarized for practical applications. Finally, some applications in medical devices are reviewed as examples of current trends in the use of shape memory alloys. In conclusion, Ni–Ti shape memory alloys are a very useful biocompatible material because of their unique mechanical properties and good corrosion resistance. A better understanding of shape memory alloys should allow further developments in this area.



Figure 17. Failed arthrodesis of the carpometacarpal joint when only one titanium–nickel (TiNi) clamp was used (81). (From Arch. Orthop. Trauma Surg., Vol. 117, 1998. Figure 1 on page 342, Musialek J., Filip P. and Nieslanik J. Reproduced with kind permission of Springer Science and Business Media.)

BIBLIOGRAPHY

Cited References

1. Properties and selection. Metal handbook 8th edition volume 1. American Society for Metals; 1961. p 1.
2. Jena AK, Chaturvedi MC. Phase transformation in materials. Prentice Hall; 1992. p 1–3.
3. Park JB, Kim YK. Metallic biomaterials. In: Bronzino JD, editor. The biomedical engineering handbook. 2nd ed. Volume 1, CRC Press; 2000. p 37-1–37-20.
4. Buehler WJ, Gilfrich JV, Wiley RC. Effect of low-temperature phase changes on the mechanical properties of alloys near composition TiNi. J Appl Phys 1963;34:1475–1477.
5. Wayman CM, Duerig TW. An introduction to martensite and shape memory. In: Duerig TW, Melton KN, Stoeckel D, Wayman CM, editors. Engineering aspects of shape memory alloys. Butterworth-Heinemann; 1990. p 3–20.
6. Wang FE, Buehler WJ, Pickart SJ. Crystal structure and a unique martensite transition on TiNi. J Appl Phys 1965;36: 3232–3239.
7. Ling CH, Kaplow R. Stress-induced shape changes and shape memory in the R and Martensite transformations in equiatomic NiTi. Metal Trans A 1981;12A:2101–2111.
8. In: Nishiyama Z, Fine ME, Meshii M, Wayman CM, editors. Martensitic Transformation. London: Academic Press; 1978. p 1–13.
9. Kim YK. Thermo-mechanical study of annealed and laser heat treated nickel–titanium alloy dental arch wire. Ph.D. dissertation, University of Iowa, Iowa, Dec. 1989.
10. Wayman CM, Bhadeshia H. Phase transformations, Nondiffusive. In: Cahn RW, Haasen P, editor. Physical Metallurgy. 4th ed. Volume 2, North-Holland: 1996. p 1507–1554.
11. Wang FE, Pickart SJ, Alperin HA. Mechanism of the TiNi transformation and the crystal structures of TiNi-II and TiNi-III phases. J Appl Phys 1972;43:97–112.
12. Otsuka K, Wayman CM, Nakai K, Sakamoto H, Shimizu K. Superelasticity effects and stress-induced martensite transformations in Cu–Al–Ni alloys. Acta Metallurgica 1976;24: 207–226.
13. Kim YK, Doo JK, Park JP. The application of shape memory alloy to abdominoscopic suture needles, In: Shin KS, Yoon JK, Kim SJ, editors. Proceeding of 2nd Pacific RIM International conference on Advanced Materials and Processing. Korean Institue of Metals and Materials; 1995. p 1691–1696.
14. Oelander A. Z Kristallogr 1932;83A:145. as cited in Lieberman DS. Crystal geometry and mechanisms of phase transformations in crystalline solids. In: Aaronson HI, editor. Phase Transformations. American Society for Metals; 1970. p 1–58.
15. Greninger AB, Mooradian VG. Strain transformation in metastable beta copper-zinc and beta copper-tin alloys. Am Inst Mining Met Eng 1937;19:867.
16. Bush RE, Leudeman RT, Gross PM. Alloys of improved properties. AMRA CR 65-02/1, AD629726, U.S. Army Materials Research Agency, 1966.
17. Kurdjumov GV, Khandros LG. Dokl Akad Nauk SSSR 1949;66:211. (as cited in Delaey L, Krishnan RV, Tas H, Warlimont H. Review: thermoelasticity, pseudoelasticity and memory effects associated with martensitic transformations. J Mater Sci 1974;9:1521–1535.
18. Delaey L, Krishnan RV, Tas H, Warlimont H. Review Thermoelasticity, pesudoelasticity and the memory effects associated

with martensitic transformations Part 1 Structural and microstructural changes associated with the transformations. J Mat Sci 1974;9:1521–1535.

19. Krishnan RV, Delaey L, Tas H, Warlimont H. Review Thermoelasticity, pesudoelasticity and the memory effects associated with martensitic transformations Part 2 The macroscopic mechanical behaviour. J Mater Sci 1974;9:1536–1544.
20. Warlimont H, Delaey L, Krishnan RV, Tas H. Review Thermoelasticity, pesudoelasticity and the memory effects associated with martensitic transformations Part 3 Thermodynamics and kinetics. J Mater Sci 1974;9:1545–1555.
21. Melton KN. General applications of SMA's and smart materials. In: Duerig TW, Melton KN, Stoeckel D, Wayman CM, editors. Engineering aspects of shape memory alloys. Butterworth-Heinemann; 1990. p 220–239.
22. Miayazaki S. Medical and dental applications of shape memory alloys, In: Duerig TW, Melton KN, Stoeckel D, Wayman CM, editor. Engineering aspects of shape memory alloys. Butterworth-Heinemann; 1990. p 267–281.
23. Filip P. Titanium-Nickel shape memory alloys in medical applications. In: Brunette DM, Tengvall P, Textor M, Thomsen P, editor. Titanium in Medicine. Springer; 2001. p 53–86.
24. Andreasen GF, Hilleman TB. An evaluation of 55 cobalt substituted Nitinol wire for use in orthodontics. JADA 1971;82: 1373–1375.
25. Dotter CT, Bushmann RW, McKinney MK, Rosch J. Transluminal expandable nitinol coil stent grafting: preliminary report. Radiology 1983;147:259–260.
26. Cragg A, Lund G, Rysavy J, Castaneda F, Castaneda-Zuniga W, Amplatz K. Nonsurgical placement of arterial endoprostheses: a new technique using nitinol wire. Radiology 1983;147: 261–263.
27. Rösch J, Keller FS, Kaufman JA. The Birth, Early Years, and Future of Interventional Radiology. JVIR 2003;14(7):841–853.
28. Rauber K, Franke C, Rau WS, Syed Ali S, Bensmann G. Perorally insertable endotracheal stents made from NiTi memory alloy - an experimental animal study. Rofo Fortschr Geb Rontgenstr Neuen Bildgeb Verfahr 1990;152(6):698–701.
29. Rabkin JE, Germashev V. The Rabkin nitinol coil stent: a fiveyear experience. In: Castaneda-Zuniga WR, Tadavarthy SM, editors. Interventional Radiology, 2nd ed. Williams & Wilkins; 1992. p 576–581.
30. Kikuchi Y, Graves VB, Strother CM, McDermott JC, Babel SG, Crummy AB. A new guidewire with kink-resistant core and low-friction coating. Cardiovasc Intervent Radiol 1989;12(2): 107–109.
31. Kauffman GB, Mayo I. The story of Nitinol: the serendipitous discovery of the memory metal and its applications. Chem Educator 1997;2(2):S1430–4171; http://chemeducator.org/bibs/0002002/00020111.htm, Feb.2. 2005.
32. Castleman LS, Motzkin SM. The Biocompatibility of Nititnol. In: Williams DF, editor. Biocompatibility of Clinical Implant Materials volume I. CRC Press; 1981. p 129–154.
33. Cross WB, Karitos AH, Wasilewski RJ. Nitinol characterization study. NASA CR-1433, National Aeronautics and Space Administration, Houston. 1969.
34. Buehler WJ, Wiley RC. TiNi-ductile intermetallic compound. Trans ASM 1962;55:269–276.
35. Otsuka K, Kakeshita T. Science and Technology of Shape memory Alloys: New Developments. MRS Bull 2002;27(2): 91–100.
36. Kim YK. The study of the shape recovery temperature change of cold-worked nickel-titanium alloys. Inje J 1994;10(1): 341–352.
37. Aboelfotoh MO, Aboelfotoh HA, Washburn J. Observations of pretransformation lattice instability in near equiatomic NiTi alloy. J Appl Phys 49(10): 1978; 5230–5232.
38. Ling HC, Kaplow R. Phase transitions and shape memory in NiTi. Metal Trans A 1980;11A:77–83.
39. Chandra K, Purdy GR. Obseravation of thin crystals of TiNi in premartensite states. J Appl Phys 19(5): 1968; 2176–2181.
40. Shin SH. The study of heat-treatment temperature effect on hardness and compressional properties of nickel-titanium alloy. Master. dissertation, Inje University, Korea, Dec. 1998.
41. Burkart MW, Read TA. Trans Met Soc AIME 1953;197:1516. (as cited in Krishnan RV, Delaey L, Tas H, Warlimont H. Review Thermoelasticity, pesudoelasticity and the memory effects associated with martensitic transformations Part 2 The macroscopic mechanical behaviour. J Mat Sci 1974;9:1536–1544.
42. Andreasen GF, Fahl JL. Alloys, Shape Memory. In: Webster JG, editor. Encyclopedia of Medical Devices and Instrumentation. Volume 1, New York: Wiley-Interscience; 1988. p 15–20.
43. Thierry B, Merhi Y, Bilodeau L, Trepanier C, Tabrizian M. Nitinol versus stainless steel stents: acute thrombogenicity study in an ex vivo porcine model. Biomaterials 2002;23:2997–3005.
44. Moberly WJ, Melton KN. Ni–Ti–Cu shape memory alloys. Engineering Aspects of Shape Memory Alloys. London: Butterworth-Heinemann; 1990. p 46–57.
45. Murakami Y, Asano N, Nakanishi N, Kachi S. Phase relation and kinetics of the transformations in Au–Cu–Zn thernary alloys. Jpn J Appl Phys 1967;6:1265–1271.
46. Gil FJ, Planell JA. Effect of copper addition on the superelastic behavior of Ni–Ti shape memory alloys for orthodontic applications. J Biomed Mater Res Appl Biomat 1999;48:682–688.
47. Goldstein D, Kabacoff L, Tydings J. Stress effects on Nitinol phase transformations. J Metals 1987;39(3):19–26.
48. Lee JH, Park JB, Andreasen GF, Lakes RS. Thermo mechanical study of Ni–Ti alloys. J Biomed Mater Res 1988;22: 573–588.
49. Kim YK. The Grain size distribution study of heat treated Ni–Ti alloy. Inje J 1993;9(2):857–868.
50. Differential Scanning Calorimetry, Dept. of Polymer Science, University of Southern Mississippi. Available at http://www.psrc.usm.edu/macrog/dsc.htm. Accessed Feb. 8. 2005.
51. Harrison JD. Measurable changes concomitant with the shape memory effect transformation, In: Duerig TW, Melton KN, Stoeckel D, Wayman CM, editors. Engineering aspects of shape memory alloys. Butterworth-Heinemann; 1990. p 106–111.
52. Wang FE, DeSavage BF, Buehler WJ, Hosler WR. The irreversible critical range in the TiNi transition. J Appl Phys 1968;39(5):2166–2175.
53. Kim YK. unpublished experimental data (ykkimbme.inje.ac.kr).
54. Cutright DE, Bhaskar SN, Perez B, Johnson RM, Cowan GS, Jr. Tissue reaction to nitinol wire alloy. Oral Surg 1973;35(4): 578–584.
55. Castleman LS, Motzkin SM, Alicandri FP, Bonawit VL. Biocompatibility of Nitinol alloy as an implant material. J Biomed Mater Res 1976;10:695–731.
56. Castleman LS, Motzkin SM. The biocompatibility of Nitinol. In: Williams DF, editor. Biomcompatibility of Clinical Implant Materials. Volume 1, CRC Press; 1981. p 129–154.
57. Park JB. Metallic implant materials. Biomaterials Science and Engineering. Joon Bu Park: Plenum Press; 1984. p 193–233.
58. Ryhaenen J. Biocompatibility Evaluation of Nickel-Titanium Shape Memory Metal Alloy. Academic Dissertation, University hospital of Oulu, on May 7th, 1999.
59. Trepanier C, Tabrizian M, Yahia LH, Bilodeau L, Piron DL. Effect of modification of oxide layer on NiTi stent corrosion resistance. J Biomed Mater Res (Appl Biomater) 1998;43:433–440.
60. Kammula RG, Morris JM. Considerations for the Biocompatibility Evaluation of Medical Devices. Available at http://www.devicelink.com/mddi/archive/01/05/008.html. Medical Device Link. Accessed Feb. 2. 2005.

61. Austian J. Toxicological evaluation of biomaterials: primary acute toxicity screening program. Artif Organs 1977;1:53–60.
62. Mears DC. The use of dissimilar metals in surgery. J Biomed Mater Res 1975;9:133–148.
63. Williams DF. Future prospects for biomaterials. Biomed Eng 1975;10:206–218.
64. Thierry B, Tabrizian M, Trepanier C, Savadogo O, Yahia LH. Effect of surface treatment and sterilization processes on the corrosion behavior of NiTi shape memory alloy. J Biomed Mater Res 2000;51:685–693.
65. Wever DJ, Veldhuizen AG, Sanders MM, Schakenraad JM, Horn V, Jr. Cytotoxic, allergic and genotoxic activity of a nickel–titanium alloy. Biomaterials 1997;18(16):1115–1120.
66. Motzkin SM, Castleman LS, Szablowski W, Bonawit VL, Alicandri FP, Johnson AA. Evaluation of nitinol compatibility by cell culture. Proc. 4th New England Bioeng Conf. New Haven: Yale University; 1976. p 301.
67. Ryhanen J, Kallioinen M, Tuukkanen J, Junila J, Niemela E, Sandvik P, Serlo W. In vivo biocompatibility evaluation of nickel-titanium shape memory metal alloy: muscle and perineural tissue responses and encapsule membrane thickness. J Biomed Mater Res 1998;41(3):481–488.
68. Castleman LS. Biocompatibility of Nitinol alloy as an implant material. Proceeding of the 5th Annual International Biomaterials Symposium. Clemson (SC): Clemson University; 1973.
69. Shih CC, Lin SJ, Chen YL, Su YY, Lai ST, Wu GJ, Kwok CF, Chung KH. The cytotoxicity of corrosion products of nitinol stent wire on cultured smooth muscle cells. J Biomed Mater Res 2000;52:395–403.
70. Andreasen GF. Method and system for orthodontic moving of teeth. US pat. 4,037,324. 1977.
71. Andreasen GF. A clinical trial of alignment of teeth using a 0.019 inch thermal nitinol wire with a transition temperature range between 31 °C and 45 °C. Am J Orthod 1980;78(5):528–537.
72. Andreasen GF, Morrow RE. Laboratory and clinical analyses of nitinol wire. Am J Orthod 1978;73:142–151.
73. Miyazaki S. Medical and dental applications of shape memory alloys. In: Otsuka K, Wayman CM, editor. Shape memory materials. Cambridge University Press; 1998. p 267–281.
74. Mooney MR, Mooney JF, Pedersen WR, Goldenberg IF, Gobel FL. The Ultra-Select guidewire: a new nitinol guidewire for coronary angioplasty. J Invasive Cardiol 1991;3(5):242–245.
75. Kim YK. unpublished photograph (ykkimbme.inje.ac.kr).
76. Kim YK. unpublished photograph (ykkimbme.inje.ac.kr).
77. Kim YK. unpublished photograph (ykkimbme.inje.ac.kr).
78. Palmaz JC, Kopp DT, Hayashi H, Schatz RA, Hunter G, Tio FO, Garcia O, Alvarado R, Rees C, Thomas SC. Normal and stenotic renal arteries: experimental balloon-expandable intraluminal stenting. Radiology 1987;164(3):705–708.
79. Kousbroek R. Shape memory alloys, In: Ducheyne P, editor. Metal and Ceramic Biomaterials, Volume II: Strength and Surface. CRC Press; Chapt. 3. 1984. p 63–90.
80. Schemerling MA, Wilkov MA, Sanders AE, Woosley JE. Using the shape recovery of Nitinol in the Harrington rod treatment of scoliosis. J Biomed Mater Res 1976;10:879–892.
81. Musialek J, Filip P, Nieslanik J. Titanium-nickel shape memory clamps in small bone surgery. Arch Orthop Trauma Surg 1998;117:341–344.

Reading List

Castleman LS, Motzkin SM. The Biocompatibility of Nititnol. In: Williams DF, editor. Biocompatibility of Clinical Implant Materials volume I. CRC Press; 1981. p 129–154.

Kousbrock R. Shape Memory Alloys, In: Ducheyne P, Hastings GW, editors. Metal and Ceramic Biomaterials Volume II. CRC Press; 1984. p 63–90.

Otsuka K, Wayman CM, editors. Shape Memory Materials. Cambridge University Press; 1998.

Nishiyama Z, Fine ME, Meshii M, Wayman CM, editors. Martensitic Transformation. London: Academic Press; 1978.

Jena AK, Chaturvedi MC. Phase Transformation in Materials. New Jersey: Prentice Hall; 1992.

Duerig TW, Melton KN, Stockel D, Wayman CM. Engineering Aspects of Shape Memory Alloys. London: Butterworth-Heinemann; 1990.

Wayman CM, Bhadeshia HKDH. Phase Transformations, Nondiffusive. Cahn RW, Hassen P, editors. Physical Metallurgy. 4th ed. Amsterdam: North-Holland; 1996. p 1507–1554.

Filip P. Titanium–Nickel Shape Memory Alloys in Medical Applications. In: Brunette DM, Tengvall P, Textor M, Thomsen P, editors. Titanium in Medicine. Berlin: Springer; 2001. p 53–86.

Perkins J, editor. Shape Memory Effects in Alloys. New York: Plenum Press; 1975.

See also HIP JOINTS, ARTIFICIAL; SPINAL IMPLANTS.

AMBULATORY MONITORING

HAIBO WANG
AHMAD ELSHARYDAH
RANDALL CORK
JAMES FRAZIER
Louisiana State University

INTRODUCTION

Due to advances in technology, especially computer sciences, ambulatory monitoring with medical instruments has increasingly become an important tool in the diagnosis of some diseases and medical conditions. Some devices used or in development for current clinical practice are shown in Table 1.

The ideal device for ambulatory monitoring should be consistently sensitive, accurate, lightweight, noninvasive, and easy to use. The Holter monitor is a popular device for ambulatory monitoring. Therefore, this article will start with a discussion of the Holter monitor.

AMBULATORY MONITORING WITH A HOLTER DEVICE

A Holter monitor is a continuous recording of a patient's ecocardiogram (ECG) for 24 h as shown in Fig. 1. It was named in honor of Norman J. Holter for his contribution in creating the world's first ambulatory ECG monitor in 1963 (1). Since it can be worn during the patient's regular daily activities, it helps the physician correlate symptoms of dizziness, palpitations, and syncope with intermittent

Table 1. Current Devices for Ambulatory Monitoring

Devices	Uses
Holter monitoring	Cardiac arrhythmia and ischemia
Ambulatory BP monitoring	Hypertension and hypotension
Ambulatory glucose monitoring	Hyperglycemia and hypoglycemia



Figure 1. Holter monitor.

cardiac arrhythmias. When compared with the ECG, which lasts < 1 min. The Holter monitor is more likely to detect abnormal heart rhythm. It can also help evaluate the patient's ECG during episodes of chest pain due to cardiac ischemia. The common clinical applications for Holter monitor are summarized in Table 2 (2,3).

The basic components of a Holter monitor include at least a portable ECG recorder and a Holter analyzer (scanner). Functional characteristics of both components have improved dramatically since the first Holter monitor was developed > 40 years ago.

Portable ECG Recorder

The recorder is a compact, light-weight device used to record an ambulatory patient's three or more ECG leads, typically for 24 h for dysrhythmia or ischemia detection. There are two types of the recorder available on the market: the classical cassette type (tape) or the newer digital type (flash memory card). The cassette recorder uses magnetic tape to record ECG information. The tape needs to be sent to the physician's office for analysis with a scanner to produce a patient's report. The problems with this type of recorder are its limited memory for ECG recording, its inability to transmit ECG information to the service center digitally, and its difficulty in processing the information with computer software. Therefore, it normally takes days to produce a monitoring report for a patient.

The newer digital recorder has an increased memory compared to the classical cassette type, making it possible to extend the monitoring time beyond 24 h if indicated. More importantly, the recorded signs are digital, which can be transmitted to the service center or on-call physician by digital transmission system via a phone line, email, or wireless technology, and can be processed rapidly with computer software. Therefore, the patient's report will be available for the patient's physician much sooner. If indicated, treatment can be started without delay. Additionally, a patient event button has been incorporated in some of newer recorders to allow correlation of symptoms and activity with ECG changes to obtain more clinical data useful for making a correct clinical diagnosis.

Another new development is the Cardiac Event Monitoring (CEM), which is similar to Holter monitor for recording an ambulatory patient's ECG. The difference between them is that the CEM is an event-triggered device, only recording the patient's ECG when they experiences a detectable symptoms (4). As a result, the CEM makes prolonged monitoring possible even with a limited recorder memory.

Table 2. Clinical Application of the Holter Monitor

1. Evaluation of symptomatic events: dizziness, syncope, heart palpitations, fatigue, chest pain, shortness of breath, episodic diaphoresis.
2. Detection of asymptomatic dysrhythmia: asymptomatic atrial fibrillation.
3. Evaluation of rate, rhythm or ECG interval changes during drug therapy.
4. Evaluation for specific clinical situations: postmyocardial infarction, postcoronary bypass surgery, postpercutaneous transluminal coronary angioplasty, postpacemaker implant, first or second degree heart block, possible pacer malfunction, automatic implanted defibrillator functions.
5. Evaluation of ECG changes during specific activities.

Holter Analyzer (Scanner)

There are different types of Holter analyzer systems currently available. The original system for analyzing the Holter cassette was a scanner with manual observer detection. With manual observer detection, the trained technician watches for audiovisual clues of abnormal beats while playing the tape back at 60–120 times real time. The process is time consuming. It requires a skilled technician who can withstand high boredom and fatigue levels to minimize possible human error rate.

The modern Holter analyzer system has been revolutionized due to the application of computer technologies. It is available in a variety of options, such as auto analysis and complete editing capabilities. Some of the newer systems provide easy-to-use professional features that allow rapid review of recorded information, producing a fast, accurate report.

Future Development

Ambulatory Holter monitoring is a valuable tool in patient care and is becoming more and more popular. Integration of computer technology, digital technology, wireless technology, and nanotechnology may lead to an ideal Holter device, which is minimal in size and weight, user-friendly, noninvasive, sensitive and accurate, wirelessly connected to a physician on-call center, and with automatic data analysis capacity. Newer analysis techniques involving fuzzy logic, neural networks and genetic algorithms will also enhance automatic detection of abnormal ECG. Hopefully, such an ideal ambulatory Holter monitor will be available in the near future.

AMBULATORY BLOOD PRESSURE MONITORING

Introduction

An ambulatory blood pressure monitoring device is a noninvasive instrument used to measure a patient's 24 h ambulatory blood pressure as shown in Fig. 2. The first device was developed by Hinman in 1962 (5). He used a



Figure 2. Ambulatory blood pressure monitoring device.

microphone placed over the brachial artery distal to a compression cuff and a magnetic tape recorder for recording of onset and disappearance of Korotkoff sounds. It weighed ~ 2.5 kg and was obviously inconvenient for an ambulatory patient to use. The first fully automatic device was developed, using compressed carbon dioxide to inflate the cuff. An electronic pump was introduced later and automatic data recording systems have been used since 1979.

Since then, the techniques for ambulatory blood pressure monitoring have been improved significantly. The modern device is light-weighted, compact in size, accurate, and automated in nature. It can be belt-worn and battery powered. The newest generation available in the current market is fully automatic, microprocessor-controlled, digitalized in memory, and extremely light weight (< 500 g).

Basic Techniques

The techniques for ambulatory blood pressure monitoring include auscultation, cuff oscillometry, and volume oscillometry.

Auscultation is a technique based on detection of onset and disappearance of Korotkoff sounds via a piezoelectric microphone taped over an artery distal to a deflating compression cuff. The Korotkoff sound is produced by turbulent flow while arterial blood flows through a segment of artery narrowed by a blood pressure cuff. The pressure at the onset of sound corresponds to systolic blood pressure, and at the disappearance of the sound to diastolic pressure. The advantage of this technique is simplicity, but the device is sensitive to background noise. This technique may also underestimate systolic pressure due to his flow dependency.

Cuff oscillometry is a technique based on detection of cuff pressure oscillations or vibrations to calculate systolic and diastolic values using an algorithmic approach. The systolic pressure corresponds to the cuff pressure at which oscillations first increase, and the diastolic pressure corresponds to the cuff pressure at which oscillations cease to decrease. The endpoints are estimated by analysis of oscillation amplitudes and cuff pressures. Different algorithms are used by different manufacturers, which may result in variability among different devices. This technique is insensitive to background noise, but arm movement may cause an errant reading. It may overestimate systolic pressure because of transmitted cuff pressure oscillations.

Volumetric oscillometry is a technique based on detection of finger volume pulsations under a cuff. The pressures are estimated as the cuff pressures at which finger volume oscillations begin (systolic pressure) and become maximal (mean pressure). Diastolic pressure is then derived from the known systolic and mean pressures. One problem with this technique is that this finger pressure may have a variable relationship to the brachial pressure. Another problem is that the technique cannot directly assess diastolic pressure.

Despite some problems associated with the mentioned techniques, their accuracy has been confirmed by validation testing using mercury sphygmomanometry and intraarterial measurement. The discrepancy is generally < 5 mmHg (0.399 kPa) between ambulatory devices and readings taken by trained professionals.

Patients are advised to wear the monitor for a period of 24 h, preferably during a normal working day. The monitor is preprogrammed to measure and record blood pressure at certain time intervals, preferably every 15–20 min during daytime hours and every 20–30 min during nighttime hours. Patients are also advised to document their activity during the testing period for assessment of any stress-related blood pressure.

The monitoring device consists of a small central unit and an attached cuff. The central unit contains a pump for cuff inflation and deflation, and the memory device, such as tape or digital chip, for recording. The time intervals between the measurements, maximal and minimal inflation pressures, and deflation rate are programmable according to the physician's order. The recording pressures can be retrieved from the tape or memory chip for analysis. Due to recent applications of digital technology and advanced software programs, a large amount of data can be stored in a small chip, and analysis can also be done automatically to generate a patient's report for the physician's use. A complete patient's report normally contains all blood pressure readings over a 24 h period, heart rates, mean arterial pressures, and statistic summaries for daytime, nighttime, and 24 h periods.

New Clinical Concepts Related to Ambulatory Blood Pressure Monitoring

A few new considerations related to ambulatory blood pressure monitoring have emerged. These include blood pressure load, pressure dipping, pressure variability, and white-coat hypertension. Health professionals need to understand these concepts in order to properly interpret or use data collected from monitoring.

Blood Pressure Load. This is defined as the proportion of the 24 h pressure recordings above the thresholds for waking and sleep blood pressure. The threshold commonly used for estimating the pressure load during waking hours is 140/90 and 120/80 mmHg (15.99/10.66 kPa) during sleep. Blood pressure load is helpful in the diagnosis of hypertension and in the prediction of end-organ damage. It has been considered closely correlated with left ventricle hypertrophy. It has been reported that the incidence of left ventricular hypertrophy is $\sim$ 90% in untreated patients with systolic blood pressure loads $>$ 50%, and $\sim$ 70% with diastolic blood pressure loads $<$ 40% (6,7).

Dipping and Circadian Blood Pressure Variability. Dipping is a term used to describe the circadian blood pressure variation during 24 h ambulatory blood pressure monitoring. In normotensive patients there is circadian blood pressure variability. Typically, the peak blood pressures occur around 6 a.m., and then taper to lower levels during the evening hours and further at night with the lowest levels between 2 and 4 a.m.. A patient whose blood pressure drops by at least 10% during sleep is considered normal (a dipper), and by $<$ 10% abnormal (nondipper). In comparison to dippers, nondippers have been reported associated with higher prevalence of left ventricular hypertrophy, albuminuria, peripheral arterial changes, and cerebral lacunae. Nondippers have also been reported to have increased cardiovascular mortality rates (8).

White-Coat Hypertension. This is a condition in which blood pressure is persistently elevated in the presence of a doctor, but falls to normal levels when the patient leaves the medical facilities. Measurement by a nurse or trained nonmedical staff may reduce this effect. Because decisions regarding treating hypertension are usually made on the basis of isolated office blood pressure reading, a doctor may incorrectly diagnose this group of patients as sustained hypertension and prematurely start the therapy. This phenomenon has been reported in 15–35% of patients currently diagnosed and treated as hypertensive. However, white-coat hypertension can be easily detected by either ambulatory blood pressure monitoring or self-monitoring at home. It may or may not be benign, requiring definitive outcome studies to rule out any end-organ damages. It also requires continued surveillance by self-monitoring at home and repeat ambulatory blood pressure monitoring every 1–2 years (9,10).

Interpretation of Ambulatory Blood Pressure Profile

Normal ambulatory blood pressure values for adults are currently defined to be $<$ 135/85 mmHg (17.99/11.33 kPa) during the day, $<$ 120/75 mmHg (15.99/9.99 kPa) during the night, and $<$ 130/80 mmHg (17.33/10.66 kPa) over 24 h. Daytime and night time blood pressure loads should be less 20% above normal values. Mean day-time and nighttime (sleep) blood pressure measurements should differ by at least 10%. The ambulatory blood pressure profile should also be inspected in relation to diary data and time of drug therapy.

Indications of Ambulatory Blood Pressure Monitoring

Although ambulatory blood pressure monitoring was originally developed as a research tool, it has widely been applied in clinical practice to help diagnose and manage hypertensive patients. It is indicated to rule out white-coat hypertension, to evaluate drug-resistant hypertension, to assess symptomatic hypertension or hypotension, to diagnose hypertension in pregnancy, and to assess adequacy of blood pressure control in patients at high risk of cardiovascular diseases.

White-Coat Hypertension. Office-based blood pressure measurement cannot differentiate sustained hypertension from white-coat hypertension. Historical appraisal and review of self-recorded blood pressures may aid in identification of patients with white-coat hypertension. However, ambulatory blood pressure monitoring is more effective in this clinical scenario to rule out white-coat hypertension. Recognition and proper management of patients with white-coat hypertension may result in a reduction in medication use and eliminate related cost and side effects. Although white coat hypertension may be a prehypertensive state and can eventually evolve to sustained hypertension, data collected from ambulatory blood pressure monitoring suggest, patients with white coat hypertension who maintain low ambulatory blood pressures ($<$ 130–135/80 mmHg) have a low cardiovascular risk status and no demonstrable end-organ damage (11).

Drug-Resistant Hypertension. Drug resistant hypertension is defined as a condition when adequate blood pressure control ($<$ 140/90 mmHg) (18.66/11.99 kPa) cannot be achieved despite the use of appropriately combined antihypertensive therapies in proper dosages for a sufficient duration. Ambulatory blood pressure monitoring helps evaluate whether additional therapy is needed. The causes include true drug-resistant hypertension as well as other conditions such as superimposition of white-coat hypertension on existing hypertension, patient's noncompliance, pseudohypertension secondary to brachial artery calcification, and sleep apnea and other sleep disorders. Ambulatory blood pressure monitoring can help differentiate the true drug resistant hypertension from the above-mentioned conditions (12).

Episodic Hypertention. A single office-based measurement of blood pressure may or may not detect episodic hypertension as in pheochromocytoma. In this clinical scenario the 24 h ambulatory blood pressure monitoring is a useful diagnostic tool. It is indicated if a patient's symptoms or signs are suggestive of episodic hypertension (13).

Borderline or Labile Hypertension. Patients with borderline hypertension often demonstrate only some (but not all) elevated blood pressure readings in office-based measurement, 24 h ambulatory blood pressure monitoring can benefit these patients and provide a useful diagnostic information for physician's use (14).

Hypertension with End-Organ Damage. Patients who exhibit worsening of end-organ damage may suggest inadequate 24 h blood pressure control. Occasionally, those patients may demonstrate adequate blood pressure control based on the office-based measurements. In this condition, a 24 h blood pressure monitoring is needed to rule out inadequate blood pressure control, which is associated with worsening of end-organ damage (15).

Hypentensive Patients with High Risk of Cardiovascular Events. Some hypertensive patients are at particularly high risk of cardiovascular events, such as those with diabetes and/or past stroke. Those patients require rigorous blood pressure control over 24 h. Ambulatory blood pressure monitoring can be applied to assess the 24 h control (15).

Suspected Syncope or Orthostatic Hypotension. Transient hypotensive episodes and syncope are difficult to assess with the office-based blood pressure measurements, but are readily recorded with ambulatory blood pressure monitoring. Therefore, if symptoms and signs are suggestive of syncope or orthostatic hypertension, patients can benefit from 24 h blood pressure monitoring, especially in conjuction with Holter monitoring (15).

Hypertension in Pregnancy. About 10% of pregnancies may be complicated by hypertension. At the same time, white-coat hypertension may affect up to 30% of patients. It is important to differentiate true hypertension in pregnancy from white-coat hypertension, to avoid unwarranted hospitalizations or medication use. In this clinical scenario, ambulatory blood pressure monitoring would help to rule out white-coat hypertension and identify pregnancy-induced hypertension (16).

Clinical Research. Since ambulatory blood pressure monitoring can provide more samples of blood pressure measurements, data from this device is therefore much more statistically significant than a single isolated office-based reading. Therefore, statistical significance of clinical studies can possibly be achieved with smaller numbers of patients. This is very important for the efficient study of new therapeutic agents (17).

Limitations of Ambulatory Blood Pressure Monitoring

Although ambulatory blood pressure monitoring has been proved useful in the diagnosis and management of hypertension, the technology remains underused secondary to lack of experience in interpretation of results, unfamiliarity with devices, and some economic issues. Adequate staff training, regular calibration of devices, and good quality control are required. The patient's diary of daily activities and time of drug treatment are also needed for proper data analysis and interpretation.

Future Development

Like any other ambulatory device, an ideal noninvasive ambulatory blood pressure monitoring device should be user-friendly, light-weight, compact in size, digitalized for automated data management, and low in cost. Application of newer technologies will make such devices available, hopefully, in the near future.

AMBULATORY BLOOD GLUCOSE MONITORING

Introduction

Diabetes is one of most common diseases suffered by millions of people around the world. It is essential to monitor blood glucose to ensure overall adequate blood glucose control. Traditional standard blood glucose monitoring devices require invasive blood samplings and are therefore unsuitable for ambulatory blood glucose monitoring. Development of minimally invasive or noninvasive ambulatory glucose monitoring devices that provide accurate, near-continuous measurements of blood glucose level have the potential to improve diabetes care significantly. Such devices will provide information on blood glucose levels, as well as rate and direction of change, which can be displayed to patients in real-time and be stored for later analysis by physicians. Guardian RT system recently developed by Medtronic MiniMed is an example (Fig. 3). It provides continuous real-time glucose readings around the clock. Due to the huge market potential, many biomedical and medical instrument companies are developing similar devices for ambulatory glucose monitoring. Several innovative devices have recently been unveiled; many more are still in development. It is expected that some of them will be eventually U. S. Food and Drug Administration (FDA) approved as a replacement for standard blood glucose monitors, providing patients with a new option for long-term, daily monitors in the near future. The FDA is concerned about the accuracy of ambulatory continuous glucose monitoring devices when compared to the accuracy of standard monitoring devices. This issue will be eventually eliminated as related technologies become more and more mature. Technically, a typical ambulatory glucose monitoring device consists of a glucose sensor to measure glucose levels and a memory chip to record data information.



Figure 3. Ambulatory glucose monitoring with guardian real time system (Medtronic MiniMed).

Glucose Sensors

The glucose sensors for ambulatory glucose monitoring devices are either minimally invasive or completely noninvasive. A variety of technologies have emerged over the past decade aiming at development of ideal glucose sensors suitable for ambulatory monitoring.

A typical minimally invasive ambulatory continuous glucose sensor is a subcutaneous device developed by Minimed, Inc. (18). The sensor is designed to be inserted into a patient's abdominal subcutaneous tissue. It measures glucose levels every 10 s and records means $>$ 5 min intervals. The technology involves measurement of glucose levels of interstitial fluid via the subcutaneous sensor. The blood glucose levels are then derived from the measured interstitial fluid glucose levels. The detection mechanism involves use of a low fluorescence molecule. Electrons are transferred from one part of the molecule to another when excited by light. This prevents bright fluorescence from occurring (19). When bound to glucose, the molecule prevents the electrons from interfering with fluorescence, and the molecule becomes a bright fluorescent emitter. Therefore, the glucose levels can be determined based on the brightness of fluorescence. The glucose information will be transmitted from the sensor to a watch-like device worn on the wrist. Using this type of sensor, two devices have been developed by the company. One is a device that can be worn by the patient for a few days to record the glucose levels for the physician's analysis. The other is a device that can alert patients of impending hyperglycemia or hypoglycemia if the glucose levels go beyond the physician's predetermined upper and lower limits. The sensor can also work in conjunction with an implanted insulin pump, creating a "biomechanical" or artificial pancreas in response to the change at the glucose levels (20). It is predictable that such a biomechanical pancreas will eventually benefit millions of diabetic patients whose glucose control is dependant on insulin.

Complete noninvasive sensors for ambulatory glucose monitoring are even more attractive since they do not need any blood or interstitial samples to determine glucose levels. Several such sensors have recently been developed based on different technologies. For example, a glucose sensor that can be worn like a wristwatch has been developed by Pendragon Medical AG (Zurich, Switzerland). This sensor can continuously monitor blood glucose level without the need for a blood sample. It is based on impedance spectroscopy technology (21). The principle of this technology relates to the fact that blood glucose changes produce significant conductivity changes, causing electric polarization of cell membranes. At the same time, the sensor generates an electronic field that fluctuates according to the electrical conductivity of the body. A micro antenna in the sensor then detects these changes and correlates them with changes in serum glucose. With this technology, blood glucose levels can be monitored noninvasively in real time. Another promising noninvasive sensor is based on the possibility of measuring glucose by detecting small changes in the retinal capillaries. By scanning the retinal microvasculature, the sensor can directly measure glucose levels in aqueous humor using a reflectometer. Recently, a plastic thin sensor, which can be worn like a contact lens, has been innovated (22,23). The sensor changes its color based on the concentration of glucose, from red, which indicates dangerously low glucose levels, to violet, which indicates dangerously high glucose concentrations. When glucose concentration is normal, the sensor is green. Integration of the sensor material into commercial contact lenses may also be possible with this technology.

Memory Chips

Memory chips are used to record glucose data information for later use by the physician. The digital chips have many advantages, such as compact size, large memory, easy data transmission via wire or wireless, and possible autoanalysis with computer software. Patients can also upload their glucose data from digital memory chips to web-based data management systems, allowing diabetic patients and their health care providers to analyze and communicate glucose information using the internet.

Significances of Ambulatory Glucose Monitoring

Ambulatory glucose monitoring can provide continuous data on blood glucose levels. Such data can improve diabetic care by enabling patients to adjust insulin delivery according to the rate and direction of blood glucose change, and by warning of impending hypoglycemia and hyperglycemia. Doctors can use ambulatory glucose monitoring to help diagnose problematic cases, fine-tune medications, and get tighter control of blood glucose levels for high risk patients. Obviously, the monitoring will improve overall blood glucose control, reducing short-term adverse complications and delaying onset of long-term serious complications, such as end-stage renal disease, heart attack, blindness, stroke, neuropathy, and lower extremity amputation.

In addition, continuous ambulatory glucose monitoring is a key step toward the development of artificial pancreas, which could deliver insulin automatically in response to blood glucose levels. It is expected that such an artificial pancreas would greatly benefit many diabetic patients and provide them new hope for better quality of life.

Future Development

Although many continuous ambulatory glucose monitoring devices are still in the stage of clinical trials, there is little doubt as to the value of the devices in management of diabetic patients. It is expected that millions of diabetic patients will be benefited once such devices are widely available. At the same time, introduction of more and more new devices highlights the need for careful evaluation to ensure accuracy and reliability. Cooperation between the manufacturers and physicians to fine-tune the technology will eventually lead to approval of the devices by the FDA to replace traditional invasive standard glucose monitoring. Technology for continuous ambulatory glucose monitoring is also required to make an artificial pancreas, which would offer great hope for millions of patients with diabetes.

CONCLUSION

Ambulatory monitoring has increasingly provided a powerful alternative tool to diagnose and manage some diseases. Continuous advancement in a variety of technologies provides more and more innovative ambulatory devices to serve the patients' need. Applications of information technology and specialized software tools make autotransmission and autoanalysis of ambulatory monitoring data possible. Clinicians will be able to monitor their ambulatory patients distantly without a hospital or office visits. In addition, integration of the technology of continuous ambulatory monitoring with an implantable automatic therapeutic pump may create a biomechanical system in response to specific abnormal changes. The artificial pancreas currently in development is a typical example for such hybrid devices. Such devices will be available in the market in the near future.

BIBLIOGRAPHY

Cited References

1. Holter NJ. New method for heart studies: Continuous electrocardiography of active subjects over long periods is now practical. Science 1961;134:1214–1220.
2. Heilbron EL. Advances in modern electrocardiographic equipment for long-term ambulatory monitoring. Card Electrophysiol Rev 2002;6(3):185–189.
3. Kadish AH, et al. ACC/AHA clinical competence statement on electrocardiography and ambulatory electrocardiography: a report of the ACC/AHA/ACPASIM task force on clinical competence. Circulation 2001;104:3169–3178.
4. Kinlay S, et al. Event recorders yield more diagnoses and are more cost-effective than 48 hour Holter monitoring in patients with palpitations. Ann Intern Med 1996;124:16–20.
5. Hinman AT, Engel BT, Bickford AF. Portable blood pressure recorder accuracy and preliminary use in evaluation intradaily variations in pressure. Am Heart J 1962;63:663–668.
6. Zachariah PK, et al. Blood pressure load: A better determinant of hypertension. Mayo Clin Proc 1998;63:1085–1091.
7. White WB, Dey HM, Schulman P. Assessment of the daily blood pressure load as a determinant of cardiac function in patients with mild-to-moderate hypertension. Am Heart J 1989;118:782–795.
8. Pickering TG. The clinical significance of diurnal blood pressure variations: dippers and nondippers. Circulation 1990;81:700–702.
9. Verdecchia P, et al. White-coat hypertension: not guilty when correctly defined. Blood Press Monit 1998;3:147–152.
10. Pickering TG, et al. How common is white coat hypertension. Hypertension 1988;259:225–228.
11. Palatini P, et al. Target-organ damage in stage-1 hypertensive subjects with white coat and sustained hypertension: results from the HARVEST study. Hypertension 1998;31:57–63.
12. Brown MA, Buddle ML, Martin A. Is resistant hypertension really resistant ? Am J Hypertens 2001;14:1263–1269.
13. Myers MG, Haynes RB, Rabkin SW. Canadian hypertension society quidelines for ambulatory blood pressure monitoring. Am J Hypertens 1999;12:319–331.
14. Pickering T. for the American Society of Hypertension ad-hoc Panel. Recommendations for the use of home (self) and ambulatory blood pressure monitoring. Am J Hypertens 1996;9:1–11.
15. O'Brien E, et al. Use and interpretation of ambulatory blood pressure monitoring: recommendations of the British Hypertension Society. BMJ 2000;320:1128–1134.
16. Halligan A, et al. Twenty-four-hour ambulatory blood pressure measurement in a primigravid population. J Hypertens 1993;11:869–873.
17. Conway J, et al. The use of ambulatory blood pressure monitoring to improve the accuracy and reduce the numbers of subjects in the clinical trials of antihypertensive agents. J Clin Exper Hypertension 1986;8:1247–1249.
18. Cross TM, et al. Performance evaluation of the MinMed continuous glucose monitoring system during patient home use. Diab Technol Ther 2000;2:49–56.
19. Pickup JC, Shaw GS, Claremont DJ. *In vivo* molecular sensing in diabetes mellitus: an implantable glucose sensor with direct electron transfer. Diabetes 1989;32:213–217.
20. Jaremko J, Rorstad O. Advances toward the implantable artificial pancreas for treatment of diabetes. Diabs Care 1998;21:444–450.
21. Caduff A, et al. First human experiments with a novel noninvasive, non-optical continuous glucose monitoring system. Biosens Bioelecs 2003;19:209–217.
22. Badugu R, Lakowicz JR, Geddes CD. Ophthalmic glucose sensing: a novel monosaccharide sensing disposable and colorless contact lens. Analyst (England) 2004;129:516–521.
23. Badugu R, Lakowicz JR, Geddes CD. Ophthalmic glucose monitoring using disposable contact lenses—a review. J Fluoresc 2004;14:617–633.

See also ARRHYTHMIA ANALYSIS, AUTOMATED; BIOTELEMETRY; HOME HEALTH CARE DEVICES; PACEMAKERS.

ANALYTICAL METHODS, AUTOMATED

LAKSHMI RAMANATHAN
Mount Sinai Medical Center
LASZLO SARKOZI
Mount Sinai School of Medicine

INTRODUCTION

The chemical composition of blood, urine, spinal fluid, sweat, provides a wealth of information on the well being or illness of the individual. The presence, concentration, and activity of chemical constituents are indicators of various organ functions. Concentrations higher or lower than expected sometimes require immediate attention. Some of the reasons to analyze body fluids:

1. Screening of an apparently healthy population for unsuspected abnormalities.
2. Confirming or ruling out a diagnosis.
3. Monitoring changes during treatment, improvement of condition or lack of improvement.
4. Detecting or monitoring drug levels for diagnosis or maintenance of optimal therapeutic levels.

By the 1950s, demands of clinicians for laboratory tests increased rapidly. Classical methods of manual laboratory techniques could not keep up with these demands. The cost of performing large numbers of laboratory tests by manual methods became staggering and the response time was unacceptable.

The article in the first edition of this Encyclopedia published in 1988 describes the history of laboratory instrumentation during the previous three decades (1). Reviewing that long list of automated instruments, with the exception of a few, all became museum pieces. During the last 15 years the laboratory landscape changed drastically. In addition, new group of automated instruments were introduced during this period. They were developed to perform bedside or near patient testing, collectively called Point of Care Testing instruments. In this period in addition to new testing instruments, perianalytical instrumentation for specimen handling became available. Their combined result is increased productivity and reduction of manpower requirements, which became imperative due to increased cost of healthcare and dwindling resources.

This article will present some financial justification of these investments.

PATIENT PREPARATION, SPECIMEN COLLECTION, AND HANDLING

The prerequisites for accurate testing include proper patient preparation, specimen collection, and specimen handling. Blood specimens yield the most information about the clinical status of the patient though in many cases urine is the preferred sample. For specialized tests, other body fluids that include sweat and spinal fluid are used. When some tests, such as glucose and lipids, require fasting specimens, patients are prepared accordingly.

Common errors affecting all specimens include the following:

Inaccurate and incomplete patient instructions prior to collection.
Wrong container/tube used for the collection.
Failure to label a specimen correctly.
Insufficient amount of specimen to perform the test.
Specimen leakage in transit due to failure to tighten specimen container lids.
Interference by cellular elements of blood.

Phlebotomy techniques for blood collection have considerably improved with better gauge needles and vacuum tubes for collection. The collection tubes are color coded with different preservatives so that the proper container can be used for a particular analyte. The cells should be separated from the serum by centrifugation within 2 h of collection. Grossly or moderately hemolyzed specimens may be unsuitable for certain tests. If not separated from serum or plasma, blood cells metabolize glucose and produce a false decrease of $\sim$5%/h in adults. The effect is much greater in neonates (2). If there is a delay in separating the cells from the serum, the blood should be collected in a gray top tube containing sodium fluoride as a preservative that inhibits glycolysis.

Urine collection is prone to errors as well, some of which include (3):

Failure to obtain a clean catch specimen.
Failure to obtain a complete 24 h collection/aliquot or other timed specimen.
No preservative added if needed prior to the collection.

Once specimens are properly collected and received in the clinical laboratory, processing may include bar coding, centrifugation, aliquoting, testing and reporting of results.

AUTOMATED ANALYZERS

A large variety of instruments are available for the clinical chemistry laboratory. These may be classified in different ways based on the type of technology applied, the test menu, the manufacturer, and the intended application. Depending on the size of the laboratory, the level of automation varies. Clinical chemistry analyzers can be grouped according to throughput of tests and diversity of tests performed and by function, such as immunoassay analyzers, critical care blood gas analyzers, and urinalysis testing systems. Point of Care analyzers vary in terms of accuracy, diversity and menu selection.

Some of the features to consider while evaluating low or high volume analyzers are listed below:

Test menu available on instrument:

  Number of different measured assays onboard simultaneously.
  Number of different assays programmed/calibrated at one time.
  Number of user-defined (open) channels.

Reagents:

  Preparation of reagents if any.
  Storage of reagents.
  On board stability.
  Bar-coding for inventory control.

Specimen volume:

  Minimum sample volume.
  Dead volume.

Instrument supplies:

  Use of disposable cuvettes.
  Washable/reusable cuvettes.

Clot detection features along with quantitation of hemolysis and turbidity detection.
Auto dilution capabilities of analyzer.
Frequency of calibration.
Quality control requirements.
Stat capability.
LIS interface.
Maintenance procedures on instrument; anticipated downtime.
Analyzer costs expressed in cost per reportable test.

Our goal is not to review every analyzer available on the market. We have chosen a few of the instruments–vendors. This is by no means endorsing any particular vendor, but merely discussing some of the most frequently utilized features or describing our personal experiences. The College of American Pathologists has provided excellent surveys of instruments and the reader is referred to those articles for more complete details (4).

CHEMISTRY ANALYZERS

Routine chemistry analyzers have broad menus capable of performing an average of 45 (20 to >70) different on board tests simultaneously, selected from an available menu of 26

Table 1. Automated Analyzers from Different Manufacturers

Instrument Type	Generic Menu	Vendor
Routine chemistry	Electrolytes, BUN, Glucose, Creatinine, Protein, Albumin, Lipids, Iron, Drugs of abuse, Therapeutic drug monitoring, etc.	Abbott, Bayer, Beckman Dade, J&J, Olympus, Roche
Immunoassays	Tumor markers, Cardiac markers, Anemia, B12, Folate and misc. Endocrine tests	Abbott, Bayer, Beckman, DPL, J&J, Olympus, Roche
Critical Care	Blood gases, Cooximetry, Electrolytes Ionized calcium, Lactate, Hematocrit	Abbott, Bayer, Instrumentation Lab, Nova, Radiometer, Roche

to >100 different analytes (5,6). Selection is based on test menu, analytic performance, cost (reagents, consumables and labor), instrument reliability (downtime etc.), throughput, and ease of use, customer support and robotic connectivity, if needed. Some automated analyzers from different manufacturers are listed in Table 1.

General Chemistry

Virtually all automated chemistry analyzers offer random access testing, multiple tests can be performed simultaneously and continuously. This is different from batch-mode instruments that perform a single test on a batch of samples loaded on the instrument (Abbott TDX and COBAS Bio). Many analyzers are so-called "open systems" that use reagents from either the instrument manufacturer or different vendors. The advantage of these systems being that the customer has a choice of reagent vendors and the reagent can be selected based on performance and cost.

An example of a closed system is a line of analyzers manufactured by Ortho Clinical Diagnostics. The Vitros 950 and the analyzers in this category use a unique, dry chemistry film-based technology developed by Kodak. The slide is a dry, multilayer, analytical element coated on a polyester support. A 10 μL drop of patient sample is deposited on the slide and is evenly distributed by the spreading layer to the underlying layers that contain the ingredients for a particular chemical reaction.

The reaction slide (Fig. 1.) for albumin shows the reactive ingredient is the dye (bromcresol green), which is in the reagent layer. The inactive ingredients that include polymeric beads, binders, buffer, and surfactants are in the spreading layer. When the specimen penetrates the reagent layer, the bromcresol green (BCG) diffuses to the spreading layer and binds to albumin from the sample. This binding results in a shift in wavelength of the reflectance maxima of the free dye. The color complex that forms is measured by reflectance spectrophotometry. The amount of albumin-bound dye is proportional to the concentration of albumin in the sample. Once the test is completed the slide is disposed into the waste container.

Some manufacturers close their system by labeling their individual reagent packs with unique barcodes, rejecting packs not distributed by them. Examples of "open systems" include analyzers manufactured by Olympus, Roche (Fig. 2.), Beckman, Dade and Abbott. Many instruments have both open and closed channels allowing greater flexibility in the use of reagents. In addition to diverse menus, open and closed channels, compatibility of analyzers



Figure 1. The Vitros 950 (J&J Diagnostics) slide is a dry, multilayer, analytical element coated on a polyester support. A drop of patient sample is deposited on the slide and is evenly distributed by the spreading layer to the underlying layers that contain the ingredients for a particular chemical reaction.

Figure 2. The Roche/Hitachi Modular^{TM} analytic system has a theoretical throughput of 3500–5000 tests or 150–250 samples/h. They test 24 different analytes simultaneously with a total menu of > 140 available tests.

with perianalytical technology is becoming an important feature.

Perianalytical systems include front-end automation with specimen processing and aliquoting, track systems or other technologies to move specimens between instruments in the laboratory, and robots to place specimens on and remove them from the analyzers.

Immunoassay Analyzers

Immunoassay systems are presently the fastest growing areas of the clinical laboratory where advances in immunochemical methodology, signal detection systems, microcomputers and robotic processing are taking place at an accelerated pace (7). At present, manufacturers have high volume immunoassay analyzers that can be modularly integrated along with chemistry and hematology analyzers into fully automated laboratory systems. In addition, expanding menus of homogeneous immunoassays allow integration into many laboratories using "open reagent kits" designed for use on automated clinical chemistry analyzers.

One of the several analyzers in this category is the Bayer Advia Centaur (Fig. 3.)

Of the different enzyme immunoassays (EIA) available, only the two homogeneous methods, EMIT and CEDIA have been easily adapted to fully automated chemistry analyzers (8–11). The other EIAs require a separation step to remove excess reagent that will interfere with the quantitation of the analyte. Abbott uses a competitive assay involving a fluorescent-labeled antigen that competes for a limited number of sites on antigen specific antibody. The amount of analyte is inversely proportional to the amount of fluorescence polarization. Chemiluminescence technology is used in the Bayer ACS and Roche Elecsys systems combines very high sensitivity with low levels of background interference. Essentially, it involves a sandwich immunoassay direct chemiluminometric technology, which uses constant amounts of two antibodies. The first antibody in the Lite Reagent is a polyclonal goat anticompound antibody labelled with acridinium ester. The second antibody in the Solid Phase is a monoclonal mouse anticompound antibody, which is covalently coupled to paramagnetic particles. A direct relationship exists between the amount of compound present and the amount of relative light units (RlU) detected by the system (Table 2).

Critical Care Analyzers

Blood gas measurements performed on arterial, venous, and capillary whole blood includes electrolytes and other tests in addition to the gases. These tests are listed in Table 3.

The Nova CCX series combines blood gas measurements with co-oximetry, electrolytes, a metabolic panel and hematology on 50 μL of whole blood. Several blood gas analyzers are utilizing the concept of "Intelligent Quality Management" whereby the analyzers run controls automatically at specified time intervals set by the operator. If a particular analyte is not within the specified range, the analyzer will not report out any patient results on the questionable test. Selected blood gas and critical care analyzers are listed in Table 4.

The unique specimen and turnaround time requirements for blood gases have prevented the tests from



Figure 3. The Bayer Advia Centour system has large on-board capacity for reagents and supplies combined with automated maintenance and monitoring features streamline operations. Categories such as fertility, therapeutic drug monitoring, infectious disease, allergy, cardiovascular, anemia, and oncology, therapeutic drug monitoring and thyroid tests are available. Up to 30 different reagent packs can be placed on the instrument. It has a throughput of 240 tests/h.

Table 2. Immunoassay Analyzers

Manufacturer	Model	Methodology
Abbott diagnostics	Axsym	FPIA, MEIA
	TDX, IMX	FPIA
	ADX	FPIA
	Architect	Chemiluminescence
Bayer Diagnostics	ACS 180	Chemiluminescence
	Centaur	Chemiluminescence
	Immuno 1	EIA
Beckman Coulter	Access	EMIT
	LX-20	EMIT
	DCI	Chemiluminescence
Boehringer Manheim ES-300	EIA	
	Elecsys	Chemiluminescence
Dade Behring	Opus Magnum	EIA
	Stratus	FIA
	ACA	EIA, Petinia
	ACA	EIA, turbidimetric
Diagnostic Product Corp.	Immulite	Chemiluminescence, EIA
Nichols Diagnostics CLS ID	Chemiluminescence	
Ortho Clinical	Eci	Chemiluminescence

Table 3. Test Menus for Critical Care Analyzers

Category	Tests Included
Blood gases	pH, pCO_2, pO_2 and other calculated parameters
Electrolytes	Sodium, potassium, chloride, bicarbonate, ionized calcium
Co-oximetry	Carboxyhemoglobin, methemoglobin, total hemoglobin, O_2 saturation
Metabolic panel	Glucose, blood urea nitrogen, creatinine, lactate
Hematology	Hematocrit, hemoglobin, activated clotting time

being performed in combination with general chemistry tests.

Point of Care Testing

Point of care testing (POCT) is defined as laboratory diagnostic testing performed close to the location of the patient. Recent advances over the last decade have resulted in smaller, more accurate devices with a wide menu of tests (12,13). Today POCT can be found from competitive sports to the prison system, from psychiatric counseling to pre-employment and shopping mall health screening. Use of POCT devices can be found in mobile transport vehicles such as ambulances, helicopters cruise ships and even the space shuttle.

The advantage of POCT is the ability to obtain extremely rapid laboratory results. However, it is necessary to be aware of the limitations of POCT devices in clinical practice. Venous blood samples often have to be drawn and sent to the main laboratory for confirmation if the results are not within a certain specified range. Another disadvantage of POCT is costs.

In compliance with the guidelines set by federal, state regulatory agencies and the College of American Pathologists (CAP), point of care testing programs are usually overseen by dedicated staff under the direction of the central laboratory. The responsibilities of the POCT staff include education and training of hospital staff, troubleshooting of equipment, maintaining quality control and

Table 4. Partial List of Critical Care Instruments

Vendor	Instrument
Abbott (iSTAT)	iSTAT
Bayer	200,300 800 series, Rapidpoint
Diametrics	IRMA
Instrumentation Lab	1600, 1700 series, Gem series
NOVA	Stat profile series, CCX
Radiometer	ABL series
Roche (AVL)	900 series, Omni and Opti series



Figure 4. The Roche Accu-Check is a small, easy to use blood glucose meter; it is widely used by our Point of Care Testing program. Test results are downloaded to the Laboratory Information System.

quality assurance standards. For a successful POCT program, the laboratory and clinical staff need to effectively work together.

The handheld Accu-Chek POCT device is shown on Fig. 4.

The most widely used point of care tests are bedside glucose testing, critical care analysis, urinalysis, coagulation, occult blood and urine pregnancy testing. Selected point of care devices are listed in Table 5. Other available POCT tests: cardiac markers, pregnancy, influenza A/B, Rapid Strep A, *Helicobacter pylori*, urine microalbumin and creatinine.

CLINICAL LABORATORY AUTOMATION

Historical Perspective

Along with innovations in instrumentation, automating perianalytical activities such as centrifuging, aliquoting, delivering specimens to the automated testing instruments, recapping and storing plays significant role in the modern clinical laboratory (14). Robotic systems that automate some or virtually all of the above functions are available. Automated laboratory and information systems offer benefits in terms of speed, operating efficiency, integrated information sharing and reduction of error.

Table 5. Selected Point of Care Devices

Test	Vendor
Bedside glucose test	Abbott (Medisense PCx) Bayer Ortho (Lifescan: One Touch) Roche
Critical care	Abbott (iSTAT) Bayer (Rapidpoint) IL (Gem series)
Coagulation	Abbott (iSTAT) Bayer (Rapid point) Hemosense ITC (Hemochron series) Medtronics (Hepcon) Roche (Coaguchek)
Fecal occult blood	Helena Smithkline Diagnostics
Urinalysis	Bayer (Multistix and Clintek) Roche (Chemstrip and CUA)

However, the individual needs of each laboratory have to be considered in order to select the optimum combination of instrumentation and perianalytical automation. For small laboratories, front-end work cell automation may be applied economically. For large commercial reference labs and hospital labs, total laboratory automation (TLA) is appropriate where samples move around the whole lab, or from place to place (15).

Clinical laboratory automation evolved with the development of the hematology “Coulter Counter” and the chemistry “AutoAnalyzer” in the 1950s. Automated cell counting by the Coulter involved placing a sample of whole blood in a hemocytometer and using a microscope to count the serial passage of individual cells through an aperture. Likewise, the automated analysis of patient samples for several chemistries dramatically changed the testing process in the chemistry laboratory.

In the 1980s in Japan, Dr. Sasaki’s group developed a point-to-point laboratory system that was based on overhead conveyor transportation, delivering specimens placed in 10 position racks (16). These initial designs are the basis of several automation systems available today.

Automation Options and System Design

Available options for automation include the following:

Interfaced instruments (some can be operated as stand alone analyzers and later linked to a modular system).

Modular instruments (including, processing, and instrument work cells).

Multidiscipline platforms (including multifunction instruments and multiwork cells).

Total laboratory automation robotics system that automates virtually all routine functions in the laboratory.

Automation system design usually rests on the needs of the user. However, the following concepts should be considered:

Modern information technology with hardware and operating systems that are vertically upgraded.

Transportation system management at both the local level (device) and overall system level.

Specimen tracking so that any specimen can be located in the automation system.

Reflex testing where an additional test can be performed at the same instrument or the specimen can be retrieved to another instrument.

Information systems agreement with the Laboratory Information System (LIS).

The ability to interface between the hospital LIS and the laboratory automation system (LAS) has been significantly enhanced by the implementation of the HL7 system-to-system interface. The National Committee on Clinical Laboratory Standards (NCCLS) has issued a proposal level standard (Auto 3 –P) that specifies the HLA interface as the system-to-system communications methodology for connecting an LIS and an LAS (17–21).

NCCLS Guidelines

Components of an optimized laboratory automation system per NCCLS may include:

Preprocessing specimen sorting.
Automated specimen centrifugation.
Automated specimen aliquoting.
Specimen–aliquot recapping/capping.
Specimen integrity monitoring.
Specimen transportation.
Automated specimen sampling.
Automated specimen storage and retrieval.

It is also recommended that process control software should support:

Specimen routing.
Reflex testing.
Repeat testing.
Rules based processing.
Patient data integration.

Available Automation Systems

In the mid-1990s, several laboratory automation technologies implemented hardware-based automation solutions that were centered on defining a limited number of specimen containers compatible with the transportation system. By limiting the number of specimen containers, the hardware can be better defined and more efficient. The original Coulter IDS automation system and the original Hitachi CLAS were based on fixed, rigid or hard-coded hardware technologies.

In the Hitachi CLAS and modular systems, the automation transportation devices use the Hitachi 747 five-place specimen container rack. In order to move the specimen container rack from one analyzer to the next, the automation system must carry along four other patient specimens. The requirement to carry along additional specimens along with the target specimen creates significant mathematical complexity in routing and scheduling of tests. The use of a simple specimen container per specimen carrier model allows the routing of an individual specimen to a workstation without interrupting the flow of other individual specimens in the system.

Total laboratory automation is used to describe the Beckman Coulter IDS system (22). We have two parallel systems in our laboratory (Fig. 5). The basic components include the inlet module, where samples are placed, a centrifuge, serum level sensor, decapping unit, aliquoter-labeler units, outlet units, refrigerated storage unit and a disposal unit. A line PC that interacts with the LIS and all the individual components of the automation system controls the entire system. Each of the automated instruments has their own individual attachment for the handling of specimens being received from the robotic system. View of our automated (perianalytical and analytical) clinical laboratory is shown on Fig. 6.

Work Cell Technologies

The work cell model can be divided into two basic approaches. The first includes all instruments from the same discipline (Chemistry). The second approach is the development of a platform that includes multiple disciplines. An example of this is the Bayer Advia work cell in which chemistry, hematology, immunoassay, and urinalysis processing can take place on one platform. However, this work cell does not have front-end specimen processing and handling capability. Several automated work cells are available in the market at the present time. They include Abbott (Abbott hematology work cell), Beckman-Coulter (Acel-Net work cell), Bayer (Advia work cell), Johnson and Johnson (lab interlink labframe select), and Roche (modular system). The work cell technology varies from simple specimen transportation to complex specimen management.

LABORATORY AUTOMATION-A FINANCIAL PERSPECTIVE

Several studies are being reported on the financial aspects of automation. The most significant impact has been the reduction in FTEs and improvement in turnaround time. A retrospective analysis of 36 years of the effects of initially automation followed by total laboratory automation in the clinical chemistry laboratory at Mount Sinai Medical Center indicated that workload was significantly increased with a reduction of personnel (23). We present these productivity changes in Table 6.

Increased productivity resulted in significant reduction of performing laboratory tests (Table 7).

The effect of increased productivity is illustrated by the drastic reduction of cost/test (Fig. 7)

CALCULATIONS FOR NET PRESENT VALUE OF THE MOUNT SINAI CHEMISTRY AUTOMATION PROJECT (FIG. 8)

Net Present Value

The Net Present Value (NPV) is the value of the net cash flows generated by the project in 1998 \$ (the year in which the project was initiated). The NVP is calculated by discounting the value of the annual cash flows [using values taken from the Present Value Interest Factor (PVIF) table for a given project length and cost of capital] to the purchasing value of the dollar at the date of inception of the project (1998). The length of the investment project is a conservative estimate of the useful economic lifetime of the investment project. In this case, we believe that after 8 years additional investments in upgrades



Figure 5. Floor plan of our Total Laboratory Automation. (a) Sample reception. Specimens are picked up, 5 at a time, from 50-position racks and loaded into individual tube holders. A bar-code verification unit determines the legibility of the labels, determines if the specimen is on the right processing location, rejects the suspect samples into a holding area and accepts the correct ones by a message to the Laboratory Information System:“Specimen Received”. (b) Sample transport. The transport lanes are conveyor belts that move the samples about the system. (c) Centrifugation. Samples are loaded and unloaded automatically. The rotor has 50 positions. In our laboratory 350 specimens/h can be processed in these centrifuges. (d) Serum level detection. After centrifugation the samples are lowered into an optical well and based on the transmitted information the amount of the available serum is calculated. (e) Cap removal. A gentle rocking motion removes the cups without creating potentially hazardous aerosols. (f) Tube labeling and sample aliquoting. For each primary serum sample secondary aliquot tuber are prepared. The tube labeler prints a bar-code label and applies it to each aliquot tube. The number of aliquot tubes is defined by the system. Disposable pipette tips transfer the serum from the primary to the secondary (aliquot) tubes. The primary tubes are directed to a storage unit. (g) Instrument connections. Several instruments are connected to the transport system. Connection units load and unload samples. Samples not going to the analyzer can continue down the main line. (h) Cap replacement. When the testing of a secondary aliquot tube has been completed, the tube is directed toward an outlet unit, stockyard or storage locker. Before storage, the tube can receive a clean cap. (i) Refrigerated Sample storage. It holds up to 3000 tubes. Samples can be retrieved automatically through a request in the computer and sent to the location requested by the operator.

Figure 6. A portion of the Chemistry automated Core Laboratory at The Mount Sinai Hospital, New York.

beyond normal maintenance may be required. The cost of capital used was the interest rate of the lease taken out to finance the project. The relevant calculations are shown below:

1. Total cost of the lease (capital and interest):	\$121,963/month×60 months	=	\$7,318,480
2. Total interest paid over the life of the lease:	\$7,318,380 – \$6,194,650	=	\$1,123,730
3. Annual interest payments:	\$1,123,730/5 years	=	\$ 224,730
4. Interest rate paid on lease:	(\$224,746/\$6,194,650) × 100	=	**3,628%**

Negative Cash Flows

Negative cash flows represent money spent on the project. This includes capital outlays, lease payments (\$3,140,000 or \$741,921/year for 5 years, represented the portion on chemistry automation), project-related expenses (annual maintenance contract, years 1999 and 2000 = \$74,240 annually, 2001–2005 = \$39,000 annually.



Figure 7. Automation increased Productivity and reduced cost. While the number of specimens processed increased from 2.500 to 10,000 specimens/year the cost/test was reduced from \$0.79 to 0.15 (in 1965\$).

Positive Cash Flows

Positive cash flows are those that represent money saved and/or costs avoided as the result of the chemistry automation project. There are recurring positive cash flows, resulting from savings that are essentially perpetual, such as salaries and benefits of workers replaced permanently by the chemistry automation project. Savings realized in a given year that are not expected to be repeated in subsequent years are nonrecurring positive cash flows. Staff pay raises during the years 1998, 1999, 2000, and 2002 were

Table 6. Increased Productivity

Year	Tech Staff	Other Staff	Total Staff	No. of Tests/Tech	No. of Tests/tot. Staff	No. of Tests/Specimen	Total No. of Specimens
1965	19	6.00	24.00	14,000	10,600	4.2	2,560
1970	34	17.00	51.00	36,205	24,150	8.8	2,745
1980	39	22.00	61.00	82,359	53,732	10.0	5,268
1997	38	17.00	55.00	94,058	66,099	11.8	5,529
2000	29	13.00	42.00	151,190	104,558	10.4	10,066
2002	29	39.00	35.00	169,582	128,530	10.5	12,190

Table 7. Cost/Test Reduction

Year	Tech Salary, \$	Salary \$/Test	Supplies \$/Test	Total \$/Test	Salary 1965 \$/Test	Supplies 1965 \$/Test	Total 1965 \$/Test
1965	5,170	0.70	0.19	0.79	0.70	0.09	0.79
1970	9,114	0.38	0.17	0.55	0.31	0.14	0.45
1980	16,500	0.37	0.20	0.57	0.14	0.08	0.22
1997	38,000	0.66	0.41	1.07	0.13	0.08	0.21
2000	41,000	0.45	0.36	0.81	0.08	0.07	0.15
2002	44,000	0.38	0.34	0.72	0.07	0.06	0.13



Figure 8. The Internal Rate of Return for the Chemistry Automation project was a remarkable 22%.

financed directly from chemistry automation project savings. These amounts are not reflected in the net salary and benefits savings. As such they are positive cash flow, since they represent costs covered by the automation savings that otherwise would have had to be financed through other sources.

The NPV Profile and Internal Rate of Return

The interest rate employed to discount the value of cash flows to the baseline year (1998) is the marginal cost of capital (the interest rate of the lease), which is 4%. The interest rate at which the NPV equals zero is especially interesting. This is called the internal rate of return (IRR) of the project. For all interest rates below the IRR, the NPV will generate positive values. In order to determine the IRR, we construct an NPV profile for different interest rates and locate the rate where the NPV crosses the X axis where the $\text{NPV} = 0$ (Fig. 8.). It shows that the chemistry automation project can tolerate interest rates up to 18.0% (the IRR) and still generate positive returns.

The Payback Period and Average Return on Investment

Although the NPV and IRR are vastly superior indicators of project profitability because of their use of discounted cash flows, the payback period and return on investment (ROI) are still key determinant of project viability by a majority of financial managers.

The Payback Period. After 8 years the raw dollar value of positive cash flows is $5,371,743 versus negative cash flows of $4,0053,085. The payback period therefore:

$$8\,\text{years} \times (\$4,053,085/\$5,371,743)$$

$$8\,\text{years} \times 0.755 = 6.04\,\text{years}$$

Average ROI

Average Annual Cash Outlay:	$4,053,085/8 years = $506,635/ year
Average Annual Net Return:	(5,371,743 − $4,053,085)/8 years = $164,822
Average ROI:	($164,832/$506,635) × 100 = 32.5%

CONCLUSIONS

Productivity is a key issue for labs.

The major financial benefit of automation is increased productivity.

Perianalytical automation increased our chemistry productivity by 120% (from 5,530 to 12,190 specs/tech/year).

Perianalytical automation reduced our chemistry labor cost/test by 42% (from 66¢ to 38¢/test).

Automation is a key solution for staff shortages.

Speedy implementation, speedy labor reductions and speedy revenue generation improve financial performance.

To achieve financial success, laboratorians must understand key financial principles.

ACKNOWLEDGMENTS

We thank E. Simson for practical advice on the financial perspective and M. Gannon for teaching us the meaning and calculation of the Net Present Value.

BIBLIOGRAPHY

Cited References

1. Eggert AA. Analytical methods, automated. In: Webster JG, editor. Encyclopedia of Medical Devices and Instrumentation. Hoboken (NJ): John Wiley & Sons; 1988.
2. Narayanan S. The preanalytical phase: an important component of laboratory medicine. Am J Clin Pathol 2000;113:429–452.
3. Labcorp directory of services and interpretive guide 2003.
4. Ford A. Latest chemistry wish list in low volume labs. CAP today 2004; April 44–58.
5. Lee-Lewandrowski E, Lewandrowski K. Contemporary instruments in the clinical laboratory: A brief overview. In: Lewandrowski K, editor. Clinical chemistry. Philadelphia: Lippincott Williams & Wilkins; 2002.
6. Aller R. Chemistry analyzers. CAP today 1999; July 58–83.
7. Adesoji BB, Peterson JR. Immunoassay and immunoassay analyzers: A perspective from the clinical laboratory. In: Lewandrowski K, editor. Clinical chemistry. Philadelphia: Lippincott Williams & Wilkins; 2002.
8. Goslimg JP. A decade of development in immunoassay technology. Clin Chem 1990;36:1408–1427.
9. Ehrhardt V, Assmann G, Batz O, et al. Results of the multicentre evaluation of an electrochemiluminescence immunoassay for hcg on elecsys 2010. Wein Klin Wochenschr 1998;3 (Suppl): 61–67.
10. Aller RD, Smalley D. Of all analyzers, immunoassay the trickiest. CAP today 2000;April 30–64.
11. Ford A. Automated immunoassay analyzers: the latest lineup. CAP today 2003; June 72–96.
12. Jacobs E. Acute care and stat lab testing. In: Lewandrowski K, editor. Clinical chemistry. Philadelphia: Lippincott Williams & Wilkins; 2003.

13. Ford A. Choosing cost-efficiency in low-volume labs. CAP today 2003; June 32–52.
14. Markin RS. Clinical laboratory automation. In: Henry JB, editor. Clinical diagnosis and management by laboratory methods. Philadelphia: W.B. Saunders; 2001.
15. Ford A. Laboratory automation systems and work cells. CAP today 2003; May: 35–52.
16. Sasaki M. Completed automatic clinical laboratory using a sample transportation system: the belt-line system. Jpn J Clin Pathol 1984;32:119–126.
17. NCCLS laboratory automation: specimen container/specimen carrier; proposed standard. NCCLS document auto 1 P; December 1995.
18. NCCLS laboratory automation: bar codes for specimen container identification; proposed standard. NCCLS document 2 P; April 1999.
19. NCCLS laboratory automation: communications with automated clinical laboratory systems, instruments, devices and information systems; proposed standard. NCCLS document 3 P; December 1998.
20. NCCLS laboratory automation: systems operational requirements and information elements; proposed standard. NCCLS document auto 4 P; October 1999.
21. NCCLS laboratory automation; electromechanical interface; proposed standard. NCCLS document auto 5 P; April 1999.
22. Markin RS, Whalen SA. Laboratory automation; trajectory, technology and tasks. Clin Chem 2000;46:764–771.
23. Sarkozi L, Simson E, Ramanathan L. The effects of total laboratory automation on the management of a clinical chemistry laboratory. Retrospective analysis of 36 years. Clinica Chimica Acta 2003;329:89–94.

See also BLOOD COLLECTION AND PROCESSING; COMPUTERS IN THE BIOMEDICAL LABORATORY; CYTOLOGY, AUTOMATED; DIFFERENTIAL COUNTS, AUTOMATED.

ANALYZER, OXYGEN. See OXYGEN ANALYZERS.

ANESTHESIA MACHINES

ROBERT LOEB
University of Arizona
Tuscon, Arizona

JEFFREY FELDMAN
Children's Hospital of
Philadelphia
Philadelphia, Pennsylvania

INTRODUCTION

On October 16, 1846, W. T. G. Morton gave the first successful public demonstration of inhalational anesthesia. Using a hastily devised glass reservoir to deliver diethyl ether, he anesthetized a patient before an audience at the Massachusetts General Hospital (Fig. 1). This glass reservoir thus became the first, crude, anesthesia machine. The technology of anesthesia machines has advanced immeasurably in the ensuing 150 years. Modern anesthesia machines are used to administer inhalational anesthesia safely and precisely to patients of any age, in any state of health, for any duration of time, and in a wide range of operating environments.


W.T.G. MORTON ETHER INHALER
Massachusetts General Hospital
Dept of Biomedical Engineering • MGH

Figure 1. A reproduction of the Morton Inhaler, ~ 1850. (Image © by the Wood Library-Museum of Anesthesiology, Park Ridge, Illinois.)

The term anesthesia machine colloquially refers to all of the medical equipment used to deliver inhalational anesthesia. Inhalational anesthetics are gases that, when inhaled, produce a state of general anesthesia, a drug-induced reversible loss of consciousness during which the patient is not arousable, even in response to painful stimulation. Inhalational anesthetics are supplied as either compressed gases (e.g., nitrous oxide), or volatile liquids (e.g., diethyl ether, sevoflurane, or desflurane). In recent years, the anesthesia machine has been renamed the anesthesia delivery system, or anesthesia workstation because modern devices do more than simply deliver inhalational anesthesia. Defined precisely, the term "anesthesia machine" specifically refers to that component of the anesthesia delivery system that precisely mixes the compressed and vaporized gases that are inhaled to produce anesthesia. Other components of the anesthesia delivery system include the ventilator, breathing circuit, and waste gas scavenger system. Anesthesia workstations are anesthesia delivery systems that also incorporate patient monitoring and information management functions (Fig. 2).

The most obvious goals of general anesthesia are to render a patient unaware and insensible to pain so that surgery or other medically necessary procedures can be performed. In the process of achieving these goals, potent medications are administered that interfere with normal body functions, most notably circulation of blood and the ability to breathe (see the text box Typical Process of Delivering General Anesthesia). The most important goal of anesthesia care is therefore to keep the patient safe and free from injury.

Patient safety is a major principle guiding the design of the anesthesia workstation. Precise control of the dose of anesthetic gases and vapors reduces the risk of administering an overdose. The ventilator and breathing circuit are fundamental components of the anesthesia delivery system designed to allow for continuous delivery of oxygen to the lungs and removal of exhaled gases. To fulfill national and international standards, anesthesia delivery systems must have essential safety features and meet specified minimum performance criteria (1–6)

Typical Process of Delivering General Anesthesia

Check the anesthesia delivery system for proper function: At the start of each day, the anesthesia provider places disposable components on the breathing circuit and performs an equipment check to ensure proper function of the anesthesia workstation (7).

Identify the patient and confirm the surgical site: Healthcare institutions are required to have formal procedures to identify patients and the site of surgery before the patient is anesthetized.

Establish venous access to administer medications and fluids: Using this catheter, drugs can be administered intravenously and fluids can be given to replace loss of blood or other body fluids.

Attach physiologic monitors: Monitoring the effects of anesthesia on the body is of paramount importance to guide the dose of anesthetic given and to keep the patient safe. Typical monitors include a blood pressure cuff, electrocardiogram, and pulse oximeter. Standards require that additional monitors be used during most anesthesia care (8).

Have the patient breathe 100% oxygen through a mask and circuit attached to the anesthesia machine: A tightly fitting mask is held over the patient's face while 100% oxygen is administered using the anesthesia machine. The goal is to eliminate the nitrogen in the lungs and provide a reservoir of oxygen to sustain the patient from the time anesthesia is induced until mechanical ventilation is established.

Inject a rapidly acting sedative–hypnotic medicine into the patient's vein: This injection induces general anesthesia and often causes the patient to stop breathing. Typical induction medications (e.g., thiopental, propofol) are quickly redistributed and metabolized, so additional anesthetics must be administered shortly thereafter to maintain anesthesia.

Breathe for the patient: This is typically accomplished by holding a mask attached to the breathing circuit tightly over the patient's face and squeezing the bag on the anesthesia machine to deliver oxygen to the lungs. This process is also known as manual ventilation.

Inject a neuromuscular blocking drug to paralyze the patient's muscles: Profound muscle relaxation makes it easier for the anesthesia provider to insert a tracheal tube into the patient's trachea. Neuromuscular blockers are also often used to make it easier for the surgeon to perform the procedure.

Insert a tube into the patient's trachea: This step is called endotracheal intubation and is used to establish a secure path for delivering oxygen and inhaled anesthetics to the patient's lungs as well as eliminating carbon dioxide.

Confirm correct placement of the endotracheal tube: This step is fundamental to patient safety. Numerous methods to confirm correct placement have been described. Identifying the presence of carbon dioxide in the exhaled gas is considered the best method for confirming tube placement. Continuous monitoring of carbon dioxide in the exhaled gases is considered a standard of care during general anesthesia.

Deliver anesthetic agents: General anesthesia is typically maintained with inhaled anesthetic gases. Dials are adjusted on the anesthesia machine to dispense a specified concentration of anesthetic vapor mixed with oxygen and air or nitrous oxide.

Begin mechanical ventilation: The anesthesia delivery system is switched from spontaneous to mechanical ventilation mode, and a ventilator, built into the anesthesia delivery system, is set to breathe for the patient. This frees the anesthesia provider's hands and ensures that the patient breathes adequately during deeper levels of anesthesia and while under the effect of neuromuscular blockers. The ability to deliver anesthetic gases while providing mechanical ventilation is a unique feature of the anesthesia machine.

Adjust ventilation and depth of anesthesia: During the case, the gas flows are reduced to minimize anesthetic usage. The inhaled anesthetic concentration is adjusted to optimize the depth of anesthesia in response to changing levels of surgical stimulus. The ventilator settings are tuned to optimize the patient's ventilation and oxygenation status. Information form the physiologic monitors helps to guide these adjustments.

Establish spontaneous ventilization: Toward the end the operation, the magnitude of ventilation is decreased. The patient responds by starting to breathe spontaneously, at which time the anesthesia delivery system is switched from mechanical to spontaneous ventilation mode and the patient continues to breath from the bag on the anesthesia machine.

Remove the endotracheal tube: At the end of the case, the anesthetic gases are turned off and the patient regains consciousness. The endotracheal tube is removed and the patient breathes oxygen from a cylinder while being transported to the recovery area.

System Overview

Anesthesia delivery systems allow anesthesia providers to achieve the following goals:

1. Precisely deliver a prescribed concentration of inhaled gases to the patient.
2. Support multiple modes of ventilation (i.e., spontaneous, manually assisted, and mechanically controlled).
3. Precisely deliver a wide variety of prescribed ventilator parameters.
4. Conserve the use of anesthetic vapors and gases.
5. Minimize contamination of the operating room atmosphere by anesthetic vapors and gases.
6. Minimize the chance of operator errors.
7. Minimize patient injury in the event of operator error or equipment malfunction.



Figure 2. Four contemporary anesthesia workstations. The top two are manufactured by GE Healthcare, and the bottom two by Draeger Medical.

These goals will be discussed further in the following section, which describes the major components of the anesthesia delivery system. The following overview of anesthesia delivery system function will refer to these goals.

The anesthesia delivery system consists of four components: a breathing circuit, an anesthesia machine, a waste gas scavenger system, and an anesthesia ventilator. The breathing circuit is the functional center of the system, since it is physically and functionally connected to each of the other components and to the patient's airway (Fig. 3). There is a one-way flow of gas from the anesthesia machine into the breathing circuit, and from the breathing circuit into the scavenger system. There is a bidirectional flow of gas between the breathing circuit and the patient's lungs, and between the breathing circuit and the anesthesia ventilator or reservoir bag. The ventilator and the reservoir bag are functionally interchangeable units, which are used during different modes of ventilation (Goal 2). During spontaneous and manually assisted modes of ventilation, the elastic reservoir bag is used as a source of inspired gas and a low impedance reservoir for exhaled gas. The anesthesia ventilator is used during mechanically controlled ventilation to automatically inflate the lungs using prescribed parameters (Goal 3).

During inhalation, gas flows from the anesthesia ventilator or reservoir bag through the breathing circuit to the patient's lungs. The patient's bloodstream takes up a small portion of gas (e.g., oxygen and anesthetic agent) from the lungs and releases carbon dioxide (CO_2) into the lungs.



Figure 3. Block diagram of anesthesia delivery system components. The arrows show the direction of gas flow between components.

During exhalation, gas flows from the patient's lungs through the breathing circuit back to the anesthesia ventilator or reservoir bag. This bulk flow of gas, between the patient and the ventilator or reservoir bag, constitutes the patient's pulmonary ventilation; the volume of each breath is referred to as tidal volume, and the total volume exchanged during one minute is referred to as minute volume.

Over time, the patient absorbs oxygen and anesthetic agents from, and releases CO_2 to, the gas in the breathing circuit. Without intervention, the gas within the breathing circuit would progressively decrease in total volume, oxygen concentration, and anesthetic concentration. The anesthesia provider, therefore, dispenses fresh gas into the breathing circuit, replacing the gas absorbed by the patient. Using the anesthesia machine, the anesthesia provider precisely controls both the flow rate and the concentration of various gases in the fresh gas (Goal 1). The anesthesia machine is capable of delivering a total fresh gas flow that far exceeds the volume of gas absorbed by the patient. When higher fresh gas flows are used (for example, to rapidly change the concentration of gases in the breathing circuit), the excess gas is vented into the scavenger system to be evacuated from the operating room (Goal 5).

To conserve the use of anesthetic gases (Goal 4), the anesthesia provider will use a fresh gas flow rate that is significantly lower than the patient's minute volume. In this situation, the patient reinhales gas that they had previously exhaled into the breathing circuit (this is called rebreathing). Carbon dioxide absorbent contained within the breathing circuit prevents the patient from rebreathing CO_2, which would be deleterious. All other gases (oxygen, nitrous oxide, nitrogen, and anesthetic vapors) can be rebreathed safely.

During the course of a typical anesthetic, the anesthesia provider will use a relatively high fresh gas flow at the beginning and end of the anesthetic when a rapid change in anesthetic concentration is desired, and a lower fresh gas flow when little change in concentration is desired. The technique of closed circuit anesthesia refers to the process of adjusting the fresh gas flow to exactly match the amount of gas used by the patient so that no gas is vented to the scavenging system.

Because anesthesia delivery systems provide critical life support functions to unconscious patients, equipment malfunctions and user errors can have catastrophic consequences. In 1974, the American National Standards Institute published an anesthesia machine standard that specified minimum performance and safety requirements for anesthesia gas machines (Goals 6 and 7). That standard was a landmark one, in that it was the first systematic approach to standardize the safety requirements for a medical device. Similar standards have since been written for other medical equipment, and the anesthesia machine standards have been regularly updated.

Breathing Circuit (Semiclosed Circle System)

The semiclosed circle system is the most commonly used anesthesia breathing circuit, and the only type that will be discussed in this article. It is so named because expired gases can be returned to the patient in a circular fashion (Fig. 4). The components of the circle system include a carbon dioxide absorber canister, two one-way valves, a reservoir bag, an adjustable pressure-limiting valve, and tubes that connect to the patient, ventilator, anesthesia machine, and scavenger system.

During inspiration, the peak flow of gas exceeds 25 $L{\cdot}min^{-1}$, far in excess of the rate of fresh gas supply. As a result, the patient will inspire both fresh gas and gas stored in the reservoir bag or ventilator bellows. Inspired gas travels through the carbon dioxide absorber canister, past the one-way inspiratory valve, to the patient. During


Inspiratory
one-way valve
Fresh gas inlet
(from anesthesia machine)
Carbon dioxide
absorber canister
Ventilator control unit
and bellows
Compressed gas inlet
(for ventilator drive gas)
Ventilator exhaust
valve
Expiratory
one-way valve
Circuit exhaust outlet
(to scavenger system)
APL valve
Bag/Ventilator
selector switch
Circuit exhaust outlet
(to scavenger system)
Reservoir bag

Figure 4. This schematic of the circle breathing circuit shows the circular arrangement of components. The one-way valves permit flow in only one direction.

exhalation, gas travels from the patient, past the one-way expiratory valve, to the reservoir bag (or ventilator bellows, depending upon the position of the bag–ventilator selector switch). The one-way valves establish the direction of gas flow in the breathing circuit. Carbon dioxide is not rebreathed because exhaled gas is directed through the carbon dioxide absorber canister prior to being reinhaled. Fresh gas from the anesthesia machine flows continuously into the breathing circuit. During inhalation, this gas joins with the inspiratory flow and is directed toward the patient. During exhalation, the fresh gas enters the breathing circuit and travels retrograde through the carbon dioxide absorber canister toward the reservoir bag (it does not travel toward the patient because the inspiratory one-way valve is closed during exhalation). Thus, during exhalation, gas enters the reservoir bag from the expiratory limb and from the carbon dioxide absorber canister. Once the reservoir bag is full, excess returning gas is vented out the adjustable pressure-limiting (APL) valve to the scavenger system (when the ventilator is used, the excess gas is vented out the ventilator exhaust valve). The total fresh gas flow will therefore control the amount of gas that is rebreathed. At high fresh gas flows, the exhaled gases are washed out through the scavenging system between each inspiration. At low fresh gas flow, very little exhaled gas is forced out to the scavenging system and most of the exhaled gas is reinhaled in subsequent breaths.

CIRCLE SYSTEM COMPONENTS

CO_2 Absorbents

Alkaline hydroxides of sodium, potassium, calcium, and barium in varying concentrations are most commonly used as carbon dioxide absorbents. These alkaline hydroxides irreversibly react with carbon dioxide to eventually form carbonates, releasing water and heat. Absorbent granules are 4- to 8-mesh in size (25–35 granules cm^{-3}) to maximize the surface area available for chemical reaction and minimize the resistance to gas flow through the absorber canister. Ethyl violet is incorporated into the granules as a pH indicator; fresh granules are white, while a purple color indicates that the absorbent needs to be replaced. Absorber canisters are constructed with transparent sides so that absorbent color can be easily monitored during use. Canisters have a typical capacity of 900–1200 cm^3 and the absorbent is good for $\sim$10–30 h of use, depending on the operating conditions.

Many of the absorbent materials have the potential to interact with anesthetic agents to degrade the anesthetics and produce small amounts of potentially toxic gases, such as carbon monoxide. This is especially true if the absorbents are allowed to dessicate by exposure to high flows of dry gas (e.g., leaving the fresh gas flowing on the anesthesia machine over a weekend). Periodic replacement of absorbent, especially at the end of a weekend is therefore desirable. Newer absorbent materials, which are more costly, are designed to reduce or eliminate the potential for producing toxic gases by eliminating the hydroxides of sodium, barium, and potassium.

Unidirectional Valves

The inspiratory and expiratory one-way valves are simple, passive devices. Each has an inlet tube that is capped by a valve disk. When the pressure in the inlet tube exceeds that in the outlet tube, the valve opens to allow gas to flow downstream. The valve disks are light in weight to minimize gas flow resistance. Each valve has a clear dome to allow visual monitoring of valve function. Rarely, valves malfunction by failing to open or close properly. Carbon dioxide rebreathing can occur if either valve becomes incompetent (i.e., fails to close properly). This can occur if a valve disk becomes warped, sticks open due to humidity, or fails to seat properly.

Reservoir Bag

The reservoir bag is an elastic bag that serves three functions in the breathing circuit. First, it is a compliant element of an otherwise rigid breathing circuit that allows changes in breathing circuit gas volume without changes in breathing circuit pressure. Second, it provides a means for manually pressurizing the circuit to control or assist ventilation. Third, it provides a safety limit on the peak pressure that can be achieved in the breathing circuit. It acts as a pressure-limiting device in the event that fresh gas inflow exceeds APL valve outflow. Reservoir bags are designed such that, at fresh gas flow rates below 15 $L{\cdot}min^{-1}$, the breathing circuit pressure will remain < 35 cm H_2O (3.4 kPa) until the bag reaches more than twice its full capacity. Yet, inspiratory pressures up to 70 cm H_2O (6.9 kPa) can be achieved by quickly compressing the reservoir bag.

APL Valve

The APL valve (euphemistically referred to as the pop-off valve) is a spring-loaded device that controls the flow of gas from the breathing circuit to the scavenger system. The valve opens when the pressure gradient from the circuit to the scavenger exceeds the force exerted by the spring (as discussed later, the pressure in the scavenger system is regulated to be equal to atmospheric pressure plus or minus a few cm H_2O). When the patient is breathing spontaneously, the anesthesia practitioner minimizes the spring tension allowing the valve to open with minimal end-expiratory pressure (typically < 3 cm H_2O, or 0.3 kPa). When the anesthesia practitioner squeezes the reservoir bag to manually control or assist ventilation, the APL valve opens during inhalation. Part of the gas exiting the reservoir bag escapes to the scavenger system and the remainder is directed toward the patient. By turning a knob, the anesthesia practitioner increases the pressure on the spring so that the APL valve remains closed until the pressure in the circuit achieves a level that is adequate to inflate the patients lungs; the APL valve thus opens toward the end of inhalation, once the lungs are adequately inflated. Continual adjustment of the APL valve is sometimes needed to adapt to changing fresh gas flow rate, circuit leaks, pulmonary mechanics, and ventilation parameters.

Bag–Ventilator Selector Switch

During mechanical ventilation, the reservoir bag and APL valve are disconnected from the breathing circuit and an anesthesia ventilator is connected to the same spot. Modern breathing circuits have a selector switch that quickly toggles the connection to either the ventilator or the reservoir bag and APL valve.

VIRTUES AND LIMITATIONS OF THE CIRCLE BREATHING CIRCUIT

Primary advantages of the circle breathing system over other breathing circuits include conservation of anesthetic gases and vapors, ease of use, and humidification and heating of inspired gases.

As stated previously, anesthetic agents are conserved when very low fresh gas flows are used with the circle breathing system. The minimum adequate flow is one that just replaces the gases taken up by the patient; for a normal adult, flows below 0.5 $L{\cdot}min^{-1}$ can be achieved during anesthesia maintenance. It is customary to use higher fresh gas flow rates in the range of 1–2 $L{\cdot}min^{-1}$, but this is still well below typical minute ventilation rates of 5–10 $L{\cdot}min^{-1}$ which is the fresh gas flow that would be required for a nonrebreathing ventilation system.

The circle breathing circuit is easy to use because the same fresh gas settings can be used with patients of various sizes. A 100 kg adult and a 1 kg infant can each be anesthetized with a circle breathing system and a fresh gas maintenance flow rate of 1–2 $L{\cdot}min^{-1}$. Since the larger patient would take up more anesthetic agent and more oxygen, and would give off more carbon dioxide, higher *minimal* flows would be required for the larger patient and the carbon dioxide absorbent would become exhausted quicker. Also, for convenience, a smaller reservoir bag and smaller bore breathing tubes would be selected for the smaller patient. But, otherwise, the system would function similarly for both patients.

Humidification and warming of inspired gases is another advantage of rebreathing. Fresh gas is mixed from compressed gases that contain zero water vapor, and breathing this dry gas can have detrimental effects on lung function. But, within the circle breathing system, inspired gas is humidified by the admixture of rebreathed gas, and by the water vapor that forms as a byproduct of carbon dioxide absorption. Both of these mechanisms also act to warm the inspired gas. By using low flows, enough heat and humidity is conserved to eliminate the need to actively heat and humidify inspired gas.

Most disadvantages of the circle breathing system are due to the large circuit volume. Internal volumes are primarily


N_2O Flowmeters
Pipeline pressure gauge
N_2O Pipeline inlet
Check valve
Gas proportioning system
Fail-safe mechanism
Cylinder pressure gauge
Check valve
Pressure regulator
Low O_2 pressure alarm
N_2O Cylinder
N_2O Flow control valve
Vaporizers
O_2 Flowmeters
Check valve
Fresh gas outlet
Pipeline pressure gauge
Check valve
O_2 Pipeline inlet
Cylinder pressure gauge
Check valve
Pressure regulator
Main switch
O_2 Flow control valve
O_2 Flush
O_2 Cylinder
Ventilator control unit
Ventilator bellows
Auxillary O_2 flowmeter

Figure 5. Schematic showing the internal piping and placement of components within the anesthesia machine. Dark gray indicates oxygen (O_2) and light gray indicates nitrous oxide (N_2O).

determined by the sizes of the absorbent canister, reservoir bag, and breathing hoses; 3–6 L are typical. Large circuits are physically bulky. They also increase the time required to change inspired gas concentrations because the large reservoir of previously exhaled gas is continually added to fresh gas. Finally, large circuits are more compliant, which degrades the efficiency and accuracy of ventilation. This effect will be discussed further in the section on ventilators.

Anesthesia Machine

The anesthesia machine is used to accurately deliver into the breathing circuit a precise flow and concentration of gases and vapors. Anesthesia machines are manufactured to deliver various compressed gases; all deliver oxygen, most deliver nitrous oxide or air, some deliver helium or carbon dioxide. They have one or more vaporizers that convert liquid anesthetic agents into anesthetic vapors; currently used inhaled vapors include halothane, enflurane, isoflurane, sevoflurane, and desflurane. Anesthesia machines include numerous safety features that alert the anesthesia provider to malfunctions and avert use errors.

The anesthesia machine is a precision gas mixer (Fig. 5). Compressed gases enter the machine from the hospital's centralized pipeline supply or from compressed gas cylinders. The compressed gases are regulated to specified pressures, and each passes through its own flow controller and flow meter assembly. The compressed gases then are mixed together and may flow through a single vaporizer where anesthetic vapor is added. The final gas mixture then exits the common gas outlet (also called the fresh gas outlet) to enter the breathing circuit.

ANESTHESIA MACHINE COMPONENTS

Compressed Gas Inlets

Compressed gases from the hospital pipeline system or from large compressed gas cylinders enter the anesthesia machine through flexible hoses. The inlet connector for each gas is unique in shape to prevent the connection of the wrong supply hose to a given inlet. The standardized design of each hose-inlet connector pair conforms to the Diameter Indexed Safety System (DISS) (9).

Anesthesia machines also have inlet yokes that hold small compressed gas cylinders; these cylinders provide compressed gas for emergency backup and for use in locations without piped gases. Each yoke is designed to prevent incorrect placement of a cylinder containing another gas. Two pins located in the yoke must insert into corresponding holes on the cylinder valve stem. The standardized placement of these pins and corresponding holes, referred to as the Pin Indexed Safety System (PISS), is unique for each gas (10).

Pressure Regulators And Gauges

Gauges on the front panel of the anesthesia machine display the cylinder and pipeline inlet pressures of each gas. Gases from the pipeline inlets enter the anesthesia machine at pressures of 45–55 psig (310–380 kPa), whereas gases from the compressed gas cylinders enter at pressures up to 2000 psig (1379 kPa). (Pressure conversion factors: $1\ \text{psig} = 0.068\ \text{atm} = 51.7\ \text{mmHg} = 70.3\ \text{cm}\ H_2O = 6.89\ \text{kPa}$.) Pressure regulators on each cylinder gas inlet line reduce the pressure from each cylinder to ~ 45 psig (310 kPa). The pressure regulators provide a relatively constant outlet pressure in the presence of a variable inlet pressure, which is important since the pressure within a gas cylinder declines during use. Lines from the pipeline inlet and the cylinder inlet (downstream of the pressure regulator) join to form a common source line for each gas. Gases are preferentially used from the pipelines, since the pressure regulators are set to outlet pressures that are less than the usual pipeline pressures.

Flow Controllers And Meters

A separate needle-valve controls the flow rate of each compressed gas. Turning a knob on the front panel of the anesthesia machine counterclockwise opens the needle valve and increases the flow; turning it clockwise decreases or stops the flow. A flowmeter assembly, located above each flow-control knob, shows the resulting flow rate. The flowmeter consists of a tapered glass tube containing a movable float; the internal diameter of the tube is larger at the top than at the bottom. Gas flows up through the tube, which is vertically aligned, and in doing so blows the float higher in the tube. The float balances in midair partway up the tube when its weight equals the force of the gas traveling through the space between the float and the tube. Thus, the height to which the float rises within the tube is proportional to the flow rate of the gas. Flow rate is indicated by calibrated markings on the tube alongside the level of the float.

Each flowmeter assembly is calibrated for a specific gas. The density and viscosity of the gas significantly affects the force generated in traveling through the variable-sized annular orifice created by the outer edge of the float and the inner surface of the tube. Temperature and barometric pressure affect gas density, and major changes in either can alter flowmeter accuracy. Accuracy is also impaired by dirt or grease within the tube, static electricity between the float and the tube, and nonvertical alignment of the tube.

To increase precision and accuracy, some machines indicate gas flow rate past a single needle valve using two flowmeter assemblies, one for high flows and the other for low flows. These flowmeters are connected in series and the flow rate is indicated on one flowmeter or the other. A flow rate below the range of the high-flow meter shows an accurate flow rate on the low flow meter and an unreadable low flow rate on the high flow meter. While, a flow rate that exceeds the range of the low-flow meter shows an accurate flow rate on the high flow meter and an unreadable high flow rate on the low flow meter.

Each gas, having passed through its individual flow controller and meter assembly, passes into a common manifold before continuing on. Only the individual gas flow rates are indicated on the flowmeters; the user must calculate the total gas flow rate and the percent concentration of each gas in the mixture.

Vaporizers

Vaporizers are designed to add an accurate amount of volatilized anesthetic to the compressed gas mixture. Anesthetic vapors are pharmacologically potent, so low concentrations (generally $< 5\%$) are typically needed. The volatilized gases contribute to the total gas flow rate and dilute the concentration of the other compressed gases. The user can calculate these effects since they are not displayed on the machine front panel; luckily, these are generally negligible and can be ignored. Even though most anesthesia machines have multiple vaporizers, only one is used at a time; interlock mechanisms prevent a vaporizer from being turned on when another vaporizer is in use. Vaporizers are anesthetic agent specific and keyed filling systems prevent filling a vaporizer with the wrong liquid anesthetic.

All current anesthesia machines have direct-setting vaporizers that add a specified concentration of a single anesthetic vapor to the compressed gas mixture. Variable-bypass vaporizers are the most common (Fig. 6). In these, the inflowing compressed gas mixture is split into two streams. One stream is directed through a bypass channel and the other is directed into a chamber within the vaporizer that contains liquid anesthetic agent. The gas entering the vaporizing chamber becomes saturated with anesthetic vapor at a concentration that depends on the vapor pressure of the particular liquid anesthetic. For example, sevoflurane has a vapor pressure of 157 mmHg (20.9 kPa) at 20 °C, so the gas within the vaporizing chamber is about 20% sevoflurane (at sea level). This highly concentrated anesthetic mixture exits the chamber (now, at a flow rate greater than that entering the chamber, due to the addition of anesthetic vapor) to join, and be diluted by, gas that traversed the bypass channel. A dial on the vaporizer controls the delivered anesthetic concentration by regulating the resistance to flow along each path. For example, setting a sevoflurane vaporizer to a dialed concentration of 1% splits the inflowing compressed gas mixture so that one-twenty-fourth of the total is directed through the vaporizing chamber and the remainder is directed through the bypass. Direct-reading variable-bypass vaporizers are calibrated for a specific agent, since each anesthetic liquid has a different vapor pressure. Vapor pressure varies with



Figure 6. Schematic of a variable-bypass vaporizer. Arrows indicate direction of gas flow; heavier arrows indicate larger flow rates. Gas enters the Inlet Port and is split at the Bypass Cone into two streams. One stream is directed through a bypass channel and the rest enters the Vaporizing Chamber. Gas entering the Vaporizing Chamber equilibrates with Liquid Anesthetic Agent to become saturated with Anesthetic Vapor. This concentrated anesthetic mixture exits the chamber to join, and be diluted by, gas that traversed the bypass channel. The Concentration Control Dial is attached to the Concentration Cone, which regulates resistance to flow exiting the Vaporizing Chamber and thus controls the anesthetic concentration dispensed from the Outlet Port.

temperature, so vaporizers are temperature compensated; at higher temperatures, a temperature sensitive valve diverts more gas through the bypass channel. Vaporizers are designed to ensure that the gas within the liquid-containing chamber is saturated with anesthetic vapor. A cotton wick within the chamber promotes saturation by increasing the surface area of the liquid. Thermal energy is required for liquid vaporization (heat of vaporization). To minimize cooling of the anesthetic liquid, vaporizers are constructed of metals with high specific heat and high thermal conductivity so that heat is transferred easily from the surroundings. The output of variable-bypass vaporizers varies with barometric pressure; delivered concentration increases as barometric pressure decreases.

Desflurane vaporizers are designed differently because desflurane has such a high vapor pressure (664 mmHg, or 88.5 kPa, at 20 °C) and low boiling point (22.8 °C). Uncontrollably high output concentrations could easily occur if desflurane were administered at room temperature from a variable-bypass vaporizer. In a desflurane vaporizer, the liquid desflurane is electrically heated to a controlled temperature of 39 °C within a pressure-tight chamber. At this temperature, the vapor pressure of desflurane is 1500 mmHg (200 kPa) and the anesthetic vapor above the liquid is a compressed gas. The concentration dial on the vaporizer regulates a computer-assisted flow proportioning mechanism that meters pressurized desflurane into the incoming gas mixture to achieve a set output concentration of desflurane vapor. Room temperature does not affect the output concentration of the vaporizer, nor does barometric pressure. The vaporizer requires electrical power for the heater, the onboard computer, and two electronic valves.

Safety Systems

By written standard, the anesthesia machine has numerous safety systems designed to prevent use errors. Some of these, such as the DISS and PISS systems to prevent compressed gas misconnections, interlock mechanisms to prevent simultaneous use of multiple vaporizers, and keyed filler systems to prevent misfilling of vaporizers, have already been discussed. Others are presented, below.

Failsafe Mechanism And Oxygen Alarm. The anesthesia machine has a couple of safety systems that alert the user and stop the flow of other gases when the oxygen supply runs out (for example, when an oxygen tank becomes depleted). An auditory alarm sounds and a visual message appears to alert the user when the oxygen supply pressure falls below a predetermined threshold pressure of ~ 30 psig (207 kPa). A failsafe valve in the gas line supplying each flow controller-meter assembly, except oxygen, stops the flow of other gases. The failsafe valve is either an on–off valve or a pressure-reducing valve that is controlled by the pressure within the oxygen line. When the oxygen supply pressure falls below the threshold level, the failsafe valves close to stop the flow, or proportionally reduce the supply pressure, of all the other gases. This prevents administration of hypoxic gases (e.g., nitrous oxide, helium, nitrogen, carbon dioxide) without oxygen, which could rapidly cause injury to the patient, but it also prevents administration of air without oxygen. The failsafe mechanisms do *not* prevent delivery of hypoxic gas mixtures in the presence of adequate oxygen supply pressure; the gas proportioning system, described below, prevents this.

Gas Proportioning System. Anesthesia machines are equipped with proportioning systems that prevent the delivery of high concentrations of nitrous oxide, the most commonly used non-oxygen containing gas. A mechanical or pneumatic link between the oxygen and nitrous oxide lines ensures that nitrous oxide does not flow without an adequate flow of oxygen. One such mechanism, the Datex-Ohmeda Link-25 system, is a chain linkage between sprockets on the nitrous oxide and oxygen flow needle valves. The linkage is engaged whenever the nitrous oxide is set to exceed three-times the oxygen flow, or when the oxygen flow is set to less than one-third of the nitrous oxide flow; this limits the nitrous oxide concentration to a maximum of 75% in oxygen. Another mechanism, the Draeger Oxygen Ratio Monitor Controller (ORMC), is a slave flow control valve on the nitrous oxide line that is pneumatically linked to the oxygen line. This system limits the flow of nitrous oxide to a maximum concentration of $72 \pm 3\%$ in oxygen. Both of the above systems control the ratios of nitrous oxide and oxygen, but do not compensate for other gases in the final mixture; a hypoxic mixture (oxygen concentration $< 21\%$) could be dispensed, therefore, if a third gas were added in significant concentrations.

Oxygen Flush. Each anesthesia machine has an oxygen flush system that can rapidly deliver 45–70 $\mathrm{L{\cdot}min^{-1}}$ of oxygen to the common gas outlet. The user presses the oxygen flush valve in situations where high flow oxygen is needed to flush anesthetic agents out of the breathing circuit, rapidly increase the inhaled oxygen concentration, or compensate for a large breathing circuit leak (for example, during positive pressure ventilation of the patient with a poorly fitted face mask). The oxygen flush system also serves as a safety system because it bypasses most of the internal plumbing of the anesthesia machine (e.g., safety control valves, flow controller-meter assemblies, and vaporizers) and because it is always operational, even when the anesthesia machine's master power switch is off.

Monitors and User-Interface Features. Written standards specify that all anesthesia machines must be equipped with essential safety monitors and user-interface features. To protect against hypoxia, each has an integrated oxygen analyzer that monitors the oxygen concentration in the breathing circuit whenever the anesthesia machine is powered on. The oxygen monitor must have an audible alarm that sounds whenever the oxygen concentration falls below a preset threshold, which cannot be set $< 18\%$. To protect against dangerously high and low airway pressures, the breathing circuit pressure is continuously monitored by an integrated system that alarms in the event of sub-atmospheric airway pressure, sustained high airway pressure, or extremely high airway pressure. To protect against ventilator failure and breathing circuit disconnections, the breathing circuit pressure is monitored to ensure that adequate positive pressure is generated at least a few times a minute whenever the ventilator is powered on; a low airway pressure alarm (AKA disconnect alarm) is activated whenever the breathing circuit pressure does not reach a user-set threshold level over a 15 s interval. User-interface features protect against mistakes in gas flow settings. Oxygen controls are always positioned to the right of other gas flow controls. The oxygen flow control knob has a unique size and shape that is different from the other gas control knobs. The flow control knobs are protected against their being bumped to prevent accidental changes in gas flow rates. All gas flow knobs and vaporizer controls uniformly increase their settings when turned in a clockwise direction.

LIMITATIONS

Anesthesia machines are generally reliable and problem-free. Limitations include that they require a source of compressed gases, are heavy and bulky, are calibrated to be accurate at sea level, and are designed to function in an upright position within a gravitational field. Machine malfunctions are usually a result of misconnections or disconnections of internal components during servicing or transportation. Aside from interlock mechanisms that decrease the likelihood of wrong gas or wrong anesthetic agent problems, there are no integrated monitors to ensure that the vaporizers are filled with the correct agents and the flow meters are dispensing the correct gases. Likewise, except for oxygen, the gas supply pressures and anesthetic agent levels are not automatically monitored. Thus, problems can still result when the anesthesia provider fails to diagnose a problem with the compressed gas or liquid anesthetic supplies.

Ventilator

General anesthesia impairs breathing by two mechanisms, it decreases the impetus to breath (central respiratory depression), and it leads to upper airway obstruction. Additionally, neuromuscular blockers, which are often administered during general anesthesia, paralyze the muscles of respiration. For these reasons, breathing may be supported or controlled during anesthesia to ensure adequate minute ventilation. The anesthesia provider can create intermittent positive pressure in the breathing circuit by rhythmically squeezing the reservoir bag. Ventilatory support is often provided in this way for short periods of time, especially during the induction of anesthesia. During mechanical ventilation, a selector switch is toggled to disconnect the reservoir bag and APL valve from the breathing circuit and connect an anesthesia ventilator instead. Anesthesia ventilators provide a means to mechanically control ventilation, delivering consistent respiratory support for extended periods of time and freeing the anesthesia provider's hands and attention for other tasks. Most surgical patients have normal pulmonary mechanics and can be adequately ventilated with an unsophisticated ventilator designed for ease of use. But, high performance anesthesia ventilators allow safe and effective ventilation of a wide variety of patients, including neonates and the critically ill.

Most anesthesia ventilators are pneumatically powered, electronically controlled, and time cycled. All can be set to deliver a constant tidal volume at a constant rate (volume control). Many can also be set to deliver a constant inspiratory pressure at a constant rate (pressure control). All anesthesia ventilators allow spontaneous patient breaths between ventilator breaths (intermittent mandatory ventilation, IMV), and all can provide PEEP during positive pressure ventilation (note that in some older systems PEEP is set using a PEEP-valve integrated into the expiratory limb of the breathing circuit, and is not actively controlled by the ventilator). In general, anesthesia ventilators do not sense patient effort, and thus do not provide synchronized modes of ventilation, pressure support, or continuous positive airway pressure (CPAP).

As explained above, the anesthesia delivery system conserves anesthetic gases by having the patient rebreathe previously exhaled gas. Unlike intensive care ventilators, which deliver new gas to the patient during every breath, anesthesia ventilators function as a component of the anesthesia delivery system and maintain rebreathing during mechanical ventilation. In most anesthesia ventilators, this is achieved by incorporating a bellows assembly (see Fig. 4). The bellows assembly consists of a distensible bellows that is housed in a clear rigid chamber. The bellows is functionally equivalent to the reservoir bag; it is attached to, and filled with gas from, the breathing circuit. During inspiration, the ventilator injects drive gas into the rigid chamber; this squeezes the bellows and directs gas from the bellows to the patient via the inspiratory limb of the breathing circuit. The drive gas, usually oxygen or air, remains outside of the bellows and never enters the breathing circuit. During exhalation, the drive gas within the rigid chamber is vented to the atmosphere, and the patient exhales into the bellows through the expiratory limb of the breathing circuit.

The bellows assembly also contains an exhaust valve that vents gas from the breathing circuit to the scavenger system. This ventilator exhaust valve serves the same function during mechanical ventilation that the APL valve serves during manual or spontaneous ventilation. However, unlike the APL valve, it is held closed during inspiration to ensure that the set tidal volume dispensed from the ventilator bellows is delivered to the patient. Excess gas then escapes from the breathing circuit through this valve during exhalation.

The tidal volume set on an anesthesia ventilator is not accurately delivered to the patient; it is augmented by fresh gas flow from the anesthesia machine, and reduced due to compression-loss within the breathing circuit. Fresh gas, flowing into the breathing circuit from the anesthesia machine, augments the tidal volume delivered from the ventilator because the ventilator exhaust valve, which is the only route for gas to escape from the breathing circuit, is held closed during inspiration. For example, at a fresh gas flow rate of 3 $L{\cdot}min^{-1}$ (50 $mL{\cdot}s^{-1}$), and ventilator settings of 10 breaths min^{-1} and an I/E ratio of 1:2 (inspiratory time = 2 s), the delivered tidal volume is augmented by 100 mL per breath (2 s per breath × 50 $mL{\cdot}s^{-1}$). Conversely, the delivered tidal volume is reduced due to compression loss within the breathing circuit. The magnitude of this loss depends on the compliance of the breathing circuit and the peak airway pressure. Circle breathing circuits typically have a compliance of 7–9 $mL{\cdot}cm^{-1}$ H_2O (70–90 $mL{\cdot}kPa^{-1}$), which is significantly higher than the typical 1–3 $mL{\cdot}cm^{-1}$ H_2O (10–30 $mL{\cdot}kPa^{-1}$) circuit compliance of intensive care ventilators, because of their large internal volume. For example, when ventilating a patient with a peak airway pressure of 20 cm H_2O (2 kPa) using an anesthesia ventilator with a breathing circuit compliance of 10 mL·cm H_2O, delivered tidal volume is reduced by 200 mL per breath.

LIMITATIONS

Until recently, anesthesia ventilators were simple devices designed to deliver breathing circuit gas in volume control mode. The few controls consisted of a power switch, and dials to set respiratory rate, inspiratory/expiratory (I/E) ratio, and tidal volume. While simple to operate, these ventilators had a number of limitations. As discussed above, delivered tidal volume was altered by peak airway pressure and fresh gas flow rate. Tidal volume augmentation was particularly hazardous with small patients, such as premature infants and neonates, since increasing the gas flow on the anesthesia machine could unintentionally generate dangerously high tidal volumes and airway pressures. Tidal volume reduction was particularly hazardous since dramatically lower than set tidal volumes could be delivered, unbeknown to the provider, to patients requiring high ventilating pressures (e.g., those with severe airway disease or respiratory distress syndrome). Worse yet, the pneumatic drive capabilities of these ventilators were sometimes insufficient to compensate for tidal volume losses due to compression within the breathing circuit; anesthesia ventilators were unable to adequately ventilate patients with high airway pressures (> 45 cm H_2O) requiring large minute volumes (> 10 $L{\cdot}min^{-1}$). Another imperfection of anesthesia ventilators is that they are pneumatically powered by compressed gases. The ventilator's rate of compressed gas consumption, which is approximately equal to the set minute volume (5–10 $L{\cdot}min^{-1}$ in a normal size adult), is not a concern when central compressed gas supplies are being used. But the ventilator can rapidly deplete oxygen supplies when compressed gas is being dispensed from the emergency backup cylinders attached to the anesthesia machine (e.g., a backup cylinder could provide over 10 h of oxygen to a breathing circuit at low flow, but would last only one-hour if also powering the ventilator). Lastly, anesthesia ventilators that do not sense patient effort are unable to provide synchronized or supportive modes of ventilation. This limitation is most significant during spontaneous ventilation, since CPAP and pressure support cannot be provided to compensate for the additional work of breathing imposed by the breathing circuit and endotracheal tube, or to prevent the low lung volumes and atalectasis that result from general anesthesia. New anesthesia ventilators, introduced in the past 10 years, address many of these limitations as discussed later in the section on New Technologies.

Scavenger System

Waste anesthetic gases are vented from the operating room to prevent potentially adverse effects on health care workers. High volatile anesthetic concentrations in the operating room atmosphere can cause problems such as headaches, dysphoria, and impaired psychomotor functioning; chronic exposure to trace levels has been implicated as a causative factor for cancer, spontaneous abortions, neurologic disease, and genetic malformations, although many studies have not borne out these effects. The National Institute for Occupational Safety and Health (NIOSH) recommends that operating room levels of halogenated anesthetics be < 2 parts per million (ppm) and that nitrous oxide levels be < 25 ppm. Waste gases can be evacuated from the room actively via a central vacuum system, or passively via a hose to the outside; alternatively, the waste gas can pass through a canister containing activated charcoal, which absorbs halogenated anesthetics.

The scavenger system is the interface between the evacuation systems described in the preceding sentence and the exhaust valves on the breathing circuit and ventilator (i.e., APL valve and ventilator exhaust valve). It functions as a reservoir that holds waste gas until it can vent to the evacuation system. This is necessary because gas exits the exhaust valves at a non-constant rate that may, at times, exceed the flow rate of the evacuation system. The scavenger system also ensures that the downstream pressure on the exhaust valves does not become too high or too negative. Excessive pressure at the exhaust valve outlet could cause sustained high airway pressure leading to barotrauma and cardiovascular collapse; whereas, excessive vacuum at the exhaust valve outlet could cause sustained negative airway pressure leading to apnea and pulmonary edema.

There are two categories of scavenger systems, open and closed. Open scavenger systems can only be used with a vacuum evacuation system. In an open scavenger system, waste gas enters the bottom of a rigid reservoir that is open to the atmosphere at the top, and gas is constantly evacuated from the bottom of the reservoir into the vacuum. Room air is entrained into the reservoir whenever the vacuum flow rate exceeds the waste gas flow rate, and gas spills out to the room through the openings in the reservoir whenever the waste gas flow rate exceeds the vacuum flow rate. The arrangement of the components prevents spillage of waste gas out of the reservoir openings unless the *average* vacuum flow rate is less than the *average* flow out of the exhaust valves.

Closed scavenger systems consist of a compliant reservoir bag with an inflow of waste gas from the exhaust valves of the breathing system and an outflow to the active or passive evacuation system. Two or more valves regulate the internal pressure of the closed scavenger system. A negative pressure release valve opens to allow entry of room air whenever the pressure within the system becomes too negative, < -1.8 cm H_2O (-0.18 kPa) (i.e., in situations where the evacuation flow exceeds the exhaust flow and the reservoir bag is collapsed). A positive pressure release valve opens to allow venting of waste gas to the room whenever the pressure within the scavenger system becomes too high, > 5 cm H_2O (0.5 kPa) (i.e., in situations where the reservoir bag is full and the exhaust flow exceeds the evacuation flow). Thus, the pressure within the scavenger system is maintained between -1.8 and 5.0 cm H_2O.

Integrated Monitors

All anesthesia delivery systems have integrated electronic safety monitors intended to avert patient injuries. Included are (*1*) an oxygen analyzer, (*2*) an airway pressure monitor, and (*3*) a spirometer.

The oxygen analyzer measures oxygen concentration in the inspiratory limb of the breathing circuit to guard against the administration of dangerously low inhaled oxygen concentrations. Most analyzers use a polarographic or galvanic (fuel cell) probe that senses the rate of an oxygen-dependent electrochemical reaction. These analyzers are inexpensive and reliable, but are slow to equilibrate to changes in oxygen concentration (response times on the order of 30 s). They also require daily calibration. Standards stipulate that the oxygen analyzer be equipped with an alarm, and be powered-on whenever the anesthesia delivery system is in use.

The airway pressure monitor measures pressure within the breathing circuit, and warns of excessively high or negative pressures. It also guards against apnea during mechanical ventilation. Most anesthesia delivery systems have two pressure gauges: an analog Bourdon tube pressure gauge that displays instantaneous pressure on a mechanical dial, and an electronic strain-gauge monitor that displays a pressure waveform. Most electronic pressure monitors embody an alarm system with variable-threshold negative pressure, positive pressure, and sustained pressure alarms that can be adjusted by the user. An apnea alarm feature, which is enabled whenever the ventilator is powered-on, ensures that positive pressure is sensed within the breathing circuit at regular intervals. On some anesthesia delivery systems pressure is sensed within the circle system absorber canister; on other systems it is sensed on the patient side of the one-way valves; the latter gives a more accurate reflection of airway pressure.

The spirometer measures gas flow in the expiratory limb of the breathing circuit and guards against apnea and dangerously low or high respiratory volumes. A number of different techniques are commonly used to measure flow. These include spinning vanes, rotating sealed spirometers, ultrasonic, and variable orifice differential pressure. Respiratory rate, tidal volume, and minute volume are derived from the sensor signals and displayed to the user. Some machines also display a waveform of exhaled flow versus time. Most spirometers have an alarm system with variable-threshold alarms for low and high tidal volume, as well as an apnea alarm that is triggered if no flow is detected during a preset interval.

In addition to these standard monitors, some anesthesia workstations have integrated gas analyzers that measure inhaled and exhaled concentrations of oxygen, carbon dioxide, nitrous oxide, and volatile anesthetic agents. Although stand-alone gas analyzers are available, they are likely to be integrated into the anesthesia workstation because they monitor gas concentrations and respiratory parameters that are controlled by the anesthesia delivery system.

Other patient monitors, such as electrocardiography, pulse oximetry, invasive and noninvasive blood pressure, and thermometry may also be integrated into the anesthesia workstation; but often stand-alone monitors are placed on the shelves of the anesthesia delivery system. In either case, standard patient monitors must be used during the conduct of any anesthetic to evaluate the adequacy of the patient's oxygenation, ventilation, circulation, and body temperature. Monitoring standards, which have contributed to the dramatic increase in anesthesia safety, were initially published by the American Society of Anesthesiologists in 1986 and have been continually evaluated and updated (8).

New Technologies

The anesthesia delivery system as described thus far has evolved incrementally from a pneumatic device designed in 1917, by Henry Boyle for administration of anesthesia using oxygen, nitrous oxide and ether. The evolution of Boyle's machine has occurred in stages. In the 1950s and 1960s the failsafe devices and fluidic controlled ventilators were added. In the 1970s and early 1980s the focus was on improving safety with features, such as gas proportioning systems, safety alarms, electronically controlled ventilators, and standardization of the user interface to decrease errors. In the late 1980s and 1990s, monitors and electronic recordkeeping were integrated to create anesthesia workstations. Since 2000 the focus has been on improving ventilator performance, incorporating automated machine self-checks, and transitioning to electronically controlled and monitored flow meters and vaporizers. Some of the new technologies that have been introduced in the last few years are discussed, below.

BREATHING CIRCUIT

As discussed above, the tidal volume set on an anesthesia ventilator is not accurately delivered to the patient because of two breathing circuit effects. First, a portion of the volume delivered from the ventilator is compressed within the breathing circuit and does not reach the patient. Second, fresh gas flowing into the breathing circuit augments the delivered tidal volume. A number of techniques are used to minimize these effects in new anesthesia delivery systems.

Two techniques have been used to minimize the effect of gas compression. First, smaller, less compliant breathing circuits are being used. This has been achieved by minimizing the use of compliant hoses between the ventilator and breathing circuit and by decreasing the size of the absorber canister. A tradeoff is that the absorbent must be changed more frequently with a smaller canister, hence new breathing circuits are designed so that the carbon dioxide absorbent can be exchanged during use. Second, many new machines automatically measure breathing circuit compliance during an automated preuse checkout procedure and then compensate for breathing circuit compliance during positive pressure ventilation; the ventilator continually senses airway pressure and delivers additional volume to make up for that lost to compression.

A number of techniques have also been used to eliminate augmentation of tidal volume by fresh gas flowing into the circuit. In one approach, the ventilator automatically adjusts its delivered volume to compensate for the influx of fresh gas into the breathing circuit. The ventilator either adjusts to maintain a set exhaled tidal volume as measured by a spirometer in the expiratory limb of the breathing circuit, or it responds to maintain a set inhaled tidal volume sensed in the inspiratory limb, or it modifies its delivered volume based on the total fresh gas flow as measured by electronic flowmeters in the anesthesia machine. None of the above methods requires redesign of the breathing circuit, except for the addition of flow sensors that communicate with the ventilator.

In a radically different approach, called fresh gas decoupling, the breathing circuit is redesigned so that fresh gas flow is channeled away from ventilator-delivered gas during inspiration, which removes the augmenting effect of fresh gas flow on tidal volume. An example of such a breathing circuit is illustrated in Fig. 7. In this circuit, during inhalation, gas dispensed from a piston driven ventilator travels directly to the patient's lungs; retrograde flow is blocked by a passive fresh gas decoupling valve, and expiratory flow is blocked by the ventilator-controlled expiratory valve, which is actively closed during the inspiratory phase. Fresh gas does not contribute to the delivered tidal volume; instead it flows retrograde into a nonpressurized portion of the breathing circuit. During exhalation, the ventilator-controlled expiratory valve opens, and the ventilator piston withdraws to actively fill with a mixture of fresh gas and gas from the reservoir bag. This design causes a number of other functional changes. First, the breathing circuit compliance is lower during positive pressure ventilation, since only part of the breathing circuit is pressurized during inspiration (the volume between the fresh gas decoupling valve and the ventilator-controlled expiratory valve). Second, the reservoir bag remains in the circuit during mechanical ventilation. As a result, it fills and empties with gas throughout the ventilator cycle, which is an obvious contrast to the absence of bag movement during mechanical ventilation with a conventional circle breathing circuit.

ANESTHESIA MACHINE

Many new anesthesia machines have electronic gas flow sensors instead of tapered glass tubes with internal floats. Advantages include (*1*) improved reliability and reduced maintenance; (*2*) improved precision and accuracy at low-flows; and (*3*) ability to automatically record and use gas flows (for instance to adjust the ventilator). The electronic sensors operate on the principle of heat transfer, measuring the energy required to maintain the temperature of a heated element in the gas flow pathway. Each sensor is calibrated for a particular gas, since every gas has a different specific heat index. Gas flows are shown on dedicated light-emitting diode (LED) displays or on the


Ventilator control unit
Ventilator piston
Inspiratory one-way valve
Fresh gas inlet (from anesthesia machine)
Fresh gas decoupling valve
Carbon dioxide absorber canister
Reservoir bag
APL valve
Expiratory one-way valve
Circuit exhaust outlet (to scavenger system)
Circuit exhaust outlet (to scavenger system)
Ventilator-controlled expiratory valve
Ventilator-controlled exhaust valve

Figure 7. Example of a breathing circuit with fresh gas decoupling. This breathing circuit is used in the Draeger Fabius anesthesia machine. It contains three passive one-way valves and two active valves that are controlled by the ventilator during mechanical ventilation.

main anesthesia machine flat panel display. Most anesthesia machines still regulate the flow of each gas using mechanical needle valves, but in some these have been replaced with electronically control valves. Electronically controlled valves provide a mechanism for computerized gas proportioning systems that limit the ratios of multiple gases. Some machines with electronic flow control valves allow the user to select the balance gas (i.e., air or nitrous oxide) and set a desired oxygen concentration and total flow, leaving the calculation of individual gas flow rates to the machine.

Most new anesthesia machines continue to use mechanical vaporizers as described above, but a few incorporate electronic vaporizers. These operate on one of two principles: either computer-controlled variable bypass, or computer-controlled liquid injection. Computerized variable bypass vaporizers control an electronic valve that regulates the flow of gas exiting from the liquid anesthetic containing chamber to join the bypass stream. The valve is adjusted to reach a target flow that is based upon the: (*1*) dial setting, (*2*) temperature in the vaporizing chamber, (*3*) total pressure in the vaporizing chamber, (*4*) bypass flow, and (*5*) liquid anesthetic identity. Computerized injectors continuously add a measured amount liquid anesthetic directly into the mixed gas coming from the flowmeters based upon the: (*1*) dial setting, (*2*) mixed gas flow, and (*3*) liquid anesthetic identity. Electronic vaporizers offer a number of advantages. First, they provide a mechanism for vaporizer settings to be automatically recorded and controlled. Second, a number of different anesthetics can be dispensed (one at a time) using a single control unit, provided that the computer knows the identity of the anesthetic liquid.

VENTILATOR

Anesthesia ventilator technology has improved dramatically over the past 10 years and each new machine brings further advancements. As discussed above, most new ventilators compensate for the effects of circuit compliance and fresh gas flow, so that the set tidal volume is accurately delivered. Older style ventilators notoriously delivered low tidal volumes to patients requiring high airway pressures, but new ventilators overcome this problem with better flow generators, compliance compensation and feedback control. Many new anesthesia ventilators offer multiple modes of ventilation (in addition to the traditional volume control), such as pressure control, pressure support, and synchronized intermittent mandatory ventilation. These modes assess patient effort using electronic flow and pressure sensors that are included in many new breathing circuits. Lastly, some anesthesia ventilators use an electronically controlled piston instead of the traditional pneumatically compressed bellows. Piston ventilators, which are electrically powered, dramatically decrease compressed gas consumption of the anesthesia delivery system. However, they actively draw gas out of the breathing circuit during the expiratory cycle (as opposed to bellows, which fill passively) so they cannot be used with a traditional circle system (see Fig. 7 for an example of a piston ventilator used with a fresh gas decoupled breathing circuit).

AUTOMATED CHECKOUT

Many new anesthesia delivery systems feature semiautomated preuse checkout procedures. These ensure that the machine is functioning properly prior to use by (*1*) testing electronic and computer performance, (*2*) calibrating flow sensors and oxygen monitors, (*3*) measuring breathing circuit compliance and leakage, and (*4*) testing the ventilator.

Future Challenges

The current trend is to design machines that provide advanced capabilities through the use of computerized electronic monitoring and controls. This provides the infrastructure for features such as closed-loop feedback, smart alarms, and information management that will be increasingly incorporated in the future. We can anticipate closed-loop controllers that automatically maintain a user-set exhaled anesthetic concentration (an indicator of anesthetic depth), or exhaled carbon dioxide concentration (an indicator of adequacy of ventilation). We can look forward to smart alarms that pinpoint the location of leaks or obstructions in the breathing circuit, alert the user and switch to a different anesthetic when a vaporizer becomes empty, or notify the user and switch to a backup cylinder if a pipeline failure or contamination event is detected. We can foresee information management systems that automatically incorporate anesthesia machine settings into a nationwide repository of anesthesia records that facilitate outcomes-guided medical practice, critical event investigations, and nationwide access to patient medical records. Anesthesia machine technology continues to evolve.

BIBLIOGRAPHY

Cited References

1. ASTM F1850. Standard Specification for Particular Requirements for Anesthesia Workstations and Their Components. ASTM International; 2000.
2. ISO 5358. Anaesthetic machines for use with humans. International Organization for Standardization; 1992.
3. ISO 8835-2. Inhalational anaesthesia systems—Part 2: Anaesthetic breathing systems for adults. International Organization for Standardization; 1999.
4. ISO 8835-3. Inhalational anaesthesia systems—Part 3: Anaesthetic gas scavenging systems—Transfer and receiving systems. International Organization for Standardization; 1997.
5. ISO 8835-4. Inhalational anaesthesia systems—Part 4: Anaesthetic vapour delivery devices. International Organization for Standardization; 2004.
6. ISO 8835-5. Inhalational anaesthesia systems—Part 5: Anaesthetic ventilators. International Organization for Standardization; 2004.
7. Anesthesia Apparatus Checkout Recommendations. United States Food and Drug Administration. Available at http://www.fda.gov//cdrh/humfac//anesckot.html. 1993.
8. Standards for Basic Anesthetic Monitoring, American Society of Anesthesiologists. Available at http://www.asahq.org/publicationsAndServices/standards/02.pdf. Accessed 2004.
9. CGA V-5. Diameter Index Safety System (Noninterchangeable Low Pressure Connections for Medical Gas Applications). Compressed Gas Association; 2000.
10. CGA V-1. Compressed Gas Association Standard for Compressed Gas Cylinder Valve Outlet and Inlet Connections. Compressed Gas Association; 2003.

Reading List

Dorsch J, Dorsch S. Understanding Anesthesia Equipment. 4th ed. Williams & Wilkins; 1999.

Brockwell RC, Andrews JJ. Inhaled Anesthetic Delivery Systems. In: Miller RD. et al. editors. Miller's Anesthesia. 6th ed. Philadelphia: Elsevier Churchill Livingstone; 2005.

Ehrenwerth J, Eisenkraft JB, editors. Anesthesia Equipment: Principles and Applications. St. Louis: Mosby; 1993

Lampotang S, Lizdas D, Liem EB, Dobbins W. The Virtual Anesthesia Machine. http://vam.anest.ufl.edu/.

See also CONTINUOUS POSITIVE AIRWAY PRESSURE; EQUIPMENT ACQUISITION; EQUIPMENT MAINTENANCE, BIOMEDICAL; GAS AND VACUUM SYSTEMS, CENTRALLY PIPED MEDICAL; VENTILATORY MONITORING.

ANESTHESIA MONITORING.

See MONITORING IN ANESTHESIA.

ANESTHESIA, COMPUTERS IN

LE YI WANG
HONG WANG
Wayne State University
Detroit, Michigan

INTRODUCTION

Computer applications in anesthesia patient care have evolved with advancement of computer technology, information processing capability, and anesthesia devices and procedures.

Anesthesia is an integral part of most surgical operations. The objectives of anesthesia are to achieve hypnosis (consciousness control), analgesia (pain control), and immobility (body movement control) simultaneously throughout surgical operations, while maintaining the vital functions of the body. Vital functions, such as respiration and circulation of blood, are assessed by signs such as blood pressures, heart rate, end-tidal carbon dioxide (CO_2), oxygen saturation by pulse oximetry (SpO_2), and so on. These objectives are



Figure 1. Some anesthesia equipment in an operating room.

carefully balanced and maintained by a dedicated anesthesia provider using a combination of sedative agents, hypnotic drugs, narcotic drugs, and, in many surgeries, muscle relaxants. Anesthesia decisions and management are complicated tasks, in which anesthetic requirements and agent dosages depend critically on the surgical procedures, the patient's medical conditions, drug interactions, and coordinated levels of anesthesia depth and physiological variables. Anesthesia decisions impact significantly on surgery and patient outcomes, drug consumptions, hospital stays, and therefore quality of patient care and healthcare cost (Fig. 1).

Computer technologies have played essential roles in assisting and improving patient care in anesthesia. Development of computer technology started from its early stages of bulky computing machines, progressed to minicomputers and microcomputers, exploded with its storage capability and computational speed, and evolved into multiprocessor systems, distributed systems, computer networks, and multimedia systems. Computer applications in anesthesia have taken advantage of this technology advancement. Early computer applications in medicine date back to the late 1950s when some hospitals began to develop computer data processing systems to assist administration, such as storage, management, and analysis of patient and procedural data and records. The main goals were to reduce manpower in managing ever-growing patient data, patient and room scheduling, anesthesia supply tracking, and billing. During the past four decades computer utility in anesthesia has significantly progressed to include computer-controlled fluid administration and drug dispersing, advanced anesthesia monitoring, anesthesia information systems, computer-assisted anesthesia control, computer-assisted diagnosis and decisions, and telemedicine in anesthesia.

COMPUTER UTILITY IN ADVANCED ANESTHESIA MONITORING

The quality of anesthesia patient care has been greatly influenced by monitoring technology development. A patient's state during a surgery is assessed using vital signs. In earlier days of anesthesiology, vital signs were limited to manual measurements of blood pressures, stethoscope auscultation of heart–lung sounds, and heart rates. These values were measured intermittently and as needed during surgery. Thanks to advancement of materials, sensing methods, and signal processing techniques, many vital signs can now be directly, accurately, and continuously measured. For example, since the invention of pulse oximetry in the early 1980s, this noninvasive method of continuously monitoring the arterial oxygen saturation level in a patient's blood (SpO_2) has become a standard method in the clinical environment, resulting in a significant improvement of patient safety. Before this invention, blood must be drawn from patients and analyzed using laboratory equipment.

(a) Paramagnetic Oxygen Analyzer in 1940 (b) Carbon Dioxide Monitor in 1960

Figure 2. Anesthesia monitoring devices without computer technologies. (Courtsey of Sheffield Museum of Anesthesia used with permission.)

Integrating these vital signs into a comprehensive anesthesia monitoring system has been achieved by computer data interfacing, multisignal processing, and computer graphics. Advanced anesthesia monitors are capable of acquiring multiple signals from many vital sign sensors and anesthesia machine itself, displaying current readings and historic trends, and providing audio and visual warning signals. At present, heart rate, electrocardiogram (ECG), arterial blood pressures, temperature, ventilation parameters (inspired–expired gas concentration, peak airway pressure, plateau airway pressure, inspired and expired volumes, etc.), end-tidal CO_2 concentrations, blood oxygen saturation (SpO_2), and so on, are routinely and reliably monitored (Figs. 2 and 3).

However, there are still many other variables reflecting a patient's state that must be inferred by the physician, such as anesthesia depth and pain intensity. Pursuit of new

Figure 3. An anesthesia monitor from GE Healthcare in 2005. (Courtsey of GE Healthcare.)

physiological monitoring devices for direct and reliable measurements of some of these variables is of great value and imposes great challenges at the same time (1). Anesthesia depth has become a main focus of research in the anesthesia field. At present, most methods rely in part or in whole on processing of the electroencephalogram (EEG) and frontalis electromyogram (FEMG) signals. Proposed methods include the median frequency, spectral edge frequency, visual evoked potential, auditory evoked potential, entropy, and bispectral index (2,3). Some of these technologies have been commercialized, leading to several anesthesia depth monitors for use in general anesthesia and sedation. Rather than using indirect implications from blood pressures, heart rate, and involuntary muscle movements to derive consciousness levels, these monitors purport to give a direct index of a patient's anesthesia depth. Consequently, combined effects of anesthesia drugs on the patient anesthesia depth can potentially be understood clearly and unambiguously. Currently (the year 2005), the BIS Monitor by Aspect Medical Systems, Inc. (www.aspectmedical.com), Entropy Monitor by GE Healthcare (www.gehealthcare.com), and Patient State Analyzer (PSA) by Hospira, Inc. (www.hospira.com) are three FDA (U.S. Food and Drug Administration) approved commercial monitors for anesthesia depth.

Availability of commercialized anesthesia depth monitors has prompted a burst of research activity on computerized depth control. Improvement of their reliability remains a research frontier. Artifacts have fundamental impact on reliability of EEG signals. In particular, muscle movements, eye blinks, and other neural stimulation effects corrupt EEG signals, challenging all the methods that rely on EEG to derive anesthesia depth. As a result, reliability of these devices in intensive care units (ICU) and emergency medicine remains to be improved.

Another area of research is pain-intensity measurement and monitoring. Despite a long history of research and development, pain intensity is still evaluated by subjective assessment and patient self-scoring. The main thrust is to establish the relation between subjective pain scores, such as the visual analog scale (VAS) system, and objective measures of vital signs. Computer-generated objective and continuous monitoring of pain will be a significant advance in anesthesia pain control. This remains an open and active area of research and development (R&D). As an intermediate step, patient-controlled analgesia (PCA) devices have been developed (see, e.g., LifeCare PCA systems from Hospira, Inc., which is a 2003 spin-off of Abbott Laboratories) that allow a patient to assess his/her pain intensity and control analgesia as needed.

Currently, anesthesia monitors are limited to data recording and patient state display. Also, their basic functions do not offer substantial interaction with human and environment. Future monitors must enhance fundamentally human-factors design: Intelligent human–machine interface and integrated human–machine–environment systems (4). Ideally, a monitor will intelligently organize observation data into useful information, adapt its functions according to surgical and anesthesia events, select the most relevant information to display, modify its display layouts to reduce distraction and amplify essential information, tune safety boundaries for its warning systems on the basis of the individual medical conditions of the patient, analyze data to help diagnosis and treatment, and allow user-friendly interactive navigation of the monitor system. Such a monitor will eventually become an extension of a physician's senses and an assistant of decision-making processes.

COMPUTER INFORMATION TECHNOLOGY IN ANESTHESIA

Anesthesia Information Systems

Patient information processing systems have undergone a long history of evolution. Starting in the 1960s, some computer programming software and languages were introduced to construct patient information systems. One example is MUMPS (Massachusetts General Hospital Utility Multi-Programming System), which was developed in Massachusetts General Hospital and used by other hospitals, as well as the U.S. Department of Defense and the U.S. Veteran's Administration. During the same period, Duke University's GEMISCH, a multi-user database programming language, was created to streamline data sharing and retrieval capabilities.

Currently, a typical anesthesia information system (AIS) consists of a central computer station or a server that is interconnected via wired or wireless data communication networks to many subsystems. Subsystems include anesthesia monitors and record-keeping systems in operating rooms, preoperative areas, postanesthesia care units (PACU), ICUs; data entry and record systems of hospital testing labs; office computers of anesthesiologists. The system also communicates with hospital mainframe information systems to further exchange information with in- and out-patient care services, patient database, and billing systems.

Information from an operating room is first collected by medical devices and anesthesia monitors and locally sorted and recorded in the record-keeping system. Selected data are then transmitted to the mainframe server through the data network. Anesthesia events, procedures, physician observations and diagnosis, patient care plans, testing results, drug and fluid data can also be entered into the record-keeping system, and broadcast to the main server and/or other related subsystems.

The main server and observation station provide a center in which patient status in many operating rooms, preoperative area and PACUs can be simultaneously monitored in real time. More importantly, the central anesthesia information system keeps accurately patient data and makes them promptly accessible to many important functions, including patient care assessment, quality assurance, room scheduling, physician assignment, clinical studies, medical billing, regulation compliance, equipment and personnel utility, drug and blood inventory, postoperative in-patient and out-patient service, to name just a few examples (Fig. 4).

One example of AIS is the automation software system CareSuite of PICIS, Inc. (www.picis.com). The system delivers comprehensive perioperative automation. It provides surgical



Figure 4. An illustration of a surgical/anesthesia information management system from surgical information systems, Inc. (www. orsoftware.com).

and anesthesia supply management, intraoperative nursing notes, surgical infection control monitoring, adverse event tracking and intervention, patient tracking, resource tracking, outlier alerts, anesthesia record, anesthesia times, case compliance, and so on. Similarly, the surgical and anesthesia management software by Surgical Information Systems (SIS), Inc. (www.orsoftware.com) streamlines patient care and facilitates analysis and performance improvement.

Anesthesia information systems are part of an emerging discipline called medical informatics, which studies clinical information and clinical decision support systems. Although technology maturity of computer hardware and software has made medical information systems highly feasible, creating seamless exchange of information among disparate systems remain a difficult task. This presents new opportunities and challenges for broader application of medical informatics in anesthesia practice.

Computer Simulation: Human Patient Simulators

Human patient simulators (HPS) are computerized mannequins whose integrated mechanical systems and computer hardware, and sophisticated computer software mimic authentically many related physiological, pathological, and pharmacological aspects of the human patient during a surgery or a medical procedure (Fig. 5). The mannequins are designed to simulate an adult or pediatric patient of either gender under a medical stress condition. They are accommodated in a clinical setting, such as an operating room, a trauma site, an emergence suite, or an ICU. Infusion pumps use clean liquid (usually water) through bar-coded syringes, whose barcodes are read by the HPS code recognition system to identify the drugs, to administer the simulated drugs, infusion liquids, or transfused blood during an anesthesia administration. The HPS allows invasive procedures such as intubation.

The HPS responds comprehensively to administered drugs, surgical events, patient conditions, and medical crisis; and displays on standard anesthesia monitors most related physiological vital signs, including blood pressures, heart rate, EKG, and oxygen saturations. They also generate normal and adventurous heart and lung sounds for auscultation. All these characteristics are internally generated by the computer software that utilizes mathematics models of typical human patients to simulate the human responses. The patient's physical parameters (age, weight, smoker, etc.), preexisting medical conditions (high blood pressure, asthma, diabetic, etc.), surgical procedures, clinical events, and critical conditions are easily programmed by a computer Scenario Editor with a user-friendly graphical interface. The Scenario Editor also allows interactive reprogramming of scenarios during an operation. This on-the-fly function of scenario generation is especially useful for training. It gives the instructor great flexibility to create new scenarios according to the trainee's reactions to previous scenarios.

The HPS is a great educational tool that has been used extensively in training medical students, nurse anesthetists, anesthesia residents, emergency, and battlefield



Figure 5. Human patient simulator complex at Wayne State University.

Figure 6. Anesthesia resident training on an HPS manufactured by METI, Inc. (Used with permission.)

medics. Its preliminary development can be traced back to the 1950s, with limited computer hardware or software. Its more comprehensive improvement occurred in pace with computer technology in the late 1960s when highly computerized models were incorporated into high fidelity HPS systems with interfaces to external computers.

Due to rareness of anesthesia crisis, student and resident training on frequent and repeated critical medical conditions and scenarios is not possible in operating rooms. The HPS permits the trainee to practice clinical skills and manage complex and critical clinical conditions by generating and repeating difficult medical scenarios. The instructor can design individualized programs to evaluate and improve trainees' crisis management skills. For invasive skills, such as intubation, practice on simulators is not harmful to human patients. Catastrophic or basic events are presented with many variations so that trainees can recognize their symptoms, diagnose their occurrences, treat them according to established guidelines, and avert disasters. For those students who have difficulties to transform classroom knowledge to clinical hands-on skills, the HPS training is a comfortable bridge for them to rehearse in simulated clinical environments (5) (Fig. 6).

There are several models of HPSs on market. For example, the MedSim-Eagle Patient Simulator (Fig. 7) is a realistic, hands-on simulator of the anesthetized or critically ill patient, developed at Stanford University and manufactured by Eagle Simulation, Inc. METI (Medical Education Technologies, Inc.) (www.meti.com) manufactures adult HPS (Stan), pediatric HPS (PediaSim), emergency care simulator (ECS), pediatric emergency simulator (PediaSim-ECS), and related simulation suites such as airway tools (AirSim), surgical training tools (SurgicalSim). Laerdal Medical AS (www.laerdal.com) has developed a comprehensive portable HPS that can be operated without the usual operating room settings for HPS operations.

Human simulations, however, are not a total reality. Regardless how comprehensive the HPS has become, real environments are far more complex. There are many complications that cannot be easily simulated. Consequences of overly aggressive handling of certain medical catastrophic events may not be fully represented. Issues like these have prompted further efforts in improving HPS technologies and enhancing their utilities in anesthesia education, training, and research.



Figure 7. A human patient simulator SimMan, by Laerdal Medical Corporation. (Used with permission.)



Figure 8. Telemedicine connects remote medical centers for patient care.

Large Area Computer Networks: Telemedicine in Anesthesia

Telemedicine can be used to deliver healthcare over geographically separated locations. High speed telecommunication systems allow interactive video-mediated clinical consultation, and the possibility in the future of remote anesthesia administration. Wide availability of high speed computer and wireless network systems have made telemedicine a viable area for computer applications. Telemedicine could enable the delivery of specialized anesthesia care to remote locations that may not be accessible to high quality anesthesia services and knowledge, may reduce significantly travel costs, and expand the supervision capability of highly trained anesthesiologists.

In a typical telemedicine anesthesia consultation, an anesthesiologist in the consultation center communicates by a high speed network with the patient and the local anesthesia care provider, such as a nurse, at the remote location (Fig. 8). Data, audio and video connections enable the parties to transfer data, conduct conversations on medical history and other consultation routines, share graphs, discuss diagnosis, and examine the patient by cameras. The anesthesiologist can evaluate the airway management, ventilation systems, anesthesia monitor, and cardiovascular systems. Heart and lung sound auscultation can be remotely performed. Airway can be visually examined. The anesthesiologist can then provide consultation and instructions to the remote anesthesia provider on anesthesia management.

Although telemedicine is a technology-ready field of computer applications and has been used in many medicine specialties, at present its usage for systematic anesthesia consultation remains at its infancy. One study reports a case of telemedicine anesthesia between the Amazonian rainforests of Ecuador and Virginia Commonwealth University, via a commercially developed telemedicine system (6). In another pilot study, the University Health Network in Toronto utilized Northern Ontario Remote Telecommunication Health (NORTH) Network to provide telemedicine clinical consultations to residents of central and northern Ontario in Canada (7).

COMPUTER-AIDED ANESTHESIA CONTROL

The heart of most medical decisions is a clear understanding of the outcome from drug administration or from specific procedures performed on the patient. To achieve a satisfactory decision, one needs to characterize outcomes (outputs), establish causal links between drugs and procedures (inputs) and the outcomes, define classes of decisions in consideration (classes of possible actions and controllers), and design actions (decisions and control). Anesthesia providers perform these cognitive tasks on the basis of their expertise, experience, knowledge of guidelines, and their own subjective judgments. It has long been perceived in the field of anesthesiology that computers may help in this decision and control process.

At a relatively low level of control and decision assistance, there has been routine use by anesthesia providers of computers to supply comprehensive and accurate information about anesthesia drugs, procedures, and guidelines in relation to individual patient care. Thanks to miniaturization and internets, there are now commonly and commercially available digital reference databases on anesthesia drugs, their detailed user manuals, and anesthesia procedures. With a palm-held device, all information becomes readily available to anesthesia providers in operating rooms, and other clinical settings. New data can be routinely downloaded to keep information up-to-date.

More challenging aspects of computer applications are those involving uncertainty, control, and intelligence that are the core of medical decision processes. These include individualized models of human patients, outcome prediction, computer-assisted control, diagnosis, and decision assistance. Such tools need to be further developed and commercialized for anesthesia use.



Figure 9. Utility of patient models to predict outcomes of drug infusion.

Patient Modeling and Outcome Prediction

Response of a patient's physiological and pathological state to drugs and procedures is the key information that an anesthesiologist uses in their management. The response, that is, the outcome, can be represented by either the values of the patient vital signs such as anesthesia depth and blood pressures, or consequence values such as length of ICU stay, hospital stay, complications. Usually, drug impact on patient outcomes is evaluated in clinical trials on a large and representative population and by subsequent statistical analysis. These population-based models (average responses of the selected population) link drug and procedural inputs to their effects on the patient state. These models can then be used to develop anesthesia management guidelines (Fig. 9).

For real-time anesthesia control in operating rooms, the patient model also must represent dynamic aspects of the patient response to drugs and procedures (8). This real-time dynamic outcome prediction requires a higher level of modeling accuracy, and is more challenging than off-line statistical analysis of drug impact. Real-time anesthesia control problems are broadly exemplified by anesthesia drug infusion, fluid resuscitation, pain management, sedation control, automated drug rates for diabetics, and so on.

There have been substantial modeling efforts to capture pharmacokinetic and pharmacodynamic aspects of drug impact as well as their control applications (9). These are mostly physiology-based and compartment-modeling approaches. By modeling each process of infusion pump dynamics, drug propagation, concentration of drugs on various target sites, effect of drug concentration on nerve systems, physiological response to nerve stimulations, and sensor dynamics, an overall patient response model can be established. Verification of such models has been performed by comparing model-predicted responses to measured drug concentration and physiological variables. These models have been used in evaluating drug impact, decision assistance and control designs.

Computer Automation: Anesthesia Control Systems

At present, an anesthesiologist decides on an initial drug control strategy by reviewing the patient's medical conditions, then adapts the strategy after observing the patient's actual response to the drug infusion. The strategy is further tuned under different surgical events, such as incision, operation, and closing. Difficulties in maintaining smooth and accurate anesthesia control can have dire consequences, from increased drug consumption, side effects, short- and long-term impairments, and even death. Real-time and computer-assisted information processing can play a pivotal role in extracting critical information, deriving accurate drug outcome predictions, and assisting anesthesia control.

Research efforts to develop computer-assisted anesthesia control systems have been ongoing since the early 1950s (10–14). The recent surge of interest in computer-assisted anesthesia diagnosis, prediction, and controls is partly driven by the advances in anesthesia monitoring technologies, such as depth measurements, computer-programable infusion pumps, and multisignal real-time data acquisition capabilities. These signals provide fast and more accurate information on the patient state, making computer-aided control a viable possibility. Research findings from computer simulations, animal studies, and limited human trials, have demonstrated that many standard control techniques, such as proportional-integral-derivative (PID) controllers, nonlinear control techniques, fuzzy logic, model predictive control, can potentially provide better performance under routine anesthesia conditions in operating rooms (Fig. 10).

Target Concentration and Effect Control. Target concentration or drug effect control is an open-loop control strategy. It relies on computer models that relate drug infusion rates to drug concentrations on certain target sites or to drug effects on physiological or nerve systems. Since at present drug concentration or drug effects are not directly measured in real-time, feedback control is often not possible. Implementation of this control strategy can be briefly described as follows. For a prespecified time interval, the desired drug concentration profile is defined. This profile is usually determined *a priori* by expert knowledge, safety mandates, and smooth control requirements. A performance index is then devised that includes terms for control accuracy (to follow the desired profiles closely), drug consumption, constraints on physiological variables (safety constraints), and so on. Then, an optimal control is derived by optimizing the performance index under the given constraints and the dynamic



Figure 10. Computer-assisted drug infusion control (a) without expert interference: automated anesthesia feedback control. (b) With expert interference: anesthesia decision assistance systems.

models of the patient. One common method of designing optimal control strategies is dynamic programming, although many other optimal or suboptimal control design methodologies for nonlinear control systems are also available in the control field. Due to lack of feedback correction in target concentration control, optimality and accuracy of control actions may be compromised. However, even this open-loop control has seen many successful applications, such as glucose level control. Feedback control may become feasible in the future when new sensors become available to measure directly drug concentration.

Automatic Feedback Control. Computer-assisted anesthesia control has been frequently compared to autopilot systems in aviation. The autopilot system controls flying trajectories, altitude and position, airplane stability and smoothness, automatically with minimum human supervision. Success of such systems has resulted in their ubiquitous applications in most airplanes. It was speculated that an anesthesia provider's routine control tasks during a surgery may be taken over by a computer that adjusts automatically drug infusions to maintain desirable patient states. Potential and speculated advantages of such systems may include less reliance on experience, avoidance of fatigue-related medical mistakes, smoother control outcomes, reduced drug consumptions, and consequently faster recovery. So far, these aspects have been demonstrated only in a few selective cases of research subjects.

System Identification and Adaptive Control for Individualized Control Strategies. One possible remedy for compensating variations in surgical procedures and patient conditions in control design is to use real-time data to adjust patient models that are used in either target concentration control or feedback control. Successful implementation of this idea will generate individualized models that will capture the unique characteristics of the patient. This real-time patient model can then be used to tune the controllers that will deliver best performance for the patient. This control tuning is the core idea of adaptive control systems: Modifying control strategies on the basis of individually identified patient models. Adaptive control has been successfully applied to a vast array of industrial systems. The main methods of model reference adaptive control, gain scheduling, self-tuning regulators, and machine learning are potentially applicable in anesthesia control. This is especially appealing since variations and uncertainties in patient conditions and surgical events and procedures are far more complicated than industrial systems.

Most control algorithms that have been employed in anesthesia control are standard. The main difficulties in applying automated anesthesia control are not the main control methodologies, but rather an integrated system with high reliability and robustness, and well-designed human-machine interaction and navigation. Unlike an airplane in midair or industrial systems, anesthesia patients vary vastly in their responses to drugs and procedures. Control strategies devised for a patient population may not work well in individual patients. Real-time, on-site, and automatic calibration of control strategies are far more difficult than designing an initial control strategy for a patient population. Adaptation adds a layer of nonlinear feedback over the underlying control, leading to adaptive PID, tuned fuzzy, adaptive neural frameworks, and so on. Stability, accuracy, and robustness of such control structures are more difficult to establish. Furthermore, human interference must be integrated into anesthesia control systems to permit doctors to give guidelines and sometimes take control. Due to high standard in patient safety, at present automated anesthesia control remains largely in a phase of research, and in a very limited sense, toward technology transfer to medical devices. It will require a major commercialization effort and large clinical studies to transform research findings into product development of anesthesia controllers.

Moreover, medical complications occur routinely, which cannot be completely modeled or represented in control strategies. Since such events usually are not automatically measured, it is strenuous to compensate their impact quickly. In addition, medical liability issues have raised the bar of applying automated systems. These concerns have curtailed a widespread realization of automated anesthesia control systems, despite a history of active research over four decades on anesthesia control systems.

COMPUTER INTELLIGENCE: DIAGNOSIS AND DECISION ASSISTANCE

In parallel to development of automatic anesthesia control systems, a broader application of computers in anesthesia management is computer-aided anesthesia diagnosis, decision assistance, and expert systems. Surveys of anesthesia providers have indicated that the field of anesthesiology favors system features that advise or guide rather than control (15). Direct interventions, closed-loop control, lockout systems, or any other coercive method draw more concerns. In this aspect, it seems that anesthesia expert decision support systems may be an important milestone to achieve before automated systems.

Anesthesia Diagnosis and Decision Assistance

Computer-aided diagnosis will extract useful information from patient data and vital-sign measurements, apply computerized logic and rigorous evaluations of the data, provide diagnosis on probable causes, and suggest guideline-driven remedy solutions. The outcome of the analysis and diagnosis can be presented to the anesthesia care provider with graphical displays, interactive user interfaces, and audio and visual warnings.

Decision assistance systems provide decision suggestions, rather direct and automatic decision implementations. Such systems provide a menu of possible actions for an event, or dosage suggestions for control purposes, and potential consequences of selected decisions. Diagnosis of possible causes can remind the anesthesiologist what might be overlooked in a crisis situation. The system can have interactive interfaces to allow the physician to discuss further actions and the corresponding outcomes with the computer. This idea of physician-assistant systems aims to provide concise, timely, and accurate references to the anesthesiologist for improved decisions. Since the physician remains as the ultimate decision maker, their management will be enhanced by the available information and diagnosis, but not taken over.

Suggested remedies of undesirable events are essentially recommendations from anesthesia management guidelines, brought out electronically to the anesthesiologist. Some computer simulators for anesthesia education are developed on the basis of this idea. For example, Anesthesia Simulator by Anesoft Corporation (www.anesoft.com) contains a software module of expert consultation that incorporates anesthesia emergency scenarios and suggests expert advices. Utility of expert systems in resident training has been widely accepted. However, decision support systems in the operating rooms are slow in development and acceptance. Generally speaking, a decision support system must interact with the complicated cognitive environment of the operating rooms. To make such systems a useful tool, they must be designed to accommodate the common practice in which the anesthesiologist thinks, sees, and reasons, rather than imposing a complicated new monitoring mode for the clinician to be retrained. This is again an issue of human-factors design.

Dosage recommendations for anesthesia drugs are internally derived from embedded modeling and control strategies. In principle, the control strategies discussed in the previous sections can support the decision assistance system. By including the physician in the decision loop, some issues associated with automated control systems can be alleviated. Reliability of such control strategies, user interfaces, and clinical evidence of cost-effectiveness of the decision support system will be the key steps toward successful clinical applications of such systems.

FUTURE UTILITY OF COMPUTER TECHNOLOGY IN ANESTHESIA

The discussions in the previous sections outline briefly critical roles that computers have played in improving anesthesia management. New development in computer-related technologies are of much larger potential.

Micro-Electro-Mechanical Systems (MEMS) is a technology that integrates electrical and mechanical elements on a common silicon material. This technology has been used in developing miniature sensors and actuators, such as micro infusion pumps and *in vivo* sensors. Integrated with computing and communication capabilities, these devices become smart sensors and smart actuators. The MEMS technology has reached its maturity. Further into the realms of fabrication technology at atom levels, emergence of nanotechnology holds even further potential of new generations of medical devices and technologies. There are many exciting possibilities for utility of these technologies in anesthesia: *In vitro* sensors based on nanodevices can potentially pinpoint drug concentrations at specific target sites, providing more accurate values for automated anesthesia drug control; Microactuators can directly deliver drugs to the target locations promptly and accurately, reducing drastically reliance on trial-and-error and sharpened experience in anesthesia drug infusion control; MEMS and nanosensors together with computer graphical tools will allow two-dimensional (2D) or three-dimensional (3D) visual displays of drug propagation, drug concentration, distributed blood pressures, heart and lung functions, brain functions, consequently assisting anesthesiologists in making better decisions about drug delivery for optimal patient care.

On another frontier of technology advancement, computer parallel computing (many computers working in symphony to solve complicated problems), computer imaging processing, data mining (extracting useful information from large amount of data), machine intelligence, wireless communication technologies, and human-factors science and design provide a vast opportunity and a promising horizon in advancing anesthesia management.

Advanced anesthesia control systems will manage routine drug infusion with their control actions tuned to individual patients' conditions and surgical procedures, relieving anesthesiologists from stressful and strenuous routine tasks to concentrate on higher level decisions in patient care.

Patient physiological conditions can be more accurately and objectively measured by computer-processed sensor and imaging information.

Computer-added imaging processing will make it possible to consolidate information from CT-Scan (Computed Tomography), TEE (Transesophageal Echocardiography), MRI (Magnetic Resonance Imaging), and fMRI (Functional Magnetic Resonance Imaging) into regular anesthesia monitoring.

Anesthesia decisions will be assisted by computer database systems and diagnosis functions.

Anesthesia monitoring devices will become wireless, eliminating the typical spaghetti conditions of monitoring cables in operating rooms.

Anesthesia information systems will become highly connected and standard in anesthesia services, automating and streamlining the total patient care system: From patient admission to patient discharge, as well as follow-up services.

BIBLIOGRAPHY

Cited References

1. Penelope M, et al. Advanced patient monitoring displays: tools for continuous informing. Anesthes Analges 2005;101: 161–168.
2. Bonhomme V, et al. Auditory steady-state response and bispectral index for assessing level of consciousness during propofol sedation and hypnosis. Intravenous Anesthes 2000; 91:1398–1403.
3. Drummond JC. Monitoring depth of anesthesia. Anesthesiology 2000;93(3):876–882.
4. Blike GT. Human factors engineering: It's all about 'usability'. ASA Newslett Oct. 2004;68.
5. Peteani LA. Enhancing clinical practice and education with high-fidelity human patient simulators. Nurse Educ 2004; 29(1):25–30.
6. Stephen W, et al. Case report of remote anesthetic monitoring using telemedicine. Anesthes Analges 2004;98:386–388.
7. Wong DT, et al. Preadmission anesthesia consultation using telemedicine technology: A pilot study. Anesthesiology June 2004;100(6):1605–1607.
8. Wang LY, Yin G, Wang H. Identification of Wiener models with anesthesia applications. Int J Pure Appl Math Sci 2004; 35–61.
9. Shafer A, Doze VA, Shafer SL, White PF. Pharmacokinetics and pharmacodynamics of propofol infusions during general anesthesia. Anesthesiology 1988;69:348–356.
10. Eisenach JC. Reports of scientific meetings-workshop on safe feedback control of anesthetic drug delivery. Anesthesiology August 1999;91:600–601.
11. Linkens DA, Hacisalihzade SS. Computer control systems and pharmacological drug administration: A survey. J Med Eng Technol 1990;14(2):41–54.
12. Mortier EM, et al. Closed-loop controlled administration of Propofol using bispectral analysis. Anaesthesia 1998;53: 749–754.
13. Rao RR, et al. Automaded regulation of hemodynamic variables. IEEE Eng Med Biol Mag 2001;20:24–38.
14. Tackley RM, et al. Computer controlled infusion of propofol. Br J Anesthes 1989;62:46–53.
15. Beatty PT, et al. User attitudes to computer-based decision support In anesthesia and critical care: A preliminary survey. Internet J Anesthesiol 1999;3(1).

See also ANESTHESIA MACHINES; CARDIAC OUTPUT, THERMODILUTION MEASUREMENT OF; ELECTROCARDIOGRAPHY, COMPUTERS IN; ELECTROENCEPHALOGRAPHY; MEDICAL RECORDS, COMPUTERS IN; MONITORING IN ANESTHESIA.

ANGER CAMERA

MARK T. MADSEN
University of Iowa

INTRODUCTION

In nuclear medicine, radioactive tracers are used to provide diagnostic information for a wide range of medical indications. Gamma-ray emitting radionuclides are nearly ideal tracers, because they can be administered in small quantities and yet can still be externally detected. When the radionuclides are attached to diagnostically useful compounds (1), the internal distribution of these compounds provides crucial information about organ function and physiology that is not available from other imaging modalities. The Anger camera provides the means for generating images of the radiopharmaceuticals within the body. Example images of some common studies are shown in Figs. 1 and 2.

Initially, nonimaging detectors were used to monitor the presence or absence of the radiotracer. However, it was clear that mapping the internal distribution of the radiotracers would provide additional diagnostic information. In 1950, Benedict Cassen introduced the rectilinear scanner. The rectilinear scanner generated images of radionuclide distributions by moving a collimated sodium iodide detector over the patient in a rectilinear fashion. The detected count rate modulated the intensity of a masked light bulb that scanned a film in an associated rectilinear pattern. While this device did produce images, it was very slow and had no capability for imaging rapidly changing distributions. The rectilinear scanner was used into the 1970s, but was finally supplanted by the Anger camera (2–5).

The Anger camera, also referred to as the scintillation camera (or gamma camera), is a radionuclide imaging device that was invented by Hal O. Anger. It is the predominant imaging system in nuclear medicine and is responsible for the growth and wide applicability of nuclear medicine. Anger was born in 1920. He received his BS degree in electric engineering from the University of California at Berkeley in 1943 and in 1946 he began working at the Donner Laboratories, where he developed a large number of innovative detectors and imaging devices including the scintillation well counter and a whole body rectilinear scanner using 10 individual sodium iodide probes. In 1957, he completed his first gamma



Figure 1. Anger camera clinical images. A. Lung ventilation and perfusion images are used to diagnose pulmonary emboli. B. Renal function images are used to diagnose a variety of problems including renal hypertension and obstruction. C. Gated blood pool studies permit evaluation of heart wall motion and ejection fraction.

imaging camera that he called a scintillation camera and is often referred to as the Anger camera (6). Anger's scintillation camera established the basic design that is still in use today. The first Anger camera had a 10 cm circular field of view, seven photomultiplier tubes, pinhole collimation, and could only be oriented in one direction. A picture of this initial scintillation camera is shown in Fig. 3 and a schematic drawing of the electronics is shown in Fig. 4. In 1959, Anger adapted the scintillation camera for imaging positron emitting radionuclides without collimation using coincidence between the camera and a sodium iodide detector. He also continued improving the scintillation camera for conventional gamma emitting radionuclides. By 1963, he had a system with a 28 cm field of view and 19 photomultiplier tubes (7). This device became commercialized as the nuclear Chicago scintillation camera. Throughout the 1960s, 1970s, and 1980s Anger remained active at Donner labs developing numerous other radionuclide imaging devices. He has received many prestigious awards including the John Scott Award (1964), a Guggenheim fellowship (1966), an honorary Doctor of Science degree from Ohio State University (1972), the Society of Nuclear Medicine Nuclear Pioneer Citation (1974), and the Society of Nuclear Medicine Benedict Cassen Award (1994) (8–10).

About the same time that the Anger camera was introduced, the molybdenum-99/technetium-99m radionuclide generator became available. This finding is mentioned because the advantages offered by this convenient source of ^{99m}Tc had a large influence on the development of the Anger camera. Technetium-99m emits a single gamma ray at 140 keV, has a 6 h half-life and can be attached to a large number of diagnostically useful compounds. Because it is available from a generator, it also has a long shelf life. The ^{99m}Tc is used in $> 80\%$ of nuclear medicine imaging studies. As a result, both the collimation and detector design of the Anger camera has been optimized to perform well at 140 keV (1).

SYSTEM DESCRIPTION

The Anger camera is a position sensitive gamma-ray imaging device with a large field of view. It uses one



Figure 2. Anger camera clinical images. A. Bone scans are used to evaluate trauma and metastatic spread of cancer. B. Myocardial perfusion studies are used to evaluate coronary artery disease.

large, thin sodium iodide crystal for absorbing gamma-ray energy and converting that into visible light. The light signal is sampled by an array of photomultilier tubes that convert the light signal into an electronic pulse. The pulses from individual PMTs are combined in two ways. An energy pulse is derived from the simple summation of the PMT signals. The *X* and *Y* locations of the event are calculated from the sum of the PMT signals after position-dependent weighting factors have been applied. When a signal from a detected event falls within a preselected energy range, the *X* and *Y* locations are recorded in either list or frame modes. The components that make up the Anger camera are shown in Fig. 5 and are described in detail in the following section (11,12).

Sodium Iodide Crystal

Sodium iodide activated with thallium, NaI(Tl), is the detecting material used throughout nuclear medicine. Sodium iodide is a scintillator giving off visible light when it absorbs X- or gamma-ray energy. At room temperature, pure NaI has very low light emission, however, when small amounts (parts per million, ppm) of thallium are added, the



Figure 3. Initial Anger camera used to image a patient's thyroid with I-131. The field of view of this device was 10 cm. (Reprinted from Seminars in Nuclear Medicine, Vol 9, Powell MR, H.O. Anger and his work at Donner Laboratory, 164–168., 1979, with permission from Elsevier.)


Y+
Multiplier phototubes
20
40
20
40
20
10
10
Sodium iodide crystal
30
30
6
1
20
X−
X+
40
5
7
2
40
Y direction
20
4
3
X direction
30
30
10
10
20
40
20
40
20
Y−
Capacitances in pF
X−
X+
Y−
Y+
X−
X+
Y−
Y+
Difference circuit
Difference circuit
Addition circuit
X
Y
Z
Pulse-height selector
Z input
X input
Y input
Image-readout oscilloscope

Figure 4. Electronic schematic for Anger's first scintillation camera. The photomultiplier tube position weighting was accomplished with a capacitor network. (From Instrumentation in Nuclear Medicine, Hine and Sorenson, Elsevier, 1967.)

efficiency for light emission is greatly enhanced. This is an especially important aspect for its application in the Anger camera since the light signal is used to determine both the energy and location of the gamma-ray interaction with the detector. In addition to its high light ouput, NaI(Tl) has several other desirable properties. It has a relatively high effective atomic number ($Z_{\text{eff}} = 50$) and the density is $3.67\ \text{g}\cdot\text{cm}^{-3}$. This results in a high detection efficiency for gamma rays under 200 keV with relatively thin crystals (8,12–15).

Sodium iodide is grown as a crystal in large ingots at high temperatures ($> 650\ ^\circ\text{C}$). The crystals are cut, polished, and trimmed to the required size. For Anger cameras, the crystals are typically 40 × 55 cm and 9.5 mm thick. Because NaI(Tl) absorbs moisture from the air (hygroscopic), it must be hermetically sealed. Any compromise of this seal often results in the yellowing of the crystal and its irreversible destruction.

In addition to the need to keep the crystal hermetically sealed, the temperature of the detector must be kept relatively constant. Temperature changes $> 2\ ^\circ\text{C}\cdot\text{h}^{-1}$ will often shatter the detector.


Pulse height analyzer
Energy signal
Position signals
X
Y
Z
NaI(Tl) crystal
Collimator
Image display

Figure 5. Anger camera components.

Light Pipe

The scintillation light generated in the crystal is turned into electronic signals by an array of photomultiplier tubes (PMTs). These signals provide both event energy and localization information. It is desirable that the magnitude of the signal from the photomultiplier tube be linearly related to the event location as shown in Fig. 6. However, when the PMTs are in close proximity to the crystal, the relationship between the signal magnitude and the event location is very nonlinear. In early designs of the Anger camera, a thick transparent material referred to as a light pipe was coupled to the crystals to improve spatial linearity and uniformity. Glass, lucite, and quartz have been used for this purpose. Design enhancement of the light pipe included sculptured contouring to improve light collection and scattering patterns at the PMT interface to reduce positional nonlinearities (Fig. 7). In the past decade, many of the spatial nonlinearities have been corrected algorithmically operating on digitized PMT signals. This has allowed manufacturers to either reduce the thickness of the light pipe or completely eliminate it (2,16,17).

PMT Array

The visible light generated by the absorption of a gamma ray in the NaI(Tl) crystal carries location and energy information. The intensity of the scintillation is directly proportional to the energy absorbed in the event. To use this information, the scintillation must be converted into an electronic signal. This is accomplished by photomultiplier tubes. In a PMT, the scintillation light liberates electrons at the photocathode and these electrons are amplified through a series of dynodes. The overall gain available from a photomultiplier tube is on the order 10^6.

Photomultiplier tubes are manufactured in a wide variety of shapes and sizes. Those with circular, hexagonal, and square photocathodes have all been used in Anger cameras. Hexagonal and square PMTs offer some advantages for



Figure 6. Photomultiplier tube response with source position. The ideal response can be approximated by interposing a light pipe between the crystal and photomultiplier tube.

close packing the PMTs over the surface of the detector. However, the sensitivity of all PMTs falls off near the edge of the field, so that "dead" space between the PMTs is unavoidable.

It is important to determine the energy of the detected event. Gamma rays that are totally absorbed produce a scintillation signal that is directly proportional to the gamma-ray energy. Thus, the signal resulting from the unweighted sum of the PMTs represents gamma-ray energy. This signal is sent to a pulse height analyzer. Scattered radiation from within the patient can be rejected by setting an energy window to select events that have resulted from the total absorption of the primary gamma ray. Gamma rays that have been scattered in the patient necessarily lose energy and are (largely) not included.

The position of the gamma-ray event on the detector is determined by summing weighted signals from the PMTs (2,6,7,12,16,18,19). Each PMT contributes to four signals: X^+, X^-, Y^+, Y^-. The magnitude of the contribution is determined both by the amount of light collected by the PMT and its weighting factor. For the tube located exactly at the center of the detector, the four weighting factors are equal. A tube located along the x axis on the left side (e.g., tube 5 in Fig. 4) contributes equally to Y^+ and Y^-, has a large contribution to X^-, and a small contribution to X^+. In Anger's original design, the weighting factors were provided by capacitors with different levels of capacitance (Fig. 4). In commercial units, the capacitor network was replaced by resistors (Fig. 8). In the past decades, the resistor weighting matrix has been largely supplanted by digital processing where nonlinear weighting factors can be assigned in software (Fig. 9).



Figure 7. The light pipe is a transparent light conductor between the crystal and the photomultiplier tubes. The sculpturing grooves and black dot pattern spread the light to improve the positioning response of the photomultiplier tube.

It is clear that PMTs located near the event collect most of the scintillation light while those far away get relatively little. Because each PMT has an unavoidable noise component, the PMTs that receive the least light increase the error associated with the event localization. Initially, all the PMTs were included. Later, in order to eliminate PMTs that have little real signal, diodes were used to set current thresholds. In digital Anger cameras, the PMT thresholds are set in software (20–22).

The weighted signals from the PMTs are summed together to generate four position signals: X^+, X^-, Y^+, and Y^-. The X and Y locations are determined from: $(X^+ - X^-)/Z$ and $(Y^+ - Y^-)/Z$, where Z is the energy signal found from the unweighted sum of the PMT signals discussed above. This energy normalization is necessary to remove the size dependence associated with the intensity of the scintillation. This is not only important for imaging radionuclides with different gamma-ray energies, but it also improves the spatial resolution with a single gamma ray energy because of the finite energy resolution of the system. The energy signal is also sent to a pulse height analyzer where an energy window can be selected to include only those events associated with total absorption of the primary gamma.

Image Generation

Anger camera images are generated in the following way (see Fig. 10). A gamma ray is absorbed in the NaI(Tl)


Analog position electronics
Position-based signal weights
Position signal (X or Y)
Weighted sum
X/Z
Y/Z
Normalized position signal (X or Y)
Normalization
Energy signal (Z)
Total sum
Pulse height analyzer

Figure 8. The Anger camera of the 1980s used resistors to provide position weighting factors. The energy signal was used both for normalization and scatter discrimination.

crystal and the resulting scintillation light is sampled by the PMT array to determine the event energy and location. The energy signal is sent to a pulse height analyzer and if the signal falls within the selected energy window, a logic pulse is generated. At the same time, the *X* and *Y* coordinates of the event are determined and the logic pulse from the PHA enables the processing of this information. For many years, Anger camera images were generated photographically with the enabled *X* and *Y* signals intensifying a dot on a cathode ray tube (CRT) viewed by a camera. In modern Anger cameras, the CRT has been replaced with computer memory and the location information is digital. The *X* and *Y* coordinate values, still enabled by the PHA, point to a memory element in a computer matrix. The contents of that memory element are incremented by 1. Information continues to accrue in the computer matrix until the count or time stopping criteria are met.


Digital position electronics
ADC
ADC
ADC
ADC
ADC
ADC
ADC
ADC
ADC
ADC
ADC
Digital event processor
Signal weights, Position calculations, Energy summation, Normalization and pulse height analysis are all performed in software. (Light pipe is often eliminated)
Digital X location
Digital Y location

Figure 9. Digital Anger camera electronics. The photomultiplier tube signals are digitized so that signal weighting, energy and position determination are performed in software rather than with digital electronics.

The image generation described in the previous paragraph is referred to as frame or matrix mode. The information can also be stored in list mode where the *X* and *Y* coordinate of each event is stored sequentially along with a time marker. The list mode data can then be reconstructed at a later time to any desired time or spatial resolution.

Collimation

In order to produce an image of a radionuclide distribution, it has to be projected onto the detector. In a conventional camera, image projection is accomplished by the camera lens. However, gamma rays are too energetic to be focused with optics or other materials. The first solution to projecting gamma-ray images was the pinhole collimator. The pinhole collimator on an Anger camera is conceptually identical to a conventional pinhole camera. There is an inversion of the object and the image is magnified or minified depending on the ratio of the pinhole to detector distance and the object to pinhole distance. Pinhole collimators are typically constructed out of tungsten and require lead shielding around the "cone". Because the amount of magnification depends on the source to pinhole distance, pinhole images of large, three-dimensional (3D) distributions are often distorted. In addition, the count sensitivity falls off rapidly for off-axis activity. A better solution for most imaging situations is a multiholed parallel collimator (Fig. 11). As the name implies, the parallel collimator consists of a large number of holes with (typically) lead septae. Most parallel collimators have hexagonal holes that are $\sim$ 1.5 mm across and are 20–30 mm long. The septal walls are typically 0.2 mm thick. The parallel hole collimator produces projections with no magnification by brute force. Gamma rays whose trajectories go through the holes reach the detector while those with trajectories that intersect the septae are absorbed. Less than 1 out of 5000 gamma rays that hit the front surface of the collimator are transmitted through to the detector to form the image (2,7,11,12,20,23,24).


Pulse height analyzer
Energy signal
Position signals
Y
Z
X
X
NaI(T1) crystal
Collimator
1
Y
Image display

Figure 10. Schematic of Anger camera showing how image information is acquired.


d = 1.5 mm (hole width)
L = 25 mm (hole length)
t = 0.2 mm (septal thickness)
D (source to collimator distance)
*
Parallel hole collimator
Spatial resolution
$R_{Col} = d(D + L)/L$
Count efficiency
$\varepsilon = K^2(d/L)^2\,(d/d + t)^2$

Figure 11. Collimation. Collimators are the image forming aperture of the Anger Camera, but are also the limiting component in spatial resolution and count sensitivity.

The spatial resolution of the collimator, R_{col}, is determined by the hole size (d), hole length (L), and the source to collimator distance (D): $R_{\mathrm{col}} = d(L + D)/L$. The efficiency of a parallel hole collimator is expressed as $K^2(d/L)^2\,(d/d + t)^2$, where K is a shape factor constant equal to 0.26 and t is the septal wall thickness. Collimation design is an optimization problem since alterations in d and L to improve resolution will decrease count sensitivity. Collimator spatial resolution has a strong dependence on the source to collimator distance. As shown in Fig. 12, the spatial resolution rapidly falls with distance. However, the count sensitivity of a parallel hole collimator is *not* affected by the source distance because the parallel hole geometry removes the divergent rays that are associated with the inverse square loss. Another factor that influences collimator design is the energy of the gamma ray being imaged. Higher energy gamma rays require thicker septae and


5 cm
10 cm
15 cm
20 cm
25 cm
30 cm
5 cm
10 cm
15 cm
20 cm
25 cm
30 cm

Figure 12. Spatial resolution dependence on source to collimator distance.

larger holes resulting in poorer resolution and count sensitivity (2,7,25).

CORRECTIONS

The analog Anger camera had a number of limitations because of nonlinearities in the position signals and because of the uneven light collection over the NaI(Tl) crystal. As digital approaches became viable over the last two decades, a number of corrections to improve energy, spatial, and temporal resolution have evolved. All of these corrections, and particular those involving spatial and energy resolution, require system stability. This challenge was significant because of the variation in PMT output associated with environmental conditions and aging. In order for corrections to be valid over an extended period of time, a method to insure PMT stability has to be implemented. Several different approaches have evolved. In one method, PMT gains are dynamically adjusted to maintain consistent output signals in response to stabilized light emitting diodes (LEDs). An LED is located beneath each PMT where its light is sampled 10–100 times·s^{-1}. Gains and offsets on the PMTs are adjusted so that the resulting signal is held close to its reference value. Another approach uses the ratio of photopeak/Compton plateau counts from a ^{99m}Tc or ^{57}Co source as the reference.

Flood Field Image

When the Anger camera is exposed to a uniform flux of gamma rays, the resulting image is called a flood field image. Flood field images are useful for identifying nonuniform count densities and may be acquired in two different ways. An intrinsic flood field is obtained by removing the collimation and placing a point source of activity 1.5–2 m from the detector. An extrinsic flood field is obtained with the collimator in place and with a large, distributed source (often called a flood source) placed directly on the collimator. Flood field sources using ^{57}Co are commercially available. Alternatively, water-filled flood phantoms are available into which ^{99m}Tc or other radionuclide can be injected and mixed.

Energy Correction

The energy signal represents the total energy absorbed in a gamma-ray interaction with the detector. This signal is determined by the intensity of the scintillation and by how much of the scintillation light is captured by the PMTs. Because the efficiency for sampling the scintillation is position dependent, there are fluctuations in the energy signals across the detector as shown in Fig. 13. These variations degrade energy resolution and have a significant effect on the performance of the scintillation camera that limit corrections for nonuniformity. The idea of using a reference flood field image to correct nonuniformities has been around for a long time. However, if the reference flood field image is acquired with little or no scattered radiation (as it often is), the correction factors are not appropriate during patient imaging. The reason is that scattered radiation and the amount of scatter entering the selected energy window will be position dependent. Energy correction electronics was introduced in the late 1970s that essentially generated an array of energy windows that are adjusted for the local energy spectra. Typically, the detector field of view is sampled in a 64 × 64 matrix and a unique energy window is determined for each matrix element. With the energy windows adjusted on the local photopeaks, the variations in the scatter component are greatly reduced. As shown in Fig. 13, energy correction does not significantly improve intrinsic field uniformity. Its role is to reduce the influence of source scatter on the other correction factors (11,20,26–28).



Figure 13. Energy correction. Local spectral gain shifts are evident across the crystal because of the variable sampling imposed by the photomultiplier tube array.

Spatial Linearity Correction

The nonlinearities in the PMT output with respect to source location causes a miss-positioning of events when Anger logic is used. This finding can be demonstrated by acquiring an image of a straight line distribution or a grid pattern. The line image will have a “wavy” appearance (Fig. 14). In the early 1980s, a method to improve the spatial linearity was developed. An imaging phantom array of precisely located holes in a sheet of lead is placed on the uncollimated detector and is exposed to a point source of ^{99m}Tc located 1–2 m away. The image of the hole pattern is used to calculate corrective x and y offsets for each point in the field of view. These correction factors are stored in a ROM. When an event is detected and the Anger logic produces x and y coordinates, the offsets associated with these coordinates are automatically added generating the new, accurate event location. Improving the spatial linearity has a profound affect on field uniformity as can be seen in Fig. 14 (17,28–31).

Uniformity Correction

After the energy and spatial linearity corrections have been made, there are still residual nonuniformities that are present in a flood field image. Typically, these will vary $< 10\%$ from the mean count value for the entire field. A high count reference flood field image can be acquired and


Event location is estimated as x',y'
Spatial linearity correction
New location
x = x' + Δx'
y = y' + Δy'
Before correction
After correction

Figure 14. Spatial linearity correction. Accurate correction for inaccurate event localization has a profound effect on field uniformity.

this image is then used to generate regional flood correction factors that are then applied to subsequent acquisitions (Fig. 15) (17,29,32).

Pulse Pileup Correction


Uniformity correction

Figure 15. Uniformity correction. Residual non-uniformities can be reduced by skimming counts based on a reference flood field image.

An Anger camera processes each detected event sequentially. Because the scintillation persists with a decay time of 230 ns, pulses from events occurring closely in time are distorted from summation of the light. This distortion is referred to as pulse pileup. As the count rate to the detector increases, the amount of pulse pileup also increases and becomes significant at count rates $> 30{,}000$ cps. For much of conventional nuclear medicine imaging, this is not a problem since the count rate is typically well below that level. There are certain applications such as coincidence positron emission tomography (PET) imaging where the detectors are exposed to event rates that can exceed 1,000,000 cps. Because the Anger logic used to establish the event location is essentially a centroid method, pulse pileup causes errors. An example of this is shown in Fig. 16, which shows an Anger camera image of four high-count rate sources. In addition to the actual sources, false images of source activity between the sources are also observed (33,34). The effects of pulse pileup can be minimized by electronic pulse clipping, where the pulse is forced to the baseline before all the light has been emitted and processed. While this increases the count rate capability, it compromises both spatial and energy resolution, which are optimal when the whole pulse can be sampled and integrated. One approach to reduce losses in spatial and energy resolution is to alter the integration time event-by-event, based on count rate demands. In addition, algorithms have been developed that can extrapolate the pulse to correct for


Pulse pileup
Observed signal
Individual events
Time(∝s)
t_{int}
t_{int}
t_{int}
Extrapolate pulse to estimate true size
Pulse amplitude
Inseparable pileup
Valid event
Time

Figure 16. Pulse pileup correction. Pulse pileup correction improves the count rate capability and reduces the spurious placement of events.

its contribution to a second pileup pulse. This process can be repeated if a third pileup is also encountered. When this correction is performed at the PMT level, it reduces the "false" source images discussed above (35).

PERFORMANCE

Uniformity

When the Anger camera is exposed to a uniform flux of gamma rays, the image from that exposure should have a uniform count density. Anger cameras with energy, spatial linearity, and uniformity correction are uniform to within 2.5% of the mean counts.

Intrinsic Spatial Resolution

The intrinsic spatial resolution refers to the amount of blurring associated with the Anger camera independent of the collimation. It is quantified by measuring the full width at half-maximum (fwhm) of the line spread response function. The intrinsic spatial resolution for Anger cameras varies from 3 to 4.5 mm depending on the crystal thickness and the size of the PMTs. Another way of evaluating intrinsic spatial resolution for gamma-ray energies < 200 keV is with a quadrant bar phantom consisting of increasingly finer lead bar patterns where the bar width is equal to the bar spacing (Fig. 17). Typically an Anger camera can resolve a 2 mm bar pattern.

Extrinsic Spatial Resolution

The extrinsic spatial resolution, also referred to as the system spatial resolution, refers to the amount of blurring associated with Anger camera imaging. It depends on the collimation, gamma-ray energy, and the source to collimator distance. The standard method for determining the extrinsic resolution is from the fwhm of the line spread response function generated from the image of a line source positioned 10 cm from the collimator. Typical values for the extrinsic spatial resolution range from 8 to 12 mm.



Figure 17. Intrinsic spatial resolution is routinely assessed with bar pattern images. An Anger camera can typically resolve the 2 mm bar pattern.

Energy Resolution

The energy signal generated from gamma-ray absorption in the detector has statistical fluctuations that broaden the apparent energy peaks of the gamma rays. Energy resolution is determined from $100\% \times \text{fwhm}/E\gamma$, where fwhm is of energy peak and $E\gamma$ is the gamma-ray energy. At 140 keV the energy resolution of an Anger camera is 10%. Good energy resolution is important because it permits the discrimination of scattered radiation from the patient. Gamma rays that are scattered in the patient necessarily loose energy and these scattered photons degrade image quality.

Spatial Linearity

Spatial linearity refers to the accurate positioning of detected events. On an Anger camera with spatial linearity correction, the misplacement of events is < 0.5 mm.

Multiwindow Spatial Registration

Because the Anger camera has energy resolution, it can acquire images from radionuclides that emit more than one gamma ray or from two radionuclides. However, the images from different energy gamma rays may have slightly different magnifications or have offsets because of imperfections in the energy normalization. The multiwindow spatial registration parameters quantifies the misalignment between different energy gamma rays (Fig. 18). For Anger cameras, the multiwindow spatial registration is < 2 mm, which is well below the system spatial resolution and therefore is not perceptible.

Count Rate Performance

The count rate capability of Anger camera ranges from 100,000 to 2,000,000 cps depending on the sophistication of the pulse handling technology as discussed above. Anger cameras that are used for conventional nuclear medicine imaging are designed to operate with maximum count rates of 200,000–400,000 cps range, whereas Anger cameras that are used for coincidence imaging require count rate capabilities that exceed 1,000,000 cps (25,28,30,32,36–41).



Figure 18. Multi-window spatial registration refers to ability to accurately image different gamma ray energies simultaneously. The figure on the right is an example of poor multi-window spatial registration.

SUMMARY

The Anger camera has been the primary imaging device in nuclear medicine for > 30 years and is likely to remain in that role for at least the next decade. Although it has evolved with the development of digital electronics, the basic design is essentially that promulgated by H.O. Anger. Special purpose imaging instruments based on semiconductor cadmium zinc telluride detectors are actively being pursued as imaging devices for ^{99m}Tc and other low energy gamma emitters. Their pixilated design removes the need for Anger logic position determination and the direct conversion of the absorbed energy into an electronic signal removes the need for photomultiplier tubes allowing compact packaging. However, over the range of gamma-ray energies encountered in nuclear medicine, NaI(Tl) still provides the best efficiency at a reasonable cost.

BIBLIOGRAPHY

Cited References

1. Banerjee S, Pillai MR, Ramamoorthy N. Evolution of Tc-99m in diagnostic radiopharmaceuticals. Semin Nucl Med 2001;31: 260–277.
2. Hine GJ, editor. Instrumentation in Nuclear Medicine. Volume 1, New York: Academic Press; 1967.
3. Pollycove M, Fish MB, Khentigan A. Clinical radioisotope organ imaging–diagnostic sensitivity and practical factors. Rectilinear scanner versus the anger-type scintillation camera. J Nucl Med 1967;8:321–322.
4. Blahd WH. Ben Cassen and the development of the rectilinear scanner. Semin Nucl Med 1996;26:165–170.
5. McCready VR. Milestones in nuclear medicine. Eur J Nucl Med 2000;27:S49–S79.
6. Anger H. A new instrument for mapping gamma ray emitters. Bio Med Quart Rep 1957; UCRL-3653 38.
7. Anger H. Scintillation camera with multichannel collimators. J Nucl Med 1964;5:515–531.
8. Hine GJ. The inception of photoelectric scintillation detection commemorated after three decades. J Nucl Med 1977;18:867–871.
9. Powell MR. H.O. Anger and his work at the Donner Laboratory. Semin Nucl Med 1979;9:164–168.
10. Tapscott E. Nuclear medicine pioneer: Hal O. Anger. First scintillation camera is foundation for modern imaging systems. J Nucl Med 1998;39:15N, 19N, 26N–27N.
11. Murphy PH, Burdine JA. Large-field-of-view (LFOV) scintillation cameras. Semin Nucl Med 1977;7:305–313.
12. Cherry S, Sorenson J, Phelps M. Physics in Nuclear Medicine. Philadelphia: W. B. Saunders; 2003.
13. Muehllehner G. Effect of crystal thickness on scintillation camera performance. J Nucl Med 1979;20:992–993.
14. Royal HD, Brown PH, Claunch BC. Effects of a reduction in crystal thickness on Anger-camera performance. J Nucl Med 1979;20:977–980.
15. Keszthelyi-Landori S. NaI(Tl) camera crystals: imaging capabilities of hydrated regions on the crystal surface. Radiology 1986;158:823–826.
16. Anger H. Scintillation Camera. Rev Sci Instrum 1958;29: 27–33.
17. Genna S, Pang SC, Smith A. Digital scintigraphy: principles, design, and performance. J Nucl Med 1981;22:365–371.
18. Anger H. Scintllation camera with 11 inch crystal. UCRL-11184 (1963).
19. Scrimger JW, Baker RG. Investigation of light distribution from scintillations in a gamma camera crystal. Phys Med Biol 1967;12:101–103.
20. White W. Resolution, sensitivity, and contrast in gamma-camera design: a critical review. Radiology 1979;132:179–187.
21. Zimmerman RE. Gamma cameras—state of the art. Med Instrum 1979;13:161–164.
22. Goodwin PN. Recent developments in instrumentation for emission computed tomography. Semin Nucl Med 1980;10:322–334.
23. Strand SE, Lamm IL. Theoretical studies of image artifacts and counting losses for different photon fluence rates and pulse-height distributions in single-crystal NaI(T1) scintillation cameras. J Nucl Med 1980;21:264–275.
24. Kereiakes JG. The history and development of medical physics instrumentation: nuclear medicine. Med Phys 1987;14:146–155.
25. Chang W, Li SQ, Williams JJ, Bruch PM, Wesolowski CA, Ehrhardt JC, Kirchner PT. New methods of examining gamma camera collimators. J Nucl Med 1988;29:676–683.
26. Budinger TF. Instrumentation trends in nuclear medicine. Semin Nucl Med 1977;7:285–297.
27. Myers WG. The Anger scintillation camera becomes of age. J Nucl Med 1979;20:565–567.
28. Heller SL, Goodwin PN. SPECT instrumentation: performance, lesion detection, and recent innovations. Semin Nucl Med 1987;17:184–199.
29. Muehllehner G, Colsher JG, Stoub EW. Correction for field nonuniformity in scintillation cameras through removal of spatial distortion. J Nucl Med 1980;21:771–776.
30. Muehllehner G, Wake RH, Sano R. Standards for performance measurements in scintillation cameras. J Nucl Med 1981;22: 72–77.
31. Johnson TK, Nelson C, Kirch DL. A new method for the correction of gamma camera nonuniformity due to spatial distortion. Phys Med Biol 1996;41:2179–2188.
32. Murphy PH. Acceptance testing and quality control of gamma cameras, including SPECT. J Nucl Med 1987;28:1221–1227.
33. Strand SE, Larsson I. Image artifacts at high photon fluence rates in single-crystal NaI(T1) scintillation cameras. J Nucl Med 1978;19:407–413.
34. Patton JA. Instrumentation for coincidence imaging with multihead scintillation cameras. Semin Nucl Med 2000;30: 239–254.
35. Wong WH, Li H, Uribe J, Baghaei H, Wang Y, Yokoyama S. Feasibility of a high-speed gamma-camera design using the high-yield-pileup-event-recovery method. J Nucl Med 2001;42: 624–632.
36. O'Connor MK, Oswald WM. The line resolution pattern: a new intrinsic resolution test pattern for nuclear medicine [see comments]. J Nucl Med 1988;29:1856–1859.
37. De Agostini A, Moretti R. Gamma-camera quality control procedures: an on-line routine. J Nucl Med Allied Sci 1989;33:389–395.
38. Lewellen TK, Bice AN, Pollard KR, Zhu JB, Plunkett ME. Evaluation of a clinical scintillation camera with pulse tail extrapolation electronics. J Nucl Med 1989;30:1554–1558.
39. Links JM. Toward a useful measure of flood-field uniformity: can the beauty in the eye of the beholder be quantified? [editorial] [see comments]. Eur J Nucl Med 1992;19:757–758.
40. Hander TA, Lancaster JL, Kopp DT, Lasher JC, Blumhardt R, Fox PT. Rapid objective measurement of gamma camera resolution using statistical moments. Med Phys 1997;24:327–334.
41. Smith EM. Scintillation camera quality control, Part I: Establishing the quality control program. J Nucl Med Technol 1998;26:9–13.

See also COMPUTED TOMOGRAPHY, SINGLE PHOTON EMISSION; IMAGING DEVICES; MICROPOWER FOR MEDICAL APPLICATIONS; NUCLEAR MEDICINE INSTRUMENTATION.

ANGIOPLASTY. See CORONARY ANGIOPLASTY AND GUIDEWIRE DIAGNOSTICS.

ANORECTAL MANOMETRY

ASHOK K. TUTEJA
University of Utah
Salt Lake City, Utah

GEORGE E. WAHLEN
Veterans Affairs Medical Center
and the University of Utah
Salt Lake City, Utah

SATISH S.C. RAO
University of Iowa College of
Medicine
Iowa City, Iowa

INTRODUCTION

The most commonly performed test is the evoluation of anorectal function. These tests can provide useful information regarding the pathophysiology of disorders that affect defecation, continence, or anorectal pain. Anorectal manometry quantifies anal sphincter tone and assesses anorectal sensory response, recto anal reflexes, and rectal compliance. Sensory testing is usually performed along with anorectal manometry and is generally considered a part of the manometry.

The functional anatomy of the anorectum, the equipment, and the technique used for performing anorectal manometry and the parameters for measuring and interpreting the test are discribed in this article. The indications for anorectal manometry are shown in Table 1.

FUNCTIONAL ANATOMY AND PHYSIOLOGY OF THE ANORECTUM

The neuromuscular integrity of the rectum, anus, and the pelvic floor musculature help to maintain normal fecal continence and evacuation. The rectum is an S-shaped muscular tube, which serves as a reservoir and as a pump for emptying stool. The anus is a 2–4 cm long muscular cylinder, which at rest forms an angle with the axis of the rectum of $\sim 90^\circ$. During voluntary squeeze the angle becomes more acute, $\sim 70^\circ$, and during defecation, the angle becomes more obtuse, ~ 110–130° (1,2). The puborectalis muscle, one of the pelvic floor muscles, is responsible for these changes. The anal canal is surrounded by specialized muscles that form the anal sphincters [internal anal sphincter (IAS) and the external anal sphincter (EAS)]. The IAS is 0.5 cm thick and is an expansion of circular smooth muscle layer of the colon. It is an involuntary muscle innervated by fibers of the autonomic nervous system. The EAS is composed of striated muscle, is 0.6–1 cm thick, and is under voluntary control (3). The anus is normally closed by the tonic activity of the IAS. This barrier is reinforced during voluntary squeeze by the EAS. The IAS contributes $\sim$ 70–85% of the resting anal pressure. The IAS does not completely seal the anal canal and requires the endo-anal cushions to interlock and seal the canal. The anal mucosal folds, together with the expansive anal vascular cushions, provide a tight seal. These barriers are further augmented by the puborectalis muscle, which forms a flap-like valve that creates a forward pull and reinforces the anorectal angle to prevent fecal incontinence (3,4). The rectum and the IAS are innervated by the autonomic nervous system. The EAS and the anoderm are supplied by somatic nerves. The mucosa of the rectum and proximal anal canal is lack of somatic sensory innervation. The pudendal nerve, arising from second, third, and fourth sacral nerves is the principal somatic nerve and innervates the EAS, the puborectalis muscle, and the anal mucosa (5).

Table 1. Indications for Anorectal Manometry

Fecal Incontinence
Chronic idiopathic constipation
Diagnosis of Hirschsprung's disease and/or follow up
Megarectum
Pelvic floor dyssynergia
Rectocele
Solitary rectal ulcer
Rectal prolapse
Functional anorectal pain
Neurological diagnostic investigations
Biofeedback training
Pre- and Postsurgery (pouch)

EQUIPMENT FOR ANORECTAL MANOMETRY

The manometric system has two major components: the manometric probe and the pressure recording apparatus. Several types of probes and pressure recorders are available. Each system has distinct advantages and disadvantages. The most commonly used probes and recording devices are reviewed here (6).

Water-Perfused Catheter

This catheter has multiple canals through which water is perfused slowly using a pneumohydraulic pump (Arndorfer, Milwaukee, WI; MUI Scientific Ltd., Toronto, Canada). The infusion rate is $0.5\ \mathrm{mL} \cdot \mathrm{canal}^{-1} \cdot \mathrm{min}^{-1}$. In the catheter with helicoidal configuration the side holes of the canals are arranged radially and spaced 1, 2, 3, 4, 5, and 8 cm from the "0" reference point. A compliant balloon is tied to one end of the probe, which has a 200 mL capacity. The catheter is placed inside the anorectum, but the pressure transducers are located outside the body and across the flow of water. Resistance generated to the flow of water by luminal contractile activity is quantified as intraluminal pressure. The transducers located on the perfusion pump and the perfusion ports must be at the same level during calibration and when performing the study. The maintenance of the water perfused system requires relatively skilled personnel and air bubbles in the water tubing can affect the pressure recordings. The probe and the recording system are inexpensive and versatile. The closely spaced pressure sensors along the probe can record rectal and anal canal pressures and discriminate between EAS and IAS activity (7).

Solid-State Probe

This system has pressure sensors (microtransducers) that are mounted on the probe. This allows more accurate measurement by placing the pressure sensors directly at the source of pressure activity. The transducers are true strain gauge, that is, they consist of a pressure sensitive diaphragm with semiconductor strain gauges that are mounted on its inner surface. Currently, this is the most accurate catheter system for performing manometery (8). It is user friendly, offers higher fidelity, and is free of limitations imposed by the perfused system. However, it is expensive.

Amplifier–Recorder

The pressure signals that are obtained from the transducer are amplified and recorded on computerized small size amplifiers and recorders (e.g., Polygraph-Medronics/ Functional Diagnostics, Minneapolis, MN; Insight, Sandhill Scientific Ltd. Littleton, CO; 7-MPR, Gaeltec, Isle of Sky, UK, and others). They are small, compact, and not only serve as amplifiers and recorders, but also facilitate analysis of data and provide convenient storage for future retrieval of data or for generating a database. No one system is ideal, although each has its strengths and weakness.

STUDY PROTOCOL

General Instructions for Patients Undergoing Anorectal Manometry

In order to maximize uniformity, the manometry should be accomplished with the rectum emptied of feces. The preparation cannot be indispensable for incontinent patients. Constipated patients must be examined several hours after a 500 mL tap water enema or a single Fleets phospho-soda enema. Patients may continue with their routine medications, but the medications should be documented to facilitate interpretation of the data. Patients may eat or drink normally up to the time of the test. Upon arrival at the motility laboratory, the patient may be asked to change into a hospital gown.

The duration of the test is $\sim$ 1 h. The manometry catheter is inserted into the rectum while patients lie on their left side. Patients will feel movement of the catheter and distension of the balloon. After the test, patients can drive home and resume their usual work and diet. It is a safe procedure. There should be little, if any, discomfort during manometry. No anesthetic is used. Absolute contraindication to manometry is recent surgery of the rectum and anal canal, relative contraindication is a poorly compliant patient and rectum loaded with stool.

Patient Position and Digital Examination

It is recommended that the patient is placed in the left lateral position with knees and hips bent to 90°. After explaining the procedure, a digital rectal examination is performed using a lubricated gloved finger. The presence of tenderness, stool, or blood on the finger glove should be noted.

Probe Placement

Next, the lubricated manometry probe is gently inserted into the rectum and oriented such that the most distal sensor (1 cm level) is located posteriorly at 1 cm from anal verge. The markings on the shaft of the probe should aid this orientation.

Run-in Time

After probe placement, a rest (run-in) period should be allowed ($\sim$ 5 min) to give the subject time to relax and allow the sphincter tone to return to basal levels.

Resting Anal Pressure

Currently, two methods are available for assessing this function (9). *Station pull-through*: In this technique, the most distal sensor of a multiport catheter assembly is placed 5 cm above the anal margin. At every 30 s intervals, the catheter is withdrawn by 0.5 cm either manually or with a probe withdrawal device (10). As the sensors straddle the high pressure zone, there is a step up of pressure. The length and the highest pressure of the anal sphincter is then measured. Because pull-through excites anal contraction and the individual is conscious of these movements, the recorded pressure is high (10). For the same reason, a rapid pull through is not an accurate method and is not advisable for measuring anal sphincter function. *Stationary method*: Uses radially arranged multiport catheter, at least three sensors, 1 cm apart that is placed in the anal sphincter zone, that is, 0–3 cm from the anal verge (11). After allowing the tracings to stabilize, the highest sphincter pressure that is observed at any level in the anal canal is taken as the maximum resting sphincter pressure. Resting pressures can be expressed as the average obtained from each transducer or as a range to identify asymmetry of anal canal pressures (12).

Normal anal canal pressures vary according to sex, age, and techniques used (10). Normal values for anorectal manometry are shown in Table 2. There are normal variations in external sphincter pressures both radially and longitudinally (12,14). Anterior quadrant pressures are lower in the orad part of anal canal while posterior quadrant pressures are lower in the distal part of the anal canal. In the mid-anal canal, pressures are equal in all four quadrants. Manometry also enables routine calculation

Table 2. Suggested List of Tests/Maneuver Based on Indication (s)^a

	Indications for maneuver	
Test	Incontinence	Constipation
Resting pressure	Yes	Yes
Squeeze pressure/duration	Yes	No
Cough reflex	Yes	No
Attempted defecation	No	Yes
RAIR	No	Yes
Rectal sensation	Yes	Yes
Rectal compliance	Optional	Optional

^{a}From Ref. 13 with permission.

of anal canal length. Overall pressures are higher in men and younger persons and men have longer anal canals than women. But there is considerable overlap in values and disagreement among various studies about the effect of age and gender on anal canal pressures (10–12,15). Furthermore, subjects with values outside the normal range may not have clinical symptoms and patients with clinical symptoms may exhibit normal values (16).

Squeeze Sphincter Pressure

This pressure can be measured with either the station pull-through or the alternative technique. In the station pull-through technique; after placing the multiport assembly as describe above, at each level the subject is asked to squeeze and to maintain the squeeze for as long as possible (at least 30 s). Alternatively, with a multiport catheter is place, the subject is instructed to squeeze on three separate occasions, with a minutes' rest between each squeeze to allow for recovery from fatigue. The average of the three highest sphincter pressures recorded at any level in the anal canal is taken as the maximum anal squeeze pressure (13). The duration of maximum sustained squeeze should also be determined and is defined as the time interval in seconds during which the subject can maintain a squeeze pressure at or above 50% of the maximum pressure.

Weak squeeze pressures may be a sign of external sphincter damage, neurological damage of the motor pathways, or a poorly compliant patient. Squeeze pressures should be evaluated together with response to cough reflex (16).

Response to Increases in Intraabdominal Pressure

An increase in intraabdominal pressure brought about by asking the subject to blow up a party balloon or by coughing is associated with a reflex increase in the activity of the EAS (11); also called the cough reflex. This reflex response causes the anal sphincter pressure to rise above that of the rectal pressure so that continence is maintained. The response may be triggered by receptors in the pelvic floor and mediated through a spinal reflex arc. In patients with complete supra conal spinal cord lesions, this reflex response is present, but the voluntary squeeze may be absent whereas in patients with lesions of the cauda equina or of the sacral plexus, both the reflex response and the voluntary squeeze are absent.

Rectoanal Pressure Changes During Attempted Defecation

In this maneuver, the subject is asked to bear down, and simulate the act of defecation. The side holes of catheter are located within the anal canal and the rectal balloon is kept inflated. The normal response consists of an increase in rectal pressure coordinated with a relaxation of the intra-anal pressure. Alternatively, there may be a paradoxical increase in anal canal pressures, or absent relaxation or incomplete relaxation of the anal sphincter (Fig. 1) (17). It must be appreciated that laboratory conditions may induce artifactual changes, which is a learned response and is under voluntary control.



Figure 1. Structures of the anorectum: Reprinted from Ref. 17 with permission from American Gastroenterological Association.

Rectoanal Inhibitory Reflex

This consists of reflex relaxation of the IAS in response to rectal distension. The catheter is positioned with its side holes within the anal canal. Volumes of air are rapidly inflated in the rectal balloon and removed. The inflated time is 10 mL · s. The reflux is evoked with 10, 20, 40, 60, 80, 140, and 200 mL. As the volume of rectal distension is increased, the amplitude and duration of IAS relaxation increases (7). The absolute or relative amplitude of the IAS relaxation depends on the preexisting tone of the IAS and the magnitude of its contribution to the basal anal tone. This reflex may facilitate sampling of rectal contents by the sensory receptors in the upper anal canal and may also help to discriminate flatus, from liquid or solid stools. This reflex is regulated by the intrinsic myenteric plexus. In patients with Hirschsprung's disease and in those with a history of rectal resection and colo- or ileo-anal anastomosis, this reflex is absent. However, in patients with spinal cord injury and in patients with transaction of the hypogastric nerves or lesions of the sacral spinal cord, it is present (18).

Sensory Testing

Rectal Sensory Function. In this technique, the rectal sensory threshold for three common sensations (first detectable sensation, the sensation of urgency to defecate, and the sensation of pain or maximum tolerable volume) is assessed. This can be assessed either by the intermittent rectal distension or by the ramp inflation method.

Intermittent Rectal Distension. This technique is performed by inflating a balloon in the rectum using a handheld syringe. After each inflation, the balloon is deflated completely and after a rest period it is reinflated to the next volume (19).

Ramp Inflation. In this method, the rectum is progressively distended without deflation. This is performed by continuously inflating the balloon at a constant rate with a peristaltic pump or a syringe using increasing volumes of air or fluid or in a stepwise fashion, with a 1 min interval between each incremental inflation of 10–30 cm^3. It is known that the type of inflation (phasic vs. continuous) and the speed of continuous inflation affect the threshold



Figure 2. Normal squeeze profile.

volume required for healthy control subjects to perceive distension (20). Also the size and shape of the balloon will affect the threshold volume. Some of this variability can be reduced by using a high compliance balloon and a continuous-infusion pump or a barostat (21).

The maximum tolerable volume or pain threshold may be reduced in patients with a noncompliant rectum (e.g., proctitis) abdominoperineal pull-through, and rectal ischemia (9). Pain threshold also may be reduced in patients with irritable bowel syndrome (22). Higher sensory threshold is seen in autonomic neuropathy, congenital neurogenic anorectal malformations (spinal bifida, Hirschprung's disease, meningocele) and with somatic alteration in rectal reservoir (megarectum, descending perineum syndrome) (20,23). Rectal sensory threshold is altered by change in rectal wall compliance and sensory data should be interpreted along with measurement of rectal compliance (24).

Anal Sensation. At present, assessment of anal canal sensation is not of established value for the diagnosis and treatment of patients with constipation or fecal incontinence (9).

Rectal Compliance

The capacity and distensibility of the rectum are reflected by its compliance. It is a measure of the rectal reservoir function and is defined as the change in rectal volume per unit change in rectal pressure (11). The rectal compliance can be measured by the balloon distension method or more accurately by using a computerized barostat. The higher the compliance, the lower the resistance to distension and vice versa. Low rectal compliance is also seen in patients with acute ulcerative colitis, radiation proctitis, and low spinal cord lesions (20). High compliance is seen in patients with megarectum. Decreased rectal compliance can result in decreased rectal capacity, fecal urgency, and may contribute to fecal incontinence (25).

MANOMETRIC FEATURES OF FECAL INCONTINENCE AND CONSTIPATION

Fecal Incontinence

Anorectal manometry can provide useful information regarding the pathophysiology and management of fecal incontinence (26). Anal sphincter pressures may be decreased in patients with fecal incontinence; either circumferentially or in one quadrant of the anal canal (Fig. 2). Manometry can also determine if compensatory squeeze pressure can be activated. A reduced resting pressure correlate with predominant weakness of IAS and decreased squeeze pressures correlate with EAS defects (27). Two large studies have reported that maximum squeeze pressure has the greatest sensitivity and specificity in discriminating fecal incontinence from continent and healthy controls (28,29). The ability of the EAS to contract reflexly can also be assessed during abrupt increases of intra-abdominal pressure (e.g., when coughing). This reflex response causes the anal sphincter pressure to rise above that of the intrarectal pressure to preserve continence. This reflex response is absent in patients with lesions of the cauda equina or the sacral plexus (18,30). On sensory testing, both hyper- and hyposensitivity can be seen. Assessment of rectal sensation is useful in patients with fecal incontinence associated with neurogenic problems, such as diabetes mellitus (decrease in rectal sensations) or multiple sclerosis (increase in rectal sensation) (31). In some patients, rectal sensory thresholds may be altered because of changes in the compliance of the rectal wall. Patients with megarectum have decreased rectal sensation; and can present with fecal incontinence. Patients with incontinence often have lower rectal compliance (i.e., chronic rectal inschemia, proctitis).

Because of the wide range of normal values in anorectal physiologic testing, no single test can predict fecal incontinence. However, a combination of the tests with clinical evaluation is helpful in assessment of patients with fecal incontinence (32). Anorectal manometry is also useful in evaluating the responses to biofeedback training as well as assessing objective improvement following drug therapy or surgery.

Constipation

Anorectal manometry is useful in the diagnosis of dyssynergic defecation. Manometry helps to detect abnormalities during attempted defecation. Normally, when subjects bear down or attempt to defecate, there is a rise in rectal pressure, which is synchronized with a relaxation of the EAS (Fig. 3). The inability to perform this coordinated



Figure 3. Strain maneuver: A normal coordinated response of the anorectum during attempted defecation shows a rise in rectal pressure associated with a decrease in anal sphincter pressure.

movement represents the chief pathophysiologic abnormality in patients with dyssynergic defecation (17). This inability may be due to impaired rectal contraction, paradoxical anal contraction, impaired anal relaxation, or a combination of these mechanisms (Fig. 4) (Fig. 5). Anorectal manometry also helps to exclude the possibility of Hirschsprung's disease. The absence of the rectoanal inhibitory reflex accompanied by a normal intrarectal pressure increase during distension of the intrarectal balloon is evidence of denervation of the intrinsic plexus at the recto-anal level. Megarectum can cause a falsely negative reflex. In this condition, there is hypotonia of the rectal wall due to a deficiency of visceroelastic properties of the rectum and high degrees of rectal distension are necessary to produce the reflex. In addition to the motor abnormalities, sensory dysfunction may be present. The rectal sensations are reduced in patients with megarectum. The first sensation and the threshold for a desire to defecate may be higher in ~ 60% of patients with dyssynergic defecation (33). The threshold for urge to defecate may be absent on elevated in patients with chronic constipation. Maximum tolerable volume can also be elevated (34). But is not clear whether these findings are the cause or secondary to constipation. When rectal sensation is impaired, neuromuscular conditioning using biofeedback technique can be effective in improving the dysfunction.

Select Appropriate Test/Maneuver

Because anorectal manometry consists of several maneuvers, it is important to determine whether a patient needs all of the maneuvers or only a selection from the array of tests described below. The patient's symptoms and the reason for referral are helpful in choosing the appropriate list. A suggested list is given in Table 3.

Prolonged Anorectal Manometry. It is now feasible to perform anorectal manometry for prolonged periods of time outside the laboratory setting. With the use of this technique, it is possible to measure physiologic functions of the anal sphincter while the person is mobile and free (35). This technique shows promise as an investigational procedure, but its clinical applicability has not been established.

Clinical Utility and Problems with Anorectal Manometry. A systematic and careful appraisal of anorectal function can provide valuable information that can guide treatment of patients with anorectal disorders. Prospective studies have shown that manometric tests of anorectal function provide not only an objective diagnosis, but also a better understanding of the underlying pathophysiology. In



Figure 4. Weak resting and squeeze anal sphincter pressure in a patient with fecal incontinence.



Figure 5. Dyssynergic defecation. During strain maneuver there is rise in intrarectal pressure together with a paradoxical rise in anal sphincter pressure.

addition, it provides new information that could influence the management and outcome of patients with disorder of defecation (36,37).

Anorectal manometry has gained wide acceptance as a useful method to objectively assess the physiology of defecation. However, there are some problems with anorectal physiologic testing. There is a lack of uniformity with regards to the anorectal manometry equipments, methods of performance, and interpretation of the tests. A multiplicity of catheter designs exists, including water-perfused catheters, microtransducers, and microballoons. The techniques of manometric measurement are variable. The catheter can be left at one position (stationary technique), it can be manually moved from one position to another (manual pull through technique), or it can be automatically delivered from one position to another (automatic pull-through technique). If the automated technique is selected, pressure can be recorded while the catheter is at rest or in motion. Pressure can be recorded in centimeters of H_2O, millimeters of mercury (mmHg), or kilopascals (kPa). There is also a relative lack of normative data stratified for age and gender. A more uniform method of performing these tests and interpreting the results is needed to facilitate a wider use of this technecology for the assessment of patients with anorectal disorders. Recently, experts from the American and European Motility Society have described a consensus document, where minimum standards for performing ARM have been described (13). By adopting such standards it is possible to standardize the technique globally that should help diagnosis and interpretation.

Medical Terms:

Compliance:	It is defined as the capacity of the organ to stretch (expand) in response to an imposed force.
Defecation:	The discharge of feces from the rectum.
Distal:	Situated away from the center of the body, or from the point of origin, in contrast to proximal.

Table 3. Normal Manometric Data During Anorectal Manometry[a,b]

	All ($n = 45$)	Male ($N = 18$)	Female ($N = 22$)
Length of anal sphincter, cm	3.7 (3.6–3.8)	4.0 (3.8–4.2)	3.6 (3.4–3.8)
Maximum anal rest pressure, mmHg	67 (59–74)	71 (52–90)	64 (53–75)
Sustained squeeze pressure, mmHg	138 (124–152)	163 (126–200)	117 (100–134)
Squeeze duration, s	28 (25–31)	32 (26–38)	24 (20–28)
% increase in anal sphincter pressure during squeeze	126 (89–163)	158 (114–202)	103 (70–136)
Rectal pressure when squeezing, mmHg	19 (14–23)	24 (15–33)	16 (11–21)
Anal pressure during party balloon inflation, mmHg	127 (113–141)	154 (138–170)	106 (89–123)
Rectal pressure during party balloon inflation, mmHg	63 (54–72)	66 (51–81)	62 (51–73)

[a] Mean 95% cl.
[b] From Ref. 11 with permission.

Dyssynergia:	When an act is not performed smoothly or accurately because of lack of harmonious association of its various components; when there is lack of coordination or dyssynergia of the abdominal and pelvic floor muscles that are involved in defecation it is called dyssynergic defecation
ENS:	Abbreviation for enteric nervous system.
Endoanal Cushion:	Within the anus. Anal mucosal folds together with anal vascular cushion.
High pressure zone:	Intense compression area.
Intrinsic Plexus:	A network or inter-joining of nerves and blood vessels or of lymphatic vessels belonging entirely to a part.
Myenteric Plexus:	A plexus of unmyelinated fibers and postganglionic autonomic cell bodies lying in the muscular coat of the esophagus, stomach, and intestines; it communicates with the subserous and submucous plexuses, all subdivisions of the enteric plexus.
Orad:	In a direction toward the mouth.
Phasic:	In stages, in reference to rectal balloon distension for sensory testing.
Proctalgia:	Pain in the anus, or in the rectum.
Proximal:	Nearest the trunk or the point of origin, in contrast to distal.
Supraconal:	Above a condyle.
Tone:	Normal tension or resistance to stretch.

BIBLIOGRAPHY

Cited References

1. Strohbehn K. Normal pelvic floor anatomy. Obstet Gynecol Clin N Am 1998;25:683–705.
2. Whitehead WE, Schuster MM. Anorectal physiology and pathophysiology. Am J Gastroenterol 1987;82:487–497.
3. Matzel KE, Schmidt RA, Tanagho EA. Neuroanatomy of the striated muscular anal continence mechanism. Implications for the use of neurostimulation. Dis Colon Rectum 1990;33: 666–673.
4. Fernandez-Fraga X, Azpiroz F, Malagelada JR. Significance of pelvic floor muscles in anal incontinence. Gastroenterology 2002;123:1441–1450.
5. Gunterberg B, Kewenter J, Petersen I, Stener B. Anorectal function after major resections of the sacrum with bilateral or unilateral sacrifice of sacral nerves. Br J Surg 1976;63: 546–554.
6. Sun WM, Rao SS. Manometric assessment of anorectal function. Gastroenterol Clin N Am 2001;30:15–32.
7. Sun WM, Read NW. Anorectal function in normal human subjects: effect of gender. Int J Colorectal Disease 1989;4: 188–196.
8. Rao SSC. Book Chapter—Colon Transit and Anorectal Manometry. In: Rao SSC, editors. Gastrointestinal Motility: Tests and Problem-Orientated Approach. New York: Kluwer Academic/Plenum Publishers; 1999. pp 71–82.
9. Diamant NE, Kamm MA, Wald A, Whitehead WE. AGA technical review on anorectal testing techniques. Gastroenterology 1999;116:735–760.
10. McHugh SM, Diamant NE. Effect of age, gender, and parity on anal canal pressures. Contribution of impaired anal sphincter function to fecal incontinence. Dig Dis Sci 1987; 32:726–736.
11. Rao SS. Manometric tests of anorectal function in healthy adults. Am J Gastroenterol 1999;94:773–783.
12. Taylor BM, Beart RW, Jr., Phillips SF. Longitudinal and radial variations of pressure in the human anal sphincter. Gastroenterology 1984;86:693–697.
13. Rao SS. Minimum standards of anorectal manometry. Neurogastroenterol Motil 2002;14:553–559.
14. McHugh SM, Diamant NE. Anal canal pressure profile: a reappraisal as determined by rapid pullthrough technique. Gut 1987;28:1234–1241.
15. Pedersen IK, Christiansen J. A study of the physiological variation in anal manometry. Br J Surg 1989;76: 69–70.
16. Azpiroz F, Enck P, Whitehead WE. Anorectal functional testing: review of collective experience. Am J Gastroenterol 2002;97:232–240.
17. Rao SS. Dyssynergic defecation. Gastroenterol Clin N Am 2001;30:97–114.
18. MacDonagh R, et al. Anorectal function in patients with complete supraconal spinal cord lesions. Gut 1992;33:1532–1538.
19. Wald A. Colonic and anorectal motility testing in clinical practice. Am J Gastroenterol 1994;89:2109–2115.
20. Sun WM, et al. Sensory and motor responses to rectal distention vary according to rate and pattern of balloon inflation. Gastroenterology 1990;99:1008–1015.
21. Whitehead WE, Delvaux M. Standardization of barostat procedures for testing smooth muscle tone and sensory thresholds in the gastrointestinal tract. The Working Team of Glaxo-Wellcome Research, UK. Dig Dis Sci 1997;42: 223–241.
22. Mertz H, et al. Altered rectal perception is a biological marker of patients with irritable bowel syndrome. Gastroenterology 1995;109:40–52.
23. Sun WM, Read NW, Miner PB. Relation between rectal sensation and anal function in normal subjects and patients with faecal incontinence. Gut 1990;31:1056–1061.
24. Rao SS, et al. Anorectal sensitivity and responses to rectal distention in patients with ulcerative colitis. Gastroenterology 1987;93:1270–1275.
25. Salvioli B, et al. Rectal compliance, capacity, and rectoanal sensation in fecal incontinence. Am J Gastroenterol 2001;96: 2158–2168.
26. Tuteja AK, Rao SS. Review article: Recent trends in diagnosis and treatment of faecal incontinence. Aliment Pharmacol Ther 2004;19:829–840.

27. Engel AF, Kamm MA, Bartram CI, Nicholls RJ. Relationship of symptoms in faecal incontinence to specific sphincter abnormalities. Int J Colorectal Disease 1995;10:152–155.
28. Felt-Bersma RJ, Klinkenberg-Knol EC, Meuwissen SG. Anorectal function investigations in incontinent and continent patients. Differences and discriminatory value. Dis Colon Rectum 1990;33:479–485; discussion 485–486.
29. Sun WM, Donnelly TC, Read NW. Utility of a combined test of anorectal manometry, electromyography, and sensation in determining the mechanism of 'idiopathic' faecal incontinence. Gut 1992;33:807–813.
30. Sun WM, et al. Anorectal function in patients with complete spinal transection before and after sacral posterior rhizotomy. Gastroenterology 1995;108:990–998.
31. Caruana BJ, Wald A, Hinds JP, Eidelman BH. Anorectal sensory and motor function in neurogenic fecal incontinence. Comparison between multiple sclerosis and diabetes mellitus. Gastroenterology 1991;100:465–470.
32. Tjandra JJ, et al. Anorectal physiological testing in defecatory disorders: a prospective study. Aust N Z J Surg 1994;64: 322–326.
33. Rao SS, Welcher KD, Leistikow JS. Obstructive defecation: a failure of rectoanal coordination. Am J Gastroenterol 1998;93: 1042–1050.
34. Read NW, et al. Anorectal function in elderly patients with fecal impaction. Gastroenterology 1985;89:959–966.
35. Kumar D, et al. Prolonged anorectal manometry and external anal sphincter electromyography in ambulant human subjects. Dig Dis Sci 1990;35:641–648.
36. Rao SS, Patel RS. How useful are manometric tests of anorectal function in the management of defecation disorders? Am J Gastroenterol 1997;92:469–475.
37. Vaizey CJ, Kamm MA. Prospective assessment of the clinical value of anorectal investigations. Digestion 2000;61:207–214.

See also Biofeedback; esophageal manometry; gastrointestinal hemorrhage.

ANTIBODIES, MONOCLONAL. See Monoclonal antibodies.

APNEA DETECTION. See Ventilatory monitoring.

ARRHYTHMIA, TREATMENT. See Defibrillators; pacemakers.

ARRHYTHMIA ANALYSIS, AUTOMATED

Stephanie A. C. Schuckers
Clarkson University
Potsdam, New York

INTRODUCTION

Sudden cardiac death is estimated to affect ~ 400,000 people annually (1). Most of these cases are precipitated by ventricular fibrillation (VF), a chaotic abnormal electrical activation of the heart. Ventricular fibrillation disturbs systemic blood circulation and causes immediate death if therapy in the form of an electrical shock is not immediately applied. In fact, survival depends dramatically on the time it takes for therapy to arrive (2). Automated arrhythmia detection is a key component for speeding up defibrillation therapy through medical devices that detect arrhythmia and provide treatment automatically without human oversight. Examples of devices include implantable defibrillators, public access automated external defibrillators, and more.

Arrhythmias generally are an abnormal electrical activation of the heart. These abnormalities can occur in the atrial chambers, ventricular chambers, or both. Since the ventricles are the chambers responsible for providing blood to the body and lungs, disruptions in the electrical system that stimulates the mechanical contraction of the heart can be life threatening. Examples of ventricular arrhythmias include VF and ventricular tachycardia (VT), as seen in Fig. 1. Atrial arrhythmias including atrial fibrillation (AF), atrial flutter (AFl), and supraventricular tachycardia (SVT) are not immediately life threatening, but can cause uncomfortable symptoms and complications over the long term.

Automated arrhythmia analysis is the detection of arrhythmias through the use of a computer. This article focuses on arrhythmia detection performed *without human oversight*. The primary focus will be algorithms developed for the implantable cardioverter defibrillator (ICD). An implantable cardioverter defibrillator is a device that provides an electrical shock to ventricular fibrillation and tachycardia to terminate it and restart NSR. The implantable cardioverter defibrillator was developed in the late 1970s and FDA-approved in the mid-1980s (4–7). A



Figure 1. Unipolar electrograms (measurements of the electrical activity from inside the heart) for normal sinus rhythm (NSR), ventricular tachycardia (VT), and VF [10 s of the passage are shown (AAEL234) (3)].

Table 1. Truth Table Used to Determine Sensitivity and Specificity, Measurements of Automated Algorithm Performance

Device/Truth->	VT/VF	All Others
VT/VF	True positive	False positive
All others	False negative	True negative

catheter placed in the right ventricle is used for both sensing and therapy. This device has a long history of arrhythmia detection algorithms developed in research laboratories and brought to the marketplace. Other medical devices that use purely automated arrhythmia detection include the automatic external defibrillator and the implantable atrial defibrillator. Semiautomated arrhythmia detection is used in ambulatory and bedside monitoring. These topics will be touched on briefly.

It is important to consider the measurements used to assess the performance of automated arrhythmia analysis. Sensitivity is defined as the percent correct detection of disease, while specificity is the percent correct detection of not disease. Take the case of an implantable defibrillator that detects ventricular tachycardia and ventricular fibrillation. Consider the truth table in Table 1.

$$\text{Sensitivity} = \frac{\text{True Positives}}{\text{True Positives} + \text{False Negatives}}$$

$$\text{Specificity} = \frac{\text{True Negatives}}{\text{True Negatives} + \text{False Positives}}$$

A false positive is one minus the specificity, while a false negative is one minus the sensitivity.

Early Work

The earliest examples of computer-based arrhythmia analysis are semiautomated approaches for bedside and ambulatory monitoring. Ambulatory monitoring typically uses a 24 or 48 h, three-lead, portable electrocardiogram (ECG) recorder that the patient wears to diagnosis arrhythmias. Arrhythmia analysis is done in an off-line fashion with technician oversight, such that it is not purely automated (8). Other ambulatory monitors include loop recorders or implanted monitors like Medtronic Reveal Insertable Loop Recorder that permanently records with patient interaction. Clinical bedside monitors typically are also not fully automated, but are used as initial alarms, which is then over read by clinical staff.

In ambulatory monitoring, in addition to detection of arrhythmias, it is typical to also detect premature ventricular contractions (PVCs). These PVCs are beats that form ectopically in the ventricle and result in an early, wide ECG beat and occur alone or in small groups of two or more. They are considered a potential sign of susceptibility to arrhythmias.

Use of correlation is a common tool in surface arrhythmia analysis (9–18). Correlation waveform analysis (CWA) uses the correlation coefficient between a previously stored template of sinus rhythm and the unknown cycle under analysis. The correlation coefficient, used by CWA, is computed as

$$\rho = \frac{\sum_{i=1}^{i=N}(t_i - \bar{t})(s_i - \bar{s})}{\sqrt{\sum_{i=1}^{i=N}(t_i - \bar{t})^2 \sum_{i=1}^{i=N}(s_i - \bar{s})^2}}$$

where $\rho =$ the correlation coefficient, $N =$ the number of template points, $t_i =$ the template points, $s_i =$ the signal points under analysis, $\bar{t} =$ the average of the template points, and $\bar{s} =$ the average of the signal points. The correlation coefficient falls within a range $-1 < \rho < +1$, where $+1$ indicates a perfectly matched signal and template.

To compute CWA, a beat detector (described in more detail in the section implantable cardioverter defibrillators) finds the location of each beat. From the location of each beat, the template is aligned with the beat under analysis, typically using the peak, and the correlation coefficient is calculated. Often, the template is shifted and the procedure is repeated to determine the best alignment indicated by the highest correlation coefficient. An example of CWA is shown in Fig. 2. Sustained high correlation indicates normal sinus rhythm and low indicates an arrhythmia.

Examples of other features used in PVC and arrhythmia detection include timing, width, height, area, offset, first spectral moment (5–25 Hz), T-wave slope, and others (9,13,14,17,20–24). Another early approach was to develop a database of electrocardiogram templates grouping similar shaped complexes based on shape, width, and prematurity (17,25–28).

Some of the earliest algorithms for *purely automated* arrhythmia detection involved algorithms for newly developing implantable devices for SVT termination and the developing implantable defibrillator (29,30). With problems of inducing ventricular arrhythmias in the devices for SVT termination, focus shifted to the implantable



Figure 2. Example of use of correlation waveform analysis. The first electrogram is the stored normal sinus rhythm template, the second is a NSR beat with correlation equal to 0.999 and the third is a ventricular tachycardia with correlation equal to 0.535. (Used with permission from Ref. 19.)

defibrillator (31,32). In the early 1980s, Furman (29) proposed that two sensors (atrial and ventricular) be required for automatic diagnosis of tachycardia (with even a possible refinement of a third sensor for hestidine (His) bundle detection). He also suggested examining the QRS configuration for a match with sinus rhythm as a schema for diagnosing supraventricular tachycardia. Other early work included the development of algorithms for surface electrocardiography that used an esophogeal electrode for analysis of atrial information (33,34).

The original detection mechanism in the first implantable defibrillator, the AICD, was the probability density function (PDF). This algorithm utilized the derivative of the signal to define the duration of time that the signal departed from baseline (31,32) and was empirically based upon the observation that the ventricular fibrillation signal spends the majority of its time away from the electrocardiographic isoelectric baseline when compared to sinus rhythm or supraventricular rhythms (Fig. 1). The PDF was supplanted at a very early stage by intrinsic heart rate measures.

The need to identify and cardiovert ventricular tachycardia in addition to detecting and defibrillating ventricular fibrillation, and the recognition that sufficiently slow VT might have rates similar to those that may occur during sinus rhythm or supraventricular tachycardias resulted in several changes being incorporated into the second generation of devices. An alternative time-domain method called temporal electrogram analysis was incorporated into some second-generation devices (35). This algorithm employed positive and negative thresholds, or rails, placed upon electrograms sensed during sinus rhythm. A change in electrogram morphology was identified when the order of the excursion of future electrograms crossed the predetermined thresholds established during sinus rhythm. The combination of this morphologic method with ventricular rate was intended to differentiate ventricular tachycardia from other supraventricular tachycardias including sinus tachycardia.

Experience with probability density function and temporal electrogram analysis in first- and second-generation devices was disappointing. Probability density function was found to be unable to differentiate sinus tachycardia, supraventricular tachycardia, ventricular tachycardia, and ventricular fibrillation whose respective rates exceeded programmed device thresholds for tachycardia identification (36). A similar experience was encountered with temporal electrogram analysis. As a result, these criteria were utilized less and less frequently as increasing numbers of second-generation devices were implanted. By 1992, $< 15\%$ of all ICDs implanted worldwide utilized either algorithm for tachycardia discrimination (37).

IMPLANTABLE CARDIOVERTER DEFIBRILLATORS

Over time, the implantable cardioverter defibrillator added capabilities to pace terminate and cardiovert ventricular tachycardia and provide pacemaker functions, single and dual chamber. Early reviews of automated algorithms particularly for implantable defibrillators are given in Refs. 38–40. More recent reviews of automated arrhythmia detection algorithms include a thorough review by Jenkins and the author in 1996 (41) and reviews incorporating recent developments in dual chamber algorithms in 1998 and 2004 (42,43).

Rate-Based Analysis

The main method for detection of arrhythmias after initial use of PDA and TEA was the use of intrinsic heart rate for detection of ventricular tachycardia and ventricular fibrillation. To this day, all algorithms in ICDs have rate as a fundamental component for detection of arrhythmias. Since implantable defibrillators have a stable catheter screwed in the apex of right ventricle, the rate of the ventricles can be determined with little of the noise that is present at the surface of the body, like motion artifact and electromyogram noise. Ventricular tachycardia and ventricular fibrillation have rates of $\sim$ 120–240 beats per minute and $>$ 240 beats per minute, respectively.

Many approaches abound for arrhythmia detection using rate, but the general procedure is the same (Fig. 3). First, each ECG beat must be detected. Second, the time between beats (or the cycle length) is determined. Most algorithms rely on cycle length (CL) values over beats per minute. The value of the CL determines the zone it falls into: Normal, VT, or VF. In some cases, zones may be further divided depending on the device and therapy options. The thresholds that define the zones are programmable. Each zone has a programmable counter that will determine when therapy will need to be considered. In addition, each zone has a reset mechanism that may be different depending on the zone. For example, typical VT zones require *X* consecutive beats within the zone or the counter is reset. While VF often has an *X* of *Y* criteria, for example, 12 of 16 beats. This flexibility is due to the fact that VF is of varying amplitude, morphology, and rate, such that each beat may not be detected reliably and/or may not be in the VF zone. The CL thresholds, counters, and associated therapies are all programmable.

The fundamental basis of automated rate algorithms is the detection of each beat. Many approaches have been suggested and utilized including fixed thresholds, exponentially varying thresholds, amplitude gain control, and


Sense cycle; Calculate cycle length (CL)
Divide into zones based CL or CL derivative
SR
1
2
3
Count # of cycles in each zone
Determine therapy based on zone
Deliver therapy

Figure 3. Typical rate-based arrhythmia detection scheme for implantable cardioverter defibrillators. First, each beat is detected and the cycle length between beats determined. A counter is incremented in the zone that the CL falls and therapy is delivered when the counter reaches a programmed threshold.



Figure 4. Example of beat detector that utilizes an exponentially decaying threshold. After a beat is detected, a blanking period prevents detection of the same beat twice. Then, the threshold (dotted line) for determination of the next beat is calculated as a percentage of the peak amplitude of the previous beat. This threshold exponentially decays, such that beats that are smaller than the currently detected beat will be not be missed (47).

others (9,44–46). In implantable devices, most are hardware-based and beyond the scope of this article. For example, one software method relies on an exponentially varying threshold (Fig. 4) (47). After a beat is detected, there is first a blanking period to prevent a beat from being detected more than once. After the blanking period, the threshold for detection of the next beat is set as a percentage of the previous beat. This threshold then decays exponentially such that subsequent beats that have a smaller peak amplitude will be detected. Most beat detectors also have a floor for the threshold, that is, the smallest amplitude by which a beat can be detected to prevent detection of noise as a beat.

An example of one rate-based algorithm is given in Fig. 5 (40). This algorithm uses three CL thresholds, fibrillation detection interval (FDI), fast tachycardia interval (FTI), and tachycardia detection interval (TDI), and two counters, VF counter (VFCNT) and VT counter (VTCNT). These are combined to result in three zones, VF, fast VT, and slow VT, which can have different therapeutic settings, utilizing defibrillation shock, cardioversion, and antitachycardia pacing. Therapy for ventricular fibrillation is given when 18 of 24 beats are shorter than the FDI. Therapy for slow ventricular tachycardia is delivered when 16 beats counted by the VTCNT are between the FDI and TDI thresholds. The VTCNT will be reset by one long CL greater than TDI. The fast VT zone is a combination of these techniques.

A thorough description of the rate-based algorithms is given in Ref. 40. While many additional features have been added to refine the decision, the main structure of automated arrhythmia detection algorithms still rely on this fundamental approach (42).

As can be see from Fig. 1, heart rate in VT and VF increase substantially over normal sinus rhythm. This is a reliable means of detecting VT and VF for implantable devices, resulting in high sensitivity. Unfortunately, while providing high sensitivity, heart rate also increases for normal reasons, exercise, stress, resulting in sinus tachycardia or for nonventricular-based arrhythmias like atrial fibrillation, supraventricular tachycardia, atrial flutter, and so on, which do not require therapy from the ICD. Thus, rate-based algorithms have low specificity. False therapies have been estimated in as much as 10–40% in the early devices (48–50). Morphology and other extended algorithmic approaches have long been suggested as a means to increase specificity.

Early rate-based algorithms to prevent false therapies, due to sinus tachycardia, atrial fibrillation, and so on, include onset and rate stability. Rate-based methods were chosen initially over morphology due to the simplicity of calculations in battery operated devices.

Onset is the difference between the rate changes during the onset of sinus tachycardia compared to those of VT, since the onset of VT is typically sudden compared to sinus tachycardia. False therapies due to sinus tachycardia are determined by onset. Figure 6a shows the sudden onset of ventricular tachycardia.

Rate stability is used to prevent false therapies due to AF. In AF, it is common for the ventricle to respond to the atrium at a fast rate. This response is typically irregular since atrial fibrillation, by definition has an irregular rate,


Wait for a new cycle length, CL
Decrement VFCNT if CL-24 < FDI; CL < FDI?
Increment VFCNT; VFCNT = 18?
Detection of VF
All Last 8 CL ≥ FTI?
Detection of fast VT via VF
VTCNT + VFCNT = 21 and VFCNT ≥ 6?
All Last 8 CL ≥ FDI?
FDI ≤ CL < TDI?
Increment VTCNT; VTCNT = 16;
Detection of slow VT
If CL ≥ TDI, then VTCNT = 0
To therapies
Medtronic, Inc. PCD Jewel™
N
Y

Figure 5. Example of rate-based algorithm for the Medtronic PCD Jewel. The VFCNT is the VF counter, FDI is the fibrillation detection interval, FTI is the fast tachycardia interval, VTCNT is the VT counter, and TDI is the tachycardia detection interval. This algorithm has three zones that has associated programmable therapies including defibrillation shock, cardioversion, and antitachycardia pacing (40).

and since not every beat is conducted from the atrium to the ventricle. Rate stability considers the stability of the ventricular rate, since VT typically has a stable rate compared to the ventricular response to atrial fibrillation. Figure 6b shows an irregular ventricular response to atrial flutter.

Rate and rate-derived measures that measure onset and stability (based on cycle-by-cycle interval measurements) include average or median cycle length, rapid deviation in cycle length (onset), minimal deviation of cycle length (stability), and relative timing measures in one or both chambers or from multiple electrodes within one or more chambers. Among the methods most widely used for detection of VT in commercially available single chamber antitachycardia devices have been combinations of rate, rate stability, and sudden onset (51–56). Pless and Sweeney published an algorithm for (1) sudden onset, (2) rate stability, and (3) sustained high rate (57). This schema among others (58,59) was a forerunner of many of the methods introduced into tachycardia detection by ICDs (60).

Morphological Pattern Recognition

Instead of relying purely on rate, it has been suggested that morphology may provide the means for automated arrhythmia detection to separate VT and VF from rhythms with fast rates that do not need therapy. Morphology in this context refers to characteristics of the electrogram waveform itself, which are easily identifiable and measurable. Such features might include peak-to-peak amplitude, slew rate (a measure of waveform), sequence of slope patterns, sequence of amplitude threshold crossings, statistical pattern recognition of total waveform shape by correlation coefficient measures, and others (61,62). Figure 1 shows an example of distinctly different waveforms recorded from the right ventricular apex during SR, VT, and VF (3). Furthermore, morphology in the ventricle appears normal



Figure 6. Atrial (top) and ventricular (bottom) electrograms. (a) Sudden onset of VT with normal atrial electrogram, (b) irregular response of ventricular to atrial flutter, (c) simultaneous atrial flutter and ventricular tachycardia, and (d) sudden onset of supraventricular tachycardia with ventricular response.

even during supraventricular arrhythmias since the rhythm typically is conducted normally in the ventricles.

The ICDs often have two channels of electrograms. The first channel is typically bipolar, which is associated with two electrodes on the lead, or an electrode–coil combination, both located within the ventricle. This channel provides a near-field electrical view of the ventricle and is usually used for beat detection because the electrogram typically has a narrow QRS (the main depolarization of the electrogram). The second electrode configuration is far-field which, for example, may use an electrode in the ventricle versus the implantable device casing. The far-field electrode combination is used primarily for giving the electrical shock. However, this far-field view typically has a more global perspective of the electrogram depolarization and is helpful in differentiating the morphology changes between normal beats and ventricular abnormalities.

Template-Based Algorithms

Correlation Waveform Analysis. Lin et al. (19,62,63) investigated three techniques for morphologic analysis of VT: correlation waveform analysis, amplitude distribution analysis, and spectral analysis. Correlation waveform analysis (CWA) is a classic method of pattern recognition applied to the surface electrocardiogram, described earlier, but was first applied to intracardiac signals in this study. Correlation waveform analysis was shown to be superior and has the advantage of being independent of amplitude and baseline fluctuations. However, it requires heavy computational demands. Less computationally demanding algorithms based on the same principle have been developed and are described in the next section.

Less Computationally Demanding Template-Based Algorithms. Another template matching algorithm based on raw signal analysis measured the area of difference between electrograms, that is, adding absolute values of the algebraic differences between each point on the electrogram and corresponding point on the SR template (64,65). The area of difference was expressed as a percentage of the total area of the template. The measurement of an area of difference is simple computationally, but has the disadvantage of producing erroneous results in the face of baseline and amplitude fluctuations, and this method fails to produce a bounded measure. An improvement on this technique by signal normalization and scaling to create a metric bounded by ±1 was utilized by Throne et al. (66).

Steinhaus et al. (67) modified correlation analysis of electrograms to address computational demand by applying data compression to filtered data (1–11 Hz) by retaining only samples with maximum excursion from the last saved sample. The average squared correlation coefficient (ρ^2) was used for separation of SR and VT. Comparison with noncompressed correlations demonstrated that data compression had negligible effects on the results.

Throne et al. (66) designed four fast algorithms and compared discrimination results to CWA performance. These morphological methods were the bin area method (BAM); derivative area method (DAM); accumulated difference of slopes (ADIOS); and normalized area of difference (NAD). All four techniques are independent of amplitude fluctuations and three of the four are independent of baseline changes.

The bin area method is a template matching algorithm that compares corresponding area segments or bins of the template with the signal to be analyzed. Each bin (average of three consecutive points) is adjusted for baseline fluctuations by subtracting the average of the bins over one cycle and normalized to eliminate amplitude variations. This BAM equation is given in the following equation:

$$\rho = 1 - \sum_{i=1}^{i=M} \left| \frac{T_i - \overline{T}}{\sum_{k=1}^{k=M} \left| T_k - \overline{T} \right|} - \frac{S_i - \overline{S}}{\sum_{k=1}^{k=M} \left| S_k - \overline{S} \right|} \right|$$

where the bins are $S_1 = s_1 + s_2 + s_3$, $S_2 = s_4 + s_5 + s_6, \cdots$, $S_M = s_{N-2} + s_{N-1} + s_N$ and the average of M bins is $\overline{S} = (1/M)\Sigma_{k=1}^{k=M} S_k$. The bins and average of the bins is calculated similarly for the template. The BAM metric falls between -1 and $+1$, allowing a comparison to CWA.

Normalized area of difference is identical to BAM except that the average bin value is not removed. By not removing the average value the algorithm avoids one division that would otherwise increase computational demand each time the BAM algorithm is applied. The NAD is independent of amplitude changes.

The DAM uses the first derivative of the template and the signal under analysis. The method creates segments from zero crossings of the derivative of the template. It imposes the same segmentation for analysis of the derivative of the signal to be compared. The segments are normalized, but are not adjusted for baseline variations since derivatives are by their nature baseline independent. The DAM metric is calculated as follows:

$$\rho = 1 - \sum_{i=1}^{i=M} \left| \frac{\dot{T}_i}{\sum_{k=1}^{k=M} \left| \dot{T}_k \right|} - \frac{\dot{S}_i}{\sum_{k=1}^{k=M} \left| \dot{S}_k \right|} \right|$$

where $\dot{T}_k$ represents the kth bin of the first derivative of the template. The DAM metric falls between -1 and $+1$.

The ADIOS is similar to DAM in that it also employs the first derivative of the waveforms. A template is constructed of the sign of the derivative of the ventricular depolarization template. This template of signs is then compared to the signs of the derivative for subsequent depolarizations. The total number of sign differences between the template and the current ventricular depolarization is then computed as

$$\rho = \sum_{i=1}^{i=N} \operatorname{sign}(\dot{t}_i) \oplus \operatorname{sign}(\dot{s}_i)$$

where $\oplus$ is the exclusive or operator. The number of sign changes is bounded by 0 and the maximum number of points in the template (N), that is, $\rho \in \{0, \ldots, N\}$.

Evaluation of these four algorithms was performed on 19 patients with 31 distinct ventricular tachycardia morphologies. Three of the algorithms (BAM, DAM, and

NAD) performed as well or better than correlation waveform analysis, but with one-half to one-tenth the computational demands.

A morphological scheme for analysis of ventricular electrograms (SIG) was devised for minimal computation (68) and compared to NAD. The SIG is a template-based method that creates a boundary window enclosing all template points that form a signature of the waveform to be compared. Equivalent results of VT separation were seen in the two techniques at two thresholds, but at an increased safety margin of separation SIG outperformed NAD and yielded a fourfold reduction in computation.

Another simplified correlation-type algorithm has been designed using electrogram vector timing and correlation, developed for the Guidant ICD (69). In this algorithm, the rate (near-field) channel is used for determining the location of each beat. The peak of the near-field electrogram or fiducial point is used for alignment of the template with the beat under analysis. From this fiducial point, eight specific points are chosen on the shock (far-field) electrogram. The amplitude of the shock channel at the rate-channel fiducial point is one point. In addition, amplitudes at the turning point, intermediate, and baseline values on the shock channel are selected as shown in Fig. 7. This provides an eight-point template that is compared to subsequent beats using the square of the correlation coefficient, as follows:

$$\mathrm{FCC} = \frac{(8\sum t_i s_i - (\sum t_i)(\sum s_i))^2}{(8\sum t_i^2 - (\sum t_i)^2)(8\sum s_i^2 - (\sum s_i)^2)}$$

where each summation is $i = 1$–8.

When an unknown beat is analyzed, the exact same timing relative to the fiducial point as the template is used for selecting the amplitudes of the unknown beat. For beats that have a different morphology, those points will not be associated with the same amplitudes as the normal template beat and, thus, the correlation coefficient will be low. To incorporate this into an overall scheme to detect an arrhythmia, morphology was calculated for a sliding window of 10 beats. If 8 or more beats were detected as abnormal, a VT was detected.

Another algorithm that reduces computational complexity of the standard correlation algorithm uses the wavelet transform of the sinus beat for the template (70). Wavelets can reduce the number of coefficients needed to characterize a beat while still retaining the important morphologic information. The sinus electrogram is transformed using the Haar (square) wavelet, considering a family of 48 wavelets over 187.5 ms window aligned by the fiducial point of the QRS. The wavelet transform is simplified by removing the standard factor of square root of 2. In addition, wavelet coefficients that do not carry much information, defined by a threshold, are set to zero. The remaining coefficients are normalized. This gives a variable template size, depending on the electrogram, but typically between 8 and 20 coefficients. To analyze an unknown electrogram, the electrogram is aligned using the peak (negative or positive) point. The wavelet transform is computed for the unknown electrogram and each coefficient is compared using the absolute difference in wavelet coefficients (c_i) between the template and unknown beat. A match is determined by the following equation:

$$\text{Match\%} = \left| 1 - \frac{\sum \left| c_i^{\text{template}} - c_i^{\text{unknown}} \right|}{\sum \left| c_{\mathrm{i}}^{\text{template}} \right|} \right| * 100$$

The nominal threshold used in this study is 70%. This morphology algorithm is incorporated into an overall rate scheme by remaining inactive until a ventricular tachycardia has been detected by the rate algorithm. Then, the morphology is calculated for the preceding eight beats. A VT is detected if six or more beats are detected as abnormal.

A novel way of testing this algorithm was used. Instead of, as in most tests, using data prerecorded in laboratory conditions, this algorithm was downloaded to the Medtronic clinical ICDs and tested off-line, while the device functioned with its regular algorithm.



Figure 7. Example for vector timing and correlation algorithm. Alignment of the template is based on the peak of the rate electrogram channel. From the peak, eight specific points on the shock channel are automatically selected for the template (left). These exact points in time relative to the fiducial point selected from the template are applied to the "unknown" beat (right). (Used with permission from Ref. 69.)

Another algorithm that utilizes morphology is termed morphology discrimination (MD) in St. Jude implantable cardioverter defibrillators (71,72). This algorithm uses an area-based approach. First, the template is defined based on the three consecutive peaks with the largest area. The area under each peak is normalized by the maximum peak area. When analyzing an unknown beat, the beat is aligned with the template using the dominant peak of the unknown beat. If this peak does not have same polarity, the second largest peak is used. If this also does not have the same polarity, a nonmatch is declared. Once the unknown beat and template are aligned, the morphology score is determined by the following:

$$\text{Score} = (1 - \big||N\text{Area}A - N\text{Area}A'| + |N\text{Area}B - N\text{Area}B'| + |N\text{Area}C - N\text{Area Peak}C'|\big|) * 100$$

where NArea stands for the normalized area of the three corresponding peaks of the template (A, B, C) and test complexes (A', B', C'). For arrhythmia diagnosis, once the rate criteria is met, the algorithm determines the number of matching complexes in the morphology window. If the number of matching complexes equals or exceeds a programmed number of matching complexes, VT is not confirmed and therapy is not delivered. This is repeated for as long as the rate criteria has been met or VT is confirmed.

Template matching by CWA was further examined for distinction of multiple VTs of unique morphologies in the same patient (73,74). It was hypothesized that, in addition to a SR template, a second template acquired from the clinical VT could provide confirmation of a later recurrence of the same VT. The recognition of two or more different VTs within the same patient could play an important role in future devices in the selection of therapy to be delivered to hemodynamically stable versus unstable VTs.

Considerations for Template Analysis. While template-based algorithms appear the most promising, several issues need to be addressed. The first is that it is necessary that the normal sinus rhythm beat or template remain stable, that is, does not change over time or due to position or activity. Several studies using temporary electrodes saw changes in the morphology of normal rhythm due to increase in rate or positional changes (75–78) but further studies with fixed electrodes showed no changes in morphology due to heart rate or position, with some changes in amplitude (76,79). A second consideration is that paroxysmal (sudden) bundle branch block (BBB) may be misdiagnosed as ventricular tachycardia (80). While this may result in a false therapy, it does not result in withholding of therapy during life-threatening arrhythmias (the more critical mistake).

Feature-Based Algorithms

Depolarization Width for Detection of Ventricular Tachycardia. Depolarization width (i.e., duration) in ventricular electrograms has been used as a discriminant of supraventricular rhythm (SR) from VT (81,82). Electrogram width is available in the Medtronic single chamber ICDs. This criterion uses a slew threshold to find the beginning and end of the QRS. Analysis of electrogram width compared to a patient-specific width threshold is performed using the previous eight beats after a VT detected by the rate component of the algorithm. If a minimum of six complexes are greater than the width, then a VT is detected. Otherwise, the counter is reset. This algorithm is not appropriate in patients with BBB that have a wider width for normal beats. Exercise induced variation should be considered in programming (83). Electrogram width has been shown to be sensitive to body position and changes over longer periods of time (6 months in this study) (84).

Amplitude and Frequency Analysis. Amplitude and frequency are distinguishing characteristics of arrhythmia. Amplitude during ventricular tachycardia is typically higher and during ventricular fibrillation is lower than normal sinus rhythm (85,86). These differences have not been considered pronounced and consistent enough, such that a classifier could be based on them.

Frequency-domain analysis is often proposed for classification of rhythms (87) but little success has been solidly demonstrated for the recognition of VT (63). Distinctly different morphological waveforms (SR vs VT), which are easily classified in the time domain, can exhibit similar or identical frequency components if one focuses on the depolarization component alone. Examination of longer segments of 1000–15,000 ms yields the same phenomenon because the power present in small visually distinctive high frequency notches is insignificant compared to the remainder of the signal, and changes in polarity of the waveform, easily recognized in the time domain, are simply not revealed by frequency analysis (63). Frequency-domain recognition of AF (88) and VF (89,90) is perhaps more promising. However, frequency has not been applied in commercial applications given the success of rate and time-domain morphology approaches.

Other Morphologic Approaches. Other approaches that have been suggested in the literature include use of neural networks (91–97). Neural network approaches utilize either features, the time-series, or frequency components as inputs to the neural network. The network is trained on one dataset and tested on a second. Limitations with the approaches developed thus far are related to the fact that there is only limited data for development of the neural network. One problem is that in some studies the training set and test set both include samples from the same patient. Thus, these networks cannot be considered a general classifier for all patients, since it did not have a valid test set for assessing results on unseen patients. Ideally, three sets should be utilized: training, validation, and testing. The purpose of the validation set is to test the generalization of the network, such that it is not overtrained. Plus, it is typical practice to retrain neural networks until good results are achieved on the validation set. A separate testing set verifies that success on the validation set was not just by chance. Until large datasets are available for development of the algorithms, neural networks will not be considered for clinical use. Furthermore, neural networks generally have not achieved much acceptance by the clinical community who prefer methods that are tied to underlying physiologic understanding.

Dual-Chamber Arrhythmia Detection

Since dual-chamber pacemakers have been combined into ICDs, the possibility of the use of information from the atrial electrogram for arrhythmia diagnosis has opened up. The most prevalent cause of delivery of false therapy is AF, which accounts for $> 60\%$ of all false shocks according to the literature. The simple addition of an atrial sensing lead can dramatically change the false detection statistics.

The first two-channel algorithm for intracardiac analysis incorporated timing of atrial activation as well as ventricular into the diagnostic logic of arrhythmia classification (98,99). This scheme was based on earlier work in which an esophageal pill electrode (33) provided P-wave identification as an adjunct to surface leads in coronary care and Holter monitoring (34). The early argument for adding atrial sensing for improvement of ICD tachycardia detection was advanced conceptually by Furman in 1982 (29), was demonstrated algorithmically by Arzbaecher et al. in 1984 (58), and was further confirmed by Schuger (100). This simple two-channel analysis offers a first-pass method for confirming a VT diagnosis when the ventricular rate exceeds the atrial (Fig. 8). Recognition of a run of short intervals was followed by a comparison of atrial versus ventricular rate. With both chambers (atrial and ventricular) under analysis, most supraventricular arrhythmias could be detected by an $N : 1$ $(A : V)$ relationship, and most ventricular arrhythmias could be detected by a $1 : N$ $(A : V)$ relationship. Ambiguity occurred in tachycardias characterized by a $1 : 1$ relationship, where SVT with $1 : 1$ ventricular conduction could be confounded with ventricular tachycardia with retrograde $1 : 1$ atrial conduction. In addition, an $N : 1$ $(A : V)$ relationship should not be an automatic detection of atrial arrhythmia, since a concurrent ventricular arrhythmia could be masked by a faster atrial arrhythmia, as seen in Fig. 6c. Thus the limitations of two-channel timing analysis, although powerful, needs to be addressed by more advanced logical relationships.

A system designed for two-channel analysis using rate in both chambers plus three supplemental time features (onset derived by median filtering, regularity, and multiplicity) was designed for real-time diagnosis (101) of spontaneous rhythms. This system was an integration of previously tested stand-alone timing schemes (102,103). The combined system is able to recognize competing atrial and ventricular tachycardias and produces joint diagnoses of the concurrent rhythms. Simultaneous VT and atrial flutter is classified via atrial rate, ventricular rate, and a lack of multiplicity. Fast ventricular response in AF is detected via the regularity criterion. Onset (employed in 1:1 tachycardias) utilizes a median filter technique (102).

Commercially, each manufacturer now has available algorithms that utilize information from both chambers for making the diagnosis, particularly for improving specificity. These algorithms are implemented in commercial devices and continually updated and improved. Examples of the algorithms are in the following paragraphs. Reviews are given in Refs. 42,43 along with a thorough comparison of clinical results of the various commercial dual-chamber algorithms (43). Other comparisons include Refs. 104,105.

The first actual realization of a two-channel ICD appeared with the introduction into clinical trials (1995) of the ELA *Defender,* a dual chamber sensing and pacing ICD that uses both atrial and ventricular signals for its tachycardia diagnoses (106) (Fig. 9). The first step after a fast rate is detected is to consider stability of the ventricular rate. If the rhythm is not stable, atrial fibrillation is detected and no therapy delivered. The next consideration is the association between the A and V. For $A : V$ association of $1 : N$ or no association, a VT is detected. For $N : 1$ association, atrial arrhythmia is detected and no therapy delivered. For 1:1 association, the last step is consideration of chamber of onset, ventricular acceleration will result in VT therapy, while no acceleration or atrial acceleration will result in no therapy. An example of a sudden onset in the atrium due to SVT is seen in Fig. 6d. The most recent algorithm, PARAD+ incorporates additional features after the association criteria (second step) (107). If there is no PR association, a second criteria is considered where a single



Figure 8. Basic dual chamber arrhythmia detection algorithm. For a sequence of intervals, the number of atrial (A) intervals is compared to the number of ventricular (V) intervals. If there are more V than A, a diagnosis of ventricular fibrillation (VF), ventricular flutter (VFl), or ventricular tachycardia (VT) is made based on the rate. If there are more V than A beats, a diagnosis of atrial fibrillation (AF), atrial flutter (AFl), or atrial tachycardia is made (AT) (58).



Figure 9. Flowchart of dual-chamber arrhythmia detection algorithm using simple rate-based features. For unstable RR interval (time between beats), atrial fibrillation is detected. For stable RR and no association between the atrium (A)and ventricle (V), ventricular tachycardia (VT) is detected. For $N:1$ ($A:V$) association, atrial flutter (AFl) is detected. For $1:1$ ($A:V$) association with no acceleration (Accel), sinus tachycardia (ST) is detected. Last, with a ventricular acceleration, VT is detected and with atrial acceleration (Aaccel) supraventricular tachycardia (SVT) is detected (106).

long ventricular cycle will result in the diagnosis of atrial fibrillation (for the next 24 consecutive cycles) while no long ventricular cycles will result in VT detection.

The Guidant Ventak AV III DR algorithm uses the following scheme, shown in Fig. 10 (104). First, it checks if the ventricular rate is greater than the atrial rate (by 10 bpm). If yes, then VT is detected. If no, then more analysis is performed. If the atrial rate is greater than the atrial fibrillation threshold and the RR intervals are not stable, then supraventricular rhythm is classified. If the RR intervals are stable, VT is detected. If the atrial rate is not greater than the atrial fibrillation threshold, then ventricular tachycardia is detected if the RR intervals are stable and there is a sudden onset of ventricular rate. An updated algorithm from Guidant is described in the next section.


Fast ventricular rate
Ventricular rate > Atrial rate by >= 10 bpm
yes
no
Atrial rate > Atrial fibrillation threshold
yes
no
Stable R-R intervals and sudden onset of ventricular rate
yes
no
Stable R-R intervals
no
yes
Detection of ventricular tachycardia

Figure 10. Algorithm for Guidant Ventak AV III DR, using comparison of the rate of A and V, stability and onset. (Used with permission from Ref. 104.)

Perhaps the most complex of the dual chamber algorithms rests with the PR Logic algorithm, by Medtronic (42). This algorithm uses a series of measurements from the timing of the atrial ventricular depolarizations to create a code (1 of 19 possible). These codes are then used for ultimate diagnosis. The main component of the algorithm is the timing between the atrial and ventricular beat to determine if the conduction was antegrade or retrograde. For a given ventricular RR interval, if the atrial beat falls 80 ms before or 50 ms after the ventricular beat, the rhythm is considered junctional. Outside of this, if the atrial beat (P-wave) falls within the first one-half of the RR interval, it is considered retrograde conduction. If the atrial beat falls in the second half of the RR interval it is considered antegrade. This is performed for the previous two beats and incorporated in the code. There are only a few programmable components in the algorithm. The first is the type of SVT for which rejection rules apply (AF/AFL, ST, SVT). The second is the SVT limit. The rest are not programmable.

Dual-Chamber with Ventricular Morphological Analysis

The Photon DR from St. Jude incorporates morphology in its dual chamber defibrillator algorithm. The MD in the ventricular chamber described earlier is incorporated in the full algorithm as follows (108). For $V > A$, ventricular tachycardia is detected. For $V < A$, a combination of morphology discrimination and interval stability is used to inhibit therapy for atrial fibrillation/flutter and SVT. For the branch $V = A$, morphology discrimination and sudden onset is used to inhibit therapy for ST and SVT. This algorithm has an automatic template feature update (ATU) for real-time calibration of the sinus template.

A new dual chamber algorithm from Guidant uses the vector timing and correlation (VTC) algorithm, described earlier (69). If the V rate exceeds A rate by $>$ 10 bpm, a VT is detected. Otherwise, VTC algorithm is implemented. If the atrial rate does not exceed the AF threshold, then VTC will be used for diagnosis. Otherwise, stability will be used for diagnosis. Therapy would be inhibited for an unstable ventricular rhythm.

Two-Channel Morphological Analysis. An early algorithm that uses morphological analysis of both the intraatrial signal and the intraventricular signal (109,110) is based on strategy developed previously for surface and esophageal signals (111). A five-feature vector was derived for each cycle containing an atrial and a ventricular waveform metric (ρ_a, ρ_v), where ρ is the correlation coefficient for each depolarization, and AA, AV, and VV interval classifiers (short, normal, and long). Single-cycle codes were mapped to 122 diagnostic statements. The eight most current cycles were employed for a contextual interpretation of the underlying rhythm. This addition of morphological analysis of both atrial and ventricular channels combined with rate determination in each channel on a cycle-by-cycle basis, dramatically demonstrated the power of modern signal processing in the interpretation of arrhythmias.

One aspect in which analysis of the atrial morphology would be very useful in ICDs is the separation of antegrade versus retrograde atrial conduction. During a 1:1 tachycardia, it is difficult to separate an SVT with 1:1

anterograde conduction (forward conduction from the sinus node through the atrium and AV node to the ventricle) versus a ventricular arrhythmia with retrograde conduction (retrograde conduction from the ventricle through the AV node to the atrium). To differentiate these cases, morphology differences in the atrial electrogram could be utilized, where abnormal morphology would indicate retrograde conduction. Various methods have been described in the literature which use similar approaches as ventricular morphology (112–118).

Distinction of Ventricular Tachycardia and Ventricular Fibrillation

Discriminating between VT and VF might be useful to allow unique zone settings for choice of therapy. Antitachycardia pacing is a lower energy therapy used to treat VT, which is not painful to the patient. Currently, there is difficulty in detecting each VF cycle, leading to electrogram dropout, which leads physicians to expand the VF detection zone to eliminate the possibility of misdiagnosing VF (119,120). Therefore, many VTs are detected as VF and given shock therapy directly. While these are typically fast VTs, there is a possibility that fast VTs can be terminated using anti-tachycardia pacing protocols, with only limited delay of shock therapy, if fast VTs and VF could be differentiated (121). In one study, 76% of fast VTs would have received shock therapy if programmed traditionally (121). However, by expanding the fast VT zone, 81% diagnosed as fast VT were effectively pace-terminated. More sophisticated digital signal processing techniques could be applied to ensure proper separation of VT and VF by methods more intelligent than counting alone.

For separation of VT and VF, CWA using a sinus rhythm template was tested on a passage of monomorphic ventricular tachycardia and a subsequent passage of ventricular fibrillation in each patient (122–124). The standard deviation of the correlation coefficient (ρ) of each class (VT and VF) was used as a discriminant function. This scheme was based upon the empiric knowledge that correlation values are more tightly clustered in the cycle-by-cycle analysis of monomorphic VT and more broadly distributed in the dissimilar waveforms in VF. Results showed easy separation of sinus rhythm from VT and VF; however in the VT/VF separation, standard deviation only achieved limited success Standard deviation requires patient-specific thresholds, may not hold for all template-based algorithms, and adds further computational requirements to the algorithm; therefore, it is not a promising algorithm in its present form for discrimination of VT from VF.

Throne et al. (125) addressed the problem of separating monomorphic and polymorphic VT/VF by using scatter diagram analysis. A moving average filter was applied to rate and morphology channels and plotted as corresponding pairs of points on a scatter diagram with a 15 × 15 grid. The percentage of grid blocks occupied by at least one sample point was determined. Investigators found that monomorphic VTs trace nearly the same path in two-dimensional space and occupy a smaller percentage of the graph than nonregular rhythms such as polymorphic VT or VF.



Figure 11. Basic algorithm for separation of VT and VF using PSC. Once a fast rate is detected, VT and VF are detected for slow fast rates and very fast rates, respectively. Only in the overlap between fast VT and VF rates, is the morphology algorithm implemented. Interquartile range (IQR) of the paired signal concordance over a passage is used.

A magnitude-squared coherence function was developed by Ropella et al. (126), which utilizes filtering and Fourier transformation of intraventricular electrograms derived from two leads with a sliding window to distinguish monomorphic ventricular tachycardia from polymorphic ventricular tachycardia and ventricular fibrillation. This method, while elegant, requires multiple electrode sites and is at present too computationally demanding for consideration in battery operated devices. As technology advances, the possibility of hardware implementation of frequency-based methods such as magnitude-squared coherence and time-domain CWA may become feasible.

A similar algorithm uses two “unipolar” ventricular electrograms, 1 cm apart, to compare the paired signal concordance (PSC) between the electrograms using correlation analysis (127). During normal rhythms and VT, the two closely spaced electrograms will exhibit high correlation, while during VT, the two electrogram will experience low correlation. Considering only rhythms that have a fast rate in the overlap between fast VT and VF rates, the variability of the correlation, measured by interquartile range, over a passage distinguishes VT from VF (Fig. 11).

Complexity measurements have also been utilized for distinction of ventricular tachycardia and fibrillation, including approximate entropy (128), Lempil–Ziv complexity (129), least-squares prony modeling algorithm (130).

OTHER DEVICES THAT USE AUTOMATED ARRHYTHMIA DETECTION

Other commercially available devices that use automated arrhythmia detection algorithms include the automatic external defibrillator and the implantable atrial defibrillator.

Automatic External Defibrillators

Recently, automatic external defibrillators (AEDs) have become widespread and available. The AED is able to determine if the rhythm for an unresponsive, pulseless patients is shockable or unshockable and is able to apply therapy automatically or to inform the user to deliver the therapy (131–133). The AEDs are available on location for large organizations, such as airports, airplanes, businesses, sporting events, schools, and malls (134). This expanded availability dramatically increases the possibility that victims of ventricular fibrillation could receive defibrillation in a timely manner, thus, improving survival rates (135).

The AEDs, operating in a truly automated mode, must be exquisitely accurate in their interpretation of the ECG signal (136,137). In an AED, shockable rhythms are rhythms that will result in death if not treated immediately and include coarse ventricular fibrillation and ventricular tachycardia. Nonshockable rhythms are rhythms where no benefit and even possible harm may result from therapy and include supraventricular tachycardia, atrial fibrillation normal sinus rhythm, and asystole. Asystole is not considered shockable for these devices since the leads may be misplaced and no signal captured. Intermediate rhythms are rhythms that may or may not receive benefit from therapy and include fine VF and VT. Ventricular tachycardia is an intermediate rhythm because often it is hemodynamically tolerated in the patient. A rate threshold is usually programmed in the device (even though there is still no universally accepted or obvious delineation in rate for hemodynamic tolerance in the literature).

Contrary to the ICD, AEDs have an extremely necessary requirement for accurate specificity (shocks when not needed) since these devices are expected to be used by untrained personnel. Algorithms must consider large variations in cardiac rhythms and artifact from CPR or patient movement. The risk to the patient and the technician is too great to allow public use for devices with decreased specificity. Given that a bystander is on the scene and that trained help may soon be available, specificity is more important for the first, or immediate response. However, sensitivity must be considered to ensure the AEDs potential to save lives is maximized. In the AED, more battery power can be utilized (since the device is not implanted), and therefore more sophisticated schemes borrowed from ICD technology have been considered.

Current devices use numerous schemes for determining if the patient is in ventricular fibrillation. Common components include isoelectric content (like PDF algorithm of the ICD), zero crossings, rate, variability, slope, amplitude and frequency (138), all similar techniques to those described in the ICD literature. A review of AED algorithms is given in Ref. 138.

One example of a recent algorithm described in the literature is for a programmable automatic external defibrillator designed to be used in the hospital setting for monitoring and automatic defibrillation, if needed (139). This device uses a programmable rate criterion to detect shockable rhythms. In addition, the device has an algorithm which distinguishes VT and SVT rhythms below a SVT threshold. The algorithm uses three features to discriminate between SVT and VT. The first is the modulation domain function that uses amplitude and frequency characteristics. The second, called waveform factor (WF), provides a running average of the electrocardiogram signal amplitude normalized by the R-wave amplitude. The WF for one beat is as follows:

$$\mathrm{WF}_i = \frac{100 \times \sum_{1}^{N} \mathrm{abs}(A_n)}{N \times \mathrm{abs}(A_r)}$$

where N is the total number of samples between the previous and current beat, A_n is the nth amplitude of the signal, and A_r is the peak. The algorithm uses an eight beat running average. The SVT rhythms would have a small WF value, while VT (which has a wide QRS complex on the surface of the body) would have a high WF value. This algorithm should not be used with patients who have bundle branch block, chronic or paroxysmal. The third feature is called amplitude variability analysis factor, which uses distribution of the average derivative. The measurement is found by calculating the number of derivatives which fall into the baseline bin as a percentage of the total number of sample points. Amplitude variability analysis (AVA) is calculated as follows:

$$\mathrm{AVA} = \frac{100 \times \sum n(i)}{N}$$

where the summation is performed across the baseline bins and $n(i)$ is the number of samples for the ith bin. The baseline bins are defined as 25% of the total bins centered at $n(i)_{\max}$. Exact use of these features in the AED algorithm are not described.

Implantable Atrial Defibrillators

Implantable atrial defibrillators are used in patients with paroxysmal or persistent atrial fibrillation, particularly those which are symptomatic and drug refractory (140,141). Goals in atrial defibrillators are different than ICDs since atrial tachyarrhythmias are typically hemodynamically tolerable, therefore, more time and care can be used to make the decision. The challenge is that the device must sense low, variable amplitude atrial signals, while not sensing far-field ventricular waves. Furthermore, there are also multiple therapies available, antitachycardia pacing for atrial tachycardia, and cardioversion for atrial fibrillation. Lastly, some atrial defibrillators have been combined with ICDs such that back-up ventricular defibrillation therapy is available in this susceptible population (140,142).

A review of algorithms used in atrial defibrillators in given in Ref. 143. For example, Medtronic has a dual-chamber defibrillator that has both atrial and ventricular therapies (140,142). The algorithm for detection uses the same algorithm as the dual-chamber ventricular (only) defibrillator, PR Logic. In addition to this algorithm, there are two zones used for detection of atrial tachycardia and of atrial fibrillation. If the zones overlap, AT is detected if it is regular and AF if it is irregular. The purpose of multiple zones is similar to ventricular devices, in that a variety of therapies can be selected and utilized for each zone. For this device, this includes pacing algorithms for prevention, pacing therapies for termination, and high voltage shocks.

CONCLUSION

This article focuses on the overall approaches used for automated arrhythmia detection. However, this review did not delve into the specifics of comparisons of sensitivity and specificity results for the various algorithms. While, each paper referenced gives performance for a specific test database, it is difficult to compare the results from one study to another. There have been some attempts to develop standardized datasets, including surface electrocardiograms from Physionet (including the MIT-BIH databases) (144) and American Heart Association (145), and intracardiac electrograms, in addition to surface, from Ann Arbor Electrogram Libraries (3). Use of these datasets allows for comparisons, but does not address the differences between performance at the system level that incorporates the hardware components of the specific device. A comprehensive description of the pitfalls in comparing results from one study to another is given in (43). These include limitations of (*1*) benchtesting that does not incorporate specific ICD-system differences and spontaneous arrhythmias, (*2*) limited storage in the ICD making gold standard clinical diagnosis difficult, (*3*) great variations in settings of rate based thresholds and zones, (*4*) variability of types of rhythms included in the study, among others.

In conclusion, examples from the long history of automated arrhythmia detection for implantable cardioverter defibrillators is given with a brief mention of automated external defibrillators and implantable atrial defibrillators. The ICDs are beginning to reach maturity in terms of addressing both sensitivity and specificity in performance of the algorithms to achieve close to perfect detection of life-threatening arrhythmias, with greatly reduced false therapies. In the meantime, automated external defibrillators and implantable atrial defibrillators have learned many lessons from the ICD experience to provide accurate arrhythmia diagnosis. Devices on the horizon incorporating automated arrhythmia detection may include wearable external defibrillators (146,147), wearable wireless monitors, and beyond. This rich area of devices that detect and treat life-threatening arrhythmias shall reduce the risk of sudden cardiac death.

BIBLIOGRAPHY

Cited References

1. American Heart Association. Heart Disease and Stroke Statistics—2005 Update. American Heart Association. Available at http://www.americanheart.org. Accessed 2005.
2. Vilke GM, et al. The three-phase model of cardiac arrest as applied to ventricular fibrillation in a large, urban emergency medical services system. Resuscitation 2005;64:341–346.
3. Jenkins JM, Jenkins RE. Arrhythmia database for algorithm testing: surface leads plus intracardiac leads for validation. J Electrocardiol 2003;36(Suppl):157–1610. Available at http://www.electrogram.com.
4. Nisam S, Barold S. Historical evolution of the automatic implantable cardioverter defibrillator in the treatment of malignant ventricular tachyarrhythmias. In: Alt E, Klein H, Griffin JC, editors. The implantable cardioverter/defibrillator. Berlin: Springer-Verlag; 1992. pt. 1, p 3–23.
5. Mower MM, Reid PR. Historical development of automatic implantable cardioverter-defibrillator. In: Naccarelli GV, Veltri EP, editors. Implantable Cardioverter-Defibrillators, Boston: Scientific Publications; 1993. Chapt. 2. p 15–25.
6. Mower MJ. Clinical and historical perspective. In: Singer I, editor. Implantable Cardioverter Defibrillator. Armonk (NY): Futura; 1994, Chapt. 1. p 3–12.
7. Bach SM, Shapland JE. Engineering aspects of implantable defibrillators. In: Saksena S, Goldschlager N, editors. Electrical Therapy for Cardiac Arrhythmias. Philadelphia: Saunders; 1990. Chapt. 18. p 371–383.
8. Kennedy HL. Ambulatory (Holter) Electrocardiography Technology. Cardiol Clin 1992;10:341–359.
9. Feldman CL, Amazeen PG, Klein MD, Lown B. Computer detection of ventricular ectopic beats. Comput Biomed Res 1970 Dec; 3(6):666–674.
10. Thomas LJ, et al. Automated Cardiac Dysrhythmia Analysis. Proc IEEE Sept 1979;67(9):1322–1337.
11. Collins SM, Arzbaecher RC. An efficient algorithm for waveform analysis using the correlation coefficient. Comput Biomed Res 1981 Aug; 14(4):381–389.
12. Hulting J, Nygards ME. Evaluation of a computer-based system for detecting ventricular arrhythmias. Acta Med Scand 1976;199(12):53–60.
13. Thakor NV. From Holter monitors to automatic defibrillators: developments in ambulatory arrhythmia monitoring. IEEE Trans Biomed Eng 1984 Dec; 31(12):770–778.
14. Feldman CL, Hubelbank M. Cardiovascular Monitoring in the Coronary Care Unit. Med Instrum 1977;11:288–292.
15. Hubelbank M, Feldman CL. A 60x computer-based Holter tape processing system. Med Instrum 1978;Nov–Dec; 12(6):324–326.
16. Govrin O, Sadeh D, Akselrod S, Abboud S. Cross-correlation technique for arrhythmia detection using PR and PP intervals. Comput Biomed Res 1985 Feb; 18(1):37–45.
17. Shah PM, et al. Automatic real time arrhythmia monitoring in the intensive coronary care unit. Am J Cardiol 1977 May 4; 39(5):701–708.
18. Lipschultz A. Computerized arrhythmia monitoring systems: a review. J Clin Eng 1982 Jul–Sep; 7(3):229–234.
19. Lin D, et al. Analysis of time and frequency domain patterns of endocardial electrograms to distinguish ventricular tachycardia from sinus rhythm. Comp Cardiol 1987; 171–174.
20. Knoebel SB, Lovelace DE, Rasmussen S, Wash SE. Computer detection of premature ventricular complexes: a modified approach. Am J Cardiol 1976 Oct; 38(4):440–447.
21. Yanowitz F, Kinias P, Rawling D, Fozzard HA. Accuracy of a continuous real-time ECG dysrhythmia monitoring system. Circulation. 1974 July; 50(1):65–72.
22. Mead CN, et al. A detection algorithm for multiform premature ventricular contractions. Med Instrum 1978;12:337–339.
23. Knoebel SB, Lovelace DE. A two-dimensional clustering technique for identification of multiform ventricular complexes. Med Instrum 1978;12:332–333.
24. Cheng QL, Lee HS, Thakor NV. ECG waveform analysis by significant point extraction. II. Pattern matching. Comput Biomed Res 1987 Oct; 20(5):428–442.
25. Spitz AL, Harrison DC. Automated family classification in ambulatory arrhythmia monitoring. Med Instrum 1978 Nov–Dec; 12(6):322–323.
26. Oliver GC, et al. Detection of premature ventricular contractions with a clinical system for monitoring electrocardiographic rhythms. Comput Biomed Res 1971 Oct; 4(5): 523–541.
27. Yanowitz F, Kinias P, Rawling D, Fozzard HA. Accuracy of a continuous real-time ECG dysrhythmia monitoring system. Circulation 1974 July; 50(1):65–72.

28. Cooper DH, Kennedy HL, Lyyski DS, Sprague MK. Holter triage ambulatory ECG analysis. Accuracy and time efficiency. J Electrocardiol. 1996 Jan; 29(1):33–38.
29. Furman S, Fisher JK, Panizzo F. Necessity of signal processing in tachycardia detection. In: Barold SS, Mugica J, editors. The Third Decade of Cardiac Pacing: Advances in Technology and Clinical Applications. Mt Kisco (NY): Futura; 1982. Pt. 3, Chapt. 1. p 265–274.
30. Jenkins J, et al. Present state of industrial development of devices. PACE May–June 1984;7(II):557–568.
31. Mirowski M, Mower MM, Reid PR. The automatic implantable defibrillator. Am Heart J 1980;100:1089–1092.
32. Langer A, Heilman MS, Mower MM, Mirowski M. Considerations in the development of the automatic implantable defibrillator. Med Instrum May–June 1976;10:163–167.
33. Arzbaecher R. A pill electrode for the study of cardiac dysrhythmia. Med Instrum 1978;12:277–281.
34. Jenkins JM, Wu D, Arzbaecher R. Computer diagnosis of supraventricular and ventricular arrhythmias. Circulation 1979;60:977–987.
35. Paul VE, O'Nunain S, Malik M. Temporal electrogram analysis: algorithm development. PACE Dec. 1990;13:1943–1947.
36. Toivonen L, Viitasalo M, Jarvinen A. The performance of the probability density function in differentiating supraventricular from ventricular rhythms. PACE May 1992;15: 726–730.
37. DiCarlo L, et al. Tachycardia detection by antitachycardia devices: present limitations and future strategies. J Interven Cardiol 1994;7:459–472.
38. Pannizzo F, Mercando AD, Fisher JD, Furman S. Automatic methods for detection of tachyarrhythmias by antitachycardia devices. PACE Feb. 1988;11:308–316.
39. Lang DJ, Bach SM. Algorithms for fibrillation and tachyarrhythmia detection. J Electrocardiol 1990;23(Suppl):46–50.
40. Olson WH. Tachyarrhythmia sensing and detection. In: Singer I, editor. Implantable Cardioverter Defibrillator. Armonk (NY): Futura; 1994. Chapt. 4. p 71–107.
41. Jenkins JM, Caswell SA. Detection algorithms in implantable defibrillators. Proc IEEE 1996;84:428–445.
42. Olson WH. Dual chamber sensing and detection for implantable cardioverter-defibrillators. In: Singer I, Barold SS, Camm AJ, editors. Nonpharmacological Therapy of Arrhythmias for the 21st century. Armonk (NY): Futura; 1998. p 385–421.
43. Aliot E, Mitzsche R, Ribart A. Arrhythmia detection by dual-chamber implantable cardioverter defibrillators: a review of current algorithms. Europace 2004;6:273–286.
44. Thakor NV, Webster JG. Design and evaluation of QRS and noise detectors for ambulatory ECG monitors. Med Biol Eng Comput 1982;20:709–714.
45. Jalaleddine S, Hutchens C. Ambulatory ECG wave detection for automated analysis: a review. ISA Trans 1987;26(4): 33–43.
46. Warren JA, et al. Implantable cardioverter defibrillators. Proc IEEE 1996;84:468–479.
47. MacDonald R, Jenkins J, Arzbaecher R, Throne R. A software trigger for intracardiac waveform detection with automatic threshold adjustment. Proc Computers Cardiol IEEE 30276-6574 1990; 167–170.
48. Winkle RA, et al. Long-term outcome with the automatic implantable cardioverter-defibrillator. J Am Coll Cardiol May 1989;13:1353–1361.
49. Grimm W, Flores BF, Marchlinski FE. Electrocardiographically documented unnecessary, spontaneous shocks in 241 patients with implantable cardioverter defibrillators. PACE Nov. 1992;15:670–669.
50. Nunain SO, et al. Limitations and late complications of third-generation automatic cardioverter-defibrillators. Circulation April 15 1995;91:2204–2213.
51. Warren J, Martin RO. Clinical evaluation of automatic tachycardia diagnosis by an implanted device. PACE 1986; 9:16.
52. Nathan AW, Creamer JE, Davies DW. Clinical experience with a new versatile, software based, tachycardia reversion pacemaker. J Am Coll Cardiol 1987;7:184A.
53. Olson W, Bardy G, Mehra R. Onset and stability for ventricular tachycardia detection in an implantable pacer-cardioverter-defibrillator. Comp Cardiol 1987;34:167–170.
54. Tomaselli G, Scheinman M, Griffin J. The utility of timing algorithms for distinguishing ventricular from supraventricular tachycardias. PACE March–April 1987;10:415.
55. Geibel A, Zehender M, Brugada P. Changes in cycle length at the onset of sustained tachycardias-importance for antitachycardia pacing. Am Heart J March 1988;115:588–592.
56. Ripley KL, Bump TE, Arzbaecher RC. Evaluation of techniques for recognition of ventricular arrhythmias by implanted devices. IEEE Trans Biomed Eng June 1989;36:618–624.
57. Pless BD, Sweeney MB. Discrimination of supraventricular tachycardia from sinus tachycardia of overlapping cycle length. PACE Nov–Dec 1984;7:1318–1324.
58. Arzbaecher R, et al. Automatic tachycardia recognition. PACE May–June 1984;7:541–547.
59. Jenkins JM, et al. Tachycardia detection in implantable antitachycardia devices. PACE Nov–Dec 1984;7:1273–1277.
60. Swerdlow CD, et al. Discrimination of ventricular tachycardia from sinus tachycardia and atrial fibrillation in a tiered-therapy cardioverter. J Am Coll Cardiol 1994;23:1342–1355.
61. Pannizzo F, Furman S. Pattern recognition for tachycardia detection: a comparison of methods. PACE July 1987;10:999.
62. Santel D, Mehra R, Olson W. Integrative algorithm for detection of ventricular tachyarrhythmias from the intracardiac electrogram. Comp Cardiol 1987; 175–177.
63. Lin D, DiCarlo LA, Jenkins JM. Identification of ventricular tachycardia using intracavity ventricular electrograms: analysis of time and frequency domain patterns. PACE Nov. 1988;1592–1606.
64. Tomaselli GF, et al. Morphologic differences of the endocardial electrogram in beats of sinus and ventricular origin. PACE Mar. 1988;11:254–262.
65. Langberg JL, Gibb WJ, Auslander DM, Griffin JC. Identification of ventricular tachycardia with use of the morphology of the endocardial electrogram. Circulation June 1988;77: 1363–1369.
66. Throne RD, Jenkins JM, Winston SA, DiCarlo LA. A comparison of four new time domain methods for discriminating monomorphic ventricular tachycardia from sinus rhythm using ventricular waveform morphology. IEEE Trans Biomed Eng June 1991;38:561–570. (U. S. Pat. No. 5,000,189 Mar. 19, 1991).
67. Steinhaus BM, et al. Detection of ventricular tachycardia using scanning correlation analysis. PACE Dec. 1990;13: 1930–1936.
68. Greenhut SE, et al. Separation of ventricular tachycardia from sinus rhythm using a practical, real-time template matching computer system. PACE Nov. 1992;15:2146–2153.
69. Gold MR, et al. Advanced rhythm discrimination for implantable cardioverter defibrillators using electrogram vector timing and correlation. J Cardiovasc Electrophysiol 2002; 13:1092–1097.
70. Swerdlow CD, et al. Discrimination of ventricular tachycardia from supraventricular tachycardia by a downloaded wavelet transform morphology algorithm. J Cardiovasc Electrophysiol 2002;13:432–441.

71. Duru F, et al. Morphology discriminator feature for enhanced ventricular tachycardia discrimination in implantable cardioverter defibrillators. PACE 2000;23:1365–1374.
72. Boriani G, et al. Clinical evaluation of morphology discrimination: an algorithm for rhythm discrimination in cardioverter defibrillators. PACE 2001;24:994–1001.
73. Throne RD, Jenkins JM, Winston SA, DiCarlo LA. Use of tachycardia templates for recognition of recurrent monomorphic ventricular tachycardia. Comp Cardiol 1989;171–174.
74. Stevenson SA, Jenkins JM, DiCarlo LA. Analysis of the intraventricular electrogram for differentiation of distinct monomorphic ventricular arrhythmias. J Am Coll Cardiol (submitted June 1995;).
75. Paul VE, et al. Variability of the intracardiac electrogram: effect on specificity of tachycardia detection. PACE Dec. 1990;13:1925–1829.
76. Finelli CJ, et al. Intraventraventricular electrogram morphology: effect of increased heart rate with and without accompanying changes in sympathetic tone. Comp Cardiol 1990; 115–118.
77. Rosenheck S, Schmaltz S, Kadish AH, Morady F. Effect of rate augmentation and isoproterenol on the amplitude of atrial and ventricular electrograms. Am J Cardiol July 1 1990;66:101–102.
78. Belz MK, et al. The effect of left ventricular intracavitary volume on the unipolar electrogram. PACE Sept. 1993;16: 1842–1852.
79. Caswell SA, et al. Chronic bipolar electrograms are stable during changes in body position and activity: implications for antitachycardia devices. PACE April 1995;18:871.
80. Throne RD, Jenkins JM, Winston SA, DiCarlo LA. Paroxysmal bundle branch block of supraventricular origin: a possible source of misdiagnosis in detecting ventricular tachycardia using ventricular electrogram morphology. PACE April 1990;13:453–458.
81. Gilberg JM, Olson WH, Bardy GH, Mader SJ. Electrogram width algorithms for discrimination of supraventricular rhythm from ventricular tachycardia. PACE April 1994;17:866.
82. Unterberg C, et al. Long-term clinical experience with the EGM width detection criteria for differentiation of supraventricular and ventricular tachycardia in patients with implantable cardioverter defibrillators. PACE 2000;23: 1611–1617.
83. Kingenheben T, Sticherling C, Skupin M, Hohnloser SH. Intracardiac QRS electrogram width—an arrhythmia detection feature for implantable cardioverter defibrillators: exercise induced variation as a base for device programming. PACE 1998;21:1609–1617.
84. Favale S, et al. Electrogram width parameter analysis in implantable cardioverter defibrillators: influence of body position and electrode configuration. PACE 2001;24:1732–1738.
85. Leitch JW, et al. Correlation between the ventricular electrogram amplitude in sinus rhythm and in ventricular fibrillation. PACE Sept. 1990;13:1105–1109.
86. Ellenbogen KA, et al. Measurement of ventricular electrogram amplitude during intraoperative induction of ventricular tachyarrhythmias. Am J Cardiol Oct. 15 1992;70:1017–1022.
87. Pannizzo F, Furman S. Frequency spectra of ventricular tachycardia and sinus rhythm in human intracardiac electrograms: application to tachycardia detection for cardiac pacemakers. IEEE Trans Biomed Eng June 1988; 421–425.
88. Slocum J, Sahakian A, Swiryn S. Computer discrimination of atrial fibrillation and regular atrial rhythms from intra-atrial electrograms. PACE May 1988;11:610–621.
89. Aubert AE, et al. Frequency analysis of VF episodes during AICD implantation. PACE June 1988;11(Suppl):891.
90. Lovett EG, Ropella KM. Autoregressive spread-spectral analysis of intracardiac electrograms: comparison of Fourier analysis. Comp Cardiol 1992; 503–506.
91. Minami K, Nakajima H, Toyoshima T. Real-time discrimination of ventricular tachyarrhythmia with Fourier-transform neural network. IEEE Trans Biomed Eng 1999;46:179–185.
92. Yan MC, Jenkins JM, DiCarlo LA. Feasibility of arrhythmia recognition by antitachycardia devices using time-frequency analysis with neural network classification. PACE 1995;18: 871.
93. Farrugia S, Yee H, Nickolls P. Implantable cardioverter defibrillator electrogram recognition with a multilayer perceptron. PACE Jan. 1993;16:228–234.
94. Leong PH, Jabri MA. MATIC-An intracardiac tachycardia classification system. PACE Sept. 1982;15:1317–1331.
95. Rojo-Alvarez JL, et al. Automatic discrimination between supraventricular and ventricular tachycardia using a multilayer perceptron in implantable cardioverter defibrillators. PACE 2002;25:1599–1604.
96. Wang Y, et al. A short-time multifractal approach for arrhythmia detection based on fuzzy neural network. IEEE Trans Biomed Eng 2001;48:989–995.
97. Al-Fahoum AS, Howitt I. Combined wavelet transformation and radial basis neural networks for classifying life-threatening cardiac arrhythmias. Med Biol Eng Comp 1999;27: 566–573.
98. Arzbaecher R, et al. Automatic tachycardia recognition. PACE May–June 1984;7:541–547.
99. Jenkins JM, et al. Tachycardia detection in implantable antitachycardia devices. PACE Nov–Dec 1984;7:1273–1277.
100. Schuger CD, Jackson K, Steinman RT, Lehmann MH. Atrial sensing to augment ventricular tachycardia detection by the automatic implantable cardioverter defibrillator: a utility study. PACE Oct. 1988;11:1456–1463.
101. Caswell SA, DiCarlo LA, Chiang CJ, Jenkins JM. Automated analysis of spontaneously occurring arrhythmias by implantable devices: limitation of using rate and timing features alone. J Electrocardiol 1994;27(Suppl):151–156.
102. Chiang CJ, Jenkins JM, DiCarlo LA. Discrimination of ventricular tachycardia from sinus tachycardia by antitachycardia devices: value of median filtering. Med Engr Phys Nov. 1994;16:513–517.
103. Chiang CJ, Jenkins JM, DiCarlo LA. The value of rate regularity and multiplicity measures to detect ventricular tachycardia in atrial fibrillation of flutter with a fast ventricular response. PACE Sept. 1994;17:1503–1508.
104. Hintringer F, Schwarzacher S, Eibl G, Pachinger O. Inappropriate detection of supraventricular arrhythmias by implantable dual chamber defibrillators: a comparison of four different algorithms. PACE 2001;24:835–841.
105. Hintringer F, et al. Comparison of the specificity of implantable dual chamber defibrillator detection algorithms. PACE 2004;27:976–982.
106. Lavergne T, et al. Preliminary clinical experience with the first dual chamber pacemaker defibrillator. PACE 1997;20: 182–188.
107. Mletzko R, et al. Enhanced specificity of a dual chamber ICD arrhythmia detection algorithm by rate stability criteria. PACE 2004;27:1113–1119.
108. Bailin SJ, et al. Clinical investigation of a new dual-chamber implantable cardioverter defibrillator with improved rhythm discrimination capabilities. J Cardiovasc Electrophysiol 2003;14:144–149.
109. Chiang CJ, et al. Real-time arrhythmia identification from automated analysis of intraatrial and intraventricular electrograms. PACE Jan. 1993;16:223–227.

110. Caswell SA, et al. Pattern recognition of cardiac arrhythmias using two intracardiac channels. Comp Cardiol 1993; 181–184.
111. DiCarlo LA, Lin D, Jenkins JM. Automated interpretation of cardiac arrhythmias. J Electrocardiol Jan. 1993;26:53–67.
112. Amikan S, Furman S. A comparison of antegrade and retrograde atrial depolarization in the electrogram. PACE May 1983;6:A111.
113. Wainwright R, Davies W, Tooley M. Ideal atrial lead positioning to detect retrograde atrial depolarization by digitization and slope analysis of the atrial electrogram. PACE Nov–Dec. 1984;7:1152–1157.
114. Davies DW, Wainwright RJ, Tooley MA. Detection of pathological tachycardia by analysis of electrogram morphology. PACE March–April 1986;9:200–208.
115. McAlister HF, et al. Atrial electrogram analysis: antegrade versus retrograde. PACE Nov. 1988;11:1703–1707.
116. Throne RD, et al. Discrimination of retrograde from anterograde atrial activation using intracardiac electrogram waveform analysis. PACE Oct. 1989;12:1622–1630.
117. Saba S, et al. Use of correlation waveform analysis in discrmination between anterograde and retrograde atrial electrograms during ventricular tachycardia. J Cardiovasc Electrophysiol 2001;12:145–149.
118. Strauss D, Jung J, Rieder A, Manoli Y. Classification of endocardial electrograms using adapted wavelet packets and neural networks. Ann Biomed Eng 2001;29:483–492.
119. DiCarlo LA, et al. Impact of varying electrogram amplitude sensing threshold upon the performance of rate algorithms for ventricular fibrillation detection. Circulation Oct. 1994;90:I–176.
120. Caswell SA, et al. Ventricular tachycardia versus ventricular fibrillation: Discrimination by antitachycardia devices. J Electrocardiol 1996;28:29.
121. Wathen MS, et al. PainFREE Rx II Investigators. Prospective randomized multicenter trial of empirical antitachycardia pacing versus shocks for spontaneous rapid ventricular tachycardia in patients with implantable cardioverter-defibrillators: Pacing Fast Ventricular Tachycardia Reduces Shock Therapies (PainFREE Rx II) trial results. Circulation 2004;110:2591–2596.
122. Jenkins JM, Kriegler C, DiCarlo LA. Discrimination of ventricular tachycardia from ventricular fibrillation using intracardiac electrogram analysis. PACE April 1991;14:718.
123. DiCarlo LA, Jenkins JM, Winston SA, Kriegler C. Differentiaion of ventricular tachycardia from ventricular fibrillation using intraventricular electrogram morphology. Am J Cardiol Sept. 15 1992;70:820–822.
124. Jenkins JM, Caswell SA, Yan MC, DiCarlo LA. Is waveform analysis a viable consideration for implantable devices given its computational demand? Comp Cardiol 1993; 839–842.
125. Throne RD, et al. Scatter diagram analysis: a new technique for discriminating ventricular tachyarrhythmias. PACE July 1994;17:1267–1275.
126. Ropella KM, Baerman JM, Sahakian AV, Swiryn S. Differentiation of ventricular tachyarrhythmias. Circulation Dec. 1990;82:2035–2043.
127. Caswell SA, Jenkins JM, DiCarlo LA. Comprehensive scheme for detection of ventricular fibrillation for implantable cardioverter defibrillators. J Electrocardiol 1998;30: 131–136.
128. Schuckers SA. Use of approximate entropy measurements to classify ventricular tachycardia and fibrillation. J Electrocardiol 1998;31(Suppl):101–105.
129. Zhang HX, Zhu YX, Wang ZM. Complexity measure and complexity rate information based detection of ventricular tachycardia and fibrillation. Med Biol Eng Comp 2000;38: 553–557.
130. Chen SW. A two-stage discrmination of cardiac arrhythmias using a total least squares-based prony modeling algorithm. IEEE Trans Biomed Eng 2000;47:1317–1327.
131. American Heart Assocation. Emergency Cardiac Care Committee and Subcommittees. Guidelines for cardiopulmonary resuscitation and emergency cardiac care. JAMA 1992;268: 2171–2302.
132. Aronson AL, Haggar B. The automatic external defibrillator-pacemaker: clinical rationale and engineering design. Med Instrum 1986;20:27–35.
133. Charbonnier FM. External defibrillators and emergency external pacemekers. Proc IEEE 1996;84:487–499.
134. Weisfeldt ML, et al. American Heart Association Report on the Public Access Defibrillation Conference December 8–10, 1994. Automatic External Defibrillation Task Force. Circulation 1995;92:2740–2747.
135. Dimmit MA, Griffiths SE. What's new in prehospital care? Nursing 1992;22:58–61.
136. Association for the Advancement of Medical Instrumentation. Automatic external defibrillators and remote-control defibrillators [American National Standard]. AAMI 1993; ANSI/AAMI DF39-1993.
137. American Heart Association. AED Task Force, Subcommittee on Safety and Efficacy. Automatic External Defibrillators for Public Access Use: Recommendations for Specifying and Reporting Arrhythmia Analysis Algorithm Performance, Incorporating new Waveforms, and Enhancing Safety. AHA 1996.
138. Charbonnier FM. Algorithms for arrhythmia analysis in AEDs. In: Tacker WA Jr, editor. Defibrillation of the Heart: ICDs, AEDs and Manual. St Louis (MO): Mosby/Yearbook; 1994.
139. Mattioni T, et al. Performance of an automatic external cardioverter-defibrillator algorithm in discrimination of supraventricular from ventricular tachycardia. Am J Cardiol 2003;91:1323–1326.
140. Sopher SM, Camm AJ. Atrial defibrillators. In: Singer I, Barold SS, Camm AJ, editors. Nonpharmacological Therapy of Arrhythmias for the 21st century. Armonk (NY): Futura; 1998. p 473–489.
141. Gold MR, et al. Clinical experience with a dual-chamber implantable cardioverter defibrillator to treat atrial tachyarrhythmias. J Cardiovasc Electrophysiol 2001;12: 1247–1253.
142. Swerdlow CD, et al. Detection of atrial fibrillation and flutter by a dual-chamber implantable cardioverter-defibrillator. Circulation 2000;101:878–885.
143. KenKnight BH, Lang DJ, Scheiner A, Cooper RAS. Atrial defibrillation for implantable cardioverter-defibrillators: lead systems, waveforms, detection algorithms, and results. In: Singer I, Barold SS, Camm AJ, editors. Nonpharmacological Therapy of Arrhythmias for the 21st century. Armonk (NY): Futura; 1998. p 457–471.
144. Costa M, Moody GB, Henry I, Goldberger AL. PhysioNet: an NIH research resource for complex signals. J Electrocardiol 2003;36(Suppl) 139–144. Available at http://www.physionet.org.
145. American Heart Association ECG Database, Available from ECRI, 5200 Butler Pike, Plymouth Meeting, PA 19462 USA, http://www.ecri.org/.
146. Reek S, et al. Clinical efficacy of a wearable defibrillator in acutely terminating episodes of ventricular fibrillation using biphasic shocks. PACE 2003;26:2016–2022.
147. Feldman AM, et al. Use of a wearable defibrillator in terminating tachyarrhythmias in patients at high risk for sudden death: results of WEARIT/BIROAD. PACE 2004;27:4–9.

See also AMBULATORY MONITORING; DEFIBRILLATORS; ELECTROCARDIOGRAPHY, COMPUTERS IN; EXERCISE STRESS TESTING.

ARTERIAL TONOMETRY. See TONOMETRY, ARTERIAL.

ARTIFICIAL BLOOD. See BLOOD, ARTIFICIAL.

ARTIFICIAL HEART. See HEART, ARTIFICIAL.

ARTIFICIAL HEART VALVE. See HEART VALVE PROSTHESES.

ARTIFICIAL HIP JOINTS. See HIP JOINTS, ARTIFICIAL.

ARTIFICIAL LARYNX. See LARYNGEAL PROSTHETIC DEVICES.

ARTIFICIAL PANCREAS. See PANCREAS, ARTIFICIAL.

ARTERIES, ELASTIC PROPERTIES OF

KOZABURO HAYASHI
Okayama University of Science
Okayama, Japan

INTRODUCTION

The elastic properties of the arterial wall are very important because they are closely related to arterial physiology and pathology, especially via effects on blood flow and arterial mass transport. Furthermore, stresses and strains in the arterial wall are prerequisite for the understanding of the pathophysiology and mechanics of the cardiovascular system. Stresses and strains cannot be analyzed without exact knowledge of the arterial elasticity.

STRUCTURE OF ARETRIAL WALL AND BASIC CHARACTERISTICS

Arteries become smaller in diameter with increasing distance from the heart, depending on functional demands (1). In concert with this reduction in size, their structure, chemical composition, and wall thickness-inner diameter ratio gradually change in a way that leads to a progressive increase both in stiffness and in their ability to change their inner diameter in response to a variety of chemical and neurological control signals.

Arterial wall is inhomogeneous not only structurally, but also histologically. It is composed of three layers (intima, media, and adventitia), which are separated by elastic membranes. Because the media is much thicker than the other two layers and supports load induced by blood pressure, its mechanical properties represent the properties of arterial wall. The media is mainly composed of elastin, collagen, and cells (smooth muscle cell and fibroblast). Roughly speaking, elastin gives an artery its elasticity, while collagen resists tensile forces and gives the artery its burst strength. Smooth muscle cells contract or relax in response to mechanical, chemical, and the other stimuli, which alters the deformed configuration of arteries. The wall compositions vary at different locations depending on required functions. For example, collagen and smooth muscle increase and elastin decreases at more distal sites in conduit arteries; the ratio of collagen to elastin increases in more distally located arteries. Collagen and elastin are essentially similar proteins, but collagen is very much stronger and stiffer than elastin. Therefore, the change of arterial diameter developed by blood pressure pulsation depends on the arterial site; it is larger in more proximal arteries.

Like most biological soft tissues, arteries undergo large deformation when they are subjected to physiological loading, and their force-deformation and stress–strain relations are nonlinear partly because of the above-mentioned inhomogeneous structure and partly because of the nonlinear characteristics of each component itself. Since collagen is a long-chained high polymer, it is intrinsically anisotropic. Moreover, not only collagen and elastin fibers, but also cells, are oriented in tissues and organs in order so that their functions be most effective. Inevitably, the arterial wall is mechanically anisotropic like many other biological tissues. Biological soft tissues including arterial wall demonstrate opened hysteresis loops in their force–deformation and stress–strain curves, which means that those tissues are viscoelastic. In such materials, the stress state is not uniquely determined by current strain, but depends also on the history of deformation. When a viscoelastic tissue is elongated and maintained at some length, load does not stay at a specific level, but decreases rather rapidly at first and then gradually (relaxation). If some constant load is applied to the tissue, it is elongated with time rather rapidly at first and then gradually (creep). Viscoelastic materials generally show different stress–strain properties under different strain rates. It is true, and higher strain rates give higher stresses. However, such a strain rate effect is not so much in biological soft tissues like arteries, namely, their elastic properties are not more sensitive to strain rate. Therefore, it is not always necessary to consider viscoelasticity for arterial mechanics; it is very often enough to assume wall material to be elastic. Many biological soft tissues contain water of $> 70\%$. Therefore, they hardly change their volume even if load is applied, and they are almost incompressible. The incompressibility assumption is very important in the formulation of constitutive laws of soft tissues, because it imposes a constraint on the strains and they are not independent.

MEASUREMENT OF ARTERIAL ELASTICITY

In Vitro Tests

It is widely recognized that the mechanical properties of blood vessels do not change for up to 48 h if tissues are stored at $\sim 4\ ^\circ\mathrm{C}$ (1). One of the basic methods for the determination of the mechanical properties of biological tissues is uniaxial tensile testing on excised specimens. In this test, an increasing force is steadily applied to the longitudinal direction of a specimen, and the resulting specimen deformation is measured, which gives relations between stress (force divided by specimen cross-sectional area) and strain (specimen elongation divided by reference specimen length). This *in vitro* test is simple but, nevertheless, provides us with basic and useful information on



Figure 1. An *in vitro* experimental setup for the pressure–diameter–axial force test of a tubular arterial specimen. Internal pressure or outer diameter can be controlled with a feedback system (2).

the mechanical properties of tissues. Dumbbell-shape specimens, helically stripped specimens, and ring specimens are commonly used for arterial walls.

Under *in vivo* conditions, arteries are tethered to or constrained by perivascular connective tissues and side branches, and pressurized by blood from inside. These forces develop multiaxial stresses in the wall. For the determination of the mechanical characteristics of arteries under multiaxial conditions, biaxial tensile tests on flat specimens are utilized to simultaneously apply forces in the circumferential and longitudinal directions; however, the effect of wall radial stress is ignored in this case.

Although stress–strain data obtained from the above-mentioned uniaxial and biaxial tests on flat, strip, and ring specimens are often used to represent the elastic properties of arterial walls, the data obtained from pressure–diameter tests on the tubular segments of blood vessels are more important and realistic. An example of the test devices is shown in Fig. 1 (2). A tubular specimen is mounted in the bath filled with Krebs–Ringer solution, which is kept at 37 °C and aerated with 95% O_2 and 5% CO_2 gas mixture. Then, it is extend to the *in vivo* length to mimic the *in vivo* condition, because arteries inside the body are tethered to the surrounding tissues as mentioned above and, therefore, they are extended in the axial direction. A diaphragm-type actuator, which is controlled with a sequencer, is incorporated in the device for the application of internal pressure to the specimen. The internal pressure or specimen diameter can be controlled with the sequencer during pressure–diameter tests. The pressure is measured with a fluid-filled pressure transducer, while the outer diameter of the specimen is determined with a video dimension analyzer combined with a CCD camera. If the measurements of axial force are required in order to obtain pressure–diameter–axial force relations for the purpose of determining multiaxial constitutive laws, a load cell attached to one end of the vessel can be used.

In Vivo Measurements

It may be more realistic to obtain data from *in vivo* experiments under *in situ* conditions rather than to get data from *in vitro* biomechanical tests. As a result of recent progress in ultrasonic techniques, arterial diameter and even arterial wall thickness can be measured noninvasively with fairly good precision. These methods are being used not only for *in vivo* animal experiments, but also for clinical diagnosis of vascular diseases. It is true that the data obtained from these experiments and clinical cases are very useful, and provide important information concerning arterial mechanics. On the other hand, it is also true that many factors considerably affect the results obtained. These include physiological reactions to momentary changes in body and ambient conditions as well as the effects of anesthesia and respiration. In addition, since there has been some difficulty in applying the methods to small-diameter blood vessels, accurate measurements of vascular diameter and wall thickness with current techniques have been mostly limited to aortas and large arteries.

Before noninvasive ultrasonic techniques were developed, *in vivo* measurements of vascular diameter were invasively performed following surgical exposure of blood vessels, using strain gauge-mounted cantilevers, strain gauge-pasted calipers, and sonomicrometers. For example, a pair of miniature ultrasonic sensors may be used for the measurement of the outer diameter of a blood vessel (3). They are attached to the adventitial surface of a blood vessel so as to face each other across the vascular diameter. The diameter is determined from the transit time of the pulses between the two sensors. Similar sonomicrometers have been used for the measurement of arterial diameter not only in anesthetized, but also in conscious animals.

The noninvasive measurement of the elastic properties of arteries offers several significant advantages over invasive techniques. First, the nontraumatic character of the measurement guarantees a physiological state of the arterial wall, whereas such key functional elements of the wall as endothelium and smooth muscle might be affected in certain invasive measurement techniques. Second, it is of great clinical interest because it allows the monitoring of many outpatients and, therefore, it is well adapted for epidemiological or cross-sectional studies.

Noninvasive measurement of the arterial diameter can be done with ultrasonic echo-tracking techniques; recent improvements of the original technique have been proposed, which include digital tracking, prior inverse filtering, and coupling with B-mode imaging (1).

There exist no direct ways to measure pressure noninvasively in large central arteries, such as the aorta. Thus, regardless of the progress of ultrasonic and magnetic resonance imaging techniques which allow for the noninvasive measurement of vascular diameter, mechanical properties, such as compliance and elastic modulus cannot be derived from first principles. Therefore, primarily for clinical use, as an indirect, but noninvasive way of estimating the mechanical properties, the pulse wave velocity, c (see the next section), is often obtained from the measurements of pulsation at two distinct points along the vessel. One of the major drawbacks of this technique is low accuracy. The other one is that it yields a single value for the wave velocity. Because of the nonlinear elastic properties of the arterial wall, the pulse wave velocity sensitively changes depending on blood pressure. Therefore, the determination of a single value or a typical value of the arterial stiffness estimated from the pulsation does not provide a full description of the mechanical properties of the arterial wall.

MATHEMATICAL EXPRESSION OF ARTERIAL ELASTICITY

Uniaxial Tensile Behavior

There are many tensile test data from arterial walls in humans and animals (4). Arterial walls exhibit nonlinear force-deformation or stress–strain behavior, having higher distensibility in the low force or stress range and losing it at higher force or stress. To represent strain in such biological soft tissues that deform largely and nonlinearly, we commonly use extension ratio, λ, which is defined by the ratio of the current length of a specimen (L) to its initial length (L_0). If we plot a stress/extension ratio curve as the slope of a stress/extension ratio curve versus stress, we can see that the relation is composed of one or two straight lines (1). Each line is described by

$$dT/d\lambda = BT + C \tag{1}$$

where T is Lagrangian stress defined by F/A_0 (F, force; A_0, cross-sectional area of an undeformed specimen), and B and C are constants. This is also expressed by

$$T = A[\exp B(\lambda - 1) - 1] \tag{2}$$

where A is equal to C/B. This type of exponential formulation is applicable to the description of the elastic behavior of many other biological soft tissues (5).

Pressure–Diameter Relations

For practical purposes, it is convenient to use a single parameter that expresses the arterial elasticity under living conditions. In particular, for noninvasive diagnosis in clinical medicine, material characterization should be simple, yet quantitative. For this purpose, several parameters have been proposed and commonly utilized (1). These include pressure–strain elastic modulus, E_{p} and vascular compliance, C_{v}. Pulse wave velocity, c, which was mentioned above, is also used to express elastic properties of the arterial wall. These parameters are described by

$$E_{\mathrm{p}} = \Delta P/(\Delta D_{\mathrm{o}}/D_{\mathrm{o}}) \tag{3}$$

$$C_{\mathrm{v}} = (\Delta V/V)/\Delta P \tag{4}$$

and

$$c^2 = (S/\rho)(\Delta P/\Delta S) = (V/\rho)(\Delta P/\Delta V) \tag{5}$$

where D_{o}, V, and S are the outer diameter, volume, and luminal area of a blood vessel at pressure P, respectively, and ΔD_{o}, ΔV, and ΔS are their increments for the pressure increment, ΔP. The parameter ρ is the density of the blood.

To calculate these parameters, we do not need to measure the wall thickness; for E_{p} and C_{v}, we need to know only pressure–diameter and pressure–volume data, respectively, at a specific pressure level. However, we should remember that these parameters express the stiffness or distensibility of a blood vessel. Therefore, they are structural parameters, and do not rigorously represent the inherent elastic properties of the wall material; in this sense, they are different from the elastic modulus which is explained below. In addition, these parameters are defined at specific pressures, and give different values at different pressure levels because the pressure–diameter relations of arteries are nonlinear.

To overcome this shortcoming, several functions have been proposed to mathematically describe pressure–diameter, pressure–volume, and pressure-luminal area data, and one or several parameters included in these equations have been used for the expression of the elastic characteristics of arteries. Among these functions, the following equation is one of the simplest and most reliable for the description of pressure-diameter relations of arteries in the physiological pressure range (6):

$$\ln(P/P_s) = \beta(D_{\mathrm{o}}/D_s - 1) \tag{6}$$

where P_{s} is a standard pressure and D_{s} is the wall diameter at pressure P_{s}. A physiologically normal blood pressure like 100 mmHg (13.3 kPa) is recommended for the standard pressure, P_{s}. As an example, Fig. 2 shows the pressure–diameter relationships of a human femoral artery under normal and active conditions of vascular smooth muscle and the relations between the logarithm of pressure ratio, P/P_{s}, and distension ratio, $D_{\mathrm{o}}/D_{\mathrm{s}}$. Figure 2a demonstrates nonlinear behavior of the artery under both conditions, while Fig. 2b shows the close fit of the data to Eq. 6 over a rather wide pressure range. The coefficient, β, called the stiffness parameter, represents the structural stiffness of a vascular wall; it does not depend upon pressure. This parameter has been used for the evaluation of the stiffness of arteries not only in basic investigations, but also in clinical studies (1).

As can be seen from Fig. 2a, under the normal condition, arteries greatly increase the diameter with pressure under a low pressure range, say < 60 mmHg (8 kPa), and then gradually lose the distensibility at higher pressures. When vascular smooth muscle cells are activated by stimuli, arteries are contracted and their diameter decreases in a



Figure 2. Pressure–diameter (a) and pressure ratio–distension ratio (b) relations of a human femoral artery under normal and active conditions (*in vitro* study) (1,7).

physiological pressure range and below the range [< 200 mmHg (26.6 kPa) in Fig. 2], and their pressure–diameter curves become greatly different from those observed under the normal condition.

To express the elastic properties of wall material, it is necessary to use a material parameter such as elastic modulus or Young's modulus, which is the slope of a linear stress–strain relation. For arterial walls that have nonlinear stress–strain relations, the following incremental elastic modulus has been often used for this purpose (8):

$$H_{\theta\theta} = 2D_i^2 D_o(\Delta P/\Delta D_o)/(D_o^2 - D_i^2) + 2PD_o^2/(D_o^2 - D_i^2) \quad (7)$$

where D_i is the internal diameter of a vessel. This equation was derived using the theory of small elastic deformation superposed on finite deformation in the case of a pressurized orthotropic cylindrical tube.

To calculate this modulus, it is necessary to know the thickness or internal diameter of a vessel. In *in vitro* experiments, we can calculate them from D_o, the internal and external diameters under no-load conditions measured after pressure–diameter testing, the *in vivo* axial extension ratio, and assuming the incompressibility of wall material. Noninvasive measurement of wall thickness or internal diameter on intact vessels has been rather difficult compared with the measurement of external diameter; however, it is now possible with high accuracy ultrasonic echo systems as mentioned above.

Constitutive Laws

Mathematical description of the mechanical behavior of a material in a general form is called a constitutive law or constitutive equation. We cannot perform any mechanical analyses without knowledge of constitutive laws of materials. Strain energy functions are commonly utilized for formulating constitutive laws of biological soft tissues that undergo large deformation (5). Let W be the strain energy per unit mass of a tissue, and ρ_0 be the density in the zero-stress state. Then, $\rho_0 W$ is the strain energy per unit volume of the tissue in the zero-stress state, and this is called the strain energy density function. Because arterial tissue is considered as an elastic solid, a strain energy function exists, and the strain energy W is a function solely of the Green strains:

$$W = W(E_{ij}) \quad (8)$$

where E_{ij} are the components of the Green strain tensor with respect to a local rectangular Cartesian coordinate system.

Under physiological conditions, arteries are subjected to axisymmetrical loads, and the axes of the principal stresses and strains coincide with the axes of mechanical orthotropy. Moreover, the condition of incompressibility is used to eliminate the radial strain E_{rr}, and therefore the strain energy function becomes a function of the circumferential and axial strains $E_{\theta\theta}$ and E_{zz}. Then, the constitutive equations for arteries are

$$\sigma_{\theta\theta} - \sigma_{rr} = (1 + 2E_{\theta\theta})\partial(\rho_0 W)/\partial E_{\theta\theta} \quad (9)$$

and

$$\sigma_{zz} - \sigma_{rr} = (1 + 2E_{zz})\partial(\rho_0 W)/\partial E_{zz} \quad (10)$$

where $\sigma_{\theta\theta}$, σ_{zz}, and σ_{rr} are Cauchy stresses in the circumferential, axial, and radial directions, respectively. Thus, we need to know the details of the strain energy function to describe stress–strain relations.

Three major equations have so far been proposed for the strain energy function of arterial wall. Vaishnav et al. (9) advocated the following equation:

$$\rho_0 W = (c/2)\exp(b_1 E_{rr}^2 + b_2 E_{\theta\theta}^2 + b_3 E_{zz}^2 + 2b_4 E_{rr}E_{\theta\theta} + 2b_5 E_{\theta\theta}E_{zz} + 2b_6 E_{zz}E_{rr}) \quad (11)$$

where $E_{\theta\theta}$ and E_{zz} are Green strains in the circumferential and axial directions, respectively, and A, B, and so on, are constants.

Chuong and Fung (10) proposed another form with an exponential function:

$$\rho_0 W = (c/2)\exp(b_1 E_{rr}^2 + b_2 E_{\theta\theta}^2 + b_3 E_{zz}^2 + 2b_4 E_{rr}E_{\theta\theta} + 2b_5 E_{\theta\theta}E_{zz} + 2b_6 E_{zz}E_{rr}) \quad (12)$$

where c, b_1, b_2, and so on, are material constants.

Later, Takamizawa and Hayashi (11) proposed a logarithmic form of the function described by

$$\rho_0 W = -C\ln(1 - a_{\theta\theta}E_{\theta\theta}^2/2 - a_{zz}E_{zz}^2/2 - a_{\theta z}E_{\theta\theta}E_{zz}) \quad (13)$$

where C, $a_{\theta\theta}$, a_{zz}, and $a_{\theta z}$ characterize the elastic properties of a material.

By using one of these strain energy equations or another type of equation for W in Eqs. 9 and 10, and applying the equations of equilibrium and boundary conditions, we determine the values of material constants. Although all of the proposed formulations describe quite well the elastic behavior of arterial walls, we prefer to reduce the number of constants included in the equations in order to handle them more easily, as well as to give physical meanings to the constants. For this reason, the logarithmic expression (Eq. 13) may be advantageous.

ELASTIC PROPERTIES OF NORMAL ARTERIES

Figure 3 shows β values of common carotid arteries, intracranial vertebral arteries, and coronary arteries obtained from autopsied human subjects of different ages (7). Note that arterial stiffness is much larger in the coronary arteries than in the other arteries, and also that intracranial vertebral arteries are considerably stiffer than extracranially located common carotid arteries. As can be seen from this figure, almost all the data obtained from normal human aortas and conduit arteries show that the structural stiffness of wall (e.g., E_p and β) increases with age rather gradually until the age of 40 years, and rapidly thereafter; on the other hand, the wall compliance (C_v) decreases with age. The stiffness of intracranial arteries like the intracranial vertebral artery progressively increases until 20 years, and then more slowly (6). There seems to be almost no age-related change in the human coronary artery (12).



Figure 3. Age-related changes in the wall stiffness of human arteries. (*In vitro* studies, reproduced from Ref. 7.)

Most of the data obtained from arteries in animals indicated that the incremental elastic modulus or the slope of stress–strain curve increases with age, although there are several opposite data (13).

ELASTIC PROPERTIES OF DISEASED ARTERIES

Hypertension

Hypertension is recognized as one of the important risk factors for many cardiovascular diseases, including atherosclerosis and stroke. Elevated blood pressure exerts influences on the synthetic activity of vascular smooth muscle cells, and is believed to induce changes in structure and morphology of the arterial wall, its mechanical properties, and vascular contractility. It is therefore very important to understand arterial mechanics in hypertension. However, results from the extensive literature concerning the elastic properties of hypertensive arteries are contradictory and inconclusive (1,7,13,14). As mentioned above, when we analyze the reported data, we should remember that the values of such parameters as E_p (Eq. 3) and C_v (Eq. 4) are dependent on pressure. Without this consideration, comparisons between the results from different studies have little meaning.



Figure 4. Structural stiffness of thoracic arotas in normotensive and hypertensive rats (7).

Several studies have been performed to determine the pressure–diameter or pressure–volume relationships of aortas and arteries in hypertensive animals and humans. For example, comparison of hypertensive rats to normotensive controls has shown that at 100 mmHg (13.3 kPa) and also at the working pressure (systolic blood pressure before sacrifice, P_{sys}) of each group, the pressure strain elastic modulus, E_p of the thoracic aorta is greater in hypertensives than in normals; whereas at 200 mmHg (26.6 kPa) the E_p values in the hypertensive animals are slightly lower than those of the normals (Fig. 4) (7). These results do not depend on the duration of hypertension for 2–16 weeks.

With regard to the inherent elastic modulus of wall material calculated from pressure–diameter data, it has been shown that the incremental elastic moduli of the rat thoracic aorta ($H_{\theta\theta}$ in Eq. 7) at systolic blood pressure levels have significant correlations with blood pressure until 8 weeks after the induction of hypertension; at 16 weeks, however, the correlation disappears and the elastic modulus tends to be at the same level as that in control, normotensive rats (Fig. 5) (7). There are no significant differences in the incremental elastic modulus at



Figure 5. Incremental elastic modulus versus blood pressure in the rat aorta at 2, 4, 8, and 16 weeks after the treatment for hypertension (7).

100 mmHg (13.3 kPa) regardless of the period of hypertension. The aortic wall in hypertensive rats seems to restore the *in vivo* elastic properties to a normal level in 16 weeks due to the functional adaptation and remodeling of the wall.

In connection with the elastic properties of wall, many data have shown that the arterial wall is thickened by hypertension and hypertrophy occurs (14). Wall thickness critically depends on pressure level and, therefore, we have to pay attention to the pressure for the thickness measurement when we interpret the results. If the thickness of wall at the *in vivo* blood pressure level is used to calculate *in vivo* wall stress in the circumferential direction (hoop stress), the stress is independent of the degree of hypertension and is always maintained at a control, normal level even at 2 weeks after the induction of hypertension. This phenomenon is attributable to a functional adaptation and remodeling of the arterial wall (15).

Atherosclerosis

Effects of flow dynamics and wall shear stress on the initiation and development of atherosclerosis have been studied extensively. However, less attention has been paid to the mechanical properties of atherosclerotic wall tissue. Does atherosclerosis stiffen the arterial wall or increase the elastic modulus of wall? The results obtained have been conflicting and inconclusive, as shown in Table 1 (7). One of the reasons for this is that the structural stiffness of arterial wall and the elasticity of wall material have been confusingly used for the expression of the elastic properties of atherosclerotic wall. In this table, the elastic modulus represents the elasticity of wall material, which corresponds to the slope of stress–strain curve and is given by, for example, the incremental elastic modulus, $H_{\theta\theta}$; the stiffness is the structural stiffness expressed by, for example, the stiffness parameter, β.

Several studies have shown that the arterial wall is stiffened by the development of atherosclerosis. However, others have presented different results. Thus it has not been clear whether atherosclerosis increases the elastic modulus of arterial wall. We can see from Table 1 that atherosclerosis is mostly accompanied by wall thickening. This might be a reason why there are no data indicating a decrease in the structural stiffness associated with atherosclerosis. The structural stiffness is determined not only by the elastic modulus of wall material, but also by wall dimensions such as wall thickness.

A detailed and systematic study on the mechanical properties and morphology of atherosclerotic aortas in the rabbit has shown that the changes in the wall stiffness (β) and the elastic modulus ($H_{\theta\theta}$) are not always correlated with the time of cholesterol diet feeding (16). Thus, the grade of atherosclerosis was defined from the percent fraction of the luminal surface area stained with Sudan IV as well as from wall stiffening. The area fraction of intimal hyperplasia increases with the grade (Fig. 6). Likewise, wall thickness steadily increases with the progression

Table 1. Distributions of Reported Data of the Elasticity, Stiffness, and Thickness of Atherosclerotic Wall[a]

	No. of Data	Increase, %	No Change, %	Decrease, %
Elastic modulus	17	29	47	24
Stiffness	17	71	29	0
Wall thickness	12	67	25	8

[a] See Ref. 7



Figure 6. Area fraction of intimal hyperplasia in atherosclerotic thoracic aortas in the rabbit (7). Atherosclerosis was induced by the combination of denudation of endothelial cells and cholesterol diet.



Figure 7. Elasticity, wall thickness, and calcification of athorosclerotic thoracic aortas in the rabbit (7).

of atherosclerosis (Fig. 7). However, the elastic modulus is not significantly different from the control artery until the highest grade of atherosclerosis. On the other hand, there appears a significant increase in the arterial stiffness in the grade II atherosclerosis, which is attributable to the wall thickening. Significantly increased calcification and intimal hyperplasia are observed in the wall of the grade III atherosclerosis. From these results, it is concluded that the progression of atherosclerosis induces wall thickening, followed by wall stiffening. However, even if atherosclerosis is advanced, there is essentially no change in the elastic modulus of wall material unless considerable calcification occurs in the wall. Calcified aortas have high elastic moduli. At the most advanced stage of atherosclerosis, the arterial wall has high structural and material stiffness due to calcification and wall hypertrophy (16).

BIBLIOGRAPHY

Cited References

1. Hayashi K, et al. Techniques in the Determination of the Mechanical Properties and Constitutive Laws of Arterial Walls. In: Leondes C, editor. Cardiovascular Techniques – Biomechanical Systems: Techniques and Applications Vol. II. Boca Raton (FL): CRC Press; 2001. p 6-1–6-61.
2. Hayashi K, Mori K, Miyazaki H. Biomechanical response of femoral vein to chronic elevation of blood pressure in rabbits. Am J Physiol 2003;284:H511–H518.
3. Hayashi K, Nakamura T. Implantable miniature ultrasonic sensors for the measurement of blood flow. Automedica 1989;12:53–62.
4. Abe H, Hayashi K, Sato M, editors. Data Book on Mechanical Properties of Living Cells, Tissues, and Organs. Tokyo: Springer-Verlag; 1996. p 25–125.
5. Fung YC. Biomechanics: Mechanical Properties of Living Tissues. New York: Springer-Verlag; 1993. p 242–320.
6. Hayashi K, et al. Stiffness and elastic behavior of human intracranial and extracranial arteries. J Biomech 1980;13: 175–184.
7. Hayashi K. Mechanical Properties of Soft Tissues and Arterial Walls. In: Holzapfel G, Ogden RW, editors. Biomechanics of Soft Tissue in Cardiovascular Systems. (CISM Courses and Lectures No. 441), Wien: Springer-Verlag; 2003. p 15–64.
8. Hudetz AG. Incremental elastic modulus for orthotropic incompressible arteries. J Biomech 1979;12:651–655.
9. Vaishnav RN, Young JT, Patel DJ. Distribution of stresses an strain energy density through the wall thickness in a canine aortic segment. Circ Res 1973;32:577–583.
10. Chuong CJ, Fung YC. Three-dimensional stress distribution in arteries. Trans ASME J Biomech Eng 1983;105:268–274.
11. Takamizawa K, Hayashi K. Strain energy density function and uniform strain hypothesis for arterial mechanics. J Biomech 1987;20:7–17.
12. Hayashi K, Igarashi Y, Takamizawa K. Mechanical properties and hemodynamics in coronary arteries. In: Kitamura K, Abe H, Sagawa K, editors. New Approaches in Cardiac Mechanics. New York: Gordon and Breach; 1986. p 285–294.
13. Hayashi K. Experimental approaches on measuring the mechanical properties and constitutive laws of arterial walls. Trans ASME J Biomech Eng 1993;115:481–488.
14. Humphrey JD. Cardiovascular Solid Mechanics: Cells, Tissues, and Organs. New York: Springer-Verlag; 2002. p 365–386.
15. Matsumoto T, Hayashi K. Response of arterial wall to hypertension and residual stress. In: Hayashi K, Kamiya A, Ono K, editors. Biomechanics: Functional Adaptation and Remodeling. Tokyo: Springer-Verlag; 1996. p 93–119.
16. Hayashi K, Ide K, Matsumoto T. Aortic walls in atherosclerotic rabbits -Mechanical study. Trans ASME J Biomech Eng 1994;116:284–293.

See also BLOOD PRESSURE, AUTOMATIC CONTROL OF; BLOOD RHEOLOGY; CUTANEOUS BLOOD FLOW, DOPPLER MEASUREMENT OF; HEMODYNAMICS; INTRAAORTIC BALLOON PUMP; TONOMETRY, ARTERIAL.

ASSISTIVE DEVICES FOR THE DISABLED. See ENVIRONMENTAL CONTROL.

ATOMIC ABSORPTION SPECTROMETRY. See FLAME ATOMIC EMISSION SPECTROMETRY AND ATOMIC ABSORPTION SPECTROMETRY.

AUDIOMETRY

THOMAS E. BORTON
BETTIE B. BORTON
Auburn University Montgomery
Montgomery, Alabama
JUDITH T. BLUMSACK
Disorders Auburn University
Auburn, Alabama

INTRODUCTION

Audiology is, literally, the science of hearing. In many countries around the world, audiology is a scientific discipline practiced by audiologists. According to the American Academy of Audiology, "an audiologist is a person who, by virtue of academic degree, clinical training, and license to practice and/or professional credential, is uniquely qualified to provide a comprehensive array of professional services related to the prevention of hearing loss and the audiologic identification, assessment, diagnosis, and treatment of persons with impairment of auditory and vestibular function, as well as the prevention of impairments associated with them. Audiologists serve in a number of roles including clinician, therapist, teacher, consultant, researcher and administrator" (1).

An important tool in the practice of audiology is audiometry, which is the measurement of hearing. In general, audiometry entails one or more procedures wherein precisely defined auditory stimuli are presented to the listener in order to elicit a measurable behavioral or physiologic response. Frequently, the term audiometry refers to procedures used in the assessment of an individual's threshold of hearing for sinusoidal (pure tones) or speech stimuli (2). So-called conventional audiometry is conducted with a calibrated piece of electronic instrumentation called an audiometer to deliver controlled auditory signals to a listener. Currently, however, an expanded definition of audiometry also includes procedures for measuring various physiological and behavioral responses to the presentation of auditory stimuli, whether or not the response involves cognition. More sophisticated procedures and equipment are increasingly used to look beyond peripheral auditory structures in order to assess sound processing activity in the neuroauditory system.

Today, audiologists employ audiometric procedures and equipment to assess the function of the auditory system from external ear to brain cortex and serve as consultants to medical practitioners, education systems, the corporate and legal sectors, and government institutions such as the Department of Veterans Affairs. Audiologists also use audiometric procedures to identify and define auditory system function as a basis for nonmedical intervention with newborns, young children with auditory processing disorders, and adults who may require sophisticated amplification systems to develop or maintain their communication abilities and quality of life.

The purpose of this chapter is to acquaint the reader with the basic anatomy of the auditory system, describe some of the instrumentation and procedures currently used for audiometry, and briefly discuss the application of audiometric procedures for the assessment of hearing.

AUDIOMETRY AND ITS ORIGINS

Audiometry refers broadly to qualitative and quantitative measures of auditory function/dysfunction, often with an emphasis on the assessment of hearing loss. It is an important tool in the practice of audiology, a healthcare specialty concerned with the study of hearing, and the functional assessment, diagnosis, and (re)habilitation of hearing impairment. The profession sprang from otology and speech pathology in the 1920s, about the same time that instrumentation for audiometry was being developed. Audiometry grew rapidly in the 1940s when World War II veterans returned home with hearing impairment related to military service (3). Hearing evaluation, the provision of hearing aids, and auditory rehabilitation were pioneered in the Department of Veterans Affairs and, subsequently, universities began programs to educate and train audiologists for service to children and adults in clinics, hospitals, research laboratories and academic settings, and private practice. Audiometry is now a fundamental component of assessing and treating persons with hearing impairment.

Audiometers

Audiometers are electroacoustic instruments designed to meet internationally accepted audiometric performance standards for valid and reliable assessment of hearing sensitivity and auditory processing capability under controlled acoustic conditions. The audiometer was first described around the turn of the twentieth century (4) and was used mainly in laboratory research at the University of Iowa. A laboratory assistant at the university, C. C. Bunch, would later publish a classic textbook describing audiometric test results in patients with a variety of hearing disorders (5). The first commercial audiometer, called the Western Electric 1A, was developed in the early 1920s by the Bell Telephone Laboratories in the United States, and was described by Fowler and Wegel in 1922 (6). More than 20 years elapsed before the use of audiometers for hearing assessment was widely recognized (7), and it was not until the early 1950s (8) that audiometry became an accepted clinical practice. Since that time, electroacoustic instrumentation for audiometry has been described in standards written by scientists and experts designed to introduce uniformity and facilitate the international exchange of data and test results. The American National Standards Institute (ANSI), the International Standards Organization (ISO), and the International Electrotechnical Commission (IEC) are recognized bodies that have developed accepted standards for equipment used in audiometry and in psychophysical measurement, acoustics, and research. In the present day, audiometric procedures are routinely used throughout the world for identifying auditory dysfunction in newborns, assessing hearing disorders associated with ear disease, and monitoring the hearing of patients at risk for damage to the auditory system (e.g., because of exposure to hazardous noise, toxic substances).

Types of Audiometers

In the United States, ANSI (9) classifies audiometers according to several criteria, including the use for which they are designed, how they are operated, the signals they produce, their portability, and other factors.

In general, Type IV screening audiometers (designed to differentiate those with normal hearing sensitivity from those with hearing impairment) are of simpler design than those instruments used for in-depth diagnostic evaluation for medical purposes (Type I audiometers). There are automatic and computer-processor audiometers (Bekesy or self-recording types), extended high-frequency (Type HF), free-field equivalent audiometers (Type E), speech audiometers (Types A, B, and C depending on available features), and others for specific purposes.

Audiometers possess one or more oscillation networks to generate pure tones of differing frequencies, switching networks to interrupt and direct stimuli, and attenuating systems calibrated in decibels (dB) relative to audiometric zero. The intensity range for most attenuation networks usually approximates 100 dB, typically graduated in steps of 5 dB. The “zero dB” level represents normal hearing sensitivity across the test frequency range for young adults under favorable, noise-free laboratory conditions. Collection of these hearing level reference data from different countries began in the 1950s and 1960s. These reference levels have been accepted by internationally recognized standards organizations. Audiometers also include various types of output transducers for presentation of signals to the listener, including earphones, bone-conduction vibrators, and loudspeakers. As the audiometrically generated signals are affected substantially by the electroacoustic characteristics of these devices (e.g., frequency response), versatile audiometers have multiple calibrated output networks to facilitate switching between transducers depending on the clinical application of interest.

Figure 1 shows the general layout of a Type I diagnostic audiometer. Such instruments are required by standards governing them to produce a stable output at a range of



Figure 1. Typical diagnostic audiometer.

operating temperatures and humidity and meet a wide variety of electrical and other safety standards, in addition to precise electroacoustic standards for frequency, intensity, spectral purity, maximum output sound pressure level (SPL), and harmonic distortion. Type II audiometers have fewer required features and less flexibility, and Type IV audiometers have even more limitations.

Audiometric Calibration

To ensure that an audiometer is performing in accordance with the relevant standard, the instrument's electroacoustic characteristics are checked and adjusted as necessary, usually following a routine procedure. These calibration activities may be conducted at the manufacturing facility or an outside laboratory, but are most often accomplished on site at least annually. Calibration of speakers in a sound field is typically conducted on site because the unique acoustic characteristics of a specific field cannot easily be reproduced in a remote calibration facility.

Calibration of audiometers is routinely checked using instruments such as oscilloscopes, multimeters, spectrometers, and sound-level meters to verify frequency, intensity, and temporal characteristics of the equipment. Output transducers such as earphones and bone stimulators can be calibrated in two ways: (*1*) using "real ear" methods, involving individuals or groups of persons free from ear pathology and who meet other criteria, or (*2*) using hard-walled couplers (artificial ears) and pressure transducers specified by the relevant standard.

Audiometric Standards

Electroacoustic instrumentation for audiometry has been described in national and international standards written by scientists and experts designed to introduce uniformity and facilitate the international exchange of data and test results. ANSI, ISO, and IEC are recognized bodies that have developed accepted standards for equipment used in audiometry and acoustics. Some standards relate to equipment, others to audiometric procedures, and still others to the environment and conditions in which audiometry should be conducted (10).

The aim of standards for audiometric equipment and procedures is to assure precision of equipment functions to help ensure that test results can be interpreted meaningfully and reliably within and between clinics and laboratories using different equipment and personnel in various geographical locations. The results of audiometry often help to provide a basis for decisions regarding intervention strategies, such as medical or surgical intervention, referral for cochlear implantation, hearing aid selection and fitting, application of assistive listening devices, or selection of appropriate educational or vocational placement. As in any measurement scheme, audiometric test results can be no more precise than the function of the equipment and the procedures with which those measurements are made.

PURE TONE AUDIOMETRY

Psychophysical Methods

Audiometry may be conducted with a variety of methodologies depending on the goal of the procedure and subject variables such as age, mental status, and motivation. For example, the hearing sensitivity of very young children may be estimated by assessing the effects of auditory stimuli presented in a sound field on startle-type reflexes, level of arousal, and localization. Patients who are developmentally delayed may be taught with reinforcement to push a button upon presentation of a test stimulus. Children of preschool age may be taught to make a motor response to auditory test stimuli using play audiometric techniques.

In conventional audiometry, auditory stimuli are presented through special insert or supra-aural earphones, or a bone oscillator worn by the patient. When indicated, a sound field around the listener may be created by presenting stimuli through strategically placed loudspeakers. Most threshold audiometric tests in school-aged children and adults can be conducted using one of two psychophysical methods originally developed by Gustav Fechner: (*1*) the method of adjustment, or (*2*) the method of limits (11). In the method of adjustment, the intensity of an auditory stimulus is adjusted by the listener according to some criterion (just audible or just inaudible), usually across a range of continuously or discretely adjusted frequencies. Nobel Prize Laureate Georg von Bekesy initially introduced this methodology into the practice of audiometry in 1947 (12). With this approach, listeners heard sinusoidal stimuli that changed from lower to higher test frequencies, and adjusted the intensity of continuous and interrupted tones from "just inaudible" to "just audible". As shown in Fig. 2, this methodology yielded information about the listener's auditory threshold throughout the test frequency range. The relationship of threshold tracings for the pulsed and continuous stimuli added additional information about the site of lesion causing the hearing loss (13,14).

Later, it was found that the tracing patterns tracked by hearing-impaired patients at their most comfortable loudness levels, instead of their threshold levels, yielded additional useful diagnostic information (15). A myriad of



Figure 2. Bekesy audiometric tracing of continuous and interrupted tones around auditory threshold.

factors associated with this psychophysical measurement method, including the age of the listener, learning effects, and the length of time required to obtain stable test results, make these methods unsuitable for routine diagnostic purposes, especially in young children. Nevertheless, audiometers incorporating this methodology are manufactured to precise specifications (9) and are routinely used in hearing conservation programs to record the auditory sensitivity of large numbers of employees working in industrial or military settings.

In most clinical situations today, routine threshold audiometry is conducted using the method of limits. In this approach, the examiner adjusts the intensity of the auditory stimuli of various frequencies according to a predetermined schema, and the listener responds with a gross motor act (such as pushing a button or raising a hand) when the stimulus is detected. Although auditory threshold may be estimated using a variety of procedural variants (ascending, descending, mixed, adaptive), research has established (16) that an ascending approach in which tonal stimuli are presented to the listener from inaudible intensity to a just audible level is a valid and reliable approach for cooperative and motivated listeners, and the technique most parsimonious with clinical time and effort. In this approach, tonal stimuli are presented at intensity levels below the listener's threshold of audibility and raised in increments until a response is obtained. At this point, the intensity is lowered below the response level and increased incrementally until a response is obtained. When the method of limits is used, auditory threshold is typically defined as the lowest intensity level that elicits a reliable response from the patient on approximately 50% or more of these "ascending" trials.

Sound Pathways of the Auditory System

The fundamental anatomy of the ear is depicted in Fig. 3. Sound enters the auditory mechanism by two main routes, air conduction and bone conduction. Most speech and other sounds in the ambient environment enter the ear by air conduction. The outer ear collects and funnels sound waves into the ear canal, provides a small amount of amplification to auditory signals, and conducts sound to the tympanic membrane (eardrum). Acoustic energy strikes the tympanic membrane, where it is converted to mechanical energy in the form of vibrations to be conducted by small bones across the middle ear space to the inner ear. These mechanical vibrations are then converted to hydraulic energy in the fluid-filled inner ear (cochlea). This hydrodynamic form of energy results in traveling waves on cochlear membranous tissues. Small sensory hair cells are triggered by these waves to release neurotransmitters, resulting in the production of neural action potentials that are conducted through the auditory nerve (N. VIII) via central auditory structures in the brainstem to the auditory cortex of the brain, where sound is experienced.



Figure 3. Anatomy of the peripheral auditory mechanism. Adapted from medical illustrations by NIH, Medical Arts & Photography Branch.

Disorders affecting different sections of the ear depicted in Fig. 3 produce different types of hearing impairment. The outer ear, external auditory canal, and ossicles of the middle ear are collectively considered as the conductive system of the ear, and disorders affecting these structures produce a conductive loss of hearing. For example, perforation of the tympanic membrane, presence of fluid (effusion) in the middle ear due to infection, and the disarticulation of one or more bones in the middle ear all produce conductive hearing loss. This type of hearing loss is characterized by attenuation of sounds transmitted to the inner ear, and medical/surgical treatment often fully restores hearing. In a small percentage of cases, the conductive disorder may be permanent, but the use of a hearing aid or other amplification device can deliver an adequate signal to the inner ear that usually permits excellent auditory communication.

The inner ear and auditory nerve comprise the sensorineural mechanism of the ear, and a disorder of this apparatus often results in a permanent sensorineural hearing loss. Sensorineural disorders impair both perceived sound audibility and sound quality typically because of impaired frequency selectivity and other effects. Thus, in sensorineural-type impairments, sounds become difficult to detect, and they are also unclear, leading to poor understanding of speech. In some cases, conductive and sensorineural disorders simultaneously co-exist to produce a mixed-type hearing impairment. Listeners with this disorder experience the effects of conductive and sensorineural deficits in combination.

Finally, the central auditory system begins at the point the auditory nerve enters the brainstem, and comprises the central nerve tracts and nuclear centers from the lower brainstem to the auditory cortex of the brain. Disorders of the central auditory nervous system produce deficits in the ability to adequately process auditory signals transmitted from the outer, middle, and inner ears. The resulting hearing impairment is characterized not by a loss of sensitivity to sound, but rather difficulties in identifying, decoding, and analyzing auditory signals, especially in difficult listening environments with background noise present. Auditory processing disorders require sophisticated test paradigms to identify and diagnose.

The Audiogram

The results of basic audiometry may be displayed in numeric form or on a graph called an audiogram, as shown in Fig. 4. As can be seen, frequency in hertz (Hz) is depicted on the abscissa, and hearing level (HL) in dB is displayed on the ordinate. Although the normal human ear can detect frequencies below 100 Hz and as high as 20,000 Hz, the audible frequency range most important for human communication lies between 125 and 8000 Hz, and the audiogram usually depicts this more restricted range. For special diagnostic purposes, extended high frequency audiometers produce stimuli between 8000 and 20,000 Hz, but specialty audiometers and earphones must be used to obtain thresholds at these frequencies. A few commercially available audiometers produce sound pressure levels as high as 120 dB HL, but such levels are potentially hazardous to the human ear and hearing thresholds poorer than 110 dB do not represent "useful" hearing for purposes of communication.



Figure 4. Graphic audiogram for a normal hearing listener. Bone conduction, right ear = <; Bone conduction, left ear = >; Air conduction, right ear = O; Air conduction, left ear = X.



Figure 5. Graphic audiogram for a listener with conductive hearing loss. Bone conduction, right ear = [; Bone conduction, left ear =]; Air conduction, right ear = O; Air conduction, left ear = X.

The dashed line across the audiogram in Fig. 4 at 25 dB HL represents a common depiction of the boundary between normal hearing levels and the region of hearing loss (below the line) in adults. The recorded findings on this audiogram represent normal test results from an individual with no measurable loss of hearing sensitivity.

Figure 5 displays test results for a listener with a middle ear disorder in both ears and a bilateral conductive loss of hearing, which is moderate in degree, and similar in each ear. Bone conduction responses for the two ears are within normal limits (between 0 and 25 dB HL), suggesting normal sensitivity of the inner ear and auditory nerve, while air conduction thresholds are depressed below normal, suggesting obstruction of the air conduction pathway to the inner ear. Thus, conductive hearing losses are characterized on the audiogram by normal bone conduction responses and depressed air conduction responses. In



Figure 6. Graphic audiogram. Bone conduction, right ear = <; Bone conduction, left ear = >; Air conduction, right ear = O; Air conduction, left ear = X.



Figure 7. Graphic audiogram for a listener with mixed hearing loss. Masked bone conduction, right ear = [; Masked bone conduction, left ear =]; Unmasked bone conduction, right ear = <; Unmaksked bone conduction, left ear = >; Air conduction, right ear = O; Air conduction, left ear = X.

sensorineural-type hearing losses, air conduction and bone conduction responses in each ear are equally depressed on the audiogram. Figure 6 shows a high frequency loss of hearing in both ears, falling in pattern and sensorineural in type. Air and bone conduction hearing sensitivity is similar in both ears, suggesting that the cause of the hearing loss is not in the conductive mechanism (outer and middle ears).

The audiogram shown in Fig. 7 depicts a mixed-type loss of hearing in both ears. The gap between air and bone conduction thresholds in the two ears at the lower frequencies suggests a conductive disorder affecting the outer or middle ears. However, at frequencies above 500 Hz, hearing sensitivity via both air and bone conduction pathways in the two ears is nearly identical, which points to a disorder affecting the inner ear or auditory nerve.

In summary, an audiogram displays the results of basic audiometry in a stylized “shorthand”, so that the hearing impairment can be readily characterized according to type of loss, degree of deficit, configuration (shape) of loss, and the degree of symmetry between the two ears. Such findings constitute the basis for first-order description of a listener’s hearing sensitivity across the audible frequency range and provide important clues about the cause of hearing loss, the effects of the impairment on auditory communication ability, and the prognosis for treatment and rehabilitation.

SPEECH AUDIOMETRY

The first attempts to categorize hearing impairment on the basis of tests using speech stimuli were made in the early 1800s, when sounds were ranked according to their intensity and used to estimate the degree of hearing loss (17). Throughout the 1800s, refinements were introduced in methodologies for using speech stimuli to evaluate hearing. These improvements included the control of word intensities by varying distance between speaker and listener, the introduction of whispered speech to reduce differences in audibility between words, recording speech stimuli on the phonograph devised by Edison in 1877, and standardizing words lists in English and other languages (17). Most of the early research on speech perception focused on the sensitivity of the auditory system to speech, but progress in this area accelerated in the early 1900s because of work at the Bell Telephone Laboratories centered on the discrimination of speech sounds from each other. This emphasis led to the development of modern materials for assessing speech recognition at the Harvard Psychoacoustic Laboratories (18), which have been refined and augmented since that time.

Although pure tone audiometry provides important information about hearing sensitivity, as well as the degree, configuration, and type of hearing loss in each ear, it provides little information about a listener’s auditory communication status and the ability to hear and understand speech in quiet as well as difficult listening situations. Attempts to predict speech recognition ability from the pure tone audiogram, even with normal hearing listeners, have met with only partial success, and the task is particularly complicated when listeners have a hearing impairment.

Instrumentation

Speech audiometry is conducted in the “speech mode” setting of a clinical audiometer. Speech stimuli are presented through the same types of transducers as those used for pure tone audiometry. Live speech stimuli via microphone and monitored with a VU meter can be used for speech audiometry, or recorded speech materials can be presented by CD or tape and routed through the audiometer to either one ear or both ears simultaneously by earphone or loudspeaker. Recorded speech materials typically include a calibration tone, and the input level is adjusted for individual recordings to a specified intensity level. Many different speech audiometric tests have been developed, and most currently in use are available in recorded form. Monitored live-voice presentation enables greater flexibility, but recorded speech materials enhance consistency across test conditions and avoid performance differences related to talker speech and vocal eccentricities.

In general, speech audiometry is conducted with the examiner in one room and the listener in another. With this arrangement, the examiner is able to observe the listener and maintain easy communication through microphones in both rooms, but the speech stimuli can be presented under carefully controlled conditions.

Speech Recognition Threshold

Speech recognition threshold (SRT) testing typically entails presentation of spondees (two-syllable, compound words), spoken with equal stress on each syllable (e.g., baseball, toothbrush, airplane). The use of these words for audiometric purposes has been investigated extensively, especially with respect to similarity in audibility (19).

Audiologists now generally select stimulus words from a list of commonly accepted spondees, and the words are presented at varying intensities using protocols similar to those used for pure tone audiometry. The speech recognition threshold (SRT) is the lowest intensity level at which the patient correctly responds to (repeats, writes down, points to) approximately 50% of the words, with the goal of determining the threshold of hearing for speech. The relationship between thresholds for speech and pure tone was identified in the early part of the twentieth century (20) and later described in detail (21,22). For purposes of clinical speech audiometry, speech recognition thresholds are expected to be within ± 6 dB of the average of the patient's pure tone air conduction thresholds at 500, 1000, and 2000. However, if the pure tone air conduction thresholds slope steeply, the speech recognition threshold is expected to agree with the average of the two best pure tone thresholds in the range of 500–2000 Hz.

The expected agreement between pure tone thresholds and speech recognition thresholds enables audiologists to use the SRT as a cross-check of pure tone air conduction threshold values. Disagreement between SRTs and pure tone threshold averages occurs for a variety of reasons. For example, poor agreement may exist between pure tone thresholds and SRTs in each ear if the patient misunderstands instructions regarding the test procedure for pure tone audiometry, or if the patient attempts to deceive the audiologist regarding actual hearing sensitivity.

SRTs can also be used to estimate/predict pure tone air conduction thresholds in the so-called speech frequency range of 500–2000 Hz in patients who are difficult to test with pure tones. Young children, for example, may reliably repeat or point to pictures of spondees (baseball, toothbrush) while exhibiting inconsistent responses to more abstract pure tones. Speech recognition thresholds have also been used as a basis for predetermining the presentation level for suprathreshold speech stimuli.

Speech Detection Threshold

Whereas the SRT represents the least intensity at which 50% of the speech stimuli presented to the listener can be recognized, the Speech Detection Threshold (SDT), sometimes called the Speech Awareness Threshold (SAT), represents the lowest intensity at which the patient exhibits an awareness of the presence of speech stimuli. If thresholds for spondaic words cannot be established, because of language impairment or other limitations such as young age or inability to speak because of injury, the SDT may represent a useful estimate of the level at which the patient indicates awareness of the presence of speech. In this type of speech threshold testing, the patient is not required to repeat the speech stimulus, which may be just a simple word or nonsense sound, but, instead, the patient simply responds with a hand movement or other gesture to indicate that a sound was detected. The SDT is obtained with protocols similar to those used for speech recognition measurement, and it is expected to be approximately 7–9 dB less intense than the value that would be obtained for the SRT (23,24).

Suprathreshold Speech Audiometry

In suprathreshold speech audiometry, speech stimuli (live-voice or recorded) are presented at levels well above the speech threshold in order to assess the listener's ability to understand speech. Depending on the purpose of the evaluation, the stimuli may be presented in quiet or in the presence of noise (e.g., speech babble, speech-spectrum noise), and the stimuli may be single nonsense syllables, monosyllabic words, nonsense sentences, or sentences. For some purposes, the stimuli are intentionally degraded by filtering or mixing them with noise, and depending on the purpose of suprathreshold evaluation, stimuli may be presented to one ear only (monaurally) or to both ears (binaurally). When stimuli are presented binaurally (both ears simultaneously), they may be identical (diotic) or different (dichotic). Stimuli may be presented at a specified level greater than speech recognition threshold or at varying intensity levels to establish a performance-intensity function. In suprathreshold testing, patient performance is often characterized in terms of percent correct, and standardized norms are used to interpret results.

Purposes for assessment of speech understanding include assessing auditory communication impairment, evaluating effectiveness of a hearing aid fitting, facilitating a comparison between hearing aids, and detecting possible VIIIth nerve or central auditory processing disorder. Suprathreshold stimuli may also be used to determine most comfortable and uncomfortable listening levels for purposes related to hearing aid fitting.

ELECTROPHYSIOLOGIC AUDIOMETRY

Auditory Evoked Potentials—Introduction

The electrophysiological response of the auditory system is often used by audiologists to evaluate auditory function. The techniques are derived from electroencephalography (EEG), which is the measurement of ongoing neural activity and has long been used to monitor brain function. The EEG can be recorded with surface electrodes attached to the scalp and connected to instrumentation that amplifies and records neural activity. Embedded in ongoing EEG activity is the brain's specific response to sensory stimulation. Auditory nervous system responses can be intentionally evoked with an auditory stimulus (such as an acoustic click) presented via an earphone (or other transducer) coupled to the ear. Neural responses that are time-linked to the stimulus can be recorded and differentiated from background EEG activity and other electrical noise sources (e.g., muscle artifact, 60 Hz electrical line noise).

Auditory Evoked Potentials—Clinical Applications

Auditory evoked response recording is an important tool for estimation of auditory sensitivity, particularly when conventional audiometry cannot be used. Evoked auditory potentials are also used routinely to assess the integrity of the auditory system (e.g., in tumor detection, auditory processing assessment, intra-operative monitoring), but the following discussion will focus on threshold estimation/prediction.

Auditory evoked responses are used in place of conventional audiometry primarily in (*1*) infant hearing screening and assessment, (*2*) auditory evaluation of noncooperative children and adults, and (3) threshold estimation for people whose neurological status precludes use of conventional techniques. Although evoked potentials are not true measures of hearing, evoked potentials can be used in conjunction with other tests and information to estimate or predict hearing sensitivity. The capacity to make such estimates has important implications for early identification and rehabilitation of hearing impairment in newborns and young children, provision of auditory rehabilitation to people who have neurological problems, and even evaluation of nonorganic hearing impairment.

Historical Perspective

Early work indicated that ongoing EEG activity can be modified by sensory input (25). In order for a response specific to sensory stimulation to be observed, however, it was necessary to develop techniques to extract the sensory response from the ongoing EEG voltages. One important extraction technique that was developed involved algebraic summation (often called averaging) of responses that are linked in time to the sensory stimulus (26). When a bioelectric potential that is time-locked to a stimulus is recorded repeatedly and added to itself, the amplitude of the observed response will gradually increase with each stimulus repetition. In contrast, as EEG voltages during the same recording period are random, EEG voltages, when repeatedly summed, will gradually diminish or average out. Signal averaging was a critical advancement toward the clinical use of auditory evoked potentials. Other developments followed, and clinical applications of auditory potentials have now been investigated extensively. Measurement and assessment of evoked potentials are currently standard components of audiological practice.

Instrumentation

Many systems for recording auditory evoked potentials are now commercially available and are used widely. Components of the recording equipment typically include a stimulus generator capable of generating a variety of stimuli (e.g., clicks, tone bursts, tones), an attenuator, transducers for stimulus presentation (e.g., insert earphones, standard earphones, bone oscillator), surface electrodes, a differential amplifier, amplifier, filters, analog-to-digital converter, a signal averaging computer, data storage, display monitor, and printer. A simplified schematic diagram of a typical instrument is shown in Fig. 8.

In preparation for a typical single-channel recording, three electrodes are placed on the scalp. The electrodes often are called noninverting, inverting, and ground, but other terminology may be used (e.g., positive/negative or active/passive). A typical electrode montage is shown in Fig. 8, but electrode placements may vary depending on the potentials being recorded and the judgment of the clinician. Unwanted electrical or physiologic noise that may distort or obscure features of the response is reduced by the use of differential amplifiers with high common mode rejection ratios and filters. It is important to note that electrode placement, stimulus polarity, stimulus presentation rate, number of signal presentations, signal repetition rate, filter characteristics, stimulus characteristics, and sampling rate during analog-to-digital conversion all affect the recording, and so must be controlled by the clinician.



Figure 8. Simple block diagram of an auditory evoked response audiometry system.

Classification of Evoked Auditory Potentials

After the onset of an auditory stimulus, neural activity in the form of a sequence of waveforms can be recorded. The amount of time between the onset of the stimulus and the occurrence of a designated peak or trough in the waveform is called the latency. The latency of some auditory evoked potentials can be as short as a few thousandths of a second, and other latencies can be 400 ms or longer. Auditory evoked potentials are often classified on the basis of their latencies. For example, a system of classification can divide the auditory evoked potentials into “early” [< 15 ms (e.g., electrocochleogram and auditory brainstem response)], “middle” [15–80 ms (e.g., Pa, Nb, and Pb)], and “late” [> 80 ms (e.g., P300)] categories. Various classification systems based on latencies have been described, and other forms of classification systems based on the neural sites presumed to be generating the potentials (e.g., brainstem, cortex) are also sometimes used.

It is important to note that recording most bioelectric potentials requires only passive cooperation from the patient, but for some electrical potentials originating in the cortex of the brain, patients must provide active, cognitive participation. In addition, certain potentials are affected by level of consciousness. These factors, combined with the purpose of the evaluation, are important in the selection of the waveforms to be recorded.

Auditory Threshold Estimation/Prediction with AEPs

Auditory threshold estimations/predictions have been made on the basis of early, middle, and late potentials, but the evoked potentials most widely used for this purpose are those recorded within the first 10–15 ms after stimulus onset, particularly the so-called auditory brainstem response (ABR). An ABR evoked by a click consists of 5–7 peaks that normally appear in this time frame (27–29). Typical responses are shown in Fig. 9. The figure depicts three complete ABRs, and each represents the algebraic average of 2048 responses to a train of acoustic transient stimuli. The ABR is said to be time-locked such that each of the prominent peaks occurs in the normal listener at



Figure 9. Normal auditory brainstem response; three complete responses.

predictable time periods after stimulation. Reliability is a hallmark of the ABR, and helps assure the audiologist that a valid estimation of conduction time through auditory brainstem structures has been made. A brief, gated, square-wave signal (click) stimulus is often used to generate the response, and stimulus intensity is reduced until the amplitude of the most robust peak (Wave V) is indistinguishable from the baseline voltage.

The response amplitude and latency (which lengthens as stimulus intensity decreases) are used to estimate behavioral auditory thresholds. In some equipment arrangements, computer software is used to statistically analyze the potentials for threshold determination purposes. ABR thresholds obtained with click stimuli correlate highly with behavioral thresholds at 2000–4000 Hz when hearing sensitivity ranges from normal to the severe range hearing impairment. Click stimuli are commonly used in clinical situations because their transient characteristics can excite many neurons synchronously, and thus a large amplitude response is evoked. However, variability limits the usefulness of click-evoked thresholds for prediction/estimation of auditory sensitivity of any particular patient (30), and the frequency specificity desired for audiometric purposes may not be obtained. As a result, gated tone bursts of differing frequencies are often used to estimate hearing sensitivity across the frequency range. These tonal stimuli can be embedded in bursts of noise to sharpen the frequency sensitivity and specificity of the test procedure.

In recent years, another evoked potential technique similar to the ABR has been developed to improve frequency specificity in threshold estimation while maintaining good neural synchronization. This technique, the auditory steady-state response (ASSR), uses rapidly (amplitude or frequency) modulated pure tone carrier stimuli (see Fig. 10). Evidence suggests that the ASSR is particularly useful when hearing sensitivity is severely impaired because high intensity stimuli can be used (31). Research on the ASSR is ongoing, and this technique currently is considered to be a complement to click and tonal ABR in threshold estimation/prediction.



Figure 10. Auditory steady-state response.

ACOUSTIC IMMITTANCE MEASUREMENT

Introduction

One procedure that helps audiologists interpret the results of conventional audiometry and other audiological tests is a measure of the ease with which energy can flow through the ear. Heaviside (1850–1925) coined the term impedance, as applied to electrical circuitry, and these principles were later applied in the United States during 1920s to acoustical systems (32). Mechanical impedance-measuring devices were initially designed for laboratory use, but electroacoustic measuring instruments were introduced for clinical use in the late 1950s (33). As acoustic impedance is difficult and expensive to measure accurately, measuring instruments using units of acoustic admittance are now widely used. The term used to describe measures incorporating the principles of both acoustic impedance and its reciprocal (acoustic admittance) is acoustic immittance. Modern instrumentation permits an estimate of ear canal and middle ear acoustic immittance (including resistive and reactive components).

Instrumentation

Commonly available immittance measuring devices (see Fig. 11) employ a probe-tone delivered to the tympanic membrane through the external ear canal. Sinusoids of differing frequencies are presented through a tube encased in a soft probe fitted snugly in the ear canal. The probe also contains a microphone and tubing connected to an air pump so that air pressure in the external ear canal can be varied from -400 to $+400$ mmH_2O.

Immittance devices also typically have a signal generator and transducers that can be used to deliver high intensity tones at various frequencies for the purpose of acoustic reflex testing. The American National Standards Institute (ANSI) has published a standard (S3.39-1987) for immittance instruments (34).

Immittance Measurement Procedures

As mentioned earlier in this chapter, the middle ear transduces acoustic energy into mechanical form. The transfer function of the middle ear can be estimated by measuring acoustic immittance at the plane of the tympanic membrane. These measures are often considered (in conjunction with the results of other audiological tests) in determining the site of lesion of an auditory disorder.

Static Acoustic Immittance

The acoustic immittance of the middle ear system is usually estimated by subtracting the acoustic immittance of the ear canal. This value is termed the compensated static acoustic immittance and is measured in acoustic mhos (reciprocal of acoustic ohms). The peak compensated



Figure 11. Block diagram of an acoustic immittance measuring device.

static acoustic immittance is obtained by adjusting the air pressure in the external ear canal so that a peak in the tympanogram exists. The magnitude of this peak, relative to the uncompensated immittance value, is clinically useful, because it can be compared with norms (e.g., 0.3 to 1.6 mmho) to determine the presence of middle ear pathology. It is important to note that at ear canal pressures of + 200 daPa or more, the sound pressure level (SPL) in the ear canal is directly related to the volume of air in the external ear canal, because the contribution of the middle ear system is insignificant at that pressure. A measure of the external ear canal volume is a valuable measure that can be used to detect tympanic membrane perforations otherwise difficult to detect visually. That is, a large ear canal volume (i.e., a value considerably greater than 1.5 mL) indicates a measurement of both the external ear canal and the middle ear as a result of a perforation in the tympanic membrane.

Dynamic Acoustic Immittance (Tympanometry)

The sound pressure of the probe-tone directed at the eardrum is maintained at a constant level and the volume velocity is measured by the instrumentation while positive and negative air pressure changes are induced in the external ear canal.

The procedure is called tympanometry and the resulting changes in immittance are recorded graphically as a tympanogram. A typical tracing is seen in Fig. 12.

Admittance is at its maximum when the pressures on both sides of the tympanic membrane are equal. Sound transmission decreases when pressure in the ear canal is greater or less than the pressure at which maximum admittance occurs. As a result, in a normal ear, the shape of the tympanogram has a characteristic peaked shape (see Fig. 13) with the peak of admittance occurring at an air pressure of 0 decapascals (daPa).

Tympanograms are sometimes classified according to shape (Fig. 13) (35).

The Type A tympanogram shown in Fig. 13, so-called because of it's resemblance to the letter "A", is seen in normal ears. When middle ear effusion is present, the fluid contributes to a decrease in admittance, regardless of the changes of pressure in the external ear canal. As a result, a characteristically flat or slightly rounded Type B tympanogram is typical. When the Eustachian tube malfunctions, the pressure in the middle ear can become negative relative to the air pressure in the external auditory canal. As energy flow through the ear is maximal when the pressure differential across the tympanic membrane is zero, tympanometry reveals maximum admittance when the pressure being



Figure 12. Tympanogram of a normal ear.



Figure 13. Tympanogram types (see text for descriptions).

varied in the external ear canal matches the negative pressure in the middle ear. At that pressure, the peak admittance will be normal but will occur at an abnormal negative pressure value. This tympanogram type is termed a Type C. It is important to note that variations exist of the type A tympanogram associated with specific pathophysiology affecting the middle ear. For example, if the middle ear is unusually stiffened by ear disease, the height of the peak may be reduced (Type A_s). Similarly, if middle ear pathology such as a break in the ossicular chain occurs, the energy flow may be enhanced, which is reflected in the Type A_d tympanogram depicted in Fig. 13.

Multifrequency Tympanometry

Under certain circumstances, particularly during middle ear testing of newborns and in certain stages of effusion in the middle ear, responses to the 226 Hz probe-tone typically used in tympanometry may fail to reveal immittance changes caused by disorders of the middle ear. In these circumstances, tympanometry with probe-tone frequencies above 226 Hz may be very useful in the detection of middle ear dysfunction. With probe-tone frequencies above 226 Hz, tympanometric shapes are more complex. More specifically, multifrequency tympanometric tracings normally progress through an expected sequence of shapes as probe frequency increases (36), and deviations from the expected progression are associated with certain pathologies.

Acoustic Reflex Measurement

In humans, a sufficiently intense sound causes a reflexive contraction of the middle ear muscles in both ears, acoustically stiffening the middle ear systems in each ear, called the acoustic reflex and is a useful tool in the audiometric test battery. When the reflex occurs, energy flow through both middle ears is reduced, and the resulting change in immittance can be detected in the probe ear by an immittance measuring device. Intense tones can be introduced to the probe ear (ipsilateral stimulation) or by earphone to the ear opposite the probe ear (contralateral stimulation).

One acoustic reflex measure is the minimum sound intensity necessary to elicit the reflex. The minimum sound pressure level necessary to elicit the reflex is called the acoustic reflex threshold. Acoustic reflex thresholds that are from 70 to 100 dBHL are generally considered to be in the normal range when pure tone stimuli are used. In general, the acoustic reflex thresholds in response to broadband noise stimuli tend to be lower than those for pure tones. Reduced or elevated thresholds, as well as unusual acoustic reflex patterns, are used by audiologists to localize the site of lesion and as one method of predicting auditory sensitivity.

OTOACOUSTIC EMISSIONS

When sound is introduced to the ear, the ear not only is stimulated by sound, it can also generate sounds that can be detected in the ear canal. The generated sounds, so-called otoacoustic emissions, have become the basis for the development of another tool that audiologists can use to assess the auditory system. In the following section, otoacoustic emissions will be described, and their relationship to conventional audiometry will be discussed.

Otoacoustic Emissions—Historical Perspective

Until relatively recently, the cochlea was viewed as a structure that converted mechanical energy from the middle ear into neural impulses that could be transmitted to and used by the auditory nervous system. This conceptual role of the cochlea was supported by the work on human cadavers of Georg von Bekesy during the early and middle 1900s, and summarized in 1960 (37). In Nobel Prize-winning research, von Bekesy developed theories to account for the auditory system's remarkable frequency sensitivity, and his views were widely accepted. However, a different view of the cochlea was proposed by one of von Bekesy's contemporaries, Thomas Gold, who suggested that processing in the cochlea includes an active process, a mechanical resonator (38). This view, although useful in explaining cochlear frequency selectivity, was not widely embraced at the time it was proposed.

In later years, evidence in support of Gold's idea of active processing in the cochlea accumulated. Particularly significant were direct observations of outer hair cell motility (39). In addition, observed differences in inner hair cell and outer hair cell innervation such as direct efferent innervation of outer but not inner hair cells (40) suggested functional differences in the two cell types. Most relevant to the present discussion were reports of the sounds that were recorded in the ear canal (41) and attributed to a mechanical process occurring in the cochlea, which are now known as otoacoustic emissions.

Otoacoustic Emissions—Description

Initially, otoacoustic emissions (OAEs) were thought to originate from a single mechanism, and emissions were classified on the basis of the stimulus conditions under which they were observed. For example, spontaneous otoacoustic emissions (SOAEs) are sounds that occur spontaneously without stimulation of the hearing mechanism. Two categories of otoacoustic emissions that are most widely used clinically by audiologists are (*1*) transient otoacoustic emissions (TOAEs), which are elicited by a brief stimulus such as an acoustic click or a tone burst, and (*2*) distortion product otoacoustic emissions (DPOAEs), which are elicited by two tones (called primaries) that are similar, but not identical, in frequency. A third category of otoacoustic emissions that may prove helpful to audiologists in the future is the stimulus frequency otoacoustic emission (SFOAE), which is elicited with a pure tone. Currently, SFOAEs are used by researchers studying cochlear function, but they are not used widely in clinical settings.

Recent research indicates that, contrary to initial thinking, otoacoustic emissions are generated by at least two mechanisms, and a separate classification system has been proposed to reflect improved understanding of the physical basis of the emissions. Specifically, it is believed that the mechanisms that give rise to evoked otoacoustic emissions include (*1*) a nonlinear distortion source mechanism and (*2*) a reflection source that involves energy reflected from irregularities within the cochlea such as variations in the number of outer hair cell motor proteins or spatial variations in the number and geometry of hair cell distribution (42). Emissions currently recorded in the ear canal for clinical purposes are thought to be mixtures of sounds generated by these two mechanisms.

Instrumentation

Improved understanding of the mechanisms that generate otoacoustic emissions may lead to new instrumentation that can "unmix" evoked emissions. Currently, commercially available clinical equipment records "mixed" emissions and includes a probe placed in the external ear canal that both delivers stimuli (i.e., pairs of primary tonal stimuli across a broad range of frequencies, clicks or tone-bursts) and records resulting acoustic signals in the ear canal. The microphone in the probe equipment is used in (*1*) the verification of probe fit, (*2*) monitoring probe status (e.g., for cerumen occlusion), (*3*) measuring noise levels, (*4*) verifying stimulus characteristics, and (*5*) detecting emissions. Otoacoustic measurement recording entails use of probe tips of various sizes to seal the probe in the external ear canal and hardware/software that control stimulus parameters and protocols for stimulus presentation. The computer equipment performs averaging of responses time-locked to stimulus presentation, noise measurement, artifact rejection, data storage, and so on, and can provide stored normative data and generate printable reports. An example of a typical DPOAE data display is shown in Fig. 14.

It is important to note that outer or middle ear pathology can interfere with transmission of emissions from the cochlea to the ear canal, and thus the external ear canal and middle ear status are important factors in data interpretation. Also, although otoacoustic emissions ordinarily are not difficult to record and interpret, uncooperative patient behavior and high noise levels can hamper or even preclude measurement of accurate responses.



Figure 14. DPAOE responses from 1000 to 6,000 Hz from the left ear of a normal listener. X = DPOAE response amplitudes; squares = physiologic noise floor; bold curves = 95% confidence limits for normal ears.

Otoacoustic Emissions—Clinical Applications

Measurement of otoacoustic emissions is used routinely as a test battery component of audiometric evaluations in children and adults, and it is particularly useful for monitoring cochlear function (e.g., in cases of noise exposure and during exposure to ototoxic medication) as well as differentiating cochlear from neural pathology. Currently, otoacoustic emission evaluation is also useful, either alone or in combination with evoked potential recording, in newborn hearing screening. In addition, OAE assessment is sometimes used in preschool and school-age hearing screening, as well as with patients who may be unwilling to cooperate during audiometry.

Otoacoustic Emissions and Audiometric Threshold Prediction/Estimation

Audiologists do not use otoacoustic emissions as a measure of "hearing" because OAEs constitute an index of cell activity in the inner ear, not "hearing." Research suggests, however, that otoacoustic emissions may become an important indicator for predicting/estimating auditory thresholds when conventional audiometry cannot be conducted (42).

Many sources of variability exist that affect DPOAE use in audiometric threshold prediction/estimation, including variability with respect to etiology of the hearing loss, age, gender, and uncertainty regarding locations of DPOAE generation and their relationship to audiometric test frequencies. Individual DPOAE amplitude variation, intra- and inter-subject variations occurring at different frequencies and at different stimulus levels, and the mixing of emissions from at least two different regions of the cochlea (as described above) can reduce frequency selectivity and specificity in DPOAE measurement.

It has been suggested that developing methods to "unmix" the emissions associated with different generators (e.g., through the use of suppressor tones to reduce or eliminate one source component or with the use of Fourier analysis to analyze the emissions) may reduce variability and improve specificity in threshold prediction/estimation and determination of etiology (41). It is likely that future commercial otoacoustic measurement instruments will enable the user to differentiate distortion source emissions from reflection source emissions and that this improvement will lead to more widespread use of otoacoustic emissions in audiometric threshold estimation and prediction.

BIBLIOGRAPHY

1. American Academy of Audiology. Scope of practice. Audiol Today 2004;15(3):44–45.
2. American National Standards Institute. Methods of manual pure tone threshold audiometry. (ANSI S3.21-2004). New York: ANSI; 2004.
3. Bergman M. On the origins of audiology: American wartime military audiology. Audiol Today Monogr 2002;1:1–28.

4. Seashore CE. An Audiometer. University of Iowa Studies in Psychology (No. 2). Iowa City, NA: University of Iowa Press; 1899.
5. Bunch CC. Clinical Audiometry. St. Louis, MO: C. V. Mosby; 1943.
6. Fowler EP, Wegel RL. Presentation of a new instrument for determining the amount and character of auditory sensation. Trans Am Otol Soc 1922;16:105–123.
7. Bunch CC. The development of the audiometer. Laryngoscope 1941;51:1100–1118.
8. Carhart R. Clinical application of bone conduction audiometry. Archi Otolaryngol 1950;51:798–808.
9. American National Standards Institute. Specification of audiometers. (ANSI-S3.6-1996). New York: ANSI; 1996.
10. American National Standards Institute. Maximum permissible ambient noise levels for audiometric test rooms. (ANSI-S3.1-1999 [R2003]). New York: ANSI; 1999.
11. Breakwell GM, Hammond S, Fife-Shaw C. Research Methods in Psychology. 2nd ed. London: Sage; 2000. p 200–205.
12. von Bekesy G. A new audiometer. Acta Oto-laryngologica Stockholm 1947;35:411–422.
13. Jerger J. Bekesy audiometry in analysis of auditory disorders. J Speech Hear Res 1960;3:275–287.
14. Jerger J, Herer G. Unexpected dividend in Bekesy audiometry. J Speech Hear Disord 1961;26:390–391.
15. Jerger S, Jerger J. Diagnostic value of Bekesy comfort loudness tracings. Arch Otolaryngol 1974;99:351–360.
16. Carhart R, Jerger J. Preferred method for clinical determination of pure-tone thresholds. J Speech Hear Disord 1959;24: 330–345.
17. Feldmann H. A history of audiology: A comprehensive report and bibliography from the earliest beginnings to the present. Translations Beltone Institute Hear Res 1960;22:1–111. [Translated by Tonndorf J. from Die Geschichtliche Entwicklung der Horprufungsmethoden, Kuze Darstellung and Bibliographie von der Anfrongen bis zur Gegenwart. In: Leifher H, Mittermaiser R, Theissing G, editors. Zwanglose Abhandunger aus dem Gebeit der Hals-Nasen-Ohren-Heilkunde. Stuttgart: Georg Thieme Verlag; 1960.]
18. Hudgins CV, Hawkins, JE Jr, Karlin JE, Stevens SS. The development of recorded auditory tests for measuring hearing loss for speech. Laryngoscope 1947;57:57–89.
19. Olsen WO, Matkin ND. Speech audiometry. In: Rintelmann WF, editor. Hearing Assessment. 2nd ed. Austin, TX: Pro-Ed; 1991. 39–140.
20. Fletcher H. Speech and Hearing. Princeton NJ: Von Nostrand; 1929.
21. Fletcher H. A method of calculating hearing loss for speech from an audiogram. Acta Otolaryngologica 1950; (Suppl 90): 26–37.
22. Carhart R. Observations on the relations between thresholds for pure tones and for speech. J Speech Hear Disord 1971; 36:476–483.
23. Beattie RC, Edgerton BJ, Svihovec DV. An investigation of Auditec of St. Louis recordings of Central Institute for the Deaf spondees. J the Am Audiol Soc 1975;1:97–101.
24. Cambron NK, Wilson RH, Shanks JE. Sondaic word detection and recognition functions for female and male speakers. Ear Hear 1991;12:64–70.
25. Loomis A, Harvey E, Hobart G. Disturbances of patterns in sleep. J Neurophysiol 1938;1:413–430.
26. Clark WA Jr, Goldstein MH Jr, Brown RM, Molnar CE, O'Brien DF, Zieman HE. The average response computer (ARC): A digital device for computing agerages and amplitudes and time histograms of physiological responses. Trans of IRE 1961;8:46–51.
27. Jewett DL, Romano MN, Williston JS. Human auditory evoked potentials: Possible brainstem components detected on the scalp. Science 1970;167:1517–1518.
28. Jewett DL, Williston JS. Auditory evoked far fields averaged from the scalp of humans. Brain 1971;94:681–696.
29. Stapells DR, Oates P. Estimation of the pure-tone audiogram by the auditory brainstem response: A review. Audiol Neurootol 1997;3(5):257–280.
30. Rance G, Briggs RJS. Assessment of hearing in infants with moderate to profound impairment: The Melbourne experience with auditory stead-state evoked potential testing. Ann Otol Rhinol Laryngol 2002;111(5) (Part 2, Suppl. 189):22–28.
31. Swanepoel D, Roode R. Auditory steady-state responses for children with severe to profound hearing loss. Arch of Otolaryngol Head Neck Surg 2004;130(5):531–535.
32. Margolis RH, Hunter LH. Acoustic Immittance Measurements. In: Roeser RJ, Valente M, Hosford-Dunn H, editors. Audiology Diagnosis. New York: Thieme; 2002. pp 381–423.
33. Terkildsen K, Nielsen S. An electroacoustic impedance measuring bridge for clinical use. Arch Otolaryngol 1960;72:339–346.
34. American National Standards Institute. National Standard Specifications for instruments to measure aural acoustic impedance and admittance. (ANSI S3.39-1987). New York: ANSI; 1987.
35. Jerger J. Clinical experience with impedance audiometry. Arch Otolaryngol 1970;92:311–324.
36. Vanhuyse VJ, Creten WL, Van Camp KJ. On the W-notching of tympanograms. Scand Audiol 1975;4:45–50.
37. von Bekesy G. Experiments in Hearing. New York: McGraw Hill; 1960.
38. Gold T. Hearing. II. The physical basis of the acton of the cochlea. Proc Roy Soc Brit 1948;135:492–498.
39. Brownell WE, Bader CR, Bertrand D, Ribaupierre Y. Evoked mechanical responses of isolated cochlear outer hair cells. Science 1985;227:194–196.
40. Smith CA. Innervation pattern of the cochlea. Ann Otol Rhinol Otolaryngol 1961;70:504–527.
41. Kemp DT. Stimulated acoustic emissions from within the human auditory system. J Acoust Soc Am 1978;64:1386–1391.
42. Shera CA. Mechanisms of mammalian otoacoustic emission and their implications for the clinical utility of otoacoustic emissions. Ear Hear 2004;25:86–97.

See also COCHLEAR PROSTHESES; COMMUNICATION DEVICES.

AUDITORY IMPLANTS.

See COCHLEAR PROSTHESES.

AUGMENTATIVE COMMUNICATION SYSTEM.

See COMMUNICATION DEVICES.

B

BACTERIAL DETECTION SYSTEMS. See Microbial detection systems.

BALLOON PUMP. See Intraaortic balloon pump.

BANKED BLOOD. See Blood collection and processing.

BAROTRAUMA. See Hyperbaric medicine.

BARRIER CONTRACEPTIVE DEVICES. See Contraceptive devices.

BIOCERAMICS. See Biomaterials: bioceramics.

BIOCOMPATIBILITY OF MATERIALS

Zhou Xiang
Myron Spector
Brigham and Women's Hospital
Boston, Massachusetts

INTRODUCTION

Most surgical specialties have been revolutionized by the introduction of implantable devices. These advances have been founded, in large part, on biomaterials science and engineering. One of the critical determinants of the performance of the device relates to its compatibility with the structure and function of the tissue or organ (a structure comprised of two or more tissues) in which it is implanted. Moreover, the tissue response to the implant should not impede the required function of the device. This article will deal with the response to biomaterials implanted into solid tissues. Biocompatibility issues related to blood-contacting applications will be outside the scope of this discussion.

Implantation of the device requires the production of a surgical wound, and in this respect the tissue response to the implant may be looked upon as the modification of the wound healing response by the very presence of the implant. In vascularized tissues, the creation of a surgical wound elicits an inflammatory process that can be considered part of the natural course of healing. The end result of the healing process is tissue similar to that naturally occurring at the site (the process of "regeneration") or scar tissue (the process of "repair"), which in many tissues and organs comprises fibrous tissue. Infectious organisms (viz., bacteria) when present serve as a persistent injurious agent that prolongs and can further incite the inflammatory process, not only jeopardizing the performance of the implant, but threatening the life of the individual. The principles of biocompatibility including the mechanisms underlying inflammatory and infectious processes apply regardless of the type of material of fabrication of the implant. There are, however, features of the biomaterials that can affect certain aspects of these processes. It can therefore be instructive to also consider issues of biocompatibility in the context of the various classes of materials: metals, ceramics, and polymers.

CLASSES OF MATERIALS

The term "biomaterials" generally refers to synthetic materials and treated natural materials that are employed for the fabrication of implantable devices that are to replace or augment tissue or organ function. An understanding of the chemical makeup of biomaterials can provide insights into their biocompatibility for selected applications. Generally, biomaterials may be considered "inert" or "reactive" with the biological milieu. In the latter case, the reactivity could relate to the release of moieties or the adsorption of biological molecules. Inert materials may also release small amounts of ions and molecules or nonspecifically bind biomolecules. The feature that distinguishes inert from reactive biomaterials is the degree to which the interactions of the implant with the biological environment affects the tissue response and device performance. Those materials designed to effect specific tissue responses through their reactivity may also be referred to as "bioactive".

This article provides a brief description of materials used for the fabrication of implantable devices relative to issues related to biocompatibility. A more comprehensive discussion of biomaterials can be found elsewhere in this encyclopedia.

Metals

In metals, closely packed arrays of positively charged atoms are held together in a loosely associated "cloud" of free electrons. The essential features of the metallic bond are that it is nondirectional and the electrons are freely mobile. The metals most often used for the fabrication of implantable devices are stainless steel, cobalt–chromium alloys, and titanium and titanium alloy. The specific members of these families used as biomaterials are usually identified by a designation provided by the American Society for Testing and Materials (ASTM). Metallic materials have certain properties that make them ideal for load-bearing applications; in particular, they can maintain very high strength under the aggressive aqueous environment in the body.

The biocompatibility of the implantable metallic materials is related to their corrosion resistance, in that they can generally be considered as inert. While they release detectable levels of metal ions (1,2), these ions have not yet been found to significantly affect tissue or organ function or cause pathological changes. One conundrum related to biomaterials is that while the ions released from certain metallic devices are known to be carcinogenic when administered to certain animals models (3,4) and when encountered by humans in certain circumstances (1), there have not yet been definitive studies relating the incidence of various cancers to the ions released by metallic implants (see later section).

The following sections provide a brief description of three metal systems most frequently used for the fabrication of implantable devices.

Stainless Steels. The stainless steels, like all steels, are iron-based alloys. Chromium is added to improve the corrosion resistance through the formation of a chromium-oxide surface layer; at least 17% chromium is required for the term "stainless" to be used. Carbon and nickel are employed as alloying elements to increase strength. The most common type of stainless steel used for implants is 316L (American Iron and Steel Institute designation; ASTM F-138), containing 17–19% chromium, 13–15.5% nickel, and <0.03% carbon. Despite their very good corrosion resistance, stainless steels are subject to several types of corrosion processes, including crevice, pitting, intergranular, and stress corrosion. These processes can profoundly degrade the mechanical strength of the alloy and can lead to the elevated release of metallic ions into the surrounding tissue with undesirable biological consequences.

Alloying with chromium generates a protective, self-regenerating oxide film that resists perforation, has a high degree of electrical resistivity, and, thus, provides a major protection against corrosion; formation of the chromium oxide "passivation" layer is facilitated by immersion of the alloy in a strong nitric acid solution. The nickel imparts more corrosion resistance and ease of fabrication. The molybdenum addition provides resistance to pitting corrosion. Other alloying elements facilitate manufacturing processes.

Cobalt–Chromium Alloys. Surgical cobalt–chromium alloy is a cobalt-based system with chromium added for increased corrosion resistance. Its composition contains 27–30% chromium and 5–7% molybdenum. Tungsten is added to the wrought alloy to enhance ductility. As with stainless steels, the chromium content of this alloy generates a highly resistive passive film that contributes substantially to corrosion resistance. The Co–Cr Mo (F-75) alloy has superior corrosion resistance to the F-138 stainless steel, particularly in crevice corrosion. There is an extensive, decades-long history of biocompatibility in human implantation. The Co–Cr Mo devices are currently produced by a process referred to as hot isostatic pressing that results in parts with more favorable strength characteristics than results from casting processes. The Co–Cr Tn–Ni Alloy (ASTM F90) is very different from the F-75 alloy with which it is often confused. Parts can be fabricated from this alloy by hot forging and cold drawing; it is not used in the cast form. In clinical practice, F90 is used to make wire and internal fixation devices (e.g., plates, intramedullary rods, and screws).

Unalloyed Titanium (ASTM F-67) and Titanium Alloy (ASTM F-136). Titanium and its alloy with 6% aluminum and 4% vanadium, Ti-6A1-4V, are used for their excellent corrosion resistance and their modulus of elasticity that is approximately one-half that of stainless steel and cobalt–chromium alloys. This lower modulus results in devices with lower stiffness that may be advantageous in certain applications such as implants in bone as they will result in less stress-shielding of bone. The alloy of titanium has much better material properties than the pure titanium. Problems with titanium are its severe notch sensitivity and poor wear resistance.

Titanium and its alloys are of particular interest for biomedical applications due to their outstanding biocompatibility. In general, their corrosion resistance significantly exceeds that of the stainless steels and the cobalt–chromium alloys. In saline solutions near neutral pH, the corrosion rate is extremely small, and there is no evidence of pitting, intergranular, or crevice corrosion. Unalloyed titanium is used less frequently than the alloy for the fabrication of implants. It is, however, available in various configurations, such as plain wire for manufacturing purposes. In addition, it is used to produce porous coatings for certain designs of total joint replacement prostheses.

ASTM F-136 specifies a titanium alloy with a content of 5.5–6.5% Al, 3.5–4.5% V, 0.25% Fe (maximum), 0.05% N (maximum) and 0.08% C (maximum), 0.0125% H (maximum), and other 0.1% (maximum 0.4% total). Developed by the aircraft industry as one of a number of high strength titanium alloys, this particular formulation has a yield strength reaching 1110 MPa. The ASTM F-136 specification limits the oxygen to an especially low level of 0.13% maximum. This is also known in the industry as the ELI (extra low interstitial) grade. Limiting the level of oxygen improves the mechanical properties of the material, particularly increasing its fatigue life. One interesting feature of titanium and its alloys is the low modulus of elasticity of 100 GPa as compared to 200 GPa for the cobalt–chromium alloys. This feature leads to their use in plates for internal fixation of fractures. Some have found that the lower stiffness of these plates may decrease the severity of bone stress-shielding that results in osteopenia under these devices.

One of the weaknesses of titanium is its poor wear resistance. It appears that this problem relates to the mechanical stability of the passive film covering the surface of the alloy. On a carefully polished surface, the film is highly passive but mechanically weak. The poor wear resistance of titanium can result in the release of particulate wear debris if the material is not judiciously employed in the fabrication of implants (5). While the metal in bulk form may be biocompatible adverse cell and tissue responses may be elicited by titanium particles (5–8).

Permanent and Absorbable Synthetic and Natural Polymers

Polymers consist of long chains of covalently bonded molecules characterized by the repeated appearance of a monomeric molecular unit. They can be produced de novo by the polymerization of synthetic monomers or prepared from natural polymers isolated from tissues. Most synthetic and natural polymers have a carbon backbone. Bonding among polymer chains results from much weaker secondary forces—hydrogen bonds or van der Waal's forces. Covalent bonding among chains, referred to as cross-linking, can be produced in certain polymer systems. Physical entanglements of the long polymer chains, the degree of crystallinity, and chemical cross-linking among chains play important roles in determining polymer properties. The molecular bonding of the backbone of the polymer can be designed to undergo hydrolysis or enzymatic breakdown thus allowing for the synthesis of absorbable, as well as permanent, devices.

Polymeric materials are generally employed for the fabrication of implants for soft tissue applications that require a greater degree of compliance than can be achieved with metals. However, they have also been shown to be of value as implants in bone for indications that would also benefit from their lower modulus of elasticity, and the ability of some to be polymerized *in vivo* so as to adapt to defects of complex shape. For some indications, the radiolucency of polymeric materials may be an important benefit. Because of the limited strength and wear resistance of polymers, care must be given to the load-bearing requirements of the applications in which they are used.

The following sections provide a summary of a few of the most frequently used polymers.

Polymethyl Methacrylate (PMMA). Polymethyl methacrylate (9) is used in a self-curing form as a filling material for defects in bone and as a grouting agent for joint replacement prostheses. It can be shaped *in vivo* while in a dough stage prior to complete polymerization and thus makes a custom implant for each use. Its purpose is the redistribution of stress in a more even pattern to the surrounding bone. Often referred to as “bone cement”, when PMMA is employed for joint arthroplasty it acts as a grout to support the prosthesis rather than a glue; it has minimal adhesive properties. The time-dependent properties of PMMA during curing require an understanding of its handling characteristics. Immediately after mixing, the low viscosity permits interdigitation with cancellous bone. Viscosity rises quickly once the chemical setting reaction begins requiring that the prosthesis be accurately positioned and stationary to achieve maximum fixation.

The chemical toxicity of the methyl methacrylate monomer and the heat generated during the polymerization exothermic reaction need be considered when using PMMA. While the toxicity of the monomer has not prevented the material from being employed successfully for a wide array of applications, there are efforts to reduce the monomer content (10) and to employ alternative activating agents that would be less toxic (11).

Its brittle nature after curing and low fatigue strength make PMMA vulnerable to fracture under high mechanical loading and production of wear debris in situations when other harder materials rub against it. The cellular response to PMMA particles can promote an inflammatory response (12,13) that can result in osteolysis. This process has been referred to as “cement disease” (14). This underscores the importance of reducing the circumstances that can result in the production of PMMA debris.

Silicone. Silicones (15) are polymers having a backbone comprising alternating silicon and oxygen atoms with organic side groups bonded to the silicon through covalent bonding with the carbon atom. One form of silicone commonly used for the fabrication of implants is polydimethylsiloxane (PDMS). In PDMS, methyl (CH_3) side groups are covalently bonded to the silicon atom and it can be used in three forms: (a) a fluid comprising linear polymers of varying molecular weight (i.e., chain length); (b) a cross-linked network referred to as a gel; and (c) a solid elastomer comprising a highly cross-linked gel filled with small particles of silica. In considering the performance of silicone implants, the role of each form of PDMS in the device need be considered. Attributing specific biological responses to individual components of a silicone device is complicated by the many molecular forms of silicone that the implant comprises.

The PDMS elastomers contain a noncystalline silica particles 7–22 nm in diameter that has been surface-treated to facilitate chemical bonding of the particle to the PDMS gel. Addition of the silica particle to a highly cross-linked PDMS gel is done to modify the mechanical properties of the elastomer. One of the challenges in investigating tissue responses that may have been elicited by the release of the silica particles is their small size that requires transmission electron microscopy (TEM) for analysis.

Polyethylene. Ultrahigh molecular weight polyethylene (UHMWPE) (16,17) has a very low frictional coefficient against metal and ceramics, and is therefore used as a bearing surface for joint replacement prostheses. Moreover, the wear resistance of UHMWPE is higher than other polymers investigated for this application. Low strength and creep, however, present potential problems.

The term polyethylene refers to plastics formed from polymerization of ethylene gas. The possibilities for structural variation on molecules formed by this simple repeating unit for different molecular weight, crystallinity, branching, cross-linking, and so on, are so numerous and dramatic with such a wide range of attainable properties that the term polyethylene truly refers to a subclass of materials. The earliest type of polyethylene was made by reacting ethylene at high (20,000–30,000 lb/in.^{2}) pressure and temperatures of 200–400 °C with oxygen as catalyst. Such material is referred to as conventional or low density polyethylene. Much polyethylene is produced now by newer, low pressure techniques using aluminum–titanium (Ziegler) catalysts. This is called linear polyethylene due to the linearity of its molecules, in contrast to the branched molecules produced by high pressure processes. The linear polymers can be used to make high density polyethylene by means of the higher degree of crystallinity attained with the regularly shaped molecules. Typically, there is no great difference in molecular weight between the low density and high density varieties, (e.g., 100,000–500,000). However, if the low pressure process is used to make extremely long molecules, (i.e., UHMWPE), the result is different and quite remarkable. This material, with a molecular weight between 1 and 10 million, is less crystalline and less dense than high density polyethylene and has exceptional mechanical properties. The material is used in very demanding applications and is by far the most successful polymer used in total joint replacements. It far outperforms the various acrylics, fluorocarbons, polyacetals, polyamides, and polyesters that were tried for such purposes. In recent years, cross-linking methods including chemical agents and ionizing radiation have been implemented in an attempt to further improve the wear performance of UHMWPE.

The principal biocompatibility issue with polyethylene relates to the inflammatory response provoked by particles of the polymer, as can be generated by the wear of total joint replacement prostheses prostheses (18,19).

Absorbable Polymers. Absorbable polymers have been used in the fabrication of surgical implants for decades in the form of absorbable sutures. More recently, this class of materials has been investigated for the application of resorbable devices including fracture fixation implants and scaffolds for tissue engineering. The principal issues associated with the implementation of absorbable polymers as implants include: mechanical properties (i.e., strength), degradation rate, and biological response to the degradation products.

Synthetic Absorbable Polymers. One of the classes of polymers used frequently for the fabrication of absorbable implants is the alpha-hydroxy acids including L-lactic acid, glycolic acid, and dioxanone. These molecules normally are used in their polymeric forms: poly L-lactic acid (PLLA), polyglycolic acid (PGA), and polydioxanone. Copolymers of lactic and glycolic acids are also frequently employed.

This particular class of polyester undergoes breakdown as a result of the hydrolytic scission of the ester bond. The access of water to this bond in PGA is much greater resulting in a more rapid degradation rate compared to that which occurs with PLLA, which has a bulkier CH_3 side group instead of the H atom in PGA. The copolymer of polylactic and polyglycolic acid can be designed to have an intermediate degradation rates. While the majority of the breakdown of these polymers is due to hydrolytic scission there is some lesser extent of nonspecific enzymatic action.

Several factors affect the rate of breakdown of these polymers: the relative amount of monomers comprising the copolymers, the degree of crystallinity, and the surface area. These polymers are normally broken down to natural body components excreted in the urine or exhaled. The process of degradation involves the gradual decrease in the average molecular weight of the polymer as hydrolysis proceeds. At some point, the molecular weight decreases to the extent that the polymer becomes soluble in the aqueous environment and there is a bolus release of the molecules. Depending on the mass of the implanted device, the concentration of the molecules may elicit an inflammatory response (20).

Natural Absorbable Polymers. Myriad devices are fabricated from collagen (21), the principal structural protein of the body. The collagen molecule comprises three tightly coiled helical polypeptide chains. *In vivo* the collagen molecule, tropocollagen, is assembled to form fibrils that in turn assume various orientations and configurations to form the architecture of various tissues. The wide array of properties of tissues comprising collagen, from dermis to musculoskeletal tissues including articular cartilage, meniscus, and ligament, is due to differences in the chemistry, density, and orientation of the fibrils formed from the collagen molecule.

Collagen is soluble in specific solutions in which the chains can become disentangled to produce gelatin. It can be isolated from tissue and purified through the use of several agents: acids, alkalis, enzymes, and salt. Treatment in acid results in the elimination of acidic proteins and glycosaminoglycans that result in the dissociation of the collagen fibrils. A similar effect can be achieved using alkaline extraction with the removal of basic proteins. Proteolytic enzymes that cleave the telopeptides, that serve as natural cross-linking agents for collagen, allow for the dissolution of collagen molecules and aggregates in aqueous solutions. Salt extraction leads to the removal of newly synthesized collagen molecules and certain noncollagenous molecules thus facilitating the disaggregation of collagen fibrils.

That collagen is soluble in acidic medium facilitates its extraction from tissues and reprocessing into biomaterials. Several factors are critical determinants of the properties of reconstituted collagen biomaterials. The degree to which denaturation or degradation of the collagen structures isolated from tissue occurs will affect the mechanical properties. These properties will also be affected by the degree to which the material is subsequently cross-linked.

An important biological property related to the molecular structure of collagen is the collagen-induced blood platelet aggregation. The quarternary structure of collagen resulting from the periodic aggregation of the collagen molecules has been well documented. Methods for isolating and purifying collagen fibrils, that result in the preservation or destruction of this quarternary structure are employed to produce either hemostatic or thromboresistant biomaterials. Another factor relates to the removal of soluble components that might serve as antigens. The immunogenicity can be reduced, to clinically nonconsequential levels, by chemically modifying the antigen molecules.

A wide variety of methods have been employed for the fabrication of collagen sutures, fleeces for hemostasis, and sponge-like materials for scaffolds for tissue engineering.

Ceramics

Ceramics are typically three-dimensional (3D) arrays of positively charged metal ions and negatively charged nonmetal ions, often oxygen. The ionic bond localizes all the available electrons in the formation of a bond. Network organization ranges from highly organized, crystalline, 3D arrays to amorphous, random arrangements in glassy materials.

Ceramics, for reasons described above, may be the most chemically inert implant materials currently in use. However, their relatively low tensile strength, high modulus, and brittleness limit the applications in which they may be used. Current techniques allowing the formation of ceramic coatings on metallic substrates have revitalized interest in ceramics for hard tissue applications.

Aluminum Oxide. Aluminum oxide has been found of value for the articulating components of total joint arthroplasties because of its high wear resistance and its low coefficient of friction when prepared in congruent, polished geometries. The brittle nature of alumina remains a detriment.

Calcium Phosphates/Hydroxyapatite. Calcium-based ceramics, closely related to the naturally occurring hydroxyapatite in bone, have generated a large amount of interest in recent years. The ability to bond directly to bone as well as their osteoconductive capability promise to enhance biological fixation of implant devices. Hydroxyapatite is only slightly resorbable and is used in both dense and porous forms as a permanent implant. Tricalcium phosphate is bioabsorbable to varying degrees, depending on formulation and structure. There are currently a wide array of calcium phosphate materials undergoing investigation as bone graft substitute materials (see the Section on Calcium Phosphate Materials as Matrices for Bone Regeneration: Bone Graft Substitute Materials).

Composite Materials

Composite materials are combinations of two or more materials, and usually more than one material class (i.e., metals polymers, ceramics). They are used to achieve a combination of mechanical properties for specific applications. Composite technology, much of it developed for the aerospace industry, is beginning to make it way into biomedical materials. Carbon fiber reinforced polymers are being investigated as substitutes for metals. The advantage is that devices with comparable strength, but with significantly lower stiffness can be produced. Moreover, these types of composite devices are radiolucent.

BIOLOGICAL RESPONSE TO BIOMATERIALS

The biological processes comprising the tissue response are affected by implant-related factors including (22):

1. The "dead space" created by the presence of the implant.
2. Soluble agents released by the implant (e.g., metal ions or polymer fragments).
3. Insoluble particulate material released from the implant (e.g., wear debris).
4. Chemical interactions of biological molecules with the implant surface.
5. Alterations in the strain distribution in tissue caused by the mismatch in modulus of elasticity between the implant and surrounding tissue, and the movement of the implant relative to adjacent tissue as a result of the absence of mechanical continuity.

Study of the tissue response to implants requires methodology capable of measurements at the molecular, cellular, and tissue levels. Moreover, time is an important variable owing to the criticality of the temporal relationship between the molecular and cellular protagonists of the biological reactions, and because implant-related factors act with different time constants on the biological responses. The dynamic nature of implant-tissue interactions requires that the final assessment of tissue compatibility be qualified by the time frame in which it has been evaluated.

The tissue response to an implant is the cumulative physiological effect of (*1*) modulation of the acute wound healing response to the surgical trauma of implantation and the presence of the implant, (*2*) the subsequent chronic inflammatory reaction associated with the presence of the device, and (*3*) remodeling of surrounding tissue as it adapts to the presence of the implant (23). Moreover, the healing and stress-induced adaptive remodeling responses of different tissues vary considerably. In this regard, the response of various tissues to the same implant can vary greatly.

In considering the biological response that might be elicited by an implant, the healing–remodeling characteristics of the four basic types of tissue: connective tissue, muscle, epithelia, and nerve, should be recalled. The characteristics of the parenchymal cells in each type of tissue can provide a basis for understanding the tissue response to an implant. The following characteristics of an implant site are determinants of the biological response:

1. Vascularity.
2. The nature of the parenchymal cell with respect to its capability for mitosis and migration, because these processes determine the regenerative capability of the tissue.
3. The presence of regulatory cells such as macrophages/histiocytes.
4. The effect of mechanical strain, associated with deformation of the extracellular matrix, on the behavior of the parenchymal cell.

Surgical wounds in avascular tissue (e.g., the cornea and inner third of the meniscus) will not heal because of the limited potential for the proliferation and migration of surrounding parenchymal cells and the absence of a fibrin clot in the wound site into which the cells can migrate. Gaps between an implant and surrounding avascular tissue can remain indefinitely. Implant sites in vascular tissues in which the parenchymal cell does not have the capability for mitosis heal by the formation of scar in the gap between the implant and surrounding tissue. Moreover, adjacent cells that have died as a result of the implant surgery will be replaced by fibroblasts and scar tissue.

Normal Local Tissue Response

Wound Healing. Implantation of a medical device initiates a sequence of cellular and biochemical processes that lead to "healing by second intention" (i.e., healing by the formation of granulation tissue within a defect; as opposed to the healing of an incision, i.e., healing by first intention). The first phase of healing in vascularized tissues is inflammation, which is followed by a reparative phase, the replacement of the dead or damaged cells by healthy cells. The pathway that the reparative process takes depends on the regenerative capability of the cells comprising the injured tissue (i.e., the tissue or organ into which the implant has been placed). Cells can be distinguished as labile, stable, or permanent based on their capacity to regenerate. Labile cells continue to proliferate throughout life, replacing cells that are continually being destroyed. Epithelia and blood cells are examples of labile cells. Cells of splenic, lymphoid, and hematopoietic tissues are also labile cells. Stable cells retain the capacity for proliferation, although they do not normally replicate. These cells can undergo rapid division in response to a variety of stimuli and are capable of reconstitution of the tissue of origin. Stable cells include the parenchymal cells of all of the glandular organs of the body (e.g., liver, kidney, and pancreas), mesenchymal derivatives such as fibroblasts, smooth muscle cells, osteoblasts and chondrocytes, and vascular endothelial cells. Permanent cells are those which cannot reproduce themselves after birth. Examples are nerve cells.

Tissues comprised of labile and stable cells have the capability for regeneration after surgical trauma. The injured tissue is replaced by parenchymal cells of the same type, often leaving no residual trace of injury. However, tissues comprised of permanent cells are repaired by the production of fibrocollagenous scar. Despite the capability of many tissues to undergo regeneration, destruction of the tissue stroma, remaining after injury or constructed during the healing process, will lead to formation of scar. The biological response to materials thereby depends on the influence of the material on the inflammatory and reparative stages of wound healing. Does the material yield leachables or corrosion products that interfere with the resolution of inflammation initiated by the surgical trauma? Does the presence of the material interfere with the stroma required for the regeneration of tissue at the implant site? These are the types of questions that need to be addressed when assessing the "biocompatibility" of materials.

A number of systemic and local factors influence the inflammatory-reparative response. Systemic influences include age, nutrition, hematologic derangements, metabolic derangements, hormones, and steroids. While there is a prevailing "conventional wisdom" that the elderly heal more slowly than the young, there are few control data and animal experiments to support this notion. Nutrition can have a profound effect on the healing of wounds. Prolonged protein starvation can inhibit collagen formation, while high protein diets can enhance the rate of tensile strength gained during wound healing. Local influences that can affect wound healing include infection, inadequate blood supply, and the presence of a foreign body.

Fibrous Tissue Interface. The very presence of the implant provides a dead space in tissue that attracts macrophages to the implant–tissue interface (24). These cells are attracted to the prosthesis as they are to any dead space (e.g., bursa or joint space), presumably because of certain microenvironmental conditions (e.g., low O_2 and high lactate). In this regard it is not clear why macrophages are absent from the surface of osseointegrated implants (see below).

Macrophages along with fibroblasts of the scar comprise synovial tissue (25) that can be considered the chronic inflammatory response to implants (unless the device is apposed by osseous tissue, i.e., osseointegrated). This process is often termed "fibrous encapsulation" (26,27). The presence of regulatory cells such as macrophages at the implant-tissue interface can profoundly influence the host response to a device because these cells can release proinflammatory mediators if irritated by the movement of the device or substances released from the biomaterial (28). The inflammatory response of the synovial tissue around implants is comparable to the inflammation that can occur in the synovium lining any bursa (e.g., bursitis); hence, the response to implants has been termed "implant bursitis" (25).

Response to Implants in Bone: Osseointegration, Bone Ingrowth, Chemical Bonding of Bone to a Biomaterial. Wound healing governs the makeup of the tissue that forms around implants. Because of its capability for regeneration bone should be expected to appose implants in osseous tissue, and form within the pore spaces of porous coatings. Is this bone bonded in any way to the implant? Bonding of a prosthesis to bone would enhance its stability, limiting the relative motion between the implant and bone. In addition, bonding might provide a more favorable distribution of stress to surrounding osseous tissue.

Bonding of bone to an implant can be achieved by mechanical or chemical means., Interdigitation of bone with PMMA bone cement or with irregularities in implant topography, and bone ingrowth into porous surfaces, can yield interfaces capable of supporting shear and tensile as well as compressive forces. These types of mechanical bonding have been extensively investigated and are reasonably well understood. Chemical bonding of bone to materials could result from molecular (e.g., protein) adsorption–bonding to surfaces with subsequent bone cell attachment. This phenomenon has undergone intensive investigation in recent years but is not yet as well understood as mechanical bonding.

The term "osseointegration" has been used to describe the presence of bone on the surface of an implant with no histologically (light microscopy) demonstrable intervening nonosseous (e.g., fibrous) tissue. All implants in bone should become osseointegrated unless the bone regeneration process is inhibited.

The bone ingrowth into a porous-surface coating on an implant leads to an interlocking bond that can serve to stabilize the device. In order for the porous material to accommodate the cellular and extracellular elements of bone, the average pore diameter should be above $\sim 100\ \mu m$.

The bone ingrowth process proceeds in two stages. The surgical trauma of implantation initially leads to the regeneration of bone throughout the pores of the coating. Then mechanical stress-induced remodeling leads to resorption of bone from certain regions of the implant and continued formation and remodeling of bone in other regions.

Previous investigations have provided evidence of bone bonding to many different types of calcium phosphate materials, calcium carbonate substances, and calcium-containing "bioactive" glasses. Chemical bonding was evidenced by the high strength of the implant-bone interface that could not be explained by a mechanical interlocking bond alone. In addition, TEM has shown that there is no identifiable border between these calcium-containing implants and adjacent bone.

Many recent studies have investigated the bonding of bone to one particular calcium phosphate mineral, hydroxyapatite, chosen because its relationship to the primary mineral constituent of bone; natural bone mineral is a calcium-deficient carbonate apatite. Experiments have been performed on both hydroxyapatite coated metallic implants and on particulate and block forms of the mineral employed as bone substitute materials. Histology of specimens from animals and retrieved from human subjects show that a layer of new bone ~100 μm in thickness covers most of the hydroxyapatite surface within a few weeks of implantation and remains indefinitely. This layer of bone is attached to the surrounding osseous tissue by trabecular bridges.

In studying the mechanism of bone bonding, researchers have found that within days of implantation, biological apatites precipitate (from body fluid) onto the surface of the calcium-containing implants. These biological apatites are comparable to the carbonate apatite that is bone mineral. Proteins probably adsorb to this biological mineral layer thereby facilitating bone cell attachment and the production of osteoid directly onto the implant. This osteoid subsequently undergoes mineralization as it does normally in osteogenesis, thus forming a continuum of mineral from the implant to the bone. In this light, the bone cell responds to the biological apatite layer that has formed on the implant and not directly to the implant itself. Recent studies have shown that this biological apatite layer forms on many different calcium phosphate substances, explaining why bone bonding behavior has been reported for many different types of calcium phosphate materials. Of course, the clinical value of this phenomenon will depend (*1*) for coatings, on how well these substances can be bonded to implants; and (*2*) for bone graft substitute materials, their strength, modulus of elasticity, and ability to be resorbed. However, the finding that bone can become chemically bonded to certain biomaterials is a significant advance in our understanding of the implant-bone interface.

Effects of Implant-Induced Alterations of the Mechanical Environment. The presence of the implant can alter the stress distribution in the extracellular matrix (ECM), and thereby reduce or increase the strains experienced by the constituent cells. Many studies have demonstrated immobilization-induced atrophy of certain tissues resulting from the decrease in mechanical strains. Loss of bone mass around stiff femoral stems and femoral condylar prostheses of total hip and knee replacement devices has been associated with the reduced strains due to "stress shielding". Hyperplasia and hypertrophy of tissue in which mechanical strains have increased due to the presence of an implant have also been evidenced.

Criteria for Assessing Acceptability of the Tissue Response

The *in vivo* assessment of tissue compatibility of biomaterials requires that certain criteria be implemented for determining the acceptability of the tissue response relative to the intended application of the material–device. The biomaterial–device should be considered biocompatible only in the context of the criteria used to assess the acceptability of the tissue response. In this regard, every study involving the *in vivo* assessment of tissue compatibility should provide a working definition of biocompatibility. Biomaterials–devices implanted into bone can become apposed by the regenerating osseous tissue, and thus be considered compatible with bone regeneration. However, altered bone remodeling around the device due to stress shielding, with a net loss of bone mass (i.e., osteopenia), could lead to the assessment that the material–device is not compatible with normal bone remodeling. In situations in which the implant is surrounded by fibrous tissue the macrophages on the surface of the material are the expected response to the dead space produced by the very presence of the implant. The synovial tissue thus produced might be considered an acceptable response relative to the chemical compatibility of the material. Utilization of the thickness of the scar capsule around implants alone as a measure of biocompatibility is problematic because it can be influenced by movement of the tissue at the site relative to the implant.

The cellular and molecular make-up of tissue and the interactions among these components are complex. Therefore, criteria for assessing certain features of the biocompatibility of biomaterials–devices should focus on specific aspects of the biological response. The tissue compatibility of materials should be assessed specifically in the context of the effects of the material–device on certain aspects of the response. Moreover, it is important to note that materials yielding acceptable tissue compatibility in one site of implantation might yield unfavorable results in another site.

Degeneration of the Biomaterial–Tissue Interface

As noted earlier it is the wound healing response that initially establishes the tissue characteristics of the implant–tissue interface. Several agents have the potential for initiating degenerative changes in the interface tissue. Others probably act as promoters to stimulate the production of proinflammatory mediators that stimulate tissue degradation, and potentiate the failure process. Of the many factors affecting the implant–tissue interface, motion of the prosthetic component and particulate debris are two of the most important. However, it is difficult to determine the causal relationships between these factors and implant failure from only studying the end-stage tissue. Other histopathological findings and laboratory studies indicate that metal ions and immune reactions might play roles in the degenerative processes leading to prosthesis loosening in certain patients. Systemic diseases and drugs employed for the treatment of the disorders could also serve as factors contributing to the breakdown of the implant–bone interface. Finally, there might be interindividual differences in genetically determined cellular responses that could explain why prostheses fail in some patients in whom there is a low mechanical risk factor for failure.

Effects of Implant Movement. Movement of the implant relative to the surrounding tissue can interfere with the wound healing response by disrupting the granulation tissue. In the case of implants in bone this relative movement, if excessive, can destroy the stroma required for osseous regeneration, and a fibrous scar results. Another important effect of implant motion is the formation of a bursa within connective tissue in which shearing and tensile movement has led to disruption of tissue continuity and led to the formation of a void space or sack (lined by synovial-like cells). It is to be expected, then, that tissue around prosthetic components removed due to loosening might display features of synovial-like tissue. The presence of synovial cells (macrophage and fibroblast-like cells) is important because they could be activated by other agents, such as particulate debris, to produce proinflammatory molecules. The process of activation of this tissue might be similar to that which occurs in inflammatory joint synovium or bursitis.

An explanation of how prosthetic motion leads to the formation of the synovial-like tissue can be found in previous studies (29) that have shown that "synovial lining is simply an accretion of macrophages and fibroblasts stimulated by mechanical cavitation of connective tissue". These findings are based on experiments in which the mechanical disruption of connective tissue was produced by injection of air and/or fluid into the subcutaneous space of animals (30). The resulting sack was initially described as a "granuloma pouch". Later studies (29) demonstrated that the membrane lining the pouch displayed the characteristics of synovium, and referred to this tissue as "facsimile synovium".

Prosthetic motion can also contribute to wear of the prosthetic component abrading against the bone cement sheath or surrounding bone, thereby generating increased amounts of particulate debris that might contribute to activation of the macrophages and synovial-like cells at the implant–tissue interface.

Effects of Implant-Derived Particles. Particulate debris can be generated from the abrasion of the implant against surrounding tissue. Understandably, the potential for wear is greater with materials–devices rubbing against a hard surface such as bone and with the articulating components of joint replacement prostheses. This particulate debris can induce changes in the tissue around the implants. Adverse responses have been found to both metallic and polymeric particles. The biological reactions to particles are related to (*1*) particle size, (*2*) quantity, (*3*) chemistry, (*4*) topography, and (*5*) shape. While it is not clear what role each of these factors play in the biological response, particle size appears to be particularly important. Particles small enough to be phagocytosed (<10 μm) elicit more of an adverse cellular response than larger particles.

Particulate metallic particles (viz., cobalt–chromium alloy particles) can induce rapid proliferation of macrophages and focal degeneration of synovial tissues (31). Because previous animal investigations and histopathological studies of tissues retrieved from human subjects have suggested that titanium alloy is more "biocompatible" than cobalt–chromium alloys it has been assumed that titanium particulate debris would be less problematic than particles of cobalt–chromium alloy. Histology of pigmented tissue surrounding titanium implants has generally revealed considerably fewer macrophages and multinucleated foreign body giant cells than seen around cobalt–chromium alloy particles and polymeric particulate debris. However, titanium alloy particles generated by the abrasion of femoral stems against bone cement in human subjects can cause histiocytic and lymphoplasmacytic reactions to the metallic particles (32). Titanium particles have also been found to cause fibroblasts in culture to produce elevated levels of PGE_2. These findings show that there may be adverse aspects of the biological response to titanium particles as well as to cobalt–chromium alloy particulate debris.

Many investigations evaluating the histological response to polyethylene and polymethylmethacrylate particles in animals and in tissue recovered from revision surgery have revealed the histiocytic response to these polymer particles. Moreover, it has been shown that this macrophage response can lead to bone resorption.

Synovial cells also respond to calcium-containing ceramic particles (33). Local leukocyte influx, proteinase, PGE_2, and tumor necrosis factor (TNF) levels have been measured after injection of calcium containing ceramic materials into the "air pouch model" described above. The TNF was detected in significant amounts after injection of the ceramics. These substances also provoked elevated leukocyte counts and levels of proteinase and PGE_2, showing that substances with surface chemistries that elicit a beneficial tissue response (e.g., bone bonding) when implanted in bulk form can cause destructive cellular reactions when present in particulate form.

Investigations indicate that most biomaterials, when present in particulate form in a size range small enough to be phagocytosed (<10 μm), can elicit a biological response that could cause the bone resorption that initiates and promotes the loosening process. This degenerative process has been referred to as "small particle disease".

Metallic Ions. Animal and human investigations have revealed elevated levels of metal ions in subjects with certain types of implants (viz., total joint replacement prostheses). Our knowledge is still incomplete with respect to the mechanisms of metal ion release. Results are often variable with respect to the concentration of specific metal ions in certain tissues and fluids. The fact that metal in ionic form is often not distinguished from that present as particles serves to confound interpretation of results.

Rises in serum and urinary chromium levels in patients who have undergo conventional cemented cobalt–chromium alloy hip replacement have previously been reported (34). However, an attempt to determine the valency of chromium as either +3 (III) or +6 (VI) from the concentration of metal ion in blood clot was not successful. This experiment was based on the fact that erythrocytes display a unidirectional uptake of Cr(VI) while effectively excluding Cr(III). The distinction of the valency of chromium is important because Cr(VI) is much more biologically active than Cr(III).

Unfortunately, our knowledge of the local and systemic biological and clinical sequelae of metal ion release has not significantly advanced over the past several years. Addition of cobalt ions in the form of cobalt fluoride solutions to the media of synovial cells can stimulate their production of neutral proteinases and collagenase (35). These findings may be relevant to findings of tissue degradation (e.g., osteolysis) around implants in that metal ions could activate synovial cells in the surrounding synovial tissue to produce agents that promote tissue degeneration.

Diseases and Drugs. There has been little work correlating the failure of implants with disease states and drugs employed to treat the disorders. Some observations indicate that antiinflammatory agents, as well as certain anticancer drugs, can reduce the amount of bone formation around devices in the early stages of wound healing after implantation. Little is known, however, about the role of these and other agents on tissue remodeling and degeneration at the biomaterial-tissue interface.

Immune Reactions

It is not infrequent that two patients matched for sex, age, weight, activity level, and other factors, that might be expected to affect the performance of the prosthesis (implanted with the same device by same surgeon), have very different outcomes. This suggests that immune reactions, or genetically determined responses, might play a role in the failure of prostheses in some patients.

Immune responses include antibody and cell-mediated reactions and activation of the complement system. Certain small molecules released from implants (e.g., metal ions), while not antigenic themselves, can bind to existing antibodies and then to larger antigenic molecules or carrier proteins and subsequently elicit antibody production by activation of B lymphocytes by the small molecule (the "hapten") and by activation of helper T lymphocytes by the carrier protein to which it is bound.

The cell types that might be expected to occur at sites of antibody and cell-mediated reactions are not often found in tissue retrieved with revised devices. These cells include lymphocytes and plasma cells. The finding of occasional lymphocytic infiltrates in peri-implant tissue does not provide enough information for the role of immune reactions to implant. Immune reactions to polymeric materials (viz., silicone) have also been suggested as the cause of certain systemic diseases. However, mechanisms for such a response, and its prevalence, remain in question. Much more additional work is necessary to determine the role of immune reactions in the response to implantable devices.

The complement system, comprising circulating proteins and cell-surface receptors, plays an important role in immune processes engaged in the host defense against infectious agents. Te complement system consists of 20–30 proteins circulating in blood plasma. Most of these are inactive until they are cleaved by the chemical action of an enzyme of the interaction with a biomaterial surface. Once activated, the proteins can initiate a cascade of reactions resulting in the mobilization of immune cells resulting in inflammatory processes. Previous studies have demonstrated that many biomaterials can activate (cleave) certain molecules (C_3 and C_5) in the complement system and thereby stimulate the alternative pathway of the immune response. It has been suggested that complement activation by biomaterials could play a role in adverse reactions to certain devices. However, additional studies are required.

One form of cell-mediated immune reaction associated with implants, that has been studied, is the delayed hypersensitivity response. "Metal allergy" has been incriminated as the cause of failure in certain patients (36). However, results obtained to date are not definitive. "The incidence of metal sensitivity in the normal population is high, with up to 15% of the population sensitive to nickel and perhaps up to 25% sensitive to at least one of the common sensitizers Ni, Co, and Cr. The incidence of metal sensitivity reactions requiring premature removal of an orthopedic device is probably small (less than the incidence of infection). Clearly, there are factors not yet understood that caused one patient, but not another, to react" (37).

A similar situation exists with respect to sensitivity reactions to polymeric materials including bone cement (PMMA). The monomer of PMMA is a strong skin sensitizer (38). However, failure of cemented devices has not yet been correlated with a hypersensitivity response in patients.

The fact that there is no clear etiology of the prosthesis loosening in some patients while in other individuals with multiple risk factors for failure the prosthesis functions well has suggested that there may be genetic determinants for loosening.

Carcinogenicity

Chromium and nickel are known carcinogens and cobalt is a suspected carcinogen. Therefore, it is understandable that some concern might be raised about the release of these metal ions into the human body from implants. Fortunately, there have been few reports of neoplasms around implanted devices (e.g., total joint replacement prostheses). While no causal relationship has been evidenced, there is a high enough index of suspicion to warrant serious investigation of this matter through epidemiological and other studies. The use of porous coated metallic devices (with large surface area) in younger patients (e.g., noncemented total joint replacement prostheses) has added to concern about the long-term clinical consequences of metal ion release because of the significant increase in exposure of patients to metal ions.

Prior publications have reviewed the relationship of metallic ion release to oncogenesis (1), and reports of neoplasms found around orthopedic implants have been reviewed (39). The difference in the tumor types, time to appearance, and type of prosthesis confounds attempts to conclude an association of the neoplasm to the implant materials and released moieties.

In an epidemiological investigation conducted in New Zealand (40), >1300 total joint replacement patients were followed to determine the incidence of remote site tumors. The incidences of tumors of the lymphatic and hemapoietic systems were found to be significantly greater than expected in the decade following arthroplasty. It is important to note that the incidences of cancer of the breast, colon, and rectum were significantly less than expected. The investigators acknowledged that while the association might be due, in part, to an effect of the prosthetic implants, other mechanisms, particularly drug therapy, require consideration. Somewhat similar results were obtained from another recent study (41) of the cancer incidence in 443 total hip replacement (McKee–Farrar) patients operated on between 1967 and 1973 (followed to the end of 1981). The risk of leukemias and lymphomas increased while the risk of breast cancer decreased. The authors concluded that the local occurrence of cancer associated with prostheses made of cobalt–chromium–molybdenum as reported in the literature as well as animal experiments indicate that “chrome–cobalt–alloy plays some role in cancerogenesis (sic)”.

In a recent publication (42), a nationwide cohort study performed in Sweden to evaluate cancer incidence among > 100,000 hip replacement patients found no overall cancer excess relative to the general population. The standardized incidence ratios (SIRs) were, however, elevated for prostate cancer and melanoma and reduced for stomach cancer risk. Long-term follow-up (> or = 15 years) revealed an excess of multiple myeloma. The study found no material increase in risk for bone or connective tissue cancer. The investigators noted that, while hip implant patients had similar rates of most types of cancer to those in the general population, excesses in certain types of cancers warranted further investigation, particularly because of the ever-increasing use of hip implants at younger ages.

BACTERIAL INFECTION

Biomaterial surfaces can provide favorable substrates for the colonization by bacteria. The adherence of bacteria to solid surfaces is facilitated by the their production of a “biofilm”. The biofilm is a complex structure comprising bacterial cells encapsulated in a polymeric matrix. The detailed composition of the matrix has yet to be fully determined. Little is still known about how certain biomaterials may favor the production and adherence of a biofilm. Studies are still seeking to understand how certain material characteristics might favor bacterial colonization.

Infection following material implantation may be defined as multiplication of pathogenic microorganisms in the tissue of the host after a material implantation, causing disease by local cellular injury, secretion of a toxin, or antigen–antibody reaction in the host. The pathogenic microorganisms could be bacteria, fungi or viruses; the mostly common pathogenic microorganisms are bacteria.

Implant-related infection is one of the most serious and difficult complications to treat, often requiring reoperation including the surgical removal of the implant, and it may result in osteomyelitis, amputation, or even death. About 25–50% of infected vascular prostheses for cardiac, abdominal, and extremity vessel replacement cases result in amputation or death (43–45). Infectious complications are the principal concerns in the use and development of implanted materials for several indications.

The Biological Response to Bacterial Infection

We have noted above that the surgical trauma associated with the implantation of medical device is an injury that elicits an inflammatory response. Bacteria are another form of injurious agent that similarly elicits inflammation. While there are similarities in the cellular reactions to these two forms of injury there are important differences. That cells of the immune system are involves in the inflammatory reaction to bacterial infection is cause for use of the term “immune response” to describe the biological process elicited by a bacterial infection.

The immune response (also called the “immune reaction) is a defense function of the body that protects it against invading pathogens, foreign proteins, and malignancies. It consists of the “humoral immune response” and the “cell-mediated immune response”. In the humoral immune response, B lymphocytes produce antibodies that react with specific antigens brought by invading pathogens, foreign proteins, and malignancies. The antigen–antibody reactions activate the complement cascade, which causes the lysis of pathogens or cells bearing those antigens. The humoral response may begin immediately on invasion by an antigen in acute type or up to days later in chronic type. In the cell-mediated immune response, T lymphocytes mobilize tissue macrophages in the presence of foreign antigen, which causes the pathogens or cells bearing those antigens been taken by phagocyte.

An implant-related infection occurs when an adequate number of a sufficiently virulent organism overcomes the host’s immune response and establishes a focus of infection at the implant site. Implant-related infections remain a formidable challenge to the surgeon as well as material scientist. The high success rate obtained with antibiotic therapy in most bacterial diseases has not been obtained with implant-related infections for several known and as yet unidentified reasons. One important factor is that the sites on and around implants colonized by bacteria have little or no blood supply and thus do not allow blood-borne antimicrobial agents to reach the bacteria. The biofilm in which the bacteria grow may also shield the pathogens from the antimicrobial agents. Illness, malnutrition, and inadequacy of the immune system may be other factors that allow for the development implant-related infections.

Classification of Pathogens in Environment

Pathogens in the environment can be divided into three categories: primary pathogen, opportunistic pathogen, and nonpathogen. Primary pathogens are organisms that can cause infection in normal host when it has attached to the host’s tissue and has gained sufficient numbers. It is also called a professional pathogen. Only a very small proportion of microbial species may be considered to be primary or professional pathogens, and even among these species only a relatively small number of clones have been shown to cause infection. Pathogenic organisms are highly adapted to the pathogenic state and have developed characteristics that enable them to be transmitted, to attach to surfaces, to invade tissue, to escape host defenses, to multiply, and thus to cause infection.

Opportunistic pathogens are those organisms that can only cause infection in impaired hosts. For opportunistic pathogens, the state is the main determinant of whether infection will be the outcome of their interaction with the host's local tissue. This group of organisms may lack effective means to overcome an unimpaired host's defense mechanisms. They have limited growth opportunities outside their restricted niche in an unimpaired individual. As a result, infection may be only a rare consequence of the host–microbe encounter.

Nonpathogens are harmless members of the normal flora in healthy individuals. They may, however, in some rare situations, act as virulent invaders in an individual with severe deficiencies in host defense mechanisms.

The Most Common Bacteria that Cause Implant-Related Infection and Routes of Transmitting Pathogens

Studies of infected implants that have been retrieved for analysis indicate that a few species seem to dominate implant-related infections. Coagulase negative staphylococci are most frequently involved in the implant-related infections. Aerobic Gram-negative bacteria and anaerobic bacteria, which are usually present in deep infections (46), can also cause implant-related infection. *Staphylococcus aureus* (*S. aureus*) and *Staphylococcus epidermidis* (*S. epidermidis*) have been most frequently isolated from infected implant material surfaces. However, *Escherichia coli* (*E. coli*), *Pseudomonas aeruginosa*, β-hemolytic streptococci, and enterococci have also been isolated (43,47). These bacteria more often act as a component of mixed infections.

The different physical and chemical properties of implant material surfaces appear to be responsible for favoring infection with certain bacteria. *Staphylococcus aureus* is mostly involved in infection of metallic implants, such as metallic artificial joints, whereas *S. epidermidis* is a primary cause of infection of polymeric biomaterial implants, such as vascular grafts, catheters, and shunts (47).

The most pathogenic species is *S. aureus* because the infection caused by *S. aureus* often results in a much higher rate of mortality, and it is rarely cleared without removal of the implant. The recent emergence of *S. aureus* that are more resistant to all approved antibiotics raises more serious concerns for the future (48).

Implant-related infections may be the result of bacterial contamination of the implant material prior to its implantation. Pathogenic microorganisms may obtain access into the body by, direct contact, airborne spreading, contaminated water transmission, and blood stream transmission. If microorganisms exit in the host's tissue or on the skin or mucous membrane away from the implant site and break through blood barrier (e.g., associated dental treatment) they can gain access to the blood circulation. This can bring the microorganisms to the implant site (i.e., hematogenous infection).

Risk Factors for Implant-Related Infections

Implant-related infections occur when an adequate number of a sufficiently virulent organism overcomes the host's defense systems. During this process, many factors may be involved or even cooperate in establishing a focus of infection at the local implant area. The risk factors may involve the implant material, the process of implantation surgery, and the host.

Material-Related Factors. A large surface increases the possibility of microorganism attachment and thus can lay a role in implant-related infection. The avascular zone surrounding a device also favors infection as it contains tissue fluid and is often free of microorganism-monitoring agents because of the absence of blood circulation. A small initial number of microorganisms can grow to significant numbers and cause infection without interruption.

Sterile implant materials are commonly packaged in sterile paper, cloth, and plastic bags. However, all of these may be accidentally broken without notice and allow bacterial contamination of the implant.

Implantation-Related Factors. Implantation-related factors include the operating environment, skin and wound care, and surgical technique. In the operating room, airborne microorganisms (usually Gram-positive bacteria) are a source of wound contamination, originating with operating room personnel. Each person in the operating room sheds as many as 5000–55,0000 particles/min. Conventional operating room air may contain 10–15 bacteria/ft^3(49).

The microorganisms present on the host's skin are another source of wound contamination. Although the skin and hair can be sterilized with disinfectant agents, it is almost impossible to sterilize the hair follicles and sebaceous glands because the disinfectants now used in surgery do not penetrate an oily environment. Many disinfectants that do penetrate the oily environment, such as hexachlorophene, are absorbed by the body and have potentially toxic side effects. For this reason, skin preparations now used in surgery have a limited effect on sebaceous glands and hair follicles where microorganisms normally reside and reproduce (49). Because the skin can never be disinfected completely, the number of residual microorganisms present on the skin after disinfection builds the possibility of infection.

Any factor or event that delays wound healing increases the risk of implant-related infection. Ischemic necrosis, seroma, hematoma, wound infection, and suture abscesses are common preceding events for implant-related infection. Surgical technique and operating time also contribute to infection rates.

Host-Related Factors. Systematic factors that can contribute to implant-related infections include: immunological status, nutrition, chronic disease, and infection at a remote site or bacteremia caused by other reasons. A deficiency in the host's defense mechanisms predisposes the host to infection by specific groups of opportunistic pathogens (49). Deficiencies in the immune system may be acquired (such as acquired immune deficiency syndrome, AIDS) or may result from congenital abnormalities. Malnutrition and chronic disease decreases both the immune and inflammatory response to microorganism invasion. Although the contaminating microorganisms may be few in number, the altered host's defense mechanisms implies that even small bacterial counts have to be regarded as highly virulent species.

If there is infection at a remote site in the host, the microorganisms can be brought to the implant site by blood stream and cause implant-related infection. Under several other conditions which the blood barrier are broken, such as a dental treatment, microorganisms are transported by the blood stream to find their way to the implant site, causing hematogenous infections (50,51). Infection of total hip arthroplasties after dental treatment is not rare (52).

The Most Common Feature of Implant-Related Infection: Biofilm

At the implant site, the surface of the material is immersed in the tissue fluid of the host's local tissue. If microorganisms appear, they have a strong tendency to colonize surfaces to form a microecosystem in which various microbial strains and species grow in a complex community-like structure, which is called biofilm.

Biofilms are defined as bacterial populations reside and produce in matrix that adheres to a surface, interface, or each other. During most implant-related infections, microbial products may assist the development and persistence of the infection in association with adsorbed macromolecules from the biological environment in which the implant material is placed. In the presence of implant material, bacteria elaborate a fibrous exopolysaccharide material called the "glycocalyx". The glycocalyx modifies the local environment in favor of the pathogen by hiding and protecting the organism from surfactants, antibodies, phagocytes, and antimicrobial agents. This increases the population of microorganisms on the surface of implant materials *in vivo* (53,54). These protective biofilms may act as bases in predisposing to tissue invasion and also result in the persistence of infection. Biofilms are implant-associated and troublesome. They have been reported to be 500 times more resistant to antibiotics than planktonic cells (55).

Growth of the organisms is the main mechanism of multiplication in a biofilm and eventually leads to the formation of a thick film. The biofilm is formed in three phases. The first phase is the formation of "conditioning film". As soon as the implantation of material performs, the material surfaces adsorbed macromolecules from the surrounding fluid, forming a conditioning film. The macromolecules are a number of extracellular proteins that interact with host intracellular matrix and blood proteins. For example, joint materials adsorb macromolecules from synovial fluid, bone materials adsorb macromolecules from plasma, while dental materials adsorb macromolecules from salivary fluid. The conditioning film forms within seconds of exposure of the implant to a body fluid (56). This conditioning film provides a suitable substrate for microorganism's adhesion.

The second phase is an initial, reversible adherence of microorganisms to the conditioning film. This adhesion depends on the physicochemical characteristics of the microbial cell surface, the material surface and the conditioning film. Microorganisms can reach the surface via various transport mechanisms, such as diffusion, convection or sedimentation (57). Implants can become contaminated before or during surgery, and more likely, by hematogenous seeding (58). Several factors are reported to contribute to this initial adherence, including surface hydrophobicity, proteinaceous adhesins, and capsular polysaccharides, such as fibrinogen, fibronectin, thrombospondin, von Willebrand factor, collagen, bone sialoprotein, and elastin (59). It seems that different bacteria is helped by different group of factors. *Staphylococcus aureus* appears to be enhanced by mostly fibronectin and plasma glycoprotein in adhering to polymethylmethacrylate *in vivo*, and this may contribute to the establishment of infection (60).

The third phase of biofilm development is microcolony formation and exopolymer production, which results in the firm anchoring of the biofilm and complex biofilm architecture. The adhered organisms multiply and form microcolonies and higher ordered structure glycocalyx. As soon as glycocalyx have been formed, the organisms gain some resistance. In favor of the protection, the microorganisms keep multiplying within this matrix. New layers of film are added and allowing the microorganisms room to multiply, forming thick biofilms (56). Biofilm protects the resident microorganisms against environmental attacks and antibiotics. However, the mechanism for resistance is not well understood.

As biofilms grow thicker and thicker, microorganisms on the periphery of the expanding biofilm may detach, which plays a large part in the pathogenesis of septic processes (61,62).

Latent Infections

As the biofilm protects microorganisms against environmental attacks and antibiotics, the microorganisms can survive in the biofilm for a long period of time when the host's defense system is strong or sufficient concentration of antibiotics is exit. There is no clinical symptom or sign of infection, but the microorganisms exit in the implant site. However, if the host's defense system becomes weakened or a sufficient concentration of antibiotics is no longer administered, the microorganisms may become more active, and cause a latent infection.

Latent infection also can be caused in other situations by a remote wound. The remote wound can give microorganisms access to the blood circulation. The blood stream can bring the microorganisms to the implant, causing a latent infection. Infection of total hip arthroplasty after dental treatment is not rare (52).

The Outcomes of Infection

Implant-related infection produces all the symptoms of infectious inflammation with a wide spectrum of severity.

The clinical presentation is determined largely by the virulence of the infecting pathogen, the extent of the area involved, the location of the infection and the nature of the infected host tissue. The infection may cause large changes to the host's internal environment as well as the implant material. As we mentioned in former section, *S. aureus* is a common pathogen in implant-related infection. In the mean while, it is particularly a very virulent pathogen in this setting and usually produces a fulminant infection.

The early stage of implant-related infection may be obvious or obscure. Signs and symptoms vary with the location and extent of tissue or organ involvement. Common characteristics of infection, such as fever, chills, nausea, vomiting, malaise, erythema, swelling, and tenderness may or may not be present. The classic triad is fever, swelling, and tenderness or pain. Tenderness or pain probably is the most common and earliest symptom. Swelling may be mild. Fever is not always a consistent finding.

During the mid-late stage of infection, the severity of the infection, its specific microorganism, and the particular tissue, site, and material involved all introduce morphologic variations in the basic patterns of acute and chronic infection. The implant-related infection can appear as serous inflammation, fibrinous inflammation, suppurative or purulent infection, abscesses, or more seriously lead septicemia, septic shock, or patient death.

Serous inflammation is marked by the outpouring of a thin fluid derived from the blood serum. Fibrinous inflammation is a fibrinous exudate develops when the vascular leaks are large enough. These two are the clinical appearance of mild infection. Fibrinous exudate may convert to scar tissue if the infection is controlled in this stage (63).

Suppurative or purulent infection is commonly seen in implant-related infection. It is characterized by the production of large amounts of pus or purulent exudate consisting of neutrophils, necrotic cells, and tissue fluid. Certain pyogenic (pus-producing) microorganisms (e.g., staphylococci) produce this localized suppuration.

Abscesses are focal localized collections of purulent inflammatory tissue caused by suppuration buried in a tissue. They are produced by pyogenic bacteria. Abscesses have a central region that appears as a cavity full of pus that consists of necrotic tissue, died white blood cells, bacteria, and material. There is usually a zone of neutrophils around this necrotic focus. Vascular dilation, parenchymal and fibroblastic proliferation occurs outside this region, indicating the beginning of repair. Sometimes, the abscess may become walled off by connective tissue that limits it from further spread (64).

Microorganisms on the periphery of the expanding biofilm may detach or separate. These microorganisms may present in blood and can be confirmed by blood culture, which is called bacteremia. If the bacteria are strong enough to survive in blood and produce toxin, it is called septicemia, which can be life-threatening.

Diagnosis of Implant-Related Infection

The specific diagnosis of implant-related infection is dependent, in large part, upon isolation of the pathogen by aspiration of secreted fluid or by culture of tissue obtained at debridement. However, there are other assessments that can indicate an infection, such as blood count and different morphologic examinations.

Roentgenographic studies are helpful in implant-related infections. Plain roentgenograms show soft tissue swelling, joint space narrowing or widening, bone destruction and non-X-ray transparent implant materials. These roentgenograms can reveal (*1*) abnormal lucencies at the material–host tissue interface, (*2*) bone or periosteal reaction, (*3*) motion of components on stress views, or (*4*) changes in the position of implant materials. If initial roentgenograms are normal in the evaluation of a suspected implant-related infection, other imaging modalities that show soft tissue swelling and loss of normal fat planes about the involved site should be used.

Computed tomography (CT) scanning can help determine the extent of surrounding tissue involvement. Pus within the cavity can cause an increased density on the CT scan. Adjacent soft tissue abscesses also are easily seen. However, the use of CT scan is limited if the implanted material is made of metal.

Magnetic resonance imaging (MRI) can also be implemented for evaluating implant-related infections. The images can reflect the increase in water content resulting from edema in the implant or surrounding tissue due to infection. The MRI detects changes much earlier in the course of disease than roentgenograms, because it shows the condition of the surrounding soft tissue.

Fate of Material During Infection

The biofilm and bacterial modification of the microenvironment around implants may affect the biomaterial in several ways. Biodegradable materials, such as collagen, may degrade faster than expected due the elevated levels of enzymes and the changes in pH. Such implants may collapse before being replaced by host tissue and thus become a component of the local abscess. The low pH often found at sites of infection may also accelerate the corrosion of metallic materials. Implant-related infections indirectly affect implant materials by causing the destruction of surrounding tissue thus contributing to loosening of the implant.

Treatments of Implant-Related Infection

Successful treatment of an implant-related infection often depends on both extensive and meticulous surgical debridement and effective antimicrobial therapy. Debridement should be emphasized because infection often persists despite treatment with systemic antibiotic therapy in the absence of extensive and meticulous debridement of the implant-tissue interface.

It is of paramount importance to confirm the microorganism causing the infection. Distinguishing infection from pure inflammation is also very important because they have some similarities. The timing and selection of bacteria culture are critical. Many implant-related infections are deep seated, and adequate culture specimens are difficult to obtain. In spite of this, every effort should be made to obtain a culture specimen. The preferred specimen in implant-related infections is aspirated fluid. A deep wound biopsy or a curetted specimen after cleaning the wound is acceptable.

Antibiotic therapy should begin as early as implant-related infection is diagnosed. Treatment with systemic antibiotic therapy can at least prevent the infection from transmission. In the meanwhile, local symptoms and signs of infection should be observed carefully. If there are signs show the infection is not under control, a debridement may be indicated.

Treatment of an implant-related infection at mid–late stage may require both systemic antimicrobial treatment and local surgical treatment. Antibiotic treatment alone sometimes may still be sufficient at this stage, however, it should be performed under careful observation and cannot last long. If there are signs that the infection is not under control, surgery is needed.

Surgery may go hand in hand with antibiotic treatment. The purpose of surgery is clearance of the necrotic tissue with the bacteria and augmentation of the host response. Debridement and irrigation removes necrotic and avascular tissue, bacteria, and harmful bacterial products. It is essential when pus is found on aspiration, signifying an abscess, or when roentgenographic changes indicating pus, necrotic material, and chronic inflammation. If an abscess has formed, removal of the implant is indicated.

Frequently, the only way to treat an infected large implant is to remove it in associate with antibiotic treatment.

If the infection is very severe, septic shock may exist and threaten the patient's life. At this situation, the most important work is antishock and save life. Supported by antishock and antibiotic treatment, removal of implant and open debridement, or even amputation must be performed.

How to Prevent Implant-Related Infection

Recognizing the unique characteristics and outcomes of implant-related infections, the best course is prevention. The close relationship and cooperation of implant designer, manufacturer, and surgeon are necessary for prevention of implant-related infection. The implant must be kept free of bacteria, while the surgeon should evaluate the risk of infection in each patient by considering both host- and surgeon-dependent factors. Simply stated, it is much easier to prevent an implant-related infection than to treat it.

Sterilization Methods. There are several methods for sterilizing implants prior to implantation. The first concern when choosing a sterilization method is the physical and chemical properties of the implant material itself as well as the packaging material required to maintain the implant sterile prior to delivery to the operative site. Autoclaving is the method of choice for the sterilization of metallic or heat-resistant implants. The advantages of autoclaving are efficacy, speed, process simplicity, and no toxic residues. The disadvantages are the relatively high temperature of the process (121 °C) may damage some non-heat resistant implant materials as well as the packaging materials. Thus, most nonmetallic implants and packaging materials cannot be sterilized by this method.

Ethylene oxide (EtO) gas sterilization is a low temperature sterilizing process. It is compatible with a wide range of implant and packaging materials. It is commonly used to sterilize a wide range of medical implants, including surgical sutures, absorbable and nonabsorbable meshes, absorbable bone repair devices, heart valves, and vascular grafts. The advantages of EtO are its efficacy, high penetration ability, and compatibility with a wide range of materials. The main disadvantage is EtO residuals in the sterilized materials.

Exposure to ^{60}Co gamma rays is another widespread sterilizing method. Gamma rays have a high penetrating ability. This method of sterilization is widely used for medical products, such as surgical sutures and drapes, syringes, metallic bone implants, knee and hip prostheses. The advantages of ^{60}Co gamma-ray sterilization are efficacy, speed, process simplicity, no toxic residues. The main disadvantages are the very high costs and incompatibility of some radiation sensitive materials such as the fluoropolymer and polytetrafluoroethylene (PTFE).

Medical implant may also be sterilized with machine-generated accelerated electrons called electron beam sterilization. It has a similar range of applications and material compatibility characteristics as the ^{60}Co process. However, the main disadvantages are short penetration distance. This limits its usage. A unique application for this method is the on-line sterilization of small, thin materials immediately following primary packaging.

Several new technologies are emerging that have potential utility for implant material sterilization, such as gaseous chlorine dioxide, low temperature gas plasma, gaseous ozone, vapor-phase hydrogen peroxide, and machine-generated X rays. Machine-generated X rays have the advantage of a nonisotopic source and penetrating power similar to gamma rays.

Prevention of Operative Contamination, Wound Sepsis Contiguous to the Implant, and Hematogenous Infection. The importance of irrigation during and at the end of surgery has been well documented. The principles of no dead space, no avascular tissue, evacuation of hematomas, and soft tissue coverage should be practiced strictly during implantation surgery. Good surgical technique and minimal operating times also contribute to lowering of infection rates. Prophylactic antibiotics are definitely indicated when implants are involved. New methods are on the way of developing. Direct local delivery of polyclonal human antibodies to abdominal implant sites reduced infection severity and mortality in an animal model of implant-related peritoneal infection (65).

Any bacteremia can induce an implant-related infection by the hematogenous route (51,66,67). Dentogingival infections and manipulations are known causes of streptococcal and anaerobic infections in prostheses (51). Pyogenic skin processes can cause staphylococcal and streptococcal infections of joint replacement. Genitourinary and gastrointestinal tract procedures or infections are associated with Gram-negative bacillary, enterococcal, and anaerobic infections of prostheses (66,68). Twenty-to-forty percent of prosthetic joint infections are caused by the hematogenous route (68).

To prevent hematogenous implant-related infection, any factor that might predispose to infection should be avoid before insertion of the implant material. For elective implant surgery, the patient should be evaluated for the presence of pyogenic dentogingival pathology, skin, and other even very small local infection. Perioperative antibiotic prophylaxis is also very important. It has been reported to reduce infections in total joint replacement surgery (69).

For patients with indwelling implant materials, it is of paramount important to diagnose and treat infections in any location as early as possible. This reduce the risk of seeding bacteria to the implant materials hematogenously in large extent. Any situation likely to cause bacteremia, even a dental care should be avoided or seriously evaluated.

Antimicrobial Biomaterials

Two factors necessary for an implant-related infection are attachment of bacteria to the implant surface and multiplication of bacteria to a significant number. Antibacteria materials are designed to decrease the surface attachment of microorganism and/or inhibit the multiplying of microorganism.

A variety of antibiotics incorporating implant materials were designed to inhibit the microorganism against multiplying. Antibiotics for incorporation in materials should have a broad antibacterial spectrum, sufficient bactericidal activity, high specific antibacterial potency, low rate of primary resistant pathogens, minimal development of resistance during therapy, low protein binding, low sensitizing potential, marked water solubility, and stable (70). During these years, various antibiotics have been evaluated both *in vitro* and *in vivo*. The studies are most regarding their suitability for incorporation in materials.

Cefazolin loaded bone matrix gelatin (C-BMG) was made from putting cefazolin into BMG by vacuum adsorption and freeze-drying techniques (71). It was tested for repair of long segmental bone defects and preventing infection in animal experiment. The effective inhibition time to staphylococcus aureus of C-BMG was 22 days in vitro, while 14 days in vivo. The drug concentration in local tissues (bone and muscle) were higher than that of plasma, and the drug concentration in local tissues was higher in early stage, later it kept stable low drug release.

Rifampin-bonded gelatin-sealed polyester was tested in another animal experiment (72). Their results indicated that rifampin-bonded gelatin-sealed polyester grafts were significantly more resistant to bacteremic infection than were silver/collagen-coated polyester grafts.

For developing antibiotics delivery biodegradable materials, polylactide–polyglycolide copolymers were mixed with vancomycin (73). The mixture was compressed and sintered at 55 °C to form beads of different sizes. The biodegradable material released high concentrations of antibiotic *in vitro* for the period of time needed to treat infection. The diameter of the sample inhibition zone ranged from 6.5 to 10 mm, which is equivalent to 12.5–100% of relative activity. By changing the processing parameters, the release rate of the beads was able to be controlled. This provides advantages of meeting the specific requirement for prevention of implant-related infection.

Besides incorporating antibiotics in implant materials, antimicrobial materials have been made in different ways. Bovine serum albumin was used to coat material surfaces by using carbodiimide, a cross-linking agent (74). The inhibition rate of the albumin coating on bacterial adherence remained high throughout the experiment. This suggests the potential use of this cross-linked albumin coating to reduce bacterial adherence and thus the subsequent possibility of prosthetic or implant infection *in vivo*.

In the future, the use of implant materials will surely increase with growing demands for a higher quality of life. In 1997, operating expenses allocated to tissue engineering exceed \$450 million and fund the activities of nearly 2500 scientists and support personnel. Growth rate is 22.5% / annum (75). At the beginning of 2001, operating expenses allocated to tissue engineering exceed \$600 million and fund the activities of nearly 3300 scientists and support personnel. Spending by tissue engineering firms has been growing at a compound annual rateof 16% (76). However, implant-related infection remains a significant problem in this field. Research on the development of biomaterial surfaces with antimicrobial properties has increased to an annual expenditure of ~\$430 million (75).

BIBLIOGRAPHY

1. Black J. Metallic ion release and its relationship to oncogenesis. In: Fitzgerald RHJ, editor. The Hip, Proceedings of the Thirteenth Open Scientific Meeting of the Hip Society. St. Louis: C.V. Mosby; 1985. p 119–213.
2. Bartolozzi A, Black J. Chromium concentrations in serum, blood clot and urine from patients following total hip arthroplasty. Biomaterials 1985;6:2–8.
3. Takamura K, Hayashi K, Ishinishi N, Yamada T, Sugioka Y. Evaluation of carcinogenicity and chronic toxicity associated with orthopedic implants in mice. J Biomed Mater Res 1994;28:583–589.
4. Bouchard PR et al. Carcinogenicity of CoCrMo (F-75) implants in the rat. J Biomed Mater Res 1996;32:37–44.
5. Lombardi AV, Mallory TH, Vaughn BK, Drouillard P. Aseptic loosening in total hip arthroplasty secondary to osteolysis induced by wear debris from titanium-alloy modular femoral heads. J Bone Jt Surg 1989;71A:1337.
6. Blaine TA et al. Increased levels of tumor necrosis factor-a and interleukin-6 protein and messenger RNA in human peripheral blood monocytes due to titanium particles. J Bone Jt Surg 1996;78-A:1181–1192.
7. Gonzales JB, Purdon MA, Horowitz SM. In vitro studies on the role of titanium in aseptic loosening. Clin Orthop 1996;330:244–250.
8. Goodman SB, Fornasier VL, Lee J, Kei J. The effects of bulk versus particulate titanium and cobalt chrome alloy implanted into the rabbit tibia. JBMR 1990;24:1539–1549.
9. Donkerwolcke M, Burny F, Muster D. Tissues and bone adhesives—historical aspects. Biomaterials 1998;19:1461–1466.
10. Nivbrant B, Karrholm J, Rohrl S, Hassander H, Wesslen B. Bone cement with reduced proportion of monomer in total hip arthroplasty: preclinical evaluation and randomized study of 47 cases with 5 years' follow-up. Acta Orthop Scand 2001;72:572–584.

11. de la Torre B et al. Biocompatibility and other properties of acrylic bone cements prepared with antiseptic activators. J Biomed Mater Res 2003;66B:502–513.
12. Thomson LA, Law FC, James KH, Matthew CA, Rushton N. Biocompatibility of particulate polymethylmethacrylate bone cements: a comparative study *in vitro* and *in vivo*. Biomaterials 1992;13:811–818.
13. Davis RG, Goodman SB, Smith RL, Lerman JA, Williams RJ., III The effects of bone cement powder on human adherent monocytes/macrophages *in vitro*. J Biomed Mater Res 1993;27: 1039–1046.
14. Jones LC, Hungerford DS. Cement Disease. Clin Orthop Rel Res 1987;225:192–206.
15. LeVier RR, Harrison MC, Cook RR, Lane TH. What is silicone? Plas Reconstr Surg 1992;92:163–167.
16. Bobyn JD, Spector M. Polyethylene. In: Encycolpedia of Materials Science and Engineering. New York: Pergamon Press; 1987. p 3649.
17. Li S, Burstein AH. Ultra-high molecular weight polyethylene. J Bone Jt Surg 1994;76-A:1080–1090.
18. Schmalzried TP, Jasty M, Harris WH. Periprosthetic bone loss in total hip arthroplasty: polyethylene wear debris and the concept of the effective joint space. J Bone Jt Surg 1992;74-A:849–863.
19. Green TR, Fisher J, Stone M, Wroblewski BM, Ingham E. Polyethylene particles of a 'critical size' are necessary for the induction of cytokines by macrophages in vitro. Biomaterials 1998;19:2297–2302.
20. Vert M, Pascal C, Chabot F, Leray J. Bioresorbable plastic materials for bone surgery. In: Hastings GW, Ducheyne P, editors. Macromolecular Biomaterials. Vol. Chap. 5 Boca Raton: CRC Press, Inc.; 1984. p 119–142.
21. Yannas IV. Natural materials. In: Ratner BD, Hoffman AS, Schoen FJ, Lemons JE, editors. Biomaterials Science: An Introduction to Materials in medicine. San Diego: Academic Press; 1992. p 84–94.
22. Spector M, Lalor PA. *In vivo* assessment of tissue compatibility. In: Ratner BD, Hoffman AS, Schoen FJ, Lemons JE, editors. Biomaterials Science: An Introductory Text. San Diego; CA: Academic Press; 1996. p 220–227.
23. Spector M, Cease C, Xia T-L. The local tissue response to biomaterials. CRC Crit Rev Biocompat 1989;5:269–295.
24. Silver IA. The physiology of wound healing. In: Hunt TK, editor. Wound Healing and Wound Infection. New York: Appleton-Century-Crofts; 1984. p 11–28.
25. Spector M. et al. Synovium-like tissue from loose joint replacement prostheses: comparision of human material with a canine model. Sem Arthr Rheum 1992;21:335–344.
26. Coleman DL, King RN, Andrade JD. The foreign body reaction: a chronic inflammatory response. J Biomed Mater Res 1974;8:199–211.
27. Laing PG, Ferguson AB, Hodge ES. Tissue reaction in rabbit muscle exposed to metallic implants. J Biomed Mater Res 1967;1:135–149.
28. Anderson JM, Miller K. M. Biomaterial biocompatibility and the macrophage. Biomaterials 1984;5:5–10.
29. Edwards JCW, Sedgwick AD, Willoughby DA. The formation of a structure with the features of synovial lining by subcutaneous injection of air: an in vivo tissue culture system. J Pathol 1981;134:147–156.
30. Selye H. Use of "granuloma pouch" technic in the study of antiphlogistic corticoids*. Proc Soc Exp Biol Med 1953;82: 328–333.
31. Howie DW, V-Roberts B. The synovial response to intraarticular cobalt-chrome wear particles. Clin Orthop 1988;232: 244–254.
32. Agins HJ et al., Metallic wear in failed titanium-alloy total hip replacements. J Bone Jt Surg 1988;70A:347–356.
33. Nagase M, Baker DG, Schumacher, Jr., HR. Prolonged inflammatory reactions induced by artificial ceramics in the rat air pouch model. J Rheum 1988;15:1334–1338.
34. Bartolozzi A, Black J. Chromium concentrations in serum, blood clot and urine from patients following total hip arthoplasty. Biomaterials 1985;6:2–8.
35. Ferguson GM, Watanabe S, Georgescu HI, Evans CH. The synovial production of collagenase and chondrocyte activating factors in response to cobalt. J Orth Res 1988;6:525–530.
36. Merritt K, Rodrigo JJ. Immune response to synthetic materials. Clin Orthop 1996;326:71–79.
37. Merritt K, Brown SA. Biological effects of corrosion products from metals. In: Fraker A, editor. Vol. STP 859 Corrosion and Degradation of Implant Material. Philadelphia: American Society for Testing and Materials; 1985. p 195–207.
38. Merritt K. Role of medical materials, both in implant and surface applications, in immune response and in resistance to infection. Biomaterials 1984;5:47–53.
39. Martin A, Bauer TW, Manley MT, Marks KE. Osteosarcoma at the site of total hip replacement. JB J S 1988;70A:1561–1567.
40. Gillespie WJ, Frampton CMA, Henderson RJ, Ryan PM. The incidence of cancer following total hip replacement. JB J S 1988;70B:539–542.
41. Visuri T, Koskenvuo M. Cancer risk after McKee-Farrar total hip replacement. Acta Orthop Scand 1989;60:25.
42. Signorello LB et al. Nationwide study of cancer risk among hip replacement patients in Sweden. J Natl Cancer Inst 2001;93:1405–1410.
43. Gristina AG. Implant-associated infection. In: Ratner BD, Schoen FJ, Lemons JE, editors. Biomaterials science: an introduction to materials in medicine. San Diego: Academic Press; 1996.
44. Gristina AG, Oga M, Webb LX, Hobgood CD. Adherent bacterial colonization in the pathogenesis of osteomyelitis. Science 1985;228:990–993.
45. Gristina AG, Costerton JW. Bacterial adherence to biomaterials and tissue. The significance of its role in clinical sepsis. J Bone Joint Surg Am 1985;67:264–273.
46. Fitzgerald RH, Jr., Infected Total Hip Arthroplasty: Diagnosis and Treatment. J Am Acad Orthop Surg 1995;3:249–262.
47. Gristina AG. Biomaterial-centered infection: microbial adhesion versus tissue integration. Science 1987;237: 1588–1595.
48. Proctor RA. Toward an understanding of biomaterial infections: a complex interplay between the host and bacteria. J Lab Clin Med 2000;135:14–15.
49. William C. General Principles of Infection. Campbell's Operative Orthopaedics. Mosby, Inc.; 1998.
50. Stinchfield FE, Bigliani LU, Neu HC, Goss TP, Foster CR. Late hematogenous infection of total joint replacement. J Bone Joint Surg Am 1980;62:1345–1350.
51. Lindqvist C, Slatis P. Dental bacteremia–a neglected cause of arthroplasty infections? Three hip cases. Acta Orthop Scand 1985;56:506–508.
52. LaPorte DM, Waldman BJ, Mont MA, Hungerford DS. Infections associated with dental procedures in total hip arthroplasty. J Bone Joint Surg Br 1999;81:56–59.
53. Costerton JW, Irvin RT, Cheng KJ. The bacterial glycocalyx in nature and disease. Annu Rev Microbiol 1981;35:299–324.
54. Gristina AG, Kolkin J. Current concepts review. Total joint replacement and sepsis. J Bone Joint Surg Am 1983;65:128–134.
55. Costerton JW, Lewandowski Z, Caldwell DE, Korber DR, Lappin-Scott HM. Microbial biofilms. Annu Rev Microbiol 1995;49:711–745.

56. Barry D. Infected orthopedic prostheses. Infections associated with indwelling medical devices. Washington, DC: ASM Press; 1994.
57. van Loosdrecht MC, Lyklema J, Norde W, Zehnder AJ. Influence of interfaces on microbial activity. Microbiol Rev 1990;54:75–87.
58. Schmalzried TP, Amstutz HC, Au MK, Dorey FJ. Etiology of deep sepsis in total hip arthroplasty. The significance of hematogenous and recurrent infections. Clin Orthop 1992; 200–207.
59. Patti JM, Allen BL, McGavin MJ, Hook M. MSCRAMM-mediated adherence of microorganisms to host tissues. Annu Rev Microbiol 1994;48:585–617.
60. Vaudaux P, Suzuki R, Waldvogel FA, Morgenthaler JJ, Nydegger UE. Foreign body infection: role of fibronectin as a ligand for the adherence of Staphylococcus aureus. J Infect Dis 1984;150:546–553.
61. Neu TR, Marshall KC. Bacterial polymers: physicochemical aspects of their interactions at interfaces. J Biomater Appl 1990;5:107–133.
62. Busscher HJ, Van der Mei HC. Relative importance of surface-free energy as a measure of hydrophobicity in bacterial adhesion to solid surfaces. In: Doyle RJ, Rosenberg M, editors. Microbial cell surface hydrophobicity. Washington DC: American Society for Microbiology; 1990. p 335–359.
63. Mandell B, Dolin. Principles and Practice of Infectious Disease. Churchill Livingstone; 2000.
64. Kuma C. Robbins Patholog. Basis Disease, 1999.
65. Poelstra KA et al. Prophylactic treatment of gram-positive and gram-negative abdominal implant infections using locally delivered polyclonal antibodies. J Biomed Mater Res 2002;60:206–215.
66. Ahlberg A, Carlsson AS, Lindberg L. Hematogenous infection in total joint replacement. Clin Orthop 1978; 69–75.
67. Lattimer GL, Keblish PA, Dickson TB, Jr., Vernick CG, Finnegan WJ. Hematogenous infection in total joint replacement. Recommendations for prophylactic antibiotics. JAMA 1979;242:2213–2214.
68. Inman RD, Gallegos KV, Brause BD, Redecha PB, Christian CL. Clinical and microbial features of prosthetic joint infection. Am J Med 1984;77:47–53.
69. Norden CW. A critical review of antibiotic prophylaxis in orthopedic surgery. Rev Infect Dis 1983;5:928–932.
70. Wahlig H, Dingeldein E. Antibiotics and bone cements. Experimental and clinical long-term observations. Acta Orthop Scand 1980;51:49–56.
71. You HB, Chen AM. The effect of cefazolin loaded bone matrix gelatin on repairing large segmental bone defects and preventing infection after operation, Zhongguo Xiu Fu Chong Jian Wai Ke Za Zhi 2000;14:162–165.
72. Goeau-Brissonniere O.A. et al. Comparison of the resistance to infection of rifampinbonded gelatin-sealed and silver/collagen-coated polyester prostheses. J Vasc Surg 2002;35: 1260–1263.
73. Liu SJ et al. In vitro elution of vancomycin from biodegradable beads. J Biomed Mater Res 1999;48:613–620.
74. An YH et al. Prevention of bacterial adherence to implant surfaces with a crosslinked albumin coating in vitro. J Orthop Res 1996;14:846–849.
75. Lysaght MJ, Nguy NA, Sullivan K. An economic survey of the emerging tissue engineering industry. Tissue Eng 1998;4: 231–238.
76. Lysaght MJ, Reyes J. The growth of tissue engineering. Tissue Eng 2001;7:485–493.

See also ALLOYS, SHAPE MEMORY; POLYMERIC MATERIALS; POROUS MATERIALS FOR BIOLOGICAL APPLICATIONS; RESIN-BASED COMPOSITES.

BIOELECTRODES

ERIC MCADAMS
University of Ulster at
Jordanstown
Newtownabbey,
Ireland

INTRODUCTION

Biomedical electrodes are used in various forms in a wide range of biomedical applications, including:

1. The detection of bioelectric events such as the electrocardiogram (ECG).
2. The application of therapeutic impulses to the body [e.g., cardiac pacing and defibrillation and transcutaneous electrical nerve stimulation (TENS)].
3. The application of electrical potentials in order to facilitate the transdermal delivery of ionized molecules for local and systemic therapeutic effect (iontophoresis).
4. The alternating current (ac) impedance characterization of body tissues.

Good electrode design is not as simple and straightforward a matter as is often assumed, and all electrode designs are not equal in performance (1). One must, therefore, not simply choose an electrode with as conductive a metal plate as possible, which unfortunately, was and appears to still be the case in many designs. Probably due to this mistaken view, it would appear that the associated electronic systems are often first developed and the electrode design is left to the end, almost as an afterthought. If the clinician is to properly diagnose the patient's cardiac problem, for example, it is imperative that the measured biosignal is clear, undistorted, and artefict-free. Unfortunately, monitoring bioelectrodes, if they are not chosen correctly, give rise to significant problems that make biosignal analysis difficult, if not impossible. Similarly, stimulation electrodes must be well-chosen if they are to optimally supply the therapeutic waveforms without causing trauma to the patient.

Current or charge is carried by ions inside the patient's body and by electrons in the electronic device itself and in its leads. The "charge-transfer" mechanism between current/charge carriers takes place at the electrode-patient interface and is of major importance in the design of an optimal electrode. Both the electrode–electrolyte interface and the skin under the electrode (collectively known as the contact) give rise to potentials and impedances that can distort the measured biosignal or adversely affect the electrotherapeutic procedure.

Implanted electrodes are generally made from inert or noble materials that do not react with surrounding tissues. Unfortunately, as a consequence, they tend to give rise to large interface impedances and unstable potentials. Implanted biosignal monitoring electrodes, in particular, require stable potentials and low interface impedances to minimize biosignal distortion and artifact problems. External biosignal-monitoring electrodes can generally use high electrical performance nonnoble materials such as silver–silver chloride without fear of biocompatibility problems (2). They do, however, have to address the additional and very significant problem of the skin with its sizeable impedance and unstable potential. Along with the desired biosignal, one amplifies the difference between the two contact potentials. If the contact potentials were identical (highly improbable), they would cancel each other out due to the use of a differential amplifier. If the potential mismatch were very large (several hundred mV), the amplifier would not be able to cope and would saturate. If the mismatch in contact potentials is small and stable, this mismatch will be amplified along with the biosignal, and the biosignal will appear shifted up or down on the oscilloscope screen or printout paper, which would generally not be a major problem as the additional voltage offset can be easily removed. What is a significant problem, however, is when the contact potentials fluctuate with time. Their mismatch, therefore, varies and the baseline of the biosignal is no longer constant, which leads to the problem termed baseline wonder or baseline drift, which makes analysis of some of the key features of the biosignal difficult. Filtering out of the drift is often not an option, as the filtering often also removes key components of the desired biosignal.

Large mismatched contact impedances can cause signal attenuation, filtering, distortion, and interference in biosignal monitoring. If contact impedances are significant compared with the input impedance of the amplifier, they can give rise to signal attenuation as a result of the voltage divider effect. Attenuation of the signal is not a major problem, after all, the amplifier is going to be used to amplify the signal by a factor of around 1000 (in the case of an ECG). A significant problem develops, however, because the contact impedance varies with frequency. The frequency-dependence of the contact impedance is a consequence of the presence of parallel capacitances at the electrode-electrolyte interface or at the skin under the electrode. At very high frequencies, the contact impedances are very small and, therefore, no attenuation of the high frequency parts of the biosignal exists. At low frequencies, the contact impedances can be very large and, hence, significant attenuation of low frequency components of the biosignal can exist. The overall signal is not only attenuated, it is also distorted with its low frequency components selectively reduced. The measurement system in effect acts as a high pass filter and the signal is differentiated. In the case of the ECG, the P, S, and T waves are deformed, leading in particular to a modification of the S–T segment. The S–T segment is of vital importance to the electrocardiologist, hence the importance of avoiding such biosignal distortions.

50/60 Hz interference can be amplified along with any monitored biosignal due to the mismatch of the contact impedances. Displacement currents flow from power lines through the air to the monitor cables and then through the electrodes and the patient to ground. If the contact impedances are not identical, the displacement currents flowing through the two contact impedances connected to a differential amplifier will give rise to different voltages at the amplifier's inputs. This 50 Hz offset voltage will be amplified along with the desired biosignal and its amplitude is proportional to an electrode–skin impedance mismatch (3).

Other applications, such as electrical impedance plethysmography and electrical impedance tomography (4), do not monitor intrinsic biosignals emanating from the body, but inject small currents or voltages into the body and record the resultant voltages or currents. The electrical properties of the body or a body segment can then be calculated. In many of these applications, the magnitude and mismatch of contact impedances can give rise to significant errors or artifacts (5). As relatively high frequencies are often involved in these techniques, even the series resistance of the gel pad (which is generally ignored) may become significant.

Although interface impedance and potential are generally less critical for implanted stimulation electrodes, many such electrodes (e.g., implanted pacing electrodes) are used to monitor biosignals as well as to deliver the required stimulation impulses. Even in the case of a purely stimulating electrode, a low interface impedance is required to minimize energy waste and to prolong the life of the power source. Various techniques are therefore used to effectively decrease the otherwise large interface impedances of the noble or inert materials used for their biocompatible properties. Electrode material and high electrical performance is generally less critical for external stimulation electrodes such as TENS and external defibrillation electrodes. Current density distribution is of major importance in these applications in order to avoid electrical hotspots and resultant burns to the skin. In some applications, such as TENS and external pacing, it is even sometimes advantageous to use a relatively resistive electrode material or gel, as this has been found to optimize current density distribution under the stimulation electrode.

As in the above applications, the avoidance of current density hotspots is one of several key factors in iontophoretic, transdermal delivery (6). An additional important constraint that is generally not relevant in other electrotherapies is the maintenance of the delicate electrochemical balance at the electrode/reservoir/skin interface. The electrode potential and impedance, as well as the composition of the drug reservoir, must generally remain within certain narrow ranges in order to avoid the deterioration of the electrode, the contamination of the drug reservoir, and the irritation of the patient's skin.

The electrical properties of the electrode contacts are, therefore, of great importance in most applications. Ideally, the contact with the patient should give rise to the following:

- Zero potential. Unfortunately, zero potential is not possible and a more realistic goal is to achieve a low, stable potential at each of the contacts.
- Zero Impedance. Unfortunately, zero impedance too is not possible and a more realistic goal is to achieve impedances at the two contacts that are low and as similar as possible.

The potentials and impedances of the electrode–electrolyte interface and the skin will therefore be studied in more depth in the following sections.

ELECTRICAL PROPERTIES OF ELECTRODE–SKIN INTERFACE

As briefly outlined above, the electrode–electrolyte interface and the skin under the electrode both give rise to potentials and impedances that can either distort any measured biosignal or give rise to problems during electrical stimulation.

The Electrode–Electrolyte Interface

The Electrode–Electrolyte Potential. When a metallic electrode comes in contact with an electrolyte (in body tissues or in an electrode gel), an ion–electron exchange occurs as a result of an electrochemical reaction. A tendency exists for metal atoms M to lose n electrons and pass into the electrolyte as metal ions, M^{+n}, causing the electrode to become negatively charged with respect to the electrolyte (Fig. 1). Reaction (**1**) is termed oxidation.

$$\mathrm{M} \rightarrow \mathrm{M}^{+n} + n\mathrm{e}^{-} \tag{\textbf{1}}$$

Similarly, under equilibrium conditions, some of the ions in solution M^{+n} take n electrons from the metal and deposit onto the electrode as metal atoms M. The electrode becomes positively charged with respect to the electrolyte. Reaction (**2**) is termed reduction.

$$\mathrm{M}^{+n} + n\mathrm{e}^{-} \rightarrow \mathrm{M} \tag{\textbf{2}}$$

The overall chemical reaction taking place at the interface is therefore

$$\mathrm{M} \rightleftharpoons \mathrm{M}^{n+} + n\mathrm{e}^{-} \tag{\textbf{3}}$$

Under equilibrium conditions, the rate at which metal atoms lose electrons and pass into solution is exactly balanced by the rate at which metal ions in solution deposit onto the electrode as metal atoms. The current flowing in one direction, i_0, is equal to and cancels out the current flowing in the opposite direction. The electrode is said to be behaving reversibly and the common value of currents, io, is termed the exchange current (density). Although the net current flowing through the electrode interface is zero, a potential difference is found to exist between the electrode and the electrolyte and depends on the position of the equilibrium between the two processes (**1**) and (**2**). Generally, the metal is negative relative to the electrolyte. The potential difference depends on the relative activities (or concentrations) of the ions present and on the electrode metal (7). This potential has been termed the equilibrium, reversible, or half-cell (i.e., one interface only) potential in the literature.



Figure 1. The electrode–electrolyte interface and reactions involved in generating its reversible or equilibrium potential.

When trying to measure the potential of a half-cell (i.e., one interface only), one is immediately faced with a problem, as one requires two electrodes to make a potential measurement, thus effectively creating an electrochemical cell with two electrode–electrolyte interfaces. One, therefore, measures not only the potential of the electrode–electrolyte interface under study, but also that of the second electrode used to complete the circuit. If one uses the same metal for the second electrode to that used in the first, the potentials will be identical (in theory at least) and will cancel each other out. The measured potential will be (theoretically) equal to zero. (In practice, however, slight differences in the composition of the metal used, the electrode surfaces, and in the gel will result in differences in the two half-cell potentials.) If, on the other hand, one uses a different metal for the second electrode, the measured potential of the cell will be due to the combination of the potentials of the two half-cells. It will be impossible to separate the potential of the half-cell under investigation.

In order to resolve this problem, early electrochemists decided to measure all electrode interface potentials with respect to a standardized electrode or reference electrode. The standard hydrogen electrode (SHE) was chosen to be the universal reference electrode and its half-cell potential was specified as zero. Other metal-to-ion interface potentials were then measured with reference to SHE and the entire measured offset voltage was attributed to electrode system being tested.

Hydrogen electrode consists of a platinized plate submerged to one-half its height HCl over which hydrogen gas at atm is bubbled. The half-cell potential of SHE depends on concentration of hydrogen ions in the solution, hence it is quite stable and reproducible. At the time that this decision was reached, the necessary glass blowing and silver soldering were common skills and the SHE was thus easy and inexpensive to make. Although, however, it is no longer convenient for modern routine measurements as a reference electrode (the flowing hydrogen gas is potentially explosive), electrode potentials are standardized with respect to the SHE (7).

The reversible, equilibrium, or half-cell potential of a given electrode–electrolyte interface depends on the activity (almost synonymous with concentration) of the ions taking part in the reactions (Table 1). This potential, E_{rev}, is given by the Nernst equation,

$$E_{\mathrm{rev}} = E_0 + [RT/nF]\mathrm{In}[\text{activity of oxidized form}/\text{activity of reduced form}] \tag{1}$$

Table 1. Reversible Potentials for Common Electrode Materials at 25 °C[a]

Metal and Reaction	Potential E^V,V
$Al \rightarrow Al^{3+} + 3e^-$	−1.706
$Zn \rightarrow Zn^{2+} + 2e^-$	−0.763
$Cr \rightarrow Cr^{3+} + 3e^-$	−0.744
$Fe \rightarrow Fe^{2+} + 2e^-$	−0.409
$Cd \rightarrow Cd^{2+} + 2e^-$	−0.401
$Ni \rightarrow Ni^{2+} + 2e^-$	−0.230
$Pb \rightarrow Pb^{2+} + 2e^-$	−0.126
$H_2 \rightarrow 2H^+ + 2e^-$	0.000 by definition
$Ag + Cl^- \rightarrow AgCl + e^-$	+0.223
$2\,Hg + 2Cl^- \rightarrow Hg_2Cl_2 + 2e^-$	+0.268
$Cu \rightarrow Cu^{2+} + 2e^-$	+0.340
$Cu \rightarrow Cu^+ + e^-$	+0.522
$Ag \rightarrow Ag^+ + e^-$	+0.799
$Au \rightarrow Au^{2+} + 3e^-$	+1.420
$Au \rightarrow Au^+ + e^-$	+1.680

[a] The metal undergoing the reaction shown has the magnitude and polarity of standard half-cell potential, E_0. Listed when the metal is referenced to the standard hydrogen electrode (3).

E_{rev} is the reversible, equilibrium, or half-cell potential
E_0 is the standard half-cell potential (measured relative to the standard hydrogen electrode)
R the universal gas constant,
n the number of electrons involved in reaction,
T the absolute temperature (K).

Activity, $a = \gamma C$, where C is concentration and γ, the activity coefficient, is a measure of the interaction between ions. When solution is infinitely dilute, $\gamma = 1$ and activity is equal to concentration.

Note the two components of E_{rev}. One is constant, E_0, wheras the other will vary due to slight variations in concentration, from one electrode to another. If two chemically identical electrodes make contact with the same electrolyte/body, the two interfaces should, in theory, develop identical half-cell potentials. When connected to a differential amplifier, the half-cell potentials of such electrodes would cancel each other out and the offset voltage would be zero. The electrode potentials would, therefore, make zero contribution to a biosignal they were being used to detect. Unfortunately, slight differences in electrode metal or gel result in the creation of offset voltages, which can greatly exceed the physiological variable to be measured. Generally, a more significant problem is that the electrode offset voltage can fluctuate with time, thus distorting the monitored biosignal (8).

The Electrode–Electrolyte Impedance. It has already been stated that in the electrode and the connecting lead, electrical charge is carried by electrons, whereas in the gel and in the human body, charge is carried by ions. A transition exists at the interface between the electrode and the electrolyte where charge is transferred from one kind of carrier to the other. In order for some of the ions in the electrode gel or in the body fluids to transfer their charge across the interface, many must first diffuse to the electrode–electrolyte interface under the influence of electrostatic attraction. Here they stick (or adsorb, as it is termed in electrochemistry) to the electrode surface and form the outer Helmholtz plane (OHP) (7). If the electrode has a negative charge relative to the electrolyte, positive ions will be attracted to the interface region and adsorb onto the electrode surface. As a consequence, there is a layer of negative charge on the metal surface and a layer of equal but opposite charge on the electrolyte side of the interface, both separated by a small distance across the OHP (see Fig. 2). A double layer of charge therefore exists at the interface, and such a system behaves like a parallel-plate capacitor. Not altogether surprising, the interface's capacitance is often termed the double-layer capacitance, C_{dl}, and is connected in parallel to the charge-transfer resistance in our simple equivalent circuit model.



Figure 2. The electrode–electrolyte interface. A metal in an electrolyte forms a double layer of charge. (Redrawn from Ref. 7).

Just in case one believed that the electrode interface was that simple, one must point out, for example, that as well as the cations electrostatically attracted to the negatively charged electrode surface (coulombic adsorption) anions may exits that are adsorbed on the electrode surface and form the inner Helmholtz layer or plane (IHP). These anions have tended to lose their hydration sphere and, consequently, are in close contact with the electrode. As they are negative ions adsorbed onto a negative electrode surface, electrostatic forces cannot be responsible. Some force *specific* to the ion (rather than its electric charge) must be responsible, hence the use of the term specific adsorption to describe this phenomenon. The van der Waals or chemical forces is thought to be responsible (7).

In order to understand some aspects of the double-layer capacitance, it is good to consider the basic equation for a parallel-plate capacitor. If two identical conductive plates, each of area A cm^2, are separated by a distance d cm, which is filled with a material of dielectric constant ε_0, then the capacitance of this parallel-plate capacitor, C_{pp}, is given by:

$$C_{pp} = \varepsilon_0 A/d \tag{2}$$

and the magnitude of the capacitive impedance, Z_{pp}, is given by

$$Z_{pp} = 1/2\pi f C_{pp} \tag{3}$$

where f is the frequency of the applied ac signal and π is a constant.

Some dc (or faradaic) current does, however, manage to leak across the double layer due to electrochemical reactions (**1**) and (**2**) taking place at the interface. These reactions experience a charge transfer resistance, R_{CT}, which can be thought of as shunting the nonfaradaic, double-layer capacitance and whose expression can be derived from the Butler–Volmer equation.

For small applied signal amplitudes (7),

$$R_{CT} = \frac{RT}{nF}\frac{1}{i_0} \tag{4}$$

A good electrode, from an electrical point of view, will have a very low value of R_{CT}. Charge will be transferred across the interface almost unimpeded and little voltage will be dropped across the interface. One should note that R_{CT} is inversely proportional to i_0. i_0 is the exchange current [i.e., the current flowing across the interface (in both directions) under equilibrium conditions (no net current flow)]. Simplistically, if an interface can cope with large currents under equilibrium conditions, it will be able to cope well with currents under nonequilibrium conditions. A good electrode system will therefore be characterized by a large value of exchange current or a low value of R_{CT}.

The interface impedance should theoretically be well represented by an equivalent circuit model comprising the double-layer capacitance in parallel with the charge transfer resistance, R_{CT}. Both are in series with R_{TOTAL}, the relatively small resistance due to the sum of the lead and electrolyte resistances.

Complex Impedance Plot. If, for each frequency of ac signal used to measure the impedance, the real part of the measured impedance (Z' or R_S) is plotted on the x axis and the imaginary part (Z'' or X_S) on the y axis of a graph, one obtains a Nyquist or complex impedance plot. The impedance locus for the above simple equivalent circuit model (Fig. 3.) of the interface impedance is plotted on a complex impedance plot in Fig. 4. *Note*: Electrochemists plot–X_S versus R_S and not X_S versus R_S as electrode (and tissue) impedances tend to be capacitive and thus negative. It is generally found easier to look at the plots with the Z'' axis inverted. Low frequency data are on the right side of the plot and higher frequencies are on the left, which is generally the case for electrode interface data.



Figure 3. Simple equivalent circuit model of the electrode-electrolyte interface. C_{dl} represents the double-layer capacitance, R_{CT} the charge transfer resistance, R_{TOTAL} the sum of the lead and electrolyte resistances, and E_{rev} represents the reversible or equilibrium potential.

The impedance locus has the form of a semi-circle with high and low frequency intercepts with the real axis at 90° (due to the presence of C_{dl} in parallel with R_{CT}). At very low frequencies, the impedance is equal to $R_{TOTAL} + R_{CT}$, the diameter of the semicircle being equal to R_{CT}. At higher frequencies, the impedance is influenced by the value of the parallel capacitance C_{dl}. As the capacitive impedance decreases with increasing frequency, current therefore flows through it and the total impedance of the parallel combination decreases. The reactive component and the phase angle increases from zero, reaches a maximum value (which depends on the relative sizes of R_{TOTAL} and R_{CT}), and then decreases again toward zero (see Figs. 4 and 5). The frequency at which the reactive component reaches its maximum value (ω_0) is given by $\omega_0 = 1/\, R_{CT}C_{dl}$ (Fig. 4).

At high frequencies, the impedance is determined by the series resistance R_{TOTAL}.

Bode Plot. Another popular method of presenting impedance data is the Bode plot. The impedance is plotted



Figure 4. Impedance plot for simple equivalent circuit model of the electrode–electrolyte interface. The impedance locus is semicircular as a result of the parallel combination of C_{dl} (the double layer capacitance) and R_{CT} (the charge transfer resistance), both of which are in series with R_{TOTAL}, the sum of the lead and electrolyte resistances.



Figure 5. Bode plot for the simple '3-component' equivalent circuit model. The magnitude of the impedance decreases from its low frequency value (R_{TOTAL} $+R_{CT}$) to R_{TOTAL} at very high frequencies. The phase angle of the overall interface impedance increases from 0° at low frequencies, reaches a maximum, which depends on the relative sizes of R_{TOTAL} and R_{CT} and then decreases again.

with log frequency on the x axis and both the absolute value of the impedance ($|Z| = [Z'^2 + Z''^2]^{1/2}$) and the phase-shift ($\phi = \tan^{-1}[Z''/Z']$) on the y axis. Unlike the complex impedance plot, the Bode plot explicitly shows frequency information.

The Bode plot for the electric circuit of Fig. 3 is shown in Fig. 5.

As in the complex impedance plot, the magnitude of the impedance is equal to $R_{TOTAL} + R_{CT}$ at very low frequencies (R_{dc}). The phase angle is zero at this point as the impedance is purely resistive. At very high frequencies, the magnitude of the impedance (R_∞) is equal to that of the series resistance R_{TOTAL}. At frequencies in between these two limits, the interface impedance is influenced by the value of the parallel capacitance C_{DL}. As the capacitive impedance decreases with increasing frequency, current therefore flows through it and the total impedance of the parallel combination decreases. The phase angle increases from zero, reaches a maximum value (generally less than 90° or π/2 rad), and then decreases again toward zero (see Fig. 5).

The above model can be used to explain most key aspects of the electrode–electrolyte interface. It must be pointed out, however, that the equivalent circuit is a gross approximation.

For example, diffusion of ions to the interface from the bulk of the electrolyte (gel or patient) takes place at a finite rate and thus gives rise to impedance to current flow, especially at low frequencies. The diffusion (often termed Warburg) impedance is generally located in series with the charge transfer resistance, both of these being in parallel with the double-layer capacitance. The diffusion impedance has been ignored in the above model as it tends not to be observed for many biomedical electrode systems over the range of frequencies typically used.

A further simplification is the use of a simple capacitance in the above model. Such ideal capacitive behavior is rarely observed with solid metal electrodes. Instead, an empirical pseudo capacitance or constant phase angle impedance, Z_{CPA}, is often used that has a constant phase angle, much like a capacitor.

$$Z_{CPA} = K(i\omega)^{-\beta} \quad (5)$$

where K is a measure of the magnitude of Z_{CPA} and has units of $\Omega s^{-\beta}$, and β is constant such that $0 < \beta < 1$. The phase angle of this empirical circuit element ($\phi = \beta\pi/2$ radians or $90\beta°$) generally lies between 45° and 90° (9). Typically, β has a value of 0.8 for many biomedical electrode systems.

Fricke (10) used the term polarization to describe the constant phase angle impedance and postulated that it was due to spontaneous depolarization of the electrode. Although he did not enlarge on the hypothesis, many authors have used Fricke's terminology over the intervening years. The present author must concur with Cole and Curtis' observation that "the use of the term polarization for describing the unexplained effects occurring at the metal–electrolyte interface is only an admission of our ignorance" (11).

The two most likely causes of the observed constant phase angle impedance are specific adsorption and surface roughness effects (12). With solid biomedical electrodes, the nonideal behavior is probably due to the surface roughness of the electrodes (13), which is supported by reports that roughing an electrode surface decreases the measured value of phase angle.

It is also naive to think that surface effects will only distort the nonfaradaic impedance and will have no effect on R_{CT} as assumed in the above model. It is more realistic that surface effects will affect the parallel combination of C_{dl} and R_{CT} giving rise to skewed (14,15) or distorted (16) arcs. The simple equivalent circuit used in this presentation is, however, a useful approximation that enables qualitative interpretation of much of the published data.

Polarization. Since the work of Fricke (10), the term polarization has been used to describe just about anything associated with the electrode–electolyte interface—frequency-dependence, nonlinearity, noise, and so on. Polarization has been defined as "the departure of the electrode potential from the reversible value upon the passage of faradaic current" (7).

Under equilibrium conditions, the electrode potential E is equal to its reversible potential E_{rev}. When a dc or faradaic current, i_{dc}, is applied to the electrode interface, it must flow through the resistance R_{CT}, which is in parallel with C_{dl}. From Ohm's law, the voltage dropped across this charge transfer resistance will be equal to i_{dc} multiplied by R_{CT} (Fig. 6). The electrode potential E is now given by:

$$E = E_{rev} + i_{dc}R_{CT} \quad (6)$$

The electrode, therefore, is no longer operating at its equilibrium or reversible value E_{rev}. This change in the



Figure 6. Polarization, the departure of the electrode potential from its reversible value upon the passage of faradaic current.

electrode interface's potential from its equilibrium value is termed polarization. The degree of polarization is measured by the additional voltage dropped across R_{CT}, (or overpotential, η, as it is termed in electrochemistry) where:

$$\eta = /E - E_{rev}/ \tag{7}$$

An ideal nonpolarizable electrode would have a value of R_{CT} equal to zero and, hence, would exist no resistance to faradaic current. The nonfaradaic impedance would effectively be shorted out and the total interface impedance would be zero. In this case, current would pass freely across the interface unimpeded. Measured biosignals, for example, would be unattenuated and undistorted. A perfect electrode system! The electrode potential would always remain constant at its reversible value.

A perfectly polarizable electrode would not permit the flow of any dc or faradaic current as the charge-transfer resistance in this case is infinite. Such an electrode is sometimes termed a blocking electrode. No faradaic charge would cross the interface, even for large overpotentials, and the electrode couples capacitvely with the tissues/electrolyte in this extreme case (Fig. 7).

Real electrodes are, however, neither perfectly polarizable nor perfectly nonpolarizable. Any net current flow across an electrode–electrolyte interface will experience a finite faradaic impedance across which an overpotential will develop.

An electrode system that has a very low value of R_{CT} lets current traverse the interface almost unimpeded, wastes little energy at the interface, has a relatively small overpotential, and has a relatively nonpolarizable electrode system. Such electrode systems are highly sought after, especially when recording small biosignals from the body surface.

Electrodes made of noble metal come closest to behaving as perfectly polarizable electrodes. As these metals are inert, they tend not to react chemically with the surrounding electrolyte or tissue. Noble metals are, therefore, generally used in the construction of implant electrodes where chemical reaction with surrounding tissues must be avoided in order to minimize tissue toxicity problems. Little steady current can pass in such cases as the charge transfer resistance for these electrodes is therefore very large (Fig. 7). The small current that does pass represents the charging and discharging of the double-layer capacitance. A problem, therefore, exists when designing implant electrodes. For a biocompatibility point of view, one requires a noble, hence polarizable, electrode system, whereas from an electrical performance point of view, one requires a nonpolarizable system. A compromise is achieved by using a polarizable electrode and roughening the surface of the electrode, thus decreasing the large interface impedance.



Figure 7. The dc current–voltage plots for Ideal Nonpolarizable, General Polarizable, and Ideal Polarizable electrode interfaces.

Transient Response and Tissue Damage. The response of the electrode system to sine waves of varying frequencies has been considered above (Complex Impedance and Bode plots) as this is a very useful tool in analyzing circuits or, in this case, electrode systems. Equally relevant is the response of an electrode system to voltage and current steps or pulses, as these will approximate therapeutic stimulation applications.

It must be borne in mind that the conversion from electrical to ionic current takes place at the electrode-tissue interface. Based on the simple equivalent circuit model, current can flow either through the parallel resistance or through the double-layer capacitance.

Current flowing through the parallel resistance involves faradaic charge transfer reactions. At the anode, the electrolysis of water and the oxidation of organic compounds can occur. The oxidation of the electrode itself can also occur, which results in the dissolution of metal. At the cathode, hydrogen ions are reduced to form hydrogen gas, which results in a change in pH near the electrode. The new chemical by products in all of these reactions may lead to tissue damage and, hence, faradaic charge transfer reactions must be avoided (17,18). Current must not, therefore, be allowed to flow through R_{CT}.



Figure 8. Voltage response to a pulse or step in current.



Figure 9. Current response to a pulse or step in voltage.

For current flowing through the double-layer capacitance, no charge actually crosses the electrode-tissue interface. Instead, ions in the tissue are attracted or repelled by charges on the electrode, resulting in transient pulses of ionic current. As no net current flows through the interface and electrochemical reactions are not involved, capacitive current is relatively safe. One must therefore seek, as far as possible, to couple capacitively with tissue when seeking to stimulate tissue without causing trauma.

If one applies a pulse of current of amplitude I_{dc} at time $t = 0$, the voltage response of the electrode-interface equivalent circuit model and, it is believed, the electrode-patient system is as shown in Fig. 8.

$$V(t) = I_{dc}R_{TOTAL} + I_{dc}R_{CT}(1 - \exp[-t/R_{CT}C_{dl}]) \quad (8)$$

At $t = 0$, the applied current flows unopposed through the capacitor and, hence, only sees the series resistance R_{TOTAL}. The initial voltage response is, therefore,

$$V_0 = I_{dc}R_{TOTAL} \quad (9)$$

The voltage response is then observed to gradually increase from V_0. The initial increase in voltage with time is inversely proportional to the magnitude of the capacitance.

For long pulse durations, all of the current will flow through the resistances R_{CT} and R_{TOTAL}. The total resistance seen by the current is, therefore,

$$Z_{(t=\infty)} = R_{TOTAL+}R_{CT} \quad (10)$$

and the limit voltage V_∞ is given by

$$V_\infty = I_{dc}(R_{TOTAL} + R_{CT}) \quad (11)$$

The voltage response will reach this limit value V_∞ in a time period of approximately five time constants, T, where $T = C_{dl}R_{CT}$.

If a perfect step in voltage, V_{dc}, is applied to the electrode system or the three-component model, the current response is as shown in Fig. 9 and given by the equation

$$I(t) = V_{dc}\left\{\left(\frac{1}{R_{TOTAL} + R_{CT}}\right)\right\} + \left(\frac{R_{CL}/R_{TOTAL}}{R_{CT} + R_{TOTAL}}\right)\exp\left[-\frac{R_{CT} + R_{TOTAL}}{R_{CT}R_{TOTAL}C_{dl}}t\right] \quad (12)$$

At the beginning of the voltage step, the resultant current jumps to a relatively large value I_0, where

$$I_0 = V_{dc}/R_{TOTAL} \quad (13)$$

As time passes, the resultant current decreases exponentially with an initial slope inversely proportional to the capacitance C_{dl}. Eventually, the current will reach a limiting value of I_∞, where

$$I_\infty = \frac{V_{dc}}{R_{TOTAL} + R_{CT}} \quad (14)$$

Tissue Damage. The rise in voltage response or the decrease in current response is often attributed in the literature to a mysterious phenomena called polarization. It is, in fact, nothing more than the transient response of a simple three-component circuit model.

When one applies pulses to an electrode-tissue interface (either for implanted or surface stimulation), the applied or resultant current initially flows into the patient via the double-layer capacitance. No reactions are associated with the capacitive flow of current and, hence, few undesirable effects exist when using short duration pulses (i.e. with a duration less than one time constant). As the pulse duration is increased, however, progressively more current flows through the parallel charge transfer resistance and the patient is more at risk due to the reaction byproducts, which is especially true if the pulse is applied for a length of time longer than five time constants giving the voltage or current response time to level off and reach its steady-state value of V_∞ (or I_∞). At this point, most of the current is flowing through the charge-transfer resistance and charge is therefore injected into the tissues via a faradaic process. The byproducts of the electrochemical reactions involved in the charge-transfer process will diffuse into the skin or tissue, causing chemical injury (19). As the leveling off of the voltage response is indicative of pure charge transfer control, this feature must be avoided at all costs by either avoiding long duration pulses or by using electrode systems with very long time constants, $T = C_{\mathrm{dl}} R_{\mathrm{CT}}$. In both cases, charge will be largely applied to the body via relatively safe capacitive processes.

It may not always be possible to use sufficiently short pulse durations to avoid tissue damage and still achieve therapeutic effect. It must also be noted that even when using short pulses where the current or voltage response has not leveled off, some current still flows through R_{CT} and a faradaic charge-transfer reaction takes place, with the associated, albeit reduced, problems (18). Over extended periods of stimulation, the byproducts will accumulate in the tissues. In the past, however, the applied waveforms found experimentally to minimize electrode and tissue damage are consistent with the basic goal of minimizing the flow of faradaic current across the electrode interface (20) and thus ensuring little, if any, net transfer of charge. Decreasing the duration, amplitude, and rate of current pulses have all been suggested as each ensures C_{dl} control of the transients and thus avoids, to some extent at least, the undesirable faradaic processes.

An alternative to using short pulse durations is to use electrode systems with long time constants [i.e., with a large value of R_{CT} (faradaic charge-transfer resistance) or C_{dl} (double-layer capacitance)]. As we have seen, noble metals react with difficulty with surrounding tissues and thus have large values of R_{CT} (19). For a given pulse duration, they tend to couple capacitively with tissue. The reactions on both anode and cathode are reversible, involving surface oxygen, and this reversibility explains the observed identical nature of anodic and cathodic waveforms (19). As a result, noble electrodes are widely used for physiological stimulation. Unfortunately, noble metals give rise to large interface impedances. From a biocompatibility point of view, one requires a noble (hence, large impedance) electrode system, whereas from an electrical performance point of view, one requires a low impedance system. A compromise is achieved by using such polarizable electrode materials and roughening the surface of the electrode, thus decreasing the large interface impedance. Roughening the electrode surface gives rise to a significant increase in the interface capacitance, thus increasing further the time constant ($T\uparrow = C_{\mathrm{dl}}\uparrow R_{\mathrm{CT}}$) and ensuring that the voltage or current response is even more dominated by the highly desirable capacitive processes while decreasing the interface impedance.

It would be a gross oversimplification to attempt to demystify biomedical electrode design by stating that all high performance biomedical electrodes simply have rough surfaces. However, a significant element of truth exists in the statement. For example, terms like activated, sintered, and porous have been used to describe implant electrodes for cardiac pacing and indicate that the electrode fabrication process results, deliberately or otherwise, in a rough-surfaced electrode. It could be argued that it is often the surface finish rather than the electrode metal that gives rise to the favorable electrical properties reported, especially the low interface impedances.

Most electrical stimulation electrodes rely, to some extent, on faradaic mechanisms at the interface between the metal and the tissue. Even in the case of noble metal electrodes with short pulse durations, byproducts of the electrochemical reactions involved will accumulate over time in the tissues when a signal is applied in one direction (monophasic) and will eventually give rise to irritation. With surface stimulation, for example, early designs of electrodes incorporated thick pads of electrolyte-impregnated lint in order to distance the patient's skin from the electrode–electrolyte interface and the undesirable byproducts. Obviously, with implanted electrodes, that short term solution is not possible.

In particular, monophasic anodic pulses must be avoided as they will cause corrosion problems. Additionally, for most applications, cathodic stimulation has a lower threshold than anodic stimulation. Even in the case of monophasic cathodic pulses, however, current flows in only one direction and the chemical reactions at the interface are not reversed.

Biphasic waveforms are preferred in most electrotherapies as the byproducts of the forward reaction are thought to be recaptured by the reverse reaction (21). In using charge balanced waveforms, it is often believed that because no net charge transfer exists across the electrode–skin interface, no net flow of potentially harmful byproducts into the skin. Unfortunately, the electrochemical reaction that occurs to enable the flow of current during the first phase is not necessarily that involved in the second. Byproducts of the first reaction are therefore not always recaptured and may escape from the interface into the patient (22). However, it must be pointed out that the use of charge balanced biphasic waveforms does indeed greatly minimize the problem and, hence, its widespread use in a range of surface and implant applications. Additionally, surface biphasic stimulation is found to be more comfortable than monophasic.

Limit Voltages and Currents of Linearity. Although the non-linearity of the skin's electrical properties has been investigated under a range of conditions, the phenomenon is still far from well understood. "There appears to be, so far, no model available which accounts for both the linear and nonlinear behavior of the electrodes in the frequency and time domains" (23). It is an important feature of an electrode as 'it appears . . . that electrodes often introduce nonlinear characteristics that are erroneously ascribed to the biological system under study (24).

Schwan proposed empirical relationships for the limit current of linearity and the limit voltage of linearity.

Limit Current of Linearity. If has been observed that electrode–tissue interface impedance nonlinear behavior is first evidenced at low frequencies. As the applied current amplitude is increased, progressively higher frequency points are affected. Schwan proposed a limit current of linearity i_L. He observed that the relationship between the angular velocity of a given impedance point and the current amplitude required to drive it into nonlinearity (deviate by more than 10% from its linear, small-signal value) was well expressed by the empirical relationship

$$i_L = B\,\omega^{\beta} \tag{15}$$

where B is a constant particular to the electrode system and β is the fractional power that appears in equation 5.

Schwan and others (25–28) have observed that this empirical relationship is valid for many electrode systems over wide frequency ranges.

The presence of β (a parameter describing the frequency dependence of the linear interface impedance) in a relationship describing the nonlinearity of the system was found most intriguing.

The solution to this mystery is quite simple when it is approached from the right direction. Generally, researchers have assumed that the observed nonlinear behavior is attributable to the high frequency Z_{CPA} impedance (Eq. 5), which they observe under linear, small-signal conditions and over the limited frequency ranges they use. However, in parallel with Z_{CPA} is the charge transfer resistance R_{CT}, which, in the linear range, has a very large value $R_{CT}{}^{0}$, where

$$R^{0}_{CT(0)} = \frac{RT}{nF}\frac{1}{i_0} \tag{16}$$

As a result, its contribution is either not observed or ignored.

The value of the charge-transfer resistance can be derived from the Butler–Volmer equation and is very nonlinear, decreasing rapidly with applied signal (ac or dc) amplitude. Compared with R_{CT}, Z_{CPA} is relatively linear. R_{CT} is therefore the source of the observed nonlinear behavior.

As the applied current amplitude is increased, the charge transfer resistance decreases rapidly, causing the diameter of the impedance locus to decrease. As the low frequency end of the arc is dominated by the charge transfer resistance, the effects of such nonlinearity will be first evidenced at these frequencies. Low frequency points are therefore the first to deviate significantly (by more than 10%) from their small-signal, linear values, as observed by Schwan and others. As the applied signal amplitude is further increased, the diameter of the impedance locus decreases further, and progressively higher frequencies are affected (29,30).

Simplistically, it can be shown that the following approximations can be made over limited ranges of frequency or applied signal amplitude:

- Approximate relationship between applied current and R_{CT}

$$i \propto 1/R_{CT} \tag{17}$$

- Approximate relationship between R_{CT} and the frequency at which nonlinearity occurs

$$R_{CT} \propto \omega^{-\beta} \tag{18}$$

Then, by cancelling R_{CT}, in the above two equations,

- Approximate relationship between applied current and the frequency at which nonlinearity occurs

$$i_L \propto \omega^{\beta} \tag{19}$$

as found by Schwan. The presence of β in the expression of an electrode system's nonlinear behavior is therefore simply due to the presence of a very nonlinear resistance in parallel with a relatively linear, frequency-dependent Z_{CPA}. A more accurate calculation based on the equivalent circuit model outlined above and the Butler–Volmer equation was published (29).

Limit Voltage of Linearity. Schwan and others (25,28) also postulated that the electrode–electrolyte interface impedance becomes nonlinear at a certain limit voltage, V_L, which they found to be independent of the frequency of the applied signal.

Using the Butler–Volmer equation and the equation for the impedance of the equivalent circuit model, the voltage limit of linearity can be calculated for a range of frequencies (31). It can be shown that the charge-transfer resistance decreases pseudo exponentially with applied voltage amplitude, initially causing low frequency impedance points on the locus to deviate from their small-signal values (32,33).

At very low frequencies, such that $\omega \to 0$, the voltage limit of linearity, V_L, approximates to the voltage at which the charge-transfer resistance decreases by 10% from its small-signal value, which occurs at $V_L = 40/n$ mV, where n is the number of electrons per molecule oxidized or reduced (31).

As the applied voltage is increased above this low frequency limiting value, the charge transfer resistance further decreases and affects progressively higher frequency points (i.e., become nonlinear). The derived log (f) versus V_L plot is found to be a straight line over a wide range of frequencies. V_L is observed to increase only very slightly with frequency, which would agree qualitatively with Onaral and Schwan's results (28), where V_L increased from 106 to only 129 mV over the frequency range of 10 mHz–100 Hz for platinum electrodes in saline, which would also explain why, in the past, V_L has been assumed constant and independent of the applied frequency.

Electrode Metals. As biocompatibility is of great importance in implants, implant electrode materials are generally confined to those that are essentially inert and do not react with the surrounding tissues. As cardiac pacing electrodes were among the first implanted and have had a long, generally successfully and well-researched history, most conclusions drawn on the suitability of materials for implant electrodes are based on pacing electrodes.

Implant electrodes are and have been generally made from noble metals such as gold, platinum, iridium, rhodium, and palladium. Platinum has been the most widely used as it has excellent corrosion resistance and produces relatively low polarization (34). Platinum, however, is mechanically relatively soft and for many applications is alloyed with much harder iridium, producing platinum-iridium. Other noble metal alloys that have been used include gold–platinum–rhodium, platinum–rhodium, and gold–palladium–rhodium.

Passive metals, such as titanium, tantalum, zirconium, tungsten, and chromium, have been successfully implanted. Titanium has been widely used because it forms a nonconducting oxide layer at the surface. This coating prevents charge transfer at the electrode interface. Titanium, therefore, exhibits a high resistance to corrosion. Stainless steel is similar in that it acquires a protective oxide layer that renders it inert. Although stainless steels were used in early pacing electrodes, they do not appear to have the required corrosion resistance for long-term use. Stainless-steel pacing electrodes were discontinued after the 1960s because of unreliable corrosion resistance (34,35).

Some early pacing electrodes were made of Elgiloy (an alloy of Fe, Ni, CO, Cr, and MO from Elgin Watch Co.) However, Elgiloy has marginal corrosion resistance and produces a relatively high polarization overvoltage. It was discontinued in the 1980s. Carbon is an inert, nonmetallic element that has similar electrochemical characteristics to noble metals and continues to be used successfully as an implant electrode. Materials such as zinc, copper, mercury, nickel, lead, copper, silver, silver chloride, iron, and mild steel have been found toxic to body tissues and are normally not used.

Biocompatibility has been defined as the ability of a material to perform with an appropriate host response in a specific application (36). Strictly speaking, no such thing as a biocompatible material exists as an implant's biocompatibility will also depend on a range of variables including its shape and surface finish.

Stimulation threshold is a key parameter in implant stimulation electrode design. When activitated vitreous carbon electrodes were first introduced in pacing electrodes, they were found to have relatively low chronic thresholds. These thresholds were thought to be the result of the superior biocompatibility of the carbon electrode. Other researchers similarly interpreted the low thresholds observed for their new exotic materials such as indium oxide, titanium nitride, and semimetal ceramics. Stokes (34), however, concluded that "material selection appears to have little or nothing to do with threshold evolution—as long as the material is biocompatible and reasonably corrosion resistant. Thus our experiments with biocompatible materials such as carbon, titanium, platinum, iridium oxide, and many more have all produced about the same results when tested as polished electrodes, all other factors held equal". Stokes went on to point out "while the bulk properties of an electrode material are important, it is the electrode-tissue interface that determines the electrode's performance. In fact, the surface microstructure of the electrode is critical" (34). It would appear that the microstructure of an electrode surface may affect cellular adhesion and activation, thus reducing the foreign body response. It is, therefore, the surface structure of many of the new materials (resulting from their fabrication process) that gives rise to the observed positive effect on threshold evolution over time, rather than the biocompatibility of the bulk material.

Another advantage of porous and microporous implant surfaces is their reduced interface impedance. Although interface impedance is generally less critical for implanted stimulation electrodes, many such electrodes (e.g., implanted pacing electrodes) are used to monitor biosignals as well as to deliver the required stimulation impulses. Decreased interface impedance helps in this regard.

Implanted biosignal monitoring electrodes require stable potentials as well as low interface impedances to minimize biosignal recording problems. These metals have high positive standard electrode potentials (E^0 in Eq. 1) and are the lowest ones on the electromotive series. As noble metal electrodes do not tend to react chemically with the electrolyte, the Nernst equation is not defined and the measured potential is often influenced more by any traces of impurities on the surface than by the intrinsic properties of the metal itself. The electrode potential can drift randomly, especially immediately following implantation. It may fluctuate widely under apparently identical circumstances, which is an inherent disadvantage of noble materials.

External biosignal monitoring electrodes can generally use high electrical performance nonnoble materials such as silver–silver chloride without fear of biocompatibility problems (2). Silver–silver chloride has been found to be an excellent electrode sensor material as, when it is in contact with a chloride gel, it has the following characteristics:

1. A low, stable electrode potential.
2. A low level of intrinsic noise.
3. A small value of charge transfer resistance (i.e., it is relatively nonpolarizable).
4. A small interface impedance.

A silver–silver chloride electrode is generally made by the deposition of a layer of silver chloride onto a silver electrode. Silver chloride is a sparingly soluble salt and, thus, effectively provides the silver electrode with a saturated silver–chloride buffer, which facilitates exchanges of charge between the silver electrode and the sodium chloride environment of the gel and human body. The system behaves as a reversible chloride ion electrode, and the Nernst potential, in this case, depends on the activity (which is closely related to concentration) of the environment chloride ions and not on that of the silver ions. The potential of this electrode is, therefore, quite stable (as well as small) when the electrode is placed in an electrolyte containing Cl as the principal anion—as is the case in the human body and electrode gels (2).

Electrical noise (potential fluctuations) can occur spontaneously at the electrode interface without any physiological input. Ag/AgCl electrodes have been shown to be particularly stable and resistant to noise (37).

A silver–silver chloride electrode has a relatively large value of exchange current density (2) (Eq. 4) and, hence, a very low value of charge transfer resistance, R_{CT}. Charge is transferred across the interface with relative ease and little voltage is dropped across the interface. The electrode therefore operates close to its equilibrium or reversible potential. Ag-AgCl electrodes are, therefore, relatively nonpolarizable.

When a smooth-surfaced electrode is chlorided, the AgCl deposit can give rise to a very rough surface and thus to relatively very low interface impedances (37,38). K, the magnitude of the interface pseudocapacitance (Eq. 5), is observed to decrease following the deposition of an AgCl layer (39). However, although AgCl facilitates the interfacial electrochemistry, it is very resistive having a resistivity of around 10^5–$10^6\ \Omega\cdot\text{cm}$ (2). As the layer thickness increases, the series resistance, R_{TOTAL} will therefore increase. This series resistance dominates the very high frequency interface impedance, and the latter will also increase with chloride deposit. Therefore, an optimal layer thickness exists, for a given frequency, that decreases the interface impedance and yet does not significantly increase the series resistance, R_{TOTAL} (29). The optimal silver chloride layer thickness consequently depends on the frequency range of interest (40).

Tin-stannous chloride, a material somewhat similar to silver–silver chloride, was used in some biosignal electrodes (41).

Electrode material and high electrical performance is generally less critical for external stimulation electrodes such as TENS and external pacing electrodes (current density distribution is the key concern). The majority of commercially available TENS electrodes are molded from an elastomer such as silicone rubber or a plastic such as ethylene vinyl acetate and loaded with electrically conductive carbon black. Mannheimer and Lampe (42) pointed out that the only tangible disadvantage with having a large electrode interface impedance is that more power will be required from the stimulator to drive the stimulating current through the electrodes into the patient.

Graphite-loaded polyesters and similar materials are used in external pacing electrodes, for example. Some are constructed using tin as the metal layer. In early electrodes, the combination of tin and the chloride-based gel gave rise to pitting of the metal. Improvements made to the gels and the use of high purity tin have effectively removed this problem.

Although silver-silver chloride has been and still is used in some external electrostimulation electrodes, it should be used with care. Silver chloride is deposited electrolytically and can therefore be either removed by the passage of current or a thicker, high resistance layer deposited, depending on the polarity of the electrode, which can be a significant problem in iontophoretic transdermal drug delivery and may cause problems in multifunction pads, which include a silver–silver chloride layer to enable distortion-free monitoring of the ECG through electrodes designed to deliver the pacing or defibrillation impulses.

The Skin

Structure of the Skin. The skin is a multi layered organ that covers and protects the body. It is made up of three principal layers—the epidermis, the dermis, and the subcutaneous layer. (*Note:* In the literature, variations exist in the terminology used to denote these layers.)

The epidermis, the outermost layer, is around 100 μm thick, depending on body site. It is the strongest layer, providing a protective barrier against the outside hostile environment. Unlike any other organ of the body, the epidermis renews itself continually. It can be subdivided into several layers, with the basal layer forming the innermost layer and the stratum corneum the outermost layer. Cells in the basal layer constantly multiply and, as they are pushed up toward the skin's external surface, the cells undergo changes. Eventually, layers of compacted, flattened, nonnucleated, dehydrated cells (called corneocytes) form the stratum corneum. These dead cells are continuously being shed and are replaced from the underlying epidermal layers. The intercellular spaces between corneocytes are occupied by arrays of bilaminar membranes with the morphological features of polar lipids (43). This matrix appears to serve to bind the cells and the stratum corneum has been described in terms of corneocyte bricks surrounded by lipid mortar (44). On average, the stratum corneum comprises around 20 cell layers thick and has a thickness of around 10–15 μm. Thickness will, however, vary with the number of cell layers making up the stratum corneum and the state of hydration. On some body areas, it can be several hundred micrometers thick. The epidermal layer is traversed by numerous skin appendages such as hair follicles, sebaceous glands, and sweat glands.

The underlying layers of the epidermis are, in contrast, a relatively aqueous environment. The transition from an essentially nonconductive, lipophilic membrane (the stratum corneum) to an aqueous tissue (viable epidermis and dermis) gives rise to the skin's barrier properties.

The dermis is the second layer of the skin and, with an approximate thickness of 2 mm, is considerably thicker than the epidermis. It is formed from a dense network of connective tissue made of collagen fibers, giving the skin much of its elasticity and strength. Embedded in the dermis are blood vessels, hair follicles, sebaceous and sweat glands, and several types of sensory nerve endings.

The final layer of the skin (the subcutaneus layer) is found beneath the dermis layer. It contains structures of connective tissues and enables the skin on most parts of the body to move freely across the underlying bone structures. It is one of the body's areas for fat storage and acts as a cushion to protect delicate organs lying beneath the skin.

Skin Impedance

Electrical Properties of the Skin. As the stratum corneum is relatively nonconductive, it presents a high impedance to the transmission of electric currents. As a result, the impedance of the skin is the largest component of the overall interelectrode impedance (Fig. 10). Nonetheless, due to the stratum corneum's dielectric properties and its thinness, it permits capacitive coupling between a conductive metal electrode placed on the skin surface and the underlying conductive tissues. One can imagine the relatively nonconductive stratum corneum sandwiched between the conductive electrode and the conductive tissues underlying the stratum corneum forming a parallel-plate capacitor. The stratum corneum's electrical impedance is, therefore, often represented by a simple capacitor, C_{SP}. (The subscript SP refers to Skin and Parallel.)



Figure 10. Schematic representation of the skin and its equivalent circuit model.

Some ions do, however, manage to cross the stratum corneum via paracellular pathways and through the skin's appendages (hair follicles, sweat ducts, sebaceous glands, imperfections in the integrity of the skin). As skin appendages extend through the stratum corneum barrier they can act as shunts to the interior. The flow of ionic current can be represented electrically by a large resistance, R_{SP}, in parallel with C_{SP}.

The underlying layers of the epidermis are, in contrast, relatively conductive and can be collectively represented by a tissue resistance, R_{Tissue}.

A simple equivalent circuit model of the overall electrode-gel-skin system is therefore shown in Fig. 10 and includes the electrode lead resistance, R_{Lead}; the electrode–gel interface impedance (the double-layer capacitance, C_{dl}, in parallel with the charge transfer resistance, R_{CT}); the gel resistance, R_{Gel}; the skin impedance (the parallel combination of a capacitance, C_{SP} and a resistance, R_{SP}), and the underlying tissue resistance, R_{Tissue}.

It must be borne in mind that this equivalent circuit model is a simplification of the rather complex electrical properties of the skin. For example, it has been found experimentally (45,46) that the capacitance of the skin is better described by an empirical, constant phase angle impedance, Z_{CPA}, where

$$Z_{CPA(S)} = K_S(j\omega)^{-\alpha} \tag{20}$$

[which is similar to the empirical expression for the pseudo capacitance often used to represent the nonideal capacitive properties of the electrode interface's double-layer capacitance (Eq. 5)].

K has units of $\Omega \cdot s^{-\alpha}$. The parameter α is constant such that $0 \leq \alpha \leq 1$. The fractional power, α, of the capacitive impedance has been found to be related to the degree of hydration of the stratum corneum (47). If the epidermal layer behaved as a simple capacitance, α would equal unity. The actual value of α, normally around 0.8–0.9, is a measure of the deviation from this ideal behavior.

The use of C_{SP} will, however, be sufficient for this present review. The lead resistance, the gel resistance, the tissue resistance, and the electrode–gel interface impedance are all relatively small in comparison with the large skin impedance. Skin impedance, therefore, generally dominates and will be studied in more depth.

The Skin's Parallel Capacitance, C_{SP}. It was suggested above that the electrode–skin interface can be approximated by a capacitor with the stratum corneum forming the dielectric layer sandwiched between the electrode and the underlying tissues that form the conductive plates. It can be seen from Eq. 2 that the skin's capacitance will increase as the thickness of the stratum corneum decreases, its dielectric constant increases, or the area of the electrode increases.

The number of cell layers in the stratum corneum can range from 12 to 30 (48). Epidermal thickness can, therefore vary greatly for different body sites within the range of about 10 to well over 100 μm (49). The stratum corneum can be, for example, as thick as 400–600 μm in the palm and plantar areas and as little as 10–20 μm on the back, legs, and abdomen (50). The value of the capacitance of the skin is related to the thickness and composition of the stratum corneum and has a typical value in the range $0.02\text{–}0.06\,\mu F \cdot cm^{-2}$ when measured using electrodes with "wet" electrolyte gels several minutes following electrode application (51,52). As the stratum corneum is typically at least 10 times as thick on the palms of the hands and soles of the feet as compared with other body areas, the skin capacitance at these points is considerably smaller than at other sites on the body. The stratum corneum on the face and scalp is not as thick as on other body parts and is characterized by large capacitance values.

Dark-skinned subjects have stratum corneum layers that are more dense and contain more layers of cells than fair-skinned subjects (48). Not surprisingly, they are characterized by skin capacitances that are much lower (skin impedances, Eq. 3, much higher) than those for fair-skinned subjects. One should therefore take care when assessing a new electrode system or associated device that they are tested on a range of subjects and skin sites. What may work well on a subject with low skin impedance in a warm and humid environment may be found later to fail on a high impedance subject, especially in a cold or dry environment.

The Skin's Parallel Resistance, R_{SP}. Although the stratum corneum does not easily allow foreign substances to traverse it, some current, carried by ions, manages to flow through it. The difficulty or resistance, this current experiences in passing through the skin is represented in the equivalent circuit (Fig. 10) by the parallel resistance, R_{SP}.

The skin's resistance is highly dependent on the presence and activity of sweat glands and on the presence of other appendageal pathways. An average human skin surface is believed to contain between 200 and 250 sweat ducts on every square centimeter (53). The density of sweat glands varies greatly over the body surface with a value of approximately 370 per cm^2 on the palms of the hands and the soles of the feet and a value of approximately 160 per cm^2 on the forearm (49). The diameter of the ducts can range from 5 to 20 μm. It is, therefore, not surprising that R_{SP} is reported to vary greatly from patient to patient, from body site-to-body site, and with time. The measured values of R_{SP} are much smaller on areas with high densities of sweat glands, such as the palms of the hands (in spite of the thicker stratum corneum layer), especially when the glands are active in response to thermal or psychophysiological stimuli.

An average human skin surface is reported to contain between 40 and 70 hair follicles per square centimeter (53). The presence of a high density of hair follicles (which act as low resistance shunts) gives rise to a very low value of skin parallel resistance, R_{SP}. However, this observation is counterbalanced by the difficulty in making firm mechanical and electrical contact to hirsute body sites or patients. In such cases, the skin impedance is very large at best. Generally, the electrodes fall off and, hence, require the shaving of the skin site prior to electrode application.

Observed intersite and interpatient variations in skin impedance tend to be due to large variations in R_{SP}. In the low frequency range, dominated by R_{SP}, regional differences in skin impedance were observed by Rothman (54), Lawler et al. (55), and Rosell et al. (56). Low frequency skin impedance was observed to decrease in the following order: thumb, forearm, abdomen and, smallest of all, forehead. Similarily, Almasi and Schmitt (57) observed the low frequency skin (10 Hz) impedance to decrease in the order of outer forearm, leg, inner forearm, back, chest, earlobes, and forehead. The forehead appears to have a very low skin impedance value (58), presumably as a result of the stratum corneum on the face and scalp being thinner than that on other body parts (48) and the presence of a high density of sweat glands. Almasi and Schmitt (57) plotted their average impedance values for the body sites on a complex impedance plot and found that most of the points lay along a "smooth common locus of monotonically increasing phase angle and impedance magnitude." This behavior was successfully interpreted by McAdams and Jossinet (32), who showed that such frequency loci were formed when the skin's parallel resistance varied greatly from site to site while the skin's capacitance remained relatively constant. Two body sites did not fit the locus and, hence, the physical explanation; these sites were the palm and fingertips. These body sites have much larger epidermal thicknesses and, hence, have skin capacitance values much smaller than other body sites.

One must be very careful when assessing different electrode designs or gels. Testing different electrodes on different patients is certain to give misleading results due to the intersubject variations, unless, of course, large numbers of subjects are used and statistically significant differences are observed.

R_{SP} varies greatly over time due to a number of parameters including room temperature and psychophysiological stimuli. The latter effect is exploited in so-called lie detectors. Schmitt and Almasi (59) reported that a considerable daily variation exists in a given subject, and seasonal changes have also been reported (60). Testing a range of electrodes on the same subject but on different days is, therefore, not optimal either, as day-to-day variations in skin impedance, especially fluctuations in R_{SP}, will nullify the validity of this approach. For example, Searle and Kirkup (61) found that the diurnal variations on a given subject for a given electrode was much larger than any difference between the range of electrode designs they tested in any one recording session. It should be further noted that the electrode test sites should be allowed to recover for several days between experiments to enable the skin to recover. For example, pealing off an adhesive electrode will remove some of the underlying stratum corneum. Any electrode subsequently tested on the site will benefit from this prior skin stripping (see below).

Electrode designs must, therefore, be compared *in vivo* by testing them at the same time on the same subject. One must still bear in mind the significant differences in skin impedance that exist over the subject's body, as outlined above. Even testing the electrodes at the same time on a limb of a given subject remains problematic. The different skin sites involved, even if located close together, will give rise to significant differences in the measured electrode–skin impedances, which may be wrongly attributed to the electrode designs or gels under test. Searle and Kirkup (61), for example, showed that testing a range of dry electrode metals on the inner forearm gave rise to potentially very misleading results. Electrodes placed closer to the wrist gave rise to lower impedances due to the presence of a higher concentration of sweat glands.

Electrodes must therefore be repeatedly tested at the same time, under the same conditions, varying their relative positions in order to clearly establish their relative performances. McAdams et al. developed a four-channel impedance monitoring system to enable the simultaneous comparison of electrode designs/gels (62).

Skin Potential Motion Artifact. A potential difference E_{S}, given by the Nernst equation, exists across the epidermis as a result of ionic concentration differences. This potential varies from patient to patient, from site to site, and depends on gel composition (if used) and skin condition.

The skin surface is normally negative with respect to the inside of the body. Skin potential becomes more negative when sweat glands are active, and palmer and plantar surfaces, with their higher sweat gland concentrations, are the most negative. Increasing gel concentrations of NaCl or KCl also render the site more negative. The parameter E_{S} has a typical value of 15–30 mV (63).

The dependence of the skin potential on the thickness of the epidermal layer is important to many ECG recording applications. If the thickness of the layer is changed by stretching or pressing down on the skin, the skin potential can vary by 5–10 mV compared with, for example, the 1 or 2 mV ECG signal. As these fluctuations generally result from patient movement, they are termed motion artifact. Motion or skin-deformation artifact is a serious problem during exercise cardiac stress testing of patients on treadmills or exercise bicycles, during ambulatory monitoring, and while monitoring patients lying in bed (64,65) (Fig. 11).



Figure 11. Disturbance of biosignal due to patient movement. (Redrawn from Ref. 65.)

Abrading or puncturing the skin is often used in stress testing to remove or bypass the problem source. Although skin potential increases with gel concentration, artifact gradually decreases with time as the conductive electrode gel soaks into the skin and renders the stratum corneum more conductive. High concentration gels are often used for short-term diagnostic applications where the risk of skin irritation is outweighed by the need for clear traces.

In general, hydrogel-based electrodes (see below) should not be used for stress testing or in other monitoring applications that are likely to suffer motion artifact problems. Hydrogels tend not to hydrate the skin and, hence, do not actively attack the source of the problem. The same comment applies for dry (gel-less) electrodes.

In stress testing and ambulatory event monitoring, modified electrode locations are used to avoid muscular or flabby areas of the body and thus minimize skin-deformation (and EMG) artifact. Stress loops are formed in the connecting leads, which are taped to the patient and used to avoid direct pull on electrodes and the underlying skin. The use of foam-backed electrodes tends to absorb any pull on the electrode and minimizes artifact.

Electrode Gels and Their Effects. Dry electrodes are successfully used in some monitoring applications. Suitably designed gel-less electrodes have advantages when used in the home environment where the patient may not remember or have the time to apply gel electrodes prior to use (66).

For many home-based monitoring applications, electrodes are manufactured from noncorroding materials such as stainless steel, which can be repeatedly washed and reused. Unfortunately, such polarizable materials give rise to poor electrical performances. In order to ensure good, stable electrode potentials, silver–silver chloride electrodes should be used (see below).

Jossinet and McAdams (67) demonstrated that the impedance of a dry electrode decreases pseudoexponentially due to the gradual buildup of sweat under an occlusive, gel-less electrode and the resultant progressive hydration of the underlying skin. Searle and Kirkup (61) reported that the decrease in skin impedance of dry electrodes is polyexponential and requires two time constants, one very short ($\sim$45 s) and the other almost 10 times longer ($\sim$450 s), possibly indicating two different processes at work.

Given that the surface of the skin is irregular, a flat dry electrode will initially only make contact with a few ‘peaks’ on the skin surface. Therefore, a smaller effective contact area exists than one would otherwise expect. However, as sweat builds up under the occlusive, dry electrode, a better contact with the skin will result in a relatively rapid increase in the measured value of C_{SP}. Human sweat contains a small amount of sodium chloride [$\sim$0.1–0.4% NaCl (49)], and hence serves as a weak electrolyte. It is suggested by the author that this accounts for the shorter time constant. (The longer time constant is probably indicative of the progressive hydration on the underlying skin resulting in a gradual decrease in R_{SP}.) As will be outlined below, R_{SP} is observed to decrease with a time constant of around 10 min in the presence of an electrolyte gel, which agrees quite well with the 7.5 min observed by Searle and Kirkup (61).

Before leaving gel-less electrodes, it should be pointed out that in certain applications that employ very high frequency signals, such as electrical impedance tomography (EIT), the use of a gel pad may not be needed as it will contribute a small but significant contact resistance to the desired measurement (5). In such instances, the use of a very thin spray of moisture onto the electrode surface prior to its firm application to the patient’s skin may be all that is required. Profiled dry electrodes firmly pressed onto the skin may also be adequate for certain home-based biosignal applications. If skin impedance is a problem with standard button electrode designs, this can be addressed by increasing the electrode area in the noncritical axis. For example, long, narrow, dry electrodes are used for precordial ECG recording, which enable a large contact area while ensuring sufficient interelectrode distances on the chest (66).

Electrode gels serve (*1*) to ensure a good electrical contact between the electrode and the patient’s skin, (*2*) to facilitate the transfer of charge at the electrode-electrolyte interface between the two kinds of charge carrier (electrons in the electrode and ions in the gel), and (*3*) to decrease the large impedance of the stratum corneum.

Two main types of electrode gel exist, viz. wet gels (often described as pastes, creams, or jellies) and hydrogels.

Wet gels are generally composed of water, a thickening agent, a bactericide/fungicide, an ionic salt, and a surfactant (68). The ionic salt is present to achieve the appropriate electrical conductivity of the gel, which will depend on the specific application. As the major portion of ions present in tissue fluids and sweat are sodium, potassium, and chloride (Cl^-), in order to ensure biocompatibility, the ionic salts most commonly used in electrode gels are NaCl (sodium chloride) and KCl (potassium chloride). High concentrations of these salts tend to be better tolerated by the body than other salts. The ions in the gel serve not only to ensure electrical conductivity of the gel but to decrease the skin impedance by diffusing into the skin due to the existing concentration gradient. A relatively high concentration of electrolyte will also decrease the value of the charge transfer resistance (thus rendering the electrode more nonpolarizable).

When a standard pregelled wet electrode is applied to the skin, the gel rapidly fills up the troughs on the electrode and skin surfaces, thus ensuring maximum effective contact area. The skin capacitance, C_{SP}, is therefore observed to initially increase rapidly in value following electrode application and then to remain relatively constant (32). [A similar effect was probably noticed by Searle and Kirkup (61) as a result of sweat accumulation under a dry occlusive electrode.] Although C_{SP} does not exhibit a strong time dependence, it does vary with the electrolyte composition and concentration (49), increasing with increasing concentration (69).

Following electrode application, the skin’s parallel resistance, R_{P}, generally decreases with time in a pseudo exponential manner as the ions in the gel diffuse through the skin rendering it more conductive (32,70) (see Fig. 12).



Figure 12. Variation of skin resistance with time for a range of gel concentrations and skin preparation techniques (1).



Figure 13. Variation of skin resistance with time for a hydrogel-based electrode. Fluctuations are due to variations in subjects state of relaxation/arousal (32).

It has been observed, however, that when a cold gel is applied to a skin site, the measured value of R_{SP} is observed to initially increase (32,56), which is attributed to the cold gel causing the sweat pores to contract. Once the gel and skin has warmed up, the value of R_{SP} is observed to decrease as the electrolyte ions diffuse through the epidermal layer.

The skin temperature effect should be borne in mind when assessing a range of electrode designs. If, for example, the patient/subject removes his/her shirt just before the tests, the electrodes tested at the start of the experiment will have an advantage (i.e., smaller skin impedance) over those tested later as the uncovered skin sites will gradually cool down with time following removal of the shirt. Meaningful *in vivo* assessment of electrodes is not straightforward, and wrong conclusions can very easily be made by the unaware or the unscrupulous.

The time constant for the skin's parallel resistance, R_{SP}, appears to be inversely proportional to the concentration of the gel. The decay has a time constant of around 10 min (1), thus indicating that it takes almost 1 h for the electrode-skin impedance to decrease to its lowest value. For example, 50/60 Hz interference, linked to mismatch of electrode-skin impedances, is often observed experimentally to decrease with time. One should, therefore, where possible, apply the electrodes to the patient first, for example, before setting up the rest of the measurement system, to enable the skin impedance to decrease as much as possible.

High salt concentrations give rise to a more rapid diffusion of ions into the skin and a more rapid decrease in the skin's parallel resistance, R_{SP} (1,32) (Fig. 13). Such aggressive gels tend to be used in short-term biosignal monitoring applications such as stress testing, where instant, high quality traces are required (71). Biological tissues cannot tolerate long-term exposure to salt concentrations, which depart significantly from physiological levels [~0.9% NaCl for body fluids and around 0.1–0.4% NaCl for human sweat (49)]. Aggressive gels (5% NaCl) should not be used, for example, for the long-term monitoring of bed-ridden patients or for the monitoring of neonates. In the latter case, the incompletely formed skin is very susceptible to skin irritation problems. In any monitoring application, aggressive gels should not be used in combination with skin abrasion (see below). It is especially to be avoided in longer term monitoring applications where the removal of the body's defensive barrier coupled with the long-term exposure to an aggressive gel will lead to sever discomfort to the patient.

The second kind of electrode gel commonly used in electrode systems are hydrogels. Hydrogel-based electrodes have recently become popular for numerous biomedical applications including resting ECG. Hydrogels are solid gels, which originally incorporated natural hydrocolloids (e.g., Karaya gum a polysaccharide obtained from a tree found in India) (68). The use of natural hydrocolloids give rise to variable performances and, in some cases, an unattractive color. Synthetic (e.g., polyvinyl pyrrolidone) hydrocolloids are now widely used.

The use of such solid gels entails numerous advantages when they are used in conjunction with screen-printing or similar technologies. The use of an adhesive hydrogel pad dispenses with the need of the standard gel-impregnated sponge, gel- retaining ring, and surrounding disk of adhesive foam that are used in wet-gel electrode designs. It is possible to construct thin, lightweight, highly flexible electrode arrays with accurately defined electrode/gel areas, shapes, and interelectrode distances (72,73).

Hydrogels also tend to cause less skin irritation compared with wet gels. A simplistic explanation of the advantageous/disadvantageous features of hydrogels is that hydrogel serves principally to ensure a good electrical contact between the skin and the electrode and that they do not significantly affect (compared with wet gels) the properties of the stratum corneum.

The impedance of the gel layer can be represented by a simple resi stance in series with the impedances of the skin and the electrode plate–electrolyte interface. The magnitude of the gel resistance will depend on the composition and concentration of the gel and on the dimensions of the gel layer. Hydrogels are generally more resistive than wet gels. Typical resistivities for wet gels are of the order of 5–500 Ω·cm (the higher the salt concentration, the lower the resistivity) compared with 800–8000 Ω·cm for hydrogels (the higher resistivity hydrogels tend to be used in cardiac pacing electrodes). Wet ECG electrodes, for example, have a gel layer thickness of around 0.3 cm and typical areas of 3 cm^2. The resistance of a wet gel layer is, therefore, generally in the range 0.5–50 Ω. Although hydrogels have higher resistivities, this disadvantage is generally compensated for by the use of larger gel areas, which need not necessarily entail the use of a larger overall electrode area as the adhesive hydrogel may not require the use of a large surrounding disk of adhesive foam. Another way to compensate for hydrogel's inherent disadvantage is to decrease the gel layer thickness, a variable generally ignored in electrode design even though it can have a significant effect on electrical performances. Many commercial hydrogels used in biosignal monitoring electrodes have layer thicknesses of around 1 mm (compared with around 3 mm for pregelled wet electrodes) and, coupled with larger areas of around 7 cm^2, can lead to hydrogel pad resistances in the range 10–100 Ω (5).

It is suggested that further improvements can be made to the performances of hydrogel electrodes (and wet electrodes) by the use of even thinner gel layers. It must be borne in mind that gel-layer resistance is not solely determined by the dimensions and properties of the gel pad. When a large area gel pad is used in conjunction with a small area sensor, the dimensions of the smaller sensor will largely determine the magnitude of the gel-layer resistance, the overlapping section of gel pad carrying relatively little current, which is important in both biosignal monitoring and electrostimulation applications.

Hydrogels, being hydrophilic, are used for wound dressings in order to absorb exudate. They are, therefore, poor at hydrating the skin and will even absorb surface moisture. With hydrogel electrodes, R_{SP} is observed to fluctuate with sweat gland activity and the subject's state of mental arousal, decreasing during increased activity and gradually increasing again as the hydrogel absorbs the excess surface moisture (74,75). In contrast, C_{SP} remains relatively constant after a slight initial increase (32).

Hydrogels are therefore not only more resistive than wet gels, but they hydrate the skin less effectively and give rise to higher skin impedances (i.e., higher values of R_{SP} and lower values of C_{SP}). Typical values of R_{SP} for hydrogels can be as high as 15 MΩ·cm^2 compared with a high of 5 MΩ·cm^2 for wet gels (75). Once again, this disadvantage can be overcome, at least partially, by the use of larger hydrogel pad areas. An additional way of increasing the value of C_{SP} is the use of thinner hydrogel pads (32).

Skin Preparation Techniques. In the clinical environment, the skin site is often degreased using an alcohol wipe prior to electrode application, which probably removes some of the loose, outermost cells of the stratum corneum and the poorly conducting lipid substances from the surface of the skin (55). However, the use of alcohol wipes may initially increase the impedance of the skin by dehydrating the outer layers of the skin (76). Motion artifact also may increase initially following application of alcohol to the skin (64). When wet gel electrodes are applied to alcohol-wiped skin, the gel will eventually penetrate the degreased skin more readily once the electrode has been on the skin for several minutes, leading to a more rapid decrease in skin impedance and possibly to a decrease in motion artifact, which may not be the case, however, in the case of hydrogel electrodes, which do not actively hydrate the skin. The use of an alcohol wipe accompanied by vigorous rubbing should result in low initial impedances due to the additional mild abrasion.

A related method of rapidly decreasing skin impedance is to prerub the skin site with a high concentration electrolyte, thus forcing the gel into the outer layers of the skin, resulting as in a significant decrease in R_{SP} (Fig. 12) and an increase in C_{SP}, especially when accompanied by vigorous rubbing. Arbo-prep cream is supplied for this purpose and it is claimed to reduce skin resistance by up to 90% (from 40 or 50 to 4 or 5 kΩ, according to an advertisement). Some commercial gels such as Hewlett-Packard's Redox paste contain abrasives such as crushed quartz, which, when rubbed into the skin prior to electrode application, greatly reduce skin impedance. Such aggressive gels should only be used in short-term biosignal monitoring applications such as stress testing where high quality traces are required.

The outer layers of the stratum corneum can also be removed by rubbing the skin with abrasive pads especially designed for this purpose, which can give rise to a major decrease in R_{SP} (Fig. 12) and an increase in C_{SP}.

Unomedical, for example, markets a small disposable skin preparation abrasive pad that, when adhered to the finger tip, can be used to dramatically reduce skin impedance. A Skin Rasp, which resembles a strip of Velcro, is marketed by Medicotest for this purpose. The Quinton Quick-Prep Applicator, rotates the abrasive center of the Quick-Prep electrodes, causing a marked decrease in skin impedance. ECG electrodes are often supplied with abrasive pads built into the electrode release backing.

In skin stripping, the stratum corneum is progressively removed by repeatedly applying and removing adhesive tape to and from the skin (55,77). Skin stripping can greatly decrease skin impedance as a consequence of a dramatic decrease in the value of R_{SP} and an increase in C_{SP}. As the outermost layers of the stratum corneum are the most resistive, the most significant decrease in skin impedance is achieved with the first few strippings (77). Therefore, no need exists for the complete removal of the stratum corneum, which would obviously be clinically unacceptable due to the discomfort (pain, bleeding, or irritation) caused to the patient during and following the recording. The more the skin is abraded for a given gel composition, the sooner discomfort develops and the more severe the irritation. The level of irritation also varies with the salt concentration and the additives present in the gel.

As pointed out above, abrading or stripping the skin is often used in stress testing to decrease motion artifact (63) as well as the 50/60 Hz noise induced by any mismatch of the contact impedances. High concentration gels are also often used for such demanding applications, rapidly soaking the skin and, thus, effectively removing the source of the problem.

The use of both skin abrasion/stripping and an aggressive gel will, however, maximize the potential for severe skin irritation problems. These approaches should not be used together. Even with the use of mild gels, it is probably unwise to abrade the skin for long-term monitoring applications. The increased length of exposure of the abraded skin to the gel will be conducive to skin irritation. Somewhat surprisingly, long-term monitoring electrodes are sometimes commercially supplied with integral abrasive pads, which is not only risky but probably unnecessary as the use of a suitable mild gel would eventually decrease the skin impedance without the need for skin abrasion.

ELECTRODE DESIGN

External Biosignal Monitoring Electrodes

Historical Background. In 1887, Augustus Waller, using Etienne Jules Marey's modification of the capillary electrometer, obtained surface ECGs (as opposed to recording directly from the exposed heart of an animal) of one of his patients, 'Jimmy'. The patient turned out to be his pet dog. Waller used two buckets of saline to measure the canine ECG, one for the front paws and one for the hind paws (78–80).

Waller eventually succeeded in recording the first human ECG in 1887 using the capillary electrometer (Fig. 14) (81). However, he initially concluded "I do not imagine that electrocardiography is likely to find any very extensive use in the hospital. It can at most be of rare and occasional use to afford a record of some rare anomaly of cardiac action" (82).

It was, therefore, left to a more visionary and tenacious Dutchman, Willem Einthoven, to establish the clinical relevance of this strange new trace and to develop and commercialize a clinically acceptable system based on the string galvanometer. Einthoven's achievement was truly awesome. However, it must be pointed out that he did build (very significantly, it is conceded) on the work of earlier pioneers. The electrode system used, for example, was Waller's bucket electrode, whereas the moving photographic plate recording technique was originated by Marey (83).


Figure 14. Human subject connected to capillary electrometer via large area bucket electrodes (81).


Figure 15. Early commercial ECG machine and electrodes (84).

The input impedance of Einthoven's galvanometer was such that very low contact impedances were necessary, hence, the very large bucket electrodes (Fig. 15) (84). Obviously, the range of applications was somewhat limited.

Realistically, only one's limbs could be conveniently placed into the buckets. Hence, the use of limb leads exists in electrocardiograpghy, even to the present day. It is, therefore, important to note several points. Present state-of-the-art is often based on historical quirks rather than on a profound scientific basis. The monitoring device and amplifier determined the electrode size, design, and location of the electrodes, which in turn determined the clinical application and the presentation of the physiological data.

Einthoven's device in its early form could not be used for the monitoring of bed-ridden patients or for ambulatory monitoring. These applications had to wait for improvements to be made to the amplifiers, which then enabled the use of smaller electrodes that could be more conveniently attached in other anatomical locations. However, the early monitoring locations and the form of the signals observed became accepted as standard and there is often considerable resistance to novel monitoring scenarios (e.g., smart clothing), which require or are based on different lead systems and present physiological data in a different format to that familiar to the clinician.

In the 1920s vacuum tubes were used to amplify the electrocardiogram instead of the mechanical amplification of the string galvanometer, which lead to smaller, more rugged systems that were transportable (Fig. 16) (84). The input impedances of the new ECG monitors were larger, and the large metal buckets could be replaced by smaller metal-plate electrodes (still large compared with present-day electrodes) (83). These advances enabled bedside monitoring, and, by the 1930s, some ECG devices could be carried to the patient's home. Not unsurprisingly, the new plate electrodes were attached to the limbs, both for historical and practical reasons. The metals used were chosen for their availability and ease of machining (Fig. 17). They included German silver, nickel-silver,



Figure 16. Mobile ECG used to monitor bed-ridden patient in hospital ward circ. 1920 (84).



Figure 17. Metal plate limb electrode.

and nickel-plated steel. The foil plates were used in conjunction with moistened pads of paper toweling, lint, cotton gauze, or sponge and were generally held in place with rubber straps. Around 1935, conductive gels were developed to replace the soaked pads. A wide range of gel ingredients were assessed, and it was noticed that the presence of an abrasive in the gel greatly reduced the skin impedance (5).

They also noted that slightly abrading the skin before applying the electrolyte helped achieve very low skin impedances.

A dry version of the plate electrode was reported by Lewes (85). The multipoint stainless-plate electrode resembled a large nutmeg grater that penetrated the skin when firmly strapped onto the limb or applied to the skin with a slight rotary movement, thus resulting in a very significant reduction in skin impedance.

Modern versions of the limb plate electrode still exist. Some have a convenient spring clip mechanism, which dispenses with the need for the rubber strap.

In the 1930s, clinicians, some using electrodes held on the chest by the patient himself or by another member of clinical staff, experimented with precordial leads and established their clinical value (86). In 1938, the American Heart Association and the Cardiac Society of Great Britain defined the standard positions and wiring of chest leads V1–V6 (87).

Research then focused on the development of electrodes that could be conveniently attached to the chest to enable convenient routine clinical measurements. Several designs involved a rubber bulb, which was used to create suction sufficient to hold the metal electrode on the chest. One of the first suction electrodes was developed by Rudolph Burger in 1932 for the precordial leads (88). The suction electrode shown in Fig. 18a (85,89) is one developed by Ungerleider (89). Another more recent system incorporated the multipoint electrode of Lewes (85) into the suction head (Fig. 18b). The most popular suction electrode design, widely used around the world and still in use today, was developed by Welch (90) and often called the Welch or Suction cup/bulb electrode (Fig. 19) (3). It consists of a hollow, metallic, cylindrical electrode that makes contact with the skin at its base. A rubber suction bulb fits over the other end of the cylinder. The suction bulb was squeezed while the electrode was held against the skin. Upon releasing the bulb, the electrode is held in place. The suction electrode can be used anywhere on the chest and can even be used on hairy subjects. A single electrode can, if necessary, be used to take a measurement at a given location and then moved to another site.

Although the Welch cup electrode became widely used as a precordial electrode, it could only be realistically used for resting (supine) diagnostic ECG recording. The weight and bulk of the electrode generally rules out its use on upright, ambulatory, or clothed subjects. Since then, more suitable, lightweight, low profile suction electrodes have been developed that are pneumatically connected to remote vacuum pumps (37). Some arrays of suction electrodes are commercially available, for example, for use with exercise bicycles for cardiac stress testing (72).

A method had to be invented to attach small disks of suitable metal and their conductive gel coating to a patient's chest (in the case of ECG) or to other body parts in the case of other biosignal applications, such as EEG and EMG. Simply taping a metal disk to the skin site with a sandwiched gel layer was a method often used (91).



Figure 18. Early designs of suction precordial electrode (a) Ungerleider (89). (b) Lewes (85).



Figure 19. A metallic suction electrode is often used as a precordial electrode on clinical electrocardiographs (3).

Conically formed metal disk electrodes were and often still are used for EEG recordings (Fig. 20). The base of the metal cone is attached to the patient's scalp using elastic bandages, wire mesh, or more recently, using a strong adhesive such as colloidon. Aperture exists in the apex of the cone to enable the introduction into the recessed electrode of electrolyte gel or to enable the abrasion of the underlying skin by means of a blunt hypodermic needle. The cone electrodes were often made of gold as it has high conductivity and inertness, desirable in reusable electrodes. More recently, Ag/AgCl has been used.

Early plate electrode designs were presumably very messy and gave rise to considerable artifact problems. The observed artifacts were attributed to disturbance of the double-layer region at the electrode/skin (or, more precisely, electrode/electrolyte) interface [termed the electrokinetic effect by Khan and Greatbatch (94)]. When the electrode moves with respect to the electrolyte, the distribution of the double layer of charge on electrode interface was thought to change and cause transient fluctuations in the half cell potential or give rise to a streaming potential.

Recessed or floating electrodes were introduced in an effort to protect the electrode–gel interface from such mechanical disturbance and resultant movement artifact. A metal disk was recessed in a plastic housing that was filled with electrolyte gel prior to application to the patient. The top hat-shaped container was adhered to the skin by means of an annulus of double-sided adhesive tape, (Fig. 21) (3). Later a gel-impregnated sponge was used to ensure good electrical contact between the electrode disk and the skin surface. The electrode disk was, therefore, not in direct contact with the skin, which was found to reduce motion artifact. At first, various metal plates were used as the electrode conductor, then a sintered Ag/AgCl disk with preattached wire ensured better performances for more demanding applications.



Figure 20. Conically formed metal disk EEG electrodes.



Figure 21. Examples of a floating or recessed biosignal electrode. (a) Recessed electrode with top-hat structure. (b) Cross-sectional view of the electrode in (a)(3).

Modern Disposable Electrodes. The top hat housing was eventually replaced with a smaller retaining ring or plastic cup and the electrode was held in place by means of a surrounding disk of adhesive foam. The plastic cup holds the gel-impregnated sponge in place and stops the gel from spreading beyond the set boundary, either during storage or use on the patient. Low cost Ag/AgCl-plated plastic eyelets (part of a snap fastener) are used in these disposable electrodes and the leads are connected to the electrodes via the electrodes' snap fastener studs. The rigid retaining ring was, however, uncomfortable as it did not allow the electrode to conform optimally to body contours. It was eventually removed in many modern disposable electrodes and the recess is now often formed by a hole in the adhesive foam layer. The backing label serves to hold the snap and eyelet in place as well as to present the company's logo (Fig. 22). The resultant electrode structure is much more flexible and more comfortable to wear.

The use of a snap fastener-style connection in disposable electrodes has one significant drawback for certain applications. The male stud protruding from the back of the electrode and the female connector required on the connecting lead results in a relatively heavy, large-profile electrode/connector interface, which is less than optimal for applications such as neonatal and pediatric monitoring. The use of such electrodes in long-term monitoring of bedridden patents could lead to considerable discomfort and the heavy connection could also give rise to significant motion artifact problems. The integrated lead design seeks to overcome these disadvantages. A thin, highly flexible lead wire is bonded directly to the back of a specially designed Ag/AgCl-coated eyelet, which results in a very low profile, lightweight electrode-connector system much used in neonatal and pediatric monitoring and attractive for long-term monitoring applications (Fig. 23).



Figure 22. Modern wet gel disposable electrode. (Courtesy of Unomedical A/S.)

In an effort to decrease motion artifact, many electrode designs feature an offset center. The connector, often in the form of a snap fastener, is separated from the gelled sensor by a strip of metal or similar conductive layer. The connector is thus 1 or 2 cm away from the metal–gel–skin interface, and it is possible to connect the lead to the electrode or to pull on the connector without pulling directly on the gelled, skin site, thus causing artifact problems. This design appears well suited for stress testing applications although arguably less so for long-term monitoring of bed-ridden patients due to the bulky connector. The invention was patented by Manley (93) and the concept has been commercially exploited very successfully by Ambu A/S.



Figure 23. (a) Specially designed Ag/AgCl-coated eyelet with bonded lead. (b) Low profile, lightweight pediatric electrode with bonded lead. (Courtesy of Unomedical A/S.)



Figure 24. An example of an off-set connector electrode. (Courtesy of Unomedical A/S.)

More recently, many other manufactures supply electrodes with offset connectors (Fig. 24). Leadlock have developed an electrode that incorporates a slit in the foam backing. Once the electrode has been applied to the patient and the lead connected to it, part of the foam backing is used tape down the lead, locking it in place and minimizing direct pull on the connector and underlying electrode/skin interface.

A wide range of backing materials now exists, and some are better suited for specific monitoring applications, types of patients, skin types, and so on. Given the great variety of materials, adhesives, and designs used, the following comments are generalizations.

Open-cell foam layers, made from a plastic such as polyethylene, are much used and have thicknesses typically in the range 1–2 mm. They have a 10–100 μm coating of a pressure-sensitive adhesive, generally a polymeric hydrophobic substance (68,94). Adhesive foams generally give rise to firm adhesion, are resistant to liquids, and tend to cushion lead pull, thus giving rise to less artifact. They are, therefore, generally well-suited to cardiac stress testing and similar applications. However, as they are occlusive and generally have a relatively aggressive adhesive, they can give rise to more skin irritation and they must be used with caution for neonatal and long-term monitoring.

Porous, breathable layers, such as nonwoven clothes or tapes, have the advantages of being soft, stretchable, and conformable with the skin. (*Note:* The term micropore, although sometimes used loosely to describe any breathable backing material, is strictly a 3M product.) Porous layers tend to cause less mechanically induced trauma to the skin, which can occur with more rigid materials and is due to shearing of underlying skin layers. As they are highly air permeable and use milder adhesives, porous tapes cause less skin irritation and are well suited for long-term monitoring. Larger backing areas tend to be required. The gelled center can, however, pull away from the skin as a result of the stretchable backing. Ambu A/S use a central ring of adhesive around the gelled eyelet to minimize this problem.

As we have already seen, wet (as opposed to solid gels) vary in composition and concentration depending on the application. Aggressive gels with higher concentrations of electrolyte or including abrasive particles are used for short-term, demanding monitoring applications such as cardiac stress testing. Mild gels are used in pediatric and neonatal applications due to the increased vulnerability of the patient's skin. It should be noted that no matter how hypoallergenic a gel or an adhesive is claimed to be, some patients will experience some form of skin reaction to one of the components.

Solid Conductive Adhesive Electrodes. The growing monitoring market has led to the development of even lower-cost disposable electrodes. Solid conductive adhesive or hydrogel electrodes were first introduced by LecTec Corp around 1980 (95). Hydrogels are composed of a hydrocolloid, alcohol, a conductive salt, water, and a preservative. The hydrocolloid use can be either natural (e.g., Karaya gum) or synthetic (e.g., polyvinyl pyrrolidone) (68). Early hydrogel electrodes were based on the natural hydrocolloid, Karaya, which comes from the bark of a tree. The rather unaesthetic appearance of these early gels and the variations in their electrical and mechanical properties limited their widespread acceptance. The use of synthetic hydocolloids, with their more attractive appearance and performances, has led to the recent revolution in electrode design.

Solid adhesive gels reduce the number of electrode parts required, dispensing with the need of a gel-impregnated sponge or a surrounding disk of adhesive tape, which gives rise to small-area, low profile electrodes suitable for neonatal monitoring, especially when coupled with integrated leads as discussed above (Fig. 23b).

Tab solid adhesive electrodes are now widely used for many biosignal monitoring (and stimulation) applications. Thin, highly flexible metallic/conductive foils or printed conductive ink layers are laminated with solid, adhesive hydrogels. A section of the foil or printed layer is left uncovered. Once the electrodes are cut out, the exposed conductive tab acts as a means of connection, the leads being connected via alligator clips (Fig. 25). Electrode design is therefore very simple and manufacturing costs are low. These flexible, low profile electrodes are best used for short-term, resting diagnostic monitoring. Tab electrodes are not suitable for ambulatory or long-term monitoring as the tab connection will cause the electrode to peal off quite easily when pulled from any angle other than directly downward. Also, hydrogels are hydrophilic and tend to absorb moisture, lose their adhesive properties over time, and fall off the patient if an additional adhesive backing is not used. Hydrogels, being solid, do not leave a messy residue on the skin requiring cleaning. Tab electrodes are also repositionable and are reuseable (on the same patient!) in certain home monitoring applications.

When used with an adhesive backing layer, the hydrophilic hydrogels tend to be relatively nondrying (a significant problem with pregelled wet electrodes) and their electrical properties may even improve as they absorb moisture. As they do not actively hydrate or otherwise affect the skin, they tend to be relatively nonirritating compared with wet gels.



Figure 25. Hydrogel-based tab electrode with connector. (Courtesy of Unomedical A/S.)

Some disadvantages exist, however, associated with hydogels. Hydrogels are more resistive than wet gels and, hence, the gel pad resistance will be higher, which can be compensated for by using larger hydrogel pad areas and thinner layer thicknesses as compared with those used with wet gels. Although the area of the solid adhesive gel in a tab electrode, for example, is considerably larger for this reason than that in a standard disposable wet gelled electrode, the absence of a surrounding adhesive layer results in the tab electrode having a smaller overall area.

Hydrogels, being hydrophilic, are poor at hydrating the skin and may even absorb surface moisture. They, therefore, give rise to larger skin impedances. This disadvantage can also be overcome, at least partially, by the use of larger hydrogel pad areas. Hydrogels are also more expensive than wet gels but generally lead to less expensive electrodes due to the simpler designs involved.

Hydrogels are more sensitive to motion artifact as they do not actively hydrate the skin. They are, therefore, not well-suited for stress testing.

The use of such solid gels entails numerous advantages when they are used in conjunction with screen printing technology (73,96), especially for body surface mapping and similar applications. It is possible to construct thin, lightweight, highly flexible electrode arrays with accurately defined electrode/gel areas, shapes, and interelectrode distances for a wide range of novel stimulation and biosignal recording applications. As the solid gel will not spread between electrodes, it is possible to position electrodes very close together without electrical shorting (Fig. 26).

Wearable Electrodes for Personalized Health. The recent and continuous trend toward home-based and ambulatory monitoring for personalized healthcare, although exciting and potentially leading to a revolution in healthcare provision, necessitates even more demanding performance



Figure 26. Cardiac mapping electrode harness.

criteria for the monitoring sensors (97,98). Many groups around the world are seeking to incorporate electrodes into clothing in order to monitor military personnel, firefighters and eventually the average citizen who wishes to monitor his or her health. Systems already exist on the market (e.g., Life Shirt) that resemble waistcoats into which one plugs-in standard ECG electrodes and other sensors. These sensors are removed and replaced periodically by the subject and, hence, require the knowledgable involvement of the motivated wearer, presently military personnel, athletes, rescue workers, and so on.

For the more widespread use of wearable monitoring systems, especially by the average citizen, the system must be very easy and comfortable to use and require no preparation—literally as simple as putting on their shirt. Electrodes must, therefore, (*1*) require no prepping, (*2*) be located in the correct location once the smart garment is put on, (*3*) make good electrical contact with the skin, (*4*) not give rise to motion artifact problems, (*5*) not cause discomfort or skin irritation problems, and (*6*) be reusable and machine-washable. Although much work has been carried out in this novel area, it is not surprising given the above list of required performance criteria that the electrodes/sensors tend to form the bottleneck in the success of the overall monitoring systems. One must, therefore, not simply choose an electrode with as conductive a metal element as possible. Unfortunately, it would often appear that the associated electronic systems are first developed and the electrode design is left to the end, almost as an afterthought. The author would, therefore, suggest that researchers start with the desired biosignal and establish the optimal body site(s) and electrode design for the given application before developing the rest of the monitoring system. This process may involve the use of novel lead or montage electrode positions in order to conveniently pick up artifact-free signals. Although this method will necessitate clinicians interpreting nontraditional waveforms, it will at least enable feasible monitoring and, as it involves novel body sites and electrode designs, it may well be patentable. After all, if it is not patented and commercialized, it will not benefit the patient.

One of the most promising smart garments is that developed under a European Fifth Framework programme called WEALTHY (Wearable Health Care System) (Fig. 27). WEALTHY is a wearable, fully integrated system, able to monitor a range of physiological parameters including electrocardiogram, respiration, posture, temperature, and a movement index. Fabric electrodes are made using conductive fibers woven into the stretchable yarn of the body-contour hugging garment and connections are integrated into the fabric structure (Fig. 27b). Various membranes are being assessed to ensure optimal electrode-skin contact and minimize skin irritation. The garment is comfortable and can be worn during everyday activities. It is washable and easy to put on.

External Electrostimulation Electrodes

Historical Background. The evolution of external stimulation electrode design shares some of the key landmarks as the development of biosignal monitoring electrode and, hence, this section will be somewhat shorter.

From the mid-1700s, when electrostatic generators were used to deliver arguably therapeutic impulses to various parts of the body, handheld (by the practitioner) electrodes had to be designed capable of delivering the impulses to the patient without shocking the practitioner who was holding them against the body part in question. The electrodes used tended to be simply long metal rods insulated with wooden handles (Fig. 28) (99). Although the electrodes were initially terminated in a simple metallic sphere, more exotic terminations were soon invented as these were observed to lead to different therapeutic effects on the body by means of the variations in the streams of the electric fluid. A modern parallel would be the use of different pencil electrodes (ball, loop, and needle) in electrosurgery for different effect.



Figure 27. (a) The WEALTHY physiological monitoring vest with integrated sensors. (b) An early version of the fabric electrodes.



Figure 28. Early electrostatic generator and handheld electrodes (99).



Figure 30. Duchenne's moistened conical electrodes for localized electrization (101).

Around 1800 came the discovery of Galvanism (dc current) and Voltaic Piles (early batteries). Numerous examples exist of practitioners using their handheld probe for localized effect, and the second contact to the patient was made by means of a container of water into which the patient put a hand or foot (Fig. 29) (100).

Following the discoveries of self-and mutual induction (~1830), Guillaume Duchenne made great contributions to the clinical application of the new Faradic current. At that time, much interest existed in the localization of what became known as motor points. It was common to combine the prevailing interest in acupuncture and use needles to stimulate muscles and nerves under the skin, termed electropuncture (83). Duchenne was not happy with this approach and developed his own electrodes for localized electrization. His electrodes were in various shapes (disks spheroids, and cones) covered with leather moistened with salt water prior to application (101). (Fig. 30).

During the 1900s, as with biosignal monitoring electrodes, electrostimulation electrodes involved the use of simple metal buckets or receptacles, filled with water or another electrolyte, into which the subject introduced their foot or hand, especially in early iontophoretic applications. Obviously, the range of applications was somewhat limited. Metal probes were still manually pressed against skin for short-term applications. The electrodes were either gelled before application or had moistened chamois coverings similar to those used by Duchenne. In the 1950s, early external pacing and defibrillator electrodes, termed paddles because of their shape, consisted of bare metal disks made of noncorrosive material and were simply pressed against the patient's chest (102) see Fig. 31.



Figure 29. Container electrode. Used on the dead and the living (100).



Figure 31. Early pacing equipment and handheld electrodes (102).



Figure 32. Early pacing equipment and metal-plate electrodes (103).

Rigid metal plate electrodes were eventually held in place with rubber straps on the limbs and even the thorax (Fig. 32) (103). Some of these electrodes were and still are made with rigid stainless-steel plates (104). The foil plates were generally used in conjunction with moistened pads of paper toweling, lint, cotton gauze, or sponge. The pads were moistened by the therapist prior to electrode application with water or electrolyte. Such electrodes could be easily reused by simply washing and regelling the electrode. Being rigid, however, these plate electrodes did not always make optimal contact with the body surface and gave rise to current density hot spots. External cardiac pacing at this time, for example, was very painful (83).

Malleable metal foil electrodes were the next evolutionary step in electrode design. Malleable electrodes have been made using a range of metals including tinplate lead and aluminium foils (105). Such electrodes had the advantage of being able to conform, to some extent, with body contours, thus ensuring a better, more comfortable contact between the electrode and the patient than was the case with rigid plates. Wrinkles in malleable metal foil could, however, encourage preferential current flow through small areas of the gel and into the patient.

More convenient, disposable pregelled foil electrodes were then developed for a range of external electrostimulation applications. The metal foil was laminated onto an adhesive foam backing. A gel-impregnated sponge layer was located on top of the metal layer and the complete electrode is attached to the patient by means of the surrounding layer of adhesive backing foam.

Unfortunately, the wet gel in these disposable pregelled electrodes tended to pool to one side, depending on how they were stored, giving rise once again to current density hotspots. More recently, the gel-impregnated sponge layer has been replaced by a conductive adhesive gel layer, as it does not have the potential for pooling to one area during storage and it does not squeeze out under pressure (68) (Fig. 33).


Label
Print Graphic
Medical Grade Polyethylene Foam
Conducting Tin Foil
Cable/Connector
Conducting Adhesive Gel
Rivet
Silicone Coated Polyester Release Liner
Medical Grade Polyethylene Foam
Print Graphic

Figure 33. Construction of a modern external pacing or defibrillation electrode (courtesy Unomedical A/S).

Current Density Considerations. The distribution of current density under an electrode is an important parameter when designing and using electrostimulation electrodes. In the simplest case, current density (the amount of current per unit of conduction area) is inversely proportional to the electrode/skin contact area. For a given current, the current density under a small-area electrode will be higher and more localized than that under a large-area electrode. Generally, an optimal electrode area exists for a given therapeutic application, based on a range of criteria including the anatomical position and size of the nerve/muscle/organ and the relative positions and sizes of the electrodes. Small electrodes are, therefore, well existd to target precisely known points such as motor points. If a small electrode is used in conjunction with a large-area electrode, the effect is more pronounced under the smaller of the two. In such monopolar stimulation, the small electrode is often used as the active electrode to target the therapeutic effect. The larger electrode is simply used to complete the electrical circuit and is termed the indifferent or dispersive electrode. The use of two equally sized electrodes is termed biopolar stimulation. In TENS, for example, biopolar stimulation is often used to stimulate large muscle groups sandwiched between the (large) electrodes. Too large an area of electrode, however, may cause the current to spread to neighboring tissues.

High current densities can cause tissue injury due to, among other things, heating effects. The passage of electricity through any conductor will cause the dissipation of heat within that conductor. The amount of heat generated in a tissue depends on spatial and temporal patterns of current density and tissue resistivity (49).

The total energy dissipated at an electrode–skin interface is given by the formula:

$$E = I^2Rt \tag{21}$$

where

E is energy dissipated (J)
I is root-mean-squared (rms) electrode current (A)
t is the duration of current flow (s)
R is the real part of the impedance at the electrode site (Ω).

The change in temperature at the skin, ΔT, site is proportional to the energy dissipated and, hence, ΔT is proportional to I^2Rt. When skin or muscle tissue is heated to about 45 °C for prolonged periods, thermal damage can result. For short durations (i.e., $<5\,\mathrm{s}$), a temperature rise approaching 70 °C would be needed to cause heat damage.

As the electrode–skin resistance, R, is not generally known for a given site, it is often found convenient to use a heating factor (HF), where

$$\mathrm{HF} = I^2t \qquad (\mathrm{A}^2 \cdot \mathrm{s}) \tag{22}$$

Assuming uniform current density distribution under an electrode, it is possible to calculate the minimum area of electrode necessary to achieve therapeutic effect and avoid tissue trauma (42). In theory, the applied currents flowing through standard dispersive electrodes used for electrosurgery, for example, will generally not give rise to sufficiently high overall current densities to cause thermal damage. However, analysis shows that current density distribution is not uniform under a stimulation electrode and that localized hotspots can occur and cause considerable pain and trauma to the patient when applying apparently safe' therapeutic impulses (49). At best, in cases such as TENS, the applied current may have to be limited to less than therapeutic values due to the patients discomfort (68).

Many potential sources exist of accidentally high current densities. Wrinkles or breaks in the metal electrodes, gel squeezing out from under the electrode or drying out, electrodes partially peeling off the skin, poor electrode application, and so on can encourage preferential current flow through small areas of the gel and into the patient. However, current density hotspots can also occur due to poor electrode design, and a considerable amount of research has been and is being spent investigating this important problem.

In this presentation, stimulation electrodes have been divided into conductive electrodes and resistive electrodes in order to facilitate the review of the various design features.

With highly conductive metal electrodes, such as those used for external cardiac pacing, defibrillation, or electrosurgery, current density hotspots are observed to occur under the perimeter of the electrode, often evidenced in the past by annular-shaped burns to the patient (49,106).

Current density hotspot problems are now often studied using thermal imaging cameras. Thermograms of the patient's skin (or a substitute such as pig skin) are taken immediately following the application of a given series of pulses and the removal of the electrode under test (Fig. 34). Increases in skin temperature reflect the magnitude of the current density at a particular point (107).

Wiley and Webster (108) showed that current flow through a circular electrode placed on a semi-infinite medium could be solved analytically. They found that for an electrode of radius, a, and total current, I_0, into the electrode, the current density into the body as a function of radial distance from the center, r, was given by:

$$J(r,0) = \frac{J_0}{2[1-(r/a)^2]^{1/2}} \qquad (\mathrm{A}\cdot\mathrm{cm}^{-2}) \tag{23}$$

where $J_0 = I_0/\pi a^2$, (i.e., a hypothetical uniform current density).



Figure 34. (a) Schematic representation of the current density distribution under a conductive electrode plate. (b) Thermal image of the skin under an electrosurgical electrode following testing.

As a result of the approximations made in deriving this simple equation, the value of current density at the edge (when $r = a$) would theoretically approach infinity. More realistically, the current density at the perimeter can be around three times higher than that at the center of the electrode (109) (Fig. 34). The above equation shows that the middle portion of the electrode is relatively ineffective in carrying the current as half the total current flows through an outermost annulus 0.14 a wide or one-seventh of the radius.

Efforts in this area concentrate on encouraging more of the current to flow through the central portion of the electrode.

A main concern in the design of the conductive stimulation electrodes used for external cardiac pacing, defibrillation, or electrosurgery is the decrease in the high current densities observed at the edges.

In TENS, relatively resistive conductive rubber is often used and the opposite problem develops. When current is introduced into the conductive rubber (via a small metallic connector), it tends to flow into the skin immediately under the connector rather than laterally through the resistive electrode. Efforts in this area concentrate on encouraging the current to flow laterally through more of the electrode surface.

Modern Electrode Designs

Conductive Electrodes. Electrosurgery, external cardiac pacing, and defibrillation share a common problem: Electrodes tend to deliver or sink a substantial portion of the outgoing or incoming current through their peripheral area as opposed to providing a uniform current density along their surface. This problem is referred to in the literature as the fringe, edge, or perimeter effect.

Many suggestions have been made to reduce this edge effect observed with metal electrodes, including:

1. Increasing overall area of the electrode. Obviously, an increase in electrode area will lead to a decrease in current density (110,111). However, it is generally not practical to use very large electrodes as the applied electrical field must be sufficiently focused to stimulate the targeted tissues and them alone. Also, a strong commercial interest exists in decreasing the size of the electrodes to save money and to facilitate packaging and storage of the electrodes.
2. Avoiding sharp edges in the metal plate (110,111). It has long been observed that square or rectangular electrodes with angular edges concentrate the electrical field at their corners, giving rise to current density hotspots in these locations. Using round electrodes or rectangular ones with rounded edges have been found advantageous in this regard.
3. Making the gel pad slightly larger than the electrode to enable the electric field lines to spread out before reaching the skin (111) (Fig. 35). Using a gel pad much larger than the size of the metal plate has less effect than would be expected as the perimeter of such a large gel pad will carry little current and the additional gel is electrically redundant, which arguably applies to some of the snap connection electrodes used in TENS that do not have an additional current dispersing element.
4. Increasing the overall resistance or thickness of the gel layer in order to give the current more time to spread out evenly through the gel (110,111). It is well-known that, in applications such as external cardiac pacing, the use of relatively resistive gels decreases the pain and burning to the patient's chest. Krasteva and Papazov (110) suggest that the use of a layer of intermediate resistivity, comparable with that of the underlying tissues, optimally improves the distribution. However, in other applications such as external defibrillation, a high resistance gel pad would lead to energy wastage and a decrease in the desired therapeutic effect. Taken to its logical conclusion, this approach results in the coating of the electrode metal plate surface with a dielectric film. Such capacitive electrodes have been shown to give rise to nearly uniform current densities (107).
5. Increasing the resistance or thickness of the gel at the edges. Kim et al. (112) proposed covering the electrode metal with resistive gel of increasing resistivity as one moved out from the center toward the periphery, according to a specific relation with respect to the electrode radius. Although an intriguing concept, the commercial manufacture of such an electrode system is not yet feasible.
6. Making the electrode conductive plate progressively more resistive toward the peripheral edge of the electrode. Wiley and Webster (108) suggested subdividing the electrode plate into concentric segments and connecting external resistors to the individual segments. The connected resistors had progressively higher resistances toward the periphery in order to equalize the currents in the separate segments. A simpler system that has been successfully commercialized was patented by Netherly and Carim (113). A resistive layer is deposited on the outer edge of the electrode conductive plate, thus forcing more current to flow through the central portion of the electrode (Fig. 36). Krasteva and Papazov (110) demonstrated theoretically that a high resistivity perimeter ring



Figure 35. Schematic representation of the current density distribution under an electrode plate coupled with a larger gel pad. Current is allowed to spread out beyond the boundaries of the metal plate, thus minimizing the edge effect.



Figure 36. 3M's electrosurgical dispersive electrode. Note the green lossy dielectric material deposited around the peripheral edge of the electrode.



Figure 38. An electrostimulation electrode with cut-out metal plate in an effort to increase peripheral edge. The green sponge impregnated with gel has largely been removed to facilitate inspection of the underlying plate.

decreased the maximum periphery current by 12% without increasing the total interface resistance, hence the resistance to the defibrillation current.

Another related approach to this problem starts with a resistive graphite-based conductive layer and progressively builds up multilayered (at least two) coatings of more conductive silver/silver chloride toward the center of the electrode (114). The perimeter resistance is approximately 200 times that of the center, this is the technique exploited in Medtronic EDGE system electrodes for defibrillation, noninvasive pacing, and ECG monitoring (Fig. 37). It is claimed that the design distributes the current density evenly over the entire surface area of the electrode, rather than concentrating it at the edges.

7. Scalloping or otherwise shaping the edges of the metallic plate so that the length of the perimeter is increased and, hence, the peripheral current density is decreased. Over the years, various designs have incorporated this concept. For example, it has been shown that using a figure-eight design rather than a rectangular metal plate reduced the maximum temperature (reflective of current density) by 30–50% (107). An alternative design is shown in Fig. 38. Caution is advised with this approach as the formation of fingers in the metal layer may serve only to concentrate the current at the tips of the fingers, and one could be effectively left with a reduced peripheral area.
8. Making holes in the central portion of the metal plate in order to provide internal peripheral edges to block the lateral flow of current. Some early claims were made that holes in the metal layer improved current density under the electrode. Presumably, it was believed that the holes blocked the current from flowing from the connector to the edge of the metal plate, forcing it to flow into the patient at the edges. It is the authors belief that such holes in the metal plate achieve little apart from further decreasing the area of the electrode and, if anything, increasing the current density at the edges. This impression appears to be confirmed by the work of Krasteva and Papazov (110), who investigated electrode structures with openings in the metal plate for skin breathing.



Figure 37. Medtronic's EDGE system electrode.

The author has suggested that the use of concave slits in the metal layer rather than circular holes may well have a favorable effect on current density distribution with the concave internal peripheral edges effectively blocking the lateral flow of current, forcing the trapped current to flow into the gel and, thus achieving a more uniform current density distribution over the surface of the conductive layer (115). Early work on the project with an industrial partner appeared promising, but the work was never completed.

Resistive Electrodes. A TENS electrode system appears relatively simple and generally comprises a conductive plate, an ion-containing gel, a means of attachment to the skin, and a means of connection to the stimulators lead. Mannheimer and Lampe (42) pointed out, however, that of all the component parts of the overall TENS system, the electrode–skin interface has probably been the least understood and the most problematic. In addition to influencing the effectiveness of the treatment, poor electrode design can give rise to electrically, chemically, and mechanically induced skin irritation and trauma to the patient.

Initially, electrodes originally designed for ECG and other biosignal monitoring applications were used with TENS units, and some still are. Larger, more suitable electrode designs were eventually developed in order to reduce the current densities under the electrodes, to reduce skin irritation problems, and to increase stimulation comfort (116).

A large percentage of commercially available TENS electrodes are now molded from an elastomer (e.g., silicone rubber) or a plastic (e.g., ethylene vinyl acetate) and loaded with electrically conductive carbon black (Fig. 39) (3). Very few irritation or allergic reactions have been reported for conductive rubber electrodes as they do not generate the corrosion products often observed with metal electrodes (42). The great advantage of such electrodes is that they can be molded into almost any size or shape and a wide range of choice exists in the market. They can be made sufficiently thin to have high flexibility and, thus, are able to conform with body contours, making them suitable for a wide range of TENS applications.

Conductive rubber electrodes are often used in conjunction with an electrolyte gel and attached to the patient using elastic straps or custom-cut disks or patches of adhesive tape. Expanded polyester foam tends to give the most secure adhesion. However, as this backing is occlusive, the use of foam can give rise to skin irritation problems. Breathable, cloth-like fabrics allow the transmission of air and moisture and generally cause less skin irritation problems. Cloth-like materials tend to stretch, however (an advantage when it accommodates skin stretching due to movement), which can lead to the electrode working loose and making poor contact with the skin, possibly resulting in current density hot spots.



Figure 39. Carbon-filled silicone rubber electrode (3).

Wet gels can squeeze out from under parts of the electrode and give rise to increased current densities in other areas. The use of hydrogel minimizes this problem source (68). Conductive, adhesive pads of solid hydrogel help ensure firm electrical contact between the electrode and the skin, reduce the incidence of current density hotspots, and often simplify the design of the electrode. As a large surrounding disk of adhesive tape is not required, the electrode size can be reduced to the active electrode area. These solid gel pads can be, depending on the application, replaced, refreshed, or simply reused in various semi- or totally-reusable electrode systems. In some applications, the gel pads can be removed and the conductive rubber electrode cleaned and regelled with a fresh gel pad for further use. In other cases, the electrode can be intermittently reused, on the same patient, by rehydrating the gel pad. Such reusable electrodes are ideal for home-based patient use.

One disadvantage with such conductive rubber electrodes is that they are relatively resistive. More power is required to drive the stimulating current through the resistive electrodes into the body and achieve the desired stimulation. Therefore, some reduction in battery life may occur which is generally not a significant problem, however.

A more serious problem involves current density distribution under the resistive electrode. When current is applied through the conductive rubber (via a small metallic connector), it tends to flow into the skin immediately under the connector rather than laterally through the resistive electrode, thus giving rise to a current density hotspot under the connector, which effectively, is the opposite problem to that encountered when using highly conductive electrodes.

Efforts to overcome this problem include incorporating conductive elements in the rubber to more evenly to help spread the current over the entire interface surface. Some electrodes have a thin metallic layer coated onto the back of the conductive rubber, which appear to give rise to the most uniform current density profiles (68).

The growing home-based market has led to the great variety of low cost disposable and reusable electrodes that are generally based on solid adhesive gels. Some electrodes are made using conductive cloth-like materials, thin metallic foils, aluminized carbon-filled mylar, or wire strands. Electrical connection is generally made to these electrodes via alligator clips, snap fasteners, or pin connectors. Many of these hydrogel-based electrodes can be trimmed to the desired size or shape by simply cutting with a pair of scissors. The current density profiles under these electrodes will very much depend on the relative resistivities of the metal and gel layers as well as on the actual design.

Snap fastener designs resembling standard ECG electrodes and are available with hydrodel pads or sponge



Figure 40. (a) Current density distribution under a conventional snap electrode. (b) Axelguaard's UltraStim snap electrode with current controlling grid. (c) Current density distribution under Axelguaard's UltraStim snap electrode. (Courtesy of Axelgaard Ltd.)

disks containing low chloride wet gels (to minimize skin irritation). These desists may require an additional current-dispersing element to ensure that the current spreads out beyond the immediate confines of the eyelet electrode (68). Axelgaard Ltds UltraStim Snap Electrodes feature a highly conductive grid pattern printed on to a conductive flexible layer and coated with a moderately conductive adhesive gel layer. The conductivity of the conductive pattern is controlled through the use of various grid designs with preselected line widths and spacing as well as thickness and ink compositions (117). The pattern is thus used to control and optimize the spread of electric current over the surface of the electrode with an intentional current drop off toward the edge of the electrode (Fig. 40).

It is interesting to note that considering current density under conductive and resistive electrodes leads to a similar optimal design. To improve conductive electrodes, one places a resistive layer between it and the patient. To improve a resistive electrode, one puts a conducting layer either behind or in front of the resistive layer. Such sandwich electrode designs appear promising for a range of electrostimulation applications.

Garment Electrodes. A range of researchers in the TENS, FES, and body-toning areas of electrostimulation are endeavoring to incorporate electrodes in to body hugging garments to enable the convenient and accurate application of a (large) number of electrodes to the body part to be stimulated. The use of a large number of electrodes can enable, for example, several muscle groups to be stimulated together or sequentially in a coordinated manner to achieve a more natural movement of a limb. Garments are already on the market that resemble tight-fitting cycling shorts and have integrated wires and connectors for the attachment of standard TENS (or similar) snap electrodes prior to application. Other, more challenging designs include the integration of reusable electrodes into a stretchable garment.

Implant Electrodes

Implantable monitors/stimulators and their electrodes are used, or are being developed, for a wide range of applications, including cardiac pacing and defibrillation, cochlear implants; urinary control, phrenic nerve stimulation for respiration control; functional electrical stimulation of limbs; vagal stimulation for control of epilepsy, spinal stimulation for chronic pain relief, deep-brain stimulation for Parkinsons disease or depression, bonehealing, and several visual neuroprostheses.

Implanted monitoring electrodes are used to more accurately pick up the desired signal while minimizing the contributions of extraneous signals. Implanted stimulation electrodes deliver the applied waveform more selectively to the targeted tissue, making the therapy more effective and, as the stimulation electrode is generally implanted away from cutaneous pain receptors and afferent nerve fibers, more comfortable for the patient. One significant drawback, however, is the greater potential for damage from improper electrode design, installation, and use.

The design of an implant electrode will depend greatly on the anatomical structure it is to be implanted against, into, or around. Electrodes can be or have been implanted in, on, or near a given muscle; in, on, or around a given nerve; in, on, or around a given bone; in, on, or around the spinal cord; and in or on the surface of the cerebellar cortex.

A review of all of these designs is beyond the scope of this chapter. The reader is referred to the appropriate chapters in this Encyclopedia.

To facilitate this overview of some of the key design possibilities, two main application areas will be concentrated on: muscular and neural electrodes. Muscular (especially cardiac) electrodes, using more traditional electrode fabrication, are presented in a separate section. Neural electrodes will be largely covered in the section on newer microelectrodes constructed using thin-film and similar techniques. These categories are very loose and a considerable degree of overlap obviously exists between applications and the various electrode fabrication techniques. Once again, the reader is referred to the appropriate chapters in this Encyclopedia for more detailed descriptions of electrodes and their fabrication for specific applications.

Cardiac electrodes are the most important example of muscular electrodes. As cardiac pacemakers and defibrillators have the longest and most successful track records as implantable devices, much of the science underpinning the newer (and future) implantable devices (muscular, neural, and other) has been developed by the cardiac implant pioneers. Key contributions were made in the areas of implant electrodes, biomaterials, and powersources, to


Palliation of thoracic aortic aneurysms by electropuncture in mid-nineteenth century.
d
c
e
Needle used for that purpose, modifications of which were made in few instances in which electrocardioresuscitation was attempted.

Figure 41. Kimer's electropuncture of the heart (103).

name but a few. The present review of electrodes is, therefore, largely based on cardiac electrodes. However, ideas can be gleaned from this area and, once suitably customized, applied to others with success. The advantageous aspects of biphasic impulses (discovered in the 1950s, arguably earlier) is a good example of something being rediscovered in a range of stimulation applications over the past few decades

Historical Background. Implant stimulation electrodes, or at least percutaneous stimulation electrodes, predate the earliest biosignal monitoring electrodes. In the early 1800s, there appeared a renewal of interest in acupuncture in Europe that had been introduced into Europe in the second half of the eighteenth century by Jesuit missionaries. In 1825, Sarlandière was the first to apply an electric (galvanic) current to thin metal needle electrodes (derived from acupuncture needles) thus creating electropuncture for the application of current to specific points on or in the body (98,118).

Electropuncture soon became the accepted method of stimulating muscles, nerves, or organs beneath the skin (83). Electropuncture of the heart was first attempted by Krimer in 1828 without recorded success (Fig. 41) (103). This technique was then abandoned for several decades. Meanwhile, W. Morton successfully introduced the use of ether as an anesthetic in 1846. Eventually, chloroform was found to be more suitable although cardiac arrest was a frequent complication of chloroform anesthesia in those early days. In 1871, Steiner overanesthetized horses, dogs, cats, and rabbits to produce cardiac arrest. He reported successfully applying an intermittent galvanic current to a percutaneous needle in the heart to evoke rhythmic contractions. Terms such as galvano and farado puncture soon started to appear in the literature (103).

In the early 1900s, cardio-stimulating drugs such as epinephrine were injected directly into the heart of sudden death victims by means of a large needle inserted through the chest wall to restore automatic activity. It was eventually established that one of the key factors in the occasional success of these intracardiac injection procedures was the actual puncture of the heart wall rather than the medication administered. Based on this observation, Hymen went on to build the first hand-cranked, spring-driven artificial pacemaker (119). He used transthoracic needle electrodes plunged into the atrium and even introduced the concept of using a biopolar needle arrangement as in having the two electrodes so close together that only a small pathway is concerned in the electric arc established by the heart muscle, an irritable point is produced (103).

In the 1950s, Lillehei, Weirich, and others pioneered the use of cardiac pacing for the management of heart block accidentally resulting from cardiac surgery and for other emergency cardiac treatment. Slender wire electrodes were implanted into the myocardium before closing the chest with the connecting leads thus exiting through the chest wall. Pacing impulses could then be delivered through these wires for a week or so until the heart healed. Once the heart had recovered, the electrodes were pulled out. Early versions of these electrodes consisted of silver-plated braided copper wires insulated with polyethylene or Teflon (103,120).

In 1958, Furman and Schwedel reported the first instance of transvenous pacing of the heart. They inserted a unipolar catheter electrode into the right ventricle of the patient through a superficial vein and paced the heart via the endocardial surface. The electrode used was a solid copper wire with a bare terminal tip (120). The electrode was withdrawn once the patients heart resumed its own idioventrcular rhythm. Although the cardiac pacing employed by Lillehei et al. and by Furman and Schwedel



Figure 42. (a) Chardack, Gage, and Greatbatch's wholly implantable pacemaker and the Hunter–Roth bipolar intramyocardial electrode (83) (b) Diagram of an early Hunter–Roth lead with two bipolar myocardial pin electrodes (35).

was much better tolerated than the external stimulation of Zoll, perielectrode infection was a major drawback as was the transport of the external pacemaker. The development of an implantable pacemaker, therefore, became the goal of several groups around the world.

In 1958, Senning and Elmqvist successfully implanted the first Pacemaker without leads emerging from the patient's chest to invite infection. The implanted unit was powered by cells that were recharged from outside the body using a line-connected, vacuum-tube radiofrequency generator. The electrodes/leads used were stainless-steel wires. The second version of the unit failed due to a lead fracture one week following implantation. It was then decided to abandon pacemaker therapy for this patient until better leads were developed (120).

At that time, many of the electrodes used were unipolar. The active electrode tended to consist of the bared tip of an insulated wire implanted in the myocardium whereas the indifferent electrode was a similar wire implanted subcutaneously in the chest wall. Unfortunately, the stimulation threshold was observed to rise following implantation during longer-term pacing. This increase in threshold was thought to be due to the development of scar tissue around the active electrode. Hunter and Roth developed a bipolar electrode system in 1959. This electrode consisted of two rigid, 0.5 cm long, stainless-steel pins attached to a silicone rubber patch. The cathode–anode pins were positioned in to myocardial stab wounds surgically created for the purpose and the pad was then sutured to the epicardial surface (35). The lead wire was a Teflon-coated, multistrand stainless-steel wire with an outer sleeve made from silicone rubber tubing (121).

In 1960, Chardack, Gage, and Greatbatch successfully produced a wholly-implantable battery-powered pacemaker (Fig. 42a). Initially, they used a pair of multistrand stainless steel wires in a Teflon sleeve with the bare ends sutured to the myocardium (35). Other metallic formulations were tried, such as solid wire, silver wire, stainless steel, orthodontic gold, and platinum and its alloys (122).

They eventually adopted the Hunter–Roth intramyocardial electrode (Fig. 42a and b). Considerable surgery was required as the pacemaker had to be implanted into the abdomen and the electrodes were sutured to the heart wall. The bipolar electrode did, however, dispense with the need of a dispersive chest electrode and the associated pain it caused (103). Stimulation thresholds tended to stabilize at much lower levels with this electrode (120), which enabled successful pacing for many months.

Breakage of lead wires, due to metal fatigue, was a major concern. One of the main problem areas occurred at the point were the two metal components were welded together (121). Corrosion also occurred at the small-area stainless-steel anode, causing cessation of pacing within a few months.

Chardack et al. (123) devised a replacement for the Hunter–Roth electrode based on a continuous helical coil of platinum-iridium (Fig. 43). The electrode was simply a few turns of the coiled lead wire, exposed and extended to enable fibrous tissue to grow between the spirals and firmly anchor the electrode in place. The use of a helical coil greatly increased flexibility and decreased the number of fatigue failures, as did the use of one continuous wire (without a join) for both lead and electrode. The use of the same metal for lead and electrode also had the advantage of preventing corrosion from galvanic action. Additionally, platinum-iridium is more corrosion resistant than the metals used in many electrodes prior to Chardack's electrode.

The sutureless screw-in lead was later introduced by Hunter in 1973 (35). The screw-in electrode was simply rotated into the myocardium and did not require a stab wound or sutures for insertion. The electrode was effectively the means of attachment. As this corkscrew electrode tended not to dislodge, it dominated pacing for a long time and is still used today for many epimyocardial implants (Fig. 44).

A thoracotomy was required to attach many of the above electrodes to the heart, which complicated surgical procedure and resulted in a 10% early mortality (122). The first so-called modern pacemaker, which combined an implanted generator and a transvenous lead, was developed simultaneously in 1962 by Parsonnet and Lagergren (124,125). The endocardial catheter electrodes could be



Figure 43. The "Chardack" electrode (a) (35) (b) Chardack et al. (123).



Figure 44. The corkscrew myocardial electrode (35).

installed under local anesthesia, and this approach virtually eliminated early mortality. As they did not require the opening of the chest cavity, the use of catheter leads opened the field of pacemaker implantation to nonsurgeons in later decades.

To minimize the risk of venous perforation, the electrode leads were made flexible by winding bands of stainless steel around a core of textile fibers (120). The electrode was a small stainless-steel cylinder at the end of the catheter.

As time passed, the transvenous route progressively evolved over the myocardial approach, so much so that, at present, the transverse route is almost exclusively used for pacemaker implantation.

Cardiac pacing has been the earliest and most successful example of implanted electrodes and associated hardware. Many present and future developments in other implanted electrostimulation (and biosignal recording) areas are and will be based, to a large extent, on the pioneering work carried out in the pacing area.

Some Modern Electrode Designs. With the early transvenous leads, the stimulation threshold was observed to greatly increase if the electrode pulled away even slightly from the myocardium. A wide variety of active fixation devices was therefore invented. These devices included springs, deployable radiating needles, barbs, hooks, claws and screws designed to anchor the electrodes by actively penetrating the myocardium (35,126). The "Bisping" transvenous screw-in electrode is the most popular, as it allows the screw helix to be extended from the tip once the lead has been successfully threaded through the vein and located against the desired part of the heart (Fig. 45). It can be used as a combined anchor and electrode. The screw can be retracted allowing for an easier extraction of the lead, when necessary. (*Note:* A similar design of electrode is used for detecting the fetal electrocardiogram during labor. The intracutaneous needles are screwed in to the fetus' presenting scalp. Similar designs are also used in EEG monitoring.)

A wide variety of passive fixation devices were also invented. Various tines, flanges, and other soft, pliant projections were formed at the distal end of the lead, generally as an extension of the silicone or polyurethane lead insulation, and designed to passively and atraumatically wedge the electrode between endocardial structures such as trabeculae (Fig. 46). In some designs, the electrode has the form of a closed-loop helical coil that, when twisted clockwise, becomes lodged in the trabeculae (126).

Early electrodes had smooth metal surfaces. Techniques were then developed to roughen the surface in the hope of encouraging tissue in-growth, thus locking the electrode in place, minimizing mechanical irritation and excessive fibrous encapsulation, and ensuring low chronic stimulation thresholds. Studies found that porous electrodes did indeed achieve better fixation, thinner fibrous capsules, and stable thresholds.

A variety of porous electrode tips have been developed including totally porous structures such as CPIs meshed screen electrode and electrodes whose surfaces had been textured using a range of techniques (Fig. 47). Porous surfaces have been generated by coating metal surfaces with metallic granules, by sintering metal spheres to form a network of cavities, and by laser-drilling the surface of electrodes (126).

Not only does roughening improve electrode fixation and threshold stability, it has been found to have a very advantageous effect on interface impedance. From a stimulation point of view, one is keen to use a small-area electrode to increase current density at the small tip and



Figure 45. The "Bisping" transvenous screw-in lead with the helical screw electrode extended. [From S.S. Barold's The Third Decade of Cardiac Pacing (35).]



Figure 46. Transvenous lead with silicone rubber tines (35).

thus decrease stimulation threshold. A small-area electrode also has a high pacing impedance that can decrease current drain on the generator and thus prolong implant life (35). However, one would also like to have a low sensing impedance in order to avoid excessive attenuation of the cardiac signal. Two ways that exit these conflicting criteria can be optimized, modifying the electrode surface or modifying its design.

Roughening the surface of a small-area electrode increases its effective area without changing its geometric or outer envelope surface area (35). Many electrode systems have been developed that incorporate this concept—electrodes with terms such as activated, porous, and sintered in their company's description. These electrodes have been found to be effective in lowering the electrode interface impedance under small-signal sensing conditions. [Note: the electrode–electrolyte interface is very nonlinear and, hence, smaller under stimulation.] Unfortunately, the reduction in interface impedance has been erroneously interpreted as rendering the electrode nonpolarizable. As stated previously, the word polarization appears to be used in a rather vague manner and has been used as the explanation of, among other things, the nonlinearity of the interface impedance as well as its frequency- and time-dependence. The fact that the current or voltage response to a step in voltage or current is not a simple step has been attributed to polarization. The observed transient responses are merely due to the presence of the double layer capacitance (see Figs. 8, and 9). Roughening the surface of an electrode effectively increases the area of the interface and the value of C_{dl}, which in turn results in an increase in the response's time constant ($T = R_{\mathrm{CT}}C_{\mathrm{dl}}$). The observed response thus looks stretched out along the time axis. This flattened response has been mistaken for that of a purely resistive, nonpolarizable electrode. At any rate, roughening the surface of the electrode almost gives us the best of both worlds, a noble or inert electrode with a low interface impedance.

Another way of achieving a small simulation surface area (high current density) while ensuring a large-sensing surface area (low interface impedance) is to modify the design of the electrode.

The porous electrode of Amundson involved a hemispherical platinum screen that enclosed a ball of compacted 20 μm diameter platinum–iridium fibers (127). As electrolyte could penetrate this three-dimensional (3D) or multilayered electrode, the design resulted in a major increase in



Figure 47. (a) Cross-section of a totally porous electrode (35). (b) Cross-section of a porous surface electrode (35). (c) Photo of totally porous electrode (126).



Figure 48. The differential current density (DCD) electrode (129).



Figure 49. The target tip electrode. Microporous, plantinized plantinum electrode. The target appearance is due to shallow grooves separated by peaks. (Courtesy Medtronic, Inc.)

effective surface area as well as promoting tissue in-growth and long-term stability of thresholds. Lagergren et al. (128) introduced the birdcage design, which also exploited some of these features (126).

One interesting example of a modified design by Parsonnet et al. involved the use of an electrolyte-filled hollow electrode, called a differential current density (DCD) electrode (129). The actual stimulating electrode is the mouth of the electrolyte filled pore, which can be small to provide high current density at the point of contact with tissue (Fig. 48). The inside of the hollow electrode chamber has a large metallic surface (a helical coil forming a cylinder) and thus gives rise to a low electrode-electrolyte interface impedance.

Figure 48 appears to be an electrode design that could readily be customized and used in a wide range of monitoring or stimulation applications. The electrode–electrolyte interface is effectively recessed and protected from any disturbance, a further advantage to those already listed above.

Several other designs exist that aim to achieve a similar effect by manipulating the current density distribution around an electrode tip. Electrodes with complex shapes have irregular patterns of current density with localized hotspots at points of greatest curvature (126). It is possible to exploit these areas of high current density for stimulation purposes while the larger overall surface area gives rise to a low interface impedance (130). A hollow, ring-tipped electrode (effectively similar to the DCD electrode) has a large current density at its annular mouth while having a large electrode–electrolyte interface area. Such electrodes are reported to have better stimulation thresholds and sensing characteristics than hemispherical designs and have proved popular. Several manufactures have combined this ring-tip design with increased surface porosity (126). Other related designs include a dish-shaped electrode for edge-focusing of current (with laser-drilled pores for interface impedance reduction) and a grooved hemispherical platinum electrode coated with platinum black particles (target-tip electrode, Fig. 49) (126,130).

Steroid-eluting electrodes were introduced in 1983 in an effort to minimize the growth of connective tissue. The first-generation electrode was made of titanium, with a platinum-coated porous titanium surface (Fig. 50). The electrodes incorporated a silicone core that was impregnated with a small quantity an anti-inflammatory corticosteroid (34). Upon implant, the steroid is gradually eluted into the interface between the lead electrode and the endocardium, reducing the inflammation and fibrosis that would normally occur. Steroid-eluting leads are characterized by a lower long-term capture threshold. Similar improvements in capture thresholds have been achieved (131,132).

Most cardiac electrodes now involve the combination of drugs and complex surface structures at the macro and micro scales.

For newer applications, such as Cochlear implant electrodes, an array of electrodes is involved. In some such multielectrode applications, one may be interested not only in the current density profiles under the surfaces of the individual electrodes, but in the interplay between the electrical fields produced by the electrodes in the array in the hope of achieving more effective stimulation or more effectively imitate physiological stimulation. For example, the Clarion hi-focus electrode system of Advanced Bionics Corp. incorporates 16 electrodes in a flexible array that are designed to deliver improved focused stimulation to the auditory nerve (133).

Microelectrodes. Over the past few years, exciting developments have taken place in areas of biomedical



Figure 50. (a) Steroid-eluting electrode. (b) Cross-sectional diagram of an early design of steroid-eluting electrode. Behind the electrode is the silicone rubber plug compounded with steroid. (Courtesy Medtronic, Inc.)

engineering that involve implantable devices for the recording or stimulation of the nervous system.

In the previous section, we saw the success in commercializing pacemakers. Other implant devices that have also reached the patient in clinical routine practice or research settings include Cochlear implants to restore hearing; deep-brain stimulators to alleviate symptoms of Parkinson's Disease and depression; vagal nerve stimulators to minimize the effects of epilepsy; as well as FES systems to restore or improve function in the upper extremity, lower extremity, bladder and bowel, and respiratory system (134,135). Other areas of research that are likely to come to fruition within the next few years include various visual prostheses to restore functional vision in the profoundly blind and the exploration of the brain–computer interface (134,136,137).

Much of the early research in these areas started around the 1960s (135). Where possible and appropriate, surface and percutaneous electrodes were first used to establish the feasibility of the given recording/therapy. Early implant electrodes involved fine metallic wires or small disks placed near, in, on, or around the targeted muscle or nerve. The fabrication of these electrodes was time-consuming and the electrode properties were not very reproducible given the variations in areas, surfaces, inter-electrode distances, and so on, which was particularly a problem when several electrodes were to be used in an array. As the demands on human implantable diagnostic/stimulation devices increases, an increased need for a larger number of smaller-area electrodes with well-defined and reproducible surfaces and dimensions generally occors. Although, due to their high level of specificity, muscle-based electrodes will continue to be used, new electrode designs tend to concentrate more on direct nerve stimulation as this may provide more complete muscle recruitment and the same electrode may successfully recruit several muscles, thus reducing the number of electrode leads required (135). Electrodes are, therefore, needed that can interface electrically with the neural system at the micrometer scale (136).

For example, the goal for a high resolution retinal prosthesis is a 1000-electrode stimulating array in a 5 × 5 mm package (137). If this area of research is to be clinically successful and if the other areas are to continue to improve, microelectrodes must be (and are being) manufactured using the thin-film technologies associated with the IC circuit industry. Microfabrication involves either material deposition or removal. Either rigid silicon wafers or flexible polyimide substrates act as platforms for the microelectrodes and associated circuitry. The deposited films (for connectors, leads, electrodes, or insulation) are produced by electroplating, evaporation, and sputtering. The layers can be photo-patterned and etched to submicrometer resolutions and finally encapsulated in biomaterials such as diamond-like carbon, bioceramic, or a biocompatible polymer. Processes such as photolithography, reactive ion etching (RIE), CMOS processing, MEMS processing, focused ion beam patterning, and AFM lithography can be used to achieve the desired microelectrode design.

The benefits of a microfabrication approach include a high degree of reproducibility in physical, chemical, and electrical characteristics. Microfabrication is a high yield, low cost process once the design and processing sequence have been developed. Additionally, precise control of the spatial distribution of electrode sites exists, which may be of interest when seeking to optimally stimulate or record from a target site. A high packing density of electrode sites for a given implant volume is also readily achievable using photolithographic techniques. The possibility exits of incorporating the interface circuitry directly on the microsensor platform thus reducing the need for complex interconnections.

The widespread availability of silicon micromanufacturing techniques has enabled the fabrication of a range of silicon-based wedge- or needle-shaped electrodes to allow penetration of the nervous tissue. 3D arrays of such structures have been developed for insertion into, for example, the cortex to detect local potentials (134).

1D arrays of electrodes are fabricated using lithographic patterning and deposition of thin-film metal leads and electrodes onto not only silicon, but also glass and even flexible polyimide substrates (136). Much of the work on silicon-based microprobe fabrication has been pioneered at the Center for Integrated Sensors and Circuits at the University of Michigan.

A 3D electrode array can be fabricated by assembling a range of 1D probes (such as those shown in Fig. 51). As each probe has multiple recording sites along its length, the complete volume of the tissue under study can be assessed, giving rise to very dense sampling. The Michigan Probe has evolved a large number of single-shaft, multishaft, and 3-D-stacked microelectrode arrays (136).



Figure 51. (a) Multielectrode silicon probe. [After Drake et al. (138).] (b) Michigan micromachined multielectrode probe for recording and stimulation of central nervous system.



Figure 52. (a) Utah electrode array shown on a U.S. penny to convey size. (b) Modified Utah electrode array in which the length of the needles is uniformly graded (134).

Recent improvements in silicon microtechnology have made it possible to create not only planar microelectrodes but also penetrating brush electrode structures for *in vivo* measurements. In contrast to the University of Michigan's planar devices, the 2D and 3D cortical multimicroelectrode arrays developed at the University of Utah are fabricated out of a single solid block of silicon. Etching of the block results in a 10 × 10 array of needles, each 1.0–1.5 mm long, arranged on a 4.2 × 4.2 mm base. The metal and insulation layers are then applied, creating 35–75 μm long platinum recording tips (134,136,139) (Fig. 52a).

This design has the advantage of placing a relatively large number of recording sites in a compact volume of the cortex. However, with a single recording site on the end of each needle set at a fixed depth into the cortex, this version of the Utah array is classified as a 2D array as all the electrodes are in the same plane (140). The Utah probe can achieve high-density sampling by spacing many needles close together but does not have multiple sites along each shaft. When the length of the needles in such an array is graded (the array is said to be slanted, Fig. 52b) or the needles have some other distribution of lengths, these arrays are termed 3D as the electrode tips are no longer in the same plane. These designs are thought to give the better spatial selectivity (134,136).

Implanting such needle or brush electrode systems is obviously associated with damage of the tissue. Moreover, the stiffness of many systems may lead to damage of nervous tissue, especially if relative movement exists between the sharp needles and the delicate tissues. Breakage of the brittle needle is also a concern. Considerable efforts are therefore being directed at miniaturizing the width of the needles or at introducing more flexible materials.

For example, some versions of the Michigan Probe consist of four parallel, dagger-like probes connected to a micro-silicon ribbon cable. The ribbon cable is semiflexible and allows the probes to move up and down with the cortex as it pulses (139).

In the development of subretinal stimulating arrays using current silicon micromanufacturing techniques, it has been pointed out that a planar, rigid implant is likely to mechanically damage the compliant, spherical retina (137). Concerns have also been expressed regarding the use of penetrating microelectrodes, the relative micromotion between the array and the retina potentially provoking mechanical damage and a significant encapsulation response (134). The ideal retinal-stimulating electrode would therefore have the flexibility to match the curvature of the retina and the next generation of electrode arrays are likely to be constructed on flexible substrates.

Microelectrode arrays on flexible substrate have been demonstrated in a range of applications including the European project “Microcard”, Si-Based Multifunctional Microsystem needle for Myocardial Ischemia Monitoring. Initially, work centered on silicon-based microprobes to monitor the electrical impedance of tissue, tissue temperature, pH, and local ionic concentrations of potassium, sodium, and calcium. These parameters were found to vary considerably when, for example, a heart undergoes an ischaemic phase, thus establishing the clinical value of the technique and device, (140).

In the course of the silicon probe development, it was foreseen that the brittle nature of silicon could make intact probe removal difficult. Additionally, the rigid needle could cause damage to the delicate tissues. The thrust of the project thus changed to the development of flexible, polymer-based probes.

Thin-film devices for the measurement of tissue impedance and ion concentrations were manufactured on flexible polyimide substrates (Fig. 53a) (141). Gold thin-film electrodes were deposited using an improved photolithography process for 1 μm resolution. Polyimide insulation



Figure 53. Microfabrication of sensors onto flexible substrates. 1D probe electrode array. [After Mastrototaro et al. (141).]

layers were spin-coated onto the PTFE surface after suitable conditioning, and they proved to be insulating and continuous.

Electrochemical characterization of the gold thin-film impedance electrodes showed them to possess high interface impedance. Pt and IrO oxide coatings were electrochemically applied to the gold thin-film surface and resulted in a drastic reduction in interface impedance for monitoring or stimulation applications (142).

Encircling neural electrodes may be of a cuff or spiral design. The term cuff electrodes applies to those devices that engulf the entire circumference of a nerve First model, which rather stiff, carried only one or two electrodes and they were made using a platinum foil electrodes that were located on the inside of a cylinder of silicone rubber, which was wrapped around a nerve (Fig. 54b). (136). It is generally recommended that the diameter of the cuff be 50% larger than the nerve diameter to avoid nerve compression and necrosis due to swelling and fibrous tissue ingrowth. Cuff electrodes do however have a long and successful track record in a range of FES applications (143).

The spiral electrode is a loose, open helix that is wound around the nerve (143). The open design can accommodate swelling and is very flexible. A version of this electrode is marketed by Cyberonics for use with their vagus nerve stimulator (Fig. 54b). New designs of nerve cuff electrodes seek to reshape the geometry of the nerve to more selectively stimulate or record from particular nerve fascicles. Efforts are also directed at controlling the electrical fields generated by the electrode arrays to better focus the stimulation (135).



Figure 54. (a) Neural cuff electrode. (b) Spiral electrode (Cyberonics).

As part of a European project NEUROS, NIBEC developed a flexible thin-film-based stimulation and sensing cuff electrode for FES-related application. IrO, Pt, and Au electrodes were deposited onto a polyimide substrate. In order to facilitate implantation and ensure good contact between nerves, fascicles and electrode surface was self-curling. Polyimide resin with a thermal expansion coefficient differing from that of the polyimide substrate was chosen so that the curing process gives rise to a residual stress and curl in the device. The diameter of the electrode cylinder could be made less than 1 mm.

Diamond-like carbon (DLC) encapsulation was deposited onto the device using a plasma-enhanced chemical vapor deposition (PECVD) process. Adhesion to the polyimide substrate was found to be satisfactory following the addition of a silane adhesion layer at the interface (144,145).

With the aid of micofabrication techniques, one can control the area and properties of the electrodes and greatly decrease them in size. However, as electrode area decreases, the interface impedances increase with resultant difficulties in making accurate measurement. The key to success in this case is in the choice of electrode design, material, and electrode surface topography.

A similar concept to Chardack's differential current density pacemaker electrode was suggested for use in thin-film electrodes. The metal electrode is housed within a hollow chamber (Fig. 55). The chamber is filled with electrolyte and has a small aperture to enable electrical contact with tissues (146). As the metal–electrolyte interface is relatively large, the interface impedance is relatively small. The interface is also protected from mechanical disturbance (similar to the floating electrode) and, hence, should suffer from less artifact. As the small aperture determines the area of contact with the tissue, the effective stimulation or recording area is very small.

Other 3D designs with etched meshes should be assessed for their potentially larger interfacial areas.

Once again, surface roughness is an important factor in decreasing interface impedance and possibly in helping anchor the electrode in position. Rough-surfaced electrodes must be used with caution, depending on the application, in case the surface causes damage to the surrounding tissues. Certain materials and the electrode fabrication processes involved may well result in favorable macro-, micro-, and nano- surface features. Presently, investigators are studying modifications to the electrode surface using such things as nanotubes. Nanotechnology offers much promise for



Figure 55. Thin-film differential current density electrode. [After Prohaska et al. (146).]

new sensor devices, particularly in the biomedical sector. Not only do individual nanotubes offer the possibility of using them as ultrafine needles for *in vivo* probing at the cellular level, but surfaces can be created with optimal distributions of clusters of nanotubes to maximize performance.

ELECTRODE STANDARDS

The Association for the Advancement of Medical Instrumentation (AAMI) produce a range of labeling, electrical, and other performance requirements for manufacturers and users to help ensure acceptable levels or product safety and efficacy. Some of the key electrode-related standards are briefly reviewed below.

Standards For Biosignal Monitoring Electrodes

Standards for Disposable ECG Electrodes. ANSI/AAMI EC 12 (2000)

Introduction. In an effort to minimize ECG recording problems associated with the performance of electrodes coupled to a standard ECG monitor or electrocardiograph, AAMI has proposed a series of simple bench tests designed to assess pregelled, disposable ECG electrodes.

Although originally conceived to assess disposable ECG electrodes, these standards are widely used to assess other biosignal monitoring electrodes, which is a consequence of the lack of other widely accepted standards for these monitoring applications and to the general applicability of the ECG standards to the other applications.

Although AAMI also lays down stipulations for electrode labeling, adhesion testing, and soon, only the electrical performance requirements are reviewed here.

AC Impedance. The average value of 10 Hz impedance for at least 12 electrode pairs connected gel-to-gel, at a level of impressed current not exceeding 100 μA peak-to-peak, shall not exceed 2 kΩ. None of the individual pair impedances shall exceed 3 kΩ.

Low impedance electrodes are desirable to avoid signal attenuation and distortion and to minimize 50/60 Hz interference pickup. High electrode impedances can also give rise to serious burns when the ECG electrodes are used in the presence of electrosurgery or defibrillator discharges. (147).

The impedance of the skin's outer layer, the stratum corneum, is many times larger than that of the metal/electrolyte interface, and hence, the former is of key concern when endeavoring to ensure good electrode performance. The skin preparation technique, the extent of diaphoresis, and the ability of the electrode gel in penetrating and reducing the skin impedance are generally more important than the electrode–electrolyte interface impedance.

The Standards Committee decided that the electrode gel-to-gel impedances should be significantly less than the expected impedance of clean, dry skin to ensure a minimal contribution by the electrode itself to the overall impedance (147). In the UBTL tests carried out on behalf of the Standards Committee, it was found that the mean 10 Hz impedance of a standard pair of ECG electrodes on unabraded skin was of the order of 100 kΩ. The AAMI committee chose 2000 kΩ as a reasonable limit for 10 Hz gel-to-gel impedance to ensure that the electrodes did not contribute significantly to the overall impedance nor to power dissipation in the presence of defibrillation overload and electrosurgery currents.

As the electrode-gel interface impedance is nonlinear and decreases with applied signal amplitude, the standard stipulates that the level of impressed current must not exceed 0.1 mA peak-to-peak when carrying out the test.

In the UBTL tests, it was found that the impedance as measured on abraded skin correlated well (99%) with the impedance measured with the electrodes connected gel-to-gel, whereas the impedance measured with electrodes applied to clean, dry skin correlates very poorly (47%) with the gel-to-gel measurements. Obviously, the bench test simply evaluates the ac impedance performance of the electrode-gel interface and will, therefore, not accurately predict or represent the clinical performance of an electrode on intact skin. For example, cases of electrodes that performed poorly as per the AAMI bench test exist, yet which proved very satisfactory *in vivo*. Conversely, some of the best electrodes according to the bench tests performed relatively badly in vivo (148).

DC Offset Voltage. After a 1 min stabilization period, a pair of electrodes connected gel-to-gel, shall not exhibit an offset voltage greater than 100 mV.

Ideally, the potentials of both electrodes used to monitor a biosignal should be identical and, thus, cancel each other out. Slight differences in the gels and metals used, however, result in an offset voltage. The potentials of the skin sites further complicate the recording, especially as these latter potentials (and their amplified difference) tend to be much larger. If the overall electrode-skin potential difference is larger than 300 mV, the amplifier may saturate and the biosignal will not be observed.

The UBTL report studied the correlation between gel-to-gel and electrode-skin offset voltages and found that gel-to-gel offsets were in the order of 2.5 times smaller than those recorded *in vivo* for the same electrodes on a patient's skin. As the maximum allowable *in vivo* dc offset should be less than 300 mV, the Committee decided that the limit for gel-to-gel dc offset should therefore be less than 300/2.5 mV (i.e., 100 mV).

Some reviewers of the standard argued that the limit should be reduced to 10 mV as this would help minimize motion artifact problems. The Committee rejected this suggestion, pointing out that no clear evidence exists that links high gel-to-gel offset voltages with motion artifact (largely caused by skin deformation).

Offset Instability and Internal Noise. After a 1 min. stabilization period, a pair of electrodes connected gel-to-gel, shall not generate a voltage greater than 150 $\mu V_{\text{p-p}}$ in the passband (first-order frequency response) of the 0.15–100 Hz for a period of 5 min following the stabilization period.

This standard is concerned with the problem of baseline wander, which introduces a low frequency component into the monitored biosignal making accurate diagnosis difficult. The American College of Cardiology's Task Force on the Quality of Electrocardiographic Records judged that drift rates less than 400 $\mu V \cdot s^{-1}$, although not highly rated, were not considered unacceptable.

The UBTL report detailed several experimental limitations that prohibited their detailed study of *in vivo* dc offset drift. Consequently, no correlational analysis was carried out between dc offset drift measurements made with electrodes applied to human skin and those joined gel-to-gel. They, however, decided to use the factor of 2.5 they had observed between clinical and bench test result for dc offsets, given that the measurement techniques are fundamentally similar. A limit of 150 $\mu V \cdot s^{-1}$ was therefore arrived at by dividing the 400 $\mu V \cdot s^{-1}$ baseline drift rating by a factor of 2.5. As the test circuit used in the bench test differentiates the offset voltage, the offset instability requirement is specified in μV rather than $\mu V \cdot s^{-1}$.

The Committee was contacted and asked to decrease the limit from 150 μV to 40 μV p-p in order to be in line with the AAMI standard "Cardiac monitors, heart rate meters and alarms (EC13)". The working group agreed that this requirement could be made more stringent but refused to decrease the limit to 40 $\mu V_{p\text{-}p}$. This requirement is under study and may well be altered.

This calculation involved in reaching the 150 $\mu V \cdot s^{-1}$ limit implies that skin potential fluctuations are only 2.5 times larger than those of the electrode–gel interface, which is most unlikely, and problems developing from drifting electrolyte/skin potentials will depend on skin preparation, electrode design, and electrode gel rather on than the electrode–gel interface characteristics per se (64).

Defibrillation Overload Recovery. Five seconds after each of four capacitor discharges, the absolute value of polarization potential of a pair of electrodes connected gel-to-gel shall not exceed 100 mV. Also during the 30 s interval following each polarization potential measurement, the rate of change of the residual polarization potential shall be no greater than $\pm 1\,mV \cdot s^{-1}$.

It is important that a clinician, having defibrillated a patient, be able to see a meaningful ECG within 5–10 s in order to judge the efficacy of the delivered impulse and to decide if another is required. The offset voltage across the electrode-skin interfaces, which drastically increased as a result of the defibrillation impulse, must therefore return to below 300 mV within 5 s following the discharge. Once again, using the 2.5 factor between bench test and *in vivo* potentials, this requirement translates to a gel-to-gel bench test offset voltage under 100 mV within 5 s of applying an overload of 2 mC (representing the worst possible situation encountered *in vivo* where the defibrillator paddles are placed in immediate contact with the ECG electrodes). Electrodes made of stainless steel, for example, tend to acquire offset voltages of several hundred mV for minutes and, consequently, no ECG trace is observable on the monitor (68).

Following the initial 5 s the EGC must not only be visible on the monitor but must also be recognizable and clinically useful. Hence, the stipulation that the offset voltage should not drift with time by more than $\pm 1\,mV \cdot s^{-1}$.

The UBTL results indicate good correlation exists between the results of this bench tests and animal tests, particularly at the higher recovery voltages encountered with non-Ag/AgCl electrodes.

Although only a very low percentage of ECG electrodes are, in fact, subjected to defibrillation impulses *in vivo*, the AAMI committee decided after some deliberation to insist that all ECG electrodes meet the proposed standard as it is impossible to guarantee that a given electrode would not be used in an emergency defibrillation situation.

Bias Current Tolerance. The observed dc voltage offset change across a pair of electrodes connected gel-to-gel shall not exceed 100 mV when the electrode pair is subjected to a continuous 200 nA dc current over the period recommended by the manufacturer for the clinical use of the electrodes. In no case shall this period be less than 8 h.

When a dc current passes through the metal-gel interface of an electrode, the electrode potential deviates from its equilibrium value and the electrode is said to be polarized. If the current is maintained indefinitely, the reactants become depleted causing the electrode potential to deviate further, possibly exceeding the limit allowable at the input of the ECG recording device.

Although most modern ECG recorders pass less than 10 nA of bias current through the electrodes, some older models can have bias currents as high as 1000 nA. A number of cardiac monitor manufacturers use dc bias currents to sense high electrode impedances to warn of disconnected leads or poorly affixed electrodes. The standard for cardiac monitors permits input bias currents of up to 200 nA. UBTL, therefore, adopted the 200 nA limit on the dc input bias current suggested for cardiac monitors for the tests. The ability of an electrode to cope with this value of bias current must therefore be demonstrated by not exceeding the AAMI dc offset requirement of 100 mV over the time period recommended by the manufacturer for the clinical use of the electrodes.

The 200 nA current level is generally well-tolerated by Ag/AgCl electrodes. Stainless-steel electrodes rapidly fail this test even at 10 nA with major increases in electrode potential.

Discussion. The AAMI standards bench tests are currently the only widely accepted electrode standard tests in use. The tests are simple and inexpensive to set up and have been widely embraced by manufacturers and users for production quality control purposes. One must bear in mind, however, that these tests evaluate only the electrode-gel interface and that they do not include the more important properties of the gel–skin interface. Assessment of the clinical performance of electrode impedance using the proposed bench tests is only relevant if the skin has been suitably abraded. Skin abrasion is not widely used by the clinical community and, hence, the relevance of at least some of the standard tests to the clinical situation is open to question.

Especially several decades ago, fulfillment of the AAMI requirements was commonly quoted as a guarantee of the high *in vivo* electrical performance of an electrode. An electrode with, for example, a dc offset of 1 mV was widely believed by customers to be a much better electrode than one with an offset of 5 mV. This naivety appears to be on the wane, however, and manufacturers and customers are shifting toward low cost electrodes that score less highly in the AAMI tests but are good enough for a given application.

The author once supplied a leading company with dry metal-loaded polymer electrodes. The company connected the electrodes together and tested them as per the AAMI standards (for pregelled electrodes). Perfect electrical performances were measured given that what was effectively being assessed was metal-to-metal contact. Direct current offsets of 0 mV were obtain. Once the dry electrodes were applied to a patient's skin, a less than favorable result was obtained.

The attitude to adopt, therefore, when interpreting AAMI standard bench tests results for pregelled, disposable ECG electrodes is that electrodes that meet the AAMI standards have a tendency rather than a certainty to perform well *in vivo*. Electrodes that perform better as per the bench tests do not necessarily perform better *in vivo*. They are a useful set of tests nonetheless.

The ANSI/AAMI standard tests were conceived such that the test apparatus needed can be readily assembled by an electrode manufacturer. However, one can can buy a convenient-to-use, custom-built electrode tester (as per AAMI standards) called the Xtratek electrode tester ET65A (Direct Design Corporation, Lenexa, Kansas.) (Fig. 56).

Electrocardiograph surface electrode testers also exist for the *in vivo* testing of the quality of (*1*) the design ECG electrodes, (*2*) the application of the electrodes, and (*3*) the skin preparation technique used.

The electrode tester generally measures the ac impedance and dc offset of the electrode-patient system. These measurements can be used, for example, in stress testing to decide if the skin sites have been sufficiently well prepared (i.e., contact impedances are low enough) to proceed with the clinical procedure. They can also be used to detect the presence of loose cables or bad contacts.



Figure 56. Early version of the Xtratek electrode tester ET65A. (Direct Design Corporation; Lenexa, Kansas.)

Standards for Stimulation Electrodes

Although not covered in this article, the following standards exist that stipulate minimum labeling, safety, and performance requirements for the given stimulators. The rationale for the standards is also presented.

- Transcutaneous electrical nerve stimulators ANSI/AAMI NS4.
- Implantable spinal cord stimulators ANSI/AAMI NS14.
- Implantable peripheral nerve stimulators ANSI/AAMI NS15.

Standards for Automatic External Defibrillators and Remote-Control Defibrillators. ANSI/AAMI DF 80 (2003)

AC Small Signal Impedance. The 10 Hz impedance for any of at least 12 electrode pairs connected gel-to-gel, at a level of impressed current not exceeding 100 μA peak-to-peak, shall not exceed 3 kΩ. The impedance at 30 kHz shall be less than 5 Ω. The rationale for this requirement is based on the performance criteria in ANSI/AAMI EC 12 for disposable ECG electrodes. Interestingly, the permissible gel-to-gel 10 Hz impedance for large-area defibrillation pads is higher than that allowed for small-area ECG electrodes. The gel-to-gel impedance measured at 30 kHz will be largely that of the gel pads as the interface impedances at this frequency will be almost zero.

AC Large Signal Impedance. The impedance of an electrode pair connected gel-to-gel, in series with a 50 Ω load and measured at the maximum rated energy of the defibrillator shall not exceed 3 Ω. A value of 50 Ω is thought to represent the typical (rather low) *in vivo* transthoracic impedance between the electrodes. One wants the delivered energy to be dissipated in the patient's chest and not in the electrodes where the wasted energy may give rise to skin burns. The above requirement is therefore thought to provide a reasonable limit on the impedance contributed to the overall impedance by the electrode pair during defibrillation (<6%).

Combined Offset Instability and Internal Noise. A pair of electrodes connected gel-to-gel shall generate, after a 1 min stabilization period, a voltage no greater than 100 μV peak-to-peak in the pass band of 0.5–40 Hz, for a period of 5 min following the stabilization period. The rationale for this requirement is based on the performance criteria in ANSI/AAMI EC 12 for Disposable ECG electrodes. The frequency range used is more limited in recognition that the cardiac monitor bandwidth is more appropriate in this application.

Defibrillation Recovery. The potential of a pair of gel-to-gel electrodes in series with a 50 Ω resistor and subjected to three shocks at 360 J or maximum energy at 1 min intervals shall not exceed 400 mV at 4 s and 300 mV at 60 s after the last shock delivery. The rationale for this requirement is largely based on the performance criteria in ANSI/AAMI EC 12 for Disposable ECG electrodes. An actual defibrillation impulse is applied instead of that from a simulation circuit. The offset voltage across the simulated electrode-patient load must return to below 400 mV within 4 s following the discharge (slightly different values, 300 mV and 5 s, are used in ANSI/AAMI EC 12). As the patient's chest is represented by the 50 Ω resistor, no need exists for the 2.5 factor used in ANSI/AAMI EC 12 to correlate bench test and *in vivo* results.

DC Offset Voltage. A pair of electrodes connected gel-to-gel shall, after a 1 min stabilization period, exhibit an offset voltage no greater than 100 mV. The rationale for this requirement is based on the performance criteria in ANSI/AAMI EC 12 for disposable ECG electrodes.

Universal-Function Electrodes. With conventional defibrillators, it has been customary to use separate pregelled ECG electrodes for monitoring and defibrillator paddle electrodes for defibrillation. The monitoring electrodes are not capable of effectively delivering a defibrillation shock, and the paddle electrodes have only limited monitoring capability. For recent applications, particularly automatic external defibrillation, it is very desirable to use self-adhesive pregelled disposable combination electrodes that perform well in the dual monitoring and defibrillation functions. These electrodes may also be used for delivery of transcutaneous pacing. Hence, combination electrodes may become preferred for defibrillation, and it is appropriate in a standard for defibrillators to consider their use and to outline a few requirements for them.

If the electrodes are designed and intended for use in multiple modes (i.e., monitoring, defibrillation, and pacing) the electrode shall meet all (of the above) requirements after 60 min of pacing at the maximum current output and maximum pacing rate through a pair of gel-to-gel electrodes in series with a 50 Ω resistor.

No general performance standards exist for combination pacing/defibrillation/monitoring electrodes, the (above) requirements define the basic minimum controls necessary to ensure safe and reliable operation.

Standards for Electrosurgical Devices. ANSI/AAMI HF 18 (2001)

Introduction. Although AAMI lays down stipulations for the testing of a range of parameters, only the key electrical performance requirements for the dispersive electrodes are reviewed below.

Maximum Safe Temperature Rise. The maximum patient tissue temperature rise shall not exceed 6 °C when the dispersive electrode carries a current of 700 mA under the test conditions below, unless the device is labeled in accordance with 4.1.4.2 (i.e., for use on infants). For devices labeled for use on infants, the maximum patient tissue temperature rise shall not exceed 6 °C when the dispersive electrode carries a current of 500 mA under the test conditions stipulated in the standard. In monopolar electrosurgical procedures, the dispersive electrode must be able to reliably conduct the required surgical current without generating a significant rise in skin temperature. It is widely accepted that the maximum safe skin temperature for short-term and long-term exposure is 45 °C, as normal resting skin temperature varies between 29° and 33 °C. Electrodes must not generate skin temperature increases approaching 12 °C. A 6 °C increase in temperature is therefore thought to represent an acceptable upper limit.

The temperature measurement method must have an overall accuracy of better than 0.5 °C and a spatial resolution of at least one sample per square centimeter of the electrode thermal pattern. The thermal pattern must include the area extending 1 cm beyond the geometry of the electrode under test. This degree of special resolution is stipulated as electrosurgical burns may be confined to very small areas and these must be detected. As current tends to flow to the edge of the electrode and spread out further in the skin, the test requires that the surround area of skin is also scanned.

The electrode under test is to carry a current from an electrosurgical generator of 700 $\mathrm{mA_{rms}}$ for 60 s, unless the device is labeled in accordance with 4.1.4.2, in which case the test current may be 500 mA. A current of 700 mA applied for 60 s yields a heating factor of 30 $\mathrm{A^2}$ s. [Heating Factor $= I^2t$ ($\mathrm{A^2s}$).] This value is far in excess of the maximum likely current and duration for a TUR (transurethral resection) procedure. A more realistic heating factor is less than 10 and, hence, the stipulated testing procedure is very conservative.

These tests must be conducted on human volunteers or on a suitably structured surrogate medium. When human volunteers are used, the tester must include a variety of body types in the sample group rather than concentrate on a single body type (thin, average, or thick layers of subcutaneous body fat). If surrogate media are used, the tester must demonstrate that the media are electrically and thermally similar to human volunteers. Human volunteer subjects are the reference standard. Current density distribution under an electrode depends on a wide range of factors, including the electrical properties of the skin and underlying tissues, hence, the need to test a given electrode on a wide range of individuals. The use of a surrogate material, even pig skin, which is commonly used, will not necessarily replicate with sufficient accuracy the clinical performance of the electrode. If a surrogate medium is used, the tester must demonstrate the equivalence of the test medium to human tissue. It is the Committee's view that no adequate surrogate medium has yet been suggested or used that has all of the properties of human tissue for the purpose of determining electrode performance.

Nessler et al. (149) point out that the above experiments are laborious, time-consuming, and expensive to perform. They have developed a new test device, swaroTEST, which includes a surrogate electronic skin, which, they claim, simulates the relevant electrical features of human skin and thus can replace the required volunteer experiments (Fig. 57). The device consists of a 3D resistor network representing the electric features of the skin and muscle tissue, and a temperature-sensing array (one transistor for each $\mathrm{cm^2}$) to measure the resultant temperature increase after a standardized current load (700 mA hf current during 60 s, proposed in the relevant AAMI HF-18 standard). The authors claim that a comparison of results obtained with their device and those with thermo camera images of



Figure 57. Swaro Test device with a measuring board electronic skin to simulate the electrical properties of human skin. It is hoped that this device will replace the human volunteer experiments required for ANSI.AAMI HF 18.

volunteer experiments correspond sufficiently well to justify the acceptance of their test device as a surrogate medium.

Electrode Contact Impedance. The electrode contact impedance must be low enough that the dispersive electrode represents the preferred current pathway, thus avoiding skin burns at alternative pathways. For conductive electrodes, the maximum electrode contact impedance shall not exceed 75 Ω over the frequency range of 200 kHz–5 MHz when measured as described on a human subject. The frequency range of 200kHz–5 MHz encompasses the frequency ranges of existing generators. As electrode-tissue impedance increases as applied current decreases, the committee decided on an impedance measuring current of 200 mA as it represents the lower limit of average currents reported for TUR procedures. Under these conditions, a maximum contact impedance value of 75 Ω was judged an acceptable for the conductive electrodes.

For capacitive electrodes, the minimum capacitance shall be no less than 4 nF (0.004 μF) when measured as described. In this case, electrode contact impedance is measured by placing the capacitively coupled dispersive electrode under test on a rigid metal plate larger than the electrode contact area. The test current and frequencies are the same as those specified for conductive electrodes. Their impedance characteristics are described in terms of capacitance as their impedances vary as the inverse of the frequency. The majority of capacitive electrodes that have been found to be clinically acceptable typically have a capacitance value of 4 nF, hence the minimum acceptable capacitance value specified by the Committee.

SUMMARY

With external biosignal monitoring electrodes, difficult challenges exist in the exciting new area of personalized health. Such electrodes must form part of the patient's (or health-conscious citizen's) clothing and must continue to work, day after day, wash after wash, without gelling or preparation of any kind, without suffering from motion artifacts, and without causing skin irritation, which is no mean achievement.

An old monitoring problem still remains to be adequately conquered. A convenient and rapid method of applying many high performance electrodes to the head of a patient for EEG measurement awaits invention. The problem (and that of ECG ambulatory monitoring above) can be side-stepped to some extent by finding new electrode positions (montages or leads) that avoid the most problematic skin sites, hairy head in EEG and muscle and flabby areas in ECG.

For external stimulation, exciting new areas include public access defibrillation. The electrodes and their application to the victim must be almost literally fool-proof, given the seriousness of the possible consequences for all concerned. The electrodes must work after having been stored in the most inhospitable locations and possibly under extreme temperature fluctuations, for example, in the trunk of a car in the desert. In the more mainstream areas of cardiac pacing and defibrillation and electrosurgery, the optimal distribution of current density under the electrodes remains a goal still to be achieved. The solution to this problem offers the hope of decreased electrode areas and the design of truly multifunction pads.

The integration of electrodes into garments for FES and body toning is a relatively new area with considerable possibilities.

At present, implant electrodes and associated technologies already offer amazing potential for the deaf, lame, and even the blind. The development of multimicroelectrode arrays and waveforms that can help optimally shape the electrical fields to facilitate more effective and natural stimulation is a thrilling prospect. The interface properties of the microelectrodes will require further research so as to offset the potentially high interface impedances. Ideas already exploited in cardiac pacing, for example, may prove rewarding when adapted for these areas.

It is hard to overstate the potential of research being undertaken in the area of brain–machine interface. We live in exciting times.

BIBLIOGRAPHY

Cited References

1. Gatzke RD. In: Miller HA, Harrison DC, editors. The electrode: A measurement systems viewpoint. Biomedical Electrode Technology. New York: Academic Press; 1974.
2. Janz GJ, Ives DJG. Silver-silver chloride electrodes. Ann NY Acad Sci 1968;148:210–221.
3. Webster JG. Medical Instrumentation: Application and Design. 3rd ed. New York: John Wiley & Sons; 1998.
4. Cheney M, Isaacson D, Newell JC. Electrical impedance tomography. SIAM Rev 1999;41:85–101.
5. McAdams ET, Jossinet J, Lackermeier A, Risacher F. Factors affecting the electrode-gel-skin interface impedance in electrical impedance tomography. Med Biol Eng Comput 1996;34(6):397–408.

6. Singh S, Singh J. Transdermal drug delivery by passive diffusion and iontophoresis: A review. Med Res Rev 1993;13(5):569–621.
7. Bard AJ, Faulkner LR. Electrochemical Methods. New York: John Wiley & Sons; 1980.
8. Almasi JJ, Hart MW, Schmitt OH, Watanabe Y.Bioelectrode voltage offset time profiles and their impact on ECG measurement standards. Can Med Biol Eng Conf 4th, Winnipeg, Manitoba, Canada, 1972.
9. McAdams ET. Effect of surface topography on the electrode-electrolyte interface impedance, Part 1: The high frequency, small signal interface impedance. Surface Topogr 1989;2: 107–122.
10. Fricke H. The theory of electrolytic polarization. Philos Mag 1932;7:310–318.
11. Cole KS, Curtis HJ. Transverse electric impedance of squid giant axon. J Gen Physiol 1938;22:3764.
12. Sluyters-Rechbach M, Sluyters JH. Sine wave methods in the study of electrode processes. In: Bard AJ, editor. Electroanalytical Chemistry, vol. 4. New York: Marcel Dekker; 1970. pp 1–128.
13. De Levie R. The influence of surface roughness of solid electrodes on electrochemical measurements. Electrochim Acta 1965;10:113–130.
14. de Levie R. On the impedance of electrodes with rough interfaces. J Electroanal Chem 1989;261:1–9.
15. Maritan A, Toigo F. On skewed arc plots of impedance of electrodes with an irreversible electrode process. Electrochim. Acta 1990;35:141–145.
16. McAdams ET. Effect of surface topography on the electrode-electrolyte interface impedance, Part 2: The low frequency (F<1 Hz), small signal interface impedance. Surface Topogr 1989;2:223–232.
17. Bergveld P. Med Biol Eng Comput 1976;14:479–482.
18. Brummer SB, Robblee LS, Hambrecht FT. Criteria for selecting electrodes for electrical stimulation: Theoretical and practical considerations. Ann NY Acad Sci USA 1983;405: 159–171.
19. Brummer SB, Turner MJ. Electrical stimulation of the nervous system: The principle of safe charge injection with noble metal electrodes. Bioelectrochem Bioenerget 1975; 2:13–25.
20. Dymond AM. IEEE Trans BME 1976;23:274–280.
21. Lilly JC, Hughes JR, Alvord EC, Galkin TW. Brief, noninjurious electric waveform for stimulation of the brain. Science 1955;121:468–469.
22. Weinman J. Biphasic stimulation and electrical properties of metal electrodes. J Appl Physiol 1965;20:787–790.
23. Fischler H, Schwan HP. Polarisation impedance of pacemaker electrodes: *In vitro* simulating practical operation. Med Biol Eng Comput 1981;19:579–588.
24. Schwan HP. Electrode polarization impedance and measurements in biological materials. Ann NY Acad Sci USA 1968;148:191–209.
25. Schwan HP. Alternating current electrode polarisation. Biophysik 1966;3:181–201.
26. Simpson RW, Berberian JG, Schwan HP. Nonlinear AC and DC polarization of platinum electrodes. IEEE Trans Biomed Eng 1980;27:166–171.
27. Jaron D, Briller SA, Schwan HP, Geselowitz DB. Nonlinearity of cardiac pacemaker electrodes. IEEE Trans Biomed Eng 1969;16:132–138.
28. Onaral B, Schwan HP. Linear and non-linear properties of platinum electrode polarization: Part 1.Frequency dependence at very low frequencies. Med Biol Eng Comput 1982;20:299–306.
29. McAdams ET, Henry P, Anderson JMcC, Jossinet J. Optimal electrolytic chloriding of silver ink electrodes for use in electrical impedance tomography. Clin Phys Physiol Meas 1992;13(Suppl 1):19–23.
30. McAdams ET, Jossinet J. The importance of electrode-skin impedance in high resolution electrocardiography. Automedica 1991;13:187–208.
31. McAdams ET, Jossinet J. A Physical Interpretation of Schwan's limit voltage of linearity. Med Biol Eng Comput 1994; March: 126–130.
32. McAdams ET. Jossinet J. DC nonlinearity of the solid electrode-electrolyte interface impedance. Inn Tech Biol Med 1991;12:329–343.
33. McAdams ET, Jossinet J. A physical interpretation of Schwan's limit current of linearity. Ann Biomed Eng 1992; 20:307–319.
34. K Stokes. Cardiac pacing electrodes. Proc IEEE 1996;84(3): 457–467.
35. Stokes K. Implantable pacing lead technology. IEEE Eng Med Biol 1990;9(2):43–49.
36. Williams DF. The Williams Dictionary of Biomaterials. Liverpool University Press; 1999.
37. Geddes LA. Electrodes and the Measurement of Bioelectric Events. New York: John Wiley & Sons; 1972.
38. Crenner F, Angel F, Ringwald C. Ag/AgCl electrode assembly for thin smooth muscle electromyography. Med Biol Eng Comput 1989;27:346–356.
39. Kingma YJ, Lenhart J, Bowes KL, Chambers MM, Durdle NG. Improved Ag/AgCl pressure electrodes. Med Biol Eng Comput 1983;21:351–357.
40. Geddes LA, Baker LE, Moore AG. Optimum electrolytic chloriding of silver electrodes. Med Biol Eng 1969;7:49–56.
41. Heath R. Tin-stannous chloride electrode element. U.S. Patent 4,852,585, 1989.
42. Mannheimer JS. Lampe GN. Clinical Transcutaneous Electrical Nerve Stimulation. Philadelphia, F.A. Davis, PA; 1987.
43. Prausnitz MR, Bose VG, Langer R, Weaver JC. Electroporation of mammalian skin: A mechanism to enhance transdermal drug delivery. Proc Natl Acad Sci USA 1993;90:10504–20508.
44. Brown L, Langer R. Transdermal derlivery of drugs. Ann Rev Med 1988;39:221–229.
45. Rosendal T. Further studies on the conducting properties of human skin to direct and alternating current. Acta Physiol Scand 1945;8:183–202.
46. Rosendal T. Concluding studies on the conducting properties of human skin to alternating current. Acta Physiol Scan 1945;9:39–49.
47. Salter DC. A study of some electrical properties of normal and pathological skin in vivo. Ph.D. dissertation, University of Oxford. Oxford (UK): 1980.
48. Klingman AM. Skin permeability: Dermatologic aspects of transdermal drug delivery. Am Heart J 1984;108(1):200–207.
49. Reilly JP. Electrical Stimulation and Electropathology. Cambridge, UK: Cambridge University Press; 1992.
50. Chien YW. Transdermal controlled-release drug administration.In: Swarbrick J. editor Novel Drug Delivery Systems. New York: Marcel Dekker Inc.; 1982. p 149.
51. Edelberg R. Electrical properties of the skin. In: Elden HR, editor. A Treatise of the Skin. New York: John Wiley & Sons; 1971.
52. Yamamoto Y, Yamamoto T. Dispersion and correlation of the parameters for skin impedance. Med Biol Eng Comput 1978;16:592–594.

53. Chien YW. Development of transdermal drug delivery systems. Drug Develop Industr Pharm 1987;13(4&5):589–651.
54. Rothman S. Electrical behavior. In:Physiology and Biochemistry of the Skin. Chicago (IL): The University of Chicago Press; 1956. p 9–25.
55. Lawler JC, Davis MJ, Griffith EC. Electrical characteristics of the skin. J Invest Dermatol 1960; 301–308.
56. Rosell J, Colominas J, Riu P, Pallas-Areny R, Webster JG. Skin impedance from 1 Hz to 1 MHz. IEEE Trans Biomed Eng 1980;35:649–651.
57. Almasi JJ, Schmitt OH. Systemic and random variations of ECG electrode system impedance. Ann N Y Acad Sci 1970;170:509–519.
58. Grimnes S. Dielectric breakdown of human skin in vivo. Med Biol Eng Comput 1983;21:379–381.
59. Schmitt OH, Almasi JJ. Electrode impedance and voltage offset as they affect efficacy and accuracy of VCG and ECG measurements. Proc. XIth International Vectorcardiography Symposium, New York, 1970; 245–253.
60. Yamamoto T, Yamamoto Y. Analysis for the change of skin impedance. Med Biol Eng Comput 1977;15:219–227.
61. Searle A, Kirkup L. A direct comparison of wet, dry and insulating bioelectric recording electrodes. Physiol Meas 2000;21:271–283.
62. McAdams ET, Lackermeier A, Woolfson ET, Moss GP, McCafferty DF, In vivo ac impedance monitoring of percutaneous drug delivery. Proc. 9th Int. Conf. on BioImpedance, Heidelberg, Germany, 1995: 344–347.
63. De Talhouet H, Webster JG. The origin of skin-stretch-caused motion artefacts under electrodes. Physiol Meas 17:81–93.
64. Tam HW, Webster JG. Minimizing motion artifact by skin abrasion. IEEE Trans Biomed Eng 1977; BME 24:134–140.
65. Zinc R, Distortion and interference in the measurement of electrical signals from the skin (ECG, EMG, EEG). Innovation and Technology in Biology and Medicine, 12, special issue. 1991; 1: 46–59.
66. McLaughlin J, McAdams ET, Anderson JMcC. Novel dry electrode ECG sensor system. 16th Annual Int Conf IEEE Eng Med Biol Soc Baltimore (MD), Nov. 1994:804.
67. Jossinet J, McAdams ET. Skin Impedance. Innovation and technology in biology and medicine, 12, special issue. 1991;1:21–31.
68. Carim HM. Bioelectrodes. In: Webster JG. editor Encyclopaedia of Medical Devices and Instrumentation. New York: Wiley & Sons; 1988. p 195–226.
69. Oh SY, Leung L, Bommannan D, Guy RH, Potts RO. Effect of current, ionic strength and temperature on the electrical properties of skin. J Controlled Release 1993;27:115–125.
70. Olson WH, Schmincke DR, Henley BL. Time and frequency dependence of disposable ECG electrode-skin impedance. Med Instrum 1979;13:269–272.
71. McAdams ET. Surface biomedical electrode technology. Int Med Device Diagnost Ind 1990; 44–48.
72. McAdams ET, McLaughlin JA, Anderson J McC. Multi-electrode systems for electrical impedance tomography. Physiol Meas 1994;15:A101–A106.
73. McAdams ET, McLaughlin J, Brown BN, McArdle F. In: London HD, editor. The NIBEC EIT harness, Clinical and Physiological Applications of Electrical Impedance Tomography. Chapt 8, UCL Press; 1993. p 85–92.
74. McAdams ET, Jossinet J. Hydrogel electrodes in bio-signal recording. Proceedings of the 12th Annual International Conference of the IEEE, Philadelphia, PA: Engineering in Medicine and Biology Society; 1990: 1490–1491.
75. McAdams ET, Lackermeier A, Jossinet J. AC impedance of the hydrogel-skin interface. 16th Annual Int. Conf IEEE Eng in Med and Biol Soc Baltimore (MD), 1994: 870–871.
76. Carim HM, Hawkinson RW. EKG electrode electrolyte-skin AC impedance studies. Proc. 4th Ann Conf IEEE Eng Med Biol Soc 1982:503–504.
77. Yamamoto T, Yamamoto Y. Electrical properties of the epidermal stratum corneum. Med Biol Eng 1976;14:151–158.
78. Geddes LA. A. Historical perspectives 2: The electrocardiograph. In: Bronzino JD, editor. The Biomedical Engineering Handbook. Boca Raton FL: CRC Press; 1995; p 788–798.
79. Waller AD. A demonstration on man of electromotive changes accompanying the heart's beat. J Physiol 1887; 8:229–234.
80. Waller AD. On the electromotive changes connected with the beat of the mammalian heart, and of the human heart in particular. Phil Trans R Soc London Ser B 1989;180:169–194.
81. Waller AD. Introductory address on the electromotive properties of the human heart. Brit Med J 1888;2:751–754.
82. Barker LF:. Electrocardiography and phonocardiography: A collective review. Bull Johns Hopkins Hosp 1910;21:358–359.
83. Rowbottom ME, Susskind C. In: Electricity and Medicine: History of their Interaction. San Francisco (CA): San Francisco Press; 1984.
84. Barron SL. The development of the electrocardiograph in Great Britain. Br Med J 1950;1:720–725.
85. Lewes D. Multipoint electrocardiography without skin preparation. Lancet 1965;2:17–18.
86. Wolferth CC, Wood FC. The electrocardiographic diagnosis of coronary occlusion by the use of chest leads. Am J Med Sci 1932;183:30–35.
87. Barnes AR, et al. Standardization of precordial leads. Am Heart J 1938;15:235–239.
88. Burch GE, DePasquale NP: A History of Electrocardiography with a New Introduction by Joel D Howell, 2nd ed. San Francisco, CA: Jeremy Norman; 1990.
89. Ungerleider HE. A new precordial electrode. Am Heart J 1939;18:94.
90. Welch W. Self-retaining electrocardiographic electrode. JAMA 1951;147:1042.
91. Jasper HH, Carmichael L. Electrical potentials from the intact human. Science 1935;81:51–53.
92. Khan A, Greatbatch W. Physiologic electrodes. In: Ray CD. editor. Medical Engineering. Chicago, IL: Year Book Medical Publishers; 1974.
93. Manley AG, Medical electrode. US patent 3,977,392, 1976.
94. K Krug, Marecki NM. Porous and other medical and pressure sensitive adhesives. Adhes Age 1983;26(12):19–23.
95. Hymes AC. Monitoring and stimulating electrode. U.S. Patent 4,274,420, June 23, 1981.
96. Dempsey GJ, McAdams ET, McLaughlin J, Anderson JMcC. NIBEC cardiac mapping harness. 14th Annual Int. Conf. IEEE Eng. In Med and Biol Soc Paris, France, Nov 1992: 2702–2703.
97. Lymberis A. Research and Development of Smart Wearable Health Applications: The Challenge Ahead, Wearable eHealth Systems for Personalised Health Management, Studies in Health Technology and Informatics 108. Lymberis A, de Rossi D, editors, IOS Press; 2004.
98. Axisa F, Schmitt PM, Gehin C, Delhomme G, McAdams E, Dittmar A. Flexible technologies and smart clothing for citizen medicine, home healthcare and disease prevention. IEEE Trans Inform Technol Biomed 2005;9(3): 325–336.
99. Adams G. An Essay on Electricity. London; 1785.

100. Aldini G. Account of Late Improvements in Galvanism. London; 1803.
101. Duchenne GBA. In: De l'Électrisation Localisée et de son Application á la Physiologie, á la Pathologie et à la Thérapeutique. 1855.
102. Duchenne GBA. In: Baillière JB et al., editors. Mécanisme de la Physionomie Humaine. 1876.
103. Schechter DC. In: Exploring the Origins of Electrical Cardiac Stimulation. Medtronic; 1983.
104. Robinson AJ, Snyder-Mackler L. Clinical Electrophysiology: Electrotherapy, Electrophysiologic Testing. Baltimore (MD): Williams and Wilkins; 1995.
105. Low J, Reed A, Electrotherapy Explained: Principles and Practice. Oxford: Butterworth–Heinmann Ltd; 1994.
106. Stankevich BA. 4% of professional liability claims involve electromedicine equipment. Mod Health Care 1980;10(12): 74–76.
107. Pearce JA. The thermal performance of electrosurgical dispersive electrodes. Ph.D. dissertation. Purdue University, West Lafayette (IN); 1980.
108. Wiley JD, Webster JG. Analysis and control of the current distribution under circular dispersive electrodes. IEEE Trans Biomed Eng 1982;29:381–385.
109. Caruso PM, Pearce JA, DeWitt DP. Temperature and current density distributions at electrosurgical dispersive electrode sites. Proc 7th N Engl Bioeng Conf., Troy, New York, March 22–23, 1979: 373–376.
110. V Krasteva, Papazov S. Estimation of current density distribution under electrodes for external defibrillation. Bio-Medical Engineering Online, 2002; 1:7. Available http://www.biomedical-engineering-online.com/content/1/1/7.
111. Y Kim, Schimpf PH. Electrical behavior of defibrillation and pacing electrodes. Proc IEEE 1996;84(3):446–456.
112. Kim Y, Fahy JB, Tupper B. Optimal electrode designs for electrosurgery, defibrillation, and external cardiac pacing IEEE Trans Biomed Eng 1986;33:845–853.
113. Netherly SG, Carim HM. Biomedical electrode with lossy dielectric properties. US pat 5,836,942, 1998.
114. Ferrari RK. X-ray transmissive transcutaneous stimulating electrode. US pat 5,571,165, 1996.
115. McAdams ET, Andrews P. Biomedical electrodes and biomedical electrodes for electrostimulation. US pat 2003, 134,545, 2003.
116. Szeto AYJ. Pain relief from transcutaneous electrical nerve stimulation (TENS). In: Webster JG. ed. Encyclopedia of Medical Devices and Instrumentation. New York: John Wiley & Sons; 1988. p 2203–2220.
117. AXELGAARD J. Reverse current controlling electrode. US pat 2004,158,305, 2004.
118. Sarlandière. "Mémoires sur l'électropuncture considérée comme moyen nouveau de traiter efficacement la goutte, les rhumatismes et les affections nerveuses. Paris, 1825.
119. Hyman AS. Resuscitation of the stopped heart by intracardial therapy. Arch Intern Med 1932;50:283.
120. Mittal T. Pacemakers – A journey through the years. Ind J Thorac Cardiovasc Surg 2005;21:236–249.
121. Myers GH, Parsonnet V. Pacemaker electrodes In: Myers GH, Engineering in the Heart and Blood. New York: Wiley-Interscience; 1969.
122. Greatbatch W, Holmes CF. History of implantable devices. IEEE Eng Med Biol 1991; Sept: 36–49.
123. Chardack WM, Gage AA, Greatbatch W. Correction of complete heart block by a self-contained and subcutaneously implanted pacemaker. J Thorac Cardiovasc Surg 1961;42: 418.
124. Lagergren H, Johansson L. Intracardiac stimulation for complete heart block. Acta Chir Scand 1963;125:562–566.
125. Parsonnet V, Zucker IR, Asa MM.Preliminary investigation of the development of a permanent implantable pacemaker utilizing an intracardiac dipolar electrode. Clin Res 1962; 10:391.
126. Timmis G. The electrobiology and engineering of pacemaker leads. In: Saksena S, Goldschlager N. eds. Electrical Therapy for Cardiac Arrhythmias. New York: Saunders W.B. Co.; 1990.
127. Admundson DC, McArthur W, Mosharrafa M. The porous endocardial electrode. PACE 1979;2:40–50.
128. Lagergren H, Edhag O, Wahlberg I. A low threshold non-dislocating endocardial electrode. J Thorac Cardiovasc Surg 1976;72:259.
129. Lewin G, Myers GH, Parsonnet V, Zucker IR. A non-polarizing electrode for physiological stimulation. Trans Am Soc Artific Intern Organs 1967;13:345.
130. Ellenbogen KA, Wood MA. Cardiac Pacing and ICDs. New York: Blackwell Science Inc; 2002.
131. Mond H, Stokes KB. The electrode-tissue interface: The revolutionary role of steroid elution. PACE 1991;15:95–107.
132. Mond HG, Stokes KB. The steroid-eluting electrode: A 10-year experience. Pacing Clin Electrophysiol 1996 Jul; 19(7):1016–1020.
133. Lenarz T, Battmer R-D, Goldring JE, Neuburger J, Kuzma J, Reuter G. New electrode concepts (Modiolus–Hugging Electrodes). Adv Otorhinolaryngol Basel Karger 2000;57:347–353.
134. Maynard EM. Visual prostheses. Annu Rev Biomed Eng 2001;3:145–168.
135. Peckham PH, Knutson JS. Functional electrical stimulation for neuromuscular applications. Annu Rev Biomed Eng 2005;7:327–360.
136. Rutten WLC. Selective electrical interfaces with the nervous system. Annu Rev Biomed Eng 2002;4:407–452.
137. Weiland JD, Liu W, Humayun MS. Retinal prosthesis. Annu Rev Biomed Eng 2005;7:361–401.
138. Drake KL, Wise KD, Farraye J, Anderson DJ, BeMent SL. Performance of planar multisite microprodes in recording extracellular single-unit intracortical activity. IEEE Trans Biomed Eng 1988;35:719–732.
139. Schwartz AB. Cortical neural prosthetics. Annu Rev Neurosci 2004;27:487–507.
140. Aguiló J. Microprobe multisensor for graft viability monitoring during organ preservation and transplantation. 2nd Annual International IEEE-EMB Special Topic Conference on Microtechnologies in Medicine & Biology, Madison, WI. February 2002; 15–20.
141. Mastrototaro JJ, Massoud HZ, Pilkington TC, Ideker RE. Rigid and flexible thin-film multielectrode assays for transmural cardiac recording. IEEE Trans Biomed Eng 1992; 39:271–279.
142. Linquette-Mailley SC, Hyland M, Mailley P, McLaughlin J, McAdams ET. Electrochemical and structural characterisation of electrodeposited iridium oxide thin film electrodes applied to neurostimulating electrical signal. Mater Sci Eng 2002;21:167–175.
143. Mortimer JT, Bhadra N. Peripheral nerve and muscle stimulation. In: Horch KW, Dhillon GS, editors. Neuroprosthetics: Theory and Practice (Series on Bioengineering & Biomedical Engineering), vol. 2. New York: World Scientific; 2004. p 638–744.
144. Hyland M, McLaughlin J, Zhou DM, McAdams E. Surface modification of thin film gold electrodes for improved in vivo performance. Analyst 1996;121:705–709.
145. Rieger R, Taylor J, Comi E, Donaldson N, Russold M, Mahony CMO, McLaughlin JA, McAdams E, Demosthenous A, Jarvis JC. Experimental determination of compound A-P

direction and propagation velocity from multi-electrode nerve cuffs. Med Biol Eng Comput Phys 2004;26:531–534.
146. Prohaska OJ, Olcaytug P, Pfundner P, Dragaun H. Thin film multiple electrode probes: Possibilities and limitations. IEEE Trans Biomed Eng 1986;33:223–229.
147. Schoenberg AG, Klingler DR, Baker CD, Worth NP, Booth HE, Lyon PC. Final report:Development of test methods for disposable ECG Electrodes. UBTL Technical Report No. 1605–005, Salt Lake City (UT); 1979.
148. Hollander JI, ECG-Electrodes.Report No. 83.336, MFI-TNO, Utrecht, The Netherlands, 1983.
149. Nessler N, Reischer W, Salchner M. Electronic skin replaces volunteer experiments. Measure Sci Rev 2003;3(2):71–74.

Reading List

Bell GH, Knox AC, Small AJ. Electrocardiography electrolytes. Br Heart J 1939;1:229–236.
Geddes LA, Baker LE. Principles of Applied Biomedical Instrumentation, 3rd edition. New York: John Wiley & Sons; 1989.
Licht S. History of electrotherapy. In: Licht S. ed. Therapeutic Electricity and Ultraviolet Radiation. New Haven, CT: Elizabeth Licht Pub; 1959. p 1–69.

See also DEFIBRILLATORS; ELECTROCARDIOGRAPHY, COMPUTERS IN; ELECTROENCEPHALOGRAPHY; ELECTROSURGICAL UNIT (ESU); FUNCTIONAL ELECTRICAL STIMULATION; TRANSCUTANEOUS ELECTRICAL NERVE STIMULATION (TENS).

BIOFEEDBACK

JOHN C. ARENA
VA Medical Center and Medical College of Georgia
TRISHUL DEVINENI
Conemaugh Health System
EDWARD J. MCGOWAN
E.J. McGowan & Associates

INTRODUCTION

Biofeedback is a term that first arose in the 1960s for a methodology that uses instrumentation to record the physiological responses of organisms and then in real time give information about those physiological responses back to the organism. It is presumed that by getting such timely feedback about physiological responding, the organism will learn, through a trial and error basis, how to control the desired physiological response.

The most concise definition of biofeedback is probably that of Olton and Noonberg (1), who characterized it as, "any technique that increases the ability of a person to control voluntarily physiological activities by providing information about those activities" (p. 4). In practice, the process of clinical biofeedback training involves the use of a machine (usually a computer-based system in contemporary applications), which allows a therapist to monitor the patient's bodily responses (most commonly surface muscle tension or surface skin temperature). Information concerning the patient's physiological responses are then relayed back to the patient, generally either through an auditory modality (a tone that goes higher or lower depending on, say, electrical activity of the target muscles increasing or decreasing) and/or a visual modality (now usually a computer screen where, e.g., surface skin temperature is sampled and then graphed on a second by second basis in real time). Through this physiological feedback, it is anticipated that the patient will learn how to control his/her bodily responses through mental means.

Biofeedback arose as an application of the learning theories of B.F. Skinner, Hull, Thorndike, Dollard and Miller, and John Watson. In particular, Neal Miller postulated that the established principles of learning that had so far been applied to overt behaviors could validly be applied to behaviors that were covert and presumed not under voluntary control.

Classical conditioning is also referred to as Pavlovian Conditioning after the seminal work of Russian scientists Pavlov and Sechenov in the early twentieth century. Classical conditioning is a laboratory learning paradigm by which a neutral stimulus (conditioned stimulus; CS) comes to elicit a new response (conditioned response; CR) by repeated pairing in close temporal proximity with another stimulus (unconditioned stimulus; UCS) that already elicits that response (unconditioned response; UCR). In subsequent presentations of the CS, the organism will then emit the UCR without pairing of the UCS. For example, the UCS might be food and the UCR is salivation, the CS, the ringing of a bell, is presented immediately prior in temporal pairing with the UCS, food. After repeated pairing of the ringing bell with food, the organism will come to salivate in response to the bell's ringing. The behaviors conditioned in this paradigm are typically unlearned, such as most physiological responses utilized in biofeedback practice. However, the learning paradigm most often appealed to as the theoretical underpinning of the field of biofeedback is not classical conditioning. Rather, biofeedback is generally considered a form of operant conditioning. This learning theory postulates that the consequence of a response changes the likelihood that the organism will produce that response again. The essential assumption of operant conditioning is that behavior is lawful and follows the rules of cause and effect and probability.

A basic supposition of operant conditioning is, if you wish a behavior to continue, you reinforce or reward that behavior. If you wish a behavior to decrease, or to stop completely, you do not reinforce that behavior. Thus, within the theoretical framework of operant conditioning, the main way that you strengthen a behavior is to follow it in close temporal proximity with a reward. The definition of a reinforcer is any stimulus change that occurs after a response and tends to increase the likelihood that a response will be repeated. It is important that the reinforcer follow the desired behavior quickly such that the delay in the presentation of the reward is kept to an optimally short delay. As the delay in the reward increases, the effectiveness of the reinforcer is generally decreased. There are many examples of positive reinforcement in our everyday life—receiving a bonus for outstanding work, receiving an A in a course for intensive studying, scoring a touchdown in a football game and the crowd's adulation.

In addition to positive reinforcement, there are three other possible consequences to behavior in operant conditioning: (a) Negative reinforcement involves the removal of a consequence to a response that results in reduced likelihood that the behavior will be repeated in the future. (b) Positive punishment involves adding a consequence when a response is performed that serves to decrease the likelihood of the response occurring in the future. Examples are plentiful: child misbehaves, parent scolds child, child less likely to misbehave; drive over the speed limit, get ticket, less likely to speed; do poorly at work, get demoted, less likely to perform poorly on the job. Negative punishment involves the removal of a consequence to a behavior that serves to reduce the likelihood of that behavior occurring in the future. An examples is a parent playing with their child who is clearly enjoying the playtime; the child starts to yell loudly, the parent stops playing with the child, parent less likely to engage in positive play with the child. In clinical biofeedback applications, these other types of reinforcement contingencies are rarely used, with biofeedback clinicians preferring to use positive rewards to influence behavior.

Perhaps the most important principle in operant conditioning that directly involves clinical biofeedback training is that of shaping. Shaping is the learning process by which the predefined target response is achieved through gradual and systematic reinforcement. The training begins with a simple, existing response and basic criteria for reinforcement, with gradually more stringent criteria applied for reinforcement in order to achieve more complex and reliable responses. After the initial behavior is reliably performed, reinforcement is given contingent on the performance of more complex or difficult responses. This pattern of increasingly stringent contingent reinforcement continues until the final target behavior is achieved. Shaping can be assisted by modeling the skill to be learned before shifting the reinforcement schedule. In clinical biofeedback, the target behavior in shaping is often tailored to the individual learning style and abilities of the patient. For example, a patient undergoing EMG biofeedback training may be initially reinforced for detecting gross changes in electrical activity in a particular muscle group. Following the initial success, the reinforcement is tapered and made contingent on the patient being able to detect ever more subtle changes in muscular tension in the target region. This may continue until the patient is unable to further demonstrate more refined skill in detecting muscle tension.

There are other principles within operant conditioning that also apply to biofeedback practice. One of these involves discrimination training, in which the organism demonstrates the ability to differentiate between at least two stimulus conditions by emitting a different response to each stimuli. In clinical biofeedback, the concept of discrimination applies to the patients' ability to distinguish relatively subtle differences in physiological states. Another important principle, indeed the mortar that lays the foundation of clinical biofeedback training, is the concept of generalization: If a response is conditioned to one stimulus, the organism may also respond to a similar stimulus (generalization), but not to a dissimilar stimulus (discrimination). Discrimination learning is a goal in the early stages of biofeedback training, while generalization is a longer range goal. Clearly, the overarching aim of clinical biofeedback training is to take the learned process applied in the office setting and have that learning process come to apply to the everyday "real world" setting.

In addition to basic operant conditioning principles, there are general principles in basic psychophysiology that are important in clinical biofeedback training. The law of initial values states that the autonomic nervous system response to stimulation is a function of the prestimulus level (2). The higher the level of the response measure prior to a stressful stimulus being presented, the smaller the increase in response to the stressor, which is often referred to as a ceiling effect. Conversely, the higher the level of the measure prior to a relaxing stimulus being presented, the larger the decrease in response to the relaxing stimulus. When prestimulus response values are low prior to the presentation of a relaxing stimulus, this will lower the magnitude of the response and is often referred to as a floor effect. While the law has been shown to generally hold for measures of respiration and cardiovascular activity (such as heart rate and the vasomotor response), measures such as salivation and electrodermal response have not been found to be influenced by prestimulus values.

Homeostasis refers to the tendency of any organism to strive to maintain a state of equilibrium or rest. Homeostasis is believed to be maintained by a negative feedback loop, which is a theorized set of bodily mechanisms that provide information. This information directs the organism's physiological systems to decrease activity if levels of functioning are higher than normal, or to increase activity if levels are diminished relative to normal. Thus, all organisms strive to return to prestimulus levels of physiological arousal when presented with any stimulus.

Theories Underlying Clinical Biofeedback Training

There are two general theories underlying the use of biofeedback for most chronic benign medical disorders, such as anxiety, headache, musculoskeletal pain, and incontinence (3). The first is a direct psychophysiological theory, which attributes the etiology and/or maintenance of the disorder to specific physiological pathology. This biofeedback training modulates in a therapeutic direction. For example, it has traditionally been assumed that tension headache is caused by sustained contraction of skeletal muscles in the forehead, neck, and shoulder regions. Through the use of biofeedback, the patient learns to decrease muscle tension levels, leading to a decrease in headache activity. The second theory is predominantly psychological and postulates that there is a relationship between situational stress and the disorder in question. Through the use of biofeedback, the patient learns to regulate physiological responses such as muscle tension levels or sympathetic nervous system activity. This regulation leads to a decrease in overall stress levels, which brings about symptomatic relief. This amelioration of symptoms brought about by the learning of voluntary control of specific peripheral responses is postulated to be underpinned by central changes that occur along pain-relay and sympathetic pathways. For the case of headache treatment, this means that both muscle relaxation and hand warming may indirectly dampen central brain mechanisms involved in the onset of headache. It is not necessary to view these theories as competing; they may be more appropriately viewed as complementary. Most clinicians subscribe to both theories, depending on the patient's presenting problem, clinical findings, and medical history.

Biofeedback Modalities and Instrumentation

Biofeedback instruments are first and foremost psychophysiological measuring instruments, to which has been added the capability to display the value of the measured parameter(s) in a form understandable to the subject. Feedback can be visual, auditory, or tactile.

The physiological measures generally employed in clinical biofeedback training are surface electromyographic activity (EMG) and skin surface temperature. Less often used physiological responses include measures of neuronal activity using electroencephalography (EEG), and measures of electrodermal response (skin resistance, skin conductance), cardiovascular activity (simple heart rate, heart rate variability, blood pressure, and vasomotor activity), and respiration (generally, respiration rate and depth).

Biofeedback instruments can be used to gain insight into a subject even if biofeedback therapy is not the goal. When assessment is the goal, care must be taken that the results are not contaminated by unintended biofeedback, such as the subject viewing the display. Subject spatial position with respect to windows, doors, and the professional must also be considered to avoid influencing the results. Environmental control of ambient temperature, humidity, and drafts is strongly recommended to minimize effects of these stressors on the subject.

Biofeedback instruments fall into three categories: research, clinical, and trainers. Research instruments are often configured from very flexible laboratory modules and their use is beyond the scope of this article. Many modern clinical instruments, however, are precise enough for basic or clinical research.

Clinical instruments are generally accurate, calibrated, and reliable. They are available as either stand-alone discrete units measuring a single parameter, or as computer-based multimodality systems. Some are comprehensive and accurate enough to be used for research. Trainers are single modality instruments intended to be purchased by or loaned/rented to the subject. They are less accurate and expensive than clinical instruments. Modern technology has made most trainers accurate and reliable despite their relatively low cost.

To protect both the subject and the professional, it is recommended that only FDA listed equipment be used. Even third-party software should meet this recommendation unless it is to be used only for educational purposes.

The biofeedback professional should have the proper academic credentials for the applications offered. Certification in use of the specific instrument modalities and applications is also recommended. The Biofeedback Certification Institute of America (BCIA), an affiliate of the Association for Applied Psychophysiology and Biofeedback (AAPB), offers certification in many areas. The American Physical Therapy Association (APTA) offers certification in EMG treatment of urinary incontinence. It is further recommended that the biofeedback professional receive training for the specific instruments used as there are some differences among instruments of the same type.

Most modern instruments are manufactured using standards traceable to the National Bureau of Standards (NBS). Modern electronic technology permits instruments to remain calibrated throughout their life, with the exception of sensors, which must be replaced occasionally. Instrument performance while attached to a subject, even the same subject at different times, can vary widely from improperly placed sensors, electromagnetic interference (EMI) and the subjects' condition. Even the professional is not a psychophysiological constant. Therefore it is strongly recommended that the using professional invest in test instruments and fixtures for each modality to be used so they can independently establish that the instrument(s) are operating correctly. The test device could be as simple as a laboratory thermometer used in a stirred water bath to verify temperature or a precision resistor to verify electrodermal accuracy. Biopotentials (EMG, EEG, ECG) require an electrode meter, and electrical safety, a volt Ω-ampere meter. Some commercial ECG signal simulators also provide sine and square-wave outputs, useful for testing EMG, EEG, and ECG instruments.

Circuitry and software of commercial instruments varies as to amplifier bandwidth, filter cutoffs, signal rectifiers, and integrators, which make it difficult to measure accurately direct comparisons between instruments of the same type from different manufacturers. Comparing results from different instruments of the same model from one manufacturer depends on the technology used. Older instruments with discrete component filters vary more than modern instruments due to component tolerances. Modern computer-based instruments employing software filters are more similar.

Professionals making comparisons with other professionals should use relative values such as percent decrease in finger temperature. A rough rule of thumb follows: Instruments vary about ± 10% across models and manufacturers, but subjects can vary as much as an order of magnitude in some measures. Lesson: Rely on known standard inputs to evaluate instrument performance.

Safety falls into three major areas: environmental, biological, and electrical. Environmental safety concerns trip hazards, sharp edges–corners, heaters, lamps and machinery in the subject–professional area. Biological safety concerns disinfecting re-useable sensors, subject chair, area, and so on. Disposable biopotential (EMG,EEG,ECG) electrodes are recommended. Until disposable EEG electrodes become available, they and all reusables should be cleaned and disinfected between uses. Electrical safety concerns both subject and professional. Battery powered instruments are intrinsically safe but if connected to a alternating current (ac), line operated device (i.e., computer, recorder, oscilloscope), through a nonisolated interface, they become a potential hazard.

Most computer-based instruments are isolated to stringent standards and provide complete electrical safety for the connected subject. By isolating the computer system with a medical grade power transformer, the professional is also protected. Use the (recommended) ac current meter to verify isolation.

EMG Biofeedback Instrumentation

Biofeedback applications of EMG range from simple relaxation, using electrodes placed on the forehead, to complex neuromuscular retraining of stroke (cardiovascular accident, or CVA) victims utilizing four EMG channels on each of the affected and unaffected sides to retrain functional movements using both inhibition and reinforcement learning techniques.

The EMG signals for clinical biofeedback are the summation of muscle cell action potentials generated by the underlying muscles seen at the skin. They are acquired from surface electrodes applied over (or in the vicinity of) muscle(s) to be monitored. Signals from the electrodes are amplified and conditioned by high performance differential amplifiers. Signal characteristics of interest are in the range of 0.1–2000 μV amplitude, over a bandwidth of ~25–500 Hz. The amplified signal is then processed to a form suitable for display to the subject.

EMG Electrodes. Muscle signals are acquired using two (active) electrodes located along the muscle fiber axis. A third electrode (common, often erroneously called ground) establishes the instrument common at the subject common potential. Well-placed surface electrodes provide an adequate EMG signal to enable subjects to learn control and change in the desired direction (i.e., relaxation, EMG lower; reeducation, EMG higher).

Needle or wire subcutaneous electrodes can collect a more comprehensive representation of the EMG (motor and nerve cellular action potentials), but their use is limited to Neurology or research, due to the complexity and invasive nature of the procedures.

A surface electrode is a complex electrochemical network. The manufacturing process reduces and stabilizes all internal parameters, leaving only the electrolyte–subject skin interface for the clinician to cope with. Fortunately, EMG amplifier technology has considerably reduced requirements for electrode preparation (for most applications) to a good skin cleaning using alcohol or a commercial prep solution. A surface electrode basically consists of a contact resistance (i.e., 10–100 kΩ), paralleled by a capacitance (i.e., 1 nF), in series with a half-cell potential (i.e., 300 mV "battery").

The care required in electrode–lead–amplifier placement and mechanical stabilization depends on procedure dynamics and electrical environment considerations. For relatively static applications (i.e., relaxing in a chair), in a relatively benign electrical environment, much less preparation and virtually no stabilization are required. For dynamic (i.e., treadmill) applications in a hostile electrical environment (i.e., central urban), considerable care and expertise are required to obtain reliable signals. Proper electrode choice and stabilization means (i.e., taping) are required. Electrode mechanical stabilization is required in dynamic applications to minimize disturbing the half-cell potentials that form at the electrolyte–skin interface.

Other considerations for electrode selection and placement include surface curvature, movement, and sweating.

Today, most EMG biofeedback clinicians use disposable electrodes in consideration of disease and litigation problems. One newer type of surface electrode (hydrogel) can be moved between (properly prepared) sites on one patient during one session, but using any type of electrodes between subjects is not recommended.

EMG Amplifiers. The EMG amplifiers have benefited considerably from integrated circuit technology and today achieve performance inconceivable two decades ago. Many products still connect to electrodes with a cable or leads, but some amplifiers are small enough to mount directly on the electrode structure. While the amplifier characteristics are exceptional, the performance of the EMG channel can be compromised by asymmetries in electrodes and connecting leads, resulting in unequal electrical induction, causing artifact to appear as a differential error signal. The following are considered to be minimal specifications for a modern EMG amplifier:

Low internal noise ($<0.5\ \mu$V, p–p).
High input impedance (Zin >100 MΩ).
Flat bandwidth and sharp high and low frequency cutoffs (>18 dB/octave).
High common mode rejection ratio (CMRR $> 10^7$).
Common mode input range (CMR $> \pm 200$ mV).
Static electricity shock protection (>2000 V).
Gain stability (all causes) $> \pm 1\%$.

Bandwidths (3 dB) in common use for clinical biofeedback are 25–500 Hz, primarily used for neuromuscular reeducation training, and 100–200 Hz used for relaxation training and where bandwidth must be limited because of EMI considerations. A hardware or software switch provides bandwidth selection. The narrow bandwidth loses some of the EMG frequency spectrum, but is adequate for many applications, having the advantages of lower in-band noise and less artifact susceptibility. Some manufacturers believe that a single bandwidth of ~30–300 Hz captures most of the EMG signal and provides simplicity.

EMG Biofeedback Application Example. Consider the problem of acquiring a 1 μV signal from a muscle using two (active) surface electrodes and a reference (common) electrode. Characteristics of the reference electrode are not as critical as the actives because the high CMRR of the amplifier minimizes disturbances in its impedance and half-cell potential.

The two active signal acquiring electrodes are effectively back to back, in series with the (muscle) signal source impedance and generator. Impedance of the active electrodes is probably close, since they were applied in a like manner, and the very high input impedance of the amplifier makes differences negligible.

Active electrode half-cell potentials are a different matter. While they are similar, they are of such a great magnitude (i.e., 300 mV) compared to the signal (i.e., 1 μV) that small abrupt changes in either half-cell potential will be coupled through the amplifier as a large artifact, which is the reason why it is so important to mechanically stabilize surface electrodes. Small disturbances of electrodes and leads outside of the frequency band of interest are not seen.

Leads connecting electrodes to the amplifier must also be stabilized to reduce artifact. They should be twisted and taped down for dynamic applications. Triode (equilateral triangle group) electrodes allow placing the miniaturized amplifier directly on the electrode(s), reducing lead length to zero. Amplifier and lead mass must also be considered in dynamic applications.

In some applications, such as treadmill and (internal) pelvic floor applications, some artifact must be tolerated and either average or quiescent levels used for training.

Following successful acquisition and amplification of the EMG signal it is usually rectified in a precision operational circuit or subroutine to produce the time-variant average that is needed for quantification and display. Older instruments provide integral average and modern instruments provide root-mean-square (rms) average that is loosely held as an analog of power by some authors. A related instrument response parameter is the time constant (TC) of integration that follows rectification.

Neuromuscular reeducation applications require a short (i.e., 50 ms) TC to sense the slightest voluntary (phasic) response and relaxation training as long as one second, to provide a more slowly changing display promoting relaxation, when tonic levels are of more interest.

Therapists having detailed knowledge of the frequency spectral characteristics of the specific muscle(s) being trained view (on an oscilloscope) the raw (filtered but not rectified ac) signal for assessment and training effectiveness. Raw EMG is seldom used as feedback due to its' visual complexity.

Stand-alone instruments use either analogue operational or microprocessor implemented filtering, rectification, averaging, and display. Most modern instruments are microcomputer based. The biofeedback instrument manufacturer provides signal acquisition and conditioning hardware to be interfaced, and software to be installed in a PC. Most recent biofeedback software has been for use on Windows operating system PCs.

Some stand-alone instruments have data storage, statistical reporting, and downloading capabilities. Microcomputer-based systems provide very sophisticated data reporting capabilities, with raw data exporting for advanced analysis. Some systems feature general purpose software for more advanced users and application specific software for less sophisticated users performing repetitive procedures, such as pelvic floor muscle strengthening and synchrony training for urinary incontinence.

Temperature Biofeedback Instrumentation

Temperature biofeedback is primarily used to improve poor peripheral blood flow caused by chronic sympathetic arousal. Other medical conditions causing low peripheral blood flow must be ruled out prior to attempting biofeedback. Temperature is then taken as a partial integration of blood flow and thus of peripheral vasoconstriction caused by sympathetic arousal.

Training criteria are determined by the therapist for the particular subject, but digit temperature training goals range from 31.1 to 35 °C for most subjects.

There are several types of low cost "instruments" primarily used for group education. These include glass-alcohol thermometers, liquid-crystal (i.e., mood-dots and biotic bands), and digital thermometers. This section concerns itself with clinical grade instruments employing sensors, amplifiers, and displays.

Temperature Sensors. Small sensor(s) are affixed to finger(s) or toe(s) with porous surgical tape at nearly zero tension so as not to occlude blood flow, or provide a heat reservoir. The sensor(s) are in good thermal contact with, but electrically isolated from, the subject. Accuracy and linearity of modern commercial sensors are excellent, but it is essential to use sensors having a short thermal time-constant and minimal hysteresis so minute changes in temperature (i.e., blood flow) are immediately communicated to the subject.

Modern sensors are thermistors, compensated negative coefficient resistors that provide a linear negative change in resistance over the temperature range of 21–37.8 °C. A small direct current (dc) voltage is impressed across the thermistor resulting in increased current flow for increases in heat (due to increased blood flow) from the subject.

Temperature Amplifiers. Whether the temperature instrument is stand-alone or one modality of a multimodality system, the circuit consists of a compensated thermistor sensor, powered by a constant voltage, and a current-to-voltage amplifier that produces a temperature proportional voltage that is then displayed and/or digitized for further processing.

Amplifier characteristics depend on the thermistor resistance range, the excitation voltage, and the required output voltage. Bandwidths of 0–5 Hz provides adequate response and minimizes noise, improving resolution. Since signals are high level, a single-ended current amplifier can be used.

Absolute accuracy is important because both subjects and therapists tend to discuss readings in their respective groups for comparative purposes. Subjects particularly are very sensitive to numbers and an instrument differences could impede training progress.

Most instruments specify ± 0.56 °C absolute accuracy. It is often better than claimed and can be checked in a stirred waterbath against a standard lab mercury thermometer.

Resolution of most instruments is selectable for either 0.056 or 0.0056 °C resolution. Subjects tend to make large improvements in initial states of training and the coarser (0.056 °C) resolution is adequate. There is some question by these authors about whether the 0.0056 °C resolution has clinical utility.

Temperature Displays. A time-based line graph is the most common display, as it shows past history and current trend. Bar graphs, digital meters, and computer animation displays are also used. These should be selected by the therapist–subject team to be relevant to the subject's beliefs; and sometimes varied to keep motivation high.

Temperature Biofeedback Application. Sensor attachment is often the back of the finger or toe of interest using a breathable tape to prevent heat build-up. Tape tension should be just enough to affix the sensor without constricting blood flow. Lead length should be sufficient to allow the subject to achieve a comfortable position without lead tension.

Room temperature should be in the comfort range for the subject (i.e., 21.1–23.9 °C) and without any breeze. Relative humidity should be between 30 and 50% to avoid humidity stress or evaporation cooling.

A location free of transient noises (i.e., office activity, elevator, emergency vehicles) will facilitate subject focus and relaxation.

EEG Biofeedback Instrumentation

The EEG biofeedback instrumentation is similar to EMG biofeedback instrumentation in acquiring the biopotential signal. The reader is encouraged to review the section on EMG biofeedback instrumentation for a background on the following section.

Whereas EMG instrumentation acquires surface muscle signals at the skin, EEG instruments acquire signals on the scalp generated by brain cellular activity below. The EMG activity in this region is considered artifact and care must be taken in EEG signal processing to minimize EMG contamination. When large EMG artifacts cannot be removed from the EEG signal, feedback must be blocked or held constant until the EMG artifact has passed.

The EEG signal is acquired on the scalp using surface electrodes, generally different from EMG electrodes, in either a differential (bipolar) or referential (monopolar) mode. High performance differential amplifiers increase and condition the signals. Signals of interest are in the range of 0.5–100 V (p–p), over the frequency range of 1–30 Hz. Newer clinical research extends the frequency range to 1–50 Hz.

Modern EEG biofeedback instruments perform digital filtering on the amplified and conditioned EEG signal to obtain the frequency band(s) or full spectrum of interest (i.e., fast fourier transform, FFT).

Viewing the full frequency spectrum EEG signal is of interest in assessing brain state(s) and is sometimes used as feedback, displayed as bilateral (left and right hemisphere) displays back to back about as vertical centerline.

More often the feedback display is less complicated, consisting of vertical bars or lights representing several spectral bands logically combined to reward increases in the band of interest (i.e., beta, 16–20 Hz) and decreases in the band to be reduced (i.e., theta, 4–9 Hz). The EMG activity is also monitored and acts to inhibit or freeze the feedback if present.

This logic is also used to drive a computer generated graphic animation sequence (i.e., games) and/or audio feedback comprising several types of files and songs (i.e., wav, midi). Auditory feedback is useful for closed eyes training and can also be used to provide simultaneous reward-inhibit band information when the visual presentation does not provide it, as in the case of animation sequence visual feedback.

EEG Electrodes. The EEG electrodes are placed on the scalp in a standardized grid called the 10–20 system. Coordinates are determined with respect to the midline, between the nasion and the inion, and a line between the right and left ears, in percent of the distance from the reference axis.

Bipolar recordings are made between (2) active scalp electrodes, with a neutral site serving as amplifier common (i.e., center forehead). An active pair of electrodes is used for each additional site to be monitored. Only one common is required unless the amplifiers have isolated commons, in which case they must be tied to the subject, usually at the same neutral site.

Monopolar recordings are made with a single scalp electrode (+) with respect to a chosen reference site (−). Amplifier common is placed at a third (neutral) site. For bilateral monopolar recording, the left channel has a scalp electrode (+) somewhere on the left side of mid-line with its reference (−) on the left ear. Amplifier common could be either the left mastoid bone or forehead.

The right channel placement somewhat mirrors the left with the active scalp electrode (+) on the right side of mid-line, the active reference (−) on the right ear, and the common on the right mastoid bone or forehead. The left and right active electrodes are placed according to training objectives, not necessarily symmetrical.

Multichannel systems are monopolar having a scalp electrode for each of the (20) sites in the 10–20 system, all having the same (forehead) reference and instrument common.

An Electro-Cap having 20 scalp and one reference–common electrode, sized to the subject, is worn. Electrode sites are prepared through holes in each electrode. A cable harness connects the cap to a junction-box for connecting amplifiers to desired sites, or directly to the instrument, for the 20 channel system. Since all sites are measured referentially (i.e., monopolar), differential comparison between any sites can then be accomplished in software or circuitry.

It is important that both active electrodes (i.e., +, −) have the same electrode material and electrolyte, since the initial stage of the amplifier is dc coupled, and a large difference in half-cell potentials could saturate (block) the amplifier. The (2) active electrodes must be prepared similarly even if one is a scalp (cup or disk) placement and the other an ear-clip.

Gold, silver–silver chloride, and tin are common active electrode materials. The common electrode can be a different type, usually a disposable silver–silver chloride EMG electrode.

Electrode sites are prepared by mild abrading and infusing a conductive "prep" gel to stabilize and improve conductance of the scalp. This is followed by application of an thixo-tropic electrolyte (i.e., 10–20 paste). The cup or disk electrode is then pressed on the paste until it is firmly sealed. Viscous force holds the scalp electrode in place during recording. Hair is managed with tape or cottonballs, which also helps retain and stabilize the placement. Ear clip electrodes are spring retained.

Reusable cup scalp and ear clip electrodes are in common use despite potential health and litigation problems. Several disposable systems have been or are being developed, but are not in wide use at this writing.

Careful electrode preparation will result in an impedance of $<10\ \mathrm{k}\Omega$, usually measured using a 20 Hz ac impedance meter. The actual value required depends on the electrical environment of the treatment area. The EEG electrodes are generally unshielded, so electric induction is reduced with low impedance placements.

Electrode half-cell potentials must also be checked differentially with an electrode meter. Differences of more than ± 25 mV between the active electrodes usually indicates unstable placements or different materials used. If a different type of common electrode was used, a large half-cell potential difference between each active and the common is not problematical, as long as they are similar and stable.

EEG Amplifiers. Like EMG amplifiers, EEG amplifiers make good use of integrated circuit and surface-mount technologies to achieve performance never before seen. While amplifier characteristics are exceptional, the effective performance of the EEG channel can be compromised by asymmetries in electrodes, cables, and leads. The resulting imbalance between the plus (+) and minus (−) inputs to the differential amplifier can cause unequal electric induction producing an error that shows as increased noise or offset. Fortunately, most unwanted electric fields are outside the amplifier bandwidth. Still, good practice in electrode preparation, lead routing, and electrical environment control are necessary to avoid a setup that is electrostaticly "hot".

The following parameters are considered minimum for the modern EEG differential amplifier:

Low internal voltage and current noise($<1\ \mu$V, 100 pA, p–p)
High input impedance (Zin $>10^8$).
Bandwidth (1–50 Hz).
Frequency cutoffs (>18 dB/octave).
High common mode rejection ratio ($>10^7$).
Common mode input range (greater than ± 200 mV).
Static electricity shock protection (>2000 V).
Gain stability (all causes) greater than $\pm 1\%$.

The amplified EEG signal is then digitally filtered to produce the desired bands of frequencies to be used for assessment, training, or mapping.

EEG Displays and Feedback. The modern EEG instrument utilizes a computer to perform the signal processing, auditory and visual display generation, data collection–reduction, and reporting necessary for effective assessment and training. Today's sophisticated programs require a fairly high performance computer to perform all these tasks in apparent real time. Most manufacturers design around readily available Windows based personal computers having the following minimum characteristics:

Processor:	Pentium 3
Speed:	600 MHz
Memory	256 MB
Storage	10 GB
Display resolution	800×600
Video memory	32 MB ($4 \times$ AGP)
Operating system	Windows '98, or later
Auditory system	Sound Blaster Live
Speakers	Good quality with sub-woofer

Recent advances in clinical biofeedback have shown subjects can comprehend complex visual and multiparameter auditory feedback simultaneously. A higher performance computer with more working and video memory, and the very best auditory system is suggested for these applications.

A very useful feature of Windows'98 and later operating systems is the support of multiple display monitors. This makes it possible to stretch the display onto a second monitor. The therapist can construct displays having highly technical items on their monitor while the subject sees nontechnical items, such as animation.

A common use of the digitally filtered EEG signal is for treatment of Attention Deficit Disorder. Other applications using other bands of frequencies include hyperactivity and performance enhancement.

Full frequency spectrum displays are used to "quiet" a "noisy" brain under the guidance of a skilled therapist. Animation sequence displays accompanied by contingent auditory feedback provide effective training tools for the therapist.

Some 20 channel systems are capable of mapping the entire EEG frequency spectrum at every electrode location in the 10–20 coordinate system in (nearly) real time. The displays are updated in 50 ms providing a useful assessment mode.

EEG Biofeedback Application. The most important factor is the therapist's training. The EEG assessment and biofeedback treatment has progressed considerably beyond that required to use the less complex modalities of temperature, electrodermal, and EMG. Fortunately, few schools are keeping up with advances. The International Society for Neuronal Regulation (ISNR) is a good source to inquiry. The Neurofeedback division of the Association for Applied Psychophysiology and Biofeedback (AAPB) and ISNR have together addressed several critical issues in EEG biofeedback methodology and clinical application.

As with most psychophysiological assessment and biofeedback applications environmental temperature (21.1–23.9 °C), humidity (30–50%), illumination (as required), auditory noise (transient free, white noise is usually acceptable), and therapist's physical position with respect to the subject must be considered and controlled.

An electrically quiet environment is also desirable. Power lines, TV and radio antennas, and mobile communications are frequent sources of interference. Basement locations usually offer the electrically quietist locations and well-placed electrodes along with carefully routed leads provide the best immunity under the therapist's control.

Electrodermal Biofeedback Instrumentation

Electrodermal activity (EDA) is essentially a measure of palmar sweat gland activity of the fingers or hands. Bulk tissue impedance is largely ignored, being clinically less significant than the eccrine sweat gland activity, modulated by the sympathetic nervous system that modern instruments measure.

Electrodermal activity can be measured either as resistance, called skin resistance activity (SRA = SRL + SRR) or it's reciprocal skin conductance activity (SCA = SCL + SCR). The SCA has the advantage of being a linear function of the number of sweat glands conducting, while SRA has a hyperbolic relationship to the number of sweat glands conducting.

Electrodermal activity includes both the tonic (average) level (SRL or SCL) and short-term (phasic) response (SRR or SCR). Training goals for SCA are to lower the tonic level, indicative of chronic sympathetic arousal and reduce the phasic changes percent, indicative of over reactivity, either spontaneously or in response to stimuli.

The magnitude of phasic changes tend to occur as a percentage of the tonic level. For conductance, a 1 μS SCR change from a tonic level of 5 μS SCL is approximately equivalent to a 2 μS SCR change from a 10 μS tonic SCL level (i.e., 20%).

Most modern instruments measure conductance although one manufacturer recently reverted to resistance so that the same programmable amplifier could be used to measure any variable resistance sensor (i.e., temperature). Since conductance and resistance are reciprocals, either can be displayed with the conversion made in circuitry or software.

Subject phasic responses are delayed by 1–3 s neurophysiologically. This latency limits the usefulness of EDA as an early in-training feedback modality. It is an excellent assessment modality where the subject receives no feedback.

The EDA is a passive electrical parameter and must be elicited by impressing a small voltage on (conductance), or passing a small current through (resistance) the two electrodes, usually placed on the fingers. Either method is referred to as "excitation".

The normal range of EDA for human subjects is

Conductance:	0.5–50 μS
Resistance:	2 MΩ–20 kΩ

Most untrained subjects range between 2 and 10 μS. A value of 50 μS would be indicative of a soaking wet hand.

Electrodermal Electrodes. Normal placement of electrodes is on the palmar surface of the index and middle fingers of either hand, selection dictated by other modality sensors on a particular hand. Electrodes are held on the fingers by Velcro straps set for just enough tension to hold them on without causing blood "pulsing" or pounding in the fingers. Silver–silver chloride is the most common electrode material, but gold, stainless steel, and nickel-plated brass are also used.

Early instruments used monopolar (dc) excitation. At the values then used, electrode polarization and subsequent amplifier blocking tended to occur. Modern instruments use 10 μA current (resistance) or 200 mV (conductance) and reverse the excitation several times per second resulting in no net charge, thus avoiding electrode polarization. These values also limit current to 10 μA as required by the FDA.

Electrolyte between electrode and skin is not normally used clinically for EDA, but should be used, along with finger cleaning for clinical research or published studies.

Electrodermal Biofeedback Amplifier. Modern EDA amplifiers employ a switching technique to reverse electrode excitation several times per second to avoid electrode polarization. This requires a reversible voltage (conductance) or current (resistance) source, circuits easily implemented by operational amplifier techniques. Values are sampled after transient effects caused by the switching. The EDA is a relatively slowly changing modality and an effective amplifier bandwidth of 1–2 Hz is adequate.

The entire EDA (EDL + EDR) should be measured and later separated. Phasic changes (EDR) can be ac coupled to remove the EDL and amplified to produce the desired display sensitivity. This produces bipolar components to each phasic response (EDR), which can be difficult for subjects to understand.

Another method is to introduce an offset in the amplifier equal to the EDL resulting in only the phasic (EDR) component that can then be amplified separately. This method requires a relatively stable EDL or a circuit that samples the EDL and adjusts the offset continuously.

Electrodermal Feedback. Use of EDA as an assessment (without feedback) modality is highly recommended since it provides insight into the chronic sympathetic arousal level and reactivity of the subject.

Using EDA as a feedback modality in the beginning subject is discouraged as it is so nonspecifically reactive, subject relaxation and learning may be impeded. Advanced subjects, however, may find it challenging to control EDR while performing tasks.

For assessment, the time line graph of the entire EDA provides the most information on current and recent past history to the therapist.

The line graph, bar graph or contingent animation are all useful visual displays for the advanced subject.

Pitch-proportional (SCA) or pitch inversely proportional (SRA) auditory tones are useful for eyes-closed or task performance training. Care must be taken in choosing the pitch range to avoid alarming the subject with a "siren" effect.

Electrodermal Biofeedback Application. Silver–silver chloride electrodes are recommended. Low cost velcro-strap electrodes are affordable for each subject's course of training. Using these between subjects is not recommended from disease and therapist liability considerations. Disposable Ag/Ag CL EMG electrodes provide an alternative, but affixing them to digits is not as convenient.

Hand washing prior to the session is advisable for both uniformity and sanitation.

Use of electrolyte is not required for most clinical training, but should be used for clinical research or published studies. Saline gel or cream is suitable for most subjects. Non-saline gel is useful for allergic subjects. Hand washing following the session is good practice.

A small percentage (i.e., 7%) of subjects show little or no EDA. Always check the instrument with a known conductance–resistance standard (or the therapist) before concluding that the instrument is mal-functioning.

Since EDA is an elicited or exosomatic measure, care must be taken to place sensors from all used instrument modalities so that the current from EDA does not interfere with or impede other simultaneous measurements. Manufacture of multimodality biofeedback systems provide guidelines to minimize these situations. This is of particular concern if two EDA channels are used on the same subject.

As EDA is a relatively high level signal and excitation switching is slow, the modality is relatively impervious to electromagnetic interference.

Cardiopulmonary Biofeedback

Respiration (RSP) training has been shown to greatly improve the subjects' ability to relax and maintain self-regulation in the face of psychological and performance stressors. It tends to reduce performance anxiety and increases oxygen uptake and waste expulsion. It also increases peripheral circulation by reducing sympathetically activated vasoconstriction. Heart rate increase during inhalation is normal, implemented by the sympathetic nervous system. Para-sympathetic action slows heart rate during exhalation. Heart rate variability (HRV) training has also provided benefits in reducing rapid heart rate and tachycardia.

The HRV (measured as HR max - HR min) is frequently as high as 20 BPM in healthy 20 year-old adults, and decreases by age 50 often to ~10 BPM. Athletically active and physically well-conditioned individuals have higher variation in heart rate. Heart rate variability training aims at increasing the variability, and frequently increases it significantly higher than 20 BPM. Some authors have claimed that it goes as high as 50 BPM in peak training. Higher HRV is considered desirable in disease prevention and health promotion applications, and lower HRV correlates with cardiovascular morbidity and mortality. For example, lower HRV is a strong independent predictor of post-MI death (4).

By combining respiratory (RSP) and heart rate (HR) instrumentation, the interplay between respiration and heart rate, referred to as respiratory sinus arrhythmia (RSA), can be assessed and used as biofeedback to train subjects to optimize their natural cardiopulmonary rhythms under the influence of stressors.

Norms for HRV training have been published (5). One of the persistent problems in the field is the failure of researchers and practitioners alike to adhere to standard nomenclature and normative values for training. The following HRV frequency ranges have been established as standard for cardiopulmonary training:

Cardiac Rhythms. High frequency: 0.15–0.4 Hz; low frequency: 0.04–0.15 Hz; very low frequency: 0.0033–0.04 Hz; and ultra low frequency: <0.0033 (beyond clinical biofeedback measurement technology) (5).

Recently, a more careful examination of HRV has shown the very slow rhythms to be of interest in assessing dysregulation, other than that caused by the ANS, to be discussed in a separate HRV section, below. The very low frequency (VLF) range is to some extent correlated with dysregulation. Rhythms in the low frequency range are to some extent correlated with optimal homeostasis. Higher HR oscillations are found in rhythms in this range.

The RSP rates vary from 2 to 30 bpm requiring channel bandwidths of 0–5 Hz to faithfully reproduce the RSP waveform. Trained subject's RSP rates at rest are individually optimum and range from 6 to 9 pm.

The HR rates vary from ~40–180 bPM. Trained subject's HRs rest at ranges between 60 and 80 BPM The HRV (RSA) of 8–16 BPM as a function of RSP is normal and desirable.

Some instruments are capable of RSA assessment and biofeedback only. Instruments designed for HRV generally can also perform RSA procedures.

Respiratory Sinus Arrhythmia Instruments. Instruments for RSA have one or two respiration channels and one heart rate channel. Two respiration channels are desirable to train the subject to breathe abdominally, not thoracically.

The RSA instruments are computer implemented. Time line graphs of abdominal and thoracic RSP along with a beat-by-beat line graph of HR comprise an excellent assessment and training display. The line or (better) filled line graph is the most common display as it shows recent past history as well as current performance. Digital meters showing RSP and HR rates can be added, but the display tends to be too complicated, particularly for beginning subjects.

Raw data is saved, so the session can be replayed as desired. Statistics can be generated, but care must be taken to consider the effect of artifact. Both RSP and PPG HR channels are susceptible to movement artifacts. Some instrument software permits editing the raw data to minimize artifact contamination of statistics.

Respiration Sensors and Amplifiers. Respiration sensors for biofeedback comprise a stretchable segment and a belt or chain that is wrapped around the circumference of the abdominal and the thoracic regions of the subject. A slight prestretch (set at the point of maximum exhalation) allows the sensor to operate over the full range of circumference change caused by breathing. Care must be taken that restrictive clothing does not impede breathing.

Circumference change caused by breathing is a relative measure affected by subject breathing, posture, type of sensor, even temperature depending on the type of sensor used. Three types of sensors are in common use.

1. Rubber Bellows (Air Filled): Following placement the system is sealed, and sensor internal pressure changes with stretch. A transducer (half or full bridge strain gage) measures pressure changes. A dc coupled bridge amplifier, with offset control, provides amplification and the ability to "position" the output at the desired level for display and/or quantification. Typical pressure variations are on the order of ±15 mmHg (1.99 kPa) gage.
2. Tubular liquid-filled strain gage: An elastometric tube filled with a conductive thixo-tropic liquid. Changes in length and diameter of the tube, caused by breathing, varies the resistance of the gauge. Since the liquid is ionic, excitation (current or voltage) is reversed several times per second to prevent polarization. The amplifier comprises a reversible voltage or current source, gain, and offset capability to provide the desired output signal positively proportional to inhalation.
3. Magneto-position transducer: A magnetic armature is moved within an excited coil to produce a current proportional to movement. An elastomeric tubing provides a restorative force to track breathing movements. The amplifier converts the magnetically induced signal, provides gain and offset to provide a voltage positively proportional to inhalation.

Heart Rate Sensors and Amplifiers. Heart rate for clinical biofeedback is measured using either a finger photoplethysmograph (PPG) sensor or by acquiring the electrocardiogram (ECG) biopotential signal. The PPG sensor is easy to use, but its' output is subject to artifact from any disturbance of the placement. Acquiring the ECG requires placement of surface electrodes, but provides the virtually artifact-free signal that is required for reliable HRV analysis, and will be discussed in that section.

The PPG sensors employ an (invisible) infrared (IR) source of ~0.9 nm wavelength to illuminate the vascular bed of a finger (or toe). A photocell detects the backscatter caused by the opacity of blood at that wavelength. It is held in place with a Velcro strap or elastic band. The amplifier provides gain producing a pulse signal having information on HR, peripheral pulse amplitude (PPA), pulse volume (PPV) and rise and decay characteristics of the pulse.

Heart Rate Variability Instruments. Heart rate variability is useful for more than RSA training. Other factors, such as chemoreceptors, baroreceptors, the renin-angiotension system and various disease states affect HRV. Many of these variations occur at frequencies too slow to be perceived by or used as feedback for subjects.

Research has shown the frequency spectrum of HRV from 0.003 to 0.4 Hz to be useful in assessing disregulation of various systems. When HRV spectral components are distributed throughout the range of 0.003–0.4 Hz, HRV is said to be incoherent. In the coherent state, virtually all the energy occurs at one frequency in the range of 0.08–0.12 Hz and is individual specific.

The most comprehensive analysis of the slowest rhythms requires a 24 h data string of HR, such as is obtained in a Holter portable monitor of ECG, so various segments of Circadian rhythms can be analyzed. Data must be edited for artifact before spectral analysis by fast fourier transform (FFT) is performed. The comprehensive analysis can give insight into undiagnosed medical conditions.

In clinical psychophysiology, 5 min HRV data resolves frequencies from 0.003 to 0.4 Hz, adequate for observing ANS activity. Some instruments have added a 60 s HRV data gathering to provide 0.06–0.4 Hz spectral data, more easily obtained in the clinical situation, and adequate for determining coherence.

The ECG amplitude ranges between 0.3 and 2 mV for the QRS complex that is used to determine the interbeat interval from which the frequency spectrum is derived. The exact characteristics of the ECG signal are not as important in HRV applications as in clinical cardiology.

ECG Sensors and Amplifiers. The ECG is most reliably obtained by placement of chest electrodes using pregelled disposable Ag/AgCl sensors. For 24 h HRV studies, chest placement is mandatory.

In clinical psychophysiology, it is preferable not to remove clothing, so the wrist–wrist or wrist–ankle placement of sensors is preferred. Polarity of the ECG signal is important so the amplifier leads must be connected according to the manufacturer's instructions.

The EMG disposable sensors can be used to acquire the ECG in the clinic, but are not recommended for longer term studies as their adhesive surface area is considerably smaller than disposable ECG sensors, promoting half-cell disturbance artifact.

Typical ECG Amplifier Specifications:

Low internal noise ($<2\ \mu$V p–p).
High Input Impedance [Zin$>$ 10 MΩ].
Bandwidth (0.16–250 Hz).
Bandwidth cutoffs ($>$18 dB/octave).
Notch filter (60 Hz, in the United States).
Common mode rejection ratio [CMRR$> 10^7$].
Common mode input range (CMR ± 200 MV).
Static electricity shock protection ($>$2000 V).

Heart Rate Variability Instruments. The HRV instruments are computer implemented. They are also capable of performing RSA procedures using either ECG or PPG sensors to acquire HR.

Most HRV/RSA software is written for the Windows operating system. It is recommended that a fairly high performance computer be used to reduce HRV analysis computational time. A computer similar to that recommended for EEG is suitable.

Some instruments also support TMP and EDA in addition to the ECG, RSP, and PPG modalities.

One manufacturer offers a dual instrument interface making it possible for two computers to access one multimodality instrument, to perform simultaneous RSA/HRV, EEG, and other psychophysiological modality assessment and biofeedback procedures, with synchronized data collection. This instrument capability makes heart–mind interaction training and clinical research possible.

Heart Rate Variability Application. As with all biofeedback procedures establishing comfortable levels of temperature and humidity, with absence of transient auditory noise, is essential for focused, efficient, and reputable performance.

The Electromagnetic Interference (EMI) environment should meet the requirements of the most sensitive modality used (i.e., EEG).

Digitization of the ECG signal should be at least $256\ \mathrm{s \cdot s^{-1}}$, with $512\ \mathrm{s \cdot s^{-1}}$ recommended.

APPLIED CLINICAL EXAMPLES: TENSION AND MIGRAINE HEADACHE

We will now describe the typical EMG and hand surface temperature biofeedback procedures for tension and migraine headache, which we have used both clinically and in our research (3,6–8). As noted above, it is important to remember that when referring to EMG, the authors are alluding to surface electromyography, which uses noninvasive electrodes, is painless, and involves measuring the pattern of many motor action potentials; this is in contrast to EMG used as a diagnostic procedure in neurology, which uses invasive needle electrodes, measure the activity of a single motor unit, and is often quite painful.

The standard EMG biofeedback procedure for tension headache involves measuring the muscle tension in the frontalis muscle region by placing electrodes ~2.5 cm above each eyebrow and a ground electrode in the center of the forehead (9). The frontalis region has traditionally been assumed in clinical practice to be the best overall indicator of general muscular tension throughout the body. The standard thermal biofeedback training procedure involves attaching a sensitive temperature sensor, called a thermister, to a fingertip (usually the ventral surface of the index finger of the nondominant hand) with care taken not to create a tourniquet or inhibit circulation to this phalange.

EMG biofeedback is the modality most commonly used for tension headache, with the psychophysiological rationale being that muscle tension levels in the forehead, neck, and facial areas are directly causing or maintaining/exacerbating the headaches. It is also believed that individuals suffering from tension headache have high levels of stress and using EMG biofeedback as a general relaxation technique reduces their levels of stress, enabling tension headache sufferers to better cope with their headache activity.

Hand surface temperature biofeedback for migraine headache also has two possible mechanisms of action. The psychophysiological theory states that temperature biofeedback prevents the first of the two stages of migraine (vasoconstriction of the temporal artery and arterioles; the second stage is vasodilation, which causes the actual pain) from occurring by decreasing sympathetic arousal and increasing vasodilation to the temporal artery and arterioles. An alternative mechanism of action is the use of temperature as a general relaxation technique.

The EMG or temperature signal is then electronically processed using transducers to provide the patient with information on changes in the electrical activity of the muscles or surface skin temperature on a moment by moment basis. Generally, the signals are sampled every one-tenth of a second and integrated over the entire second. Both are quite sensitive, with the EMG sensor generally detecting changes of magnitude as low as a hundredth of a microvolt. The temperature sensor typically detects changes as low as one-tenth of a degree Fahrenheit. Through this feedback, the patient undergoing EMG biofeedback training learns how to relax the musculature of the face and scalp, and also learns how to detect early symptoms of increased muscle tension. In temperature biofeedback, the patient is taught how to detect minute changes in peripheral skin temperature, with the training goal being to increase hand temperature rapidly upon detection of low hand temperature. For EMG biofeedback, the feedback signal is usually auditory, and may consist of a tone that varies in pitch, a series of clicks that vary in frequency, and so on. Given the choice, >80% of patients receiving thermal biofeedback choose the visual display. The feedback display can be the pen on a voltmeter, a numeric output of the actual surface skin temperature, or a changing graph on a video screen. The format of the visual feedback display does not seem to affect learning or treatment outcome (10).

Common Type of Feedback Schedules in Clinical Applications. One of the challenges faced by both the biofeedback clinician and patient is selecting what type of feedback is most appropriate to facilitate learning to achieve rapid therapeutic benefit. There has been little research in this area; however, there are abundant anecdotal reports among the biofeedback community. There are three types of feedback schedules in clinical practice. By far, the most widely used method for delivering feedback is an analog display, which provides continuous information to the patient. For example, a tone that varies in relative pitch and frequency depending on an increase or decrease in the response being measured. However, in many applications, this may provide too much information to the patient, leading to information processing overload, retarding the learning process. A second type of feedback schedule employed in clinical practice is a binary display, where the patient receives information that is discrete, depending on achievement of a predefined training threshold. In threshold training, the feedback is turned on or off depending on whether the patient falls above or below the threshold. Threshold training is a clinical application of an operant shaping procedure, where the patient is reinforced for achieving successively closer approximations to the training goal. The third type of feedback schedule is an aggregate display of the training progress. In this type of feedback, the patient is given summary information at the conclusion of the treatment session (e.g., data averaged over each min interval in a 20 min training session). In clinical practice, the integrated display of aggregate feedback is the most commonly applied training schedule.

Training to Criterion. Training to criterion is a term used by clinicians that involves continuing biofeedback training until the patient achieves a specified criterion of a learning end state. For example, biofeedback training will persist until the tension headache patient has demonstrated reduced muscle tension levels in the frontalis region to a stable 1-μV level. Although there is compelling logic behind this notion, there is little empirical data to support the practice of training to criterion. Exceptions to this are a report by Libo and Arnold (11) who found that every patient who achieved training criteria on both EMG and finger temperature also reported long-term improvement, and 73% of patients who did not improve failed to achieved training criterion in either modality. In another study, Blanchard et al. (12) presented data supporting the concept of training to criterion. They observed a discontinuity in outcome for migraine headache patients who achieve 35.6 °C or higher at any point during temperature biofeedback training. Those who reached this level had a significantly higher likelihood of experiencing a clinically meaningful reduction in headache activity (at least 50%) than those who reached lower maximum levels. This apparent threshold was replicated in a subsequent study (13). More representative of the research is a recent study by Tsai et al. (14), where they found no evidence to support the concept of training to criterion in a study of hypertensives. Fifty-four stage I or stage II hypertensives were taught thermal, EMG, and respiratory sinus arrhythmia biofeedback. Most participants (76%) achieved the thermal criterion; only 33 and 41% achieved the EMG and respiratory sinus arrhythmia criterion, respectively. Achievement of the criterion level in any of the three modalities was not associated with a higher improvement rate. These results contradict the notion that training to criterion is associated with clinical improvement.

Electrode Placement. An important consideration to be made by the clinician utilizing EMG biofeedback is at what sites to place the electrodes. This decision depends in large part on which of the two general theories underlying the use of biofeedback the clinician adheres to. In most instances, electrode placements appear not to matter. However, for tension headache this may not be the case.

Although the vast majority of published reports on tension headache utilize the frontalis region electrode placement, their is some controversy about this practice. This is perhaps because the Task Force Report of the Biofeedback Society of America, in their influential position paper on tension headache (15), strongly implied that frontal placement was the "gold standard" for biofeedback with tension headache sufferers, making no mention of other site placements. In the standard placement, muscle activity is detected not only in the forehead, but probably also from the rest of the fact, scalp, and neck, down to the clavicles (16).

Some writers (17,18) advocated attaching electrodes to other sites, such as the back of the neck or temporalis area, especially if the patient localizes his/her pain there. However, three of the four studies that compared biofeedback training from different sites between subjects found no advantage of one cite over the other (19–21). Arena et al. (22) published the only systematic comparison of a trapezius (neck and shoulder region) versus frontal EMG biofeedback training regimen with tension headache sufferers. They found clinically significant (50% or greater) decreases in overall headache activity in 50% of subjects in the frontal biofeedback group versus 100% in the trapezius biofeedback group. The trapezius biofeedback group was more effective in obtaining significant clinical improvement than the frontal biofeedback group. Thus, there is some limited support for the use of an upper trapezius electrode placement with tension headache sufferers. More research needs to be done in this area.

Discrimination Training. A concept in clinical biofeedback applications that is quite often discussed, particularly among those practitioners of EMG biofeedback training, is that of discrimination training. In this procedure, patients are taught to discriminate high levels of muscle tension from moderate and low levels. Feedback is given contingent upon successful differentiation among these varying levels of muscle tension. For example, a patient is asked to produce maximal muscle tension in a particular region, and given feedback reflective of this high level of muscle activity, followed by instruction to halve this level and consequent feedback. Then, finally, they are asked to halve this again, that is produce one-quarter of the initial level of muscle activity, followed by appropriate feedback reflecting success at this level. To our knowledge, there is little reliable data demonstrating that individuals specifically taught a muscle discrimination training procedure have clinical outcomes superior to those taught a standard tension-reduction method.

Sensitivity–Gain. The gain or sensitivity of the feedback signal is important to facilitate the training process in clinical biofeedback. Too high a gain may interfere with learning by providing indiscriminate feed back for extraneous responding, leading to frustration on the part of the learner. In addition, in many response measures, too high a sensitivity leads to increased artifact. Conversely, setting the gain too low leads to lack of feedback for responses that may be clinically meaningful, thereby interfering with the learning process. In clinical practice, there are established ranges in various applications, depending on the response measure employed, individual differences in patient responsivity, and the nature of the disease state. Sensitivity may be adjusted as needed using a shaping procedure. Some response measures involve more frequent changes in gain settings than others. For example, gain is frequently adjusted in EMG biofeedback applications, because the goal often is detection of quite subtle muscular activity changes, but infrequently changed in hand surface temperature training, where gross changes in skin temperature are usually necessary for clinical improvement.

Session Length and Outline. Treatment sessions usually last 30–50 min; 15–40 min of each session is devoted to the actual feedback training. In our research (and in our clinical work), we have typically used the following format for biofeedback training sessions:

1. Attachment of electrodes and initial adaptation: 10 min.
2. In-session baseline, during which patients are asked to sit quietly with their eyes closed: 5 min.
3. Self-control 1, during which patients are asked to attempt to decrease their forehead muscle tension levels in the absence of the feedback signal: 3 min.
4. Feedback training, with the feedback signal available: 20 min.
5. Self-control 2, during which patients are asked to continue to decrease their forehead muscle tension levels in the absence of the feedback signal: 3 min.

The two self-control conditions are included to determine whether generalization of the biofeedback response has occurred. Generalization involves preparing the patient to, or determining whether or not the patient can, carry the learning that may have occurred during the biofeedback session into the "real world". If the patient can decrease muscle tension without any feedback prior to the biofeedback condition (Self-control 1 condition), then the clinician can assume that between-session generalization has occurred. If the patient can decrease their muscle tension without any feedback following the biofeedback condition (Self-control 2 condition), then the clinician can assume that within-session generalization has occurred.

There are other methods clinicians use to train for generalization of the biofeedback response. For example, in an attempt to make the office biofeedback training simulate real world situations, many clinicians initially train patients on a recliner; then, once they have mastered the rudiments of biofeedback in this extremely comfortable chair, they progress to, respectively, a less comfortable office chair (with arms), an uncomfortable office chair (without arms), and, lastly, the standing position. Finally, giving the patient homework assignments to practice the biofeedback response in the real world is a routine way of preparing them for generalization.

BRIEF REVIEW OF CLINICAL OUTCOME LITERATURE FOR BIOFEEDBACK

Anxiety Disorders–Stress Reduction

Biofeedback as a general relaxation technique has been in existence since the late 1960s. Indeed, it is common practice to call any form of biofeedback "biofeedback assisted relaxation", stressing the stress-reduction quality of the procedure. Where diagnoses are given, it is usually generalized anxiety disorder, although mostly the research defines anxiety or stress by global self-report measures or a simple paper and pencil instrument such as the Spielberger State-Trait Anxiety Inventory (i.e., scoring in the ninetieth percentile or above), rather than standard criteria such as the American Psychiatric Association's Diagnostic and Statistical Manual IV: revised (23). The primary modalities used for anxiety and stress reduction are EMG, hand surface temperature, and EEG. Nearly all the research has demonstrated that biofeedback is superior to placebo and wait-list controls for the treatment of stress and anxiety. There is some data to suggest (24) that EEG biofeedback to increase alpha waves may be superior to forehead EMG biofeedback and EEG biofeedback to decrease alpha waves in terms of decreasing heart rate activity, but not in terms of decreasing self-reported anxiety levels, where their were no differences between the three groups. When biofeedback has been compared to relaxation therapy, there is no difference between the two treatments in terms of their clinical efficacy (25).

One typical study was that of Spence (26). He took 55 anxious subjects, and gave them either electrodermal response, hand surface temperature, or forehead EMG biofeedback based on a pretreatment psychophysiological assessment (subjects were given feedback corresponding to that physiological parameter that changed the most during stress). All groups reported significant reductions in their anxiety symptoms, and 15 months later 76% of subjects were still symptom-free for anxiety, regardless of the type of feedback they received.

Moore (27) reviewed the EEG biofeedback treatment of anxiety disorders and pointed out that there are many limitations in the research to date. Unfortunately, many of his concerns hold for the EMG and temperature biofeedback literature as well, such as comparisons to relevant placebos, examination of such factors as duration of treatment, type and severity of anxiety, and so on.

Tension and Vascular (Migraine And Combined Migraine–Tension) Headache

By a large margin, the greatest number of articles supporting the efficacy of biofeedback for any disorder in the clinical treatment literature pertains to its use with vascular and tension headache. For both types of headache, biofeedback has been shown to be superior to both pharmacological and psychological placebo, as well as wait list control, in numerous controlled outcome studies. Biofeedback for headache is usually compared to relaxation therapy or cognitive therapy (a form of psychotherapy focusing on changing an individual's pain-and stress-related self-statements and behaviors). Arena and Blanchard have recently reviewed the biofeedback treatment outcome literature on tension and vascular headache (3,7,8).

With tension headache, the biofeedback approach used is EMG (muscle tension) feedback from the forehead, neck, and/or shoulders. For relaxation therapy alone, successful tension headache treatment outcomes generally range from 40 to 55%, for EMG biofeedback alone, this value ranges from 50 to 60%, and for cognitive therapy, from 60 to 80%; when EMG biofeedback and relaxation are combined, the average number of treatment successes improves from $\sim$50 to $\sim$75%; when relaxation and cognitive therapy are combined, success increases from 40 to 65%. When compared to relaxation therapy, there is usually comparable efficacy.

For patients with pure migraine headache, hand surface temperature (or thermal) is the biofeedback modality of choice, and it leads to clinically significant improvement in

40–60% of patients. Cognitive therapy by itself gets ~50% success. A systematic course of relaxation training seems to help when added to thermal biofeedback (increasing success from ~40 to 55%), but cognitive therapy added to the thermal biofeedback and relaxation does not improve outcome on a group basis. Relaxation training alone achieves success in from 30 to 50% of patients, and adding thermal biofeedback boosts that success (from ~30 to 55%). There appears to be a trend in the literature for thermal biofeedback to be superior to relaxation therapy.

For patients with both kinds of primary benign headache disorders (migraine and tension type), the results with thermal biofeedback alone are a bit lower, averaging 30–45% success; relaxation training alone leads to 20–25% success. Thermal biofeedback consistently appears to be superior to relaxation therapy with combined headache. The best results come when thermal biofeedback and relaxation training are combined. With this combination treatment, results show 50–55% success rates (adding thermal biofeedback to relaxation raises success from 20 to 55%; adding relaxation therapy to thermal biofeedback increases success from 25 to 55%). Most experts strongly recommend a combination of the two treatments for these headache sufferers.

Lower Back Pain

Arena and Blanchard (7) recently reviewed the biofeedback literature for low back pain and concluded that biofeedback appears to hold promise as a clinically useful technique in the treatment of patients with back pain. While the evidence indicates that optimal clinical improvement is clearly obtained when biofeedback is used within the context of a comprehensive, multidisciplinary pain management program, the cumulative weight of the evidence suggest that EMG biofeedback is likely to be helpful, as a single therapy, in the treatment of musculoskeletal low back pain, obtaining success rates of from 35 to 68% improvement on follow-up.

However, there were many concerns about the literature. Only two studies have directly compared biofeedback to relaxation therapy, and both of these studies were significantly flawed so as to limit definitive conclusions. Direct comparisons of biofeedback to relaxation therapy are clearly needed. Longer (at least 1 year) and larger scale (at least 50/group) follow-up studies are required. Evaluations of treatments based on diagnosis (i.e., the cause of the pain) should be conducted. Comparisons of various biofeedback treatment procedures, such as paraspinal versus frontal electrode placement, or training while supine versus training while standing, are necessary. Finally, further evaluations of patient characteristics predictive of outcome, such as gender, race, chronicity, psychopathology, and psychophysiological reactivity, are needed.

Myofascial Pain Dysfunction

Myofascial pain dysfunction (MPD) syndrome, also known as temporomandibular joint (TMJ) syndrome, is considered a subtype of craniomandibular dysfunction that is caused by hyperactivity of the masticatory muscles. It is characterized by diffuse pain in the muscles of mastication, mastication muscle tenderness, and joint sounds and limitations. Although disagreement exists as to the cause of the hyperactivity (e.g., occlusal problems vs. psychological stress), several researchers have examined the use of EMG biofeedback as a treatment, which can provide relief by teaching patients to relax the muscles of the jaw. Consistent with the logic of this approach, the most common electrode placement is on the masseter muscle, although frontal muscle placements have also been used. Excellent overviews of the treatment of MPD syndrome can be found (28,29).

Arena and Blanchard (7) recently reviewed the MPD biofeedback literature and noted that, although the majority of the studies had significant limitations, when taken as a whole they appeared to be quite impressive in support of the efficacy of EMG biofeedback for MPD syndrome. EMG biofeedback is at least as effective as traditional dental treatments such as occlusal splint therapy. Curiously, it was noted that no MPD syndrome study of biofeedback as a treatment in and of itself had been published since 1989. Given the extremely positive results, this observation is somewhat perplexing.

Deficiencies in the research on biofeedback treatment for MPD syndrome are similar to those discussed in the lower back pain section, above. Large scale outcome studies are needed, comparing (a) masseter versus frontal versus temporalis placement sites; (b) biofeedback versus relaxation; (c) biofeedback versus traditional dental strategies, and, (d) biofeedback in conjunction with other treatments versus traditional dental strategies. The latter approach has been used by Turk and co-workers (30–32), in a number of recent, methodologically elegant studies. In these studies various combinations of biofeedback, stress management training, and intraoral appliances were used, with results showing strong support for combined treatments. Finally, lack of long-term follow-ups, or for that matter, any follow-up at all, is a serious limitation that needs to be corrected.

Fibromyalgia

There have been a number of studies examining the efficacy of EMG biofeedback in the treatment of fibromyalgia (see Arena and Blanchard (5), for a review of the studies before 2000). The majority of the studies concluded that EMG biofeedback is useful in reducing fibromyalgic pain. Fibromyalgia is a type of nonarticular, noninflammatory rheumatism that is characterized by diffuse pain, sleep disturbance, tenderness, and functional impairment. Three studies have been published since 2000. Mueller et al. (33) gave 38 fibromyalgia patients EEG biofeedback, noted statistically significant decreases in pain, mental clarity, mood, and sleep. Van Santen et al. (34) compared physical fitness traing to EMG biofeedback and usual treatment on 143 female patients with fibromyalgia. They found no difference between the three groups on any measure. Recently, Drexler et al. (35) broke 24 female fibromyalgia patients down into those with abnormal psychological test (MMPI) results and those with normal psychological test profiles. Psychologically abnormal individuals were helped more by the biofeedback training than were psychologically normal individuals. Given the relatively promising results [all five of the pre-2000 studies (36–40) obtained positive results], it appears that large scale, controlled EMG biofeedback studies looking at factors such as psychological profiles and gender would now be appropriate.

Biofeedback for Gastrointestinal Disorders: Constipation Pain, Irritable Bowel Syndrome, Urinary, and Fecal Incontinence

The biofeedback literature on treatment of constipation pain, especially in children, is both impressive and growing. In adults, Jorge et al. (41) recently reviewed the literature and noted that, overall, mean percentage of success is 68.5% for studies that examine constipation attributable to paradoxical puborectalis syndrome. Mason et al. (42) examined 31 consecutive patients who received biofeedback training for idiopathic constipation. Twenty-two of the patients felt subjectively symptomatically improved. They noted that the symptomatic improvement produced by biofeedback in constipated patients was associated with improved psychological state and quality of life factors.

In the constipation pain literature regarding children, three studies particularly stand out. Benninga et al. (43) gave 29 children who suffered from constipation and encopresis an average of five sessions of EMG biofeedback of the external anal sphincter. At 6 weeks, 55% were symptom free. Another group of investigators (44) placed 13 children who suffered from constipation into a standard medical care group, while another group of 13 children were placed in a EMG biofeedback (of the external anal sphincter–from 1 to 6 sessions) plus standard medical care group. At 16 month follow-up, all children were significantly improved, with the biofeedback plus standard medical care group significantly more improved than the standard medical care only group.

One large scale study, however, does not support the efficacy of EMG biofeedback for constipation pain. In a procedure similar to Cox et al. (44), van der Plas et al. (45) placed 94 children who suffered from constipation into a standard medical care group, while another group of 98 children were placed in a five-session EMG biofeedback (of the external anal sphincter) plus standard medical care group. At 18 month follow-up, over one-half of the children in both groups were significantly improved, with no significant difference between the two groups. In spite of this large scale study suggesting no advantage to the inclusion of EMG biofeedback to conventional medical care, we believe that there is sufficient evidence to conclude that EMG biofeedback is a useful technique in treating the pain of both adult and childhood constipation, especially when the patient has proven refractory to standard medical care.

Biofeedback for irritable bowel syndrome has been in existence since 1972, but nearly all of the studies are small and uncontrolled. The type of feedback is generally thermal biofeedback, however, two groups have used novel feedback approaches with some success. Leahy et al. (46) have developed an electrodermal response biofeedback device that uses a computer biofeedback game based on animated gut imagery. This significantly reduced symptoms in 50% of 40 irritable bowel syndrome patients. Radnitz and Blanchard (47), using an electronic stethoscope placed on subjects' abdomens, gave bowel sound biofeedback to five individuals with irritable bowel syndrome. Three of the five patients had reductions in their chronic diarrhea by over 50% (54, 94, and 100%). Results were maintained at 1- and 2-year follow-up (48). Large scale controlled outcome studies comparing biofeedback to pharmacological and dietary interventions for irritable bowel syndrome symptoms need to be conducted.

Biofeedback For Cancer Chemotherapy Effects

Biofeedback has been used to decrease the negative side effects of cancer chemotherapy, especially the anticipatory nausea. While biofeedback assisted relaxation does seem to help these patients, biofeedback by itself (i.e., not using a relaxation emphasis), while reducing physiological arousal, does not reduce the anticipatory nausea. This is an area where relaxation therapy seems to have a clear advantage over biofeedback. For example, Burish and Jenkins (49) randomly assigned 81 cancer chemotherapy patients to one of six groups in a 3 (EMG biofeedback/skin temperature biofeedback/no biofeedback) × 2 (relaxation/no relaxation) factorial design. They concluded, "The findings suggest that relaxation training can be effective in reducing the adverse consequences of chemotherapy and that the positive effects found for biofeedback in prior research were due to the relaxation training that was given with the biofeedback, not the biofeedback alone" (p. 17).

Biofeedback for Cardiovascular Reactivity: Hypertension, Raynaud's Disease, and Cardiac Arrhythmia

Biofeedback has been used as a treatment for essential hypertension since the late 1960s. The type of feedback used is either direct blood pressure feedback or temperature biofeedback. There appears to be no difference in terms of clinical outcomes between the two biofeedback modalities. In a recent influential meta-analysis of 22 randomized controlled outcome studies, Nakao et al. (50) found that biofeedback resulted in averaged blood pressure decreases of 7.3/5.8 mmHg (0.97/0.77 kPa) compared to clinical visits or nonintervention controls. It resulted in averaged blood pressure decreases of 4.9/3.5 mmHg (0.65/0.46 kPa) compared to sham or nonspecific behavioral interventions. Statistical analysis indicated that, after controlling for the effects of initial blood pressures, biofeedback decreased blood pressure more than nonintervention controls, but not more than sham or nonspecific behavioral interventions. Further analyses revealed that when the treatments were broken down into two types, biofeedback assisted relaxation, as opposed to simple biofeedback that did not offer other relaxation procedures, was superior to sham or nonspecific behavioral intervention. Nakao et al. (50) concluded that, "Further studies will be needed to determine whether biofeedback itself has an antihypertensive effect beyond the general relaxation response" (p. 37).

It has long been believed that temperature biofeedback is more efficacious than medication in the treatment of Raynaud's disease (51,52). Raynaud's disease is a disease of the peripheral circulatory system that is caused by insufficient blood supply to the hands and feet. It can result in cyanosis, numbness, pain, and, in extreme cases, gangrene and subsequent amputation of the affected finger or toe. The vasospastic attacks are triggered by cold and, to a lesser extent, anxiety and stress. Recent data, however, has failed to transparently support the belief that temperature biofeedback is a more effective treatment than medication for Raynaud's disease.

The Raynaud's treatment study (53) was a large, multicenter randomized controlled trial comparing sustained relief nifedipine, pill placebo, temperature biofeedback, and EMG biofeedback (a behavioral control) on 313 individuals diagnosed with primary Raynaud's disease. Results indicated that while nifedipine was significantly different from medication placebo in reducing vasospastic attacks, temperature biofeedback was not significantly different from psychological placebo (EMG biofeedback) in reducing vasospastic attacks. Comparison of nifedipine and temperature biofeedback indicated a nonsignificant ($p = 0.08$) trend for the nifedipine to result in greater reductions in vasospastic attacks. However, 15% of the nifedipine group had to discontinue the treatment due to adverse reactions to the medication. The interpretation of the biofeedback results of the Raynaud's treatment study, however, have been criticized by the behavioral investigators of the project (54). They note that a substantial proportion of subjects in the temperature group (65%) did not achieve learning, compared to only 33% in a normal comparison group who achieved successful learning by the end of the 10 biofeedback sessions in the protocol.

EEG Biofeedback (Neurofeedback)

Ramirez et al. (55) exhaustively reviewed the scientific literature on EEG biofeedback treatment of Attention Deficit Disorder (ADD). These authors conclude that, as in many other areas of clinical biofeedback practice, the positive evidence from anecdotal sources and case reports is plentiful, but a dearth of rigorous studies does not allow firm inferences to be drawn about the therapeutic efficacy of enhanced alpha wave activity and hemispheric lateralized biofeedback training. The EEG biofeedback training with a combined training goal of modifying the pattern of theta and beta wave activity has shown promising implications for management of ADD in adults. Studies using the theta/beta training paradigm have reported significant improvement in academic, intellectual, and adaptive behavioral functioning following EEG treatment. Other studies using sensorimotor rhythm training (recording from the "Rolandic" cortex) have produced behavioral and cognitive improvements in ADD patients. Unfortunately, these studies like those in other therapeutic areas of biofeedback are plagued with methodological problems including small sample sizes, absent or inadequate placebo controls, no randomization to treatment conditions, and insufficient follow-up of patient status. However, some authors of recent nonrandomized studies contend that EEG biofeedback shows promising evidence of therapeutic efficacy on the core symptoms of childhood ADHD in comparison to or in combination with standard stimulant medication therapy, family counseling, and an individualized educational intervention (56).

Another clinical problem in which EEG biofeedback was tested in the early 1970s was for control of frequent and disabling seizures. These studies have been reviewed by Lubar (57). The most common types of EEG recording and feedback training successfully studied in human subjects are EEG alpha rhythm (8–13 Hz) recorded from the occipital region of the brain, theta activity (4–7 Hz), and beta activity (>14 Hz). With the introduction over the recent decades of effective and relatively safe antiepileptic drugs, interest in systematic research and clinical application of EEG biofeedback as a nonmedication method of seizure control has waned. However, intractable seizures are still encountered in routine clinical practice despite all pharmacotherapeutic efforts. Implantable stimulatory devices and surgical interventions are reserved for highly selected patients and carry significant risks. For those patients with uncontrolled seizure disorder who have been unresponsive to standard anticonvulsant medication regimens and/or are not candidates for surgical treatment, Lubar has advocated that they be considered for a trial of sensorimotor rhythm EEG biofeedback training for the most common types of psychomotor seizures (57). Note that the equipment is expensive and the training procedures are complex and time consuming, and thus practitioners familiar with EEG biofeedback treatment of epilepsy may be difficult to find.

Quantitative EEG recording and specialized biofeedback training protocols have been developed and tested in the treatment of addictive disorders such as alcoholism. Peniston et al. (58) studied a protocol for enhancing EEG alpha and theta wave activity, and improving "synchrony" among the brain wave rhythms along the power spectrum. Peniston et al. (58) propose that alcoholics have a predisposition to "brain wave desynchrony" and deficient alpha activity and show a vulnerability to alcohol's capacity to produce reinforcing (pleasant and relaxing) levels of slow brain wave activity. These investigators have evaluated the treatment in a series of studies suggesting that their neurotherapy protocol reduces subjective craving among severe alcohol abusers, improves psychological functioning on personality measures, increases alpha and theta activity levels, increases beta-endorphin levels, and increases time to relapse. However, a large, independent randomized controlled trial of Neurotherapy did not show the incremental benefit to relapse prevention of adding electronic neurotherapy to a traditional residential treatment program for severe, chronic alcoholics (59). Although widely practiced, the clinical utility and theoretical rationale of EEG biofeedback in treating alcohol abusers remains controversial among the scientific biofeedback community. While promising data exists to suggest the potential role of EEG biofeedback in substance abuse treatment, further research is needed to illuminate the conceptual basis of such treatment and the reliability of clinical improvements for alcoholism and other addictive disorders.

There are very limited data from controlled studies on the use of EEG biofeedback for control of symptoms associated with Tourette syndrome, a behavioral impulse control disorder characterized by a constellation of motor and vocal tics (involuntary behaviors). A few scattered case reports describe positive results using a course of EEG sensorimotor rhythm biofeedback training to treat complex motor tics and associated attention deficit symptoms (60). There may be overlap in this treatment approach with the observation that epilepsy cases with motor involvement show some remediation following sensorimotor EEG biofeedback training. There is speculation and anectodal reports to suggest that anxiety, depression, and attentional symptoms associated with complex tics in Tourette's may be the most responsive targets for psychophysiological treatment. Because of the multiple symptom clusters of Tourette's, and the likelihood that different treatment protocols are needed to address the range of affected behaviors, focusing treatment on the whole condition is difficult, and often a prioritization of the most severe problems must occur to serve as the focus of clinical attention. Most patients are managed on a medication regimen by their physicians and EEG biofeedback is seen a useful adjunct in selected cases that have not responded adequately to pharmacologic management alone or where medication usage is to be reduced for some reason.

Cardiovascular Reactivity

Heart rate variability (HRV) biofeedback is being studied as a psychophysiological means of managing heart problems such as cardiac arrhythmia. Earlier isolated attempts at biofeedback interventions with cardiovascular ailments using simpler unitary heart rate (beats/min) or blood pressure (mmHg) measures have not been remarkably successful on modifying disease states. Heart rate variability is derived from the standard deviation of the beat-to-beat time interval (in ms) recorded in the laboratory with an ECG machine or with a Holter monitor using 24 h ambulatory monitoring methods. Heart rate variability has been proposed as a more robust metric of overall cardiac health in that it provides an indirect marker of the heart's ability to respond to normal regulatory impulses that affect its rhythm. With higher levels of HRV, it is proposed that there is a better balance between the combined sympathetic and parasympathetic inputs to the heart. Generally, greater HRV is associated with relaxed states and slow or regular breathing pattern. The HRV biofeedback training is claimed to offer a more precise method for helping clients to moderate the heightened sympathetic activity that is associated with elevated stress, anxiety, and dysphoric mood. Relatively greater levels of heart rate variability have been associated with better heart health. Biofeedback of breathing rate and depth is also used to increase respiratory sinus arrhythmia, which may be connected to therapeutic increases in HRV. A few small-scale studies have been conducted that show the clinical potential of HRV biofeedback in cardiovascular diseases (61); however, the results are inconsistent, and methodological problems abound with the existing studies. As yet, there is little evidence from larger scale randomized controlled trials conducted at independent laboratories demonstrating the therapeutic efficacy of HRV biofeedback in specific cardiovascular disease states such as cardiac arrhythmia.

Incontinence: Urinary and Fecal

EMG biofeedback training of the bladder-urinary sphincter and pelvic floor musculature has been found to be an efficacious intervention for urge urinary incontinence, especially among female geriatric populations, and is usually related to destrusor muscle contraction instability or reduced bladder volume (62). Some form of Kegel exercises are often used to train the muscles of the pelvic floor that are in continuity with the external urethral sphincter. Biofeedback with behavior modification training of the anorectal-anal sphincter musculature along the pelvic floor has been reported to be successful in treatment of fecal incontinence of various etiologies (63). Small, insertable EMG sensors are usually used in current treatment protocols for urinary incontinence in female patients and for fecal incontinence. A second EMG channel with abdominal placement is often recommended to better isolate contraction of the pelvic muscles from activity of accessory muscle of the legs, buttocks, and abdomen during the training exercises. Some degree of voluntary contractibility of sphincter muscles and rectal sensitivity are necessary for successful biofeedback treatment. While biofeedback training for urinary incontinence has a longer history of usage, and thus a larger empirical base (64), there is considerable evidence to suggest the efficacy of EMG biofeedback in a majority of adult patients with fecal incontinence (65). Unfortunately, there was a great deal of variability in biofeedback instrumentation used among these studies, treatment protocols followed, and outcome measures with uncertain validity.

Stroke and Mild Traumatic Brain Injury

There is very limited research in the area of EEG biofeedback in treatment and rehabilitation of the neurological impairments resulting from stroke or closed head injury. There are a number of anecdotal reports and small case series that suggest a place for quantitative EEG analysis in the functional assessment of neurological symptoms secondary to stroke and head injury. A highly individualized QEEG protocol used in these studies is sometimes called EEG entrainment feedback recording from the surface of brain regions suspected to be pathologically involved in the functional impairments (66,67). Neuromuscular reeducation is a general term used to describe assessment and treatment methods that may include EMG biofeedback and are applied to helping neurologically impaired patients (such as poststroke patients) with regaining gross motor functions necessary for carrying out activities of daily living and ambulation. In a meta-analysis of controlled trials using EMG biofeedback for neuromuscular reeducation in hemiplegic stroke patients, the authors concluded that EMG biofeedback resulted in significant functional gains (68). While these results are promising, the specific effects of EMG biofeedback in stroke rehabilitation remain unclear as some of the studies reviewed included other interventions such as physical therapy or gait training as part of the rehabilitation program.

Sexual Dysfunction

Surface EMG biofeedback of targeted abnormalities in pelvic floor musculature are implicated in the pathogenesis of vulvovaginal pain (vulvodynia) syndromes such as dyspareunia resulting from vulvar vestibulitis. These have been successfully used in the stabilization of pelvic floor muscles leading to 83% reduction of pain symptoms, improved sexual function, and psychological adjustment at 6-month follow-up (69). As in other EMG biofeedback protocols for assessment and modification of abnormal pelvic floor musculature, an individualized assessment is performed to identify the patient's specific neuromuscular abnormality, with subsequent biofeedback training designed to modify the muscle tension and contractile weakness of the target muscles. However, gynecological surgery (vestibulectomy), on average, appears to produce superior outcomes (70).

FUTURE DIRECTIONS OF BIOFEEDBACK THERAPY

There are five areas that biofeedback research and clinical work are heading or should focus on. They are (*1*) expanding upon and refining current research; (*2*) applications of biofeedback and psychophysiological assessment to the "real world" environment (i.e., ambulatory monitoring); (*3*) applications of biofeedback training to new populations; (*4*) applications of biofeedback to applicatuons of biofeedback to the prinany the primary care setting; (*5*) alternative methods of treatment delivery.

1. Expanding Upon and Refining Current Research. Although biofeedback is considered a mature treatment, there are surprisingly many basic areas that need to be explored further. Such basic questions as (a) whether massed versus distributed practice produces greater physiological learning, (b) whether the presence or absence of the therapist in the room retards or enhances the acquisition of the biofeedback response, (c) the usefulness of coaching, (d) is their any value in training to criterion, (e) whether group biofeedback enhances or retards psychophysiological learning or clinical affects clinical outcome, have not been satisfactorily answered. Moreover, with the notable exception of headache, nearly every area is missing large scale treatment outcome studies (i.e., 25 or greater subjects per condition), in which biofeedback treatment is compared to placebo, another psychological treatment, conventional medical treatment, and so on. Many studies fail to describe the instrumentation and biofeedback procedures sufficiently to allow replication of the research. Often diagnostic criteria are not given, or diagnoses are commingled (e.g., conduct disorder children with attention deficit disorder children, or generalized anxiety disorder with simple phobias). Such failures to answer basic research questions or to conduct research in a scientifically acceptable manner are troubling and need to be corrected.

2. Applications of Biofeedback and Psychophysiological Assessment To the "Real World" Environment (i.e., ambulatory monitoring). Biofeedback clinicians have attempted to use their psychophysiological monitoring equipment to assist in setting treatment goals and to further explore the relationship between the mechanism of action believed to be involved in the underlying pathology of the disorder in question. For example, many clinicians use ambulatory blood pressure monitors to determine when their hypertensive patients are most reactive (work, driving, etc.) and tailor exercises to be maximized around those situations of elevated blood pressures. Use of such ambulatory equipment for other responses such as EMG, hand temperature, and respiration would be quite useful and such studies need to be performed.

There have been only a few studies examining the relationship between ambulatory monitoring in the naturalistic environment and the presumed pathological response underlying the disease, with the exception of bruxism and temporomandibular joint dysfunction, where measurement in the natural environment by telemetry, portable tape recording, and digital EMG integration have been reported (71). Unfortunately, with those exceptions, when such studies have been conducted, they have arrived at negative findings, quite possibly due to the difficulty in reducing the data and inability to control all the relevant variables (sleep is a relatively controlled environment). For example, Hatch et al. (72) had 12 tension headache subjects and nine nonheadache controls wear a computer-controlled EMG activity recorder in their natural environment for 48–96 consecutive hours. The EMG activity of the posterior neck or frontal muscles was recorded 24 h/day. During waking hours, subjects rated their perceived levels of stress, pain, and negative affect at 30-min intervals. The EMG activity of headache and control subjects did not differ significantly, and EMG activity did not covary with stress, pain, or negative affect. Cross-correlations among EMG activity, pain, and stress revealed little evidence of leading, contemporaneous, or lagging relationships. Interrupted time series analysis showed no consistent muscle hyperactivity during a headache attack compared to a headache-free baseline period.

Arena and co-workers designed a portable activity monitor for simultaneously recording and quantifying surface EMG signals and body movements in the natural environment (73). Two independent channels record EMG activity from symmetric muscle groups to determine contraction patterns. The EMG signals are amplified, filtered, integrated for 1 s, and converted to a digital value. Full scale was jumper selected to accommodate a wide range of muscle activity. Electrode resistance >20 kΩ generates an alarm to signal poor contact or lead-off condition. The EMG voltages less than a preset threshold are not integrated.

The movement sensors are electrolytic potentiometers whose output are proportional to angular position and linear acceleration. The outputs are differentiated and summed to obtain angular acceleration with minimal response to linear movement. The peak value and 1 s integral are converted to digital values.

Subjective evaluation of pain and activity may be annotated by a 16-button keypad. An hourly auditory alarm reminds the user to enter subjective evaluations.

Data is saved in static random-access memory in binary coded 3-byte words. Power is supplied by a 9 V alkaline battery and converted to ±5 V by switching regulators. At the end of 18 h of recording, all power is turned off except for standby power to memory. A low-battery condition will also switch power to the standby mode. Data retained in the standby mode is valid for at least 7 days.

Arena et al. demonstrated that the device is highly reliable in 26 healthy controls (74). They then had 18 tension-type headache subjects and 26 control subjects wear the device attached to the bilateral upper trapezius muscles for 5 consecutive days for up to 18 h a day (75). During waking hours, subjects rated their perceived levels of stress, pain, and physical activity at 60-min intervals. Similar to Hatch, the EMG activity of headache and control subjects did not differ significantly, and EMG activity did not covary with stress, pain, or physical activity levels. Examination of cross-correlations among EMG activity, pain, physical activity, and stress revealed little evidence of an isomorphic, precursor or consequence relationship. There were no consistent differences between a headache and nonheadache state on muscle activity levels.

Arena et al. (75) concluded that there were so many variables entering into the natural environment, that use of such devices required a sophistication not available to the average clinician or researcher, and that treating headache patients nomothetically as an aggregate, rather than idiographically, as individuals, may also present difficulties. For example, some individuals may lie down as soon as a headache begins, while others may continue with their daily routine. Other individuals may have consequence, precursor, or isomorphic relationships between their head pain, except the changes occur on an every 5 min basis rather than a 1 h basis. With still others, to identify a relationship 5 consecutive days is not enough. Given the fact that the technology has increased exponentially to allow much more sophisticated data reduction and statistical analysis, we feel that the time is now ripe for a renaissance in such an area of research, which has been dormant for nearly a decade.

3. Applications of Biofeedback Training to Other Populations. As biofeedback is considered to be an established field, investigators have begun to take the treatments and expand it to other, similar clinical problems. For example, in the field of headache, biofeedback has been shown to be effective with the elderly, children, and pregnant women (6). Areas that need to be explored further to determine whether biofeedback treatment effects can be generalized are headaches in depressed individuals, headaches in individuals following cerebral aneurysm, headaches due to eyestrain, posttraumatic headache, and headache in multiple sclerosis patients. Similarly, the anxiety disorders literature needs to be expanded to include children, the elderly, anxiety due to a medical condition, and so on.
4. Application in Primary Care Medical Settings. Because of the growing recognition of the high prevalence of psychosomatic and psychophysiological disorders that present in primary care settings, the increased availability and implementation of psychophysiological assessment and biofeedback interventions in these healthcare settings appears to be timely (76). Many behavioral medicine interventions including biofeedback may be more efficiently and effectively delivered in these primary practice settings as the focus of these interventions is often toward the goals of preventing or slowing disease progression rather than treating severe or complicated problems that are well established. This approach is in contrast to conventional practice where patients with complicated medical problems or cooccurring psychological symptoms are referred out to specialty behavioral medicine clinics or other specialists (e.g., physical therapists) for psychophysiological treatment. As many chronic health problems are progressive in nature, by the time referral is made, the patient's condition is likely to have worsened to the point where behavioral intervention including biofeedback training may have far less impact than had it been instituted earlier in the disease course.

However, for biofeedback to be successfully integrated into the busy primary care office practice setting, certain modifications will have to be made in the context of assessment protocol and treatment delivery. First, behavioral assessment will have to be brief, but informative and practical, yielding results that are helpful to the primary care team in managing the patient's medical problems. The assessment results will have to be readily incorporated into the medical record of the patient rather than assigned privileged status, as mental health records frequently are, and therefore accessible to few if any providers for reference in primary care delivery. Second, the psychophysiology assessment and biofeedback treatment program will have to be carefully standardized and mid-level providers such as nurses, physician assistants, psychology technicians, or other mental health therapists trained in the competent and efficient delivery of these services. A doctoral level psychologist on staff or consulting from another facility should be available to supervise these services to monitor quality and assess outcomes. Third, the rapid advancement of biofeedback equipment in terms of measurement accuracy, increased reliability with precision electronics, lowered cost, much improved portability through miniaturization, and enhanced patient convenience with alternative sensor technology has enabled the possibility of almost entirely home-based, self-administered treatment. Instruction and support can be provided by nursing staff, consultant psychologist, or other health professional through less frequent office visits and telephone consultation as needed. Arena and Blanchard have recently outlined in greater detail steps one should take to apply behavioral medicine techniques such as biofeedback to the trement of headaches in the primary care setting (3).

5. Alternative Methods of Treatment Delivery. The availability of relatively low cost, high precision biofeedback training devices lends itself to the possibility of a limited-therapist-contact, largely home-based treatment regimen. Blanchard and co-workers published three separate studies (77–79) evaluating a treatment regimen of three sessions (>2 months) combining thermal biofeedback and progressive relaxation training. In all three instances, very positive results were found for this attenuated form of treatment. Similar results were reported by Tobin et al. (80).

We believe that some limited therapist contact is often necessary, so that patients understand the rationale for the treatment and that problems (trying too hard, thermistor misplacement, etc.) can be caught and corrected early. We also believe that detailed manuals to guide the home training, and telephone consultation to troubleshoot problems, are crucial in this approach. Given the national push for improving the efficiency of treatments, this approach has much to recommend it. We should also note that this home-based approach was not as successful as office-based treatment of essential hypertension with thermal biofeedback (81).

This limited therapist contact does not have to be face-to-face with the therapist, however. It can be conducted via the Internet or using a videoconferencing telemedicine application. Devineni and Blanchard (under review 82) conducted a randomized controlled study of an Internet-delivered behavioral regimen composed of progressive relaxation, limited biofeedback with autogenic training, and stress management in comparison to a symptom monitoring waitlist control. Thirty-nine percent of treated individuals showed clinically significant improvement on self-report measures of headache symptoms at post-treatment. At 2-month follow-up, 47% of participants maintained improvement. There was a 35% within-group reduction of medication usage among the treated subjects. The Internet program was noticeably more time cost-efficient than traditional clinical treatment. Treatment and follow-up dropout rates, 38.1 and 64.8%, respectively, were typical of behavioral self-help studies.

Arena et al. (83) recently reported a small ($n = 4$) uncontrolled study investigating the feasibility of an Internet and/or telemedicine delivery modality for relaxation therapy and thermal biofeedback for vascular headache. Each subject was over the age of 50 and had suffered from headaches for >20 years. Subjects came into the clinic for treatment but never saw the therapist in person. Instead, all treatment was conducted through the use of computer terminals and monitors. The only difference between this treatment and office-based treatment was the physical presence of the therapist. Results indicated one of the subjects was a treatment success (>50% headache improvement, and two others had between 25 and 50% improvements. Thus, it seems that further exploration into the potential of telemedicine and internet delivery of psychophysiological interventions is warranted.

In summary, an attempt has been made to review the basic theories underlying the application of biofeedback training to the amelioration of a broad range of general medical and psychiatric disorders. Also covered are the main types of biofeedback systems, technical specifications of instrumentation, and engineering design considerations for major functional components of biofeedback apparatus. A sampling of the many clinical problem areas in which psychophysiological assessment technology and biofeedback instrumentation have been utilized with varying degrees of success is discussed. This coverage of instrumentation is not exhaustive. Given the rich basic science underpinnings of biofeedback and the wide appeal among both health professionals and the general public, this coverage was by necessity selective and opportunistic. Throughout this article are found references to key resources of primary literature and authoritative reviews of the biofeedback field. This technological area is one of the most promising of both professional psychology practice and consumer oriented general healthcare. The field of biofeedback is far from matured, with medical application of basic research finding beginning only ~30 years ago. The field is probably in its second generation with a more rigorous examination of its scientific underpinnings, casting aside unproven or implausible theories related to disease process and treatment efficacy, and development of a sound empirical basis for its assessment methods and interventions. We are witnessing the continued rapid advancement of microcomputer technology and digital electronics coupled with the accumulation of knowledge of the basic mechanisms involved in human health and disease. There is a great potential for an evolution of biofeedback from its early origins with focus on nonpathological states and development of body awareness, human potential, and wellness to a more refined and sophisticated understanding and application of techniques toward the maintenance of health and prevention of disease states that is seamlessly integrated into the individual's lifestyle.

BIBLIOGRAPHY

Cited References

1. Olton DS, Noonberg AR. Biofeedback: Clinical applications in behavioral medicine. Englewood Cliffs, NJ.: Prentice Hall; 1980.
2. Wilder J. The law of initial values. Psychosom Med 1950;12: 392–400.
3. Arena JG, Blanchard EB. Assessment and treatment of chronic benign headache in the primary care setting. In: O'Donohue W, Cummings N, Henderson D, Byrd M, editors. Behavioral integrative care: Treatments that work in the primary care setting. New York: Allyn & Bacon; 2005. p 293–313.
4. Carney RM, Blumenthal JA, Stein PK, Watkins L, Catellier D, Berkman LF, Czajkowski SM, O'Connor C, Stone PH, Freedland KE. Depression, heart rate variability, and acute myocardial infarction. Circulation 2001; 104:2024–2028.
5. Task Force of the European Society of Cardiology and The North American Society of Pacing and Electrophysiology. Heart rate variability: Standards of measurement, physiological interpretation, and clinical use. Eur Heart J 1996;17:354–381.
6. Arena JG, Blanchard EB. Biofeedback training for chronic pain disorders: A primer. In: Gatchel RJ, Turk DC, editors. Chronic pain: Psychological perspectives on treatment. 2nd ed. New York: Guilford Publications; 2002. p 159–186.
7. Arena JG, Blanchard EB. Biofeedback Therapy for Chronic Pain Disorders. In: Loeser JD, Turk D, Chapman RC, Butler S, editors. Bonica's Management of Pain. 3rd ed. Baltimore: Williams & Wilkins; 2001. p 1755–1763.
8. Blanchard EB, Arena JG. Biofeedback, relaxation training and other psychological treatments for chronic benign headache. In: Diamond ML, Solomon GD, editors. Diamond's and Dalessio's The Practicing Physician's Approach to Headache. 6th ed. New York: W. B. Saunders; 1999. p 209–224.
9. Lippold DCJ. Electromyography. In: Venables PH, Martin I, editors. Manual of Psychophysiological Methods. New York: John Wiley & Sons; 1967.
10. Evans DD. A comparison of two computerized thermal biofeedback displays in migraine headache patients and controls. [Unpublished dissertation]. State University of New York at Albany; 1988.
11. Libo LM, Arnold GE. Does training to criterion influence improvement? A follow-up study of EMG and thermal biofeedback. J Behav Med 1983;6:397–404.
12. Blanchard EB, Andrasik F, Neff DF, Saunders NL, Arena JG, Pallmeyer TP, Teders SJ, Jurish SE, Rodichok LD. Four process studies in the behavioral treatment of chronic headache. Behav Res Ther 1983;21:209–220.
13. Morrill B, Blanchard EB. Two studies of the potential mechanisms of action in the thermal biofeedback treatment of vascular headache. Headache 1989;29:169–176.
14. Tsai P, Calderon KS, Yucha CB, Tian L. Biofeedback training to criteria and blood pressure reduction. Proceedings of the 34th Annual Meeting of the Association for Applied Psychophysiology and Biofeedback. Wheat Ridge, Colorado: AAPB; 2003.
15. Budzynski T. Biofeedback in the treatment of muscle-contraction (tension) headache. Biofeedback Self Regul 1978; 3:409–434.
16. Basmajian JV. Facts vs. myths in EMG biofeedback. Biofeedback Self Regul 1976;1:369–378.
17. Belar CD. A comment on Silver and Blanchard's (1978) review of the treatment of tension headaches by EMG biofeedback and relaxation training. J Behav Med 1979;2:215–218.
18. Hudzinski LG. Neck musculature and EMG biofeedback in treatment of muscle contraction headache. Headache 1983;23:86–90.
19. Hart JD, Cirhanski KA. A comparison of frontal EMG biofeedback and neck EMG biofeedback in the treatment of muscle-contraction headache. Biofeedback Self Regul 1981;6:63–74.
20. Philips C. The modification of tension headache pain using EMG biofeedback. Behav Res Ther 1977;15:119–129.
21. Philips C, Hunter M. The treatment of tension headache. II. Muscular abnormality and biofeedback. Behav Res Ther 1981;19:859–489.
22. Arena JG, Bruno GM, Hannah SL, Meador KJ. A comparison of frontal electromyographic biofeedback training, trapezius electromyographic biofeedback training and progressive muscle relaxation therapy in the treatment of tension headache. Headache 1995;35:411–419.
23. American Psychiatric Association. Diagnostic and Statistical Manual of Mental Disorders IV-TR. Washington, DC: APA Press; 2000.
24. Rice KM, Blanchard EB, Purcell M. Biofedback treatments of generalized anxiety disorder: preliminary results. Biofeedback Self Regul 1993;18:93–105.
25. Eppley KR, Abrams AJ, Shear J. Differential effects of relaxation techniques on trait anxiety: a meta analysis. J Clin Psychol 1989;45:957–974.
26. Spence J. Maximization of biofeedback following cognitive stress pre-selection in generalized anxiety. Percept Mot Skills 1986;63:239–242.
27. Moore NC. A review of EEG biofeedback treatment of anxiety disorders. Clin Electroencephalog 2000;31:1–6.
28. Crider AB, Glaros AG. A meta-analysis of EMG biofeedback treatment of temporomandibular disorders. J Orofac Pain 1999;13:29–37.
29. Gevirtz RN, Glaros AG, Hooper D, Schwartz MS. Temporomandibular disorders. In: Schwartz MS, editor. Biofeedback: A practitioner's guide. 2nd ed. New York: Guilford; 1995. p 411–428.
30. Turk DC, Rudy TE, Kubinski JA, Zaki HS, Greco CM. Dysfunctional patients with temporomandibular disorders: Evaluating the efficacy of a tailored treatment protocol. J Consult Clin Psychol 1996;64:139–146.
31. Turk DC, Zaki HS, Rudy TE. Effects of intraoral appliance and biofeedback/stress management alone and in combination in treating pain and depression in patients with temporomandibular disorders. J Prosthet Dent 1993;70:158–164.
32. Greco CM, Rudy TE, Turk DC, Herlich A, Zaki HH. Traumatic onset of temporomandibular disorders: Positive effects of a standardized conservative treatment program. Clin J Pain 1997;13:337–347.
33. Mueller HH, Donaldson CC, Nelson DV, Layman M. Treatment of fibromyalgia incorporating EEG-Driven stimulation: a clinical outcomes study. J Clin Psychol 2001;57: 933–952.
34. van Santen M, Bolwijn P, Verstappen F, Bakker C, Hidding A, Houben H, van der Heijde D, Landewe R, van der Linden S. A randomized clinical trial comparing fitness and biofeedback training versus basic treatment in patients with fibromyalgia. J Rheumatol 2002;29:575–581.
35. Drexler AR, Mur EJ, Gunther VC. Efficacy of an EMG-biofeedback therapy in fibromyalgia patients. A comparative study of patients with and without abnormality in (MMPI) psychological scales. Clin Exp Rheumatol 2002; 20:677–682.
36. Nolli M et al. Evaluation of chronic fibromyalgic pain before and after EMG-BFB training. Algos 1986;3:249–253.

37. Ferraccioli G et al. EMG-biofeedback training in fibromyalgia syndrome. J Rheumatol 1987;14:820–825.
38. Waylonis GW, Perkins RH. Post-traumatic fibromyalgia: A long-term follow-up. Am J Phys Med Rehabil 1994;73:403–412.
39. Buckelew SP et al. Self-efficacy predicting outcome among fibromyalgia patients. Arthritis Care Res 1996;9:97–104.
40. Sarnoch H, Adler F, Scholz OB. Relevance of muscular sensitivity, muscular activity, and cognitive variables for pain reduction associated with EMG biofeedback for fibromyalgia. Percept Mot Skills 1997;84:1043–1050.
41. Jorge JM, Habr-Gama A, Wexner SD. Biofeedback therapy in the colon and rectal practice. Appl Psychophysiol Biofeedback 2003;28:47–61.
42. Mason HJ, Serrano-Ikkos E, Kamm MA. Psychological state and quality of life in patients having behavioral treatment (biofeedback) for intractable constipation. Am J Gastroenterol 2002;97:3154–3159.
43. Benninga MA, Buller HA, Taminiau JA. Biofeedback training in chronic constipation. Arch Dis Child 1993;68:126–129.
44. Cox DJ, Sutphen J, Borowitz S, Dickens MN, Singles, Whitehead WE. Simple electromyographic biofeedback treatment for chronic pediatric constipation/encopresis: Preliminary report. Biofeedback Self Regul 1994;19:41–50.
45. Van der Plas RN et al. Biofeedback training in treatment of childhood constipation: A randomized controlled trial. Lancet North Am Ed 1996;348:776–780.
46. Leahy A, Clayman C, Mason I, Lloyd G, Epstein O. Computerized biofeedback games: a new method for teaching stress management and its use in irritable bowel syndrome. J R Coll Phys London 1998;32:552–556.
47. Radnitz CL, Blanchard EB. Bowel sound biofeedback as a treatment for irritable bowel syndrome. Biofeedback Self Regul 1988;13:169–179.
48. Radnitz CL, Blanchard EB. A 1- and 2-year follow-up study of bowel sound biofeedback as a treatment for irritable bowel syndrome. Biofeedback Self Regul 1989;14:333–338.
49. Burish TG, Jenkins RA. Effectiveness of biofeedback and relaxation training in reducing side effects of cancer chemotherapy. Health Psychol 1992;11:17–23.
50. Nakao M, Yano E, Nomura S, Kuboki T. Blood pressure-lowering effects of biofeedback treatment in hypertension: A meta-analysis of randomized controlled trials. Hypertens Res 2003;26:37–46.
51. Freedman RR. Long-term effectiveness of behavioral treatments for Raynaud's Disease. Behav Ther 1987;18:387–399.
52. Sedlacek K, Taub E. Biofeedback treatment of Raynaud's Disease. Prof Psychol Res Pr 1996;27:548–553.
53. Raynaud's Treatment Study Investigators. Comparison of sustained-release nifedipine and temperature biofeedback for treatment of primary Raynaud phenomenon. Results from a randomized clinical trial with 1-year follow-up. Arch Intern Med 2000;24:1101–1108.
54. Middaugh SJ, Haythornthwaite JA, Thompson B, Hill R, Brown KM, Freedman RR, Attanasio V, Jacob RG, Scheier M, Smith EA. The Raynaud's Treatment Study: biofeedback protocols and acquisition of temperature biofeedback skills. Appl Psychophysiol Biofeedback 2001;26:251–278.
55. Ramirez PM, DeSantis D, Opler LA. EEG biofeedback treatment of ADD: A viable alternative to traditional medical intervention? Adult Attention Deficit Disorder: Brain Mechanisms and Life Outcomes. In: Wasserstein J, et al., editors. Ann. N. Y. Acad. Sci. New York: New York Academy of Sciences; 2001.
56. Monastra VJ, Monastra DM, George S. The effects of stimulant therapy, EEG biofeedback, and parenting style on the primary symptoms of attention-deficit/hyperactivity disorder. Appl Psychophysiol Biofeedback 2002;27:231–249.
57. Luber JF. Electroencephalographic biofeedback methodology and the management of epilepsy. Integr Physiol Behav Sci 1998;33:1053–1088.
58. Peniston EG, Kulkosky PJ. Neurofeedback in the treatment of addictive disorders. In: Evans JR, Abarbanel A, editors. Introduction to Quantitative EEG and Neurofeedback. San Diego: Academic Press; 1999. p 157–179.
59. Taub E, Steiner SS, Weingarten E, Walton KG. Effectiveness of broad spectrum approaches to relapse prevention in severe alcoholism: A long-term, randomized, controlled trial of Transcendental Meditation, EMG biofeedback, and electronic neurotherapy. Alcohol Treat Q 1994;11:187–220.
60. Tansey MA. A simple and a complex tic (Gilles de la Tourette's syndrome): Their response to EEG sensorimotor rhythm biofeedback training. Int J Psychophysiol 1986;4:91–97.
61. Brody C, Davison ET, Brody J. Self-regulation of a complex ventricular arrhythmia. Psychosom: J Consult-Liaison Psychiat 1985;26:754–756.
62. Burgio KL, Locher JL, Goode PS, Hardin JM, McDowell BJ, Dombrowski M, Candib D. Behavioral vs. drug treatment for urge urinary incontinence: A randomized controlled trial. J Am Med Assoc 1998;280:1995–2000.
63. Jorge JMN, Habr-Gama A, Wexner SD. Biofeedback therapy in the colon and rectal practice. Appl Psychophysiol Biofeedback 2003;28:47–61.
64. Tries J, Brubaker L. Application of biofeedback in the treatment of urinary incontinence. Prof Psychol Res Pr 1996;27:554–560.
65. Norton C, Kamm MA. Anal sphincter biofeedback and pelvic floor exercises for faecal incontinence in adults—A systematic review. Aliment Pharmacol Ther 2001;15:1147–1154.
66. Rozelle GR, Budzynski TH. Neurotherapy for stroke rehabilitation: A single case study. Biofeedback Self Regul 1995;20:211–228.
67. Byers AP. Neurofeedback therapy for a mild head injury. J Neurother 1995;1:22–37.
68. Schleenbaker RE, Mainous AG. Electromyographic biofeedback for neuromuscular reeducation in the hemiplegic stroke patient—A meta-analysis. Arch Phys Med Rehabil 1993;74:1301–1304.
69. Glazer HI, Rodke G, Swencionis C, Hertz R, Young AW. Treatment of Vulvar Vestibulitis Syndrome with Electromyographic Biofeedback of Pelvic Floor Musculature. J Reprod Med 1995;40:283–290.
70. Bergeron S, Binik YM, Khalife S, Pagidas K, Glazer HI, Meana M, Amsel R. A randomized comparison of group cognitive-behavioral therapy, surface electromyographic biofeedback, and vestibulectomy in the treatment of dyspareunia resulting from vulvar vestibulitis. Pain 2001;91:297–306.
71. Burger C, Rough J. An EMG integrator for muscle activity studies in ambulatory subjects. IEEE Trans Biomed Eng 1983; 66–69.
72. Hatch JP, Prihoda TJ, Moore PJ, Cyr-Provost M, Borcherding S, Boutros NN, Seleshi E. A naturalistic study of the relationships among electromyographic activity, psychological stress, and pain in ambulatory tension-type headache patients and headache-free controls. Psychosom Med 1991;53:576–584.
73. Searle JR, Arena JG, Sherman RA. A portable activity monitor for musculoskeletal pain disorders. Proc Annu Int Conf IEEE Eng Med Biol Soc. 1989.

74. Arena JG, Bruno GM, Brucks AG, Searle JD, Sherman RA, Meador KJ. Reliability of an ambulatory electromyographic activity device for musculoskeletal pain disorders. Int J Psychophysiol 1994;17:153–157.
75. Arena JG, Bruno GM, Brucks AG, Searle JD, Sherman RA, Meador KJ (unpublished manuscript). The measurement of surface EMG in tension-headache subjects in the natural environment: Ambulatory recordings of data from five consecutive days.
76. Gatchel RJ, Oordt MS. Future trends and opportunities. In: Gatchel RJ, Oordt MS, editors. Clinical Health Psychology and Primary Care: Practical Advice and Clinical Guidance for Successful Collaboration. Washington, DC: American Psychological Association; 2003.
77. Blanchard EB, Andrasik F, Appelbaum KA, Evans DD, Jurish SE, Teders SJ, Rodichok LD, Barron KD. The efficacy and cost-effectiveness of minimal-therapist contact, non-drug treatments of chronic migraine and tension headache. Headache 1985a;25:214–220.
78. Blanchard EB, Appelbaum KA, Nicholson NL, Radnitz CL, Morrill B, Michultka D, Kirsch C, Hillhouse J, Dentinger MP. A controlled evaluation of the addition of cognitive therapy to a home-based biofeedback and relaxation treatment of vascular headache. Headache 1990a;30:371–376.
79. Jurish SE, Blanchard EB, Andrasik F, Teders SJ, Neff DF, Arena JG. Home versus clinic-based treatment of vascular headache. J Consult Clin Psychol 1983;51:743–751.
80. Tobin DL, Holroyd KA, Baker A, Reynolds RVC, Holms JE. Development and clinical trial of a minimal contact, cognitive-behavioral treatment for tension headache. Cognit Ther Res 1988;12:325–339.
81. Blanchard EB, McCoy GC, Musso A, Gerardi RJ, Cotch PA, Siracusa K, Andrasik F. A controlled comparison of thermal biofeedback and relaxation training in the treatment of essential hypertension: I. Short-term and long-term outcome. Behav Ther 1986;17:563–579.
82. Devineni T, Blanchard EB. A Randomized Controlled Trial of an Internet-based Treatment for Chronic Headache. Behav Res Ther 2005;43:277–292.
83. Arena JG, Dennis N, Devineni T, McClean R, Meador KJ. A pilot study of the feasibility of a telemedicine delivery system for psychophysiological treatments for vascular headache. Tele Meo J E-Health 2005;10:449–454.

See also BIOELECTRODES; ELECTROENCEPHALOGRAPHY; ELECTROGASTROGRAM; ELECTROMYOGRAPHY.

BIOHEAT TRANSFER

JONATHAN W. VALVANO
The University of Texas
Austin, Texas

INTRODUCTION

Bioheat transfer is the study of the transport of thermal energy in living systems. Because biochemical processes are temperature dependent, heat transfer plays a major role in living systems. Also, because the mass transport of blood through tissue causes a consequent thermal energy transfer, bioheat transfer methods are applicable for diagnostic and therapeutic applications involving either mass or heat transfer. This article presents the characteristics of bioheat transfer that distinguish it from nonliving systems, including the effects of blood perfusion on temperature distribution, coupling with biochemical processes, therapeutic and injury processes, and thermoregulation.



Figure 1. Countercurrent blood vessels have arterial blood flowing in the opposite direction as venous blood.

The study of bioheat transfer involves phenomena that are not found in systems that are not alive. For example, blood perfusion is considered a three-dimensional (3D) process as fluid traverses in a volumetric manner through tissues and organs via a complex network of branching vessels. Heat transfer is affected by vessel geometry, local blood flow rates, and thermal capacity of the blood (1). One factor that makes modeling blood perfusion difficult is the complex network of pairs of arteries and veins with countercurrent flow (2), as shown in Fig. 1. Arterial and venous blood temperatures may be different, and it is possible that neither is equal to the local tissue temperature. These temperatures may vary as a function of many transient physiological and physical parameters. The regulation of temperature and blood flow is quite nonlinear and has presented a major challenge to understand and model. Nevertheless, these critical processes must be accounted for in the design of many types of systems that interface with humans and animals.

Many scientists view life from either the macroscopic (systems) or the microscopic (cellular) level, but in reality one must be aware that life processes exist continuously throughout the spectrum. In order to better understand life processes at the molecular level, a significant research effort is underway associated with molecular biology. Because temperature and blood flow are critical factors, bioengineers are collaborating with molecular biologists to understand and manipulate the molecular and biochemical processes that constitute the basis of life. Research has found that the rates of nearly all physiological functions are altered 6–10%/°C (3). Similarly, heat can be added or removed during therapeutic or diagnostic procedures to produce or measure a targeted effect, based on the fact that a change in local temperature will have a large effect on rates of biochemical process rates. Thus, the measurement and control of temperature in living tissues is of great value in both the assessment of normal physiological function and the treatment of pathological states.

The study of the effects of temperature alterations on biochemical rate processes has been divided into three broad categories: hyperthermia (increased temperature), hypothermia (decreased temperature), and cryobiology (subfreezing temperature). An extensive review of these domains has been published (4), to which the reader is referred for further details and bibliography.

Effects of Blood Perfusion on Heat Transfer

Blood perfusion through the vascular network and the local temperature distribution are interdependent. Many environmental (e.g., heat stress and hypothermia), pathophysiologic (e.g., inflammation and cancer), therapeutic (e.g., heating–cooling pads) situations create a significant temperature difference between the blood and the tissue through which it flows. The temperature difference causes convective heat transport to occur, altering the temperatures of both the blood and the tissue. Perfusion-based heat transfer interaction is critical to a number of physiological processes, such as thermoregulation and inflammation.

The convective heat transfer depends on the rate of perfusion and the vascular anatomy, which vary widely among the different tissues, organs of the body, and pathology. Diller et al. published an extensive compilation of perfusion data for many tissues and organs and for many species (5). Charney reviewed the literature on mathematical modeling of the influence of blood perfusion on bioheat transfer phenomena (6).

The rate of perfusion of blood through different tissues and organs varies over the time course of a normal day's activities, depending on factors, such as physical activity, physiological stimulus, and environmental conditions. Further, many disease processes are characterized by alterations in blood perfusion, and some therapeutic interventions result in either an increase or decrease in blood flow in a target tissue. For these reasons, it is very useful in a clinical context to know what the absolute level of blood perfusion is within a given tissue. Many thermal techniques have been developed that directly measure heat flux to predict blood perfusion by exploiting the coupling between vascular perfusion and local tissue temperature using inverse mathematical solutions.

In 1948, Pennes (7) published the seminal work describing the mathematical coupling between the mass transfer of blood perfusion and the thermal heat transfer. His work consisted of a series of experiments to measure temperature distribution as a function of radial position in the forearms of nine human subjects. A butt-junction thermocouple was passed completely through the arm via a needle inserted as a temporary track, with the two leads exiting on opposite sides of the arm. The subjects were unanesthetized so as to avoid the effects of anesthesia on blood perfusion. Following a period of normalization, the thermocouple was scanned transversely across the mediolateral axis to measure the temperature as a function of radial position within the interior of the arm. The environment in the experimental suite was kept thermally neutral during experiments. Pennes' data showed a temperature difference of 3–4° between the skin and the interior of the arm, which he attributed to the effects of metabolic heat generation and heat transfer with arterial blood perfused through the microvasculature.

Pennes proposed a model to describe the effects of metabolism and blood perfusion on the energy balance within tissue. These two effects were incorporated into the standard thermal diffusion equation, which is written in its simplified form as

$$\rho c \frac{\partial T}{\partial t} = \nabla \cdot k \nabla T + \rho_{\mathrm{bl}} c_{\mathrm{bl}} w (T_a - T) + Q_{\mathrm{met}} \qquad (1)$$

Metabolic heat generation, Q_{met}, is assumed to be homogeneously distributed throughout the tissue of interest as rate of energy deposition per unit volume. It is assumed that the blood perfusion effect is homogeneous and isotropic, and that thermal equilibration occurs in the microcirculatory capillary bed. In this scenario, blood enters capillaries at the temperature of arterial blood, T_a, where heat exchange occurs to bring the temperature to that of the surrounding tissue, T. There is assumed to be no energy transfer either before or after the blood passes through the capillaries, so that the temperature at which it enters the venous circulation is that of the local tissue. The total energy exchange between blood and tissue is directly proportional to the density, ρ_{bl}, specific heat, c_{bl}, and perfusion rate, w, of blood through the tissue. The basic principle that couples mass transfer to heat transfer is the change in sensible energy caused by the moving blood. The units of perfusion in equation 1 are volume of blood per volume of tissue per time (s^{-1}). This thermal transport model is analogous to the process of mass transport between blood and tissue, which is confined primarily to the capillary bed.

A major advantage of the Pennes model is that the added term to account for perfusion heat transfer is linear in temperature, which facilitates the solution of Eq. 1. Since the publication of this work, the Pennes model has been adapted by many researchers for the analysis of a variety of bioheat transfer phenomena. These applications vary in physiological complexity from a simple homogeneous volume of tissue to thermal regulation of the entire human body (8,9). As more scientists have evaluated the Pennes model for application in specific physiological systems, it has become increasingly clear that many of the assumptions to the model are not valid. For example, it is now well established that the significant heat transfer due to blood flow occurs in the terminal arterioles (vessels 60–300 μm in diameter) (10–17). Thermal equilibration is essentially complete for vessels <60 μm (precapillaries and capillaries). Therefore, no significant heat transfer occurs in the capillary bed; the exchange of heat occurs in the larger components of the vascular tree. The vascular morphology varies considerably among the various organs of the body, which contributes to the need for specific models for the thermal effects of blood flow (as compared to the Pennes model that incorporates no information concerning vascular geometry). It would appear as a consequence of these physiological realities that the validity of the Pennes model is questionable.

Many investigators have developed alternative models for the exchange of heat between blood and tissue. These models have accounted for the effects of vessel size, countercurrent heat exchange, as well as a combination of partial countercurrent exchange and bleed-off perfusion. All of these models provided a larger degree of rigor in the analysis, but at the compromise of greater complexity and reduced generality. These studies also led to an increased appreciation of the necessity for a more explicit understanding of the local vascular morphology as it governs bioheat transfer, which has given rise to experimental studies to measure and characterize the 3D architecture of the vasculature in tissues and organs of interest (18). The quantitative analysis of the effects of blood perfusion on the internal temperature distribution in living tissue remains a topic of active research after one-half of a century of study (19).

THERAPEUTIC APPLICATIONS OF BIOHEAT TRANSFER

The elevation of tissue temperature into the 40–42 °C range provides some relief from pain (analgesia). In addition, wound healing can be enhanced by this modest increase in temperature. Increased temperature does not cause healing by itself, but rather it creates the improved conditions for the natural processes to heal wounds.

Hot or cold packs can be used to create therapeutic heating for injuries near the skin surface. Heating packs are effective for injuries such as sprains, muscle strains, and postoperative swelling. Elevated temperatures cause an increase in blood perfusion, supplying nutrients to the injured tissue. During the first 12–24 h after injury, cold packs will reduce perfusion, thereby reducing vascular pressure and tissue swelling. Afterward, hot packs (up to 45 °C) are applied to increase perfusion and promote healing (20).

When the injury is deeper, the therapy requires a volumetric heater, such as radio frequency (rf) electromagnetic heating, microwave frequency electromagnetic heating, and ultrasonic heating. The Industrial-Medical-Scientific (ISM) frequencies are 6.78, 13.56, 27.12, and 40.68 MHz. The ISM frequencies typically used in medical applications of microwaves are 915 MHz and 2.45 GHz. Medical ultrasonic devices operate in the 500 kHz to 10 MHz range. There are three engineering parameters to consider when designing a therapeutic device. The first parameter is the amount of local volumetric heat generation, the second parameter is the shape of the heating field, and the third parameter is the depth of penetration. Higher frequencies have shorter wavelengths, causing higher absorption and less penetration. The electrical properties of the tissue, which depend on structure and composition, strongly affect the effectiveness of volumetric heating using rf and microwave EM fields. Similarly, acoustic properties of the tissue are important in ultrasonic systems. Often the design of an effective therapeutic device hinges on proper control of the boundary conditions where energy is transferred across the transducer–tissue interface.

There is a systemic effect of local heating, controlled by the hypothalamus, involving both neuronal and hormonal signals. Local heating of organs or peripheral muscles can also cause a spinal cord mediated response. A local release of bradykinins can affect the vascular tone of the terminal arterioles (see Fig. 1), which in turn affect the vascular resistance to blood flow. In general, an increase in local temperature causes an increase in local blood flow, whereas a decrease in local temperature creates a decrease in local blood flow, but the behavior is highly complex.

Smooth muscles surrounding the 40–200 μm diameter arterioles play a dominate role in controlling local blood flow. Normal capillary pressure is ~3.3 kPa (25 Torr). When local tissues are heated, these arterioles dilate causing an increase in capillary pressure and capillary blood flow. Edema occurs when this pressure widens gaps in the capillary wall causing excess fluid to leak from the vascular to intravascular space. High capillary flow promotes healing by removing wastes, delivering nutrients, and supplying oxygen. Leukocytes (white blood cells) control the healing process by first breaking down, then removing damaged and dead tissue.

The volumetric heating created by electromagnetic fields in governed by the electrical conductivity, σ ($\mathrm{S \cdot m^{-1}}$), the imaginary part of the electrical permittivity, ε'' ($\mathrm{F \cdot m^{-1}}$), and the magnitude of the local electric field, $|E|$ ($\mathrm{V \cdot m^{-1}}$):

$$q''' = (\sigma + \omega\varepsilon'')|E|^2 \tag{2}$$

where ω is the angular frequency of the field in rad $\mathrm{s^{-1}}$. Direct heating from the magnetic fields in medical applications is usually neglected. Magnetic fields can be used to heat tissue, but because of Faraday's law of induction, the time-varying magnetic field will induce an electric field, and it is this electric field that heats the tissue. A comprehensive review of electromagnetic heating can be found in Roussy and Pearce (21). Tables of electrical and acoustic properties can be found in Diller (5).

THERMOREGULATION

Thermoregulation is an elaborate control system, used by mammals, to maintain internal body temperatures near a physiological set point under a large spectrum of environmental conditions and metabolic rate activities. Even though there have been many years of research, much remains unknown about the human thermoregulatory system. Therefore, active investigation continues. Heat transfer due to conduction, convective heat transfer via the blood flow, local generation of thermal energy, and thermal boundary conditions comprise the major components of thermoregulation. Once these individual mechanisms are understood, they can be combined to create mathematical models to simulate and predict thermoregulatory behavior. The mathematical models are used to design systems to interact thermally with the human body (such as a space suit) without compromising the health and safety of the subject.

The prevailing theory is that the main objective of a human thermoregulation system is to maintain the body core temperature at a constant value consistent with that required for normal physiological functions, regardless of the environmental conditions. An alternative theory, suggested by Chappuis et al. (22) and Webb (23), is that the goal of the human regulation system is to maintain the body's energy balance. In this theory, tissue temperatures are a result, rather than a cause, of the regulation process.

Nunneley (24,25) showed that temperature and internal energy storage of the human body vary with time of day, metabolic activity, and individuality of the human. To maintain body core temperature, the thermoregulatory system incorporates a number of energy production and dissipation mechanisms, many of them controlled by feedback from other body parameters. Examples of such feedback control are that for sweating, shivering, and varying blood flow.

Ganong (26) showed that the main control center for feedback mechanisms is located in the hypothalamus of the brain, where reflex responses operate to maintain the body temperature within its narrow range. The signals that activate the hypothalamic temperature regulating centers come largely from two sources: the temperature-sensitive cells in the anterior hypothalamus and cutaneous temperature receptors. The cells in the anterior hypothalamus sense the temperature of the body core or, specifically, the temperature of the arterial blood that passes through the head.

The theory of energy regulation is based on the demonstration of the existence of temperature sensors at several levels in the skin enabling the sensing of heat flow within and from the body. Evidence has also shown neurological sensing of thermal gradients, of which changes relate to the thermal regulating responses. Therefore, the hypothesis behind the theory of energy content regulation based on Webb's experimental observations is "Heat (energy) regulation achieves heat (energy) balance over a wide range of heat (energy) loads. Heat flow to or from the body is sensed, and physiological responses defend the body heat (energy) content. Heat (energy) content varies over a range that is related to heat (energy) load. Changes in body heat (energy) content drive deep body temperatures" (23). Energy regulation involves constantly changing metabolic energy production and the adjustment of heat losses to maintain a system in equilibrium. This mechanism is opposed to temperature regulation where adjustments are required to maintain body temperature.

The thermal energy balance over time within the human body combines the heat added by internal production minus the heat lost by various heat-transfer processes.

$$\Delta E = M - (W + Q_{\mathrm{conv}} + Q_{\mathrm{cond}} + Q_{\mathrm{rad}} + Q_{\mathrm{evap}} + Q_{\mathrm{resp}}) \tag{3}$$

where ΔE is the rate of energy storage in the body (W), M is the metabolic energy production (W), W is the external work (W), Q_{conv} is the surface heat loss by convection (W), Q_{cond} is the surface heat loss by conduction (W), Q_{rad} is the surface heat loss by radiation (W), Q_{evap} is the surface heat loss by evaporation (W), and Q_{resp} is the respiratory heat loss (W).

The human body produces energy, exchanges heat with the environment, and loses heat by evaporation of body fluids. Thermal energy is produced by metabolism, a biochemical process occurring in cells has adenosine triphosphate (ATP) is combined with oxygen to produce the various life functions. Fulcher (27) defined the basal metabolic rate as "the minimal metabolism measured at a temperature of thermal neutrality in a resting homeotherm with normal body temperature several hours after a meal and not immediately after hypothermia". Energy is also produced at an increased rate due to muscle activity, including physical exercise and shivering, and by food intake. Therefore, the total energy production in the body is determined by the energy needed for basic body processes plus any external work. Since the body operates with <100% efficiency only a fraction of the metabolic rate is applied to work. The remainder shows up as heat. The mechanical efficiency associated with metabolic energy utilization is zero for most activities except when the person is performing external mechanical work, such as in walking upstairs, lifting something to a higher level, or cycling on an exercise machine. When external work is dissipated into heat in the human body, the mechanical efficiency is negative. An example of negative mechanical efficiency is walking downstairs.

Convection, radiation, conduction, and evaporation of sweat at the skin surface allow heat to be dissipated from the body. There is also heat transfer, especially when the environmental air temperature is extremely high or low, through the respiratory tract and lungs. Storage of energy takes place whenever there is an imbalance of production and dissipation mechanisms. In many instances, such as astronauts in space suits or military personnel in chemical defense garments, energy storage is forced due to the lack of appropriate heat exchange with the environment.

The human thermoregulatory system is quite complicated and behaves mathematically in a highly nonlinear manner. It contains multiple sensors, multiple feedback loops, and multiple outputs. The control mechanisms to release excess energy include the production of sweat, and vasodilatation of the blood vessels in the skin. Conversely, to conserve energy there can be shivering of the muscles, and vasoconstriction of blood vessels, which engage in the transportation of heat to the surface of the body.

Heat transfer within the body is due to the internal conductance that governs the flow of heat from the core, through the tissue, to the surface. This component of heat transfer is governed by peripheral blood flow, the core-skin temperature gradient, and the conductivity of the body tissue. Blood flow provides the majority of the peripheral conductance where there is convection between blood and tissue and countercurrent heat exchange between the arteries and the veins. Blood flow is controlled according to metabolic needs of the body as well as the need to maintain the appropriate core temperature. When the core becomes too hot, the blood vessels in the skin dilate to allow increased blood flow to the surface of the skin. Then, the environment cools the blood and the cooler blood returns to the core. Increased blood flow to the skin surface increases extravascular pressure enabling greater sweat production, again adding to the cooling process. In contrast, when the core becomes too cold, blood flow to the skin is constricted to conserve the body's internal energy.

Sweating is centrally controlled by the hypothalamus. When the body senses an increase temperature the hypothalamus increases nerve impulses to the sweat glands. Shivering, on the other hand, is an involuntary response of the skeletal muscles when passive body cooling exceeds metabolic energy production.

This section briefly introduced the concepts of thermoregulation. For a quantitative analysis of this topic, see Wissler (8,9).

THERMAL INJURY

Thermal injury is defined as irreversible changes to living tissue caused by temperature. Injury can occur when the tissue temperature exceeds the range between which normal life processes exist. Both high and low temperature can cause irreversible changes to biomolecules, resulting in injury. Common examples are burns and frostbite. Recently, it has been discovered that under some kinds of moderate thermal stress that is subthreshold to injury, cells produce molecules that render temporary protection against levels of many types of stress (thermal, mechanical, chemical, etc.) that would normally cause injury. These protective molecules are called heat shock proteins, and they are the subject of widespread investigation to identify the kinetics of their expression and function. It is an effort to develop applications in which they may be induced either before or even after a traumatic event.

The most commonly encountered type of thermal injury is the burn. Accidental burns are encountered most frequently in domestic and industrial settings as well as many other venues of activity. Most burns result from the propagation of heat inward into tissues as a result of contact at the surface (skin) with a hot solid, liquid, or vapor. One exception is electrical burns in which the tissue temperature is elevated owing to I^2R dissipation of electric energy when a voltage is applied. In this case, the primary source of heating is internal since the impedance of muscle is higher than of skin and fat.

It is generally assumed that thermal burns can be modeled as a simple Arrhenius rate process such that

$$\Omega(t) = \int_0^t A e^{\Delta E/RT(\tau)} d\tau \qquad (4)$$

where Ω is a dimensionless damage parameter (e.g., $\Omega = 1$ means first degree burn), A is a frequency factor (s^{-1}), ΔE is the activation energy in $\mathrm{J \cdot mol^{-1}}$, R is the universal gas constant ($8.314\,\mathrm{J \cdot mol^{-1} \cdot K^{-1}}$), and T is the tissue temperature (K). The constants A and ΔE are tissue parameters, and $T(\tau)$ is the time history of the tissue temperature (28).

This model was first posed for predicting the severity of a burn as a function of the temperature and time of exposure at the skin surface by Moritz and Henriques (29) shortly after World War II. They also performed experiments to determine threshold conditions for eliciting first and second degree burns in humans and applied this data to determine values for the scaling constant and activation energy in their Arrhenius model. Their experiments were conducted at temperatures between 44 and 70°C and exposure times between 1 and 25,000 s. The model parameter values are $A = 3.1 \times 10^{98}\,\mathrm{s}^{-1}$ and $\Delta E = 6.28 \times 10^5\,\mathrm{kJ \cdot mol^{-1}}$. Over the ensuing 50 years many subsequent investigators have studied this process with mathematical models and experimental investigations (30–40). Although a considerable body of literature has been accrued, there is by no means a consensus on how to accurately predict the occurrence of thermal injury over the wide range of conditions that cause burns.

SUBZERO EFFECTS

One application of subzero temperatures is the long-term preservation of biologic tissue. Therapeutic devices based on subzero temperatures can be used to destroy cancerous cells or remove necrotic tissue. The rate of biochemical processes is governed by local temperature. Lowering the temperature has the effect of reducing reaction rates, and at sufficiently low temperatures, a state of suspended animation can be achieved. Because of the water component of physiological fluids, temperatures low enough to affect suspended animation normally result in freezing. The freezing of native biomaterials is nearly always lethal to the affected tissue upon thawing. The formation of ice has two damaging effects. The first effect is mechanical as intracellular ice crystals physically damage cell structures. The second and more lethal effect is osmotic. The local concentration of ions, such as $\mathrm{Na^+}$, $\mathrm{K^+}$, and $\mathrm{Cl^-}$, are critical for sustaining life, and a high concentration of these ions is produced as liquid water freezes into ice. The effected injury can be used to benefit in cryosurgery for the purpose of destroying a target tissue, such as cancer. Alternatively, the tissue can be modified prior to freezing by the introduction of a chemical cryoprotective agent (CPA) to afford protection from freeze–thaw injury. The CPA either protects against the injurious effects of ice formation or blocks the formation of ice so that a glassy state results, which is called vitrification. Organ transplantation, blood banks, and animal husbandry are three applications that require the successful long-term cryopreservation of biologic tissue. The response of living biomaterials to freezing and thawing is intimately tied to the thermal history during processing, especially at subzero temperatures. Thus, bioheat transfer analysis has played a key role in the design and development of effective cryopreservation techniques. Polge was first to report the successful use of glycerol to freeze fowl sperm >55 years ago (41). Successes were reported in succession for other types of tissues having rather simple cell structures, such as erythrocytes, gametes and various cells obtained from primary cultures (42–44). Most of these cryopreservation techniques were derived via largely empirical methods, and starting in the 1970s it came to be realized that the cryopreservation of more complex systems, such as multicellular tissues and whole organs require a more rigorous scientific understanding of the mechanisms of the governing biophysical processes and cellular response to freezing and thawing. Since that time engineers have made significant contributions to the developing science of cryobiology, not the least of which has been to identify some of the key biophysical problems to be solved (45,46).

MEASUREMENT OF THERMAL CONDUCTIVITY AND THERMAL DIFFUSIVITY

While the other sections in this article presented brief overviews of the various disciplines within the field of



Figure 2. A glass-coated thermistor is placed into or on the surface of the tissue of interest.

bioheat transfer, this section will present in detail a specific measurement technique. In particular, this section presents an instrument used to measure thermal properties in tissue. The section begins with definitions of thermal properties, overviews of the technique, then develops the heat-transfer equations that form the basis of the instrument. Finally, calibration methods and error analyses are presented.

Definitions of Thermal Properties

Thermal conductivity (k) is the ability of a material to transport heat in the steady state. In one dimension, the total heat (Q) transported across a flat surface of area A and thickness Δx is related to the temperature gradient across the surface (ΔT) and the thermal conductivity of the material.

$$Q = -kA\frac{\Delta T}{\Delta x} \tag{5}$$

Thermal diffusivity (α) is the ability of a material to conduct heat in the transient state. Thermal properties of conductivity and diffusivity are related. The quotient of conductivity divided by diffusivity equals density times specific heat.

$$\frac{k}{\alpha} = \rho c \tag{6}$$

Diffusivity is often defined in the partial differential equation used to describe transient heat transfer. Assuming homogeneous thermal properties, the Fourier conduction equation in one dimension is

$$\frac{\partial^2 T}{\partial x^2} = \frac{1}{\alpha}\frac{\partial T}{\partial t} \tag{7}$$

Measurement Technique

The technique involves inserting a thermistor into the tissue of interest or placing it on the tissue surface, as shown in Fig. 2. Thermometrics P60DA102M and Fenwal 121-102EAJ-Q01 are glass probe thermistors that make excellent transducers (shown on the left of Fig. 2). The diameter of these thermistors is ~0.15 cm. The glass-coated spherical probes provide a large bead size and a rugged, stable transducer. The Thermometrics BR55KA102M and Fenwal 112-102EAJ-B01 bead thermistors also provide excellent results (shown on the right of Fig. 2).

If the tissue is living, the properties measured are called effective thermal conductivity, k_{eff}, and effective thermal diffusivity, α_{eff}. Effective thermal properties include the contribution to heat transfer due to intrinsic conduction added to the contribution caused by the transport of blood through the tissue.

In the constant temperature heating technique (47–52), the instrument first measures the baseline tissue temperature, T_s. Then, an electronic feedback circuit applies a variable voltage, $V_0(t)$, in order to maintain the average thermistor temperature at a predefined constant, T_h. The electrical circuit used to implement the constant temperature heating technique is shown in Fig. 3. Three high quality, gold-plated, electromagnetic relays are used to switch the thermistor (R_s) between "heat" and "sense" mode. Figure 3 shows the position of the three relays in "heat" mode. Initially, the instrument places the circuit in "sense" mode with the three relays in



Figure 3. Instrumentation used for the constant temperature heating technique.

the opposite position as shown in Fig. 3. A precision +5.00 V reference (PMI REF02) supplies voltage to the four-resistor bridge, formed by the two 50 kΩ, R_{set}, and R_s resistors. The voltage difference $V_2 - V_1$ is fed to a differential amplifier, passed through a low pass filter, then fed to a 12-bit ADC.

Fundamental Equations

Resistance calibration is performed to determine the relationship between the ADC sample and the unknown R_s. Next, temperature calibration is performed by placing the thermistor adjacent to an accurate temperature monitor and placing the combination in a temperature- controlled waterbath. The thermistor resistance varies nonlinearly with its temperature. For small temperature ranges equation 8 can be used for temperature calibration.

$$R_s = R_O\, e^{\beta/(T_s+273.15)} \qquad (8)$$

where T_s is the temperature in degrees Celsius, and R_s is the thermistor resistance in ohms.

In heat mode, the integrator–inverter circuit varies the voltage across the thermistor until the thermistor resistance, R_s, matches the fixed resistor, R_{set}. It takes just a few milliseconds for the electrical control circuit to stabilize. Once stable, R_s is equal to R_{set}, meaning the volume average thermistor temperature is equal to a constant. The instrument uses a calibration temperature versus resistance curve to determine the heated temperature T_h from the fixed resistor R_{set}. The power applied to the thermistor, P, is calculated from $(V_0)^2/R_{\text{set}}$. The applied thermistor power includes a steady state and a transient term:

$$P(t) = A + Bt^{-1/2} \qquad (9)$$

In order to measure thermal conductivity, thermal diffusivity, and tissue perfusion the relationship between applied thermistor power, P, and resulting thermistor temperature rise, $\Delta T(t) = T_h - T_s$, must be known. In the constant temperature method, ΔT is constant. The thermistor bead is treated as a sphere of radius a embedded in a homogeneous medium. Since all media are considered to have constant parameters with respect to time and space, the initial temperature will be uniform when no power is supplied to the probe.

$$T_b = T_m = T_s = T_a + \frac{Q_{\text{met}}}{w\rho_{\text{bl}}c_{\text{bl}}} \qquad \text{at} \quad t = 0 \qquad (10)$$

Let V be the temperature rise above baseline, $V = T - T_s$. Both the thermistor bead temperature rise (V_b) and the tissue temperature rise (V_m) are initially zero.

$$V_b = V_m = 0 \qquad \text{at} \quad t = 0 \qquad (11)$$

To solve this coupled thermistor–tissue system, equation 7 is written in spherical coordinates and the applied power is deposited into the thermistor, while the perfusion heat sink is added to the tissue, equation 1. Assuming the venous blood temperature equilibrates with the tissue temperature and that the metabolic heat is uniform in time and space, the Pennes' bioheat transfer equation in spherical coordinates is given by

$$\rho_b c_b \frac{\partial V_b}{\partial t} = k_b \frac{1}{r^2}\frac{\partial}{\partial r}\left(r^2 \frac{\partial V_b}{\partial r}\right) + \frac{A + Bt^{-1/2}}{4/3\pi a^3} \qquad r < a \qquad (12)$$

$$\rho_m c_m \frac{\partial V_m}{\partial t} = k_m \frac{1}{r^2}\frac{\partial}{\partial r}\left(r^2 \frac{\partial V_m}{\partial r}\right) - w\rho_{bl}c_{bl}V_m \qquad r > a \qquad (13)$$

where w is the tissue perfusion (s^{-1}). Perfect thermal contact is assumed between the finite-sized spherical thermistor and the infinite homogeneous perfused tissue. At the interface between the bead and the tissue, continuity of thermal flux and temperature leads to the following boundary conditions:

$$V_b = V_m \qquad \text{at } r = a \qquad (14)$$

$$k_b \frac{\partial V_b}{\partial r} = k_m \frac{\partial V_m}{\partial r} \qquad \text{at } r = a \qquad (15)$$

The other boundary conditions are necessary at positions $r \to 0$ and $r \to$ infinity. Since no heat is gained or lost at the center of the thermistor:

$$k_b \frac{\partial V_b}{\partial r} = 0 \qquad \text{as } r \to 0 \qquad (16)$$

Because the thermistor power is finite and the tissue is infinite, the tissue temperature rise at infinity goes to zero:

$$V_m \to 0 \qquad \text{as } r \to \text{infinity} \qquad (17)$$

It is this last initial condition that allows the Laplace transform to be used to solve the coupled partial differential equations. The Laplace transform converts the partial differential equations into ordinary differential equations that are independent of time t. The steady-state solution allows for the determination of thermal conductivity and perfusion (49).

$$V_b(r) = \frac{A}{4\pi a k_b}\left(\frac{k_b}{k_m(1+\sqrt{z})} + \frac{1}{2}\left[1 - \left(\frac{r}{a}\right)^2\right]\right) \qquad (18)$$

$$V_m(r) = \frac{A}{4\pi r k_m}\left(\frac{e^{(1-r/a)\sqrt{z}}}{1+\sqrt{z}}\right) \qquad (19)$$

where z is a dimensionless Pennes' model perfusion term ($w\rho_{\text{bl}}\, c_{\text{bl}}\, a^2/k_m$). The measured thermistor response, ΔT, is assumed be the simple volume average of the thermistor temperature:

$$\Delta T = \frac{\int_0^a V_b(r) 4\pi r^2 dr}{4/3\pi a^3} \qquad (20)$$

Inserting equation 18 into Eq. 20 yields the relationship used to measure thermal conductivity assuming no perfusion (49).

$$k_m = \frac{1}{\frac{4\pi a \Delta T}{A} - \frac{0.2}{k_b}} \qquad (21)$$

A similar equation allows the measurement of thermal diffusivity from the transient response, again assuming no perfusion (49).

$$\alpha_m = \left(\frac{a}{\sqrt{\pi}\,\frac{B}{A}(1 + 0.2\frac{k_m}{k_b})}\right)^2 \tag{22}$$

Calibration Equations

The first calibration determines relationship between the ADC sample and the thermistor resistance when in sense mode. For this calibration, precision resistors are connected in place of the thermistor, and the computer-based instrument is used to sample the ADC in sense mode. A simple linear equation works well for converting ADC samples to measured resistance. In this procedure, the device acts like a standard ohmmeter.

The second calibration determines the relationship between thermistor temperature and its resistance. The instrument measures resistance, and a precision thermometer determines true temperature. Equation 23 yields an accurate fit over a wide range of temperature:

$$T = \frac{1}{H_0 + H_1 \ln(R) + H_3[\ln(R)]^3} - 273.15 \tag{23}$$

where T is in degrees Celsius. Temperature resistance data are fit to Eq. 23 using nonlinear regression to determine the calibration coefficients H_0, H_1, and H_3.

The applied power, $P(t)$, is measured during a 30 s transient while in heat mode. Nonlinear regression is used to calculate the steady-state and transient terms in equation 9. Figure 4 shows some typical responses. The steady-state response (time equals infinity) is a measure of the thermal conductivity. The transient response (slope) indicated the thermal diffusivity.

The third calibration maps measured power to thermal properties while operating in heat mode. Rather than using the actual probe radius (a) and probe thermal conductivity (k_b), as shown in Eqs. 21 and 22, the following empirical equations are used to calculate thermal properties.



Figure 4. Typical $P/\Delta T$ versus $t^{-1/2}$ data for the constant temperature heating technique. The agar-gelled water and glycerol curves are used for empirical calibration.

$$k_m = \frac{1}{(c_1\,\Delta T/A) + c_2} \tag{24}$$

$$\alpha_m = \left(\frac{c_3}{B/A(1 + k_m/c_4)}\right)^2 \tag{25}$$

The coefficients c_1, c_2, c_3, and c_4 are determined by operating the probe in two materials of known thermal properties. Typically, agar-gelled water and glycerol are used as thermal standards. This empirical calibration is performed at the same temperatures at which the thermal property measurements will be performed.

Error Analysis

It is assumed that the baseline tissue temperature, T_0, is constant during the 30 s transient. Patel has shown that if the temperature drift, dT_0/dt, is $>0.002\,^{\circ}\mathrm{C}\cdot\mathrm{s}^{-1}$, then significant errors will occur (52). The electronic feedback circuit forces T_h to a constant. Thus, if T_0 is constant then ΔT does not vary during the 30 s transient.

The time of heating can vary from 10 to 60 s. Shorter heating times are better for small tissue samples and for situations where there is baseline tissue temperature drift. Another advantage of shorter heating times is the reduction in the total time required to make one measurement. Longer heating times increase the measurement volume and reduce the effect of imperfect thermistor–tissue coupling. Typically, shorter heating times are used *in vivo* because it allows more measurements to be taken over the same time period. On the other hand, longer heating times are used *in vitro* because accuracy is more important than measurement speed.

Thermal probes must be constructed in order to measure thermal properties. The two important factors for the thermal probe are thermal contact and transducer sensitivity. The shape of the probe should be chosen in order to minimize trauma during insertion. Any boundary layer between the thermistor and the tissue of interest will cause a significant measurement error. The second factor is transducer sensitivity that is the slope of the thermistor voltage versus tissue thermal conductivity. Equation 21 shows for a fixed ΔT k_m and k_b the thermistor power (A) increases linearly with probe size (a). Therefore larger probes are more sensitive to thermal conductivity. For large tissue samples, multiple thermistors can be wired in parallel, so they act electrically and thermally as one large device. There are two advantages to using multiple thermistors. The effective radius, $a = c_1/4\pi$, is increased from ~0.08 cm for a typical single P60DA102M probe to ~0.5 cm for a configuration of three P60DA102M thermistors. The second advantage is that the three thermistors are close enough to each other that the tissue between the probes will be heated by all three thermistors. This cooperative heating tends to increase the effective measurement volume and reduce the probe/tissue contact error. Good mechanical–thermal contact is critical. The probes are calibrated after they are constructed, so that the thermistor geometry is incorporated into the coefficients

c_1, c_2, c_3, and c_4. The same waterbath, and probe configuration should be used during the calibration and during the tissue measurements.

Calibration is a critical factor when using an empirical technique. For temperatures $<0\,^\circ$C, ice and ethylene glycol are used as thermal standards. For temperatures between 0 and 15 °C, agar-gelled water and ethylene glycol can be used as thermal standards. For temperatures between 15 and 75 °C, agar-gelled water and glycerol were used. To prevent convection, 1 g of agar/100 mL of water should be added. A mixture of water and glycerol can be used to estimate the accuracy of the technique. The mass fraction, m, can be used to determine the true thermal properties of the mixture (53,54). The ability to determine measurement accuracy is critical for the acceptance of new technology. These two equations provide for the capability to create reference materials of known thermal properties, which can be used to experimentally determine measurement accuracy.

$$k_m = m\,k_g + (1-m)k_w + 1.4\,m(m-1)(k_w - k_g - 2) - 0.014\,m(m-1)(T - 20\,^\circ\mathrm{C}) \qquad (26)$$

$$\alpha_m = m\,\alpha_g + (1-m)\alpha_w \qquad (27)$$

where T is in degrees Celsius. Self-heat thermistors have also been successfully used to measure the convective heat transfer coefficient on the endocardial surface of the heart (55,56).

ADDITIONAL STUDIES

In this article, the general concepts of bioheat transfer were introduced, and a detailed design and analysis of an instrument that measures thermal properties was presented. Although out of print, the 1985 book *Heat Transfer in Medicine and Biology*, is a wonderful collection of detailed works that address a wide spectrum of topics in bioheat transfer. The book *Optical-Thermal Response of Laser Irradiated Tissue* covers the issues involved in high temperature effect such as tissue damage and thermal ablation. Valvano's chapter titled Temperature Measurements, in *Advances In Heat Transfer: Bioengineering Heat Transfer*, covers many practical issues involved in measuring temperature in the biomedical setting. An in depth treatment of bioheat transfer topics can be found in the 2005 edition of *CRC Handbook of Heat Transfer*. This reference has excellent treatments of thermoregulation and low temperature effects.

BIBLIOGRAPHY

Cited References

1. Baish JW, Ayyaswamy PS, Foster KR. Heat transport mechanisms in vascular tissues: a model comparison. J Biomech Eng 1986;108:324–331.
2. Baish JW. Heat transport by countercurrent blood vessels in the presence of an arbitrary temperature gradient. J Biomech Eng 1990;112:207–211.
3. Johnston KA, Bennett AF, editors. Animals and Temperature: Phenotypic and Evolutionary Adaptation. Cambridge: Cambridge University Press; 1996.
4. Diller KR. Modeling of bioheat transfer processes at high and low temperatures. Adv Heat Trans 1992;22:157–357.
5. Diller KR, Valvano JW, Pearce JA. Bioheat Transfer. In: Kneith F, editor. CRC Handbook of Heat Transfer, 2nd ed. 2005.
6. Charney CK. Mathematical models of bioheat transfer. Adv Heat Trans 1992;22:19–155.
7. Pennes HH. Analysis of Tissue and Arterial Blood Temperature in the Resting Human Forearm. J Appl Phys 1948;1:93–102.
8. Wissler E. A review of human thermal models. In: Morrison MB, editor. Environmental Ergonomics. New York: Taylor and Francis; 1988. p 267–285.
9. Wissler EH. Mathematical simulation of human thermal behavior using whole-body models. In: Shitzer A, Eberhart RC, editors. Heat Transfer in Medicine and Biology. Vol. 1. New York: Plenum Press; 1985. p 325–373.
10. Chato JC. Heat transfer to blood vessels. J Biomech Eng 1980;102:110–118.
11. Chen MM, Holmes KR. Microvascular contributions in tissue heat transfer. Annals NY Acad Sci 1980;335:137–150.
12. Weinbaum S, Jiji L, Lemons DE. Theory and Experiment for the Effect of Vascular Temperature on Surface Tissue Heat Transfer—Part 1: Anatomical Foundation and Model Conceptualization. ASME J Biomech Eng 1984;106:246–251.
13. Weinbaum S, Jiji L, Lemons DE. Theory and Experiment for the Effect of Vascular Temperature on Surface Tissue Heat Transfer—Part 2: Model Formulation and Solution. ASME J Biomech Eng 1984;106:331–341.
14. Weinbaum S, Jiji L. A New Simplified Bioheat Equation for the Effect of Blood Flow on Average Tissue Temperature. J of Biomech Eng 1985;107:131–139.
15. Charny CK, Weinbaum S, Levin RL. An Evaluation of the Weinbaum-Jiji Bioheat Equation for Normal and Hyperthermic Conditions. ASME J Biomech Eng 1990;112:80–87.
16. Xu LX, Chen MM, Holmes KR, Arkin H. The Evaluation of the Pennes, the Chen-Holmes, the Weinbaum-Jiji Bioheat Transfer Models in the Pig Kidney Cortex. ASME WAM Proc HDT 1991;189:15–21.
17. Arkin H, Xu LX, Holmes KR. Recent Developments in Modeling Heat Transfer in Blood Perfused Tissues. IEEE Trans Biomed Eng 1994;41(2):97–107.
18. Wissler EH. Pennes' 1948 paper revisited. J Appl Physiol 1998;85:35–41.
19. Pennes HH. Analysis of tissue and arterial blood temperatures in the resting forearm. J Appl Physiol 1948;1:93–122 (republished for fiftieth anniversary issue of J Appl Physiol 1998;85:5–34).
20. Scully RM, Barnes MR. Physical Therapy. Philadelphia: J.B. Lippincott Co.; 1989.
21. Roussy G, Pearce JA. Foundations And Industrial Applications Of Microwaves Physical And Chemical Processes. New York: John Wiley & Sons, Inc.; 1995.
22. Chappuis P et al. Heat storage regulation in exercise during thermal transients. J Appl Physiol 1976;40:384–392.
23. Webb P. The physiology of heat regulation. Am J Physiol 1995;268:R838–R850.
24. Nunneley SA. Water cooled garments: a review. Space Life Sci 1970;2:335–360.
25. Nunneley SA. Physiological response of women to thermal stress: A review. Med Sci Sports 1978;10:250–255.
26. Ganong WF. Review of Medical Physiology. 16th ed. Norwalk (CT): Appleton and Lange; 1993.
27. Fulcher CWG. Control of a liquid cooling garment for extravehicular astronauts by cutaneous and external auditory meatus temperatures, Ph.D. dissertation, Houston (TX): University of Houston; 1970.

28. Thomsen S. Mapping of thermal injury in biologic tissues using quantitative pathologic techniques. Proc SPIE 1999;3594-09:822–897.
29. Moritz AR, Henriques FC. Studies of Thermal Injury. II. The Relative Importance of Time and Surface Temperature in the Causation of Cutaneous Burns. Am J Path 1947;23:695–720.
30. Büttner K. Effects of extreme heat and cold on human skin. I. analysis of temperature changes caused by different kinds of heat application. J Appl Physiol 1951;3:691–702.
31. Büttner K. Effects of extreme heat and cold on human skin. II. surface temperature, pain and heat conductivity in experiments with radiant heat. J Appl Physiol 1951;3: 691–702.
32. Stoll AM. A computer solution for determination of thermal tissue damage integrals from experimental data. I R E Trans Med Electron 1960;7:355–358.
33. Stoll AM, Chianta MA. Burn production and prevention in convective and radiant heat transfer. Aerospace Med 1968;39:1232–1238.
34. Stoll AM, Green LC. Relationship between pain and tissue damage due to thermal radiation. J Appl Physiol 1959;14:373–382.
35. Ross DC, Diller KR. An experimental investigation of burn injury in living tissue. J Heat Trans 1976;98:292–296.
36. Lawrence JC, Bull JP. Thermal conditions which cause skin burns. J Inst Mech Eng Eng Med 1976;5:61–63.
37. Takata AN. Development of criterion for skin burns. Aerospace Med 1974;45:634–637.
38. Welch AJ, Polhamus GD. Measurement and prediction of thermal injury in the retina of Rhesus monkey. IEEE Trans Biomed Eng 1984;BME-31:633–644.
39. Thomsen S, Pearce JA, Cheong WF. Changes in birefringence as makers of thermal damage in tissues. IEEE Trans Biomed Eng 1989;BME-36:1174–1179.
40. Pearce JA, Thomsen S. Kinetic models of tissue fusion processes. Proc SPIE Laser Tissue Int III 1992;1643.
41. Polge C, Smith AU, Parkes AS. Revival of spermatozoa after vitrificaiton and dehydration at low temperatures. Nature 1949;164:666.
42. Lovelock JE The mechanism of the protective action of glycerol against haemolysis by freezing and thawing. Biochim Biophys Acta 1953;11:28–36.
43. Strumia MM, Clawell LS, Strumia PV. The preservation of blood for transfusion. J Lab Clin Med 1960;56:576–593.
44. Whittingham DG, Leibo SP, Mazur P. Survival of mouse embryos frozen to −196°C and −296°C. Science 1972;178: 411–414.
45. McGrath JJ, Diller KR, editors. Low Temperature Biotechnology: Emerging Applications and Engineering Contributions. New York: ASME; 1988. p 1–380.
46. Diller KR, Ryan TP. Heat transfer in living systems: current opportunities. J Heat Trans 1998;120:810–829.
47. Bowman HF. Estimation of Tissue Blood Flow. In: Shitzer, Eberhart, editors. Heat Transfer in Medicine and Biology. New York: Plenum; 1985. p 193–230.
48. Chato JC. Measurement of Thermal Properties of Biological Materials. In: Shitzer, Eberhart, editors. Heat Transfer in Medicine and Biology. New York: Plenum; 1985. p 167–192.
49. Valvano JW, et al. The simultaneous measurement of thermal conductivity, thermal diffusivity and perfusion in small volumes of tissue. J Biomech Eng 1984;106:192–197.
50. Valvano JW, et al. Thermal conductivity and diffusivity of biomaterials measured with self-heated thermistors. Intern J Thermophys 1985;6:301–311.
51. Valvano JW, Chitsabesan B. Thermal conductivity and diffusivity of arterial wall and atherosclerotic plaque. Lasers Life Sci 1987;1:219–229.
52. Patel PA, et al. A self-heated thermistor technique to measure effective thermal properties from the tissue surface. J Biomech Eng 1987;109:330–335.
53. Rastorguev YL, Ganiev YA. Thermal conductivity of aqueous solutions or organic materials. Russ J Phys Chem 1966;40: 869–871.
54. Touloukian YS, et al. Thermophysical Properties of Matter: Thermal Conductivity. Vol. 3. New York: IFI/Plenum; 1970. p 120, 209.
55. dos Santos I, et al. An instrument to measure the heat convection coefficient on the endocardial surface. Physiol Measur 2003;24:321–335.
56. dos Santos I, et al. In vivo measurements of heat transfer on the endocardial surface. Physiol Measur 2003;24:793–804.

Reading List

Welch AJ, van Gemert M, editors. Optical-Thermal Response of Laser Irradiated Tissue. New York: Plenum Press; 1995.
Valvano JW. Temperature Measurements. In: Advances In Heat Transfer: Bioengineering Heat Transfer. Vol. 22. New York: Academic Press; 1992. p 359–436.
Roussy G, Pearce JA. Foundations And Industrial Applications of Microwaves Physical And Chemical Processes. New York: John Wiley & Sons, Inc.; 1995.
Shitzer, Eberhart, editors. Heat Transfer in Medicine and Biology. New York: Plenum; 1985.
Kreith F, editor. CRC Handbook of Heat Transfer. 2nd ed. 2005.

See also CYSTIC FIBROSIS SWEAT TEST; HYPERTHERMIA, SYSTEMIC; TEMPERATURE MONITORING; THERMOMETRY.

BIOIMPEDANCE IN CARDIOVASCULAR MEDICINE

DOUGLAS A. HETTRICK
TODD M. ZIELINSKI
Medtronic, Inc.
Minneapolis, Minnesota

INTRODUCTION

Historical Context

Electrical impedance measurements have been applied to the study of biologic systems for nearly 200 years. Indeed, the history of continuously flowing electricity began with Luigi Galvani's famous experiments on bioelectricity at the University of Bologna (1,2). It was not until the 1870s however, that Hermann Müller in Konigsberg/Zürich discovered the capacitive properties of tissue and the anisotropy of muscle conductance based on alternating current measurements. In 1864, James C. Maxwell contrived his now famous equations by specifically calculating the resistance of a homogeneous suspension of uniform spheres as a function of their volume concentration (1). In 1928, Kenneth S. Cole expanded on Maxwell's model by determining the impedance of a suspension of capacitively coated spheres over a range of frequencies.

Several additional and important developments occurred before the start of World War II. Rudolph Hoebers studied the conductivity of blood and found it to be dependent on the stimulation frequency. Simultaneously, the electrical properties of proteins and amino acids were discovered and extensively studied by Oncley, Fricke, and Wyman (3). These contributions lead to further developments in the science of biophysics and electrophysiology.

Bioimpedance research accelerated after World War II. In 1950, Nyboer et al. launched an investigation into thoracic electrical bioimpedance (TEB) as an alternative to invasive methods of measuring cardiac function and published a novel method termed "Impedance Plethysmography" (4,5). However, Kubicek and Patterson were credited with the development of the original TEB system in conjunction with the National Aeronautics and Space Administration in the mid-1960s (6). This device was designed to monitor stroke volume (SV) and cardiac output (CO) noninvasively during space flight. In addition, Djordjevich and Sadove coined the term "electrohemodynamics" in 1981 to describe a science that relates the theories of fluid mechanics and elasticity to the continuous impedance signal and to the time variations of arterial blood pressure (7). Jan Baan et al. introduced the impedance or conductance catheter technique to measure real time chamber volume in the mid-1980s (8). This technique revolutionized the study of cardiovascular mechanics in both the laboratory and clinical settings by making the study of ventricular-pressure volume relationships practical.

More recently, bioimpedance applications have continued to expand, especially in the area of implantable devices. Modern pacemakers and defibrillators routinely use biompedance measurements to verify pacing lead performance and position, monitor minute ventilation and thoracic fluid content, and optimize programmable device features such as pacing rate and AV delay in a closed-loop fashion (9–11).

The terms bioimpedance or tissue impedance describe both the resistive and reactive components of tissue at the applied stimulus frequency. The capacitive reactive components of the measured tissue impedance change at higher frequencies due to the relative conductive properties of tissue fluids and cellular membranes. Bioimpedance methods can be categorized into two areas: impedance plethysmography and impedance cardiography. Impedance plethysmography, by definition, refers to the measurement of a volume change in a heterogeneous tissue segment using electrical impedance in which the changing impedance waveform (ΔZ) is used to determine cardiac, respiration, and peripheral volume change as a function of time. In contrast, impedance cardiography is a subdivison of impedance plethysmography that focuses on the measurement of cardiac stroke volume and widely uses the first derivative (dZ/dt) of the changing impedance waveform (ΔZ) to monitor fiducial time element points such as cardiac valve opening and closing. Both methods primarily use a single low frequency stimulus current ($<$100 kHz) where most of the elements in the current paths are primarily resistive. Techniques such as impedance plethysmography and impedance cardiography primarily depend on resistive rather than reactive components of the blood impedance. Thus, applications using low frequency stimulus current to primarily measure the resistive component of bioimpedance will be categorized in this article as resistive applications of bioimpedance.

The second general category of bioimpedance measurement involves estimation of fluid volume distributions such as intracellular and extracellular volume, percent body fat vs. percent muscle mass, and cell and tissue viability. This area primarily employs a multifrequency stimulus current bandwidth ($>$1000 Hz) where most of the elements in the current path contain significant resistive and reactive components. Thus, applications using high frequency stimulus current to measure the resistive and reactive components of bioimpedance will be categorized as reactive applications of bioimpedance.

Bioimpedance Theory

When constant electric current is applied between two electrodes through a biological medium and the corresponding voltage is measured between the two source poles, the resultant impedance or bioimpedance is determined by Ohm's law. The recorded voltage is the sum of the potential difference contributions due to the electrical conductivity properties of the tissue medium. The exchange of electrons from source to sink occurs from electrons of the metal electrode (such as platinum or silver-silver chloride) to ions of the tissue medium. The electrode is the site of charge carrier exchange between electrons and ions and thus serves as a transducer of electrical energy. Impedance measurements most commonly use a two-electrode (bipolar) or four-electrode (tetrapolar) arrangement (Fig. 1). In the bipolar arrangement, the electrodes serve as both the current source (anode and cathode, respectively) and as the measurement electrodes. In the tetrapolar arrangement, one electrode serves as current source anode, one as the current source cathode, and the remaining two electrodes serve as the respective measurement electrodes. A disadvantage of the bipolar electrode system is electrode polarization due to a frequency-dependent polarization impedance. Therefore,



Figure 1. Bipolar (left) and tetrapolar (right) electrode configurations. With a constant current stimulation source, the change in measured voltage (ΔV) is proportional to the change in calculated impedance (ΔZ). Tetrapolar systems require additional electrodes but avoid electrode polarization effects.

the measured voltage in a bipolar impedance system reflects the combined impedance of both the tissue segment and the electrode tissue interface. When the voltage is measured with an isolated high input impedance electrode system, such as with the tetrapolar lead configuration, minimal current flows in the isolated sensing electrodes, thus problems with electrode polarization can be effectively reduced (12).

Endogenic ionic current movement between and within cellular structures encompasses the electrical properties of tissues and the term bioelectricity. In tissue and the living cell, an inseparable alliance exists between electricity and chemistry (1). The perception of current through human tissue is dependent on frequency, current density, effective electrode area, and current duration. The maximum sensitivity of the nervous system is approximately in the range of 10 to 1000 Hz for sine waves. At frequencies greater than 1 kHz, the sensitivity is strongly reduced.

Measured bioimpedance is a function of the real and reactive components of the tissue medium at the applied frequency of the stimulus current. Tissue characteristics at low frequencies are almost independent of cellular membrane reactance and internal intracellular resistivity. Thus, most of the applied current is conducted via the extracellular fluid. The cellular membrane behavior at intermediate or high frequencies is primarily a characteristic of membrane reactance and internal resistivity. The membranes are an impure reactance and, therefore, show a dielectric loss and a phase angle, which is independent of frequency (13). At higher frequencies, the cell's membrane reactance and resistance become negligible and the applied current is conducted through both the intracellular and extracellular fluid.

RESISTIVE APPLICATIONS OF BIOIMPEDANCE

Transthoracic Bioimpedance

The Cylindrical Model. Many applications of bioimpedance measurement focus on primarily resistive changes. These techniques are all based on the cylindrical model (Fig. 2) represented by a tissue volume with uniform cross-sectional area (A), length (L), and resistivity (ρ) (14).

$$R = \rho \frac{L}{A} \tag{1}$$

The resistance of the vessel segment is directly proportional to the resistivity of the conductive medium and length of the vessel segment and inversely proportional to the cross-sectional area of the vessel segment (Eq. 1). As shown in Fig. 2, as the cross-sectional area of the vessel segment increases from A_1 to A_3, the measured resistance decreases. Resistivity (ρ) is a tissue property that varies substantially between tissues. Typical tissue resistivities are shown in Table 1 (15).

Equation 1 can be modified to determine the volume of the tissue by multiplying both sides of the equation by L, substituting impedance (Z) for resistance, and solving for volume (V) as a function of time (Eq. 2):

$$V(t) = \rho \frac{L^2}{Z(t)} \tag{2}$$



Figure 2. Cylindrical model of a vessel segment. A_1–A_3 represent cross-sectional area changes of the tissue of the interest (e.g., blood). Tissue length (L) is often determined by measurement electrode spacing. Blood resistivity (ρ) also determines the resistance (R) of the tissue volume. Resistance measured is directly proportional to the measured voltage and indirectly proportional to the constant alternating current (i) applied to the vessel segment.

The cylindrical model is based on several important assumptions: The electrical field, and hence current density, is homogeneous within the tissue of interest, the current is completely confined to the tissue of interest, and the values shown in Table 1 do not account for tissue anisotropy. Most biological tissues have lower resistivity in the longitudinal direction of cell or fiber orientation (12,16–18). For example, the ratio of resistivity in the transverse to parallel direction can be > 3 in cardiac tissue (18). These assumptions may not be valid for some applications of bioimpedance such as the conductance catheter technique for chamber volume estimation (see below). Therefore, the

Table 1. Various Tissue Resistivities in ohms-meter ($\Omega \cdot m$) (15)

Tissue	ρ ($\Omega \cdot m$)
Blood (Hematocrit = 45)	1.6
Plasma	0.7
Heart Muscle (Longitudinal)	2.5
Heart Muscle (Transverse)	5.6
Skeletal Muscle (Longitudinal)	1.9
Skeletal Muscle (Transverse)	13.2
Lung	21.7
Fat	25



Figure 3. Parallel-column model of the thoracic cavity. This two-column model (C_{TC} and C_{BV}) represents a thoracic cavity segment of length (L), cross-sectional areas of the great blood vessels (A_{BV}), and thoracic cavity segment (A_{TC}), and resistivities of the thoracic cavity segment tissues (ρ_{TC}) and blood volume (ρ_{BV}).

cylindrical model must be adjusted for particular applications.

The Parallel-Column Model. The parallel-column model, first described by Nyboer (5) (Fig. 3) is closely related to the cylindrical model, but accounts for current leakage into surrounding tissues. The model consists of a smaller cylindrical conductor (C_{BV}) of length L representing the large blood vessels of the thoracic cavity (i.e., aortic and pulmonary arteries) embedded in a larger cylindrical conductor (C_{TC}) of the same length (L) representing the tissues of the thoracic cavity. C_{BV} consists of blood with specific resistivity (ρ_{BV}) and time-varying cross-sectional area (A_{BV}). C_{TC} is assumed to be heterogeneous (i.e., bone, fat, muscle) with specific resistivity (ρ_{TC}) and constant cross-sectional area (A_{TC}). Thus, the cylindrical model of the time-varying volume can be modified:

$$V_T(t) = \rho_{RV}\frac{L^2}{Z_{BV}(t)} + \rho_{TC}\frac{L^2}{Z_{TC}} \tag{3}$$

where $V_T(t)$ represents the total volume change. As the distribution of the measured resistance and the net resistivity of the parallel tissues are unknown, calculation of absolute volume can be problematic. However, the constant volume term drops out when the change in volume is calculated from Eq. 3:

$$\Delta V_{BV}(t) \cong \rho_{BV}\left(\frac{L^2}{Z_0^2}\right)\bullet \Delta Z(t) \tag{4}$$

where Z_0 is the basal impedance measured and $\Delta Z(t)$ is the pulsatile thoracic impedance change. Thus, Eq. 4 links the parallel cylindrical model to TEB estimates of stroke volume (ΔV_{BV}).

Noninvasive Measurement of Cardiac Output. Transthoracic electrical bioimpedance (TEB) was first introduced by Patterson et al. in 1964 (19). As shown in Fig. 4 (13), this system employs two pairs of band electrodes positioned at the superior and inferior ends of the thorax in the cervical and substernal regions, respectively. The outer electrode pair drives a constant current (I) and the inner electrode pair is used to measure the corresponding voltage (V), which is a function of the varying impedance changes during respiration and the cardiac cycle.



Figure 4. Transthoracic band electrode placement for stroke volume estimates. The two outer-band electrodes supply the stimulus current (I); the two inner electrodes measure the corresponding voltage (V). Impedance is calculated from the ratio of V/I (15).

Noninvasive measurements of stroke volume can be determined with the configuration in Fig. 4 by applying Eq. 5.

$$SV = \left[\rho_{BV}\left(\frac{L^2}{Z_0^2}\right)\bullet \Delta Z(t)\right]\bullet LV_{ET} \tag{5}$$

Cardiac output may then be determined by multiplying stroke volume (SV) by heart rate (HR). $\Delta Z(t)$ is the measured time-varying impedance signal, and Z_0 represents the nonpulsatile basal impedance.

Sramek et al. (20) modified Patterson et al.'s (19) parallel cylinder model into a truncated cone in order to improve stroke volume predictions (Eq. 6). The physical volume of the truncated cone was determined to be one-third the volume of the larger thoracic cylinder model.

$$SV = \left(\frac{(L)^3}{4.2}\right)\bullet LV_{ET}\bullet\left(\frac{(dZ/dt)_{\max}}{Z_0}\right) \tag{6}$$

Sramek et al. (20) also found that in a large normal adult population, the measured linear distance (L) is equal to 17% of body height (cm). Cardiac output is directly proportional to body weight (21). As ideal body weight is a linear function of overall height (22), the proportionality of height (H) to cardiac output can be represented in the first term of Eq. 6 by $(0.17\text{H})^3/4.2$.



Figure 5. Impedance cardiography waveforms. Three waveforms depict the electrocardiogram (ECG), transthoracic impedance change as a function of time (ΔZ), and first-time derivative of the impedance change dZ/dt. Impedance waveforms are intentionally inverted to show a positive deflection during cardiac contraction. Fiducial points on the dZ/dt waveform are represented by the opening of the aortic and pulmonic valves (B), closure of the aortic (X) and pulmonic (Y) valves, mitral valve opening (O), ventricular pre-ejection period (PEP), and left ventricular ejection time (LVET). Q represents the end of atrial contraction (46).

Other empirical modifications to the original model have also been proposed in order to improve CO and SV estimates (20,22–28). In addition, various modifications to the external lead configuration have also been proposed to improve SV estimates, including the application of tranesophageal electrodes (29,30).

Several commercial bioimpedance systems are available for clinical noninvasive estimation of cardiac output and other hemodynamic parameters. The advantages of such systems include noninvasive application, relatively low cost, and lack of noninvasive alternatives. However, these techniques have gained somewhat limited clinical acceptance due to suspect reliability over a wide range of clinical conditions.

A myriad of validation studies of TEB estimates of cardiac output have been published with equivocal results (6,7,19,24,28,31–40). For example, Engoren et al. (35) recently compared cardiac output as determined by bioimpedance, thermodilution, and the Fick method and showed that the three methods were not interchangeable in a heterogenous population of critically ill patients. Their data showed that measurements of cardiac output by thermodilution were significantly greater than by bioimpedance. However, the bioimpedance estimates varied less than the thermodilution estimates for each subject. In contrast, a meta-analysis of impedance cardiography validation trials by Raaijmakers et al. (38) showed an overall correlation between cardiac output measurements using transthoracic electrical bioimpedance cardiography and a reference method of 0.82 (95% CI: 0.80–0.84). The performance of impedance measurement of cardiac output was similar in various groups of patients with different diseases with the exception of cardiac patients, in which group the correlation was decreased. Additional investigations by Kim et al. (41) and Wang et al. (42) used a detailed 3D finite element model of the human thorax to determine the origin of the transthoracic bioimpedance signal. Contrary to the theory that lead to the parallel column model formulae, these investigators determined that the measured impedance signal was determined by multiple tissues and other factors that make reliable estimates of cardiac output over a wide variety of physiological conditions difficult. Nevertheless, commercially available impedance plethysmographs provide estimates of cardiac output that may be useful for assessing relative changes in cardiac function during acute interventions, such as optimization of implantable pacemaker programmable options such as AV delay (11).

Cardiac Cycle Event Detection. TEB also focuses on measurements of the change in impedance (ΔZ) and the impedance first time derivative (dZ/dt) measured simultaneously with the electrocardiogram (ECG). Figure 5 depicts a typical waveform of the aforementioned parameters. Note that the impedance change (ΔZ) and the impedance first time derivative (dZ/dt) are inverted by convention (43). The value of dZ/dt is measured from zero to the most negative point on the waveform. The ejection time (LV_{ET}) is an important parameter in determining stroke volume (Eqs. 5 and 6). This systolic time interval allows an estimation of cardiac contractility. The Heather Index (HI) is another proposed index of contractility from systolic time intervals determined by the dZ/dt waveform (33,44) (Eq. 7):

$$HI = \frac{dZ/dt_{\max}}{\mathrm{Q}Z_1}$$

where $dZ/dt_{\max}$ (point C) is the maximum deflection of the initial waveform derived from the ΔZ waveform and QZ_1 is the time from the beginning of the Q wave to peak $dZ/dt_{\max}$ (Fig. 5). In this figure, point Q represents the time between the end of the ECG p-wave (atrial contraction) and the beginning of the QRS wave (ventricular depolarization) (45). Point B depicts the opening of the aortic and pulmonic valves. After the ventricles depolarize and eject the blood volume into the aortic and pulmonary arteries, points X and Y represent the end systolic component of the cardiac cycle as closure of the aortic and pulmonic valves, respectively.

Passive mitral valve opening and passive ventricular filling begins at point O. Although the timing of the various fiducial notches of the dZ/dt waveform is well known, controversy remains with the origins of the main deflections and are not well understood (15).

Signal Noise. In TEB measurements, several filtering techniques have been proposed to attenuate undesired noise sources depending on which component of the impedance waveform is desired (i.e., respiratory, cardiac, or mean impedance) (47). Most of the signal processing techniques for impedance waves use ensemble averaging for the elimination of motion artifacts (48). A recent signal processing technique described by Wang et al. (48) uses the time-frequency distribution to identify fiducial points on the dZ/dt signal for the computation of left ventricular ejection time and $dZ/dt_{\max}$. As shown in Fig. 5, many of the fiducial points on the dZ/dt waveform are clearly identifiable, but may be somewhat more difficult to observe under severe interference conditions.

Filtering techniques have also been proposed to eliminate noise caused by respiration such as narrow band-pass filtering around the cardiogenic frequency. However, such filtering techniques often eliminate the high frequency components of the cardiac signal and introduce phase distortion (49). To help alleviate this problem, various techniques to identify breathing artifacts with forward and backward filtering have been employed (50,51). Despite these techniques, motion artifact remains with unknown frequency spectra that may overlap the desired impedance frequency spectra during data acquisition. Adaptive filters represent another approach and may eliminate the motion artifact by tracking the dynamic variations and reduce noise uncorrelated to the desired impedance signal (49). Raza et al. (51) developed a method to filter respiration and low frequency movement artifacts from the cardiogenic electrical impedance signal. Based on this technique, the best range for the cutoff frequency appears to be from 30–50% of the heart rate under supine, sitting, and moderate exercise conditions (51).

Applications of Transthoracic Bioimpedance. ***Hypertension.*** TEB has emerged as a noninvasive tool to assess hemodynamic parameters, especially within the framework of hypertension monitoring (24–28,52–54). Measurement of the various hemodynamic components such as stroke volume, ejection time, systemic vascular resistance, aortic blood velocity, thoracic fluid content, and contractility (i.e., Heather Index) using impedance cardiography in patients with hypertension allows more complete characterization of the condition, a greater ability to identify those at highest risk, and allows more effectively targeted drug management (25,53). Several studies have used TEB to evaluate hemodynamic parameters and demonstrated that TEB-guided therapy improves blood pressure control (53,55,56). For example, in a three month clinical study by Taler et al. (55) 104 hypertensive patients were randomized to either TEB-guided therapy or standard therapy. The results showed improved blood pressure control in the TEB-guided group. The investigators concluded that measurement of hemodynamic parameters with TEB methods was more effective than clinical judgment alone in guiding selection of antihypertensive therapies in patients resistant to empiric therapy (53).

Pacemaker Programming. TEB estimates of cardiac index technique has been investigated as a noninvasive method to optimize AV delay intervals in pacemaker patients in an open-loop fashion (57,58). Ovsyshcher et al. (58) measured stroke volume changes at various programmed AV delays via impedance cardiography in dual-chamber pacemaker patients. The optimal and worst programmed AV delays were identified as the settings that produced the highest and lowest cardiac index, respectively. As shown in Fig. 6 (58), the highest cardiac index values resulted with mean AV delays <200 ms and the lowest cardiac index values resulted with mean AV delays >200 ms.

More recently, a study by Tse et al. (59) evaluated AV delay interval optimization during permanent left ventricular pacing using transthoracic impedance cardiography in conjuction with Doppler echocardiography over a range of AV intervals. This study revealed no significant difference between the optimal mean AV delay interval determined by transthoracic impedance cardiography and that determined by Doppler echocardiography. However, as shown in Fig. 7, the mean cardiac output at different AV



Figure 6. Highest and lowest cardiac indices at varied AV delays and pacing rates. Highest cardiac index values (closed circles) resulted with mean AV delays <200 ms and the lowest cardiac index values (open circles) resulted with mean AV delays >200 ms (58).



Figure 7. Cardiac output measured by impedance cardiography and Doppler echocardiography at various AV delay intervals (59).

delay intervals was significantly higher when measured by transthoracic impedance cardiography than when measured by Doppler echocardiography.

Electrical Impedance Tomography. Electrical impedance tomography (EIT) is a technique to reconstruct low resolution cross-sectional images of the body based on differential tissue resistivity (60). The image is created using an array of 16–32 electrodes, usually positioned around the thorax (Fig. 8). Impedance is computed from all electrodes as the drive electrodes rotate sequentially about the tissue surface. The "image" is then reconstructed using standard tomographic techniques. The advantages of EIT include low cost and the potential for ambulatory applications. The disadvantages include the low resolution of the image, the contribution of "out-of-plane" tissues to the "in-plane" image, and the limited clinical applications.

Recent improvements in hardware and software systems that increase the accuracy and speed of regional lung volume change have maintained interest in this technology (60–62). Besides pulmomary monitoring, other potential applications of EIT include neurophysiology, stroke detection, breast cancer detection, gastric emptying, and cryosurgery (63–66).

Lead Field Theory. An analysis of sensitivity is crucial to interpretation and application of EIT images as well as other bioimpedance applications. The sensitivity distribution of an impedance measurement provides the relation between the measured impedance resulting from the conductivity distribution of the measured region. It describes the relative contribution of each region to the measured impedance signal. The contribution of any region to the measurement is not always intuitively obvious and the magnitude of the sensitivity may be less than zero (Fig. 9). Therefore, the relative contribution of various tissues to the reconstructed "image" can be difficult to interpret.



Figure 9. High resolution computer simulated model of the thorax. Regions of both positive and negative sensitivity contribute to the total impedance measured. Negative impedance sensitivity regions, (1.54 Ω) and positive impedance sensitivity regions (red, 2.92 Ω) both contribute to the measure total impedance of 1.38 Ω. RL = contribution of right lung to measured impedance. LR = con-contribution of left lung to measured impedance (62).

The applicability of lead field theory in impedance measurements has been shown theoretically by Geselowitz (67). According to that theory, appropriate selection of the electrode configuration enables increased measurement sensitivity and selectivity to particular regions (68). Also, the measured impedance change (ΔZ) can be evaluated from the change in conductivity within a volume conductor $\Delta\sigma$ and the sensitivity distribution S by (67):

$$\Delta Z = \int_{v} \frac{1}{(\Delta)\sigma} \bullet S_{dv} \tag{8}$$



Figure 8. Left: Cartoon representation of a system to generate an electrical impedance tomographic image: 16 electrodes around the chest inject currents and record the resultant voltage in a sequential manner. Right: Electrical impedance tomographic image of the thoracic cavity. Heart and lung tissue are distinguishable (60).



Figure 10. Simulated measurement sensitivities of tissues. Values are indicated for each tissue type in addition to three tissue groups consisting of pulmonary circulation, systemic circulation, and all the blood masses and heart muscle (68).

The measurement sensitivity S is obtained by first determining the current fields generated by a unit current applied to the current injection electrodes and the voltage measurement electrodes. These two lead fields form the combined sensitivity field of the impedance measurement associated with the electrode configuration by:

$$S = J_{\mathrm{LE}} \bullet J_{\mathrm{LI}} \tag{9}$$

where:

S = the scalar field giving the sensitivity to conductivity changes at each location,

J_{LI} = the lead field produced by current excitation electrodes,

J_{LE} = the lead field produced by voltage measurement leads.

Therefore, sensitivity at each location depends on the angle and magnitude of the two fields and can be positive, negative, or null. The relative magnitude of the sensitivity field in a tissue segment provides a measure of how conductivity variation in that tissue segment will affect the detected ΔZ (69).

Lead field theory suggests that the relative contribution of a tissue to the measured impedance depends on the properties of the tissue, the symmetric arrangement of the tissues, and the geometry of the applied current and voltage electrodes. The precise relative contribution of various tissues to measure impedance is therefore difficult to predict (Fig. 10) (68).

Intrathoracic Bioimpedance

Minute Ventilation. As described earlier, respiratory rate can be estimated with TEB. However, intrathoracic impedance sensing has also been applied to measure respiratory rate and minute ventilation in implantable devices such as pacemakers and implantable cardiac defibrillators (ICDs). Intrathoracic impedance vector configurations typically consist of a tripolar arrangement with bipolar pacing or ICD leads placed in the right ventricle (RV) and the device "can" (metal case or housing) placed subcutaneously in the left or right pectoral region. A variety of anode/cathode electrode arrangements are possible with current source electrodes such as the proximal electrode (RV-ring) to can or the distal electrode (RV-tip) to can and voltage sense electrodes between RV-coil to can. Typically, a low energy pulse of low current amplitude (1 mA with pulse duration of 15 μs) is delivered every 50 milliseconds (10). Figure 11 depicts a typical lead arrangement used for intrathoracic impedance measurements.

The electric fields generated with this electrode configuration must be arranged to intersect in parallel in order to provide the greatest sensitivity. The sensitivity of an electrode is proportional to the current density of the applied stimulus. Moreover, the sensitivity is highest close to the current-injecting electrodes and lowest toward the center of the tissue medium within the lead field vector,



Figure 11. Lead configuration for intracardiac impedance measurments. Stimulus current injected from RV-tip to can. Voltage is measured from RV-Ring to can. The large size of the can reduces electrode polarization effects of the tripolar lead configuration.



Figure 12. Respiratory variation in impedance waveform. Electrocardiogram (ECG) shown with ΔZ waveform. ΔZ waveform is comprised of higher frequency cardiac components superimposed on the lower frequency respiratory variation component (46).

because the applied field current density is lowest in this region.

Experimental evidence indicates that the frequency and amplitude of the respiratory component of the bioimpedance signal are related to changes in both the respiratory rate and the tidal volume and, hence, the minute ventilation (MV). MV sensing in rate-adaptive pacing systems has also been shown to closely correlate with carbon dioxide production (VCO_2) (10). This relationship has been applied in some commercially available pacemakers with automatic rate-adaptive pacing features (9,10).

As shown in Fig. 12 (46), the amplitude of impedance changes during respiration are significantly larger than the higher frequency cardiac components. By magnitude, the change in the cardiac component of the impedance waveform is in the range of 0.1–0.2 Ω, which correlates to approximately 0.3–0.5% of the thoracic impedance (ΔZ) (46). Moreover, each component has a different frequency, typically 1.0–3.0 Hz for cardiac activity and 0.1–1.0 Hz for respiratory activity (9). This differentiation allows extraction of each signal by specific filtering techniques.

In general, the minute-ventilation sensor is characterized by a highly proportional relationship to metabolic demand over a wide variety of exercise types (10). However, optimal performance of impedance-based MV sensors to control pacing rate during exercise often requires careful patient-specific programming.

Fluid Status. Fluid congestion in the pulmonary circulation due to volume overload results in preferential transport of fluid primarily into the extracelluar fluid space and not into the intracellular compartments. Clinical symptoms to assess fluid overload include hypertension, increased weight, pulmonary or peripheral edema, dyspnea, and left ventricular dysfunction. Recently, implantable device-based bioimpedance measurements have been applied to detect thoracic fluid accumulation in patients with congestive heart failure (CHF) and to provide early warning of decompensation caused by factors such as volume overload and pulmonary congestion (32,70,71). This application is the result of a substantial body of new and historical experimental evidence (32,70–73).

Externally measured transthoracic impedance techniques have been shown to reflect alterations in intrathoracic fluid and pulmonary edema in acute animal and human studies (72). The electrical conductivity and the value for transthoracic impedance are determined at any point in time by relative amounts of air and fluid within the thoracic cavity (73). Additional studies have suggested that transthoracic impedance techniques provide an index of the fluid volume in the thorax (32,71). Wang et al. (70) employed a pacing-induced heart failure model to demonstrate that measurement of chronic impedance using an implantable device effectively revealed changes in left ventricular end-diastolic pressure in dogs with pacing-induced cardiomyopathy (Fig. 13) (70). Several factors were identified that may influence intrathoracic impedance with an implantable system, including (*1*) fluid accumulation in the lungs due to pulmonary vascular congestion, pulmonary interstitial congestion, and pulmonary edema; (*2*) as heart failure worsens, heart chamber dilation and venous congestion occur and pleural effusion may develop; and (*3*) after implant, the tissues near the pacemaker pocket swell and surgical trauma can cause fluid buildup (70).

Yu et al. (74) also showed that sudden changes in thoracic impedance predicted eminent hospitalization in 33 patients with severe congestive heart failure (NYHA Class III–IV). During a mean follow-up of 20.7 ± 8.4 months, 10 patients had a total of 25 hospitalizations for worsening heart failure. Measured impedance gradually decreased before admission by an average of $12.3 \pm 5.3\%$ ($p < 0.001$) over a mean duration of 18.3 ± 10.1 days. The decline in impedance also preceded the symptom onset by a mean lead time of 15.3 ± 10.6 days ($p < 0.001$). During hospitalization, impedance was inversely correlated with



Figure 13. Impedance vs. LVEDP during pacing-induced heart failure. Intrathorcic impedance via an implantable device-lead configuration and LVEDP are inversely correlated in a canine model of pacing-induced cardiomyopathy. A general trend for impedance to decrease as heart failure developed is shown. Once pacing induced heart failure was terminated, LVEDP and impedance returned to basal levels (70).

pulmonary wedge pressure (PWP) and volume status with $r = -0.61$ ($p < 0.001$) and $r = -0.70$ ($p < 0.001$), respectively. Automated detection of impedance decreases was 76.9% sensitive in detecting hospitalization for fluid overload with 1.5 false-positive (threshold crossing without hospitalization) detections per patient-year of followup. Thus, intrathoracic impedance from the implanted device correlated well with PWP and fluid status, and may predict eminent hospitalization with a high sensitivity and low false-alarm rate in patients with severe heart failure (Fig. 14) (74). Some commercially available implantable devices for the treatment of CHF or ventricular tachyarrhythmias now continually monitor intrathoracic impedance and display fluid status trends. This information is then provided to the clinician via direct-device interrogation or by remote telemetry.

Volume Conductance Catheter. The conductance catheter technique, first described by Baan et al. (8), enables continuous measurements of chamber volume, particularly left ventricular (LV) volume. This method has been used extensively to assess global systolic and diastolic ventricular function (75). In many respects, the conductance catheter revolutionized the study of cardiovascular mechanics in both the laboratory and clinical settings by making the study of ventricular pressure-volume relationships practical. The technique led to a renaissance of cardiac physiology over the past 25 years (76) by increasing the understanding of the effect of pharmacologic agents, disease states, pacing therapies, and other interventions on cardiovascular function. Conductance catheter systems are available for clinical and laboratory monitoring applications, including a miniature system capable of measuring LV volume and pressure in mice (77).

The conductance methodology is based on the parallel cylinder model (Fig. 3). However, the cylindrical model assumes that the volume of interest has a uniform cross-sectional area across its length. Therefore, the ventricular volume is subdivided into multiple segments determined by equipotential surfaces bounded by multiple sensing electrodes along the axis of the conductance catheter (Fig. 15).



Figure 14. Fluid status monitoring with an implanted device. A: Operation of algorithm for detecting decreases in impedance over time. Differences between measured impedance (bottom; °) and reference impedance (solid line) are accumulated over time to produce fluid index (top). Threshold values are applied to fluid index to detect sustained decreases in impedance, which may be indicative of acutely worsening thoracic congestion. B: Example of impedance reduction before heart failure hospitalization (arrow) for fluid overload and impedance increase during intensive diuresis during hospitalization. Label indicates reference baseline (initial reference impedance value when daily impedance value consistently falls below reference impedance line before hospital admission). Magnitude and duration of impedance reduction are also shown. Days in hospital are shaded (74).



Figure 15. Conductance catheter modeled in the left ventricle (LV). Stimulus current is injected from the proximal and distal catheter electrodes. Voltage is measured between the remaining adjacent electrode pairs. Total conductance is calculated by the summation of all segmental conductances measured in the individual segments.

The two most distal electrodes are used to generate an electric field, typically 0.4 mA p-p, at 20 kHz. The remaining electrodes are used in pairs to measure the conductance of several segments ($n =$ number of segments), which represent the instantaneous volumes of the corresponding segment. The conductance is then converted to volume by modifying Eq. 2:

$$V(t) = \rho L^2 \sum_{i=1}^{n} G_i(t) \tag{10}$$

where G is the time-varying conductance of segment i. However, the conductance technique also violates two other key assumptions of the cylindrical model. First, the electrical field generated by the drive current electrodes is not homogenous and, second, the electric field is not confined to the chamber of interest (i.e., the LV). Thus, the multiple segment cylindrical model has been modified in order to allow conductance catheter estimates of volume to agree with gold standard estimates such as echocardiography (Eq. 11):

$$V(t) = \left(\frac{\rho L^2 \Sigma G(t)}{\alpha}\right) - V_P \tag{11}$$

where correction factor α accounts for nonhomogeneity of the electric field and the correction factor V_P accounts for the current leakage into the surrounding tissues. The terms α and V_p are related and may vary somewhat during the cardiac cycle (16,78). Various methods have been applied to determine the values of α and V_P, including the method of hypertonic saline injection. Recently, the concept of dual-frequency excitation has been applied to estimate V_P for conductance volume measurements in mice (79). This method takes advantage of the relative reactive components of impedance between blood and tissue (80). Despite some theoretical limitations regarding the basic assumptions of field heterogeneity and current leakage, the conductance catheter technique has also been applied to the study of biomechanics in other chambers besides the left ventricle, including the right ventricle (81), right and left atria (82), and aorta (83,84).

Other Pacing Applications. Intracardiac impedance, or transvalvular impedance (TVI), can be used in the assessment of cardiac hemodynamics. This method involves determining the impedance between pacemaker leads in the right atrium and ventricle using a typical dual-chamber pacing configuration. The TVI waveform can be categorized into atrial, valvular, and ventricular components (Fig. 16) (85). Information derived from the atrial component may be useful to identify the loss of electrical capture in the atrium, or the impairment in atrial hemodynamic function associated with supraventricular tachyarrhythmias. The valvular and ventricular components may provide information on the presence, timing, and strength of ventricular mechanical activity (86).

In a study performed by Gasparini et al. (85), the representative TVI tracings (Fig. 16) were recorded from atrial ring to ventricular tip. TVI was measured by application of 64 Hz subthreshold current pulses of 125 μs duration and the amplitude ranging from 15 to 45 μA. The TVI



Figure 16. TVI during spontaneous A-V sequential activity. Fiducial points on the TVI waveform used to optimize A-V delay. t_1 corresponds to the end of atrial systole; t_2 corresponds to the end of ventricular ejection (85).

signal was recorded without high-pass filtering to determine the absolute minimum and maximum impedance in each cardiac cycle, which were assumed to reflect the end-diastolic volume and the end-systolic volume, respectively. TVI may represent a useful approach to determine hemodynamic parameters such as stroke volume, ejection fraction, pre-ejection interval, and atrio-ventricular delay. One significant advantage with this technique is that the source and sense leads are of those typically used in pacing systems and offer the advantage of a high signal-to-noise ratio (86). Moreover, the use of this technique has the potential to differentiate atrial from ventricular function that would be paramount if this technique is used for atrio-ventricular delay optimization (87).

Hematocrit Measurement. Measurement of the resistivity of whole blood has been investigated by a number of researchers, particularly in the area of transthoracic impedance techniques (88–91). A number of investigators have found blood resistivity to be an exponential function of hematocrit (Fig. 17) (15,89–95). These studies have demonstrated a strong correlation between the electrical resistivity of blood at frequencies between 20 to 50 kHz, as the red blood cell is the major resistive component in blood, compared with the relatively conductive plasma. Pop et al. (93) employed a four ring catheter electrode system with narrow electrodes spacing (2 mm center-to-center) to estimate hematocrit in the right atrium of anesthetized pigs. As shown in Fig. 17, good correlation existed between the hematocrit of blood and its electrical resistivity ($r^2 = 0.95$–0.99). Moreover, this study also showed a strong correlation between whole blood viscosity and electrical resistivity.

This interesting observation implies that intracardiac impedance has potential to monitor thrombosis risk in patients with hyperviscosity.

Blood Flow Conductivity Based on Erythrocyte Orientation. The electrical properties of blood are of practical interest in medicine because blood has the highest conductivity of all living tissues (89,96,97). Blood is a heterogeneous suspension of erthrocyctes that have a higher resistivity than the suspending fluid (plasma). The resistivity of blood is a function of the resistivities of plasma, the (fractional) packed-cell volume or hematocrit, and the orientation of the erythrocytes, due to their biconcave shape (98). The orientation of the erythrocytes can be influenced by the viscous forces in flowing blood, resulting in a shear rate-dependent resistivity. In stationary blood, the erythrocytes assume a random distribution while in flowing blood, the plane of the erythrocytes becomes oriented parallel to the axis of flow (99). Thus, minimum resistance occurs when the erythrocytes are oriented in an axial direction, parallel to the stream line. Conversely, maximum resistance occurs when the erythrocytes are oriented in a transverse direction to the stream line (100). The electrical properties of pulsatile blood flow are important when applying transthoracic bioimpedance to estimate cardiac output. In an experiment performed by Katsuyuki et al. (101), erythrocyte orientation, deformation, and axial accumulation caused differences in resistance between flowing and resting blood. Frequency characteristics of blood resistance under pulsatile flow showed that at low pulse rates, the resistance change was minimal, whereas at higher pulse rates, the resistance change increased because the orientation of the erythrocytes cannot follow the rapid changes of pulsatile blood flow. These results suggest that one mechanism of the varying resistance of blood in the aorta during pulsatile blood flow occurs because the orientation of the erythrocyte changes due to shear as a function of heart rate. Therefore, hemodynamic parameters such as cardiac output measured by impedance plethysmography must take into account the anisotropic electrical properties of oriented erythrocytes in blood. Moreover, the resulting resistance of flowing blood depends on the direction of the electrical field applied for impedance measurement and may be affected by the orientation of the erythrocytes during pulsatile flow (101).

REACTIVE APPLICATIONS OF BIOIMPEDANCE

Tissue Impedance

The reactive component of tissue impedance does not contribute significantly to measured impedance when the driving frequency range is less than 1 kHz (8,15). However,



Figure 17. Left figure depicts the correlation between hematocrit of blood and electrical resistivity in five subjects. Right figure depicts a similar correlation between hematocrit of blood and electrical resistivity based on equations by Maxwell–Fricke (upper curve) and Geddes and Sadler (lower curve) (15,93).



Figure 18. Relationship in phase angle and amplitude for tissue electrical properties. This example shows a capacitive tissue segment since the current waveform (I) leads the voltage waveform (V) by phase angle (θ) (103).

at higher driving current frequencies, the reactive component may contribute more substantially. As different tissues have different reactance, different frequencies may be selected for impedance measurement in order to discriminate various tissues (15,102).

Tissue impedance is characterized by four components: the in-phase component of voltage (V) with respect to the current intensity (I), the tissue resistance (R), and the phase angle (θ). The phase angle represents the time delay between the voltage and current intensity waves due to the capacitance of cell membranes (Fig. 18) (103).

Figure 19 shows cellular tissue structure representing alternating current distribution between a bipolar electrode pair at high and low frequencies. The change in polarity that occurs with AC current causes the cell membrane to charge and discharge at the rate of the applied frequency, and the impedance decreases as a function of increased frequency, because the amount of conducting volume increases through intracellular space. At higher frequencies, the rate of cell membrane charge and discharge becomes such that the effect of the cellular membrane on measured impedance becomes insignificant and the current flows through the intracellular and extracellular space (104).

Capacitance causes the voltage to lag behind the current (Fig. 18), creating a phase shift that is quantified as the angular transformation (θ) of the ratio of reactance to resistance (105). Note that the uniform orientation of cells in a tissue (Fig. 19) can result in anisotropy of electrical properties. That is, impedance will be lower in the longitudinal versus transverse direction of the tissue segment cellular structure (12,18).

The parallel-column model (Fig. 3) must be modified to describe higher frequency applications of bioimpedance in which the capacitive properties of the cell membranes become important. The Cole–Cole plot (Fig. 20) is a useful characterization of the three element RC model that describes the behavior of tissue impedance as a function of frequency (f), impedance (Z), resistance (R), reactance (X_C), and phase angle (ϕ) (103). The real components (R_1 and R_2) can be plotted versus the negative imaginary component of the capacitor (C) with reactance (X_C) in the complex series impedance ($R + jX_C$), with the frequency as a parameter where $j = (\sqrt{\ } - 1)$ (15). As the frequency is



Figure 19. Low and high frequency current distribution is a cellular structure. The low frequency stimulus current flows through the highly conductive extracellular space, whereas the high frequency stimulus current flows through both the extracellular and intracellular space once the reactance of the capacitive cellular membrane is reduced.



Figure 20. Cole–Cole plot and equivalent tissue impedance circuit. Resistance (abscissa) and reactance (ordinate) plotted as a function of frequency. A three-element electrical equivalent tissue impedance model is shown. At low frequency (f_L), the equivalent circuit is resistive and $R_0 = R_1 + R_2$. As the frequency increases, the phase angle (ϕ) increases until the resistance and reactance are equal at the characteristic frequency of the tissue (f_C). As the frequency increases beyond the characteristic frequency, the reactive element C is reduced to a low impedance and the tissue displays purely resistive properties where $R_\infty = R_1$. The depressed locus at angle α is presumed to represent electrode polarization.

changed between R_0 and R_∞, the impedance will change continually along a curve in the R-X plane. At very low frequencies (f_L), the capacitive component of the system is effectively an open circuit so the reactance is equal to zero and the measured impedance (Z) is purely resistive (R_0). As the frequency increases, reactance (X_C) increases in proportion to resistance causing the phase angle (ϕ) to increase until a maximum angle is reached at the critical (characteristic) frequency (f_C). As shown in Fig. 20, phase angle is positively associated with reactance and negatively associated with resistance (106). Beyond the critical frequency, the reactance begins to decrease in proportion to resistance with increasing frequency and, at very high frequencies (f_H), the capacitive component is essentially short-circuited so the measured impedance is purely resistive at R_∞ (105).

If impedance of a tissue is measure over a broad spectrum, then the resultant impedance Cole–Cole plot can be fit to the three element model or other similar lumped-parameter models. Changes in the model elements can reflect changes in tissue properties due to pathological conditions such as ischemia (see below). In many biologic systems, the center of loci of the plot lies below the real axis and is represented by the angle α, a fixed number between 0 and 1 (2). This behavior can only be modeled by adding an inductive element to the electrical parameter model shown in Fig. 20. However, the physiological interpretation of the inductance is uncertain. Fricke et al. hypothesized that a possible source of this observed inductance might be electrode polarization (107). These investigations demonstrated behavior similar to constant depression angle of electrode polarization. They demonstrated that a frequency-dependent resistance and reactance could mathematically assume a constant depression angle (2). However, the physiologic explanation for $\alpha > \text{zero}$ remains controversial. An additional theory related to the origin of the depressed loci is the distribution of time constants in a heterogeneous tissue segment. This distribution could result from variability in cell size or variability in properties of the individual cells (2).

Ischemia Detection. Tissue degradation due to ischemia can alter both the real and reactive components of bioimpedance (40). The dielectric polarization of matter (e.g., myocardial tissue) is given by the dimensionless parameter ε', which is called dielectric permittivity. ε' describes the capacitance increase of a capacitor filled with matter:

$$\varepsilon' = \frac{C}{C_0} \tag{12}$$

where:

C = a capacitor with matter (i.e., cellular structure),
C_0 = vacuum capacitor.

As the dielectric polarization processes are frequency-dependent, they show relaxation phenomena with increasing frequency (108). The relaxation process is defined by the complex dielectric permittivity ε, thus:

$$\varepsilon(\omega) = \varepsilon'(\omega) - i\varepsilon''(\omega) \tag{13}$$

where:

ε' = dielectric permittivity,
ε'' = dielectric loss factor,
$\omega = 2\pi f$,
f = frequency of stimulus current,
i = imaginary unit $(\sqrt{-1})$.

The method of dielectric spectroscopy has been proposed to investigate heart tissue during global ischemia, because the dielectric polarization of matter can be measured by the application of weak electric fields. An electrical circuit model to describe myocardial ischemia, initially developed by Gersing (109) and modified by Schaefer et al. (108), is depicted in Fig. 21. This model can be considered as a variation of the simplified three element physiologic model as shown in Fig. 20. The resistance R_{ext} describes the properties of the extracellular electrolyte, and the resistance R_{int} describes the intracellular cytosol. This model assumes that the transcellular current has to pass the membrane with capacitance C_{m} and the resistance R_{m}, through the cytosol, and from cell to cell through the interstitial membranes described by C_{is} or, alternatively, through gap junctions with resistance R_{g} (108,109). Application of this model enables quantification of the variation of intracellular coupling via gap junctions due to myocardial ischemia (108–111).

The measurement of alterations in impedance spectra with ischemia is often referred to as impedance spectroscopy. Myocardial electrical impedance (MEI), a specific application of impedance spectroscopy, has been shown to



Figure 21. Electronic equivalent model of heart tissue. Electrical elements consist of the intracellular (R_{int}) and extracellular resistance (R_{ext}), cellular membrance capacitance (C_m) and resistance (R_m), cell-to-cell interstitial membrane capacitance (C_{is}), and gap junction resistance (R_g).

identify localized and global myocardial tissue in various disease states in *in vitro* and *in vivo* experimental models (112).

Recently, MEI has been used in conjunction with electrocardiogram (ECG) ST-segment deviations to assess the magnitude of the ischemic region of the myocardium (103,112–116).

Injury currents, secondary to myocardial ischemia result in ST-segment displacements in the ECG of patients with myocardial ischemia (117). Injury currents deriving from resting depolarization in ischemic myocardial cells are associated with slow conduction through the myocardium. The mechanisms by which these injury currents correlate with the impedance spectroscopy alterations in the ischemic myocardial tissue are well described (103,108,109,112–117). Figure 22 depicts a segment of the myocardium with subendocardial and transmural ischemic tissue. Blood flow through the heart is interrupted during ischemia, and the tissue undergoes progressive changes leading to irreversible loss of its viability (108). Transmural ischemia causes ST-segment elevation and subendocardial ischemia causes ST-segment depression (117). The electrocardiographic differences between transmural and subendocardial ischemia are clinically important. Supply ischemia, as occurs following total interruption of flow through a coronary artery supplying a large area of the left ventricle, typically causes ST-segment elevation (63). In contrast, demand ischemia, as occurs during a stress test, begins in the subendocardial regions of the left ventricle and causes ST-segment depression (117).



Figure 22. Ischemic regions of myocardial tissue and corresponding ST-segment. Subendocardial ischemia (top) with depressed ST-segment. Transmural ischemia (bottom) with elevated ST-segment (117).

The mechanism by which MEI changes with ischemia is not certain, but may well be associated with ultrastructural changes or cellular biochemical changes that occur in the myocardial tissue similar to those viewed by ST-segment deviations (113). The increase in MEI may result from reductions in the conductive fluid volume in the affected region of the myocardium (113). Gap junctions play a critical role in the propagation of electrical impulse in the heart, and its conductivity has been shown to be reduced and eventually abolished during ischemia and rapidly restored during reperfusion (103). Thus, gap junction closure is a reasonable hypothesis to explain observed impedance changes with ischemia. The intraischemic variation of intracellular and extracellular coupling is one possible explanation for the observed impedance changes of the dielectric frequency spectrum (108).

As MEI correlates with myocardial tissue viability (118,119), the measure has several important potential monitoring applications. Intraoperatively, MEI could be used to detect ischemia in aortic or myocardial tissue during cardiopulmonary bypass surgery as an early indication of damage. Following cardiopulmonary bypass, MEI could be used to assess reperfusion afforded by the new grafts. MEI could also aid in drug titration after cardiac surgery as well as to chronically monitor tissue perfusion with implantable devices such as pacemakers or cardioverter-defibrillators, or with patients whom have received a heart transplant (12,113,120).

In a study performed by Howie et al. (113), acute ischemia was induced in anesthetized dogs via left anterior descending (LAD) coronary artery occlusion for randomly assigned periods of 15, 30, 45, 60, or 120 min. MEI was simultaneously recorded using ventricular pacing leads sutured into the exposed heart tissue. As shown in Fig. 23, MEI increased immediately after LAD coronary artery occlusion and returned to baseline following reperfusion. A statistically significant increase occurred from baseline impedance when compared at 64, 68, 72, 76, and 80 min (113). This intracardiac technique used by Howie et al. suggested other possible applications for MEI with implantable devices and intracardiac pacing/monitoring leads. However, further development in the direction of optimal electrode placement to isolate the targeted tissue region and obtain the highest quality data for diagnosis of tissue alteration is warranted (12).



Figure 23. Change in myocardial impedance during LAD coronary artery occlusion (113).

Dialysis. Whole-body bioimpedance spectroscopy has been proposed by several investigators for measuring extracellular (ECW) and intracellular (ICW) water volumes in dialysis patients in order to assess nutritional status and to monitor hydration (121–125). An adequate assessment of body water compartments is crucial in dialysis patients because overhydration and underhydration are often difficult to detect and may result in severe morbidity in this population (126). Despite the continuous progress in the delivery of renal replacement therapy, mortality in patients on maintenance dialysis remains higher than in the general population (127).

During acute volume overload, most of the extra fluid collects in the ECW not the ICW. At very low frequencies, current only penetrates the ECW because the cell membrane acts as a capacitor and the impedance becomes equal to the ECW resistance (see Fig. 19). At very high frequencies, the injected current penetrates both the ECW and the ICW, and the impedance represents the total body water (TBW) resistance (125). Several investigators (128–131) have used single- and multiple-frequency impedance to monitor fluid shifts during hemodialysis. However, when attempting to determine precise fluid volumes from the measured impedance, difficulties occur due to the complex geometry of the human body and electrical inhomogeneity of nonconducting elements such as bone and fat (125). Signal processing methods to account for these aforementioned difficulties are described in the literature (104,124,125,132).

Whole-body bioelectrical impedance measurements typically apply single (e.g., 50 kHz) (133) or multifrequency (e.g., 5 to 1000 kHz) alternating currents applied via cutaneous electrodes placed on the hands and feet with more proximal electrodes uses for voltage measurements (126). The precise method for calculation of body fluid volumes depends on whether the single-frequency or multiple-frequency method is applied. The single-frequency method often uses an empirically derived regression formula to assess TBW, whereas the multiple-frequency method predicts the volume of TBW and ECW from a general mixture theory, assuming specific resistance values for ECW and ICW (104,126,134). Moreover, the contribution of body weight, which is strongly related to ECW and TBW, is greater in the regression approach compared with the mixture approach (126).

Although reliable measurements of fluid content in dialysis patients have been reported (121–131), uncertainty remains regarding the agreement of whole-body bioimpedance in dialysis patients with tracer dilution techniques, which are considered the gold standard methods (126). One explanation for the lack of satisfactory agreement between techniques is that whole-body bioimpedance techniques consider the body as a multiple conductive cylinder model (e.g., arms, legs, trunk) connected in series (Fig. 24). With conductors connected in series, conductors with the smallest cross-sectional area (e.g., extremities) will determine most of the resistance, whereas the component with the largest cross-sectional area (e.g., trunk) will have minimal contribution to the resistance



Figure 24. Whole-body impedance measurement technique. Total Conductance (C_T) = Left Arm Conductance ($1/R_{LA}$) + Thor-Thoracic Cavity Conductance ($1/R_{TC}$) + Right Leg Conductance ($1/R_{RL}$).

although it contains a significant amount of body water (126). However, assessment of the sum of segmental bioelectrical impedance analysis measurements, which take into account resistance of the extremities and the trunk independently, have been shown to detect changes in trunk water more accurately (135). A seminal study performed by Patterson et al. (136) used multiple linear regression analysis combining data measured independently from the arms, legs, and trunk correlated with weight change on patients undergoing hemodialysis, gave a correlation coefficient of 0.87, whereas the correlation coefficient from measurements between just the wrist and ankle was 0.64.

Pulmonary Edema Detection. Patients developing pulmonary edema initially accumulate fluid in the interstitial spaces of the lung. As the condition progresses, fluid ultimately accumulates in the alveoli. To accurately measure pulmonary fluid status, the different bioelectric properties of blood, lung tissue, and extravascular fluid must be considered, and an impedance parameter not influenced by the patient's geometry should be used (137). Thus, using a dual-frequency measurement of thoracic impedance, an impedance ratio can be calculated that represents the ratio between intracellular and extracellular water. This ratio, therefore, changes as a result of the fluid shift caused by edema formation. As the low frequency current only passes through the extracellular resistance, the measured low frequency impedance (Z_{LF}) over a specified thoracic length equals the total extracellular resistance. As the frequency is increased, current is divided over the intracellular and extracellular compartments. Therefore, the measured high frequency impedance (Z_{HF}) over a specified thoracic length equals the parallel equivalent of intracellular and extracelluar impedance. Thus, a dual-frequency impedance ratio that represents the intracellular/extracellular impedance fraction can be defined by $Z_{\mathrm{HF}}/Z_{\mathrm{LF}}$. As pulmonary fluid accumulates in the extracellular space, the impedance ratio increases (137).

BIBLIOGRAPHY

Cited References

1. Grimnes S, Martinsen O. Bioimpedance and Bioelectricity Basics. London: Academic Press; 2000. p 313–320.
2. Ackmann J, Seitz M. Methods of complex impedance measurements in biologic tissue. CRC Crit Rev Biomed Eng 11(4):281–311.
3. Schwan HP. The bioimpedance field: Some historical observations. Proceedings of the 4th International Conference on Electrical Bioimpedance. 1995; 1–4.
4. Nyboer J, et al. Radiocardiograms: Electrical impedance changes of the heart in relation to electrocardiograms and heart sounds. J Clin Invest 1940; 19:963.
5. Nyboer J. Electrical impedance plethysmography: A physical and physiologic approach to peripheral vascular study. Circulation 1950;2:811–821.
6. Kubicek W, et al. Development and evaluation of an impedance cardiac output system. Aerospace Med 1966;37:1208–1212.
7. Djordjevich L, Sadove M. Basic principles of electrohemodynamics. J Biomed Eng 1981; 3:25–33.
8. Baan J, et al. Continuous measurement of left ventricular volume in animals and humans by conductance catheter. Circulation 1984;70(5):812–823.
9. Min M, Parve T, Kink A. Thoracic impedance as a basis for pacing control. Ann NY Acad Sci 1999;873: 155–166.
10. Ellenbogen K, Wood M. Cardiac Pacing and ICD's. 3rd ed. Malden (MA): Blackwell Science; 2002. p 106–109.
11. Kindermann M, et al. Optimizing the AV delay in DDD pacemaker patients with high degree AV block: Mitral valve doppler versus impedance cardiography. PACE 1997;20(10 pt 1):2453–2462.
12. Steendijk P, et al. The four-electrode resistivity technique in anisotropic media: Theoretical analysis and application on myocardial tissue in vivo. IEEE Trans Biomed Eng 1993;40(11):1138–1147.
13. Nyboer J. Electrorheometric properties of tissues and fluids. Ann NY Acad Sci 1970;170(2):410–420.
14. Geddes LA, Hoff HE. The measurement of physiological events by electrical impedance, a review. Am J Med Electron 1964; 14:16–27.
15. Malmivuo J, Plonsey R. Bioelectromagnetism. In: Principles and Application of Bioelectric and Biomagnetic Fields. United Kingdom: Oxford Univeristy Press; 1995. p 141, 405–419.
16. Hettrick DA, Battocletti JH, Ackmann JJ, Linehan JH, Warltier DC. Effects of physical parameters on the cylindrical model for conductance volume measurement. Ann Biomed Eng 1997;24:126–134.
17. Hettrick D, et al. Finite element model determination of correction factors used for measurement of aortic diameter via conductance. Ann Biomed Eng 1999;27(2): 151–159.
18. Roberts DE, Hersh LT, Scher AM. Influence of cardiac fiber orientation on wavefront voltage, conduction velocity, and tissue resistivity in the dog. Circ Res 1979; 44:701–712.
19. Patterson R, et al. Development of an electrical impedance plethysmography system to monitor cardiac output. Proceedings of the First Annual Rocky Mountain Bioengineering Symposium, 1964: 56–71.
20. Sramek B, Rose D, Miyamoto A. A stroke volume equation with a linear base impedance model and its accuracy, as compared to thermodilution and magnetic flowmeter techniques in humans and animals. Proceedings of the Sixth International Conference on Electrical Bioimpedance, Zadar, Yugoslavia, 1983: 38.
21. Milnor WR. Hemodyanmics. Baltimore: Williams & Wilkins Co.; 1982. p 155.
22. Statistical Bulletin. Metropolitan Life Foundation, January-June 1983. p 64.
23. Quail A, et al. Thoracic resistivity for stroke volume calculation by impedance cardiography. J Appl Physiol 1981;50:191.
24. Albert N, et al. Equivalence of bioimpedance and thermodilution in measuring cardiac output in hospitalized patients with advanced, decompensated chronic heart failure. Am J Crit Care 2004;13:469–479.
25. Van DeWater J, et al. Impedance cardiography: The next vital sign technology? Chest 2003;123: 2028–2033.
26. Drazner M, et al. Comparison of impedance cardiography with invasive hemodynamic measurments in patients with heart failure secondary to ischemic or nonischemic cardiomyopathy. Am J Cardiol 2002;89:993–995.
27. Sageman W, Riffenburgh R, Spiess B. Equivalence of bioimpedance and thermodilution in measuring cardiac index

after cardiac surgery. J Cardiothroracic Vasc Anesth 2002; 16:8–14.

28. Yung G, et al. Comparison of impedance cardiography to direct Fick and thermodilution cardiac output determination in pulmonary arterial hypertension. Congest Heart Fail 2004;10(Suppl 2):7–10.
29. Patterson RP. Possible technique to measure ventricular volume using electrical impedance measurements with an oesophageal electrode. Med Biol Eng Comput 1987;25:677–679.
30. Hettrick DA, et al. Correlation of esophageal conductance measurements with aortic and left ventricular diameters and stroke volume. IEEE Trans Biomed Eng 2000;47:559–564.
31. Patterson R. Handbook of Biomedical Engineering. Bioelectric Impedance Measurements. Boca Raton, FL: CRC Press; 1995. p 1223–1230.
32. Ebert T, et al. The use of thoracic impedance for determining thoracic blood volume changes in man. Aviation Space Environ Med 1986 57:49–53.
33. Mancini R, et al. Cardiac output and contractility indices: Establishing a standard in response to low-to-moderate level exercise in healthy men. Arch Phys Med Rehabil 1979;60:567–573.
34. Levett J, Replogle R. Thermodilution cardiac output: A critical analysis and review of the literature. J Surg Res 1979;27:392–404.
35. Engoren M, Barbee D. Comparison of cardiac output determined by bioimpedance, thermodilution, and the Fick method. Am J Crit Care 2005;14(1):40–45.
36. Imhoff M, Lehner J, Lohlein D. Noninvasive whole-body electrical bioimpedance cardiac output and invasive thermodilution cardiac output in high-risk surgical patients. Crit Care Med 2000;28:2812–2818.
37. Cotter G, et al. Accurate, Noninvasive continuous monitoring of cardiac output by whole body electrical bioimpedance. Chest 2004;125:1431–1440.
38. Raaijmakers E, et al. A meta-analysis of published studies concerning the validity of thoracic impedance cardiography. Ann NY Acad Sci 1999;873: 121–134.
39. Patterson R, Witsoe D. Impedance stroke volume compared with dye and electromagnetic flowmeter values during drug induced inotropic and vascular changes in dogs. Ann NY Acad Sci 1999;873:143–148.
40. Min M, Ollmar S, Gersing E. Electrical impedance and cardiac monitoring: Technology, potential and applications. Int J Bioelectromag 2003;5(1):53–56.
41. Kim D, et al. Origins of the impedance change in impedance cardiography by a three-dimensional finite element model. IEEE Trans Biomed Eng 1988 ;35(12): 993–1000.
42. Wang L, Patterson R. Multiple sources of the impedance cardiogram based on 3-D finite difference human thorax models. IEEE Trans Biomed Eng 1995;42(4): 141–148.
43. Wang X, et al. An impedance cardiography system: A new design. Ann Biomed Eng 1989;17: 535–556.
44. Summers R, Kolb J, Woodward L. Differentiating systolic from diastolic heart failure using impedance cardiography. Academ Emerg Med 1999;6(7):693–699.
45. Lababidi Z, et al. The first derivative thoracic impedance cardiogram. Circulation 1970;41(4): 651–658.
46. Osypka M, Berstein D. Electrophysiologic principles and theory of stroke volume determination by thoracic electrical bioimpedance. Non-invasive monitoring using thoracic bioimpedance. AACN Clin Issues 1999;10(3): 385–399.
47. Christov I. Dynamic powerline interference subtraction from biosignals. J Med Eng Technol 2000;24(4):169–172.
48. Wang X, Sun H, Van DeWater J. An advanced signal processing technique for impedance cardiography. IEEE Trans Biomed Eng 1995;42(2):224–230.
49. Barros A, Yoshizawa M, Yasuda Y. Filtering noncorrelated noise in impedance cardiography. IEEE Trans Biomed Eng 1995;42(3):324–327.
50. Eiken O, Segerhammer P. Elimination of breathing artifacts from impedance cardiograms at rest and during exercise. Med Biol Eng Comput 1988;13–16.
51. Raza S, Patterson R, Wang L. Filtering respiration and low-frequency movement artifacts from the cardiogenic electrical impedance signal. Med Biol Eng Comput 1992; 556–561.
52. Abdelhammed A, et al. Noninvasive hemodynamic profiles in hypertensive subjects. Am J Hypertens 2005;18:51S–59S.
53. Ventura H, Taler S, Strobeck J. Hypertension as a hemodynamic disease: The role of impedance cardiography in diagnostic, prognostic, and therapeutic decision making. Am J Hypertens 2005;18:26S–43S.
54. Alfie J, Galarza C, Waisman G. Noninvasive hemodynamic assessment of the effect of mean arterial pressure on the amplitude of pulse pressure. Am J Hypertens 2005;18:60S–64S.
55. Taler S, Textor S, Augustine J. Resistant hypertension: Comparing hemodynamic management to specialist care. Hypertension 2002;39:982–988.
56. Sharman D, Gomes C, Rutheford J. Improvement in blood pressure control with impedance cardiograph-guided pharmacologic decisions making. Congest Heart Fail 2004;10: 54–58.
57. Eugene M, et al. Assessment of the optimal atrio-ventricular delay in DDD paced patients by impedance plethysmography. Eur Heart J 1989;10:250–255.
58. Ovsyshcher I, et al. Measurements of cardiac output by impedance cardiography in pacemaker patients at rest: Effects of various atrioventricular delays. JACC 1993; 21(3):761–767.
59. Tse H, et al. Impedance cardiography for atrioventricular interval optimization during permanent left ventricular pacing. PACE 2003;26(Pt II):189–191.
60. Wolf GK, Arnold JH. Noninvasive assessment of lung volume: Respiratory inductance plethysmography and electrical impedance tomography. Crit Care Med 2005;33(3): S163–S169.
61. Coulombe N, et al. A parametric model of the relationship between EIT and total lung volume. Physiol Meas 2005;26(4):401–411.
62. Zhang J, Patterson RP. EIT images of ventilation: What contributes to the resistivity changes? Physiol Meas 2005; 26(2):S81–S92.
63. Edd JF, Horowitz L, Rubinsky B. Temperature dependence of tissue impedivity in electrical impedance tomography of cryosurgery. IEEE Trans Biomed Eng 2005;52(4): 695–701.
64. Xiao C, Lei Y. Analytical solutions of electric potential and impedance for a multilayered spherical volume conductor excited by time-harmonic electric current source: Application in brain EIT. Phys Med Biol 2005;750(11): 2663–2674.
65. Clay MT, Ferree TC. Weighted regularization in electrical impedance tomography with applications to acute cerebral stroke. IEEE Trans Med Imag 2002; 21(6):629–637.

66. Zlochiver S, Rosenfeld M, Shimon A. Contactless bio-impedance monitoring technique for brain cryosurgery in a 3D head model. Ann Biomed Eng 2005;33(5):616–625.
67. Geselowitz D. An application of electrocardiographic lead theory to impedance plethysmography. IEEE Trans Biomed Eng 1971;18(1):38–41.
68. Kauppinen P, et al. Application of computer modelling and lead field theory in developing multiple aimed impedance cardiography measurments. J Med Eng Technol 1999;23(5):169–177.
69. Kauppinen P, et al. Lead field theoretical approach in bioimpedance measurements: Towards more controlled measurment sensitivity. Ann NY Acad Sci 1999; 135–142.
70. Wang L, Lahtinen S, Lentz L, et al. Feasibility of using and implantable system to measure thoracic congestion in an ambulatory chronic heart failure canine model. PACE 2005; 28:404–411.
71. Pomerantz M, et al. Transthoracic electrical impedance for the early detection of pulmonary edema. 1969;66:260–268.
72. Fein A, et al. Evaluation of transthoracic electrical impedance in the diagnosis of pulmonary edema. Circulation 1979;60:1156–1160.
73. Gotshall R, Davrath L. Bioelectric impedance as an index of thoracic fluid. Aviation Space Environ Med 1999;70(1):58–61.
74. Yu C, et al. Intrathoracic impedance monitoring in patients with heart failure. Correlation with fluid status and feasibility of early warning preceding hospitalization. Circulation 2005;112:841–848.
75. Steendijk P, et al. Pressure-volume measurements by conductance catheter during cardiac resynchronization therapy. Eur Heart J Suppl 2004;6(Suppl D): D35–D42.
76. Baan J, Van der Velde E, Steendijk P. Ventricular pressure-volume relations in vivo. Eur Heart J 1992;13(Suppl E):2–6.
77. Segers P, et al. Conductance catheter based assessment of arterial input impedance, arterial function, and ventricular-vascular interaction in mice. Am J Physiol Heart Circu Physiol 2005;288:H1157–H1164.
78. Szwarc RS, Laurent D, Allegrini PR, Ball HA. Conductance catheter measurement of left ventricular volume: evidence for nonlinearity within cardiac cycle. Am J Physiol 1995;268: H1490–H1498.
79. Georgakopoulus D, Kass DA. Estimation of parallel conductance by dual-frequency conductance catheter in mice. Am J Physiol Heart Circu Physiol 2000;279:H443–H450.
80. Gawne TJ, Gray KS, Goldstein RE. Estimating left ventricular offset volume using dual frequency conductance catheters. J Appl Physiol 1987;63:872–876.
81. Nicolosi AC, Hettrick DA, Warltier DC. Assessment of right ventricular function in swine using sonomicrometry and conductance. Ann Thorac Surg 1996;61:1281–1387.
82. Schwartzman D, et al. Atrial pacing lead location alters left atrial-ventricular mechanical coupling relationships independent of AV delay in humans: A dual-chamber pressure-volume analysis. Heart Rhythm 2005;2:S85.
83. Hettrick DA, et al. In vivo measurement of real time aortic segmental volume using the conductance catheter. Ann Biomed Eng 1998;26:431–440.
84. Kornet L, et al. Conductance method for the measurement of cross-sectional areas of the aorta. Ann Biomed Eng 1999;27:141–150.
85. Gasparini G, et al. Rate-responsive pacing regulated by cardiac hemodynamics. Europace 2005; 7:234–241.
86. Di Gregorio F, et al. Transvalvular impedance (TVI) recording under electrical and pharmacological cardiac stimulation. PACE 1996;19(Pt.II):1689–1693.
87. Salo R. Application of impedance volume measurement to implantable devices. Int J Bioelectromagn 2003;5(1): 57–60.
88. Fricke H, Morse S. The electrical resistance and capacity of blood for frequencies between 800 and 4.5 MHz. J Gen Physiol 1926;9:153–167.
89. Geddes L, Sadler C. The specific resistance of blood at body temperature. IEEE Trans Biomed Eng 1973;20: 336–339.
90. Hill D, Thompson F. The effect of hematocrit on the resistivity of human blood at 37 degrees celsius and 100 kHz. Med Biol Eng 1975;March:182–186.
91. Mohapatra S, Costeloe K, Hill D. Blood resistivity and its implications for the calculation of cardiac output by the thoracic electrical impedance technique. Intens Care Med 1977;3:63–67.
92. Fuller H. The electrical impedance of plasma: A laboratory simulation of the effect of changes in chemistry. Ann Biomed Eng 1991;19:123–129.
93. Pop G, et al. Catheter based impedance measurements in the right atrium for continuously monitoring hematocrit and estimating blood viscosity changes. An in vivo feasibility study in swine. Biosens Bioelectron 2004;19:1685–1693.
94. Geddes L, Sadler C. The specific resistance of blood at body temperature. Med Biol Eng 1973;11(5):336–339.
95. Fricke H. A mathematical treatment of the electric conductivity and capacity of disperse systems. Physiol Rev 1924;4:575–587.
96. Sigman E, Kolin A, Katz L. Effect of motion on the electrical conductivity of blood. Am J Physiol 1937;118:708.
97. Gollan F, Namon R. Electrical impedance of pulsatile blood flow in rigid tubes and in isolated organs. Ann NY Acad Sci 1970;170(2):568–576.
98. Visser K. Electric properties of flowing blood and impedance cardiography. Ann Biomed Eng 1989;17: 463–473.
99. Peura R, et al. Influence of erythrocyte velocity on impedance plethysmographic measurements. Med Biol Eng Comput 1978;16:147–154.
100. Tanaka K, et al. The impedance of blood: The effects of red cell orientation and its application. Japan J Med Electron Biol Eng 1970;8:14–21.
101. Katsuyuki S, Hiroshi K. Electrical characteristics of flowing blood. IEEE Trans Biomed Eng 1979;26(12):686–695.
102. Lozano A, Rossell J, Pallas-Areny R. Two frequency impedance plethysmograph: Real and imaginary parts. Med Biol Eng Comput 1990;28(1):38–42.
103. Padilla F, et al. Protection afforded by ischemic preconditioning is not mediated by effects on cell-to-cell electrical coupling during myocardial ischemia reperfusion. Am J Heart Circ Physiol 2003;285:H1909–H1916.
104. De Lorenzo A, et al. Predicting body cell mass with bioimpedance by using theoretical methods: A technological review. J Appl Physiol 1997;82(5):1542–1558.
105. Baumgartner R, Chumlea W, Roche A. Bioelectric impedance phase angle and body composition. Am J Clin Nutr 1988; 48:16–23.
106. Barnett A, Bango S. The physiological mechanisms involved in the clinical measure of phase angle. Am J Physiol 1936; 114:366–382.
107. Fricke H. The theory of electrolyte polarization. Phil Mag 1932;14:310.
108. Schaefer M, et al. The complex dielectric spectrum of heart tissue during ischemia. Bioelectrochemistry 2002;58:171–180.

109. Gersing E. Impedance spectroscopy on living tissue for determination of the state of organs. Bioelectrochem Bioenerget 1998;45:145–149.
110. Owens L, et al. Correlation of ischemia-induced extracellular and intracellular ion changes to cell-to-cell electrical uncoupling in isolated blood-perfused rabbit hearts. Circulation 1996;94:10–13.
111. Schafer M, Gebhard Gersing E. Characterization of organ tissue during the transition between life and death: Cardiac and skeletal muscle. Med Biol Eng Comput 1999;37:100–101.
112. Dzwonczyk R, et al. Myocardial electrical impedance responds to ischemia and reperfusion in humans. IEEE Trans Biomed Eng 2004;51(12):2206–2209.
113. Howie M, Dzwonczyk R, McSweeney T. An evaluation of a new two-electrode myocardial electrical impedance monitor for detecting myocardial ischemia. Anesthesia Analgesia 2001;92:12–18.
114. Sezer M, et al. New support for clarifying the relation between ST segment resolution and microvascular function: Degree of ST segment resolution correlates with the pressure derived collateral flow index. Heart 2004;90: 146–150.
115. Leung J, et al. Automated electrocardiograph ST segment trending monitors: Accuracy in detecting myocardial ischemia. Anesthesia Analgesia 1998;87:4–10.
116. Leung J, et al. Electrocardiographic ST-segment changes during acute, severe isovolemic hemodilution in humans. Anesthesiology 2000;93:1004–1010.
117. Katz A. Physiology of the Heart. 2nd ed. New York: Raven Press; 1992. p 609–637.
118. Garrido H, et al. Bioelectrical tissue resistance during various methods of myocardial preservation. Ann Thorac Surg 1983;36:143–151.
119. Gebhard M, et al. Impedance spectroscopy: A method for surveillance of ischemia tolerance of the heart. Thorac Cardiovasc Surg 1987;35:26–32.
120. Mueller J, et al. Electric impedance recording: A noninvasive method of rejection diagnosis. J Extra Corpor Technol 1992;23:49–55.
121. Matthie J, et al. Development of commercial complex bioimpedance spectroscopic system for determining intracellular and extracellular water volumes. Proceedings of the 8th International Conference on Electrical Bioimpedance, Kupio, Finland, 1992. p 203–205.
122. Van Loan M, et al. Use of bioimpednace spectroscopy to determine extracellular fluid, intracellular fluid, total body water, and fat-free mass. In: Human body composition: In vivo methods, models and assessment. New York: Plenum; 1993. p 67–70.
123. Van Marken Lichtenbelt W, et al. Validation of bioelectric impedance measurements as a method to estimate body water compartments. Am J Clin Nutr 1994;60: 159–166.
124. Van Loan M, et al. Fluid changes during pregnancy: Use of bioimpedance spectroscopy. J Appl Physiol 1995;27:152–158.
125. Jaffrin M, et al. Continuous monitoring of plasma, interstitial, and intracellular fluid volumes in dialyzed patients by bioimpedance and hematocrit measurements. ASAIO J 2002;48:326–333.
126. Cox-Reijven P, et al. Role of bioimpedance spectroscopy in assessment of body water compartments in hemodialysis patients. Am J Kidney Dis 2001; 38(4):832–838.
127. Mancini A, et al. Nutritional status in hemodialysis patients and bioimpedance vector analysis. J Renal Nutrition 2003;13(3):199–204.
128. DeVries P, et al. Measurement of transcellular fluid shifts during hemodialysis. Med Biol Eng Comput 1989;27:152–158.
129. Sinning W, et al. Monitoring hemodialysis with bioimpedance: What do we really measure? ASAIO J 1993;39:M584–M589.
130. Scanferla F, et al. On-line bioelectric impedance during hemodialysis: Monitoring of body fluids and cell membrane status. Nephrol Dial Transplant 1990; 5(Suppl 1):167–170.
131. Jaffrin M, et al. Extracellular and intracellular fluid volume during dialysis by multifrequency impedancemetry. ASAIO J 1996;42:M533–M537.
132. Hanai T. Electrical properties of emulsions. In: Emulsions Science. London: Academic Press; 1968. p 354–477.
133. Foley K, et al. Use of single-frequency bioimpedance at 50 kHz to estimate total body water in patients with multiple organ failure and fluid overload. Crit Care Med 1999;27(8):1472–1477.
134. Ward L, Elia M, Cornish B. Potential errors in the application of mixture theory to multifrequency bioelectrical impedance analysis. Physiol Meas 1998;19:53–60.
135. Zhu F, et al. Estimation of body fluid changes during peritoneal dialysis by segmental bioimpedance analysis. Kidney Int 2000;57:299–306.
136. Patterson R, et al. Measurement of body fluid volume change using multisite impedance measurements. Med Biol Eng Comput 1988;26:33–37.
137. Raaijmakers E, et al. Estimation of non-cardiogenic pulmonary edema using dual-frequency electrical impedance. Med Biol Eng Comput 1998;36:461–466.

Further Reading

Cole KS, Cole RH. Dispersion and absorption in dielectrics. J Chem Phys 1941;9:341–351.

See also ELECTROCARDIOGRAPHY, COMPUTERS IN; EXERCISE STRESS TESTING; FLOWMETERS, ELECTROMAGNETIC; IMPEDANCE PLETHYSMOGRAPHY; NEONATAL MONITORING; PHONOCARDIOGRAPHY.

BIOINFORMATICS

ALI ABBAS
LEI LIU
University of Illinois
Urbana, Illinois

INTRODUCTION

The past two decades have witnessed revolutionary changes in biomedical research and biotechnology and an explosive growth of biomedical data. High throughput technologies developed in automated DNA sequencing, functional genomics, proteomics, and metabolomics enable production of such high volume and complex data that the data analysis becomes a big challenge. Consequently, a promising new field, bioinformatics has emerged and is growing rapidly. Combining biological studies with computer science, mathematics, and statistics, bioinformatics develops methods, solutions, and software to discover patterns, generate models, and gain insight knowledge of complex biological systems.



Figure 1. Central dogma of molecular biology.

Before bioinformatics is discussed further, a brief review of the basic concepts in molecular biology, which are the foundations for bioinformatics studies, is provided. The genetic information is coded in DNA sequences. The physical form of a gene is a fragment of DNA. A genome is the complete set of DNA sequences that encode all the genetic information for an organism, which is often organized into one or more chromosomes. The genetic information is decoded through complex molecular machinery inside a cell composed of two major parts, transcription and translation, to produce functional protein and RNA products. These molecular genetic processes can be summarized precisely by the central dogma shown in Fig. 1. The proteins and active RNA molecules combined with other large and small biochemical molecules, organic compounds, and inorganic compounds form the complex dynamic network systems that maintain the living status of a cell. Proteins form complex 3D structures that carry out functions. The 3D structure of a protein is determined by the primary protein sequence and the local environment. The protein sequence is decoded from the DNA sequence of a gene through the genetic codes as shown in Table 1. These codes have been shown to be universal among all living forms on earth.

The high throughput data can be generated at many different levels in the biological system. The genomics data are generated from the genome sequencing that deciphers the complete DNA sequences of all the genetic information in an organism. We can measure the mRNA levels using microarray technology to monitor the gene expression of all the genes in a genome known as transcriptome. Proteome is the complete set of proteins in a cell at a certain stage, which can be measured by high throughput 2D gel electrophoresis and mass spectrometry. We also can monitor all the metabolic compounds in a cell known as metabolome in a high throughput fashion. Many new terms ending with "ome" can be viewed as the complete set of entities in a cell. For example, the "interactome" refers to the complete set of protein-protein interactions in a cell.

Bioinformatics is needed at all levels of high throughput systematic studies to facilitate the data analysis, mining, management, and visualization. But more importantly, the major task is to integrate data from different levels and prior biological knowledge to achieve system-level understanding of biological phenomena. As bioinformatics touches on many areas of biological studies, it is impossible to cover every aspect in a short chapter. In this chapter, the authors will provide a general overview of the field and focus on several key areas, including sequence analysis, phylogenetic analysis, protein structure, genome analysis, microarray analysis, and network analysis.

Sequence analysis often refers to sequence alignment and pattern searching in DNA and protein sequences. This area can be considered classic bioinformatics, which can be dated back to 1960s, long before the word bioinformatics appeared. It deals with the problems such as how to make an optimal alignment between two sequences and how to

Table 1. The Genetic Code

	Second Position				
First Position	T	C	A	G	Third Position
T	TTT Phe [F]	TCT Ser [S]	TAT Tyr [Y]	TGT Cys [C]	T
	TTC Phe [F]	TCC Ser [S]	TAC Tyr [Y]	TGC Cys [C]	C
	TTA Leu [L]	TCA Ser [S]	TAA *Stop*[end]	TGA *Stop*[end]	A
	TTG Leu [L]	TCG Ser [S]	TAG *Stop*[end]	TGG Trp [W]	G
C	CTT Leu [L]	CCT Pro [P]	CAT His [H]	CGT Arg [R]	T
	CTC Leu	CCC Pro [P]	CAC His [H]	CGC Arg [R]	C
	CTA Leu [L]	CCA Pro [P]	CAA Gln [Q]	CGA Arg [R]	A
	CTG Leu [L]	CCG Pro [P]	CAG Gln [Q]	CGG Arg [R]	G
A	ATT Ile [I]	ACT Thr [T]	AAT Asn [N]	AGT Ser [S]	T
	ATC Ile [I]	ACC Thr [T]	AAC Asn [N]	AGC Ser [S]	C
	ATA Ile [I]	ACA Thr [T]	AAA Lys [K]	AGA Arg [R]	A
	ATG Met [M]	ACG Thr [T]	AAG Lys [K]	AGG Arg [R]	G
G	GTT Val [V]	GCT Ala [A]	GAT Asp [D]	GGT Gly [G]	T
	GTC Val [V]	GCC Ala [A]	GAC Asp [D]	GGC Gly [G]	C
	GTA Val [V]	GCA Ala [A]	GAA Glu [E]	GGA Gly [G]	A
	GTG Val [V]	GCG Ala [A]	GAG Glu [E]	GGG Gly [G]	G

```
(a)   Sequence 1   C O U N T I N G
      Sequence 2   N T I G


(b)   Sequence 1   C O U N T I N G   Possible Alignment
      Sequence 2   - - - N T I G -   (Shifting Sequence 2)


(c)   Sequence 1   C O U N T I N G   Possible Alignment
      Sequence 2   - - - N T - I G   (Shifting Sequence 2 and inserting a gap)


(d)   Sequence 1   C O U N T I N G   Possible Alignment
      Sequence 2   - - - N T I - G   (Shifting Sequence 2 and inserting a gap)
```

Figure 2. Possible alignments of two sequences.

search sequence databases quickly with an unknown sequence. Phylogenetic analysis is closely related to sequence alignment. The idea is to use DNA or protein sequence comparison to infer evolution history. The first step in this analysis is to perform multiple sequence alignment. Then, a phylogenetic tree is built based on the multiple alignments. The protein structure analysis involves the prediction of protein secondary and tertiary structures from the primary sequences. So far, the analyses focus on individual sequences or a handful of sequences. The next three areas are involved in system-wide analysis. Genome analysis mainly deals with the sequencing of a complete or partial genome. The problems include genome assembly, gene structure prediction, gene function annotation, and so on. Many techniques of sequence analysis are used in genome analysis, but many new methods were developed for the unique problems. Microarray technologies provide an opportunity for biologists to study the gene expression at a system level. The problems faced in the analysis are completely different from sequence analysis. Many statistical and data mining techniques are applied in the field. Network analysis is another system level study of the biological system. Biological networks can be divided into three categories: metabolic network, protein-protein interaction network, and genetic network. The questions in this area include network modeling, network inference from high throughput data, such as microarray, and network properties study. In the following several sections, the authors will provide a more in-depth discussion of each area.

SEQUENCE ALIGNMENT

Pair-Wise Sequence Alignment

Sequence alignment can be described by the following problem. Given two strings of text, *X* and *Y* (which may be DNA or amino acid sequences), find the optimal way of inserting dashes into the two sequences so as to maximize a given scoring function between them. The scoring function depends on both the length of the regions of consecutive dashes and the pairs of characters that are in the same position when gaps have been inserted. The following example from Abbas and Holmes (1) illustrates the idea of sequence alignment for two strings of text. Consider the two sequences, COUNTING and NTIG, shown in Fig. 2a. Figures 2b, 2c, and 2d show possible alignments obtained by inserting gaps (dashes) at different positions in one of the sequences. Figure 2d shows the alignment with the highest number of matching elements. The optimal alignment between two sequences depends on the scoring function that is used. As shall be shown, an optimal sequence alignment for a given scoring function may not be.

Now that what is meant by an optimal sequence alignment has been discussed, the motivation for doing so must be explained. Sequence alignment algorithms can detect mutations in the genome that lead to genetic disease and also provide a similarity score, which can be used to determine the probability that the sequences are evolutionarily related. Knowledge of evolutionary relation between a newly identified protein sequence and a family of protein sequences in a database may provide the first clues about its 3D structure and chemical function. Furthermore, by aligning families of proteins that have the same function (and may have very different sequences), a common subsequence of amino acids can be observed that is key to its particular function. These subsequences are termed protein motifs. Sequence alignment is also a first step in constructing phylogenetic trees that relate biological families of species.

A dynamic programming approach to sequence alignment was proposed by Needleman and Wunsch (2). The idea behind the dynamic programming approach can be explained using the two sequences, CCGAT and CA-AT, of Fig. 3a. If this alignment is broken into two parts (Fig. 3b),

```
C C G A T      C C G A   T      C C G A T
|     | |      |     | + |      |     | |
C A _ A T      C A _ A   T      C _ A A T

   (a)              (b)              (c)
```

Figure 3. Overview of the dynamic programming approach.

two alignments exist: the left is the alignment of the two sequences CCGA and CA-A, and the right is the alignment of the last elements T-T. If the scoring system is additive, then the score of the alignment of Fig. 3b is the sum of the scores of the four base-alignment on the left plus the score of the alignment of the pair T-T on the right. If the alignment in Fig. 3a is optimal, then the four-base alignment in the left-hand side of Fig. 3b must also be optimal. If this were not the case (e.g., if a better alignment would be obtained by aligning A with G), then the optimal alignment of Fig. 3c would lead to a higher score than the alignment shown in Fig. 3a. The optimal alignment ending at any stage is therefore equal to the total (cumulative) score of the optimal alignment at the previous stage plus the score assigned to the aligned elements at that current stage.

The optimal alignment of two sequences ends with either the last two symbols aligned, the last symbol of one sequence aligned to a gap, or the last symbol of the other sequence aligned to a gap. In the author's analysis, x_i refers to the *i*th symbol in sequence 1 and y_i refers to the *jth* symbol in sequence 2 before any alignment has been made. The authors will use the symbol $S(i,j)$ to refer to the cumulative score of the alignment up until symbols x_i and y_j, and the symbol $s(x_i,y_j)$ to refer to the score assigned to matching elements x_i and y_j. The authors will use d to refer to the cost associated with introducing a gap.

1. If the current stage of the alignment matches two symbols, x_i and y_j, then the score, $S(i,j)$, is equal to the previous score, $S(i{-}1,j{-}1)$, plus the score assigned to aligning the two symbols, $s(x_i,y_j)$.
2. If the current match is between symbol x_i in sequence 1 and a gap in sequence 2, then the new score is equal to the score up until symbol x_{i-1} and the same symbol y_j, $S(i{-}1,j)$, plus the penalty associated with introducing a gap, $-d$
3. If the current match is between symbol y_j in sequence 2 and a gap in sequence 1, then the new score is equal to the previous score up until symbol y_{j-1} and the same symbol x_i, $S(i,j{-}1)$, plus the gap penalty $-d$

The optimal cumulative score at symbols x_i and y_j is:

$$S(i,j) = \max\begin{cases} S(i-1,j-1) + s(x_i,y_j) \\ S(i-1,j) - d \\ S(i,j-1) - d \end{cases}$$

The previous equation determines the new elements at each stage in the alignment by successive iterations from the previous stages. The maximum at any stage may not be unique. The optimal sequence alignment (s) is the one that provides the highest score, which is usually performed using a matrix representation, where the cells in the matrix are assigned an optimal score, and the optimal alignment is determined by a process called trace back (3,4).

The optimal alignment between two sequences depends on the scoring function that is used, which brings the need for a score that is biologically significant and relevant to the phenomenon being analyzed. Substitution matrices present one method of achieving this alignment using a "log-odds" scoring system. One of the first substitution matrices used to score amino acid sequences was developed by Dayhoff et al. (5). Other matrices such as the BLOSUM50 matrix (6) were also developed and use databases of more distantly related proteins.

The Needleman–Wunsch (N–W) algorithm and its variation (3) provide the best *global* alignment for two given sequences. Smith and Waterman (7) presented another dynamic programming algorithm that deals with finding the best *local* alignment for smaller subsequences of two given sequences rather than the best global alignment of the two sequences. The local alignment algorithm identifies a pair of subsegments, one from each of the given sequences, such that no other pair of subsegments exist with greater similarity.

Heuristic Alignment Methods

Heuristic search methods for sequence alignment have gained popularity and extensive use in practice because of the complexity and large number of calculations in the dynamic programming approach. Heuristic approaches search for local alignments of subsegments and use these alignments as "seeds" in which to extend out to longer sequences. The most widely used heuristic search method available today is BLAST (Basic Local Alignment Search Tool) by Altschul et al. (8). BLAST alignments define a measure of similarity called MSP (Maximal Segment Pair) as the highest scoring pair of identical length subsegments from two sequences. The lengths of the subsegments are chosen to maximize the MSP score.

Multiple Sequence Alignments

Multiple sequence alignments are alignments of more than two sequences. The inclusion of additional sequences can improve the accuracy of the alignment, find protein motifs, identify related protein sequences in a database, and predict protein secondary structure. Multiple sequence alignments are also the first step in constructing phylogenetic trees.

The most common approach for multiple alignments is progressive alignment, which involves choosing two sequences and performing a pairwise alignment of the first to the second. The third sequence is then aligned to the first and the process is repeated until all the sequences are aligned. The score of the multiple alignment is the sum of scores of the pairwise alignments. Pairwise dynamic programming can be generalized to perform multiple alignments using the progressive alignment approach; however, it is computationally impractical even when only a few sequences are involved (9). The sensitivity of progressive alignment was improved for divergent protein sequences using CLUSTAL-W (10) (available at http://clustalw.genome.ad.jp/).

Many other approaches to sequence alignment have been proposed in the literature. For example, a Bayesian approach was suggested for adaptive sequence alignments (11,12). The data that is now available from the human genome project has suggested the need for aligning whole genome sequences where large-scale changes can be studied as opposed to single-gene insertions, deletions, and nucleotide substitutions. MuMMer (12) follows this direction and performs alignments and comparisons of very large sequences.

PHYLOGENETIC TREES

Biologists have long built trees to classify species based on morphological data. The main objectives of phylogenetic tree studies are (*1*) to reconstruct the genealogical ties between organisms and (*2*) to estimate the time of divergence between organisms since they last shared a common ancestor. With the explosion of genetic data in the last few years, tree building has become more popular, where molecular-based phylogenetic studies have been used in many applications, such as the study of gene evolution, population subdivisions, analysis of mating systems, paternity testing, environmental surveillance, and the origins of diseases that have transferred species.

From a mathematical point of view, a phylogenetic tree is a rooted binary tree with labeled leaves. A tree is binary if each vertex has either one or three neighbors. A tree is rooted if a node, R, has been selected and termed the root. A root represents an ancestral sequence from which all other nodes descend. Two important aspects of a phylogenetic tree are its topology and branch length. The topology refers to the branching pattern of the tree, and the branch length is used to represent the time between the splitting events (mutations). Figure 4a shows a rooted binary tree with six leaves. Figure 4b shows all possible distinct rooted topologies for a tree with three leaves.

The data that is used to construct trees is usually in the form of contemporary sequences and is located at the leaves. For this reason, trees are represented with all their leaves "on the ground level" rather than at different levels.

The tree-building analysis consists of two main steps. The first step, estimation, uses the data matrix to produce a tree, $\tilde{T}$, that estimates the unknown tree, T. The second step provides a confidence statement about the estimator $\tilde{T}$, which is often performed by bootstrapping methods.

Tree-building techniques can generally be classified into one of four types: distance-based methods, parsimony methods, maximum likelihood methods, and Bayesian methods. For a detailed discussion of each of these methods, see Li (13).



Figure 4. (a) Rooted tree with six leaves. (b) All possible topologies for three leaves.

Tree-building methods can be compared using several criteria such as accuracy (which method gives the true tree, T, when we know the answer?), consistency (when the number of characters increases to infinity, do the trees provided by the estimator converge to the true tree?), efficiency (how quickly does a method converge to the correct solution as the data size increases?), and robustness (is the method stable when the data does not fulfill the necessary assumptions?). To clarify some of these issues, read Holmes (14), where a geometric analysis of the problem is provided and these issues are further discussed.

The second part of the tree-building analysis is concerned with how close we believe the estimated tree is to the true tree. This analysis builds on a probability distribution on the space of all trees. The difficult part of this problem is that, exponentially, many possible trees exist. A nonparametric approach using a multinomial probability model on the whole set of trees would not be feasible as the number of trees is (2N-3)!!. The Bayesian approach defines parametric priors on the space of trees, and then computes the posterior distribution on the same subset of the set of all trees. This analysis enables confidence statements in a Bayesian sense (15).

PROTEIN FOLDING, SIMULATION, AND STRUCTURE PREDICTION

The main motivation for this study is that the structure of a protein greatly influences its function. Knowledge of protein structure and function can help determine the chemical structure of drugs needed to reverse the symptoms that develop due to its malfunction.

The structure of a molecule consists of atoms connected together by bonds. The bonds in a molecular structure contribute to its overall potential energy. The authors shall neglect all quantum mechanical effects in the following discussion and consider only the elements that contribute largely to the potential energy of a structure [as suggested by Levitt and Lifson (16)].

1. **Pair Bonds:** A bond that exists between atoms physically connected by a bond and separated by a distance b. It is like a spring action where energy is stored above and below an equilibrium distance, b_0. The energy associated with this bond is $U(b) = \frac{1}{2}K_b (b - b_0)^2$, where b_0 can be determined from X rays and K_b can be determined from spectroscopy.
2. **Bond Angles:** This bond exists when an angular deviation from an equilibrium angle, θ_0, occurs between three atoms. The bond angle energy associated with the triplet is $U(\theta) = \frac{1}{2}K_\theta(\theta - \theta_0)^2$.
3. **Torsion Angles:** This bond exists when a torsion angle, ϕ, exists between the first and fourth atoms on the axis of the second and third atoms. The energy associated with this bond is $U(\phi) = K_\phi(1 - \cos(n\phi + \delta))$, where θ is an initial torsion angle.
4. **Nonbonded pairs:** Bonds also exist between atoms that are not physically connected in the structure. These bonds include:

a. Van der Waal forces, which exist between nonbonded pairs and contribute to energy, $U(r) = \varepsilon[(\frac{r_0}{r})^{12} - 2(\frac{r_0}{r})^6]$, r_0 is an equilibrium distance and ε a constant.
b. Electrostatic interactions, which contribute to an energy of $U(r) = \alpha\frac{q_i q_j}{r}$; and
c. Hydrogen bonds, which result from van Der Waals forces and the geometry of the system, and contribute to the potential energy of the structure.

The total potential energy function of a given structure can thus be determined by the knowledge of the precise position of each atom. The three main techniques that are used for protein structure prediction are homology (comparative modeling), fold recognition and threading, and *ab initio* folding.

Homology or Comparative Modeling. Comparative modeling techniques predict the structure of a given protein sequence based on its alignment to one or more protein sequences of known structure in a protein database. The approach uses sequence alignment techniques to establish a correspondence between the known structure "template" and the unknown structure. Protein structures are archived for public use in an Internet-accessible database known as the Protein Data Bank (http://www.rcsb.org/pdb/) (17).

Fold Recognition and Threading. When the two sequences exhibit less similarity, the process of recognizing which folding template to use is more difficult. The first step, in this case, is to choose a structure from a library of templates in the protein databank, called fold recognition. The second step "threads" the given protein sequence into the chosen template. Several computer software programs are available for protein structure prediction using the fold recognition and threading technique such as PROSPECT (18).

Ab Initio (New Fold) Prediction. If no similarities exist with any of the sequences in the database, the *ab initio* prediction method is used. This method is one of the earliest structure prediction methods, and uses energy interaction principles to predict the protein structure (16,19,20). Some of these methods include optimization where the objective is to find a minimum energy structure (a local minimum in the energy landscape has zero forces acting on the atoms and is therefore an equilibrium state).

Monte Carlo sampling is one of the most common techniques for simulating molecular motion. The algorithm starts by choosing an initial structure, *A*, with potential energy, *U*(*A*). A new structure, *B*, is then randomly generated. If the energy of the new structure is less than that of the old structure, the new structure is accepted. If the energy of the new structure is higher than the old structure, then we generate a random number, RAND, from a uniform distribution U(0,1). The new structure is accepted if $e - \frac{\Delta E}{\mathrm{KT}} > RAND$, where $\Delta E = E_B - E_A$ is the difference in energy levels, K is Boltzman's constant, and T is the temperature in kelvins. Otherwise, the new structure is rejected. Another random structure is then generated (either from the new accepted structure or from the old structure if the first one was rejected) and the process is repeated until some termination condition is satisfied (e.g., the maximal number of steps has been achieved).

Another type of analysis uses molecular dynamics uses equations of motion to trace the position of each atom during folding of the protein (21). A single structure is used as a starting point for these calculations. The force acting on each atom is the negative of the gradient of the potential energy at that position. Accelerations, a_i, are related through masses, m_i, to forces, F_i, via Netwon's second law ($F_i = m_i a_i$). At each time step, new positions and velocities of each of the atoms are determined by solving equations of motion using the old positions, old velocities, and old accelerations. Beeman (22) showed that new atomic positions and velocities could be determined by the following equations of motion

$$x(t+\Delta t) = x(t) + v(t)\Delta t + [4a(t) - a(t+\Delta t)]\frac{(\Delta t)^2}{6}$$

$$v(t+\Delta t) = v(t) + [2a(t+\Delta t) + 5a(t) - a(t-\Delta t)]\frac{\Delta t}{6}$$

where $x(t)$ = position of the atom at time t, $v(t)$ = velocity of the atom at time t, $a(t)$ = acceleration at time t, and Δt = time step in the order of 10^{-15} s for the simulation to be accurate.

In 1994, the first large-scale experiment to assess protein structure prediction methods was conducted. This experiment is known as CASP (Critical Assessment of techniques for protein Structure Prediction). The results of this experiment were published in a special issue of *Proteins* in 1995. Further experiments were developed to evaluate the fully automatic web servers for fold recognition. These experiments are known as CAFASP (Critical Assessment of Fully Automated Structure Prediction). For a discussion on the limitations, challenges, and likely future developments on the evaluation of the field of protein folding and structure prediction, the reader is referred to Bourne (23).

GENOME ANALYSIS

Analysis of completely sequenced genomes has been one of the major driving forces for the development of the bioinformatics field. The major challenges in this area include genome assembly, gene prediction, function annotation, promoter region prediction, identification of single nucleotide polymorphism (SNP), and comparative genomics of conserved regions. For a genome project, one must ask several fundamental questions: How can we put the whole genome together from many small pieces of sequences? where are the genes located on a chromosome? and what are other features we can extract from the completed genomes?

Genome Assembly

The first problem is pertaining to the genome mapping and sequence assembly. During the sequencing process, large DNA molecules with millions of base pairs, such as a human chromosome, are broken into smaller fragments (~ 100 kb) and cloned into vector such as bacterial artificial chromosome (BAC). These BAC clones can be tiled together by physical mapping techniques. Individual BACs can be further broken down into smaller random fragments of 1–2 kb. These fragments are sequenced and assembled based on overlapping fragments. With more fragments sequenced, enough overlaps will exist to cover most of the sequence. This method is often referred as "shotgun sequencing". Computer tools were developed to assemble the small random fragments into large contigs based on the overlapping ends among the fragments using similar algorithms as the ones used in the basic sequence alignment. The widely used ones include PHRAP/Consed (24,25) and CAP3 (26). Most of the prokaryotic genomes can be sequenced directly by the shotgun sequencing strategy with special techniques for gap closure. For large genomes, such as the human genome, two strategies exist. One is to assemble large contigs first and then tile together the contigs based on the physical map to form the complete chromosome (27). Another strategy is called Whole Genome Shotgun Sequencing (WGS) strategy, which assemble the genome directly from the shotgun sequencing data in combination with mapping information (28). WGS is a faster strategy to finish a large genome, but the challenge of WGS is how to deal with the large number of repetitive sequences in a genome. Nevertheless, WGS has been successfully used in completing the *Drosophila* and human genomes (29,30).

Genome Annotation

The second problem is related to deciphering the information coded in a genome, which is often called genome annotation. The process includes the prediction of gene structures and other features on a chromosome and the function annotation of the genes. Two basic types of genes exist in a genome: RNA genes and protein encoding genes. RNA genes produce active RNA molecules such as ribosomal RNA, tRNA, and small RNA. The majority of genes in a genome are protein encoding genes. Therefore, the big challenge is how to find the protein encoding region in a genome. The simplest way to search for a protein encoding region is to search for open reading frames (ORF), which is a contiguous set of codons between two stop codons. Six possible reading frames for a given DNA sequence exist, three of which start at the first, second, and third base. The other three reading frames are at the complementary strand. The longest ORFs between the start codon and the stop codon in the same reading frame provide good, but not sufficient, evidence of a protein encoding region. Gene prediction is generally easier and more accurate in prokaryotic than eukaryotic organisms due to the intron/exon structure in eukaryote genes. Computational methods of gene prediction based on the Hidden Markov Model (HMM) have been quite successful, especially in prokaryote genome. These methods involve training a gene model to recognize genes in a particular organism. As a result of the variations in codon usage, a model must be trained for each new genome. In a prokaryote genome, genes are packed densely with relatively short intergenic sequences. The model reads through a sequence with unknown gene composition and find the regions flanked by start and stop codons. The codon composition of a gene is different from that of an intergenic region and can be used as a discriminator for gene prediction. Several software tools, such as GeneMark (31) and Glimmer (32) are widely used HMM methods in prokaryotic genome annotation. Similar ideas are also applied to eucaryote gene prediction. As a result of the intron/exon structure, the model is much more complex with more attention on the boundary of intron and exon. Programs such as GeneScan (33) and GenomeScan (34) are HMM methods for eukaryote gene prediction. Neural network-based methods have also been applied in eukaryote gene prediction, such as Grial (35). Additional information for gene prediction can be found using expressed sequence tags (ESTs), which are the sequences from cDNA libraries. As cDNA is derived from mRNA, a match to an EST is a good indication that the genomic region encodes a gene. Functional annotation of the predicted genes is another major task in genome annotation. This process can be also viewed as gene classification with different functional classification systems such as protein families, metabolic pathways, and gene ontology. The simplest way is to infer annotation from the sequence similarity to a known gene (e.g., BLAST search against a well-annotated protein database such as SWISS-PROT). A better way can be a search against protein family databases [e.g., Pfam (36)], which are built based on profile HMMs. The widely used HMM alignment tools include HMMER (37) and SAM (38). All automated annotation methods can produce mistakes. More accurate and precise annotation requires manual checking and a combination of information from different sources.

Besides the gene structures, other features such as promoters can be better analyzed with a finished genome. In prokaryotic organisms, genes involved in the same pathway are often organized in an operon structure. Finding operons in a finished genome provides information on the gene regulation. For eukaryotic organisms, the completed genomes provide upstream sequences for promoter search and prediction. Promoter prediction and detection has been a very challenging bioinformatics problem. The promoter regions are the binding sites for transcription factors (TF). Promoter prediction is to discover the sequence patterns that are specific for TF binding. Different motif finding algorithms have been applied including scoring matrix method (39), Gibbs sampling (40), and Multiple EM for Motif Elicitation (MEME) (41). The results are not quite satisfactory. Recent studies using comparative genomics methods on the problem have produced some promising results and demonstrated that the promoters are conserved among closely related species (42). In addition, microarray studies can provide additional information for promoter discoveries (see the section on microarray analysis).

Comparative Genomics

With more and more genomes being completely sequenced, comparative analysis becomes increasingly valuable and provides more insights of genome organization and evolution. One comparative analysis is based on the orthologous genes, called clusters of orthologous groups (COG) (43). Two genes from two different organisms are considered orthologous genes if they are believed to come from a common ancestor gene. Another term, paralogous genes, refers to genes in one organism and are related to each other by gene duplication events. In COG, proteins from all completed genomes are compared. All matching proteins in all the organisms are identified and grouped into orthologous groups by speciation and gene duplication events. Related orthologous groups are then clustered to form a COG that includes both orthologs and paralogs. These clusters correspond to classes of functions. Another type of comparative analysis is based on the alignment of the genomes and studies the gene orders and chromosomal rearrangements. A set of orthologous genes that show the same gene order along the chromosomes in two closely related species is called a synteny group. The corresponding region of the chromosomes is called synteny blocks (44). In closely related species, such as mammalian species, the gene orders are highly conserved. The gene orders are changed by chromosomal rearrangements during evolution including the inversion, translocation, fusion, and fission. By comparing completely sequenced genomes, for example, human and mouse genomes, we can reveal the rearrangement events. One challenging problem is to reconstruct the ancestral genome from the multiple genome comparisons and estimate the number and types of the rearrangements (45).

MICROARRAY ANALYSIS

Microarray technologies allow biologists to monitor genome-wide patterns of gene expression in a high throughput fashion. Gene expression refers to the process of transcription. Gene expression for a particular gene can be measured as the fluctuation of the amount of messenger RNA produced from the transcription process of that gene in different conditions or samples.

DNA microarrays are typically composed of thousands of DNA sequences, called probes, fixed to a glass or silicon substrate. The DNA sequences can be long (500–1500 bp) cDNA sequences or shorter (25–70 mer) oligonucleotide sequences. The probes can be deposited with a pin or piezoelectric spray on a glass slide, known as spotted array technology. Oligonucleotide sequences can also be synthesized *in situ* on a silicon chip by photolithographic technology (i.e., Affymetrix GeneChip). Relative quantitative detection of gene expression can be carried out between two samples on one array (spotted array) or by single samples comparing multiple arrays (Affymetrix GeneChip). In spotted array experiments, samples from two sources are labeled with different fluorescent molecules (Cy3 and Cy5) and hybridized together on the same array. The relative fluorescence between each dye on each spot is then recorded and a composite image may be produced. The relative intensities of each channel represent the relative abundance of the RNA or DNA product in each of the two samples. In Affymetrix GeneChip experiments, each sample is labeled with the same dye and hybridized to different arrays. The absolute fluorescent values of each spot may then be scaled and compared with the same spot across arrays. Figure 5 gives an example of a composite image from one spotted array.



Figure 5. An image from a spotted array after laser scanning. Each spot on the image represents a gene and the intensity of a spot reflects the gene expression.

Microarray analyses usually include several steps including: image analysis and data extraction, data quantification and normalization, identification of differentially expressed genes, and knowledge discovery by data mining techniques such as clustering and classification. Image analysis and data extraction is fully automated and mainly carried out using a commercial software package or a freeware depending on the technology platforms. For example, Affymetrix developed a standard data processing procedure and software for its GeneChips (for detailed information, see http://www.affymetrix.com); GenePix is widely used image analysis software for spotted arrays. For the rest of the steps, the detailed procedures may vary depending on the experiment design and goals. We will discuss some of the procedures below.

Statistical Analysis

The purpose of normalization is to adjust for systematic variations, primarily for labeling and hybridization efficiency, so that the true biological variations can be discover as defined by the microarray experiment (46,47). For example, as shown in the self-hybridization scatter plot (Fig. 6) for a two-dye spotted array, variations (dye bias) between dyes is obvious and related to spot intensities. To correct the dye bias, one can apply the following model:

$$\log_2(R/G) \rightarrow \log_2(R/G) - c(A)$$

where R and G are the intensities of the dyes; A is the signal strength ($\log_2(R^*G)/2$); M is the logarithm ratio ($\log_2(R/G)$); $c(A)$ is the locally weighted polynomial regression (LOWESS) fit to the MA plot (48,49).

After correction of systematic variations, we want to determine which genes are significantly changed during the experiment and to assign appropriately adjusted p values to the genes. For each gene, we wish to test the null hypothesis that the gene is not differentially expressed. The P value is the probability of finding a result



Figure 6. Self-hybridization scatter plot. The y axis is the intensity from one dye; the *x* axis is the intensity from the other dye. Each spot is a gene.



Figure 7. Hierarchical clustering of microarry data. Rows are genes. Columns are RNA samples at different time points. Values are the signals (expression levels) that are represented by the color spectrum. Green represents down-regulation whereas red represents up-regulation. The color bars beside the dendrogram show the clusters of genes that exhibit similar expression profiles (patterns). The bars are labeled with letters and description of possible biological processes involving the genes in the clusters. [Reprinted from Eisen et al. (58).]

by chance. If *P* value is less than a cut-off (e.g., 0.05), one would reject the null hypothesis and state that the gene is differentially expressed (50). Analysis of variance (ANOVA) is usually used to model the factors for a particular experiment. For example,

$$\log(m_{ijk}) = \mu + A_i + D_j + V_k + \varepsilon_{ijk}$$

where m_{ijk} is the ratio of intensities from the two dye-labeled samples for a gene; μ is the mean of ratios from all replicates; *A* is the effect of different arrays; *D* is the dye effects; and *V* is the treatment effects (51). Through *F* test, it will be determined if the gene exhibits differential expression between any V_k. For a typical microarray, thousands of genes exist. We need to perform thousands of tests in an experiment at the same time, which introduce the statistical problem of multiple testing and adjustment of *p* value. False discovery rate (FDR) (52) has been commonly adopted for this purpose.

For Affymetrix GeneChips analysis, even though the basic steps are the same as spotted microarrays, because of the difference in technology, different statistical methods were developed. Besides the statistical methods provided by Affymetrix, several popular methods are packaged into software such as dChip (53) and RMA (54) in Bioconductor (http://www.bioconductor.org). With rapid accumulation of microarray data, one challenging problem is how to compare microarray data across different technology platforms. Some recent studies on data agreements have provided some guidance (55–57).

Clustering and Classification

Once a list of significant genes is obtained from the statistical test, different data mining techniques would be applied to find interesting patterns. At this step, the microarray dataset is organized as a matrix. Each column represents a condition; each row represents a gene. An entry is the expression level of the gene under the corresponding condition. If a set of genes exhibit the similar fluctuation under all of the conditions, it may indicate that these genes are co-regulated. One way to discover the co-regulated genes is to cluster genes with similar fluctuation patterns using various clustering algorithm. Hierarchical clustering was the first clustering method applied to the problem (58). The result of hierarchical clustering forms a 2D dendrogram as shown in Fig. 7. The measurement used in the clustering process can be either a similarity, such as Pearson's correlation coefficient, or a distance, such as Euclidian distance.

Many different clustering methods have been applied later on, such as *k* means (59), self-organizing map (60), and support vector machine (61). Another type of microarray study involves classification techniques. For example, we can use the gene expression profile to classify cancer types. Golub et al. (62) first reported using classification techniques to classify two different types of leukemia as shown in Fig. 8. Many commercial software packages (e.g., GeneSpring and Spotfire) offer the use of these algorithms for microarray analyses.

COMPUTATIONAL MODELING AND ANALYSIS OF BIOLOGICAL NETWORKS

The biological system is a complex system involving hundreds of thousands of elements. The interaction among the elements forms an extremely complex network. With the development of high throughput technologies in functional genomics, proteomics, and metabolomics, one can start looking into the system-level mechanisms governing the interactions and properties of biological networks. Network modeling has been used extensively



Figure 8. An example of microarray classification. Genes distinguishing acute myeloid leukemia (AML) and acute lymphoblastic leukemia (ALL). The 50 genes most highly correlated with the ALL-AML class distinction are shown. Each row corresponds to a gene, with the columns corresponding to expression levels in different samples. Expression levels for each gene are normalized across the samples such that the mean is 0 and the SD is 1. The scale indicates SDs above or below the mean. The top panel shows genes highly expressed in ALL, the bottom panel shows genes more highly expressed in AML. [Reprinted from Golub et al. (62).]

in social and economical fields for many years (63). Many methods can be applied to biological network studies.

The cellular system involves complex interactions between proteins, DNA, RNA, and smaller molecules and can be categorized in three broad subsystem, metabolic network or pathway, protein network, and genetic or gene regulatory network. *Metabolic network* represents the enzymatic processes within the cell, which provide energy and building blocks for cells. It is formed by the combination of a substrate with an enzyme in a biosynthesis or degradation reaction. Considerable information about metabolic reactions has been accumulated through many years and organized into large databases, such as KEGG (64), EcoCyc (65), and WIT (66). *Protein network* refers to the signaling networks where the basic reaction is between two proteins. Protein-protein interactions can be determined systematically using techniques such as yeast two-hybrid system (67) or derived from the text mining of literatures (68). *Genetic network or regulatory network* refers to the functional inference of direct causal gene interactions (69). One can conceptualize gene expression as a genetic feedback network. The network can be inferred from the gene expression data generated from microarray or proteomics studies in combination with computation modeling.

Metabolic network is typically represented as a graph with the vertex being all the compounds (substrates) and the edges being reactions linking the substrates. With such representation, one can study the general properties of the metabolic network. It has been shown that metabolic network exhibits typical property of small world or scale-free network (70,71). The distribution of compound connectivity follows a power law as shown in Fig. 9. Nodes serving as hubs exist in the network. Such property makes the network quite robust to random deletion of nodes, but vulnerable to selected deletion of nodes. For example, deletion of hub nodes will cause the network collapse very quickly. A recent study also shows that the metabolic network can be organized in modules based on the connectivity. The connectivity is high within modules, but low between modules (72).

Flux analysis is another important aspect in metabolic network study. Building on the stoichiometric network analysis, which only uses the well-characterized network topology, the concept of elementary flux modes was introduced (73,74). An elementary mode is a minimal set of enzymes that could operate at steady state, with the



Figure 9. a. In the scale-free network, most nodes have only a few links, but a few nodes, called hubs (filled circle), have a very large number of links. b. The network connectivity can be characterized by the probability, $P(k)$, that a node has k links. $P(k)$ for a scale-free network has no well-defined peak, and for large k, it decays as a power-law, $P(k) \approx k^{-\gamma}$, appearing as a straight line with slope $-\gamma$ on a log–log plot. [Reprinted from Jeong et al. (70).]

enzymes weighted by the relative flux they need to carry out the mode to function. The total number of elementary modes for given conditions has been used as a quantitative measure of network flexibility and as an estimate of fault-tolerance (75,76).

A system approach to model regulatory networks is essential to understand their dynamics. Recently, several high-level models have been proposed for the regulatory network including Boolean models, continuous systems of coupled differential equations, and probabilistic models. *Boolean networks* assume that a protein or a gene can be in one of two states, active or inactive, represented by 1 or 0. This binary state varies in time and depends on the state of the other genes and proteins in the network through a discrete equation:

$$X_i(t+1) = F_i[X_1(t), \ldots, X_N(t)] \tag{4}$$

Thus, the function F_i is a Boolean function for the update of the ith element as a function of the state of the network at time t (69). Figure 10 gives a simple example.

Gene expression patterns contain much of the state information of the genetic network and can be measured experimentally. We are facing the challenge of inferring or reverse engineering the internal structure of this genetic network from measurements of its output. Genes with similar temporal expression patterns may share common genetic control processes and may, therefore, be related functionally. Clustering gene expression patterns according to a similarity or distance measure is the first step toward constructing a wiring diagram for a genetic network (78).

Differential equations can be an alternative model to the Boolean network and applied when the state variables X are continuous and satisfy a system of differential equations of the form

$$\frac{dX_i}{dt} = F_i[X_1(t), \ldots, X_N(t), I(t)]$$

where the vector $I(t)$ represents some external input into the system. The variable X_i can be interpreted as representing concentrations of proteins or mRNAs. Such a model has been used to model biochemical reactions in the metabolic pathways and gene regulation (69).

Bayesian networks are provided by the theory of graphical models in statistics. The basic idea is to approximate a complex multidimensional probability distribution using a product of simpler local probability distributions. Generally, a Bayesian network model is based on a directed acyclic graph (DAG) with N nodes. In genetic network, the nodes may represent genes or proteins and the random variables X_i levels of activity. The parameters of the model are the local conditional distributions of each random variable given the random variables associated with the



(b)

A’= B
B’= A OR C
C’= (A AND B) OR (B AND C) OR (A AND C)

(c)

Input			Output		
A	B	C	A’	B’	C’
0	0	0	0	0	0
0	0	1	0	1	0
0	1	0	1	0	0
0	1	1	1	1	1
1	0	0	0	1	0
1	0	1	0	1	1

Figure 10. Target Boolean network for reverse engineering. (a) The network wiring and (b) logical rules determine (c) the dynamic output. The challenge lies in inferring (a) and (b) from (c). [Reprinted from Liang et al. (77).]

parent nodes

$$P(X_1,\ldots,X_N)=\prod_i P(X_i|X_j : j\in N^-(i)) \tag{4}$$

where $N^-(i)$ denotes all the parents of vertex i. Given a dataset D representing expression levels derived using DNA microarray experiments; it is possible to use learning techniques with heuristic approximation methods to infer the network architecture and parameters. As data from microarray experiments are still limited and insufficient to completely determine a single model, people have developed heuristics for learning classes of models rather than single models, for instance, for a set of co-regulated genes (69). Bayesian networks have recently been shown to combine heterogeneous datasets, for instance, microarray data with functional annotation and mutation data to produce an expert system (79).

In this chapter, some major development in the field of bioinformatics were reviewed and some basic concepts in the field were introduced covering six areas: sequence analysis, phylogenetic analysis, protein structure analysis, genome analysis, microarray analysis, and network analysis. Due to the limited space, some topics have been left out. One such topics is text mining, which uses Natural Language Processing (NLP) techniques to extract information from the vast amount of literature in biological research. Text mining has become an integral part in bioinformatics. With the continuing development and maturing of new technologies in many system-level studies, the way that biological research is conducted is undergoing revolutionary change. Systems biology is becoming a major theme and driving force. The challenges for bioinformatics in the post-genomics era lie on the integration of data and knowledge from heterogeneous sources and system-level modeling and simulation providing molecular mechanism for physiological phenomena.

BIBLIOGRAPHY

Cited References

1. Abbas A, Holmes S. Bioinformatics and management science. Some common tools and techniques. Operations Res 2004; 52(2):165–190.
2. Needleman SB, Wunsch CD. A general method applicable to the search for similarities in amino acid sequence of two proteins. J Mol Biol 1970;48:443–453.
3. Gotoh O. An improved algorithm for matching biological sequences. J Mol Biol 1982;162:705–708.
4. Durbin S, Eddy S, Krogh A, Mitchison G. Biological Sequence Analysis: Probabilistic Models of Proteins and Nucleic Acids. Cambridge, (UK): Cambridge University Press; 1998.
5. Dayhoff MO, Schwartz RM, Orcutt BC. A model of evolutionary change in proteins. Atlas of Protein Sequence and Structure. vol. 5, supplement 3. National Biomedical Research Foundation. Washington, (DC): 1978. p 345–352.
6. Henikoff S, Henikoff JG. Amino acid substitution matrices from protein blocks. Proc Natl Acad Sci USA 1992;89:10915–10919.
7. Smith TF, Waterman MS. Identification of common molecular subsequences. J Mol Biol 1981;147:195–197.
8. Altschul SF, Gish W, Miller W, Myers E, Lipman J. Basic local alignment search tool. J Molec Biol 1990;215:403–410.
9. Lipman JD, Altschul SF, Kececioglu JD. A tool for multiple sequence alignment. Proc Natl Acad Sci 1989;86:4412–4415.
10. Thompson JD, Higgins DG, Gibson TJ. CLUSTAL W: Improving the sensitivity of progressive multiple sequence alignment through sequence weighting, position specific gap penalties and weight matrix choice. Nucleic Acids Res 1994;22: 4673–4680.
11. Lawrence CE, Altschul SF, Boguski MS, Liu JS, Neuwald AN, Wootton J. Detecting subtle sequence signals: A Gibbs sampling strategy for multiple alignment. Science 1993;262:208–214.
12. (a) Delcher et al. 2002. (b) Zhu J, Liu JS, Lawrence CE. Bayesian adaptive sequence alignment algorithms. Bioinformatics 1998; 14:25–39.
13. Li WH. Molecular Evolution. Boston, MA: Sinauer Associates; 1997.
14. Holmes S. Bootstrapping phylogenetic trees. To appear in Statistical Science. Submitted in (2002).
15. Li S, Pearl DK, Doss H. Phylogenetic tree construction using MCMC. J Am Statist Assoc 2000;95:493–503.
16. Levitt M, Lifson S. Refinement of protein confirmations using a macromolecular energy minimization procedure. J Mol Biol 1969;46:269–279.
17. Berman HM, Westbrook J, Feng Z, Gilliland G, Bhat TN, Weissig H, Shindyalov IN, Bourne PE. The protein data bank. Nucleic Acids Res 2000;28:235–242.
18. Xu Y, Xu D. Protein threading using PROSPECT: Design and evaluation. Proteins Structure, Function, and Genetics 2000;40:343–354.
19. Levitt M, Warshel A. Computer simulation of protein folding. Nature 1975;253:694–698.
20. Nemethy G, Scheraga HA. Theoretical determination of sterically allowed conformations of a polypeptide chain by a computer method. Biopolymers 1965;3:155–184.
21. Levitt M. Molecular dynamics of native protein: Computer simulation of the trajectories. J Mol Biol 1983;168:595–620.
22. Beeman D. Some multi-step methods for use in molecular dynamics calculations. J Comput Phys 1976;20:130–139.
23. Bourne PE. CASP and CAFASP experiments and their findings. Methods Biochem Anal 2003;44:501–507.
24. Gordon D, Abajian C, Green P. Consed: A graphical tool for sequence finishing. Genome Res 1998;8(3):195–202.
25. Gordon D, Desmarais C, Green P. Automated finishing with autofinish. Genome Res 2001;11(4):614–625.
26. Huang X, Madan A. CAP3: A DNA sequence assembly program. Genome Res 1999;9(9):868–877.
27. Waterston RH, Lander ES, Sulston JE. On the sequencing of the human genome. Proc Natl Acad Sci USA 2002; 99(6):3712–3716.
28. Myers EW, et al. A whole-genome assembly of Drosophila 2000;287(5461):2196–2204.
29. Adams MD, et al. The genome sequence of Drosophila melanogaster Science 2000;287(5461):2185–2195.
30. Venter JC, et al. The sequence of the human genome. Science 2001;29:1304–1351.
31. Lukashin AV, Borodovsky M. GeneMark.hmm: New solutions for gene finding. Nucleic Acids Res 1998;26(4):1107–1115.
32. Delcher AL, Harmon D, Kasif S, White O, Salzberg SL. Improved microbial gene identification with GLIMMER. Nucleic Acids Res 1999;27(23):4636–4641.
33. Burge C, Karlin S. Prediction of complete gene structures in human genomic DNA. J Mol Biol 1997;268:78–94.
34. Yeh R-F, Lim LP, Burge CB. Computational inference of homologous gene structures in the human genome. Genome Res 2001;11:803–816.

35. Xu Y, Uberbacher CE. Automated gene identification in large-scale genomic sequences. J Comp Biol 1997;4:325–338.
36. Bateman A, Coin L, Durbin R, Finn RD, Hollich V, Griffiths-Jones S, Khanna A, Marshall M, Moxon S, Sonnhammer ELL, Studholme DJ, Yeats C, Eddy SR. The Pfam Protein Families Database. Nucleic Acids Res 2004;32:D138–D141.
37. Eddy S. Profile hidden Markov models. Bioinformatics 1998;14:755–763.
38. Krogh A, Brown M, Mian IS, Juolander K, Haussler D. Hidden Markov models in computational biology applications to protein modeling. J Mol Biol 1994;235: 1501–1531.
39. Stomo GD, Hartzell GW. Identifying protein-binding sites from unaligned DNA fragments. Proc Natl Acad Sci 1989;86:1183–1187.
40. Lawrence CE, Reilly AA. An expectation maximization (EM) algorithm for the identification and characterization of common sites in unaligned biopolymer sequences. Proteins Struct Funct Genet 1990;7:41–51.
41. Bailey LT, Elkan C. Fitting a mixture model by expectation maximization to discover motifs in biopolymers. Proceedings of the Second International Conference on Intelligent Systems for Molecular Biology 1994; 28–36.
42. Kellis M, Birren BW, Lander ES. Proof and evolutionary analysis of ancient genome duplication in the yeast Saccharomyces cerevisiae. Nature 2004;428:617–624.
43. Tatusov RL, Koonin EV, Lipman DJ. A genomic perspective on protein families. Science 1997; 631–637.
44. O'Brien SJ, Menotti-Raymond M, Murphy WJ, Nash WG, Wienberg J, Stanyon R, Copeland NG, Jenkins NA, Womack JE, Graves JAM. The promise of comparative genomics in mammals. Science 1999;286:458–481.
45. Bourque G, Pevzner AP. Genome-scale evolution: Reconstructing gene orders in the ancestral species. Genome Res 2002;12:26–36.
46. Bolstad BM, Irizarry RA, Astrand M, Speed TP. A comparison of normalization methods for high density oligonucleotide array data based on bias and variance. Bioinformatics 2003;19(2):185–193.
47. Bajesy et al. 2005.
48. Yang YH, Dudoit S, Luu P, Lin DM, Peng V, Ngai J, Speed TP. Normalization for cDNA microarray data: A robust composite method addressing single and multiple slide systematic variation. Nucleic Acids Res 2002;30(4):e15.
49. Yang YH, Thorne N. Normalization for two-color cDNA microarray data. Science and statistics: A festschrift for terry speed. In: Goldstein D, ed. IMS Lecture Notes, Monograph Series. Vol. 40; 2003. p 403–418.
50. Smyth GK, Yang YH, Speed TP. Statistical issues in microarray data analysis. In: Brownstein MJ, Khodursky AB, eds. Functional Genomics: Methods and Protocols. Methods in Molecular Biology. vol. 224. Totowa, (NJ): Humana Press; 2003. p 111–136.
51. Kerr M, Churchill G. Analysis of variance for gene expression microarray data. J Comp Biol 2000;7:819–837.
52. Benjamini Y, Hochberg Y. Controlling the false discovery rate: A practical and powerful approach to multiple testing. J Royal Statist Soc B 1995;57(1):289–300.
53. Li C, Wong WH. Model-based analysis of oligonucleotide arrays: Expression index computation and outlier detection. Proc Natl Acad Sci 2001;98:31–36.
54. Bolstad BM, Irizarry RA, Astrand M, Speed TP. A comparison of normalization methods for high density oligonucleotide array data based on bias and variance. Bioinformatics 2003;19(2):185–193.
55. Wang H, He X, Band M, Wilson C, Liu L. A study of inter-lab and inter-platform agreement of DNA microarray data. BMC Genomics 2005;6(1):71.
56. Jarvinen A, Hautaniemi S, Edgren H, Auvinen P, Saarela J, Kallionierni O, Monni O. Are data from different gene expression microarray platforms comparable? Genomics 2004;83: 1164–1168.
57. Culhane AC, Perriere G, Higgins DG. Cross-platform comparison and visualisation of gene expression data using co-inertia analysis. BMC Bioinformatics 2003;4:59.
58. Eisen MB, Spellman PT, Brown PO, Botstein D. Cluster analysis and display of genome-wide expression patterns. Proc Natl Acad Sci USA 1998;95(25):14863–14868.
59. Ben-Dor A, Shamir R, Yakhini Z. Clustering gene expression patterns. J Comp Biol 1999;6(3/4):281–297.
60. Tamayo P, Solni D, Mesirov J, Zhu Q, Kitareewan S, Dmitrovsky E, Lander ES, Golub TR. Interpreting patterns of gene expression with self-organizing maps: Methods and application to hematopoietic differentiation. Proc Natl Acad Sci USA 1999;96(6):2907–2912.
61. Alter O, Brown PO, Bostein D. Singular value decomposition for genome-wide expression data processing and modeling. Proc Natl Acad Sci USA 2000;97(18):10101–10106.
62. Golub TR, Slonim DK, Tamayo P, Huard C, Gaasenbeek M, Mesirov JP, Coller H, Loh ML, Downing JR, Caligiuri MA, Bloomfield CD, Lander ES. Molecular classification of cancer: Class discovery and cass prediction by gene expression monitoring. Science 1999;286:531–537.
63. Sole RV, Ferrer-Cancho R, Montoya JM, Valverde S. Selection, tinkering, and emergence in complex networks. Complexity 2003;8:20–33.
64. Kanehisa M. A database for post-genome analysis. Trends Genet 1997;13:375–376.
65. Keseler IM, Collado-Vides J, Gama-Castro S, Ingraham J, Paley S, Paulsen IT, Peralta-Gil M, Karp PD. EcoCyc: A comprehensive database resource for Escherichia coli. Nucleic Acids Res 2005;33:D334–D337.
66. Overbeek R, Larsen N, Pusch GD, D'Souza M, Selkov E, Kyrpides N, Fonstein M, Maltsev N, Selkov E. WIT: Integrated system for high-throughput genome sequence analysis and metabolic reconstruction. Nucleic Acids Res 2000;28(1): 123–125.
67. Fields S, Song OK. A novel genetic system to detect protein-protein interactions. Nature 1989;340:245–246.
68. Daraselia N, Yuryev A, Egorov S, Novichkova S, Nikitin A, Mazo I. Extraction of human protein interactions from MEDLINE using full-sentence parser. Bioinformatics 2003;19:1–8.
69. Baldi P, Hatfield GW. Microarrays and Gene Expression. Cambridge, (UK): Cambridge University Press; 2001.
70. Jeong H, Tombor B, Albert1 R, Oltvai ZN, Barabási AL. The large-scale organization of metabolic networks. Nature 2000; 407:651–654.
71. Wagner A, Fell DA. The small world inside large metabolic networks. Proc Royal Soc Lond B 2001;268:1803–1810.
72. Guimera R, Nunes Ameral AL. Functional cartography of complex metabolic networks. Nature 2005;433:895–900.
73. Schuster S, Hilgetag C, Woods JH, Fell DA. Reaction routes in biochemical reaction systems: algebraic properties, validated calculation procedure and example from nucleotide metabolism. J Math Biol 2002;45(2):153–181.
74. Schuster S, Fell DA, Dandekar T. A general definition of metabolic pathways useful for systematic organization and analysis of complex metabolic networks. Nature 2000;18: 326–332.
75. Stelling J, Klamt S, Bettenbrock K, Schuster S, Gilles ED. Metabolic network structure determines key aspects of functionality and regulation. Nature 2002;420:190–193.

76. Cakir T, Kirdar B, Ulgen KO. Metabolic pathway analysis of yeast strengthens the bridge between transcriptomics and metabolic networks. Biotechnol Bioeng 2004;86:251–260.
77. Liang S, Fuhrman S, Somogyi R. REVEAL, a general reverse engineering algorithm for inference of genetic network architectures. Pacific Symp Biocomput 1998;3:18–29.
78. Somogyi R, Fuhrman S, Wen X. Genetic network inference in computational models and applications to large-scale gene expression data. Cambridge, (MA): MIT Press; 2001.
79. Troyanskaya OG, Dolinski K, Owen AB, Altman RB, Botstein D. A Bayesian framework for combining heterogeneous data sources for gene function prediction (in Saccharomyces cerevisiae). Proc Natl Acad Sci USA 2003;100: 8348–8353.

Further Reading

Altschul SF, Madden TL, Schaffer AA, Zhang J, Zhang Z, Miller W, Lipman DJ. Gapped BLAST and PSI-BLAST: A new generation of protein database search programs. Nucleic Acids Res 1997;25:3389–3402.

Baldi P, Chauvin Y, Hunkapillar T, McClure M. Hidden Markov models of biological primary sequence information. Proc Natl Acad Sci USA 1994;91:1059–1063.

Baldi P, Brunak S. Bioinformatics: The Machine Learning Approach. 2nd ed. Cambridge, (MA): MIT Press; 2001.

Bork P, Dandekar T, Diaz-Lazcoz Y, Eisenhaber F, Huynen M, Yuan Y. Predicting function: From genes to genomes and back. J Mol Biol 1998;283:707–725.

Bower J, Bolouri H. Computational Modeling of Genetic and Biochemical Networks. Cambridge, (MA): MIT Press; 2001.

Bray N, Dubchak I, Pachter L. AVID: A global alignment program. Genome Res 2003;13(1):97–102.

Brown PO, Botstein D. Exploring the new world of the genome with DNA microarrays. Nature Genetics 1999;21:33–37.

Brudno M, CB Do, Cooper GM, Kim MF, Davydov E, Green ED, Sidow A, Batzoglou A. LAGAN and Multi-LAGAN: efficient tools for large-scale multiple alignment of genomic DNA. Genome Res 2003;13:(4):721–731.

Brudno M, Malde S, Poiakov A, Do C, Couronne O, Dubchak I, Batzoglou A. Glocal alignment: Finding rearrangements during alignment. Bioinformatics Special Issue on the Proceedings of the ISMB 2003;19:54i–62i.

Bryant SH, Altschul SF. Statistics of sequence-structure threading. Curr Opin Structur Biol 1995;5:236–244.

Cohen FE. Protein misfolding and prion diseases. J Mol Biol 1999;293:313–320.

Diaconis P, Holmes S. Random walks on trees and matchings. Electron J Probabil 2002;7:1–17.

Doyle JC. Robustness and dynamics in biological networks. In: The First International Conference on Systems Biology. New York: Japan Science and Technology Corporation, MIT Press; 2000.

Dudoit S, Fridlyand J, Speed TP. Comparison of discrimination methods for the classification of tumors using gene expression data. J Am Statistic Assoc 2002;97:77–87.

Eddy S, Mitchison G, Durbin R. Maximum discrimination hidden Markov models of sequence consensus. J Comput Biol 1995; 2:9–23.

Eddy SR. Non-coding RNA genes and the modern RNA world. Nature Rev Genet 2001;2:919–929.

Efron B, Halloran EE, Holmes S. Bootstrap confidence levels for phylogenetic trees. Proc Natl Acad Sci 1996;93:13429–13434.

Farris JS. The logical basis of phylogenetic analysis. In: Platnick N, Funk V, eds. Advances in Cladistics. vol. 2. 1983. p 7–36.

Fedorov AN, Baldwin TO. Contranslational protein folding. Biol Chem 1997;272(52):32715–32718.

Felsenstein J. Evolutionary trees from DNA sequences: A maximum likelihood approach. J Mol Evol 1981;17(6):368–376.

Felsenstein J. 1993. (Phylogeny Inference Package) version 3.5c. Department of Genetics, University of Washington, Seattle, WA. Available http://evolution.genetics.washington.edu/phylip.html.

Fischer D, Barret C, Bryson K, Elofsson A, Godzik A, Jones D, Karplus KJ, Kelley LA, MacCallum RM, Pawowski K, Rost B, Rychlewski L, Sternberg M. CAFASP-1: Critical assessment of fully automated structure prediction methods. Proteins 1999;3:209–217.

Fitch WM, Margoliash E. Construction of phylogenetic trees. Science 1967;155:279–284.

Foulds LR, Graham RL. The Steiner problem in Phylogeny is NP-complete. Adv Appl Math 1982;3:43–49.

Friedman N, Linial M, Nachman I, Peter D. Using Bayesian networks to analyze expression data. J Comp Bio 2000;7: 601–620.

Gardner M. The Last Recreations. New York: Copernicus-Springer Verlag; 1997.

Geman S, Geman D. Stochastic relaxation, Gibbs distribution and the Bayesian restoration of images. IEEE Trans Pattern Anal Machine Intell 1984;6:721–741.

Gibson KD, Scheraga HA. Revised algorithms for the build-up procedure for predicting protein conformations by energy minimization. J Comp Chem 1987;9:327–355.

Goloboff PA. SPA. 1995. (S)ankoff (P)arsimony (A)nalysis, version 1.1. Computer program distributed by J. M. Carpenter, Department of Entomology, American Museum of Natural History, New York.

Gribaldo S, Cammarano P. The root of the universal tree of life inferred from anciently duplicated genes encoding components of the protein-targeting machinery. J Mol Evol 1998;47(5):508–516.

Haeckel E. Morphologie der Organismen: Allgemeine Grundzuge der Organischen FormenWissenschaft, Mechanisch Begrundet durch die von Charles Darwin Reformirte Descendenz-Theorie. Berlin: Georg Riemer; 1866.

Hannenhalli S, Pevzner PA. Transforming cabbage into turnip: Polynomial algorithm for sorting signed permutations by reversals. STOC 1995; 178–189.

Helden JV, Andre B, Collado-Vides J. Extracting regulatory sites from the upstream region of yeast genes by computational analysis of oligonucleotide frequencies. J Mol Bio 1998;281: 827–842.

Hooper E. The River. Boston, (MA): Little, Brown; 1999.

Huelsenbeck J, Ronquist F. 2002. Mr. Bayes. Bayesian inference of phylogeny. Available at http://morphbank.ebc.uu.se/mrbayes/links.php.

Jukes T, Cantor C. Evolution of protein molecules. In: eds. Munro HN, Mammalian Protein Metabolism. New York: Academic Press; 1969. p 21–132.

Karlin S, Altschul SF. Methods for assessing the statistical significance of molecular sequences features by using general scoring schemes. Proc Natl Acad Sci USA 1990;87(6):2264–2268.

Keith JM, Adams P, Bryant D, Kroese DP, Mitchelson KR, Cochran DAE, Lala GH. A simulated annealing algorithm for finding consensus sequences. Bioinformatics 2002;18: 1494–1499.

Kent WJ. BLAT–the BLAST-like alignment tool. Genome Res 2002;12(4):656–664.

Kirkpatrick S, Gelatt CD Jr, Vecchi MP. Optimization by simulated annealing. Science 1983;220:671–680.

Korf I, Flicek P, Duan D, Brent MR. Integrating genomic homology into gene structure prediction. Bioinformatics 2001;17:S140–S148.

Levitt M. Protein folding by restrained energy minimization and molecular dynamics. J Mol Biol 1983;170:723–764.
Ly DH, Lockhart DJ, Lerner RA, Schultz PG. Mitotic misregulation and human aging. Science 2000;287:1241–1248.
Ma B, Tromp J, Li M. PatternHunter: Faster and more sensitive homology search. Bioinformatics 2002;18:440–445.
Ma B, Wang Z, Zhang K. Alignment between two multiple alignments. In: Combinatorial Pattern Matching: 14th Annual Symposium, CPM 2003, Morelia, Michoacán, Mexico, June 25–27. Lecture Notes in Computer Science, vol. 2676. Heidelberg, Germany: Springer-Verlag; 2003.
Maddison D, Maddison W. 2002. Sinauer. Available at http://phylogeny.arizona.edu/macclade.
McAdams H, Shapiro L. Circuit simulation of genetic networks. Science 1995;269:650–656.
Metropolis N, Rosenbluth A, Rosenbluth M, Teller A, Teller E. Simulated Annealing. J Chem Phys 1953;21:1087–1092.
Mjolsness E, Sharp DH, Rinetz J. A connectionsit model of development. J Theor Biol 1991;152:429–453.
Morales LB, Garduno-Juarez R, Romero D. Applications of simulated annealing to the multiple-minima problem in small peptides. J Biomol Struc Dyn 1991;8:721–735.
Morgenstern B. Dialign2: improvement of the segment-to-segment approach to multiple sequence alignment. Bioinformatics 1999;15:211–218.
Mountain JL, Cavalli-Sforza LL. Inference of human evolution through cladistic analysis of nuclear DNA restriction polymorphisms. Proc Natl Acad Sci USA 1994;91:6515–6519.
Muckstein U, Hofacker IL, Stadler PF. Stochastic pairwise alignments. Bioinformatics 2002;18(sup. 2):S153–S160.
Notredame C, Higgins D, Heringa J. T-Coffee: A novel method for multiple sequence alignments. J Mol Biol 2000;302:205–217.
Peitsch MC. ProMod and Swiss-Model: Internet-based tools for automated comparative protein modeling. Biochem Soc Trans 1996;24:274–279.
Pevzner PA. Computational Molecular Biology, an Algorithmic Approach. Cambridge, (MA): MIT Press; 2000.
Pieper U, Eswar N, Ilyin VA, Stuart A, Sali A. ModBase, a database of annotated comparative protein structure models. Nucleic Acids Res 2002;30:255–259.
Ramachandran GN, Sasisekharan V. Conformation of polypeptides and proteins. Adv Protein Chem 1968;23:283–438.
Rannala B, Yang Z. Probability distribution of molecular evolutionary trees: A new method of phylogenetic inference. J Mol Evol 1996;43:304–311.
Richards FM. The protein folding problem. Sci. Am 1991; January: 54–63.
Saitou N, Nei M. The neighbor-joining method: A new method for reconstructing phylogenetic trees. Mol Biol Evol 1987;4(4): 406–425.
Schlick T. Optimization methods in computational chemistry. In: Reviews in Computational Chemistry, III. New York: VCH Publishers; 1992. p 1–71.
Schmulevich I, Dougherty E, Kim S, Zhang W. Probabilistic Boolean networks: A rule-based uncertainty model for gene regulatory networks. Bioinformatics 2002;18:261–274.
Schröder E. Vier combinatorische probleme. Z Math Phys 1870;15:361–376.
Shannon CE. A mathematical theory of communication. Bell Sys Tech J 1948;27:379–423, 623–656.
Snow ME. Powerful simulated annealing algorithm locates global minima of protein folding potentials from multiple starting conformations. J Comput Chem 1992;13:579–584.
Stanley R. Enumerative Combinatorics. vol. I. 2nd ed. Cambridge (MA): Cambridge University Press; 1996.
Swofford DL. PAUP. Phylogenetic analysis using parsimony. V4.0. Boston, (MA): Sinauer Associates; 2001.
Tozeren A, Byers SW. New Biology for Engineers and Computer Scientists. Englewood Cliffs, (NJ): Prentice Hall; 2003.
Wang LS, Jansen R, Moret B, Raubeson L, Warnow T. Fast phylogenetic methods for the analysis of genome rearrangement data: An empirical study. Proc of 7th Pacific Symposium on Biocomputing, 2002.
Watson JD, Crick FH. A structure for deoxyribose nucleic acid. Nature 1953; April.
White KP, Rifkin SA, Hurban P, Hogness DD. Microanalysis of drosphila development during metamorphosis. Science 1999; 286:2179–2184.
Winkler H. Verbeitung und Ursache der Parthenogenesis im Pflanzen und Tierreiche. Jena: Verlag Fischer; 1920.
Xu J, Hagler A. Review: Chemoinformatics and drug discovery. Molecules 2002;7:566–600.
Yang Z, Rannala B. Bayesian phylogenetic inference using DNA sequences: A Markov chain Monte Carlo method. Mol Biol Evol 1997;14:717–724.

See also COMPUTERS IN THE BIOMEDICAL LABORATORY; DNA SEQUENCE; MEDICAL EDUCATION, COMPUTERS IN; POLYMERASE CHAIN REACTION; STATISTICAL METHODS.

BIOLOGIC THERAPY. See IMMUNOTHERAPY.

BIOMAGNETISM

DOUGLAS CHEYNE
Hospital for Sick Children
Research Institute
JINI VRBA
VSM MedTech Ltd.

INTRODUCTION

The science of *biomagnetism* refers to the measurement of magnetic fields produced by living organisms. These tiny magnetic fields are produced by naturally occurring electric currents resulting from muscle contraction, or signal transmission in the nervous system, or by the magnetization of biological tissue. The first observation of biomagnetic activity in humans was the recording of the magnetic field produced by the electrical activity of the heart, or *magnetocardiogram*, by Baule and McFee in 1963 (1). In 1968, David Cohen (2) at the Massachusetts Institute of Technology reported the first measurement of the alpha rhythm of the human brain, demonstrating that it was possible to measure magnetic fields of biological origin that are only several hundred femtotesla in magnitude (1 femtotesla $= 10^{-15}$ T)—more than 1 million times smaller than the earth's magnetic field ($\sim 5 \times 10^{-5}$ T). These early measurements were achieved using crude instruments consisting of inductance coils of 1–2 million windings in magnetically shielded enclosures and using extensive signal averaging. Instruments with increased sensitivity and performance based on the *superconducting quantum interference device*, or SQUID became available shortly after these pioneering measurements. The SQUID is a highly sensitive magnetic flux detector based on the properties of electrical currents flowing in superconducting circuits, as predicted by Nobel laureate Brian Josephson in 1962 (3). The SQUID was soon adapted for use in biomagnetic measurements (4) and by the early 1970s, measurements of the spontaneous activity of the human heart (5) and brain (6) had been achieved without the need for signal averaging using superconducting sensing coils coupled to SQUIDs immersed in cryogenic vessels containing liquid helium. Thereafter, the field of biomagnetism continued to expand with the further development of SQUID based instrumentation during the 1970s and 1980s. The introduction in 1992 of multichannel biomagnetometers capable of simultaneous measurement of neuromagnetic activity from the entire the human brain (7,8) has resulted in widespread interest in the field of *magnetoencephalography* or *MEG* as a new method of studying human brain function.

Biomagnetic measurements are considered to have a number of advantages over more traditional electrophysiological measurements of heart and brain activity, such as the electrocardiogram or electroencephalogram. One significant advantage is that propagation of magnetic fields through the body is less distorted by the varying conductivities of the overlying tissues in comparison to electrical potentials measured from the surface of the scalp or torso, and can therefore provide a more precise localization of the underlying generators of these signals. In applications such as MEG and magnetocardiography (MCG), these measurements are completely passive and can be made repeatedly without posing any risk or harm to the patient. Also, biomagnetic signals are a more direct measure of the underlying currents in comparison to surface electrical recordings that measure volume conducted activity that must be subtracted from a reference potential at another location complicating the interpretation of the signal. In addition, magnetic measurements from multiple sites can be less time consuming since there is no need to affix electrodes to the surface of the body. As a result, biomagnetic measurements provide an accurate and noninvasive method for locating sources of electrical activity in the human body. The development of multichannel MEG systems has dramatically increased the usefulness of this technology in clinical assessment and treatment of various brain disorders. This has resulted in the recognition of routine clinical procedures by health agencies in the United States for the use of MEG to map sensory areas of the brain or localize the origins of seizure activity prior to surgery. Clinical applications of MCG have also been developed although to a lesser extent than MEG. This includes the assessment of coronary artery disease and other disorders affecting the propagation of electrical signals in the human heart. Another biomagnetic technique, known as *biosusceptometry*, involves measuring magnetized materials in the human body by measuring their moment as they are moved within a strong magnetic field. These measures can provide useful information regarding the concentration of ferromagnetic or strongly paramagnetic materials in various organs of the body, such as iron particles in the lung or iron-containing proteins in the liver. In addition, novel biomagnetometer systems are now available for the assessment of fetal brain and heart function in utero, and may provide a new clinical tool for the assessment of fetal health. Currently, there are >100 multichannel MEG systems worldwide and advanced magnetometer systems specialized for the measurement of magnetic signals from the heart, liver, lung, peripheral nervous system, as well as the fetal heart and fetal brain are currently being commercially developed. Although biomagnetism is still regarded as a relatively new field of science, new applications of biomagnetic measurements in basic research and clinical medicine are rapidly being developed, and may provide novel methods for the assessment and treatment of a variety of biological disorders. The following section reviews the current state of biomagnetic instrumentation and signal processing and its application to the measurement of human biological function.

BIOMAGNETIC INSTRUMENTATION

SQUID Sensors and Electronics

The SQUID sensor is the heart of a biomagnetometer system and provides high sensitivity detection of very small magnetic signals. The most popular types of SQUIDs are direct current (dc) and radio frequency (rf) SQUIDs, deriving their names from the method of their biasing. The modern commercial biomagnetometer instrumentation uses dc SQUIDs implemented in low temperature superconducting materials (usually Nb). In recent years, there has been significant progress in the development of high Tc SQUIDs, both dc and rf. These devices are usually constructed from $YBa_2Cu_3O_{7-x}$ ceramics. However, due to their poorer low frequency performance and difficulties with reproducible large volume manufacturing they are not yet suitable for large-scale applications. An excellent review of SQUID operation can be found in (9).

The rf SQUID was popular in the early days of superconducting magnetometry because they required only one Josephson junction. However, in majority of low Tc commercial applications, the rf SQUIDs have been displaced by dc SQUIDs due to their greater sensitivity, although in recent years, interest in rf SQUIDs has been renewed in connection with high Tc superconductivity. The operation of SQUIDs is illustrated in Fig. 1a. The dc SQUID can be modeled as a superconducting ring interrupted by two resistively shunted Josephson junctions as in Fig. 1a (11). The Josephson junctions are superconducting quantum mechanical devices that allow passage of currents with zero voltage, and when voltage is applied to them, they exhibit oscillations with a frequency to voltage constant of $\sim 484\ \mathrm{MHz} \cdot \mu\mathrm{V}$. The resistive shunting causes the Josephson junctions to work in a nonhysteretic mode, which is necessary for low noise operation (9). An example of a thin-film dc SQUID, consisting of a square washer and Josephson junctions near the outside edge is shown in Fig. 1b (12,13). The usual symbol used to represent a dc SQUID is shown in Fig. 1c.

The SQUID ring (or washer) must be coupled to the external world and to the electronics that operates it (see Fig. 2a). When the dc SQUID is current biased, its I–V characteristics is similar to that of a nonhysteretic Josephson junction and the critical current I_0 is modulated



Figure 1. Thin-film dc SQUID. (a) Schematic diagram indicating inductances of the SQUID ring and shunting resistors to produce nonhysteretic Josephson junctions. (b) Diagram of a simple SQUID washer with Josephson junctions near the outer edge. (c) Symbolic representation of a dc SQUID, where the Josephson junctions are indicated by 'x'. (Reproduced with permission from Ref. 10).

by magnetic flux externally applied to the SQUID ring. The modulation amplitude is roughly equal to Φ_0/L (9), where Φ_0 is the flux quantum with magnitude $\sim 2.07 \times 10^{-15}$ Wb and L is inductance of the SQUID ring. The critical current is maximum for applied flux $\Phi = n\Phi_0$ and minimum for $\Phi = (n + 1/2)\Phi_0$. For monotonically increasing flux the average SQUID voltage oscillates as in Fig. 2d with period equal to 1 Φ_0. The SQUID transfer function is periodic (Fig. 2d) and to linearize it, the SQUID is operated in a feedback loop as a null detector of magnetic flux (14). Most SQUID applications use analogue feedback loop whereby a modulating flux with $\pm 1/4\ \Phi_0$ amplitude is applied to the SQUID sensor through the feedback circuitry (Fig. 2a,b). The modulation, feedback signal, and the flux transformer output are superposed in the SQUID, amplified, and demodulated in a lock-in detector fashion. The demodulated output is integrated, amplified, and fed back as a flux to the SQUID sensor to maintain its total input close to zero. The modulation flux superposed on the dc SQUID transfer function is shown in Fig. 2d and the modulation frequencies are typically several hundreds of kilohertz.

For satisfactory MEG operation, the SQUID system must exhibit large dynamic range, excellent interchannel matching, good linearity, and satisfactory slew rates. The analogue feedback loop is not always adequate and the dynamic range can be extended by implementing digital integrator as shown in Fig. 2c, and by utilizing the flux periodicity of the SQUID transfer function (15). The dynamic range extension works in the following manner: The loop is locked at a certain point on the SQUID transfer function and remains locked for the applied flux in the range of $\pm 1\ \Phi_0$, Fig. 2d. When this range is exceeded, the loop lock is released and the locking point is shifted by 1 Φ_0 along the transfer function. The flux transitions along the transfer function are counted and are merged with the signal from the digital integrator to yield 32 bit dynamic range. This "flux slipping" concept can also be implemented using four-phase modulation (16), where the feedback loop jumps by $\Phi_0/2$ and can also provide compensation for the variation of SQUID inductance with the flux changes.

Flux Transformers

The purpose of flux transformers is to couple the SQUID sensors to the measured signals and to increase the overall magnetic field sensitivity. The flux transformers are superconducting and consist of one or more pickup coil(s) that are exposed to the measured fields. The pickup coil(s) are connected by twisted leads to a coupling coil that inductively couples the measured flux to the SQUID ring (as



Figure 2. Examples of SQUID electronics, where the SQUID is operated as a null detector. (a) SQUID sensor is coupled to an amplifier. (b) Analogue feedback loop. (c) Digital feedback loop using digital signal processor (DSP) or a programmable logic array (PGA). (d) Feedback loop modulation. (Adapted with permission from Ref. 10).



Figure 3. Examples of hardware flux transformers for biomagnetic applications. It is assumed that the scalp surface is at the bottom of the figure, (a) Radial magnetometer; (b) tangential magnetometer; (c) radial first-order gradiometer; (d) planar first-order gradiometer; (e) radial gradiometer for tangential fields; (f) second-order symmetric gradiometer; (g) second-order asymmetric gradiometer; (h) third-order gradiometer. (Reproduced with permission from Ref. 10).

shown in Fig. 2a). Because the flux transformers are superconducting, their gain is noiseless and their response is independent of frequency. The flux transformer pickup coil can have diverse configurations as shown in Fig. 3. A single loop of wire acts as a magnetometer and is sensitive to the magnetic field component perpendicular to its area, Fig. 3a and b. Two magnetometer loops can be combined with opposite orientation and connected by the same wire to the SQUID sensor. The loops are separated by a distance b and such a device is called a first-order gradiometer Fig. 3c–e, and the distance b is referred to as gradiometer baseline. The magnetic fields detected at the two coils are subtracted and the gradiometer acts as a spatial differential detector (this differential action is comparable to differential detection of electric signals (e.g., in electroencephalography, EEG). Fields induced by distant sources will be almost completely canceled by a gradiometer because both its coils will detect similar signals. On the other hand, near sources will produce markedly different fields at the two gradiometer coils and will be detected. Thus the gradiometers diminish the effect of the environmental noise that is typically generated by distant sources while remaining sensitive to near sources (e.g., neural sources). Similarly, first-order gradiometers can be combined with opposing polarity to form second-order gradiometers (Fig. 3f,g) and second-order gradiometers can be combined to form third-order gradiometers, (Fig. 3h). The flux transformers in Fig. 3 are called hardware flux transformers, because they are directly constructed in hardware by interconnecting various coils.

The main types of flux transformers used in commercial practice as the primary sensors are magnetometers (Fig. 3a), radial gradiometers (Fig. 3c), and planar gradiometers (Fig. 3d). These different sensor types will measure different spatial pattern of magnetic flux when placed over a current dipole as shown in Fig. 4. The radial magnetometer produces a field map with one maximum and one minimum, symmetrically located over the dipole with zero field measured directly above the dipole (Fig. 4a). The radial gradiometer in Fig. 4b produces similar field pattern as the magnetometer, except that the pattern is spatially tighter since it subtracts two field patterns measured at different distances from the dipole. The planar gradiometer field patterns are quite different from that of the radial devices. If the two coils of the planar gradiometer are aligned perpendicular to the dipole, as in Fig. 4c, the planar gradiometer exhibits a peak directly above the dipole; if the two coils were aligned parallel to the dipole, the planar gradiometer exhibits a weak, clover-leaf pattern. When two orthogonal planar gradiometers are positioned at the same location, their two independent components can determine orientation of the current dipole located directly under the gradiometers (17).



(a) Magnetometers (b) Radial grads.



(c) Planar grads. (d) Planar grads.

Figure 4. Response to a point dipole of several flux transformer types. A tangential dipole is positioned 2 cm deep in a semi infinite conducting space bounded by $x_3 = 0$ plane and its field is scanned by a flux transformer with its sensing coil positioned at $x_3 = 0$. Dipole position is indicated by a black arrow. Dimensions of each map are 14 × 14 cm. Schematic top view of the flux transformers is shown in the upper part of each figure. Solid and dashed lines indicate different field polarities. (a) Radial magnetometer; (b) radial gradiometer with 4 cm baseline; (c) planar gradiometer with 1.5 cm baseline aligned for maximum response; (d) planar gradiometer with 1.5 cm baseline aligned for minimum response. (Reproduced with permission from Ref. 10).

In the absence of noise, there are no practical differences between these types of flux transformers. However, in the presence of noise, the signal-to-noise ratios (SNR) can differ greatly, resulting in significant performance differences between devices. For MEG applications, the magnitude of both the detected brain signal and environmental noise increases with increasing gradiometer baseline (distance between coils). Since the signal and noise functional dependencies on baseline are different, SNR exhibits a peak corresponding to an optimum baseline of ~3–8 cm for first-order radial gradiometers (10). Magnetometers can be thought of as gradiometers with very long baseline and are not optimal because they can be overly sensitive to environmental noise. Planar gradiometers have good SNR for shallow brain sources but are suboptimal for deeper sources due to their short baselines resulting in poor depth sensitivity. Too long a baseline can also result in greater sensitivity to noise sources arising from the body itself, such as the magnetic field of the heart that may then contaminate the MEG signal. A detailed comparison of gradiometer design and performance can be found in (10).

Noise Cancelation

Introduction. Since biomagnetic measurements must be made in real world settings, the influence of noise on the measurements is a major concern in the design of biomagnetic instrumentation. Environmental noise affects biomagnetometer systems even when they are operated within shielded rooms. Environmental noise results from moving magnetic objects and currents (cars, trains, elevators, power lines, etc.). These noise sources are many orders of magnitude larger than signals of biomagnetic origin as shown in Fig. 5a. Note also, that only SQUID magnetometers have sufficient sensitivity for measuring biomagnetic signals of interest [atomic magnetometers are not yet suitable for biomagnetic applications (19)]. For MEG applications, the resolution or white noise level of the sensors should be much less than the "noise" level of brain activity ($\sim 30\ \mathrm{fT \cdot Hz^{1/2}}$). An example of background brain activity is shown in Fig. 5b. Also, certain MEG signal interpretation methods require the white noise to be as low as possible, however, the noise level cannot be made lower than the contribution of noise from the cryogenic vessel (dewar) itself. As a compromise, the majority of the existing MEG systems exhibit intrinsic noise levels of $<10\ \mathrm{fT \cdot Hz^{1/2}}$ (typically $\sim 5\ \mathrm{fT \cdot Hz^{1/2}}$), yet are able to tolerate unwanted environmental noise many orders of magnitude greater.

Magnetic Shielding. Magnetic shielding is the most straightforward, though most costly method for reduction of environmental noise. A variety of shielded rooms have been used for biomagnetic applications and their relative shielding performance is shown in Fig. 6. The simplest shielding is accomplished through eddy currents by using a thick layer of high conductivity metal (20). Eddy current shielding is not effective at low frequencies, and therefore shielded rooms utilize high permeability μ-metal, which depending on the number of layers, can provide attenuation in the range from ~ 30 to $\sim 10^5$ (21–24). Low frequency attenuation of nearly 10^8 was demonstrated with a whole-body, high Tc superconducting shield (25).

Environmental noise can also be reduced by active shielding, which can be employed either in unshielded environments (26), or in combination with shielded rooms (24,27,28). Active shielding system consists of a reference magnetometer, feedback electronics, and a set of compensating coils. The references measure the environmental noise and provide a signal that is amplified and fed into the



Figure 5. Environmental and brain generated noise. (a) Comparison of biomagnetic fields, environmental noise, and sensitivity in 1 Hz bandwidth of various types of magnetometers. (b) Spontaneous brain activity and the system noise measured in an unshielded environment, noise cancelation by synthetic third-order gradiometer, primary sensors are radial first-order gradiometers with 5 cm baseline. Control trace was collected with no subject in the helmet, large lines correspond to signals due to nearby rotating machinery. Eyes closed and open were collected with the subject in the MEG helmet. The presence of alpha activity (peak at 8 Hz) is visible in the eyes closed condition. (Reproduced with permission from Ref. 18).



Figure 6. Noise attenuation of various shielded rooms as a function of frequency. (a) Eddy current Al rooms. (b) Standard µ-metal rooms used for MEG applications. (c,d) High attenuation µ-metal rooms. (e) Combination of high attenuation m-metal room in "d" and active shielding. (f) Whole-body high temperature superconducting shield. (Adapted with permission from Ref. 18).

compensating coils to reduce the noise. In general, the active shielding reduces the magnetic field noise due to far field sources and is effective only for magnetometers with no noise cancelation, while it has only a small effect on first-order gradiometers or magnetometers with noise cancelation. For higher order gradiometers, active shielding actually degrades system performance since the active coils can produce higher order gradients that are larger than that of the environmental noise.

Noise Reduction Using Higher Order Gradients. Since hardware noise cancelation (shielding or active noise cancelation) is usually not sufficient, additional methods, implemented in software or firmware, are employed. These methods either incorporate information from additional reference sensors or operate directly on the primary sensors. The reference sensors are typically a combination of SQUID magnetometers and gradiometers and the noise is canceled by synthesizing either higher order gradiometers or adaptively minimizing noise. The principle of synthetic gradiometer operation is similar for all gradiometer orders, and the method is illustrated for first-order gradiometer synthesis in Fig. 7a (29). The primary magnetometer detects the magnetic field component parallel to its coil normal, **p** (unit vector). The three reference magnetometers are orthogonal and their vector output, **r**, corresponds to the environmental field at the reference location, $\mathbf{r} \approx \mathbf{B}$. Then, if α_p is the primary magnetometer gain and α_r the reference gain (identical for all three references), the synthetic first-order gradiometer, $g^{(1)}$, can be derived as

$$g^{(1)} = m_p - \frac{\alpha_p}{\alpha_r}(\mathbf{p}\cdot\mathbf{r}) \approx \alpha_p \mathbf{p}\cdot\mathbf{G}\cdot\mathbf{b} \qquad (1)$$

where **b** is the gradiometer baseline (a vector connecting the primary sensor and the reference centers), and **G** is the first gradient tensor at the coordinate origin. Equation 1 states that the synthetic first-order gradiometer is a projection of the first-gradient tensor to the primary magnetometer orientation, **p**, and the baseline, **b**. To synthesize a second-order gradiometer, a primary hardware or synthetic first-order gradiometer, and a tensor first-gradient reference are used (Fig. 7b). Similar to Eq. 1, it can be shown that the synthetic second-order gradiometer output is a projection of the second gradient tensor to the coil orientation **p** and the first- and second-order gradiometer baselines $\mathbf{b}_1$ and $\mathbf{b}_2$. Synthesis of third- and higher order gradiometers is similar (29).



Figure 7. An illustration of gradiometer synthesis. (a) Synthesis of a first-order gradiometer from a primary magnetometer sensor and a vector magnetometer reference. (b) Synthesis of a second-order gradiometer from hardware first-order gradiometer and a first-gradient tensor reference. (Adapted from Ref. 30).

Adaptive methods can also be applied in addition to the synthetic gradiometers and can incorporate the same references as the gradiometers, but their coefficients are explicitly computed to minimize correlated noise (29). The advantage of synthesizing higher order gradiometers is that their coefficients are universal, independent of the noise character or sensor orientation (18). In contrast, the coefficients determined to adaptively minimize background noise are not universal because they depend on the noise character and sensor orientations (18) and assume that the noise environment is unchanging.

The noise cancelation achieved by various methods is illustrated in Fig. 8. The upper trace (a) shows the magnetic field noise outside a shielded room; and trace (b) shows the field noise after attenuation by the shielded room. The difference of the two slopes is due to the



Figure 8. Reduction of environmental noise by a moderately shielded room, synthetic gradiometers, and adaptive methods. (a) Magnetic field noise outside a shielded room. (b) Field noise after attenuation by the shielded room. (c) Noise reduction by hardware first-order gradiometer with 5 cm baseline. (d) Noise reduction by synthetic third-order gradiometer (nearly four orders of magnitude lower noise than that of a shielded magnetometer in "b"). (e) Noise reduction by addition of adaptive methods to synthetic third-order gradiometer. (Adapted from Ref. 31).

frequency dependent eddy current shield that is part of the room. Hardware first-order radial gradiometers with 5 cm baseline reduce noise by nearly a factor of 100; and (c) a synthetic third-order gradiometer; (d) reduces the noise by almost another factor of 100. The low frequency environmental noise can further be reduced by adaptive method (e). The combination of all methods in Fig. 8 achieves attenuation of $>10^7$ at low frequencies.

Additional noise reduction methods can be employed in systems with a large number of channels. The simplest method is spatial filtering using Signal Space Projection (SSP) (32–34), which projects out from the measurement the noise components oriented along specific spatial vectors in signal space. The method works best when the signal and noise subspaces are nearly orthogonal. Related to SSP is noise elimination by rotation in signal space (35), which avoids loss of degrees of freedom encountered in SSP. These methods are discussed further in the Signal Interpretation section. More recently Signal Space Separation (SSS) has been proposed as a noise cancelation method in MEG (36). This approach was first proposed by Ioannides et al. (37) and reduces environmental noise by retaining only the "internal" component of the spherical expansion of the measured signal. This method can be applied to a number of problems inherent in biomagnetic measurements, including environmental noise reduction and motion compensation.

Cryogenics

The sensing elements of a biomagnetometer system (SQUIDs, flux transformers, and their interconnections) are superconducting and must be maintained at low temperatures. Since all commercial systems use low temperature superconductors, they must be operated at liquid He temperatures of 4.2 K. These temperatures can be achieved either with cryocoolers or by a cryogenic bath in contact with the superconducting components. The cryocoolers are attractive because they eliminate the need for periodic refilling of the cryogenic container. However, because they contribute magnetic and electric interference, vibrational noise, thermal fluctuations, and Johnson noise from metallic parts (38), they are not yet commonly used in MEG instrumentation. Present commercial biomagnetometer systems rely on cooling by liquid He bath in a nonmagnetic vessel with an outer vacuum space also referred to as a Dewar. An example of how the components may be organized within the Dewar for an MEG system is shown in Fig. 9a (39). The primary sensing flux transformers are positioned in the Dewar helmet area. The reference system for the noise cancelation is positioned close to the primary sensors and the SQUIDs with their shields are located at some distance from the references, all immersed in liquid He or cold He gas. The Dewar is a complex dynamic device that incorporates various forms of thermal insulation, heat conduction, and radiation shielding, as shown Fig. 9b. Most commercial MEG and MCG systems have reservoirs holding up to 100 L of liquid He and can be operated for periods of several days before refilling. An excellent review of the issues associated with the Dewar construction is presented in (38).

Biomagnetometer Systems: Overview

Even though magnetic fields have been detected from many organs, so far the most important application of biomagnetism has been the detection of neuromagnetic activity of the human brain. This interest led to the development of sophisticated commercial MEG systems. The current generation of these systems consists of helmet shaped multisensor arrays capable of measuring activity


Vacuum space
Vacuum plug
Liquid helium
SQUIDs
Calibration points (for head localization)
References
Sensing coils
(a)
Escaping vapors (warm, ~ room T)
Vapor cooled heat shields
Super-insulation
Cold vapors
Liquid He4
4.2K
Incoming heat radiation
Heat reflected by super-insulation
(b)

Figure 9. Schematic diagram of cryogenic containers used for whole-cortex MEG. (a) Placement of various MEG components relative to the cryogenic Dewar. (b) Principles of the Dewar operation. Reproduced with permission from (10).

simultaneously from the entire cerebrum. In contrast, multichannel magnetocardiogram (MCG) systems consist of a flat array of radial or vector devices (40–45) or systems with a smaller number of channels operating at liquid N_2 temperatures (46–51) for better placement over the chest directly above the heart. These flat array systems can also be placed over other areas of the body to measure peripheral nerve, gastrointestinal, or muscle activity. These systems can even be placed over the maternal abdomen to measure heart and brain activity of the fetus and a custom shaped multichannel array specifically designed for fetal measurements has recently been introduced (39,52).

MEG Systems. A diagram of a generic MEG system is shown in Fig. 10. The SQUID sensors and their associated flux transformers are mounted within a liquid He dewar suspended in a movable gantry to allow for supine or seated patient position. The patient rests on an adjustable chair or a bed. All signals are preamplified and transmitted from the shielded room to a central workstation for real-time acquisition and monitoring of the magnetic signals. At present, the majority of MEG installations use magnetically shielded rooms, however, progress is being made toward unshielded operation (18,40). The MEG measurements are often complemented by simultaneous EEG measurements or peripheral measures of muscle activity or eye movement. Most MEG installations have provisions for stimulus delivery in order to study brain responses to sensory stimulation and video and intercom systems in order to interact with the patient from outside the shielded room. Multichannel MEG systems are commercially available from a number of manufacturers (39,53–56).

For MEG localization of brain activity to be useful, particularly in clinical applications, it must be accurately known relative to brain anatomy. The anatomical information is usually obtained by magnetic resonance imaging


Magnetically shielded room (optional)
Video monitor
Intercom
System electronics
Adjustable dewar and gantry
Video camera
EEG electronics
SQUID electronics
DSP processing
Data interpretation
EEG
Stimulus interface
Auditory
Visual
Somatosens.
Other
Stimulus computer
Acquisition work station
Analysis work stations

Figure 10. Schematic diagram of a typical MEG installation in a magnetically shielded room. (Reproduced with permission from Ref. 10).

(MRI), and the MRI images are required during the MEG interpretation phase. The registration of the MEG sensors to the brain anatomy is performed in two steps. First, the head position relative to the MEG sensor array is determined in order to accurately position MEG sources within a head-based coordinate system. Second, the head position relative to the MRI anatomical image is determined to allow transfer of MEG sources to the anatomical images. There are different methods for such registration. The simplest one uses a small number of anatomical markers positioned on identical locations on the head surface that can be measured both by MEG and MRI (e.g., small coils for MEG and lipid contrast markers for MRI) usually placed at anatomical landmarks near the noise and ears (18). To improve localization accuracy, the head shape can be digitized in the MEG coordinate system by a device mounted on the dewar (57) or by the MEG sensors (10). The surface of the head can also be constructed from segmented MRI and the transformation between the two systems can be determined by alignment of the two surfaces (58–60).

Biosusceptometers. A somewhat different system design is encountered in biomagnetometer systems used for the measurement of magnetic materials in the human body, such as iron content in the liver or magnetic contaminants in the lung. These instruments contain both SQUID sensing coils and a superconducting magnet operated in persistent mode. The system is suspended over the patient's body on a bed with a waterbag placed between the patient and dewar to provide continuity of the diamagnetic properties of body tissue. Figure 11 illustrates the layout of a biosusceptometer system for liver measurements with a patient in a supine position on a moveable bed. The patient is moved vertically relative to the SQUID gradiometer-magnet system and flux changes due to the susceptibility of the liver are monitored. These measures of magnetic moment can then be used to estimate the concentration of the paramagnetic compounds within the liver (62–64).



Figure 11. Schematic diagram of a liver susceptometer. (a) SQUID gradiometer. (b) Superconducting magnet. (c) Bag filled with water to simulate the diamagnetism of human body tissue. (d) Patient on a bed that is vertically movable. (Reproduced with permission from Ref. 61).

Signal Interpretation

Biomagnetometers measure the distribution of magnetic field outside of the body. Although the observed field patterns provide some information about the underlying physiological activity, ideally one would like to invert the magnetic field and provide a detailed image of the current distribution within the body. Such inversion problems are nonunique and ill defined. The nonuniqueness is either physical (65) or mathematical due to being highly underdetermined (i.e., there are many more sources than sensors). In order to determine the current distribution, it is necessary to provide additional information, constraints, or simplified mathematical models of the sources. The field of source modeling in both MEG and MCG has been an intensive area of study over the last 20 years. In the following section we shall review briefly various methods of source analysis as it is applied to MEG, although these methods apply to other biomagnetic measurements such as MCG, with the main difference being the physical geometry of the conductor volumes containing the sources. For detailed reviews of mathematical approaches used in biomagnetism (see 66–69).

Neural Origin of Neuromagnetic Fields. Magnetic fields of the brain measured by MEG are thought to be the primarily due to activation of neurons in the gray matter of the neocortex, whereas action potentials in the underlying fiber tracts (white matter) have been shown to produce only poorly synchronized quadrupolar sources associated with weak fields (70,71). Some subcortical structures have also been shown to produce weak yet measurable magnetic fields, but are difficult to detect without extensive signal processing (72,73). The generation of magnetic fields in the human brain is illustrated in Fig. 12. The neocortex of the brain (shown in Fig. 12a) contains a large number of pyramidal cells arranged in parallel (Fig. 12b) that in their resting state maintain an intracellular potential of ca. −70 mV. Excitatory (or inhibitory) synaptic input near the cell body or at the superficial apical dendrites results in the flow of charged ions across the cell membrane producing a graded depolarization (or hyperpolarization) of the cell. This change in polarization results in current flow inside the cell, called *impressed* current and corresponding return or *volume* currents that flow through the extracellular space in the opposite direction. Studies carried out in the early 1960s (74,75) demonstrated that these extracellular or volume currents are main generators of electrical activity measured in the electroencephalogram or EEG. The combination of excitatory and inhibitory synaptic inputs to different cortical layers can produce a variety of sink and source patterns through the depth of the cortex, each associated with current flow along the axes of elongated pyramidal cells toward or away from the cortical surface.



Figure 12. Origin of the MEG signal. (a) Coronal section of the human brain. The neocortex is indicated by dark outer surface. (b) Pyramidal cells in the cortex have vertically oriented receptive areas (dendrites). Depolarization of the dendrites at the cortical surface due to excitatory synaptic input results in Na^+ ions entering the cell producing a local current source and a current sink at the cell body, resulting in intracellular current flowing toward the cell body (arrow). (c) The cortex has numerous sulci and gyri resulting in currents flowing either tangentially or radially relative to the head surface. (d) Tangential currents will produce magnetic fields that are observable outside the head if modeled as a sphere. (e) Radial currents will not produce magnetic fields outside of the head if modeled as a sphere. (Adapted from Ref. 10).

Synchronous activity in large populations of these cells summate to produce the positive and negative time-varying voltages measured at the scalp surface in the EEG (76).

Okada et al. (77) carried out extensive studies over the last 20 years on the neural origin of evoked magnetic fields using small array “microSQUID” systems to measure directly magnetic fields from *in vitro* preparations in the turtle cerebellum and mammalian hippocampus. These studies have shown that although both extracellular and intracellular currents may contribute to externally measured magnetic fields, it is primarily intracellular or impressed currents flowing along the longitudinal axis of pyramidal cells that are the generators of evoked magnetic fields. A recent review of this work is presented in (78). Note that, since MEG measures mainly intracellular currents and EEG the return volume currents, the pattern of electrical potential over the scalp due to an underlying current source will reflect current flow in opposite direction to that of the magnetic field, as has been demonstrated in physical models (79) and human brain activity (80). In addition, activation of various regions of the enfolded cortical surface (the gyri and sulci) will result in current flow that is either radial or tangential to the scalp surface, respectively (Fig. 12c). If the brain is modeled as a spherical conducting volume, then due to axial symmetry it can be shown that only the tangential currents will produce fields outside the sphere (81) (Fig. 12d and e). Using *in vivo* preparations in the porcine brain, it has been experimentally demonstrated that, in contrast to the EEG, magnetic fields are relatively undistorted by the presence of the skull, and are generated primarily in tangentially oriented tissue (78). It has been recently shown, however, that MEG is insensitive only to a relatively small percentage of the total cortical surface in humans due to this tangential constraint (82). There is some uncertainty as to the extent of cortical activation typically measured by MEG. Current densities in the cortex have been estimated to be on the order of 50 $\mathrm{pA \cdot m \cdot mm^2}$(83) suggesting that cortical areas of at least 20 mm^2 must be activated in order to produce a sufficiently large external field to be observed outside the head (66,68). However, current densities as high as 1000 $\mathrm{pA \cdot m \cdot mm^2}$ have been recorded *in vitro* (77) indicating that much smaller areas of activation may be observed magnetically.

Equivalent Current Dipoles. The equivalent current dipole or ECD (81,84) is the oldest and most frequently used model for brain source activity. It is based on the assumption that activation of a specific cortical region involves populations of functionally interconnected neurons (macrocolumns) within a relatively small area. When measured from a distance, this local population activity can be modeled by a vector sum or “equivalent” current dipole that represents the aggregate activity of these neurons. The ECD analysis proceeds by estimating a priori the number of equivalent dipoles and their approximate locations, and then adjusting the dipole parameters (location and orientation) by a nonlinear search that minimizes differences between the field computed from the dipole model and the measured field (Fig. 13). This can be done at one time sample, or it can be extended to a time segment, where several dipoles are assumed to have fixed positions in space, but variable amplitude. Such models are referred to as “spatiotemporal” dipole models (85). The dipole fit procedures require the calculation of the magnetic field produced by a current dipole at each sensor: also termed the *forward solution*. Since the frequency range of interest for biomagnetic fields is <1 kHz, the quasistatic approximations of Maxwell’s equations apply. If the head is assumed to be approximately spherical in shape it can be represented by a uniformly conducting sphere and the radial magnetic field of an ECD with magnitude **q**, is given by the radial component of the well-known Biot–Savart law, $B_{\mathrm{rad}}(\mathbf{r}) = \mathbf{B}(\mathbf{r}) \cdot \mathbf{r}/|\mathbf{r}|$, where the Biot–Savart



Figure 13. Magnetic fields due to an equivalent current dipole source will exit and reenter the head that can be modeled as a spherical shaped conducting medium. Calculation of the field magnitude ($\mathbf{B}_{\text{coil}}$) measured by a magnetometer coil due to a current dipole $\mathbf{q}$ at location $\mathbf{r_0}$ inside a sphere is given by the projection of the calculated vector field $\boldsymbol{B(r)}$ onto the direction normal to the surface area of the coil indicated by the unit vector $\mathbf{p}$, such that $\boldsymbol{B}_{\text{coil}} = \boldsymbol{B}(\boldsymbol{r}) \cdot \boldsymbol{p}$. The orientation of $\mathbf{q}$ is assumed to be tangential to the sphere surface. For gradiometer devices, the measured output of the gradiometer can be calculated as the difference between the field magnitudes calculated separately at each of the coils.

vector field, $\mathbf{B}(\mathbf{r})$, is given by

$$\mathbf{B}(\mathbf{r}) = \frac{\mu_0}{4\pi} \frac{\mathbf{q} \times (\mathbf{r} - \mathbf{r}_{\text{o}})}{|\mathbf{r} - \mathbf{r}_{\text{o}}|^3} \tag{2}$$

where $\mathbf{r}_{\text{o}}$ is the ECD position and $\mathbf{r}$ is the position where the field is measured. For multiple ECDs or continuously distributed sources, Eq. 2 will also include the sum over all sources or the integral over the volume of the conducting sphere.

Generally, the vector of the external magnetic field is produced by both the primary current density reflecting the impressed (intracellular) currents, and volume currents that produce "secondary sources" on the surface of the volume conductor. For complex shapes, the calculation of the external field also requires knowledge of the conductivity profile of the conducting volume. The assumption of spherical symmetry, however, simplifies the calculation, and the vector field $\mathbf{B(r)}$ due to a current dipole $\mathbf{q}$ in a sphere at location $\mathbf{r}_{\text{o}}$ (Fig. 13b) is given by Sarvas (81) as

$$\mathbf{B}(\mathbf{r}) = \frac{\mu_0}{4\pi F^2} \{F\mathbf{q} \times \mathbf{r}_{\text{o}} - [(\mathbf{q} \times \mathbf{r}_{\text{o}}) \cdot \mathbf{r}]\nabla F\} \tag{3a}$$

where

$$F = a(ra + r^2 - \mathbf{r}_{\text{o}} \cdot \mathbf{r}) \tag{3b}$$

and

$$\nabla F = (r^{-1}a^2 + a^{-1}\mathbf{a} \cdot \mathbf{r} + 2a + 2r)\mathbf{r} - (a + 2r + a^{-1}\mathbf{a} \cdot \mathbf{r})\mathbf{r}_{\text{o}} \tag{3c}$$

and $\mathbf{a} = \mathbf{r} - \mathbf{r}_{\text{o}}$, $a = |\mathbf{a}|$, $r = |\mathbf{r}|$ and the permeability of free space $\mu_0 = 4\pi \times 10^{-7}$ H · m. The sensing coil measures the component of the vector field $\mathbf{B(r)}$ perpendicular to its surface area as shown in Fig. 13b. If the field is measured only in the radial direction, Eq. 3 simplifies to the radial component of the Biot–Savart law (Eq. 2), and the volume currents do not contribute any field. It can be seen from Fig. 13 that the definition of the origin of the theoretical sphere relative to the head will influence the calculation of the external magnetic field and thus plays a significant role in the accuracy of the single sphere approach. Since the head is not perfectly spherical, improved accuracy of the forward solution can be achieved by using more realistic models of the conducting surfaces and boundary element methods for the calculation of the magnetic field (69), but these methods are more computationally demanding. A simple improvement over the single sphere model can be achieved by using a multiple-sphere model, where independent spheres are determined for each sensor by evaluating local head curvature in the sensor vicinity (86).

The ECD procedure is very sensitive to the SNR and dc offsets, and therefore works best when applied to averaged brain responses that are well time locked to a sensory or motor event and requires an accurate estimate of signal baseline (e.g., prestimulus activity). This approach has proven useful for modeling simple patterns of focal brain activity, yet is compromised by interaction or "cross-talk" between simultaneously active sources, requiring that the number of dipoles be correctly specified. Also, ECD models do not correctly describe spatially "extended" sources: areas of cortical activity that may extend over an area of several square centimeters.

Minimum Norm. The dipole model assumes that the brain activity is localized in one or several small areas of the brain. Sometimes it is required to obtain a more general solution without an a priori assumption about the source distribution. This can be obtained by minimum norm methods, first proposed for MEG by Hämäläinen and Ilmoniemi (84). This inverse problem is underdetermined, solutions are diffuse, and the unweighted minimum norm favors solutions close to the sensors. The minimum norm method has subsequently been adapted to produce more localized solutions. The algorithm, FOCal Undetermined System Solution (FOCUSS) utilizes a recursive linear estimation based on weighted pseudoinverse solution (87) and the Minimum Current Estimate (MCE) utilizes the L1-norm approach (88). A related method, Magnetic Field Tomography (MFT) (89) utilizes weights and a regularization parameter that are optimized according to the given experimental geometry and noise. Another minimum norm-based method is the algorithm LORETA (LOw Resolution Electromagnetic TomogrAphy) (90). This algorithm introduces a spatial second derivative operator (Laplacian) into the weighting function and seeks the minimum norm solution subject to the maximum smoothness condition. This requirement is justified on a physiological assumption that neighboring points in the brain are likely to be synchronized. The method produces low spatial resolution that is a consequence of the smoothness constraint. Methods based on simulated (surrogate) data have also been proposed for producing distributed, unbiased solutions based on the minimum norm (91).

Bayesian Inference. Bayesian inference has also been applied to the biomagnetic inverse problem, using probability distributions of many possible source solutions. This approach can easily incorporate a priori information that may influence the likelihood of features of the current distribution based on anatomy, maximum current strength, smoothness, and so on (92,93). This method determines expectation and variance of the a posteriori source current probability distribution given source prior probability distribution and data set (94,95). The model can include probability weightings determined from other imaging techniques such as functional MRI (fMRI) or positron emission tomography (PET) to influence the MEG current images.

Signal Space Projection. Signal space projection. (33,34) and beamformers are spatial filters that can separate signal from noise on the basis of their relationship in signal space (a M-dimensional space, where M is the number of MEG channels). The application of spatial filtering to MEG was first proposed by Robinson and Rose (96). This original article sparked growing interest in spatial filtering by the MEG community that still continues. The spatial filtering depends on the assumption that component vectors corresponding to different neuronal sources have distinct and stable (fixed) directions in signal space, and only their magnitudes are functions of time. If the vectors are defined by modeling the field produced by known dipole sources, SSP can be used as a spatial filter that passes only signals corresponding to these known sources. Thus, we can define the output of a spatial filter as $y_\theta(t) = \mathbf{P}_{\|}\mathbf{m}(t)$, where $\mathbf{P}_{\|}$ is the parallel projection operator (95) constructed from the forward solutions of the dipole source(s) of interest, and $\mathbf{m}(t)$ represents a vector of instantaneous MEG measurement at time t. The output of the spatial filter then provides a time series that is the estimate of changing strength of the dipole source(s) over time. Alternatively, if the vectors associated with artifact patterns are known, SSP can be used to remove these artifacts from the signal using orthogonal projection operators (32). If the signal vectors are determined from patterns in the data, the source model need not even be known. Note that restricting all sources to current dipoles in a known volume conductor model reduces SSP to a multiple dipole approximation (34).

Beamformers. The SSP method does not separate well sources that are not in orthogonal subspaces. To overcome this limitation, source analysis can be done by beamforming (borrowed from radio-communication and radar work). Beamformers utilize spatial and temporal correlations to obtain information about uncorrelated dipolar sources. The Linearly Constrained Minimum Variance (LCMV) beamformer in the form now used in MEG analysis was first described in 1972 (97) and can be used without specific information about source orientation. An introduction to the beamformers may be found in (98) and a relatively recent review of various beamforming techniques in (99). As in the case of SSP, if vector $\mathbf{m}(t)$ represent an instantaneous MEG measurement in M-dimensional space, we can define a spatial filter centered on the location "θ" as $y_\theta(t) = \mathbf{W}_\theta^T m(t)$, where $\mathbf{W}_\theta$ is a weight matrix. Only tangential sources contribute to the MEG signal. They can be decomposed into two orthogonal tangential directions and the corresponding forward solutions, $\mathbf{B}_{\theta 1}$ and $\mathbf{B}_{\theta 2}$, can be arranged in a forward solution matrix as $\mathbf{H}_\theta = [\mathbf{B}_{\theta 1}, \mathbf{B}_{\theta 2}]$. The beamformer weights are determined by minimizing the power projected from the location , $P_\theta = \mathbf{W}_\theta^T \mathbf{C} \mathbf{W}_\theta$, subject to the unity gain condition, $\mathbf{W}_\theta^T \mathbf{H}_\theta = \mathbf{I}$, where $\mathbf{C}$ is the covariance matrix of the measurement and $\mathbf{I}$ is the identity matrix. The weights are given as (100)

$$\mathbf{W}_\theta = \mathbf{C}^{-1}\mathbf{H}_\theta(\mathbf{H}_\theta^T \mathbf{C}^{-1}\mathbf{H}_\theta)^{-1} \tag{4}$$

An alternative approach known as synthetic aperture magnetometry (SAM) defines an optimal dipole orientation for each spatial filter location (101). Only one vector is retained, $\mathbf{H}_\theta = \mathbf{B}_\theta$ simplifying Eq. 6 to $\mathbf{W}_\theta = \mathbf{C}^{-1}\mathbf{B}_\theta (\mathbf{B}_\theta^T \mathbf{C}^{-1}\mathbf{B}_\theta)^{-1}$. This approach produces higher spatial resolution due to less projected sensor noise by the spatial filter (102). The beamformer weights can be used to compute the time course of the dipole magnitude variation or power at a single location in the brain independently of other active sources, provided sources are not highly correlated. An especially useful quantity is the normalized power $Z_\theta^2 = P_\theta / N_\theta$, where $N_\theta^2 = \mathbf{W}_\theta^T \Sigma \mathbf{W}_\theta$ is the sensor noise projected by the beamformer from location 'θ', and Σ is the sensor noise covariance matrix (100). In contrast to P_θ and N_θ, the parameter Z_θ^2 behaves gracefully through the center of the model sphere and does not exhibit a singularity. A spatial image of brain activity can be obtained by computing the normalized power at individual brain voxels, θ, one at a time over a region of interest.

Multiple Signal Classification. MUltiple SIgnal Classification (MUSIC) is a signal space scanning method and is related to beamforming (103,104). MUSIC requires an initial nonlinear step of partitioning the data covariance matrix into signal and noise subspaces using standard eigendecomposition methods. This partitioning can be more readily determined from the averaged data and as a result the method is more difficult to apply to spontaneous brain activity. Sources are located by scanning of the brain volume and at each location requiring that the dipole forward solution be orthogonal to the noise subspace (or parallel to the signal subspace). A more recent implementation known as recursively applied and projected MUSIC (RAP-MUSIC) projects out each located source and then repeats the scanning procedure (105). Similar to beamforming, MUSIC also assumes there are fewer sources than sensors, the sources are uncorrelated and the noise is white. In the limit of high SNR (e.g., averaged data), a small number of sources, and white noise, the MUSIC localizer function and beamformer based source power estimates differ only by a scaling factor.

Principal Component Analysis. Principal Component Analysis (PCA), for example (106,107), also determines the signal and noise subspaces. The method is based on second order statistics and attempts to fit dipoles into the orthogonal principal spatial vectors of the singular value decomposition of the data. For mixtures of components corresponding to nonorthogonal spatial vectors, the PCA cannot account for the structure of the data (108). The PCA has been shown to be potentially inaccurate, as it can mislocalize dipoles even in noiseless simulations.

Independent Component Analysis. Independent Component Analysis (ICA) is a relatively new technique that allows separation of sources that are linearly mixed at the sensors. The method is also called blind source separation, because the source signals are not directly observed and nothing is known about their mixture (109,110). The method uses higher order statistics and in realistic situations is often more successful than PCA (108). The mixing model used for the separation is usually stated as $\mathbf{m}(t) = \mathbf{A}\mathbf{s}(t)$, where $\mathbf{m}(t)$ is the instantaneous vector of the measurement, $\mathbf{s}(t)$ is the instantaneous source activity vector, and $\mathbf{A}$ is the mixing matrix. The procedure provides solution for an unmixing matrix $\mathbf{B}$, such that the estimated source activity is given as $\hat{\mathbf{s}}(t) = \mathbf{B}m(t)$, where $\hat{\mathbf{s}}$ is the estimate of the source vector $\mathbf{s}$. The sources are assumed to be statistically independent and the separation is obtained by optimizing a contrast function, that is, a scalar measure of some distributional property of the output $\hat{\mathbf{s}}$. The contrast functions are based on entropy, mutual independence, high order decorrelations, and so on. The ICA has been applied to MEG and EEG to either remove artifacts or extract desired signals (111,112).

APPLICATIONS OF BIOMAGNETIC MEASUREMENTS

Magnetoencephalography: Basic Studies

The most prevalent and rapidly growing application of biomagnetism is the field of magnetoencephalography (MEG): the measurement of human brain activity. This field of basic and clinical research is also referred to as *neuromagnetism* or *magnetic source imaging* (113–117). The latter term is often used to refer to the localization of neural sources with respect to individual brain anatomy by the combination of MEG source modeling with structural imaging techniques such as MRI (see Magnetic Resonance Imaging). As noted in the introduction, the first magnetic fields recorded from the human brain involved the observation of spontaneous alpha rhythm activity. This was soon followed by the application of MEG measurements to the study of *evoked responses* of the human brain: Time-averaged responses to discrete sensory or motor events that provide sufficient SNR to allow for the localization of brain regions contributing to the externally measured field patterns. Due to its excellent time resolution and ability to measure neuronal function directly, MEG has continued to generate interest within the field of human neuroscience as a complement to other methods of functional brain imaging based on metabolic or hemodynamic changes in brain function, such as fMRI (see Magnetic Resonance Imaging) or PET (see Positron Emission Tomography). Present MEG practice includes measurement of both evoked and spontaneous signals and is used for clinical purposes and for investigation of a wide range of brain processes.

Somatosensory Evoked Fields. Evoked responses to stimulation of the human somatosensory system (somatosensory evoked fields or SEFs) were first reported by Brenner and colleagues in 1987 (118). The observed magnetic brain response to electrical stimulation of the digit was of great interest since it demonstrated a well-characterized dipolar field pattern over the scalp indicative of a single neural generator located in the underlying somatosensory cortex. Subsequent studies have shown that early components of the SEF occurring at latencies of 20–50 ms reflect early activation of the primary somatosensory cortex contralateral to the side of stimulation, and are generally well modeled as single ECD source in these brain regions [see (119) for a recent review]. The earliest component at a poststimulus latency of 20 ms (sometimes referred to as the "M20" or "N20m" since it is considered the magnetic equivalent of the negative N20 potential measured in the EEG) arises from the posterior bank of the central sulcus: a primary somatosensory projection area. By stimulating different body parts, it can be shown that the N20m source reflects the somatotopic or "homuncular" organization of the ascending neural pathways of the somatosensory system to this brain region (120). Figure 14 shows a typical SEF response to stimulation of the median nerve at the wrist and the localization of an ECD model fit to the N20m source in the corresponding somatosensory cortex.

When using extensive signal averaging, MEG recordings also reveal low amplitude high frequency oscillations in the 300–900 Hz range during the period of the N20m



Figure 14. (a) Topographic map (polar projection with nose upwards) of the magnetic field pattern recorded from 151 MEG channels over the scalp at a latency of 20 ms following stimulation of the right median nerve (average of 600 stimuli). White contours indicate outgoing fields and solid contours, ingoing fields. Arrow indicates direction of current flow below the scalp corresponding to the dipolar field pattern over the left hemisphere. (b) Location of a single ECD source corresponding to the magnetic field pattern shown in (a) indicated by white dot with tail indicating direction of current flow superimposed on an axial slice of the individual's MRI. Location is in the hand region of the primary somatosensory cortex.

response (121). These oscillations have been proposed to reflect the activity of inhibitory interneurons in the somatosensory cortex (122) although cortico-thalamic pathways have also been shown to play a possible role (123). The N20m is followed by reversals of the same pattern at latencies of 30 and 40 ms that appear to reflect additional activation of somatosensory areas. These are followed by more complex and widespread activity from ~80 to 150 ms after stimulation that reflects bilateral activation of secondary somatosensory areas in the parietal operculum and is most likely related to higher order processing of somatosensory input (124). The MEG responses at latencies of 50–70 ms are elicited by mechanical stimulation of the digits (125) and reflect somatotopically organized sources in the primary somatosensory cortex (80). A number of MEG studies have used mechanical SEFs to demonstrate functional reorganization or "plasticity" of the somatosensory cortex resulting from anesthetic block or damage to the peripheral nerves or amputation (126), or even as the result of musical training (127).

Movement Related Fields. The first recordings of magnetic fields accompanying simple finger movements were reported in the early 1980s. Deecke et al. (128) observed slow magnetic field changes over sensorimotor areas of the brain preceding voluntary movements of the digits. These "readiness fields" begin approximately a half a second prior to the onset of a voluntary movement and are thought to represent activation of brain areas involved in motor preparation (129). Dipole source analysis suggests that premovement fields arise primarily from bilateral activation of the primary motor cortex (even for unilateral movements) with larger amplitude fields and dipole magnitudes the contralateral to the side of movement (130).

Movement-evoked fields (MEFs) accompany the onset and execution phase of simple movements. The first component (MEFI) is the largest in amplitude and begins ~100 ms after onset of EMG activity in the involved muscles. These responses appear to arise from sources in the postcentral gyrus, most likely reflecting sensory feedback to cortex from proprioceptors in the muscles (131) and are correlated with movement velocity (132). Movements made in response to a sensory cue show a very similar pattern of activity, but with a shorter latency of onset of premovement activity (133). Passive movements also elicit magnetic responses thought to reflect activation of the proprioceptive inputs to areas of the postcentral gyrus (134). MEG mapping studies have demonstrated activity in motor cortex during motor imagery providing evidence of the involvement of these brain areas in the simple imagination of movement (135).

MEG–EMG Coherence. By using a single channel magnetometer, Conway et al. (136) made the interesting observation of increased coherence (correlation in the frequency domain) between the surface electromyogram (EMG) in a contracting muscle and MEG recordings made over the contralateral motor areas. Subsequently, there has been a great deal of interest in the relationship between MEG–EMG coherence and the functional relationship between spontaneous cortical rhythms and EMG activity during movement (137). Interestingly, changes in the frequency of coherence varies with the strength of muscular contraction and recent studies have shown that MEG–EMG coherence may reflect the underlying physiology of tremor in patients with Parkinson's disease (138) or essential tremor (139).

Sensorimotor Rhythms. The MEG studies have also provided evidence for the functional significance of specific oscillatory brain activity in humans associated with both somatosensory stimulation and motor output. These centrally distributed rhythms were first observed in the EEG, and are predominant at frequencies ~10 Hz (also referred to as the mu rhythm) and in the range of 20–30 Hz. The MEG studies have been able to show that these are functionally independent cortical oscillations that originate from postcentral and precentral regions, respectively (140,141). These sensorimotor rhythms are suppressed during median nerve stimulation, followed by a transient increase or "rebound" of 20–30 Hz rhythms within 500 ms after stimulus onset. A similar pattern of suppression followed by rebound is observed during voluntary movements (142). These rhythmic changes are modulated by sensorimotor tasks such as movement or passive tactile stimulation and motor imagery or even observation of another individual's movements (140). Rhythmic activity is not amenable to the same signal averaging technique used for evoked fields and therefore the ECD source modeling approach is more difficult to apply. Spatial filtering methods, however, provide a new approach to the localization of frequency dependent power changes in cortical areas using MEG and have been applied to the localization of rhythmic changes induced by somatosensory stimulation (141,143) and voluntary movements of the digits (144).

Visual Evoked Fields. One of the first magnetic evoked responses recorded from the human brain was the visual evoked field or VEF reported by Brenner et al. in 1975 (145). Robust responses can be elicited at latencies of 100–150 ms following visual stimulation using light flashes or visual pattern contrast changes (e.g., reversing checkerboard stimuli). However, early VEF responses pose a challenge in terms of modeling their sources due to the complex enfolded cross-like shape of the primary (striate) visual cortex: also referred to as the "cruciform" model. More recently, investigators have successfully modeled early VEF components in primary visual cortex by stimulating restricted portions of the total visual field using both monochrome (146) and color (147) pattern stimuli and have produced source configurations that reflect the retinotopic organization of the primary visual cortex. Due to the difficulty in applying ECD models to the VEF response, spatial filtering methods such as beamforming have been found to be useful for imaging visual cortex function (148). Figure 15 shows the activation of primary visual cortex by a steady state visual pattern (reversing checkerboard) using the SAM beamforming algorithm. Visual stimuli also activate several nonprimary (extrastriate) visual areas depending on the attributes of the stimulus. A number of MEG studies have shown activation of brain areas related to higher order visual processes such as detection



Figure 15. Images of following response to flickering checkerboard stimulus at $f = 17$ Hz presented to the left or right visual field, using a whole-head MEG recordings and the synthetic aperture magnetometry (SAM) beamformer algorithm. The image shows increased source power as yellow (lighter) colored areas at the posterior portion of the brain, corresponding to increased power at 34 Hz ($2f$) in the primary visual cortex of the contralateral hemisphere. Unpublished data. (Courtesy of K. Singh.)

of coherent motion (149,150). Clinical applications of VEFs have been limited, although abnormal VEFs have been reported in cases of strabismic amblyopia (151).

Auditory Evoked Fields. Auditory evoked fields were first reported by Reite et al. (152) and subsequent MEG mapping studies have demonstrated that responses at latencies of 50 and 100 ms reflect activity of primary auditory cortex in the temporal lobes (153). The largest response occurring ~100 ms following stimulus onset, termed the M100, has been the most extensively studied auditory evoked field response. The M100 is bilateral for both binaural and monaural stimuli and has been shown to reflect the frequency specific (tonotopic) organization of the primary auditory cortex (154). These magnetic evoked responses are of interest in the study of the functional organization of the auditory system as they reflect perceptual attributes of auditory stimulation such as perceived pitch or the frequency profiles of complex speech sounds (155,156). Auditory responses to repetitive (steady-state) auditory stimuli show enhanced amplitude in the EEG at presentation rates of ~40 Hz and were initially thought to represent volume conducted thalamic responses. However, MEG steady-state auditory responses were shown by Weinberg et al. (157) to reflect oscillations at the stimulus frequency in the auditory cortex. Subsequent studies have suggested that 40 Hz auditory responses reflect thalamocortical networks in the brain responsible for integration of sensory input (158). The 40 Hz MEG response has recently been used to measure temporal integration times in the primary auditory cortex (159).

MEG Studies of Higher Brain Function. Although early MEG studies have provided useful information regarding the early processing of sensory input and motor output, one of the more intriguing potential uses of MEG is the non-invasive study of higher brain function. The EEG studies of cognitive function have been carried out using event-related potentials (ERPs) for many decades. The MEG measurements using similar paradigms have helped gain a better understanding of the neural basis of many ERP components. Early MEG studies have had some success in measuring brain responses related to short-term memory (160), target detection tasks (161), or selective attention (162). More recently, the use of whole head MEG systems have enabled the study of more complex aspects of cognitive processing in humans, such as face recognition (163) and object naming (164). Basic research on brain mechanisms related to speech and language is also a promising area of application for MEG. Early studies have shown that speech processing is affected by incongruous visual feedback at the level of the auditory cortex (165). More recent studies have attempted to localize magnetic brain responses related to syntactic (166) and semantic (167) language processes as well as the processing of speech sounds (168). The MEG responses have also been used to study abnormal processing of sensory input during reading in dyslexic children (169) and during speech in stutterers (170).

A great deal of progress has been made in studying higher brain function with MEG by applying traditional source analysis methods to ERP components. However, these complex brain processes often involve activation of multiple brain regions complicating the interpretation of the data in terms of simple ECD models. Moreover, many of these processes may not be highly time-locked to specific sensory or motor events. More recent approaches have focused on oscillatory brain activity and synchronization or "phase-locking" between different cortical areas. Accordingly, this has produced increased interest in brain imaging methods with fine temporal resolution such as MEG. Rhythmic activity in the so-called gamma frequency band (30–90 Hz) is of particular interest since it is associated with cognitive processes such as feature binding within a sensory modality that may underlie perception (171). Recent studies have also described changes in neuromagnetic rhythms associated with observation and imitation of other individual's actions that appear to originate in brain areas associated with learning through imitation (172). Since changes in spontaneous brain rhythms are not necessarily time-locked to a stimulus onset, alternative signal processing techniques are required (173). The combination of spatial filtering source analysis methods and time frequency and phase analysis may be particularly well suited to measure these aspects of higher order brain function (141) and constitute a new and interesting avenue of research in human cognition.

Magnetoencephalography: Clinical Applications

Presurgical Functional Mapping. One of the more prevalent clinical applications of MEG is the localization of so-called "eloquent cortex" (those areas that subserve sensory, motor, speech, and memory function) prior to neurosurgery in order to prevent loss of these functions as a result of the surgical procedure. Due to displacement cortical tissue by space occupying lesions such as tumors, or natural variability in cortical morphology, identification of these brain areas may not be possible by visual inspection alone and can be aided by functional localization of these areas using MEG. This is achieved by activating primary sensory areas associated with visual, somatosensory and auditory stimulation, and applying ECD models to the early evoked response—a method generally referred to as *presurgical functional mapping* (114,116). For example, the N20m source of the somatosensory evoked field can be consistently and reliably localized in most individuals and used as an estimate of the location of the central sulcus prior to surgical removal of brain tissue in the region of the primary motor or somatosensory cortex (174).

Determination of the language dominant hemisphere is also necessary prior to surgical resection of cortical tissue near language areas of the temporal lobe. This is routinely done through highly invasive procedures such as selective anesthesia of the left and right hemispheres (*Wada test*) or direct cortical stimulation intraoperatively. The use of MEG for the localization of brain areas that are specific to the processing of speech, as distinct from areas associated with the simple processing of auditory input, constitutes a challenging area of research, however, some recent progress has been made in this area (175–177). In addition to using MEG source imaging to identify functional and pathological brain areas in surgical planning, these functional data can also be incorporated into frameless stereotaxic *neuronavigation* systems. These systems allow surgeons to identify the corresponding brain areas in the functional and structural images during the surgical procedure. The MEG-based neuronavigation is rapidly becoming a useful clinical tool for the surgical treatment of epilepsy, tumors and other brain disorders (114,178,179).

Epilepsy. Due to its high temporal resolution and ability to localize focal brain activity, there has been a long interest in the application of MEG to the study of epilepsy. In many case, intractable seizures can be controlled by the removal of the epileptogenic zone: brain tissue from which seizure activity originates. The identification of this area may be aided by the measurement of abnormal electrical activity between seizures. These interictal (between seizure) spikes arise from an *irritative zone* that may be correlated with the epileptogenic zone in cases of focal epilepsy (180). The localization of ECD sources based on MEG recordings of interictal spiking activity has been shown to be highly correlated with the localization of this zone as identified by other methods such as direct intracranial monitoring from depth or subdural electrode grids [for recent reviews see (181–184)]. Interictal spikes are generally of much larger amplitude than sensory evoked responses and ECD models can be used to localize individual spike events without averaging. However, the area activated may be quite large and exhibit a high degree of spatial variability, and as a result the aggregate locations or clusters of many spike sources are often used to estimate the putative location of the irritative zone. Other methods, such as spatial filtering by beamformers (SAM), are currently being investigated and may help overcome some of the limitations of the single ECD approach to the localization of epileptogenic areas. Even in cases where the precise location of the epileptogenic zone is not clearly identified, MEG may help to guide the placement of subdural grids, and in some cases may be used to evaluate the propagation of abnormal electrical activity between multiple brain regions. The diagnostic yield of MEG measurements of interictal activity varies with different forms of epilepsy and appears to be highest for neocortical epilepsy (185) and can also aid in the differentiation of different types of epilepsy (186).

Since the site of brain pathology may not be known in advance, particularly in nonlesional epilepsy, the introduction of whole-head MEG systems has drastically improved the feasibility of using MEG as a routine clinical procedure for presurgical epilepsy evaluation allowing the data to be acquired in a more rapid and standardized manner. The main drawbacks to the application of MEG in epilepsy is the inability to measure brain activity during or just prior to seizure onset due to head movement, and the difficulty in performing long-term monitoring of interictal activity, although this is somewhat ameliorated by the introduction of MEG systems that allow recording from patients in the supine position and while asleep. Although there is some debate on the overall usefulness of MEG in the presurgical evaluation of epilepsy (183) comparisons with other modalities such as EEG, functional MRI, and intracranial electrical recordings (114,182) indicate that MEG provides useful complementary, and in some cases unique information for the surgical treatment of epilepsy.

Other Clinical Applications. Although presurgical functional mapping and epilepsy have been the main areas of clinical application of MEG, other brain disorders have been studied. This includes the use of MEG to study changes in electrical brain activity associated with tumors that often manifests as abnormal low frequency activity (187) or other disturbances in brain rhythmic activity (188) and may help identify the functional integrity of surrounding brain tissue (189). Abnormal low frequency activity has been associated with other brain lesions such as those due to stroke and in epilepsy (190). The MEG has also been used to study recovery after stroke due to functional reorganization of the cortex (191) and its relationship to rehabilitation and outcome (192) and in the evaluation of patients with mild head injury (193). Low frequency neuromagnetic activity has been hypothesized to be an index of spreading cortical depression associated with migraine (194).

The MEG studies have focused on pain related brain responses by selectively stimulating the $A\delta$ and C fiber systems painful CO_2 laser stimulation of the skin (195) or direct electrical stimulation of nerve fibers (196). This type of somatosensory stimulation produces long latency responses in secondary somatosensory areas located in the parietal operculum, and insula: brain regions known to be involved in the perception of pain. Such studies are promising for the clinical treatment of chronic pain, although are challenging due to the difficulty in discriminating activation of brain areas due to painful versus nonpainful somatosensory input, and the invasiveness of the procedure.

More recently, MEG measures have also been combined with neurochemical imaging methods such as magnetic resonance spectroscopy (MRS). In these studies, correlations have been found between MEG activity and changes in levels of neurotransmitter and other brain metabolites in ischemia or in brain areas harboring tumors (197). Although still a new area of study, there is a great deal of interest in the application of MEG to psychiatric disorders. For example, MEG studies have reported abnormal auditory evoked magnetic fields in schizophrenic patients (198) and patients with Alzheimer's disease (199) or in individuals with developmental disorders such as autism (200).

Magnetocardiography

The first biomagnetic measurements in humans were measurements of the magnetic field of the heart. The field of magnetocardiography or MCG has not expanded as rapidly as that of MEG, although a number of research centers have continued to develop the MCG method for the noninvasive evaluation of cardiac disease. As described in the Instrumentation section, MCG requires instrumentation designed for the adequate sampling of the heart's magnetic field over the chest and a number of instruments have been developed and installed at research centers around the world, including systems based on high temperature SQUIDs. Source modeling based on magnetic field measurements is somewhat simplified in the case of MEG due the ability to model the head as a spherically shaped conductor, whereas, modeling of the electrical activity of the heart requires realistic models of the conducting properties of the thorax and its influence on the distribution of magnetic fields arising from the heart. As a result, source localization methods in MCG often employ boundary element methods for forward calculations (201). Source localization in MCG is further complicated by the continuous movement of the heart itself. Nevertheless, MCG has been successfully used in the diagnosis of cardiac disease. For recent reviews see (202–204).

Since the 1980s a number of studies have focused on the use of MCG for the 3D localization of the origins of abnormal electrical activity of the heart. This includes abnormal activity underlying cardiac arrhythmias, such as Wolff–Parkinson–White syndrome, which involves abnormal electrical activity (preexcitation) in the accessory pathway. Recent studies have shown that MCG studies provide more accurate localization of the site of pathology than standard multichannel electrocardiogram techniques (205). The identification of the generators of heart arrhythmias is useful in presurgical evaluation for interventional procedures such as catheter ablation therapy, or in the screening of patients at risk for ventricular tachycardia (202) or coronary artery disease (206). Another application of MCG is in the assessment of ischemic areas of the heart after infarction by the detection of regions of low current density (207).

Fetal Studies

One of the more intriguing new applications of biomagnetism is the noninvasive measurement of activity of the fetal heart and brain. Since the first report of the detection of an evoked response from the fetal brain in 1985 (208) there has been a great of interest in developing instrumentation for the measurement of biomagnetic fields from the human fetus. The main challenges for the measurement of fetal MCG or MEG is the detection of biomagnetic sources that are distant from the detector array, and the difficulty in establishing the position of the fetal heart and brain during measurement. The latter has been partially resolved by the combination of fetal biomagnetic measurements with 3D ultasound imaging and new instrumentation has been recently designed for optimum placement and sensitivity of the sensory array to detect fetal heart and brain responses.

Fetal MCG. The largest biomagnetic signal arising from the fetus is the fetal magnetocardiogram or fMCG. The first recording of fMCG was demonstrated in 1984 (209). The fMCG signal magnitude is quite large, but due to proximity of the fetus to the mother's heart, signal processing methods are required to first remove the large maternal heart signal, after which the P, QRS, and T segments of the fMCG can be discerned with high reliability in fetuses beyond the twentieth week of gestation (210). Fetal heart rate variability has been shown to be a good indicator of fetal well being (211). This method has been applied to the detection of fetal arrhythmias (212) and may provide a useful diagnostic or screening tool for fetal congenital heart defects (213), or for the assessment of fetal health in high risk pregnancies. An overview of fMCG can be found in (214).

Fetal MEG. Due to the distance of the fetal brain from the surface of the maternal abdomen, the fetal MEG (fMEG) signal is difficult to detect without high sensitivity biomagnetometer with large coverage, large number of channels, and optimal placement of the sensor array. In addition, the fetal brain signals are small in comparison with an adult and their measurement is performed in the presence of strong interference from the maternal and fetal heart signals and various abdominal signals (intestinal electrical activity, uterine contractions, etc.). Measurements of fetal brain responses to sensory stimulation are also hampered by the difficulty in delivering the sensory stimulus to the fetus. However, fetal auditory evoked responses have been successfully recorded by presenting high amplitude auditory stimuli directly to the mother's abdomen (215,216). In order to successfully eliminate the interference due to cardiac signals, which can be >100 times larger than the fMEG, the latter efforts employed various signal extraction methods (spatial filtering, PCA, etc.) in addition to averaging. Magnitudes of fMEG responses to transient tone bursts are in the range of ~8–180 fT and the latencies range from ~125 to nearly 300 ms, decreasing with the increasing gestation age (217). The response is typically observed in not more than about 50% of examined subjects. Fetal responses to steady-state auditory clicks have also been reported (218) as well as spontaneous fetal brain activity in the form of burst suppression (219). The strength of these signals can be



Figure 16. Dedicated system for fetal MEG measurement. (a) Schematic diagram of SQUID Array for Reproductive Assessment (SARA) (52). (b) Layout of 151 sensing channels. (c) Example of flash evoked fMEG response, overlay of 151 SARA channels. The fetus with gestation age of 28 weeks was stimulated by 33 ms duration flashes of 625 nm wavelength light (220). Vertical dashed line corresponds to the flash stimulus onset. (Adapted from Ref. 221).

relatively large, up to 500 fT, and can represent interference during evoked fMEG responses.

Early fMEG experiments used single or multiple-channel probes with relatively small area of coverage, requiring a search for the region with the largest signals. Recently, a dedicated fetal MEG system, the SQUID Array for Reproductive Assessment (SARA), was constructed and operated (52). The SARA system consists of an array of 151 SQUID sensors covering the mother's anterior abdominal surface in late gestation, from the perineum to the top of the uterus as shown in Fig. 16a and b. The primary sensor flux transformers are axial first-order gradiometers, with 8 cm baseline with a nominal SQUID sensor noise density of $4\ \mathrm{fT/Hz}^{1/2}$. The SARA system is now being used routinely and was recently used to measure the first fetal visual evoked field to high intensity light stimuli presented to the maternal abdomen (220). An example of a flash evoked response from the fetal brain is shown in Fig. 16c.

Other Applications

Biosusceptometry. The greatest interest in biosusceptometry has stemmed from its potential to assess noninvasively iron overload in the human liver. This potentially fatal condition arises in individuals with hemoglobinopathies that require frequent blood transfusions (e.g., sickle cell anemia) or involve abnormal production of hemoglobin (hemachromatosis and beta-thalassemia). Standard methods for assessing iron overload can be highly invasive (e.g., liver biopsy) and biosusceptometry offers a safer and potentially more accurate diagnostic tool. Iron, which is normally strongly ferromagnetic, is stored in the liver bound by the proteins ferritin and hemosiderin and exhibits a strong paramagnetic response. As a result, measurement of the magnetic moment produced by placing the liver in a uniform magnetic field will be proportional to the total amount of iron in the liver: a method known as *biomagnetic liver susceptometry* (BLS). The basis for this technique was first proposed and the first measurements carried out in the late 1970s (222).

Most approaches to the measurement of hepatic iron concentration involve placing the patient's abdomen directly under a magnetic sensor that also contains a field coil that produces a magnetic field, and lowering the patient by a fixed distance to measure the change in field amplitude due to the magnetized liver (Fig. 11). In order to eliminate the effect of the surrounding air, a water-filled bellows is placed between the abdomen and the device to simulate the diamagnetic properties of the other tissues in the body. The main challenge to accurate estimates of hepatic iron content using BLS is the remaining effect of the varying susceptibility of the lungs and air filled compartments in the abdomen. Since this technique requires the application of a dc magnetic field to the body on the order of about 0.1 T, it is a much more invasive technology in comparison to MEG and MCG, and may be contraindicated in patients with implanted medical devices such as pacemakers. A detailed review of the clinical applications of BLS can be found in (223).

Peripheral Nerve Studies. It is known from the pioneering studies of Wikswo and colleagues (70) that the propagation of action potentials in nerve fibers produces quadrupolar like sources that have a rapidly diminishing magnetic field with distance. This is due to the fact that action potentials consist of a traveling wave of depolarization in the axon, followed closely by a wave of repolarization. In addition, due to varying conduction velocities in the peripheral nerves, action potentials in different axons will not necessarily summate to produce coherent synchronous activity. As a result, activation of compound nerve bundles does not produce coherent dipole-like sources as in the case of the neocortex. However, with sufficient signal averaging it is possible to record the magnetic signature of the sensory nerve action potentials noninvasively in the human: a technique referred to as *magnetoneurography*. These measures have been achieved by placing single channel magnetometers or flat arrays of magnetic sensors over the peripheral nerve pathways and electrically stimulating the nerve. The predicted quadrapolar pattern of traveling actions potentials resulting from electrical stimulation of the finger was reported by Hoshiyama et al. (224) using a 12 channel "micro-SQUID" device placed over the wrist. Mackert et al. (225), using a 49 channel flat triangular array of first-order radial gradiometers were able to measure compound action potentials elicited by tibial nerve stimulation in sensory nerves entering the spinal cord at the lower lumbar region, and have recently using this method clinically to demonstrate impaired nerve conduction in the patients with S1 root compression.

Magnetopneumography. Magnetopneumography refers to the measurement of the remanent magnetism of ferromagnetic particles in the lungs. This technique may be used to assess lung contamination encountered in occupations that may involve the inhalation of ferromagnetic dust particles such as arc-welders, coalminers, asbestos, and foundry and steel workers. Similar to liver biosusceptometry, magnetopneumography involves the application of a weak dc magnetic field to the thorax. However, the field is applied for only a short interval in order to produce a remanent magnetization of ferromagnetic material, usually iron oxides such as magnetite. This remanent magnetic field is then measured to assess to total load of ferromagnetic particles in the lung. These measures can be used to evaluate the quantity and clearance rates of these substances (226,227). A related measure is *relaxation*: the decay of the remanent field due to the reorientation of the magnetic particles away from their aligned state after application of the dc field. Relaxation times are thought to reflect cellular processes in the lung associated with clearance or macrophage activity on the foreign particles. Recent studies have used magnetopneumography to study the effect of smoking on clearance times of inhaled magnetic particles (228).

Gastrointestinal System. Biomagnetic measurements have also been applied to other areas of the human body. The human gastrointestinal system produces electrical activity associated with the processes of peristalsis and digestion of food. For example, slow electrical activity at frequencies of ~3 cycles/min (0.05 Hz) can be recorded from the human stomach using cutaneous surface electrodes or magnetically: a technique referred to as *magnetogastrography* (MGG). This activity arises from the smooth muscle of the stomach and the detection of changes in frequency with time has been proposed as a method of characterizing gastric disorders (229). Another novel application of biomagnetic instrumentation to gastrointestinal function, is the 3D tracking of the transport of magnetic materials through the gut. This technique has been termed *magnetic marker monitoring* (MMM) and can be used to monitor the passage and disintegration (by measuring decrease in magnetic moment) of magnetically labeled pharmaceutical substances through the gastrointestinal system (230).

FUTURE DIRECTIONS

Since its inception 40 years ago with the first recording of the magnetic field of the heart, the field of biomagnetism has expanded immensely to become a major field of basic and applied research. The field of magnetoencephalography, or MEG, has in recent years become a recognized neuroimaging technique, with the development of advanced instruments for the measurement of the electrical activity of the brain with exquisite temporal and spatial resolution. Biomagnetic instrumentation is now at a mature state, with commercially developed measurement systems available for a variety of biomagnetic applications. For example, whole head MEG systems are installed worldwide in >100 research laboratories and clinical centres and are now being used in routine clinical diagnostic procedures. Nevertheless, there remain many areas for further improvement of both instrumentation and data analysis approaches and techniques. In terms of instrumentation, biomagnetometer systems with increased number of sensing channels and capable of unshielded operation will likely be developed, and present systems that require frequent refilling with liquid Helium may be replaced by systems with longer hold times and less frequent cryogen replenishment. The latter may be accomplished either by incorporation of cryocoolers, or the use of sensors that do not require liquid He. The last two technical innovations, combined with production of larger numbers of MEG systems will also help reduce the cost of these instruments.

The analysis and interpretation of biomagnetic measurements is possibly the most significant area for continued research and development, and much progress has been made in the implementation of new signal processing algorithms for the extraction of biomagnetic signals, or improving the spatial resolution of source localization methods. There has been recent interest in combining MEG with its high temporal resolution and other functional imaging techniques such as functional MRI. In addition, advanced image processing techniques, such as the automated extraction of the cortical surface of the brain from structural MRI, will allow the use of more precise physical models of biomagnetic sources. Combination of MEG with its counterpart EEG may also help to develop more accurate models of brain activity. These advancements will aid the development of new clinical applications of biomagnetism such as the use of MEG to study psychiatric disorders, or to study the effects of drug treatments on brain processes related to cognitive deficits, or gain insight into the physiological mechanisms underlying various brain disorders in children, for example, learning disabilities, dyslexia, and autism. Finally, novel applications of biomagnetic measurements, for example, the measurement of heart and brain activity in the fetus, will lead to new applications of biomagnetism in clinical medicine and will further drive the development of improved technology. In sum, biomagnetism will continue to grow as a novel and powerful noninvasive technique for the study of physiological processes in humans in both health and disease.

BIBLIOGRAPHY

Cited References

1. Baule GM, McFee R. Detection of the magnetic field of the heart. Am Heart J 1963;66:95–96.
2. Cohen D. Magnetoencephalography: evidence of magnetic fields produced by alpha-rhythm currents. Science 1968; 161:784–786.
3. Josephson BD. Possible new effect in superconductive tunneling. Phys Lett 1962;1:251–253.
4. Zimmerman JE. Recent developments in superconducting devices. J Appl Phys 1971;42:30–37.
5. Cohen D, Edelsack EA, Zimmerman JE. Magnetocardiograms taken inside a shielded room with a superconducting point-contact magnetometer. Appl Phys Lett 1970;16:278–280.
6. Cohen D. Magnetoencephalography: detection of the brain's electrical activity with a superconducting magnetometer. Science 1972;175:664–666.
7. Cheyne D, Vrba J, Crisp D, Betts K, Burbank M, Cheung T, Fife A, Haid G, Kubik P, Lee S, McCubbin J, McKay J, McKenzie D, Spear P, Taylor B, Tillotson M, Weinberg H, Basar E. Use of an unshielded, 64 channel, whole cortex MEG system in the study of normal and pathological brain function. Proceedings of the Satellite Symposium on Neuroscience and Technology, 14th Annu Conf IEEE Eng Med Biol Soc Lyon. France: 1992; 46–50.
8. Ahonen AI, Hämäläinen MS, Kajola MJ, Knuutila JET, Laine PP, Lounasmaa OV, Simola JT, Tesche CD, Vilkman VA. A 122-channel magnetometer covering the whole head. Proceedings of the Satellite Symposium on Neuroscience and Technology, 14th Annu Conf IEEE Eng Med Biol Soc Lyon. France: 1992; 16–20.
9. Clarke J. SQUIDs: theory and practice. In: Weinstock H, Ralston RW, editors. The New Superconducting Electronics. Dordrecht, Boston: Kluwer Academic; 1993. p 123–180.
10. Vrba J, Robinson SE. Signal processing in magnetoencephalography. Methods 2001;25:249–271.
11. Jaklevic R, Lambe RC, Silver AH, Mercereau JE. Quantum interference effects in Josephson tunneling. Phys Rev Lett 1964;12:159–160.
12. Jaycox JM, Ketchen MB. Planar coupling scheme for ultra low noise dc SQUIDs. IEEE Trans Magn 1981;MAG-17:400–403.
13. Ketchen MB, Jaycox JM. Ultra low noise tunnel junction dc SQUID with a tightly coupled planar input coil. Appl Phys Lett 1982;40:736–738.
14. Clarke J, Goubau WM, Ketchen MB. Tunnel junction DC SQUID: fabrication, operation, and performance. J Low Temp Phys 1976;25:99–144.
15. McKay J, Vrba J, Betts K, Burbank MB, Lee S, Mori K, Nonis D, Spear P, Uriel Y. Implementation of multichannel biomagnetic measurement system using DSP technology. Proc Can Conf Elect Comp Eng 1993; 1090–1093.
16. Robinson SE. A digital SQUID controller for unshielded biomagnetic measurement. In: Aine C, Okada Y, Stroink G, Swithenby S, Wood C, editors. Biomag96: Proc 10th Int Conf Biomag; 2000; New York: Springer; p 103–106.
17. Knuutial JET, Ahonen AI, Hamalainen MS, Kajola MJ, Petteri Laine P, Lounasmaa OV, Parkkonen LT, Simola JTA, Tesche CD. A 122-channel whole-cortex SQUID system for measureing the brain's magnetic fields. IEEE Trans Mag 1993;29:3315–3321.
18. Vrba J. Multichannel SQUID biomagnetic systems. In: Weinstock H, editor. Applications of Superconductivity. Dordrecht: Kluwer Academic Publishers; 2000. p 61–138.
19. Kominis IK, Kornack TW, Allred JC, Romalis MV. A subfemtotesla multichannel atomic magnetometer. Nature (London) 2003;422:596–599.
20. Zimmerman JE. SQUID instruments and shielding for low level magnetic measurements. J Appl Phys 1977;48:702–710.
21. H. G. Vacuumschmelze GmbH, Shielded room model AK-3.
22. Sullivan GW, Flynn ER. Performance of the Los Alamos Shielded Room. In: Atsumi K, Kotani M, Ueno S, Katila T, Williamson SJ, editors. Biomagnetism '87. Tokyo: Tokyo Denki University Press; 1987. p 486–489.
23. Erné SN, Hahlbohm HD, Scheer G, Trontelj Z. The Berlin magnetically shielded room (BMSR). In: Erné SN, editor. Biomagnetism. Berlin: Walter de Gruyter; 1981. p 79–87.
24. Bork J, Hahlbohm HD, Klein R, Schnabel A. The 8-layered magnetically shielded room of the PTB: Design and construction. In: Nenonen J, Ilmoniemi R, Katila T, editors. Biomag 2000. Proc 12th Int Conf Biomag. Espoo, Finland: Helsinki University of Technology; 2001. p 970–973.
25. Matsuba H, Shintomi K, Yahara A, Irisawa D, Imai K, Yoshida H, Seike S. Superconducting shielding enclosing a human body for biomagnetic measurement. In: Baumgartner C, Deecke L, Stroink G, Williamson SJ, editors. Biomagnetism: Fundamental research and clinical applications. Amsterdam, The Netherlands: Elsevier Science, IOS Press; 1995. p 483–489.
26. Matsumoto K, Yamagishi Y, Wakusawa A, Noda T, Fujioka K, Kuraoka Y. SQUID based active shield for biomagnetic measurements. In: Hoke M, Erné SN, Okada Y, Romani Gl, editors. Biomagnetism: clinical aspects. Proc 8th Int Conf Biomag. Amsterdam: Excerpta Medica; 1992. p 857–861.
27. Malmivuo J, Lekkala J, Kontro P, Suomaa I, Vihinin H. Improvement of the properties of an eddy current magnetic shield with active compensation. J Phys E: Sci Instr 1987;20:151–164.
28. ter Brake HJM, Wieringa HJ, Rogalla H. Improvement of the performance of a μ-metal magnetically shielded room by means of active compensation. Meas Sci Technol 1991;2: 596–601.
29. Vrba J. SQUID gradiometers in real environments. In: Weinstock H, editor. SQUID sensors: Fundamentals, Fabrication, and Applications. Dordrecht, Boston: Kluwer Academic Publishers; 1996. p 117–178.
30. Vrba J, Robinson SE. SQUID sensor array configurations for magnetoencephalography applications. Supercond Sci Technol 2002;15:R51–R89.
31. Vrba J. Magnetoencephalography: the art of finding a needle in a haystack. Phys C 2002;368:1–9.
32. Huotilainen M, Ilmoniemi RJ, Tiitinen H, Lavikainen J, Alho K, Kajola M, Naatanen R. The projection method in removing eye blink artefacts from multichannel MEG measurements. In: Baumgartner C, Deecke L, Stroink G, Williamson SJ, editors. Biomagnetism: Fundamental research and clinical applications. Elsevier Science, IOS Press; 1995. p 363–367.
33. Tesche CD, Uusitalo MA, Ilmoniemi RJ, Huotilainen M, Kajola M, Salonen O. Signal-space projections of MEG data characterize both distributed and well-localized neuronal sources. Electroencephalogr Clin Neurophys 1995; 95:189–200.

34. Uusitalo MA, Ilmoniemi RJ. Signal-space projection method for separating MEG or EEG into components. Med Biol Eng Comput 1997;35:135–140.
35. Parkkonen LT, Simola JT, Tuoriniemi JT, Ahonen AI. An interference suppression system for multichannel magnetic field detector arrays. In: Yoshimoto T, Kotani M, Kuriki S, Karibe H, Nakasato N, editors. Recent Advances in Biomagnetism. Sendai: Tohoku University Press; 1999. p 13–16.
36. Taula S, Kajola MJ, Simola JT. The Signal Space Separation method. 14th Conf Int Soc Brain Electromagnetic Topography. Santa Fe, NM; 2003.
37. Ioannides AA, Mütter J, Barna-Popescu EA. Irreducible tensor representation of MEG signals: Theory and applications. In: Nenonen J, Ilmoniemi R, Katila T, editors. Biomag 2000. Proc 12th Int Conf Biomag. Espoo, Finland: Helsinki University of Technology; 2001. p 883–886.
38. ter Brake HJM. Cryogenic systems for superconducting devices. In: Weinstock H, editor. Applications of superconductivity. Dordrecht: Kluwer Academic Publishers; 2000. p 561–639.
39. VSM MedTech Ltd. (CTF) 9 Burbidge St. Coquitlam, B.C., Canada (www.vsmmedtech.com).
40. Nowak H. Biomagnetic Instrumentation. In: Andrä W, Nowak H, editors. Magnetism in Medicine. Berlin: Wiley VCH; 1998. p 88–135.
41. Hoenig HE, Daalmans GM, Bär L, Bömmel F, Paulus A, Uhl D, Weisse HJ, Schneider S, Seifert H, Reichenberger H, Abraham-Fuchs K, Multichannel DC. SQUID sensor array for biomagnetic applications. IEEE Trans Magn 1991; 27:2777–2785.
42. Tsukada K, Kandori A, Miyashita T, Sasabuchi H, Suzuki H, Kondo S, Komiyama Y, Teshogawara K. A simplified superconducting quantum interference device system to analyze vector components of a cardiac magnetic field. Proc 20th Annu Int Conf IEEE/EMBS. Hong Kong; 1998. p 524–527.
43. Van Leeuwen P, Haupt C, Hoormann C, Hailer B, Mackert BM, Stroink G. A 67 channel biomagnetometer designed for cardiology and other applications. In: Yoshimoto T, Kotani M, Kuriki S, Karibe H, Nakasato N, editors. Recent Advances in Biomagnetism. Sendai: Tohoku University Press; 1999. p 89–92.
44. Erné SN, Pasquarelli A, Kammrath H, Della Penna S, Torquati K, Pizzella V, Rossi R, Granata C, Russo M. Argos 55 - the new MCG system in Ulm. In: Yoshimoto T, Kotani M, Kuriki S, Karibe H, Nakasato N, editors. Recent Advances in Biomagnetism. Sendai: Tohoku University Press; 1999. p 27–30.
45. Montonen J, Ahonen A, Hämäläinen M, Ilmoniemi R, Laine P, Nenonen J, Paavola M, Simelius K, Simola J, Katila T. Magnetocardiographic functional imaging studies in BioMag Laboratory. In: Aine CJ, Okada Y, Stroink G, Swithenby S, Wood C, editors. Biomag 96: Proc Tenth Int Conf Biomag. New York: Springer; 2000. p 494–497.
46. ter Brake HJM, Janssen N, Flokstra J, Veldhuis D, Rogalla H. Multichannel heart scanner based on high-Tc SQUIDs. IEEE Trans Appl Supercond 1997;7:2545–2548.
47. Seidel P, Schmidl F, Wunderlich S, Dörrer L, Vogt T, Schneidewind H, Weidl R, Lösche R, Leder U, Solbig O, Nowak H. High-Tc SQUID systems for practical use. IEEE Trans Appl Supercond 1999;9:4077–4080.
48. Kouznesov KA, Borgmann J, Clarke CJS. High-Tc second-order gradiometer for magnetocardiography in an unshielded environment. Appl Phys Lett 1999;75:1979–1981.
49. Zhang Y, Panaitov G, Wang SG, Wolters N, Otto R, Schubert J, Zander W, Krause HJ, Soltner H, Bousack H, Braginski A. Second-order, high-temperature superconducting gradiometer for magnetocardiography in an unshielded environment. Appl Phys Lett 2000;76:906–908.
50. Ludwig F, Jansman ABM, Drung D, Lindström M, Bechstien S, Beyer J, Flokstra J, Schurig T. Optimization of direct-coupled high-Tc SQUID magnetometers for operation in a magnetically shielded environment. IEEE Trans Appl Supercond 2001;11:1824–1827.
51. Barthelmess H-J, Halverscheid M, Schiefenhövel B, Heim E, Schilling M, Zimmerman R. Low-noise biomagnetic measurements with a multichannel dc-SQUID system at 77 K. IEEE Trans Appl Supercond 2001;11:657–660.
52. Robinson SE, BM, FA, HG, KP, I Sekachev, Taylor B, Tillotson M, Wong VJG, Lowery C, Eswaran H, Wilson D, Murphy P, Preissl H. A biomagnetic instrument for human reproductive assessment. In: Nenonen J, Ilmoniemi R, Katila T, editors. Biomag2000, Proc 12th Int Conf Biomag. Espoo, Finland: Helsinki University of Technology; 2001. p 919–922.
53. 4-D Neuroimaging Inc. 9727 Pacific Heights Blvd., San Diego, CA 92121-3719 (www.4dneuroimaging.com).
54. Neuromag Oy, P.O. Box 68, FIN-00511 Helsinki, Finland (www.neuromag.com).
55. Eagle Technology, Inc. 1-2-23 Hirosaka, Kanazawa Ishikawa 920-0962, Japan (www.eagle-tek.com).
56. Advanced Technologies Biomagnetics S.r.l, Via Martiri di Pietransieri 2, 65129 Pescara, Italy (www.atb-it.com).
57. Polhemus Inc., Hercules Drive, P.O. Box 560, Colchester, VT 05446.
58. Bramidis PD, Ioannides AA. Combination of point and surface matching techniques for accurate registration of MEG and MRI. In: Aine CJ, Okada Y, Stroink G, Swithenby S, Wood C, editors. Biomag 96: Proc 10th Int Conf Biomag. New York: Springer; 1997. p 1126–1129.
59. Abraham-Fuchs K, Lindner L, Weganer P, Nestel F, Schneider S. Fusion of biomagnetism with MRI or CT images by contour fitting. Biomed Eng 1991;36(Suppl.): 88–89.
60. Kober H, Nimsky C, Vieth J, Fahlbusch R, Ganslandt O. Co-registration of function and anatomy in frameless stereotaxy by contour fitting, Stereotact Funct. Neurosurg 2002;79:272–283.
61. Braginski A, Krause HJ, Vrba J. SQUID magnetometers. In: Francombe MH, editor. Handbook of Thin Film Devices, Volume 3: Superconducting Film Devices. San Diego: Academic Press; 2000. p 149–225.
62. Farrell DE, Tripp JH, Zanzucchi PE. Magnetic measurements of human iron stores. IEEE Transactions on Magnetics May-1980;16:818–823.
63. Paulson DN, Fagaly RL, Toussaint RM, Fischer R. Biomagnetic susceptometer with SQUID instrumentation. IEEE Trans Magn 1991;27:3249–3252.
64. Fischer F. Liver iron susceptometry. In: Andrä W, Nowak H, editors. Magnetism in medicine: a handbook. Berlin; New York: Wiley-VCH; 1998. p 286–301.
65. Helmholtz H. Über einige Gesetze der Vertheilung elektrischer Ströme in köperlichen Leitern mit Anwendung auf die thierisch-elektrischen Versuche. Ann Phys Chem 1853;89:211–233, 353–377.
66. Hämäläinen M, Hari R, Ilmoniemi RJ, Knuutila JET, Lounasmaa OV. Magnetoencephalography-theory, instrumentation, and applications to noninvasive studies of the working human brain. Rev Mod Phys 1993;65:413–497.
67. Jeffs B, Leahy R, Singh M. An evaluation of methods for neuromagnetic image reconstruction. IEEE Trans Biomed Eng 1987;34:713–723.

68. Baillet S, Mosher JC, Leahy R. Electromagnetic brain mapping. IEEE Signal Proc Mag 2001;18:14–30.
69. Mosher JC, Leahy RM, Lewis PS. EEG and MEG: forward solutions for inverse methods. IEEE Trans Biomed Eng 1999;46:245–259.
70. Wikswo JP, Barach JP, Freeman JA. Magnetic field of a nerve impulse: first measurements. Science 1980;208:53–55.
71. Swinney KR, Wikswo, Jr. JP. A calculation of the magnetic field of a nerve action potential. Biophys J 1980;32:719–731.
72. Tesche CD. Non-invasive imaging of neuronal population dynamics in human thalamus. Brain Res 1996;729:253–258.
73. Tesche CD, Karhu J, Tissari SO. Non-invasive detection of neuronal population activity in human hippocampus. Brain Res Cogn Brain Res 1996;4:39–47.
74. Humphrey DR. Re-analysis of the antidromic cortical response. II. On the contribution of cell discharge and PSPs to the evoked potentials. Electroencephalogr Clin Neurophysiol 1968;25:421–442.
75. Creutzfeldt OD, Watanabe S, Lux HD. Relations between EEG phenomena and potentials of single cortical cells. I. Evoked responses after thalamic and epicortical stimulation. Electroencephalogr Clin Neurophysiol 1966;20:1–18.
76. Mitzdorf U. Current source-density method and application in cat cerebral cortex: investigation of evoked potentials and EEG phenomena. Physiol Rev 1985;65:37–100.
77. Okada YC, Wu J, Kyuhou S. Genesis of MEG signals in a mammalian CNS structure. Electroencephalogr Clin Neurophysiol 1997;103:474–485.
78. Okada Y. Toward understanding the physiological origins of neuromagnetic signals. In: Lu Z-L, Kaufman L, editors. Magnetic Source Imaging of the Brain. Mahwah. New Jersey: Lawrence Erlbaum Associates; 2003. p 43–76.
79. Weinberg H, Brickett P, Coolsma F, Baff M. Magnetic localisation of intracranial dipoles: simulation with a physical model. Electroencephalogr Clin Neurophysiol 1986;64:159–170.
80. Cheyne D, Roberts LE, Gaetz W, Bosnyak D, Nahmias C, Christoforou N, Weinberg H. Somatotopic organization of human somatosensory cortex: a comparison of EEG, MEG and fMRI methods. In: Koga Y, Nagata K, Hirata K, editors. Brain Topography Today. Amsterdam: Elsevier Science; 1998. p 76–81.
81. Sarvas J. Basic mathematical and electromagnetic concepts of the biomagnetic inverse problem. Phys Med Biol 1987;32: 11–22.
82. Hillebrand A, Barnes GR. A quantitative assessment of the sensitivity of whole-head MEG to activity in the adult human cortex. Neuroimage 2002;16:638–650.
83. Lu ZL, Williamson SJ. Spatial extent of coherent sensory-evoked cortical activity. Exp Brain Res 1991;84:411–416.
84. Hämäläinen MS, Ilmoniemi RJ. Interpreting measured magnetic fields of the brain: Estimates of current distribution. Report TKK-F-A559. Helsinki University of Technology: Espoo, Finland, 1984.
85. Scherg M, Von Cramon D. Two bilateral sources of the late AEP as identified by a spatio-temporal dipole model. Electroencephalogr Clin Neurophysiol 1985;62:32–44.
86. Huang MX, Mosher JC, Leahy RM. A sensor-weighted overlapping-sphere head model and exhaustive head model comparison for MEG. Phys Med Biol 1999;44:423–440.
87. Gorodnitsky IF, George JS, Rao BD. Neuromagnetic source imaging with FOCUSS: a recursive weighted minimum norm algorithm. Electroencephalogr Clin Neurophysiol 1995;95: 231–251.
88. Wagner M, Wischmann HA, Fuchs M, Kohler T, Drenckhahn R. Current density reconstruction using the L1 norm. In: Aine CJ, Okada Y, Stroink G, Swithenby S, Wood C, editors. Biomag96. New York: Springer-Verlag; 2000. p 393–396.
89. Ioannides AA, Bolton JPR, Clarke CJS. Continuous probabilistic solutions to the biomagnetic inverse problem. Inverse Problems 1990;6:523–542.
90. Pascual-Marqui RD, Michel CM, Lehmann D. Low resolution electromagnetic tomography: a new method for localizing electrical activity in the brain. Int J Psychophysiol 1994; 18:49–65.
91. David O, Garnero L, Cosmelli D, Varela FJ. Estimation of neural dynamics from MEG/EEG cortical current density maps: application to the reconstruction of large-scale cortical synchrony. IEEE Trans Biomed Eng 2002;49: 975–987.
92. Baillet S, Garnero L. A Bayesian approach to introducing anatomo-functional priors in the EEG/MEG inverse problem. IEEE Trans Biomed Eng 1997;44:374–385.
93. Schmidt DM, George JS, Wood CC. Bayesian inference applied to the electromagnetic inverse problem. Hum Brain Mapp 1999;7:195–212.
94. Hämäläinen MS, Haario H, Lehtinen MS. Inferences about sources of neuromagnetic fields using Bayesian parameter estimation. Espoo, Finland: Helsinki University of Technolgy; 1987.
95. Sorenson HW. Parameter estimation. New York: Marcel Dekker; 1980.
96. Robinson SE, Rose DF. Current source estimation by spatially filtered MEG. In: HokeM, Erné SN, Okada Y, Romani GL, editors. Biomagnetism: clinical aspects. Proc 8th Int Conf Biomag. Amsterdam: Excerpta Medica; 1992. p 761–765.
97. Frost OL. An algorithm for linearly constrained adaptive array processing. Proc IEEE 1972;60:926–935.
98. Van Veen B, Buckley K. Beamforming: A versatile approach to spatial filtering, in IEEE ASSP Mag.; 1988. p 4–24.
99. Godara LC. Application of antenna array to mobile communications, Part II: Beam-Forming and direction-of-arrival considerations. Proc IEEE 1997;85:1195–1245.
100. Van Veen BD, Van Drongelen W, Yuchtman M, Suzuki A. Localization of brain electrical activity via linearly constrained minimum variance spatial filtering. IEEE Trans Biomed Eng 1997;44:867–880.
101. Robinson SE, Vrba J. Functional neuroimaging by synthetic aperture magnetometry (SAM). In: Yoshimoto T, Kotani M, Kuriki S, Karibe H, Nakasato N, editors. Recent Advances in Biomagnetism. Sendai: Tohoku University Press; 1999. p 302–305.
102. Vrba J, Robinson SE. Linearly constrained minimum variance beamformers, synthetic aperture magnetometry and MUSIC in MEG applications. IEEE, Proc 34th Asilomar Conf. Signals, Systems, Comput. Pacific Grove, CA: Omnipress; 2000. p 313–317.
103. Schmidt RO. Multiple emitter location and signal parameter estimation. IEEE Trans Anten Propagat 1986;AP-34:276–280.
104. Mosher JC, Lewis PS, Leahy RM. Multiple dipole modeling and localization from spatio-temporal MEG data. IEEE Trans Biomed Eng 1992;39:541–557.
105. Mosher JC, Leahy R. Source localization using recursively applied and projected (RAP) MUSIC. IEEE Trans Signal Proc 1999;47:332–340.
106. Maier J, Dagnelie G, Spekreijse H, van Dijk BW. Principal components analysis for source localization of VEPs in man. Vision Res 1987;27:165–177.
107. Achim A, Richer F, Saint-Hilaire JM. Methods for separating temporally overlapping sources of neuroelectric data. Brain Topogr 1988;1:22–28.

108. Jung TP, Makeig S, Mckeown MJ, Bell AJ, L. T, Sejnowski TJ. Imaging brain dynamics using independent component analysis. Proc IEEE 2001;89:1107–1122.
109. Cardoso J-F. Blind signal separation: Statistical principles. Proc IEEE 1998;86:2009–2025.
110. Hyvarinen A. Fast and robust fixed-point algorithms for independent component analysis. IEEE Trans Neural Networks 1999;10:626–634.
111. Makeig S, Jung TP, Bell AJ, Ghahremani D, Sejnowski TJ. Blind separation of auditory event-related brain responses into independent components. Proc Natl Acad Sci USA 1997;94:10979–10984.
112. Ziehe A, Muller KR, Nolte G, Mackert BM, Curio G. Artifact reduction in magnetoneurography based on time-delayed second-order correlations. IEEE Trans Biomed Eng 2000; 47:75–87.
113. Lewine JD, Orrison, Jr. WW. Magnetic source imaging: basic principles and applications in neuroradiology. Acad Radiol 1995;2:436–440.
114. Wheless JW, Castillo E, Maggio V, Kim HL, Breier JI, Simos PG, Papanicolaou AC. Magnetoencephalography (MEG) and magnetic source imaging (MSI). Neurologist 2004; 10:138–153.
115. Lu Z-L, Kaufman L, editors. Magnetic Source Imaging of the Brain. Mahwah, NJ: Lawrence Erlbaum Associates; 2003.
116. Gallen CC, Schwartz BJ, Bucholz RD, Malik G, Barkley GL, Smith J, Tung H, Copeland B, Bruno L, Assam S. Presurgical localization of functional cortex using magnetic source imaging. J Neurosurg 1995;82:988–994.
117. Roberts TP, Poeppel D, Rowley HA. Magnetoencephalography and magnetic source imaging. Neuropsychiat Neuropsychol Behav Neurol 1998;11:49–64.
118. Brenner D, Lipton J, Kaufman L, Williamson SJ. Somatically evoked magnetic fields of the human brain. Science 1978;199:81–83.
119. Kakigi R, Hoshiyama M, Shimojo M, Naka D, Yamasaki H, Watanabe S, Xiang J, Maeda K, Lam K, Itomi K, Nakamura A. The somatosensory evoked magnetic fields. Prog Neurobiol 2000;61:495–523.
120. Nakamura A, Yamada T, Goto A, Kato T, Ito K, Abe Y, Kachi T, Kakigi R. Somatosensory homunculus as drawn by MEG. Neuroimage 1998;7:377–386.
121. Curio G, Mackert BM, Burghoff M, Koetitz R, Abraham-Fuchs K, Harer W. Localization of evoked neuromagnetic 600 Hz activity in the cerebral somatosensory system. Electroencephalogr Clin Neurophysiol 1994;91:483–487.
122. Hashimoto I, Mashiko T, Imada T. Somatic evoked high-frequency magnetic oscillations reflect activity of inhibitory interneurons in the human somatosensory cortex. Electroencephalogr Clin Neurophysiol 1996;100:189–203.
123. Ikeda H, Leyba L, Bartolo A, Wang Y, Okada YC. Synchronized spikes of thalamocortical axonal terminals and cortical neurons are detectable outside the pig brain with MEG. J Neurophysiol 2002;87:626–630.
124. Hari R, Karhu J, Hämäläinen MS, Knuutila J, Salonen O, Sams M, Vilkman V. Functional organization of the human first and second somatosensory cortices: a neuromagnetic study. Eur J Neurosci 1993;5:724–734.
125. Suk J, Ribary U, Cappell J, Yamamoto T, Llinas R. Anatomical localization revealed by MEG recordings of the human somatosensory system. Electroencephalogr Clin Neurophysiol 1991;78:185–196.
126. Flor H, Elbert T, Knecht S, Wienbruch C, Pantev C, Birbaumer N, Larbig W, Taub E. Phantom-limb pain as a perceptual correlate of cortical reorganization following arm amputation. Nature (London) 1995;375:482–484.
127. Elbert T, Pantev C, Wienbruch C, Rockstroh B, Taub E. Increased cortical representation of the fingers of the left hand in string players. Science 1995;270:305–307.
128. Deecke L, Weinberg H, Brickett P. Magnetic fields of the human brain accompanying voluntary movement: Bereitschaftsmagnetfeld. Exp Brain Res 1982;48:144–148.
129. Cheyne D, Weinberg H. Neuromagnetic fields accompanying unilateral finger movements: pre-movement and movement-evoked fields. Exp Brain Res 1989;78:604–612.
130. Kristeva R, Cheyne D, Lang W, Lindinger G, Deecke L. Movement-related potentials accompanying unilateral and bilateral finger movements with different inertial loads. Electroencephalogr Clin Neurophysiol 1990;75:410–418.
131. Cheyne D, Endo H, Takeda T, Weinberg H. Sensory feedback contributes to early movement-evoked fields during voluntary finger movements in humans. Brain Res 1997;771:196–202.
132. Kelso JA, Fuchs A, Lancaster R, Holroyd T, Cheyne D, Weinberg H. Dynamic cortical activity in the human brain reveals motor equivalence. Nature (London) 1998;392:814–818.
133. Endo H, Kizuka T, Masuda T, Takeda T. Automatic activation in the human primary motor cortex synchronized with movement preparation. Cogn Brain Res 1999;8:229–239.
134. Xiang J, Hoshiyama M, Koyama S, Kaneoke Y, Suzuki H, Watanabe S, Naka D, Kakigi R. Somatosensory evoked magnetic fields following passive finger movement. Brain Res Cogn Brain Res 1997;6:73–82.
135. Lang W, Cheyne D, Hollinger P, Gerschlager W, Lindinger G. Electric and magnetic fields of the brain accompanying internal simulation of movement. Cogn Brain Res 1996;3:125–129.
136. Conway BA, Halliday DM, Farmer SF, Shahani U, Maas P, Weir AI, Rosenberg JR. Synchronization between motor cortex and spinal motoneuronal pool during the performance of a maintained motor task in man. J Physiol 1995;489(Pt. 3): 917–924.
137. Brown P. Cortical drives to human muscle: the Piper and related rhythms. Prog Neurobiol 2000;60:97–108.
138. Salenius S, Avikainen S, Kaakkola S, Hari R, Brown P. Defective cortical drive to muscle in Parkinson's disease and its improvement with levodopa. Brain 2002;125: 491–500.
139. Timmermann L, Gross J, Dirks M, Volkmann J, Freund HJ, Schnitzler A. The cerebral oscillatory network of parkinsonian resting tremor. Brain 2003;126:199–212.
140. Hari R, Salmelin R. Human cortical oscillations: a neuromagnetic view through the skull. Trends Neurosci 1997;20: 44–49.
141. Cheyne D, Gaetz W, Garnero L, Lachaux JP, Ducorps A, Schwartz D, Varela FJ. Neuromagnetic imaging of cortical oscillations accompanying tactile stimulation. Brain Res Cogn Brain Res 2003;17:599–611.
142. Feige B, Kristeva-Feige R, Rossi S, Pizzella V, Rossini PM. Neuromagnetic study of movement-related changes in rhythmic brain activity. Brain Res 1996;734:252–260.
143. Gaetz WC, Cheyne DO. Localization of human somatosensory cortex using spatially filtered magnetoencephalography. Neurosci Lett 2003;340:161–164.
144. Taniguchi M, Kato A, Fujita N, Hirata M, Tanaka H, Kihara T, Ninomiya H, Hirabuki N, Nakamura H, Robinson SE, Cheyne D, Yoshimine T. Movement-related desynchronization of the cerebral cortex studied with spatially filtered magnetoencephalography. Neuroimage 2000;12:298–306.
145. Brenner D, Williamson SJ, Kaufman L. Visually evoked magnetic fields of the human brain. Science 1975;190:480–482.
146. Supek S, Aine CJ, Ranken D, Best E, Flynn ER, Wood CC. Single vs. paired visual stimulation: superposition of early

neuromagnetic responses and retinotopy in extrastriate cortex in humans. Brain Res 1999;830:43–55.

147. Fylan F, Holliday IE, Singh KD, Anderson SJ, Harding GF. Magnetoencephalographic investigation of human cortical area V1 using color stimuli. Neuroimage 1997;6:47–57.

148. Singh KD, Barnes GR, Hillebrand A, Forde EM, Williams AL. Task-related changes in cortical synchronization are spatially coincident with the hemodynamic response. Neuroimage 2002;16:103–114.

149. Anderson SJ, Holliday IE, Singh KD, Harding GF. Localization and functional analysis of human cortical area V5 using magneto-encephalography. Proc R Soc London Sev B Biol Sci 1996;263:423–431.

150. Maruyama K, Kaneoke Y, Watanabe K, Kakigi R. Human cortical responses to coherent and incoherent motion as measured by magnetoencephalography. Neurosci Res 2002;44:195–205.

151. Anderson SJ, Holliday IE, Harding GF. Assessment of cortical dysfunction in human strabismic amblyopia using magnetoencephalography (MEG). Vision Res 1999;39:1723–1738.

152. Reite M, Edrich J, Zimmerman JT, Zimmerman JE. Human magnetic auditory evoked fields. Electroencephalogr Clin Neurophysiol 1978;45:114–117.

153. Romani GL, Williamson SJ, Kaufman L, Brenner D. Characterization of the human auditory cortex by the neuromagnetic method. Exp Brain Res 1982;47:381–393.

154. Pantev C, Hoke M, Lehnertz K, Lutkenhoner B, Anogianakis G, Wittkowski W. Tonotopic organization of the human auditory cortex revealed by transient auditory evoked magnetic fields. Electroencephalogr Clin Neurophysiol 1988;69: 160–170.

155. Pantev C, Lutkenhoner B. Magnetoencephalographic studies of functional organization and plasticity of the human auditory cortex. J Clin Neurophysiol 2000;17:130–142.

156. Roberts TP, Ferrari P, Stufflebeam SM, Poeppel D. Latency of the auditory evoked neuromagnetic field components: stimulus dependence and insights toward perception. J Clin Neurophysiol 2000;17:114–129.

157. Weinberg H, Cheyne D, Brickett P, Harrop R, Gordon R. An interaction of cortical sources associated with simultaneous auditory and somatosensory stimulation. In: Pfurtscheller G, Lopes da Silva FH, editors. Functional Brain Imaging. Lewiston, N.Y.: Hans Huber Publishers; 1988. p 83–88.

158. Ribary U, Ioannides AA, Singh KD, Hasson R, Bolton JP, Lado F, Mogilner A, Llinas R. Magnetic field tomography of coherent thalamocortical 40-Hz oscillations in humans. Proc Natl Acad Sci USA 1991;88:11037–11041.

159. Ross B, Picton TW, Pantev C. Temporal integration in the human auditory cortex as represented by the development of the steady-state magnetic field. Hear Res 2002;165:68–84.

160. Starr A, Kristeva R, Cheyne D, Lindinger G, Deecke L. Localization of brain activity during auditory verbal short-term memory derived from magnetic recordings. Brain Res 1991;558:181–190.

161. Mecklinger A, Maess B, Opitz B, Pfeifer E, Cheyne D, Weinberg H. A MEG analysis of the P300 in visual discrimination tasks. Electroencephalogr Clin Neurophysiol 1998;108:45–56.

162. Alho K. Cerebral generators of mismatch negativity (MMN) and its magnetic counterpart (MMNm) elicited by sound changes. Ear Hear 1995;16:38–51.

163. Halgren E, Raij T, Marinkovic K, Jousmaki V, Hari R. Cognitive response profile of the human fusiform face area as determined by MEG. Cereb Cortex 2000;10:69–81.

164. Salmelin R, Hari R, Lounasmaa OV, Sams M. Dynamics of brain activation during picture naming. Nature (London) 1994;368:463–465.

165. Sams M, Aulanko R, Hamalainen M, Hari R, Lounasmaa OV, Lu ST, Simola J. Seeing speech: visual information from lip movements modifies activity in the human auditory cortex. Neurosci Lett 1991;127:141–145.

166. Pulvermuller F, Shtyrov Y, Ilmoniemi R. Spatiotemporal dynamics of neural language processing: an MEG study using minimum-norm current estimates. Neuroimage 2003;20:1020–1025.

167. Pylkkanen L, Marantz A. Tracking the time course of word recognition with MEG. Trends Cogn Sci 2003;7:187–189.

168. Roberts TP, Ferrari P, Poeppel D. Latency of evoked neuromagnetic M100 reflects perceptual and acoustic stimulus attributes, Neuroreport 1998;9:3265–3269.

169. Helenius P, Salmelin R, Service E, Connolly JF. Semantic cortical activation in dyslexic readers. J Cogn Neurosci 1999;11:535–550.

170. Salmelin R, Schnitzler A, Schmitz F, Jancke L, Witte OW, Freund HJ. Functional organization of the auditory cortex is different in stutterers and fluent speakers. Neuroreport 1998;9:2225–2229.

171. Tallon-Baudry C, Bertrand O. Oscillatory gamma activity in humans and its role in object representation. Trends Cogn Sci 1999;3:151–162.

172. Nishitani N, Hari R. Temporal dynamics of cortical representation for action. Proc Natl Acad Sci USA 2000;97:913–918.

173. Varela F, Lachaux JP, Rodriguez E, Martinerie J. The brainweb: phase synchronization and large-scale integration. Nat Rev Neurosci 2001;2:229–239.

174. Gallen CC, Sobel DF, Waltz T, Aung M, Copeland B, Schwartz BJ, Hirschkoff EC, Bloom FE. Noninvasive presurgical neuromagnetic mapping of somatosensory cortex. Neurosurgery 1993;33:260–268; discussion 268.

175. Papanicolaou AC, Simos PG, Castillo EM, Breier JI, Sarkari S, Pataraia E, Billingsley RL, Buchanan S, Wheless J, Maggio V, Maggio WW. Magnetocephalography: a noninvasive alternative to the Wada procedure. J Neurosurg 2004;100:867–876.

176. Naatanen R, Lehtokoski A, Lennes M, Cheour M, Huotilainen M, Iivonen A, Vainio M, Alku P, Ilmoniemi RJ, Luuk A, Allik J, Sinkkonen J, Alho K. Language-specific phoneme representations revealed by electric and magnetic brain responses. Nature (London) 1997;385:432–434.

177. Bowyer SM, Moran JE, Mason KM, Constantinou JE, Smith BJ, Barkley GL, Tepley N. MEG localization of language-specific cortex utilizing MR-FOCUSS. Neurology 2004;62: 2247–2255.

178. Firsching R, Bondar I, Heinze HJ, Hinrichs H, Hagner T, Heinrich J, Belau A. Practicability of magnetoencephalography-guided neuronavigation. Neurosurg Rev 2002; 25:73–78.

179. Ganslandt O, Fahlbusch R, Nimsky C, Kober H, Moller M, Steinmeier R, Romstock J, Vieth J. Functional neuronavigation with magnetoencephalography: outcome in 50 patients with lesions around the motor cortex. J Neurosurg 1999;91:73–79.

180. Rosenow F, Luders H. Presurgical evaluation of epilepsy. Brain 2001;124:1683–1700.

181. Stefan H, Hummel C, Scheler G, Genow A, Druschky K, Tilz C, Kaltenhauser M, Hopfengartner R, Buchfelder M, Romstock J. Magnetic brain source imaging of focal epileptic activity: a synopsis of 455 cases. Brain 2003.

182. Barkley GL. Controversies in neurophysiology. MEG is superior to EEG in localization of interictal epileptiform activity. Pro Clin Neurophysiol 2004;115:1001–1009.

183. Baumgartner C. Controversies in clinical neurophysiology. MEG is superior to EEG in the localization of interictal epileptiform activity: Con. Clin Neurophysiol 2004;115: 1010–1020.

184. Otsubo H, Snead III OC. Magnetoencephalography and magnetic source imaging in children. J Child Neurol 2001;16:227–235.
185. Stefan H, Hummel C, Hopfengartner R, Pauli E, Tilz C, Ganslandt O, Kober H, Moler A, Buchfelder M. Magnetoencephalography in extratemporal epilepsy. J Clin Neurophysiol 2000;17:190–200.
186. Baumgartner C, Pataraia E, Lindinger G, Deecke L. Magnetoencephalography in focal epilepsy. Epilepsia 2000;41 (Suppl 3): S39–47.
187. de Jongh A, Baayen JC, de Munck JC, Heethaar RM, Vandertop WP, Stam CJ. The influence of brain tumor treatment on pathological delta activity in MEG. Neuroimage 2003;20:2291–2301.
188. Taniguchi M, Kato A, Ninomiya H, Hirata M, Cheyne D, Robinson SE, Maruno M, Saitoh Y, Kishima H, Yoshimine T. Cerebral motor control in patients with gliomas around the central sulcus studied with spatially filtered magnetoencephalography. J Neurol Neurosurg Psychiat 2004;75: 466–471.
189. Schiffbauer H, Ferrari P, Rowley HA, Berger MS, Roberts TP. Functional activity within brain tumors: a magnetic source imaging study. Neurosurgery 2001;49:1313–1320; discussion 1320–1311.
190. Gallen CC, Tecoma E, Iragui V, Sobel DF, Schwartz BJ, Bloom FE. Magnetic source imaging of abnormal low-frequency magnetic activity in presurgical evaluations of epilepsy. Epilepsia 1997;38:452–460.
191. Rossini PM, Tecchio F, Pizzella V, Lupoi D, Cassetta E, Pasqualetti P, Paqualetti P. Interhemispheric differences of sensory hand areas after monohemispheric stroke: MEG/MRI integrative study. Neuroimage 2001;14:474–485.
192. Gallien P, Aghulon C, Durufle A, Petrilli S, De Crouy AC, Carsin M, Toulouse P. Magnetoencephalography in stroke: a 1-year follow-up study. Eur J Neurol 2003;10: 373–382.
193. Lewine JD, Davis JT, Sloan JH, Kodituwakku PW, Orrison Jr. WW. Neuromagnetic assessment of pathophysiologic brain activity induced by minor head trauma. Am J Neuroradiol 1999;20:857–866.
194. Bowyer SM, Aurora KS, Moran JE, Tepley N, Welch KM. Magnetoencephalographic fields from patients with spontaneous and induced migraine aura. Ann Neurol 2001;50:582–587.
195. Tran TD, Inui K, Hoshiyama M, Lam K, Qiu Y, Kakigi R. Cerebral activation by the signals ascending through unmyelinated C-fibers in humans: a magnetoencephalographic study. Neuroscience 2002;113:375–386.
196. Inui K, Tran TD, Qiu Y, Wang X, Hoshiyama M, Kakigi R. Pain-related magnetic fields evoked by intra-epidermal electrical stimulation in humans. Clin Neurophysiol 2002;113: 298–304.
197. Kamada K, Moller M, Saguer M, Ganslandt O, Kaltenhauser M, Kober H, Vieth J. A combined study of tumor-related brain lesions using MEG and proton MR spectroscopic imaging. J Neurol Sci 2001;186:13–21.
198. Reite M, Teale P, Rojas DC. Magnetoencephalography: applications in psychiatry. Biol Psychiat 1999;45:1553–1563.
199. Pekkonen E, Hirvonen J, Jaaskelainen IP, Kaakkola S, Huttunen J. Auditory sensory memory and the cholinergic system: implications for Alzheimer's disease. Neuroimage 2001;14:376–382.
200. Nishitani N, Avikainen S, Hari R. Abnormal imitation-related cortical activation sequences in Asperger's syndrome. Ann Neurol 2004;55:558–562.
201. Hren R, Zhang X, Stroink G. Comparison between electrocardiographic and magnetocardiographic inverse solutions using the boundary element method. Med Biol Eng Comput 1996;34:110–114.
202. Fenici R, Melillo G. Magnetocardiography: ventricular arrhythmias. Eur Heart J 1993;14(Suppl E): 53–60.
203. Stroink G, Moshage W, Achenbach S. Cardiomagnetism. In: Andrä W, Nowak H, editors. Magnetism in Medicine: A Handbook. Berlin: Wiley; 1998. p 136–189.
204. Tavarozzi I, Comani S, Del Gratta C, Di Luzio S, Romani GL, Gallina S, Zimarino M, Brisinda D, Fenici R, De Caterina R. Magnetocardiography: current status and perspectives. Part II: Clinical applications. Ital Heart J 2002;3:151–165.
205. Fenici R, Brisinda D, Nenonen J, Fenici P. Noninvasive study of ventricular preexcitation using multichannel magnetocardiography. Pacing Clin Electrophysiol 2003;26: 431–435.
206. Kanzaki H, Nakatani S, Kandori A, Tsukada K, Miyatake K. A new screening method to diagnose coronary artery disease using multichannel magnetocardiogram and simple exercise. Basic Res Cardiol 2003;98:124–132.
207. Leder U, Pohl HP, Michaelsen S, Fritschi T, Huck M, Eichhorn J, Muller S, Nowak H. Noninvasive biomagnetic imaging in coronary artery disease based on individual current density maps of the heart. Int J Cardiol 1998; 64:83–92.
208. Blum T, Saling E, Bauer R. First magnetoencephalographic recordings of the brain activity of a human fetus. Br J Obstet Gynaecol 1985;92:1224–1229.
209. Kariniemi V, Ahopelto J, Karp PJ, Katila TE. The fetal magnetocardiogram. J Perinat Med 1974;2:214–216.
210. Lowery CL, Campbell JQ, Wilson JD, Murphy P, Preissl H, Malak SF, Eswaran H. Noninvasive antepartum recording of fetal S-T segment with a newly developed 151-channel magnetic sensor system. Am J Obstet Gynecol 2003;188: 1491–1496; discussion 1496–1497.
211. Wakai RT, Leuthold AC, Martin CB. Atrial and ventricular fetal heart rate patterns in isolated congenital complete heart block detected by magnetocardiography. Am J Obstet Gynecol 1998;179:258–260.
212. Quartero HW, Stinstra JG, Golbach EG, Meijboom EJ, Peters MJ. Clinical implications of fetal magnetocardiography. Ultrasound Obstet Gynecol 2002;20:142–153.
213. Kahler C, Schleussner E, Grimm B, Schneider U, Haueisen J, Vogt L, Seewald HJ. Fetal magnetocardiography in the investigation of congenital heart defects. Early Hum Dev 2002;69:65–75.
214. Van Leeuwen P. Future topics in fetal magnetocardiography. In: Nenonen J, Ilmoniemi R, Katila T, editors. Biomag 2000: Proc 12th Int Conf Biomag. Espoo, Finland: Helsinki University of Technology; 2001. p 587–590.
215. Lengle JM, Chen M, Wakai RT. Improved neuromagnetic detection of fetal and neonatal auditory evoked responses. Clin Neurophysiol 2001;112:785–792.
216. Schneider U, Schleussner E, Haueisen J, Nowak H, Seewald HJ. Signal analysis of auditory evoked cortical fields in fetal magnetoencephalography. Brain Topogr 2001;14:69–80.
217. Schleussner E, Schneider U, Olbertz D, Kahler R, Huonker R, Michels W, Nowak H, Seewald HJ. Assessment of the fetal neuronal maturation using auditory evoked fields in fetal magnetoencephalography. In: Yoshimoto T, Kotani M, Kuriki S, Karibe H, Nakasato N, editors. Recent Advances in Biomagnetism. Sendai: Tohoku University Press; 1999. p 975–977.

218. Lowery C, Robinson S, Eswaran H, V. J, H. G, Cheung T. Detection of the transient and steady-state auditory evoked responses in the human fetus. In: Yoshimoto T, Kotani M, Kuriki S, Karibe H, Nakasato N, editors. Recent Advances in Biomagnetism. Sendai: Tohoku University Press; 1999. p 963–966.
219. Rose D, Eswaran H. Spontaneous neuronal activity in fetuses and newborns. Exp Neurol, in press.
220. Eswaran H, Wilson J, Preissl H, Robinson S, Vrba J, Murphy P, Rose D, Lowery C. Magnetoencephalographic recordings of visual evoked brain activity in the human fetus. Lancet 2002;360:779–780.
221. Vrba J, Robinson SE, McCubbin J, Murphy P, Eswaran H, Wilson JD, Preissl H, Lowery CL. Human fetal brain imaging by magnetoencephalography: verification of fetal brain signals by comparison with fetal brain models. Neuroimage 2004;21:1009–1020.
222. Paulson DN, Fagaly RL, Toussaint RM, Fischer F. Biomagnetic susceptometry with SQUID instrumentation. IEEE Trans Mag 1991;27:3249–3252.
223. Brittenham GM, Sheth S, Allen CJ, Farrell DE. Noninvasive methods for quantitative assessment of transfusional iron overload in sickle cell disease. Semin Hematol 2001; 38: 37–56.
224. Hoshiyama M, Kakigi R, Nagata O. Peripheral nerve conduction recorded by a micro gradiometer system (micro-SQUID) in humans. Neurosci Lett 1999;272:199–202.
225. Mackert BM, Curio G, Burghoff M, Trahms L, Marx P. Magnetoneurographic 3D localization of conduction blocks in patients with unilateral S1 root compression. Electroencephalogr Clin Neurophysiol 1998;109:315–320.
226. Le Gros V, Lemaigre D, Suon C, Pozzi JP, Liot F. Magnetopneumography: a general review. Eur Respir J 1989;2: 149–159.
227. Huvinen M, Oksanen L, Kalliomaki K, Kalliomaki PL, Moilanen M. Estimation of individual dust exposure by magnetopneumography in stainless steel production. Sci Total Environ 1997;199:133–139.
228. Moller W, Barth W, Kohlhaufl M, Haussinger K, Stahlhofen W, Heyder J. Human alveolar long-term clearance of ferromagnetic iron oxide microparticles in healthy and diseased subjects. Exp Lung Res 2001;27:547–568.
229. Moraes R, Toncon LE, Baffa O, Oba-Kunyioshi AS, Wakai RT, Leuthold AC. Adaptive, autoregressive spectral estimation for analysis of electrical signals of gastric origin. Physiol Meas 2003;24:91–106.
230. Kosch O, Osmanoglou E, Hartman V, Strenzke A, Weitschies W, Wiedenmann B, Monnikes H, Trahms L. Investigation of gastrointestinal transport by magnetic marker localization. Biomed Tech (Berl) 2002;47(Suppl 1, Pt 2): 506–509.

See also ELECTROCARDIOGRAPHY, COMPUTERS IN; ELECTROENCEPHALOGRAPHY; EVOKED POTENTIALS; PULMONARY PHYSIOLOGY.

BIOMATERIALS, ABSORBABLE

MARK BORDEN
Director of Biomaterials
Research
Irvine, California

INTRODUCTION

Historically, the use of implants in orthopedic surgery has originated from fracture repair and joint replacement applications. During the late 1920s, stainless-steel bone implants such as Kirshner nails and Steinman pins were popularized for the surgical treatment of fractures (1). With the introduction of new surgical materials such as cobalt alloys, polyethylene and poly(tetrafluoroethylene) [Teflon], surgeons and engineers began working toward the design and fabrication of artificial joints. The advent of new high strength implant materials allowed researchers such Dr. John Charnley to begin pioneering work in total hip replacement surgery in the late 1930s (1,2). As advances in chemistry, metallurgy, and ceramics progressed throughout the years, a large variety of implants have entered the orthopedic market. Today, orthopedic implants are composed of specialized metals, ceramics, polymers, and composites that possess a large range in properties. Although these materials have been successfully fabricated into a variety of implants, one common issue has remained. Once the device has performed its required function and is no longer needed, it remains as a bystander in the now healthy tissue. The issue is that the long-term presence of an implant in the body can result in implant-related complications such as loosening, migration, mechanical breakdown and fatigue, generation of wear particles, and other negative effects (3–6). With prolonged patient life spans and higher activity levels, more and more people are now outliving the lifetime of their implants.

The potential for long-term implant problems has driven researchers to look to a unique category of materials that are capable of being completely resorbed by the body. These bioresorbable or biodegradable materials are characterized by the ability to be chemically broken down into harmless byproducts that are metabolized or excreted by the body. Materials of this type offer a great advantage over conventional nonresorbable implant materials. Bioresorbable implants provide their required function until the tissue is healed, and once their role is complete, the implant is completely resorbed by the body. The end result is healthy tissue with no signs that an implant was ever present. As the implant is completely gone from the site, long-term complications associated with nonresorbable devices do not exist.

ORTHOPEDIC APPLICATIONS OF RESORBABLE IMPLANTS

The ability of a resorbable implant to provide temporary fixation followed by complete resorption is a desirable property for a large variety of surgical applications. In relation to orthopedic surgery, this behavior is particularly useful based on the goal of restoring physiological function to the tissues and joints of the skeleton. In general, orthopedic surgery is often compared with carpentry in that the surgeon's instruments often consist of hammers, drills, and saws. Similar to carpentry, specialized screws, plates, pins, and nails are used to fix one material to another. In orthopedics, this fixation can be categorized into two main areas: bone-to-bone fixation and soft tissue-to-bone fixation. Bone fixation is used in the treatment of complex fractures and in reconstructive procedures of the skeleton. The implants used in these surgeries are designed to maintain the position of the bone fragments, to stabilize the site, and to allow for eventual fusion of the fracture. As a result of the fracture healing process, the bone is remodeled so effectively that it is often difficult to locate the initial injury. With nonresorbable implants, the long-term presence of the device only serves as a source for potential complications. Resorbable implants, on the other hand, alleviate this concern by fully resorbing and allowing the bone to completely remodel into its normal physiological state.

In addition to bone fixation, soft tissue fixation is also an excellent application of resorbable implants. This type of reconstruction is often the result of trauma to joints such as the knee and shoulder. Typically developing from sports injuries or accidents, the goal is to restore stability to the joint by replacing or reconstructing the ligament or tendon interface to bone. In the knee, for example, the reconstruction of a torn anterior cruciate ligament (ACL) is a common sports medicine procedure. This type of surgical reconstruction consists of replacing the torn ACL with a bone-tendon-bone graft taken from the patient's patella and fixing the graft across the joint. During the procedure, the bony portion of the ACL graft is fixed in bone tunnels drilled into the tibia and femur. In order to stabilize the graft and aid in the formation of a stable bone-to-ligament interface, interference screws are used to fix the graft to the site. Once bone has been incorporated into the graft, the device is no longer needed.

Another example of soft tissue reconstruction is the repair of a tear in the rotator cuff tendon of the shoulder. This type of injury requires reestablishing the tendon-to-bone interface. To facilitate this process and restore stability to the shoulder, implants called suture anchors are used to provide a means to affix the torn tendon to the bone of the humerous. Just as the name describes, these implants function by providing an anchor in bone that allows the attached suture to tighten down on the tendon and pull it in contact with bone. As healing progresses, a stable interface develops and joint function is restored. Similar to other fixation applications, once the interface has fully healed, the implant is no longer needed.

FUNCTION OF A RESORBABLE IMPLANT

As seen from the various types of tissue fixation procedures within orthopedic surgery, resorbable implants are exposed to a variety of healing environments. Out of the currently used materials in orthopedic surgery, only the polymer and ceramic groups contain resorbable biomaterials. It is the specific properties of these materials that allow them to be used as resorbable devices. In evaluating a material for potential use as an implant, the key properties include implant biocompatibility, resorbability, and mechanical properties. The first criteria, biocompatibility, refers to the ability of the material to be implanted into the body without negatively affecting the surrounding tissue, which includes the absence of inflammation, toxicity (materials that kill surrounding cells), carcinogenicity (materials that can cause cancer), genotoxicicty (materials that damage the DNA of surrounding cells), and mutagenicity (materials that cause genetic mutations within the cell). More specifically related to bone, the implant must also be osteocompatible, which means the material does not interfere with the normal bone healing process (7).



Figure 1. Optimal stress transfer profile for resorbable implants demonstrating the load-sharing properties of the implant.

Although biocompatibility has a direct effect on how the tissue surrounding the device heals and is an important property of the implant, the main criteria related to implant function are the resorbability and mechanical properties. Once the device is implanted, it provides immediate mechanical stabilization to the site while the tissue heals. As the regenerating bone, ligaments, or tendons become stronger over time, the implant site becomes less dependent on the device and more dependent on the healing tissue. This concept is shown in Fig. 1. In this situation, the implant provides all of the mechanical support immediately following placement. As the device begins to degrade, the mechanical properties decrease over time and are gradually transferred to the new tissue. During this period, the regenerating tissue responds to the gradual loads and begins to remodel and become stronger. In the healing of musculoskeletal tissue, the sharing of the load between the implant and the tissue results in further regeneration. Once healing is complete, the load is fully transitioned to the tissue, which is now mechanically independent from the implant. Upon final resorption of the device, the site is left fully functional and entirely free of any implant material.

The ability to gradually transfer load to regenerating tissue is an important part of the musculoskeletal healing process. This characteristic is only found in resorbable materials. Although metallic implants offer effective load-bearing properties in applications such as joint replacement and certain spinal surgeries, these high strength materials do not resorb and do not effectively transfer loads to the implant site. Due to the high strength of metals, these implants bear the majority of the force at the site and can shield the surrounding tissues from any load. This phenomenon is called stress shielding and can actually cause bone to resorb in certain areas around the implant (8,9). The stress-shielding effect is based on a concept called Wolff's Law, which describes the ability of bone to dynamically respond to the presence or lack of stress by changing its density and strength.

When bone is subjected to new loads, the additional stress stimulates bone formation and the tissue increases in strength and density. When the remodeling process is complete, the stronger tissue can now fully support the added load. However, when a high strength material such as metal is placed in bone, the bone surrounding the implant is shielded from the normal stresses, which results in a decrease in the strength and density of this tissue and possible bone resorption. This phenomenon can cause complications such as implant loosening or fracture of the implant site. Polymer and ceramic materials, on the other hand, have mechanical properties that are similar to bone, which allows them to share the stresses with newly regenerating tissue thereby preventing resorption and other stress-shielding complications (10–12).

Although load transfer and strength retention are common properties of all resorbable implants, not all surgical sites heal at the same rate. In fracture fixation applications where bone-to-bone contact is maintained, healing can be as short as 6–8 weeks. However, in applications such as spinal fusion where significant amounts of tissue need to be formed in the intervertebral space, the healing process can take up to 6–12 months. Based on the dependence of implant function on the surgical site, the material choice becomes an important part of implant development. The challenge in designing an implant lies in choosing a material that correctly matches the function and strength requirements of the surgical application, which can be accomplished through a thorough understanding of the function of the implant, the load requirements of the implant site, and the properties of the material.

RESORBABLE POLYMERS

One of the most versatile materials used in orthopedic surgery are polymers. Polymers are a group of materials that are produced through a chemical reaction that results in a long chain of repeating molecules called monomers. In addition to polymers composed of a single monomer repeating unit, there are other materials, called copolymers, that have two or more monomer repeating units. By combining different monomers, the properties of the resultant copolymer can be specifically modified to serve a certain purpose. This versatility can also be achieved by modifying the polymerization reaction and the postprocessing techniques used to create polymer implants. Table 1 shows a few examples of the many properties that characterize polymers. These characteristics can be altered by changing the molecular weight, chemical structure, and morphology of the polymer or copolymer.

Table 1. Range of Common Properties Found in Orthopedic Polymers

Property	Range	
Resorbability	Fully Resorbable	Nonresorbable
Strength	Low Strength	High Strength
Moldability	Flexible	Rigid
Physical State	Gel/Liquid	Solid
Temperature Sensitivity	Flexible at higher Temperature	Rigid at all Temperatures
Radiation Resistance	Low	High

The molecular weight of a polymer is a measurement of the number of repeating units found in the entire molecule. During the formation of polymers and copolymers, the length of the molecule can be controlled to give a variety of molecular weights. The length of the polymer chain can be as small as a few thousand repeating units or as large as a million, which can have a significant effect on the degradation properties of the polymer. When a polymer breaks down, it occurs through random cleavage of the chemical bonds along the polymer chain. It is not until the polymer finally fragments into its monomer form that the material is absorbed by the surrounding tissue. Therefore, longer polymers chains with higher molecular weights will take a longer time to degrade because more bonds exist to the cleaved.

Additionally, the chemical structure can also affect degradation. As described previously, the backbone of a polymer consists of a long, continuous chain of monomer units linked together. In all resorbable polymers, it is the backbone of the polymer where degradation occurs. The typical linkage that allows polymers to break down is a carbon–oxygen–carbon (C-O-C) bond. This bond is found in ester, carbonate, carboxylic acid, and amide-based polymers. The degradation process occurs at this bond when the material is exposed to water. In a process called hydrolytic degradation, water molecules chemically react with the C-O-C bonds causing them to break apart at random areas throughout the polymer chain. The chemical structure of the polymer dictates the ability of the water molecules to access these bonds and start the degradation reaction. If the polymer is characterized by large bulky side chains or strong C-O-C bonds, it becomes difficult for the water molecule to penetrate the polymer chains to react with the backbone, which results in a prolonged degradation period. The opposite is true for polymers that tend to absorb water and do not have any large side chains. In these polymers, the water molecules can easily access the backbone and the degradation process proceeds at a relatively fast rate.

The final characteristic that can affect the degradation and strength of a polymer is the morphology. The morphology of the polymer refers to the orientation of the long polymer chains throughout the material. Polymer morphology can be classified into three groups: crystalline polymers, semicrystalline polymers, and amorphous polymers. The crystallinity of a polymer develops from areas within the material where the polymer chains are aligned and tightly packed together. This type of orientation forms dense crystalline regions within the random arrangement of the polymer chains. A highly organized polymer is considered crystalline, whereas a completely random orientation is considered amorphous. Semicrystalline polymers fall between these two extremes and exist with varying degrees of crystallinity (Fig. 2).

The effect of crystallinity on the degradation of the polymer is due to the tight orientation between the polymer chains in the crystalline regions. With highly crystalline



Figure 2. Semicrystalline polymer showing orientation of amorphous regions and crystalline regions.

polymers, the degradation rate is very slow due to the difficulty of water gaining access to the C-O-C bonds. These polymers degrade at a rate much slower than polymers that are completely amorphous with no crystalline regions (13). The crystallinity also affects the mechanical properties of the polymer. The dense, organized areas within crystalline polymer make these regions stronger than the unorganized, amorphous regions. As a result, an increase in crystallinity translates into an increase in mechanical properties.

The ability to alter the properties of a polymer has resulted in thousands of different materials used in a wide range of applications. However, only a few of these polymers can be effectively used as medical implants due to the strict requirements of surgical implants. The following sections describe some of the polymers currently used in orthopedic surgery.

Poly(hydroxy acids)

Poly(hydroxy acids) were the first group of resorbable materials to be used in surgery (14). The main polymers in this family are poly(lactic acid) (PLA), poly(glycolic acid) (PGA), and the copolymer poly(lactide-*co*-glycolide) (PLG). The basic chemical structure of these materials in shown in Fig. 3. Originally, PLA and PGA were initially used as a degradable sutures (15–18). However, since their initial success in the wound closure field, both of these polymers have been fabricated into several orthopedic implants including screws (19,20), plates (19,21), pins (22–25), suture anchors (26), and bone grafting scaffolds (27–30). In addition, several new devices composed of the PLG copolymer have been developed over the past 10 years (31–35).

Although the chemical structure of PLA and PGA is somewhat similar, the presence of a methyl group (–CH_3) in PLA significantly changes its physical properties compared with PGA. Comparatively, PGA has a lower strength and degrades in approximately 3–6 months, whereas certain forms of PLA can take 3–5 years to fully degrade. Although only a single methyl group differentiating PLA from PGA exists, the location of this side group close to the C-O-C bond makes it difficult for the water molecules to gain access to cleavage site, thereby prolonging degradation.



POLY (LACTIC ACID)



POLY (GLYCOLIC ACID)



POLY (LACTIDE-*co*-GLYCOLIDE)

Figure 3. Chemical structure of poly(lactic acid), poly(glycolic acid), and the copolymer poly(lactide-*co*-glycolide).

In addition, the methyl group in PLA also gives the polymer a unique chemical orientation. As a monomer, lactic acid is a molecule that can have two different molecular orientations: L-lactic acid and D-lactic acid. These isomers are based on the orientation of the methyl and hydrogen groups on the molecule. Figure 4 shows the chiral nature of the lactic acid molecule and the resulting stereoregular polymers: poly(L-lactic acid) (PLLA), poly (D-lactic acid (PDLA), and poly (D,L-lactic acid) (PDLLA). Although three forms of PLA exist, in the medical field, poly(L-lactic acid) is used more often than poly(D-lactic acid) because the degradation product is the same as naturally occurring L-lactic acid (13).

Using the various forms of PLA, polymers with significantly different properties can be synthesized. The effect of the starting isomer on the physical properties of the material is dramatically seen in the properties of PLLA and PDLLA. In Fig. 4, the chemical structure of poly (L-lactic acid) is represented by a long chain with all of the –CH_3 groups on one side. This uniformity allows the chains to pack tightly together resulting in a highly crystalline material that has a high strength and long degradation period (3–5 years). Poly(D,L lactic acid), on the other hand, is characterized by either a random or alternating arrangement of the –CH_3 groups and –H groups. This molecule orientation prevents the polymer chains from packing together, resulting in a completely amorphous polymer with a lower strength and shorter degradation profile (9–12 months). In addition, the polymerization of L-lactic acid and D,L-lactic acid together results in a copolymer with properties in between PLLA and PDLLA. In recent years, the 70:30 combination of poly(L/D,L lactic acid) has gained popularity in orthopedic applications due to its ability to retain its strength for 9–12 months while being completely resorbed within 1.5–2 years (36–38). This copolymer appears to provide the best



Figure 4. The optically active center in lactic acid is allows it to have two different molecular orientations. These orientations result in three types of stereoregular polymers.

of both worlds in that it has the strength retention of PLLA but has a degradation period only slightly longer than PDLLA.

In addition to the lactic acid-based copolymers, a combination of PLA and PGA has also been shown to be an effective implant material (31–35). Due to the large differences in the degradation properties of PLA and PGA, the poly(lactide-*co*-glycolide) (PLG) copolymer can be modified based on the PLA to PGA ratio to provide varying degradation periods. Common PLG copolymers used in orthopedic surgery have PLA/PGA ratios of 50:50, 75:25, and 85:15. This combination not only provides both slow and fast resorbing monomer units but also eliminates any crystallinity, making the copolymer completely amorphous. These materials have been commonly used as fracture implants due to the shorter 6–12 month degradation period.

Although PLA and PGA polymers have been successfully used in patients for several years, there have been certain cases where the abundance of acidic monomers at the site has caused inflammation and bone resorption (39–48). When PLA and PGA polymers near the end of degradation, they release lactic acid and glycolic acid, respectively. Although these degradation products can be metabolized by the body, if the surrounding tissue cannot absorb the acid in a timely manner, the build up of acid and resultant drop in pH at the implant site can cause bone to resorb. Historically, this effect has mainly been seen in the fast-resorbing PGA implants; however, a few cases have been reported with PLA (43,46,49,50). Although the bone resorption complication is detrimental to the healing of the implant site, the complication rate has been relatively low. In a review of over 2000 patients by Bostman, only 5% of the patients have shown implant-associated reactions (44).

Additionally, the copolymers PLG and PLDLLA have been shown to possess a more osteocompatible degradation profile due to a gradual release of the acidic byproducts (36,51–56), which has minimized acid dumping and the associated bone resorption complications. In a study by Eppley et al. (35), 1883 patients treated with PLG plates and screws for bone fixation in craniofacial procedures showed an implant-related complication rate of only 0.5%, which was well below the 5% rate reported by Bostman for PGA and PLA implants. Overall, the PLG and PLDLLA copolymers have been shown to be effective devices for fracture fixation, bone graft containment, and soft tissue fixation, and have begun to replace the outdated PLA and PGA devices (37,38,57,58).

Polycarbonates

Another group of resorbable polymers are the polycarbonates. Although the majority of the polymers and copolymers within the polycarbonate family are nonresorbable plastics used for industrial applications, a select few exist that are resorbable and can be used as orthopedic implants. One group of medical-grade polycarbonates are the copolymers based off of poly(trimethylene-carbonate) (PTMC) and poly(glycolic acid) or poly(lactic acid). These combinations offer the combined advantage of the processing versatility of PTMC and the resorbability and strength of PLA and PGA. The PTMC copolymers have been used for soft tissue fixation in shoulder surgery as suture anchors and soft tissue tacks (59–61).

Although the PTMC copolymers with PGA and PLA offer improved implant properties compared with PTMC alone, the degradation of the material still produces acidic monomers. In order to avoid the issues with glycolic acid- and lactic acid-based polymers and copolymers, an amino acid-based polycarbonate was developed by Joachim Kohn at Rutgers University. Designed specifically for orthopedic applications, the amino acid poly(carbonates) combine the biocompatibility of individual amino acids with the strength and processability of standard industrial poly(carbonates) (62–64). One such promising polymer, poly(DTE carbonate), is derived from the amino acid tyrosine and has been shown to have excellent strength-retention properties, an optimal degradation profile, and biocompatible degradation products (65–68). Based on large amount of characterization data, a material safety file has been recently established at the U.S. Food and Drug Administration (FDA) that allows manufacturers to begin development of poly(DTE carbonate) implants. Due to the advantages of poly(DTE carbonate) over conventional resorbable polymers, amino acid-based poly(carbonate) implants may soon be a common sight in orthopedic operating rooms.

Other Resorbable Polymers

In addition to the widely used PLA and PGA polymers and the up-and-coming amino acid-based poly(carbonates), several other polymers have applications as medical devices. Although not specifically used in orthopedics, the poly(anhydride) family of polymers developed by Robert Langer at MIT has been effectively used as drug-delivery vehicles (69–73). The function of these resorbable implants is to provide a sustained and controlled release of drugs to a specific implant site. The device functions by releasing molecules entrapped within the implant as it degrades. Another polymer, poly(dioxanone), has been used as a resorbable suture material for several years (74–80). The flexibility of this polymer enables it to be used as a monofilament suture instead of the typical braided fiber of PGA, which provides the suture with an improved ability to move through tissue with less friction, thereby minimizing the tearing and pulling of the surrounding areas (81,82). Looking specifically at orthopedic applications, additional polymers currently in development include poly(caprolactone) (83–86), poly(hydroxybutyrate) (87–89), polyurethanes (90–93), and poly(phosphazenes) (94–96).

RESORBABLE CALCIUM CERAMICS

Aside from the polymers, the other group of resorbable implant materials are the calcium-based ceramics. Due to the similarity of these materials with the mineral content of bone, hydroxyapatite [$Ca_{10}(PO_4)_6(OH)_2$], calcium ceramics are highly biocompatible and osteocompatible materials that have a long history of clinical use. These materials are typically used in orthopedic surgery to fill voids in bone as self-setting cements or as porous blocks and granules.

Calcium Sulfate

One the first materials to ever be used as a filler for bone defects was calcium sulfate (Plaster of Paris) (97). In its dehydrated form (calcium sulfate hemihydrate), this material undergoes a chemical reaction when mixed with water that allows it to function as a resorbable cement. As the cement reacts, it transforms from a slurry, to a paste, to a dough, and then fully sets into its final hardened form (calcium sulfate dihydrate). This reaction is exothermic in that it produces heat; however, the increase in temperature is only slightly above body temp (37 °C). Figure 5 shows a typical timeline of the calcium sulfate setting reaction. In the slurry and paste form, the calcium sulfate is able to be added to a syringe and injected to the bone graft site. Near the end of the reaction, the cement becomes much thicker and has a putty-like consistency. During this phase, the doughy cement can be molded into a variety of shapes and provides a custom fit when placed directly at the implant site. Once the cement has fully hardened, it can be shaped by using powered surgical instruments such as osteotomes, burrs, and drills.



Figure 5. Typical setting reaction and phase changes for a calcium sulfate cement.

The resorption of calcium sulfate graft materials is based on the microstructure of the fully hardened cement. Figure 6 shows electron micrographs of the surface of fully reacted calcium sulfate dihydrate. These high magnification images show small calcium sulfate crystals packed together in a microporous structure. Upon implantation, the presence of these small pores allows the calcium sulfate to absorb water throughout the cement. Unlike polymers, which undergo active breakdown of the polymer chains, calcium sulfate materials are slowly dissolved by the water. As the material dissolves, Ca^{2+} and ${SO_4}^{-3}$ ions are released over a 6–8 week period. During healing, bone formation initially begins on the outer area of the calcium sulfate and progresses inward as the cement slowly breaks apart. During the resorption process, the dissolution of the calcium sulfate material aids bone formation by providing a direct source Ca^{2+} ions to the surrounding osteoblasts. These cells absorb the calcium and use it during the mineralization phase of bone regeneration. From a mechanical standpoint, the hardened cement can provide initial stabilization to the site, but quickly loses it strength as the calcium sulfate begins to fragment. Although the strength of the calcium sulfate quickly decreases within the first few weeks, additional bone regeneration takes place within the cement and the implant site becomes mechanically stable. At the 6–8 week period, the majority of the calcium sulfate is resorbed by the body and has been replaced by bone.

In general, calcium sulfate cements and implants offer an effective means to fill small voids in bone resulting from cysts, tumors, or fractures (98–101). The initial strength



Figure 6. High magnification scanning electron micrographs of fully reacted calcium sulfate dihydrate showing crystalline structure and microporosity (1000X and 2000X magnification).

can also help maintain the spacing of fracture fragments and aid in placement of additional hardware. The moldability of the cement allows a custom fit to the defect site and makes the material easy to use. However, due to the quick resorption time and quick loss in strength, this material can not be effectively used in large defects or in areas under high mechanical loads. In these applications, supplemental hardware and grafting materials are needed to ensure complete bone regeneration (102,103). From a commercial standpoint, calcium sulfate graft materials are available in a cement form (requires mixing at the time of surgery) or in a preformed pellet form (fully reacted calcium sulfate dihydrate).

Calcium Phosphate. Calcium phosphates are another class of calcium containing bone graft materials that offer different properties than the calcium sulfates. As the name describes, these material are composed of varying amounts of calcium (Ca^{2+}) and phosphate ($PO_4{}^{-3}$). One of the first calcium phosphate materials to be used as a bone graft was hydroxyapatite, which was chosen because it is the main inorganic component of bone accounting for 40% of its weight. Most calcium phosphate graft materials are produced synthetically and can be chemically altered to create materials with different properties. By slightly varying the calcium-to-phosphate ratio, the resorption times and mechanical properties of these materials can be significantly altered. Hydroxyapatite [$Ca_{10}(PO_4)_6(OH)_2$] with a Ca/P ratio of 1.67 has slow resorption rate, which, depending on crystallinity, can be as little are 2–5% resorption per year. Tricalcium phosphate $Ca_3(PO_4)_2$ has a ratio of 1.5, which results in a much faster resorption time of 9–12 months.

Due to the chemical composition of calcium phosphates, the mechanism of resorption is different than the dissolution mechanism seen with calcium sulfates. The chemical similarity of calcium phosphates to bone results in a cell-mediated resorption profile. During healing, bone-resorbing cells called osteoclasts migrate to the surface of the calcium phosphate ceramics. Once activated, the osteoclasts release specific enzymes that dissolve the calcium phosphate into its base ions. As the osteoclasts tunnel through the calcium phosphate, bone-forming cells called osteoblasts trail behind filling in the region with new tissue. Similar to calcium sulfate, the calcium ions resulting from the resorption process are transported to the osteoblasts, which create new mineralized bone. Over time, the entire structure is slowly dissolved by the osteoclasts and replaced with new bone.

To facilitate this type of resorption process, many of the calcium phosphate bone graft materials exist as porous scaffolds (104–109). A typical example of an osteoconductive calcium phosphate bone graft scaffold is shown in Fig. 7. This material, called Pro Osteon (developed and manufactured by Interpore Cross), was one of the first porous calcium phosphates used in orthopedics (110–113). Derived from sea coral, it is fabricated by chemically converting the calcium carbonate skeleton of the coral into hydroxyapatite. This reaction can be run to completion to give a implant composed entirely of hydroxyapatite or intentionally stopped to result in an implant with a thin (4–10 μm) surface of hydroxyapatite over the calcium carbonate skeleton. The conversion of coral to Pro Osteon



Pro Osteon 500 Pro Osteon 200

Figure 7. Photographs of a two commercially available calcium phosphate scaffolds derived from coral (Interpore Cross, Irvine, CA).

allows the relatively short degradation time of calcium carbonate (6–8 weeks) to be prolonged to 8–18 months for Pro Osteon R (HA layer on the calcium carbonate skeleton) and to 3–5 years for Pro Osteon HA (fully converted hydroxyapatite). With a natural pore structure similar to cancellous bone, the Pro Osteon graft materials offer an effective scaffold for new bone growth. Since development of the Pro Osteon bone graft materials, several other porous calcium phosphates have entered the market. These materials are synthetically made to mimic the porosity of cancellous bone, which is done through various foaming and void creation techniques.

In contrast to calcium sulfate graft materials, the slower resorption profile of porous calcium phosphate ceramics allow these material to be used in larger defects. In this scenario, the graft serves as a cellular "bridge" for continued bone growth. In bone grafting surgery, once a defect reaches a size when it can no longer completely heal itself, it is called a critical-sized defect. Typical bone regeneration can bridge empty gaps of up to 4 mm, but anything larger will not fill in with bone. A porous ceramic scaffold alleviates this problem by providing the means for bone to grow across the entire defect.

This effect was demonstrated in a study by Holmes who implanted a block of Pro Osteon 500R (calcium carbonate scaffold with an HA coating) into a rabbit tibial defect (114). The healing sequence of the this scaffold is shown in Fig. 8. As seen from cross sectional image of the implant before implantation (Fig. 8a), the structure is characterized by an open pore structure (black regions) within areas of calcium carbonate/HA ceramic (light-gray regions). After initial placement of the porous ceramic, cells migrated to the graft site and began to infiltrate the pore system. At the same time, proteins were released from surrounding bone and blood cells to stimulate the bone regeneration process, which was seen in the 6 week histology of the Pro Osteon 500R implant (Fig. 8b). In this image, bone formation was evident within the porosity of the scaffold, and osteoclasts were seen resorbing the scaffold (arrows). By 12 weeks, further bone growth was seen within the porosity, and significant portions of the scaffold were replaced by bone. At the 24 week time point, the scaffold was fully replaced by bone with the exception of the thin HA layer that once covered the calcium carbonate. As seen from this study, porous ceramics are capable of functioning as a scaffold for bone growth. The pore system allowed for immediate bone regeneration and the resorbability allowed the implant to be completely replaced by bone.



Figure 8. Typical healing mechanism of a porous ceramic implanted into a rabbit tibial defect. (Figure A – 0 weeks; Figure B – 6 weeks; Figure C – 12 weeks; Figure D – 24 weeks).

In addition to porous blocks and granules, calcium phosphates are also used in cement form (115–119). In this application, the base components that create calcium phosphates are provided in an unreacted form. With the addition of water, dilute acid, or other initiators, a chemical reaction takes place, and the components are converted to calcium phosphate. The result is a moldable paste or putty that can be shaped to the graft site and hardens into a solid mass. Although these cements have longer resorption times than calcium sulfate cements and can be used in broader applications, the resulting hardened cement does not possess the porosity to function as a scaffold for bone repair, which has limited the use of calcium phosphate cerments because surgeons prefer the porous blocks and granules over the self-setting cements.

RESORBABLE COMPOSITES

As discussed, both polymers and ceramics have properties suitable for fabricating orthopedic implants. However, certain drawbacks exist with these materials that can not be avoided no matter how the material is fabricated or chemically altered. One technique for combining the desirable properties of two or more materials is the fabrication of a composite. Composites used in the medical device area are fabricated by physically mixing two or more resorbable materials. One of the most common composite combinations is the creation of a polymer-ceramic composite. On their own, ceramics are excellent substrates for new bone growth due to the chemical similarity with bone mineral. However, their brittleness limits their use in load-bearing applications. Polymers, on the other hand, are elastomeric materials that can flex under deformation without major structural collapse. The combination of these two materials results in a high strength, yet ductile composite that allows for direct bone attachment on its surface. In this combination, the polymer adds to the overall mechanical properties of the composite, whereas the ceramic allows for bone formation directly on the ceramic phase.

The fabrication of a composite is a relatively straightforward process. Typically, ceramic particles in the shape of spheres or fibers are added to the polymer during processing. The various orientations of the particles within a polymer are shown in Fig. 9. As seen from these illustrations, each particle is surrounded by the polymer and serves to reinforce the polymer phase and improve it mechanical properties. Once fabricated in a block or rod



Random Fiber Composite **Oriented Fiber Composite**



Particulate Composite **Continuous Phase Composite**

Figure 9. Orientation of various types of polymer-ceramic composites (ceramic is depicted as the black particles).

form, composites of these different types can be machined into a variety of implants such as fracture screws, pins, and plates. During the machining process, the ceramic on the outer surfaces of the implant are exposed. From a bone implant standpoint, the presence of the exposed calcium ceramic particles on the surface of the polymer aids in creating a solid bone-to-implant interface. In comparison, pure polymer implants typically heal with limited bone contact or a continuous layer of fibrous tissue usually covering the surface. Although the implant can still provide stabilization, it is not directly bonded to the surrounding bone. A composite implant improves on the stabilizing effect of the device through this bone-bonding ability.



Porous Scaffold **Continuous Phase Composite**

Figure 10. A continuous phase composite is formed when a polymer is infiltrated into the porosity a porous, ceramic scaffold. The result is a solid block with an intact polymer and ceramic phase.



Figure 11. Backscattered electron microscope images demonstrating bone and blood vessel in-growth into a CPC implant (bone is shown in gray, ceramic is white, and polymer is black).

In addition to the particulate ceramic composites, a new type of composite has recently been developed by Interpore Cross (Irvine, CA). This novel material consists of two intact, continuous phases of polymer and ceramic. Shown in Fig. 10, a continuous phase composite (CPC) is the result of infiltrating a porous ceramic block with polymer. The end result is a composite material with continuous seams of ceramic running through the polymer. Similar to the particulate composites, the CPC material will allow for bone growth on the surface and into the ceramic regions. However, the continuity of the ceramic phase throughout the composite gives the material a unique ability to allow for bone to penetrate into the center of a CPC implant. Figure 11 shows the histology a CPC implant composed of the Pro Osteon porous ceramic infiltrated with poly(L/D,L lactic acid) implanted in a sheep femur at 9 months. This backscattered electron microscope image shows the ability of a CPC implant to support bone and blood vessel in-growth into the center of the implant wall. In addition to acting as a structural implant, a CPC device also functions as an eventual scaffold for bone in-growth. From a healing standpoint, this type of composite will result in more bone formation at the site. Additionally, the presence of bone and blood vessels within the implant wall significantly improves the ability of the tissue to absorb the degradation products. Typically occurring at the surface of polymer implants, the presence of bone within the CPC material allows resorption throughout the entire device. This new composite is currently being investigated for use as spinal fusion implants, fracture screws and plates, interference screws, and suture anchors.

CONCLUSION

As seen from this article, resorbable polymers and ceramics possess the desired properties needed for orthopedic implants. They have been shown to be versatile materials with a range in degradation rates and mechanical properties. The resorbable nature of these devices allows them to provide temporary stabilization and mechanical support. Combined with the ability to be completely resorbed by the body and replaced by natural tissue, these implants are highly desirable alternatives to their nonresorbing counterparts. The elimination of long-term implant complications and the ability to share load with regenerating tissues are large driving forces behind the use of these implants in orthopedics. With further advancements in biomaterial research, resorbable implants may soon become the standard of care.

BIBLIOGRAPHY

Cited References

1. History of Total Joint Replacement. Utah Hip and Knee Center. Available: http://www.utahhipandknee.com/history.htm. Accessed September 24, 2004.
2. History of Innovation. Zimmer Corporate Website. Available:http://www.zimmer.com/ctl?op=global&action=1&id=1420&template= CP. Accessed September 24, 2004.
3. Parker DA, Dunbar MJ, Rorabeck CH. Extensor mechanism failure associated with total knee arthroplasty: Prevention and management. J Am Acad Orthop Surg 2003;11:238–247.
4. Ries MD. Complications in primary total hip arthroplasty: Avoidance and management: wear. Instrum Course Lect 2003;52:257–265.
5. Sochart DH. Relationship of acetabular wear to osteolysis and loosening in total hip arthroplasty. Clin Orthop 1999; 135–150.
6. Moreland JR. Mechanisms of failure in total knee arthroplasty. Clin Orthop 1988; 49–64.
7. Borden MD. The development of bone graft materials using various formulations of demineralized bone matrix. In Laurencin CT, editor, Bone Graft Substitutes. Conshohocken, (PA): ASTM International; 2003.
8. Uhthoff HK, Finnegan M. The effects of metal plates on post-traumatic remodelling and bone mass. J Bone Joint Surg Br 1983;65:66–71.
9. van der EM, Dijkema AR, Klein CP, Patka P, Haarman HJ. Tissue reaction on PLLA versus stainless steel interlocking nails for fracture fixation: An animal study. Biomaterials 1995;16:103–106.
10. Bos RR, Rozema FR, Boering G, Nijenhuis AJ, Pennings AJ, Verwey AB. Bio-absorbable plates and screws for internal fixation of mandibular fractures. A study in six dogs. Int J Oral Maxillofac Surg 1989;18:365–369.
11. Viljanen J, Kinnunen J, Bondestam S, Majola A, Rokkanen P, Tormala P. Bone changes after experimental osteotomies fixed with absorbable self-reinforced poly-L-lactide screws or metallic screws studied by plain radiographs, quantitative computed tomography and magnetic resonance imaging. Biomaterials 1995;16:1353–1358.
12. van der EM, Klein CP, Blieck-Hogervorst JM, Patka P, Haarman HJ. Bone tissue response to biodegradable polymers used for intra medullary fracture fixation: A long-term in vivo study in sheep femora. Biomaterials 1999; 20:121–128.
13. Engelberg I, Kohn J. Physico-mechanical properties of degradable polymers used in medical applications: A comparative study. Biomaterials 1991;12:292–304.
14. Kulkarni RK, Pani KC, Neuman C, Leonard F. Polylactic acid for surgical implants. Arch Surg 1966;93:839–843.
15. Chu CC. A comparison of the effect of pH on the biodegradation of two synthetic absorbable sutures. Ann Surg 1982;195:55–59.
16. Chu CC. Mechanical properties of suture materials: An important characterization. Ann Surg 1981;193:365–371.
17. Chu CC, Campbell ND. Scanning electron microscopic study of the hydrolytic degradation of poly(glycolic acid) suture. J Biomed Mater Res 1982;16:417–430.
18. Chu CC. The in-vitro degradation of poly(glycolic acid) sutures–effect of pH. J Biomed Mater Res 1981;15:795–804.
19. Leenslag JW, Pennings AJ, Bos RR, Rozema FR, Boering G. Resorbable materials of poly(L-lactide). VI. Plates and screws for internal fracture fixation. Biomaterials 1987;8:70–73.
20. Tuompo P, Partio EK, Jukkala-Partio K, Pohjonen T, Helevirta P, Rokkanen P. Comparison of polylactide screw and expansion bolt in bioabsorbable fixation with patellar tendon bone graft for anterior cruciate ligament rupture of the knee. A preliminary study. Knee Surg Sports Traumatol Arthrosc 1999;7:296–302.
21. Koskikare K, Hirvensalo E, Patiala H, Rokkanen P, Pohjonen T, Tormala P, Lob G. Fixation of osteotomies of the distal femur with absorbable, self-reinforced, poly-L-lactide plates. An experimental study on rabbits. Arch Orthop Trauma Surg 1997;116:352–356.
22. Makela EA, Vainionpaa S, Vihtonen K, Mero M, Laiho J, Tormala P, Rokkanen P. Healing of physeal fracture after fixation with biodegradable self-reinforced polyglycolic acid pins. An experimental study on growing rabbits. Clin Mater 1990;5:1–12.
23. Pihlajamaki H, Bostman O, Hirvensalo E, Tormala P, Rokkanen P. Absorbable pins of self-reinforced poly-L-lactic acid for fixation of fractures and osteotomies. J Bone Joint Surg Br 1992;74:853–857.
24. Tormala P, Vasenius J, Vainionpaa S, Laiho J, Pohjonen T, Rokkanen P. Ultra-high-strength absorbable self-reinforced polyglycolide (SR-PGA) composite rods for internal fixation of bone fractures: In vitro and in vivo study. J Biomed Mater Res 1991;25:1–22.
25. Vainionpaa S, Kilpikari J, Laiho J, Helevirta P, Rokkanen P, Tormala P. Strength and strength retention in vitro, of absorbable, self-reinforced polyglycolide (PGA) rods for fracture fixation. Biomaterials 1987;8:46–48.
26. Barber FA, Deck MA. The in vivo histology of an absorbable suture anchor: A preliminary report. Arthroscopy 1995;11:77–81.
27. Borden M, El Amin SF, Attawia M, Laurencin CT. Structural and human cellular assessment of a novel microsphere-based tissue engineered scaffold for bone repair. Biomaterials 2003;24:597–609.
28. Borden M, Attawia M, Laurencin CT. The sintered microsphere matrix for bone tissue engineering: in vitro osteoconductivity studies. J Biomed Mater Res 2002;61:421–429.
29. Borden M, Attawia M, Khan Y, Laurencin CT. Tissue engineered microsphere-based matrices for bone repair: design and evaluation. Biomaterials 2002;23:551–559.

30. Thomson RC, Yaszemski MJ, Powers JM, Mikos AG. Fabrication of biodegradable polymer scaffolds to engineer trabecular bone. J Biomater Sci Polym Ed 1995;7:23–38.
31. Hollier LH, Rogers N, Berzin E, Stal S. Resorbable mesh in the treatment of orbital floor fractures. J Craniofac Surg 2001;12:242–246.
32. Edwards RC, Kiely KD, Eppley BL. The fate of resorbable poly-L-lactic/polyglycolic acid (LactoSorb) bone fixation devices in orthognathic surgery. J Oral Maxillofac Surg 2001;59:19–25.
33. Edwards RC, Kiely KD, Eppley BL. Resorbable PLLA-PGA screw fixation of mandibular sagittal split osteotomies. J Craniofac Surg 1999;10:230–236.
34. Westermark A. LactoSorb resorbable osteosynthesis after sagittal split osteotomy of the mandible: A 2-year follow-up. J Craniofac Surg 1999;10:519–522.
35. Eppley BL, Morales L, Wood R, Pensler J, Goldstein J, Havlik RJ, Habal M, Losken A, Williams JK, Burstein F, Rozzelle AA, Sadove AM. Resorbable PLLA-PGA plate and screw fixation in pediatric craniofacial surgery: Clinical experience in 1883 patients. Plast Reconstr Surg 2004;114:850–856.
36. Toth JM, Wang M, Scifert JL, Cornwall GB, Estes BT, Seim HB, III, Turner AS. Evaluation of 70/30 D,L-PLa for use as a resorbable interbody fusion cage. Orthopedics 2002;25: s1131–s1140.
37. Vaccaro AR, Madigan L. Spinal applications of bioabsorbable implants. Orthopedics 2002;25:s1115–s1120.
38. Lowe TG, Coe JD. Bioresorbable polymer implants in the unilateral transforaminal lumbar interbody fusion procedure. Orthopedics 2002;25:s1179–s1183.
39. Bostman OM. Osteolytic changes accompanying degradation of absorbable fracture fixation implants. J Bone Joint Surg Br 1991;73:679–682.
40. Pelto-Vasenius K, Hirvensalo E, Vasenius J, Rokkanen P. Osteolytic changes after polyglycolide pin fixation in chevron osteotomy. Foot Ankle Int 1997;18:21–25.
41. Bostman OM. Reaction to biodegradable implants. J Bone Joint Surg Br 1993;75:336–337.
42. Bostman OM. Intense granulomatous inflammatory lesions associated with absorbable internal fixation devices made of polyglycolide in ankle fractures. Clin Orthop 1992; 193–199.
43. Bostman OM. Osteoarthritis of the ankle after foreign-body reaction to absorbable pins and screws: A three- to nine-year follow-up study. J Bone Joint Surg Br 1998;80:333–338.
44. Bostman OM, Pihlajamaki HK. Adverse tissue reactions to bioabsorbable fixation devices. Clin Orthop 2000; 216–227.
45. Bostman O, Pihlajamaki H. Clinical biocompatibility of biodegradable orthopedic implants for internal fixation: A review. Biomaterials 2000;21:2615–2621.
46. Rovinsky D, Nissen TP, Otsuka NY. Osteolytic reaction to polylevolactic acid fracture fixation. Orthopedics 2001;24: 177–179.
47. Bostman O, Hirvensalo E, Makinen J, Rokkanen P. Foreign-body reactions to fracture fixation implants of biodegradable synthetic polymers. J Bone Joint Surg Br 1990;72:592–596.
48. Taylor MS, Daniels AU, Andriano KP, Heller J. Six bioabsorbable polymers: in vitro acute toxicity of accumulated degradation products. J Appl Biomater 1994;5:151–157.
49. Bergsma JE, de Bruijn WC, Rozema FR, Bos RR, Boering G. Late degradation tissue response to poly(L-lactide) bone plates and screws. Biomaterials 1995;16:25–31.
50. Bergsma EJ, Rozema FR, Bos RR, de Bruijn WC. Foreign body reactions to resorbable poly(L-lactide) bone plates and screws used for the fixation of unstable zygomatic fractures. J Oral Maxillofac Surg 1993;51:666–670.
51. Lanman TH, Hopkins TJ. Lumbar interbody fusion after treatment with recombinant human bone morphogenetic protein-2 added to poly(L-lactide-*co*-D,L-lactide) bioresorbable implants. Neurosurg Focus 2004;16:E9.
52. Couture DE, Branch CL, Jr. Posterior lumbar interbody fusion with bioabsorbable spacers and local autograft in a series of 27 patients. Neurosurg Focus 2004;16:E8.
53. Vaccaro AR, Robbins MM, Madigan L, Albert TJ, Smith W, Hilibrand AS. Early findings in a pilot study of anterior cervical fusion in which bioabsorbable interbody spacers were used in the treatment of cervical degenerative disease. Neurosurg Focus 2004;16:E7.
54. Cornwall GB, Ames CP, Crawford NR, Chamberlain RH, Rubino AM, Seim HB, III, Turner AS. In vivo evaluation of bioresorbable polylactide implants for cervical graft containment in an ovine spinal fusion model. Neurosurg Focus 2004;16:E5.
55. Lippman CR, Hajjar M, Abshire B, Martin G, Engelman RW, Cahill DW. Cervical spine fusion with bioabsorbable cages. Neurosurg Focus 2004;16:E4.
56. Robbins MM, Vaccaro AR, Madigan L. The use of bioabsorbable implants in spine surgery. Neurosurg Focus 2004;16:E1.
57. Ames CP, Crawford NR, Chamberlain RH, Cornwall GB, Nottmeier E, Sonntag VK. Feasibility of a resorbable anterior cervical graft containment plate. Orthopedics 2002;25: s1149–s1155.
58. DiAngelo DJ, Kitchel S, McVay BJ, Scifert JL, Cornwall GB. Bioabsorbable anterior lumbar plate fixation in conjunction with anterior interbody fusion cages. Orthopedics 2002;25: s1157–s1165.
59. Speer KP, Warren RF, Pagnani M, Warner JJ. An arthroscopic technique for anterior stabilization of the shoulder with a bioabsorbable tack. J Bone Joint Surg Am 1996;78:1801–1807.
60. Warner JJ, Miller MD, Marks P, Fu FH. Arthroscopic Bankart repair with the Suretac device. Part I: Clinical observations. Arthroscopy 1995;11:2–13.
61. Warner JJ, Miller MD, Marks P. Arthroscopic Bankart repair with the Suretac device. Part II: Experimental observations. Arthroscopy 1995;11:14–20.
62. Bourke SL, Kohn J. Polymers derived from the amino acid L-tyrosine: polycarbonates, polyarylates and copolymers with poly(ethylene glycol). Adv Drug Deliv Rev 2003;55:447–466.
63. Ertel SI, Kohn J. Evaluation of a series of tyrosine-derived polycarbonates as degradable biomaterials. J Biomed Mater Res 1994;28:919–930.
64. Ertel SI, Kohn J, Zimmerman MC, Parsons JR. Evaluation of poly(DTH carbonate), a tyrosine-derived degradable polymer, for orthopedic applications. J Biomed Mater Res 1995;29:1337–1348.
65. Choueka J, Charvet JL, Koval KJ, Alexander H, James KS, Hooper KA, Kohn J. Canine bone response to tyrosine-derived polycarbonates and poly(L-lactic acid). J Biomed Mater Res 1996;31:35–41.
66. Tangpasuthadol V, Pendharkar SM, Peterson RC, Kohn J. Hydrolytic degradation of tyrosine-derived polycarbonates, a class of new biomaterials. Part II: 3-yr study of polymeric devices. Biomaterials 2000;21:2379–2387.
67. Chaikof EL, Matthew H, Kohn J, Mikos AG, Prestwich GD, Yip CM. Biomaterials and scaffolds in reparative medicine. Ann N Y Acad Sci 2002;961:96–105.
68. Kohn J, Langer R. Poly(iminocarbonates) as potential biomaterials. Biomaterials 1986;7:176–182.

69. Ibim SM, Uhrich KE, Bronson R, El Amin SF, Langer RS, Laurencin CT. Poly(anhydride-*co*-imides): in vivo biocompatibility in a rat model. Biomaterials 1998;19:941–951.
70. Ibim SE, Uhrich KE, Attawia M, Shastri VR, El Amin SF, Bronson R, Langer R, Laurencin CT. Preliminary in vivo report on the osteocompatibility of poly(anhydride-co-imides) evaluated in a tibial model. J Biomed Mater Res 1998;43:374–379.
71. Uhrich KE, Ibim SE, Larrier DR, Langer R, Laurencin CT. Chemical changes during in vivo degradation of poly(anhydride-imide) matrices. Biomaterials 1998;19: 2045–2050.
72. Katti DS, Lakshmi S, Langer R, Laurencin CT. Toxicity, biodegradation and elimination of polyanhydrides. Adv Drug Deliv Rev 2002;54:933–961.
73. Attawia MA, Uhrich KE, Botchwey E, Langer R, Laurencin CT. In vitro bone biocompatibility of poly (anhydride-co-imides) containing pyromellitylimidoalanine. J Orthop Res 1996;14:445–454.
74. Ray JA, Doddi N, Regula D, Williams JA, Melveger A. Polydioxanone (PDS), a novel monofilament synthetic absorbable suture. Surg Gynecol Obstet 1981;153:497–507.
75. Ping OC, Cameron RE. The hydrolytic degradation of polydioxanone (PDSII) sutures. Part I: Morphological aspects. J Biomed Mater Res 2002;63:280–290.
76. Ping OC, Cameron RE. The hydrolytic degradation of polydioxanone (PDSII) sutures. Part II: Micromechanisms of deformation. J Biomed Mater Res 2002;63:291–298.
77. Ray JA, Doddi N, Regula D, Williams JA, Melveger A. Polydioxanone (PDS), a novel monofilament synthetic absorbable suture. Surg Gynecol Obstet 1981;153:497–507.
78. Bartholomew RS. PDS (polydioxanone suture): A new synthetic absorbable suture in cataract surgery. A preliminary study. Ophthalmologica 1981;183:81–85.
79. Lerwick E. Studies on the efficacy and safety of polydioxanone monofilament absorbable suture. Surg Gynecol Obstet 1983;156:51–55.
80. Cohen EL, Kirschenbaum A, Glenn JF. Preclinical evaluation of PDS (polydioxanone) synthetic absorbable suture vs chromic surgical gut in urologic surgery. Urology 1987;30:369–372.
81. Apt L, Henrick A. "Tissue-drag" with polyglycolic acid (Dexon) and polyglactin 910 (Vicryl) sutures in strabismus surgery. J Pediatr Ophthalmol 1976;13:360–364.
82. Homsy CA, McDonald KE, Akers WW, Short C, Freeman BS. Surgical suture-canine tissue interaction for six common suture types. J Biomed Mater Res 1968;2:215–230.
83. Rhee SH, Lee YK, Lim BS, Yoo JJ, Kim HJ. Evaluation of a novel poly(epsilon-caprolactone)-organosiloxane hybrid material for the potential application as a bioactive and degradable bone substitute. Biomacromolecules 2004;5: 1575–1579.
84. Rhee SH. Bone-like apatite-forming ability and mechanical properties of poly(epsilon-caprolactone)/silica hybrid as a function of poly(epsilon-caprolactone) content. Biomaterials 2004;25:1167–1175.
85. Ciapetti G, Ambrosio L, Savarino L, Granchi D, Cenni E, Baldini N, Pagani S, Guizzardi S, Causa F, Giunti A. Osteoblast growth and function in porous poly epsilon-caprolactone matrices for bone repair: a preliminary study. Biomaterials 2003;24:3815–3824.
86. Im SY, Cho SH, Hwang JH, Lee SJ. Growth factor releasing porous poly (epsilon-caprolactone)-chitosan matrices for enhanced bone regenerative therapy. Arch Pharm Res 2003;26:76–82.
87. Wang YW, Wu Q, Chen J, Chen GQ. Evaluation of three-dimensional scaffolds made of blends of hydroxyapatite and poly(3-hydroxybutyrate-*co*-3-hydroxyhexanoate) for bone reconstruction. Biomaterials 2005;26:899–904.
88. Yang M, Zhu S, Chen Y, Chang Z, Chen G, Gong Y, Zhao N, Zhang X. Studies on bone marrow stromal cells affinity of poly (3-hydroxybutyrate-*co*-3-hydroxyhexanoate). Biomaterials 2004;25:1365–1373.
89. Kose GT, Kenar H, Hasirci N, Hasirci V. Macroporous poly(3-hydroxybutyrate-*co*-3-hydroxyvalerate) matrices for bone tissue engineering. Biomaterials 2003;24:1949–1958.
90. Farso NF, Karring T, Gogolewski S. Biodegradable guide for bone regeneration. Polyurethane membranes tested in rabbit radius defects. Acta Orthop Scand 1992;63:66–69.
91. Gorna K, Gogolewski S. Preparation, degradation, and calcification of biodegradable polyurethane foams for bone graft substitutes. J Biomed Mater Res 2003;67A:813–827.
92. Grad S, Kupcsik L, Gorna K, Gogolewski S, Alini M. The use of biodegradable polyurethane scaffolds for cartilage tissue engineering: potential and limitations. Biomaterials 2003; 24:5163–5171.
93. Warrer K, Karring T, Nyman S, Gogolewski S. Guided tissue regeneration using biodegradable membranes of polylactic acid or polyurethane. J Clin Periodontol 1992;19:633–640.
94. Ambrosio AM, Sahota JS, Runge C, Kurtz SM, Lakshmi S, Allcock HR, Laurencin CT. Novel polyphosphazene-hydroxyapatite composites as biomaterials. IEEE Eng Med Biol Mag 2003;22:18–26.
95. Laurencin CT, El Amin SF, Ibim SE, Willoughby DA, Attawia M, Allcock HR, Ambrosio AA. A highly porous 3-dimensional polyphosphazene polymer matrix for skeletal tissue regeneration. J Biomed Mater Res 1996;30:133–138.
96. Laurencin CT, Norman ME, Elgendy HM, El Amin SF, Allcock HR, Pucher SR, Ambrosio AA. Use of polyphosphazenes for skeletal tissue regeneration. J Biomed Mater Res 1993;27:963–973.
97. Coetzee AS. Regeneration of bone in the presence of calcium sulfate. Arch Otolaryngol 1980;106:405–409.
98. Gitelis S, Piasecki P, Turner T, Haggard W, Charters J, Urban R. Use of a calcium sulfate-based bone graft substitute for benign bone lesions. Orthopedics 2001;24:162–166.
99. Ladd AL, Pliam NB. Use of bone-graft substitutes in distal radius fractures. J Am Acad Orthop Surg 1999;7:279–290.
100. Guarnieri R, Pecora G, Fini M, Aldini NN, Giardino R, Orsini G, Piattelli A. Medical grade calcium sulfate hemihydrate in healing of human extraction sockets: Clinical and histological observations at 3 months. J Periodontol 2004;75:902–908.
101. Kelly CM, Wilkins RM. Treatment of benign bone lesions with an injectable calcium sulfate-based bone graft substitute. Orthopedics 2004;27:s131–s135.
102. Urban RM, Turner TM, Hall DJ, Infanger S, Cheema N, Lim TH. Healing of large defects treated with calcium sulfate pellets containing demineralized bone matrix particles. Orthopedics 2003;26:s581–s585.
103. Turner TM, Urban RM, Hall DJ, Infanger S, Gitelis S, Petersen DW, Haggard WO. Osseous healing using injectable calcium sulfate-based putty for the delivery of demineralized bone matrix and cancellous bone chips. Orthopedics 2003;26:s571–s575.
104. Thalgott JS, Giuffre JM, Fritts K, Timlin M, Klezl Z. Instrumented posterolateral lumbar fusion using coralline hydroxyapatite with or without demineralized bone matrix, as an adjunct to autologous bone. Spine J 2001;1:131–137.
105. McConnell JR, Freeman BJ, Debnath UK, Grevitt MP, Prince HG, Webb JK. A prospective randomized comparison of coralline hydroxyapatite with autograft in cervical interbody fusion. Spine 2003;28:317–323.
106. Thalgott JS, Klezl Z, Timlin M, Giuffre JM. Anterior lumbar interbody fusion with processed sea coral (coralline

hydroxyapatite) as part of a circumferential fusion. Spine 2002;27:E518–E525.
107. Delecrin J, Takahashi S, Gouin F, Passuti N. A synthetic porous ceramic as a bone graft substitute in the surgical management of scoliosis: A prospective, randomized study. Spine 2000;25:563–569.
108. McAndrew MP, Gorman PW, Lange TA. Tricalcium phosphate as a bone graft substitute in trauma: Preliminary report. J Orthop Trauma 1988;2:333–339.
109. Bucholz RW, Carlton A, Holmes RE. Hydroxyapatite and tricalcium phosphate bone graft substitutes. Orthop Clin North Am 1987;18:323–334.
110. Holmes R, Mooney V, Bucholz R, Tencer A. A coralline hydroxyapatite bone graft substitute. Preliminary report. Clin Orthop 1984; 252–262.
111. Finn RA, Bell WH, Brammer JA. Interpositional “grafting” with autogenous bone and coralline hydroxyapatite. J Maxillofac Surg 1980;8:217–227.
112. Holmes RE. Bone regeneration within a coralline hydroxyapatite implant. Plast Reconstr Surg 1979;63:626–633.
113. Holmes RE, Salyer KE. Bone regeneration in a coralline hydroxyapatite implant. Surg Forum 1978;29:611–612.
114. Jamali A, Hilpert A, Debes J, Afshar P, Rahban S, Holmes R. Hydroxyapatite/calcium carbonate (HA/CC) vs. plaster of Paris: A histomorphometric and radiographic study in a rabbit tibial defect model. Calcif Tissue Int 2002;71:172–178.
115. Kenny SM, Buggy M. Bone cements and fillers: A review. J Mater Sci Mater Med 2003;14:923–938.
116. Horstmann WG, Verheyen CC, Leemans R. An injectable calcium phosphate cement as a bone-graft substitute in the treatment of displaced lateral tibial plateau fractures. Injury 2003;34:141–144.
117. Kamano M, Honda Y, Kazuki K, Yasudab M. Palmar plating with calcium phosphate bone cement for unstable Colles’ fractures. Clin Orthop 2003; 285–290.
118. Zimmermann R, Gabl M, Lutz M, Angermann P, Gschwentner M, Pechlaner S. Injectable calcium phosphate bone cement Norian SRS for the treatment of intra-articular compression fractures of the distal radius in osteoporotic women. Arch Orthop Trauma Surg 2003;123:22–27.
119. Schildhauer TA, Bauer TW, Josten C, Muhr G. Open reduction and augmentation of internal fixation with an injectable skeletal cement for the treatment of complex calcaneal fractures. J Orthop Trauma 2000;14:309–317.

See also DRUG DELIVERY SYSTEMS; MATERIALS AND DESIGN FOR ORTHOPEDIC DEVICES; POROUS MATERIALS FOR BIOLOGICAL APPLICATIONS.

BIOMATERIALS: AN OVERVIEW

BRANDON L. SEAL
ALYSSA PANITCH
Arizona State University
Tempe, Arizona

INTRODUCTION

Biomaterials are materials that are used or that have been designed for use in medical devices or in contact with the body. Traditionally, they consist of metallic, ceramic, or synthetic polymeric materials, but more recent developments in biomaterials design have attempted to incorporate materials derived from or inspired by biological materials (e.g., silk and collagen). Often, the use of biomaterials focuses on the augmentation, replacement, or restoration of diseased or damaged tissues and organs. The prevalence of biomaterials within society is most evident within medical and dental offices, pharmacies, and hospitals. However, the influence of biomaterials has reached into many households with examples ranging from increasingly common news media coverage of medical breakthroughs to the availability of custom color noncorrective contact lenses.

The evolving character of the discipline of biomaterials is evidenced by how the term biomaterial has been defined. In 1974, the Clemson Advisory Board, in response to a request by the World Health Organization (WHO), stated that a biomaterial is a “systemically pharmacologically inert substance designed for implantation within or incorporation with living tissue” (1). Dr. Jonathan Black further modified this definition to state that a biomaterial is “any pharmacologically inert material, viable or nonviable, natural product or manmade, that is part of or is capable of interacting in a beneficial way with a living organism” (1). An National Institute of Health (NIH) consensus definition appeared in 1983 and defined biomaterials as “any substance (other than a drug) or combination of substances, synthetic or natural in origin, which can be used for any period of time, as a whole or as a part of a system that treats, augments, or replaces any tissue, organ, or function of the body” (2). Thus, relatively newer definitions of the term biomaterial recognize that more modern medical and diagnostic devices will rely increasingly upon direct biological interaction between biological molecules, cells, and tissues and the materials from which these devices are manufactured.

HISTORY OF BIOMATERIALS

Compared with the much larger field of materials science, the field of biomaterials is relatively new. Although there exist recorded cases of glass eyes and metallic or wooden dental implants (some of which can be dated back to ancient Egypt), the modern age of biomaterials could not have existed without the adoption of aseptic surgical techniques pioneered by Sir Joseph Lister in the mid-nineteenth century and indeed, did not fully emerge as an industry or discipline until after the development of synthetic polymers just prior to, during, and following World War II. Prior to World War II, implanted biomaterials consisted primarily of metals (e.g., steel, used in pins and plates for bone fixation, joint replacements, and the covering of bone defects). In the late 1940s, Harold Ridley observed that shards of poly(methyl methacrylate) (PMMA), from airplane cockpit windshields, embedded within the eyes of World War II aviators did not provoke much of an inflammatory response (3). This observation led not only to the development of PMMA intraocular lenses, but also to greater experimentation of available materials, especially polymers, as biomaterials that could be placed in direct contact with living tissue.

As the fields of cellular, molecular, and developmental biology began to grow during the 1970s and 1980s, new insights into the organization, function, and properties of biological systems, tissues, and interactions led to a greater understanding of how cells respond to their environment. This wealth of biological information allowed the field of biomaterials to undergo a paradigm shift. Instead of focusing primarily on replacing an organ or a tissue with a synthetic, usually nondegradable biomaterial, a new branch of biomaterials would attempt to combine biologically active molecules, therapeutics, and motifs into existing and novel biomaterial systems derived from both synthetic and natural sources (4–6). Although there exist many examples of successful, commercially available biomaterials consisting of metallic and ceramic bases, the focus of biomaterials research has shifted to the development of polymeric or composite materials with biologically sensitive or environmentally controlled properties. This change has resulted largely due to the reactivity and variety of chemical moieties that are found in or that can be engineered into natural and synthetic polymers. Indeed, by viewing biomaterials as materials designed to interact with biology rather than being inert substances, the field of biomaterials has exploded with innovative designs that promote cell attachment, encapsulation, proliferation, differentiation, migration, and apoptosis, and that allow the biomaterial to polymerize, swell, and degrade under a variety of environmental conditions and biological stimuli. Evidence of this polymer and composite revolution is the dramatic increase in the number of publications relating to biomaterials research. Figure 1 shows a plot of the number of journal articles with biomaterial or biomaterials in their title, abstract, or keyword as a function of publication year as searched in the Web of Science database. As seen in Fig. 1, publications matching the search criteria have increased exponentially starting around the early 1990s and continuing until the present. The number of scientific journals, shown in Table 1, related to research in the field of biomaterials has also grown. Although the number of journal articles related to biomaterials research may have resulted primarily from the large increase in the number of biomaterials-related scientific journals, the exponential growth of biomaterials is evidenced further by the growth of the number of bioengineering or biomedical engineering departments (the department in which most biomaterials programs reside) established at universities throughout the United States (Fig. 1).



Figure 1. A plot of the number of publications (○) containing the word biomaterial or biomaterials in the title, abstract, or keywords, as searched in the Web of Science database, as a function of the publication year as well as a plot of the number of bioengineering or biomedical engineering departments (BME departments) within the United States as a function of time (■).

MARKET SIZE AND TYPES OF APPLICATIONS

The field of biomaterials, by nature, is interdisciplinary. Successful biomaterial designs have involved talents, knowledge, and expertise provided by physicians and clinicians, materials scientists, engineers, chemists, biologists, and physicists. As a result, it is not surprising that the biomaterials industry is both relatively young and very diversified. The diversity of this industry has resulted from the types of products created and marketed, the size and location of involved companies, and the types of regulatory policies imposed by government agencies and third party reimbursement organizations. Specifically, the biomaterials industry is part of the Medical Device and Diagnostic Industry, a multibillion dollar industry comprised of organizations that design, fabricate, and/or manufacture materials that are used in the health and life science fields. The end use applications are medical and dental devices, prostheses, personal hygiene products, diagnostic devices, drug delivery vehicles, and biotechnology systems. Some examples of these applications include full and hybrid artificial organs, biosensors, vascular grafts, pacemakers, catheters, insulin pumps, cochlear implants, contact lenses, intraocular lenses, artificial joints and bones, burn dressings, and sutures. Table 2 shows a list of some common medical devices that require various biomaterials, and Table 3 displays a list of the prevalence and market potential of a few of these applications (7).

GOVERNMENT REGULATION

Within the United States, in a research only environment, biomaterials by themselves do not necessarily require government regulation. However, if any biomaterial is used within a medical or diagnostic device designed and destined for commercialization, the biomaterials used within the medical device (as well as the device itself) are subject to the jurisdiction of the U.S. Food and Drug Administration (FDA) as set forth in the Federal Food, Drug, and Cosmetic Act of 1938, the Medical Device Amendments of 1976, and the Food and Drug Administration Modernization Act of 1997. These laws have empowered the FDA to regulate conditions involving premarket controls, postmarket reporting, production involving Good Manufacturing Practices, and the registration and listing of medical devices. Any biomaterial within a marketed medical device prior to the Medical Device Amendments of 1976 were grandfathered and are considered approved materials. Modifications to these materials or

Table 1. A List of Journals with Publications Related to the Field of Biomaterials[a]

Name of Journal	Name of Journal	Name of Journal
Advanced Drug Delivery Reviews (1987)	Biosensors and Bioelectronics (1985)	Journal of Biomaterials Science: Polymer Edition (1990)
American Journal of Drug Delivery (2003)	Cells and Materials (1991)	Journal of Biomedical Materials Research (1967)
American Society of Artificial Internal Organs Journal (1955)	Cell Transplantation (1992)	Journal of Controlled Release (1984)
Annals of Biomedical Engineering (1973)	Clinical Biomechanics (1986)	Journal of Drug Targeting (1993)
Annual Review of Biomedical Engineering (1999)	Colloids and Surfaces B: Biointerfaces (1993)	Journal of Long Term Effects of Medical Implants (1991)
Artificial Organs (1977)	Dental Materials (1985)	Journal of Nanobiotechnology (2003)
Artificial Organs Today (1991)	Drug Delivery (1993)	Macromolecules (1968)
Biomacromolecules (2000)	Drug Delivery Systems and Sciences (2001)	Materials in Medicine (1990)
Biofouling (1985)	Drug Delivery Technology (2001)	Medical Device and Diagnostics Industry (1996)
Biomedical Engineering OnLine (2002)	e-biomed: the Journal of Regenerative Medicine (2000)	Medical Device Research Report (1995)
Bio-medical Materials and Engineering (1991)	European Cells and Materials (2001)	Medical Device Technology (1990)
Biomaterial-Living System Interactions (1993)	Federation of American Societies for Experimental Biology Journal (1987)	Medical Plastics and Biomaterials (1994)
Biomaterials (1980)	Frontiers of Medical and Biological Engineering (1991)	Nanobiology
Biomaterials, Artificial Cells and Artificial Organs (1973)	IEEE Transactions on Biomedical Engineering (1954)	Nanotechnology (1990)
Artificial Cells, Blood Substitutes, and Immobilization Biotechnology (1973)	International Journal of Artificial Organs (1976)	Nature: Materials (2002)
Biomaterials Forum (1979)	Journal of Bioactive and Compatible	Tissue Engineering (1995)
Biomedical Microdevices (1998)	Polymers (2002) Journal of Biomaterials Applications (2001)	Trends in Biomaterials and Artificial Organs (1986)

[a] The date of first publication is listed in parentheses following the name of each journal.

new materials are subject to controls established by the FDA. These controls consist of obtaining an Investigational Device Exemption for the medical device, including the biomaterials used within the device, prior to conducting clinical trials.

In addition, biomaterials can be considered part of a Class I, II, or III device depending on FDA classifications and depending on whether or not the biomaterial is considered to be part of a biologic, drug, or medical device. Class I devices are generally considered those devices needing the least amount of regulatory control since they do not present a great risk for a patient. Examples include tongue depressors and surgical drills. Class II devices represent a moderate risk to patients and require additional regulation (e.g., mandatory performance standards, additional labeling requirements, and postmarket surveillance). Some examples include X-ray systems and cardiac mapping catheters. Class III devices (e.g., cardiovascular stents and heart valves), represent those devices with the highest risk to patients and require extensive regulatory control. Usually, for biomaterials in direct contact with tissue within the body, devices are considered Class III devices and are subject to a Premarket Approval process before they can be sold within the United States. In general, for most biomaterials, some of the tests the FDA reviews to evaluate biomaterial safety includes tests

Table 2. Some Common Uses for Biomaterials

Organ/Procedure	Associated Medical Devices
Bladder	Catheters
Bone	Bone plates, joint replacements (metallic and ceramic)
Brain	Deep brain stimulator, hydrocephalus shunt, drug eluting polymers
Cardiovascular	Polymer grafts, metallic stents, drug eluting grafts
Cosmetic enhancement	Breast implants, injectable collagen
Eye	Intraocular lenses, contact lenses
Ear	Artificial cochlea, artificial stapes
Heart	Artificial heart, ventricular assist devices, heart valves, pacemakers
Kidney	Hemodialysis instrumentation
Knee	Metallic knee replacements
Lung	Blood oxygenator
Reproductive system	Hormone replacement patches, contraceptives
Skin	Artificial skin, living skin equivalents
Surgical	Scalpels, retractors, drills
Tissue repair	Sutures, bandages

Table 3. A Summary of the Prevalence and Economic Cost of Some of the Healthcare Treatments Requiring Biomaterials for the Year 2000

Medical Application[a]	Incident Patient Population[a]	Prevalent Patient Population[a]	Total Therapy Cost (Billions of US Dollars)[a]
Dialysis	188,000	1,030,000	$67
Cardiovascular			
Bypass grafts	733,000	6,000,000	$65
Valves	245,000	2,400,000	$27
Pacemakers	670,000	5,500,000	$44
Stents	1,750,000	2,500,000	$48
Joint replacement	1,285,000	7,000,000	$41
Hips	610,000		
Knees	675,000		

[a] All data taken from that reported by Lysaght and O'Loughlin (7).

involving cellular toxicity (both direct and indirect), acute and chronic inflammation, debris and degradation byproducts and associated clearance events, carcinogenicity, mutagenicity, fatigue, creep, tribology, and corrosion. Further information regarding FDA approval for medical devices can be found on the FDA webpage, www.fda.gov.

Many FDA approved biomaterials continue to be monitored for efficacy and safety in an effort not only to protect patients, but also to improve biocompatibility and reduce material failure. Perhaps the best known example of an FDA regulated biomaterial is silicone. Silicone had been used since the early 1960s in breast implants. As a result, silicone breast implants were grandfathered into the Medical Device Amendments of 1976. During the 1980s, some concerns regarding the safety of silicone breast implants arose and prompted the FDA to request, in 1990, additional safety data from manufacturers of breast implants. Due to fears of connective tissue disease, multiple sclerosis, and other ailments resulting from ruptured silicone implants, the FDA banned silicone breast implants in 1992. Recently, however, manufacturers (e.g., the Mentor Corporation) have applied for and received premarket approval for the sale of silicone breast implants contingent on the compliance of various conditions (8). Thus, silicone is a good example of the complexity surrounding the testing of both efficacy and safety for biomaterials.

TYPES OF BIOMATERIALS



Figure 2. A representation of a few medical devices made from various biomaterials. From the upper left corner and moving clockwise, this picture shows a kidney hemodialyzer, two pacemakers, a hip replacement, an articulating wrist joint, a heart valve, and a vascular graft.

Similar to the field of materials science, the field of biomaterials focuses on four major types of materials: metals, ceramics, polymers, and composites. Examples of a few selected medical devices made from these materials are shown in Fig. 2. The materials selected for any particular application depend on the properties desired for a particular function or set of functions. In all materials applications, the structure, properties, and processing of the selected material will affect performance. As a result, physicians, scientists and engineers who design biomaterials need to understand not only mechanical and physical properties of materials, but also biological properties of materials. Mechanical and physical properties include strength, fatigue, creep resistance, flexibility, permeability to gases and liquids, thermal and electrical properties, chemical reactivity, and degradation. Biological properties of materials largely focus on biocompatibility issues related to toxicity, immune system reactivity, thrombus formation, tribiology, inflammation, carcinogenic and teratogenic potential, integration with tissues and cells, and the ability to be sterilized. Regardless of the material, recent approaches to biomaterials research has focused on directing specific tissue interaction by using materials to introduce chemical bonds with the surrounding tissue, to act as scaffolds for tissue ingrowth, to introduce an inductive signal that will influence the behavior of surrounding cells or matrix, or to form new tissue when incubated or presented to transplanted cells.

Metals

Metals have been used as biomaterials for centuries. Although some fields (e.g., dentistry) continue to use amalgams, gold, and silver, most modern metallic biomaterials consist of iron, cobalt, titanium, or platinum bases. Since they are strong, metals are most often employed as biomaterials in orthopedic or fracture fixation medical devices; however, metals are also excellent conductors, and are therefore used for electrical stimulation of the heart, brain, nerves, muscle, and spinal cord. The most common alloys for orthopedic applications include stainless steel, cobalt, and titanium alloys. These alloys have enjoyed frequent use in medical procedures related to the function of joints and load-bearing. For example, metal alloys are commonly found in medical devices for knee replacement as well as in the femoral stem used in total hip replacements. Since all metals are subject to corrosion, especially in the salty, aqueous environment within the body, metals used as biomaterials often require an external oxide layer to protect against pitting and corrosion. These electrochemically inert oxide layers consist of Cr_2O_3 for stainless steel, Cr_2O_3 for cobalt alloys, and TiO_2 for



Figure 3. Photographs of stainless steel (a), cobalt–chromium (b), and titanium alloy (Ti6Al4V) (c) hip implants. (All three photographs are used with permission from the Department of Materials at Queen Mary University of London.)

titanium alloys. Figure 3 displays examples of three types of metallic hip replacements.

Stainless Steel Alloys. The stainless steel most commonly used as orthopedic biomaterials is classified 316L by the American Iron and Steel Institute. This particular austenitic alloy contains a very low carbon content (a maximum of 0.03%) and chromium content of 17–20%. The added chromium will react with oxygen to produce a corrosion-resistant chromium oxide layer. The 316L grade of stainless steel is a casting alloy, and its relatively high ductility makes this alloy amenable to extensive postcasting mechanical processing. Compared to cobalt and titanium alloys, stainless steel has a moderate yield and ultimate strength, but high ductility. Furthermore, it may be fabricated by virtually all machining and finishing processes and is generally the least expensive of the three major metallic alloys (4,5,9).

Cobalt Alloys. Cobalt alloys have been used since the early twentieth century as dental alloys and in heavily loaded joint applications. For use as a biomaterial, cobalt alloys are either cast (i.e., primarily formed within a mold) or wrought (i.e., worked into a final form from a large ingot). Two examples of cobalt alloys include Vitallium (designated F 75 by ASTM International), a cast alloy that consists of 27–30% chromium and >34% cobalt, and the wrought cobalt alloy MP35N (designated F 563 by ASTM International), which consists of 18–22% chromium, 15–25% nickel, and >34% cobalt. Compared to Vitallium, the MP35N alloy has demonstrated superior fatigue resistance, larger ultimate tensile strength, and a higher degree of corrosion resistance to chlorine. Consequently, this particular alloy is good for applications requiring long service life without fracture or stress fatigue. Compared to stainless steel alloys, cobalt-based alloys have slightly higher tensile moduli, but lower ductility. In addition, they are more expensive to manufacture and more difficult to machine. However, relative to stainless steel and titanium, cobalt-based alloys can offer the most useful balance of corrosion resistance, fatigue resistance, and strength (4,5,9).

Titanium Alloys. The most recent of the major orthopedic metallic alloys to be employed as biomaterials are titanium alloys. Although pure titanium is relatively weak and ductile, titanium can be stabilized by adding elements (e.g., aluminum and vanadium) to the alloy. Often, pure titanium (designated F 67 by ASTM International) is primarily used as a surface coating for orthopedic medical devices. For load-bearing applications, the alloy Ti6Al4V (designated F 136 by ASTM International) is much more widely used in implant manufacturing. As in the case of stainless steel and cobalt alloys, titanium contains an outer oxide layer, composed of TiO_2, that protects the implant from corrosion. In fact, of the three major orthopedic alloys, titanium shows the lowest rate of corrosion. Moreover, the density of titanium is almost half that of stainless steel and cobalt alloys. As a result, implants made from titanium are lighter and reduce patient awareness of the implant; however, titanium alloys are among the most expensive metallic biomaterials. Relative to stainless steel and cobalt alloys, titanium has a lower Young's modulus, which can aid in reducing the stresses around the implant by flexing with the bone. Titanium has a lower ductility than the other alloys, but does demonstrate high strength. These properties allow titanium alloys to play a diverse role as a biomaterial. Titanium alloys are used in parts for total joint replacements, screws, nails, pacemaker cases, and leads for implantable electrical stimulators (4,5,9).

Despite the reduced weight and improved mechanical match of titanium alloy implants to bone relative to stainless steel and chromium alloy implants, titanium alloy implants still exhibit issues with regard to mechanical mismatch. This problem stems from the large differences in properties (e.g., elastic moduli) between bone, metals, and polymers used as acetabular cups. For example, metals have elastic moduli ranging from $\sim$100 to 200 GPa, ultrahigh molecular weight polyethylene has an elastic modulus of 1–2 GPa, and the elastic modulus of cortical bone is $\sim$ 12 GPa (10). In addition, it is difficult to produce a titanium implant surface that is conducive to bone ingrowth or attachment. Novel titanium foams have been investigated as a method for reducing implant weight, better matching tissue mechanics, and improving bone ingrowth. The process involves mixing titanium powder with ammonium hydrogen carbonate powder and compressing and heating the mixture to form foams with densities varying from 0.2 to 0.65 times the density of solid titanium. These densities are close to those of cancellous bone (0.2–0.3 times the density of solid titanium) and cortical bone (0.5–0.65 times the density of solid titanium) (11). While they are preliminary, studies with novel materials such as these titanium foams illustrate a trend toward the development of materials that better mimic the properties of the native tissue they are designed to replace.



Figure 4. A photograph of the SMARTeR nitinol stent developed by the Cordis Corporation. (Reprinted from Ref. 12, with permission from Royal College of Radiologists.)

Other Metals. Besides stainless steel, cobalt alloys, and titanium alloys, there exist other examples of metals used as biomaterials. Some examples include nitinol, a single-phase nickel/titanium shape memory alloy, tantalum, a very dense, chemically inert, weak, but fatigue-resistant metal, and platinum, a very expensive metal used by itself or with iridum as a corrosion-resistant electrical conductor for electrode applications. Nitinol stents (e.g., that seen in Fig. 4) (12) and drug-eluting nitinol stents used for cardiovascular applications recently have seen enormous medical and commercial success. Indeed, metallic stents have significantly changed the way coronary blockages are treated (4,5,9).

Ceramics

Of the major types of materials used as biomaterials, ceramics have not been used as frequently as metals, polymers, or composites. However, ceramics continue to enjoy widespread use in certain bone-related applications (e.g., dentistry and joint replacement surgeries), due to their high compressive strength, high degree of hardness, excellent biocompatibility, superior tribological properties, and chemical inertness. Although they are very strong in compression, ceramics are susceptible to mechanical and thermal loading, have lower tensile strengths relative to other materials, and are very brittle in tension; this brittleness limits potential biomaterials applications.

Ceramics consist of a network of metal and nonmetal ions, with the general structure X_mY_n, arranged in a repeating structure. This structure depends on the relative size of the ions as well as the number of counterions needed to balance total charge. For example, if $m = n = 1$, and both ions are approximately the same size, then the structure would be of a simple cubic nature (e.g., CsCl or CsI); if the anion is much larger than the cation, then typically, a face centered cubic (fcc) structure would emerge (e.g., ZnS or CdS). If $m = 2$ and $n = 3$, as is the case with oxide ceramics (e.g., Al_2O_3), then a hexagonal closed pack structure would often result (13).

Ceramics used as biomaterials can be classified by processing–manufacturing methods, by chemical reactivity, or by ionic composition. Regarding chemical reactivity, ceramics can be bioinert, bioactive, or bioresorbable. Bioinert or nonresorbable ceramics are either porous or nonporous and are essentially not affected by the environment at the implant site. Bioactive or reactive ceramics are designed with specific surface properties that are intended to react with the local host environment and to elicit a desired tissue response. Bioresorbable ceramics dissolve over some prescribed period of time *in vivo* mediated by physiochemical processes. If one considers the application of bone replacement, then there would be about four ways for ceramics to interact with and attach to bone. First, a nonporous, inert ceramic material could be attached via glues, surface irregularities, or press-filling methods. Second, a porous, inert ceramic could be designed to have an optimal pore size, which promotes direct mechanical attachment of bone through bone ingrowth. Third, a nonporous, inert ceramic with a reactive surface could direct bone attachment via chemical bonding. Fourth, a nonporous or porous, resorbable ceramic could eventually be replaced by bone. When describing real examples of ceramics used as biomaterials, it is more useful to classify the ceramics based on ionic composition. This type of classification reveals a few major bioceramic groups: oxide ceramics, multiple oxides of calcium and phosphorus, glasses and glass ceramics, and carbon.

Oxide Ceramics. As their name implies, oxide ceramics consist of oxygen bound to a metallic species. Oxide ceramics are chemically inert, but can be nonporous or porous. One example of a nonporous oxide ceramic used as a biomaterial is aluminum oxide, Al_2O_3. Highly pure aluminum oxide (F 603 as designated by ASTM International), or alumina, has high corrosion resistance, good biocompatibility, high wear resistance, and good mechanical properties due to high density and small grain size. Aluminum oxide has been manufactured as an acetabular cup for total hip replacement. In comparison with metal or ultrahigh molecular weight polyethylene, Al_2O_3 provides better tribological properties by greatly decreasing friction within the joint and substantially increasing wear resistance. Recently, the FDA approved ceramic on ceramic hip replacements made from alumina and marketed by companies such as Wright Medical Technology and Stryker Osteonics. This ceramic on ceramic design is very resistant to wear and results in a much smaller amount of wear debris than traditional metal–polymer joints. With better wear properties and longer useful lifespan, ceramic on ceramic hip replacements likely will provide an attractive alternative to other biomaterial options, especially for younger patients that need better long-term solutions for joint replacements (4,5,9).

Ceramic oxides can also be porous. In bone formation, these pores are useful for allowing bone ingrowth, which will stabilize the mechanical properties of the implant without sacrificing the chemical inertness of the ceramic material. In general, there are three ways to make a porous ceramic oxide. First, a soluble metal or salt can be mixed with the ceramic and etched away. Second, a foaming agent that evolves gases during heating (e.g., calcium carbonate) can be mixed with the ceramic powder prior to firing. Third, the microstructure of corals can be used as a template to create a ceramic with a high degree



Figure 5. Photographs of (a) a cross-section of human cancellous bone and (b) coral of the genus Porites. These images illustrate how biologically derived materials (e.g., coral) can be used as scaffolds to create ceramic biomaterials that mimic the structure and porosity of natural bone. (Both photographs are used with permission from Biocoral, Inc.)

of interconnectivity and uniform pore size. In this third approach, coral is machined into the desired shape. Then, the coral is heated up to drive off carbon dioxide. The remaining calcium oxide provides a scaffold around which the ceramic material is deposited. After firing, the calcium oxide can be dissolved using hydrochloric acid. This dissolved calcium oxide will leave behind a very uniform and highly interconnected porous structure. Interestingly, the type of coral used will affect the pore size of the resulting ceramic. For example, if the genus *Porites* is used, then the pore size will range from 140 to 160 μm; the genus *Goniopora* will result in a pore size of 200–1000 μm (5). Porous ceramics do have many advantages for bone ingrowth, especially since the porous structure more closely mimics that of cancellous bone (see Fig. 5). However, the porous structure does result in a loss of strength and a tremendous increase in surface area that interacts with an *in vivo* saline environment.

Multiple Oxides of Calcium and Phosphorus. Aside from many types of proteins, the extracellular environment of bone contains a large concentration of organic mineral deposits known as hydroxyapatite. Chemically, hydroxyapatite generally has the following composition: $Ca_{10}(PO_4)_6(OH)_2$. Since hydroxyapatite is a naturally occurring ceramic produced by osteoblasts, it seemed reasonable to apply hydroxyapatite as filler or as a coating to allow better integration with existing bone. Coatings of hydroxyapatite have been applied (usually by plasma spraying) to metallic implants used in applications requiring bone ingrowth to provide a tight fit between bone and the implanted device, to minimize loosening over time, and to provide some measure of isolation from the foreign body response. Although hydroxyapatite is the most commonly used bioceramic containing calcium and phosphorus, there do exist other forms of calcium and phosphorus oxides including tricalcium phosphate, $Ca_3(PO_4)_2$, and octacalcium phosphate, $Ca_8H_2PO_4{\cdot}5H_2O$ (4,5,9,14).

Glasses and Glass Ceramics. Just as in the case of traditional glass, glass ceramics used as biomaterials contain large amounts of silica, SiO_2. Glass ceramics are formed using controlled crystallization techniques during which silica is cooled down at rate slow enough to allow the formation of a hexagonal crystal structure with small, crystalline grains ($\sim$1 μm) surrounded by an amorphous phase. Bioactive glass ceramics have been studied as biomaterials because they can attach directly to tissue via chemical bonds, they have a low thermal coefficient of expansion, they have good compressive mechanical strength, the mechanical strength of the glass–tissue interface is close to that of tissue, and they resist scratching and abrasion. Unfortunately, as with all ceramics, bioactive glasses are very brittle. Two well-known examples of commercially available glass ceramics include Bioglass, which consists of SiO_2, Na_2O, CaO, and P_2O_5, and Ceravital, which contains SiO_2, Na_2O, CaO, P_2O_5, K_2O, and MgO. Relative to traditional soda lime glass, bioactive glass ceramics contain lower amounts of SiO_2 and higher amounts of Na_2O and CaO. The high ratio of CaO to P_2O_5 in bioactive ceramics allows the rapid formation of a hydroxycarbonate apatite (HCA) layer at alkaline pH. For example, a 50 nm layer of HCA can form from Bioglass 45S5 after 1 h. The release of calcium, phosphorus, and sodium ions from bioactive ceramics also allows the formation of a water-rich gel near the ceramic surface. This cationic-rich environment creates a locally alkaline pH that helps to form HCA layers and provide areas of adhesion for biological molecules and cells (4,5,9).

Carbon. Processed carbon has been used in biomaterials applications as a bioceramic coating. Although carbon can exist in several forms (e.g., graphite, diamond), bioceramic carbons consist primarily of low temperature isotropic (LTI) and ultralow temperature isotropic (ULTI) carbon. This form of carbon is synthesized through the pyrolysis of hydrocarbon gases resulting in the deposition of isotropic carbon in a layer $\sim$ 4 mm thick. Advantages to LTI and ULTI carbon include high strength, an elastic modulus close to that of bone, resistance to fatigue compared with other materials, excellent resistance to thrombosis, superior tribological properties, and excellent bond strength with metallic substances. The LTI carbon has been used as a coating for heart valves; however, applications remain limited primarily to coatings due to processing methods (4,5,9).

Polymers

Since the early to mid-twentieth century, the discovery of organic polymerization schemes and the advent of new polymeric species have fueled an incredible interest in the research of biomaterials. The popularity of polymers as potential biomaterials likely stems from the fact that polymers exist in a seemingly endless variety, can be easily fabricated into many forms, can be chemically modified or synthesized with chemically reactive moieties that interact with biological molecules or living tissues and cells, and can have physical properties that resemble that of natural tissues. Some disadvantages to polymeric biomaterials include relatively low moduli, instability following certain forms of sterilization, lot-to-lot variability, a lack of well-defined standards related to manufacturing, processing, and evaluating, and, for some polymers, hydrolytic instability, the need to add potentially toxic polymerization catalysts, and tissue biocompatibility of both the polymer and potential degradation byproducts. There also exist some characteristics of polymers that can be advantageous or disadvantageous depending on the application and type of polymer. Some of these characteristics include polymer degradation, chemical reactivity, polymer crystallinity, and viscoelastic behavior. Early examples of polymeric biomaterials included nylon for sutures and cellulose for kidney dialysis membranes, but more recent developments in the design of polymeric biomaterials are leading the field of biomaterials to embrace cellular and tissue interactions in order to directly induce tissue repair or regeneration.

Polymers consist of an organic backbone from which other pendant molecules extend. As their name implies, polymers consist of repeating units of one or more “mers”. For example, polyethylene consists of repeating units of ethylene; nylon is comprised of repeating units of a diamine and a diacid. In general, polymers used as biomaterials are made in one of two ways: condensation or addition reactions. In condensation reactions, two precursors are combined to form larger molecules by eliminating a small molecule (e.g., water). Examples of condensation polymeric biomaterials include nylon, poly(ethylene terephthalate) (Dacron), poly(lactic acid), poly(glycolic acid), and polyurethane. In addition to synthetic polymers, biological polymers (e.g., cellulose and proteins) are formed through condensation-like polymerization mechanisms. The other major polymerization mechanism used to synthesize polymers is addition polymerization. In addition polymerization, an initiator or catalyst (e.g., free radical, heat, light, or certain ions) is used to promote a rapid polymerization reaction involving unsaturated bonds. Unlike condensation reactions, addition polymerization does not result in small molecular byproducts. Furthermore, polymers can be formed using only one type of monomer or a combination of several monomers susceptible to free radical initiation and propagation. Some examples of addition reaction polymeric biomaterials include polyethylene, poly(ethylene glycol) (PEG), poly(*N*-isopropylacrlyamide), and poly(hydroxyethyl methacrylate) (PHEMA). The chemical structure of various synthetic and natural polymers used as biomaterials are shown in Figs. 6a and b (15).

The properties of polymers are affected greatly by chemical composition and molecular weight. In general, as polymer chains become longer, their mobility decreases, but their strength and thermal stability increases. The tacticity and size of pendant chains off the backbone will affect temperature-dependent physical properties. For example, small side groups that are regularly oriented in an isotactic or syndiotactic arrangement will allow the polymer to crystallize much more readily than a polymer containing an atactic arrangement of bulky side groups. The crystalline and glass transition temperatures of polymers will affect properties (e.g., stiffness, mechanical moduli, and thermal stability) *in vivo* and will consequently influence the potential application and utility of the polymer system as a biomaterial. When the functionality of a monomer exceeds two, then the polymer will become branched upon polymerization. If a sufficient number of these high functionality monomers exist within the material, then the main chains of the polymer will become chemically cross-linked. Cross-linked polymers can be much stronger and more rigid than noncross-linked polymers. However, like linear and branched polymers, cross-linked polymers can be designed such that they degrade through hydrolytic or enzymatic mechanisms.

Due to their weaker moduli compared with that of metals or ceramics, polymers are not often used in load-bearing biomaterial applications. One exception to this observation is the example of ultrahigh molecular weight polyethylene (UHMWPE), which has a molecular weight $\sim 2{,}000{,}000\ \mathrm{g{\cdot}mol^{-1}}$ and has a higher modulus of elasticity than high or low density polyethylene. Additionally, UHMWPE is tough and ductile and demonstrates good wear properties and low friction. As a result, UHMWPE has been used extensively in the manufacturing of acetabular cups for total hip replacements. As an acetabular cup, UHMWPE is used in conjunction with metallic femoral stems to act as a load-bearing, low wear and friction interface. Some drawbacks to using UHMWPE include water absorption, cyclic fatigue, and a somewhat significant creep rate (4,5,9). Part of the problems surrounding UHMWPE involves its lower elastic modulus (~1–2 GPa) relative to bone (~12 GPa) and metallic implants (~100–200 GPa)

Polymers in Sutures. One of the first widespread uses of polymers as biomaterials involved sutures. In particular, polyamides and polyesters are among the most common suture materials. Nylons, an example of a polyamide, have an increased fiber strength due to a high degree of crystallinity resulting from interchain hydrogen bonding between atoms of the amide group. Nylon can be attacked by proteolytic enzymes *in vivo* and can absorb water. As a result, nylon has been used more as a short-term biomaterial. Polyester sutures, such as poly(glycolic acid), poly(lactic acid), and poly(lactic-*co*-glycolic acid) are readily degraded through hydrolytic mechanisms *in vivo*. Since one side chain of lactic acid contains a bulky hydrophobic methyl group (relative to the hydrogen side group of glycolic acid), polyesters comprised principally of lactic acid degrade at a rate slower than that of polyesters consisting mostly of glycolic acid. The degradation rate of copolymers



Figure 6. (a) Chemical schematics representing synthetic polymers used as biomaterials. The structures represent polyethylene (**1**), polytetrafluoroethylene (**2**), poly(vinyl alcohol) (**3**), poly(dimethyl siloxane) (**4**), poly(N-isopropylacrylamide) (**5**), polyanhydride (**6**), poly(ethylene terephthalate) (**7**), poly(methyl methacrylate) (**8**), poly(hydroxyethyl methacrylate) (**9**), poly(glycolic acid) (**10**), poly(lactic acid) (**11**), poly(lactic-co-glycolic acid) (**12**), poly(ethylene oxide) (**13**), and poly(e-caprolactone) (**14**). (Adopted from Ref. 15 with permission from Elsevier.) (b) Chemical schematics representing naturally derived polymers used as biomaterials. The structures represent alginate (**15**), chondroitin-6-sulfate (**16**), chitosan (**17**), hyaluronan (**18**), collagen (**19**), polylysine (**20**), dextran (**21**), and heparin (**22**). (Reprinted from Ref. 15 with permission from Elsevier.)



Figure 7. A photograph of a Carboflo vascular graft made out of expanded polytetrafluoroethylene (ePTFE) impregnated with carbon and marketed by Bard Peripheral Vascular, Inc.

of glycolic and lactic acid can be tailored based on the relative molar ratios of each monomer. Although the local pH of degrading polyesters can cause local inflammation concerns, the degradation byproducts of glycolic and lactic acid can be readily cleared through existing biochemical pathways. As a result, polyester sutures are commonly used within the body in applications where removal of sutures would warrant an invasive procedure (4,5,16).

Polymers in Cardiovascular Applications. Poly(ethylene terephalate) (Dacron) and expanded polytetrafluoroethylene (Teflon) have been used for decades as vascular grafts. An example of a Teflon vascular graft is shown in Fig. 7. Both of these polymers have excellent burst strengths and can be sutured directly to existing vasculature. For applications involving large diameter vascular grafts (> 6 mm), these two materials have worked well. However, neointimal hyperplasia and thrombus formation severely limit the patency of all known polymeric materials used for small diameter vascular grafts (17). Most current strategies to improve vascular graft patency involves chemically modifying the polymers used as vascular grafts to include the anticoagulant heparin, endothelial binding peptide analogues, and growth factors to stimulate endothelialization and minimize proliferation of smooth muscle into the lumen of the graft (15,18).

Polymers for Tissue Engineering. For many *in vivo* applications, researchers continue to evaluate a variety of polymeric biomaterials. Some more recent additions to the repertoire of biomaterials include naturally derived or recombinantly produced biological polymers. As an example, in the case of articular cartilage repair, it is evident that many types of polymers can be designed, modified, or combined with other materials to create new generations of biomaterials that promote healing and/or restore biological function. For example, synthetic polymers, such as poly(vinyl alcohol) (PVA), PMMA, poly(hydroxyethyl methacrylate), poly(*N*-isopropylacrylamide), polyethylene, poly(lactic acid), poly(glycolic acid), poly(lactic-*co*-glycolic acid), and poly(ethylene glycol) and naturally derived polymers (e.g., alginate, agarose, chitosan, hyaluornic acid, collagen, and fibrin) have been studied extensively with and without biochemical modifications to replace cartilage function or to promote neocartilage formation (15,19,20). These and other polymeric biomaterials have been used in studies related to liver, nerve, cardiovascular, bone, ophthalmic, skin, and pancreatic repair or restoration (15,21).

Hydrogels. As the name implies, hydrogels are polymer networks that contain large amounts of water (up to or > 90% water). As a result, hydrogels generally are hydrophilic materials, although, the presence of hydrophobic domains within the hydrogel backbone can enhance mechanical properties. To avoid dissolution into the aqueous phase, the polymeric component of the hydrogel must contain cross-links. The majority of hydrogel systems use chemical cross-links, such as covalent bonds to create a three-dimensional (3D) network; however, some hydrogels exist that rely on physical interactions to maintain gel integrity.

The high water content of hydrogels provides many benefits. First, of all the materials within materials science, the physical and mechanical properties of hydrogels most closely resemble those of biological tissue. Due to their polymeric content, hydrogels exhibit viscoelastic behavior. The elastic modulus, G', of many gel compositions reaches 1 MPa, but some hydrogels can be as strong as 20 MPa. These mechanical properties match well with those reported for many tissues. Second, the large presence of water within hydrogels can limit nonspecific interactions within the body, can shield the polymer from leukocytes and can decrease frictional effects at the site of implantation. Third, the relatively low concentration of polymer within the hydrogel can result in materials with higher porosities. Consequently, it is possible not only for cells to migrate within the hydrogel structure, but also for nutrients and waste products to diffuse into and out of the gel structure (15,22,23).

In addition to high water content, hydrogels possess other characteristics that are beneficial for biomedical applications. For example, chemical composition of polymers used in hydrogel formulations is amenable to chemical modification of the backbone and/or side group structures. These polymer derivatives allow the incorporation of various gelation chemistries, degradation rates and biologically active molecules. Although not a complete list, some of the polymers used as biomaterial hydrogels include poly(ethylene glycol), PVA, poly(hydroxyethyl methacrylate) PHEMA, poly(*N*-isopropylacrylamide), poly(vinyl pyrrolidone), dextran, alginate, chitosan, and collagen. These hydrogels, in addition to many others, are currently being explored as materials for use in cartilage, skin, liver, nerve, muscle, cardiovascular, and bone tissue engineering applications.

Poly(ethylene glycol). One of the most widely studied hydrogel materials is PEG, which contains repeats of the monomer CH_2CH_2O and exhibits a large radius of hydration due to its high hydrophilicity. As a result, PEG can avoid detection by the body, and often is coupled to pharmaceuticals or other molecules to extend circulation half-life within the body. Of all the materials used in biomedical research, few polymers have better biocompatibility properties than PEG. Also, the chemical structure of PEG is fairly stable within aqueous environments, although hydrolytic degradation can occur. Furthermore, removal of PEG from the body is not a major concern since PEG, with a molecular weight $< 20{,}000\,\mathrm{g{\cdot}mol^{-1}}$, can be cleared readily by the kidneys. Traditionally, PEG hydrogels have been cross-linked through chemical initiators, however, other work has shown that photoinitiators can be used to gel PEG *in situ*. Recently, more attention has focused on the use of star PEG, which contain a central core out of which proceeds several linear PEG arms. Consequently, these materials offer improved control over mechanical properties and biological interactions since each molecule of polymer contains many more potential sites for cross-linking or for incorporating biologically active molecules. Cell adhesion peptides, polysaccharides, and polysaccharide ligands have all been coupled to various PEG molecules and studied as biomaterials (15,23,24).

Acrylics. One of the greatest success stories involving polymeric biomaterials involves PMMA and PHEMA. Many polymers have not yet been approved by the FDA. However, many polymers of the acrylic family (e.g., PMMA used for bone cement and intraocular lenses) were grandfathered into the Medical Device Amendments of 1976 as approved materials. The PHEMA polymer allows for sufficient gas exchange, and both PHEMA and PMMA have excellent optical properties and a good degree of hydration. As a result, intraocular lenses, hard, and soft contact lenses (see Fig. 8) made in whole or in part from these polymers are commercially available (3,5). Even though contact lenses only touch the eye on one side, the polymers that comprise the contact lenses are still bathed in tears and are therefore subject to protein deposition. This protein deposition can cause eye irritation and lead to contact lens failure if the contacts are not properly cleaned. With the development of disposable contact lenses, however, the problem of protein buildup can be minimized since the useful lifespan of each contact lens does not have to extend very long.



Figure 8. A photograph of a disposable contact lens made from PHEMA.

Biomimetic Materials. Recently, the field of biomaterials has started to incorporate features found within mechanisms involved in biomolecular assembly and interaction (24). These biomimetic materials show great promise since assembly is directed through biological affinity, recognition and/or interactions. As a result, these materials often have properties more similar to those of natural materials. Biomimetic materials exist as polymer scaffolds and hydrogels, but can also consist of ceramic and metallic materials machined or chemically modified to mimic porous structure of tissue (e.g., bone). Further elucidation of mechanisms responsible for biological self-assembly most likely will lead to improved biomaterials that are capable of interacting very specifically with an environment containing cells, tissue, or ECM molecules. In addition, many researchers are borrowing biological concepts to provide appropriate signals for cellular proliferation or differentiation and to deliver pharmaceuticals in a much more controlled manner. The scanning electron micrograph (SEM) shown in Fig. 9 illustrates a biologically oriented approach of using a biomaterial like chitosan–collagen as a scaffold on which cells can adhere (25).

Drug Delivery. Applications involving biomaterials have evolved from those focused on mostly structural requirements to those combining multiple design considerations including structure, mechanics, degradation, and drug delivery. The latest trend in biomaterials design is to promote healing, repair, or regeneration via the delivery of pharmaceutical agents, drugs, or growth factors. There exist many examples of biomaterials used as delivery vehicles or as drugs (22); however, many of these examples



Figure 9. A SEM showing chondrocytes (denoted by white arrows) attached to a biomaterial scaffold comprised of chitosan-based hyaluronic acid hybrid polymer fibers. (Reprinted from Ref. 25 with permission from Elsevier.)

are just beginning to transition from research materials into commercially available products. One example of a commercially available drug delivery biomaterial is known as Gliadel, made by Guilford Pharmaceuticals. Gliadel wafers consist of a polyanhydride polymer loaded with carmustine, a chemotherapeutic drug. This system is intended as a treatment for malignant gliomas. Following removal of the tumor, the Gliadel wafers are added to the cavity and allowed to degrade and release the carmustine in order to kill remaining tumor cells. In addition to cancer treatments, biomaterials as drug delivery vehicles have been extensively employed in cardiovascular applications. Recently, FDA approval was granted to several types of drug eluting metallic stents. Among these include the Sirolimus-eluting CYPHER stent manufactured by the Cordis Corporation, the TAXUS Express^2 Paclitaxel-eluting stent manufactured by the Boston Scientific Corporation. The purpose behind releasing the drugs from the stents is to decrease the occurrence of restenosis, or the renarrowing of vessels treated by the stent. As a result of the drug delivery aspect of the system, the stents are expected to have better long-term viability. Several more examples of drug delivery and biomaterial hybrid systems exist; however, a comprehensive review of biomaterials as drug delivery systems is beyond the scope of this article. It is important to note that more interest and attention have been given to modify biomaterials so that the material is more integrally involved in interacting with and manipulating organ and tissue biology.

FACTORS CONTRIBUTING TO BIOMATERIAL FAILURE

Although there exists a multitude of commercially available and successful metallic, ceramic, and polymeric biomaterials, biomaterials have and will continue to fail. The human body is a very hostile environment for synthetic and natural materials. In some instances, like orthopedic applications, it is much easier to understand why materials can fail since no material can survive cyclical loading indefinitely without showing signs of fatigue or wear. However, for most biomaterial failures, the exact reason for failure is still not well understood. Some factors contributing to the failure of a biomaterial include corrosion, wear, degradation, and biological interactions.

Corrosion

By weight, more than one-half of the human body consists of water. As a result, all implanted biomaterials will encounter an aqueous environment. Moreover, this aqueous environment is also very saline due to the presence of a relatively large concentration of extracellular salts. The aqueous and saline conditions of physiological solutions create favorable conditions for metallic corrosion. Corrosion involves oxidation and reduction reactions between a metal, ions, and species (e.g., dissolved oxygen). In fact, the lowest free energy state of many metals in and oxygenated and hydrated environment is an oxide. Most corrosion reactions are electrochemical. For example, if zinc metal is placed in an acidic environment (e.g., hydrochloric acid), hydrogen gas will evolve as the zinc become cationic and binds to chloride ions. The actual reaction consists of two half reactions. In the first reaction, zinc metal is oxidized to a Zn^{2+} state; the second reaction involves the reduction of hydrogen ions to hydrogen gas. During this process, the newly formed metal ions diffuse into solution. Both the oxidation and reduction reactions must occur at the same time to avoid charge buildup within the material. This process occurs at the surface and exposed pore of metals, and, in an attempt to passivate the surface to avoid this process, corrosion resistant oxides have been incorporated into an implant surface (13). Care must be taken, however, to ensure that the protective oxide coating is not damaged during processing, packaging, or surgical procedure.

In addition to oxidative corrosion, bimetallic or galvanic corrosion is a concern with implants composed of more than one type of metal, such as alloys with mixing defects and implants containing parts made from distinct metals. Galvanic corrosion can occur because all metals have a different tendency to corrode. If two distinct metals are in contact with one another through a conductive medium, oxidation of one metal will occur while reduction of the other occurs. In both oxidative corrosion and bimetallic corrosion, bits of metal, metal ions, and oxidative debris can enter the surrounding tissue and even travel to distant body parts. This can result in inflammation and even in metal toxicity.

Wear

In addition to corrosion, metal, as well as other materials can wear as a result of friction. For example, in hip implants, the acetabular cup is in contact with the ball of the metal or ceramic stem. Every time a movement occurs within the joint, rubbing between the ball and cup occurs and small wear particles of metal and polymer are left behind (see Fig. 10). More often than not, the particles are shed from the softer surface (e.g., ultrahigh molecular weight polyethylene); however, metal particles are also produced. The particles range in size from



Figure 10. A photograph of some worn biomaterials. Examples in this photograph include screws, a femoral head replacement, and a polyethylene acetabular cup. (Used with permission from the Department of Materials at Queen Mary University of London.)

nanometers to microns with the smaller particles able to enter the lymph fluid and travel to distant parts of the body. The small particles increase the surface area of the material, and this increased surface area can result in increased corrosion (5,13). Thus, wear can lead to deleterious effects (e.g., corrosion), described above, and inflammation, as will be discussed below.

Degradation

Although not affected by corrosion, certain bioactive ceramics and polymers are susceptible to degradation. In the case of bioactive ceramics, however, this process is relatively slow compared with the potential rate of bone regeneration. For polymers, degradation can occur via hydrolytic or, in some cases, enzymatic mechanisms. The chemical structures of both polyamides and polyesters lend themselves toward enzymatic degradation. For polyesters, acidic or alkaline conditions will lead to a deesterification reaction that will eventually destroy the backbone of the polymer. The degradation rate varies greatly depending on the composition of the polymer. For example, within the body, poly(lactic acid) will degrade over many months to years, but poly(glycolic acid) can degrade over a few days or weeks. The degradation rate of polyamides is slower than that of polyesters, but is still an important design consideration when choosing a polymeric biomaterial for a specific application. For applications (e.g., sutures), degradation of the material is a beneficial property since the sutures only need to remain in place for a few days to weeks until the native tissue heals. For applications needing a material with a longer lifespan, degradation poses a larger problem.

Increasingly, degradable polymers or polymers with degradable cross-links are being studied as biomaterials. This interest in degradable systems stems largely from more current research involving tissue engineering and drug delivery (15,16,22,24,26,27). The philosophy of tissue engineering holds that the polymeric biomaterial acts as a scaffold with or without viable cells or biological molecules to promote tissue ingrowth. As cells proliferate and migrate within these scaffolds and begin to create new tissue, the material can and should degrade to leave, ultimately, regenerated or repaired tissue in its place. One of the engineering design constraints, therefore, is to balance the rate of degradation with that of tissue ingrowth. If the biomaterial degrades too rapidly and the newly formed tissue cannot provide the necessary mechanical support, then the biomaterial will have failed. At the same time, if the biomaterial degrades too slowly, then the process of tissue ingrowth may become inhibited or may not occur at all. To this end, more recent research has attempted to include enzymatically sensitive cross-links, usually made from synthetic peptide analogues of enzyme substrates, within polymer networks. Instead of relying upon relatively uncontrolled hydrolytic degradation, the polymeric biomaterial would degrade at a rate controlled by migrating cells. Thus, the cells themselves could degrade the material and produce new tissue in a much more controlled and physiologically relevant manner.

Biological Interactions

Most modern biomaterials are intended to come into direct contact with living tissue and biological fluids. This interaction often makes the biomaterial a target for the protective mechanisms within the body. These protective mechanisms include protein adsorption, hemostasis, inflammation and the foreign body response, and the immune response. Although it has been well established that all types of tissue-contacting biomaterials invoke some degree of biological response, it has only been during the past decade or so when investigations have revealed that all implanted tissue-containing biomaterials invoke an almost identical inflammatory and foreign body response regardless of whether the biomaterial is of metallic, ceramic, polymeric, or composite origin. Although future research in the field of biomaterials aims to better understand and to eventually mitigate the biological interactions that currently result in the failure of many biomaterials, the following biological responses remain of great importance when considering the design and potential applications of any biomaterial. In fact, most current obstacles related to the design of biomaterials involve the interaction of biomaterials with the body and the reaction of the body to biomaterials. As a result, current biomaterial research trends aim to provide an environment that allows the body to invade, remodel, and degrade the implanted material (23,27,28).

Protein Adsorption. As soon as a biomaterial comes into contact with biological fluid (e.g., blood) the material becomes coated with adsorbed proteins. This adsorption is very rapid and is based primarily on noncovalent interactions between various hydrophilic and hydrophobic domains within the adsorbed proteins and the surface of the implanted biomaterial. Initially, the composition of the protein layer depends on the relative concentration of various proteins within the biological fluid. Certain proteins (e.g., albumin) are very abundant in serum and will initially be found abundantly in the adsorbed protein layer. However, over time the adsorbed protein layer will change its composition as proteins with higher affinities for the surface of the material, but lower serum concentrations will displace proteins with lower affinities and higher serum concentrations. This rearrangement and equilibration of the protein layer is known as the Vroman effect. When biomaterials become coated with proteins, surrounding cells no longer see the surface of the material. Instead, they see a layer of serum-soluble proteins. Increasingly, biomaterials design has focused on optimizing surface chemistries and incorporating selective reactive domains that will promote a specific biological response. In reality, these engineered surfaces become masked by a nonspecific protein layer, and it is this protein layer that drives the biological response to an implanted biomaterial. Some successful examples of surface modifications aimed at reducing nonspecific protein adsorption involve the use of nonfouling hydrophilic polymers (e.g., PEG and dextran), the pretreatment of the biomaterial with a specific protein, and the replacement of certain chemically reactive functional groups with others. Time, however, remains the



Figure 11. A schematic representing the temporal events involved in acute and chronic inflammation as well as the foreign body response. (Adopted from Anderson et al. as found in Ref. 5.)

largest obstacle with any of these surface treatments. Often, surface treatments will only function for a limited time before serum and other extracellular proteins becomes adsorbed. Once adsorbed, proteins can undergo conformational changes that expose cryptic sites, allow autoactivation, or that influence the behavior of other proteins or cells (5,6,18).

Blood Contact. Direct contact with blood is a major concern of all biomaterials regardless of whether or not they were designed for cardiovascular applications. During surgical implantation, blood vessels are broken, which results in an increased probability that the biomaterial will contact blood. Although exact mechanisms remain unclear, serum proteins (e.g., Factor XII, Factor XI, plasma prekallikrein, and high molecular weight kininogen) interact to initiate contact activation of the coagulation cascade through the intrinsic pathway. This calcium- and platelet-dependent cyclic network involves the activation of thrombin, which ultimately cleaves specific protein domains within fibrinogen and Factor XIII. Activated Factor XIIIa and fibrinogen then react to form a cross-linked fibrin clot. The formation of blood clots as well as the activation of various serum proteins and platelets can lead to local inflammation. Recent approaches have attempted to passivate the blood contact response of implanted biomaterials by incorporating heparin or other antithrombotic agents on the biomaterial surface (5,6,18).

Inflammation and the Foreign Body Response. The human body is well equipped to handle injuries that affect hemostasis. During trauma, proteins within blood can initiate a relatively large biological response lasting days, weeks, and even months. Initially, the area around a trauma site, including the implantation of a biomaterial, becomes inflamed. Inflammation is a normal process involved with healing that is characterized by four major events: swelling, pain, redness, and heat. The vasculature around an injury will become leaky to allow extravasation of various leukocytes (e.g., neutrophils and macrophages). With the presence of cytokines and other growth factors, leukocytes, primarily macrophages, are stimulated to remove bacteria and foreign material. Macrophages also recruit fibroblasts and other cells to the injury site to aid in healing by forming granulation tissue. Over the course of several days or weeks, this initial granulation tissue is remodeled and replaced with restored, functional tissue or, more commonly, scar tissue (Fig. 11).

In the case of implanted biomaterials, the implantation site is the injury site and will become inflamed. As a result, macrophages will be recruited to the site and attempt to remove the “foreign” biomaterial. Unlike smaller injuries, macrophages are unable to remove biomaterials through phagocytosis. When they become frustrated, macrophages will fuse together to form foreign body giant cells. These foreign body giant cells can secrete superoxides and free radicals, which can damage biomaterials, but these cells usually cannot completely remove the foreign biomaterial. In the event that the body cannot eliminate a foreign object through phagocytosis, activated macrophages and foreign body giant cells remain around the implant and can promote a chronic localized area of inflammation. Remaining fibroblasts and other cells around the biomaterial then will begin to secrete a layer of avascular collagen around the biomaterial to effectively encapsulate it and wall it off from the rest of the body (5,6,18). Although the function of some biomaterials is not affected by this foreign body response, biomaterials ranging from sensors to orthopedic implants to soft tissue replacements are adversely affected by this biological reaction. To date, it is not known how to minimize or eliminate an inflammation or foreign body reaction. However, a great deal of research is attempting to create biomaterials that do not evoke a tremendous inflammatory response or that degrade in a way that allows the restoration or repair of native tissue without the adverse affects of chronic inflammation.

Immune Response. The innate and adaptive immune responses of the body also pose a challenge for biomaterials designed for long-term applications. Increasingly, new biomaterials have attempted to incorporate cellular components in an attempt to create new tissues *in vitro* or to seed materials with autologous, allogeneic, or xenogenic cells, including stem cells, to promote tissue repair. Unfortunately, the adaptive immune response will actively eliminate allogeneic or xenogenic cell types. As a result, biomaterials have been designed to act as barriers that limit lymphocyte activation. Often, cells are encapsulated in microspheres made from various polymers or layers of polymers. For example, pancreatic Islets of Langerhans from animal and human donors have been encapsulated within polymers [e.g., polysulfones, poly(*N*-isopropylacrylamide)] and alginates, to provide an immunoisolated environment that still retains enough permeability to allow for the diffusion of insulin. One of the major complications of this type of biomaterials design is to balance the creation of volume within the microsphere to accommodate enough Islets to allow for sufficient insulin production with the need to provide appropriate diffusion rates so that the cells within the center of the microsphere remain viable. As more polymeric biomaterials incorporate or consist of peptide and protein motifs, there remains a concern as to whether or not these motifs might elicit an adaptive immune response. Even if protein domains derived from human proteins are incorporated into biomaterials, these domains might not be presented the same way to lymphocytes. As a result, the body may start producing antibodies against these domains, which might also lead to certain forms of autoimmune diseases (29).

Although the adaptive immune system is playing an increasingly important role in the rejection of new types of biomaterials, the innate immune system remains a very large threat to the success of a biomaterial. As mentioned above, proteins bind to biomaterials upon implantation. One of the most abundant proteins within the blood is the complement protein C3. Within the blood, C3 can spontaneously hydrolyze to form an active convertase complex, which can cleave C3 into C3a and C3b. Although C3b is rapidly inactivated within the blood, it can remain active if it binds to a surface (e.g., a biomaterial). As a result, the alternative pathway of the complement system can be activated very rapidly leading to formation of membrane-attack complexes but more importantly, the formation of the soluble anaphylotoxins C3a, C4a, and C5a. These anaphylotoxins induce smooth muscle contraction, increase vascular permeability, recruit phagocytic cells, and promote opsonization by phagocytic cells. These phagocytic cells (e.g., macrophages) have receptors recognizing C3b. As a result, macrophages will attempt to engulf the C3b-coated biomaterial. When this fails, the macrophages will form foreign body giant cells, and the body will attempt to encapsulate the biomaterial in a manner similar to that described above for the inflammation and foreign body response (29). Overall, all of the above mentioned biological responses can affect the performance of any biomaterial, and active biomaterials research is striving not only to better understand the mechanisms of inflammation, protein adsorption, hemostasis, and innate and adaptive immune responses, but also to develop strategies to minimize, eliminate, evade, or alter adverse biological responses to materials.

BIOCOMPATIBILITY

Since biomaterials are intended for direct contact with biologically viable tissue, all biomaterials need to possess some degree of biocompatibility. In a manner similar to that of the term biomaterials, the term biocompatibility has experienced many changing definitions over the past several decades. Initially, biocompatibility implied that the biomaterial remained inert to its surroundings in order to refrain from being toxic, carcinogenic, or allergenic. As the definition of biomaterials evolved to include biologically derived materials and molecules, the term biocompatibility needed to encompass these changes. In 1987, David Williams suggested that biocompatibility is "the ability of a material to perform with an appropriate host response in a specific application" (30). Although there does not yet exist a universal consensus with regard to the definition of the term biocompatibility, the definition proposed by Williams provides enough generality to serve as an adequate and accurate description of biocompatibility.

Instead of remaining inert, biomaterials are becoming increasingly reliant on biochemical reactions and physiological processes in order to serve a useful function. In some cases (e.g., in the case of bone plates and artificial joints), biomaterials can remain inert and still provide satisfactory performance. In other instances (e.g., drug delivery vehicles), tissue engineering applications, and *in vivo* organ replacement therapies, biomaterials not only need to actively minimize or adapt to the surrounding biological responses (e.g., inflammation and foreign body responses), but also need to depend on interactions with surrounding tissues and cells in order to provide a useful function (15,22,24–27). In addition, the performance of traditionally inert biomaterials is being enhanced by incorporating chemical or mechanical modifications that interact with biology at the cellular level. For example, the bone-contacting surfaces of metallic femoral stems, for hip replacement, have been modified to contain bioactive ceramic porous networks or hydroxyapatite crystal networks. These ceramic networks allow better osteointegration of the implant with the host tissue and, in some cases, eliminate the need to use bone sealants (e.g., PMMA).

Obviously, if a successful biomaterial needs to show some level of biocompatibility, then there must exist various testing conditions and manufacturing standards to establish safety controls. Organizations [e.g., ASTM International and the International Organization for Standardization (ISO)] do have guidelines and standards for the testing and evaluation of biomaterial biocompatibility. These regulations include tests include the measuring of cytotoxicity, sensitization, skin irritation, intracutaneous reactivity, acute systemic toxicity, genotoxicity, macroscopic and microscopic evaluation of implanted materials and devices, hemocompatibility, subchronic and chronic toxicity, carcinogenicity, the effect of degradation byproducts, and the effect of sterilization (31). For many of these paramenters, the associated standards dictate the size and shape of the material to be tested, appropriate *in vitro* testing procedures and analysis schemes, and relevant testing and evaluation protocols for *in vivo* experimentation. Although standards related to the manufacturing and performance of some biomaterials exist, there remains a lack of uniform biocompatibility testing standards for new classes of biomaterials that rely heavily upon cellular and tissue interactions or that contain biologically active molecules. New developments in biologically active biomaterials have resulted in not only nonuniform approaches to biocompatibility testing, but also confusions related to the regulatory classification of new types of biomaterials.

FUTURE DIRECTIONS

As more information becomes available regarding biological responses to materials, mechanisms that control embryonic development and early wound healing, and matrix biology, materials will be designed to more adequately address, promote or inhibit biological responses as needed. As a result, the field of biomaterials will not only incorporate principles from materials science and engineering, but also rely increasingly upon design constraints governed by biology (see Fig. 12). Recent trends in biomaterial research show an increased emphasis in designing materials that better match the biological environment with respect to mechanics and biological signals. Materials promote cell attachment using biologically derived signals, degrade through relevant enzymatic degradation and release and store bioactive factors using methods derived from biology. Continued adaptation of materials to more appropriately interact with the living system will result in devices that work with the body to promote tissue regeneration and healing.


Factors to Consider When Designing a New Biomaterial
Required Mechanical Properties
Required Degradation Rate
Required Porosity
Materials Science and Engineering
Moldability or Shapability
Required Surface Properties
New Material for Tissue Regeneration
Inhibit Immune and Foreign Body Reactions
Required Bioactivity
Biology and medicine
Growth Factor Requirements
How to Connect New Tissue to Existing Vasculature
Number of Cell Types to Support
Nutrient Requirements

Figure 12. An illustration depicting the various engineering and biological factors that need to be considered in the design of modern biomaterials. Successful, new biomaterials will require the optimization of a variety of parameters and the cooperation of interdisciplinary scientists, engineers, and clinicians. (Reprinted from Ref. 15 with permission from Elsevier.)

BIBLIOGRAPHY

Cited References

1. Black J. The education of the bio-materialist—report of a survey. 1980–1981. J Biomed Mater Res 1982;16(2):159–167.
2. Galletti PM, Boretos JW. Report on the consensus development conference on clinical-applications of biomaterials, 1–3 november 1983. J Biomed Mater Res 1983;17(3):539–555.
3. Lindstrom RL. The polymethylmetacrylate (pmma) intraocular lenses. In: Steinert RF, et al. editors. Cataract surgery: Technique, Complications, and Management. Philadelphia: Saunders; 2003.
4. Barbucci R, editor. Integrated Biomaterials Science. New York: Kluwer Academic; 2002.
5. Ratner BD, Hoffman AS, Schoen FJ, Lemons JE, editors. Biomaterials Science: An Introduction to Materials in Medicine. San Diego: Academic Press; 1996.
6. Greco RS, editor. Implantation Biology: The Host Response and Biomedical Devices. Boca Raton (FL): CRC Press; 1994.
7. Lysaght MJ, O'Loughlin JA. Demographic scope and economic magnitude of contemporary organ replacement therapies. Asaio J 2000;46(5):515–521.
8. Harris G. Step forward for implants with silicone. New York: The New York Times; 2005.
9. Park JB, Lakes RS. Biomaterials: An introduction. 2nd ed. New York: Plenum Press; 1992.
10. Black J, Hastings G, editors. Handbood of Biomaterial Properties. New York: Chapman & Hall; 1998.
11. Wen CE, et al. Novel titanium foam for bone tissue engineering. J Mater Res 2002;17(10):2633–2639.
12. Graham, et al. The use of SMARTeR stents in patients with binary obstrevition. Cliro Radiol 2004;59:288–291.
13. Smith WF, Foundations of Materials Science and Engineering. 2nd ed. New York: McGraw-Hill, Inc.; 1993.
14. Fernandez E, et al. Calcium phosphate bone cements for clinical applications—part ii: Precipitate formation during setting reactions. J Mater Sci-Mater M 1999;10(3):177–183.
15. Seal BL, Otero TC, Panitch A. Polymeric biomaterials for tissue and organ regeneration. Mater Sci Eng R 2001; 34(4–5):147–230.
16. Langer R. 1994 Whitaker lecture—polymers for drug-delivery and tissue engineering. Ann Biomed Eng 1995;23(2): 101–111.
17. Greenwald SE, Berry CL. Improving vascular grafts: The importance of mechanical and haemodynamic properties. J Pathol 2000;190(3):292–299.
18. Dee KC, Puleo DA, Bizios R. An Introduction to Tissue-Biomaterial Interactions. Hoboken (NJ): John Wiley & Sons, Inc.; 2002.
19. Temenoff JS, Mikos AG. Review: Tissue engineering for regeneration of articular cartilage. Biomaterials 2000;21 (5):431–440.
20. Temenoff JS, Mikos AG. Injectable biodegradable materials for orthopedic tissue engineering. Biomaterials 2000;21(23): 2405–2412.
21. Palsson BØ, Bhatia SN. Tissue Engineering. Upper Saddle River (NJ): Pearson Prentice Hall; 2004.
22. Peppas NA, Bures P, Leobandung W, Ichikawa H. Hydrogels in pharmaceutical formulations. Eur J Pharm Biopharm 2000;50(1):27–46.
23. Hubbell JA. Biomaterials in tissue engineering. Bio-Technol 1995;13(6):565–576.
24. Sakiyama-Elbert SE, Hubbell JA. Functional biomaterials: Design of novel biomaterials. Ann Rev Mater Res 2001;31: 183–201.

25. Yamane S, et al. Feasebelety of chitosan-based hyaluronic acid hybrid biomaterial for a novel scaffold in cartilage tissue engineering. Biomaterials 2005;26:611–619.
26. Gupta P, Vermani K, Garg S. Hydrogels: From controlled release to ph-responsive drug delivery. Drug Discov Today. 2002;7(10):569–579.
27. Ratner BD, Bryant SJ. Biomaterials: Where we have been and where we are going. Annu Rev Biomed Eng 2004;6:41–75.
28. Ratner BD. New ideas in biomaterials science—a path to engineered biomaterials. J Biomed Mater Res 1993;27(7): 837–850.
29. Janeway CA, Travers P, Walport M, Shlomchik MJ. Immunobiology: The Immune System in Health and Disease. 6th ed. New York: Garland Science; 2005.
30. Williams D. Revisiting the definition of biocompatibility. Med Device Technol 2003;14(8):10–13.
31. Bollen LS, Svensen O. Regulatory guidelines for biocompatibility safety testing. Med Plastics Biomater 1997;(May): 16.

See also Alloys, shape memory; biomaterials: bioceramics; biomaterials, corrosion and wear of; biomaterials, testing and structural properties of; polymeric materials.

BIOMATERIALS: BIOCERAMICS

Julian R. Jones
Larry L. Hench
Imperial College London

INTRODUCTION

During the last century, there has been a revolution in orthopedics with a shift in emphasis from palliative treatment of infection in bone to interventional treatment of chronic age-related ailments. The evolution of stable metallic fixation devices, and the systematic development of reliable total joint prostheses were critical to this revolution in health care. Two alternative pathways of treatment for patients with chronic bone and joint defects are now possible: (*1*) transplantation or (*2*) implantation. Figure 1 shows how approaches to tissue repair have changed and how we think they need to develop.

At present the “gold standard” for the clinical repair of large bone defects is the harvesting of the patient’s tissue from a donor site and transplanting it to a host site, often maintaining blood supply. This type of tissue graft (an *autograft*) has limitations; limited availability, morbidity at the donor site, tendency toward resorption, and a compromise in biomechanical properties compared to the host tissue.

A partial solution to some of these limitations is use of transplant tissue from a human donor, a *homograft*, either as a living transplant (heart, heart-lung, kidney, liver, retina) or from cadavers (freeze-dried bone). Availability, the requirement for lifetime use of immunosuppressant drugs, the concern for viral or prion contamination, ethical, and religious concerns all limit the use of homografts.

The first organ transplant (homograft) was carried out in Harvard in 1954. In the United States alone, there are now >80,000 organs needed for transplantation at one time, only a quarter of which will be found. The shortage of donors increases every year.

A third option for tissue replacement is provided by transplants (living or nonliving) from other species called *heterografts* or *xenografts*. Nonliving, chemically treated xenografts are routinely used as heart valve replacements (porcine) with ~50% survivability after 10 years. Bovine bone grafts are still in use, but concern of transmission of prions (disease transmission) is growing.

The second line of attack in the revolution to replace tissues was the development of manmade materials to interface with living, host tissues (e.g., implants or prostheses made from biomaterials). There are important advantages of implants over transplants, including



Figure 1. Schematic of the past, present and future of the treatment for diseased and damaged tissue.

availability, reproducibility, and reliability. Failure rate of the materials used in most prostheses are very low, at $< 0.01\%$ (1). As a result, survivability of orthopedic implants such as the Charnley low friction metal–polyethylene total hip replacement is very high up to 15 years (2).

Many implants in use today continue to suffer from problems of interfacial stability with host tissues, biomechanical mismatch of elastic moduli, production of wear debris, and maintenance of a stable blood supply. These problems lead to accelerated wear rates, loosening and fracture of the bone, interface or device that become worse as the patient ages (3). Repair of failed devices, called revision surgery, also becomes more difficult as the patient ages due to decreased quality of bone, reduced mobility, and poorer circulation of blood. In addition, all present day orthopedic implants lack two of the most critical characteristics of living tissues: (*1*) ability to self-repair; and (*2*) ability to modify their structure and properties in response to environmental factors such as mechanical load. The consequences of these limitations are profound. All implants have limited lifetimes. Many years of research and development have led to only marginal improvements in the survivability of orthopedic implants for >15years.

Ideally, artifical implants or devices should be designed to stimulate and guide cells in the body to regenerate tissues and organs to a healthy and natural state. We need to shift our thinking toward regenerative medicine (Fig. 1) (4).

BIOCERAMICS AS MEDICAL DEVICES

A bioceramic is a ceramic that can be implanted into a patient without causing a toxic response. Bioceramics can be classified into three categories; resorbable (e.g., tricalcium phosphate), bioactive (e.g., bioactive glass, hydroxyapatite), and nearly inert materials (e.g., alumina and zirconia) (5). A bioactive material is defined as a material that elicits a specific biological response at the interface of the material, which results in a formation of a bond between the tissue and that material (6). Bioceramics can be polycrystalline (alumina or hydroxyapatite), bioactive glass, bioactive glass–ceramic (apatite/ wollastonite, A/W), or used in bioactive composites such as polyethylene–hydroxyapatite.

This article begins with examples of successful bioceramics used clinically that improve the length and quality of life for patients. Developments of porous bioceramic and composite scaffolds for tissue engineering applications are then discussed. The article ends by discussing how bioactive ceramics may be the future of regenerative medicine due to their potential for guiding tissue regeneration by stimulating cells at the genetic level (Fig. 1).

NEARLY INERT BIOCERAMICS

High density, high purity α-alumina (Al_2O_3) was the first bioceramic widely used clinically, as the articulating surfaces of the ball and socket joints of total hip replacements because of its combination of low friction, high wear resistance, excellent corrosion resistance, good biocompatibility, and high strength (7). The physical properties of alumina depend on the grain size. Medical grade alumina exhibits an average grain size <4 μm, a compressive strength of 4.5 GPa and a Young's modulus of 400 GPa (8). Other clinical applications of Al_2O_3 include bone screws, jaw and maxillofacial reconstructions, middle ear bone substitutions, and dental implants.

Zirconia is a bioinert ceramic that has higher flexural strength and fracture toughness and a lower Young's modulus than alumina. Zirconia may therefore be suitable for bearing surfaces in total hip prostheses, however, there are concerns over the wear rate and radioactivity of the material in the body (9).

When an almost inert implant is implanted into soft or hard tissue, a nonadherent fibrous capsule surrounds the implant. If the implant is loaded such that interfacial movement can occur, the fibrous capsule can become several hundred micrometers thick and cause loosening of the implant, which will eventually lead to clinical failure (8).

An improved interface between nearly inert implants and tissue can be achieved by using an implant containing pores in excess of 100 μm in diameter. The fibrous connective (scar) tissue grows into these pores and anchors the implant in place. This technique is termed "biological fixation" (10). Viable bone requires pores of > 200 μm. However, connective tissue still allows some movement of the prothesis, which will increase with age and cause bone resorption.

THE CHALLENGE FOR BIOCERAMICS

Bone is a natural composite of collagen (type I) fibers, noncollagenous proteins, and mineralized bone. It is a rigid material that exhibits a hierarchical structure with an outer layer of dense cortical bone and an internal structure of porous cancellous and trabecular (spongy) bone. Trabecular bone is orientated spongy bone that is found at the end of long bones and in vertebras (11). This structure provides excellent mechanical properties: cortical bone exhibits a compressive strength of 100–230 MPa and a Young's modulus of 7–30 GPa; cancellous bone exhibits a compressive strength of 2–12 MPa and a Young's modulus of 0.05–0.5 GPa (8). Bone is generated by cells called osteoblasts and resorbed by cells called osteoclasts, which remodel the bone in response to external stimuli such as mechanical load (11). In order to regenerate bone, the implant should exhibit a Young's modulus similar to that of the bone. If the modulus of the implant is higher than the bone then stress shielding can occur, where the stem supports the total load. If this occurs, osteoclasts resorb bone from the implant interface (12). An example of this is the use of alumina as in total hip replacements. Alumina exhibits a modulus 10–50 times higher than cortical bone. If the modulus of the implant is substantially lower than the bone, the implant is unlikely to be able to withstand the loading environment and will fracture.

Ceramics have the potential to prevent stress-shielding and have many properties that can aid bone regeneration (8). Therefore, we will concentrate on the use of bioceramics in orthopedics, but will also describe adaption for soft tissue applications.

Osteoporosis is a condition where the density and strength of the trabecular bone decreases (13), due to osteoblasts becoming progressively less active and the pore walls (trabeculae) in the internal spongy bone are reduced in thickness and number causing spinal problems, hip fracture, and subsequent hip replacement operations.

The challenge for bioceramics is to replace old, deteriorating bone with a material that can function for as long as is needed, which may be > 20 years. There are two options to satisfy increasing needs for orthopedic repair in the new millennium: (*1*) improve implant survivability by 10–20 years; or (*2*) develop alternative devices that can regenerate tissues to their natural form and function. Decades of research have not been able to achieve the first, discussion of the second, the application of bioactive bioceramics, and their role in regenerative medicine, particularly in bone regeneration follows.

RESORBABLE BIOCERAMICS

Tricalcium phosphate (TCP) resorbs on contact with body fluid. Resorbable materials are designed to dissolve at the same rate that a tissue grows, so that they eventually are totally replaced by the natural host tissue. However, matching the resorption rate of TCP with bone growth is difficult and since TCP ceramics exhibit low mechanical strength, so they cannot be used in load bearing applications (14).

THE BIOACTIVE ALTERNATIVE

During the last decade, considerable attention has been directed toward the use of bioceramic implants with bioactive fixation, where bioactive fixation is defined as interfacial bonding of an implant to tissue by means of formation of a biologically active hydroxyapatite layer on the surface of the implant. This layer bonds to the biological apatite in bone (8).

An important advantage of bioactive fixation is that a bioactive bond forms at the implant–bone interface with a strength equal to, or greater than, bone after 3–6 months. The level of bioactivity of a specific material can be related to the time taken for $> 50\%$ of the interface to bond to bone ($t_{0.5\text{bb}}$) (15);

$$\text{Bioactivity index}, I_\text{B} = 100/t_{0.5\text{bb}} \tag{1}$$

Materials exhibiting an I_B value > 8 (class A), will bond to both soft and hard tissue. Materials with an I_B value < 8 (class B), but > 0, will bond only to bone. Biological fixation is capable of withstanding more-complex stress states than implants that only achieve morphological fixation, that is surface fixation to roughness (15). There are a number of bioactive bioceramics.

SYNTHETIC HYDROXYAPATITE

Synthetic hydroxyapatite (HA) $Ca_{10}(PO_4)_6(OH)_2$ has been developed to match the biological apatite in bone. Biological apatite, although similar, exhibits different stoichiometry, composition, and crystallinity to pure HA. Biological apatites are usually calcium deficient and carbonate substituted (primarily for phosphate groups) (16). Hydroxyapatite is a class B bioactive material, that is, it bonds only to bone and promotes bone growth along its surface (osteoconduction). The mechanism for bone bonding involves the development of a cellular bone matrix on the surface of the HA, producing an electron dense band 3–5 μm wide. Collagen bundles appear between this area and the cells. On contact with body fluid, a dissolution–precipitation process occurs at the HA surface resulting in the formation of carbonated apatite microcrystals, which are similar to biological HA and are incorporated into the collagen. As the site matures, collagen fibrils mineralize and the interfacial layer decreases in thickness as crystallites of the growing bone align with those of the implant. Commercial production methods for synthetic HA usually involve a dropwise addition of phosphoric acid to a stirring suspension of calcium hydroxide in water, which causes an apatite precipitate to form. Ammonia is added to keep the pH very alkaline and to ensure formation of HA when the precipitate is sintered at 1250 °C. Commercial dense HA exhibits a compressive strength in excess of 400 MPa and a Young's modulus of 12 GPa. There are many clinical applications for HA implants including the repair of bony defects and tooth root replacement (16).

Hydroxyapatite has also been used as a plasma-sprayed coating on porous metallic implants in total hip replacements, allowing a bond to form between the bone and the implant (17). Initial bone ingrowth is more rapid than uncoated porous metallic implants, but the long-term survivability of the implants will not be known until after 10-year follow-up clinical trails have been completed.

BIOACTIVE GLASSES

Bioactive glasses are class A bioactive materials (I_B value > 8) that bond to soft and hard tissue and are osteoconductive, which means that bioactive glass implants stimulate bone formation on the implant away from the host bone–implant interface (15). Bioactive glasses undergo surface dissolution in a physiological environment in order to form a hydroxycarbonate apatite (HCA) layer. This is very similar to the carbonate-substituted apatite in bone. The higher the solubility of a bioactive glass, the more pronounced is the effect of bone tissue growth. The structures of bioactive glasses are based on a cross-linked silica network modified by cations. The original bioactive glasses were developed by Hench and colleagues in the early 1970s (18) and were produced using conventional glass melt-processing techniques with a composition of 45S5, 46.1% SiO_2, 24.4% NaO, 26.9% CaO, and 2.6% P_2O_5, in mol percent. This composition was given the name Bioglass.

MECHANISM OF BIOACTIVITY OF BIOACTIVE GLASSES

When a glass reacts with an aqueous solution, both chemical and structural kinetic changes occur as a function of time within the glass surface (8). Accumulation of dissolution products causes both the chemical composition and pH of solution to change. The formation of HCA on bioactive glasses and the release of soluble silica to the surrounding tissue are key factors in the rapid bonding of these glasses to tissue and the stimulation of tissue growth.

There are 11 stages in process of complete bonding of bioactive glass to bone. Stages 1–5 are chemical; stages 6–11 are biological (4,15);

1. Rapid exchange of Na^+ and Ca^{2+} with H^+ or H_3O^+ from solution (diffusion controlled with a $t^{1/2}$ dependence, causing hydrolysis of the silica groups, which creates silanols;

   $$\mathrm{Si{-}O{-}Na^+ + H^+ + OH^- \rightarrow Si{-}OH^+ + Na^+_{(aq)} + OH^-}$$

   The pH of the solution increases as a result of H^+ ions in the solution being replaced by cations.
2. The cation exchange increases the hydoxyl concentration of the solution, which leads to attack of the silica glass network. Soluble silica is lost in the form of $Si(OH)_4$ to the solution, resulting from the breaking of Si–O–Si bonds and the continued formation of Si–OH (silanols) at the glass solution interface:

   $$\mathrm{Si{-}O{-}Si + H_2O \rightarrow Si{-}OH + OH{-}Si}$$

   This stage is an interface-controlled reaction with a $t^{1.0}$ dependance.
3. Condensation and repolymerization of a SiO_2-rich layer on the surface, depleted in alkalis and alkali earth cations:
4. Migration of Ca^{2+} and ${PO_4}^{3-}$ groups to the surface through the SiO_2-rich layer, forming a $CaO–P_2O_5$-rich film on top of the SiO_2-rich layer, followed by growth of the amorphous $CaO–P_2O_5$-rich film by incorporation of soluble calcium and phosphates from solution.
5. Crystallization of the amorphous $CaO–P_2O_5$ film by incorporation of OH^- and ${CO_3}^{2-}$ anions from solution to form a mixed-HCA layer.
6. Adsorption and desorption of biological growth factors, in the HCA layer (continues throughout the process) to activate differentiation of stem cells.
7. Action of macrophages to remove debris from the site.
8. Attachment of stem cells on the bioactive surface.
9. Differentiation of stem cells to form bone growing cells, such as osteoblasts.
10. Generation of extra cellular matrix by the osteoblasts to form bone.
11. Crystallization of inorganic calcium phosphate matrix to enclose bone cells in a living composite structure.

Interfacial bonding occurs with bone because of the biological equivalence of the inorganic portion of bone and the growing HCA layer on the bioactive implant. For soft tissues, the collagen fibrils are chemisorbed on the porous SiO_2-rich layer via electrostatic, ionic and/or hydrogen bonding, and HCA is precipitated and crystallized on the collagen fiber and glass surfaces.

Reaction stages one and two are responsible for the dissolution of a bioactive glass, and therefore greatly influence the rate of HCA formation. Studies have shown that the leaching of silicon and sodium to solution, from melt-derived bioactive glasses, is initially rapid, following a parabolic relationship with time for the first 6 h of reaction, then stabilizes, following a linear dependence on time, which agree with the dissolution kinetics of soda lime–silica glasses:

$$Q = Kt^{\gamma} \quad \text{for total diffusion, or more generally} \qquad (2)$$

$$Q = at^{\gamma} + bt \quad \text{for total diffusion and selective leaching} \qquad (3)$$

where Q is the quantity of alkali ions from the glass, t is the duration of experiment, a,b are empirically determined constants, K is the reaction rate constant, assuming constant glass area and temperature, and $\gamma = 1/2$ (for stage 1) or 1 (for stage 2); as $t \rightarrow 0$ $\gamma = 1/2$, as $t \rightarrow \infty$ $\gamma = 1$ (19).

Phosphorous and calcium contents of the solution follow a similar parabolic trend over the first few hours, after which they decrease, corresponding with the formation of the Ca–P-rich film (stage 4). The pH change of the solution mirrors dissolution rates. An initial rapid increase of pH is a result of ion exchange of cations such as Na^+ from the glass with H^+ from solution during the first minutes of reaction at the bioactive glass surface. As release rate of cations decreases, the solution pH value tends toward a constant value.

For bioactive implants, it is necessary to control the solubility (dissolution rate) of the material. A low solubility material is needed if the implant is designed to have a long life, for example, a coating on orthopedic metals, such as synthetic hydroxyapatite on a titanium alloy femoral stem. A high solubility implant is required if it is designed to aid bone formation, such as 45S5 Bioglass powders for bone graft augmentation. A fundamental understanding of factors influencing solubility and bioreactivity is required when developing new materials for *in situ* tissue regeneration and tissue engineering.

FACTORS AFFECTING THE DISSOLUTION AND BIOACTIVITY OF GLASSES

Many factors affect the dissolution rate, and therefore bioactivity of bioactive glasses. The composition, initial pH, ionic concentration, and temperature of the aqueous environment have a large effect on the dissolution of the glass. The presence of proteins in the solution has been found to reduce dissolution rates due to the adsorption of serum proteins onto the surface of the bioactive glass, which form a barrier to nucleation of the HCA layer (19).

A change in geometry and surface texture of an implant will generally mean a change in the surface area/solution volume ratio (SA/V). An increase in the SA/V generally causes an increase in the dissolution rate, as the amount of surface exposed to solution for ion exchange increases. An increase in SA/V can be caused by a decrease in particle size or by an increase in surface roughness or porosity (19). A similar effect occurs if the volume of surrounding solution increases (20).

If silicate glasses are considered to be inorganic polymers of silicon cross-linked by oxygen, the network connectivity is defined as the average number of cross-linking bonds for elements other than oxygen that form the backbone of a silicate glass network. The network connectivity can be used to predict solubility (21). Calculation of network connectivity is based on the relative numbers of network forming oxide species (those that contribute to cross-linking or bridging) and network-modifiers (nonbridging) present. Silicate structural units in a glass of low network connectivity are probably of low molecular mass and capable of going into solution. Consequently, glass solubility increases as network connectivity is reduced. The network connectivity can be used to predict bioactivity. Crystallization of a glass inhibits its bioactive properties, because ion exchange is inhibited by crystalline phases, and interferes with network connectivity.

Slight deviations in glass composition can radically alter the dissolution kinetics and the basic mechanisms of bonding. It is widely accepted that increasing silica content of melt-derived glass decreases dissolution rates by reducing the availability of modifier ions such as Ca^{2+} and HPO^{4-} to the solution and the inhibiting development of a silica-gel layer on the surface. The result is the reduction and eventual elimination of the bioactivity of the melt-derived bioactive glasses as the silica content approaches 60%. The addition of multivalent cations, such as alumina, stabilizes the glass structure by eliminating nonbridging oxygen bonds reducing the rate of break-up of the silica network and reducing the rate of HCA formation. Melt-derived glasses with > 60 mol% silica are not bioactive. In order to obtain bioactivity at silica levels > 60 mol%, the sol–gel process is used, which is a novel processing technique for the synthesis of tertiary bioactive glasses.

CLINICAL APPLICATIONS OF MELT-DERIVED BIOACTIVE GLASSES

Bioactive glasses have been used for >15 years to replace the small bones of the middle ear (ossicles) damaged by chronic infection (22). The glass bonds to the soft tissue of the eardrum and to the remaining bone of the stapes footplate, anchoring both ends of the implant without the formation of fibrous (scar) tissue.

In 1993, particulate bioactive glass, 45S5 Bioglass was cleared in the United States for clinical use as a bone graft material for the repair of periodontal osseous defects (Perioglas, USBiomaterials Alachua, Florida). The glass powder is inserted into the cavities in the bone between the tooth and the periodontal membrane and the tooth, which have eroded due to periodontitis. New bone is rapidly formed around the particles restoring the anchorage of the tooth in place (23). Since 1993, numerous oral and maxillofacial clinical studies have been conducted to expand the use of this material. More than 2,000,000 reconstructive surgeries in the jaw have been done using Perioglas. The same material has been used by several orthopedic surgeons to fill a variety of osseous defects and for clinical use in orthopedics, now termed NovaBone, it is now approved for clinical use worldwide.

GLASS-CERAMICS

Bioactive glasses and sintered HA do not have mechanical properties as high as that of cortical bone. Kokubo et al. (24) developed dense apatite/ wollastonite (A/W) glass-ceramics by heating crushed quenched melt-derived glass (MgO 4.6, CaO 44.7, SiO_2 34.0, P_2O_5 6.2, CaF_2 0.5 wt%) to 1050 °C at a rate of 5 °C · min. Oxyapatite (38 wt%) and β-wollastonite (34 wt%) precipitated and were homogeneously dispersed in a glassy matrix (28 wt%). A/W glass-ceramic (Cerabone) has a compressive strength of 1080 MPa and a Young's modulus of 118 GPa, an order of magnitude higher than cortical bone. On contact with body fluid, the A/W glass-ceramic forms a surface layer of carbonated apatite (HCA) similar to biological apatite. The release of calcium to solution causes a hydrated silica layer to form on the glass phase, providing nucleation sites for the HCA layer. Figure 2 shows how A/W glass-ceramics bond to bone more rapidly than sintered HA, but less rapidly than Bioglass. The A/W glass-ceramics are not resorbable, but due to the high compressive strengths A/W glass-ceramics are used as replacement vertebrae, iliac prostheses and in a granular form as bone defect fillers.

SOL–GEL-DERIVED BIOACTIVE GLASSES

Until the late 1980s, bioactive glasses were generally melt-derived, with the majority of research aimed at the 45S5 Bioglass composition (46.1% SiO_2, 24.4% NaO, 26.9% CaO,



Figure 2. Graph of rate of bone ingrowth into the spaces between bioactive ceramic particles (diameters 300–500 μm) as a function of implantation time for Bioglass (BG), A/ W glass–ceramics (A/ W) and sintered hydroxyapatite (s-HA).

and 2.6% P_2O_5, in mol%) and apatite-wollastanite (A/W) glass-ceramics. The recognition that the silica gel layer plays a role in HCA nucleation and crystallization led to the development of the bioactive three component $CaO–P_2O_5–SiO_2$ sol–gel-derived glasses by Li et al. (25).

A sol is a dispersion of colloidal particles (solid particles with diameters 1–100 nm) in a liquid. A gel is an interconnected, rigid network of polymeric chains with average lengths > 1 μm in a continuous fluid phase and pores of submicrometer dimensions.

There are three methods that are used to produce sol–gel monoliths (26):

1. Network growth of discrete colloidal powders in solution.
2. Simultaneous hydrolysis and polycondensation of alkoxide or nitrate precursors, followed by hypercritical point drying of gels.
3. Simultaneous hydrolysis and polycondensation of alkoxide precursors, followed by ageing and drying under ambient conditions.

The pore liquid is removed from the three-dimensional (3D) network as a gas phase. A gel is defined as dried when the physically absorbed water is completely evacuated. This occurs between 100 and 180 °C. Homogeneous gel–glasses are only obtained when a sol–gel method using alkoxide precursors is employed (i.e., methods 2 or 3).

Liquid alkoxide precursors, such as $Si(OR)_4$, where R is CH_3, C_2H_5, and so on, are mixed with a solvent (usually water) and a catalyst. Tetraethylorthosilicate (TEOS) and tetramethylorthosilicate (TMOS) are the alkoxide precursors most commonly used for sol–gel derived silica. Hydrolysis and condensation (aqueous and alcoholic) reactions follow, forming a 3D SiO_2 network of continuous Si–O–Si links that span throughout the solvent medium. When sufficient interconnected Si–O–Si bonds are formed in a region, they respond cooperatively as a sol. A silica network is formed by the condensation reactions and the sol becomes a gel when it becomes rigid and it can support a stress elastically. The gel point is characterized by a steep increase in elastic and viscous moduli. A highly interconnected 3D gel network is obtained, composed of $(SiO_4)_4$ tetrahedra bonded either to neighboring silica tetrahedra via bridging oxygen (BO) bonds or by Si–O–Ca or Si–O–P nonbridging (NBO) bonds. The gel consists of interpenetrating solid and liquid phases: the liquid (a byproduct of the polycondensation reactions) prevents the solid network from collapsing and the solid network prevents the liquid from escaping. The gel is aged at ~60 °C to allow cross-linking of silica species and further network formation. The liquid is then removed from the interconnected pore network by evaporation of the solvent at elevated temperature to form a "xerogel". During this stage, the gel network undergoes considerable shrinkage and weight loss. This stage is critical in obtaining crack-free bodies as large capillary stresses can develop due to solvent evaporation through the pore network. To prevent cracking, the drying process must be controlled by decreasing liquid surface energy, by controlling the rates of hydrolysis and condensation using the precursors, and controlling the thermal drying conditions carefully. Extending the ageing time can help prevent cracking during drying (27). However, even under optimum conditions it is difficult to produce multicomponent crack-free silica-based glasses with diameters in excess of 10 mm.

Dried xerogels have a very large concentration of silanols on the surface of the pores, which renders them chemically unstable at room temperature. The gel is stabilized by sintering at > 500 °C, which removes chemically active surface groups (such as silanols or trisiloxane rings) from the pore network, so that the surface does not rehydroxylate in use. Thermal methods are most common, but chemical methods, involving replacing silanols with more hydrophobic and less reactive species are also possible.

In multicomponent systems, the stabilization process also decomposes other species in the gel such a nitrates or organics. In this thesis nitrates are present after drying. Such species are a source of inhomogeneity and are biologically toxic. Pure $Ca(NO_3)_2$ decomposes at 561 °C, therefore thermal stabilization must be carried out above this temperature.

Sol–gel derived bioactive glasses exhibit a mesoporous texture, that is, pores with diameters in the range 2–50 nm that are inherent to the sol–gel process. The textural properties of the glass are affected by each stage of the sol–gel process, that is, temperature, sol composition, ageing, drying rate, and stabilization temperatures and rates.

Advantages of Sol–Gel-Derived Glasses

There are several advantages of a sol–gel-derived glass over a melt-derived glass, which are important for biomedical applications. Sol–gel-derived glasses have (26):

1. Lower processing temperatures (600–700 °C for gel–glasses compared to 1100–1300 °C for melt-derived glasses).
2. The potential of improved purity, required for optimal bioactivity due to low processing temperatures and high silica and low alkali content.
3. Improved homogeneity.
4. Wider compositions can be used (up to 90 mol% SiO_2) while maintaining bioactivity.
5. Better control of bioactivity by changing composition or microstructure.
6. Structural variation can be produced without compositional changes by control of hydrolysis and polycondensation reactions during synthesis.
7. A greater ease of powder production.
8. Interconnected nanometer scale porosity that can be varied to control dissolution kinetics or be impregnated with biologically active phases such as growth factors.
9. A higher bioactivity due to the textural porosity (SA/V ratio two orders of magnitude higher than melt-derived glasses).
10. Gel–glasses are resorbable and the resorption rate can be controlled by controlling the mesoporosity.

11. Can be foamed to provide interconnected pores of 10–200 μm, mimicking the architecture of trabecular bone.

The mechanism for HCA formation on bioactive gel–glasses follows most of the same 11 stages as those for melt-derived glasses except that dissolution rates are much higher due to the mesoporous texture which creates a higher SA/ V ratio, increasing the area of surface exposed for cation exchange (stage 1) and silica network break-up (stage 2). There are also more sites available for HCA layer formation (19).

FEATURES OF CLASS A BIOACTIVE MATERIALS

An important feature of Class A bioactive materials is that they are osteoproductive as well as osteoconductive. In contrast, Class B bioactive materials exhibit only *osteoconductivity*, defined as the characteristic of bone growth and bonding along a surface. Dense synthetic HA ceramic implants exhibit Class B bioactivity. *Osteoproduction* occurs when bone proliferates on the surfaces of a material due to enhanced osteoblast activity. Enhanced proliferation *and* differentiation of osteoprogenitor cells, stimulated by slow resorption of the Class A bioactive particles, are responsible for osteoproduction.

Is Bioactive Fixation the Solution?

During the last decade, it has been assumed that improved interfacial stability achieved with bioactive fixation would improve implant survivability. Clinical trials have shown this to often not be the case. Replacement of the roots of extracted teeth with dense HA ceramic cones to preserve the edentulous alveolar ridge of denture wearers resulted in generally <50% survived at only 5 years. Early use of HA-coated orthopedic implants seldom survived 10 years >85% figure for cemented total hip prostheses (1). However, long-term success rates of bioactive HA coatings have improved during the last decade due to greater control of the coating process. The survivability of HA coated femoral stems is now equivalent at 10 years to cemented prostheses. It will take another 5 years to know if survivability is superior when HA coatings are used.

Why is bioactive fixation not a panacea to hip implant survivability? There are three primary reasons: (*1*) metallic prostheses with a bioactive coating still have a mismatch in mechanical properties with host bone, and therefore less than optimal biomechanical and bioelectric stimuli, at the bonded interface; (*2*) the bioactive bonded interface is unable to remodel in response to applied load; and (*3*) use of bioactive materials does not solve the problem of osteolysis due to wear debris generated from the polyethylene cups. Use of alumina–alumina bearing surfaces eliminates most wear debris from total hip prostheses, but increases the cost of the prosthesis by 200–300%. For younger patients the cost is acceptable, but for the general population it often is considered to be too expensive.

Most biomaterials in use today and the prostheses made from the materials have evolved from trial and error experiments. Optimal biochemical and biomechanical features that match living tissues have not been achieved, so it also is not surprising that long-term implant survivability has not been improved very much during the last 15 years.

THE BIOCOMPOSITES ALTERNATIVE

Bone is a natural composite of collagen fibers (polymer) and mineral (ceramic). Therefore to create an implant that mimics the mechanical properties of bone, a composite should provide high toughness, tensile strength, fatigue resistance, and flexibility while maintaining modulus similar to bone. Biocomposites are being developed to eliminate elastic modulus mismatch and stress shielding of bone. Two approaches have been tried. Bioinert composites, such as carbon–carbon fiber composite materials, are routinely used in aerospace and automotive applications. These lightweight, strong, and low modulus materials would seem to offer great potential for load-bearing orthopedic devices. However, delamination can occur under cyclic loading that releases carbon fibers into the interfacial tissues. The carbon fibers can give rise to a chronic inflammatory response. Thus, bioinert composites are not widely used and are unlikely to be a fruitful direction for development in the next decade.

BIOACTIVE COMPOSITES

The second approach is to make a bioactive composite that does not degrade, such as pioneered by at the IRC in Biomedical Materials, University of London. Bonfield and co-workers (28) increased the stiffness of a biocompatible polymer (polyethylene) from 1 to 8 GPa by adding a secondary phase with higher modulus (HA). The compressive strength of the composite, now called HAPEX, was 26 MPa. Addition of HA also meant that the composite would also bond to bone. Applications for HAPEX have included ossicular replacement prostheses and the repair of orbital floors in the eye socket. Ideally, it is possible to match the properties of both cancellous and cortical bone, although this is seldom achieved by the biocomposites available today. A challenge for the next decade is to use advanced materials processing technology to improve the interfacial bonding between the phases and reduce the size of the second-phase particles, thereby increasing the strength and fracture toughness of these new materials.

Another option is to use a resorbable polymer matrix for a biocomposite that will be replaced with mineralizing bone as the load on the device is increased. Work in this area is in progress, but it is difficult to maintain structural integrity as resorption occurs. The tissue engineering alternative is based upon this concept (29). Further details on biomedical composites can be found in a review by Thompson and Hench (30).

A NEW REVOLUTION IN ORTHOPEDICS?

We suggest that the orthopedics revolution of the last 30 years, the revolution of replacement of tissues by transplants and implants, has run its course. It has led to a remarkable increase in the quality of life for millions of patients; total joint prostheses provide excellent performance and survivability for 15–20 years. Prostheses will still be the treatment of choice for many years to come for patients of 70 years or older. However, continuing the same approach of the last century; that is, modification of implant materials and designs is not likely to reach a goal of 25–30 years implant survivability, an increasing need of our ageing population. We need a change in emphasis in orthopedic materials research; in fact, we need a new revolution.

BIOCERAMICS IN REGENERATIVE MEDICINE

The challenge for the next millennium in bioceramics and biomedical materials in general is to shift the emphasis of research toward assisting or enhancing the body's own reparative capacity. We must recognize that within our cells lies the genetic information needed to replicate or repair any tissue. We need to learn how to activate the genes to initiate repair at the right site.

Our goal of regeneration of tissues should involve the restoration of metabolic and biochemical behavior at the defect site, which would lead to restoration of biomechanical performance, by means of restoration of the tissue structure leading to restoration of physiological function.

The concept requires that we develop biomaterials that behave in a manner equivalent to an autograft, that is, what we seek is a *regenerative allograft* or *scaffold*. This is a great challenge. However, the time is ripe for such a revolution in thinking and priorities. Regenerative medicine encompasses many fields. We concentrate here on the use of bioceramics in tissue engineering and regeneration applications that require scaffolds to promote tissue repair. Tissue regeneration techniques involve the use of a scaffold that can be implanted into a defect to guide and stimulate tissue regrowth *in situ*. The scaffold should resorb as the tissue grows, leaving no trace. In tissue engineering applications, the scaffolds are seeded with cells *in vitro* to produce the basis of a tissue before implantation; cells extracted from a patient, seeded on a scaffold of the desired architecture and the replacement tissue grown in the laboratory, ready for implantation. The use of the patient's own cells from the same patient would eliminate any chance of immunorejection (31).

GENETIC CONTROL BY BIOACTIVE MATERIALS

We have now discovered the genes involved in phenotype expression and bone and joint morphogenesis, and thus are on the way toward learning the correct combination of extracellular and intracellular chemical concentration gradients, cellular attachment complexes, and other stimuli required to activate tissue regeneration *in situ*. Professor Julia Polak's group at the Imperial College London Centre for Tissue Engineering and Regenerative Medicine has recently shown that seven families of genes are up- and down-regulated by bioactive glass extracts during proliferation and differentiation of primary human osteoblasts *in vitro* (32). These findings should make it possible to design a new generation of bioactive materials for regeneration of bone. The significant new finding is that low levels of dissolution of the bioactive glass particles in the physiological environment exert a genetic control over osteoblast cell cycle and rapid expression of genes that regulate osteogenesis and the production of growth factors.

Xynos et al. (33) showed that within 48 h a group of genes was activated including genes encoding nuclear transcription factors and potent growth factors. These results were obtained using cultures of human osteoblasts, obtained from excised femoral heads of patients (50–70 years) undergoing total hip arthroplasy.

In particular, insulin-like growth factor (IGF) II, IGF-binding proteins, and proteases that cleave IGF-II from their binding proteins were identified (34). The activation of numerous early response genes and synthesis of growth factors was shown to modulate the cell cycle response of osteoblasts to the bioactive glasses and their ionic dissolution products. These results indicate that bioactive glasses enchance osteogenesis through a direct control over genes that regulate cell cycle induction and progression. However, these molecular biological results also confirm that the osteoprogenitor cells must be in a chemical environment suitable for passing checkpoints in the cell cycle toward the synthesis and mitosis phases. Only a select number of cells from a population are capable of dividing and becoming mature osteoblasts. The others are switched into apoptosis and cell death. The number of progenitor cells capable of being stimulated by a bioactive medium decreases as a patient ages, which may account for the time delay in formation of new bone in augmented sites.

Enormous advances have been made in developmental biology, genetic engineering, cellular and tissue engineering, imaging and diagnosis, and in microoptical and micromechanical surgery and repair. Few of these advances have, as yet, been incorporated with the molecular design of new biomaterials. This must be a high priority for the next two decades of research. However, for large defects a scaffold is required to guide tissue regeneration in 3D. Ideally, the scaffold should also release active agents that can also stimulate the cells within the tissue.

AN IDEAL SCAFFOLD

An ideal scaffold is one that mimics the extracellular matrix of the tissue that is to be replaced so that it can act as a 3D template on which cells attach, multiply, migrate, and function. The criteria for an ideal scaffold for bone regeneration are that it (35,36):

1. Is made from a material that is biocompatible (i.e., not cytotoxic).
2. Acts as template for tissue growth in 3D.
3. Has an interconnected macroporous network containing pores with diameters in excess of 100 μm for cell penetration, tissue ingrowth and vascularization, and nutrient delivery to the center of the regenerating tissue on implantation.
4. Bonds to the host tissue without the formation of scar tissue (i.e., is made from an bioactive and osteoconductive–osteoproductive material).

5. Exhibits a surface texture that promotes cell adhesion, adsorption of biological metabolites.
6. Influences the genes in the bone generating cells to enable efficient cell differentiation and proliferation.
7. Resorbs at the same rate as the tissue is regenerated, with degradation products that are nontoxic and that can be easily be excreted by the body, for example, via the respiratory or urinary systems. Is made from a processing technique that can produce irregular shapes to match that of the defect in the patient. Has the potential to be commercially producible to the required ISO (International Standards Organization) or FDA (Food and Drug Administration) standards.
8. Can be sterilized and maintained as a sterile product to the patient.
9. Can be produced economically to be covered by national and/ or private healthcare insurances.

For *in situ* bone regeneration applications, the mechanical properties of the scaffold are also critical and the modulus and elastic strength the scaffold should be similar to that of the natural bone. However, for tissue engineering applications only the mechanical properties of the final tissue engineered construct are critical (36).

TYPES OF BIOCERAMIC SCAFFOLD

Many types of porous bioceramics have been developed and are reviewed in Ref. (37). The simplest way to generate porous scaffolds from ceramics such as HA or TCP is to sinter particles. Particles are usually mixed with a wetting solution, such as poly(vinyl alcohol), and compacted by cold isostatic pressing to form a "green" body, which is sintered (heated to ~1200 °C) to improve mechanical properties. Porosity can be increased by adding fillers such as sucrose to the powder and the wetting solution, which burnout on sintering. Komlev et al. (38) produced porous HA scaffolds with interconnected interparticle pore diameters of ~100 μm, and a tensile strength of ~0.9 MPa by sintering HA spheres 500 μm in diameter.

Other techniques include adding a combustible organic material to a ceramic powder burned away during sintering leaving closed pores; freeze drying where ice crystals are formed in ceramic slurries and then sublimation of the ice leaves pores; polymer foam replication where the ceramic slurry is poured into a polymer foam, which is then burnt out on sintering leaving a pore network. Most of these techniques produced porous ceramics that were not suitable for tissue engineering applications. Typical problems were either that the pore diameters were too low, the pores were closed, the pore distributions were very heterogeneous or mechanical strengths were very low.

Recently, rapid prototyping has been adapted for producing scaffolds with controlled and homogeneous interconnected porosity (39). Rapid prototyping is a generic term for a processing technique that produces materials in a shape determined by CAD (computer aided design) software on a computer. Such materials are usually built up layer-by-layer using a liquid phase or slurry of the material that cures or sets on contact with a substrate. Specific techniques include stereolithography, selective laser sintering, fused deposition modeling and ink-jet printing. It is a challenge to apply these techniques to direct processing of bioactive ceramic scaffolds.

Perhaps the most successful technique for synthesis of porous HA that could be produced in any size of shape, with interconnected macropore diameters in excess of 100 μm is the gel-casting process.

GEL-CASTING OF HA

In the gel-casting of HA, aqueous suspensions of HA particles, dispersing agents, and organic monomers (6 wt% acrylate/diene) are foamed. The organic monomers must be water soluble and retain a high reactivity. Foaming is the incorporation of air into a ceramic to produce a porous material. Once the slurry has foamed, *in situ* polymerization of the monomers is initiated and cross-linking occurs, forming a 3D polymeric network (gel), which produces strong green bodies. Foaming is achieved by vigorous agitation at 900 rpm with the addition of a surfactant (Tergitol TMN10; polyethylene glycol trimethylnonyl ether) under a nitrogen atmosphere (40). Surfactants are macromolecules composed of two parts, one hydrophobic and one hydrophilic. Owing to this configuration, surfactants tend to adsorb onto gas–liquid interfaces with the hydrophobic part being expelled from the solvent and a hydrophilic part remaining in contact with the liquid. This behavior lowers the surface tension of the gas–liquid interfaces, making the foam films thermodynamically stable, which would otherwise collapse in the absence of surfactant (41). Once stable bubble formation is achieved, the polymerization process is initiated using ammonium persulphate and a catalyst (TEMED, *N*,*N*,*N'*,*N'*-tetramethylethylenediamine) and the viscous foam is cast into moulds immediately prior to gelation. The surfactant stabilises the air bubbles until gelation provides permanent stability (40).

The porous green bodies are then sintered to provide mechanical strength and to burnout the organic solvents. Foam volume (and hence porosity) can be controlled by the surfactant concentration in the slurry. The materials produced exhibited interconnected pores of maximum diameter of 100–200 μm, which is ideal for tissue engineering applications.

The gel-cast HA scaffolds satisfy many of the criteria of the ideal scaffold, however, the criteria of controlled resorbability and genetic stimulation are not fulfilled. A bioactive glass scaffold would fulfil these criteria and also be able to bond to soft tissue. However, producing a 3D macroporous scaffold from a glass is difficult.

POROUS MELT-DERIVED BIOACTIVE GLASSES

Theoretically, the gel-casting process could be applied to melt-derived bioactive glass powders. However, such glasses undergo surface reactions on contact with solutions to produce an HCA surface layer and it is desirable to control the reaction before a scaffold is ready for clinical use.

Livingston et al. (42) produced a simple sintered scaffold by mixing 45S5 melt-derived bioactive glass (Bioglass) powders, with a particle size range of 38–75 μm, with 20.2 wt% camphor ($C_{10}H_{16}O$) particles, with particle size range of 210–350 μm. The mixture was dry pressed at 350 MPa and heat treated at 640 °C for 30 min. The camphor decomposed to leave porous Bioglass blocks. Macropores were in the region of 200–300 μm in diameter, however, the total porosity was just 21% as there were large distances between pores.

Yuan et al. (43) produced similar scaffolds by foaming Bioglass 45S5 powder with a dilute H_2O_2 solution and sintered at 1000 °C for 2 h to produce a porous glass–ceramic. The pores were irregular in shape and relatively few in number, implying that interconnectivity was poor, but pore diameters were in the range 100–600 μm. The pores appeared to be more like orientated channels running through the glass, rather than an interconnected network. The samples were implanted into the muscle of dogs and were found for the first time to be osteoinductive. Bone was formed directly on the solid surface and on the surface of crystal layers that formed in the inner pores. Osteogenic cells were observed to aggregate near the material surface and secrete bone matrix, which then calcified to form bone. However, although the implants had a porosity of ~30% only 3% bone was formed. It seems that creating interconnected pore networks in bioactive glasses by sintering is not practical at the present time, although sol–gel derived bioactive glasses may do so.

SOL–GEL DERIVED BIOACTIVE GLASS FOAMS: AN IDEAL SCAFFOLD?

The foaming process has also been applied to sol–gel derived bioactive glasses (44). The resulting scaffolds exhibit the majority of the criteria for an ideal scaffold.

Figure 3 shows an scanning electron microscopy (SEM) micrograph of a typical foam of the 70S30C composition (70 mol% SiO_2, 30 mol% CaO). The scaffolds have a hierarchical pore structure similar to that of trabecular bone, with interconnected macropores with diameters in excess of 100 μm and a textural porosity with diameters in range 10–20 nm (mesopores), which are inherent to the sol–gel process. The scaffolds have the potential to guide tissue growth, with the interconnected macropores providing channels for cell migration, tissue ingrowth, nutrient delivery, and eventually vascularisation (blood vessel ingrowth throughout the regenerated tissue). The mesoporous texture enhances the resorbability and biaoctivity of the scaffolds and provides nucleation points for the HCA layer and sites for cell attachment for anchorage dependant cells such as osteoblasts. The bioactive glass composition contributes high bioactivity, controlled resorbability, and the potential for the ionic dissolution products (Si and Ca) to stimulate the genes in bone cells to enhance bone regeneration.

Figure 4 shows a flow chart of the sol–gel foaming process. Sol–gel precursors [e.g., tetraethoxyl orthosilicate (TEOS, $Si(OC_2H_5)_4$] are mixed in deionized water in the presence of an acidic hydrolysis catalyst. Simultaneous hydrolysis and polycondensation reactions occur beginning with the formation of a silica network. Viscosity of the sol increases as the condensation reaction continues and the network grows. Other alkoxides–salts can be added to introduce network modifiers (e.g., CaO species). On completion of hydrolysis, the sol is foamed by vigorous agitation with the addition of a surfactant. A gelling agent [hydrofluoric acid (HF), a catalyst for polycondensation] is added to induce a rapid increase in viscosity and reduce the gelling time.

The surfactant stabilized the bubbles that were formed by air entrapment during the early stages of foaming by lowering the surface tension of the solution. As viscosity rapidly increased and the gelling point was approached, the solution was cast into airtight moulds. The gelling point is the point at which the meniscus of the foamed sol does not move, even if the mold is tilted. Casting must



Figure 3. An SEM micrograph of a sol–gel derived bioactive glass foam scaffold.


Sol-preparation from a mixture of alkoxides
(HNO3, TEOS, Ca(NO3)2)
Mixed in stoichiometric proportions depending on glass composition required
Sol + gelling agent + surfactant.
Foaming by vigorous agitation as viscosity increases
Pouring of foamed mixture into moulds.
Completion of gelation
Ageing at 60 °C
Drying at 130 °C
Thermal stabilization at 600–800 °C

Figure 4. Flow chart of the sol–gel foaming process.

take place immediately prior to the gelation point. The gelation process provided permanent stabilization for the bubbles.

A foam scaffold is produced that sits in the liquid mixture of water and alcohol (pore liquor) produced as a byproduct of the polycondensation reaction. The foams are then subjected to the thermal treatments of ageing, drying, and stabilization. Ageing is done at 60 °C, leaving the foam immersed in its pore liquor. Ageing allows further cross-linking of the silica network and a thickening of the pore walls. Pore coarsening also occurs when larger pores grow at the expense of smaller ones.

Drying involves the evaporation of the pore liquor, which is critical and must be carried out under very carefully controlled conditions to prevent cracking under capillary pressure. Silica-based glasses that only contain the textural mesopores cannot be produced as monoliths with diameters in excess of 10 mm due to the high capillary stresses during drying. The formation of interconnected pore channels with large diameters allows efficient evaporation of the pore liquor; therefore very large crack-free scaffolds (in excess of 100 mm diameter) can be made. Thermal stabilization is carried out (again under carefully controlled heating regimes) at a minimum of 600 °C to ensure removal of silanol and nitrate groups from the glass.

The variables in each stage of the foaming process affect the final structure and properties of the foams (45,46). The percentage and pore volume of the textural mesopores can be controlled by the glass composition and the alkoxide: water ratio in initial sol preparation. Therefore the resorbability and bioactivity of the scaffolds can be easily controlled. The macropore diameters are little affected until the sintering temperature increases >800 °C. However, the glass composition, the foaming temperature, the surfactant concentration and type, the gelling agent concentration heavily affect the macropore diameters, and interconnectivity, which are vital for tissue engineering applications.

Three compositions have been successfully foamed; the tertiary 58S (60 mol% SiO_2, 36 mol% CaO, 4 mol% P_2O_5), the binary 70S30C (70 mol% SiO_2, 30 mol% CaO) composition, and 100S silica. The binary composition 70S30C (70 mol% SiO_2, 30 mol% CaO) has been found to be the most suitable to the foaming process, producing crack-free foams scaffolds with porosities in the range 60–95% (depending on the other variables in the process). Macropores were homogeneously distributed with diameters up of up to 600 μm and modal interconnected pore diameters of up to 150 μm.

Due to the nature of the sol–gel process the scaffolds can be produced in many shapes, which are determined simply by the shape of the casting mould. The scaffolds can be produced from various compositions of gel-derived glasses. All foam compositions can be easily cut to a required shape. Figure 5 shows foams produced in various shapes.



Figure 5. Sol–gel derived bioactive glass scaffolds. (Courtesy of Dr. P. Sepulveda.)

The only criterion not addressed is the matching of mechanical properties of the scaffolds to bone for *in situ* bone regeneration applications. The compressive strength of the foams (~2.5 MPa for 70S30C foams sintered at 800 °C) is less than that of trabecular bone (~10 MPa). However, the mechanical properties of these foams should be sufficient for tissue engineering applications, where bone would be grown on a scaffold in the laboratory before implantation. Work on improving the mechanical properties is ongoing.

BIOLOGICAL RESPONSES TO SOL–GEL DERIVED BIOACTIVE GLASSES

The biological response to bioactive gel–glasses made from the $CaO–P_2O_5–SiO_2$ system provides evidence that bone regeneration is feasible. An important factor for future research is that the structure and chemistry of bioactive gel–glasses can be tailored at a molecular level by varying the composition (such as SiO_2 content) or the thermal or environmental processing history. The compositional range for Class A bioactive behavior is considerably extended for the bioactive gel–glasses over Class A bioactive glasses and glass–ceramics made by standard high temperature melting or hot pressing. Thus, gel–glasses offer several new degrees of freedom over the influence of cellular differentiation and tissue proliferation. This enhanced biomolecular control will be vital in developing the matrices and scaffolds for engineering of tissues and for the *in vivo* regenerative allograft stimulation of tissue repair.

Evidence of the regenerative capacity of bioactive gel–glasses powders is based on a comparison of the rates of proliferation of trabecular bone in a rabbit femoral defect (47). Melt-derived Class A 45S5 bioactive glass particles exhibit substantially greater rates of trabecular bone growth and a greater final quantity of bone than Class B synthetic HA ceramic or bioactive glass–ceramic particles. The restored trabecular bone has a morphological structure equivalent to the normal host bone after 6 weeks; however, the regenerated bone still contains some of the larger (>90 μm) bioactive glass particles. Wheeler et al. (48) showed that the use of bioactive gel–glass particles in the same animal model produces an even faster rate of trabecular bone regeneration with no residual gel–glass particles of either the 58S or 77S composition. The gel–glass particles resorb more rapidly during proliferation of trabecular bone. Thus, the criteria of a regenerative allograft cited above appear to have been met. Recent results of *in vivo* subperiosteum implantation of 58S foams on the calvaria of New Zealand rabbits (49) showed that bone regeneration occurred more rapidly for 58S foams compared to 58S powder and that the regeneration was in line with that produced by compacted melt-derived Bioglass powders that are available commercially as Perioglas and Novabone.

SOFT TISSUE ENGINEERING

The interactions between cells and surfaces play a major biological role in cellular behavior. Cellular interactions with artificial surfaces are mediated through adsorbed proteins. A common strategy in tissue engineering is to modify the biomaterial surface selectively to interact with a cell through biomolecular recognition events. Adsorbed bioactive peptides can allow cell attachment on biomaterials, and allow 3D structures modified with these peptides to preferentially induce tissue formation consistent with the cell-type seeded, either on or within the device (50). The surface of the gel-derived foams has been modified with organic groups and proteins to create scaffolds that have potential for lung tissue engineering (50,51). If cells can recognize the proteins adsorbed on the surface of a biomaterial they can attach to it and start to differentiate, inducing tissue regeneration. However, if cells do not recognize the proteins, an immunogenic response may result, initiating a chronic inflammation that can lead to failure of the device. Besides promoting cell-surface recognition, bioactive peptides can be used to control or promote many aspects of cell physiology, such as adhesion, spreading, activation, migration, proliferation, and differentiation.

Three-dimensional scaffolds have been produced that allow the incorporation and release of biologically active proteins to stimulate cell function. Laminin was adsorbed on the textured surfaces of binary 70S30C (70 mol% SiO_2–30 mol% CaO) and ternary 58S (60 mol% SiO_2–36 mol% CaO–4 mol% P_2O_5) sol–gel derived bioactive foams. The covalent bonds between the binding sites of the protein and the ligands on the scaffolds surface do not denaturate the protein. *In vitro* studies show that the foams modified with chemical groups and coated with laminin maintained bioactivity, as demonstrated by the formation of the (HCA) layer formed on the surface of the foams on exposure to simulated body fluid (SBF). Sustained and controlled release from the scaffolds over a 30-day period was achieved. The laminin release from the bioactive foams followed the dissolution rate of the material network. These findings suggest that bioactive foams have the potential to act as scaffolds for soft tissue engineering with a controlled release of proteins that can induce tissue formation or regeneration.

The way that proteins or other bioactive peptides interact with surfaces can alter their biological functionality. In order to achieve full functionality, peptides have to adsorb specifically. They also must maintain conformation in order to remain functional biologically. Chemical groups, such as amine and mercaptan groups, are known to control the ability of surfaces to interact with proteins (51). In addition, these chemical groups can allow protein–surface interactions to occur such that the active domains of the protein can be oriented outward, where they can be maximally effective in triggering biospecific processes. Cell cultures of mouse lung epithelial cells (MLE-12) on modified 58S foam scaffolds showed that cells attached and proliferated best on 58S foam modified with amine groups (using aminepropyltriethoxysilane, APTS) and coated with laminin (52).

SUMMARY

During the last century, a revolution in orthopedics occurred that has led to a remarkably improved quality of life for millions of aged patients. Specially developed bioceramics were a critical component of this revolution. However, survival of prostheses appears to be limited to ~20 years. We conclude that a shift in emphasis from replacement of tissues to regeneration of tissues should be the challenge for orthopedic materials in the new millennium. The emphasis should be on the use of materials to activate the body's own repair mechanisms, that is, regenerative allografts. This concept will combine the understanding of tissue growth at a molecular biological level with the molecular design of a new generation of bioactive scaffolds that stimulate genes to activate the proliferation and differentiation of osteoprogenitor cells and enhance rapid formation of extracellular matrix and growth of new bone *in situ*. The economic and personal benefits of *in situ* regenerative repair of the skeleton on younger patients will be profound.

BIBLIOGRAPHY

Cited References

1. Jones JR, Hench LL. Biomedical materials for the new millennium: A perspective on the future. J Mat Sci T 2001;17: 891–900.
2. Ratner BD, Hoffman AS, Schoen FJ, Lemmons JE. Biomaterials Science: An Introduction to Materials in Medicine. London: Academic Press; 1996.
3. Berry DJ, Harmsen WD, Cabanela ME, Morrey MF. Twenty-five-year survivorship of two thousand consecutive primary Charnley total hip replacements. J Bone Jt Surg 2002;84A(2): 171–177.
4. Hench LL, Polak JM. Third generation biomedical materials. Science 2002;295(5557):1014–1018.
5. Hench LL, Wilson J. An Introduction to Bioceramics. Singapore: World Scientific; 1993.
6. Hench LL. Biomaterials: A forecast for the future. Biomaterials 1998;19:1419–1423.
7. Black J, Hastings G. Handbook of Biomaterial Properties. London: Chapman and Hall; 1998.
8. Hench LL. Bioceramics. J Am Ceram 1998;81(7):1705–1728.
9. Hulbert SF. The use of alumina and zirconia in surgical implants. In: Hench LL, Wilson J, editors. An Introduction to Bioceramics. Singapore: World Scientific; 1993.
10. Hulbert SF, Bokros JC, Hench LL, Heimke G. Ceramics in Clinical Applications: Past, Present, and Future. In: Vincenzini P, editor. High tech Ceramics. Amsterdam: Elsevier; 1987.
11. Bilezikian JP, Raisz LG, Rodan GA. Principles of bone biology. London: Academic Press; 1996.

12. Sumner DR, Galante JO. Determinants of stress shielding—design versus materials versus interface. Clin Orthop Relat R 1992;274:202–212.
13. Marcus R, Feldman D, Kelsey JL. Osteroporosis. London: Academic Press; 1996.
14. de Groot K. Bioceramics of Calcium Phosphate. Boca Raton, FL: CRC Press; 1983.
15. Hench LL, West JK. Biological applications of bioactive glasses. Life Chem Rep 199;13:187–241.
16. LeGeros RZ, LeGeros JP. Dense Hydroxyapatite. In: Hench LL, Wilson J, editors. An Introduction to Bioceramics. Singapore: World Scientific; 1993.
17. Ducheyne P, Hench LL, Kagan A, Martens M, Burssens A, Mulier JC. The effect of hydroxyapatite impregnation of skeletal bonding of porous coated implants. J Biomed Mater Res 1980;14:225–237.
18. Hench LL, Splinter RJ, Allen WC, Greenlee TK. Bonding mechanism at the interface of ceramic prosthetic implants. J Biomed Mater Res 1971;74:1478–1570.
19. Sepulveda P, Jones JR, Hench LL. *In vitro* dissolution of melt-derived 45S5 and sol–gel derived 58S bioactive glasses. J Biomed Mater Res 2002;61(2):301–311.
20. Jones JR, Sepulveda P, Hench LL. Dose-dependent behaviour of bioactive glass dissolution. J Biomed Mater Res 2001;58:720–726.
21. Wallace KE, Hill RG, Pembroke JT, Brown CJ, Hatton PV. Influence of sodium oxide content on bioactive glass properties. J Mater Sci Mater Med 1999;10(12):697–701.
22. Wilson J, Douek E, Rust K. Bioglass® Middle Ear Devices: 10 Year Clinical Results. In: Hench LL, Wilson J, Greenspan DC, editors. Bioceramics 8. Oxford: Pergamon; 1995. p 239–245.
23. Fetner AE, Hartigan MS, Low SB. Periodontal repair using Perioglas® in non-human primates: Clinical and histologic observations. Comp Cont E Dent 1994;15(7):932–939.
24. Kokubo T, Ito S, Shigematsu M, Sakka S, Yamamuro T, Higashi S. Mechanical properties of a new type of apatite containing glass-ceramic for prosthetic application. J Mater Sci 1985;20:2001–2004.
25. Li R, Clark AE, Hench LL. Effect of structure and surface area on bioactive powders made by sol–gel process. In: Hench LL, West JK, editors. Chemical Processing of Advanced Materials. Vol. 56, New York: John Wiley & Sons; 1992. 627–633.
26. Hench LL, West JK. The Sol–Gel Process. Chem Rev 1990;90: 33–72.
27. Ishizaki K, Komarneni S, Nanko M. Sol–Gel Processing: Designing Porosity, Pore Size and Polarity and Shaping Processes. In: Ishizaki K, Komarneni S, Nanko M, editors. Porous Materials: Process Technology and Applications. London: Kluwer Academic Publishers; 1998. p 67–180.
28. Huang J, DiSilvo L, Wang M, Tanner KE, Bonfield W. *In vitro* mechanical and biological assessment of hydroxyapatite-reinforced polyethylene composite. J Mat S-M M 1997;8: 775–779.
29. Day R, Boccaccini AR, Roether JA, Surey S, Forbes A, Hench LL, Gabe S. The effect of Bioglass® on epithelial cell and fibroblast proliferation and incorporation into a PGA matrix. Gastroenterology 2002;122(4) T875 Suppl 1.
30. Thompson ID, Hench LL. Medical Applications of Composites. Comprehensive Composite Mater 2000; (6.39) 727–753.
31. Ohgushi H, Caplan AI. Stem Cell Technology and Bioceramics: From cell to Gene Engineering. J Biomed Mater Res B 1999;48:913–927.
32. Hench LL, Polak JM, Xynos ID, Buttery LDK. Bioactive Materials to Control Cell Cycle. Mat Res Innovat 2000;3: 313–323.
33. Xynos ID, Hukkanen MVJ, Batten JJ, Buttery LD, Hench LL, Polak JM. Bioglass® 45S5 Stimulates Osteoblast Turnover and Enhances Bone Formation In Vitro: Implications and Applications for Bone Tissue Engineering. Calciff Tiss 2000;67:321–329.
34. Xynos ID, Edgar AJ, Buttery LD, Hench LL, Polak JM. Ionic Dissolution Products of Bioactive Glass Increase Proliferation of Human Osteoblasts and Induce Insulin-like Growth Factor II mRNA Expression and Protein Synthesis, Biochem Biophys Res 2000;276:461–465.
35. Freyman TM, Yannas IV, Gibson LJ. Cellular materials as porous scaffolds for tissue engineering. Prog Mat Sci 2001;46: 273–282.
36. Holy CE, Fialkov JA, Davies JE, Shoichet MS. Use of a biomimetic strategy to engineer bone. J Biomed Mater Res 2003;65A:447–553.
37. Jones JR. Bioactive Glass 3D Scaffolds for Tissue Engineering, [dissertation]. London (UK): Imperial College London; 2002.
38. Komlev VS, Barimov SM. Porous hydroxyapaptite ceramics of bi-modal pore size distribution. J Mater Sci Mater Med 2002;13:295–299.
39. Chu GTM, Orton DG, Hollister SJ, Feinberg SE, Halloran JW. Mechanical and *in vivo* performance of hydroxyapatite implants with controlled architectures. Biomaterials 2002; 23:1283–1293.
40. Sepulveda P, Binner JGP, Rogero SO, Higa OZ, Bressiani JC. Production of porous hydroxyapatite by the gel-casting of foams and cytotoxic evaluation. J Biomed Mater Res 2000;50: 27–34.
41. Rosen MJ. Surfactants and Interfacial Phenomena. 2nd ed, New York: Wiley; 1989. p 277–303.
42. Livingston T, Ducheyne P, Garino J. *In vivo* evaluation of a bioactive scaffold for bone tissue engineering. J Biomed Mater Res 2002;62:1–13.
43. Yuan H, de Bruijn JD, Zhang X, van Blitterswijk CA, de Groot K. Bone Induction by porous glass ceramic made from Bioglass® (45S5). J Biomed Mater Res 2001;58(3): 270–276.
44. Sepulveda P, Jones JR, Hench LL, Bioactive sol–gel foams for tissue repair. J Biomed Mater Res 2002;59(2):340–348.
45. Jones JR, Hench LL. The effect of processing variables on the properties of bioactive glass foams. J Biomed Mater Res In press.
46. Jones JR, Hench LL. The effect of surfactant concentration and glass composition on the structure and properties of bioactive foam scaffolds. J Mat Sci In press.
47. Oonishi H, Hench LL, Wilson J, Sugihara F, Tsuji E, Kushitani S, Iwaki H. Comparative bone growth behaviour in granules of bioceramic materials of various sizes. J Biomed Mater Res 1999;44(1):31–43.
48. Wheeler DL, Hoellrich RG, McLoughlin SW, Chamerland DL, Stokes KE. In Vivo Evaluation of Sol–Gel Bioglass®–Biomechanical Findings. In: Sedel L, Rey C, editors. Bioceramics. Volume 10, 1997. p 349–350.
49. Cook R 58S sol–gel Bioglass: a study of osteoproductive, interfacial and handling properties using new microscopic techniques. [dissertation] London (UK). University of London; 2003.
50. Lenza RFS, Jones JR, Vasconcelos WL, Hench LL. *In vitro* release kinetics of proteins from bioactive foams. J Biomed Mater Res In press.
51. Lenza RFS, Jones JR, Vasconcelos WL, Hench LL. *In vitro* release kinetics of proteins from bioactive foams. J Biomed Mater Res In press.
52. Mansur HS, Vasconcelos WL, Lenza RFS, Oréfice RL, Reis EF, Lobato ZP. Sol–gel silica based networks with controlled chemical properties. J Non-Cryst 2000;273:109–115.
53. Tan A, Romanska HM, Lenza R, Jones J, Hench LL, Polak JM, Bishop AE. The effect of 58S bioactive glass sol–gel

derived foams on the growth of murine lung epithelial cells. Key Eng Mat 2003;240–242: 719–724.

References List

Clifford A, Hill R, Rafferty A, Mooney P, Wood D, Samuneva B, Matsuya S. The influence of calcium to phosphate ratio on the nucleation and crystallization of apatite glass-ceramics. J Mater Sci Mater Med 2001;12(5): 461–469.

Healy KE. Molecular engineering of materials for bioreactivity. Curr Op Sol 1999;4: 381–387.

See also BIOMATERIALS FOR DENTISTRY; BONE AND TEETH, PROPERTIES OF; HEART VALVE PROSTHESES; HIP JOINTS, ARTIFICIAL.

BIOMATERIALS: CARBON

ROBERT B MORE
RBMore Associates,
Austin, Texas

JACK C BOKROS
Medical Carbon Research
Institute
Austin, Texas

INTRODUCTION

Inorganic, elemental carbon is one of the oldest, and yet newest, biomaterials. Carbon utilization began with prehistoric human's use of charcoal and continues today with a variety of applications exploiting the physicochemical, adsorptive, structural, and biocompatible properties of different forms of carbon. To date, the most important carbon biomaterials have been the isotropic pyrolytic carbons (PyC), produced in a fluidized bed, for use as structural blood contacting components for heart valve prostheses and for small joint orthopedic prostheses. Adsorptive properties of activated carbons also find widespread use for the removal of toxins from the body either by direct ingestion, dialysis, or by plasmapheresis.

Other carbons, such as carbon fibers and glassy carbons have been proposed for use in a variety of structural implants, but because of limited strength and durability, have not been generally accepted. However, carbon fibers and glassy carbons are used as electrodes and electronic components in biomedical analytical devices. Diamond-like coatings have been proposed to provide enhanced wear resistance for large orthopedic components, but this technology is still under development. For the future, carbon holds a central focus in nanotechnology with investigations into the use of fullerenes and carbon nanotubes as means of imaging and manipulating nanoscale bioactive molecules, as selective markers, and perhaps as inhibitors to virulent organisms such as the human immunodeficiency virus (HIV).

Elemental carbon is allotropic, meaning that it can exist in two or more forms (1). There are at least two perfectly crystalline allotropic forms: graphite and diamond, and a myriad of intermediate, imperfectly crystalline, amorphous structures (2). This diversity in structure leads to considerable variability in physical and mechanical properties ranging from graphite, one of the softest materials, to diamond, the hardest material known to human. Thus, carbon rather than being a single material is actually a spectrum of materials (3). For this reason, it is necessary to qualify the use of the term *carbon* as designating a generic material with a carbon elemental composition. A specific carbon material must then be qualified with a description of it's structure.

In general, most of the pure carbons are biocompatible in that they are bioinert, do not provoke thrombosis, hemolysis, inflammatory response, nor activate the complement system (4). Furthermore pure carbons are biostable: toxic products are not generated and the materials retain their properties. However, just because a candidate material is a carbon does not mean that its particular microstructure and properties are appropriate for the desired application. For example, structural applications such as cardiovascular and orthopedic prostheses require strength, fatigue resistance, wear resistance, low friction and durability, in addition to tissue compatibility (3). Not all carbons have the appropriate properties needed for structural use.

In order to appreciate the medically important carbons, some of the various forms of elemental carbon, their synthesis, structure, and properties will be presented and briefly discussed. We will then return to the important carbon biomaterials, discuss their utilization, and conclude with speculations as future directions.

BACKGROUND

Structure of Carbons

Diversity in carbon arises from the electronic configuration: $1s^22s^22p^2;{}^3P$, which allows the formation of a number of hybridized atomic orbitals that share four valence electrons to form covalent bonds with directional properties. On the basis of bond structures that arise from the hybridized orbital bonds, carbon compounds are classed as aliphatic and as aromatic (5). Originally, aliphatic meant “fatty” and aromatic meant “fragrant”, but these descriptions no longer have any real significance. Aliphatic compounds are further subdivided into alkane, alkenes, alkynes, and cyclic aliphatic. Aromatic compounds are benzenes and compounds that resemble benzene in chemical behavior. With a few exceptions, organic compounds of medical importance tend to be aromatic or benzene-like. Details of electronic structure beyond that given here may be found in standard chemistry and organic chemistry textbooks (1,5).

Naturally Occurring Carbons

Diamond. Diamond is the ultimate polycyclic aliphatic system, but is not a hydrocarbon; rather, it is one of the allotropic forms of elemental carbon. In the diamond allotropic structure, one s and three p orbitals undergo hybridization to form the sp^3 orbital that has tetrahedral symmetry. This symmetry allows covalent bonds to connect each carbon atom with four others. Bond angles are 109.5° and the carbon–carbon bond length is 0.154 nm. Each carbon is bonded to the original plus three others and this structure propagates throughout the entire crystal forming one giant isotropic molecule of covalently bonded carbons (1,2), as shown in Fig. 1. The diamond crystallographic



Figure 1. Crystallographic structure of diamond with tetrahedral bond angles of 109.5° and bond lengths of 0.154 nm. The unit cell with a length of 0.358 nm is shown by the dashed lines. The spheres represent the location of the atoms and not size.



Figure 2. Crystallographic structure of graphite. Basal planes *a* and *b* contain the hexagonal covalently bonded carbons with bond angles of 120° and bond lengths of 0.142 nm. Because of sp^2 coordination, each basal plane is shifted one atomic position relative to one another. The successive basal planes are separated by 0.34 nm in the *c* direction. The distances 0.246 and 0.67 nm are the dimensions of the graphite hexagonal close-packed unit cell.

structure can be visualized as a repetition of the six-carbon cyclohexane "chair" configuration. Because of the large number covalent bonds with an interlocking isotropic orientation, the structure is very rigid. A large amount of energy is required to deform the crystal, hence diamond is the hardest material known.

Graphite. Where diamond is the ultimate polycyclic aliphatic system, graphite is the ultimate polycyclic aromatic system. Graphite has a layered structure consisting of planar arrays in which each carbon atom is bonded by two single bonds and one double bond with its three nearest neighbors. Where diamond can be visualized as a repeated cyclohexane chair, graphite is visualized as a repeated six-carbon benzene ring structure. Within a single plane, each carbon is bonded with a single atomic distance of 0.142 nm to its three nearest neighbors by sp^2 orbitals with hexagonal symmetry and 120 ° bond angles (1). Three of the four valence electrons are used to form these regular covalent σ (sigma) bonds, which forms the basal planes of hexagonal covalently bonded atoms as shown in Fig. 2. A single basal layer of the hexagonal carbons is known as a *graphene* structure.

The fourth π (pi) electron resonates between valence structures in overlapping *p* orbitals forming π bond donut-shaped electron clouds with one lying above and one below and perpendicular to the plane of the σ bonded carbons (2). Successive layers of the hexagonal carbons are held together at a distance of 0.34 nm by weak van der Waals forces or by interactions between the π orbitals of the adjacent layers (6,7). Thus the graphite structure is highly anisotropic, consisting of stacked parallel planes of strong covalent in-plane bonded carbons with the planes held together by much weaker van der Waals type forces. Because of weak interlayer forces, the layers are easily separated, which accounts for softness and lubricity of graphite. These weak interlayer forces also account for (a) the tendency of graphitic materials to fracture along planes, (b) the formation of interstitial compounds; and (c) the lubricating, compressive, and many other properties of graphite (2,6).

Amorphous Carbons. There are many cystallographically disordered forms of carbon with structures that are intermediate between those of graphite and diamond. The majority tends to be imperfectly layered graphene, turbostratic, and randomly oriented structures (2). X-ray diffraction patterns for amorphous carbons are broad and diffuse because of the small crystallite size, imperfections, and a turbostratic structure (2). In turbostratic structures, there is order within the graphene planes (denoted as *a* and *b*), but no order between planes (denoted as *c* direction) as shown in Fig. 3. Crystallographic defects such as lattice vacancies, kinked or warped layer planes, and possible aliphatic bonds tend to increase the turbostratic layer spacing relative to graphite and inhibit the ability of the layer planes to slip easily as occurs in graphite (2). Like graphite, there is strong in plane covalent bonding, but, because the ability of the planes to slip past one another is inhibited, the materials are much harder and stronger than graphite. Turbostratic carbons occur in a spectrum of amorphous ranging through mixed-amorphous structures and include materials such as soot, pitch, and coals.

Fullerenes. The recently discovered fullerenes (2,8,9) can occur naturally as a constituent of soot. Fullerenes are hollow cage-like structures that can be imagined as graphene sheets that have been folded or rolled into a ball or cylindrical tube. However, the structures are actually formed by the reassociation of individual carbon atoms rather than a folding or rolling of a graphene structure. The most famous fullerene is the ~1 nm diameter C_{60}



Figure 3. Turbostratic amorphous structure.

(60 carbon) buckminsterfullerene (bucky ball) with a truncated icosahedron structure that resembles a European football. Because the structure is reminiscent of the geodesic dome designed by the architect Buckminister Fuller, the proposed structure was named after him (8).

Geometrically, the bucky ball has a repeating structure that consists of a pentagon surrounded by five hexagons (see Fig. 4). In order to wrap into a nonplanar ball, the graphitic *p* orbitals must assume an angle of 101.6° relative to the plane of the C bonds rather than 90° for graphite (9). There are a number of other possible carbon number ball structures, but the smallest sizes are thought to be limited to C_{60} and C_{70} by the molecular strain induced at the edge-sharing pentagons. Although remarkably stable, C_{60} can photodisassociate when pulsed with laser light and loose carbon C_2 pairs down to $\sim C_{32}$, where it explodes into open fragments because of strain energy (10).

Metals can also be inserted into the buckyball cage simply by conducting fullerene synthesis in the presence of metals (11). Such internally substituted endohedral fullerenes are fancifully called "dopyballs" for doped fullerenes (12) and denoted as M_aC_n, where M_a is the metal and C_n the carbon complex. "Fullerite" refers to a solid-state association of individual C_{60} molecules, named by analogy to graphite, in which the bucky balls assume a face-centered cubic (fcc) crystallographic structure with lattice constant $a = 1.417$ nm (13). Treatment of fullerite with 3 equiv of alkali metal, A_3C_{60}, makes it a super conductor at room temperature (14), whereas treatment with 6 equiv of alkali metal, A_6C_{60}, makes it an insulator.

An excellent introduction to fullerenes by Bleeke and Frey, Department of Chemistry, Washington University, St. Louis, MO, is available on the Internet at http://www.chemistry.wustl.edu/~edudev/Fullerene/fullerene.html (15).

Nanotubes. Although most likely synthetic, because of the basic fullerene structure, nanotubes will be discussed here. A nanotube consists of a single graphene sheet SWNT (single-wall nanotube) or multiple concentric graphene sheets MWNT (multiwall nanotube) rolled into a cylindrical tube (16). In MWNT, the nested concentric cylinders are separated by the ~0.34–0.36 nm graphite layer separation distance.

There are several different wrapping symmetries to give chiral, zigzag or arm chair nanotubes and the tubes may be end capped by a bucky ball half-sphere. Lengths range from well > 1 μm and diameters range from 1 nm for SWNT to 50 nm for MWNT. A zigzag SWNT is shown in Fig. 5. Additional information regarding nanotubes can be found at Tomanek's laboratory, at the University of Michigan. A very informative web page dedicated to nanotubes (17) is at http://www.pa.msu.edu/cmp/csc/nanotube.html.



Figure 4. A surface view of a C_{60} structure, buckminsterfullerene (buckyball), with an ~1 nm diameter, is shown.



Figure 5. A short section of SWNT with a zigzag chiral symmetry is shown. The arrow indicates the long axis of the tube and bonds on the forward wall are more heavily drawn. Like the buckyball, this SWNT has a diameter of ~1 nm.

Synthetic Carbons

Carbon structures can be synthesized through a variety of processes. Because these processes define the resulting materials, both will be presented together. The most important synthesis processes include carbonization or pyrolysis and graphitization (2). Carbonization is a thermal process in which an organic precursor is converted into an all carbon residue with the diffusion of non-carbon volatile compounds to the atmosphere (2,6). The resulting all-carbon residue is known as a coke or a char.

Coke is a graphitizable carbon and chars are nongraphitizing (2). Cokes and chars are amorphous, lacking long-range crystallographic structure (turbostratic), with the degree of structure dependant on the precursor and the particular carbonization process. A coke may then be graphitized. In graphitization, residual non-carbon impurities are removed and the turbostratic structure is converted into a well-ordered graphite crystallographic structure by heating to high temperatures (6). A char, when graphitized retains its disordered turbostratic structure (2).

Synthetic Graphites. These carbons are prepared by grinding or milling a solid precursor material (coke) into fine particles, binding with a material such as coal tar pitch, and then molding into shape (2,6). The resulting material is then carbonized baked and graphitized. Typical milled grain sizes may range from 1 μm up to ~ 1 cm. The mixture of filler and binding may be doped or impregnated with the addition of non-carbon elements such as tungsten. The final properties of the molded graphite depend on the degree of graphitization and the grain size (6). Other important parameters are porosity, anisotropy, and density (6). One synthetic graphite used in medical devices, POCO AXF 5Q, has a grain size of 5 μm, a pore size of 0.6 μm, and a 23% volume total porosity. This particular graphite grade is often mixed with 10% by weight fine powdered tungsten before molding and baking to confer radio opacity (6).

Viterous, Glassy Carbons. Carbonization of certain polymer chars produces glassy carbons. These materials are amorphous, turbostratic, and thought to contain some sp^3 character in addition to sp^2(2). Precursors are polymers such as phenolformaldehyde, poly(furfuryl alcohol) and poly(vinyl alcohol). Shapes are attained by carbonization in molds and are limited to ~ 7 mm thickness because of volumetric shrinkage (~ 50%) and the need for gases generated during carbonization to diffuse out and not nucleate bubbles (18). The resulting material is hard, brittle, and difficult to machine.

Carbon Fibers. Thomas Edison produced the first carbon fiber in 1879 as a filament of an incandescent lamp and the first patent was issued in 1892 (2,3). Hiram Maxim received a process patent for the production of carbon fibers in 1899 (3). However, prior to the 1950s carbon fibers were of marginal strength and used primarily for their electrical properties.

Carbon fibers are highly oriented, small (with diameters on the order of 7 μm), crystalline filaments that are prepared by carbonization of polymeric filament precursors and sequential heat treatment. There are three classes of fibers based on the precursor material: PAN (polyacrylonitrile), rayon, and pitch (2). Other precursors and processes exist, but have not been as successful commercially (3). In general, fibers are classified according to structure and degree of crystallite orientation (2): high modulus (345 GPa and above), intermediate modulus (275 GPa), and low modulus (205 GPa and below). Structures are turbostratic and can contain mixed sp^2 and sp^3 bonding (2). Because of their small volume, tensile strengths can be quite high, on the order of 1000–7000 MPa.

Chemical Vapor Deposited (CVD) Carbons. Carbonization of a gaseous or liquid precursor such as gaseous hydrocarbons produces a material known as pyrolytic carbon or pyrolytic graphite (2). Thermal decomposition of hydrocarbons produces carbon free radicals in the vapor phase, which can then polymerize to form coatings on exposed surfaces. Common precursor hydrocarbons are methane, propane, and acetylene. The resulting turbostratic pyrolytic carbons can be isotropic or anisotropic depending on the pyrolysis reaction conditions (19). The coating process can be prolonged so as to produce structural components for heart valve and orthopedic prostheses with coating thickness on the order of 1 mm.

The pyrolytic carbons for medical applications are formed by CVD processes in fluidized-bed reactors (20). Propane is the precursor gas and an inert gas such as nitrogen or helium provides the levitation needed to fluidize a bed of small refractory particles. Graphite preformed substrates (e.g., POCO AXF 5Q) suspended in the fluidized bed are coated with the pyrolytic carbon (20). The resulting coating structures are turbostratic and isotropic with very small randomly oriented crystallites: These crystallites will henceforth be designated as *isotropic fluidized-bed pyrolytic carbons*. Nonfluidized-bed CVD reactors tend to produce a highly anisotropic coating with column-like, (columnar) crystallites or laminar structures with the basal planes oriented parallel to the deposition surface (2,19).

Highly Oriented Pyrolytic Graphite (HOPG). Columnar and laminar pyrolytic carbons when annealed $> 2700\,^\circ$C are reordered, the turbostratic imperfections disappear and the resulting structure closely approaches the ideal graphite structure with an angular spread of the crystallite c axes of $< 1^\circ$ (2).

Vapor-Phase Carbons. Carbon CVD coatings formed from solid precursors carbonized by vaporization are considered vapor-deposited coatings (VPC). Precursors can be graphite or vitreous carbon vaporized by heating to high temperature at low pressure to generate the carbon free radicals. This technique produces line-of-sight coatings of nanometer and micrometer level thickness. The VPC coatings tend to be turbostratic and amorphous (3).

Diamond-Like Carbon. Diamond-like carbon coatings containing mixed sp^3 and sp^2 bonds can be prepared by physical vapor deposition (PVD). These PVD methods produce carbon free radicals by ion beam sputtering, or laser or glow discharge of solid carbon targets. There are also mixed PVD/CVD methods such as plasma or ion beam deposition from hydrocarbon gas precursors (2).

Activation. Activated carbons have large surface areas and large pore volumes that lend to a unique adsorption capability (21). Activation is a thermal or chemical treatment that increases adsorption capability. The mechanisms for adsorption are complex and include physical and chemical interactions between the carbon surface and the sorbed substances. Activity includes (a) adsorption, (b) mechanical filtration, (c) ion exchange, and (d) surface oxidation (22). Of these, adsorption and surface oxidation are the most important for medical applications. Incompletely bonded basal plane carbons as occur at crystal edges exposed at the surface, as well as defects, are chemically active and can chemisorb substances, particularly oxidizing gases such as carbon monoxide and carbon dioxide (23). Surface oxidation involves the chemisorbance of atmospheric oxygen and further reaction of the sorbed oxygen with other substances (24). Physical adsorbance occurs because of charge interactions, and chemical adsorbance occurs because of reactions between the adsorbant and adsorbate (24).

Any high carbon material can be “activated” by various oxidizing thermal and chemical processes that increase porosity and active surface area, which increases the ability for chemisorption (25). A char is formed and then treated chemically or physically to generate pores and the surface oxidized (21). Surface oxide complexes such as phenols, lactones, carbonyls, carboxylic acids, and quinones form that have a strong affinity for adsorbing many substances such as toxins or impurities (26). Carbon fibers may be activated in order to enhance the ability to bind with a matrix material when used as a filler.

PROPERTIES

Representative physical and mechanical properties of the carbon allotropes are summarized in Table 1 (2,3,27). Materials included span the spectrum from natural diamond to natural graphite. There is considerable variability

Table 1. Representative Mechanical and Physical Properties for Carbon Allotrophs

Property	Natural Diamond	Amorphous Carbons	HOPG	Natural Graphite
Density, $g \cdot cm^{-3}$	3.5–3.53	1.45–2.1	2.25–2.65	2.25
Young’s modulus, GPa	700–1200	17–31	20	4.8
Hardness, mohs	10	2–5		1–2
Hardness, DPH 500 g		150–(>230)		
Flexural strength, MPa		175–520	80 (*c*) 120 (*ab*)	
Compressive yield strength, MPa	8680–16530	700–900	100	
Fracture toughness, $MPa \cdot m^{1/2}$	3.4	0.5–1.67		
Poisson’s ratio	0.1–0.29	0.2–0.28		
Wear resistance	Excellent	Poor to excellent	Poor	Poor
Electrical resistivity, Ω·cm	2700		0.15–0.25 (*c*) 3.5×10^{-5}–4.5×10^{-5}(*ab*)	0.006
Magnetic susceptibility, $\times 10^6$ emu/mol	−5.9			−6
Melting point, °C	3550		3650	3652–3697 (sublimes)
Boiling point, °C	4827			4220
CTE linear, (20°C)$\mu m \cdot (m \cdot {}^\circ C)^{-1}$	1.18	2.6–6.5	−0.1 (*ab*) 20 (*c*)	0.6 (*ab*) 4.3 (*c*)
Heat capacity, J/g·°C	0.4715			0.69
Thermal conductivity, $W \cdot (m \cdot K)^{-1}$	2000	4.6–6.3	16–20 (*ab*) 0.8 (*c*)	19.6 (*ab*) 0.0573 (*c*)

[a] Values from Matweb.com and from Refs. (2,3).

in properties depending on the structure, anisotropy, and crystallinity, particularly in the amorphous carbons. Physical properties such as resistivity, coefficient of thermal expansion, thermal conductivity, and tensile strength (28) show profound sensitivity to direction in the graphitic materials. This anisotropy is most easily seen in HOPG by comparing the *ab* direction, parallel to the σ-bonded basal plane, to the perpendicular *c* direction. For example, the resistivity drops for HOPG because of the mobility of the π-electron clouds in the *ab* direction relative to the *c* direction (2). Diamond, with full covalent bonding, is an insulator.

Thermal conductivity, which occurs by lattice vibration, is related to a mean-free-path length for wave scattering. Little scattering occurs in the near-perfect graphite crystal basal plane, so the scattering path length and thermal conductivity are high in the *ab* direction. In the *c* direction, thermal conductivity is much lower because the amplitude of lattice vibration is considerably lower than for the *ab* direction (2). Thermal expansion is related to the interatomic spacing of the carbon atoms, bond strength, and vibration. As temperature increases, the atoms vibrate and the mean interatomic spacing increases. For weak bonding in the *c* direction, the interatomic vibrational amplitude and dimensional changes are larger than for the strongly bonded *ab* direction (2). The CTE values are stated for room temperature to ~200 °C; the negative values shown in Table 1 are possibly due to internal stresses and become positive at higher temperatures. Large anisotropic differences in CTE can result in large internal stresses and possible structural problems with heating and cooling over large temperature differences.

BIOCOMPATIBILITY

Pyrolytic carbons used in heart valve and orthopedic prostheses have a successful clinical experience as long-term implant materials for blood and skeletal tissue contact (3,29–31). These isotropic, fluidized-bed, pyrolytic carbons that were originated at General Atomics in the 1960s demonstrate negligible reactions in the standard Tripartite and ISO 10993-1 type biocompatibility tests. Results from such tests are given below in Table 2 (20). This material is so nonreactive that it has been proposed as a negative control for these tests. However, the surface is not totally inert and is capable of adsorption and desorption of a variety of substances including protein (32–39). The mechanism for biocompatibility is yet poorly understood, but probably consists of a complex, interdependent, and time-dependent series of interactions between the proteins and the carbon surface (32).

Because of the similarity in surface sp^2 and sp^3 character among the various pure carbons, most can be expected to have the tissue compatibility and biostability to perform well in these biocompatibility tests also. Vitreous carbons (40), activated carbons, and diamond-like coatings (41) are known to exhibit tissue compatibility, likewise the fullerenes will probably be found tissue compatible. As an extreme example, in testing the safety of an activated charcoal for hemoperfusion, Hill (42) introduced finely ground charcoal suspensions into the blood stream of rats in varying concentrations up to 20 mg/kg charcoal and observed no differences in survival or growth relative to controls over a 2-year observation period.

A reasonable working definition for biocompatibility has been given by Williams (43) as, "*The ability of a material to perform with an appropriate response in a specific application*". The important point here is that while many carbons provoke a minimal biological reaction, "*the specific application*" demands a complete set of mechanical and physical properties, in addition to basic cell compatibility. Because there are a number of possible microstructures, each with different properties, a given carbon will probably not have the entire set of properties needed for a specific application. Historically, the clinically successful isotropic, fluidized-bed, pyrolytic carbons required extensive development and tailoring to achieve the set of mechanical and physical properties needed for long-term cardiovascular and orthopedic applications (20,30–32).

Blood compatible glassy carbons, for example, are often proposed for use in heart valves. However, glassy carbons were evaluated in the early 1970s as a replacement for the polymer Delrin in Bjork–Shiley valve occluders and actually found to have inferior wear resistance and durability relative to the polymer (44). Thus, the fact that a material is carbon, a turbostratic carbon, or a pyrolytic carbon and is cell compatible, does not justify its use in a long-term implant devices (3,32,33). The entire range of physical and mechanical properties as dictated by the intended application are required.

MEDICAL APPLICATIONS

Activated Charcoal–Activated Carbons

Charcoal, the residue from burnt organic matter, was probably one of the first materials used for medical and

Table 2. Biological Testing of Pure PyC

Test description	Protocol	Results
Klingman maximization	ISO/CD 10993-10	Grade 1; not significant
Rabit pyrogen	ISO/ DIS 10993-11	Nonpyrogenic
Intracutaneous injection	ISO 10993-10	Negligible irritant
Systemic injection	ANSI/AAMI/ISO 10993-11	Negative—same as controls
Salmonella typhimurium Reverse mutation assay	ISO 10993-3	Nonmutagenic
Physiochemical	USP XXIII, 1995	Exceeds standards
Hemolysis–rabbit blood	ISO 10993-4/NIH 77-1294	Nonhemolytic
Elution test, L929 mammalian cell culture	ISO 10993-5, USP XXIII, 1995	Noncytotoxic

biocompatible applications. Prehistoric humans knew that pulverized charcoal could be placed under the skin indefinitely without ill effects, thus allowing decorative tattoos (45). Because granulated charcoal has an active surface area, it can adsorb toxins when ingested. Likewise, charcoal has long been used to clear water and other foods. The ancient Egyptians first recorded the medical use of charcoal ~1500 BC (21). During the 1800s, the first formal scientific studies of charcoal as an antidote to treat human poisoning appeared in Europe and The United States. In some of these studies, the researchers demonstrated charcoals effectiveness by personally ingesting charcoal along with an otherwise fatal dose of strychnine or arsenic (21). Activation was discovered ~1900 and activated charcoals were used as the sorbant in World War I gas masks (21).

Today's activated carbons or activated charcoals are derived from a number of precursor organic materials ranging from coal, wood, coconut shells, and bone. Chars are prepared by pyrolyzing the starting organic material using heat in the absence of oxygen. The char is then activated by treatment with chemicals or steam. Activated carbon has remarkable adsorptive properties that vary with the starting material and activation process. Common active surface areas are on the order of 1000–2000 m^2/g. Prior to the discovery of activation processes, charcoals were naturally oxidized by exposure to the atmosphere and moisture, as in charcoal, or oxidized in a more controlled activating process (46).

Orally administered activated carbon applications include use as an antidote to poisoning and to drug overdoses, where it acts at the primary site of drug adsorption in the small intestine. There are no contraindications for patients with intact GI tracts. There are numerous advantages and few disadvantages. One of the main disadvantages is that it is unpleasant for the health care professional to use because it can be messy, staining walls, floors, clothing, and so on. It may also be unpleasant to swallow because of a gritty texture (46).

There are extracorporal, parenteral, methods such as hemoperfusion, hemofilteration, and plasmapheresis where activated carbon is used to remove toxins from a patient's blood. The patient's heparinized blood is passed via an arterial outflow catheter into an extracorporal filter cartridge containing the activated carbon and then returned to the patient via a venous catheter. These techniques are effective when there is laboratory confirmation of lethal toxin concentrations in the blood and for poorly dialyzable and nondialyzable substances (47).

Pyrolytic Carbons

Isotropic, fluidized-bed PyCs, appropriate for cardiovascular applications originated at General Atomics in the late 1960s as a cooperative effort between an engineer, Jack Bokros, working with pyrolytic carbons as coatings for nuclear fuel particles and a surgeon, Vincent Gott, who was searching for thromboresistant materials for cardiovascular applications (48). Together, they tailored a specific fluidized-bed, isotropic pyrolytic carbon alloy with the biocompatibility, strength and durability needed for long-term structural applications in the cardiovascular system. The original material was a patented silicon-alloyed pyrolytic carbon given the tradename "Pyrolite" (20).

In the early 1960s, heart valve prostheses constructed from polymers and metal were prone to early failure from wear, thrombosis, and reactions with the biological environment. Prosthesis lifetimes were limited to several years because of wear in one or more of the valve components. Incorporation of PyC as a replacement for the polymeric valve components successfully eliminated wear as an early failure mechanism. Subsequently, in most valve designs, metallic materials were replaced with PyC also (20,29–33,49).

During the 1970s and 1980s Pyrolite was only available from a single source until the original patents expired. Since that time, several other sources have appeared with copies of the original silicon-alloyed General Atomics material. In the early 1990s, the Bokros group revisited the synthesis methods and found that with the then available technology for process control, that a pure carbon pyrolytic carbon could be made with better mechanical properties and potentially better biocompatibility than the original silicon-alloyed Pyrolite (20). This new pure isotropic, fluidized-bed, pyrolytic carbon material was patented and named On-X carbon. On-X carbon is currently utilized in mechanical heart valves and in small joint orthopedic applications.

These PyC materials are turbostratic in structure and isotropic with fine randomly oriented crystallite sizes on the order 2.5–4.0 nm and c layer spacing of ~0.348 nm (50–52). Implants are prepared by depositing the hydrocarbon gas precursor coating in a fluidized bed on to a preformed graphite substrate to a thickness of ~0.5 mm (29–32,53). The coatings then may be ground and polished if desired and subjected to a proprietary process that minimizes the degree of surface chemisorbed oxygen.

Some of the mechanical and physical properties of the pure and silicon-alloyed PyC materials appropriate for use in long-term implants are given Table 3 (3,20). A typical glassy carbon and a fine-grained synthetic graphite are also included for comparison. The PyC flexural strength, fatigue, and wear resistance provide adequate structural integrity for a variety of implant applications. The density is low enough to allow components to be actuated by flowing blood. Relative to orthopedic applications, Young's modulus is in the range reported for bone (54,55), which allows for compliance matching and minimizes stress shielding at the prosthesis bone interface. The PyC strain-to-failure is low relative to ductile metals and polymers; but it is high relative to ceramics. Because PyC is a nearly ideal linear elastic material, component design requires the consideration of brittle material design principals. Certain properties such as strength vary with the effective stressed volume, or stressed area as predicted by Weibull theory (56). Table 3 strength levels were measured for specimens tested in four-point bending, third-point loading (57) with an effective stressed volume of 1.93 mm^3. The Weibull modulus for PyC is ~10 (57).

Fluidized-bed isotropic PyCs are remarkably fatigue resistant. There is strong evidence for the existence of a fatigue threshold that is very nearly the single cycle

Table 3. Biomedical Fluidized-Bed Pyrolytic Carbon Properties

Property	Pure PyC	Typical Si-Alloyed PyC	Typical Glassy Carbon	POCO Graphite AXF-5Q
Flexural strength, MPa	493.7 ± 12	407.7 ± 14.1	175	90
Young's modulus, GPa	29.4 ± 0.4	30.5 ± 0.65	21	11
Strain-to-failure, %	1.58 ± 0.03	1.28 ± 0.03		0.95
Fracture toughness, $\text{MPa} \cdot \sqrt{\text{m}}$	1.68 ± 0.05	1.17 ± 0.17	0.5–0.7	1.5
Hardness, DPH, 500 g load	235.9 ± 3.3	287 ± 10	150	120
Density, $\text{g} \cdot \text{cm}^{-3}$	1.93 ± 0.01	2.12 ± 0.01	< 1.54	1.78
CTE, $\mu\text{m} \cdot \text{cm}^{-1}$ EC	6.5	6.1		7.9
Silicon content, %	0	6.58 ± 0.32	0	0
Wear resistance	Excellent	Excellent	Poor	Poor

fracture strength (58–60). Paris-law fatigue crack propagation rate exponents are high; on the order of 80 and *da*/*dN* fatigue crack propagation testing displays clear evidence of a fatigue crack propagation threshold (58–63).

Crystallographic mechanisms for fatigue crack initiation and damage accumulation are not significant in the PyC at ambient temperatures (59,61). There have been no clear instances of fatigue failure in a clinical implant during the accumulated 30-year experience (64). Less than 60 out of > 4 million implanted PyC components have fractured (65), and these were caused by damage from handling or cavitation (66–68).

The PyC wear resistance is excellent. Wear testing performed in the 1970s identified titanium alloy, cobalt chromium alloy, and PyC as low wear contact materials for use in contact with PyC (69,70). This study determined that wear in PyC occurred due to an abrasive mechanism and interpreted wear resistance as approximately proportional to the ratio $H^2/2E$, where H is the Brinell hardness number and E is Young's modulus. This criteria is related to the amount of elastic energy that can be stored in the wearing surface (70). The greater the amount of stored energy, the greater the wear resistance. Successful low wearing contact couples used for mechanical heart valves include PyC against itself, cobalt chromium alloy, and ELI titanium alloy.

Observed wear in retrieved PyC mechanical heart valve prosthesis implant components utilizing PyC coupled with cobalt chromium alloy is extremely low with PyC wear mark depths of < 2 μm at durations of 17 years (71–73). Wear in the cobalt chromium components was higher, 19 μm at 12 years (71–73). But, wear in the cobalt chromium components was concentrated at fixed contact points instead of being distributed over a large area as for the PyC rotating disk. Wear depths in all PyC prostheses, with fixed contact points are also low, < 3.5 μm at 13 years (74,75). In contrast, the wear depths in valves utilizing polymeric components such as the polyacetyl Delrin in contact with cobalt chromium and titanium alloys are much higher at 267 μm at 17 years (76). Incorporation of PyC in heart valve prostheses has eliminated wear as a failure mode (29,77).

The PyC is often used in contact with metals and behaves as a noble metal in the galvanic series. Testing using mixed potential corrosion theory and potentiostatic polarization has determined that no detrimental effects occur for PyC coupled with titanium or cobalt–chrome alloys (78,79). Use of PyC with stainless steel alloys is not recommended.

To date, PyC has been used in ~25 mechanical heart valve prosthesis designs. One such design, the On-X valve, by Medical Carbon Research Institute, http://www.mcritx.com, is shown in Fig. 6.

Pyrolytic carbon has a good potential for orthopedic applications because of advantages over metallic alloys and polymers (3,30,31):

1. A modulus of elasticity similar to bone to minimize stress shielding.
2. Excellent wear characteristics.
3. Excellent fatigue endurance.
4. Low coefficient of friction.
5. Excellent biocompatibility with bone and hard tissue.
6. Excellent biocompatibility with cartilage.
7. Fixation by direct bone apposition.

A brief comparison of PyC properties to those of conventional/orthopedic implant materials is given in Table 4. Pyrolytic carbon coatings for orthopedic implants can reduce wear, wear particle generation, osteolysis aseptic loosening, and thus extend implant useful lifetimes. Furthermore, good PyC compatibility with bone and the native joint capsule enables conservative hemiarthroplasty replacements as an alternative to total joint replacement.

Cook et al. (80) studied hemijoint implants with a PyC femoral head in the canine hip and observed a greater potential for acetabular cartilage survival in PyC than for cobalt–chromium–molybdenum alloy and titanium alloy femoral heads. There were significantly lower levels of gross acetabular wear, fibrillation, eburnation, glycosaminoglycan loss, and subchondral bone change for PyC than the metallic alloys.

Tian et al. (81) surveyed *in vitro* and clinical *in vivo* PyC orthopedic implant studies conducted during the 1970s through the early 1990s and concluded that PyC demonstrated good biocompatibility and good function in clinical applications.

A 10-year follow-up of PyC metacarpophalangeal (MCP) finger joint replacements implanted in patients at the Mayo Clinic, Rochester Minnesota (82) between 1979 and 1987, demonstrated excellent performance. Ascension Orthopedics was able to use these results in part to justify a FDA premarket approval application (PMA) for the semi-constrained, uncemented MCP finger joint replacement, PMA P000057, Nov. 2001.



Figure 6. On-X prosthetic heart valves manufactured by Medical Carbon Research Institute from the elementally pure, fluidized-bed isotropic pyrolytic carbon, On-X carbon. The valves consist of a central flow circular orifice with two semicircular occluder disks. A polymeric sewing cuff is used to attach the valve to the annulus tissue. Aortic and mitral valves with two different sewing cuff designs each are shown.

Currently, Ascension Orthopedics, http://www.ascensionortho.com, manufactures PyC prostheses for finger joints: metacarpophalengeal (MCP) and proximal interphalangeal (PIP) in addition to carpometacarpal (CMC) thumb and an elbow radial head (RH) prostheses (see Fig. 7). Because of the excellent PyC compatibility with bone and cartilage, the CMC and radial head are used in hemiarthroplasty directly contacting the native joint capsule and bone. Fixation is by direct bone opposition for all of the prostheses. To date, ~6500 Ascension Orthopedics prostheses have been implanted. Another company, Bioprofile, http://www.bio-profile.com, manufactures hemiarthroplasty PyC prostheses for the wrist: scapoid, scapho-trapezo-trapezoid, trapezium bone, capitate head, and an elbow radial head.

Glassy carbons have been proposed as an attractive low cost alternative for a variety of orthopedic and cardiovascular devices (3). However, because of relatively low strength and poor wear resistance it has not been generally accepted as a suitable material for long-term critical implants. An example of poor glassy carbon durability when used for heart valve components was cited earlier in the text (44).

Carbon fibers are popular as high strength fillers for polymers and other material composites and have been proposed for use in tendon and ligament replacements in addition to orthopedic and dental implants (83–86). Spinal interbody fusion cages using PEEK and carbon fibers (86) are an example of an orthopedic application. However, the ultimate properties of the implant depend largely upon the

Table 4. Material Properties of Orthopedic Materials

Property	Unit	PyC	Al_2O_3	TZP	CoCrMo	UHMWPE
Density	$g \cdot cm^{-3}$	1.93	3.98	6.05	8.52	0.95
Bend strength	MPa	494	595	1000	690, uts	20
Young's modulus, E	GPa	29.4	400	150	226	1.17
Hardness, H	HV	236[a]	2400	1200	496	NA
Fracture toughness, K_{1c}	$MN \cdot m^{-3/2}$	1.68	5	7		
Elongation at failure	%	2	0.15		1	>300
Poisson's ratio		0.28	0.2	0.2	0.3	
$H^2/2E$[b]		7.6	12.2		1.8	

[a] The hardness value for PyC is a hybrid definition that represents the indentation length at a 500 g load with a diamond penetrant indentor. Because PyC elastically completely recovers the microhardness indentation a replica material such as a cellulose acetate coating, or a thin copper tape is used to "record" the fully recovered indentation length. Although unusual, this operational definition for hardness is a common practice used throughout the PyC heart valve industry.

[b] Approximate values, there are no exact conversions.



Figure 7. Ascension Orthopedics small joint PyC prostheses for finger joints.

matrix in which the carbon fibers are included and the geometry and orientation of the fiber inclusions (3).

Diamond-like carbon (DLC) coatings may find use as low friction, wear resistant surfaces for joint articulating surfaces in orthopedic implants (87,88). However, the coating thickness is limited to the micrometer level; the technology is still in development and ultimately may not be competitive with the newer ceramic joint replacement materials.

Buckyballs (fullerenes) and carbon nanotubes are cage-like structures that suggest use as a means to encapsulate and selectively deliver molecules to tissues. Because of their nanometer dimensions, fullerenes can potentially travel throughout the body. Some current biomedical applications under study involve functionalizing fullerenes with a number of substances including DNA and peptides that can specifically target, mark, or interfere with active sites on enzymes and perhaps inhibit virulent organisms such as the human immunodeficiency virus (89–93). They may also be used to selectively block ion channels on membranes (94). Fullerenes are synthesized by CVD and PVD techniques and can have a variety of novel properties depending on preparation. Currently, there are production difficulties with separation and isolation of fullerenes from the rest of soot-like materials that can occur during synthesis. However, bulk separation methods have been developed and some commercial sources have appeared. See http://www. chemistry.wustl.edu/~edudev/Fullerene/fullerene.html#index and http://www.pa.msu.edu/cmp/csc/nanotube. html. There is a wealth of information available on the Internet that is readily accessed. Medical applications of fullerenes are currently a topic of intense interest and activity and hold much promise for future developments.

CONCLUSION

Uses of carbon as a biomaterial range from burnt toast, as mother's first aid remedy for suspected poisoning, to the newly discovered fullerene nanomaterials as a possible means to treat disease on a molecular level. The most successful and widespread medical applications have been the use of activated carbons for detoxification and the use of the General Atomics family of isotropic, fluidized-bed, pyrolytic carbons for structural components of long-term critical implants. However, the successful biomedical application of carbon requires an understanding that carbon is a spectrum of materials with wide variations in structure and properties. While a given carbon may be biocompatible, it may not have the mechanical and physical properties needed for the intended application.

As for the future, additional applications of the biomedical PyC materials to orthopedic applications in larger joints and in the spine can be expected, especially if successful long-term hemiarthroplasty devices can be demonstrated. New cardiovascular devices can be expected, such as components for venous shunts and venous valves. The most exciting new developments will probably occur in nanotechnology with the creation of functional, fullerene type, materials, devices, and systems through control of matter at the scale of 1–100 nm, and the exploitation of novel properties and phenomena at the same scale.

BIBLIOGRAPHY

Cited References

1. Pauling L. College Chemistry. San Francisco: W.H. Freeman; 1964.
2. Pierson HO. Handbook of Carbon, Graphite, Diamond and Fullerenes. Park Ridge, New Jersey: Noyes Publications; 1993.
3. Haubold AD, More RB, Bokros JC. Carbons. In: Black J, Hastings G, editors. Handbook of Biomaterial Properties. London: Chapman & Hall; 1998. p 464–477.
4. Janvier G, Baquey C, Roth C, Benillan N, Belisle S, Hardy J. Extracorporeal circulation, hemocompatibility, and biomaterials. Ann Thorac Surg 1996;62:1926–1934.
5. Morrison RT, Boyd RN. Organic Chemistry. Boston: Allyn and Bacon; 1974.
6. Properties and Characteristics of Graphite for the Semiconductor Industry. In: Sheppard RG, Mathes DM, Bray DJ, editors. Decatur, TX: POCO Graphite, Inc.; November 2001. Can be downloaded from http://www.poco.com.
7. Spain IL. Electronic Transport Properties of Graphite, Carbons, and Related Materials. Chem Phys Carbon 1981; 16:119
8. Kroto HW, Heath JR, O'Brien SC, Curl RF, Smalley RE. C_{60}: Buckminsterfullerene. Nature (London) 1985;318(6042): 162–163.
9. Haddon RC, Brus LE, Raghavachari K. Electronic Structure and Bonding in Icosahedral C_{60}. Chem Phys Lett 1986; 125:459.
10. O'Brien SC, Heath JR, Curl RF, Smalley RE. Photophysics of Buckminsterfullerene and Other Carbon Cluster Ions. J Chem Phys 1988;88:220.
11. Heath JR, O'Brien SC, Zhang Q, Liu Y, Curl RF, Kroto HW, Tittel FK, Smalley RE. Lanthanum Complexes of Spheroidal Carbon Shells. J Am Chem Soc 1985;107:7779–7780.
12. Chai Y, Guo T, Jin C, Haufler RE, Chibante LPF, Fure J, Wang L, Alford JM, Smalley RE. Fullerenes with Metals Inside. J Phys Chem 1991;95:7564
13. Heiney PA, Fischer JE, McGhie AR, Romanow WJ, Denenstein AM, McCauley JP, Jr., Smith AB, III, Cox DE. Orientational Ordering Transition in Solid C_{60}. Phys Rev Lett 1991;66:2911.
14. Haddon RC, Hebard AF, Rosseinsky MJ, Murphy DW, Duclos SJ, Lyons KB, Miller B, Rosamilia JM, Fleming RM, Kortan AR, Glarum SH, Makhija AV, Muller AJ, Eick RH, Zahurak SM, Tycko R, Dabbagh G, Thiel FA. Conducting Films of C_{60} and C_{70} by Alkali-Metal Doping. Nature (London) 1991; 350:320.
15. Bleeke JR, Frey RF. Fullerene Science Module. St. Louis, MO: Department of Chemistry, Washington University; Available at http://www.chemistry.wustl.edu~/edudev/Fullerene/fullerene.html.
16. Iijima S. Helical microtubules of graphitic carbon. Nature (London) 1991;354:56.
17. Tomanek D, of the University of Michigan, nanotube web page http://www.pa.msu.edu/cmp/csc/nanotube.html.
18. Jenkins GM, Kawamura K. Polymeric Carbons–Carbon Fibers, Glass and Char. Cambridge: Cambridge University Press; 1976.
19. Bokros JC. Deposition, Structure and Properties of Pyrolytic Carbon. In: Walker PL, editor. Chemistry and Physics of Carbon. Volume 5, New York: Marcel Dekker, Inc.; 1969. p 1–118.
20. Ely JL, Emken MR, Accuntius JA, Wilde DS, Haubold AD, More RB, Bokros JC. Pure Pyrolytic Carbon: Preparation and Properties of a New Material, On-X Carbon for Mechanical Heart Valve Prostheses. J Heart Valve Dis 1998;7:626–632.
21. Cooney DO. Activated Charcoal: Antidotal and Other Medical Uses. New York: Marcel Dekker; 1980.
22. Baker FS, Miller CE, Repik AJ, Tolles ED. Activated Carbon, in Kirk–Othmer. Encyc Chem Technol 1992;4:1015–1037.
23. Puri Balwant Rai. Chemsiorbed oxygen evolved as carbon dioxide and its influence on surface reactivity of carbons. Carbon 1966;4:391–400.
24. Cheremishoff NP, Moressi AC. Carbon adsorption applications. In: Cheremisinoff NP, Ellerbusch F, editors. Carbon Adsorption Handbook. Ann Arbor: Ann Arbor Science; 1978.
25. Pradhan BK, Sandle NK. Effect of different oxidizing agent treatments on the surface properties of activated carbons. Carbon 1999;37:1323–1332.
26. McQreey RL. Carbon electrodes: structural effects on electron transport kinetics. In: Bard AJ, editor. Electroanalytical Chemistry. New York: Dekker; 1991.
27. See Matweb.com for a variety of properties for engineering materials.
28. Diefendorf RJ, Stover ER. Pyrolytic Graphites…How structure affects properties. Metals Prog 1962;8 (May): 103–108.
29. Schoen FJ. Carbons in Heart Valve Prostheses: Foundations and clinical Performance. In: Zycher M, editor. Biocompatible Polymers, Metals and Composites. Lancaster PA: Technomic; 1983. p 240–261.
30. Bokros J. Carbon biomedical devices. Carbon 1977;15:355–371.
31. Haubold AD, Shim HS, Bokros JC. Carbon in Medical Devices. In: Williams DF, editor. Biocompatibility of Clinical Implant Materials. Volume 2, Boca Raton, FL: CRC Press; 1981. p 3–42.

32. More RB, Haubold AD, Bokros JC. Pyrolytic Carbon for Long-Term Medical Implants. In: Ratner B, Hoffman A, Schoen F, Lemons J, editors. Biomaterials Science: An Introduction to Materials in Medicine. 2nd ed. Academic Press; 2004.
33. More RB, Sines G, Ma L, Bokros JC. Pyrolytic Carbon. Encyclopedia of Biomaterials and Biomedical Engineering. Marcel Dekker; 2004.
34. Baier RE, Gott VL, Feruse A. Surface Chemical Evaluation of Thromboresistant Materials Before and After Venous Implantation. Trans Am Soc Artif Intern Organs 1970; 16:50–57.
35. Lee RG, Kim SW. Adsorption of Proteins onto Hydrophobic Polymer Surfaces: Adsorption Isotherms and Kinetics. J Biomed Mater Res 1974;8:251.
36. Nyilas E, Chiu TH. Artificial Surface/Sorbed Protein Structure/Hemocompatibility Correlations. Artif Organs 1978;2 (Suppl): 56–62.
37. Salzman EW, Lindon J, Baier D, Merril EW. Surface-Induced Platelet Adhesion, Aggregation and Release. Ann NY Acad Sci 1977;283:114.
38. Feng L, Andrade JD. Protein Adsorption on Low-Temperature Isotropic Carbon: I Protein Conformational Change Probed by Differential Sacnning Calorimetry. J Biomed Mater Res 1994;28:735–743.
39. Chinn JA, Phillips RE, Lew KR, Horbett Fibrinogen and Albumin Adsorption to Pyrolite Carbon. Trans Soc Biomater 1994;17:250.
40. Guglielmotti MB, Renou S, Cabrini RL. A histomorphometric study of tissue interface by laminar implant test in rats. Int J Oral Maxillofac Implants 1999;14:565–570.
41. Santavirta S, Takagi M, Gomez-Barrena E, Nevalainen J, Lassus J, Salo J, Konttinen YT. Studies of host response to orthopedic implants and biomaterials. J Long Term Eff Med Implants 1999;9:67–76.
42. Hill JB, Horres CR. The BD Hemodetoxifier: Particulate release and its significance. In: Chang TMS, editor. Artificial Kidney, Artificial Liver and Artificial Cells. New York: Plenum Press; 1978. p 199–207.
43. Williams DF. The Williams' Dictionary of Biomaterials. United Kingdom: Liverpool University Press; 1999.
44. Fettel BE, Johnston DR, Morris PE. Accelerated life testing of prosthetic heart valves. Med Inst 1980;14(3): 161–164.
45. Bensen J. Pre-Survey on the Biomedical Applications of Carbon. 1969. North American Rockwell Corporation Report R-7855.
46. Ford X. Clinical Toxicology. 1st ed., W. B. Saunders Company; 2001.
47. Roberts X. Clinical Procedures in Emergency Medicine. 3rd ed., W. B. Saunders Company; 1998.
48. LaGrange LD, Gott VL, Bokros JC, Ramos MD. Compatibility of Carbon and Blood. In: Hegyeli RJ, editor. Artificial Heart Program Conference Proceedings. Washington, DC: US Government Printing Office; 1969. Chapt. 5. p 47–58.
49. Sadeghi H. Dysfonctions des prostheses valvulaires cardaques et leur traitment chirgical. Schwiez Med Wschr 1987; 117:1665–1670.
50. Kaae JL. The mechanism of deposition of pyrolytic carbon. Carbon 1985;23(6): 665–667.
51. Kaae JL, Wall DR. Microstructural Characterization of Pyrolytic Carbon for Heart Valves. Cells Mater 1996;6(4): 281–290.
52. Ma L, Sines G. High resolution structural studies of a pyrolytic carbon used in medical applications. Carbon 2002;40:451–454.
53. Akins RJ, Bokros JC. The Deposition of Pure and Alloyed Isotropic Carbons and Steady State Fluidized Beds. Carbon 1974;12:439–452.
54. Reilly DT, Burstein AH, Frankel VH. The Elastic Modulus for Bone. J Biomech 1974;7:271.
55. Reilly DT, Burstein AH. The Mechanical Properties of Bone. J Bone Jt Surg Am 1974;56:1001.
56. De Salvo G. Theory and Structural Design Applications of Weibull Statistics. 1970. WANL-TME-2688, Westinghouse Electric Corporation.
57. More RB, Kepner JL, Strzepa P. Hertzian Fracture in Pyrolite Carbon. In: Ducheyne P, Christiansen D, editors. Bioceramics. Volume 6, Oxford: Butterworth-Heinemann Ltd; 1993. p 225–228.
58. Gilpin CB, Haubold AD, Ely JL. Fatigue Crack Growth and Fracture of Pyrolytic Carbon Composites. In: Ducheyne P, Christiansen D, editors. Bioceramics. Volume 6, Oxford: Butterworth-Heinemann Ltd; 1993. p 217–223.
59. Ma L, Sines G. Fatigue of Isotropic Pyrolytic Carbon Used in Mechanical Heart Valves. J Heart Valve Dis 1996;5(Suppl.I): S59–S64.
60. Ma L, Sines G. Unalloyed Pyrolytic Carbon for Implanted Heart Valves. J Heart Valve Dis 1999;8(5): 578–585.
61. Ma L, Sines G. Fatigue Behavior of Pyrolytic Carbon. J Biomed Mat Res 2000;51:61–68.
62. Ritchie RO, Dauskardt RH, Yu W, Brendzel AM. Cyclic Fatigue-crack Propagation, Stress Corrosion and Fracture Toughness Behavior in Pyrolite Carbon Coated Graphite for Prosthetic Heart Valve Applications. J Biomed Mat Res 1990;24:189–206.
63. Beavan LA, James DW, Kepner JL. Evaluation of Fatigue in Pyrolite Carbon. In: Ducheyne P, Christiansen D, editors. Bioceramics. Volume 6, Oxford: Butterworth-Heinemann Ltd; 1993. p 205–210.
64. Bokros JC, Haubold AD, Akins RJ, Campbell LA, Griffin CD, Lane E. The durability of mechanical heart valves replacements: past experience and current trends. In: Bodnar E, Frater RWM, editors. Replacement Cardiac Valves. New York: Pergamon Press; 1991. p 21–47.
65. Haubold AD. On the Durability of Pyrolytic Carbon In Vivo. Med Prog Through Technol 1994;20:201–208.
66. Kelpetko V, Moritz A, Mlczoch J, Schurawitzki H, Domanig E, Wolner E. Leaflet Fracture in Edwards-Duromedics Bileaflet Valves. J Thorac Cardiovasc Surg 1989;97: 90–94.
67. Kafesjian R, Howanec M, Ward GD, Diep L, Wagstaff L, Rhee R. Cavitation Damage of Pyrolytic Carbon in Mechanical Heart Valves. J Heart Valve Dis 1994;3(Suppl I): S2–S7.
68. Richard G, Cao H. Structural failure of Pyrolytic Carbon Heart Valves. J Heart Valve Dis 1996;5(Suppl I): S79–S85.
69. Shim HS, Schoen FJ. The wear resistance of pure and silicon-alloyed isotropic carbons. Biomater Med Dev Art Org 1974;2(2): 103–118.
70. Shim HS. The wear of titanium alloy, and UHMW polyethylene caused by LTI carbon and Stellite 21. J Bioengr 1977;1:223–229.
71. More RB, Silver MD. Pyrolytic Carbon Prosthetic Heart Valve Occluder Wear: In Vivo vs. In Vitro Results for the Björk-Shiley Prosthesis. J Appl Biomater 1990;1:267–278.
72. More RB. An Examination of Two Retrieved Long-Term Human Implant Bjork-Shiley Valves. Med Prog Technol 1994;20:195–200.
73. More RB, Haubold AD, Silver MD. Pyrolytic Carbon Wear in Retrieved Mechanical Heart Valve Prosthesis Implants. 25th Annual Meeting of the Society for Biomaterials, 1999. p 553.
74. More RB, Chang BC, Hong YS, Cao BK, Butany J, Wear Analysis of Retrieved Mitral Bileaflet Mechanical Heart Valve Prostheses, Presented to the Society for Heart Valve Disease, 1st Biennial Symposium, London; June 2001.
75. More RB, Haubold AD, Silver MD. Pyrolytic Carbon Wear in Retrieved Mechanical Heart Valve Prosthesis Implants. 25th Annual Meeting of the Society for Biomaterials, 1999. p 553.

76. Wieting DW. The Björk-Shiley Delrin Tilting Disc Heart Valve: Historical Perspective, Design and Need for Scientific Analyses After 25 Years. J Heart Valve Dis 1996;5(Suppl I): S157–S168.
77. Schoen FJ, Titus JL, Lawrie GM. Durability of Pyrolytic Carbon-Containing Heart Valve Prostheses. J Biomed Mater Res 1982;16:559–570.
78. Griffin CD, Buchanan RA, Lemons JE. In Vitro Electrochemical Corrosion Study of Coupled Surgical Implant Materials. J Biomed Mater Res 1983;17:489–500.
79. Thompson NG, Buchanan RA, Lemons JE. In Vitro Corrosion of Ti-6Al-4V and Type 316L Stainless steel When Galvanically Coupled with Carbon. J Biomed Mater Res 1979;13:35–44.
80. Cook SD, Thomas KA, Kester MA. Wear characteristics of the canine acetabulum against different femoral prostheses. J Bone Joint Surg 1989;71B:189–197.
81. Tian CL, Hetherington VJ, Reed S. A Review of Pyrolytic carbon: Application in Bone and Joint Surgery. J Foot Ankle Surg 1993;32(5):490–498.
82. Cook SD, Beckenbaugh RD, Redondo J, Popich LS, Klawitter JJ, Linscheid RL. Long term follow-up of pyrolytic carbon metacarpophalangeal implants. J Bone Joint Surg 1999; 81A(5): 635–648.
83. Ferrari M. Clinical evaluation of fiber-reinforced epoxy resin posts and cast post and cores. Am J Dent 2000; 01-May-13 (Spec No): 15B–18B.
84. Pamula E. Studies on development of composite biomaterials for reconstruction of the larynx. Polim Med 2001;31(1–2):39–44.
85. Katoozian H. Material optimization of femoral component of total hip prosthesis using fiber reinforced polymeric composites. Med Eng Phys 2001;23(7):503–509.
86. Früh HJ. Fusion implants of carbon fiber reinforced plastic. Orthopade 2002;31(5):454–458.
87. Dearnaley G. Diamond-like carbon: a potential means of reducing wear in total joint replacements. Clin Mater 1993;12:237–244.
88. Lappalainen R, Anttila A, Heinonen H. Diamond coated total hip replacements. Clin Orthop 352 (July 1998): 118–127.
89. Pantarotto D, Partidos CD, Graff R, Hoebeke J, Briand JP, Prato M. Bianco A. Synthesis, structural characterization, and immunological properties of carbon nanotubes functionalized with peptides. J Am Chem Soc 2003 May 21; 125(20): 6160–6164.
90. Qingnuan L, Yan X, Xiaodong Z, Ruili L, Qieqie D, Xiaoguang S, Shaoliang C, Wenxin L. Preparation of (99m)Tc-C(60)(OH)(x) and its biodistribution studies. Nucl Med Biol 2002 Aug; 29(6): 707–710.
91. Gonzalez KA, Wilson LJ, Wu W, Nancollas GH. Synthesis and in vitro characterization of a tissue-selective fullerene: vectoring C(60)(OH)(16)AMBP to mineralized bone. Bioorg Med Chem 2002 Jun; 10(6): 1991–1997.
92. Wolff DJ, Barbieri CM, Richardson CF, Schuster DI, Wilson SR. Trisamine C(60)-fullerene adducts inhibit neuronal nitric oxide synthase by acting as highly potent calmodulin antagonists. Arch Biochem Biophys 2002 Mar 15; 399(2): 130–141.
93. Schinazi RF, Sijbesma R, Srdanov G, Hill CL, Wudl F. Synthesis and virucidal activity of a water-soluble, configurationally stable, derivatized C60 fullerene. Antimicrob Agents Chemother 1993 Aug.; 37(8): 1707–1710.
94. Park KH, Chhowalla M, Iqbal Z, Sesti F. Single-walled carbon nanotubes are a new class of ion channel blockers. J Biol Chem 2003 Dec. 12; 278(50): 50212–50216, Epub 2003 Sep. 30.

See also Biomaterials: tissue engineering and scaffolds; biomaterials, testing and structural properties of; biosurface engineering; materials and design for orthopedic devices; heart valve prostheses.

BIOMATERIALS CORROSION AND WEAR OF

Roger J. Narayan
University of North Carolina
Chapel Hill, North Carolina

Miroslav Marek
Georgia Institute of Technology
Atlanta, Georgia

Chunming Jin
North Carolina State University
Raleigh, North Carolina

INTRODUCTION

Many materials suffer degradation with time when exposed to aggressive chemical environments within the human body. In metallic biomaterials, degradation results from electrochemical corrosion. Ceramic and polymeric biomaterials may undergo physical or chemical deterioration processes. In addition, mechanical forces may act to increase damage by wear, abrasion, or environment-induced cracking processes.

Corrosion of implants, dental restorations, and other objects placed in the human body may result in degradation of function as a result of loss of mass, decrease in mechanical integrity, or deterioration of aesthetic qualities. The associated release of corrosion products and the flow of the corrosion currents also may cause inflammation, allergic reactions, local necrosis, and many other health problems.

For electronic conductors (e.g., metals), corrosive interaction with ionically conducting liquids (e.g, body fluids) is almost always electrochemical. The degradation of metals is due to an oxidation process that involves the loss of electrons. This process involves a change from a metallic state to an ionic state, in which the ions dissolve or form nonmetallic solid products. For the process to continue, the released electrons must be consumed in a complementary reduction, which usually involves species present in the biological environment (e.g., hydrogen ions or dissolved oxygen). The reaction resulting in oxidation is usually called an anodic process and reaction resulting in reduction is usually called a cathodic process. The metal is referred to as an electrode, and the liquid environment is referred to as an electrolyte.

For many metals, the most important environmental variables are the concentrations of chloride ions, hydrogen ions, and dissolved oxygen. In many human body fluids, the chloride ion concentration varies in a relatively narrow range near $0.1\,\text{mol}\cdot\text{L}^{-1}$; however, it may be variable (e.g., urine) or lower (e.g., saliva) in certain body fluids. The hydrogen ion concentration is expressed as a pH value and is near neutral ($\text{pH} = 7$) for plasma, interstitial fluid, bile, and saliva; however, it is more variable ($\text{pH} = 4$–8) in urine and very low ($\text{pH} = 1$–3) in gastric juice (1). The chloride concentration and pH are most important factors determining the rate of oxidation because of their effect on protective oxide passivating films on metals. The dissolved oxygen concentration affects mainly the cathodic process. The usual range of partial pressure of oxygen in body fluids is $\sim$40–100 mmHg (5.33–13.33 kPa) (1–3).

For electrochemical oxidation to cause clinically relevant degradation of a material, the electrochemical reaction must be energetically possible (thermodynamics) and the reaction rate must be appreciable (kinetics). Oxidation of nickel, for example,

$$\mathrm{Ni} \rightarrow \mathrm{Ni}^{2+} + 2\mathrm{e}^- \tag{1}$$

will proceed in the indicated direction if the potential of the electrode on which the reaction occurs is higher (more positive or less negative) than the equilibrium potential for a given electrolyte, and is a function of the energy change involved. The equilibrium potential also depends on temperature, pressure, and activity ($\approx$concentration) of ions. The values of potentials for reactions between metals and their ions in water are given under standard conditions (temperature 25 °C, pressure 1 atm, and activity of ions equal to 1) and are written in the form of materials reduction. These values, known as standard single electrode potentials, are listed in the so-called electrochemical or electromotive (EM) series (1). Noble metals, which have no tendency to dissolve in water have positive standard single-electrode potentials. On the other hand, active metals with a high tendency to react with water exhibit negative potentials.

While the potential of the anodic process must be above the equilibrium potential for the reaction to proceed as oxidation, for the cathodic process the electrode potential must be below (more negative or less positive) the equilibrium potential for net reduction to occur. For reduction of hydrogen ions,

$$2\mathrm{H}^+ + 2\mathrm{e}^- = \mathrm{H}_2 \tag{2}$$

the equilibrium potential at normal body temperature (37 °C) and pH 7.4 (blood or interstitial fluids) is -0.455 V (SHE) (-0.697 V, SCE), while the equilibrium potential of the other likely cathodic reaction,

$$\mathrm{O}_2 + 4\,\mathrm{H}^+ + 4\mathrm{e}^- = 2\,\mathrm{H}_2\mathrm{O} \tag{3}$$

is -0.753 V (SHE) (0.511 V, SCE) at 40 mmHg (5.33 kPa) of oxygen partial pressure. Although reaction 3 is more sluggish than reaction 2, for most metals in the human body the electrode potential of reaction 3 is above the equilibrium potential of the hydrogen reaction 2, and reduction of oxygen is the dominant cathodic process.

In spontaneous electrochemical corrosion, at least two reactions occur simultaneously. At least one reaction occurs in the direction of oxidation, and at least one reaction occurs in the direction of reduction. Each reaction has its own equilibrium potential, and this potential difference results in a current flow, as the electrons released in oxidation flow to the sites of reduction and are consumed there. In the absence of a significant electrical resistance in the current path between the reaction sites, a common potential is established, which is known as mixed potential or corrosion potential (E_{corr}). At this potential, both reactions produce the same current in opposite directions in order to preserve electrical neutrality. The value of the oxidation current, which is equal to the absolute value of the reduction current, per unit area at this potential is known as the corrosion current density (i_{corr}). The oxidation and reduction reactions may be distributed uniformly on the same metal surface; however, there are often some regions of the biomaterial surface that are more favorable for oxidation and other regions that are more favorable for reduction. As a result, either local anodic and cathodic areas or completely separate anodes and cathodes are formed.

The corrosion rate (mass of metal oxidized per unit area and time) is proportional to the corrosion current density. The conversion is given by the Faraday's law, which states that an electric charge of 96,485 C is required to convert 1 equiv weight of the metal into ions, or vice versa. The shift of the potential of a reaction from the equilibrium value to the corrosion potential is called polarization by the flow of the current. The resulting current flowing at corrosion potential depends on the way the current of each reaction varies with the potential. If the current is controlled by the activation energy barrier for the reaction at the electrode surface, then the reaction rate increases exponentially with increasing potential for oxidation reactions and decreases exponentially with increasing potential for reduction reactions. The activation energy controlled current typically increases or decreases ten times for a potential change of ~50–150 mV. At high reaction rates, the current may become limited by the transport of reaction species to or from the electrodes; eventually, the corrosion process may become completely controlled by diffusion and independent of potential.

The vast majority of uses for metallic biomaterials in the human body are successful due to the phenomenon of passivity. In a passive state, these metals become covered with thin, protective films of stable, poorly soluble oxides or hydroxides when exposed to an aqueous electrolyte. Once this passivating film forms, the current density drops to a very low value and becomes much less dependent on the potential. The variation of the reaction current density with the potential can be illustrated in a polarization diagram. A schematic diagram in Fig. 1 shows some of the main reactions in corrosion and relevant parameters. A straight-line relationship in a semilogarithmic (E vs. $\log I$) diagram indicates that an activation energy-controlled reaction is occurring. This electrochemical activity is known as Tafel behavior, and the slopes of the lines (~50–150 mV per 10-fold change in the current or current density) are equal to the values of the Tafel constants. When the oxidation reaction of the metal shows this relationship at the corrosion potential, it indicates that the metal is actively corroding. If a metal forms a passivating film when the potential exceeds a critical value in the active corrosion region, then the current density drops from a value called the critical current density for passivation (i_{crp}) at a primary passivation potential (E_{pp}) to a low current density in the passive state (i_{p}). This behavior is illustrated schematically in Fig. 2. For an electrode to maintain a stable passive state, the intersection of the oxidation (anodic) and reduction (cathodic) lines must occur in the region of passivity.

The polarization characteristics of a biomaterial can be experimentally determined using a device called a potentiostat, which maintains the sample potential at a set value



Figure 1. Schematic polarization diagram showing oxidation (anodic) and reduction (cathodic) reactions of a corrosion process, for reactions controlled by activation energy and by mass transport (diffusion). In this figure, e_a and e_c refer to equilibrium potentials of the anodic and cathodic process, respectively, i_{oa} and i_{oc} refer to exchange current densities, E_{corr} refers to mixed corrosion potential, and i_L refers to limiting current density.

versus a reference electrode by passing current between the sample and an auxiliary counterelectrode. A scan generator can be used to vary the controlled potential over a range of interest, and the E–i relationship can be determined. The relationship of main interest is usually the oxidation rate as a function of the potential, which can be depicted in an anodic polarization diagram. Since only a net current (difference between the absolute values of the oxidation and reduction currents) can be measured, the experimental polarization curve shows a value approaching zero at the intersection of the anodic and cathodic polarization curves.

Experimental anodic polarization curves for passivating metals and alloys often do not exhibit the passivation peak shown in Fig. 2, either because the metal forms an oxide in the electrolyte without undergoing active dissolution or because an oxide film already has formed as a result of exposure to air. More importantly for human body fluids and other chloride-containing electrolytes, the region of passivity is often limited by a localized passivation breakdown above a critical breakdown potential (E_b). When a breakdown occurs, intensive oxidation takes place within localized regions on the biomaterial surface, resulting in sometimes significant pit formation. In an experimental anodic polarization diagram, breakdown appears as a sharp increase in the measured current above the critical breakdown potential. Because of the destructive nature of surface pitting, the determination of critical breakdown potential is one of the most important ways of assessing the suitability of novel metallic biomaterials for use in medical devices.

The high current density in active pits is due to the absence of a passivating film, which results from local chemical and electrochemical reactions that change the electrolyte to become highly acidic and depleted in dissolved oxygen. A similar corrosion mechanism may occur in interstices known as crevices, where the transport of species to and from the localized corrosion cell is difficult. This process, known as crevice corrosion, does not require a potential exceeding the critical breakdown potential for the initiation of corrosion. Both pit and crevice corrosion cells may repassivate if the potential is lowered below a value needed for maintenance of a high oxidation rate on the bare (nonpassivated) metal surface. The potential below which active pits repassivate is called the repassivation or protection potential (E_p). The concept of a protection potential also applies to crevice corrosion. Experimentally, repassivation can be studied by reversing the anodic polarization scan and recording the potential at which the current returns to a passive state value (Fig. 3). Repassivation can also be examined by initiating pitting or crevice corrosion and lowering the potential in steps until the current



Figure 2. Schematic polarization diagram, showing a transition from active to passive state and a breakdown of passivity. In this figure, i_{crp} refers to critical current density for passivation, i_p refers to current density in the passive state, E_{pp} refers to primary passivation potential, and E_b refers to breakdown potential.



Figure 3. Schematic experimental cyclic polarization diagram for a passivating electrode, showing passivity breakdown and repassivation after potential scan reversal. In this figure, E_{prot} refers to protection (repassivation) potential.

shows low values that decrease with time (standard test methods F2129 and F746, respectively, ASTM 2005) (4). The difficulty in finding a reliable protection potential value is due to the fact that the ease of repassivation depends on the extent of pitting or crevice corrosion damage that has occurred before the potential drop.

For some polyvalent metals (e.g., chromium), soluble species (e.g., CrO_4^{2-}) become thermodynamically stable as the valence changes (e.g., from 3 to 6 in chromium) at potentials above those for a stable oxide. This process may result in another region of active dissolution at high potentials in a phenomenon known as transpassivity.

When corrosion is relatively uniform throughout the biomaterial, the most important corrosion parameter is the average corrosion rate. For biomaterials with very low corrosion rates, the average corrosion rate is mostly determined by sensitive electrochemical techniques. The average corrosion current density (i_{corr}) is usually determined either from the results of the polarization scan by extrapolating the anodic and cathodic lines to the corrosion potential or from calculating the value of the polarization resistance. The polarization resistance (R_{p}) is defined as the slope of the polarization curve at zero current density [$R_{\text{p}} = (dE/di_{\text{n}})_{i_{\text{n}}=0}$], in which i_{n} is the net (measured) current density.

When two or more dissimilar metals are placed in contact within an electrolyte, their interaction may cause galvanic corrosion. The oxidation degradation is enhanced for the metal with the lower individual corrosion potential, which becomes the anode of the cell. It is polarized towards a higher potential at the other electrode, which becomes the cathode. Since the oxidation current increase on the anode must be balanced by an identical reduction current increase on the cathode, a combination of a small anode with a large cathode is more detrimental than the reverse situation, since a larger increase in the oxidation current density is produced. In practical situations, resistance in the current path between the electrodes often reduces the galvanic effect. Differences in the concentrations of reaction species at different regions on the metal surface may result in a potential difference, which leads to additional polarization. An increase in the oxidation current density, a difference in the equilibrium potentials, and a flow of current may result. Differences in concentrations of hydrogen ions, dissolved metal ions, or dissolved oxygen may result in concentration cell corrosion.

Metal parts subjected to mechanical loading in a corrosive environment may fail by environment-induced cracking (EIC). Stress corrosion cracking (SCC) may occur in some biomaterials when they are subjected to static loading under certain environmental conditions. Corrosion fatigue (CF) may result from variable loading in reactive environments. When the failure can be attributed to the entry of hydrogen atoms into the metal, the phenomenon is referred to as hydrogen induced cracking (HIC). Environment-induced cracking may be caused by complex combinations of mechanical, chemical, and electrochemical forces; however, the exact mechanisms of this behavior are subject to significant controversy. In these cases, mechanical factors may play important roles in crack propogation.

Intergranular corrosion occurs when dissolution is confined to a narrow region along the grain boundaries. This process is either due to precipitation of corrosion susceptible phases or due to depletion in elements that provide corrosion protection along the boundaries, which is caused by precipitation of phases rich in those elements. Some stainless steel and nickel-chromium alloys may be sensitized due to precipitation of chromium-rich carbides along grain boundaries when heated to a specific temperature range. Sensitization is normally prevented from occurring in stainless steels currently used in medical devices, which contain very low amounts of carbon.

Passivating films may also be mechanically destroyed in wear- , abrasion- , erosion- , and fretting-corrosion processes. Wear-corrosion involves materials in a friction contact that exhibit substantial relative movement. Fretting occurs in situations in which there are only small relative movements between materials that are essentially fixed with respect to one another. The resulting wear debris may cause abrasion–corrosion behavior. Wear-corrosion may occur in artificial joints, including the metal ball of a hip joint in contact with the polyethylene cup. Fretting may take place between the ball and the stem of multicomponent hip implants. In both forms of corrosion, the narrow gap between contacting surfaces creates crevice conditions. In addition, the destructive effect of friction and abrasion on the protective surface film is superimposed on the corrosion mechanism in the crevice cell. Erosion corrosion may occur on devices exposed to rapidly flowing fluids, including the surfaces of artificial heart valves.

A wide variety of metals and alloys have been used in medical devices. The three most commonly used alloys are stainless steel, cobalt alloys, and titanium alloys (5). Type 316 LVM (low carbon, vacuum-melted) stainless steel is less corrosion resistant than cobalt or titanium alloys, and it is most often used for temporary implants (5–8). This material is referred to as an austenitic steel, because it contains an iron carbide phase called austenite (γ-iron). Implant-grade steel has a nominal composition of 18% chromium, 14% nickel, and 2.5% molybdenum; the compositional limits and properties are specified by ASTM standards F 138 and F 139 for wrought steel and F 745 for cast steel (ASTM, 2005) (4). Chromium serves to improve corrosion resistance through the formation of a highly protective surface film rich in chromium oxide. Implant-grade steel has a low carbon content in order to prevent sensitization and intergranular corrosion. Alloying with - molybdenum further improves the resistance, especially to crevice corrosion and pitting. Nickel serves to stabilize the face-centered cubic (fcc) structure. On the other hand, manganese sulfide inclusions, which contribute to initiation of pitting, are minimized.

The corrosion resistance of stainless steel greatly depends on the surface conditions, and stainless steel implants are almost always electropolished and prepassivated by exposure to nitric acid (standard practice F86, ASTM 2005) (4). The breakdown potential is usually around 0.4 V (SCE), with a large hysteresis loop and a low protection potential (9). Considering that the potential in the human body is not likely to exceed about 0.5 V (SCE) (see Eq. 3 and its equilibrium potential), a well polished and passivated 361 LVM stainless steel is not very susceptible to pitting in the human body, especially for unshielded and undisturbed implant surfaces. Once localized attack is initiated, however, repassivation is difficult. As a result, stainless steel implants are very susceptible to crevice corrosion, especially when the crevice situation is combined with destruction of the surface film (e.g., fretting of bone plates under the screw heads). Small single component stainless steel implants, such as balloon-expandable vascular stents, that are made of high purity precursor materials and are subjected to a high quality surface treatment and inspection can achieve a breakdown potential in excess of 0.8 V (SCE); these materials are considered very resistant to localized corrosion (10). Stainless steel bars [containing 22% chromium 12.5% nickel , 5% manganese, and 2.5% molybdenum (ASTM F 1586)] and wires [containing 22% chromium, 12.5% nickel, 5% manganese, and 2.5% molybdenum (ASTM F 1314)] strengthened with nitrogen have shown a higher breakdown potential than ASTM F 138 steel (4).

Vitallium and other cobalt–chromium alloys were developed as a corrosion resistant, high strength alternative to stainless steel alloys. These materials were first used in dentistry, and were later introduced to orthopedics and other surgical specialties. The cast cobalt–chromium alloy most commonly used in medical devices (ASTM F 75) contains 28% chromium and 6% molybdenum (4). This alloy was found to be suitable for investment casting into intricate shapes. In addition, it exhibited very good corrosion and excellent wear resistance; however, it possessed low ductility. Alloys with slightly modified compositions were later developed for forgings (ASTM F 799) and wrought bars, rods, and wire (ASTM F 1537) (4). Alloy F75 has shown corrosion resistance superior to stainless steel in the human body. Laboratory studies reported a breakdown potential of 0.5 V (SCE) and protection potential of 0.4 V (SCE) (6,7,9,11). These properties have made it possible to use cobalt–chromium alloys for permanent implants. Cobalt–chromium alloys with porous surfaces have been used for bone ingrowth, although they have been superseded by even more crevice corrosion resistant and biocompatible titanium alloys. The excellent corrosion resistance of cobalt–chromium alloys can be attributed to a high chromium content and a protective surface film of chromium oxide. Concerns have been raised, however, regarding the release of biologically active hexavalent chromium ions (12). Other cobalt-based wrought surgical alloys include F90 (Co-Cr-W-Ni), F563 (Co-Ni-Cr-Mo-W-Fe), F563 (Co-Ni-Cr-Mo-W-Fe), F1058 (Co-Cr-Ni-Mo), and F688 (Co-Ni-Cr-Mo) (4). These alloys provide good to excellent corrosion behavior and a variety of mechanical properties, which depend on thermomechanical treatment. However, there is some concern regarding metal ion release in these alloys, which contain high nickel concentrations.

Titanium and titanium alloys have been used in orthopedic implants and other medical devices since the 1960s. Their popularity has rapidly increased because they possess high corrosion resistance, adequate mechanical properties, and relatively benign degradation products. Although titanium is thermodynamically one of the least stable structural metals in air and water, it acquires high resistance to corrosion due to a very protective titanium oxide film. Unalloyed titanium (ASTM F67 and F1341) and titanium-6 % aluminum, 4 % vanadium alloy (ASTM F136 and F1472 for wrought alloy and F1108 for castings) are commonly used in orthopedic prostheses (4). These materials exhibit a breakdown potential in body fluid substitutes well above the physiological range of potentials (several volts vs. SHE). In addition, they readily repassivate in biological fluids, which makes them highly resistant to pitting and crevice corrosion. The high crevice corrosion resistance and biocompatibility of titanium alloys have made it possible to create porous titanium surfaces that allow for bone ingrowth and cementless fixation of implants.

One shortcoming of titanium and titanium alloys is their relatively poor wear resistance (5). Since resistance to corrosion depends on the integrity of the protective oxide film, wear-corrosion remains a problem for titanium alloy prostheses. Surface treatments (including nitrogen diffusion hardening, nitrogen ion implantation, and thin-film deposition) may be used to provide more wear-resistant articulating surfaces. Another solution to titanium wear involves the use of multicomponent implants (e.g., implants that contain smooth surfaces made of cobalt–chromium alloy for articulating components and porous surfaces made out of titanium alloy for bone ingrowth and biological fixation). However, fretting corrosion may occur as a result of micromovement at the taper joints between the components, which may destroy the surface passivating films and increase overall corrosion rates (13–15). In spite of the very successful use of the Ti-6Al-4V alloy orthopedic implants, some concern remains regarding the possible toxicity of the aluminum and vanadium components within this alloy. A variety of vanadium-free or aluminum- , and vanadium-free alloys have been developed, including Ti-15Sn-4Nb-2Ta-0.2Pd, Ti-12Mo-6Zr-2Fe (TMZF), Ti-15Mo, and Ti-13Nb-13Zr (5). Ti-12Mo-6Zr-2Fe (TMZF) and Ti-13Nb-13Zr alloys exhibit lower elastic moduli and higher tensile properties. The alloying elements also form highly protective oxides, which contribute to the excellent corrosion resistance of these materials (16).

An equiatomic nickel–titanium alloy (Nitinol) has received considerable interest as an implant material because of its shape memory and pseudoelasticity properties, the latter resulting in a very low apparent elastic modulus. This superelastic behavior has allowed the development of self-expandable vascular stents, bendable eyeglass frames, orthodontic dental archwire, and intracranial aneurysm clips. Several studies have shown good biocompatibility of Nitinol; however, clinical failures have also been reported (17–19). Laboratory studies have shown a wide variety of performance, with resistance to the breakdown of passivity ranging from poor to excellent (20–22). Resistance to the initiation of pitting critically depends on the surface conditions. A surface film that consists mostly of titanium oxide results in a high resistance to pitting; however, the presence of elemental nickel or nickel oxide reduces the breakdown potential. In addition, recent studies have shown that strained nickel–titanium alloy exhibits significant improved corrosion resistance over as-prepared materials. Other conditions that may affect corrosion resistance include surface roughness, the presence of inclusions, and the concentration of intermetallic species (23).

Another group of biomaterials is used in restorative dentistry and orthodontics. Materials for restorative dentistry must not only meet corrosion, wear, and compatibility considerations described earlier, but also satisfy aesthetic requirements and must have the capacity to be either precisely cast into intricate shapes or used to directly fill a prepared cavity in a tooth. Dental cast alloys can be roughly divided into three major groups of high noble alloys, seminoble alloys, and base alloys. The high noble alloys include those with a high percentage of gold or other noble metals (e.g., platinum), and derive their corrosion resistance mainly from a low thermodynamic tendency to react with the environment. Seminoble alloys often have complex compositions, and either possess a relatively low noble metal content or contain a significant concentration of silver. These materials possess a higher thermodynamic tendency to react than high noble alloys; however, their kinetics of aqueous corrosion in saliva is sufficiently slow, and allows these materials to provide adequate corrosion resistance under biological conditions. The main corrosion concern for seminoble alloys is their tendency to react with sulfur in food and drinks and form dark metallic sulfide film, resulting in the loss of aesthetic quality. Base dental cast alloys include cast titanium, titanium alloys, and nickel–chromium alloys. These materials lack the aesthetic qualities of noble alloys; however, they are resistant to sulfide tarnishing. Nickel–chromium alloys exhibit passivation behavior and some susceptibility to pitting and crevice corrosion. Cast titanium and titanium alloys exhibit highly protective passive films and high resistance to chloride corrosion; however, they demonstrate some susceptibility to fluoride attack, which is of some concern due to the prophylactic use of fluoride rinses and gels. Direct-filling metallic materials include unalloyed gold and dental amalgams, which are alloys of mercury, silver, tin, copper, and some other minor elements. Dental amalgams have a higher thermodynamic tendency for reaction with the oral environment than noble and seminoble cast dental alloys. In addition, these materials receive weaker protection by passivating surface films than implant alloys. However, these materials have shown adequate long-term clinical corrosion resistance. This property has been greatly improved by the transition from low copper amalgams, which contain a corrosion susceptible Sn–Hg structural phase, to high copper amalgams, which contain a more corrosion resistant Sn–Cu phase. Low copper amalgams exhibit breakdown of passivity and suffer from selective corrosion of the tin–mercury phase, which penetrates and weakens the structure. On the other hand, high copper amalgams do not show breakdown in laboratory testing and have demonstrated better clinical performance. The use of dental amalgam in dentistry has been on the decline as a result of concerns regarding the release of small amounts of toxic mercury and due to improvements in the performance of nonmetallic dental composites. Recent reviews on dental alloys and their corrosion behavior can be found in Refs. (24) and (25). Materials for orthodontic applications include cobalt–chromium alloys, titanium alloys, nickel–titanium alloys, which exhibit similar corrosion behavior in dental applications and medical applications.

Ceramic materials were first used in medical devices in the early 1970s. These materials are either crystalline or amorphous, and contain atoms linked by highly directional ionic bonds. Alumina (Al_2O_3) and zirconia (ZrO_2) exhibit high passivation tendencies and resistance to breakdown properties. These materials exhibit better corrosion resistance, hardness, stiffness, wear resistance, and biocompatibility properties than metal alloys. Zirconia and alumina used in medical devices exhibit full-densities and uniformly controlled small grain sizes ($<5\,\mu m$) (26). Full-density ceramics are used in medical devices, because voids may increase stresses and degrade mechanical properties. Ceramics containing uniform small grains are used in order to minimize internal stresses from thermal contraction. In addition, ceramics with small grain sizes exhibit enhanced wear, hardness, and strength properties (27–31). Typical material combinations for ceramic hip prostheses include ceramic-on-ceramic; ceramic-on-metal; and ceramic-on-polymer wear couples.

A ceramic coating material that may provide corrosion resistance to an orthopedic prosthesis is diamond-like carbon (DLC). Diamond-like carbon refers to amorphous carbon materials that contain some component of sp^3-hybridized atoms. Nano- or microcrystalline graphite regions may also be present within the amorphous matrix. Hydrogen-free diamond-like carbon exhibits atomic number densities $>3.19\,g\ atom\cdot cm^{-3}$. Hydrogenated diamond-like carbon (HDLC) contains up to 30 atomic percent hydrogen and up to 10 atomic percent oxygen within CH_3 and OCH_3 inclusions, which are surrounded by an amorphous carbon matrix. The density of hydrogenated coatings rarely exceeds $2.2\,g\cdot cm^{-3}$. Hydogenated or hydrogen-free diamond-like carbon coatings may provide a medical device with an atomically smooth, low friction, wear resistant, corrosion resistant hermetic seal between the bulk biomaterial, and the surrounding tissues. Tiainen demonstrated extremely low corrosion rates for diamondlike carbon-coated metals (32). The hydrogen-free diamond-like carbon coated-cobalt–chromium–molybdenum alloy and cobalt–chromium–molybdenum alloy were placed in saline solution equivalent to placement in body fluid for 2 years at a temperature of 37 °C. The DLC-coated cobalt–chromium–molybdenum alloy exhibited 10^5 lower corrosion rate than cobalt–chromium–molybdenum alloy. Similarly, the corrosion rate of DLC-coated titanium–aluminum-vanadium alloy in saline solution has been shown to be extremely low.

Bioactive ceramic materials, which develop a highly adherent interface with bony tissue, have been developed for several medical and dental applications, including coatings for promoting bone ingrowth, grouting agents for hip arthroplasty, and replacements for autologous bone grafts. The most commonly used bioactive ceramics include hydroxyapatite, $Ca_{10}(PO_4)_6(OH)_2$, tricalcium phosphate, $Ca_3(PO_4)_2$, and $Na_2OCaOP_2O_5SiO_2$ glasses (e.g., Bioglass). These materials undergo chemical–biochemical processes, which are dependent on several material properties. For example, 45S5 Bioglass, which contains 45 wt% SiO_2 and 5:1 $CaO:P_2O_5$ ratio, forms SiOH bonds, hydrated silica gel, hydroxyl carbonate apatite layer, matrix, and bone at the material/tissue interface. Materials with high (>60 mol%) SiO_2, low CaO/P_2O_5 ratios, and additions of Al_2O_3, ZrO_2, or TiO_2 are not highly reactive in aqueous media, and do not demonstrate bonding to bone. For example, Bioglass degradation is highly dependent on composition. The dissolution behavior of calcium phosphate ceramics depends on their composition, crystallinity, and processing parameters. For example, materials with larger surface areas (e.g., powders) and smaller grain sizes resorb more rapidly due to preferential degradation at grain boundaries. Phase is another important factor, with alpha-tricalcium phosphate and beta-tricalcium phosphate degrading more slowly than hydroxyapatite. Hydrated forms of calcium phosphate are more soluble than nonhydrated forms. In addition, ionic substitutions affect resorption rate; CO_3^{2-}, Mg^{2+}, and Sr^{2+} increase and F^- decreases biodegradation. Finally, low pH conditions seen in infection and inflammation can result in locally active dissolution processes.

Polymers used in medicine include polyethylene, poly(methyl methacrylate), poly(dimethylsiloxane), poly(tetrafluoroethylene), and poly(ethyleneterephylate). These structures contain primarily covalent atomic bonds, and many undergo several *in vivo* degradation processes. Water, oxygen, and lipids may be absorbed by the polymer, which may result in local swelling. Polyamides avidly absorb lipids and undergo a stress-cracking process known as crazing; these materials may swell up to five volume percent, and can serve as locking inserts for screws. Desorption (leaching) of low molecular weight species can occur due to release of species remaining from fabrication or from chain scission processes, including free radical depolymerization and hydrolysis. Hydrolytic- and enzymatic-based degradation processes are also possible. Wettability also has a prominent effect on the degradation rate of polymers. Degradation of hydrophilic polymers occurs by surface recession, and may resemble uniform corrosion of metals. Hydrophobic polymers may absorb water and other polar species. As a result, the amorphous regions may dissolve preferentially to crystalline ones, increasing the surface area and the effective dissolution rate. A process similar to inter-granular corrosion may result, with abrupt loss of integrity and small particle release.

WEAR

Wear is the loss of material as debris when two materials slide against one another, which may result in abrasion, burnishing, delamination, pitting, scratching, or embedding of debris. The study of wear, friction, and lubrication was integrated in a 1966 British Department of Education and Science report into a new branch of science known as tribology. The term biotribology was coined in 1973 by Dowson to describe wear, friction, and lubrication in biological systems (33). Over the past 30 years, biotribologists have considered the wear properties of orthopedic, dental, cardiovascular, ophthalmic, and urologic devices, including artificial joints, dental restorations, artificial vessels, prosthetic heart valves, and urinary catheters.

Much of biotribology research has focused on orthopedic prostheses, including devices that replace the function of the hip, knee, shoulder, and finger joints. Hip prostheses have provided control of pain and restoration of function for patients with hip disease or trauma, including osteoarthritis, rheumatoid arthritis, osteonecrosis, posttraumatic arthritis, ankylosing spondylitis, bone tumors, and hip fractures. Polymers, metals, ceramics, and composites have been used on the bearing surfaces of orthopedic prostheses. At present, there are three material combinations used in hip prostheses: a metallic head articulating with a polymeric acetabular ceramic cup; a metallic head articulating with a metallic acetabular metallic cup; a ceramic head articulating with a ceramic acetabular polymeric cup.

Osteolysis and aseptic loosening (loosening in the absence of infection) are the major causes of hip prosthesis failure. In 1994, the National Institutes of Health concluded that the major issues limiting hip prosthesis lifetime include the long-term fixation of the acetabular component, biological response due to wear debris, and problems related to revision surgery (34). Although problems with acetabular fixation have been significantly reduced in the intervening years, wear and the biological response to wear debris remain major problems that reduce the longevity of hip prostheses.

Wear may affect the longevity and the function of hip and other orthopedic prostheses. Clinical practices, patient-specific factors, design considerations, materials parameters, and tissue-biomaterial interaction all play significant roles in determining implant wear rates (35). The complex interaction between these parameters makes it difficult to determine a relationship between the in vitro properties of biomaterials and the *in vivo* wear performance for joint prostheses. For example, particles produced by wear may excite both local and systemic inflammatory responses. In addition, the function of prostheses may be affected by the shape changes that are caused by uneven wear of surfaces. More effective collaboration among clinicians, material scientists, and biologists is necessary to understand the underlying biological, chemical, mechanical, and patient related parameters associated with wear of prostheses.

Wear may occur via adhesive, abrasive, fatigue, or corrosive mechanisms (30–33). The wear process for a given medical device is usually a combination of these mechanisms; however, one mechanism often plays a dominant role. The most important wear mechanism in orthopedic prostheses is adhesive wear. Adhesive wear is caused by adhesive forces that occur at the junction between rough surfaces. Adhesive wear may occur at asperities, or regions of unevenness, on opposing surfaces. Extremely large local stresses and cold welding processes may occur at the junctions between materials. Material may be transferred from one surface to the other as a result of relative motion at the junction. The transferred fragments may be either temporarily or permanently attached to the counterface surface. During this process, the volume of wear material produced is proportional to both the sliding distance acting on the device and the load. The volume of wear materials produced is also inversely proportional to the hardness of the material. For acetabular hip and tibial knee prostheses, adhesive wear is dependent on the large-strain deformation of polyethylene. For acetabular components under multiaxial loading conditions, plastic strain is locally accumulated until a critical strain is reached. Adhesive wear and submicron wear particle release occurs if this critical value is exceeded (30). Although adhesive wear is the most commonly occurring wear mechanism, it is also the most difficult one to prevent.

Abrasive wear takes place when a harder material ploughs into the surface of a softer material, resulting in the removal of material and the formation of depressions on the surface of the softer material. In general, materials that possess higher hardness values exhibit greater resistance to abrasive wear; however, the relationship between resistance to abrasive wear and hardness is not directly proportional. Abrasive wear is called two-body wear when asperities on one surface plough into and cause abrasion on the counterface surface (36). For example, hip prosthesis simulator testing has shown a positive correlation between the surface roughness of the metallic femoral head and the amount of wear damage to the polyethylene acetabular cup. Isolated scratches on a metallic counterface may also participate in abrasive wear. Three-body wear can also occur if hard, loose particles grind between two opposing surfaces that possess similar hardness values. These loose particles may arise from the material surfaces or from the immediate environment, and may become either trapped between the sliding surfaces or embedded within one of the surfaces. For example, metal, polymer, or tissue (e.g., bone) particles embedded in a polyethylene-bearing surface may act to produce third-body wear in orthopedic prostheses. The overall rate of abrasive wear in polyethylene, metal, and ceramic orthopedic prosthesis components depends both on the surface roughness of the materials and the presence of hard third-body particles.

Fatigue wear is caused by the fracture of materials that results from cyclical loading (fatigue) processes. Surface cracks created by fatigue may lead to the generation of wear particles. Cracks deeper within the biomaterial may generate larger particles, in a process known as microcracking. This process typically occurs in metal components; however, has been observed in other materials (e.g., polyethylene) as well. Corrosive wear results from chemical or electrochemical reactions at a wear surface. For example, metals may react with oxygen at a wear surface (oxidation). The resulting oxide may have a lower shear strength than the underlying metal, and may exhibit a more rapid wear rate than the surrounding material. The rate of corrosive wear is governed by the reactivity of the biomaterial, the chemical properties of the implant site, and the mechanical activity of the medical device.

A film or layer of lubricant between the two bearing surfaces can serve to reduce frictional forces and wear. Lubrication can be divided into three regimes: full film (hydrodynamic) lubrication, boundary lubrication, and mixed lubrication. In full film lubrication, the sliding surfaces are entirely separated by a lubricant film that is greater in thickness than the roughness of the surfaces. In boundary lubrication, the surfaces are separated by an incomplete lubricant film, which does not prevent contact by asperities on the surfaces. A mixed lubrication is the one that encompasses aspects of full film and boundary lubrication, in which a region of the two surfaces exhibits boundary lubrication, and the remainder exhibits full film lubrication. The healthy synovial joint provides a low wear and low friction environment, which may exhibit combination of these lubrication modes. Under normal conditions, the hip, knee, and shoulder joints exhibit full film lubrication, in which the two opposing surfaces are entirely separated by a lubricant film of synovial fluid, which carries the load of the joint.

Wear testing is an important consideration during the development of novel biomaterials and medical devices. Any changes in biomaterial or implant design parameters, including composition, processing, and finishing, should be accompanied by studies that confirm that these changes provide either equivalent or improved wear performance to the implant under clinical conditions. As mentioned earlier, asperities on the contact surfaces generally have a significant effect on overall wear performance. In addition, wear has been described as an accumulative process, because overall wear behavior is highly dependent on the material and testing history. An isolated event during a wear test (e.g., the presence of a third-body wear particle) may have a significant impact on the behavior that is observed.

Wear can be assessed in several ways, including which involve changes in shape (dimensions), size, weight of the implant, weight of the debris, or location of radioactive tracers (37). A standard parameter, known as a wear factor, can be used to estimate the wear effects obtained from different wear tests. The wear factor (K) is defined as

$$K = V/LX \tag{4}$$

in which V is the volume of wear (mm^3), L is the applied load (N), and X is the sliding distance (m). Many parameters can influence the results of wear testing,



Figure 4. Schematic illustration of geometries in which wear phenomena are likely to occur: (1) pin-on-disk; (2) crossed cylinder; (3) journal bearing; and (4) ball-and-socket bearing (After Ref. 31.)

including test lubricants, test duration, sliding velocity, contact area, alignment, and vibration.

Wear studies fall under three broad categories: (a) screening studies that involve testing of materials with simple geometries under well-controlled conditions; (b) simulator studies that involve testing of partial or complete prostheses; and (c) *in vivo* and retrieval studies of complete implanted devices. Screening studies may provide a basis for comparing novel materials against established materials; however, they can only provide estimations for wear of medical device components. Screening studies involve four general types of geometries: (1) pin-on-disk; (2) crossed cylinder; (3) journal bearing; and (4) spherical or ball and socket bearing. Geometries (3) and (4) are most similar to those encountered in orthopedic protheses (Fig. 4) (35). Simulator studies can be used to assess biomaterials and compare the wear characteristics of materials within a medical device. Various design and material combinations can be examined prior to animal studies and the clinical trials. Clinical assessments and implant retrieval studies also provide useful information for improving biomaterials, medical device design, and manufacturing protocols.

Much of current biotribology research focuses on the relationship between wear performance and biomaterial properties, including composition, processing, and finishing. However, other parameters have significant impact on the wear performance of the prostheses, including surgical and patient factors. The wear performance of polymer, metal, and ceramic biomaterials is discussed below.

Ultrahigh molecular weight polyethylene is commonly used in load-bearing components of total joint prostheses (38–45). The use of a polyethylene/cobalt–chromium wear couple in orthopedic prosthesis was first advocated by Charnley. In many contemporary total hip prosthesis designs, an ultrahigh molecular weight polyethylene acetabular cup slides against a cobalt–chromium alloy femoral ball. Significant numbers of submicron-sized ultrahigh molecular weight polyethylene wear particles are commonly released from these prostheses with each movement of the joint. These particles may remain in the synovial fluid that serves to lubricate the joint (and contribute to third-body wear), embed in prosthesis surfaces, or enter lymphatic circulation. Immune cells (e.g., macrophages) may identify these particles as foreign materials and initiate an inflammatory response, which can lead to rapid bone loss (osteolysis), prosthesis loosening, or bone fracture (39). The volume and size of wear particles are critical factors that affect macrophage activation (40). These biological and physical effects of ultra-high molecular weight polyethylene wear particles are presently the leading cause of long term failure for metal-on-polyethylene hip prostheses (41,42).

Several mechanisms have been proposed to describe wear of ultrahigh molecular weight polyethylene prosthesis components. The wear mechanism of ultrahigh molecular weight polyethylene in hip prostheses has been described by Jasty et al. (43). They found that ultrahigh molecular weight polyethylene surfaces of retrieved implants contained numerous elongated fibrils, which were indicative of large strain deformation. This plastic deformation resulted from strain hardening of the material in the sliding direction and weakening of the material in the transverse direction. Once strain deformation of the surface has occurred, the surface will fragment during the relative motion, and micron- and submicron-sized wear particles will be released. Subsurface cracking, pitting, and delamination caused by oxidative embrittlement and subsurface stresses are responsible for wear of ultra-high molecular weight polyethylene tibial knee inserts.

The wear resistance of ultrahigh molecular weight polyethylene can be improved by reducing the plastic-strain deformation and increasing the oxidization stability (30). The large-strain plastic deformation of ultrahigh molecular weight polyethylene can be diminished by increasing the number of covalent bonds between the long molecular chains of the polymer, which reduces the mobility of the polymer chain and minimizes the creep of the polymer. This process can be achieved by chemical methods (e.g., silane reactions) or, more commonly, by exposing polyethylene to ionizing radiation (46–50). Gamma-ray, e-beam, or X-ray radiation is used to cleave C=C and C=H bonds in polyethylene, which leads to the formation of species with unpaired electrons (free radicals). If the carboncarbon bond is cleaved (chain scission), the polymer molecular weight is reduced. Cross-linking can occur if free radicals from separate chains react with one another, and form an inter-chain covalent bond. If cross-linking occurs as a result of recombination by two radicals cleaved from C=H bonds, it is referred to as an H-type cross-link. If one of the free radicals comes from the cleavage of the C=C bond, it is referred to as a Y-type cross-link. The Y-type cross-linking process can increase the extent of polymer side chain branching (51). The yield of cross-linking processes has been estimated to be three times greater than the yield of chain scission processes for radiation/ultrahigh molecular weight polyethylene interaction. Cross-linking is most significant in amorphous regions of ultrahigh molecular weight polyethylene. An 83% reduction in wear rate has been reported for ultrahigh molecular weight polyethylene surfaces treated with 5 Mrad radiation (38).

However, not all of the free radicals recombine with other free radicals. In crystalline regions, where the spatial separation between free radicals is large, the residual free radicals become trapped. These species are often confined to the crystalline-amorphous interfaces (52,53). Residual free radicals can cause long-term embrittlement through a series of complex cascade reactions. The residual free radicals first react with oxygen, leading to the formation of oxygen-centered radicals. The oxygen-centered radicals can take a hydrogen atom from a nearby chain to form a hydroperoxide species and another free radical on a chain. This additional free radical can repeat the process by generating another hydroperoxide and forming another free radical on a chain. These unstable species may decay into carbonyl species after exposure to high temperatures or after long periods of time, resulting in lower molecular weights and recrystallization. These processes result in increased stiffness, which is highly undesirable for biotribological applications.

Significant research has been done on reducing the concentration of residual free radicals and limiting the brittleness of irradiated ultrahigh molecular weight polyethylene. One cross-linking postprocessing treatment involved annealing the polymer above its melting transition, which allowed the residual free radicals to be removed through recombination reactions. The polymer recrystallized on cooling; however, the covalent bonds obtained during cross-linking were maintained. Unfortunately, the ultrahigh molecular weight polyethylene exhibited slightly lower crystallinity after this treatment. Another treatment involved annealing the cross-linked polymer at a temperature below the peak melting transition. One advantage of this technique is that a greater degree of crystallinity is retained; however, only a partial reduction in the number of residual free radicals is achieved. Other treatments for residual free radicals include irradiation at room temperature followed by annealing at temperatures below the melting transition; irradiation at room temperature with gamma or electron beams followed by melting; or irradiation at high temperatures followed by melting (34).

The physical properties of the ultrahigh molecular weight polyethylene can be significantly altered by cross-linking and annealing treatments. The effect of these treatments is dependent on the cross-linking parameters (e.g., technique, radiation source, dose, temperature during irradiation) and the annealing parameters (e.g., annealing temperature, annealing time). For example, the ultimate elongation ($<45\%$) and the work to failure for ultrahigh molecular weight polyethylene are reduced as the radiation dose level is increased. Large radiation doses also reduce the yield strength ($<30\%$) and the modulus ($<27\%$) of ultrahigh molecular weight polyethylene (34). In addition, toughness decreases as the radiation dose level is increased, since the energy absorption before failure decreases as the chain mobility is reduced (54).

One alternative to the use of ultrahigh molecular weight polyethylene involves the use of so-called metal-on-metal prostheses, which contain two metallic load-bearing components. The primary motivation for use of these implants is friction; metal-on-metal bearings generate less frictional torque during simulated gait than metal-on-polyethylene bearings (55–59). A stainless steel metal-on-metal hip prosthesis design was attempted by Wiles in 1938. Cobalt–chromium alloy/cobalt–chromium alloy prostheses designs were later developed by McKee and Watson-Ferrar (55,56). Although many of these early cobalt–chromium alloy metal-on-metal hip prostheses failed relatively soon after implantation, others have remained in place for >20 years (35). These first-generation metal-on-metal prostheses were displaced by ultrahigh molecular weight polyethylene/cobalt-chromium alloy prostheses in the 1970s for several reasons, including seizure of the cast metal surfaces (56). In the 1980s, second generation cobalt–chromium alloy/cobalt–chromium alloy prostheses were developed, which have again attracted interest from biomaterials researchers and prosthesis manufacturers (58). Earlier problems with seizing have been minimized through the use of wrought alloys, which are prepared using a thermal-mechanical forming process. Scholes et al. recently demonstrated using a hip simulator system that the mode of lubrication in metal-on-metal hip prostheses is strongly influenced by the diameter of the femoral head and diameter clearance (42). In small diameter joints, the wear rate increased as the diameter of the femoral head was increased. These results were attributed to the development of mixed lubrication in this system.

Alumina and zirconia have also been considered for use in orthopedic prostheses. Alumina exhibits very high hardness and elastic modulus values of $1900\ \mathrm{kgf \cdot mm^{-2}}$ (Vickers hardness) and 380 GPa, respectively (60). This material is polished to provide an extremely smooth finish; surface roughness values $<0.005\ \mu\mathrm{m}$ are routinely obtained. In addition, alumina surfaces are hydrophilic and may provide prostheses with full film lubrication (35). Fracture toughness and wear resistance can be improved by lowering grain size, increasing grain uniformity, increasing purity, and lowering porosity.

Alumina prostheses have demonstrated wear rates $<1\ \mathrm{mm \cdot million^{-1}}$ cycles during simulator testing (35). In addition, the *in vivo* wear rate for early alumina-on-alumina hip prostheses was shown to be as low as 1 mm·year (61). However, retrieval studies involving early alumina-on-alumina hip prostheses found high rates of wear on some prostheses. Microseparation of the head and cup was shown to be responsible for this *in vivo* wear behavior (62). Insley et al. examined alumina-on-alumina prostheses with a laboratory simulator, and found that many very small (~40 nm) and some large (100–3000 nm) particles were generated under microseparation conditions (35). Zirconia is harder than alumina, and is used to fabricate smaller components that can withstand higher stresses. Deformation-induced phase transformation has a significant effect on the mechanical properties of zirconia (63). The crystalline phase of a pure zirconium changes from monoclinic to tetragonal during deformation, which is accompanied by volume expansion of ~3–4%. The addition of either yttrium oxide (Y_2O_3) or magnesium oxide (MgO) stabilizes the tetragonal phase at room temperature. However, aging can cause zirconia to return the more stable monoclinic phase, and can limit the lifespan of zirconia prostheses (64,65). In addition, Sato et al. showed that the tetragonal-monoclinic transformation on the surface of zirconia prostheses can be promoted by the presence of water molecules in the environment (66). The resulting volume change can lead to the generation of surface microcracks and an increase in surface roughness. The failure of some zirconia prostheses has been attributed to this microcracking process. Finally, *in vivo* fracture of some zirconia prostheses has been attributed to variations in sintering.

Thermal oxidation of zirconium alloys has also been used to create biocompatible, corrosion- and wear-resistant surfaces for orthopedic prostheses (67). Wrought zirconium-2.65 weight % niobium alloy contains a two-phase microstructure, which consists of elongated hexagonal alpha-zirconium grains that are bordered by cubic beta-zirconium grains. This material is oxidized for up to 8 h in air at temperatures near 620 °C (the eutectoid temperature). The resulting ~5 μm thick monoclinic ZrO_2 surface contains 40 nm wide × 200 nm long grains that are arranged in a brickwork pattern, which is resilient to grain pull-out and lateral fracture. At the interface between the alloy and the surface oxide, regions of unoxidized niobium in beta-zirconium second-phase grains continue from the alloy into the oxide and serve to anchor the oxide to the alloy. The outermost portion of the oxide surface is burnished to create a smooth bearing surface. The oxide surface provides excellent wear behavior against polyethylene components, with reduced wear particle generation and inflammation.

Diamond-like carbon coatings on orthopedic prostheses can exhibit a wide range of elastic modulus and hardness values, which can be correlated with the fraction of sp^3-hybridized atoms within the coating (68–71). Collins et al. developed a relation between sp^3 fraction and Vickers hardness values for hydrogen-free diamond-like carbon coatings. They found that an sp^3 fraction of 10% corresponded to a hardness value of 2000–3000 Hv, an sp^3 fraction of 50% corresponded to a hardness value of 7000-8000 Hv, and an sp^3 fraction of 100% corresponded to a hardness value of 10,000 Hv (72). Schneider et al. found that hydrogen-free and diamond-like carbon films with sp^3 fractions between 0 and 90% provided elastic modulus values between 300 and 800 GPa. In contrast, typical hardness and elastic modulus values for hydrogenated diamond-like carbon films are <17 and <200 GPa, respectively (73).

The coefficients of friction values for diamond-like carbon coatings depend on ambient humidity, topology, and sliding partner (74). The most important parameter determining the coefficient of friction for hydrogenated diamond-like carbon thin films is relative humidity. Friction values for hydrogenated diamond-like carbon films can be as low as 0.01–0.3 in vacuum conditions, but greatly increase under humid conditions due to incomplete formation of the graphitic transfer surface. This variation in coefficient of friction values can be correlated with hydrogen/carbon ratio in the precursor material. As the hydrogen content in the precursor material increases, the friction coefficient demonstrates a greater positive correlation with ambient humidity. For example, hydrogenated diamond-like carbon films produced from hydrogen-diluted methane demonstrate lower friction coefficients under high humidity conditions than other hydrogenated diamond-like carbon films. On the other hand, hydrogen-free diamond-like carbon thin films maintain low friction coefficients (<0.1) under low and high humidity conditions (75,76).

The combination of high hardness and low coefficient of friction values allows diamond-like carbon coatings to provide significant wear protection to a bulk implant material (71). Hirvonen et al. found that the wear resistance of diamond-like carbon coatings is superior to that of silicon carbide, tungsten carbide–cobalt, silicon nitride, or alumina by factors of 40, 60, 230, and 290, respectively (77). Hydrogen-free diamond-like carbon thin films exhibit wear rates of 10^{-9} $mm^3 \cdot N^{-1} \cdot m^{-1}$, these values are ~100 times lower than those for hydrogenated diamond-like carbon thin films (10^{-7} $mm^3 \cdot N^{-1} \cdot m^{-1}$) under similar testing conditions (78). Many diamond-like carbon substrate materials are significantly softer than the diamond-like carbon coatings; high contact pressures can initiate substrate deformation and coating failure. Nitriding processes can harden the substrate surface, reduce subsurface deformation, and extend diamond-like carbon coating lifetimes (79).

The friction and wear properties of diamond-like carbon-coated metal hip prostheses against diamond-like carbon-coated polyethylene cups have been determined using both screening and simulator techniques (80). For example, Tiainen et al. demonstrated extremely low coefficients of friction for prostheses coated with hydrogen-free diamond-like carbon using a pulsed arc discharge method. They demonstrated coefficients of friction for diamond-like carbon/diamond-like carbon and metal–metal pairs of 0.05 and 0.14, respectively. In addition, they found that wear rate in the diamond-like carbon-coated metal/diamond-like carbon-coated metal wear couple was 10^5–10^6 times lower than that observed in conventional metal–polyethylene and metal–metal wear couples. They also observed that wear of polyethylene in the diamond-like carbon-coated metal/ultrahigh molecular weight polyethylene wear couple was 10–600 times lower than that observed in conventional metal/ultrahigh molecular weight polyethylene wear couples. On the other hand, other investigators have found little difference in wear rates between diamond-like carbon-coated prosthesis materials and conventional prosthesis materials. For example, Sheeja et al. found little difference in wear rates between cobalt-chromium–molybdenum alloy/ultrahigh molecular weight polyethylene and multilayered diamond-like carbon-coated cobalt–chromium–molybdenum alloy/ultrahigh molecular weight polyethylene wear couples (81,82). The seemingly contradictory results suggest other factors, such as use of lubricant, may play a significant role in determining wear rates (83–85). For example, physiologic lubricants may not allow graphitic layers to form on the surfaces of the test materials. In addition, diamond-like carbon coatings that contain particulates and pits may increase adhesive wear (86).

Adhesion of diamond-like carbon coatings is dependent on several factors, including film stress, film–substrate chemical bonding, and substrate topology (87,88). Large internal compressive stresses (as high as 10 GPa) are typically observed in diamond-like carbon coatings. These stresses limit maximum diamond-like carbon coating thickness to 0.1–0.2 mm and prevent widespread medical use. Lifshitz et al. attributed these stresses to subplantation (low energy subsurface implantation) of carbon ions during coating formation (89). They suggested that carbon ions with energies between 10 and 1000 eV undergo shallow implantation to depths of 1–10 nm during growth of diamond-like carbon coatings. Carbon species are trapped in subsurface sites due to restricted mobility, leading to the development of very large internal compressive stresses.

Diamond-like carbon can be alloyed with metals in order to reduce internal compressive stresses and promote specific biological responses (90,91). Diamond-like carbon–metal composite coatings retain hardness and wear properties similar to those of unalloyed diamond-like carbon films, and exhibit excellent adhesion to metal alloy substrates (Fig. 5). The metal component can provide additional biological functionality to the implant surface; for example, silver has been shown to possess a wide antimicrobial spectrum against a broad range of Gram-negative bacteria (including *Pseudomonas aeruginosa*),



Figure 5. Wear testing of diamond-like carbon–metal composite coatings using a linear tribometer (screening wear test). (a) Wear track of functionally gradient diamond-like carbon–silver composite film after 10,000 cycles, (b) Wear track of functionally gradient diamond-like carbon–titanium composite film after 10,000 cycles.

Gram-positive bacteria (including methicillin-resistant *Staphylococcus aureus*), fungi, viruses, and yeasts. Films containing both silver and platinum may demonstrate enhanced antimicrobial activity due to formation of a galvanic couple that accelerates silver ion release. Narayan et al. showed that diamond-like carbon–silver–platinum nanocomposite films reduce bacterial colonization rates by 90% compared to uncoated silicon substrates (92).

Corrosion and wear are critical parameters that affect overall success of a biomaterial or a medical device design. The complicated interaction between material-, device-, surgical-, patient-specific parameters has made it difficult to predict clinical behavior of implanted medical devices. In addition, the large variation in measurement techniques for corrosion and wear has led problems in interpreting and comparing the work performed in the biomaterials community. If these issues can be successfully resolved, significant advances in these areas may be achieved in the coming years.

BIBLIOGRAPHY

Cited References

1. Burke DR. The Composition and Function of Body Fluids, 3rd ed. St. Louis: C. V. Mosby; 1980.
2. Lentner C, editor. Geigy Scientific Tables, Vol. 1: Units of Measurement, Body Fluids, Composition of the Body, Nutrition. Basel: CIBA-Geigy; 1981.
3. Lentner C, editor. Geigy Scientific Tables, Vol. 3: Physical Chemistry, Composition of Blood, Hematology, Somatometric Data. Basel: CIBA-Geigy; 1984.
4. ASTM, Annual Book of ASTM Standards. West Conshohocken (PA): ASTM. International; 1977.
5. Pilliar RM. Metals and irthopaedic implants — past successes, present limitations, future challenges. Shrivastava S, editor. Proceedings of the Materials & Processes for Medical Devices Conference. Materials Park (OH): ASM International; 2004.
6. Hoar TP, Mears DC. Corrosion-resistant alloys in chloride solutions: materials for surgical implants. Proc R Soc London 1966;294:486–510.
7. Sury P, Semlitsch M. Corrosion behavior of cast and forged cobalt-based alloys for double-alloy joint endoprostheses. J Biomed Mater Res 1978;12:723–741.
8. Steinemann S. Corrosion of surgical implants – *in vivo* and *in vitro* tests. In: Winder GD, editor. Evaluation of Biomaterials. Chichester: John Wiley & Sons Inc.; 1980.
9. Cahoon JR, Bandyopadhya R, Tennese L. The concept of protection potential applied to the corrosion of metallic orthopedic implants. J Biomed Mater Res 1975;9:259–264.
10. Bandy CR. Effects of composition on the electrochemical behavior of austenitic stainless steel in Ringer's solution. Corrosion (Houston) 1977;33:204–208.
11. Scales JT, Winter GD, Shirley HT. Corrosion of orthopaedic implants. J Bone Joint Surg 1959;41B:810–820.
12. Merritt K, Brown SA. Release of hexavalent chromium from corrosion of stainless steel and cobalt-chromium alloys. J Biomed Mater Res 1995;29:627–633.
13. McKellop HA, Sarmiento A, Brien W, Park SH. Interface corrosion of a modular head total hip prosthesis. J Arthroplasty 1992;7:291–294.
14. Brown SA, et al. Fretting corrosion accelerates crevice corrosion of modular hip tapers. J Appl Biomater 1995;6:19–26.
15. Kawale JS, Brown SA, Payer JH, Merritt K. Mixed-metal fretting corrosion of Ti6Al4V and wrought cobalt alloy. J Biomed Mater Res 1995;29:867–873.
16. Metikos-Hukovic M, Kwokal A, Piljac J. The influence of niobium and vanadium on passivity of titanium-based implants in physiological solution. Biomaterials 2003;24: 3765–3775.
17. Cutright DE, et al. Tissue reaction to nitinol wire alloy. Oral Surg Oral Med Oral Pathol 1973;35:578–584.
18. Kapanen A, Ryhänen J, Danilov A, Tuukkanen J. Effect of nickel-titanium shape memory metal alloy on bone formation. Biomaterials 2001;22:2475–2480.
19. Ryhänen J, et al. Bone healing and mineralization, implant corrosion, and trace metals after nickel-titanium shape memory metal intramedullary fixation. J Biomed Mater Res 1999;47:472–480.
20. Villermaux F, et al. Corrosion resistance improvement of NiTi osteosynthesis staples by plasma polymerized tetrafluorethylene coating. Biomed Mater Eng 1996;6:241–254.
21. Rondelli G, Vincentini B. Localized corrosion behavior in human body fluids of commercial NiTi orthodontic wires. Biomaterials 1999;20:785–792.
22. Carroll W, Kelly M, Brien B. Corrosion behavior of Nitinol wires in body fluid environment. Int Conf Shape Memory Superelastic Technol 1999; 240–249.
23. Montero-Ocampo C, Lopez H, Salinas RA. Effect of compressive straining on corrosion resistance of a shape memory Ni-Ti alloy in Ringer's solution. J Biomed Mater Res 1996;32: 583–591.
24. Shabalovskaya SA. Surface, corrosion and biocompatibility aspects of Nitinol as an implant material. Bio-Med Mater Eng 2002;12:69–109.
25. Niinomi M. Recent research and development in titanium alloys for biomedical applications and healthcare goods. Sci Technol Adv Mat 2003;4:445–454.
26. Senda T, Yasuda E, Kaji M, Bradt RC. Effect of Grain Size on the Sliding Wear and Friction of Alumina at Elevated Temperatures. J Am Ceram Soc 1999;82:1505–1511.
27. Dogan CP, Hawk JA. Role of composition and microstructure in the abrasive wear of high-alumina ceramics. Wear 1999; 225:1050–1058.
28. Rodríguez J, et al. Sliding wear of alumina/silicon carbide nanocomposites. J Am Ceram Soc 1999;55:2252–2306.
29. Webster TJ, Siegel RW, Bizios R. Osteoblast adhesion on nanophase ceramics. Biomaterials 1999;20:1221–1227.
30. Morsi K, Keshavan H, Bal S. Hot pressing of graded ultrafine-grained alumina bioceramics. Mater Sci Eng A 2004;386:384–389.
31. Kingery WD. Introduction to Ceramics. New York: John Wiley & Sons Inc.; 1976.
32. Tiainen VM. Amorphous Carbon as a Bio-mechanical coating-mechanical properties and biological applications. Diamond Related Mater 2001;10:153–160.
33. Hutchings IM. Biotribology-A Personal View. In: Hutchings IM, editor. Friction, Lubrication and Wear of Artificial Joints. Bury St. Edmunds (UK): Professional Engineering Publishing Ltd.; 2003.
34. Wright TM, Goodman SB, editors. Implant Wear in Total Joint Replacement: Clinical and Biologic Issues, Material and Design Considerations. Rosemont (IL): American Academy of Orthopaedic Surgeons; 2001.
35. Hutchings IM, editor. Friction, Lubrication and Wear of Artificial Joints. Bury St. Edmunds (UK): Professional Engineering Publishing Ltd; 2003.
36. Schmalzreid TP, Callaghn JJ. Current concepts review: Wear in total hip and knee replacement. J Bone Joint Surg Am 1999;81:115–136.

37. Clarke IC, McKellop HA. Wear Testing. In: von Recum AF, editor. Handbook of biomaterials evaluation: scientific, technical, and clinical testing of implant materials. New York: Macmillan; 1986.
38. McKellop H, Shen FW, DiMaio W, Lancaster JG. Wear of gamma-crosslinked polyethylene acetabular cups against roughened femoral balls. Clin Orthop 1999;369:73–82.
39. Unsworth A, Dowson D, Wright V. Some new evidence on human joint lubrication. Ann Rheum Dis 1975;34:277–285.
40. Green TR, et al. Effect of size and dose on bone resorption activity of macrophages by *in vitro* clinically relevant ultra high molecular weight polyethylene particles. J Biomed Mater Res 2000;B53:490–497.
41. Ingham E, Fisher J. Biological reactions to wear debris in total joint replacement. Proc Inst Mech Eng H 2000;214:21–37.
42. Scholes C, Unsworth A. Comparison of friction and lubrication of different hip prostheses. Proc Inst Mech Eng H 2000;214:49–57.
43. Jasty MJ, et al. Wear of polyethyene acetabular components in total hip arthroplasty: an analysis of 128 components retrieved at autopsy or revision operation. J Bone Joint Surg Am 1977;79:349–358.
44. Charnley JC. Arthroplasty of the hip: a new operation. Lancet 1961;280:1129–1132.
45. Charnley JC. Tissue reaction to polytetrafluorethylene. Lancet 1963;285:1379.
46. Collier JP, et al. Overview of polyethylene as a bearing material: comparison of sterilization methods. Clin Orthop Rel Res 1996;333:76–86.
47. Wang A, Sun DC, Stark C, Dumbleton JH. Wear Mechanisms of UHMWPE in total joint replacements. Wear 1998;181–183:241–249.
48. Collier JP, et al. Results of implant retrieval from postmortem specimens in patients with well-function, long term total hip replacement. Clin Orthop 1992;274:97–112.
49. Cameron HU. Tibial component wear in total knee replacement. Clin Orthop 1994;309:29–32.
50. Atkinson JR, Cicek RZ. Silane crosslinked polyethylene for prosthetic applications: Part II. Creep and wear behavior and a preliminary molding test. Biomaterials 1984; 5:326–335.
51. Muratoglu OK, et al. Larger diameter femoral heads used in conjunciton with a highly cross-linked ultra high molecular weight polyethylene: A New Concept. J Arthroplasty 2001;16: 24–30.
52. Pearson RW. Mechanism of the radiation crosslinking of polyethylene. J Polym Sci 1957;25:189–200.
53. Zhu QR, Horii F, Kitamaru R, Yamaoka H. C-13-NMR study of cross-linking and long-chain branching in linear polyethylene induced by Co-60 gamma-ray irradiation at different temperatures. J Polym Sci, Part A: Polym Chem 1990;28: 2741–2751.
54. Premnath V, Harris WH, Jasty M, Merrill EW. Gamma sterilization of UHMWPE articular implants: an analysis of the oxidation problem. Biomaterials 1996;17:1741–1753.
55. Steinberg DR, Steinberg ME. The early history of arthroplasty in the United States. Clin Orthop Relat Res 2000;374:55–89.
56. McKee GK, Watson-Farrar, J. Replacement of arthritic hip by the McKee-Farrar prostheses. J Bone Joint Surg 1966;48B: 245–259.
57. Wimmer MA, et al. The acting wear mechanisms on metal-on-metal hip joint bearings: in vitro results. Wear 2001; 250:129–139.
58. Dorr LD, et al. Total hip arthroplasty with use of the metasul metal-on-metal articulation: 4–7-year results. J Bone Joint Surg Am 2000;82:789–798.
59. Poggie RA, Afflitto R, St John K. The wear performance of precision Co–Cr–Mo alloy metal-on-metal hip bearings. Proc Conf Trans 12th Ann Int Symp Technol Arthroplasty 1999;11: 1–2.
60. Boutin P, et al. The use of dense alumina- alumina ceramic combination in total hip replacement. M J Biomed Mater Res 1988;22:1203–1232.
61. Willmann G. Development in medical-grade alumina during the past two decades. J Mater Process Technol 1996;56:168–176.
62. Nevelos J, et al. Microseparation of the centers of alumina-alumna artificial hip joints during simulator testing produces clinically relevant wear and patterns. J Arthroplasty 2000;15: 793–795.
63. Christel P, et al. Mechanical properties and short-term In vivo evaluation of yttrium-oxide-partially-stabilized zirconia. J Biomed Mater Res 1989;23:45–61.
64. Chevalier J, et al. Critical effect of cubic phase on aging in 3 mol% yttria-stabilized zirconia ceramics for hip replacement prosthesis. Biomaterials 2004;25:5539–5545.
65. Gremillard L, et al. Modeling the aging kinetics of zirconia ceramics. J Eur Ceram Soc 2004;24:3483–3489.
66. Sato T, Ohtaki S, Endo T, Shimada M. Science and technology of zirconia. Advances in Ceramics. Westerville (OH): American Ceramic Society; 1988.
67. Hobbs LW, et al. Oxidation microstructures and interfaces in the oxidized zirconium knee. Int J Appl Ceram Technol 2005;2:221–246.
68. Enke K, Dimigen H, Hubsch H. Frictional properties of diamondlike carbon layers. Appl Phys Lett 1980;36:291–292.
69. Pharr GM, et al. Hardness, elastic modulus, and structure of very hard carbon films produced by cathodic-arc deposition with substrate pulse-biasing. Appl Phys Lett 1996;68:779–781.
70. Ronkainen H, Varjus S, Koskinen J, Holmberg K. Differentiating the tribological performance of hydrogenated and hydrogen-free DLC coatings. Wear 2001;249:260–266.
71. Holmberg K, Mathews A. Coatings tribology: a concept, critical aspects, and future directions. Thin Solid Films 1994;253:173–178.
72. Collins CB, et al. Noncrystalline films with the chemistry, bonding, and properties of diamond. J Vac Sci Technol B 1993;11:1936–1941.
73. Schneider D, Schwarz T, Scheibe HJ, Panzner M. Nondestructive evaluation of diamond and diamond-like carbon films by laser induced surface acoustic waves. Thin Solid Films 1997;295:107–116.
74. Erdemir A, Bindal C, Pagan J, Wilbur P. Characterization of Transfer layers on Surfaces Sliding Against Diamond-like Hydrocarbon Films in Dry Nitrogen. Surf Coatings Technol 1995;76–77:559–563.
75. Liu Y, Erdemir A, Meletis EI. An investigation of the relationship between graphitization and frictional behavior of DLC coatings. Surface Coatings Technol 1996;86:564–568.
76. Oguri K, Arai T. Friction mechanisms of Diamond-like carbon with silicon coatings formed by plasma-assisted chemical vapor-deposition. J Mater Res 1992;7:1313–1316.
77. Hirvonen JP, Koskinen J, Lappalainen R, Anttila A. Preparation and properties of high density hydrogen free hard carbon films with direct ion beam or arc discharge deposition. Mater Sci Forum 1990;52:197.
78. Voevodin AA, Donley MS, Zabinski JS, Bultman JE. Mechanical and tribological properties of diamond-like carbon coatings prepared by pulsed laser deposition. Surface Coatings Technol 1995;77:534–539.
79. Voevodin AA, Phelps AW, Zabinski JS, Donley MS. Friction induced phase transformation of pulsed laser deposited diamondlike carbon. Diamond Related Mater 1996;5:1264–1269.

80. Santavirta S, Lappalainen R, Heinonen H, Anttila A. Some relevant issues related to the use of amorphous diamond coatings for medical applications. Diamond Related Mater 1998;7:482–485.
81. Sheeja D, et al. Mechanical and tribological characterization of diamond-like carbon coatings on orthopedic materials. Diamond Related Mater 2001;10:1043–1048.
82. Sheeja D, Tay BK, Lau SP, Nung LN. Tribological characterization of diamond-like carbon coatings on Co-Cr-Mo alloy for orthopaedic applications. Surface Coatings Technol 2001;146: 410–416.
83. Ahlroos T, Saikko V. Wear of prosthetic joint materials in various lubricants. Wear 1997;211:113–119.
84. Saikko V, Ahlroos T. Phospholipids as boundary lubricants in wear tests of prosthetic joint materials. Wear 1997;207:86–91.
85. Affatato S, Frigo M, Toni A. An *in vitro* investigation of diamond-like carbon as a femoral head coating. J Biomed Mater Res 2000;53:221–226.
86. Dong H, Shi W, Bell T. Potential of improving tribological performance of UHMWPE by engineering the Ti6Al4V counterfaces. Wear 1999;229:146–153.
87. Morshed MM, McNamara BP, Cameron DC, Hashmi MSJ. Effect of surface treatment on the adhesion of DLC film on 316L stainless steel. Surface Coatings Technol 2003;163:541–545.
88. Schwan J, et al. Stress-induced formation of high-density amorphous carbon thin films. J Appl Phys 1997;82:6024–6030.
89. Lifshitz Y, et al. Growth mechanisms of DLC films from C+ ions- experimental studies. Diamond Related Mater 1995;4: 318–323.
90. Narayan RJ, Scholvin D. Nanostructured carbon-metal composite films. J Vac Sci Technol B 2005;23:1041–1046.
91. Narayan RJ. Pulsed laser deposition of functionally gradient diamondlike carbon-metal nanocomposites. Diamond Related Mater 2005;14(8):1319–1330.
92. Narayan RJ, et al. Antimicrobial properties of diamond-like carbon-silver-platinum nanocomposite thin films. J Mater Eng Perform 2005;14:435–440.

See also BIOMATERIALS, TESTING AND STRUCTURAL PROPERTIES OF; HEART VALVE PROSTHESES; HIP JOINTS, ARTIFICIAL.

BIOMATERIALS FOR DENTISTRY

STEVE ARMSTRONG
University of Iowa

INTRODUCTION

Gold has been used for dental purposes for at least 2500 years; the fabrication of gold crowns and bridgework flourished in Etruria and Rome as early as 700–500 BC. Gold leaf came into use during the fifteenth century for the restoration of carious teeth. Restorative materials and techniques continued to develop through the nineteenth century including the use of waxes, fused porcelain, "silver paste" amalgam, cements, vulcanite, the angle handpiece, and a gold inlay casting machine. A rapid development in materials and instrumentation has occurred since the 1950s, to include the high speed handpiece, steel and diamond cutting instruments, adhesive techniques to metal, ceramics, enamel and dentin, resin-based composites, glass ionomers, base-metal alloys for partial dentures, metal-ceramic systems, high-strength all ceramic structures, and titanium alloys for dental implants. This increasing complexity and body of knowledge has lead to the establishment of uniform material standards and the recognition of the science of dental materials as a distinct and essential branch of dentistry.

Biomaterials are used in the oral cavity either to restore function, comfort, or aesthetics caused by developmental disorders, disease, or trauma. More elective procedures are being requested and performed purely for aesthetic purposes as the incidence of caries has dropped in certain population groups and as patients have become more aware of various restorative or cosmetic options. However, the replacement of diseased tooth structure or missing teeth accounts for the bulk of work in restorative dentistry. The instruments and materials used in the surgical aspects of oral, maxillofacial and periodontal surgery have much in common with medicine. This article will focus on those commonly used materials in the restoration of individual teeth or the replacement of missing teeth.

Restorative materials include noble and base metal alloys, resin-based composites (RBCs), glass ionomers, ceramics, acrylics, and amalgam alloys. Techniques to apply these materials include both direct and indirect approaches. Materials or "fillings" can be directly placed in a prepared cavity by the use of adhesives and/or retentive-type preparations. Full or partial coverage crowns, bridges, and dentures are fabricated indirectly by dental laboratories or computer aided milling machines and then attached or cemented into the mouth for the coverage of missing or weakened tooth structure or the replacement of missing teeth. Various forms of ceramic or metallic implants can be placed into the upper or lower jaw bones to serve as tooth root substitutes upon which a prosthesis is attached to replace missing teeth. Auxiliary materials, such as waxes, gypsum, and impression materials are also utilized during clinical and laboratory steps but will not be covered in this article.

DIRECTLY PLACED RESTORATIVE MATERIALS: 'FILLINGS'

Amalgam

Dental amalgam has been very successfully used in dentistry for 150 years and is one of the most technique insensitive dental restorative materials available. Dental amalgams are inexpensive and have demonstrated a relatively long service life. The disadvantages of amalgam are the silver color and the presence of mercury. The presence of mercury requires regulatory control of wastewater effluent and has raised unsubstantiated health concerns regarding mercury toxicity to the individual patient.

Dental amalgam is a mixture of mercury and a solid metal alloy of silver, tin, copper, and sometimes zinc, palladium, indium, and selenium. Once the mercury and alloy is mixed, the plastic mass is condensed into the prepared cavity and carved to required form before hardening. The alloy particles are microspheres of various sizes, irregular lathe-cut particles or mixtures of the two. "High copper" alloys (13–30%) have essentially replaced the low copper alloys of the past. These high copper alloys, along with the addition of zinc for manufacturing procedures, have improved early clinical strength, lowered creep, and improved corrosion resistance. The mixing of mercury and the alloy is referred to as trituration or amalgamation. A surface reaction occurs between the alloy and liquid mercury that binds the unreacted particles together by a surrounding matrix of reaction products. Increasing the copper content eliminates most of the weakest and most corrosive phase ($Sn_{7-8}Hg$) from the setting reaction.

After the carious lesion is removed, the plastic dental amalgam is condensed into the prepared cavity before hardening and subsequently retained by the mechanical resistance and retention form of the surgically prepared cavity. An adhesive liner is not required. The material slowly corrodes and the corrosion products "self-seal" the margin between tooth and amalgam, thereby protecting the tooth from leakage of oral fluids and bacteria and their byproducts. Dental amalgam is brittle and undergoes creep at mouth temperature, which can lead to marginal or bulk fracture and clinical failure. However, if the cavity is well designed and the amalgam placed with technical competence, many years of service should be expected. A vast number of studies have shown the safety and efficacy of dental amalgam. When a dentist is faced with a patient's request to remove amalgam fillings due to a claimed medical malady, the dentist is professionally obligated to explain that the possibility of their medical condition(s) being related to the presence of dental amalgam fillings is extremely remote. These patients typically face a complex problem with biological, psychological, and social components unrelated to mercury intake.

Resin Composites

Modern day resin-based composites placed with dental adhesives have replaced the silicates and acrylic resins of the past and are now widely used throughout dentistry. In addition to the treatment of decay and trauma, RBCs are used in aesthetic or cosmetic dentistry procedures due to their versatility and conservative nature. Discolored, misshapen, or misaligned dentition can be aesthetically treated with cosmetic "bonding". The RBCs are composed of four main components: (*1*) a continuous organic polymer matrix, (*2*) a dispersion of inorganic filler particles, (*3*) silane coupling agents to bind the filler particles with the polymer matrix, and (*4*) an initiator–accelerator system. They also contain various pigments for matching tooth shades and ultraviolet (UV) absorbers to minimize oxidative color changes. The two most common oligomers are the dimethacrylates 2,2- bis[4(2-hydroxy-3-metharcyloyloxy-propyloxy)-phenyl] (bis-GMA) and urethane dimethacrylate (UDMA). Diluents such as triethylene glycol dimethacrylate (TEGDMA) are added to reduce the viscosity for the addition of filler and to obtain clinically acceptable handling properties. The inorganic filler particles can be of borosilicate, lithium aluminum silicate, barium aluminum silicate, strontium or zinc glasses, quartz, or colloidal silica. The combination of relatively larger glass or quartz particles and a significant addition of colloidal silica are referred to as a "hybrid". A useful classification method is by filler particle size (Table 1) with minifill hybrids and microfills being the most popular types. Recently, using a proprietary process, manufacturers have been able to produce a smaller average silica particle size (0.02 μm) as compared with traditional microfills (0.04 μm). Marketed as "nanofills", these smaller silica particles are produced in a nondrying method thereby avoiding agglomeration due to physical forces and thusly enabling a higher degree of filler loading. The microfill RBCs polish to the most enamel-like surface, but lack the strength of the hybrids due to the lower filler volume. Newer formulations of minifill hybrids can be used as "universal" RBCs possessing both the strength for posterior chewing forces and acceptable surface finish for use in aesthetic anterior regions. Clinical studies showed that the long-term wear resistance of RBC restorations placed on posterior teeth is still inferior to the dental amalgam restorations.

Table 1. Classification of Resin-Based Composites by Filler Particle Size

Class	Particle Size, μm	Filler Loading, vol%
Macrofill	>10	50–70
Midifill	1–10	50–70
Minifill	0.1–1	50–70
Microfill	0.01–0.1	20–50

Polymerization occurs through either a self-cured free radical initiation when a peroxide–amine system is mixed or through light-activated free radical initiation when a diketone–amine system is exposed to blue light. The photoactivator, most commonly camphoroquinone, is added in small amounts, which forms a free radical when exposed to 467-nm blue light. Dual-cure varieties of RBCs are available as well. Halogen light-curing units are most commonly used, but several other light curing units are currently being marketed to include: plasma-arc, laser and light-emitting diodes. To insure proper polymerization care must be taken to match the unit's spectral emission and the RBCs spectral requirements. One aspect that all RBCs currently share is 2–4% volumetric shrinkage of the continuous polymeric network upon polymerization. Shrinkage induces residual stress that can disrupt the adhesive bond between the RBC and the tooth structure, damage enamel or the RBC. Incremental placement of light-cured RBCs can help to reduce the net effect of this shrinkage stress. Manufacturer's are currently working to develop no- or low shrinkage RBCs; several approaches are noted: (*1*) addition of ring-opening monomers that expand upon polymerization (spiroorthocarbonates, oxiranes, vinylcyclopropanes), (*2*) low shrinkage cyclopolymerizable di- and multifunctional oligomers synthesized through the reaction of acrylates and formaldehyde, and (*3*) the addition of strain-absorbing polybutadiene rubber polymer adsorbed onto the fumed silica.

Variations in filler loading, viscosity, and polymerization initiating systems allow RBCs to be used in a wide variety of clinical situations, to include: sealants, cements, crown core buildups, so-called flowables and packables, provisional restorations, and in a variety of laboratory processed RBCs for adhesive cementation as inlays, onlays, crowns and veneers. Several manufacturer's have promoted fiber reinforced RBCs for use as bridges, as well, but these lack convincing clinical data for their recommended usage.

Glass Ionomers

Smith (1968) developed glass ionomer cements (GIC) by combining the polyacrylic acid from polycarboxylate cement, which is strongly adhesive to tooth structure, and the aluminosilicate glass from the fluoride-containing silicate cements. The GICs form a true chemical bond to the tooth mineral (hydroxyapatite) by ionic bonding between calcium and carboxylic ions and act as chemotherapeutic agents in the treatment and prevention of dental caries through the release of fluoride.

The GIC are composed of a basic ion-leachable aluminosilicate glass powders that, upon exposure to water-soluble homopolymer or copolymers of alkenoic acids, form a matrix of continuous polysalts (polyalkenoates) surrounded by partially solubilized glass filler particles. The clinical placement technique must account for the relatively slow-setting reaction and moisture sensitivity. Fluoride easily passes in and out of the matrix without any degradative effects due to the substitution of carboxyl ions for fluoride within the salt matrix. Fluoride "recharging" has been clearly demonstrated in vitro to prevent the demineralization of tooth structure at the margins adjacent to the GIC under an artificial caries challenge. In vivo evidence is not as clearly demonstrated, but when evaluating clinical data from high caries risk cohort populations the anticariogenic effect of GIC is elucidated.

Since their development GIC has been modified in a number of different ways to improve their clinical handling properties and durability. A significant development was the addition of water soluble monomers, for example, HEMA, and the grafting of methacrylate side groups on the polyacid polymer. By the addition of visible light initiator–accelerator systems these resin-modified glass ionomers (RMGI) can be command set with a light curing unit while also self-curing through the acid–base reaction. These improvements to the conventional GIC and RMGI have made these materials widely used as restorative materials. The self-adhesive and self-cure properties of GIC, along with improvements in strength have allowed these materials to be used in nontraditional field situations without the luxuries of electricity or modern equipment. Auxiliary personnel have been trained to remove caries with sharp hand instruments with the cavity then filled with a heavier filled GIC. This treatment has aided thousands through a technique termed Atraumatic Restorative Treatment or "ART". These materials are also used as cements and liners.

Adhesives, Cements, and Liners

Adhesive dentistry has become increasingly important as the use of dental amalgam and direct compacted gold foil and cemented gold restorations has declined. Unlike dental amalgam, RBCs require an adhesive liner for placement and retention. A durable bond of RBCs to enamel can be accomplished by first cleaning and demineralizing the surface with a 30–40% phosphoric acid, followed by a polymerizable methacrylate monomer [bis(GMA), UDMA, TEGDMA], which diffuses into the porosities created by the acid etching. However, bonding to dentin is a much greater challenge due to the compositional differences in dentin relative to enamel and its extremely variable clinical presentation. Dentin contains less inorganic components and more organic components and water than enamel. Dentin is made permeable by tubules that travel from the dental pulp through the dentin to the coronal enamel.

Similar to enamel, the dentin is treated with an acid that removes any smear layer and exposes the collagen fibers by demineralizing the surface. An adhesive primer containing a hydrophilic solvent (water, acetone, ethanol, or HEMA) and an amphipathic monomer (hydrophilic–hydrophobic functionalities) then penetrates the exposed collagen network. After the solvent is evaporated from the primed surface, an adhesive monomer is applied that attaches to the hydrophobic functionality of the primer to create a wetted surface for subsequent copolymerization with the RBC. This bonding process is also approached with so-called "self-etch" adhesives. The initial acid application is eliminated and a water-soluble acidic polymer is included in the primer to simultaneously demineralize the tooth surface while penetrating with the adhesive monomers and oligomers. Regardless of the approach, the adhesive liner penetrates into the exposed collagen network and also partially into the dentinal tubules. The interdiffusion of the synthetic adhesive polymer within the collagen network forms a micromechanical bond and is commonly referred to as a hybrid layer (Fig. 1). In the last 20 years,



Figure 1. Scanning electron micrograph (SEM) image of a total-etch three-step dental adhesive system applied to dentin. A = filled adhesive resin (ceramic filler particles visible within resin matrix), HL = hybrid layer (interdiffusion zone of adhesive polymers and collagen network), T = dentinal tubules, D = laboratory demineralized dentin. Original magnification = 2000X, black bar=10 μm. (Photomicrograph courtesy of Marcos Vargas, University of Iowa College of Dentistry.)

dentin bonding has improved the clinical success of adhesively placed restorations, but difficulties remain. Completely penetrating the exposed collagen matrix with the adhesive monomers can be hindered by the presence of excess solvent, dentinal fluids, or by physical blockage of the interpenetrating microchannels between collagen fibrils. Even if the adhesive fully wets the dentin surface, suboptimal polymerization may reduce bonding effectiveness. This union of restorative material to enamel and dentin is critical not only for retaining restorations in place, but also for sealing the margin from the passage of bacterial fluids, molecules, or ions. Leakage between the interface of the dental restoration and the wall of the cavity preparation has been associated with marginal discoloration, secondary caries, and pulpal pathology.

Adhesive liners or bonding agents are also used in conjunction with resin-based composite cements when adhesively cementing crowns or other fixed appliances into or onto prepared teeth. The ceramic elements or oxides of the internal surface of dental porcelain–ceramic, metals, and resin-based composite restorative materials are mechanically or chemically roughened before applying a silane coupling agent. The silane bonds to the ceramic surface with both covalent and hydrogen-bonding protecting from hydrolytic degradation while making the surface hydrophobic and organophilic for resin cement wettability and copolymerization. Self-adhesive cements include the glass ionomer and polycarboxylate cements. Zinc phosphate and zinc oxide eugenol are nonadhesive cements that act as mortar or a luting agent.

Additional uses of the above mentioned cements include (*1*) cavity liners to achieve a physical barrier to bacteria and their products and/or to provide a therapeutic effect, such as fluoride release from glass ionomer or pulpal obtundent with zinc oxide eugenol, (*2*) cavity bases to block out undercuts in cavity preparations for indirect restorations or for insulating the pulp from thermal changes, and (*3*) temporary or provisional restorations. The beneficial effects of adhesion to tooth structure and fluoride release obtained from adhesive liners and glass ionomer materials are rapidly replacing the traditional liner, base, and cement materials, that is, zinc phosphate, polycarboxylate, and zinc oxide eugenol.

PROSTHETIC RESTORATIVE MATERIALS: CROWNS, BRIDGES, DENTURES

Metals and Alloys

Noble and base metal alloys are used for (*1*) crowns and bridges with fused porcelain in esthetic areas, (*2*) inlays, onlays, crowns, and bridges without porcelain veneering in the posterior or nonaesthetic regions of the mouth, and (*3*) partial and complete removable denture bases. Base metals commonly used in dental alloys include, nickel, chromium, copper, zinc, gallium, silver, indium, and tin. Silver, a "precious" metal, is not considered a noble metal in dentistry due to its corrosion in the oral cavity. The noble metals utilized in dentistry are gold, platinum, palladium, iridium, rhodium, and ruthenium. Cold-worked or wrought noble and base alloys can be cast with or "soldered" (brazed) to cast structures as attachments or clasps to removable partial dentures. High purity gold, being soft and malleable, can be cohesively adapted in the form of gold foil into small cavity preparations by careful condensation techniques. This process develops adequate hardness and physical properties through work hardening, resulting in a clinically successful, long-lasting restoration. However, the compacted gold foil restoration is becoming increasingly uncommon due to the success of adhesively bonded tooth colored restorations and the skill and time required to properly place gold foil. Almost all fixed-dental prostheses contained a minimum of 75% gold before the dramatic increase in the price of gold after the United States separated gold from monetary standards in 1969. The increase in gold prices, and rise in palladium prices three decades later, has lead to an increased use of alternative alloys containing base metals.

The lost wax technique became common in dentistry after W.H. Taggart introduced his casting machine in 1907. A wax pattern of the desired restoration is fabricated and then invested in a ceramic material (casting investment), which is subsequently heated to burn out the wax pattern, that is "lost wax". A molten metal alloy is then cast into the resultant space previously occupied by the wax. The restoration is recovered, finished, and polished before cementing or delivering to the patient. The investment must be able to expand enough upon setting and heating to compensate for the wax and metal shrinkage if a precise fit is to be obtained.

Alloys should (*1*) produce no toxic, carcinogenic, or allergic reactions; (*2*) resist corrosion and physical changes in the oral environment; (*3*) possess physical properties, that is, strength, fusing temperature, thermal conductivity, and coefficient of thermal expansion, appropriate for the desired application; (*4*) be able to be fabricated in a technically feasible manner; and (*5*) be available and relatively inexpensive. The alloys used for metal-ceramic or commonly termed porcelain-fused-to-metal (PFM) restorations must possess a fusion temperature range that is substantially higher ($>100\,^{\circ}\mathrm{C}$) than the ceramic firing temperature, have sufficient creep resistance at that temperature, and have the ability to form a good bond between its oxide surface and the ceramic veneer.

Wrought stainless steel alloys are used in orthodontic brackets and wires, endodontic instruments, prefabricated temporary crowns and space maintainers. In addition, wrought cobalt–chromium–nickel, nickel–titanium, copper–nickel–titanium, and beta-titanium alloys are also used as orthodontic wires. Nickel–titanium and copper–nickel–titanium orthodontic wires have a unique superelastic (pseuedoelastic) property that delivers a constant low-level force over an extended range of deformation. Nickel–titanium and copper–nickel–titanium alloys are also the shape memory alloy (SMA), that is, they can be deformed plastically below its transition temperature range (TTR), then after heating through and above the TTR, they will return to their original desired shape due to a crystallographic transformation from martensitic phase into austenitic phase. Titanium and titanium alloys, especially due to their thin stable oxide layers, are very important endosseous dental implant materials and, with the recent refinement in casting techniques, can be used for crowns, partial dentures and complete denture bases.

Ceramics

The first porcelain was developed in the T'ang Dynasty from 618 to 906 AD and the first suggested use of porcelain for dentistry was by Pierre Fauchard in France after the porcelain formula was brought from China by a Jesuit priest. Several developments followed but the current approaches to ceramic-metal crowns and bridges occurred from the 1950s–1960s. High-fusing alloys combined with the development of low-fusing thermally compatible leucitic porcelains permitted the fabrication of ceramic-metal restorations. High expansion leucite was mixed with feldspar glass during manufacturing to refine the coefficient of thermal expansion (α) creating a successful junction between dental porcelain and metal. The combination of which must be thermally compatible for fabrication and so that the veneering materials surface is left in a residual state of compression. The α of the veneering material is generally $\sim 0.5–1.0 \times 10^{-6}\,^{\circ}C^{-1}$ lower than the core material so that upon cooling the inner core will contract more resulting in a residual compressive state resisting crack formation and propagation of the relatively brittle veneering material.

Minor refinements have continued with metal–ceramic systems, but more recently significant advances have occurred in the area of "all-ceramic" systems, in which the metal is replaced with a ceramic core upon which veneering porcelain is fused. This eliminates the masking of the metal with opaquing agents and greatly simplifies the aesthetic technical procedures by the dental technician. However, more tooth structure may need to be removed in preparation for the construction of these all-ceramic restorations and their brittle nature does not yet permit their function in long-span bridges.

Ceramic systems can be classified by their fusion temperature, clinical usage, processing methods, or crystalline phase. Table 2 lists some crystalline types used for the three major applications of ceramics in dentistry: (*1*) metal–ceramic crowns and fixed-partial dentures (bridges); (*2*) all-ceramic crowns, inlays, onlays, veneers, and shortspan bridges; and (*3*) denture teeth.

Table 2. Classification of Dental Ceramic Materials

	Fabrication	Crystalline (dispersed) Phase
Ceramic–Metal (PFM)	Sintered	Leucite ($KAlSi_2O_6$)
All-Ceramic	Machined	Alumina (Al_2O_3)
		Feldspar ($KAlSi_3O_8$)
		Mica ($KMg_{2.5},Si_4O_{10}F_2$)
	Slip-cast	Alumina (Al_2O_3)
		Spinel ($MgAl_2O_4$)
		Zirconia (ZrO_2)
	Heat-pressed	Leucite ($KAlSi_2O_6$)
		Lithium disilicate ($Li_2Si_2O_5$)
	Sintered	Alumina (Al_2O_3)
		Leucite ($KAlSi_2O_6$)
Denture Teeth		Feldspar ($KAlSi_3O_8$)

[a] Adapted from Ref. (1) p. 553.

"Porcelains" are composed of kaolin (clay), feldspar, and quartz (flint), while the dental porcelains being quite similar, are fabricated from silica (SiO_2), soda (NaO_2), potash (K_2O), alumina (Al_2O_3), with the addition of pigments, opacifiers and fluxes. Naturally occurring minerals such as feldspar ($K_2O\ Al_2O_3\ 6SiO_2$), quartz, and nepheline syenite have been utilized to provide these constituents. The use of feldspar has lead to the term feldspathic porcelain, however, feldspar is not necessarily present in the final processed porcelain, nor is it essential to form leucite, the major crystalline phase of the porcelain. Like all dental ceramics, dental porcelain is composed of a glassy (vitreous) matrix phase surrounding a dispersed crystalline phase. The glassy matrix, composing 75–85% of the porcelain, is formed by heating the raw materials into a glassy state then quenching. This pyrochemical reaction produces a supercooled liquid of metastable equilibrium that is quenched then ground into a fine powder. These fine powders or frit can be reheated and will fuse at a lower temperature with little pyroplastic flow giving increased homogeneity, translucency, smoother texture, a lower fusion temperature, and less shrinkage. The temperature at which the surface glassy phase softens allowing the fritted particles to coalesce without further pyrochemical change is called sintering. These sintered dental porcelains, in general, will have little change in the physical, chemical, or optical properties of the glassy matrix upon repeated firings during the necessary steps of the restoration fabrication. However, if improperly fired or over fired, the dispersed leucite crystals can be altered leading to reduced strength or porcelain–metal (core) thermal incompatibilities. During the fritting process the silica matrix is disordered due to the rapid cooling from the molten state and also by the addition of fluxes that break up the silica tetrahedral network by occupying oxygen. These alkali ions reduce the number of cross-linkages between the silicon–oxygen tetrahedra by randomly occupying space in the open network. The net effect of flux (LiO_2, Na_2O, K_2O, BaO, CaO, MgO, ZnO) addition is lower softening or fusion temperature, decreased viscosity, production of glassy phase, increased α, decreased strength, lowered chemical resistance, increased risk of devitrification during repeated firing cycles. The lower fusing temperatures and increased α made possible the modern day metal–ceramic systems. Three components of the porcelain to metal bond are classically described: (*1*) mechanical interlocking through good wetting of the porcelain on the roughened metal surface, (*2*) chemical physical bonding between the oxides of the porcelain and the oxides on the metal surface, and (*3*) a controlled mismatch in α leading to residual compressive forces in the porcelain (described earlier). Any of these may predominate depending on the ceramic system.

Achieving superior esthetics, in general, is simplified by having a ceramic core. However, strength, wear, fit, and longevity must be proven in controlled clinical trials. Increasing the strength of the ceramic core to perform comparably to metal substructures is approached by manipulating the crystalline phase for reinforcement.

Techniques for fabricating all-ceramic systems include (*1*) sintering with alumina-based, magnesia- based, and leucite-reinforced ceramics; (*2*) heat-pressed techniques with leucite-reinforced and lithium-disilicate-based ceramics; (*3*) slip-casting with alumina-, spinel-, and zirconia-based ceramics; and (*4*) the machining of manufactured ceramic blocks available in several types of ceramic. One method uses computer-aided designing/computer aided machining (CAD/CAM) technology to fabricate inlays, onlays, veneers, and crowns. An "optical" impression is obtained from the prepared tooth with an optical scanner and the computerized image of the restoration is designed by the computer software. Subsequently, a ceramic block is machined in the computer-controlled milling machine according to the design and later cemented into or on the tooth by the dentist.

Slip-cast all-ceramics are fabricated by a process very similar to that used for the production of common objects such as plumbing fixtures and beer steins. Successive layers of ceramic slurry are applied to porous refractory gypsum that draws in the water depositing a solid layer of alumina on its surface. The ceramic buildup is dried then sintered for 4 h at 1100 °C, the porous alumina coping is then carved into the desired shape before infiltrating with a slurry of lanthanum aluminosilicate glass by firing at 1120–1150 °C for 3–5 h. The resultant ceramic is a three-dimensional (3D) interpenetrating network of alumina and glass of high strength due to the presence of densely packed alumina and low porosity. The excess glass is removed and the core is subsequently veneered with a thermally compatible veneering ceramic. Improved translucency (esthetics) can be obtained by glass infiltrating a core composed of magnesium spinel and alumina. The strongest slip-cast material currently available contains tetragonal zirconia along with alumina and glass. When a load is induced on the tetragonal zirconia it absorbs energy by transforming into a monoclinic crystal form accompanied by a volume increase of 3% in a crack arresting manner. Flexural strengths (380–700 MPa) and fracture toughness (2–7 $\mathrm{MPa \cdot m^{1/2}}$) for these core materials are in the following rank order: spinel < alumina < zirconia.

Prosthetic Resin Materials

Poly(methylmethacrylate) was introduced as a denture base material in 1937 and in roughly a decade had virtually replaced the use of vulcanite. Acrylic polymers also enjoy a wide variety of uses in additional prosthetic applications, such as, artificial denture teeth, provisional restorations and temporary crowns, denture base repair, relining and rebasing materials, and obturators for maxillofacial defects.

Denture base materials are typically fabricated from heat-cured poly(methylmethacrylate) and rubber-reinforced poly(methylmethacrylate) and perform surprisingly well. These plastics are supplied in a powder liquid or gel form. The 10 poly(methylmethacrylate) powder is modified with ethyl, butyl, or other alkyl methacrylates for impact resistance and contains benzoyl peroxide or diisobutylazonitrile to initiate polymerization when mixed with the liquid monomer. Pigments are added to obtain natural tissue appearance, for example, mercuric sulfide, cadmium sulfide, cadmium selenide, ferric oxide, or carbon black. Various glasses, ceramics and polymer fibers have been added as dispersed phases to various products in an attempt to reinforce the acrylic polymers. The liquid component is methyl methacrylate, modified with various other monomers while including an inhibitor such as hydroquinone to prevent premature polymerization for adequate shelf life. The liquid of cold-, self-, or autocuring resins contain tertiary amine or sulfinic acid chemical accelerators to allow the polymerization of the monomer at room temperature. Plasticizers for resilience and cross-linkers for hardness and decreased solubility may also be included. Denture base resins can also be fabricated through pressure, heat and light-activated techniques with compositional modifications for the various initiation reactions and physical handling properties during fabrication. A number of general requirements for denture base resins are outlined in ANSI/ADA Specification No. 12 (ISO 1567) providing guidance to dentists and dental manufacturers.

Denture teeth are also fabricated from acrylic and modified acrylic materials and are generally preferred over porcelain denture teeth due to wear characteristics, phonetics and technical considerations during fabrication and repair. Temporary or provisional restorations are also fabricated from acrylic-based resins, placed during an interim period in or over the coronal aspects of the tooth while a crown or bridge is fabricated in the dental laboratory. Due to ease of fabrication and tooth-like appearance these are much more popular than aluminum shells or polycarbonate crowns that typically must be relined before temporary cementation to the tooth.

Defects of the head and neck resulting from cancer surgery, accidents and congenital deformities have been corrected with a wide variety of maxillofacial resin materials, including poly(methylmethacrylate), plasticized polyvinylchloride, polyurethane, heat- vulcanized and room temperature-vulcanized (RTV) silicone and a whole host of various other elastomers. It is important to use prosthetic resin materials with color stability, ease of fabrication, dimensional stability, edge strength, flexibility, low thermal conductivity, biocompatibility, and surface texture to achieve clinical success and patient acceptance. Silicones are the most widely used materials for facial restorations in the United States, with RTV Silicone MDX-4-4210, possessing surface texture and hardness within the range of human skin. The prosthesis can be held in place by tissue undercuts, the patient's glasses or dentures, medical grade adhesives, magnetic attachment to endosseous implant-retained metallic attachments or bars or through a combination of methods. A mold is made from an impression of the defect upon which a prosthesis is fabricated and color matched by mixing small amounts of pigments into the elastomer. Surface coloration and texturing is completed and the patient returns periodically for esthetic touchups to achieve a lifelike match to the skin.

Implants

The surgical placement of endosseous dental implants to support dental restorations has become a routine aspect of



Figure 2. Dental implant demonstrating osseointegration. I = implant, B = bone. (Courtesy of John Keller, University of Iowa College of Dentistry.)

dental care enjoying a high success rate. Commercially pure titanium (CpTi) and Ti-6Al-4V are the materials most commonly used for endosseous dental implants. The stable oxides surfaces formed on CpTi and Ti- 6Al-4V have proven to successfully biointegrate with bone. The terms osseointegration and functional ankylosis are used to describe the direct bone apposition on the implant surface giving evidence to support a direct biochemical bonding (Fig. 2). The clinical success of these implants depends not only on osseointegration, but also the quantity, quality and distribution of bone at the implant site, the technical skill during surgical placement, and the timing and degree of mechanical loading under function. Many other factors play a role but six biological and technical factors are recognized as key to implant success: (*1*) implant surface texture, (*2*) biocompatibility, (*3*) implant design, (*4*) host tissue condition, (*5*) surgical technique, and (*6*) loading conditions.

Lower success is observed in areas of the mouth that may have less cancellous bone or thin cortical plates such as the posterior regions of the maxilla. Therefore, attempts are made to manipulate the osseous response to the implant so that the bone quantity and quality at the implant interface is optimized for the clinical requirements. This will not only help the routine implant but is especially important for those patients with: (*1*) poor bone quality, (*2*) heavy masticatory loading, and (*3*) the need for multiple tooth replacement. Surgical procedures are also utilized that enhance the osseous tissues at the intended implant site by auto- or allo-grafting.

Implant surface modifications have been heavily investigated with every major manufacturer offering various implant designs and surface textures. Two of the most thoroughly investigated and successful surfaces are machined titanium and titanium plasma-sprayed (TPS) surface, with the latter significantly increasing the surface area for bone contact. These rougher surfaces have been shown to require higher forces to be removed from the bone than do smoother surface implants and may allow: shorter healing periods, the use of less invasive shorter implants and may not require bicortical implant engagement. Improving the bone adaptation through microretentive mechanisms can be divided into those that attempt to enhance the immigration of new bone through surface topography, that is, osteoconduction, and those that attempt to manipulate the type of cell response and growth for new bone formation, that is, osteoinduction. Osteinductive methods also include the use of the implant as a delivery device for biomolecules for the induction of the desired response. A complex cascade of molecular and cellular processes occur after the placement of the implant into a surgical site, many of which are just now beginning to be understood, leading to the possibility of implant-mediated tissue engineering. Calcium phosphates or “hydroxyapatite” can also be coated on titanium implants and have been documented to create a very intimate bone-to-implant contact with a reduced healing period; however, the long-term results are less favorable than that achieved with TPS due to surface degradation and coating separation problems.

Macroretentive features are also part of the implant design including: screw threads, solid body press-fit designs, and sintered bead technology. These macroretentive features are intended to improve initial implant stability and enhanced bone ingrowth. Without the aid of a periodontal ligament (present between the natural tooth root and bone) the bone responds most favorable to compressive loading, which must accounted for in the implant design.

The original guidelines for implant success have changed over time with an increased use of nonsubmerged (not covered by the gum tissue) and single-staged surgical techniques (immediate abutment placement). These time- and cost-saving changes have come about after studies revealed similar end-results, in terms of “biological width” (composed of junctional epithelial and connective tissue attachment) and clinical survival rates. Considerations such as these are blurring the distinction between the clinical healing period (Phase I) and the functional period (Phase II). Additionally, studies have shown similar clinical predictability using both solely implant supported and mixed tooth-implant-supported fixed partial dentures (bridges), while the use of cemented rather than screw-retained prostheses have reduced technique complications.

Abutments of either titanium or alumina, as compared with those abutments of more “esthetic” quality, such as gold alloys or dental porcelains, are most likely to have favorable soft-tissue healing with formation of a physiological epithelial and connective tissue attachment without subsequent bone resorption. Therefore, surgical techniques to help hide the prosthesis-abutment in the casual viewing region of a patient's mouth by careful peri-implant soft tissue manipulation with proven implant materials is currently recommended.

As work continues to optimize the osteoconductive (passive) response to implant surfaces, research will also progress toward predictable osteoinductive (active) responses. As hard and soft tissue responses are optimized through surgical protocols and biomaterial influences, healing phases will be shortened, retention rates will be increased, and loading capabilities will be improved, allowing the placement of fewer, less invasive and less expensive implants for predictable long-term, implant supported prostheses.

SUMMARY

This article briefly reviewed those commonly used metal, ceramic, polymer, and composite materials used in dentistry for the restoration of individual teeth or the replacement of missing teeth. Restorative materials include noble and base metals, resin based composites, glass ionomers, ceramics, acrylics, and amalgam alloys. These materials are either directly placed into the prepared tooth cavity or cemented in place after laboratory fabrication. An increasing number of "fillings" are retained by the use of dental adhesives. The dentist, in consult with the patient, must take several factors into consideration in the selection of restorative materials, to include (1) chewing forces, (2) esthetic demands' (3) strength of remaining tooth structure, (4) diet, (5) hygiene, and (6) cost. No one material type possesses all the desired physical properties; therefore, several materials are required for successful dental restoration.

Our population is living longer while retaining more of their teeth. With the increased emphasis on preventive dental care, increased awareness and the desire for health, our population will require more partial and single tooth restorations or replacements, especially in the area of root caries and less of a need for removable partial dentures, complete dentures and fixed bridges. Improvements in adhesive dental procedures and direct placed tooth colored resin-based composites will allow more conservative dental care. The interplay of biomaterials and biomolecules may also lead to the predictable regeneration of hard and soft tissues, while tissue engineering may someday lead to the induction of whole tooth regeneration.

BIBLIOGRAPHY

Cited References

1. Craig RG, Powers JM. Restorative Dental Materials. 11th ed. St. Louis: Mosby; 2002.

Reading List

Anusavice KJ. Phillip's Science of Dental Materials. 10th ed. Philadelphia: W. B. Saunders; 1996.

Denry IL. Recent advances in ceramics for dentistry. Crit Rev Oral Biol Med 1996;7(2):134–143.

Ferracane JL. New polymer resins for dental restoratives. Oper Dent 2001; Suppl 6: 199–209.

Keller JC. Dental Implants: The relationship of materials characterization to biologic properties. In: Bronzino JD, editor. The Biomedical Engineering Handbook. 2nd ed. Boca Raton, FL: CRC Press LLC; 2000.

Osborne JW. Mercury, its impact on the environment and its biocompatibility. Oper Dent 2001; Suppl 6:87–104.

Salvi GE, Lang NP. Changing paradigms in implant dentistry. Crit Rev Oral Biol Med 2001;12(3):262–272.

Smith DC. A new dental cement. Br Dent J 1968;125:381–384.

Stanford CM. Surface modifications of implants. Oral Maxillofacial Surg Clin N Am 2002;14:39–51.

See also BIOCOMPATIBILITY OF MATERIALS; BONE AND TEETH, PROPERTIES OF; RESIN-BASED COMPOSITES; TOOTH AND JAW, BIOMECHANICS OF.

BIOMATERIALS, POLYMERS

MIN ZHANG
University of Washington
Seattle, Washington
SUSAN P. JAMES
Colorado State University
Fort Collins, Colorado

INTRODUCTION

Biomaterials are materials of synthetic as well as of natural origin in contact with tissue or biological fluids, including metals, ceramics, polymers, and composites. The main advantages of polymeric biomaterials over ceramics and metals are the variety of composition, properties and available forms (solid, hydrogel, and solution), and ease of fabrication into complex shapes (films, sheets, fibers, powders, etc.) and structures because synthetic polymers are easily tailored to specific applications. In addition, polymeric materials are much lighter than metals and ceramics. Since most natural biomaterials are polymeric, mimicking the function and/or structure of natural materials (e.g., skin) is more easily achieved with polymers or polymeric composites than metals and ceramics. As with other biomaterials, there are some basic requirements for polymeric biomaterials. They must be (*1*) nontoxic, for example, not causing carcinogenesis, pyrogenicity, hemolysis, sustained inflammation, and allergy; (*2*) biocompatible, that is, not causing foreign body reactions, such as complement activation, thrombus formation, collagenous tissue encapsulation, calcification, and compatability with the contact tissue in physical and mechanical properties; (*3*) sterilizable with autoclave, dry heating, ethylene oxide, gas plasma or γ irradiation, or be produced in a sterile fashion so no postmanufacture sterilization is required (1a).

Synthetic polymers have been widely used in biomedical devices, for example, hard and soft tissue implants, extracorporeal devices, drug delivery systems, and medical disposable supplies. They exhibit diverse properties, ranging from hydrophobic, non-water-absorbing materials (e.g., polyethylene, polypropylene, and polytetrafluoroethylene), to hydrophilic, water-swelling hydrogels [e.g., poly(hydroxyethyl methacrylate)], and to water-soluble materials [e.g., poly(vinyl alcohol)] (2a). Biological polymers are obtained from animals, plants, bacteria, or other living creatures. Their remarkable advantages over synthetic polymers include their excellent physiological activities. These activities include cellular activity regulation (e.g., hyaluronic acid), selective cell adhesion (e.g., collagen), and similar properties to natural tissues (3). Most biopolymers are biodegradable, so they are suitable for use in temporary medical devices, drug-delivery systems, and tissue engineering scaffolds.

This section introduces the synthesis methods of generic polymers, and the effect of composition and structure on their properties. Following this, 13 groups of polymers that have found wide biomedical application are reviewed and their properties and uses are discussed.

POLYMERIZATION–SYNTHESIS

Polymers are long molecules made up of a large number of simple repeating units. They are prepared from monomers through a process called polymerization. Small monomer molecules react chemically to form either linear chains or three-dimensional (3D) networks. Conventionally polymerization mechanisms are divided into two main categories: condensation polymerization (also called step-growth polymerization) and addition polymerization (also called chain polymerization).

Condensation or Step-Growth Polymerization

Condensation polymerization occurs between an organic base (e.g., an alcohol and amine) and an organic acid (e.g., carboxylic acid and acid chloride), and a small molecule (e.g., water) is condensed out during the reaction. In a condensation reaction to combine two monomers together to form a dimer, each monomer molecule loses an atom or a group of atoms at the reactive end, leading to the formation of a covalent bond between the two molecules, while the eliminated atoms bond with others to form small molecules. The dimers can react with each other or with unreacted monomers until finally a long molecule is generated. An equilibrium exists between the reactants and products during condensation polymerization. The condensate (e.g., water) should be removed to drive the reaction toward the product direction. A high molecular weight product can be obtained only after a sufficiently long reaction time.

The reaction between a diacid and a dialcohol to produce an ester is a typical condensation polymerization example.

$$n\,\mathrm{HOOC{-}R_1{-}COOH} + n\,\mathrm{HO{-}R_2{-}OH} \rightarrow$$

$$\mathrm{HO{+}OCR_1COOR_2{-}O{+}_{\!n}H} + (2n-1)\mathrm{H_2O}$$

Some condensation polymers used as biomaterials are given in Table 1. They are typically synthesized from reactions of acids and alcohols to produce polyesters, reactions of acids with amines to produce polyamides, or reactions of alcohols or amines with isocyanates to produce polyurethanes or polyurea, respectively.

Synthesis of biopolymers is very complicated, but typically involves enzyme-catalyzed condensation polymerization occurring in animal or plant cells, or in microorganisms via their metabolic pathways (4,5a).

Table 1. Typical Condensation Polymers

Polymer	Repeat Unit
Polyurethane	 $-\overset{O}{\overset{\|}{C}}-NH-R-NH-\overset{O}{\overset{\|}{C}}-O-(CH_2)_x-O-$
Silicone rubber	 $-O-\underset{(CH_3)_3}{\overset{(CH_3)_3}{Si}}-$
Polyamide (Nylon 66)	 $-HN-(CH_2)_6-NH-\overset{O}{\overset{\|}{C}}-(CH_2)_4-\overset{O}{\overset{\|}{C}}-$
Poly(ethylene terephthalate)	
Polycarbonate	
Polyacetal	$-O-CH_2-$
Polyglycolic acid (PGA)	 $-CH_2-\overset{O}{\overset{\|}{C}}-O-$
Polylactic acid (PLA)	 $-\overset{CH_3}{\overset{\|}{C}H}-\overset{O}{\overset{\|}{C}}-O-$

Addition or Chain Polymerization

Addition polymerization occurs among small molecules with double bonds. Polymer chains are formed by opening-up double bonds of unsaturated monomer units and successive addition to a growing chain with an active center. No small molecule byproducts are formed during addition polymerization. Consequently, the composition of the repeating unit of the polymer is identical to that of its monomer. Addition polymerization takes place in three distinct steps: initiation, propagation, and termination. Initiation occurs by an attack on the monomer molecule by a free radical, a cation, an anion, or Ziegler–Natta catalysts; accordingly, addition polymerization can be divided into four types: free-radical polymerization, cationic polymerization, anionic polymerization, and coordination polymerization. No matter how the reaction is initiated, once a reactive center is created, many monomers are added onto it and the molecule chain grows very large within a few seconds or less, so the addition polymer size (i.e., molecular weight) is independent of reaction time. Unlike condensation polymerization, no dimer, trimer, or other intermediates can be found in addition polymerization. Polymerization of ethylene is a typical example of addition polymerization.

$$n\,\mathrm{H_2CCH_2} \rightarrow \mathrm{{+}H_2C{-}CH_2{+}_{\!n}}$$

Typical addition polymers are listed in Table 2.

Table 2. Typical Addition Polymers

Polymer	Repeat Unit
Polyethylene	$-CH_2-CH_2-$
Polypropylene	 $-CH_2-\overset{\overset{CH_3}{\mid}}{CH}-$
Polyvinyl chloride	 $-CH_2-\overset{\overset{Cl}{\mid}}{CH}-$
Poly(terafluoroethylene) (Teflon)	 $-\underset{\underset{F}{\mid}}{\overset{\overset{F}{\mid}}{C}}-\underset{\underset{F}{\mid}}{\overset{\overset{F}{\mid}}{C}}-$
Poly(methyl methacrylate)	 $-CH_2-\underset{\underset{COOCH_3}{\mid}}{\overset{\overset{CH_3}{\mid}}{C}}-$
Poly(vinyl alcohol)	 $-CH_2-\overset{\overset{OH}{\mid}}{CH}-$
Poly(hydroxyethyl methacrylate)	 $-CH_2-\underset{\underset{COOCH_2CH_2OH}{\mid}}{\overset{\overset{CH_3}{\mid}}{C}}-$
Polystyrene	

The stereoregularity and branching of addition polymers can be controlled through varying the type of initiator and the reaction conditions (6). Inonic addition polymerization can lead to some control of tacticity and a stereoregular structure. Polymers produced through coordination polymerization have a high degree of stereoregularity. The polyethylene produced with peroxide initiator is highly branched. By using a Ziegler–Natta catalyst, linear, high density polyethylene or ultrahigh molecular weight polyethylene (UHMWPE) can be obtained. Living free-radical polymerization is a newer form of free-radical polymerization. By using rapid initiation, slow propagation, and inhibition of termination and transfer reactions, the molecular structure of polymers can be precisely controlled. This method can be applied to vinyl monomers to produce block, graft, star polymers, polymer brushes, and many other architectures (5a,7).

Molecular Weight and Its Distribution

Almost all polymers consist of molecules (a.k.a., chains) with a variety of lengths, so it is only possible to quote an average value of molecular weight. The length of a polymer molecule is represented by the degree of polymerization (DP), which is equal to the number of repeat units in the chain. The relationship between polymer molecular weight (MW) and degree of polymerization can be expressed as

$$\text{MW of polmer} = \text{DP} \times \text{MW of repeating units}$$

The number-average molecular weight (M_n) and weight-average molecular weight (M_w) are the most commonly used average values of molecular weight. The number average molecular weight is defined as the sum of the products of the molecular weight of each fraction (M_i) multiplied by its mole fraction (x_i) (Eq. 1), which can be obtained using gel filtration chromatography, light scattering, or ultracentrifugation. Whereas M_w is the sum of the products of the MW of each fraction (M_i) multiplied by its weight fraction (w_i) (Eq. 2), which can be measured with osmometry.

$$M_n = \sum x_i M_i \tag{1}$$

$$M_w = \sum w_i M_i \tag{2}$$

The ratio of M_w/M_n is defined as the polydispersity index (PDI), representing the breadth of the molecular weight distribution. When all the polymer chains have the same length, the ratio is 1. A low polydispersity index is necessary to control physical and mechanical properties of polymers because the short chains usually present when PDI is high degrade properties.

COMPOSITION, STRUCTURE, AND PROPERTIES

The structure and behavior of polymers is strongly temperature dependant. There are two major transition temperatures for polymers: T_g and T_m. The glass-transition temperature is a second-order transition temperature, associated with the amorphous regions of polymers. It marks the onset of significant molecular motion. Above T_g, polymers soften, and become rubber-like and more easily deformed. Below T_g, polymers become hard and brittle, and glass-like. Applications of polymeric biomaterials are related with their T_g values. For example, silicone rubber with a T_g of $-127\,^\circ C$ is soft and acts as an elastomer at $37\,^\circ C$ (human body temperature), while poly(methyl methacrylate) (PMM) used as bone cement with a T_g of $105\,^\circ C$ retains high strength, stiffness, and creep resistance at $37\,^\circ C$. The melting temperature is associated with crystalline regions of polymers. It is a first-order transition temperature. Above T_m, the polymer is in a melt liquid state. Polymeric materials with a low T_m value can be melt processed.

Polymer molecules can be linear, branched, or a cross-linked network. Schematic representations are given in Fig. 1. Based on their molecular structure and their mechanical and thermal behavior, polymers are classified into three major categories: thermoplastics, thermosets and elastomers. They are discussed in detail respectively.

Thermoplastics

These polymers soften and harden reversibly with changes in temperature. Both linear and branched polymers are thermoplastic. The properties of thermoplastics can be changed by controlling the following factors.



Figure 1. Schematic representation of different types of polymer molecules.

Molecular Weight. The molecular weight and its distribution have a great effect on the properties of thermoplastics. By increasing molecular weight, the polymer chains become longer and more entangled, resulting in a higher melting temperature and improved strength, including resistance to creep (8a). The strength properties increase with the molecular weight rapidly at first, but level off after reaching a certain point. Uniform molecular length is also important, because short molecules act as plasticizers, which decrease the mechanical properties of polymers. For example, ultrahigh molecular weight polyethylene must have a high molecular weight (MW, $2\text{–}4 \times 10^6$ g·mol^{-1}) and narrow MW distribution (i.e., low PDI) to obtain excellent mechanical properties for orthopedic applications.

Chemical Composition. The changes in the composition of the backbone or side chains also affect the properties of polymers. When atoms that can increase the flexibility of polymer chains (e.g., O and S) are incorporated into the carbon backbone, for example, polyethylene oxide (CH_2CH_2O) (T_g: $-41\,^\circ C$; T_m: $69\,^\circ C$), the glass transition and melting temperatures will decrease. On the other hand, the insertion of groups that stiffen the polymer chains markedly raises the T_g and T_m and leads to higher strength and stiffness, as seen in the case of polyethylene terephthalate



(T_g: 60/85 °C; T_m: 280 °C).

The replacement of pendant hydrogen atoms in polyethylene by other atoms also changes the polymer properties. Large atoms or groups (e.g., methyl groups in polypropylene), hinder the rotation about the backbone, resulting in higher T_g and T_m, strength, and stiffness. Similar results are observed for the polymers with polar pendant atoms or groups [e.g. poly(vinyl chloride), PVC]. van der Waals forces are enforced and even hydrogen bonds may be formed among the chains of these polymers.

Branching. Branching prevents dense packing and crystallization of the polymer chain, and thus reduces the density, melting temperature, strength, and stiffness of polymers. For example, branched low density polyethylene (LDPE) is much weaker than linear high density polyethylene (HDPE).

Tacticity. When the repeat units of a polymer are nonsymmetrical, the location of the side atoms or groups also plays an important role in the structure and properties of the polymer. If all the side atoms or groups are on one side of the main chain, the polymer is termed isotactic. In a syndiotactic polymer, the side groups alternatively appear on both sides of the chain. In both cases, the polymer is stereoregular or stereotactic. Polymer chains with stereoregularity are better able to crystallize, resulting in high T_m, stiffness and less solubility. In an atactic polymer, side groups are randomly distributed along the molecular chain. Atactic polymers give poor packing, low density, low stiffness, and strength. A typical example of the importance of tacticity is polypropylene. Isotactic and syndiotactic polypropylene have a high T_m (176 °C for isotactic, 150 °C for syndiotactic) and good mechanical properties. They are widely used as biomaterials, whereas atactic propylene is an amorphous waxlike polymer without any application in biomedical field (8b,9).



Figure 2. Four types of copolymers.

Copolymer. Copolymers contain two or more different types of repeat units. According to the distribution of the repeat units, they are divided into four types (Fig. 2). Copolymers are synthesized to obtain the desirable combination of properties of simple homopolymers.

Temperature and Time. Amorphous thermoplastics exhibit viscoelastic behavior, meaning that their properties are time or temperature dependent. At low temperatures or high rates of loading, the polymers behave in a brittle manner. However, at high temperature or low rates, the materials behave as a viscous liquid with chains easily passing one another. The application temperature of most biomaterials is 37 °C, which cannot be changed, but the properties of the materials can be controlled by selecting appropriate T_g.

Thermosets

Thermosets are highly cross-linked 3D molecular networks. High density cross-links between molecules restrict the motion of the chains of thermosets, leading to a high T_g, good strength, stiffness, and hardness, but poor ductility. The hard and stiff thermosetting polymers find uses in hard tissues (e.g., bone and teeth). Poly(carboxylic acid) cross-linked with zinc is a hard and rigid cement used for dental restorations (2a,10a). Epoxy resin is sometime used to fill the cavities of the teeth and provide hardness.

Elastomers

Elastomers are lightly cross-linked macromolecular networks. The cross-linking can be covalent or physical. In thermoplastic elastomers, the hard and tightly packed domains with high T_g (e.g., the hard isocyanate segments in polyurethane elastomer) act as physical cross-links. The loose cross-links prevent viscous plastic deformation while retaining large elastic deformation, so elastomers can be easily stretched to high extension and will go back to their original position on removal of the stress. To act as a biomedical elastomer, a T_g much lower than 37 °C is required, and the polymer should not easily crystallize.

POLYMERS USED AS BIOMATERIALS

Many polymers have been synthesized for biomedical applications. This section just focuses on 13 groups of polymers most commonly used in clinical practice. Each part of the following deals with one polymer or one group of polymers with similar structures. The synthesis, structure, properties, and applications of these polymers will be discussed. Their trade names and related ASTM standards are listed in Tables 3 and 4, respectively, while the thermal and mechanical properties are summarized in Table 5.

Polyolefins

Polyolefins are a group of thermoplastics polymers derived from simple olefins. The most important polyolefins are polyethylene, polypropylene, and their copolymers.

Polyethylene. Commercially available polyethylene has four major grades: LDPE, linear low density (LLDPE), high density (HDPE), and UHMWPE. These materials have good toughness and excellent chemical resistance, and can be easily processed into products at low cost.

Low density polyethylene is produced through the free-radical polymerization of ethylene gas at high pressure (100–300 MPa) in the presence of peroxide initiator (5c). The synthesis conditions lead to the highly branched structure, low density (0.915–0.935 g·cm^{-3}) and crystallinity of LDPE (11a). By using Ziegler–Natta catalyst, HDPE can be synthesized at a low temperature (60–80 °C) and pressure ($\sim$10 MPa). Unlike LDPE, HDPE is linear. The linearity leads to good packing of the molecular chains, high crystallinity, and density (0.94–0.965 g·cm^{-3}) of HDPE. The LLDPE is produced by a low pressure process in the presence of metal catalysts. Up to 10% of a 1-alkene (e.g., butene-1, hexene-1, and octane) is used as the comonomer. Unlike LDPE, the side chains of LLDPE are very short, resulting in better properties than LDPE (12). All three types of polyethylene can be melt-processed through extrusion or molding. The LDPE cannot withstand sterilization temperatures, so only HDPE and LLDPE are used for biomedical applications (2a). The HDPE is used in tubing for catheters and drains, and in pharmaceutical bottles and nonwoven fabrics. The LLDPE is frequently used for pouches and bags due to its excellent puncture resistance. Biocompatibility tests for PE used as human tissue contact devices, short-term implantation of 30 days or less and fluid transfer devices are given in ASTM F 639 (not applicable for UHMWPE).

When molecular weights of the linear polyethylene obtained through Ziegler–Natta catalyst are $>1\times 10^6$g·mol^{-1}, there is a sudden jump in the properties (13). The melt viscosity becomes extremely high so that the polyethylene cannot be processed with conventional extrusion and injection molding. Also it is practically insoluble in all solvents, so only sintering at high temperature and pressure may be used to fabricate the desired products. The polyethylene has excellent mechanical properties and a very low coefficient of friction and wear. It is termed UHMWPE. The UHMWPE, currently

Table 3. Structures and Trade Names of Polymeric Biomaterials

Polymeric Biomaterials	Structure	Trade Names
Cross-Linked UHMWPE	UHMWPE Cross-Linked through Radiation or Chemical Reactions	Crossfire (Stryker Howmedica Osteonics), Marathon (DePuy Orthopaedics), and Durasul (Sulzer Medica)
Polypropylene	Linear macromolecules	Prolene (Ethicon), Surgipro (Syneture)
PTFE	Linear macromolecules, highly crystalline	Teflon (DuPont)
Expanded PTFE	PTFE with microporous structure	GoreTex (Gore)
PMMA	Atactic, linear macromolecules	Plexiglas (Rohm & Haas), Lucite (DuPont)
Polyurethane	Thermoplastic segmented polyurethane elastomers	Biomer (Ethicon), Pellethane (Dow Chemical), Tecoflex (Thermedics)
Polyamide	Linear macromolecules, strong intermolecular hydrogen bonding	Nylon (DuPont)
PET	Linear, stiff macromolecules	Dacron (DuPont)
Polyacetal	Closely packed, linear molecules	Delrin (DuPont)
Poly(hydroxyethyl methacrylate)	Hydrogel	Hydron (Hydron Technologies)
PGA	Biodegradable polymer	Dexon (American Cyanamid)
PLGA	Biodegradable polymer	Vicryl (Ethicon)
Poly(ethylene oxide/propylene oxide) copolymers	PEO-PPO-PEO triblock copolymer	Pluronic F127 (BASF)
Hyaluronan	Crosslinked hyaluronan Hyaluronan with carboxyl groups esterified by alcohol	Hylan (Biomatrix)Hyaff (Fidia Advanced Biopolymer)

Table 4. Polymeric Biomaterials and Related ASTM Standards

Polymer	ASTM Standards	Scope
Polyethylene	F 639	Specifies requirements and physical/biological test methods for PE plastics used in medical devices (not applicable to UHMWPE).
UHMWPE	F 648	Specifies property requirements for UHMWPE powder and fabricated forms used for surgical implants, such as joint implants.
PVC	F 665	Classifies formulations of PVC plastics used for short-term biomedical application.
PTFE	F 754	Specifies the performance of PTFE in sheet, tube and rod shapes used for surgical implants.
PMMA bone cement	F 451	Specifies composition, physical performance, packaging requirements, and biocompatibility of acrylic bone cement.
	F 2118	Provides test methods to evaluate the fatigue properties of acrylic bone cement.
Polyurethane	F 624	Provides guide to evaluate thermoplastic polyurethane in solid and solution forms for biomedical applications.
Silicone rubbers	F 2038	Provides information about formulation and use of silicone elastomers, gels, and foams used in medical applications.
	F 2042	Provides information about fabrication and processing of silicone elastomers, gels and foams used in medical applications.
Polycarbonates	F 997	Specifies requirements and test methods for polycarbonates used for medical devices.
Polyacetal	F 1855	Specifies requirements and test methods for polyacetal used for medical devices.
L-PLA	F 1925	Specifies requirements for virgin poly(L-lactic-acid) resin used for surgical implants.
	F 1635	Defines testing methods to assess biodegradation rates and changes in material and properties of poly(L-lactic-acid) resin and devices.

used for fabrications of acetabular cups in hip replacements (Fig. 3), tibial plateau and patellar surfaces in knee replacements, sliding core in spinal disk replacements, and glenoid components in shoulder replacements, has a MW $\sim 2\text{–}4 \times 10^6$ g·mol^{-1}. The property requirements of UHMWPE for surgical implants are defined by ASTM F648. Before 1995, γ radiation in air was a standard method to sterilize UHMWPE orthopedic implants. However, free radicals within UHMWPE from gamma radiation caused oxidation and property degradation on shelf aging and *in vivo*. By 1998, all of the major orthopedic manufactures in the United States changed to use gamma radiation in an inert or a reduced oxygen environment, ethylene oxide, or gas plasma to sterilize UHMWPE (14). Despite the recognized success of UHMWPE as loading bearing surfaces in joint arthroplasties, UHMWPE wear debris and associated osteolysis and loosening of implants remains a major obstacle limiting the longevity of current joint replacements. To further improve the wear resistance, highly cross-linked UHMWPE is developed by

Table 5. Properties of Polymeric Biomaterials^a

Polymer	T_g, °C	T_m, °C	Tensile Strength, MPa	Tensile Modulus, GPa	Elongation, %
Polyethylene					
LDPE	−120	115	7.6	0.096–0.26	150
HDPE	−120	137	23–40	0.41–1.24	400–500
UHMWPE	−120	130–145	30	1.1–2.0	300
Polypropylene	−20	175	28–36	1.1–1.55	400–900
Polyvinyl chloride	80	180	40–50	2.4–4.1	2–80
Teflon	117	327	15–35	0.40	2–5
Poly(methyl methacrylate)	105		50–75	2.0–6.0	2–10
Polyurethane (elastomer)			23–58		400–600
Silicone rubbers	−123				
Soft			6.0		600
Hard			7.0		350
Polyamide					
Nylon 6	50/100	270	70	0.7	300
Nylon 66	50	280	75		300
Poly(ethylene terephthalate)	60–85	280	50–70	3.0–4.0	30–300
Polycarbonate	150	230	65	2.4	110
Polyacetal	−85	181	65–80	5.0–13.0	9.5–12
Poly(lactic acid)					
L-PLA	54–59	159–178	28–50	1.2–3.0	2.0–6.0
DL-PLA	51		29	1.9	5.0
Poly(glycolic acid)	35	210			
Collagen fibers			50–1000	1.0	10
Cellulose acetate	230		13–60	0.45–2.8	1.9–9.0

[a] Refs. 5b 9, 10c, and 17e.



Figure 3. A total joint replacement: (1) metal backing of acetabular cup, (2) UHMWPE acetabular cup, (3) metallic femoral prosthesis.

cross-linking conventional UHMWPE through chemical reactions, or through gamma or electron beam radiation. Cross-linked UHMWPEs available on the market include Crossfire (Stryker Howmedica Osteonics), Marathon (DePuy Orthopaedics), and Durasul (Sulzer Medica). Both research and clinical applications have demonstrated that cross-linking dramatically reduces the wear rate of UHMWPE (14).

Polypropylene. Like linear polyethylene, syndiotactic and isotactic polypropylene are also polymerized through Ziegler–Natta catalyst. Although polypropylene is similar to polyethylene in structure, polypropylene has a lower density $\sim 0.90\ \mathrm{g{\cdot}cm^{-3}}$ and a higher T_g ($-12\,^{\circ}\mathrm{C}$) and T_m (125–$167\,^{\circ}\mathrm{C}$). The higher melting temperature makes polypropylene suitable for autoclave sterilization (15). The chemical resistance of polypropylene is similar to high density polyethylene, while its stress-cracking resistance and creep resistance is superior to that of polyethylene. It has an exceptionally long flex life, and thus is used to make integrally molded hinges in finger joint prostheses (11a). Also as a suture material, polypropylene yarn (e.g., Prolene from Ethicon, Surgipro from Syneture) has been used clinically (2a,10b). It causes least fibroblastic response compared with other nondegradeable suture materials and does not lose strength after it is implanted.

Poly(vinyl chloride)

Poly(vinyl chloride) is a linear, atactic polymer synthesized through free-radical polymerization. Due to the large volume and high polarity of the chlorine atoms, it is difficult for the molecular chains to rotate and disentangle and hydrogen bonds are formed between adjacent chains, resulting in high strength and stiffness, and T_g ($80\,^{\circ}\mathrm{C}$) and T_m ($180\,^{\circ}\mathrm{C}$) (10c). Pure PVC is hard and brittle, but with the addition of plasticizers, it becomes soft and flexible. In the medical formulations of PVC, di-2-ethylhexylphthalate (DEHP or DOP) is used as a plasticizer. Plasticized PVC is used in temporary blood storage bags, catheters, cannulae, and dialysis devices. The PVC may pose problems for long-term applications because of possible extraction of the plasticizer by body fluid. Standard classification for vinyl chloride plastics used in biomedical applications is provided by ASTM F665.

Poly(tetrafluoroethylene)

Poly(tetrafluoroethylene) (PTFE), commonly known as Teflon (DuPont), is made from tetrafluoroethylene through free-radical polymerization in the presence of excess of water for removal of heat. The polymer is highly crystalline ($>94\%$ crystallinity, T_m $327\,^{\circ}\mathrm{C}$), dense ($2.2\ \mathrm{g{\cdot}cm^{-2}}$) and insoluble in all common solvents. It is very stable both thermally and chemically, and as a result it is very difficult to process. The PTFE can only be sintered into products at a temperature $>327\,^{\circ}\mathrm{C}$ under pressure.

The PTFE has excellent lubricity, its coefficient of friction is very low (0.1), but it is not wear resistant, its modulus of elasticity and tensile strength are very low, and even more importantly it can not maintain shape very well due to the cold-flow (5c). The use of Teflon as the acetabular component material by Charnley (2b) in his total hip replacement design 40 years ago caused a catastrophe. All Teflon cups failed *in vivo*, requiring revision surgery.

Although not suitable for load bearing surfaces, PTFE can be used for other biomedical applications because of its excellent biocompatibility and stability. Standard specifications for the implantable PTFE are given in ASTM F754. Expanded PTFE (ePTFE) vascular grafts, made by stretching paste-extruded PTFE tubes at a temperature $< T_m$ and then sintering, are soft microporous tubes (GoreTex). They show good clinical results as medium diameter (5–11 mm) vessel grafts, (e.g., femoral and popliteal artery replacements) (10d,16a). However, intimal hyperplasia of smooth muscle cells at the anastomosis frequently leads to their failure. The ePTFE grafts are also popular in hemodialysis as an interposition between radial artery and cubital vein. However, thrombosis occurring at the graft venous ends may be a concern (16b). The PTFE fabrics find applications in heart valve prosthesis as suture ring (10b). Sheets or films of PTFE or its composite with graphite are widely used by plastic surgeons in reconstruction of the maxillofacial areas (10b). The PTFE tubes are used for middle ear drain, while PTFE shunts are used to carry cerebral spinal fluid from brain to venous in the treatment of hydrocephalus.

Poly(methyl methacrylate)

The commercially important poly(methyl methacrylate) (PMMA) is atactic, which is produced by free-radical polymerization of methyl methacrylate monomer (liquid) using initiator, or thermal, or photochemical initiation. Because of the bulky side chains, atactic PMMA is completely amorphous (T_g: $105\,^{\circ}\mathrm{C}$) and has an excellent light transparency (92% transmission) and a high index of refraction (1.49). The transparent material is familiar as Plexiglas or Lucite. For the same side group argument presented above, the strength and stiffness of PMMA are also relatively high. As a hard thermoplastic polymer, PMMA can be easily formed into any desirable shapes by regular cast, molding, or machining.



Figure 4. Chemical formula of bisphenol-A-glycidyl dimethacrylate (a new bone cement).

Table 6. Composition of PMMA Bone Cement (Surgical Simplex)

Components	Composition	Amount, %
Powder (40 g in a packet)	Polymethyl methacrylate	15.0 (w/o)[a]
	Methyl methacrylate –styrene copolymer	75.0 (w/o)
	$BaSO_4$	10.0 (w/o)
	Dibenzoyl peroxide	Trace
Liquid (20 mL in an ampoule)	Methyl methacrylate	97.4 (v/o)[b]
	N, *N*-Dimethyl-*p*-toluidine	2.6 (v/o)
	Hydroquinone	Trace

[a] w/o: weight percentage.

[b] v/o: volume percentage.

Poly(methyl methacrylate) is highly biocompatible and chemical resistant. It has been used in a variety of medical applications including hard contact lenses and intraocular lenses, membranes for blood dialysis, cranioplasty, bone cement for joint prostheses fixation, dentures, and maxillofacial implants.

The PMMA resin used for bone cement and dentures are usually formulated from two components: prepolymerized PMMA solid particles and the methyl methacrylate monomer liquid. When the two components are mixed during a clinical procedure, an easily moldable dough is obtained that cures in ~ 10 min. The liquid monomer polymerizes by free-radical reaction and binds the solid particles together. The composition of a commercial bone cement product (Surgical Simplex) is given in Table 6. Dibenzoyl peroxide is included in the solid component to initiate polymerization of the methyl methacrylate monomer. *N*, *N*-Dimethyl-*p*-toluidine is an activator to promote self-curing of the monomer at room temperature. Hydroquinone is added as an inhibitor to prevent premature polymerization of the monomer during storage. Barium sulfate ($BaSO_4$) is a radioopacifier. The methyl methacrylate–styrene copolymer is added to adjust the mixing and handling characteristics (e.g., viscosity, exotherm) of the cement. The physical and mechanical properties of the cement can be controlled through changing the composition and relative proportions of the components, solid particle size and its molecular weight. The requirements for PMMA bone cement are given in ASTM F451. The test methods for its fatigue performance are provided in ASTM F2118.

The PMMA bone cement is inert (no bioactivity), and the fatigue failure occurring at the cement-prosthesis and the cement-bone is a main cause of implant loosening (16c). New bioactive bone cements (BABCs) have been developed to improve the bonding strength and biochemical properties of PMMA bone cement (17a). These BABCs consist of bioactive glass ceramic powder (e.g., $CaOMgOSiO_2P_2O_5CaF_2$) and a bisphenol-A-glycidyl dimethacrylate-based resin shown in Fig. 4.

Polyurethanes

Polyurethanes are a family of heterogeneous polymers containing the urethane linkage (NHCOO) and frequently the urethane groups are not the predominant functional groups (5d,18). The most common method to synthesize polyurethanes consists of two steps (Fig. 5). The first step involves formation of an isocyanate terminated prepolymer from polyester or polyether polyols and di- or higher isocyanate. Subsequent reaction of the prepolymer with a chain extender, usually a diol or diamine, produces a multiblock copolymer. These two reactions are a step-growth polymerization, but no condensed byproduct is eliminated, so this type of polymerization is often referred to as a polyaddition or rearrangement polymerization. Due to the multiple choices in the chemistry and molecular weight of the various components, polyurethanes exhibit a broad range of physical properties: from hard and brittle thermoset polymers, through thermoplastic elastomers, to viscous materials. Thermoplastic segmented polyurethanes usually are valuable in producing medical devices (e.g., extruded blood tubing), while the cross-linked ones have received more attention for long-term devices and implants. The ASTM F624 provides test methods to evaluate properties of thermoplastic polyurethanes.



Figure 5. Two-step synthesis of polyurethane.

The isocyanates used for linear polyurethane elastomers are aromatic diisocyanates [e.g., toluene diisocyanate (TDI) and 4,4′-diphenylmethane diisocyanate (MDI)], which comprise the hard segments of the thermoplastic elastomers with the chain extenders. The soft segments of the elastomers are blocks of polyether polyols (usually polyethylene glycol PEG) or polyester polyols. These two types of segments tend to aggregate into different domains, resulting in microphase separation with the hard blocks acting as physical crosslinks in the thermoplastic elastomer.

Polyurethane elastomers are good materials for use in medical devices due to their good mechanical properties and blood compatibility. The very high flexural endurance of polyurethanes makes them major candidates for cardiovascular implants. Biomer (Ethicon, NJ), Pellethane (Dow Chemical, TX), and Tecoflex (Thermedics, MA) are all polyurethanes under different trade names. They have been widely used for cardiac guiding catheters, pacemaker lead insulation, vascular prostheses, artificial heart assist devices, blood tubing, and hollow fiber dialysers. Polyurethanes are also used extensively for wound healing. Bioclusive (Johnson and Johnson Medical, Inc.) and Opsite (Smith and Nephew) are two types of nonabsorbent wound dressings made from polyurethane films.

Although these ether-based polyurethanes are stable *in vitro*, environmental stress cracking after implanted makes their long-term biostability questionable. The microcracks caused by biological peroxidation of the ether linkage not only weaken the materials, but also serve as nucleation sites for thrombus formation (19a). To solve the problem, polycarbonate-based polyurethanes have been developed and investigated to provide an unsurpassed combination of biostability, strength, flexibility, and ease of manufacture.

Silicone Rubbers

The basic repeat unit of silicone rubbers is dimethyl siloxane. They are made by vulcanization of silicone prepolymers or by ring-opening polymerization of octamethylcyclotetrasiloxane. Silicone prepolymers are obtained by the hydrolysis of dimethyldichlorosilane with water. The hydrolysis product is dimethylsilanol, which is unstable and condenses to low molecular weight silicone prepolymers in the presence of hydrochloric acid (5d,12,17b) (Fig. 6). Silicone prepolymers are also useful as silicone oil. The vulcanization of the prepolymers can be performed at room or at high temperature. Room temperature vulcanization silicone rubbers are available in two formats: one-component or two-component. The one-component silicone rubbers result from a reaction between atmospheric moisture and a mixture of silicone prepolymers and catalyst, whereas the two-component systems result from a reaction between prepolymers and a cross-linker added to initiate the reaction. In heat vulcanization, peroxides are used to produce free radicals on heating that react with the side groups of prepolymers to form cross-links. Several copolymer silicone rubbers have been developed to meet diverse biomedical applications. Copolymers made from dimethyl siloxane and a small amount of methylvinyl siloxane result in medium and hard grades of silicone rubbers. Soft grades of silicone rubber are copolymers with phenyl-methyl-siloxane. Requirements for medical grade silicone gels and elastomers are provided in ASTM F2038 and F2042.

Silicone rubbers have many excellent properties, (e.g., extreme inertness, nonadhesion, high oxygen permeability, thermal and oxidative stability, and high flexibility at low temperature). A major disadvantage of silicone rubbers is poor resistance to tearing. Silicone rubbers are one of the widely used polymeric biomaterials in modern medicine. Since Alfred Swanson introduced silicone rubber for small flexible joints in 1960s, > 600,000 silicone rubber hinge or end-bearing prostheses have been implanted to treat arthritic conditions of finger and wrist joints. These silicone implants are successful in relieving pain and restoring motion of joints at initial stage, but their long-term durability and biocompatibility have been questioned. Silicone microparticles from fragmentation or wear may cause immune reactions (20a). The largest use of silicone rubber and gel has been in breast augmentation and reconstruction (19b). Gel bleed, calcified deposit, and autoimmune diseases are concerns related to these gel-filled silicone rubber bag implants. In the earliest prosthetic cage-and-ball heart valves, silicone rubber was used for the ball, but uptake of blood lipids by the silicone led to the swelling and fracturing of the ball after several years of service. Presently, silicone rubber is only used for the suture ring in bioprosthetic heart valves (10d). Other medical applications of silicone rubber include soft contact lenses, catheters and drainage tubing, oxygenator membranes, wound dressings, and facial implants.

Polyamides

Polyamides are known as nylons. They are divided into two types: dyadic nylons and monadic nylons. The dyadic nylons, (e.g., nylon 66 and nylon 610) are made through condensation polymerization of diamine and dicarboxylic acid or its derivatives (Fig. 7a). There are two numbers following the name, the first for the number of carbon atoms in the diamine and the second for that in the diacid. The monadic nylons (e.g., nylon 6 and nylon 11) are made through self-amidation of an amino acid or through ring-opening polymerization of a cyclic lactam (Fig. 7b). The single number following the name represents the number of monomer carbon atoms. These polymers have high crystallinity and very strong intermolecular hydrogen bonding between amide groups. Thus, they have excellent fiber forming properties, and the strength along the fiber



$$\mathrm{Cl{-}\overset{CH_3}{\underset{CH_3}{Si}}{-}Cl} + \mathrm{H_2O} \longrightarrow \mathrm{HO{-}\overset{CH_3}{\underset{CH_3}{Si}}{-}OH} + \mathrm{HCl} \longrightarrow \left(\mathrm{\overset{CH_3}{\underset{CH_3}{Si}}{-}O}\right)_n + \mathrm{H_2O}$$

Figure 6. Formation of silicone prepolymer.



Figure 7. Synthesis of nylons: (a) nylon 66, (b) nylon 6.

direction is very high. The number and distribution of amide groups play an important role in determining the properties of nylons. Generally, the T_g and tensile properties increase with increasing the number of amide groups. For example, nylon 66 is stronger than nylon 610 and nylon 6 is stronger than nylon 11 (11a).

Nylon plastics are stiff and tough, and have a high abrasion resistance; but they are sensitive to water. Water adsorption reduces their strength and lowers their T_g. It is the amorphous region of polyamide chains that is sensitive to the attack of water. The greater the degree of crystallinity, the less the water adsorption. Nylons are used as surgical sutures, components of dialysis devices, hypodermic syringes, and intracardiac catheters.

Polyesters

Polyethylene Terephthalate. Polyethylene Terephthalate (PET) is known as Dacron. Commercially, it is manufactured by ester interchange polymerization between dimethyl terephthalate and excess glycol (1:1.7). The reaction has two stages (5d,12) (Fig. 8). In the first stage, methanol is displaced from dimethyl terephthalate by glycol. In the second stage, the excess glycol is driven off under vacuum. The polymer is semicrystalline with a T_m value of 265 °C and a T_g value of 80–120 °C depending on crystallinity. The PET fibers made from melt spinning have high strength and good crease resistance, so they are used as nondegradeable surgical sutures. Like PTFE, PET is also hydrophobic and hydrolysis resistant. The knitted or woven PET tubes are widely used for large diameter (12–30 mm) and medium diameter (5–11 mm) vascular grafts. However, Dacron graft devices are not fully satisfactory. Thrombosis is a major problem. Another drawback of Dacron grafts is the need for preclotting the grafts with autologous blood before implantation to prevent bleeding from their micropores (16a).

Polycarbonates. Bisphenol A polycarbonate is the only commercially significant polycarbonate product, so this material is often referred to as polycarbonate. It is prepared either by the reaction of phosgene with bisphenol A, or by ester interchange of a diphenyl carbonate with bisphenol A (Fig. 9). Polycarbonate is a clear, tough material. It has excellent mechanical and thermal properties (T_g 150 °C). The high transparency and impact strength make polycarbonate useful as lenses for eyeglasses and safety glasses, and housings for oxygenators and heart–lung bypass machines (2a). Requirements for medical grade polycarbonates are given in ASTM F 997.

Polyacetal

Polyacetal, also called poly(oxymethylene) is known as Delrin (DuPont). It is prepared from formaldehyde in an inert hydrocarbon solvent along with an initiator (ring-scission polymerization) (5d). The polymer has a high melting temperature (184 °C) and low glass transition temperature (−82 °C) (5b). It is lubricious, strong, and has good dimensional stability, resistance to creep and fatigue, high abrasion, and chemical resistance. A cementless polyacetal isoelastic femoral stem was introduced in the early 1970s to solve two important problems in total hip replacement (THR): stress shielding and cement disease. The modulus of elasticity of polyacetal (∼ 5–13 GPa) is close to that of bone, thus providing the condition of isoelasticity. However, the prostheses were unsuccessful in clinical practice due to high rate of loosening (20). The successful use of polyacetal in medical devices includes use in the valve disk in Penn State circulatory-assitant devices, which is one of only two approved for heart replacement by the U.S. Food and Drus admistration (FDA) (16d). Specifications for polyacetal are given in ASTM F 1855.

Hydrogels

Hydrogels are 3D networks of hydroplilic polymers held together by chemical or physical crosslinks. Typical methods to prepare hydrogels include irradiation, chemical reactions, and physical association. Hydrogels have inherently weak mechanical properties, so hydrophobic



Figure 8. Synthesis of poly(ethylene terephthalate).



Figure 9. Synthesis of polycarbonate through (a) phosgene, (b) ester interchange.

constituents are often incorporated to improve the mechanical strength. The low interfacial tension with surrounding biological fluids makes hydrogels desirable for nonfouling surfaces (10c). Hydrogels tend to calcify under physiological conditions, limiting the use of hydrogels as implantable biomaterials (17c).

Poly(hydroxyethyl methacrylate) (PHEMA) is the most frequently used hydrogel. It is a rigid acrylic polymer when dry, but it takes up ~40% water when wet and changes into an elastic gel. PHEMA hydrogel is transparent, and thus is used for soft contact lens (17c). Other more hydrophilic hydrogel monomers, such as methacrylic acid and 1-vinyl-2-pyrrolidone, are often copolymerized with hydroxyethyl methacrylate to improve the oxygen permeability coefficient and water adsorption of PHEMA hydrogel. This hydrogel was also the first successfully used for wound dressings under the trade name Hydron (17c).

Poly(vinyl alcohol) is a water-soluble polymer. Solutions of PVA are used as ophthalmic lubricants and viscosity-increasing agents. The solution thickens the natural film of tears in eyes. Poly(vinyl alcohol) can crystallize even in its highly hydrolyzed state, and thus it has a relatively high tensile strength for a hydrogel. The PVA hydrogel is a candidate material for artificial articular cartilage in reconstructive joint surgery, and has been used for releasing bovine serum albumin. Physically cross-linked PVA hydrogels prepared by free-thaw processes have been investigated for protein-releasing matrix (17c).

Other synthetic hydrogels of biomedical interest include polyacrylamides, poly(*N*-vinyl-2-pyrrolidone), poly(methacrylic acid), and poly(ethylene oxide).

Biodegradable Synthetic Polymers

The interest in biodegradable polymers has dramatically increased in recent years, because these biomaterials do not permanently leave residuals in the implantation site, do not elicit permanent foreign-body reactions, and avoid second surgeries in the case of temporary implants like fracture fixation devices (10c,11b,17d). The major biomedical applications of biodegradable polymers include: temporary scaffolding and barrier, drug delivery matrix, tissue engineering scaffolds, and adhesives. Biodegradable polymers are generally hydrophilic. They degrade either by simple hydrolysis without enzyme catalysis or by enzymatic mechanisms. The degradation products should be inert or a natural metabolite of the body (11b).

The most commercially successful biodegradable polymers are polyglycolide (PGA), polylactide (PLA) and their copolymer poly(glycolide-*co*-lactide) (PLGA). The polymers PGA, PLA, and PLGA are a group of poly α-hydroxy acids belonging to absorbable polyesters. They degrade by bulk hydrolysis of their ester bonds. The hydrolysis byproduct of PLA is lactic acid, which is a normal byproduct of anaerobic metabolism in the human body (17e). The degradation of PGA involves both hydrolytic scission and enzymatic degradation, and the product is glycolic acid that can be eliminated by the metabolic pathway as carbon dioxide and water (1b).

Polylactide is prepared in the solid state through ring-opening polymerization. It has four stereoisomers: D-PLA, L-PLA, DL-PLA, and *meso*-PLA. The most frequently used forms in biomedical practice are L-PLA, and DL-PLA (2c). The L-PLA is a semicrystalline polymer with a T_m of 159–178 °C and T_g of 54–59 °C (17e). Compared with other biodegradable polymers, L-PLA exhibits high strength and modulus, and a very slow biodegradation rate. It is suitable for light load-bearing applications (e.g., orthopedic fixation devices, vascular grafts, and surgical meshes). Self-reinforced L-PLA bolts, screws, pins and anchors have been used for bone fracture fixation (1b). The DL-PLA is an amorphous polymer with a T_g of 51 °C. It degrades very fast, and thus usually is used for drug delivery (11b). The L-PLA polymer and its *in vitro* degradation tests are specified in ASTM F 1925 and F 1635, respectively.

Polyglycolide can be synthesized either by direct polycondensation of glycolic acid or by ring-opening polymerization of the cyclic dimers of glycolic acid. Due to tight molecular packing, PGA has a high melting point (225–230 °C). Its T_g ranges from 35 to 40 °C. The PGA degrades faster than LPLA because it is more hydrophilic (11b) and PGA can be melt spun into fibers and fabricated into sutures, meshes, and surgical products. Dexon (American Cyanamid) is a trade name of polyglycolide products. It has been successfully used for wound closure and sutures (10c,11b). The Properties and degradation rate of PLGA can be controlled by varying the ratio of monomers. Vicryl from Ethicon is a poly(glycolide-L-lactide) random copolymer with 90:10 ratio of glycolide to lactide. It completely degrades *in vivo* after 90 days, and has been successfully used as surgical meshes and sutures, and for wound closure and drug delivery (10c,21b). Several other biodegradable polymers have been developed and investigated for drug delivery, tissue engineering, and medical devices [e.g., polyorthoesters, poly(ϵ-caprolactone), polydioxanone, and polyanhydride] (11b).

The concern with PLA and PGA is that their degradation products (lactic acid and glycolic acid) may significantly lower the local pH in a closed and less body-fluid-buffered region, leading to irritation at the site of polymer implant (11b).

Smart Polymers

Smart polymers are "polymers that respond with large property changes to small physical or chemical stimuli" (22). The most common stimuli are pH values and temperatures. Some polymers [e.g., poly(hydroxypropyl acrylate), poly(*N*-isopropylacrylamide), and poly(ethylene oxide/propylene oxide) copolymers] exhibit thermally induced precipitation and have a lower critical solution temperature (LCST). The polymers are soluble in water below LCST, but precipitate sharply as temperature is raised above LCST. Pluronic F127 (BASF, NJ) is a polyethylene oxide–polypropylene oxide–polyethylene oxide triblock copolymer with a LCST around the physiological temperature. It is used for controlled release of drugs including proteins and liposomes (23).

In general, pH-responsive hydrogels can be prepared from polymers with ionizable groups (e.g., carboxyl, sulfonic, amino, and phosphate groups). The pH change influences the ionization degree of the polymer to govern its solubility in water. Lysozyme (a cationic protein) immobilized within a hydrogel with phosphate groups is released at pH 7.4 (enteric conditions), but is not released at pH 1.4 (gastric conditions), ensuring the drug is delivered to the small intestines, and is not released in the stomach (17f).

Besides drug delivery, smart polymers can be used for sensors, chemical valves, mechanochemical actuators, specialized separation systems, and artificial muscles.

Biopolymers

Biopolymers are polymers of natural origin that can be obtained from animals, plants, and microorganisms. They are produced during the growth cycles of all organisms by enzyme catalyzed stepwise polymerization rather than a chain polymerization (5a). Biopolymers most frequently used for medical applications are polysaccharides and proteins.

Cellulose is a polysaccharide of plant origin. It is the primary structural component of plant cell walls. The molecular chain of cellulose is linear, consisting of D-glucose residues linked by β(1-4) glycoside bonds (Fig. 10a). The strongly hydrogen-bonded structure make cellulose highly crystalline and exceptional in strength, but insoluble in water and most organic solvents, and infusible. Ether and ester derivatives of cellulose, such as cellulose acetate and hydroxyethyl cellulose, have been developed to improve its processability (24). Cellophane (regenerated cellulose) semipermeable membrane was first used for hemodialysis to remove blood waste in the 1960s, and it is still in use today, but mostly in hollow fiber forms. Cellulose acetate (di- and triacetate) membranes and hollow fibers also find in hemodialysis. Hydroxypropylmethylcellulose is the most widely used hydrophilic drug delivery matrix (17f). The matrix tablets can be formed by compression, slugging, or wet granulation. Cellulose and its derivatives are also used as wound dressings.

Hyaluronan (HA) is a natural mucopolysaccharide, present in connective tissues of all vertebrates, which consists of repeating disaccharides of *N*-acetylglucosamine and glucuronic acid (Fig. 10b). Besides inherent biocompatibility, hyaluronan has some other unique properties: viscoelasticity, hydrophilicity, lubricity, and biological activity (regulator of cellular activity) (25). Unlike cellulose, hyaluronan is soluble in water forming a viscous solution, and it is biodegradable. Many derivatives have been developed to improve its residence time in water. Hylan (crosslinked hyaluronan, Biomatrix) and Hyaff (hyaluronan with carboxyl groups esterified by alcohol, Fidia Advanced Biopolymer) are two groups of widely used and commercialized hyaluronan derivatives. Native hyaluronan and Hylan are used for viscosupplementation to treat arthritis, viscoseparation to prevent adhesion and facilitate wound healing after surgeries, and viscoaugmentation to correct scars and facial wrinkles. Hyaff is widely used for wound dressings as sheets, meshes, or nonwoven fleeces. Hyaluronan and its derivatives have also been investigated for lubricious coatings of biomedical devices, control released drug delivery and tissue engineering scaffolds (26).

Collagens are a family of structural fiber proteins present in all animals (27). They are the most abundant proteins in



(a) (b)

Figure 10. Structure of polysaccharides: (a) cellulose, (b) hyaluronan.

vertebrates, widely distributed in pliant connective tissues and tensile structures (e.g., tendon and ligament) as scaffolds to keep their shape, maintain integrity, and support tensile stress. A collagen molecule is composed of three polypeptide chains wound into a triple helix, stabilized by interchain hydrogen bonds. They are subject to degradation by lysozomal enzymes and collagenase. Glutaraldehyde and carbodiimides can be used to crosslink collagens to improve their mechanical properties (10c). Collagens are probably the most common proteins used as biomaterials. They are used in artificial skins, in soft tissue, and plastic surgery to fill up tissue defects, in surgical sutures, vascular grafts, and corneal replacements (11c).

POLYMERIC BIOMATERIALS EVALUATION

Bulk Characterization

Initial characterizations give information about the composition, structure, and physical and mechanical properties of the investigated polymers to examine if the properties match the specific application requirements, and the reproducibility of batch-to-batch properties. Infrared (IR) spectroscopy and nuclear magnetic resonance (NMR) are often used to analyze the chemical composition and structures of polymers. Crystalline and multiphase structures are usually determined using wide- (WAXS) or small-angle (SAXS) X-ray scattering, or transmission electron microscopy (TEM). Differential scanning calorimetry (DSC), and dynamic mechanical analysis (DMA) can provide thermal transition information of polymers (e.g., T_m and T_g). Furthermore, DMA can provide significant insight into the viscoelastic nature of the polymer. The mechanical properties are determined using the standard ASTM methods. A second level of characterizations needs to be made on the candidate materials to investigate if sterilization and physiological environments' exposure significantly change their properties.

Surface Characterization

Biomaterials contact the body through their surface, and thus the surface chemistry and topography determine the host's response to the materials. The surface chemistry of polymers can be characterized with X-ray photoelectron spectroscopy (XPS), attenuated total reflectance Fourier transform infrared (ATR–FTIR) and secondary ion mass spectroscopy (SIMS). Scanning electron microscopy (SEM) and atomic force microscopy (AFM) are typical techniques to determine the surface topography. A contact angle goniometer is used to measure the wettability (i.e., hydrophilicity) of surfaces.

Biocompatibility Assessment

Biocompatibility tests generally include two levels. The first level tests are biosafety testing, while the second level involves biofunctional testing (28). In biosafety tests, the materials or their extracts are tested to see if they are toxic to cultured cells, cause hemolysis or allergic responses, induce heritable genetic alterations, or tissue necrosis after animal implantation. Those materials passing the first level tests need to be further inspected with the second level tests. This level of testing focuses on the specific functions of a medical device, in which the responses of all the cell and tissue types contacting the device are investigated with both *in vitro* and *in vivo* methods. The functionality of the medical device is also tested during this phase of testing, and changes in material can have significant effects on functionality just as changes in medical device design or function can have significant effects on the biocompatibility of the material.

BIBLIOGRAPHY

Cited References

1. (a) Ikada Y. Polymeric biomaterials in medical systems. (b) Mauliagrawal C. Biodegradable polymers for orthopaedic applications. In: Reis RL, Cohn D, editors. Polymer Based Systems on Tissue Engineering, Replacements and Regeneration. Dordrecht: Kluwer Academic Publishers; 2002.
2. (a) Cooper SL, Visser SA, Hergenrother RW, Lamba NMK. Polymers. (b) Hallab NJ, Jacobs JJ, Katz JL. Orthopedic applications. (c) Kohn J, Abramson S, Langer R. Bioresorbable and bioerodible materials. In: Ratner BD, Hoffman AS, Schoen FJ, Lemons JE, editors. Biomaterials Science: An Introduction to Materials in Medicine. 2nd ed., San Diego: Academic Press; 2004.
3. Ikada Y. Biological Materials. In: Barbucci R, editor. Integrated Biomaterials Science. New York: Kluwer Academic/Plenum Publishers; 2002.
4. Cheng HN, Gross RA. Polymer Biocatalysis and Biomaterials. In: Cheng HN, Gross RA, editors. Polymer Biocatalysis and Biomaterials. Washington, (DC): American Chemical Society; 2005.
5. Rodriguez F, Cohen C, Ober CK, Archer LA. Principles of Polymer Systems, 5th ed., New York: Taylor & Francis; 2003. Chapt 4(a); Chapt 3(b); Chapt 15(c); Chapt 16(d).
6. Young RJ. Introduction to Polymers. London: Chapman and Hall; 1981. Chapt 2.
7. Matyjaszewski K. Comparison and classification of controlled/living radical polymerizations. In: Matyjaszewski K, editor. Controlled/Living Radical Polymerization: Progress in ATRP, NMP, and RAFT. Washington, (DC): American Chemical Society; 2000.
8. Chanda M. Advanced Polymer Chemistry: a Problem Solving Guide. New York: Marcel Dekker; 2000; Chapt 1(a); Chapt 2(b).
9. Askeland DR, Phule PP. The Science and Engineering of Materials. 4th ed., Boston: PWS Publishing Company; 2003; Chapt 15.
10. Bhat SV. Biomaterials. Boston: Kluwer Academic Publishers; 2002; Chapt 12(a); Chapt 8(b); Chapt 5(c); Chapt 9(d); Chapt 6(e).
11. (a) Lee HB, Khang G, Lee JH.. Polymeric biomaterials. (c) Chu CC. Biodegradable polymeric biomaterials: an updated overview. (d) Li ST. Biologic biomaterials: tissue-derived biomaterials (collagen). In: Park JB, Bronzino JD, editors. Biomaterials: Principles and Applications. Boca Raton (FL): CRC Press; 2003.
12. Alger MSM. Polymer Science Dictionary. London: Elsevier Science Publishers; 1989.
13. Birnkraut HW. Synthesis of UHMW-PE. In: Willert H-G, Buchhorn GH, Eyerer P, editors. Ultra-High Molecular Weight Polyethylene as Biomaterial in Orthopedic Surgery. Toronto: Hogrefe & Huber Publishers; 1991.

14. Kurtz SM, Muratoglu OK, Evans M, Edidin AA. Advances in the processing, sterilization of ultra-high molecular weight polyethylene for total joint arthroplasty. Biomaterials 1999;20:1659–1688.
15. Teoh SH, Tang ZG, Hastings GW. Thermoplastic polymers in biomedical applications: Structures, properties and and processing. In: Black J, Hastings G, editors. Handbook of Biomaterial Properties. London: Chapman & Hall; 1998.
16. (a) Ramshaw JAM, Werkmeister JA, Edwards GA. Tissue-polymer composite vascular prostheses. (b) Kowligi RR, Edwin TJ, Banas C, Calcote RW. Vascular grafts: materials, methods, and clinical applications. (c) Planell JA, Vila MM, Gil FJ, Driessens FCM. Acrylic bone cements. (d) Felder G III, Donachy JH, Sr. Fabrication techniques and polymer considerations for the blood contacting components of the Penn State circulatory–assist devices. In: Wise DL, Trantolo DJ, Altobelli DE, Yaszemski MJ, Gresser JD, Schwartz ER, editors. Encyclopedic Handbook of Biomaterials and Bioengineering, Part B: Applications Vol. 2. New York: Marcel Dekker; 1995.
17. (a) Tomita N, Fujita H, Nagata K. Polymers for artificial joints. (b) El-Zaim HS, Heggers JP. Silicones for pharmaceutical and biomedical applications. (c) Kishida A, Ikada Y. Hydrogels for biomedical and pharmaceutical applications. (d) Rokkanen PU. Bioabsorbable polymers for medical applications with an emphasis on orthopedic surgery. (e) Domb AJ, Kumar N, Sheskin T, Bentolila A, Slager J, Teomim D. Biodegradable polymers as drug carrier systems. (f) Miyata T, Uragami T. Biological stimulus-responsive hydrogels. (g) Dumitriu S. Polysaccharides as biomaterials. In: Dumitriu S, editor. Polymeric Biomaterials, 2nd ed. New York: Marcel Dekker; 2002.
18. Lamba NMK, Woodhouse KA, Cooper SL. Polyurethanes in Biomedical Applications, Boca Raton (FL): CRC Press; 1998. Ch. 2.
19. (a) Szycher M, Reed AM. Biodurable polyurethane elastomers. (b) Tiffany JS, Petraitis DJ. Silicone biomaterials. In: Wise DL, Trantolo DJ, Altobelli DE, Yaszemski MJ, Gresser JD, Schwartz ER, editors. Encyclopedic Handbook of Biomaterials and Bioengineering, Part A: Materials (Vol. 2). New York: Marcel Dekker; 1995.
20. (a) Pappas MA, Schmidt CC, Shanbhag AS, Whiteside TA, Rubash HE, Herndon JH. Biological response to particulate debris from nonmetallic orthopedic implants. (b) Gresser JD, Trantolo DJ, Lyons CH, Nagaoka H, Shuster L, Swift RM, Wise DL. In vitro and in vivo release of naltrexone from two types of poly(lactide-co-glycolide) matrices. In: Wise DL, Trantolo DJ, Altobelli DE, Yaszemski MJ, Gresser JD, editors. Human Biomaterials Applications. Totowa (NJ): Humana Press; 1996.
21. Minovic A, Milosev I, Pisot V, Cor A, Antolic V. Isolation of polyacetal wear particles from periprosthetic tissue of isoelastic femoral stems. J Bone Joint Surg 2001; 83B:1182–1190.
22. Hoffman AS, Stayton PS, Bulmus V, Chen G. Really smart bioconjugates of smart polymers and receptor proteins. J Biomed Mater Res 2000;52:577–586.
23. Chandaroy P, Sen A, Hui SW. Temperature-controlled release from liposomes encapsulating Pluronic F127. J Controlled Release 2001;76:27–37.
24. Klemm D, Philipp B, Heinze T, Heinze U, Wagenknecht W. Comprehensive Cellulose Chemistry Vol. 2: Functionalization of Cellulose. Weinheim, Germany: Wiley-VCH; 1998.
25. Laurent TC. The Chemistry, Biology and Medical Applications of Hyaluronan and its Derivative. London: Portland Press; 1998.
26. Kennedy JF, Philips GO, Williams PA. Hyaluronan 2000. Cambridge (England): Woodhead Publishing Limited; 2002.
27. Wainwright SA, Biggs WD, Currey JD, Gosline JM. Mechanical Design in Organism. Princeton (NJ): Princeton University Press; 1982. Chapt 3.
28. Zhang M. Biocompatibility of materials. In: Shi D, editor. Biomaterials and Tissue Engineering, Heidelberg: Springers; 2003. p 83–137.

See also BONE CEMENT, ACRYLIC; CONTACT LENSES; LENSES, INTRAOCULAR; POLYMERIC MATERIALS.

BIOMATERIALS, SURFACE PROPERTIES OF

SALLY L. MCARTHUR
ALEXANDER G. SHARD
University of Sheffield

INTRODUCTION

In the broadest of definitions, biomaterials are nonliving materials that come into contact with biological systems. The point of contact between the two different phases is at the interface, or surface, of the material. It is quite common for the surface of a material to have properties that are not trivially related to the bulk of the material. These differences can arise because of a number of processes, such as surface segregation, surface reactions, contamination, scratching, and phase separation. It should therefore be recognized that the interactions between a biomaterial and the biological medium and in turn, the physical and chemical activity or stability of a medical device, can depend critically upon the properties of the surface.

In general, materials selection for biomedical devices and applications is based on a combination of physical properties, manufacturability, and availability. In many cases, materials are chosen because they have been used previously in medical devices and as such, detailed records of *in vivo* behavior and performance already exist. Due to the costs and time involved with the testing of new materials to meet regulatory standards for safety and efficacy, relatively few materials are currently used in the manufacture of biomedical devices. The most common of these are titanium-based alloys, 316L stainless steels, ultrahigh molecular weight polyethylene (UHMWPE), expanded poly(tetrafluoroethylene) (e-PFTE), poly(ethylene terephthalate) (PET), poly(hydroxyethyl methacrylate) (pHEMA), polyglycolic and lactic acids (PGA and PLA), polystyrene, polyurethanes, hydroxyapatite, alumina, and zirconia.

Of course, mechanical properties are only one of a number of materials characteristics that may be required for biomedical applications. Each biomedical application may desire a range of properties that are directly influenced by the nature of the surface. Specific characteristics and modifications made to biomaterial surfaces include:

1. Orthopedic Devices

Improved wear resistance and frictional properties for joints and bearing surfaces via cross-linking of UHMWPE and the introduction of carbide, nitride and crystalline structures on metallic components.

  Bone conductive coatings for improved osseointegration via implantation of specific chemical species (e.g., Ca, P) into metals and deposition of hydroxyapatite coatings

2. Cardiovascular Devices

  Improved hemocompatibility via diamond-like carbon (DLC) coatings (e.g., mechanical heart valve leaflets) and via the immobilization of biomolecules to promote epithelialization
  Short- and long-term drug delivery via degradable polymeric coatings (e.g., stents).
  Polymeric barrier coatings to prevent transmission of electrical signals and improve corrosion resistance (e.g., pacemaker cases and leads).

3. Diagnostics, Sensors and *in vitro* Applications,

  Reflective coatings for optical sensors.
  Nonfouling coatings to prevent protein and cell attachment and reduce background signal in biological assays and sensors.
  Oriented biomolecule immobilization for DNA, protein, and antibody arrays.
  Topographical and chemical patterning of microfluidic devices and sensors for the control of fluid flow and chemical mixing.

4. Tissue Engineering

  Improved cell proliferation and growth in culture via oxidation of polystyrene to produce a hydrophilic substrate (tissue culture polystyrene, TCPS).
  Immobilization of biological ligands for controlled cell adhesion (e.g., RGD and other cell receptor binding domains).

In this article, we intend to provide a broad overview of the basic properties of surfaces, their interactions with biological systems, and how surfaces can be changed to suit particular biomaterial applications. Of particular importance is the requirement for surface characterization. As stated earlier, differences between surface and bulk properties can arise via a number of different processes. However they arise, it is important to ensure that the surface properties of the material are verified before ascribing any biological effect to the material. To complete this article, we provide an outline of the most commonly employed surface characterization techniques and include references to more detailed texts to aid the interested reader.

PROPERTIES OF SURFACES

One of the most important properties of a surface or interface is that it exhibits free energy. This means that if the surface was extended in some way so that it had a larger area then work would have to be done. If this was not the case, then for fluid interfaces at least, the surface could grow without limit, eventually resulting in a homogenous mixture. The existence of surface energy leads to a tendency for surfaces to contract resulting in a higher pressure on the inside of curved surfaces. Measuring the interfacial energy between liquids and air is relatively trivial, as the surface may be extended without producing a bulk strain. Thus the energy required to extend an area of surface or, more usually, the force of contraction normal to a length of surface can be directly obtained. Liquid surface tensions scale with the strength of intermolecular interactions in the bulk of the liquid, so hydrocarbons typically have surface energies of $\sim 25\ \mathrm{mN \cdot m^{-1}}$, water has $72\ \mathrm{mN \cdot m^{-1}}$ due to hydrogen bonding and the metallic bonding in mercury results in a surface energy of over $470\ \mathrm{mN \cdot m^{-1}}$ (1).

In contrast, the surface energy of solids cannot be obtained directly. There are, however, a variety of methods of estimating it from a series of contact angle experiments and it is found that the surface energies between solids and air are very similar to those of analogous liquids. However, for most biomaterial applications it is the solid–water interfacial energy that is important. One should note that "low energy" hydrophobic surfaces typically have interfacial energies with both air and water of $\sim 30\ \mathrm{mN \cdot m^{-1}}$. Hydrophilic surfaces, such as clean glass or aluminium, can have high surface energies in air, higher than $80\ \mathrm{mN \cdot m^{-1}}$, but have negligibly small interfacial energies with water. The difference between the air and water interfacial energies for glass and aluminium is greater than the surface energy of water, and hence water does not form drops, but completely wets these materials. Protein adsorption, described in detail later, can be thought of as being driven by the minimization of surface energy. A comparison of the surface energies for hydrophilic and hydrophobic materials gives an appreciation of the strength and importance of the hydrophobic interaction, described later, during this process.

Other properties of surfaces that are important are chemistry, mechanical properties, and topology. In the context of a biomaterial, the chemistry of a surface will determine the initial interactions with proteins through ionic, hydrogen bonding, and hydrophobic interactions as well as the promotion of specific interactions by the presence of surface bound ligands. It is important to realize that the surface chemistry of a material may bear little or no resemblance to the bulk chemistry. In many cases, this is due to the presence of thin layers of contaminants that naturally accumulate on the surfaces of all materials. The deliberate alteration of biomaterial surface chemistry is carried out to enhance or inhibit certain properties, usually the alteration of protein adsorption and cell attachment. Whether the surface chemistry is a result of contamination or modification, it is important to specifically characterize the surface to ensure that correlations between biomaterial chemistry and performance are correctly obtained. The mechanical properties of a biomaterial surface are also of some importance, particularly for cellular attachment. It is generally found that cells attach more strongly to rigid substrates and will migrate from soft-to-hard materials. Note that the mechanical properties of some materials, in particular polymers, may be somewhat different at the surface compared to the bulk. It has been observed, for example, that the glass transition temperature of polymers is reduced close to an interface. The topology of a surface is also important as it defines the surface area of the interface, and has been shown to influence cell behavior (2).

The Adsorption of Proteins at Surfaces

One of the most important events that occur in biomaterial applications is the sequestration of proteins from solution to the surface of the material. Proteins are polyamino acids in which, for each protein, there is a predetermined and specific sequence of amino acids. This sequence is termed the primary structure of the protein. The secondary structure consists of a variety of common folding motifs, such as α-helices and β-sheets. The tertiary structure of the protein comprises the folding and packing of the secondary structure into a particular three-dimensional (3D) shape. For most proteins, the tertiary structure creates unique, and often rather small sites of activity that allow the protein to function (e.g., cell-binding domains). In contrast, synthetic macromolecules form random coils because they lack the well-defined structure that allows the strong bonding that occurs between different parts of the protein chain.

When one considers protein adsorption at interfaces, it is common to draw analogies to the adsorption of synthetic macromolecules. While these comparisons are extremely useful, it is important to remember that proteins are capable of site specific and highly selective binding, whereas synthetic macromolecules in general are not. Examples of such selective binding include the much utilized affinity of avidin for biotin and the binding of antigens to antibodies. Protein adsorption occurs primarily due to a number of intermolecular forces. These include ionic and hydrogen bonding and the hydrophobic interaction (3). Although the ionic interaction is rather strong in solid materials, in aqueous media it is diminished due to strong ion–dipole interactions with water, the high dielectric constant of water and the presence of other solvated ions that cause a decrease in the effective range of ionic interactions. Nevertheless, ionic interactions are important at short ranges and can have a strong effect on the rate of adsorption of proteins at surfaces. It is commonly observed, for example, that a protein adsorbs most rapidly to an uncharged surface when it is at its isoelectric point, that is, when it is itself uncharged. The presence of a charged interface can decrease or increase the rate of adsorption depending on whether the protein has a like or an unlike total charge. Furthermore, if the protein has a dipole moment, then it may be possible to influence the orientation of the protein upon adsorption at a charged surface.

Hydrogen bonding is a particularly strong example of a dipole–dipole interaction. A hydrogen atom bound to an electronegative element such as oxygen or nitrogen forms a strong association with a lone pair of electrons on another electronegative atom, which may be part of another molecule. There is no great driving force for the formation of hydrogen bonds in the presence of water, since water very effectively makes such bonds. Without the generation of highly specific geometries of complementary hydrogen donors and acceptors, hydrogen bonding is almost certainly not a major driving force for adsorption of proteins at interfaces.

The "hydrophobic interaction" is something of a misnomer, since the driving force is in fact the formation of hydrogen bonds in water and not the attraction between two hydrophobic species. Water cannot form hydrogen bonds with regions of predominantly hydrocarbon species, whether these are part of a protein or on a surface. The result is that at such an interface water is in a state of higher free energy than if the interface was not present. Hydrocarbons thus tend to aggregate together to minimize the area of contact between themselves and water and lower the free energy of the system as a whole. These interactions are critical to the folding of proteins, with the interior of the protein generally consisting of hydrophobic amino acids and the exterior of hydrophilic amino acids. It is undoubtedly also an important interaction in the adsorption of proteins at interfaces. While the exterior surface of most globular proteins contain few hydrophobic sites, if the protein can unfold upon the surface (denature) then many more such sites become available.

When a surface is exposed to a solution of a single protein it is generally found that adsorption occurs rapidly and in many cases is diffusion limited. It is usual for adsorption to reach a maximum at a single layer with close contact between adsorbed proteins. Following adsorption, the rate of desorption from the surface is extremely slow. Proteins cannot commonly be removed from surfaces simply by changing the protein solution for pure solvent. However, if other proteins are present there may be exchange between adsorbed and solvated proteins. This includes self-exchange, as has been demonstrated by the exchange of unlabelled proteins with their radiolabeled analogues (4). Different proteins can have different affinities for surfaces, so that one protein may adsorb initially because it is in a high solution concentration, but at later times be displaced by other proteins that have higher affinity, but are in low concentrations. This effect is named after Leo Vroman and the classic example is the adsorption of proteins from serum that occurs in the order albumin, fibrinogen, and high molecular weight kininogen. It is also thought that immunoglobulin G adsorbs transiently between albumin and fibrinogen (5). This exchange can take place in a matter of seconds in pure serum, but may take minutes or hours in diluted serum. It is also noted that the amount of protein that can be exchanged in this manner diminishes the longer the protein is in contact with the surface. This indicates that the initial state of adsorption is metastable and that some activation energy barrier needs to be overcome for an adsorbed protein to reach a free energy minimum. It is possible that this energy barrier relates to the unfolding of tertiary or secondary structure and represents a denaturation of the protein.

Although the precise details of protein adsorption are unclear, it is generally agreed that the stability of adsorbed protein layers derives from the large number of contact points possible between a single protein molecule and a surface. Although each individual contact may be weak and temporarily displaced by smaller molecules the probability of breaking enough bonds for the protein to actually desorb is extremely small. The stability of an adsorbed layer is therefore related to both the strength of individual interactions with the surface and the number of interactions. One should expect on this basis that, neglecting the detailed interactions and protein conformation, a high molecular weight protein should displace a low molecular weight protein because it is able to form more bonds to the surface. It is instructive to note that this trend is at least partially followed in the Vroman effect, the exception being high molecular weight kininogen that has a slightly lower molecular weight than fibrinogen.

Cell Behavior at Surfaces

In comparison with protein adsorption, the adhesion of cells to a biomaterial surface is a rather slow process. In standard cell culture, the adsorption and equilibration of proteins at the surface will occur much more rapidly than cellular attachment. The behavior of cells at a surface is thought to be governed by the initial layer of protein. Cells with surfaces via interactions of their transmembrane proteins (e.g., integrins) with proteins in the extracellular matrix. One approach to encourage cell adhesion is to incorporate such specific sequences at the surface of the biomaterial. A variety of suitable peptide sequences have been reported. From fibronectin, the RGD sequence mentioned above and also REDV, which targets integrins found in endothelial cells, but not blood platelets. Laminin contains sequences such as YIGSR and SIKVAV, which may be employed to encourage nerve cell growth (6).

If cell attachment and growth is to be discouraged, then the biomaterial surface should adsorb as few proteins as possible or only adsorb proteins that are not implicated in cellular adhesion. In the first alternative, this is typically achieved by using a hydrogel-like polymer layer, such as grafted chains of polyethylene glycol. These highly hydrated films provide few sites for protein attachment and cell attachment is also strongly discouraged. It is commonly observed that cells attach poorly to hydrophobic surfaces; this may indicate that there is a selective adsorption of proteins that do not contain binding domains for cells. The modification of surfaces to promote and inhibit cell attachment is discussed later in this article.

Once a cell has formed attachment points at a surface it will strengthen these by accumulating integrin receptors in the vicinity of each site. These eventually form a focal adhesion that acts as a connection between the actin cytoskeleton of the cell and the surface. As these adhesive contacts are made the cell spreads upon the surface and will then enter the normal cell cycle. The formation of focal adhesions is critical to the survival of the cell, without sufficient spreading a cell will normally die. There are proteins that trigger signals from the focal adhesion to the cellular interior such as focal adhesion kinase, which may be implicated in this decision making process.

The movement of mammalian cells is achieved by crawling. This involves the myosin driven contraction of actin filaments in the cell to supply the mechanical power, the detachment of focal adhesions at the trailing edge of the cell and the formation of new adhesions at the leading edge (7). Cells will generally move in the direction in which they can make the largest number of focal adhesions. The surface of a biomaterial can thus be tailored to concentrate cells in particular locations.

SURFACE MODIFICATION

In many cases, surface characteristics can be modified by designing the chemical constituents of the materials, for example, surface segregating components in polymer blends to alter frictional properties; or induced during the manufacturing process, for example, the introduction of topography via die and mould design. However, it is not always possible or practical to use these approaches and secondary processing capable of inducing specific surface properties without detrimentally affecting the bulk characteristics is often required.

In broad terms, surface modification techniques can be divided into two categories: those that treat the existing surface and those that result in the addition of a surface coating. As shown in Table 1, there are a number of different surface modification techniques that are currently used in industry or applied to bioengineering research. In this section, we give a brief overview of a number of these techniques, discuss their advantages, and limitations and give some specific examples of their application.

Plasma Treatment and Polymerization

Plasma-based modifications have been applied, with varying degrees of success, to biomaterials and biomedical devices since the early 1960s. Also termed radio frequency glow discharge (rfgd), the process involves the volatilization of a liquid or gaseous “monomer” into an evacuated process chamber. An electric field at rf is applied across the vapor, ionizing a fraction of the molecules and generating electrons, ions, free radicals, photons, and molecules in both ground and excited states, within the gas plasma. When the resultant reactive species impinge on a surface within the plasma zone, they create reactive sites resulting in alteration of the surface chemistry and properties.

There are two classes of glow discharge plasma modification, treatment and Polymerization. Plasma treatment results in the introduction of chemical species or physical changes to the surface of the material. Plasma treatments are often used to etch polymeric, metallic and ceramic surfaces, remove contaminants, and improve adhesion and hydrophilicity (8). Chemical modifications resulting from plasma treatments can also be used as an activation step for graft polymerization. Plasma generated radicals can be used to initiate polymerization of monomers in the liquid or gas phase, resulting in surface -grafted polymer layers. Typically “monomers” used for plasma treatment include oxygen, argon, ammonia, air, and water.

Plasma Polymerization occurs when a plasma is struck in an organic vapor and results in the deposition of a polymeric film from the vapor phase. Excitation of the monomer results in reactive species impinging on a surface within the plasma zone creating reactive sites that are then used for the covalent attachment of other species and subsequent growth of a coating of controllable thickness (typically tens of nanometers). A wide range of monomers can be used to produce plasma polymer coatings suitable

Table 1. Methods and Applications of Surface Modification Commonly Used in Biomedical Devices

Method	Application	References
Plasma polymerization	Organic and inorganic coatings for use as barrier coatings (thermal and chemical). Improved abrasion resistance, electrical and optical properties. Control of chemical functionality, cell and protein adhesion	8,9
Plasma treatment	Introduction of chemical functionality, crosslinking of polymers for improved wear and frictional properties	9,10
Plasma immersion or source ion implantation (PIII)	Wear resistance and improved friction properties for metals ceramics and polymers. Improved biocompatibility	11–13
Radiation techniques [ultraviolet (UV), gamma and laser irradiation]	Polymer grafting, introduction of topographical features and chemical functionality	14–17
Ion implantation	Improved wear and friction properties. Implantation of specific elements can improve cellular integration on polymers and metals	18–20
IBAD	Enhanced cell and tissue compatibility, antimicrobial properties, friction, wear, and chemical stability.	20–22
Polymer grafting	Nonfouling and biomimetic surfaces. Control of hydrophilicity, introduction of chemical functionality. Chemical, thermal, and biologically responsive coatings	23–25
Biomolecule immobilization	Biomimetic surfaces, introduction of specific biological function and activity.	26–29

for biomaterials applications. Table 2 lists some of the most common monomers and their applications. In general, plasma polymers tend to be highly cross-linked and do not reproduce the chemistry of the monomer. In the last 10 years, there has been increasing interest in the production of plasma polymers with the functionality and specific characteristics of their parent monomer. This can range from simple systems for retaining more amine or acid functionality in coatings (30) to more complex cases such as optimizing the protein resistance of poly(ethylene oxide)-like plasma polymers (31) or the production of thermally responsive *N*-isopropylacrylamide (NIPPAm) surfaces (32).

A range of deposition parameters can be used to manipulate the characteristics of a plasma polymer and encourage coating properties that are commensurate with those of a traditionally synthesized polymer. Lower deposition powers, pulsing of the power supply, and copolymerization have all been used to modify the coating properties (30,33,34). The resulting materials have been shown to retain higher monomer functionality and in some cases specific physicochemical properties normally associated with multi-step polymer grafted surfaces (32).

Ion Implantation and Ion-Beam Assisted Deposition

As is the case with plasma techniques discussed previously, the key difference between these two ion-based surface modification techniques is that ion implantation is a surface treatment while ion-beam assisted deposition (IBAD), as the name suggests, results in a surface coating. In both cases ionized species are produced via an ion source and accelerated in an electric field to reach the surface with kiloelectronvolt energies. Parameters affecting the process include beam energy, dose, and current density as well as the nature of the ion species (20).

In polymers, ion impacts and interactions induce modifications of the macromolecular structure through gas evolution, formation of double bonds, chain scissions, and cross-linking over a thickness corresponding to the penetration depth of the ions. Factors such as chain scission and cross-linking obviously have diametrically opposing effects on the properties of the polymeric surface. Generally, manufacturers utilize ion-beam implantation to increase cross-link density, a factor that can improve wear properties at load bearing interfaces and create polymers with improved chemical resistance. In metals and ceramics, ion implantation can be used to induce the formation of new surface phases, surface disorder. The formation of hard-phase nitride, carbide, and oxide precipitates via ion implantation has been used to harden the surfaces of Ti and Ti alloy orthopedic implants, improving their wear resistance (35). The application of specific ion species such as nitrogen and calcium enables the generation of specific chemical

Table 2. Common Plasma Polymerization Monomers and the Coating Properties They Produce

Monomer	Coating Properties and Applications
Organosilanes (silanes and disiloxanes)	Thermal and chemical resistance Specific electrical and optical properties
Fluorine (e.g.) and hydrocarbon (octadiene) containing	Hydrophobic coatings Chemical barrier coatings, non cell adhesive.
Acid containing (acrylic acid)	Hydrophilic coatings
Amine containing (heptylamine, allylamine)	Acid and amine functionality used for polymer and biomolecule immobilization Controlled cell attachment and growth
Ethylene oxide containing (glymes, diethylene glycol vinyl ether)	Nonfouling coatings Controlled protein and cell adhesion

changes at the surface. The bone conductivity, corrosion and wear resistance of Ti alloys have all been shown to improve after calcium and phosphorous ion implantation (35). On polymeric materials, nitrogen ion implantation has been used to induce complex crosslinked surfaces with increased solvent and wear resistance (36), while the incorporation of silver (Ag) ions has been used to impart antimicrobial properties on indwelling catheters (21). Ion-beam assisted deposition, combines ion-beam implantation with physical vapor deposition (PVD), producing a low stress, uniform and adherent coating via interactions of the ions from the beam with the coating atoms (20). Ion-beam assisted deposition (IBAD) has been used to produce a variety of metallic and inorganic coatings on Co–Cr and Ti alloys, alumina, and UHMWPE (37). Titanium alloy coatings have been produced on Co–Cr components to improved cellular integration in orthopedic applications (38) and bone conductivity has been improved on a variety of metallic substrates with the deposition of adherent hydroxyapatite coatings. Commercially, IBAD is used to produce DLC coatings that are chemically inert, optically transparent, have a low friction coefficient, and are extremely hard. These DLC coatings are used to treat the bearing surfaces of orthopedic implants to improve wear and friction properties and reduce the incidence of wear debris (39). On polymeric substrates, IBAD is used to produce adhesive silver coatings for antimicrobial applications (40).

Plasma Immersion Ion Implantation

Plasma immersion ion implantation (PIII) has a critical advantage over the standard ion implantation methods discussed in the previous section: it is not a line of sight technique, a factor that enables the modification of complex shapes commonly found in biomedical applications. Unlike ion implantation, PIII samples are pulse-biased to a high negative potential relative to the chamber wall and surrounded by high density plasma. Ions generated in the plasma are accelerated across the sheath formed around the samples and are implanted into the surface. Gaseous plasmas can be induced using a variety of sources including rf and microwave, and combining these gas plasmas with a metallic plasma allows interface mixing that result in metallic coatings with low intrinsic stress, significantly reducing the risk of coating delamination (12). Plasma immersion ion implantation has been used to surface modify skeletal prosthetic implants with Ti alloy coatings (for cell recruitment) while maintaining the mechanical properties of the Co–Cr substrate (41) and to deposit carbon and Ti–N coatings on both metals and polymers for improved wear and scratch resistance (12).

Wet Chemical Techniques

There is a vast array of wet chemical techniques that can be used to modify the surfaces of biomaterials. In their simplest incarnation, wet chemical routes for surface modification can involve the immersion of a device in a chemical bath to adsorb polymer to the surface. The complexity of the modification increases incrementally through the grafting of polymers to form nonfouling and bioresponsive coatings toward the construction of biomimetic surfaces that attempt to imitate the outer surface of a cell and can contain a range of lipids, proteins, and sugars.

Grafted polymer layers can be used to manipulate both the physical and the chemical characteristics of a surface. Grafting can be achieved via a number of routes including covalent coupling, surface graft polymerization; surface segregation and interpenetration of a substrate. One of the most popular current applications is in the generation of nonfouling surfaces via the immobilization of water-soluble polymers like polyethylene oxide (PEO). While there is considerable debate on the efficacy of these coating, recent reviews on surface modification for nonfouling behavior have detailed the critical roles of polymer molecular weight, graft density, and residual charge on the performance of these types of grafted polymer layers (23,42).

An alternative approach to polymer grafting is the self-assembly of molecules to form monolayers. Self-assembled monolayers (SAMs) can be formed spontaneously via a range of specific molecule–surface interactions. Common systems include alkane thiol on gold or silver and chlorosilanes on hydroxyl-terminated surfaces. By tailoring the headgroup chemistry of the immobilized molecules, surface can be designed with a range of properties. Commercially, these systems are currently used as platforms for biosensors and bioarray technologies (43). The well-defined nature of these systems has resulted in their extensive application in research as model systems for protein and cell–surface interaction studies (42).

Increasing focus on the development of coatings capable of eliciting specific biological responses has seen a significant research focus on the incorporation of peptide sequences, particularly from the receptor-binding domains of adhesion proteins, in order to promote cell adhesion (6,27). In more general terms, there is significant interest in the immobilization of a range of biomolecules. Array and sensor technologies require antibody, protein, and DNA immobilization, while the immobilized proteoglycans such as heparin have been used to the modulate hemocompatibility of biomedical devices (44). As illustrated in Fig. 1, immobilization strategies for biomolecules can be as simple as nonspecific adsorption or as complex as molecular imprinting. The adsorption of biomolecules tends to result in coatings with limited functionality as the molecules are randomly oriented and tend to be desorbed from the surface over time. Covalent immobilization can eliminate problems associated with desorption, but there is often little control over conformation or orientation and thus activity of the biomolecule can be limited. The use of spacer polymer chains or amino acid sequences between the surface and the protein can reduce the denaturation of the molecule. Examples of this type of approach are the site specific modification of proteins with cysteine that enable immobilization of the proteins in specific orientations on gold (45). The success of strategies designed to present biological ligands can also be maximized if the immobilized molecule is coupled to a surface capable of preventing nonspecific adsorption. In general terms, biological response is influenced by the presentation, average density and the spatial distribution of the immobilized molecule



Figure 1. A range of immobilization strategies for biomolecules at interfaces.

(1). One of the most challenging applications for wet chemical surface modification lies in the development of surfaces that borrow from structures observed in Nature. Surfaces that mimic the structure of a cell wall are increasingly sought for use in biosensors and as model systems to further investigate cell, protein, and pharmaceutical interactions. These systems generally consist of a lipid bilayer that may containing a range of different lipids, transmembrane and membrane proteins, and in some cases oligosaccharides. Critically, these structures need to retain their fluidity; molecules need to be able to move within and through the structure in order to maintain their activity and function. The most simple cell mimetic surfaces discussed in the literature have been based on transferring lipid bilayers onto glass substrates. Under these conditions, a thin film of water lubricates the interface between the glass and bilayer and allows free lateral diffusion. These types of bilayers generally have poor long-term stability, show limited transmembrane protein activity, and cannot be transferred through the air–water interface without disrupting the structure (46). An alternative approach lies in either the formation of hybrid bilayers, where the inner leaflet is formed from alkane thiol on gold (47), or the deposition of the lipids on a polymer support (46). Hydrogel layers can also be used and act as a hydrated cushion that is both a self-lubricating and a spacer, creating an area for protein insertion without affecting protein function. At present, there are a number of commercial biosensors that utilize this type of technology for disease diagnosis (48).

SURFACE ANALYSIS

The study of surfaces and coatings is an advanced field and ranges from the investigation of elementary chemical processes on single crystals in ultrahigh vacuum (UHV) to the analysis of rather more “dirty” and real surfaces in engineering applications. The development of techniques suitable for surface science has a long history, the driving force for which has only recently included attempting to understand and control biomaterial surface interactions. Table 3 details some of the more common surface analysis techniques used today in the characterization of biomaterials. The physical principles of all the techniques commonly employed today are well understood and have been for many decades. Many of the approaches described here have their origin in the study of elementary chemical and physical processes, the semiconductor industry, and from engineering disciplines.

When considering the choice of surface analytical tools, it is important to appreciate the questions that require answering. A single technique cannot generally provide a complete picture of the surface characteristics. In this section, a description of the some of the most commonly used techniques is provided with reference to more detailed and extensive reviews. It is important to note that the techniques fall into two classes, those that operate inside a vacuum and those that can directly probe the biomaterial–water interface. While it is obviously preferable to use those techniques that can perform under ambient conditions, in general these techniques are either not as informative or not as surface sensitive as the vacuum techniques. For this reason, the vacuum techniques are commonly utilized to provide a detailed characterization, but in doing so it must always be under the assumption that the surface is the same in vacuum as it is under water. This is a rather large assumption, particularly if the material is able to reorganize itself relatively easily. The surface energy change following immersion in water can be rather large, as indicated above, and in mixed biomaterial phases components that are absent at the surface in vacuum may dominate when the material is immersed in an aqueous environment. There is evidence for this kind of surface reorientation in the contact angle hysteresis of water on some polymers.

Hysteresis is the difference in contact angle between a water contact line advancing or receding across a surface. For some polymers, the advancing angle is high and the receding angle is low, indicating that at the polymer–air interface the polymer is hydrophobic and at the polymer–water interface it is hydrophilic. As long as the surface is flat and homogenous, this is evidence of surface reorganization. For some materials it is possible to reduce the rate of reorganization by cooling. This is typically achieved by hydrating the sample in air, and then freezing the sample in liquid nitrogen prior to entry into the vacuum chamber. The sample needs to be held at low temperature while the ice on the surface sublimes and then vacuum techniques

Table 3. Surface Analysis Techniques Used in the Characterization of Biomaterials

Technique	Sampling Depth/Height (Spatial Resolution)	Information Obtained	References
Ultrahigh Vacuum			
Static secondary ion mass spectrometry	<5 nm (500 Å)	Chemical Spectroscopy and Imaging	49,50
X-ray photoelectron spectroscopy	2–10 nm (5 μm)	Elemental, chemical Spectroscopy and Imaging	51
Ambient Techniques			
Attenuated total reflectance Fourier transform Infrared (ATR/FTIR) spectrometry	> 100 nm (1 μm)	Chemical	52
Contact angle measurement	<1 nm (1 mm)	Surface free energy, wettability	53
Atomic force microscopy (AFM)			54
Imaging	Atomic = 20 μm	Topography, coverage, atomic structure	
Surface force measurement	Å = μm		
		Chemical, conformational, structural	
Ellipsometry	Å = 300 nm	Layer thickness, adsorption kinetics	55,56
Streaming potential measurements/electroosmosis	Not applicable	Electrokinetics	57
Surface plasmon resonance	~300 nm	Adsorbed mass and adsorption kinetics	58

can be applied to the surface, which should not have reorganized from the hydrated state (59).

Vacuum Techniques

Traditional surface analysis techniques are usually based on ultrahigh vacuum instrumentation. One of the reasons for this was that much of the initial interest in the field was concentrated upon extremely clean and often highly reactive surfaces. To maintain the surface in this state during the analysis it is important to prevent undesired gas or vapor molecules sticking to the surface and changing its characteristics. This is only possible in ultrahigh vacuum ($<10^{-9}$ mbar or so). A second important reason is that to study just the surface and eliminate contributions from the bulk of the material it is necessary to use probe species that strongly interact with matter, such as ions and electrons. These cannot penetrate through more than a few atomic layers, and hence provide highly surface sensitive information. However, the detection of such species normally requires that they travel a considerable distance from the surface. At atmospheric pressure the average distance traveled prior to interaction with gaseous species is too short for the detection systems to work. A vacuum of, typically, 10^{-7} mbar or better is required for the techniques described here to operate. In addition, many of the components necessary for the production and detection of probe species can only be operated in vacuum; at atmospheric pressure, they would be irreparably damaged. We will now briefly describe some of the key surface analysis techniques used in the characterization of biomaterials. More detailed information and discussion on the interpretation of these techniques can be found in books by Vickerman (54) and Watts (51).

X-Ray Photoelectron Spectroscopy

During X-ray photoelectron spectroscopy (XPS) analysis, the sample is illuminated with X rays of a particular energy that causes electrons to be emitted from the sample. This phenomenon is called the photoelectric effect and it is generally found that an X-ray photon imparts all of its energy to a single electron during the process. Since the electrons are bound in orbitals of well-defined energy (binding energy) that are characteristic of the material, the outgoing electrons have a kinetic energy that is essentially the difference between the photon and binding energies. For core level electrons, this binding energy is characteristic of the nucleus to which the electron is closely bound. Only those electrons that are generated close to the surface can escape from the sample without loss of energy due to inelastic collisions with other atoms. Thus, by analyzing the number of electrons emitted from the surface as a function of electron kinetic energy it becomes possible to identify the elements present on, or near to, the material surface. As long as the photon energy is significantly larger than the binding energy of the electron, the probability of generating a photoelectron from a core level is independent of the chemical situation of the element. This means that it is possible not only to identify the elements present but, with appropriate sensitivity factors, quantify the relative amounts of each element.

The chemical situation of the element may, however, have an influence on the binding energy of the core level electron. Chemical bonds to different elements may cause some charge to accumulate on the element of interest, this will directly affect the binding energy of the core electrons. This change in the binding energy is termed the “chemical shift” by analogy to nuclear magnetic resonance (NMR) spectroscopy. The appearance of a chemical shift is extremely useful in surface analysis as it can provide information on how the various elements in the surface are bonded to each other. Where the same element is in a range of chemical environments it is often possible to deduce the fraction of atoms in each environment by careful curve fitting of the spectrum. An example of these types of chemical shifts is illustrated in Fig. 2. In this case, there are chemical shifts evident in a high resolution carbon 1*s*



Figure 2. The XPS high resolution C1*s* spectrum of a HEMA contact lens. The figure illustrates the various chemical shifts associated with the chemical bonds in the polymer chain.

(C1*s*) spectrum due to the various chemical bonds present in poly(hydroxyethylmethacrylate), pHEMA, a common soft contact lens material.

The surface sensitivity of XPS is dependent on the angle at which electrons are emitted from the sample. For smooth, flat samples it is possible to enhance the surface sensitivity by analyzing electrons which are emitted at a grazing incidence from the sample. By collecting at a number of different angles it is possible to obtain information on the depth distribution of components close to the material surface. This depth profiling capability is particularly important when thin films and coatings of < 10 nm thickness are being studied.

The XPS has been utilized to chemically characterize biomaterials in four principal areas: identification and characterization of the surface chemistry of bulk polymers; characterization of surface specific modifications; characterization of coatings; detection of biomolecules. Factors that are commonly investigated using XPS include: surface oxidation and reorientation of polymer segments; surface segregation (blooming) of plasticizers, additives, and low molecular weight fragments; adventitious contaminants such as silicones and protein adsorption.

Secondary Ion Mass Spectrometry

The impact of a high kinetic energy (typically 1–100 keV) ion, atom, or molecule causes material to be sputtered from a surface. The origin of the vast majority of ejected species is from the topmost layer of the sample. Therefore analysis of the sputtered fragments can provide information on the composition of the material surface. A small proportion of the ejected atomic and molecular fragments are ionized, these are called the secondary ions. Secondary ion mass spectrometry (SIMS) is the application of mass spectrometry to the secondary ions. Note that SIMS is an ablative, destructive technique and this can be used to advantage in generating a depth profile of layered surfaces. The use of SIMS for depth profiling is termed "dynamic" SIMS and is most often employed in the study of layered materials in which the elemental composition of the layers is of interest, for example, doping levels in semiconductors. It is not possible to obtain more detailed chemical information using dynamic SIMS because of the damage induced by the high energy primary ions. In contrast, "static" SIMS employs a low density, low dose ion bombardment such that the probability of two ion impacts occurring at the same place on the sample is negligibly small ($< 10^{13}$ ions $\cdot$ cm^{-2}). The mass spectrum then contains information that is characteristic of the undamaged surface. This information is particularly useful in the analysis of organic materials, when the normal rules of organic mass spectrometry can be applied to the interpretation of SIMS data. Most modern static SIMS instruments are based on time-of-flight mass analyzers (TOF–SIMS), which have a far greater combined sensitivity and mass resolution than quadrupole or magnetic sector detectors. The probability of ion generation is influenced by a daunting range of factors and thus SIMS is regarded as a nonquantitative technique. However, it is commonly found that in a range of similar materials the characteristic ion intensities are approximately proportional to the concentration of species from which they are generated. With a suitable set of calibration data it is then possible to use SIMS in a quantitative manner. The application of TOF–SIMS in the analysis of biomaterials and biological interfaces has historically revolved around the characterization of polymeric interfaces. This has included the study of degradation pathways for biodegradable polymers, the monitoring of coating chemistries, detection of surface contamination and surface chemical characterization of copolymer systems. The surface sensitivity of TOF–SIMS has lead to its application in the detection and identification of biomolecules adsorbed at interfaces. The process is not without its problems though as the largest ions detected from any protein are the immonium ions ($^{+}NH_2{=}CHR$) from each amino acid (MW<200). As a result of this fragmentation, the identification of proteins is often more like a jigsaw puzzle, where the amino acid fragments have to be pieced together using pattern recognition or multivariate analysis techniques, to identify and quantify the parent molecules (60). These types of statistical analysis are being increasingly used to analyze, compare and reconstruct data collected in TOF–SIMS.

In addition to spectroscopy, TOF–SIMS can be used in an imaging mode to chemically map the surface of a material. There is always a trade off between high special resolution and high mass resolution, but with the advent of liquid metal ion sources (e.g., Ga^{+} and In^{+}), systems are typically capable of spatial resolution of < 10 μm, while retaining atomic mass resolution. As a result there is increasing application of TOF–SIMS for the chemical imaging of a range of biomaterial surfaces. Significantly, developments in ion sources have shown that polyatomic (e.g., Au_3) and cluster ion (C_{60}) sources can significantly improve the molecular ion yield of both biological and polymeric materials. With the development of integrated freeze hydration stages for sample preparation, this has lead to increased activity in the application of TOF–SIMS in the analysis of cell membranes and other hydrated biological systems (49).

AMBIENT TECHNIQUES

Atomic Force Microscopy

Atomic force microscopy (AFM) can be utilized to characterize surfaces via either an imaging or a spectroscopic mode. There are two common methods of imaging utilized in AFM, contact, and tapping mode. Both can be performed in either air or liquid, a factor that makes AFM particularly attractive in biomaterial research. In contact mode, the tip is scraped across the surface, while in tapping mode, the tip is in intermittent contact with the surface and as such, there is limited substrate disturbance. As a result, tapping mode AFM is more common for the characterization of biomaterials and biological surfaces. Common applications of AFM to biomaterial surfaces include: surface topography and coating continuity assessment, measurement and monitoring of coating thickness (see Fig. 3) and phase imaging. The last application is an extension of tapping mode imaging that gives nanometer-scale two-dimensional (2D) information about surface structure. It can be used to locate and characterize the distribution of discrete phases within polymer blends such as polyurethane–urea, and a range of other polymers of biological importance. There is also considerable interest in using AFM to image the surfaces of cells and biomolecules on surfaces (61,62).

Surface Force Measurements

The forces that act between particles and surfaces determine a wide range of interactions. They control the stability of dispersions and emulsions; determine the adhesion of colloids onto surfaces and the adsorption properties of proteins and cells at surfaces. Surface force measurements are used in variety of industries and increasingly there is interest in the application of surface force analysis to biomaterials. with the aim of characterizing protein–protein, cell–protein, protein–surface and cell–surface interactions.

There are a number of techniques that can be used to measure force interactions between surfaces. They are divided into two classes based on the method used to determine surface separation. Absolute surface separation can only be determined using an interferometric technique such as the surface force apparatus (SFA). These techniques are limited by the need for a transparent substrate and specific geometric configuration. In response, noninterferometric techniques have been developed that can employ a wider variety of substrates, and that rely on indirect determination of the surface separation rather than interferometry. One of these is AFM surface force measurement.

Force measurements can be made with an AFM using both a bare tip and a tip modified with a probe particle. If the results from these measurements are to be quantitative, knowledge of the radius of curvature for the probe or tip is critical. While it is possible to measure the nominal radius of a bare AFM tip, the indirect nature of the measurement adds to the error associated with the resulting force calculations (63). The Derjaguin approximation is only valid when the radius is much larger than the surface separation, which is not necessarily the case if an unmodified tip is used. If a colloid probe is utilized, the radius of curvature can be measured easily and accurately using scanning electron microscope (SEM) or optical microscopy.



Figure 3. The AFM tapping mode image of a 40 nm step between coated and uncoated regions on a silicon wafer. The step is produced by masking a section of the sample surface prior to plasma polymerization. Once the coating is deposited, the mask is removed and surface imaged. This enables the plasma polymer thickness to be measured with nm resolution. (Image courtesy of Dr. P.G. Hartley, CSIRO Molecular Science, Australia.)

The zero surface separation for noninterferometric techniques are set at the hard wall encountered when the two surfaces are forced together. Termed the constant compliance regime, this is the region of the force curve in which the displacement of the colloid probe is linear with respect to the surface motion. This assumption of hard wall contact is an inherent limitation of these techniques, particularly if the surface deforms or compresses under pressure, as is often the case with polymer surfaces. The compression of a polymer layer can have a number of effects on the force curve. In the first instance, compression of a dense polymer layer can result in a compliance line mimicking hard wall contact, with a layer of compressed polymer between the probe and the substrate. If the polymer is less densely packed, the probe may displace the material, squeezing the polymer out of the gap between the probe and the surface. This results in discontinuities in the compliance region as the force increases and the probe pushes through the polymer layers (63). As a result, conclusions about absolute layer thickness cannot be inferred from this data.

While XPS is able to characterize the chemistry of a surface in the dry state, surface force measurements are well suited to characterizing the intermolecular forces and stability in a variety of environments. A number of studies have investigated the surface force characteristics of rfgd films, grafted polymer layers, and adsorbed protein films in a variety of media (64). Other studies have used surface force measurements to characterize the interactions of polymer modified surfaces in an attempt to elucidate parameters that control the structure of the polymer layer (64). Surface force techniques have been used to investigate the effects of molecular weight, ionic strength, charge density, and polymer concentration on the interaction forces of adsorbed and grafted polymers layers. Increasingly, strategies to eliminate protein adsorption are based on the characterization and modification of the surfaces and thus the interaction forces that govern protein adsorption (65). A number of theoretical studies have also used surface force interactions as design parameters when modeling polymer coatings capable of resisting protein adsorption (66).

In addition to these standard modes of operation, by chemically modifying the AFM cantilever it is possible to map specific interactions between the tip and the surface. Depending on the type of modification made to the cantilever, a range of interactions can be investigated. With a cantilever modified with a receptor specific integrin, dynamic force spectroscopy can be used to identify and map receptor sites on a cell surface (67). By modifying the cantilever with specific chemical functional groups, differences in frictional properties and the distribution of different phases can be probed where there is no topographical variation (68).

Optical Techniques

The refractive index close to an interface can be measured by a number of optical techniques. The two most commonly employed for this purpose are surface plasmon resonance (SPR) (58) and ellipsometry (55,56). Since proteins have a higher refractive index (~1.55) than water (~1.33) it is possible to monitor the amount of protein adsorption at an interface through a measurement of the refractive index and thickness of the adsorbed layer. These techniques have found utility in a wide range of areas relevant to biomaterials research, such as the study of protein adsorption to biomaterials. ligand–receptor interactions and the dissolution and swelling of polymers. The advantage over traditional approaches such as enzyme linked immunosorbent assay (ELISA), fluorescent labeling or radiolabeling is that the proteins under study do not have to be chemically altered in any way.

The disadavantages of these techniques are that the substrate must be flat and conform to a number of optical requirements for the techniques. Additionally, these techniques cannot directly distinguish between different proteins, since all proteins have roughly equivalent optical densities. To determine the identity of proteins adsorbed from a mixed solution it is necessary to subsequently expose the surface to antibodies specific to each protein of interest. Binding of the antibody can be monitored as an increase in the adsorbed layer thickness, however, this approach is difficult to employ quantitatively as there may be nonspecific and competitive adsorption of the antibody as well as a limited availability of binding sites on the adsorbed target protein.

Surface Plasmon Resonance

A surface plasmon is a collective oscillation of electrons that can be excited in certain metals such as silver and gold. The frequency of this oscillation depends on the refractive index of the dielectric material close to the metal interface. If the metal is a thin film it is possible to excite surface plasmons by reflecting light of a wavelength greater than the thickness of the metal from the reverse side of the film. The ability to cause this excitation depends on the wavelength of light, the refractive index of the material through which the light travels (which remains constant in this geometry) and the angle of reflection. When the conditions are correct, light is absorbed. In the usual set up for surface plasmon resonance (SPR) instruments the light undergoes total internal reflection at the interface and the angle at which light is absorbed is monitored. If there is a change in the refractive index close to the interface then a corresponding shift in the angle at which light is absorbed can be followed. The sensitivity of SPR decreases exponentially in distance from the surface with a decay length of the order of the wavelength of the light. If the layer to be analysed is significantly smaller than the decay length, which is usual for protein adsorption, then it can be assumed that any change in refractive index is proportional to the mass of adsorbed protein.

Ellipsometry

When light is reflected at an oblique angle from a planar surface it commonly undergoes a change in polarization. By analyzing these changes, it is possible to infer both the optical properties and thickness of thin films on the surface. To obtain the most complete characterization, a large number of different wavelengths of light or different angles of incidence must be studied. The measured data is then compared to the expected polarization changes calculated from a model, and parameters in the model changed (such as thickness or refractive index) to find a fit between the two. The sensitivity of ellipsometry is comparable to SPR ($\sim 0.01/\mathrm{g{\cdot}cm^2}$), however, it is able to analyze comparatively thick layers of material.

CONCLUSION

While materials selection for most biomedical devices needs to be based upon bulk properties, in this article we have provided a broad overview of the basic properties of surfaces, and introduced some of the reasons why the surface properties may significantly 3 influence the efficacy of biomaterials and biomedical devices. Surface modification aims to tailor the surface characteristics of a material for a specific application without detrimentally affecting the bulk properties. Throughout this article we have shown how a range of physical, chemical, and biological modifications can be made to surfaces and used to manipulate surface characteristics. Finally, we discussed a range of highly sensitive surface analytical methods that can be utilized to investigate both the nature of an interface and its interactions with biological environments. As is always the case with review articles of this type, it is impossible to give detailed accounts of all of the material being discussed. We have included a range of references (*Reading List*) to aid the reader in further developing their understanding of each of the specific concepts and techniques. Additionally, we have included a list of more general references that cover many of the fundamental concepts discussed within this article.

BIBLIOGRAPHY

Cited References

1. Mittal KL, editor. Contact Angle, Wettability and Adhesion. Utrecht: VSP; 1993.
2. Berry CC, Campbell G, Spadiccino A, Robertson M, Curtis ASG. The influence of microscale topography on fibroblast attachment and motility. Biomaterials 2004;25(26):5781–5788.
3. Andrade JD. Principles of Protein Adsorption. In: Andrade JD, editor. Surfaces and Interfacial Aspects of Biomedical Polymers. Vol. 2: Protein Adsorption. New York: Plenum Press; 1985.
4. Underwood PA, Steele JG. Practical limitations of estimation of protein adsorption to polymer surfaces. J Immunol Methods 1991;142(1):83–94.
5. Leduc CA, Vroman L, Leonard EF. A Mathematical-Model for the Vroman Effect. Ind Eng Chem Res 1995;34(10):3488–3495.
6. Hubbell JA. Bioactive Biomaterials. Curr Opin Biotechnol 1999;10:123–129.
7. Bray D. Cell Movements:From Molecules to Motility. 2nd ed. New York: Garland; 2001. p 372.
8. Chu PK, Chen JY, Wang LP, Huang N. Plasma-surface modification of biomaterials. Mat Sci Eng R 2002;36(5-6): 143–206.
9. Favia P, d'Agostino R. Plasma Treatments and Plasma Depositions of Polymers for Biomedical Applications. Surf Coat Tech 1998;98:1102–1106.
10. Aronsson BO, Lausmaa J, Kasemo B. Glow discharge plasma treatment for surface cleaning and modification of metallic biomaterials. J Biomed Mater Res 1997;35(1):49–73.
11. Mandl S, Rauschenbach B. Plasma immersion ion implantation. New technology for homogeneous modification of the surface of medical implants of complex shapes. Biomed Tech 2000;45(7–8):193–198.
12. Bilek MMM, McKenzie DR, Tarrant RN, Lim SHM, McCulloch DG. Plasma-based ion implantation utilising a cathodic arc plasma. Surf Coat Tech 2002;156(1–3):136–142.
13. Shin GH, Lee YH, Lee JS, Kim YS, Choi WS, Park HJ. Preparation of plastic and biopolymer multilayer films by plasma source ion implantation. J Agric Food Chem 2002;50(16):4608–4614.
14. McPherson TB, Shim HS, Park K. Grafting of PEO to glass, nitinol, and pyrolytic carbon surfaces by gamma irradiation. J Biomed Mater Res 1997;38(4):289–302.
15. Benson RS. Use of radiation in biomaterials science. Nucl Instrum Meth B 2002;191:752–757.
16. Welle A, Gottwald E. UV-based patterning of polymeric substrates for cell culture applications. Biomed Microdevices 2002;4(1):33–41.
17. Zhang F, Kang ET, Neoh KG, Wang P, Tan KL. Surface modification of stainless steel by grafting of poly(ethylene glycol) for reduction in protein adsorption. Biomaterials 2001;22(12):1541–1548.
18. Krupa D, Baszkiewicz J, Kozubowski J, Barcz A, Sobczak J, Bilinski A, Rajchel B. The influence of calcium and/orphosphorus ion implantation on the structure and corrosion resistance of titanium. Vacuum 2001;63(4): 715–719.
19. Braceras I, Alava JI, Onate JI, Brizuela M, Garcia-Luis A, Garagorri N, Viviente JL, de Maeztu MA. Improved osseointegration in ion implantationtreated dental implants. Surf Coat Tech 2002;158:28–32.
20. Cui FZ, Luo ZS. Biomaterials modification by ion-beam processing. Surf Coat Tech 1999;112(1–3):278–285.
21. Bambauer R, Mestres P, Schiel R, Schneidewind JM, Latza R, Bambauer S, Sioshansi P. Surface treated catheters with ion beam based process for blood access. Ther Apher 2000;4(5):342–347.
22. Li DJ, Zhao J, Gu HQ. Hemocompatibility of DLC coatings synthesized by ion beam assisted deposition. Sci China Ser E-Technol Sci 2001;44(4):427–431.
23. Kingshott P, Griesser HJ. Surfaces that resist bioadhesion. Curr Opin Solid St M 1999;4:403–412.
24. Bures P, Huang YB, Oral E, Peppas NA. Surface modifications and molecular imprinting of polymers in medical and pharmaceutical applications. J Control Release 2001;72(1–3):25–33.
25. Kato K, Uchida E, Kang ET, Uyama Y,Ikada Y. Polymer surface with graft chains. Prog Polym Sci 2003;28(2):209–259.
26. Cai KY, Lin SB, Yao KD. Advances in research on surface engineering of biomaterials for tissue engineering. Prog Chem 2001;13(1):56–64.
27. Sakiyama-Elbert SE, Hubbell JA. Functional biomaterials: Design of novel biomaterials. Ann Rev Mater Res 2001; 31:183–201.
28. Massia SP, Stark J. Immobilized RGD peptides on surface-grafted dextran promote biospecific cell attachment. J Biomed Mater Res 2001;56(3):390–399.
29. Whitesides GM, Ostuni E, Takayama S, Jiang X, Ingber DE. Soft Lithography in Biology and Biochemistry. Annu Rev Biomed Eng 2001;3:335–373.
30. Beck AJ, Jones FR, Short RD. Plasma copolymerization as a specific route to the fabrication of new surfaces with controlled amounts of specific chemical functionality. Polymer 1996;37:5537–5539.
31. Shen MC, Martinson L, Wagner MS, Castner DG, Ratner BD, Horbett TA. PEO-like plasma polymerized tetraglyme surface interactions with leukocytes and proteins: in vitro and in vivo studies. J Biomater Sci Polym Ed 2002;13(4):367–390.
32. Pan YV, Wesley RA, Luginbuhl R, Denton DD, Ratner BD. Plasma polymerized *N*-isopropylacrylamide: synthesis and characterization of a smart thermally responsive coating. Biomacromolecules 2001;2(1):32–36.
33. Fraser S, Short RD, Barton D, Bradley JW. A multi-technique investigation of the pulsed plasma and plasma polymers of acrylic acid: Millisecond pulse regime. J Phys Chem B 2002;106(22):5596–5603.
34. Han LCM, Timmons RB. Pulsed-plasma polymerization of 1-vinyl-2- pyrrolidone: Synthesis of a linear polymer. J Polym Sci Pol Chem 1998;36(17):3121–3129.

35. Hanawa T. In vivo metallic biomaterials and surface modification. Mat Sci Eng A-Struct 1999;267(2):260–266.
36. Guzman L, Celva R, Miotello A, Voltolini E, Ferrari F, Adami M. Polymer surface modification by ion implantation and reactive deposition of transparent films. Surf Coat Tech 1998;104:375–379.
37. Cui FZ, Luo QL, Feng J. Highly adhesive hydroxyapatite coatings on titanium alloy formed by ion beam assisted deposition. J Mater Sci Mater M 1997;8:403–405.
38. Howlett CR, Zreiqat H, Wu Y, McFall DW, McKenzie DR. Effect of ion modification of commonly used orthopedic materials on the attachment of human bone-derived cells. J Biomed Mater Res 1999;45(4):345–354.
39. Sioshansi P, Tobin EJ. Surface treatment of biomaterials by ion beam processes. Surf Coat Tech 1996;83(1–3):175–182.
40. Davenas J, Thevenard P, Philippe F, Arnaud MN. Surface implantation treatments to prevent infection complications in short term devices. Biomol Eng 2002;19(2–6):263–268.
41. Leng YX, Chen JY, Zeng ZM, Tian XB, Yang P, Huang N, Zhou ZR, Chu PK. Properties of titanium oxide biomaterials synthesized by titanium plasma immersion ion implantation and reactive ion oxidation. Thin Solid Films 2000;377:573–577.
42. Ostuni E, Chapman RG, Holmlin RE, Takayama S, Whitesides GM. A survey of structure-property relationships of surfaces that resist the adsorption of protein. Langmuir 2001;17:5605–5620.
43. Textor M, Ruiz L, Hofer R, Rossi A, Feldman K, Hahner G, Spencer ND. Structural chemistry of self-assembled monolayers of octadecylphosphoric acid on tantalum oxide surfaces. Langmuir 2000;16(7):3257–3271.
44. Chandy T, Das GS, Wilson RF, Rao GHR. Use of plasma glow for surface-engineering biomolecules to enhance bloodcompatibility of Dacron and PTFE vascular prosthesis. Biomaterials 2000;21(7):699–712.
45. Peluso P, Wilson DS, Do D, Tran H, Venkatasubbaiah M, Quincy D, Heidecker B, Poindexter K, Tolani N, Phelan M, Witte K, Jung LS, Wagner P, Nock S. Optimising antibody Immobilization strategies for the construction of protein microarrays. Anal Biochem 2003;312:113–124.
46. Sackmann E, Tanaka M. Supported membranes on soft polymer cushions: fabrication, characterization and applications. Trends Biotechnol 2000;18:58–64.
47. Plant AL. Supported hybrid bilayer membranes as rugged cell membrane mimics. Langmuir 1999;15(15):5128–5135.
48. Krishna G, Schulte J, Cornell BA, Pace RJ, Osman PD. Tethered bilayer membranes containing ionic reservoirs: Selectivity and conductance. Langmuir 2003;19(6):2294–2305.
49. Winograd N. Prospects or imaging TOF-SIMS: from fundamentals to biotechnology. Appl Surf Sci 2003;203:13–19.
50. Castner DG, Ratner BD. Biomedical surface science: Foundations to frontiers. Surface Sci 2002;500(1–3):28–60.
51. Watts JF, Wolstenholme J. An Introduction to Surface Analysis by XPS and AES. Chichester: John Wiley & Sons; 2003.
52. Chittur K. FTIR/ATR for protein adsorption to biomaterials surfaces. Biomaterials 1998;19:357–369.
53. Adamson AP, Gast AW. Physical Chemistry of Surfaces. New York: John Wiley & Sons; 1997.
54. Vickerman JC, editor. Surface analysis: The Principal Techniques. Chichester: John Wiley & Sons; 1997, p. 457.
55. Elwing H. Protein adsorption and ellipsometry in biomaterials research. Biomaterials 1998;19:397–406.
56. Arwin H. Ellipsometry on thin organic layers of biological interest: characterization and applications. Thin Solid Films 2000;377:48–56.
57. Hunter RJ. Zeta Potential in Colloid Science. London: Academic Press; 1988. p 67.
58. Green RJ, Frazier RA, Shakesheff KM, Davies MC, Roberts CJ, Tendler SJB. Surface plasmon resonance analysis of dynamic biological interactions with biomaterials. Biomaterials 2000;21(18):1823–1835.
59. Lewis KB, Ratner BD. Observation of surface restructuring of polymers using ESCA. J Colloid Interface Sci 1993;159:77–85.
60. Wagner MS, Castner DG. Characterization of adsorbed protein films by time of flight secondary ion mass spectrometry (ToF-SIMS) in conjunction with prinicpal component analysis (PCA). Langmuir 2001;17:4649–4660.
61. Boonaert C, Rouxhet P, Dufrene Y. Surface propaerties of microbial cells probed at the nanometre scale with atomic force microscopy. Surf Interface Anal 2000;30:32–35.
62. Fritz M, Radmacher M, Cleveland JP, Allersma MW, Stewart RJ, Gieselmann R, Janmey P, Schmidt CF, Hansma PK. Imaging globular and filamentous proteins in physiological buffer solutions with tapping mode atomic force microscopy. Langmuir 1995;11:3529–3535.
63. Hartley PG. Farinato R, Dubin P, editors. Measurement of Colloidal Interactions Using the Atomic Force Microscope, in Colloid-Polymer Interactions: From Fundamentals to Practice. New York: John Wiley & Sons; 1999.
64. Hartle PG, McArthur SL, McLean KM, Griesser HJ. Physicochemical properties of polysaccharide coatings based on grafted multilayer assemblies. Langmuir 2002;18(7):2483–2494.
65. Leckband D, Sheth S, Halperin A. Grafted poly(ethylene oxide) brushes as nonfouling surface coatings. J Biomater Sci Polym Ed 1999;10(10):1125–47.
66. Halperin A. Polymer brushes that resist adsorption of model proteins: Design parameters. Langmuir 1999;15:2525–2533.
67. Evans E. Energy landscapes of biomolecular adhesion and receptor anchoring at interfaces explored with dynamic force microscopy. Faraday Discuss 1998;111:1–16.
68. Sun S, Chong KS, Leggett GJ. Nanoscale molecular patterns fabricated by using scanning near-field optical lithography. J Am Chem Soc 2002;124(11):2414–2415.

Reading List

Andrade JD, editor. Surfaces and Interfacial Aspects of Biomedical Polymers. New York: Plenum Press; 1985.

Malmsten M, editor. Biopolymers at Interfaces. New York: Marcel Dekker; 1998/2004.

Castner DG, Ratner BD. Biomedical surface science: Foundations to frontiers. Surface Sci 2002;500(1–3):28–60.

Adamson AW, Gast AP. Physical Chemistry of Surfaces. New York: John Wiley & Sons; 1997.

See also BIOCOMPATIBILITY OF MATERIALS; BIOSURFACE ENGINEERING; MICROSCOPY, SCANNING TUNNELING.

BIOMATERIALS, TESTING AND STRUCTURAL PROPERTIES OF

DONGLU SHI
University of Cincinnati
XUEJUN WEN
Clemson University
Clemson, South Carolina

INTRODUCTION

Tissue transplantation and synthetic devices have been utilized in order to substitute the function of lost or damaged hard tissue, such as bone and tooth. Tissue transplants can be autologous, allogeneic, or xenogeneic. However, the use of autologous tissue involves additional surgery and donor site morbidity while the use of allogeneic or xenogeneic tissue involves the risks of immune rejection and disease transmission. Therefore, synthetic hard tissue implants are very necessary. Metals, ceramics, composites, and even polymers are investigated as candidates for the hard tissue replacements. For heavy loaded applications, such as hip prostheses, metals (e.g., Ti–alloys, Co–Cr), and strong inert ceramics (e.g., alumina, zirconia) are extensively studied. Unfortunately, various problems related to both the metallic materials and the bioinert ceramics, for example, corrosion, elastic modulus mismatch (stress concentration and shielding), and bioinertness (only physical connection with host) with metals, and brittle, elastic modulus mismatch, and bioinertness with bioinert ceramics. For these reasons, bioceramics are showing very promising results in the high bioactivity and the formation of interfacial chemical bond with host tissue, which was called osseointegration (1). So far, several bioactive ceramics have been proposed for hard tissue replacements, hydroxyapatide (HA) and bioactive glasses are the most acceptable materials for hard tissue applications (2). The advantages of bioceramics over inert ceramics and metals allow for developing better hard tissue replacements with the characteristics of bioactive and elastic modulus more close to that of bone (2). On the other hand, the mechanical properties of bioceramics are fairly poor when compared with their replaced natural hard tissues. The poor mechanical properties, especially inside the body aqueous environments, limit their applications to only small, unloaded, and low loaded implants, powders, coatings, composites, porous scaffolds for tissue engineering, and so on. Bioceramic coatings and porous scaffold are showing the most promising results for the future hard tissue replacements (3–5). There are various methods developed to produce HA coatings (3–5). Among these techniques, plasma spraying has widely been used. However, this method is not applicable for deposition HA films onto a porous substrate.

In order to obtain a bone substitute possessing both desirable mechanical properties and bioactivity, two major deposition routes in coating the bioactive HA on a highly porous alumina substrate with the similar range of tensile and compressive strength as natural bone were developed. Coated reticulated bioactive substrates can provide the needed mechanical strength for the replacement of the bear-loading functions. The first one is a suspension method in which the ceramic substrates are first coated with a suspension containing the HA powder followed by a sintering with an appropriate time–temperature cycle to densify the HA coating. The second one is a synthesis route or called thermal deposition.

The techniques of coating uniformly thin layers of bioactive HA onto highly porous alumina substrate, the structural properties, especially the interfaces between the coating and the substrate, and the bioactive behavior of the coated substrate in the simulated body fluid (SBF) will be presented in this article.



Figure 1. Cross-section of reticulated alumina substrate, showing the interconnected porosity.

MATERIALS AND METHODS

Reticulated alumina Al_2O_3 was used as the substrate materials. Figure 1 is the gross morphology of the substrate; and Fig. 2 is the cross-section showing the interconnected pores. The average size of the pores is 500 μm, which are large enough to allow the ingrowth of bone tissue. Substrates were cleaned using ultrasonic cleaner in acetone and dried at 100 °C before applying the coating.

Suspension Method

The coating suspension was made up of finely milled ceramic powders, an organic solvent, and a binder. The binder was used to prevent the precipitation of particles and to provide bonding strength to the coating after drying. One important property of the suspension is its viscosity. Specifically, when the porous substrate was immersed in the coating suspension, the suspension must be fluid enough to enter, fill, and uniformly coat the substrate skeleton. Low viscosity could result in undesirable thin films while highly viscous slurry would block the pore, thus impairing the interconnectivity of the pores. The viscosity



Figure 2. Cross-section of reticulated alumina substrate, showing the interconnected porosity.

Table 1. Sample Group Assignment

Sample	Source and Treatment	SSA, $m^2 \cdot g^{-1}$
HA	Commercial	63.02
HA600	HA heated at 600 °C, 30 min	40.92
HA900	HA heated at 900 °C, 30 min	17.45
SHA700	Synthesized HA heated at 700 °C, 4 h	15.19
SHA800	Synthesized HA heated at 800 °C, 4 h	1.49
SHA900	Synthesized HA heated at 900 °C, 4 h	1.23
No. 1	HA heated at 700 °C, 3.5 h, particle size: 40–100 mesh	24.38
No. 2	HA heated at 700 °C, 3.5 h, particle size: 100–200 mesh	25.70
No. 3	HA heated at 700 °C, 3.5 h, particle size: > 200 mesh	27.02

was controlled by the relative amount of solvent, binder, and particles. The porous substrates were subsequently immersed into the mixture. After the porous substrates were completely infiltrated, they were spun briefly in a high speed centrifuge for removal of excess solution. Coated substrates were dried in an oven at 100 °C. The dried specimens were heated in air to 400 °C for 1 h to burn out the organic binder from suspension. During the burnout process, a slow and controlled heating rate was necessary to avoid bubbling in the coating. Then the samples were subject to sintering at different temperatures. Two types of suspension were developed for coating. One was prepared by suspending HA particles (300 mesh) (Chemat Technology, Inc.) in an organic binder–solvent system without glass sintering aid, glass frits. The other was prepared by partially substitution of HA by sintering aid, glass frits (65%), which have good adhesion to the Al_2O_3 substrate and a weak reaction with HA during firing. The glass frits used in this work were borosilicate glasses containing $\sim 75\%$ of a mixture of SiO_2 and B_2O_3, and 20 wt% alkali metal oxides. After melting, the glass was quenched in water and ground in a ball mill into a glass frit of the desired particle size (325 mesh).

Thermal Deposition

Mixing calcium 2-ethyl hexanoate with bis(2-ethyhexyl) phosphite stoichiometrically in ethanol. The viscosity of the solution was controlled by the quantity of ethanol added. The mixture was stirred for 2 days at room temperature. Then mixture was used to coat porous substrates. The coating method used is the same as used in suspension method described earlier. Coated substrates were air-dried and calcinated up to 1000 °C at a heating rate of 2 °C/min. Then the samples were subject to sintering at different temperatures. For phase analysis purpose, the HA was prepared in the powder form as well through same procedures. Briefly, the solution was open to the air and stirred to vaporize the solvent in chemical hood. Finally, a highly viscous, translucent mixture was obtained and then subject to calcinations at desirable temperatures.

Mechanical strength measurements were carried out on an Instron testing unit. Bars of the porous substrate ($5 \times 5 \times 60$ mm^3) were cut using a diamond saw. Tension tests were performed in three-point bending. Compression tests were made on cylinder-shaped sample of 10-mm height and 23 mm diameter. X-ray diffraction (XRD), Scanning electron microscopy (SEM) with an energy dispersive spectrometer (EDS) was utilized to study the coating structure, surface morphology, and the interface structure. The coating bonding strength was measured through tape test (ASTM D 3359), which was originally designed for organic coatings on metallic substrates. This method was used to find the relative bonding strength. All the tests were performed on dense alumina substrates with one or multilayer HA coatings. Permacel 670 tape (Permacel) was used in the test. After removal from the coating, the tape was examined under a light microscope. Sintering process and chemical bonding of the sintering products were examined using differential thermal analysis (DTA) and Fourier transform infrared spectroscopy (FTIR).

The *in vitro* tests were conducted to evaluate the bioactivity of the synthetic HA produced by thermal deposition method (commercial HA as control). All the samples were tested in the powder form (Table 1). Table 1 summarizes the different treatments used to obtain a variety of crystalline structures in the materials; and also names the samples according to the treatment conditions, such as HA, HA600, HA900, SHA700, SHA800, SHA900, No. 1, No. 2, and No. 3. The HA sample group refers to commercial hydroxyapatite samples. HA600 and HA 900 groups refer to commercial HA samples treated for 30 min under 600 and 900 °C, respectively. The SHA700, SHA800, SHA900 conditions refer to synthesized HA using the thermal deposition method described earlier and heated for 4 h at 700, 800, and 900 °C, respectively. Sample No. 1, No. 2, and No. 3 refer to commercial HA and are heat-treated at 700 °C for 3.5 h and with different specific surface area (SSA). Sample No. 3 has the highest SSA; Sample No. 1 has the lowest SSA; and Sample No. 2 is in the middle. The simulated body fluid (SBF) solution that had ionic concentrations close to human blood plasma, as shown in Table 2, was prepared by dissolving reagent grade NaCl, $NaHCO_3$, KCl, $K_2HPO_4 \cdot 3H_2O$, $MgCl_2 \cdot 3H_2O$, $CaCl_2$, and Na_2SO_4 in ion-exchanged distilled water. The solution was buffered at pH 7.4 with 1 *M* HCl and tris(hydroxymethyl) aminomethane, $(CH_2OH)_3CNH_2$ at 37 °C. Powders were immersed into solution at 1 mg/mL ratio and maintained at 37 °C at periods ranging from 15 min to 9 weeks. The calcium concentrations in the solutions were measured by inductively coupled plasma (ICP). Subsequent to immersion, the solutions were vacuum filtered. The powders were gently rinsed with alcohol, ion-exchanged distilled water and then dried at room temperature. The surface microstructures before and after immersion of SBF solution were analyzed via scanning electron microscope (SEM). Both

Table 2. Ionic Concentration of SBF in Comparison With Those of Human Blood Plasma

	Concentration, m*M*							
	Na^+	K^+	Ca^{2+}	Mg^{2+}	HCO_3^-	Cl^-	HPO_4^{2-}	SO_4^-
Blood plasma	142.0	5.0	2.5	1.5	27.0	103.0	1.0	0.5
SBF	142.0	5.0	2.5	1.5	4.2	147.8	1.0	0.5

XRD and FTIR determined the contents of the phases that were present in the coatings. Measurements were obtained on a Philips X-ray diffractometer with CuK-radiation at 35 kV and 23 mA.

RESULTS

Suspension Method

The phase diagram for anhydrous calcium phosphates (Fig. 3) shows that the liquid phase appears at a temperature $> 1500\,^\circ C$, and presumably the induced liquid could improve the bonding between HA and the Al_2O_3 substrate during sintering. However, such as liquid-enhanced bonding process was not experimentally observed. Meanwhile, XRD analysis of the coating made from HA solution (without glass additive) showed that HA was decomposed, and in turn, the bioactivity of the coating was changed. A high density of cracks was found to exist in the coating. The adherence of the coating to the Al_2O_3 substrate was low and the coating layer could be peeled off by scraping. These results indicated that HA solution without sintering aid, such as glass frits, was not suitable for this particular application.

Using the sintering aid, glass frits, a well-bonded HA coating was produced. Figures 4–6 are SEM photographs of the surfaces and interfaces of the coatings made from solution with glass frits. As is apparent from Figs. 5 and 6, the glass–HA ceramic layer is firmly attached to the alumina substrate. An average coating thickness is 15 μm. The interfacial strength between the coating and the



Figure 3. Phase diagram of the system CaO–P_2O_5, indicating the appearance of the liquid phase at high temperatures.



Figure 4. The SEM photograph of the coated surface.



Figure 5. The SEM photograph of the coating interface for dense alumina. The interface is indicated by arrows.



Figure 6. The SEM photograph of the coating interface for porous alumina. The interface is indicated by arrows.



Figure 7. Aluminum content profile along the interface. The solid line is a guide to the eye.

substrate depends on the adherence of the glass to the Al_2O_3. Figure 7 is the aluminum compositional profile across the interface. The data showed that the aluminum concentration decreased when scanning from the substrate to the outer surface of the coating. It was concluded that aluminum ions diffused during sintering, and consequently bonded the glass to the alumina substrate by ion diffusion. This diffusion bonding is attributed to the formation of a eutectic compound at the interface during the sintering, and thus ensures the strong bonding between the coating and the substrate.

The above results indicate that the development of glass frits is essential for having an excellent adhesion of HA coating to the alumina substrate. Great efforts were therefore made in the preparation of the glass frits. As a sintering aid, the glass must wet the substrate and HA, and its melting point should be lower than the decomposing temperature of HA (1300 °C). Furthermore, for successful coating, optimizing the coefficient of thermal expansion of the glass to match the substrate is critical. It has been known that the mismatch in expansion coefficients between the coating and the substrate materials will give rise to interfacial stress that weakens the bonding strength or leads to the cracking and spalling of the coating. The magnitude of this stress is proportional to the difference between the thermal expansion coefficients of the coating and the substrate. The expansion coefficient of HA ($13.3\times10^{-6}/^{\circ}C$) is relatively higher than that of alumina ($8.0\times10^{-6}/^{\circ}C$). The expansion coefficient of the selected glass should then be an intermediate one to reduce this difference. Another important aspect of the glass is chemical durability. For biological applications, it is essential for glass to be nontoxic and stable in the body fluid. The dissolution of the glass will lead to the degradation of the coating. The HA particles will escape from the coating, and this will have an extremely negative effect, such as interfacial loosening and tissue inflammation, on the bone regeneration. The optimal properties of the glass can be achieved by adjusting the glass compositions. The glass selected in this work was borosilicate glass. Its expansion coefficient is compatible with that of Al_2O_3 substrate. No crack was found in the coating (Fig. 4). The XRD pattern of the coating (Fig. 8) shows that there is no negative reaction between the glass and HA. Figure 8 is a typical HA diffraction pattern. Mechanical properties of HA-coated reticulated alumina are ~ 7–10.35 MPa for compressive strength and 5–8 MPa for tensile strength. Compared to previously reported porous materials, such as porous HA (1.3 MPa for compressive strength and 2.5 MPa for tensile strength) and coralline ceramic (5.8 MPa for compressive strength and 1.3 MPa for tensile strength) (6), a substantial increase in strength was obtained. These values are comparable to those of cancellous bone (2–12 MPa for compressive strength and 10–20 for tensile strength) (2). Some much stronger substrate materials, such as fiber reinforced composites, are excellent candidates for the HA coating using the developed approaches discussed in this article. The mechanical properties of the substrate can also be significantly improved by other ceramics routes. In addition, after bone ingrowth, the strength of the implant (bone composites) will be expected to further increase by a factor of 2–7 as previously demonstrated (7).



Figure 8. The XRD spectra showing a typical HA pattern of the coating surface.

Thermal Deposition Method

Figure 9 shows the FTIR spectra of an unfired sample and samples fired at 500, 600, 700, and 900 °C. According to standard IR transmission spectra, peaks observed at 3573 and 631 cm^{-1} are assigned to OH stretching and librational modes. Peaks ~600 and 1100 cm^{-1} are due to the bending and stretching modes of PO bonds in the phosphate groups (8). These are characteristic peaks of HA. At a sintering temperature of 500 °C, PO bonds formed, but hydroxyl groups were not detected. Compared with the spectra of the unfired sample, most organic groups were burned out by this temperature. At 600 °C, all the characteristic lines of HA were recorded, but some organic residual could still be seen. At 700 °C and higher the peak positions match all those of standard HA, and the organic groups were not detectable.

Figure 10 shows the XRD spectra of HA sintered at different temperatures in the range of 600–900 °C. The results of the XRD are quite consistent with that of the FTIR. The crystalline phase started to form at 600 °C, and



Figure 9. The FTIR spectra of HA-coated samples sintered for 4 h at the temperature indicated (thermal deposition).

all peaks were attributed to the HA phase. According to the Scherrer equation,

$$\Delta(2\theta) = K\lambda/D \tag{1}$$

where D is the crystallite dimension; K is the Scherer constant (here $K = 0.9$); is the X-ray wavelength in angstroms; Δ(2) is the true broadening of the diffraction peak at half-maximum intensity. The crystallite size is inversely proportional to the peak width. The broadening of peaks was evident at lower sintering temperatures, indicating the initial state of crystal formation. At higher sintering temperatures, the sharpening of peaks evidenced the growth of crystals. The peak shift could also be noted by comparing it with the standard XRD spectra of HA. At lower temperatures the shift was considerable, suggesting great lattice distortion.



Figure 10. The XRD spectra of HA samples sintered at the temperatures indicated.



Figure 11. The DTA profile of the HA-coated sample showing a reaction near 300 °C.

Monitoring the sintering process and the evolution of chemical bonds is important in determining the bioactivity of the sintered products. The material with more lattice defects would be expected to be more reactive (2). This assumption will be experimentally verified later in *in vitro* tests. The high temperature and long sintering time will result in well-crystallized products. Therefore, to enhance the bioactivity, low temperature and short sintering time is preferred. It is critical to find an optimal sintering procedure so that the sintered HA is poorly crystallized but with no organic residuals. The DTA profile (Fig. 11) shows that burn-out of organic residuals occurs over the temperature range of 300–350 °C. In the current work, the samples were baked at 500 °C to burn out the organic groups. At this temperature, the structure of the sample is amorphous and most of the organic groups can be easily removed. This procedure will be helpful in eliminating residual carbon in the coating. Without this treatment, some organics could be incorporated in the final crystal lattice. It was found that the carbon disappeared at much lower temperatures than those samples treated in a rapid sintering process because most organic groups were not burned out at low temperatures. Therefore, a higher temperature is needed to remove them. However, the reactivity of HA is considerably reduced. It should be noted that the removal of the organic residue is not only related to the microstructure, but also to the macrostate of the samples. For example, for a thick and dense coating, a high temperature is needed to remove the residual carbon.

The bonding strength between the HA coating and the substrate was determined using the tape test. No peeling of the coating film was observed for all samples, indicating a strong bonding between the HA coating and the substrate. Figure 12 is the SEM micrographs showing the surfaces of the HA coating on dense alumina. As can be seen in this figure, the coating is fairly porous, which contributes to the bioactivity when immersed in SBF. Figure 13 is an SEM image of HA-coated reticulated alumina with significant open pores in the matrix. Figure 13b is the X-ray map recorded with Ca K_α lines for coated porous alumina. As can be seen in Fig. 13b, the distribution of calcium demonstrated that HA is uniformly coated on the skeleton of the



Figure 12. The SEM photographs showing the coated surface for a dense alumina substrate.



Figure 13. The SEM photographs showing (a) porous alumina substrate and (b) an X-ray map recorded with Ca K_α lines.

substrate. Figure 14 is the SEM micrograph showing the interface between the HA coating and the substrate. The coating thickness was $\sim 1\ \mu$m, which can also be altered by a second or third coating.

Bioactivity Test

Due to bioactivity of HA, dissolution occurs after the sample is immersed in SBF. Consequently, some of the elements such as calcium in the solution are expected to change. The elemental-concentration changes of calcium in the SBF solution as a function of time are given in Figs. 15,16. As can be seen in Fig. 15, both HA and HA600 exhibit an immediate uptake of the Ca concentration. Initially, there is a high rate of ion uptake, suggesting the formation of a new phase on the HA surface in supersaturated solution. After 24 h, with the depletion of supersaturation, the reaction proceeds at a lower rate of uptake. For HA900, there is an induction time of 60 min prior to a detectable decrease in Ca concentration, and the initial rate of Ca uptake is much lower than those of HA and HA600. The SHA700 behaves similarly to HA and HA600 with a slow reaction rate, as can be seen in Fig. 16. However, the reaction behaviors of SHA800 and SHA900 significantly differ from the HA samples. During the first hour, an increase of Ca concentration was measured, indicating that dissolution of SHA800 and SHA900 has surpassed the new phase formation. Note that the rise in supersaturation for SHA900 is greater than that for SHA800. The ion uptake takes place after this initial dissolution. Another difference between HA and SHA series is that the latter took longer to reach the solid–solution equilibrium stage, clearly indicating a slower reaction rate in the HA series. These results suggest that the dissolution and precipitation rates are



Figure 14. The SEM photograph showing the interface between the HA coating and the dense alumina substrate.



Figure 15. The Ca concentration in SBF versus immersion time for the HA group sintered at temperature indicated.



Figure 16. The Ca concentration in SBF versus immersion time for the SHA group sintered at temperature indicated.



Figure 18. Initial reaction rate versus specific area for the samples showing in Fig. 17.

critically dependent on the crystal structures developed in the HA samples.

Figure 17 represents the Ca concentration in the solution as a function of immersion time for samples Nos. 1, 2, and 3. All these samples are commercial HA heat treated at 700 °C for 30 min. Therefore, these samples are of the same structural crystallinity, but with different specific surface areas. Sample No. 3 has the highest SSA; Sample No. 1 has the lowest SSA; and Sample No. 2 is in the middle. They were tested at a ratio of 1 mg · mL^{-1} SBF. It is apparent in Fig. 17 that the rates of precipitation are highly dependent on the surface area. From these kinetic curves, the initial rate of precipitation, R_0, was determined by the slope of the first two data points. As shown in Fig. 18, there is a linear relationship between the initial precipitation rate and the surface area.

Figure 19 is a plot of Ca concentration versus immersion time for HA, HA600, SHA800, and SHA900. Samples of each group have been selected to have the same surface area. As can be seen, the initial rates of HAs and SHAs separate into two branches. The HA group exhibits an initial gradual decrease, while that of SHA group increases quite rapidly. However, as can also be seen in this figure, calcium concentration of SHA800 initially increases, but reaches a peak at 3 h, and thereafter decreases. In SHA900, although with a different rate, the calcium concentration always increases up to 9 h. Therefore, it can be concluded that the specific surface area is not the only factor that affects the reaction behavior of various HA samples. As discussed later, the degree of crystillinity in fact plays an even more important role in the reaction rates. The SHA700 sample behaves similarly to HA and HA600 with a slow reaction rate as can be seen in (Fig. 19). However, the reaction behaviors of SHA800 and SHA900 significantly differ from the HA samples. During the first hour, an increase of Ca concentration was measured indicating that dissolution of SHA800 and SHA900 has surpassed the new phase formation. It is noted that the rise in super-



Figure 17. The Ca concentration in the solution as a function of immersion time for samples No. 1, No. 2, and No. 3.



Figure 19. The Ca concentration versus immersion time for some of the typical HA and SHA samples.



Figure 20. The SEM photograph showing the surface morphology of the SHA700 immersed in SBF for 1 week.

saturation for SHA900 is greater than that for SHA800. The ion uptake takes place after this initial dissolution. Another difference between HA and SHA series is that the latter took longer time to reach the solid–solution equilibrium stage, clearly indicating a slower reaction rate in the HA series. These results suggest that the dissolution and precipitation rates are critically dependent on the crystal structures developed in the HA samples.

Figures 20 and 21 are surfaces of SHA700 and SHA900 coatings after immersion in SBF for 1 week and 9 weeks, respectively. As can be seen, the morphology of these two surfaces is quite different. The SHA700 coating is fully converted to flake shape with an average diameter of 1–10 μm. The surface of the flakes exhibits fine, needle-like structures within 1 week, which have been identified to be HCA by IR analysis. For SHA900 coating, after 9 weeks of immersion in SBF, a layer of precipitation has been observed under high magnification, which is shown to be amorphous or poorly crystallized new phase instead of HCA.



Figure 21. The SEM photograph showing the surface morphology of the SHA900 immersed in SBF for 9 weeks.

Figure 22 shows the FTIR spectra of HA and SHA samples after immersion in SBF at time periods up to 1 week. The absorption bands at 1460 cm^{-1} (high C=O region) and 872 cm^{-1} (low CO region) are characteristic features of HCA (8). As can be seen from spectrum of HA (Fig. 22a), these bands became significantly greater after 76 h of immersion indicating an increase in carbonate content. A gradual reduction of the splitting of the major PO_4^{3-} absorption bands (1100–1000 and 600–550 cm^{-1}) with immersion time is also observed, suggesting the formation of amorphous or fine, poorly crystallized new phases. For HA900, a broad band appears in the high energy C=O region (Fig. 22b). However, the low energy C=O band at 872 cm^{-1} is not recorded. At the same time, a gradual reduction of the splitting of the major PO_4^{3-} bands is observed, indicating again the formation of amorphous or fine, poorly crystallized new phases. The HCA phase cannot be identified from these weak bands, and it is likely that some intermediate phases other than HCA have formed. The HCA peaks have appeared in the spectra of SHA700 within 7 days (Fig. 22c). A time-dependent increase in the carbonate band intensities accompanied by a reduction of splitting of the major PO_4^{3-} bands is again recorded. Similar changes have occurred in the spectra of immersed SHA800 (Fig. 22d). However, no characteristic HCA peaks are recorded for SHA900 up to 3 weeks, only a broad band has appeared in the high energy C=O region (Fig. 22c). This trend seems to indicate that the reactivity of HA is considerably reduced at higher temperatures.

DISCUSSION

Structural Effects

The results indicate that *in vitro* behavior of the HA coatings is strongly affected by the structural characteristics induced by heat treatment. The SBF used in this work represents physiological ion concentration in human body, and it is supersaturated with respect to HA. In this chemical environment, HA is the most stable phase among all the calcium phosphate phases, thus the HCA formation is thermodynamically possible. However, only HA, HA600, and SHA700 have led to immediate Ca ions uptake. The HA900, SHA800, and SHA900 samples show a partial dissolution prior to precipitation. The difference in the dissolution ability of the HA samples is not the only factor in bioactivity. Figure 10 shows XRD spectra of HA sintered at different temperatures in the range of 600–900 °C. The structural evolution begins from an amorphous state in the commercial HA. Crystalline phase started to form at 600 °C, and all peaks were attributed to the HA phase. In addition, relative peak intensities are in agreement with the expected values for HA. Therefore, it can be decided that the structure consists primarily of crystalline HA, no additional peaks were observed to appear at any firing temperatures. However, the peak shift could be noted by comparing with the standard XRD spectra of HA. At lower temperatures, the shift was considerable suggesting great lattice distortion. The breadth of the peaks was used as an indicator of crystal dimension in the direction perpendicular to the diffracting plane hkl. The crystal size D is



Figure 22. The FTIR spectra of HA and SHA samples after immersion in SBF for the time indicated.

inversely proportional to the peak breadth according to the Scherer equation. The contribution to the peak breadth from instrumental broadening was determined to be ~0.12 °C (0.002 rad), independent of 2θ. This amount subtracted from the total experimental width is the value of true broadening, assuming the two contributions add linearly. The peak breadth (D002) is given as a function of temperature in (Fig. 23). It can be seen that the peak breadth decreases with sintering temperature, indicating that the crystal size increases with increasing sintering temperature, from 600 to 900 °C. On the basis of above analysis, the important difference with annealing temperature was the size of the individual crystals and the amount of crystal defects.

It is possible that the crystal growth rate is controlled by more than one of the elementary rate controlling mechanisms. The rate controlling process can change depending on particle size, solution concentration, and surface properties of the crystallites. The mechanisms of crystal growth are usually interpreted from measured reaction rates at different driving forces or from the activation energies of reactions. It is common practice to fit the data to an empirical rate law, which is represented by simple empirical kinetics (9):

$$R_g = k_g s \sigma^n \qquad (2)$$

where k_g is the rate constant for crystal growth, s is a function of the total number of available growth sites, is the degree of supersaturation, and n is the effective order of reaction. A broad empirical test for growth mechanism can be achieved from a logarithmic plot of Eq. 2. From the n value, the probable mechanism can be deduced. It is possible that the crystal growth rate is controlled by more than one of the elementary rate controlling mechanisms listed above. Under these circumstances, the rate-limiting steps are dependent on the jump frequency of lattice ions: (*1*) through the solution for mass transport control; (*2*) to the crystal surface for adsorption control, or (*3*) along the crystal surface or into a crystal lattice kink site for spiral and polynuclear control. The rate controlling process can change depending on particle size, solution concentration, and surface properties of the crystallites. A broad empirical



Figure 23. The X-ray diffraction peak breadth versus processing temperature for the HA synthesized in this study.

test for growth mechanism can be achieved by plotting the data according to Eq. 2. An effective order reaction in the range $0 < n < 1.2$, $n \sim 2$, or $n > 2.5$ indicates that the rate controlling process is one of adsorption and /or mass transport, surface spiral, or polynucleation, respectively (9). Experimentally, it is found that the growth rates of the calcium phosphates are insensitive to changes in fluid dynamics indicating surface controlling mechanisms rather than mass transport of ions to the crystal surfaces. A dynamic fluid may effect the growth rate, but not in a pronounced fashion. However, in our experiment, we found the growth to be insensitive. But we have no comparison of growth rates in both static and dynamic fluids.

Temperature Dependence of Activation Energy

Activation energies, obtained from experiments at different temperatures, can be used to differentiate between volume diffusion and surface controlled processes. The activation energy for volume diffusion, reflecting the temperature dependence of the diffusion coefficient, usually lies between 16 and 20 $\text{kJ} \cdot \text{mol}^{-1}$, while for a surface reaction the value may be in excess of 35 $\text{kJ} \cdot \text{mol}^{-1}$. If a reaction has activation energy of < 20 $\text{kJ} \cdot \text{mol}^{-1}$, it is safe to assume that it is overwhelmingly controlled by volume diffusion. However, if the activation energy is higher than 35 $\text{kJ} \cdot \text{mol}^{-1}$, it is quite certain that an adsorption process predominates. In all other cases, both adsorption and volume diffusion mechanisms may participate for a first-order reaction (10).

Figure 17 represents the Ca concentration in solutions as a function of immersion time at different surface areas. These samples were the same kind of powders to ensure that they have the same crystal structure and surface morphology; while the ratio of surface area to volume of SBF was different. It is apparent in Fig. 17 that the rates of precipitation were highly dependent on the surface area. Based on the empirical kinetics in Eq. 2, to build a relationship between the reaction rate R_g and surface area s, the degree of supersaturation σ should be kept at a constant value. The corresponding reaction rates were calculated by a simple fitting procedure from the above kinetic plots. As shown in Fig. 18, there was a linear relationship between the precipitation rates and the total surface area, which is in agreement with the above empirical kinetics equation. This result also showed that crystallization occurred only on the added seed materials without any secondary nucleation or spontaneous precipitation. Furthermore, the advantage of porous bioceramics over dense bioceramics was proved by this relationship.

The initial precipitation rate was not used here because of the following considerations. First, the empirical fitting procedure used to calculate R_0 is greatly affected by the slower rates occurring after the initial fast stage of the precipitation process. Thus, the fitting data could not represent the true initial rate. Second, initial rate was a complicated factor. Rapid adjustment of surface composition usually happened when the solids were introduced into the growth or dissolution media. In the case of HA, initial uptaking surges were observed, which might be attributed to calcium ion adsorption. Therefore, considerable uncertainties can arise if too much emphasis is placed upon initial rates of reaction.

Another point needed to be noted was that in this test, the different surface areas were not originated from the distribution of particle sizes, considering that different particle sizes might bring in the factor of surface morphology, which has great influence on the reaction rate. The effect of particle size would be demonstrated later. In the current method, the same powders were used, so that the factor of morphology was eliminated and a linear relationship was obtained.

The particles of different sizes behaved differently under the same surface area to volume (SA/V) test conditions. When comparing the 40–100-mesh and < 200-mesh particles at SA/V of $0.02\ \text{m}^2 \cdot \text{mL}^{-1}$, it is apparent that the Ca adsorption rate is slower for the smaller particles. This may be attributed to physical differences such as the radius of curvature and surface roughness.

Figure 19 is a plot of Ca concentration verses immersion time for HA, HA600, and SHA800, SHA900. Samples of each group were tested under the same SA/V ratio. As can be seen, the initial rate of HA was greater than that of HA600; the behavior of SHA800 differed from the one of SHA900. Therefore, it is concluded that the specific surface area is not the only reason that affects the reaction behavior of various HA powders, the degree of crystallinity also plays an important role in their reaction rates.

Chemical reactions, specifically in this case, the process of nucleation and crystal growth from solution, is described as an activated process with temperature, which is represented by the following relationship:

$$\text{rate} \propto \exp\left(-\frac{E_a}{kT}\right) \tag{3}$$

where E_a is the activation energy, so that reaction rate increases exponentially with temperature increase. The reaction rate constant K is related to temperature by an Arrhenius equation:

$$K = K_0 \exp\left(-\frac{E_a}{kT}\right) \tag{4}$$

By keeping σ at a constant value, plot $\ln R$ versus $1/T$, the slope of the curve will be E_a/k, and consequently E_a can be calculated.

According to the procedures described above, the activation energy for HA, HA600, HA900, and SHA700 was calculated. The parameter σ was selected at $\Delta\text{Ca} = -8\text{m}M$ for all the reaction temperatures. The computed activation energy was listed in Table 3. The above results showed that the activation energy increased with the sintering temperature for HA powders. The activation energy of synthesized HA700 was much higher than those of HA and HA600.

In Vitro Biochemistry Behavior of Hydroxyapatite

The formation of biological apatite on the surface of implanted synthetic calcium phosphate ceramics goes

Table 3. Activation Energies for the Samples Indicated

Samples	Activation energy, $\text{kJ} \cdot \text{mol}^{-1}$
HA	66.3
HA600	80.3
HA900	172.7
SHA700	130.4

through a sequence of chemical reactions. It has been shown that the reaction rate *in vitro* appears to correlate with the rate of apatite mineral formation *in vivo*.

Therefore, the laboratory observations can be projected to the *in vivo* situation. The *in vitro* behavior of bioceramics is determined by its stability at ambient and body temperatures. Many factors have significant influence on their stability, including the pH and supersaturation of the solution, crystallinity, structure defects, and porosity of the material (11,12). Driessens (13) showed that, among the phases composed of calcium and phosphate, hydroxyapatite is the most stable at room temperature when in contact with SBF, which was used to represent the ionic concentrations of plasma. Generally, SBF will initiate a partial dissolution of the HA material causing the release of Ca^{2+}, $HPO_4{}^{2-}$, and $PO_4{}^{3-}$, and increasing the supersaturation of the microenvironment with respect to HA phase that is stable in this environment. Following this initial dissolution is the reprecipitation. Carbonate ions, together with other electrolytes, which are from the biological fluids, become incorporated in the new apatite microcrystals forming on the surfaces of the HA.

Since any clinical use of calcium phosphate bioceramics involves contact with water, it is important to understand the stability of HA in the presence of water at ambient temperatures. As Driessens showed (13), there were only two classes of calcium phosphate materials that were stable at room temperature when in contact with aqueous solution. Temperature, ionic strength, and pH are major parameters influencing the stability of calcium phosphate. In the body, temperature and ion strength are constant, therefore, the pH value at the local tissue determines which form of calcium phosphate is the most stable. At a $pH < 4.2$, the component $CaHPO_4{\cdot}2H_2O$ was the most stable, while at higher pH (>4.2), HA was the stable phase. However, HA does not form at the first place. Other mineral phases such as dicalcium phosphate dihydrate (DCPD), octacalcium phosphate (OCP), and amorphous tricalcium phosphate (TCP) form as precursor phases that transform to HA.

Therefore, in this *in vitro* test, at biological pH value, only HA or its precursor phase can be found in contact with SBF. It is believed that synthetic HA ceramic surfaces can be transformed to biological apatite through a set of reactions including dissolution, precipitation, and ion exchange. Following the introduction of HA to SBF, a partial dissolution of the surface is initiated causing the release of Ca^{2+}, $HPO_4{}^{2-}$, and $PO_4{}^{3-}$, which increases the supersaturation of the microenvironment with respect to the stable (HA) phase. Carbonated apatite can form using the calcium and phosphate ions released from partially dissolving ceramic HA and from the biological fluids that contain other electrolytes, such as $CO_3{}^{2-}$ and Mg^{2+}. These become incorporated in the new CO_3-apatite microcrystals forming on the surfaces of ceramic HA crystals. The *in vitro* reactivity of HA is governed by a number of factors, which can be considered from the two aspects: *in vitro* environment and properties of HA material.

CONCLUSIONS

In order to produce highly strengthened porous bioactive materials for bone substitutes, suspension method and thermal deposition method, were employed to coat the inner-pore surfaces of a porous ceramic substrate. A thin layer of HA has been uniformly coated onto inner-pore surfaces of reticulated alumina substrates. The *in vitro* bioactivity of HA coatings was found to be strongly affected by structure characteristics, which are a combination of crystallinity and specific surface area. The bioactivity is reduced at a higher degree of crystallinity, which is likely related to the higher driving force for the formation of a new phase, and the reaction rate was proportional to the surface area. The surface morphology and HA treating temperature also have a direct affect on the reaction rates of the HA coatings. The calcium absorption rate is slower for smaller particles; this could be attributed to physical differences including radius of curvature and surface roughness. The activation energy increased with the heat-treatment temperature for HA powders.

BIBLIOGRAPHY

Cited References

1. Shinzato S, et al. Bioactive bone cement: Effect of silane treatment on mechanical properties and osteoconductivity. J Biomed Mater Res 2001;55(3):277–284.
2. Hench LL. Introduction to Bioceramics. Singapore: World Scientific; 1993. p 139–180.
3. Barth E, Hero H. Bioactive glass ceramic on titanium substrate: the effect of molybdenum as an intermediate bond coating. Biomaterials 1986;7(4):273–276.
4. Kasuga T, et al. Bioactive calcium phosphate invert glass-ceramic coating on beta-type Ti-29Nb-13Ta-4.6Zr alloy. Biomaterials 2003;24(2):283–290.
5. Livingston T, Ducheyne P, Garino J. In vivo evaluation of a bioactive scaffold for bone tissue engineering. J Biomed Mater Res 2002;62(1):1–13.
6. Roy DM, Linnehan SK. Hydroxyapatite formed from coral skeletal carbonate by hydrothermal exchange. Nature (London) 1974;247(438):220–222.
7. Holmes R, et al. A coralline hydroxyapatite bone graft substitute. Preliminary report. Clin Orthop 1984;188:252–262.
8. Radin SR, Ducheyne P. The effect of calcium phosphate ceramic composition and structure on in vitro behavior. II. Precipitation. J Biomed Mater Res 1993;27(1):35–45.
9. Nielsen AE. Electrolyte Crystal Growth Mechanisms. J Crystal Growth 1984;67: 289–310.
10. Gengwei J. Development of Bioactive Materials using Reticulated Ceramics for Bone Substitue. Ph. D. dissertation, University of Cincinnati; 2000. p 118.
11. Margolis HC, Moreno EC. Kinetics of hydroxyapatite dissolution in acetic, lactic, and phosphoric acid solutions. Calcif Tissue Int 1992;50(2):137–143.
12. Christoffersen J, Christoffersen MR. Kinetics of Dissolution of Calcium Hydroxyapatite. 5. The Acidity Constant for the Hydrogen Phosphate Surface Complex. J Crystal Growth 1982;57: 21–26.
13. Driessens FCM. Formation and Stability of Calcium Phosphates in Relation to the Phase Composition of the Mineral in Calcified Tissues. In: de Groot K, editor. Bioceramics of Calcium Phosphate. Boca Raton, (FL): CRC Press; 1983; p 1–31.

See also BIOMATERIALS, CORROSION AND WEAR OF; NUCLEAR MAGNETIC RESONANCE SPECTROSCOPY; POROUS MATERIALS FOR BIOLOGICAL APPLICATIONS.

BIOMATERIALS: TISSUE-ENGINEERING AND SCAFFOLDS

Gilson Khang
Chonbuk National University
Sang Jin Lee
Moon Suk Kim
Hai Bang Lee
Korea Research Institutes of Chemical Technology

INTRODUCTION

Tissue engineering offers an alternative to whole organ and tissue transplantation for diseased, failed, or abnormally functioning organs. Millions suffer from end-stage organ failure or tissue loss annually. In the United State alone, at least 8 million surgical operations are carried out each year at a total national healthcare cost exceeding $400 billion annually (1–4). Approximately 500,000 coronary artery bypass surgeries are conducted in the United States annually (5). Autologous and allogenic natural tissue, such as the saphenous vein or the internal mammary artery, is generally used for coronary artery replacement. The results have been favorable for these procedures with patency rates generally ranging from 50–70%. Failures are caused by intimal thickening due largely to adaptation of the vessel in response to increased pressure and wall shear stress, compression, inadequate graft diameter, and disjunction at the anastomosis. Also, successful treatment has been limited by the poor performance of the synthetic materials used, such as polyethyleneterephthalate (PET, Dacron) and expanded polytetrafluoroethylene (ePTFE, Gore-Tex), which are used for tissue replacement due to plaguing problems (6). For example, in cases of tumor resection in the head, neck, and upper and lower extremities, as well as in cases of trauma and congenital abnormalities, there are often outline defects due to the loss of soft tissue, this tissue is largely composed of subcutaneous adipose tissue (7). The defects lead to abnormal cosmesis, affect the emotional comfort of patients, and may impair function. A surgeon would prefer to use an autologous adipose tissue to sculpt contour deformities. Because mature adipose tissue does not transplant effectively, numerous natural, synthetic, and hybrid materials have been used to act as adipose surrogates. Despite improved patient outcomes, the use of many of these materials results in severe problems, such as unpredictable outcomes, fibrous capsule contraction, allergic reactions, suboptimum mechanical properties, distortion, migration, and long-term resorption.

To offset the short supply of donor organs as well as the problems caused by the poor biocompatibility of the biomaterials used, a new hybridized method of “tissue engineering”, which combines both cells and biomaterials has been introduced (8). To reconstruct new tissue by tissue engineering, a triad of components are requried: (*1*) harvested and dissociated *cells* from the donor tissue including nerve, liver, pancreas, cartilage, and bone as well as embryonic stem, adult stem, or precursor cell; (*2*) *scaffolds* made of biomaterials on which cells are attached and cultured, then implanted at the desired site of the functioning tissue; (*3*) *growth factors* that promote and/or prevent cell adhesion, proliferation, migration, and differentiation by up-regulating or down-regulating the synthesis of protein, growth factors, and receptors (see Fig. 1). In a typical application for cartilage regeneration, donor cartilage is harvested from the patient and dissociated into individual chondrocyte cells using enzymes as collagenase, and then mass cultured *in vitro*. The chondrocyte cells are then seeded onto a porous and synthetic biodegradable scaffold. This cell–polymer structure is massively cultured in a bioreactor. The abnormal tissue is removed and the cell–polymer structure is then implanted in the patient. Finally, the synthetic biodegradable scaffold resorbs into the body and the chondrocyte cell produces collagen and glycosaminoglycan as its own natural extracellular matrix (ECM), which results in regenerated cartilage. This approach can theoretically be applied to the manufacture of almost all organs and tissues except for organs such as the brain (3).

In this section, a review is given of the biomaterials and procedures used in the development of tissue-engineered scaffolds, including: (*1*) natural and synthetic biomaterials, (*2*) natural–synthetic hybrid scaffolds, (*3*) the fabrication methods and techniques for scaffolds, (*4*) the required physicochemical properties for scaffolds, and (5) cytokine-released scaffolds.


Cells
(e.g., chondrocytes, osteoblasts, stem cells)
Tissue Engineering
Scaffolds
(e.g., collagen, gelatin, PGA, PLA, PLGA)
Signaling molecules
(e.g., growth factors, morphogens, adhesins)
Time
Appropriate Environment
Regeneration of tissues/organs

Figure 1. Tissue engineering triad. The combination of three key elements, cells, biomaterials, and signaling molecules, results in regenerated tissue-engineered neo-organs.

BIOMATERIALS FOR TISSUE ENGINEERING

The Importance of Scaffold Matrices in Tissue Engineering

Scaffolds play a very critical role in tissue engineering. Scaffolds direct the growth (*1*) of cells seeded within the porous structure of the scaffold, or (*2*) of cells migrating from surrounding tissue. Most mammalian cell types are anchorage dependent; the cells die if an adhesion substrate is not provided. Scaffold matrices can be used to achieve cell delivery with high loading and efficiency to specific sites. Therefore, the scaffold must provide a suitable substrate for cell attachment, cell proliferation, differentiated function, and cell migration. The prerequisite physicochemical properties of scaffolds are (*1*) to support and deliver the cells; (*2*) to induce, differentiate, and promote conduit tissue growth; (*3*) to target the cell-adhesion substrate, (*4*) to stimulate cellular response; (*5*) to create a wound healing barrier; (*6*) to be biocompatible and biodegradable; (*7*) to have relatively easy processability and malleability into the desired shapes; (*8*) to be highly porous with large surface–volume; (*9*) to have mechanical strength and dimensional stability; and (*10*) to have sterilizability (9–16). Generally, three-dimensional (3D) porous scaffolds can be fabricated from natural and synthetic polymers (Fig. 2 shows these chemical structures), ceramics, metal, and in a very few cases, composite biomaterials and cytokine-releasing materials.

Natural Polymers

Many naturally occurring scaffolds can be used for tissue engineering purposes. One such example is the ECM, which is composed of very complex biomaterials and controls cell function. For the ECM used in tissue engineering, natural and synthetic scaffolds are designed to mimic specific function. The natural polymers used are alginate, proteins, collagens (gelatin), fibrins, albumin, gluten, elastin, fibroin, hyarulonic acid, cellulose, starch, chitosan (chitin), sclerolucan, elsinan, pectin (pectinic acid), galactan, curdlan, gellan, levan, emulsan, dextran, pullulan, heparin, silk, chondroitin 6-sulfate, polyhydroxyalkanoates, and others. Much of the interest in these natural polymers comes from their biocompatibility, relatively abundance and commercial availability, and ease of processing (17).

Alginate. Alginate (from seaweed) is composed of two repeating monosaccharides: L-guluronic acid and D-mannuronic acid. Repeating strands of these monomers form linear, water-soluble polysaccharides. Gelation occurs by interaction of divalent cations (e.g., Ca^{2+}, Mg^{2+}) with blocks of guluronic acid from different polysaccharide chains (as shown in Fig. 3). From this gelation property, the encapsulation of calcium alginate beads impregnated with various pharmaceutics, cytokines, or cultured cells, has been extensively investigated. Varying the preparation conditions of the gelation can control structure and physicochemical properties. Calcium alginate scaffolds do not degrade by hydrolytic reaction, whereas they can be degraded by a chelating agent such as ethyleneaminetetraaceticacid (EDTA) or by an enzyme. Also, the diffusion of calcium ions from an alginate gel can cause dissociation between alginate chains, which results in a decrease of mechanical strength over time. One of the disadvantages of an alginate matrix is a potential immune response and the lack of complete degradation, since alginate is produced in the human body (10). For these reasons, the chemical modification and incorporation of biological peptides, such as Arg-Gly-Asp cell adhesion peptides, have been used to improve the functionality and flexibility of natural scaffolds and their potential application (18).

Many researchers have studied the encapsulation of chondrocytes. Growth plate chondrocytes, fetal chondrocytes, and mesenchymal stem cells derived from bone marrow have been encapsulated in alginate (19). In each system, the chondrocytes demonstrated a differentiated phenotype, producing an ECM and retaining the cell morphology of typical chondrocytes. In addition, novel hybrid composites, such as alginate/agarose (a thermosensitive polysaccharide), alginate/fibrin, alginate/collagen and alginate/hyaruronic acid, and different gelling agents (water, sucrose, sodium chloride, and calcium sulfate) were investigated to optimize the advantages of each component material for tissue engineered cartilage (20–22). It was found that this hybrid material provides a reason why the microenvironments of composite materials affect chondrogenesis.

Collagen. At least 22 types of collagen exist in the human body. Among these, collagen types I, II, and III are the most abundant and ubiquitous. Conformation of the collagen chain consists of triple helices that are packed or processed into microfibrils. Molecularly, the three repeating amino acid sequences, such as glycine, proline, and hydroxyproline, form protein chains resulting in the formation of a triple helix arrangement. Type I collagen is the most abundant and is the major constituent of bone, skin, ligament, and tendon, whereas type II collagen is the collagen in cartilage. Collagen can promote cell adhesion as demonstrated by the Asp-Gly-Glu-Ala peptide in type I collagen, which functions as a cell-binding domain. Due to the abundance and ready accessibility of these tissues, they have been used frequently in the preparation of collagen (23).

The purified collagen materials obtained from either molecular or fibrillar technology are subjected to additional processing to fabricate the materials into useful scaffold types for specific tissue-engineered organs. Collagen can be processed into several types such as membrane (film and sheet), porous (sponge, felt, and fiber), gel, solution, filamentous, tubular (membrane and sponge), and composite matrix for the application of tissue repair, patches, bone and cartilage repair, nerve regeneration, and vascular and skin repair with/without cells (24). The Physicochemical properties of collagen can be improved by the addition of a variety of homogeneous and heterogeneous composites. Homogeneous composites can be formed between ions, peptides, proteins, and polysaccharides in a collagen matrix by means of ionic and covalent bonding, entrapment, entanglement, and coprecipitation. Heterogeneous composites, such as collagen–synthetic polymers, collagen–biological polymers, and collagen–ceramic hybrid



Figure 2. Chemical structures of some commonly used biodegradable and nondegradable polymers in tissue engineering. (a) Synthetic nondegradable polymers: (**1**). polyethylene, (**2**). poly(vinylidene fluoride), (**3**). polytetrafluoroethylene, (**4**). poly(ethylene oxide), (**5**). poly(vinyl alcohol), (**6**). poly(ethyleneterephthalate), (**7**). poly(butyleneterethphalate), (**8**). poly(methylmethacrylate), (**9**). poly- (hydroxymethylmetacrylate), (**10**). poly(*N*-isopropylacrylamide), (**11**). polypyrrole, (**12**). poly(dimethyl siloxane), and (**13**). polyimides. (b) Synthetic biodegradable polymers: (**14**). poly(glycolic acid), (**15**). poly(lactic acid), (**16**). poly(hydroxyalkanoate), (**17**). poly(lactide-*co*-glycolide), (**18**). poly(ε-caprolactone), (**19**). polyanhydride, (**20**). polyphsphazene, (**21**). poly(orthoester), (**22**). poly(propylene fumarate), and (**23**). poly(dioxanone). (c) Natural polymers: (**24**). alginate, (**25**). chondroitin-6-sulfate, (**26**). chitosan, (**27**). hyarunonan, (**28**). collagen, (**29**). polylysine, (**30**). dextran, and (**31**). heparin. (d) PEO-based hydrogels: (**32**). Pluronic, (**33**). Pluronic R, (**34**). Tetronic, and (**35**). Tetronic R.



24



25



26



27



28



29



30



31

(c)



$$\mathrm{HO}\!\left(\mathrm{CH_2\text{-}CH_2\text{-}O}\right)_n\!\left(\mathrm{CH_2\text{-}\overset{CH_3}{C}H\text{-}O}\right)_m\!\left(\mathrm{CH_2\text{-}CH_2\text{-}O}\right)_n\!\mathrm{H}$$

32



$$\mathrm{HO}\!\left(\mathrm{CH_2\text{-}\overset{CH_3}{C}H-O}\right)_n\!\left(\mathrm{CH_2\text{-}CH_2\text{-}O}\right)_m\!\left(\mathrm{CH_2\text{-}\overset{CH_3}{C}H-O}\right)_n\!\mathrm{H}$$

33



$$\begin{array}{ccc} \mathrm{H}\!\left(\mathrm{O-CH_2\text{-}CH_2}\right)_m\!\left(\mathrm{O-\overset{CH_3}{C}H-CH_2}\right)_n & & \left(\mathrm{CH_2\text{-}\overset{CH_3}{C}H-O}\right)_n\!\left(\mathrm{CH_2\text{-}CH_2\text{-}O}\right)_m\!\mathrm{H} \\ & \mathrm{N-CH_2\text{-}CH_2\text{-}N} & \\ \mathrm{H}\!\left(\mathrm{O-CH_2\text{-}CH_2}\right)_m\!\left(\mathrm{O-\underset{CH_3}{C}H\text{-}CH_2}\right)_n & & \left(\mathrm{CH_2\text{-}\underset{CH_3}{C}H-O}\right)_n\!\left(\mathrm{CH_2\text{-}CH_2\text{-}O}\right)_m\!\mathrm{H} \end{array}$$

34



$$\begin{array}{ccc} \mathrm{H}\!\left(\mathrm{O-\overset{CH_3}{C}H\text{-}CH_2}\right)_m\!\left(\mathrm{O-CH_2-CH_2}\right)_n & & \left(\mathrm{CH_2\text{-}CH_2\text{-}O}\right)_n\!\left(\mathrm{CH_2-\overset{CH_3}{C}H-O}\right)_m\!\mathrm{H} \\ & \mathrm{N-CH_2\text{-}CH_2\text{-}N} & \\ \mathrm{H}\!\left(\mathrm{O-\underset{CH_3}{C}H\text{-}CH_2}\right)_m\!\left(\mathrm{O-CH_2-CH_2}\right)_n & & \left(\mathrm{CH_2\text{-}CH_2\text{-}O}\right)_n\!\left(\mathrm{CH_2-\underset{CH_3}{C}H-O}\right)_m\!\mathrm{H} \end{array}$$

35

(d)

Figure 2. (*continued*)



Figure 3. Schematic representation of the guluronate junction zone in alginate; eggbox model. The circles represent calcium ions.

polymers (collagen–nano-hydroxyapatite and collagen–calcium phosphate) have been investigated for use in tissue-engineered products (10).

Fibrin. Fibrin plays a major role during wound healing as a hemostatic barrier to prevent bleeding and to support a natural scaffold for fibroblasts. Actual polymerization is triggered by the conversion of fibrinogen to fibrin monomer by thrombin, and gelation occurs within 30–60 s. One advantage of using fibrin in this manner is its ability to completely fill the defect by gelling in situ. Fibrin sealant composed of fibrinogen and thrombin in addition to antifibronolytic agents has been used already in such surgical applications as sealing lung tears, cerebral spinal fluid leaks, and bleeding ulcers, because of its natural role in wound healing. Fibrin sealant might be made from autologous blood or from recombinant proteins (22). Fibrin gels can degrade either through hydrolytic or proteolytic means. Fibrinogen is commercially available from several manufacturers, so the cost of the fabrication of fibrin gels is relatively low. Recently, much work has been done to develop fibrin as a potential tissue-engineered scaffold matrix, especially for cartilage, which is formed from a fibrin/chondrocyte construct. Biochemical and mechanical analysis has demonstrated its cartilage-like properties. In neural tissue engineering, fibrin modified the incorporation of bioactive peptide in fibrin gels (25). Also, fibrin/hydroxyapatite hybrid composites have been investigated to optimize the mechanical strength of tissue-engineered subchondral bone substitutes.

Hyaluronan. Hyaluronic acid, a natural glycosaminoglycans polymer, can be found in abundance within cartilaginous ECM. It has some disadvantages in its natural form, such as high water solubility, fast resorption, and fast tissue clearance times, which are not conducive to biomaterials. To overcome these undesirable characteristics, chemical modifications were made to increase biocompatibility, tailor the degradation rate, control water solubility, and to fit the mechanical property. To increase hydrophobicity, esterification was carried out to increase the hydrocarbon content of the added alcohol, which resulted in tailored degradation rates since hydrophobicity directly influences hydration and the deesterification reaction (10). Another approach, the condensation reaction between the carboxylic group of unmodified hyaluronan molecules with the hydroxyl group of other hyalunonic acid molecules, was used to fabricate the sponge form. Then, bone marrow-derived mesenchymal progenitor cells were seeded to induce chondrogenesis and osteogenesis on this scaffold. Results from animal studies indicate that modified hyaluronic acid can successfully support mesenchymal stem cell proliferation and differentiation for osteochondral application (15). Also, a sulfate reaction on a hyaluronan gel created a variety of sulfate derivatives, ranging from one-to-four sulfate groups per disaccharide subunit. A crosslinking network hydrogel can be formed by using diamines from individual hyaluronic acid chains. Chondrocytes seeded on sulfated hyaluronic acid hydrogels appear to have good cell compatibility with the tissue-engineered cartilage. The benzyl ester hyaluronan products HYAFF-11 and LaserSkin (Fidia Advanced Biopolymers, FAB, Abano Terme, Italy) have been introduced to engineer skin bilayers *in vitro* (26).

Chitosan. Chitosan, a polysaccharide derived from chitin, is composed of a simple glucosamine monomer and has physicochemical properties similar to many glycosaminoglycans. Chitosan is relatively biocompatible and biodegradable; it does not evoke a strong immune response. It is relatively cheap due to its abundance and good reactivity with diverse methods of chemical processing. Chitin is typically extracted from arthropod shells by means of acid–alkali treatment to hydrolyze acetamido groups from the *N*-acetylglucosamine resulting in the production chitosan. It has a molecular weight of 800,000–1,500,000 $g \cdot mol^{-1}$ and dissolves easier than the native chitin polymer (27). For its use in the tissue-engineered cartilage, a 3D composite, such as a chondroitin sulfate A/chitosan hydrogel scaffold, was prepared. This hydrogel supported a differentiated phenotype of seeded articular chondrocytes and type II collagen and proteoglycan production (28). Also, the organic–inorganic hybrid scaffold, used as a chitosan/tricalcium phosphate scaffold, was fabricated for tissue-engineered bone. When osteoblast cells collected from rat fetal calvary were seeded onto a chitosan/tricalcium phosphate scaffold, the cells proliferated in a multiplayer manner and deposited a mineralized matrix (29).

Agarose. Agarose is another type of marine source polysaccharide purified extract from sea creatures, such as agar or agar-bearing algae. One of the unique properties of agarose is the formation of a thermally reversible gel, which starts to set at a concentration in excess of 0.1% at a temperature $\sim 40\,^{\circ}C$ and a gel melting temperature of $90\,^{\circ}C$. Agarose gel is widely used in the electrophoresis of proteins and nucleic acid. Its good gelling behavior could make it a suitable injectable bone substitute and cell carrier matrix (17). Allogenic chondrocyte-seeded agarose gels have been used as a model to repair osteochondral defects in vivo. The repaired tissues were scored histologically based on the intensity and extent of the proteoglycan and the type II collagen immunoassay, the structural features of the various cartilaginous zones, integration with host cartilage, and the morphological features and arrangement of chondrocytic cells. The allogenic chondrocyte–agarose-grafted repairs had a higher semiquantitative score than control grafts. These results showed a good potential for use in tissue engineering (30). More detailed studies, such as the in vivo mechanical properties, biocompatibility and toxicity, and the balance degradation and synthesis kinetics of agarose-based tissue-engineered products, must be undertaken to further successful agarose applications (31).

Small Intestine Submucosa. Porcine small intestine submucosa (SIS) is an important material for natural ECM scaffolds (15). Many experiments have shown systematically that an acellular resorbable scaffold material, derived from SIS, is rapidly resorbed, supports early and abundant new blood vessel growth, and serves as a template for the constructive remodeling of several body tissues including musculoskeletal structures, skin, body wall, dura mater, urinary bladder, and blood vessels (32). The SIS material consists of a naturally occurring ECM, rich in components that support angiogenesis, including fibronectin, glycosaminoglycans including heparin, several collagens (including types I, III, IV, V, and VI), and angiogenic growth factors such as basic fibroblast growth factor and vascular endothelial cell growth factor (33). For these reasons, SIS scaffolds have been successfully used to reconstruct the urinary bladder, for vascular grafts, to reconstruct cartilage and bone alone or as a composite with synthetic polymers and inorganic biomaterials (34).

Acellular Dermis. Acellular human skin, that is skin removed of all cellular components, may be one of the most significant ECMs. An acellular dermis can be seeded with fibroblasts and keratinocytes to fabricate a dermal–epidermal composite for the regeneration of skin. AlloDerm (LifeCell, Branchburgh, NJ) is a typical commercialized product, a split-thickness acellular allograft prepared from human cadaver skin and cryopreserved for off-shelf use (35). Alloderm has been successful in the treatment of burn patients because of its nonantigenic dermal scaffold that includes elastin, proteoglycan, and basement membrane.

Poly(hydroxyalkanoates). Poly(hydroxyalkanoates) are entirely natural and are obtained from the microorganism *Alcaligen eutrophus* as Gram-negative bacteria. The physical properties of polyhydroxybutyrate (PHB) are similar to nondegradable polypropylene. Its copolymers with hydroxyvalerate [poly(hydroxybutylate-*co*-hydrovalerate); PHBV] have a modest range of mechanical properties and a correspondingly modest range of chemical compositions for monomers and processing conditions. Due to their good processability, these polymers can be manufactured into many forms, such as fibers, meshes, sponges, films, tubes, and matrices through standard processing techniques.

The family of poly(hydroxyalkanoates) does not appear to cause any acute inflammation, abscess formation, or tissue necrosis in whethers in the form of nonporous disks or cylinders, adjacent tissues (36). To optimize the mechanical property of PHBV, organic–inorganic hybrid composites such as PHBV–hydroxyapatite were developed for the tissue engineering of bone; hydroxyapatite promotes osteoconductive activity (13). Also, Schwann cell-seeded PHB was applied to regenerate a nerve in the shape of a conduit to guide and induce neonerve tissue at the nerve ends. Good nerve regeneration in PHB conduits as compared to nerve grafts was observed. The shape, mechanical strength, porosity, thickness, and degradation rate of PHB and its copolymers can be engineered.

Other Natural Polymers. Excluding those polymers discussed in the Natural Polymers section above, other natural polymers, are proteins, albumin, gluten, elastin, fibroin, cellulose, starch, sclerolucan, elsinan, pectin (pectinic acid), galactan, curdlan, gellan, levan, emulsan, dextran, pullulan, heparin, silk, and chondroitin 6-sulfate. Although they are not discussed here, these biopolymers are of interest because of their unusual and useful functional properties as well as their abundance. This group of natural polymers are (*1*) biocompatible and nontoxic, (*2*) easily processed as film and gel, (*3*) heat stable and thermal processable over a broad temperature range, and (*4*) water soluble (17). *In vivo* and *in vitro* experiments, and physicochemical modifications should be performed in the near future to promote the use of these natural polymers in tissue-engineered scaffolds.

Synthetic Polymers

Natural polymers are not used more extensively because they are expensive, differ from batch to batch, and there is a possibility of cross-contamination from unknown viruses or unwanted diseases due to their isolation from plant, animal, and human tissue. Alternatively, synthetic polymeric biomaterials have easily controlled physicochemical properties and quality, and no immunogenecity. Also, they can be processed by various techniques and supplied consistently in large quantities. To adjust the physical and mechanical properties of a tissue-engineered scaffold at a desired place in the human body, the molecular structure, and molecular weight are adjusted during the synthetic process. Synthetic polymers are largely divided two categories: biodegradable, and nonbiodegradable. Some nondegradable polymers include poly(vinylalcohol) (PVA), poly(hydroxylethylmethacryalte), and poly(*N*-isopropylacryamide). Some synthetic degradable polymers are in the family of poly(α-hydroxy ester)s, such as polyglycolide (PGA), polylactide (PLA) and its copolymer poly(lactide-*co*-glycolide) (PLGA), polyphosphazene, polyanhydride, poly(-propylene fumarate), polycyanoacrylate, polycaprolactone, polydioxanone and biodegradable polyurethanes.

Between these two polymers, synthetic biodegradable polymers are preferred for use in tissue-engineered scaffolds because they have minimal chronic foreign body reactions and they promote the formation of completely natural tissue. That is, they can form a temporary scaffold for mechanical and biochemical support. More detailed polymer fabrication methods are discussed in the section, Scaffold Fabrication and Characterization.

Poly(α-Hydroxy Ester)s. The family of poly(α-hydroxy acid)s, such as PGA, PLA, and its copolymer PLGA, are among the few synthetic polymers approved for human clinical use by the U.S. Food and Drug Administration (FDA). These polymers are extensively used or tested as scaffold materials, because they are as bioerodible with good biocompatibility, have controllable biodegradability, and relatively good processability (37). This family of poly(α-hydroxy éster)s has been used for three decades: PGA as a suture; PLA in bone plate, screw and reinforced materials; and PLGA in surgical and drug delivery devices. The safety of these materials has been prove for many medical applications (38–47).

These polymers degrade by nonspecific hydrolytic scission of their ester bonds. Polyglycolide biodegrades by a combination of hydrolytic scission and enzymatic (esterase) action producing glycolic acid, which can either enter the tricarboxylic acid (TCA) cycle or be excreted in urine and eliminated as carbon dioxide and water. The hydrolysis of PLA yields lactic acid, which is a normal byproduct of anaerobic metabolism in the human body and is incorporated in the TCA cycle to be excreted finally by the body as carbon dioxide and water. With the addition of a methyl group to glycolide, PLA is much more hydrophobic than the highly crystalline PGA. As a result, PLA has a slower degradation rate over a year's time. The degradation time of PLGA as a copolymer can be controlled from weeks to over a year by varying the ratio of monomers, its molecular weight, and the processing conditions. The synthetic methods and physicochemical properties, such as melting temperature, glass transition temperature, tensile strength, Young's modulus, and elongation, were reviewed elsewhere (48).

The mechanism of biodegradation of poly(α-hydroxy acid)s is bulk degradation, which is characterized by a loss in polymer molecular weight, while its mass is maintained. Mass maintenance is useful for tissue-engineering applications that require a specific shape. However, a loss in molecular weight causes a significant decrease in mechanical properties. Degradation depends on its chemical history, porosity, crystallinity, steric hindrance, molecular weight, water uptake, and pH. Degradable products, such as lactic acid and glycolic acid, decrease the pH in the surrounding tissue resulting in inflammation and potentially poor tissue development. The PGA, PLA, and PLGA scaffolds are applied for the regeneration of all tissue, including skin, cartilage, blood vessel, nerve, liver, dura mater, bone, and other tissue (10,12,17). For the application of these polymers as scaffolds, the development of fabrication methods for porous structures is also important.

The hybrid structure of chondrocytes and fibroblast/PGA fiber felts was successfully tested in the regeneration of cartilage and skin, respectively (49). Also, porous PLGA scaffolds with an average pore sizes of 150–300 or 500–710 μm were seeded with osteoblast cells, which resulted in good bone generation. Composites of PLA/tricalcium phosphate and PLA/hydroxyapatite were attempted to induce bone formation both *in vitro* and *in vivo* (13,50). Porous PLA tubes with an inside diameter of 1.6 mm, are outside diameter of 3.2 mm, and lengths of 12 mm, were implanted into 12 mm gaps in the rat sciatic nerve model. Compared to control grafts, both the number and density of axons were significantly less for the tabulated implants. The PGA tube was also tested for the regeneration of vascular grafts, and showed good *in vivo* results.

To improve the physicochemical properties of poly(α-hydroxy acid)s for use as scaffold materials, the chemical modification of both end groups of PLA and PGA was undertaken; the additional reaction of the moieties helps to control the biological and/or physical properties of biomaterials (17). For example, poly(lactic acid-*co*-lysine-*co*-aspartic acid) (PLAL-ASP) was synthesized to add a cell adhesion property. Similarly, a copolymer of lactide and ε-caprolactone was synthesized to improve the elastic property of PLA. The PLA-poly(ethylene oxide) (PEO) copolymers were synthesized to have the degradative and mechanical properties of PLA and the biological control offered by PEO and its functionalization (51). One of the unique characteristics of PLA-PEO block copolymers is its temperature sensitivity. Because of the hydrophobicity of PLA and hydrophilicity of PEO, the sol–gel property can be applied to injectable cell carriers. Also, a nano-hybrid composite with other materials has been developed for application to all organs in the body.

Poly(vinyl Alcohol). Poly(vinyl alcohol) is synthesized from poly(vinyl acetate) by saponification. The result is a hydrogel that contains some water, which is similar to cartilage. It is relatively biocompatible, swells with a large amount of water, easily sterilized, and easily fabricated and molded into desired shapes. It has a reactive pendant alcohol group that can be modified by chemical cross-linking, physical cross-linking, or by incorporating an acrylate group, which results in improvement of its mechanical properties. A typical commercialized PVA gel is Salubria (Salumedica, Atlanta, GA), which was created by completing a series of freeze–thaw cycles with PVA polymers and 0.9% saline solution. By changing the ratio of PVA and H_2O, the molecular weight of PVA, and the quantity and duration of the freeze–thaw cycles, the physical properties of the PVA hydrogel can be controlled. Poly(vinyl alcohol) has been used in cartilage regeneration; it has similar mechanical properties needed in breast augmentation, diaphragm replacement, and bone replacement (10). One significant drawback is that it is not fully biodegradable because of the lack of labile bonds within the polymer backbone. So, it is recommended that low molecular weight PVA, $\sim 15{,}000\ \text{g}\cdot\text{mol}^{-1}$, which can be absorbed through the kidney, might be applied to tissue-engineered scaffolds.

Polyanhydride. Polyanhydride is synthesized by the reaction of diacids with anhydride to form acetyl anhydride prepolymers. High molecular weight anhydrides are synthesized from the anhydride prepolymer in a melt condensation. Polyanhydrides are modified to increase their physical properties by a reaction with imides (17). A typical example of this is copolymerization with an aromatic imide monomer that results in the polyanhydride-*co*-imide used in hard tissue engineering. To control degradability and to enhance mechanical properties, photo-crosslinkable functional groups were introduced by the substituted methacrylate groups on polyanhydrides for orthopedic tissue engineering (48,50). The degradation mechanism of polyanhydrides is a highly predictable and controlled, surface erosion whereas that of poly(α-hydroxy ester) is bulk erosion. To optimize the degradation behavior of anhydride-based copolymers, the polymer backbone chemistry needs to be controlled to achieve a ratio of monomer and molecular weight.

Poly(Propylene Fumarate). Poly(propylene fumarate) and its copolymer, a biodegradable and unsaturated linear polyester, were synthesized as potential scaffold biomaterials. The degradation mechanism is a hydrolytic chain scission similar to poly(α-hydroxy ester). The mechanical strength and degradable behaviors were controlled by crosslinking with a vinyl monomer at the unsaturated double bonds. The physical properties are enhanced by a composite with degradable bioceramic β-tricalcium phosphate, which is used as injectable bone (52). Copolymerization of propylene fumarate with ethylene glycol can be made elastic with poly(propylene fumarate) and used as a cardiovascular stent. New materials for propylene fumarate polymers are continually being investigated through copolymer synthesis, hybrid composites, and blends.

PEO and Its Derivatives. Poly(ethylene oxide) is one of the most important and widely used polymers in biomedical applications because of its excellent biocompatibility (51,53,54). It can be produced by anionic or cationic polymerization from ethylene oxide by initiators. Poly(ethylene oxide) is used to coat materials used in medical devices to prevent tissue and cell adhesion, as well as in the preparation of biologically relevant conjugates, and in induction cell membrane fusion. These PEO hydrogels can be fabricated by crosslinking reactions which gamma rays, electron beam irradiation, or chemical reactions. This hydrogel can be used for drug delivery and tissue engineering. Vigilon (C.R. Bard, Inc., Murray Hill, NJ) is a radiated crosslinked, high molecular weight PEO, which swells with water and is used as a wound-covering material. The hydroxyl in the glycol end group is very active, making it appropriate for chemical modification. The attachment of bioactive molecules, such as cytokines and peptides to PEO or poly(ethylene glycol) (PEG) promotes the efficient delivery of bioactive molecules. See the section, Cytokine Release System for Tissue Engineering, for a more detailed explanation.

To synthesize biodegradable PEO, block copolymerization with PGA or PLA degradable units has been carried out. The hydrogel can be polymerized into two- or three-block copolymers such as PEO-PLA, PEO-PLA-PEO, and PLA-PEO-PLA. For the biodegradable block, ε-caprolactone, δ-valerolactone, and PLGA can be used (50). A characteristic of this series of hydrogels is a temperature-sensitive phenomena. A solid state at room temperature changes to a gel state at body temperature. Hence, biodegradable hydrogels are very useful in injectable cell loading scaffolds (55). After injection of the chondrocyte cell hybrid structure and biodegradable hydrogels, the hydrogels degrade in vivo and neocartilage tissue remains.

Also, the copolymers of PEO and poly(propylene oxide) (PPO), including PPO-PEO-PPO or PEO-PPO-PEO block copolymers, are the basis for the commercially available Pluronics and Tetronics. Pluronics form a thermosensitive gel by shrinking hydrophobic segments of the copolymer PPO (54). The physicochemical property of the hydrogel can be varied with the composition and structure of the ratio of PPO and PEO. Some have been approved by the FDA and EPA for use as food additives, pharmaceutical ingredients, and agricultural products. Although the polymer is not degraded by the body, the gels dissolve slowly and the polymer is eventually cleared. Chondrocytes-loaded Pluronics, when directly injected at the injured site containing tissue-engineered cartilage, maintained its original shape in the developing neocartilage (56). Also, these polymers are used in the treatment of burn patients and for protein delivery. The advantages of these injectable hydrogels include: (*1*) no need for surgical intervention, (*2*) easy pore-size manipulation, and (*3*) no need for complex shape fobrication.

Polyphosphazene. Polyphossphazene consists of an inorganic backbone of alternating single and double bonds between phosphorous and nitrogen atoms, while most of the polymer is made up of a carbon–carbon organic backbone (10,12,17). It has side groups that can react with other functional groups which result in block or star polymers. Biological and physical properties can be controlled by the substitution of functional side groups. For example, the rate of degradation can be varied by controlling the proportion of hydrolytically labile side groups. The wettability such as hydrophilicity, hydrophobicity, and amphiphilicity, of polyphosphazene might be dependent on the properties of the side group. It can be made into films, membranes, and hydrogels for scaffold applications by cross-linking or grafting modifications (48). The cytocompatibility of highly porous polyphosphazene scaffolds offers possibilities for skeletal tissue engineering. Also, the blend of polyphosphazene with PLGA may be modified and its miscibility and degradability determined (57).

Biodegradable Polyurethane. Polyurethane is one of the most widely used polymeric biomaterials in biomedical fields due to its unique physical properties, such as durability, elasticity, elastomer-like character, fatigue resistance, compliance, and tolerance. Moreover, the reactivity of the functional group of the polyurethane backbone can be achieved by the attachment of biologically active biomolecules and the adjustment of their hydrophilicity–hydrophobicity (58). Recently, the synthesis of a new generation of nontoxic biodegradable peptide-based polyurethanes was achieved. Typical biodegradable polyurethane is composed of an amino acid-based hard segment (such as lysine diisocyanate), a polyol soft segment (such as a hydroxyl doner-like polyester), and sugar (59). Hence, the degradation products of these nontoxic lysine diisocyanate-based urethane polymers are nontoxic lysine and the polyol. If the covalent bonding of various proteins, such as cytokines, growth factors, and peptides, are introduced in the polymer backbone, the controlled release of the bioactive molecules can be achieved in a degradable manner using polyurethane scaffolds. The mechanisms of degradation are hydrolysis, oxidation—both thermal, and enzymatic. Both the chemistry and the composition of soft and hard segments play an important role in the degradability of polyurethane. Poly(urethane-urea) matrices with lysine diisocyanate as the hard segment and glucose, glycerol, or PEG as the soft segments have been studied. In the application of biodegradable polyurethane as a scaffold various types of cells, such as chondrocytes, bone marrow stromal cells, endothelial cells, and osteoblast cells, were successfully adhered and proliferated. Also, toxicity, induction of a foreign body reaction, and antibody formation were not observed in in vivo experiments. The long-term safety and biocompatibility of biodegradable polyurethane must be continuously monitored for use in tissue-engineered scaffold substrates.

Other Synthetic Polymers. Besides the synthetic polymers already introduced in the above sections, many other synthetic polymers, either degradable or nondegradable, are being developed and tested to mimic the natural tissue and wound-healing environment. Examples are poly(2-hydroxyethylmethacrylate) hydrogel, injectable poly(*N*-isopropylacrylamide) hydrogel, and polyethylene for neocartilage; poly(iminocarbonates) and tyrosine-based poly(iminocarbonates) for bone and cornea; crosslinked collagen–PVA films and an injectable biphasic calcium phosphate–methylhydroxypropylcellulose composite for bone regeneration materials; a polyethylene oxide-*co*-polybutylene terephthalate for bone bonding; poly(orthoester) and its composites with ceramics for tissue-engineered bone; synthesized conducting polymer polypyrrole–hyaruronic acid composite films for the stimulation of nerve regeneration; and peptide-modified synthetic polymers for the stimulation of cell and tissue.

It is very important for the design and synthesis of more biodegradable and biocompatible scaffold biomaterials to mimic the natural ECM in terms of bioactivity, mechanical properties, and structures. The more biocompatible biomaterials tend to elicit less of an immune response and reduce an inflammatory response at the implantation site.

Bioceramic Scaffolds

Bioceramic is a term used for biomaterials that are produced by sintering or melting inorganic raw materials to create an amorphous or a crystalline solid body that can be used as an implant. Porous final products have been used mainly as scaffolds. The components of ceramics are calcium, silica, phosphorous, magnesium, potassium, and sodium. Bioceramics used in tissue engineering might be classified as nonresorbable (relatively inert), bioactive, or surface active (semi-inert), and biodegradable or resorbable (non-inert). Alumina, zirconia, silicone nitride, and carbons are inert bioceramics. Certain glass ceramics are dense hydroxyapatites [$9CaO \cdot Ca(OH)_2 \cdot 3P_2O_5$] and semi-inert (bioactive). Calcium phosphates, aluminum–calcium–phosphates, coralline, tricalcium phosphates ($3CaO \cdot P_2O_5$), zinc-calcium-phosphorous oxides, zinc-sulfate-calcium-phosphates, ferric–calcium–phosphorous–oxides, and calcium aluminates are resorbable ceramics (60). Among these bioceramics, synthetic apatite and calcium phosphate minerals, coral-derived apatite, bioactive glass, and demineralized bone particles are widely used in the hard tissue engineering area, hence, they will be discussed in this section.

Synthetic crystalline calcium phosphate can be crystallized into salts such as hydroxyapatite and β-whitlockite, depending on the Ca/P ratio. These salts are very tissue compatible and are used as bone substitutes in a granular, sponge form or as a solid block. The apatite formed with calcium phosphate is considered to be closely related to the mineral phase of bone and teeth. The chemical composition of crystalline calcium phosphate is a mixture of $3CaO \cdot P_2O_5$, $9CaO \cdot Ca(OH)_2 \cdot 3P_2O_5$ and calcium pyrophosphate ($4CaO \cdot P_2O_5$). The active exchange of ions occurs on the surface and leads to the exchange composition of minerals (9,61). When porous ceramic scaffolds were implanted in the body, both with or without cells for tissue-engineered bone, the delivery of some elements to the new bone was at the interface between the materials and the osteogenic cells.

Tricalcium phosphate is the rapidly resorbable calcium phosphate ceramic resulting in resorption 10–20 times faster than hydroxyapatite (13). Porous tricalcium phosphate may stimulate local osteoblasts for new bone formation. Injectable calcium phosphate cement containing β-tricalcium phosphate, dibasic dicalcium phosphate, and tricalcium phosphate monoxide, was investigated for the treatment of distal radius fractures. Calcium sulfate hemihydrate (plaster of Paris), as a synthetic graft material, was also tested for tissue-engineered bone.

Coral-derived apatite (Interpore; Interpore international, Irvine, CA) is a natural substance made by marine vertebrate (62). The porous structure of coral, which is structurally similar to bone, is a unique physicochemical property that promotes its use as a scaffold matrix for bone. The main component of natural coral is calcium carbonate or aragonite, the metastable form of calcium carbonate. This compound can be converted to hydroxyapatite by a hydrothermal exchange process, which results in a mixture of hydroxyapatites, $9CaO \cdot Ca(OH)_2 \cdot 3P_2O_5$, and fluoroapatite, $Ca_5(PO_4)_3F$. For tissue-engineered bone, the hybrid structure of porous coral-derived scaffolds and mesenchymal stem cells were demonstrated in vitro. The results showed the differentiation of bone marrow derived from stem cells to osteoblasts; successive mineralizations were successfully accomplished (63).

Glass ceramics are polycrystalline materials manufactured by controlled crystallization of glasses using nucleating agents, such as small amounts of metallic agent Pt groups, TiO_2, ZrO_2, and P_2O_5, which result in a fine-grained ceramic that possesses excellent mechanical and thermal properties (60,61). Typical bioglass ceramics developed for implantations are SiO_2-CaO-Na_2O-P_2O_5 and Li_2O-ZnO-SiO_2 systems. These bioglass scaffolds are suitable for inducing direct bonding with bone. Bonding to bone is related to the composition of each component.

One significant natural bioactive material is the demineralized bone particle, which is a powerful inducer of new bone growth (38,41). Demineralized bone particles contain many kinds of osteogenic and chondrogenic cytokines such as bone morphogenetic protein, and are widely used as filling agent for bony defects. Because of their improved availability through the tissue bank industry, demineralized bone particles are widely used in clinical settings. To achieve more optimal results in the application of demineralized bone particles to tissue engineering, nanohybridization with synthetic (PLGA/demineralized bone particle hybrid scaffolds) and with natural organic compounds (collagen/demineralized bone particle hybrid scaffolds), has been carried out.

Porosity—the size of the mean diameter and the surface area—is a critical factor for the growth and migration of tissue into bioceramic scaffolds (60). Several methods have been introduced to optimize the fabrication of porous ceramics, such as dip casting, starch consolidation, the polymeric sponge method, the foaming method, organic additives, gel casting, slip casting, direct coagulation consolidation, hydrolysis-assisted solidification, and freezing methods. Therefore, it is very important to choose an appropriate method of preparation based on the physical properties of the desired organs.

A CYTOKINE-RELEASE SYSTEM FOR TISSUE ENGINEERING

Growth factors, a type of cytokine, are polypeptides that transmit signals to modulate cellular activity and tissue development including cell patterning, motility, proliferation, aggregation, and gene expression. As in the development of tissue-engineered organs, regeneration of functional tissue requires maintenance of cell viability and differentiated function, encouragement of cell proliferation, modulation of the direction and speed of cell migration, and regulation of cellular adhesion. For example, transforming growth factor-β_1 (TGF-β_1) might be required to induce osteogenesis and chondrogenesis from bone marrow derived mesenchymal stem cells. Also, brain-derived neurotrophic factor (BDNF) can be enhanced to regenerate the spinal cord after injury. The easiest method for the delivery of growth factor is injection near the site of cell differentiation and proliferation (4). The most significant problems associated with the direct injection method are that the growth factors have a relatively short half-life, have a relatively high molecular weight and size, display very low tissue penetration, and have potential toxicity at systemic levels (4,10,11,16).

A promising technique for the improvement of their efficacy is to locally control the release of bioactive molecules for a specified release period to promote impregnation into a biomaterial scaffold. Through impregnation into the scaffold carrier, protein structure and biological activity can be stabilized to a certain extent, resulting in prolonging the release time at the local site. The duration of cytokine release from a scaffold can be controlled by the types of biomaterials used, the loading amount of cytokine, the formulation factors, and the fabrication process. The release mechanisms are largely divided into three categories: (*1*) diffusion controlled, (*2*) degradation controlled, and (*3*) solvent controlled. The mechanism of biodegradable scaffold materials was regulated by degradation control, whereas that of the nondegradable material was regulated by diffusion and/or solvent control. The desired release pattern, such as a constant, pulsatile, and time programed behavior over the specific site and injury can be achieved by the appropriate combination of these mechanisms. Also, the cytokine-release system's geometries and configurations can be altered to produce the necessary scaffold, tube, microsphere, injectable form or fiber (46,51,54).





Figure 4. (a) Bone marrow-derived mesenchymal stem cells impregnated TGF-β_1 loaded alginate beads (original magnifications 40×), and (b) inner structure of alginate beads (original magnifications 100×).

Figures 4–6 show the TGF-β_1 loaded alginate bead and the release pattern of TGF-β_1 from alginate beads for the chondrogenesis from bone marrow-derived mesenchymal stem cells (64). The pore structure of 10 μm width and 100 μm length, was well suited to promote cell proliferation (Fig. 4); TGF-β_1 released at a near zero-order rate for 35 days (Fig. 5). By using the alginate bead with TGF-β_1 delivery system, chondrogenesis was successfully attained, as shown in Fig. 6.

To fabricate a new sustained delivery device for nerve growth factor (NGF), we developed NGF-loaded biodegradable PLGA films by a novel and simple sandwich solvent casting method for possible applications in the central nervous system (45). The release of NGF from the NGF-loaded PLGA films was prolonged > 35 days with a zero-order rate, without initial burst, and controlled by variation of different molecular weights and different NGF loading amounts as shown in Fig. 7. After 7 days, NGF



Figure 5. Release pattern of TGF-β_1 from TGF-β_1 loaded alginate beads; (■) 0.5 μg TGF-β_1, (•) 0.5 μg TGF-β_1 with heparin, (▲) 1.0 μg TGF-β_1, and (▼) 1.0 μg TGF-β_1 with heparin.

was released in a phosphate buffered saline solution (PBS; pH 7.0) and rat pheochromocytoma (PC-12) cells were cultured on the NGF-loaded PLGA film for 3 days. The released NGF stimulated neurite sprouting in the cultured PC-12 cells; the remaining NGF in the NGF/PLGA film at 37°C for 7 days was still bioactive, as shown in Fig. 8. These studies suggest that NGF-loaded PLGA sandwich film can be released in the delivery system over the desired time period, thus, it can be a useful neuronal growth culture serving as a nerve contact guidance tube for applications in neural tissue engineering.



Figure 6. Safranin-O staining of chondrogenesis cells from bone marrow-derived mesenchymal stemcells in alginate beads. We can observe typical chondrocyte cells in alginate beads; (a) 0.5 $\mu g \cdot mL^{-1}$ TGF-β_1, (b) 1.0 $\mu g \cdot mL^{-1}$ TGF-β_1, (c) 0.5 $\mu g \cdot mL^{-1}$ TGF-β_1 with heparin (d) 1.0 $\mu g \cdot mL^{-1}$ TGF-β_1 with heparin, and (e) control (without TGF-β_1) (Original magnification 100×).



Figure 7. (a) Release profiles and (b) logarithmic plot of release rate for NGF from NGF-loaded PLGA films of 43,000 g/mol. (•) 25.4 ng, and (■) 50.9 ng NGF/cm² PLGA.

One serious problem during the fabrication of cytokine-loaded scaffolds is the denaturation and deactivation of cytokines, which result in loss of biological activity (65,66). Hence, the optimized method must be developed for stabilized cytokine-release scaffolds. For example, the release of NGF from a PLGA matrix was investigated using codispersants, such as polysaccharides (dextran) and proteins (albumin and β-lactoglobulin), with different molecular weights and charges. Negatively charged codispersants stabilized NGF in the PLGA system. Similarly, albumin stabilized epidermal growth factor (EGF) and heparin stabilized other growth factors.

Another available emerging technology is the "tethering of protein", that is, immobilization of protein on the surface



Figure 8. Effect of NGF released on neurites formation of PC-12 cells for 3-day cultivation on control (a) PLGA, (b) 25.4 ng, and (c) 50.9 ng NGF/cm^2 PLGA just after 7 days. There were total medium changes (Molecular weight of PLGA; 83,000 g/mol, original magnification; 400×).

of a scaffold matrix. Immobilization of insulin and transferrin to the poly(methylmetacrylate) films stimulates the growth of fibroblast cells compared to the same concentrations of soluble or physically adsorbed proteins (67). For the enhancement of cytokine activity, the PEO chain was applied as a short spacer between the surface of the scaffold and the cytokine. Tethered EGF, immobilized to the scaffold through the PEO chain, showed better DNA synthesis or cell rounding compared to the physically adsorbed EGF surface (68).

Conjugation of cytokine with an inert carrier prolongs the short half-life of protein molecules. Inert carriers are albumin, gelatin, dextran, and PEG. In PEGylation, PEG conjugated cytokine is most widely used for the release. This carrier appears to decrease the rate of cytokine degradation, attenuate the immunological response, and reduce clearance by the kidneys (69). Also, this PEGylated cytokine can be impregnated into scaffold materials by physical entrapment for sustained release. For example, the NGF-conjugated dextran (70,000 $\text{g} \cdot \text{mol}^{-1}$) impregnated polymeric device was implanted directly into the brain of adult rats. Conjugated NGF could penetrate into the brain tissue 8 times faster than the unconjugated NGF. This conjugation method can be applied to the delivery of proteins and peptides. Immobilized RGD (arginin-glycine-aspartic acid) and YIGSR (tyrosin-leucineglycine-serine-arginine), which are typical ECM proteins, can enhance cell viability, function, and recombinant products in the cell (70).

Gene-activating scaffolds are being designed to deliver the targeted gene that results in the stimulation of specific cellular responses at the molecular level (4,3,11). Modification of bioactive molecules with resorbable biomaterial systems obtain specific interactions with cell integrins resulting in cell activation. These bioactive bioglasses and macroporous scaffolds also can be designed to activate genes that stimulate regeneration of living tissue (9). Gene delivery would be accomplished by complexation with positively charged polymers, encapsulation, and gel by means of the scaffold structure (51). Methods of gene delivery for gene-activating scaffolds are almost the same methods as for those with protein, drug, and peptides.

SCAFFOLD FABRICATION AND CHARACTERIZATION

Scaffold Fabrication Methods

Engineered scaffolds may enhance the functionalities of cells and tissues to support the adhesion and growth of a large number of cells because they provide a large surface area and pore structure within a 3D structure. The pore structure needs to provide enough space, permit cell suspension, and allow penetration of the 3D structure. Also, these porous structures help to promote ECM production, transport nutrients from nutrient media, and excrete waste products (10,12,15). Therefore, an adequate pore size and a uniformly distributed, and an interconnected pore structure, which allow for easy distribution of cells throughout the scaffold structure, are very important. Scaffold structures are directly related to their fabrication methods; over 20 methods have been proposed (10,71).

The most common and commercialized scaffold is the PGA nonwoven sheet (Albany International Research Co., Mansfield, MA; porosity ~ 97%, ~ 1–5 mm thick); it is one of the most tested scaffolds for tissue-engineered organs. To stabilize dimensionally and provide mechanical integrity, fiber-bonding technology was developed using heat and PLGA or PLA solution spray coating methods (72).

Porogen leaching methods have been combined with polymerization, solvent casting, gas foaming, or compression molding of natural and synthetic scaffolds biomaterials. The leaching of pore-generating particles such as sodium chloride crystal, sodium tartrate, and sodium citrate were sieved using a molecular sieve (10,71). PLGA, PLA, collagen, poly(orthoester), or SIS-impregnated PLGA scaffolds were successfully fabricated into a biodegradable sponge structure by this method with $> 93\%$ porosity and a desired pore size of 1000 μm. By using the solvent casting/particulate leaching method, complex geometries, such as tube, nose, and specific organ types (e.g., nano-composite hybrid scaffolds), could be fabricated by means of conventional polymer-processing techniques, such as calendaring, extrusion, and injection. Complex geometry can be fabricated from porous film lamination (33,39,42,47). The advantage of this method is its easy control of porosity and geometry. However, the disadvantages include: (*1*) the loss of water-soluble biomolecules or cytokines during the leaching porogen process, (*2*) the possibility that the remaining porogen as a salt can be harmful to the cell culture, and (*3*) the different geometry surface and cross-section that results.

The gas-foaming method consists of a solid scaffold matrix exposured to a sudden expansion of CO_2 gas under high pressure, which results in the formation of a sponge structure due to nucleation and expansion in a dissolved CO_2 scaffold matrix. The PLGA scaffolds with $> 93\%$ porosity and ~ 100 μm median pore size were developed by this method (71). A significant advantage is that there is no loss of bioactive molecules in the scaffold matrix, since there is no more need for the leaching process and there is no residual organic solvent. The disadvantage is the presence of a skimming film layer on the scaffold surface, which results in a need for an additional process to remove the skin layer.

The phase-separation method is divided into the freeze–drying, freeze–thaw, freeze–immersion precipitation, and emulsion freeze–drying techniques (37,72,73). Phase separation by freeze–drying can be induced by the appropriate concentration of polymer solution obtained by rapid freezing. Then, the used solvent is removed by freeze–drying, leaving in porous structure made up of a portion of the solvent. These can be collagen scaffolds with pores ~ 50–150 μm; collagen–glycosaminoglycan blend scaffolds with an average pore size ~ 90–120 μm; or chitosan scaffolds with a pore size ~ 1–250 μm, dependent on the freezing conditions (71). Also, scaffold structures of synthetic polymers, such as PLA or PLGA, have been successfully made much $> 90\%$ porosity and ~ 15–250 μm size by this method. The freeze–thaw technique induces phase separation between a solvent and a hydrophilic monomer upon freezing, followed by the polymerization of the hydrophilic monomer by means of ultraviolet (UV) irradiation and removal of the solvent by thawing. This technique leads to the formation of a macroporous hydrogel. A similar method is the freeze–immersion precipitation technique. The polymer solution is cooled, immersed in a nonsolvent, and then the vaporized solvent leads to a porous scaffold structure. Also, the emulsion freeze–drying method is used to fabricate a porous structure. Mixtures of polymer solution and nonsolvent are thoroughly sonicated, freezed quickly in liquid nitrogen at $-198\,^{\circ}C$, and then freeze–dried, resulting in a sponge structure. The advantage of these techniques is that they result in the loading of hydrophilic or hydrophobic bioactive molecules, whereas the disadvantages are relatively small pore sized scaffolds with precise pore structures that are hard to control (73).

Nano-electrospinning of PGA, PLA, PLGA, caprolactone copolymers, collagen, and elastin, has been extensively developed (74). For example, electrostatic processing can consistently produce PGA fiber diameters $\leqslant 1$ μm. By controlling the pick-up of these fibers, the orientation and mechanical properties can be tailored to the specific needs of the injured site. Also, collagen electrospinning was performed utilizing type I collagen dissolved in 1,1,1,3,3,3-hexafluoro-2-propanol with a concentration of $0.083\ g \cdot mL^{-1}$. The optimally electrospun type I collagen nonwoven fabric appeared with an average diameter of 100 ± 40 nm, which resulted in biomimicking fibrous scaffolds.

Injectable gel scaffolds have also been reported (10,16,51,54). An injectable, gelforming scaffold offers several advantages: (*1*) it can fill any space based on its ability to flow; (*2*) it can load various types of bioactive molecules and cells by simple mixing; (*3*) it does not contain residual solvents that may be present in a preformed scaffold; and (*4*) it does not require a surgical procedure for placement. Typical examples are thermosensitive gels such as Pluronics and PEG-PLGA-PEG triblock copolymer, pH sensitive gels such as chitosan and its derivates, an ionically cross-linked gel such as alginate, and fibrin and hyaluronan gels, as well as others previously introduced in the Natural Polymers section. In the near future, multifunctional gels which are tissue-specific, have a very fast sol–gel transition, are fully degradable over the necessary time period will be available.

Newly hybridized fabrication techniques such as organic–inorganic and synthetic–natural techniques at the nanosize level that biomimic, are also being developed for use in engineered scaffolds.

Physicochemical Characterization of Scaffolds

For the successful achievement of 3D scaffolds, several characterization methods are needed. These methods can be divided into four categories. (*1*) Morphology—porosity, pore size, and surface area; (*2*) mechanical properties—compressive and tensile strength; (*3*) bulk properties—degradation and its relevant mechanical properties; and (*4*) surface properties—surface energy, chemistry, and charge.

Porosity is defined as the fraction of the total volume occupied by voids that appear as percentages. The most widely used methods for the measurement of porosity are mercury porosimetry, scanning electron microscopy (SEM), and confocal laser microscopy.

Mechanical properties are extremely important when designing tissue-engineered products. Conventional testing instruments can be used to determine the mechanical properties of a porous structure. Mechanical tests can be divided into (*1*) creep tests, (*2*) stress–relaxation tests, (*3*) stress–strain tests, and (*4*) dynamic mechanical tests. These test methods are similar to those used for conventional biomaterials.

The rate of degradation of manufactured scaffolds is a very important factor in the design of tissue-engineered products. Ideally, the scaffold constructs provide mechanical and biochemical supports until the entire tissue regenerates, then the scaffold completely biodegrades at a rate consistent with tissue generation. Immersion studies are commonly conducted to track the degradation of the biodegradable matrix. Changes in weight loss and molecular weight can be evaluated by the chemical balance of the matrix, by SEM, and by gel permeation chromatography. These results produce the mechanism of biodegradation.

It is generally recognized that the adhesion and proliferation of different types of cells on polymeric materials depend largely on the materials' surface characteristics, such as wettability (hydrophilicity/hydrophobicity of surface free energy), chemistry, charge, roughness, and rigidity (37,40,41,44,45). The 3D aspects of tissue engineering are more important for cell migration, proliferation, DNA/RNA synthesis, and phenotype presentation on the scaffold materials. Surface chemistry and charge can be analyzed by electron scanning chemical analysis and streaming potential, respectively. Also, wettability of the scaffold surface can be measured by the contact angle using static and dynamic methods.

SURFACE MODIFICATION OF SCAFFOLDS FOR THE IMPROVEMENT OF BIOCOMPATIBILITY

As explained above, the surface properties of scaffold materials are very important. For example, the hydrophobic surfaces of PLA, PGA, and PLGA possess high interfacial free energy in aqueous solutions, which tends to unfavorably influence their cell, tissue, and blood compatibility in the initial stage of contact. Moreover, it does not allow the nutrient media to permeate into the center of the scaffolds. For these reasons, a surface treatment is applied by several methods: (*1*) chemical treatment using oxidants, (*2*) physical treatment using glow discharge, and (*3*) a blend with hydrophilic biomaterials or bioactive molecules.

The physicochemical treatment has been demonstrated to improve the wetting property and hydrophilicity of PLGA porous scaffolds fabricated by the emulsion freeze–drying method (37,45). The chemical treatments were 70% perchloric acid, 50% sulfuric acid, and 0.5 *N* sodium hydroxide solution. The physical methods included corona and plasma treatments generated by a radiofrequency glow discharge. After treatment, water contact angles decreased (Fig. 9). The wetting property of chemically treated PLGA scaffolds also ranked in the order of perchloric acid, sulfuric acid, and sodium hydroxide solution by blue dye intrusion experiment, whereas physical methods had no effect, as shown in Fig. 10. Thus, the chemical treatment method may be useful in uniform cell seeding into porous biodegradable PLGA scaffolds. Wettability plays an important role in cell adhesion, spreading, and growth on the PLGA surface, and the intrusion of nutrient media into the PLGA scaffold.



Figure 9. Changes of water contact angles after physicochemical treatment. The significant decreasing of water contact angle, that is, increased hydrophilicity, was observed.

Scaffolds impregnated with bioactive and hydrophilic material might be better for cell proliferation, differentiation, and migration due to cell stimulation. To give scaffolds new bioactive functionality from SIS powder as a natural source, scaffolds consisting of porous SIS/PLA and SIS/PLGA as a natural–synthetic composite, were prepared by the solvent casting–salt leaching method for use in tissue-engineered bone. A uniform distribution of good interconnected pores from the surface-to-core region was observed (pore size 40–500 μm), independent of the SIS amount, by using the solvent casting–salt leaching method. Porosities, specific pore areas as well as pore size distribution were also similar. After the fabrication of SIS/PLGA hybrid scaffolds, the wetting properties were greatly improved resulting in more uniform cell seeding and distribution, as shown in Fig. 11. Five different scaffolds, a PGA nonwoven mesh scaffold without glutaraldehyde (GA) treatment, PLA scaffolds without and with GA treatment, PLA/SIS scaffolds without and with GA treatment, were implanted into the back of nude mouse to observe the effect of SIS on the induction of cell proliferation by hematoxylin and eosin using von Kossa staining, for 8 weeks. It was observed that the effect of PLA/SIS scaffolds with GA treatment on bone induction is stronger than PLA scaffolds, that is the effects of PLA/SIS scaffolds with GA treatment > PLA/SIS scaffolds without GA treatment > PGA nonwoven > PLA scaffolds only with GA treatment = PLA scaffolds only without GA treatment for osteoinduction activity (Fig. 12).



Figure 10. Wetting properties of physicochemically treated porous PLGA scaffolds by blue dye intrusion methods for 0.5, 1, 2, 4, 12, and 24 h.

STERILIZATION METHODS FOR SCAFFOLDS

The sterilizability of polymeric scaffold biomaterials is an important property, since polymers have lower thermal and chemical stability than other materials, such as ceramics and metals. Consequently, polymers are more difficult to sterilize using conventional techniques. Commonly used sterilization techniques are dry heat, autoclaving, radiation, and ethylene oxide gas (EOG). In addition, plasma glow discharge and electron beam sterilization recently were proposed due to their convenience (6,75).

In dry heat sterilization, the temperature varies between 160 and 190 °C. This temperature is above the melting and softening temperatures of many linear polymers, such as PLGA, resulting in the shrinking of the scaffold dimension. The PLA scaffolds were sterilized at 129 °C for 60 s, resulting in a minimal change in tensile properties. One of the significant problems was a decrease in molecular weight, which might have an affect on the degradation kinetics of the polymers. In the case of polyamide (Nylon) used as a nonbiodegradable polymer, oxidation occurs at the dry sterilization temperature, even though this is below its melting temperature. The only polymers that can safely be dry sterilized are polytetrafluoroethylene (PTFE) and silicone rubber. However, ceramic and metallic scaffolds were safe in this temperature range.

Steam sterilization (autoclaving) is performed under high steam pressure at a relatively low temperature (125–130 °C). However, if the polymer is subjected to attack by water vapor, this method cannot be employed. The PVC, polyacetals, PE (low density variety), and polyamides belong to this category. In the poly(α-hydroxy ester) family, a trace of water can deteriorate the PLGA backbone.

Chemical agents such as EOG and propylene oxide gases, and phenolic and hypochloride solutions are used widely for sterilizing all biomaterials, since they can be used at relatively low temperatures. Chemical agents



Figure 11. Wetting properties of SIS impregnated PLGA scaffolds by red dye intrusion methods. We observed the rapid penetration of water into SIS/PLGA scaffolds compared to the control PLGA scaffolds; (a) control PLGA, (b) 40% SIS/PLGA, and (c) 160% SIS/PLGA scaffolds.



Figure 12. Photomicrographs of von Kossa and H&E histological sections of implanted (a) PGA nonwoven, (b) PLA scaffold only without GA treatment, (c) PLA scaffold only with GA treatment, (d) SIS/PLA scaffold without GA treatment, (e) SIS/PLA scaffold with GA treatment, and (f) SIS/PLA scaffold with GA treatment (H&E) (Original magnification 100×).

sometimes cause polymer deterioration even when sterilization takes place at room temperature. However, the time of exposure is relatively short (overnight), and most scaffolds can be sterilized with this method. The cold EOG sterilization method is the most widely used, with conditions of 35°C and 95% humidity. While the hot EOG method, which uses 60°C and 95% humidity, can cause shrinkage of the PLGA scaffold. One significant problem is residual EOG, which is harmful on the surface and within the polymer. Therefore, it is important that the scaffolds are subjected to adequate degassing or aeration subsequent to EOG sterilization, so that the concentration of residual EOG can be reduced to acceptable levels.

Radiation sterilization using isotopic ^{60}Co can also deteriorate polymers, since at high dosages the polymer chains can be dissociated or crosslinked according to the characteristics of the chemical structures. At a 2.5 Mrad dose, the tensile strength and molecular weight of PLGA decreases. Also, there is a rapid decrease in the molecular weight of the PGA nonwoven felt with increasing doses of radiation. It is important to remember that the properties and useful lifetime of the PLGA implant can be significantly affected by irradiation. In the case of polyethylene, it becomes a brittle and hard material at doses as high as 25 Mrad; This is due to a combination of random chain scission crosslinking. Polypropylene will often discolor during irradiation giving the product an undesirable tint, but a more severe problem is the embrittlement resulting in flange breakage, luer cracking, and tip breakage. The physical properties continued to deteriorate with time following irradiation.

Sterilization methods might significantly affect the physicochemical properties of the scaffold matrix. The specific effects with various methods are determined by the kinds of scaffold materials themselves, the scaffold preparation methods, and the sterilization factors. It is essential that a new standard for sterilizing scaffold devices be designed and established.

CONCLUSIONS

Tissue engineering, including regenerative medicine in recognition of its tremendous potential, has received a revolutionary “research push.” As a result, there have been many reports on the successful regeneration of tissues and organs including skin, bone, cartilage, the peripheral and central nerves, tendon, muscle, cornea, bladder and urethra, and liver as well as composite systems like the human phalanx and joint, using scaffold biomaterials from polymers, ceramic, metal, composites and its hybrids. As previously emphasized, scaffold materials must contain a site of cellular and molecular induction and adhesion, and must allow for the migration and proliferation of cells through porosity. They must also maintain strength, flexibility, biostability, and biocompatibility to mimic a more natural, 3D environment. From this standpoint, control over a precise biochemical signal must be fostered by the combination of a scaffold matrix and bioactive molecules including genes, peptide molecules, and cytokines. Moreover, the combination of cells and redesigned bioactive scaffolds should expand to a tissue level of hierarchy. To achieve this goal, novel scaffold biomaterials, scaffold fabrication methods, and characterization methods must be developed.

ACKNOWLEDGMENTS

This work was supported by grants from the Korea Ministry of Wealth and Health (0405-BO01-0204-0006) and stem cell Research Center (SC3100).

BIBLIOGRAPHY

Cited References

1. Langer R, Vacanti J. Tissue engineering. Science 1993;260: 920–926.
2. Nerem RM , Sambanis A. Tissue engineering: from biology to biological substitutes. Tissue Eng 1995;1:3–13.
3. Griffith LG, Naughton G. Tissue engineering—Current challenges and expanding opportunity. Science 2002;295:1009–1014.
4. Baldwin SP, Saltzman WM. Materials for protein delivery in tissue engineering. Adv Drug Deliv Rev 1998;33:71–86.
5. Mann BK, West JL. Tissue engineering in the cardiovascular system: Progress toward a tissue engineered heart. Anat Record 2001;263:367–371.
6. Lee HB, Khang G, Lee JH. Chapter 3, Polymeric biomaterials. In: Park JB, Bronzino JD, editors. Biomaterials: Principles and Applications. Boca Raton: CRC Press; 2003.
7. Patrick CW, Jr. Tissue engineering strategies for adipose tissue repair. Anat Record 2001;263:361–376.
8. Petit-Zeman S. Regenerative medicine. Nature Biotech 2001;19:201–206.
9. Hench LL, Polak JM. Third-generation biomedical materials. Science 2002;295:1014–1017.
10. Seal BL, Otero TC, Panitch A. Polymeric biomaterials for tissue and organ generation. Mater Sci Eng 2001;R34:147–230.
11. Babensee JE, McIntire LV, Mikos AG. Growth factor delivery for tissue engineering. Pharm Res 2000;17:497–504.
12. Chaignaud BE, Langer R , Vacanti JP. Chapter 1, The history of tissue engineering using synthetic biodegradable polymer scaffolds and cells. In: Atala A, Mooney DJ, editors. Synthetic Biodegradable Polymer Scaffolds. Boston: Birkhauser; 1996.
13. Rose FRA, Oreffo ROC. Bone tissue engineering: Hope vs Hype. Biochem Biophys Res Commun 2002;292:1–7.
14. Freyman TM, Yannas IV, Gibson LJ. Cellular materials as porous scaffolds for tissue engineering. Prog Mater Sci 2001;46:273–282.
15. Woolverton CJ, Fulton JA, Lopina ST, Landis WJ. Chapter 3, Mimicking the natural tissue environment. In: Lewandrowski K-U, Wise DL, Trantolo DJ, Gresser JD, Yasemski MJ, Altobeli DE, editors. Tissue Engineering and Biodegradable Equivalents: Scientific and Clinical Applications. New York: Marcel Dekker; 2002.
16. Tabata Y. The importance of drug delivery systems in tissue engineering. PSTT 2000;3:80–89.
17. Wong WH, Mooney DJ. Chapter 4, Synthesis of properties of biodegradable polymers used as synthetic matrices for tissue engineering. In: Atala A, Mooney DJ, editors. Synthetic Biodegradable Polymer Scaffolds. Boston: Birkhauser; 1996.
18. Rwoley JA, Madlambayan G, Mooney DJ. Alginate hydrogels as synthetic extracellular matrix. Biomaterials 1999;20:45–53.
19. Shakibaei M, De Souza P. Differentiation of mesenchymal limb bud cells to chondrocytes in alginate bead. Cell Biol Int 1997;21:75–86.
20. Madihally SV, Matthew HW. Porous chitosan scaffolds for tissue engineering. Biomaterials 1999;20:1133–1142.
21. Kang HW, Tabata Y, Ikada Y. Fabrication of porous gelatin scaffolds for tissue engineering. Biomaterials 1999;20:1339–1344.
22. Dunn CJ, Goa KL. Fibrin sealant: A review of its use in surgery and endoscopy. Drugs 1999;58:863–886.
23. Mayne R, Burgeson RE. Structure and function of collagen types. In: Mecham RP, editor. Biology of extracellular matrix: A Series. Orlando: Academic Press; 1987.
24. Li S-T. Chapter 6, Biologic biomaterials: Tissue-derived biomaterials (Collagen). In: Park JB, Bronzino JD, editors. Biomaterials: Principles and Applications. Boca Raton (FL): CRC Press; 2003.
25. Schense JC, Bloch J, Aebischer P, Hubbell JA. Enzymatic incorporation of bioactive peptides into fibrin matrices enhances neurite extension. Nature Biotech 2000;18:415–419.
26. Zacchi V, Soranzo C, Cortivo R, Radice M, Brun P, Abatangelo G. In vitro engineering of human skin-like tissue. J Biomed Mater Res 1998;40:187–194.
27. Malette WG, Quigley HJ, Gaines RD, Johnson ND, Rainer WG. Chitosan: a new hemostatic. Ann Thorac Surg 1983;36: 55–58.
28. Sechriest VF, Miao YJ, Niyibizi C, Westerhauzen-Larson A, Matthew HW, Evans CF, Fu FH, Suh J-K. GAG-augmented polysaccharide hydrogel: a novel biocompatible and biodegradable material to support chondrogenesis. J Biomed Mater Res 2000;49:534–541.
29. Lee YM, Park YJ, Lee SJ, Ku Y, Han SB, Choi SM, Klokkevoid PR, Chung CP. Tissue engineered bone formation using chitosan/tricalcium phosphate sponges. J Periodontol 2000; 71:410–417.
30. Lee DA, Noguchi T, Knight MM, O'Donnell L, Bently G, Bader DL. Response of chondrocyte subpopulations cultured within unloaded and loaded agarose. J Orthop Res 1998;16: 726–733.
31. Lee DA, Frean SP, Lee P, Bader DL. Dynamic mechanical compression influences nitric oxide production by articular chondrocytes seeded in agarose. Biochem Biophys Res Commun 1998;251:580–585.
32. Badylak SF, Record R, Lindberg K, Hodde J, Park K. Small intestine submucosa: a substrate for in vitro cell growth. J Biomater Sci, Polymer Ed 1998;9:863–878.
33. Khang G, Shin P, Kim I, Lee B, Lee SJ, Lee YM, Lee HB, Lee I. Preparation and characterization of small intestine submucosa particle impregnated PLA scaffolds: The application of tissue engineered bone and cartilage. Macromol Res 2002;10:158–167.
34. Badylak SF. The extracellular matrix as a scaffolds for tissue reconstruction. Cell Develop Biol 2002;13:377–383.
35. Gustafson C-J, Katz G. Cultured autologous keratinocytes on a cell-free dermis in the treatment of full-thickness wounds. Burns 1999;25:331–335.
36. Williams SF, Martin DP, Horowitz DM, Peoples OP. PHA applications: Addressing the price performance issue, I. Tissue Engineering. Int J Biolog Macromol 1999;25:111–121.
37. Khang G, Lee HB. Chapter 67. Cell-synthetic surface interaction: Physicochemical surface modifications. In: Atala A, Lanza R, editors. Orlando: Academic Press; 2001.
38. Khang G, Seong H, Lee HB. Sustained delivery of drugs with biodegradable. In: Hsuie GH, Okano T, Kim YU, Sung W-W, Yui N, Park KD, editors. Taipei, Taiwan: Princeton International Publishing Co.; 2002.
39. Khang G, Lee SJ, Han CW, Rhee JM, Lee HB. Preparation and characterization of natural/synthetic hybrid scaffolds.

In: Elcin M, editor. London, England: Kluwer-Plenum Press; 2003.

40. Khang G, Lee JH, Lee I, Rhee JM, Lee HB. Interaction of different types of cells on PLGA surfaces with wettability chemogradient. Macromol Res 2000;8:276–284.
41. Khang G, Choi MK, Rhee JM, Rhee SJ, Lee HB, Iwasaki Y, Nakabayashi N, Ishihara K. Biocompatibility of poly(MPC-*co*-EHMA)/PLGA blends. Macromol Res 2001;9:107–115.
42. Khang G, Park CS, Rhee JM, Lee SJ, Lee YM, Lee I, Choi MK, Lee HB. Preparation and characterization of demineralized bone particle impregnated PLA scaffolds. Macromol Res 2001;9:267–276.
43. Choi HS, Khang G, Shin H-C, Rhee JM, Lee HB. Preparation and characterization of fentanyl-loaded PLGA microspheres; *In vitro* release profiles. Int J Pharm 2002;234:195–203.
44. Lee SJ, Khang G, Lee YM, Lee HB. Interaction of human chondrocyte and fibroblast cell onto chloric acid treated poly(α-hydroxy acid) surface. J Biomater Sci, Polym Ed 2002;13:197–212.
45. Khang G, Choi CW, Rhee JM, Lee HB. Interaction of different types of cells on physicochemically treated PLGA surfaces. J Appl Polym Sci 2002;85:1253–1262.
46. Khang G, Jeon EK, Rhee JM, Lee I, Lee SJ, Lee HB. Controlled release of NGF from sandwiched PLGA films for the application of neural tissue engineering. Macromol Res 2003; 11:334–340.
47. Jang JW, Lee B, Han CW, Lee I, Lee HB, Khang G. Preparation and characterization of ipriflavone-loaded PLGA scaffolds for tissue engineered bone. Polymer(Korea) 2003;27:226–234.
48. Khon J, Langer R. Chapter 2.5, Bioresorbable and bioerodible materials. In: Ratner BD, Hoffman AS, Scheon FJ, Lemons JE, editors. Biomaterials Science: An Introduction to Materials in Medicine, San Diego: Academic Press; 1996.
49. Vacanti CA, Langer R, Schloo B, Vacanti JP. Synthetic polymers seeded with chondrocytes provide a template for new cartilage formation. Plast Reconstr Surg 1991;88:753–759.
50. Burg KJL, Porter S, Kellam JF. Biomaterials developments for tissue engineering. Biomaterials 2000;21:2347–2359.
51. Gutowska A, Jeong B, Jasionowski M. Injectable gel for tissue engineering. Anat Record 2001;263:342–349.
52. Suggs LJ, Krishna RS, Garcia CA, Peter SJ, Anderson JM, Mikos AG. In vitro and in vivo degradation of poly(propylene fumarate-*co*-ethylene glycol) hydrogel. J Biomed Mater Res 1998;42:312–320.
53. Harris JM, editor. Poly(ethylene glycol) Chemistry: Biotechnical and Biomedical Applications. New York: Plenum Publish. Co.; 1997.
54. Qui Y, Park K. Environment-sensitive hydrogels for drug delivery. Adv Drug Deliv Rev 2001;53:321–339.
55. Webb D, An YH, Gutowska A, Mironov VA, Friedman RJ. Propagation of chondrocytes using thermosensitive polymer gel culture. Orthoped J Musc Orthoped Surg 2000;3:18–22.
56. Sims CD, Butler P, Casanova R, Lee BT, Randolph MA, Lee A, Vacanti CA, Yaremchuk MJ. Injectable cartilage using polyethylene oxide polymer substrate. Plast Reconstruct Surg 1996;95:843–850.
57. Laurencin CT, El-Amin SF, Ibim SE, Willoughby DA, Attawia M, Allcock HR, Ambrosio AA. A highly porous 3-dimensional polyphosphazene polymer matrix for skeletal tissue engineering. J Biomed Mater Res 1996;30:133–138.
58. Agarwal S, Gassner R, Piesco NP, Ganta SR. Chapter 7, Biodegradable urethanes for biomedical applications. In: Lewandrowski K-U, Wise DL, Trantolo DJ, Gresser JD, Yasemski MJ, Altobeli DE, editors. Tissue Engineering and Biodegradable Equivalents: Scientific and Clinical Applications. New York: Marcel Dekker; 2002.
59. Zhang JY, Beckman EJ, Piesco NP, Agarwal S. A new peptide based urethane polymer: synthesis, degradation, and potential to support cell growth in vitro. Biomaterials 2000;21:1247–1258.
60. Billotte WG. Chapt. 2, Ceramic biomaterials. In: Park JB, Bronzino JD, editors. Biomaterials: Principles and Applications. Boca Raton (FL): CRC Press; 2003.
61. Hench LL. Bioactive ceramics. Ann NY Acad Sci 1988; 523:54–71.
62. Frician JC, Bareille R, Rouais F. In vitro dissolution of coral in periodontal or fibroblast cell culture. J Dent Res 1998;77:406–411.
63. Yoshikawa T, Oghushi H, Uemura T. Human marrow cells derived cultured bone in porous ceramics. Bio-Med Mater Eng 1998;8:311–320.
64. Unpublished data.
65. Krewson C, Dause R, Mak M, Saltzman WM. Stabilization of nerve growth factor in controlled release polymers and in tissue. J Biomater Sci, Polym Ed 1996;8:103–117.
66. Haller MF, Saltzman WM. Localized delivery of proteins in the brain. Pharm Res 1998;15:377–385.
67. Ito Y, Lui SQ, Imanishi Y. Enhancement of cell growth on growth factor-immobilized polymer films. Biomaterials 1991; 12:449–453.
68. Khul PR, Grriffith-Cima LG. Tethered epidermal growth factor as a paradigm for growth factor-induced stimulation from the solid phase. Nature Med 1996;2:1022–1027.
69. Duncan R, Spreafico F. Polymer conjugates. Pharmacokinetic considerations for design and development. Clin Pharmacokinet 1994;27:290–306.
70. Massia SP, Hubbell JA. Covalent surface immobilization of Arg-Gly-Asp- and Tyr-Ile-Gly-Ser-Arg-containing peptides to obtain well-defined cell-adhesive substrate. Anal Biochem 1990;187:292–301.
71. Leibmann-Vinson A, Hemperly JJ, Guarino RD, Spargo CA, Heidaran MA. Chapter 36, Bioactive extracellular matrices: Biological and biochemical evaluation. In: Lewandrowski KU, Wise DL, Trantolo DJ, Gresser JD, Yasemski MJ, Altobeli DE, editors. Tissue Engineering and Biodegradable Equivalents: Scientific and Clinical Applications. New York: Marcel Dekker; 2002.
72. Thompson RC, Wake MC, Yasemski MJ, Mikos AG. Biodegradable polymer scaffolds to regenerate organs. Adv Polym Sci 1995;122:245–274.
73. Khang G, Jeon JH, Cho JC, Lee HB. Fabrication of tubular porous PLGA scaffolds by emulsion freeze drying methods. Polymer(Korea) 1999;23:471–177.
74. Bowlin GL, Pawlowski KJ, Boland ED, Simpson DG, Fenn JB, Wnek GE, Stitzel JD. Chapter 9, Electrospinning of polymer scaffolds for tissue engineering. In: Lewandrowski K-U, Wise DL, Trantolo DJ, Gresser JD, Yasemski MJ, Altobeli DE, editors. Tissue Engineering and Biodegradable Equivalents: Scientific and Clinical Applications. New York: Marcel Dekker; 2002.
75. Athanasious KA, Neiderauer GG, Agrawal CM. Sterilization, toxicity, biocompatibility and clinical applications of polylactic acid/polyglycolic acid copolymers. Biomaterials 1996;17:93–102.

Reading List

Jeon EK, Khang G, Lee I, Rhee JM, Lee HB. Preparation and release profile of NGF-loaded PLA scaffolds for tissue engineered nerve regeneration. Polymer(Korea) 2001;25:893–901.

See also ENGINEERED TISSUE; STERILIZATION OF BIOLOGIC SCAFFOLD MATERIALS.

BIOMECHANICS OF EXERCISE FITNESS

Gideon Ariel
Ariel Dynamics
Canyon, California

INTRODUCTION

Normal human development spans a lifetime from infancy to old age. Modern civilization is confronted with the lengthening of that time and its effect on the individual and society. Housing improvements, employment alterations, labor saving devices, and modern medicine are but a few of the factors protecting humanity from those instances which previously shortened life. While many of the difficult, threatening experiences have been eliminated or reduced in severity, problems remain to be solved. Concerns for the quality of life as people become older include maintaining self-sufficiency. Many solutions conflict with beliefs generally termed "current wisdom" in areas, such as training, dieting, exercising, and aging. While society ages, the challenge for each individual is to strive to retain the lowest "biological" age while their "chronological" birthdays increase. The dilemma concerns the best way to accomplish this task.

The main purpose of this article is to focus on the biomechanical principles of movement, the scientific bases of training and fitness, and the optimization of human performance at any age. These are not just nonsense concepts added to the quantities of known theories, but are objectively quantifiable procedures that encompass our understandings and can produce precise conclusions. Mathematical principles and gravitational formulations provide the cornerstones for optimizing human performance. Biological, anatomical, physiological, and medical discoveries are always under investigation, challenge, and improvement and these findings will be incorporated into many of the current theories. Figure 1 illustrates just part of the anatomy and its complicated structure. The struggle will continue among scientists to establish new principles for revolutionizing the world of gerontology, diet, physical fitness and training, and amplifying those factors necessary for extending life not only in length, but also in quality. Scientists with expertise in many different areas will be addressing the problems associated with aging from their specialized perspective.

In order to address the optimization of human movement and performance, the underlying philosophical premise metaphorically compares life with sport. The goal is that everyone should be a gold medalist in their own body regardless of age. Most people, however, do not achieve their Gold Medal because their goals, potential, and/or timing are uncoordinated or nonexistent. For example, an individual may envision themselves as a tennis champion, yet lack the requisite physical and physiological traits of the greatest players. Given this situation, can a person's potential be maximized? Achieving one's maximum potential necessitates tools applicable to everyone for improving their performance, whether in tennis, fitness, overcoming physical handicaps, or fighting disease. Useful tools must be based, however, on correct, substantive scientific principles.

SCIENTIFIC PRINCIPLES FOR QUANTIFYING MOTION

Human movement has fascinated humans for centuries including some of the world's greatest thinkers, such as Leonardo da Vinci, Giovanni Borelli, Wilhelm Braune, and others. Many questions posed by these stellar geniuses have been or can be addressed by the relatively new area of Biomechanics. Biomechanics is the study of the motion of living things, primarily, and it has evolved from a fusion of the classic disciplines of anatomy, physiology, physics, and engineering. Bio refers to the biological portion, incorporating muscles, tendons, nerves, and so on, while mechanics is associated with the engineering concepts based upon the laws described by Sir Isaac Newton. Human bodies consist of a set of levers that are powered by muscles. Quantification of movements, whether human, animal, or inanimate objects, can be treated within biomechanics according to Newtonian equations. It may seem obvious, with the perfect vision of hind sight, that humans and their activities, such as the wielding of tools (e.g., hammer, axe) or implements (e.g., baseball bat, golf club, discus), must obey the constraints of gravitational bodies, just as bridges, buildings, and cars do. For some inexplicable reason, humans and their activities had not been subjected to the appropriate engineering concepts that architects would use when determining the weight of books to be housed in a new library or engineers would apply to designing a bridge to span a wide, yawning abyss. It was not until Newton's



Figure 1. The human structure.



Figure 2. The modern coach and his tools.

apple fell again during the twentieth century that biomechanics was born.

Biomechanics, then, is built on a foundation of knowledge and the application of the basic physical laws of gravitational effects as well as those of anatomy, chemistry, physiology, and other human sciences. Early quantification efforts of human movement organized the body as a system of mechanical links. Activities were recorded on movie film that normally consisted of hundreds of frames for each of the desired movement segment. Since each frame of the activity had to be processed individually, the task was excessively lengthy, tedious, and time intensive. Figure 2 illustrates an abstract of todays sophisticated coaching tools in athletics. The hand calculations of a typical 16 segment biomechanical human required many hours for each frame, necessitating either numerous assistants or an individual investigator's labor-of-love and, frequently, both. Unfortunately, these calculations were susceptible to numerical errors.

The introduction of large, main-frame computers improved reliability and reasonableness of the results, replacing much of the skepticism or distrust associated with the manually computed findings. Computerization accelerated the calculations of a total movement much more rapidly than had been previously possible, but presented new difficulties to overcome. Many of the early biomechanical programs were cumbersome, time intensive main-frame endeavors with little appeal except to the obsessed, devotee of computers, and movement assessment. However, even these obstacles were conquered in the ever expanding computerization era. The computerized hardware/software system provides a means to objectively quantify the dynamic components of movement in humans regardless of the nature of the event. Athletic events, gait analyses, job-related actions as well as motion by inanimate objects, including machine parts, air bags, and auto crash dummies are all reasonable analytic candidates. Objectivity replaces mere observation and supposition.

One of the most important aspects included in the Bio portion of biomechanics is the musculoskeletal system. Voluntary human movement is caused by muscular contractions that move bones connected at joints. The neuromuscular system functions as a hierarchical system with autonomic and basic, life sustaining operations, such as heart rate and digestion, controlled at the lowest, noncognitive levels and with increasing complexities and regulatory operations, such as combing the hair or kicking a ball, controlled by centers that are further up the nervous system. Interaction of the various control centers is regulated through two fundamental techniques each governed like a servosystem.

The first technique equips each level of decision making with subprocessors that accept the commands from higher levels as well as accounting for the inputs from local feedback and environmental information sensors. Thus, a descending pyramid of processors is defined that can accept general directives and execute them in the presence of varying loads, stresses, and other perturbations. This type of input–output control is used for multimodal processes, such as maintaining balance while walking on an uneven terrain, but would be inappropriate for executing deliberate, volitional, complex tasks like the conductor using the baton to coordinate the music of the performing musicians.

The second technique utilized by the brain to control muscular contractions applies to the operation of higher level systems that generate output strategies in relation to behavioral goals. These tasks use information from certain sensory inputs, including joint angle, muscle loading, and muscular extension or flexion that are assessed, transmitted to higher centers for computation, which then executes the set of modified neural transmissions received. Cognitive tasks requiring the type of informational input that influences actions are the ones with which humans are most familiar since job execution requires more thought than breathing or standing upright. A frequently misunderstood concept is that limb movement is possible only through contractions of individual muscle fibers. For most cases of voluntary activity, muscles work in opposing pairs with one set of muscles opening or extending the joint (extensors) while the opposite muscle group closes or flexes the joint. The degree of contraction is proportional to the frequency of signals from the nerve as signaled from the higher centers. Movement control is provided by a programmable mechanism so that when flexors contract, the extensors relax, and vice versa. The motor integration programmed generated in the higher, cognitive levels regulates not only the control of the muscle groups around a joint, but also those necessary actions by other muscles and limbs to redistribute weight, to counteract shifts in the center of gravity.

One of the most important, but frequently misunderstood, concepts of the nervous system is the control and regulation of coordinated movement. When a decision is made to move a body segment, the prime muscles or agonists receive a signal to contract. The electrical burst stimulates the agonist muscular activity causing an acceleration of the segment in the desired direction. At the same time, a smaller signal is transmitted to the opposite muscle group, or antagonist, which causes it to function as a joint stabilizer. With extremely rapid movements, the antagonist is frequently stimulated to slow the limb in time to


"Desired" course of action from "higher" centers
Controller
Control signal
Controlled system
Output
Feedback as to current state of system
Sensors

Figure 3. Feedback control mechanism of movement.

protect the joint from injury. It is the strength and duration of the electrical signal to both the agonist and antagonist that govern the desired action. The movement of agonists and antagonists, whether a cognitive process, such as throwing a ball, or an acquired activity, such as postural control, is controlled by the nervous system. Figure 3 illustrates a flowchart for the control system for movement. Many ordinary voluntary human activities resulting from agonist–antagonist muscular contraction are classified by different terms, isotonic, variable resistance, and ballistic. Slower movements, demonstrating smaller, more frequent, electrical signal alterations, are intricately controlled by both agonist and antagonist. These types of motion are tracking movements.

One control mechanism available involves the process of information channeled between the environment and the musculature. Closed-loop control involves the use of feedback whereby differences between actual and desired posture are detected and subsequently corrected, whereas open-loop control utilizes feed forward strategies that involve the generation of a command based on prior experience rather than on feedback. Braitenberg and Onesto (ARBIB) proposed a network for converting space into time by providing that the position of an input would determine the time of the output. This open loop system would trigger a preset signal from the nervous system to the muscle generating a known activity. Kicking a ball, walking, throwing a baseball, swinging a golf club, and hand writing are considered ballistic movements.

When a limb moves, a sophisticated chain of events occurs before, during, and after the movement is completed. The fineness of control depends on the number of muscle fibers innervated by each motor neuron. A motor unit is generally defined as a single motor neuron and the number of muscle fibers it innervates. Fine control is achieved when a single motor neuron innervates just a few fibers. Less fine control, as in many large muscle groups, is attained when individual motor units innervate hundreds or even thousands of fibers. The more neurons there are, the finer the ability to maneuver, as with eye movements or delicate hand manipulations. In contrast to the high innervations ratio of the eye, the biceps of the arm has a very low rate of nerve-to-muscle fiber resulting in correspondingly more coarse movements.

While the amount of nervous innervations is important when anticipating the precision of control, the manner of interaction and timing between muscles, nerves, and desired outcome is probably more important when evaluating performance. Recognizable actions elicit execution of patterned, synchronous nervous activity. Frequently repeated movements are usually performed crudely in the beginning stages of learning, but become increasingly more skilled with use and/or practice. Consider the common activity of handwriting and the execution of one's own signature. The evolution from a child's irregular, crude printing to an adult's recognizable, consistently repeatable signature is normal. Eventually, the individual's signature begins to appear essentially the same every time and is uniquely different from any other person. Not only can the person execute handwritten signatures consistency, but can use chalk to sign the name in large letters on a blackboard producing a recognizably similar appearance. The individuality of the signature remains whether using the fine control of the hand or recruiting the large shoulder and arm muscles not normally required for the task. Reproduction of recognizable movements occurs from preprogrammed control patterns stored in the brain and recruited as necessary. Practicing a golf swing until it results in a 300 yard drive down the middle of the fairway, getting the food-laden fork from the plate into the mouth, and remembering how to ride a bike after a 30 year hiatus illustrate learned behavior that has become "automatic" with practice and can be recalled from the brain's storage for execution.

Volitional tasks require an integration of neurological, physiological, biochemical, and mechanical components. There are many options available when performing a task, such as walking, but eventually, each person will develop a pattern that will be recognizable as that skill, repeatable, and with a certain uniqueness associated with that particular individual. Although any person's movement could be quantified with biomechanical applications and compared to other performers in a similar group, for example, the gold, silver, and bronze medalists in an Olympic event, perhaps it will be the ability to compare one person to themselves that will provide the most meaningful assistance in the assault on aging.

There are many areas of daily living in which biomechanical analyses could be useful. Biomechanics could be utilized to design a house or chair to suit the body or to lift bigger, heavier objects with less strain. This science could be useful in selecting the most appropriate athletic event for children or for improving an adult's performance. With increasing international interest in competitive athletics, it was inevitable that computers would be used for the analysis of sports techniques. Computer calculations can provide information that surpasses the limits of what the human eye can see and intuition can deduce. Human judgment, however, is still critically important. As in business and industry, where decisions are based ultimately upon an executive's experience and interpretive ability, the coach or trainer is, and will remain, the ultimate decision maker in athletic training. Rehabilitation and orthopedic specialists can assess impaired movement relative to normal performance and/or apply computerized biomechanical techniques to the possibilities of achieving the restoration of normal activities. With the increase in the population of older citizens, erotological applications will increase. The computer should be regarded as one more tool, however, complex, which can be skillfully used by humans in order to achieve a desired end.

One factor that humans have lived with is change. The environment in which we live is changing during every one of the ~ 35 million min of our lives. The human body itself changes from birth to maturity and from maturity to death. The moment humans first picked up a stone to use as a tool, the balance between humans and the environment was altered. After that adaptation, the ways in which the surrounding world changed resulted in different effects and these were no longer regular or predictable. New objects were created from things that otherwise would have been discounted. These changes were made possible by humans due to the invention of tools. The more tools humans created, the faster was the rate of environmental change. The rate of change due to tools has reached such a magnitude that there is danger to the whole environment and frequently to the people who use the tools, such as occurred during the Industrial Revolution, as well as in our own times with such problems as carpal tunnel syndrome. Human beings seem to have become so infatuated with their ability to invent things that they have concentrated almost exclusively upon improving the efficiency, safety, durability, cost, or aesthetic appeal of the device. It is ironic that with all of the innovative development, little consideration has been given to the most complex system with the most sophisticated computer in the world: the human body.

When they talk about their physical goals in work or in sports, people usually say they would like to do their best, meaning, reach their maximum output. It is a matter of achieving their absolute limit in speed, strength, endurance or skill and combining the elements with accuracy. This is no different than an athlete training for maximum performance in the Olympic games. The difficulty with focusing everything on maximum performance is that only a single goal, getting the highest results—fastest, biggest, quickest, longest, or most graceful—is considered a superlative or acceptable achievement. Maximums do not take into consideration other aspects of body performance that often prove to be just as important to the individual. Emphasis upon the demands for maximum performance is frequently portrayed with the thought that Winning isn't everything, it's the only thing. Figure 4 illustrates todays sophisticated biomechanical system to quantify human performance.



Figure 4. The modern biomechanical system.

Imagine for a moment a maximum performance in the car industry—the perfect automobile. It is incredibly graceful and the aerodynamic, functional lines make it a thing of beauty. It accelerates from 0 to 60 miles $\cdot$ h^{-1} within a few seconds. It brakes, corners, and steers with a fineness that would permit a shortsighted 75-year old to compete at Le Mans. The suspension is so smooth that a passenger can pour liquids without spilling a drop. The car requires only minimal maintenance while averaging 50 miles $\cdot$ gal^{-1} in city driving. Best of all, it is the vehicle of the common man at a price of $5000. If all that sounds impossible—it is. Incorporating all of these maximums into a single automobile exceeds the ability of any designer or manufacturer. Instead, the individual shopping for a car must choose the attributes he or she feels are most important.

Therein lies the problem, some goals are partly, if not wholly, incompatible with others. An automatic transmission uses more gas than a standard shift, but it does make driving easier. Sleek aerodynamic lines add grace and reduce drag, but they can also lessen head room. High performance engines provide power, but require constant care. The solution is a compromise, a willingness to make tradeoffs.

This same spirit of compromise, of accepting something less than a single maximum, should govern the operation of the most important machine in our lives—our body. Reality must be applied when comparing ourselves to Olympic athletes or, with the progression of age, mimicking various youthful physical activities. For example, there is no need to have an endurance capacity equal to the current gold medalist or the strength level equivalent to the World heavyweight record holder. Likewise, senior citizens may resist relinquishing their drivers' licenses despite their slower reaction times, poorer eyesight, and/or hearing, as well as frequently suffering from some type of chronic disease that may further reduce their strength, joint mobility, or even cognitive processes, such as memory or decision making.

Instead of a maximum, what most people really want from their bodies is to optimize their performances and lives. They seek the most efficient use of energy, of bodily action consonant with productive output, health, and enjoyment. Many people are beginning to appreciate that certain types of exercise add to the vitality of the cardiovascular system, lessen the risk of heart attack, and make it possible to live longer and more active lives. In other words, the willingness to sacrifice 20 yards on a drive off the golf tee may mean that the golfer's feet will be able to walk the entire course without being tortured during every step. The desire is to play a couple of hours of winning tennis, stroking the ball with pace and purpose, but not if the extra zing means a tennis elbow that will be sore for several weeks. Sensible joggers prefer to run 6 rather than 10 miles a day in 40 min, if the latter leads to tender knees and shin splints. In other words, human beings must compromise between anatomy (the structural components) and physiology (the bodily processes). A correct balance between the two, at all ages, will assist in optimizing bodily efficiency.

In addition to the desire for our internal environment to be physical fit, pertinent questions should be posed about our external environment. For example, is it really necessary for that designer chair to cause a bone ache deep in the buttocks after sitting for 5 min? Can a person not spend a day laboring over a desk or piece of machinery without feeling as if a rope had been tightly tied around the shoulders at the end of the project? Why must a weekend with shovel or rake inevitably produce lower back pain on Monday? Why is it that some individuals who are 50 years old seem able to work and play as if 10–20 years younger, while some 30 year olds act as if infected with a malignant decrepitude? The answer is that, as with the anatomy and physiology achieving optimal coordination, so should the whole human organism coordinate better with its environment.

Perhaps these examples could be dismissed as the minor aches of a hypochondriac society overly concerned with its comfort. But the overall health facts for the United States and many other modern civilizations appall even those jaded by constant warnings of disaster. The American Heart Association, in urging the 2005 Congress to fund prevention programs, contends that the Number One killer of Americans is heart disease, stroke, and other cardiovascular diseases. In addition, a total of 75 million Americans are afflicted with chronic disease. On any given day, >1 million workers do not show up for their jobs because of illness, and sickness prevents a million of these from returning in <1 week. Twenty-eight million Americans have some degree of disability. Perhaps not coincidentally, a quarter of the population is classified as overweight. At least 3 million citizens have diabetes, and one-half are unaware of the problem, and the United States accounts for most of the deaths due to cardiovascular disease. The health profile of the future, the condition of the youth of today, offers no comfort. About 1 in 5 youngsters still cannot pass even a simple test of physical performance. More than 9 million American children under the age of 15 have a chronic ailment. From one-third to one-half of U.S. children are overweight and one-third of America's young men fail to meet military physical fitness requirements.

In pursuit of technological achievement, Americans have almost ignored the one major element besides food and rest needed to sustain the human body: physical activity. This has lent impetus to a subtle yet deadly disease that has reached epidemic proportions in this country and others. Cardiovascular disease is often referred to as hypokinetic disease or lack of-motion disease. Unfortunately, degeneration with Americans begins earlier rather than later. One study indicates that middle age characteristics start to show at approximately age 26. The peak age for heart disease among American men is 42 years. In Europe, it is 10 years later. A corporate wide employee health survey conducted by a large computer manufacturer indicated that smokers have 25% higher healthcare costs and 114% longer hospital stays than nonsmokers. People who did not exercise have 36% higher healthcare costs and 54% longer hospital stays than people who did exercise. Overweight people have 7% higher healthcare costs and 85% longer hospital stays than people who are not. In general, people with poor health habits have higher healthcare costs, longer hospital stays, lower productivity, more absenteeism, and more chronic health problems than those who do not. Some questions both workers and their companies should ask are (*1*) How many heart attacks, strokes, cancers, or coronary by-pass operations did your company pay for last year? (*2*) How much better would profits have been if heart diseases had been reduced 10, 20, or 30%? (*3*) How much would corporate profits increase if employee healthcare costs were reduced by 10%?

One large U.S. corporation developed a comprehensive wellness program at numerous sites. During the first year, grievances decreased by 50%, on-the-job accidents by 50%, lost time by 40%, and sickness and accident payments by 60%. The corporation estimated at least a 3:1 return per dollar invested.

The requirement for such an optimum way of life is a scientific analysis of the way people live and use their bodies. Only after such a quantitative examination can a concept of cost be determined or a better way of doing something that is more efficient and less damaging to the body, discovered. For example, rapid weight loss may result from running long distances, such as 15 miles a day, fasting drastically, or performing aerobics for 5 h a day. However, such excessive training regimens may be as detrimental to the body as sitting all day in an easy chair and simply ignoring one's obesity.

Evolution, culture, and the changing demands of existence have tended to develop forces and stresses upon the body that are not necessarily in harmony with the basic design and structure of the human equipment. Standing upright, humans employ one pair of extremities for support and the other pair capable of tremendous versatility. It would seem that of all animals, humans, fortuitously assisted by the evolution of their brain and other organs, optimized the use of their body. Unfortunately, the human body has had to pay a stiff price for its upright posture. Human vertical posture is inherently unstable; therefore, humans must devote more neuromuscular effort and control to maintain balance, than four-legged animals. There is a tendency to lean forward, which adds to the ability to move in that direction, but increases the risk of falling.

A complex neuromuscular process is constantly at work to prevent humans from toppling. Many things may interfere with this balancing act, such as consuming too much whiskey or walking on an icy sidewalk. These interruptions of the flow of information to and from the brain centre which coordinates the balancing process can result in staggering or falling. This postural condition creates a constant strain on all the muscles employed to retain balance and upon the set of bones forming the spine. The spine is basically a tower of I-beams supports the skeletal frame and, in order to remain in good health, proper mechanical alignment is essential. Any deviation from this mechanical alignment will result in pain relating to non-alignment, such as low back or neck pain. The vulnerability of the back is threatened frequently by work, recreation situations, and furnishings, since their uses subject an already tenuous upright position to undergo increased stresses. As the body compensates for alignment problems by creating excess bone tissue and neural pain, certain arthritic conditions may be the result.

Correction or prevention in tools or activities may assist in the optimization of performance and in more closely aligning the biological with the chronological age. Clearly, optimization and compensation may conflict within the human mechanism since a logical idea may violate physical principles. Based on this introduction of merely a few of the internal and external challenges to the human organism, the need for adequate and accurate assessments, improved tools, and human behavioral modifications becomes more apparent.

With each passing year, the composition of the population in America and probably many other modern societies is becoming older. This population increase of older citizens appears to be due, in part, to the large number of individuals of all ages who are experiencing modifications of lifestyle in a variety of ways, including better working conditions, improved health–medical opportunities, and changing activity levels. Pollock et al. (1) noted that the activity levels of elderly people have increased during the previous 20 years. However, it was estimated that only 10% of elderly individuals participate in regular vigorous physical activity and that 50% of the population who are 60 or more years of age described their lifestyles as sedentary.

Scientific studies and personal experiences continue to link many of the health problems and physical limitations found in the aged to lifestyle. Sedentary living appears to be a major contributor to the significantly adverse effect on health and physical well being. Certainly, there is increasing evidence indicating the vital need for improved national and international policies for better fitness, health, and sports for older individuals. In order to address some of these indicators, new attitudes and policies must emphasize activities and resources to meet the minimal requirements for keeping older people in good health, preventing their deterioration with age, and meeting the special interests of individuals with various disorders. In addition to the difficulties that hospitals, insurance companies, children of the elderly, and legislators face, the medical and scientific communities require time to determine the most appropriate solutions for improving the quality of these lengthening lives.

Many of the myths about aging are being disproved while the true nature of age-related changes appears to be less bleak than previously thought. Disuse and disease, not age alone, are increasingly, revealed as culprits. There is an increasing awareness of the need for more emphasis on fitness to maintain wellness and prevent degenerative illness, for more research to understand the aging body of the healthy older person, and to determine the exercise needs of the ill and/or the handicapped. Pollock et al. (1) noted that physical capacity decrements are normally associated with the aging process. This loss has been attributed to the influence of disease, medication, age, and/or sedentary lifestyle. Additionally, it was noted that the majority of the elderly do not exercise and that it is unclear whether the reduced state of physical conditioning associated with aging results from the deconditioning due to sedentary living, age, or both.

It is a fact of life that muscle tissue suffers some diminution from age. Age-associated changes in organ and tissue function, such as a decline in fat-free mass, total body and intracellular water, and an increase in fat mass (2) may alter the physiological responses to exercise or influence the effect(s) of medication. However, any discussion about age realistically utilizes arbitrary time periods apportioned eons ago by men who evaluated time relative to the number of revolutions of the earth around the sun and the rotation of the earth on its own axis. These predetermined periods may or may not have any relationship with the aging of the cells in the body. The linkage between the chronological age and the biological age of people is imprecise. Perhaps a more accurate consideration of the relationship between chronological and biological age would be one that is nonlinear, may differ with gender, or be dependent on other factors.

It is an inevitable evolutionary consequence that individuals within a species differ in many ways. The characterization of an individual on the basis of a chronological age scale may be practical, but biologically inappropriate. It may be that use or functional activities may have a greater influence on determining biological age rather than the number of times the earth has revolved around the sun. It appears that biological age can be affected by genetic code, nutrition and, most physical activity. Astrand (3) suggested that as an individual ages, the genetic code may have more of an effect on the function of systems with key importance in physical performance. He also noted that a change in lifestyle, at almost any chronological age, can definitely modify the biological age, either upward or downward. It has been suggested that the disparity of older persons is a hallmark of aging itself (4). It is important to determine how much age variance is due to the passage of time and how much is caused by the accumulation of other, nontime dependent, alterations. Previous attitudes towards physical adversities observed in the elderly were that they were attributable to disease. More recently, a third dimension associated with poor health in older persons has been described by Bortz and Bortz (4) as The Disuse Syndrome. For example, one of the most common markers of aging was thought to be a decreased lean body mass. However, analysis of 70 year old weight lifters revealed no such decline. The components of the Disuse Syndrome have been similarly grouped by Kraus and Raab (5) in their book, Hypokinetic Disease, and are (*1*) cardiovascular vulnerability; (*2*) musculoskeletal fragility; (*3*) obesity; (*4*) depression; (*5*) premature aging.

Use is a universal characteristic of life. When any part of the body has little or no use, it declines structurally and functionally. The effects of disuse can be observed on any body part, such as atrophied intestinal mucosa, when a loop is excluded from digestive functions or the lung becomes atelectatic when not aerated. A lack of adequate conditioning and physical activity causes alterations in the heart and circulatory system, as well as the lungs, blood volume, and skeletal muscle (6–9). During prolonged bed rest, blood volume is reduced, heart size decreases, myocardial mass falls, blood pressure response to exercise increases, and physical performance capability is markedly reduced. On the other hand, although acute changes within the cardiovascular system result in response to increased skeletal muscle demands during exercise, there is evidence that chronic endurance exercise produces changes in the heart and circulation that are organic adaptations to the demands of chronic exercise (10–15).

Cardiac performance undergoes direct and indirect age-associated changes. There is a reduction in contractility of the myocardium (16) and this increased stiffness impairs ventricular diastolic relaxation and increases end diastolic pressure (17). This suggests that exercise-induced increases in heart rate would be less well tolerated in older individuals than in younger populations. The decline in maximal heart rate is known and the cause is multifactorial, but is mostly related to a decrement in sympathetic nervous system response. Fifty percent of Americans who are > 65 years of age have a diagnostically abnormal resting electrocardiogram (18). Another factor associated with aging is a progressive increase in rigidity of the aorta and peripheral arteries due to a loss of elastic fibers, increase in collagenous materials, and calcium deposits (19). When aortic rigidity increases, the pulse generated during systole is transmitted to the arterial tree relatively unchanged. Therefore, systolic hypertension predominates in elderly hypertensive patients.

Other bodily systems demonstrate age-related alterations. Baroreceptor sensitivity decreases with age and hypertension (20,21) such that rapid adjustment of the cerebral circulation to changes in posture may be impaired. Kidney function reveals a defect in renal concentrating ability and sluggish renal conservation of sodium intake causes elderly patients to be more susceptible to dehydration (22). Hyaline cartilage on the articulator surface of various joints shows degenerative changes and clinically represents the fundamental alteration in degenerative osteoarthritis (23). A decrease in bone mineral density (osteoporosis) can reduce body stature as well as predispose the individual to spontaneous fractures. Older women are more prone to osteoporosis than older men and this may reflect hormonal differences (23). Older persons are less tolerant of high ambient temperatures than younger people (24) due to a decrease in cardiovascular and hypothalamic function which compromises the heat dissipating mechanisms. Heat dissipation is further compromised by the decrease in fat-free mass, intracellular and total body water, and an increase in body fat.

Unfortunately, the effects of disuse on the body manifest themselves slowly since humans normally have redundant organs that can compensate for ineffectiveness or disease. In addition, humans are opaque so that disease or deterioration are externally unobservable and, thus, go unheeded (e.g., the early changes in bones due to osteoporosis are subclinical and are normally detected only after becoming so pronounced that fractures ensue). Cummings et al. (25) mentioned the difficulty of distinguishing manifestations in musculoskeletal changes due to disease related to aging. Muscle mass relative to total body mass begins decreasing in the fifth decade and becomes markedly reduced during the seventh decade of life. This change results in reduced muscular strength, endurance, size, as well as a reduction in the number of muscle fibers. Basmajian and De Luca (26) reported numerous alterations in the electrical signals associated with voluntary muscular contractions with advancing age. As yet, there are no findings published that have definitively located age-related musculoskeletal changes in either the nervous or the muscular system. The diaphragm and cardiac muscle do not seem to incur age changes. Perhaps this is due to constant use, from exercise, or possibly a genetic survival mechanism.

There is growing consensus that many illnesses are preventable by good health practices including physical exercise. Milliman and Robertson (27) reported that, of the 15,000 employees of a major computer company, the nonexercisers accounted for 30% more hospital stays than the exercisers. Lane et al. (28) reported that regular runners had only two-thirds as many physician visits as community matched controls. The beneficial effect of exercise on diabetes has long been recognized and is generally recommended as an important component in the treatment of diabetes (29). Regular endurance exercise favorably alters coronary artery disease risk factors, including hypertension, triglyceride and high density lipoprotein cholesterol concentrations, glucose tolerance, and obesity. In addition, regular exercise raises the angina threshold (30).

Jokl (31) suggested three axioms of gerontology that are affected by exercise. He contents that sustained training results in the following: (*1*) decline of physique with age; (*2*) decline of physical fitness with age; (*3*) decline of mental functions with age.

Health in older people is best measured in terms of function, mental status, mobility, continence, and a range of activities of daily living. Preventive strategies appear to be able to forestall the onset of disease. Whether exercise can prevent the development of atherosclerosis, delay the occurrence of coronary artery disease, or prevent the evolution of hypertension is at present debatable. But moderate endurance exercise significantly decreases cardiovascular mortality (32). Endurance exercise can alter the contributions of stress, sedentary lifestyle, obesity, and diabetes to the development of coronary artery disease (33).

For example, the four-time Olympic discus champion, Al Oerter, at the age of 43, focused his training to qualify for the 1980 Olympic Games that would have been his fifth consecutive Olympiad Oerter threw his longest throw [220 f (67.05 m)] but, since the United States boycotted the 1980 Moscow Olympic Games, his chance was denied. By the time of the 1984 Los Angeles Games, Oerter was 47 years old. Even at an age well beyond most Olympic competitors, he again threw his best, exceeding 240 f (73.15 m) in practice sessions. Oerter's physique and strength suggested that his biological age was less than his chronological age.

Biologically, he was probably between 25 and 30, although chronologically he was 15–20 years older. Unfortunately, in the competition that determined which athletes would represent the United States, Oerter suffered an injury that precluded him from trying to achieve an unprecedented fifth consecutive Olympic Gold medal.

PRINCIPLES FOR EXERCISE AND TRAINING

Physical fitness and exercise have become, as previously discussed, an increasing concern at nearly all levels of American society. The goal of attaining peak fitness has existed for centuries, yet two problems continue to obfuscate understanding. The ability to assess strength and/or to exercise has occupied centuries of thought and effort. For examples, Milo the Greek lifted a calf each day until the baby grew into a bull. Since this particular procedure is not commonly available, humans have attempted to provide more suitable means to determine strength levels and ways to develop and maintain conditioning. Technology for assessing human performance in exercise and fitness evaluations, in both theory and practice, exhibits two problems. First, a lack of clearly defined and commonly accepted standards results in conflicting claims and approaches to both attaining and maintaining fitness. Second, a lack of accurate tools and techniques for measuring and evaluating the effectiveness of a given device designed to diagnose present capabilities for exercising or even to determine which exercises are appropriate to provide "fitness", regardless of age or gender. Vendors and consumers of fitness technology have lacked sound scientific answers to simple questions regarding the appropriateness of exercise protocols.

Reviewing studies conducted to determine the effects of strength training on human skeletal muscle suggests many benefits with appropriate exercise. In general, strength training that uses large muscle groups in high resistance, low repetition efforts increases the maximum work output of the muscle group stressed (34). Since resistance training does not change the capacity of the specific types of skeletal muscle fibers to develop different tensions, strength is generally seen to increase with the cross-sectional area of the fiber (35). The human body can exercise by utilizing its own mass (e.g., running, climbing, sit ups). These and other forms of nonequipment based exercises can be quite useful. In addition, there are various types of exercise equipment that allow selection of a weight or resistance and then the exercise against that machine resistance is performed.

The relationship between resistance exercises and muscle strength has been known for centuries. Milo the Greek's method of lifting a calf each day until it reached its full growth probably provides the first example of progressive resistance exercises. It has been well-documented in the scientific literature that the size of skeletal muscle is affected by the amount of muscular activity performed. Increased work by a muscle can cause that muscle to undergo compensatory growth (hypertrophy), whereas disuse leads to wasting of the muscle (atrophy).



Figure 5. Integration of our muscular system.

The goal of developing hypertrophy has stimulated the medical and sports professions, especially coaches and athletes, to try many combinations and techniques of muscle overload. Attempts to produce a better means of rehabilitation, an edge in sporting activities, as a countermeasure for the adverse effects of space flight, or as a means to improve or enhance bodily performances throughout a lifetime have only scratched the surface of the cellular mechanisms and physiological consequences of muscular overload.

Muscular strength can be defined as the force that a muscle group can exert against a resistance in a maximal effort. In 1948, Delorme and Watkins (36) adopted the name "progressive resistance exercise" for his method of developing muscular strength through the utilization of counter balances and weight of the extremity with a cable and pulley arrangement. This technique gave load-assisting exercises to muscle groups that did not perform antigravity motions. McQueen (37) distinguished between exercise regimes for producing muscle hypertrophy and those for producing muscle power. He concluded that the number of repetitions for each set of exercise determines the different characteristics of the various training procedures. Figure 5 illustrates the complexity of the skeletal–muscular structure.

When muscles contract, the limbs may appear to move in unanticipated directions. One type of motion is a static contraction, known as an isometric type of contraction. Another type of contraction is a shortening or dynamic contraction that is called an isotonic contraction. Dynamic contractions are accompanied by muscle shortening and by limb movement. Dynamic contractions can exhibit two types of motion. One activity is a concentric contraction in which the joint angle between the two bones become smaller as the muscular tension is developed. The other action is an eccentric contraction in which, as the muscles contract, the joint angle between the bones increases. Owing to ambiguity in the literature concerning certain physiologic terms and differences in laboratory procedures, the following terms are defined below.

1. *Muscular strength*: the contractile power of muscles as a result of a single maximum effort.
2. *Muscular endurance*: ability of the muscles to perform work by holding a maximum contraction for a given length of time or by continuing to move submaximal load to a certain level of fatigue.

3. *Isometric*: a muscular contraction of total effort but with little or no visible limb movement (sometimes referred to as static or anaerobic).
4. *Isotonic*: a muscular contraction of less than total effort with visible limb movement (sometimes called dynamic or aerobic).
5. *Isokinetic training (accommodating resistance)*: muscular contraction at a constant velocity. In other words, as the muscle length changes, the resistance alters in a manner that is directly proportional to the force exerted by the muscle.
6. *Concentric contraction*: an isotonic contraction in which the muscle length decreases (that is, the muscle primarily responsible for movement becomes shorter).
7. *Eccentric contraction*: an isotonic contraction in which the muscle length of the primary mover and the angle between the two limbs increases during the movement.
8. *Muscle overload*: the workload for a muscle or muscle group that is greater than that to which the muscle is accustomed.
9. *Variable resistance exercise*: as the muscle contracts, the resistance changes in a predetermined manner (linear, exponentially, or as defined by the user).
10. *Variable velocity exercise*: as the muscle contracts with maximal or submaximal tension, the speed of movement changes in a predetermined manner (linear, exponentially, or as defined by the user).
11. *Repetitions*: the number of consecutive times a particular movement or exercise is performed.
12. *Repetition maximum (1 RM)*: the maximum resistance a muscle or muscle group can overcome in a maximal effort.
13. *Sets*: the number of groups of repetitions of a particular movement or exercise.

Based on evidence presented in these early studies (36–38), hundreds of investigations have been published relative to techniques for muscular development, including isotonic exercises, isometric exercises, eccentric contractions, and many others. The effectiveness of each exercise type has been supported and refuted by numerous investigations, but no definitive, irrefutable conclusions have been established.

Hellebrandt and Houtz (38) shed some light on the mechanism of muscle training in an experimental demonstration of the overload principle. They found that the repetition of contractions that place minimal stress on the neuromuscular system had little effect on the functional capacity of the skeletal muscles. They also found that the amount of work done per unit of time is the critical variable upon which extension of the limits of performance depends. The speed with which functional capacity increases suggests that the central nervous system, as well as the contractile tissue, is an important contributing component of training.

Results from the work of Hellebrandt and Houtz (38) suggest that an important consideration in both the design of equipment for resistive exercise and the performance of an athlete or a busy executive is that the human body relies on preprogrammed activity by the central nervous system. Since most human movements are ballistic and the neural control of these patterns differs from slow controlled movements, it is essential that training routines employ programmable motions to suit specific movements. This control necessitates exact precision in the timing and coordination of both the system of muscle contraction and the segmental sequence of muscular activity. Research has shown that a characteristic pattern of motion is present during any intentional movement of body segments against resistance. This pattern consists of reciprocally organized activity between the agonist and antagonist. These reciprocal activities occur in consistent temporal relationships with the variables of motion, such as velocity, acceleration, and forces.

In addition to the control by the nervous system, the human body is composed of linked segments, and rotation of these segments about their anatomic axes is caused by force. Both muscle and gravitational forces are important in producing these turning effects, which are fundamental in body movements in all sports and daily living. Pushing, pulling, lifting, kicking, running, walking, and all human activities result from the rotational motion of the links which, in humans, are the bones. Since force has been considered the most important component of athletic performance, many exercise equipment manufacturers have developed various types of devices employing isometrics and isokinetics. When considered as a separate entity, force is only one factor influencing successful athletic performance. Unfortunately, these isometric and isokinetic devices inhibit the natural movement patterns of acceleration and deceleration.

The three factors underlying all athletic performances and the majority of routine human motions are force, displacement, and the duration of movement. In all motor skills, muscular forces interact to move the body parts through the activity. The displacement of the body parts and their speed of motion are important in the coordination of the activity and are also directly related to the forces produced. However, it is only because of the control provided by the brain that the muscular forces follow any particular displacement pattern and, without these brain centre controls, there would be no skilled athletic performances. In every planned human motion, the intricate timing of the varying forces is a critical factor in successful performances. In any human movement, the accurate coordination of the body parts and their velocities is essential for maximizing performances. This means that the generated muscular forces must occur at the right time for optimum results. For this reason, the strongest weightlifter cannot put the shot as far as the experienced shotputter, although the weightlifter possesses greater muscular force, he has not trained his brain centers to produce the correct forces at the appropriate time. Older individuals may be unable to walk up and down stairs or perform many of the daily, routine functions that had been virtually automatic before the deterioration produced by weakness, disease, or merely age.

There are significant differences in the manner of execution of the various resistive training methods. In isotonic exercises, the inertia, which is the initial resistance, must be overcome before the execution of the movement progresses. The weight of the resistance cannot be heavier than the maximum strength of the weakest muscle acting in a particular movement or the movement cannot be completed. Consequently, the amount of force generated by the muscles during an isotonic contraction does not maintain maximum tension throughout the entire range of motion. In an isokinetically loaded muscle, the desired speed of movement occurs almost immediately and the muscle is able to generate a maximal force under a controlled and specifically selected speed of contraction.

The use of the isokinetic principle for overloading muscles to attain their maximal power output has direct applications in the fields of sport medicine and athletic training. Many rehabilitation programmed utilize isokinetic training to recondition injured limbs of athletes to their full range of motion. The unfortunate drawback to this type of training is that the speed is constant and there are no athletic activities that are performed at a constant velocity. The same disadvantage applies to normal human activities.

In isotonic resistive training, if more than one repetition is to be used, a submaximal load must be selected for the initial contractions in order to complete the required repetitions. Otherwise, the entire regimen would not be completed, owing to fatigue or, the inability to perform. A modality that can adjust the resistance so that it parallels fatigue to allow a maximum effort for each repetition would be a superior type of equipment. This function could be accomplished by manually removing weight from the bar while the subject trained. This is neither convenient nor practical. With the aid of the computer, the function can be performed automatically.

Another drawback with many isotonic types of resistive exercises is that the inertia resulting from the motion changes the resistance depending on the acceleration of the weight and of the body segments. In addition, since overload on the muscle changes due to both biomechanical levers and the length–tension curve, the muscle is able to achieve maximal overload only in a small portion of the range of motion. To overcome this shortcoming in resistive training, some strength training devices have been introduced that have "variable resistance" mechanisms, such as a cam, in them. However, these variable resistance systems increase the resistance in a linear fashion and this linearity may not truly accommodate the individual. When including inertial forces to the variable resistance mechanism, the accommodating resistance can be canceled by the velocity of the movement.

There seem to be unlimited training methods and each is supported and refuted by as many "experts". In the past, the problem of accurately evaluating the different modes of exercise was rendered impossible because of the lack of adequate diagnostic tools. For example, when trying to evaluate isotonic exercises, the investigator does not know exactly the muscular effort nor the speed of movement, but knows only the weight that has been lifted. When a static weight is lifted, the force of inertia provides a significant contribution to the load and cannot be quantified by feel or observation alone. In the isokinetic mode, the calibration of the velocity is assumed, but has been poorly verified since the mere rotation of a dial to a specific speed setting does not guarantee the accuracy of subsequently generated velocity. In fact, discrepancies as great as 40% have been observed when verifying the bar velocity.

Most exercise equipment currently available lack intelligence. In other words, the equipment is not aware that a subject is performing an exercise or how it is being conducted. Verification of the speed is impossible since a closed-loop feedback and sensors are absent. However, with the advent of miniaturized electronics in computers, it became possible to unite exercise equipment with the computer's artificial intelligence. In other words, it became possible for exercise equipment to adapt to the user rather than forcing the user to adapt to the equipment.

HIGH TECHNOLOGY TOOLS

High technology refers to the use of advanced, sophisticated, space age mathematical and electronic methods and devices for creating tools that can enhance human activities as well as expanding the horizons for future inventions. NASA put a man on the moon, sent exploratory spacecraft to Mars and beyond, and is sending shuttle missions to the Space Station. Polymer science invented plastics, mechanical science produced the automobile, and aeronautical engineering developed the airplane. Despite all of the knowledge and explosive developments since the rock became a tool, few advances have considered first the most important component in a complicated system, the human body.

The usual developmental cycle creates something and humans must adapt to it rather than the reverse. Computers can provide precise computations rapidly for complex problems that would otherwise require enormous quantities of time, talent, and energy to complete. The strength of these electronic wizards to follow instructions exactly, remember everything, and perform calculations within thousandths of a second has made them indispensable in finance, industry, and government. Application of the computer was a perfect enhancement for the human mind in order to quantify and evaluate movement performances. Used in conjunction with the human mind's ability to deduce, interpret, and judge, the computer provides the necessary enhancement to surpass the limits of what the eye can see or what intuition can surmise. Technological advances, such as these, can assist humans irrespective of their age.

For good health, it is necessary to follow a training method that incorporates all of the various bodily systems. In other words, the body should be treated as a complex, but whole, entity rather than as isolated parts. While it is not wrong to evaluate one's diet, an assessment of health would be incomplete without consideration of physical training, stress reduction, and other components that constitute the integrated organism of the human body. For a person to be able to jog 5 miles it is not important only to run, but to develop the cardiovascular system in a systematic way to achieve a healthy status. Strength exercise, flexibility routines, proper nutrition and skill are necessary to achieve this goal.

Two sophisticated systems have been developed to analyze human performance and both are appropriate for the assault on aging. These systems include tools to (*1*) assess movements of the human body and (*2*) assist in exercising human beings. The first one is the biomechanical system that was developed to analyze movement performance. Currently, biomechanical analyses are routinely performed on a wide range of human motions in homes, work settings, recreation, hospitals, and rehabilitation centers. The second system, which incorporates space age technology, allows diagnoses and training of the musculoskeletal system. Each of these systems will be discussed subsequently in detail. Both of these technologies and the scientific principles and techniques discussed may help achieve physical and mental goals. The technological advances provide tools for quantification of the results and to analyze the potential of a person. With this information and these tools, it should be possible to train the various body systems for optimal results at any age.

The first commercially available computerized biomechanical system was described in 1973 (39) and that system can serve to illustrate the general concepts and procedures associated with biomechanical quantification of movement. Figure 6 illustrates device system. The computerized hardware–software system provides a means to objectively quantify the dynamic components of movement in humans, such as athletic events, gait analyses, work actions, as well as motion by inanimate objects, including such items as machinery actions, air bag activation, and auto crash dummies. This objective technique replaces mere observation and supposition. This system provides a means to quantity motion utilizing input information from any or all of the following mediums: visual (video), electromyography (EMG), force platforms, or other signal processing diagnostic equipment.

Figure 6. Analyses of vertical jump.

The Ariel Performance Analysis System provides a means of measuring human motion based on a proprietary technique for the processing of multiple high speed video recordings of a subject's performance (40–42). This technique demonstrates significant advantages over other common approaches to the measurement of human performance. First, except in those specific applications requiring EMG or kinetic (force platform) data, it is noninvasive. No wires, sensors, or markers need be attached to the subject. Second, it is portable and does not require modification of the performing environment. Cameras can be taken to the location of the activity and positioned in any convenient manner so as not to interfere with the subject. Activities in the workplace, home, hospital, therapist's office, health club, or athletic field can be studied with equal ease. Third, the scale and accuracy of measurement can be set to whatever levels are required for the activity being performed. Camera placement, lens selection, shutter and film speed may be varied within wide limits to collect data on motion of only a few centimeters or of many meters, with a duration from a few milliseconds to a number of seconds. Video equipment technology currently available is sufficiently adequate for most applications requiring accurate motion analysis. Determination of the problem, error level, degree of quantification, and price affect the input device selection.

A typical kinematic analysis consists of four distinct phases: data collection (filming); digitizing; computation; and presentation of the results. Data collection is the only phase that is not computerized. In this phase, video recordings of an activity are made using two or more cameras with only a few restrictions: (*1*) all cameras must record the action simultaneously. (*2*) If a fixed camera is used, it must not move between the recording of the activity and the recording of the calibration points. These limiting factors are not necessary when a panning camera and associated mechanism are used. A specialized device accompanied by specialized software was developed to accommodate camera movement particularly for use with gait analysis and some longer distance sporting events, such as skiing or long jumping. (*3*) The activity must be clearly seen throughout its duration from at least two camera views. (*4*) The location of at least six fixed noncoplanar points visible from each camera view (calibration points) must be known. These points need not be present during the activity as long as they can be seen before or after the activity. Usually they are provided by some object or apparatus of known dimensions that is placed in the general area of the activity, filmed and then removed. (*5*) The speed of each of the cameras (frames/second) must be accurately known, although the speeds do not have to be identical. (*6*) Some



Figure 7. Digitizing system.

event or time signal must be recorded simultaneously by all cameras during the activity in order to provide synchronization.

These rules for data collection allow great flexibility in the recording of an activity. Figure 7 illustrates a modern digitizing system to quantify human movement. Information about the camera location and orientation, the distance from camera to subject, and the focal length of the lens is not needed. The image space is self-calibrating through the use of calibration points that do not need to be present during the actual performance of the activity. Different types of cameras and different film speeds can be used and the cameras do not need to be mechanically or electronically synchronized. The best results are obtained when camera viewing axes are orthogonal (90° apart), but variations of 20–30° can be accommodated with negligible error. Initially, the video image is captured by the computer and stored in memory. This phase constitutes the "Grabbing" mode. Brightness, contrast, saturation, and color can be adjusted so that the grabbed picture may, in fact, be better than the original. Grabbing the image and storing it on computer memory eliminates any further need for the video apparatus.

Digitizing is the third step in biomechanical quantification. The image sequence is retrieved from computer memory and displayed, one frame at a time, on the digitizing monitor. Using a video cursor, the location of each of the subject's body joints (e.g., ankle, knee, hip, shoulder, elbow) is selected and stored in computer memory. In addition, a fixed point, which is a point in the field of view that does not move, is digitized for each frame as an absolute reference. The fixed point allows for the simple correction of any registration or vibration errors introduced during recording or playback. At some point during the digitizing of each view, a synchronizing event must be identified and, additionally, the location of the calibration points as seen from that camera must be digitized. This sequence of events is repeated for each camera view. This type of digitizing is primarily a manual process.

An alternative digitizing option permits the procedure to proceed automatically using any number of marker sets. This requires that the subject have the markers placed on the body prior to the filming phase. The types of markers and their placements have a substantial number of adherents particularly in the rehabilitation, gait measurement, and computer game communities. This type of digitizing combines manual and automatic, so that the activity progresses under manual control with computer-assisted selection of the joint segments or points. User participation in the digitizing process provides an opportunity for error checking and visual feedback which rarely slows the digitizing process adversely. A trained operator, with reasonable knowledge about digitizing and anatomy, can rapidly produce high quality digitized images. It is essential that the points are selected precisely because all subsequent information is based on the data provided in this phase.

The computation phase of analysis is performed after all camera views have been digitized. At this point in the procedures, the three-dimensional (3D) coordinates of the joints centers of a body are calculated. The transformation methods for transforming the data to two-dimensional (2D) or 3D coordinates are Direct Linear Transformation, Multiplier, and Physical Parameters Transformation. This phase computes the true 3D image space coordinates of the subject's body joints from the 2D digitized coordinates obtained from each camera's view. The Direct Linear Transformation Computation is determined by first relating the known image space locations of the calibration points to the digitized coordinate locations of those points. The transformation is then applied to the digitized body joint locations to yield true image space locations. This process is performed under computer control with some timing information provided by the user. The information needed includes, for example, starting and ending points if all the data are not to be used, as well as a frame rate for any image sequence that differs from the frame rate of the cameras used to record the sequence. The Multiplier technique for transformation is less rigorous mathematically and is utilized for those situations when no calibration device was used and only a few objects in the background are available to calibrate the area. This situation usually occurs when a nonscientific, third-party recorded the pictures such as a home video or even a televised sporting event. The third type of transformation, the Physical Parameters Transformation, is primarily applied with panning camera views or when greater accuracy is required on known image sources.

Following data transformation, a smoothing or filtering operation is performed on the image coordinates to remove small random digitizing errors and to compute body joint velocities and accelerations. Smoothing options include polynomial, cubic and quintic splines, a Butterworth second-order digital and fast Fourier filters (43–45). Smoothing may be performed automatically by the computer or interactively with the user controlling the amount of smoothing applied to each joint. Error measurements from the digitizing phase may be used to optimize the amount of smoothing selected. Another unique feature is the ability to display the Power Spectrum for each of the x, y, and z coordinates. This enhancement permits the investigator to evaluate the effect of the smoothing technique and the chosen value selected for that curve by examining the Power Spectrum. Thus, the investigator can determine the method and level of smoothing that best meets the requirements of the specific research. After smoothing, the true 3D body joint displacements, velocities, and accelerations will have been computed on a continuous basis throughout the duration of the sequence.

Analogue data can be obtained from as many as 256 channels for input into the analogue-to-digital (A/D) system. Processing of the analogue signals, such as those obtained from transducers, thermistors, accelerometers, force platforms, EMG, ECG, EEG, or others, can be recorded for analysis and, if needed, synchronized with the video system. The displayed video picture and the vectors from the force plate can be synchronized so that the force vectors appear to be "inside the body". At this point, optional kinetic calculations can be performed to provide for measurement and analysis of the external forces that are applied to the body during movement. Inverse Dynamics are used to compute joint forces and torques as well as energy and momentum parameters of single or combined segments. External forces include anything external to the body that is applying force or resistance such as a golf club held in the hand. The calculations that are performed are made against the force distribution of the body.

The presentation phase of analysis allows computed results to be viewed and recorded in a number of different formats. Body position and motion can be presented in both still frame and animated stick figure format in 3D. Multiple stick figures may be displayed simultaneously for comparison purposes. Joint velocity and acceleration vectors may be added to the stick figures to show the magnitude and direction of body motion parameters. Copies of these displays can be printed for reporting and publication. Results can also be reported graphically. Plots of body joints and segments, linear and angular displacements, velocities, accelerations, forces, and moments can be produced in a number of format options. An interactive graphically oriented user interface allows the selection and plotting of such results to be simple and straightforward. In addition, body motion parameter results may also be reported in numerical form and printed as tables.

Utilizing this computerized system for biomechanical quantification of various movements performed by the elderly may assist in developing strategies of exercise, alterations in lifestyle, modifications in environmental conditions, and inventions to ease and/or extend independence. For example, rising from a chair is a challenging task for many elderly persons and getting up quickly is associated with a particularly high risk for falling. Hoy and Marcus (46) observed that older women moved more slowly and altered their posture to a greater extent than younger women. The strength levels were greater for the younger subjects, but it could not be concluded that strength was the causal mechanism for the slower speed. Following an exercise program affecting a number of muscle groups, younger and older women significantly increased in strength. Results of this study suggest that age-associated changes in muscle strength have an important effect on movement strategies used during chair rising. Following participation in a strength-training program, biomechanical assessment revealed changes in movement strategies that increased both static and dynamic stability. Other areas appropriate for biomechanical assessment would be on the well-known phenomenon of increased postural sway (47) and problems with balance (48–50) in the aged.

It is also important to study the motor patterns used by older persons while performing locomotor tasks associated with daily life such as walking on level ground and climbing or descending stairs. Craik (51) demonstrated that older subjects walking at the same speed as younger ones exhibited similar movement characteristics. Perhaps the older subjects selected slower movement speeds that produced apparent rather than real reductions in performance. These types of locomotors studies are easily assessed by biomechanical procedures. A biomechanical inquiry by Williams (52) examined the age-related differences of intralimb coordination by young and old individuals. Williams observed a similarity of general intralimb coordination for both old and young participants for level ground motions. One age-related change was suggested with regard to the additional balance constraints required for going up stairs because of adjustments not required on level ground. More profound differences were observed by Light et al. (53) with complex, multilimb coordinated movements performed in a standing position which necessitated dynamic balance control. These types of tasks showed significant age-dependent changes. Compared with younger subjects, the older participants were slower in all timing components, had less predominance in their movement patterns, less coupling of their limbs for movement end-points, and were more susceptible to environmental uncertainties. The alterations in movement performance reflected age-related loss in the ability to coordinate fast, multilimb movements performed from an upright stance suggesting that older individuals may have uncoordinated and unpredictable movement patterns when required to move quickly. Additionally, it was suggested that the more uncertain the environment, the greater the disturbance on the movement, thus, increasing the risk of falling. These studies provide realistic examples of one role biomechanics can perform by not only specifically identifying the locus of change but also providing objective quantification.

Another interesting application of the biomechanical system involves a multidimensional study of Alzheimer's disease currently in progress at a leading medical school. The study's strength is similar to the blind men who must integrate all of the information each has gathered in order to accurately describe the elephant. Examination of the brain's response to specific drugs and at varying dosages, magnetic resonance imaging (MRI), thermographic, endocrine, and hormonal changes, vascular chemistry, as well as other aspects are being evaluated for each patient and their specific motor performances are being quantified biomechanically with the Ariel Performance Analysis system. Preliminary evidence indicates that performance on a simple bean-bag tossing skill improves daily although there is no cognitive recognition of the task. The activity of tossing a bean bag into a target circle from a standing position employs postural adjustments as well as coordinated arm and hand directed skills. Skill acquisition, or motor learning, involves both muscular capability and neural control mechanisms. Both activities involve closed- and open-loop mechanisms. The goal-directed movements needed to perform the bean-bag toss require the anticipatory postural adjustments that are inherent in an open-loop control. Because these findings suggest that muscular control and skill acquisition remain viable, this enables investigators to narrow the direction of the research and continue the study while continuously honing the focus. With each scientific finding, the research can be directed toward identification of the underlying cause.

The preceding discussion has described a computerized biomechanical system that can be utilized for the quantification of activities and performance levels particularly where appropriate for gerontological issues. Following the identification and definition of an activity, a second and equally necessary component follows. This is the ability to evaluate, test, and/or train the musculoskeletal components of the body in a manner appropriate to the specifically identified task(s) and according to the capabilities of the age and health of the individual. The integration of both technological assessment tools should assist the individual and others involved in their daily life to identify and measure those portions of an exercise program that can enhance performance, fitness status, or exercise capabilities for each gender and at different ages. In other words, one of the principles should be remembered is the goal of optimizing performance at every age.

For centuries, many devices have been created specifically for strength development. These devices include treadmills, bicycle ergometers, rowing machines, skiing simulators, as well as many of the more traditional resistive exercises with dumbbells, bar bells, and commercially available weight equipment. Figure 8 illustrates one of these equipment. Each type of exercise has some advantages, but none are designed to cope with the difficulties inherent with the gravitational effects that affect the multilinked human body performing on various exercise equipment.

All systems that employ weights as the mechanism for resistance have major drawbacks in four or more areas, as follows: (*1*) biomechanical considerations; (*2*) inertia; (*3*) risk of injury; (*4*) unidirectional resistance.

The biomechanical parameters are extremely important for human performance and should be incorporated into exercise equipment. The biomechanical factors were discussed previously. Inertia is the resistance to changes in motion. In other words, a greater force is required to begin moving weights than is necessary to keep them moving. Similarly, when the exercising person slows at the end of a movement, the weights tend to keep moving until slowed by gravity. This phenomenon reduces the force needed at the end of a motion sequence. Inertia becomes especially pronounced as acceleration and deceleration increase, effectively reducing the useful range of motion of weight-based exercise equipment.



Figure 8. The computerized exercise equipment.

The risk of injury is obvious in most weight-based exercise equipment. When weights are raised during the performance of an exercise, they must be lowered to their original resting position before the person using the equipment can release the equipment and stop exercising. If the person exercising loses their grip, or is unable to hold the weights owing to exhaustion or imbalance, the weights fall back to their resting position; serious injuries can, and have, occurred. Finally, while being raised or lowered, weights, whether on exercise equipment or free standing, offer resistance only in the direction opposite to that of gravity. This resistance can be redirected by pulleys and gears but still remains unidirectional.

In almost every exercise performed, the muscle or muscles being trained by resistance in one direction are balanced by a corresponding muscle or muscles that could be trained by resistance in the opposite direction. With weight-based systems, a different exercise, and often a different mechanism, is necessary to train these opposing muscles. Exercise mechanisms that employ springs, torsion bars, and the like are able to overcome the inertia problem of weight-based mechanisms and, partially, to compensate the unidirectional force restriction by both expanding and compressing the springs. However, the serious problem of safety remains. An additional problem is the fixed, nonlinear resistance that is characteristic of springs and is usually unacceptable to most exercise equipment users.

The third resistive mechanism commonly employed in existing exercise equipment is a hydraulic mechanism. Hydraulic devices are able to overcome the inertial problem of weights, the safety problem of both weights and springs, and, with the appropriate selection or configuration, the unidirectional problem. However, previous applications of the hydraulic principle have demonstrated a serious deficiency that has limited their popularity in resistive training. This deficiency is that of a fixed or a preselected flow rate through the hydraulic system. With a fixed-flow rate, it is a well established fact that resistance is a function of the velocity of the piston and, in fact, varies quite rapidly with changes in velocity. It becomes difficult for a person exercising to select a given resistance for training due to the constraint of moving either slower or faster than desired in order to maintain the resistance. Additionally, at any given moment, the user is unsure of just what the performing force or velocity actually is.

In the field of rehabilitation (54) especially, isokinetic or constant velocity training equipment is a technology that has enjoyed wide acceptance. These mechanisms typically utilize active or passive hydraulics or electric motors and velocity-controlling circuitry. The user or practitioner selects a constant level of velocity for exercise and the mechanism maintains this velocity while measuring the force exerted by the subject. Although demonstrating significant advantages over weight-based systems, isokinetic systems possess a serious limitation. There are virtually no human activities that are performed at a constant velocity. Normal human movement consists of patterns of acceleration and deceleration. When a person learns to run, ride a bike, or write, an acceleration–deceleration sequence is established that may be repeated at different rates and with different levels of force, but always with the pattern unique to that activity. To train, rehabilitate, or diagnose at a constant velocity is to change the very nature of the activity being performed and to violate most biomechanical performance principles.

FEEDBACK CONTROL OF EXERCISE

A newer form of exercise equipment can determine the level of effort by the person, compare it to the desired effort, and then adjust accordingly. The primary advantage of this resistive mechanism is that the pattern of resistance or the pattern of motion is fully programmable. The concept of applying a pattern of resistance or motion to training and rehabilitation was virtually impossible until the invention of computerized feedback control. Prior to the introduction of computerized feedback control, fitness technology could provide only limited modes of resistance and motion. Bar bells or weights of any type provide an isotonic or constant resistance type of training only when moved at a constant velocity. Typically, users are instructed to move the weights slowly to avoid the problem of inertia resulting from the acceleration or deceleration of mass. Weights used with cams or linkages that alter the mechanical advantage can provide a form of variable resistance. However, the pattern is always fixed and the varying mechanical advantage causes a variation in velocity that increases inertial effects. Users must move the weights slowly to preserve the resistance pattern. Another deficiency with these types of equipment is that they do not approximate the body or limb movement pattern of a normal human activity.

An exercise machine controlled by a computer possesses several unique advantages over other resistive exercise mechanisms, both fixed and feedback controlled. The most significant of these advances is the introduction of software to the human/computer feedback loop. The computer and its associated collection of unique programs can regulate the resistance to vary with the measured variables of force and displacement as well as modify the resistance according to data obtained from the feedback loop while the exercise progresses. This modification can, therefore, reflect changes in the pattern of exercise over time. The unique programmed selection can effect such changes in order to achieve a sequential or patterned progression of resistance for optimal training effect. The advantage of this capability over previous systems is that the user can select the overall pattern of exercise and the machine assumes responsibility for changing the precise force level, the speed of movement, and the temporal sequence to achieve that pattern.

There are a wide range of treadmills, bikes, and exercise devices currently available that employ electrical control features. These include such options as fat burn, up hill training, or cardiac modes. These types of equipment change the speed or elevations with preprogrammed actions that are determined at the manufacturing center when the machines are made rather than by the person exercising. The exerciser can select the programs presented on the control panel, but the response by the machine to the user is not at all related to the performance but rather to the preset events stored in the memory. Therefore, the person may be running "uphill" on the treadmill as determined by the imbedded system, but not with responsive interaction between the equipment and the individual moment by moment. This is a limitation of most of the exercise equipment available in the marketplace of the twenty-first century.

In the early 1980s, the first resistive training and rehabilitation device to employ computerized feedback control of both resistance and motion during exercise was introduced to overcome the lack of machine–human interactivity (55). For the first time, a machine dynamically adapted to the activity being performed rather than the traditional approach of modifying the activity to conform to the limitations of the machine. Biomechanical results previously calculated could be used to program the actual patterns of motion for training or rehabilitation. The equipment utilizes a passive hydraulic resistance mechanism operating in a feedback-controlled mode under control of the system's computer.

A simplified functional description of this mechanism, the Ariel Computerized Exercise System, and its operation is described. A hydraulic cylinder is attached to an exercise bar through a mechanical linkage. As the bar is moved, the piston in the hydraulic cylinder moves which pushes oil from one side of the cylinder, through a valve, and into the other side of the cylinder. When the valve is fully open there is no resistance to the movement of oil and, thus, no resistance in the movement of the bar. As the valve is closed, it becomes harder to push the oil from one side of the cylinder to the other and, thus, harder to move the bar. When the valve is fully closed, oil cannot flow and the bar will not move. In addition to the cylinder, the resistance mechanism contains sensors to measure the applied force on the bar and the motion of the bar. To describe the operation of the computerized feedback loop, assume the valve is at some intermediate position and the bar is being moved at some velocity with some level of resistance. If the computer senses that the bar velocity is too high or that bar resistance is too low, it will close the valve by a small amount and then check the velocity and resistance values again. If the values are incorrect, it will continue to regulate the opening of the valve and continually check the results until the desired velocity or resistance is achieved. Similar computer assessments and valve adjustments are made for every exercise. Thus, an interactive feedback loop between the computer and the valve enable the user to exercise at the desired velocity or resistance. The feedback cycle occurs hundreds of times a second so that the user experiences no perceptible variations from the desired parameters of exercise.

There are a number of advantages in a computerized feedback controlled resistance mechanism over devices that employ weights, springs, motors, or pumps. One significant advantage is safety. The passive hydraulic mechanism provides resistance only when the user pushes or pulls against it. The user may stop exercising at any time and the exercise bar will remain motionless. Another advantage is that of bidirectional exercise. The hydraulic mechanism can provide resistance with the bar moving in each direction, whereas weights and springs provide resistance in only one direction. Opposing muscle groups can be trained in a single exercise. Two additional problems associated with weight training, noise and inertia, are also eliminated because the hydraulic mechanism is virtually silent and full resistance can be maintained at all speeds. Figure 9 illustrates an olympic training system utilized by the olympic athletes.

The Ariel Computerized Exercise System allows the user to set a pattern of continuously varying velocity or resistance. The pattern can be based on direct measurements of that individual's motion derived from the biomechanical analysis or can be designed or created by the user with a goal of training or rehabilitation. During exercise, the computer uses the pattern to adjust bar velocity or bar resistance as the subject moves through the full range of motion. In this manner, the motion parameters of almost any activity can be closely duplicated by the exercise system allowing training or rehabilitation using the same pattern as the activity itself.

The software consists of two levels. One level of software is invisible to the individual using the equipment since it controls the hardware components. The second level of software allows interaction between the user and the computer. The computer programs necessary to provide the real-time feedback control, the data program and storage, and the additional performance manipulations are extensive. The software provides computer interaction with the individual operator by automatically presenting a menu of options when the system is activated. Selection of the diagnostics option allows several parameters about that person to be evaluated and stored if desired. Some of the diagnostic parameters available include range of motion, maximum force, and maximum speed that the individual can move the bar for the specific activity selected. The maximum force and maximum speed data can be determined at each discrete point in the range of movement as well as the average across the entire range. The diagnostic data can be used solely as isolated pre- and post-test measurements. However, the data can also be stored within the person's profile so that subsequent actions and tests performed on the equipment can be customized to adjust to that specific individual's characteristics.



Figure 9. Olympic training on the computerized exercise system.

The controlled velocity option permits the individual to control the speed of bar movement. The pattern of the velocity can be determined by the person using the equipment and these choices of velocity patterns include: (*1*) isokinetic, which provides a constant speed throughout the range of motion; (*2*) variable speed, in which the speed at the beginning of the motion and the speed at the end of the stroke are different with the computer regulating a smooth transition between the two values; and (*3*) programmed speed, which allows the user to specify a unique velocity pattern throughout the range of movement. For each of the choices, determination of the initial and final velocities is at the discretion of the individual through an interactive menu. The number of repetitions to be performed can be indicated by the person. Also, it is possible to designate different patterns of velocity for each direction of bar movement.

The controlled resistance option enables the person to control the resistance or amount of force required to move the bar. The alternatives include (*1*) isotonic, which provides a constant amount of force for the individual to overcome in order to move the bar; (*2*) variable resistance, in which the force at the beginning of the motion and the force at the end of the movement are different with the computer regulating a smooth transition between the two values; (*3*) programmed resistance, which permits the individual to specify a unique force pattern through-out the range of movement. An interactive menu enables the person to indicate the precise initial and final values, the number of repetitions to be used, and each direction of bar motion for the three choices. The controlled work option allows the individual to determine the amount of work, in Newton/meters or joules, to be performed rather than the number of repetitions. In addition, the person can choose either velocity or resistance as the method for controlling the bar movement. As with the previous options, bidirectional control is possible. The data storage capability is useful in the design of research protocols. The software allows an investigator to program a specific series of exercises and the precise manner in which they are to be performed, for example, number of repetitions and amount of work, so that the user need only select their name from the graphic menu and the computer will then guide the procedures. Data gathered can be stored for subsequent analysis. The equipment is fully operational for all options irrespective of whether the data storage option is activated.

Numerous features further enhance the application of this advanced fitness technology. Individual exercise programs can be created and saved on the computer, a CD, an internet file, or a USB disk. Users can perform their individual program at any time merely by loading it from any of the memory options used. Measurements of exercise results can be automatically saved and progress monitored by comparing current performance levels to previous ones. Performance can be measured in terms of strength, speed, power, repetitions, quantity of work, endurance and fatigue. Comparison of these quantities can be made for flexors versus extensors, right limb versus left limb, as well as between different dates and different individuals. Visual and audio feedback are provided during exercise to ensure that the subject is training in the proper manner and to provide motivation for optimal performance. Accuracy of measurement is essential and it is deemed as one of the most important considerations in the software. Calibration of the equipment is performed dynamically and is a unique feature that the computerization and the feedback system allow. Calibration is performed using weights with known values and the procedure can be performed for both up and down directions. This type of calibration is unique since the accuracy of the device can be ascertained throughout the range of motion.

FUTURE DEVELOPMENTS

As discussed previously, a large diagnostic and/or exercise system exists, but sheer bulk precludes its convenient use at home or in small spaces. One future goal is to develop a computerized, feedback-controlled, portable, battery-powered, hydraulic musculoskeletal exercise assessment and training equipment based on the currently available full-sized system. The device will be portable, compact, and operate at low voltage. Although physical fitness and good health have become increasingly more important to the American public, no compact, affordable, accurate device either for measurement or conditioning human strength or performance exists. This deficit hinders both America's ability to provide convenient, affordable, and accurate diagnostic and exercise capabilities for hospital or home-bound patients, children or elderly, to adequately perform within small-spaced military areas, as would be found in submarines, or in NASA shuttle projects to explore the frontiers of space. Figure 10 illustrates an astronaut running on a computerized treadmill in a zero gravity environment.



Figure 10. Motion analysis in space.

The frame will be compact and light-weight with a target weight of < 10 kg. This is an ambitious design goal that will require frame materials to have maximum strength/weight ratios and the structure must be engineered with attention directed toward compactness, storage size, and both ease and versatility of operation. The design of a smaller and lighter hydraulic valve, pack, and cylinder assembly is envisioned. Software can be tailored to specific applications such as for the very young or the aged, specific orthopedic and/or disease training, or other applications.

Another future development will be the ability to download programs through the Internet. For example, each patient could have one of the small exercise devices at home. His/her doctor can prescribe certain diagnostic activities and exercise regiments and transmit them via the Internet. The individual can perform the exercises at home and then submit the results to the doctor electronically. Biomechanical quantification of performances will become available electronically by downloading the software and executing the procedures on the individual's personal computer. Parents will be able to assist their child's athletic and growth performances, doctors or physical therapists can compare normal gait with their patient's, and many other uses which may not be apparent at this time. The Internet can also function as a conduit between a research site and a remote location. Consider a hypothetical example of the National Institute of Health conducting a study on the effects of exercise on various medical, chemical, neural, and biomechanical factors for a large number of subjects around the world. The exercise equipment could be linked directly with Internet sources; the other data could be collected, and sent to the appropriate participating institutes. Findings from each location could then be transmitted to the main data collection site for integration.

CONCLUSION

National and international attitudes and policies focused on improving the health of children, workers, and the elderly must be directed towards good nutrition and improving lifestyles. It is made abundantly clean in print and televised media, that obesity has become a severe threat to the health and well being of Americans. That this problem is or will become an international epidemic may depend on the manner in which it is addressed. Exercise is no substitute for poor lifestyle practices, such as excessive alcohol consumption, smoking, overeating, and poor dietary practices. Attention must be directed to the importance of creative movements, posture, perceptual motor stimulation, body awareness, body image, and coordination. However, the importance of physical activity is too valuable to be limited to the young and healthy. Exercise, sports, and other physical activities must include all ages without regard to their frailty or disabilities.

The laws of nature rule the human body. Chemical and biological laws affect food metabolism, neurological transmissions within the nervous system and the target organs, hormonal influences, and all other growth, maintenance, and performance activities. Mechanical influences occur at the joints according to the same laws that return the pole vaulter to earth. Food, water, air, and environmental factors interact with work and societal demands. Human life is an interplay of external and internal processes and energy and, according to the second law of thermodynamics, the system will move toward increased disorder over time (56).

In terms of the universe, the first law of thermodynamics states that the total energy of the universe is constant. The second law states that the total entropy of the universe is increasing. The measure of a system's disorder is referred to as entropy and Eddington said, Whenever you conceive of a new theory of unusually attractiveness, but it does not in some way conform to the second law, then that theory is most certainly wrong (57). Everyone inevitably grows older. Delaying the process of disorder by keeping the subsystems of the organism at a low level of entropy does not flaunt the second law, but rather exploits it.

Science and technology have afforded us the ability to quantify movement so that humans can use their bodies more efficiently. Normal movement of small children can be reflected in improved diapers that do not alter their gait. Assessment of workplace activities can identify movements that are biomechanically inappropriate for healthy workers. Changing the design of the work bench, providing variable height stools for the conveyor belt operators, and evaluating the job requirements to assist in matching the employee to the work, improved wheelchair design, and adaptations in housing for the elderly are just a few examples of how biomechanical analysis can be applied. Figure 11 shows how athletic performance and equipment are assessed scientifically.



Figure 11. The EMG analysis of a tennis stroke.

Not only has scientific and technological means provided quantitative assessment abilities, but has also allowed the development of improved means for exercising. Exercise equipment has become so sophisticated that it is appropriate for all ages. The youngest and the oldest can benefit from improved muscular health; the weakest and the strongest can always improve or, at the very least, sustain, healthy muscles; and those with compromised health or bodily functions should enjoy the opportunities to improve their musculature.

Logically, consumption of proper food, sleeping or resting sufficiently, and engaging in an appropriately amount of intense physical activity should keep the tissues and organs functioning maximally. To extend and improve the length and the quality of life depends on an increased awareness of human anatomy, biology, and physiology with continuous research efforts in these and other areas which impact human life. The aging process cannot be overcome, but it should be possible to negate many of the debilitating aspects of it. The Declaration of the United States of America is the only document of any country in history which includes the statement of "pursuit of happiness" and this concept should apply to the health and quality of life for all peoples, regardless of location, and at every age: from infancy to the twilight years.

BIBLIOGRAPHY

Cited References

1. Pollack L, Lowenthal DT, Graves JE, Carroll JF. The elderly and endurance training. In: Shephard RJ, Astrand P-O, editors. Endurance in Sport. London: Blackwell Scientific Publications; 1992. p 390–406.

2. Sidney K, Shephard R, Harrison J. Endurance training and body composition in the elderly. Am J Clin Nutr 1977;30:326–333.
3. Astrand P-O. Influences of biological age and selection. In: Shephard RJ, Astrand P-O, editors. Endurance in Sport. London: Blackwell Scientific Publications; 1992. p 285–289.
4. Bortz WM IV, Bortz WM II. Aging and the disuse syndrome - effect of lifetime exercise. In: Harris S, Harris R, Harris WS, editors. Optimization of human performance. Physical Activity, Aging and Sports, Vol. H.- P, Program and Policy. Albany (NY): Center for the Study of Aging; p 44–50.
5. Kraus H, Raab W. Hypokinetic diseases—diseases produced by the lack of exercise. Philadelphia: Thomas; 1961.
6. Bove AA. Heart and circulatory function in exercise. In: Lowenthal DT, Bharadwaja, Oaks WW, editors. Therapeutics Through Exercise. New York: Grune & Stratton; 1979. p 21–31.
7. Saltin B. et al. Response to exercise after bed rest and after training. Circulation 38(7): 1.
8. Erick H, Knottinggen A, Sarajas SH. Effects of physical training on circulation at and during exercise. Am J Cardiol 1963;12:142.
9. Saltin B, et al. Responses to exercise after bed rest and after training. Circulation 38(8): 1.
10. Clausen JP. Effect of physical training on cardiovascular adjustments to exercise. Ph Rev 1977;37:779.
11. Scheuer J, Tipton CM. Cardiovascular adaptations to physical training. Ann Rei Physiol 1977;39:221.
12. Ritzer TF, Bove AA, Lynch PR. Left ventricular size and performance followir term endurance exercise in dogs. Fed Proc 1977;36:447.
13. Miller PB, Johnson RL, Lamb LE. Effects of moderate exercise during four w(bed rest on circulatory function in man. Aerosp Med 1965;38:1077.
14. Oscai LB, Williams BT, Hertig BA. Effect of exercise on blood volume. J A Physiol 1968;24:622.
15. Hanson JS, Tabakin BS, Levy AM, Nedde W. Long term physical training and cardiovascular dynamics in middle aged men. Circulation 1968;38:783.
16. Becklake B, et al. Age changes in myocardial function and exercise response. Prog Cardiovasc Dis 1965;19:1–21.
17. Templeton G, Platt M, Willerson J, Weisfeldt M. Influence of aging on left ventricular hemodynamics and stiffness in beagles. Circ Res 1979;44:189–194.
18. Gottlieb SO, et al. Silent ischemia on Holter monitoring predicts mortality in high risk infarction patients. JAMA 1988;259:1030–1035.
19. Dustan H. Atherosclerosis complicating chronic hypertension. Circulation 1974;50:871.
20. Gribbin B, Pickering T, Sleight P, Peto R. Effect of age and high blood presst baroflex sensitivity in man. Circ Res 1971;29:424.
21. Bristow J, et al. Diminished baroflex sen; in high blood pressure. Circulation 1969;39:48.
22. Papper S. The effects of age in reducing renal function. Geriatrics 1973;28:83–87.
23. Lane C, et al. Long distance running, bone density, and osteoarthritis. JAMA 1986;255:1147–1151.
24. Shock N. Systems integration. In: Finch C, Hayflick L, editors. Handbook of the Bio1 Aging. New York: Van Nostrand Reinhold; 1977. p 639–665.
25. Cummings S, et al. Epidemiology of osteop and osteoporotic fractures. Epidemiol Rev 1985;7:178–208.
26. Basmajian JV, De Luca CJ. Muscles Alive. Baltimore: Williams & Wilkins; 1985.
27. Milliman and Robertson, Inc. Health risks and behavior: The impact on medical costs. C Data Corporation. 1987.
28. Lane N, et al. Long distance rut bone density and osteoarthritis. JAMA 1986;255:1147–1151.
29. Felig P, Koivisto V. The metabolic response to exercise: Implications for diabetes. In: Lowenthal DT, Bharadwaja K, Oaks WW, editors. Therapeutics Through Exercise. New York: Grune & Stratton; 1979. p 3–20.
30. Pollock M, Wilmore J, editors. Exercise in Health and Disease: Evaluation and Prescription for Prevention and Rehabilitation. Philadelphia: Saunders; 1990.
31. Jokl E. Physical activity and aging. In: Harris S, Harris R, Harris WS, editors. Physical Activity, Aging and Sports. Vol. II, Albany: Center for the Study of Aging; 1992. p 12–20.
32. Paffenbarger R, Hyde R, Wing A, Hsieh C. Physical activity and all-cause mortality and longevity of college alumni. N Engl J Med 1986;314:605–613.
33. Kannel W, et al. Prevention of cardiovascular disease in the elderly. J Am Coll Cardiol 1987;10:25A–8A.
34. Dudley G, Fleck S. Strength and endurance training: Are they mutually exclusive? Sports Med 1987;4:79–85.
35. McDonaugh M, Davies C. Adaptive response of mammalian skeletal muscle to exercise with high loads. Eur J Appl Phys 1984;52:139–155.
36. Delorme TL, Watkins AL. Techniques of progressive resistance exercise. Arch Phys Med 1948;29:645–667.
37. McQueen I. Recent advances in the technique of progressive resistance exercise. Br Med 1954;2:328–338.
38. Hellebrandt F, Houtz S. Mechanism of muscle training in man: Experimental demonstration of overload principle. Physiol Ther Rev 1956;36:371–376.
39. Ariel GB. Computerized biomechanical analysis of human performance. Mechanics and Sport, Vol. 4, New York: The American Society of Mechanical Engineers; 1973. p 267–275.
40. Wainwright RW, Squires RR, Mustich RA. Clinical significance of ground reaction forces in rehabilitation and sports medicine. Presented at the Canadian Society for Biomechanics, 5th Biannial Conference on Biomechanics and Symposium on Human Locomotion; 1988.
41. Llacera I, Squires RR. An analysis of the shoulder musculature during the forehand racquetball serve. Las Vegas: Presented at the American Physical Therapy Association meeting; 1988.
42. Susanka P. Biomechanical analyses of men's handball. Presented at International Handball World Federation 12th Men's Handball World Championship, Prague, Czechoslovakia, Charles University; 1990.
43. Reinsch C. Smoothing by spline functions. Numer Math 1967;10:177–183.
44. Wood GA, Jennings LS. On the use of spline functions for data smoothing. J Biomech 1975;12(6): 477–479.
45. Kaiser JF. Digital Filters. In: Liu D, editor. Digital Filters and the Fast Fourier Transform, 5-79. Stroudsburg (PA): Dowden, Hutchinson & Ross; 1975.
46. Hoy MG, Marcus R. Effects of age and muscle strength on coordination of rising from a chair. In: Woollacott M, Horak F, editors. Posture and Gait: Control Mechanisms. Vol. II. Portland (OR): University of Oregon Books; 1992. p 187–190.
47. Teasdale N, Stelmach GE, Bard C, Fleury M. Posture and elderly persons: Deficit; the central integrative mechanisms. In: Woollacott M, Horak F, editors. Posture and Gait: Control Mechanisms. Vol. II. Portland, (OR): University of Oregon Books; 1992. p 203–207.
48. Vamos L, Riach CL. Postural stability limits and vision in the older adult. In: Woollac M, Horak F, editors. Posture and Gait: Control Mechanisms. Vol. II. Portland (OR): University of Oregon Books; 1992. p 212–215.
49. Frank J, et al. Control of upright stand active, healthy elderly. In: Woollacott M, Horak F, editors. Posture and Gait:

Control Mechanisms. Vol. II. Portland (OR): University of Oregon Books; 1992. p 216–219.
50. Panzer V, Kaye J, Edner A, Holme L. Standing postural control in the elderly and v elderly. In: Woollacott M, Horak F, editors. Posture and Gait: Control Mechanisms. Vol. II. Portland (OR): University of Oregon Books; 1992. p 220–223.
51. Craik R. Changes in locomotion in the aging adult. In: Woollacott MH, Shumway-Co A, editors. Development of Posture and Gait across the Life Span. Columbia (SC): University of South Carolina Press; 1989. p 150–153.
52. Williams K. Intralimb coordination of older adults during locomotion: Stair climbing. In: Woollacott M, Horak F, editors. Posture and Gait: Control Mechanisms. Vol. II. Portland (OR): University of Oregon Books; 1992. p 208–211.
53. Light KE, Tang PF, Krugh CR. Performance differences between young and elderly females in a step-reach task. In: Woollacott M, Horak F, editors. Posture and Gait: Control Mechanisms. Vol. II. Portland (OR): University of Oregon Books; 1992. p 287–290.
54. Jacobs I, Bell DG, Pope J. Comparison of isokinetic and isoinertial lifting tests as predictors of maximal lifting capacity. Eur J Appl Physiol 1988;57:146–153.
55. Ariel GB. Computerized dynamic resistive exercise. In: Landry F, Orban WAR, editors. Mechanics of Sports and Kinanthropometry. Book 6. Miami (FL): Symposia Specialists, Inc.; 1978. p 45–51.
56. Benson H. University Physics. New York: John Wiley & Sons; 1991.
57. Eddington A. The Nature of the Physical World. Cambridge: New Press; 1928.

See also EXERCISE STRESS TESTING; HUMAN SPINE, BIOMECHANICS OF; JOINTS, BIOMECHANICS OF; LOCOMOTION MEASUREMENT, HUMAN; REHABILITATION AND MUSCLE TESTING.

BIOMECHANICS OF JOINTS. See JOINTS, BIOMECHANICS OF.

BIOMECHANICS OF SCOLIOSIS. See SCOLIOSIS, BIOMECHANICS OF.

BIOMECHANICS OF SKIN. See SKIN, BIOMECHANICS OF.

BIOMECHANICS OF THE HUMAN SPINE. See HUMAN SPINE, BIOMECHANICS OF.

BIOMECHANICS OF TOOTH AND JAW. See TOOTH AND JAW, BIOMECHANICS OF.

BIOMEDICAL ENGINEERING EDUCATION

PAUL BENKESER
Georgia Institute of Technology
Atlanta, Georgia

INTRODUCTION

Biomedical engineering is that interdisciplinary field of study combining engineering with life sciences and medicine. It is a relatively new field of study that has only recently experienced sufficient maturity to enable it to establish its own identity. Often, this field will be described using the term bioengineering. In 1997, the Bioengineering Definition Committee of the National Institutes of Health released the following definition of the field (1): “Bioengineering integrates physical, chemical, mathematical, and computational sciences and engineering principles to study biology, medicine, behavior, and health. It advances fundamental concepts; creates knowledge from the molecular to the organ systems level; and develops innovative biologics, materials, processes, implants, devices and informatics approaches for the prevention, diagnosis, and treatment of disease, for patient rehabilitation, and for improving health.”

While many use biomedical engineering and bioengineering interchangeably, it is generally accepted today that bioengineering is a broader field that combines engineering with life sciences, but is not necessarily restricted to just medical applications.

The Biomedical Engineering Society further elaborated on the definition of biomedical engineering as part of a guide on careers in the field. In it is stated (2): “A Biomedical Engineer uses traditional engineering expertise to analyze and solve problems in biology and medicine, providing an overall enhancement of health care. Students choose the biomedical engineering field to be of service to people, to partake of the excitement of working with living systems, and to apply advanced technology to the complex problems of medical care. The biomedical engineer works with other health care professionals including physicians, nurses, therapists and technicians. Biomedical engineers may be called upon in a wide range of capacities: to design instruments, devices, and software, to bring together knowledge from many technical sources to develop new procedures, or to conduct research needed to solve clinical problems.”

Educational programs in the field of biomedical engineering had their origins in a handful of specialized graduate training programs in the 1950s focusing primarily on diagnostic and therapeutic devices and instrumentation. By 2004, there were undergraduate and graduate programs in biomedical engineering at ~100 universities in the United States. The diversity in the content of undergraduate educational programs that was commonplace in its early years is gradually diminishing as the field has matured. While the current undergraduate programs still maintain their own unique identity, there has been a steady movement toward the definition of a core curriculum in the field.

The purpose of this article is to give the reader some historical perspective on the origins of educational programs in the field, the challenges associated with preparing bachelor-level graduates for careers in the field, and the current state-of-the-art in undergraduate biomedical engineering curriculums.

HISTORY

The first steps toward establishing biomedical engineering as a discipline occurred in the 1950s as several formalized training programs were created. Their establishment was significantly aided by the National Institutes of Health creation of training grants for doctoral studies in biomedical engineering. The Johns Hopkins University, the University of Pennsylvania, the University of Rochester, and Drexel University were among the first to be awarded these grants.

During the late 1960s and early 1970s, growing opportunities in the field helped prompt the development of a second generation of biomedical engineering programs and departments. These included Boston University in 1966; Case Western Reserve University in 1968; Northwestern University in 1969; Carnegie Mellon University, Duke University, Rensselaer Polytechnic Institute and a joint program between Harvard and the Massachusetts Institute of Technology in 1970; Ohio State University and University of Texas, Austin, in 1971; Louisiana Tech, Texas A&M and the Milwaukee School of Engineering in 1972; and the University of Illinois, Chicago in 1973 (3). Many of these first and second generation of programs were concentrating the training of their students in areas defined either using quasiclassical engineering terminology, such as bioinstrumentation, biomaterials and biomechanics, or by application area, such as rehabilitation engineering or clinical engineering.

The late 1990s witnessed a substantial increase in the growth of the number of departments and programs in biomedical engineering, especially at the undergraduate level. The growth of this third generation of programs was fueled in part by grants from The Whitaker Foundation to help institutions establish or develop biomedical engineering departments or programs. In 2004, ~100 universities have programs or departments in biomedical engineering, including 33 offering undergraduate degree programs accredited by the Engineering Accreditation Commission of the Accreditation Board for Engineering and Technology (ABET) (4). The growth in the numbers of ABET accredited degree programs is illustrated in Fig. 1.

The arrival of the third generations of programs coincided with the development of several new areas of training in biomedical engineering, such as systems biology–physiology, and tissue, cellular, and biomolecular engineering. These areas typically require significantly more training in life sciences than was present in the first and second generation biomedical engineering training programs. This presented significant challenges for undergraduate programs trying to add this life science content to their curricula without increasing the number of credit hours required for the programs. Many of these programs accomplished this by creating a new generation of courses in which the engineering and life science concepts are integrated together within courses. The integration of such courses into the curriculum is discussed in more detail in the Curriculum section.

CAREER PREPARATION

The design of a high quality educational program should always start with its educational objectives. By using the definition established by ABET, these program educational objectives are statements that describe the expected accomplishments of graduates during the first several years following graduation (5). This requires programs to be cognizant of the needs of prospective employers of its graduates and design learning environments and curricula to meet those needs. This is particularly challenging task for a relatively new and evolving field like biomedical engineering.

Biomedical engineers are employed in industry, in research facilities of educational and medical institutions, in teaching, in government regulatory agencies, and in hospitals. They often serve as integrators or facilitators, using their skills in both the engineering and life science fields. They may work in teams in industry to help design devices, systems, and processes that require an in-depth understanding of both living systems and engineering. Frequently, biomedical engineers will be found in technical sales and marketing positions in companies seeking to provide their customers with technically trained individuals who are capable of better understanding their needs and communicating those needs back to product development teams. Government regulatory positions, such as those with the Food and Drug Administration, often involve testing medical devices for performance and safety. In research institutions, biomedical engineers participate in or direct research activities in collaboration with other



Figure 1. Number of ABET accredited programs in biomedical engineering.

researchers with such backgrounds as medicine, biology, chemistry, and a variety of engineering disciplines.

According to the U.S. Department of Labor's Bureau of Labor Statistics, manufacturing industries employed 38% of all biomedical engineers, primarily in the pharmaceutical and medicine manufacturing and medical instruments and supplies industries (6). Others worked in academia, hospitals, government agencies, or as independent consultants. Employment of biomedical engineers is expected to increase faster than the average for all occupations through 2012 (6). The demand for better and more cost-effective medical devices and equipment designed by biomedical engineers is expected to increase with the aging of the population and the associated increased focus on health issues. Most of these employment opportunities will be filled with graduates from B.S. and M.S. degree programs. However, for research-oriented jobs, like faculty positions in academia and research and development positions in industry, employers typically require their employees to possess a Ph.D. degree.

The needs of the employers that hire biomedical engineers undoubtedly vary by industry and job title. However, there are some skills that appear to be in universal demand by all employers of biomedical engineers. They include proficient oral and written communication skills, the ability to speak the languages of engineering and medicine, a familiarity with physiology and pathophysiology, and teamwork skills (6).

In spite of this seemingly impressive list of career paths and options, one of the most significant challenges facing entry-level biomedical engineers are prospective employers who complain that they do not understand what skill sets biomedical engineers possess (7). The perception is that the skills possessed by engineers from other disciplines, like electrical or mechanical engineering, are more predictable and in large part are independent of the university where the engineer was educated. It is likely that this perception is a result of a combination of two factors. First, often the individuals responsible for making the hiring decisions in companies did not receive their degrees in biomedical engineering, and thus do not have first-hand experience with the training received by biomedical engineers. Second, until relatively recently, many undergraduate biomedical engineering programs lacked a substantive core curriculum and were structured in such a way that students had to select from one of several "tracks" offered by the program. These tracks were typically pattered along traditional engineering lines, such as bioelectronics and biomechanics, in an attempt to address another concern expressed by prospective employers—that graduates of bachelor degree programs in biomedical engineering were too broadly trained and thus lacked sufficient depth of engineering skills. Due to this perceived lack of depth, it is not uncommon to find employers for which the entry-level degree for biomedical engineering positions is the masters degree. Undoubtedly the presence of these tracks, and their variability from program to program, contributed to the confusion in industry over the what skill sets they should expect from a biomedical engineer.

As a result of these concerns over depth, breadth, and uniformity of curriculum, the biomedical engineering education community has recognized the need to reach consensus on what constitutes a core undergraduate curriculum in biomedical engineering. This has become one of the major initiatives of the National Science Foundation (NSF) sponsored VaNTH Engineering Research Center (ERC) for Biomedical Engineering Educational Technologies. This ERC, a collaboration of teams from Vanderbilt University, Northwestern University, The University of Texas at Austin, Harvard University, and the Massachusetts Institute of Technology, was created in 1999. Its vision is to transform bioengineering education to produce adaptive experts by developing, implementing and assessing educational processes, materials, and technologies that are readily accessible and widely disseminated (8). The Whitaker Foundation has also sponsored workshops at its 2000 and 2005 Biomedical Engineering Summit meetings with the goal of delineating the core topics in biomedical engineering that all biomedical engineering students should understand. White papers from these meetings can be found at the Foundation's web site (9).

In spite of the movement toward the creation of a common core curriculum in undergraduate programs of study in biomedical engineering, there will undoubtedly continue to be some differences in curricula between programs. This is not only permitted in the current accreditation review process of ABET, but in some sense encouraged. Within the past decade this process has changed from a prescriptive evaluation to an outcomes-based assessment centered on program-defined missions and objectives (10). Thus, it will be incumbent on programs to work closely with the prospective employers of their graduates to ensure that the programs provide the graduates with the skills the employers desire. For example, Marquette University's biomedical engineering program has an established industrial partners program with >30 companies participating (11).

THE UNDERGRADUATE CURRICULUM

Contained within this section is a description of a core undergraduate curriculum that the author believes the biomedical engineering educational community is converging upon. The contents are based upon reviews of curriculums from biomedical engineering programs (12) and information disseminated by the Curriculum Project of the VaNTH ERC (13). It is important to note that the core described herein is not being presented as the prescription for what a biomedical engineering curriculum should look like, but rather a reflection of the current trends in the field.

Course Requirements

To be accredited by ABET, the curriculum must include the following:

- One year of an appropriate combination of mathematics and basic sciences.
- One-half year of humanities and social sciences.
- One and one-half years of engineering topics and the requirements listed in ABETs Program Criteria for bioengineering.

A year is defined as 32 semester or 48 quarter hours.

The typical math and science content of biomedical engineering curriculums, as described in Table 1, are similar to those of other engineering disciplines. The notable exceptions are courses in biology and organic chemistry. In general, most programs rely on other departments within their university to provide the instruction for these courses. Some programs with large enrollments have been successful in collaborating with faculty in their university's science departments to create biology and chemistry courses for biomedical engineering students. For example, the School of Chemistry and Biochemistry at the Georgia Institute of Technology has created organic and biochemistry courses specifically designed for biomedical engineering students.

Table 1. Mathematics and Science Core Curriculum Subjects

Subject	Sampling of Topical Coverage
Math	Linear algebra Differential, integral, multivariable calculus Differential equations Statistics
Physics	Classical mechanics, oscillations and waves Electromagnetism, light and modern physics
Computer Science	Algorithms, data structures, program design and flow control Graphics and data visualization Higher level programming language (e.g., Matlab, Java, C++)
Chemistry	General and inorganic chemistry Organic chemistry Biochemistry
Biology	Modern biological principles Genetics Cell biology

The core biomedical engineering content is described in Table 2. Depending on the size of the program, some of the content may be delivered in courses outside of biomedical engineering (e.g., thermodynamics from mechanical engineering). It is not uncommon to find some variability between programs in the content of their core curriculums. This will likely always be the case as each program must provide the curriculum that best enables its graduates to achieve the program's unique educational objectives.

ABET Criterion 3 stipulates that engineering programs must demonstrate achievement of a minimum set of program outcomes. These outcomes are statements that describe skills that "students are expected to know or be able to do by the time of graduation from the program" (5). A closer examination of these skills suggests that they can be divided into two sets as illustrated in Table 3. The first set, "domain" skills, is one that engineering educators are typically adept in both teaching and quantitatively measuring achievement. Programs generally use courses, like those listed in Tables 1 and 2, to develop these domain skills in their students. The second set, "professional" skills, is more difficult to teach and assess. However, these professional skills are often the ones most frequently cited by employers of engineers as the most important skills they value in their employees.

Table 2. Biomedical Engineering Core Curriculum Subjects

Subject	Sampling of Topical Coverage
Biomechanics	Principles of statics Mechanics of biomaterials Dynamics
Biotransport	Mass transfer Heat transfer Momentum transfer
Biothermodynamics	Thermodynamic principles Mass and energy balances
Biomaterials	Metals, polymers and composite materials Biocompatibility
Bioinstrumentation	Instrumentation concepts Amplifiers and filters Sensors and transducers
Biofluids	Blood vessel mechanics Hydrostatics and steady flow models Unsteady Flow and non-uniform geometric models
Systems Physiology	Cellular metabolism Membrane dynamics Homeostatis Endocrine, cardiovascular and nervous systems Muscles
Biosignal Analysis	Digital signal processing theory Filtering Frequency-domain characterization of signals

Humanities and social science courses are integral to the achievement of these professional skills. However, programs must avoid employing the "inoculation" model for teaching these skills to the students. In this model, it is assumed that students can learn these skills by simply taking isolated courses in ethics, technical communications, and so on. There are several problems with this model. It can decontextualize these skills, treating them as add-ons and not an integral part of everyday engineering practice. This is a false and even dangerous message to give the students—that written and oral communication and ethical behavior are peripheral to the real world of engineering. This message is further driven home because the faculty responsible for teaching these skills is humanities or social science faculty not engineering faculty. In addition, the complexity of these skills to be learned is too great for students to master within the framework of isolated courses. Research suggests, however, that students need quasirepetitive activity cycles and practice in multiple settings to develop proficiency in these professional skills (14–16).

Professional Skills

Before describing methods of developing these professional skills in students, it is necessary to establish operational

Table 3. Program Outcomes Specified in ABET Criterion 3

Domain Skills	Professional Skills
An ability to apply knowledge of mathematics, science, and engineering	An ability to function on multi-disciplinary teams
An ability to design and conduct experiments, as well as to analyze and interpret data	An understanding of professional and ethical responsibility
An ability to design a system, component, or process to meet desired needs	An ability to communicate effectively
An ability to identify, formulate, and solve engineering problems	The broad education necessary to understand the impact of engineering solutions in a global and societal context
A knowledge of contemporary issues	A recognition of the need for, and an ability to engage in lifelong learning
An ability to use the techniques, skills, and modern engineering tools necessary for engineering practice	

descriptions for these constructs. Such descriptions serve two functions. They reveal the complexity of the particular skills in terms of the subskills required to demonstrate the higher level skills specified in the ABET lists. Descriptions can also serve as articulations of learning outcomes, which can be designed toward and assessed. The following represents one interpretation of the variables that are indicators of these constructs (16).

Ability to communicate effectively.

$$\text{Oral} + \text{written communication skills}$$

- Convey information and ideas accurately and efficiently.
- Articulate relationships among ideas.
- Inform and persuade.
- Assemble and Organize evidence in support of an argument.
- Make communicative purpose clear.
- Provide sufficient background to anchor ideas–information.
- Be aware of and address multiple interlocutors.
- Clarify conclusions to be drawn from information.

Ability to function on multidisciplinary teams.

$$\text{Team} - \text{collaboration skills} + \text{communication skills } 3$$

- Help group develop and achieve team goals.
- Avoid contributing excessive or irrelevant information.
- Confront others directly when necessary.
- Demonstrate enthusiasm and involvement.
- Monitor group progress and complete tasks on time.
- Facilitate interaction with other members.

Understanding professional and ethical responsibilities.

- Recognize moral problems and issues in engineering.
- Comprehend, clarify, and critically assess opposing arguments.
- Form consistent and comprehensive viewpoints based on facts.
- Develop imaginative responses to problematic conflicts.
- Think clearly in the midst of uncertainty and ambiguity.
- Appreciate the role of rationale dialogue in resolving moral conflicts.
- Ability to maintain moral integrity in face of pressures to separate professional and personal convictions.

Broad education necessary to understand the impact of engineering solutions in a global and societal context.

- Identify human needs or goals technology will serve.
- Analyze and evaluate the impact of new technologies on economy, environment, physical and mental health of manufacturers, uses of power, equality, democracy, access to information and participation, civil liberties, privacy, crime and justice.
- Identify unintended consequences of technology development.
- Create safeguards to minimize problems.
- Apply lessons from earlier technologies and experiences of other countries.

Recognition of the need for, and an ability to engage in life-long learning.

- Identify learning needs and set specific learning objectives.
- Make a plan to address these objectives.
- Evaluate inquiry.
- Assess the reliability of sources.
- Evaluate how the sources contribute to knowledge.
- Question the adequacy and appropriateness of forms of evidence used to report back on learning needs.
- Apply knowledge discovered to the problem.

Table 4. Repetitive Activities in the Problem-Solving Cycle

	Professional Skill				
Activity	Communicate	Teams	Responsibilities	Impact	Learning
Identifying learning–knowledge needs as a team–individual					X
Acquiring knowledge needed to solve problem			X	X	X
Reporting back to team	X	X			X
Digging deeper and solving	X	X	X	X	X
Presenting solution to audience of experts	X				
Writing a report on problem solution	X				

There are a variety of methods programs can employ to foster the development of these professional skills in students. These include the use of team-based capstone design experiences, facilitating student participation in coop and internship experiences, encouraging involvement in undergraduate research projects, and incorporating oral and written communication exercises throughout the curriculum.

The creation of new undergraduate biomedical engineering programs has led to the development of some new approaches to professional skills development. For example, the Wallace H. Coulter Department of Biomedical Engineering at Georgia Tech and Emory University has implemented an integrative approach to the development of professional skills and adaptive expertise in its program. This approach anchors professional skills development in the context of team-based problem solving and design experiences over the four-year curriculum. This approach provides multiple opportunities for the students to work on and develop skills and knowledge in a variety of "real-world" engineering settings in which these professional skills are practiced. Within each experience, activities are identified within the problem-solving cycle that help students develop these professional skills. These activities are described in Table 4.

The need for real-world problems cannot be overstated. Authentic, open-ended problems are needed as contexts and catalysts for the development of these professional skills. Not only do they help prepare students for the professional practice of engineering, but they are also a significant motivator for the students to delve more deeply into the problem space. Moreover, the use of these skills in the context of a large problem makes them central not peripheral to biomedical engineering problem solving. They begin to understand the value of clear, thoughtful communication, and collaboration when confronting complex problems. They see how ethical issues can arise when seeking design solutions. If the problems are authentic, then the information needed to solve them must be found in multiple places, which helps students to develop inquiry and research skills for lifelong learning.

SUMMARY

The field of biomedical engineering had its foundations laid roughly 50 years ago. Undergraduate degree programs in the field followed shortly thereafter. Fueled in part by generous support from the Whitaker Foundation, there has been a significant increase in the number of new undergraduate degree programs in the field. This has led to a significant increase in student interest in the field. This growth has increased the need for the biomedical engineering education community to work with industry to better define the skills that graduates need to obtain to lead productive careers in the field. There exists a movement, led by the NSF VaNTH ERC, to define a core undergraduate curriculum within the constraints imposed by ABET accreditation criteria. The VaNTHs vision to transform bioengineering education to produce adaptive experts has been adopted by new undergraduate degree programs and has produced demonstrated examples of pedagogical advances in the field of engineering education.

BIBLIOGRAPHY

Cited References

1. NIH working definition of bioengineering. 1997, July 24. National Institutes of Health Bioengineering Consortium. Available at http://www.becon.nih.gov/bioengineering_definition.htm. Accessed 2004 Nov. 18.
2. Planning a career in biomedical engineering. 1999. Biomedical Engineering Society. Available at http://www.bmes.org/careers.asp. Accessed 2004 Nov. 18.
3. A history of biomedical engineering. 2002, May. The Whitaker Foundation. Available at http://www.whitaker.org/glance/definition.html. Accessed 2004 Nov. 19.
4. Accredited engineering programs. 2004. Accreditation Board for Engineering and Technology. Available at http://www.abet.org/ accredited_programs/engineering/EACWebsite.asp. Accessed 2004 Nov. 19.
5. Criteria for accrediting engineering programs. 2004. Accreditation Board for Engineering and Technology. Available at http://www.abet.org/criteria.html. Accessed 2004 Nov. 19.
6. Bureau of Labor Statistics, U.S. Department of Labor, Occupational Outlook Handbook. 2004–2005 edition, Biomedical Engineers. Available at http://www.bls.gov/oco/ocos262.htm. Accessed 2005 Feb. 10.
7. RA Linsenmeier, What makes a biomedical engineer, IEEE Eng Med Biol Mag 2003;22(4):32–38.
8. Cordray DS, Pion GM, Harris A, Norris P. The value of the VaNTH Engineering Research Center. IEEE Eng Med Biol Mag 2003;22(4):47–54.
9. Biomedical Engineering Educational Summit, The Whitaker Foundation. Available at http://summit.whitaker.org/. Accessed 2005 Feb 10.
10. Enderle J, Gassert J, Blanchard S, King P, Beasley D, Hale P, Aldridge D. The ABCs of preparing for ABET. IEEE Eng Med Biol Mag 2003;22(4):122–132.

11. Waples LM, Ropella KM. University partnerships in biomedical engineering. IEEE Eng Med Biol Mag 2003;22(4): 118–121.
12. The biomedical engineering curriculum database 2004. The Whitaker Foundation. Available at http://www.whitaker.org/academic/database/index.html. Accessed 2004 Nov. 18.
13. VaNTH ERC curriculum project (2004, June 10). VaNTH ERC [Online]. Available at http://www.vanth.org/curriculum/. Accessed [2004 Nov. 18].
14. Bransford JD, Brown AL, Cocking RR, editors. How People Learn: Brain, Mind, Experience, and School. Washington: National Academy Press; 1999.
15. Harris TR, Bransford JD, Brophy SP. Roles for learning sciences and learning technologies in biomedical engineering education: A review of recent advances. Annu Rev Biomed Eng 2002;4:29–48.
16. Benkeser PJ, Newstetter WC. Integrating soft skills in a BME curriculum, Proc. 2004 ASEE Annu Conf. 2004, June. American Society for Engineering Education. Available at http://www.asee.org/about/events/conferences/search.cfm. Accessed 2004 Nov. 19.

See also BIOINFORMATICS; MEDICAL EDUCATION, COMPUTERS IN; MEDICAL ENGINEERING SOCIETIES AND ORGANIZATIONS.

BIOSURFACE ENGINEERING

PETER MOLNAR
MELISSA HIRSCH-KUCHMA
JOHN W. RUMSEY
KERRY WILSON
JAMES J. HICKMAN
University of Central Florida
Orlando, Florida

INTRODUCTION

One primary reason there is a tremendous amount of interest in cellular patterning techniques is that numerous examples in nature use these techniques to segregate cells into tissues, vessels, and organs. The idea of templates in nature abounds for the creation of organized biological systems using both inorganic (1), as well as organic template systems (2). There is also a certain allure to being able to integrate electrically active cells directly to electronic devices using standard electronic fabrication techniques. Researchers have attempted to use surface cues to pattern cells since as early as 1917, in which spider webs were used to pattern cells (3). Most of the early work on cellular patterning used topographical cues until 1988, when a landmark publication by Kleinfeld et al. (4) used lithographic templating to fabricate simple patterns of cortical neurons. This was an adaptation of standard technology developed by the electronics industry to create computer chips that was then applied to the creation of patterns to guide neuronal cell attachment. It was at this point that interest in this field mushroomed, as the idea of creating neuronal networks from living neurons has potential applications in understanding biological information processing, creating hybrid computer systems, as well as a whole host of biomedical applications. Some prominent efforts to use cell patterning have been for spinal cord repair, creation of *in vitro* test bed systems to study diseases, as well as blood vessel formation from patterned endothelial cells (5). The initial lithography-based technique used by Kleinfeld et al. has been extended to include many other methods for the patterning of cells, including self-assembled monolayer (SAM) patterning, laser ablation, microcontact printing or stamping, ink jet printing, AFM printing, as well as patterning using microfluidic networks. Methods have also been extended in the area of topographical cues for 3D patterning, which has evolved from early work that used scratched grooves in glass surfaces. At this point, depending on the facilities that one has available, some form of mask making and pattern templating is available to just about any laboratory in the world. However, the biological interactions with these patterns that have been created are still not well developed, and this limits applications at this point.

There are many reasons for the lack of long-term applications of this technique, even after the large amount of work that has been done in this area. The first is that, in many instances, the patterns direct the initial attachment of cells, but as the extracellular matrix is deposited by the cells, long-term adherence to the patterns is not maintained. Another issue is that longer term cell survival is also dependent on factors besides the surface, such as media composition, cell–cell contact interactions, and the lack of growth factors that are normally present from other support cells and tissues. Defined systems are being developed in an attempt to control these other variables in addition to the surface (6,7), but these efforts have been limited to date. However, as progress is made in these areas, it will open up possible applications in tissue engineering, tissue repair, biosensors, and functional *in vitro* test beds.

PATTERNING METHODS

Many methods have been developed for creating templates to be used for cell patterning. These can be divided roughly into two categories: those that are derived from photolithography techniques and those that depend on physical segregation, although there is some crossover in the methods between the two. The photolithography-based systems typically use some sort of organic layer, from polymers to monolayers, which is illuminated, either directly with a pattern or through the template pattern to be created. This can involve many or a few steps depending on the particular method used. Generally, a second layer is deposited in the area where material was removed. Specific variations of this technique are discussed in this section.

The second major category, physical segregation, involves the actual placement of the molecules or cells in a pattern on a surface. Stamping is the most well-known method of creating a molecular-based template and of all the techniques is probably the most economical, but other techniques have been investigated for physical placement of cells in a desired pattern on the surface. Finally, both of these methods, which are 2D in nature, are now being extended into 3D patterning using many of the same


(a)
Grafting of fluorosilane
UV
UV exposure of photoresist
Development and plasma cleaning
Polylysine absorption
Removal of unexposed photoresist
(b)

Figure 1. Protocol and images of the pattern. (a) Protocol of photolithography. A glass coverslip (continuous line) is coated with domains of fluorosilane molecule (dark) and with regions of polylysine (light gray) according to the pattern designed on the mask (dashed line), using ultraviolet (UV) exposure of a spin-coated photoresist (gray). (b) Images of neural networks of controlled architecture. Top: linear network. Bottom left: matrix 4 × 4. Bottom right: star. Cell bodies of neurons are restricted to squares or disks of 80 μm and neurites to line (80 μm length, 2–4 μm wide). Square and disk diameters are 80 μm for each figure. Scale bar is 50 μm (Ref. 9).

techniques, or combinations thereof, described therein. Below there is a brief description, along with the appropriate references, of the techniques that can be used to create these cellular templates.

Photolithography

A variety of photolithographic techniques has been employed to pattern proteins and cells on surfaces from the micrometer to the nanometer scale (8). The basic tools needed are a radiation source and a photomask. The photomask can be created using standard photolithography processes developed for the electronics industry. Irradiation of the surface through the photomask is used to create the patterns by ablation or by using a photosensitive material such as a photoresist as shown in Fig. 1.

Kleinfeld et al. (4) first demonstrated that dissociated neurons could be grown on 2D substrates consisting of lithographically defined patterned monolayers of diamines and triamines with alkylsilanes. The method used by Kleinfeld et al. started with a clean silicon or quartz surface that was spin coated with a layer of photoresist (an organic photosensitive polymer used in the electronics industry). The resist was exposed to UV light with a patterned photomask and then developed. The surface was refluxed in the presence of an alkylsilane, and the photoresist was then stripped off so that areas the photomask covered were reduced to bare silicon or quartz. These areas were then reacted with an aminosilane to form the patterned surface. The patterned cells developed electrical excitability and immunoreactivity for neuron-specific proteins. A further modification of this technique eliminated the photoresist from the pattern formation by direct ablation of the SAM layer (10).

Patterns of self-assembled monolayers formed from organosilanes on glass or silicon substrates and on gold surfaces can be made by using a photoresist mask and deep UV radiation (10–18). Monolayers can also be directly ablated with various forms of radiation such as UV, X ray, ions, and electrons (8) depending on the resolution needed for the patterns. Organosilanes self-assemble and condense onto substrates that have surface –OH functionalities (19). The –SH functionality of the alkanethiol (20) is also highly reactive to ozone and other irradiation sources and has been used in patterning (21). Methods using X-ray or extreme UV (EUV) radiation give better resolution than the traditional photolithography using deep UV and photoresist masks. The ablated regions of the SAM can then be reacted with an organosilane or alkanethiol with different characteristics from the original layer to enable cell growth (22). Azides (23) and aromatic hydrocarbon silanes (24) have also been shown to be reactive for creating patterns.

A typical method to prepare a patterned glass silanated surface is illustrated next. The glass must first be acid cleaned or oxygen plasma cleaned to maximize the surface –OH functional density. Next, the glass is reacted with a silane that contains -chloro, -methoxy, or -ethoxy bonds in the presence of a small amount of water that acts as a catalyst. A mask is then used to protect certain areas of the surface while allowing the radiation source to ablate others in the desired pattern. The ablated regions of the surface can then be coated with a different silane with different properties than the original, thus forming the patterned surface; an example of this is shown in Fig. 2.

The photoreactivity of polymers, such as poly(ethylene) glycol and polystyrene, has also been used to pattern surfaces (25). Biologically based polymers, such as poly-L-lysine and extracellular matrix proteins, have been ablated tso create patterns (26). Polymer photolithography followed by protein adsorption has been combined to create patterned cytophobic and cytophilic areas. Patterning of perfluoropolymers followed by adsorption of poly-L-lysine



Pattern Cells obeying pattern region

Figure 2. Micrograph of circuit-patterned day 2 *in vitro* hippocampal neurons plated onto DETA/15F modified glass coverslips. Electrophysiology of day 12 *in vitro* hippocampal neurons displaying both spontaneous and evoked activity on a DETA/15F line-space patterned surface. Top trace: post-synaptic neuron. Bottom trace: stimulated presynaptic neuron.

and albumin has been one method used (27). Photosensitive polymers have been treated with UV radiation to create an –COOH functional unit on the surface and then patterned via the linkage of proteins to form cytophilic and cytophobic regions (28). A bioactive photoresist (bioresist) has been developed that does not require the use of solvents that can denature the biomolecule that is patterned (29).

Photolithographic protein patterning requires the attachment of photosensitive groups to proteins on a substrate. Patterns can be made using a patterned mask and selective ablation. This method has been shown to be useful to produce micropatterned cultures (30). Various methods are used to covalently attach proteins in patterns to surfaces (31), to pattern using biomolecule photoimmobilization (32), and to create density gradients of photoreactive biomolecules (33). Heterobifunctional crosslinker molecules have been used to attach proteins to silanated surfaces both before and after the photolithographic patterning step (34). Protein patterning has been achieved using a micromirror array (MMA), which can transfer a pattern from the mirrors that are switched on, ablating a photolabile protecting group (35). Photolithography was also used to pattern thermosensitive copolymers through polymer grafting (36). The surface micropattern appeared and disappeared interchangeably, as observed under a phase-contrast microscope, by varying the temperature between 10 and 37 °C. The copolymer-grafted polystyrene surface was hydrophobic at 37 °C and hydrophilic at 10 °C.

Photolithography provides high resolution patterning and the ability to make complex patterns on surfaces. Unlike stamping techniques, the patterns are more permanent; however, the process can be relatively expensive as it generally requires the use of a laser and clean room facilities for the mask production. To attach proteins, such as ECM proteins, the use of a covalently attached crosslinker is necessary, and stamping techniques are generally preferred for this application.

Microcontact Printing (Stamping)

Microcontact printing was introduced by George Whiteside's group at Harvard in 1994 (37) to pattern self-assembled monolayers on gold substrates to control surface properties, cell adhesion, proliferation, and protein secretion by patterned cells. The basic method to create surface patterns by microcontact printing has not changed much since then. Usually, a poly(dimethylsiloxane) (PDMS) stamp is created using a molding technique from a master pattern relief mold and then used to transfer chemical patterns to flat or curved surfaces. The master is usually prepared from silicon by standard photolithography and/or etching, but other substrates can also be used. The transferred chemical patterns can be created using a compound that binds covalently to the substrate (e.g., self-assembled monolayers or proteins immobilized by cross-linkers) (38) or a compound that binds noncovalently, such as absorbed extracellular matrix proteins (39). This methodology is illustrated in Fig. 3. Oliva et al. presented a novel method to couple proteins to patterned surfaces based on the strong interaction of protein A and the Fc fragment of immunoglobulins. This method involved the creation of a covalently coupled Fc fragment and the target protein (41). Methods have also been developed to transfer proteins from a fluid phase to a surface using hydrogels as the stamp (42). Moreover, recently introduced techniques are allowing the creation of protein gradients with microcontact printing (43). Although alignment of the stamp/patterns with surface features such as microelectrodes is more difficult than in the case of photolithographic patterning, several groups are beginning to address this issue (44). Microcontact printing is usually a favored method among biologists compared with photolithography, because (*1*) the equipment and controlled environment facilities required for photolithography are not routinely available to cell biologists and (*2*) the steps are simpler to pattern proteins, the molecules of greatest interest to biologists, using microcontact printing than with photolithography and crosslinkers. The refinement of the PDMS molding technique has directly led to the development of another important patterning method, microfluidics, which gained wider applications with the introduction of microelectromechanical systems (MEMS) and "lab-on-a-chip" systems. However, initial results using PDMS indicated some transfer of the PDMS to the surface during the stamping process. This can be troublesome in cell patterning applications as PDMS can be toxic to cells or mask the chemical functionality of interest. Methods of "curing" the stamps or presoaking to enable better release of the compound has been reported (45).


Si
Silicon wafer
Spin coat photoresist
Photoresist
Si
Expose to UV light through a mask and then expose to a solution of developer
"Master"
Si
Cast PDMS
PDMS
Si
Remove PDMS from master
"Stamp"
PDMS
100 μm - 1 cm
1 μm - 500 μm
Features: ~500 nm - 500 μm
"Stamp"
PDMS
1. Ink stamp with alkanethiol
2. Place stamp on metal
A.
B.
Mold polyurethane against PDMS
Stamp
Alkanethiol
Gold or silver
PDMS
Si or Glass
PDMS
Glass
Polyurethane
Remove stamp
1. Remove PDMS
2. Evaporate Au or Ag
Patterned SAM
Si or Glass
Glass
Wash with other alkanethiol
Place stamp on metal
PDMS
Alkanethiol
Gold or silver
Si or Glass
Glass
Remove stamp
Glass
Wash with other alkanethiol
Glass

Figure 3. The creation of the master stamp is indicated on the left side of the figure, and its use to make patterns is indicated on the flow chart to the right (40).

Inkjet Printing

Inkjet technology used in desktop printers can be applied to the creation of viable cell patterns by printing proteins on to a surface (46). It is a fast and inexpensive method that does not require any contact (such as with stamping) to the surface. This method is desirable for high throughput printing of surfaces, and there is good control of the drop volume and of the alignment of the pattern. Printing occurs when small volumes of a protein solution or a solution containing cells is pumped through a nozzle in a continuous jet or small droplets of the solution are formed either by an acoustic or thermal pulse. The drop size is in the range of 10–20 pL (8). Inkjet printing and the use of computer-aided design (CAD) have impacted the biomaterials field greatly in the areas of biosensor development (47), immobilization of bacteria on biochips (48), DNA arrays and synthesis (49), microdeposition of proteins on cellulose (50), and free-form fabrication techniques to create acellular polymeric scaffolds. A drawback of this method is that the resolution, in the 20–50 μm range, is limited by the statistical variations in the drop direction and spreading on the surface (8). Other high throughput printing methods have also been adapted to pattern proteins on surfaces for biological application such as the already developed DNA spotter used to create DNA microchips (51).

Patterning via Microfluidic Networks

Synthetic surfaces may also be patterned using microfluidic networks (μFNs) to selectively generate regions with greater cytophilicity. This method involves the use of a microfluidic network fabricated in an elastomeric polymer, usually polydimethylsiloxane (PDMS), to direct a protein solution to the regions where cell-adhesion is desired. Gravity and pressure-driven flows are the most common methods for circulating the solution.

The most basic application of this method involves allowing a solution of the material to be patterned noncovalently to the substrate surface using the microchannels as guides. Some of the earliest work done with this method by Folch and Toner (52) involved patterning of various polymer surfaces with human plasma fibronectin (Fn) and collagen to create adhesion promoting domains for hepatocyte/fibroblast cocultures. Similar work by Chiu et al. (53) involved the patterning of glass coverslips with fibrinogen (Fb) and bovine serum albumin (BSA) for patterned cocultures with bovine adrenal capillary endothelial cells (BCEs) and human bladder cancer cells (ECVs). Further work by Takayama et al. (54) demonstrated an added degree of sophistication of this technique by using the laminar flow characteristics of microchannels to generate patterns using a single microchannel.

In addition to simple noncovalent binding of proteins to the substrate, it is possible to use a crosslinking agent to covalently link a molecule of interest. Delamarche et al. (55) used a hydroxylsuccinimidyl ester to chemically couple immunoglobulin G (IgG) to various substrates. Another more commonly used method involves functionalized silane SAMs on substrates, such as 3-aminopropyltriethoxysilane (APTES), and a crosslinking reagent, such glutaraldehyde (GA), to achieve crosslinking of protein molecules to a substrate. Romanova et al. (25) demonstrated the applicability of this method using microfluidic patterning to study controlled growth of *Aplysia* neurons on geometric patterns of poly-L-lysing and collagen IV. Yet another variation on this method was developed by Itoga et al. (56), who generated patterns by photopolymerization of acrylamide on 3-methacryloxypropyltrimethoxysilane modified glass coverslips. In this method, the acrylamide monomer was flowed through microchannels adhered to the derivatized coverslip and cross-linked via photopolymerization to generate cytopholic poly-acrylamide regions.

Perhaps the most sophisticated application of microfluidic patterning of substrates for cell adhesion was demonstrated by Tan and Desai (57,58), who demonstrated the fabrication of complex multilayer cocultures for biomimetic blood vessels. In this work, the 3D structure of blood vessels was recreated by differential deposition of protein and cell layers on a glass coverslip. By alternately layering proteins (Collagen I, collagen/chitosan, and matrigel) and cell types found in blood vessels (fibroblasts, smooth muscle, and endothelial cells), it was possible to recreate layers mimicking the adventitial, medial, and intimal layers observed in blood vessels.

Topographical (3D) Patterning Methods

Control of Cell Placement, Movement, and Process Growth Based on Topographical Clues. It has been known for many years that cells react to topographical clues in their environment (59). Originally, natural fibers were used to create topological clues. Later, fabrication methods developed for the microchip industry were adapted to micromachine silicon surfaces for cell culture applications (45). For the creation of micro- or nanotopography, sophisticated methods and equipment are necessary, which are available in most electronics laboratories, but are usually not available to cell biologists. In recent years, as a response to the increased need for high- throughput screening methods (planar patch clamp, lab-on-a-chip) and in response to the challenge of biological applications of nanoscience, several multidisciplinary team/centers have been established with microfabrication capabilities. The most commonly used fabrication methods are (*1*) silicon etching (60), (*2*) photoresist-based methods (61), (*3*) PDMS molding (62), and (*4*) polymer/hydrogel molding (63). Methods have also been developed for the creation of complex 3D structures by the rapid prototyping/layer-by-layer technique (58). Tan et al. (62) used 3D PDMS structures not only to control attachment and morphology of cells but also to measure attachment force through flexible microneedles as the culture substrate. Xi et al. used AFM cantilevers to demonstrate and measure the contracting force of cardiac muscle cells (64).

3D Patterning of Living Cells. Several hydrogel scaffold-based methods have also been developed to create 3D patterns from cells. For example, photo-polymerization of hydrogels can be used to create patterns of entrapped cells (65). These scaffolding methods offer possible intervention in spinal cord injury (66). Layer-by-layer methods have also been used to create complex “tissue analog” cellular structures, such as blood vessels (57).

Other Patterning Methods

Several other methods, based on microcontact printing and PDMS stamping, have been developed to create cellular patterns. Folch et al. used an inexpensive method to create microwells for coculture experiments based on a reusable elastomeric stencil (i.e., a membrane containing thru holes), which seals spontaneously against the surface (67,68). Gole and Sastry developed a novel method to pattern surfaces with lipids followed by selective protein incorporation into the lipid patterns that result in complex protein patterns on the surface (69). A scanning electrochemical microscope has also been adapted to pattern self-assembled monolayers on surfaces with high spatial resolution by either chemical removal of SAMs (70) or by gold deposition (71). Amro et al. used an AFM tip to directly print nanoscale patterns using the so-called dip-pen technique (72–74). However, none of these methods has been proven beyond the demonstration step.

Applications

Many *potential* applications for cell patterning remain in the biomedical and biotechnology fields. However, there has been limited success to date, besides demonstrations in the literature, for any of the applications envisioned by the host of researchers in this area. However, the promise of the use of cellular patterning for real applications is bolstered by the success that has been achieved for patterning of DNA, RNA, and protein arrays (42,51) as well as for enzymatic biosensors, such as simple pregnancy tests. Much like with cellular patterning, there was a period of time during the development of molecular patterning techniques before the applications became relevant, and the authors believe this is the situation that exists for cell patterning at this time. One reason for this long development stage is that viable and reproducible cellular patterns have many other variables that are not a major issue with biomolecule patterning applications. The cellular media are very important for cell survival, especially long term, as well as cell preparation, which has a significant affect on an extracellular attachment. In addition, no universal combination will be good for every cell, as each cell type has a unique environment that it needs to survive and function, and some aspect of these factors needs to be reproduced for long-term applications. That said, many examples of tissues exhibit some segregation, including blood vessels, lung tissue, the lining of the stomach and intestines, as well as a host of other tissues, which could benefit from this methodology. However, one of the most studied cell tissues is that of the central nervous system (CNS), which exhibits a complicated network of structures that will be difficult to reproduce for reconstruction or repair of neuronal tissue or for other *in vivo* as well as *in vitro* applications. To date, there has been some success in manipulating cells in patterns and controlling certain variables that would be necessary for the creation of functional tissues, but a complete system, using this methodology, has not been reported in the literature. However, there has been some success in demonstrating the intermediate steps that will be necessary for the realization of applications of this method for biomedical and biotechnological applications. Cell attachment has been demonstrated by several researchers, and generally, pattern adherence is maintained for approximately 1 week although longer times have been demonstrated (75). Control of cell morphology and differentiation are two important factors that are necessary in creating functional systems, and these have also been demonstrated. For neuronal-based systems, the primary variable, that of axonal polarity, has also been demonstrated. Brief descriptions and progress in these areas are described below.

Controlling Cell Attachment, Morphology, and Differentiation. *In vivo*, cells are arranged in distinct patterns (76). This patterning effect is dictated during development, with cues provided by both physical contact with other cells and chemicals present in the extracellular matrix (77). Because the random arrangement of cells cultured *in vitro* does not represent the complex architecture seen in tissues, studies of many cell types lack a clear *in vivo* relationship. Consequently, techniques to create defined and reproducible functional patterns of cells on surfaces have been created.

Controlling Attachment and Morphology. Several methods have been developed to control the attachment of cells on surfaces creating patterns that more accurately mimic conditions found *in vivo*. Using photolithography, microcontact printing, and microstamping, groups have been able create 2D patterns that guide cell attachment and alignment (37,78–81). Three-dimensional patterning techniques have also been employed to influence cell orientation and polarity of neurons and osteoblasts (82–84). Cells have also been attached to capillaries and microfluidic devices using SAMs and protein adsorption or microcontact printing (85,86). Additionally, cell attachment and proliferation has been enhanced using biomolecules attached covalently, by stamping, or microcontact printing to surfaces (37,78–82,84–87).

Controlling Morphology and Differentiation of Cell Types Other Than Neurons. Microfabrication and photolithography used to create microtextured membranes for cardiac myocyte culture showed greater levels of attachment and cell height relative to 2D culture techniques (88). Similar techniques applied to vascular smooth muscle also showed the ability to control shape and size of the cells (89). Furthermore, microtextured surfaces were shown to influence gene expression and protein localization in neonatal cardiomyocytes (90). Cues provided to cells by the topography of their extracellular environment are thought to play a role in differentiation. The generation of microtopographical surfaces in titanium has been used to regulate the differentiation of osteoblasts *in vitro* (91).

Study of Axon Guidance in Neurons. Using photolithographic techniques and SAMs, the 2D patterns created were shown to influence neuronal polarity (22). Photolithographically fabricated 3D surfaces demonstrated that topology also influenced the orientation of neurons and the polarity of axonal outgrowth (83). The ability to guide neurite outgrowth and axonal elongation has significant applications in the areas of spinal cord repair, synapse, formation, and neural network formation. Initial studies using striped patterns on glass coverslips showed that neurons would adhere and preferentially extend axons along the length of the pattern (4,92). Growth of neurons on micropatterned 2D surfaces showed preferential axon extension along the length of the pattern as well as increased axon extension (92–96).

The use of 3D microchannels and microstructured surfaces has also been shown to increase the complexity of neuronal architecture, increase neurite growth, and enhance cell activity (61). Photolithography has also been used to pattern neurons and control axon elongation for the formation of neuronal networks (25,97). The synapses formed by these hippocampal neurons showed strong electrophysiological activity up to 17 days in culture (10). These network formations show promise for use in screening pharmacological agents as well as for electronic connection.

BIBLIOGRAPHY

Cited References

1. Fritz M, Belcher AM, Radmacher M, Walters DA, Hansma PK, Stucky GD, Morse DE, Mann S. Flat pearls from biofabrication of organized composites on inorganic substrates. Nature Biotechnol 1994;371:49–51.
2. Noctor SC, Flint AC, Weissman TA, Dammerman RS, -Kriegstein AR. Neurons derived from radial glial cells establish radial units in neocortex. Nature 2001: 409(6821): 714–720.
3. Harrison RG. The reaction of embryonic cells to solid structures. J Exp Zool 1914;17:521–544.
4. Kleinfeld D, Kahler KH, Hockberger PE. Controlled outgrowth of dissociated neurons on patterned substrates. J Neurosci 1988;8(11):4098–4120.
5. Spargo BJ, Testoff MA, Nielsen TB, Stenger DA, Hickman JJ, Rudolph AS. Spatially controlled adhesion, spreading, and differentiation of endothelial-cells on self-assembled molecular monolayers. Proc Nat Acad Sci 1994;91(23):11070–11074.
6. Das M, Molnar P, Gregory C, Riedel L, Jamshidi A, Hickman JJ. Long-term culture of embryonic rat cardiomyocytes on an organosilane surface in a serum-free medium. Biomaterials 2004;25(25):5643–5647.
7. Das M, Bhargava N, Gregory C, Riedel L, Molnar P, Hickman JJ. Adult rat spinal cord culture on an organosilane surface in a novel serum-free medium. In Vitro Animal Cell Develop Bio 2005. In press.
8. Geissler M, Xia Y. Patterning: Principles and some new developments. Adv Mater 2004;16(15):1249–1269.
9. Wyart C, Ybert C, Bourdieu L, Herr C, Prinz C, Chatenay D. Constrained synaptic connectivity in functional mammalian neuronal networks grown on patterned surfaces. J Neurosci Methods 2002;117(2):123–131.
10. Dulcey CS, Georger JHJr. Krauthamer V, Stenger DA, Fare TL, Calvert JM. Deep UV photochemistry of chemisorbed monolayers: Patterned coplanar molecular assemblies. Science 1991;252(5005):551–554.
11. Dressick WJ, Calvert JM. Patterning of self-assembled films using lithographic exposure tools. Appl Phys Part 1 1993; 32(12B):5829–5839.
12. Bhatia SK, Teixeira JL, Anderson M, Shriver-Lake LC, Calvert JM, Georger JH, Hickman JJ, Dulcey CS, Schoen PE, Ligler FS. Fabrication of surfaces resistant to protein adsorption and application to two-dimensional protein patterning. Anal Biochem 1993;208(1):197–205.
13. Liu J, Hlady V. Chemical pattern on silica surface prepared by UV irradiation of 3-mercaptopropyltriethoxy silane layer: Surface characterization and fibrinogen adsorption. Colloids Surfaces B-Biointerfaces 1996;8(1–2):25–37.
14. Dressick WJ, Dulcey CS, Chen MS, Calvert JM. Photochemical studies of (aminoethylaminomethyl)phenethyltrimethoxysilane self-assembled monolayer films. Thin Solid Films 1996;285:568–572.
15. Georger JH, Stenger DA, Rudolph AS, Hickman JJ, Dulcey CS, Fare TL. Coplanar patterns of self-assembled monolayers for selective cell-adhesion and outgrowth. Thin Solid Films 1992;210(1–2):716–719.

16. Stenger DA, Georger JH, Dulcey CS, Hickman JJ, Rudolph AS, Nielsen TB, McCort SM, Calvert JM. Coplanar molecular assemblies of aminoalkylsilane and perfluorinated alkylsilane—characterization and geometric definition of mammalian-cell adhesion and growth. J Am Chem Soc 1992;114 (22):8435–8442.
17. Calvert JM. Lithographic patterning of self-assembled films. J Vacuum Sci Technol B 1993;11(6):2155–2163.
18. Ravenscroft MS, Bateman KE, Shaffer KM, Schessler HM, Jung DR, Schneider TW, Montgomery CB, Custer TL, Schaffner AE, Liu QY, Li YX, Barker JL, Hickman JJ. Developmental neurobiology implications from fabrication and analysis of hippocampal neuronal networks on patterned silane- modified surfaces. J Am Chem Soc 1998;120(47): 12169–12177.
19. Plueddemann EP. Silane adhesion promoters in coatings. Progr Organic Coatings 1983;11(3):297–308.
20. Whitesides GM, Laibinis P, Folkers J, Prime K, Seto C, Zerkowski J. Self-assembly—alkanethiolates on gold and hydrogen-bonded networks. Abstr Papers Am Chem Soc 1991;201:103-INOR.
21. Gillen G, Wight S, Bennett J, Tarlov MJ. Patterning of self-assembled alkanethiol monolayers on silver by microfocus ion and electron-beam bombardment. Appl Phys Lett 1994;65(5): 534–536.
22. Stenger DA, Hickman JJ, Bateman KE, Ravenscroft MS, Ma W, Pancrazio JJ, Shaffer K, Schaffner AE, Cribbs DH, Cotman CW. Microlithographic determination of axonal/dendritic polarity in cultured hippocampal neurons. J Neurosci Methods 1998;82(2):167–173.
23. Matsuda T, Sugawara T. Development of surface photochemical modification method for micropatterning of cultured-cells. J Biomed Mater Res 1995;29(6):749–756.
24. Dulcey CS, Georger JH, Chen MS, McElvany SW, Oferrall CE, Benezra VI, Calvert JM. Photochemistry and patterning of self-assembled monolayer films containing aromatic hydrocarbon functional groups. Langmuir 1996;12(6):1638–1650.
25. Romanova EV, Fosser KA, Stanislav SR, Nuzzo RG, Sweedler JV. Engineering the morphology and electrophysiological parameters of cultured neurons by microfluidic surface patterning. FASEB J 2004.
26. Corey JM, Wheeler BC, Brewer GJ. Compliance of hippocampal neurons to patterned substrate networks. J Neurosci Res 1991;30(2):300–307.
27. Griscom L, Degenaar P, LePioufle B, Tamiya E, Fujita H. Techniques for patterning and guidance of primary culture neurons on micro-electrode arrays. Sen Actuators B 2002;83 (1–3):15–21.
28. Nicolau DV, Taguchi T, Taniguchi H, Tanigawa H, Yoshikawa S. Patterning neuronal and glia cells on light-assisted functionalised photoresists. Biosens Bioelectron 1999;14(3):317–325.
29. He W, Halberstadt CR, Gonsalves KE. Lithography application of a novel photoresist for patterning of cells. Biomaterials 2004;11:2055–8063.
30. Liu GY, Amro NA. Positioning protein molecules on surfaces: A nanoengineering approach to supramolecular chemistry. Proc Nat Acad Sci 2002;99(8):5165–5170.
31. Pirrung MC, Huang CY. A general method for the spatially defined immobilization of biomolecules on glass surfaces using "caged" biotin. Bioconjugate Chem 1996;7(3):317–321.
32. Sigrist H, Collioud A, Clemence JF, Gao H, Luginbuhl R, Sanger M, Sundarababu G. Surface immobilization of biomolecules by light. Opt Eng 1995;34(8):2339–2348.
33. Herbert CB, McLernon TL, Hypolite CL, Adams DN, Pikus L, Huang CC, Fields GB, Letourneau PC, Distefano MD, Hu WS. Micropatterning gradients and controlling surface densities of photoactivatable biomolecules on self-assembled monolayers of oligo(ethylene glycol) alkanethiolates. Chem Bio 1997;4(10): 731–737.
34. Sorribas H, Padeste C, Tiefenauer L. Photolithographic generation of protein micropatterns for neuron culture applications. Biomaterials 2002;23(3):893–900.
35. Lee K-N, Shin D-S, Lee Y-S, Kim Y-K. Protein patterning by virtual mask photolithography using a micromirror array. J Micromech Microeng 2003;13(1):18–25.
36. Chen GP, Imanishi Y, Ito Y. Effect of protein and cell behavior on pattern-grafted thermoresponsive polymer. J Biomed Mater Res 1998;42(1):38–44.
37. Singhvi R, Kumar A, Lopez GP, Stephanopoulos GN, Wang DI, Whitesides GM, Ingber DE. Engineering cell shape and function. Science 1994;264(5159):696–698.
38. Lahiri J, Ostuni E, Whitesides GM. Patterning ligands on reactive SAMs by microcontact printing. Langmuir 1999;15 (6):2055–2060.
39. Cornish T, Branch DW, Wheeler BC, Campanelli JT. Microcontact printing: A versatile technique for the study of synaptogenic molecules. Mol Cell Neurosci 2002;20(1):140–153.
40. Kane RS, Takayama S, Ostuni E, Ingber DE, Whitesides GM. Patterning proteins and cells using soft lithography. Biomaterials 1999;20(23–24):2363–2376.
41. Oliva AA, James CD, Kingman CE, Craighead HG, Banker GA. Patterning axonal guidance molecules using a novel strategy for microcontact printing. Neurochem Res 2003;28 (11):1639–1648.
42. Martin BD, Gaber BP, Patterson CH, Turner DC. Direct protein microarray fabrication using a hydrogel "stamper". Langmuir 1998;14(15):3971–3975.
43. Mayer M, Yang J, Gitlin I, Gracias DH, Whitesides GM. Micropatterned agarose gels for stamping arrays of proteins and gradients of proteins. Proteomics 2004;4(8):2366–2376.
44. Lauer L, Ingebrandt S, Scholl M, Offenhausser A. Aligned microcontact printing of biomolecules on microelectronic device surfaces. IEEE Trans Biomed Eng 2001;48(7):838–842.
45. Craighead HG, James CD, Turner AMP. Chemical and topographical patterning for directed cell attachment. Curr Opin Solid State Mater Sci 2001;5(2–3):177–184.
46. Roth EA, Xu T, Das M, Gregory C, Hickman JJ, Boland T. Inkjet printing for high-throughput cell patterning. Biomaterials 2004;25(17):3707.
47. Newman JD, Turner APF, Marrazza G. Ink-jet printing for the fabrication of amperometric glucose biosensors. Anal Chim Acta 1992;262(1):13–17.
48. Xu T, Jin J, Gregory C, Hickman JJ, Boland T. Inkjet printing of viable mammalian cells. Biomaterials 2005;26(1):93–99.
49. Schena M, Heller RA, Thieriault TP, Konrad K, Lachenmeier E, Davis RW. Microarrays: Biotechnology's discovery platform for functional genomics. Trends Biotechnol 1998;16(7):301–306.
50. Roda A, Guardigli M, Russo C, Pasini P, Baraldini M. Protein microdeposition using a conventional ink-jet printer. Biotechniques 2000;28(3):492–496.
51. Flaim CJ, Chien S, Bhatia SN. An extracellular matrix microarray for probing cellular differentiation. Nature Methods 2005;2(2):119–125.
52. Folch A, Toner M. Cellular micropatterns on biocompatible materials. Biotechnol Progr 1998;14(3):388–392.
53. Chiu DT, Jeon NL, Huang S, Kane RS, Wargo CJ, Choi IS, Ingber DE. Whitesides GM. Patterned deposition of cells and proteins onto surfaces by using three-dimensional microfluidic systems. Proc Natl Acad Sci USA 2000;97(6):2408–2413.
54. Takayama S, McDonald JC, Ostuni E, Liang MN, Kenis PJA, Ismagilov RF, Whitesides GM. Patterning cells and their

environments using multiple laminar fluid flows in capillary networks. Proc Natl Acad Sci USA 1999;96(10):5545–5548.
55. Delamarche E, Bernard A, Schmid H, Michel B, Biebuyck H. Patterned delivery of immunoglobulins to surfaces using microfluidic networks. Science 1997;276(5313):779–781.
56. Itoga K, Yamamoto JK, Kikuchi A, Okano T. Micropatterned surfaces prepared using a liquid crystal projector-modified photopolymerization device and microfluidics. J Biomed Mater Res 2004;69A:391–397.
57. Tan W, Desai TA. Microscale multilayer cocultures for biomimetic blood vessels. J Biomed Mater Res 2005;72A(2):146–160.
58. Tan W, Desai TA. Layer-by-layer microfluidics for biomimetic three-dimensional structures. Biomaterials 2004;25(7–8): 1355–1364.
59. Curtis A, Wilkinson C. Topographical control of cells. Biomaterials 1997;18(24):1573–1583.
60. Turner S, Kam L, Isaacson M, Craighead HG, Shain W, Turner J. Cell attachment on silicon nanostructures. J Vacuum Sci Technol B 1997;15(6):2848–2854.
61. Mahoney MJ, Chen RR, Tan J, Saltzman WM. The influence of microchannels on neurite growth and architecture. Biomaterials 2005;26(7):771–778.
62. Tan JL, Tien J, Pirone DM, Gray DS, Bhadriraju K, Chen CS. Cells lying on a bed of microneedles: An approach to isolate mechanical force. Proc Natl Acad Sci USA 2003;100(4):1484–1489.
63. Recknor JB, Recknor JC, Sakaguchi DS, Mallapragadaa SK. Oriented astroglial cell growth on micropatterned polystyrene substrates. Biomaterials 2004;25(14):2753–2767.
64. Xi JZ, Schmidt J, Montemagno C. Development of self-assembled muscle-MEMS microdevices. Biophys J 2004;86 (1):481A.
65. Albrecht DR, Tsang VL, Sah RL, Bhatia SN. Photo- and electropatterning of hydrogel-encapsulated living cell arrays. Lab Chip 2005;5(1):111–118.
66. Bloch J, Fine EG, Bouche N, Zurn AD, Aebischer P. Nerve growth factor- and neurotrophin-3-releasing guidance channels promote regeneration of the transected rat dorsal root. Exper Neurol 2001;172(2):425–432.
67. Folch A, Jo BH, Hurtado O, Beebe DJ, Toner M. Microfabricated elastomeric stencils for micropatterning cell cultures. J Biomed Mater Res 2000;52(2):346–353.
68. Ostuni E, Kane R, Chen CS, Ingber DE, Whitesides GM. Patterning mammalian cells using elastomeric membranes. Langmuir 2000;16(20):7811–7819.
69. Gole A, Sastry M. A new method for the generation of patterned protein films by encapsulation in arrays of thermally evaporated lipids. Biotechnol Bioeng 2001;74(2):172–178.
70. Shiku H, Uchida I, Matsue T. Microfabrication of alkylsilanized glass substrate by electrogenerated hydroxyl radical using scanning electrochemical microscopy. Langmuir 1997;13(26):7239–7244.
71. Turyan I, Matsue T, Mandler D. Patterning and characterization of surfaces with organic and biological molecules by the scanning electrochemical microscope. Anal Chem 2000;72 (15):3431–3435.
72. Amro NA, Xu S, Liu GY. Patterning surfaces using tip-directed displacement and self-assembly. Langmuir 2000; 16(7): 3006–3009.
73. Schwartz PV. Molecular transport from an atomic force microscope tip: A comparative study of dip-pen nanolithography. Langmuir 2002;18(10):4041–4046.
74. Agarwal G, Sowards LA, Naik RR, Stone MO. Dip-pen nanolithography in tapping mode. J Am Chem Soc 2003; 125(2):580–583.
75. Chang JC, Brewer GJ, Wheeler BC. A modified microstamping technique enhances polylysine transfer and neuronal cell patterning. Biomaterials 2003;24:2862–2870.
76. Curtis A, Riehle M. Tissue engineering: the biophysical background. Phys Med Biol 2001; 46(4):R47–R65.
77. Curtis A, Wilkinson C. Reactions of cells to topography. J Biomater Sci Pol Educ 1998;9:1313–1329.
78. Li B, Ma Y, Wang S, Moran PM. A technique for preparing protein gradients on polymeric surfaces: effects on PC12 pheochromocytoma cells. Biomaterials 2005;26:1487–1495.
79. McFarland CD, Thomas CH, DeFilippis C, Stelle JG, Healy KE. Protein adsorption and cell attachment to patterned surfaces. J Biomed Mater Res 2000;49(2):200–210.
80. Veiseh M, Wickes BT, Castner DG, Zhang MQ. Guided cell patterning on gold-silicon dioxide substrates by surface molecular engineering. Biomaterials 2004;25(16):3315–3324.
81. Zheng H, Berg MC, Rubner MF, Hammond PT. Controlling cell attachment selectively onto biological polymer-colloid templates using polymer-on-polymer stamping. Langmuir 2004;20(17):7215–7222.
82. Ber S, Kose GT, Hasirci V. Bone tissue engineering on patterned collagen films: An *in vitro* study. Biomaterials 2005; 16:1977–1986.
83. Dowell-Mesfin NM, Abdul-Karim MA, Turner AM, Schanz S, Craighead HG, Roysam B, Turner JN, Shain W. Topographically modified surfaces affect orientation and growth of hippocampal neurons. J Neural Eng 2004;1(2): 78–90.
84. Mohammed JS, DeCoster MA, McShane MJ. Micropatterning of nanoengineered surfaces to study neuronal cell attachment *in vitro*. Biomacromolecules 2004;5(5):1745–1755.
85. Mrksich M, Chen CS, Xia YN, Dike LE, Ingber DE, Whitesides GM. Controlling cell attachment on contoured surfaces with self- assembled monolayers of alkanethiolates on gold. Proc Natl Acad Sci USA 1996;93(20):10775–10778.
86. Theibaud P, Lauer L, Knoll W, Offenhausser A. PDMS device for patterned application of microfluids to neuronal cells arranged by microcontact printing. Biosen Bioelectro 2002; 17:87–93.
87. Scholl M, Sprossler C, Denyer M, Krause M, Nakajima K, Maelicke A, Knoll W, Offenhausser A. Ordered networks of rat hippocampal neurons attached to silicon oxide surfaces. J Neurosci Methods 2000;104(1):65–75.
88. Deutsch J, Motiagh D, Russell B, Desai TA. Fabrication of microtextured membranes for cardiac myocyte attachment and orientation. J Biomed Mater Res 2000;53(3):267–275.
89. Goessl A, Bowen-Pope DF, Hoffman AS. Control of shape and size of vascular smooth muscle cells *in vitro* by plasma lithography. J Biomed Mater Res 2001;57(1):15–24.
90. Motlagh D, Senyo SE, Desai TA, Russell B. Microtextured substrata alter gene expression, protein localization and the shape of cardiac myocytes. Biomaterials 2003;24(14):2463–2476.
91. Zinger O, Zhao G, Schwartz Z, Simpson J, Wieland M, Landolt D, Boyan B. Differential regulation of osteoblasts by substrate microstructural features. Biomaterials 2005;26 (14):1837–1847.
92. Matsuzawa M, Liesi P, Knoll W. Chemically modifying glass surfaces to study substratum-guided neurite outgrowth in culture. J Neurosci Methods 1996;69(2):189–196.
93. Clark P, Britland S, Connolly P. Growth cone guidance and neuron morphology on micropatterned laminin surfaces. J Cell Sci 1993;105:203–212.

94. Saneinejad S, Shoichet MS. Patterned poly(chlorotrifluoroethylene) guides primary nerve cell adhesion and neurite outgrowth. J Biomed Mater Res 2000;50(4):465–474.
95. Tai H, Buettner HM. Neurite outgrowth and growth cone morphology on micropatterned surfaces. Biotechnol Prog 1998;14:364–370.
96. Zhang ZP, Yoo R, Wells M, Beebe TP, Biran R, Tresco P. Neurite outgrowth on well-characterized surfaces: Preparation and characterization of chemically and spatially controlled fibronectin and RGD substrates with good bioactivity. Biomaterials 2005;26(1):47–61.
97. Heller DA, Garga V, Kelleher KJ, Lee TC, Mahbubani S, Sigworth LA, Lee TR, Rea MA. Patterned networks of mouse hippocampal neurons on peptide-coated gold surfaces. Biomaterials 2005;26(8):883–889.

See also BIOCOMPATIBLITY OF MATERIALS; BIOMATERIALS, SURFACE PROPERTIES OF; BIOMATERIALS: TISSUE ENGINEERING AND SCAFFOLDS.

BIOMEDICAL EQUIPMENT MAINTENANCE. See EQUIPMENT MAINTENANCE, BIOMEDICAL.

BIOSENSORS. See IMMUNOLOGICALLY SENSITIVE FIELD-EFFECT TRANSISTORS.

BIOTELEMETRY

BABAK ZIAIE
Purdue University
W. Lafayette, Indiana

INTRODUCTION

The ability to use wireless techniques for measurement and control of various physiological parameters inside human and animal bodies has been a long-term goal of physicians and biologists going back to the early days of wireless communication. From early on, it was recognized that this capability could provide effective diagnostic, therapeutic, and prosthetic tools in physiological research and pathological intervention. However, this goal eluded scientists prior to the invention of transistor in 1947. Vacuum tubes were too bulky and power hungry to be of any use in many wireless biomedical applications. During the late 1950s, MacKay performed his early pioneering work on what he called Endoradiosonde (1). This was a single-transistor blocking oscillator designed to be swallowed by a subject and was able to measure pressure and temperature in the digestive track. Following this early work, came a number of other simple discrete systems each designed to measure a specific parameter (temperature, pressure, force, flow, etc.) (2). By the late 1960s, progress in the design and fabrication of integrated circuits provided an opportunity to expand the functionality of these early systems. Various hybrid single and multichannel telemetry systems were developed during the 1970s and the 1980s (3). In addition, implantable therapeutic and prosthetic devices started to appear in the market. Cardiac pacemakers and cochlear prosthetics proved effective and reliable enough to be implanted in thousands of patients. We direct the interested readers to several excellent reviews published over the past several decades summarizing these advances in their perspective time periods. These include a review article by W. H. Ko and M. R. Neuman in the *Science* covering the technologies available in the 1960s (4) and another similar paper by Topich covering the 1970s period (5). Three subsequent reviews detailed the efforts in the 1980s (6–8) followed by the most recent article published in 1999 (9). An outdated, but classic reference book in biotelemetry, is by MacKay, which still can be used as a good starting point for some simple single channel systems and includes some ingenious techniques used by early investigators to gain remote physiological information (10).

The latter part of the 1990s witnessed impressive advances in microelectromechanical (MEMS) based transducer and packaging technology, new and compact power sources (high efficiency inductive powering and miniature batteries), and CMOS low power wireless integrated circuits that provided another major impetus to the development of biotelemetry systems (11–18). These advances have created new opportunities for increased reliability and functionality, which had been hard to achieve with pervious technologies. The term biotelemetry itself has been for most part superseded by Microbiotelemetry or Wireless Microsystems to denote these recent changes in technology. Furthermore, the burgeoning area of nanotechnology is poised to further enhance these capabilities beyond what have been achievable using current miniaturization techniques. This is particularly true in the biochemical sensing and chemical delivery areas and will undoubtedly have a major impact on the future generations of implantable biotelemetry microsystems.

This review article is intended to complement and expand the earlier reviews by emphasizing newer developments in the area of biomedical telemetry in particular attention is paid to the opportunities created by recent advances in the area of microbiotelemetry (i.e., systems having volumes $\sim$1 cm^3 or less) by low power CMOS wireless integrated circuits, micromachined–MEMS transducers, biocompatible coatings, and advanced batch-scale packaging. We have both expanded and narrowed the traditional definition of biotelemetry by including therapeutic–rehabilitative microsystems and excluding wired devices that although fit under the strict definition of biotelemetry; do not constitute an emerging technology. In the following sections, after discussing several major components of such biotelemetry microsystems, such as transducers, interface electronics, wireless communication, power sources, and packaging, we will present some selected examples to demonstrate the state of the art. These include implantable systems for biochemical and physiological measurements, drug delivery microsystems, and neuromuscular and visual prosthetic devices. Although our primary definition of biotelemetry encompass devices with active electronics and signal processing capabilities, we will also discuss passive MEMS-based transponders that do not require on-board signal processing and can be interrogated using simple radio-frequency (rf) techniques. Finally, we should mention that although in a strict sense biotelemetry encompasses systems targeted for physiological measurements, this narrow definition is no longer valid or desirable. A broader scope including neuromuscular stimulation and chemical delivery is currently understood to be more indicative of the term biotelemetry.

BIOTELEMETRY SYSTEMS

For the purpose of current discussion biotelemetry systems can be defined as a group of medical devices that (*1*) incorporate one or several miniature transducers (i.e., sensors and actuators), (*2*) have an on-board power supply (i.e., battery) or are powered from outside using inductive coupling, (*3*) can communicate with outside (bidirectional or unidirectional) through an rf interface, (*4*) have on-board signal processing capability, (*5*) are constructed using biocompatible materials, and (*6*) use advanced batch-scale packaging techniques. Although one microsystem might incorporate all of the above components, the demarcation line is rather fluid and can be more broadly interpreted. For example, passive MEMS-based microtransponders do not contain on-board signal processing capability, but use advanced MEMS packaging and transducer technology and are usually considered to be a telemetry device. We should also emphasize that the above components are interrelated and a good system designer must pay considerable attention from the onset to this fact. For example, one might have to choose a certain power source or packaging scheme to accommodate the desired transducer, interface electronics, and wireless communication. In the following sections, we will discuss various components of a typical biotelemetry system with more attention being paid to the wireless communication block. For other components, we provide a brief discussion highlighting major recent developments and refer the reader to some recent literature is these areas.

Transducers

Transducers are interfaces between biological tissue and readout electronics–signal processing. Their performance is critical to the success of the overall microsystem (19–24). Current trend in miniaturization of transducers and their integration with signal processing circuitry have considerably enhanced their performance. This is particularly true with respect to MEMS-based sensors and actuators, where the advantages of miniaturization have been prominent. Development in the area of microactuators has been lagging behind the microsensors due to the inherent difficulty in designing microdevices that efficiently and reliably generate motion. Although some transducing schemes, such as electrostatic force generation, has advantageous scaling properties in the microdomain, problems associated with packaging and reliability has prevented their successful application. The MEMS-based microsensors have been more successful and offer several advantages compared to the macrodomain counterparts. These include lower power consumption, increased sensitivity, higher reliability, and lower cost due to batch fabrication. However, they suffer from a poor signal/noise ratio, hence requiring a close by interface circuit. Among the many microsensors designed and fabricated over the past two decades, physical sensors have been by and large more successful. This is due to their inherent robustness and isolation from any direct contact with biological tissue in sensors, such as accelerometers and gyroscopes. Issues related to packaging and long-term stability have plagued the implantable chemical sensors. Long-term baseline and sensitivity stability are major problems associated with implantable sensors. Depending on the type of the sensor, several different factors contribute to the drift. For example, in implantable pressure sensors, packaging generated stresses due to thermal mismatch and long-term material creep are the main sources of baseline drift. In chemical sensors, biofouling and fibrous capsule formation is the main culprit. Some of these can be mitigated through clever mechanical design and appropriate choice of material, however, some are more difficult to prevent (e.g., biofouling and fibrous capsule formation). Recent developments in the area of antifouling material and controlled release have provided new opportunities to solve some of these long standing problems (25–27).

Interface Electronics

As mentioned previously, most miniature and MEMS-based transducers suffer from poor signal/noise ratio and require on-board interface electronics. This, of course, is also more essential for implantable microsystems. The choice of integrating the signal processing with the MEMS transducer on the same substrate or having a separate signal processing chip in close proximity depends on many factors, such as process complexity, yield, fabrication costs, packaging, and general design philosophy. Except for post-CMOS MEMS processing methods, which rely on undercutting micromechanical structures subsequent to the fabrication of the circuitry (28), other integrated approaches require extensive modifications to the standard CMOS processes and have not been able to attract much attention. Post-CMOS processing is an attractive approach although packaging issues still can pose roadblocks to successful implementation. Hybrid approach has been typically more popular with the implantable biotelemetry microsystem designers providing flexibility at a lower cost. Power consumption is a major design consideration in implantable wireless microsystems that rely on batteries for an energy source. Low power and subthreshold CMOS design can reduce the power consumption to nanowatt levels (29–33). Important analogue and mixed-signal building blocks for implantable wireless microsystems include amplifiers, oscillators, multiplexers, A/D and D/A converters, and voltage references. In addition, many such systems require some digital signal processing and logic function in the form of finite-state machines. In order to reduce the power consumption, it is preferable to perform the DSP functions outside the body although small finite-state machines can be implemented at low power consumptions.

Wireless Communication

The choice of appropriate communication scheme for a biotelemetry system depends on several factors, such as (*1*) number of channels, (*2*) device lifetime, and (*3*) transmission range. For single (or two) channel systems, one can choose a variety of modulation schemes and techniques.

These systems are the oldest type of biotelemetry devices (1) and can range from simple blocking oscillators to single channel frequency modulation (FM) transmitters. They are attractive since one can design a prototype rather quickly using off-the-shelf components. Figure 1 shows a schematic of the famous blocking oscillator first used by MacKay to transmit pressure and temperature (10). It consists of a single bipolar transistor oscillator configured to periodically turn itself on and off. The oscillation frequency depends on the resonant frequency of the tank circuit that can be made to vary with parameters, such as pressure, by including a capacitive or inductive pressure sensor. The on–off repetition frequency can be made to depend on the temperature by incorporating a thermistor in the circuit. This is an interesting example of an ingenious design that can be accomplished with a minimum amount of effort and hardware. An example of a more recent attempt at single channel telemetry is a two-channel system designed by Mohseni et al. to transmit moth electromyograms (34). The circuit schematic and a picture of the fully assembled device are shown in Fig. 2. As can be seen, each channel


$R_{\text{Thermistor}}$
V_{CC}
C_1
L
C_2

Figure 1. Schematic circuit of a blocking oscillator used to transmit pressure and temperature.


Vcc
Lt
Rb
Rb1
Cc2
C2
Cc1
T1
C1
Cby
J1
EMG
Rg
Rs
Cs
Cb
Rb2
Re
Biopotential amplifier
FM transmitter
Antenna Pad
RC Chip
Battery Clips
Polyimide Substrate
One Channel
1 cm

Figure 2. Schematic diagram and photograph of a biotelemetry system used to transmit flight muscle electromyograms in moths showing the polyimide flex circuit and various components (the Colpitts Oscillator inductor is used as the transmitting antenna).

consists of a biopotential amplifier followed by a Colpitts oscillator with operating frequency tunable in the 88–108 MHz commercial FM band. The substrate for the biotelemetry module was a polyimide flex circuit in order to reduce the weight such that the Moth can carry the system during flight. The overall system measures $10 \times 10 \times 3$ mm, weighs 0.74 g, uses two 1.5 V batteries, dissipates ~ 2 mW, and has a transmission range of 2 m.

Multichannel systems are of more scientific and clinical interest. These systems rely on different and more elaborate communication schemes. For the purpose of current discussion, we will divide these systems into the ones that operate with a battery and the ones that are powered from outside using an inductive link. Battery-operated biotelemetry microsystems rely on different communication schemes than the inductively powered ones. Figure 3 shows a schematic block diagram of a time-division multiplexed multichannel system. It consists of several transducers with their associated signal conditioning circuits. These might include operations, such as simple buffering, low level amplification, filtering, or all three. Subsequent to signal conditioning, different channels are multiplexed using an analogue MUX. Although recent advances in AD technology might allow each channel to be digitized prior to multiplexing, this is not an attractive option for biotelemetry systems (unless there are only a few channels), since it requires an increase in power consumption that most biotelemetry systems cannot afford. All the timing and framing information is also added to the outgoing multiplexed signal at this stage. After multiplexing, an AD converter is used to digitize the signal. This is followed by a rf transmitter and a miniature antenna. The transmitted signal is picked up by a remote receiver and the signal is demodulated and separated accordingly. The described architecture is the one used currently by most investigators. Although over the years many different modulation scheme (pulse-width-modulation, pulse-position-modulation, pulse-amplitude-modulation, etc.) and system architectures have been tried; due to the proliferation of inexpensive integrated low power AD converters, the pulse-code-modulation (PCM) using an integrated AD is the dominant method these days.

The transmission of the digitized signal can be accomplished using any of the several digital modulation schemes (PAM, PFM, QPSK, etc.), which offer standard trade offs between transmitter and receiver circuit complexity, power consumption, and signal/noise ratio (35). Typical frequencies used in such systems are in the lower UHF range (100–500 MHz). Higher frequencies result in smaller transmitter antenna at the expense of increased tissue loss. Although tissue loss is a major concern in transmitting power to implantable microsystems, it is less of an issue in data transmission, since a sensitive receiver outside the body can easily demodulate the signal. Recent advances in low power CMOS rf circuit design has resulted in an explosive growth of custom made Application Specific Integrated Circuits (ASIC), and off-the-shelf rf circuits suitable for a variety of biotelemetry applications (36–38). In addition, explosive proliferation of wireless communication systems (cell phones, wireless PDAs, Wi-Fi systems, etc.) have provided a unique opportunity to piggyback major WLAN manufacturers and simplify the design of biotelemetry microdevices (39,40). This cannot only increase the performance of the system, but also creates a standard platform for many diverse applications. Although the commercially available wireless chips have large bandwidths and some superb functionality, their power consumption is higher than what is acceptable for many of the implantable microsystems. This, however, is going to change in the future by the aggressive move



Figure 3. Block diagram of a multichannel biotelemetry system.

toward lower power handheld consumer electronics. A particularly attractive WLAN system suitable for biotelemetry is the Bluetooth system (41). This system, which was initially designed for wireless connection of multiple systems (computer, fax, printer, PDA, etc.) located in close proximity, has been adopted by many medical device manufacturer for their various biotelemetry applications. The advantage of Bluetooth compared to other Wi-Fi system, such as 902.11-b, is its lower power consumption at the expense of a smaller data rate (2.4 GHz carrier frequency, 1 Mbps data rate, and 10 m transmission range). This is not critical in most biotelemetry applications since the frequency bandwidth of most physiologically important signals are low (< 1 kHz). However, note that since the Bluetooth carrier frequency is rather high (2.4 GHz), the systems using Bluetooth or similar WLAN devices can not operate from inside the body and has to be worn by the subject on the outside.

Inductively powered telemetry systems differ from the battery operated ones in several important ways (42). First and foremost, the system has to be powered by an rf signal from outside; this puts several restrictions on frequency and physical range of operation. For implantable systems, the incoming signal frequency has to remain low in order for it to allow enough power to be coupled to the device (this means a frequency range of 1–10 MHz, see next section). In addition, if the device is small, due to a low coupling coefficient between the transmitter and receiver coil, the transmission range is usually limited to distances < 10 cm. Finally, in inductively powered systems, one has to devise a method to transmit the measured signal back to the outside unit. This can be done in several different ways with the load-modulation being the most popular method (43). In "load modulation", the outgoing digital stream of data is used to load the receiver antenna by switching a resistor in parallel with the tank circuit. This can be picked up through the transmitter coil located outside the body. A second technique that is more complex requires an on-chip transmitter and a second coil to transmit the recorded data at a different frequency. The inward link can be easily implemented using amplitude modulation, that is, the incoming rf signal that powers the microsystem is modulated by digitally varying the amplitude. It is evident that the modulation index cannot be 100% since that would cut off the power supply to the device (unless a storage capacitor is used). The coding scheme is based on the pulse time duration, that is,"1" and "0" have the same amplitude, but different durations (42). This modulation technique requires a simple detection circuitry (envelope detector) and is immune to amplitude variations, which are inevitable in such systems.

In addition to the above mentioned differences between the battery operated and inductively powered biotelemetry systems, the implanted circuit in the latter case also includes several modules that are unique and require special attention. These have mostly to do with power reception (rectifier and voltage regulator), clock extraction, and data demodulation. Figure 4 shows a block diagram of the receiver circuit for an inductively powered microsystem currently being developed in the author's laboratory for the measurement of intraocular pressure in glaucoma patients. It consists of a full-bridge rectifier, a voltage regulator, a piezoresistive pressure sensor, and voltage to frequency converter. The incoming rf signal is first rectified and used to generate a stable voltage reference being used by the rest of the circuit (amplifiers, filters, etc.). The clock is extracted from the incoming rf signal and is used wherever it is needed in the receiver circuit. The pressure sensor bridge voltage is first amplified and converted to a stream of pulses having a frequency proportional to the pressure. This signal is then used to load-modulate the tank circuit. The receiver circuitry for most of the reported inductively powered biotelemetry systems were fabricated through CMOS foundries, such as MOSIS. This is due to the fact that one can simply design a single chip performing all of the mentioned functions in a CMOS technology, and hence save valuable space. In the sections dealing with various applications, we will describe several other inductively powered telemetry systems.



Figure 4. Block diagram of an implantable biotelemetry system used in the measurement of intraocular pressure in glaucoma patients.

There has not been much effort in the area of antenna design for biotelemetry applications. This is due to the basic fact that these systems are small and operate at low frequencies, hence, most antennas employed in such systems belong to the"small antenna" category, that is, the antenna size is much smaller than the wavelength. In such cases it is difficult to optimize the design and most investigators simply use a short electrical or magnetic dipole. For example, in many situations the inductor in the output stage can be used to transmit the information. Or alternatively, a short wire can be used in the transmitter as an electrical dipole. These antennas are usually low gain and have an omnidirectional pattern (44). Systems operating at higher frequencies, such as externally worn Wi-Fi modules, however, can benefit from an optimized design.

In addition to using an rf signal to transmit information that constitutes the majority of the work in the biotelemetry area, the use of ultrasound and infrared (IR) have also been explored by some investigators (45,46). The use of ultrasound is attractive in telemetering physiological information from aquatic animals and divers. This is due to the fact that rf signals are strongly absorbed by seawater while ultrasound is not affected to the same extent. The use of IR is also limited to some specific areas, such as systems that can be worn by the animal on the outside and are not impeded by solid obstructions. This is due to the inability of IR to negotiate solid opaque objects (line of sight propagation) and its severe absorption by tissue. The advantage of free space IR transmission lies in its very wide bandwidth making it useful for transmitting neural signals. The rf, ultrasonic, and IR systems share many of the system components discussed so far, with the major difference between them having to do with the design and implementation of the output stage. The output transmitter for the ultrasonic biotelemetry systems is usually an ultrasonic transducer, such as PZT or PVDF, whereas for the IR systems it is usually a simple light-emitting diode (LED). The driver circuitry has to be able to accommodate the transducers, that is, a high voltage source for driving the ultrasonic element and a current.

Power Source

The choice of power source for implantable wireless microsystems depends on several factors, such as implant lifetime, system power consumption, temporal mode of operation (continuous or intermittent), and size. Progress in battery technology is incremental and usually several generations behind other electronic components (47). Although lithium batteries have been used in pacemakers for several years, they are usually large for microsystem applications. Other batteries used in hearing aids and calculators are smaller, but have limited capacity and can only be used for low power systems requiring limited lifespan or intermittent operation. Inductive powering is an attractive alternative for systems with large power requirements (e.g., neuromuscular stimulators) or long lifetime (e.g., prosthetic systems with >5 years lifetime) (14,15). In such systems, a transmitter coil is used to power a microchip using magnetic coupling. The choice of the transmission frequency is a trade-off between adequate miniaturization and tissue loss. For implantable microsystems, the frequency range of 1–10 MHz is usually considered optimum for providing adequate miniaturization while still staying below the high tissue absorption region ($>$10 MHz) (48). Although the link analysis and optimization methods have been around for many years (49), recent integration techniques that allow the fabrication of microcoils on top of CMOS receiver chip has allowed a new level of miniaturization (50). For applications that require the patient to carry the transmitter around, a high efficiency transmitter is needed in order to increase the battery lifetime. This is particularly critical in implantable microsystem, where the magnetic coupling between the transmitter and the receiver is low ($<1\%$). Class-E power amplifier/transmitters are popular among microsystem designers due to their high efficiency ($>80\%$) and relatively easy design and construction (51,52). They can also be easily amplitude modulated through supply switching.

Although ideally one would like to be able to tap into the chemical reservoir (i.e., glucose) available in the body to generate enough power for implantable microsystems (glucose-based fuel cell), difficulty in packaging and low efficiencies associated with such fuel cells have prevented their practical application (53). Thin-film batteries are also attractive, however, there still remain numerous material and integration difficulties that need to be resolved (54). Another alternative is nuclear batteries. Although they have been around for several decades and were used in some early pacemakers, safety and regulatory concerns forced medical device companies to abandon their efforts in this area. There has been a recent surge of interest in microsystem nuclear batteries for military applications (55). It is not hard to envision that due to the continuous decrease in chip power consumption and improve in batch scale MEMS packaging technology, one might be able to hermetically seal a small amount of radioactive source in order to power an implantable microsystem for a long period of time. Another possible power source is the mechanical movements associated with various organs. Several proposals dealing with parasitic power generation through tapping into this energy source have been suggested in the past few years (56). Although one can generate adequate power from activities, such as walking, to power an external electronic device, difficulty in efficient mechanical coupling to internal organ movements make an implantable device hard to design and utilize.

Packaging and Encapsulation

Proper packaging and encapsulation of biotelemetry microsystems is a challenging design aspect particularly if the device has to be implanted for a considerable period. The package must accomplish two tasks simultaneously: (*1*) protect the electronics from the harsh body environment while providing access windows for transducers to interact with the desired measurand, and (*2*) protect the body from possible hazardous material in the microsystem. The second task is easier to fulfill since there is a cornucopia of various biocompatible materials available to the implant designer (57). For example, silicon and glass, which are the material of choice in many MEMS applications, are both biocompatible. In addition, polydimethylsiloxane (PDMS) and several other polymers (e.g., polyimide, polycarbonate, parylene) commonly used in microsystem design are also accepted by the body. The first requirement is, however, more challenging. The degree of protection required for implantable microsystems depends on the required lifetime of the device. For short durations (several months), polymeric encapsulants might be adequate if one can conformally deposit them over the substrates (e.g., plasma deposited parylene) (58). These techniques are considered non-hermetic and have a limited lifetime. For long-term operation, hermetic sealing techniques are required (59). Although pacemaker and defibrillator industries have been very successful in sealing their systems in tight titanium enclosures; these techniques are not suitable for microsystem applications. For example a metallic enclosure prevents the transmission of power and data to the microsystem. In addition, these sealing methods are serial in nature (e.g., laser or electron beam welding) and are not compatible with integrated batch fabrication methods used in microsystem design. Silicon–glass electrostatic and silicon–silicon fusion bonding are attractive methods for packaging implantable microsystems (60). Both of these bonding methods are hermetic and can be performed at the wafer level. These are particularly attractive for


External telemeteric components
External coil
Spectacles
Cable to hand-held-unit
Pressure sensor, internal telemetric components
Eye
Artificial intraocular lens

Figure 5. Schematic of the IOP measurement microsystem (61).



Figure 6. Micrograph of the IOP measurement microsystem receiver chip showing surface micromachined capacitive pressure sensors and other parts of the receiver circuitry (62).

inductively powered wireless microsystems since most batteries cannot tolerate the high temperatures required in such substrate bondings. Other methods, such as metal electroplating, have also been used to seal integrated MEMS microsystems. However, their long-term performance is usually inferior to the anodic and fusion bondings. In addition to providing a hermetic seal, the package must allow feeedthrough for transducers located outside the package (18). In macrodevices, such as pacemakers, where the feedthrough lines are large and not too many, traditional methods, such as glass–metal or ceramic–metal has been employed for many years. In microsystems, such methods are not applicable and batch scale techniques must be adopted.

DIAGNOSTIC APPLICATIONS

Diagnostic biotelemetry microsystems are used to gather physiological or histological information from within the body in order to identify pathology. Two recent examples are discussed in this category. The first is a microsystem designed to be implanted in the eye and to measure the intraocular pressure in order to diagnose low tension glaucoma. The second system, although not strictly implanted, is an endoscopic wireless camera-pill designed to be swallowed in order to capture images from the digestive track.

Figure 5 shows the schematic diagram of the intraocular pressure (IOP) measurement microsystem (61,62). This device is used to monitor the IOP in patients suffering from low tension glaucoma, that is, the pressure measured in the doctor's office is not elevated (normal IOP is ~10–20 mmHg, 1.33–2.66 kPa) while the patient is showing optic nerve degeneration associated with glaucoma. There is great interest in measuring the IOP in such patients during their normal course of daily activity (exercising, sleeping, etc). This can only be achieved using a wireless microsystem. The system shown in Fig. 5 consists of an external transmitter mounted on a spectacle, which is used to power a microchip implanted in the eye. A surface micromachined capacitive pressure sensor integrated with CMOS interface circuit is connected to the receiving antenna. The receiver chip implemented in an n-well 1.2 μm CMOS technology has overall dimensions of $2.5 \times 2.5\ \mathrm{mm}^2$ and consumes 210 μW (Fig. 6). The receiver polyimide-based antenna is, however, much larger (1 cm in diameter and connected to the receiver using flip chip bonding) requiring the device to be implanted along with an artificial lens. The incoming signal frequency is 6.78 MHz, while the IOP is transmitted at 13.56 MHz using load-modulation scheme. This example illustrates the levels of integration that can be achieved using low power CMOS technology, surface micromachining, and flip chip bonding.

The second example in the category of diagnostic microsystems is an endoscopic wireless pill shown in Fig. 7 (63,64). This pill is used to image small intestine, which is a particularly hard area to reach using current fiber optic technology. Although these days colonoscopy and gastroscopy are routinely performed, they cannot reach the small intestine and many disorders (e.g., frequent bleeding) in this organ have eluded direct examination. A wireless endoscopic pill cannot only image the small intestine, but also will reduce the pain and discomfort associated with regular gastrointestinal endoscopies. The endoscopic pill is a perfect example of what can be called *Reemerging Technology*, that is, the rebirth of an older technology based on new capabilities offered by advances in modern technology. Although the idea of a video pill is not new, before the development of low power microelectronics, white LED, CMOS image sensor, and wide-band wireless communication, fabrication of such a device was not feasible. The video pill currently marketed by Given Imaging Inc. is 11 mm in diameter and 30 mm in length (size of a large vitamin tablet) and incorporates: (*1*) a short focal length lens, (*2*) a CMOS image sensor (90,000 pixel), (*3*) four white LEDs, (*4*) a low power ASIC transmitter, and (*5*) two batteries (enough to allows the pill to go though the entire digestive track). The pill can capture and transmit



(a)

(b)

Figure 7. A photograph (a) and internal block diagram (b) of Given Imaging wireless endoscopic pill. (Courtesy Given Imaging.)

two images per second to an outside receiver capable of storing up to 5 h of data.

THERAPEUTIC APPLICATIONS

Therapeutic biotelemetry microsystems are designed to alleviate certain symptoms and help in the treatment of a disease. In this category, two such biotelemetry microsystems unit be described. The first is a drug delivery microchip designed to administer small quantities of potent drugs upon receiving a command signal from the outside. The second device is a passive micromachined glucose transponder, which can be used to remotely monitor glucose fluctuations allowing a tighter blood glucose control through frequent measurements and on-demand insulin delivery (pump therapy or multiple injections).

Figure 8 shows the central component of the drug delivery microchip (65,66). It consists of several microreservoirs (25 nL in volume) etched in a silicon substrate. Each microreservoir contains the targeted drug and is covered by a thin gold membrane (0.3 μm), which can be dissolved through the application of a small voltage (1 V vs. Saturated Calomel Electrode). The company marketing this technology (MicroCHIPS Inc.) is in the process of designing a wireless transceiver that can be used to address individual wells and release the drug upon the reception of the appropriate signal (67). Another company (ChipRx Inc.) is also aiming to develop a similar microsystem (Smart Pill) (68). Their release approach, however, is different and is based on conductive polymer actuators acting similar to a sphincter, opening and closing a tiny reservoir. Due to the potency of many drugs, safety and regulatory issues are more stringent in implantable drug delivery microsystems and will undoubtedly delay their appearance in the clinical settings.

Figure 9 shows the basic concept behind the glucose-sensitive microtransponder (69). A miniature MEMS-based microdevice is implanted in the subcutaneous tissue and an interrogating unit remotely measures the glucose levels without any hardwire connection. The microtrasponder is a passive LC resonator, which is coupled to a glucose-sensitive hydrogel. The glucose-dependent swelling and deswelling of the hydrogel is coupled to the resonator causing a change the capacitor value. This change translates into variations of the resonant frequency, which can be detected by the interrogating unit. Figure 10 shows the schematic drawing of the microtransponder with a capacitive sensing mechanism. The glucose sensitive hydrogel is mechanically coupled to a glass membrane and is separated from body fluids (in this case interstitial fluid) by a porous stiff plate. The porous plate allows the unhindered flow of water and glucose while blocking the hydrogel from escaping the cavity. A change in the glucose concentration of the external environment will cause a swelling or deswelling of the hydrogel, which will deflect the glass membrane and change the capacitance. The coil is totally embedded inside the silicon and can achieve a high quality factor and hence increased sensitivity by utilizing the whole wafer thickness (reducing the series resistance). The coil-embedded silicon and the glass substrate are hermetically sealed using glass–silicon anodic bonding.

REHABILITATIVE MICROSYSTEMS

Rehabilitative biotelemetry microsystems are used to substitute a lost function, such as vision, hearing, or motor activity. In this category, two microsystems are described. The first one is a single-channel neuromuscular microstimulator used to stimulate paralyzed muscle groups in paraplegic and quadriplegic patients. The second microsystem is a visual prosthetic device designed to stimulate ganglion cells in retina in order to restore vision to people afflicted with macular degeneration or retinitis pigmentosa.

Figure 11 shows a schematic of the single channel microstimulator (13). This device is $10 \times 2 \times 2$ mm^3 in dimensions and receives power and data through an inductively coupled link. It can be used to stimulate paralyzed muscle groups using thin-film microfabricated electrodes located at the ends of a silicon substrate. A hybrid capacitor


(a)
Silicon nitride or dioxide
Anode
Silicon
Cathode
Active substance
(b)
(c)

Figure 8. MicroCHIP drug delivery chip (a), a reservoir before and after dissolution of the gold membrane (b,c), the bar is 50 μm (65).

is used to store the charge in between the stimulation pulses and to deliver 10 mA of current to the muscle every 25 ms. A glass capsule hermetically seals a BiCMOS receiver circuitry along with various other passive components (receiver coil and charge storage capacitor) located on top of the silicon substrate. Figure 12 shows a photograph of the microstimulator in the bore of a gauge 10 hypodermic needle. As can be seen, the device requires a complicated hybrid assembly process in order to attach a wire-wound coil and a charge storage capacitor to the


Interrogating Unit
Glucose-Sensitive Microtransponder
Skin
Glucose-Sensitive Hydrogel
Passive LC Resonator

Figure 9. Basic concept behind the glucose-sensitive microtransponder.


Filling port
(epoxy sealed)
Hydrogel
Glass
Silicon
Capacitor
SiO_2
Coil
(Au,Cu)
Passivation
(SiO_2/ Si_3N_4)

Figure 10. Cross-section of glucose microtransponder.


REFERENCE ELECTRODE
RECEIVING COIL (ANTENNA)
HYBRID CHARGE STORAGE CHIP CAPACITOR
GLASS CAPSULE PACKAGE
HYBRID CMOS AND BIPOLAR INTEGRATED CIRCUIT CHIP
SILICON SUBSTRATE
STIMULATING ELECTRODE
2 mm

Figure 11. Schematic of a single-channel implantable neuromuscular microstimulator.


AMERICA
ONE CENT

Figure 12. Photograph of the microstimulator in the bore of a gage 10 hypodermic needle.

receiver chip. In a subsequent design targeted for direct peripheral nerve stimulation (requiring smaller stimulation current), the coil was integrated on top of the BiCMOS electronics and on-chip charge storage capacitors were used thus considerably simplifying the packaging process. Figure 13 shows a micrograph of the chip with the electroplated copper inductor (70). A similar microdevice (i.e., a single channel microstimulator) was also developed by another group of investigators with the differences mainly related to the packaging technique (laser welding of a glass capsule instead of silicon–glass anodic bonding), chip technology (CMOS instead of BiCMOS), and electrode material (tantalum and iridium instead of iridium oxide) (42). Figure 14 shows a photograph of the microstimulator developed by Troyk, Loeb, and their colleagues.

Figure 15 shows the schematic of the visual prosthetic microsystem (71,72). A spectacle mounted camera is used to capture the visual information followed by digital conversion and transmission of data to a receiver chip


Exposed links
for tuning
Connections between
coil and circuitry
Pads for connecting
up to 16 electrodes

Figure 13. Microstimulator chip with integrated receiver coil and on-chip storage capacitor (70).


Ta electrode
Alumina substrate
Ir electrode
Glass-Ta-seal each end
Cu microcoil
Au-plated elgiloy spring
Space for moisture getter
1 cm

Figure 14. Photograph of a single channel microstimulator developed by Troyk (42).

implanted in the eye. The receiver uses this information to stimulate the ganglion cells in the retina through a microelectrode array in sub or epi-retinal location. This microsystem is designed for patients suffering from macular degeneration or retinitis pigmentosa. In both diseases, the light sensitive retinal cells (cones and rods) are destroyed while the more superficial retinal cells, that is, ganglion cells, are still viable and can be stimulated. Considering that macular degeneration is an age related pathology and will be afflicting more and more people as the average age of the population increases, such a microsystem will be of immense value in the coming decades. There are several groups pursuing such a device with different approaches to electrode placement (epi-or sub-retinal), chip design, and packaging. A German consortium that has also designed the IOP measurement microsystem is using a similar approach in antenna placement (receiver antenna in the lens), chip design, and packaging technology to implement a retinal prosthesis (61). Figure 16 shows photographs of the retinal stimulator receiver chip, stimulating electrodes, and polyimide antenna. The effort in the United States is moving along a similar approach (72,72).

CONCLUSIONS

In this article, several biotelemetry microsystems currently being developed in the academia and industry were reviewed. Recent advances in MEMS-based transducers, low power CMOS integrated circuit, wireless communication transceivers, and advanced batch scale packaging have provided a unique opportunity to develop implantable biotelemetry microsystems with advanced functionalities not achievable previously. These systems will be indispensable to the twenty-first century physician by providing assistance in diagnosis and treatment. Future research and development will probably be focused on three areas: (*1*) nanotransducers, (*2*) self-assembly, and (*3*) advanced biomaterials. Although MEMS-based sensors and actuators have been successful in certain areas (particularly physical sensors), their performance could be further improved by utilizing nanoscale fabrication technology. This is particularly true in the area of chemical sensors where future diagnostic depends on detecting very small amounts of chemicals (usually biomarkers) well in advance of any


Stimulating electrodes
1cm
Antenna
Receiver chip

Figure 16. Retinal stimulator receiver chip, stimulating electrodes, and polyimide antenna (61). Chip size.


Transmitter unit
CMOS image-sensor
Neural signal processor
signal / power
FF/ optoelectronic transmission
Retina
Receiver unit
Microcable
Encapsulated stimulator-chip (flexible silicon chip)
Microelectrode array
Stimulation circuitry
Retina encoder
Telemetery
Retina stimulator

Figure 15. Schematic of a visual prosthetic microsystem (61).

physical sign. Nanosensors capable of high sensitivity chemical detection will be part of the future biotelemetry systems. In the actuator–delivery area, drug delivery via nanoparticles is a burgeoning area that will undoubtedly be incorporated into future therapeutic microsystems. Future packaging technology will probably incorporate self-assembly techniques currently being pursued by many micro–nanoresearch groups. This will be particularly important in microsystems incorporating multitude of nanosensors. Finally, advanced nanobased biomaterials will be used in implantable microsystems in order to enhance biocompatibility and prevent biofouling. These will include biocompatible surface engineering and interactive interface design (e.g., surfaces that release anti-inflammatory drugs in order to reduce postimplant fibrous capsule formation).

BIBLIOGRAPHY

Cited References

1. MacKay RS, Jacobson B. Endoradiosonde. Nature (London) 1957;179:1239–1240.
2. MacKay RS. Biomedical telemetry: The Formative Years. IEEE Eng Med Biol Mag 1983;2:11–17.
3. Knutti JW, Allen HV, Meindl JD. Integrated Circuit Implantable telemetry Systems. IEEE Eng Med Biol Mag 1983;2:47–50.
4. Ko WH, Neuman MR. Implant Biotelemetry and Microelectronics. Science 1867;156:351–360.
5. Topich JA. Medical Telemetry. CRC Handbook of Engineering in Medicine and Biology; 1976, p 41–75.
6. Jeutter DC. Biomedical Telemetry Techniques. CRC Crit Rev Biomed Eng 1982;11:121–174.
7. Meindl JD, et al. Implantable Telemetry. Methods Animal Exper 1986;3:37–111.
8. Kimmich HP. Biotelemetry. Encyclopedia of Medical Devices In: Webster JG, editor. 1988, p 409–425.
9. Santic A. Biomedical Telemetry. Wiley Encyclopedia of Electrical and Electronics Engineering, In: Webster JG, editor. 1999. p 438–454.
10. MacKay RS. Biomedical Telemetry, Sensing and Transmitting Biological Information from Animals and Man, 2nd ed. Piscataway (NJ): IEEE Press; 1993.
11. Wise KD. Special Issue on Sensors, Actuators, and Microsystems Proc. IEEE, 1998;86.
12. Cameron T, et al. Micromodular Implants to Provide Electrical Stimulation of Paralyzed Muscles and Limbs. IEEE Trans. Biomed. Eng. 1997;44:781–790.
13. Ziaie B, Nardin M, Coghlan AR, Najafi K. A Single Channel Microstimulator for Functional Neuromuscular Stimulation. IEEE Trans Biomed Eng 1997;44:909–920.
14. Hamici Z, Itti R, Champier J. A High-Efficiency Power and Data Transmission System for Biomedical Implanted Electronic Devices. Measurement Sci Technol. 1996;7:192–201.
15. Heetderks WJ. RF Powering of Millimeter- and Submillimeter-Sized Neural Prosthetic Implants. IEEE Trans Biomed Eng 1988;35:323–327.
16. Gray PR, Meyer RG. Future Directions in Silicon ICs for RF Personal Communications. Proceedings of the Custom Integrated Circuits Conference. 1995, p 83–89.
17. Abidi AA. RF CMOS Come of Age. IEEE Microwave Mag 2003;4:47–60.
18. Ziaie B, Von Arx JA, Dokmeci MR, Najafi K. A Hermetic Glass-Silicon Micropackage with High-Density on-chip Feedthroughs for Sensors and Actuators. IEEE J Microelectromech Systems, 1996;5:166–179.
19. Gopel W, Hesse J, Zemel JN. Sensors: A Comprehensive Survey, Vols. 1–8, New York: VCH Publishers; 1989.
20. Hohler JM, Sautz HP, editor. Microsystem Technology: A Powerful Tool for Biomolecular Studies. Boston: Birkhauser; 1999.
21. Taylor RF, Schultz JS. Handbook of Chemical and Biological Sensors, Boston: IOP Press; 1996.
22. Rogers EK. editor, Handbook of Biosensors and Electronic Nose, Boca Raton, (FL): CRC Press; 1997.
23. Hak GA. editor, The MEMS Handbook. Boca Raton (FL): CRC Press; 2001.
24. Webster JG. editor, The Measurement Instrumentation and Sensors Handbook, Boca Raton (FL): CRC Press; 1998.
25. Zhang M, Desai T, Ferrari M. Proteins and Cells on PEG Immobilized Silicon Surfaces. Biomaterials 1998;19:953–960.
26. Branch DW, Wheeler BC, Brewer GJ, Leckband DE. Long-Term Stability of Grafted Polyethylene Glycol Surfaces for use with Microstamped Substrates in Neuronal Cell Culture. Biomaterials, 2001;22:1035–1047.
27. Alcantar NA, Aydil ES, Israelachvili JN. Polyethylene Glycol-Coated Biocompatible Surfaces. J Biomed Mat Res 2000;51:343–351.
28. Baltes H, Paul O, Brand O. Micromachined Thermally Based CMOS Microsensors. Proc IEEE 1998;86:1660–1678.
29. Stotts LJ. Introduction to Implantable Biomedical IC Design. IEEE Circuits Devices Mag 1989;5:12–18.
30. Stouraitis T, Paliouras V. Considering the Alternatives in Low-Power Design. IEEE Circuits Devices Mag 2001;17:22–29.
31. Tsividis Y, Krishnapura N, Palakas Y, Toth L. Internally Varying Analog Circuits Minimize Power Dissipation. IEEE Circuits Devices Mag 2003;19:63–72.
32. Benini L, De Micheli G, Macii E. Designing Low-power Circuits: Practical Recipes. IEEE Circuits Systems Mag 2001;1:6–25.
33. Rajput SS, Jamuar SS. Low Voltage Analog Circuit Design Techniques. IEEE Circuits Systems Mag 2002;2:24–42.
34. Mohseni P, et al. An Ultra-Light Biotelemetry Backpack for Recording EMG Signals in Moths. IEEE Trans Biomed Eng. June 2001;48:734–737.
35. Proakis JG, Salehi M. Communication System Engineering. Pearson Education; 2001.
36. Lee TH. Design of CMOS Radiofrequency Integrated Circuits. Cambridge: Cambridge University Press, 1998.
37. Razavi B. Challenges in Portable RF Transceiver Design. IEEE Circuits Devices Mag 1996;12:12–25.
38. Larson LE. Integrated Circuit Technology Options for RFICs-Present Status and Future Directions. IEEE J Solid-State Circuits 1998;33:387–399.
39. Crow BP, Wudiaja I, Kim LG, Saki PT. IEEE 802.11 Wireless Local Area Networks. IEEE Commun Mag 1997;35:116–126.
40. Chatschik B. An Overview of the Bluetooth Wireless technology. IEEE Commun Mag 2001;39:86–94.
41. Saltzstein WE. Bluetooth and Beyond: Wireless Options for Medical Devices. Med Device Diagnostic Ind June 2004.
42. Troyk P. Injectable Electronic Identification, Monitoring, and Stimulation Systems. Ann Rev Biomed Eng 1999;1:177–209.
43. Finkenzeller K. RFID Handbook, New York: John Wiley & Sons, Inc; 2003.
44. Kraus JD. Antenna. New York: McGraw-Hill; 2001.
45. Woodward B, Istepanian RSH.Acoustic Biotelemetry of Data from Divers, Proc 15th Annu Int IEEE Eng Med Biol Soc Conf Paris 1992;1000–1001.
46. Kawahito S, et al. A CMOS Integrated Circuit for Multichannel Multiple-Subject Biotelemetry using Bidirectional Optical Transmissions. IEEE Trans Biomed Eng 1994;41:400–406.

47. Linden D, Reddy T. Handbook of Batteries. New York: McGraw-Hill; 2001.
48. Foster KR, Schwan HP. Handbook of Biological Effects of Electromagnetic Fields, In: Polk C, Postow E, editor. Boca Raton (FL): CRC Press; 1996.
49. Ko WH, Liang SP, Fung CDF. Design of Radio-Frequency Powered Coils for Implant Instruments. Med Biol Eng Computing 1977;15:634–640.
50. Ashby KB, et al. High Q Inductors for Wireless Applications in a Complementary Silicon Bipolar Process. IEEE J Solid-State Circuits 1996;31:4–9.
51. Sokal NO, Sokal AD. Class E-A New Class of High-Efficiency Tuned Single-Ended Switching Power Amplifiers. IEEE J. Solid-State Circuits 1975;10:168–176.
52. Ziaie B, Rose SC, Nardin MD, Najafi K. A Self-Oscillating Detuning-Insensitive Class-E Transmitter for Implantable Microsystems. IEEE Trans Biomed Eng 2001;48:397–400.
53. Mehta V, Cooper JS. Review and Analysis of PEM Fuel Cell Design and Manufacturing. J Power Sources 2003;114:32–53.
54. Singh D, et al. Challenges in Making of Thin Films for $\mathrm{Li}_x\mathrm{M}_n\mathrm{yO}_4$ Rechargeable Lithium Batteries for MEMS. J Power Sources 2001;97–98:826–831.
55. Lal A, Blanchard J. Daintiest Dynamos: Nuclear Microbatteries. IEEE Spectrum 2004;42:36–41.
56. Starner T. Human Powered Wearable Computing. IBM J Systems 1996;35:618–629.
57. Ratner BD, Schoen FJ, Hoffman AS, Lemons JE. Biomaterials Science: An Introduction to Materials in Medicine. New York: Elsevier Books; 1997.
58. Loeb GE, Bak MJ, Salcman M, Schmidt EM. Parylene C as a Chronically Stable reproducible Microelectrode material. IEEE Trans Biomed Eng 1977;24:121–128.
59. Nichols MF. The Challenges for Hermetic Encapsulation of Implanted Devices. Critical Rev Biomed Eng 1994;22:39–67.
60. Schmidt MA. Wafer-to-Wafer Bonding for Microstructure Formation. Proc IEEE 1998;86:1575–1585.
61. Mokwa W, Schenakenberg U. Micro-Transponder Systems for Medical Applications. IEEE Trans Instr Meas 2001;50: 1551–1555.
62. Stangel K, et al., A Programmable Intraocular CMOS Pressure Sensor System Implant. IEEE J Solid-State Circuits 2001;36:1094–1100.
63. Iddan G, Meron G, Glukhovsky A, Swain P. Wireless Capsule Endoscopy. Nature (London) 2000;405:417.
64. http://www.givenimaging.com.
65. Santini JT, Cima MJ, Langer R. A Controlled-Release Microchip. Nature (London) 1999;397:335–338.
66. Santini JT, et al. Microchips as Controlled Drug-Delivery Devices. Angew Chem 2000;39:2396–2407.
67. Available at http://www.mchips.com.
68. Available at http://www.chiprx.com.
69. Lei M, et al. A Hydrogel-Based Wireless Chemical Sensor. Proc IEEE MEMS 2004;391–394.
70. Von Arx JA, Najafi K. A Wireless Single-Chip Telemetry-Powered Neural Stimulation System. IEEE Solid-State Circuits Conf 1999;15–17.
71. Liu W, et al. Retinal Prosthesis to Aid the Visually Impaired. IEEE Systems, Man, and Cybernetics, Conf 1999;364–369.
72. Humayun MS, et al. Towards a Completely Implantable, Light-Sensitive Intraocular Retinal Prosthesis. Proc 23rd Ann IEEE EMBS Conf 2001;3422–3425.

See also BIOFEEDBACK; BLADDER DYSFUNCTION, NEUROSTIMULATION OF; MONITORING, INTRACRANIAL PRESSURE; NEONATAL MONITORING; PACEMAKERS.

BIRTH CONTROL. See CONTRACEPTIVE DEVICES.

BLEEDING, GASTROINTESTINAL. See GASTROINTESTINAL HEMORRHAGE.

BLADDER DYSFUNCTION, NEUROSTIMULATION OF

MAGDY HASSOUNA
Toronto Western Hospital

NADER ELMAYERGI
MAZEN ABDELHADY
McMaster University

INTRODUCTION

The discovery of electricity introduced enormous changes to human society: Electricity not only improved daily life, but also opened up new opportunities in scientific research. The effects of electrical stimulation on muscular and nervous tissue have been known for several centuries, but the underlying electrophysiological theory to explain these effects was first derived after the development of classical electrodynamics and the development of nerve cell models (1).

Luigi Galvani first suggested that electricity could produce muscular contraction in his animal experiments (2). He found that a device constructed from dissimilar metals, when applied to the nerve or muscle of a frog's leg, would induce muscular contraction. His work formed the foundation for later discoveries of transmembrane potential and electrically mediated nerve impulses. Alessandro Volta, the inventor of the electrical battery (or voltaic pile) (3), was later able to induce a muscle contraction by producing a potential with his battery and conducting it to a muscle strip. The use of Volta's battery for stimulating nerves or muscles became known as galvanic stimulation.

Another basis for modern neural stimulators was the discovery of the connection between electricity and magnetism, demonstrated by Oersted in 1820; he described the effect of current passing through a wire on a magnetized needle. One year later, Faraday showed the converse—that a magnet could exert a force on a current-carrying wire. He continued to investigate magnetic induction by inducing current in a metal wire rotating in a magnetic field. This device was a forerunner of the electric motor and made it possible to build the magnetoelectric and the induction coil stimulator. The latter, the first electric generator, was called the Faraday stimulator. Faradic stimulation could produce sustained titanic contractions of muscles, instead of a single muscle twitch as galvanic stimulation had done.

Duchenne used an induction coil stimulator to study the anatomy, physiology, and pathology of human muscles. Finally, he was able to study the functional anatomy of individual muscles (4,5). This work is still valid for the investigation of functional neuromuscular stimulation.

Another basis for modern stimulator devices lay in the work of Chaffee and Light (6). They examined the problem of stimulating neural structures deep in the body, while avoiding the risk of infection from percutaneous leads: They implanted a secondary coil underneath the skin and placed a primary coil outside the body, using magnetic induction for energy transfer and modulation. Further improvement was achieved by radio frequency (rf) induction (7,8). The Glenn group developed a totally implanted heart pacemaker—one of the first commercially available stimulators. In the ensuing years, stimulators for different organ systems were developed, among them the above-mentioned heart pacemaker, a diaphragmatic pacemaker (7,8), and the cochlear implant (9).

BLADDER STIMULATION

Electrical stimulation of the bladder dates back to 1878. The Danish surgeon M.H. Saxtorph treated patients with urinary retention by inserting a special catheter with a metal electrode into the urinary bladder transurethrally and placing a neutral electrode suprapubically (10). Also, Katona et al. (11) described their technique of intraluminal electrotherapy, a method that was initially designed to treat a paralytic gastrointestinal tract, but was later used for neurogenic bladder dysfunction in patients with incomplete central or peripheral nerve lesions (11,12).

Further interest in the electrical control of bladder function began in the 1950s and 1960s. The most pressing question at that time was the appropriate location for stimulation. Several groups attempted to initiate or prevent voiding (in urinary retention and incontinence, respectively) by stimulation of the pelvic floor, the detrusor directly, the spinal cord, or the pelvic and sacral nerves or sacral roots. Even other parts of the body, such as the skin, were stimulated in an attempt to influence bladder function (13).

In 1954, McGuire performed extensive experiments of direct bladder stimulations in dogs (14) with a variety of electrodes, both single and multiple, in a variety of positions. Boyce and associates continued this research (15).

It was realized that with a single pair of electrodes, the maximal response was obtained when the electrodes were placed on both lateral bladder walls so that the points of stimulation encompassed a maximal amount of detrusor muscle. When this was performed in human studies, an induction coil for direct bladder stimulation was implanted in three paraplegic men with complete paralysis of the detrusor muscle. The secondary coil was implanted in the subcutaneous tissue of the lower abdominal wall. Of the three, only one was a success, with the other a failure and the third only partially successful (15).

In 1963, Bradley and associates published their experience with an implantable stimulator (16). They were able to achieve complete bladder evacuation in the chronic dog model over 14 months. However, when the stimulator was implanted in seven patients, detrusor contraction was produced, but bladder evacuation resulted in only two. Further experiments were performed in the sheep, calf, and monkey in an attempt to resolve species discrepancies. These animals were chosen because, in the sheep and calf, the bladder is approximately the same size as in the human, and this similarity could determine whether more power is needed for a bladder larger than that of the dog. In addition, the pelvis of monkeys and humans is similarly deep; thus, the influence (if any) of pelvic structure could be investigated. The results showed that a larger bladder needs more power and wider contact between the electrodes and that differences in structure do not necessitate different stimulation techniques (13,16).

PELVIC FLOOR STIMULATION

In 1963, Caldwell described his clinical experience with the first implantable pelvic floor stimulator (17). The electrodes were placed into the sphincter, with the secondary coil placed subcutaneously near the iliac spine. Though this device was primarily designed for the treatment of fecal incontinence; Caldwell also treated urinary incontinence successfully.

Another approach to pelvic floor stimulation for females is intravaginal electrical stimulation, reported initially by Magnus Fall's group (1977) (18). They published numerous studies dealing with this subject in the ensuing years and found that intravaginal electrical stimulation also induces bladder inhibition in patients with detrusor instability. Lindstram, a member of the same group, demonstrated that bladder inhibition is accomplished by reflexogenic activation of sympathetic hypogastric inhibitory neurons and by central inhibition of pelvic parasympathetic excitatory neurons to the bladder (13,19). The afferent pathways for these effects could be shown to originate from the pudendal nerves.

POSTERIOR TIBIAL OR COMMON PERONEAL

Another interesting application of electrical stimulation for inhibition of detrusor activity is the transcutaneous stimulation of the posterior tibial or common peroneal nerve. This technique, drawn from traditional Chinese medicine, is based on the acupuncture points for inhibition of bladder activity and was reported by McGuire et al. in 1983 (20).

A percutaneous tibial nerve stimulation (PTNS) (Urgent PC, CystoMedix, Anoka, MN) was approved by the Food and Drug Administration in 2000. A needle is inserted ~5 cm cephalad from the medial malleolus and just posterior to the margin of the tibia. Stimulation is done using a self-adhesive surface stimulation electrode without an implanted needle electrode (21). Current data describe results after an initial treatment period of 10–12 weeks. If patients get a good response, they are offered tapered chronic treatment. As in sacral root neuromodulation, PTNS seems less effective for treating chronic pelvic pain (22).

More substantial data, in particular on objective parameters and long-term follow up, are needed, as are studies looking into the underlying neurophysiological mechanisms of this treatment modality. Although minimally invasive, easily applicable, and well tolerated, the main disadvantage of PTNS seems to be the necessity of chronic treatment. The development of an implantable subcutaneous stimulation device might ameliorate this problem (23). It has never found widespread acceptance.

PELVIC NERVE STIMULATION

Pelvic nerves do not tolerate chronic stimulation and the pudendal nerves are activated, increasing outflow resistance. Also, in humans the fibers of the parasympathetic nervous system innervating the bladder split early in the pelvis, forming a broad plexus unsuitable for electrode application (24).

DETRUSOR STIMULATION

Direct detrusor stimulation offers high specificity to the target organ (25), but its disadvantages are electrode displacement and malfunction due to bladder movement during voiding, and fibrosis (even erosion) of the bladder wall. In 1967, Hald et al. (26) reported their experience of direct detrusor stimulation with a radio-linked stimulator in four patients, three with upper motor-neuron lesions and one with a lower motor-neuron lesion. The receiver was placed in a paraumbilical subcutaneous pocket. Two wires from the receiver were passed subcutaneously to the ventral bladder wall, where they were implanted. A small portable external transmitter generated the necessary energy. The procedure worked in three patients; in one it failed because of technical problems (13).

SPINAL CORD STIMULATION

The first attempt to achieve micturition via spinal cord stimulation was through the exploration of the possibility of direct electrical activation of the micturition center in the sacral segments of the conus medullaris. This was conducted by Nashold, Friedman, and associates, and had reported that the region for optimal stimulation was S1–S3.

Effectiveness was determined not only by location, but also by frequency. In two subsequent experiments, the same group compared the stimulation of the dorsal surface of the spinal cord at LS, S1, and S2 with depth stimulation (2–3 mm) at S1 and S2 in acute and chronic settings (27). It was only through the latter, the depth stimulation, that voiding was produced: High bladder pressures were achieved by surface stimulation, but external sphincter relaxation did not occur, and was noted only after direct application of the stimulus to the micturition center in the spinal cord. Stimulation between L5 and S1 produced pressure without voiding, even with depth stimulation (13).

Jonas et al. continued the investigation of direct spinal cord stimulation to achieve voiding (28–30). They compared 12 different types of electrodes: three surface (bipolar surface electrode, dorsal column electrode, and wraparound electrode) and nine depth electrodes. These differed in many parameters (e.g., bipolar–tripolar, horizontal–vertical–transverse). Regardless of the type of electrode, the detrusor response to stimulation was similar. Interestingly, the wrap-around surface electrode with the most extended current spread provoked the same results as the coaxial depth electrode with the least current spread, prompting those authors to theorize that current does not cross the midline of the spinal cord. Unfortunately, no real voiding was achieved. It was found that the stimulation of the spinal cord motor centers stimulates the urethral smooth and striated sphincteric elements simultaneously: The expected detrusor contraction resulted, but sphincteric contraction was associated. The sphincteric resistance was too high to allow voiding: It allowed only minimal voiding at the end of the stimulation, so-called poststimulus voiding (13). These results contrasted with the earlier work of Nashold and Friedman (27,31).

Thurhoff et al. (32) determined the existence of two nuclei, a parasympathetic and a pudendal nucleus. The parasympathetic nucleus could be shown within the pudendal nucleus; thus, at the level of the spinal cord, stimulation of the bladder separate to that of the sphincter is difficult.

SACRAL ROOT STIMULATION

Based on the hypothesis that different roots would carry different neuronal axons to different locations. The culmination of these studies led to the feasibility of sacral rootlet stimulation.

It appears that sacral nerve-root stimulation is the most attractive method since the space within the spinal column facilitates mechanically stable electrode positioning and the application of electrodes is relatively simple due to the long intraspinal course of the sacral roots.

The University of California, San Francisco (UCSF) group performed numerous experiments on a canine model (33), as the anatomy of bladder innervation of the dog is similar to that of the human. After laminectomy, the spinal roots were explored and stimulated, either intradurally or extradurally, but within the spinal canal, in the following modes:

1. Unilateral stimulation of the intact sacral root at various levels.
2. Simultaneous bilateral stimulation of the intact sacral root at various levels.
3. Stimulation of the intact ventral and dorsal root separately.
4. Stimulation of the proximal and distal ends of the divided sacral root.
5. Stimulation of the proximal and distal ends of the divided dorsal and ventral roots (13).

From these studies, it became clear that stimulating the intact root is least effective and stimulating the ventral component is most effective and that no difference exists between right- and left-root stimulation (33).

However, this stimulation also causes some sphincteric contraction, owing to the presence of both autonomic and somatic fibers in the ventral root, and the studies were continued with the addition of neurotomy to eliminate the afferent fibers. These experiments showed that, to achieve maximally specific detrusor stimulation, the dorsal component must be separated from the ventral component and the somatic fibers of the root must be isolated and selectively cut (34).

The experiments also demonstrated that stimulation with low frequency and low voltage can maintain adequate sphincteric activity, but that stimulation with high frequency and low voltage will fatigue the external sphincter and block its activity. When high frequency/low voltage stimulation is followed by high voltage stimulation, bladder contraction will be induced and voiding achieved.

The finding that detrusor contraction can be activated separately from sphincteric activity and that adequate sphincteric contraction can be sustained without exciting a detrusor reaction made it seem possible that a true bladder pacemaker could be achieved. In addition, in histological and electron microscopic examination of the stimulated sacral roots, no damage was found when they were compared with the contralateral nonstimulated roots. Neither the operation nor the chronic stimulation damaged the ventral root, and the responses remained reliable and stable (13).

Tanagho's group later performed detailed anatomical studies on human cadavers. The aim was to establish the exact anatomical distribution of the entire sacral plexus, following it from the sacral roots in the spinal cord through the sacral foramen inside the pelvic cavity. Emphasis was placed on the autonomic pelvic plexus as well as the somatic fibers. With this anatomical knowledge, the stimulation of human sacral roots in neurogenic bladder dysfunction was developed and made clinically applicable as a long-term treatment (35). Direct electrical stimulation was performed through a permanently implanted electrode, placed mostly in contact with S3 nerve roots in the sacral foramen, after deafferentation.

The stimulation of sacral rootlet bundles isolated from the rest of the sacral root gave the same increase of bladder pressure when stimulated close to the exit from the dura, in the mid-segment, or close to the origin in the spinal cord. This could make the stimulation more selective, eliminating detrusor-sphincter dyssynergia.

In additional work, taking advantage of the knowledge that high frequency current can block large somatic fibers, electrical blockade of undesired responses was tested to replace selective somatic neurotomies. High frequency sinusoidal stimulation was effective in blocking external sphincter activity. However, the sinusoidal waveform is not efficient. Alternate-phase, rectangular wave is more efficient and induces the same blockade: alternating pulses of high frequency and low amplitude followed by pulses of low frequency and high amplitude were effective in inducing low pressure voiding without the need for somatic neurotomies. This approach has not yet been tried clinically, but it might prove to be the answer to the problem of detrusor-sphincter dyssynergia in electrically stimulated voiding (13).

The three main devices used for sacral neuromodulation is the Medtronic InterStim, the Finetech–Brindley (VOCARE) bladder system, and the rf BION systems. Each is explained in detail below.

MEDTRONIC INTERSTIM

Indications for use: urge incontinence, retention and urgency frequency, male and female dysfunctional voiding syndromes and postprostatectomy incontinence. There are also benefits beyond voiding disorders, including re-establishment of pelvic floor awareness, resolution of pelvic floor muscle tension and pain, reduction in bladder pain (interstitial cystitis) and normalization of bowel function.

The basic concept behind the implantable pulse generator (IPG) that provides stimulation to the sacral nerve is not far removed from the concepts behind cardiac pacing. A long-lived battery encased in biocompatible material is programmed to deliver pulses of electricity to a specific region of the body through an electrode at the end of an encapsulated wire.

Medtronic is the manufacturer of the InterStim neurostimulator. Earl Bakken, the founder of the company, first created a wearable, battery-operated pacemaker at the request of Dr. C. Walton Lillehei, a pioneer in open-heart surgery at the University of Minnesota Medical School Hospital, who was treating young patients for heart block.

The Itrel I, the first-generation neurostimulator, was introduced in 1983. Current versions are used for the treatment of incontinence, pain, and movement disorders.

System Overview

There are two established methods for sacral root neuromodulation using the Medtronic InterStim system.

1. An initial test phase, then the more permanent hardware is implanted.
2. An alternative method uses a staged testing–implant procedure, where a chronic lead is implanted and connected to a percutaneous extension and test stimulator.

Testing Phase (See Fig. 1). The testing hardware consists of a needle, test lead, test stimulator, interconnect cabling and a ground pad (Fig. 1).

- Needle (see Figs. 2 and 3).

A 20-gauge foramen needle with a bevelled tip is used to gain access to the sacral nerve for placing the test stimulation lead. The stainless steel needle is depth-marked along its length and electrically insulated along its center length. The portion near the hub is exposed to allow connection to



Figure 1. Test stimulation system.

Figure 2. Model 041828 (20 gauge) 3.5 in. (88.9 mm) foramen needles.

Figure 3. Model 041829 (20 gauge) 5 in. (127 mm) foramen needles.

the test stimulator. By stimulating through the uninsulated tip of the needle, the physician can determine the correct SNS site for the test stimulation lead.

- Test lead (see Fig. 4).

The initial test lead is a peripheral nerve evaluation (PNE) test lead with a coiled, seven-stranded stainless steel wire coated with fluoropolymer. Its electrode is extended to 10 mm (0.4 in.) to increase the length of coverage and reduce the effects of minor migration. Depth indicators help to align the lead electrode with the needle tip. The lead contains its own stylet, which is removed once the correct position has been found, leaving the lead flexible and stretchable, to mitigate migration.

- Test stimulator (see Fig. 5).

The most current version of test stimulators is the model 3625. The model 3625 test stimulator can be used both for patient screening, where the patient is sent home with the device, and for intraoperative usage in determining lead placement thresholds. It provides output characteristics that are similar to those of the implantable neurostimulator and can be operated in either monopolar or bipolar modes. It is battery operated by a regular, 9 V battery. The physician sets the maximum and minimum amplitude settings, allowing the patient to control the amplitude (within those maximum and minimum settings) to whatever level is comfortable.

The safety features of the stimulator include; an automatic output shut-off occurs when the amplitude is turned up too rapidly (as when the control is inadvertently bumped), a loose device battery will cause output shutoff also to prevent intermittent stimulation and shock to the patient, and sensors, which detect when electrocautery is being used, shut the output off. Turning the test stimulator off for a minimum of 3 s can reset the protection circuitry.

- Interconnect cables (see Fig. 6).

Single-use electrical cables are used to hook the test stimulation lead to the model 3625 test stimulator during the test stimulation procedure in the physician's office and when the patient goes home for the evaluation period.

Figure 4. Model 3057 test stimulation lead.



Figure 5. Model 3625 sacral nerve test stimulator.

The patient cable is used to deliver acute stimulation during the test procedure. The insulated tin-plated copper cable has a 2 mm socket at one end and a spring-activated minihook at the other end. The minihook makes a sterile connection to the foramen needle, test stimulation lead, or implant lead. The socket end is connected to the test stimulator by a long screener cable, the latter being a two-wire cable with a single connector to the model 3625 test stimulator at one end; one of the wires is connected to the patient cable and the other to the ground pad. After the test stimulation, the patient cable is removed and a short screener cable is substituted for at-home use. This cable is connected to the ground pad and directly to the test lead. It is designed to withstand the rigours of home use and can be disconnected, to facilitate changing clothes (13).

- Ground pad.

The ground pad provides the positive polarity in the electrical circuit during the test stimulation and the at-home trial. It is made of silicone rubber and is adhered to the patient's skin. As described above, for the at-home trial a short screener cable is substituted for the long screener cable and connected directly to the lead.

Surgical Technique Used for Acute Testing Phase:. The aims of percutaneous neurostimulation testing (PNE) are to check the neural and functional integrity of the sacral nerves, to determine whether neurostimulation is beneficial for each particular patient, and to clarify which sacral spinal nerves must be stimulated to achieve the optimum therapeutic effect in each individual case.

Local anesthetic is injected into the subcutaneous fatty tissue and the muscles, but not into the sacral foramen itself. The S3 foramen is localized on one side with a 20-gauge foramen needle. By stimulating through the uninsulated tip of the needle, the physician can find the correct sacral nerve stimulation site for placement of the test stimulation lead. Once the location of the S3 foramen is established, tracing of the other foramina is done. The



Figure 6. Model 041831 patient cable.

portion near the hub is exposed to allow connection to the test stimulator.

Keeping the needle at a 60° angle to the skin surface with a rostrocaudal and slightly lateral pointing tip of the needle will ensure that the needle is inserted into the targeted foramen. The puncture should progress parallel to the course of the sacral nerve, which normally enters at the upper medial margin of the foramen. This method achieves optimal positioning of the needle for stimulation and avoids injuring the spinal nerve. The insulated needle (cathode) is then connected to an external, portable pulse generator (Medtronic model 3625 test stimulator) via a connection cable. The pulse generator itself is connected to a neutral electrode (anode) attached to the shoulder.

Because patient sensitivity varies, the voltage used is between 1–6 V, which starts at 1 and is increased in 20 Hz increments. Stimulation of the S3 evokes the "bellows" effect (contraction of the levator ani and the sphincter urethrea). Also, there is plantar flexion of the foot on the ipsilateral side. If plantar flexion of the entire foot is observed, the gastrocnemius muscle should be palpated, because a strong contraction usually indicates stimulation of S2 fibers and should be avoided.

Stimulation of S3 generally produces the most beneficial effect. Furthermore, most patients will not tolerate the permanent external rotation of the leg caused by stimulation of S2. Occasionally, stimulating S4 also causes clinical improvement. Stimulation of S4 provokes a strong contraction of the levator ani muscle, accompanied by a dragging sensation in the rectal region. If stimulating one side produces an inadequate response, the contralateral side should be tested; the aim is to obtain a typical painless stimulatory response.

Once the optimal stimulation site has been identified, the obturator is removed from the foramen needle, and a temporary wire test lead (Medtronic model 3057 test lead) is inserted through the lumen of the needle. Once the test lead has been inserted into the needle, the latter must not be advanced any further in order to avoid severing the lead. The needle is then carefully removed from the sacral foramen, leaving the test lead in place. The stimulation is then repeated to check the correct position of the test electrode. To mitigate migration the lead contains its own stylet, which is removed once the correct position has been found, leaving the lead flexible and stretchable.

A repetition of the test stimulation, confirming the correct position of the test lead, is therefore mandatory at this stage; otherwise the test lead cannot be reinserted.

After correct positioning, the test lead is coiled on the skin and fixed with adhesive transparent film. Finally, the correct position of the wire is radiologically confirmed and the portable external impulse generator is connected.

Percutaneous Extension Hardware (see Fig. 7). If acute testing is inconclusive, or when there is a need for positive fixation of the test lead, percutaneous extension hardware is the best method used. Also called the staged implant, it is an alternative method for patient screening.

The chronic lead is implanted in the normal manner and is connected to a percutaneous extension (model 3550-05). The extension is designed to provide a connection between the chronic lead and the external test stimulator. Positive contact is made using four set screws; the connection is sealed with a silicone boot that covers the set screws. The percutaneous extension, which is intended for temporary use, features four insulated wires, wound together and sized for a small incision, so that they can be brought through the skin. The percutaneous extension is then connected to the screener cable, as described above (13).



Figure 7. Percutaneous extension system.

Chronic System. The chronic system consists of an implantable neurostimulator, a lead, an extension, a physician programmer and a patient programmer.

- Neurostimulator (see Fig. 8).

The implantable neurostimulator (Medtronic model 3023) weighs ~42 g and has a volume of 22 cm^3. It comprises ~70% battery and 30% electronics. The physician has unlimited access to programmable parameters such as amplitude, frequency, and pulse width. Each parameter can be changed by means of an external, physician programmer that establishes a rf link with the implanted device. A patient programmer provides limited access to allow the patient to turn the neurostimulator on and off, or to change amplitude within a range established by the physician (via the physician programmer) (13).

The external titanium container of the neurostimulator may be used in either a monopolar configuration (lead negative, can positive) or a bipolar configuration, which will result in marginally better longevity. The life of the neurostimulators is usually ~7–10 years. Factors that affect this are the mode, programming of the amplitude, pulse width and frequency, and the use of more than one active electrode.

- Implantable lead system (see Fig. 9–14).

Figure 8. Model 3023 implantable neurostimulator.



Figure 9. Model 3080 lead.



Figure 10. Model 3092 lead.



Figure 11. Model 3093 lead.



Figure 12. Model 3886 lead.



Figure 13. Model 3889 lead.



Figure 14. Model 3966 lead.

The lead is a quadripolar design, with four separate electrodes that can be individually programmed to plus, minus, or off. This allows the physician to optimize the electrode configuration for each patient and to change programming, without additional surgery, at a later date, to adapt to minor lead migration or changing disease states. The electrode sizes, spacing, and configurations have been designed specifically for SNS.

The lead is supplied with multiple stylets and anchors, to accommodate physician preferences. A stylet (straight or bent) is inserted into the lumen of the lead to provide extra stiffness during implant. Two different degrees of stiffness provide the physician with options to tailor the handling and steering properties of the lead, as preferred. The stylet must be removed before connection with the mating component.

The physician also has a choice of anchors, which allow fixation of the lead to stable tissue to prevent dislodging of the lead after implantation. Three anchor configurations are available: a silicone rubber anchor fixed in place on the lead has wings, holes and grooves to facilitate suturing; a second type, also made of silicone, slides into place anywhere along the lead body, and must be sutured to the lead to hold it in place; a new plastic anchor is also available, which can be locked in place anywhere along the lead body without a suture to the lead.

- Quadripolar extension (see Fig. 15).



Figure 15. Series 3095 extension.



Figure 16. Physician programmer.

The quadripolar extension, which is available in varying lengths to facilitate flexibility in IPG placement, is designed to provide a sealed connection to the lead. This extension provides the interface with the neurostimulator. Positive contact is made with four set screws, and the connection is sealed with a silicone boot covering the screws.

- Physician programmer (Fig. 16).

The console programmer (Medtronic model 8840 N'Vision) is a microprocessor-based system that the physician uses to program the implanted neurostimulator noninvasively. The programmer uses an application-specific memory module, installed by means of a plug-in software module.

- Patient programmer (Fig. 17).

The patient programmer also communicates with the implanted neurostimulator by an rf link. The patient can adjust stimulation parameters within the range set by the physician. This range is intended to allow the patient to turn the device on or off, and to change amplitude for comfort (as during postural changes), without returning to the physician's office.

Surgical Technique Used for Chronic Implantable System. The sacral foramen electrode and impulse generator are implanted under general anesthesia. Long-acting muscle relaxants must not be used, as these would impair the intraoperative electrostimulation.

The patient is placed in the prone position with a 45° flexion of the hip and knee joints. An 8 cm long midline



Figure 17. Patient programmer.

incision is made above the sacrum, reaching one-third caudal and two-thirds cranial from the S3 foramen. After transection of the subcutaneous fat, the muscle fascia (thoracolumbar fascia) is incised approximately 1 cm lateral of the midline in a longitudinal direction.

Usually, the Gluteus maximus has to be incised over a length of 1–2 cm for good exposure of the S3 foramen and a little further caudal if implantation of the S4 foramen is intended. The paraspinal muscles are then divided longitudinally and the dorsal aspect of the sacrum is exposed.

Intraoperative test stimulation, using the same equipment as for the acute testing phase, will confirm the precise location of the foramen selected. The foramen needle is left in place to avoid relocalisation of the foramen while preparing the permanent electrode for implantation. Proximal to the four contact points of the permanent electrode, a silicon rubber cuff is glued to the electrode body. The cuff is fitted with three eyelets to accommodate nonabsorbable atraumatic needle-armed sutures.

After removal of the foramen needle, the permanent electrode (Medtronic quadripolar lead, model 3080) is gently inserted into the foramen. Renewed test stimulation will determine the most effective contact point between the electrode and spinal nerve; the most distal contact point is termed “0”, with the subsequent three being numbered 1–3 sequentially. An identical motor response at all four contact points is ideal. If only one contact gives a satisfactory response, the electrode should be repositioned at a different angle to the foramen and the test stimulation repeated. The preattached sutures are then used to secure the electrode to the ligaments overlying the periosteum of the sacral bone. Test stimulation should be repeated at this stage to confirm an appropriate position of the electrode after fixation.

A small skin incision is now made in the flank between the iliac crest and the 12th rib on the side where the electrode has been placed. A subcutaneous tunnel is formed between the two wounds, starting from the flank incision and running toward the sacral incision.

The obturator of the tunneling device is removed and the silicone sheath, which is open at both ends, left in place. The free end of the electrode is guided through the sheath to the flank incision, after the stylet has been removed from the electrode.

The silicone sheath is now removed from the flank incision, the proximal end of the electrode is marked with a suture, and the electrode is buried in a subcutaneous pocket that has been created at the site of the flank incision. The flank incision is temporarily closed, leaving the marking suture exposed between the skin sutures. The sacral incision is then closed in layers and covered with a sterile dressing.

The patient is now positioned on the contralateral flank. The flank and abdomen on the side chosen previously for placement of the Medtronic InterStim model 3023 implantable pulse generator are disinfected and the surgical field is draped with a sterile cover. The flank incision is now reopened, and a subcutaneous tunnel is again created between the flank incision and the subcutaneous pocket in the lower abdomen through which a connecting extension cable (Medtronic quadripolar extension, model 3095) between electrode and impulse generator is guided.

Once the electrode has been connected to the extension cable in the area of the flank incision, the contact point is sealed with a silicone cover, fixed with two sutures and placed subcutaneously. The flank incision is closed in layers and covered with a sterile dressing.

Finally, the other end of the connecting cable is attached to the impulse generator. The generator is attached to the rectus fascia using two nonabsorbable sutures. The abdominal incision is closed in two layers and covered with sterile dressings.

On the first postoperative day, anterior–posterior and lateral radiographs of the implant are obtained to verify that all components are correctly positioned and will act as a control for comparison in case of subsequent problems.

Modifications of the surgical procedure include placement of the pulse generator in the gluteal area thus avoiding repositioning of the patient during the procedure and implantation of bilateral electrodes, which should be powered by a two-channel pulse generator (Medtronic Synergy, model 7427) for adequate synchronous independent stimulation of each side. The implant remains deactivated at least until the day following surgery and will be activated by a telemetric programming unit (Medtronic Console Programmer, model 7432) allowing programming of all features of the implant by the physician during the initial activation and follow-up stages.

NEW MEDTRONIC TINED LEAD PERCUTANEOUS IMPLANT (SEE FIGS. 18 AND 19)

Tined leads offer sacral nerve stimulation through a minimally invasive implant procedure. The use of local anesthesia allows for patient sensory response during the implant procedure. This response helps ensure optimal lead placement and may result in better patient outcomes. With previous lead designs, many physicians used general anesthesia, which did not allow for patient sensory response.



Figure 18. Tined lead percutaneous implant.

Among the advantages of the minimally invasive implant procedure are the radiopaque markers to identify where tines are deployed, helping physicians in identifying the exact lead location relative to the sacrum and nerves. Tactile markers indicate lead deployment, and a white marker bands on the lead and tactile markers aid in proper lead placement and to notify the physician when the tines are ready to be deployed.

Percutaneous lead placement allows use of local anesthesia. This reduces the risks of general anesthesia and surgical incision and may facilitate faster patient recovery time as a result of less muscle trauma and a minimized surgical incision. Also, it may reduce surgical time as a result of a sutureless anchoring procedure and reduced number of surgical steps.

To date, a positive response to the PNE test has been the only predictive factor for the long-term efficacy of sacral nerve stimulation therapy. Current studies show that up to 40% of patients who experience improvement in symptoms during PNE test stimulation with a temporary lead do not have this improvement carried through after neurostimulator implantation (36). A study by Spinelli et al. looked at patients who underwent tined lead implant without PNE testing, and reported a positive outcome of 80% during the screening phase, which was maintained at an average follow up of 11 months, resulting in a higher success rate than that currently reported in the literature (37).

The development of the new tined lead allows fully percutaneous implantation of the permanent lead and offers the possibility of a longer and more reliable screening period than that possible with the PNE test. The advantage for patient screening are that the permanent tined lead is less prone to migration, hence if the results of screening are positive, the lead is already in the precise place where positive results were obtained, and there is a decrease in false-positive and false-negative results after screening (37). However, use (or lack thereof) of PNE testing in conjunction with the tined lead differs from center to center, depending on fiscal and/or other reasons.



Figure 19. Tined lead percutaneous implant.



Figure 20. The foramen needle stylet and directional guide.

The tined lead models 3093 and 3889 are designed to work with the current lead introducer model 355018 or 042294.

Surgical Technique for Tined Lead Implant. The foramen needle is inserted and tested for nerve response. The foramen needle stylet is then removed and replaced with the directional guide (see Fig. 20). The foramen needle itself is then removed.

A small incision is made on either side of the directional guide, which is followed by fitting the dilator and the introducer sheath over the directional guide and advanced into the foramen (see Fig. 21). The guide and the dilator are then removed, leaving the introducer sheath in place.

The lead is then inserted into the introducer sheath and advanced until visual marker band C on the lead lines up with the top of the introducer sheath handle. Using fluoroscopy, electrode 0 of the lead is confirmed to be proximal to the radiopaque marker band at the distal tip of the sheath (see Fig. 22).

While holding the lead in place, the introducer sheath is retracted until visual marker band D on the lead lines up with the introducer sheath handle. Using fluoroscopy, radiopaque marker band at the tip of the sheath is



Figure 21. Fitting the dilator and introducer sheath.



Figure 22. Confirming lead proximal to radiopaque marker band.

confirmed to be proximal to electrode 3 and adjacent to radiopaque marker band A on the lead (see Fig. 23).

Test stimulation of the various electrodes (0, 1, 2, 3) is done and the responses are observed. If necessary, the lead is repositioned within the foramen. When the lead is in the proper position, the lead is held in place and the introducer sheath and lead stylet are carefully withdrawn, thereby deploying the tines and anchoring the lead.

FINETECH–BRINDLEY (VOCARE) BLADDER SYSTEM

Introduction (see Fig. 24)

Indications for use: The VOCARE bladder system is indicated for the treatment of patients who have clinically complete spinal cord lesions with intact parasympathetic innervation of the bladder and are skeletally mature and neurologically stable. However, patients with other neurological disorders, including multiple scleroses, spinal cord tumours, transverse myelitis, cerebral palsy and meningomyelocele, have also benefited from the implant(38). *A secondary use of the device is to aid in bowel evacuation and promote penile erection*.

The sacral anterior root stimulation (SARS) system was developed by Brindley with the support of the Medical Research Council (Welwyn Garden City, Herts, UK), is manufactured by Finetech Medical Ltd. in England, and is marketed as the Vocare system by NeuroControl Corporation (Cleveland, OH) (1).



Figure 23. Confirming marker band proximal to electrode 3.

Beginning in 1969, Brindley developed a new device to stimulate sacral roots at the level of the cauda equina. This technique, first tested in baboons, led to the development of a stimulator that was first successfully implanted in a patient in 1978 (39).

Hardware

The Finetech–Brindley bladder controller is composed of external and internal equipment.

1. External (see Fig. 25):

   One analog and three digital versions of the external controller are available in different countries (1). This device has no batteries but is powered and controlled by rf transmission from a portable external controller operated by the user and programmed by the clinician. It consists of a transmitter block connected to the control box via a transmitter lead. The patient holds the transmitter over the implanted receiver to apply stimulation. A new, smaller control box that is more powerful will be available in the coming months (39).
2. Internal (see Fig. 26):

   The internal equipment consists of three main parts: (1) the electrodes, (2) the cables, (3) and the receiver block.

   Two types of electrodes are used, depending on the approach (intra- or extradural).

   For intradural implantation the electrode mounts in which the anterior sacral roots are trapped are called "books" because of their shape.

   The two-channel implant has an upper book with only 1 slot. Trapping of S3 and S4 roots is often sufficient to obtain bladder contractions. In males, S2 roots were trapped in the upper book and S3 and S4 roots, in the lower book.

   The three-channel implant is composed of two electrode books. The upper book contains three parallel slots for S3 and S2 roots and the lower contains one slot for S4 roots. There are three electrodes in each slot (one cathode in the center and two anodes at the two ends) to avoid stimulation of unwanted structures.

   The four-channel implant has two books like those of the three- channel implant, and the four slots allow independent stimulation of four sets of nerve fibers. It is used in patients who retained sacral-segment pain sensitivity.

   The special eight-channel implant allowed the stimulation of four anterior roots and the destruction of any of the four posterior roots, if necessary, after implantation. It is no longer used.

   For extradural implantation the cables end with three helical electrodes (a cathode between two anodes) and are attached to the roots with a strip of Dacron-reinforced silicone rubber. The cables used


(C) The External Transmitter sends the signal across the skin of the abdomen to a pacemaker-like implantable Receiver-Stimulator.
(D) The VOCARE Bladder System sends electrical signals through Electrodes to the spinal nerves that lead to the bladder. Theses signals cause the muscles of the bladder and urethral sphineter to contract. After the bladder has contracted in response to the electrical stimulus, the sphincter muscles relax allowing the bladder to empty.
Spinal Column
(B) Command signals and power are sent to the External Transmitter which is held against the skin
Sacral Nerves
Bladder
Nerve Plexus
Urethra
Sphincter
Bowel
(A) The VOCARE Bladder System features an External Controller. This unit transmits a signal to the External Transmitter.

Figure 24. VOCARE bladder system.


1
2
3
0
SAR Stimulator
NeuroControl
a
FINETECH-BRINDLEY BLADDER CONTROLLER
d
c
b

Figure 25. External equipment. (a) New control box. (b) Original control box. (c) Transmitter lead. (d) Transmitter block.


Extradural Electrode and Cable Assembly
Intradural Electrode and Cable Assembly
2 and 3 Channel reciever blocks with plug connectora

Figure 26. Internal equipment.



Figure 27. Finetech–Brindley system.

are encapsulated in silicone rubber, and the wires are made of 90% platinum and 10% iridium and connect the electrodes to the radio receiver block. The radio receiver block, which contains two, three, or four radioreceivers imbedded in silicone rubber, is activated by pulse-modulated rf waves (39).

Surgical Technique for Finetech–Brindley System (see Fig. 27):. The surgical technique for ***intrathecal*** implantation developed by Brindley et al. (40) involves laminectomy of the fourth and fifth lumbar vertebrae and the first two pieces of the sacrum, exposing 10–12 cm of dura. The dura and arachnoid are opened at the midline to expose the roots. The roots are identified by their size and situation and by perioperative stimulation during the recording of bladder pressure and observation of skeletal muscle responses with the naked eye.

The S2 anterior roots contract the triceps surae, the glutei, and the biceps femoris. The S3 anterior roots innervate the pelvic floor and the toe flexors. The S4 anterior roots innervate the pelvic floor. The sphincters (anorectal and urethral) are innervated predominantly by S4 and also by S3 and S2. The detrusor response is always obtainable by stimulation of S3 and S4 and sometimes achievable by stimulation of S2.

The roots are split into the anterior and posterior components. The identity of the posterior root is confirmed by electrical stimulation and then a segment measuring ~20–40 mm in length is removed. When the S5 root has been identified, it is resected if no bladder response is obtained (39).

If a posterior rhizotomy is performed, stimulation can be applied to mixed sacral nerves in the sacral spinal canal extradurally, since the action potentials generated on the afferent axons do not reach the spinal cord. This has the advantage that the electrodes can be placed extradurally, reducing the risk of leakage of cerebrospinal fluid along the cables, and reducing the risk of breakage of the cables where they cross the dura. In addition, the extradural nerves are more robust than the intradural roots, being covered with epineurium derived from the dura, and require less dissection than the intradural roots; therefore, there is less risk of neuropraxia of the axons, which could otherwise lead to a delay in usage of the stimulator but not usually in permanent loss of function (1,41).

The benefits of a posterior rhizotomy include abolition of the neurogenic detrusor over activity, resulting in increased bladder capacity and compliance, reduced incontinence, and protection of the kidneys from ureteric reflux and hydronephrosis. The rhizotomy also reduces detrusor-sphincter dyssynergia, which improves urine flow, and prevents autonomic dysreflexia arising from distension or contraction of the bladder or bowel. In addition, a posterior rhizotomy improves implant-driven micturition. However, there are also drawbacks with a rhizotomy. They include abolition of reflex erection, reflex ejaculation, reflex defecation and sacral sensation, if present. Still, in many subjects with spinal lesions, these reflexes are not adequately functional, and function can be restored by other techniques (42).

The surgical technique for *extradural* implantation involves laminectomy of the first three pieces of the sacrum. It may also involve laminectomy of the L5 vertebra, depending on whether it is decided to implant electrodes on S2 roots (39). Extradural electrodes are used for patients in whom arachnoiditis makes separation of the sacral roots impossible. In some centers, however, extradural electrodes are used for all or nearly all patients.

After electrode implantation, the operation proceeded with closure of the dura, tunneling of the leads to a subcutaneous pocket in the flank, and closure of the skin. The patient is turned over and the leads are prepared for connection to the implantable stimulator.

At this time the leads are connected via an aseptic cable to an experimental stimulator. Prior to stimulation the bladder is filled with 200 mL saline using a transurethral filling catheter. The experimental stimulator consisted of two synchronized current sources with a common cathode. Pressure responses are elicited using pulse trains of 3–5 s duration; containing identical monophasic rectangular pulses delivered at a rate of 25 pulses $\cdot$ s^{-1}. Stimulation is usually limited to the S3 and S4 ventral roots since they contain most of the motoneurons innervating the lower urinary tract.

After 15–20 min of experimental stimulation the leads are disconnected from the stimulator and the normal procedure is resumed with implantation stimulator.

A two-channel transurethral pressure catheter is used to measure intravesical and intraurethral pressure. The urethral pressure sensor is positioned at the level of the external sphincter such that in response to suprathreshold stimulation a maximal pressure response is measured. Pressures are sampled at 8 Hz, displayed on a monitor, and stored in a portable data logger (43).

All patients are followed up according to a fixed protocol. Urodynamic measurements are taken at 2 days, 15 days, 4 months, and 1 year after surgery and every 2–3 years thereafter. Renal ultrasound examination is performed every year. Stimulation is performed for the first time



Figure 28. BION microstimulator.

between days 8 and 14, depending on the level of the spinal cord lesion (33).

PUDENDAL NERVE STIMULATION FOR THE TREATMENT OF THE OVERACTIVE BLADDER (rf BION) (SEE FIGS. 28 AND 29)

Indications for use: The rf Bion system is still relatively new, and though no clear, established indications have been set so far, its activity on the pudendal nerve and inhibition of the detruser muscle makes it ideal for overactive bladder disorders.

Electrical stimulation of the pudendal nerve has been demonstrated to inhibit detrusor activity and chronic electrical stimulation may provide effective treatment for overactive bladder disorders (44). The hurdle to date has been the technical challenge of placing and maintaining an electrode near the pudendal nerve in humans; however, recent development of the BION has made chronic implantation feasible.

The BION is a small, self-contained microstimulator that can be injected directly adjacent to the pudendal nerve (see Fig. 28). The ischial spine is an excellent marker for the pudendal nerve as it re-enters the pelvis through Alcock's canal. This is a very consistent anatomical landmark in both men and women. Also, the implanted electrode is protected in this area by both the sacral tuberous and sacrospinous ligaments. Stimulation in this area activates afferent innervation over up to three sacral segments. Efferent stimulation also provides direct activation of the external urethral sphincter, the external anal sphincter, and the levator ani muscles, which may be of some benefit in bladder control. The external components of this neural prosthesis include a coil that is worn around the subject's hips and a controller that is worn around the shoulder or waist.

The technique chosen to implant the device is that of the transperineal pudendal block. This approach is minimally invasive and is well established. A special implant tool was devised to facilitate placement. The BION implantation technique was developed in cadavers. The optimum insertion location is 1.5 cm medial to the ischeal tuberosity using a vaginal finger to guide the implant toward the ischial spine where electrical stimulation of the pudendal nerve may be confirmed (see Fig. 29).



Figure 29. Placement of BION system near pudendal nerve.

A percutaneous stimulation test (PST) was developed and proved to be a very effective way to assess acute changes in bladder volumes while stimulating the pudendal nerve. A baseline cystometrogram (CMG) was obtained followed by percutaneous pudendal nerve stimulation for 10 min with a repeat CMG.

The first implant was done on August 29, 2000. The BION was implanted under local anesthesia with intravenous sedation. Proper placement was verified by palpation and EMG activity. An intermittent stimulation mode of 5 s on 5 s off was used. Subjects returned 5–7 days later for activation, to distinguish between postoperative pain and potential stimulation pain. Subjects were followed up at 15, 30, and 45 days after activation. At each follow-up visit they underwent another cystometrogram and brought in a 72 h voiding diary. The results indicated a favorable response to maximum cystometric capacity throughout the study period. Diary entries verified improvement—incontinent episodes decreased by 65%, and both daytime and nighttime voids were decreased, as was pad use per day.

FUTURE DIRECTION OF THE THERAPY HARDWARE

The ongoing development of tools and hardware is driven by the desire to reduce the invasiveness of the implant and the likelihood of adverse events. Development efforts are concentrated on system components and tools that will allow implantation of the lead system through small incisions or percutaneous approaches. It is inevitable that the size of the neurostimulator will be reduced as future generations of the device are developed; more efficient power batteries and packaging will drive this aspect of development.

A rechargeable power battery may allow a smaller device. Although a smaller device would be welcomed, attaining this goal with a rechargeable battery is not seen as the best approach. A rechargeable neurostimulator would require the patient frequently to recharge the unit; this would inconvenience the patient and could reduce patient compliance. Additionally, a rechargeable battery would be more expensive than a nonrechargeable one owing to the technology required and the additional equipment necessary for recharging. Furthermore, this would not eliminate the need for periodic replacement of the neurostimulator every 5–10 years. System components will be optimized for the therapy, to reduce the time needed for management of both implant and patient. The incorporation of microprocessors and implementation of features such as a battery gauge will provide additional operational information while decreasing the time needed to manage the patient.

Physicians will be able to analyze system use, lead status, and other parameters. The addition of sensing technology may provide an opportunity to create a closed-loop system that captures data to optimize both diagnosis and functioning.

Bilateral stimulation may provide more efficacious therapy. There is considerable interest in this approach, and it seems to be a probable avenue of research in the near future. However, any use of bilateral stimulation would have to justify the larger neurostimulator, the extra lead system, and the additional costs associated with this approach; at present, there is no scientific experience to support this approach.

Apart from a reduction in the size of the implanted device, enhanced physician control is the most likely development to occur in the foreseeable future. Graphics-based programming and control will simplify device programming; it will allow more complex features to be incorporated in the neurostimulator without adding undue complexity to the physician programmer. Management of patient data files will become easier as additional data-management features are added to the programmer; the physician will be able to obtain a patient-programming history and other patient-management data. It is conceivable that, in the not-so-distant future, the physician may be able to access patient-device data over the Internet, thus making unnecessary some clinic visits and allowing for remote follow-up of patients who are on holiday or have moved house.

Future devices may allow software loading in a noninvasive manner, to upgrade the device long after implantation. Such capability could be used to provide new therapy algorithms as well as new therapy waveforms.

The future will also bring enhanced test stimulation devices, which will provide improved fixation during the test stimulation period. The development of new leads is one such focus with the aim of allowing a longer test stimulation period without lead migration.

The future application of SNS is dependent on new clinical research. Pelvic disorders, such as pelvic pain and sexual dysfunction, appear likely to be the First areas of investigation; sacral anterior root stimulation for spinal cord injury may also provide a worthwhile avenue of enquiry. The development of these applications—or of any other, for that matter—will potentially require new waveforms and the development of new therapy algorithms. The future is as open as the availability of resources and the application of science allow (45).

BIBLIOGRAPHY

Cited References

1. Jezernik S, Craggs M, Grill WM, et al.Electrical stimulation for the treatment of bladder dysfunction: current status and future possibilities. Neurol Res 2002;24(5):413–430.
2. Galvani L. De virfbus electricitatis in motu musculari, commentaffus. De Bononiensi Scientarium et Artium Instituto Atque Academia. 1791;7:363–418.
3. Volta A. Letter to Sir Joseph Banks, March 20, 1800. On electricity excited by the mere contact of conducting substances of different kinds. Philos Trans R Soc London (Biol) 1800;90:403–431.
4. Duchenne GBA. De I'dlectrisation localisde et de son application & la physiologie, & la pathologie et b la therapeutique. Paris; 1855.
5. Duchenne GBA. Physiologie des moumments demonstrde b I'aide de I'experimentation electrique et de l'observation clinique, et applicable b I'6tude des paralysies et des deformations. Paris; 1867.
6. Chaffee EL, Light RE. A method for remote control of electrical stimulation of the nervous system. Yale J Biol Med 1934;7:83.
7. Glenn WWL, Phelps ML. Diaphragm pacing by electrical stimulation of the phrenic nerve. Neutosurgery 1985; 17:974–1044.
8. Glenn WWL, Mauro A, Longo E, et al.Remote stimulation of the heart by radiofrequency transmission. N Engl J Med 1959;261:948.
9. House WF. Cochlear implants. Ann Otol Rhinol Laryngol 1976;85(27):1–93.
10. Saxtorph MH. Strictura urethrae—Fistula petinei—Retentio urinae. Clinisk Chirurgi. Copenhagen: Gyldendalske Fodag; 1878.
11. Katona F, Benyo L, Lang J. Uber intraluminare elektrotherapie vor verschiedenen paralytischen zustlinden des gastrointestinalen tractes mit quadrangularstrom. Zentralbl Chir 1959;84:929.
12. Matona F. Stages otvegetative afferentation in reorganization of bladder control during electrotherapy. Urol Int 1975;30:192–203.
13. Schlote N, Tanagho EA. Electrical Stimulation of the lower urinary tract: historical overview. In: Jonas U, Grunewald V, editors. New Perspectives in sacral nerve stimulation. Dunitz; 2002. p 1–8.
14. McGuire WE. Response of the neurogenic bladder to vadous electrical stimuli [dissertation]. Department of Surgery, Bowman Gray School of Medicine; 1955.
15. Boyce WH, Lathem JE, Hunt LD. Research related to the development ofan artificial electrical stimulator for the paralyzed human bladder: a review. J Urology 1964;91:41–51.
16. Bradley WE, Chou SN, French LA. Further experience with the radio transmitter receiver unit for the neurogenic bladder. J. Neurosurg 1963;20:953–960.
17. Caldwell KPS. The electrical control of sphincter incompetence. Lancet 1963;2:174.
18. Fall M, Erlandson BE, Carlsson CA, Lindstr6m S. The effect of intravagnal electrical stimulation on the feline urethra and urinary bladder. Scand) Urol Nephrol (Supp) 1977;44: 19–30.
19. Lindstrim S, Fall M, Carlsson CA, Edandson BE. The neurophysiologcal basisaf bladder inhlbition in response to intravaginal electrical stimulation. Urology 1983;129:405–410.
20. McGuire EL, ZIang SC, Horwinski ER, Lytton B. Treatment of motor and sensory detrusor instability by electical stimulation. J Urol 1983;129:78–79.
21. Govier FE, Litwiller S, Nitti V, Kreder KJ, Jr., Rosenblatt P. Percutaneous afferent neuromodulation for the refractory

overactive bladder: results of a multicenter study. J Urol 165:1193, 2001.

22. van Balken MR, Vandoninck V, Messelink BJ, Vergunst H, Heesakkers JP, Debruyne FM, et al. Percutaneious tibial nerve stimulation as neuromodulative treatment of chronic pelvic pain. Eur Urol; 43:158, 2003.
23. van Balken, Michael R, Vergunst Henk, Bemelmans Bart LH. The use of Electrical Devices for the Treatment of Bladder Dysfunction: A Review of Methods. Urol September 2004;172(3):846–851.
24. Ingersoll EH, Jones LL, Hegre ES. Effect on urinary bladder of unilateral stimulation of pelvic nerves in the dog. Am Physiol 1957;189:167.
25. Hald T, Agrawal O, Mantrowitz A. Studies in stimulation of the bladder and its motor nerves. Surgery 1966;60:848–856.
26. Hald T, Meier W, Khalili A, et al. Clinical experience with a radio-linked bladder stimulator. J Urol 1967;97:73–78.
27. Friedman H, Nashold BS, Senechat R. Spinal cord stimulation and bladder function in normal and paraplegic animals. J Neurosurg 1972;36:430–437.
28. Jonas U, Heine JR, Tanagho EA. Studies on the feasibility of urinary bladder evacuation by direct spinal cord stimulation. 1. Parameters of most effective stimulation. Invest Urol 1975;13:142–150.
29. Jonas U, James LW, Tanagho EA. Spinal cord stimulation versus detrusor stimulation. A comparative study in six acute dogs. Invest Urol 1975;13:171–174.
30. Jonas U, Tanagho EA. Studies on the feasibility of urinary bladder evacuation by direct spinal cord stimulation. II. Poststimulus voiding: a way to overcome outflow resistance. Invest Urol 1975;13:151–153.
31. Nashold BS, Friedman H, Boyarsky S. Electrical activation of micturition by spinal cord stimulation. J Surg Res 1971;11:144–147.
32. Thirhoff JW, Bazeed MA, Schmidt RA, et al. Regional topography of spinal cord neurons innervating pelvic floor muscles and bladder neck in the dog: a study by combined horseradish peroxidase histochemistry and autoradiography. Utol Int 1982;37:110–120.
33. Tanagho EA, Schmidt RA. Bladder pacemaker: scientific basis and clinical future. Urology 1982;20:614–619.
34. Schmidt RA, Bruschini H, Tanagho EA. Sacral root stimulation in controlled micturition: peripheral somatic neurotomy and stimulated voiding. Invest Urol 1979;17:130–134.
35. Probst M, Piechota HA, Hohenfeliner M, et al.Neurostimulation for bladder evacuation: is sacral root stimulation a substitute for microstimulation? Br J Urol 1997;79:554–566.
36. Bosch JLHR, Groen J. Sacral nerve neuromodulation in the treatment of patients with refractory motor urge incontinence: long-term results of a prospective longitudinal study. J Urol 2000;163:1219.
37. Spinelli M, Giardiello G, Gerber M, Arduini A, Van Den Hombergh U, Malaguti S. New Sacral Neuromodulation Lead For Percutaneous Implantation Using Local Anesthesia: Description And First Experience. J Urol 2003;170(5): 1905–1907.
38. Brindley GS. The first 500 patients with sacral anterior root stimulator implants: general description. Paraplegia 1994; 32:795–805.
39. Egon G, Barat M, Colombel P, et al.Implantation of anterior sacral root stimulators combined with posterior sacral rhizotomy in spinal injury patients. World J Urol 1998;16:342–349.
40. Brindley GS, Polkey CE, Ruston DN. Sacral anterior root stimulators of bladder control in paraplegia. Paraplegia 1982;28:365–381.
41. Brindley GS, Polkey CE, Rushton DN, Cardozo L. Sacral anterior root stimulators for bladder control in paraplegia: The first 50 cases. J Neurol Neurosurg Psychiat 1986;49: 1104–1114.
42. Rijkhoff N. Neuroprostheses to treat neurogenic bladder dysfunction: current status and future perspectives. Childs Nerv Syst 2004 Feb; 20(2): 75–86.
43. Rijkhoff N, Wijkstra H, Kerrebroeck P, et al.Selective detrusor activation by sacral ventral nerve-root stimulation: results of intraoperative testing in humans during implantation of a Finetech-Brindley system. World J Urol 1998;16: 337–341.
44. Vodus¢ek DB, Light KJ, Libby JM. Detrusor inhibition induced by stimulation of pudendal nerve afferents. Neurourol Urodyn 1986;5:381.
45. Gerber M, Swoyer J, Tronnes C. Hardware: development and function. New Perspectives in sacral nerve stimulation. In: Jonas U, Grunewald V, editors. Dunitz: 2002. p 81–88.

See also BIOTELEMETRY; FUNCTIONAL ELECTRICAL STIMULATION; TRANSCUTANEOUS ELECTRICAL NERVE STIMULATION (TENS).

BLIND AND VISUALLY IMPAIRED, ASSISTIVE TECHNOLOGY FOR

Andrew Y. J. Szeto
San Diego State University
San Diego, California

INTRODUCTION

Severe visual impairment represents one of the most serious sensory deficits that a human being can have. When this sensory input channel is so impaired that little useful information can pass through it, assistive devices that utilize alternative sensory input channels are often necessary. Familiar examples include the use of Braille and the white cane, respectively, for reading and obstacle avoidance by persons who are blind. Both of these assistive devices provide environmental information to the user via the sense of touch. Other assistive devices provide environmental feedback via the sense of hearing.

In the material that follows, examples of available assistive technology and promising new assistive technology under development for persons who are blind or severely visually impaired are presented. This article begins with an overview of the prevalence and impairments associated with blindness impairments and follows with an examination of reading aids, independent living aids, and mobility aids. The article concludes with a brief look at kinds of assistive technology likely to be available in the near future for persons with severe visual impairments.

The term blindness has many connotations and is difficult to define precisely. To many people, blindness refers to the complete loss of vision with no perception of light. The U.S. government, however, defines blindness as the best corrected visual acuity of 20/200 or worse in the better seeing eye. The acuity designation 20/200 means that a vision impaired person is able to see at a distance of 20 ft (6.09 m) what a person with normal visual acuity is able see at 200 ft (60.96 m). Low vision is defined as the

Table 1. Prevalence of Blindness and Low Vision Among Adults 40 Years and Older in the United States[a]

	Blindness		Low Vision		All Vision Impaired	
Age, Years	Persons	%	Persons	%	Persons	%
40–49	51,000	0.1	80,000	0.2	131,000	0.3
50–59	45,000	0.1	102,000	0.3	147,000	0.4
60–69	59,000	0.3	176,000	0.9	235,000	1.2
70–79	134,000	0.8	471,000	3.0	605,000	3.8
>80	648,000	7.0	1,532,000	16.7	2,180,000	23.7
Total	*937,000*	*0.8*	*2,361,000*	*2.0*	*3,298,000*	*2.7*

[a] Abstracted from Ref. 3 Arch. Ophthalmol. Vol. 122, April 2004.

best corrected visual acuity that is worse than 20/40 in the better seeing eye. People with extreme tunnel vision (a visual field that subtends an angle $>20^\circ$ regardless of the acuity within that visual angle) also are classified as being legally blind and thus qualify for certain disability benefits.

It is important to realize that a great majority ($\sim$70–80%) of people with severe impairments has some degree of usable vision (1,2). The severity of vision loss can vary widely and result in equally varying degrees of functional impairment. Although the degree of impairment may differ from one person to another, people who are blind or have low vision experience the common frustration of not being to see well enough to perform common everyday tasks.

The prevalence of blindness and low vision among adults 40 years and older is given in Table 1. According to the National Eye Institute (2), a component of the National Institutes of Health in the United States Department of Health and Human Services, the leading causes of vision impairment and blindness are primarily age-related eye diseases. These include age-related macular degeneration, cataract, diabetic retinopathy, and glaucoma. The 2000 census data revealed >5 million people of all ages in America have visual impairments severe enough to significantly interfere with their daily activities.

CONSEQUENCES OF SEVERE VISUAL IMPAIRMENTS

The two major difficulties faced by persons who are blind or severely visually impaired are access to reading material and independent travel or mobility. Simple-to-sophisticated technology has been used in a variety of assistive devices to help overcome these problems. The term reading is used in this context to include access to all material printed on paper or electronically. Reading material can include text, pictures, drawing, tables, maps, food labels, signs, mathematical equations, and graphical symbols. Safe and independent mobility is used to encompass both obstacle avoidance and navigation. For safe and independent mobility, the first concern is avoiding obstacles, such as curbs, chairs, low hanging branches, and platform drop-offs. After the sight impaired traveler has gained an awareness of the basic spatial relationships between objects within the travel environment, their needs wayfinding or navigational assistance, which involves knowing one's position, one's heading with respect to the intended destination, and a suitable path to reach it.

LOW VISION READING AIDS

People with low vision significantly out number those who are totally without sight (Table 1). Hence, the consumer market for low vision aids is much larger than the one dedicated to people with zero vision. The technology used in low vision aids is rather straightforward and the technologically used is relatively mature. Hence, only a brief overview of such assistive devices will be presented before discussing the more challenging issues faced by persons with zero useful vision. For readers desiring detailed product information about low vision aids, a search of the Internet using the term low vision aids will yield a bounty of pictures, product specifications, and purchasing information.

All low vision aids aim to maximize an individual's residual vision to its fullest. Low vision aids can be categorized as optical, nonoptical, and electronic. Optical aids include handheld magnifying glasses, telescopes mounted on eyeglass frames, and even microscope lenses. Nonoptical aids include enlarged high contrast print and high intensity lamps.

Electronic low vision aids represent the highest level in terms of cost, complexity, and performance. They include electronic video magnifiers that project printed material on a closed circuit monitor, regular television, or computer screen. Electronic video magnifiers can maximize readability of the written material by providing a wide range of magnification, brightness, contrast, type of fonts, and foreground and background colors. A good example of a modern closed circuit TV type of electronic low vision aid is the Optelec Traveller (Fig. 1). This portable video



Figure 1. This portable video magnifier has a built-in 6 in. (15.24 cm) color screen and can magnify text and pictures up to 16 times. (Courtesy of Optelec International, New York.)



Figure 2. Closed-circuit television with computer based text-to-speech output, a talking computer.

magnifier has a built-in 6 in. (15.24 cm) color screen and can magnify text and pictures up to 16 times and more if its video signal is sent to a television set.

People with tunnel vision or central blind spots due to macular degeneration often find it difficult and tiring to read an entire computer screen. For such individuals, the advent of the talking computer (Fig. 2) represented a major technological breakthrough. The capability and flexibility of such a computer or reading machine addressed many of their needs as well as the needs of persons without any useful vision.

READINGS AIDS FOR THE BLIND

For persons with essentially zero useful vision, the tactile sense has been utilized as an alternative sensory input channel for reading. One of the oldest reading substitutes for the blind is Braille, a six dot matrix code that Louise Braille adapted in 1824 for use by blind persons to read written text. The standard Braille cell consists of two columns and three rows of dots separated by 2.3 mm with 4.1 mm separating adjacent cells. Each Braille cell occupies a rectangular area of 4.3×8.6 mm and can represent 2^6-1 (or 63) possible symbols within that areas. Grade I Braille maps each cell a one-to-one basis to each letter of the alphabet, basic punctuation marks, and simple abbreviations so that Grade I Braille has an informational density of approximately 1 bit per 6 mm^2 of surface area. For greater informational compactness and faster reading rates, Grade II Braille uses combinations of dots to represent contractions, frequently used words, prefixes, and suffices. Grade III Braille is even more compact and affords the highest reading rates, but very few people ever master it. The largest proportion of Braille literature is produced at the Grade II level, which can be read at up to 200 words per minute (4) by those proficient in Braille. Braille is a unique reading aid that not only gives blind persons access to printed material but also provides them with a writing medium.

Despite Braille's unique place as a complete writing system that is spatially distributed and retains many advantages of a printed page, Braille is a specialized code that only a small percentage of blind individuals learn to use. This is especially true for persons who become blind after the age of 15 years. Given the difficulty of mastering Braille, the lack of up-to-date Braille printed material, and advances in alternate technologies such as electronic reading machines, many blind individuals choose to not bother with Braille.



Figure 3. Portable refreshable Braille reader that can playback or store messages using a cassette recorder. The reader has a single-line tactile display, a Braille keyboard, and a tape cassette for data storage and recall. (Picture taken from Fig. 2.8 of Ref. 5.)

Other disadvantages of Braille printed material include the cost to produce it, store it, and maintain it. Embossable Braille paper is not only bulky, heavy, and expensive, the pattern of raised dots (laboriously and noisily impressed into the paper) is fragile and short lived. Assistive technologies such as portable Braille readers (Fig. 3) have mitigated some of the inconveniences associated with Braille (5), but these electronic Braille readers–recorders often do not display the two-dimensional (2D) information embedded in graphs, tables, and mathematical formulas. The single and dual line tactile displays found in most portable readers also makes the rapid search for content via headings very difficult.

Refreshable Braille readers can be used as a computer interface for accessing information on the computer screen. Some full-sized electronic Braille displays are 80 cells long and cost upward of $10,000. The dots in these transient Braille displays are produced by pins raised and lowered (refreshed) to form Braille characters. Refreshable Braille readers allow users to access any portion of the screen information via specialized control buttons and status Braille cells. Tactually distinguishable arrow keys offer screen cursor control while extra status cells provide additional information about text-attributes or line and colon positions.

Refreshable Braille displays are especially useful for deaf blind individuals and users working with computer programming languages. For example, the Braille Voyager 44 (Fig. 4), made by F.J. Tieman BV, has a 44 cell Braille display, and 5 thumb keys for screen navigation. Using its built-in macro program, USB connection, and any screen reader, the Voyager enables a user to access many features of the Windows operating system.



Figure 4. The Braille Voyager 44 made by Manufacturer: F.J. Tieman BV. It has a 44 cell Braille display and 5 navigation keys.

Despite Braille's many drawbacks and limited popularity, its long history, status as the only complete writing and reading system for the blind, and tenacity of advocates like the American Federation for the Blind combine to keep Braille viable as an informational medium. Nonprofit groups like the Braille Institute produce millions of pages of Braille each year for business, schools, government agencies and individuals across the nation. They sell recreational reading material in Braille to both children and adults and provide low cost transcription, embossing, and tactile graphic services.

For the majority of blind persons who do not know Braille, reading material converted into the audio format (aka talking books) and played back on variable speed tape recorders have proven to be popular and convenient to use. To overcome spoken speech's inherently slower reading rate, variable speed tape recorders with special electronic circuits that compensate for the pitch change during high speed playback (1.5–3 times normal speed) can be used. Obtaining reading material in audio form for playback on such recorders also has become more convenient as vendors make downloading of electronic text and audio files available to their subscribers (6).

Although audio books are popular for persons with severe visual impairments, this approach does not work for reading the newspaper, daily mail, memoranda, cookbooks, technical reports, handwritten notes, and common everyday correspondence, such as utility bills and bank statements. Before the advent of a reading machine, which has now become part of a general purpose talking computer, persons with no useful vision relied on human readers with its attendant inconvenience, loss of independence, and lack of privacy.

For severely sight impaired individuals and even those who know Braille, the power, convenience, and versatility of a reading machine, also known as a talking computer, have made it the preferred method of accessing most reading material. First marketed in the early 1980s, reading machines of today are affordable, compact, and can reliably and rapidly convert alphanumeric text into synthetic speech. In addition to a synthetic voice that reads aloud the actual text, the talking computer or reading machine also provides auditory feedback of cursor location and navigational commands.

A talking computer or dedicated reading machine contains artificial intelligence that converts alphanumeric text into spoken speech. The multistep process begins with an optical device that scans the text of a printed document or web page and, using optical character recognition, converts that alphanumeric text string into prefixes, suffixes, and root words (Fig. 5).

The process through which the text string is converted into speech output is somewhat complex and undergoing refinement. The clarity and naturalness of the voice output depend on the text-to-speech technique employed. In general, clearer and more natural costlier sounding speech requires more memory and greater processing power and is thus more expensive.

After the written material has been converted into a text string by optical character recognition software, one of



Figure 5. Functional components of a reading machine. (Taken from Fig. 2.18 of Ref. 5.)

three basic methods can be employed to convert the string into speech sounds. The first method is called whole word look-up. It produces the most intelligible, life-like speech, but it is the most memory intensive even for modest sized vocabularies. Despite steady advances in low cost, high density memory chips, whole-word-look-up tends to be prohibitively expensive or the vocabulary is limited (7).

A less memory intensive approach is the letter-to-sound conversion in which a synthetic sound processor divides the text string into basic letter groups and then follows certain pronunciation rules for the creation of speech. Many languages (especially American English) are replete with numerous exceptions to the usual rules of pronunciation. Hence, the quality of the speech output using letter-to-sound conversion depends on the sophistication of the rules and the number of exceptions employed (7,8).

The third method of converting text into speech is called morphonemic text-to-speech conversion. This approach relies on prestored combination of morphemes (basic units of language such as prefixes, suffixes, and roots) and their corresponding speech sounds. Some 8000 morphemes can generate $\sim 95\%$ of the English words (8,9) so this approach avoids the memory demands of the whole word look-up approach. Morphonemic based speech generation generally yields synthetic speech output that is more intelligible than the letter to speech approach, but is more demanding computationally. Continuing advances in technology have now made single chip text to speech converters powerful, capable, and affordable in consumer electronics (10).

A blind individual using a computer running a text-to-speech program can now hear what is on the screen and use cursor keys to select a specific part of the screen to read. Equipped with such a computer, high speed connection to the Internet, and a modern reading machine, sight impaired individuals now have wide access to news, e-mail, voice messaging, and Internet's vast repository of information. These powerful information technologies have reduced the social isolation formerly felt by blind persons while also broadening their employment opportunities.

One example of how recent technological advances are improving access to reading materials is the Spoken Interface that Apple Computer unveiled at the 2005 Annual Technology & Persons with Disabilities Conference held in Los Angeles. Because Spoken Interface is a screen reader that is fully integrated into Apple's operating system, assistive technology developers should be able to set up easy inter-operability between their software and the operating platform with little additional modifications.

Another example of a low cost, user friendly, and powerful text-to-speech software is the TextAloud MP3 by Nextup Technologies (http://www.nextuptech.com/about.html). This software converts any text into natural sounding speech or into MP3 files for downloading and later playback on portable electronic devices (e.g., MP3 players, pocket PCs, and portable data assistants).

MANDATED WEB ACCESSIBILITY

With so much information available on the Internet and the blind people's increasing dependence on it, the United States government included web accessibility in its 1998 amendment of the Rehabilitation Act (11). Section 508 of this law requires that when Federal agencies develop, procure, maintain, or use electronic information technology, they must ensure that this technology offers comparable access to Federal employees who have disabilities. Although the scope of Section 508 is limited to the Federal sector, these requirements have gradually spread to the private sector, especially to large corporations that deal frequently with the Federal government.

The accessibility requirements of Section 508 are reflected in several guidelines, including as the Web Content Accessibility Guidelines (WCAG) from the World Wide Web Consortium (W3C). The WCAG recommendations, which are updated periodically, include implementing standardized style sheets instead of custom HTML tags and offering closed-captioning and transcripts of multimedia presentations. Other recommendations for making a web site compliant (12) include the following: provide text alternates to images; make meaning independent of color; identify language changes; make pages style sheet independent; update equivalents for dynamic content; include redundant text links for server-side image maps; use client-side image maps when possible; put row and column headers in data tables; associate all data cells with header cells; title all frames; make the site script independent.

An assortment of adaptive hardware and software can be effectively utilized once a web site satisfies the WCAG recommendations (13). Persons with low vision can change their browser settings or use screen magnifiers. Internet users who are blind or have very limited vision can use text-based Web browsers with voice-synthesized screen readers, audio browsers, or refreshable Braille displays to read and interact with the Web.

Recent efforts to increase internet's compatibility with assistive technologies used by sight impaired persons include the development and implementation of search engines that read aloud their results using male and female voices. Some websites offer speech-synthesized renditions of articles from news organizations like BBC, Reuters, and the New York Times (14).

While internet accessibility by persons with severe visual impairments is improving, a number of problems and challenges remain. Screen readers or Braille keyboards that blind people use to navigate the Internet cannot scan or render graphical elements into a readable format. Spam, security checks, popup ads, and other things that slow down a sighted person's Web searches are even worse impediments for those with severe visual impairments using assistive technology.

INDEPENDENT LIVING AIDS

Because blindness and severe visual impairments are so pervasive in their impact, numerous and relatively low cost assistive devices have been developed to make non-reading activities of daily living (ADL) easier. In general, these ADL devices rely on the users' auditory or tactile sense for their operation.



Figure 6. A talking calculator with a female voice speaks the individual digits or whole integers. Its large 8 digit LCD readout is ~0.6 in. (1.52 cm) high. The calculator can add, subtract, divide, multiply and calculate percentages. (Reproduced from Ref. 5.)

A quick check of electronic catalogs on the Internet shows that many types of independent living aids are available. For example, special clocks and timers that give both voice and vibratory alarms are available in various sizes and features. Other assistive devices for ADL include talking wrist watches, push-button padlocks, special money holders, Braille embossed large push button phones, and jumbo sized playing cards embossed with Braille. Personal care items for the blind include talking bathroom scales, thermometers, glucose monitors, blood pressure gauges, and prescription medicine organizers. Educational aids that facilitate note taking, calculating, searching, printing, and organizing information include talking calculators (Fig. 6), pen-like handheld scanner for storing text, letter writing guides with raised lines, Braille metal guides and styluses, and signature guides.

MOBILITY AIDS

For persons with severe visual impairments, the advent of powerful and affordable reading machines and the vast amount information (already in electronic form) on the internet, the problem of access to reading materials has been significantly ameliorated. In contrast, their other major problem (the ability to travel safely, comfortably, gracefully, and independently through the environment) has only been partially solved.

Despite years of effort and some major advances in technology, there is no widely accepted electronic travel aid (ETA). Most blind individuals rely on the sighted human guide, a guide dog, and the familiar white cane. The human sighted guide offers companionship, intelligence, wayfinding capability, route recall, and adaptability. Unfortunately, human guides are not always available, and their very presence constitutes a lack of independence. A guide dog or animal guide has been popular, but not every blind person can independently care for a living animal nor afford the cost of its care. In some social situations, a guide dog can be awkward or unacceptable. The white cane, which is both a tool and a symbol for the blind, can alert sight-impaired travelers to obstacles in their path, but only those at ground level and < 5 ft. (1.5 m) away. Above ground obstacles and especially those at head height remain a source of apprehension and danger for travelers depending on just the white cane.

To understand why decades of research and development efforts have not yielded an efficacious and widely accepted electronic travel aid, one needs to realize that mobility aids must deal with a very different set of constraints and inputs than do reading aids. An identification error made by reading aids results only in misinformation, mispronunciation, or inconvenience. In contrast, a failed detection of an obstacle or step-down or a missed landmark can lead to confusion, frustration, apprehension, and physical injury.

Another major difference between a mobility aid and a reading aid lies in their operating milieu. Mobility aids must detect and analyze unconstrained, long range, and highly variable environmental inputs, that is, obstacles of differing sizes, textures, and shapes distributed over a 180° wide area. In contrast reading machines must identify and convert into intelligible speech inputs that are often well defined and short ranged, for example, high contrast printed alphanumeric symbols and punctuation marks (15).

To further complicate matters, users of reading aids often have the luxury of focusing all or most of their attention on the task at hand: interpreting the output of the reading aid. Users of mobility aids, however, must divide their attention among several demanding tasks associated with traveling, such as avoiding obstacles, listening to environmental cues, monitoring their physical location, recalling the memorized route, and interpreting the auditory or tactile cues from their mobility aid. Given these challenges, today's mobility aids represent a much less satisfactory solution (in comparison to available reading aids) to the problem of independent and safe mobility for persons with severe visual impairments.

THE IDEAL MOBILITY AID

Before examining the capabilities of currently available mobility aids, it is desirable to enumerate the fundamental features of an ideal electronic travel or mobility aid (Table 2) (16–18). The first three items of an ideal mobility aid can be categorized as nearby obstacle avoidance; features 4–7 fall under the category of navigational guidance or wayfinding; and features 8–10 represent good ergonomic design or user friendliness.

CONVENTIONAL ELECTRONIC TRAVEL AIDS

Standard or conventional electronic travel aids detect nearby obstacles, but provide no wayfinding assistance. Obstacle detection entails the transmission of some sort of energy into the surrounding space and the detection of the reflections. After analyzing the reflected signals, the ETA warns the traveler of possible obstacles using either auditory feedback or tactile feedback.

Table 2. The Ideal Mobility Aid

	Capabilities and Features	Description
Feature No. 1	Obstacle detection	Detect nearby obstacles that are ahead, at head level, and at ground level and indicate their approximate locations and distances without causing sensory overload.
Feature No. 2	Warn of impending Obstacles	Reliably locate and warn of impending potholes, low obstacles, step-downs and step-ups.
Feature No. 3	Guidance around obstacles	Guide the traveler around impending obstacles.
Feature No. 4	Ergonomically designed	Offer voice and/or tactile feedback of traveler's present location. Capable of voice input operation and/or have tactually distinct push buttons
Feature No. 5	Wayfinding	Able to monitor the traveler's present location and indicate the direction toward the destination
Feature No. 6	Route recall	Be able to remember a previous route and warn of changes in the environment due to construction or other blockages
Feature No. 7	Operational flexibility	Reliably function in a variety of settings, that is, outdoors, indoors, stairways, elevators, and cluttered open spaces
Feature No. 8	User friendliness	Be portable, rugged, fail-safe, and affordable for a blind user
Feature No. 9	Cosmesis	Be perceived by potential users as cosmetically acceptable and comfortable to use in terms of size, styling, obtrusiveness, and attractiveness
Feature No. 10	Good battery life	Have rechargeable batteries that can last for at least 6 h per charge

The LASER CANE (Fig. 7) is one of the few conventional ETAs that can serve as a stand-alone, primary travel aid because it has obstacle detection (features 1–3 of Table 2) and is reasonably user friendly and cosmetic (features 8–10). The laser cane's shaft houses three narrow-beam lasers; the lasers scan upward, forward, and downward. Reflections from objects in these zones are detected by three optical receivers also housed in the shaft. The UP channel monitors head level obstacles and causes high pitched beeps to be emitted. The FORWARD channel monitors objects located 4–10 ft. (1.21–3.01 m) ahead of the cane's tip and produces warning signals in the form of either vibrations in the handle of the cane or a medium (1600 Hz) audio tone. Obstacles encountered by the DOWN channel produce a low frequency (200 Hz) warning tone (19). Because the laser cane is swept through an arc ~ 3–4 ft. (0.91–1.21 m) wide in the direction of the intended path (in a manner similar to standard long cane usage), the laser cane augments the auditory and tactile feedback of an ordinary white cane by detecting objects at greater distances and, most importantly, head level obstructions.

The laser cane's main drawbacks include it being somewhat costly and fragile. It also cannot monitor the traveler's geographic location nor guide the traveler toward the intended destination (features 5 and 6). Field tests and consumer feedback revealed that laser obstacle detection can be highly variable because certain surfaces and objects reflect laser light better than others. For example, the laser beam mostly passes through glass so that the laser cane may miss glass doors or large glass windows ahead.

Although the laser cane is imperfect, it has one major advantage as an ETA; It is failsafe. Should its batteries run down or its electronics malfunction, the laser cane can still serve as a standard long cane (20) and thus still be useful to the traveler.

Another commercially available electronic travel aid is the Sonic Guide, an eyeglass frame equipped with one ultrasonic transmitter and two receivers embedded in



Figure 7. The laser cane projects three narrow beams of laser light. If any of the beams (up, forward, and downward) encounter an object and is reflected back to the receivers in the cane's shaft, a tactile or auditory warning is generated. (Reproduced from Ref. 19.)

the nose piece (21). The pulsed ultrasonic beam radiates through a forward solid angle of $\sim 100^\circ$. Objects in the environment reflect ultrasound back to the two receivers with time delays proportional to their distance and angle with respect to the wearer's head. The wearer is given awareness of his surroundings via binaural auditory feedback of the reflected signals, recreating the experience of echolocation as found in bats or dolphins. An object's distance is displayed in terms of frequencies proportional to the object's distance from the user. The azimuth of an object relative to the user's head is displayed via the relative intensity of tones sent to the ears (stereoscopic aural imaging). As a result, the binaural sounds heard by the user changes as he moves or turns his head.

To circumvent Sonic Guide's tendency to interfere with normal hearing, Kuc (22) investigated the utility of using vibrotactile feedback via a pair of sonar transceivers and vibrators worn on the wrists. Being on opposite sides of the body, the dual sonar transceivers offered better left–right obstacle discrimination than could a single sonar unit embedded in the nose piece of the eyeglasses. The wrist mounted pager-like device vibrated at a frequency inversely related to the reflecting object's distance from that side of the body.

Unfortunately, neither the original eyeglass frame based Sonic Guide nor the wrist worn sonar guide can serve as a stand-alone travel aid because neither can detect impending step-ups, step-downs, or other tripping hazards in the pathway. Other user comments about the Sonic Guide include interference with normal hearing, sensory overload, and difficulty in combining the aid's feedback with other important environmental cues such as the sound of traffic at street intersections, tactile feedback from a white cane, or the subtle pull of a guide dog.

In contrast to Sonic Guide's rich auditory feedback, the Mowat Sensor implements the design philosophy that simpler is better. The Mowat Sensor is a handheld ultrasonic flash light that acts like a clear path detector. It measures $6 \times 2 \times 1$ in. ($15 \times 5 \times 2.5$ cm), weighs 6.5 oz (184.2 g), can be easily carried in a pocket or purse, and is manufactured by Pulse Data International Ltd. of New Zealand and Australia.

The Mowat device emits a pulsed elliptical ultrasonic beam $\sim 15^\circ$ wide by 30° high, a beam pattern that should detect doorway sized openings located some 6 ft. (1.8 m) away. Reflections from objects in the beam pattern cause the Mowat to produce vibrations that are inversely proportional to the object's distance from the detector. As the traveler points at and gets closer to the object, the Mowat vibrates faster and faster. As the traveler aims moves away from that object, the vibrations slow and then cease. Objects outside of Mowat's beam pattern produce no vibrations.

The Sonic Guide, Mowat Sensor, and their various derivatives share similarities while representing two divergent design philosophies. They all employ ultrasound instead of laser light to detect nearby obstacles. None of them can detect tripping hazards, such as impending step-ups, step-downs, uneven concrete walkways, or small low obstacles in the path of travel so they cannot serve as a stand-alone travel aid. The Mowat sensor scans a small portion of the environment, displays limited data from that region, and offers easily interpreted vibratory information to the user. Alternatively, the Binaural Sonic Guide sends a broad sonic beam into much of the traveler's forward environment, displays large amounts of environmental information, and leaves it up to the user to select which portion of the auditory feedback to monitor and which to ignore.

While similar in concept, obstacle detection via ultrasound and obstacle detection via laser light interact with the environment differently. For example, hard vertical surfaces and glossy painted surfaces reflect sound and light very well so they tend to be detected by both methods at greater distances than oblique surfaces or dark cloth covered soft furnishings. Transparent glass, however, reflects sound very well, but laser light very poorly. Hence an ultrasonic beam would readily note the presence of a glass door whereas laser light could miss it entirely. Sonar based ETAs, however, are susceptible to spurious sources of ultrasound such as squealing air breaks on buses. Such sources and even heavy precipitation can cause the sonar sensor to signal the presence of a phantom obstacle or produce unreliable feedback. Furthermore, because all ETAs display environmental information via the sense of touch or hearing, severe environmental noise and wearing gloves or ear muffs can reduce a user's ability to monitor an ETAs feedback signals.

Other drawbacks of conventional electronic travel aids include the lack of navigational guidance (features 5 and 6 of Table 2), thus limiting the blind traveler to familiar places or necessitating directional guidance from a sighted guide until they have memorized the route. Furthermore, conventional ETAs often require the user to actively scan the environment and interpret the auditory and tactile feedback from the aids. These somewhat burdensome tasks require conscious effort and can slow walking speed.

INTELLIGENT ELECTRONIC TRAVEL AIDS

Recent advances in technology have sparked renewed efforts to develop mobility aids that address some of the aforementioned drawbacks. One promising intelligent electronic travel aid, under development at the University of Michigan Mobile Robotics Laboratory, is the GuideCane (23). The GuideCane (Fig. 8) is a semiautonomous robotic guide that improves user friendliness by obviating the burden of constant scanning while also guiding the traveler around obstacles, not merely detecting them. It consists of a self-propelled and servocontrolled mobile platform connected to a cane. An array of 10 ultrasonic sensors is mounted on the small platform. The sensors emit slightly overlapping signals to detect ground-level obstacles over a 120° arc ahead of the platform. The sonar units, made by Polaroid Corporation, emit short bursts of ultrasound and then uses the time of flight of the reflections to gauge the distance to the object. The sonar has a maximum range of 30 ft. (10 m) and an accuracy of $\sim 0.5\%$ (24).

When walking with the GuideCane, the user indicates his intended direction of travel via a thumb-operated mini-joystick mounted at the end of a cane attached to the



Figure 8. The GuideCane functions somewhat like a robotic guide dog. It is able to scan the environment and steer around obstacles by using its ultrasonic sensors, steering servomotors, and on-board computer to keeps track of nearby obstacles and the intended path of travel. (Reprinted from figure on p. 435 of Ref. 23.)

platform. The mobile platform maintains a map of its immediate surroundings and self-propels along the indicated direction of travel until it detects an obstacle at which time the robotic guide steers itself around it. The blind traveler senses the GuideCane's change of direction and follows it accordingly.

Like the Laser cane, the GuideCane can function as a stand-alone travel aid because it gives advance warning of impending step-downs and tripping hazards. Its bank of 10 ultrasonic detectors and ability to navigate around detected obstacles make the GuideCane easier and less mentally taxing to use than the Laser Cane. To address the wayfinding needs of the blind traveler, efforts are underway to add GPS capability, routing software and area maps to the GuideCane. The drawbacks of the wheel mounted GuideCane, however, include its size and weight and its inability to detect head height objects.

NAVIGATIONAL NEEDS

Electronic travel aids like those described above are becoming proficient at detecting and enabling the traveler to avoid obstacles and other potential hazards. Avoiding obstacles, however, represents only a partial solution to a blind person's mobility problem. Many visually impaired or blind travelers hesitate to visit unfamiliar places because they fear encountering an emergency or possibly getting lost. Their freedom of travel is hampered by having to pre-plan their initial trip to a new place or needing to enlist the help of a sighted person.

Furthermore, blind pedestrians, even those with training in orientation and mobility, often experience difficulty in unfamiliar areas and areas with free flowing traffic, such as parking lots, open spaces, shopping malls, bus terminals, school campuses, and roadways or sidewalks under construction. They also have difficulty crossing nonorthogonal, multiway traffic intersections (25). Conventional traffic signals combined with audible pedestrian traffic signals have proven somewhat helpful in reducing the pedestrian accident rates at intersections (26–28), but audible traffic signals offer guidance only at traffic intersections and not other important landmarks.

One proposed solution for meeting the wayfinding needs of blind travelers is the Talking Sign, a remote infrared signage technology that has been under development and testing at The Smith-Kettlewell Eye Research Institute in San Francisco, CA (29,30). The Talking Signs system consists of strategically located modules that transmit environmental speech messages to small, hand held receivers carried by blind travelers (Fig. 9). The repeating and directionally selective voice messages are transmitted to the receiver by infrared (IR) light (940 nm, 25 kHz). Guided by these orientation aids, blind travelers can know their present location and move in the direction from which the desired message, for example, Corner of Front Street and Main Street, is being broadcasted, thus finding their way without having to remember the precise route.

The Talking Sign and other permanently mounted voice output devices, however, require standardization, costly retrofitting of existing buildings, and the possession of a suitable transceiver to detect or activate the installed devices. Retrofitting buildings with such devices is not cost effective due to their inherent inflexibility and the need for many users to justify the implementation costs. What's especially frustrating for persons with severe visual impairments is that talking signs may not reflect their travel patterns or be available at unfamiliar locations and wide open spaces. To be truly useful, talking signs would have to be almost ubiquitous and universally adopted.

GPS NAVIGATIONAL AIDS

In addition to obstacle avoidance, the ideal navigational aid also must address two other key aspects of independent travel: orientation (the ability to monitor one's position in relationship to the environment) and route guidance (the ability to determine a safe and appropriate route for reaching one's destination). As an orientation aid, the Global Positioning System (GPS) seems promising. For route guidance, a notebook computer or personal data assistant (PDA) equipped with speech input/output software, route planning software (artificial intelligence), and digital maps have been proposed (18,31,32). A voice operable, handheld GPS unit used in combination with obstacle detecting ETAs like the Laser Cane might constitute the ideal navigational aid for blind persons.

Several GPS equipped PDAs have recently become available. For example, the iQue 3600 ($600 from Garmin International Inc., Olathe, Kansas) is a handheld device that combines a PDA and mapping software with a built-in GPS receiver. The iQue 3600 uses the Palm operating system and offers a color screen and voice output turn-by-turn navigational guidance. For someone who already possesses a PDA (e.g., Palm Pilot or Microsoft's Pocket



Figure 9. Talking Signs not only gives location information, but also tells the pedestrian the current status of the pedestrian cycle, aids in finding the cross-walk, and indicates the direction of the destination corner. (Reproduced from Ref. 29.)

PC), various third party software and GPS add-on units can be used.

While promising as a navigational aid for persons with severe visual impairments, GPS equipped portable PDAs (or notebook computers) have significant limitations. To fully appreciate these limitations, a brief review of how the Global Positioning System works (Fig. 10) would be apropos.

Global Positioning System (GPS) began some 30 years ago when Aerospace Corporation in Southern California studied ways to improve radio navigation systems for the military (33). Although GPS was not fully operational at the outbreak of the Persian Gulf War in January 1991, its exceptional performance in accurately locating fighting units evoked a strong demand from the military for its immediate completion.

Currently, 24 satellites of the GPS circle the earth every 12 h at a height of 20,200 km. Each satellite continuously transmits pseudorandom codes at 1575.42 and 1227.6 MHz. The orbital paths of the satellites and their altitude enable an unobstructed observer to see between five and eight satellites from any point on the earth. Signals from different visible satellites arrive at the GPS receiver with different time delays. The time delay needed to achieve coherence between the satellites' pseudorandom codes and the receiver's internally generated code equals the time-of-flight delay from a given satellite. GPS signals from at least four satellites are analyzed to determine the receiver's longitude, latitude, altitude (as measured from earth's center) and the user's clock error with respect to system time (33).

For civilian applications, position accuracy of a single channel receiver is about 100 m and its time accuracy is ~340 ns. Greater accuracy, usually within 1 m, can be achieved using differential GPS wherein signals from additional satellites are analyzed and/or the satellite signals are compared with and corrected by a GPS transceiver at a known fixed location (33).

At first glance, GPS signals seem fully able to meet the orientation needs of persons with severe visual impairments. The GPS signals are sufficiently accurate if combined with differential GPS and signals are immune to weather and are available at any time of the day, anywhere there's a line of sight to at least four GPS satellites. Lastly, a GPS receiver is relatively inexpensive, < $200.

Unfortunately, just equipping blind persons with a voice-output GPS receiver for wayfinding outdoors is insufficient. The GPS signals are often unavailable or highly attenuated under bridges, inside natural canyons, and between tall buildings in urban areas. The altitude GPS information is generally not useful, and its longitudinal and latitudinal coordinates are useless when unaccompanied by local area maps (17). For college campuses or even major metropolitan areas, the location of major buildings and their entrances in terms of longitude and latitude coordinates are rarely available. Without these key pieces



Figure 10. Synchronized signals from four satellites are analyzed by the mobile receiver to determine its precise position in three dimensions. The distances for the four satellites include an unknown error due to the inaccuracy of the receiver's clock and Doppler effects. (Reprinted from Ref. 33.)

of information, the GPS navigational aid is unable to offer directional guidance to the blind traveler.

INDOOR NAVIGATIONAL AIDS

One of the key characteristics of an ideal mobility aid is that the device reliably function indoors, outdoors, and within changing environments (Table 2). When used in combination with detailed local area maps, the GPS receiver and voice output could form the basis for a navigational aid. However, GPS signals may not be available at all times and are totally absent indoors. To function indoors, an electronic navigational aid will need to rely on some other set of electronic beacons as signposts.

For wayfinding within a large building, several investigators have borrowed the idea found in the Hansel and Gretel fairy tale about two children leaving a trail of bread crumbs to find their way home again. Instead of bread crumbs, Szeto (18) proposed placing small, low cost electronic beacons along corridors or at strategic locations (e.g., elevators, bathrooms, stairs) of buildings visited. Acting like personal pathmarkers, these radio frequency (RF) emitting electronic beacons would be detected by the associated navigational aid and guide the traveler back to a previous location or exit. To avoid confusion with other users, the electronic beacons could be keyed to work with one navigational aid.

Kulyukin et al. (34) recently studied the efficacy of using Radio Frequency Identification (RFID) tags in robot-assisted indoor navigational for the visually impaired. They described how strategically located, passive (nonpowered) RFID tags could be detected and identified by a RFID reader employing a square 200×200 mm antenna and linked to a laptop computer. In field tests, wall-mounted RFID tags responded to the spherical electromagnetic field from an RFID antenna at a distance of ~ 1.5 m. Since each tag is given a unique identifier, its location inside a building can be easily recalled and used to locate one's position inside a building.

In comparison to wall-mounted Talking Signs, the approach of Szeto (18) and Kulukin et al. (34) seems to be less costly and more flexible. Placing disposable electronic beacons in the hands of individual travelers does not require permanent retrofits of buildings, can be cost effective even for single users, and easily changes with the travel patterns of the user.

The electronic beacons and handheld electronic transceivers also should be economically feasible because they utilize a technology that's being developed for the mass market. World's largest retailer, Wal-Mart, has mandated 2008 as the year when all its suppliers must implement an RFID tracking system for their deliveries. It is likely that RFID tags, antenna, and handheld interrogators developed for inventory tracking can be adapted for use in an indoor navigational aid.

Although not yet a reality, a low cost, portable, handheld, indoor–outdoor mobility aid that embodies many of the features listed in Table 2 is clearly feasible. The needed technological infrastructure will soon be in place. For obstacle avoidance, the Laser Cane, Guide Cane, or their variants can be used. For indoor wayfinding and route guidance, the blind traveler could augment the cane or guide dog with a handheld voice output electronic navigational aid linked to strategically placed electronic beacons. For outdoor wayfinding, the blind traveler could augment the Laser Cane with a handheld mobility aid equipped with a GPS receiver, compass, local area maps, and wireless internet link.

The intelligent navigational aid just described would address the mobility needs of the blind by responding to voice commands; automatically detecting GPS signals or searching for the presence of electronic beacons; wirelessly linking to the local area network to obtain directory information; converting the GPS coordinates or the signals from electronic beacons into a specific location on a digital map; and, with the help of routing finding software, generating step-by-step directions to the desired destination.

FUTURE POSSIBILITIES

Of course, the ultimate assistive technology for overcoming the many problems of severe visual impairment would be an artificial eye. Since the mid-1990s, research by engineers, ophthalmologists, and biologists to develop a bionic eye have grown and artificial retina prototypes are nearing animal testing. An artificial eye would incorporate a small video camera to capture light from objects and transmit the image to a wallet-sized computer processor that in turn sends the image to an implant that would stimulate either the retina (35) or visual cortex (36).

Researchers at Stanford University recently announced progress toward an artificial vision system that can stimulate a retina with enough resolution to enable a visually impaired person to orient themselves toward objects, identify faces, watch television, read large fonts, and live independently (37). Their optoelectronic retinal prosthesis system is expected to stimulate the retina with resolution corresponding to a visual acuity of 20/80 by employing 2500 pixels per square millimeter. The researchers see the device as being particularly helpful for people left blind by retinal degeneration. Although such developments are exciting, tests with human subjects on practical but experimental prototypes won't likely occur for another 6–8 years (38).

What else the does the future hold in terms of assistive technology in general and mobility aids in particular? In an address to the CSUN 18th Annual Conference on Technology and Persons with Disabilities in 2003, futurist and U.S. National Medal of Technology recipient, Ray Kurzweil, presented his vision of the sweeping technological changes that he expected to take place over the next few decades (39). His comments are worthy of reflection and give cause for optimism.

With scientific and technological progress doubling every decade, Kurzweil envisions ubiquitous computers with always-on Internet connections, systems that would allow people to fully immerse themselves in virtual environments, and artificial intelligence embedded into Web sites by 2010. Kurzweil (39) expects the human brain to be fully reverse-engineered by 2020, which would result in computers with enough power to equal human intelligence. He forecasted the emergence of systems that provide subtitles for deaf people around the world, as well as listening systems geared toward hearing-impaired users. Blind people would be able to take advantage of pocket-sized reading devices within a decade or have retinal implants that restore useful vision in 10–20 years. Kurzweil believed that people with spinal cord injuries would be able to resume fully functional lives by 2020, either through the development of exoskeletal robotic systems or techniques that bridged severed neural pathways, possibly by wirelessly transmitting nerve impulses to muscles. Even if one-half of what Kurzweil predicted became reality, the future of assistive technology for the blind is bright and an efficacious intelligent mobility aid for such persons will soon be commercially available.

BIBLIOGRAPHY

Cited References

1. Beck AF, Stern A, Uslan MM, Wiener WR, editors. Access to Mass Transit for Blind and Visually Impaired Travelers. New York: American Foundation for the Blind; 1990.
2. National Eye Institute and Prevent Blindness America®, Vision Problems in the U.S., 4th ed., 2002.
3. Arch Ophtha Imol. April 2004; 122.
4. Allen J. Electronic aids for the severely visually handicapped. CRC Crit Rev Bioeng 1971;1:137–167.
5. Servais SB. Visual Aids. In: Webster JG, Cook AM, Tompkins WJ, Vanderheiden GC, editors. Electronic Devices for Rehabilitation. New York: John Wiley & Sons, Medical; 1985. p 31–78.
6. Independent Living Aids, Inc. (No date) [Online] product catalog. Available at http://www.independentliving.com/home.asp. Accesse May 2005
7. Allen J. Linguistic-based algorithms offer practical text-to-speech systems. Speech Technol 1981;1(1):12–16.
8. Breen A. Speech synthesis models: a review. Elect Commun Eng J 1992;4(1):19–31.
9. O'Shaughnessy D. Interacting with computers by voice: Automatic speech recognition and synthesis. Proc IEEE 2003;91(9): 1272–1305.
10. Jackson G, et al. A single-chip text-to-speech synthesis device utilizing analog nonvolatile multi-level flash storage. IEEE J. Solid State Cir Nov 2002;37(11):1582–1592.
11. Thatcher J, et al. Constructing Accessible Websites, ISBN: 1904151000, New York: Glasshaus; 2002.
12. Matthews W. 13 rules for accessible web pages, August 07, 2000 of the Federal Computer Week. (No date). [Online]. Available at http:// www.fcw.com/fcw/articles/2000/0807/cov-access2-08-07-00.asp. Accessed March 2005.
13. Lazzaro JJ. Adaptive Technologies for Learning and Work Environments. 2nd ed., New York: The American Library Association; 2000.
14. Tucker A. Net surfing for those unable to see, Baltimore Sun, p. 1C. [Online] Available at http://www.baltimoresun.com/features/lifestyle/bal-to.blind16mar16,1,1345515.story?ctrack=1&cset=true. Accessed March 16, 2005.
15. Shao S. Mobility Aids For The Blind. In: Webster JG, Cook AM, Tompkins WJ, Vanderheiden JC, editors. Electronic Devices for Rehabilitation. New York: John Wiley & Sons, Medical; 1985. p. 79–100.
16. Farmer LW. Mobility Devices. In: Welsh RL, Blasch BB, editors. Foundation of Orientation and Mobility. New York: American Foundation for the Blind; 1980. p 206–209.
17. Bentzen BL. Orientation aids. In: Blasch B, Weiner W, Welsh W, editors. Foundations of Orientation and Mobility. 2nd ed. New York: American Foundation for the Blind; 1997. p 284–316.
18. Szeto AYJ. A navigational aid for persons with severe visual impairments: a project in progress. Proceeding of the 25th Annual International Conference IEEE Engineering and Medicine & Biology Society; Vol 25(2), Cancun, Mexico, Sep. 2003 p 1637–1639.
19. Nye PW, Bliss JC. Sensory aids for the blind: a challenging problem with lessons for the future. Proc IEEE 1970;58: 1878–1879.
20. Cook AM, Hssey SM. Assistive Technologies: Principles and Practice. 2nd ed., St. Louis, (MO): Mosby; 2002. p. 423–426.
21. Kay L. A sonar aid to enhance spatial perception of the blind: Engineering design and evaluation. Radio Elect Eng 1974;44(11):605–627.
22. Kuc R. Binaural sonar electronic travel aid provides vibrotactile cues for landmark, reflector motion and surface texture classification. IEEE Trans Biomed Eng Oct 2002; 49(10):1173–1180.
23. Shovel S, Ulrich I, Borenstein J. Computerized Obstacle Avoidance Systems for the Blind and Visually Impaired. In: Teodorescu HNL, Jain LC, editors. Intelligent Systems and Technologies in Rehabilitation Engineering. Boca Raton(FL): CRC Press; 2001.
24. Polaroid Corp, Ultrasonic Ranging System—Description, operation and use information for conducting tests and experiments with Polaroid's Ultrasonic Ranging System, Ultrasonic Components Group, 119 Windsor Street, Cambridge (MA).
25. National Safety Council, Pedestrian accidents, National Safety Council Accident Facts (Injury Statistics), 1998.
26. Szeto AYJ, Valerio N, Novak R. Audible pedestrian traffic signals: Part 1. Prevalence and impact. J Rehabilit R & D 1991;28(2):57–64.
27. Szeto AYJ, Valerio N, Novak R. Audible pedestrian traffic signals: Part 2. Analysis of sounds emitted. J Rehabilit R & D 1991;28(2):65–70.
28. Szeto AYJ, Valerio N, Novak R. Audible pedestrian traffic signals: Part 3. Detectability. J Rehabilit R & D 1991;28(2):71–78.
29. Farmer LW, Smith DL. Adaptive technology. In: Blasch B, Weiner W, Welsh R. Foundations of Orientation and Mobility. 2nd ed., New York: American Foundation for the Blind; 1997. p. 231–259.
30. Brabyn J, Crandall W, Gerrey W. Talking Signs®: A Remote Signage Solution for the Blind, visually Impaired and Reading Disabled, Proceeding of the 15th Annual International Conference in IEEE Engineering in Medicine & Biology Society; 1993; Vol. 15: p. 1309–1311.
31. Vogel S. A PDA-based navigational system for the blind. [Online], Available at http://www.cs.unc.edu/~vogel/IP/IP/IP_versions/IPfinal_SusanneVogel. Accessed Spring 2003.pdf.
32. Helal A, Moore SE, Ramachandran B. Drishti: An integrated navigation system for visually impaired and disabled. Procedings of the 5th International Symposiun on Wearable Computers, Zurich, Switzerland; October 2001; p. 149–155.
33. Getting IA. The Global Positioning System. IEEE Spectrum Dec. 1993;30(12):36–47.
34. Kulyukin V, Gharpure C, Nicholson J, Pavithran S. RFID in Robot-Assisted indoor Navigation for the Visually Impaired. Proceedings of the 2004 IEEE/RSJ International Conference on Intelligent Robots and Systems; Sept. 28–Oct. 2, 2004; Sendai, Japan, p 1979–1984.
35. Wyatt J, Rizzo J. Ocular implants for the blind. IEEE Spectrum May 1996;33(5):47–53.
36. Normann RA, Maynard EM, Guillory KS, Warren DJ. Cortical implants for the blind. IEEE Spectrum May 1996;33 (5):54–59.
37. Palanker D, Vankov A, Huie P, Baccus S. Design of a high-resolution optoelectronic retinal prosthesis. J Neural Eng 2005;2:105–120.

38. Braham R. Toward an artificial eye. IEEE Spectrum May 1996;33(5):20–21.
39. Kurzweil R. The future of intelligent technology and its impact on disabilities. J Visual Impairment Blindness Oct 2003;97(10):582–585.

Reading List

Cook AM, Hussey SM. Assistive Technologies: Principles and Practice. 2nd ed., St. Louis (MO): Mosby, Inc.; 2002. A thorough text on assistive technologies that is especially suited for the rehabilitation practitioner or those in allied health.

Smith RV, Leslie JH Jr., editors. Rehabilitation Engineering. Boca Rotan (FL): CRC Press; 1990. Contains diverse articles that should be of particular interest to practitioners in the rehabilitation field although several of the articles present definitive state-of-the-art information on rehabilitation engineering.

Webster JG, Cook AM, Tompkins WJ, Vanderheiden GC, editors. Electronic Devices for Rehabilitation. New York: John Wiley & Sons Inc. Medical; 1985. Though somewhat dated, this book offers a comprehensive overview of rehabilitation engineering and describes many of the design issues that underlie various types of assistive devices. A useful introductory text for undergraduate engineering students interested in rehabilitation.

Golledge RG. Wayfinding Behavior: Cognitive Mapping and Other Spatial Processes. Baltimore: John Hopkins University Press; 1999. A good reference that covers the cognitive issues of wayfinding behavior in blind and sighted humans.

Teodorescu HNL, Jain LC, editors. Intelligent Systems and Technologies in Rehabilitation Engineering. Boca Rotan (FL): CRC Press; 2000. A compendium of technical review articles covering intelligent technologies applied to retinal prosthesis, auditory & cochlear prostheses, upper and lower limb orthoses/ prostheses, neural prostheses, pacemakers, and robotics for rehabilitation.

Yonaitis RB. Understanding Accessibility-A Guide to Achieving Compliance on Websites and Intranets, ISBN: 1-930616-03-1, HiSoftware, 2002. This is a free booklet in electronic form for complying with the Federal government's "Section 508" of the Workplace Rehabilitation Act (amendments of 1998). The book gives a brief and clear discussion of accessibility testing and how to integrate this activity into web design and related tasks.

Blasch B, Weiner W, Welsh R. Foundations of Orientation and Mobility. 2nd ed., New York: American Foundation for the Blind; 1997. A useful book for general background regarding the issues of orientation and mobility.

IEEE Spectrum, Vol. 33(5), May 1996, carries six special reports on the development of an artificial eye. Articles in this issue examine physiology of the retina, neural network signal processing, electrode array design, and sensor technology.

Journal of Visual Impairment and Blindness, Vol. 97(10), Oct. 2003, is a special issue that focused on the impact of technology on blindness.

Speech Technology, a magazine published bimonthly by AmCom Publications, 2628 Wilhite Court, Suite 100, Lexington, KY 450503. This magazine regularly covers the development and implementation of technologies that underlie speech recognition and speech generation. For example, its March/April 2005 issue contained articles on the following topics: guide to speech standards; applications of transcription; role of speech in healthcare, embedding speech into mobile devices, technology trends, new products, and speech recognition software.

See also COMMUNICATION DEVICES; ENVIRONMENTAL CONTROL; MOBILITY AIDS; VISUAL PROSTHESES.

BLOOD BANKING. See BLOOD COLLECTION AND PROCESSING.

BLOOD CELL COUNTERS. See CELL COUNTERS, BLOOD.

BLOOD COLLECTION AND PROCESSING

TERESA M. TERRY
JOSEPHINE H. COX
Walter Reed Army Institute of Research
Rockville, Maryland

INTRODUCTION

Phlebotomy may date back to the Stone Age when crude tools were used to puncture vessels to allow excess blood to drain out of the body (1). This purging of blood, subsequently known as blood letting, was used for therapeutic rather than diagnostic purposes and was practiced through to modern times. Phlebotomy started to be practiced in a more regulated and dependable fashion after the Keidel vacuum tube for the collection of blood was manufactured by Hynson, Wescott, and Dunning. The system consisted of a sealed ampoule with or without culture medium connected to a short rubber tube with a needle at the end. After insertion onto the vein, the stem of the ampoule was crushed and the blood entered the ampoule by vacuum. Although effective, the system did not become popular until evacuated blood collection systems started to be used in the mid-twentieth century. With evacuated blood collection systems came a new interest in phlebotomy and blood drawing techniques and systems. A lot of technical improvements have been made, not only are needles smaller, sharper, and sterile, they are also less painful. The improved techniques of obtaining blood samples assure more accurate diagnostic results and less permanent damage to the patient. Today, the main purpose of phlebotomy synonymous with venipuncture is to obtain blood for diagnostic testing.

Venipuncture Standards and Recent Standard Changes

The Clinical and Laboratory Standards Institute (CLSI, formerly the National Committee for Clinical Laboratory Standards, NCCLS) develops guidelines and sets standards for all areas of the laboratory (www.CLSI.org). Phlebotomy program approval as well as certification examination questions are based on these important national standards. Another agency that affects the standards of phlebotomy is the College of American Pathologists (CAP; www.CAP.org). This national organization is an outgrowth of the American Society of Clinical Pathologists (ASCP). The membership in this specialty organization is made up of board-certified pathologists only and offers, among other services, a continuous form of laboratory inspection by pathologists. The CAP Inspection and Accreditation Program do not compete with the Joint Commission on Accreditation of Health Care Organizations

(JCAHO) accreditation for health care facilities, because it was designed for pathology services only.

The CLSI have published the most current research and industry regulations on standards and guidelines for clinical laboratory procedures (2,3). The most significant changes to specimen collection are (*1*) collectors are now advised to discard the collection device without disassembling it, this reflects the Occupational Safety and Health Administration's (OSHA) mandate against removing needles from tube holders; (*2*) the standard now permits gloves to be applied just prior to site preparation instead of prior to surveying the veins; (*3*) collectors are advised to inquire if the patient has a latex sensitivity; (*4*) sharp containers should be easily accessible and positioned at the point of use; (*5*) there is a caution recommended against the use of ammonia inhalants on fainting patients in case the patient is asthmatic; (*6*) collectors must attempt to locate the median cubital vein on either arm before considering alternative veins due to the proximity of the basilica vein to the brachial artery and the median nerve; (*7*) forbids lateral needle relocation in an effort to access the basilica vein to avoid perforating or lacerating the brachial artery; (*8*) immediate release of tourniquet "if possible" upon venous access to prevent the effects of hemoconcentration from altering test results.

The Role of the Phlebotomist Today

Professionalism. Phlebotomists are healthcare workers and must practice professionalism and abide by state and federal requirements. A number of agencies have evolved offering the phlebotomist options for professional recognition (1). Certification is a process that indicates the completion of defined academic and training requirements and the attainment of a satisfactory score on a national examination. Agencies that certify phlebotomists and the title each awards include the following: American Society of Clinical Pathologists (ASCP): Phlebotomy Technician, PBT (ASCP); American Society for Phlebotomy Technology (ASPT): Certified Phlebotomy Technician, CPT (ASPT); National Certification Agency for Medical Laboratory Personnel (NCA): Clinical Laboratory Phlebotomist (CLP) (NCA); National Phlebotomy Association (NPA); Certified Phlebotomy Technician, CPT (NPA). Licensure is defined as a process similar to certification, but at the state or local level. A license to practice a specific trade is granted through examination to a person who can meet the requirements for education and experience in that field. Accreditation and approval of healthcare training programs provides an individual with an indication of the quality of the program or institution. The accreditation process involves external peer review of the educational program, including an on-site survey to determine if the program meets certain established qualification or educational standards referred to as 'essentials'. The approval process is similar to accreditation; however, programs must meet educational—standards and competencies—rather than essentials, and an on-site survey is not required.

Public Relations and Legal Considerations. The Patient's Bill of Rights was originally published in 1975 by the American Hospital Association. The document, while not legally binding, is an accepted statement of principles that guides healthcare workers in their dealings with patients. It states that all healthcare professionals, including phlebotomists, have a primary responsibility for quality patient care, while at the same time maintaining the patient's personal rights and dignity. Two rights especially pertinent to the phlebotomist are the right of the patient to refuse to have blood drawn and the right to have results of lab work remain confidential. Right of Privacy: "An individual's right to be let alone, recognized in all United States jurisdictions, includes the right to be free of intrusion upon physical and mental solitude or seclusion and the right to be free of public disclosure of private facts. Every healthcare institution and worker has a duty to respect a patient's or client's right of privacy, which includes the privacy and confidentiality of information obtained from the patient–client for purposes of diagnosis, medical records, and public health reporting requirements. If a healthcare worker conducts tests on or publishes information about a patient–client without that person's consent, the healthcare worker could be sued for wrongful invasion of privacy, defamation, or a variety of other actionable torts." In 1996, the Health Insurance Portability and Accountability Act (HIPAA) law was signed. It is a set of rules to be followed by health plans, doctors, hospitals, and other healthcare providers. Patients must be able to access their record and correct errors and must be informed of how their personal information will be used. Other provisions involve confidentiality of patient information and documentation of privacy procedures.

SAFETY

Universal Precautions

An approach to infection control that is mandated by federal and state laws is the so-called Universal Precautions. The guidelines for Universal Precautions are outlined by OSHA (www.OSHA.gov). According to the concept of Universal Precautions, all human blood and certain human body fluids are treated as if known to be infectious for human immunodeficiency virus (HIV), hepatitis B virus (HBV), and other blood borne pathogens. For blood collections, the use of needles with a safety device or a needle integrated into a safety device and the use of gloves is now mandatory in most institutions. Biohazard material should be disposed of in an appropriately labeled biohazard container. Needles and other sharp instruments should be disposed of in rigid puncture-resistant biohazard containers.

First Aid Procedures

Most phlebotomy programs require cardio pulmonary resuscitation (CPR) certification as a prerequisite or include it as part of the course and in the event of an emergency situation: basic First Aid Procedures should be performed by the phlebotomist. These procedures are not in the scope of this article and training needs to be performed by qualified experts.



*A butterfly with luer adapter is shown as well as a standard needle

Figure 1. Basic components of the Evacuated Blood Collection System.

BLOOD COLLECTION SYSTEM AND EQUIPMENT

Blood Collection System

The components of the Evacuated Blood Collection System are shown in Fig. 1. The system consists of the following;

Plastic evacuated collection tube: The tubes are designed to fill with a predetermined volume of blood by vacuum. The rubber stoppers are color coded according to the additive that the tube contains (see Table 1). Evacuated collection devices are supplied by many vendors worldwide. These evacuated collection devices use similar color coding systems, proprietary additives, and recommended uses. Various sizes are available.

Tube holder (single use): For use with the evacuated collection system.

Needles (also available with safety device): The gauge number indicates the bore size: the larger the gauge number, the smaller the needle bore. Needles are available for evacuated systems and for use with a syringe, single draw, or butterfly system.

Additional Materials

Tourniquet: Wipe off with alcohol and replace frequently. Nonlatex tourniquets are recommended.

Table 1. Tube Guide[a]

Tube Top Color	Additive	Inversions at Blood Collection[a]	Laboratory Use
Gold or Red/Black	Clot activator Gel for serum separation	5	Tube for serum determinations in chemistry. Blood clotting time: 30 min
Light Green or Green/Gray	Lithium heparin Gel for plasma separation	8	Tube for plasma determinations in chemistry
Red	Clot activator	5	Tube for serum determination in chemistry, serology, and immunohematology testing
Orange or Gray/Yellow	Thrombin	8	Tube for stat serum determinations in chemistry. Blood clotting occurs in < 5 min
Royal Blue	Clot activator K_2EDTA, where EDTA = ethylenediaminetetraacetic acid	5 8	Tube for trace-element, toxicology and nutritional chemistry determinations.
Green	Sodium heparin Lithium heparin	8 8	Tube for plasma determination in chemistry
Gray	Potassium oxalate/sodium fluoride Sodium fluoride/Na_2EDTA Sodium fluoride (serum tube)	8 8 8	Tube for glucose determination. Oxalate and EDTA anticoagulants will give plasma samples. Sodium fluoride is the antiglycolytic agent
Tan	K_2EDTA	8	Tube for lead determination. This tube is certified to contain $< 0.01\ \mu g \cdot mL^{-1}$ lead
Lavender	Spray-coated K_2EDTA	8	Tube for whole blood hematology determination and immunohematology testing
White	K_2EDTA with gel	8	Tube for molecular diagnostic test methods such as polymerase chain reaction (PCR) and/or DNA amplification techniques.
Pink	Spray-coated K_2EDTA	8	Tube for whole blood hematology determination and immunohematology test. Designed with special cross-match label for required patient information by the AABB[b]
Light Blue	Buffered sodium citrate (3.2%) Citrate, theophylline, adenosine, dipyridamole (CTAD)	3	Tube for coagulation determinations. The CTAD for selected platelet function assays and routine coagulation determination

[a] Reproduced from Becton Dickinson www.bd.com/vacutainer. Evacuated collection devices made by other manufacturers use similar color coding systems and additives. Recommended inversion times and directions for use are provided by each supplier.

[b] AABB = American Association of Blood Banks.

Gloves: Worn to protect the patient and the phlebotomist. Nonlatex gloves are recommended.

Antiseptics–Disinfectants: 70% isopropyl alcohol or iodine wipes (used if blood culture is to be drawn).

Sterile gauze pads: For application on the site from which the needle is withdrawn.

Bandages: Protects the venipuncture site after collection.

Disposal containers: Needles should never be broken, bent, or recapped. Needles should be placed in a proper disposal unit immediately after use.

Syringe: May be used in place of evacuated collection system in special circumstances.

Permanent marker or pen: To put phlebotomist initials, time, and date of collection on tube as well as any patient identification information not provided by test order label.

BEST SITES FOR VENIPUNCTURE

The most common sites for venipuncture are located in the antecubital (inside elbow) area of the arm (see Fig. 2). The primary vein used is the median cubical vein. The basilica and cephalic veins can be used as a second choice. Although the larger and fuller median cubital and cephalic veins of the arm are used most frequently, wrist and hand veins are also acceptable for venipuncture. Certain areas are to be avoided when choosing site such as; (*1*) Skin areas with extensive scars from burns and surgery (it is difficult to puncture the scar tissue and obtain a specimen); (*2*) the upper extremity on the side of a previous mastectomy (test results may be affected because of lymphedema); (*3*) site of a hematoma (may cause erroneous test results). If another site is not available, collect the specimen distal to the hematoma; (*4*) Intravenous therapy (IV)/blood transfusions (fluid may dilute the specimen, so collect from the opposite arm if possible); (*5*) cannula/fistula/heparin lock (hospitals have special safety and handling policies regarding these devices). In general, blood should not be drawn from an arm with a fistula or cannula without consulting the attending physician; (*6*) edematous extremities (tissue fluid accumulation alters test results).



Figure 2. Venipuncture sites.

ROUTINE PHLEBOTOMY PROCEDURE

Venipuncture is often referred to as “drawing blood”. Most tests require collection of a blood specimen by venipuncture and a routine venipuncture involves the following steps *Note*: The following steps were written using guidelines established by the CLSI/NCCLS (3).

1. **Prepare Order.** The test collection process begins when the physician orders or requests a test to be performed on a patient. All laboratory testing must be requested by a physician and results reported to a physician. The form on which the test is ordered and sent to the lab is called the test requisition. The requisition may be a computer-generated form or a manual form.
2. **Greet and Identify Patient.** Approach the patient in a friendly, calm manner. Identify yourself to the patient by stating you name. Provide for their comfort as much as possible. The most important step in specimen collection is patient identification. When identifying a patient, ask the patient to state their name and date of birth. Outpatients can use an identification card as verification of identity. Even if the patient has been properly identified by the receptionist, the phlebotomist must verify the patient’s ID once the patient is actually called into the blood drawing area. The phlebotomist should ask for two identifiers that match the test requisition form (e.g., name and social security or name and date of birth).
3. **Verify Diet Restrictions and Latex Sensitivity.** Once a patient has been identified, the phlebotomist should verify that the patient has followed any special diet instructions or restrictions. The phlebotomist should also inquire about the patients’ sensitivity to latex.

Assemble Supplies: See the section on Blood Collection System and Equipment

Position Patient

A patient should be either seated or lying down while having blood drawn. The patient’s arm that will be used for the venipuncture should be supported firmly and extended downward in a straight line.

4. **Apply Tourniquet.** A tourniquet is applied to increase pressure in the veins and aid in vein selection. The tourniquet is applied 3–4 in. (7.62–10.18 cm) above the intended venipuncture site. Never leave the tourniquet in place longer than 1 min.

5. **Select a Vein.** Palpate and trace the path of veins in the antecubital (inside elbow) area of the arm with the index finger. Having a patient make a fist will help make the veins more prominent. Palpating will help to determine the size, depth, and direction of the vein. The main veins in the antecubital area are the median cubical, basilica, and cephalic (see the section; Best Sites for Venipucture). Select a vein that is large and well anchored.
6. **Put on Gloves.** Properly wash hands followed by glove application.
7. **Cleanse Venipuncture Site.** Clean the site using a circular motion, starting at the center of the site and moving outward in widening concentric circles. Allow the area to air dry.
8. **Perform Venipuncture.** Grasp patients arm firmly to anchor the vein. Line the needle up with the vein. The needle should be inserted at a 15–30° angle BEVEL UP. When the needle enters the vein, a slight "give" or decrease in resistance should be felt. At this point, using a vacuum tube, slightly, with firm pressure, push the tube into the needle holder. Allow tube to fill until the vacuum is exhausted and blood ceases to flow to assure proper ratio of additive to blood. Remove the tube, using a twisting and pulling motion while bracing the holder with the thumb. If the tube contains an additive, mix it immediately by inverting it 5–10 times before putting it down.
9. **Order of Draw.** Blood tubes are drawn in a particular order to ensure integrity of each sample by lessening the chances of anticoagulants interference and mixing. The order of draw also provide a standardized method for all laboratories (3,4).

Blood Cultures: With sodium polyanethol sulfonate anticoagulant and other supplements for bacterial growth.
Light Blue: Citrate Tube (*Note*: When a citrate tube is the first specimen tube to be drawn, a discard tube should be drawn first). The discard tube should be a nonadditive or coagulation tube.
Gold or Red/Black: Gel Serum Separator Tube, no additive.
Red: Serum Tube, no additive.
Green: Heparin Tube.
Light Green or Green/Gray: Gel Plasma Separator Tube with Heparin.
Lavender: EDTA Tube.
Gray: Fluoride (glucose) Tube.

10. **Release the Tourniquet.** Once blood begins to flow the tourniquet may be released to prevent hemoconcentration.
11. **Place the Gauze Pad.** Fold clean gauze square in half or in fourths and place it directly over the needle without pressing down. Withdraw the needle in one smooth motion, and immediately apply pressure to the site with a gauze pad for 3–5 min, or until the bleeding has stopped. Failure to apply pressure will result in leakage of blood and hematoma formation. Do not bend the arm up, keep it extended or raised.
12. **Remove and Dispose of the Needle.** Needle should be disposed of immediately by placing it and the tube holder in the proper biohazard sharps container. Dispose of all other contaminated materials in proper biohazard containers.
13. **Bandage the Arm.** Examine the patients arm to assure that bleeding has stopped. If bleeding has stopped, apply an adhesive bandage over the site.
14. **Label Blood Collection Tubes.** Specimen tube labels should contain the following information: patient's full name, patient's ID number, date, time, and initials of the phlebotomist must be on each label of each tube.
15. **Send Blood Collection Tube to be Processed.** Specimens should be transported to the laboratory processing department in a timely fashion. Some tests may be compromised if blood cells are not separated from serum or plasma within a limited time.

SPECIMEN PROCESSING

Processing of blood is required in order to separate out the components for screening, diagnostic testing, or for therapeutic use. This section will concentrate primarily on processing of blood for screening purposes and diagnostic testing. An overview of the main blood processing procedures, specimen storage, and common uses for each of the components is provided in Table 2. Because there are many different blood components and many different end uses for these components, the list is not comprehensive and the reader should refer to other specialized literature for further details. The OSHA regulations require laboratory technicians to wear protective equipment (e.g., gloves, labcoat, and protective face gear) when processing specimens. Many laboratories mandate that such procedures are carried out in biosafety cabinets.

Whole Blood Processing

Because whole blood contains all but the active clotting components, it has the ability to rapidly deteriorate and all blood components are subject to chemical, biological, and physical changes. For this reason, whole blood has to be carefully handled and any testing using whole blood has to be performed as soon as possible after collection to ensure maximum stability. Whole blood is typically used for the complete blood count (CBC). The test is used as a broad screening test to check for such disorders as anemia, infection, and many other diseases (www.labtestsonline.org). The CBC panel typically includes measurement of the following: white blood, platelet and red blood cell count, white blood cell differential and evaluation of the red cell compartment by analysis of hemoglobin and hematocrit, red cell distribution width and mean corpuscular volume, and mean corpuscular hemoglobin. The CBC assays are now routinely performed with automated

Table 2. Blood Processing Procedures and Specimen Storage

Component	Processing	Short-Term Storage	Long-Term Storage	Uses
Red blood cells	Gravity and/or centrifigation	~1 month at 4 °C	Frozen up to 10 years	Transfusion
Plasma	Gravity and/or centrifigation	Use immediately	Frozen up to 7 years	Serology, diagnostics, immune monitoring source of biologics
Serum	Clotting and centrifugation	Use immediately	Frozen up to 7 years	Serology, diagnostics, immune monitoring source of biologics
Platelets	Plasma is centrifuged to enrich for platelet fraction	Five days at room temperature	Cannot be cryopreserved	Transfusion
Granulocytes	Centrifigation and separation from red blood cells	Use within 24 h	Cryopreserved in liquid nitrogen[a]	Transfusion
Peripheral blood mononuclear cells	Ficoll–hypaque separation	Use immediately	Cryopreserved in liquid nitrogen[a]	Immune monitoring, specialized expansion and reinfuison
Albumin, immune globulin, specific immune globulins, and clotting factor concentrates	Specialized processing, fractionation and separation	Not applicable	Variable	Multiple therapeutic uses

[a] Although it has been shown that cells can be stored indefinitely in liquid nitrogen, the functionality of the cells would have to be assessed and storage lengths determined for each type of use proposed.

analyzers in which capped evacuated collection devices are mixed and pierced through the rubber cap. Whole blood drawn in EDTA (lavender) tubes are usually used, although citrate (blue top) vacutainers will also work (although the result must be corrected because of dilution). Blood is sampled and diluted, and moves through a tube thin enough that cells pass by one at a time. Characteristics about the cell are measured using lasers or electrical impedance. The blood is separated into a number of different channels for different tests.

The CBC technology has expanded in scope to encompass a whole new field of diagnostics, namely, analytical cytometry. Analytical cytometry is a laser-based technology that permits rapid and precise multiparameter analysis of individual cells and particles from within a heterogeneous population of blood or tissues. Analytical cytometry is now routinely used for diagnosis of different pathological states. This technique can be used to examine cell deoxyribonucleic acid (DNA) and ribonucleic acid (RNA) content, cell-cycle distribution, cellular apoptosis, tumor ploidy, cell function measurements (i.e., oxidative metabolism, phagocytosis), cellular biochemistry (i.e., intracellular pH, calcium mobilization, membrane potential, microviscosity, glutathione content), and fluorescence image analysis of individual blood cells. Since the blood is truly a window on what happens in the body, it is possible to use blood samples for a wide array of diagnostic and research purposes.

A second important use for whole blood is in the setting of HIV infection and treatment as a way to monitor CD4 T cell counts and percentages. These single or multiplatform tests use fresh whole blood with EDTA as anticoagulant ($<$ 18 h after collection) samples are run with or without lysis of red cells and fixation of the lymphocytes. There are several different companies that make specialized equipment for enumeration of CD4 cell counts, the basic principle of which is to use a fluorescently tagged anti CD4 cell surface marker. The results for the CD4 or other subset are expressed as a percentage of total gated lymphocytes. In order to determine the absolute CD4 cell counts, the percent CD4 must be multiplied by an absolute lymphocyte count derived from a hematology analyzer or by an integrated volumetric analysis method (5–7).

Another common use for whole blood is for the detection of secretion of cytokines from antigen or mitogen stimulated lymphocytes. This assay can provide information on a patients T cell response to pathogens [e.g., cytomegalo virus (CMV) and Epstein Ban virus (EBV), HIV, and tuberculosis (TB)]. The technique can also be used to monitor vaccine induced responses or responses to immunotherapy. Whole blood is drawn into heparin, 0.5–1 mL of blood is stimulated with antigen of interest and costimulatory antibodies in the presence of Brefeldin-A. The latter inhibits transport of proteins from the Golgi so that secreted cytokines accumulate inside the cell. The samples are incubated at 37 °C for 6 h, after which they can be placed at 4 °C overnight or processed immediately. The samples are treated with EDTA to reduce clumping, red cells are lysed, and the sample is fixed by addition of paraformaldehyde. At this stage, the samples can be stored frozen for up to 4 months prior to detection of cell surface markers and intracellular cytokines by flow cytometry (8).

Serum Processing

Because of the ease of performing serum separation and the fact that so many tests rely on the use of serum, the technique has become routine in clinical and diagnostic laboratories. Specimens are drawn into tubes that contain no additives or anticoagulants (Table 1). Two commonly used tubes are the red serum collection tubes or commercially available serum separation tubes. Serum is obtained by drawing the blood into a red top or the serum separator tube, allowing it to clot, and centrifuging to separate the serum. The time allowed for clotting depends on the ambient temperature and the patient sample. The typical recommendation is to allow the tube to clot for 20–30 min in a vertical position. A maximum of 1 h should suffice for all samples except those from patients with clotting disorders. Once the clot has formed, the sample is centrifuged for a recommended time of 10 min at 3000 revolutions per minute (rpm). The serum is transferred into a plastic transport tube or for storage purposes into a cryovial. Many tests collected in the serum separator tubes do not require transferring the supernatant serum unless the serum is to be stored frozen. Specimens transported by mail or stored > 4 h should be separated from the clot and placed into a transport tube. Polypropylene plastic test tubes or cryovials are more resistant to breakage than most glass or plastic containers, especially when specimens are frozen. Caution needs to be observed with serum separator tubes for some tests since the analyte of interest may absorb to the gel barrier. Erroneous results may be obtained if the serum or plasma is hemolyzed, lipemic, or icteric. As eloquently described by Terry Kotrla, phlebotomist at Austin Community College these conditions cause specimen problems. (www.austin.cc.tx.us/ kotrla/ PHBLab15SpecimenProcessingSum03.pdf).

1. **Hemolysis** is a red or reddish color in the serum or plasma that will appear as a result of red blood cells rupturing and releasing the hemoglobin molecules. Hemolysis is usually due to a traumatic venipuncture (i.e., vein collapses due to excessive pressure exerted with a syringe, " digging" for veins, or negative pressure damages innately fragile cells. Gross hemolysis (serum or plasma is bright red) affects most lab tests performed and the specimen should be recollected. Slight hemolysis (serum or plasma is lightly red) affects some tests, especially serum potassium and LDH (lactate dehydrogenase). Red blood cells contain large amounts of both of these substances and hemolysis will falsely elevate their measurements to a great extent. In addition to hemolysis caused during blood draw procedures, blood collection tubes (for serum and or whole blood) that are not transported correctly or in a timely fashion to the processing laboratory may be subject to hemolysis. Extremes of heat and cold in particular can cause red blood cells to lyze and sheering stresses caused by shaking of the specimens during transport may cause lysis. Finally, incorrect centrifugation temperatures and speeds may cause hemolysis of red blood cells.
2. **Icterus**. Serum or plasma can be bright yellow or even brownish due to either liver disease or damage or excessive red cell breakdown inside the body. Icterus can, like hemolysis, affect many lab tests, but unfortunately, recollection is not an option since the coloration of the serum or plasma is due to the patient's disease state.
3. **Lipemia**. Occasionally, serum or plasma may appear milky. Slight milkiness may be caused when the specimen is drawn from a nonfasting patient who has eaten a heavy meal. A thick milky appearance occurs in rare cases of hereditary lipemia.

Both for serum and plasma there are documented guidelines for specimen handling dependent on which analyte, is being examined. The kinds of tests that can be done on blood samples is ever expanding and includes allergy evaluations, cytogenetics, cytopathology, histopathology, molecular diagnostics, tests for analytes, viruses, bacteria, parasites, and fungi. Incorrect preparation, shipment, and storage of specimens may lead to erroneous results. The guidelines for preparing samples can be obtained from the CLSI (9). Diagnostic testing laboratories (e.g., Quest diagnostics) provide comprehensive lists of the preferred specimen type, transport temperature, and rejection criteria (www.questest.com).

Plasma Processing

Specimens are drawn into tubes that contain anticoagulant (Table 1.). The plasma is obtained by drawing a whole blood specimen with subsequent centrifugation to separate the plasma. Plasma can be obtained from standard blood tubes containing the appropriate anticoagulant or from commercially available plasma separation tubes. The plasma separation tubes combine spray-dried anticoagulants and a polyester material that separates most of the erythrocytes and granulocytes, and some of the lymphocytes and monocytes away from the supernatant. The result is a convenient, safe, single-tube system for the collection of whole blood and the separation of plasma. Samples can be collected, processed, and transported *in situ* thereby reducing the possibility of exposure to bloodborne pathogens at the collection and sample processing sites. One drawback is that plasma prepared in a plasma separation tube may contain a higher concentration of platelets than that found in whole blood. For plasma processing, after drawing the blood, the tube for plasma separation must be inverted five to six times to ensure adequate mixing and prevent coagulation. The recommended centrifugation time is at least 10 min at 3000 rpm. Depending on the tests required, plasma specimens may be used immediately, shipped at ambient or cooled temperatures, or may require freezing. The plasma is transferred into a plastic transport tube or for storage purposes into a cryovial. Some tests require platelet poor plasma, in which case the plasma is centrifuged at least two times.

Processing and Collection of Peripheral Blood Mononuclear Cells (PBMC) from Whole Blood

Peripheral blood mononuclear cells are a convenient source of white blood cells, T cells comprise $\sim 70\%$ of the white cell compartment and are the work-horses of the immune system. These T cells play a crucial role in protection from or amelioration of many human diseases and can keep tumors in check. The most readily accessible source of T cells is the peripheral blood. Thus collection, processing, cryopreservation, storage, and manipulation of human PBMC are all key steps for assessment of vaccine and disease induced immune responses. The assessment of T cell function in assays may be affected by procedures beginning with the blood draw through cell separation, cryopreservation, storage, and thawing of the cells prior to the assays. Additionally, the time of blood collection to actual processing for lymphocyte separation is critical. Procedures for PBMC collection and separation are shown in Table 3 along with potential advantages and disadvantages.

When conducting cellular immunology assays, the integrity of the PBMC, especially the cellular membranes, is critical for success. A correct cellular separation process yields a pure, highly viable population of mononuclear cells consisting of lymphocytes and monocytes, minimal red blood cell and platelet contamination, and optimum functional capacity. The standard method for separation of PBMC is the use of Ficoll-hypaque gradients as originally described by Boyum in 1968 (10). A high degree of technical expertise is required to execute the procedure from accurate centrifuge rpm and careful removal of the cellular interface to avoid red cell contamination. Within the last 10 years, simplified separation ficoll procedures have largely replaced the standard ficoll method, two such procedures are outlined below (Adapted from Ref. 11) and in Fig. 3. The simplicity of these methods, superior technical reliability, reduced interperson variability, faster turnaround, and higher cell yields makes these the methods of choice.

The Cell Preparation Tube (CPT) method is described below and in greater detail in literature provided by Becton Dickinson (http://www.bd.com/vacutainer/products/molecular/citrate/procedures.asp). Vacutainer cell preparation tubes (VACUTAINER CPT tubes, Becton Dickinson) provide a convenient, single-tube system for the collection and separation of mononuclear cells from whole blood. The CPT tube is convenient to use and results in high viability of the cells after transportation. The blood specimens in the tubes can be transported at ambient temperature, as the gel forms a stable barrier between the anticoagulated blood and ficoll after a single centrifuge step. Cell separation is performed at the processing–storage laboratory using a single centrifugation step. This reduces the risk of sample contamination and eliminates the need for additional tubes and processing reagents. In many instances, and in particular when biosafety level 2 (BL2) cabinets are not available on site, the CPT method is useful because the centrifugation step can be done on site and the remaining processing steps can be performed after shipment to a central laboratory within the shortest time possible, optimally within 8 h. The central laboratory can complete cell processing in a BL2 cabinet and set up functional assays or cryopreserve the samples as needed.

Centrifuge speed is critical for PBMC processing. The centrifugal force is dependent on the radius of the rotation of the rotor, the speed at which it rotates, and the design of the rotor itself. Centrifugation procedures are given as xg measures, since rpm and other parameters will vary with the particular instrument and rotor used. The rpms may be calculated using the following formula where r = radius of rotor g = gravity; $g = 1.12\, r\, (\mathrm{rpm}/1000)^2$. This conversion can be read-off a nomogram chart available readily online or in centrifuge maintenance manuals. Typically laboratory centrifuges can be programmed to provide the correct rpm.

Protocol 1. Separation of PBMC Using CPT Tubes

1. **Materials and Reagents:** Vacutainer CPT tubes (Becton Dickinson); Sterile Phosphate Buffered Saline (PBS) without Ca^+ and Mg^+, supplemented with antibiotics (Penicillin and Streptomycin); Sterile RPMI media containing 2% fetal bovine serum (FBS) and supplemented with antibiotics.

   The CPT tubes are sensitive to excessive temperature fluctuations, resulting in deterioration of the gel and impacting successful cellular separation. This problem is particularly serious in tropical countries where ambient storage temperatures may be $> 25\,^{\circ}C$. Following PBMC separation, one

Table 3. Stages and Variables in the Separation of PBMC from Whole Blood

Procedure/Technology	Alternatives	Advantages	Disadvantages
PBMC collection	Heparin	Greater cellular stability than EDTA	Impacts DNA isolation. Plasma from whole blood cannot be used for PCR based assays[a]
	EDTA		Time dependent negative impact on T cell responses
	Sodium Citrate	Greater cellular stability than EDTA	
PBMC separation	Standard Ficoll		Technically challenging Time consuming
	CPT	Rapid Technically easy and less inter-person variability Blood is drawn into same tube that is used for separation	Subject to temperature fluctuations manifested by gel deterioration and contamination in PBMC fraction.
	Accuspin/Leucosep	Rapid Technically easy and less inter-person variability	

[a] The inhibitory effects of heparin on DNA isolation can be removed by incubation of plasma or other specimens with silicon glass beads or by heparinase treatment prior to DNA extraction.


A
Step 1: Overlay Fresh, Dilute Anticoagulated Whole Blood
Whole Blood
Ficoll Hypaque
5 minutes
Step 2: Centrifuge
400g for 30 minutes no brake
45 minutes
Step 3: Remove Plasma and PBMC
Plasma
PBMC
Ficoll Hypaque
RBC and Granulocytes
Store
Remove
Discarded
Total Time = 50–60 minutes
B
Step 1: Pour Fresh Anticoagulated Whole Blood
Whole Blood
Frit
Ficoll Hypaque
1 minutes
Step 2: Centrifuge
1000g for 15 minutes
15 minutes
Step 3: Remove Plasma and PBMC
Plasma
PBMC
Ficoll Hypaque
Frit
RBC and Granulocytes
Store
Remove
Discarded
Total Time = 16–20 minutes

Figure 3. Gradient separation of peripheral blood mononuclear lymphocytes (PBMC). (a) The standard ficoll gradient method. (b) The Accuspin or Leucosep method. RBC = red blood cells, g = gravity. (Graphic courtesy of Greg Khoury and Clive Gray, National Institute for Communicable Diseases, Johannesburg, South Africa.)

may macroscopically observe the presence of gel spheres in the cellular layer, which are very difficult to distinguish from the actual PBMC. This has been observed after storage at temperatures $> 25\,^{\circ}$C. Where possible, the tubes should be stored at no $> 25\,^{\circ}$C. Once the tubes have blood drawn into them, an attempt should be made to keep them at temperatures of between 18 and 25 °C. Blood filled CPT should under no circumstances be stored on ice or next to an ice pack. It is recommended that they are separated from any ice-packs by bubble wrap or other type of insulation within a cooler so that the temperature fluctuations are kept to a minimum.

2. **Method:** (a) Specimens should be transported to the laboratory as soon as possible after collection. The manufacturer recommends the initial centrifugation to separate the lymphocytes be within 2 h. The samples may then be mixed by inversion and the processing completed preferably within 8 h after centrifugation. If there is a significant time delay, the specimens should be put into a cooler box and transported at room temperature (18–25 °C). (b) Spin tubes at room temperature (18–25 °C) in a horizontal rotor (swinging bucket head) for a minimum of 20 min and maximum of 30 min at $\sim 400\,g$. The brake is left off to assure that the PBMC layer is not jarred or disturbed while the centrifuge rotors are being mechanically halted. (c) Remove the tubes from the centrifuge and pipete the entire contents of the tube above the gel into a 50 mL tube. This tube will now contain both PBMC and undiluted plasma. An additional centrifugation step will allow removal of undiluted plasma if desired. Wash each CPT tube with 5 mL of PBS/1% Penicillin/Streptomycin (Pen/Strep). This wash step will remove cells from the top of the gel plug. Combine with cells removed from tube. This wash increases yield of cells by as much as 30–40%. (d) Spin down this tube at $300\,g$ for 15–20 min at room temperature with the brake on. (e) The PBMC pellet is resuspended in RPMI, 2% FBS and washed one more time to remove contaminating platelets. The PBMC are counted and cryopreserved or used as required.
3. **Separation of PBMC Using Accuspin or Leucosep Tubes.** More recently, the Leucosep and Accuspin tube have become available. Further information on the Leucosep is available at www.gbo.com and for the Accuspin at www.sigmaaldrich.com The principle of these tubes is the

same. The tube is separated into two chambers by a porous barrier made of highly transparent polypropylene (the frit). This biologically inert barrier allows elimination of the laborious overlaying of the sample material over Ficoll. The barrier allows separation of the sample material added to the top from the separation medium (ficoll added to the bottom). Figure 3 shows a comparison of the standard ficoll method and the Accuspin or Leucosep method. The tubes are available in two sizes and may be purchased with or without Ficoll. There is an advantage of buying the tubes without Ficoll because they can be stored at room temperature rather than refrigerated. This may be an important problem if cold space is limiting or cold chain is difficult. The expiration date of the Ficoll will not affect the tube expiration. The following procedure describes the separation procedure for Leucosep tubes that are not prefilled with Ficoll-hypaque. The Accuspin procedure is virtually identical. Note that whole blood can be diluted 1:2 with balanced salt solution. While this dilution step is not necessary, it can improve the separation of PBMC and enhance PBMC yield. The procedure is carried out using aseptic technique.

Protocol 2: Separation of PBMC Using Accuspin or Leucosep Tubes

1. Warm-up the separation medium (Ficoll-hypaque) to room temperature protected from light.
2. Fill the Leucosep tube with separation medium: 3 mL for the 14 mL tube and 15 mL for the 40 mL tube.
3. Close the tubes and centrifuge at 1000*g* for 30 s at room temperature.
4. Pour the whole blood or diluted blood into the tube: 3–8 mL for the 14 mL tube and 15–30 mL for the 50 mL tube.
5. Centrifuge for 10 min at 1000*g* or 15 min at 800*g* in a swinging bucket rotor, with the centrifuge brake off. The brake is left off to assure that the PBMC layer is not jarred or disturbed while the centrifuge rotors are being mechanically halted.
6. After centrifugation, the sequence of layers from top to bottom should be plasma and platelets; enriched PBMC fraction; Separation medium; porous barrier; Separation medium; Pellet (erythrocytes and granulocytes).
7. Plasma can be collected to within 5–10 mm of the enriched PBMC fraction and further processed or stored for additional assays.
8. Harvest the enriched PBMC and wash with 10 mL of PBS containing 1% Pen/Strep and centrifuge at 250*g* for 10 min.
9. The PBMC pellet is resuspended in RPMI, 2% FBS and washed one more time to remove contaminating platelets. The PBMC are counted and cryopreserved or used as required.

1. **Specimen Rejection Criteria**

Incomplete or inaccurate specimen identification.

Inadequate volume of blood in additive tubes (i.e., partially filed coagulation tube) can lead to inappropriate dilution of addition and blood.

Hemolysis (i.e., potassium determinations)

Specimen collected in the wrong tube (i.e., end product is serum and test requires plasma).

Improper handling (i.e., specimen was centrifuged and test requires whole blood).

Insufficient specimen or quantity not sufficient (QNS).

For PBMC, the rejection criteria are not usually evaluated at the time of draw due to the complexity of the tests performed. However, a minimum of 95% viability would be expected after PBMC separation unless the specimens have been subjected to heat or other adverse conditions (see note below).

The optimal time frame between collection of blood sample to processing, separation and cryopreservation of PBMC should be < 8 h or on the same day as collection. It is not always feasible to process, separate and cryopreserve PBMC within 8 h when samples are being shipped to distant processing centers. Under these conditions, PBMC left too long in the presence of anticoagulants or at noncompatible temperatures, adversely affect PBMC function and causes changes which affect the PBMC separation process (11).

There have been significant revisions to the procedures for the handling and processing of blood specimens; specimens for potassium analysis should not be recentrifuged because centrifugation may cause results to be falsely increased; the guidelines recommend that serum or plasma exposed to cells in a blood-collection tube prior to centrifugation should not exceed 2 h; storage recommendations for serum–plasma may be kept at room temperature up to 8 h, but for assays not completed within 8 h, refrigeration is recommended (2–8 °C), if the assay is not completed within 48 h serum–plasma should be frozen at or below −20 °C.

2. **Disclaimer.** The opinions or assertions contained herein are the private views of the author, and are not to be construed as official, or as reflecting true views of the Department of the Army or the Department of Defense.

BIBLIOGRAPHY

Cited References

1. McCall RE, Tankersley CM. Phlebotomy Essentials. Philadelphia: J.B. Lippincott; 1993.
2. Ernst DJ, Szamosi DI. 2005. Medical Laboratory Observer Clinical Laboratory, Specimen-collection standards complete major revisions, Available at www.mlo-online.com, Accessed 2005 Feb.
3. Arkin CF, et al. Procedures for the Collection of Diagnostic Blood Specimens by Venipuncture; CLSI (NCCLS) Approved

Standard – 5th ed. H3-A5, Vol 23, Number 32. NCCLS, Wayne (PA).

4. Becton, Dickinson and Company. 2004, BD Vacutainer Order of Draw for Multiple Tube Collections. Available at www.bd.com/vacutainer.
5. Centers for Disease Control and Prevention (CDC). Revised Guidelines for performing CD4+ T-cell determinations in persons infected with human immunodeficiency virus (HIV). MMWR. 1997;46(No.RR-2):1–29.
6. Deems D, et al. 1994, FACSCount White paper. Becton Dickenson. Available at www.bdbiosciences.com/immunocytometrysystems/ whitepapers/pdf/FcountWP.pdf.
7. Dieye TN, et al. Absolute CD4 T-Cell Counting in Resource-Poor Settings: Direct Volumetric Measurements Versus Bead-Based Clinical Flow Cytometry Instruments. J Acquir Immune Defic Syndr 2005;39:32–37.
8. Maino VC, Maecker HT. Cytokine flow cytometry: a multiparametric approach for assessing cellular immune responses to viral antigens. Clin Immunol. 2004;110:222–231.
9. Wiseman JD et al. Procedures for the Handling and Processing of Blood Specimens; CLSI (NCCLS) Approved Guideline. 2nd ed. H18-A2. Vol. 19 Number 21. 1999. NCCLS, Wayne, PA
10. Boyum A. Isolation of mononuclear cells and granulocytes from human blood. Scand J Clin Lab Invest 1968;21:77–89.
11. Cox J et al. Accomplishing cellular immune assays for evaluation of vaccine efficacy. In: Hamilton RG, Detrich B, Rose NR; Manual Clinical Laboratory Immunology 6th ed. Washington (DC): ASM Press; 2002. Chapt. 33. pp 301–315.

See also Analytical methods, automated; cell counters, blood; differential counts, automated.

BLOOD FLOW.

See Blood rheology; hemodynamics.

BLOOD GAS MEASUREMENTS

Ahmad Elsharydah
Randall C. Cork
Louisiana State University
Shreveport, Louisiana

INTRODUCTION

Blood gas measurement–monitoring is essential to monitor gas exchange in critically ill patients in the intensive care units (1,2), and "standard of care" monitoring to deliver general anesthesia (3). It is a cornerstone in the diagnosis and management of the patient's oxygenation and acid–base disorders (4). Moreover, it may indicate the onset or culmination of cardiopulmonary problems, and may help in evaluating the effectiveness of the applied therapy. Numerous studies and reports have shown the significance of utilizing blood gas analyses in preventing serious oxygenation and acid–base problems. This article gives a summarized explanation of the common methods and instruments used nowadays in blood gas measurements in clinical medicine. This explanation includes a brief history of the development of these methods and instruments, the principles of their operation, a general description of their designs, and some of their clinical uses, hazards, risks, limitations, and finally the direction in the future to improve these instruments or to invent new ones. Blood gas measurement in clinical medicine can be classified into two major groups: (1) Noninvasive blood gas measurement, which includes blood oxygen–carbon dioxide measurement–monitoring by using different types of pulse oximeters (including portable pulse oximeters), transcutaneous oxygen partial pressure–carbon dioxide partial pressure ($P\text{O}_2$/$P\text{CO}_2$) monitors, intrapartum fetal pulse oximetry, cerebral oximetry, capnometry, capnography, sublingual capnometry, and so on; (2) invasive blood gas measurement, which involves obtaining a blood sample to measure blood gases by utilizing blood gas analyzers (in a laboratory or by using a bedside instrument), or access to the vascular system to measure/monitor blood gases. Examples include, but not limited to, mixed venous oximetry ($S\text{vO}_2$) monitoring by utilizing pulmonary artery catheter or jugular vein ($S\text{vO}_2$) measurement (5); continuous fibroptic arterial blood gas monitoring, and so on. In this article, we will talk about some of these methods; others have been mentioned in other parts of this encyclopedia.

BASIC CONCEPTS IN INVASIVE AND NONINVASIVE BLOOD GAS MEASUREMENTS

The Gas Partial Pressure

Gases consist of multiple molecules in rapid, continuous, random motion. The kinetic energy of these molecules generate a force as the molecules collide with each other and bounce from one surface to another. The force per unit area of a gas is called pressure, and can be measured by a device called a manometer. In a mixture of gases (e.g., a mixture of O_2, CO_2, and water vapor), several types of gas molecules are present within this mixture, and each individual gas (e.g., O_2 or CO_2) in the mixture is responsible for a portion of the total pressure. This portion of pressure is called partial pressure (P). According to Dalton's law, the total pressure is equal to the sum of partial pressures in a mixture of gases. Gases dissolve freely in liquids, and may or may not react with the liquid, depending on the nature of the gas and the liquid. However, all gases remain in a free gaseous phase to some extent within the liquid. Gas dissolution in liquids is a physical, not chemical, process. Therefore, gases (e.g., CO_2, O_2) dissolved in liquid (blood) exist in two phases: liquid and gaseous phase. Henry's law states that the partial pressure of a gas in the liquid phase equilibrates with the partial pressure of that gas in the gaseous phase (6,7).

BLOOD GAS ELECTRODES

Basic Electricity Terms

Electricity is a form of energy resulting from the flow of electrons through a substance (conductor). Those electrons flow from a negatively charged pole called Cathode, which has an excess of stored electrons, to a positively charged pole called Anode, which has a relative shortage of electrons. The potential is the force responsible for pumping these electrons between the two poles. The greater the difference in electron concentration between these two poles, the greater is the potential. Volt is the potential measurement unit. The electrical current is the actual flow of electrons through a conductor. Ampere (amp) is the unit of measurement for the electrical current. Conductors display different degree of electrical resistance to the flow of the electrical current. The unit of the electrical resistance is ohm (Ω). Ohm's law states: voltage = current × resistance.

The Principles of Blood Gas Electrodes

Blood gas electrodes are electrochemical devices used to measure directly pH and blood gases. These blood gas electrodes use electrochemical cells. The electrochemical cell is an apparatus that consists of two electrodes placed in an electrolyte solution. These cells usually incorporated together (one or more cells) to form an electrochemical cell system. These systems are used to measure specific chemical materials (e.g., PO_2, PCO_2 and pH). The basic generic blood gas electrode consists of two electrode terminals, which are also called half-cells: one is called the working half-cell where the actual chemical analysis occurs, or electrochemical change is taken place; and the other one is called the reference half-cell. The electrochemical change occurring on the working terminal is compared to the reference terminal, and the difference is proportional to the amount of blood gas in the blood sample (6,7).

PO_2 Electrode

The PO_2 electrode basically consists of two terminals (1). The cathode, which usually made of platinum (negatively charged) and (2) the anode, which usually made of silver–sliver chloride (positively charged). How does this unit measure PO_2 in the blood sample? As shown in Fig. 1, the electricity source (battery or wall electricity) supplies the platinum cathode with energy (voltage of ~700 mV). This voltage attracts oxygen molecules to the cathode surface, where they react with water. This reaction consumes four electrons for every oxygen molecule reacts with water and produces four hydroxyl ions. The consumed four electrons, in turn, are replaced rapidly in the electrolyte solution as silver and chloride react at the anode. This continuous reaction leads to continuous flow of electrons from the anode to the cathode (electrical current). This electrical current is measured by using an ammeter (electrical current flow meter). The current generated is in direct proportion to the amount of dissolved oxygen in the blood sample, which in direct proportion to PO_2 in that sample.

Oxygen Polarography

The electrical current and PO_2 have a direct (linear) relationship when a specific voltage is applied to the cathode. Therefore, a specific voltage must be identified, to be used in PO_2 analysis. The polarogram is a graph that shows the relationship between voltage and current at a constant PO_2. As shown in Fig. 2, when the negative voltage applied to the cathode is increased, the current increases initially, but soon it becomes saturated. In this plateau region of the polarogram, the reaction of oxygen at the cathode is so fast that the rate of reaction is limited by the diffusion of oxygen to the cathode surface. When the negative voltage is further increased, the current output of the electrode increases rapidly due to other reactions, mainly, the reduction of water to hydrogen. If a fixed voltage in the plateau region (e.g., −0.7 V) is applied to the cathode, the current output of the electrode can be linearly calibrated to the dissolved oxygen. Note that the current is proportional not to the actual concentration, but to the activity or equivalent partial pressure of dissolved oxygen. A fixed voltage between −0.6 and −0.8 V is usually selected as the



Figure 1. PO_2 electrode.



Figure 2. Polarogram.

polarization voltage when using Ag/AgCl as the reference electrode.

pH Electrode

The pH electrode uses voltage to measure pH, rather than actual current as in PO_2 electrode. It compares a voltage created through the blood sample (with unknown pH) to known reference voltage (in a solution with known pH). To make this possible, the pH electrode basically needs four electrode terminals (Fig. 3), rather than two terminals (as in the PO_2 electrode). Practically, one common pH-sensitive glass electrode terminal between the two solutions is adequate. This glass terminal allows the hydrogen ions to diffuse into it from each side. The difference in the hydrogen ions concentration across this glass terminal creates a net electrical potential (voltage). A specific equation is used to calculate the blood sample pH, using the reference fluid pH, the created voltage, and the fluid temperature.

PCO_2 Electrode

The PCO_2 electrode is a modified pH electrode. There are two major differences between this electrode and the pH electrode. The first difference is that in this electrode, the blood sample comes in contact with a CO_2 permeable membrane (such as Teflon, Silicone rubber), rather than a pH-sensitive glass (in the pH electrode), as shown in Fig. 4. The CO_2 from the blood sample diffuses via the CO_2 permeable (silicone) membrane into a bicarbonate solution. The amount of the hydrogen ions produced by the hydrolysis process in the bicarbonate solution is proportional to the amount of the CO_2 diffused through the silicone membrane. The difference in the hydrogen ions concentration across the pH-sensitive glass terminal creates a voltage. The measured voltage (by voltmeter) can be converted to PCO_2 units. The other difference is that the CO_2 electrode has two similar electrode terminals (silver–silver chloride). However, the pH electrode has two different electrode terminals (silver–silver chloride and mercury–mercurous chloride).

BLOOD GAS PHYSIOLOGY (8,9)

Oxygen Transport

Oxygen is carried in the blood in two forms: A dissolved small amount and a much bigger, more important component combined with hemoglobin. Dissolved oxygen plays a small role in oxygen transport because its solubility is so low, 0.003 mL O_2/100 mL blood per mmHg (133.32 Pa). Thus, normal arterial blood with a PO_2 of ~100 mmHg (13332.2 Pa) contains only 0.3 mL of dissolved oxygen per 100 mL of blood, whereas ~20 mL is combined with hemoglobin. Hemoglobin consists of heme, an iron–porphyrin compound, and globin, a protein that has four polypeptide chains. There are two types of chains, alpha and beta, and differences in their amino acid sequences give rise to different types of normal and abnormal human hemoglobin, such as, hemoglobin F (fetal) in the newborn, and hemoglobin S in the sickle cell anemia patient. The combination of oxygen (O_2) with hemoglobin (Hb) (to form oxyhemoglobin–HbO_2) is an easily reversible. Therefore, blood is able to transport large amounts of oxygen.

The relationship between the partial pressure of oxygen and the number of binding sites of the hemoglobin that have oxygen attached to it, is known as the oxygen dis-



Figure 3. pH electrode.


VOLTMETER
AMPLIFIER
Common pH-sensitive glass electrode terminal
Ag/AgCl half-cell
Ag/AgCl half-cell
Reference solution with known pH
Bicarbonate solution
H^+
H^+
H^+
H^+
$H^+ + HCO_3^- \leftarrow H_2CO_3 \leftarrow H_2O + CO_2$
Silicone membrane
Blood
CO_2

Figure 4. PCO_2 electrode.

sociation curve (Fig. 5). Each gram of pure hemoglobin can combine with 1.39 mL of oxygen, and because normal blood has ~15 g Hb/100 mL, the oxygen capacity (when all the binding sites are full) is ~20.8 mL O_2/100 mL blood. The total oxygen concentration of a sample of blood, which includes the oxygen combined with Hb and the dissolved oxygen, is given by $(Hb \times 1.36 \times SaO_2) + (0.003 \times PaO_2)$ Hb is the hemoglobin concentration.

The characteristic shape of the oxygen dissociation curve has several advantages. The fact that the upper portion is almost flat means that a fall of 20–30 mmHg in arterial PO_2 in a healthy subject with an initially normal value (e.g., ~100 mmHg or 13332.2 Pa) causes only a minor reduction in arterial oxygen saturation. Another consequence of the flat upper part of the curve is that loading of oxygen in the pulmonary capillary is hastened. This results from the large partial pressure difference between alveolar gas and capillary blood that continues to exist even when most of the oxygen has been loaded. The steep lower part of the oxygen dissociation curve means that considerable amounts of oxygen can be unloaded to the peripheral tissues with only a relatively small drop in capillary PO_2. This maintains a large partial pressure difference between the blood and the tissues, which assists in the diffusion process. Various factors affect the position of the oxygen dissociation curve, as shown in Fig. 5. It is shifted to the right by an increase of temperature, hydrogen ion concentration, PCO_2, and concentration of 2,3-diphosphoglycerate in the red cell. A rightward shift indicates that the affinity of oxygen for hemoglobin is reduced. Most of the effect of the increased PCO_2 in reducing the oxygen affinity is due to the increased hydrogen concentration. This is called the Bohr effect, and it means that as peripheral blood loads carbon dioxide, the unloading of oxygen is assisted. A useful measure of the position of the dissociation curve is the PO_2 for 50% oxygen saturation; this is known as the $P50$. The normal value for human blood is ~27 mmHg (3599.6 Pa).

Carbon Dioxide Transport

Carbon dioxide is transported in the blood in three forms: dissolved, as bicarbonate, and in combination with proteins such as carbamino compounds (Fig. 6). Dissolved carbon dioxide obeys Henry's law (as mentioned above). Because carbon dioxide is some 24 times more soluble than oxygen in blood, dissolved carbon dioxide plays a much more significant role in its carriage compared to oxygen. For example, ~10% of the carbon dioxide that evolves into the alveolar gas from the mixed venous blood comes from the dissolved form. Bicarbonate is formed in blood by the following hydration reaction:

$$CO_2 + H_2O \leftrightarrow H_2CO_3 \leftrightarrow H^+ + HCO_3^-$$

The hydration of carbon dioxide to carbonic acid (and vice versa) is catalyzed by the enzyme carbonic anhydrase (CA), which is present in high concentrations in the red cells, but is absent from the plasma. However, some carbonic anhydrase is apparently located on the surface of the endothelial cells of the pulmonary capillaries. Because of the presence of carbonic anhydrase in the red cell, most of the hydration of



Figure 5. Oxygen dissociation curve and the effects of different factors on it.


CO_2
Tissue
Blood
5–10% CO_2 in physical solution
20–30% CO_2 bound to proteins
60–70%
plasma protein albumin
CO_2 chemically converted to HCO_3^-
RBC
HCO_3^- travels to lung capillaries in plasma

Figure 6. Carbon dioxide transport in blood.

carbon dioxide occurs there, and bicarbonate ion moves out of the red cell to be replaced by chloride ions to maintain electrical neutrality (chloride shift). Some of the hydrogen ions formed in the red cell are bound to Hb, and because reduced Hb is a better proton acceptor than the oxygenated form, deoxygenated blood can carry more carbon dioxide for a given PCO_2 than oxygenated blood can. This is known as the Haldane effect. Carbamino compounds are formed when carbon dioxide combines with the terminal amine groups of blood proteins. The most important protein is the globin of hemoglobin. Again, reduced hemoglobin can bind more carbon dioxide than oxygenated hemoglobin, so the unloading of oxygen in peripheral capillaries facilitates the loading of carbon dioxide, whereas oxygenation has the opposite effect. The carbon dioxide dissociation curve, as shown in Fig. 7, is the relationship between PCO_2 and total carbon dioxide concentration. Note that the curve is much more linear in its working range than the oxygen dissociation curve, and also that, as we have seen, the lower the saturation of hemoglobin with oxygen, the larger the carbon dioxide concentration for a given PCO_2.



Figure 7. The carbon dioxide dissociation curve showing the effect of PO_2 variations.

OXIMETRY

Historical Development

Oximetry has its origins in the early 1860s (10), when Felix Hoppe-Seyler described the hemoglobin absorption of light using the spectroscope. He demonstrated that the light absorption was changed when blood was mixed with oxygen, and that hemoglobin and oxygen formed a compound called oxyhemoglobin. Soon after, George Gabriel Stokes reported that hemoglobin was in fact the carrier of oxygen in the blood. In 1929, Glen Allan Millikan (11), an American physiologist, began construction of a photoelectric blood oxygen saturation meter, which, used to measure color changes over time when desaturated hemoglobin solutions were mixed with oxygen solutions in an experimental setting. The use of photoelectric cells later proved to be crucial to the development of oximeters. In 1935, Kurt Kramer demonstrated, for the first time, *in vivo* measurement of blood oxygen saturation in animals. The same year, Karl Matthes introduced the ear oxygen saturation meter. This was the first instrument able to continuously monitor blood oxygen saturation in humans. In 1940, J.R. Squire introduced a two-channel oximeter that transmitted red and infrared (IR) light through the web of the hand. In 1940, Millikan and colleagues developed a functioning oximeter, and introduced the term "oximeter" to describe it. The instrument used an incandescent, battery-operated light and red and green filter. In 1948, Earl Wood of the Mayo Clinic made several improvements to Millikan's oximeter, including the addition of a pressure capsule. Then, in the 1950s, Brinkman and Zijlstra of the Netherlands developed the reflectance oximetry. However, oximetry did not fully achieve clinical applicability until the 1970s.

Principles of Operation

It is important to understand some of the basic physics principles that led to the development of oximetry and pulse oximetry. This is a summary of these different physics principles and methods (7,12).

Spectrophotometry. The spectroscope is a device which was used initially to measure the exact wavelengths of light emitted from a light generator (bunsen burner) (10). Each substance studied with the spectroscope has its unique light emission spectrum, in other words, each substance absorbed and then emitted light of different wavelengths. The graph of the particular pattern of light absorption–emission of sequential light wavelengths called the absorption spectrum. Figure 8 reveals the absorption spectra of common forms of hemoglobin.

Colorimetry. Colorimetry is another method of qualitative analysis (10). In this method, the color of known substance is compared of that of unknown one. This method is not highly exact, because it depends on visual acuity and perception.

Photoelectric Effect. The photoelectric effect is the principle behind spectrophotometry. It is defined as the ability of light to release electrons from metals in proportion to the



Figure 8. Absorption spectra of common forms of hemoglobin. Absorption spectra of oxyhemoglobin, deoxyhemoglobin, methemoglobin, carboxyhemoglobin.



Figure 9. Major components of transmission and reflection oximeters.

intensity of the light. In spectrophotometry, light passes via a filter that converts the light into a specific wavelength. This light then passes through a container that contains the substance being analyzed. This substance absorbs part of this light and emits the remaining part, which goes through a special cell. This cell is connected to a photodetector, which detects and measures the emitting light (spectrophotometry). This method can be used for quantitive as well as qualitative analyses.

Lambert–Beer Law. This law combines the different factors that affect the light absorption of a substance:

$$\log 10 I_o/I_x = kcd$$

I_o = intensity of light incident on the specimen

I_x = intensity of the transmitted light

I_o/I_x = optical density

As shown in the above formula, the concentration of absorbing substance, the path length of the absorbing medium (d) and the characteristics of the substance and the light wavelength (k = constant) all affect light absorption (12).

Transmission Versus Reflection Oximetry. When the light at a particular wavelength passes through a blood sample, which contains Hb, this light would be absorbed, transmitted, or reflected. The amount of the absorbed, transmitted, or reflected light at those particular wavelengths is determined by various factors, including the concentration (Lambert–Beer law) and the type of the Hb present in the blood sample. The amount of light transmitted through the blood sample at a given wavelength is related inversely to the amount of light absorbed or reflected. The transmission oximetry is a method to determine the arterial oxygen saturation (S_aO_2) value by measuring the amount of light transmitted at certain wavelengths. On the other side, in the reflection oximetry, measuring the amount of light reflected is used to determine the S_aO_2 value. The significant difference between these two methods is the location of the photodetecor (Fig. 9). In the reflection method, the photodetector is on the same side of the light source. However, in the transmission oximetry, it is on the opposite site side of the light source (7,12).

Oximetry Versus Cooximetry. Each form of hemoglobin (e.g., oxyhemoglobin, deoxygenated hemoglobin, carboxyhemoglobin, methemoglobin) has its own unique absorption–transmission–reflection spectrum. By plotting the relative absorbance to different light wavelengths for both oxyhemoglobin and deoxygenated Hb as shown in Fig. 10. It is clear that these two hemoglobins absorb light differently at different light wavelengths. This difference is big in some light wavelengths (e.g., 650 nm in the red region), and small or not existing in other light wavelengths. The isosbestic point (13) is the light wavelength at which there is no difference between these two hemoglobins in absorbing light (~ 805 nm near the IR region). The difference in these two wavelengths can be used to calculate the S_aO_2.



Figure 10. Light absorption spectra of oxygenated and deoxygenated hemoglobin.

However, these two hemoglobins are not only the hemoglobins exist in the patient's blood. There are other abnormal hemoglobins (dyshemoglobins) that can join these two hemoglobins in some abnormal conditions (such as carboxyhemoglobin and methemoglobin). Each one of these dyshemoglobins has its unique transmission–reflection–absorption spectrum. Some of these spectra are very close to the oxyhemoglobin spectrum at the routinely used two light wavelengths (see above). This makes these two wavelengths are incapable in detecting those dyshemoglobins. Therefore, the use of regular oximeters in these conditions may lead to erroneous and false readings, which may lead to detrimental effects on the patient's care. To overcome this significant problem a special oximeter (cooximeter, i.e., cuvette oximeter) is needed when there is a suspicion of presence of high level of dyshemoglobins in the patient's blood. Functional S_aO_2 is the percentage of oxyhemoglobin compared to sum of oxy- and deoxyhemoglobins. Therefore, the abnormal hemoglobins are not directly considered in the measurement of functional S_aO_2 by using regular oximetry. Cooximetry uses four or more light wavelengths, and has the ability to measure carboxyhemoglobin and methemoglobin as well as normal hemoglobins. The fractional S_aO_2 measures the percentage of oxyhemoglobin to all hemoglobins (normal and abnormal) present in the blood sample (14,15).

EAR OXIMETRY

Historical Development

In 1935, Matthes (16,17) showed that transmission oximetry could be applied to the external ear. However, a major problem with noninvasive oximetry applied to the ear was the inability to differentiate light absorption due to arterial blood from that due to other ear tissue and blood. In the following years, two methods were tried to solve this problem. The first was increasing local perfusion by heating the ear, applying vasodilator, or rubbing the ear. The second was comparing the optical properties of a "bloodless" earlobe (by compressing it using a special device) to the optical properties of the perfused ear lobe. Arterial S_aO_2 was then determined from the difference in these different measurements. This step was a significant step toward an accurate noninvasive measurement of S_aO_2. In 1976, Hewlett-Packard (18) used the collected knowledge about ear oximetry to that date to develop the model 47201A ear oximeter, Fig. 11.

HEWLETT-PACKARD EAR OXIMETER

This oximeter (18) is based on the measured light transmission at eight different wavelengths, which made this sensor less accurate and more complex than pulse oximeters. It used a high intensity tungsten lamp that generated a broad spectrum of light wave lengths. This light passes through light filters, then enters a fiberoptic cable, which carrys the filtered light to the ear. A second fibroptic cable carries the light pulses transmitted through the ear to the device for detection and analysis. The ear probe is relatively bulky ($\sim 10 \times 10$ cm) equipped with a temperature-controlled heater (to keep temperature of 41°C). It is attached to the antihelix after the ear has been rubbed briskly. This monitor is no longer manufactured because of its bulkiness and cost, and because of the development widely of a more accurate, smaller, and cost-effective monitor, the pulse oximeter.



Figure 11. The Hewlett-Packard Model 47201A ear oximeter.

PULSE OXIMETRY

Historical Development

In the early 1970s, Takuo Aoyagi (16,19,20), a Japanese physiological bioengineer, introduced pulse oximetry, the underlying concept of which had occurred to him while trying to cancel out the pulsatile signal of an earpiece densitometer with IR light. In early 1973, Dr. Susumu Nakajima, a Japanese surgeon, learned of the idea and ordered oximeter instruments from Nihon Kohden. After several prototypes were tested, Aoyagi and others delivered the first commercial pulse oximeter in 1974. This instrument was the OLV-5100 ear pulse oximeter, (Fig. 12). In 1977, the Minolta Camera Company



Figure 12. The OLV-5100 ear pulse oximeter, the first commercial pulse oximeter, it was introduced by Nihon Kohden in 1974.



Figure 13. The basic components of a pulse oximeter sensor. Two LEDs with different wavelengths as light sources and a photodiode as receiver.

introduced the Oximet MET-1471 pulse oximeter with a fingertip probe and fiberoptic cables. Nakajima and others tested the Oximet MET-1471 and reported on it in 1979. In the years since, pulse oximetry has become widely used in a number of fields, including Anesthesia, intensive care, and neonatal care.

Principles of Operation

Pulse oximetry differs from the previously described oximetry in that it does not rely on absolute measurements, but rather on the pulsations of arterial blood. Oxygen saturation is determined by monitoring pulsations at two wavelengths and then comparing the absorption spectra of oxyhemoglobin and deoxygenated hemoglobin (20,21). Pulse oximetry uses a light emitter with red and infrared LEDs (light-emitting diodes) that shine through a reasonably translucent site with good blood flow (Fig. 13). Typical adult–pediatric sites are the finger, toe, pinna (top), or lobe of the ear. Infant sites are the foot or palm of the hand and the big toe or thumb. On the opposite side of the emitter is a photodetector that receives the light that passes through the measuring site. There are two methods of sending light through the measuring site (see above) (Fig. 9). The transmission method is the most common type used, and for this discussion the transmission method will be implied. After the transmitted red (R) and IR signals pass through the measuring site and are received at the photodetector, the R/IR ratio is calculated. The R/IR is compared to a "look-up" table (made up of empirical formulas) that converts the ratio to pulse oxygen saturation (S_pO_2) value. Most manufacturers have their own tables based on calibration curves derived from healthy subjects at various S_pO_2 levels. Typically, an R/IR ratio of 0.5 equates to approximately 100% S_pO_2, a ratio of 1.0 to $\sim$82% S_pO_2, while a ratio of 2.0 equates to 0% S_pO_2. The major change that occurred from the eight-wavelength Hewlett-Packard oximeters (see above) of the 1970s to the oximeters of today was the inclusion of arterial pulsation to differentiate the light absorption in the measuring site due to skin, tissue, and venous blood from that of arterial blood. At the measuring site there are several light absorbers (some of them are constant) such as skin, tissue, venous blood, and the arterial blood (Fig. 14). However, with each heart beat the heart contracts and there is a surge of arterial blood, which momentarily increases arterial blood volume across the measuring site. This results in more light absorption during the surge. Light signals received at the photodetector are looked at as a waveform (peaks with each heartbeat and troughs between heartbeats). If the light absorption at the trough, which should include all the constant absorbers, is subtracted from the light absorption at the peak, then the resultants are the absorption characteristics due to added volume of blood only, which is arterial blood. Since peaks occur with each heartbeat or pulse, the term "pulse oximetry" was applied.



Figure 14. Schematic Representation of light absorption in adequately perfused tissue.

New Technologies

Conventional pulse oximetry accuracy degrades during motion and low perfusion. This makes it difficult to depend on these measurements when making medical decisions. Arterial blood gas tests have been and continue to be commonly used to supplement or validate pulse oximeter readings. Pulse oximetry has gone through many advances and developments since the Hewlett-Packard Model 47201A ear oximeter invention in 1976. There are several types of pulse oximeters manufactured by different companies available in the market nowadays. Different technologies have been used to improve pulse oximetry quality and decrease its limitations, which would lead eventually to better patient care. Figure 15 shows a modern pulse oximeter (Masimo Rad-9) designed by Masimo using the Signal Extraction Technology (Masimo SET) (22,23), is a software system composed of five parallel algorithms designed to eliminate nonarterial "noise" in a patient's blood flow. This monitor display includes: S_pO_2, pulse rate, alarm, trend, perfusion index (PI) (24), signal IQ, and plethysmographic waveform. Moreover, Masimo manufactures a handheld pulse oximeter by utilizing the same technology (Masimo SET) as shown in Fig. 16. Its small size ($\sim 15.7 \times 7.6 \times 3.5$ cm) and broad catalog of features make it suited for hospital, transport, and home use. Nellcor (25) uses the OxiMax technology to produce a list of pulse oximetry monitors and sensors. These sensors have a small digital memory chip that transmits

Figure 15. Masimo Rad-9 pulse oximeter.

Figure 17. Nellcor N-595 pulse oximeter.

sensor-specific data to the monitor. These chips contain all the calibration and operating characteristics for that sensor design. This gives the monitor the flexibility to operate accurately with a diverse range of sensor designs without the need for calibrating each sensor to the specific monitors. This opens a new area of pulse oximetry innovations. Figure 17 reveals some of the Nellcor monitors and sensors available. Furthermore, Nellcor has designed a handheld pulse oximeter, as shown in Fig. 18, compatible with its line of OxiMax pulse oximetry sensors. Nellcor combines two advanced technologies in measuring blood gases: the OxiMax technology and Microstream CO_2 technology (see the section Capnography) to produce a S_pO_2 and end-tidal CO_2 partial pressure (PetCO_2) handheld capnograph–pulse oximeter to monitor both S_pO_2 and PetCO_2. Several additional parameters are now available on the modern oximeter, and they add additional functionality for these monitors and decrease their limitations. One of these parameters is called the “perfusion index” (PI) (24,26). This is a simple measure of the change that has occurred in the tissue-under-test (e.g., the finger) over the cardiac cycle. When this parameter was first recognized as being something that a pulse oximeter could measure, it was difficult to imagine a value to the measurement because it is affected by so many different physiological and environmental variables, including systemic vascular resistance, volume status, blood pressure, and ambient temperature. But as time continues to pass since its introduction, more applications for PI have been found. The most obvious use for perfusion index is as an aid in sensor placement. It provides a means to quantify the validity of a given sensor site and, where desired, to maximize measurement accuracy. Perfusion index has also provided a simple and easy way test for sufficient collateral blood flow in the ulnar artery to allow for harvest of the radial artery for coronary artery bypass graft (CABG) surgery and for monitoring peripheral perfusion in critically ill patients.

Figure 16. Masimo Rad-5 handheld pulse oximeter.

Clinical Uses

Pulse oximeters are widely used in clinical practice (27–30). They are used extensively in the intensive care units to monitor oxygen saturation, and to detect and prevent hypoxemia. Monitoring oxygen saturation during anesthesia is a standard of care, which is almost always done by pulse oximeters. Pulse oximeters are very helpful in monitoring patients during procedures like bronchoscopy, endoscopy, cardiac catheterization, exercise testing,

Figure 18. Nellcor N-45 handheld pulse oximeter.



Figure 19. Portable Nonin Onyx 9500 pulse oximeter.

and sleep studies. Also, they are commonly used during labor and delivery for both the mother and infant. These sensors have no significant complications related to their use. There are several types of portable pulse oximeters on the market. These oximeters are small in size, useful for patients transport, and can be used at home. Figure 19 shows one of these pulse oximeters.

Accuracy and Limitations

The accuracy of pulse oximeters in measuring exact saturation has been shown to be ~±4% as compared to blood oximetry measurements. Several studies have shown that with low numbers of S_aO_2, there is a decreased correlation between S_pO_2 and S_aO_2, especially when $S_aO_2 < 70\%$ and in unsteady conditions (31). However, newer technologies have improved accuracy during these conditions substantially. Another factor that influences the accuracy of pulse-oximetry is the response time. There is a delay between a change in S_pO_2 and the display of this change. This delay ranges from 10 to 35 s. Pulse-oximeters have several limitations that may lead to inaccurate readings. One of its most significant limitations is that it estimates the S_aO_2, not the arterial oxygen tension (P_aO_2). Another limitation is the difficulty these sensors have in detecting arterial pulsation in low perfusion states (low cardiac output, hypothermia etc.) (32). Furthermore, the presence of dyshemoglobins (e.g., methemoglobin, carboxyhemoglobin) (15) and diagnostic dyes (e.g., methylene blue, indocyanine green, and indigo carmine) (33) affects the accuracy of these monitors, leading to false readings. High carboxyhemoglobin levels will falsely elevate S_pO_2 readings, which may lead to a false sense of security regarding the patient's oxygenation, and possible disastrous outcome. CO-oximetry should be used to measure S_aO_2 in every patient who is suspect for elevated carboxyhemoglobin (such as fire victims). Methemoglobinemia may lead to false ~85% saturation reading. The clinician should be alert to the potential causes and possibility of methemoglobinemia (e.g., nitrites, dapsone, and benzocaine). The CO-oximetry is also indicated in these patients. Vascular dyes may also affect the S_pO_2 readings significantly, especially methylene blue, which is also used in the treatment of methemoglobinemia. Brown, blue, and green nail polish may affect S_pO_2 too. Therefore, routine removal of this polish is recommended. The issue of skin pigmentations effect on S_pO_2 reading is still controversial. Motion artifacts are a common problem in using pulse oximeters, especially in the intensive care units.

Future Directions for Pulse Oximeters

As mentioned above, there are several limitations with the recent commercially available pulse oximeters. Pulse oximeters technology is working on decreasing those limitations and improving pulse oximeters function (34). In the future, techniques to filter out the noise component common to both R and IR signals, such as Masimo signal extraction, will significantly decrease false alarm frequency. Pulse oximeters employing more than two wavelengths of light and more sophisticated algorithms will be able to detect dyshemoglobins. Improvements in reflection oximetry, which detects backscatter of light from light-emitting diodes placed adjacent to detectors, will allow the probes to be placed on any body site. Scanning of the retinal blood using reflection oximetry can be used as an index of cerebral oxygenation. Combinations of reflectance oximetry and laser Doppler flowmetry may be used to measure microcirculatory oxygenation and flow.

Continuous Intravascular Blood Gas Monitoring (CIBM)

The current standard for blood gas analysis is intermittent blood gas sampling, with measurements performed *in vitro* in the laboratory or by using bedside blood gas analyzer. Recently, miniaturized fiberoptic devices have been developed that can be placed intravascularly to continuously measure changes in PO_2, PCO_2, and pH. These devices utilize two different technologies: Electrochemical sensors technology, based on a modified Clark electrode, and optode (photochemical/optical) technology (35,36).

Optode (Photochemical–Optical) Technology. An optode unit consists of optical fibers with fluorescent dyes encased in a semipermeable membrane. Each analyte, such as hydrogen ion, oxygen, or carbon dioxide, crosses the membrane and equilibrates with a specific chemical fluorescent dye to form a complex. As the degree of fluorescence changes with the concentration of the analyte, the absorbance of a light signal sent through the fiberoptic bundles changes, and a different intensity light signal is returned to the microprocessor. Optode technology has accuracy comparable to that of a standard laboratory blood gas analyzer. However, several reasons and problems, including the cost (see below) still limit the use of this monitor routinely.

At present, the Paratrend 7+ (PT7+; Diametric Medical Inc., High Wycombe, U.K.; distributed by Philips Medical Systems), and Neotrend (NT) are the only commercially available multiparameter CIBM systems. The original probe of Paratrend 7 (PT7) was introduced in 1992. It consists of a hybrid probe incorporating four different sensors: miniaturized Clark electrode to measure PO_2, optode to determine PCO_2, and pH (absorbance sensors, phenol red in bicarbonate solution), and a thermocouple (copper, constantan) to measure temperature and allow temperature correction of the blood gas values. All these sensors were encased in a heparin-coated microporous polyethylene tube that was permeable to the analytes to be measured. This sensor was modified in 1999. In the new sensor (PT7+) (Fig. 20), the Clark electrode was replaced by an optical PO_2 sensor. According to the manufacturer, this new PO_2 sensor is more accurate and has a faster response time.

Clinical Uses

Continuous intravascular blood gas monitoring has been applied in various clinical settings (36,37) in the operating room and the intensive care unit. In the operating room, especially in adults undergoing one lung ventilation for major surgery (e.g., one lung ventilation for thoracoscopic surgery or lung transplantation, major cardiac or vascular surgery). The most common site for CIBM measurement is the radial artery in adults and the femoral artery in children. The umbilical artery is used for probe insertion in neonates. Reports and studies showed that performance and accuracy of CIBM devices appear to be sufficient for clinical use.



Figure 20. The Paratrend 7+ (PT7+; Diametric Medical Inc.) sensor.

Limitations and Complications

Reliable intravascular blood gas measurement depends on a number of mechanical, electrical, and physicochemical properties of the CIBM probe as well as the conditions of the vessel into which the probe is inserted (36,37). Therefore, several factors can affect the performance of CIBM, including mechanical factors related to the intraarterial probe (e.g., not advanced adequately in the artery, the sensor becomes attached to the wall of the vessel), factors related to the artery itself (e.g., vasospasm), interference from electrocautery and ambient or endoscopic light, or related to the "flush" solution used to flush the intraarterial catheter, which may lead to false measurements. Complications may include thrombosis, ischemia, vasospasm, and failure. Although CIBM appears to be advantageous, there are no prospective, randomized, double-blind studies of its impact on morbidity and mortality. Future outcome studies should focus on well-defined groups of selected patients who might benefit from CIBM (e.g., critically ill patients with potentially rapid and unexpected changes in blood gas values). Furthermore, no data is available on the cost/benefit ratio of CIBM, and more studies are still needed to know if this monitor is cost-effective.

Intrapartum Fetal Pulse Oximetry

Intrapartum fetal pulse oximetry is a direct continuous noninvasive method of monitoring fetal oxygenation (38). Persistent fetal hypoxemia may lead to acidosis and neurological injury, and current methods to confirm fetal compromise are indirect and nonspecific. Therefore, intrapartum fetal pulse oximetry may improve intrapartum fetal assessment and, most important, improve the specificity of detecting fetal compromise (39,40). Intrapartum fetal pulse oximetry may monitor, not only the fetal heart rate (FHR), but also the arterial oxygen saturation and peripheral perfusion may be assessed.

Principle of Operation and Placement

The fetus *in utero* does not have an exposed area that would allow placement of a transmission sensor (38). Thus, reflectance sensors have been designed where the light-emitting diodes are located adjacent to the photodetector (Fig. 9). During labor, the sensor is placed transvaginally between the uterine wall and the fetus, with contact on the fetal presenting part, usually the soft tissue of the fetal cheek. Monitoring of fetal oxygen saturation has been encumbered by multiple technical obstacles (38). For example, reflectance sensors not directly attached to the fetus, work only when in contact with fetal skin and may not produce an adequate S_pO_2 signal when contact is suboptimal during intense uterine contractions or during episodes of fetal movement. In this situation, sensor position may require adjustment. Improved reflectance sensor contact has been attempted via a variety of sensor modifications, including suction devices, application with glue, and direct attachment to the fetal skin with a special clip. The Nellcor (Fig. 21) sensors have been developed with a "fulcrum" modification, which mechanically places the sensor surface into better contact with the fetal skin. Other technical

Figure 21. Nellcor OxiFirst fetal pulse oximeter.

advances, such as modification of the red light-emitting diode from a 660 to a 735 nm wavelength, have resulted in improved registration times.

Future Direction of Intrapartum Fetal Pulse Oximetry. Ideally, calibration of these monitors in human fetuses should be done by simultaneous measurement of S_pO_2 and preductal S_aO_2. Because the access to fetal circulation during labor is not feasible, calibration of these monitors is still a major problem (38). It appears that well-designed animal laboratory studies and human infant and neonatal studies will have to suffice for calibration and validation of these monitors. To make this monitor more valuable and accurate as a guide for obstetric and neonatal management during labor, prospective studies with a larger number of abnormal fetuses will be necessary to determine duration and level of hypoxia leading to metabolic acidosis in humans. Also, more studies are needed to answer questions about its safety and efficacy. Finally, further refinements in equipment design should improve the accuracy of S_pO_2 determination and the ability to obtain an adequate signal. Decreased signal-to-noise ratios, motion artifacts (e.g., contractions, fetal movement, maternal movement), impediments to light transmission (e.g., vernix, fetal hair, meconium), and calibration difficulties are unique obstacles in accurately assessing the fetus by this monitor. Technical development goals of fetal pulse oximetry should include improvement of sensor optical design, hardware, and software modification to obtain high signal quality and precise calibration. Major advantages of fetal oxygen saturation monitoring include its ease of interpretation for clinicians of varying skills, being noninvasive method, and the ability to monitor fetal oxygenation continuously during labor. However, more studies are needed to evaluate its safety, efficacy, and cost issues (41). When these issues are resolved, intrapartum fetal oxygen saturation monitoring could perhaps be one of the major advances in obstetrics during the twenty-first century.

TRANSCUTANEOUS BLOOD GAS MONITORING (TCM)

Historical Development

The possibility of continuously monitoring arterial blood oxygen and carbon dioxide using a heated surface electrode on human skin was discovered in the early 1970s and made commercially available by 1976 (42). In 1951, Baumberger and Goodfriend published an article showing a method to determine the arterial oxygen tension in man by equilibration through intact skin. By immersing a finger in a phosphate buffer solution heated to 45 °C, they found that the PO_2 of the buffer approached that of the alveolar air. They showed that if skin blood flow increased by the highest tolerable heat (45°C), the surface PO_2 rises to arterial blood PO_2. A few years later (in 1956), Clark invented the membrane covered platinum polarographic electrode to measure O_2 tissue tensions. By 1977, at least three commercial transcutaneous PO_2 (tcPO_2) electrodes were available (Hellige, Roche, RADIOMETER). These devices were applied initially to premature infants in an effort to reduce the incidence of blindness due to excessive oxygen administration. Throughout more than three decades, the TCM technology has been closely linked to the care of neonates; however, recent studies suggest that TCM technology may work just as well for older children and adults (29). The TCM offers continuous noninvasive measurement of blood gases, which is especially advantageous in critically ill patients in whom rapid and frequently life-threatening cardiopulmonary changes can occur during short periods of time. However, with the widespread use of pulse oximetry, the use of transcutanenous blood gas monitors has decreased.

Blood Gas Diffusion Through the Skin

The human skin consists of three main layers: the stratum corneum, epidermis, and dermis (Fig. 22). The thickness of the human skin varies with age, sex, and region of the body. The thickness of the stratum corneum varies from 0.1 to 0.2 mm depending on the part of the body. This is nonliving layer composed mainly of dehydrated cells (dead layer), which do not consume oxygen or produce carbon dioxide. The next layer is the epidermis layer, which consists of proteins, lipids, and melanin-forming cells. The epidermis is living, but is blood-free. The thickness of this layer ~0.05–1 mm. Underneath the epidermis is the dermis, which consists of dense connective tissue, hair follicles, sweat glands, fat cells, and capillaries. These capillaries receive blood from arterioles and drain in venules. Arteriovenous anastomoses innervated by nerve fibers are commonly found in the dermis of the palms, face, and ears. These shunting blood vessels regulate blood flow



Figure 22. Human skin.

through the skin. Heat increases blood flow through these channels almost 30-fold. Gas diffusion through the skin occurs due to a partial pressure difference between the blood and the outermost surface of the skin. Diffusion of blood gases through the skin normally is very low, however, the heated skin (~43 °C) becomes considerably more permeable to these gases.

Principle of Transcutaneous PO_2 Measurement (tcPO_2)

The probe used to measure the tcPO_2 is based on the idea of oxygen polarography (see above). This probe (7,12) consists of a platinum cathode and a silver reference anode encased in an electrolyte solution and separated from the skin by a membrane permeable to oxygen (usually made of Teflon, polypropylene, or polyethylene). The electrode is heated, thereby melting the crystalline structure of the stratum corneum, which otherwise makes this skin layer an effective barrier to oxygen diffusion. The heating of the skin also increases the blood flow in the capillaries underneath the electrodes. Oxygen diffuses from the capillary bed through the epidermis and the membrane into the probe, where it is reduced at the cathode, thereby generating an electric current that is converted into partial pressure measurements and displayed by the monitor. Because of an *in vitro* drift inevitably occurring inside the probe, where several chemical reactions are going on, the tcPO_2 sensor must be calibrated before using, and be repeated every 4–8 h. Since the O_2-dependent current flow exhibits a linear relationship at a fixed voltage, only two known gas mixtures are required for the calibration. Two *in vitro* calibration techniques can be employed: by using two precision gas mixtures (e.g., nitrogen and oxygen), and by using a "zero O_2 solution" (e.g., sodium sulfite) and room air.

The Transcutaneous PO_2 Sensor. The modern transcutaneous PO_2 sensors still use the principles used by Clark decades ago (7,12). Figure 23 illustrates a cross-sectional diagram of a typical Clark-type sensor. This particular sensor consists of three glass-sealed platinum cathodes that are separately connected via current amplifiers to a surrounding Ag–AgCl cylindrical ring. A buffered KCl electrode, which has a low water content to reduce drying of the sensor, is used. The following basic reactions happen between the two electrodes:

At the anode (+ electrode):

$$4\,\mathrm{Ag} + 4\,\mathrm{Cl}^- \leftrightarrow 4\,\mathrm{AgCl} + 4\,\mathrm{e}^-$$

(the electrons complete the circuit)

At the cathode (− electrode):

$$4\,\mathrm{H}^+ + 4\,\mathrm{e}^- + \mathrm{O}_2 \leftrightarrow 2\,\mathrm{H_2O}$$

(the electrons are boiled off of the platinum electrode)

Overall:

$$4\,\mathrm{Ag} + 4\,\mathrm{Cl}^- + 4\,\mathrm{H}^+ + \mathrm{O}_2 \leftrightarrow 4\,\mathrm{AgCl} + 2\,\mathrm{H_2O}$$

The two electrodes are covered with a thin layer of electrolytic solution that is maintained in place by a membrane that allows slow diffusion of O_2 from the skin into the sensor. The diffusion of O_2 through the skin is normally very low. Under normal physiological conditions, the PO_2 measured at the surface of the skin using a nonheated transcutaneous PO_2 electrode is near zero, regardless of the underlying blood PO_2. In order to facilitate O_2 diffusion through the skin, abrasion of the skin and drug-induced hyperemia through the application of nicotinic acid cream were initially used. However, since direct skin heating gives a more prolonged and consistent effect, a heating element is now used in all commercial transcutaneous PO_2 sensors. Generally, temperatures between 43 and 44° yield adequate vasodilatation of the cutaneous blood vessels with minimal skin damage. Heating the skin speeds up O_2 diffusion through the stratum corneum. In addition, it also causes vasodilatation of the dermal capillaries, which increases blood flow to the region of skin in contact with the sensor. With increased blood flow, more O_2 is available to the tissues surrounding the capillaries in the skin, and consequently the PO_2 of the blood in these capillary loops approximate more closely that of the arterial blood. Heating the blood also shifts the oxygen dissociation curve to the right. Therefore, the binding of hemoglobin with O_2 is reduced and the release of O_2 to the cells is increased. Simultaneously, skin heating also increases local tissue O_2 consumption. Fortunately, however, these two factors tend to cancel each other.



Figure 23. A cross-sectional diagram of a typical Clark-type sensor.

Transcutaneous PCO_2 Monitoring

Continuous PCO_2 monitoring is helpful in monitoring lung ventilation during spontaneous breathing or artificial ventilation. It makes it easier to adjust the parameters of the ventilator and prevent respiratory acidosis or alkalosis.

The Transcutaneous PCO_2 Sensor

The typical sensor is similar the O_2 sensor that was described above, as shown in Fig. 24. This sensor (7,12) consists of glass pH electrode with a concentric Ag–AgCl reference electrode that also serves as a temperature-



Figure 24. The transcutaneous PCO_2 sensor.

controlled heater. A buffer electrolyte (e.g., HCO_3^-) is placed on the surface of the electrode and a thin CO_2 permeable membrane (e.g., Teflon) stretched over the electrode separates the sensor from its surroundings. As CO_2 molecules diffuse via the CO_2-permeable membrane into the HCO_3^- containing solution, the following chemical reaction occurs:

$$CO_2 + H_2O \leftrightarrow H_2CO_3 \leftrightarrow H^+ + HCO_3^-$$

A potential between the pH and the reference electrodes is generated as a result of this reaction. This potential is proportional to the CO_2 concentration. Measurement of pH with a pH electrode can lead to estimation of the skin PCO_2, which correlates with the $PaCO_2$. According to the Henderson–Haselbach relationship, pH is proportional to the negative logarithm of PCO_2.

Skin temperature must be considered when analyzing PCO_2 measurements, because the skin heating can affect the transcutaneous PCO_2 sensor reading. This effect is due to the high temperature coefficient of the PCO_2 sensor. Heating the sensor results in an increase in PCO_2, since CO_2 solubility decreases, increase in local tissue metabolism, and increase in the rate of CO_2 diffusion through the stratum corneum. Therefore, the transcutaneous PCO_2 values are usually higher than the corresponding arterial PCO_2. Calibration of the PCO_2 sensor is different from the PO_2 sensor calibration. In the CO_2 sensor case, the voltage signal generated in the PCO_2 sensor is proportional to the logarithm of the CO_2 concentration (not to CO_2 concentration directly, as the case in PO_2). Therefore, there is no "zero point" calibration in transcutaneous PCO_2 sensor as there is with a transcutaneous PO_2 sensor. For this reason, one needs two different precisely analyzed gas mixtures for calibration. Usually, gas mixtures containing 5 and 10% CO_2 are used for calibrating the PCO_2 sensor. On the other side, PCO_2 sensor calibration must be done at the temperature at which it will be operated.

Clinical Applications of Transcutaneous PO_2 and PCO_2 Monitoring

Transcutaneous PO_2 and PCO_2 monitoring have found numerous applications in clinical medicine and research (42,43) during the past two decades: (1) neonatology: tcPO_2 monitoring remains the most commonly used technique to guide oxygen therapy in premature infants. In low birth weight infants, tcPO_2 is one of the best available monitor of ventilation. (2) Fetal monitoring: specially designed electrodes attached to the fetal scalp have been used. Changes in tcPO_2 rapidly reflected changing maternal and fetal conditions. Some studies showed that fetal tcPO_2 is considerably affected by local scalp blood flow, therefore repeated episodes of asphyxia, which may lead to increase in catecholamines, can reduce fetal scalp blood flow and lead to misleading reduction in tcPO_2. (3) Sleep studies: pulse oximetry and combined tcPO_2–tcPCO_2 electrode are used in sleep studies. This combination made it possible to study the ventilator response of hypoxia in sleeping infants. (4) Peripheral circulation: tcPO_2 electrodes are extensively used in evaluation peripheral vascular disease (44). Furthermore, transcutaneous oximetry has been used in several clinical situations such as prediction of healing potential for skin ulcers or amputation sites, assessment of microvascular disease (45), and determination of cutaneous vasomotor status. Figure 25 shows one of the commercially available transcutaneous blood gas monitor.

Figure 25. Radiometer TCM 4 transcutaneous blood gas monitor.

CAPNOMETRY AND CAPNOGRAPHY

Introduction

Capnometry is the measurement of carbon dioxide (CO_2) in the exhaled gas. Capnography is the method of displaying CO_2 measurements as waveforms (capnograms) during the respiratory cycle. The end-tidal PCO_2($PetCO_2$) is the maximum partial pressure of the exhaled CO_2 during tidal breathing (just before the beginning of inspiration). The measurement of CO_2 in respiratory gases was first accomplished in 1865, using the principle of Infrared(IR) absorption. Capnography was developed in 1943 and introduced to clinical practice in the 1950s (27). Since then, capnometry–capnography has gone through significant advances. Now capnography is a "standard of care" for general anesthesia (3), as described by the American Society of Anesthesiologists (ASA).

Measurement Techniques

Capnometry most commonly utilizes IR light absorption or mass spectrometry. Other technologies include Raman spectra analysis and a photoacoustic spectra technology (46,47)

Infrared Light Absorption Technique. This is the most common technique used to measure CO_2 in capnometers.



Figure 26. Single-beam infrared CO_2 analyzer, used in some mainstream sampling systems.

This method is cheaper and simpler than mass spectrometry. However, it is less accurate and has a slower response time (~ 0.25 vs. 0.1 s for mass spectrometry). There are two types of IR analyzers, a double and a single beam. The double-beam positive-filter model consists of an IR radiation source, which radiates to two mirrors. The two beams pass via a filter to two different chambers (sample chamber and reference chamber), and then to a photodetector. Consequently, it is possible to process the detector output electronically to indicate the concentration of CO_2 present. The single-beam negative-filter (Fig. 26), utilizes only one beam without using a reference. The principle behind this technique is that gases generally absorb electromagnetic IR radiation, and gas molecules with two or more atoms, provided these atoms are dissimilar (e.g., CO_2, but not O_2) absorb IR radiation in the range 1000–15000 nm. By filtering particular wavelengths, carbon dioxide and other gases can be measured. Carbon dioxide absorbs IR radiation strongly between 4200 and 4400 nm. Nitrous oxide and water have absorption peaks close to this area. Thus, there is a potential for the introduction of error with these substances in this method.

Raman Spectrography. Raman spectrography uses the principle of “Raman Scattering” for CO_2 measurement. The gas sample is aspirated into an analyzing chamber, where the sample is illuminated by a high intensity monochromatic argon laser beam. The light is absorbed by molecules, which are then excited to unstable vibrational or rotational energy states (Raman scattering). The Raman scattering signals (Raman light) are of low intensity and are measured at right angles to the laser beam. The spectrum of Raman scattering lines can be used to identify all types of molecules in the gas phase. Raman scattering technology has been incorporated into many newer anesthetic monitors (RASCAL monitors) to identify and quantify instantly CO_2 and inhalational agents used in anesthesia practice (48).

Mass Spectrography. The mass spectrograph separates molecules on the basis of mass to charge ratios. A gas sample is aspirated into a high vacuum chamber, where an electron beam ionizes and fragments the components of the sample. The ions are accelerated by an electric field into a final chamber, which has a magnetic field, perpendicular to the path of the ionized gas stream. In the magnetic field, the particles follow a path wherein the radius of curvature is proportional to the charge: mass ratio. A detector plate allows for determination of the components of the gas and for the concentration of each component. Mass spectrometers are quite expensive and too bulky to use at the bedside and are rarely used presently. They are either “stand alone”, to monitor a single patient continuously, or “shared”, to monitor gas samples sequentially from several patients in different locations (multiplexed). Up to 31 patients may be connected to a multiplexed system, and the gas is simultaneously sampled from all locations by a large vacuum pump. A rotary valve (multiplexer) is used to direct the gas samples sequentially to the mass spectrometer. In a typical 16-station system, with an average breathing rate of 10 $\text{breaths} \cdot \text{min}^{-1}$, each patient will be monitored about every 3.2 min. The user can interrupt the normal sequence of the multiplexer and call the mass spectrometer to his patient for a brief period of time (46–48).

Photoacoustic Spectrography. Photoacoustic gas measurement is based on the same principles as conventional IR-based gas analyzers: the ability of CO_2, N_2O and anesthetic agents to absorb IR light (46,49). However, they differ in measurement techniques. While IR spectrography uses optical methods, photoacoustic spectrography (PAS) uses an acoustic technique. When an IR energy is applied to a gas, the gas will expand and lead to an increase in pressure. If the applied energy is delivered in pulses, the gas expansion would be also pulsatile, resulting in pressure fluctuations. If the pulsation frequency lies within the audible range, an acoustic signal is produced and is detected by a microphone. Potential advantages of PAS over IR spectrometry are higher accuracy, better reliability, less need of preventive maintenance, and less frequent need for calibration. Furthermore, as PAS directly measures the amount of IR light absorbed, no reference cell is needed and zero drift is nonexistent in PAS. The zero is reached when there is no gas present in the chamber. If no gas is present there can be no acoustic signal (49).

CO_2 Sampling Techniques

Sidestream versus Mainstream. Capnometers that are used in clinical practice use two different sampling techniques (50) (Fig. 27): sidestream or mainstream. A mainstream (flow-through) capnometer has an airway adaptor cuvette attached in-line and close to the endotracheal tube. The cuvette incorporates an IR light source and sensor that



Figure 27. Sidestream vs. mainstream CO_2 sampling techniques. (a) Mainstream CO_2 sampling. (b) Sidestream sampling.

senses carbon dioxide absorption to measure PetCO_2. A sidestream capnometer uses a sampling line that attaches to a T-piece adapter at the airway opening, through which the instrument continually aspirates tidal airway gas for analysis of carbon dioxide. The main advantage of the mainstream analyzer is its rapid response, because the measurement chamber is part of the breathing circuit. The sample cuvette lumen, through which inspired and expired gases pass, is large in order to minimize the work of breathing, and pulmonary secretions generally do not interfere with carbon dioxide analysis. Compared with sidestream (aspiration) sampling, the airway cuvette is relatively bulky and can add dead space. However, within the past few years lighter and smaller airway cuvettes have been developed to allow its use in neonates. The sidestream $P$$CO_2$ analyzer adds only a light T-adapter to the breathing circuit, and can be easily adapted to non-intubation forms of airway control. Because the sampling tubing is small bore, it can be blocked by secretions. During sidestream capnography, the dynamic response, the steepness of the expiratory upstroke and aspiratory downslope, tends to be blunted because of the dispersive mixing of gases through the sampling line, where gas of high $P$$CO_2$ mixes with gas of low $P$$CO_2$. In addition, a washout time is required for the incoming sampled gas to flush out the volume of the measuring chamber. The overall effect is an averaging of the capnogram, resulting in a lowering of the alveolar plateau and an elevation of the inspiratory baseline. Thus, PetCO_2 may be underestimated and rebreathing can be simulated. These problems are exacerbated by high ventilatory rates and by the use of long sampling catheters. In addition, the capnogram is delayed in time by transport delay, the time required to aspirate gas from the airway opening adapter through the sampling tubing to the sampling chamber.

Micro-Stream Technology. Micro-stream technology (51) is a new CO_2 sampling techneque that uses a low aspiration rate (as low as 50 $mL \cdot min^{-1}$), such as NBP-75, Nellcor Puritan Bennett, as shown in Fig. 28. In addition, this technology uses a highly CO_2-specific IR source, where the IR emission exactly matches the absorption spectrum of the CO_2 molecules. The advantages of this technology, compared to the traditional high flow side-stream capnometer (150 $mL \cdot min^{-1}$), is that it gives more accurate PetCO_2 measurements and better waveforms in neonates and infants with small tidal volumes and high respiratory rates. Furthermore, these low flow capnometers are less likely to aspirate water and secretions into the sampling tubes, resulting in either erroneous PetCO_2 values or in total occlusion of sampling tube.

Phases of Capnography

A normal single breath capnogram (time capnogram) is shown in Fig. 29. Time capnogram is the partial pressure of expired CO_2 plotted against time on the horizontal axis. This capnogram can be divided into inspiratory (phase 0) and expiratory segments. The expiratory segment, similar to a single breath nitrogen curve or single breath CO_2 curve, is divided into phases I, II, and III, and occasionally, phase IV, which represents the terminal rise in CO_2 concentration. The angle between phase II and III is the alpha angle. The nearly 90° angle between phase III and the descending limb is the beta angle. Changes in time

Figure 28. Nellcor Microstream $ETCO_2$ breath sampling unit.



Figure 29. Normal single breath capnogram.

capnogram help to diagnose some of the breathing and ventilation problems, especially during anesthetic management of patients undergoing surgery (e.g., bronchospasm, esophageal intubation, CO_2 rebreathing, and even cardiac arrest).

Clinical Uses of Capnography

Capnography and capnometry (52) are safe, noninvasive test, and have few hazards. They are widely used in clinical medicine. Their uses include, but are not limited to (*1*) evaluating the exhaled CO_2, especially end-tidal CO_2 in mechanically ventilated patients during anesthesia. (*2*) Monitoring the severity of pulmonary disease and evaluating response to therapy, especially therapy intended to improve the ratio of dead space to tidal volume (V_D/V_T) and the matching of ventilation to perfusion (V/Q). (*3*) Determining that tracheal rather than esophageal intubation has taken place (low or absent cardiac output may negate its use for this indication) (53). Colorimetric CO_2 detectors are adequate devices for this purpose. (*4*) Evaluating the efficiency of mechanical ventilatory support by determination of the difference between the arterial partial pressure for CO_2 (PCO_2) and the PetCO_2. Figure 30 shows a combined handheld capnograph/pulse oximeter.

Limitations

Note that although the capnograph provides valuable information (52) about the efficiency of ventilation, it is not a replacement or substitute for assessing the PCO_2. The difference between PCO_2 and PetCO_2 increases as dead-space volume increases. In fact, the difference between the PCO_2 and PetCO_2 has been shown to vary within the same patient over time. Alterations in breathing pattern and tidal volume may introduce error into measurements designed to be made during stable, steady-state conditions. Interpretation of results must take into account the stability of physiologic parameters, such as minute ventilation, tidal volume, cardiac output, ventilation/perfusion ratios, and CO_2 body stores. Certain situations may affect the reliability of the capnogram. The extent to which the reliability is affected varies somewhat among types of devices (IR, photoacoustic, mass spectrometry, and Raman spectrometry). Furthermore, the composition of the respiratory gas mixture may affect the capnogram (depending on the measurement technology incorporated). The IR spectrum of CO_2 has some similarities to the spectra for both oxygen and nitrous oxide. High concentrations of either or both oxygen or nitrous oxide may affect the capnogram, and, therefore, a correction factor should be incorporated into the calibration of any capnograph used in such a setting. The reporting algorithm of some devices (primarily mass spectrometers) assumes that the only gases present in the sample are those that the device is capable of measuring. When a gas that the mass spectrometer cannot detect (such as helium) is present, the reported values of CO_2 are incorrectly elevated in proportion to the concentration of helium in the gas mixture. Moreover, the breathing frequency may affect the capnograph. High breathing frequencies may exceed the response capabilities of the capnograph. In addition, the breathing frequency, >10 breaths $\cdot$ min^{-1}, has been shown to affect devices differently. Contamination of the monitor or sampling system by secretions or condensate, a sample tube of excessive length, a sampling rate that is too high, or obstruction of the sampling chamber, can lead to unreliable results. Use of filters between the patient airway and the sampling line of the capnograph may lead to lowered PetCO_2 readings. Inaccurate measurement of expired CO_2 may be caused by leaks of gas from the patient–ventilator system preventing collection of expired gases, including, leaks in the ventilator circuit, leaks around tracheal tube cuffs, or uncuffed tracheal tubes.

Figure 30. Nellcor OxiMax NBP-75 handheld capnograph/ pulse oximeter.

Sublingual Capnometry

Sublingual capnometry is a method to measure the partial pressure of carbon dioxide under the tongue (PSLCO_2). This method is being used mainly in the critical care units to evaluate patients with poor tissue perfusion and multiple organ dysfunction syndrome.

Pathophysiologic Basis. Significant increases in the partial pressure of carbon dioxide (PCO_2) in tissue have



Figure 31. Nellcor CapnoProbe Sublingual capnometer.

been associated with hypoperfusion, tissue hypoxia, and multiple organ dysfunction syndrome (54). When perfusion of the intestinal mucosa is compromised, CO_2 accumulates in the gut. The high diffusability of CO_2 allows for rapid equilibration of PCO_2 throughout the entire gastrointestinal (GI) tract. The vasculature of the tongue and the GI tract are controlled by similar neuronal pathways. Thus, the vasculatures of both respond similarly during vasoconstriction (55). Because the tongue is the most proximal part of the GI tract, measurement of PCO_2 can be conveniently and noninvasively obtained by placing a sensor under the tongue. Clinical studies have demonstrated that $PSLCO_2$ can be used in the assessment of systemic tissue hypoperfusion and hypercapnia (56).

Capnometer Components and Principle of Operation. Figure 31 shows a commercially available sublingual capnometer (Nellcor CapnoProbe Sublingual System). This system (25) consists of two components: (1) SLS-l Sublingual Sensor: This sensor contains an optrode (a sensitive analyte detector) consists of an optical fiber capped with a small silicone membrane containing a pH-sensitive solution (Fig. 32). When the optrode is brought into contact with sublingual tissue, CO_2 present in the tissue freely diffuses across the silicone membrane into the fluorescent dye solution. No other commonly encountered gases or liquids can pass across the membrane. The CO_2 dissolves and forms carbonic acid, which in turn lowers the pH of the solution. The fluorescence intensity of the dye in the solution is directly proportional to pH.

This single use sensor is packaged in a sealed metal canister. Inside the canister, the sensor tip is enclosed in a gas permeable reservoir that contains a buffer solution. The solution prevents the optrode from drying out. The solution also allows calibration just prior to use, as it is in equilibrium with a known concentration of CO_2 within the canister. To begin use, the clinician opens the canister and inserts the cable handle into the SLS-l Sublingual Sensor. This action initiates a calibration cycle that allows the instrument to observe the sensor signal at the known PCO_2 of the calibrant (2). The N-80 instrument contains a precision optical component that emits light at two wavelengths in the violet and blue portions of the visible spectrum. The fluorescence intensity generated by the violet wavelength is insensitive to pH, whereas that generated by the blue wavelength is strongly sensitive to pH. The light is launched into an optical fiber and delivered to the tip of the disposable sensor. The green fluorescent light generated in the optrode is directed back to the N-80 instrument through an optical fiber. The light is then ratio metrically quantitated and directly correlated to $PSLCO_2$. When the fluorescence intensity of the optrode has stabilized (within 60–90 s), the N-80 instrument reports the measured value of $PSLCO_2$ on its LCD screen.



Figure 32. Diagram of Nellcor CapnoProbe sublingual capnometer basic components.

Chemical Colorimetric Airway Detector

This is a device (57,58) that uses a pH-sensitive indicator to detect breath-by-breath exhaled carbon dioxide (Fig. 33).



Figure 33. Nellcor Easy Cap II Pedi-Cap chemical colorimetric CO_2 detector.

The colorimetric airway detector is interposed between the endotracheal tube (ETT) and the ventilation device. Both adult and pediatric adaptors exist, but they cannot be used in infants who weigh < 1 kg. Because of excessive flow resistance, they are not suited for patients who are able to breathe spontaneously. Excessive humidity will render them inoperative in 15–20 min. The devices can be damaged by mucous, edematous, or gastric contents, and by administration of intratracheal epinephrine. Despite these drawbacks, colorimetric sensors have been found to be useful in guiding prehospital CPR (cardiopulmonary resuscitation) both in intubated patients and those with a laryngeal mask airway.

Role of Capnometry–Capnography in CPR. The relationship between cardiac output and $P\text{etCO}_2$ is logarithmic (59). Decreased presentation of CO_2 to the lungs is the major rate-limiting determinant of the $P\text{etCO}_2$ during low pulmonary blood flow. Capnography can detect the presence of pulmonary blood flow even in the absence of major pulses (pseudoelectromechanical dissociation, EMD) and also can rapidly indicate changes in pulmonary blood flow (cardiac output) caused be alterations in cardiac rhythm. Data suggests that $P\text{etCO}_2$ correlates with coronary perfusion pressure, cerebral perfusion pressure, and blood flow during CPR. This correlation between perfusion pressure and $P\text{etCO}_2$ is likely to be secondary to the relationship of $P\text{etCO}_2$ and cardiac output (60).

SUMMARY

Blood gas measurement methods and instruments have gone through significant improvements and advances in the last few decades. Invasive techniques have moved steadily toward using smaller instruments and closer to the patient's bed (bedside), which requires smaller blood sample. These improvements have made these devices more convenient, need less personnel to operate them, and more cost-effective. These bedside devices have comparable accuracy and reliability to the traditional central laboratory instruments. Continuous intravascular blood gas monitoring is a new invasive technique that uses miniaturized fiberoptic devices. This method has been used in different clinical settings with good results. However, several limitations and complications still exist. More studies and improvements are needed to know its cost-effectiveness in clinical medicine and to minimize its complications (such as ischemia and thrombosis). Other invasive instruments and methods were discussed in other parts of this encyclopedia. On the other hand, noninvasive blood gas measurement methods and devices improved greatly since its instruction to clinical medicine. These devices have been used extensively during anesthesia administration and in critical care units. Using pulse oximetry is "standard of care" in anesthesia practice. The use of pulse oximeter decreased the risk of hypoxia and its deleterious effect significantly. However, several limitations to its use still exist, especially in low perfusion states, during the presence of dyshemoglobins and motion artifacts. New technologies, such as the Oxi-Max and the Signal Extraction technologies, have been developed to overcome some of these limitations, and to add more features for these instruments (such as scanning the retina as an index of cerebral oxygenation and using Laser Doppler flowmetry–reflection oximetry to measure microcirculatory oxygenation and flow). Other types of pulse oximetry have been introduced to clinical medicine. Intrapartum fetal pulse oximetry is an example of these new pulse oximeters. This device provides a continuous, noninvasive method of monitoring fetal oxygenation, which may help in detecting persistent fetal hypoxemia and improve intrapartum fetal assessment. However, more studies are needed to evaluate its safety, efficacy, and cost issues. Transcutaneous blood gas monitoring is another noninvasive method to measure blood gases. This method is losing ground and popularity against the newer pulse oximeters, which have replaced this method in several situations. Capnometry–capnography has been used extensively in anesthesia practice in the last two decades. New CO_2 sampling technique such as microstream technology has been introduced. This method uses a low aspiration rate, making it more accurate than the previous techniques. Moreover, this technique can detect very small amount of CO_2. Photoacoustic sepectrography is a new technique has been developed to measure $P\text{etCO}_2$. This method is more reliable, accurate, and needs less calibration than the traditional methods. Studies showed an encouraging result and an important role for capnometry–capnography in cardiopulmonary resuscitation, which may lead to widespread use of these devices in CPR, in prehospital and inhospital settings.

BIBLIOGRAPHY

Cited References

1. Cadden K, Norman E, Booth J. Use of ABG in trauma for early recognition of acidosis and hypoxemia (Abstract). Respir Care 2001;46:1106.
2. Levin KP, Hanusa BH, Rotondi A, Singer DE, et al. Arterial blood gas and pulse oximetry in initial management of patients with community-acquired pneumonia. J Gen Intern Med 2001;9:590.
3. Morgan Jr GE, Mikhail MS, Murray MJ. Clinical Anesthesiology. 3rd ed. New York: Lange Medical Books/McGraw-Hill; 2002. p 124–125.
4. Severinghaus JW, Astrup P, Murray JF. Blood gas analysis and critical care medicine. Am J Resp Crit Care Med 1998;157:S114–S122.
5. Schell RM, Cole DJ. Cerebral monitoring: Jugular venous oximetry. Anesth Analg 2000;90:559.
6. Goodwin ALP. Physics of Gases, Anaesthesia and Intensive Care Medicine. (UK): The Medicine Publishing Company, Ltd.; 2003.
7. Malley WJ. Clinical Blood Gases: Assessment and Intervention. 2nd ed. New York: Elsevier; 2005.
8. West JB. Respiratory Physiology-Essentials. 6th ed. Baltimore: Williams & Wilkins; 2000.
9. Murray JF, Nadel JA. Textbook of Respiratory Medicine. 3rd ed. New York: W. B. Saunders.
10. Severinghaus JW, Astrup PB. History of blood gas analysis. VI: Oximetry. J Clin Monit 1986;2:270–288.
11. Millikan GA, Pappenheimer JR, Rawson AJ, et al. Continuous measurement of oxygen saturation in man. Am J Physiol 1941;133:390.

12. Adams AP, Hahn CEW. Principles and Practice of Blood Gas Analysis. London: Franklin Scientific Products; 1979.
13. Payne JB, Severinghaus JW. Pulse Oximetry. New York: Springer-Verlag; 1986.
14. Baker SJ, Tremper KK. The effect of carbon monoxide inhalation on pulse oximetry and transcutaneous PO_2. Anesthesiology 1987;66:677–679.
15. Baker SJ, Tremper KK, Hyatt J. Effects of methemoglobinemia on pulse oximetry and mixed venous oximetry. Anesthesiology 1989;70:112–117.
16. Severinghaus JW, Honda Y. History of blood gas analysis. VII. Pulse oximetry. J Clin Monit 1987;3:135–138.
17. Severinghaus JW. History and recent developments in pulse oximetry. Scand J Clin Lab Invest 1993;214 (1 Suppl): 105–111.
18. Merrick EB, Hayes TJ. Continuous noninvasive measurements of arterial blood oxygen levels. Hewlett-Packard J 1976;28920:2–9.
19. Aoyagi T, Miyasaka K. Pulse oximetry: its invention, contribution to medicine, and future tasks. Anesth Analg 2002;94(1 Suppl): S1–3.
20. Tremper KK, Barker SJ. Pulse oximetry. Anesthesiology 1989;70:98–108.
21. Welch JP, DeCesare MS, Hess D. Pulse oximetry: Instrumentation and clinical applications. Respir Care 1990;35: 584–601.
22. Robertson F, Hoffman G. Clinical evaluation of Masimo SET and Nellcor N395 oximeters during signal conditions in difficult-to-monitor neonates. Anesthesiology 2002;96:A556.
23. Barker SJ. The performance of six "motion-resistant" pulse oximeters during motion, hypoxemia, and low perfusion in volunteers. Anesthesiology 2001;95:A587.
24. Pologe JA, Tobin RM. Method and apparatus for improved photoplethysmographic perfusion-index monitoring. US patent 5,766,127. 1998.
25. http://www.nellcor.com.
26. Lima AP, Beelen P, Bakker J. Use of peripheral perfusion index derived from the pulse oximetry signal as a noninvasive indicator of perfusion. Crit Care Med 2002;30(6):1210–1213.
27. Soubani AO. Noninvasive monitoring of oxygen and carbon dioxide. Am J Emerg Med 2001;19(2).
28. Shapiro BA, Harrison RA, Cane RD. Clinical Application of Blood Gases. 4th ed. Chicago: Year Book Medical Publishers, Inc.; 1989.
29. Williams AJ. ABC of oxygen: Assessing and interpreting arterial blood gases and acid–base balance. Br Med J 1998;317(7167): 1213–1216.
30. Poets FC, Southall DP. Noninvasive monitoring of oxygenation in infants and children: Practical considerations and areas of concern. Pediatrics 1994;93(5): 737–746.
31. Severinghaus JW, Naifeh KH, Koh SO. Errors in 14 pulse oximeters during profound hypoxia. J Clin Monit 1989;5: 72–81.
32. Clayton DG, Webb RK, Ralston AC, et al. A comparison of the performance of 20 pulse oximeters under conditions of poor perfusion. Anaesthesia 1991;46:3–10.
33. Sidi A, Paulus DA, Rush W, et al. Methylene blue and indocyanine green artifactually low pulse oximetry readings of oxygen saturation. Studies in dogs. J Clin Monit 1987; 3:249–256.
34. Lynn LA. Interpretive Oximetry: Future Directions for Diagnostic Applications of SpO_2 Time-Series. Anesthesia Analgesia 2002;94:S84–S88.
35. Zimmerman JL, Dellinger RP. Initial evaluation of a new intra-arterial blood gas system in humans. Crit Care Med 1993;21:495–500.
36. Ganter M, Zollinger A. Continuous intravascular blood gas monitoring: development, current techniques, and clinical use of a commercial device. Br J Anaesth 2003;91:397–407.
37. Coule LW, Truemper EJ, Steinhart CM, Lutin WA. Accuracy and utility of a continuous intra-arterial blood gas monitoring system in pediatric patients. Crit Care Med 2001;29(2): 420–426.
38. Dildy GA. Intrapartum fetal pulse oximetry: past, present, and future. Am J Obstet Gynecol 1996;175(1): 1–9.
39. Dildy GA, Van den Berg PP, Katz M, et al. Intrapartum fetal pulse oximetry: fetal oxygen saturation trends during labor and relation to delivery outcome. Am J Obstet Gynecol 1994; 171:679–684.
40. Papiernik E. Fetal pulse oximetry: correlation between changes in oxygen saturation and neonatal outcome. Eur J Obstet Gynecol Reprod Biol 1994;57:73–77.
41. McNamara H, Chung DC, Lilford R, Johnson N. Do fetal pulse oximetry readings at delivery correlate with cord blood oxygenation and acidaemia. Br J Obstet Gynaecol 1992;99: 735–738.
42. Severinghaus JW. The current status of transcutaneous blood gas analysis and monitoring. Blood Gas News 1998; 9(2).
43. Franklin ML. Transcutaneous measurement of partial pressure of oxygen and carbon dioxide. Respir Care Clin North Am 1995;1:119–131.
44. Padberg FT, Back TL, Thompson PN, et al. Transcutaneous oxygen ($TcPO_2$) estimates probability of healing in the ischemic extremity. J Surg Res 1996;60:365–369.
45. Rooke TW. The use of transcutaneous oximetry in the noninvasive vascular laboratory. Int Angiol 1992;11(1): 46–40.
46. Tremper KK, Barker SJ. Fundamental principles of monitoring instrumentation. In: Miller RD, editor. Anesthesia. Vol I, 3rd ed. New York: Churchill Livingstone; 1990. p 957–999.
47. Raemer BD, Philip JH. Monitoring anesthetic and respiratory gases. In: Blitt CE, editor. Monitoring in Anesthesia and Critical Care Medicine. 2nd ed. New York: Churchill Livingstone; 1990. p 373–386.
48. Graybeal JM, Russell GB. Relative agreement between Raman and mass spectrometry for measuring end-tidal carbon dioxide. Respir Care 1994;39:190–194.
49. Mollgaard K. Acoustic gas measurement. Biomed Instr Technol 1989;23:495–497.
50. Block FE, McDonald JS. Sidestream versus mainstream carbon dioxide analyzers. J Clin Monit 1992;8:139–141.
51. Casti A, Gallioli G, Scandroglio G, Passaretta R, Borghi B, Torri G. Accuracy of end-tidal carbon dioxide monitoring using the NBP-75 microstream capnometer. A study in intubated ventilated and spontaneously breathing nonintubated patients. Euro J Anesthesiol 2000;17:622–626.
52. AARC Clinical Practice Guidelines. Capnography/capnometry during mechanical ventilation (2003 update). Respir Care 2003;48:534–539.
53. Shibutani K, Muraoka M, Shirasaki S, Kubal K, Sanchala VT, Gupte P. Do changes in end-tidal PCO_2 quantitatively reflect changes in cardiac output? Anesth Analg 1994;79(5): 829–833.
54. Rackow EC, et al. Sublingual capnometry and indexes of tissue perfusion in patients with circulatory failure. Chest 2001;120:1633–1638.
55. Weil MB, et al. Sublingual capnometry: a new noninvasive measurement for diagnosis and quantitation of severity of circulatory shock. Crit Care Med 1999;27:1225–1229.
56. Marik PE. Sublingual capnography: a clinical validation study. Chest 2001;120:923–927.

57. Kelly JS, Wilhoit RD, Brown RE, James R. Efficacy of the FEF colorimetric end-tidal carbon dioxide detector in children. Anesth Analg 1992;75:45–50.
58. Nakatani K, Yukioka H, Fujimori M, et al. Utility of colorimetric end-tidal carbon dioxide detector for monitoring during prehospital cardiopulmonary resuscitation. Am J Emerg Med 1999;17:203–206.
59. Ornato JP, Garnett AR, Glauser FL, Virginia R. Relationship between cardiac output and the end-tidal carbondioxide tension. Ann Emerg Med 1990;19:1104–1106.
60. White RD, Asplin BR. Out of hospital quantitative monitoring of end-tidal carbondioxide pressure during CPR. Ann Emerg Med 1994;23:25–30.

See also CHROMATOGRAPHY; FIBER OPTICS IN MEDICINE; PERIPHERAL VASCULAR NONINVASIVE MEASUREMENTS.

BLOOD PRESSURE MEASUREMENT

CAN ISIK
Electrical Engineering and
Computer Science Department,
Syracuse University Syracuse,
New York

INTRODUCTION

Blood pressure is an important signal in determining the functional integrity of the cardiovascular system. Scientists and physicians have been interested in blood pressure measurement for a long time. The first blood pressure measurement is attributed to Reverend Stephen Hales, who in the early eighteenth century connected water-filled glass tubes in the arteries of animals and correlated their blood pressures to the height of the column of fluid in the tubes. It was not until the early twentieth century that the blood pressure measurement was introduced into clinical medicine, albeit with many limitations.

Blood pressure measurement techniques are generally put into two broad classes: direct and indirect. Direct techniques of blood pressure measurement, which are also known as invasive techniques, involve a catheter to be inserted into the vascular system. The indirect techniques are noninvasive, with improved patient comfort and safety, but at the expense of accuracy. The accuracy gap between the invasive and the noninvasive methods, however, has been narrowing with the increasing computational power available in portable units, which can crunch elaborate signal processing algorithms in a fraction of a second.

During a cardiac cycle, blood pressure goes through changes, which correspond to the contraction and relaxation of the cardiac muscle, with terminology that identifies different aspects of the cycle. The maximum and minimum pressures over a cardiac cycle are called the systolic and diastolic pressures, respectively. The time average of the cardiac pressure over a cycle is called the mean pressure, and the difference between the systolic and diastolic pressures is called the pulse pressure.

Normal blood pressure varies with age, state of health, and other individual conditions. An infant's typical blood pressure is 80/50 mmHg (10.66/6.66 kPa) (systolic/diastolic). The normal blood pressure increases gradually and reaches 120/80 (15.99/10.66 kPa) for a young adult. Blood pressure is lower during sleep and during pregnancy. Many people experience higher blood pressures in the medical clinic, a phenomenon called the "white coat effect." Therefore, the ranges given in Table 1 are used as guidelines rather than as diagnostic facts.

Table 1. Classification of Blood Pressure for Adults

Category	Systolic—mmHg		Diastolic—mmHg
Normal	<120	and	<80
Prehypertension	120–139	or	80–89
Stage 1 Hypertension	140–159	or	90–99
Stage 2 Hypertension	160 or higher	or	100 or higher

DIRECT TECHNIQUES

The operation of direct measurement techniques can be summarized in very simple terms: They all use a pressure transducer that is coupled to the vascular system through a catheter or cannula that is inserted to a blood vessel, followed by a microcontroller unit with electronics and algorithms for signal conditioning, signal processing, and decision making. There are many advantages of this set of techniques, including:

- The pressure is measured very rapidly, usually within one cardiac cycle.
- The measurement is done to a very high level of accuracy and repeatability.
- The measurement is continuous, resulting in a graph of pressure against time.
- The measurement is motion tolerant.

Therefore, the direct techniques are used when it is necessary to accurately monitor patients' vital signs, for example, during critical care and in the operating room. Although direct techniques have a lot in common, there are differences in the details of various approaches.

Extravascular Transducers

The catheter in this type of device is filled with a saline solution, which transmits the pressure to a chamber that houses the transducer assembly. As a minor disadvantage, this structure affects the measured pressure through the dynamic behavior of the catheter. As the catheter has a known behavior, this effect can be minimized to insignificant levels through computational compensation (1).

Intravascular Transducers

The transducer is at the tip of the catheter in this type of device. Then the measured signal is not affected by the hydraulics of the fluid in the catheter. The catheter diameter is larger in this class of transducers.

Transducer Technology

A wide spectrum of transducer technologies is available to build either kind of transducer. They include metallic or semiconductor strain is gauges, piezoelectric, variable capacitance, variable inductance, and optical fibers. Appropriate driver and interface circuitry accompanies each technology (2).

Other Applications of Direct Pressure Measurement

Another advantage of direct measurement techniques is that they are not limited to measuring the simple arterial pressure. They can be used to obtain central venous, pulmonary arterial, left atrial, right atrial, femoral arterial, umbilical venous, umbilical arterial, and intracranial pressures by inserting the catheter in the desired site (3).

Sources of Errors

Direct blood pressure measurement systems have the flexibility of working with a variety of transducers/probes. It is important that the probes are matched with the appropriate compensation algorithm. Most modern equipment does this matching automatically, eliminating the possibility of operator error. An additional source of error occurs when air bubbles get trapped in the catheter. This changes the fluid dynamics of the catheter, causing an unintended mismatch between the catheter and its signal processing algorithm. This may cause distortions in the waveforms and errors in the numeric pressure values extracted from them. It is difficult to recognize this artifact from the waveforms, so it is best to avoid air bubbles in the catheter.

NONINVASIVE (INDIRECT) TECHNIQUES

An overwhelming majority of blood pressure measurements do not require continuous monitoring or extreme accuracy. Therefore, noninvasive techniques are used in most cases, maximizing patient comfort and safety. Currently available devices for noninvasive measurement are

- Manual devices: These devices use the auscultatory technique.
- Semiautomatic devices: These devices use oscillatory techniques.
- Automatic devices: Although most of these devices use oscillatory techniques, some use pulse-wave velocity or plethysmographic methods.

The Auscultatory Technique

In the traditional, manual, indirect measurement system, an occluding cuff is inflated and a stethoscope is used to listen to the sounds made by the blood flow in the arteries, called Korotkov sounds. When the cuff pressure is above the systolic pressure, blood cannot flow, and no sound is heard. When the cuff pressure is below the diastolic pressure, again, no sound is heard. A manometer connected to the cuff is used to identify the pressures where the transitions from silence to sound to silence are made. This combination of a cuff, an inflating bulb with a release valve, and a manometer is called a sphygmomanometer and the method an auscultatory technique. Usually, the cuff is placed right above the elbow, elevated to the approximate height of the heart, and the stethoscope is placed over the brachial artery. It is possible to palpate the presence of pulse under the cuff, rather than to use a stethoscope to listen to the sounds. The latter approach works especially well in noisy places where it is hard to hear the heart sounds.



Figure 1. Blood pressure waveform, and systolic, diastolic, and mean pressures, from an invasive monitor screen (4).

This method has various sources of potential error. Most of these sources are due to misplacement of the cuff, problems with hearing soft sounds, and using the wrong cuff size. Using a small cuff on a large size arm would result in overestimating the blood pressure, and vice versa. Nevertheless, an auscultatory measurement performed by an expert healthcare professional using a clinical grade sphygmomanometer is considered to be the gold standard in noninvasive measurements.

Oscillatory Techniques

Most automatic devices base their blood pressure estimations on the variations in the pressure of the occluding cuff, as the cuff is inflated or deflated. These variations are due to the combination of two effects: the controlled inflation or deflation of the cuff and the effect of the arterial pressure changes under the cuff. The Korotkov sounds are not used in the oscillatory techniques.

The cuff pressure variation data may be collected while the cuff is being inflated or deflated. Furthermore, the inflation or deflation during the data collection may be controlled in a continuous fashion or in a step-wise fashion. This variability gives four different strategies in data collection. Their differences may seem insignificant at first, but they have significant effects on the way a variety of algorithms are designed.

Data in Fig. 2 were collected using an experimental system. The cuff is first rapidly inflated to a value higher than the anticipated systolic pressure, an approximate pressure of 170 mmHg (22.66 kPa) in this case. Then it is deflated in small steps until the cuff pressure is below the anticipated diastolic pressure, ~50 mmHg (6.66 kPa). Please note that when the cuff pressure is very high or very low, the arterial blood pressure variations contribute very little to the cuff pressure trajectory. As a matter of fact, the height of those pulses above the cuff pressure baseline is at their maximum when the baseline pressure is equal to the mean arterial pressure (MAP). We demonstrate this in Fig. 3, with a plot of pulses relative to their baseline pressure (pulse-wave amplitude), against their respective baseline cuff pressures. Please note that only



Figure 2. Cuff pressure trajectory when data are collected during step-wise deflation of the cuff (5).



Figure 4. Cuff pressure trajectory and pulse-wave amplitude when data are collected during continuous inflation of the cuff.

a few of the pulses observed in Fig. 2 are transferred to Fig. 3 to maintain clarity.

Figure 4 shows a cycle of data collected during the continuous inflation of the cuff as well as the pulse-wave amplitude. The pulse-wave amplitude is obtained by subtracting the baseline cuff pressure from the raw pressure data. Next, we will return to the example developed in Figs. 2 and 3 and continue with the estimation of blood pressure values.

It seems trivial to pick the pulse with the tallest height above baseline and to select its baseline pressure to be the MAP. So, for the example at hand, MAP would be just under 100 mmHg (13.33 kPa), as shown in Fig. 5. The systolic and diastolic pressures are then estimated from the MAP using a variety of heuristic rules. A common class of these heuristic rules works as follows. First, the peak values (heights) of the pulse-wave amplitudes are connected to form an envelope. Again, the baseline pressure at the peak of this envelope is the MAP value. Then, the height of the MAP pulse is reduced by a predetermined systolic ratio, and the intersection of this "systolic height" with the envelope to the right of the MAP pulse is selected as the systolic location. The baseline pressure at this location is assigned as the estimate of the systolic pressure, as depicted in Fig. 5. The diastolic pressure is estimated in a similar fashion by using a ratio of its own to arrive at the diastolic height and then by finding the corresponding intersection with the envelope to the left of the MAP pulse.

In the example shown in Fig. 5, the systolic ratio and diastolic ratio were arbitrarily selected as 0.5 and 0.7, respectively. In a realistic system, those ratios would be found statistically (using methods such as regression, fuzzy rule-based systems, neural networks, or evolutionary algorithms) to minimize deviations between estimated and actual blood pressure values.

Algorithmic Components of Blood Pressure Measurement

In the earlier measurement units, it was a combination of hardware and software that controlled the various aspects of the automated measurement (or estimation) of blood pressure. With the ever increasing computational power of microcontrollers, all decision making and control are now implemented in software and with more elaborate algorithms. Here are some functions that are included in a measurement system. Please refer to Fig. 6 for a typical organization of such algorithms in a blood pressure measurement system.

- **Inflation/deflation control**: Whether data collection is done during inflation or deflation, continuously



Figure 3. Pulse-wave amplitude profile (6).



Figure 5. Blood pressure estimation from pulse-wave amplitude profile.


Inflation/ Deflation Control
Cuff
Algorithm Management/ Cycle Control
Blood Pressure Estimation/ Display
Pulse Profile/ Feature Extraction
Cuff Pressure Measurement

Figure 6. A typical organization of algorithmic components of (oscillatory) blood pressure measurement.

or in steps, there are many challenges to appropriately controlling the air pump. They include maintaining a smooth baseline cuff pressure without filtering out the arterial variations; adjusting the pump speed to variations arising from different cuff sizes, arm sizes, and cuff tightness; and selecting the range of cuff pressures for which data will be collected.

- **Pulse detection**: This is a fundamental part of extracting features from raw cuff pressure data. It becomes especially challenging when conditions such as arrhythmia, or tremors, affect the regularity of pulses. Pattern recognition techniques with features found in time, frequency, or wavelet domains are used to deal with difficult situations.
- **Blood pressure estimation**: The indirect method of measurement is a process of estimating pressures with the use of features extracted from cuff-pressures or other transducer data. This algorithm used to be limited to linear interpolation, as described in the example of Fig. 5. Recently, more elaborate decision-making and modeling tools such as nonlinear regression, neural networks, and fuzzy logic also are being used for this purpose.

Sources of Inaccuracy

Many factors contribute to the inaccuracies in the automated measurement of blood pressure. The following are some of the more significant sources of error:

- **Sparseness of data**: An important design criterion of a blood pressure monitor is to go through a cycle as quickly as possible. However, the faster a device functions, the fewer pulses it will have in a cycle. A cycle time of 1 min would yield about 60–70 pulses, whereas a 20-min cycle would have only 20–23 pulses. The oscillatory techniques are based on collecting cuff pressure due to pulses at baseline pressures that change from above systolic to below diastolic. If we divide a cuff pressure range of about 150–180 mmHg (10.99–23.99 kPa) by the number of pulses in a cycle, we can see that the baseline increment between successive pulses varies from 2 to 3 mmHg (0.26 to 0.39 kPa) in a 1 min cycle to 6 to 9 mmHg (0.79 to 1.19 kPa) in a 20 s cycle. This quantization error affects the accuracy in the estimate of the mean arterial pressure as well as the shape of the pulse envelope, hence, the accuracy of the systolic and diastolic values. Various curve-fitting and interpolation techniques are used to remedy this problem.
- **Pulse extraction uncertainty**: Whether the baseline cuff pressure is varied continuously or in steps, figuring out where one pulse ends and another one starts is not a trivial matter. An inspection of Fig. 2 will show that many artifacts in the data stream may confuse a pulse extraction algorithm and cause errors in the pulse-wave amplitude profile in Fig. 3. In addition, common factors such as an irregularity in the pulses as in arrhythmia, small wrinkles, or folds in the cuff changing its volume suddenly during data collection, or small movements of the patient may amplify those artifacts. A variety of pattern recognition techniques are employed to improve the accuracy of pulse detection (7).
- **Motion artifacts**: The performance of the oscillatory techniques depends on all measurements during a cycle. Therefore, any error caused by a motion of the patient may affect the accuracy of the blood pressure estimations. A comparative study of six noninvasive devices has found that average percent errors due to motion artifacts may be as high as 39% (8). Remedies to this source of error may be a combination of three strategies: (*1*) to identify and compensate for minor artifacts, (*2*) to identify and discard data that include significant artifacts or to repeat the entire cycle if the estimates are deemed unreliable, and (*3*) to incorporate features from additional sensors or monitors such as electrocardiogram (EKG) to help identify motion artifacts (8,9).

Other Blood Pressure Measurement Techniques

Oscillometry is by far the most common technique in automatic noninvasive blood pressure measurement. However, other methods are found in commercial units or in units that are being developed. In this section, a few of these methods are summarized and references are given for further information. It should be noted that algorithmic components and sources of inaccuracy presented within the context of oscillatory technique may apply to other automated measurement methods.

Arterial Tonometry. This relatively new technique in blood pressure measurement is inspired by the tonometry devices that were made in the mid-1950s to measure intraocular pressure. The arterial tonometry device is based on a pressure sensor and pneumatic actuator combination, which is placed on the wrist, above the radial artery. When the pressure applied on the artery is adjusted to the appropriate level (called the hold-down pressure), the portion of the artery wall that is facing the actuator is partially flattened. This configuration maximizes the energy transfer between the artery and the sensor, yielding pulses with the highest amplitude. The relative amplitudes of the tonometry pulses are calibrated to the systolic and the diastolic pressures. Tonometry is suitable for continuous monitoring applications. Sensor placement sensitivity, calibration difficulties, and motion sensitivity are problems that need improvement (10,11).

Pulse-Wave Velocity. A pulse wave is generated by the heart as it pumps blood, and it travels ahead of the pumped blood. By solving analytical equations of fluid dynamics, it has been shown that changes in blood pressure heavily depend on changes in pulse-wave velocity. Blood pressure can be continuously calculated from pulse wave velocity, which in turn is calculated from EKG parameters and peripheral pulse wave measured by an $S\mathrm{pO}_2$ probe on the finger or toe. This method is suitable for continuous monitoring as well as for detecting sudden changes in blood pressure to trigger an oscillometric cycle (12).

Plethysmographic Methods. In this method, changes in the blood volume during a cardiac cycle are sensed using a light emitter and receiver at the finger. Tissue and blood have different infrared light absorbance characteristics. That is, the tissue is practically transparent to the infrared light, whereas blood is opaque to it. A prototype of a ring-like sensor/signal processor/transmitter combination has been reported (13,14)

DIFFERENT FORMS OF BLOOD PRESSURE MEASUREMENT DEVICES

The techniques, algorithms, and transducers discussed in the previous sections have led to a variety of forms of devices, differentiated by where in the body the measurements are taken, or for what purpose the device is used.

Ambulatory Blood Pressure Monitoring

These portable and wearable devices monitor the patient's blood pressure over a long period, say for 24 h. While the patient is following her daily routine, the device periodically takes measurements and saves the results. These measurements are later downloaded for analysis by a physician. The first ambulatory devices, introduced in the early 1960s, were rudimentary and used tape recorders to capture the Korotkoff sounds with an occluding cuff. Most current ambulatory devices use the oscillatory technique. As the patient is subjected to repeated blood pressure measurements with an ambulatory device, it is essential to improve motion tolerance, patient comfort, measurement time, and of course overall accuracy of measurement algorithms that are employed in ambulatory monitors (15).

Ambulatory devices have been instrumental in clinical research and practice. Through their use, there have been significant improvements in our understanding of blood pressure dynamics in a variety of physiological and psychological conditions, and concepts such as "white-coat hypertension," "episodic hypertension," and "circadian rhythm of blood pressure" (e.g., daytime/nighttime variations of blood pressure) have been investigated and added to the medical lexicon (16).

Wrist Blood Pressure Monitoring

These monitors have smaller cuffs than their upperarm-attached counterparts. Hence, they are more compact and more conducive to self-measurement. It is important that the monitors are held at the heart level for correct measurement. They are popular with the home users but typically less accurate than the full-size arm monitors.

Finger Blood Pressure Monitoring

Finger monitors are not nearly as common as the arm or wrist monitors. The approaches used are auscultatory and plethysmographic.

Semiautomatic Blood Pressure Monitoring

The semiautomatic devices have cuffs that are inflated manually by an attached bulb, like a sphygmomanometer. Once the cuff is inflated, the monitor functions in the same manner as an automatic device, taking cuff-pressure measurements while releasing the pressure in a controlled way. These devices are more economical and have longer battery lives than their fully automated counterparts.

ACCURACY OF BLOOD PRESSURE MEASUREMENT DEVICES

Blood pressure measurement devices play an important role in medicine, as they measure one fundamental vital sign. In addition to this traditional use, noninvasive blood pressure devices, especially the automated ones, have become ubiquitous in the home, regularly used by lay people. Two widely used protocols for testing the accuracy of these devices are those set by the Association for the Advancement of Medical Instrumentation (AAMI), a pass/fail system published in 1987 and revised in 1993, and the protocols of the British Hypertension Society (BHS), an A–D graded system, established in 1990 and revised in 1993. These protocols describe in detail the process manufacturers should follow in validating the accuracy of their devices. Their numeric accuracy thresholds can be summarized as follows. A device would pass the AAMI protocols if its measurement error has a mean of no >5 mmHg (0.66 kPa) and a standard deviation of no >8 mmHg (1.06 kPa). The BHS protocol would grant a grade of A to a device if in its measurements 60% of the errors are within 5 mmHg, 85% of the errors are within 10 mmHg (1.33 kPa), and 95% within 15 mmHg (1.99 kPa). BHS has progressively less stringent criteria for the grades of B and C, and it assigns a grade D if a device performs worse than C.

The European Society of Hypertension introduced in 2002 the International Protocol for validation of blood pressure measuring devices in adults (17). The working group that developed this protocol had the benefit of analyzing many studies performed according to the AAMI and BHS standards. One of their motivations was to make the validation process simpler, without compromising its ability to assess the quality of a device. They achieved it by simplifying the rules for selecting subjects for the study. Another change was to devise a multistage process that recognized devices with poor accuracy early on. This is a pass/fail process, using performance requirements with multiple error bands.

Whether blood pressure measurement devices are used by professionals or lay people, their accuracy is important.

Table 2. Summary of Accuracy of Blood Pressure Measurement Devices

Device Type	Number Surveyed	Recommended?		
		Yes	Questionable	No
Manual, clinical	4	1	1	2
Auto, clinical	6	3	2	1
Auto, home, arm	20	4	4	12
Auto, home, wrist	4	0	2	2
Ambulatory	50	26	5	19
Total	84	34	14	36

Yet, most devices in the market have not been evaluated for accuracy independently, using the established protocols (18). In their study, O'Brien et al. surveyed published independent evaluations of manual sphygmomanometers, automated devices for clinical use, and automated devices for personal use. If a device was found acceptable by AAMI standards, and received a grade of A or B by BHS standards, for both systolic and diastolic measurements, then it was "recommended". Otherwise it was not recommended. Few studies they surveyed had issues such as specificity, so devices reported in those studies were "questionably recommended."

Table 2 summarizes the result of their survey. It is interesting to note that of the four clinical grade sphygmomanometers, a kind that is highly regarded by health-care providers, only one was "recommended". Overall, the number of devices "not recommended" is more than the number of "recommended" devices. What one should take away from this analysis is that at every level of quality, price, and target market, it is essential to research the accuracy of a device before investing in it and relying on it.

BIBLIOGRAPHY

Cited References

1. Gibbs NC, Gardner RM. Dynamics of invasive pressure monitoring systems: Clinical and laboratory evaluation. Heart Lung 1988;17:43–51.
2. Webster JG, editor. Medical Instrumentation: Application and Design, 3rd ed. New York: Wiley; 1998.
3. Hambly P. Measuring the blood pressure. Update Anaesthesia 2000;11(6).
4. Philips Invasive Monitoring literature. Available at http://www.medical.philips.com/main/products/patientmonitoring/products/invasivepressure/.
5. Colak S, Isik C. Blood pressure estimation using neural networks. IEEE International Conference on Computational Intelligence for Measurement Systems and Applications, Boston, July 2004.
6. Colak S, Isik C. Fuzzy pulse qualifier. 23rd International Conference of the North American Fuzzy Information Processing Society (NAFIPS 2004) Proceedings, Banff, June 2004.
7. Osowski S, Linh TH. ECG beat recognition using fuzzy hybrid neural network. IEEE Trans Biomed Eng 2001;48:1265–1271.
8. Revision Labs, Beaverton, OR, Noninvasive Blood Pressure Measurement and Motion Artifact: A Comparative Study, December 3, 1998. Available at http://www.monitoring.welchallyn.com/pdfs/smartcufwhitepaper.pdf.
9. Dowling Jr NB. Measuring blood pressure in noisy environments. US patent No. 6,258,037 B1, July 10, 2001.
10. Sato T, Nishinaga M, Kawamoto A, Ozawa T, Takatsuji H. Accuracy of a continuous blood pressure monitor based on arterial tonometry. Hypertension 1993;21:866–874.
11. Matthys K, Verdonck P. Development and modelling of arterial applanation tonometry: A review. Technol Health Care 2002;10:65–76.
12. Williams B. Pulse wave analysis and hypertension: Evangelism versus skepticism. J Hypertension 2004;22:447–449.
13. Yang BH, Asada HH, Zhang Y. Cuff-less continuous monitoring of blood pressure, d'Arbeloff Laboratory of Information Systems and Technology, MIT, Progress Report No. 2–5, March 31, 2000. Available at http://darbelofflab.mit.edu/ProgressReports/HomeAutomation/Report2-5/Chapter01.pdf.
14. Rhee S, Yang BH, Asada HH. Artifact-resistant power-efficient design of finger-ring plethysmographic sensors. IEEE Trans Biomed Eng 2001;48:795–805.
15. McGrath BP. Ambulatory blood pressure monitoring. Med J Australia 2002;176:588–592.
16. National High Blood Pressure Education Program (NHBPEP) Working Group Report On Ambulatory Blood Pressure Monitoring. NIH Publication 92-3028. Reprinted February 1992. Available at http://www.nhlbi.nih.gov/health/prof/heart/hbp/abpm.txt.
17. O'Brien E, Pickering T, Asmar R, Myers M, Parati G, Staessen J, Mengden T, Imai Y, Waeber B, Palatini P. Working Group on Blood Pressure Monitoring of the European Society of Hypertension International Protocol for validation of blood pressure measuring devices in adults. Blood Pressure Monitoring 2002;7:3–17. Available at http://www.eshonline.org/documents/InternationalPS2002.04.29.pdf.
18. O'Brien E, Waeber B, Parati G, Staessen J, Myers MG. Blood pressure measuring devices: Recommendations of the European Society of Hypertension. Br Med J 2001;398. Available at http://bmj.bmjjournals.com/cgi/content/full/322/7285/531.

Further Reading

O'Brien E, Atkins N, Staessen J. State of the market: A review of ambulatory blood pressure monitoring devices. *Hypertension* 1995;26:835–842.

U.S. Food And Drug Administration. Non-Invasive Blood Pressure (NIBP) Monitor Guidance. March 10, 1997. Available at http://www.fda.gov/cdrh/ode/noninvas.html.

See also ARTERIES, ELASTIC PROPERTIES OF; BLOOD PRESSURE, AUTOMATIC CONTROL OF; CAPACITIVE MICROSENSORS FOR BIOMEDICAL APPLICATIONS; LINEAR VARIABLE DIFFERENTIAL TRANSFORMERS.

BLOOD PRESSURE, AUTOMATIC CONTROL OF

YIH-CHOUNG YU
Lafayette College
Easton, Pennsylvania

INTRODUCTION

Arterial pressure is one of the vital indexes of organ perfusion in human bodies. Generally speaking, blood pressure is determined by the amount of blood the heart pumps and the diameter of the arteries receiving blood from the heart. Several factors influence blood pressure. The nervous system helps to maintain blood pressure by adjusting the size of the blood vessels, and by influencing the heart's pumping action. The heart pumps blood to make sure a sufficient amount of blood circulates to all the body tissues for organ perfusion. The more blood the heart pumps and the smaller the arteries, the higher the blood pressure is. The kidneys also play a major role in the regulation of blood pressure. Kidneys secrete the hormone rennin, which causes arteries to contract, thereby raising blood pressure. The kidneys also control the fluid volume of blood, either by retaining salt or excreting salt into urine. When kidneys retain salt in the bloodstream, the salt attracts water, increasing the fluid volume of blood. As a higher volume of blood passes through arteries, it increases blood pressure.

Hypertension is defined as abnormal high systemic arterial blood pressure, systolic and diastolic arterial pressures > 140 and 95 mmHg (18.662 and 12.664 kPa). The causes of hypertension might be due to acute myocardial infarction, congestive heart failure, and malignant hypertension. Postoperative cardiac patients may experience hypertension because of pain, hypothermia, reflex vasoconstriction from cardiopulmonary bypass, derangement of the rennin-angiotension system, and ventilation difficulties. A prolonged postoperative hypertension could lead to complications, including myocardial ischemia, myocardial infarction, suture line rupture, excessive bleeding, and arrhythmia. As a result, clinical treatment to postoperative hypertension is needed to reduce the potential risk of complications.

Postoperative hypertension is usually treated pharmacologically in the intensive care unit (ICU). Sodium nitroprusside (SNP) is one of the most frequently used pharmaceutical agents to treat hypertensive patients and is a vasodilating drug that can reduce the peripheral resistance of the blood vessel, and thus causes the reduction of arterial blood pressure. A desired mean arterial pressure (MAP) can be achieved by monitoring MAP and regulating the rate of SNP infusion. The mean arterial pressure can be measured from a patient by using an arterial pressure transducer with appropriate signal amplification. Low pass filtering is used to remove high frequency noise in the pressure signal and provide MAP for monitoring purpose. Administration of SNP infusion could be performed by manual operation. The drug infusion rate should be adjusted frequently in response to the spontaneous pressure variation and patient's condition changes. In addition, blood pressure response to the drug infusion changes over time and varies from patient to patient. Therefore, this manual approach is extremely difficult and time consuming for the ICU personnel. As the result, the use of control techniques to regulate the infusion of the pharmaceutical agents and maintain MAP within a desired level automatically has been developed in the last 30 years.

IVAC Corporation developed an automatic device, TITRATOR, to infuse SNP and regulate MAP in postoperative cardiac patients in early 1990s. Clinical evaluation for the clinical impact of this device in multiple centers was reported by Chitwood et al. (1). Patients who participate in this trial were treated by either automatic or manual control. The automated group showed a significant reduction in the number of hypertensive episodes per patient. Chest tube drainage, percentage of patients receiving transfusion, and total amount transfused were all reduced significantly by the use of an automated titration system. Although TITRATOR was not commercialized successfully due to economic reasons, the promising clinical experiences encouraged future development of automatic blood pressure regulation devices.

An automatic blood pressure control system usually includes three components: sensors, a controller, and a drug delivery pump. This article provides an overview of automatic control schemes, including proportional-integral-derivative (PID) controllers, adaptive-controllers, rule-based controllers, and artificial neural network controllers that regulate mean arterial blood pressure using SNP. A brief description of each control strategy is provided, followed by examples from literature. Testing of the control performance in computer simulations, animal studies, and clinical trials, is also discussed.

CONTROL SCHEMES

PID Controller

The PID control of MAP determines the SNP infusion rate, $u(t)$, based on the difference between the desired output and the actual output,

$$u(t) = K_P e(t) + K_I \int_{t_0}^{t_1} e(t)dt + K_D \frac{d}{dt} e(t) \qquad (1)$$

where $e(t) = P_d(t) - P_m(t)$, $P_d(t)$ is the desired MAP, and $P_m(t)$ is the actual mean arterial pressure. The parameters K_P, K_I, and K_D are the proportional, integral, and differentiation gain respectively. The design of this type of controller involves the selection of appropriate control gains, K_P, K_I, and K_D, such that the actual blood pressure, $P_m(t)$, can be stabilized and maintained close to the desired level, $P_d(t)$. Typical components of the automatic blood pressure control system, including the PID controller, the infusion pump, the patient, as well as the patient monitor along with physiologic sensors are illustrated in Fig. 1.

Sheppard and co-worker (2–4) developed a PI-type controller, by setting $K_D = 0$ in (1), to regulate SNP, which has been tested over thousands of postcardiac-surgery patients in the ICU. The control gains were tuned to satisfy an acceptable settling time with minimal overshoot. The discrete-time PI controller updates the infusion rate as

$$u(k) = u(k-1) + \Delta u(k) \qquad (2)$$

where $u(k-1)$ is the previous infusion rate a minute ago and $\Delta u(k)$ is the infusion rate increment defined by,

$$\Delta u(k) = K\{0.4512\, e(k) + 0.4512\, [e(k) - e(k-1)]\} \qquad (3)$$

where $e(k)$ and $e(k-1)$ are the current and previous error, respectively. The gain K in Eq. 3 as well as the further correction of $\Delta u(k)$ were determined by the region of current MAP $P_m(k)$ as described in the following:



Figure 1. Proportional-integral-derivative control scheme of blood pressure control.

Rule 1 If $P_m(k) \geq P_d + 5$, then $K = -1$ and $\Delta u(k) = \Delta u(k)$ from Eqs. 3–2

Rule 2 If $P_d \leq P_m(k) < P_d + 5$, then $K = -0.5$ and $\Delta u(k) = \Delta u(k)$ from Eq. 3

Rule 3 If $P_d - 5 \leq P_m(k) < P_d$, then $K = -1$ and $\Delta u(k) = \Delta u(k)$ from Eq. 3

Rule 4 If $P_m(k) \leq P_d - 5$, then $K = -2$ and $\Delta u(k) = \Delta u(k)$ from Eq. 3

Rule 5 If $P_m(k) < P_d - 5$ and $\Delta u(k) > 0$, then $\Delta u(k) = 0$

Rule 6 If $P_m(k) \geq P_d$ and $\Delta u(k) > 7$, then $\Delta u(k) = 7$

These rules were designed to provide a boundary for the controller and achieve the optimal performance with the minimal pharmacological intervention. As a result, the controller is a nonlinear PI-type controller.

The automatic blood pressure controller described herein performed better than human operation in a comparison study (5). Automatic blood pressure regulation exhibits approximately one-half of the variation observed during manual control; MAP are more tightly distributed about the set-point, as shown in Fig. 2 (2). Forty-nine postcardiac surgery patients in ICU were managed by the automatic controller. The patients' MAPs were maintained within ±5 mmHg (±0.667 kPa) of the desired MAP 94% of the total operation time (103 out of the 110 operation hours). A group of 37 patients were managed with manual operation provided by experienced personals, with which only 52% of the time the patients' MAPs were within the prescribed range.

Adaptive Controller

The PID controller considered previously was with the control gains determined prior to their implementation. The control gains were usually tuned to satisfy the performance criterion in simulation or animal studies where the parameters characterizing the system dynamics were fixed variables. In clinical applications, the cardiovascular vascular dynamics change over time as well as from patient to patient. In addition, the sensitivity to drugs varies from one patient to another and even with the same patient at different instant. Therefore, it would be beneficial if the control gains can be adjusted automatically during operation to adapt the differences between patients as well as physiologic condition changes in a patient over time. This type of controllers is called adaptive controller.

An adaptive control system usually requires a model, representing plant (the patient and the drug infusion system) dynamics. Linear black box models, expressed by

$$\begin{aligned} y(k) &= \frac{B(q^{-1})}{A(q^{-1})}u(k) + \frac{C(q^{-1})}{A(q^{-1})}n(k) \\ A(q^{-1}) &= 1 + a_1q^{-1} + a_2q^{-2} + \cdots + a_nq^{-n} \\ B(q^{-1}) &= 1 + b_1q^{-1} + b_2q^{-2} + \cdots + b_lq^{-l} \\ C(q^{-1}) &= 1 + c_1q^{-1} + c_2q^{-2} + \cdots + c_mq^{-m} \end{aligned} \tag{4}$$

are typically used to represent the plant dynamics. A, B, and C are polynomials in the discrete shift operator q, where a_i, b_i, and c_i are coefficients in the polynomials; $y(k)$, $u(k)$, and $n(k)$ are the model input, output, and noise, respectively. Depending on the polynomials B and C, the model in Eq. 4 can be classified as autoregressive [AR, $B(q^{-1}) = 0$, $C(q^{-1}) = 1$], autoregressive with inputs [ARX, $C(q^{-1}) = 1$], autoregressive moving average [ARMA, $B(q^{-1}) = 0$], and autoregressive moving average with inputs (ARMAX). The coefficients of the polynomials are time-varying, much slower than the plant dynamic changes. The controller updates the control input, $u(k)$, by taking the model parameter changes into consideration. General reviews and descriptions on adaptive control theory can be found in literature (6–8). Three types of adaptive control schemes are frequently used in blood pressure controller design: self-tuning regulator, model reference adaptive control, and multiple model adaptive control.

Self-Tuning Regulator. The self-tuning regulator (STR) is based on the idea of separating the estimation of unknown parameters from the design of the controller. It is assumed that a priori knowledge of the model structure, that is, l, m, and n in Eq. 4. In choosing l, m, and n, one must compromise between obtaining an accurate representation of the system dynamics while keeping the system representation simple. The parameters of the regulator are adjusted by using a recursive parameter estimator and a



Figure 2. Comparison of manually controlled SNP infusion with computer control in the same patient. (Redrawn with permission from L.C. Sheppard, Computer control of the infusion of vasoactive drugs, *Ann. of Biomed. Eng.*, Vol. 8: 431–444, 1980. Pergamon Press, Ltd.)

regulator design calculation as shown in Fig. 3. The parameter estimates are treated as if they are true or at least asymptotically the true parameters. Several algorithms are available for parameter estimation, including recursive least-squares, generalized least-squares, stochastic approximation, maximum likelihood, instrumental variables, and Kalman filter. Every technique has its advantages and disadvantages. Descriptions of parameter estimation algorithms can be found in (9). Various approaches are available for regulator design calculation, such as minimum variance, gain and phase margin analysis, pole placement, and linear quadratic Gaussian (LQG). More detailed information of STR can be found in literature (6–8).

Various STR-type blood pressure controllers have been developed and tested in computer simulations, animal experiments, as well as clinical studies. Arnsparger et al. (10) used a second-order ARMA model to design the STR. A recursive least-mean-squares estimator was used to estimate the model parameters. The parameter estimates were then used to calculate the control signal, the drug infusion rate, based upon a minimum variance or a one-step-ahead control law. Both algorithms were implemented in microprocessor and tested in dog experiments for comparison. Both controllers were able to maintain the MAP at the desired level. However, the one-step-ahead controller performed better in the test with less variation in the infusion rate.



Figure 3. Configuration of self-tuning regulator for blood pressure control.

A combination of proportional derivative with minimum variance adaptive controller was designed by Meline et al. (11) to regulate MAP using SNP. The plant dynamics was represented by a fifth-order ARMAX model, while the model parameters were estimated through a recursive least-squares algorithm. The controller was tested on ten dog experiments as well as human subjects (12). Twenty patients with postsurgical hypertension were randomly assigned to either the manual group, where SNP was administrated by experience nurse, or the automatic group. Statistical analysis showed that MAP was maintained within ± 10% from the desired MAP for 83.3% of the total operation time in the "automatic" group versus 66.1% of the total operation time in the "manual" group. This implies the automatic control performed better than the manual operation.

A pole-assignment STR was designed by Mansour and Linkens (13) to regulate blood pressure using a fifth-order ARMAX model. The model parameters were identified through a recursive weighted least-squares estimator. These parameters were then used to determine appropriate feedback gains for the controller. Pole-placement algorithm was used because of its robustness to a system with nonminimum phase behavior or unknown time delay. Effectiveness of the controller was evaluated extensively in computer simulation, using a clinically validated model developed by Slate (3) as shown in Fig. 4(2). The controller demonstrated a robust performance even with the inclusion of the recirculation term or a variable time delay.

Voss et al. (14) developed a control advance moving average controller (CAMAC) to simultaneously regulate arterial pressure and cardiac output (CO) using SNP and dobutamine. CAMAC is a multivariable STR, which has the advantage of controlling nonminimum phase plants with unknown or varying dead times. The controller determines the drug infusion rates based on the desired MAP and CO, past inputs, past outputs, and a on-line recursive least-squares estimator with an exponential forgetting factor identifying the subject's response to the drugs.


INFUSION RATE
I(s)
i(t)
$G_d(s)$
TRANSFER FUNCTION
CHANGE DUE TO DRUG
$\Delta P_d(s)$
$\Delta P_d(t)$
ARTERIAL PRESSURE
$P_a(t)$
$\frac{1}{2s+1}$
MEASUREMENT SYSTEM
MEAN ARTERIAL PRESSURE
$\bar{P}_a(t)$
BACKGROUND ACTIVITY
$P_{ba}(t)$
BROAD BAND RANDOM INPUT
$\frac{K_{sq}}{(30s+1)^2}$
STOCHASTIC ACTIVITY
RESPIRATION
D.C. PRESSURE
$\frac{1}{240s+1}$
RENIN – ANGIOTENSIN REFLEX

Figure 4. Model of MAP in response to SNP infusion. (Redrawn with permission from L.C. Sheppard, Computer control of the infusion of vasoactive drugs, *Ann. Biomed. Eng.* 1980; 8: 431–444. Pergamon Press, Ltd.)

The plant model for designing the controller and estimator was a second-order ARMAX model. The control algorithm was designed and tested in simulations prior to dog experiments. Although animal studies demonstrated that the controller was capable to maintain MAP and CO at their desired level, changing vasomotor tone and the lack of high frequency excitation signals could lead to inaccuracy in the parameter estimation, causing poor performance in transient response.

Model Reference Adaptive Control. The basic principle of the model reference adaptive control is illustrated in Fig. 5). The desired input–output response is specified by the reference model. The parameters of the regulator are adjusted by the error signal, the difference between the reference model output and the system output, such that the system output follows the reference output. More detailed information about MRAC can be found in Ref. 7.

The use of MRAC to regulate blood pressure was introduced by Kaufmann et al. (15). The format of the reference model was adopted form that developed by Slate (3). Controller design and evaluation were carried out in computer simulation. The controller with adaptation gains showed lower steady-state error than that with nonadaptive gains in simulations, particularly when a process disturbance was introduced. Animal studies were conducted to compare the performance of the MRAC with that of a well-tuned PI controller. Neosynephrine was introduced to change the transfer function characteristics of the subjects during experiments. The MRAC was superior to the PI controller and maintained MAP closed to the reference with an error within ±5 mmHg (±0.667 kPa) regardless of the plant characteristic changes due to drug intervention.

Pajunen et al. (16) designed a MRAC to regulate blood pressure using SNP with the ability to adjust the reference model by learning the patient's characteristics, represented by the model parameters, coefficients and time delays, of the transfer function. These model parameters were assumed to be unknown and exponentially time-varying. The time-varying reference model was automatically tuned to achieve the optimal performance while meeting the physical and clinical constraints imposed on the drug infusion rate and MAP. Extensive computer simulation was used to evaluate the robustness of the controller. The MAP was maintained within ±15 mmHg (±2 kPa) around the set-point regardless of changes in patient's characteristics and the presence of high level noises.

Polycarpou and Conway (17) designed a MRAC to regulate MAP by adjusting SNP infusion rate. The plant model was a second-order model discretized from the Slate's model (3). Time delay terms in the model were assumed to be known while the model parameters were constant with nonlinear terms. The constant terms were assumed to be known and the nonlinear terms were estimated by a radial basis function (RBF) neural network. The resulting parameter estimates were then used to update the control law such that the system output follows the reference model. Although the RBF was able to model the unknown nonlinearity and thus improve the closed-loop characteristics in computer simulation, the


Reference Model
Adaptation
$e(t)$
−
+
Blood Pressure Transducer
Patient
$P_d(t)$
+
−
Controller
$u(t)$
Drug Infusion Pump
$P_m(t)$

Figure 5. Configuration of MRAC for blood pressure regulation.

assumption that the model parameters and time delays were known would need further justification in practical applications.

Multiple Model Adaptive Control. The concept of multiple model adaptive control (MMAC) was first introduced by Lainiotis (18). This technique assumes that the plant response to the input can be represented by a bank of models. A controller is designed *a priori* to give a specified performance for each particular model. A probability, $P(q_i\,|\,t)$, describing the accuracy of each model, q_i, to represent the actual system, is calculated and used as the weighting factor to update the control input,

$$u = \sum_{i=1}^{N} u_i \cdot P(q_i|t) \qquad (5)$$

where u_{i} is the control input based on the model q_{i}. As the response of the system changes, the probability, $P(q_{\mathrm{i}}\,|\,t)$, will also be adjusted accordingly such that the model closest represents current dynamics gets the greatest probability. As a result, the contribution of the control input, obtained from the model with the greatest probability, to the updated control input in equation 5 is more significant than the inputs from other models with lower probabilities. Configuration of the MMAC is illustrated in Fig. 6.

He et al. (19) introduced the first blood pressure controller using the MMAC technique. There were eight plant models derived from Slate's model (3) for controller design. Each plant model contains a constant model gain between 0.32 and 6.8, representing the plant gain of 0.25–9 in Slate's model (3), along with the same time constants and delays at their nominal values. A proportional-plus-integral (PI) type controller was designed for each plant model. These controllers were with the same time constant but different gains. Computer simulation was used to test the controller performance in response to the variations of model parameters and the presence of background noise. The controller was able to settle MAP within 10 min with the error within ± 10 mmHg (± 1.333 kPa) from the set-point. The control algorithm was further tested in animal experiments. The controller stabilized MAP in < 10 min with ± 5 mmHg (± 0.667 kPa) error from its set-point, regardless of the plant characteristic changes due to neosynephrine injection, the sensitivity of the subject to the SNP infusion, and the background noise. The mean error was < 3 mmHg (0.4 kPa) over the entire studies.

Martin et al. (20) developed a MMAC blood pressure controller with seven models modified from Slate's model (3). The model gains in the seven models were from 0.33 to 9.03 to cover the variation of the plant gain between 0.25 and 10.86. The other model parameters were held constant at their nominal values. A pole-placement compensator was designed for each model. A Smith predictor was used to remove the effects of infusion delay, and thus simplify the control analysis and design. A PI unit was included to achieve zero steady-state error. Two constrains were used to limit the infusion rate when the patient's blood pressure is too low or the resulting SNP infusion rate from the controller is beyond the preset threshold. The controller was able to maintain MAP with the settling time < 10 min, the maximum overshoot < 10 mmHg (1.333 kPa), and the steady-state error within ± 5 mmHg (± 0.667 kPa) around the pressure set-point in computer simulations. The controller was also tested on 5 dogs as well as 19 patients during cardiac surgery with the aid of a supervisor module, which oversees the overall environment and thus improves the safety (21,22).

Yu et al. (23) designed a MMAC to control MAP and CO by adjusting the infusion rates of SNP and dopamine for congested heart failure subjects. There were 36 linear multiinput and multioutput (MIMO) models, represented by first-order transfer functions with time delays, to cover the entire range of possible dynamics. A model predictive controller [MPC, (24)] was designed for each individual model to find a sequence of control signals such that a quadratic cost function can be minimized. In order to save computation time, only the control signals corresponding to the six models with the highest probability weights were used to determine the drug infusion rates. The control



Figure 6. Block diagram of multiple model predictive control. [Redrawn with permission from Rao et al., Automated regulation of hemodynamic variables, *IEEE Eng. Med. Biol.* 2001; 20 (1): 24–38. (© Copyright 2004 IEEE).]



Figure 7. Modified multiple model predictive control strategy. [Redrawn with permission from Rao et al., Automated regulation of hemodynamic variables, *IEEE Eng. Med. Biol.* 2001; 20 (1): 24–38. (© Copyright 2004 IEEE).]

algorithm was tested in six dogs, including some cases with induced heart failure. It took 3–10.5 min to settle MAP within ±5 mmHg (±0.667 kPa) of the steady-state set-point with the mean of 5.8 min in all cases. The overshoot was between 0 and 12 mmHg (1.6 kPa) with the average of 5.92 mmHg (0.79 kPa). The standard deviation of MAP about its set-point was 4 mmHg (0.533 kPa).

The major challenge of implementing MPC in MMAC is the computation time, especially for a large model bank. Rao et al. (25) designed a MMAC with a single constrained MPC as shown in Fig. 7. The model bank, constituted first-order-plus-time-delay MIMO models spanning sufficient spectrum of model gains, time constants, and time delays, was run in parallel to obtain the possible input–output characteristics of a patient's response to drug dosages. A Bayesian weight was generated for each model based on the patient's response to drugs. The MPC used the combination of model weights to determine the optimal drug infusion rates. This control scheme combines the advantages of model adaptation according to patient variations, as well as the ability to handle explicit input and output constraint specifications. The controller effectively maintained MAP and cardiac output in seven canine experiments (26). Figure 8 illustrates the results of control MAP and CO using SNP and dopamine in on study. High levels of fluothane were introduced to reduce CO, mimicking congestive heart failure. The controller achieved both set-points of MAP = 60 mmHg (8 kPa) and CO = 2.3 $\mathrm{L{\cdot}min^{-1}}$ in ~ 12 min. In average over the entire studies, MAP was maintained within ±5 mmHg (±0.667 kPa) of its set-point 89% of the time with a standard deviation of 3.9 mmHg (0.52 kPa). Cardiac output was held within ±1 $\mathrm{L{\cdot}min^{-1}}$ of the set-point 96% of the time with a standard deviation of 0.5 $\mathrm{L{\cdot}min^{-1}}$. Manual regulation was performed in the experiments for comparison. The MAP was kept within ±5 mmHg (±0.667 kPa) of its set-point 82% of the time with a standard deviation of 5.0 mmHg (0.667 kPa) while CO stayed in the ±1 $\mathrm{L{\cdot}min^{-1}}$ band of the set-point 92% of the time with a standard deviation of 0.6 $\mathrm{L{\cdot}min^{-1}}$. Clearly, the automatic control performed better than the manual approach.

Rule-Based Controller

The blood pressure controllers discussed previously rely on mathematical models that can characterize plant dynamics, including the drug infusion system, human cardiovascular dynamics, and pharmacological agents. Identifying such mathematical forms could be a challenge due to the complexity of human body. Despite this, there exist experienced personnel, whose ability to interpret linguistic statements about the process and to reason in a qualitative fashion prompts the question: "can we make comparable use of this information in automatic controllers?"

In rule-based or intelligent control, the control law is generated from linguistic rules. This model-free controller usually consists of an inference engine and a set of rules for reasoning and decision making. A typical control rules are represented by *if <condition> then <action>* statements. Rule-based approaches have been proposed as a way of dealing with the complex natural of drug delivery systems and, more importantly, as a way of incorporating the extensive knowledge of clinical personnel into the automatic controller design.

One of the most popular rule-based control approaches is fuzzy control. Fuzzy control approach is based on fuzzy set theory and is a rule-based control scheme where scaling functions of physical variables are used to cope with uncertainty in the plant dynamics. A typical fuzzy controller, shown in Fig. 9, usually includes three components: (*1*) membership functions to fuzzify the physical input, (*2*) an inference engine with a decision rule base, and (*3*) a defuzzifier that converts fuzzy control decisions into physical control signals. More details on fuzzy set theory and its control applications are available in (27–29).

Isaka et al. (30) applied an optimization algorithm to determine the membership functions of a fuzzy blood pressure controller using SNP. This method reduced the time and efforts to determine appropriate values for a large number of membership functions. In addition, it also provided the knowledge of the effect of membership functions to the fuzzy controller performance, as well as the effect of



Figure 8. Multiple model adaptive control of MAP and CO using SNP and dopamine in canine experiment. (© Copyright 2004 IEEE).

plant parameter variations to the changes in membership functions. Efficacy of using this controller to regulate MAP by infusing SNP was evaluated in computer simulation model proposed by Slate (3). The MAP was initialized at 120 mmHg (16 kPa) at the beginning of simulation. The target MAP value was first set at 80 mmHg (10.665 kPa) and then changed to 110 mmHg (14.665 kPa). The target MAP values were achieved in < 3 min with overshoots < 10 mmHg (1.333 kPa).

Ying et al. (31) designed an expert-system-shell-based fuzzy controller to regulate MAP using SNP. The controller was a nonlinear PI-type control while the control gains were predetermined by analytically converting the fuzzy control algorithm. This converting process provided the advantage of execution time reduction. The controller was further fine-tuned to be more responsive to the rapid and large changes of MAP. It was successfully tested in 12 postsurgical patients for the total of 95 hs and 13 min. MAP was maintained within ±10% of its target value, 80 mmHg (10.665 kPa), 89.3% of the time over the entire test.

Neural-Network Based Controller

Artificial neural networks (ANN) are computation models that have learning and adaptation capabilities. An ANN-based controller is usually more robust than the traditional controllers in the presence of plant nonlinearity and uncertainty if the controller is trained properly. A survey article about the use of ANN in control by Hunt et al. (32) provides more detailed information.

The use of ANN-type controller in arterial blood pressure regulation was investigated in feasibility studies in either computer simulation or animal experiments. Chen et al. (33) designed an ANN-type adaptive controller to control MAP using SNP. The controller was tested in computer simulation with various gains and different levels of noise. The controller was able to maintain MAP close to the set point, 100 mmHg (13.33 kPa) with error within ±15 mmHg (±2 kPa) in an acceptable tolerance settling time < 20 min.

Kashihara et al. (34) compared various controllers, including PID, adaptive predictive control using ANN ($\mathrm{APP_{NN}}$), a combined control of PID with $\mathrm{APP_{NN}}$, a fuzzy controller, and a model predictive controller, to maintain MAP for acute hypotension using norepinephrine. The controllers were tested in computer simulation and animal studies. The controllers based on neural network approach were more robust in the presence of unexpected hypotension and unknown drug sensitivity. Adding an ANN or a fuzzy logic scheme to the PID or adaptive controller improved the ability of the controller to handle unexpected conditions more effectively.



Figure 9. Block diagram of a fuzzy controller. [Redrawn with permission from Isaka et al., An optimization approach for fuzzy controller design, 1992; SMC 22: 1469–1473. (© Copyright 2004 IEEE).]

DISCUSSION

Numerous controllers have been developed since 1970s to regulate SNP and control MAP for hypertension patients. The control strategies can generally be classified as PID control, adaptive control (including STR, MRAC, and MMAC), rule-based control, as well as neural network control. Most controllers were developed and tested in computer simulation and animal experiments successfully. A few controllers were tested clinically with satisfactory results. Table 1 summarizes the control algorithms reviewed in this article.

Controller performance is influenced by several factors, including the fit of the process model to the plant, signal conditioning of the sensors under various clinical environments, as well as the diagnosis ability of the devices. Model selection is crucial for the stability and robustness of a controller. In blood pressure regulation, variable time delay, patient's sensitivity to SNP, and rennin regulatory mechanism are important factors. These factors could cause parameter variations in the plant model that might reduce the performance of a fixed-gain controller. Adaptive controllers that can adjust the control signal based on the estimation of model parameters or the probability of model errors could overcome the limit of the fixed-gain control. Some controllers have been tested in the laboratory with promising results. However, clinical applications of this type of controllers were very few. Rule-based and ANN controllers do not need a specific plant model for control design. The training signals or information must provide a broad coverage of possible events in the clinical environment to assure the reliability of the control algorithm.

Patient care practices and other aspects of the clinical environment must be considered in the design of a clinical useful system. A supervisory algorithm that can detect potential risks, determine appropriate control signals to

Table 1. Summary of Blood Pressure Controllers Reviewed in this Article

		Controller Performance			Controller Test		
Articles	Control Scheme	Settling Time (min)	Overshoot, mmHg	Steady-State about the Set-Point, mmHg	Simulation	Animal Studies	Clinical Studies
Slate et al.(2–4)	Nonlinear PI	< 10		± 10	x	x	x
Arnsparger et al.(10)	STR	2	30	10		x	
Mansour et al.(13)	STR	5–20	< 10	± 5	x		
Voss et al.(14)	CAMAC	1.3–7.3	0–22	−4–9.8	x	x	
Kaufmann et al.(15)	MRAC (w/known time-constant and delay)	< 5		± 5	x	x	
Pajunen et al.(16)	MRAC (w/time-varying parameters)	< 5	< 15	± 15	x		
Polycarpou et al.(17)	MRAC	5		± 10	x		
He et al.(19)	MMAC	< 8	< 5	± 5	x	x	
Martin et al.(20–22)	MMAC	< 10	< 10	± 5	x	x	x
Yu et al.(23)	MMAC	3–10.5	0–12	± 5	x	x	
Rao et al.(25,26)	MMPC	12		± 5	x	x	
Isaka et al.(30)	Fuzzy controller	< 3	< 10	± 5	x		
Ying et al.(31)	Fuzzy controller			± 8	x		x
Chen et al.(33)	ANN	5 to 20		± 15	x		
Kashihara et al.(34)	ANN	2		± 5	x	x	

stably maintain a patient's blood pressure near the set point, and identify excessive noise or artifact in sensor measurements would be beneficial (21,22,31). The supervisor oversees the entire conditions of the control environment and directs the controller to take control actions efficiently and safely. Control decision is based upon sensor measurements. It is very important that the supervisor is able to process measurements and detect the nonphysiological signals, such as the noisy signals duo to suction the airway and flushing the arterial catheter, and thus avoid acting on unreliable information. In addition, the supervisor must have the ability to assure the proper operation of the infusion system for drug delivery. This monitoring system should be able to detect the potential faults that could prevent abnormal operation of the device (e.g., blood clotting, infusion kinking, leakage, and infusion pump stoppage).

CONCLUSION

Because of the quick action of SNP in blood pressure reduction, frequent monitoring of MAP followed by infusion rate adjustment is necessary. The use of manual control to achieve desired MAP would be burdensome to ICU personnel, who are already loaded with many duties. Successful development of a blood pressure controller that could automatically maintain patient's MAP within a preset range with self-monitoring capability would reduce the workload of the patient care providers and improve the patient's quality of life in the clinical environment.

Blood pressure control systems designed previously provide valuable experiences for further development. The future controller should be able to adapt the characteristic changes (represented by gains, time delays, and time constants) from patient to patient as well as the variations within a patient over time. In order to improve the reliability and safety of the controller, incorporating a supervisory scheme that can monitor system operation as well as identify and manage unexpected mechanical errors and clinical environment changes with the control system would be essential.

BIBLIOGRAPHY

Cited References

1. Chitwood Jr WR, Cosgrove 3rd DM, Lust RM. Multicenter trial of automated nitroprusside infusion for postoperative hypertension. Titrator Multicenter Study Group. Ann Thorac Surg 1992;54:517–522.
2. Sheppard LC. Computer control of the infusion of vasoactive drugs. Ann Biomed Eng 1980;8:431–444.
3. Slate JB. Model-based design of a controller for infusing sodium nitroprusside during postsurgical hypertension. Ph.D. dissertation. University of Wisconsin-Madison, 1980.
4. Slate JB, Sheppard LC. Automatic control of blood pressure by drug infusion. Proc Inst Electr Eng 1982;129, (Pt. A):639–645.
5. de Asla RA, Benis AM, Jurado RA, Litwak RS. Management of postcardiotomy hypertension by microcomputer-controlled administration of sodium nitroprusside. J Thrac Cardiovas Surg 1985;89:115–120.
6. Astrom KJ. Theory and application of adaptive control— a survey. Automatica 1983;19:471–486.
7. Astrom KJ, Wittenmark B. Adaptive Control 2nd ed. New York: Addison-Wesley; 1994.
8. Goodwin GC, Sin KS. Adaptive Filtering, Prediction, and Control. Englewood Cliffs (NJ): Prentice Hall; 1984.
9. Ljung L. System Identification: Theory for the User. 2nd ed. Englewood Cliffs (NJ): Prentice Hall; 1998.
10. Arnsparger JM, McInnis BC, Glover Jr JR, Norman NA. Adaptive control of blood pressure. IEEE Trans Biomed Eng 1983;BME-30:168–176.
11. Meline LJ, Westenskow DR, Pace NL, Bodily MN. Computer controlled regulation of sodium nitroprusside infusion. Anesth Analog 1985;64:38–42.
12. Waller JL, Roth JV. Computer-controlled regulation of sodium nitroprusside infusion in human subjects. Anesthesiology 1985;63:A192.
13. Mansour NE, Linkens DA. Pole-assignment self-tuning control of blood pressure in postoperative patients: a simulation study. Proc Inst Electr Eng 1989;136, (Pt. D):1–11.
14. Voss GI, Katona PG, Chizeck HJ. Adaptive multivariable drug delivery: control of arterial pressure and cardiac output in anesthetized dogs. IEEE Trans Biomed Eng 1987;BME-34:617–623.
15. Kaufman H, Roy R, Xu X. Model reference control of drug infusion rate. Automatica 1984;20:205–209.
16. Pajunen GA, Steinmetz M, Shankar R. Model reference adaptive control with constraints for postoperative blood pressure management. IEEE Trans Biomed Eng 1990;BME-37:679–687.
17. Polycarpou MM, Conway JY. Indirect adaptive nonlinear control of drug delivery systems. IEEE Trans Auto Control 1998;AC-43:849–856.
18. Lainiotis DG. Partition: a unifying framework for adaptive systems II: control. Proc IEEE 1976;64:1182–1198.
19. He WG, Kaufman H, Roy R. Multiple model adaptive control procedure for blood pressure control. IEEE Trans Biomed Eng 1986;BME-33:10–19.
20. Martin JF, Schneider AM, Smith NT. Multiple-model adaptive control of blood pressure using sodium nitroprusside. IEEE Trans Biomed Eng 1987;BME-34:603–611.
21. Martin JF, Schneider AM, Quinn ML, Smith NT. Improved safety and efficacy in adaptive control of arterial blood pressure through the use of a supervisor. IEEE Trans Biomed Eng 1992;BME-39:381–388.
22. Martin JF, Smith NT, Quinn ML, Schneider AM. Supervisory adaptive control of arterial blood pressure during cardiac surgery. IEEE Trans Biomed Eng 1992;BME-39:389–393.
23. Yu C, Roy RJ, Kaufman H, Bequette BW. Multiple-model adaptive predictive control of mean arterial pressure and cardiac output. IEEE Trans Biomed Eng 1992;BME-39:765–778.
24. Garcia CE, Prett DM, Morari M. Model predictive control: theory and practices—a survey. Automatica 1989;25:335–348.
25. Rao RR, Palerm CC, Aufderheide B, Bequette BW. Automated regulation of hemodynamic variables. IEEE Eng Med Biol 2001;20 (1):24–38.
26. Rao RR, Aufderheide B, Bequette BW. Experimental studies on multiple-model predictive control for automated regulation of hemodynamic variables. Trans Biomed Eng 2003;50 (3):277–288.
27. Zadeh LA. Fuzzy sets. Inform Contr 1965;8:338–353.
28. Tong RM. A control engineering review of fuzzy systems. Automatica 1977;13:559–569.
29. Sugeno M. An introductory survey of fuzzy control, Inform. Science 1985;36:59–83.
30. Isaka S, Sebald AV. An optimization approach for fuzzy controller design. IEEE Trans Sys, Man, Cyber 1992;SMC 22:1469–1473.

31. Ying H, McEachern M, Eddleman DW, Sheppard LC. Fuzzy control of mean arterial pressure in postsurgical patients with sodium nitroprusside infusion. IEEE Trans Biomed Eng 1992;BME-39:1060–1070.
32. Hunt KJ, Sbarbaro D, Zbikowski R, Gawthrop PJ. Neural networks for control systems—a survey. Automatica 1992;28: 1083–1112.
33. Chen CT, Lin WL, Kuo TS, Wang CY. Adaptive control of arterial blood pressure with a learning controller based on multilayer neural networks. IEEE Trans Biomed Eng 1997;BME-44:601–609.
34. Kashihara K, et al. Adaptive predictive control of arterial blood pressure based on a neural network during acute hypotension. Ann Biomed Eng 2004;32:1368–1383.

See also BIOFEEDBACK; BLOOD PRESSURE MEASUREMENT; DRUG INFUSION SYSTEMS; HEMODYNAMICS; PHYSIOLOGICAL SYSTEMS MODELING.

BLOOD RHEOLOGY

ROGER TRAN-SON-TAY
University of Florida
Gainesville, Florida
WEI SHYY
University of Michigan
Ann Arbor, Michigan

INTRODUCTION

Blood rheology has had broad impact in our understanding of diseases and in the development of medical technology. Rheology is the science dealing with the flow and deformation of matter. Therefore, it encompasses work in mechanical, chemical, and biomedical engineering. It plays a vital role not only in the design, manufacture, and testing of materials, but also in the health of the human body. Biorheology is therefore concerned with the description of the flow and deformation of biological substances. More specifically, hemorheology, or blood rheology, deals with the rheological behavior of blood, including plasma and cellular constituents.

Blood flow is known to be responsible for the delivery of oxygen to tissue and the removal of carbon dioxide. However, it also plays a pivotal role in the transport of substances (nutrients, metabolites, hormones, cells, etc.) involved not only in the maintenance of the body and its immune response, but also in diseases. For example, cancer cells are transported through blood as they spread from one tissue to another in a process known as metastasis.

The rheology of blood is altered in a number of pathological conditions. Sickle cell disease is a genetic disease producing abnormal hemoglobin causing red blood cells (RBCs) to become crescent shaped when they unload oxygen molecules or when the oxygen content of the blood is lower than normal. Under these conditions, the sickle hemoglobin aggregates and the RBCs become rigid, and consequently obstruct and/or damage the capillaries. Sickle cell disease is also known as sickle cell anemia because of the abnormally low oxygen-carrying capacity of the blood due to an insufficient number of RBCs and an abnormal hemoglobin. During a heart attack or stroke, there is a partial or complete occlusion of blood vessels due to the formation of a blood clot that alters blood flow. It is clear that many diseases and factors (artherosclerosis, hypertension, vasodilator agents, etc.) can compromise blood flow by occluding vessels or modifying their rheological properties. However, the study presented here will focus mainly on the rheology of blood.

It is important to recognize that the rheological properties of blood and its components, that is, blood cells, are important in the aptitude of blood to perform its functions correctly. The ability of a blood cell to flow into capillaries or migrate through tissues is governed, but its rheological properties. In addition, flow is expected to affects cells in two ways: (*1*) the fluid moving over or around the cell will exert mechanical stress on the cell, and (*2*) the motion of fluid will alter the concentration of chemical species in the immediate surrounding of the cell, leading to the mass transport of nutrients, waste products, drugs, hormones, and so an, to and from the cell. Finally, blood rheology can also have an indirect but critical role in our immune system and in diseases since a given applied stress, such as fluid shear, can generate a signal that can induce or modify cellular response.

Blood rheology is an extremely broad subject that cannot be covered in a single review. Therefore, the scope of the present article is to provide an understanding of blood rheology, and an appreciation of its contributions to the improvement of our understanding and assessment of diseases. The article also provides a review of the most common methods used to measure the rheological properties of blood and blood cells.

RHEOLOGICAL PROPERTIES OF BLOOD

Is blood a Newtonian fluid? A Newtonian fluid is a fluid that has a viscosity that is constant and independent of the properties of the flow. This simple question is not easily answered because blood is a complex fluid. It is a non-Newtonian fluid that behaves as a Newtonian fluid under certain conditions. For example, for a shear rate $> 100\,\mathrm{s}^{-1}$ and a vessel/tube diameter $> 500\,\mu\mathrm{m}$, blood behaves as a Newtonian fluid. Blood is composed of formed elements (red cells, white cells, platelets, etc.) suspended in plasma. Blood cells are viscoelastic particles (possess both viscous and elastic properties), whereas plasma is Newtonian. Therefore, depending on the characteristics of the flow and size of the vessel (extent of deformation), the size and properties of the blood cells may not play a major role in the flow characteristics of blood. The behavior of blood needs to be described as a function of the size of the vessel and the rate of flow. Because of that behavior, the concept of apparent and relative viscosities is introduced. The viscosity value of a non-Newtonian fluid depends on the experimental conditions and instrument used to perform the measurement. Therefore, that measured viscosity is called the apparent viscosity, μ_{app}. The relative apparent viscosity, μ_{rel}, is defined as

$$\mu_{\mathrm{rel}} = \frac{\mu_{\mathrm{app}}}{\mu_{\mathrm{p}}} \qquad (1)$$



Figure 1. Effect of hematocrit on blood viscosity. Plasma has a relative viscosity of ~ 1.8 at 37 °C, that is a viscosity of $\sim 1.2\,\mathrm{mPa \cdot s}$. Human blood at 40% hematocrit has a viscosity of ~ 3–4 $\mathrm{mPa \cdot s}$. However, it is a function of both hematocrit and shear rate.

where μ_p is the viscosity of plasma or other suspending medium.

In general, the viscosity of plasma is ~ 1.8 times the viscosity of water (termed relative viscosity) at 37 °C and is related to the protein composition of the plasma. Whole blood has a relative viscosity of ~ 4 depending on hematocrit (RBC concentration), temperature, and flow rate. The average hematocrit for a man and a woman is 42 and 38%, respectively. Hematocrit is an important determinant of the viscosity of blood. As hematocrit increases, there is a disproportionate (exponential) increase in viscosity (Fig. 1). For example, at a hematocrit of 40%, the relative viscosity is 4. At a hematocrit of 60%, the relative viscosity is ~ 8. Therefore, a 50% increase in hematocrit from a normal value increases blood viscosity by $\sim 100\%$. Such changes in hematocrit and blood viscosity occur in patients with polycythemia.

Because blood is non-Newtonian, the effect of shear rate is important. Figure 2 illustrates the shear thinning characteristic (decrease in viscosity as the shear rate increases) of blood at two different temperatures. On the other hand, it is clearly seen that plasma is Newtonian. It has a viscosity of $\sim 1.2\,\mathrm{cP}$ or $1.2\,\mathrm{mPa \cdot s}$ at 37 °C. The poise, P, is a unit of viscosity. The different viscosity units are related as follows: $1\,\mathrm{P} = 1\,\mathrm{dyn \cdot s \cdot cm^{-2}} = 0.1\,\mathrm{N \cdot s \cdot m^{-2}} = 0.1\,\mathrm{Pa \cdot s}$; therefore, $1\,\mathrm{cP} = 1\,\mathrm{mPa \cdot s}$. The fact that blood viscosity increases at low shear is one of the key factors for the initiation of atherosclerosis at specific sites in the arterial system. Increases in the viscosity of blood and plasma reflect clinical manifestations of atherothrombotic (formation of fibrinous clot) vascular disease. High blood viscosity invariably accompanies degenerative diseases. It is therefore not surprising that many treatments involve lowering blood viscosity to treat or prevent heart attacks, strokes, atherosclerosis, and so on.

Temperature also has a significant effect on viscosity. This can be seen in Figs. 3 and 4 where the effect of temperature on the viscosity of plasma and human blood is shown. Temperature has a similar effect on plasma and water. As temperature decreases, viscosity increases. Viscosity increases $\sim 2\%$ for each degree celcius decrease in temperature. This effect has several implications. For example, when whole-body hypothermia is used during certain surgical procedures, it increases blood viscosity and therefore augments resistance to blood flow.



Figure 2. Effect of shear rate on blood viscosity. The Newtonian behavior of plasma and non Newtonian behavior of blood are clearly demonstrated. Plasma has a constant viscosity of $\sim 1.2\,\mathrm{mPa \cdot s}$ at 37 °C. The effect of temperature on blood viscosity is also shown.

The viscoelastic profile of normal human blood can be divided into three regions depending on the shear rate levels. In the low shear rate region ($\dot{\gamma} \leq 20\,\mathrm{s^{-1}}$), red cells are in large aggregates and as the shear rate increases, the size of the aggregates diminishes. Blood viscoelasticity is dominated by the aggregation properties of the red blood cells. In this region, human blood behaves like a Casson fluid with a small but finite yield stress (i.e., blood will not flow or deform unless the applied stress exceeds that critical stress),

$$\sqrt{\tau} = a + b\sqrt{\dot{\gamma}} \qquad (2)$$

where a and b are constant (Fig. 5). The magnitude of the rheological parameters like yield stress and viscosity depends on various factors such as plasma protein concentration,



Figure 3. Effect of temperature on plasma viscosity. Temperature has similar effects on the viscosity of plasma and water. Viscosity increases $\sim 2\%$ for each degree celcius decrease in temperature.



Figure 4. Effects of shear rate and hematocrit on blood viscosity. The shear thinning characteristics of blood is well illustrated in this figure. The solid and dashed lines represent, respectively, whole blood and washed red blood cells in a saline solution at 45 and 90% red cell volume concentrations. (Adapted from Ref. 1.)



Figure 6. Effects of cell aggregation and deformability on blood viscosity. The logarithmic relation between the apparent viscosity and shear rate in three types of suspensions, each containing 45% human RBCs by volume is shown. Suspending plasma viscosity = 1.2 mPa.s; NP = normal RBCs in plasma; NA = normal RBCs in 11% albumin; HA = hardened RBCs in 11% albumin solution. (Adapted from Ref. 3.)

hematocrit, and properties of the blood cells. At low flow rates, there are increased cell-to-cell and protein-to-cell adhesive interactions that can cause erythrocytes (RBC) to adhere to one another and increase the blood viscosity. However, at shear rates $> 100\,\mathrm{s}^{-1}$, cell aggregation and rouleaux formation break up and blood behaves as a Newtonian fluid with a viscosity of ~ 3–4 mPa·s depending on the hematocrit and other factors (Fig. 6). In the mid-shear rate range ($20 \leq \dot{\gamma} \leq 100\,\mathrm{s}^{-1}$), the cells are progressively disaggregated with increasing shear rate. Increasing shear rate causes the cells to deform and orient in the direction of flow, and the viscoelasticity of the blood is dominated by the deformability of the RBC. Figure 6 also demonstrates the effect of cell deformabilty on blood viscosity. It is seen that deformable cells lower the blood viscosity as compared to rigid ones.

However, when the dimensions of the cells are not negligible in comparison with the diameter of the vessel through which flow is occurring, the two phase nature of blood has to be recognized. Thus blood flow through vessels narrower than 500 μm in diameter is accompanied by several anomalous effects which can be directly traced to the two phase nature of blood. The important artifacts are the Fahraeus (a decrease in the hematocrit of the vessel–tube as compared to the larger feeding vessel–reservoir hematocrit) and Fahraeus–Lindqvist (a decrease in the vessel–tube apparent viscosity as compared to the larger feeding vessel–reservoir viscosity) effects. The effects are more pronounced as the vessel–tube diameter decreases. For vessel diameters < 10 μm (capillaries), blood cells must travel in single file and the flow must be analyzed as creeping (low Reynold number) flow of a Newtonian fluid with particles embedded in it. The transition from a single file to suspension flow occurs in the diameter range of 10–25 μm and this domain is difficult to analyze.



Figure 5. Blood behavior at low shear—casson behavior. These plots were generated from blood data obtained at 25 °C. They show that blood has a yield stress that depends on hematocrit. (Adapted from Ref. 2.)

To add to the complexity of blood behavior, vessels also affect blood flow characteristics. For example, the most noticeable feature of blood flow in the arteries is the pulsatile nature of the flow. However, this feature is lost in the microcirculation because its effect has been dampened by the viscoelastic blood vessels. The flow in the microcirculation occurs at very low Reynolds number (i.e., inertial forces due to transient and convective accelerations are negligible) and is determined by a balance of viscous stress and pressure gradient. Individual cells must be recognized. In the capillaries, 3–10 μm diameter vessels, cells flow in single line and their flow–deformation must be analyzed. Finally, in the veins, where ~ 80% of the total volume of blood is located, the most noticeable feature is that vessels can collapse and that their mechanical properties cannot be neglected.

The above descriptions represent just some of the rheological characteristics of blood, but many more factors can affect its behavior. However, they prove the point that blood is an extremely complex fluid with many facets and that only a few have been unveiled so far.

CORRELATION BETWEEN BLOOD RHEOLOGICAL PROPERTIES AND CLINICAL CONDITIONS

Blood is a complex fluid whose flow (rheological) properties are significantly affected by the arrangement, orientation, and deformability of red blood cells. Variations in blood rheology among healthy individuals are very small. Thus, changes due to disease or surgical intervention can be readily identified, making blood rheology a useful clinical marker. Variations in blood rheology are observed in such conditions as cardiovascular disease, peripheral vascular disease, sickle cell anemia, diabetes, and stroke.

Although studies of blood rheology date from at least the early studies of Poiseuille (4), the discipline of clinical hemorheology is relatively new. It underwent a rapid growth in 1970–1980, in large part due to support by pharmaceutical companies and equipment manufacturers. Various instruments and devices were developed specifically for studying blood rheology.

Some of the early clinical tests dealing with blood rheology were on blood coagulation and the formation of blood clots. Most people think of blood in its liquid state, but its ability to thicken into a blood clot is a vital part of the body's natural defense. This process of forming a clot is referred to as coagulation. Blood coagulation, or blood clotting, is a complex process involving platelets, coagulation factors present in the blood and blood vessels. If blood becomes too thin, it loses the ability to form the blood clots that stop bleeding. When blood becomes too thick, the risk of blood clots developing within the blood vessels rises creating a potentially life-threatening condition. Blood disorders occur when hemostasis falls out of balance. Hemostasis is achieved when blood chemicals, hormones and proteins are correctly balanced. Hemostasis refers to the complicated chemical interplay that maintains blood fluidity (e.g., viscosity, elasticity, and other rheological properties).

Coagulation, or the lack thereof, is a key factor in various diseases. Sometimes thrombi (large clots) can completely occlude vessels. This can lead to ischemia, and ultimately death in any part of the body. Myocardial infarction and stroke are among the major life-threatening conditions caused by vessel occlusion due to clots. Conversely, there are various coagulatory disorders in which thrombus formation does not occur when it should. These bleeding disorders include various forms of hemophilia [e.g., (5,6)].

A great deal of research has focused on the effects of rheology on thrombus formation. Various *ex vivo* and *in vitro* systems have been designed to mimic *in vivo* blood flow in order to study thrombus formation within the circulatory system (7), and on various devices. For example, these systems have been used to model blood flow in order to study thrombus formation on stents (8) and mechanical heart valve prostheses (9). In addition, some research has focused on the effect of shear on thrombus dissolution. These studies suggest that thrombi lysis is accelerated with increasing shear rates (10,11).

It is impossible to cite all the contributions of blood rheology to our understanding of diseases in this review, but it is clear that viscosity was and still is clinically the most commonly used rheological property. The principal factors determining blood viscosity are hematocrit, plasma viscosity, cell aggregation, and cell deformability. Earlier rheological work was mainly performed on whole blood and on RBCs because the latter are by far the most numerous cells in our body (99% of the blood cells are RBCs). However, in the last two decades, the focus has shifted toward understanding the rheology of leukocytes or white blood cells (WBC) because they have been found to be bigger and more rigid that RBC. The major motivation behind all these blood cell studies is that the ability of a cell to deform and flow through the capillaries and/or to migrate in the tissue is determined by its rheological properties, and this ability is vital in its response to disease/infection. These properties, in turn, are a manifestation of the underlying structure of the cell and the organization of the structural components (microfilaments (F-actin), microtubules, intermediate filaments, lipid bilayer) in the cellular cytoplasm and cortex.

Because blood rheology is a very broad subject, this article focuses on the role of RBC deformability in clinical studies. The role of other blood cell types, cytoskeleton, proteins, adhesion molecules, and so on., although important and of interest, is beyond the scope of this article and will not be addressed.

RBC Deformability

Deformability is a term used to describe the ability of a body (cell in the present context) to change its shape in response to an applied force. A very important characteristics of a normal RBC is that it has a surface area $\sim 30\%$–40% greater than that of a sphere of equal volume. Other major determinants of RBC deformability include rheological properties of the cell membrane, and intracellular fluid.

Cell deformability can be determined by direct microscopic measurement (micropipette) or indirect estimation (filtration). By using micropipettes with diameters $\geq 3\ \mu\text{m}$, the entire RBC can be aspirated. The deformability of the cell can be estimated from the pressure required for its total aspiration.

The importance of cell deformability is well established in the studies of the rheological behavior of RBCs in the capillary network. It was clearly demonstrated that reductions in RBC deformability may adversely affect capillary perfusion (12) and that many diseases manifest reductions in RBC deformability (13–15). Of the many determinants of capillary perfusion, the size of the undeformed RBC relative to the capillary diameter may play the greatest role in affecting capillary perfusion. For example, studies of the passage of RBCs through capillary-sized pores of polycarbonate sieves (16) reveal that the flow resistance may increase 30–40 times as the ratio of pore to cell diameter is reduced from 1 to 0.1. Furthermore, after entry into a capillary, the ability of RBCs to deform may play an equally important role as RBCs negotiate irregularities in the capillary lumen, as manifested by encroachment of endothelial cell nuclei on the capillary lumen (17). It was also demonstrated that the microvascular network may passively compensate for increased RBC stiffness by shunting RBCs within the capillary network through pathways of lesser resistance (18).

There are many methods for assessing the erythrocyte deformability but only two (filtration of RBCs through pores of 3–5 mm diameter and the measurement of RBC elongation using laser diffractometry) have been widely applied clinically. A brief description of these two methods is provided below.

Erythrocyte Filtration. Filtration method has been commonly used to study the deformability of RBC. The basic idea is to force the RBC suspension to flow through 3–5 μm pores (by using a negative or positive pressure or gravity), and obtain the relationship between pressure and flow rate to estimate the deformability of the cells. Either the flow rate is measured under a constant pressure or the pressure is measured under a constant flow rate. Contaminants, such as WBC, which is poorly deformable affect the experiment by plugging the pores.

The techniques for whole-blood filtration are almost all derived from that described by Reid et al. in 1976 (19). The results of these methods are expressed as volume of blood cells (VBCs) in the time unit. However, this technique is susceptible to aggregation of RBCs and contamination with leukocytes. A modified version of the apparatus was developed to reduce these problems (20). Nevertheless, WBC contamination remains an issue with whole-blood filtration techniques.

A common draw back among all these filtrometry-based instruments is the lack of any measure of individual cell volume, thereby making it difficult to distinguish changes in RBC filtration due to the volume distribution (or aggregates) within the RBC sample from those due to intrinsically less deformable cells.

Another filtration technique that is commonly used is the Bowden assay (21,22). However, this assay involves the migration of cells (WBCs) through a filter membrane with pores of defined diameter and is beyond the scope of this article.

Erythrocyte Elongation. The Ektacytometer (23) combines viscosity with laser diffractometry. It consists of a transparent cylindrical Couette or a cone-plate viscometer, which allows a helium–neon laser beam to pass through the erythrocyte test suspension during rotational shear. The laser diffracted image becomes elliptical as the RBCs are sheared, and the ratio of the major over minor axes of the image is called the elongation index. This dynamic measurement of RBC elongation has been used for the rheological studies of congenital defects of RBC membrane protein (24), and many blood disorders (25–27).

It is important to remember that the two methods described above provide information on the bulk deformability of the RBC only, and are not suited for characterizing the deformability of subpopulations. Alternative methods need to be used for these studies. Some of the methods that have been developed for specifically characterizing the rheological properties of individual cells are provided in the next section.

RHEOLOGICAL PROPERTIES MEASUREMENTS

The goal of this section is to provide an overview of the most commonly used techniques for characterizing the rheological properties of blood. Therefore, devices will be divided into two groups: one for characterizing fluids, the other for individual cells.

Techniques for Measuring the Rheological Properties of a Fluid

Cylindrical Tube. The first studies of blood rheology have been done in cylindrical tubes. In his quest toward developing a better method for measuring blood pressure, French physician and physiologist Jean Louis (or sometimes called Leonard) Marie Poiseuille (1799–1869) studied the flow of liquid through tubes. (There is some confusion about Poiseuille's precise name and year of birth, sometimes quoted as 1797.) In 1838, he established a series of meticulously executed experiments: At a given temperature the rate of water flow through tubes of very fine bore is inversely proportional to the length of the tube and directly proportional to the pressure gradient and to the fourth power of the tube diameter. In 1840 and 1846, he formulated and published an equation known as Poiseuille's law (or Hagen-Poiseuille law, named also after the German hydraulic engineer Gotthilf Heinrich Ludwig Hagen who independently carried out friction experiments in low speed pipe flow in 1840) based on his experimental pipe flow observation. Little is known of the life of Jean Leonard Marie Poiseuille. However, he made important contributions to the experimental study of circulatory dynamics. His law can be successfully applied to blood flow in capillaries and veins, and to air flow in lung alveoli, as well as for the flow through hypodermic needle or tubes, in general (28,29).

The derivation of Poiseuille's law for a Newtonian fluid, that is, the viscosity of the fluid is constant and independent of the properties of the flow. (Viscosity is a property of fluid related to the internal friction of adjacent fluid layers sliding past one another, as well as the friction generated between the fluid and the wall of the vessel. This internal friction contributes to the resistance to flow.) For example, water and plasma are Newtonian fluids. For a Newtonian, laminar (nonturbulent) case, the flow through a cylindrical tube is one-dimensional (1D) (Fig. 7) reaching the fully



Figure 7. Flow in a cylindrical tube. Fully developed, laminar, viscous flow in tubes produces a parabolic velocity profile. The shear stress varies linearly with the radial distance r. Parameters are as follows: velocity field, $V_x = V_x(r)$, $V_r = 0$, $V_\theta = 0$; shear rate, $\dot{\gamma} = -(\partial V_z/\partial r)$; lines of shear, straight lines parallel to the tube axis; shearing surfaces, concentric cylinders.

developed state, that is, exhibiting no variation in velocity profiles in the streamwise, x direction, and the streamwise velocity, V_x, has the following distribution on any cross-section

$$V_x = \frac{R^2 \Delta P}{4\mu L}\left[1 - \left(\frac{r}{R}\right)^2\right] \tag{3}$$

where ΔP is the pressure drop between two points located at a distance L apart, R is the tube radius, r is the radial distance from the tube axis, and μ is the fluid viscosity.

For 1D laminar flows in pipe, the pressure gradient, ΔP, necessary to produce a given flow rate, Q, is proportional to the viscosity and, as shown from the above equation, inversely proportional to the fourth power of the tube radius,

$$\frac{\Delta P}{L} = \frac{8\mu Q}{\pi R^4} \tag{4}$$

This equation has important clinical implications. It tells us that for a given pressure drop, a 10% change in vessel radius will cause $\sim$50% change in blood flow. Conversely, for a fixed flow, a 10% decrease in vessel radius will cause $\sim$50% increase in the required pressure difference. Poiseuille law tells us the consequences of having a reduced vessel lumen like in arteriosclerosis.

Thus, the average fluid velocity can be expressed in terms of the volumetric flow rate Q or pressure ΔP

$$\overline{V} = \frac{Q}{\pi R^2} = \frac{R^2 \Delta P}{8\mu L} \tag{5}$$

For a Newtonian fluid, the shear stress distribution in the tube is linear with r,

$$\tau = \mu\dot{\gamma} = -\mu\frac{dV_z}{dr} = \frac{r\Delta P}{2L} \tag{6}$$

The shear stress is the frictional force per unit area as one layer of fluid slides past an adjacent layer. Therefore, the maximum shear stress occurs along the tube wall and is equal to

$$\tau_z = \frac{R\Delta P}{2L} = \frac{4\mu Q}{\pi R^3} = \frac{4\mu\overline{V}}{R} \tag{7}$$

The viscosity of blood and other fluids have been characterized with cylindrical tube devices. For example, Cannon–Fenske viscometers are cylindrical tubes used to measure the viscosity of fluids. However, they are not commonly used for measuring non–Newtonian fluids because the shear rate generated in these devices is not constant so its effect on viscosity cannot be easily characterized.

Viscometers. Viscometers are designed to measure the viscosity of fluids. They come in many forms (e.g., concentric cylinders, parallel disks) (30), but the review will focus only on instruments that have been used to characterize biological fluids (31,32). The most common is the cone-plate arrangement (Fig. 8) because it produces a linear velocity profile and, consequently, a constant shear rate throughout the gap for small cone angles.

For a cone-plate viscometer of radius R and cone angle α_o, the relevant parameters, such as viscosity and shear rate, can be found by setting the angular speed of rotation of the cone, ω, and observing the resultant torque, T. These relationships are provided through the expressions of the shear stress, τ, and shear rate, $\dot{\gamma}$.



Figure 8. Cone-plate viscometer. For small cone angles, the flow between the cone and the plate is linear. Parameters are as follows: velocity field, $V_\phi = V_\phi(r,\theta)$, $V_\theta = 0$, $V_r = 0$; shear rate, $\dot{\gamma} = -(\frac{1}{r})(\frac{\partial V_\phi}{\partial \theta})$; lines of shear, circles of constant r and z; shearing surfaces, cones of constant θ.

$$\tau = \frac{3T}{2\pi R^3} = \frac{\mu\omega}{\alpha_o} \tag{8}$$

$$\dot{\gamma} = -\frac{\sin\theta}{\mathrm{r}}\frac{d}{d\theta}\left(\frac{V_\phi}{\sin\theta}\right) \cong -\frac{1}{r}\frac{dV_\phi}{d\theta} = \frac{r\omega}{d} = \frac{\omega}{\alpha_o} \tag{9}$$

In Eq. 9, d represents the gap width at a radial distance, r.

In order to measure the elastic properties, dynamic testing needs to be performed. These viscometers have to be run in an oscillatory mode so that elastic effects can be detected. In general, the rheological properties of the fluid can be described in terms of the complex viscosity η^*, or complex modulus G^*. These complex parameters are composed of a viscous and an elastic components, and are related to each other by the angular frequency of the oscillation ω ($G^* = \omega\eta^*$). It is common to mix the notation and use the viscous component, η', of η^*, and the elastic component or storage modulus, G', of G^*, to characterize the viscoelastic properties of the fluid. The viscous and elastic components represent, respectively, energy lost irreversibly and stored reversibly by the sample during an oscillatory cycle.

Microrheometers. As opposed to viscometers, rheometers are devices that measure not only viscosity, but also other rheological properties, like elasticity and yield stress. However, that characterization is very casual since many viscometers have been modified, as described above, to measure the viscoelastic properties of fluids.

As their names indicate, microrheometers have been developed to measure the rheological properties of small volume biological fluids. Typically, these machines require one drop of fluid or less. The design of the magneto-acoustic ball microrheometer for measuring the rheological properties of a liquid is shown in Fig. 2 (33). This instrument requires a much smaller sample size (20 μL, i.e., about a drop) than traditional rheometers, and opaque suspensions can be studied with it. The small-volume rheometer permits accurate temperature control and rapid temperature changes for kinetics studies, if needed (34).

The instrument itself consists of a magnetically driven 0.8 or 1.3 mm stainless steel ball that is tracked by ultrasonic echo location as it moves within the sample fluid. Using a system consisting of a time-to-voltage Converter (TVC), a pulse generator, a differential amplifier, and an oscilloscope (150 MHz), ball displacements as small as 3 μm are measured. The improved microrheometer (34) is capable of accurately measuring the viscosity of water in the very short chamber. Two measurements can be made (*1*) a falling-ball viscosity and (*2*) an oscillating-ball frequency dependent viscoelastic measurement. Parameters measured are η, the falling ball or steady-state viscosity; η', the viscous or loss modulus; and *G'*, the elastic or storage modulus.

An experiment with the falling ball consists of dropping the ball along the centerline of a 10 mm long tube with a radius of 1.6 mm. The tube is surrounded by a large flow-through chamber for accurate temperature control (Fig. 9). The terminal velocity of the ball, *V*, is inversely proportional to the viscosity, η. In rheology, it is common to denote the viscosity as η for a viscoelastic fluid. This velocity–viscosity relationship is readily derived from the Stokes drag equation:

$$\eta = 2[(\rho_s - \rho)R^2 g]/9VK \qquad (10)$$

where ρ_s and ρ are the ball and fluid density, respectively, R is the ball radius, g is the acceleration due to gravity, and K is the wall correction factor to account for the tube wall effect.

Oscillating ball experiments are operated over a frequency range of 1–20 Hz, whereby the sinusoidal driving force and the resulting sinusoidal sphere displacement are recorded. The magnitude of the displacement sinusoid and its phase shift relative to the driving force provide a measure for η' and G'. The system is calibrated with a series of Newtonian silicone oils from 0.1 to 100 P (1 P = 0.1 Pa·s). For a ball oscillating in a viscoelastic medium, the viscous and elastic moduli, when inertia is negligible, are defined as

$$\eta' = \frac{F_o \sin\phi}{6\pi K R \omega X_o} \qquad (11)$$

and

$$G' = \frac{F_o \cos\phi}{6\pi K R X_o} \qquad (12)$$

where F_o is the magnitude of the oscillating magnetic force, ω is the angular frequency of oscillation ($\omega = 2\pi f$), and X_o is the amplitude of the ball displacement.

The viscoelastic properties of blood have been characterized using the instruments described above in an oscillatory mode. However, these viscoelastic data, although useful as a tool for comparing different blood types and diseases, are not widely used because they are difficult to relate to the mechanical properties of the blood cells. For a non Newtonian fluid, the apparent viscosity (i.e., the slope of the curve of shear stress vs. shear rate at a particular value of shear rate) is used instead of viscosity since the latter is no longer a constant value and will depend on the rate and extent of deformation.



Figure 9. The magneto-acoustic ball microrheometer. (a) sample chamber, (b) stainless steel ball, (c) ultrasound crystal, (d) ultrasound transducer, (e) water jacket, (f) electromagnet, (g) electromagnet bath cap, (h) water flow outlet, (i) water flow inlet.

Techniques for Measuring the Rheological Properties of Blood Cells

Micropipette. The most popular technique for measuring the mechanical properties of blood cells is the micropipette technique (35). The micropipette manipulation technique has been used for studying liquid drops, cells, and aggregates. It has been used to investigate the effects of diseases (36,37) as well as treatments (38,39).

Micropipettes are made from 1mm capillary-glass tubing pulled to a fine point by quick fracture to give an orifice of desired diameter with a square end. The micropipette technique has been extensively used to characterize the mechanical properties of the RBC, but its use is limited in



Figure 10. Schematic of the micropipette technique. Two micropipette experiments for determining cell viscosity and surface tension are depicted. (a) Aspiration experiment; for a given aspiration pressure, the length of the aspirated cell, Lp, is tracked as a function of time. (b) Recovery experiment; a cell fully aspirated inside a pipette is expelled from it. The length of the cell, *L*, is recorded as a function of time.

practice by the complexity of the theory associated with the biconcave shape of the cell. As an example of the micropipette technique, work on the characterization of WBCs will be presented below. The theoretical work is simplified because the shape of a WBC can be treated as a sphere. An equivalent simulation for a RBC will require extensive numerical work. Two typical types of experiment, aspiration and recovery (Fig. 10), are usually performed to determine the mechanical properties of individual WBCs (40–43).

Aspiration. Passive leukocytes (WBCs) are aspirated at a constant pressure into a micropipette. The length of the aspirated cell, L_p, is measured over time to generate an aspiration curve (Fig. 10a). Viscosity values, μ, can be derived from the slope, dL_p/dt, of the aspiration curves (42):

$$\mu = \frac{(\Delta P)R_p}{(dL_p/dt)m(1-\frac{1}{\bar{R}})} \qquad (13)$$

where ΔP is the aspiration pressure, R_p is the pipet radius, $\bar{R} = R/R_p$, R is the radius of the cell outside the pipette, and $m = 6$. Figure 11 shows the aspiration of a white blood cell (lymphocyte) into a 4 μm diameter pipette. Fluorescence is used to better see the deformation of the cell nucleus.

Recovery. White blood cells are drawn by a small suction pressure into a micropipette, held there for ~ 15 s, and quickly expelled out. The changing length of the cell, *L*, as it recovers its spherical shape (Fig. 10b), is recorded as a function of time, *t*, and is described by a polynomial (43):

$$\frac{L}{D_o} = \frac{L_i}{D_o} + A\bar{t} + B(\bar{t})^2 + C(\bar{t})^3 \qquad (14)$$



Figure 11. Flow of a lymphocyte inside a 4 μm pipette. The flow of an 8 μm lymphocyte (a WBC) inside a 4 μm diameter micropipette as a function of time is shown. Fluorescent technique was used to track the cell nucleus as well as the cellular membrane.

where *A*, *B*, *C* are known functions of (L_i/D_o). The parameters L_i and D_o are the initial deformed length and resting diameter of the cell, respectively. The variable $\bar{t} = 2t/[(\mu/T_o)D_o]$ represents a dimensionless time, where μ is the cell viscosity, and T_o is the surface tension of the membrane.

Figure 12 shows a lymphocyte (about 8 μm in diameter) aspirated inside a 4 μm diameter pipette (top picture). The cell is then expelled from the pipette and recovers its initial shape (bottom, left-hand side pictures). Pictures generated on the right hand side are from numerical simulation (44). In addition to the experimental techniques, significant progress has been made in the computational capabilities to simulate the dynamic behavior of blood at both large vessel and cellular scales (45).

Rheoscope

To allow direct observation of suspended cells during shear stress application, a modified cone-plate viscometer, called a rheoscope (Fig. 13), has been developed (46). In which the cone and plate counterrotate. This gives the advantage that a particle midway between the cone and plate is subjected to a well-defined shear stress field and remains nearly stationary in the laboratory frame of reference so that it can be studied without the help of high speed cinematography. It is important to note that, for an identical speed of rotation, that the shear rate generated in the rheoscope is twice that in the



Figure 12. Pictures of a lymphocyte inside a pipette and its recovery. The top left frame is a picture of a lymphocyte (a type of leukocyte) aspirated inside a micropipette, the frames below it show the cell recovering its initial shape. Pictures on the right hand side are those generated by a theoretical compound drop model (44).



Figure 13. The Rheoscope. The main feature of this instrument is the counterrotation of the cone and plate. This gives the advantage that a particle midway between the cone and plate, subjected to a well-defined shear stress can be studied without the help of high speed cinematography. At a distance r from the axis of rotation, the shear rate is equal to $\dot{\gamma} = 2r\omega/d$, where d is the local gap width and ω is the angular velocity of the cone and plate



Figure 14. Parallel-Plate Flow Channel. The velocity profile is parabolic, and the shear rate is linear with y. Parameters are as follows: velocity field, $V_x = V_x\ (y)$, $V_y = 0$, $V_z = 0$; shear rate, $\dot{\gamma} = (\partial V_x/\partial y)$; lines of shear, straight lines parallel to the channel axis; shearing surfaces, plane surfaces parallel to the channel axis.

conventional cone-plate viscometer because of the counter rotation of the cone and plate. Effects of shear and mechanical properties of individual cells and anchorage dependent cells have been determined with the rheoscope (e.g., 1,36,47–49). The rheoscope is popular for studying RBC under shear because the analysis of the behavior of RBC is simplified since its shape is an ellipsoid.

Parallel Plate Flow Channel. Another popular technique for characterizing the rheological properties of blood cells under flow or for studying the effects of shear stress on anchorage dependent cells is the parallel plate flow system (Fig. 14).

The flow between infinite parallel plates is often referred to as plane Poiseuille flow. The velocity field reduces to one component in the direction of flow, V_x,

$$V_x = \frac{h^2 \Delta P}{8\mu L}\left[1 - \left(\frac{2y}{h}\right)^2\right] \tag{15}$$

where h is the distance between the plates, μ is the fluid viscosity, ΔP is the pressure drop between the inlet and outlet located at a distance L apart, and y is the vertical distance from the origin taken at the centerline of the channel.

The relationship between the pressure drop and volumetric flow rate Q is

$$\Delta P = \frac{12\mu QL}{wh^3} \tag{16}$$

where w is the channel width.

From the velocity field, Eq. 5, the shear rate across the channel gap is readily derived:

$$\dot{\gamma} = -\frac{dV_x}{dy} = \frac{12Q}{wh^3}y \tag{17}$$

For a Newtonian fluid, the relationship between shear rate and shear stress, τ, is linear, and the shear stress across the flow channel gap is

$$\tau = \mu\dot{\gamma} = \frac{12\mu Q}{wh^3}y \tag{18}$$

From the above equation, the shear stress is zero along the channel centerline, and the maximum shear stress, τ_s, is at the surface of the plate

$$\tau_s = \frac{h\Delta P}{2L} = \frac{6\mu Q}{wh^2} \tag{19}$$

Vote stressed that, although they allow direct observation of individual particles, these devices do not provide a direct measurement of the particle viscosity. It is necessary to know the material constitutive properties of the particles, that is, expressions that relate stresses to strains, or to develop a mathematical model in order to determine the mechanical properties of the particles. Existing models can describe fairly accurately the rheological behavior of blood cells, but the exact rheological property values of these cells, with the exemption of red blood cells, are not known. That topic will not be covered here. For a review on the mechanical properties of blood cells, the reader is referred to Waugh and Hochmuth (35), and for a discussion on the discrepancy between the rheological data on white blood cells reported in the literature to Kan et al. (44).

CONCLUSION

Some of the major advances in blood rheology are now being linked to the development and application of microfabrication to medicine. As reviewed by Voldman et al. (50) and Shyy et al. (51), these new tools will be used to better characterize the rheological properties of blood and blood cells, as well as to detect and diagnose cardiovascular and blood related diseases. Microfabrication is a process used to construct objects with dimensions in the micrometer to millimeter range. These objects are composed of miniature structures that can include moving parts such as cantilevers.

Soft lithography is a tool for micro/nanofabrication. It provides a convenient and effective method for the formation and manufacturing of micro- and nanostructures. Soft lithography is the collective name for a set of techniques that include replica molding, microcontact printing, microtransfer molding (52). The major advantages of soft lithography are that it is very fast as compared to conventional methods, relatively inexpensive, and applicable to almost all polymers. It is possible to go from design to production of replicated structures in $<$ 24 h. In soft lithography, a master mold is first made by a lithographic technique, and an elastomeric stamp is then cast using the master mold. The elastomeric stamp with patterned relief structures on its surface is used to generate patterns and structures with feature sizes as small as 30 nm (53). Polydimethylsiloxane (PDMS) is the polymer of choice for many biological applications because it is optically transparent, isotropic, homogeneous, durable, and has interfacial properties that are easy to modify (53,54). As opposed to photolithography, soft lithography provides a mean for producing nonplanar surfaces.

Microfabricated devices, also known as microelectromechanical systems (MEMS), are ideal tools for studying specific biological phenomena, for example, cell adhesion, as well as biological systems such as the microcirculation. For example, the fabrication of in vitro blood vessels can help to (*1*) determine blood cell distributions during blood flows through both arterial and venous type bifurcations, with successive bifurcations arranged as in microcirculation; (*2*) validate computer simulations and experimental methods used for *in vivo* measurements of parameters such as blood average velocity and hematocrits; and (*3*) to separate vessel or wall effects from hemodynamics effects. Figure 15 shows channels that were created using soft lithography. The different configurations shown are a series of 10 mm diameter channel in parallel, a series of



Series of 5 channels (150 μm long × 10 μm width) in parallel with smooth surface

Series of channels with endothelial cell pattern surface



Channel with constriction, smooth surface

Channel with bifurcation
Smooth surface

Figure 15. Photographs of microfabricated channels. The dashed lines on the top and bottom of the channels are length scales and each line represents 100 μm. Channels were created with inner diameters ranging from 5 to 100 μm.

channels with an endothelial cell like pattern surface, a channel with a constriction, and a channel with a bifurcation.

The application of MEMS in the area of microfluidics is a new and emerging field. It includes the development of miniature devices in fluid control, fluid measurement, and medical testing. Because of our need and interest in understanding, preventing, and treating diseases, most of the emerging MEMS applications are expected to be in biomicrofluidics. One of these applications is the development of gene chips and related deoxyribonucleic acid (DNA) tools. Others applications include microscale chemical analysis, known as microelectrophoresis, blood chemistry measurements using micromachined thin-film sensor, micropumps, drug delivery systems, glucose sensors, and chip-based microflow cytometry devices.

The major advantages of MEMS-based devices are that they are smaller and have the potential to be less expensive, more durable, and more reliable than conventional techniques. In addition, they can perform chemical tests much faster.

Finally, another area that will benefit from the advancement of technology is the development of blood substitutes. This is a needed area since the demand for blood continues to outpace the supply, especially in developing countries. With new technologies, the life span of blood substitutes based on cell-free hemoglobin, which is presently too short, could be lengthened. New methods could also be developed in order to produce human red cells, and other cell types, in culture.

Needless to say that, in order to be successful, all these new technical advances will need to be combined with an improved understanding of cell biology and rheology. This advancement will also depend on the successful incorporation of more sophisticated mathematical and computational techniques. In general, the field of biorheology is moving towards better understanding phenomena at the molecular level. For example, the knowledge of the signal transduction pathways associated with the responses of cells to deformation is essential in the field of tissue engineering, where mechanical environment during growth can affect cell response and the material properties of the tissue construct or living implant.

It is clear that blood rheology plays a major role in the maintenance of the human body and in the development of artificial organs and other medical devices, but our understanding, of that role and of the clinical implications of having an altered blood rheology, is far from being complete.

BIBLIOGRAPHY

Cited References

1. Chien S. Red Cell Deformability and its Relevance to Blood Flow. Ann Rev Physiol 1987;49:177–192.
2. Cokelet GR, et al. The rheology of human human blood measurement near and at zero shear rate. Trans Soc Rheol 1963;7:303–317.
3. Chien S, Usami S, Dellenbeck RJ, Gregersen M. Shear dependent deformation of erythrocytes in rheology of human blood. Am J Physiol 1970; 219:136–142.
4. Sutera SP. The history of Poiseuille's law. Ann Rev Fluid Mech 1993;25:1–19.
5. White GC, Montgomery RR. Clinical aspects of and therapy for von Willebrand disease. In: Hoffman R, et al., editors. Hematology: Basic principles and practice. 3rd ed. New York: Churchill Livingstone Inc.; 2000. 1946–1958.
6. Curry H. Bleeding Disorder Basics. Ped Nursing 2004;30(5): 402–404 and 428–429.
7. Hafezi-Moghadam A, Thomas KL, Cornelssen C. A novel mouse-driven *ex vivo* flow chamber for the study of leukocyte and platelet function. Am J Phys Cell Physiol 2004;286: C876–C892.
8. Sakakibara M, et al. Applicaion of *ex vivo* flow chamber system for assessment of stent thrombosis. Arterioscler Thromb Vasc Biol 2002;22(8):1360–1364.
9. Zimmer R, Steegers A, Paul R, Affeld K, Reul H. Velocities, shear stresses and blood damage potential of the leakage jets of the Medtronic Parallel bileaflet valve. Int J Artif Organs 2000;23(1):41–48.
10. Komorowicz E, Kolev K, Lerant I, Machovich R. Flow rate-modulated dissolution of fibrin with clot-embedded and circulating proteases. Circ Res 1998;82:1102–1108.
11. Blinc A, et al. Flow through clots determine rate and pattern of fibrinolysis. Thromb Haemost 1994;71:230–235.
12. Driessen GK, et al. Effect of reduced red cell "deformability" on flow velocity in capillaries of rat mesentery. Pflügers Arch 1980;388:75–78.
13. Schmalzer EM, Manning RS, Chien S. Filtration of sickle cells: recruitment into a rigid fraction as a function of density and oxygen tension. J Lab Clin Med 1989. 113:727–734.
14. Schmid-Schonbein H, Volger E. Red-cell aggregation and red-cell deformability in diabetes. Diabetes 1976;25(Suppl. 2): 897–902.
15. Schrier SL, Rachmilewitz E, Mohandas N. Cellular and membrane properties of alpha and beta thalassemic erythrocytes are different: implications for differences in clinical manifestations. Blood 1989;74:2194–2202.
16. Reinhart WH, Chien S. Roles of cell geometry and cellular viscosity in red cell passage through narrow pores. Am J Physiol 1985;248(Cell Physiol. 17):C473–C479.
17. Secomb TW, Hsu R. Motion of red blood cells in capillaries with variable cross-sections. J Biomech Eng 1996;118:538–544.
18. Lipowsky HH, Cram LE, Justice W, Eppihimer M. Effect of erythrocyte deformability on *in vivo* red cell transit time and hematocrit and their correlation with *in vitro* filterability. Microvasc Res 1993;46:43–64.
19. Reid HL, Barnes AJ, Lock PJ, Dormandy JA, Dormandy TL. A simple method for measuring erythrocyte deformability. J Clin Pathol 1976;29(9):855–858.
20. Dodds AJ. et al. Haemorheological response to plasma exchange in Raynaud's syndrome. Br Med J 1979. 1186–1187,
21. Boyden S. The chemotactic effect of mixtures of antibody and antigen on polymorphonuclear leucocytes. J Exp Med 1962; 115:453–466.
22. Zigmond SH, Hirsch JG. Leukocyte locomotion and chemotaxis. New methods for evaluation, and demonstration of a cell-derived chemotactic factor. J Exp Med 1973;137:387–410.
23. Bessis M, Mohandas N, A diffractometric method for the measurement of cellular deformability. Blood Cells 1975;1: 307–313.
24. Bull B, Feo C, Bessis M, Behavior of elliptocytes under shear stress in the rheoscope and the ektacytometer. Cytometry 1983;3:300–304.
25. Bareford D, et al. Erythrocyte deformability in peripheral occlusive arterial disease. J Clin Pathol 1985;38:135–139.
26. Erythrocyte deformability in peripheral occlusive arterial disease. J Clin Pathol 1985;38:135–139.
27. Yip R, et al. Red cell membrane stiffness in iron deficiency. Blood 1983;62:99–106.

28. Fung YC. Biomechanics—Circulation 2nd ed. New York: Springer-Verlag; 1997.
29. Pedley TJ. Pulmonary Fluid Dynamics. Ann Rev Fluid Mech 1977;9:229–274.
30. Ferry JD. Viscoelastic Properties of Polymers. 3rd ed. New York: John Wiley; 1980.
31. Whitemore RL. Rheology of the Circulation. New York: Pergamon Press; 1968.
32. Tran-Son-Tay R. Techniques for Studying the Effects of Physical Forces on Mammalian Cells and for Measuring Cell Mechanical Properties. In: Frangos JA, editor. Physical Forces and the Mammalian Cell. New York: Academic Press; 1993;p. 1–59.
33. Tran-Son-Tay R, Beaty BB, Acker DN, Hochmuth RM. Magnetically Driven, Acoustically Tracked Translating Ball Rheometer for Small, Opaque Samples. Rev Sci Instru 1988; 59:1399–1404.
34. Tran-Son-Tay R. A Microrheometer for Studying the Rheological Properties of Sickle Cell Suspensions and Hemoglobin. Proceedings of The Fourth China-Japan-USA-Singapore Conference on Biomechanics. In: Yang G, Hayashi K, Woo SL-Y, Goh JCH, editors. International Academic Publishers; 1995; p. 429–432.
35. Waugh RE, Hochmuth RM. Mechanics and Deformability of Hematocytes. In: Schneck DJ, Bronzino JD, editors. Biomechanics—Principles and Applications. New York: CRC Press; 2202; 227–239.
36. Linderkamp O, Ruef P, Zilow EP, Hoffmann GF. Impaired deformability of erythrocytes and neutrophils in children with newly diagnosed insulin-dependent diabetes mellitus. Diabetologia 1999;42:865–869.
37. Perrault CM, et al. Altered Rheology of Lymphocytes in the Diabetic Mouse. Diabetologia 2004;47:1722–1726.
38. Tsai MA, Frank RS, Waugh RE. Paasive Mechanical Behavior of Human Neutrophils: Effect of Cytochalasin B. Biophys J 1994;66:2166.
39. Thomas SJ, et al. Effects of X-Ray Radiation on the Rheological Properties of Platelets and Lymphocytes. Transfusion 2003;43:502–508.
40. Evans EA,, Yeung A. Apparent viscosity and Cortical Tension of Blood Granulocytes Determined by Micropipet Aspiration. Biophys J 1989;56:151.
41. Hochmuth RM, et al. Viscosity of Passive Neutrophils Undergoing Small Deformations. Biophy J 1993;64:1596–1601.
42. Needham D, Hochmuth RM. Rapid Flow of Passive Neutrophils into a 4 mm Pipet and Measurement of Cytoplasmic Viscosity. J Biomech Eng 1990;112:269.
43. Tran-Son-Tay R, Needham D, Hochmuth RM. Recovery of Passive Neutrophils after Large Deformation: Liquid Drop Model. Proceedings of the ASME, Adv Bioeng 1991;20:421–424.
44. Kan H-C, et al. Effects of Nucleus on Leukocyte Recovery. Ann Biomed Eng 1999;27(5):648–655.
45. Shyy W, et al. Moving Boundaries in Micro-Scale Biofluid Dynamics. Appl Mecha Rev 2001;54:405–453.
46. Schmid-Schoenbein H, et al. A Counter-Rotating “Rheoscope Chamber for the Study of the Microrheology of Blood Cell Aggregation by Microscopic Observation and Microphotometry. Microvasc Res 1973;6:366–376.
47. Tran-Son-Tay R, Sutera SP, Rao PR. Determination of RBC Membrane Viscosity from Rheoscopic Observations of Tank-Treading Motion. Biophy J 1984;46:65–72.
48. Tran-Son-Tay R, Sutera SP, Zahalak GI, Rao PR. Membrane Stress and Internal Pressure in Red Blood Cells Freely Suspended in Shear Flow. Biophys J 1987;51:915–924.
49. Glover S, et al. Phosphorylation of Tyrosine 397 Critically Mediates Gastrin-Releasing Peptide’s Morphogenic Properties. J Cellular Physiol 2004;199:77–88.
50. Voldman J, Gray ML, Schmidt MA. Microfabrication in biology and medicine. Annu Rev Biomed Eng 1999;1:401–425.
51. Shyy W, Tran-Son-Tay R, N’Dri N. Micro-Nano Coupling in Biological Systems. In: Harik VM, Luo LS, Salas M, editors. Nano-Scale Mechanics of Solid and Liquid Materials Systems. The Netherlands: Kluwer Academic; 2003.
52. Maddou M. Fundamentals of Microfabrication: The Science of Miniaturization. 2nd ed. Washington (DC): CRC Press; 2001.
53. Xia Y, Whitesides GM. Soft lithography. Ann Rev Mater Sci 1998;28:153–184.
54. Branham ML, et al. Rapid Prototyping of Micropatterned Substrates Using Conventional Laser Printers. J Materials Res 2002;17(7):1559–1562.

Reading List

Adjizian JC, et al. Clinical applications to the Ektacytometer. Clin Hemorheol 1984;4:245–254.

Chien S, et al. Effects of hematocrit and plasma proteins of human blood rheology at low shear rates. J Appl Physiol 1966;21:81–87.

See also CELL COUNTERS, BLOOD; HEMODYNAMICS.

BLOOD, ARTIFICIAL

BRIAN WOODCOCK
University of Michigan
Ann Arbor, Michigan

INTRODUCTION

Blood has such a multitude of physiological functions; it provides a circulating volume to transport substrate and metabolites, and it transports the most valuable of substrates, oxygen. It is an organ intimately involved in the immune system, delivering antibodies and cellular elements to sites of infection. It carries the instruments for coagulation. It is the communication highway for the endocrine system. It is a metabolic organ containing enzyme systems to convert molecules to active and inactive forms. Blood is intimately involved in temperature regulation. The manufacture of an artificial substitute to fulfill all those purposes is beyond the capability of current science. However, several of the functional capabilities of blood have been incorporated into various blood substitutes.

The most basic function of blood is to provide a circulating volume for transportation of substrate and metabolites. Supplementation of intravascular volume with crystalloid and colloid fluids has been a part of medical practice for a century. Recent progress has concentrated on the development of substitute solutions that can transport oxygen. These solutions are known as oxygen therapeutics or red cell substitutes.

Currently, the only available oxygen therapeutic is typed and cross-matched allogeneic human blood. This is made available in the civilian setting by the Red Cross, the American Blood Centers, and the blood banking system. Blood shortages, due to increasing blood usage and declining blood donations (1), are one of the factors driving the search for alternatives. In the past two decades there has also been an increasing concern regarding the infectious risks of blood borne pathogens (2,3). Awareness of the potential significance of the problem occurred with the increasing risk of human immunodeficiency virus (HIV) transmission from blood transfusion during the 1980s. Improved screening for HIV in the 1990s saw a dramatic improvement in blood safety so that now the risk of contracting HIV from a unit of blood is approaching 1/1,000,000. But there are still substantial concerns regarding not only the risk of contracting acquired immune deficiency syndrome (AIDS) or hepatitis, and also of other infectious diseases newly recognized as possibly being transmissible by transfusion, such as bovine spongiform encephalopathy (mad cow disease) and West Nile virus.

Another concern leading to the need for blood substitutes is that some groups Jehovah's Witnesses, have religious beliefs that cause them to refuse all blood products.

Banked blood is often wasted while active bleeding continues in the surgical setting. While hemorrhage continues, blood products administered are rapidly lost through the site of bleeding. Blood substitutes could be used as a resuscitation bridge until bleeding is controlled (4).

Initial research on artificial blood was lead by the U.S. military, which needed a ready supply of a substitute that could be stored easily and indefinitely in the field and not require typing or cross-matching. These considerations would also make a blood substitute valuable to the emergency medical services in ambulance and helicopter transfers.

All these concerns have stimulated efforts to develop red cell substitutes for use in the routine clinical setting. In an initial approach, prior to World War II, the defense department sought a hemoglobin solution that could be stored indefinitely at room temperature, preferably in a powdered form to be dissolved in normal saline, and that could be transfused without a need for cross-matching. Although the development of a reconstitutable powder has not been feasible, there are several hemoglobin-based products that are in various stages of clinical testing (5).

Other molecules apart from hemoglobin have been assessed for the function of oxygen transportation. Most success has been achieved with emulsions of perfluorochemicals.

Perfluorochemicals are inert liquids, which have a solubility for oxygen and carbon dioxide 20 times that of water. These liquids are immiscible in water and an emulsion form is required to allow them to mix with the recipient's blood after administration. A comparison of the advantages and disadvantages of perfluorocarbon and hemoglobin solutions is shown in Table 1.

Emulsions of perfluorochemicals have completed animal testing and have been investigated in the clinical setting. However, difficulties in their use have been observed, to date they have not been made available for routine use.

Table 1. Comparison of Perfluorocarbon and Hemoglobin Solutions

	Advantages	Disadvantages
Perfluorocarbon Emulsions	High O_2 Solubility Inert Ample supply	Requires high PO_2 Long tissue life Short vascular life Toxicities
Hemoglobin Solutions	Carry O_2 at normal P_aO_2 Unloads like RBCs May be stored dry?	Vasoconstriction Supply Short vascular life Toxicities

CURRENT RISKS OF BANKED BLOOD

Risks of Transfusion

Blood transfusion is safer today than it has ever been, with a death rate for each blood transfusion of ~ 1 in 300,000 (6). Two-thirds of these deaths are due to clerical errors (i.e., the wrong blood given to the wrong patient). Other risks associated with blood transfusion include infection and immune reactions (7,8). However, 20 million blood transfusions are administered each year in the United States, with an impressive safety record (9).

Infection

The risk of transmission of infection includes viral agents, other exotic infectious agents, and the risk of bacterial contamination of blood products. Blood donors with a history of risk factors are excluded from donation. Screening donated units and elimination of units that contain known infectious agents eliminates most of the remaining risk of infection.

HIV

The risk of HIV transmission from blood transfusion has caused the most public concern, though it is difficult to accurately assess the true risk of transmission because it is small and cases can be determined only after a significant period. Initial testing for HIV consisted of antibody testing alone, but this was felt to leave a risk of HIV from individuals who were infected, but had not yet sero-converted. In March 1996, HIV antigen p24 testing was instituted in the United States and only 3 out of 18 million units were identified as being antibody negative and antigen positive over the next 18 months (10). Blood donations are now tested for HIV-1 and HIV-2 (11). The apparent risk of HIV transmission is currently ~ 1 in 1,000,000.

Hepatitis

Hepatitis has a higher prevalence; 1:60,000 for hepatitis B, and 1:103,000 for hepatitis C, but is much less feared by the general public. Antigen screening tests have reduced the risk of post-transfusion hepatitis (B or C) to < 1 in 34,000 (12). Hepatitis G has more recently been recognized, and has a high incidence worldwide of 1 (13)–7% (14). Approximately 2% of blood donors and 15–20% of intravenous drug abusers in the United States have detectable hepatitis G (15). It may be identified by the polymerase chain reaction test, but this has not been implemented as a routine screening test. Fortunately, it appears that the hepatitis G virus is not responsible for non-A, non-B, non-C post-transfusion hepatitis and the results of infection appear to be minimal (16,17), although there is a weak link between hepatitis G and fulminant hepatitis in rare cases (18).

Other Viruses

Creutzfeldt–Jakob disease (vCJD) can be transmitted by transfer of central nervous system tissue (or extract). However, no cases have been definitively linked to blood transfusion (19).

In the United Kingdom an outbreak of bovine spongiform encephalopathy (BSE) or "Mad Cow Disease" has led to concern that a new variant vCJD could be transferred to the human population through consumption of contaminated beef products. Transmission of BSE by blood transfusion can occur in sheep (20). In the United Kingdom, blood products for transfusion are leucodepleted, which is thought to reduce the risk of transmission of vCJD. The possibility that infection might occur has led the U.S. Food and Drug Administration (FDA) to institute a policy "deferring", that is, declining, blood donations from anyone who has lived in the United Kingdom for a cumulative period of more than 6 months during the years 1980–1996 (21).

West Nile virus transmission has occurred in four patients who received solid organ donations from an infected donor. The organ donor had received blood transfusions from 63 donors, and follow up of those donors showed that one of them was viremic at the time of donation (22).

Bacterial contamination of stored blood is rare (1:500,000), but has a mortality rate of 25–80%. The most common infectious contaminants in red cells are gram-negative species such as *Pseudomonas* or *Yersinia* (23). Platelets are stored at room temperature, allowing rapid bacterial proliferation, and there is a risk of 1:3000–7000 of bacterial infection with these units. Bacterial contamination of platelets is typically with Gram-positive staphylococci.

Immune Reactions

Minor immune reactions, such as febrile reactions, are common and may be discomforting to the patient, but are not associated with significant morbidity, though the transfusion may have to be stopped and the product discarded. The risk of serious immune reactions is small, but present. Most acute hemolytic reactions are due to clerical errors, because cross-matching should predict and prevent these events. However, immune reactions remain the most common cause of fatality associated with transfusions.

Graft versus host disease may occur rarely after transfusion, most commonly after transfusion of nonirradiated blood components to patients with immunodeficiency. Transfusion-associated graft versus host disease has a high mortality and is rapidly fatal. Immunodeficienct patients should receive irradiated units. Immunocompetent individuals may develop graft versus host disease if common histocompatibility leukocyte antigen haplotypes between the donor and recipient prevent destruction of stem cells transfused. This can occur between first-degree family members and therefore, relative-to-patient-directed donations, which are often preferred by patients because of a perceived reduction in risk of infection, may in fact carry an increased risk of initiating transfusion-associated graft versus host disease.

Transfusion-related immunomodulation has been recognized since the mid-1970s, but is not well quantified. Exposure to allogeneic blood can cause both allosensitization and immunosuppression. Studies have demonstrated a beneficial effect of allogeneic blood transfusion on transplant organ survival, but increases in the rates of cancer recurrence and postoperative infection have also been noted (23,24). Leukocyte depletion and removal of plasma may ameliorate the effects of TNF- suppression and interleukin induction (25).

The risk of infection and concerns regarding immune reactions and immunomodulation have been a large incentive to the development of oxygen-carrying colloids.

PERFLUOROCHEMICAL EMULSIONS

Perfluorochemicals (PFCs) are chemically inert liquids with a high solubility for gases. The PFCs that have been used as blood substitutes are 8–10-carbon atom structures that are completely fluorinated. The PFCs are chemically inert, clear, odorless liquids with a density nearly twice that of water. The solubility of PFCs for oxygen is nearly 20 times that of water.

In 1965, Clark and Gollan (26) performed an experiment to see whether an animal could survive if it breathed liquid PFC equilibrated with 1 atm of oxygen. A rat could be submerged beneath this liquid for 30 min and be retrieved in good condition. Respiration of liquid PFC allowed oxygen absorption from the lungs together with CO_2 excretion.

An intravenous injection of PFC is immediately lethal because the injectate is immiscible with water and forms a liquid embolus. An emulsion of an immiscible liquid can, however, mix with water or blood. In 1968, Gehes (27) produced a microemulsion (particle size, 0.1 μm) of a PFC in normal saline. An exchange transfusion could be done, eliminating all normal blood elements, and a rat with a hemoglobin of 0 could survive breathing 100% oxygen.

Because of the inert nature of these compounds, they are not metabolized, but are cleared from the vascular space by the reticulo-endothelial system (RES), and ultimately collected in the liver and spleen. Eventually, the PFC slowly leaves the body as vapor in the respiratory gas.

Perfluorochemical Oxygen Content

Because PFCs transport oxygen by simple solubility, the amount of oxygen they carry is directly proportional to the percentage of PFC in the bloodstream and to the P_aO_2.

Hemoglobin carries most of the oxygen in whole blood and does so in a nonlinear fashion. The plot of oxygen content against P_aO_2 for hemoglobin, known as the oxygen dissociation curve, is seen in Fig. 1. Perfluorochemicals (PFCs) carry oxygen by direct solubility, as does plasma. Because of the shape of the oxygen dissociation curve, hemoglobin is fully saturated and carries little or no more oxygen above a PO_2 of 90 mmHg (11.99 kPa). Because oxygen content dissolved in plasma, or carried by PFCs, is linearly related to PO_2, additional oxygen is dissolved in the plasma phase or by PFC as oxygen tension increases.

Arterial content of oxygen (C_aO_2) is defined as the volume of oxygen in milliliters (mL) carried by each 100 mL of blood and is defined as follows:

$$C_aO_2 = (\text{Hb} \times 1.34 \times SaO_2) + (0.003 \times P_aO_2) \approx 20\,\text{mL}/100\,\text{mL} \qquad (1)$$

(Hb = hemoglobin: S_aO_2, arterial oxygen saturation: P_aO_2, arterial oxygen tension)

With a normal 15 g of hemoglobin and normal P_aO_2 and S_aO_2 values of 90 mmHg (11.99 kpa) and 97%, respectively, an arterial oxygen content of $20\ \text{mL} \cdot \text{dL}^{-1}$ is obtained.

When blood contains an oxygen carrying PFC, the oxygen content equation requires a third term to represent the contribution from perfluorocarbon.

$$C_aO_2 = (\text{Hb} \times 1.34 \times S_aO_2) + (0.003 \times P_aO_2) + (0.057 \times \text{Fct}/100 \times P_aO_2) \qquad (2)$$

where Fct = fluorocrit, which is the fraction of the blood volume that is PFC (analogous to the Hct).

Note that the solubility factor of PFC in the third term should be 0.06, that is, 20 times that of the solubility factor for oxygen in plasma (0.003), however, it is reduced by the amount of the plasma solubility factor to account for the plasma displaced by the presence of PFC.

The PFCs carry much more oxygen than plasma, but hemoglobin itself is able to carry much more than any PFC. Figure 1 shows that blood with a Hct of 45% will have a C_aO_2 of 20 mL/100 mL at a PO_2 of 100 mmHg (13.33 kPa), but a solution with a Fct of 45% would have an oxygen content of 2.7 mL/100 mL. Because the PFC carries oxygen by direct solubility, it also releases it in direct proportion to the PO_2, unlike the cooperative binding effect of Hg, with which the PO_2 has to fall below the elbow of the curve for oxygen release to occur. The potential contribution of PFCs to oxygen transport can be assessed by looking at the oxygen consumption required by tissues, the Fct and the PO_2 required to allow this quantity of oxygen to be released in the tissues (28).

Mixed venous blood has an oxygen content of 15 mL/100 mL; therefore 5 mL/100 mL of oxygen is consumed in the periphery.

If we assume a mixed venous oxygen tension (P_vO_2) level of 40 mmHg (5.33 kPa) and an oxygen extraction of 5 mL/dL, a bloodless animal could survive with a Fct of 45% with a P_aO_2 of 235 mmHg (31.33 kPa). Any increase in P_aO_2 above this value would raise the P_vO_2 by the same amount (Fig. 2). The elevated P_vO_2 in these circumstances could have the beneficial effect of increasing the pressure gradient for oxygen diffusion from the vascular space into the tissues and cells, theoretically increasing tissue oxygenation.

It is, however, difficult to manufacture a 45% emulsion of PFC. In the late 1970s, the Green Cross Corporation in Japan developed a product called Fluosol DA 20%. This solution contains only 10% PFC (Fluosol DA 20% is 20% by weight, 10% by volume). To supply 5 mL/100 mL of oxygen consumption and a P_vO_2 of 40 mmHg (5.33 kPa), a bloodless animal with a fluocrit of 10% would require a P_aO_2 of 920 mmHg (122.65 kPa).

In practice, this would make it difficult to completely replace the blood with PFC emulsion. Although the emulsion is cleared from the vascular space within 24 h, the long tissue half-life of a PFC in the body (months to years), make it unfeasible to continuously redose the patient.



Figure 1. Oxygen content plotted against PO_2 for whole blood, plasma, and a perfluorochemical emulsion, with a 45% content of PFC. Hemoglobin saturates at a PO_2 of 100 mmHg (13.33 kPa), but the curve continues to rise because of the dissolved oxygen in plasma, so the whole blood and plasma lines are parallel above a PO_2 of 100. The line for perflubron is similar to plasma, but has a higher slope because of the greater affinity for oxygen (Hct = hemocrit).



Figure 2. At an arterial PO_2 (P_aO_2) of 300 mmHg (13.33 kPa) blood has an oxygen content of 21 mL/100 mL. If 5 mL/100 mL are extracted the venous PO_2 (P_vO_2) will be < 50 mmHg. A PFC with a Fct of 45% could carry enough oxygen at a P_aO_2 of 235 to deliver 5 mL and give a similar P_vO_2. Increasing the P_aO_2 to 300 mmHg (39.99 kPa), increases the oxygen carried by the PFC so the P_vO_2 will be > 100 mmHg (13.33 kPa) after delivery of 5 mL O_2. (Adapted, with permission, from Woodcock BJ, Tremper KK. Red Blood Cell Substitutes. In: Evers AS, Maze M, editors. Anesthetic Pharmacology, Physiological Principles and Clinical Practice: A Companion to Miller's Anesthesia. Philidelphia: Churchill Livingstone; 2004.)



Figure 3. Structures of the constituents of Fluosol DA; perfluorodecalin (a) and perfluortripropylamine (b).

CLINICAL STUDIES WITH PFCS

Fluosol DA

Fluosol DA 20% was developed in the 1970s and was an emulsion composed of two perfluorochemicals; perfluorodecalin, which has emulsion stability and perfluorotripropylamin, which has a shorter half-life (29) (Fig. 3). The surfactant used to maintain this emulsion of Fluosol DA was Pluronic F68, an emulsifier used in other medical products. The product needed to be frozen to maintain stability until used.

Initial clinical studies were in patients who were actively bleeding, required surgery, and refused blood transfusion. A 20-$\text{mL} \cdot \text{kg}^{-1}$ body weight of Fluosol DA 20% PFC emulsion was transfused preoperatively with a maximum of one additional dose postoperatively (29,30). The patients achieved a maximal fluorocrit of $< 3\%$ with an intravascular half-life of ~ 19 h. Subsequent studies confirmed the oxygen-carrying contribution of the PFC, but could not show a beneficial effect on patient outcome (31).

Fluosol DA 20% gained FDA approval, not for use as a red cell substitute but for intracoronary infusion in patients undergoing angioplasty. Fluosol is no longer being manufactured because of low demand.

Perflubron

Second generation PFC emulsions have been developed. One of these, Oxygent, employs perfluoro-octylbromide or perflubron (32) (Fig. 4). This PFC has one bromine replacing fluorine, making it radiopaque. The emulsion (Oxygent: Alliance Pharmaceutical, San Diego, CA) contains 60% PFC by weight, or 30% by volume. It is emulsified with lecithin (egg yolk phospholipids) and is stable at room temperature for > 6 years.

Because of a short intravascular half-life and the need for a high F_iO_2, it has been suggested that these PFC solutions should be used in conjunction with acute normovolemic hemodilution. In this setting, patients who are expected to have significant surgical blood loss should have two to four units of blood removed immediately before surgery. Initial volume expansion is with crystalloid or colloid. As surgical bleeding continues, the PFC is administered at the first transfusion trigger, allowing for adequate oxygen delivery at low hemoglobin levels. When surgical bleeding stops, the patient would receive the previously harvested autologous blood.



Figure 4. Structure of perfluoro-octylbromide (Perflubron, Oxygent).

The European Perflubron Emulsion Study Group looked at this technique of normovolemic hemodilution in orthopedic surgery. Perflubron was administered in response to transfusion triggers of tachycardia, hypotension, increased cardiac, and decreased mixed venous PO_2. The triggers for transfusion were at least as effectively reversed by perflubron, with 100% oxygen ventilation, as by autologous transfusion or colloid administration (33). Patients who received perflubron had higher mixed venous PO_2 levels, which continued for longer than the other treatment groups. Allogeneic blood transfusion requirements were not reduced by perflubron administration.

A phase III cardiac surgery study of perflubron was voluntarily suspended in 2001 because of an increased incidence of stroke, but it has not been determined if this was due to PFC administration.

A phase III study of perflubron in noncardiac surgery, again from the European Perflubron Emulsion Study Group (34), in 492 patients showed an intraoperative reduction in blood transfusion requirement, but there was no significant reduction by time of the postoperative period. Of the patients in the intent-to-treat population, 33% experienced low ($< 20\ \text{mL} \cdot \text{kg}^{-1}$) blood loss. When these patients were excluded to leave a protocol defined target population, the patients treated by acute normovolemic hemodilution (ANH) and PFC administration experienced a reduction in transfusion that remained significant throughout the study (3.4 vs. 4.9 units). The PFC group also had a significantly greater avoidance of transfusion (26 vs. 16%). The clinical relevance of these findings is hard to elucidate. The control group did not undergo ANH and had higher transfusion triggers during the operative period, it is difficult to tell if the benefit accrued was due to the PFC or the hemodilution technique (35).

Microcirculation and Oxygen-Carrying Colloids

Oxygen-carrying colloids differ from red cells in terms of size. Free hemoglobin molecules in solution range in size from 68,000 to 500,000 Da, and the fluorochemical emulsion particles are $\sim 0.2\,\mu\text{m}$. These sizes are within the range of many of the plasma proteins, and like plasma proteins, PFCs are able to cross the capillary basement membrane and participate in extravascular circulation. Animal data have shown that these oxygen-carrying colloids leave the intravascular space and rejoin it through lymphatic circulation (36). Thus, these colloids may be able to provide increased oxygen delivery to the extravascular space (37,38). In addition, studies on microcirculation have shown that plasma flow continues through capillaries even when the capillary is closed to red blood cells. Oxygen delivery to tissues can be provided, even though red cells are not present in the capillaries, through the circulation of oxygen-carrying colloids.

This potential application of blood substitutes, as "therapeutic oxygenating agents" for ischemic tissue, has been investigated for myocardial ischemia (39–41) and for enhancing the effectiveness of radiation therapy and chemotherapy of ischemic tumors by rendering the tumor hyperoxic (42,43).

Perfluourochemicals have been used in other circumstances as oxygen-carrying molecules. The PFCs have been used for cardiplegia (44) and preservation of transplanted organs (45–47). The PFCs have also been studied in models of myocardial and cerebral infarcts to minimize infarct size (45,48,49).

Liquid Ventilation with PFC

Perfluorochemicals have been used for liquid ventilation in the treatment of acute respiratory distress syndrome (ARDS). The PFCs bind oxygen and carbon dioxide avidly. Perflubron (LiquiVent, Alliance Pharmaceutical Corp., San Diego, CA) can be instilled into the endotracheal tube of a ventilated patient with ARDS until a fluid level is seen outside the patient. The ET is then connected to the normal ICU ventilator and sufficient gas transfer occurs across the PFC–gas interface to allow oxygenation of the patient and CO_2 clearance (50,51). This PFC has excellent surfactant properties and is possibly able to stent open alveoli (leading it to be termed "liquid PEEP" or "PEEP in a bottle") (52). There are also benefits of increased secretion clearance and possible antiinflammatory effects (53,54). Studies to date have not shown any benefit over conventional ventilation (55).

Future of PFCs

The PFCs have inherent limitations of a short endovascular half-life and the requirement for high inspired oxygen. These problems limit the use of PFC emulsions to acute settings in which supplemental oxygen is readily available. It is yet to be seen whether PFCs can have a useful role as blood substitutes.

HEMOGLOBIN SOLUTIONS

Hemoglobin Solutions: Oxygen Content

When a solution of free hemoglobin (FHb) has the same $P50$ as blood (27 mmHg 3.59 kPa), there is no difference between the hemoglobin solution oxygen-content curve and the curve for normal whole blood.

$$C_aO_2 = (\mathrm{FHb} \times 1.34 \times \mathrm{F}S_aO_2) + (\mathrm{Hb} \times 1.34 \times S_aO_2) + (0.003 \times P_aO_2) \qquad (3)$$

[FHb is the concentration of free hemoglobin solution in blood ($g \cdot dL^{-1}$), and $\mathrm{F}S_aO_{2,}$ is the saturation of FHb.]

In clinical practice, arterial content of oxygen can be calculated using a single term for hemoglobin and saturation. A spectrophotometrically measured total hemoglobin should be used, which will measure total hemoglobin present, whereas the hematocrit only measures red blood cell hemoglobin. The saturation measured by an oximeter gives a mean saturation of both forms of hemoglobin because the device measures the amount of oxyhemoglobin and divides it by total hemoglobin to achieve the calculated saturation.

Formulation of Hemoglobin Solutions

A solution of hemoglobin from lyzed human red cells is unusable as a blood substitute for a variety of reasons. Hemoglobin outside the red cell membrane loses its tetrameric form and breaks down into dimers. The abundance of dimers in plasma has a pronounced oncotic effect creating an excessively high colloid oncotic pressure (41). This would draw fluid from the extracellular space and would cause an increase in circulating blood volume. The dimers have a molecular weight of 32,000 Da and are able to cross the renal glomerular basement membrane leading to a potent osmotic diuretic effect. The loss of oxygenated hemoglobin in the urine gave the early solutions the reputation of being "red mannitol".

The loss of 2,3-DPG, which is normally maintained inside the RBC, reduces the P50 of hemoglobin to 12–14 mmHg (1.59–1.86 kPa) from a normal level of 26. This shifts the oxygen dissociation curve markedly to the left, meaning that the free hemoglobin will avidly bind oxygen during passage through the lungs but will not release it in the peripheral tissues unless the PO_2 is extremely low.

The early attempts at making a hemoglobin solution used resuspended hemoglobin filtered from lyzed, outdated, human blood. This solution caused a high incidence of renal failure, which proved not to be due to the free hemoglobin, but due to the "stroma" of residual red blood cell elements left after cell lysis (56).

Several types of hemoglobin solution have been developed, and have taken different approaches to these problems. One product is produced from modified polymerized bovine hemoglobin (Hemopure, HBOC-201, Biopure, Cambridge, USA) (57,58). The dimer form is polymerized to form a larger roughly octomeric molecules (Fig. 5). It is



Figure 5. Hemoglobin dimer subunits can be polymerized (a) to form tetramers. These can be further polymerized (b) to form octamers or larger units, or can be cross-linked (c) to increase molecular size.

Table 2. Hemoglobin Solutions in Clinical Trials

Product (Manufacturer)	Configuration	$P50$	Status
		Bovine Hemoglobins	
HBOC201 Hemopure (Biopure)	Polymerized with glutaraldehyde	34 mmHg	Licensed in South Africa and for veterinary use. FDA review; further studies required
PEG-hemoglobin (Enzon)	PEG (polyethylene glycol) conjugated noncross-linked, encapsulated	20 mmHg	Phase 1 melanoma studies completed Now discontinued
		HumanHemoglobins	
Polyheme (Northfield)	Polymerized, tetramer-free	30 mmHg	Phase 3 study, before FDA review
Hemolink (Hemosol)	Polymerized with *o*-raffinose	32 mmHg	Under review United Kingdom and Canada
DCLHb (Baxter)	Cross-linked with diaspirin	32 mmHg	Discontinued
PHP (Curacyte)	Pyridoxylated		Studied in SIRS
		Recombinant Hemoglobins	
Optro (Somatogen)	Genetically fused	17 mmHg	Discontinued

then filtered to remove the smaller molecular weight tetrameric hemoglobin molecules. This reduces the oncotic pressure and prevents passage of the molecule though the glomerulus into the urine. Polymerization also increases the $P50$ into the normal range and allows the hemoglobin solution to release oxygen in the tissues (41).

Other products have been developed from outdated human blood: Cross-linking hemoglobin molecules with pyridoxal-5-phosphate (Fig. 5), which acts as an artificial 2, 3-DPG, can increase the $P50$. This technique is used in PolyHeme polymerized hemoglobin solution (Northfield Pharmaceutical, Chicago, IL) (59–61), and pyridoxylated hemoglobin polyoxyethylene conjugate or PHP hemoglobin (62). Diaspirin Cross-Linked Hemoglobin, DCLHb (Baxter Healthcare, Chicago, IL) (63,64) and Hemolink (Hemosol, Toronto, Ontario, Canada) also have a $P50$ within the normal range and have an increased size due to cross-linking or polymerization.

The size of the hemoglobin molecule can also be increased by attaching the dimer to a large non-hemoglobin molecule, for example, polyethylene glycol used in PEG–hemoglobin (Enzon, Piscataway, NJ). A final method of increasing molecular size is to encapsulate hemoglobin in phospholipid vesicles or liposomes (65).

Hemoglobin cannot only be obtained from outdated human blood, but also from bovine blood. There is a tremendous supply of bovine blood, since nearly 1 million units/day are produced as a byproduct of meat production. Bovine hemoglobin does not normally require 2, 3-DPG, and maintains a $P50$ in the range of 32 mmHg (4.26 kPa), even as a dimer (66). Concern over the spread of BSE or variant vCJD may impact the development of bovine products (67). The FDA has restricted the import of bovine products from Europe because of the outbreak of Mad Cow disease there (68).

Recombinant hemoglobin has been used as an alternative source of hemoglobin. Optro (Somatogen), was engineered to have a $P50$ in the normal range. However, manufacture has been discontinued (67).

The hemoglobin solutions that have undergone clinical trial are listed in Table 2. Since these solutions are produced from different hemoglobin sources, and have different sizes and different $P50$ values, each needs to be evaluated as a separate drug with its own effectiveness and toxicity profile.

All of these products have a relatively short intravascular half-life compared to hemoglobin contained in red blood cells, and are cleared from the vascular space by the reticuloendothelial system with a half-life of $\sim$24 h.

Hemodynamic Effects of Hemoglobin Solutions

Pulmonary and systemic hypertension have been observed in studies in animals (63,69–72) and human clinical studies (36,38,57,64,73–78). The cause of this appears to be related to the nitric oxide (NO) scavenging properties of hemoglobin. Endothelium derived relaxant factor (EDRF) was identified as NO in the 1990s and its role in controlling vascular resistance was elucidated. Nitric oxide is produced in the endothelial cells of blood vessel walls, and produces smooth muscle relaxation, thereby causing vasodilatation. As blood flow increases, nitric oxide is carried away, reducing its concentration and causing vasoconstriction (79). Binding of nitric oxide to hemoglobin plays an important role in its removal, and thereby the control of vascular tone. Free hemoglobin binds nitric oxide more avidly than hemoglobin within the red cell and nitric oxide clearance is increased (80). This leads to hypertension in the pulmonary and systemic vascular beds. Smaller hemoglobin molecule size appears to increase NO clearance, and pulmonary hypertension becomes more problematic. The severity of this side effect varies with the different forms and preparations of hemoglobin.

The observed vasoconstriction with hemoglobin solutions led to the evaluation of DCLHb solution as an "all-in-one" therapeutic strategy in vasodilated shock states (38) as a vasopressor in critically ill patients with septic shock. In septic shock or systemic inflammatory response syndrome, the vasodilated state may be due to excessive synthesis of NO. The scavenging effect of the hemoglobin solution may be beneficial in restoring vascular tone in this setting (37). Tissue perfusion may be improved because of the small size of the hemoglobin molecules compared to red cells, improving oxygen delivery through the microcirculation. In a mouse model of gram-negative sepsis, hemoglobin solution was associated with increased circulating tumor necrosis factor and increased lethality (81). In pigs with septic shock, DCLHb administration restored blood pressure and allowed a reduction in dopamine infusion being used for resuscitation (82). Further work is required to determine the utility of hemoglobin solutions in critical illness (83).

Although NO scavenging may play a major role in the vasoconstriction seen with hemoglobin solutions it may not explain the whole picture. Hemoglobin molecules with similar rates of NO binding may have strikingly different degrees of vasoconstriction. The fall in PO_2 in terminal arterioles may play a large role in the autoregulation of microvascular circulation by causing vasoldilation. Hemoglobin solutions may deliver excess oxygen to the terminal capillaries causing vasoconstriction and paradoxically reducing oxygen delivery to the tissue (84).

This proposed effect on microcirculation has led to the adoption of a "counterintuitive" approach to hemoglobin solution development. An anemic but hyperoncotic solution with a very low $P50$ could delay oxygen release and prevent vasoconstriction (85). Such a solution has been developed in MalPEG-Hb (maleimide-activated polyethylene glycol conjugated hemoglobin). This MalPEG-Hb solution has a $P50$ of 5.5 mmHg and has been shown to improve microvascular circulation in hypovolemic shock in hamsters (86).

Duration of Action of Hemoglobin Solutions

Just as free hemoglobin is scavenged following intravascular hemolysis, the RE system scavenges hemoglobin solution from the blood stream. The effective intravascular life of the hemoglobin solution is $\sim$12–48 h, depending on the dose (66). Therefore, hemoglobin solutions, like the PFCs, will not have a role in maintaining oxygen-carrying capacity in chronically anemic patients. They may be used in acute, limited blood-loss situations as resuscitative fluids, especially in combination with perioperative autologous hemodilution to minimize loss of the patients own blood (87,88).

Hematopoietic Effect of Hemoglobin Solutions

Hemoglobin solutions may have a profound effect in stimulating erythropoiesis. Studies in which animals are hemodiluted to a low Hct, and given a transfusion of hemoglobin solution, demonstrate a pronounced level of red blood cell production exceeding that expected even with the administration of exogenous erythropoietin (36).

Free iron liberated when hemoglobin solutions are broken may stimulate erythropoiesis, reducing the requirement for subsequent red cell transfusion (89,90). Transfusion of diaspirin cross-linked hemoglobin (DCLHb) to transfuse cardiac surgery patients in the postbypass period resulted in 19% of patients not requiring packed red blood cell transfusion, although the DCLHb was rapidly cleared from the circulation (77). After acute normovolemic hemodilution (ANH) with HBOC-201 in human volunteers there were increases in serum iron, ferritin, and erythropoietin that did not occur following ANH with Ringer's lactate solution (91).

Other Uses of Hemoglobin Solutions

Hemoglobin solutions have an oxygen delivery curve similar to that of hemoglobin in red blood cells. At low temperatures the curve is shifted to the left, preventing release of the bound oxygen, they therefore may not be of any benefit as a constituent of cardioplegia solutions or organ preservatives used for transplanted organs.

Artifical oxygen carriers have a potential for abuse by elite athletes, and international sporting federations have already added the class of agent to their banned substance lists (92).

Clinical Trials: Hemoglobin Solutions

HBOC-201 (Hemopure). The bovine product HBOC-201 (Hemopure, Biopure, Cambridge, MA) is produced from modified polymerized bovine hemoglobin and has been studied in patients undergoing abdominal aortic aneurysm surgery. Treatment with the hemoglobin solution produced an increase in pulmonary and systemic vascular resistance and an associated decrease in cardiac output (57). In another study in aortic surgery HBOC-201, 27% of patients did not need blood transfusion, but the median transfusion requirement was not decreased. Mean arterial blood pressure increased by 15% in this study (75). Vasoconstriction and hypertension have been noted in many studies with HBOC-201. A study looking at preoperative hemodilution with bovine HBOC-201 before liver resection showed an increase in systemic vascular resistance and a fall in cardiac output (73). More recently, a study by Wahr et al. (36) found this product to be useful in reducing the amount of allogeneic blood in operative patients. Increases in pulmonary or systemic resistance were not seen, but a mild increase in blood pressure occurred.

In postoperative cardiac surgery patients, administration of up to 1000 mL HBOC-201 prevented packed red blood cell administration in 34% of patients who would otherwise have received it (93). Although the HBOC-201 had a short duration in the circulation, Hct was restored rapidly, perhaps due to a hematinic effect. The HBOC-201 patients had a slightly greater increase in blood pressure after transfusion.

HBOC-201 has been administered to patients with sickle cell anemia and may have a role in the treatment of vasoocclusive or aplastic crises in this disease (94,95).

The HBOC-201 can be used instead of PRBCs to transfuse patients with severe autoimmune hemolytic anemia, the hemoglobin solution does not have the surface antigens associated with red blood cells (96). In the presence of a Hct of 4.4% the hemoglobin solution reversed both lactic acidosis and myocardial ischemia.

In South Africa, HBOC-201 (Hemopure) has been licensed to treat anemia in surgical patients; this is the first time a hemoglobin solution has reached the market in humans. It is also licensed, as Oxyglobin, for veterinary use in the United States and Europe. The FDA approval for human use in the United States has been delayed pending a request for further information and animal testing.

Diaspirin Cross-Linked Hemoglobin, DCLHb

The DCLHb (Baxter Healthcare, Chicago, IL) has been developed from outdated human blood. Clinical studies to date have had varying results with DCLHb.

The DCLHb effectively scavenges NO and has been noted to increase pulmonary and systemic vascular resistance in the hemodilution model in animals to the point of reducing cardiac index and oxygen delivery relative controls (63). Pulmonary and systemic hypertension with rises in SVR and PVR also occurred in human studies of DCLHb given after cardiac surgery, and this led to decreased cardiac output compared to patients given red cell transfusion (77). Another study (76) showed that DCLHb could be used to reduce the number of patients requiring perioperative packed red blood cell (PRBC) transfusions following vascular, orthopedic, and abdominal surgery compared with patients randomized to PRBC transfusions. However, the total PRBC and other blood product requirements of the two groups were similar over the subsequent week. Side effects of hypertension, jaundice and hemoglobinuria were noted. One death from respiratory distress syndrome was attributed to DCLHb, and the study was terminated early.

This solution was also investigated in a randomized study of patients with acute ischemic stroke (64). Patients receiving the hemoglobin solution had more deaths, serious adverse outcomes, and worse outcome scale scores.

Studies in patients with hemorrhagic shock in the United States and Europe were discontinued because of increased mortality in the U.S. study, and a lack of benefit with DCLHb administration in the European study (97).

Because of these results Baxter has discontinued further work with DCLHb. He subsequently acquired Somatogen, manufacturer of Optro, a first generation recombinant hemoglobin, development of which has since been discontinued.

PolyHeme

PolyHeme (Northfield Pharmaceutical, Chicago, IL) has been used in trials treating acute trauma patients. Gould et al. administered 1–20 units of PolyHeme to 171 patients with urgent blood loss; 81 patients received 5 or more units and 34 received 10–20 units (98). Overall there was a mortality of 10.5 compared to 16% of historical controls who declined blood transfusion because of religious reasons during surgery, and had Hb levels < 8 g/dL. However, there was no comparison with controls receiving transfusion of allogeneic packed red blood cells. An earlier study, also by Gould, randomly assigned 44 trauma patients to either receive blood (23 patients) or up to 6 units of PolyHeme (21 patients) (60). There were no adverse effects on pulmonary and systemic vascular resistance or cardiac output from the administration of PolyHeme. There were no differences in patient outcomes, although there was a reduced need for red blood cells in the PolyHeme group at day 1, which was no longer seen by day 3. The lack of effect of PolyHeme on systemic and peripheral vascular resistance is attributed to its manufacturing process, which filters out the smaller tetrameric hemoglobin (59,60). It is speculated that the smaller size hemoglobin elements can defuse through the vessel wall, increasing NO scavenging and producing vasoconstriction.

Studies have found an intravascular half-life of 24 h of PolyHeme, which is longer than that found in previous studies that found a halflife in the range of 9–12 h. It may be that the half-life of these products is dose dependent; studies showing a larger dose produces a longer half-life.

PolyHeme is currently being assessed in a large multicenter study compared to saline for trauma patients. An application to the FDA for approval may follow this study and PolyHeme could have a role in future clinical practice.

Hemolink

Hemolink (Hemosol, Toronto, Ontario, Canada) is an O-raffinose cross-linked human hemoglobin, which has been shown to cause vasoconstriction in animals (70). As with other cross-linked hemoglobin solutions, the hemodynamic effects are less pronounced than with unmodified hemoglobin solutions (99) but exceed that of polymerized hemoglobin solutions.

A Phase I study in healthy human volunteers showed the solution was well tolerated apart from some moderate to severe abdominal pain, which occurred in all subjects at higher doses. Blood pressure rose by 14% following administration, and with higher doses this elevation lasted 24 h (78). The findings of a Phase II study in coronary artery bypass (CAB) surgery (74) reported a 7–10% increase in blood pressure, which was not statistically significant, and a reduction in the number of patients requiring red cell transfusion from 57 to 10%. A further report by the same group using intraoperative autologous donation and volume replacement with Hemolink or pentastarch in CAB surgery abolished the need for intraoperative transfusion (0 vs. 17% in the pentastarch group) (100). The reduction in transfusion requirement continued at 1 day (7 vs. 37%) and 5 days (10 vs. 47 %) after surgery. Adverse effects included hypertension (43 vs. 17%) and atrial fibrillation (37 vs. 17%).

A similar study in CAB patients using intraoperative autologous blood donation (IAD) and volume replacement with Hemolink or pentastarch showed a reduction in transfusion from 76% in the pentastarch group to 56% with Hemolink (101). This was compared to an historical group of patients in whom IAD was not used, who required transfusion in 95% of operations. Hypertension was again noted in the Hemolink treated group.

Hemolink is under review for approval by the drug agencies of the United States, Canada, and the United Kingdom.

PEG Hemoglobin

The PEG Hemoglobin (Enzon, Piscataway, NJ) is a bovine hemoglobin conjugated with polyethylene glycol. This increases the molecular size without using cross-linking between molecules. Retention in the circulation is increased as the conjugated molecule does not cross the glomerular basement membrane. Administration in dogs resulted in no elevation of blood pressure and it was well tolerated (102).

The PEG hemoglobin has been used to sensitize tumors to chemotherapy (103) and radiotherapy in rodents (104). The small molecular size, compared to red cells, improves microvascular oxygenation, and tumors that are hypoxic become more responsive to chemotherapy and radiotherapy.

The PEG hemoglobin has also been used in rabbits, in the preservative perfusate, and for protection of transplanted hearts during the ischemic period with improvement in cardiac function post-transplant (105).

PHP

Pyridoxilated hemoglobin polyoxyethylene conjugate or PHP (Curacyte, Chapel Hill, NC) is a human hemoglobin solution, cross-linked by pyridoxal-5-phosphate, which is being developed as a NO scavenger for use in septic shock and systemic inflammatory response syndrome (62). A Phase II study has been completed and a Phase III study is in progress looking at PHP for the treatment of NO induced shock.

Encapsulated Hemoglobins

The problems of small hemoglobin molecule size, leading to NO scavenging, high oncotic pressures, and osmotic diuresis can be countered by encapsulating the hemoglobin. This mimics the natural presentation of hemoglobin in whole blood and is sometimes referred to as “neo red cells” (65). Most work has used liposome encapsulated hemoglobin (LEH), but biodegradable polymer microcapsules have also been used (106). Circulation time of the hemoglobin is increased by encapsulation and can be increased, from 18 to 65 h, by polyethylene glycol (PEG) modification (107), these long-lasting derivatives have been named “stealth” liposomes. However, there is significant accumulation of liposomes in the liver and spleen, when LEH is given, causing vacuolization seen on liver biopsy. Liver transaminases may also be elevated (41).

BIBLIOGRAPHY

Cited References

1. Epstein JS. The US blood supply. Am Fam Phys 2000;61: 549–550.
2. American Society of Anesthesiologists Task Force on Blood Component Therapy, Practice Guidelines for blood component therapy. Anesthesiology 1996;84:732–747.
3. Spahn DR, Casutt M. Eliminating blood transfusions: new aspects and perspectives. Anesthesiology 2000;93:242–255.
4. Cohn SM. Blood substitutes in surgery. Surgery 2000;127: 599–602.
5. Ketcham EM, Cairns CB. Hemoglobin-based oxygen carriers: development and clinical potential. Ann Emerg Med 1999; 33:326–337.
6. Myhre BA, Bove JR, Schmidt PJ. Wrong blood—a needless cause of surgical deaths. Anest Analg 1981;60:777–778.
7. Nichollis MD. Transfusions: morbidity and mortality. Anaesth Intensive Care 1993; 15–19.
8. Sazama K. Reports of 355 transfusion-associated deaths: 1976 through 1985. Transfusion (Paris) 1990;30:583–590.
9. Newman RJ, Podolsky D, Loeb P. Bad blood. US News World Rep 1994;116:68–70.
10. Lackritz EM. Prevention of hiv transmission by blood transfusion in the developing world: achievements and continuing challenges. AIDS 1998;12:81–86.
11. Chamberland M, Khabbaz RF. Emerging issues in blood safety. Inf Dis Clin North Am 1998;12:217–229.
12. Dodd RY. The risk of transfusion-transmitted infection. N Engl J Med 1992;327:419–421.
13. Yoshikawa A, Fukuda S, Itoh K, Kosaki N, Suzuki T, Hirakawa K, Nakao H, Inoue T, Fukuda M, Okamoto H. Infection with hepatitis g virus and its strain variant, the gb agent (gbv-c), among blood donors in japan. Transfusion (Paris) 1997;37:657–663.
14. Tacke M, Kiyosawa K, Stark K, Schlueter V, Ofenloch-Haehnle B, Hess G, Engel AM. Detection of antibodies to a putative hepatitis g virus envelope protein. Lancet 1997;349:318–320.
15. Fiebig EW, Busch MP. Emerging infections in transfusion medicine. Clin Lab Med 2004;24:797.
16. Alter MJ, Gallagher M, Morris TT, Moyer LA, Meeks EL, Krawczynski K, Kim JP, Margolis HS. Acute non-a-e hepatitis in the united states and the role of hepatitis g virus infection. Sentinel counties viral hepatitis study team. N Engl J Med 1997;336:741–746.
17. Alter HJ, Nakatsuji Y, Melpolder J, Wages J, Wesley R, Shih JW, Kim JP. The incidence of transfusion-associated hepatitis g virus infection and its relation to liver disease. N Engl J Med 1997;336:747–754.
18. Karayiannis P, Thomas HC. Current status of hepatitis g virus (gbv-c) in transfusion: is it relevant? Vox Sang 1997;73:63–69.
19. Ricketts MN, Cashman NR, Stratton EE, ElSaadany S. Is creutzfeldt-jakob disease transmitted in blood? Emerg Infect Dis 1997;3:155–163.
20. Houston F, Foster JD, Chong A, Hunter N, Bostock CJ. Transmission of bse by blood transfusion in sheep. Lancet 2000;356:999–1000.
21. Mitka M. Blood groups differ on donor deferral. JAMA 2001;285:1694–1695.
22. Iwamoto M, Jernigan DB, Guasch A, Trepka MJ, Blackmore CG, Hellinger WC, Pham SM, Zaki S, Lanciotti RS, Lance-Parker SE, DiazGranados CA, Winquist AG, Perlino CA, Wiersma S, Hillyer KL, Goodman JL, Marfin AA, Chamberland ME, Petersen LR. West Nile Virus in Transplant Recipients Investigation Team, Transmission of west nile virus from an organ donor to four transplant recipients. N Engl J Med 2003;348:2196–203.
23. Blumberg N, Triulzi DJ, Heal JM. Transfusion-induced immunomodulation and its clinical consequences. Transfus Med Rev 1990;4:24–35.
24. Bordin JO, Blajchman MA. Immunosuppressive effects of allogeneic blood transfusions: implications for the patient with a malignancy. Hematol Oncol Clin North Am 1995;9: 205–218.
25. Biedler AE, Schneider SO, Seyfert U, Rensing H, Grenner S, Girndt M, Bauer I, Bauer M. Impact of alloantigens and

storage-associated factors on stimulated cytokine response in an in vitro model of blood transfusion. Anesthesiology 2002;97:1102–1109.

26. Clark Jr LC, Gollan F. Survival of mammals breathing organic liquids equilibrated with oxygen at atmospheric pressure. Science 1966;152:1755–1766.
27. Gehes RP, Monroe RG, Taylor K. Survival of rats having red cells totally replaced with emulsified fluorocarbon. Fed Pro 1968;27:384.
28. Woodcock BJ, Tremper KK. Red Blood Cell Substitutes. In: Evers AS, Maze M, editors. Anesthetic Pharmacology: Physiological Principles and Clinical Practice: A Companion to Miller's Anesthesia. Philidelphia: Churchill Livingstone; 2004.
29. Tremper KK, Friedman AE, Levine EM, Lapin R, Camarillo D. The preoperative treatment of severely anemic patients with a perfluorochemical oxygen-transport fluid, Fluosol-DA. N Engl J Med 1982;307:277–283.
30. Tremper KK, Levine EM, Waxman K. Clinical experience with Fluosol-DA (20%) in the United States. Int Anesthesiol Clinic 1985;23:185–197.
31. Gould SA, Rosen AL, Sehgal LR, Sehgal HL, Langdale LA, Krause LM, Rice CL, Chamberlin WH, Moss GS. Fluosol-DA as a red-cell substitute in acute anemia. N Engl J Med 1986;314:1653–1656.
32. Keipert PE, Faithfull NS, Bradley JD, Hazard DY, Hogan J, Levisetti MS, Peters RM. Oxygen delivery augmentation by low-dose perfluorochemical emulsion during profound normovolemic hemodilution. Adv Exp Med Biol 1994;345: 197–204.
33. Spahn DR, van Brempt R, Theilmeier G, Reibold JP, Welte M, Heinzerling H, Birck KM, Keipert PE, Messmer K, Heinzerling H, Birck KM, Keipert PE, Messmer K. Perflubron emulsion delays blood transfusions in orthopedic surgery. European perflubron emulsion study group. Anesthesiology 1999;91:1195–208.
34. Spahn DR, Waschke KF, Standl T, Motsch J, Van Huynegem L, Welte M, Gombotz H, Coriat P, Verkh L, Faithfull S, Keipert P. Use of perflubron emulsion to decrease allogeneic blood transfusion in high-blood-loss non-cardiac surgery: results of a European phase 3 study. Anesthesiology 2002;97:1338–1349.
35. Tremper KK. Perfluorochemical "red blood cell substitutes": the continued search for an indication. Anesthesiology 2002;97:1333–1334.
36. Wahr JA, Levy JH, Kindscher J. Hemodynamic effects of a bovine based oxygen carrying solution in surgical patients. Anesthesiology 1996;85:A347.
37. Creteur J, Vincent JL. Hemoglobin solutions: an "all-in-one" therapeutic strategy in sepsis? Crit Care Med 2000;28: 894–896.
38. Reah G, Bodenham AR, Mallick A, Daily EK, Przybelski RJ. Initial evaluation of diaspirin cross-linked hemoglobin (DCLHB) as a vasopressor in critically ill patients. Crit Care Med 1997;25:1480–1488.
39. Robalino BD, Marwick T, Lafont A, Vaska K, Whitlow PL. Protection against ischemia during prolonged balloon inflation by distal coronary perfusion with use of an autoperfusion catheter or Fluosol. J Am Coll Cardiol 1992;20:1378–1384.
40. Kent KM, Cleman MW, Cowley MJ, Forman MB, Jaffe CC, Kaplan M, King SB 3rd, Krucoff MW, Lassar T, McAuley B. et al. Reduction of myocardial ischemia during percutaneous transluminal coronary angioplasty with oxygenated Fluosol. Am J Cardiol 1990;66:279–284.
41. Creteur J, Sibbald W, Vincent JL. Hemoglobin solutions–not just red blood cell substitutes. Crit Care Med 2000;28: 3025–3034.
42. Teicher BA, Schwartz GN, Dupuis NP, Kusomoto T, Liu M, Liu F, Northey D. Oxygenation of human tumor xenografts in nude mice by a perfluorochemical emulsion and carbogen breathing. Artif Cells, Blood Sub Immobil Biotechnol 1994; 22:1369–1375.
43. Teicher BA. An overview on oxygen carriers in cancer therapy. Artif Cells, Blood Sub Immobil Biotechnol 1995; 23:395–405.
44. Martin SM, Laks H, Drinkwater DC, Stein DG, Capouya ER, Pearl JM, Barthel SW, Chang P, Kaczer E, Bhuta S. Perfluorochemical reperfusion yields improved myocardial recovery after global ischemia. Ann Thorac Surg 1993;55: 954–960.
45. Kloner RA, Hale S. Cardiovascular applications of fluorocarbons in regional ischemia/reperfusion. Artif Cells Blood Substit Immobil Biotechnol 1992;22:1069–1081.
46. Segel LD, Follette DM, Iguidbashian JP, Contino JP, Castellanos LM, Berkoff HA, Kaufman RJ, Schweighardt FK. Posttransplantation function of hearts preserved with fluorochemical emulsion. J Heart Lung Trans 1994;13: 669–680.
47. Grunert A, Qiu H, Muller I, Schuh S, Steinbach G, Wennauer R, Wolf C, Von Schenck H. A new extracorporeal perfusion system: prolongation of liver organ vitality beyond 24 hours. Ann N Y Acad Sci 1994;723:488–490.
48. Premaratne S, Harada RN, Chun P, Suehiro A, McNamara JJ. Effects of perfluorocarbon exchange transfusion on reducing myocardial infarct size in a primate model of ischemia-reperfusion injury: a prospective, randomized study. Surgery 1995;117:670–676.
49. Cole DJ, Schell RM, Drummond JC, Pryzbelski RJ, Marcantonio S. Focal cerebral ischemia in rats: effect of hemodilution with alpha-alpha cross-linked hemoglobin on brain injury and edema. Can J Neurol Sci 1993;20:30–36.
50. Gauger PG, Overbeck MC, Chambers SD, Cailipan CI, Hirschl RB. Partial liquid ventilation improves gas exchange and increases EELV in acute lung injury. J Appl Physiol 1998;84:1566–1572.
51. Hirschl RB, Pranikoff T, Wise C, Overbeck MC, Gauger P, Schreiner RJ, Dechert R, Bartlett RH. Initial experience with partial liquid ventilation in adult patients with the acute respiratory distress syndrome. JAMA 1996;275:383–389.
52. Wong DH. Liquid ventilation: more than "PEEP in a bottle"? Crit Care Med 1999;27:1052–1053.
53. Colton DM, Till GO, Johnson KJ, Dean SB, Bartlett RH, Hirschl RB. Neutrophil accumulation is reduced during partial liquid ventilation. Crit Care Med 1998;26:1716–1724.
54. Mrozek JD, Smith KM, Bing DR, Meyers PA, Simonton SC, Connett JE, Mammel MC. Exogenous surfactant and partial liquid ventilation: physiologic and pathologic effects. Am J Resp Crit Care Med 1997;156:1058–1065.
55. Hirschl RB, Conrad S, Kaiser R, Zwischenberger JB, Bartlett RH, Booth F, Cardenas V. Partial liquid ventilation in adult patients with ARDS: a multicenter phase I-II trial. Adult PLV Study Group. Ann Surg 1998;228:692–700.
56. Rabiner SF, Friedman LH. The role of intravascular haemolysis and the reticulo-endothelial system in the production of a hypercoagulable state. Br J Haematol 1968;14: 105–118.
57. Kasper SM, Grune F, Walter M, Amr N, Erasmi H, Buzello W. The effects of increased doses of bovine hemoglobin on hemodynamics and oxygen transport in patients undergoing preoperative hemodilution for elective abdominal aortic surgery. Anesth Analg 1998;87:284–291.
58. Standl T, Burmeister MA, Horn EP, Wilhelm S, Knoefel WT, Schulte am Esch J. Bovine haemoglobin-based oxygen

carrier for patients undergoing haemodilution before liver resection. Br J Anaesth 1998;80:189–194.

59. Johnson JL, Moore EE, Offner PJ, Haenel JB, Hides GA, Tamura DY. Resuscitation of the injured patient with polymerized stroma-free hemoglobin does not produce systemic or pulmonary hypertension. Am J Surg 1998;176:612–617.
60. Gould SA, Moore EE, Hoyt DB, Burch JM, Haenel JB, Garcia J, DeWoskin R, Moss GS. The first randomized trial of human polymerized hemoglobin as a blood substitute in acute trauma and emergent surgery. J Am Coll Surg 187:113–20; discussion 1998; 120–122.
61. Sehgal LR, Rosen AL, Gould SA, Sehgal HL, Moss GS. Preparation and in vitro characteristics of polymerized pyridoxylated hemoglobin. Transfusion (Paris) 1983;23: 158–162.
62. Privalle C, Talarico T, Keng T, DeAngelo J. Pyridoxalated hemoglobin polyoxyethylene: a nitric oxide scavenger with antioxidant activity for the treatment of nitric oxide-induced shock. Free Rad Biol Med 2000;28:1507–1517.
63. DeAngeles DA, Scott AM, McGrath AM, Korent VA, Rodenkirch LA, Conhaim RL, Harms BA. Resuscitation from hemorrhagic shock with diaspirin cross-linked hemoglobin, blood, or hetastarch. J Trauma-Injury Inf Crit Care 42:406–412; discussion 1997; 412–414.
64. Saxena R, Wijnhoud AD, Carton H, Hacke W, Kaste M, Przybelski RJ, Stern KN, Koudstaal PJ. Controlled safety study of a hemoglobin-based oxygen carrier, DCLHB, in acute ischemic stroke. Stroke 1999;30:993–996.
65. Rudolph AS. Encapsulated hemoglobin: current issues and future goals. Artif Cells, Blood Sub Immobiliz Biotechnol 1994;22:347–360.
66. Hughes GS Jr., Antal EJ, Locker PK, Francom SF, Adams WJ, Jacobs EE Jr Physiology and pharmacokinetics of a novel hemoglobin-based oxygen carrier in humans. Crit Care Med 1996;24:756–764.
67. Winslow RM. Blood substitutes. Adv Drug Del Rev 2000;40: 131–142.
68. USDA Interim Rule on Import Restrictions of Ruminant Material from Europe. Fed Proc 1998;63:406–408.
69. Ulatowski JA, Nishikawa T, Matheson-Urbaitis B, Bucci E, Traystman RJ, Koehler RC. Regional blood flow alterations after bovine fumaryl beta beta-crosslinked hemoglobin transfusion and nitric oxide synthase inhibition. Crit Care Med 1996;24:558–565.
70. Ning J, Wong LT, Christoff B, Carmichael FJ, Biro GP. Haemodynamic response following a 10% topload infusion of Hemolink™ in conscious, anaesthetized and treated spontaneously hypertensive rats. Transfus Med 2000;10:13–22.
71. Krieter H, Hagen G, Waschke KF, Kohler A, Wenneis B, Bruckner UB, van Ackern K. Isovolemic hemodilution with a bovine hemoglobin-based oxygen carrier: effects on hemodynamics and oxygen transport in comparison with a non-oxygen-carrying volume substitute.[See comment]. J Cardiothor Vas Anesthes 1997;11:3–9.
72. Maxwell RA, Gibson JB, Fabian TC, Proctor KG. Resuscitation of severe chest trauma with four different hemoglobin-based oxygen-carrying solutions. J Trauma-Injury Inf Crit Care 49:200–209; discussion 2000; 209–211.
73. Standl T, Wilhelm S, Horn EP, Burmeister M, Gundlach M, Schulte am Esch J. Preoperative hemodilution with bovine hemoglobin. Acute hemodynamic effects in liver surgery patients. Anaesthesist 1997;46:763–770.
74. Cheng DC, Ralph-Edwards A, Mazer CD, Carmichael FJL, Biro GP. The hemodynamic effects of the red cell substitute Hemolink™ (o-rafinose cross-linked human hemoglobin) on vital signs in patients undergoing CABG surgery. Anesthesiology 2000;93:A-180.
75. LaMuraglia GM, O'Hara PJ, Baker WH, Naslund TC, Norris EJ, Li J, Vandermeersch E. The reduction of the allogenic transfusion requirement in aortic surgery with a hemoglobin-based solution. J Vasc Surg 2000;31:299–308.
76. Schubert A, Mascha E, O'Hara JF. Synthetic hemoglobin reduces perioperative blood transfusions in vascular, orthopedic and abdominal surgery. Anesthesiology 2000;93:180.
77. Lamy ML, Daily EK, Brichant JF, Larbuisson RP, Demeyere RH, Vandermeersch EA, Lehot JJ, Parsloe MR, Berridge JC, Sinclair CJ, Baron JF, Przybelski RJ. Randomized trial of diaspirin cross-linked hemoglobin solution as an alternative to blood transfusion after cardiac surgery. The DCLHB cardiac surgery trial collaborative group. Anesthesiology 2000;92:646–656.
78. Carmichael FJ, Ali AC, Campbell JA, Langlois SF, Biro GP, Willan AR, Pierce CH, Greenburg AG. A phase I study of oxidized raffinose cross-linked human hemoglobin. Crit Care Med 2000;28:2283–2292.
79. Patel RP. Biochemical aspects of the reaction of hemoglobin and no: implications for hb-based blood substitutes. Free Rad Biol Med 2000;28:1518–1525.
80. Kim HW, Greenberg AG. Ferrous sulphate scavenging of endothelium derived nitric oxide is a principal mechanism for hemoglobin mediated vasoactivities in isolated rat thoracic aorta. Artf Cells, Blood Sub Immobil Biotechnol 1997;25:121–133.
81. Su D, Roth RI, Levin J. Hemoglobin infusion augments the tumor necrosis factor response to bacterial endotoxin (lipopolysaccharide) in mice. Crit Care Med 1999;27:771–778.
82. Freilich E, Freilich D, Hacker M, Leach L, Patel S, Hebert J. The hemodynamic effects of diaspirin cross-linked hemoglobin in dopamine-resistant endotoxic shock in swine. Art Cells, Blood Sub Immobiliz Biotechnol 2002;30:83–98.
83. Zimmerman JJ. Deciphering the dark side of free hemoglobin in sepsis. Crit Care Med 1999;27:685–686.
84. Winslow RM. Current status of blood substitute research: towards a new paradigm. J Intern Med 2003;253:508–517.
85. Kramer GC. Counterintuitive red blood cell substitute–polyethylene glycol-modified human hemoglobin. Crit Care Med 2003;31:1882–1884.
86. Wettstein R, Tsai AG, Erni D, Winslow RM, Intaglietta M. Resuscitation with polyethylene glycol-modified human hemoglobin improves microcirculatory blood flow and tissue oxygenation after hemorrhagic shock in awake hamsters. Crit Care Med 2003;31:1824–1830.
87. Slanetz PJ, Lee R, Page R, Jacobs EE Jr, LaRaia PJ, Vlahakes GJ. Hemoglobin blood substitutes in extended preoperative autologous blood donation: an experimental study. Surgery 1994;115:246–254.
88. Lee R, Neya K, Svizzero TA, Vlahakes GJ. Limitations of the efficacy of hemoglobin-based oxygen-carrying solutions. J Appl Physiol 1995;79:236–242.
89. Vlahakes GJ. Hemoglobin solutions come of age. Anesthesiology 2000;92:637–638.
90. Levy JH. Hemoglobin-based oxygen-carrying solutions: close but still so far. Anesthesiology 2000;92:639–641.
91. Hughes GS Jr, Francome SF, Antal EJ, Adams WJ, Locker PK, Yancey EP, Jacobs EE Jr. Hematologic effects of a novel hemoglobin-based oxygen carrier in normal male and female subjects. J Lab Clin Med 1995;126:444–451.
92. Schumacher YO, Ashenden M. Doping with artificial oxygen carriers: an update. Sports Med 2004;34:141–150.
93. Levy JH, Goodnough LT, Greilich PE, Parr GV, Stewart RW, Gratz I, Wahr J, Williams J, Comunale ME, Doblar D, Silvay G, Cohen M, Jahr JS, Vlahakes GJ. Polymerized bovine hemoglobin solution as a replacement for allogeneic red blood cell transfusion after cardiac surgery:

results of a randomized, double-blind trial. J Thor Cardiovas Sur 2002;124:35–42.

94. Gonzalez P, Hackney AC, Jones S, Strayhorn D, Hoffman EB, Hughes G, Jacobs EE, Orringer EP. A phase I/II study of polymerized bovine hemoglobin in adult patients with sickle cell disease not in crisis at the time of study. J Investig Med 1997;45:258–264.
95. Feola M, Simoni J, Angelillo R, Luhruma Z, Kabakele M, Manzombi M, Kaluila M. Clinical trial of a hemoglobin based blood substitute in patients with sickle cell anemia. Surg Gynecol Obs 1992;174:379–386.
96. Mullon J, Giacoppe G, Clagett C, McCune D, Dillard T. Transfusions of polymerized bovine hemoglobin in a patient with severe autoimmune hemolytic anemia. N Engl J Med 2000;342:1638–1643.
97. Sloan EP. The clinical trials of diaspirin cross-linked hemoglobin (DCLHB) in severe traumatic hemorrhagic shock: the tale of two continents. Int Care Med 2003;29: 347–349.
98. Gould SA, Moore EE, Hoyt DB, Ness PM, Norris EJ, Carson JL, Hides GA, Freeman IH, DeWoskin R, Moss GS. The life-sustaining capacity of human polymerized hemoglobin when red cells might be unavailable. J Am Coll Surg 195: 445–452; discussion 2002; 452–455.
99. Lieberthal W, Fuhro R, Freedman JE, Toolan G, Loscalzo J, Valeri CR. O-raffinose cross-linking markedly reduces systemic and renal vasoconstrictor effects of unmodified human hemoglobin. J Pharmacol Exper Therap 1999;288:1278–1287.
100. Cheng DC, Mazer CD, Martineau R, Ralph-Edwards A, Karski J, Robblee J, Finegan B, Hall RI, Latimer R, Vuylsteke A. A phase ii dose-response study of hemoglobin raffimer (Hemolink) in elective coronary artery bypass surgery. J Thor Cardiov Sur 2004;127:79–86.
101. Greenburg AG, Kim HW, Hemolink Study Group. Use of an oxygen therapeutic as an adjunct to intraoperative autologous donation to reduce transfusion requirements in patients undergoing coronary artery bypass graft surgery. J Am Coll Surg 198:373–383; discussion 2004; 384–385.
102. Conover CD, Lejeune L, Shum K, Gilbert C, Shorr RG. Physiological effect of polyethylene glycol conjugation on stroma-free bovine hemoglobin in the conscious dog after partial exchange transfusion. Artif Organs 1997;21:369–378.
103. Teicher BA, Ara G, Herbst R, Takeuchi H, Keyes S, Northey D. Peg-hemoglobin: effects on tumor oxygenation and response to chemotherapy. In Vivo 1997;11:301–311.
104. Linberg R, Conover CD, Shum KL, Shorr RG. Increased tissue oxygenation and enhanced radiation sensitivity of solid tumors in rodents following polyethylene glycol conjugated bovine hemoglobin administration. In Vivo 1998;12: 167–173.
105. Serna DL, Powell LL, Kahwaji C, Wallace WC, West J, Cogert G, Smulowitz P, Steward E, Purdy RE, Milliken JC. Cardiac function after eight hour storage by using polyethylene glycol hemoglobin versus crystalloid perfusion. ASAIO J 2000;46:547–552.
106. Meng FT, Zhang WZ, Ma GH, Su ZG. The preparation and characterization of monomethoxypoly(ethylene glycol)-*b*-poly-*dl*-lactide microcapsules containing bovine hemoglobin. Artf Cells, Blood Sub Immobil Biotechnol 2003;31:279–292.
107. Phillips WT, Klipper RW, Awasthi VD, Rudolph AS, Cliff R, Kwasiborski V, Goins BA. Polyethylene glycol-modified liposome-encapsulated hemoglobin: a long circulating red cell substitute. J Pharmacol Exp Ther 1999;288:665–670.

See also BIOCOMPATIBILITY OF MATERIALS; BLOOD COLLECTION AND PROCESSING; BLOOD GAS MEASUREMENTS.

BONDING, ENAMEL. See RESIN-BASED COMPOSITES.

BONE AND TEETH, PROPERTIES OF

RODERIC LAKES
University of Wisconsin
Madison, Wisconsin

J. LAWRENCE KATZ
University of Missouri
Kansas City, Missouri

INTRODUCTION

Bone has a variety of functions in the body of which some of the most important are structural in nature: protection of vulnerable body parts, support of the body, and to provide muscle attachments. A knowledge of the mechanical and adaptive properties of bone is useful in the design and use of prostheses that replace a bone or a portion of a bone. Mechanical properties of bone are also of interest in trauma biomechanics and in efforts to prevent injury to the body. As for teeth, they also are replaced by artificial materials which are called upon to perform the mechanical functions of the original tooth. This article contains a survey of known properties of bone and teeth and their components collagen and apatite, with an emphasis on bone and its mechanical properties.

A voluminous literature is available dealing with the properties of bone and to a lesser extent of teeth's major constituents: collagen and apatite. Reported properties are often found to differ. Some of the differences arise from the fact that bone and tooth structures are of biological origin and consequently vary depending on the individual and on the part of the body from which the specimen is taken. Other differences are due to experimental technique and variations in environmental conditions during experiments. Of necessity, results presented in this article are selected from a large mass of published reports. The authors have endeavored to select results obtained by good techniques and representative of accepted values. Nevertheless, other results obtained by equally good techniques may be expected to differ somewhat as a result of biological variability. Therefore, it is suggested that additional measurements of the properties of bone and teeth can be found in several of the source books listed in the Bibliography [see (1–10)].

MECHANICAL PROPERTIES OF COMPACT BONE

Compact Bone Structure

The mechanical properties of bone are inseparably related to its structure. Bone tissue is a complex composite material that at different levels of scale exhibits fibrous, porous, and particulate microstructural features (1–5). The following constituents are present in bone: mineral, protein, other organic materials, and fluids such as water. The mineral, principally a carbonated apatite, where the carbonate group substitutes in part for the phosphate group [$Ca_{10}(PO_4,CO_3)_6(OH)_2$] (5,6). In mature bovine cortical bone (similar to human cortical bone) it occurs as microcrystalline inclusions of plate-like shape (mineralites) of dimensions $\sim 0.7 \times 11 \times 17$ nm (11). However, in young postnatal bovine bone, the mineralites are thicker, shorter, and narrower, [i.e. $2 \times 6 \times 9$ nm (12)]. These mineralite sizes measured by AFM are closest to the actual values as, "AFM yields the full three-dimensional structure of mineralites rather than a projection $\cdots$" thus providing the full shape of each mineralite measured. The other major techniques for measuring mineralite sizes, transmission electron microscopy (TEM) and X-ray diffraction line broadening, each suffer from artifacts that result in increased sizes of some of the dimensions (3).

On the ultrastructural level (nanoscale), the mineral crystallites are in intimate apposition with fibrils of the protein collagen. A, "(d)iagrammatic depiction of the supramolecular packing of collagen molecules in a fibril $\cdots$" plus the possible arrangement of the mineralites within a fibril is given as Fig. 7 in Ref. 12. These fibrils are from 20 to 200 nm in diameter and are organized into fibers that are in turn arranged in bone into lamellae or layers. The fibers in each lamella run longitudinally, spirally, or nearly circumferentially. Moreover, the orientation of these layers are different in alternate lamellae. A micromechanical model for the Young's modulus of bone has been proposed, based on these histological features, however, it has not yet been tested experimentally. The organization of collagen fibrils differs in woven bone and lamellar bone. Mineralized collagen fibrils and isolated crystals from the mid-diaphyses of human fetal femurs were observed with scanning, TEM, and high resolution electron microscopy. The apatite crystals in woven bone are also platelet shaped, similar to mature crystals from lamellar bone. Average crystal dimensions are considerably smaller in woven bone than those of mature crystals in lamellar bone. In diseased bone such as that affected by osteogenesis imperfecta, the apatitic crystals occur in various sizes and shapes; they are oriented and aligned with respect to collagen in a manner that differs from that found in normal calcified tissues.

In compact cortical bone, the lamellae are layers arranged circumferentially around a central canal and form the Haversian system (secondary osteon). Haversian canals typically contain small blood vessels. Haversian bone occurs in the cortices of bones in adult humans (1–3,5) and in the bones of various large animals (1,2). Osteons are roughly cylindrical structures up to $\sim$ 200 μm in diameter. In a long bone, they tend to run approximately parallel to each other and to the bone axis. Figure 1 displays the typical structure of human cortical bone, whereas Fig. 2 displays the typical structure of human cancellous (also known as trabecular or spongy) bone. The large circular or elliptical features in the former figure are the cross-sections of osteons, the concentric layers are lamellae, and the central dark circles are the cross-sections of Haversian canals. The numerous spots among the lamellae are the lacunae, in which the osteocytes, or bone cells live. The lacunae are roughly ellipsoidal and have dimensions of $\sim 10 \times 15 \times 25$ μm. The osteocytes have many thin processes that occupy channels in the bone matrix known as canaliculi; they are too small to be visible in Fig. 1. The mechanical properties of bone depend on its degree of bulk and surface hydration and the details of its structure that depend on variables such as the age, state of health, and level of physical activity of the individual, the location of the bone in the body, as well as the rate and direction at which load is applied to the bone.



Figure 1. Human Haversian bone. Reflected light micrograph of a specimen cut perpendicular to the bone axis. Scale mark: 200 μm.

The emphasis in this article is on wet skeletal tissues, bone and teeth, from healthy adults, with occasional references to dry tissues for comparison. However, there are many studies of mammalian skeletal tissues as they provide a useful counterpart to the human studies; studies of the properties of bovine bone and teeth are the most numerous in this respect. The structures of both mature bovine cortical and cancellous bone are very similar to those corresponding human tissues Figs. 1 and 2, respectively. Young bovine cortical bone structure is quite different as seen in Fig. 3. This plexiform (or lamellar) bone resorbs and remodels to Haversian bone as the animal matures. Comparison of the young and mature bovine bone properties provides added insight into the importance of structure in determining the mechanical properties of bone. Thus, where appropriate, properties of bovine bone and teeth are included in Tables 1–7.



Figure 2. Human cancellous bone from the proximal femur. The marrow has been removed. Scale mark: 5 mm.



Figure 3. Bovine plexiform bone. Reflected light micrograph of a specimen cut perpendicular to the bone axis. Scale mark: 200 μm.

Elasticity of Compact Bone: Comparison with Teeth and Other Materials

Elastic materials deform under load; elasticity entails reversible behavior in which the material returns to its original configuration after the load is removed. If the load is sufficiently small, there is a linear relationship between stress and strain. For simple tension or compression, the constant of proportionality is referred to as Young's modulus E and for shear or torsion it is the shear modulus G(4,29). The stiffness of human compact bone as quantified by Young's modulus typically lies between 12 and 25 GPa for tension or compression depending on sample orientation and experimental technique (17), (1 GPa = 145,000 lb·in.$^{-2}$). It has been suggested that the tensile and compressive elastic moduli are not equal, but at small strain, the best evidence indicates that tensile and compressive properties are identical (13).

In Table 1, some examples of the elastic moduli of wet human bone and teeth are compared with those of various other materials. The mechanical testing strain rates for bone are faster than those encountered by bones in walking, but are perhaps comparable to those in vigorous activities. They are slower than those that occur during fracture. Compact bone is ~ 10 times stiffer than most "rigid" polymers, but is about one-tenth as stiff as common metals such as steel. Table 1 also shows the relationship between stiffness and density. This relationship governs the structural efficiency of whole bones. In view of the fact that the skeleton represents ~ 17% of the weight of the human body, structural efficiency of bones is relevant to their performance in the body. For example, the overall rigidity per unit weight of a bone acting as a short column or as a tensile member is proportional to the modulus to density ratio, E/ρ, of the bone *tissue* of which it is made. By contrast, for a given weight of material, the Euler buckling load of a bone acting as a slender column or the bending stiffness of a bone acting as a beam of constant shape is proportional to E/ρ^2(2,6). Density enters these relations in a different way since the rigidity of a short column depends on its cross-sectional area while the bending rigidity of a beam is governed by its moment of inertia.

A more complete listing of the properties of both human and bovine bone and teeth is given in Table 2, the latter data are included because of the similarity in hierarchical structure and organization of mature bovine compact bone with that of human compact bone. These data were obtained using various techniques, mechanical testing, ultrasonic wave propagation (UWP). In the low megahertz (MHz) region (2–5 MHz), scanning acoustic microscopy (SAM) in the high megahertz region (400–600 MHz), and nanoindentation. The first three techniques also were used to obtain the teeth data. Here too, the properties are strongly dependent on the sample location and orientation, for example, the range in dentin properties over the sample surface obtained by SAM (21), Table 2. Corresponding properties of human trabecular bone volumes and individual trabeculae are given in Table 7.

Because SAM is not as well documented compared to either UWP or mechanical testing (MT) in obtaining elastic properties, a description of the technique follows below.

Scanning Acoustic Microscopy

The development of SAM (30,31); see also (9) enabled the analysis of the biomechanical properties of materials at much higher resolution than was previously achieved using traditional ultrasonic wave propagation techniques.

Table 1. Bone, Teeth, and Other Materials: Stiffness

Material	Young's Modulus E, GPa	Density (ρ), g·cm^{-3}	E/ρ	E/ρ^2
Human compact bone				
longitudinal direction (13)	17	1.8	9.4	5.2
transverse direction	12.5			
Tooth dentin (7,14)	18	2.1	8.6	4.1
Tooth enamel (7,15)	50	2.9	17	6.0
Polyethylene (high density) (4)	0.5	0.95	0.53	0.55
Polymethyl methacrylate (4)	3.0	1.2	2.5	2.2
Steel(structural)	200	7.9	25	3.2
Aluminum	70	2.7	26	9.5
Granite	70	2.8	25	9.1
Concrete	25	2.3	11	4.6
Wood(pine)	11	0.6	18	30

Table 2. Elastic Properties of Wet Human and Bovine Bone and Teeth

Material	Young's Modulus, GPa	References
Human compact bone		
axial direction (femur)	27.7 (U)[a]	16
	17.6 (M)[a]	17
	23.4 (S)[a]	18
(osteons)	22.4 (N)[a]	19
(interstitial lamellae)	25.7 (N)	19
radial direction (femur)	18.9 (U)	16
	12.5 (M)	17
	13.0 (N)	19
Human teeth		
dentin	13.0 (S)	20
	16.4–38.6 (S)	21
enamel	62.7 (S)	20
Bovine compact bone		
axial direction (tibia)	36.0 (M)	2
axial direction (femur)	22.7 (M)	17
axial direction (femur)	21.9 (U)	22
radial direction (tibia)	22.8 (M)	2
radial direction (femur)	10.3 (M)	17
radial direction (femur, average)	13.1 (U)	22
Bovine teeth		
dentin	26.3 (U)	23,24
dentin	25.2 (U)[b]	25
enamel	105.1 (U)	23,24
enamel	97.8 (U)[b]	25

[a] U = Ultrasonics; M = Mechanical Testing; S = Scanning Acoustic Microscopy; N = Nanoindentation.

[b] Average of measurements of several samples.

Table 5. Comparison of Materials: Tensile Strength

Material	Strength σ_{ult}, MPa	Density ρ, $g \cdot cm^{-3}$	σ_{ult}/ρ
Human femoral compact bone (17),			
longitudinal direction	148	2.0	74
transverse direction	49	2.0	25
Bovine femoral plexiform bone, (13)			
longitudinal direction	167	2.0	83
Tooth dentin (8), average	271	2.1	130
Tooth enamel (8), average	275	2.9	95
Polyethylene (high density)	20–40	0.95	21–42
Poly(methyl methacrylate) (PMMA)	70	1.2	59
Steel(structural)	400	7.8	51
Aluminum(1100-H14)	110	2.7	41
Granite	20	2.8	7.2
Concrete(compression)	28	2.3	12

A significant advantage of SAM is the ability to investigate the properties of internal and subsurface structures in addition to the surface properties of most materials, including those that are optically opaque. Another advantage of special interest for studying biological materials is that a liquid couplant must be used to transmit the acoustic waves from the acoustic lens to the specimen being studied, thus the specimen is kept wet during all measurements. Therefore, fresh tissue specimens can be used as well as embedded specimens. In addition, the use of high quality,

Table 3. Elastic Anisotropy of Bovine and Human Bone

	Tensorial Elastic Moduli (GPa), Determined Ultrasonically Wet Bovine Femur (26)		Dry Human Femur (27)
Elastic constant	Haversian (transverse isotropic)	Plexiform (orthotropic)	Haversian (transverse isotropic)
C_{11}	21.2	22.4	23.4
C_{22}	21.0	25.0	
C_{33}	29.0	35.0	32.5
C_{44}	6.30	8.20	8.71
C_{55}	6.30	7.10	
C_{66}	5.40	6.10	
C_{12}	11.7	14.0	9.06
C_{13}	12.7	15.8	
C_{23}	11.1	13.6	9.11

Table 4. Elastic Anisotropy of Bone[a]

Young's Moduli, GPa		Shear Moduli, GPa		Poisson's Ratios, Dimensionless	
Human	Bovine	Human	Bovine	Human	Bovine
$E = 17.0$[b]	22	$G = 3.6$	5.3	$v = 0.58$	0.30
$E = 11.5$[c]	15	$G = 3.3$	6.3	$v = 0.31$	0.11
$E = 11.5$[d]	12	$G = 3.3$	7.0	$v = 0.31$	0.21

[a] Technical elastic moduli. Wet human femoral bone by mechanical testing (13) and bovine femoral bone by ultrasound (23).

[b] Radial direction.

[c] Circumferential direction.

[d] Longitudinal direction.

Table 6. Elastic Properties of Apatites

Material	Young's modulus, GPa	Bulk modulus, GPa	Shear modulus, GPa	Reference
Hydroxyapatite				
(polycrystalline)	117	88.0	45.5	27
(single crystal, modeling[a])	120	111	45.3	8
Fluoroapatite				
(polycrystalline)	120	94.0	46.4	27
(single crystal, ultrasonics[a])	130	117	49.4	28
Chloroapatite				
(polycrystalline)	94.3	68.5	37.1	27

[a] Calculated from single-crystal elastic constants.

high frequency focusing acoustic lenses permits examination of the elastic properties of biological materials on a microscope scale comparable to the optical histology studies. The heart of the SAM is a spherical lens formed at the interface between a high acoustic velocity solid (e.g., sapphire) and the low acoustic velocity couplant liquid. Due to the high acoustic "refractive index", spherical aberration is negligible and an acoustic beam displaying significant convergence can be obtained. A radio frequency (RF) signal is generated from the transmitter. The acoustic lens is equipped with a piezoelectric transducer that converts the RF signal into an acoustic wave. This signal is then made to converge by the lens and propagates to the specimen through the coupling liquid. When reaching the surface of the specimen, a part of the acoustic wave is reflected back through the lens to the transducer, that, acting now as a receiver, transforms the acoustic signal into an RF signal. The amplitude of the echo reflected back to the lens is a measure of the acoustic reflectivity of the surface of the investigated material at the point in focus. It is proportional to the reflection coefficient, r, which is related to the acoustic impedances of the liquid couplant, Z_1, and the investigated material, Z_2, by the equation r given in Fig. 4. Acoustic impedance, Z, is measured in Rayls and is defined as $Z = \rho v$, where ρ is the material density and v is the velocity of the longitudinal (dilatational) acoustic wave propagating in the direction perpendicular to the surface. The images present the variations in acoustic signals that originate either from the intrinsic acoustic reflectivity of the material surface or through interference occurring between different surface and subsurface reflected signals. In the former case, surface imaging, the acoustic reflectivity variations are a result of the local changes in acoustic impedance (32).

Table 7. Elastic Modulus of Trabecular Bone Volumes and Trabeculae

Trabeculae	Elastic Modulus, GPa	Reference
Human trabecular bone (Trabeculae)	17.4 (S)	18
(longitudinal)	19.4 (N)	19
(transverse)	15.0 (N)	19
Human trabecular bone volumes		
(proximal tibia)	0.445 (M)	3

Figure 5 is a plot of elastic stiffness (GPa) versus reflection coefficient, r, for a wide range of materials. Bone has an acoustic impedance in the neighborhood of $Z = 7.5$ Mrayls, yielding a reflection coefficient in the neighborhood of $r = 0.67$. Of course, Z for bone can vary over a considerable range depending on a number of factors that would affect both the density and structural cohesivity of the specific specimen being measured. Likewise, Z for water will vary depending on the temperature at which the couplant fluid is maintained during the experiment, for example, at 0 °C, $Z(H_2O) = 1.40$ Mrayl; at body temperature, 37 °C, $Z(H_2O) = 1.51$ Mrayl; and at 60 °C, $Z(H_2O) = 1.53$, due mainly to the variations in water's acoustic properties with temperature.

As described above, the high frequency mode at 400 and 600 MHz also has been used to study the *in vitro* micromechanical elastic properties of human trabecular and



Figure 4. Schematic diagram of the incident, reflected, and transmitted signals at the interface between two materials.



Figure 5. Reflection coefficient, r versus Modulus, E.

(a)



400 MHz (120° aperture burst mode) SAM micrograph of a portion of human femoral cortical bone cut transverse to the bone axis. (full scale x dimension is 0.5 μm). The two center haversian systems show darker grey levels than the approximately more mature neighboring systems as indicated by their much lighter shades of gray. Resolution is ~ 2.5 mm.

(b)



Same figure as above showing line along which the *x–z* curve was taken passing through the darker haversian system and lighter ones on either side.

(c)



x–z SAM image taken along the line drawn on the above figure (full scale x dimension is 0.5 mm; full scale z dimension is 150 μm) The level appearance of the top of the band shows the sample was flat and well aligned perpendicular to the axis of the lens. The broadening of the left 25% and the right 50% of the white band reflects the presence of the more mature haversian systems next to the immature system.

Figure 6. (a) The 400 MHz SAM image of two hypomineralized osteons from human femoral cortical bone. (b) Same area as in part a showing the line along which an *x–z* interference image was taken. (c) The *x–z* Interference image taken along the line shown in part b.

compact cortical femoral bone (15,31). In this study, they were able to image the properties of the individual osteonic lamellae at high enough resolution so that three new micromechanical observations were made: (*1*) the outermost lamellae, always appear to be more compliant; (*2*) the outermost lamellae of adjacent abutting osteons appear to have the same acoustic impedance (and thus Young's modulus), even though structurally distinct; and (*3*) adjacent lamellae within an osteon alternate in their acoustic impedance (and thus Young's modulus).

Scanning acoustic microscopy is particularly powerful in providing physical evidence of the possible differences in sound velocity in regions of significant differences in gray level, that is, the darker the gray level, the lower the acoustic impedance, the brighter the gray level, the higher the acoustic impedance, Fig. 6a–c. Figure 6a is a SAM micrograph (400 MHz Burst mode, 120° aperture lens) of human femoral cortical bone (18). The two much darker Haversian systems in the middle of the image are surrounded by the types of Haversian systems (secondary osteons) usually observed in normal bone. The startling difference in gray levels could arise due to out-of-focus artifacts developed in cutting or polishing the specimen. However, performing a *x–z* curve along the line depicted in Fig. 6b, which goes through the lower, darker Haversian system and the surrounding tissues, yields the image, Fig. 6c; note that the upper level of the broad band is essentially level, indicating that the specimen surface is everywhere level and normal to the acoustic beam. More important, the narrow band and secondary reflection corresponding to the dark Haversian reflects the lower Z and r for the Haversian. A possible explanation for the Haversians is that there was an arrested state of development leading possibly to a hypomineralized area. Unfortunately, we do not have information concerning the possibility of a disease state or a drug modality responsible for these two underdeveloped Haversians that possibly formed just prior to the death of the individual. They are illustrated here to show the ability of the SAM to permit highly sensitive measurements, at high resolution, of variations in Z and r due to remodeling.

In order to convert from reflection coefficient to Young's modulus on the SAM scans of materials of unknown properties, taken with the Olympus UH3 SAM, it is necessary to develop three calibration curves—voltage (V) versus reflection coefficient (r); reflection coefficient (r) versus acoustic impedance (Z); and acoustic impedance (Z) versus Young's modulus (E)—based on using the values of known materials ranging from polymers at the low end of r to metals and ceramics at the high end (18).

The stiffness of compact bone tissue depends on the bone from which it is taken. Fibular bone has a Young's modulus $\sim$ 18% greater, and tibial bone $\sim$ 7% greater than that of femoral bone (33). The differences are associated with differences in the histology of the bone tissue. Femoral bone, for example, has a high proportion of osteons that appear light in the polarizing microscope and that have a preponderantly circumferential collagen fiber orientation (34). The histology of a bone is unquestionably related to its function in the body. The relationship has been explored in some detail in the context of bones of very different function in various species of animals (1,2).

Bone is elastically anisotropic, that is, its properties depend on direction. Such behavior is unlike that of steel, aluminum, and most plastics, but is similar to that of wood. Anisotropic properties of bone are shown in Tables 3 and 4. As can be seen from the data in Table 4, human compact femoral bone is $\sim$ 1.5 times as stiff in the longitudinal direction as it is in the transverse directions. The shear modulus G, determined from a torsion test upon a specimen aligned with the bone axis, is $\sim$ 3.3 GPa (13), so that $E/G = 5.15$. Such a small value of G in comparison with Young's modulus E is a further manifestation of the anisotropy of cortical bone. For normal isotropic materials (positive Poisson's ratio), E/G, must lie between 2 and 3 and is typically $\sim$ 2.6. Detailed studies of the anisotropy of bone have been conducted using ultrasonic methods as well as by mechanical testing. The elastic constants given in Table 3 are components of the elastic modulus tensor C_{ijkl} in the following relation between stress σ_{ij} and strain e_{kl} in an anisotropic material. The 3 axis is here assumed to be the bone's longitudinal axis, the 2 direction is circumferential, and the 1 direction is radial.

$$\sigma_{ij} = \sum_{k=1}^{3}\sum_{l=1}^{3} C_{ijkl} e_{kl}$$

In this equation, indexes i and j can have values 1, 2, or 3, so that there are nine components of stress of which six are independent. Since there are six independent components of strain, the number of independent C values is reduced from 81 to 36. Consideration of conservation of mechanical energy further reduces the number of elastic constants to 21, for the least symmetric anisotropic material (7). Materials that have some structural symmetry are described by fewer anisotropic elastic constants. For example, an orthotropic material, (e.g., wood), with three perpendicular planes of symmetry is described by nine constants. A material with transverse isotropic symmetry, (i.e., one that appears the same under an arbirary rotation about an axis), is described by five constants. In crystal physics, the former symmetry is referred to as orthotropic, while the latter is referred to as hexagonal. An isotropic material appears the same under any rotation and has the same properties in any direction. Two independent elastic constants are needed for the description of the elastic behavior of such a material. Equation 1 can be reduced to a more tractable form by a compaction of the counting indices, the so-called Einstein notation, that is, $\sigma_i = C_{ij} e_j$, where $11 \rightarrow 1$, $22 \rightarrow 2$, $33 \rightarrow 3$, $23 \rightarrow 4$, $13 \rightarrow 5$, $12 \rightarrow 6$ (e.g., $C_{1123} \rightarrow C_{14}$). This reduced notation is used in Table 3.

Both structural considerations and experiments indicate that human compact bone has five independent elastic constants and therefore exhibits transverse isotropic symmetry (27,35,36). Results of a different ultrasonic experiment suggest different stiffnesses in the radial and circumferential directions (16). Based on these results, it has been proposed that human compact bone is orthotropic. The difference between the stiffnesses in the radial and circumferential direction is, however, small and has been attributed to the gradient in porosity going from the periostium to the endostium. Thus, for modeling purposes transverse isotropy is the appropriate choice of symmetry (37,38).

Note that the elastic moduli found at high frequencies by ultrasonic methods are greater than those obtained statically or at low frequencies via mechanical testing machines. This is a result of the rate dependence (viscoelasticity) of bone. In the mechanics of whole bones, the principal macroscopic manifestation of cortical bone tissue anisotropy is that the bending rigidity of a bone (the femur) is much greater than its torsion rigidity (39). The degree of anisotropy and the symmetry of bone tissue depends on the species and on the location of the bone in the body. Bovine plexiform bone is stiffer than human Haversian bone, but dry bone is stiffer than the same type of bone when wet. Bovine plexiform bone is orthotropic and has significantly different elastic moduli in the longitudinal, radial, and circumferential directions (40). These properties reflect the laminar architecture of this type of bone, as shown in cross-section in Fig. 2. The scale mark is in the radial direction and is perpendicular to the laminae. Bovine plexiform bone is a type of primary bone that occurs in relativley young cattle. It is often used for experiments as a result of its availability. Canine femoral bone is also orthotropic (16), however, canine mandibular bone and possibly also human mandibular bone, is transversely isotropic (41).

Anisotropic properties of bone may also be expressed in terms of the technical elastic constants, Young's modulus E, shear modulus G, and Poisson's ratio, v, for different directions. Poisson's ratio is minus the transverse strain divided by the axial strain in the direction of stretching or of compressing force. Representative values for dry human femoral bone are shown in Table 3. The 3 direction is the long axis of the bone, the 2 direction is circumferential, and the 1 direction is radial. We note that Poisson's ratio in isotropic materials must be less than one-half (7). In anisotropic materials, larger values are permissible, so that the values reported for bone do not violate any physical law.

Bone mineral density plays an important role in determining all of the elastic properties described above. Under normal physiological and physical conditions, as bone density increases so do the respective elastic properties. However, bone density alone does not always determine fracture risk in pathologies such as osteporosis. A general term in vogue now, 'bone quality', is being used to qualify what is information is necessary to determine when bone is at risk of failure due to reduced density. Structure–property relationships are the key here, especially in understanding when trabecular bone will fail. Even under the conditions of reduced density, the approppriate structural organization of the bone may still provide adequate support during normal function. Similarly, good density alone, if associated with a genetic pathology, such as found in osteopetrosis, will not provide adequate prrotection against fracture. The hardness and elastic moduli of osteopetrotic cortical bone are even well below that of osteoporotic bone even though the density of the former is in the normal range (26,42). Indeed, osteopetrotic bone tends to fracture quite readily.

It is clear that for a detailed modeling of the elastic properties of bone, its complex hierarchical structure must be taken into account (37,38,43).

Strength

The ultimate strength of bone tissue refers to the maximum stress the material can withstand before breaking. The tensile strength of human compact bone (17) in a direction parallel to the osteons is about 150 MPa or 21,000 $\text{lb} \cdot \text{in.}^{-2}$ ($1\ \text{MPa} = 145\ \text{lb} \cdot \text{in.}^{-2}$). As indicated in Table 5, bone is stronger than various plastics, concrete, brick, some metals, (e.g., aluminum), and most woods. Although bone is stronger than aluminum, commonly used aluminum alloys are stronger than bone. Even so, bone has a lower density than aluminum and a much lower density than steel. The criterion for structural strength in beam bending is material strength divided by the 1.5 power of density [3.×]. For bending of plate-shaped structural elements the criterion is material strength divided by the square of the density. The strength to density ratio for bone is greater than that for structural steel. Therefore bone has very favorable properties in comparison with steel and is competitive with aluminum alloys. Bone is anisotropic in its strength as well as in its elastic behavior. In particular, bone is considerably weaker when loaded transversely than when loaded along the osteon direction. Fortunately, bone in the body does not normally experience significant transverse loads. Several investigators have explored the dependence of bone strength upon age. Tensile strength of adult compact bone decreases 4% per decade of age (44) as does its shear strength (45). In other studies, no significant age dependence of strength was found (46,47). More recently, it was found that the tensile strength of femoral bone decreases 2.1% per decade of age while that of tibial bone decreases 1.2% per decade of age (48). The decrease in strength was statistically significant in the case of femoral bone, but not in the case of tibial bone. Both kinds of bone exhibit significant decreases, 6.8% per decade for femur and 8.4% per decade for tibia, in energy absorption to fracture, a measure of toughness. No significant difference between age-matched males and females was found for any mechanical property (48). Tibial bone is stronger in tension than femoral bone by $\sim$ 19% (49,50) and is $\sim$ 4% stronger than fibular bone.

Currey observes that the average stiffness of human and sheep bone increases monotonically with age (in humans from age 2–50), while energy absorption to fracture decreases. The lower mineralization and stiffness and higher toughness seen in young bones is considered adaptive in view of the many falls and bumps experienced by children and young animals (1).

The fracture behavior of a material is not described fully by its yield and ultimate strengths alone; toughness is also important. Toughness is seen as an important characteristic of bone in view of the microcracks that occur in living bone. Fracture of laboratory specimens containing controlled notches provides information concerning the toughness of materials (49,50). For example, the nominal fracture strength of a tensile specimen with an edge notch of length a is $\sigma_{\text{ult}} = K_{1c} a^{-1/2}/Y$ in which Y depends on the specimen geometry and K_{1c} is called the critical stress intensity factor. A large value of K_{1c} results in high strength even in the presence of a notch; K_{1c} is a measure of material toughness.

The critical stress intensity factor K_{1c} for fracture of compact tension specimens of bovine femur bone is from 2.2 to 4.5 $\text{MN} \cdot \text{m}^{-3/2}$, and the specific surface energy for fracture is from 390 to 560 $\text{J} \cdot \text{m}^{-2}$ (49). The toughness does not, however depend on the sharpness of the controlled notch in the expected way; the significance of this observation is discussed in the section Compact Bone as a Composite Material. As for the age dependence of bone fracture toughness, the energy absorbed to fracture is observed to decrease during childhood and early middle age, and the elastic modulus increases (51). Recently, fracture surfaces from accident victims have been examined microscopically (52). Such surfaces are observed to be much rougher and more intricate than fracture surfaces produced in laboratory specimens of dead bone, which suggests a greater toughness in living bone. The influence of bone viability on its mechanical properties is not well understood. The dependence of bone elastic modulus on viability has been explored in several studies, but the evidence for a difference in elasticity is not compelling.

Currey (1), compares density, modulus, strength and toughness of bones from deer antler, cow thigh, and whale tympanic bulla. As one might expect, modulus increases and toughness decreases with density. Strength is the highest for the femoral bone. Properties vary considerably between these types of bone; the difference is attributed largely to mineralization but partly to histology. The high mineralization of the whale ear bone is responsible for its stiffness, density and brittleness. The stiffness and density are useful given the acoustic function of the ear bone. The brittleness is not a problem since the ear bone is deep within the skull. Conversely, antler is subjected to repeated severe impacts during use, so toughness is beneficial.

Yielding and Plastic Deformation

Wet bone when loaded sufficiently exhibits a yield point, $\sigma_y = 114$ MPa (13). Beyond this critical stress level, the material does not recover upon the release of the load; permanent or plastic deformation has occurred. In bone as in most materials that exhibit yielding, the yield point is approximated by the proportional limit. The proportional limit is the boundary between the linear and nonlinear portions of the stress–strain curve. The mechanism for yield in bone differs from that in metals. In bone, yield occurs as a result of microcracking and other microdamage while in metals, yield results from motion of dislocations. Published reports have not been in agreement as to the amount of plastic deformation in bone. Much of the disagreement has been attributed to the fact that the observed plastic deformation is highly sensitive to the hydration of the bone. Dry specimens or specimens with dried surfaces or dried and rewetted surfaces behave in a much more brittle manner than those which have been kept fully hydrated during preparation and testing. In the latter case (9), the maximum strain at fracture of bone under tension in the longitudinal direction is 0.031. Yielding of bone has considerable relevance to the function of bone in the body since very much mechanical energy can be absorbed in plastic deformation without fracture. In certain injuries, plasticity in bone can result in residual deformation, which is obvious on a clinical radiograph (53).

Bone Strain *In Vivo*

To ascertain the significance of bone elasticity and strength data in connection with the function of bone in the body, it is desirable to know what levels of stress and strain occur in bones during normal activities and under traumatic conditions. It is possible to make inferences from macroscopic measurements of forces acting on the extremities. The validity of such inferences is rendered uncertain by the fact that muscle forces cannot generally be uniquely determined. It has become possible to determine bone strains explicitly in various animals (54) and in humans (55) by directly cementing foil strain gages to bone surfaces (56). In a human volunteer, maximum strain along the tibia axis was $\sim 3.5 \times 10^{-4}$ during normal walking at $1.4\ \mathrm{m \cdot s^{-1}}$ and 8×10^{-4} during running at $2.2\ \mathrm{m \cdot s^{-1}}$. Strains of similar magnitudes have been observed in animals such as sheep (53). The largest strain magnitude observed in the normal activity of an animal was 3.2×10^{-3} in the tibia of a galloping horse (57). In comparison (5), in tension in the longitudinal direction human bone yields at a strain of 6.7×10^{-3} and fractures at a strain of 0.03. The strain levels observed *in vivo* are significant in view of the fatigue properties of bone. Race horses can experience bone strain exceeding 4.8×10^{-3} at maximum effort (58).

Fatigue

Bone, like other materials, accumulates damage when loaded repeatedly and this damage can lead to fracture at a lower stress than the ultimate strength measured using a single load cycle. The results of *in vitro* mechanical fatigue studies on dead bone suggest that bone may accumulate significant fatigue damage during normal daily activity. Biological bone remodelling is concluded to be essential to the long-term structural integrity of the skeletal system (59). It is notable that dead bone, unlike steel, does not exhibit an endurance limit. The endurance limit is defined as a stress below which the material can withstand an unlimited number of cycles of repetitive load without breaking in fatigue. In the absence of an endurance limit, dead bone subjected to the prolonged cyclic load of daily activity must eventually break. Living bone, by contrast, is able to repair microdamage generated during fatigue.

The resistance of human cortical bone to fatigue fracture is more strongly controlled by strain range than stress range. Fatigue strength shows a weak positive correlation with bone density and with bone modulus and a weak negative correlation with porosity (59). Fatigue strength in uniaxial tests is lower than in bending tests. In immature bone (60), bone fatigue resistance for a given strain range decreases with maturation, while the elastic modulus, density, and ash content increase with maturation. Cracking or fracture of bone due to fatigue manifests itself clinically as ‘stress fractures’ that can occur in individuals who suddenly increase their level of physical activity (61). In the case of a person in poor physical condition who sustains a fatigue fracture during military training, it is called a “march fracture”. Laboratory results for fatigue in bone are not inconsistent with clinical experience with fatigue fractures in athletes and military recruits (62). In particular, a recruit may accumulate in 6 weeks of training a load history equivalent to 100–1000 miles of very rigorous exercise, associated with peak bone strains of 0.002 and a maximum strain range of 0.004, which can be sufficient to precipitate a fatigue fracture (62).

Stress Concentrations

It is common practice in orthopedic surgery to drill holes in bones for the placement of screws. Such holes cause the bone to be weaker than an intact bone, so that it may fracture as a result of less trauma than would ordinarily be required (63,64). This phenomenon may be understood in view of the fact that holes in elastic solids are known to cause a concentration of stress in the vicinity of the hole. According to the theory of elasticity, the stress concentration is not dependent on a decrease in the amount of material available to bear the load; it can be severe even for small holes. Laboratory studies of whole bone fracture have disclosed that a 3 mm diameter hole weakens a tibia by 40% in bending and 12% in torsion (65). A 2.8-or a 3.6-mm hole reduces the strength of dog bones (63) under rapidly applied torsion by a factor of 1.6. It is of interest to compare the observed stress concentration with predicted values based on the theory of elasticity. The predicted stress concentration factor for a hole in a field of shearing stress is 4.0 provided that the hole is small compared with the structure as a whole (66). The discrepancy has been attributed to the fact that intact bone already has stress raisers by virtue of its heterogeneous structure and porosity (63). However, in specimens loaded in the linear elastic range, well below yield or fracture, distributions and concentrations of strain differ from predicted values (67). Similar discrepancies have been reported in manmade fibrous composites without preexisting porosity (68,69). The role of the fibrous architecture of bone in relation to stress concentrations is discussed in the section on composite properties of bone.

Viscoelasticity

Bone exhibits viscoelastic behavior, that is, the stress depends not only on the strain, but also on the time history of the strain. Such behavior can manifest itself as creep, which is a gradual increase in strain under constant stress; stress relaxation, which is a gradual decrease in stress in a specimen held at constant strain; load-rate dependence of the stiffness; attenuation of sonic or ultrasonic waves; or energy dissipation in bone loaded dynamically (10).

Experimental modalities based on each of the above phenomena have been used in the study of bone (70–74). The results have been converted to a common representation via the interrelationships inherent in the linear theory of viscoelasticity, to permit a direct comparison of results (75,76). In the case of tension–compression, there is very significant disagreement among the published results. This disagreement may result from nonlinear viscoelastic behavior not accounted for in the transformation process, or from experimental artifacts. In the case of shear deformation, however, there is good agreement between results obtained in different kinds of experiments. The loss tangent, which is proportional to the ratio of energy dissipated to energy stored in a cycle of deformation, achieves a minimum value of $\sim$ 0.01 at frequencies from 1 to 100 Hz. At lower and higher frequencies, the loss tangent, hence the magnitude of viscoelastic effects is greater (e.g., 0.08 at 1 MHz and at 1 μHz). To compare, the loss tangent of quartz may be $< 10^{-6}$, in metals, from 10^{-4} to 0.01, in hard plastics from 0.01 to 0.1, and in soft polymers, it may attain values > 1. It is notable that the minimum energy dissipation in bone occurs in a frequency range characteristic of load histories during normal activities.

A synopsis of wet bone viscoelastic behavior in shear is presented in Fig. 7. The tan δ attains a broad minimum over the frequency range associated with most bodily activities. Some authors have suggested that the viscoelastic behavior in bone confers a shock- absorbing role. The observed minimum in damping at frequencies of normal activities is not supportive of such an interpretation.

Some authors refer to three element spring dashpot models used in tutorials on viscoelasticity. The behavior of such a model corresponds to a Debye peak in tan δ, also shown in the figure. This corresponds, by Fourier transformation, to a single exponential in the creep or relaxation behavior. The tan δ of bone occupies a much larger region of the frequency domain than a Debye peak, so the spring dashpot model is not appropriate.

Compact Bone as a Composite Material

Early composite models (83–87) for bone were two-phase models involving the mineral and protein phases only. At the ultrastructural level one may imagine the mineral crystals as a particulate reinforcing phase and the surrounding collagen as a matrix phase. Strong arguments were presented that bone cannot be described simply as a compound bar or as a material similar to prestressed concrete. Based on measured Young's moduli of 114 GPa for hydroxyapatite (24) and 1.2 GPa for collagen derived from tendon (83), rigorous upper and lower bounds on the elastic modulus of compact bone were calculated (85,86). Young's modulus of bone lay between these bounds and was less than the value obtained by a simple rule of mixtures approach. Similar comparisons were made for other natural collagen-apatite composites such as dentin and enamel from human teeth.

The wide disparity in the upper and lower bounds in this approach limited its applicability. Later, a composite model of the elastic properties of cortical bone was attempted in order to explain the angular dependence of the elastic properties of both wet and dried bovine cortical bone as determined in an ultrasonic wave propagation experiment (87). However, this modeling failed due to the much stronger decay in the angular dependence of the elastic modulus calculated than was found experimentally. Both this



Figure 7. Viscoelastic behavior of wet compact bone in shear. Comparison of results of various authors, adapted from (3). Low frequency tan δ inferred from slope of long-term creep by Park and Lakes, 1986 (77), center circles, ⊙. Results calculated from integration of constitutive equation of Sasaki et al. 1993 (78) for torsion relaxation in bovine bone (slant squares, □). Damping adapted from data of Lakes et al., 1979 (75) for wet human tibial bone at 37°C (Calculated from relaxation, circles, ○; directly measured, ▲). Direct tan δ measurements by Garner et al., 2000 (79) for wet human bone in torsion, diamonds, →. Damping data of Thompson, 1971 (80) for whole dog radius at acoustic frequencies (diamonds, □). Damping of wet human femoral bone by Lakes, 1982 (81) via a piezoelectric ultrasonic oscillator (cross, +). Damping at ultrasonic frequency for canine bone by Adler and Cook (1975) (82) at room temperature (open triangles, △). Theoretical debye peak corresponding to an exponential in the time domain, solid circles •.

attempt (88) and the earlier calculations (84–87) failed to model the properties of compact bone because they did not incorporate the dependence of its properties on its complex hierarchical structure. Inclusion of the hierarchical structural organization of bone was accomplished by adaptation of the hollow fiber composite model (89) so that it resembled the structure of Haversian bone with the osteons viewed as hollow fibers embedded in a matrix (36,37). Subsequently, the same model (35,36,89) was adapted to calculate the viscoelastic properties of bone (90). In recent years, homogenization techniques have been applied to obtain even further improvements In the composite modeling (91,92).

The matrix is the ground substance that comprises the cement lines between osteons and is thought to be principally composed of mucopolysaccharides. The stiffness of the ground substance has not been determined experimentally, but it has been inferred from the composite model in conjunction with experimental data from the ultrasound studies on whole bone (93,94). Based on this calculation, the ground substance was computed to be about one-quarter as stiff as the osteon itself. The view of the ground substance as a compliant interface is also supported by the results of several experimental studies. Localized slippage occurs at the cement lines in specimens of bovine plexiform bone (95) of human Haversian bone (77) subjected to prolonged stress. Under such conditions, the ground substance at the cement lines appears to behave in a viscous manner. Considering the full range of load rates and frequencies, one may view the ground substance as a compliant and highly viscoelastic material. Such a conclusion is perhaps surprising (2) in view of the fact that the ground substance is highly mineralized (96). Nevertheless a view of the ground substance as a compliant interface is supported by further experiments. For example, studies of single osteons and osteon groups in torsion have revealed size effects to occur and the osteon to have a higher effective shear modulus than whole bone (97). Similar size effects were observed in torsional and bending experiments upon larger microsamples (98,99). These latter results have been interpreted in light of a generalized form of elasticity theory, known as Cosserat elasticity, which admits both strain of the material and local rotations of microscopic constituents, for example, the osteons (97–99). A twist per unit area or couple stress can occur in addition to a force per unit area or couple stress. By contrast, classical elasticity (Eq. 1), which describes most ordinary materials, involves only strains and stresses. Cosserat elasticity is likely differ significantly from classical elasticity in its predictions of stress and strain around holes, cracks, and interfaces. For large, whole bones, conventional anisotropic elasticity has been shown to be entirely adequate (39).

The interface between osteons also appears to be important in conferring a measure of fracture toughness upon compact bone. In particular, the crack blunting mechanism of Cook and Gordon (100) confers toughness in fibrous media by the action of a *weak* interface between fibers in blunting a propagating crack (101). Evidence for the role of the cement substance as such a weak interface has been presented by Piekarski (102). Pullout of fibers can result in a large energy absorption in the fracture of fibrous composites (103). This toughening mechanism also appears to be operative in compact bone, as seen in micrographs of pullout of osteons in fractured bone specimens (51,104).

Consideration of bone as a composite material may provide insight regarding various phenomena in the mechanics of bone. In particular, stress concentration around holes is significantly less than the predicted value (63). The strength of notched specimens does not decrease with the sharpness of the notch as expected; instead, the strength is independent of notch sharpness (49). Residual strain around holes in bone does not follow the predictions of classical anisotropic elasticity (98,99). The fatigue life of bone specimens in bending exceeds that of specimens in tension by a factor of several thousand (59). Similar effects have been observed in various manmade fibrous composites such as boron-epoxy and graphite-epoxy (104). Such phenomena are not correctly predicted by elasticity theory, but may be accounted for in the context of structural models, composite theories, or generalized continuum models (77).

Polycrystalline elastic properties and single-crystal elastic constants of apatites that are useful In the modeling of calcified tissues elasticity are given in Table 6.

Mechanical Properties of Cancellous Bone

Cancellous or trabecular bone is a highly porous or cellular form of bone. In a typical long bone, the cortex or exterior of the shaft (diaphysis) and flared ends (metaphysis) is composed of compact bone while the interior, particularly near the articulating ends, is filled with cancellous bone. Cancellous bone may also be found to fill the interior of short bones and flat bones as well as in the interior of bony tuberosities under mucle attachments. The structure of cancellous bone is that of a latticework of bars and plates; typical structure is shown in Fig. 3. The volume fraction of solid material can be from 5 to 70%; the interstices are filled with marrow. The compressive strength σ_{ult}(in MPa) depends very much on the density ρ (in $\text{g} \cdot \text{cm}^{-3}$) and also varies with the strain rate *de*/*dt* (in s^{-1}) as follows (105).

$$\sigma_{\text{ult}} = 68(de/dt)^{0.06}\rho^2$$

This relation also models the compressive strength of compact bone (221 MPa, at a density of $\rho. = 1.8\ \text{g} \cdot \text{cm}^{-3}$). To a certain degree of approximation, both compact and cancellous bone may be mechanically viewed as a single material of variable density (105). Density is not, however, the only determinant of the properties of cancellous bone. The microstructure can vary considerably from one part of the body to another (106). For example, in the vertebras and in the tibia (107), a highly oriented, columnar architecture is observed. This kind of trabecular bone is highly anisotropic: the Young's modulus in the longitudinal direction can exceed that in the transverse direction by more than a factor of 10 (107). By contrast, in regions such as the proximal part of the bovine humerus, the cancellous bone can be essentially isotropic (108). This bone is about twice as strong in compression as in tension. In many ways, cancellous bone (109–111) is similar in its behavior to manmade rigid cellular foams (112). For example, in compression, the stress–strain curves contain a linear elastic region, up to a strain of ~0.05, at which the cell walls bend or compress (112). A plateau region of almost constant macroscopic stress is associated with elastic buckling, plastic yield, or fracture of the cell walls. The compressive failure of the cancellous bone proceeds at approximately constant stress until the cell walls touch each other; at this point any further compression causes the stress to rise rapidly (112). By contrast, fracture of cancellous bone in tension proceeds abruptly and catastrophically (108). The energy absorption capacity of cancellous bone is consequently much less in tension than it is in compression (109). This suggests that tensile and avulsion fractures of cancellous bone observed clinically are associated with minimal energy absorption, and therefore may be precipitated by relatively minor trauma (109). The elastic modulus E for cancellous bone increases as the square of the density ($E = k\rho^2$) if the structure consists of open cells forming a network of rods (110,111). In closed-cell cancellous structures consisting of plates, the modulus E is proportional to the cube of the density ($E = k\rho^3$). Based on study of micrographs and density maps of femora and vertebras, it is suggested that an open cell structure of rods is found when the solid volume fraction is less than ~ 0.13, while a closed cell plate structure occurs at a density of $>$ 350 $\mathrm{kg \cdot m^{-3}}$ corresponding to a relative density or solid volume fraction of 0.20 (110). The relationship between density and structure may not be so straightforward in all situations. As for the highly oriented columnar cancellous bone from the human tibia (107), the modulus E in the longitudinal direction is proportional to the density ($E = k\rho$). Such behavior is anticipated on the basis of an axial compressional mode of deformation of the cell walls, in contrast to the bending mode that is expected in rod and plate structures (112).

It is important to distinguish the difference between the elastic moduli of volumetric samples of trabecular bone that are highly porous, low density structures, thus exhibiting low moduli, generally well below 1.0 GPa as obtained by mecanical testing techniques, and that of individual trabeculae, comparable in structure and density to cortical bone,thus exhibiting much higher moduli (10–20 GPa), as obtained in recent years by nanoindentation (19) and SAM (18) in addition to that obtained by mechanical testing). Values of the elastic moduli of both trabecular volumes and individual trabeculae are given in Table 7.

ADAPTIVE PROPERTIES OF BONE

Phenomenology

The relationship between the mass and form of a bone to the forces applied to it was appreciated by Galileo (113), who is credited with being the first to understand the balance of forces in beam bending and with applying this understanding to the mechanical analysis of bone. Wolff (114) published his seminal 1892 monograph on bone remodeling; the observation that bone is reshaped in response to the forces acting on it is presently referred to as Wolff's law. Cowin, in Chapter 25 of Ref. 3, discussed "The Problems with Wolff's Law ". Many relevant observations regarding the phenomenology of bone remodeling have been compiled and analyzed by Frost (115,116). Salient points are as follows:

1. Remodeling is triggered not by principal stress but by "flexure".
2. Repetitive dynamic loads on bone trigger remodelling; static loads do not.
3. Dynamic flexure causes all affected bone surfaces to drift toward the concavity that arises during the act of dynamic flexure.

These rules are essentially qualitative and they do not deal with underlying causes. A critique of these ideas has been presented by Currey (1,2). Additional aspects of bone remodeling may be found in the clinical literature. For example, after complete removal of a metacarpal and its replacement with graft consisting of a strut of tibial bone, the graft becomes remodeled to resemble a real metacarpal; the graft continues to function after 52 years (117). In the standards of the Swiss Association for Internal Fixation it is pointed out that severe osteoporosis can result from the use of two bone plates in the same region as a result of the greatly reduced stress in the bone (118). Pauwels (119) suggested that as a result of bending stresses the medial and lateral aspects of the femur should be stiffer and stronger than the anterior and posterior aspects. Such a difference has actually been observed (120). Large cyclic stress causes more resorption than large static stress (121). Immobilization of humans causes loss of bone and excretion of calcium and phosphorus (122). Long spaceflights under zero gravity also cause loss of bone (123,124); hypergravity induced by centrifugation strengthens the bones of rats (125,126). Studies of stress-induced remodeling of living bone have been performed *in vitro* (127). Recently, *in vivo* studies in pigs (128) were conducted. In this study, strains were directly measured by strain gages before and after remodeling. Remodeling was induced by removing part of the pigs' ulna so that the radius bore all the load. Initially, the peak strain in the ulna approximately doubled. New bone was added until, after 3 months, the peak strain was about the same as on the normal leg bones. *In vivo* experiments conducted in sheep (129) have disclosed similar results. It is of interest to compare the response time noted in the above experiments with the rate of bone turnover in healthy humans. The life expectancy of an individual osteon in a normal 45 year old man is 15 years and it will have taken 100 days to produce it (130,131).

Remodeling of Haversian bone seems to influence the quantity of bone but not its quality, that is, young's modulus, tensile strength, and composition (132). However, the initial remodeling of primary bone to produce Haversian bone results in a reduction in strength (1,2). As for the influence of the rate of loading on bone remodeling, there is good evidence to suggest that intermittent deformation can produce a marked adaptive response in bone, whereas static deformation has little effect (127). Experiments (133) upon rabbit tibiae bear this out. In the dental field, by contrast, it is accepted that static forces of long duration move teeth in the jawbone. In this connection (134), the direction (as well as the type) of stresses acting on the bone tissue should also be considered. Currey (1,2) points out that the response of different bones in the same skeleton to mechanical loads must differ, otherwise lightly loaded bones such as the top of the human skull, or the auditory ossicles, would be resorbed.

Failure of bone remodeling to occur normally in certain disease states is of interest: for example, osteropetrotic bone contains few if any viable osteocytes and usually contains a much larger number of microscopic cracks than adjacent living bone (135). This suggests that the osteocytes play a role in detecting and repairing the damage. In senile osteoporosis, bone tissue is removed by the body, often to such an extent that fractures occur during normal activities. Osteoporosis may be referred to as a remodeling error (116).

Some theoretical work, notably by Cowin and others (3,136) has dealt with the problem of formulating Wolff's law in a quantitative fashion. In this theory, constitutive equations are developed, which predict the remodeling response to a given stress. Stability considerations are invoked to obtain some constraints on the parameters in the constitutive equation.

Feedback Mechanisms

Bone remodeling appears to be governed by a feedback system in which the bone cells sense the state of strain in the bone matrix around them and either add or remove bone as needed to maintain the strain within normal limits. The process or processes by which the cells are able to sense the strain and the important aspects of the strain field are presently unknown. Bassett and Becker (137) reported that bone is piezoelectric, that is, that it generates electric fields in response to mechanical stress; they advanced the hypothesis that the piezoelectric effect is the part of the feedback loop by which the cells sense the strain field. This hypothesis obtained support from observations of osteogenesis in response to externally applied electric fields of the same order of magnitude as those generated naturally by stress via the piezoelectric effect. The study of bone bioelectricity has received impetus from observations that externally applied electric or electromagnetic fields stimulate bone growth (138). The electrical hypothesis, while favored by many, has not been proven. Indeed, other investigators have advanced competing hypotheses that involve other mechanisms by which the cells are informed of the state of stress around them.

For example, inhomogeneous deformation at the lamellae may impinge on osteocyte processes and thus trigger the osteocytes to initiate bone formation or remodelling (139). Motion at the cement lines was observed and it was suggested that such motion could act as a passive mechanism by which bone's symmetry axes may become aligned to the direction of time averaged principal stresses (99). Stress on bone may induce flow of fluid in channels, (e.g., canaliculi), and such flow could play a role in the nutrition and waste elimination of osteocytes, which may be significant in bone remodeling (140). In a related vein, theoretical arguments have been presented in support of the hypothesis that bone cells are directly sensitive to hydrostatic pressure transmitted to them from the bone matrix via the tissue fluid (141). Although no experimental test of this direct pressure hypothesis has been published, we observe with interest that direct hydrostatic pressure has been observed to alter the swimming behavior of paramecia, possibly by means of action upon the cell membrane (142). Otter and Salman found that a hydrostatic pressure of 68 atm abolishes the reversing of direction of swimming, 170 atm stops swimming, and 400–500 atm irreversibly damages the cell. We observe that 100 atm corresponds to 1400 psi stress, or in bone, a strain of 0.07%, which is in the normal range of bone strain and 500 atm corresponds to 7000 psi or a strain of 0.35%, well above the normal range of bone strain. Stress in bone also results in temperature differences between osteons (143); the cells may be sensitive to sudden temperature changes during human activity. A mechanochemical hypothesis has been advanced, in which the solubility of calcium may be affected by stress in the bone matrix (144). Strain energy in bone might also influence the energetics of bone mineral nucleation (145). It has also been suggested that remodeling may be initiated in response to microcracks generated by mechanical fatigue of bone (146). In summary, many hypotheses have been proposed for the mechanism by which appropriate cells sense the state of strain in bone, but little or no experimental evidence is available to discriminate among them.

Cellular and Biochemical Aspects of Bone Remodeling

The adaptive response of bone to mechanical stimuli is mediated by living cells. A great deal is known concerning bone cell function and its control by ionic and hormonal factors, but little is known concerning the effect of mechanical strain in bone upon the biochemistry of its cells. Rasmussen and Bordier (147) have presented an extensive review of studies of bone cell physiology. Recently, the biochemical consequences of electrical stimulation of bone have been reported (148). Biochemical steps associated with cell activation are as yet poorly understood, but ion fluxes appear to play a role (149). Cyclic nucleotides mediate the effects of extracellular signals (150) and prostaglandins modulate them (149). Prostaglandin E_2 has been hypothesized to mediate bone resorption in trauma, malignancy, and periodontal disease. This prostaglandin, as well as the cellular constituents cyclic AMP and cyclic GMP, has been found in association with regions of bone stimulated electrically (148).

ELECTRICAL PROPERTIES OF BONE

Fukada and Yasuda (151) first demonstrated that dry bone is piezoelectric in the classic sense, that is, mechanical stress results in electric polarization, the indirect effect; and an appplied electric field causes strain, the converse effect. The piezoelectric properties of bone are of interest in view of their hypothesized role in bone remodeling (137). Wet collagen, however, does not exhibit piezoelectric response. Studies of the dielectric and piezoelectric properties of fully hydrated bone raise some doubt as to whether wet bone is piezoelectric at all at physiological frequencies (152). Piezoelectric effects occur in the kilohertz range, well above the range of physiologically significant frequencies (152). Both the dielectric properties (153) and the piezoelectric properties of bone (154) depend strongly on frequency. The magnitude of the piezoelectric sensitivity coefficients of bone depends on frequency, on direction of load, and on relative humidity. Values up to 0.7 pC/N have been observed (154), to be compared with 0.7 and 2.3 pC/N for different directions in quartz, and 600 pC/N in some piezoelectric ceramics. It is, however, uncertain whether bone is piezoelectric in the classic sense at the relatively low frequencies which dominate in the normal loading of bone. The streaming potentials examined originally by Anderson and Eriksson (155,156) can result in stress generated potentials at relatively low frequencies even in the presence of dielectric relaxation, but this process is as yet poorly understood.

Potentials observed in bent bone differ from predictions based on the results of experiments performed in compression (157). The piezolectric polarization may consequently depend on the strain gradient (157) as well as on the strain. This piezoelectric theory has been criticized as ad hoc by some authors, however, the idea has some appeal in view of Frost's modeling (115,116) and Currey's suggestion (1,2) that strain gradients may be significant in this regard. The gradient theory is not ad hoc, but can be obtained theoretically from general nonlocality considerations (158). The physical mechanism for such effects is hypothesized to lie in the fibrous architecture of bone (26,78). Theoretical analyses of bone piezoelectricity (159–162) may be relevant to the issue of bone remodeling. Recent thorough studies have explored electromechanical effects in wet and dry bone. They suggest that two different mechanisms are responsible for these effects: Classical piezoelectricity due to the molecular asymmetry of collagen in dry bone, and fluid flow effects, possibly streaming potentials in wet bone (163).

Bone exhibits additional electrical properties which are of interest. For example, the dielectric behavior (e.g., the dynamic complex permittivity) governs the relationship between the applied electric field and the resulting electric polarization and current. Dielectric permittivity of bone has been found to increase dramatically with increasing humidity and decreasing frequency (152,153). For bone under partial hydration conditions, the dielectric permittivity (which determines the capacitance) can exceed 1000 and the dielectric loss tangent (which determines the ratio of conductivity to capacitance) can exceed unity. Both the permittivity and the loss are greater if the electric field is aligned parallel to the bone axis. Bone under conditions of full hydration in saline behaves differently: the behavior of bovine femoral bone is essentially resistive, with very little relaxation (164). The resistivity is $\sim$ 45–48 μm for the longitudinal direction, and three to four times greater in the radial direction. These values are to be compared with a resistivity of 0.72 μm for physiological saline alone. Since the resistivity of fully hydrated bone is $\sim$ 100 times greater than that of bone under 98% relative humidity, it is suggested that at 98% humidity the larger pores are not fully filled with fluid (164).

Compact bone also exhibits a permanent electric polarization as well as pyroelectricity, which is a change of polarization with temperature (165,166). These phenomena are attributed to the polar structure of the collagen molecule; these molecules are oriented in bone. The orientation of permanent polarization has been mapped in various bones and has been correlated with developmental events.

Electrical properties of bone are relevant not only as a hypothesized feedback mechanism for bone remodeling, but also in the context of external electrical stimulation of bone to aid its healing and repair (167,168).

The frequency of electrical stimulation influences its effectiveness (169). A frequency band of 20–30 Hz was found from analysis of strain data. Bone growth could be stimulated more easily in the avian ulna at relatively higher frequencies. Electromagnetic stimuli also prevent bone loss due to disuse as revealed in an isolated canine fibula model (170). Bone density may be maintained and increased by weight lifting, which involves no medical intervention. Indeed, bone mineral content values (as determined with dual photon absorptiometry) in the spines of athletes were extremely high and were closely correlated to the amount of weight lifted during training (171).

BIBLIOGRAPHY

Cited References

1. Currey J. The mechanical adaptations of bones. Princeton: Princeton University Press; 1984.
2. Currey J. Bone Structure and Mechanics. Princeton: Princeton University Press; 2002.
3. Cowin S. Bone Mechanics. 2nd ed. Boca Raton, FL: CRC Press; 2001.
4. Park JB, Lakes RS. Biomaterials. 2nd ed. New York: Plenum; 1992.
5. Hancox NM. Biology of Bone. Cambridge, (MA): Cambridge University Press; 1972.
6. LeGeros RZ. Monographs in Oral Science. Karger: 1991.
7. Sokolnikoff IS. Mathematical theory of elasticity. Krieger; 1983.
8. Ferracane JL. Materials In Dentistry. 2nd ed. Philadelphia: Lippincott, Williams & Wilkins; 2001.
9. Briggs A. Acoustic Microscopy. Oxford: Clarendon Press; 1992.
10. Lakes RS. Viscoelastic Solids. Boca Raton, FL: CRC Press; 1998.
11. Eppell SJ, Tong WL, Katz JL, Kuhn L, Glimcher MJ. Shape and size of isolated bone mineralites measured using atomic force microscopy" J Ortho Res 2001;19:1027–1034.
12. Tong W, Glimcher MJ, Katz JL, Kuhn L, Eppell SJ. Size and shape of Mineralites in young bovine bone measured by atomic force microscopy. Calcif Tiss Inter 2003;72:592–598.
13. Reilly DT, Burstein AH. The elastic and ultimate properties of compact bone tissue. J Biomech 1975;8:393–405.
14. Craig RG, Peyton FA. Elastic and mechanical properties of human dentin. J Dental Res 1958;37:710–718.
15. Craig RG, Peyton FA. Compressive properties of enamel, dental cements, and gold. J Dental Res 1961;40:936–945.
16. Ashman RB, Cowin SC, Van Buskirk WC, Rice JC. A continuous wave technique for the measurement of the elastic properties of cortical bone. J Biomech 17:349–361.
17. Reilly DT, Burstein AH. The mechanical properties of cortical bone. J Bone Jnt Surg 1974;56A:1001–1022.
18. Bumrerraj S, Katz JL. Scanning acoustic microscopy study of human cortical and trabecular bone. Ann Biomed Eng 2001;29:1–9.
19. Rho JY, Pharr GM. Effects of drying on the mechanical poroperties of bovine femur measured by nanoindentation. J Mater Sci, Matyer Med 1999;10:1–4.

20. Kapur R. The use of scanning acoustic microscopy to study the microstructural properties of the dentin/enamel junction, B.S. Project (Katz JL, Advisor), Department of Biomedical Engineering, Case Western Reserve University; 1999.
21. Löst C, Irion KM, Nussle JC. Two-dimensional distribution of sound velocity in ground sections of enamel. Endod Dent Traumatol 1992;8:215–218.
22. Van Buskirk WC, Ashman RB. The elastic moduli of bone. In: Mechanical Properties of Bone, Joint ASME-ASCE Applied Mechanics, Fluids Engineering and Bioengineering Conference. Boulder, CO; 1981.
23. Lees S, Rollins FR, Jr. Anisotropy in hard dental tissues. J Biomech 1972;5:557–566.
24. Lees S, Ahern JM, Leonard M. Parameters influencing the sonic velocity in compact calcified tissues of various species. J Acoust Soc Am 1983;74:28–33.
25. Gilmore RS, Pollack RP, Katz JL. The elastic properties of bovine dentin and enamel. Arch Oral Biol 1970;15:787– 796.
26. Katz JL, Lipson S, Yoon HS, Maharidge R, Meunier A, Christel P. The effects of remodeling on the elastic properties of bone, Calc Tiss Inter 1984;36:S31–S36.
27. Yoon HS, Katz JL. Ultrasonic wave propagation in human cortical bone. II. Measurements of elastic properties and microhardness. J Biomech 1976;9:459–464.
28. Yoon HS, Newnham RE. Elastic Properties of fluorapatite. Am Min 1969;54:1193–1197.
29. Gordon JE. Structures. Penguin; 1983.
30. Lemons RA, Quate CF. Acoustic microscopy-scanning version. Appl Phys Lett 1974;24:163–165.
31. Lemons RA, Quate CF. Acoustic microscopy. Phys Acoust 1979;14:1–92.
32. Katz JL, Meunier A. Scanning acoustic microscope studies of the elastic properties of osteons and osteon lamellae. J Biomech Eng 1993;115:543–548.
33. Evans FG, Bang S. Differences and relationships between the physical properties and the microscopic structure of human femoral, tibial, and fibular bone. Am J Anat 1967;120:79–88.
34. Evans FG, Vincentelli R. Relations of the compressive properties of human cortical bone to histological structure and calcification. J Biomech 1974;7:1–10.
35. Lang SB. Ultrasonic method for measuring elastic coefficients of boneand results on fresh and dried bovine bones. IEEE Trans Biomed Eng, BME 1970;17:101–105.
36. Yoon HS, Katz JL. Ultrasonic wave propagation in human cortical bone, I. Theoretical considerations for hexagonal symmetry, J Biomech 1976;9:407–412.
37. Katz JL. Hierarchical modeling of compact Haversian bone as a fiber reinforced material. In: 1976 Advances in Bioengineering. New York City: ASME; 1976. p 17–18.
38. Katz JL. On the anisotropy of young's modulus of bone. Nature (London) 1980;283:106–107.
39. Huiskes R, Janssen JD, Sloof TJ. A detailed comparison of experimental and theoretical stress analyses of a human femur. In: Mechanical Properties of Bone, Joint ASME-ASCE Applied Mechanics, Fluids Engineering and Bioengineering Conference. Boulder, (CO); 1981.
40. Lipson SF, Katz JL. The relationship between the elastic properties and microstructure of bovine cortical bone. J Biomech 1984;17:231–240.
41. Ashman RB, Rosina G, Cowin SC, Fontenot MG. The bone tissue of the canine mandible is elastically isotropic. J Biomech 1985;18:717–721.
42. Ashman RB, Van Buskirk WC, Cowin SC, Sandbornj PM, Wells MK, Rice JC. The mechanical Properties of immature osteopetrotic bone. Calc Tiss Inter 1985;37:73–76.
43. Lakes RS. Materials with structural hierarchy. Nature (London) 1993;361:511–515.
44. Melick RA, Miller DR. Variations of tensile strength of human cortical bone with age. Clin Sci 1966;30:243–248.
45. Hazama H. Study of the torsional strength of the compact substance of human beings. J Kyoto Pref Med Univ 1956;60:167–184.
46. Evans FG, Lebow M. Regional differences in some of the physical properties of the human femur. J Appl Physiol 1951;3:563–572.
47. Sedlin ED, Hirsch C. Factors affecting the determination of the physical properties of femoral cortical bone. Acta Orthop Scand 1966;37:29–48.
48. Burstein AH, Reilly DT, Martens M. Aging of bone tissue: mechanical properties. J Bone Jnt Surg 1976;58A:82–86.
49. Bonfield W, Datta PK. Fracture toughness of compact bone. J Biomech 1976;9:131–134.
50. Behiri JC, Bonfield W. Crack velocity dependence of longitudinal fracture in bone. J Mat Sci 1980;15:1841–1849.
51. Currey JD. Changes in the impact energy absorption of bone with age. J Biomech 1979;12:459–469.
52. Corondan G, Haworth WL. A fractographic study of human long bone. J Biomech 1986;19:207–218.
53. Carter DR, Spengler DM. Biomechanics of fracture. In: Sumner Smith G, editor. Bone in Cinical Orthopaedics. New York: Saunders; 1982. p 305–332.
54. Lanyon LE. Analysis of surface bone strain in the calcaneus of sheep during normal locomotion. J Biomech 1973;6:41– 69.
55. Lanyon LE, Hampson WGJ, Goodship AE, Shah JS. Bone deformation recorded in vivo from strain gauges attached to the human tibial shaft. Acta Orthop Scand 1975;46:256–268.
56. Caler WE, Carter DR, Harris WH. Techniques for implementing an *in vivo* bone strain gage system. J Biomech 1981;14:503–507.
57. Rubin CT. Skeletal strain and the functional significance of bone architecture. Calcif Tissue Int 1984;36:S11–S18.
58. Nunamaker DM, Butterweck DM, Provost MT. Fatigue fractures in thoroughbred racehorses: relationships with age, peak bone strain, and training. J Orthop Res 1990;8:694.
59. Carter DR, Caler WE, Spengler DM, Frankel VH. Uniaxial fatigue of human cortical bone. The influence of tissue physical characteristics. J Biomech 1981;14:461–470.
60. Keller TS, Lovin JD, Spengler DM, Carter DR. Fatigue of immature baboon cortical bone. J Biomech 1985;18:297–304.
61. Devas MB. Stress fractures. Churchill Livingstone, London; 1975.
62. Carter DR, Caler WE, Spengler DM, Frankel VH. Fatigue behavior of adult cortical bone: the influence of mean strain and strain range. Acta Orthop Scand 1981;52:481–490.
63. Brooks DB, Burstein AH, Frankel VH. The biomechanics of torsional fractures: the stress concentration effect of a drill hole. J Bone Jnt Surg 1970;52A:507–514.
64. Burstein AH, Currey JD, Frankel VH, Heiple KG, Lunseth P, Vessely JC. Bone strength: the effect of screw holes. J Bone Jnt Surg 1972;54A:1143–1156.
65. Laurence M, Freeman MA, Swanson SA. Engineering considerations in the internal fixation of fractures of the tibial shaft. J Bone Jnt Surg 1969;51B:754–768.
66. Timoshenko S, Goodier JM. Theory of elasticity, 3rd ed. New York: McGraw Hill; 1983.
67. Lakes RS, Yang JFC. Concentration of strain around holes in a strip of compact bone, Developments in mechanics, Proceedings of the 18th Midwestern Mechanics Conference. Volume 12, Iowa City; 1983. p 233–237.
68. Awerbuch J, Madhukar S. Notched strength of composite laminates: predictions and experiments, a review. J Reinforced Plast Comp 1985;4:3–159.
69. Daniel IM. Strain and failure analysis in graphite/epoxy plates with cracks. Exper Mech 1978;18:246–252.

70. Smith R, Keiper D. Dynamic measurement of viscoelastic properties of bone. Am J Med Electr 1965;4:156.
71. Currey JD. Anelasticity in bone and echinoderm skeletons. J Exper Biol 1965;43:279.
72. Black J, Korostoff E. Dynamic mechanical properties of viable human cortical bone. J Biomech 1973;16:435.
73. Tennyson RC, Ewert R, Niranjan V. Dynamic viscoelastic response of bone. Exp Mech 1972;12:502.
74. Lugassy AA, Korostoff E. Viscoelastic behavior of bovine femoral cortical bone and sperm whale dentin. In: Research in Dental and Medical Materials. New York: Plenum; 1969.
75. Lakes RS, Katz JL, Sternstein SS. Viscoelastic properties of cortical bone: Part 1: Torsional and biaxial studies. J Biomech 1979;12:657.
76. Lakes RS, Katz JL. Interrelationships among the viscoelastic functions for anisotropic solids: application to calcified tissues and related systems. J Biomech 1974;17:259.
77. Park HC, Lakes RS. Cosserat micromechanics of human bone: strain redistribution by a hydration-sensitive constituent. J Biomech 1986;19:385–397.
78. Sasaki N, Nakayama Y, Yoshikawa M, Enyo A. Stress relaxation function of bone and bone collagen. J Biomech 1993;26:1369–1376.
79. Garner E, Lakes RS, Lee T, Swan C, Brand R. Viscoelastic dissipation in compact bone: implications for stress-induced fluid flow in bone. J Biomech Eng 2000;122:166–172.
80. Thompson G, Experimental studies of lateral and torsional vibration of intact dog radii, [dissertation]. Stanford (CA): Stanford University; 1971.
81. Lakes RS. Dynamical study of couple stress effects in human compact bone. J Biomech Eng 1982;104:6–11.
82. Adler L, Cook CV. Ultrasonic parameters of freshly frozen dog tibia. J Acoust Soc Am 1975;58:1107–1108.
83. Currey JD. Three analogies to explain the mechanical properties of bone. Biorheology 1964;2:1–10.
84. Welch DO. The composite structure of bone and its response to mechanical stress. Recent Adv Eng Sci 1970;5:245–262.
85. Katz JL. Hard tissue as a composite material-I. Bounds on the elastic behavior. J Biomech 1971;4:455–473.
86. Piekarski K. Analysis of bone as a composite material. Inter J Eng Sci 1973;11:557–565.
87. Currey JD. The relationship between the stiffness and the mineral content of bone. J Biomech 1969;2:477.
88. Bonfield W, Grynpas MD. Anisotropy of Young's modulus of bone. Nature (London) 1977;270:453–454.
89. Hashin Z, Rosen BW. The elastic moduli of fiber reinforced materials. J Appl Mech 1964;31:223–2xx.
90. Gottesman T, Hashin Z. Analysis of viscoelastic behavior of bone on the basis of microstructure. J Biomech 1979;13:89–yy.
91. Hogan H. Micromechanics modeling of haversian cortical bone properties. J Biomech 1992;25:549–zzz.
92. Crolet JM, Aoubiza B, Meunier A. Compact bone: Numerical simulation of mechanical characteristics. J Biomech 1993;26:677–aaa.
93. Katz JL, Maharidge RL, Yoon HS. The estimation of interosteonal mechanical properties from a composite model for haversian bone. In: Perren SM, Scheider E, editors. Biomechanics: Current Interdisciplinary Research. Dordrecht: Martinus Injhoff, 1985. p 179–184.
94. Katz JL, Maharidge RL, Yoon HS. Calculation of inter-osteonal mechanical properties for haversian bone based on a hierarchical composite model. Biomechanics Symp. AMD-Vol. 68, FED-Vol. 21. New York City: ASME; 1985. p 33–35.
95. Lakes RS, Saha S. Cement line motion in bone. Science 1979;204:501–503.
96. Frasca P. Scanning-electron microscopy studies of 'ground substance' in the cement lines, resting lines, hypercalcified rings, and reversal lines of human cortical bone, Acta Anatomica 1981;109:115–121.
97. Frasca P, Harper R, Katz JL. Strain and frequency dependence of shear storage modulus for human single osteons and cortical bone microsamples-size and hydration effects. J Biomech 1981;14:679–690.
98. Yang JFC, Lakes RS. Transient study of couple stress effects in human compact bone: Torsion. J Biomech Eng 1981;103:275–279.
99. Yang JFC, Lakes RS. Experimental study of micropolar and couple stress elasticity in compact bone in bending. J Biomech 1982;15:91–98.
100. Cook J, Gordon JE. A mechanism for the control of crack propagation in all-brittle systems. Proc R Soc London 1964;A282:508–520.
101. Kelly A. The strengthening of metals by dispersed particles. Proc R Soc London 1964;A282:63–79.
102. Piekarski K. Fracture of Bone. J Appl Phys 1970;41:215–223.
103. Kelly A. Strong solids. London: Oxford University Press; 1966.
104. Wright TM, Barnett DM, Hayes WC. Residual stresses in bone. Volume 3, Recent Advances in Engineering Science. Boston: Scientific Publishers; 1977. p 25–32, Proceedings, 10th meeting, Society of Engineering Science, NC: Raleigh; 1973.
105. Carter DR, Hayes WC. Bone compressive strength: the influence of density and strain rate. Science 1976;194: 1174–1176.
106. Dyson ED, Jackson CK, Whitehouse WJ. Scanning electron microscope studies of human trabecular bone. Nature (London) 1970;225:957–959.
107. Williams JL, Lewis JL. Properties and an anisotropic model of cancellous bone from the proximal tibial epiphysis. J Biomech Eng 1982;104:50–56.
108. Kaplan S, Hayes WC, Stone JL, Beaupre GS. Tensile strength of bovine trabecular bone. J Biomech 1985;18: 723–727.
109. Carter DR, Schwab GH, Spengler DM. Tensile fracture of cancellous bone. Acta Orthop, Scand 1980;51:733–741.
110. Gibson LJ. The mechanical behaviour of cancellous bone. J Biomech 1985;18:317–328.
111. Carter DR, Hayes WC. The compressive behaviour of bone as a two-phase porous structure. J Bone Jnt Surg 1977;59A:954–962.
112. Gibson LJ, Ashby MF. The mechanics of three-dimensional cellular materials. Proc R Soc London 1982;A382:25–42.
113. Galilei G, Discorsi E. Dimostrazioni Matematiche intorna a due nuove Scienze. 1638, Translated by H Crew, A deSalvio, editors. New York: Macmillan; pp 158–172. 1914. p 118–134.
114. Wolff J. Das Gesetz der Transformation der Knochen. Berlin: Hirschwald; 1892.
115. Frost HM. Bone remodelling and its relation to metabolic bone diseases. Springfield, IL: C Thomas; 1973.
116. Frost HM. Bone modelling and skeletal modelling errors. Springfield, IL: C Thomas; 1973.
117. Nathan PA, Fowler A. Remodeling of a metacarpal bone graft in a child. J Bone Jnt Surg 1976;58A:719–722.
118. Muller ME, Allgouer M, Willeneger H. Manual of Internal Fixation—Technique Recommended by the AO Group. Springer Verlag; 1970.
119. Pauwels F. Die Bedeutung des Bauprinzipien des Stütz, und Bewegensapparatens für, die Beanspruchung der Rohrenknochen. Z Anat Entwicklungs 1948;114:129–166.

120. Amtmann E. The distribution of the breaking strength in the femur. J Biomech 1968;1:271–277.
121. Seirig A, Kempko W. Behavior of *in vivo* bone under cyclic loading. J Biomech 1969;2:455–461.
122. Dietrick JE, Whedon G, Shorr E. Effects of immobilization upon various metabolic and physiological functions of bone. Am Jnl Med 1948;4:3–36.
123. Mack PB, La Chance PL. Effects of recumbency and space flight on bone density. Am J Clin Nutrition 1967;20:194–205.
124. Morey ER, Baylink DK. Inhibition of bone formation during space flight. Science 1978;201:1138–1141.
125. Wunder CC, Briney SR, Skangstad CA. Growth of mouse femurs during chronic centrifugation. Nature (London) 1960;188:151–152.
126. Wunder CC, Cook RM, Welch RC, Glade R, Fleming BP. Femur bending properties as influenced by gravity: I. ultimate load and moment for 3-G rats. Aviat Space Environ Med 1977;48:339–346.
127. Glucksmann A. Studies of bone mechanics *in vitro* I-Influence of pressure on orientation of structure. Anat Rec 1938;72:97–115.
128. Goodship AE, Lanyon LE, McFie M. Functional adaptation of bone to increased stress. J Bone Jnt Surg 1979;61A:539–546.
129. Hall BK. Developmental and cellular skeletal biology. New York: Academic Press, 1978.
130. Sumner-Smith G. Bone in clinical orthopaedics. New York: W. B. Saunders; 1982.
131. Lanyon LE, Magee PT, Bagott DG. The relationship of the functional stress and strain to the process of bone remodelling: an experimental study on the sheep radius. J Biomech 1979;12:593–600.
132. Woo SLY, Kuei SC, Amiel D, Gomez MA, Hayes WC, White FC, Akeson WH. The effect of prolonged physical training on the properties of long bone: a study of Wolff's law. J Bone Jnt Surg 1981;63A:780–787.
133. Liskova M, Hert J. Reaction of bone to mechanical stimuli, part 2, periosteal and endosteal reaction of the tibial diaphysis in rabbit to intermittent loading. Folia Morpholog 1971;19:310–317.
134. Wright KWJ, Yettram AL. An analytical investigation into possible mechanical causes of bone remodelling. J Biomed Eng (England) 1979;1:41–49.
135. Frost HM. Osteocyte death in vivo. J Bone Jnt Surg 1960;42A:138–143.
136. Cowin SC, Hegedus DH. Bone Remodeling I: Theory of adaptive elasticity. J Elasticity 1976;6:313–326.
137. Bassett CAL, Becker RO. Generation of electric potentials in bone in response to mechanical stress. Science 1962;137: 1063–1064.
138. Spadaro JA. Electrically stimulated bone growth in animals and man. Clin Orthopaed 1977;122:325–332.
139. Tischendorf F. Das Verhalten der Haversschen Systeme bei Belastung. Arch Entwicklungsmech Org 1951;145:318–332.
140. Piekarski K, Munro M. Transport mechanism operating between blood supply and osteocytes in long bones. Nature (London) 1977;269:80–82.
141. Jendrucko RJ, Hyman WA, Newell PH, Chakraborty BK. Theoretical evidence for the generation of high pressure in bone cells. J Biomech 1976;9:87–91.
142. Otter T, Salman ED. Hydrostatic pressure reversibly blocks membrane control of ciliary motion in paramecium. Science 1979;206:358–361.
143. Lakes RS, Katz JL. Viscoelastic properties and behavior of cortical bone, Part II, relaxation mechanisms. J Biomech 1979;12:689–698.
144. Justus R, Luft JH. A mechanicochemical hypothesis for bone remodelling induced by mechanical stress. Calc Tiss Res 1970;5:222–235.
145. Jendrucko RJ. Energetics of hydroxyapatite nucleation in bone, Proc 30th ACEMB, Los Angeles: 1977.
146. Martin RB, Burr DB. A hypothetical mechanism for the stimulation of osteonal remodelling by fatigue damage. J Biomech 1982;15:137–139.
147. Rasmussen H, Bordier P. The Physiological and Cellular Basis of Metabolic Bone Disease. Williams & Wilkins; 1974.
148. Davidovitch Z, Furst L, Shanfield JL, Montgomery PC, Kelischeck S, Laster L, Korostoff E. Biochemical mediators of electrical stimulation of bone cells. 35th ACEMB. Philadelphia: Sept. 1982. p 217.
149. Rodan GA, Bourret LA, Norton LA. DNA synthesis in cartilage cells is stimulated by oscillating electric fields. Science 1978;199:690–692.
150. Sutherland J, Rall M. The relation of adenosine 3′:5′-phosphate and phosphorylase to the actions of catecholamines and other hormones. Pharmacol Rev 1977;12:265–299.
151. Fukada E, Yasuda I. On the piezoelectric effect of bone. J Phys Soc J 1957;12:1158–1162.
152. Reinish G. Piezoelectric properties of bone as functions of moisture content. Nature (London) 1975;253:626–627.
153. Lakes RS, Katz JL. Dielectric relaxation in cortical bone. J Appl Phys 1977;48:808–811.
154. Burr AJ. Measurements of the dynamic piezoelectric properties of bone as a function of temperature and humidity. J Biomech 1976;1:495–507.
155. Anderson JC, Eriksson C. Electrical properties of wet collagen. Nature (London) 1968;218:167–169.
156. Anderson JC, Eriksson C. Piezoelectric properties of dry and wet bone. Nature (London) 1970;227:491–492.
157. Williams WS. Sources of piezoelectricity in tendon and bone. CRC Crit Rev Bioeng 1974;2:95–117.
158. Lakes RS. The role of gradient effects in the piezoelectricity of bone. IEEE Trans Biomed Eng 1980;BME27:282–283.
159. Korostoff E. Stress generated potentials in bone: relationship to piezoelectricity of collagen. J Biomech 1979;10:41–44.
160. Korostoff E. A Linear piezoelectric Model for characterizing stress generated potentials in bone. J Biomech 1979;12:335–347.
161. Gjelsvik A. Bone remodeling and piezoelectricity II. J Biomech 1973;6:187–193.
162. Guzelsu N. A piezoelectric model for dry bone and tissue. J Biomech 1978;11:257–267.
163. Johnson M, Chakkalakal D, Harper RA, Katz JL. Comparison of the electromechanical effects in wet and dry bone. J Biomech 1980;13:437–442.
164. Chakkalakal DA, Johnson MW, Harper RA, Katz JL. Dielectric properties of fluid saturated bone. IEEE Trans Biomed Eng 1980;BME-27:95–100.
165. Athenstaedt H. Permanent electric polarization and pyroelectric behavior of the vertebrate skeleton. VI, the appendicular skeleton of man. Z Anat Entwickl Gesch 1970;131:21–30.
166. Lang SB. Pyroelectric effect in bone and tendon. Nature (London) 1966;212:704–705.
167. Bassett CAL, Pilla AA, Pawluk RJ. A non-operative salvage of surgically resistant pseudarthrosis and non-unions by pulsing electromagnetic fields: a preliminary report. Clinical Orthop 1977;124:128–143.
168. Brighton CT, Friedenberg ZB, Mitchell EI, Booth RE. Treatment of non-union with constant direct current. Clinical Orthop 1977;124:106–123.

169. McLeod KJ, Rubin CT. The effect of low frequency electrical fields on osteoporosis. J Bone Joint Surg 1992;74-A:920–929.
170. Skerry TM, Pead MJ, Lanyon LE. Modulation of bone loss during disuse by pulsed electromagnetic fields. J Orthop Res 1991;9:600–608.
171. Granhed H, Jonson R, Hansson T. The loads on the lumbar spine during extreme weight lifting., Spine 1987;12(2): 146–149.

Reference List

Gilmore RS, Katz JL. Elastic properties of apatites. J Mat Sci 1982;17:1131–1141.

Katz JL, Ukraincik K. On the anisotropic elastic properties of hydroxyapatite. J Biomech 1971;4:221–227.

Lakes RS, Katz JL. Viscoelastic properties of bone. In Hastings G, Ducheyne P, editors. Natural and Living Biomaterials. Washington, (DC): CRC Press; 1984.

Ortmann R, Perkins JP. Stimulation of adenosine 3′:5′ monophospate formation by prostaglandins in human astrocytoma cells. J Biol Chem 1977;252:6019–6025.

See also Biomaterials for dentistry; bone cement, acrylic; tooth and jaw, biomechanics of.

BONE CEMENT, ACRYLIC

Chaodi Li
Yan Zhou
University of Notre Dame
Notre Dame, Indiana

INTRODUCTION

Many years of intensive research by Rohm led to the development of poly(methyl methacrylate) (PMMA), the basis of bone cement, in 1934 (1,2). This polymer was reportedly first used to close cranial defects in monkeys in a medical application in the late 1930s (2). The use of acrylic bone cement in orthopedic surgery was first advocated in 1951 by Kiaer and Jansen. It was applied as pure anchoring material by fixing acrylic glass caps on the femoral head after removing the cartilage (2–4). At that time, the femoral components in total hip replacements were still implanted by simply press-fitting the prosthesis tightly into the prepared intramedullary (marrow) canal of the femur. Patients were confined to bed for a relatively long period of time after surgery and often experienced pain later from loosening of the implant. In 1958, Sir John Charnley first applied the self-curing bone cement for the fixation of artificial joints (4). In this surgery, the cement filled the free space between the prosthesis and the bone (2). Bone cement served as a mechanical interlock between the metallic prosthesis and the bone and it has been found to be an appropriate material to transfer the load consistently (5). In 1969, bone cement was approved for general use within the United States and since then the number of total hip and knee replacements has increased dramatically (3). Currently, it is the only material used for anchoring cemented arthroplasties to the contiguous bones (6). More than one-half million hip replacement surgeries are performed every year worldwide and 70% of the surgeries are performed using bone cements (7–10).

Bone cement is also extensively used in the fixation of pathological fractures, spinal surgery, and neurosurgery (11). Every year, osteoporosis results in $>310{,}000$ fractures in the United Kingdom alone (12). Vertebral compression fractures occur in 20% of people over the age of 70 years and in 16% of postmenopausal women (12). Although traditional conservative techniques, such as bed rest and the prescription of analgesics may be successful in a proportion of cases, a significant number of sufferers remain in long-term pain. Vertebroplasty is now being used extensively for vertebral compression fracture treatments (12,13). This technique entails the percutaneous injection of bone cement into the fractured vertebra in attempts to stabilize the fracture and reduce pain. Studies have reported excellent pain relief and improved function in most patients (12,13). Bone cements have also been applied as an adjunct to internal fixation for treating fractures. Bone cement fills voids in bone, thereby reducing the need for bone grafts, and may improve the holding strength around the devices in osteoporotic bone. Recently, the technique of PMMA bone cement injection into the osteoporotic proximal femur was proposed (14). Results indicated that cement injection increased the peak fracture load >80 and 20% in the simulated fall and one single limb stance configurations, respectively (14). This technique could become a treatment option to solve the problems with osteoporotic hip fractures in patients at risk. Such treatment may hold a significant impact on the economy and human health as hip fractures result in $\sim 300{,}000$ hospital admissions annually in the United States with an estimated $9 billion in direct medical costs (14). Therefore, bone cements are significantly valuable for biomedical applications.

In many cases, the bone cemented implants perform satisfactorily for years. However, failure of the implants may be linked to bone cement properties. It is well recognized that there are a number of drawbacks that exist with the usage of bone cement, significant ones including its poor mechanical properties and the potential necrosis of bone tissues (6,15,16). For example, bone cement has been called the “weak link” in the prosthesis system and long-term loosening of the prosthesis has been attributed to its mechanical disintegration (10). It is worth pointing out that aseptic loosening of a cemented arthroplasty is a multifactorial phenomenon involving interfacial failure, bone failure, bone remodeling, and cement failure (6). It is not firmly established whether the drawbacks of bone cements contribute to the initiation or are the consequence of aseptic loosening of the implant (6). In spite of the many drawbacks of bone cement, the survival probabilities of recently cemented joint replacements are still high. Currently, cemented total hip arthroplasty shows survival rates of 90% at 15 years and 80–85% at 20 years (10,15,17–21). Increasing bone cement properties along with improving cementing techniques and implantation methods may further extend cemented implant longevity.

In recognizing the drawbacks of bone cement usage, there have been considerable efforts to secure the implants without using cement. Early noncemented prostheses were the press-fitted or screwed-in types (10). The press-fit techniques must lead to good initial fixation; otherwise, mobility will occur and this will facilitate wear and/or formation of fibrous tissue. Such techniques have limited successes due to a number of reasons, including bone resorption, geometrical constraints, and increased operational fractures. Noncemented porous coated prostheses were also introduced to provoke bony ingrowth for improved fixation. The noncemented prostheses are used predominantly in younger patients (< 60 years), where it is assumed that these prostheses eventually simplify a revision operation (10). Bone ingrowth strategies are not appropriate for older patients. Research indicates that some of the noncemented devices have failed, but others are doing well in the mid- to long- term (10). The clinical applications of cementless total hip and knee arthroplasties induce a new set of problems, including perioprosthetic osteolysis, high thigh pain, and failure of the bone–implant interface (6). Thus, there is currently a resurgence of interest in bone cement (6). Definite conclusions about the ultimate clinical performances of cement or cementless fixation devices require longer term studies (10). The debate is still open as to which fixation method is best. The development of cementless modes of fixation is an area of active research and clinical practice; however, acrylic bone cement continues to be the most commonly used nonmetallic implant material by orthopedic surgeons (6,11).

The literature on bone cement is voluminous with respect to its material development, manufacturing, thermal response, chemical and biological effects to bone, and its short- and long-term physical and mechanical properties (static, fatigue, etc.). This article discusses some of these aspects, especially on cement's material characteristics. For more ample assessment, the readers should refer to other excellent comprehensive reviews [e.g., Krause (3,11), Lewis (6,22), Kuhn (2), Saha (23), Kenny (5), Deb (24), Hasenwinkel (15), Serbetci and Hasirci (16)]. The article is arranged into several sections. It begins with the description of bone cement compositions, followed by a section on cement setting procedure and cementing technique. Then, the thermal and volumetric change effects are discussed. The final section focuses on the physical and mechanical properties of cement. Finally, the article ends with a brief summary.

CEMENT COMPOSITIONS

There are a number of bone cements [> 60 types (2)] available to the orthopedic community. Some popular cements currently available in the United States are given in Table 1 (2,6,11). Most of the present commercial bone cements have similar compositions (Table 2) (2,11,25). The presently used form of bone cement is predominantly the same as the one Sir John Charnley introduced. All acrylic bone cements on the market are chemically based on the identical basic substance: methyl methacrylate (MMA) (2). Pure MMA exhibits a shrinkage of ~ 21% during polymerization (2), and the polymerization temperature can increase to 100–120°C. Such a high shrinkage is intolerable for use in bone cement (2). For this reason, bone cements are offered as two-component systems in the marketplace: a prepolymerized powder and a liquid mm monomer (2). The MMA in aqueous suspension is prepolymerized in easily cooled reaction boilers. The polymer, obtained in the form of tiny balls (< 150 μm), is easily dissolved in the MMA. By using the prepolymerized polymer powder, both the shrinkage of the sample and the temperature of the reaction can be considerably decreased. In most bone cements on the market, the mixing ratio is two to three parts powder to one part monomer. This reduces the shrinkage and the generation of heat by at least two-thirds, as only the monomer is responsible for these reaction symptoms (2).

Table 1. List of Popular Commercial Bone Cements Currently Available in the United States[a]

Bone Cements	Manufacturer or Distributor
CMW1	Depuy, Warsaw, IN
CMW3	Depuy, Warsaw, IN
Palacos R	Smith and Nephew, Memphis, TN
Simplex P	Stryker Howmedica Osteonics, Rutherford, NJ
Osteobond	Zimmer, Warsaw, IN
Zimmer dough-type	Zimmer, Warsaw, IN

[a] See Refs. 2,6, and 11.

Usually, the solid part of bone cement consists of prepolymerized PMMA beads ranging in size from 1 to 150 μm. Other kinds of polymers sometimes are added, including poly(ethyl acrylate), poly(methyl acrylate), poly (styrene), and poly(butyl methacrylate). Free radicals of benzoyl peroxide (BPO) are present within the beads as remnants from the emulsion polymerization process (the process by which most of the beads are manufactured). An additional amount of BPO is mixed with the solid to obtain 1–2.5% by weight benzoyl peroxide. In addition, bone cements generally contain ~ 10–15% by weight barium sulfate, zirconia, or other additive. The presence of barium sulfate or zirconium dioxide in the powder is necessary for

Table 2. Compositions of Commercial Bone Cements Currently Available in the United States[a,b]

Liquid component	
Methylmethcrylate (monomer)/ Butylmethacrylate (binding agent)	~ 98
Activator/Co-initiator: Dimethyl-paratoluidine	0.4–2.75
Stabilizer/inhibitor/radical catcher: Hydroquinone, Ascorbic acid	15–75 ppm
Coloring: Chlorophyll	267 ppm
Powder	
Poly(methyl methacrylate)/copolymer	~ 90
Initiator: Benzoyl peroxide	0.5–3
Opacifier: $BaSO_4$ or ZrO_2	10–15%
Coloring: Chlorophyllin	200 ppm
Antibiotics: Gentamicin, erythromycin, and colistin	

[a] Compositions are in percent (w/w) except where stated otherwise.

[b] See Refs. 2,6,11 and 25.

a clinical reason. The original bone cements, which did not contain radiopacifiers could not be visualized on radiographs. The main components in the liquid phase are MMA, and, in some bone cements, other esters of acrylic acid or methacrylic acid, one or more amines (as activators for the formation of radicals), a stabilizer and, possibly, a colorant (2). The amine in the bone cement, *N,N*-dimethyl-*p*-touluidine (DMPT), acts as an accelerator. The liquid component also consists of 50–100 ppm hydroquinone, which inhibits the polymerization reaction within the monomer and allows for storage of the liquid component. Some cement also contains chlorophyll that gives it a green color. This allows better distinction from body tissues during surgery.

Prosthesis-related infection is described as a devastating failure scenario of a cemented orthopedic implant. Infectious complications of a cemented prosthesis lead to a deterioration of function and increase pain. Buchholz and Engelbrecht first reported on the possibilities of mixing antibiotics in bone cement in 1970 (17). They considered gentamicin sulfate to be the antibiotic of choice because of its wide-spectrum antimicrobial activity, its excellent water solubility, its thermal stability and its low allergenicity. Apart from gentamicin, other antibiotics have also been used as an additive to bone cement. The combination of erythromycin and colistin is an example that made it to a commercial product (17). In most cases, the manufacturers make their antibiotic cements by simply mixing antibiotic to a plain cement version they have (2,15,16).

Currently, bone cement fracture is regarded as a major factor in the mechanical failure of implant fixation (26–28). It is directly related to the mechanical properties of the cement, especially the resistance to fracture of the cement in the mantle at the cement–prosthesis interface or the cement–bone interface. Thus, many investigators have attempted to incorporate second phase materials including polyethylene (29), hydroxyapatite (30), PMMA (31), Kevlar (32,33), carbon (34–36), titanium (37), and steel (38–40) to improve the fatigue properties and fracture toughness of the PMMA. Most of the results regarding the properties of these composite materials have been encouraging; however, the biocompatibility issues regarding some of these fibers are as yet unresolved (6). Consequently, none of the commercial bone cements have incorporated these fibers in cements on the market.

CEMENT SETTING AND CEMENTING TECHNIQUE

Most structural materials are fabricated under controlled conditions at a factory, then transported and assembled on site. Bone cement is one of the few structural materials that are created *in situ*. The surgeon prepares the bone cement directly at the operation table according to the manufacturer's instructions. All of the cements are supplied in sets of the polymer powder and the monomer liquid components packed in two separate containers within a package. At the time of surgery, the liquid monomer and powder are mixed, the DMPT reacts with the BPO to generate free radicals, which in turn are used in the additional polymerization of the MMA monomers to form PMMA. Polymer chains from the PMMA become available for free radical polymerization and entanglements of these chains with newly formed chains lead to an intimate connection between the newly formed PMMA with what was already present. The resulting product is a doughy mixture that later polymerizes to a hard and brittle substance.

Table 3. Four Phases of Bone Cement Polymerization Process[a]

Phases	Time Duration, min	Characteristics
I. Mixing	1–2	Wetting Cement relatively liquid (low viscous)
II. Waiting	2–3	Swelling + polymerization Increase of viscosity Polymer chains, less movable Sticky dough
III. Working	5–8	Chain propagation Reduced movability Increase of viscosity Heat generation
IV. Setting	2–6	Chain growth finished No movability Cement hardened High temperature

[a] See Ref. 2.

The curing process of acrylic PMMA bone cement can be divided into four basis steps (2): the mixing, waiting, working, and hardening phase. The characteristics of these phases, well described by Kuhn (2), are shown in Table 3. The time at which the cement does not stick to the surgeon's glove is referred to as dough time (Fig. 1). The waiting phase ends at this time point. This occurs ~2–3 min after the beginning of mixing for most PMMA cements in an ambient temperature of 23 °C (2,11). The working phase is the time during which the surgeon can easily apply cement to the femur. For manual application, the cement must no longer be sticky during this phase, and the viscosity must not to be too high. With the use of mixing systems, the user needs not to wait until the cement is no long sticky. The working time from the end of dough time to the cement is too stiff to manipulate is usually 5–8 min. The cement will fully polymerize to a hardened mass within 8–12 min after initial mixing (2,11).

The quality of the cement dough produced in the operation room will have considerable influence on the clinical long-term result of a cemented prosthesis. Mixing of cements is an important step, as it has a noticeable influence on the mechanical properties of acrylic bone cements (2,6,24). In the 1970s, loosening of the femoral stem was the most common reason for total hip arthroplasy revision, often occurring 5–10 years postoperatively with early component design and cement technique (21). Early methods of cement preparation involved hand mixing in open air of the MMA monomer with the prepolymerized powder mixture. A slurry was formed that could be hand patted or injected into the femoral canal. Many air bubble voids were



Figure 1. A typical temperature changes with respect to time during cement polymerization. Time zero is designated when the monomer liquid is added to the polymer powder.

created in the mixture during the hand-mixing process. To address this problem in cemented arthroplasty, intensive studies have attempted to improve the technique of cemented stem insertion (21). This results in advancing the cementing techniques from first generation cementing to second and third generation cementing (Table 4). Traditionally, bone cement was mixed using a spatula–bowl arrangement (first generation), which can have the consequence of introducing a high degree of porosity into the cement structure. In addition, the person mixing the cement was exposed to a high level of methyl methacrylate vapors. Second-generation cementing mainly consisted of the use of a canal plug, a cement gun and a high strength cement (21,41,42). Injection guns have been advocated for application of bone cement because long slender injection tips are useful for inserting the cement deep into the cavity, instead of trying to apply it by hand. Gun application also reduces the tendency to form laminations and voids in the cement and also reduces the inclusion of blood into the cement. Substantial improvements in stem survival were reported using such techniques, resulting in stem loosening rates of $< 5\%$ at 5–10 years (21,42). The introduction of porosity reducing measures marked the start of third generation cementing techniques. Cracks may initially occur at the voids in bone cements, which act as stress concentration points (24). Vacuum mixing is a typical ways to achieving pore reduction. Other third-generation developments in cementing techniques are the use of prosthesis positioning devices that ensure correct placement of the prosthesis, pressurization, and enhanced surface finishes (21,43). Attempts to improve cement-bone interlock using techniques such as endosteal preparation, retrograde cement insertion and cement pressurization improve implant survival. Improving cementing techniques have assisted to dramatically decrease the number of failure in the last three decades. Currently, cemented total hip arthroplasty shows survival rates of 90% at 15 years and 80–85% at 20 years (10,17,18,21).

Table 4. Developments in Cementing Techniques

Generations	Techniques	Time
1st Generation	Finger packing No cement restrictor	1960s
2nd Generation	Intramedullary femoral plug Cement gun High-strength cement	1970s
3rd Generation	Pressurization of cement after insertion Porosity reduction (vacuum mixing) Surface roughening or texturing Precoating Avoiding trochanteric osteotomy	mid-1980s–

POLYMERIZATION HEAT

Bone cement generates significant thermal energy during cement setting (an energy of 52 kJ·mol^{-1} of MMA (2)) and this may result in a temperature increase in the cemented system. The exothermic response of the bone cement can be characterized according to American Society for Testing and material (ASTM) standard F451 (44) or international standard ISO 5833. In the ASTM test, a package of cement is mixed at an air conditioned room ($23 \pm 1\,^{\circ}$C, $50 \pm 10\%$ relative humidity) as directed by the manufacturer's instructions. Within 1 min after doughing time, ~ 25 g of the dough is then gently packed into an ASTM specified test mold to achieve a 60 mm diameter with 6 mm thick disk cement mantle (44). The setting curve of temperature change with respect to time (Fig. 1) is recorded with a thermocouple (usually No. 24 gage wire k-type thermocouple) placed at the cement mantle center from the onset of mixing until cooling is observed. The setting time is defined as the time from initial mixing to the time at which the temperature of the polymerising mass has reached half of the maximum temperature (peak temperature) (44). The setting times range from 6 to 14 min and peak temperatures range from 54 to 83 °C for the popular commercial bone cements (2,11). A number of variables will affect the measured setting time and peak temperature, including the powder/liquid ratio of the cement, cement preparing method, cement mantle thickness, the initial temperature of the cement, and the ambient conditions (11). By mixing bone cement with Howmedica Mix-Kit I system and the Zimmer Osteobond vacuum system, Dunne and Orr (45) found peak temperatures increased from 36 to 46 °C and 41 to 59 °C for Palacos R and CMW3 bone cement, specifically. Cold cement in a cold room takes longer to set. Precooling cement prior to use extends the cure time and decreases the peak temperature (46). Using a test mold and cementing techniques that simulated a clinical situation, Iesaka et al. (47) showed that the peak temperatures at the bone–cement interface were 53.1, 50.2, and 48.8 °C, while the polymerization time was 4.1, 8.3 and 11.2 min, when the monomer component of bone cement was initially at 37, 23, and 4 °C, respectively. Research also found that bone cement thickness has significant effects on the thermal responses. Meyer et al. (48) found a setting temperature of 60 °C with 3 mm thick specimens of Simplex R, and 107 °C with 10 mm thick specimens. Sih and Connelly (49) showed that the temperatures were 41, 56, and 60 °C for cement thicknesses of 1, 5, and 6-7 mm, respectively. Vallo (50) and Li et al. (51) demonstrated similar results with finite element modeling. Test mold materials also affect the measured setting time and peak temperature (50,51). According to the ASTM methodology, there is no limit to the setting time. However, the maximum allowable temperature for bone cements is 90 °C (44). There are limits stipulated for setting time and doughing time with ISO 5833 Standard.

The importance of temperature rise is that it may result in thermal necrosis of the bone tissue surrounding the implant (2,11,52–56). *In vitro* studies have shown that maximum temperature of bone cement can be reach higher than 100 °C, varied between 37 and 122 °C in different reports (57). Wang et al. (58) measured four different brands of bone cement (Palaces R, Simplex P, Sulfix, and CMW 1) during polymerization and the peak temperature in the cement was 46–124 °C. Clinical tests show a considerable lower temperature in the body (2,55). The bone-cement interface temperatures have ranged from 35 to 70 °C (2,11,52,3,54,55,57,59). Reasons for this observation are the thin layer of cement (~3–5 mm) and the blood circulation and heat dissipation in the vital tissue connected with it (2). Moreover, further heat dissipation of the system is attained via the prosthesis (2). Belkoff and Molloy (59) found that peak temperatures at the anterior cortex ranged from 44 to 113 °C, in the center ranged from 49 to 112 °C, and 39 to 57 °C at the spinal canal in the *ex vivo* vertebroplasaty tests. Toksvig-Larsen (57) performed tests with 31 total hip replacements and showed that the maximum temperature in the acetabulum ranged from 38 to 52 °C and in the femur from 29 to 56 °C. It has been found that not only the temperature, but also the exposure time plays a significant role in direct thermal cell necrosis (52,60–63). The findings of Moritz and Henriques (60) suggest that epithelial cell necrosis occurs 30 s after exposure to a temperature of 55 °C and 5 h after exposure to 45 °C. Lundskog (61) roughly confirmed these trends for bone cells, although he found a slightly lower threshold level. For example, he observed bone cell necrosis after 30 s at 50 °C. He also established that the regenerative capacity of the bone tissue is only damaged after exposure to temperatures of 70 °C and above. Eriksson and Alberksson (64) found the temperature threshold for impaired bone regeneration to be in the range of 44–47 °C for 1 min exposure. Thermal damage to bone tissue caused by cement polymerization cannot be ruled out and attempts to lower the potential degree of thermal necrosis have been investigated. To reduce the risk of thermal injury it is necessary to avoid exposing bone to temperatures above a certain threshold (62). The thermal responses rely on the quantity of heat produced by the bone cement (cement formulations and cement volume, etc.), rate of heat produced and how the heat conducts (55). The temperature peak can only by influenced to a small extent by adding heat-conducing radiopaque media or by slightly changing the chemical composition of the liquid (2). This, will, however, result in quite different dissolution properties with the polymer, which means it will result in different working properties and, usually, a significant reduction in mechanical stability (2). The thicker the cement mantle, the greater the volume of material and hence the more heat generated. However, simply reducing the thickness of the mantle is not a favorable option as the mechanics of the joint is affected by this. A slightly reduced level of heat generation has been shown by vacuum mixing the bone cement (45,57). Precooling the cement constituents prior to mixing increases the setting time, but has only minor effects on the maximum temperature of the cement (56). The use of a precooled femoral prosthesis did not affect the peak temperature as well (56,57). To avoid local tissue damage, surgeons may irrigate the implant with ice-cold saline during the polymerization process to decrease both the duration and the level of temperature elevation. Without cooling, the temperature was 49 °C (41–67) at the bone–cement interface, while it decreased to 41 °C (37–47) with water cooling in 19 cases of arthroplasties (65). Investigations on the potential tissue thermal necrosis have obtained varied results: while thermal bone necrosis due to cement curing heat has not been widely reported, some studies showed that thermal necrosis of bone did occur (52,54,59). Nevertheless, few would disagree that a clear understanding of the potential thermal necrosis problem requires further investigations.

VISCOSITY

During the working stage of the cement, its viscosity must be low enough to make it easy to force the cement dough through the delivery system and cause it to flow and penetrate into the interstices of the bone surface in a very short time (6,11,22). *In vitro* determination of viscosity is usually accomplished with the use of a capillary extrusion or rotational rheometer (6,11,22). The viscosity of the material can be determined by causing the material to flow at a specific shear rate and measuring the shear stress of the fluid against the stationary instrument (11). Viscosity varies across cements. The dynamic viscosity of its dough during the mixing period has been used to categorize bone cement materials into low viscosity brands (e.g., Osteopal), medium-viscosity brands (e.g., Simplex P), and high viscosity brands (e.g., Palacos R) (22). High viscosity bone cements typically have a doughy consistency; low viscosity cements are similar to viscous oil in consistency. Low viscosity cements have a long liquid phase, or low viscosity wetting phase. The cement remains sticky for quite some time. Viscosity increases rapidly during the working phase, and the doughy cement becomes warm and sets quickly. High and low viscosity bone cements have different handling characteristics and require different cementing techniques. For optimal results, it is necessary to observe the specific mixing instructions for a given bone cement in combination with a given mixing system. Although some researchers suggest that low viscosity brands may have longer fatigue lives compared to high viscosity ones, some report no significant difference (22).

POROSITY, VOLUMETRIC CHANGES, AND RESIDUAL STRESS

Polymerized bone cement is a porous material, containing macropores (pore diameter > 1 mm) and micropores (pore diameter ≈ 0.1–1 mm) (6). The degree of porosity varies with cement brands and mixing methods. Jasty et al. (66) found that the porosities were 11.99% (CMW), 9.70% (Palacos R), 9.39% (Simplex P), 12.38% (Zimmer Regular), and 5.00% (Zimmer LVC) using manual mixing, while they were 6.00% (CMW), 4.25% (Simplex P), 6.00% (Zimmer Regular) and 4.15% (Zimmer LVC) with centrifugation. For CMW 1 cement, Muller et al. (67) found that the porosity decreased from 6.67 to 1.28% when using vacuum-mixing instead of hand-mixed methods. The pores generated in polymerized bone cement have been attributed to several sources (6,68–72). It may result from the air that is initially present in the powder interstices; entrapped during blending, mixing, transfer, or delivery; or entrained during insertion of the metal stem. Evaporation of the liquid monomer at the high temperatures of polymerization may contribute. Another aspect of porosity development is polymerization shrinkage.

The presence of pores in the polymerized cement may affect its mechanical properties. Pores may act as stress risers and initiation sites for cracks, rendering the cement susceptible to early fatigue failure (6). However, pores also may play a role in blunting crack propagation, thereby prolonging the life of the implant (73). *In vitro* experiments, the static and fatigue strength of bone cement both usually decrease with increased porosity (6,22,23,69,70). Reducing the porosity of both bulk cement and its interfaces should be of clinical benefit. Several methods of reducing the porosity of the bone cement have been developed (66). One commonly used method of void reduction is the centrifugation of a chilled, premixed bone cement prior to insertion into the bone. The other one is the mixing of the bone cement in a vacuum environment. Both techniques have been shown to substantially reduce the porosity of bone cement. It has been observed that mixing procedures plays a significant role in determining the quality of bone cement produced (2,74,75). The influence of vacuum mixing on the pores results in a 15–30% improvement of the bending strength of Palacos R while centrifuging Simplex P cement reduced its porosity from 9.4 to 2.9%. Experiments have shown that relative to hand mixing, centrifugation or vacuum mixing leads to a substantial reduction in porosity (2,6). The extent of such a reduction depends on many mixing variables, including mixing system, monomer storage temperature, vacuum pressure and centrifugation speed, and durations. In the hand-mixing process, air bubbles are mixed into the dough by thorough mixing. The porosity of the material is high and mechanical stability is endangered. Slower mixing of cement over a shorter time decreases air voids within cement and thus improves the strength characteristics. A high degree of porosity is found to exist in cement that is inadequately mixed (74). Monomer bubbles can easily appear, which may develop during the evaporation of the monomer while evacuating the system or later during polymerization under high pressure by the faulty use of vacuum-mixing systems.

Cement porosity distributions, especially at the bone–cement interface, may affect the cemented system. There is strong evidence that cracks in the cement are initiated at voids, particularly at the cement–prostheses interface (69). The preferential formation of voids at this site results from shrinkage during bone cement polymerization and the initiation of this process at the warmer bone–cement interface, which causes bone cement to shrink away from the prosthesis (2,68,69). It is expected that a reversal of polymerization direction would shrink the cement onto the prosthesis and reduce or eliminate the formation of voids at this interface (69). One innovative surgical approach to affect this behavior is to preheat the prosthesis prior to implantation. Results indicated that voids near the cement–prosthesis interface decreased significantly (69,76). The porosity at the cement–prosthesis decreased from 16.4 to 0.1% when the prosthesis was preheated to 37°C from room temperature, 23 °C. Additionally, the residual stress due to such polymerization curing was shown to decrease significantly at the cement–prosthesis interface (77). Studies also showed that preheating the prosthesis prior to implantation is unlikely to produce significant thermal damage to the bone when compared to implanting a prosthesis initially at room temperature (46,69). However, this procedure may induce more voids at the bone–cement interface, and its effects on the damage at this region should be studied (69,78).

The conversion of the monomer molecules into a polymer network is accompanied with a closer packing of the molecules, which leads to bulk contraction (68,79). A number of devices for determining the volumetric changes have been applied, including using a mercury dilatometer or a water displacement dilatometer (79,80). Theoretical calculations predict that bone cement polymerization will produce a volumetric shrinkage of 8% (81). Muller et al. (67) found volume shrinkages of CMW 1 bone cement were 3.43 and 5.99% with hand and vacuum mixing, respectively. Gilbert et al. (68) found shrinkages of Simplex P cement were 5.09 and 6.67%, respectively. The measured volume shrinkage is less than the theoretical prediction. This can be explained by void growth during polymerization (67).

In a situation where a curing material is bonded on all sides to rigid structures or constrained, bulk contraction cannot occur freely, and shrinkage must be compensated for by some kind of volume generation. This can come from a strain on the material and mainly for dislodgement of the bond, increase in porosity or internal loss of coherence (79).

Table 5. Comparison of the Values of Three Mechanical Properties of Six Different Bone Cements Under Same Test Regimes[a]

Cement Brands	ISO 5833 Bending Strength, MPa	Bending Modulus, MPa	Compressive Strength, MPa	DIN53435 Bending Strength, MPa	Impact Strength, $kJ{\cdot}m^{-2}$
CMW1	67.0	2634	94.4	86.2	3.7
CMW3	70.3	2764	96.3	72.4	2.9
Palacos	72.2	2628	79.6	87.4	7.5
Simplex P	67.1	2643	80.1	70.5	3.9
Osteobond	73.7	2828	104.6	80.1	3.5
Zimmer dough	62.5	2454	75.4	77.0	5.0

[a] See Ref. 2.

Shrinkage of the polymerizing cement *in vivo* (i. e., a constrained state) therefore might result in the development of porosity, both at the interfaces and inside the bulk cement. Thus, polymerization shrinkage may be a significant factor in porosity development (68). On the other hand, polymerization may induce high residual stresses. Shrinkage stress occurs when the material contraction is obstructed and the material is rigid enough to resist sufficient plastic flow to compensate for the original volume (79). The process of cement curing is a complex solidification phenomenon where transient stresses are generated and the residual stresses vary with different initial and boundary conditions during curing. A number of approaches have been used to estimate or measure the level of shrinkage stress in bone cement around femoral replacements, including theoretical model, finite element analysis, strain-gage methods and photoelastic methods (52,77,82–88). Currently, the subject of residual stress has often been neglected because it is assumed that residual stress will relax due to the viscoelastic properties of the cement. However, transient and residual stresses are believed to affect cement mechanical responses. Inclusion of the residual stress at the interface resulted in up to a four-fold increase in the von Mises cement stresses compared to the case without residual stresses (83,84). Recently, Orr et al. proposed that residual stresses are sufficient to initiate crack propagation in the cement before any load is applied (85). Lennon and Prendergarst have experimentally observed that residual stresses in the cement may induce cracking even before weight bearing of the cement (89). The initial residual stresses may have immediate effects influencing the possible initiation of cracks and debonding at the cement–prosthesis interface.

MECHANICAL PROPERTIES

Bone cement fills the space between the prosthesis and the bone; this connection is only a mechanical bond (1). Cement mechanical properties are therefore of particular significance for the performance of acrylic bone cement because cement must endure considerable stresses *in vivo*. There are many physical and mechanical properties of the cement that are considered germane to its clinical performance in the construct, including quasistatic tensile and compressive strength, modulus and ultimate strain, flexural strength and modulus, shear strength and modulus, fatigue properties (e.g., work of fracture, fracture toughness, fatigue resistance, fatigue crack propagation resistance), and creep (6). The mechanical properties of acrylic bone cement have been widely reported in the literature. Kuhn (2) investigated the static bending and compressive characteristics of a number of bone cements under the same test regimes (2). Test results of some of the most commonly used bone cement in United States are listed in Table 5. Osteobond cement was shown to have both the highest ISO 5833 bending strength and compressive strength among these six cement brands, while Zimmer dough has both the lowest ISO 5833 bending strength and compressive strength. All the measured bending strengths of the bone cement using the DIN53435 standard were larger than the ones using ISO 5833 standard, with Palacos R bone cement having the highest bending strength in this case. Harper and Bonfield (90) found a wide range of tensile strength (Table 6) and fatigue failure cycles (Table 7) results. They found that the Palacos R and Simplex P cements were significantly higher in tensile strength compared to the other cements tested with exception of CMW 3. There was no statistical difference between the values obtained for CMW 1 and Osteobond. The differences among the fatigue results for the different cements were much larger than those found with the static tensile results. The highest Weibull median fatigue cycles to failure obtained for Simplex P and Palacos R were considerably higher than found for Zimmer dough type. Harper and Bonfield (90) found that there was some correlation between the static and fatigue strengths, but the ranking of static strength does not exactly follow that of fatigue life. The fatigue results were found to correlated well to the clinical data (91): the order of success of implants with the cement brand was the same as that obtained from the fatigue test.

It has long been recognized that PMMA surgical bone cement undergoes viscoelastic (creep) deformation under physiological loads (92,93). Many studies have been performed to assess the viscoelastic properties of bone cement (6,23). Radiological observations of hip stems have shown subsidence of the stem within the cement mantle without visible cement fractures (94). Creep has been implicated in prosthesis subsidence, in particular subsidence of the femoral stem in hip replacements (6,95). Excessive subsidence can lead to prostheses loosening. Lu and McKellop (92) studied the effects of cement creep on the subsidence of

Table 6. Comparison of Tensile of Six Different Bone Cements[a]

Cement Brands	Ultimate Strength, MPa	Modulus of Elasticity, GPa	Strain at Fracture, %
CMW1	39.1	2.96	1.60
CMW3	44.7	3.53	1.36
Palacos	51.4	3.21	2.25
Simplex P	50.1	3.43	1.87
Osteobond	38.2	3.38	1.41
Zimmer dough	31.7	2.79	1.43

[a] See Ref. 90.

the stem and on the stress within the cement using a cyclic load and three interface bonding conditions (bonded, frictional, and debonded). Results showed that the creep deformation of the cement was accompanied by additional subsidence of the stem and a decrease in the stress components within the cement. The results agreed with an experimental study using stems cemented into cadaver femora (96). Cement creep would accumulate for the frictional stem–cement interface, resulting in 0.46 mm total stem subsidence and a 13% decrease in the stress within the cement (92). Ling et al. (97) concluded that, at least for smooth tapered stems, that substantial hoop and radial creep of the cement not only occurs, but also is essential for the optimum clinical performance of the prosthesis. On the other hand, a limited degree of creep may help in maintaining the cement–implant interface. Also, Harris (98) stated that creep of the cement mantle surrounding a hip prosthesis may be negligible under cyclic physiological loading. The role of creep of the bone cement on the chance of failure of the cement mantle is still a subject of controversy. Due to its viscoelastic nature, cement tested at different strain rates may have changing characteristics (11). There is still lack of tests of bone cement in ways that represent real-life loading patterns that mimic those experienced by the cement *in vivo* (99). The true understanding of the mechanical behavior of bone cement can only be attained if the testing procedure is truly representative (99).

There are considerable differences between the values of physical and mechanical properties of bone cement reported in the literature. This disagreement may be the result of cement type, cement preparation technique, specimen geometry, measurement technique, test parameters, and testing environment (11). Therefore it may be impossible to compare results from different investigations (90). However, results with specific conditions may be found in a number of the excellent comprehensively reviews (1–3,6,11,22,23). It has been shown that cement formulations play a significant role on the cement mechanical properties (Table 5). Also, the test methods will affect the values obtained, which can be easily seen by comparing the bending strength results using ISO 5833 standard to that using DIN 53435 standard (Table 5). Cement mixing methods (hand mixing, vacuum mixing, or centrifugation) have been shown to affect the physical properties of bone cement (74,100,101). Even with vacuum mixing, using different vacuum mixing systems have resulted in different bone cement porosity, static strength, and fatigue strength (75,102). The storage temperature of cement constitutive was shown to have minor effects on porosity and fatigue performance (100). Ishihara et al. (103) showed that the fatigue of bone cements at 1 Hz are shorter by one to two order of magnitude as compared with fatigue lives at 20 Hz. On the other hand, Lewis et al. (104) found that frequency (over the range used) did not exert a statistically significant effect on the fatigue life of cement tested in their investigations.

Table 7. Comparison of Fatigue Test Results of Six Different Bone Cements[a]

Cement Brands	Cycles to Failure	
	Range	Weibull Median
CMW1	3042–8835	4407
CMW3	5996–38262	16441
Palacos	18362–49285	27892
Simplex P	8933–93345	36677
Osteobond	5527–25825	16162
Zimmer dough	153–3978	781

[a] See Ref. 90.

SUMMARY

Acrylic bone cement has been widely used in orthopedic surgery. Currently, the cement is not without its drawbacks as discussed previously. One major research area focusing on modifications of cement formulations may lead to obtain more favorable cement mechanical properties and biological compatibilities. One example of these developments is to incorporate second phase materials (bioactive agents, reinforcement fibers, etc.) into the existing bone cement. Another approach to overcome cement weakness is to manipulate cement processing procedure and the surgical techniques. A good example is to reduce cement porosity by vacuum mixing techniques. It is worth pointing out that considerable research is needed to develop techniques for accurate characterizations of cement properties, monitoring cement curing process and evaluations of potential bone cement failure.

BIBLIOGRAPHY

Cited References

1. Walenkamp G, Murray DW. Bone cements and cementing technique. Berlin Heidelberg New York: Springer-Verlag; 2001.
2. Kuhn KD. Bone cement: up-to-date comparison of physical and chemical properties of commercial materials. Berlin: Springer-Verlag; 2000.
3. Krause W, Mathis RS. Fatigue properties of acrylic bone cements - review of the literature. J Biomed Mater Res-Appl Biomate 1988;22(A1):37–53.
4. Charnley J. Anchorage of the femoral head prosthesis to the shaft of the femur. J Bone Joint Surg 1960;43B:28–30.

5. Kenny SM, Buggy M. Bone cements and fillers: A review. J Mater Sci-Mater Med 2003;14(11): p 923–938.
6. Lewis G. Properties of acrylic bone cement: State of the art review. J Biomed Mater Res 1997;38(2):155–182.
7. NIH. Total hip replacement. NIH Consensus Statement 1994;12(5):1–31.
8. Cristofolini L. A critical analysis of stress shielding evaluation of hip prostheses. Crit Rev Biomed Eng 1997;25(4–5):409–483.
9. Chao E. Orthopaedic Biomechanics. Int Orthop (SICOT) 1996;20:239–243.
10. Huiskes R, Verdonschot N. Biomech Art Joints: the Hip, Basic Orthopaedic Biomechanics. In: Mow VC, Hayes WC, editors. Philadelphia: Lippincott-Raven Publishers; 1997. 395–460.
11. Krause WR. Bone Cement, Acrylic. In: Webster JG, editor. Encyclopedia of Medical Devices and Instrumentation. New York: John Wiley & sons Inc.; 1988. p 491–500.
12. Wilcox RK. The biomechanics of vertebroplasty: a review. Proceedings of the Institution of Mechanical Engineers Part H. J Eng Med 2004;218(H1):1–10.
13. Phillips FM. Minimally invasive treatments of osteoporotic vertebral compression fractures. Spine 2003;28(15):S45–S53.
14. Heini PF, et al. Femoroplasty-augmentation of mechanical properties in the osteoporotic proximal femur: a biomechanical investigation of PMMA reinforcement in cadaver bones. Clin Biomech 2004;19(5):506–512.
15. Hasenwinkel J. Bone Cement. In: Wnek GE, Bowin GL, editors. Encyclopedia of Biomaterials and Biomedical Engineering. New York: Marcel Dekker; 2004. p 170–179.
16. Serbetci K, Hasirci N. Recent developments in bone cements. In: Yaszemski MJ et al. editors. Biomaterials in Orthopedics. New York: Marcel-Dekker; 2004. p 241–286.
17. Hendriks JGE, et al. Backgrounds of antibiotic-loaded bone cement and prosthesis-related infection. Biomaterials 2004;25(3):545–556.
18. Murray DW, Carr AJ, Bulstrode CJ. Which Primary Total Hip-Replacement. J Bone Joint Surg-Br Vol 1995;77B(4): 520–527.
19. Nafei A, et al. Survivorship analysis of cemented total condylar knee arthroplasty: a long-term follow-up report on 348 cases. J Arthroplasty 1996;11:7–10.
20. El-Warrak AO, et al. A review of aseptic loosening in total hip arthroplasty. Veterin Compar Orthopae Traumatol 2001;14(3):115–124.
21. Barrack RL. Early failure of modern cemented stems. J Arthroplasty 2000;15(8):1036–1050.
22. Lewis G. Fatigue testing and performance of acrylic bone-cement materials: State-of-the-art review. J Biomed Mater Res Part B-Appl Biomater 2003;66B(1):457–486.
23. Saha S, Pal S. Mechanical-Properties of Bone-Cement-a Review. J Biomed Mater Res 1984;18(4):435–462.
24. Deb S. A review of improvements in acrylic bone cements. J Biomater Appl 1999;14(1):16–47.
25. Passuti N, Gouin F. Antibiotic-loaded bone cement in orthopedic surgery. Joint Bone Spine 2003;70(3):169–174.
26. Jasty M, et al. The Initiation of Failure in Cemented Femoral Components of Hip Arthroplasties. J Bone Joint Surg Br Vol 1991;73(4):551–558.
27. Hertzberg RW, Manson JA. Fatigue of engineering plastics. London: Academic Press; 1980.
28. Spector M. Biomaterial failure. Orthoped Clin N Am 1992;23(2):211–217.
29. Pourdeyhimi B, Wagner HD. Elastic and Ultimate Properties of Acrylic Bone-Cement Reinforced with Ultra-High-Molecular-Weight Polyethylene Fibers. J Biomed Mater Res 1989;23(1):63–80.
30. Harper EJ, Behiri JC, Bonfield W. Flexural and fatigue properties of a bone cement based upon polyethylmethacrylate and hydroxyapatite. J Mat Sci Mat Med 1995;6:799–803.
31. Gilbert JL, Net SS, Lauthenschlager EP. Self-reinforced composite poly(methylmethacryate): static and fatigue properties. Biomaterials 1995;16:1043–1055.
32. Pourdeyhimi B, Wagner HD, Schwartz P. A Comparison of Mechanical-Properties of Discontinuous Kevlar-29 Fiber Reinforced Bone and Dental Cements. J Mater Sci 1986;21(12):4468–4474.
33. Wright TM, Trent PS. Mechanical-Properties of Aramid Fiber-Reinforced Acrylic Bone Cement. J Mater Sci 1979;14(2):503–505.
34. Saha S. Strain-rate dependence of the compressive properties of normal and carbon-fiber-reinforced bone-cement. J Biomed Mater Res 1983;17(6):1041–1047.
35. Saha S, et al. Biomechanical Evaluation of Bony Defects Repaired with Normal, Carbon-Fiber, and Wire Reinforced Bone-Cement. Biomater Med Devices Artif Organs 1981;9(4):291–291.
36. Pilliar RM, et al. Carbon Fiber-Reinforced Bone Cement in Orthopedic Surgery. J Biomed Mater Res 1976;10(6):893–906.
37. Topoleski LDT, Ducheyne P, Cuckler JM. The Fracture-Toughness of Titanium-Fiber-Reinforced Bone-Cement. J Biomed Mater Res 1992;26(12):1599–1617.
38. Saha S, Kraay MJ. Bending Properties of Wire-Reinforced Bone-Cement for Applications in Spinal Fixation. J Biomed Mater Res 1979;13(3):443–457.
39. Kotha SP, et al. Fracture toughness of steel-fiber-reinforced bone cement. J Biomed Mater Res Part A 2004;70A(3):514–521.
40. Fishbane BM, Pond RB. Stainless steel fiber reinforcement of polymethylmethacrylate. Clin Orthop Rel Res 1977;128:194–199.
41. Mulroy WF, Harris WH. Revision total hip arthroplasty with use of so-called second-generation cementing techniques for aseptic loosening of the femoral component—A fifteen-year-average follow-up study. J Bone Joint Surg—Am Vol 1996;78A(3):325–330.
42. Mulroy WF, Estok DM, Harris WH. Total hip arthroplasty with use of so-called second-generation cementing techniques—A fifteen-year-average follow-up study. J Bone Joint—Am Vol 1995;77A(12):1845–1852.
43. Faulkner A, et al. Effectiveness of hip prostheses in primary total hip replacement: a critical review of evidence and an economic model. Health Technol Asess 1998;2(6):1–146.
44. ASTM, ASTM Standard Specification for Acrylic Bone Cement F451-99a; 1999.
45. Dunne NJ, Orr JF. Curing characteristics of acrylic bone cement. J Mater Sci Mater Med 2002;13(1):17–22.
46. Li CD, Schmid S, Mason J. Effects of pre-cooling and preheating procedures on cement polymerization and thermal osteonecrosis in cemented hip replacements. Med Eng Phys 2003;25(7):559–564.
47. Iessaka K, Jaffe WL, Kummer FL. Effects of the initial temperature of acrylic bone cement liquid monomer on the properties of the stem-cement interface and cement polymerization. J Biomed Mater Res: Appl Biomater 2003;68B:186–190.
48. Meyer PR, Lautenschlager EP, Moore BK. On the setting properties of acrylic bone cement. J Bone Joint Surg 1973;55A:139–156.
49. Sih GC, Connelly GM, Berman AT. The Effect of Thickness and Pressure on the Curing of Pmma Bone-Cement for the Total Hip-Joint Replacement. J Biomech 1980;13(4): 347–352.

50. Vallo CL. Theoretical prediction and experimental determination of the effect of mold characteristics on temperature and monomer conversion fraction profiles during polymerization of a PMMA-based bone cement. J Biomed Mater Res (Appl Biomater) 2002;63:627–642.
51. Li CD, Mason J, Yakimicki D. Thermal characterization of PMMA-based bone cement curing. J Mater Sci—Mater Med 2004;15(1):85–89.
52. Huiskes R. Some fundamental aspects of human joint replacement. Acta Orthopaed Scand 1980; (Suppl.) 185.
53. Mjoberg B. Fixation and Loosening of Hip Prostheses—a Review. Acta Orthopaed Scand 1991;62(5):500–508.
54. Mjoberg B, et al. Bone-Cement, Thermal-Injury and the Radiolucent Zone. Acta Orthopaed Scand 1984;55(6):597–600.
55. Dipisa JA, Sih GS, Berman AT. Temperature Problem at Bone-Acrylic Cement Interface of Total Hip-Replacement. Clin Orthopae Relat Res 1976;121:95–98.
56. Swenson LW, Schurman DJ, Piziali RL. Finite element temperature analysis of a total hip replacement and measurement of PMMA curing temperatures. J Biomed Mater Res 1981;15:83–96.
57. Toksviglarsen S, Franzen H, Ryd L. Cement Interface Temperature in Hip-Arthroplasty. Acta Orthopaed Scand 1991;62(2):102–105.
58. Wang JS, Franzen H, Toksviglarsen S. Does vacuum mixing of bone-cement affect heat-generation - analysis of 4 cement brands. J Appl Biomater 1995;6(2):105–108.
59. Belkoff SM, Molloy S. Temperature measurement during polymerization of polymethylmethacrylate cement used for vertebroplasty. Spine 2003;28(14):1555–1559.
60. Moritz AR, Henriques FC. The relative importance of time and surface temperature in the causation of cutaneous burns. Am J Pathol 1947;23:695–720.
61. Lundskog J. Heat and bone tissue: an experimental investigation of the thermal properties of bone and threshold levels for thermal injury. Scand J Plastic Reconstr Surg 1972;9:1–80.
62. Revie I, Wallace M, Orr J. The effect of PMMA thickness on thermal bone necrosis around acetabular sockets. Proc Instn Mech Eng 1994;208:45–51.
63. Nelson C, Krishnan E, Neff J. Consideration of physical parameters to predict thermal necrosis in acrylic cement implants at the site of giant cell tumors of bone. Med Phys 1986;13(4):462–488.
64. Eriksson AR, Albreksson T. Temperature threshold levels for heat induced bone tissue injury: a vital microscopic study in the rabbit. J Prosthetic Den 1983;50(1):101–107.
65. Wykman AGM. Acetabular Cement Temperature in Arthroplasty - Effect of Water Cooling in 19 Cases. Acta Orthopaed Scand 1992;63(5):543–544.
66. Jasty M, et al. Porosity of various preparations of acrylic bone cements. Clin Orthop Rel Res 1990;259:122–129.
67. Muller SD, Green SM, McCaskie AW. The dynamic volume changes of polymerising polymethy methacrylate bone cement. Acta Orthopaed Scand 2002;73(6):684–687.
68. Gilbert JL, et al. A theoretical and experimental analysis of polymerization shrinkage of bone cement: A potential major source of porosity. J Biomed Mater Res 2000;52(1): 210–218.
69. Bishop NE, Ferguson S, Tepic S. Porosity reduction in bone cement at the cement-stem interface. J Bone Joint Surg-Br Vol 1996;78B:349–356.
70. James SP, et al. A fractographic investigation of PMMA bone cement focusing on the relationship between porosity reduction and increased fatigue life. J Biomed Mater Res 1992;26(5):651–662.
71. James SP, et al. Extensive porosity at the cement-femoral prosthesis interface: A preliminary study. J Biomed Mater Res 1993;27:71–78.
72. Wixson RL, Lautenschlager EP, Novak MA. Vacuum mixing of acrylic bone cement. J Arthroplasty 1987;2:141–149.
73. Topoleski LDT, Ducheyne PI, Cuckler JM. Microstructural pathway of fracture in poly(methyl methacrylate) bone cement. Biomaterials 1993;14(15):1165–1172.
74. Dunne NJ, Orr JF. Influence of mixing techniques on the physical properties of acrylic bone cement. Biomaterials 2001;22(13):1819–1826.
75. Mau H, et al. Comparison of various vaccum mixing system and bone cements as regards reliability, porosity and bending stength. Acta Orthopaed Scand 2004;75(2):160–172.
76. Iessaka K, Jaffe WL, Kummer FJ. Effects of preheating of hip prosthesis on the stem-cement interface. J Bone Joint Surg—Am Vol 2003;85:421–427.
77. Li CD, Wang Y, Mason J. The effects of curing history on residual stresses in bone cement during hip arthroplasty. J Biomed Mater Res Part B-App Biomater 2004;70B(1):30–36.
78. Race A, et al. Early cement damage around a femoral stem is concentrated at the cement/bone interface. J Biomech 2003;36:489–496.
79. Davidson CL, Feilzer AJ. Polymerization shrinkage and polymerization shrinkage stress in polymer-based restoratives. J Den 1997;25(6):435–440.
80. Davies JP, Harris WH. Comparison of diametral shrinkage of centrifuged and uncentrifuged Simplex P bone cement. J Appl Biomater 1995;6:209–211.
81. Hass S, Brauer G, Dickson G. A characterization of polymethyl methacrylate bone cement. J Bone Joint Surg—Am Vol 1975;57:380–391.
82. Ahmed AM, et al. Transient and residual stresses and displacements in self-curing bone cement - part I: characterization of relevant volumetric behavior of bone cement. J Biomech Eng—Trans ASME 1982;104:21–27.
83. Nuno N, Amabili M. Modeling debonded stem-cement interface for hip implants: effect of residual stresses. Clin Biomech 2002;17:41–48.
84. Nuno N, Avanzolini G. Residual stresses at the stem-cement interface of an idealized cemented hip stem. J Biomech 2002;35:849–852.
85. Orr JF, Dunne NJ, Quinn JC. Shrinkage stresses in bone cement. Biomaterials 2003;24(17):2933–2940.
86. Ahmed AM, et al. Transient and residual stresses and displacements in self-curing bone cement-Part II: thermoelastic analysis of the stem fixation system. J Biomech Eng—Trans Asme 1982;104:28–37.
87. Roques A, et al. Quantitative measurement of the stresses induced during polymerization of bone cement. Biomaterials 2004;25:4415–4424.
88. Zor M, Kucuk M, Aksoy S. Residual stress effects on fracture energies of cement-bone and cement-implant interfaces. Biomaterials 2002;23:1595–1601.
89. Lennon AB, Prendergast PJ. Residual stress due to curing can initiate damage in porous bone cement: experimental and theoretical evidence. J Biomech 2002;35:311–321.
90. Harper EJ, Bonfield W. Tensile characteristics of ten commercial acrylic bone cements. J Biomed Mater Res 2000;53(5):605–616.
91. Malchau H, Herberts P. Prognosis of total hip replacement and revision rate in THR: A revision risk study of 148,359 primary operations. 65th Ann Meet Am Acad Ortho Surg 1998. New Orleans.
92. Lu Z, Mckellop H. Effects of cement creep on stem subsidence and stress in the cement mantle of a total hip replacement. J Biomed Mater Res 1997;34:221–226.

93. Verdonschot N, Huiskes R. Creep properties of three low temperature-curing bone cements: a preclinical assessment. J Biomed Mater Res 2000;53B:498–504.
94. Fowler GA, et al. Experience with the Exeter total hip replacement since 1970. Ortho Clin N Am 1988;19:477–489.
95. Morgan RL, et al. Creep behavior of bone cement: a method for time extrapolation using time-temperature equivalence. J Mater Sci: Mater Med 2003;14:321–325.
96. Weightman B, et al. The mechanical properties fo cement and loosening of the femoral component of hip replacements. J Bone Joint Surg Br 1987;69:558–564.
97. Ling RSM. The use of a collar and precoating on cemented femoral stems is unnecessary and detrimental. Clin Orthop Rel Res 1992;285:73–83.
98. Harris WH. Is it advantageous to strengthen the cement-matel interface and use a collar for cemented femoral components of total hip replacement. Clin Orthop Rel Res 1992;285:67–72.
99. Eden OR, Lee AJC, Hooper RM. Stress relaxation modeling of polymethylmethacrylate bone cement. Proc Instn Mech Eng 2002;216H:195–199.
100. Lewis G. Effect of mixing method and storage temperature of cement constituents on the fatigue and porosity of acrylic bone cement. J Biomed Mater Res 1999;48B:143–149.
101. Macaulay W, et al. Difference in bone-cement porosity by vacuum mixing, centrifugation, and hand mixing. J Arthroplasty 2002;17(5):569–575.
102. Dunne NJ, et al. The relationship between porosity and fatigue characteristics of bone cements. Biomaterials 2003;24(2):239–245.
103. Ishihara S, et al. On fatigue lifetimes and fatigue crack growth behavior of bone cement. J Mater Sci Mat Med 2000;11(10):661–666.
104. Lewis G, Janna S, Carroll M. Effect of test frequency on the in vitro fatigue life of acrylic bone cement. Biomaterials 2002;24:1111–1117.

See also BIOMATERIALS, TESTING AND STRUCTURAL PROPERTIES; HIP JOINTS, ARTIFICIAL; ORTHOPEDICS, PROSTHESIS FIXATION FOR; RESIN-BASED COMPOSITES.

BONE DENSITY MEASUREMENT

YIXIAN QIN
ERIK MITTRA
Stony Brook University
New York

INTRODUCTION

Chronic diseases, such as musculoskeletal complications, have a long-term debilitating effect that greatly impacts quality of life. Osteoporosis is a reduction in bone mass or density that leads to deteriorated and fragile bones and is the leading cause of bone fractures in postmenopausal women and in the elderly population for both men and women. About 13–18% of women aged 50 years and older, and 3–6% of men aged 50 years and older, have osteoporosis in the United States alone. These rates correspond to $4 \sim 6$ million women and $1 \sim 2$ million men who suffer from osteoporosis (1). One-third of women over 65 will have vertebral fractures and 90% of women aged 75 and older have radiographic evidence of osteoporosis (2–4). Another 37–50% of women aged 50 years and older, and 28–47% of men of the same age group, have some degree of osteopenia. Thus, approximately a total of 24 million people suffer from osteoporosis in the United States alone, with an estimated annual direct cost of over $18 billion to national health programs. Hence, early diagnosis that can predict fracture risk and result in prompt treatment is extremely important. Early identification of fracture risk, most commonly caused by osteoporosis-induced bone fragility, is also important in implementing appropriate treatment and preventive strategies. Indeed, the ability to accurately assess bone fracture risk noninvasively is essential for improving the diagnostic as well as therapeutic goals (i.e., assessing temporal changes in bone during therapy) for bone loss from such varied etiologies as osteoporosis, microgravity, bed rest, or stress-shielding around an implant.

Assessment of bone mineral density (BMD) has become as essential element in the evaluation of patients at risk for osteopenia and osteoporosis (2,5–8). Bone density was initially estimated from the conventional X ray by comparing the image density of the skeleton to the surrounding soft tissues. Although demineralized bone has an image density closer to soft tissues, dense mineralized skeletal tissues appears relatively white on an X-ray image. Hence, the mineral density of bone can be estimated by the degree of gray color of the X-ray image in the bone region. However, because of its resolution and variations generated in the X-ray image, it has been suggested that bone mineral losses of at least 30% are required before they may be visually measured using a conventional X ray (9,10). Growing awareness of the impact of osteoporosis on the elderly population and the consequent costs of health care, together with the development of new treatments to prevent fractures, have led to a rapid increase in the demand for bone densitometry measurements. Many image modalities and techniques have been developed to improve the quality and the accuracy of the measurement for bone mineral and dense assessment. Two major densitometry techniques are commonly used in assessing bone density, that is, radiography-based densitometry and ultrasound-based assessment.

RADIOGRAPHY-BASED DENSITOMETRY

To improve the sensitivities of X-ray images to bone density changes and assessment, several technologies have been developed. *Bone densitometry* is a term that is defined as a method for imaging density of bone. However, the “true” density is not applicable in the current radiography-based techniques. In the field of densitometry, the term “bone mineral density”, referred to as BMD, is related to the mass of bone in the tissue level, which includes both bone and marrow components as well as surrounding soft tissues. Furthermore, most densitometric techniques are projectional for the image formation that provides a two-dimensional image of the three-dimensional (3D) bone volume being measured. Therefore, the BMD defined from the projectional techniques is the mass of bone tissue mass (including marrow and/or soft surroundings) per unit area

Table 1. Radiography-Based Bone Densitometry[a]

Technique	ROI	Unit	Precision, %CV	Effective Dose, μSv
SXA	Total body	BMD ($g \cdot cm^{-2}$)	1	3
QCT	Spine	BMD ($g \cdot cm^{-2}$)	3	50–500
pQCT	Forearm	BMD ($g \cdot cm^{-2}$)	1–2	1–3
RA	Phalanx	BMD ($g \cdot cm^{-2}$)	1–2	10
SPA	Forearm	BMD ($g \cdot cm^{-2}$)	3–4	1–10
DPA	Total body	BMD ($g \cdot cm^{-2}$)	1	1–10
DXA	PA spine	BMD ($g \cdot cm^{-2}$)	1	1–10
	Proximal femur		1–2	1–10
	Total body		1	3

[a] See Refs. 5,6, 12–14.

in the image, not per unit volume of the tissue. Hence, what is actually measured is the apparent bone mineral density, which is defined by the bone mineral content contained in the area scanned, or expressed as gram per squared centimeter in unit. To detect osteoporosis accurately, several methods are developed for the noninvasive measurement of the skeleton for the diagnosis of osteopenia, osteoporosis, and/or the evaluation of an increased risk of fracture (11). These methods include single-energy X-ray absorptiometry (SXA), dual energy X-ray absorptiometry (DXA or DEXA), quantitative computed tomography (QCT), peripheral quantitative computed tomography (pQCT), radiographic absorptiometry (RA), dual photon absorptiometry (DPA), and single photon absorptiometry (SPA). There are two types of BMD measurements, peripheral BMD and central BMD. The peripheral BMD instruments are usually smaller, less expensive, and more portable than the central BMD. Central BMD is capable of measuring multiple skeletal sites, that is, the spine, the hip, and the forearm. Table 1 lists these methods currently available for the noninvasive measurement of the skeleton for the diagnosis of osteoporosis. These techniques differ substantially in physical principles, in the particular physical body sites (e.g., spine, hip, or total body), in the clinical discrimination and interpretation, and in availability of the facility and cost.

Single-Energy Densitometry

This instrumentation passes a beam of radiation through the limb of the body (e.g., forearm) and determines the difference between the incoming (or incident) radiation and the outgoing (or transmitted) radiation, referring to the attenuation. The higher the bone mineral content, the greater the attenuation. Mineral content can be calculated by the attenuation of the radiation. BMD can then be calculated by dividing the mineral content by the detected bone area. The relation between incoming and outgoing X-ray energy can be expressed as

$$I = I_0 \exp(-\lambda d) \tag{1}$$

where I_0 = incoming radiation intensity, I = transmitted radiation intensity, λ = mass attenuation coefficient, and d = area density of the attenuating materials ($g \cdot cm^{-2}$). The mass attenuation coefficient is a physical property that describes how much a given material attenuates and X-ray energy. If the attenuation coefficient can be experimentally determined, the equation becomes explicit, and the area density can be determined by

$$d = k \log(I_0/I) \tag{2}$$

where k is an experimentally determined constant for the attenuation coefficient.This technology is relatively simple and easy to understand. However, biological tissues and body are composed by multiple materials (e.g., bone, muscle, and other soft tissues). The accuracy of the technology is limited.

Single-Photon Absorptiometry

Bone density can be measured by passing a monochromatic or single-energy photon beam through bone and soft tissue. This procedure is referred as SPA. The amount of mineral content can be quantified by the attenuation of the beam intensity. After the photon beam attenuation is calculated, the value of the attenuation can be compared with a calibration parameter derived from a standard mineral content (e.g., using ashed bone of known weight). This procedure can finally determine the BMD with measured attenuation. Iodine-125 at 27 keV, or americium-241 at 59.5 keV, was initially used for generating of the SPA beam. SPA is rarely used in clinical practice today. SPA determined bone mineral content is calculated through uniform thickness of the soft tissue in the path of the beam. The targeted scan site (e.g., limb or forearm) had to be submerged in the water or a tissue-equivalent material, which limited the practical applications of the SPA. The advantages of this technique include a low dose of radiation, portable, and use for particular body sites with relatively precisely measurement. Although the SPA is an approximate method, the limitations of SPA include limited accuracy of the measurement, radiation, and used only on the particular peripheral sites, like forearm and heel.

Dual-Photon Absorptiometry

To overcome the limitations of single-energy or photon densitometry, if a dual radiation source was used, the influence of soft tissues could be eliminated. The basic principle involved in DPA for bone density measurement was similar to SPA. The degree of attenuation of the photon energy beam between incoming and outgoing energy through bone and soft tissue is quantified. As with SPA, the beam source was originally used, but with an isotope used, which emitted photon energy at two distinct photoelectric peaks. When the beam was passed through a region of the body with both hard and soft tissues, attenuation of the photon beam appeared to both photon energy peaks. The contributions of soft tissue to beam attenuation can be determined by the quantifications of the relative relations between two attenuations (15). Because of its capability to distinct bone from soft tissue, DPA has been used to quantify bone density in deep tissue and large skeletal areas where bone is surrounded by large volume of soft masses (e.g., spine and hip) (16). DPA was considered a major advance from SPA due to its ability to quantify BMD and mineral content in such deep areas like spine and hip, as well as its capability of quantifications of effects from soft tissues. However, DPA has many notable limitations. First, the maintenance of the beam source was expensive, which had to be replaced yearly. Second, the radioactive source decay increased as much as 0.6% per month, which added difficulties for the calibration. These factors may result in the precision of 2–4% for DPA measurements in the region of interests. This precision (e.g., 2%) would limit its clinical application, in which a great change (e.g., 5–6%) from the baseline value had to be observed before one could reach the 95% confidence level for the change of bone density. Nevertheless, the concept of dual-photon densitometry has impacted the development of new technologies such as DXA.

Dual-Energy X-ray Absorptiometry

Perhaps the most popular bone densitometry used in clinical practice is the DXA or DEXA. The basic principles of DXA are the same as DPA. To overcome the major limitation of DPA, it did not take long for manufacturers who originally had the DPA product to replace the decaying isotope beam source with a highly stable dual-energy X-ray tube. There are several advantages of using X-ray sources over radioactive isotopes (i.e., no beam decay concerned in the X-ray tube and no calibration required for correction of the drifting because of the source decay in the DPA). The fundamental basis for DXA is the measurement of the transmission through the body of X rays of two different photon energies. The radiation source is collimated to a pencil beam and aimed at a radiation detector placed directly opposite the objective to be measured (Fig. 1). The patients are positioned on a table in the path of the X-ray beams. Due to the dependence of the attenuation coefficient on atomic number and photon energy, assessment of the transmission factors and attenuations at two energies enables the 2D apparent density, that is, bone density per unit projected area, of two different types of tissues to be inferred (17–19). The X-ray source and detector pair is scanned back and forth across the region of interests in the body, generating annotation images, which the BMD is calculated as the ratio of the bone content to the measured area. Radiation dose to the patients is very low on the order of 1–10 μSv. The DXA system can measure the BMD of the spine, proximal femur, forearm, and the total body. Recent technology uses a fan beam geometry in the DXA scanners that can increase the speed and reduce the acquisition time (GE Medical System Inc.). The image quality of recent DXA has improved significantly via computational capability for better visualization. In addition to the body DXA scanners, recent technology has also adapted for development of lower cost, small, and particular site densitometries (Fig. 2). These systems are available to the clinic for specific body regions (e.g., spine, hip, leg, arm, and hand). The DXA systems are available for the diagnostic clinical use by many major manufacturers (e.g., GE Medical Systems of Madison, Norland, and Hologic Inc. of Bedford).



Figure 1. Scan path pattern for DXA densitometer using pencil-beam format.

The basic working principle of DXA and its ability to reduce the effects of soft tissue is to use two X-ray sources and mathematically solve the bone thickness and soft-tissue thickness (15). By using two X-ray energies, two equations can be derived by scanning the measurement site twice with low (L) and high (H) energies once at each.

$$I^L = I_0^L[\exp - (\lambda_b^L d_b + \lambda_s^L d_s)] \tag{3}$$

$$I^H = I_0^H[\exp - (\lambda_b^H d_b + \lambda_s^H d_s)] \tag{4}$$

where I_0 = incoming radiation intensity, I = transmitted radiation intensity, λ = mass attenuation coefficient, d = area density of the attenuating materials ($\mathrm{g \cdot cm^{-2}}$), and b and s refer to the bone and soft tissue. Two scans are usually performed simultaneously with either two energies or rapid switching between two energies. When the



Figure 2. DEXA machine for a whole-body scan (QDR4500 fan-beam scanner, Hologic Inc., Bedford, MA) (left). DEXA bone densitometry is widely used in.


Patient:
Patient ID: 140729 Age: 61 Sex: F
Exam Date: Mar 26 2001 Exams: 15
CT Scanner:
L2: BMD = 120.2 mg/cc

Figure 3. QCT allows selection of the region of interest.

attenuation coefficients for bone and soft tissue are known for both low and high energies, the apparent or area bone mineral density can be calculated as

$$d_b = \frac{(\lambda_s^L/\lambda_s^H)\log(I^H/I_0^H) - \log(I^L/I_0^L)}{\lambda_b^L - \lambda_b^H(\lambda_s^L/\lambda_s^H)} \tag{5}$$

The attenuation coefficient for bone is relative constant but varied to persons. The soft-tissue attenuation coefficient, however, is contributed by fat and other soft tissues and varied greatly in the body. This is the source for the errors generated in the measurement. The manufacturers usually provide phantoms for calibration for the system.

Traditionally, the focus of clinical bone evaluation has been apparent or area BMD as measured by DXA or DEXA (20–23). DEXA provides an effective way to measure BMD in a specific region of interest and is the most widely used diagnostic modality for assessing osteoporosis and osteopenia (8,24–26). However, in particular, DEXA suffers from several shortcomings. Although density (quantity) does positively correlate with strength (27,28) and fracture risk (29–31), anywhere from 10–90% of the variability in bone strength remains unexplained the (32). Additionally, as discussed below, the stereology of trabecular bone is one of its distinguishing features (especially with respect to its mechanical behavior), but because DEXA provides only a 2D image of apparent density, it is inherently limited in this regard. DEXA also suffers from an inability to differentiate trabecular from cortical bone. Although it is true that cortical bone also deteriorates with age (33,34), the effects of bone loss are more prevalent in trabecular bone due to its much higher surface area, and the greater net amount of bone mineral content in cortical bone can conceal small changes in the trabecular bone when measuring only BMD. Nevertheless, as one of the key factors that contribute to the bone's quality evaluation, BMD measured by DEXA is a most popular modality used in assessing the status of bone and the risk of fracture.

Quantitative Computed Tomography (QCT)

QCT provides the true volumetric 3D bone density ($\mathrm{mg \cdot cm^{-3}}$) compared with the 2D apparent or aeral density measurement with DEXA (35–43). Because of its high resolution, QCT can provide the measurement in the trabecular region (e.g., femoral neck and vertebral bodies) (39,40,44,45). Compared with DXA the advantage of QCT is the image-based cross-sectional anatomy, which allows for a selection of the region of interests (ROI) and a better assessment of geometrical properties (Fig. 3). Most CT systems provide a software package to automate the placement of the ROI within a particular body volume, e.g., vertebral bodies. QCT scans are generally performed using a single kilovolt setting (single-energy QCT). It is possible to use a dual-energy QCT, which can provide further improvement of the resolution, but at the price of poorer precision and higher radiation dose. New 3D volumetric techniques acquire datasets with which analysis of bone macroarchitecture may be further optimized. Due to its capability of high resolution, geometric and structural parameters determined in QCT may contribute to determine bone strength when integrated with other technology (i.e., finite element analysis). The advantage of spinal QCT is the high responsiveness of the vertebral trabecular bone to aging and disease, whereas the principal disadvantage is the cost of the equipment and the dosage received for the scanning (higher than DEXA).

Peripheral QCT (pQCT)

pQCT systems are available for measuring the forearm. The advantages of these devices are the capability of separating the trabecular and cortical bone of the ultradistal radius and of reporting volumetric density. Several clinical used pQCT devices are available (e.g., the Stratec XCT 2000, that are suitable for use in a physician's office or in primary care).

QUANTITATIVE ULTRASONOMETRY

Quantitative ultrasound (QUS) for measuring the peripheral skeleton has raised considerable interest in recent years. New methods have emerged with the potential to estimate trabecular bone modulus more directly. QUS provides an intriguing method for characterizing the

Table 2. Summary of Current QUS Devices for Calcaneus

Device	Performance	Resolution	Predict Parameter	Cost, $K
Sahara (Hologic)	Index	Nonimage	Z score	20–25
QUS-2 (Metra Biosystem)	Index	Nonimage	Z score	20–25
UBA 575 (Walker Sonix)	Index	Nonimage	Z score	20–25
Achilles (GE-Lunar)	Index + image	Image, 5 mm	Z score	40–50
UBIS 5000 (DMS)	Index + image	Image, 2 mm	Z score	30–35
DTU-one (Osteometer)	Index + image	Image, 2 mm	Z score	25–30
New SCAN	Image + index	Image, 1 mm	Stiffness, BMD, Z	20

material properties of bone in a manner that is noninvasive, nonionizing, nondestructive, and relatively accurate. The primary advantage of QUS is that it is capable of measuring not only bone quantity (e.g., BMD), but also bone quality (i.e., estimation of the mechanical property) of bone. Over the past 15 years, several research approaches have been developed to quantitate bone mass and structural stiffness using QUS (46–48). Preliminary results for predicting osteoporosis using QUS are promising, and it has great potential for widespread applications (including screening for prevention). As such, many QUS machines have been developed, and there are currently many different devices on the market. Most available systems measure the calcaneus using plane waves that use either water or gel coupling [e.g., Sahara (Hologic Inc., MA), QUS-2 (Metra Biosystems Inc., CA), Paris (Norland Inc., WI), and UBA 575 (Walker Sonix Inc., USA)] (Table 2). Recently, an image-based bone densitometry device for calcaneous ultrasound measurement is also made available using an array of plane ultrasound wave (GE-Lunar, Inc., USA). Using several available clinical devices, studies in vivo have shown the ability of QUS to discriminate patients with osteoporotic fractures from age-matched controls (49–51). It has been demonstrated that QUS predicts risk of future fracture generally as well as DEXA (51–54). However, there are several noted limitations, including the tissue boundary interaction, the nonlinear function of density associated with bone ultrasonic attenuation, the single index covering a broad range of tissues (including the cortical and trabecular regions), and the interpolation of the results. Recently, a focused ultrasound sonometer device was developed to obtain the likelihood of a broadband ultrasound attenuation (BUA) image in the human calcaneus region (center frequency 0.5 MHz, focus 50 mm) (55,56) (UBIS 5000, Diagnostic Medical Systems; and DTU-one, Osteometer MediTech). These devices provide ultrasound images in the calcaneus region, in which the parameter compares with DEXA data. Perhaps the major drawbacks of these ultrasound osteometers are low resolution and lack of physical interrelation with meaningful bone strength. Although only showing the correlation between BUA data and BMD, these devices mostly provide qualitative information for assessment of osteoporosis, not the true prediction for bone structural and strength properties. Therefore, QUS remains at a stage as a screening tool (Fig. 4), because of the nonuniformity of the porous structure in the bone tissue and its associated effects in resolution (14). Research attention is focused on developing systems to provide true images reflecting the bone's structural and strength properties at multiple skeletal sites, i.e., in the hip, which can provide a true diagnostic tool (instead of just for screening) that surpasses the radiation based DEXA machines.

If QUS bone densitometry can be developed to provide a "true" bone quality parameter-based diagnostic tool (i.e., directly related to the bone's structural and strength properties) and to target multiple and critical skeletal sites (e.g., hip and distal femur), QUS would have a greater impact on the diagnosis of bone diseases (e.g., osteoporosis) than current available bone densitometry. Research efforts are made in this regard (55–59). As an example, a new QUS modality, called the scanning confocal acoustic diagnostic system, has been developed (57–60), which is intended to provide true images reflecting the bone's structural and strength properties at a particular skeletal site at a peripheral limb and potentially at deep tissue like great trachanter. The technology may further provide both density and strength assessment in the region of interests for the risk of fracture (57–60).

Fundamental QUS Parameters in Bone Measurement

In an effort to use QUS for predicting bone quality, a variety of approaches have been explored with many studies published in the past decade, that have examined the utility of QUS and its potential application as a diagnostic tool for osteoporosis. The physical mechanisms of ultrasound applied to bone may include several fundamental approaches, [i.e., speed of sound (SOS) or ultrasonic wave propagating velocity (UV), sound energy attenuation

Figure 4. A QUS bone densitometry test in a heel region. Reproduced courtesy of GE-Lunar Inc.

(ATT), BUA, and critical angle ultrasound parameters] that closely relate to acoustic transmission in a porous structure. Most commonly, parameters for QUS measurement are BUA and SOS, which can be used to identify those persons at risk of osteoporotic fracture as reliably as BMD (52–54,61,62). It has been shown that both BUA and SOS are decreased in persons with risk factors for osteoporosis, that is, primary hyperparathyroidism (63–66), kidney disease (67), and glucocorticoid use (68,69). The proportion of women classified into each diagnostic category was similar for BMD and QUS. Using the World Health Organization (WHO) criteria to classify osteoporosis for BMD measurement using DEXA and QUS testing, approximately one third of postmenopausal women aged 50+ years with clinical risk factors were diagnosed as osteoporotic compared with only 12% of women without clinical risk factors. This suggests that the measurement of QUS with calcaneal BUA and SOS is to some extent the same as the BMD Z-score measurement.

Background of BUA in Trabecular Bone Measurement

BUA and SOS are currently two commonly used methods for QUS measurements, which make it potentially possible to predict bone density and strength. As an ultrasound wave propagates through a medium, BUA measures the acoustic energy that is lost in bone (unit: dB/MHz). The slope at which attenuation increases with frequency is generally between 0.2 and 0.6 MHz, and it characterizes BUA. The slopes of the frequency spectrum may reflect the density and structure of bone. Although relatively little is known about the fundamental interactions that determine ultrasound attenuation in bone, the potential sources contributing to the attenuation include absorption, scattering, diffraction, and refraction (70–73). Although absorption predominates in cortical bone attenuation, the mechanism of BUA in cancellous bone is believed to be scattering (14,74–76). The importance of scattering has been alluded to in the literature. Scattering is also suggested to contribute to the nonlinear variation in BUA with density observed in cancellous bone and a porous medium (77–79).

Background of SOS or UV for Bone Measurement

The strength of trabecular bone is an important parameter for bone quality. *In vitro* studies have correlated the ultrasound velocity with stiffness in trabecular bone samples (80–82). This indicates that ultrasound has the potential to be advantageous over the X-ray based absorptiometry in assessing the quality of bone in addition to the quantity of bone. The mechanism of SOS in predicting bone strength is believed to be due to the fact that the velocity of an ultrasound wave depends on the material properties of the medium through which it is propagating, but it also depends on the mode of propagation. By determining the wave velocity through a bone, the elastic modulus of bone specimens can be evaluated, or at least be approximated (80,83). When ultrasound travels through a porous material, e.g., trabecular bone, it carries information concerning material properties, such as density, elasticity, and architecture. A relationship exists between the ultrasound velocity (unit: m/s) and the material elasticity E and density ρ (14,80)

$$V = \sqrt{E/\rho} \tag{6}$$

The velocity with which ultrasound passes through normal bone is fast and varies depending on whether the bone is cortical or trabecular. Speeds of 2800–3000 $\mathrm{m \cdot s^{-1}}$ are typical in cortical bone, whereas speeds of 1550–2300 $\mathrm{m \cdot s^{-1}}$ are typical in trabecular bone.

It is demonstrated that trabecular bone strength is highly correlated with elastic stiffness (84). With the introduction of QUS, several new diagnostic parameters and experimental results, both *in vitro* and *in vivo*, have shown potential for evaluating not only bone quantity (i.e., BMD), but also bone quality (i.e., structure and strength). Two principal variables, BUA and UV, have been confirmed to identify those persons at risk of osteoporotic fracture as reliably as BMD from DEXA. However, SOS and BUA are related to bone density and strength as well as to trabecular orientation, the proportion of trabecular bone and cortical shell, the composition of organic and inorganic components, and the conductivity of the cancellous structure. Thus, QUS of trabecular bone depends on a variety of factors that contribute to the measured ultrasound parameters.

Other Bone Status Measurement Methods and Motivation to Assess Bone Quality

Beyond bone quantity, the quality (the integrity of its structure and strength) has become an equally or even more important measure to understand the bone structure and mechanical integrity. Most osteoporotic fractures occur in cancellous bone. Therefore, noninvasive assessment of trabecular bone strength and stiffness is extremely important in predicting the quality of the bone. The strength of the trabecular bone mostly depends on the mechanical properties of the bone at the local and bulk tissue level, and on its spatial distribution (i.e., the microarchitecture). A better understanding of the factors that influence bone strength is a key to developing improved diagnostic techniques and more effective treatments. To overcome the current hurdles, to improve the “quality” of the noninvasive diagnostic instrumentations, and to apply the technology for future clinical application, new clinical modality may concentrate in several main areas: (*1*) increasing the resolution, sensitivity, and accuracy in diagnosing osteoporosis through unique methods for improvement of signal/noise ratio; (*2*) directly measuring bone’s strength as one of the primary parameters for the risk of fracture; (*3*) generating real-time compatible imaging to identify local region of interest; (*4*) validating structural and strength properties with new modalities; and (*5*) predicting local trabecular and bulk stiffness and microstructure of bone, and generating a physical relationship between measurement and bone quality. In an attempt to achieve these goals, recent advances of emerging technologies are developed primarily for animal studies at this stage. These include high resolution pQCT, micro-MR-derived measures of structure, micro-CT-based BMD, and combined assessment of strength using geometry, density, and computational simulation. These methods will further lead to a better understanding of the progressive deterioration of bone in aging populations, and ultimately they may provide early prediction of fracture risk and associated musculo-skeletal complications such as osteoporosis.

ACKNOWLEDGMENT

This work has been kindly supported by the National Space Biomedical Research Institute (TD00207 and TD00405 to Y. Qin) through NASA Cooperative Agreement NCC 9-58.

BIBLIOGRAPHY

Cited References

1. Looker AC, Johnson CL. Prevalence of elevated serum transferrin saturation in adults in the United States. Ann Intern Med 1998;129:940–945.
2. Melton LJI. How many women have osteoporosis now?. J Bone Min Res 1995;10:175–177.
3. Melton LJI. Epidemiology of hip fracture: Implications of the exponential increase with age. Bone 1996;18:121S–125S.
4. Wahner HW, Fogelman I. The Evaluation of Osteoporosis: Dual Energy X-Ray Absorptiometry in Clinical Practice. London: 1994.
5. Genant HK. Current state of bone densitometry for osteoporosis. Radiographics 1998;18:913–918.
6. Kanis JA. An update on the diagnosis of osteoporosis. Curr Rheumatol Rep 2000;2:62–66.
7. Melton LJ III, Atkinson EJ, O'Connor MK, O'Fallon WM, Riggs BL. Bone density and fracture risk in men. J Bone Miner Res 1998;13:1915–1923.
8. Melton LJ III, Orwoll ES, Wasnich RD. Does bone density predict fractures comparably in men and women? Osteoporos Int 2001;12:707–709.
9. Sartoris DJ, Resnick D. Current and innovative methods for noninvasive bone densitometry. Radiol Clin North Am 1990;28:257–278.
10. Sartoris DJ, Resnick D. X-ray absorptiometry in bone mineral analysis. Diagn Imaging (San Franc) 1990;12: 108–113,159,183.
11. Lewiecki EM. Clinical applications of bone density testing for osteoporosis. Minerva Med 2005;96:317–330.
12. Blake G. M, Gluer CC, Fogelman I. Bone densitometry: Current status and future prospects. Br J Radiol 1997;70: Spec No:S177–S186.
13. Blake GM, Fogelman I. Bone densitometry and the diagnosis of osteoporosis. Semin Nucl Med 2001;31:69–81.
14. Njeh CF, Hans D, Fuerst T, Gluer C-C, Genant HK. Quantitative Ultrasound Assessment of Osteoporosis and Bone Status. Munich: 1999.
15. Nord RH. Technical consideration in DPA. In: Genany HK, editor. Osteoporosis Updates 1987. 1987:203–212.
16. Dunn WL, Wahner HW, Riggs BL. Measurement of bone mineral content in human vertebrae and hip by dual photon absorptiometry. Radiology 1980;136:485–487.
17. Blake G. M, Fogelman I. Dual energy x-ray absorptiometry and its clinical applications. Semin Musculoskelet Radiol 2002;6:207–218.
18. Blake G. M, Fogelman I. Methods and clinical issues in bone densitometry and quantitatie ultrasonometry. 1573–1585, 2002.
19. Blake G. M, Fogelman I. Fracture prediction by bone density measurements at sites other than the fracture site: The contribution of BMD correlation. Calcif Tissue Int 2005;76:249–255.
20. Kanis JA. Diagnosis of osteoporosis and assessment of fracture risk. Lancet 2002;359:1929–1936.
21. Kanis JA. Assessing the risk of vertebral osteoporosis. Singapore Med J 2002;43:100–105.
22. Kanis JA, Borgstrom F, Zethraeus N, Johnell O, Oden A, Jonsson B. Intervention thresholds for osteoporosis in the UK. Bone 2005;36:22–32.
23. Kanis JA, Borgstrom F, De Laet C, Johansson H, Johnell O, Jonsson B, Oden A, Zethraeus N, Pfleger B, Khaltaev N. Assessment of fracture risk. Osteoporos Int 2005;16:581–589.
24. Melton LJ III, Atkinson EJ, O'Connor MK, O'Fallon WM, Riggs BL. Determinants of bone loss from the femoral neck in women of different ages. J Bone Miner Res 2000;15:24–31.
25. Melton LJ III, Kanis JA, Johnell O. Potential impact of osteoporosis treatment on hip fracture trends. J Bone Miner Res 2005;20:895–897.
26. Vokes TJ, Favus MJ. Noninvasive assessment of bone structure. Curr Osteoporos Rep 2003;1:20–24.
27. Keaveny TM, Morgan EF, Niebur GL, Yeh OC. Biomechanics of trabecular bone. Annu Rev Biomed Eng 2001;3:307–333.
28. Keaveny TM, Yeh OC. Architecture and trabecular bone—toward an improved understanding of the biomechanical effects of age, sex and osteoporosis. J Musculoskelet Neuronal Interact 2002;2:205–208.
29. Johnston CC Jr, Slemenda CW. Risk assessment: Theoretical considerations. Am J Med 1993;95:2S–5S.
30. Johnston CC Jr, Slemenda CW. Peak bone mass, bone loss and risk of fracture. Osteoporos Int 1994;4 (Suppl 1):43–45.
31. Johnston CC Jr, Hui S. Absolute versus relative fracture risk. J Bone Miner Res 2005;20:704.
32. Hans D, Fuerst T, Lang T, Majumdar S, Lu Y, Genant HK, Gluer C. How can we measure bone quality? Baillieres Clin Rheumatol 1997;11:495–515.
33. Dempster DW, Ferguson-Pell MW, Mellish RW, Cochran GV, Xie F, Fey C, Horbert W, Parisien M, Lindsay R. Relationships between bone structure in the iliac crest and bone structure and strength in the lumbar spine. Osteoporos Int 1993;3:90–96.
34. Dempster DW, Cosman F, Kurland ES, Zhou H, Nieves J, Woelfert L, Shane E, Plavetic K, Muller R, Bilezikian J, Lindsay R. Effects of daily treatment with parathyroid hormone on bone microarchitecture and turnover in patients with osteoporosis: A paired biopsy study. J Bone Miner Res 2001;16:1846–1853.
35. Laib A, Hauselmann HJ, Ruegsegger P. In vivo high resolution 3D-QCT of the human forearm. Technol Health Care 1998; 6:329–337.
36. Lang T, Augat P, Majumdar S, Ouyang X, Genant HK. Noninvasive assessment of bone density and structure using computed tomography and magnetic resonance. Bone 1998;22:149S–153S.
37. Lang TF, Keyak JH, Heitz MW, Augat P, Lu Y, Mathur A, Genant HK. Volumetric quantitative computed tomography of the proximal femur: Precision and relation to bone strength. Bone 1997;21:101–108.
38. Lang TF, Augat P, Lane NE, Genant HK. Trochanteric hip fracture: Strong association with spinal trabecular bone mineral density measured with quantitative CT. Radiology 1998;209:525–530.
39. Lang TF, Li J, Harris ST, Genant HK. Assessment of vertebral bone mineral density using volumetric quantitative CT. J Comput Assist Tomogr 1999;23:130–137.
40. Lang TF, Guglielmi G, Kuijk Cvan, De Serio A, Cammisa M, Genant HK. Measurement of bone mineral density at the spine and proximal femur by volumetric quantitative com-

puted tomography and dual-energy X-ray absorptiometry in elderly women with and without vertebral fractures. Bone 2002;30:247–250.

41. Ruegsegger P, Stebler B, Dambacher M. Quantitative computed tomography of bone. Mayo Clin Proc 1982;57 (Suppl):96–103.
42. Ruegsegger P. Quantitative computed tomography at peripheral measuring sites. Ann Chir Gynaecol 1988;77:204–207.
43. Ruegsegger P, Steiger P, Felder M. Quantitative computed tomography of the rheumatic knee. Clin Rheumatol 1988; 7:486–491.
44. Cann CE, Genant HK, Kolb FO, Ettinger B. Quantitative computed tomography for prediction of vertebral fracture risk. Bone 1985;6:1–7.
45. Cann CE. Quantitative CT for determination of bone mineral density: A review. Radiology 1988;166:509–522.
46. Ashman RB, Cowin SC, Van Buskirk WC, Rice JC. A continuous wave technique for the measurement of the elastic properties of cortical bone. J Biomech 1984;17:349–361.
47. Ashman RB, Corin JD, Turner CH. Elastic properties of cancellous bone: measurement by an ultrasonic technique. J Biomech 1987;20:979–986.
48. Ashman RB, Rho JY. Elastic modulus of trabecular bone material. J Biomech 1988;21:177–181.
49. Cheng S, Tylavsky F, Carbone L. Utility of ultrasound to assess risk of fracture. J Am Geriatr Soc 1997;45:1382–1394.
50. Gregg EW, Kriska AM, Salamone LM, Roberts MM, Anderson SJ, Ferrell RE, Kuller LH, Cauley JA. The epidemiology of quantitative ultrasound: A review of the relationships with bone mass, osteoporosis and fracture risk. Osteoporos Int 1997;7:89–99.
51. Njeh CF, Boivin CM, Langton CM. The role of ultrasound in the assessment of osteoporosis: A review. Osteoporos Int 1997;7:7–22.
52. Bauer DC, Gluer CC, Cauley JA, Vogt TM, Ensrud KE, Genant HK, Black DM. Broadband ultrasound attenuation predicts fractures strongly and independently of densitometry in older women. A prospective study. Study of Osteoporotic Fractures Research Group. Arch Intern Med 1997;157:629–634, 3–24.
53. Hans D, Schott AM, Meunier PJ. Ultrasonic assessment of bone: A review. Eur J Med 1993;2:157–163.
54. Hans D, Schott AM, Arlot ME, Sornay E, Delmas PD, Meunier PJ. Influence of anthropometric parameters on ultrasound measurements of Os calcis. Osteoporos Int 1995;5:371–376.
55. Laugier P, Fournier B, Berger G. Ultrasound parametric imaging of the calcaneus: *In vivo* results with a new device. Calcif Tissue Int 1996;58:326–331.
56. Laugier P, Droin P, Laval-Jeantet AM, Berger G. In vitro assessment of the relationship between acoustic properties and bone mass density of the calcaneus by comparison of ultrasound parametric imaging and quantitative computed tomography. Bone 1997;20:157–165.
57. Qin Y-X, Lin W, Rubin C. Interdependent relationship between Trabecular bone quality and ultrasound attenuation and velocity using a scanning confocol acoustic diagnostic system. J Bone Min Res 2001;16:S470–S470.
58. Qin Y-X, Lin W, Mittra E, Mueller R, Xia Y, Rubin C. Non-invasive assessment of bone quality and quantity using confocal acoustic scanning on *ex-vivo* trabeculae. Ann Biomed Eng. In press.
59. Qin Y-X, Xia Y, Lin W, Chadha A, Gruber B, Rubin C. Assessment of bone quantity and quality in human cadaver calcaneus using scanning confocal ultrasound and DEXA measurements. J Bone Min Res 2002;17:S422–S422.
60. Xia Y, Lin W, Qin Y. The influence of cortical end-plate on broadband ultrasound attenuation measurements at the human calcaneus using scanning confocal ultrasound. J Acoustic Soc Am 2005;118:1801–1807.
61. Frost ML, Blake GM, Fogelman I. Contact quantitative ultrasound: An evaluation of precision, fracture discrimination, age-related bone loss and applicability of the WHO criteria. Osteoporos Int 1999;10:441–449.
62. Frost ML, Blake GM, Fogelman I. Quantitative ultrasound and bone mineral density are equally strongly associated with risk factors for osteoporosis. J Bone Miner Res 2001;16:406–416.
63. Gomez AC, Schott AM, Hans D, Niepomniszcze H, Mautalen CA, Meunier PJ. Hyperthyroidism influences ultrasound bone measurement on the Os calcis. Osteoporos Int 1998;8:455–459.
64. Guo CY, Thomas WE, al Dehaimi AW, Assiri AM, Eastell R. Longitudinal changes in bone mineral density and bone turnover in postmenopausal women with primary hyperparathyroidism. J Clin Endocrinol Metab 1996;81:3487–3491.
65. Minisola S, Scarnecchia L, Carnevale V, Bigi F, Romagnoli E, Pacitti MT, Rosso R, Mazzuoli GF. Clinical value of the measurement of bone remodelling markers in primary hyperparathyroidism. J Endocrinol Invest 1989;12:537–542.
66. Minisola S, Rosso R, Scarda A, Pacitti MT, Romagnoli E, Mazzuoli G. Quantitative ultrasound assessment of bone in patients with primary hyperparathyroidism. Calcif Tissue Int 1995;56:526–528.
67. Wittich A, Vega E, Casco C, Marini A, Forlano C, Segovia F, Nadal M, Mautalen C. Ultrasound velocity of the tibia in patients on haemodialysis. J Clin Densitometry 1998;1:157–163.
68. Blanckaert F, Cortet B, Coquerelle P, Flipo RM, Duquesnoy B, Marchandise X, Delcambre B. Contribution of calcaneal ultrasonic assessment to the evaluation of postmenopausal and glucocorticoid-induced osteoporosis. Rev Rhum Engl Ed 1997;64:305–313.
69. Cortet B, Flipo RM, Blanckaert F, Duquesnoy B, Marchandise X, Delcambre B. Evaluation of bone mineral density in patients with rheumatoid arthritis. Influence of disease activity and glucocorticoid therapy. Rev Rhum Engl Educ 1997;64:451–458.
70. Madsen EL, Dong F, Frank GR, Garra BS, Wear KA, Wilson T, Zagzebski JA, Miller HL, Shung KK, Wang SH, Feleppa EJ, Liu T, O'Brien WD Jr, Topp KA, Sanghvi NT, Zaitsev AV, Hall TJ, Fowlkes JB, Kripfgans OD, Miller JG. Interlaboratory comparison of ultrasonic backscatter, attenuation, speed measurements. J Ultrasound Med 1999;18:615–631.
71. Wear KA, Garra BS. Assessment of bone density using ultrasonic backscatter. Ultrasound Med Biol 1998;24: 689–695.
72. Wear KA. Frequency dependence of ultrasonic backscatter from human trabecular bone: theory and experiment. J Acoust Soc Am 1999;106:3659–3664.
73. Wear KA, Stuber AP, Reynolds JC. Relationships of ultrasonic backscatter with ultrasonic attenuation, sound speed and bone mineral density in human calcaneus. Ultrasound Med Biol 2000;26:1311–1316.
74. Strelitzki R, Evans JA. An investigation of the measurement of broadband ultrasonic attenuation in trabecular bone. Ultrasonics 1996;34:785–791.
75. Strelitzki R, Evans JA. Diffraction and interface losses in broadband ultrasound attenuation measurements of the calcaneum. Physiol Meas 1998;19:197–204.
76. Strelitzki R, Metcalfe SC, Nicholson PH, Evans JA, Paech V. On the ultrasonic attenuation and its frequency dependence

in the os calcis assessed with a multielement receiver. Ultrasound Med Biol 1999;25:133–141.
77. Aindow JD, Chivers RC. Ultrasonic wave fluctuations through tissue: An experimental pilot study. Ultrasonics 1988;26:90–101.
78. Chivers RC. The scattering of ultrasound by human tissues–some theoretical models. Ultrasound Med Biol 1977;3:1–13.
79. Chivers RC, Parry RJ. Ultrasonic velocity and attenuation in mammalian tissues. J Acoust Soc Am 1978;63:940–953.
80. Ashman RB, Rho JY, Turner CH. Anatomical variation of orthotropic elastic moduli of the proximal human tibia. J Biomech 1989;22:895–900.
81. McKelvie ML, Palmer SB. The interaction of ultrasound with cancellous bone. Phys Med Biol 1991;36:1331–1340.
82. Turner CH, Eich M. Ultrasonic velocity as a predictor of strength in bovine cancellous bone. Calcif Tissue Int 1991;49:116–119.
83. Rho JY, Ashman RB, Turner CH. Young's modulus of trabecular and cortical bone material: Ultrasonic and microtensile measurements. J Biomech 1993;26:111–119.
84. Hou FJ, Lang SM, Hoshaw SJ, Reimann DA, Fyhrie DP. Human vertebral body apparent and hard tissue stiffness. J Biomech 1998;31:1009–1015.

See also BONE AND TEETH, PROPERTIES OF; COMPUTED TOMOGRAPHY.

BONE UNUNITED FRACTURE AND SPINAL FUSION, ELECTRICAL TREATMENT OF

AR LIBOFF
Oakland University
Rochester, Michigan

DEFINING THE UNUNITED FRACTURE

Within hours following a fracture in bone and the rapidly resulting hematoma, an endogenous repair process is initiated, characterized by increased cell division in the periosteum and endosteal stem-cell differentiation leading to organization of the hematoma into fibrocartilaginous callus. The latter represents the source of osteogenic potential from which ossification and subsequent bone remodeling occurs. In the ideal case, with proper management, those suffering bone fractures will normally find themselves fully recovered within a few months, with this time varying according to the specific bone involved, the type of fracture, and the age of the patient.

However, a small percentage of fractures fall outside the norm and do not heal as readily. There are upward of 5 million fractures occurring each year in the United States (1). Approximately 5–10% of these remain ununited after a few months. One can identify two types of ununited fractures, those undergoing *delayed* fracture healing, as evidenced by a lack of full healing in 3–6 months, and *nonunions*, where there is a lack of healing 6–12 months after the fracture has occurred. Marsh (2) suggests that the best measure of fracture healing in humans may be recovery of bending stiffness (i.e., the torque measured in Newton-meters that will bend bone by 1°). He defines delayed union as failure to reach a stiffness of of $7\ \mathrm{N}\cdot\mathrm{m}\cdot\mathrm{deg}^{-1}$ at 20 weeks following fracture. Both the periosteum and the *end*osteum are deeply involved in the process of fracture healing, and it has been suggested (2) that delayed healing may be the result of cessation of the periosteal response before bridging has occurred, while nonunion may be indicative of a breakdown of both the periosteal and the endosteal repair mechanisms. A more general term for nonunion is pseudarthrosis, or false joint. Worth noting is that this problem is also infrequently found at birth (congenital pseudarthrosis). Electric and electromagnetic treatment is prescribed for both types of psuedarthroses, those that are the result of ununited fractures, and those that are found at birth. Further, because spinal fusion following back surgery can be problematic, electromagnetic treatment is also being used as an adjunctive procedure to promote spine fusion (3).

THE ELECTRIC CHARACTER OF BONE

Bone has a number of remarkable physical properties, particularly its electric character. Its electrical properties and the intimate relation of these properties to the growth process in bone were brought to light in a series of experimental discoveries, beginning in the 1950s. These revealed

1. A piezoelectric effect in bone.
2. A striking bioelectric signature specifically associated with developing bone.
3. A characteristic signature in adult unstressed bone.
4. A characteristic bioelectric signature following bone fracture.

Piezoelectricity is the rather unique property in which mechanical force is transformed into electric polarization (Fig. 1). Bone was shown to be piezoelectric by Yasuda in the early 1950s, but the work leading to this conclusion was not made generally available until 1957(4). Fukada and Yasuda (5) later found that this property could be traced to the intrinsic collagen component in bone. Since that time, a number of observers (6–8) suggested that this mechanical stress–electric polarization property should more properly be referred to as a stress-generated potential (SGP), reflecting the fact that what actually happens may not be the result of the special sort of crystal or textural structure that underlies the piezoelectric effect, but might instead result from the well-known electrokinetic effect of streaming potential. Streaming potentials, similar to piezoelectric signals, are characterized by the transformation of mechanical stress into a potential difference. However, streaming potentials do not occur because of any intrinsic crystal structure, but rather because fluid displacement through porous materials or tubes results in electric charge separation. It is generally agreed that dry bone indeed exhibits piezoelectricity, but opinions vary on whether this effect actually plays a role when bone is in its usual (i.e., wet) physiological environment. Part of the difficulty in resolving this issue is that the piezoelectric effect is not easily measured in wet bone. Whatever the pros and cons concerning studies on wet bone, it is difficult to put aside the seminal experiment by McElhaney (9). More than 600 silver epoxy electrodes were attached to cover the surface of a dried intact human femur from autopsy, and a vertical



Figure 1. Piezoelectric Effect. Here, a tensile force results in a net electrical polarization in a material that ordinarily does not exhibit any polarization. Note that a compressive force will also result in electrical polarization. The source of the piezoelectric effect in bone is collagen.



Figure 2. Map of piezoelectric voltages in dry stressed femur. When a 50-lb (220 N) load is impressed on dry human femur, piezoelectric voltages appear over the entire surface. One such set, given in millivolts (mV), is shown (9). The interpretation by Marino and Becker (10) is that the locus of these voltages, as shown by the dotted line for one slice through the femur, corresponds to the way that the bone will remodel under a specific load.

mechanical load was applied to the proximal end of the entire femur, mimicking the femur's weight bearing function. This load produced piezoelectric potentials from each of the electrode points, in effect mapping the piezoelectric response of the entire bone to this load. The voltages obtained varied widely in intensity, and included both positive and negative signs. These results were interpreted by Marino and Becker (10) as showing that, if one assumes that negative potentials tend to activate osteoblasts and positive voltages act to enhance osteoclastic function, then the voltage map (Fig. 2) represents the locus of the new remodeling surface for the femur: Areas of negative polarity are found where the femur needs thickening and areas of positive polarity are located where the bone must be reduced in thickness. Thus the potential remodeling response of the femur to the applied load is related in a very direct way to the polarity and intensity distribution of the piezoelectric signal. The McElhaney experiment showed convincingly that the piezoelectric effect in bone, *in the dry state*, conveys the information necessary to provide a remodeling template for bone under mechanical stress, in effect explaining Wolff's law (11), the empirical statement that bone remodeling follows the distribution of forces applied to the bone. Nevertheless, it is conceivable that the locus of voltages supplied by the piezoelectric effect in bone also requires local electrokinetic potentials to implement the remodeling process at the cellular level, either through cellular differentiation to produce the required osteoblasts and osteoclasts necessary for bone remodeling, or perhaps to separate the osteoblasts and osteoclasts by galvanotaxis (12).

Even in the absence of mechanical stress, bone exhibits a variety of intrinsic electric signals. One such effect is apparently part of the growth and development process. Measuring the electric potential in the same way for the same vertebral element from a group of cadavers covering a wide range of ages, Athenstaedt (13) found that this voltage was clearly connected to the age of the individual, greatest in infancy and ultimately falling to a level voltage plateau with maturity. The implication is that electric polarization in bone plays a role in the growth process. Something similar happens in long bone. One can measure voltage differences, usually referred to as bioelectric potential (BEP) along the length of a long bone (14) (Fig. 3). The BEP is always a relative measurement, where, for example, one can fix one electrode at one end (the epiphysis) and measure the potential difference at various points along the shaft of the bone (the diaphysis). Particular attention has focused on the growth plate, that region between epiphysis and diaphysis where the bone actually is ossifying as it grows. The BEP measured at the growth plate relative to the epiphysis in immature, growing, bone is markedly negative by as much as 5 mV (15), but as growth ceases, this potential difference becomes less pronounced. Furthermore, it has been demonstrated by means of tetracycline labeling (16) that the formation of new bone corresponds closely with the BEP profile.

Bone also exhibits an intrinsic electrical character even if it is not actively growing or under mechanical stress. For example, a BEP profile is also found in adult bone, albeit with a different signature. In measurements of this voltage, it is observed that the proximal metaphysis is always



Figure 3. The BEP Profile. Bioelectric potential profile of a rabbit tibia (14). Voltage differences are obtained relative to the proximal end (on the left) by means of salt bridge electrodes.



Figure 4. Effect of fracture of an 8 cm rabbit tibia on BEP. Measured potentials are shown before and after the fracture, which is at the 4 cm point.

negative with respect to the midshaft and distal portions of the bone. Because the BEP is unaffected by local nerve denervation or reduced blood flow, but slowly disappears following animal death, it is believed (17) that the origin of this voltage stems from functioning bone cells, acting in concert.

Other than this likely connection to bone cells, it is difficult to pin down a reasonable physical explanation for the ubiquitous potential profile associated with long bone. Electric polarization is readily observed in specimens of mature bone when they are even slightly heated. The origin of this effect is still unclear, but it may reflect a pyroelectric response having a textural origin (18), or perhaps, as Mascarenhas has suggested (19), bone is inherently an electret, a type of material, like many bioploymers, with the interesting property of being capable of storing electric charge. Electrets are the electrical equivalent of magnets, and some observers have suggested that bone exhibits ferroelectric properties. The characteristic property seen in electrets is a slow release of charge when heated. For example, long-term currents on the order of 100 fA can be observed (20) for bone specimens heated to 40 °C. Regardless of the cause, it is most likely the case, as stated by Brighton (21), that: *. . .in living, non-stressed bone, areas of active growth...[are] electronegative when compared with less active areas*.

There is one more impressive electric property associated with living bone, again reflecting this question of the role of negative potentials. Only a few hours following bone fracture, the bone becomes more negative relative to the prefracture BEP (22) (Fig. 4). There is some dispute as to whether this effect is limited to the fracture site or is distributed more widely along the length of the bone (14,23). This uncertainty is in all likelihood due to the fact that there are obvious measurement problems in obtaining a BEP profile for a fractured bone. As an injury current one might expect a more specific and localized expression. However, it is possible that the entire periosteum may be affected in a bone fracture at any point along its length. Worth noting are the experiments by Becker and Murray (24) on fracture healing in amphibian systems indicating a discrete electrical negativity at the fracture site, which led him to characterize the innate ability of bone to heal itself in higher animals as a form of regenerative healing.

Viewed in the context of its other electrical properties, the change in voltage profile associated with bone fracture has to be regarded as consistent with the overarching concept that bone makes extensive use of electricity in all of its growth, repair, loadbearing, and homeostatic processes. Because of this, it is hardly surprising that exogenous electric currents have been widely applied in attempts to grow and/or repair bone.

The FDA-approved devices for electric repair of ununited fractures fall either into invasive or noninvasive categories. The invasive devices make use of implanted direct current (dc) and (ac) electric signal sources, both pulsed and continuously sinusoidal. The noninvasive types are either purely electric (capacitive coupling or CC), or electromagnetic, using pulsed magnetic fields (PMF or PEMF) or ion cyclotron resonance (ICR) tuned magnetic field combinations.

DIRECT CURRENT OSTEOGENESIS

The surgeon who first observed that bone is piezoelectric, Iwao Yasuda, was also the first to demonstrate (25) that electric fields applied to long bone in vivo are capable of producing callus. He wrapped a few turns of wire around rabbit femur, and, maintaining this point at a negative potential, passed a small (1 μA) current to an anode located away from the bone. It was consistently observed that after 3 weeks this current resulted in spicules of osseus callus (called electric callus by Yasuda) (Fig. 5). Surprisingly, these spicules were not directed along the bone itself, but instead along the direction of the current, in some cases actually pointing away from the bone. To the orthopedic surgeon, one of the most positive signs during the course of fracture repair is the appearance of callus. Thus the observation by Yasuda cannot be overemphasized.



Figure 5. Formation of callus in response to 1 μA dc current. After original sketch by Yasuda (26), showing wires wrapped around the bone.

Although the reasons why electricity is capable of forming callus are still not clear, the implication of Yasuda's work was that electrical stimulation might be of assistance in bringing ununited fractures to closure.

Most of the follow-up experiments to Yasuda's discovery concentrated on determining the effects of electrical signals on normal and fractured bone. A commonly used animal experimental design was to apply an electrical signal to one femur while using the contralateral femur in the same animal as a control. Intrinsic to this approach was the use of dummy electrodes, carrying no current, but serving to affect the contralateral limb by its mere presence in whatever way the electrodes were affecting the activated side. It was in this manner that Bassett et al. (27) used implanted battery packs to deliver microampere-level currents to platinum–iridium wire electrodes extending into the medullary cavities of femora in dogs. The results clearly indicated that more bone was formed in the intermedullary space in the vicinity of the cathodes than near the anodes. Follow-up experiments (28) reinforced the finding that bone growth appeared to be effective at the cathode, but also that bone necrosis occurred at anodes for currents in excess of 20 μA. In this work Friedenberg et al. (28) found that bone growth was most pronounced for currents between 5 and 20 μA. There is some question concerning this optimal current in that the required levels may be dependent on the mode of application. In rabbit femur, circular defects ~2.8 mm in diameter were repaired within 3 weeks when subjected to currents ranging between 2.5 and 3 μA applied by two electrodes on either side of the defect (29). Not only was the current lower than that suggested by Friedenberg et al. (28), but there was no particular advantage to either polarity. Similarly, Hambury et al. (30) studying $_{85}$Sr uptake in rabbit femur observed osteogenesis at 3 μA, again with no difference due to polarity. In another attempt (31) to establish the optimal current for repairing bone defects in dog, it was reported that 0.2 μA was more effective than either 2.0 or 20 μA.

Further complicating the issue of what level of current is required to initiate osteogenesis were a number of earlier reports in which callus was formed using currents that were orders of magnitude smaller than microampere levels. Fukada and Yasuda (4) wrapped a charged Teflon electret around bone to initiate callus, work that was later successfully repeated in Japan (32,33). Three different types of current application were employed in the latter experiment: that emitted by an electret, that obtained from the piezoelectric poly-γ-methyl-L-glutamate (PMLG) film, and a battery delivering 8–10 μA. The two current levels for the electret and the film, respectively, were 1 and 10 pA, levels smaller by huge factors of 10^{-7} and 10^{-6} from the "optimal" value of 10 μA. Marino and Becker (34) raised the issue as to whether this enormous difference in currents, both seemingly effective, means that more than one mechanism is involved, with the microampere (μA) results indicative of a nonspecific osteogenic stimulus while the picoamp (pA) currents more closely mimicing the endogenous piezoelectric response.

ELECTROMAGNETIC OSTEOGENESIS

Among his other important discoveries, Michael Faraday was the first to show that voltage is induced in a conductor when a nearby magnetic field is changing rapidly. This phenomenon, often referred to as Faraday's law, can be mathematically expressed by the following expression:

$$dB/dt = -V/A \tag{1}$$

where dB/dt is the time rate of change of the magnetic field B through a region of area A, and V is the voltage induced by dB/dt along the path that is circumferential to A by this rate of change. If B is varying at some frequency f, the product fB is a good measure of the relative effectiveness of dB/dt. When the region in question is electrically conducting, as in living tissue, one can use Ohm's law to rewrite the above expression in terms of the current I instead of V. Thus if R is the resistance of the circumferential path around A, Eq. 1 is changed to read

$$dB/dt = -I(R/A) \tag{2}$$

In this way, one can induce a current in the vicinity of a bone defect by employing a nearby magnetic field that is changing rapidly—the faster the rate of change, the greater the current. One achieves a faster change (i.e., a larger dB/dt) by merely increasing the frequency at which B is changing. Further, it is important to realize that the current so induced is no different from currents that are produced by purely electrical means (Fig. 6). Most important, since the source of the magnetic field can be deployed externally, Faraday's law enables the clinician to generate the required therapeutic currents in a completely noninvasive manner.

In 1974, following 5 years of intensive effort. Bassett and Pilla(35) reported on the successful use of the Faraday induction concept (PMF) to repair fibular osteotomies in beagle. Coils were placed on either side of the leg in such a manner that the magnetic fields from the coils traversed the defect and were additive (Fig. 7). The currents through each coil were pulsed in two ways, at 1 pulse $\cdot$ s^{-1} and at 65 pulses $\cdot$ s^{-1}. As revealed by mechanical testing of the fibula subsequent to treatment, there was greater indication of recovery with 65 pulses $\cdot$ s^{-1}, a finding that was consistent



Figure 6. The current density J produced in tissue by a voltage source V acting through electrodes E is no different from the current density induced by a changing magnetic field B according to Faraday's law. The B field is produced by a current I that energizes **a** coil C, whose plane is perpendicular to the page.



Figure 7. The PMF technique uses two flat coils connected in series to generate a magnetic field (dashed line) through the bone defect. Because the magnetic field is changing rapidly, a voltage is induced, producing a current in the vicinity of the defect. The process is completely noninvasive. In this sketch (36) the two parallel coils, whose planes are perpendicular to the page, are shown outside the cast.

with the prediction from Eq. 2 of a larger current with higher frequency.

INVASIVE (IMPLANTED) ELECTRIC TREATMENTS

Although the use of pulsed magnetic fields provides a means by which one avoids electrode implantation, some surgeons still prefer the extra advantages that come with direct observation of the pseudarthrosis defect. In addition, there is a very lengthy literature background on delivering dc directly to bony defects.

In late 1971, groups at New York University (NYU) and at the University of Pennsylvania independently demonstrated that electrical stimulation using implanted dc devices was successful in repairing pseudoarthrosis defects in humans. In both cases, electrodes and battery were surgically implanted with provisions for percutaneously monitoring the current. Otherwise, however, the methods employed were strikingly different. The NYU group, led by L.S. Lavine (37) used platinum wire electrodes on either side of a congenital pseudarthrosis in the lower tibia of a 14 year old male, in effect allowing the current to pass through the defect (Fig. 8). The polarity of the current was such that the proximal side of the defect was negative. This approach was the same as successfully used in this group's previous experiment (29) to repair defects in rabbit femur. The current was monitored and maintained over the 18-week treatment period at 3.9 μA.

By contrast, Friedenberg et al. (38) in treating a nonunion in the medial malleolus of a 51 year-old woman, used a technique (Fig. 8) that had been previously been found to be successful in producing callus in rabbit fibula (28,39). A stainless steel cathode was located directly in the defect and the anode, an aluminum grid, was taped to the skin. A constant-current power source maintained the current at 10 ± 2 μA over the 9 week treatment period. Again, as with the nonunion treatment employed by the NYU group, the outcome was successful.

These differences in treatment, both leading to repair of the nonunions, remain unresolved. The one treatment (37) is consistent with prior animal work in which the proximal side of bone was found to be intrinsically negative, while the second result (38) fits those observations (24) claiming that fractures are more negative than the rest of the bone. These differences tend to highlight a key difficulty connected to the research on the electric treatment of bone. Apart from the essentially empirical nature of measurements such as the BEP profile, there is no fundamentally sound basis with which to explain the underlying mechanisms, resulting in continuing uncertainties in the clinical techniques.

A number of investigators have attempted to shed light on this question of mechanisms. Almost all such "explanations" have focused on the electrically related regulation of different factors: parathyroid hormone (PTH) (40), adenosine 3', 5'- monophosphate (cAMP) (41,42), insulin-like growth factor II (IGF-II) (43), bone morphogenetic protein (BMP) (44), transforming growth factoř-beta 1 (TGF-β1) (45), and calcium ion channel transport (46). These are contributors, in varying degrees, to the cellular signal transduction pathways controlling bone growth. However, it would be truly surprising if these factors were *not* involved in all types of osteogenic processes, including electrical osteogenesis. At best, such factors must be regarded as merely *indicators* of metabolic activity in bone. At this point in time, they provide little, if any clue as to the reason why bone is responsive to electrical stimulation.



Figure 8. Two ways of using μA-level dc currents to repair defects in bone. In one case, the electrodes are applied so as to bridge the defect. In the other case, the cathode is placed directly into the defect. Both approaches have been successful (37,38) in treating human nonunions.

Presently, there are two FDA-approved implantable direct current devices for treating bony defects, both marketed by ElectroBiology Inc. (Parsippany, NJ). These are shown in Figs. 9 and 10. The Osteogen Bone Growth Stimulator supplies 40 μA through mesh electrodes. Although the cathode is located at the defect, similar to the original placement by Friedenberg et al. (38), the current is far in excess of what was thought to lead to bone necrosis (28). Apparently, the nature of the electrodes used by Friedenberg et al. (28) may have played a role in this discrepancy. The second implantable dc device is the SpF Spinal Fusion Stimulator, prescribed for spinal fusion. The positive and negative leads, in this case carrying 60 μA, are located on either side of the repair site.

NONINVASIVE ELECTRIC TREATMENT: (CC)

One method for applying an electric current to a defect in bone in a noninvasive manner is by means of capacitive coupling (CC). The background for this technique were experiments (47,48) in which 60 kHz sinusoidal voltages were capacitively transferred to bone cell cultures resulting in an electric field within the culture medium of 20 $\mathrm{mV \cdot cm^{-1}}$ and a current density of 300 $\mu\mathrm{A \cdot cm^{-2}}$. The first clinical use of this was to treat nonunions (49) (Fig. 11). An overall efficacy of 77% was achieved in a group of 22 cases with a mean time to healing of 23 weeks. The FDA-approved version of this technique is marketed by EBI (Fig. 12) As in the earlier studies on cell culture, the pictured device makes use of a 60 kHz alternating electric field that is applied to the skin on either side of the defect using disk electrodes and conducting gel. The current density within the tissue is considerably less than the levels used in cell culture, only $\sim 7\ \mu\mathrm{A \cdot cm^{-2}}$. The term *capacitive* may not be warranted for the devices pictured in Figs. 11 and 12. Unlike the lack of ohmic coupling in the earlier, *in vitro* studies, there is a much larger ohmic contribution to the overall impedance when disk electrodes are used. A better description for this device category might be ac (i.e., simply $\underline{a}$lternating $\underline{c}$urrent) instead of CC.



Figure 9. Implantable device for bone growth stimulation. EBI (Electro-Biology, Inc.)



Figure 10. Implantable device for adjunctive treatment of spinal repair (EBI)

A wide range of parameters have been used in studying the clinical and experimental aspects of the CC signal, with various voltages applied to the skin between 1 and 10 V, and frequencies between 20 and 200 kHz. The electric field strengths generated within tissue has ranged from 1 to 100 $\mathrm{mV \cdot cm^{-1}}$ and the current densities from 0.5 to 50 $\mu\mathrm{A \cdot cm^{-2}}$.

NONINVASIVE ELECTROMAGNETIC DEVICES: (PMF)

The successful use of PMF (also called PEMF) by Bassett et al. (35) to repair bone defects in animals noninvasively led to a number of different devices aimed at applying pulsed magnetic fields. One such early design, successfully applied to the treatment of a tibial nonunion (50,51), made use of an iron-cored electromagnet driven by a square pulse with a repetition rate of 1 pps. However, this design suffered because the large inductive reactance of the iron core acted as a constraint on the repetition rate of the coil current pulses.



Figure 11. Capacitive Coupling. Electrodes are attached on either side of the bony defect external to skin (here, external to cast) supplying a 60 kHz sinusoidal signal.



Figure 12. Mode of action of EBI capacitive coupling spinal fusion stimulator (EBI).

With this constraint in mind, Bassett's group succeeded in designing (52) a low inductance air-coil system that could be pulsed at higher frequencies to repair recalcitrant pseudarthroses and nonunions in humans (Figs. 13–16). The success rate that was reported (85%) was greatly in excess of the salvage rate usually obtained by orthopedists using conventional, nonelectrical procedures. However, later (55), reviewing PMF treatments for a wider, all-inclusive group of pseudarthrosis cases, including those with the worst prognosis, Bassett lowered the success rate downward, to 54%.

The pulsed magnetic field that was originally used by Bassett was (and still is) based on the saw-tooth signal common to the fly-back refresher circuit in television receivers. A saw-tooth voltage (Fig. 17) is applied to a pair of many turn coils, creating a current in both coils that generates a single magnetic field. The planes of the coils are roughly parallel, and deployed on opposite sides of the defect (see Fig. 7), creating a commonly directed magnetic field through the defect. The sawtooth signal applied to the coils results in a rapidly changing magnetic field, ~ 10 tesla per second ($\mathrm{T \cdot s^{-1}}$), maximized at those times when the voltage applied to the coils is falling sharply. Faraday's law results in the induced voltage shown in Fig. 18. The net induced signal that appears in the vicinity of the defect consists of bursts of 21 pulses, each individual pulse 260 μs in duration, with the bursts repeating at 15 Hz. The magnetic field that actually appears in the area of the defect rises, with each pulse, to ~ 10 G (1 mT), before dropping precipitously in ~ 25 μs. It is this rapid change in B that contributes the most to the induction of current (see Eq. 2). For example, if a sine wave signal of 10 G at 60 Hz were applied to the same region instead of this pulse, the maximum current would be 600 times smaller.



Figure 13. Treatment of ununited scaphoid fracture with PMF (53).

The various PMF clinical and experimental signal repetition rates that have been attempted vary between 1 and 100 Hz, with the maximum magnetic field intensity at the defect site ranging from 0.1 to 30 G, and the induced electric field at the site ranging between 0.01 and 10 $\mathrm{mV \cdot cm^{-1}}$.

NONINVASIVE ELECTROMAGNETIC DEVICES (ICR)

Magnetic fields are also used in bone repair in ways that have nothing to do with Faraday induction. It was shown in 1985 (56) that the results embodied in the so-called calcium efflux effect (57,58) were in close agreement with predictions based on the resonance characteristics of certain biological ions subject to the Lorentz force. Specifically, the shape of the nonlinear frequency dependence of calcium binding to chick brain tissue was what might be expected for a particle with the charge-to-mass ratio of the potassium ion moving in combined parallel sinusoidal and dc magnetic fields whose ac frequency and dc intensity corresponded to the ICR condition for K^+. This observation also explained earlier work (59,60) in cell culture demonstrating that weak low frequency magnetic fields enhance DNA synthesis in a manner that is clearly not related to Faraday induction, since the additional DNA synthesis does not scale with either frequency or intensity. Ion cyclotron resonance is a magnetic effect that is fundamentally different from Faraday's law as expressed in Eq. 1. More specifically, as regards possible effects of magnetic fields on bone, it entails a totally different phenomenon than the induction of current in bone using pulsed magnetic fields.

Unlike previous attempts to arrive at the electromagnetic conditions required for electrical osteogenesis, exact predictions are possible using the ICR effect. One can focus on a specific ion and adjust the intensity of the dc magnetic



Figure 14. Treatment of congenital pseudarthrosis of the tibia with PMF (54).



Figure 15. PMF Bone healing system (EBI).



Figure 16. PMF device in place on patient (EBI).

field and the frequency of the ac magnetic field to "tune" to this ion. This is because a resonant condition occurs when the ratio of the frequency of the ac field to the intensity of the dc field is equal to the charge-to-mass ratio of the ion. The simple expression governing this resonance is

$$\omega/B = q/m \tag{3}$$

where ω is the (angular) frequency of the ac field, in rad $\cdot$ s^{-1}, B is the intensity of the dc magnetic field, in Tesla, and, q/m is the mass-to-charge ratio of the ion. For practical applications, the angular frequency ω is replaced by its equivalent, $2\pi f$, where f is the frequency in hertz (Hz). The underlying interaction mechanism for this effect in living tissue is still in question (61), but the most reasonable explanation is that ions in resonance are more likely to stimulate the gating mechanism for ion channel transport.



Figure 17. Sawtooth voltage applied to PMF coil.



Figure 18. Voltage induced in tissue by PMF.

A great deal of work has been done in examining the effects on biological expression when tuning to Ca^{2+}, Mg^{2+}, and K^{+}, not only in bone cell culture (Fig. 19) (62), but also in neural cell culture, in animal behavior, and in plants (61). It is generally agreed that ICR tuning to these ions can have striking effects on growth. One such example (63) is shown in Fig. 20 illustrating the relative effects on explanted embryonic chick femora cultured under Ca^{2+} and under K^{+} ICR magnetic field conditions.



Figure 19. Frequency response of insulin-like growth factor in bone cell culture under combined ac and dc magnetic field exposure 62. The dc field was maintained at 20 μT for each of the points shown. There is a clear peak at 15.3 Hz, corresponding to the predicted ICR condition for Ca^{2+} resonance in Table 1.



Figure 20. Effect of ICR magnetic exposures on chick embryonic growth (63). The topmost femur, the shortest, was grown under K^+ ICR tuning, while the bottom femur was grown under Ca^{2+} ICR magnetic field conditions. The middle femur was not exposed to any ICR field.

Diebert et al. (64) examined the efficacy of ICR in repairing defects in rabbit fibula, basically reusing the animal model that had been previously employed to study electrical osteogenesis (29), but applying an ICR magnetic field combination instead of a dc current. It was found that the 28-day ICR treatment yielded results equivalent to or better than those employing direct current and pulsed magnetic fields. For animals exposed to Ca^{2+} resonance magnetic fields for as little as 30 $\min \cdot \mathrm{day}^{-1}$, there was an average increase in stiffness of 175% over controls, rising to nearly 300% when the exposures were maintained for 24 h. Somewhat smaller increases in stiffness were also observed for exposures tuned to the Mg^{2+} charge-to-mass ratio.

Another aspect of the ICR effect is that one can also use harmonics, that is, multiples of the frequency condition given in Eq. 3. For theoretical reasons (65) only odd harmonics are allowed. Thus, the most general expression for cyclotron resonance frequencies is

$$f_n = (2n+1)(1/2\pi)(qB/m) \quad n = 0, 1, 2, 3, \ldots \tag{4}$$

Table 1 lists the frequency/field ratios (f_n/B) for the three ions, Mg^{2+}, Ca^{2+}, and K^+ for the first three harmonics from Eq. 4. Note that some of these ratios are numerically close to one another. The 5th harmonic of Ca^{2+} is slightly $> 1\%$ greater than the 3rd harmonic for Mg^{2+} (3.83 vs. 3.79). This observation led S.D. Smith to suggest that using a frequency/field ratio of 3.8 might be particularly effective in bone where growth is indicated for both Ca^{2+} and Mg^{2+} stimulation (66). This ratio is the basis for a number of bone stimulation devices manufactured by the djOrthopedics Corporation for treating pseudarthroses and enhancing spinal fusion (Figs. 21,22). The time variation of the magnetic field generated by these devices is shown in Fig. 23. Because the ac and dc magnetic field directions must be maintained parallel to ensure the resonance condition, these clinical devices achieve the frequency/field ratio by fixing the frequency of the applied sinusoidal magnetic field at 76.9 Hz, while using a second coil to continuously adjust for changes in the parallel component of the local dc magnetic field, to maintain this dc level at 20 μT.

Table 1.

Ion	Fundamental f_0/B, Hz · μT	3rd Harmonic f_1/B, Hz · μT	5th Harmonic f_2/B, Hz · μT
Mg^{2+}	1.26	3.79	6.31
Ca^{2+}	0.77	2.30	3.83
K^+	0.39	1.18	1.97



Figure 21. ICR bone repair device for treating nonunions. (djOrthopedics Corp.)

Some observers incorrectly use the term *combined magnetic field* (CMF), to characterize this clinical technique. It is important to understand that the fields that are combined are highly specific, following the rules expressed in Eq. 4. In addition, it is possible to achieve the same conditions in tissue with a single magnetic field, using a prepared current derived from an arbitrary waveform generator. For these reasons, the term ICR should be used for all clinical and research techniques that are otherwise termed CMF.



Figure 22. ICR device for adjunctive use in spinal fusion. (djOrthopedics Corp.)



Figure 23. Comparing ICR signal to PMF signal. In the one case, there is a 20 μT peak sinusoidal magnetic field, and in the other a very short magnetic pulse ~ 100 times larger in intensity (Orthologic Corporation).

It is also sometimes incorrectly reported that ICR is an *inductive* procedure. However, the inductive current generated in the ICR device is negligible, approximately a factor of 10^{-5} smaller than the currents induced by PMF devices. While clearly noninductive, the actual ICR interaction mechanism is still in question (45). It is most likely coupled to events occurring at membrane bound ion channels (40), as evidenced that the calcium channel blocker nifedipene prevents the ICR response (67). It has been suggested, in this regard, that the channel gating process may be sensitive to the resonance tuning of specific ions (45).

SUMMARIZING EFFICACIES FOR THE VARIOUS TREATMENT

The three types of noninvasive treatments for bone defects, PMF, ICR, and CC, have each been subjected to randomized, double-blind trials and are shown to be efficacious, with an overall success rate of between 50 and 70%. One reason for this variation is undoubtedly the inclusion, or lack therein, of patients with defects that are intrinsically more difficult to repair. As the gap in a pseudarthrosis extends to widths > 5 mm, the likelihood of successful treatment diminishes. For this reason, some clinicians choose to exclude patients with radiographic gaps > 5 mm from electrical treatment (21,68).

More than 20 years after Bassett's original use (52) of pulsed magnetic fields to repair nonunions, a definitive work on using PMF to treat delayed unions was published by Sharrard (69). A total of 45 fractures of the tibia were examined in a double-blind multicenter trial, with active PMF stimulation in 20 patients and dummy control units in 25 patients for 12 weeks at 12 h/day. The results, 9 unions in the active group compared to only 3 in the control group, were "*very significantly in favour of the active group* ($p = 0.002$)". This effectiveness of PMF stimulation was confirmed for the case of tibial osteomoties in still another randomized, double blind study (70). Similarly, the successful use of CC and ICR, respectively, in treating nonunions, was reported by Scott and King (71) and by Longo (72). Recently, there has been increasing interest in the use of these electromagnetic techniques as an adjunctive to spine fusion. Again, as with the treatment of pseudarthroses, randomized, double-blind trials carried out for the PMF (73), CC (74) and ICR (75) techniques, have indicated that each is also efficacious in the adjunctive treatment of spine fusion.

GENERAL REMARKS

A summary of the electrical and electromagnetic treatments for nonunions and spinal fusion is given in Table 2. It is difficult to make simple comparisons based solely on the relative electrical characteristics, since each modality is based on different types of specifications, including current, current density, time rate of change of magnetic field, frequency, and magnetic intensity. As mentioned above, the levels of current that have been used to achieve osteogenesis extends over a range that has many orders of magnitude, a fact that seems to preclude any mechanism that is simply connected to current alone. It is highly likely that the larger of these successful current levels achieve osteogenesis, as Becker has suggested, by acting as an irritant, and that the smaller levels are perhaps related to the sorts of currents that might occur naturally, perhaps as the result of stress-generated potentials. One measure of

Table 2. Summary of Electrical and Electromagnetic Treatments for Nonunions and Spinal Fusion

	Modality	Designation	Characteristics	Daily Treatment
Invasive	dc electric	dc	1 pA–60 μA	24 h
Noninvasive	ac electric	CC	60 kHz, $7 \mu A \cdot cm^{-2}$	24 h
	Pulsed magnetic field	PMF, PEMF	$dB/dt = 100\ T \cdot s^{-1}$ Repetition rate=15 Hz	3 h
	Sinusoidal magnetic field	ICR, CMF	77 Hz ac frequency 20 μT dc Field	30 min

this potential dichotomy is the remarkable fact that both ICR and PMF techniques are equally successful in treating nonunions, despite the fact that the induced currents differ by a factor of 10^5.

There is undoubtedly room for improvement in the efficacy of the various electromagnetic treatments to repair bony nonunion. Note that both treatments, PMF and ICR, were each adopted for clinical use on the basis of the original designs, with no subsequent studies before or after FDA approval that might have been initiated to search for waveforms and signals that conceivably could be used to optimize treatment. Thus for pulsed magnetic fields, it remains to be seen what roles are played by variables such as pulse width, rise time, repetition rate, and so on, and whether marked improvements in efficacy would follow optimization of these key variables. At least one report (76) claims that peak magnetic fields 100 times smaller than used in the EBI PMF device are just as effective in treating nonunions. Similarly, positive results were obtained in treating tibial osteotomies in rabbit with very different pulse characteristics from that of the EBI clinical device (77). Not only was the magnetic pulse reduced by a factor of 15, but the pulse repetition rate was reduced by a factor of 10, and the frequency components in excess of 20 kHz were filtered from the signal. This lack of optimization is equally true for the djOrthopedics ICR therapeutic signal, based on an approximate simultaneous stimulation of Ca^{2+} and Mg^{2+}ions as well as a very specific ratio of ac to dc magnetic intensities. The ICR device presently approved by the FDA sets this ratio at unity, despite the fact that a number of investigators (78–80) suggested that this ratio may have important consequences for the efficacy of the resonance interaction.

Furthermore, it has been suggested (31,81) that the fundamental reason why some electrical treatments of pseudarthroses are successful may have little to do with the nature of the electrical signal itself, but rather that the initiation of callus formation is known to be tied to local irritants, such as occurs with mechanical, thermal, or chemical sources. It is not inconceivable that the efficacy of treatments such as PMF may result from its role as an irritant. There is evidence (82,83) indicating an increased expression of heat shock proteins in response to low level electromagnetic fields. This type of genetic expression can result from a wide range of stress factors.

The fact that electrical osteogenesis occurs naturally, in growth, homeostasis, and repair and, further, that it can be brought about by exogenous application, begs the question as to whether the present 50–70% repair rate might be substantially improved with further research into the actual underlying mechanism.

BIBLIOGRAPHY

Cited References

1. Ryaby JT. Clinical effects of electromagnetic and electric fields on fracture healing. Clin Orth Rel Res 1998;355S: 205–215.
2. Marsh D. Concepts of fracture union, delayed union, and nonunion. Clin Orthop 1998;355S:22–30.
3. Marone MA, Feuer H. The use of electrical stimulation to enhance spinal fusion. Neurosurg Focus 2002;13: article 6.
4. Fukada E, Yasuda I. On the piezoelectric effect in bone. J Phys Soc Jpn 1957;12:1158–1162.
5. Fukada E, Yasuda I. Piezoelectric effects in collagen. Jpn J Appl Phys 1964;3:117–121.
6. Anderson JC, Eriksson C. Electric properties of wet collagen. Nature (London) 1968;218:166–168.
7. Anderson JC, Eriksson C. Piezoelectric properties of dry and wet bone. Nature (London) 1970;227:491–492.
8. Pienkowski D, Pollack SR. The origin of stress generated potentials in fluid-filled bone. J Orthop Res 1983;1:30–41.
9. McElhaney JH. The charge distribution on the human femur due to load. J Bone Joint Surg 1967;49:1561–1571.
10. Marino AA, Becker RO. Piezoelectric effect and growth control in bone. Nature (London) 1970;228:473–474.
11. Wolff J Das Gesetz der. Transformation der Knochen. Berlin: A. Hirschwohl; 1892.
12. Ferrier J, Moss SM, Kanehisa J, Aubin JE. Osteoclasts and osteoclasts migrate in opposite directions in response to a constant electrical field. J Cell Physiol 1986;129:283–288.
13. Athenstaedt H. Permanent electric polarization and pyroelectric behavior of the vertebrate skeleton III. The axial skeleton of man. Z Zellforsch 1969;93:484–504.
14. McGinnis ME. The nature and effects of electricity in bone, Chapt. 6 in Electric Fields in Vertebrate Repair. In: Borgens RP, Robinson KR, Venable JW, Jr, McGinnis ME, editors. New York: Alan R. Liss; 1989.
15. Friedenberg ZB. Bioelectric potentials in bone. J Bone Joint Surg 1966;48A:915–923.
16. Rubinacci A, Tessari L. A correlation analysis between bone formation rate and bioelectric potentials in rabbit tibia. Calc Tiss Res Int 1983;35:728–731.
17. Friedenberg ZB, Harlow MC, Heppenstall RB, Brighton CT. The cellular origin of bioelectric potentials in bone. Calc Tiss Res 1973;13:53–62.
18. Lang SB. Thermal expansion coefficients and the primary and secondary pyroelectric coefficients of animal bone. Nature (London) 1969;224:798–799.
19. Mascarenhas S. The electret effect in bone and biopolymers and the bound-water problem. Ann NY Acad Sci 1974;238: 36–52.
20. Liboff AR, Furst M. Pyroelectric effect in collagen and structures. Ann NY Acad Sci 1974;238:26–35.
21. Brighton CT. The treatment of non-unions with electricity. J Bone Joint Surg 1981;63A:847–851.
22. Friedenberg ZB, Smith HG. Electric potentials in intact and fractured tibia. Clin Orthop 1969;63:222–225.
23. Becker RO, Spadaro JA, Marino AA. Clinical experiences with low intensity direct current stimulation of bone growth. Clin Orthop Rel Res 1977;124:75–83.
24. Becker RO, Murray DG. The electric control system regulating fracture healing in amphibians. Clin Orthop Rel Res 1970;73:169–198.
25. Yasuda I. Fundamental aspects of fracture treatment. J Kyoto Med Soc 1953;4:395–406 (in Japanese) Translated in *Clin Orthop* 1977;124:5–8.
26. Yasuda I. Mechanical electrical callus. Electrically Mediated Growth mechanisms in Living Systems. Ann NY Acad Sci 1974;238:457–465.
27. Bassett CAL, Pawluk RJ, Becker RO. Effect of electric currents on bone in vivo. Nature (London) 1964;204:652–654.
28. Friedenberg ZB, Andrews ET, Smolenski BI, Pearl BW, Brighton CT. Bone reaction to varying amounts of direct current. Surg Gyn Obstet 1970;127:894–899.
29. Lavine L, Lustrin I, Shamos MH, Moss ML. The influence of electric current on bone regeneration in vivo. Acta Orthop Scand 1971;42:305–314.

30. Hambury HJ, Watson J, Toole A, Sivyer A, Ashley DBJ. Interdisciplinary approaches in electrically mediated bone growth studies. Ann NY Acad Sci 1974;238:508–518.
31. Paterson DC, Carter RF, Tilbury RF, Ludbrook J, Savage JP. The effects of varying current levels of electrical stimulation. Clin Orthop Rel Res 1982;169:303–312.
32. Ohashi T. Electrical callus formation and its osteogenesis. J Jpn Orthop Ass 1982;56:615–633.
33. Inoue S, Ohashi T, Fukada E, Ashihara T. Electric stimulation of osteogenesis in the rat: Amperage of three different stimulation mehods. In: Brighton CT, Black J, Pollack S, editors. Electric Properties of Bone and Cartilage. Philadelphia: Grune and Stratton; 1979. p 199–213.
34. Marino AA, Becker RO. Electrical osteogenesis: an analysis (Let). Clin Orthop Rel Res 1977;123:280–282.
35. Bassett CAL, Pawluk RJ, Pilla AA. Acceleration of fracture repair by electromagnetic fields. A surgically noninvasive method. Ann NY Acad Sci 1974;238:242–262.
36. Werner FW, Spadaro JA. Engineering aspects of medical surgical instruments and devices. In: Barzeley ME, editor. Product Liability. New York: Matthew Bender Publ. Co; 1993.
37. Lavine LS, Lustrin I, Shamos MH, Rinaldi RA, Liboff AR. Electric enhancement of bone healing. Science 1972;175: 1118–1121.
38. Friedenberg ZB, Harlow MC, Brighton CT. Healing of nonunion in the medial malleolus by means of direct current: a case report. J Trauma 1971;11:883–885.
39. Friedenberg ZB, Roberts PG, Jr, Didizian NH, Brighton CT. Stimulation of fracture healing by direct current in the rabbit fibula. J Bone Joint Surg 1971;53A:1400–1408.
40. Luben RA, et al. Effects of electromagnetic stimuli on bone and bone cells in vitro inhibition of responses to parathyroid hormone by low-energy, low-frequency field. Proc Natl Acad Sci USA 1982;79:4180–4184.
41. Norton LA, Rodan GA, Bourret LA. Epiphyseal cartilage cAMP changes produced by electrical and mechanical perturbations. Clin Orthop Rel Res 1977;124:57.
42. Farndale RW, Murray JC. The action of pulsed magnetic fields on cyclic AMP levels in cultured fibroblasts. Biochim. Biphys Acta 1986;881:46–53.
43. Fitzsimmons RJ, Ryaby JT, Mohan S, Magee FP, Baylink DJ. Combined magnetic fields increase IGF-II in TE-85 human bone cell cultures. Endocrinology 1995;136:3100–3106.
44. Bodamyali T, Bhatt B, Hughes FJ, Winrow VR, Kanczler JM, Simon B, Abbott J, Blake DR, Stevens CR. Pulsing electromagnetic fields simultaneously induce osteogenesis and upregulate transcription of bone morphogentic proteins 2 and 4in rat osteoblasts in vitro. Biochem Biophys Res Commun 1998;250:458–461.
45. Zhuang H, Wang W, Seldes RM, Tahemia AD, Fan H, Brighton CT. Electrical stimulation induces the level of TGF-β1 mRNA in osteoblastic cells by a mechanism involving calcium/calmodulin pathway. Biochem Biophys Res Commun 1997;237:225–229.
46. Wang Q, Zhong S, Ouyang J, Jiang L, Zhang Z, Xie Y, Luo S. Osteogenesis of electrically stimulated bone cells mediated in part by calcium ions. Clin Orthop Rel Res 1996;348:259–268.
47. Brighton CT, McCluskey WP. Response of bone cells to a capacitively coupled electric field: inhibition of cyclic adenosine monophosphate response to parathroid hormone. J Orthop Res 1988;6:567–571.
48. Lorich DG, Brighton CT, Gupta R, Corsetti JR, Levine SE, Gelb ID, Seldes R, Pollack SR. Biochemical pathway mediating the response of bone cells to capacitive coupling. Clin Orthop Rel Res 1998;350:246–256.
49. Brighton CT, Pollack SR. Treatment of recalcitrant nonunion with a capacitively coupled electric field. J Bone Joint Surg 1985;67A:577–585.
50. De Haas WG, Morrison DM, Watson J. Non-invasive treatment of the tibia using electrical stimulation. J Bone Joint Surg 1980;62:465–470.
51. Watson J, Downes EM. Light-weight battery-operable orthopaedic stimulator for the treatment of long-bone nonunions using pulsed magnetic fields. Med Biol Eng Comput 1983;21: 509–510.
52. Bassett CAL, Pilla AA, Pawluk RJ. A non-operative salvage of surgically-resistant pseudarthroses non-unions by pulsing electromagnetic fields electromagnetic fields. Clinical Orthop Rel Res 1977;124:128–143.
53. Frykman GK, Taleisnik J, Peters G, Kaufman R, Helal B, Wood VE, Unsell RS. Treatment of nonunited scaphoid fractures by pulsed electromagnetic field and cast. J Hand Surg 1986;11:344–349.
54. Kort JS, Schink MM, Mitchell SN, Bassett CAL. Congenital pseudarthrosis of the tibia: Treatment with pulsing electromagnetic fields. Clin Orthop Rel Res 1982;165:124–136.
55. Bassett CAL, Schink-Ascani M. Long-term pulsed electromagnetic field (PEMF) results in congenital pseudarthrosis. Calc Tiss Int 1991;49:216–220.
56. Liboff AR. Geomagnetic cyclotron resonance in living cells. J Biol Phys 1985;13:99–102.
57. Bawin SM, Kazmarek KL, Adey WR. Effects of modulated VHF fields on the central nervous system. Ann NY Acad Sci 1975;247:74–81.
58. Blackman CF, Benane SG, Kinney LS, Joines WT, House DE. Effects of ELF fields on calcium-ion efflux from brain tissue in vivo. Rad Res 1982;92:510–520.
59. Liboff AR, Williams T, Jr., Strong DM, Wistar R, Jr. Time-varying magnetic fields: effect on DNA synthesis. Science 1984;223:818–820.
60. Takahashi K, Keneko I, Date M, Fukada E. Effect of pulsing electromagnetic fields on DNA synthesis in mammalian cells in culture. Experientia 1986;42:185–186.
61. Liboff AR. The charge-to-mass ICR signature in weak ELF bioelectromagnetic effects. In: Lin JC, editor. Advances in Electromagnetic Fields in Living Systems. Volume 4, New York: Kluwer; 2003.
62. Fitzsimmons RJ, Ryaby JT, Mohan JT, Magee FP, Baylink DJ. Combined magnetic fields increase insulin-like growth factor-II in Te-85 human osteosarcoma bone cell cultures. Endocrinology 1995;136:3100–3106.
63. Smith SD, Liboff AR, McLeod BR. Effects of resonant magnetic fields on chick femoral development in vitro. J Bioelect 1999;10:81–99.
64. Diebert MC, McLeod BR, Smith SD, Liboff AR. Ion resonance electromagnetic field stimulation of fracture healing in rabbits with a fibular ostectomy. J Orthop Res 1994;12:878–885.
65. McLeod BR, Liboff AR. Cyclotron resonance in cell membranes; The theory of the mechanism. In: Blank M, Findl E, editors. Mechanistic Approaches to Interactions of Electric Electromagnetic Fields with Living Systems. New York: Plenum Press; 1987; p 97–108.
66. Smith SD. personal Communication.
67. Rozek RJ, Sherman ML, Liboff AR, McLeod BR, Smith SD. Nifedipene is an antagonist to cyclotron resonance enhancement of 45Ca incorporation in human lymphocytes. Cell Calcium 1987;8:413–427.
68. Barker AT, Dixon RA, Sharrard WJW, Sutcliffe ML. Pulsed magnetic field therapy for tibial non-union. The Lancet 1984;1:994–996.
69. Sharrard WJW. A double-blind trial of pulsed electromagnetic field for delayed union of tibial fractures. J Bone Joint Surg Bri 1990;72B:347–355.

70. Mammi GI, Rocchi R, Cadossi R, Traina GC. Effect of PEMF on the healing of human tibial osteomoties: a double blind study. Clin Orthop 1993;288:246–253.
71. Scott G, King JB. A prospective double blind trial of electrical capacitive coupling in the treatment of non-union of long bones. J Bone Joint Surg 1994;76A:820–826.
72. Longo JA. The management of recalcitrant nonunions with combined magnetic fields. Orthop Trans 1998;22:408–409.
73. Mooney VA. randomized double blind prospective study of the efficacy of pulsed electromagnetic fields for interbody lumbar fusions. Spine 1990;15:708–715.
74. Goodwin CB, Brighton CT, Guyer RD, Guyer RD, Johnson JR, Light KI, Yuan HA. A double blind study of capacitively coupled electrical stimulation as an adjunct to lumbar spinal fusions. Spine 1999;24:1349–1357.
75. Linovitz RJ, Pathria M, Bernhardt M, Green D, Law MD, McGuire RA, Montesano P, Rechtine G, Salib RM, Ryaby JT, Faden JS, Ponder R, Muenz LR, Magee FP, Garfin SA. Combined magnetic fields accelerate increase spine fusion: a double-blind, randomized, placebo controlled study. Spine 2002;27:1383–1389.
76. Satter SA, Islam MA, Rabbani KS, Talukder MS. Pulsed electromagnetic fields for the treatment of bone fractures. Bangladesh Med Res Council Bull 1999;25:6–19.
77. Fredericks DC, Nepola JV, Baker JT, Abbott J, Simon B. Effects of pulsed electromagnetic fields on bone healing in a rabbit tibial osteomoty model. J Orthop Trauma 2000;14:93–100.
78. Lednev VV. Possible mechanism for the influence of weak magnetic fields on biological systems. Bioelectromagnetics 1991;12:71–75.
79. Blanchard JP, Blackman CF. Clarification amplification of an ion parametric resonance model for magnetic field interactions with biological systems. Bioelectromagnetics 1994;15:217–238.
80. Prato FP, Kavaliers M, Thomas AW. Extremely low frequency magnetic fields can either increase or decrease analgesia in the land snail depending on field and light conditions. Bioelectromagnetics 2000;21:287–301.
81. Becker RO. personal communication.
82. Goodman R, Bassett CAL, Henderson AS. Pulsing electromagnetic fields induce cellular transcription. Science 1983;220:1283–1285.
83. Goodman R, Blank M. A non-thermal low-energy agent that induces stress response proteins: Magnetic fields. Cell Stress Chaperones 1998;3:79–88.

See also BONE AND TEETH, PROPERTIES OF; FUNCTIONAL ELECTRICAL STIMULATION; HUMAN SPINE, BIOMECHANICS OF.

BORON NEUTRON CAPTURE THERAPY

ROLF F. BARTH
The Ohio State University
Columbus, Ohio

JEFFREY A. CODERRE
Massachusetts Institute of Technology
Cambridge, Massachusetts

M. GRAÇA
H. VICENTE
Louisiana State University
Baton Rouge, Louisiana

THOMAS E BLUE
The Ohio State University
Columbus, Ohio

INTRODUCTION

High grade gliomas, and specifically glioblastoma multiforme (GBM), are still extremely resistant to all current forms of therapy, including surgery, chemotherapy, radiotherapy, immunotherapy, and gene therapy after decades of intensive research (1–5). Despite aggressive treatment using combinations of therapeutic modalities, the 5 year survival rate of patients diagnosed with GBM in the United States is less than a few percent (6,7). By the time they have had surgical resection of their tumors, malignant cells have infiltrated beyond the margins of resection and have spread into both gray and white matter (8,9). As a result, high grade supratentorial gliomas must be regarded as a whole brain disease (10). Glioma cells and their neoplastic precursors have biochemical properties that allow them to invade the unique extracellular environment of the brain (11,12) and biologic properties that allow them to evade a tumor associated host immune response (13). Chemo- and radiotherapy's inability to cure patients with high grade gliomas is due to their failure to eradicate microinvasive tumor cells within the brain. The challenge facing us is how to develop molecular strategies that can selectively target malignant cells with little or no effect on normal cells and tissues adjacent to the tumor. However, recent molecular genetic studies of glioma suggest that it may be much more complicated than this (14).

In theory, boron neutron capture therapy (BNCT) provides a way to selectively destroy malignant cells and spare normal cells. It is based on the nuclear capture and fission reactions that occur when boron-10, which is a nonradioactive constituent of natural elemental boron, is irradiated with low energy thermal neutrons to yield high linear energy-transfer (LET) alpha particles (^{4}He) and recoiling lithium-7 (^{7}Li) nuclei, as shown below.


^{10}B + n_{th} (0.025 eV) → [^{11}B]
^{4}He + ^{7}Li + 2.79 MeV (6%)
^{4}He + ^{7}Li + 2.31 MeV (94%)
↓
^{7}Li + γ + 0.48 MeV

In order for BNCT to be successful, a sufficient amount of ^{10}B must be selectively delivered to the tumor ($\sim 20\ \mu g \cdot g^{-1}$ weight or $\sim 10^9$ atoms/cell), and enough thermal neutrons must be absorbed by them to sustain a lethal ^{10}B(n, α) ^{7}Li capture reaction. Since the high LET particles have limited boron pathlengths in tissue (5–9 μm), the destructive effects of these high energy particles is limited to cells containing boron. Clinical interest in BNCT has focused primarily on the treatment of high grade gliomas (15), and either cutaneous primaries (16) or cerebral metastases of melanoma (17), and most recently head and neck and liver cancer. Since BNCT is a biologically rather than physically targeted type of radiation treatment, the potential exists to destroy tumor cells dispersed in the normal tissue parenchyma, if sufficient amounts of ^{10}B and thermal neutrons are delivered to the target volume. This article covers radiobiological considerations upon which BNCT is based, boron agents and optimization of their delivery, neutron sources, which at this time are exclusively nuclear reactors, past and ongoing clinical studies, and critical issues that must be addressed if BNCT is to be successful. Readers interested in more in-depth coverage of these and other topics related to BNCT are referred to several recent reviews and monographs (15,18–20).

RADIOBIOLOGICAL CONSIDERATIONS

Types of Radiation Delivered

The radiation doses delivered to tumor and normal tissues during BNCT are due to energy deposition from three types of directly ionizing radiation that differ in their LET characteristics: (*1*) low LET γ rays, resulting primarily from the capture of thermal neutrons by normal tissue hydrogen atoms [$^{1}H(n,\gamma)^{2}H$]; (*2*) high LET protons, produced by the scattering of fast neutrons and from the capture of thermal neutrons by nitrogen atoms [$^{10}N(n,p)^{14}C$]; and (*3*) high LET, heavier charged alpha particles (stripped down ^{4}He nuclei) and lithium-7 ions, released as products of the thermal neutron capture and fission reactions with ^{10}B [$^{10}B(n,\alpha)^{7}Li$]. The greater density of ionizations along tracks of high LET particles results in an increased biological effect compared to the same physical dose of low LET radiation. Usually, this is referred to as relative biological effectiveness (RBE), which is the ratio of the absorbed dose of a reference source of radiation (e.g., X rays) to that of the test radiation that produces the same biological effect. Since both tumor and surrounding normal tissues are present in the radiation field, even with an ideal epithermal neutron beam, there will be an unavoidable, nonspecific background dose, consisting of both high and low LET radiation. However, a higher concentration of ^{10}B in the tumor will result in it receiving a higher total dose than that of adjacent normal tissues, which is the basis for the therapeutic gain in BNCT (21). As recently reviewed by one of us (18), the total radiation dose delivered to any tissue can be expressed in photon-equivalent units as the sum of each of the high LET dose components multiplied by weighting factors, which depend on the increased radiobiological effectiveness of each of these components.

Biological Effectiveness Factors

The dependence of the biological effect on the microdistribution of ^{10}B requires the use of a more appropriate term than RBE to define the biological effects of the $^{10}B(n,\alpha)^{7}Li$ reaction. Measured biological effectiveness factors for the components of the dose from this reaction have been termed compound biological effectiveness (CBE) factors and are drug dependent (21–23). The mode and route of drug administration, the boron distribution within the tumor, normal tissues, and even more specifically within cells, and even the size of the nucleus within the target cell population all can influence the experimental determination of the CBE factor. Therefore, CBE factors are fundamentally different from the classically defined RBE, which primarily is dependent on the quality (i.e., LET) of the radiation administered. The CBE factors are strongly influenced by the distribution of the specific boron delivery agent, and can differ substantially, although they all describe the combined effects of alpha particles and ^{7}Li ions. The CBE factors for the boron component of the dose are specific for both the boron-10 delivery agent and the tissue. A weighted gray (Gy) unit [Gy(w)] has been used to express the summation of all BNCT dose components and indicates that the appropriate RBE and CBE factors have been applied to the high LET dose components. However, for clinical BNCT the overall calculation of photon-equivalent [Gy(w)] doses requires a number of assumptions about RBEs, CBE factors, and the boron concentrations in various tissues that have been based on the currently available human or experimental data (24,25).

Clinical Dosimetry

The following biological weighting factors, summarized in Table 1, have been used in all of the recent clinical trials in patients with high grade glioma, using BPA in combination with an epithermal neutron beam. The $^{10}B(n,\alpha)^{7}Li$ component of the radiation dose to the scalp has been based on the measured boron concentration in the blood at the time of BNCT, assuming a blood:scalp boron concentration ratio of 1.5:1 (26,27,29) and a CBE factor for BPA in skin of 2.5 (29). An RBE of 3.2 has been used in all tissues for the high LET components of the beam: protons resulting from the capture reaction with nitrogen, and recoil protons resulting from the collision of fast neutrons with hydrogen (26,27,30). It must be emphasized that the tissue distribution of the boron delivery agent in humans should be similar to that in the experimental animal model in order to use the experimentally derived values for estimation of Gy(w) doses in clinical radiations.

Dose calculations become much more complicated when combinations of agents are used. At its simplest, this could be the two low molecular weight drugs boronophenylalanine (BPA) and sodium borocaptate (BSH). These have been shown to be highly effective when used in combination to treat F98 glioma bearing rats (31,32), and currently are being used in combination in a clinical study in Japan (33). Since it currently is impossible to know the true

Table 1. Assumptions Used in the Clinical Trials of BPA Based BNCT for Calculation of the $^{10}B(n,\alpha)^{7}Li$ Component of the Gy(w) Dose in Various Tissue

Tissue	Boron Concentration[a]	CBE Factor
Blood	measured directly	
Brain	1.0 × blood (26,27)	1.3 (23)
Scalp–skin	1.5 × blood (26–28)	2.5 (29)
Tumor	3.5 × blood (28)	3.8 (21)

[a] An RBE of 3.2 is used for the high LET component of the beam dose: protons from the $^{14}N(n,n)^{14}C$ reaction, and the recoil protons from fast neutron collisions with hydrogen. Literature references are given in parentheses.

biodistribution of each drug, dosimetric calculations in experimental animals have been based on independent boron determinations in other tumor bearing animals that have received the same doses of drugs but *not* BNCT. More recently, the radiation delivered has been expressed as a physical dose rather than using CBE factors to calculate an RBE equivalent dose (34). The calculations are further complicated if low and high molecular weight delivery agents are used in combination with one another. Tumor radiation dose calculations, therefore, are based on multiple assumptions regarding boron biodistribution, which may vary from patient to patient, as well as within different regions of the tumor and among tumor cells. However, normal brain boron concentrations are much more predictable and uniform, and therefore, it has been shown to be both *safe* and *reliable* to base dose calculations on normal brain tolerance.

BORON DELIVERY AGENTS

General Requirements

The development of boron delivery agents for BNCT began ~50 years ago and is an ongoing and difficult task of the highest priority. The most important requirements for a successful boron delivery agent are (*1*) low systemic toxicity and normal tissue uptake with high tumor uptake and concomitantly high tumor/brain (T/Br) and tumor/blood (T/Bl) concentration ratios (>3-4:1); (*2*) tumor concentrations in the range of ~20 $\mu g\ {}^{10}B \cdot g^{-1}$ tumor; (*3*) rapid clearance from blood and normal tissues and persistence in tumor during BNCT. However, at this time *no* single boron delivery agent fulfills all of these criteria. With the development of new chemical synthetic techniques and increased knowledge of the biological and biochemical requirements needed for an effective agent and their modes of delivery, a number of promising new boron agents has emerged (see examples in Fig. 1). The major challenge in their development has been the requirement for selective tumor targeting in order to achieve boron concentrations sufficient to deliver therapeutic doses of radiation to the tumor with minimal normal tissue toxicity. The selective destruction of GBM cells in the presence of normal cells represents an even greater challenge compared to malignancies at other anatomic sites, since high grade gliomas are highly infiltrative of normal brain, histologically complex, and heterogeneous in their cellular composition.

First- and Second-Generation Boron Delivery Agents

The clinical trials of BNCT in the 1950s and early 1960s used boric acid and some of its derivatives as delivery agents, but these simple chemical compounds were nonselective, had poor tumor retention, and attained low T/Br ratios (35,36). In the 1960s, two other boron compounds emerged from investigations of hundreds of low molecular weight boron-containing chemicals, one, (L)-4-dihydroxyborylphenylalanine, referred to as BPA (compound **1**) was based on arylboronic acids (37), and the other was based on a newly discovered polyhedral borane anion, sodium mercaptoundecahydro-*closo*-dodecaborate (38), referred to as BSH (compound **2**). These "second" generation compounds had low toxicity, persisted longer in animal tumors compared with related molecules, and their T/Br and T/Bl boron ratios were > 1. As described later in this article, ^{10}B enriched BPA, complexed with fructose to improve its water solubility, and BSH have been used clinically in Japan, the United States, and Europe. Although these drugs are not ideal, their safety following intravenous (i.v.) administration has been established. Over the past 20 years, several other classes of boron-containing compounds have been designed and synthesized in order to fulfill the requirements indicated at the beginning of this section. Detailed reviews of the state-of-the-art in compound development for BNCT have been published (39–42), and in this overview, only the main classes of compounds are summarized with an emphasis on recently published work in the area. The general biochemical requirements for an effective boron delivery agent are also discussed.

Third Generation Boron Delivery Agents

So-called "third" generation compounds mainly consist of a stable boron group or cluster attached via a hydrolytically stable linkage to a tumor-targeting moiety, such as low molecular weight biomolecules or monoclonal antibodies (MoAbs). For example, the targeting of the epidermal growth factor receptor (EGFR) and its mutant isoform EGFRvIII, which are overexpressed in gliomas and squamous cell carcinomas of the head and neck, also has been one such approach (43). Usually, these low molecular weight biomolecules have been shown to have selective targeting properties and many are at various stages of development for cancer chemotherapy, photodynamic therapy (PDT) or antiviral therapy. The tumor cell nucleus and DNA are especially attractive targets since the amount of boron required to produce a lethal effect may be substantially reduced, if it is localized within or near the nucleus (44). Other potential subcellular targets are mitochondria, lysosomes, endoplasmic reticulum, and the Golgi apparatus. Water solubility is an important factor for a boron agent that is to be administered systemically, while lipophilicity is necessary for it to cross the blood–brain barrier (BBB) and diffuse within the brain and the tumor. Therefore, amphiphilic compounds possessing a suitable balance between hydrophilicity and lipophilicity have been of primary interest since they should provide the most favorable differential boron concentrations between tumor and normal brain, thereby enhancing tumor specificity. However, for low molecular weight molecules that target specific biological transport systems and/or are incorporated into a delivery vehicle (e.g., liposomes) the amphiphilic character is not as crucial. The molecular weight of the boron-containing delivery agent also is an important factor, since it determines the rate of diffusion both within the brain and the tumor.

LOW MOLECULAR WEIGHT AGENTS

Boron-Containing Amino Acids and Polyhedral Boranes

Recognizing that BPA and BSH are not ideal boron delivery agents, considerable effort has been directed toward



Figure 1. Some low molecular weight BNCT agents under investigation. Compound **1** (BPA) and compound **2** (BSH) are currently in clinical use in the United States, Japan, and Europe. Compound **3** (GB-10) has shown promise in animal models, as have the nucleoside derivatives D-CDU (compound **4**) and N5-2OH (compound **5**). Compound **6**, a trimethoxyindole derivative, has shown promise *in vitro* and compound **7**, a porphyrin derivative, was shown to be tumor selective. The maltose derivative **8** has shown low cytotoxicity and tumor cell uptake *in vitro*, the biphosphonate **9** has tumor targeting ability and the dequalinium derivative DEQ-B (compound **10**) has shown promise in *in vitro* studies.

the design and synthesis of third generation, boron-containing amino acids and functionalized polyhedral borane clusters. Examples include various derivatives of BPA and other boron-containing amino acids (e.g., glycine, alanine, aspartic acid, tyrosine, cysteine, methionine), as well as non-naturally occurring amino acids (45–50). The most recently reported delivery agents contain one or more boron clusters and concomitantly larger amounts of boron by weight compared with BPA. The advantages of such compounds are that they potentially can deliver higher concentrations of boron to tumors without increased toxicity. The polyhedral borane dianions, *closo*-$\mathrm{B}_{10}\mathrm{H}_{10}^{2-}$ and *closo*-$\mathrm{B}_{12}\mathrm{H}_{12}^{2-}$ and the icosahedral carboranes *closo*-$\mathrm{C}_2\mathrm{B}_{10}\mathrm{H}_{12}$ and *nido*-$\mathrm{C}_2\mathrm{B}_9\mathrm{H}_{12}^{-}$, have been the most attractive boron clusters for linkage to targeting moieties, due to their relatively easy incorporation into organic molecules, high boron content, chemical and hydrolytic stability, hydrophobic character and, in most cases, their negative charge. The simple sodium salt of *closo*-$\mathrm{B}_{10}\mathrm{H}_{10}^{2-}$ (GB-10, compound **3**) has been shown to have tumor-targeting ability and low systemic toxicity in animal models (42) and has been considered as a candidate for clinical evaluation (51). Other polyhedral borane anions with high boron content include derivatives of $\mathrm{B}_{20}\mathrm{H}_{18}^{2-}$, although these compounds have shown little tumor specificity, and therefore may be better candidates for encapsulation into either targeted or non-targeted liposomes (52,53) and folate receptor targeting, boron containing polyamidoamino (PAMAM) dendrimers (54) and liposomes (55). Boron-containing dipeptides also have shown low toxicity and good tumor-localizing properties (56,57).

Biochemical Precursors and DNA Binding Agents

Several boron-containing analogs of the biochemical precursors of nucleic acids, including purines, pyrimidines, nucleosides, and nucleotides, have been synthesized and evaluated in cellular and animal studies (58–62). Some of these compounds [e.g., β-5-*o*-carboranyl-2'-deoxyuridine (D-CDU, compound **4**] and the 3-(dihydroxypropyl-carboranyl-pentyl)thymidine derivative N5-2OH (compound **5**), have shown low toxicities, selective tumor cell uptake, and significant rates of phosphorylation into the corresponding nucleotides (63–65). Intracellular nucleotide formation potentially can lead to enhanced tumor uptake and retention of these types of compounds (64,65).

Another class of low molecular weight delivery agents are boron-containing DNA binding molecules (e.g., alkylating agents, intercalators, groove binders, and polyamines). Some examples are derivatives of aziridines, acridines, phenanthridines (compound **6**), trimethoxyindoles, carboranylpolyamines, Pt(II)–amine complexes, di- and tribenzimidazoles (66–69). A limitation of boron-containing polyamines is their frequently observed *in vitro* and *in vivo* toxicity, although promising derivatives with low cytotoxicity have been synthesized (70–73). Other nuclear-targeting molecules are *nido*-carboranyl oligomeric phosphate diesters (OPDs). Despite their multiple negative charges, OPDs have been shown to target the nuclei of TC7 cells following microinjection (74), suggesting that the combination of OPDs with a cell-targeting molecule capable of crossing the plasma membrane could provide both selectivity and nuclear binding. Such a conjugate has been designed and synthesized (75), although its biological evaluation has yet to be reported.

Boron-Containing Porphyrins and Related Structures

Several boron-containing fluorescent dyes, including porphyrin, tetrabenzoporphyrin, and phthalocyanine derivatives have been synthesized and evaluated (76–79). These have the advantage of being easily detected and quantified by fluorescence microscopy, and have the potential for interacting with DNA due to their planar aromatic structures. Among these macrocycles, boron-containing porphyrins (e.g., compound **7**: H_2DCP) have attracted special attention due to their low systemic toxicity compared with other dyes, easy synthesis with high boron content, and their remarkable stability (79–82). Porphyrin derivatives have been synthesized that contain up to 44% boron by weight using *closo*- or *nido*-carborane clusters linked to the porphyrin macrocycle via ester, amide, ether, methylene, or aromatic linkages (76–85). The nature of these linkages is believed to influence their stability and systemic toxicity. Therefore, with these and other boron delivery agents, chemically stable carbon–carbon linkages have been preferred over ester and amide linkages that potentially can be cleaved *in vivo*. Boron-containing porphyrins have excellent tumor-localizing properties (76–82) and have been proposed for dual application as boron delivery agents and photosensitizers for PDT of brain tumors (85–91). Our own preliminary data with H_2TCP (tetra[*nido*-carboranylphenyl]porphyrin), administered intracerebrally by means of convection enhanced delivery (CED) to F98 glioma bearing rats, showed tumor boron concentrations of 150 $\mu g \cdot g^{-1}$ tumor with concomitantly low normal brain and blood concentrations (92). Ozawa et al. recently described a newly synthesized polyboronated porphyrin, designated TABP-1, which was administered by CED to nude rats bearing intracerebral implants of the human glioblastoma cell line U-87 MG (93). High tumor and low blood boron concentrations were observed and both we and Ozawa have concluded that direct intracerebral administration of the carboranyl porphyrins by CED is superior to systemic administration. Furthermore, despite the bulkiness of the carborane cages, carboranylporphyrins have been shown to interact with DNA and thereby produce *in vitro* DNA damage following light activation (94,95). Boronated phthalocyanines have been synthesized, although these compounds usually have had decreased water solubility and an increased tendency to aggregate compared to the corresponding porphyrins (76,77,86,87). Boron-containing acridine molecules also have been reported to selectively deliver boron to tumors with high T/Br and T/Bl ratios, whereas phenanthridine derivatives were found to have poor specificity for tumor cells (94–98).

Other Low Molecular Weight Boron Delivery Agents

Carbohydrate derivatives of BSH and other boron-containing glucose, mannose, ribose, gulose, fucose, galactose, maltose (e.g., compound **8**) and lactose molecules have been synthesized, and some of these compounds have been evaluated in both *in vitro* and *in vivo* studies (99–105). These compounds usually are highly water soluble and as a possible consequence of this, they have shown both low toxicity and uptake in tumor cells. It has been suggested that these hydrophilic low molecular weight derivatives have poor ability to cross tumor cell membranes. However, they might selectively accumulate within the glycerophospholipid membrane bilayer and in other areas of the tumor, such as the vasculature.

Low molecular weight boron-containing receptor-binding molecules have been designed and synthesized. These have been mainly steroid hormone antagonists, such as derivatives of tamoxifen, 17β-estradiol, cholesterol, and retinoic acid (106–110). The biological properties of these agents depend on the density of the targeted receptor sites, although to date very little biological data have been reported. Other low molecular weight boron-containing compounds that have been synthesized include phosphates, phosphonates (e.g., compound **9**) phenylureas, thioureas, nitroimidazoles, amines, benzamides, isocyanates, nicotinamides, azulenes, and dequalinium derivatives (e.g., dequalinium-B, compound **10**) (111–113). Since no single chemical compound, as yet synthesized, has the requisite properties, the use of *multiple* boron delivery agents is probably essential for targeting different subpopulations of tumor cells and subcellular sites. Furthermore, lower doses of each individual agent would be needed, which could reduce systemic toxicity while at the same time enhancing tumor boron levels to achieve a therapeutic effect.

HIGH MOLECULAR WEIGHT AGENTS

Monoclonal Antibodies, Other Receptors Targeting Agents and Liposomes

High molecular weight delivery agents (e.g., MoAbs and their fragments), which can recognize a tumor-associated epitope, have been (114–116) and continue to be of interest to us (117,118) as boron delivery agents. Although they can be highly specific, only very small quantities reach the brain and tumor following systemic administration (119) due to their rapid clearance by the reticuloendothelial system and the BBB, which effectively limits their ability to cross capillary vascular endothelial cells. Boron-containing bioconjugates of epidermal growth factor (EGF) (120,121), the receptor which is overexpressed on a variety of tumors, including GBM (122,123), also have been investigated as potential delivery agents to target brain tumors. However, it is unlikely that either boronated antibodies or other bioconjugates would attain sufficiently high concentrations in the brain following systemic administration, but, as described later in this section, direct intracerebral delivery could solve this problem. Another approach would be to directly target the vascular endothelium of brain tumors using either boronated MoAbs or VEGF, which would recognize amplified VEGF receptors. The use of boron-containing VEGF bioconjugates would obviate the problem of passage of a high molecular weight agent across the BBB, but their use would most likely require repeated applications of BNCT, since tumor neovasculature can continuously regenerate. Backer et al. reported that targeting a Shiga-like toxin-VEGF fusion protein was selectively toxic to vascular endothelial cells overexpressing VEGFR-2 (124). Recently, a bioconjugate has been produced by chemically linking a heavily boronated PAMAM dendrimer to VEGF (125). This selectively targeted tumor blood vessels overexpressing VEGFR-2 in mice bearing 4T1 breast carcinoma. There also has been a longstanding interest on the use of boron-containing liposomes as delivery agents (52,53,126,127), but their size has limited their usefulness as brain tumor targeting agents, since they are incapable of traversing the BBB unless they have diameters <50 nm (128). If, on the other hand, they were administered intracerebrally or were linked to an actively transported carrier molecule (e.g., transferin), or alternatively if the BBB was transiently opened, these could be very useful delivery agents, especially for extracranial tumors (e.g., liver cancer).

Recent work of one of us (R.F.B.) has focused on the use of a chemeric MoAb, cetuximab (IMC-C225 also known as Erbitux), produced by ImClone Systems, Inc. This antibody recognizes both wild-type EGFR and its mutant isoform, EGFRvIII (129), and has been approved for clinical use by the U.S. Food and Drug Administration (FDA) for the treatment of EGFR(+) recurrent colon cancer. Using previously developed methodology (114), a precision macromolecule, a polyamido amino (PAMAM or “starburst”) dendrimer has been heavily boronated and then linked by means of heterobifunctional reagents to EGF (121), cetuximab (118) or another MoAb, L8A4, which is specifically directed against EGFRvIII (130). In order to completely bypass the BBB, the bioconjugates were administered by either direct intratumoral (i.t.) injection (131) or CED (132) to rats bearing intracerebral implants of the F98 glioma that had been genetically engineered to express either wildtype EGFR (131) or EGFRvIII (133). Administration by either of these methods resulted in tumor boron concentrations that were in the therapeutic range (i.e., $\sim 20\ \mu g \cdot g^{-1}\ wt^{-1}$ tumor). Similar data also were obtained using boronated EGF, and based on the favorable uptake of these bioconjugates, therapy studies were initiated at the Massachusetts Institute of Technology nuclear reactor (MITR). The mean survival times (MST) of animals that received either boronated cetuximab (134) or EGF (135) were significantly prolonged compared to those of animals bearing receptor negative tumors. A further improvement in MSTs was seen if the animals received BPA, administered i.v., in combination with the boronated bioconjugates, thereby validating our thesis that combinations of agents may be superior to any single agent (32). As can be seen from the preceding discussion, the design and synthesis of low and high molecular weight boron agents have been the subject of intensive investigation. However, optimization of their delivery has not received enough attention, but nevertheless is of critical importance.

OPTIMIZING DELIVERY OF BORON CONTAINING AGENTS

General Considerations

Delivery of boron agents to brain tumors is dependent on (*1*) the plasma concentration profile of the drug, which depends on the amount and route of administration; (*2*) the ability of the agent to traverse the BBB; (*3*) blood flow within the tumor, and (*4*) the lipophilicity of the drug. In general, a high steady-state blood concentration will maximize brain uptake, while rapid clearance will reduce it, except in the case of intraarterial (i.a.) drug administration. Although the i.v. route currently is being used clinically to administer both BSH and BPA, this may not be ideal and other strategies may be needed to improve their delivery. Delivery of boron-containing drugs to extracranial tumors, such as head and neck and liver cancer, present a different set of problems, including nonspecific uptake and retention in adjacent normal tissues.

Intra-arterial Administration with or without Blood–Brain Barrier Disruption

As shown in experimental animal studies (31,32,134–136) Enhancing the delivery of BPA and BSH can have a dramatic effect both on increasing tumor boron uptake and the efficacy of BNCT. This has been demonstrated in the F98 rat glioma model where intracarotid (i.c.) injection of either BPA or BSH doubled the tumor boron uptake compared to that obtained by i.v. injection (31). This was increased fourfold by disrupting the BBB by infusing a hyperosmotic (25%) solution of mannitol via the internal carotid artery. Mean survival times (MST)of animals that received either BPA or BSH i.c. with BBB-D were increased 295 and 117%, respectively, compared to irradiated controls (31). The best survival data were obtained using both BPA and BSH in combination, administered by i.c. injection with BBB-D. The MST was 140 days with a cure rate of 25%, compared to 41 days following i.v. injection with no long-term surviving animals (32). Similar data have been obtained using a rat model for melanoma metastatic to the brain. BPA was administered i.c. to nude rats bearing intracerebral implants of the human MRA 27 melanoma with or without BBB-D. The MSTs were 104–115 days with 30% long-term survivors compared to a MST of 42 days following i.v. administration (134). A similar enhancement in tumor boron uptake and survival was observed in F98 glioma bearing rats following i.c. infusion of the bradykinin agonist, RMP-7 (receptor mediated permeabilizer-7), now called Cereport (136,137). In contrast to the increased tumor uptake, normal brain boron values at 2.5 h following i.c. injection were very similar for the i.v. and i.c. routes with or without BBB-D. Since BNCT is a binary system, normal brain boron levels only are of significance at the time of irradiation and high values at earlier time points are inconsequential. These studies have shown that a significant therapeutic gain can be achieved by optimizing boron drug delivery, and this should be important for both ongoing and future clinical trials using BPA and/or BSH.

Direct Intracerebral Delivery

Different strategies may be required for other low molecular weight boron-containing compounds whose uptake is cell cycle dependent, such as boron-containing nucleosides, where continuous administration over a period of days may be required. We recently have reported that direct i.t. injection or CED of the borononucleoside N5-2OH (compound **5**) were both effective in selectively delivering potentially therapeutic amounts of boron to rats bearing intracerebral implants of the F98 glioma (61). Direct i.t. injection or CED most likely will be necessary for a variety of high molecular weight delivery agents such as boronated MoAbs (138) and ligands such as EGF (132), as well as for low molecular weight agents (e.g., nucleosides and porphyrins). Recent studies have shown that CED of a boronated porphyrin derivative similar to compound **7**, designated H_2DCP, resulted in the highest tumor boron values and T/Br and T/Bl ratios that have been seen with any of the boron agents that have been studied (92).

NEUTRON SOURCES FOR BNCT

Nuclear Reactors

Neutron sources for BNCT currently are limited to nuclear reactors and in the present section only information that is described in more detail in a recently published review will be summarized (139). Reactor derived neutrons are classified according to their energies as thermal $E_n < 0.5$ eV), epithermal ($0.5\,\text{eV} < E_n < 10$ keV), or fast ($E_n > 10$ keV). Thermal neutrons are the most important for BNCT since they usually initiate the $^{10}B(n,\alpha)^7Li$ capture reaction. However, because they have a limited depth of penetration, epithermal neutrons, which lose energy and fall into the thermal range as they penetrate tissues, are now preferred for clinical therapy. A number of reactors with very good neutron beam quality have been developed and currently are being used clinically. These include (*1*) MITR, shown schematically in Fig. 2 (140); (*2*) clinical reactor at Studsvik Medical AB in Sweden (141); (*3*) the FRi1 clinical reactor in Helsinki, Finland (142); (*4*) R2-0 High Flux Reactor (HFR) at Petten in the Netherlands (143); (*5*) LVR-15 reactor at the Nuclear Research Institute (NRI) in Rez, Czech Republic (144); (*6*) Kyoto University Research Reactor (KURR) in Kumatori, Japan (145); (*7*) JRR4 at the Japan Atomic Energy Research Institute (JAERI) (146); and (*8*) the RA-6 CNEA reactor in Bariloche, Argentina (147). Other reactor facilities are being designed, notably the TAPIRO reactor at the ENEA Casaccia Center near Rome, Italy, which is unique in that it will be a low-power fast-flux reactor (148), and a facility in South Korea. Two reactors that have been used in the past for clinical BNCT are the Musashi Institute of Technology (MuITR) reactor in Japan and the Brookhaven Medical Research Reactor (BMRR) at the Brookhaven National Laboratory (BNL) in Upton, Long Island, New York (26,27,149). The MuITR was used by Hatanaka (150) and later by Hatanaka and Nakagawa (151). The BMRR was used for the clinical trial that was conducted at the Brookhaven National Laboratory between 1994 and 1999 (27,152) and the results are described in detail later in this section. Due to a variety of reasons, including the cost of maintaining the BMRR, it has been deactivated and is no longer available for use.

Reactor Modifications

Two approaches are being used to modify reactors for BNCT. The first or direct approach, is to moderate and filter neutrons that are produced in the reactor core. The second, the fission converter-plate approach, is indirect in that neutrons from the reactor core create fissions within a converter-plate that is adjacent to the moderator assembly, and these produce a neutron beam at the patient port. The MITR (153), which utilizes a fission converter-plate, currently sets the standard for the world for the combination of high neutron beam quality and short treatment time. It operates at a power of 5 MW and has been used for clinical as well as experimental studies for BNCT. Although the power is high compared to the majority of other reactors that are being used, the treatment time is unusually short, since it utilizes a fission converter-plate to create the neutron beam. All other reactors use the direct approach to produce neutron beams for BNCT. Three examples are the FiR1 reactor in Finland (142), the Studsvik reactor in Sweden (141), and the Washington State University (WSU) reactor in the United States (154), which was built for the treatment of both small and large experimental animals.

Accelerators

Accelerators also can be used to produce epithermal neutrons and accelerator based neutron sources (ABNSs) are being developed in a number of countries (155–161), and interested readers are referred to a recently published detailed review on this subject (28). For ABNSs, one of the more promising nuclear reactions involves bombarding a ^{7}Li target with 2.5 MeV protons. The average energy of



Figure 2. Schematic diagram of the MITR. The fission converter based epithermal neutron irradiation (FCB) facility is housed in the experimental hall of the MITR and operates in parallel with other user applications. The FCB contains an array of 10 spent MITR-II fuel elements cooled by forced convection of heavy water coolant. A shielded horizontal beam line contains an aluminum and Teflon filter-moderator to tailor the neutron energy spectrum into the desired epithermal energy range. A patient collimator defines the beam aperture and extends into the shielded medical room to provide circular apertures ranging from 16 to 8 cm in diameter. The in-air epithermal flux for the available field sizes ranges from 3.2 to 4.6×10^9 $\mathrm{n \cdot cm^{-2} \cdot s^{-1}}$ at the patient position. The measured specific absorbed doses are constant for all field sizes and are well below the inherent background of 2.8×10^{-12} RBE $\mathrm{Gy \cdot cm^2 \cdot n^{-1}}$ produced by epithermal neutrons in tissue. The dose distributions achieved with the FCB approach the theoretical optimum for BNCT.

the neutrons that are produced is 0.4 MeV and the maximum energy is 0.8 MeV. Reactor derived fission neutrons have greater average and maximum energies than those resulting from the ^{7}Li(p,n)^{7}Be reaction. Consequently, the thickness of the moderator material that is necessary to reduce the energy of the neutrons from the fast to the epithermal range is less for an ABNS than it is for a reactor. This is important since the probability that a neutron will be successfully transported from the entrance of the moderator assembly to the treatment port decreases as the moderator assembly thickness increases. Due to lower and less widely distributed neutron source energies, ABNS potentially can produce neutron beams with an energy distribution that is equal to or better than that of a reactor. However, reactor derived neutrons can be well collimated, while on the other hand, it may not be possible to achieve good collimation of ABNS neutrons at reasonable proton beam currents. The necessity of good collimation for the effective treatment of GBM, is an important and unresolved issue that may affect usefulness of ABNS for BNCT. The ABNSs are also compact enough to be sited in hospitals thereby allowing for more effective, but technically more complicated procedures to carry out BNCT. However, to date, no accelerator has been constructed with a beam quality comparable to that of the MITR, which can be sited in a hospital and that provides a current of sufficient magnitude to treat patients in <30 min. Furthermore, issues relating to target manufacture and cooling must be solved before ABNS become a reality. The ABNS that is being developed at the University of Birmingham in England, by modifying a Dynamitron linear electrostatic accelerator (155), may be the first facility where patients will be treated, although progress has been slow. Another ABNS being constructed by LINAC Systems, Inc. in Albuquerque, New Mexico (162), and this could be easily sited in a hospital and produce an epithermal neutron beam.

Beam Optimization

For both reactors and ABNSs, a moderator assembly is necessary to reduce the energy of the neutrons to the epithermal range. The neutrons comprising the neutron beam have a distribution of energies and are accompanied by unwanted X rays and gamma photons. A basic tenet of BNCT is that the dose of neutrons delivered to the target volume should not exceed the tolerance of normal tissues, and this applies to neutron beam design, as well as to treatment planning (25). The implications of this for beam design is that the negative consequences of increased normal tissue damage for a more energetic neutron beams at shallow depths, outweighs the benefits of more deeply penetrating energetic neutrons. For fission reactors, the average energy of the neutrons produced is ~2 MeV, but small numbers have energies as high as 10 MeV. There is generally a trade off between treatment time and the optimum beam for patient treatment in terms of the energy distribution of the neutrons and the contamination of the neutron beam with X rays and gamma photons. Not surprisingly, reactors with the shortest treatment time (i.e., the highest normal tissue dose rate) operate at the highest power, since the number of neutrons that is produced per unit time is proportional to the power, measured in megawatts. Furthermore, high beam quality is most easily achieved using reactors with high power, since a larger fraction of the neutrons can be filtered, as the neutrons traverse the moderator assembly without making the treatment time exceedingly long.

CLINICAL STUDIES OF BNCT FOR BRAIN TUMORS

Early Trials

Although the clinical potential of BNCT was recognized in the 1930s (163), it was not until the 1950s that the first clinical trials were initiated by Farr at the BNL (145,163) and by Sweet and Brownell at the Massachusetts General Hospital (MGH) using the MIT reactor (36,164,165). The disappointing outcomes of these trials, which ended in 1961 and subsequently were carefully analyzed by Slatkin (166), were primarily attributable to (*1*) inadequate tumor specificity of the inorganic boron chemicals that had been used as capture agents; (*2*) insufficient tissue penetrating properties of the thermal neutron beams; and (*3*) high blood boron concentrations that resulted in excessive damage to normal brain vasculature and to the scalp (36,164,165).

Japanese Clinical Trials

Clinical studies were resumed by Hatanaka in Japan in 1967, following a 2 year fellowship in Sweet's laboratory at the MGH, using a thermal neutron beam and BSH, which had been developed as a boron delivery agent by Soloway at the MGH (38). In Hatanaka's procedure (150,151), as much of the tumor was surgically removed as possible (debulking), and at some time thereafter, BSH (compound **2**) was administered by a slow infusion, usually intra-arterially (150), but later intravenously (151). Later (12–14 h) BNCT, was carried out at one or another of several different nuclear reactors. Since thermal neutrons have a limited depth of penetration in tissue, this necessitated reflecting the skin and raising the bone flap in order to directly irradiate the exposed brain. This eliminated radiation damage to the scalp and permitted treatment of more deep-seated residual tumors. As the procedure evolved over time, a ping–pong ball or silastic sphere was inserted into the resection cavity as a void space to improve neutron penetration into deeper regions of the tumor bed and adjacent brain (150,151,167,168). This is a major difference between the procedure carried out by Hatanaka, Nakagawa and other Japanese neurosurgeons and the BNCT protocols that have been carried out in the United States and Europe, which have utilized epithermal neutron beams that have not required reflecting the scalp and raising the bone flap at the time of irradiation. This has made it difficult to directly compare the Japanese clinical results with those obtained elsewhere, and this has continued on until very recently when the Japanese started using epithermal neutron beams (33). Most recently, Miyatake et al. initiated a clinical study utilizing the combination of BSH and BPA, both of which were administered i.v. at 12 and 1 h, respectively, prior to irradiation with an epithermal neutron beam (33). A series of 11 patients with high grade gliomas have been treated, and irrespective of the initial tumor volume, magnetic resonance imaging (MRI) and computed tomography (CT) images showed a 17–51% reduction in tumor volume that reached a maximum of 30–88%. However, the survival times of these patients were not improved over historical controls and further studies are planned to improve the delivery of BPA and BSH, which may enhance survival.

Analysis of the Japanese Clinical Results

Retrospective analysis of subgroups of patients treated in Japan by Hatanaka and Nakagawa (167,168) have described 2, 5, and 10 year survival rates (11.4, 10.4, and 5.7%, respectively) that were significantly better than those observed among patients treated with conventional, fractionated, external beam photon therapy. However, a cautionary note was sounded by Laramore and Spence (169) who analyzed the survival data of a subset of 12 patients from the United States who had been treated by Hatanaka between 1987 and 1994. They concluded that there were no differences in their survival times compared to those of age matched controls, analyzed according to the stratification criteria utilized by Curran et al. (6). In a recent review of Hatanaka's clinical studies, Nakagawa reported that the physical dose from the $^{10}B(n,\alpha)^{7}Li$ reaction, delivered to a target point 2 cm beyond the surgical margin, correlated with survival (168). For 66 patients with GBMs, those who survived <3 years ($n = 60$) had a minimum target point dose of 9.5±5.9 Gy, whereas those who survived >3 years ($n = 6$) had a minimum target point dose of 15.6±3.1 Gy from the $^{10}B(n,\alpha)^{7}Li$ reaction (168). The boron concentrations in brain tissue at the target point, which are required to calculate the physical radiation dose attributable to the $^{10}B(n,\alpha)^{7}Li$ capture reaction, were estimated to be 1.2X that of the patient's blood boron concentration (170).

OTHER RECENT AND ONGOING CLINICAL TRIALS

Beginning in 1994 a number of clinical trials, summarized in Table 2, were initiated in the United States and Europe. These marked a transition from low energy thermal neutron irradiation to the use of higher energy epithermal neutron beams with improved tissue penetrating properties, which obviated the need to reflect skin and bone flaps prior to irradiation. Up until recently, the procedure carried out in Japan required neurosurgical intervention immediately prior to irradiation, whereas the current epithermal neutron-based clinical protocols are radiotherapeutic procedures, performed several weeks after debulking surgery. Clinical trials for patients with brain tumors were initiated at a number of locations including (*1*) the

Table 2. Summary of Current or Recently Completed Clinical Trials of BNCT for the Treatment of Glioblastoma

Facility	Number of Patients	Duration of Administration	Drug	Dose, $mg \cdot kg^{-1}$	Boron Conc.,[a] $\mu g\, ^{10}B \cdot g^{-1}$	Estimated Peak Normal Brain Dose, Gy(w)	Average Normal Brain Dose, Gy(w)	References
HTR, MuITR, JRR, KURR, Japan	> 250 (1968–present)	1 h 1 h	BSH BPA	100 250	~ 20–30	13 Gy-Eq[b] ^{10}B component	Nd	168,169 33
HFR, Petten, The Netherlands	26 (1997–)	$100\, mg \cdot kg^{-1} \cdot min^{-1}$	BSH	100	30[c]	8.6–11.4 Gy-Eq[d] ^{10}B component	Nd	177
LVR-15, Rez, Czech Republic	5 (2001–present)	1 h	BSH	100	~20–30	<14.2	<2	178
BMRR Brookhaven	53 (1994–1999)	2 h	BPA	250–330	12–16	8.4–14.8	1.8–8.5	153,179
MITR-II, M67 MIT	20[e](1996–1999)	1–1.5 h	BPA	250–350	10–12	8.7–16.4	3.0–7.4	176
MITR-II, FCB MIT	6 (2001–2003)	1.5 h	BPA	350	~15			Unpublished
Studsvik AB Sweden	17 (30)[f](2001–2005)	6 h	BPA	900	24 (range: 15–34)	7.3–15.5	3.6–6.1	142
Fir I, Helsinki Finland	18 (1999–present) protocol P-01	2 h	BPA	290–400	12–15	8–13.5	3–6<7	143
Fir 1, Helsinki Finland	3 (2001–present)[g] protocol P-03	2 h	BPA	290	12–15	<8	2–3 <6	143

[a] During the irradiation.

[b] ^{10}B physical dose component dose to a point 2 cm deeper than the air-filled tumor cavity.

[c] Four fractions, each with a BSH infusion, $100\, mg \cdot kg^{-1}$ the first day, enough to keep the average blood concentration at $30\, \mu g\, ^{10}B \cdot g^{-1}$ during treatment on days 2–4.

[d] ^{10}B physical dose component at the depth of the thermal neutron fluence maximum.

[e] Includes two intracranial melanomas.

[f] J. Capala, unpublished, personal communication.

[g] Retreatment protocol for recurrent glioblastoma.

BMR at BNL from 1994–1999 for GBM using BPA with one or two neutron radiations, given on consecutive days (171–173); (*2*) the MITR from 1996–1999 for GBM and intracerebral melanoma (174,175); (*3*) the HFR, Petten, The Netherlands and the University of Essen in Germany in 1997 using BSH (176); (*4*) the FiR1 at the Helsinki University Central Hospital (142) in 1999 to the present; (*5*) the Studsvik reactor facility in Sweden from 2001 to June 2005, carried out by the Swedish National Neuro-Oncology Group (141), and finally (*6*) the NRI reactor in Rez, Czech Republic by Tovarys using BSH (177). The number of patients treated in this study is small and the followup is still rather short.

Initially, clinical studies using epithermal neutron beams were primarily Phase I safety and dose-ranging trials and a BNCT dose to a specific volume or critical region of the normal brain was prescribed. In both the BNL and the Harvard/MIT clinical trials, the peak dose delivered to a $1\, cm^3$ volume was escalated in a systematic way. As the dose escalation trials have progressed, the treatments have changed from single-field irradiations or parallel opposed irradiations, to multiple noncoplanar irradiation fields, arranged in order to maximize the dose delivered to the tumor. A consequence of this approach has been a concomitant increase in the average doses delivered to normal brain. The clinical trials at BNL and Harvard/MIT using BPA (compound **1**) and an epithermal neutron beam in the United States have now been completed.

Analysis of the Brookhaven and MIT Clinical Results

The BNL and Harvard/MIT studies have provided the most detailed data relating to normal brain tolerance following BNCT. A residual tumor volume of $60\, cm^3$ or greater lead to a greater incidence of acute CNS toxicity. This primarily was related to increased intracranial pressure, resulting from tumor necrosis and the associated cerebral edema (152,173,174). The most frequently observed neurological side effect associated with the higher radiation doses, other than the residual tumor volume-related effects, was radiation related somnolence (178). This is a well-recognized effect following whole brain photon irradiation (179), especially in children with leukemia or lymphoma, who have received CNS irradiation. However, somnolence is not a very well-defined radiation related endpoint because it frequently is diagnosed after tumor recurrence has been excluded. Therefore, it is not particularly well suited as a surrogate marker for normal tissue tolerance. In the dose escalation studies carried out at BNL (152,173), the occurrence of somnolence in the absence of a measurable tumor dose response was clinically taken as the maximum tolerated normal brain dose. The volume-averaged whole brain dose and the incidence of somnolence increased significantly as the BNL and Harvard/MIT trials progressed (175). The volume of tissue irradiated has been shown to be a determining factor in the development of side effects (180). Average whole brain doses greater than ~5.5 Gy(w) were associated with somnolence in the trial carried out at BNL, but not in all of the patients in the Harvard/MIT study (18,152,176). The BNL and Harvard/MIT trials were completed in 1999. Both produced median and 1-year survival times that were comparable to conventional external beam photon therapy (6). Although both were primarily Phase I trials to evaluate the safety of dose escalation as the primary endpoint for radiation related toxicity, the secondary endpoints were quality of life and time to progression and overall survival. The median survival times for 53 patients from the BNL trial and the 18 GBM patients from the Harvard/MIT trial were 13 months and 12 months, respectively. Following recurrence, most patients received some form of salvage therapy, which may have further prolonged overall survival. Time to progression, which would eliminate salvage therapy as a confounding factor, probably would be a better indicator of the efficacy of BNCT, although absolute survival time still is the "gold standard" for any clinical trial. The quality of life for most of the BNL patients was very good, especially considering that treatment was given in one or two consecutive daily fraction(s).

Clinical Trials Carried Out in Sweden and Finland

The clinical team at the Helsinki University Central Hospital and VTT (Technical Research Center of Finland) have reported on 18 patients using BPA as the capture agent (290 mg·kg^{-1} infused over 2 h) with two irradiation fields and whole brain average doses in the range of 3–6 Gy(w) (142). The estimated 1-year survival was 61%, which was very similar to the BNL data. This trial is continuing and the dose of BPA has been escalated to 450 mg·kg^{-1} and will be increased to 500 mg·kg^{-1}, infused over 2 h (H. Joensuu, personal communication). Since BNCT can deliver a significant dose to tumor with a relatively low average brain dose, this group also has initiated a clinical trial for patients who have recurrent GBM after having received full-dose photon therapy. In this protocol, at least 6 months must have elapsed from the end of photon therapy to the time of BNCT and the peak brain dose should be <8 Gy(w) and the whole brain average dose <6 Gy(w). As of August 2005, only a small number of patients have been treated, but this has been well tolerated.

Investigators in Sweden have carried out a BPA-based trial using an epithermal neutron beam at the Studsvik Medical AB reactor (141). This study differed significantly from all previous clinical trials in that the total amount of BPA administered was increased to 900 mg·kg^{-1}, infused i.v. over 6 h. This approach was based on the following preclinical data: (*1*) the *in vitro* observation that several hours were required to fully load cells with BPA (181); (*2*) long-term i.v. infusions of BPA in rats increased the absolute tumor boron concentrations in the 9L gliosarcoma model, although the T:Bl ratio remained constant (182,183), and (*3*) most importantly, long-term i.v. infusions of BPA appeared to improve the uptake of boron in infiltrating tumor cells at some distance from the main tumor mass in rats bearing intracerebral 9L gliosarcomas (184). The longer infusion time of BPA was well tolerated (185–187) by the 30 patients who were enrolled in this study. All patients were treated with two fields, and the average weighted whole brain dose was 3.2–6.1 Gy(w), which was lower than the higher end of the doses used in the Brookhaven trial, and the minimum dose to the tumor ranged from 15.4 to 54.3 Gy(w). At 10 months following BNCT 23 of 29 evaluable patients had died with a median time to progression following BNCT of 5.8 months and a median survival time of 14.2 months. These results are comparable but not better than those obtained with external beam radiation therapy. Furthermore, they emphasize the need to improve the delivery of BPA, as well as BSH. As part of a broader plan to restructure the company, a decision was made by Studsvik AB in June 2005 to terminate operation of both the R2-0 reactor, which was used for this clinical trial, and the R2 reactor.

CLINICAL STUDIES OF BNCT FOR OTHER TUMORS

Treatment of Melanoma

Other than patients with primary brain tumors, the second largest group that has been treated by BNCT were those with cutaneous melanomas. Mishima and co-workers previously had carried out extensive studies in experimental animals with either primary or transplantable melanomas using ^{10}B enriched BPA as the capture agent (188,189). The use of BPA was based on the premise that it would be selectively taken up by and accumulate in neoplastic cells that were actively synthesizing melanin (190). Although it was subsequently shown that a variety of malignant cells preferentially took up large amounts of BPA compared to normal cells (191), nevertheless, Mishima's studies clearly stimulated clinical interest in BPA as a boron delivery agent. Since BPA itself has low water solubility, it was formulated with HCl to make it more water soluble. The first patient, who was treated by Mishima in 1985, had an acral lentigenous melanoma of his right toe that had been amputated (192). However, 14 months later he developed a subcutaneous metastatic nodule on the left occiput, which was determined to be inoperable due to its location. The tumor was injected peritumorally at multiple points for a total dose of 200 mg of BPA. Several hours later, by which time BPA had cleared from normal skin, but still had been retained by the melanoma, the tumor was irradiated with a collimated beam of thermal neutrons. Based on the tumor boron concentrations and the neutron fluence, an estimated 45 RBE-Gy equivalent dose was delivered to the melanoma. Marked regression was noted after 2 months, and the tumor had completely disappeared by 9 months (188,189,192). This successful outcome provided further evidence for *proof-of-principle* of the usefulness of BNCT to treat a radioresistant tumor. Subsequently, at least an additional 18 patients with either primary or metastatic melanomas have been treated by Mishima and co-workers (193). The BPA either was injected peritumorally or administered orally as a slurry (194) until Yoshino et al.

improved its formulation and water solubility by complexing it with fructose, following which it was administered i.v. (195). This important advance ultimately led to the use of BPA in the clinical trials in patients with brain tumors that were described in the preceding section. In all of Mishima's patients, there was local control of the treated primary or metastatic melanoma nodule(s) and several patients were tumor free at 4 or more years following BNCT (193).

Several patients with either cutaneous or cerebral metastases of melanoma have been treated by Busse et al. using BPA fructose as the delivery agent (18,196). The most striking example of a favorable response was in a patient with an unresected cerebral metastasis in the occipital lobe. The tumor received a dose of 24 RBE-Gy and monthly MRI studies revealed complete regression over a 4 month interval (196). As evidenced radiographically, a second patient with a brain metastasis had a partial response. Several other patients with either cutaneous or metastatic melanoma to the brain have been treated at other institutions, including the first in Argentina (197), and the consensus appears to be that these tumors are more responsive to BNCT than GBMs. This is supported by experimental studies carried out by two of us (R.F.B. and J.A.C.) using a human melanoma xenograft model (198,199), which demonstrated enhanced survival times and cure rates superior to those obtained using the F98 rat glioma model (200). In summary, multicentric metastatic brain tumors, and more specifically melanoma, which cannot be treated either by surgical excision or stereotactic radiosurgery, may be candidates for treatment by BNCT.

Other Tumor Types Treated by BNCT

Two other types of cancer recently have been treated by BNCT. The first is recurrent tumors of the head and neck. Kato et al. reported on a series of six patients, three of whom had squamous cell carcinomas, two had sarcomas, and 1 had a parotid tumor (201). All of them had received standard therapy and had developed recurrent tumors for which there were no other treatment options. All of the patients received a combination of BSH (5 g) and BPA (250 mg·kg^{-1} body weight), administered i.v. In all but one patient, BNCT was carried out at the Kyoto University Research Reactor using an epithermal neutron beam in one treatment that was given 12h following administration of BSH and 1 h after BPA. The patient with the parotid tumor, who received a second treatment one month following the first, had the best response with a 63% reduction in tumor volume at 1 month and a 94% reduction at 1 year following the second treatment without evidence of recurrence. The remaining five patients showed responses ranging from a 10–27% reduction in tumor volume with an improvement in clinical status. This study has extended the use of BNCT to a group of cancers that frequently are ineffectively treated by surgery, radio-, and chemotherapy. However, further clinical studies are needed to objectively determine the clinical usefulness of BNCT for head and neck cancers, and another study to assess this currently is in progress at Helsinki University Central Hospital.

The second type of tumor that recently has been treated by BNCT is adenocarcinoma of the colon that had metastasized to the liver (202). Although hepatectomy followed by allogeneic liver transplantation, has been carried out at a number of centers (203,204), Pinelli and Zonta et al. (202) in Pavia, Italy, have approached the problem of multicentric hepatic metastases using an innovative, but highly experimental procedure. Their patient had >14 metastatic nodules in the liver parenchyma, the size of which precluded surgical excision. Before hepatectomy was performed, the patient received a 2 h infusion of BPA fructose (300 mg·kg^{-1} b.w.) via the colic vein. Samples of tumor and normal liver were taken for boron determinations and once it was shown that boron selectively had localized in the tumor nodules with small amounts in normal liver, the hepatectomy was completed (202). The liver then was transported to the Reactor Laboratory of the University of Pavia for neutron irradiation, following which it was reimplanted into the patient. More than 2 years later in October 2004, the patient had no clinical or radiographic evidence of recurrence and CEA levels were low (205). Although it is unlikely that this approach will have any significant clinical impact on the treatment of the very large number of patients who develop hepatic metastases from colon cancer, it nevertheless again provides *proof of principle* that BNCT can eradicate multicentric deposits of tumor in a solid organ. The Pavia group has plans to treat other patients with metastatic liver cancer and several other groups (206–208) are exploring the possibility of treating patients with primary, as well as metastatic tumors of the liver using this procedure.

CRITICAL ISSUES

There are a number of critical issues that must be addressed if BNCT is to become a useful modality for the treatment of cancer, and most specifically, brain tumors. *First* and foremost, there is a need for more selective and effective boron agents, which when used either alone or in combination, could deliver the requisite amounts ($\sim$20 μg·g^{-1}) of boron to the tumor. Furthermore, their delivery must be optimized in order to improve both tumor uptake and cellular microdistribution, especially to different subpopulations of tumor cells (185). A number of studies have shown that there is considerable patient-to-patient as well-intratumoral variability in the uptake of both BSH (209,210) and BPA (184,211,212). At this point in time, the dose and delivery of these drugs have yet to be optimized, but based on experimental animal data (31,32,34,137,183), improvement in dosing and delivery could have a significant impact on increasing tumor uptake and microdistribution.

Second, since the radiation dosimetry for BNCT is based on the microdistribution of ^{10}B (209,213), which is indeterminable on a real-time basis, methods are needed to provide semiquantatative estimates of the boron content in the residual tumor. Imahori and co-workers (214–216) in Japan and Kabalka (217) in the United States have carried out imaging studies with ^{18}F-labeled BPA, and have used to establish the feasibility of carrying out BNCT. This

^{18}F-PET imaging also has been used as a prognostic indicator for patients with GBM who may or may not have received BNCT (214,215). In the former group, it has been used to establish the feasibility of carrying out BNCT based on the uptake and distribution of ^{18}F-BPA within the tumor and in the latter to monitor the response to therapy. The possibility of using MRI for either ^{10}B or ^{11}B has been under investigation (218), and this may prove to be useful for real-time localization of boron in residual tumor prior to BNCT. Magnetic resonance spectroscopy (MRS) and magnetic resonance spectroscopic imaging (MRSI) also may be useful for monitoring the response to therapy (219). Kojimoto and Miyatake et al. recently used MRS to analyze the target specificity of BPA and the effects of BNCT in a group of six patients using multivoxel proton MRS (220). There was a reduction in the choline/creatine ratio without a reduction of the *N*-acetlylaspartate/creatine ratio at 14 days following BNCT, strongly suggesting that there was selective destruction of tumor cells and a sparing of normal neurons (220). Noninvasive procedures (e.g., MRSI) may be a powerful way to follow the clinical response to BCNT in addition to MRI. However, in the absence of real-time tumor boron uptake data, the dosimetry for BNCT is very problematic. This is evident from the discordance of estimated doses of radiation delivered to the tumor and the therapeutic response, which would have been greater than that which was seen if the tumor dose estimates were correct (152).

Third, there is a discrepancy between the theory behind BNCT, which is based on a very sophisticated concept of selective cellular and molecular targeting of high LET radiation, and the implementation of clinical protocols, which are based on very simple approaches to drug administration, dosimetry, and patient irradiation. This in part is due to the fact that BNCT has not been carried out in advanced medical settings with a highly multidisciplinary clinical team in attendance. At this time BNCT has been totally dependent on nuclear reactors as neutron sources. These are a medically unfriendly environment and are located at sites at varying distances from tertiary care medical facilities, which has made it difficult to attract patients, and the highly specialized medical team that ideally should be involved in clinical BNCT. Therefore, there is an urgent need for either very compact medical reactors or ABNS that could be easily sited at selected centers that treat large numbers of patients with brain tumors.

Fourth, there is a need for randomized clinical trials. This is especially important since almost all major advances in clinical cancer therapy have come from these, and up until this time no randomized trials of BNCT have been conducted. The pitfalls of nonrandomized clinical trials for the treatment of brain tumors have been well documented (221,222). It may be somewhat wishful thinking to believe that the clinical results with BNCT will be so clearcut that a clear determination of efficacy could be made without such trials. These will require a reasonably large number of patients in order to provide unequivocal evidence of efficacy with survival times significantly better than those obtainable with promising currently available therapy for both GBMs (223,224) and metastatic brain tumors (225). This leads to the issue of conducting such trials, which might best be accomplished through cooperative groups such as the Radiation Therapy Oncology Group (RTOG) in the United State or the European Organization for Research Treatment of Cancer (EORTC).

Finally, there are several promising leads that could be pursued. The upfront combination of BNCT with external beam radiation therapy or in combination with chemotherapy has not been explored, although recently published experimental data, suggest that there may be a significant gain if BNCT is combined with photon irradiation (34). The extension of animal studies, showing enhanced survival of brain tumor bearing rats following the use of BSH and BPA in combination, administered intraarterially with or without BBB-D, has not been evaluated clinically. This approach is promising, but it is unlikely that it could be carried out at a nuclear reactor.

As is evident from this article, BNCT represents an extraordinary joining together of nuclear technology, chemistry, biology, and medicine to treat cancer. Sadly, the lack of progress in developing more effective treatments for high grade gliomas has been part of the driving force that continues to propel research in this field. BNCT may be best suited as an adjunctive treatment, used in combination with other modalities, including surgery, chemotherapy, and external beam radiation therapy, which, when used together, may result in an improvement in patient survival. Clinical studies have demonstrated the safety of BNCT. The challenge facing clinicians and researchers is how to get beyond the current impasse. We have provided a road map to move forward, but its implementation still remains a daunting challenge

ACKNOWLEDGMENTS

We thank Mrs. Michelle Smith for secretarial assistance in the preparation of this manuscript. Text and the two figures, which appear in this article, have been published in *Clinical Cancer Research* with copyright release from the American Association of Cancer Research, Inc.

Experimental studies described in this article have been supported by the National Institutes of Health grants 1R01 CA098945 (to R.F.B.) and 1R01 CA098902 to (M.G.H.V.) and Department of Energy Grants DE-FG02-93ER61612 (to T.E.B.) and DE-FG02-01ER63194 (to J.A.C.) and the Royal G. and Mae H. Westaway Family Memorial Fund at the Massachusetts Institute of Technology (to J.A.C.).

BIBLIOGRAPHY

Cited References

1. Berger MS. Malignant astrocytomas: surgical aspects. Seminars Oncol 1994;21:172–185.
2. Gutin PH, Posner JB. Neuro-Oncology: diagnosis and management of cerebral gliomas—past, present, and future. Neurosurgery 2000;47:1–8.
3. Parney IF, Chang SM. Current chemotherapy for glioblastoma. In: Market J, DeVita VT, Rosenberg SA, Hellman S, editors. Glioblastoma Multiforme, 1st ed., Sudbury (MA): Jones and Bartlett Publishers; 2005. p 161–177.

4. Paul DB, Kruse CA. Immunologic approaches to therapy for brain tumors. Curr Neurol Neurosci Rep 2001;1:238–244.
5. Rainov NG. Gene therapy for human malignant brain tumors. In: Market J, DeVita VT, Rosenberg SA, Hellman S, editors. Glioblastoma Multiforme. 1st ed. Sudbury (MA): Jones and Bartlett Publishers; 2005. p 249–265.
6. Curran WJ, et al. Recursive partitioning analysis of prognostic factors in three radiation oncology group malignant glioma trials. J Nat Cancer Inst 1993;85:704–710.
7. Lacroix M, et al. A multivariate analysis of 416 patients with glioblastoma multiforme: prognosis, extent of resection, and survival. J Neurosurg 2001;95:190–198.
8. Hentschel SJ, Lang FF. Current surgical management of glioblastoma. In: Market J, DeVita VT, Rosenberg SA, Hellman S, editors. Glioblastoma Multiforme, 1st ed., Sudbury (MA): Jones and Bartlett Publishers; 2005. p 108–130.
9. Laws ER, Shaffrey ME. The inherent invasiveness of cerebral gliomas: implications for clinical management. Int J Devel Neurosc 1999;17:413–420.
10. Halperin EC, Burger PC, Bullard DE. The fallacy of the localized supratentorial malignant glioma. Int J Radiat Oncol Biol Phys 1988;15:505–509.
11. Kaczarek E, et al. Dissecting glioma invasion: interrelation of adhesion, migration and intercellular contacts determine the invasive phenotype. Int J Devel Neurosc 1999;17:625–641.
12. Huang S, Prabhu S, Sawaya R. Molecular and biological determinants of invasiveness and angiogenesis in central nervous system tumors. In: Zhang W, Fuller GN, editors. Genomic and Molecular Neuro-Oncology. Sudbury (MA): Jones and Bartlette Publishers; 2004. pp 97–118.
13. Parney IF, Hao C, Petruk K. Glioma immunology and immunotherapy. Neurosurgery 2000;46:778–792.
14. Ware ML, Berger MS, Binder DK. Molecular biology of glioma tumorigenesis. Histol Histopathol 2003;18:207–216.
15. Barth RF. A critical assessment of boron neutron capture therapy: An overview. J Neuro-Oncol 2003;62:1–5.
16. Mishima Y. Selective thermal neutron capture therapy of cancer cells using their specific metabolic activities - melanoma as prototype. In: Mishima Y, editor. Cancer Neutron Capture Therapy. New York: Plenum Press; 1996. p 1–26.
17. Busse PM, et al. A critical examination of the results from the Harvard-MIT NCT program phase I clinical trial of neutron capture therapy for intracranial disease. J Neuro-Oncol 2003;62:111–121.
18. Coderre JA, et al. Boron neutron capture therapy: cellular targeting of high linear energy transfer radiation. Technol Cancer Res Treatment 2003;2:1–21.
19. Sauerwein W, Moss R, Wittig A, editors. Research and development in neutron capture therapy. Bologna, Italy: Monduzzi Editore S.p.A., International Proceedings Division; 2002.
20. Coderre JA, Rivard MJ, Patel H, Zamenhof RG. Proceedings of the 11th World Congress on Neutron Capture Therapy. Appl Rad Isotopes 2004; 61s.
21. Coderre JA, Morris GM. The radiation biology of boron neutron capture therapy. Radiat Res 1999;151:1–18.
22. Morris GM, et al. Response of the central nervous system to boron neutron capture irradiation: Evaluation using rat spinal cord model. Radiother Oncol 1994;32:249–255.
23. Morris GM, et al. Response of rat skin to boron neutron capture therapy with *p*-boronophenylalanine or borocaptate sodium. Radiother Oncol 1994;32:144–153.
24. Gupta N, Gahbauer RA, Blue TE, Albertson B. Common challenges and problems in clinical trials of boron neutron capture therapy of brain tumors. J Neuro-Oncol 2003;62:197–210.
25. Nigg DW. Computational dosimetry and treatment planning considerations for neutron capture therapy. J Neuro-Oncol 2003;62:75–86.
26. Coderre JA, et al. Boron neutron capture therapy for glioblastoma multiforme using p-boronophenylalanine and epithermal neutrons: Trial design and early clinical results. J Neuro-Oncol 1997;33:141–152.
27. Elowitz EH, et al. Biodistribution of p-boronophenylalanine in patients with glioblastoma multiforme for use in boron neutron capture therapy. Neurosurgery 1998;42:463–469.
28. Blue TE, Yanch JC. Accelerator-based epithermal neutron sources for boron neutron capture therapy of brain tumors. J Neuro-Oncol 2003;62:19–31.
29. Fukuda H, et al. Boron neutron capture therapy of malignant melanoma using ^{10}B-paraboronophenylalanine with special reference to evaluation of radiation dose and damage to the skin. Radiat Res 1994;138:435–442.
30. Coderre JA, et al. Derivations of relative biological effectiveness for the high-LET radiations produced during boron neutron capture irradiations of the 9L rat gliosarcoma *in vitro* and *in vivo*. Int J Radiat Oncol Biol Phys 1993;27: 1121–1129.
31. Barth RF, et al. Boron neutron capture therapy of brain tumors: enhanced survival following intracarotid injection of either sodium borocaptate or boronophenylalanine with or without blood-brain barrier disruption. Cancer Res 1997;57: 1129–1136.
32. Barth RF, et al. Boron neutron capture therapy of brain tumors: enhanced survival and cure following blood-brain barrier disruption and intracarotid injection of sodium borocaptate and boronophenylalanine. Int J Radiat Oncol Biol Phys 2000;47:209–218.
33. Miyatake S, et al. Modified boron neutron capture therapy (BNCT) for mailignant gliomas using epithermal neutrons and two boron compounds with different accumulation mechanisms-Effectiveness of BNCT on radiographic images. J Neurosurg Dec. 2005 (In Press).
34. Barth RF, et al. Combination of boron neutron capture therapy and external beam X-irradiation for the treatment of brain tumors. Int J Radiat Oncol Biol Phys 2004;58: 267–277.
35. Farr LE, et al. Neutron capture therapy with boron in the treatment of glioblastoma multiforme. Am J Roenthemol 1954;71:279–291.
36. Godwin JT, Farr LE, Sweet WH, Robertson JS. Pathological study of eight patients with glioblastoma multiforme treated by neutron-capture therapy using boron 10. Cancer 1955;8:601–615.
37. Snyder HR, Reedy AJ, Lennarz WJ. Synthesis of aromatic boronic acids, aldehydo boronic acids and a boronic acid analog of tyrosine. J Am Chem Soc 1958;80:835–838.
38. Soloway AH, Hatanaka H, Davis MA. Penetration of brain and brain tumor. VII. Tumor-binding sulfhydryl boron compounds. J Med Chem 1967;10:714.
39. Hawthorne MF. The role of chemistry in the development of boron neutron capture therapy of cancer. Angew Chem Int Ed Engl 1993;32:950–984.
40. Morin C. The chemistry of boron analogues of biomolecules. Tetrahedron 1994;50:12521–12569.
41. Soloway AH, et al. The chemistry of neutron capture therapy. Chem Rev 1998;98:1515–1562.
42. Hawthorne MF, Lee MW. A critical assessment of boron target compounds for boron neutron capture therapy. J Neuro-Oncol 2003;62:33–45.
43. Olsson P, et al. Uptake of a boronated epidermal growth factor-dextran conjugate in CHO xenografts with and without human EGF-receptor expression. Anticancer Drug Des 1998;13:279–289.
44. Gabel D, Foster S, Fairchild RG. The Monte Carlo simulation of the biological effect of the ^{10}B(n,α)^{7}L reaction in cells and

tissue and its implication for boron neutron capture therapy. Radiat Res 1987;111:14–25.

45. Srivastava RR, Singhaus RR, Kabalka GW. 4-Dihydroxyborylphenyl analogues of 1-aminocyclobutanecarboxylic acids: potential boron neutron capture therapy agents. J Org Chem 1999;64:8495–8450.
46. Das BC, et al. Synthesis of a water soluble carborane containing amino acid as a potential therapeutic agent. Syn Letteve 2001;9:1419–1420.
47. Kabalka GW, Yao M-L. Synthesis of a novel boronated 1-amino-cyclobutanecarboxylic acid as a potential boron neutron capture therapy agent. App Organomet Chem 2003;17: 398–402.
48. Diaz S, Gonzalez A, De Riancho SG, Rodriguez A. Boron complexes of *S*-trityl-L-cysteine and *S*-tritylglutathione. J Organomet Chem 2000;610:25–30.
49. Lindström P, Naeslund C, Sjöberg S. Enantioselective synthesis and absolute configurations of the enantiomers of o-carboranylalanine. Tetrahedron Lett 2000;41:751–754.
50. Masunaga S-I, et al. Potential of α-amino alcohol p-boronophenylalaninol as a boron carrier in boron neutron capture therapy, regarding its enantiomers. J Cancer Res Clin Oncol 2003;129:21–28.
51. Diaz A, Stelzer K, Laramore G, Wiersema R. Pharmacology studies of $Na_2\ {}^{10}B_{10}H_{10}$ (GB-10) in human tumor patients. In: Sauerwein W, Moss R, Wittig A, editors. Research and Development in Neutron Capture Therapy. Bologna : Monduzzi Editore, International Proceedings Division; 2002. p 993–999.
52. Hawthorne MF, Feakes DA, Shelly K. Recent results with liposomes as boron delivery vehicles from boron neutron capture therapy. In: Mishima Y, editor Cancer Neutron Capture Therapy. New York: Plenum Press; 1996. p 27–36.
53. Feakes DA, Waller RC, Hathaway DK, Morton VS. Synthesis and in vivo murine evaluation of $Na_4[1\text{-}(1'\text{-}B_{10}H_9)\text{-}6\text{-}SHB_{10}H_8]$ as a potential agent for boron neutron capture therapy. Proc Natl Acad Sci USA 1999;96:6406–6410.
54. Shukla S, et al. Evaluation of folate receptor targeted boronated starburst dendrimer as a potential targeting agent for boron neutron capture therapy. Bioconjugate Chem 2003;14:158–167.
55. Sudimack J, et al. Intracellular delivery of lipophilic boron compound using folate receptor-targeted liposomes. Pharm Res 2002;19:1502–1508.
56. Takagaki M, et al. Boronated dipeptide borotrimethylglycylphenylalanine as a potential boron carrier in boron neutron capture therapy for malignant brain tumors. Radiat Res 2001;156:118–122.
57. Wakamiya T, et al. Synthesis of 4-boronophenylalanine-containing peptides for boron neutron capture therapy of cancer cells. Peptide Sci 1999;36:209–212.
58. Lesnikowski ZJ, Schinazi RF. Boron containing oligonucleotides. Nucleosides Nucleotides 1998;17:635–647.
59. Soloway AH, et al. Identification, development, synthesis and evaluation of boron-containing nucleosides for neutron capture therapy. J Organomet Chem 1999;581:150–155.
60. Lesnikowski ZJ, Shi J, Schinazi RF. Nucleic acids and nucleosides containing carboranes. J Organo-met Chem 1999;581: 156–169.
61. Lunato AJ, et al. Synthesis of 5-(carboranylalkylmercapto)-2′-deoxyuridines and 3-(carboranylalkyl)thymidines and their evaluation as substrates for human thymidine kinases 1 and 2. J Med Chem 1999;42:3378–3389.
62. Al-Madhoun AS, et al. Synthesis of a small library of 3-(carboranylalkyl)thymidines and their biological evaluation as substrates for human thymidine kinases 1 and 2. J Med Chem 2002;45:4018–4028.
63. Schinazi RF, et al. Treatment of Isografted 9L rat brain tumors with *b*-5-o-carboranyl-2'-deoxyuridine neutron capture therapy. Clin Cancer Res 2000;6:725–730.
64. Al-Madhoun AS, et al. Evaluation of human thymidine kinase 1 substrates as new candidates for boron neutron capture therapy. Cancer Res 2004;64:6280–6286.
65. Barth RF, et al. Boron containing nucleosides as potential delivery agents for neutron capture therapy of brain tumors. Cancer Res 2004;64:6287–6295.
66. Sjöberg S, et al. Chemistry and biology of some low molecular weight boron compounds for boron neutron capture therapy. J Neuro-Oncol 1997;33:41–52.
67. Tietze LF, et al. Novel carboranes with a DNA binding unit for the treatment of cancer by boron neutron capture therapy. ChemBio-Chem 2002;3:219–225.
68. Bateman SA, Kelly DP, Martin RF, White JM. DNA binding compounds. VII. Synthesis, characterization and DNA binding capacity of 1,2-dicarba-*closo*-dodecaborane bibenzimidazoles related to the DNA minor groove binder Hoechst 33258. Aust J Chem 1999;52:291–301.
69. Woodhouse SL, Rendina LM. Synthesis and DNA-binding properties of dinuclear platinum(II)-amine complexes of 1,7-dicarba-*closo*-dodecaborane(12). Chem Commun 2001; 2464–2465.
70. Cai J, et al. Boron-containing polyamines as DNA-targeting agents for neutron capture therapy of brain tumors: synthesis and biological evaluation. J Med Chem 1997;40:3887–3896.
71. Zhuo J-C, et al. Synthesis and biological evaluation of boron-containing polyamines as potential agents for neutron capture therapy of brain tumors. J Med Chem 1999;42: 1281–1292.
72. Martin B, et al. *N*-Benzylpolyamines as vectors of boron and fluorine for cancer therapy and imaging: synthesis and biological evaluation. J Med Chem 2001;44:3653–3664.
73. El-Zaria ME, Doerfler U, Gabel D. Synthesis of [(amino-alkylamine)-*N*-amino-alkyl] azanonaborane(11) derivatives for boron neutron capture therapy. J Med Chem 2002;45: 5817–5819.
74. Nakanishi A, et al. Toward a cancer therapy with boron-rich oligomeric phosphate diesters that target the cell nucleus. Proc Natl Acad Sci USA 1999;96:238–241.
75. Maderna A, et al. Synthesis of a porphyrin-labelled carboranyl phosphate diester: a potential new drug for boron neutron capture therapy of Cancer. Chem Commun 2002; 1784–1785.
76. Vicente MGH. Porphyrin-based sensitizers in the detection and treatment of cancer: recent progress. Curr Med Chem Anti-Cancer Agents 2001;1:175–194.
77. Bregadze VI, Sivaev IB, Gabel D, Wöhrle D. Polyhedral boron derivatives of porphyrins and phthalocyanines. J Porphyrins Phthalocyanines 2001;5:767–781.
78. Evstigneeva RP, et al. Carboranylporphyrins for boron neutron capture therapy of cancer. Curr Med Chem: Anti-Cancer Agents 2003;3:383–392.
79. Vicente MGH, et al. Syntheses, toxicity and biodistribution of two 5,15-di[3,5-(*nido*-carboranyl-methyl)phenyl] porphyrin in EMT-6 tumor bearing mice. Bioorg Med Chem 2003;11: 3101–3108.
80. Miura M, et al. Evaluation of carborane-containing prophyrins as tumour agents for boron neutron capture therapy. Br J Radiol 1998;71:773–781.
81. Miura M, et al. Biodistribution of copper carboranyltetraphenylporphyrins in rodents bearing an isogeneic or human neoplasm. J Neuro-Oncol 2001;52:111–117.
82. Miura M, et al. Boron neutron capture therapy of a murine mammary carcinoma using a lipophilic carboranyltetraphenylporphyrin. Radiat Res 2001;155:603–610.

83. Gottumukkala V, Luguya R, Fronczek FR, Vicente MGH. Synthesis and cellular studies of an octa-anionic 5,10,15,20-tetra[3,5-(*nido*-carboranylmethyl)phenyl] porphyrin (H_2OCP) for application in BNCT. Bioorg Med Chem 2005;13: 1633–1640.
84. Hao E, Vicente MGH. Expeditious synthesis of porphyrin-cobaltacarborane vonjugates. Chem Commun 2005; 1306–1308.
85. Ongayi O, Gottumukkala V, Fronczek FR, Vicente MGH. Synthesis and characterization of a carboranyl-tetrabenzoporphyrin. Bioorg Med Chem Lett 2005;15:1665–1668.
86. Fabris C, Jori G, Giuntini F, Roncucci G. Photosensitizing properties of a boronated phthalocyanine: studies at the molecular and cellular level. J Photochem Photobiol B: Biol 2001;64:1–7.
87. Giuntini F, et al. Synthesis of tetrasubstitited Zn(II)-phthalocyanines carrying four carboranyl-units as potential BNCT and PDT agents. Tetrahedron Lett 2005;46:2979–2982.
88. Luguya R, Fronckzek FR, Smith KM, Vicente MGH. Synthesis of novel carboranylchlorins with dual application in boron neutron capture therapy (BNCT) and photodynamic therapy (PDT). Appl Rad Isotopes 2004;61:1117–1123.
89. Rosenthal MA, Kavar B, Uren S, Kaye AH. Promising survival in patients with high-grade gliomas following therapy with a novel boronated porphyrin. J Clin Neurosc 2003; 10:425–427.
90. Rosenthal MA, et al. Phase I and pharmacokinetic study of photodynamic therapy for high-grade gliomas using a novel boronated porphyrin. J Clin Oncol 2001;19:519–524.
91. Hill JS, et al. Selective tumor kill of cerebral glioma by photodynamic therapy using a boronated phorhyrin photosensitizer. Proc Natl Acad Sci USA 1995;92:12126–12130.
92. Kawabata S, et al. Evaluation of the carboranyl porphyrin H_2TCP as a delivery agent for boron neutron capture therapy (BNCT). Khamlichi A, editor. 13th World Congress of Neurological Surgery, Marakesh, Morocco. June 19–24, 2005. p 975–979.
93. Ozawa T, et al. *In vivo* evaluation of the boronated porphyrins TABP-1 in U-87 MG intracerebral human glioblastoma xenografts. Mol Pharmaceut 2004;5:368–374.
94. Lauceri R, Purrello R, Shetty SJ, Vicente MGH. Interactions of anionic carboranylated porphyrins with DNA. J Am Chem Soc 2001;123:5835–5836.
95. Vicente MGH, et al. Synthesis, dark toxicity and induction of in vitro DNA photodamage by a tetra(4-nido-carboranylphenyl)porphyrin. J Photochem Photobiol B: Biol 2002;68:123–132.
96. Ghaneolhosseini H, Tjarks W, Sjoberg S. Synthesis of novel boronated acridines and spermidines as possible agents for BNCT. Tetrahedron 1998;54:3877–3884.
97. Gedda L, et al. Cytotoxicity and subcellular localization of boronated phenanthridinium analogs. Anti-Cancer Drug Design 1997;12:671–685.
98. Gedda L, et al. The influence of lipophilicity on binding of boronated DNA-intercalating compounds in human glioma spheroids. Anti-Cancer Drug Design 2000;15:277–286.
99. Giovenzana GB, et al. Synthesis of carboranyl derivatives of alkynyl glycosides as potential BNCT agents. Tetrahedron 1999;55:14123–14136.
100. Tietze LF, et al. Ortho-carboranyl glycosides for the treatment of cancer by boron neutron capture therapy. Bioorg Med Chem 2001;9:1747–1752.
101. Orlova AV, et al. Conjugates of polyhedral boron compounds with carbohydrates. 1. New approach to the design of selective agents for boron neutron capture therapy of cancer. Russ Chem Bull 2003;52:2766–2768.
102. Tietze LF, Bothe U. Ortho-carboranyl glycosides of glucose, mannose, maltose and lactose for cancer treatment by boron neutron-capture therapy. Chem Eur J 1998;4:1179–1183.
103. Raddatz S, et al. Synthesis of new boron-rich building blocks for boron neutron capture therapy or energy-filtering transmission electron microscopy. ChemBioChem 2004;5:474–482.
104. Tietze LF, et al. Novel carboranyl C-glycosides for the treatment of cancer by boron neutron capture therapy. Chem Eur J 2003;9:1296–1302.
105. Basak P, Lowary TL. Synthesis of conjugates of L-fucose and *ortho*-carborane as potential agents for boron neutron capture therapy. Can J Chem 2002;80:943–948.
106. Endo Y, et al. Structure–activity study of estrogenic agonists bearing dicarba-*closo*-dodecaborane. Effect of geometry and separation distance of hydroxyl groups at the ends of molecules. Bioorg Med Chem Lett 1999;9:3313–3318.
107. Lee J-D, et al. A convenient synthesis of the novel carboranyl-substituted tetrahydroisoquinolines: application to the biologically active agent for BNCT. Tetrahedron Lett 2002;43:5483–5486.
108. Valliant JF, Schaffer P, Stephenson KA, Britten JF. Synthesis of Boroxifen, a *nido*-carborane analogue of tamoxifen. J Org Chem 2002;67:383–387.
109. Feakes DA, Spinler JK, Harris FR. Synthesis of boron-containing cholesterol derivatives for incorporation into unilamellar liposomes and evaluation as potential agents for BNCT. Tetrahedron 1999;55:11177–11186.
110. Endo Y, et al. Potent estrogen agonists based on carborane as a hydrophobic skeletal structure: a new medicinal application of boron clusters. Chem Biol 2001;8:341–355.
111. Tjarks W, et al. *In vivo* evaluation of phosphorous-containing derivatives of dodecahydro-*closo*-dodecaborate for boron neutron capture therapy of gliomas and sarcomas. Anticancer Res 2001;21:841–846.
112. Adams DM, Ji W, Barth RF, Tjarks W. Comparative *in vitro* evaluation of dequalinium B, a new boron carrier for neutron capture therapy (NCT). Anticancer Res 2000;20: 3395–3402.
113. Zakharkin LI, et al. Synthesis of bis(dialkylaminomethyl)-*o*- and *m*-carboranes and study of these compounds as potential preparations for boron neutron capture therapy. Pharm Chem J 2000;34:301–304.
114. Barth RF, et al. Boronated starburst dendrimer-monoclonal antibody immunoconjugates: evaluation as a potential delivery system for neutron capture therapy. Bioconjug Chem 1994;5:58–66.
115. Liu L, et al. Critical evaluation of bispecific antibodies as targeting agents for boron neutron capture therapy of brain tumors. Anticancer Res 1996;16:2581–2588.
116. Liu L, et al. Bispecific antibodies as targeting agents for boron neutron capture therapy of brain tumors. J Hematother 1995;4:477–483.
117. Novick S, et al. Linkage of boronated polylysine to glycoside moieties of polyclonal antibody; Boronated antibodies as potential delivery agents for neutron capture therapy. Nuclear Med Biol 2002;29:93–101.
118. Wu G, et al. Site-specific conjugation of boron containing dendrimers to anti-EGF receptor monoclonal antibody cetuximab (IMC-C225) and its evaluation as a potential delivery agent for neutron capture therapy. Bioconjugate Chem 2004;15:185–194.
119. Fallot T, et al. A Phase I study of an anti-epidermal growth factor receptor monoclonal antibody for the treatment of malignant gliomas. Neurosurgery 1996;39:478–483.

120. Carlsson J, et al. Strategy for boron neutron capture therapy against tumor cells with over-expression of the epidermal growth factor receptor. Int J Radiat Oncol Biol Phys 1994;30:105–115.
121. Capala J, et al. Boronated epidermal growth factor as a potential targeting agent for boron neutron capture therapy of brain tumors. Bioconjugate Chem 1996;7:7–15.
122. Sauter G, et al. Patterns of epidermal growth factor receptor amplification in malignant gliomas. Am J Pathol 1996;148: 1047–1053.
123. Schwechheimer K, Huang S, Cavenee WK. EGFR gene amplification-rearrangement in human glioblastoma. Int J Cancer 1995;62:145–148.
124. Backer MV, Backer JM. Targeting endothelial cells overexpressing VEGFR-2: selective toxicity of Shiga-like toxin-VEGF fusion proteins. Bioconjugate Chem 2001;12: 1066–1073.
125. Backer MV, et al. Vascular endothelial growth factor selectively targets boronated dendrimers to tumor vasculature. Mol Cancer Therapeut 2005;4:1423–1429.
126. Feakes DA, Shelly K, Hawthorne M. Selective boron delivery to murine tumors by lipophilic species incorporated in the membranes of unilamellar liposomes. Proc Natl Acad Sci USA 1995;92:1367–1370.
127. Carlsson J, et al. Ligand liposomes and boron neutron capture therapy. J Neuro-Oncol 2003;62:47–59.
128. Pardridge WM. Drug delivery to the brain. J Cerebral Blood Flow Metabol 1997;17:713–731.
129. Mendelsohn, J. Targeting the epidermal growth factor receptor for cancer therapy. J Clin Oncol 2002;20:1s–13s.
130. Nygren P, Sorbye H, Osterland P, Pfeiffer P. Targeted drugs in metastatic colorectal cancer with emphasis on guidelines for the use of bevacizumab and cetuximab. An Acta Oncologica expert report. Acta Oncolog 2005;44:203–218.
131. Wikstrand CJ, Cokgor I, Sampson JH, Bigner DD. Monoclonal antibody therapy of human gliomas: current status and future approaches. Cancer Metastasis Rev 1999;18: 451–464.
132. Barth RF, et al. Molecular targeting of the epidermal growth factor receptor for neutron capture therapy of gliomas. Cancer Res 2002;62:3159–3166.
133. Yang W, et al. Convection enhanced delivery of boronated epidermal growth factor for molecular targeting of EGFR positive gliomas. Cancer Res 2002;62:6552–6558.
134. Barth RF, et al. Neutron capture therapy of epidermal growth factor positive gliomas using boronated cetuximab (IMC-C225) as a delivery agent. App Radiat Isotopes 2004;61: 899–903.
135. Yang W, et al. Boronated epidermal growth factor as a delivery agent for neutron capture therapy of EGFR positive gliomas. App Rad Isotopes 2004;61:981–985.
136. Barth RF, et al. Enhanced delivery of boronophenylalanine for neutron capture therapy of brain tumors using the bradykinin analogue, Cereport™(RMP7). Neurosurgery 1999; 44:350–359.
137. Barth RF, et al. Neutron capture therapy of intracerebral melanoma: Enhanced survival and cure following blood–brain barrier opening to improve delivery of boronophenylalanine. Int J Radiat Oncol Biol Phys 2002;52:858–868.
138. Yang W, et al. Development of a syngeneic rat brain tumor model expressing EGFRvIII and its use for molecular targeting studies with monoclonal antibody L8A4. Clin Cancer Res 2005;11:341–350.
139. Harling O, Riley K. Fission reactor neutron sources for neutron capture therapy—a critical review. J Neuro-Oncol 2003;2:7–17.
140. Harling O, et al. The fission converter-based epithermal neutron irradiation facility at the Massachusetts Institute of Technology Reactor. Nuclear Sci Eng 2002;140:223–240.
141. Capala J, et al. Boron neutron capture therapy for glioblastoma multiforme: clinical studies in Sweden. J Neuro-Oncol 2003;62:135–144.
142. Joensuu H, et al. Boron neutron capture therapy of brain tumors: clinical trials at the Finnish Facility using boronophenylalanine. J Neuro-Oncol 2003;62:123–134.
143. Moss RL, et al. Design, construction and installation of an epithermal neutron beam for BNCT at the High Flux Reactor Petten. In: Allen BJ, et al., editors. Progress in Neutron Capture Therapy for Cancer, New York: Plenum Press; 1992. p 63–66.
144. Marek M, Viererbl M, Burian J, Jansky B. Determination of the geometric and spectral characteristics of BNCT beam (neutron and gamma-ray). In: Hawthorne MF, Shelly K, Wiersema RJ, editors., Neutron Capture Therapy, Vol. I, New York: Kluwer Academic/Plenum Publishers; 2001. p 381–389.
145. Kobayashi T, et al. The remodeling and basic characteristics of the heavy water neutron irradiation facility of the Kyoto University Research Reactor, Mainly for Neutron Capture Therapy. Nucl Technol 2000;131:354–378.
146. Yamamoto K, et al. Characteristics of neutron beams for BNCT. Proceedings of the 9th Symposium on Neutron Capture Therapy, Osaka, Japan, October 2–6, 2000. p 243–244.
147. Blaumann HR, Larrieu OC, Longhino JM, Albornoz AF. NCT facility development and beam characterisation at the RA-6 Reactor. In: Hawthorne MF, Shelly K, Wiersema RJ, editors. Frontiers in Neutron Capture Therapy. Vol. I, New York: Kluwer Academic/Plenum Publishers; 2001. p 313–317.
148. Agosteo S, et al. Design of neutron beams for boron neutron capture therapy in a fast reactor. IAEA Technical Committee Meeting about the Current Issues Relating to Neutron Capture Therapy, June 14–18, 1999, Vienna, Austria.
149. Fairchild RG, et al. Installation and testing of an optimized epithermal neutron beam at the Brookhaven Medical Research Reactor (BMRR). Proceedings of the Workshop on Neutron Beam Design, Development and Performance for Neutron Capture Therapy. MIT, Cambridge (MA), March 29–31, 1989.
150. Hatanaka H. Boron neutron capture therapy for brain tumors. In: Karin ABMF, Laws E, editor. Glioma: Berlin: Springer-Verlag; 1991. p 233–249.
151. Hatanaka H, Nakagawa Y. Clinical results of long-surviving brain tumor patients who underwent boron neutron capture therapy. Int J Radiat Oncol Biol Phys 1994;28:1061–1066.
152. Diaz AZ. Assessment of the results from the phase I/II boron neutron capture therapy trials at the Brookhaven National Laboratory from a clinician's point of view. J Neuro-Oncol 2003;62:101–109.
153. Riley K, Binns P, Harling O. Performance characteristics of the MIT fission converter based epithermal neutron beam. Phys Med Biol 2003;48:943–958.
154. Nigg D, et al. Initial neutronic performance assessment of an epithermal neutron beam for neutron capture therapy research at Washington State University. Research and Development in Neutron Capture Therapy. Proceedings of the 10th International Congress on Neutron Capture Therapy, 2002. p 135–139.
155. Beynon T, et al. Status of the Birmingham accelerator-based BNCT facility. Proceedings of the 10th International Congress on Neutron Capture Therapy, 2002. p 225–228.

156. Burlon A, et al. Optimization of a neutron production target and beam shaping assembly based on the ^{7}Li(p,n)^{7}Be reaction. Proceedings of the 10th International Congress on Neutron Capture Therapy, 2002. p 229–234.
157. Kononov O, et al. Investigations of using near-threshold ^{7}Li(p,n)^{7}Be reaction for NCT based on in-phantom dose distribution. Proceedings of the 10th International Congress on Neutron Capture Therapy, 2002. p 241–246.
158. Blackburn B, Yanch J, Klinkowstein R. Development of a high-power water cooled beryllium target for use in accelerator-based boron neutron capture therapy. Med Phys 1998;10:1967–1974.
159. Hawk A, Blue T, Woollard J, Gupta N. Effects of target thickness on neutron field quality for an ABNS. Research and Development in Neutron Capture Therapy Proceedings of the 10th International Congress on Neutron Capture Therapy, 2002. p 253–257.
160. Sakurai Y, Kobayashi T, Ono K. Study on accelerator-based neutron irradiation field aiming for wider application in BNCT - spectrum shift and regional filtering. Proceedings of the 10th International Congress on Neutron Capture Therapy, 2002. p 259–263.
161. Giusti V, Esposito J. Neutronic feasibility study of an accelerator-based thermal neutron irradiation cavity. Proceedings of the 10th International Congress on Neutron Capture Therapy, 2002. p 305–308.
162. Starling WJ. RFI Linac for accelerator-based neutrons. Abstracts of the 11th World Congress on Neutron Capture Therapy. Boston, October 11–15, 2004. p 45.
163. Locher GL. Biological effects and therapeutic possibilities of neutrons. Am J Roetgenol Radium Ther 1936;36:1–13.
164. Asbury AK, Ojeann, Nielson SL, Sweet WH. Neuropathologic study of fourteen cases of malignant brain tumor treated by boron-10 slow neutron capture therapy. J Neuropathol Exp Neurol 1972;31:278–303.
165. Sweet WH. Practical problems in the past in the use of boron-slow neutron capture therapy in the treatment of glioblastoma multiforme. Proceedings First International Symposium Neutron Capture Therapy, Brookhaven National Lab Reports 51730. October 12–14, 1983. p 376–378.
166. Slatkin DN. A history of boron neutron capture therapy of brain tumours. Postulation of a brain radiation dose tolerance limit. Brain 1991;114:1609–1629.
167. Nakagawa Y, Hatanaka H. Boron neutron capture therapy: Clinical brain tumor studies. J Neuro-Oncol 1997;33:105–115.
168. Nakagawa Y, et al. Clinical review of the Japanese experience with boron neutron capture therapy and a proposed strategy using epithermal neutron beams. J Neuro-Oncol 2003;62:87–99.
169. Laramore GE, et al. Boron neutron capture therapy: a mechanism for achieving a concomitant tumor boost in fast neutron radiotherapy. Int J Radiat Oncol Biol Phys 1994;28:1135–1142.
170. Kageji T, et al. Pharmacokinetics and boron uptake of BSH ($Na_2B_{12}H_{11}SH$) in patients with intracranial tumors. J Neuro-Oncol 1997;33:117–130.
171. Bergland R, et al. A Phase 1 trial of intravenous boronophenylalanine-fructose complex in patients with glioblastoma multiforme. Cancer Neutron Capture Therapy. Mishima Y, editor. New York: Plenum Press; 1996. p 739–746.
172. Coderre JA, et al. Biodistribution of boronophenylalanine in patients with glioblastoma multiforme: Boron concentration correlates with tumor cellularity. Radiat Res 1998; 149:163–170.
173. Chanana AD, et al. Boron neutron capture therapy for glioblastoma multiforme: interim results from the phase I/II dose-escalation studies. Neurosurgery 1999;44:1182–1193.
174. Busse PM, et al. A critical examination of the results from the Harvard-MIT NCT program phase I clinical trial of neutron capture therapy for intracranial disease. J Neuro-Oncol 2003;111–121.
175. Palmer MR, et al. Treatment planning and dosimetry for the Harvard-MIT phase I clinical trial of cranial neutron capture therapy. Int J Radiat Oncol Biol Phys 2002;53:1361–1379.
176. Wittig A, et al. Current clinical results of the EORTC-study 11961, in: Research and Development in Neutron Capture Therapy. Sauerwein W, Moss R, Wittig A, editors. Bologna: Monduzzi Editore; 2002. p 1117–1122.
177. Burian J, et al. Report on the first patient group of the Phase I BNCT trial at the LVR-15 reactor. Sauerwein W, Moss R, Wittig A, editors. Bologna, Italy: Monduzzi Editore; 2002. p 1107–1112.
178. Coderre JA, et al. Tolerance of normal human brain to boron neutron capture therapy. Appl Radiat Isotopes 2004;61: 1084–1087.
179. Emami B, et al. Tolerance of normal tissue to therapeutic irradiation. Int J Radiat Oncol Biol Phys 1991;21:109–122.
180. Flickinger JC, et al. Development of a model to predict permanent symptomatic postradiosurgery injury for arteriovenous malformation. Arteriovenous Malformation Radiosurgery Study Group. Int J Radiat Oncol Biol Phys 2000;46:1143–1148.
181. Wittig A, Sauerwein WA, Coderre JA. Mechanisms of transport of *p*-borono-phenylalanine through the cell membrane in vitro. Radiat Res 2000;153:173–180.
182. Joel DD, et al. Effect of dose and infusion time on the delivery of *p*-boronophenylalanine for neutron capture therapy. J Neuro-Oncol 1999;41:213–221.
183. Morris GM, et al. Long-term infusions of p-boronophenylalanine for boron neutron capture therapy: evaluation using rat brain tumor and spinal cord models. Radiat Res 2002;158:743–752.
184. Smith DR, Chandra S, Coderre JA, Morrison GH. Ion microscopy imaging of ^{10}B from p-boronophenylalanine in a brain tumor model for boron neutron capture therapy. Cancer Res 1996;56:4302–4306.
185. Dahlström M, et al. Accumulation of boron in human malignant glioma cells *in vitro* is cell type dependent. J Neuro-Oncology 2004;68:199–205.
186. Bergenheim AT, Capala J, Roslin M, Henriksson R. Distribution of BPA and metabolic assessment in glioblastoma patients during BNCT treatment: a microdialysis study. J Neuro-Oncol 2005;71:287–293.
187. Henriksson R, et al. Boron neutron capture therapy (BNCT) for glioblastoma multiforme: A phase 2 study evaluating a prolonged high dose of boronophenylalanine (BPA) at the Studsvik facility in Sweden. Radiother Oncol (Submitted).
188. Mishima Y, et al. New thermal neutron capture therapy for malignant melanoma. Melanogenesis-seeking ^{10}B molecular-melanoma cell interaction from in vitro to first clinical trial. Pigment Cell Res 1989;2:226–234.
189. Hiratsuka J, Kono, Mishima Y. RBEs of thermal neutron capture therapy and ^{10}B(n,α)^{7}Li reaction on melanoma-bearing hamsters. Pigment Cell Res 1989;2:352–355.

190. Tsuji M, Ichihashi M, Mishima Y. Selective affinity of ^{10}B-paraboronophenylalanine-HCI to malignant melanoma for thermal neutron capture therapy. Jpn J Dermatol 1983;93: 773–778.
191. Coderre JA, et al. Selective delivery of boron by the melanin precursor analog p-boronophenylalanine to tumors other than melanoma. Cancer Res 1990;50:138–141.
192. Mishima Y, et al. Treatment of malignant melanoma by single neutron capture therapy with melanoma-seeking ^{10}B-compound. Lancet 1989;1:388–389.
193. Mishima Y. Melanoma and nonmelanoma neutron capture therapy using gene therapy: overview. In: Larsson B, Crawford J and Weinreich, editors. Advances in Neutron Capture Therapy Vol. 1, Medicine and Physics. Elsevier; 1997. p 10–25.
194. Madoc-Jones H, et al. A phase-I dose-escalation trial of boron neutron capture therapy for subjects with metastatic subcutaneous melanoma of the extremities. In: Mishima Y, editor. Cancer Neutron Capture Therapy. New York and London: Plenum Press; 1996. p 707–716.
195. Yoshino K, et al. Improvement of solubility of p-boronophenylalanine by complex formation with monosaccharides. Strahlenther Onkol 1989;165:127–129.
196. Busse PM, et al. The Harvard-MIT BNCT Program: overview of the clinical trials and translational research. Proceedings of the 11th International Congress of Radiation Research, Vol 2. Dublin, Ireland, July 18–23, 1999. p 702–709.
197. Gonzalez SJ, et al. First BNCT treatment of a skin melanoma in Argentina: dosimetric analysis and clinical outcome. Appl Radiat Isotopes 2004;61:1101–1105.
198. Barth RF, et al. A nude rat model for neutron capture therapy of human intracerebral melanoma. Int J Radiat Oncol Biol Phys 1994;28:1079–1088.
199. Barth RF, et al. Neutron capture therapy of intracerebral melanoma: Enhanced survival and cure following blood-brain barrier opening to improve delivery of boronophenylalanine. Int J Radiat Oncol Biol Phys 2002;52:858–868.
200. Barth RF, et al. Boron neutron capture therapy of brain tumors: enhanced survival and cure following blood-brain barrier disruption and intracarotid injection of sodium borocaptate and boronophenylalanine. Int J Radiat Oncol Biol Phys 2000;47:209–218.
201. Kato I, et al. Effectiveness of BNCT for recurrent head and neck malignancies. Appl Radiat Isotopes 2004;61:1069–1073.
202. Pinelli T, et al. TAOrMINA: from the first idea to the application to the human liver. In: Research and Development in Neutron Capture Therapy. In: Sauerwein W, Moss R, Wittig A, editors. Bologna, Italy: Monduzzi Editore; 2002. p 1065–1072.
203. Ringe B, Pichlmayr R, Wittekind C, Tusch G. Surgical treatment of hepatocellular carcinoma: experience with liver resection and transplantation in 198 patients. World J Surg 1991;15:27085.
204. Iwatsuki S, et al. Hepatic resection versus transplantation for hepatocellular carcinoma. Ann Surg 1991;214:221–228.
205. Pinelli T. Neutron capture therapy for liver cancer metastases. Abstracts of the Eleventh World Congress on Neutron Capture therapy. Boston, October 11–15, 2004. p 52.
206. Suzuki M, et al. Biodistribution of ^{10}B in a rat liver tumor model following intra-arterial administration of sodium borocaptate (BSH)/degradable starch microspheres (DSM) emulsion. Appl Radiat Isotopes 2004;61:933–937.
207. Koivunoro H, et al. BNCT dose distribution in liver with epithermal D-D and D-T fusion-based neutron beams. Appl Radiat Isotopes 2004;61:853–859.
208. Chou FI, et al. Biological efficacy of BPA in malignant and normal liver cells. Abstract of the Eleventh World Cong on Neutron Capture Therapy. Boston, October 11–15, 2004. p 38.
209. Goodman JH, et al. Boron neutron capture therapy of brain tumors: biodistribution, pharmacokinetics, and radiation dosimetry of sodium borocaptate in glioma patients. Neurosurgery 2000;47:608–622.
210. Hideghéty K, et al. Tissue uptake of BSH in patients with glioblastoma in the EORTC 11961 phase I BNCT trial. J Neuro-Oncol 2003;62:145–156.
211. Coderre JA, et al. Biodistribution of boronophenylalanine in patients with glioblastoma multiforme: boron concentration correlates with tumor cellularity. Radiat Res 1998;149: 163–170.
212. Smith D, et al. Quantitative imaging and microlocalization of boron-10 in brain tumors and infiltrating tumor cells by SIMS ion microscopy: Relevance to neutron capture therapy. Cancer Res 2001;61:8179–8187.
213. Santa Cruz GA, Zamenhof RG. The microdosimetry of the ^{10}B reaction in boron neutron capture therapy: a new generalized theory. Radiat Res 2004;162:702–710.
214. Imahori Y, et al. Positron emission tomography-based boron neutron capture therapy using boronophenylalanine for high-grade gliomas: part 1. Clin Cancer Res 1998;4: 1825–1832.
215. Imahori Y, et al. Positron emission tomography-based boron neutron capture therapy using boronophenylalanine for high-grade gliomas: part 2. Clin Cancer Res 1998;4:1833–1841.
216. Takahasi Y, Imahori Y, Mineura K. Prognostic and therapeutic indicator of fluoroboronophenylalanine positron emission tomography in patients with gliomas. Clin Cancer Res 2003;9:5888–5895.
217. Kabalka GW, et al. The use of positron emission tomography to develop boron neutron capture therapy treatment plans for metastatic malignant melanoma. J Neuro-Oncol 2003;62: 187–195.
218. Bendel P. Biomedical applications of ^{10}B and ^{11}B NMR. NMR Biomed 2005;18:74–82.
219. Bendel P, Margalit R, Salomon Y. Optimized ^{1}H MRS and MRSI methods for the *in vivo* detection of boronophenylalanine. Magn Reson Med 2005;53:1166–1171.
220. Kajimoto Y, et al. Boron neutron capture therapy selectively destroys tumor cells preserving neurons in co-existing tumor lesion of malignant glioma. (Submitted)
221. Perry JR, et al. Challenges in the design and conduct of phase III brain tumor therapy trials. Neurology 1997; 49:912–917.
222. Shapiro W. Bias in uncontrolled brain tumor trials. Can J Neurol Sci 1997;24:269–270.
223. Stupp R, et al. Promising survival for patients with newly diagnosed glioblastoma multiforme treated with concomitant radiation plus temozolomide followed by adjuvant temozolomide. J Clin Oncol 2002;20:1375–1382.
224. Stupp R, et al. Radiotherapy plus concomitant and adjuvant temozolomide for gliomblastomas. N Engl J Med 2005;325: 987–996.
225. Agarwala SS, et al. Temozolomide for the treatment of brain metastases associated with metastatic melanoma: a phase II study. J Clin Oncol 2004;22:2101–2107.

See also IMMUNOTHERAPY; MONOCLONAL ANTIBODIES; RADIONUCLIDE PRODUCTION AND RADIOACTIVE DECAY; RADIOTHERAPY, HEAVY ION.

BRACHYTHERAPY, HIGH DOSAGE RATE

RUPAK DAS
University of Wisconsin
Madison, Wisconsin

INTRODUCTION

Brachytherapy is a form of radiotherapy whereby a radioactive source is used inside or at short distance from the tumor. There are three different forms of brachytherapy: interstitial, intracavitary, and skin therapy. In interstitial brachytherapy, the radioactive sources are implanted inside and throughout the tumor volume; in intracavitary brachytherapy the sources are placed in the body cavities very close to the tumor; while in skin therapy the sources are placed on the skin surface. Conventionally, brachytherapy implants have delivered the radiation at a low dose rate (dose rates of $< 1\ \mathrm{Gy \cdot h^{-1}}$). Low dose-rate (LDR) interstitial implants can be temporary (meaning that the radioactive sources are left in place for a period of time, usually a few days, and then removed) or permanent (left in place without removal), while intracavitary implants are temporary. The advent of methods to deliver the dose at a much higher dose rates, in the range of $1\text{–}5\ \mathrm{Gy \cdot min^{-1}}$, brought an increase in the use of brachytherapy. All high dose-rate (HDR) brachytherapy treatments are temporary and treatments are administered using discrete fractions.

What Is a Remote Afterloader?

A remote afterloader (RAL) is a computer driven system that transports the radioactive source from a shielded safe into the applicator placed in the patient. Upon termination or interruption of the treatment, the source is driven back to its safe. The device may move the source by one of several methods, most commonly pneumatic air pressure or cable drives.

What is Stepping-Source Remote Afterloader?

A stepping source RAL is a particular design of the treatment unit that consists of a single source at the end of a cable that moves the source through applicators placed in the treated volume. The treatment unit can treat implants consisting of many needles or catheters in the patient. Multiple catheters are often required to cover the target with adequate radiation doses. Each catheter or part of an applicator is connected to the RAL through a channel. The computer drives the cable so that the source moves from the safe through a given channel to the programmed position in the applicator (dwell position) for a specific amount of time (dwell time). In any applicator, there may be many dwell positions. After treating all the positions in a given catheter (channel) the source is retracted to its safe and then driven to the next channel. The dwell positions and the dwell time in each channel are independently programmable, thereby giving a high level of flexibility of dose delivery. All currently available HDR RALs use the stepping-source design.

Currently there are three types of HDR RALs available in the market: MicroSelectron (Fig. 1, vendor Nucletron, Veenendaal, Netherlands), Gamma-Med (Fig. 2), and VariSource (Fig. 3, both marketed by Varian Associates, Palo Alto, CA).

The specific features of the three different RALs are shown in Table 1.

COMPONENTS OF A HIGH DOSE RATE REMOTE AFTERLOADER

While different in detail, all available HDR RALs consist of the same general components. Figure 4 gives an overview of the systems, with the major parts described below.

Shielded Safe

To provide a dose rate in the range of $1\text{–}5\ \mathrm{Gy \cdot min^{-1}}$ in a RAL requires a $^{192}\mathrm{Ir}$ source of 4–10 Ci. A shielded safe, which is an integrated part of the treatment unit, provides enough radiation shielding to house the source while not in treatment mode. Once in treatment mode, the source is driven out of the safe while it follows the program through the dwell positions. In the event of an interruption or termination of the treatment, the source is driven back to the shielded safe.

Radioactive Source

While delivering the HDR brachytherapy requires an intense source, passing the source through needles placed through a tumor requires one of a small size. The radioactive source in an HDR RAL is usually 3–10 mm in length



Figure 1. The Nucletron MicroSelectron V2 HDR RAL. The RAL wheels allow it to be conveniently positioned near the patient. The treatment head is mounted on a telescopic base that allows the head to be raised or lowered to the required height for treatment without moving the patient.



Figure 2. The Varian GammaMed RAL.



Figure 3. The Varian VariSource RAL.

and < 1 mm in diameter, fixed at the end of a steel cable (Figs. 5 and 6). The Nucletron source is placed in a stainless steel capsule and welded to the cable, while the Varian source is placed in a hole drilled into the cable and closed by welding. The ^{192}Ir radionuclide is now used for all HDR RALs, although early versions of HDR RAL used ^{60}Co. A new source has an activity near 10 Ci. Since ^{192}Ir has a half-life of 74 days, the source should be replaced every 3 months to keep the treatment in the HDR radiobiological regime. A trained medical physicist calibrates the source after each installation using a re-entrant well-type ionization chamber (Fig. 7). The chambers themselves are calibrated by secondary calibration laboratories known as Accredited Dosimetry Calibration Laboratories (ADCL). The resulting source calibration is verified against the manufacturer's source calibration.

Source Drive Mechanism

When the RAL unit receives a command to initiate a treatment, the stepper motor connected to the reel containing the drive cable turns, causing the source cable to advances from the shielded safe along a path constrained by transfer tubes to the first treated dwell position in the applicator attached to the first channel. The source dwells at that position for a predetermined duration (dwell time) as calculated by the treatment planning system (see below). After completing that dwell, it goes on to the subsequent dwell positions. Some units step as the source drives out (MicroSelectron), stopping first at the dwell position most proximal to the afterloader, while the other (VariSource and Gamma-Med) the source travels first to the most distal dwell (toward the tip of the applicator), and a bit farther, and then steps as the source returns toward the safe. Stepping on the outward drive obviates any concern about the effect of slack in the drive mechanism affecting the accuracy of the source position. The unit that steps on the way back into the unit includes correction for slack in the calibration of the source location. Upon completion of the treatment for the first channel, the source is retracted into the safe, and redirected to travel to the second channel. The process is repeated for all the subsequent treatment channels. The programmed movement of the source is verified by means of an optical encoder or other devices that compare the angular rotation of the stepper motor or cable length ejected or retracted with the number of pulses sent to the drive motor. This system is capable of detecting catheter obstruction or constriction as increased friction in the cable movement. Under certain fault conditions, if the stepper motor fails to retract the source, a high torque direct current (dc) emergency motor will retract the source.

The confirmation of the source exit from and return to the safe is carried out by an "optopair", consisting of a pair of light-sensitive detector and infrared (IR) light source, that detects the cable when its tip obstructs the light path. All the currently marketed after-loaders are also equipped with check cables or dummy sources. The check cable is an exact duplicate of the radioactive source along with its cable, except not radioactive. Before the ejection of the radioactive source, the check cable is first ejected to check the integrity of the catheter system. After a noneventful check by this "dry run" with the dummy source, the radioactive source is then sent for treatment.

Indexer

The RALs are equipped with an indexer, shown in Fig. 8. The indexer consists of an S-tube (item 14 in Fig. 4) that directs the source cable from the exit of the safe to one of the exit ports from the unit (channels). The various catheters or applicator parts connect to these channels, usually through connecting guides called transfer tubes. Different units have between 3 and 24 channels available for

Table 1. Specific Features of the Three Currently Marketed HDR RALs

	MicroSelectron V2	Gamma Med+	VariSource 200/200t
Vendor	Nucletron	Varian	Varian
Sources	10 Ci of ^{192}Ir	10 Ci of ^{192}Ir	10 Ci of ^{192}Ir
Source dimension	3.5 mm L, 1.1 mm OD	4.52 mm L, 0.9 mm OD	5 mm L, 0.59 mm OD
Channels	18	3 or 24	20
Source extension	1500 mm	1300 mm	1500 mm
Channel length	Variable	Fixed	Variable
Source movement	Stepping forward	Stepping backward	Stepping backward
Step sizes	2.5, 5 or 10 mm	1–10 mm, 1 mm steps	2–99 mm, 1 mm steps
Dwells/channel	48	60	20
Speed of source	50 cm $\cdot$ s^{-1}	60 cm $\cdot$ s^{-1}	50–60 cm $\cdot$ s^{-1}


Source cable drive
Check cable drive
- Source cable drive, consisting of:
1. Source stepper motor
2. Shaft encoder
3. Wire-in switch
4. Emergency stop motor
5. Cable guide tube
- Check cable drive, consisting of:
6. Check cable stepper motor
7. Shaft encoder
8. Cable guide tube
- Indexer, consisting of:
9. Indexer stepper motor
10. Indexer disk
11. Indexer channel encoder
12. Treatment tube / adaptor optopair
13. Locking ring optopair
14. Channel selection tube
Reference optopair
Reference optopair block
Safe
Channel 18
Channel 1
1
2
3
4
5
6
7
8
9
10
11
12
13
14

Figure 4. Schematic diagram of a single stepping source RAL. (Courtesy of Nucletron Corporation, Columbia, MD.)


0 1 2 3 4 5 6
CENTIMETERS

Figure 6. A ^{192}Ir HDR source for the MicroSelectron at the end of a steel drive cable, as shown in Fig. 5.

connection. If a patient's treatment requires more than the number of channels on a given treatment unit, the treatment must be broken into sessions, where the catheters are connected up to the number of channels available and treated Then the transfer tubes are disconnected from the catheters just treated and reconnected to the next set of catheters for continuation of the treatment.


Source diameter 0.6 mm
5 mm
3.5 mm
Cable diameter 1.1 mm
Iridium source
MicroSelectron high dose-rate source
Source diameter 0.34 mm
Iridum Source
Cable diameter 0.59 mm
10 mm
VariSource high dose-rate source

Figure 5. Schematics of the two types of sources used in stepping-source RALs. The VariSource is an earlier version, while the new source has a length of 5 mm.



Figure 7. A re-entrant well-type ionization chamber used for calibration of the HDR brachytherapy sources.

Transfer Tubes

Transfer or guide tubes are long tubes that act as a conduit to transfer the source from the RAL to the applicators or catheters for treatment. One end of the transfer tube is attached to the indexer of the RAL (Fig. 9), while the other end is attached to the interstitial, intracavitary, or transluminal applicators (Fig. 10). The applicator-end of the transfer tube contains spring-loaded ball bearings that block the path through the tube if no applicator is attached. When an applicator is inserted, it pushes aside the ball bearings, opening the path for the source cable. When the



Figure 8. The frontal view of an indexer from the Nucleotron, MicroSelectron HDR RAL, consisting of 18 channels.



Figure 9. A view of two types of transfer tubes hooked up to the indexer of a RAL.



Figure 10. View of the transfer tubes connected to a gynecological applicator. Ball bearings beneath the gray polymer coating allow verification of the proper connection of the transfer tubes to the applicator. The number 1 and 2 represents that these transfer tubes must connect the channel 1 and 2 of the indexer ring and the similarly numbered parts of the applicator.



Figure 11. Gynecological applicator used for the treatment of cervical cancer. (Courtesy of Nucletron Corporation, Columbia, MD.)

check cable makes its test run, if no applicator is attached to the transfer tube, the check cable hits the obstacle of the ball bearings, and prevents ejection of the source. Each type of applicator has its own type of transfer tube.

Applicators

An array of applicators for different treatment sites are marketed by each vendor. Each vendor designs their own applicators that can only be used with their transfer tubes and HDR RALs. Figure 11 shows two cervical applicators marketed by Nucletron used for the treatment of cervical cancer.

Treatment Control Station

The treatment control station (Fig. 12) allows the user to select the source travel and dwell sequence to be used in each channel. This can be entered by three ways: (*1*) manually by the keyboard/mouse at the control station; (*2*) recalling a standard plan from the computer and then editing the data without affecting the standard plan from which it originated; or (*3*) by importing the data from a treatment planning system via transfer medium or a network connection to the treatment control station.



Figure 12. A view of the monitor of the RAL treatment control station.

Treatment Control Panel

The treatment control station transfers the data to the treatment control panel. A hard or soft START button initiates the execution of the treatment according to the program. In addition, there is an INTERRUPT button, which when pressed retracts the source and stops the timer, allowing the user to enter the treatment room without receiving radiation exposure. A RESUME or START button resumes the treatment from the time and the dwell position where it was interrupted. A master EMERGENCYOFF button initiates the high torque dc emergency motor to retract the source. In the normal course of a successful termination of the treatment, the timer runs to zero and the machine automatically retracts the source. Figure 13 shows an example of the treatment control panel.

SAFETY FEATURES

The HDR RALs are complicated devices containing very high activity radioactive sources. Serious accidents can



Figure 13. The Treatment Control Panel of the Nucletron, microSelectron HDR RAL. The START button is the white button on the right side of the panel, while the EMERGENCY OFF button is the top button on the left side of the panel.



Figure 14. A view of the access panel of the MicroSelectron treatment unit. The center button is an emergency stop button on the treatment unit. Also showing are the manual retraction of the radioactive source cable (left) and the check cable (right).

happen quickly. All such units have many safety features and operational interlocks to prevent errant source movement or facilitate rapid operator response in the event of a system failure.

Emergency Switches

Numerous EMERGENCY OFF switches are located at convenient places and are easily accessible, in case a situation arises. One EMERGENCY OFF switch is located on the control panel. Another EMERGENCY OFF button is located on the top of the remote afterloader treatment head. Vendors usually install one or two emergency switches in the walls of the treatment room. In the event a treatment is initiated with someone other than the patient in the treatment room, that person can stop the treatment and retract the source by pressing the EMERGENCY OFF button. Figure 14 shows the EMERGENCY OFF switch on the treatment unit.

Emergency Crank

All HDR RALs have emergency cranks to retract the source cable if the source fails to retract normally and the emergency motor also fails to reel in the source. Figure 14 shows such a crank for the MicroSelectron and Fig. 15 for the VariSource. Using the crank requires the operator to enter the room with the source unshielded. Exposure rates for this situation are considered below.

Door Interlock

Interlock switches prevent initiation of a treatment with the door open. While in progress, opening the door interrupts the treatment. This safety feature protects the medical personnel from radiation exposure, in the event somebody enters the treatment room without the knowledge of the operator. If a door is inadvertently opened during the treatment, the treatment is interrupted and the source returns to the safe. The treatment can be resumed at the same point where it was interrupted by closing the door and pressing the START or the RESUME button at the control panel.



Figure 15. The back panel of the VariSource showing the crank for manual source retraction in an emergency.

Audio–Visual System

All HDR brachytherapy suites are equipped with a closed circuit television system (CCTV) or shielded windows and/or mirrors for observing the patient, and a two-way audio system to communicate with the patient during treatment.

Radiation Monitor and Treatment on Indicator

Three separate independent systems alert personnel when the source is not shielded. One radiation detector is part of the treatment unit and indicates on the control panel when it detects radiation. An independent unit, usually mounted on the treatment room wall with displays both inside and outside the room also alerts the operator and other personnel when the radioactive source is out of the safe. A TREATMENT ON Indicator outside the room, activated when the source passes the reference optical pair discussed above and shown in Fig. 4, also indicates that a treatment is in progress.

Table 2. Exposure Rates from an Exposed 10 Ci ^{192}Ir Source

			Time, min, to Receive	
Typical Situation	Distance, m	Dose Equiv Rates, $Sv \cdot h^{-1}$	10 Gy (likely injury)	0.5 Sv (annual body limit)
In Patient	0.01	460	1.25 min	0.07 min
Handling with Kelly Clamps, to hands	0.1	4.6	2.1 h	6.5 min 98 min for hand limit
Handling with Kelly Clamps, to body	0.3	0.5	18.8 h	1.0 h
Standing near	1	0.046	8.7 days	11 h
Standing far	2	0.012	34.8 days	43 h

Emergency Service Instruments

In the event the radioactive source fails to retract after termination, interruption, pushing the EMERGENCY SWITCH, or cranking the stepper motor manually, the immediate priority is to remove the source from the patient. Table 2 gives the exposure rates at various distances from a 10 Ci ^{192}Ir source. Table 2 shows that the dose to the patient, with the source in contact, can cause injury in a very short time. On the other hand, the operator, working at a greater distance, is unlikely to receive a dose exceeding regulatory limits for a year, let alone one that would cause health problems. Once the source is removed from the patient and moved to a distance of even a meter, the exposure rate is quite low, and whatever actions need be taken to remove the patient from the room can be performed safely.

The effective annual limit to the body should actually be 10 times $<$ the 0.5 Sv in keeping with the principle to keep exposures as low as reasonable achievable (ALARA), and ideally should not be received in one, short exposure. The allowed exposure to the hands is 15 times that to the body.

The preferred approach to a source that will not retract by any of the methods is to remove the applicator from the patient as quickly as possible, and place the applicator containing the source in a shielded container (Fig. 16). If it is clear that the cable is caught in the transfer tube and not in the applicator itself, the applicator or catheter may be disconnected from the transfer tube and the source pulled from the applicator. In some cases, this will be faster than removing the applicator. The reason to avoid disconnecting the applicator from the transfer tube is that a source may stay in the applicator if the source capsule shatters. In that case, removing the applicator attached to the transfer tube keeps the system closed, while disconnecting the two opens a path for parts of a broken source to fall from the applicator into body cavities or crevices, or roll onto the floor.

A situation may arise when the source needs to be detached manually from the treatment unit. One (still unlikely) scenario would be if the source were stuck out of the treatment unit, the sources or the closed applicator had been removed from the patient, a person were pinned very close to the source so neither they, nor the treatment unit, could be moved, and the source on the cable could not reach the shielded container. In this special situation, the source cable should be cut from the unit and the source placed in the shielded container always present in the room. In cutting the source cable, it must be clear that the cut is *not* through the source capsule. For units with the capsule welded on the cable, the cut must be through the braided cable as opposed to the smooth steel capsule (Fig. 17). For sources imbedded in the cable, a sufficient length of the cable must be seen to assure the cut occurs behind the source. Thus, emergency tools that must be present in the treatment room and always readily accessible include a wire cutter, a pair of forceps, and a shielded service container.

Back-Up Battery

In case of a power failure during the treatment, the machine is equipped with a back-up battery to provide retraction of the source to its safe. The batteries should be tested with each source exchange.



Figure 16. The shielded container for emergency placement of an unretracted source.



Figure 17. Cutting the source cable from a treatment unit. This procedure should only be performed in very special, rare situations as described in the text. Great care must be taken to assure the cut is through the cable and not the source capsule.



Figure 18. Geometry and legend for the dosimetry of a line source as given in Eq. 1.

TREATMENT PLANNING SYSTEM

Software and hardware for the treatment planning system are provided by the vendor selling the treatment unit. Three-dimensional (3D) patient data [computed tomography (CT), magnetic resonance imaging (MRI)] can be directly transported and loaded in the planning system. Two dimensional (2D) data (e.g., from radiographs) usually are loaded interactively by computer peripherals (scanners, digitizers) although some automated input systems are available. With 2D input, the target information must be inferred since tumors are generally not visible on the images, while the 3D imaging often visualizes tumors as well as surrounding normal tissue structures. With either input, tumor volume is entered on these images, and the treatment-planning volume is constructed by adding some margin to the tumor volume. Various computer algorithms help the planner conform the prescribed dose to the target volume. Data characteristic for the radioactive source are usually supplied by the vendor and included in the software. The medical physicist enters the source strength data both in the planning system and the treatment unit at the time of the installation of the new source in the treatment unit after calibration.

Dose Calculation

The treatment-planning computer calculates the dose distribution for a patient containing an applicator with a given set of dwell positions, each with their own dwell time. In calculating the dose distribution, the computer first calculates the dose to a set of grid points. Usually, the operator wishes to see the results presented as isodose lines. An isodose line on a given plan connects all points receiving the same dose, much like elevation lines on a contour map of part of the Earth connects points with the same altitude. From the dose values at the grid points, the computer interpolates to find the path of the isodose line value specified by the user. The calculation of the dose from one dwell position, identified with the subscript i, to a point $P(r,)$ as shown in Fig. 18, uses the formula (1),

$$D_i(r_i,\theta) = S_{\mathrm{K}}\cdot\Lambda\cdot[G_i(r,\theta)/G(r_o,\theta_o)]\cdot g_i(r_i)\cdot F_i(r_i,\theta)\cdot t_i \quad (1)$$

where

$D_i(r_i,\theta)$ = The radiation dose to water, in units Gy, at position $P(r,\theta)$

S_{K} = The air kerma strength of the source in $\mu\mathrm{Gym}^2\cdot\mathrm{h}^{-1}$. The strength of photon-emitting brachytherapy sources usually is specified by the intensity of the radiation at some distant outside of the source rather than by the amount of radioactivity contained inside. In this manner, variations in the source encapsulation, which may attenuate varying amounts of the radiation given off by the contained radionuclide, have no effect on the dose delivered to the patient. While the strength of a new HDR source is often quoted as 10 Ci (the approximate activity in the capsule), the actual source strength determination accounts for the energy of radiation from the source, transferred to a mass of air at a given point. Air kerma is the energy transferred from the radiation to kinetic energy in the medium per unit mass, where the medium must be specified. That point for air kerma strength is at 1 m, and a new source would have an air kerma strength of $\sim 40\ \mathrm{mGy}\cdot\mathrm{m}^2\cdot\mathrm{h}^{-1}$, or in shorthand, 40 kU, where $1\ \mathrm{U} = \mu\mathrm{Gy}\cdot\mathrm{m}^2\cdot\mathrm{h}^{-1}$. A radiation dose of 1 gray (Gy), equals 1 joule per kilogram ($1\,\mathrm{J}\cdot\mathrm{kg}$).

Λ = The dose rate constant, that is the absorbed dose rate in $\mathrm{cGy}\cdot\mathrm{h}^{-1}$ at 1 cm from the source in the perpendicular plane that bisects the source axis per unit air kerma strength. For ^{192}Ir sources, $\Lambda = 1.12\ \mathrm{cGy}\cdot\mathrm{h}^{-1}/\mathrm{U}$.

$[G_i(r_i,\theta_i)/G(r_o,\theta_o)]$ = The geometry function, which accounts for changes in dose rate due to the relative positions of the source and the calculation point and the shape of the source. The numerator expresses the geometric dose pattern for the point of calculation while the denominator gives that for the reference condition, where $r_o = 1$ cm and $\theta_o = 90^\circ$. The geometric dose pattern usually is approximated as $1/r^2$ for a point source, and for a line source /(L·h) as shown in Fig. 18.

$g_i(r_i)$ = The radial dose function, variation in the dose rate with distance from the source due to the attenuation and scatter due to the tissue between the source and the point of calculation at distance r, normalized at 1 cm, and not including any effect in dose rate due to geometry (i.e., the geometric function has been removed from the dose at the calculation distance and at 1 cm for the ratio).

$F_i(r_i,\theta)$ = The anisotropy function, which describes the deviation of the shaped of the isodose lines from a circle. The function $F_i(r_i,\theta)$ = the dose at the calculation point $P(r,\theta)$ divided by the dose at the same distance, r_i but on the perpendicular bisector, that is with $\theta_o = 90^\circ$, and, as with the radial dose function, with the geometrical effects removed.

t_i = the dwell time for dwell position i.

Dose Optimization

The treatment planning addresses first which dwell positions will be used. Then for each of the dwell positions, the dwell time must be calculated. The goal is to match the resulting dose distribution with the target volume, a process referred to as optimization. There are several methods to assist the operator in optimizing the dwell times. The methods fall into three main categories:

Analytic methods use relatively simple algorithms to calculate the dwell time for each dwell position. One of the most common, geometric optimization (2,3), weights the dwell time for a position inversely to the sum of the doses to that position from the other dwell positions. For an intracavitary application, where the dose distribution is intended to more or less conform to the shape of the applicator tracks, "distance optimization" is used, where the contributions of all of the other dwell positions are included in the summation of the dose. For interstitial application, where the implant usually treats a volume, the process becomes "volume optimization", with the dose contributions from dwell position along the same track excluded in the summation.

Dose specification methods attempts to calculate the dwell times to deliver a specified dose to designated points (dose points or optimization points) placed throughout the volume or on the surface of the target (4–6). The dose to each specified point described an equation with the dose to the point on one side and the contributions from each of the dwell positions on the other,

$$\text{Dose} = S_K \cdot \Lambda \cdot \sum_{i}^{\text{all dwells}} \{[G_i(r_i,\theta)/G(r_o,\theta_o)] \cdot g_i(r_i) \cdot f_i(r_i,\theta) \cdot t_i\} \qquad (2)$$

In the simplest situation, such an approach becomes solving a set of simultaneous equations for the doses to the optimization points for the unknown dwell times. The problem comes when there are more equations than unknowns (more dose points than dwell positions and the set is over determined) or the converse (when the set is underdetermined). In the general case, the set is solved by a least-squares method to find the values for the dwell times that minimizes the square of the difference between the doses desired and the doses resulting from times in the set of equations. However, it is very helpful to add an additional criterion on the dwell times: controlling the fluctuation in dwell times between adjacent positions. The optimization equation becomes

$$\mathrm{X}^2 = \sum_{j=1}^{\text{All dose points}} (D_j^{\text{precribed}} - D_j^{\text{calculated}})^2 + V \sum_{i=1}^{\text{dwells}-1} (t_{i+1} - t_i)^2 + u \sum_{i=1}^{\text{all dwells}} t_i \qquad (3)$$

where the first term considers the difference between the prescribed dose and that calculated dose for each specified point. The value of the second term depends on the differences in dwell times between each dwell position and its neighbor. The factor, the dwell weight gradient factor, v, determines how important minimizing this fluctuation is. Large values for v (> 1) tend to force the dwell times to be the same, not producing a very conformal dose distribution; small values (< 0.2) permit negative times to result from the optimization (not a physical situation). The last term minimizes the overall exposure time, assuming that the set of dwell times that adequately treats the target volume with the least total time results in the lowest dose to the rest of the patient. The factor u determines how important minimizing dwell time is for the optimization. The optimized set of dwell times minimizes X^2.

Stochastic methods use iterative techniques to find adequate values for the dwell times. Generally, these approaches establish an objective function, such as the difference in dose to a set of point between that prescribed and that achieved. The function may also include penalties for excessive doses to normal tissue structures or lack of homogeneity through an implanted volume. The goal of the optimization is to obtain the best score for the objective function. The process begins with a set of values for the dwell times, evaluates the objective function, and then makes changes in the dwell times. If the new set of times improves the value of the objective function, the new set becomes the current best set. If the old set of times gave a better value for the objective function, it remains the current best set. Obviously, the strategy for how to pick each new set of values in the core of the methodology, and a more complete discussion is beyond the scope of this text. The most common approaches in the literature are simulated annealing (7) and the genetic algorithm (8).

The goal of all the optimization methods is to adequately treat the target tissues while sparing the sensitive normal structures. A resultant plan is shown in Fig. 19.

SHIELDING

The radioactive source in the high dose rate machine starts ~ 10 Ci with an exposure rate at a distance of 1 m from the



Figure 19. A 3D view of dose distribution of a breast catheter implant with 25 catheters. The inner volume is the tumor volume (lumpectomy cavity), while the outer volume (planning treatment volume) has been generated by adding some margins to the tumor volume. The gray cloud is the dose distribution generated by the treatment planning system.

source of ~ 46 mSv $\cdot$ h^{-1}. According to the rules and regulations of the United States Nuclear Regulatory Commission (USNRC), the annual limit for radiation exposure to the public is 1 mSv and the annual occupational limit is 5 mSv. (The actual limit for occupationally exposure persons is 50 mSv $\cdot$ year^{-1}, but following the principle of maintaining exposures as low as reasonable achievable, the NRC usually holds licensees to exposure 0.1 of the limit.) In addition to the annual limit, NRC requires that in an unrestricted area the dose equivalent rate should not be > 0.02 mSv in any given hour. Thus, the HDR machine needs to be housed in an adequately shielded room. To meet these requirements in a HDR brachytherapy suite, where the walls and the ceiling are at least 1.5 m from the machine head, concrete wall of $\sim$43–50 cm (or 4–5 cm of lead) are needed. For larger rooms the concrete wall thickness will be lower since the exposure rate is inversely proportional to the square of the distance from the radioactive source. For details on the procedures for calculating the thickness of barriers for a particular facility, see health physics texts such as Cember (9) or McGinley (10).

QUALITY ASSURANCE

In order to maintain the quality of patient care, a quality management program is required in every facility that provides HDR brachytherapy treatment. Such a program generally follows standards set by professional organizations and intends to minimize untoward events caused by the malfunction of the machine or human error. Such programs become exceedingly important in HDR brachytherapy because the planning and the treatments tend to happen very quickly, increasing the likelihood of accidents and mistakes. Quality Assurance (QA) tests measure some performance aspect of the treatment unit and compare the results with expectations in order to demonstrate proper operation. QA is performed at various intervals: some for each patient, some once each treatment day, and others with each source change. Moreover, for HDR RAL, the USNRC mandates that users meet certain standards, including education and training on operating the machine, emergency procedures, radiation monitoring, pre-treatment safety checks, safe and accurate delivery of the treatment, and monthly/initial calibration of the source. Since the details of quality assurance is outside the scope of this literature, interested readers can refer to the report of Task Groups 59 (11) and 56 (12) of the American Association of Physicists in Medicine and relevant texts (13).

In general, the problem of quality assurance becomes assuring that the treatment will deliver the correct dose, to the correct location, safely. Thus, the tests generally follow the outline below:

Verification of dose variables.

Checking the strength of the source compared with that projected from the initial calibration based on radioactive decay.

Checking the proper operation of the controlling timer.

Verification of position control.

Checking that the source goes to the location programmed.

Checking coincidence between the programmed positions and the respective positions indicated by imaging markers.

Checking consistent movement of the source.

Verification of proper operation of safety features.

Checking operation of the door interlocks.

Checking the operation of a handheld radiation detector.

Checking the operation of the on-board and on-wall radiation detectors.

Checking the operation of the check cable runs and interlocks.

Checking the operation of the Emergency off and Treatmentinterrupt buttons.

COSTS

Currently, two vendors (Nucletron Corporation and Varian Medical Systems) market their RAL treatment unit in the United States. Both the devices requires a capital expenditure of $\sim$\$500,000–750,000, which includes the treatment unit, a variety of transfer tubes, along with the software and hardware for the treatment planning system. Applicators that are needed to be placed in the tumor costs extra. The costs of preparing a shielded room along with ancillary equipment for X-ray imaging and operating room procedures can be another \$500,000–750,000. Hence, the total cost can run in between \$1–1.5 million (14).

ADVANTAGES AND DISADVANTAGES

HDR comparing with LDR brachytherapy offers several advantages and disadvantages. Being aware of these permits safe and effective operation and application of HDR brachytherapy.

Advantages of HDR Brachytherapy

Safety. One of the major advantages of a RAL is the reduction or elimination of radiation exposure to the radiotherapy staff. In conventional LDR, manual afterloading, the radiotherapy staff receives radiation exposure while loading the applicators with the radioactive sources, and the nursing personnel are exposed during patient care through the duration of the treatment (1–4 days). With either HDR or LDR remote afterloading, the radiotherapy personnel are outside the shielded room during the treatment, and hence are exposed to minimal radiation.

Optimization. The design of the HDR RAL with the stepping source allows greater flexibility and control over dose distribution. The stepping source allows optimization of the dose distribution by adjustment of the dwell times for each dwell position in each channel. The dwell times can be varied infinitely, permitting very fine control of the dose distribution. In LDR, either manual or using an RAL, the finite number of activities available (usually four at most) and the larger sources used with manual applications impose a restriction on the ability to conform the dose distribution to the target.

Stability. Because HDR intracavitary treatments take so little time ($\sim$ 1 h), applicators can be fixed in place much more stably than for the several day treatments using LDR brachytherapy.

Dose Reduction to Normal Tissue. As with stability, the short duration of HDR intracavitary treatments allows displacement of normal tissue structure (i.e., pushing them away from the source paths) to a greater extent than with LDR treatment.

Applicator Size. The small size of the HDR source permits the use of smaller applicators than those required for the LDR applications, increasing the comfort to the patient.

Outpatient Treatment. Almost all HDR patients are treated on an outpatient basis compared to LDR patients who usually are treated as inpatients. Outpatient treatment is more convenient for the patients and generally results in lower overall costs.

Disadvantages of HDR Brachytherapy

Investment. The initial expense of HDR RAL is very high. Machines and site preparation costs can be anywhere between \$0.5 and 1 M.

Complexity. The technological complexity of HDR RAL opens the increased probability of errors, and leads to increased regulatory scrutiny.

Compressed Time Frame. As mentioned above, the rapidity with which procedures progress in HDR brachytherapy increases the probability of executing errors.

Radiobiology. As the dose rate increases, the radiosensitivity (damage per unit dose) increases for both normal tissues and tumors. Unfortunately, the radiosensitivity for the normal tissue increases faster than that for tumors, increasing the likelihood of injuring the patient while controlling the tumor. Overcoming this radiobiological handicap requires the use of the advantages of *optimization*, *stability*, and *dose reduction to normal tissues*, in addition to fractionization. As with external-beam radiotherapy delivered using a linear accelerator, which also operates in the HDR regime, spreading the treatments over many smaller fraction delivered over several days reduces the difference in radiosensitivities between the tumor and the normal tissues.

BIBLIOGRAPHY

Cited References

1. Nath R, Anderson LL, Luxton G, Weaver KA, Williamson JF, Meigooni AS. Dosimetry of interstitial brachytherapy sources: Recommendations of the AAPM Radiation Therapy Committee Task Group No. 43. Med Phys 1995;22:209–234.
2. Edmundson GK. Geometry based optimization for stepping source implants. Activity—The Selectron User's Newsletter 1991;5:22.
3. Edmundson GK. Geometric optimisation: an American view. In: Mould RF, editor. International brachytherapy. Veenendaal, The Netherlands: Nucletron International BV; 1992, p 256.
4. van der Laarse R. Optimization of high dose rate brachytherapy. Activity—The Selectron User's Newsletter 1989;2:14–15.
5. van der Laarse R, Edmundson GK, Luthmann RW, Prins TPE. Optimization of HDR brachytherapy dose distributions. Activity—The Selectron User's Newsletter 1991;5:94–101.
6. van der Laarse, Thomadsen BR, Houdek PV, van der Laarse R, Edmunson G, Kolkman-Deurloo I-KK. Treatment planning and optimization. In: Nag S, editor. High dose rate brachytherapy: a textbook. Armonk, (NY): Futura Publishing Co.,; 1994. p 85–91.
7. Sloboda RS. Optimization of brachytherapy dose distributions by simulated annealing. Med Phys 1992;19:955–964. See also, Sloboda RS, Pearcey RG, Gillan SJ. Optimized low dose rate pellet configuration for intravaginal brachytherapy. Int J Radiation Oncol Biol Phys 1993;26:499–511.
8. Davis L. Handbook of Genetic Algorithms. New York: Van Nostrand Reinhold; 1991.
9. Cember H. Introduction to health Physics. 3rd ed. New York: McGraw-Hill; 1996.
10. McGinley P. Shielding Techniques for Radiation Oncology Facilities 2nd. Madison: Medical Physics Publishing; 2002.
11. Kubo HD, Glasgow GP, Pethel TD, et al. High dose-rate brachytherapy treatment delivery: AAPM Radiation Therapy Committee Task Group No. 59. Med Phys 1998;25:375–403.

12. Nath R, Anderson LL, Meli JA, et al.Code of practice for brachytherapy physics: AAPM Radiation Therapy Committee Task Group No. 56. Med Phys 1997;24:1557–1598.
13. Thomadsen BR. Achieving Quality in Brachytherapy. Bristol: Institute of Physics Press; 1999.
14. Rivard MJ, Kirk BL, Stapleford LJ, Wazer DE. A comparison of the expected costs of high dose rate brachytherapy using ^{252}Cf versus ^{192}Ir. Appl Radiat Isot 2004;61:1211–1216.

See also BRACHYTHERAPY, INTRAVASCULAR; HYPERTHERMIA, INTERSTITIAL; PROSTATE SEED IMPLANTS; RADIATION DOSIMETRY FOR ONCOLOGY.

BRACHYTHERAPY, INTRAVASCULAR

FIRAS MOURTADA
MD Anderson Cancer Center
Houston, Texas

INTRODUCTION

Intravascular brachytherapy (IVB) is a novel treatment modality that delivers ionizing radiation to a coronary artery to prevent renarrowing, that is, restenosis caused by stent placement within the artery. The term *brachy* is the Greek word for near since the radioactive source is placed inside or near the target cells. In general, the field of brachytherapy has been practiced for decades in the field of radiation oncology for treatment of intracavitary (vagina, bronchus, esophagus, rectum, nasopharynx, etc.) and interstitial (muscle sarcoma, prostate, breast, etc.) cancers. As a subspecialty, IVB is relatively new where most of its development took place in the 1990s. Ionizing radiation describes both electromagnetic (γ rays, X rays) and particulate (neutrons, beta, and alpha particles) of sufficient energy to remove electrons from the target atom (thus ionizing). Unlike conventional brachytherapy where the target is mostly centimeters away from the source, IVB targets the adventitia of the vessel wall, located within 1–5 mm from the radioactive source. To obtain accurate dosimetry data in such close range is a challenge. The scope of this article is on the delivery devices for IVB and tools needed to assess the dosimetric properties of such brachytherapy devices. (Dosimetry is a subspecialty of radiation physics that deals with the measurement of the absorbed dose or dose rate resulting from the interaction of ionizing radiation with matter.) Such techniques are useful and can be applied in other future applications that require delivery of ionizing radiation to a target within a few millimeters from a radioactive source.

Mechanisms of Restenosis

A diseased coronary vessel is mainly caused by atherosclerotic plaque formation containing mostly cholesterol and lipids. This condition can lead to a heart attack and chest pain (angina) where the blood flood within the lumen is compromised. Coronary artery bypass surgery (CABG) is the traditional method to alleviate this condition. In the last few decades, minimally invasive procedures have been developed in a field known as *Interventional Cardiology*. Percutaneous transluminal coronary angioplasty (PTCA), first performed by Gruentzig in 1977 (1); and endovascular prosthetic devices (stents), first performed by Dotter et al. (2) and Cragg et al. (3) in 1983, are the most common devices used in interventional cardiology today. Charles Thomas Stent (1807–1885), an English dentist who lent his name to a tooth mould. Charles Dotter used the word “stent” in 1963 to name endoluminal scaffolding devices. However, these interventions have created a new problem, restenosis.

Restenosis is a wound healing process occurring directly at the angioplasty balloon or stent site. It is believed that three processes cause restenosis: elastic recoil, neointimal hyperplasia, and negative vascular remodeling. Elastic recoil, or vessel spasm, occurs in the healthy (plaque-free) portion of the vessel within minutes after balloon expansion (angioplasty balloon or stent-expanding balloon). Elastic recoil causes a luminal cross-sectional area reduction of $\sim 50\%$, but only for a short time after the procedure. The second component of restenosis is neointimal hyperplasia resulting in new tissue growth occupying the microcracks and rapture within the plaque mass, in some patients this process can be overcompensating, filling more tissue within the vessel lumen thus compromising blood flow. The blood vessel wall (any vessel larger than capillaries) has three major layers called tunica, the innermost layer is the intima followed by a middle concentric layer called the media where mostly the smooth muscle cells reside, and then the outer most layer called the adventitia. The adventitia contains a connective tissue with mainly collagen and myofibroblasts. Some controversy still remains as to which cells are responsible for neointimal hyperplasia, media smooth muscle cells, or myofibroblasts migrating from the adventitia. In IVB, the prescription dose should reach the tunica adventitia to insure full therapeutic benefit. The third component of restenosis is negative remodeling. The term negative remodeling refers to contraction of the arterial wall following an arterial injury inflicted by an interventional procedure occurring slowly over the first 3–9 months after the angioplasty. Negative remodeling is believed to play a major factor in restenosis after a PTCA intervention. However, the stent is a mechanical scaffolding device that prevents negative remodeling. Hence, in-stent restenosis appears to derive almost exclusively from neointimal hyperplasia, even more than seen in balloon angioplasty. Schwartz and Holmes (4) provide a detailed discussion on restenosis and remodeling. Hall et al. (5) present on the radiobiological response of vascular tissue to IVB. (5).

Epidemiology and Clinical Trials

Restenosis is a very likely event (within few months of the initial intervention) and has been a frustrating problem in interventional cardiology. For example, >1 million people worldwide had percutaneous coronary interventions in 2001 and of these $>85\%$ received a stent. Restenosis occurred in $>50\%$ of the stented patients ($\sim 425{,}000$ patients worldwide), with the United States share of $\sim 150{,}000$ patients.

Restenosis as measured using quantitative coronary angiography (QCA) is arbitrarily defined as a narrowing



Figure 1. Percent restenosis reduction reported in bare-metal stent (STRESS and BENESTENT), and in intravascular brachytherapy clinical trials Gamma I (^{192}Ir), START (^{90}Sr/^{90}Y), and INHIBIT (^{32}P).

of the vessel lumen of at least 50% relative to the adjacent healthy vessel lumen ratio of minimum lumen diameter (MLD) to the reference lumen diameter (RLD). Mehran et al. (6) studied several risk factors from angiographic patterns of in-stent restenosis (ISR). The MLD, lesion length, and diabetes were found to be important factors predicting in-stent restenosis risk. Risk increased as a function of lesion length (10–40 mm) and decreased as a function of the MLD (2.5–4 mm diameter). Further, the ISR pattern is important where diffused restenosis has a larger risk those with a focal pattern.

The main complications of PTCA are acute vessel occlusion and late restenosis. Two important trials started in 1991, the North American STRESS (STent REStenosis Study) (7) and the European BENESTENT (BElgium Netherlands STENT trial) (8) using metal-bare stents (Palmaz-Schatz stent) transformed the practice of interventional cardiology. (Bare-metal stent is a term used here to make a distinction from the drug-coated stent briefly discussed in this article.) However, in-stent restenosis incidence of $>50\%$ was still observed. The introduction of IVB in the 1990s revamped the hope to eradicate restenosis. Condado et al. (9) in 1997 conducted the first small human trial showing reduction in restenosis over a 5 year follow-up period; this study, however, had some dosimetric issues. Definite multicenter double-blinded randomized clinical trials for IVB for the indication of in-stent restenosis are the GAMMA I (10), the START (Strontium-90 Treatment of Angiographic Restenosis Trial) (11), and the INHIBIT (INtimal Hyperplasia Inhibition with Beta In-stent restenosis Trial) (12). With over 5000 patients treated with IVB, this modality has recently proven its safety and efficacy. As shown in Fig. 1, IVB (GAMMA I, START, INHIBIT) clinical trials had about twofold reduction of in-stent restenosis than found from the STRESS and BENESTENT bare-metal stent versus. PTCA trials. Initial problems in the IVB trials, like edge failure due to geographic miss and increased incidence of later thrombosis, were quickly remedied by increasing the radioactive source length and prolonged use of antiplatlet therapy. Table 1 is a detailed summary of these IVB clinical trials. Many other clinical IVB clinical trials were conducted using various isotopes, delivery system, and other clinical indications.

THEORY AND DETAILED DESCRIPTION OF IVB DEVICES

Based on the clinical trials discussed above, the Food and Drug Administration (FDA) granted a premarket approval (PMA) to three IVB devices. The Checkmate system (Cordis Corporation, a Johnson & Johnson Company, Miami Lakes, FL) using ^{192}Ir and BetaCath system using ^{90}Sr (Novoste Corp. Norcross, GA) were both approved on November 3, 2000. About 1 year later, the GALILEO Intravascular Radiotherapy System (Guidant Corp., Santa Clara, CA) using ^{32}P was also approved by the FDA. All of these devices are classified as catheter-based radiation delivery systems using sealed radioactive sources. Catheter-based means the source in the form of a source wire or a train of seeds (ribbon) is placed inside a closed-tip lumen catheter. The catheter is first placed into the target vessel and the source wire or ribbon is delivered or afterloaded using manual or computer-based delivery systems. The radiation safety considerations for these devices have been greatly discussed in the literature (13,14).

Other irradiation techniques were also investigated, including inflation of dilatation balloon catheter with radioactive liquid or gas; insertion of miniature X-ray tubes; implantation of radioactive stents; and postangioplasty external beam irradiation. These techniques did not make it to the market due to variable reasons including suboptimal efficacy, safety, or practicality. Table 2 summarizes several other isotopes and delivery systems investigated for IVB applications. Tables 3 and 4 list a few radiation characteristics for important gamma and beta sources for IVB.

Cordis Checkmate System

Checkmate is indicated by the FDA for the delivery of therapeutic doses of gamma radiation for the purpose of reducing in-stent restenosis. The system is for use in the treatment of native coronary arteries (2.75–4.0 mm in

Table 1. Summary of Pivotal IVB Clinical Trial Used to Obtain FDA Approval for In-Stent Restenosis in Native Arteries Indication

					Angiographic Restenosis		TLR	
Trial	Target Lesion	Source	Dose, Gy	Patients, *n*	Rad., %	Placebo %	Rad. %	Placebo, %
Gamma-1	In-stent (<45 mm)	^{192}Ir ribbon	8–30	252	22	50 (6 months)	24	42 (9 months)
START	In-stent (<20 mm)	^{90}Sr/^{90}Y Seed train	16–20 Gy at 2 mm	476	14	41 (8 months)	16	24 (8 months)
INHIBIT	In-stent (<45 mm)	^{32}P wire	20 Gy at 1 mm into vessel wall	332	16	48 (9 months)	11	29 (9 months)

diameter and lesions up to and including 45 mm in length) with in-stent restenosis following percutaneous revascularization using current interventional techniques. Outside of the FDA approved indication, Waksman et al. (15) also examined the effects of intravascular gamma radiation in patients with in-stent restenosis of saphenous-vein bypass grafts and found favorable results.

Radioactive Source Ribbon. The Checkmate catheter-based brachytherapy system uses ^{192}Ir seeds that are preassembled in 6, 10, and 14 seed strand inside nylon ribbons (Best Medical International, Springfield, VA). Treatment lengths are 23, 39, and 55 mm for the 6-, 10-, and 14-seed ribbons, respectively (16). Iridium-192 has an average energy of 370 keV and a half-life of 73.83 days. The ^{192}Ir radioactive metal (30% Ir, 70% Pt) is 3 mm long and 0.1 mm in diameter encapsulated within a 3 mm long × 0.5 mm diameter stainless steel capsule. The seeds are placed inside a nylon ribbon with an interseed spacing of 1 mm. The overall ribbon length is 230 cm and the outer diameter is 0.76 mm (2.4 F). [1 French (F) = $1/\pi$ mm.] At both distal and proximal edges of the seed strand, radiopaque markers are placed for visualization under X rays. A nonradioactive dummy ribbon is preloaded inside the delivery catheter to provide reinforcement during shipping and to improve maneuverability during initial positioning of the catheter across the target lesion. The dummy ribbon has the same length and configuration of the radioactive source ribbon to aid in IVB therapy planning during the procedure. A source lumen plug is used to prevent the movement of the dummy ribbon inside the Checkmate delivery catheter during initial catheter placement via the femoral artery. Dosimetry characterization of the Checkmate source ribbon are discussed in the literature (17).

Delivery Catheter. This is a single lumen catheter with a distal rapid exchange tip and a closed-ended source lumen for isolation from patient blood contact. Both the radioactive source and the nonradioactive dummy ribbon use this lumen to reach the target. A single radiopaque marker at the distal end of the source lumen is to aid in catheter placement under fluoroscopy. A guidewire is used to guide the catheter along the tortuous pathway into the coronary artery. The guidewire exits the catheter 4 mm from the distal tip of the catheter. The overall length of the Checkmate catheter is 230 cm with a usable length of 145 cm. At the distal portion of the catheter, the outer diameter is 3.7 F (0.049 in.), which is deliverable with 7 F (mm) or larger guiding catheter.

Table 2. Gamma and Beta Sources with Different Delivery Systems Investigated for Intravascular Brachytherapy Applications

Gamma Delivery Systems	Beta Delivery Systems
^{192}Irseed train	^{32}P - wire, stent, balloon
^{125}I-stent	^{90}Sr/^{90}Y - seed train
^{103}Pd-stent, wire	^{90}Y - wire
^{131}Cs-stent	^{188}W/188Re - wire, balloon-liquid
^{99m}Tc-liposome–liquid	^{186}Re - balloon-liquid
	^{133}Xe - balloon-gas
	^{48}V - stent (positron)[a]
	^{62}Cu - balloon-liquid
	^{106}Ru/^{106}Rh - wire
	^{144}Ce/^{144}Pr - wire
	^{68}Ge/^{68}Ga balloon-liquid (positron)

[a] A positron is an electron with a positive charge.

Table 3. Average Energy and Half-Life of Important Gamma Emitters Investigated for Intravascular Brachytherapy Applications

Isotope	Ave Energy, keV	$T_{1/2}$, day
^{192}Ir	370	73.83
^{125}I	28	59.4
^{103}Pd	21	16.97
^{131}Cs	30	9.69

Table 4. Maximum Energy and Half-Life of Important Beta Emitters Investigated for Intravascular Brachytherapy Applications

Isotope	Max Energy, keV	$T_{1/2}$
^{32}P	1710	14.3 day
^{90}Sr/^{90}Y	2280	29.1 year
^{90}Y	2280	64 h
^{188}W/^{188}Re	2120	69.4 day
^{186}Re	1090	90.6 h
^{133}Xe	360	5.3 day
^{48}V	696	16 day
^{62}Cu	2930	9.74 min
^{106}Ru/^{106}Rh	3540	371.6 day
^{144}Ce/^{144}Pr	3000	284.9 day



Figure 2. Checkmate delivery device (Cordis Corporation, a Johnson & Johnson Company, Miami Lakes, FL) is mainly a lead shielded cylinder housing both the radioactive ^{192}Ir source ribbon and dummy ribbon.

Delivery Device. As shown in Fig. 2, the Checkmate delivery device is mainly a lead shielded cylinder housing both the radioactive ^{192}Ir source ribbon and the dummy ribbon. This is a simple device where the proximal end of the source ribbon (nonradioactive part) protrudes from the proximal end of the delivery device and is coiled when not in use. When in use, a threaded cap on the distal end of the delivery device is replaced with a luer connector, which is connected to the hub of the delivery catheter. The source ribbon is pushed forward by hand from the proximal end of the delivery device into the delivery catheter.

Dosimetry. The Checkmate IVB system dosimetry was initially based on intravascular ultrasound (IVUS). From these images, the distance from the center of the IVUS catheter to the outer edge of the media tissue, called the external elastic membrane (EEM) is measured. A minimum of three axial images is taken along the stented vessel segment to determine the maximum and minimum distance from the source to the EEM. The dwell time is then calculated to insure that 8 Gy is delivered to the EEM farthest from the source, provided that no >30 Gy is delivered to the closest EEM. The IVUS-based dosimetry was later simplified to prescribe a fixed dose of 14 Gy at a distance of 2 mm from the centerline of the source. This provided a logistic solution to shorten procedure time and to spread the use of this system since many of catheterization labs in the United States do not have IVUS image modality.

Novoste BetaCath

The first generation BetaCath is a 5.0 F (1.59 mm) system. This system was indicated by the FDA to deliver beta radiation to the site of successful percutaneous coronary intervention for the treatment of in-stent restenosis in native coronary arteries with discrete lesions of $\leq$ 20 mm in length using the 30 or 40 mm system and for longer lesions up to 40 mm using a longer source train (60 mm) in a reference vessel diameter ranging from 2.7 to 4.0 mm. The second generation BetaCath is a 3.5 F (1.17 mm) system, which has an equivalent radioactivity to the 5 F (1.59 mm) system, but is smaller in diameter and fits easily inside a (1.91 mm) guide catheter. This system is intended to deliver beta radiation.

The 3.5 F (1.17 mm) BetaCath system has three main components, the ^{90}Sr source train, the β-Rail 3.5 F delivery catheter, and the 3.5 F delivery device.

Radioactive Source. Strontium-90/Yttrium-90 is a pure beta emitter with any energy spectrum with maximum energy of 2.27 MeV and an average of 0.934 MeV. The long half-life (29.1 years) simplifies treatment planning due to the almost unchanged dose rate of the device during the life cycle of the device (6 month). Each seed is 2.5 mm long and 0.38 mm in diameter for the 3.5 F system (0.64 mm seed diameter for the 5 °F system), manufactured by AEA Technology GmbH, Germany or BEBIG Isotopen- und Medizintechnik GmbH, Berlin, Germany. The radioactive source train consists of a wire jacketed "train" of 12 (30 mm source train), 16 (40 mm source train), or 24 (60 mm source train). The jacketed design was a major improvement over the initial design to eliminate seed movement thus providing uniform dose distribution. A radiopaque mark is placed one each side of each source train to provide visualization under fluoroscopy. Dosimetry characterization of the BetaCath sources are discussed in the literature (18,19).

Delivery Catheter. Only details of the second-generation delivery catheter, β-Rail 3.5 F (1.17 mm), will be discussed. This is a closed-end catheter with a total length of 180 cm (Fig. 3). A longer catheter called β-Rail 3.5 F XL delivery catheter has an overall length of 267 cm if desired. The catheter has a guidewire exit port at 1 cm from the distal tip, that is, a rapid exchange design. This catheter accommodates all source train lengths (30, 40, or 60 mm) that reach a most distal radiopaque marker located inside the delivery catheter. The β-Rail delivery catheter is preloaded with an Indicator of Source Train (IST), this Novoste terminology is used for the nonradioactive dummy source to aid in the measurement and positioning of the delivery catheter to insure adequate radiation coverage. The IST includes two radiopaque markings to delineate 30, 40, and 40 mm source lengths. At the proximal end of the delivery catheter, a proprietary connector is provided to insure a secure connection to the delivery device described next.


Active Train Length
60 mm
40 mm
30 mm
Radiopaque Tip Marker (light)
Indicator of Source Train (IST) [pre-loaded in Catheter]
Guidewire Exit Port (1 cm from sp)
β-Rail™ 3.5F Delivery Catheter
Internal Radiopaque Marker (dark) [Source Train Stop]
100 cm Depth Marker
IST Hub
Luer Fitting
Proprietory Connector
β-Rail™ 3.5F Delivery Catheter Overall Length: 180 cm
β-Rail™ 3.5F XL Delivery Catheter Overall Length: 267 cm
Beta-Cath™ 3.5F Transfer Device

Figure 3. The β-Rail 3.5 F delivery catheter (Novoste, Norcross, GA) is a closed-end catheter with a total length of 180 cm. A longer catheter called β-Rail 3.5 F XL delivery catheter has an overall length of 267 cm is available. (Courtesy of Novoste Corporation.)

Delivery Device. This is a handheld battery-powered device used to store the radioactive source train (only one length). Hence, three separate delivery devices are needed to accommodate the 30, 40, and 60 mm source trains described above. The source train is sent into and returned from the delivery catheter using hydraulic pressure. To insure safe attachment of the delivery catheter, a connector lock latch is provided at the exit port of the delivery device. Several electronic pressure sensors are used to provide the operator with feedback on the pressure required using a saline-filled syringe to send, hold, or return the source train. Two source train position indicator lights (Green: In/Amber: Out), adjacent to the source chamber-viewing window (see Fig. 4). A fluid control lever controls the fluid flow and direction of the source train movement. A treatment counter tracks the number of procedures or test runs, a maximum of 125 transfers is allowed.

Dosimetry. The BetaCath IVB system dose prescription is the simplest out of the three systems discussed. The dose prescription is given relative to the source axis at 2 mm radial distance. The recommended dose is 18.4 Gy for a measured reference vessel diameter < 3.35 mm, but > 2.7 mm; and 23 Gy for a diameter > 3.35 mm, but < 4.0 mm. Vessel diameters < 2.75 mm or > 4.0 mm can be treated with this system; however, this is considered an off-label use of the device as defined by the FDA. The appropriate source train length (30, 40, or 60 mm) is selected after measuring the injured length using angiography and adding a margin on the distal and proximal side of a minimum of 5 mm.

Guidant Galileo

This IVB system is the only computer-based device. The GALILEO Intravascular Radiotherapy System (Guidant Corp., Santa Clara, CA) consists of three main components: the GALILEO ^{32}P Source Wire, the GALILEO Centering Catheter, and GALILEO Source Delivery Unit (SDU). The first generation product used a 27 mm long ^{32}P source and spiral centering catheter. The second generation, called GALILEO III uses a 20 mm long ^{32}P source, a trichannel centering catheter, and an automated high precision stepping algorithm.

The first generation GALILEO was indicated to deliver beta radiation to the site of successful percutaneous coronary intervention for the treatment of in-stent restenosis


Proprietary connector receptacle
Distal radiopaque source train marker
Proprietary connector lock latch (locked)
Open
Close
Gate control switch in CLOSE position
Jacketed source train
60 mm
Source chamber
Proximal radiopaque source train marker
SEND
Amber arrow indicator light
Out In
Green arrow indicator light
Fluid control lever in RETURN position
Syringe luer
On/off button
RETURN
Pressure indicator lights
Low battery indicator
Tx
Novoste
BETA-CATH™ 3.5F SYSTEM
Fluid collection bag luer

Figure 4. The BetaCath 3.5 F system (Novoste, Norcross, GA) is a handheld battery-powered device used to store the radioactive source train (only one length of 30, 40, or 60 mm source trains). Source train transfer depends on hydraulic pressure. Several electronic pressure sensors are used to provide the operator with feedback on the pressure required using a saline-filled syringe to send, hold, or return the source train. (Courtesy of Novoste Corporation.)

in native coronary arteries with discrete lesions ≤ 47 mm in reference vessel diameter 2.4–3.7 mm. The second generation GALILEO III system extended the indication to treat injured arterial length up to 52 mm.

Radioactive Source. The active wire contains linear solid-form phosphorus 32 (^{32}P) in ceramic glass fiber sealed in the distal end of a flexible nitinol (NiTi) hypotube, which is welded to a nitinol wire (total wire length is 2430 mm). The nominal active length is 27 mm (first generation system) 20 mm (second generation system). Both source wires have an outer diameter of 0.46 mm. Phosphorus-32 is a pure beta-emitting isotope with a maximum energy of 1.71 MeV, an average energy of 0.690 MeV, and a half-life of 14.28 days. The active wire can be used in multiple procedures for $\sim$4 weeks (two half-lives). The active wire has two 1 mm tungsten X-ray markers, one proximal and one distal from the source, for visualization (see Fig. 5). A dummy source is used before the active wire is delivered to verify positioning, to check for kinks and catheter obstructions that could prevent the active wire from reaching the treatment site, and to achieve accurate positioning at the treatment site. Similar to the active wire, the dummy source also has two tungsten markers, making it visually identical to that of the active wire. Dosimetry characterization of the Galileo sources are discussed in the literature (20,21).

Delivery Catheter. This is a dual-lumen catheter with a spiral-shaped (first generation) or triloped balloon (second generation) to provide source centering within the lumen to improve dose homogeneity (see Fig. 6a and b). Such balloon profiles are designed to center the source within the lumen and to allow distal and side-branch perfusion during the dwell time that can take up to 10 min. This would make the procedure more tolerable for patients. The design of the second generation was found to provide better perfusion than the spiral design, in particular for the longer balloons to treat longer lesions. One lumen allows the automatic advancement of the source wire. At the proximal end of this lumen, a key connector attaches the delivery catheter to the delivery device. The key connector has a special code that reads using an optical sensor at the entry port to automatically determine the balloon length and the number of dwell positions based on the centering catheter used. The distal end of this lumen is closed to prevent contact of the source wire with the patient blood. The second lumen



Figure 5. Cross-section of the ^{32}P source wire (Guidant Corporation, Santa Clara, CA) is shown. The radioactive core has a nominal length of 20 mm and 1 mm tungsten X-ray markers, one on each side of the core. All dimensions are in millimeters. (Courtesy of Guidant Corporation: GALIELO system is no longer manufactured or for sale.)

allows inflation (recommended pressure is 4 atm) and deflation of the centering balloon. This lumen terminates in a luer-lock connector allowing the attachment of standard inflation devices. A third lumen is 5 mm long at the most distal tip of the catheter; this is used to place the delivery catheter over a standard 0.014 in. (0.36 mm) coronary guide wire using a Rapid Exchange approach. Radiopaque markers located at the distal and proximal end of the balloon allows proper placement of the delivery catheter under fluoroscopy. Proximal shaft markers are located at 95 and 105 cm to aid in gauging catheter position relative to the tip of a brachial or femoral guiding catheter, respectively. The triloped GALILEO III centering catheter is provided with a balloon diameter of 2.5, 3.0, and 3.5 mm and balloon lengths of 32 and 52 mm. (Balloon length is defined as the distance between radiopaque balloon markers and does not include balloon tapers that extend beyond these markers). The MLD determines the appropriate centering catheter balloon diameter to use in the artery segment being treated (see Table 5). The lesion length determines the appropriate centering catheter length to use (see Table 6).

Delivery Device. The delivery device or the SDU has three main components: the head, base, and cartridge.

The front of the SDU head (Fig. 7) includes the touch screen monitor, status indicator lights, and housing for the cartridge. It also contains the manual retract wheel, the cartridge key port, the catheter key port and catheter eject button, and the red STOP button. On the back of the SDU head are the touch screen tilt lever, the swivel handle, and the system key port. The SDU head houses two motor drives—a primary motor and a battery-operated emergency retract motor. The emergency-retract motor works automatically if the primary motor fails to retract the active wire.

The SDU base provides a stable foundation for the SDU head and allows the unit to be transported easily.



Figure 6. (a) Galileo first generation spiral centering catheter (Guidant Corporation, Santa Clara, CA) is shown inside a 3 mm diameter curved lumen, balloon is inflated to 4 atm with saline to provide optimal source centering and distal blood perfusion (Courtesy of Guidant Corporation—GALIELO system is no longer manufactured or for sale.) (b) Cross-section of a Galileo second generation trilobed centering catheter (Guidant Corporation, Santa Clara, CA) is shown. Source lumen is central and the three lobes are inflated to 4 atm with saline to provide optimal source centering and distal blood perfusion. Note guide wire lumen inside one of the lobes. (Courtesy of Guidant Corporation—GALIELO system is no longer manufactured or for sale.)

Table 5. Balloon Diameter Selection for the Guidant Galileo Centering Catheter as a Function of the Measured MLD

Balloon Diameter, mm	MLD, mm
2.5	2.25–2.75
3.0	2.75–3.25
3.5	3.25–3.7

Table 6. Balloon and Equivalent Source Length Selection

Balloon Length, mm	Injured Arterial Length, mm	Equivalent Source Length, mm
32	≤ 32	40
52	33–52	60

Components of the base include the head release, the handle bar, the emergency compartment, the wheels and wheel locks, and the power cord port. The emergency compartment contains the equipment necessary to handle an emergency, including the emergency safe, the emergency wire cutter, and the emergency tongs.

The cartridge, which is inserted into the SDU head, contains the active (^{32}P source) wire, the dummy wire, and the operating software. It also contains the catheter key port, the tungsten safe, which shields the active wire when not in use, and the wire drive mechanisms. Figure 8 is an example of the GALILEO software screen of the countdown clock.


Active Wire Position

Current Position

1 OF 2

Seconds Remaining

58

Guidant Activity: 252.9 mCi

Days Remaining: 52.3

2002/04/24

13:41:00

Figure 8. A screen shot of the Galileo software of the countdown clock for a treatment with two-source positions using the automatic source positioning system. (Courtesy of Guidant Corporation—GALIELO system is no longer manufactured or for sale.)

Dosimetry. Based on the measured minimal lumen diameter and lesion length via fluoroscopy, online QCA, or IVUS, a proper centering balloon size is chosen. Also the lumen diameter of the nondiseased vessel is measured immediately proximal and immediately distal to the treatment area. The average of these two diameters is the RLD. The GALILEO prescription point for radiation delivery is 1 mm beyond the RLD. The SDU automatically calculates the dwell time required to deliver the prescribed dose of radiation (20 Gy) at the prescription point. The GALILEO



Figure 7. A front view of the Galileo source delivery system. It includes the Touch Screen Monitor, Status Indicator Lights, and housing for the Cartridge. It also contains the Manual Retract Wheel, the Cartridge Key Port, the Catheter Key Port and Catheter Eject Button, and the red STOP Button. (Courtesy of Guidant Corporation–GALIELO system is no longer manufactured or for sale.)


47 mm injured length
52 mm catheter (marker to marker)
therapeutic dose length
InActive wire position
20 mm source wire in 3rd position
20 mm source wire in 2nd position
20 mm source wire in 1st position
4 mm margin
Added margin
Added margin
4 mm margin
60 mm equivalent source length

Figure 9. An example of 60 mm equivalent source length resulting from stepping twice a 20 mm ^{32}P source to treat a 47 mm lesion. Note the added margin of 2.5 mm to the minimal margin of 4 mm to provide adequate radiation coverage.

SDU automatically steps the 20 mm ^{32}P source from most distal position to the most proximal position to yield an equivalent source length sufficient to cover the injured length with a minimal margin of 4 mm (Table 6). Equivalent source length (ESL) is defined as the total source length that will be result by stepping the 20 mm active source in tandem, either in two dwell positions (40 mm equivalent source length) or in three dwell positions (60 mm equivalent source length). Figure 9 is an example of 60 mm ESL to treat a 47 mm lesion, note the added margin of 2.5 mm to the minimal margin of 4mm to provide adequate radiation coverage.

DESIGN CONSIDERATION FOR IVB DEVICES AND DOSIMETRY

For beta emitters ($^{90}Sr/^{90}Y$, ^{32}P) used currently in intravascular brachytherapy, the prescribed dose is greatly influenced by several perturbation factors. These perturbation factors are divided into two categories; the first is *applicator* dependent and the second is *patient anatomy* dependent. Important applicator perturbation factors include the placement of a guidewire during irradiation, the source lumen eccentricity within the applicator and centering capability with the vessel lumen, use of contrast, X-ray markers, and source stepping precision (if injured lengths longer than the source radioactive length are treated). Patient perturbation factors include vessel anatomy (size, curvature, and cross-section eccentricity), plaque morphology (composition, density, and spatial distribution), and stent type. High energy gamma emitters like) ^{192}Ir (J&J Checkmate system) are influenced by such factors as well, but with almost negligible magnitudes (22), hence the next discussion will focus on the does distributions perturbation of the beta sources only.

Applicator Dependent Perturbations

The applicator dependent factors discussed in this report are specific for two commercially available IVB beta source systems, that is, Novoste ($^{90}Sr/^{90}Y$) and Guidant (^{32}P) systems. Five factors are discussed and considered most important, but are not inclusive, (*1*) guidewire, (*2*) source lumen eccentricity within the applicator and centering capability within the vessel lumen, (*3*) use of contrast, (*4*) X-ray markers, and (*5*) source stepping precision (manual vs. automatic).

Guide Wire Perturbation. The guide wire (GW) is used to navigate through the cardiovascular arteries during common interventional procedures, such as balloon angioplasty, stenting, and IVB. Commonly used guide wires are made of stainless steel and have a solid cross-section with diameter of 0.014 in. (0.36 mm). Several authors have reported on the dose perturbation due to the guide wire in IVB (23–25). Figure 6b depicts the cross-section of 3.0 mm GIII centring catheter with a 0.014 in. (0.36 mm) guide wire inside the upper lope. The distance from the center of the GW and source axis is not fixed in this design and the GW location can vary (shown at closest distance from the source lumen center). Also Fig. 10 depicts the location of the guide wire inside the 5 Fr BetaCath catheter. Shih et al. (24) provides a detailed study on dose perturbation as a function of the GW position relative to the source axis. A dose perturbation



Figure 10. Cross-section of the BetaCath 5 F delivery catheter. Note the location of the guide wore lumen relative to the source lumen. (Courtesy of Novoste Corporation.)

factor (DPF), defined as the ratio of the doses with and without the presence of a guidewire was introduced to quantify the effects.[100] The authors reported a DPF of up to 70% behind a GW for the beta sources. The dose reduction for the beta sources was found to be dependent on the guidewire location. For example, the dose reduction was 10% higher for a stainless steel guidewire located at 0.5 mm than that for the guidewire at 2 mm from the central axis of the source. The portion of the target volume affected (shadowed) dosimetrically by the guidewire was reduced when the guidewire was positioned farther away from the source. The shadow volume (in which the dose reduction occurs) can be reduced by up to 45% as the guidewire is moved away from the source axis from 0.5 to 2 mm.

Fluhs et al. (25) measured the GW [0.014 in. (0.3556 mm), stainless steel] perturbation using a plastic scintillator. The authors pointed that the insertion of a GW into the catheter close to the beta source causes a large angular asymmetry of the radiation emission. For a guide wire positioned eccentrically to the catheter the dose reduction is dominantly limited to a region of some 20° around the angle defined by catheter centerline and guide wire. At the catheter surface the maximal dose reduction in this region was found to be (30 ± 2%, DPF = 10%). At the typical dose prescription depth of 2 mm from the source axis the shielding effect decreased to (24 ± 2%) (or DPF = 76%). This value is remarkably larger than the dose reduction caused by any typical stent design.

Source Lumen Eccentricity. Sehgal et al. (26) reports on the dosimetric consequences of source centering (eccentricity) within the arterial lumen as one potentially important factor for the uniform delivery of dose to the arterial tissue. In this study, they have examined the effect of source centering on the resulting dose to the arterial wall from clinical intravascular brachytherapy sources containing ^{32}P and ^{90}Sr/^{90}Y. Monte Carlo simulations using the MCNP code (described in Advanced Topics section below) were performed for these catheter-based sources with offsets of 0.5 and 1 mm from the center of the arterial lumen in homogenous water medium as well as in the presence of residual plaque. Three different positions were modeled and the resulting dose values were analyzed to assess their impact on the resulting dose distribution. The results are shown in Table 7. The debate on the importance of centering of beta emitters used in IVB to treat native coronary vessels has been extensively published (27).

Contrast Perturbation. Contrast agents with high atomic number materials are usually injected into blood vessels to help in the determination of lesion location and to verify source placement during the IVB procedure (small fraction of the entire dwell time). Common contrast agents like Omnipaque and Hypaque are discussed. Omnipaque contains ~25% of iodine (in mass), and Hypaque contains ~23% of iodine. Iodine has an atomic number (Z) of 53. Nath et al. (22) discussed the perturbation factor of these contrast agents on ^{32}P and ^{90}Y IVB sources when the contrast is injected directly in the blood stream, however, this paper did not provide the average DPF over the treatment dwell time. Mourtada used a Monte Carlo simulation of the Galileo III centering catheter (Fig. 6b) to calculate the average dose reduction at 1 mm tissue depth if the three catheter lobes are filled with saline (as recommended by the product instruction for use) and 50 : 50 Omnipaque contrast. The results are reported in Table 8. The simulations were done for the three different sizes of the GALILEO III centering balloon.

Table 7. Results Are Reported at a Radial Distance of 2 mm from the Coronary Artery Lumen Center[a]

Offset from Center, mm	^{32}P, %	^{90}Sr/^{90}Y, %
0.5	−40 to +70	−30 to +50
1.0	−65 to +185	−50 to +140

[a] Data is from Ref. 26.

Table 8. Average DPF at 1 mm into the Vessel Wall when the Galileo III Centering Catheter is Filled with 50 : 50 Omnipaque Contrast Agent[a]

Balloon diameter, mm	DPF, %
2.5	−2.9
3.0	−4.8
3.5	−7.6

[a] The contrast remains in the balloon for the entire ^{32}P irradiation dwell time. Data calculated by Mourtada using MCNP Monte Carlo code (unpublished data).

X-Ray Markers Perturbation. The GALILEO III centering catheter has distal and proximal X-ray markers made of 90% Pt and 10% Ir (effective density is 21.6 g cm^{-3}). The X-ray markers are 0.635 mm long and the inner and outer diameter are 0.394 and 0.432 mm, respectively. The GALILEO 20 mm source first position inside the GIII centering catheter is positioned 4 mm beyond the proximal edge of the distal X-ray marker to provide adequate margins. Figure 11a depicts the 20 mm source wire (red) and distal X-ray marker (gold). Using the Monte Carlo simulation MCNP, the dose distribution in water around a 20 mm ^{32}P source was calculated with and without the distal X-ray marker. Figure 11b depicts the two-dimensional (2D) isodose map with the distal X-ray marker in place. As expected due to scattering, the X-ray marker perturbation is reduced quickly as a function of depth. For a 3.0 mm diameter vessel example, the intimal surface maximum DPF is 23% and at the prescription depth of 1 mm into the vessel wall, the maximum DPF is 15%. The effect of the radiopaque marker in the BetaCath ^{90}Sr90/^{90}Y system has not been reported, but it is expected to be minimal since the catheter markers are along the side of the radioactive seed train.

Source Stepping. Lesions that are longer than available IVB sources require stepping the source (i.e., tandem positioned) from mostly distal to most proximal lesion segment to provide adequate radiation coverage. First-generation clinical beta-source systems have gained FDA approval for clinical indication for focal lesions (< 22 mm) (12,28). For injured lesions > 22 mm, but ≤ 47 mm, the manual tandem positioning (MTP) technique was investi-



Figure 11. (a) Schematic of the distal X-ray marker of the Galileo second generation centering catheter (GIII) relative to nominal position of the 20 mm ^{32}P source inside the GIII catheter. (b) Energy deposited per unit volume in water (unit: MeV cm^{-3}) calculated using MNCNPX Monte Carlo code for the geometry shown in Fig. 11a. The origin of the coordinate system is located at the bisector of the 20 mm ^{32}P source. The proximal edge of the distal X-ray marker (gold) is located at 6 mm from the source origin. Note the large dose perturbation at closer depth (< 1 mm).

gated in the INHIBIT clinical trial using the 27 mm ^{32}P source (12). From the INHIBIT data analysis; for the 56 patients treated who had a tandem-positioning procedure (and the core lab had reported the size of gap or overlap), 44% had no gap or overlap. But, 19 and 11% of the patients had a 1 (32% increase in dose at junction) and 2 mm (56% increase in dose at junction) overlap respectively. Only one patient (1.9%) had a 1 mm gap (32% decrease in dose at junction). Hence, a 2 mm overlap and 1 mm gap are defined as the upper limits allowed for tandem positioning. Crocker et al. (29) also investigated the MTP procedure with 30 and 40 mm ^{90}Sr/^{90}Y source trains, and concluded from their data that the MTP technique was safe from both a dosimetric and a clinical point of view. However, Coen et al. (30) published a retrospective evaluation of the accuracy of manual multisegmental irradiation with 30 and 40 mm ^{90}Sr/^{90}Y source trains for irradiation of long (re)stenotic lesions in coronary arteries, following PTCA. They concluded that the positioning inaccuracy of MTP caused unacceptable dose inhomogeneities at the junction between source positions, and the procedure was not recommended. Coen et al. (30) suggested using longer line sources or source trains, or preferably an automated stepping source to insure reliable and safer technique for treatment of long lesions. Table 9 lists the dose perturbation at stepping junction due to an overlap or gap at the reference depth of 2 mm in water for GALILEO ^{32}P and Novoste ^{90}Sr/^{90}Y sources.

To reduce MTP dosimetric errors and to allow adequate coverage of radiation to longer injured lengths using the same source, an afterloader can be used to automatically step the radiation source to yield a longer equivalent source length. The only IVB system capable of this is the second generation GALILEO automated stepping system using a 20 mm ^{32}P source wire (33).

Patient Anatomy Dependent Perturbations

Patient perturbation factors discussed in this article include (*1*) vessel geometry (size, curvature, tapering,

Table 9. Dose Perturbation at Junction Due to an Overlap or Gap at the Reference Depth of 2 mm in Water for GALILEO ^{32}P and Novoste ^{90}Sr/^{90}Y Sources

Size of Overlap or Gap, mm	^{32}P^a, %	^{90}Sr/^{90}Y^b, %
0	0	0
0.5	±17	
1	±32	±23
2	±56	±44
3	±75	±60
5	±91	±80

[a] Guidant Corporation Data to Ref. 31.

[b] See Ref. 32.



Figure 12. A typical vessel cross-section is eccentric, and the vessel center does not necessarily lie on the lumen center.

and cross-sectional eccentricity); (*2*) plaque morphology (composition, density, and spatial distribution); (*3*) stenting.

Vessel Geometry Perturbation. The native coronary vessel diameter has a range from 2 to 4 mm. Due to plaque formation and tapering, the lumen diameter is a variable. It is expected that the dose perturbation factor to be worse for larger vessels, especially for the BetaCath IVB system whose dose does not have active centering. Also, a typical vessel cross-section is eccentric, and the vessel center does not necessarily lie on the lumen center (Fig. 12). As pointed by Kaluza et al. (27) in reality, plaque thickness can vary from 0.1 to 2.3 mm. The average eccentricity index was 6.38 ± 5.95 in the 59 PREVENT patients. The intimal hyperplasia of in-stent restenosis complicates the vessel cross-section. Mehran et al. (6) developed an angiographic classification of in-stent restenosis mainly under two categories: focal and diffused (6).

Another important vessel geometry factor is curvature. Xu et al. (34) studied the effect of curvature on ^{32}P beta dosimetry. As expected, the curvature causes an increase in dose in the inner surface (concave side) of the coronary vessel and a decrease in dose in the outer surface (convex side). For a maximum theoretical bend of 180°, the dose increases by as much as 20% along the inner radial distance, but decreased by as much as 20% along the outer radial distance compared to the dose along a straight wire. The authors concluded that for curvatures normally encountered in a clinical situation, the dose rate was changed by $< 5\%$.

Plaque Morphology Perturbation. The artery mostly consists of normal healthy tissue, but may also contain plaque, whose density may be unknown. Plaque is a material that develops inside the artery over time and is considered responsible for blockage of the artery. Plaque may range widely in histologic structure, density, and chemical composition. Density is expected to depend on the plaque's collagenous matrix and degree of calcification. Rahdert et al. (35) measured the density and calcium concentration in 13 cadaveric plaque specimens. This study concluded that based on the plaque calcification, the density range is between 1.25 and 1.5 $g \cdot cm^{-3}$.

Table 10. DPF Values at 2 mm Radial Distance for ^{32}P and ^{90}Sr/^{90}Y Sources[a]

Plaque Density, $g\ cm^{-3}$	DPF, ^{32}P	DPF, ^{90}Sr/^{90}Y
No plaque	1.0	1.0
1.45	0.93	0.97
1.55	0.91	0.96
3.10	0.70	0.83

[a] The plaque layer has a thick-ness of 0.2 mm for all the different cases. The relative error is within 5% for the given dose rate values. (See Ref. 26).

Several studies on dose perturbation due to plaque have been reported in the literature for catheter-based beta sources (36–38). Nath et al. (36) assumed a 1 mm thick plaque with cortical bone density of 1.84 $g \cdot cm^{-3}$ and 27% Ca composition. Both values are relatively higher than those reported by Rahdert et al. (35). For this extreme condition, however, Nath et al. (36) reported ~ 0.8 mm reduction in penetration for ^{90}Sr/^{90}Y and ^{32}P beta sources when the calcified plaque was located next to the source, and by ~ 0.9 mm when the plaque was located 1 mm away from the source.

Li et al. reported $\sim 30\%$ reduction due to plaque for the Novoste ^{90}Sr/^{90}Y source (37). The modeled calcified plaque density range in this study was 1.2–1.60 $g \cdot cm^{-3}$ with a nominal density of 1.45 $g \cdot cm^{-3}$ as reported for B100 bone equivalent by ICRU Report 26 (39). Li et al. (37) calculated the DPF as a function of the radial distance from the source axis. Sehgal et al. (26) reported on the perturbation due to concentric plaque with constant thickness of 0.2 mm and three different densities as shown in Table 10 for both the GALILEO ^{32}P and Novoste ^{90}Sr/^{90}Y sources. Comparing with Li et al. (37) the 0.2 mm thick plaque with 1.45 $g \cdot cm^{-3}$ DPF results are similar.

Stent Perturbation. Even though a stent is not part of the actual vessel anatomy, it is assumed that an expanded stent is predislodged into the intima and surrounded by new tissue growth as a result of in-stent neointimal hyperplasia. Hence, the stent becomes part of the diseased vessel segment. In a few instances, a vessel could receive a second or even a third stent, as part of the intervention of a recurrent in-stent restenosis.

For all stent types, a similar behavior can be observed. At a distance of 0.5 mm and more the typical overall dose reduction does not exceed a value of 5–15% (40). In the close vicinity of the stent struts, an increased dose reduction effect reaches up to some 30–40%. The large dose reduction directly behind the stent struts are caused by the absorption effect that is not compensated by scattering contributions from regions outside of the shielded area until a depth of ~ 0.5 mm from the strut surface (41).

Recently, a new stent made of cobalt chromium L-605 alloy (CoCr, $\rho = 9.22\ g \cdot cm^{3}$) (MULTI-LINK VISION) was introduced as an alternative to the commonly used 316L stainless steel stent design (SS, $\rho = 7.87\ g \cdot cm^{-3}$) (MULTI-LINK PENTA). Mourtada and Horton (42) used the Monte



Figure 13. A 3 mm diameter stainless steel stent DPF along the source axis ($x = 0$ is the coordinate system origin at source bisector). The parameter $r = 1.55$ mm is the radial distance from the source axis and is the centroid of the scoring bin directly behind the stent (score bin radial thickness is 0.1 mm). The parameter $r = 2.55$ mm is the centroid of the scoring bin at the 2.5 mm prescription point. Data calculated using MCNPX Monte Carlo code. (Reference 42 with permission from Medical Physics journal.)

Carlo code MCNPX to compare the dose distribution for the ^{32}P GALILEO source in CoCr and SS 8 mm stent models. The DPF, defined as the ratio of the dose in water with the presence of a stent to the dose without a stent, was used to compare results. Both stent designs were virtually expanded to diameters of 2.0, 3.0, and 4.0 mm using finite element models (ABQUS Inc., Pawtucket, RI). The complicated strut shapes of both the CoCr and SS stents were simplified using circular rings with an effective width to yield a metal/tissue ratio identical to that of the actual stents. The mean DPF at a 1 mm tissue depth, over the entire stented length of 8 mm, was 0.935 for the CoCr stent and 0.911 for the SS stent. The mean DPF at the intima (0.05 mm radial distance from the strut outer surface), over the entire stented length of 8 mm, was 0.950 for CoCr, and 0.926 for SS. The maximum DPFs directly behind the CoCr and SS struts were 0.689 and 0.644, respectively. Figures 13 and 14 depict the dose profiles behind the stainless steel stent as an example. The authors concluded that although the CoCr stent has a higher effective atomic number and greater density than the SS stent, the DPFs for the two stents are similar because the metal/tissue ratio and strut thickness of the CoCr stent are lower than those of the SS stent.

ADVANCED TOPICS

Figure 15 is the general dosimetry characterization paradigm of brachytherapy sources. This requires three important steps including the experimental measurement of the dose rate (cGy$^{-1}\cdot$s) as a function of distance from the source using a calibrated dosimeter, a measurement of the source contained activity (SI unit is the Becquerel = Bq = 1 decay s^{-1}). The normalized measure dose rate to the measured contained activity can then be compared to a theoretical calculation such as a Monte Carlo simulation, which is inherently has dose rate units per particle emitted, that is, contained activity. This section will discuss briefly an example of each component that is important in the IVB dosimetry paradigm.



Figure 14. Dose perturbation factor as a function of the radial distance from source axis in water and through a strut located 1.5 mm from the source axis (expanded inside a 3.0 mm vessel model). (Reference 42 with permission from Medical Physics journal.)

Theoretical Dosimetry: Monte Carlo Simulations

The Monte Carlo technique used for IVB dosimetry is considered the most accurate theoretical tool, particularly suited in handling the complex interactions of the emitted beta particles with the surrounding medium. Fox has published a review of IVB (43), including a rather thorough review of the theoretical dosimetry applied to these sources. Detailed reviews and discussion of the Monte Carlo method can also be found in the literature (44–46). Monte Carlo codes utilized for IVB dosimetry include CYLTRAN from the Integrated Tiger Series (ITS version 3.0, Sandia National Laboratory, Albuquerque, NM), the MCNP series (MCNP4C and MCNPX, Los Alamos



Figure 15. A general dosimetry characterization paradigm of brachytherapy sources.

National Laboratory, Los Alamos, NM), the EGS series (EGS4 Stanford Linear Accelerator Center, Stanford, CA, and EGSnrc National Research Council of Canada, Ottawa, Ontario, Canada), and PENELOPE (University of Barcelona, Barcelona, Catalonia, Spain).

Theoretical modeling is being increasingly used to supplement measurements in IVB. The Monte Carlo method, for example, is based on the idea that if all materials and dimensions of a problem, and all the probabilities of the various possible radiation interactions are known, then emitted particles can be tracked and scored as they are transported from the source through the media of the problem. A random number generator is used to select emitting source element location, emitted particle energy and direction, and results of various interactions and secondary radiations as the particle is tracked to either absorption or out of the problem boundaries. Obviously, the more "histories" (emitted particles) are tracked, the more accurate is the resulting calculation. With the advent of faster and faster computers, Monte Carlo calculations are becoming more and more attractive for determining dose distributions for brachytherapy sources in complex geometries. Often, the combination of a Monte Carlo calculation, which yields dose rate per unit contained activity, and a contained activity measurement, will give better accuracy than a dosimetric measurement. An excellent review of the Monte Carlo method has recently been published (44).

MC simulations of electron transport, for example, beta-particle transport, are usually different from those used in photon or neutron transport, for which the simulated radiation history is followed individually based on conventional methods since uncharged radiation interactions are characterized by relatively infrequent isolated collisions. For example, in photon transport, the distance to the next photon interaction is sampled from the attenuation coefficient distribution; and the change in attenuation coefficient as the photon crosses material boundaries is modeled. The type of interaction is sampled from the appropriate relative probabilities. The history of each photon is continued from collision to collision until the photon either is absorbed, escapes the problem boundary, or its energy falls below a chosen cutoff threshold at which the remaining energy of the photon is locally deposited.

For high energy electrons, such a detailed history is not practical for energies > 100 keV, because many individual elastic and inelastic Coulomb collisions per history are generated through the media resulting in very long computational time. Instead, a "condensed history" is used, where the electron trajectories are divided into many path segments (47). For each path segment, the net angular deflection and the net energy loss are sampled from relevant multiple-scattering distributions. The choice of the step size is important for accuracy and is chosen with conflicting requirements. On the one hand, the steps should be short enough that (*1*) most of the electron history steps are completely inside the boundary of a predefined surface, so that the use of multiple-scattering theories of unbounded media is valid; (*2*) the energy loss is, on average, small within a step; and (*3*) the net angular deflection is, on average, small so that the path within the step is approximated by a straight line. On the other hand, the step size should be large enough to contain a sufficient number of collisions per step to justify the use of the multiple-scattering theories and to limit the number of steps per history to reduce computing time. Further discussion can be found in the literature (45).

Experimental Dosimetry: Radiochromic Film Measurements

Both MD-55 and HD-810 radiochromic dye films (RCF) (GAFChromic type, Nuclear Associates, Carle Place, NY) are widely used in IVB dose-field measurement due to their superior spatial resolution. Also, RCF is used instead of other types of films mainly for its linear dose response. A full description of both film types is reported by AAPM Task Group 55 (48) For beta field measurements, it is recommended that the RCF dosimeter be calibrated using the same ^{90}Sr/^{90}Y ophthalmic applicator (New England Nuclear S/N 0258) calibrated at the National Institute of Standards and Technology (NIST), Gaithersburg, Maryland (20). Polystyrene or other tissue-equivalent materials are used to fabricate high precision blocks for the film measurements. Each block has a hole with a diameter slightly larger than the source diameter to reduce positional error (in IVB 0.1 mm could translate to 13% error in the measured dose rate). Several blocks are made with nominal depths (distance from center of hole to block surface) ranging from 0.5 to 5 mm. Actual depths must be verified using a traveling microscope or an optical comparator. At each of these depths, several radiochromic films should be exposed for a range of times to gain a good image of the radiation field. Digitization of film is typically done with a high resolution 2 scanning densitometer (Pharmacia LKB) using a 633 nm laser (HeNe) with a 100 μm diameter spot size and a 40 μm minimum step size. Alternatively, scanning is done using a high resolution (242 × 375) CCD densitometer (CCD100, Photoelectron, Lexington, MA) with a 665 nm LED array and a 160 × 200 μm pixel size. To account for optical-density growth as a function of time after exposure, film readout should be done 72 h postirradiation for both the calibration and experimental films. The net optical density measurements of each film were converted into a 2D dose map as shown in Fig. 16. Estimated dose uncertainties for radiochromic film are ± 15.6 % ($k = 2$); the individual components of this uncertainty are shown in Table 11.

Other radiation dosimeters mostly lack the spatial resolution of submillimeters required in IVB. However, recently Amin et al. (49) proposed using a polyacrylamide gel (PAG) dosimeter and a high field 4.7 T MRI scanner for IVB. The get/scanner final in-plane resolution of 0.4 × 0.2 mm is approaching the film resolution, but not quite. The authors confirmed that both absorbed dose and dose distributions for high gradient vascular brachytherapy sources can be measured using PAG, but the disadvantages of gel manufacture and the need for access to a high resolution scanner suggests that the use of radiochromic film is the method of choice (49).

Determination of Contained Activity. The activity content of this wire must be known in order to relate the measurements and calculations of the absorbed-dose spatial



Figure 16. A 2D HD810 radiochromic film image dose (Gy) distribution for a ^{32}P source, measured in a plane parallel to the source's longitudinal axis at 1.97 mm radial distance from the source axis in the polystyrene block.



Figure 17. Measured data (Film and EC: extrapolation chamber) depth dose curve plotted along with Monte Carlo estimates from MCNP4C and PENELOPE. The error bars estimate the 95% confidence interval. All data are measured or calculated in polystyrene. (Reference 21 with permission from Medical Physics journal.)

distribution. For the 27 mm ^{32}P source design, Mourtada et al. briefly described the determination of the absolute contained activity from the original work of Collé (50). The contained activity was then related to a calibration factor for the NIST Capintec. The CRC-12 ionization chamber (51). Similar work was done on the Novoste ^{90}S/^{90}Y seed and other beta sources used for IVB to establish radioactivity standards by NIST, Gaithersburg, MA (52,53).

For example, Fig. 17 is the Galileo 20 mm ^{32}P source wire measured radiochromic film (MD55 and HD810) depth dose curve plotted along with Monte Carlo estimates from MCNP4C and PENELOPE. The error bars estimate the 95% confidence interval. All data are measured or calculated in polystyrene (21).

Beyond IVB Treatments of Heart Disease, Other Applications, and Future Roles

In the United States, there are ~8–12 million patients affected with peripheral vascular disease. An estimated 600,000 interventional procedures are performed each year, including percutaneous transluminal angioplasty (PTA), bypass surgery, and amputation. Percutaneous transluminal angioplasty restenosis rates are high with a success rate of < 23% at 6 months follow-up. Intravascular brachytherapy has been investigated to reduce restenosis in the superficial femoral and popliteal arteries after PTA. The main IVB clinical trial for peripheral vessel is the Peripheral Artery Radiation Investigation Study (PARIS) using the Nucletron Ir-192 HDR source (mHDR v2). The PARIS study used the Nucletron micro-Selectron high dose rate (HDR) afterloader and the Guidant PARIS centering catheter (10–20 cm long and 4–8 mm diameter) (54). More recently, the MOBILE clinical trial a ^{90}Sr/^{90}Y source and the Corona gas-filled centering is being investigated (Novoste Corporation) (55).

Other possible applications of IVB include treatment of recurrent narrowing of the arteriovenous (AV) dialysis graft (56), renal artery stenosis, transjugular intrahepatic porto-systemic (TIPS) stenosis, carotid artery (57), and subclavian vein stenosis. Further application of IVB might be for treatment of atrial fibrillation, a most common cardiac arrhythmia. It is proposed that IVB radiation dose can electrically isolate ectopic foci located mostly in the adventitia of the pulmonary vein (PV), which are responsible for atrial fibrillation episodes (58). The IVB approach might alleviate undesirable side effects (PV stenosis due to heating) of rf ablation; a commonly used treatment modality to ablate myocardial tissue.

Intravascular Brachytherapy in the Drug-Eluting Stent Era

The recent introduction of drug-eluting stents (DES) in the interventional cardiology arena has a tremendous impact on the IVB practice. By incorporating antiproliferative agents onto the surface of the stent, neointimal hyperplasia

Table 11. Estimated Relative Uncertainties of the Radiochromic-Film Dose Interpretations per Measured Unit Activity

Uncertainty Component	Relative Standard Uncertainty, %
Calibration of the NIST standard ^{90}Sr/^{90}Y calibration source	6
Response of the film exposed to the calibration source	3
Response of the films exposed to the source under test	3
Activity calibration	2.6
Combined standard uncertainty	7.8
Expanded uncertainty ($k = 2$)	15.6

occurring within the stent is markedly reduced. Stents coated with agents, like Sirolimus, Paclitaxel, Tacrolimus, Everolimus, and so on, when compared to bare-metal stents, had shown remarkable reduction in binary restenosis and target vessel revascularization (TVR) rates in several clinical trials (31,59).

As discussed earlier in this article, IVB has demonstrated its safety and efficacy in limiting recurrence of in-stent restenosis with positive long-term follow-up outcome. However, the utility of IVB is being rethought in relation to its use after the placement of drug eluting stents. It is expected that the role of IVB will decrease primarily due to the simplicity of placement of drug eluting stents and the relative complexity of performing intravascular brachytherapy. The published pivotal clinical restenosis rates from both the Paclitaxel (TAXUS) (32) and Sirolimus (RAVEL, SIRIUS) drug eluting stents suggests that the need to perform an IVB will be in < 1 in 20 patients (60–62). Recently reported registry data from Europe and the United States demonstrates similar efficacy of DES to that of IVB for treatment of in-stent restenosis (63,64). However, DES technology still has to go through further investigations in more complex lesions and higher risk patients in the general population to appreciate its full potential. Other agents with potential benefits like Statins, local gene therapy, and further innovations in polymer technology (biodegradable polymers, multiple-drug release polymers) are in under evaluation (31).

DEFINITION OF TERMS

MACE: Major Adverse Cardiac Events, a composite of death, MI, target, or repeat lesion revascularization.

Angiographic Binary Restenosis: Stenosis of 50% or more of the luminal diameter.

TLR and TVR: Target Lesion and Vessel Revascularization: Describes a rate measuring how many stented lesions had to be retreated, due to clinically driven restenosis, given a specific time period.

MLD: Minimal lumen diameter, the smallest diameter of an artery in a specified segment.

RLD: Reference lumen diameter, the average of two diameters, the lumen diameter of the nondiseased vessel immediately proximal and distal to the target treatment area.

Lumen Diameter: The inner diameter of an artery in a specified segment.

Neointimal Hyperplasia: Wound-healing response to arterial injury that leads to restenosis.

Late Loss: A cardiology term referring to the angiographic measurement of neointimal hyperplasia. It's one of the most important indicators of long-term efficacy in coronary intervention.

Percutaneous Transluminal Coronary Angioplasty (PTCA): A method of treating blood vessel disorders that involves the use of a balloon catheter to enlarge the blood vessel and thereby improve blood flow.

Restenosis: Narrowing of a vessel dilated by angioplasty or other interventional procedure.

In-stent Restenosis (ISR): Narrowing of a vessel after a stent is in place; this may be acute due to a thrombus formation or late (few months) due to wound healing process (neointimal hyperplasia and remodeling).

BIBLIOGRAPHY

Cited References

1. Gruentzig AR. Seven years of coronary angioplasty. Z Kardiol 1984;73 (Suppl.) 2:159–160.
2. Dotter CT, Buschmann RW, Mckinney MK, Rosch J. Transluminal expandable nitinol coil stent grafting: Preliminary report. Radiology 1983;147:259–260.
3. Cragg A, et al. Nonsurgical placement of arterial endoprostheses: A new technique using nitinol wire. Radiology 1983;147: 261–263.
4. Schwartz RS, Homes DR. Restenosis and remodeling. In: Waksman R. editor. Vascular brachytherapy. Armonk, (NY): Futura Publishing Company; 1999.
5. Hall EJ, Miller RC, Brenner DJ. Radiobiological principles in intravascular irradiation. Cardiovasc Radiat Med 1999;1:42–47.
6. Mehran R, et al. Angiographic patterns of in-stent restenosis: Classification and implications for long-term outcome. Circulation 1999;100:1872–1878.
7. Fischman DL, et al. A randomized comparison of coronary-stent placement and balloon angioplasty in the treatment of coronary artery disease. Stent restenosis study investigators. N Engl J Med 1994;331:496–501.
8. Serruys PW, et al. A comparison of balloon-expandable-stent implantation with balloon angioplasty in patients with coronary artery disease. Benestent study group. N Engl J Med 1994;331:489–495.
9. Condado JA, et al. Long-term angiographic and clinical outcome after percutaneous transluminal coronary angioplasty and intracoronary radiation therapy in humans. Circulation 1997;96:727–732.
10. Leon MB, et al. Localized intracoronary gamma-radiation therapy to inhibit the recurrence of restenosis after stenting. N Engl J Med 2001;344:250–256.
11. Popma JJ, et al. Randomized trial of ^{90}Sr/^{90}Y beta-radiation versus placebo control for treatment of in-stent restenosis. Circulation 2002;106:1090–1096.
12. Waksman R, et al. Use of localised intracoronary beta radiation in treatment of in-stent restenosis: The inhibit randomised controlled trial. Lancet 2002;359:551–557.
13. Balter S. A health physics perspective. In: WR, editor. Vascular brachytherapy. New York: Futura Publishing Company; 1999.
14. Barish R. Radiation safety considerations for intravascular brachytherapy. In: Balter S, Chan RC, Shope TB, editors. Intravascular brachytherapy and fluoroscopically guided interventions. Madison (WI): Medical Physics Publishing; 2002.
15. Waksman R. Intravascular gamma radiation for in-stent restenosis in saphenous-vein bypass grafts. N Engl J Med 2002;346:1194–1199.
16. Jani S, Massullo V, Tripuraneni P, Teristein P. The ^{192}Ir radioactive seed ribbon. In: Waksman R, Serruys P, editors. Handbook of vascular brachytherapy. London: Martin Dunitz Ltd; 2000.
17. Chiu-Tsao ST, et al. Verification of ^{192}Ir near source dosimetry using gafchromic film. Med Phys 2004;31:201–207.
18. Roa DE, et al. Dosimetric characteristics of the novoste beta-cath ^{90}Sr/Y source trains at submillimeter distances. Med Phys 2004;31:1269–1276.

19. Soares CG, Halpern DG, Wang C-K. Calibration and characterization of beta-particle sources for intravascular brachytherapy. Med Phys 1998;25:339–346.
20. Mourtada FA, Soares CG, Seltzer SM, Lott SH. Dosimetry characterization of ^{32}P catheter-based vascular brachytherapy source wire. Med Phys 2000;27:1770–1776.
21. Mourtada F, et al. Dosimetry characterization of a ^{32}P source wire used for intravascular brachytherapy with automated stepping. Med Phys 2003;30:959–971.
22. Nath R, Yue N, Weinberger J. Dose perturbations by high atomic number materials in intravascular brachytherapy. Cardiovasc Radiat Med 1999;1:144–153.
23. Li XA, Shih R. Dose effects of guide wires for catheter-based intravascular brachytherapy. Int J Radiat Oncol Biol Phys 2001;51:1103–1110.
24. Shih R, Hsu WL, Li XA. Dose effect of guidewire position in intravascular brachytherapy. Phys Med Biol 2002;47:1733–1740.
25. Fluhs D, et al. The influence of guiding equipment and stents on the beta dose distribution in the brachytherapy of in-stent restenosis. Cardiovasc Radiat Med 2001;2:241–245.
26. Sehgal V, Li Z, Palta JR, Bolch WE. Dosimetric effect of source centering and residual plaque for beta-emitting catheter based intravascular brachytherapy sources. Med Phys 2001;28:2162–2171.
27. Kaluza GL, et al. Targeting the adventitia with intracoronary beta-radiation: Comparison of two dose prescriptions and the role of centering coronary arteries. Int J Radiat Oncol Biol Phys 2002;52:184–191.
28. Suntharalingam M, et al. Clinical and angiographic outcomes after use of 90strontium/90yttrium beta radiation for the treatment of in-stent restenosis: Results from the stents and radiation therapy 40 (Start 40) registry. Int J Radiat Oncol Biol Phys 2002;52:1075–1082.
29. Crocker I, et al. Treatment of long, diffuse, in-stent restenotic lesions with beta radiation using strontium 90 and sequential positioning “pullback” technique: Procedural details and clinical outcomes. J Invasive Cardiol 2001;13:782–787.
30. Coen VL. Inaccuracy in manual multisegmental irradiation in coronary arteries. Radiother Oncol 2002;63:89–95.
31. Fattori R, Piva T. Drug-eluting stents in vascular intervention. Lancet 2003;361:247–249.
32. Stone GW, et al. One-year clinical results with the slow-release, polymer-based, paclitaxel-eluting taxus stent: The taxus-IV trial. Circulation 2004;109:1942–1947.
33. Waksman R, et al. Beta radiation delivered via an automatic stepping device to inhibit recurrence of diffuse in-stent restenosis: Clinical and angiographic results of the multicenter galileo inhibit clinical study. Circulation (Suppl II) 2001;104:II–509.
34. Xu Z, et al. The investigation of ^{32}P wire for catheter-based endovascular irradiation. Med Phys 1997;24:1788–1792.
35. Rahdert DA, et al. Measurement of density and calcium in human atherosclerotic plaque and implications for arterial brachytherapy. Cardiovasc Radiat Med 1999;1:358–367.
36. Nath R, Yue N, Liu L. On the depth of penetration of photons and electrons for intravascular brachytherapy. Cardiovasc Radiat Med 1999;1:72–79.
37. Li XA, Wang R, Yu C, Suntharalingam M. Beta versus gamma for catheter-based intravascular brachytherapy: Dosimetric perspectives in the presence of metallic stents and calcified plaques. Int J Radiat Oncol Biol Phys 2000;46:1043–1049.
38. Hanefeld C, et al. Dosimetric measurements in isolated human coronary arteries: Comparison of commercially available iridium(192) with strontium/yttrium(90) emitters. Circulation 2002;105:2493–2496.
39. Icru Report 26. International Commission on Radiation Units and Measurements, Bethesda (MD); 1977.
40. Fan P, et al. Effect of stent on radiation dosimetry in an in-stent restenosis model. Cardiovasc Radiat Med 2000;2:18–25.
41. Amols HI, Trichter F, Weinberger J. Intracoronary radiation for prevention of restenosis: Dose perturbations caused by stents. Circulation 1998;98:2024–2029.
42. Mourtada F, Horton JL. Dose perturbation of a novel cobalt chromium coronary stent on ^{32}P intravascular brachytherapy: A monte carlo study. Med Phys 2005;32:268–274.
43. Fox RA. Intravascular brachytherapy of the coronary arteries. Phys Med Biol 2002;47:R1–30.
44. Seltzer SM. Monte Carlo modeling for intravascular brachytherapy sources. In: Shope TB, editor. Intravascular brachytherapy and fluoroscopically guided interventions. Madison (WI): Medical Physics Publishing; 2002.
45. Jenkins TM, Nelson WR, Rindi A, editors. Monte carlo transport of electrons and photons. New York: Plenum Press; 1988.
46. Icru Report 56. International Commission On Radiation Units and Measurements, Bethesda (MA); 1997.
47. Berger MJ. Monte carlo calculations of the penetration and diffusion of fast charged particles. Alder B, Fernabach S, Rotenberg M, editors. Methods in computational physics. New York: Academic Press; 1963.
48. Niroomand-Rad A, et al. Radiochromic film dosimetry: Recommendations of aapm radiation therapy committee task group 55. Med Phys 1998;25:2093–2115.
49. Amin MN, et al. A comparison of polyacrylamide gels and radiochromic film for source measurements in intravascular brachytherapy. Br J Radiol 2003;76:824–831.
50. Collé R. Chemical digestion and radionuclide assay of tini-encapsulated 32p intravascular brachytherapy sources. Appl Rad Isotopes 1999;50:811–833.
51. Colle R, Zimmerman BE, Soares CG, Coursey BM. Determination of a calibration factor for the nondestructive assay of guidant 32P brachytherapy sources. Appl Radiat Isotopes 1999;50:835–841.
52. Collé R. On the radioanalytical methods used to assay stainless-steel-encapsulated, ceramic-based ^{90}Sr/^{90}Y intravascular brachytherapy sources. Appl Radiat Isotopes 2000;52:1–18.
53. Colle R. Activity characterization of pure-beta-emitting brachytherapy sources. Appl Radiat Isotopes 2002;56:331–336.
54. Waksman R, et al. Intravascular radiation therapy after balloon angioplasty of narrowed femoropopliteal arteries to prevent restenosis: Results of the paris feasibility clinical trial. J Vasc Interv Rad 2001;12:915–921.
55. Wang R, Li XA, Lobdell J. Monte carlo dose characterization of a new 90sr/90y source with balloon for intravascular brachytherapy. Med Phys 2003;30:27–33.
56. Bloch P, Bonan R, Wallner P, Lobdell J. Dosimetry for an ^{90}Sr/^{90}Y source train used for intravascular radiation of a hemodialysis graft. Cardiovasc Rad Med 2003;4:90–94.
57. Chan AW, et al. Carotid brachytherapy for in-stent restenosis. Catheter Cardiovasc Interv 2003;58:86–92.
58. Saito T, Waki K, Becker AE. Left atrial myocardial extension onto pulmonary veins in humans: Anatomic observations relevant for atrial arrhythmias. J Cardiovasc Electrophysiol 2000;11:888–894.
59. Degertekin M, et al. Sirolimus-eluting stent for treatment of complex in-stent restenosis: The first clinical experience. J Am Coll Cardiol 2003;41:184–189.
60. Morice MC, et al. A randomized comparison of a sirolimus-eluting stent with a standard stent for coronary revascularization. N Engl J Med 2002;346:1773–1780.
61. Abizaid A, et al. Sirolimus-eluting stents inhibit neointimal hyperplasia in diabetic patients. Insights from the ravel trial. Eur Heart J 2004;25:107–112.

62. Serruys PW, et al. Intravascular ultrasound findings in the multicenter, randomized, double-blind ravel (randomized study with the sirolimus-eluting velocity balloon-expandable stent in the treatment of patients with de novo native coronary artery lesions) trial. Circulation 2002;106:798–803.
63. Bailey SR. Drug-eluting stents have made brachytherapy obsolete. Curr Opin Cardiol 2004;19:598–600.
64. Kaluza GL, Raizner AE. Brachytherapy for restenosis after stenting for coronary artery disease: Its role in the drug-eluting stent era. Curr Opin Cardiol 2004;19:601–607.

Reading List

Waksman R, Serruys P. Handbook of Vascular Bracdhytherapy. 2nd ed. London: Martin Dunitz Ltd; 2000.

Waksman R. Vascular Brachytherapy. 2nd ed. Armonk (NY): Futura Publishing Company; 1999.

Hall EJ. Radiobiology for the Radiologist. 5th ed. Philadelphia: J.B. Lippincott; 2000.

Kutryk MJ, Serruys PW. Coronary Stenting Current Perspective. London: Martin Dunitz Ltd; 1999.

Balter S, Chan RC, Shope TB. Intravascular Brachytherapy, Fluoroscopically Guided Interventions. Madison: Medical Physics Publishing; 2002.

Leon MB, Mintz GS. Interventional Vascular Product Guide. London: Martin Dunitz Ltd; 1999.

Attix FH. Introduction to Radiological Physics and Radiation Dosimetry. New York: John Wiley & Sons, Inc.; 1986.

See also BRACHYTHERAPY, HIGH DOSAGE RATE; CORONARY ANGIOPLASTY AND GUIDEWIRE DIAGNOSTICS.

BRAIN ELECTRICAL ACTIVITY.

See ELECTROENCEPHALOGRAPHY.

BURN WOUND COVERINGS.

See SKIN SUBSTITUTE FOR BURNS, BIOACTIVE.

BYPASS, CORONARY.

See VASCULAR GRAFT PROSTHESIS.

BYPASS, CARDIOPULMONARY.

See HEART-LUNG MACHINES.

ENCYCLOPEDIA OF

MEDICAL DEVICES AND INSTRUMENTATION

Second Edition

VOLUME 2

Capacitive Microsensors for Biomedical Applications – Drug Infusion Systems

ENCYCLOPEDIA OF MEDICAL DEVICES AND INSTRUMENTATION, SECOND EDITION

Editor-in-Chief
John G. Webster
University of Wisconsin–Madison

Editorial Board
David Beebe
University of Wisconsin–Madison

Jerry M. Calkins
University of Arizona College of Medicine

Michael R. Neuman
Michigan Technological University

Joon B. Park
University of Iowa

Edward S. Sternick
Tufts–New England Medical Center

Editorial Staff
Vice President, STM Books: **Janet Bailey**
Associate Publisher: **George J. Telecki**
Editorial Director: **Sean Pidgeon**
Director, Book Production and Manufacturing:
Camille P. Carter
Production Manager: **Shirley Thomas**
Illustration Manager: **Dean Gonzalez**
Senior Production Editor: **Kellsee Chu**
Editorial Program Coordinator: **Surlan Murrell**

ENCYCLOPEDIA OF

MEDICAL DEVICES AND INSTRUMENTATION

Second Edition

Volume 2

Capacitive Microsensors for Biomedical Applications – Drug Infusion Systems

Edited by

John G. Webster

University of Wisconsin–Madison

The *Encyclopedia of Medical Devices and Instrumentation* is available online at
http://www.mrw.interscience.wiley.com/emdi

WILEY-INTERSCIENCE

A John Wiley & Sons, Inc., Publication

Copyright © 2006 by John Wiley & Sons, Inc. All rights reserved.

Published by John Wiley & Sons, Inc., Hoboken, New Jersey

Published simultaneously in Canada

No part of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, scanning, or otherwise, except as permitted under Section 107 or 108 of the 1976 United States Copyright Act, without either the prior written permission of the Publisher, or authorization through payment of the appropriate per-copy fee to the Copyright Clearance Center, Inc., 222, Rosewood Drive, Danvers, MA 01923, (978) 750-8400, fax (978) 750-4470, or on the web at www.copyright.com. Requests to the Publisher for permission should be addressed to the Permissions Department, John Wiley & Sons, Inc., 111 River Street, Hoboken, NJ 07030, (201) 748-6011, fax (201) 748-6008, or online at http://www.wiley.com/go/permission.

Limit of Liability/Disclaimer of Warranty: While the publisher and author have used their best efforts in preparing this book, they make no representations or warrnaties with respect to the accuracy or completeness of the contents of this book and specifically disclaim any implied warranties of merchantability or fitness for a particular purpose. No warranty may be created or extended by sales representatives or written sales materials. The advice and strategies contained herein may not be suitable for your situation. You should consult with a professional where appropriate. Neither the publisher nor author shall be liable for any loss of profit or any other commercial damages, including but not limited to special, incidental, consequential, or other damages.

For general information on our other products and services or for technical support, please contact our Customer Care Department within the United States at (800) 762-2974, outside the United States at (317) 572-3993 or fax (317) 572-4002.

Wiley also publishes its books in a variety of electronic formats. Some content that appears in print may not be available in electronic formats. For more information about Wiley products, visit our web site at www.wiley.com.

Library of Congress Cataloging-in-Publication Data:

Encylopedia of medical devices & instrumentation/by John G. Webster,

editor in chief. – 2nd ed.
p. ; cm.
Rev. ed. of: Encyclopedia of medical devices and instrumentation. 1988.
Includes bibliographical references and index.
ISBN-13 978-0-471-26358-6 (set : cloth)
ISBN-10 0-471-26358-3 (set : cloth)
ISBN-13 978-0-470-04067-6 (v. 2 : cloth)
ISBN-10 0-470-04067-x (v. 2 : cloth)

1. Medical instruments and apparatus–Encyclopedias. 2. Biomedical engineering–Encyclopedias. 3. Medical physics–Encyclopedias. 4. Medicine–Data processing–Encyclopedias. I. Webster, John G., 1932- . II. Title: Encyclopedia of medical devices and instrumentation.

[DNLM: 1. Equipment and Supplies–Encyclopedias–English. W 13

E555 2006]
R856.A3E53 2006
610.2803–dc22
2005028946

Printed in the United States of America

10 9 8 7 6 5 4 3 2 1

CONTRIBUTOR LIST

Abdel Hady, Mazen, *McMaster University, Hamilton, Ontario Canada*, Bladder Dysfunction, Neurostimulation of

Abel, L.A., *University of Melbourne, Melbourne, Australia*, Ocular Motility Recording and Nystagmus

Abreu, Beatriz C., *Transitional Learning Center at Galveston, Galveston, Texas*, Rehabilitation, Computers in Cognitive

Alexander, A.L., *University of Wisconsin–Madison, Madison, Wisconsin*, Magnetic Resonance Imaging

Ali, Abbas, *University of Illinois, at Urbana-Champaign*, Bioinformatics

Ali, Müftü, *School of Dental Medicine, Boston, Massachusetts*, Tooth and Jaw, Biomechanics of

Alperin, Noam, *University of Illinois at Chicago, Chicago, Illinois*, Hydrocephalus, Tools for Diagnosis and Treatment of

Anson, Denis, *College Misericordia, Dallas, Pennsylvania*, Environmental Control

Arena, John C., *VA Medical Center and Medical College of Georgia*, Biofeedback

Ariel, Gideon, *Ariel Dynamics, Canyon, California*, Biomechanics of Exercise Fitness

Armstrong, Steve, *University of Iowa, Iowa City, Iowa*, Biomaterials for Dentistry

Aspden, R.M., *University of Aberdeen, Aberdeen, United Kingdom*, Ligament and Tendon, Properties of

Aubin, C.E., *Polytechniquie Montreal, Montreal Quebec, Canada*, Scoliosis, Biomechanics of

Ayres, Virginia M., *Michigan State University, East Lansing, Michigan*, Microscopy, Scanning Tunneling

Azangwe, G., Ligament and Tendon, Properties of

Back, Lloyd H., *California Institute of Technology, Pasadena, California*, Coronary Angioplasty and Guidewire Diagnostics

Badylak, Stephen F., *McGowan Institute for Regenerative Medicine, Pittsburgh, Pennsylvania*, Sterilization of Biologic Scaffold Materials

Bandyopadhyay, Amit, *Washington State University, Pullman, Washington*, Orthopedic Devices, Materials and Design for

Banerjee, Rupak K., *University of Cincinnati, Cincinnati, Ohio*, Coronary Angioplasty and Guidewire Diagnostics

Barbour, Randall L., *State University of New York Downstate Medical Center, Brooklyn, New York*, Peripheral Vascular Noninvasive Measurements

Barker, Steven J., *University of Arizona, Tucson, Arizona*, Oxygen Monitoring

Barth, Rolf F., *The Ohio State University, Columbus, Ohio*, Boron Neutron Capture Therapy

Becchetti, F.D., *University of Michigan, Ann Arbor, Michigan*, Radiotherapy, Heavy Ion

Belforte, Guido, *Politecnico di Torino – Department of Mechanics*, Laryngeal Prosthetic Devices

Benkeser, Paul, *Georgia Institute of Technology, Atlanta, Georgia*, Biomedical Engineering Education

Bennett, James R., *University of Iowa, Iowa City, Iowa*, Digital Angiography

Bersano-Begey, Tommaso, *University of Michigan, Ann Arbor, Michigan*, Microbioreactors

Biggs, Peter J., *Harvard Medical School, Boston, Massachusetts*, Radiotherapy, Intraoperative

Biyani, Ashok, *University of Toledo, and Medical College of Ohio, Toledo, Ohio*, Human Spine, Biomechanics of

Block, W.F., *University of Wisconsin–Madison, Madison, Wisconsin*, Magnetic Resonance Imaging

Blue, Thomas E., *The Ohio State University, Columbus, Ohio*, Boron Neutron Capture Therapy

Blumsack, Judith T., *Disorders Auburn University, Auburn, Alabama*, Audiometry

Bogan, Richard K., *University of South Carolina, Columbia, South Carolina*, Sleep Laboratory

Bokros, Jack C., *Medical Carbon Research Institute, Austin, Texas*, Biomaterials, Carbon

Bongioannini, Guido, *ENT Division Mauriziano Hospital, Torino, Italy*, Laryngeal Prosthetic Devices

Borah, Joshua, *Applied Science Laboratories, Bedford, Massachusetts*, Eye Movement, Measurement Techniques for

Borden, Mark, *Director of Biomaterials Research, Irvine, California*, Biomaterials, Absorbable

Borton, Bettie B., *Auburn University Montgomery, Montgomery, Alabama*, Audiometry

Borton, Thomas E., *Auburn University Montgomery, Montgomery, Alabama*, Audiometry

Bose Susmita,, *Washington State University, Pullman, Washington*, Orthopedic Devices, Materials and Design for

Bova, Frank J., *M. D. Anderson Cancer Center Orlando, Orlando, FL*, Radiosurgery, Stereotactic

Brenner, David J., *Columbia University Medical Center, New York, New York*, Computed Tomography Screening

Brewer, John M., *University of Georgia*, Electrophoresis

Brian, L. Davis, *Lerner Research Institute, The Cleveland Clinic Foundation, Cleveland, Ohio*, Skin, Biomechanics of

Britt, L.D., *Eastern Virginia Medical School, Norfolk, Virginia*, Gastrointestinal Hemorrhage

Britt, R.C., *Eastern Virginia Medical School, Norfolk, Virginia*, Gastrointestinal Hemorrhage

Brozik, Susan M., *Sandia National Laboratories, Albuquerque, New Mexico*, Microbial Detection Systems

Bruner, Joseph P., *Vanderbilt University Medical Center, Nashville, Tennessee*, Intrauterine Surgical Techniques

Brunswig Newring, Kirk A., *University of Nevada, Reno, Nevada*, Sexual Instrumentatio n

Bruyant, Philippe P., *University of Massachusetts, North Worcester, Massachusetts*, Nuclear Medicine, Computers in

Bunnell, Bert J., *Bunnell Inc., Salt Lake City, Utah*, High Frequency Ventilation

Calkins, Jerry M., *Defense Research Technologies, Inc., Rockville, Maryland*, Medical Gas Analyzers

Cannon, Mark, *Northwestern University, Chicago, Illinois*, Resin-Based Composites

Cappelleri, Joseph C., *Pfizer Inc., Groton, Connecticut*, Quality-of-Life Measures, Clinical Significance of

Cardoso, Jorge, *University of Madeira, Funchal, Portugal*, Office Automation Systems

Carello, Massimiliana, *Politecnicodi Torino – Department of Mechanics*, Laryngeal Prosthetic Devices

Caskey, Thomas C., *Cogene Biotech Ventures, Houston, Texas*, Polymerase Chain Reaction

Ceccio, Steven, *University of Michigan, Ann Arbor, Michigan*, Heart Valve Prostheses, In Vitro Flow Dynamics of

Chan, Jackie K., *Columbia University, New York, New York*, Photography, Medical

Chandran, K.B., *University of Iowa, Iowa City, Iowa*, Heart Valve Prostheses

Chatzandroulis, S., *NTUA, Athens, Attiki, Greece*, Capacitive Microsensors for Biomedical Applications

Chavez, Eliana, *University of Pittsburgh, Pittsburgh, Pennsylvania*, Mobility Aids

Chen, Henry, *Stanford University, Palo Alto, California*, Exercise Stress Testing

Chen, Jiande, *University of Texas Medical Branch, Galveston, Texas*, Electrogastrogram

Chen, Yan, *Lerner Research Institute, The Cleveland Clinic Foundation, Cleveland, Ohio*, Skin, Biomechanics of

Cheyne, Douglas, *Hospital for Sick Children Research Institute*, Biomagnetism

Chui, Chen-Shou, *Memorial Sloan-Kettering Cancer Center, New York, New York*, Radiation Therapy Treatment Planning, Monte Carlo Calculations in

Claxton, Nathan S., *The Florida State University, Tallahassee, Florida*, Microscopy, Confocal

Coderre, Jeffrey A., *Massachus etts Institute of Technology, Cambridge, Massachusetts*, Boron Neutron Capture Therapy

Collins, Beth, *University of Mississippi Medical Center, Jackson, Mississippi*, Hyperbaric Medicine

Collins, Diane, *University of Pittsburgh, Pittsburgh, Pennsylvania*, Mobility Aids

Constantinou, C., *Columbia University Radiation Oncology, New York, New York*, Phantom Materials in Radiology

Cook, Albert, *University of Alberta, Edmonton, Alberta, Canada*, Communication Devices

Cooper, Rory, *University of Pittsburgh, Pittsburgh, Pennsylvania*, Mobility Aids

Cork, Randall C., *Louisiana State University, Shreveport, Louisiana*, Monitoring, Umbilical Artery and Vein, Blood Gas Measurements; Transcuta neous Electrical Nerve Stimulation (TENS); Ambulatory Monitoring

Cox, Josephine H., *Walter Reed Army Institute of Research, Rockville, Maryland*, Blood Collection and Processing

Craig, Leonard, *Feinberg School of Medicine of Northwestern University, Chicago, Illinois*, Ventilators, Acute Medical Care

Cress, Cynthia J., *University of Nebraska, Lincoln, Nebraska*, Communicative Disorders, Computer Applications for

Cumming, David R.S., *University of Glasgow, Glasgow, United Kingdom*, Ion-Sensitive Field-Effect Transistors

Cunningham, John R., *Camrose, Alberta, Canada*, Cobalt 60 Units for Radiotherapy

D'Alessandro, David, *Montefiore Medical Center, Bronx, New York*, Heart–Lung Machines

D'Ambra, Michael N., *Harvard Medical School, Cambridge, Massachusetts*, Cardiac Output, Thermodilution Measurement of

Dadsetan, Mahrokh, *Mayo Clinic, College of Medicine, Rochester, Minnesota*, Microscopy, Electron

Daley, Michael L., *The University of Memphis, Memphis, Tennessee*, Monitoring, Intracranial Pressure

Dan, Loyd, *Linköping University, Linköping, Sweden*, Thermocouples

Das, Rupak, *University of Wisconsin, Madison, Wisconsin*, Brachytherapy, High Dosage Rate

Dattawadkar, Amruta M., *University of Wisconsin, Madison, Madison, Wisconsin*, Ocular Fundus Reflectometry

Davidson, Michael W., *The Florida State University, Tallahassee, Florida*, Microscopy, Confocal

De Luca, Carlo, *Boston University, Boston, Massachusetts*, Electromyography

De Salles, Antonio A.F., *UCLA Medical School, Los Angeles, California*, Stereotactic Surgery

Decau, Sabin, *University of Maryland, School of Medicine*, Shock, Treatment of

Dechow, Paul C., *A & M University Health Science Center, Dallas, Texas*, Strain Gages

Delbeke, Jean, *Catholique University of Louvain, Brussels, Belgium*, Visual Prostheses

Dell'Osso, Louis F., *Case Western Reserve University, Cleveland, Ohio*, Ocular Motility Recording and Nystagmus

Delorme, Arnaud, *University of San Diego, La Jolla, California*, Statistical Methods

Demenkoff, John, *Mayo Clinic, Scottsdale, Arizona*, Pulmonary Physiology

Demir, Semahat S., *The University of Memphis and The University of Tennessee Health Science Center, Memphis, Tennessee*, Electrophysiology

Demling, Robert H., *Harvard Medical School*, Skin Substitute for Burns, Bioactive

Dennis, Michael J., *Medical University of Ohio, Toledo, Ohio*, Computed Tomography

DeSanti, Leslie, *Harvard Medical School*, Skin Substitute for Burns, Bioactive

Deutsch, Steven, *Pennsylvania State University, University Park, Pennsylvania*, Flowmeters

Devineni, Trishul, *Conemaugh Health System*, Biofeedback

Di Bella Edward, V.R., *University of Utah*, Tracer Kinetics

Diakides, Nicholas A., *Advanced Concepts Analysis, Inc., Falls Church, Virginia*, Thermography

Dolan, Patricia L., *Sandia National Laboratories, Albuquerque, New Mexico*, Microbial Detection Systems

Donovan, F.M., *University of South Alabama*, Cardiac Output, Indicator Dilution Measurement of

Douglas, Wilson R., *Children's Hospital of Philadelphia, Philadelphia, Pennsylvania*, Intrauterine Surgical Techniques

Draper, Crissa, *University of Nevada, Reno, Nevada*, Sexual Instrumentation

Drzewiecki, Tadeusz M., *Defense Research Technologies, Inc., Rockville, Maryland*, Medical Gas Analyzers

Durfee, W.K., *University of Minnesota, Minneapolis, Minnesota*, Rehabilitation and Muscle Testing

Dyro, Joseph F., *Setauket, New York*, Safety Program, Hospital

Dyson, Mary, *Herts, United Kingdom*, Heat and Cold, Therapeutic

Eckerle, Joseph S., *SRI International, Menlo Park, California*, Tonometry, Arterial

Edwards, Benjamin, *University of Wisconsin-Madison, Madison, Wisconsin*, Codes and Regulations: Radiation

Edwards, Thayne L., *University of Washington, Seattle, Washington*, Chromatography

Eklund, Anders, *University of Illinois at Chicago, Chicago, Illinois*, Hydrocephalus, Tools for Diagnosis and Treatment of

El Solh, Ali A., *Erie County Medical Center, Buffalo, New York*, Sleep Studies, Computer Analysis of

Elmayergi, Nader, *McMaster University, Hamilton, Ontario, Canada*, Bladder Dysfunction, Neurostimulation of

Elsharydah, Ahmad, *Louisiana State University, Baton Rouge, Louisiana*, Ambulatory Monitoring; Monitoring, Umbilical Artery and Vein, Blood Gas Measurements

Faddy, Steven C., *St. Vincents Hospital, Sydney, Darlinghurst, Australia*, Cardiac Output, Fick Technique for

Fahey, Frederic H., *Childrens Hospital Boston*, Computed Tomography, Single Photon Emission

Fain, S.B., *University of Wisconsin–Madison, Madison, Wisconsin*, Magnetic Resonance Imaging

Feldman, Jeffrey, *Childrens Hospital of Philadelphia, Philadelphia, Pennsylvania*, Anesthesia Machines

Fellers, Thomas J., *The Florida State University, Tallahassee, Florida*, Microscopy, Confocal

Ferrara, Lisa, *Cleveland Clinic Foundation, Cleveland, Ohio*, Human Spine, Biomechanics of

Ferrari, Mauro, *The Ohio State University, Columbus, Ohio*, Drug Delivery Systems

Fontaine, Arnold A., *Pennsylvania State University, University Park, Pennsylvania*, Flowmeters

Foust, Milton J., Jr, *Medical University of South Carolina Psychiatry and Behavioral Sciences, Charleston, South Carolina*, Electroconvulsive Therapy

Frasco, Peter, *Mayo Clinic Scottsdale, Scottsdale, Arizona*, Temperature Monitoring

Frazier, James, *Louisiana State University, Baton Rouge, Louisiana*, Ambulatory Monitoring

Freiesleben De Blasio, Birgitte, *University of Oslo, Oslo, Norway*, Impedance Spectroscopy

Fresta, Massimo, *University of Catanzaro Magna Græcia, Germaneto (CZ), Italy*, Drug Delivery Systems

Freytes, Donald O., *McGowan Institute for Regenerative Medicine, Pittsburgh Pennsylvania*, Sterilization of Biologic Scaffold Materials

Froehlicher, Victor, *VA Medical Center, Palo Alto, California*, Exercise Stress Testing

Fung, Edward K., *Columbia University, New York, New York*, Photography, Medical

Gage, Andrew A., *State University of New York at Buffalo, Buffalo, New York*, Cryosurgery

Gaglio, Paul J., *Columbia University College of Physicians and Surgeons*, Liver Transplantation

Gardner, Reed M., *LDS Hospital and Utah University, Salt Lake City, Utah*, Monitoring, Hemodynamic

Gejerman, Glen, *Hackensack University Medical, Hackensack, New Jersey*, Radiation Therapy, Quality Assurance in

George, Mark S., *Medical University of South Carolina Psychiatry and Behavioral Sciences, Charleston, South Carolina*, Electroconvulsive Therapy

Gharieb, R.R., *Infinite Biomedical Technologies, Baltimore, Maryland*, Neurological Monitors

Glasgow, Glenn P., *Loyola University of Chicago, Maywood, Illinois*, Radiation Protection Instrumentation

Glasgow, Glenn, *University of Wisconsin-Madison, Madison, Wisconsin*, Codes and Regulations: Radiation

Goel, Vijay K., *University of Toledo, and Medical College of Ohio, Toledo, Ohio*, Human Spine, Biomechanics of

Goetsch, Steven J., *San Diego Gamma Knife Center, La Jolla, California*, Gamma Knife

Goldberg, Jay R., *Marquette University Milwaukee, Wisconsin*, Minimally Invasive Surgery

Goldberg, Zelenna, *Department of Radiation Oncology, Davis, California*, Ionizing Radiation, Biological Effects of

Gopalakrishnakone, P., *National University of Singapore, Singapore*, Immunologically Sensitive Field-Effect Transistors

Gopas, Jacob, *Ben Gurion University of the Negev, Beer Sheva, Israel*, Monoclonal Antibodies

Gorgulho, Alessandra, *UCLA Medical School, Los Angeles, California*, Stereotactic Surgery

Gough, David A., *University of California, La Jolla, California*, Glucose Sensors

Goustouridis, D., *NTUA, Athens, Attiki, Greece*, Capacitive Microsensors for Biomedical Applications

Graber, Harry L., *State University of New York Downstate Medical Center, Brooklyn, New York*, Peripheral Vascular Noninvasive Measurements

Graça, M., *Louisiana State University, Baton Rouge, Louisiana*, Boron Neutron Capture Therapy

Grant, Walter III, *Baylor College of Medicine, Houston, Texas*, Radiation Therapy, Intensity Modulated

Grayden, Edward, *Mayo Health Center, Albertlea, Minnesota*, Cardiopulmonary Resuscitation

Green, Jordan R., *University of Nebraska, Lincoln, Nebraska*, Communicative Disorders, Computer Applications for

Haemmerich, Dieter, *Medical University of South Carolina, Charleston, South Carolina*, Tissue Ablation

Hamam, Habib, *Université de Moncton, Moncton New Brunswick, Canada*, Lenses, Intraocular

Hammond, Paul A., *University of Glasgow, Glasgow, United Kingdom*, Ion-Sensitive Field-Effect Transistors

Hanley, Joseph, *Hackensack University Medical, Hackensack, New Jersey*, Radiation Therapy, Quality Assurance in

Harley, Brendan A., *Massachusetts Institute of Technology*, Skin Tissue Engineering for Regeneration

Harper, Jason C., *Sandia National Laboratories, Albuquerque, New Mexico*, Microbial Detection Systems

Hasman, Arie, *Maastricht, The Netherlands*, Medical Education, Computers in

Hassouna, Magdy, *Toronto Western Hospital, Toronto, Canada*, Bladder Dysfunction, Neurostimulation of

Hayashi, Kozaburo, *Okayama University of Science, Okayama, Japan*, Arteries, Elastic Properties of

Hench, Larry L., *Imperial College London, London, United Kingdom*, Biomaterials: Bioceramics

Hettrick, Douglas A., *Sr. Principal Scientist Medtronic, Inc., Minneapolis, Minnesota*, Bioimpedance in Cardiovascular Medicine

Hirsch-Kuchma, Melissa, *University of Central Florida NanoScience Technology Center, Orlando, Florida*, Biosurface Engineering

Holder, Graham E., *Moorfields Eye Hospital, London, United Kingdom*, Electroretinography

Holmes, Timothy, *St. Agnes Cancer Center, Baltimore, Maryland*, Tomotherapy

Honeyman-Buck, Janice C., *University of Florida, Gainesville, Florida*, Radiology Information Systems

Hooper, Brett A., *Areté Associates, Arlington, Virginia*, Endoscopes

Horn, Bruce, *Kaiser Permanente, Los Angeles, California*, X-Rays Production of

Horner, Patricia I., *Biomedical Engineering Society Landover, Maryland*, Medical Engineering Societies and Organizations

Horowitz, Paul M., *University of Texas, San Antonio, Texas*, Fluorescence Measurements

Hou, Xiaolin, *Risø National Laboratory, Roskilde, Denmark*, Neutron Activation Analysis

Hovorka, Roman, *University of Cambridge, Cambridge, United Kingdom*, Pancreas, Artificial

Huang, H.K., *University of Southern California*, Teleradiology

Hunt, Alan J., *University of Michigan, Ann Arbor, Michigan*, Optical Tweezers

Hutten, Helmut, *University of Technology, Graz, Australia*, Impedance Plethysmography

Iaizzo, P.A., *University of Minnesota, Minneapolis, Minnesota*, Rehabilitation and Muscle Testing

Ibbott, Geoffrey S., *Anderson Cancer Center, Houston, Texas*, Radiation Dosimetry, Three-Dimensional

Ingham, E., *University of Leeds, Leeds, United Kingdom*, Hip Joints, Artificial

Isik, Can, *Syracuse University, Syracuse, New York*, Blood Pressure Measurement

James, Susan P., *Colorado State University, Fort Collins, Colorado*, Biomaterials: Polymers

Jensen, Winnie, *Aalborg University, Aalborg, Denmark*, Electroneurography

Jin, Chunming, *North Carolina State University, Raleigh, North Carolina*, Biomaterials, Corrosion and Wear of

Jin, Z.M., *University of Leeds, Leeds, United Kingdom*, Hip Joints, Artificial

Johnson, Arthur T., *University of Maryland College Park, Maryland*, Medical Engineering Societies and Organizations

Jones, Julian R., *Imperial College London, London, United Kingdom*, Biomaterials: Bioceramics

Joshi, Abhijeet, *Abbott Spine, Austin, Texas*, Spinal Implants

Jung, Ranu, *Arizona State University, Tempe, Arizona*, Functional Electrical Stimulation

Jurisson, Silvia S., *University of Missouri Columbia, Missouri*, Radionuclide Production and Radioactive Decay

Kaeding, Patricia J., *Godfrey & Kahn S.C., Madison, Wisconsin*, Codes and Regulations: Medical Devices

Kamath, Celia C., *Mayo Clinic, Rochester, Minnesota*, Quality-of-Life Measures, Clinical Significance of

Kane, Mollie, *Madison, Wisconsin*, Contraceptive Devices

Katherine, Andriole P., *Harvard Medical School, Boston, Massachusetts*, Picture Archiving and Communication Systems

Katsaggelos, Aggelos K., *Northwestern University, Evanston, Illinois*, DNA Sequencing

Katz, J. Lawrence, *University of Missouri-Kansas City, Kansas City, Missouri*, Bone and Teeth, Properties of

Kesavan, Sunil, *Akebono Corporation, Farmington Hills, Michigan*, Linear Variable Differential Transformers

Khang, Gilson, *Chonbuk National University*, Biomaterials: Tissue Engineering and Scaffolds

Khaodhiar, Lalita, *Harvard Medical School, Boston, Massachusetts*, Cutaneous Blood Flow, Doppler Measurement of

Kim, Moon Suk, *Korea Research Institutes of Chemical Technology*, Biomaterials: Tissue Engineering and Scaffolds

Kim, Young Kon, *Inje University, Kimhae City, Korea*, Alloys, Shape Memory

Kindwall, Eric P., *St. Luke's Medical Center, Milwaukee, Wisconsin*, Hyperbaric Oxygenation

King, Michael A., *University of Massachusetts, North Worcester, Massachusetts*, Nuclear Medicine, Computers in

Klebe, Robert J., *University of Texas, San Antonio, Texas*, Fluorescence Measurements

Klein, Burton, *Burton Klein Associates, Newton, Massachusetts*, Gas and Vacuum Systems, Centrally Piped Medical

Knoper, Steven R., *University of Arizona College of Medicine*, Ventilatory Monitoring

Kontaxakis, George, *Universidad Politécnica de Madrid, Madrid, Spain*, Positron Emission Tomography

Kottke-Marchant, Kandice, *The Cleveland Clinic Foundation, Cleveland, Ohio*, Vascular Graft Prosthesis

Kripfgans, Oliver, *University of Michigan, Ann Arbor, Michigan*, Ultrasonic Imaging

Kulkarni, Amol D., *University of Wisconsin–Madison, Madison, Wisconsin*, Ocular Fundus Reflectometry, Visual Field Testing

Kumaradas, J. Carl, *Ryerson University, Toronto, Ontario, Canada*, Hyperthermia, Interstitial

Kunicka, Jolanta, *Bayer HealthCare LLC, Tarrytown, New York*, Differential Counts, Automated

Kwak, Kwanj Joo, *University of Miami Miller School of Medicine, Miami, Florida*, Microscopy, Scanning Force

Lakes, Roderic, *University of Wisconsin-Madison*, Bone and Teeth, Properties of

Lakkireddy, Dhanunjaya, *The Cleveland Clinic Foundation, Cleveland, Ohio*, Hyperthermia, Ultrasonic

Larsen, Coby, *Case Western Reserve University, Cleveland, Ohio*, Vascular Graft Prosthesis

Laster, Brenda H., *Ben Gurion University of the Negev, Beer Sheva, Israel*, Monoclonal Antibodies

Latta, Loren, *University of Miami, Coral Gables, Florida*, Rehabilitation, Orthotics in

Leder, Ron S., *Universidad Nacional Autonoma de Mexico Mexico, Distrito Federal*, Continuous Positive Airway Pressure

Lee, Chin, *Harvard Medical School, Boston, Massachusetts*, Radiotherapy Treatment Planning, Optimization of; Hyperthermia, Interstitial

Lee, Hai Bang, *Korea Research Institutes of Chemical Technology*, Biomaterials: Tissue Engineering and Scaffolds

Lee, Sang Jin, *Korea Research Institutes of Chemical Technology*, Biomaterials: Tissue Engineering and Scaffolds

Lei, Liu, *Department of General Engineering, Urbana, Illinois*, Bioinformatics

Lei, Xing, *Stanford University, Stanford, California*, Radiation Dose Planning, Computer-Aided

Lewis, Matthew C., *Medical College of Wisconsin, Milwaukee, Wisconsin*, Hyperbaric Oxygenation

Li, Chaodi, *University of Notre Dame, Notre Dame, Indiana*, Bone Cement, Acrylic

Li, Jonathan G., *University of Florida, Gainesville, Florida*, Radiation Dose Planning, Computer-Aided

Li, Qiao, *University of Michigan, Ann Arbor, Michigan*, Immunotherapy

Li, Yanbin, *University of Arkansas, Fayetteville, Arkansas*, Piezoelectric Sensors

Liboff, A.R., *Oakland University, Rochester, Michigan*, Bone Ununited Fracture and Spinal Fusion, Electrical Treatment of

Ligas, James, *University of Connecticut, Farmington, Connecticut*, Respiratory Mechanics and Gas Exchange

Limoge, Aime, *The René Descartes University of Paris, Paris, France*, Electroanalgesia, Systemic

Lin, Pei-Jan Paul, *Beth Israel Deaconess Medical Center, Boston, Massachusets*, Mammography

Lin, Zhiyue, *University of Kansas Medical Center, Kansas City, Kansas*, Electrogastrogram

Lineaweaver, William C., *Unive rsity of Mississippi Medical Center, Jackson, Mississippi*, Hyperbaric Medicine

Lipping, Tarmo, *Tampere University of Technology, Pori, Finland*, Monitoring in Anesthesia

Liu, Xiaohua, *The University of Michigan, Ann Arbor, Michigan*, Polymeric Materials

Lloyd, J.J., *Regional Medical Physics Department, Newcastle-upon-Tyne, United Kingdom*, Ultraviolet Radiation in Medicine

Loeb, Robert, *University of Arizona, Tuscon, Arizona*, Anesthesia Machines

Lopes de Melo, Pedro, *State University of Rio de Janeiro, Térreo Salas, Maracaná, Thermistors*

Loudon, Robert G., Lung Sounds

Low, Daniel A., *Washington University School of Medicine, St. Louis, Missouri*, Radiation Therapy Simulator

Lu, Lichun, *Mayo Clinic, College of Medicine, Rochester, Minnesota*, Microscopy, Electron

Lu, Zheng Feng, *Columbia University, New York, New York*, Screen-Film Systems

Lyon, Andrew W., *University of Calgary, Calgary, Canada*, Flame Atomic Emission Spectrometry and Atomic Absorption Spectrometry

Lyon, Martha E., *University of Calgary, Calgary, Canada*, Flame Atomic Emission Spectrometry and Atomic Absorption Spectrometry

Ma, C-M Charlie, *Fox Chase Cancer Center, Philadelphia, Pennsylvania*, X-Ray Therapy Equipment, Low and Medium Energy

Macia, Narciso F., *Arizona State University at the Polytechnic Campus, Mesa, Arizona*, Pneumotachometers

Mackenzie, Colin F., *University of Maryland, School of Medicine*, Shock, Treatment of

Mackie, Thomas R., *University of Wisconsin, Madison, Wisconsin*, Tomotherapy

Madnani, Anju, *LSU Medical Centre, Shreveport, Louisiana*, Transcutaneous Electrical Nerve Stimulation (TENS)

Madnani, Sanjay, *LSU Medical Centre, Shreveport, Louisiana*, Transcutaneous Electrical Nerve Stimulation (TENS)

Madsen, Mark T., *University of Iowa, Iowa City, Iowa*, Anger Camera

Magnano, Mauro, *ENT Division Mauriziano Hospital, Torino, Italy*, Drug Delivery Systems

Mandel, Richard, *Boston University School of Medicine, Boston, Massachusetts*, Colorimetry

Manning, Keefe B., *Pennsylvania State University, University Park, Pennsylvania*, Flowmeters

Mao, Jeremy J., *University of Illinois at Chicago, Chicago, Illinois*, Cartilage and Meniscus, Properties of

Marcolongo, Michele, *Drexel University, Philadelphia, Pennsylvania*, Spinal Implants

Marek, Miroslav, *Georgia Institute of Technology, Atlanta, Georgia*, Biomaterials, Corrosion and Wear of

Marion, Nicholas W., *University of Illinois at Chicago, Chicago, Illinois*, Cartilage and Meniscus, Properties of

Masters, Kristyn S., *University of Wisconsin, Madison, Wisconsin*, Tissue Engineering

Maughan, Richard L., *Hospital of the University of Pennsylvania*, Neutron Beam Therapy

McAdams, Eric, *University of Ulster at Jordanstown, Newtownabbey, Ireland*, Bioelectrodes

McArthur, Sally L., *University of Sheffield, Sheffield, United Kingdom*, Biomaterials, Surface Properties of

McEwen, Malcom, *National Research Council of Canada, Ontario, Canada*, Radiation Dosimetry for Oncology

McGowan, Edward J., *E.J. McGowan & Associates*, Biofeedback

McGrath, Susan, *Dartmouth College, Hanover, New Hampshire*, Oxygen Analyzers

Meeks, Sanford L., *University of Florida, Gainesville, Florida*, Radiosurgery, Stereotactic

Melissa, Peter, *University of Central Florida NanoScience Technology Center, Orlando, Florida*, Biosurface Engineering

Mendelson, Yitzhak, *Worcester Polytechnic Institute*, Optical Sensors

Metzker, Michael L., *Baylor College of Medicine, Houston, Texas*, Polymerase Chain Reaction

Meyerend, M.E., *University of Wisconsin–Madison, Madison, Wisconsin*, Magnetic Resonance Imaging

Michler, Robert, *Montefiore Medical Center, Bronx, New York*, Heart–Lung Machines

Micic, Miodrag, *MP Biomedicals LLC, Irvine, California*, Microscopy and Spectroscopy, Near-Field

Miller, William, *University of Missouri Columbia, Missouri*, Radionuclide Production and Radioactive Decay

Mittra, Erik, *Stony Brook University, New York*, Bone Density Measurement

Modell, Mark, *Harvard Medical School, Boston, Massachusetts*, Fiber Optics in Medicine

More, Robert B., *RBMore Associates, Austin, Texas* Biomaterials Carbon

More, Robert, *Austin, Texas*, Heart Valves, Prosthetic

Morrow, Darren, *Royal Adelaide Hospital, Adelaide, Australia*, Intraaortic Balloon Pump

Mourtada, Firas, *MD Anderson Cancer Center, Houston, Texas*, Brachytherapy, Intravascular

Moy, Vincent T., *University of Miami, Miller School of Medicine, Miami, Florida*, Microscopy, Scanning Force

Müftü, Sinan, *Northeastern University, Boston, Massachusetts*, Tooth and Jaw, Biomechanics of

Murphy, Raymond L.H., Lung Sounds

Murphy, William L., *University of Wisconsin, Madison, Wisconsin*, Tissue Engineering

Murray, Alan, *Newcastle University Medical Physics, Newcastle upon Tyne, United Kingdom*, Pace makers

Mutic, Sasa, *Washington University School of Medicine, St. Louis, Missouri*, Radiation Therapy Simulator

Narayan, Roger J., *University of North Carolina, Chapel Hill, North Carolina*, Biomaterials, Corrosion and Wear of

Natale, Andrea, *The Cleveland Clinic Foundation, Cleveland, Ohio*, Hyperthermia, Ultrasonic

Nazeran, Homer, *The University of Texas, El Paso, Texas*, Electrocardiography, Computers in

Neuman, Michael R., *Michigan Technological University, Houghton, Houghton, Michigan*, Fetal Monitoring, Neonatal Monitoring

Neuzil, Pavel, *Institute of Bioengineering and Nanotechnology, Singapore*, Immunologically Sensitive Field-Effect Transistors

Nickoloff, Edward L., *Columbia University, New York, New York*, X-Ray Quality Control Program

Niezgoda, Jeffrey A., *Medical College of Wisconsin, Milwaukee, Wisconsin*, Hyperbaric Oxygenation

Nishikawa, Robert M., *The University of Chicago, Chicago, Illinois*, Computer-Assisted Detection and Diagnosis

Nutter, Brian, *Texas Tech University, Lubbock, Texas*, Medical Records, Computers in

O'Donohue, William, *University of Nevada, Reno, Nevada*, Sexual Instrumentation

Orton, Colin, *Harper Hospital and Wayne State University, Detroit, Michigan*, Medical Physics Literature

Ozcelik, Selahattin, *Texas A&M University, Kingsville, Texas*, Drug Infusion Systems

Panitch, Alyssa, *Arizona State University, Tempe, Arizona*, Biomaterials: An Overview

Paolino, Donatella, *University of Catanzaro Magna Græcia, Germaneto (CZ), Italy*, Drug Delivery Systems

Papaioannou, George, *University of Wisconsin, Milwaukee, Wisconsin*, Joints, Biomechanics of

Park, Grace E., *Purdue University, West Lafayette, Indiana*, Porous Materials for Biological Applications

Parmenter, Brett A., *State University of New York at Buffalo, Buffalo, New York*, Sleep Studies, Computer Analysis of

Patel, Dimpi, *The Cleveland Clinic Foundation, Cleveland, Ohio*, Hyperthermia, Ultrasonic

Pearce, John, *The University of Texas, Austin, Texas*, Electrosurgical Unit (ESU)

Pelet, Serge, *Massachusetts Institute of Technology, Cambridge, Massachusetts*, Microscopy, Fluorescence

Periasamy, Ammasi, *University of Virginia, Charlottesville, Virginia*, Cellular Imaging

Persons, Barbara L., *University of Mississippi Medical Center, Jackson, Mississippi*, Hyperbaric Medicine

Piper, Ian, *The University of Memphis, Memphis, Tennessee*, Monitoring, Intracranial Pressure

Poletto, Christopher J., *National Institutes of Health*, Tactile Stimulation

Preminger, Glenn M., *Duke University Medical Center, Durham, North Carolina*, Lithotripsy

Prendergast, Patrick J., *Trinity College, Dublin, Ireland*, Orthopedics, Prosthesis Fixation for

Previte, Michael, *Massachusetts Institute of Technology, Cambridge, Massachusetts*, Microscopy, Fluorescence

Purdy, James A., *UC Davis Medical Center, Sacramento, California*, Radiotherapy Accessories

Qi, Hairong, *Advanced Concepts Analysis, Inc., Falls Church, Virginia*, Thermography

Qin, Yixian, *Stony Brook University, New York*, Bone Density Measurement

Quan, Stuart F., *University of Arizona, Tucson, Arizona*, Ventilatory Monitoring

Quiroga, Rodrigo Quian, *University of Leicester, Leicester, United Kingdom*, Evoked Potentials

Rahaghi, Farbod N., *University of California, La Jolla, California*, Glucose Sensors

Rahko, Peter S., *University of Wisconsin Medical School*, Echocardiography and Doppler Echocardiography

Ralph, Lieto, *University of Wisconsin–Madison, Madison, Wisconsin*, Codes and Regulations: Radiation

Ramanathan, Lakshmi, *Mount Sinai Medical Center*, Analytical Methods, Automated

Rao, Satish S.C., *University of Iowa College of Medicine, Iowa City, Iowa*, Anorectal Manometry

Rapoport, David M., *NYU School of Medicine, New York, New York*, Continuous Positive Airway Pressure

Rebello, Keith J., *The Johns Hopkins University Applied Physics Lab, Laurel, Maryland*, Micro surgery

Reddy, Narender, *The University of Akron, Akron, Ohio*, Linear Variable Differential Transformers

Ren-Dih, Sheu, *Memorial Sloan-Kettering Cancer Center, New York, New York*, Radiation Therapy Treatment Planning, Monte Carlo Calculations in

Rengachary, Setti S., *Detroit, Michigan*, Human Spine, Biomechanics of

Repperger, Daniel W., *Wright-Patterson Air Force Base, Dayton, Ohio*, Human Factors in Medical Devices

Ritchey, Eric R., *The Ohio State University, Columbus, Ohio*, Contact Lenses

Rivard, Mark J., *Tufts New England Medical Center, Boston, Massachusetts*, Imaging Devices

Robertson, J. David, *University of Missouri, Columbia, Missouri*, Radionuclide Production and Radioactive Decay

Roth, Bradley J., *Oakland University, Rochester, Michigan*, Defibrillators

Rowe-Horwege, R. Wanda, *University of Texas Medical School, Houston, Texas*, Hyperthermia, Systemic

Rumsey, John W., *University of Central Florida, Orlando, Florida*, Biosurface Engineering

Rutkowski, Gregory E., *University of Minnesota, Duluth, Minnesota*, Engineered Tissue

Salata, O.V., *University of Oxford, Oxford, United Kingdom*, Nanoparticles

Samaras, Theodoros, *Aristotle University of Thessaloniki Department of Physics, Thessaloniki, Greece*, Thermometry

Sangole, Archana P., *Transitional Learning Center at Galveston, Galveston, Texas*, Rehabilitation, Computers in Cognitive

Sarkozi, Laszlo, *Mount Sinai School of Medicine*, Analytical Methods, Automated

Schek, Henry III, *University of Michigan, Ann Arbor, Michigan*, Optical Tweezers

Schmitz, Christoph H., *State University of New York Downstate Medical Center, Brooklyn, New York*, Peripheral Vascular Noninvasive Measurements

Schuckers, Stephanie A.C., *Clarkson University, Potsdam, New York*, Arrhythmia Analysis, Automated

Scope, Kenneth, *Northwestern University, Chicago, Illinois*, Ventilators, Acute Medical Care

Scott, Adzick N., *University of Pennsylvania, Philadelphia, Pennsylvania*, Intrauterine Surgical Techniques

Seal, Brandon L., *Arizona State University, Tempe, Arizona*, Biomaterials: An Overview

Seale, Gary, *Transitional Learning Center at Galveston, Galveston, Texas*, Rehabilitation, Computers in Cognitive

Segers, Patrick, *Ghent University, Belgium*, Hemodynamics

Selim, Mostafa A., *Cleveland Metropolitan General Hospital, Palm Coast, Florida*, Colposcopy

Sethi, Anil, *Loyola University Medical Center, Maywood, Illinois*, X-Rays: Interaction with Matter

Severinghaus, John W., *University of California in San Francisco*, CO_2 Electrodes

Shalodi, Abdelwahab D., *Cleveland Metropolitan General Hospital, Palm Coast, Florida*, Colposcopy

Shanmugasundaram, Shobana, *New Jersey Institute of Technology, Newark, New Jersey*, Polymeric Materials

Shard, Alexander G., *University of Sheffield, Sheffield United Kingdom*, Biomaterials, Surface Properties of

Shen, Li-Jiuan, *National Taiwan University School of Pharmacy, Taipei, Taiwan*, Colorimetry

Shen, Wei-Chiang,*University of Southern California School of Pharmacy, Los Angeles, California*, Colorimetry

Sherar, Michael D., *London Health Sciences Centre and University of Western Ontario, London, Ontario, Canada*, Hyperthermia, Interstitial

Sherman, David, *The Johns Hopkins University, Baltimore, Maryland*, Electroencephalography

Shi, Donglu, *University of Cincinnati, Cincinnati, Ohio*, Biomaterials, Testing and Structural Properties of

Shucard, David W.M., *State University of New York at Buffalo, Buffalo, New York*, Sleep Studies, Computer Analysis of

Siedband, Melvin P., *University of Wisconsin, Madison, Wisconsin*, Image Intensifiers and Fluoroscopy

Silberman, Howard, *University of Southern California, Los Angeles, California*, Nutrition, Parenteral

Silverman, Gordon, *Manhattan College*, Computers in the Biomedical Laboratory

Silvern, David A., *Medical Physics Unit, Rabin Medical Center, Petah Tikva, Israel*, Prostate Seed Implants

Sinha, Piyush, *The Ohio State University, Columbus, Ohio*, Drug Delivery Systems

Sinha, Abhijit Roy, *University of Cincinnati, Cincinnati, Ohio*, Coronary Angioplasty and Guidewire Diagnostics

Sinkjær, Thomas, *Aalborg University, Aalborg, Denmark*, Electroneurography

Sloan, Jeffrey A., *Mayo Clinic, Rochester, Minnesota*, Quality-of-Life Measures, Clinical Significance of

So, Peter T.C., *Massachusetts Institute of Technology, Cambridge, Massachusetts*, Microscopy, Fluorescence

Sobol, Wlad T., *University of Alabama at Birmingham Health System, Birmingham, Alabama*, Nuclear Magnetic Resonance Spectroscopy

Sood, Sandeep, *University of Illinois at Chicago, Chicago, Illinois*, Hydrocephalus, Tools for Diagnosis and Treatment of

Spector, Myron, *Brigham and Women's Hospital, Boston, Massachusetts*, Biocompatibility of Materials

Spelman, Francis A., *University of Washington*, Cochlear Prostheses

Srinivasan, Yeshwanth, *Texas Tech University, Lubbock, Texas*, Medical Records, Computers in

Sriram, Neelamegham, *University of Buffalo, Buffalo, New York*, Cell Counters, Blood

Starko, Kenton R., *Point Roberts, Washington*, Physiological Systems Modeling

Starkschall, George, *The University of Texas*, Radiotherapy, Three-Dimensional Conformal

Stavrev, Pavel, *Cross Cancer Institute, Edmonton, Alberta, Canada*, Radiotherapy Treatment Planning, Optimization of

Stenken, Julie A., *Rensselaer Polytechnic Institute, Troy, New York*, Microdialysis Sampling

Stiefel, Robert, *University of Maryland Medical Center, Baltimore, Maryland*, Equipment Acquisition

Stokes, I.A.F., *Polytechniquie Montreal, Montreal Quebec, Canada*, Scoliosis, Biomechanics of

Stone, M.H., *University of Leeds, Leeds, United Kingdom*, Hip Joints, Artificial

Su, Xiao-Li, *BioDetection Instruments LLC, Fayetteville, Arkansas*, Piezoelectric Sensors

Subhan, Arif, *Masterplan Technology Management, Chatsworth, California*, Equipment Maintenance, Biomedical

Sweeney, James D., *Arizona State University, Tempe, Arizona*, Functional Electrical Stimulation

Szeto, Andrew Y.J., *San Diego State University, San Diego, California*, Blind and Visually Impaired, Assistive Technology for

Takayama, Shuichi, *University of Michigan, Ann Arbor, Michigan*, Microbioreactors

Tamul, Paul C., *Northwestern University, Chicago, Illinois*, Ventilators, Acute Medical Care

Tamura, Toshiyo, *Chiba University School of Engineering, Chiba, Japan*, Home Health Care Devices

Tang, Xiangyang, *GE Healthcare Technologies, Wankesha, Wisconsin*, Computed Tomography Simulators

Taylor, B.C., *The University of Akron, Akron, Ohio*, Cardiac Output, Indicator Dilution Measurement of

Temple, Richard O., *Transitional Learning Center at Galveston, Galveston, Texas*, Rehabilitation, Computers in Cognitive

Ten, Stanley, *Salt Lake City, Utah*, Electroanalgesia, Systemic

Terry, Teresa M., *Walter Reed Army Institute of Research, Rockville, Maryland*, Blood Collection and Processing

Thakor, N.V., *Johns Hopkins University, Baltimore, Maryland*, Neurological Monitors

Thierens, Hubert M.A., *University of Ghent, Ghent, Belgium*, Radiopharmaceutical Dosimetry

Thomadsen, Bruce, *University of Wisconsin–Madison, Madison, Wisconsin*, Codes and Regulations: Radiation

Tipper, J.L., *University of Leeds, Leeds, United Kingdom*, Hip Joints, Artificial

Togawa, Tatsuo, *Waseda University, Saitama, Japan*, Integrated Circuit Temperature Sensor

Tornai, Martin, *Duke University, Durham, North Carolina*, X-Ray Equipment Design

Tran-Son-Tay, Roger, *University of Florida, Gainesville, Florida*, Blood Rheology

Trautman, Edwin D., *RMF Strategies, Cambridge, Massachusetts*, Cardiac Output, Thermodilution Measurement of

Treena, Livingston Arinzeh, *New Jersey Institute of Technology, Newark, New Jersey*, Polymeric Materials

Trentman, Terrence L., *Mayo Clinic Scottsdale*, Spinal Cord Stimulation

Troken, Alexander J., *University of Illinois at Chicago, Chicago, Illinois*, Cartilage and Meniscus, Properties of

Tsaftaris, Sotirios A., *Northwestern University, Evanston, Illinois*, DNA Sequence

Tsoukalas, D., *NTUA, Athens, Attiki, Greece*, Capacitive Microsensors for Biomedical Applications

Tulipan, Noel, *Vanderbilt University Medical Center, Nashville, Tennessee*, Intrauterine Surgical Techniques

Tuteja, Ashok K., *University of Utah, Salt Lake City, Utah*, Anorectal Manometry

Ty, Smith N., *University of California, San Diego, California*, Physiological Systems Modeling

Tyrer, Harry W., *University of Missouri-Columbia, Columbia, Missouri*, Cytology, Automated

Valvano, Jonathan W., *The University of Texas, Austin, Texas*, Bioheat Transfer

Van den Heuval, Frank, *Wayne State University, Detroit, Michigan*, Imaging Devices

Veit, Schnabel, *Aalborg University, Aalborg, Denmark*, Electroneurography

Velanovich, Vic, *Henry Ford Hospital, Detroit, Michigan*, Esophageal Manometry

Venkatasubramanian, Ganapriya, *Arizona State University, Tempe, Arizona*, Functional Electrical Stimulation

Veraart, Claude, *Catholique University of Louvain, Brussels, Belgium*, Visual Prostheses

Verdonck, Pascal, *Ghent University, Belgium*, Hemodynamics

Vermarien, Herman, *Vrije Universiteit Brussel, Brussels, Belgium*, Phonocardiography, Recorders, Graphic

Veves, Aristidis, *Harvard Medical School, Boston, Massachusetts*, Cutaneous Blood Flow, Doppler Measurement of

Vicini, Paolo, *University of Washington, Seattle, Washington*, Pharmacokinetics and Pharmacodynamics

Ville, Jäntti, *Tampere University of Technology, Pori, Finland*, Monitoring in Anesthesia

Vrba, Jini, *VSM MedTech Ltd.*, Biomagnetism

Wagner, Thomas, H., *M. D. Anderson Cancer Center Orlando, Orlando, Florida*, Radiosurgery, Stereotactic

Wahlen, George E., *Veterans Affairs Medical Center and the University of Utah, Salt Lake City, Utah*, Anorectal Manometry

Walker, Glenn M., *North Carolina State University, Raleigh, North Carolina*, Microfluidics

Walterspacher, Dirk, *The Johns Hopkins University, Baltimore, Maryland*, Electroencephalography

Wan, Leo Q., *Liu Ping, Columbia University, New York, New York*, Cartilage and Meniscus, Properties of

Wang, Ge, *University of Iowa, Iowa City, Iowa*, Computed Tomography Simulators

Wang, Haibo, *Louisiana State University Health Center Shreveport, Louisiana*, Monitoring, Umbilical Artery and Vein, Ambulatory Monitoring

Wang, Hong, *Wayne State University, Detroit, Michigan*, Anesthesia, Computers in

Wang, Le Yi, *Wayne State University, Detroit, Michigan*, Anesthesia, Computers in

Wang, Qian, *A & M University Health Science Center, Dallas, Texas*, Strain Gages

Warwick, Warren J., *University of Minnesota Medical School, Minneapolis, Minnesota*, Cystic Fibrosis Sweat Test

Watanabe, Yoichi, *Columbia University Radiation Oncology, New York, New York*, Phantom Materials in Radiology

Waxler, Morris, *Godfrey & Kahn S.C., Madison, Wisconsin*, Codes and Regulations: Medical Devices

Webster, Thomas J., *Purdue University, West Lafayette, Indiana*, Porous Materials for Biological Applications

Wegener, Joachim, *University of Oslo, Oslo, Norway*, Impedance Spectroscopy

Wei, Shyy, *University of Michigan, Ann Arbor, Michigan*, Blood Rheology

Weinmeister, Kent P., *Mayo Clinic Scottsdale*, Spinal Cord Stimulation

Weizer, Alon Z., *Duke University Medical Center, Durham, North Carolina*, Lithotripsy

Weller, Peter, *City University , London, United Kingdom*, Intraaortic Balloon Pump

Wells, Jason, *LSU Medical Centre, Shreveport, Louisiana*, Transcutaneous Electrical Nerve Stimulation (TENS)

Wendelken, Suzanne, *Dartmouth College, Hanover, New Hampshire*, Oxygen Analyzers

Whelan, Harry T., *Medical College of Wisconsin, Milwaukee, Wisconsin*, Hyperbaric Oxygenation

White, Robert, *Memorial Hospital, Regional Newborn Program, South Bend, Indiana*, Incubators, Infant

Williams, Lawrence E., *City of Hope, Duarte, California*, Nuclear Medicine Instrumentation

Wilson, Kerry, *University of Central Florida, Orlando, Florida*, Biosurface Engineering

Winegarden, Neil, *University Health Network Microarray Centre, Toronto, Ontario, Canada*, Microarrays

Wojcikiewicz, Ewa P., *University of Miami Miller School of Medicine, Miami, Florida*, Microscopy, Scanning Force

Wolbarst, Anthony B., *Georgetown Medical School, Washington, DC*, Radiotherapy Treatment Planning, Optimization of

Wolf, Erik, *University of Pittsburgh, Pittsburgh, Pennsylvania*, Mobility Aids

Wood, Andrew, *Swinburne University of Technology, Melbourne, Australia*, Nonionizing Radiation, Biological Effects of

Woodcock, Brian, *University of Michigan, Ann Arbor, Michigan*, Blood, Artificial

Wren, Joakim, *Linköping University, Linköping, Sweden*, Thermocouples

Xiang, Zhou, *Brigham and Women's Hospital, Boston, Massachusetts*, Biocompatibility of Materials

Xuejun, Wen, *Clemson University, Clemson, South Carolina*, Biomaterials, Testing and Structural Properties of

Yan, Zhou, *University of Notre Dame, Notre Dame, Indiana*, Bone Cement, Acrylic

Yannas, Ioannis V., *Massachusetts Institute of Technology*, Skin Tissue Engineering for Regeneration

Yaszemski, Michael J., *Mayo Clinic, College of Medicine, Rochester, Minnesota*, Microscopy, Electron

Yeni, Yener N., *Henry Ford Hospital, Detroit, Michigan*, Joints, Biomechanics of

Yli-Hankala, Arvi, *Tampere University of Technology, Pori, Finland*, Monitoring in Anesthesia

Yoko, Kamotani, *University of Michigan, Ann Arbor, Michigan*, Microbioreactors

Yoon, Kang Ji, *Korea Institute of Science and Technology, Seoul, Korea*, Micropower for Medical Applications

Yorke, Ellen, *Memorial Sloan-Kettering Cancer Center, New York, New York*, Radiation Therapy Treatment Planning, Monte Carlo Calculations in

Yoshida, Ken, *Aalborg University, Aalborg, Denmark*, Electroneurography

Youngstedt, Shawn D., *University of South Carolina, Columbia, South Carolina*, Sleep Laboratory

Yu, Yih-Choung, *Lafayette College, Easton, Pennsylvania*, Blood Pressure, Automatic Control of

Zachariah, Emmanuel S., *University of Medicine and Dentistry of New Jersey, New Brunswick, New Jersey*, Immunologically Sensitive Field-Effect Transistors

Zaider, Marco, *Memorial Sloan Kettering Cancer Center, New York, New York*, Prostate Seed Implants

Zapanta, Conrad M., *Penn State College of Medicine, Hershey, Pennsylvania*, Heart, Artificial

Zardeneta, Gustavo, *University of Texas, San Antonio, Texas*, Fluorescence Measurements

Zelmanovic, David, *Bayer HealthCare LLC, Tarrytown, New York*, Differential Counts, Automated

Zhang, Min, *University of Washington, Seattle, Washington*, Biomaterials: Polymers

Zhang, Yi, *University of Buffalo, Buffalo, New York*, Cell Counters, Blood

Zhu, Xiaoyue, *University of Michigan, Ann Arbor, Michigan*, Microbioreactors

Ziaie, Babak, *Purdue University, W. Lafayette, Indiana*, Biotelemetry

Zielinski, Todd M., *Medtronic, Inc., Minneapolis, Minnesota*, Bioimpedance in Cardiovascular Medicine

Ziessman, Harvey A., *Johns Hopkins University*, Computed Tomography, Single Photon Emission

PREFACE

This six-volume work is an alphabetically organized compilation of almost 300 articles that describe critical aspects of medical devices and instrumentation.

It is comprehensive. The articles emphasize the contributions of engineering, physics, and computers to each of the general areas of anesthesiology, biomaterials, burns, cardiology, clinical chemistry, clinical engineering, communicative disorders, computers in medicine, critical care medicine, dermatology, dentistry, ear, nose, and throat, emergency medicine, endocrinology, gastroenterology, genetics, geriatrics, gynecology, hematology, heptology, internal medicine, medical physics, microbiology, nephrology, neurology, nutrition, obstetrics, oncology, ophthalmology, orthopedics, pain, pediatrics, peripheral vascular disease, pharmacology, physical therapy, psychiatry, pulmonary medicine, radiology, rehabilitation, surgery, tissue engineering, transducers, and urology.

The discipline is defined through the synthesis of the core knowledge from all the fields encompassed by the application of engineering, physics, and computers to problems in medicine. The articles focus not only on what is now useful but also on what is likely to be useful in future medical applications.

These volumes answer the question, “What are the branches of medicine and how does technology assist each of them?” rather than “What are the branches of technology and how could each be used in medicine?” To keep this work to a manageable length, the practice of medicine that is unassisted by devices, such as the use of drugs to treat disease, has been excluded.

The articles are accessible to the user; each benefits from brevity of condensation instead of what could easily have been a book-length work. The articles are designed not for peers, but rather for workers from related fields who wish to take a first look at what is important in the subject.

The articles are readable. They do not presume a detailed background in the subject, but are designed for any person with a scientific background and an interest in technology. Rather than attempting to teach the basics of physiology or Ohm’s law, the articles build on such basic concepts to show how the worlds of life science and physical science meld to produce improved systems. While the ideal reader might be a person with a Master’s degree in biomedical engineering or medical physics or an M.D. with a physical science undergraduate degree, much of the material will be of value to others with an interest in this growing field. High school students and hospital patients can skip over more technical areas and still gain much from the descriptive presentations.

The *Encyclopedia of Medical Devices and Instrumentation* is excellent for browsing and searching for those new divergent associations that may advance work in a peripheral field. While it can be used as a reference for facts, the articles are long enough that they can serve as an educational instrument and provide genuine understanding of a subject.

One can use this work just as one would use a dictionary, since the articles are arranged alphabetically by topic. Cross references assist the reader looking for subjects listed under slightly different names. The index at the end leads the reader to all articles containing pertinent information on any subject. Listed on pages xxi to xxx are all the abbreviations and acronyms used in the *Encyclopedia.* Because of the increasing use of SI units in all branches of science, these units are provided throughout the *Encyclopedia* articles as well as on pages xxxi to xxxv in the section on conversion factors and unit symbols.

I owe a great debt to the many people who have contributed to the creation of this work. At John Wiley & Sons, Encyclopedia Editor George Telecki provided the idea and guiding influence to launch the project. Sean Pidgeon was Editorial Director of the project. Assistant Editors Roseann Zappia, Sarah Harrington, and Surlan Murrell handled the myriad details of communication between publisher, editor, authors, and reviewers and stimulated authors and reviewers to meet necessary deadlines.

My own background has been in the electrical aspects of biomedical engineering. I was delighted to have the assistance of the editorial board to develop a comprehensive encyclopedia. David J. Beebe suggested cellular topics such as microfluidics. Jerry M. Calkins assisted in defining the chemically related subjects, such as anesthesiology. Michael R. Neuman suggested subjects related to sensors, such as in his own work—neonatology. Joon B. Park has written extensively on biomaterials and suggested related subjects. Edward S. Sternick provided many suggestions from medical physics. The Editorial Board was instrumental both in defining the list of subjects and in suggesting authors.

This second edition brings the field up to date. It is available on the web at http://www.mrw.interscience.wiley.com/emdi, where articles can be searched simultaneously to provide rapid and comprehensive information on all aspects of medical devices and instrumentation.

JOHN G. WEBSTER
University of Wisconsin, Madison

LIST OF ARTICLES

ALLOYS, SHAPE MEMORY
AMBULATORY MONITORING
ANALYTICAL METHODS, AUTOMATED
ANESTHESIA MACHINES
ANESTHESIA, COMPUTERS IN
ANGER CAMERA
ANORECTAL MANOMETRY
ARRHYTHMIA ANALYSIS, AUTOMATED
ARTERIES, ELASTIC PROPERTIES OF
AUDIOMETRY
BIOCOMPATIBILITY OF MATERIALS
BIOELECTRODES
BIOFEEDBACK
BIOHEAT TRANSFER
BIOIMPEDANCE IN CARDIOVASCULAR MEDICINE
BIOINFORMATICS
BIOMAGNETISM
BIOMATERIALS, ABSORBABLE
BIOMATERIALS: AN OVERVIEW
BIOMATERIALS: BIOCERAMICS
BIOMATERIALS: CARBON
BIOMATERIALS, CORROSION AND WEAR OF
BIOMATERIALS FOR DENTISTRY
BIOMATERIALS: POLYMERS
BIOMATERIALS, SURFACE PROPERTIES OF
BIOMATERIALS, TESTING AND STRUCTURAL PROPERTIES OF
BIOMATERIALS: TISSUE ENGINEERING AND SCAFFOLDS
BIOMECHANICS OF EXERCISE FITNESS
BIOMEDICAL ENGINEERING EDUCATION
BIOSURFACE ENGINEERING
BIOTELEMETRY
BLADDER DYSFUNCTION, NEUROSTIMULATION OF
BLIND AND VISUALLY IMPAIRED, ASSISTIVE TECHNOLOGY FOR
BLOOD COLLECTION AND PROCESSING
BLOOD GAS MEASUREMENTS
BLOOD PRESSURE MEASUREMENT
BLOOD PRESSURE, AUTOMATIC CONTROL OF
BLOOD RHEOLOGY
BLOOD, ARTIFICIAL
BONE AND TEETH, PROPERTIES OF
BONE CEMENT, ACRYLIC
BONE DENSITY MEASUREMENT
BONE UNUNITED FRACTURE AND SPINAL FUSION, ELECTRICAL TREATMENT OF
BORON NEUTRON CAPTURE THERAPY
BRACHYTHERAPY, HIGH DOSAGE RATE
BRACHYTHERAPY, INTRAVASCULAR
CAPACITIVE MICROSENSORS FOR BIOMEDICAL APPLICATIONS
CARDIAC OUTPUT, FICK TECHNIQUE FOR
CARDIAC OUTPUT, INDICATOR DILUTION MEASUREMENT OF
CARDIAC OUTPUT, THERMODILUTION MEASUREMENT OF
CARDIOPULMONARY RESUSCITATION
CARTILAGE AND MENISCUS, PROPERTIES OF
CELL COUNTERS, BLOOD
CELLULAR IMAGING
CHROMATOGRAPHY
CO_2 ELECTRODES
COBALT 60 UNITS FOR RADIOTHERAPY
COCHLEAR PROSTHESES
CODES AND REGULATIONS: MEDICAL DEVICES
CODES AND REGULATIONS: RADIATION
COLORIMETRY
COLPOSCOPY
COMMUNICATION DEVICES
COMMUNICATIVE DISORDERS, COMPUTER APPLICATIONS FOR
COMPUTED TOMOGRAPHY
COMPUTED TOMOGRAPHY SCREENING
COMPUTED TOMOGRAPHY SIMULATORS
COMPUTED TOMOGRAPHY, SINGLE PHOTON EMISSION
COMPUTER-ASSISTED DETECTION AND DIAGNOSIS
COMPUTERS IN THE BIOMEDICAL LABORATORY
CONTACT LENSES
CONTINUOUS POSITIVE AIRWAY PRESSURE
CONTRACEPTIVE DEVICES
CORONARY ANGIOPLASTY AND GUIDEWIRE DIAGNOSTICS
CRYOSURGERY
CUTANEOUS BLOOD FLOW, DOPPLER MEASUREMENT OF
CYSTIC FIBROSIS SWEAT TEST
CYTOLOGY, AUTOMATED
DEFIBRILLATORS
DIFFERENTIAL COUNTS, AUTOMATED
DIGITAL ANGIOGRAPHY
DNA SEQUENCE
DRUG DELIVERY SYSTEMS
DRUG INFUSION SYSTEMS
ECHOCARDIOGRAPHY AND DOPPLER ECHOCARDIOGRAPHY
ELECTROANALGESIA, SYSTEMIC
ELECTROCARDIOGRAPHY, COMPUTERS IN
ELECTROCONVULSIVE THERAPY
ELECTROENCEPHALOGRAPHY
ELECTROGASTROGRAM
ELECTROMYOGRAPHY
ELECTRONEUROGRAPHY
ELECTROPHORESIS

ELECTROPHYSIOLOGY
ELECTRORETINOGRAPHY
ELECTROSURGICAL UNIT (ESU)
ENDOSCOPES
ENGINEERED TISSUE
ENVIRONMENTAL CONTROL
EQUIPMENT ACQUISITION
EQUIPMENT MAINTENANCE, BIOMEDICAL
ESOPHAGEAL MANOMETRY
EVOKED POTENTIALS
EXERCISE STRESS TESTING
EYE MOVEMENT, MEASUREMENT TECHNIQUES FOR
FETAL MONITORING
FIBER OPTICS IN MEDICINE
FLAME ATOMIC EMISSION SPECTROMETRY AND ATOMIC ABSORPTION SPECTROMETRY
FLOWMETERS
FLUORESCENCE MEASUREMENTS
FUNCTIONAL ELECTRICAL STIMULATION
GAMMA KNIFE
GAS AND VACUUM SYSTEMS, CENTRALLY PIPED MEDICAL
GASTROINTESTINAL HEMORRHAGE
GLUCOSE SENSORS
HEART VALVE PROSTHESES
HEART VALVE PROSTHESES, IN VITRO FLOW DYNAMICS OF
HEART VALVES, PROSTHETIC
HEART, ARTIFICIAL
HEART–LUNG MACHINES
HEAT AND COLD, THERAPEUTIC
HEMODYNAMICS
HIGH FREQUENCY VENTILATION
HIP JOINTS, ARTIFICIAL
HOME HEALTH CARE DEVICES
HUMAN FACTORS IN MEDICAL DEVICES
HUMAN SPINE, BIOMECHANICS OF
HYDROCEPHALUS, TOOLS FOR DIAGNOSIS AND TREATMENT OF
HYPERBARIC MEDICINE
HYPERBARIC OXYGENATION
HYPERTHERMIA, INTERSTITIAL
HYPERTHERMIA, SYSTEMIC
HYPERTHERMIA, ULTRASONIC
IMAGE INTENSIFIERS AND FLUOROSCOPY
IMAGING DEVICES
IMMUNOLOGICALLY SENSITIVE FIELD-EFFECT TRANSISTORS
IMMUNOTHERAPY
IMPEDANCE PLETHYSMOGRAPHY
IMPEDANCE SPECTROSCOPY
INCUBATORS, INFANT
INTEGRATED CIRCUIT TEMPERATURE SENSOR
INTRAAORTIC BALLOON PUMP
INTRAUTERINE SURGICAL TECHNIQUES
IONIZING RADIATION, BIOLOGICAL EFFECTS OF
ION-SENSITIVE FIELD-EFFECT TRANSISTORS
JOINTS, BIOMECHANICS OF
LARYNGEAL PROSTHETIC DEVICES
LENSES, INTRAOCULAR
LIGAMENT AND TENDON, PROPERTIES OF
LINEAR VARIABLE DIFFERENTIAL TRANSFORMERS
LITHOTRIPSY
LIVER TRANSPLANTATION
LUNG SOUNDS
MAGNETIC RESONANCE IMAGING
MAMMOGRAPHY
MEDICAL EDUCATION, COMPUTERS IN
MEDICAL ENGINEERING SOCIETIES AND ORGANIZATIONS
MEDICAL GAS ANALYZERS
MEDICAL PHYSICS LITERATURE
MEDICAL RECORDS, COMPUTERS IN
MICROARRAYS
MICROBIAL DETECTION SYSTEMS
MICROBIOREACTORS
MICRODIALYSIS SAMPLING
MICROFLUIDICS
MICROPOWER FOR MEDICAL APPLICATIONS
MICROSCOPY AND SPECTROSCOPY, NEAR-FIELD
MICROSCOPY, CONFOCAL
MICROSCOPY, ELECTRON
MICROSCOPY, FLUORESCENCE
MICROSCOPY, SCANNING FORCE
MICROSCOPY, SCANNING TUNNELING
MICROSURGERY
MINIMALLY INVASIVE SURGERY
MOBILITY AIDS
MONITORING IN ANESTHESIA
MONITORING, HEMODYNAMIC
MONITORING, INTRACRANIAL PRESSURE
MONITORING, UMBILICAL ARTERY AND VEIN
MONOCLONAL ANTIBODIES
NANOPARTICLES
NEONATAL MONITORING
NEUROLOGICAL MONITORS
NEUTRON ACTIVATION ANALYSIS
NEUTRON BEAM THERAPY
NONIONIZING RADIATION, BIOLOGICAL EFFECTS OF
NUCLEAR MAGNETIC RESONANCE SPECTROSCOPY
NUCLEAR MEDICINE INSTRUMENTATION
NUCLEAR MEDICINE, COMPUTERS IN
NUTRITION, PARENTERAL
OCULAR FUNDUS REFLECTOMETRY
OCULAR MOTILITY RECORDING AND NYSTAGMUS
OFFICE AUTOMATION SYSTEMS
OPTICAL SENSORS
OPTICAL TWEEZERS
ORTHOPEDIC DEVICES, MATERIALS AND DESIGN FOR
ORTHOPEDICS, PROSTHESIS FIXATION FOR
OXYGEN ANALYZERS
OXYGEN MONITORING
PACEMAKERS
PANCREAS, ARTIFICIAL
PERIPHERAL VASCULAR NONINVASIVE MEASUREMENTS
PHANTOM MATERIALS IN RADIOLOGY
PHARMACOKINETICS AND PHARMACODYNAMICS
PHONOCARDIOGRAPHY
PHOTOGRAPHY, MEDICAL
PHYSIOLOGICAL SYSTEMS MODELING

PICTURE ARCHIVING AND COMMUNICATION SYSTEMS
PIEZOELECTRIC SENSORS
PNEUMOTACHOMETERS
POLYMERASE CHAIN REACTION
POLYMERIC MATERIALS
POROUS MATERIALS FOR BIOLOGICAL APPLICATIONS
POSITRON EMISSION TOMOGRAPHY
PROSTATE SEED IMPLANTS
PULMONARY PHYSIOLOGY
QUALITY-OF-LIFE MEASURES, CLINICAL SIGNIFICANCE OF
RADIATION DOSE PLANNING, COMPUTER-AIDED
RADIATION DOSIMETRY FOR ONCOLOGY
RADIATION DOSIMETRY, THREE-DIMENSIONAL
RADIATION PROTECTION INSTRUMENTATION
RADIATION THERAPY, INTENSITY MODULATED
RADIATION THERAPY SIMULATOR
RADIATION THERAPY TREATMENT PLANNING, MONTE CARLO CALCULATIONS IN
RADIATION THERAPY, QUALITY ASSURANCE IN
RADIOLOGY INFORMATION SYSTEMS
RADIONUCLIDE PRODUCTION AND RADIOACTIVE DECAY
RADIOPHARMACEUTICAL DOSIMETRY
RADIOSURGERY, STEREOTACTIC
RADIOTHERAPY ACCESSORIES
RADIOTHERAPY, HEAVY ION
RADIOTHERAPY, INTRAOPERATIVE
RADIOTHERAPY, THREE-DIMENSIONAL CONFORMAL
RADIOTHERAPY TREATMENT PLANNING, OPTIMIZATION OF
RECORDERS, GRAPHIC
REHABILITATION AND MUSCLE TESTING
REHABILITATION, COMPUTERS IN COGNITIVE
REHABILITATION, ORTHOTICS IN
RESIN-BASED COMPOSITES
RESPIRATORY MECHANICS AND GAS EXCHANGE
SAFETY PROGRAM, HOSPITAL
SCOLIOSIS, BIOMECHANICS OF
SCREEN-FILM SYSTEMS
SEXUAL INSTRUMENTATION
SHOCK, TREATMENT OF
SKIN SUBSTITUTE FOR BURNS, BIOACTIVE
SKIN TISSUE ENGINEERING FOR REGENERATION
SKIN, BIOMECHANICS OF
SLEEP LABORATORY
SLEEP STUDIES, COMPUTER ANALYSIS OF
SPINAL CORD STIMULATION
SPINAL IMPLANTS
STATISTICAL METHODS
STEREOTACTIC SURGERY
STERILIZATION OF BIOLOGIC SCAFFOLD MATERIALS
STRAIN GAGES
TACTILE STIMULATION
TELERADIOLOGY
TEMPERATURE MONITORING
THERMISTORS
THERMOCOUPLES
THERMOGRAPHY
THERMOMETRY
TISSUE ABLATION
TISSUE ENGINEERING
TOMOTHERAPY
TONOMETRY, ARTERIAL
TOOTH AND JAW, BIOMECHANICS OF
TRACER KINETICS
TRANSCUTANEOUS ELECTRICAL NERVE STIMULATION (TENS)
ULTRASONIC IMAGING
ULTRAVIOLET RADIATION IN MEDICINE
VASCULAR GRAFT PROSTHESIS
VENTILATORS, ACUTE MEDICAL CARE
VENTILATORY MONITORING
VISUAL FIELD TESTING
VISUAL PROSTHESES
X-RAY EQUIPMENT DESIGN
X-RAY QUALITY CONTROL PROGRAM
X-RAY THERAPY EQUIPMENT, LOW AND MEDIUM ENERGY
X-RAYS: INTERACTION WITH MATTER
X-RAYS, PRODUCTION OF

ABBREVIATIONS AND ACRONYMS

AAMI	Association for the Advancement of Medical Instrumentation
AAPM	American Association of Physicists in Medicine
ABC	Automatic brightness control
ABET	Accreditation board for engineering training
ABG	Arterial blood gases
ABLB	Alternative binaural loudness balance
ABS	Acrylonitrile–butadiene–styrene
ac	Alternating current
AC	Abdominal circumference; Affinity chromatography
ACA	Automated clinical analyzer
ACES	Augmentative communication evaluation system
ACL	Anterior chamber lens
ACLS	Advanced cardiac life support
ACOG	American College of Obstetrics and Gynecology
ACR	American College of Radiology
ACS	American Cancer Society; American College of Surgeons
A/D	Analog-to-digital
ADC	Agar diffusion chambers; Analog-to-digital converter
ADCC	Antibody-dependent cellular cytotoxicity
ADCL	Accredited Dosimetry Calibration Laboratories
ADP	Adenosine diphosphate
A-D-T	Admission, discharge, and transfer
AE	Anion exchange; Auxiliary electrode
AEA	Articulation error analysis
AEB	Activation energy barrier
AEC	Automatic exposure control
AED	Automatic external defibrillator
AEMB	Alliance for Engineering in Medicine and Biology
AES	Auger electron spectroscopy
AESC	American Engineering Standards Committee
AET	Automatic exposure termination
AFO	Ankle-foot orthosis
AGC	Automatic gain control
AHA	American Heart Association
AI	Arterial insufficiency
AICD	Automatic implantable cardiac defibrillator
AID	Agency for International Development
AIDS	Acquired immune deficiency syndrome
AL	Anterior leaflet
ALG	Antilymphocyte globulin
ALS	Advanced life support; Amyotropic lateral sclerosis
ALT	Alanine aminotransferase
ALU	Arithmetic and logic unit
AM	Amplitude modulation
AMA	American Medical Association
amu	Atomic mass units
ANOVA	Analysis of variance
ANSI	American National Standards Institute
AP	Action potential; Alternative pathway; Anteroposterior
APD	Anterioposterior diameter
APL	Adjustable pressure limiting valve; Applied Physics Laboratory
APR	Anatomically programmed radiography
AR	Amplitude reduction; Aortic regurgitation; Autoregressive
Ara-C	Arabinosylcytosine
ARD	Absorption rate density
ARDS	Adult respiratory distress syndrome
ARGUS	Arrhythmia guard system
ARMA	Autoregressive-moving-average model
ARMAX	Autoregressive-moving-average model with external inputs
AS	Aortic stenosis
ASA	American Standards Association
ASCII	American standard code for information interchange
ASD	Antisiphon device
ASHE	American Society for Hospital Engineering
ASTM	American Society for Testing and Materials
AT	Adenosine-thiamide; Anaerobic threshold; Antithrombin
ATA	Atmosphere absolute
ATLS	Advanced trauma life support
ATN	Acute tubular necrosis
ATP	Adenosine triphosphate
ATPD	Ambient temperature pressure dry
ATPS	Ambient temperature pressure saturated
ATR	Attenuated total reflection
AUC	Area under curve
AUMC	Area under moment curve
AV	Atrioventricular
AZT	Azido thymidine
BA	Biliary atresia
BAEP	Brainstem auditory evoked potential
BAPN	Beta-amino-proprionitryl
BAS	Boston anesthesis system
BASO	Basophil
BB	Buffer base
BBT	Basal body temperature

BCC	Body-centered cubic
BCD	Binary-coded decimal
BCG	Ballistocardiogram
BCLS	Basic cardiac life support
BCRU	British Commitee on Radiation Units and Measurements
BDI	Beck depression inventory
BE	Base excess; Binding energy
BET	Brunauer, Emmett, and Teller methods
BH	His bundle
BI	Biological indicators
BIH	Beth Israel Hospital
BIPM	International Bureau of Weights and Measurements
BJT	Bipolar junction transistor
BMDP	Biomedical Programs
BME	Biomedical engineering
BMET	Biomedical equipment technician
BMO	Biomechanically optimized
BMR	Basal metabolic rate
BOL	Beginning of life
BP	Bereitschafts potential; Break point
BR	Polybutadiene
BRM	Biological response modifier
BRS	Bibliographic retrieval services
BSS	Balanced salt solution
BTG	Beta thromboglobulin
BTPS	Body temperature pressure saturated
BUN	Blood urea nitrogen
BW	Body weight
CA	Conductive adhesives
CABG	Coronary artery by-pass grafting
CAD/CAM	Computer-aided design/computer-aided manufacturing
CAD/D	Computer-aided drafting and design
CADD	Central axis depth dose
CAI	Computer assisted instruction; Computer-aided instruction
CAM	Computer-assisted management
cAMP	Cyclic AMP
CAPD	Continuous ambulatory peritoneal dialysis
CAPP	Child amputee prosthetic project
CAT	Computerized axial tomography
CATS	Computer-assisted teaching system; Computerized aphasia treatment system
CAVH	Continuous arteriovenous hemofiltration
CB	Conjugated bilirubin; Coulomb barrier
CBC	Complete blood count
CBF	Cerebral blood flow
CBM	Computer-based management
CBV	Cerebral blood volume
CC	Closing capacity
CCC	Computer Curriculum Company
CCD	Charge-coupled device
CCE	Capacitance contact electrode
CCF	Cross-correlation function
CCL	Cardiac catheterization laboratory
CCM	Critical care medical services
CCPD	Continuous cycling peritoneal dialysis
CCTV	Closed circuit television system
CCU	Coronary care unit; Critical care unit
CD	Current density
CDR	Complimentary determining region
CDRH	Center for Devices and Radiological Health
CEA	Carcinoembryonic antigen
CF	Conversion factor; Cystic fibrosis
CFC	Continuous flow cytometer
CFR	Code of Federal Regulations
CFU	Colony forming units
CGA	Compressed Gas Association
CGPM	General Conference on Weights and Measures
CHO	Carbohydrate
CHO	Chinese hamster ovary
CI	Combination index
CICU	Cardiac intensive care unit
CIF	Contrast improvement factor
CIN	Cervical intraepithelial neoplasia
CK	Creatine kinase
CLAV	Clavicle
CLSA	Computerized language sample analysis
CM	Cardiomyopathy; Code modulation
CMAD	Computer managed articulation diagnosis
CMI	Computer-managed instruction
CMRR	Common mode rejection ratio
CMV	Conventional mechanical ventilation; Cytomegalovirus
CNS	Central nervous system
CNV	Contingent negative variation
CO	Carbon monoxide; Cardiac output
COBAS	Comprehensive Bio-Analysis System
COPD	Chronic obstructive pulmonary disease
COR	Center of rotation
CP	Cerebral palsy; Closing pressure; Creatine phosphate
CPB	Cardiopulmonary bypass
CPET	Cardiac pacemaker electrode tips
CPM	Computerized probe measurements
CPP	Cerebral perfusion pressure; Cryoprecipitated plasma
CPR	Cardiopulmonary resuscitation
cps	Cycles per second
CPU	Central Processing unit
CR	Center of resistance; Conditioned response; Conductive rubber; Creatinine
CRBB	Complete right bundle branch block
CRD	Completely randomized design
CRL	Crown rump length
CRT	Cathode ray tube
CS	Conditioned stimulus; Contrast scale; Crown seat
CSA	Compressed spectral array
CSF	Cerebrospinal fluid
CSI	Chemical shift imaging
CSM	Chemically sensitive membrane
CT	Computed tomography; Computerized tomography
CTI	Cumulative toxicity response index
CV	Closing volume

C.V.	Coefficient of variation
CVA	Cerebral vascular accident
CVP	Central venous pressure
CVR	Cardiovascular resistance
CW	Continuous wave
CWE	Coated wire electrodes
CWRU	Case Western Reserve University
DAC	Digital-to-analog converter
DAS	Data acquisition system
dB	Decibel
DB	Direct body
DBMS	Data base management system
DBS	Deep brain stimulation
dc	Direct current
DCCT	Diabetes control and complications trial
DCP	Distal cavity pressure
DCS	Dorsal column stimulation
DDC	Deck decompression chamber
DDS	Deep diving system
DE	Dispersive electrode
DEN	Device experience network
DERS	Drug exception ordering system
DES	Diffuse esophageal spasm
d.f.	Distribution function
DHCP	Distributed Hospital Computer Program
DHE	Dihematoporphyrin ether
DHEW	Department of Health Education and Welfare
DHHS	Department of Health and Human Services
DHT	Duration of hypothermia
DI	Deionized water
DIC	Displacement current
DIS	Diagnostic interview schedule
DL	Double layer
DLI	Difference lumen for intensity
DM	Delta modulation
DME	Dropping mercury electrode
DN	Donation number
DNA	Deoxyribonucleic acid
DOF	Degree of freedom
DOS	Drug ordering system
DOT-NHTSA	Department of Transportation Highway Traffic Safety Administration
DPB	Differential pencil beam
DPG	Diphosphoglycerate
DQE	Detection quantum efficiency
DRESS	Depth-resolved surface coil spectroscopy
DRG	Diagnosis-related group
DSA	Digital subtraction angiography
DSAR	Differential scatter-air ratio
DSB	Double strand breaks
DSC	Differential scanning calorimetry
D-T	Deuterium-on-tritium
DTA	Differential thermal analysis
d.u.	Density unit
DUR	Duration
DVT	Deep venous thrombosis
EA	Esophageal accelerogram
EB	Electron beam
EBCDIC	Extended binary code decimal interchange code
EBS	Early burn scar
EBV	Epstein–Barr Virus
EC	Ethyl cellulose
ECC	Emergency cardiac care; Extracorporeal circulation
ECCE	Extracapsular cataract extinction
ECD	Electron capture detector
ECG	Electrocardiogram
ECM	Electrochemical machining
ECMO	Extracorporeal membrane oxygenation
ECOD	Extracranial cerebrovascular occlusive disease
ECRI	Emergency Care Research Institute
ECS	Exner's Comprehensive System
ECT	Electroconvulsive shock therapy; Electroconvulsive therapy; Emission computed tomography
EDD	Estimated date of delivery
EDP	Aortic end diastolic pressure
EDTA	Ethylenediaminetetraacetic acid
EDX	Energy dispersive X-ray analysis
EEG	Electroencephalogram
EEI	Electrode electrolyte interface
EELV	End-expiratory lung volume
EER	Electrically evoked response
EF	Ejection fraction
EF	Electric field; Evoked magnetic fields
EFA	Estimated fetal age
EGF	Epidermal growth factor
EGG	Electrogastrogram
EIA	Enzyme immunoassay
EIU	Electrode impedance unbalance
ELF	Extra low frequency
ELGON	Electrical goniometer
ELISA	Enzyme-linked immunosorbent assay
ELS	Energy loss spectroscopy
ELV	Equivalent lung volume
EM	Electromagnetic
EMBS	Engineering in Medicine and Biology Society
emf	Electromotive force
EMG	Electromyogram
EMGE	Integrated electromyogram
EMI	Electromagnetic interference
EMS	Emergency medical services
EMT	Emergency medical technician
ENT	Ear, nose, and throat
EO	Elbow orthosis
EOG	Electrooculography
EOL	End of life
EOS	Eosinophil
EP	Elastoplastic; Evoked potentiate
EPA	Environmental protection agency
ER	Evoked response
ERCP	Endoscopic retrograde cholangiopancreatography
ERG	Electron radiography; Electroretinogram
ERMF	Event-related magnetic field
ERP	Event-related potential
ERV	Expiratory reserve volume

ESCA	Electron spectroscopy for chemical analysis
ESI	Electrode skin impedance
ESRD	End-stage renal disease
esu	Electrostatic unit
ESU	Electrosurgical unit
ESWL	Extracorporeal shock wave lithotripsy
ETO, Eto	Ethylene oxide
ETT	Exercise tolerance testing
EVA	Ethylene vinyl acetate
EVR	Endocardial viability ratio
EW	Extended wear
FAD	Flavin adenine dinucleotide
FARA	Flexible automation random analysis
FBD	Fetal biparietal diameter
FBS	Fetal bovine serum
fcc	Face centered cubic
FCC	Federal Communications Commission
Fct	Fluorocrit
FDA	Food and Drug Administration
FDCA	Food, Drug, and Cosmetic Act
FE	Finite element
FECG	Fetal electrocardiogram
FEF	Forced expiratory flow
FEL	Free electron lasers
FEM	Finite element method
FEP	Fluorinated ethylene propylene
FES	Functional electrical stimulation
FET	Field-effect transistor
FEV	Forced expiratory volume
FFD	Focal spot to film distance
FFT	Fast Fourier transform
FGF	Fresh gas flow
FHR	Fetal heart rate
FIC	Forced inspiratory capacity
FID	Flame ionization detector; Free-induction decay
FIFO	First-in-first-out
FITC	Fluorescent indicator tagged polymer
FL	Femur length
FM	Frequency modulation
FNS	Functional neuromuscular stimulation
FO	Foramen ovale
FO-CRT	Fiber optics cathode ray tube
FP	Fluorescence polarization
FPA	Fibrinopeptide A
FR	Federal Register
FRC	Federal Radiation Council; Functional residual capacity
FSD	Focus-to-surface distance
FTD	Focal spot to tissue-plane distance
FTIR	Fourier transform infrared
FTMS	Fourier transform mass spectrometer
FU	Fluorouracil
FUDR	Floxuridine
FVC	Forced vital capacity
FWHM	Full width at half maximum
FWTM	Full width at tenth maximum
GABA	Gamma amino buteric acid
GAG	Glycosaminoglycan
GBE	Gas-bearing electrodynamometer
GC	Gas chromatography; Guanine-cytosine
GDT	Gas discharge tube
GFR	Glomerular filtration rate
GHb	Glycosylated hemoglobin
GI	Gastrointestinal
GLC	Gas–liquid chromatography
GMV	General minimum variance
GNP	Gross national product
GPC	Giant papillary conjunctivitis
GPH	Gas-permeable hard
GPH-EW	Gas-permeable hard lens extended wear
GPO	Government Printing Office
GSC	Gas-solid chromatography
GSR	Galvanic skin response
GSWD	Generalized spike-wave discharge
HA	Hydroxyapatite
HAM	Helical axis of motion
Hb	Hemoglobin
HBE	His bundle electrogram
HBO	Hyperbaric oxygenation
HC	Head circumference
HCA	Hypothermic circulatory arrest
HCFA	Health care financing administration
HCL	Harvard Cyclotron Laboratory
hcp	Hexagonal close-packed
HCP	Half cell potential
HDPE	High density polyethylene
HECS	Hospital Equipment Control System
HEMS	Hospital Engineering Management System
HEPA	High efficiency particulate air filter
HES	Hydroxyethylstarch
HETP	Height equivalent to a theoretical plate
HF	High-frequency; Heating factor
HFCWO	High-frequency chest wall oscillation
HFER	High-frequency electromagnetic radiation
HFJV	High-frequency jet ventilation
HFO	High-frequency oscillator
HFOV	High-frequency oscillatory ventilation
HFPPV	High-frequency positive pressure ventilation
HFV	High-frequency ventilation
HHS	Department of Health and Human Services
HIBC	Health industry bar code
HIMA	Health Industry Manufacturers Association
HIP	Hydrostatic indifference point
HIS	Hospital information system
HK	Hexokinase
HL	Hearing level
HMBA	Hexamethylene bisacetamide
HMO	Health maintenance organization
HMWPE	High-molecular-weight polyethylene
HOL	Higher-order languages
HP	Heating factor; His-Purkinje
HpD	Hematoporphyrin derivative
HPLC	High-performance liquid chromatography
HPNS	High-pressure neurological syndrome
HPS	His-Purkinje system
HPX	High peroxidase activity

HR	Heart rate; High-resolution
HRNB	Halstead-Reitan Neuropsychological Battery
H/S	Hard/soft
HSA	Human serum albumin
HSG	Hysterosalpingogram
HTCA	Human tumor cloning assay
HTLV	Human T cell lymphotrophic virus
HU	Heat unit; Houndsfield units; Hydroxyurea
HVL	Half value layer
HVR	Hypoxic ventilatory response
HVT	Half-value thickness
IA	Image intensifier assembly; Inominate artery
IABP	Intraaortic balloon pumping
IAEA	International Atomic Energy Agency
IAIMS	Integrated Academic Information Management System
IASP	International Association for the Study of Pain
IC	Inspiratory capacity; Integrated circuit
ICCE	Intracapsular cataract extraction
ICD	Intracervical device
ICDA	International classification of diagnoses
ICL	Ms-clip lens
ICP	Inductively coupled plasma; Intracranial pressure
ICPA	Intracranial pressure amplitude
ICRP	International Commission on Radiological Protection
ICRU	International Commission on Radiological Units and Measurements
ICU	Intensive care unit
ID	Inside diameter
IDDM	Insulin dependent diabetes mellitus
IDE	Investigational device exemption
IDI	Index of inspired gas distribution
I:E	Inspiratory: expiratory
IEC	International Electrotechnical Commission; Ion-exchange chromatography
IEEE	Institute of Electrical and Electronics Engineers
IEP	Individual educational program
BETS	Inelastic electron tunneling spectroscopy
IF	Immunofluorescent
IFIP	International Federation for Information Processing
IFMBE	International Federation for Medical and Biological Engineering
IGFET	Insulated-gate field-effect transistor
IgG	Immunoglobulin G
IgM	Immunoglobulin M
IHP	Inner Helmholtz plane
IHSS	Idiopathic hypertrophic subaortic stenosis
II	Image intensifier
IIIES	Image intensifier input-exposure sensitivity
IM	Intramuscular
IMFET	Immunologically sensitive field-effect transistor
IMIA	International Medical Informatics Association
IMS	Information management system
IMV	Intermittent mandatory ventilation
INF	Interferon
IOL	Intraocular lens
IPC	Ion-pair chromatography
IPD	Intermittent peritoneal dialysis
IPG	Impedance plethysmography
IPI	Interpulse interval
IPPB	Intermittent positive pressure breathing
IPTS	International practical temperature scale
IR	Polyisoprene rubber
IRB	Institutional Review Board
IRBBB	Incomplete right bundle branch block
IRPA	International Radiation Protection Association
IRRAS	Infrared reflection-absorption spectroscopy
IRRS	Infrared reflection spectroscopy
IRS	Internal reflection spectroscopy
IRV	Inspiratory reserve capacity
IS	Image size; Ion-selective
ISC	Infant skin servo control
ISDA	Instantaneous screw displacement axis
ISE	Ion-selective electrode
ISFET	Ion-sensitive field effect transistor
ISIT	Intensified silicon-intensified target tube
ISO	International Organization for Standardization
ISS	Ion scattering spectroscopy
IT	Intrathecal
ITEP	Institute of Theoretical and Experimental Physics
ITEPI	Instantaneous trailing edge pulse impedance
ITLC	Instant thin-layer chromatography
IUD	Intrauterine device
IV	Intravenous
IVC	Inferior vena cava
IVP	Intraventricular pressure
JCAH	Joint Commission on the Accreditation of Hospitals
JND	Just noticeable difference
JRP	Joint replacement prosthesis
KB	Kent bundle
Kerma	Kinetic energy released in unit mass
KO	Knee orthosis
KPM	Kilopond meter
KRPB	Krebs-Ringer physiological buffer
LA	Left arm; Left atrium
LAD	Left anterior descending; Left axis deviation
LAE	Left atrial enlargement
LAK	Lymphokine activated killer
LAL	Limulus amoebocyte lysate
LAN	Local area network
LAP	Left atrial pressure
LAT	Left anterior temporalis
LBBB	Left bundle branch block
LC	Left carotid; Liquid chromatography

LCC	Left coronary cusp
LCD	Liquid crystal display
LDA	Laser Doppler anemometry
LDF	Laser Doppler flowmetry
LDH	Lactate dehydrogenase
LDPE	Low density polyethylene
LEBS	Low-energy brief stimulus
LED	Light-emitting diode
LEED	Low energy electron diffraction
LES	Lower esophageal sphincter
LESP	Lower esophageal sphincter pressure
LET	Linear energy transfer
LF	Low frequency
LH	Luteinizing hormone
LHT	Local hyperthermia
LL	Left leg
LLDPE	Linear low density polyethylene
LLPC	Liquid-liquid partition chromatography
LLW	Low-level waste
LM	Left masseter
LNNB	Luria-Nebraska Neuropsychological Battery
LOS	Length of stay
LP	Late potential; Lumboperitoneal
LPA	Left pulmonary artery
LPC	Linear predictive coding
LPT	Left posterior temporalis
LPV	Left pulmonary veins
LRP	Late receptor potential
LS	Left subclavian
LSC	Liquid-solid adsorption chromatography
LSI	Large scale integrated
LSV	Low-amplitude shear-wave viscoelastometry
LTI	Low temperature isotropic
LUC	Large unstained cells
LV	Left ventricle
LVAD	Left ventricular assist device
LVDT	Linear variable differential transformer
LVEP	Left ventricular ejection period
LVET	Left ventricular ejection time
LVH	Left ventricular hypertrophy
LYMPH	Lymphocyte
MAA	Macroaggregated albumin
MAC	Minimal auditory capabilities
MAN	Manubrium
MAP	Mean airway pressure; Mean arterial pressure
MAST	Military assistance to safety and traffic
MBA	Monoclonal antibody
MBV	Maximum breathing ventilation
MBX	Monitoring branch exchange
MCA	Methyl cryanoacrylate
MCG	Magnetocardiogram
MCI	Motion Control Incorporated
MCMI	Millon Clinical Multiaxial Inventory
MCT	Microcatheter transducer
MCV	Mean corpuscular volume
MDC	Medical diagnostic categories
MDI	Diphenylmethane diisocyanate; Medical Database Informatics

MDP	Mean diastolic aortic pressure
MDR	Medical device reporting
MDS	Multidimensional scaling
ME	Myoelectric
MED	Minimum erythema dose
MEDPAR	Medicare provider analysis and review
MEFV	Maximal expiratory flow volume
MEG	Magnetoencephalography
MeSH	Medline subject heading
METS	Metabolic equivalents
MF	Melamine-formaldehyde
MFP	Magnetic field potential
MGH	Massachusetts General Hospital
MHV	Magnetic heart vector
MI	Myocardial infarction
MIC	Minimum inhibitory concentration
MIFR	Maximum inspiratory flow rate
MINET	Medical Information Network
MIR	Mercury-in-rubber
MIS	Medical information system; Metal-insulator-semiconductor
MIT	Massachusetts Institute of Technology
MIT/BIH	Massachusetts Institute of Technology/ Beth Israel Hospital
MMA	Manual metal arc welding
MMA	Methyl methacrylate
MMECT	Multiple-monitored ECT
MMFR	Maximum midexpiratory flow rate
mm Hg	Millimeters of mercury
MMPI	Minnesota Multiphasic Personality Inventory
MMSE	Minimum mean square error
MO	Membrane oxygenation
MONO	Monocyte
MOSFET	Metal oxide silicon field-effect transistor
MP	Mercaptopurine; Metacarpal-phalangeal
MPD	Maximal permissible dose
MR	Magnetic resonance
MRG	Magnetoretinogram
MRI	Magnetic resonance imaging
MRS	Magnetic resonance spectroscopy
MRT	Mean residence time
MS	Mild steel; Multiple sclerosis
MSR	Magnetically shielded room
MTBF	Mean time between failure
MTF	Modulation transfer function
MTTR	Mean time to repair
MTX	Methotroxate
MUA	Motor unit activity
MUAP	Motor unit action potential
MUAPT	Motor unit action potential train
MUMPI	Missouri University Multi-Plane Imager
MUMPS	Massachusetts General Hospital utility multiuser programming system
MV	Mitral valve
MVO_2	Maximal oxygen uptake
MVTR	Moisture vapor transmission rate
MVV	Maximum voluntary ventilation
MW	Molecular weight

NAA	Neutron activation analysis
NAD	Nicotinamide adenine dinucleotide
NADH	Nicotinamide adenine dinucleotide, reduced form
NADP	Nicotinamide adenine dinucleotide phosphate
NAF	Neutrophil activating factor
NARM	Naturally occurring and accelerator-produced radioactive materials
NBB	Normal buffer base
NBD	Neuromuscular blocking drugs
N-BPC	Normal bonded phase chromatography
NBS	National Bureau of Standards
NCC	Noncoronary cusp
NCCLS	National Committee for Clinical Laboratory Standards; National Committee on Clinical Laboratory Standards
NCRP	National Council on Radiation Protection
NCT	Neutron capture theory
NEEP	Negative end-expiratory pressure
NEMA	National Electrical Manufacturers Association
NEMR	Nonionizing electromagnetic radiation
NEQ	Noise equivalent quanta
NET	Norethisterone
NEUT	Neutrophil
NFPA	National Fire Protection Association
NH	Neonatal hepatitis
NHE	Normal hydrogen electrode
NHLBI	National Heart, Lung, and Blood Institute
NIR	Nonionizing radiation
NIRS	National Institute for Radiologic Science
NK	Natural killer
NMJ	Neuromuscular junction
NMOS	N-type metal oxide silicon
NMR	Nuclear magnetic resonance
NMS	Neuromuscular stimulation
NPH	Normal pressure hydrocephalus
NPL	National Physical Laboratory
NR	Natural rubber
NRC	Nuclear Regulatory Commission
NRZ	Non-return-to-zero
NTC	Negative temperature coefficient
NTIS	National Technical Information Service
NVT	Neutrons versus time
NYHA	New York Heart Association
ob/gyn	Obstetrics and gynecology
OCR	Off-center ratio; Optical character recognition
OCV	Open circuit voltage
OD	Optical density; Outside diameter
ODC	Oxyhemoglobin dissociation curve
ODT	Oxygen delivery truck
ODU	Optical density unit
OER	Oxygen enhancement ratio
OFD	Object to film distance; Occiputo-frontal diameter
OHL	Outer Helmholtz layer
OHP	Outer Helmholtz plane
OIH	Orthoiodohippurate

OPG	Ocular pneumoplethysmography
OR	Operating room
OS	Object of known size; Operating system
OTC	Over the counter
OV	Offset voltage
PA	Posterioanterior; Pulmonary artery; Pulse amplitude
PACS	Picture archiving and communications systems
PAD	Primary afferent depolarization
PAM	Pulse amplitude modulation
PAN	Polyacrylonitrile
PAP	Pulmonary artery pressure
PAR	Photoactivation ratio
PARFR	Program for Applied Research on Fertility Regulation
PARR	Poetanesthesia recovery room
PAS	Photoacoustic spectroscopy
PASG	Pneumatic antishock garment
PBI	Penile brachial index
PBL	Positive beam limitation
PBT	Polybutylene terephthalate
PC	Paper chromatography; Personal computer; Polycarbonate
PCA	Patient controlled analgesia; Principal components factor analysis
PCG	Phonocardiogram
PCI	Physiological cost index
PCL	Polycaprolactone; Posterior chamber lens
PCR	Percent regurgitation
PCRC	Perinatal Clinical Research Center
PCS	Patient care system
PCT	Porphyria cutanea tarda
PCWP	Pulmonary capillary wedge pressure
PD	Peritoneal dialysis; Poly-p-dioxanone; Potential difference; Proportional and derivative
PDD	Percent depth dose; Perinatal Data Directory
PDE	Pregelled disposable electrodes
p.d.f.	Probability density function
PDL	Periodontal ligament
PDM	Pulse duration modulation
PDMSX	Polydimethyl siloxane
PDS	Polydioxanone
PE	Polyethylene
PEEP	Positive end-expiratory pressure
PEFR	Peak expiratory now rate
PEN	Parenteral and enteral nutrition
PEP	Preejection period
PEPPER	Programs examine phonetic find phonological evaluation records
PET	Polyethylene terephthalate; Positron-emission tomography
PEU	Polyetherurethane
PF	Platelet factor
PFA	Phosphonoformic add
PFC	Petrofluorochemical
PFT	Pulmonary function testing
PG	Polyglycolide; Propylene glycol

PGA	Polyglycolic add
PHA	Phytohemagglutinin; Pulse-height analyzer
PHEMA	Poly-2-hydroxyethyl methacrylate
PI	Propidium iodide
PID	Pelvic inflammatory disease; Proportional/integral/derivative
PIP	Peak inspiratory pressure
PL	Posterior leaflet
PLA	Polylactic acid
PLATO	Program Logic for Automated Teaching Operations
PLD	Potentially lethal damage
PLED	Periodic latoralized epileptiform discharge
PLT	Platelet
PM	Papillary muscles; Preventive maintenance
PMA	Polymethyl acrylate
p.m.f.	Probability mass function
PMMA	Polymethyl methacrylate
PMOS	P-type metal oxide silicon
PMP	Patient management problem; Poly(4-methylpentane)
PMT	Photomultiplier tube
PO	Per os
Po_2	Partial pressure of oxygen
POBT	Polyoxybutylene terephthalate
POM	Polyoxymethylene
POMC	Patient order management and communication system
POPRAS	Problem Oriented Perinatal Risk Assessment System
PP	Perfusion pressure; Polyproplyene; Postprandial (after meals)
PPA	Phonemic process analysis
PPF	Plasma protein fraction
PPM	Pulse position modulation
PPSFH	Polymerized phyridoxalated stroma-free hemoglobin
PR	Pattern recognition; Pulse rate
PRBS	Pseudo-random binary signals
PRP	Pulse repetition frequency
PRO	Professional review organization
PROM	Programmable read only memory
PS	Polystyrene
PSA	Pressure-sensitive adhesive
PSF	Point spread function
PSI	Primary skin irritation
PSP	Postsynaptic potential
PSR	Proton spin resonance
PSS	Progressive systemic sclerosis
PT	Plasma thromboplastin
PTB	Patellar tendon bearing orthosis
PTC	Plasma thromboplastin component; Positive temperature coefficient; Pressurized personal transfer capsule
PTCA	Percutaneous transluminal coronary angioplasty
PTFE	Polytetrafluoroethylene
PTT	Partial thromboplastin time
PUL	Percutaneous ultrasonic lithotripsy
PURA	Prolonged ultraviolet-A radiation
PUVA	Psoralens and longwave ultraviolet light photochemotherapy
P/V	Pressure/volume
PVC	Polyvinyl chloride; Premature ventricular contraction
PVI	Pressure–volume index
PW	Pulse wave; Pulse width
PWM	Pulse width modulation
PXE	Pseudo-xanthoma elasticum
QA	Quality assurance
QC	Quality control
R-BPC	Reverse bonded phase chromatography
R/S	Radiopaque-spherical
RA	Respiratory amplitude; Right arm
RAD	Right axis deviation
RAE	Right atrial enlargement
RAM	Random access memory
RAP	Right atrial pressure
RAT	Right anterior temporalis
RB	Right bundle
RBBB	Right bundle branch block
RBC	Red blood cell
RBE	Relative biologic effectiveness
RBF	Rose bengal fecal excretion
RBI	Resting baseline impedance
RCBD	Randomized complete block diagram
rCBF	Regional cerebral blood flow
RCC	Right coronary cusp
RCE	Resistive contact electrode
R&D	Research and development
r.e.	Random experiment
RE	Reference electrode
REM	Rapid eye movement; Return electrode monitor
REMATE	Remote access and telecommunication system
RES	Reticuloendothelial system
RESNA	Rehabilitation Engineering Society of North America
RF	Radio frequency; Radiographic-nuoroscopic
RFI	Radio-frequency interference
RFP	Request for proposal
RFQ	Request for quotation
RH	Relative humidity
RHE	Reversible hydrogen electrode
RIA	Radioimmunoassay
RM	Repetition maximum; Right masseter
RMR	Resting metabolic rate
RMS	Root mean square
RN	Radionuclide
RNCA	Radionuclide cineagiogram
ROI	Regions of interest
ROM	Range of motion; Read only memory
RP	Retinitis pigmentosa
RPA	Right pulmonary artery
RPP	Rate pressure product
RPT	Rapid pull-through technique
RPV	Right pulmonary veins
RQ	Respiratory quotient

RR	Recovery room
RRT	Recovery room time; Right posterior temporalis
RT	Reaction time
RTD	Resistance temperature device
RTT	Revised token test
r.v.	Random variable
RV	Residual volume; Right ventricle
RVH	Right ventricular hypertrophy
RVOT	Right ventricular outflow tract
RZ	Return-to-zero
SA	Sinoatrial; Specific absorption
SACH	Solid-ankle-cushion-heel
SAD	Source-axis distance; Statistical Analysis System
SAINT	System analysis of integrated network of tasks
SAL	Sterility assurance level; Surface averaged lead
SALT	Systematic analysis of language transcripts
SAMI	Socially acceptable monitoring instrument
SAP	Systemic arterial pressure
SAR	Scatter-air ratio; Specific absorption rate
SARA	System for anesthetic and respiratory gas analysis
SBE	Subbacterial endocarditis
SBR	Styrene-butadiene rubbers
SC	Stratum corneum; Subcommittees
SCAP	Right scapula
SCE	Saturated calomel electrode; Sister chromatid exchange
SCI	Spinal cord injury
SCRAD	Sub-Committee on Radiation Dosimetry
SCS	Spinal cord stimulation
SCUBA	Self-contained underwater breathing apparatus
SD	Standard deviation
SDA	Stepwise discriminant analysis
SDS	Sodium dodecyl sulfate
S&E	Safety and effectiveness
SE	Standard error
SEC	Size exclusion chromatography
SEM	Scanning electron microscope; Standard error of the mean
SEP	Somatosensory evoked potential
SEXAFS	Surface extended X-ray absorption fine structure
SF	Surviving fraction
SFD	Source-film distance
SFH	Stroma-free hemoglobin
SFTR	Sagittal frontal transverse rotational
SG	Silica gel
SGF	Silica gel fraction
SGG	Spark gap generator
SGOT	Serum glutamic oxaloacetic transaminase
SGP	Strain gage plethysmography; Stress-generated potential
SHE	Standard hydrogen electrode
SI	Le Système International d'Unités
SEBS	Surgical isolation barrier system
SID	Source to image reception distance
SIMFU	Scanned intensity modulated focused ultrasound
SIMS	Secondary ion mass spectroscopy; System for isometric muscle strength
SISI	Short increment sensitivity index
SL	Surgical lithotomy
SLD	Sublethal damage
SLE	Systemic lupus erythemotodes
SMA	Sequential multiple analyzer
SMAC	Sequential multiple analyzer with computer
SMR	Sensorimotor
S/N	Signal-to-noise
S:N/D	Signal-to-noise ratio per unit dose
SNP	Sodium nitroprusside
SNR	Signal-to-noise ratio
SOA	Sources of artifact
SOAP	Subjective, objective, assessment, plan
SOBP	Spread-out Bragg peak
SP	Skin potential
SPECT	Single photon emission computed tomography
SPL	Sound pressure level
SPRINT	Single photon ring tomograph
SPRT	Standard platinum resistance thermometer
SPSS	Statistical Package for the Social Sciences
SQUID	Superconducting quantum interference device
SQV	Square wave voltammetry
SR	Polysulfide rubbers
SRT	Speech reception threshold
SS	Stainless steel
SSB	Single strand breaks
SSD	Source-to-skin distance; Source-to-surface distance
SSE	Stainless steel electrode
SSEP	Somatosensory evoked potential
SSG	Solid state generator
SSP	Skin stretch potential
SSS	Sick sinus syndrome
STD	Source-tray distance
STI	Systolic time intervals
STP	Standard temperature and pressure
STPD	Standard temperature pressure dry
SV	Stroke volume
SVC	Superior vena cava
SW	Standing wave
TAA	Tumor-associated antigens
TAC	Time-averaged concentration
TAD	Transverse abdominal diameter
TAG	Technical Advisory Group
TAH	Total artificial heart
TAR	Tissue-air ratio
TC	Technical Committees
TCA	Tricarboxylic acid cycle
TCD	Thermal conductivity detector
TCES	Transcutaneous cranial electrical stimulation

TCP	Tricalcium phosphate
TDD	Telecommunication devices for the deaf
TDM	Therapeutic drug monitoring
TE	Test electrode; Thermoplastic elastomers
TEAM	Technology evaluation and acquisition methods
TEM	Transmission electron microscope; Transverse electric and magnetic mode; Transverse electromagnetic mode
TENS	Transcutaneous electrical nerve stimulation
TEP	Tracheoesophageal puncture
TEPA	Triethylenepho-sphoramide
TF	Transmission factor
TFE	Tetrafluorethylene
TI	Totally implantable
TICCIT	Time-shared Interaction Computer-Controlled Information Television
TLC	Thin-layer chromatography; Total lung capacity
TLD	Thermoluminescent dosimetry
TMJ	Temporomandibular joint
TMR	Tissue maximum ratio; Topical magnetic resonance
TNF	Tumor necrosis factor
TOF	Train-of-four
TP	Thermal performance
TPC	Temperature pressure correction
TPD	Triphasic dissociation
TPG	Transvalvular pressure gradient
TPN	Total parenteral nutrition
TR	Temperature rise
tRNA	Transfer RNA
TSH	Thyroid stimulating hormone
TSS	Toxic shock syndrome
TTD	Telephone devices for the deaf
TTI	Tension time index
TTR	Transition temperature range
TTV	Trimming tip version
TTY	Teletypewriter
TUR	Transurethral resection
TURP	Transurethral resections of the prostrate
TV	Television; Tidal volume; Tricuspid valve
TVER	Transscleral visual evoked response
TW	Traveling wave
TxB_2	Thrombozame B^2
TZ	Transformation zone
UES	Upper esophageal sphincter
UP	Urea-formaldehyde
UfflS	University Hospital Information System
UHMW	Ultra high molecular weight
UHMWPE	Ultra high molecular weight polyethylene
UL	Underwriters Laboratory
ULF	Ultralow frequency
ULTI	Ultralow temperature isotropic
UMN	Upper motor neuron
UO	Urinary output
UPTD	Unit pulmonary oxygen toxicity doses
UR	Unconditioned response
US	Ultrasound; Unconditioned stimulus
USNC	United States National Committee
USP	United States Pharmacopeia
UTS	Ultimate tensile strength
UV	Ultraviolet; Umbilical vessel
UVR	Ultraviolet radiation
V/F	Voltage-to-frequency
VA	Veterans Administration
VAS	Visual analog scale
VBA	Vaginal blood volume in arousal
VC	Vital capacity
VCO	Voltage-controlled oscillator
VDT	Video display terminal
VECG	Vectorelectrocardiography
VEP	Visually evoked potential
VF	Ventricular fibrillation
VOP	Venous occlusion plethysmography
VP	Ventriculoperitoneal
VPA	Vaginal pressure pulse in arousal
VPB	Ventricular premature beat
VPR	Volume pressure response
VSD	Ventricular septal defect
VSWR	Voltage standing wave ratio
VT	Ventricular tachycardia
VTG	Vacuum tube generator
VTS	Viewscan text system
VV	Variable version
WAIS-R	Weschler Adult Intelligence Scale-Revised
WAK	Wearable artificial kidney
WAML	Wide-angle mobility light
WBAR	Whole-body autoradiography
WBC	White blood cell
WG	Working Groups
WHO	World Health Organization; Wrist hand orthosis
WLF	Williams-Landel-Ferry
WMR	Work metabolic rate
w/o	Weight percent
WORM	Write once, read many
WPW	Wolff-Parkinson-White
XPS	X-ray photon spectroscopy
XR	Xeroradiograph
YAG	Yttrium aluminum garnet
ZPL	Zero pressure level

CONVERSION FACTORS AND UNIT SYMBOLS

SI UNITS (ADOPTED 1960)

A new system of metric measurement, the International System of Units (abbreviated SI), is being implemented throughout the world. This system is a modernized version of the MKSA (meter, kilogram, second, ampere) system, and its details are published and controlled by an international treaty organization (The International Bureau of Weights and Measures).

SI units are divided into three classes:

Base Units

length	meter[†] (m)
mass[‡]	kilogram (kg)
time	second (s)
electric current	ampere (A)
thermodynamic temperature§	kelvin (K)
amount of substance	mole (mol)
luminous intensity	candela (cd)

Supplementary Units

plane angle	radian (rad)
solid angle	steradian (sr)

Derived Units and Other Acceptable Units

These units are formed by combining base units, supplementary units, and other derived units. Those derived units having special names and symbols are marked with an asterisk (*) in the list below:

Quantity	*Unit*	*Symbol*	*Acceptable equivalent*
*absorbed dose	gray	Gy	J/kg
acceleration	meter per second squared	m/s^2	
*activity (of ionizing radiation source)	becquerel	Bq	1/s
area	square kilometer	km^2	
	square hectometer	hm^2	ha (hectare)
	square meter	m^2	

[†] The spellings "metre" and "litre" are preferred by American Society for Testing and Materials (ASTM); however, "−er" will be used in the Encyclopedia.

[‡] "Weight" is the commonly used term for "mass."

§Wide use is made of "Celsius temperature" (t) defined $t = T - T_0$ where T is the thermodynamic temperature, expressed in kelvins, and $T_0 = 273.15\,\mathrm{K}$ by definition. A temperature interval may be expressed in degrees Celsius as well as in kelvins.

Quantity	*Unit*	*Symbol*	*Acceptable equivalent*
*capacitance	farad	F	C/V
concentration (of amount of substance)	mole per cubic meter	mol/m^3	
*conductance	siemens	S	A/V
current density	ampere per square meter	A/m^2	
density, mass density	kilogram per cubic meter	kg/m^3	g/L; mg/cm^3
dipole moment (quantity)	coulomb meter	C·m	
*electric charge, quantity of electricity	coulomb	C	A·s
electric charge density	coulomb per cubic meter	C/m^3	
electric field strength	volt per meter	V/m	
electric flux density	coulomb per square meter	C/m^2	
*electric potential, potential difference, electromotive force	volt	V	W/A
*electric resistance	ohm	Ω	V/A
*energy, work, quantity of heat	megajoule	MJ	
	kilojoule	kJ	
	joule	J	N·m
	electron volt[†]	eV[†]	
	kilowatt hour[†]	kW·h[†]	
energy density	joule per cubic meter	J/m^3	
*force	kilonewton	kN	
	newton	N	kg·m/s^2
*frequency	megahertz	MHz	
	hertz	Hz	1/s
heat capacity, entropy	joule per kelvin	J/K	
heat capacity (specific), specific entropy	joule per kilogram kelvin	J/(kg·K)	
heat transfer coefficient	watt per square meter kelvin	W/(m^2·K)	
*illuminance	lux	lx	lm/m^2
*inductance	henry	H	Wb/A
linear density	kilogram per meter	kg/m	
luminance	candela per square meter	cd/m^2	
*luminous flux	lumen	lm	cd·sr
magnetic field strength	ampere per meter	A/m	
*magnetic flux	weber	Wb	V·s
*magnetic flux density	tesla	T	Wb/m^2
molar energy	joule per mole	J/mol	
molar entropy, molar heat capacity	joule per mole kelvin	J/(mol·K)	
moment of force, torque	newton meter	N·m	
momentum	kilogram meter per second	kg·m/s	
permeability	henry per meter	H/m	
permittivity	farad per meter	F/m	
*power, heat flow rate, radiant flux	kilowatt	kW	
	watt	W	J/s
power density, heat flux density, irradiance	watt per square meter	W/m^2	
*pressure, stress	megapascal	MPa	
	kilopascal	kPa	
	pascal	Pa	N/m^2
sound level	decibel	dB	
specific energy	joule per kilogram	J/kg	
specific volume	cubic meter per kilogram	m^3/kg	
surface tension	newton per meter	N/m	
thermal conductivity	watt per meter kelvin	W/(m·K)	
velocity	meter per second	m/s	
	kilometer per hour	km/h	
viscosity, dynamic	pascal second	Pa·s	
	millipascal second	mPa·s	

[†] This non-SI unit is recognized as having to be retained because of practical importance or use in specialized fields.

Quantity	*Unit*	*Symbol*	*Acceptable equivalent*
viscosity, kinematic	square meter per second	m^2/s	
	square millimeter per second	mm^2/s	
	cubic meter	m^3	
	cubic decimeter	dm^3	L(liter)
	cubic centimeter	cm^3	mL
wave number	1 per meter	m^{-1}	
	1 per centimeter	cm^{-1}	

In addition, there are 16 prefixes used to indicate order of magnitude, as follows:

Multiplication factor	*Prefix*	*Symbol*	*Note*
10^{18}	exa	E	
10^{15}	peta	P	
10^{12}	tera	T	
10^{9}	giga	G	
10^{8}	mega	M	
10^{3}	kilo	k	
10^{2}	hecto	h[a]	[a] Although hecto, deka, deci, and centi are SI prefixes, their use should be avoided except for SI unit-multiples for area and volume and nontechnical use of centimeter, as for body and clothing measurement.
10	deka	da[a]	
10^{-1}	deci	d[a]	
10^{-2}	centi	c[a]	
10^{-3}	milli	m	
10^{-6}	micro	μ	
10^{-9}	nano	n	
10^{-12}	pico	p	
10^{-15}	femto	f	
10^{-18}	atto	a	

For a complete description of SI and its use the reader is referred to ASTM E 380.

CONVERSION FACTORS TO SI UNITS

A representative list of conversion factors from non-SI to SI units is presented herewith. Factors are given to four significant figures. Exact relationships are followed by a dagger (†). A more complete list is given in ASTM E 380-76 and ANSI Z210. 1-1976.

To convert from	*To*	*Multiply by*
acre	square meter (m^2)	4.047×10^{3}
angstrom	meter (m)	$1.0 \times 10^{-10\dagger}$
are	square meter (m^2)	$1.0 \times 10^{2\dagger}$
astronomical unit	meter (m)	1.496×10^{11}
atmosphere	pascal (Pa)	1.013×10^{5}
bar	pascal (Pa)	$1.0 \times 10^{5\dagger}$
barrel (42 U.S. liquid gallons)	cubic meter (m^3)	0.1590
Btu (International Table)	joule (J)	1.055×10^{3}
Btu (mean)	joule (J)	1.056×10^{3}
Bt (thermochemical)	joule (J)	1.054×10^{3}
bushel	cubic meter (m^3)	3.524×10^{-2}
calorie (International Table)	joule (J)	4.187
calorie (mean)	joule (J)	4.190
calorie (thermochemical)	joule (J)	$4.184^{\dagger}$
centimeters of water (39.2 °F)	pascal (Pa)	98.07
centipoise	pascal second (Pa·s)	$1.0 \times 10^{-3\dagger}$
centistokes	square millimeter per second (mm^2/s)	$1.0^{\dagger}$

To convert from	*To*	*Multiply by*
cfm (cubic foot per minute)	cubic meter per second (m^3/s)	4.72×10^{-4}
cubic inch	cubic meter (m^3)	1.639×10^{-4}
cubic foot	cubic meter (m^3)	2.832×10^{-2}
cubic yard	cubic meter (m^3)	0.7646
curie	becquerel (Bq)	$3.70 \times 10^{10\dagger}$
debye	coulomb-meter (C·m)	3.336×10^{-30}
degree (angle)	radian (rad)	1.745×10^{-2}
denier (international)	kilogram per meter (kg/m)	1.111×10^{-7}
	tex	0.1111
dram (apothecaries')	kilogram (kg)	3.888×10^{-3}
dram (avoirdupois)	kilogram (kg)	1.772×10^{-3}
dram (U.S. fluid)	cubic meter (m^3)	3.697×10^{-6}
dyne	newton(N)	$1.0 \times 10^{-6\dagger}$
dyne/cm	newton per meter (N/m)	$1.00 \times 10^{-3\dagger}$
electron volt	joule (J)	1.602×10^{-19}
erg	joule (J)	$1.0 \times 10^{-7\dagger}$
fathom	meter (m)	1.829
fluid ounce (U.S.)	cubic meter (m^3)	2.957×10^{-5}
foot	meter (m)	$0.3048^{\dagger}$
foot-pound force	joule (J)	1.356
foot-pound force	newton meter (N·m)	1.356
foot-pound force per second	watt(W)	1.356
footcandle	lux (lx)	10.76
furlong	meter (m)	2.012×10^{2}
gal	meter per second squared (m/s^2)	$1.0 \times 10^{-2\dagger}$
gallon (U.S. dry)	cubic meter (m^3)	4.405×10^{-3}
gallon (U.S. liquid)	cubic meter (m^3)	3.785×10^{-3}
gilbert	ampere (A)	0.7958
gill (U.S.)	cubic meter (m^3)	1.183×10^{-4}
grad	radian	1.571×10^{-2}
grain	kilogram (kg)	6.480×10^{-5}
gram force per denier	newton per tex (N/tex)	8.826×10^{-2}
hectare	square meter (m^2)	$1.0 \times 10^{4\dagger}$
horsepower (550 ft·lbf/s)	watt(W)	7.457×10^{2}
horsepower (boiler)	watt(W)	9.810×10^{3}
horsepower (electric)	watt(W)	$7.46 \times 10^{2\dagger}$
hundredweight (long)	kilogram (kg)	50.80
hundredweight (short)	kilogram (kg)	45.36
inch	meter (m)	$2.54 \times 10^{-2\dagger}$
inch of mercury (32 °F)	pascal (Pa)	3.386×10^{3}
inch of water (39.2 °F)	pascal (Pa)	2.491×10^{2}
kilogram force	newton (N)	9.807
kilopond	newton (N)	9.807
kilopond-meter	newton-meter (N·m)	9.807
kilopond-meter per second	watt (W)	9.807
kilopond-meter per min	watt(W)	0.1635
kilowatt hour	megajoule (MJ)	$3.6^{\dagger}$
kip	newton (N)	4.448×10^{2}
knot international	meter per second (m/s)	0.5144
lambert	candela per square meter (cd/m^2)	3.183×10^{3}
league (British nautical)	meter (m)	5.559×10^{2}
league (statute)	meter (m)	4.828×10^{3}
light year	meter (m)	9.461×10^{15}
liter (for fluids only)	cubic meter (m^3)	$1.0 \times 10^{-3\dagger}$
maxwell	weber (Wb)	$1.0 \times 10^{-8\dagger}$
micron	meter (m)	$1.0 \times 10^{-6\dagger}$
mil	meter (m)	$2.54 \times 10^{-5\dagger}$
mile (U.S. nautical)	meter (m)	$1.852 \times 10^{3\dagger}$
mile (statute)	meter (m)	1.609×10^{3}
mile per hour	meter per second (m/s)	0.4470

To convert from	*To*	*Multiply by*
millibar	pascal (Pa)	1.0×10^{2}
millimeter of mercury (0 °C)	pascal (Pa)	$1.333 \times 10^{2\dagger}$
millimeter of water (39.2 °F)	pascal (Pa)	9.807
minute (angular)	radian	2.909×10^{-4}
myriagram	kilogram (kg)	10
myriameter	kilometer (km)	10
oersted	ampere per meter (A/m)	79.58
ounce (avoirdupois)	kilogram (kg)	2.835×10^{-2}
ounce (troy)	kilogram (kg)	3.110×10^{-2}
ounce (U.S. fluid)	cubic meter (m^3)	2.957×10^{-5}
ounce-force	newton (N)	0.2780
peck (U.S.)	cubic meter (m^3)	8.810×10^{-3}
pennyweight	kilogram (kg)	1.555×10^{-3}
pint (U.S. dry)	cubic meter (m^3)	5.506×10^{-4}
pint (U.S. liquid)	cubic meter (m^3)	4.732×10^{-4}
poise (absolute viscosity)	pascal second (Pa·s)	$0.10^{\dagger}$
pound (avoirdupois)	kilogram (kg)	0.4536
pound (troy)	kilogram (kg)	0.3732
poundal	newton (N)	0.1383
pound-force	newton (N)	4.448
pound per square inch (psi)	pascal (Pa)	6.895×10^{3}
quart (U.S. dry)	cubic meter (m^3)	1.101×10^{-3}
quart (U.S. liquid)	cubic meter (m^3)	9.464×10^{-4}
quintal	kilogram (kg)	$1.0 \times 10^{2\dagger}$
rad	gray (Gy)	$1.0 \times 10^{-2\dagger}$
rod	meter (m)	5.029
roentgen	coulomb per kilogram (C/kg)	2.58×10^{-4}
second (angle)	radian (rad)	4.848×10^{-6}
section	square meter (m^2)	2.590×10^{6}
slug	kilogram (kg)	14.59
spherical candle power	lumen (lm)	12.57
square inch	square meter (m^2)	6.452×10^{-4}
square foot	square meter (m^2)	9.290×10^{-2}
square mile	square meter (m^2)	2.590×10^{6}
square yard	square meter (m^2)	0.8361
store	cubic meter (m^3)	$1.0^{\dagger}$
stokes (kinematic viscosity)	square meter per second (m^2/s)	$1.0 \times 10^{-4\dagger}$
tex	kilogram per meter (kg/m)	$1.0 \times 10^{-6\dagger}$
ton (long, 2240 pounds)	kilogram (kg)	1.016×10^{3}
ton (metric)	kilogram (kg)	$1.0 \times 10^{3\dagger}$
ton (short, 2000 pounds)	kilogram (kg)	9.072×10^{2}
torr	pascal (Pa)	1.333×10^{2}
unit pole	weber (Wb)	1.257×10^{-7}
yard	meter (m)	$0.9144^{\dagger}$

C

CAPACITIVE MICROSENSORS FOR BIOMEDICAL APPLICATIONS

D. Tsoukalas
S. Chatzandroulis
D. Goustouridis
NTUA
Athens, Attiki
Greece

INTRODUCTION

The use of reliable, high performance miniature sensors in the medical field is of growing importance for patient health monitoring. Batch sensor fabrication, as this has been introduced by Integrated Circuit (IC) manufacturing, is an efficient way to produce silicon sensors with desirable characteristics. Since microsensors combine small size with electrical and mechanical principles of operation they constitute together with microactuators what is usually called Microelectromechanical Systems (MEMS). These components are mainly made from silicon and other related materials to explore existing know-how and infrastructure of silicon technology. All of the above factors have allowed for fast growth of the microsensor field during the last years. This article focuses on physical microsensors used in the medical field that are based on the capacitive approach.

Historically, silicon piezoresistive devices were first introduced in the early 1960s to monitor pressure related variations (1). Piezoresistive silicon sensors take advantage of the piezoresistance effect observed in Si and Ge crystals (2). During this phenomenon, the value of a resistor realized from these semiconductors changes when mechanical strain is applied.

Piezoresistive devices have since then been investigated and used with catheters or as implantable units to monitor blood pressure variations (3,4). Such devices are already present in the market (5,6). Problems related to the nature of the piezoresistance effect include the relatively important temperature sensitivity of piezoresistive sensors that have to be compensated for with rather sophisticated electronics as well as the increased power consumption when compared to capacitive devices (7). These drawbacks of piezoresistive devices have accelerated the investigation of other device options for pressure measurements. It was in the 1980s that research on capacitive sensors began.

THE CAPACITIVE APPROACH

The capacitive approach is based on the parallel plate capacitor principle. In that structure the capacitance between two parallel electrodes is given by

$$C = \varepsilon_r \varepsilon_0 \frac{A}{d} \tag{1}$$

where ε_r, ε_0 is the relative and vacuum permittivity constant, respectively, A is the plate surface area, and d is the plate distance.

When an applied external force acts in a way to change the distance between the two electrodes, the displacement is detected as a capacitance change. In many applications when a micromechanical structure is realized to detect a capacitance change, one of the two electrodes remains fixed and the other is flexible (Fig. 1a). The flexible electrode that is rigidly supported on its edges deflects so it does not remain parallel to the fixed electrode (Fig. 1b). In that case, the previous simple expression is modified and the capacitance is given by

$$C = \varepsilon_r \varepsilon_0 \int_A\int \left(\frac{1}{d - w(x,y)}\right) \tag{2}$$

where $w(x,y)$ is the displacement of the flexible electrode.

Since the measured capacitance depends on the distance between the two electrodes, it can be used to calculate



Figure 1. An example of a capacitive sensor is a pressure sensor. In parts a, the thin sensor diaphragm remains parallel to the fixed electrode and in part b, the diaphragm deflects under applied pressure resulting in capacitance change.

the value of the stimulus modifying the interelectrode spacing. Different approaches for capacitive micro devices have appeared that make use of the above principle.

One major application in the medical field for capacitive transducers is pressure measurement. First explorative research of capacitive microdevices made using silicon technology was initiated in the early 1980s (8–11). These initial studies have demonstrated that capacitive devices exhibit superior properties from their piezoresistive competitors in terms of pressure sensitivity, scalability, manufacturing simplicity, as well as process variation tolerance.

APPLICATIONS IN THE MEDICAL FIELD

The manufacturing advantages of micromachined silicon sensors have made them very attractive in the field of minimally invasive therapy. Catheters used in this field need to penetrate into small blood vessels putting stringent requirements on sensor size, which should be one-half of the size of the vessel to be accessed. In small vessels, catheters usually have a diameter of 2 mm, while the smallest catheter at the moment has a diameter of 0.36 mm (12). Miniaturization, therefore, of both sensor and packaging size drives this kind of application. Capacitive devices within the above size requirements have been demonstrated in silicon (13) and are mainly competing with fiber optic pressure sensors (14), or a free hanging strain gauge (15).

Catheters, however, are unsuitable for long-term monitoring of blood pressure. With AAA (abdominal aortas aneurism) and CHF (congestive heart failure) being the major cardiovascular diseases in our days, an implantable pressure monitoring system that would tailor treatment medication by measuring blood pressure appears very attractive. These implantable applications will require a miniature batteryless telemetric sensor able to communicate with an external handheld unit. In such applications, power consumption becomes an additional issue and capacitive devices offer a clear advantage over piezoresistive ones. These types of systems have been under investigation (16,17) and have already demonstrated good performance.

Capacitive pressure sensors have also been successfully applied in the following areas. (1) Intraocular pressure monitoring (10,18). Glaucoma is, for example, a serious disease characterized by an increased pressure in the eye that may result in blindness. In that case, a sensitive capacitive device has been developed for remote sensing of eye pressure (normally 10–20 mmHg 1.33–2.66 kPa above atmospheric pressure, but much increased in glaucoma). (2) Intracranial pressure monitoring (19), as well as for clinical assessment of prosthetic socket fit (20) and pressure distribution in artificial joints (21). Intracranial pressure monitoring is an implant used in the treatment of patients with trauma of the head as well as in neurological patients.

Although pressure is the field where capacitive sensors have been applied more extensively, there are also other applications under development in the medical field. Accelerometers, for example, are used for measuring inclination of body segments and activity of daily living, with application in patient rehabilitation (22), but also register the kind of movements that occur in healthy persons during normal standing (23,24). Physical activity as well as energy expenditure as these can be followed by accelerometers proves to be useful information for personal status monitoring. An accelerometer design includes the fabrication of a proof mass that is displaced in proportion with acceleration. The use of capacitance to measure that displacement significantly improves sensitivity.

Recently, ultrasound imaging technology has also exploited the advantages of capacitive sensors for both transmission and detection purposes (25). Such capacitive devices can be batch fabricated to form a transducer array with array elements that can be as small as 50 μm diameter. Ultrasound devices are made of a thin flexible electrode facing a rigid electrode. For transmission purposes, the membranes are driven into vibration by the electrostatic force exerted between the two electrodes. For reception, the membrane vibration is excited by an impinging acoustic wave that is converted by the capacitive device to electrical signal. This as well as other efforts (26,27) are driven from the need to obtain in the future high resolution images within the body using three-dimensional 3D echographic probes.

Miniature capacitive transducers, known in low frequency applications as condenser microphones, are used in hearing aids and have been reported from different research groups (28,29). In their work, Rombach et al. developed a low noise capacitive microphone with higher sensitivity and broader bandwidth than those used in traditional hearing aids. This device consists of two backplates with an intermediate membrane made of a low stress silicon-rich nitride and B^+ polysilicon multilayer. Pedersen et al., on the other hand, presented an integrated capacitive microphone based on polyimide technology and realized by postprocessing on a CMOS wafer at low processing temperatures.

Capacitive sensors have also been used as humidity sensors for the diagnosis of pulmonary diseases. In this device, a chemically absorbing layer (usually a polymer) is placed between the parallel electrodes of a capacitor. Then, humidity is detected as a change in capacitance because of the dielectric constant change as water molecules are absorbed in the polymer. In a similar configuration, hydrogel has been used between the electrodes of a capacitive sensor to measure body analytes from the capacitance variation occurring due to the swelling of the polymer (30).

FABRICATION TECHNOLOGIES FOR CAPACITIVE SENSORS

Silicon is widely accepted as the material of choice for microsensor fabrication. Known for its good mechanical properties, high mechanical strength, and light weight it's an ideal material for physical sensors (31). More importantly, the existing know-how from IC manufacturing made the use of silicon technology for transducers quite straightforward during the last decades.

This section describes the main silicon technologies that are used for the fabrication of capacitive devices. Most of the capacitive devices used in medical technology, namely, pressure sensors, accelerometers, and ultrasound sensors, have been developed using two major technology platforms.

Bulk Micromachining Technologies

Bulk micromachining has historically been developed first. It consists of engineering a silicon wafer by a series of lithographic processes followed by wet or dry etching, in order to form thin membranes or other free standing structures that can move upon an external stimulation. In bulk micromachining, the micromechanical silicon structures are fabricated by selectively removing whole sections, or in some cases, all but a small part of the silicon wafer. Thus the structures fabricated in this way are made of single- crystal silicon and have excellent mechanical properties. In bulk micromachining, processing may take place in either the front or the back side of the silicon wafer.

Wet etching of silicon is based on a chemical reaction of silicon with a base solution (KOH) in order to remove silicon material and form the intended 3D structure. Dry etching is a physicochemical process that was initially developed for the etching of thin films. During the last decade, however, this technique has also been used for the removal of thick Si material (32).

The above techniques combined with others usually used in IC manufacturing, like ion implantation, thermal processing, and thin-film (metal or silicon insulator) deposition, constitute the backbones of capacitive sensor fabrication. A detailed description of these processes is beyond the scope of this article and can be found elsewhere (33).

Apart from these processing technologies it is necessary in many applications to use other specific processes. For example, in pressure sensor fabrication it is always desirable to have a reference pressure enclosed in the sensor body. This requires a reliable technology for sealing a cavity with known pressure. For that reason, bulk micromachining techniques are combined with technologies usually referred to as bonding technologies. Two are the most established technologies in this area: anodic bonding and fusion bonding, in chronological order of their discovery and application. Anodic bonding is achieved between silicon and a glass substrate at medium temperature ($\sim 400\,^{\circ}$C) under the application of a direct current (dc) voltage across the two substrates (34). Prior to contact of the two substrates, their surfaces are adequately cleaned to remove any particle that can inhibit their good contact. Bulk micromachining combined with anodic bonding has been successfully used for the realization of medical capacitive pressure sensors by a couple of research groups (35,36). In the process developed at the University of Michigan, boron etch-stop techniques and silicon-glass anodic bonding is used to fabricate a capacitive pressure sensor. In this process, KOH is used to initially form a recess in the surface of a silicon wafer, followed by a deep boron diffusion to define the rim of the transducer, and a shallow diffusion defining the eventual thickness of the diaphragm. The completed silicon wafer is finally electrostatically bonded to a glass wafer. The silicon wafer is then dissolved in EDP letchant, leaving only the silicon transducer islands bonded to the glass. In this way, a thin silicon membrane structure over a sealed cavity is fabricated that exhibits high pressure sensitivity adequate for use in blood pressure monitoring.

A more recently discovered technique that has been applied for sealing of a pressure reference cavity is fusion bonding. This technique does not require the application of a voltage across the bonded substrate. Instead, it includes a high temperature heat treatment. So after a thorough wafer cleaning and drying process of two silicon wafers that renders their surface hydrophilic, they are brought into contact at room temperature. The two wafers are initially drawn together at room temperature by van de Waals forces developed between the hydrogen atoms of water molecules covering their surfaces. This initial attraction is commonly known as prebonding. Prebonding follows a high temperature heat treatment that during which a hydrogen atom is removed transforming the hydrogen bonds to covalent bonds between oxygen atoms thus increasing the bonding strength (37). The temperature necessary to achieve high strength bonding is $> 800\,^{\circ}$C. A successful example of this technology together with bulk micromachining is applied for the realization of a capacitive-type pressure sensor for blood pressure monitoring developed by Goustouridis et al. (13). This simple process results in robust capacitive sensors with low parasistics (Fig. 2). It involves two silicon wafers that are silicon fusion bonded to form the final 3D structure, and a thick oxide in between in which a sealed cavity is formed. The sensor diaphragm is formed by creating a heavily boron-doped region in the cavity bottom. After bonding, the wafer stack is first mechanically ground and then etched in EDP etchant to leave the sensor diaphragm on top of the cavity thus creating the pressure sensor. The sealed cavities are then metalized and packaged. Figure 3 depicts the complete pressure sensing element as it appears after the metallization step.

Hydrophobic bonding is also applied when we need to bond two bare silicon surfaces without a SiO_2 layer on the surface. This technique requires an HF final step to remove any oxide layer from the surface. In hydrophobic bonding, the water molecules necessary to complete the prebonding step are substituted from the HF molecules, while the rest of the bonding process is similar to the hydrophilic one.

More recently, plasma activated bonding (38) or other low temperature bonding ($< 400\,^{\circ}$C) using spin on glass (SOG) (39) have been applied. These techniques are more appropriate for wafer level packaging and have to be more developed in the future for use in sensor fabrication.

Recently, wafer bonding has also been used for demonstration of capacitive ultrasound devices (25), as well as of capacitive accelerometers (40).

Surface Micromachining and SOI Technologies

Surface micromachining technologies have been developed with the primary goal of cointegrating the electronic and mechanical parts on the same silicon chip. Since the active and passive layers of a surface micromachined structure are realized using the same conductive and insulating thin-film layers as in IC manufacturing, it is possible by appropriately designing the mask sequence to realize both



Figure 2. Fabrication of capacitive sensors using bulk micromachining and silicon fusion bonding. Two wafers are used for this purpose. (a) Each wafer is processed independently before the bonding; (b) after the bonding process the two wafers are permanently stacked together; (c) selective wet etching releases the boron doped silicon diaphragms; (d) metallization is performed for electrical connects of the membrane and the substrate.



Figure 3. This figure illustrates the final capacitive pressure sensor structure (not to scale).

components in parallel by adding a few mask levels after the completion of the electronic circuit. This particular feature is behind the drive for the development of this technology.

In the case of surface micromachining, all of the processing takes place only on the surface of the front side of the silicon wafer. The micromechanical structures fabricated in this manner are made out of polycrystalline silicon deposited by low pressure chemical vapor deposition (LPCVD) techniques over a sacrificial layer. The sacrificial layer is a deposited oxide, usually phosphorsilicate glass (PSG). This layer is subsequently removed by an HF solution through narrow access channels to release the polysilicon structure (Fig. 4). Sealing of the channels is necessary and it is realized by a deposition step. With surface micromachining, it is possible to fabricate far smaller microelectromechanical devices than with bulk micromachining. Depositing processes allow for very good control over the dimensions of the deposited materials.

Surface micromachining is a very important technology with a demonstrated potential. Problems related to stiction of membrane structures on the substrate during aqueous removal of sacrificial layers have been resolved by the application of other etching and drying techniques like gas-phase etching or freeze-drying techniques using cycloexane (41). A typical process sequence developed (42) for capacitive ultrasound transducers is shown in Fig. 5.

There is continuing discussion on the advantages–disadvantages of the cointegration of sensors with electronics. Although it is considered that surface micromachining can result in a higher packing density, and consequently smaller and cheaper components, it appears that yield issues still need to be overcome until this technology can be definitively adopted in preference to hybrid fabrication technologies.

A recent variation of the two technologies employs silicon-on-insulator (SOI) technology with some unique features. The SOI technology offers the possibility of using crystalline silicon as the active part of a capacitive-type structure with more predictable mechanical behavior than the polysilicon film used in surface micromachining. In fact, the internal stresses (either compressive or tensile) developed during the growth of the polysilicon film, which evolved during subsequent thermal treatment because of change of the grain size, is a source of potential uncertainties for the behavior of these films.

Silicon-on-insulator is a mature technology and nowadays can offer crystalline silicon structures of varying thicknesses over a variety of SiO_2 buried layer thicknesses. This has become possible after the discovery of wafer bonding technology, which enables the development of back-etch-silicon-on-insulator (BESOI) structures.

Thin as well as thick silicon structures allow for capacitive pressure sensors development, ultrasound capacitive sensors using rather thin membranes of some micron thickness as well as capacitive-type accelerometers, where



Figure 4. Typical surface micromachining process. (a) Deposition of the sacrificial layer (silicon oxide) and etch channels formation, (b) deposition of silicon nitride ring, (c) deposition of polysilicon film, (d) removal of the sacrificial layer by HF in wet or vapor form, (e) sealing of the device with deposited silicon oxide.

Si structures exceed some hundreds of micrometers. The introduction of deep reactive ion etching (DRIE) in silicon processing especially during the last few years, has enabled the vertical anisotropic etching of Si at the rate of several microns per minute, and the fabrication of thick proof masses on BESOI or glass structures for capacitive accelerometers (43). This accelerometer uses a silicon proof mass of 0.5 mg with 120 μm thickness formed by DRIE and measures in plane (x or y axis) acceleration. It uses a sense gap of only 2 μm between sense fingers and the electrodes (Fig. 6). As the proof mask moves under acceleration, the distance between sense fingers and fixed electrodes change, which consequently modifies the capacitance.

Finally, a different but similar approach results in capacitive-like pressure sensors based on a field effect transistor (44). In this case, the usual dielectric of a MOSFET is replaced by a vacuum cavity. The external pressure variations deflect the gate electrode, and consequently influence the capacitive coupling of the flexible membrane (gate) with the channel thus modifying the current flow in the device. Although these devices present an attractive design, there have not seen any new developments.

OPERATION ISSUES OF CAPACITIVE SENSORS

As introduced in the first paragraph a capacitive sensor is an equivalent parallel plate capacitor with clamped edges where the diaphragm deforms during the application of a deferential pressure across the two sides in the case of capacitive pressure devices.

In the normal operation mode of a capacitive pressure sensor, the diaphragm does not contact the substrate electrode. The capacitance response of a typical pressure sensor is shown in Fig. 7. The output capacitance is nonlinear because of its inverse relationship with the electrode gap d_0-w (eq. 2), which is a function of pressure, P. This nonlinearity becomes more significant for large membrane deflections. At the point when the sensor diaphragm touches the cavity bottom (Fig. 7), the behavior of the sensor changes and enters “touch mode” operation (45). In this operating region, linearity increases and the sensor capacitance is dominated by the area touching the cavity bottom, since the gap there is replaced from the very thin and high dielectric constant SiO_2 layer of the bottom electrode.

Sensitivity of the Capacitive Sensor

Because of the nonlinearity of the response, the sensitivity of a capacitive sensor is not constant. For example, the sensitivity of the capacitive pressure sensor for blood pressure monitoring (defined as $1/C_0(\Delta C/\Delta P)$ with the response shown in Fig. 7 is 1.5 fF/mmHg for the low pressure range and increases to $>$ 18 fF/mmHg for the upper part of the measurement range ($>$ 200 mmHg, 26.66 kPa). In the touch mode operation region, ($>$300 mmHg, 39.99 kPa) the sensor has a nearly linear response with a sensitivity of 12 fF/mmHg.

Temperature variation, although not a critical issue for medical application (because of the small variation of the body temperature), can affect the accuracy of the measurements. The temperature influence on the capacitive sensor response is due to either the mismatch of thermal expansion of dissimilar materials used in the fabrication process (usually Si and SiO_2), or to gas expansion in case gas is trapped in a sealed cavity of the sensor. It can of course be due to both of the above reasons. In the case of a sealed cavity, the temperature influence, because of the expansion of the gas trapped inside the cavity, can be eliminated if the cavity is sealed in vacuum. On the other hand, the effect of the different thermal expansions of the materials used is always a problem that requires appropriate design in order to reduce or even eliminate the effect. In the cases of capacitive devices fabricated with surface micromachining,



Figure 5. Surface micromachining process sequence for the fabrication of capacitive ultrasonic transducers as taken from X. Jin et al. (42).



Figure 6. Comb-shaped accelerometer structure fabricated using a combination of processes like bonding silicon with glass substrate and Deep Reactive Ion Etching (43).



Figure 7. Typical response of a capacitive pressure sensor with 325 μm OD circular diaphragm. The diaphragm touches the cavity bottom at 300 mmHg (~ 40 kPa). A pressure sensor must be designed to operate either for lower values than 300 mmHg or for higher pressure values. Otherwise an hysteresis phenomenon can be observed.

or by using anodic bonding of silicon with a glass substrate, the influence of temperature becomes more complicated.

Figure 8 shows the influence of temperature on the response of a capacitive pressure sensor, not sealed in a vacuum. The variation of the distance between the curves with temperature represents the temperature coefficient of the pressure sensitivity (TCS) while the slope of the lower curve is the temperature coefficient of zero pressure offset (TCO). The TCS is defined as $\Delta S/S\Delta T$, where S is the pressure sensitivity defined as $\Delta C/C_0\Delta P$ and TCO is defined as $\Delta C/C_0\Delta T$.

This simple configuration of a parallel plate capacitor is used mainly in pressure sensors and ultrasound imaging devices. Accelerometers are usually designed with comb-shaped electrodes that result in increased linearity and sensitivity (40,43).



Figure 8. Temperature variation of a capacitive pressure sensor in the range 0–400 mmHg (~53.3 kPa). The effect is due mainly to trapped gas expansion inside the cavity.

CAPACITIVE SENSOR ELECTRONIC INTERFACES

Although capacitive sensors offer advantages with respect to high sensitivity and low power operation, they also present difficulties in the design of electronic interfaces to convert capacitance changes into electrical signals. Parasitic capacitances often dominate system performance by reducing sensitivity and increasing nonlinearity (46). Therefore, it becomes absolutely essential for sensor systems incorporating capacitive sensors to either integrate the MEMS component with the electronic interface or place the two chips at close proximity to each other to reduce parasitics. At the same time, it is important that the electronic interface is designed to suppress the remaining parasitic capacitances and provide for a large zero capacitance range. A good starting point for the study of capacitance measurement circuits may be found in Ref. 47, where a number of basic circuits are discussed.

Depending on the technological steps used to fabricate the sensor, several parasitic capacitances $C_{\mathrm{p}1,2}$ and conductances G_{p} may be present in the device and increase in importance as devices get smaller and the sensing capacitance C_{s} gets in the pF range. These parasitic effects may originate from various sources depending on the fabrication process used (i.e., stray capacitances of metal lines and connecting pads in parallel with the sensing capacitance or leakage resitors). Further variations may also be observed, due to technological reasons, between batches of the same sensor. In Fig. 9, a simple electrical model of a typical capacitive sensor, including parasitic effects, is shown. The spread in sensor characteristics (e.g., zero capacitance, sensitivity) resulting from these effects puts a great strain in the design of electronic interfaces for capacitive sensors. For this reason, most of the capacitive interfaces to date have been designed by taking into consideration the particular sensor and application that they are going to be used for. The design is a trade-off between power consumption, interface accuracy, and resolution, or even die size in some applications in the medical field.

A number of architectures have been proposed to date to convert capacitive changes into electrical signal. Some are built around a relaxation oscillator (46,48), others use switch capacitor techniques to convert capacitance changes into voltage, and others interface the sensor directly into a sigma–delta modulator. A few attempts to develop a generic interface have also been reported (49,50). However, the power consumed is too high for remote sensing applications.



Figure 9. Simple electrical model of a capacitive sensor. Parasitic capacitances is designated by $C_{\mathrm{p}1,2}$, conductances by G_{p} and the sensing capacitance by C_{s}.

Van Der Goes and Meijer (49) presented a universal transducer interface for the read out of capacitors, platinum resistors, thermistors, resistive bridges, and potentiometers. The circuit uses the three signal technique in which the sensor signal E_{x}, a reference signal E_{ref}, and the offset E_{off} of the whole interface are measured in a identical way to achieve continuous autocalibration of offset and gain. The two port measurement technique is used to eliminate sensor parasitic capacitance. In this technique, a testing voltage, V, is forced on one capacitor electrode while current I is sensed on the other (51). The current I then depends only on the applied voltage and sensing capacitance. However, the technique is not energy efficient, since it requires four measurement cycles and three external voltage sources to determine the sensor capacitance.

Yazdi et al. (50) also developed a standardized switch capacitor interface for capacitive sensors, as shown in Fig. 10. This interface is capable of interfacing through a standard bus with a microcontroller that collects sensor data through the interface, calibrates data, and either stores or transmits it wirelessly or through a serial port. The readout circuit utilizes a low noise front-end charge integrator to read out the difference between the sensor capacitance and a reference capacitor. An input multiplexer allows for interfacing with up to six capacitive sensors. Finally, the chip can be digitally programmed to operate with one of three external or internal reference laser trimmable capacitors.

Bracke et al. (52) reports on a low power generic switched capacitor interface for capacitive sensors. The circuit uses a special clocking scheme, in which the analog sensor circuit block is clocked at a low 8 kHz frequency, while the sigma–delta modulator is clocked at 128 kHz. The technique ultimately reduces power consumption to 90 μW on the ON-state.

CAPACITIVE ELECTRONIC INTERFACES FOR IMPLANTABLE APPLICATIONS

In medical applications, where the diagnostic device is to be implanted inside the human body, only limited power is available for the electronic circuits and sensor. In such cases, power can only be found via a battery implanted together with the sensing system or through passive telemetry. In passive telemetry, energy may be harvested from a remote electromagnetic field transmitted outside the body. The same field may also be used to receive control data and transmit sensor data to a data logger. In both cases, minimizing power consumption is essential.

A simple low power interface for biomedical applications could be realized by using a simple relaxation oscillator (46,48). A capacitance-to-frequency modulated output was first proposed by Hanneborg et al. (46). This circuit delivers a digital pulse trail with frequency dependent on the sensor


Sensor 1
Sensor 2
Sensor 6
MUX
C_f
Integrator
Digital gain control
VGA
Sample & hold
Temperature sensor
Programmable reference capacitor
Sensor select
MUX
Digital control
Controls selects & commands
Self-test DAC
Bus Interface
Address register
Command decoder
Data latch
Sensor bus

Figure 10. Circuit blocks of the capacitive electronic interface as described by W. Bracke et al. (50).

capacitance. The circuit consists of two current sources: a switch and a Schmitt trigger. The unknown capacitance is periodically charged and discharged by flipping the switch between current $I+$ and $I-$ (Fig. 11).

An implementation of this type of capacitance-to-frequency converter is presented in Fig. 12. The circuit converts capacitance at its input into a frequency signal that can be readily fed to a digital microcontroller for processing. Either a capacitive sensor or a reference may be switched in, and the frequency delivered at the circuit output is dependant on the input capacitance according to

$$f = \frac{I_0}{2C_x V_h} \tag{3}$$

where I_0 is the current by which the sensor capacitance C_x is charged or discharged, and V_h is the hysteresis of the Schmitt trigger. The parameter V_c is a control signal that allows for switching between the unknown sensor capacitance C_x and a reference capacitor C_{ref}. The output frequency when the reference is selected is independent of pressure, thus compensation of temperature and long-term drifts are possible by taking the ratio of the reference frequency and sensor frequency, $F_{\text{ref}}/F_{\text{sens}}$.

The response of a pressure measuring system based on this circuit realized in 1.2 μm of CMOS technology and a capacitive pressure sensor (53) is shown in Fig. 13. It operates at 4 V and draws 20 μA of average current. The system exhibits a sensitivity of 36 Hz/mmHg and is able to resolve pressure changes of 5 mmHg (0.66 kPa). A photograph of this system is shown in Fig. 14.

In medical science, however, there is often the need for long-term monitoring of vital life parameters. A good example is abdominal aortic aneurysm (AAA), which is a ballooning of the abdominal aorta. Patients who suffer from this condition need to undergo a procedure during which a stent graft is inserted. After the operation, however, it is possible that the aneurysmal sac is not completely isolated, leading to recurrent pressurization of the sac, a complication that, if left undetected, may lead to rupture of the sac and patient death. Long-term, postoperation monitoring of the patients is therefore necessary.

Early efforts for systems for the monitoring of blood pressure (54) used miniature active transmitters to transfer measured data and were battery powered, which limited


V_{dd}
I+
VC_x
f_x, f_r
I–
C_x
GND
VC_x
V_{OUT}

Figure 11. Block diagram of the capacitive to frequency converter proposed by Hanneborg et al. (46). The circuit consists of two current sources, a switch and a Schmitt trigger.


VDD
M1
M5
Cx
M2
M6
Vc
M3
M7
M4
M8
Cref
M9
M13
M10
M11
VDD
M14
M12
M15
M16
M17
M18
Fout

Figure 12. Schematic of Schmitt-trigger based oscillator used as a capacitive interface.



Figure 13. Frequency response of a pressure measuring system consisting of the simple circuit of Fig. 12 and a capacitive pressure sensor in the range 0–300 mmHg (~40 kPa).


Sensor
ASIC
1cm

Figure 14. A photograph of a hybrid pressure measuring system consisting of a capacitive sensor and associated signal conditioning electronic circuit.

their lifetime. An alternative approach to power these modules is through induction coupling, while the same radio frequency (RF) field can be used to transfer data out of the implanted module (55). The implanted circuit should be virtually immune to supply fluctuations arising from random misalignment of the implanted and the external coil. A new circuit was developed based on the previous architecture, but in which each circuit block was redesigned.

The block diagram of the passive telemetry system is depicted in Fig. 15. It consists of an external control unit (the base unit) and an implantable transponder. Wireless communication can then be established between the two units, based on an absorption modulation mechanism. The transponder receives power and external control data


Personal computer
RS232
LCD
Base unit
Energy
Skin
RF field
5 V Supply
RF-DC converter
Data
Pressure sensor
C-F converter
RF modulator
Transponder

Figure 15. Block diagram of passive telemetry system.



Figure 16. Transponder electronics.

through an RF field, while it can transmit data by modulating the absorption rate. The base unit, on the other hand, demodulates the transmitted data and processes it though a microcontroller to convert the signal into an eight bit unsigned byte array. The resulting byte can then be sent to a PC through a serial output.

The block diagram of the transponder electronics is shown in Fig. 16. The improved capacitance-to-frequency circuit is used to interface a capacitive pressure sensor. The circuit consists of two basic blocks: a bandgap reference voltage generator and an oscillator. In order to achieve independence of the output frequency from the received power, this time the oscillator operates on an internally stabilized voltage generated from a bandgap reference. Voltage regulation is a critical part of telemetric systems as the induced power, and thus the voltage output, of the RF/dc converter in the transponder can greatly fluctuate in an actual implanted system becaused the relative position changes of the two antennas. In addition, to further immune the system from supply fluctuations a current mode comparator is used in the oscillator.

The bandgap reference voltage circuit is capable of operating at a low power supply as it operates on an internally regulated voltage VREG (56). This same node is also used for the supply of the oscillator circuit after the contributions of the extra branches of the oscillator are accounted for.

The oscillator itself is designed around a current mode comparator that results in an output frequency independent of power supply fluctuations and with small temperature drift. Triggering levels of this oscillator are defined by two currents: I_h and I_l. The period of the output pulse can then be shown to be equal to

$$T = \frac{2C_x}{I_0}(V_{\text{bias}} - V_{TN})(\sqrt{n} - 1) \qquad (4)$$

where n stands for the ratio of I_h to I_l, and V_t is the threshold voltage. By taking the inverse of eq. 4 and substituting for I_0, we obtain

$$f = \frac{k\frac{W_0}{L_0}(V_{\text{bias}} - V_{TN})}{2C_x(\sqrt{n} - 1)} \qquad (5)$$

Equation 5 implies that the output frequency is independent of the supply voltage and is dependent on temperature through the mobility term in k and the threshold voltage V_t. Note also that the bias voltage V_{bias} is chosen to be equal to the bandgap reference voltage produced from the previous stage, and is thus considered independent of voltage and temperature variations.

The *C*/*F* converter was designed and fabricated in 0.8 μm CMOS technology. A hybrid pressure measuring system composed of a capacitive pressure sensor (16) and the *C*/*F* chip. The system remains operational for a supply voltage down to 2.7 V and exhibiting high immunity to voltage variations from 3.7 to 5.5 V (Fig. 17). Simulated pressure pulses as those present in the aorta were measured using passive telemetry (Fig. 18).

CONCLUSIONS

Capacitive microsensors are in progressively increasing use in medical applications because of their advantages, such as small size, high sensitivity, and low power consumption. Silicon is the material of choice for these devices, which are finding applications for measuring pressure and



Figure 17. Pressure measuring system frequency output.



Figure 18. Simulated pressure pulses as those present in the aorta measured using passive telemetry.

acceleration, but also in ultrasound imaging and microphones and for monitoring body analytes. Actually, although most of the existing devices are not integrated together with signal conditioning electronic circuits on the same chip, in the future it is expected that there will be an increasing integration scheme driven by the need of higher level miniaturization. Because of their low power consumption advantage, capacitive microsensors are of interest as implantable monitoring devices. An attractive application appears to be a miniaturized telemetry system that combines techniques for wireless power and data transfer to a capacitive sensor integrated with signal conditioning electronics.

BIBLIOGRAPHY

1. Tufte ON, Chapman PW, Long D. Silicon Diffused-Element Piezoresistive Diaphragm. J Appl Phys 1962;33:3322–3327.
2. Smith CS. Piezoresistance Effect in Germanium and Silicon. Phys Rev 1954;94:42.
3. Samaun X, Wise KD, Angel JB. An IC Piezoresistive Pressure Sensor for Biomedical Instrumentation. IEEE Trans Biomed Eng 1973;BME-20(2):101–109.
4. Ko WH, Hynelek J, Boettcher SF. Development of a miniature Pressure Transducer for Biomedical Application. IEEE Trans Electron Dev 1979;ED-26:1896.
5. Data Science Int., Roseville Minnesota.
6. Konigberg Instruments Inc. Pasadena, California.
7. Clark SK, Wise KD. Pressure sensitivity in anisotropically etched thindiaphragm pressure sensors. IEEE Trans Electron Dev 1979;ED-26(12):1887–1896.
8. Sander GS, Knutti JW, Meindl JD. A monolithic Capacitance Pressure Sensor with Pulse Periodic Output. IEEE Trans Electron Dev 1980;ED-27(5):927–930.
9. Lee YS, Wise KD. A batch-fabricated Silicon Capacitive Pressure Transducer with low temperature Sensitivity. IEEE Trans Electron Dev 1982;ED-29(1):42–47.
10. Backlund Y, Rosengren L, Hök B. Passive Silicon Transensor Intended for biomedical, Remote Pressure monitoring. Sens Actuators 1990;A21(1–3):58–61.
11. Puers R, Peeters E, Van den Bossche A, Sansen W. A capacitive pressure sensor with low impedance output and active supression of parasitic effects. Sens Actuators 1990;A21 (1-3):108–114.
12. Goosen JFL. Design considerations for silicon sensors for use in catheters and guide wires. Smart Mater Struct 2002; 11:804–812.
13. Goustouridis D, Chatzandroulis S, Normand P, Tsoukalas D. A miniature self-aligned pressure sensing element. J Micromech Microeng 1996;6:33–35.
14. Zhu YZ, Wang AB. Miniature fiber optic pressure sensor. IEEE Photonic Technol 2005;17(2):447–449.
15. Melvås P, Kälvesten E, Enoksson P, Stemme G. A free-hanging strain-gauge for ultraminiaturized pressure sensors. Sens Actuators A 2002;97(8):75–82.
16. Chatzandroulis S, Tsoukalas D, Neukomm PA. A Miniature Pressure System with a Capacitive Sensor and a Passive Telemetry Link for Use in Implantable Applications. J MicroElectroMech S 2000;9(1):18–231.
17. Najafi N, Ludominky A. Initial Animal Studies of a Wireless, Batteryless, MEMS Implant for Cardiovascular Applications. Biomed Microdevices 2004;6(1):61–65.
18. Coosemans J, Catrysse M, Puers R. A readout circuit for an intra-ocular pressure sensor, Sens. Actuators A 2004;110 (1-3):432–438.
19. Hierold C, et al. Low power integrated pressure sensor for medical application. Sens Actuators A 1999;73(1–2):58–67.
20. Polliack AA, et al. Laboratory and clinical tests of a prototype pressure sensor for clinical assessment of prosthetic socket fit. Prosth Ortho Inter 2002;26(1):23–24.
21. Müller O, Parak WJ, Wiedemann MG, Martini F. Three-dimensional measurements of the pressure distribution in artificail joits with a capacitive sensor array. J Biomech 2004;37:1623–1625.
22. Luinge HJ, Veltink PH. Inclination measurement of human movement using a 30D accelerometer with autocalibration. IEEE T Neur Sys Reh 2004;12:112–121.
23. Puers R, Reyntjen S. Design and processing experiments of a new miniaturized capacitive triaxial accelerometer. Sens Actuators A 1998;68(1-3):324–328.
24. Lötters JC, Olthuis W, Veltink PH, Bergveld P. Design, realization and characterization of a symmetrical triaxial capacitive accelerometer for medical application. Sens Actuators A 1997;61(1-3):303–308.
25. Huang Y, et al. Fabricating capacitive micromachined ultrasonic transducers with wafer-bonding technology. J Microelectromech S 2003;12(2):128–137.
26. Cianci E, et al. One-dimensional capacitative micromachined ultrasonic transducer arrays for echographic probes. Microelect Eng 2004;73–74:502–507.
27. Knight J, McLean J, Degertekin FL. Low Temperature Fabrication of Immersion Capacitive Micromachined Ultrasonic Transducers on Silicon and Dielectric Substrates. IEEE Trans UFFC 2004;51:1324–1333.
28. Rombach P, Müllenborn M, Klein U, Rasmussen K. The first low voltage, low noise differential silicon microphone, technology development and measurement results. Sens Actuators A 2002;95:196–201.
29. Pederson M, Olthuis W, Bergveld P. High-performance condenser microphone with fully integrated CMOS amplifier and DC-DC voltage converter. J MicroElectroMech S 1998;7(4): 387–394.
30. Strong ZA, Wang AW, McConaghy CF. Hydrogel-actuated capacitive transducer for wireless biosensors. Biomed Microdevices 2002;4(2):97–103.
31. Petersen KE. Silicon as a mechanical material. Proc IEEE 1982;70(5):420–457.
32. de Boer MJ, et al. Guidelines for etching silicon MEMS structures using fluorine high-density plasmas at cryogenic temperatures. J MicroElectroMech S 2002;11(4):385–401.

33. Madou M. Fundamentals of Microfabrication: The Science of Miniaturization. 2nd ed. Boca Raton (FL): CRC Press; 2002.
34. Wallis G, Pomerantz DI. Field assisted glass-metal sealing. J Appl Phys 1969;40:3946–3949.
35. Ji J, Cho ST, Najafi K, Wise KD. An ultaminiature CMOS pressure sensor for a multiplexed Cardiovascular Catheter. IEEE Trans Electron Dev 1992;39:2260–2267.
36. Puers R, Van den Bossche A, Peeters E, Sansen W. An implantable pressure sensor for use in cardiology. Sens Actuators A 1990;23:944–947.
37. Tong QY, Gosele U. Semiconductor Wafer Bonding. New York: Wiley-Interscience; 1999.
38. Henttinen K, Suni I, Lau SS. Mechanically induced Si layer tranfer in hydrogen-implanted Si wafers. Appl Phys Lett 2000;76:2370–2372.
39. Goustouridis D, et al. Low temperature wafer bonding for thin silicon film transfer. Sens Actuators A 2004;110: 401–406.
40. Tsuchiya T, Funabashi H. A z-axis differential capacitive SOI accelerometer with vertical comb electrodes. Sens Actuators A 2004;116:378–383.
41. Kim C, Kim JY, Shridharan B. Comparative evaluation of drying techniques for surface micromachining. Sens Actuators A 1998;64:17–26.
42. Jin X, et al. Fabrication and characterization of surface micromachined capacitive ultrasonic immersion transducers. J Microelectromech S 1999;8:100–114.
43. Chae J, Kulah H, Najafi K. A CMOS-compatible high aspect ratio silicon-on-glass in-plane micro-accelerometer. J Micromech Microeng 2005;15:336–345.
44. Lysko JM, Jachowisz RS, Krzycki MA. Semiconductor pressure sensor based on FET structure. IEEE T Instrum Meas 1995;44:787–790.
45. Ko WH, Wang Q. Touch mode capacitive pressure sensors. Sens Actuators A 1999;75:242–251.
46. Hanneborg A, et al. An integrated capacitive pressure sensor with frequency-modulated output. Sens Actuators 1986; 9(4):345–351.
47. Senturia S. Microsystem Design. Boston: Kluwer Academic Publishers; 2000.
48. Matsumoto Y, Esashi M. Integrated silicon capacitive accelerometer with PLL servo technique. Sens Actuators A 1993; 39:209–217.
49. Van Der Goes FML, Meijer GCM. A universal transducer interface for capacitive and resistive sensor elements. Analog Integr Circuits Signal Process 1997;14:249–260.
50. Yazdi N, Mason A, Najafi K, Wise KD. A generic interface chip for capacitive sensors in low-power multi-parameter Microsystems. Sens Actuators A 2000;84:351–361.
51. Van Der Goes FML, Meijer GCM. A novel low-cost capacitive-sensor interface. Trans Instr Meas 1996;45(2):536–540.
52. Bracke W, Merken P, Puers R, Van Hoof C. On the optimization of ultra low power front-end interfaces for capacitive sensors. Sens Actuators A 2005;117(2):273–285.
53. Chatzandroulis S, Goustouridis D, Normand P, Tsoukalas D. A solid-state pressure-sensing microsystem for biomedical applications. Sens Actuators A 1997;62:551–555.
54. Casadei FW, Gerold M, Baldinger E. Implantable Blood Pressure Telemetry System. IEEE T Biomed Eng 1972;BME-19(5): 334–338.
55. Neukomm PA, Kuendig H. Passive wireless actuator control and sensor signal transmission. Sens Actuators 1990;A21-A23:258–262.
56. Tham KM, Nagaraj K. A low Supply Voltage High PSRR Voltage Reference in CMOS Process. IEEE J Solid-St Circ 1995;30(5):586–590.

See also BIOELECTRODES; INTEGRATED CIRCUIT TEMPERATURE SENSOR.

CARBON. See BIOMATERIALS: CARBON.

CARDIAC CATHETERIZATION. See CORONARY ANGIOPLASTY AND GUIDEWIRE DIAGNOSTICS.

CARDIAC LIFE SUPPORT. See CARDIOPULMONARY RESUSCITATION.

CARDIAC OUTPUT, FICK TECHNIQUE FOR

STEVEN C. FADDY
University of Sydney
Darlinghurst, Australia

INTRODUCTION

Cardiac output (CO) is an important measurement in many medical investigations. It is the amount of blood pumped by the ventricles of the heart and can be defined as the product of stroke volume (SV) and heart rate (HR), where stroke volume is the amount of blood expelled by the ventricle with each contraction and the HR is the number of contractions per minute:

$$\mathrm{CO} = \mathrm{SV} \times \mathrm{HR}$$

Cardiac output gives an indication of ventricular function and is also used in the calculation of a number of flow-dependent parameters, such as cardiac index, systemic vascular resistance, pulmonary vascular resistance, valve areas, and intracardiac shunt ratios.

The Fick technique is the gold standard in CO measurement. It relies on direct measurement of oxygen consumption and expenditure to derive the rate of blood flow throughout the individual.

HISTORY

In 1870, the German physiologist, Adolf Fick (1829–1901), described a novel method of determining cardiac output based on diffusion of respiratory gases in the lungs. This came after almost 30 years of work by Fick and numerous others, who reasoned that diffusion was one of the most essential events within the living organism. In 1855, Fick had published his findings relating to diffusion of gas across a fluid membrane. These became known as Fick's law of diffusion and stated that the rate of diffusion of a gas is proportional to the partial pressures of the gas on either side of the membrane, the area across which diffusion is taking place and the distance over which diffusion must take place. As an aside, Fick also invented contact lenses in 1887.

The 1870 publication by Adolf Fick stated: “It is astonishing that no one has arrived at the following obvious method by which [the amount of blood ejected by the ventricle of the heart with each systole] may be determined directly, at least in animals. One measures how much oxygen an animal absorbs from the air in a given time, and how much carbon dioxide it gives off. During the experiment one obtains a sample of arterial and venous blood; in both the oxygen and carbon dioxide content are measured. The difference in oxygen content tells how much oxygen each cubic centimeter of blood takes up in its passage through the lungs. As one knows the total quantity of oxygen absorbed in a given time one can calculate how many cubic centimeters of blood passed through the lungs in this time. Or if one divides by the number of heart beats during this time one can calculate how many cubic centimeters of blood are ejected with each beat of heart. The corresponding calculation with the quantities of carbon dioxide gives a determination of the same value, which controls the first (1)."

In simplest terms, cardiac output can be calculated as a ratio of the amount of oxygen consumed through breathing and the rate in which oxygen is taken up by the tissues.

$$\text{Cardiac Output} = \text{Oxygen consumption/Arteriovenous oxygen dierence}$$

It was not until the 1930s that quantitative measurement of the components allowed confirmation of the Fick equation as a means of calculating cardiac output.

PHYSIOLOGY OF THE FICK TECHNIQUE

Oxygen Consumption (VO_2)

The first step in calculating CO by the Fick technique is to determine the amount of oxygen consumed by the individual over a period of time. This is best done in the resting state so that there is constant oxygen consumption over the collection period. The traditional method is collection of expired gases in a Douglas bag over a period of $\sim$ 3 min. Then, from the volume of expired gas, the oxygen content of the expired gas and the oxygen content of the inspired room air, it is possible to calculate the amount of oxygen taken up by the individual.

Subtracting the oxygen content of expired gas from that of the inspired room air (%v/v or mL of $O_2 \cdot 100\ \text{mL}^{-1}$ of the gas) gives the oxygen difference between the inspired and expired gases, expressed in mL of $O_2 \cdot 100\ \text{mL}^{-1}$ of expired gas. Applying a factor of 10 gives this figure as milliliters of O_2 per liter of expired gas, which are the units used later in the calculation. Dividing the total volume of expired gas by the collection time gives the minute ventilatory rate, expressed in liters per minute $\text{L} \cdot \text{min}^{-1}$.

The product of the O_2 difference ($\text{mL} \cdot \text{L}^{-1}$) and the minute volume ($\text{L} \cdot \text{min}^{-1}$) is the oxygen consumption (VO_2) expressed in milliliters of oxygen absorbed per minute.

$$VO_2 = (O_{2\,\text{Room air}} - O_{2\,\text{expired}}) \times (\text{volume/time})$$

$$\begin{aligned} \textit{Example}: \quad & \text{Inspired}\,O_2 = 21.0\,\text{mL} \cdot 100\,\text{mL}^{-1}\,\text{room air} \\ & \text{Expired}\,O_2 = 16.7\,\text{mL} \cdot 100\,\text{mL}^{-1}\,\text{expired gas} \\ & O_2\,\text{difference} = 21.0 - 16.7 = 4.3\,\text{mL} \cdot 100\,\text{mL}^{-1} \\ & \text{Total volume expired} = 26.1\,\text{L} \\ & \text{Collection time} = 3\,\text{min} \\ & \text{Minute volume} = 26.1\,\text{L} \cdot 3\,\text{min}^{-1} = 8.7\,\text{L} \cdot \text{min}^{-1} \\ & \text{Therefore,} \\ & O_2\text{consumption} = (4.3 \times 10)\text{mL} \cdot \text{L}^{-1} \times \\ & \qquad 8.7\,\text{L} \cdot \text{min}^{-1} = 374\,\text{mL} \cdot \text{min}^{-1} \end{aligned}$$

An alternative to the Douglas bag method is the use of a metabolic rate meter with a hood or facemask, a variable-speed blower and a servocontrol loop with an oxygen sensor. This method employs essentially the same principle as the Douglas bag method, but gives a real-time measurement of VO_2. The variable-speed blower maintains a flow of room air through the hood or facemask past the patient into a polarographic oxygen sensor (gold and silver–silver chloride electrode), varying the flow in order to keep the oxygen concentration at the measuring electrode constant. By keeping the oxygen concentration at the measuring electrode constant, the only variable is the flow rate through the system. Under steady-state conditions, this is the only variable determining the oxygen consumption (VO_2).

Although this method provides a real-time measurement of VO_2, thus excluding the need for collection of a Douglas bag, it is still rather time and labor intensive. In addition, it has been suggested that it is difficult to obtain reproducible results and the method gives consistently lower results then the Douglas bag technique.

Arteriovenous Difference

As with oxygen consumption, measurement of oxygen uptake by the body involves measuring blood oxygen content before and after entering the lungs. The arteriovenous oxygen difference (AV_{diff}) is the difference between the content of oxygen (ctO_2) in the oxygenated arterial blood leaving the lungs and the deoxygenated venous blood returning to the lungs (mL O_2 per 100 mL of blood). The AV_{diff} represents the volume of oxygen delivered to meet the body's metabolic demands. Again, this figure is multiplied by 10 to give the AV_{diff} in units of mL O_2 per liter of blood.

$$AV_{\text{diff}} = ctO_{2(\text{Arterial})} - ctO_{2(\text{Venous})}$$

$$\begin{aligned} \textit{Example}: \quad & \text{Arterial}\,O_2\,\text{content} = 19.5\,\text{mL} \cdot \text{dL}^{-1}\,\text{blood} \\ & \text{Venous}\,O_2\,\text{content} = 13.2\,\text{mL} \cdot \text{dL}^{-1}\,\text{blood} \\ & AV_{\text{diff}} = 19.5 - 13.2 = 6.3\,\text{mL} \cdot \text{dL}^{-1} = 63\,\text{mL} \cdot \text{L}^{-1} \end{aligned}$$

Typically, a sample from the main pulmonary artery is used for venous blood and a sample from the left ventricle or aorta is used for arterial blood oxygen content measurements.

Cardiac Output

The rate at which oxygen is taken up by the lungs and the rate at which it is taken up by the body is now known from the above calculations. The ratio of these two figures gives the cardiac output. The examples above show that the lungs take up 374 mL of oxygen each minute and that the blood takes up 63 mL of oxygen for each liter that passes through the lungs. How many lots of 63 mL (1 L aliquots of blood) must pass through the lungs to take up 374 mL of oxygen each minute? The answer is 5.9 L of blood must pass through the lungs each minute in order to absorb this amount of inspired oxygen.

$$\begin{aligned} \textit{Example}: \quad & VO_2 = 374\,\text{mL} \cdot \text{min}^{-1} \\ & AV_{\text{diff}} = 63\,\text{mL} \cdot \text{L}^{-1} \\ & CO = 374/63 = 5.9\,\text{L} \cdot \text{min} \end{aligned}$$

PRACTICAL CONSIDERATIONS FOR USING THE FICK TECHNIQUE

Oxygen Consumption

The measured volume of a gas is affected in part by the ambient temperature and atmospheric pressure in which it is collected. Obviously, these will vary from day to day, leading to a potential source of variation in the calculation of oxygen consumption, and ultimately, cardiac output. The combined gas law (a combination of Boyle's and Charles' law) describes the relationship of pressure, temperature, and volume in a gas. This law can be used to correct measured gas volumes to standard temperature and pressure (STP). This means that the measured volume of gas is standardised to 273 K and 760 mmHg (101.32 kPa).

As well as correcting for variations in atmospheric pressure, it is also necessary to correct for water vapor pressure. Dalton's law tells us that the pressure of a gas mixture is equal to the partial pressures of all of the components of the mixture. Water vapor is present in the atmosphere and in exhaled gas and its partial pressure contributes to the total atmospheric pressure. Water vapor exerts a constant pressure at a given temperature, regardless of the atmospheric pressure. Water vapor pressure is 47 mmHg (6.26 kPa) at normal body temperature and 17.5 mmHg at (2.33 kPa) 20 °C. Before correcting for STP it is necessary to subtract the water vapor pressure from the total atmospheric pressure to obtain the dry gas pressure at the ambient temperature. This is known as 'standard temperature and pressure, dry' (STPD), which is used for the correction.

Example : Atmospheric pressure $= 762\,\text{mmHg}\,(6.26\,\text{kPa})$
Ambient temperature $= 23\,^\circ\text{C}$
Water vapor pressure at
$23\,^\circ\text{C} = 21\,\text{mmHg}\,(2.79\,\text{kPa})$
Dry gas pressure $= 762 - 21\,\text{mmHg}$
$= 741\,\text{mmHg}\,(98.79\,\text{kPa})$
STPD correction factor for 741 mmHg and
$23\,^\circ\text{C} = 0.8991$ {from standard tables}
Volume of expired gas $= 9.68\,\text{L}\cdot\text{min}^{-1}$
STPD corrected volume $= 9.68 \times 0.8991$
$= 8.7\,\text{L}\cdot\text{min}^{-1}$

By standardizing to STPD, we have removed the effect of water vapor pressure, ambient pressure, and temperature on the volume measurement and, hence, potential sources of day to day variation in measurement of the cardiac output.

Arteriovenous Oxygen Difference

Although many current generation analyzers can calculate oxygen content (ctO_2), earlier models did not. It may be necessary to manually calculate oxygen content from the hemoglobin level (Hb) and oxygen saturation of a sample. Hemoglobin is able to carry 1.36 mL of oxygen per gram of hemoglobin. Therefore, by multiplying the hemoglobin level by 1.36 it is possible to calculate the oxygen carrying capacity of the individual. Simply stated, this is the maximum amount of oxygen that can be carried by 100 mL of the individual's blood and is dependent on the hemoglobin level. Some textbooks have quoted the constant as 1.34 and others add a value of 0.03 to account for oxygen dissolved in plasma, but 1.36 is the generally accepted constant for calculation of oxygen carrying capacity.

$$\text{Oxygen carrying capacity} = \text{Hgb} \times 1.36\,\text{mL}\cdot\text{dL}^{-1}$$

If the total amount of oxygen that the blood is capable of carrying and the saturation of the sample is known, it is possible to calculate the oxygen content of that sample.

$$ctO_2 = \text{oxygen carrying capacity} \times \%\,\text{saturation}$$

The arteriovenous oxygen difference is the difference in oxygen content between arterial and venous blood.

Example : $\text{Hb} = 14.5\,\text{g}\cdot\text{dL}^{-1}$
Oxygen carrying capacity $= 14.5 \times 1.36$
$= 19.72\,\text{mL}\cdot\text{dL}^{-1}$
Arterial saturation $= 98.9\%$
Arterial oxygen content $= 19.72 \times 98.9\%$
$= 19.5\,\text{mL}\cdot\text{dL}^{-1}$
Venous saturation $= 66.9\%$
Venous oxygen content $= 19.72 \times 66.9\%$
$= 13.2\,\text{mL}\cdot\text{dL}^{-1}$

Therefore,

$$\text{AV}_{\text{diff}} = 19.5 - 13.2 = 6.3\,\text{mL}\cdot\text{dL}^{-1} = 63\,\text{mL}\cdot\text{L}^{-1}$$

In this example, each liter of blood leaving the lungs delivers 63 mL of oxygen to the tissues.

Figure 1 shows a complete example of CO measurement using the Fick technique.

ASSUMPTIONS WHEN USING THE FICK TECHNIQUE FOR CARDIAC OUTPUT

Absence of Intracardiac Shunt

The method of calculating cardiac output described above uses the amount of oxygen absorbed by the blood as it travels through the lungs. We then assume that the amount of blood pumped by the right ventricle through the lungs is equal to the amount pumped by the left ventricle through the systemic vessels since the cardiovascular system is a closed system. This assumption does not always hold true and it is sometimes necessary to alter the calculation.

The term shunt describes the condition where a communication exists between the left- and right-sided chambers of the heart. If this condition results in shunting of blood between the venous and arterial circulation, the assumption becomes invalid because some blood is being recirculated through part of the circuit and the two ventricles are pumping unequal volumes. If an intracardiac shunt is known or suspected, it is necessary to collect blood samples at different points than the standard arterial and pulmonary artery sites. Calculation of cardiac output and



A. Standard Temperature and Pressure

Atmospheric pressure = 762 mmHg
Ambient temperature = 23 °C
Water vapor pressure at 23 °C = 21 mmHg
Dry gas pressure = 762 – 21 mmHg = 741 mmHg
STPD correction factor for 741 mmHg and 23 °C = **0.8991**

B. Volume measurement

Total volume expired = 28.14 L
Collection time = 3 min
Minute volume = $28.14\ \text{L}\cdot 3\ \text{min}^{-1}$ = **9.68** $\text{L}\cdot\text{min}^{-1}$

STP corrected volume
$0.8991 \times 9.68\ \text{L}\cdot\text{min}^{-1}$ = **8.7** $\text{L}\cdot\text{min}^{-1}$

C. Oxygen Difference

Inspired O_2 = $21.0\ \text{mL}\ 100\ \text{mL}^{-1}$
Expired O_2 = $16.7\ \text{mL}\ /100\ \text{mL}^{-1}$
O_2 difference = 21.0 – 16.7 = **4.3** $\text{mL}/100\ \text{mL}^{-1}$

D. Oxygen Consumption

O_2 consumption = $(4.3 \times 10)\ \text{mL}\cdot\text{L}^{-1} \times 8.7\ \text{L}\cdot\text{min}^{-1}$ = **374** $\text{mL}\cdot\text{min}^{-1}$

E. Arteriovenous O_2 Difference

Arterial O_2 content = $19.5\ \text{mL}\cdot\text{dL}^{-1}$ blood
Venous O_2 content = $13.2\ \text{mL}\cdot\text{dL}^{-1}$ blood
AV_{diff} = 19.5 – 13.2 = $6.3\ \text{mL}\cdot\text{dL}^{-1}$ = **63** $\text{mL}\cdot\text{L}^{-1}$

F. Cardiac Output

VO_2 = $374\ \text{mL}\cdot\text{min}^{-1}$
AV_{diff} = $63\ \text{mL}\cdot\text{L}^{-1}$
Cardiac output = 374 / 63 = **5.9** $\text{L}\cdot\text{min}^{-1}$

Figure 1. Example of cardiac output measurement using the Fick technique. The arrows indicate how the various parameters discussed in the text are interrelated in the various calculations.

shunt ratios in the presence of an intracardiac shunt is discussed later in this article.

Collection of True Arterial Sample

In a normal heart, it is not easy to gain access to the pulmonary veins to collect an arterial sample as the blood leaves the lungs. As a result, left ventricular or aortic blood is used to measure arterial oxygen content. This method ignores the small amount of venous admixture from bronchial and thebesian venous drainage into the left atrium.

Direct Measurement of Oxygen Consumption

Owing to the time- and labor-intensive methods of measurement of oxygen consumption (VO_2), there is often a temptation to use an estimate of oxygen consumption rather than direct measurement. Standard formulas and nomograms are used to estimate VO_2 from height, weight, age, and sex. The body surface area (BSA) is calculated from height and weight and expressed in units of square meters (m^2).

$$\text{BSA} = 0.007184 \times \text{weight}^{0.425} \times \text{height}^{0.725}$$

Age, sex, and basal metabolic rate are used to determine heat production from standard nomograms. Finally, heat production and BSA are used to estimate the oxygen consumption.

$$VO_2 = [\text{BSA} \times \text{Heat Production}]/291.72$$

This method estimates the basal oxygen consumption at rest. It does not make allowances for any pathological conditions, including those being investigated, that may affect the resting oxygen consumption. Studies comparing measured and estimated VO_2 have shown that estimating VO_2 from the various available formulas can lead to large and unpredictable errors in both VO_2 and cardiac output values (2,3). The practice of estimating VO_2 is strongly discouraged.

DETECTION AND ASSESSMENT OF INTRACARDIAC SHUNTS

Earlier in this article it was seen how the oxygen content of blood entering and leaving the lungs was used to calculate the cardiac output. It was assumed that blood flowing through the lungs is equal to blood flowing through the systemic circulation (since the cardiovascular system is a closed circuit). Several conditions may result in blood being recirculated between the left and right sides of the heart, leading to unequal flow in the pulmonary and systemic circulation. These conditions include atrial septal defects, patent foramen ovale, ventricular septal defects, and patent ductus arteriosus. Patent foramen ovale has been estimated to be present in 27.3% of the population (4), but the presence of a defect does not necessarily result in intracardiac shunting.

A communication between the left- and right-sided chambers of the heart can result in blood being shunted from right to left (venous blood being mixed into the arterial circulation), left to right (arterial blood being mixed into the pulmonary circulation), or as a bidirectional shunt (blood moves back and forth across the communication at different stages of the cardiac cycle). Although the method of calculating cardiac output remains essentially the same, the sites of blood collection are different in cases where intracardiac shunting exists. The following passages describe the methods for calculating systemic and pulmonary flow in the presence of different intracardiac shunts.

Left-to-Right Shunt

In a left-to-right shunt, arterial blood is pushed across the defect into the pulmonary circulation. This will artificially elevate the oxygen saturation and oxygen content in the pulmonary artery. To avoid error in the calculation of systemic cardiac output in the presence of a left-to-right shunt, it is necessary to collect the venous blood sample in the chamber immediately proximal to the shunt. In the case of atrial defects, blood is collected from both the inferior and superior vena cavae. Oxygen content (ctO_2) from these sites is used in the calculation of mixed venous oxygen content (MVO_2). The individual values are weighted and averaged according to the relatively higher flow from the superior vena cava and the absence of coronary sinus blood in the measurements. The generally accepted formula used for estimation of mixed venous oxygen content is

$$MVO_2 = [3 \times ctO_{2(SVC)} + ctO_{2(IVC)}]/4$$

MVO_2 becomes the venous component of the arteriovenous difference calculation and cardiac output (systemic flow, Q_s) is calculated as described earlier.

It is also possible to calculate pulmonary flow (Q_p) by using the pulmonary artery oxygen content as the venous component (blood entering the lungs) and left ventricular or aortic oxygen content as the arterial component (blood leaving the lungs). The pulmonary flow is equal to the systemic flow returning to the heart plus the volume being recirculated from the left-sided chambers via the shunt. This is reflected in the CO calculation. Because of the recirculated arterial blood, the venous oxygen content in the pulmonary artery will be elevated, leading to a decrease in the arteriovenous difference and, hence, a higher pulmonary flow.

Right-to-Left Shunt

The opposite occurs in a right-to-left shunt. Venous blood is mixed into the arterial circulation leading to a decrease in systemic arterial oxygen saturation. The calculation of systemic flow (Q_s) uses the arterial and venous (pulmonary artery) samples as usual. The calculation of pulmonary flow (Q_p) requires a sample to be taken after the blood leaves the lungs, but proximal to the shunt. In a right-to-left shunt it is necessary to sample blood from the pulmonary veins. In practical terms, this requires the catheter to pass from the right atrium across the defect to the left atrium and then into a pulmonary vein. Pulmonary vein oxygen content becomes the arterial component of the arteriovenous difference and pulmonary flow is calculated as usual.

In the presence of a right-to-left shunt, systemic flow is equal to the pulmonary flow leaving the lungs plus the amount that passes across the shunt directly from the right-sided chambers. Sampling in the left ventricle or aorta distal to the shunt will therefore give a lower arterial oxygen content than would be measured in the pulmonary veins, leading to an decrease in the arteriovenous difference and, hence, a higher systemic flow compared to the pulmonary flow.

A right-to-left shunt should be suspected in any patient who has an arterial oxygen saturation less than 95%. Investigation of these patients should include assessment for the presence of a bidirectional shunt.

Bidirectional Shunt

The presence of a bidirectional shunt complicates the calculation of pulmonary and systemic flow. Neither of the methods described above is suitable since both assume shunting in only one direction. The systemic blood flow (SBF) is calculated using oxygen contents sampled at the sites where blood enters and leaves the systemic circulation (arterial and mixed venous sites, respectively). Pulmonary blood flow (PBF) is calculated using sampling sites where blood enters and leaves the lungs (pulmonary artery and pulmonary vein, respectively). Finally, effective blood flow (EBF) is calculated using samples taken where the blood enters the heart and leaves the lungs (mixed venous and pulmonary vein oxygen contents). The mixed venous oxygen values should be the same as the pulmonary artery sample if no shunts are present. Similarly, the pulmonary vein should be the same as the left ventricular or aortic

$VO_2 = 201\ \text{mL·min}^{-1}$

$\text{Hb} = 13.9\ \text{g·dL}^{-1}$

Oxygen carrying capacity = $13.9 \times 1.36 = 18.9\ \text{mL·dL}^{-1}$

Site	Saturation %	ctO_2 mL·dL^{-1}
Arterial		
Pulmonary vein (PV)	94.1	17.8
Radial artery (RArt)	83.0	15.7
Venous		
Superior vena cava (SVC)	58.6	11.1
Inferior vena cava (IVC)	61.0	11.6
Right atrium (RA)	68.8	13.0
Pulmonary artery (PA)	63.4	12.0
Mixed venous (MV) = (3 × SVC + IVC)/4	59.2	11.2

Pressure measurements

Mean Pulmonary Artery pressure = 43 mmHg (5.73 kPa)

Mean Left Atrial pressure = 4 mmHg (0.53 kPa)

$$\text{PBF} = \frac{VO_2}{ctO_{2\,(PV)} - ctO_{2\,(PA)}} = \frac{201}{17.8 - 12.0} = 3.5\ \text{L·min}^{-1}$$

$$\text{SBF} = \frac{VO_2}{ctO_{2\,(R\,Art)} - ctO_{2\,(MV)}} = \frac{201}{15.7 - 11.2} = 4.5\ \text{L·min}^{-1}$$

$$\text{EBF} = \frac{VO_2}{ctO_{2\,(PV)} - ctO_{2\,(MV)}} = \frac{201}{17.8 - 11.2} = 3.0\ \text{L·min}^{-1}$$

$$\text{Left-to-right shunt} = \text{PBF} - \text{EBF} = 3.5 - 3.0 = 0.5\ \text{L·min}^{-1}$$

$$\text{Right-to-left shunt} = \text{SBF} - \text{EBF} = 4.5 - 3.0 = 1.5\ \text{L·min}^{-1}$$

$$\text{PVR} = \frac{80 \times (\text{PA}_m - \text{LA}_m)}{Q_p} = \frac{80 \times (43 - 4)}{3.5} = 891\ \text{dyn·s·cm}^{-5}$$

Figure 2. Bidirectional shunt calculation in a 55 year old woman with Eisenmenger's syndrome secondary to an atrial septal defect (ASD). Note the predominantly right-to-left shunt due to increased pulmonary vascular resistance. These results show little deterioration compared to measurements taken six months earlier [$Q_p = 3.7\ \text{L}\cdot\text{min}^{-1}$, mean PA pressure = 39 mmHg (5.19 kPa) and PVR = 800 $\text{dyn}\cdot\text{s}\cdot\text{cm}^{-5}$].

sample in the absence of any shunts. Therefore, by sampling at these sites, the pulmonary (and hence, systemic) flow that would normally occur if no shunts were present is being calculated

$$\begin{aligned} \text{SBF} &= VO_2/[ctO_{2(\text{Art})} - ctO_{2(\text{MV})}] \\ \text{PBF} &= VO_2/[ctO_{2(\text{P vein})} - ctO_{2(\text{P art})}] \\ \text{EBF} &= VO_2/[ctO_{2(\text{P vein})} - ctO_{2(\text{MV})}] \end{aligned}$$

Since the systemic flow (SBF), pulmonary flow (PBF), and the flow that would occur in the absence of any shunts (EBF) is known, the size of the shunts can also be calculated

$$\begin{aligned} \text{Right to left} &= \text{SBF} - \text{EBF} \\ \text{Left to right} &= \text{PBF} - \text{EBF} \end{aligned}$$

Figure 2 shows calculations for a bidirectional shunt based on the principles discussed above. Note the changes in oxygen saturation and content as blood passes the atrial defect. In the left heart, oxygen saturation decreases as blood passes from pulmonary veins to the left ventricle due to mixing of deoxygenated blood being shunted across the defect. Conversely, oxygen saturation in the right heart increases as blood passes from the vena cavae (mixed venous) to pulmonary artery due to oxygenated blood being shunted across the defect from the left atrium.

Pulmonary–Systemic Flow Ratio

An alternative to calculating flow across a defect is to calculate the pulmonary/systemic flow ratio (P/S ratio). This value is a ratio of the pulmonary flow relative to the systemic flow. Calculation of the P/S ratio does not involve calculation of actual flows, so it is not necessary to collect expired gases to calculate the VO_2. The P/S ratio is calculated using only the oxygen content (or saturation) from arterial, pulmonary artery, mixed venous, and pulmonary vein samples.

The AV_{diff} for the pulmonary component is calculated by subtracting mixed venous oxygen content from systemic arterial oxygen content. The systemic AV_{diff} is calculated by subtracting the pulmonary artery oxygen content from the pulmonary vein oxygen content. If a pulmonary vein sample is not possible, use an estimate of 98% unless the arterial saturation is higher. Using arterial oxygen content to estimate the pulmonary vein content will assume that there is no right-to-left shunt. The P/S ratio (or P:S ratio) is the calculated by dividing the pulmonary component by the systemic component.

The P/S ratio is the proportion of flow through the pulmonary circulation relative to the systemic circulation. Therefore, a value > 1.0 indicates left-to-right shunting. An arbitrary value of between 1.5 and 2.0 is often used to determine the need for definitive treatment to correct the defect, in order to avoid late sequelas from prolonged pulmonary vascular overload. A P/S flow ratio < 1 indicates right-to-left shunting and may be a sign of irreversible pulmonary vascular disease.

$$\textit{Example}: \mathrm{Hb} = 14.5\,\mathrm{g}\cdot\mathrm{dL}^{-1}$$

$$\text{Oxygen carrying capacity} = 19.72\,\mathrm{mL}\cdot\mathrm{dL}^{-1}$$

$$\begin{aligned}&\text{Arterial oxygen content} = 98.9\%\\ &\quad ctO_{2(Art)} = 19.5\,\mathrm{mL}\cdot\mathrm{dL}^{-1}\\ &\text{Pulmonary artery oxygen content} = 66.9\%\\ &\quad ctO_{2(PA)} = 13.2\,\mathrm{mL}\cdot\mathrm{dL}^{-1}\\ &\text{Mixed venous oxygen content} = 63.1\%\\ &\quad ctO_{2(MV)} = 12.4\,\mathrm{mL}\cdot\mathrm{dL}^{-1}\end{aligned}$$

$$\begin{aligned}\text{Pulmonary}:\quad & ctO_{2(Art)} - ctO_{2(MV)} && = 19.5 - 12.4\\ & && = 7.1\,\mathrm{mL}\cdot\mathrm{dL}^{-1}\\ \text{Systemic}:\quad & ctO_{2(PV)} - ctO_{2(PA)} && = 19.5 - 13.2\\ & && = 6.3\,\mathrm{mL}\cdot\mathrm{dL}^{-1}\end{aligned}$$

$$\text{P/S ratio}:\ 7.1/6.3 = 1.13$$

FLOW-DEPENDENT PARAMETERS

A number of frequently used parameters in cardiovascular medicine are dependent on knowing systemic or pulmonary flow. Calculation of these parameters, and the effect that the cardiac output has on each, is discussed. Table 1 lists expected normal ranges for a number of common flow-dependent parameters.

Cardiac Index

Cardiac output is often corrected for patient's size, based on body surface area (BSA). Cardiac index (CI) is calculated by dividing the cardiac output by the body surface area.

$$\mathrm{CI} = \mathrm{CO/BSA}\ \mathrm{L}\cdot\mathrm{min}^{-1}\cdot\mathrm{m}^{-2}$$

Table 1. Expected Ranges for Common Flow-Dependent Parameters

$$\text{Cardiac Output} = \frac{\text{Oxygen consumption}}{\text{Arteriovenous oxygen difference}}$$

$$VO_2 = \frac{\text{BSA} \times \text{Heat Production}}{291.72}$$

$$\mathrm{MVO_2} = \frac{3 \times ctO_{2(SVC)} + ctO_{2(IVC)}}{4}$$

$$\mathrm{SBF} = \frac{VO_2}{ctO_{2(Art)} - ctO_{2(MV)}}$$

$$\mathrm{PBF} = \frac{VO_2}{ctO_{2(P\,vein)} - ctO_{2(P\,art)}}$$

$$\mathrm{EBF} = \frac{VO_2}{ctO_{2(P\,vein)} - ctO_{2(MV)}}$$

$$\mathrm{CI} = \frac{\mathrm{CO}}{\mathrm{BSA}}\,\mathrm{L}\cdot\mathrm{min}^{-1}\cdot\mathrm{m}^{-2}$$

$$\text{Area} = \frac{\left\{\frac{\mathrm{CO}}{(\mathrm{SEP}\times\mathrm{HR})}\right\}}{(44.3 \times \sqrt{\text{gradient}})}$$

$$\text{Area} = \frac{\text{Cardiac output}}{\sqrt{\text{Gradient}}}$$

$$\text{Area} = \frac{(\mathrm{CO} \times \mathrm{DFP} \times \mathrm{HR})}{37.7 \times \sqrt{\text{gradient}}}$$

$$\mathrm{SVR} = \frac{80 \times (Ao_m - RA_m)}{Q_s}$$

$$\mathrm{PVR} = \frac{80 \times (PA_m - LA_m)}{Q_p}$$

$$\mathrm{CO} = \frac{VCO_2}{ctCO_{2(Ven)} - ctCO_{2(Art)}}$$

$$\mathrm{CO} = \frac{\Delta VCO_2}{\Delta ctCO_{2(Art)}}$$

$$\mathrm{CO} = \frac{\Delta VCO_2}{S \times \Delta ETCO_2}$$

Some believe cardiac index is a more useful parameter than cardiac index because it accounts for the patient's size. A large person (as approximated by BSA) would be expected to have a higher cardiac output while a low cardiac output in a smaller person may not necessarily be indicative of a poorly functioning ventricle. Many authors only express cardiac output in terms of cardiac index for this reason.

Valve Areas

Basic fluid dynamic principles state that a fluid exerts pressure equally in all directions. Therefore, when the valves of the heart are open they should allow equalisation of pressure in the two chambers that they separate. Sometimes the valves of the heart become stiff, thickened or do not open properly, inhibiting flow through the valve. This is referred to as valve stenosis. A result of this process is a pressure gradient, a difference in pressure on either side of the valve. Take an example of aortic valve stenosis. When the left ventricle contracts, it is pushing against an obstruction. The systolic pressure will be higher in the ventricle that in the aorta. The difference in pressure is referred to as a pressure gradient (expressed in mmHg) and can be measured during cardiac catheterisation. The pressure gradient across a valve is often used to determine the severity of a valve stenosis. However, the main parameter that should be considered is the cross-sectional area of the valve. A pressure gradient of 20 mmHg (2.66 kPa) is often considered an indication of mild aortic stenosis. However, in the presence of low cardiac output, it is necessary to have quite a narrow valve orifice to achieve this gradient. Conversely, a less severe stenosis could achieve a gradient of 50 mmHg (6.66 kPa) in a patient with a high cardiac output.

Both the cardiac output and mean pressure gradient are used in the calculation of valve area. The Gorlin formula is used for calculating valve area of the aortic or pulmonary valve:

$$\text{Area} = [\{\text{CO}/(\text{SEP} \times \text{HR})\}/(44.3 \times \sqrt{\text{gradient}})]$$

where HR is the heart rate and SEP is the systolic ejection period (since gradients in these valves are measured during systole). However, a shorter formula is often used as an approximation:

$$\text{Area} = \text{Cardiac output}/\sqrt{\text{Gradient}}$$

Taking the example of aortic stenosis, a mean gradient of 20 mmHg (2.66 kPa) in a patient with a normal cardiac output of $4.5\,\text{L}\cdot\text{min}^{-1}$ would give a valve area of $4.5/\sqrt{20} = 1.00\,\text{cm}^2$. In a patient with a low cardiac output of $3.1\,\text{L}\cdot\text{min}^{-1}$, the valve area ($3.1/\sqrt{20} = 0.69\,\text{cm}^2$) would be much smaller to achieve this gradient. Similarly, our patient with a mean gradient of 50 mmHg (6.66 kPa) would not have such a severe narrowing if a high cardiac output (e.g., $7.1\,\text{L}\cdot\text{min}^{-1}$) is present ($7.1/\sqrt{50} = 1.00\,\text{cm}^2$).

The Gorlin formula for calculating mitral or tricuspid valve area is slightly different:

$$\text{Area} = (\text{CO} \times \text{DFP} \times \text{HR})/(37.7 \times \sqrt{\text{gradient}})$$

where DFP is the diastolic filling period (since gradients in these valves are measured during diastole).

Vascular Resistance

Measurements of vascular resistance are based on principles of fluid dynamics where resistance is defined as the decrease in pressure between two points in a vascular segment divided by the flow through that segment. While this simplification does not account for pulsatile flow, calculation of vascular resistance in this way is useful in a number of clinical settings.

In the past, Wood units ($\text{mmHg}\cdot\text{L}\cdot\text{min}^{-1}$) were used to express vascular resistance. Today, vascular resistance is more commonly expressed in absolute resistance units (dyn.s.cm^{-5}), which are derived from the mean pressure gradient ($\text{dyn}\cdot\text{cm}^{-2}$) divided by the mean flow ($\text{cm}^3\cdot\text{s}^{-1}$). A constant of 80 is used to convert values from traditional units (mmHg and $\text{L}\cdot\text{min}^{-1}$) to absolute resistance units.

Systemic vascular resistance (SVR) is therefore defined as the difference in pressure between blood entering the systemic circulation (mean aortic pressure) and blood leaving the systemic circulation (mean right atrial pressure) divided by the systemic blood flow:

$$\text{SVR} = [80 \times (A\text{O}_\text{m} - \text{RA}_\text{m})/Q_\text{s}]$$

Similarly, pulmonary vascular resistance (PVR) is defined as the difference between mean pulmonary artery pressure and mean left atrial pressure divided by the pulmonary flow:

$$\text{PVR} = [80 \times (\text{PA}_\text{m} - \text{LA}_\text{m})/Q_\text{p}]$$

In the absence of intracardiac shunting both SVR and PVR can be calculated using the standard cardiac output measurement. If intrapulmonary shunting is present, systemic and pulmonary flow must be individually calculated for use in the SVR and PVR calculations, respectively.

There are a number of causes of increased systemic or pulmonary vascular resistance, some reversible and some permanent. The use of serial cardiac output and pressure measurements during drug challenges can assist in identifying management strategies that may be helpful in reducing vascular resistance.

VARIATIONS OF THE FICK METHOD

The Fick principle can be applied to any gas involved in diffusion, including carbon dioxide. Such variations to the classic Fick formula are often referred to as the indirect Fick principle.

By measuring the difference between inspired and expired CO_2 and the minute ventilation volume we can calculate CO_2 production ($V\text{CO}_2$). Arteriovenous CO_2 difference is calculated from the measured values of arterial and venous carbon dioxide content (ctCO_2). The ratio of $V\text{CO}_2$ and the arteriovenous CO_2 difference gives the cardiac output.

Earlier in this article it was seen how the oxygen content (ctO_2) of blood is calculated from the amount of hemoglobin and oxygen saturation of the sample, since nearly all of the oxygen is bound to hemoglobin. A relatively smaller proportion of CO_2 is bound to hemoglobin. About 70% is transported in the blood as bicarbonate. Only 23% is bound to hemoglobin and 7% is transported as dissolved CO_2. Therefore, the calculation of CO_2 content is not dependent on hemoglobin level.

Carbon dioxide content (ctCO_2) is calculated from the formula:

$$\text{ctCO}_2 = 11.02 \times P\text{CO}_2^{0.396}$$

Thus, if we have partial CO_2 pressure of arterial ($P\text{aCO}_2$) and venous ($P\text{vCO}_2$) samples, we can calculate the arteriovenous carbon dioxide difference as

$$\text{ctCO}_{2(\text{Ven})} - \text{ctCO}_{2(\text{Art})} = 11.02(P\text{vCO}_2^{0.396} - P\text{aCO}_2^{0.396})$$

Then cardiac output is calculated with the formula:

$$\text{CO} = V\text{CO}_2/(\text{ctCO}_{2(\text{Ven})} - \text{ctCO}_{2(\text{Art})})$$

There are some advantages to using the carbon dioxide method. When a patient is receiving high concentrations of supplemental oxygen, analysis of inspired and expired oxygen will give a small difference between two relatively large values. Even a small error in the estimation of either value will yield an inaccurate VO_2. Additionally, some oxygen analysers (e.g., paramagnetic analyzers) have poor accuracy at high oxygen concentrations. Measurement of cardiac output in patients receiving high concentrations of supplemental oxygen may be erroneous and the Fick principle using carbon dioxide may prove more accurate.

Applying the Fick principle to carbon dioxide involves the same steps as using oxygen for the calculation. There is still the requirement for analysis of expired gases, as well as collection and analysis of arterial and mixed venous blood samples. However, there are a number of ways of estimating, rather than directly measuring, the various parameters necessary to calculate cardiac output using the Fick CO_2 technique.

Infrared (IR) light absorption sensors in the breathing circuit can measure inspired and expired CO_2 content. Alternatively, an assumption can be made about the content of CO_2 in the inhaled gas (especially if the patient is being ventilated with 100% oxygen) and only expired CO_2 needs to be measured. Along with an airflow sensor (e.g., as a differential pressure pneumotachometer), these measurements can provide real-time estimation of VCO_2.

There is a logarithmic relationship between cardiac output and end-tidal CO_2 ($ETCO_2$). At normal or high cardiac output the respiratory rate determines the amount of CO_2 that is eliminated by the lungs with each breath. If it is assumed that CO_2 exchange at the alveolar–arterial membrane reaches equilibrium, then $ETCO_2$ can be used to estimate $PaCO_2$. In this way, it is possible to estimate cardiac output without subjecting the patient to unnecessarily invasive procedures.

The critically ill patient presents a number of challenges. These patients are usually intubated and manually ventilated with high concentrations of inspired oxygen. While many will have arterial lines for blood pressure monitoring, those that do not are exposed to added risk of morbidity if arterial access is necessary to determine cardiac output. In addition, placement of a pulmonary artery catheter for the measurement of mixed venous gas tension exposes the patient to significant risk of sepsis, pneumothorax, thrombosis, or pulmonary artery rupture. However, cardiac output is often vital in determining end-organ perfusion.

Recently, a system for noninvasive measurement of cardiac output using the Fick principle and carbon dioxide was developed for use with ventilated patients in the intensive care unit, based on the estimations described above. A number of assumptions allow this system to be used without the need for arterial or mixed venous blood samples. The technique involves measuring changes in carbon dioxide production and arterial CO_2 content between normal breathing conditions and under rebreathing conditions with 10–15% CO_2 and a reservoir with a volume 1.5 times the tidal volume. Carbon dioxide production (VCO_2) is calculated from the minute ventilation and expired CO_2 content under normal breathing conditions. Arterial CO_2 content [$ctCO_{2(Art)}$] is estimated from the end-tidal CO_2 ($ETCO_2$) with adjustments for the slope of the CO_2 dissociation curve and degree of dead space ventilation.

During partial rebreathing, carbon dioxide elimination from the blood is reduced, but $ETCO_2$ increases and reaches a plateau within a few breaths. Studies conducted in anaesthetised dogs have showed that during a brief period of CO_2 rebreathing there is a change in $PaCO_2$ and in calculated VCO_2, but little or no change in venous carbon dioxide content ($ctCO_{2(Ven)}$) (5). It is believed that this finding is due to the quantity of CO_2 stores in the body being large and new equilibrium levels not being attained for 20–30 min. This finding becomes highly important in the noninvasive estimation of cardiac output. Any change in the arteriovenous CO_2 difference during the brief rebreathing period can be attributed to changes in the arterial CO_2 component alone.

If it is assumed that the cardiac output and $ctCO_{2(Ven)}$ remain constant during normal breathing (N) rebreathing (R):

$$\begin{aligned} CO &= VCO_{2(N)}/(ctCO_{2(Ven)(N)} - ctCO_{2(Art)(N)}) \\ &= VCO_{2(R)}/(ctCO_{2(Ven)(R)} - ctCO_{2(Art)(R)}) \end{aligned}$$

From basic algebra it is known that

$$X = A/B = C/D = (A - C)/(B - D)$$

Then,

$$\begin{aligned} CO = (VCO_{2(N)} - VCO_{2(R)})/[(ctCO_{2(Ven)(N)} - ctCO_{2(Art)(N)}) \\ - (ctCO_{2(Ven)(R)} - ctCO_{2(Art)(R)})] \end{aligned}$$

Rearranging this equation:

$$\begin{aligned} CO = (VCO_{2(N)} - VCO_{2(R)})/[(ctCO_{2(Ven)(N)} - ctCO_{2(Ven)(R)}) \\ - (ctCO_{2(Art)(N)} - ctCO_{2(Art)(R)})] \end{aligned}$$

Since it has been assumed that $ctCO_{2(Ven)}$ does not change during rebreathing ($ctCO_{2(Ven)(N)}$ is equal to $ctCO_{2(Ven)(R)}$), these values cancel each other out and the equation becomes:

$$CO = (VCO_{2(N)} - VCO_{2(R)})/(ctCO_{2(Art)(R)} - ctCO_{2(Art)(N)})$$

In other words, cardiac output is equal to the change in VO_2 divided by the change in arterial CO_2 content between the normal and rebreathing states:

$$CO = \Delta VCO_2/\Delta ctCO_{2(Art)}$$

As $ctCO_{2(Art)}$ is estimated from $ETCO_2$ and the slope (S) of the CO_2 dissociation curve:

$$CO = \Delta VCO_2/S \times \Delta ETCO_2$$

This method of cardiac output estimation gives a measure of the pulmonary capillary blood flow (Q_{PCBF}). Changes in VCO_2 and $ETCO_2$ only reflect the blood flow that participates in gas exchange. An intrapulmonary shunt occurs when venous blood passes through unventilated areas of the lungs and moves into the arterial circulation without taking up oxygen or releasing carbon dioxide. A large intrapulmonary shunt will not be reflected in the changes seen in VCO_2 and $ETCO_2$. Therefore, it is necessary to estimate the degree of shunting and correct the cardiac output estimation accordingly. For example, if only 80% of pulmonary blood flow is participating in gas exchange, the Q_{PCBF} estimated by this method will be 80% of the total cardiac output. The shunting fraction is calculated using the arterial oxygen saturation (SaO_2, from a pulse oximeter), the fraction of inspired oxygen (FiO_2), arterial oxygen tension (PaO_2) and standard isoshunt tables. The requirement of an arterial blood gas sample for PaO_2 means that this method is not truly noninvasive.

As mentioned previously, this noninvasive method involves a number of assumptions. In summary, these assumptions are the CO_2 exchange at the alveolar–arterial membrane reaches equilibrium. Therefore, $ETCO_2$ is equal to $PaCO_2$; cardiac output remains constant during rebreathing; venous CO_2 content does not change during a brief period of rebreathing; and there is little or no intrapulmonary shunting.

SUMMARY

The Fick method remains the gold standard of cardiac output measurement. While technically challenging, it relies on direct measurement of oxygen consumption and uptake to determine the rate of blood flow through the lungs and around the body. Accurate measurement of cardiac output is necessary for the estimation of several important parameters and assessment of complex congenital cardiac conditions. Variations of the classical Fick principle allow estimation of cardiac output in patients who might otherwise be unsuitable.

BIBLIOGRAPHY

1. Vandam LD, Fox JA, Fick A. (1829–1901), Physiologist: A heritage for anaesthesiology and critical care medicine. Anaesthesiology 1998;88(2):514–518.
2. Kendrick AH, West J, Papouchado M, Rozkovec A. Direct Fick cardiac output: Are assumed values for oxygen consumption acceptable? Eur Heart J 1988;9(3):337–342.
3. Wolf A, et al. Use of assumed versus measured oxygen consumption for the determination of cardiac output using the Fick principle. Catheterization Cardiovascular Diagnosis 1998;43(4): 372–380.
4. Hagen PT, Scholz DG, Edwards WD. Incidence and size of patent foramen ovale during the first 10 decades of life: An autopsy study of 965 normal hearts. Mayo Clinic Proc 1984; 59(1):17–20.
5. Tachibana K, et al. Effect of ventilatory settings on accuracy of cardiac output measurement using partial CO(2) rebreathing. Anesthesiology 2002;96(1):96–102.

Reading List

Grossman W. Blood flow measurement: The cardiac output. In: Baim DS, Grossman W. Cardiac Catheterization, Angiography and Intervention. 5th ed. Baltimore: Williams and Wilkins; 1996: pp 109–120.

Davidson CJ, Fishman RF, Bonow RO. Cardiac Catheterization (Ch 6). In: Braunwald E, editor. Heart Disease: A textbook of cardiovascular medicine. 5th ed. Philadelphia: WB Saunders; 1997: pp 177–203.

Grossman W. Shunt detection and measurement. In: Baim DS, Grossman W. Cardiac Catheterization, Angiography and Intervention. 5th ed. Baltimore: Williams and Wilkins; 1996: pp 167–180.

Feneley MP. Measurement of cardiac output and shunts. In: Boland J, Muller DWM, editors. Cardiology and cardiac catheterisation: The essential guide. Amsterdam: Harwood Academic Publishers; 2001: pp 197–205.

See also BLOOD GAS MEASUREMENTS; CARDIAC OUTPUT, INDICATOR DILUTION MEASUREMENT OF; CARDIAC OUTPUT, THERMODILUTION MEASUREMENT OF; PERIPHERAL VASCULAR NONINVASIVE MEASUREMENTS; RESPIRATORY MECHANICS AND GAS EXCHANGE.

CARDIAC OUTPUT, INDICATOR DILUTION MEASUREMENT OF

F. M. DONOVAN
University of South Alabama
B. C. TAYLOR
The University of Akron
Akron, Ohio

INTRODUCTION

Cardiac output is defined as the volume of blood pumped by the left or right ventricle per unit of time and is normally expressed in $L \cdot min^{-1}$ (1). For the average 70 kg adult male, the cardiac output is $\sim 5\ L \cdot min^{-1}$, however, exercise can cause this figure to increase as much as six times the resting value in well-trained athletes (2). Knowledge of cardiac function is an important tool for determining the hemodynamic status of an individual whether he/she is a trained athlete or a patient in a critical care setting. Accurate direct measurement of cardiac output is a rather difficult task since to obtain a direct measurement would require collecting and measuring all of the blood pumped from the heart into the aortic outflow tract. It is necessary, therefore, to develop indirect methods for the measurement of cardiac output that would provide equivalent accuracies. The Fick (2) and other indicator dilution methods (3) are two of the invasive procedures that provide good reasonable results. More recently, echo cardiography and other noninvasive techniques have been gaining in popularity, yet the Fick and Indicator Dilution methods remain the “Gold Standards” against which all other methods are compared because of their accuracy, safety, reproducibility, and relative simplicity (1).

The Fick principle (4) is based on the fact that the amount of an indicator taken up (or released) by an organ is the product of its blood flow and the difference in concentration of the substance between the organ’s arterial and venous blood. Cardiac output can be determined by dividing the amount of oxygen consumed by the arterial-venous oxygen difference (AVO_2 difference). The theory behind this procedure is explained more fully below.

The indicator dilution method became widely accepted after Hamilton, in 1948, demonstrated that this technique agreed with the Fick method. In the indicator dilution method (5) an indicator(dye, thermal, saline) is injected into the venous blood and its concentration is measured continuously in the arterial blood as it passes through the circulatory system The cardiac output is determined by analyzing the resulting time-dependent concentration curve.

INDICATOR DILUTION METHOD FUNDAMENTAL EQUATIONS



Figure 1. Simple mixing chamber.

Consider the simple mixing chamber shown in Fig. 1, where Q is the constant volumetric flow rate into and out of the chamber, m_i is the mass of indicator injected into the inflow stream, $C(t)$ is the concentration of indictor in the chamber at any instant, and m_L is the mass of indicator that leaves the chamber due to diffusion to the wall and/or metabolism. The differential mass of indicator that leaves the chamber at point 2 per differential time is given by

$$dm_2 = C(t)Q dt$$

where $C(t)$ at point 2 is the same as the concentration of indictor in the mixing chamber assuming complete mixing in the chamber. The total mass of indicator that leaves the chamber is determined by integrating the above equation with the result shown below.

$$m_2 = Q \int_0^{\infty} C(t) dt$$

The differential mass of indicator that leaves the chamber due to diffusion to the chamber wall and/or metabolism is proportional to the concentration of indicator, $C(t)$, and the surface area of the chamber, A.

$$dm_{\mathrm{L}} = C(t) A D dt$$

where D is the proportionality constant for diffusion and/or metabolism.

The total mass of indicator leaving the chamber due to diffusion is

$$m_{\mathrm{L}} = AD \int_0^{\infty} C(t) dt$$

The total mass of indicator leaving the chamber is equal to the mass of indicator entering the chamber minus the mass loss of indicator due to diffusion

$$m_2 = m_{\mathrm{i}} - m_{\mathrm{L}}$$

which leads to

$$Q \int_0^{\infty} C(t) dt = m_{\mathrm{i}} - AD \int_0^{\infty} C(t) dt$$

and subsequently to the equation for volumetric flow rate

$$Q = \frac{m_{\mathrm{i}}}{\int_0^{\infty} C(t) dt} - AD$$

The integral of $C(t)dt$ is determined from the area under the indicator dilution curve. Note that if the area of the chamber wall is large and/or the diffusion coefficient is large, then the flow rate will be overestimated unless the diffusion is taken into account. In practice, the effect of diffusion is taken into account by a multiplying calibration factor (K) as shown in equation 1.

$$Q = \frac{m_{\mathrm{i}}}{\int_0^{\infty} C(t) dt} K \qquad (1)$$

This is the familiar Stewart–Hamilton equation for calculating cardiac output from the indicator dilution curve (6).

INDICTOR DILUTION CURVE FUNDAMENTAL EQUATIONS

The equations for the indicator dilution curve are determined by the indicator mass flow rate conservation, which states that the mass flow rate of indicator into the mixing chamber must equal the mass flow rate of indicator out of the mixing chamber plus the mass rate of removal by diffusion plus the rate of change of indictor stored in the chamber.

$$C_{\mathrm{i}} Q = C(t) Q + C(t) AD + V \frac{dC(t)}{dt}$$

The parameter V is the volume of the chamber and complete mixing is assumed so that the concentration of indicator leaving the container at point 2 is equal to the concentration of indicator in the chamber at any instant.

Rearranging this equation results in the first-order differential equation

$$\left(\frac{V}{Q + AD}\right) \frac{dC(t)}{dt} + C(t) = \frac{Q}{Q + AD} C_{\mathrm{i}}$$

which has a time constant of

$$\tau = \frac{V}{Q + AD}$$

After the injection of the indicator is complete, the concentration of indicator flowing into the chamber becomes zero resulting in the following equation during the washout phase.

$$\tau \frac{dC(t)}{dt} + C(t) = 0$$

The solution to this equation is

$$C(t) = C(t_1) e^{-[(t - t_1)/\tau]}$$

where $C(t_1)$ is the indicator concentration at time t_1 on the washout part of the indicator dilution curve.

Taking the natural log of this equation results in

$$\ln C(t) = \ln C(t_1) - [(t - t_1)/\tau]$$

This shows that if the indicator dilution curve is plotted as natural log of C versus t, then the curve will become a straight line during the washout phase and the slope of the curve is the negative reciprocal of the system time constant.

Rearranging this equation yields

$$\tau = \frac{t_1 - t_2}{\ln C(t_2) - \ln C(t_1)}$$

where $C(t_1)$ and $C(t_2)$ are indicator concentrations at time t_1 and t_2, respectively, all located on the washout part of the indicator dilution curve.

This equation can be rearranged to the following:

$$\tau = -C(t_1) \bigg/ \left(\frac{dC}{dt}\right)_{t_1}$$

The total area under the indicator dilution curve from t_1 to infinity is given by

$$\int_{t_1}^{\infty} C(t)dt = \tau C(t_1) \int_{t_1}^{\infty} e^{-[(t-t_1)/\tau]} d\left(\frac{t-t_1}{\tau}\right)$$

which results in the equation for the remaining area under the curve.

$$\int_{t_1}^{\infty} C(t)dt = C(t_1)\tau = \frac{(t_1 - t_2)}{\ln C(t_2) - \ln C(t_1)} C(t_1) \qquad (2)$$

This equation can be rearranged to the following:

$$\int_{t_1}^{\infty} C(t)dt = \frac{-[C(t_1)]^2}{[C(t)/dt]_{t_1}} \qquad (3)$$

APPLICATION OF THE INDICATOR DILUTION EQUATIONS AND RECIRCULATION

The following results are from a computer simulation in which 6 mg of indicator are injected into the right atrium of an average male with indicator concentrations being read from the radial artery. The volumes used by the simulation for the chambers involved are shown in Figure 2.



Figure 2. Schematic of simulation system.

Q is cardiac output ($6\ \mathrm{L \cdot min^{-1}}$)
1 is the right atrium ($V1 = 100$ mL)
2 is the right ventricle ($V2 = 100$ mL)
3 is the pulmonary circulatory system ($V3 = 600$ mL)
4 is the left atrium ($V4 = 100$ mL)
5 is the left ventricle ($V5 = 100$ mL)
6 is the systemic artery volume from the left ventricle to the radial artery ($V6 = 100$ mL)

The total circulatory system volume is taken to be 6 L.

The diffusion coefficient D is taken to be zero in the simulation. The resulting indicator dilution curve as measured in the radial artery is shown in Fig. 3.

The dashed line beginning at ~ 22 s shows what the curve would do if there were no recirculation of the indicator through the circulatory system back to the right atrium. The solid line shows the actual curve with recirculation.



Figure 3. Indicator dilution curve.

The area under the indicator dilution curve can not be determined directly from the dilution curve. The dilution curve is plotted on a semilog graph in Fig. 4.

During the washout phase, the concentration curve approaches a straight line (dashed line) before the recirculation distorts the plot (solid line). This indicates that the system is behaving as a first-order decay, and we can use equation 2 to determine the area under the curve from any chosen time on the straight-line portion of the curve to infinity.

In this simulation, the area under the indicator dilution curve that would occur if there were no recirculation from 0 to 40 s is found to be $59.8\ \mathrm{mg \cdot s \cdot L^{-1}}$, which results in a calculated cardiac output of $6.02\ \mathrm{L \cdot min^{-1}}$.

With recirculation we determine the area under the curve from 0 to 15 s to be $47.387\ \mathrm{mg \cdot s \cdot L^{-1}}$ and use equation 2 to calculate the area from 15 s to infinity.

For example, use the concentrations at 15 and 20 s that are in the straight-line portion of the semilog plot.

$$C_{t=15} = 2.096\,\mathrm{mg \cdot L^{-1}} \quad C_{t=20} = 0.908\,\mathrm{mg \cdot L^{-1}}$$

Equation 2 gives the area from 15 s to infinity as $12.528\ \mathrm{mg \cdot s \cdot L^{-1}}$ so the total area from 0 to infinity is calculated to be $59.915\ \mathrm{mg \cdot s \cdot L^{-1}}$. Now using equation 1, the cardiac output is found to be $6.01\ \mathrm{L \cdot min^{-1}}$.

Using equation 3 at 15 s yields the same result.



Figure 4. Semilog plot of indicator dilution curve.

FICK PRINCIPLE

If the indicator is supplied to the mixing chamber shown in Fig. 1 at a steady rate until steady state is reached, then the concentration of indicator in the stream leaving the chamber will be constant and is given by the equation

$$m_{\mathrm{f}_2} = C_2 Q$$

where m_{f_2} is the mass flow rate of indicator flowing out of the chamber.

Under steady flow conditions the mass flow rate of indicator into the chamber in the inflow stream plus the mass flow rate of indicator entering the chamber by injection will be equal to the mass flow rate of indicator flowing out of the chamber in the outflow stream.

$$m_{\mathrm{f}_1} + m_{\mathrm{f}_\mathrm{i}} = m_{\mathrm{f}_2}$$

In terms of inflow and outflow concentration of indicator, this equation is

$$C_1 Q + m_{\mathrm{f}_1} = C_2 Q$$

Solving for Q yields the equation on which the Fick method is based.

$$Q = \frac{m_{\mathrm{f}_\mathrm{i}}}{C_2 - C_1}$$

In practice, the indicator used in the measurement of cardiac output by the Fick method is oxygen so that $m_{\mathrm{f}_\mathrm{i}}$ is the consumption rate of oxygen in the lungs, C_1 is the concentration of oxygen in the venous blood, and C_2 is the concentration of oxygen in the arterial blood.

THERMAL DILUTION METHOD FUNDAMENTAL EQUATIONS

For thermal dilution measurement of cardiac output, a warm or cold injectate is injected into the right atrium and the temperature of blood in the pulmonary artery is measured by a thermistor as shown in Fig. 5. A warm injectate would need to be considerably warmer than the blood that might be hot enough to denature proteins (60°C). If it were not very warm, the poor signal/noise ratio would render the method unusable. Therefore cold injectate is the only practical thermal indicator (7,8).

A bolus of cold fluid is injected into the right atrium and the resulting temperature is recorded from the pulmonary artery. Conservation of energy requires that the total thermal energy entering the system during the procedure must be equal to the total thermal energy that leaves the system as the system returns to normal temperatures.

The thermal energy carried across a boundary by a differential volume of fluid is given by

$$dE = \rho C_\mathrm{P} T(t) Q dt$$

where ρ is the density of the fluid, C_P is the specific heat of the fluid, $T(t)$ is the temperature of the fluid at any instant, Q is the volumetric flow rate of fluid crossing the boundary, and dt is the differential time.



Figure 5. Catheter in place for thermal dilution measurement.

The total thermal energy that crosses a boundary for a constant volumetric flow rate with constant thermal properties is

$$E = \rho C_\mathrm{P} Q \int_0^\infty T(t) dt$$

The total thermal energy that enters the system is a combination of energy carried into the system by blood flow and the thermal energy carried into the system by the injectate, where the subscript b refers to blood and subscript i refers to injectate.

$$E_\mathrm{i} = \rho_\mathrm{b} Q C_{P_\mathrm{b}} \int_0^\infty T_\mathrm{b} dt + \rho_\mathrm{i} C_{\mathrm{P}_\mathrm{i}} V_\mathrm{i} T_\mathrm{i}$$

The total thermal energy that leaves the system is a combination of the energy carried out of the system by blood flow and thermal energy loss to the walls of the atrium and ventricle.

$$E_\mathrm{o} = \rho_\mathrm{b} Q C_{\mathrm{P}_\mathrm{b}} \int_0^\infty T(t) dt + \rho_\mathrm{i} C_{\mathrm{P}_\mathrm{i}} V_\mathrm{i} T_\mathrm{b} + hA \int_0^\infty (T - T_\mathrm{b}) dt$$

where $T(t)$ is the temperature recorded by the thermistor at any instant, h is the thermal convection coefficient, and A is the internal surface area of the right atrium and right ventricle.

Using these equations in the thermal energy conservation equation

$$E_\mathrm{i} = E_\mathrm{o}$$

and rearranging gives

$$\rho_\mathrm{b} C_{\mathrm{P}_\mathrm{b}} Q \int_0^\infty (T(t) - T_\mathrm{b}) dt = \rho_\mathrm{i} C_{\mathrm{V}_\mathrm{i}} V_\mathrm{i} (T_\mathrm{i} - T_\mathrm{b}) - hA \int_0^\infty (T(t) - T_\mathrm{b}) dt$$

Solving for Q yields the thermal dilution equation for volumetric flow rate.

$$Q = \frac{\rho_\mathrm{i} C_{\mathrm{V}_\mathrm{i}}}{\rho_\mathrm{b} C_{\mathrm{V}_\mathrm{b}}} \frac{V_\mathrm{i}(T_\mathrm{i} - T_\mathrm{b})}{\int_0^\infty (T(t) - T_\mathrm{b}) dt} - \frac{hA}{\rho_\mathrm{b} C_{\mathrm{P}_\mathrm{b}}}$$

The term on the right represents the heat loss to the walls of the atrium and ventricle. In practice, there would be an additional heat loss in the catheter. The heat loses are normally accounted for by a correction term (K) that is a function of the catheter type being used as shown below.

$$Q = \frac{\rho_i C_{V_i}}{\rho_b C_{V_b}} \frac{V_i(T_i - T_b)}{\int_0^\infty (T(t) - T_b)dt} K$$

The thermal dilution method has the advantage that recirculation is not a problem due to the large surface available in the circulation to bring the injectate temperature to body temperature. A disadvantage is that the injection site and the sensing site must be close together to avoid large heat losses and the absence of total mixing in the ventricle can cause inaccuracies.

BIBLIOGRAPHY

1. Yang SS, Bentivoglio LG, Maranhao V, Goldberg H. From Cardiac Catheterization Data To Hemodynamic Parameters. 2nd ed. Philadelphia: F.A. Davis Company; 1980. p 55.
2. Geddes LA. Cardiovascular Devices and Their Applications. New York: John Wiley & Sons, Inc.; 1984. p 102–106.
3. Stewart GN. The output of the heart in dogs. Am J Physiol 1921;57:27–50.
4. Fick A. Uber die Messung des Blutstroms in den Herzventrikeln. Verhandl Phys Med Ges Zu Wurzburg 1870;2:XVI.
5. Hamilton W, et al. Comparison of the Fick and dye injection methods of measuring the cardiac output in man. Am J Physiol 153:309–321.
6. Valentinuzzi ME, Posey JA. Fast estimation of the dilution curve area by a procedure based on a compartmental hypothesis. Med Ins Sept-Oct1972;(6)5.
7. Taylor BC, Sheffer DB. Understanding Techniques for Measuring Cardiac Output. Biomedi Inst Technol May/June, 1990; 188–197.
8. Swinney RS, Davenport MW, Wagers P, Sebat F, Johnston W. Iced versus room temperature injectate for thermal dilution cardiac output. Ninth Annual Scientific and Educational Symposium. Soc Crit Care Med, May12–16,1980;137.

See also CARDIAC OUTPUT, FICK TECHNIQUE FOR; CARDIAC OUTPUT, THERMODILUTION MEASUREMENT OF; ECHOCARDIOGRAPHY AND DOPPLER ECHOCARDIOGRAPHY; FLOWMETERS, ELECTROMAGNETIC; TRACER KINETICS.

CARDIAC PACEMAKER. See PACEMAKERS.

CARDIAC OUTPUT, THERMODILUTION MEASUREMENT OF

EDWIN D. TRAUTMAN
RMF Strategies
Cambridge, Massachusetts
MICHAEL N. D'AMBRA
Harvard Medical School
Cambridge, Massachusetts

INTRODUCTION

The amount of blood pumped by the heart each minute, the cardiac output, provides a measure of the body's potential for supplying oxygen and nutrients and is relevant to assessing the condition of the heart. Taken together with various pressures, it is a key clinical indication of the heart's ability to meet the body's needs and an indirect indication of the status of those needs. In the clinical setting, measurement of cardiac output is required to guide drug therapy aimed at manipulating the function of the cardiac muscle (inotropic drugs) and the state of the systemic and pulmonary vascular resistance (vasoconstrictor and vasodilator drugs). Combined with ultrasound velocity data, cardiac output allows precise assessment of the status of mitral and aortic valve stenosis and regurgitation.

G. N. Stewart articulated the basic principle of indicator- dilution measurement of cardiac output in a landmark paper in 1897 (1). Stewart stated that if a substance was introduced at a constant rate into the flowing bloodstream and allowed to mingle with the blood, then the measured steady-state concentration of that substance downstream of the site of introduction would be inversely proportional to the flow rate (cardiac output). Of greater practical importance was his additional observation that if a small amount of the substance was introduced rapidly, then the cardiac output could still be computed. To do that one would divide the average rate at which the substance is introduced (total amount divided by measurement time) by the average concentration. Stewart called this technique the "sudden injection" method. In the late 1920s, W. F. Hamilton and his colleagues further investigated Stewart's sudden injection method (2,3). They found that the concentration curve from timed samples did not simply return to baseline, but exhibited a secondary rise. This was attributed to fast physiologic recirculation of an unknown amount of the indicator. To eliminate the influence of any recirculating indicator on measurement calculation, they proposed extrapolating the original down slope of concentration to zero using an exponential function. This method proved successful in validation studies both in mechanical models and animal experiments, and the sudden injection method with exponential extrapolation is commonly referred to as the Stewart–Hamilton method.

Various indicators have been used to measure cardiac output with the Stewart–Hamilton method, notably saline (detected by its effect on electrical conductivity) and optical dye (detected by its effect on optical absorption), but G. Fegler's proposal in the mid-1950s that heat could be used has proved the most convenient, although initially controversial (4,5). His earliest report "was received with polite incredulity" (6). Fegler rapidly injected a small amount of cold Ringer's solution into the vena cava and recorded the transient decrease in temperature in the aortic arch and in the right ventricle. He computed both left and right heart outputs from these data.

Concerns were voiced regarding the ability to quantify this "negative" indicator, the stability of the baseline temperature, and the background noise (6). These are all valid concerns, but concerns that have been successfully addressed with clinical technology. Current practice is to introduce a small bolus of cold solution into the right atrium (via a venous catheter) and to measure the consequent transient temperature decrease in the pulmonary artery. With the advent of balloon-flotation pulmonary-artery pressure measurement catheterization techniques in the late 1960s (7), small thermistor sensors could be readily placed in the pulmonary artery, and the thermal dilution measurement became clinically accepted even as validation experiments progressed. The pulmonary-artery catheters provide important hemodynamic pressure information and, for that reason alone, are placed in many patients.

Swan and Ganz are credited with developing and popularizing the pulmonary-artery pressure catheter containing a thermistor and injection port for thermal dilution (8), and these catheters are commonly called Swan–Ganz catheters, although Swan–Ganz, strictly speaking, is a registered trademark of Edwards Lifesciences Corporation. The instrumentation required to process the temperature signal and determine cardiac output is modest, fitting into either a small, battery-operated instrument easily used at the patient's bedside, or into a module component of a bedside workstation in the ICU or operating room, making the method easy and convenient. The additional "invasion" of a thermistor is negligible, and the additional value of cardiac output measurements is great. And since the indicator is a physiologically innocuous solution, thermal dilution measurement of cardiac output has become an important part of clinical care. Today, bolus thermal dilution cardiac output is considered the gold standard against which other methods are compared.

THEORY

Principle of Indicator Dilution

The basic principle of indicator dilution is quite simple: If the concentration of a uniformly dispersed indicator in an unknown volume is measured, then the unknown volume can be simply determined by dividing that concentration into the total amount of indicator. If the volumeis flowing past a sensor, then the volume in any given period of time will equal the amount of indicator in that period of time divided by the concentration. If the rate at which the indicator is flowing past the sensor is controlled and known, then the amount of indicator in a period of time is also known and the volume flow rate can be determined. Alternatively, if the total amount of indicator over a larger period of time is known, such as when a bolus is introduced all at once, then average flow rates can be determined. Each approach has strengths and weaknesses in technique, necessary assumptions, and equipment. We focus on the popular bolus technique but, particularly with thermal techniques, the theory can be extended.

In the case of thermal dilution, the indicator is introduced into the right atrium and its concentration is measured in the pulmonary artery. We assume that all of the indicator introduced, an amount I, eventually passes into the pulmonary artery at some rate $i(t)$. If we assume no indicator recirculates, we may write this as

$$I = \int_0^\infty i(t)\,dt \tag{1}$$

$$= \int_0^\infty F(t)c(t)dt \tag{2}$$

where F is volumetric flow and c is concentration. When the flow is constant, F can be moved out of the integral and we can solve for F as

$$F = \frac{I}{\int_0^\infty c(t)dt} \tag{3}$$

Several assumptions have been made in arriving at this equation. Equation 1 is a statement of conservation and requires that all indicators pass the sensor exactly once. Equation 2 requires that the concentration in the pulmonary artery be uniform across the area where the concentration is being measured, and equation 3 requires that the flow rate be constant. All but the first requirement can be satisfied for the pulmonary artery catheter-based measurements if we consider the right heart to be a perfect mixing chamber, with a competent valve at the outflow, and a pumping rate that is constant over the integration time. The mixing chamber guarantees that the blood will be equivalently labeled at its outflow so that each flow stream is representative of the total, and the valve guarantees that the concentration changes in a stepwise fashion in all flow streams, which allows legitimate averaging of pulsatile variations in flow. A rigorous proof can be found in Perl et al. (9) and the assumptions and necessary conditions are discussed in Trautman and Newbower (10). Each of these articles contains numerous relevant references.

Heat as an Indicator: "Thermal" Dilution

In thermal dilution, the indicator is caloric, introduced as a known volume of a cold physiologic solution whose concentration is measured via the induced temperature change. The relationship between temperature and the concentration of heat in a solution, the amount of heat in a unit volume, involves the specific heat and density of the solution. When two solutions at different temperatures, such as the indicator and blood, are mixed, the temperature of the mixture may be predicted by

$$T = \frac{T_1 C_{p1} m_1 + T_2 C_{p2} m_2}{C_{p1} m_1 + C_{p2} m_2} \tag{4}$$

where C_p and m are, respectively, the specific heat and mass of the solutions. If we take the first solution to be the indicator solution and the second to be the blood, then the difference in temperature due to the indicator will be predicted by

$$T - T_2 = \frac{(T_1 - T_2) C_{p1} m_1}{C_{p1} m_1 + C_{p2} m_2} \tag{5}$$

A very good assumption, at least prior to significant heat exchange with tissue, is that the indicator solution and the temperature transient travel together. In this case, equation 5 holds for all instances of time, and the mass concentration of the indicator solution may be predicted from the temperature transient by

$$c(t) = \frac{[T(t) - T_2]\rho_1}{T(t) - T_2 - (C_{p1}\rho_1/C_{p2}\rho_2)[T(t) - T_1]} \tag{6}$$

where ρ is the density of the solution. The amount of indicator is equal to the volume of the physiologic solution V times its density ρ_1 (giving its mass) and equation 3 becomes

$$F = \frac{V\rho_1}{\int_0^\infty c(t)\,dt} \tag{7}$$

$$F = \frac{V\rho_1}{\int_0^\infty \frac{[T(t) - T_2]\rho_1}{T(t) - T_2 - (C_{p1}\rho_1/C_{p2}\rho_2)[T(t) - T_1]}dt} \tag{8}$$

Equation 8 forms the basis for the thermal dilution method for measuring cardiac output. This equation may be easily programmed, but it generally has been approximated to simplify implementation, The most common approximation is based on the assumption that the indicator solution has no effect on the thermal properties of the blood. In this case, the increment in the amount of heat leaving the heart due to the indicator is equal to

$$H = \rho_2 C_{p2} F \int_0^\infty [T(t) - T_2]dt \tag{9}$$

This is equivalent to equation 2 and requires the same assumptions. The amount of heat added in a certain volume of an indicator solution is equal to

$$H = \rho_1 C_{p1} V(T_1 - T_2) \tag{10}$$

Equating equations 9 and 10 leads to the simpler formula for flow:

$$F = \left(\frac{C_{p1}\rho_1}{C_{p2}\rho_2}\right)\frac{V[T_1 - T_2]}{\int_0^\infty [T(t) - T_2]dt} \tag{11}$$

Equations 8 and 11 are equivalent only when cool blood is used as the indicator. Equation 11 is simpler than equation 8 and can be implemented in an analog circuit. However, it is based on the implausible condition that the indicator solution carries heat (or cold) into the blood and then is either transported completely apart from the thermal transient or has no thermal effect on the blood. Fortunately, the practical difference between flow estimates based on these two equations is small. The ratio of thermal properties for a dextrose-in-water (D5W) indicator solution is approximately equal to 1.08, and for a normal (0.9%) saline solution it is approximately equal to 1.10. Since the expected temperature transient is 0.5–1.0 °C, the expected difference between equations 8 and 11 is only 1–2% for these indicators.

If the indicator is not introduced as a finite bolus, then the conservation statement of equations 1 and 2 needs to be generalized and other assumptions made. The product of flow rate and concentration at the outflow of the mixing chamber will still be equal to the amount of indicator passing by, but its relationship to the input indicator can be more complex. A simple example is where the indicator is infused at a constant rate in which case, absent recirculation, the flow rate will be inversely proportional to measured concentration. If the infusion rate is not constant then the transient response of the heart system needs to be considered.

Heat can be introduced by direct energy transfer, such as from an electrical heater. In this case, the volume factor in the numerator of equation 11 is not relevant and must be replaced by a measure of the amount of heat introduced. It is, however, impractical to introduce a large bolus (impulse) of heat comparable to the 750 W of 10 mL of iced saline: The surface temperature would be dangerously high. Instead, the heater is pulsed at low power, the resulting temperature changes measured with a fast-response thermistor, and sophisticated signal processing used to extract the dilution signal from the baseline. Such techniques have the potential to measure cardiac output continuously and were introduced in the early 1980s (11). Catheters with heating elements (10 cm long filaments in the right ventricle) have been produced since the early 1990s (12). The surface temperature and thus the amount of heat that can be introduced are limited by physiological concerns (4–7 °C), and therefore the technique is sensitive to background thermal noise. The heater is typically pulsed, and the accuracy is dependent on processing the correlation between the heating waveform and the measured temperature response (11–13). These techniques are entering clinical use as a companion to bolus thermal dilution, but are not considered here.

Necessary Conditions

For the preceding development, we assumed that the flow is constant; the volume and temperature of the solution are known, the indicator does not recirculate, and perfect mixing occurs somewhere between injection and sampling. Little can be done to control the variation of flow; it is flow that is being measured. (In those situations where flow is *not* constant, it can be shown that the computed result will be a concentration-weighted average of the true cardiac output over the period of measurement.) The other assumptions are usually reasonable, although in practice it is difficult to have an accurate measure of the volume or temperature of the injected solution since heat will exchange with all material contacting the solution. There is also a lost volume in the dead space of the catheter used to introduce the solution, and it is impossible to eliminate the physiologic recirculation of indicator. In addition, the integrals must be truncated to permit a practical measurement. These and other practical issues are covered next.

Notably absent from these formulas is the time response of the thermal sensor. Although not intuitively appealing, it can be shown that this response is of little importance as long as the curve does not become distorted by the effects of noise and recirculating indicator. The area under the thermal curve is preserved even with slow-responding thermal sensors. The operator should, however, be aware that the thermal curve obtained with a slow thermistor is not necessarily a high fidelity representation of the temperature transient. The observed or recorded temperature curve will be smoothed and filtered over time.

PRACTICAL APPLICATION OF THE THEORY

The practical application of thermal dilution theory is simple; all that is typically necessary to measure cardiac output is to reset the "cardiac output computer," inject 2–10 mL of an ice-cold or room temperature solution into the catheter port, and wait for the answer to appear on the computer. The thermal sensor is contained on a special pulmonary artery catheter that also provides the injection lumen into the right atrium. The temperature curve may be recorded to reassure the operator that a reasonable signal was obtained. Typical curves for various flow rates are shown in Fig. 1.

When the computer is reset, it samples the baseline temperature, integrates the processed temperature curve until recirculation is detected or assumed, and calculates the cardiac output assuming predefined conditions. It applies a correction for the portion of the curve that is lost by the truncation of the integral (to avoid influence of recirculation). The predefined conditions include the volume and temperature of the injectate, the thermal characteristics of the fluids, and a correction factor that corrects for the physical properties of the particular injection catheter employed. Most computers make approximations and apply corrections. The most common are listed below.

Thermal Properties of Blood Are Approximately Constant

The thermal properties of blood vary with hematocrit. However, the convenience of assuming a normal hematocrit—and thus not requiring knowledge of the actual hematocrit and entering it—far outweighs the importance of the potential error. The specific heat-density product for erythrocytes is $\sim 3.52\ \mathrm{J \cdot K^{-1} \cdot mL^{-1}}$, and for plasma it is $\sim 4.03\ \mathrm{J \cdot K^{-1} \cdot mL^{-1}}$ (14). Therefore, for blood with a hematocrit of 40% this product is $3.83\ \mathrm{J \cdot K^{-1} \cdot mL^{-1}}$, with a hematocrit of 30% it would be $3.88\ \mathrm{J \cdot K^{-1} \cdot mL^{-1}}$, and with 50% it would be $3.78\ \mathrm{J \cdot K^{-1} \cdot mL^{-1}}$. Thus, the nominal value assumed for blood could be in error by 1–2% causing an error in the cardiac output measurement of the same value.

Indicator Does not Affect Thermal Properties of Blood

The specific heat-density product for normal (0.9%) saline is $\sim 4.19\ \mathrm{J \cdot K^{-1} \cdot mL^{-1}}$, and that for 5% dextrose-in-water is $\sim 4.11\ \mathrm{J \cdot K^{-1} \cdot mL^{-1}}$ (15). These are significantly different from the nominal $3.81\ \mathrm{J \cdot K^{-1} \cdot mL^{-1}}$ for blood. The thermal properties of the indicator-blood mixture will thus vary with the level of dilution. However, most computers assume that the indicator does not affect the thermal properties of blood. This assumption leads to the simpler equation [Eq. 11] derived above. Cardiac output computers using this approximation can be expected to overestimate the cardiac output by 1–2%.



Figure 1. Typical thermal dilution curves, taken at different flows and superimposed to illustrate variations in shape and area.

Heat Loss Is Predictable

When the syringe containing the cold solution is taken from the ice bath it immediately begins to warm. The solution warms further as it is injected through caloric exchange with the walls of the catheter. Only a negligible amount of heat is gained during manipulation of the syringe before injection. However, the exchange with the wails of the catheter can account for several percentages with a 0 °C solution (16). In addition to those conductive losses of indicator, a significant amount of solution is left in the catheter after the injection has been terminated. The typical dead space volume is 0.9 mL so that only 91% of the solution is injected into the bloodstream. However, the solution that filled the dead space prior to injection is pushed into the blood stream and, if not at blood temperature, can add to the effective indicator volume. In addition, some of the "cold" left in the dead space after injection can leak through the catheter wall and add to the injectate.

Empirical studies have shown that the combination of these losses and gains can be grouped into a single correction factor, multiplying the total indicator volume. This correction factor varies only a few percentages with catheter insertion length and other mechanical factors (17). The correction factor does depend on the temperature and volume of the injected solution and on the design of the catheter. Catheter manufacturers generally provide, with their package inserts, a table of values for the correction factor or "computation constant" under various typical conditions. This factor is determined by measuring the average temperature of the injectate, as it emerges from the injectate, lumen of the catheter, while the appropriate length of catheter is immersed in a 37 °C bath. The amount of injectate that emerges is a reasonably constant fraction of the amount introduced.

Devices can be used to measure the temperature of the injected solution as it enters the injection catheter. This reduces the need for precisely controlling the initial temperature of the solution and reduces errors due to warming of the solution during handling. These devices do not improve knowledge about the unknown heat loss during injection. Catheters have also been fabricated with thermistors in the distal port of the injection lumen, to measure true injectate temperature. These catheters demonstrate better reproducibility particularly with room temperature injectates, but have yet to win clinical acceptance due to cost and complexity. Note also that the rate at which the indicator is introduced must be controlled and consistent to allow inferring amount of heat from temperature.

Decay of Dilution Signal Is Exponential

Recirculation of the thermal indicator is relatively small in humans since there is ample opportunity for exchange with the tissue beds. In smaller animals, recirculation is more apparent. In either case, the decay of the temperature signal measured in the pulmonary artery approximates an exponential (the result of the mixing chamber) and, once truncated, the true but obscured curve can be mathematically extrapolated with reasonable accuracy. The relatively small amount of curve area being estimated limits the significance of errors in extrapolation. Some cardiac output computers actually fit an exponential to the uncorrupted curve and use the parameters of fit to extrapolate the curve, while most assume that curves generally have the same shape and integrate to a fraction of the peak temperature and multiply this area by a constant. Either method appears to result in a reliable measure of cardiac output. Certain pathologies can alter the shape of the thermal dilution curve and reduce the effectiveness of these extrapolation procedures.

Baseline Temperature Is Constant

The baseline temperature is not constant, varying with the respiratory cycle and subject to the fluid infusions from other sources (i.e., intravenous fluid administrations). In addition, the heart itself generates heat that can be observed as very small pulsatile variations in temperature in the pulmonary artery. Fortunately, these variations and the baseline shifts are usually small compared to the ~ 0.5–$1.0\,^{\circ}\mathrm{C}$ dilution signal. Cardiac output computers thus assume that the baseline acquired prior to the arrival of the dilution signal remains constant during the course of the measurement. (Note that shifts in baseline can adversely affect the extrapolation procedure used to reduce the effects of recirculation.)

Flow Rate Is Constant Throughout the Integral

Cardiac output can vary by as much as 10–20% over the respiratory cycle. Since thermal dilution measurement integrals typically average only 5–10 s of the cardiac output, the measured cardiac output could vary by as much as 10–15% depending on where in the cycle the injection is made. There is really nothing the computer can do about this without information about the phases of the respiratory cycle. Cardiac arrhythmias, which can result from the cold injection, can cause dramatic errors in the measured output. The clinical practice of averaging several separate cardiac output determinations helps to average out some of the potential variation from both of these sources. See section on *Measurement Performance* for more discussion on accuracy and reproducibility.

EQUIPMENT

The thermal dilution method for cardiac output measurement is popular because it is easily performed with a minimum of equipment and little additional invasion of the patient. The basic equipment consists of a pulmonary artery catheter to position a thermistor or other temperature-sensitive element in the pulmonary artery, a means for making thermal indicator (usually saline) injections into the right atrium (usually a syringe), typically through a separate lumen in the catheter, a source of measured volumes of a cold solution, and an electronic instrument to determine the blood temperature from the thermistor signal, to determine and integrate the dilution signal, and to compute a final result. Each of these elements is described separately.

Pulmonary Artery Catheters

The pulmonary artery (PA) catheter generally contains several lumens (channels) that terminate at measured distances from the tip. A balloon, located at or near the tip, is inflated during catheter insertion to carry the tip through the heart and into the pulmonary artery (flow directed). One lumen terminates at the tip and is used to measure the pressure during catheter insertion to follow its position relative to the heart; later it measures pulmonary artery pressure and, intermittently, pulmonary capillary wedge pressure (with the balloon inflated). A second lumen typically terminates in the right atrium and is used to monitor right atrial pressure (central venous pressure). Indicator solutions are injected either through the right atrial port or through a second atrial lumen intended for drug infusion. Catheters can have several additional lumens (e.g., atrial and RV pacing wires) and sensors (e.g., mixed venous oxygen saturation). The pulmonary artery catheter provides important hemodynamic information and may be inserted in patients for that purpose alone.

For use with thermal dilution, the pulmonary artery catheter is augmented by adding a thermistor proximal to (before) the balloon (typically, 4 cm from the tip). A thermal dilution catheter is illustrated in place in Fig. 2. The



Figure 2. A pulmonary artery catheter in place in the right heart. The balloon, shown inflated here for wedge pressure measurement, normally remains deflated during pressure monitoring and cardiac output measurements. The cold injectate enters the bloodstream through the injection port, and the temperature transient is sensed by the thermistor.

thermistor typically is encapsulated in glass and coated with epoxy to fully insulate it electrically from the blood. The relatively slow time response of this encapsulated sensor does not affect the accuracy of the measurement since the area under a temperature curve is preserved. Wires connecting the thermistor are contained in a separate lumen. The thermistor wires terminate in an external connector that typically contains an electrical resistance used to standardize the response of the thermistor. Thus the catheter contains one-half of a Wheatstone bridge. The overall length is ~100 cm, with distance marks every 10 cm to guide insertion. The typical size is 7–8.5 Fr although pediatric catheters may be 5–6 Fr. (One French is equal to one millimeter in circumference.)

Edwards Lifesciences was the original commercial manufacturer of the thermal dilution catheter, basing it on a concept acquired from Swan and Ganz, researchers involved with validation experiments. Their Swan–Ganz catheter was introduced in 1971. Since that time several manufacturers (e.g., Instrumentation Laboratories, Cobe, Abbott, Arrow) produce thermal dilution catheters, disposable items selling for ~$50–80 each, although catheters with heating filaments and multiple sensors can cost $200 and up. A thermal dilution catheter is shown in Fig. 3.

Pulmonary artery catheters are not without clinical complications. The threat of infection is always present. Clots can form on the poly vinyl chloride (PVC) catheter surface, but this complication has been mostly eliminated with anticoagulant coatings. Unfortunately, there are patients who have severe reaction to heparin (i.e., heparin induced thrombosis) and in these patients heparin-coated catheters need to be avoided. The catheter can become knotted in the right heart, a complication that requires a trip to the cardiac catheterization laboratory to resolve.

Most dangerous is the rare complication of the catheter tip puncturing the pulmonary artery. In normal use, the balloon is temporarily inflated, the balloon wedges into a branch of the pulmonary artery, flow through that branch of the pulmonary circulation is stopped and the pressure measured from the distal lumen will approximate the left atrial pressure. It is critical that nurses and physicians understand the waveforms associated with "permanent wedge" position to avoid pulmonary rupture. This complication is almost always associated with erosion of the pulmonary artery from a catheter permanently in the wedge position or with inflating a catheter that is in the distal pulmonary arterial position.



Figure 3. A Swan–Ganz pulmonary artery catheter produced by Edwards Lifesciences. The various lumens are accessed through individual Luer-Lok connectors fanning out from an external divider on the main catheter. The electrical connector for the thermistor wires is also connected to the main catheter at the same point. (Photograph courtesy of Edwards Lifesciences Corporation, Irvine, CA.)

The balloon is an important feature of pulmonary artery catheters since it plays a key role in the acquisition of pressure information in addition to facilitating placement of the catheter. Balloons are generally made from latex and designed to inflate beyond the tip of the catheter while not occluding the distal pressure lumen. This shields the tip reducing the tip trauma to the pulmonary artery. Manufacturers attach the balloon to the base catheter in a way that minimizes rough surfaces and overall size of the catheter while being durable. Latex-free balloon catheters are available for use in patients with latex allergies, but are expensive and have limited functionality, usually having only a single right atrial port. The non-latex balloon is also not as durable and measurements of wedge pressure must be kept to a minimum.

The size and material of the catheters can vary among manufacturers and models, both of which can affect their stiffness and thus the ease of insertion, and the size of the dead space in the injection lumen and, thus, the heat loss correction factor. The injection port may be larger in some catheters, reducing injection effort. The frequency response of the pressure measurement lumens may be different due to attention to details of fluid mechanics. Personal preference, reliability, and economic concerns are also clearly important in purchase decisions. Some catheters offer other capabilities such as continuous cardiac output measurements based on advanced signal processing algorithms, mixed venous oximetry, and the ability to electrically pace right atrium and ventricle.

Cold Solution

The indicator solution is typically an isotonic saline or dextrose solution cooled to 0 °C by placing the bottle or prefilled capped syringes in an ice bath. This makes the injected indicator ~37 °C cooler than body temperature. This 10 mL of 37 °C difference injected in 2 s represents extraction of thermal energy from the bloodstream at a rate of ~750 W. Cold indicator is most useful in the operating room where patient temperatures can vary rapidly and dramatically. In the non-OR setting, or in operative patients where normothermia is expected, room-temperature solutions are frequently used because they are more convenient, but the variable room temperature must be monitored by the computer. The injected energy is reduced by a factor of ~3, reducing the signal-to-noise ratio and, thus, expected measurement performance. Most cardiac output computers provide a temperature probe to measure the actual temperature of the bath or of the room, which is presumably the temperature of the injectate. Manufacturers also produce an optional temperature-measuring probe that attaches to the injection port on the thermal dilution catheter and measures the temperature of the injectate as it enters the catheter. This further reduces concern about the actual room or bath temperature. Some catheters also have thermistors at the injection port itself.

The ice bath is the subject of some unproved concerns regarding infection. Undesirable organisms could remain



Figure 4. A closed injection system for cold injectate, by Edwards Lifesciences. A cooling coil rests in a Styrofoam ice bucket, the syringe serves as a piston pump to draw up a known volume of precooled injectate from the coil and to force it into the injection lumen of the catheter. The closed system reduces the risk of nosocomial contamination associated with traditional injectate delivery methods. CO-Set+ System improves reproducibility and accuracy through its in-line temperature probe and volume-limited syringe. (Photograph courtesy of Edwards Lifesciences, Irvine, CA.)

or grow in the capped syringes when left in the bath for long periods of time. A cleaner alternative to the ice bath is offered by a closed injectate system with a cooling coil, offered as an optional accessory by some manufacturers. One such device is shown in Fig. 4. The coil sits in an ice bath keeping the solution cold. The syringe is used to draw up solution and then immediately introduce it into the catheter port. Fig. 5 shows the complete system.

Although these solutions are generally benign, in some circumstances, such as in small pediatric patients, there is a risk of volume overload from frequent measurements. In these situations, smaller volumes are used (e.g., 3 mL) and fewer measurements are made.

Cardiac Output Computers

When thermal dilution measurements were first introduced in the early 1970s, manufacturers produced catheters with nonstandardized thermistors. Each manufacturer then produced a computer to mate with its catheter. In addition to generic differences in thermistor types, each individual thermistor of a given type can have a different temperature response requiring the operator to enter a calibration constant, idiosyncratic to the specific catheter, its thermistor response, and even the patient's blood temperature. In current products, the thermistor connector contains an electrical resistance selected to match the particular thermistor and complete a half Wheatstone bridge with a standard response. The value of the resistance in this circuit is chosen such that the voltage response of the half bridge will be the same for all thermistors of a given family and also will be linear near 37 °C. The nearly linear range is ~ 20 °C. With these catheters, the catheter is merely connected to the computer's electronics, and the pulmonary artery blood temperature and the cardiac output can be measured. The electronic circuitry used to measure the thermal response is electrically isolated, since the thermistor is in the conductive bloodstream quite close to the heart and insulation failures can conceivably occur. Since the catheter functions as half of a Wheatstone bridge, the electronics merely mimic the other half of the bridge circuit, excite the bridge with a low level of current, and amplify the voltage difference proportional to temperature change.



Figure 5. Basic thermal dilution system, with computer, syringe, catheter, and source of cold injectate, in this case from a closed system. (Courtesy of Edwards Lifesciences, Irvine, CA.)

When the operator signals that a measurement is to be made, the baseline temperature is acquired and the indicator concentration is computed (or approximated) and integrated. When the "end of curve" criterion is reached, the integration is stopped, the integral is adjusted for area lost by truncation, and the final area is inverted and multiplied by the appropriate constants for the measurement conditions. This constant is entered in the computer and only changed when conditions change. Cardiac output computers differ both in the method they use to truncate the integration and in the options they offer, such as, syringe size, injectate temperature, and integration into bedside systems.

Calibration of Equipment

Each catheter is individually calibrated by the manufacturer to give a standard response (as described previously), and the heat loss correction factor is determined also by the manufacturer for the particular catheter model for a variety of measurement conditions. No operator calibrations are necessary or practical.

In certain research settings (e.g., custom-made catheters), it is desirable to add the calibration resistor to the catheter. The value of the resistance is given by

$$R = R_0(\beta - 2T_0)/(\beta + 2T_0) \tag{12}$$

where R_0 is the thermistor resistance at 37 °C, T_0 is 310 K, and β is the characteristic temperature (a gain constant) for the thermistor, equal to 3500 K for those used in thermal dilution catheters compatible with the Edwards Lifesciences standard.

Example Equipment

Most cardiac output computers are fully integrated into hemodynamic monitoring systems. The cardiac output component is usually part of the temperature-sensing module. Data from the measurements are acquired into the system's data recording and analysis packages and automated calculations of systemic and pulmonary vascular resistances are obtained.

In the typical computer, the preamplifier is fully isolated and uses a conservative 7 μA to sense the thermistor resistance. When a new cardiac output is desired, the operator presses a button and rapidly injects the cold solution. The dilution curve is typically shown as it is measured and the result is displayed once the curve has finished. Analog and digital outputs may be provided for integrating into a larger measurement or workstation system. In a typical computer the temperature difference is integrated from baseline up to its peak, then down to 30% of the peak value, and multiplied by 1.22. This integral is then inverted and multiplied by the computation constant provided by the catheter manufacturer. The computation constant is the product of all constants (e.g., the ratio of thermal constants, the injectate volume, 60 $s \cdot min^{-1}$, and 0.001 $L \cdot mL^{-1}$) and the catheter heat-loss correction factor (e.g., 0.825). Although the method for extrapolating the integral appears overly simple, it is quite effective. As pointed out earlier, the dilution curve has a consistent shape, and amount of area obscured by recirculation is small and comes relatively late in time (in humans). Some computers use more elaborate methods.

A typical computer and display is shown in Fig. 6. This example from Philips Medical Systems integrates into the monitoring system and computes several derived values as well as displaying hemodynamic information.

MEASUREMENT PERFORMANCE

Direct measurement of cardiac output is quite difficult given the location of the measurement site and the necessity to divert flow in some manner. The performance of thermal dilution measurements of cardiac output has been assessed in a number of less direct ways. Validation studies have been performed in mechanical flow models to assure that the measurement theory is sound in practice (and to determine the heat-loss corrections appropriate to specific catheters). Simultaneous thermal dilution and dye- dilution measurements, and also thermal dilution and direct Fick measurements, have been performed in animals and humans. Comparisons have also been made with electromagnetic flowmeters in animal preparations. All of these methods have shown thermal dilution to be effective for measuring cardiac output and as accurate as these other methods. In addition, an important consideration in the clinic is the reproducibility of the measurement over time and from operator to operator. Clinical studies of this sort have shown thermal dilution to be reliable and it is now considered the gold standard against which other measurements are compared.



Cardiac output (right heart) setup and review screen.

Figure 6. A modern cardiac output computer, integrated into a monitoring system, by Philips Medical Systems. The thermal dilution curve is displayed for inspection, and the cardiac indices can be automatically computed from the cardiac output and body parameters entered by the clinician. (Photograph courtesy of Philips Medical Systems, Andover, MA.)

It is interesting to note that the dye-dilution method was the incumbent standard, using indicators, such as indocyanine green dye measured by withdrawing blood from an artery through an optical sensor. This technique measures somewhat different flows—left-heart output rather than right-heart output, for example—and is subject to other issues of physiology and technique, such as greater recirculation and accumulation of indicator. Nevertheless, dye-dilution was clinically useful and thermal dilution was shown to be better and more convenient. By the early 1980s, thermal dilution was the technique of choice.

Accuracy

The accuracy of thermal dilution is degraded by the various assumptions and approximations discussed previously. Thus, even in the absence of physiologic noise, this measurement can only be expected to be within 2–7% of the true value without other measurements and specific corrections relevant only to a research setting. This accuracy is, however, well within a clinically acceptable range and is no worse than that of other methods. In his first trials with this technique, Fegler compared thermal dilution with standard direct Fick measurements in animals, finding a discrepancy of $< 7\%$. Early validation studies with thermal dilution catheters were performed by Ganz and colleagues in the early 1970s (8,17,18). In addition to supporting the overall accuracy of thermal dilution, they determined that the sensitivity of the result to mechanical and technique-dependent factors, such as catheter insertion length and speed of injection, was within 3%. This they considered to be biologically insignificant (17).

Others have since obtained good correlation with simultaneous dye dilution and other methods for measuring flow, if not slopes of identity. It is interesting to note that since the dye concentration is usually measured in a systemic artery, dye dilution will provide a measurement of left heart output that is $\sim 4\%$ higher than the right heart output measured by thermal dilution, due to the bronchiolar circulation bypassing the right heart. In addition, all of these reference methods have some of their own uncertainty in calibration, and conclusions are thus necessarily limited.

Exploration of the heat loss during injection has yielded interesting information on variability (16,19,20) but has not quantified the systematic loss to the point of accurate prediction of total injected heat (cold). The *in vitro* studies of effective losses and determination of correction constants provide adequate foundation for an accurate measurement.

Reproducibility

Cardiac output need not be known to great accuracy (within 10% is quite adequate) as long as the measurements are reproducible and can be used to track therapies. The reproducibility (variance) of the measurement with 10 mL of iced solution is generally accepted to be in the range of 10–15%. This is higher with room temperature solutions, and with smaller volumes (21). The reproducibility can be improved by 20–40% with a thermistor sensing the injectate temperature at the injection port in the right atrium. (20,22)

Some factors that can affect the reproducibility of this measurement derive from physiology and some from technique.

Physiology. As noted previously, the cardiac output can be expected to vary over the respiratory cycle, particularly with positive-pressure-assisted ventilation. This is shown quite succinctly in a careful study in animals by Jansen et al. (23) where the injection was made at random, but at known phases of the ventilation cycle. When plotted sequentially in time, the results span a range of ±15% and appear randomly distributed. When ordered according to the phase of the ventilator, the cardiac output result varies cyclically over the course of ventilation, Therefore, a determination of cardiac output using an arbitrary injection time could differ from another determination at another arbitrary time by as much as 30% due, presumably, to real physiologic variations, with flow modulated by intrathoracic and intra-abdominal pressure. Some contribution of baseline drift and thermal noise cannot be discounted by this study.

Clinically, the baseline temperature is usually assumed to be constant during the period of the measurement. Yet blood temperature varies by as much as $0.1\,^{\circ}\mathrm{C}$ over the ventilatory cycle due to differential blood return from the upper and lower extremities. This fluctuation in baseline temperature is typically small compared with the $\sim 1\,^{\circ}\mathrm{C}$ thermal dilution signal obtained with $0\,^{\circ}\mathrm{C}$ injectate, but extends over significant time. It is more significant with room temperature injectates and with heated-filament (continuous cardiac output) signals. The magnitude of the baseline drift can be much greater, particularly with patient movement. Of note, intravenous fluid infusions will affect the blood temperature enormously, particularly during flushes of the lines. The heat output from the heart itself returns into the right atrium from the coronary veins in synchrony with the heartbeat. These pulsations in temperature are less pronounced, being smoothed by the mixing volume in the right ventricle, and cause little practical difficulty.

Since the indicator is introduced immediately upstream of the heart, the solution can, conceivably, transit the heart in a single beat (or very few beats) if the ejection fraction is high. (Thermal dilution curves obtained with fast-response thermistors can be used to determine the ejection fraction by quantifying this washout time when the injection is made directly into the ventricle.) Therefore, these few beats must be representative of the average output for the measurement to be useful. An arrhythmia at the time of injection, occasionally caused by the injection, can lead to a single very large ejection with a very good ejection fraction. In this situation, the measured output will be much larger than the true average cardiac output. The method is not in error, but the measured output is not the steady-state output. Therefore, if arrhythmias are suspected, the measurement should be discarded or a very large variation in results anticipated.

Certain pathologies can affect thermal dilution cardiac output measurements. Tricuspid regurgitation will increase the effective mixing volume for the indicator, thus increasing the extent and decreasing the magnitude of the thermal transient. However, it is important to note that TR does not invalidate the fundamental physical principles upon which the measurement is based. If the computer can wait long enough, the CO measurement in the face of TR should be accurate. In order to be sure this is the case, the practitioner must watch the thermal dilution curve as it evolves on the monitor screen.

Very low ejection fractions can have a similar effect. Although the basic assumptions underlying the measurement remain intact, the curve can be distorted to an extent that makes the practical measurement unreliable. More serious problems are caused by an incompetent pulmonic valve. This valve is necessary to minimize the nonlinear averaging effects of the pulsatile flow, and any flow reversal at the thermistor can lead to multiple re-measurement of the thermal transient. Either of these effects degrades the cardiac output determination.

Technique. Thermal dilution measurements are reasonably insensitive to variations in operator technique. As noted above, the injectate will not warm significantly as the syringe is handled briefly prior to injection. And if this is a concern, probes can be used which measure the temperature of the injectate as it is injected. The content of the injection catheter dead space must be considered to achieve a high level of reproducibility. If multiple measurements are made over a short period of time, that is, to average several serial determinations, sufficient time must be allowed for the residual injectate to return to blood temperature. A couple of minutes appears sufficient to warm the dead space as well as to allow the blood temperature to return to a stable baseline. One strategy is to discard the first measurement, using it merely to fill the dead space with a cool solution. Another strategy for assuring a consistent effect from the dead space is to withdraw blood immediately following the injection. The potential for blood clotting, however, limits the applicability of this procedure. As noted earlier, some catheters can measure the temperature of the injectate at the point of injection (20,22) thus minimizing these effects.

In summary, judicious choice of the time of injection can improve reproducibility. Attention should be paid to the phase of ventilation, to changes in any concomitant intravenous fluid infusions, and to any concurrent cardiac arrhythmias. The temperature curve can be recorded from most cardiac output computers. This curve, and the prior baseline, can give the knowledgable operator evidence on which to judge the validity of a particular result. Recall, however, that the time course of the thermal curve is not necessarily the same as the time course of the thermal transient in the flow stream. Most clinicians use a single measurement to guide therapy although in many settings, such as in studies, it is still common practice to use the average of three serial cardiac output determinations or to discard the outlier and average the remaining two.

Ease of Use

The ease and robustness of thermal dilution measurements of cardiac output are probably responsible for its clinical popularity. The equipment is straightforward to operate, and specialized technicians are not needed to acquire reliable data. The right heart catheters may be placed for other clinical reasons without fluoroscopy. When a measurement of cardiac output is indicated, all that is necessary is to attach a computer and inject cold solution.

FUTURE DEVELOPMENTS

This measurement is simple, fundamentally inexpensive, and has remained popular for several decades. It is, however, moderately invasive. If the need for the pressure information from the pulmonary artery catheters was reduced or supplanted, the ease of making a thermal dilution measurement would diminish. There are liabilities and contraindications associated with pulmonary artery catheters and the injection of cold solutions, and this measurement is not always prescribed in critical care. Use of PA catheters is falling somewhat as other methods of assessing cardiac filling and function become more widely available, such as ultrasound-based measurements and central venous lines. However, several million pulmonary artery catheters are used each year in North America and their widespread use is likely to continue. It is interesting that many surgeons who must manage their patients via phone consultations rely heavily on PA catheter measurements, especially when the ICU team does not include experienced physicians.

Indicator-dilution measurements of the sort described in this article are fundamentally intermittent. In many cases, a continuous measurement would be favored. Continuous cardiac output measurement with the heated filament paired with advanced signal processing is becoming popular, and other techniques such as analyzing pulse contours are also becoming more accepted. Thermal dilution with 10 mL of iced solution is the standard against which these techniques are compared, and periodically calibrated (13).

Catheters will continue to improve, with better clot resistance, materials, additional lumens, heating elements and sensing elements as measurements demand. Cardiac output is integrated into measurement systems forming part of derived parameters and important correlations, a trend that will continue to follow medical instrumentation and healthcare information technology in general. And as the reliability of the measurements increases with experience and technology, the long-promised closed-loop therapies may become a reality.

BIBLIOGRAPHY

1. Stewart GN. Researches on the circulation time and on the influences which affect it. IV. The output of the heart. J Physiol (London) 1897;22:159–183.
2. Hamilton WF, Moore JW, Kinsman JM, Spurling RG. Simultaneous determination of the pulmonary and systemic circulation times in man and of a figure related to the cardiac output. Am J Physiol 1928;84:338–344.
3. Kinsman JM, Moore JW, Hamilton WF. Studies on the circulation. I. Injection method; physical and mathematical considerations. Am J Physiol 1929;89:322–330.
4. Fegler G. Measurement of cardiac output in anaesthetized animals by a thermo-dilution method. Q J Exp Physiol Cogn Med Sci 1954;39:153–164.
5. Fegler G. The reliability of the thermodilution method for determination of the cardiac output and the blood flow in central veins. Q J Exp Physiol Cogn Med Sci 1957;42:254–266.
6. Dow P. Estimations of cardiac output and central blood volume by dye dilution. Physiol Rev 1956;36:77–102.
7. Swan HJC et al., Catheterization of the heart with use of a flow-directed balloon-tipped catheter. N Engl J Med 1970;283: 447–451.
8. Ganz W, Swan HJ. Measurement of blood flow by thermodilution. Am J Cardiol 1972;29:241–246.
9. Perl W, Lassen NA, Effros RM. Matrix proof of flow, volume and mean transit time theorems for regional and compartmental systems. Bull Math Biol 1975;37:573–588.
10. Trautman ED, Newbower RS. The development of indicator-dilution techniques. IEEE Trans Biomed Eng 1984;BME-31:800–807.
11. Philip J et al., Continuous thermal measurement of cardiac output. IEEE Trans Biomed Eng 1984;BME-31:393–400.
12. Yelderman ML et al., Continuous thermodilution cardiac output measurement in intensive care unit patients. J Cardiothorac Vasc Anesth 1992;6:270–274.
13. Schmid ER, Schmidlin D, Tornic M, Seifert B. Continuous thermodilution cardiac output: clinical validation against a reference technique of known accuracy. Intensive Care Med 1999;25:166–172.
14. Spector WS, editor. Handbook of Biological Data. Philadelphia: Saunders; 1956; Mendlowitz M. The specific heat of human blood. Science 1948;107:97–98.
15. Diem K, editor. Documenta Geigy, Scientific Tables. Ardsley (NY): Geigy Pharmaceuticals; 1962.
16. Meisner H et al., Indicator loss during injection in the thermodilution system. Res Exp Med 1973;159:183–196.
17. Forrester JS et al., Thermodilution cardiac output determination with a single flow-directed catheter. Am Heart J 1972;83:306–311.
18. Ganz W et al., A new technique for measurement of cardiac output by thermodilution in man. Am J Cardiol 1971;27:392–396.
19. Vliers ACAP, Visser KR, Zijlstra WG. Analysis of indicator distribution in the determination of cardiac output by thermal dilution. Cardiovasc Res 1973;7:125–132.
20. Lehmann KG, Platt MS. Improved accuracy and precision of thermodilution cardiac output measurement using a dual thermistor catheter system. J Am Coll Cardiol 1999;33:883–891.

21. Bourdillon PD, Fineberg N. Comparison of iced and room temperature injectate for thermodilution cardiac output. Cathet Cardiovasc Diagn 1989;17:116–120.
22. Williams JE Jr., Pfau SE, Deckelbaum LI. Effect of injectate temperature and thermistor position on reproducibility of thermodilution cardiac output determinations. Chest 1994; 106:895–898.
23. Jansen JRC et al., Monitoring of the cyclic modulation of cardiac output during artificial ventilation. In: Nair S, editor. Critical Care and Pulmonary Medicine. New York: Plenum; 1980. p 59–68.

See also CARDIAC OUTPUT, FICK TECHNIQUE FOR; CARDIAC OUTPUT, INDICATOR DILUTION MEASUREMENT OF; CORONARY ANGIOPLASTY AND GUIDEWIRE DIAGNOSTICS; MICROPOWER FOR MEDICAL APPLICATIONS; THERMISTORS.

CARDIOPULMONARY BYPASS. See HEART-LUNG MACHINES.

CARDIOPULMONARY RESUSCITATION

EDWARD GRAYDEN
Mayo Health Center
Albertlea, Minnesota

INTRODUCTION

Cardiopulmonary resuscitation (CPR) may be defined as the emergency restoration of vital functions in a person who has undergone a life-threatening event. The term "cardiopulmonary resuscitation" is actually misleading since the goal of all CPR is to return the victim to appropriate cerebral function; cardiopulmonary resuscitation is the vehicle by which the rescuer attempts to reach this goal. The process of resuscitation may be viewed as a continuum where at one end of the spectrum psychomotor skills of CPR may be initiated by a lay bystander who might be the first rescuer on the scene of an accident, witness to someone choking on food at a restaurant, or perhaps is present when a family member succumbs to a heart attack. Cardiopulmonary resuscitation may also be viewed in a more general and organizational sense to encompass the entire process of the emergency response to victims. The education and training of the public and first responders in basic life support, such as policeman and firefighters, is the cornerstone in an attempt to reduce sudden death through lifesaving skills. Training in basic life support focuses on providing the rescuer with the ability to recognize emergencies, activate the Emergency Medical System (EMS, 911), maintain an airway, provide effective rescue breathing and cardiac circulation. American Heart Association sponsored programs also focus on prevention of risk through education of the public regarding the etiologies of coronary artery disease, myocardial infarction (heart attack), and cerebrovascular disease (stroke). Information presented through these programs attempts to modify lifestyle patterns and behaviors, such as smoking, known to cause or exacerbate these events. The new focus in community emergency response is in the training of laypersons in the use of the Automatic External Defibrillator (AED). Documentation of successful resuscitation in communities with high proportions of the public trained in CPR and use of an AED reach 49% in out-of-hospital victims known to have suffered ventricular fibrillation (a terminal cardiac dysrhythmia that is a common endpoint in the progression toward death) (1,2). Currently, there has been significant progress made in making these automatic defibrillators present in communities and in public places, such as shopping centers, sporting event facilities and mass transportation. The American Heart Association "ABCs" of CPR (airway, breathing, circulation) have now been supplanted with the "ABCDs" (airway, breathing, circulation, defibrillation). The progression of CPR continues into Advanced Cardiac Life Support (ACLS) supervised by a physician and consists of BLS as well as sophisticated adjuncts to provide oxygenation and ventilation, intravenous access with administration of drugs that support circulation, monitoring of cardiac rhythms with rapid interpretation of dysrhythmias and subsequent maneuvers to terminate or suppress these harmful cardiac electrical abnormalities, and postresuscitation care.

This article will first review the history of CPR followed by a detailed analysis of the pulmonary and cardiac physiology relevant to the application of these resuscitative functions. An overview of Emergency Cardiac Care (ECC) will be undertaken to enlighten the reader about the organizational process guiding CPR. The actual mechanism of BLS and ACLS will be then addressed with a brief overview of defibrillators. Finally, the salient points of this article will be summarized and future directions of resuscitation will be explored.

HISTORICAL PERSPECTIVE

Restoration of life to the dying has been a common action from antiquity to the present time. Ancient attempts at artificial respiration have been described by the prophet Elisha in the Bible (3). Galen was able to observe the inflation of a dead animal's lungs in the second century, but there has been no recording of this significant finding applied to early attempts at resuscitation (4). Resuscitation methods during this time were futile—such as applying hot materials to the abdomen or whipping the victim; animal bladders were expanded with smoke and then the outlets of these bladders placed into the dying person's rectum (5). Centuries later Paracelsus, a Swiss physician (1493–1591), first reported the use of a fireplace bellows to ventilate a dying patient. In 1740, the Paris Academy of Sciences recommended the instillation of air into a victim through a mouth-to-mouth technique and within 4 years Tossach used this method successfully to revive a person (4). Ironically, this technique was lost, only to be rediscovered some 200 years later. During the eighteenth century, multiple new attempts at artificial respiration occurred. The "Inversion Method" practiced in Europe and America was used for drowning whereby the victim was hung upside-down in an effort to drain water from the lungs and many successful attempts have been recorded for this maneuver. The "Barrel Method" as well as the "Trotting

Horse Method" were also used at this time consisting of rotating the prone drowning victim over a barrel that alternated chest compression (expiration) and chest relaxation (inspiration) or placing the drowned individual prone on a horse, with the bouncing incurred during the trot inducing the same rhythmic compression and relaxation (5). The realization that alternating compression and relaxation of the chest could induce expiration and inhalation, respectively, led to direct manual efforts by the rescuer. DeHaen in 1783 first described a chest compression, arm-lift combination (6). Leroy reported the first use of the supine victim ventilation position ~ 1830 and later in this century (~ 1860–1870s) Silvester's, Howard's, and Schafer's prone methods of manual compression became popular and persisted into the twentieth century. The familiar Schafer–Emerson–Ivy ventilation method of scapular compression combined with pelvic-lift emerged in the United States at the beginning of this century.

The efficacy of these various methods of manual artificial respiration was resolved in the 1950s by Gordon, who performed experiments upon fresh corpses prior to rigor mortis and then on volunteers who underwent general anesthesia and paralysis by curare. Ventilatory volumes were measured and the "push–pull" maneuvers that caused active inspiration and expiration were at least twice as effective as the Schafer method or other procedures that only produced either active inspiration or expiration (7–9). The Holger–Nielson method (prone back-pressure, arm-lift) for resuscitation became the standard of care.

At the time of these scientific studies attempting to clarify manual methods of artificial respirations, Elam elected to evaluate the physiology of mouth-to-mouth ventilation. As an anesthesiologist, Elam had serendipitously performed mouth-to-mouth ventilation to paralyzed polio patients, for as long as several hours. Though mouth-to-mouth or mouth-to-nose ventilation had been know to have been practiced by midwives for the newborn, the question posed by this physician was, "What was the mechanism involved in the success of exhaled-air ventilation?" (10). The answers to this question came from a series of experiments where volunteers allowed themselves to be paralyzed while awake, and then ventilated by mouth-to-mouth, mouth-to-mask, or mouth-to-endotracheal tube by Elam and his colleagues until the paralyzing agent was allowed to wear off. Blood gas values were analyzed and the conclusion was that normal physiological parameters could be maintained by exhaled-air ventilation (11). This landmark study brought forth the subsequent challenge to the current back-pressure, arm-lift mode of artificial ventilation. In an effort to answer the question of which form of artificial oxygenation and ventilation would prove superior, a series of controlled experiments was then conducted by Elam and Safar. The various lung volumes with blood gas analysis for the back-pressure, arm-lift was compared with mouth-to-mouth ventilations. These two methods were used on awake, paralyzed volunteers and patients without any mask, endotracheal tubes or adjunctive airway support! These experiments also investigated the mechanisms of soft tissue airway obstruction and the effectiveness of head-tilt and jaw-thrust in maintaining the airway in rescue breathing (the jaw-thrust was first described in Germany by Esmarch and Heiberg in the nineteenth century). The data and conclusions of these studies were published and within one year a dramatic change was made within the American and International Red Cross, global medical associations and the Armed Forces. Modern resuscitation through mouth-to-mouth oxygenation and ventilation was born through these landmark investigations (12–20). "Airway, Breathing" of the "ABCs" for current CPR principles had been founded.

The advent of electrical energy production in the eighteenth century made possible the first recorded successful defibrillation by Squires in 1775; a landmark publication came later in 1809 when Burns hypothesized that effective resuscitation would occur with the combination of artificial ventilation and electric shock (6). Even though a primitive "shock instrument" was fabricated by Aldini (6) in the 1830s, there did not appear to be any significant research into electrical cardiac excitation until much later in the century. The miraculous discovery of anesthesia in the 1840s unfortunately led to catastrophic complications. Documentation of the first case of cardiac arrest was reported in 1848 when a child died under chloroform anesthesia while having a superficial procedure completed (21). As this type of complication became more commonplace, research began to focus upon cardiac physiology and mechanisms to restore the normal heart rhythm and function. Open-chest cardiac compression was first reported by Schiff in 1847 during unsuccessful attempts to circulate blood in dogs and 2 years later Niehans reported an emergency attempt at open cardiac compression in a patient who arrested during an induction of general anesthesia using chloroform. Cardiac contractions reoccurred for a brief time prior to the patient's death (21). Interestingly, in 1847 Boehm reported the first study of closed-chest cardiac compressions in cats (22). The chest was compressed with a rhythmic motion and a cardiac pressure was sustained. In the next 10 years, Koenig and Maass reported eight successful closed-chest cardiac compressions in humans (23) secondary to anesthetic-initiated cardiac standstill; one of these resuscitations lasted for more than 1 h (24). Unfortunately, the open-thorax mode of direct cardiac massage was to be the predominant form of attempted circulatory support for the next 60 years despite these reports.

Alternating current, brought forth by the investigations of Tesla, was first reported by Prevost and Batelli to stop dog heart fibrillation in 1899 (25). Intense research into terminal cardiac dysrhythmias and electrical termination of these lethal rhythms was started in the United States by Kouwenhoven, a professor of electrical engineering, in 1928. The funding for this project was undertaken by the Consolidated Edison Company because of the numerous fatalities induced by electrocution of its employees. Termination of ventricular fibrillation through electrical countershock was confirmed and the effects of both alternating and direct current were investigated in the dog open heart model. By 1933, this group had described the principles necessary for successful open heart alternating current (ac) defibrillation (26). In 1939, the Russians Gurvich and Yuniev were the first to describe successful external defibrillation and reported that direct current (dc) countershock was superior to ac generated currents. They reported that a capacitor discharge applied to the exterior of the dog's chest would stimulate a cardiac rhythm if only applied no later than 1.5 min after the induction of ventricular fibrillation; however, they noted that the time to successful defibrillation could be extended to as long as 8 min by the application of external chest compressions. There was no description as to how these chest compressions were done (27). Unfortunately, their report was not available to western researchers until 1947 and substantiation of the benefits of dc versus ac would not be made for a number of years.

The research of Kouwenhoven at the Johns Hopkins Hospital continued in defibrillation experiments and in 1958 Knickerbocker, a research fellow, made an astute observation; during a defibrillation experiment he noted a pressure wave form being generated by the application of external electrodes on the dog's thorax (28). During a later, but similar study, Knickerbocker had a dog unexpectedly start to fibrillate and since defibrillation electrodes were not immediately available, he employed the same type of pressure upon the dog's sternum that he had found to generate a systolic pressure. After ~5 min of chest compression, the animal was successfully defibrillated into a normal sinus rhythm. A surgeon, Dr. James Isaacs, who was also conducting experiments in the same laboratory, became aware of this incident and had the foresight to encourage new research by this group into the generation of circulatory blood pressures by external cardiac massage (29). During these subsequent studies, arterial-venous pressure gradients were found to be generated and carotid artery flow was documented. Data that was reproducible indicated that if chest compressions were initiated within 1 min of ventricular fibrillation and continued for as long as 20 min, dogs could be resuscitated by defibrillation and appeared to have no deficits in central nervous system function. Further experimentation on dogs led to the conclusion that the optimum location for chest compressions was on the distal one-third of the sternum with a force of between 35 and 45 newtons (30). Even though postmortem studies revealed numerous injuries, such as rib fractures to these animals, the life-saving benefits were very apparent. Soon the practicality of closed-chest compressions became evident when Kouwenhoven and Isaacs made these laboratory observations available to the surgical staff and, in the same year, a 2-year old child was successfully resuscitated in the operating room at Johns Hopkins Hospital. An organized approach directed at patient resuscitation followed, resulting in 118 cases of successful restoration of life by chest compression following documented ventricular dysrhythmia (31).

Further collaboration at this time by Safar, Elam, and Kouwenhoven resulted in the basic tenets of modern CPR. Since external cardiac chest compressions were found not to produce adequate tidal volumes from airway obstruction (32), control of the airway confirmed by head-tilt data became the "A" in the "ABCs" of CPR. Exhaled air ventilation would become the "B" for rescue breathing. The addition of cardiac compressions, the "C" in the rudiments of basic cardiopulmonary resuscitation was then combined to produce what is now the standard protocol of care in basic life support. The final studies determined what ratio for breathing and chest compressions would be used; one rescuer CPR utilized 2 breaths for every 15 compressions while the addition of a second rescuer could increase the ratio to 1 ventilation per 5 chest compressions (33).

While the first open chest defibrillation in an operating room was reported by Beck at Case Western University in 1947, Zoll reported the first successful closed-chest or external defibrillation in humans (34). This early defibrillator utilized 60 Hz ac current of 1.5 A at a range of 120–150 V. A 6:1 isolation step-up transformer converted the 120-V line current to a range of 0–720 V with the duration of current set at 0.15 s by a condenser-relay circuit. The machine was capable of producing 12,000 W during this time interval. The copper electrodes were 7.5 cm in diameter. This paper described the successful countershock for terminating ventricular fibrillation in four patients. The advent of external cardiac defibrillation would now usher in modern cardiopulmonary resuscitation when conjoined with airway manipulation, rescue breathing, and closed cardiac chest compressions.

The historical evolution for understanding the mechanisms of cardiopulmonary resuscitation has been paradoxical; the physiology of rescue breathing appears to have been well understood versus the mechanisms of cardiac flow due to chest compressions. Positive pressure ventilation, of which mouth-to-mouth resuscitation is an example, utilizes different mechanical principles to expand the lungs versus normal breathing, but the gas exchange once in the alveoli is very similar. The action of chest compressions, however, has remained controversial. After the serendipitous finding of increased blood pressure upon application of defibrillator paddles, Kouwenhoven hypothesized that sternum compression of the heart against the spine forced blood out of the ventricles (28), but no hemodynamic studies supported this claim. Further research demonstrated an increased venous pressure equal to arterial pressure during chest compression that brought into question whether the heart ejected blood in the normal manner (35). A study 1 year later actually measured cardiac output in patients being resuscitated utilizing external cardiac compressions. The ejected blood was found to have flows approximately one-quarter of normal even though systolic blood pressures appeared to be adequate (36). An investigation of actual intravascular pressures during external cardiac compressions determined that left atrial (venous) pressure was very close to arterial pressure, which argued against a projectile expulsion of blood by the heart. The hypothesis of this study was that the requisite flow needed for organ perfusion was driven by the action of the cardiac valves. This action was thought to account for the arterial-venous pressure gradient to sustain oxygen delivery (37). The cardiac compression–cardiac flow hypothesis was further contested with a series of studies generated by the observation that coughing by patients sustained blood pressure. Reports of successful resuscitation in documented ventricular fibrillation by coughing led to research that compared arterial pressures produced by chest compressions to that produced by cough. The conclusion was that improved hemodynamic parameters occurred with coughing CPR (38). Further interest into these mechanisms was induced by a number of reports whereby trauma patients with a flail chest were not able to be resuscitated through closed-chest compressions; a flail chest results when the thoracic cage is compromised during rib fracture. Direct cardiac compression should be easier to produce since the ribs offer no resistance. Evidence appeared to support increased intrathoracic pressure rather than direct cardiac compression as the mechanism producing blood flow (39,40). Echocardiography was also utilized in several studies where CPR was initiated in humans; the cardiac valves were visualized and noted to be in the open position. Additionally, the left ventricle did not appear to be compressed, again lending credence to the "thoracic pump" theory of blood flow (41,42). Unfortunately, this theory could not account for coronary circulation blood flow or as to the mechanism of blood flow during disruption of intrathoracic pressure, such as when a pneumothorax (collapsed lung) occurs. Subsequent research utilizing very sophisticated instrumentation determined that, indeed, pressure gradients were generated with chest compressions in animals relative to aortic and thoracic venous vessels, data not supported by the thoracic pump theory. Contrast dye echocardiography demonstrated typical opening and closure of the mitral valve with projection of the contrast being propelled throughout the heart and then into the aorta (43,44). The momentum changed with these studies in elucidating the exact mechanism for blood flow, resupporting the cardiac compression hypothesis. What is currently hypothesized today is that both mechanisms seem to operate relative to resuscitation–generated cardiac ejection of blood. The key to understanding this paradox is that chest compressions involve two forces: compression and release of pressure upon the sternum. Compression of the heart forces blood through the atria and ventricles with flow generated, as evidenced by arterial and venous pressure gradients. Release of sternum pressure appears to augment venous return, supporting the thoracic pump theory. Therefore, it appears at this time that the current literature supports both mechanisms in CPR generated blood flow (45).

PULMONARY PHYSIOLOGY

Pulmonary function provides for the oxygenation of tissues and the removal of carbon dioxide from cell metabolism; human's survival is dependent on this function. It is by no coincidence that the first two actions of cardiopulmonary resuscitation, airway establishment and then rescue breathing, must be accomplished prior to chest compressions. Resuscitation is hopeless unless oxygenation and ventilation can be established. It is easiest to appreciate pulmonary function as a progression of air transport from the airway into the lungs, with an overview of lung mechanics and the molecular basis for oxygen and carbon dioxide transport.

After a volume of air is breathed through the oral or nasal passages, this inspired gas passes to the lungs by way of the trachea, bronchi, and bronchioles. Muscular tone in the soft palate and pharynx maintain this anatomical area of the airway. The trachea is supported by numerous cartilaginous rings. At the bronchiole and alveolar level, transpulmonary pressures are responsible for patency. Cardiopulmonary resuscitation of the unconscious victim demands that the first action taken by the rescuer is to make sure that the airway is open. The usual cause is obstruction of the airway by the tongue or soft tissues. Maneuvers to open the airway are the first line treatment in CPR when a person is found to be unresponsive.

The lungs function by expanding through a negative pressure pump mechanism causing inspiration of air by two mechanisms. The diaphragm, a large muscle located at the lung bases, contracts increasing the subatmospheric pressure and thus producing a pressure gradient relative to ambient air. Movement of the rib cage acts in conjunction with the diaphragm, as lung expansion occurs during elevation of the ribs. Normally, the ribs are positioned in a superior–inferior dimension; as the thoracic cage is raised, the ribs move in an anterior–posterior direction, increasing the intrathoracic lung compartment by $\sim 20\%$. The lung expansion through this mechanism also acts to produce a subatmospheric gradient, drawing air into the lungs. This occurs because the lung volumes increase at a more rapid rate than gas flow through the airway. As energy is utilized to cause this expansion, expiration during normal breathing is simply the result of the elastic recoil of the lungs and air is expelled, as now the pressure gradient reverses. During episodes of rapid oxygen metabolism, the work of breathing increases and thus the rapidity of chest wall movement requires a forceful expiration. The abdominal musculature functions in this manner to compress the diaphragm. It should be apparent that pressure–volume relationships establish the adequacy of lung mechanics. Transmural pressures, that is, the difference between the interior of the lung minus the lung exterior (or the pleural space, which separates the lung from the chest wall), define the various lung volumes as well as being a measure of elastic forces on the lung (the force tending to cause lung collapse). The slope of the P–V curve at any point represents the lung compliance; in the normal adult lung this averages 200 mL of air/cm of water, that is, when transpulmonary pressure increases by 1 cm of water, the lungs expand by 200 mL. Lung compliance is not only affected by the elastic force of the lung tissue, but also by the forces generated by surface tension in lung and pleural fluids. This surface tension elastic force is reduced in the lung by surfactant, a complex molecule primarily composed of phospholipids, which has hydrophilic and hydrophobic moieties.

When a rescuer determines that a person is unconscious and begins CPR, the airway is first opened and then rescue breathing is attempted. As mouth-to-mouth ventilations are instituted, now the lungs are expanded by positive pressure, quite different than the previously described normal mechanism. The intraalveolar as well as intrapleural pressure will rise above atmospheric pressure. The diaphragm is progressively pushed toward the abdomen in contradistinction to this muscle's upward or cephalad movement with contraction. Upon expiration, the intrapleural pressure, which is positive, decreases to subatmospheric pressure upon end-expiration and the diaphragm also moves away from the abdomen. When



Figure 1. The dynamic lung volumes that can be measured by simple spirometry are the tidal volume, inspiratory reserve volume, expiratory reserve volume, inspiratory capacity, and vital capacity. The static lung volumes are the residual volume, functional residual capacity, and total lung capacity. Reprinted from Anesthesiology, 4th ed., Benumof: Respiratory Physiology and Respiratory Function During Anesthesia, p. 590, 1981, with permission from Elsevier Science.

positive pressure ventilation is employed in other clinical settings, such as with ventilator therapy, a constant concern is that with any damage to the lungs, gases will be propelled into the pleural space. If there is no egress of these gases, a ball-valve mechanism ensues, and the increasing positive pressure in this pleural space will compress the lung, causing hypoxemia and death (pneumothorax).

The lungs are subdivided into four static volumes and four capacities (Fig. 1). A capacity is the combination of two or more lung volumes; capacities are helpful in describing the pulmonary function and disease processes. A device called a spirometer, invented in 1846 by Huntchinson for amusement purposes, is used for these measurements (46). The original machine was a watertight bell emersed in a water tank and connected by tubing to the patient's airway. As this bell moves with inhalation or exhalation, an attached writing instrument marks these volumes on a chart. The current spirometers utilize a bellows or piston with electronic circuitry. All measurements are representative of the average adult man. These volumes and capacities are 20–25% less in women.

1. Tidal Volume: The volume of air either inspired or expired with a normal breath; This is ~500 mL; these are minimum volumes that are typically attempted in rescue breathing.
2. Inspiratory Reserve Volume: This is the maximum volume of air that can be inspired after a normal tidal volume; it is ~3000 mL.
3. Expiratory Reserve Volume: The maximum volume of air that can be ejected after expelling the tidal volume; it is ~1100 mL.
4. Residual Volume: The volume of air remaining in the lungs after a maximal expiration; this volume is ~1200 mL.

The four lung capacities consist of the following:

1. Inspiratory Capacity–Tidal Volume plus Inspiratory Reserve Volume: This volume represents the maximum amount of air that can be inspired after a normal expiration and represents ~3500 mL.
2. Functional Residual Capacity–Expiratory Reserve Volume plus Residual Volume: The volume of air in the lungs after a normal expiration; ~2300 mL.
3. Vital Capacity–Inspiratory Reserve Volume plus Tidal Volume plus Expiratory Reserve Volume: This volume is the maximum amount of air that can be expelled after a maximum inspiration and is ~4600 mL.
4. Total Lung Capacity–Vital Capacity plus Residual Volume: The maximum volume of air that can be expired after greatest possible inspiration.

The minute respiratory volume is equal to the tidal volume as a product of the respiratory rate. Since the normal tidal volume is ~500 mL and the normal respiratory rate is ~12–15 breaths/min, the minute respiratory volume is ~6–7.5 L/min. The inspired and expired volumes are not quite equal since the volume of oxygen absorbed through the alveoli is slightly greater than the volume of carbon dioxide that is expired. Only the inspired air that reaches the alveoli can participate in oxygenating the blood. There is a portion of a normal inspiration that does not reach the alveoli and this volume of gas is referred to as dead space ventilation. Anatomic dead space refers to the volume of gas from the nose, mouth, and trachea to the respiratory bronchioles. This volume averages ~2.2 mL/kg. Thus in a normal tidal volume of 500 mL, only 350 mL of air and thus 72 mL of oxygen, is available for gas exchange.

The tidal volume and the respiratory rate have a profound effect upon the total alveolar ventilation. This fact has been reflected in the revisions of CPR literature over the years. Suppose patients all have the same total minute ventilation of 5000 mL. The first patient has only a small tidal volume of 150 mL and is breathing 33 times/min, producing a minute ventilation of ~5000 mL. Recall that not all of the air in a breath reaches the alveoli; dead space is ~150 mL. The total dead space ventilation would be equivalent to the total minute ventilation. The actual alveolar ventilation would be zero. This patient will become hypoxic very quickly. The second patient has a tidal volume of 250 mL and is breathing at a rate of 20 times/min. The total minute ventilation will be again 5000 mL. The alveolar ventilation will be 2000 mL. The third patient has a tidal volume of 500 mL and a breathing rate of 10 times/min; again the total minute ventilation is 5000 mL, but in this case the actual alveolar ventilation is 3500 mL. The conclusion that should be drawn from these examples is that the efficiency of ventilation is greater when the tidal volume is increased versus the equivalent change in respiratory rate relative to total alveolar ventilation.

The composition of air that one breathes changes significantly from the atmosphere to the alveolus. At sea level, nitrogen produces a partial pressure of ~597 mmHg and composes ~78% of room air. Oxygen has a partial pressure of 159 mmHg and represents almost 21% of the total for atmospheric gas. Carbon dioxide and water make up the remaining partial pressures and percentages. Once the air is humidified by the nasal and oral airways, water vapor comprises 47 mmHg and increases to ~6% of the mixture with a corresponding reduction for nitrogen and oxygen. The alveolar air has a reduction in both nitrogen (569 mmHg, 75%) and oxygen (104 mmHg and 13%). In the clinical setting, the alveolar oxygen tension is an extremely useful measurement to evaluate the variables in pulmonary mechanics and gas exchange. The ideal alveolar gas equation is useful approximation and is expressed as follows:

$$PA_{O_2} = [(P_B - P_{H_2O})(F_IO_2)] - \frac{PA_{CO_2}}{R} + F$$

Where PA_{O_2} is the partial pressure of oxygen in the alveoli; P_B is the barometric pressure; P_{H_2O} is the partial pressure of the water vapor in the alveoli at 37 °C; F_IO_2 is the partial pressure of oxygen; $PACO_2$ is the partial pressure of alveolar carbon dioxide; R is the ratio between the volume of carbon dioxide diffusing from the pulmonary blood to the alveoli and the oxygen diffusing from alveoli into pulmonary blood. Approximately 200 mL/min of carbon dioxide versus 250 mL of oxygen exchange, so the ratio 0.8. F is a small correction factor that can be ignored clinically. Therefore, for example, suppose that a patient has been medicated with opioids after a painful operation and the alveolar partial pressure rises to 65 mmHg since these drugs reduce the respiratory sensitivity to carbon dioxide. The barometric pressure is 760 mmHg.

Therefore,

$$PA_{O_2} = [(760 - 47)](0.21) - \frac{65}{0.8}$$

$$PA_{O_2} = 68 \text{ mmHg}$$

These figures have a profound influence upon oxygenation in resuscitation. A simplified example will enlighten the reader; from the previous review of lung volumes, the total lung capacity is ~5000 mL. If roughly 20% of the atmosphere is oxygen, then 20% of the total lung volume, 1000 cm^3, will contain oxygen. As mentioned earlier, the basal metabolic rate for oxygen consumption is ~250 mL/min. Therefore, the quotient of the 1000 cm^3 relative to the oxygen consumption of 250 mL/min yields 4 min until hypoxia ensues from lack of oxygen. This is reason why time is so critical for the rescuer; unfortunately, the brain is the most oxygen-sensitive organ in the body and cerebral function diminishes rapidly after this critical four minutes. In ACLS, supplemental oxygen is immediately made available to the victim. Given the previous example, if 100% oxygen is administered without entrainment of room air (and nitrogen), now the total lung volume of oxygen would be 5000 cm^3. At the same basal metabolic rate for oxygen utilization, 250 mL/min, theoretically the patient could remain apneic for 20 min before hypoxia would ensue! Practically, this does not occur because of the metabolic byproduct of carbon dioxide diffusing into the alveoli as well as the tremendously increased energy requirements caused by the ventricular dysrhythmias; however, the point to be made here is how the atmospheric composition of gases can easily be altered by the addition of supplemental oxygen to improve the mortality and morbidity of cardiopulmonary resuscitation.

Alveolar ventilation is the ultimate endpoint with respect to lung mechanics. Air must be transmitted throughout the respiratory passages until oxygen can be absorbed by the blood. As a person inspires a normal tidal volume, the contained oxygen reaches the terminal bronchioles. Interestingly there is no organized flow of gas from this point to the alveoli; the oxygen traverses the respiratory bronchiole and alveolar duct into the alveolus for gas exchange by simple diffusion. Once the oxygen reaches the alveolar membrane, the diffusing capacity, which averages 21 mL/min per mmHg, causes the 250 mL of oxygen to traverse the respiratory membrane since the driving oxygen pressure difference is ~12 mmHg. The basic metabolic rate for oxygen utilization is equal to 250 mL/min. Therefore, during quiet respiration, with normal tidal volumes, oxygen intake is appropriate for oxygen utilization. When physical work or exercise increases the metabolic requirements for oxygen, the diffusing capacity can increase threefold in a young healthy adult male. The egress of carbon dioxide through the alveolar membrane is also crucial for survival. The diffusing capacity has never been measured accurately for carbon dioxide due to the rapidity with which this gas passes from red blood cell to alveolus; however, since the diffusion coefficient of carbon dioxide is ~20 times that of oxygen, a range of between 400 and 1200 mL/min per mmHg would be expected for this gas.

OXYGEN AND CARBON DIOXIDE TRANSPORT

Once oxygen diffuses through the alveolar membrane and enters the venous pulmonary blood, it is primarily carried in combination with hemoglobin encased in the red blood cells and secondarily in solution. Hemoglobin is a tetramer molecule consisting of four amino acid polypeptide chains and four heme groups. The globin, or protein portion, consists of two pairs of identical alpha chains and, in the adult hemoglobin, two beta chains. The locus for the alpha chains is located on chromosome 16. The alpha chain is always present; however, there may be some variety in the non-alpha chain. Fetal hemoglobin, for example, has two gamma chains, which increases the hemoglobin binding of oxygen, increasing the efficiency of maternal oxygen transport across the placenta. The four heme moieties are located in the center of each globin molecule. Heme is synthesized from glycine and succinyl coenzyme A to form a tetrapyrrol ring. Subsequent enzymatic reactions produce a protoporphrin and, finally, ferrous iron is inserted into the center of this ring as a function of mitochondrial synthesis. Since there are four heme-combining sites in each hemoglobin molecule, a maximum of four oxygen molecules can attach to the receptors. When all four receptor sites are combined with oxygen, the hemoglobin has a 100% saturation. If only three molecules of oxygen are bound, the hemoglobin is 75%, and so forth. Oxyhemoglobin is hemoglobin that has oxygen bound to the heme sites (HbO_2); unbound hemoglobin is termed “reduced hemoglogin” or “deoxyhemoglobin” (Hb). The key principle to



Figure 2. The oxygen–hemoglobin dissociation curve. Four different ordinates are shown as a function of oxygen partial pressure (the abscissa). In order from right to left, they are: saturation (%), O_2 content (mL of O_2/0.1 L) of blood; deoxygen (O_2) supply to the peripheral tissues (mL/min); and O_2 available to the peripheral tissues (mL/min), which is the O_2 supply minus ~200 mL/min that cannot be extracted below a partial pressure of 20 mmHg. Three points are shown on the curve: a, normal arterial: v, normal mixed venous; and P_{50}, the partial pressure (27 mmHg) at which hemoglobin is 50% saturated. Reprinted from Anesthesiology, 4th ed., Benumof: Respiratory Physiology and Respiratory Function During Anesthesia, p. 596, 1981, with permission from Elsevier Science.

understand is that oxygen binding to hemoglobin is directly related to the partial pressure of oxygen. As the inhaled air reaches the alveoli and participates in gas exchange, hemoglobin becomes fully saturated with oxygen relative to the partial pressure at the alveolar membrane. Oxygen delivery and unbinding occurs at the tissue partial pressure. The initial binding of the first oxygen molecule to hemoglobin facilitates the further binding of the second molecule, and in turn, these first two molecules facilitate further binding of the third oxygen molecule. This interaction occurs until the fourth oxygen molecule is bound, and this characteristic of changing oxygen affinity of hemoglobin is reflected in a sigmoid curve when the percent saturation of hemoglobin is plotted against the partial pressure of oxygen (Fig. 2).

The curve has a steep and flat portion. The steep slope of the curve reflects the rapid combination of oxygen with hemoglobin as the partial pressure increases. Beyond ~ 60 mmHg, the curve flattens, reflecting very low increases in saturation relative to increases in oxygen partial pressures. The clinical significance of this flat portion of the curve can be observed by noting that a fall from 100 to 60 mmHg only decreases the oxygen saturation from near ~100–90%. This zone of the curve provides for a safe range of minimal saturation and decreases relative to great decreases in partial pressure during oxygen loading. Furthermore, increasing the partial pressure beyond 100 mmHg of O_2 does not really oxygenate the blood to any significant degree; since the hemoglobin is fully saturated, only the dissolved plasma oxygen will increase.

Another significant property of hemoglobin is the fact that the oxygen affinity of this molecule changes with intracellular pH (Bohr effect). As the end product of metabolism, carbon dioxide is present at the tissue level and is converted to a weak acid by the red blood cell catalyst, carbonic anhydrase. This weak acid ionizes to hydrogen ion and lowers the intracellular pH, which decreases the oxygen affinity of hemoglobin, and thus facilitates the unloading of oxygen at the tissue level where it is precisely needed. Since reduced hemoglobin is a weaker acid than hemoglobin, the hydrogen ions are bound and thus deoxyhemoglobin returns to the lungs, where the reverse situation occurs. Carbon dioxide is reconverted in the red blood cell, and with the diffusion of this CO_2 into the alveoli, the pH rises and the affinity of hemoglobin increases for oxygen.

PULMONARY CIRCULATION

Pulmonary blood flow begins with ejection of venous blood from the right ventricle into the pulmonary arteries. Successive arterial branching occurs so that at the level of the alveolar circulation the capillaries lie in intimate contact with the alveoli allowing for a very efficient and exceedingly large surface area for gas exchange. Since the pulmonary arterial pressure is only 20% or so of the systemic circulation, with a mean pressure of ~18 mmHg, these arterioles do not require significant amounts of smooth muscle. Thus the walls of these vessels are extremely thin, allowing for the diffusion of oxygen and carbon dioxide. This characteristic makes these capillaries very susceptible to distortion relative to alveolar pressure. Since the arterial pressure is so low, alveolar pressure may at times exceed pulmonary capillary pressure and this transmural pressure will cause these tiny vessels to collapse. In the upright lung, this situation occurs where pulmonary blood flow pressure is minimal, that is, at the superior aspect of the lungs. This pressure gradient scenario may be observed in Fig. 3.

In *zone 1*, where pulmonary pressure can fall below alveolar pressure, the potential exists for no flow to occur in the capillary. Any situation that decreases systemic blood pressure and thus pulmonary blood flow such as hemorrhage, or increases alveolar transmural pressure, such as might positive pressure ventilation encountered in rescue breathing, might cause this change. The alveolar pressure exceeds pulmonary arterial pressure and, in turn, pulmonary venous pressure.

In *zone 2*, the pulmonary arterial pressure increases due to the elevated hydrostatic pressure as a function of position relative to the column of blood. The alveolar pressure exceeds pulmonary arterial pressure in this zone; however, the pulmonary venous pressure relative to alveolar pressure is low and thus the gradient in this zone is the difference between arterial and alveolar pressure. The analogy to this unique lung region has been described as the vascular waterfall effect (47). The elevation of the river above the dam is described as pulmonary arterial pressure



Figure 3. The Four Zones of the Lung. Schematic diagram showing distribution of blood flow in the upright lung. In zone 1, alveolar pressure (P_A) exceeds pulmonary artery pressure (P_{pa}), and no flow occurs because the intraalveolar vessels are collapsed by the compressing alveolar pressure. In zone 2, arterial pressure exceeds alveolar pressure, but alveolar pressure exceeds venous pressure (P_{pv}). Flow in zone 2 is determined by the arterial–alveolar pressure difference (P_{pa}–P_A) and has been likened to an upstream river waterfall over a dam. Since *P*pa increases down zone 2 and P_A remains constant, the perfusion pressure increases, and flow steadily increases down the zone. In zone 3, pulmonary venous pressure exceeds alveolar pressure, and flow is determined by the arterial–venous pressure difference (P_{pa}–P_{pv}), which is constant down this portion of the lung. However, the transmural pressure across the wall of the vessel increases down this zone so that the caliber of the vessels increases (resistance decreases), and therefore flow increases. Finally, in zone 4 pulmonary interstitial pressure becomes positive and exceeds both pulmonary venous pressure and alveolar pressure. Consequently, flow in zone 4 is determined by the arterial interstitial pressure difference (P_{pa}–P_{ISF}). Reprinted from Anesthesiology 4th ed., Benumof: Respiratory Physiology and Respiratory Function During Anesthesia, p. 578, 1981, with permission of Elsevier Science. Diagram modified and reprinted with permission from West JB: Ventilation/Blood Flow and Gas Exchange, 4th ed., Blackwell Scientific Publishers, Oxford, 1970.

and the dam height analogous to alveolar pressure. The downstream river is equivalent to pulmonary venous pressure. Pulmonary blood flow is relative only to the difference between the height of the river upstream and the elevation of the dam. The distance that the water falls over the dam is immaterial to flow rate. Since the alveolar pressure tends to remain constant throughout this zone, but the pulmonary alveolar pressure increases secondary to the gravity, flow increases linearly. *Zone 2* circulation is unique in that ventilation and cardiac changes may alter flow dynamics, shifting these relationships into a momentary *zone 1* or *3* picture.

The dynamics in *zone 3* are straightforward. Here pulmonary venous pressure exceeds alveolar pressure and blood flow is governed by the arterial–venous gradient, which occurs in the systemic circulation. Blood flow never ceases and all capillaries remain patent, with the additional feature of decreasing alveolar pressure maximizing vessel diameters and decreasing pulmonary vascular resistance. The rate of pleural pressure rises as a function of the transmural pressure gradient between lung apex and base; this pressure does not increase as rapidly as the pulmonary artery–venous difference that optimizes blood flow.

Zone 4 is ordinarily not present in normal lung physiology. Some pathological process is required to increase fluid pressure between cells where pulmonary venous and alveolar pressure is exceeded. Conditions such as iatrogenic fluid overload, pulmonary embolism, high levels of negative pleural pressure encountered with airway obstruction in a spontaneously breathing patient, or thoracentesis maneuvers causing profound negative pleural pressures (48,49) may cause this situation. Pulmonary arterial pressures exceed interstitial pressures, which, in turn exceeds venous and alveolar pressures. Since interstitial pressures are greater than venous pressures, regional blood flow is decreased relative to *zone 3*, and flow is governed by the pulmonary arterial-to- interstitial gradient.

In conclusion, it should be evident that both alveolar ventilation and pulmonary blood flow have a variable distribution throughout the lung. The lung base not only receives more blood flow than the apex but, because the compliance of the basal alveoli is greater than the apical alveoli, the lung base receives a greater amount of the tidal volume. Since the blood flow gradient is steeper than the ventilation gradient, the base is relatively overperfused and thus hypoventilated; the reverse situation occurs in the apex where the lung is overventilated and hypoperfused. These conditions have a profound effect upon end-organ oxygen transport. The first scenario refers to physiologic shunt blood flow; should absolutely no ventilation occur, a true shunt occurs. Decreased ventilation relative to perfusion increases alveolar carbon dioxide and thus, as seen in the alveolar gas equation, alveolar oxygen concentration will decrease. The oxygen content of the systemic arterial blood is decreased and thus oxygen transport to the tissue results in hypoxemia. A ventilated alveoli that is not perfused, as in *zone 1*, does not participate in gas exchange. Alveolar carbon dioxide decreases and alveolar oxygen increases due to the absence of blood flow. This situation is termed “alveolar dead space ventilation”. The composition of alveolar gas is essentially equal to atmospheric gas. The extremes of alveolar dead space ventilation and shunt are ends of a continuum in lung ventilation and perfusion dynamics. Ventilation and perfusion ratios will vary throughout the lung both on an anatomical and physiological basis. The total effective gas exchange can thus be seen as the complex interplay between lung mechanics, ventilation, perfusion, and molecular interactions.

CARDIAC PHYSIOLOGY

The heart is an extremely efficient pump, which results in the progressive pulsatile ejection of blood to the organs. The heart is composed of four chambers: two atria and two ventricles. As blood enters the right atrium from the large veins, passive flow continues into the right ventricle. The right atrium then contracts, forcefully ejecting the remaining 25% of this blood into the right ventricle. After a delay, this right ventricular blood flow is directed into the pulmonary arteries. A progressive reduction in vessel size results in a capillary meshwork intimately in contact with the alveoli whereby the gas exchange mechanisms function. Pulmonary venous blood, now oxygenated and devoid of carbon dioxide, enters the left atrium. This blood is pumped to the left ventricle, and into the systemic circulation where the cycle is continuously repeated.

Cardiac muscle has some similarities to skeletal muscles, but also some very significant differences as well. Cardiac muscle is arranged in a striated latticework with actin and myosin filaments, which lie adjacent to one another and contract in the same manner as skeletal muscle. However, cell membranes separate these fibers yet allow ionic diffusion between these membranes or *intercalated disks*. Thus during a chemical depolarization resulting in an action potential, unimpeded progression of this electrical current flows with minimal resistance throughout the heart. The *intercalated disks* allow for the heart to actually act as two separate systems. The two atria are electrically excited as a unit, as are the ventricles. The anatomical division of atria and ventricles by nonconducting fibrous tissue does not allow conduction to occur between the atrial and muscle in an unorganized manner. A very specialized conduction system ensures that atria and ventricles are depolarized in a progressive manner.

The atrioventricular valves close during ventricular contraction (systole) preventing the backflow of blood into the atria. The tricuspid valve lies between the right atrium and right ventricle; the mitral valve is located between the left atrium and left ventricle. As blood is ejected out of the right and left ventricles, the semilunar valves open; the pulmonary and aortic valves, respectively, then close during cardiac relaxation (diastole) to prevent blood from returning from the pulmonary and systemic circulation. Note that the first arterial branches off the aorta are the coronary arteries.

The specialized conducting system of the heart that produces a progressive, rhythmical contraction of atria and ventricles has several components. The sinus node provides the genesis for cardiac depolarization. This specialized cardiac muscle is located in the right atrium just below and lateral to the superior vena caval ostium. This strip of tissue, ~ 15 mm long, connects directly to the atrial musculature. Generation of action potentials in the sinus node progresses directly to the entire atria causing a unified contraction of all muscle fibers at once. The resting membrane potential of the sinus node fibers is ca. −60 mV compared with the ca. −90 mV for cardiac muscle. This difference in the sinus node electronegativity is due to the fact that sodium ions with their positive charge progressively “leak” intracellularly. A progressive rise in threshold voltage occurs until ca. −40 mV; opening of the rapid sodium channels at this point then produces the initial cardiac depolarization. The sustained contraction of the cardiac muscles is due to the secondary influx of calcium ions, followed by the influx of potassium ions, which exchange with the outward diffusion of the sodium ions. This last ion counterexchange of potassium for sodium limits the induced hyperpolarization of the cell allowing repolarization. This phenomenon of “leaky” sodium channels produces the rhythmic excitation, which initiates the cardiac cycle. The rate of this sinus node depolarization is controlled by the autonomic nervous system through the interaction of the para-sympathetic (acetylcholine) and sympathetic (norepinephrine) fibers. Generally, the length of time for this activation is on the order of 10 ms. Drugs utilized in ACLS, such as atropine and epinephrine, affect the firing interval of the sinus node.



Figure 4. Rhythmical sinus node action potential compared with ventricular muscle fiber. Reprinted from Textbook of Medical Physiology, 10th ed., Guyton and Hall, p. 108, 2000, with permission from Elsevier Science.

Once the atrial muscle fibers are activated, the action potentials cause a generalized contraction of all of these fibers at once, again due to the unique anatomy of the cardiac musculature. Activation of the left atrium occurs through the specialized fibers termed the “anterior interatrial band”. The anterior, middle, and posterior internodal pathways transmits the pacemaker impulses to the atrioventricular node in ~ 0.03 s. The AV node is essentially a junction box that has two unique features; a delay in the pacemaker action potential occurs here, which affords a delay in ventricular contraction so that the blood is allowed to empty from the atria to both ventricles and normally action potentials can only travel in one direction. This atrioventricular node is positioned in the right atrial posterior wall just behind the tricuspid valve. The delay in the ventricular depolarizing impulse is ~0.13 s.

The final pathway for the activation of the ventricles occurs through the Purkinje fibers, which terminate in the left and right bundle branches. These branches run in the ventricular septum separating the right and left ventricle and then terminate into progressively smaller branches throughout the ventricular muscle. The Purkinje fibers act in contradistinction to the AV node; action potentials are transmitted at a velocity 100-fold allowing rapid excitation and contraction of both ventricles. Transit through the Purkinje fibers is only ~0.03 s with the same approximate time necessary for complete ventricular muscle activation.

The electrical activity described in Fig. 5 can be measured at the skin such that electrical potentials are recorded as the ECG. A normal ECG consists of several



Figure 5. A normal electrocardiogram (ECG) cycle with wave segments and intervals. Reprinted from Anesthesiology, 5th Edition, Hillel and Thys: Electrophysiology, p. 1232, 2000, by permission from Elsevier Science.

waves of depolarization and repolarization. The P wave is produced from the summed action potentials generated during atrial depolarization. It is upright and, after returning to baseline, a pause is observed reflecting the progressive depolarization through the AV node. This P–R interval (actually the P–Q interval, but often the Q-wave is not visualized) begins at the initiation of the P wave and ends at the beginning of the QRS complex. The normal duration of the P–R interval is $\sim$0.12–0.21 s or three to five of the small squares on the ECG graph paper. During the P–R interval atrial depolarization occurs as well as the electrical activity generated in the AV node. The QRS complex, which consists of a Q wave, R wave, and S wave, represents the electrical activity causing ventricular depolarization. The Q wave is seen as a negative deflection from the baseline, which is followed by the large positively deflected R wave. The S wave follows the R wave and, like the Q wave, has a negative deflection. Often the Q wave and S wave may not be observed in the complex. The normal QRS duration is usually no $>$0.10 s or 2.5 of the small ECG squares. The S–T segment begins at the end of the S wave (commonly termed the "J point") and ends at the onset of the T wave. This interval is usually isoelectric, but can have a normal variance of ca. -0.5 to $+2.0$ in the precordial leads (see below). The normal duration is $<$0.12 s and $\sim$2.5 ECG squares. The T wave is a repolarization wave and reflects potentials generated with ventricular recovery. This wave usually has a positive deflection of $\sim$0.5 mV, but often is not observed because of decreased amplitude. The T wave represents a continuum of absolute to a relative refractory period of ventricular depolarization. It is important to note that the electrical activity observed in the electrocardiogram represents electrical activation of the atrial and ventricular muscles and not the actual contractions themselves. A standardized method for recording ECGs consists of graph paper upon that positivity is reflected with upward deflections and negativity, downward deflections. Ten small divisions represent 1 mV. The large vertical lines represent 0.20 s with the smallest intervals representing 0.04 s. These voltages recorded at the skin are very small relative to the actual potentials of $\sim$110 mV at the heart. Proximity of the recording electrodes as well as angular direction from the heart then will affect the size and shape of the ECG, respectively.

The standard electrocardiogram utilizes 12 leads (electrodes) to view the electrical activity of the heart. Six standard limb leads are combined with six chest (precordial) leads. Initial resuscitation events that require dysrhythmia interpretation usually view the bipolar leads I, II, III. These leads utilize two electrodes, one positive and one negative, to monitor the heart and record potential differences. Electrodes are applied through an adherent conductive gel to the left shoulder, right shoulder and left leg essentially forming a triangle (Einthoven's triangle, Fig. 6). The ground lead is usually placed on the right leg. Lines that bisect the sides of the triangle have their origin at the heart, the center of the triangle, which is the zero axis of each side. In lead I, the left shoulder is connected to the positive electrode and the right shoulder electrode is negative; the recording is the potential difference between the left shoulder and right shoulder. In lead II, which is the most common limb lead to be monitored, the negative electrode is placed on the right shoulder and the positive terminal to the left leg. Depolarization in the heart follows this same electrical vector as lead II and thus optimizes P wave height and shape as well as QRS morphology. Lead III places the positive terminal on the left leg and the negative terminal on the left arm. These three leads are very similar to one another in that the P, Q, and T waves are positive. They are excellent for dysrhythmia interpretation; since electrical activity from atria to ventricles is displayed, waveform and time related changes are very apparent, both to the diagnostician and computer (such as in an automatic external defibrillator).

CARDIAC ARREST DYSRHYTHMIAS

The previous section presented information relevant to understanding and interpreting the normal ECG. This



Figure 6. Einthoven's triangle.



Figure 7. The fatal rhythm of ventricular fibrillation.

primer of basic electrocardiography will enable the reader to now have some ability to differentiate the lethal rhythms that cardiopulmonary resuscitation demands for optimizing treatment.

The fatal dysrhythmia of ventricular fibrillation (Fig. 7) is a common endpoint in cardiac arrest. There are no QRS complexes, P waves or T waves that are identifiable. Scientific evidence over the years has conclusively established that only early defibrillation has any hope of restoring a normal sinus rhythm to the heart and subsequent survival. The fibrillating heart has no ability to eject blood since there is no coordination of heart muscle and no progressive flow of blood from atria to ventricles to systemic circulation. Cardiac depolarization and repolarization within the ventricular muscle occurs in a chaotic manner; ventricular muscle is activated in an unorganized fashion. This electrical activity sustains a vicious cycle of reexcitation, never allowing the return of normal cardiac function. The ventricles neither relax nor contract and in this ventricular fibrillating state consume massive amount of energy. Since there is no ejection of blood, unconsciousness from lack of cerebral blood flow occurs within seconds and death ensues from hypoxia.

After a normal cardiac sequence there is a refractory period (as mentioned previously with the beginning of the T wave, which is at the end of the cardiac cycle), whereby this cardiac impulse cannot reexcite the heart until a new electrical stimulus is generated from the sinoatrial node. However, the underlying etiology of ventricular fibrillation appears to be due to electrical reentry or "circus movements", where the normal termination of depolarization does not occur. These abnormal electrical pathways may be generated in several ways: a shortened refractory period, decreased depolarization velocities, or increased distance for the normal electrical impulse to travel. Recall that the progression of depolarization takes place only in one direction and essentially travels almost in a circle with excitation of the ventricles. If this normal impulse reaches cardiac muscle that has already been depolarized, the refractory time will not allow another depolarization. Stimulation of cardiac muscle will not occur until the entire myocardium is ready to be energized as one unit. Suppose that one of the three abnormal conditions were present; any ventricular muscle that was not refractory could be stimulated to contract in an unorganized manner. In a clinical setting, many individuals have hypertension and develop enlarged hearts. A large ventricular muscle mass would create an increased distance for the normal electrical impulse to follow, thus creating the potential for a "circus movement" to initiate reexcitation of muscle fiber. Rates of depolarization from the sinoatrial node through the AV node may result from blockade of this specialized system from a variety of causes. Electrolyte imbalance, as well as coronary artery disease, are common factors in inducing conduction block. Alterations in the sympathetic nervous system as well as drugs may act in sensitizing the heart, allowing more rapid conduction of impulses and increased susceptibility to fibrillation. Once the ventricular muscle begins this chaotic activity, a chain reaction phenomena begins: conduction velocities throughout the heart decrease, allowing even more time for reentrant depolarizations to occur and the actual muscle refractory time is decreased, increasing the opportunity for these impulses to propagate this dysrhythmia.

The cornerstone of cardiopulmonary resuscitation is early defibrillation. The previous American Heart Association mnemonic of CPR, the "ABCs", which consisted of Airway, Breathing, Circulation, has been changed to "ABCDs" to include defibrillation. After one shock, 60% of all victims succumbing to ventricular fibrillation will survive; after two shocks, 80% survive; after three shocks, 90% will be successfully resuscitated (48). Electrical countershock utilizing high-voltage current can inhibit defibrillation by instantaneously depolarizing all cardiac muscle tissue. The myocardium then is totally refractory to any reentry currents. The electrocardiogram will typically record asystole, or no evidence of electrical activity, from the heart for several seconds. Resumption of the normal cardiac pacemaker will resume, and organized contraction should reoccur. Time is of the essence, since as a heart continues in fibrillation, the rapid utilization of high-energy phosphates depletes this "fuel" for resumption of normal cardiac activity. It is obvious that delay in defibrillation induces a state whereby even successful technique in countershock will be not be able to sustain a normal cardiac rhythm due to the lack of substrate for myocardial energy consumption. The underlying philosophy of cardiopulmonary resuscitation now is early access to defibrillation for the victim.

Pulseless ventricular tachycardia (Fig. 8) is the other malignant dysrhythmia that requires immediate external countershock. Unlike ventricular fibrillation, the electrocardiogram displays a rapid regular rhythm with a widened and abnormal appearing QRS complex. Usually,



Figure 8. Ventricular tachycardia.

the rate is very rapid, with a range of ~ 100–250 beats/min, contrasted to the normal sinus rhythm rate of 60–100 beats/min. Three or more of these bizarre appearing complexes define this dysrhythmia. Usually, the P wave and T wave are obscured and thus the P–R interval cannot be measured. This rapid rate does not allow adequate filling of the ventricles, and causes a ventricular lack synchrony with the atria; the result is dramatic loss of cardiac output and blood pressure. Since there is no effective cardiac output and these dysrhythmias degenerate into ventricular fibrillation, external countershock is mandated. The sinus node functions normally in VT, whereby the atria are properly depolarized. There can be a retrograde depolarization of the atria from the ventricles in some instances of ventricular tachycardia and there will be a definite P wave associated with the abnormal QRS complex. Usually, these retrograde P waves have a negative (downsloping) peak. Another unusual feature of this dysrhythmia is that at certain time intervals the atria may be able to initiate an impulse completely through the AV node and Purkinje system at the instant where the ventricular-initiated depolarizations leave the conduction system vulnerable. The result is termed a "capture beat". If this normally conducted impulse occurs at the same time that a ventricular depolarization is generated, a fusion beat is generated, which appears as a cross between the normal- and ventricular-originated complex. This dysrhythmia may either be paroxysmal or sustained and the shape of these QRS waves either monomorphic or polymorphic. Degeneration into ventricular fibrillation is a common course; for this reason countershock is required. The mechanism for pulseless ventricular tachycardia is hypothesized to be a reenty depolarizing current due to delayed conduction. The site of occurrence for this aberrant mechanism would localize to the Purkinje system and ventricles.

An unusual form of ventricular tachycardia (Fig. 9) is termed "Torsade de Pointes" or twisting of points (49). Notice the QRS morphology viewing the rhythm strip from left to right. On first appearance, this dysrhythmia appears to be ventricular tachycardia. The QRS complexes are wide (versus the normal narrow QRS shape), but constantly changing in shape and amplitude yet there appears to be a rhythmic oscillation about the baseline. The depolarization wave appears to twist around the central axis or helix. This dysrhythmia is triggered by electrical potentials that either occur before or after the normal spontaneous depolarization of the heart or is associated with a prolonged QT interval. Should this dysrhythmia be associated with no evidence of effective blood flow, immediate countershock would be the treatment of choice after the "ABCs" of CPR have been accomplished. However, if Torsade de Pointes is misdiagnosed as ventricular tachycardia and a pulse is present, the potential exists for the wrong treatment and lethal results. This dysrhythmia usually occurs when there is an underlying prolongation of the QT interval. Since many of the antiarrhythmic agents will prolong this interval, it should be apparent that selection of one of these drugs to terminate a misdiagnosed ventricular fibrillation when Torsade is present has the potential to produce a nontreatable dysrhythmia. Antidepressants, antipsychotics, and electrolyte abnormalities (particularly hypokalemia and hypomagnesemia) will produce the underlying QT prolongation that serves as the catalyst for Torsade



Figure 9. Torsade de Pointes.



Figure 10. Asystole.

to appear (50). Strategies for treating this rhythm are to correct the factors providing the substrate for dysrhythmia; magnesium supplementation, and correction of all electrolyte abnormalities as well as what is termed "overdrive pacing" to externally pace the heart to rates of between 100 and 120 beats/min (51).

Asystole (Fig. 10) is the terminal arrhythmia that represents a dying heart. Observation of the above example shows the absence of electrical activity (flat line), but occasionally P waves, or what is termed "ventricular escape beats", may be present. Usually, the presence of asystole means death for the victim, so rescuers are taught to view this rhythm in more than one lead since fine ventricular fibrillation may actually be the abnormal rhythm rather than asystole. This distinction is extremely important since VF needs to be immediately treated with defibrillation, whereas in asystole the possible causes need to be identified, and defibrillation is contraindicated for resuscitation. Why not shock the heart that is in asystole? The answer lies in the fact that rarely a victim may experience high levels of parasympathetic nerve input to the heart. This parasympathetic stimulation can produce complete cessation of the atrial and ventricular pacemaker. Defibrillation also produces an intense parasympathetic nerve discharge, which, in this specific situation could terminate any chances for the heart to recover normal pacing function (52). Evidence substantiates that defibrillation for asystole does not improve the survival rates in out-of-hospital arrest scenarios (53). There have been rare occasions reported in the literature where victims have positively responded to transcutaneous cardiac pacing for which many defibrillators now have this capability. The heart is stimulated externally to produce an effective cardiac output. The caveat is that this maneuver can only be effective if there are only several minutes of asystole. A specific situation that lends itself to transcutaneous pacing is the asystole that occurs after defibrillation. This witnessed arrhythmia occurs immediately after some countershock attempts and thus there can be a window of < 1 min for pacing to be initiated. There may be certain types of patients who also might respond to asystolic pacing, such as those with Stokes–Adams–Morgagni syndrome, where intermittent atrioventricular block produces asystole or the hypoxia initiated P wave asystole (54).

The last terminal rhythm group that occurs frequently in resuscitation efforts is pulseless electrical activity (PEA). Observe the rhythm strip in Fig. 11; this is an example of a normal sinus rhythm. At first, one would question why a normal ECG would be included in emergency cardiac care and treatment. The key to understanding pulseless electrical activity is that the rhythm may appear to be entirely normal; however, upon further physical assessment of the victim, no pulse is detectable. Historically, cardiologists have referred to this state as electromechanical dissociation, where the normal atrial and ventricular depolarization progresses without any myocardial muscle contraction. Recent scientific evidence utilizing echocardiography and invasive pressure monitoring catheters have found that minute myofibril contractions do occur with depolarization; however, there is not enough effective projectile pressure generated to produce any external signs of perfusion, thus the term pseudoelectromechanical dissociation has been proposed (55,56).



Figure 11. Pulseless electrical activity.

Other rhythms are also included in this group; ventricular escape rhythms, postdefibrillation rhythms, and bradyasystolic rhythms have different QRS morphology than the normal sinus rhythm; however, the same underlying problem of no pulse and no organ perfusion is the defining issue. The key to resuscitation of the victim in PEA is to quickly recognize and treat the underlying problem that has created this scenario. Since there is no perfusing rhythm it should be obvious that the "ABC" basics must be immediately made available to the victim while the differential diagnosis prioritized to the specific situation is reviewed.

There have been a number of mnemonic memory aids suggested to recall the most common conditions provoking pulseless electrical activity. Two common lists are the '5 Hs' and '5Ts' and the "MATCH-HHH-ED" (57,58).

Hypovolemia; Hypoxia; Hydrogen ion excess (acidosis).
Hyper or Hypokalemia (excess or loss of potassium ions).
Hypothermia; "Tablets" (referring to medications or drug overdose).
Tamponade (blood trapped around the heart chamber).
Tension pneumothorax (trapped air causing lung overinflation and resultant loss of cardiac perfusion).
Thrombosis (secondary to myocardial infarction) and Thrombosis (secondary to pulmonary embolism).
M—Myocardial injury or infarction
A—Acidosis
T—Tension pneumothorax
C—Cardiac tamponade
H—Hypothermia
H—Hypo or Hyperkalemia
H—Hypoxia
H—Hypovolemia
E—Embolism
D—Drug overdose or chemical toxins.

The most common cause of PEA is hypovolemia: inadequate intravascular fluid volume. These fluid volume losses may be real, such as in acute hemorrhage or relative, wherein the capacitance vessels (veins) vasodilate, leaving inadequate vascular blood and fluids to compensate. A classic evolution to pulseless electrical activity would ensue from hemorrhage, producing normal electrical complexes, with progression to a tachycardia where the heart rate increases to compensate for pressure loss. Peak pressure for each cardiac ejection of blood (systolic pressure) would decrease, but increased constriction of the circulatory vessels would increase (diastolic pressure). As the blood pressure continues to drop to extremely low levels secondary to the hemorrhage, the sinus tachycardia continues. At this point, the astute clinician would consider this cause for PEA and immediately give the victim intravascular fluid followed by blood products to stabilize the victim. It is obvious that the definitive treatment in this case would be surgery; the goal of the resuscitative response is to maintain perfusion and oxygen delivery to the tissues. Time again is critical since without effective cardiac flow, perfusion of the myocardium is nonexistent and hypoxia develops quickly. Progression toward ventricular fibrillation, asystole, and death are the end result. An example of relative hypovolemia is septic shock. In this situation, a bacterial infection produces endotoxins, which causes the resistance vessels to dilate. There is normal circulating blood volume, but increased vessel capacitance resulting in a progressive blood pressure drop. Due to the underlying pathology, the vessels are unable to adequately constrict and the evolution to cardiac dysfunction secondary to poor or absent coronary perfusion occurs, eventually producing the terminal rhythms of ventricular fibrillation and asystole. Treatment in this scenario consists of increasing the fluid volume as well as to utilize drugs that act to constrict the blood vessels.

Each one of the other conditions mentioned above that can cause pulseless electrical activity also has an immediate treatment response, after the appropriate steps in basic life support have been met. Thus while the victim is being oxygenated and ventilated, and perfusion accomplished through chest compressions, the clinician is rapidly focusing upon the conditions that would be most causative and then initiating treatment. In hypoxia, treatment consists of supplemental oxygen and adequate mechanical ventilation of the lungs. In cardiac tamponade or tension pneumothorax, needle decompression of the pericardial sac or lung is the required emergency management. Electrolyte imbalances require immediate infusion or neutralization of the ion. A preexisting acidosis might require exogenous sodium bicarbonate. An acute myocardial infarction (heart attack) causing PEA would need supplemental oxygen, pain management, fluid resuscitation and immediate infusion of coronary artery thrombolytics. Pulseless electrical activity is always associated with an underlying clinical condition that, when identified and treated early, has the potential to be reversed and thus effective perfusion restored to the victim.

MECHANISMS FOR COMMUNITY CPR

The American Heart Association is a volunteer organization that has as its goal the reduction of mortality and morbidity secondary to cardiovascular and cerebrovascular disease. The AHA established a scientific mission in 1963 to evaluate and promulgate standards of CPR. In 1971, the Emergency Cardiac Care Committee was founded. Since the first conference on CPR in 1966 sponsored by the National Academy of Sciences and the National Research Council, guidelines for CPR have been based upon the available scientific evidence. Since this time there have been six conferences, the last in 2000 consisting of resuscitation experts worldwide. All aspects of CPR have been evaluated, including the actual access for emergency care in the community, education of the layperson, and delivery of basic CPR and ACLS. "Emergency Cardiovascular Care" is the term used to describe the organized response to life-threatening emergencies for the adult, pediatric, and neonatal victim. Other ECC provisions for care include educating the layperson to recognize the signs and symptoms of myocardial ischemia and infarction, stroke, activation of the EMS system (911) as well as early implementation of basic life support, defibrillation, and advanced cardiac life support with immediate victim transfer to the hospital. The goal of ECC is to save lives and this also includes educating the public regarding cardiovascular risk and how to maintain healthy lifestyles. The cornerstone of all emergency care is the layperson. Effective emergency care can only occur with public awareness of these events as well as prompt administration of CPR and use of the automatic external defibrillator. Once the EMS system has become involved with the victim, progression of care is dictated by a physician and ACLS protocol. The optimization of oxygenation and ventilation through supplemental oxygen and adjunctive respiratory devices, electrocardiographic monitoring with rhythm assessment and treatment, establishment of intravenous access for appropriate medications and post-resuscitation management are all elements of ACLS.

The American Heart Association "Chain of Survival" is a crucial concept to be understood in the context of CPR and is taught to the layperson in the basic lifesaving courses. There are four critical links in this chain that require specific actions on the part of the public. In the event of an emergency the first link involves activating the emergency medical services system. Obviously, the layperson must be able to recognize that a true emergency exists, and this underscores the efforts by the community organizations to educate the public regarding signs and symptoms of heart attack, stroke, and loss of the airway. The key is unresponsiveness; anyone found unconscious should initiate the first link by way of immediately involving EMS through calling 911. Once an emergency medical dispatcher is contacted, immediate aid in the form of paramedicals is sent to the scene. The dispatcher is also taught how to aid the layperson in how to provide basic CPR, which is the second link in the chain. Only until the EMS personnel arrive and begin managing care for the victim does the dispatcher terminate the call. In some communities, "enhanced 911" is available in which a computer will provide the dispatcher with the address from which the call is made in case communication is difficult or there is a premature telephone disconnection. This second link of CPR is the most critical phase in the Chain of Survival since the rescuer provides oxygen to the victim and, if needed, circulates this oxygen by chest compressions to the brain, heart, and vital organs. If bystander CPR is initiated within 4 min after a victim collapses, the odds of survival, after discharge from the hospital, are doubled (59).

The third link in the chain is early defibrillation, either by the public use of the automated external defibrillator or by the paramedic on the scene. Early access to defibrillation for the victim of cardiac arrest will significantly improve the chance for survival: each minute of delay for defibrillation for the victim in ventricular fibrillation decreases the chance of survival by 7–10%, and if defibrillation is provided within the first 5 min, chance of survival is 50% (60). Unfortunately, if >12 min of delay from collapse to initial resuscitation is encountered, the survival rate only ranges between 2 and 5%, and intact neurological function is compromised (61).

Recently, gambling casinos have implemented access for defibrillators and for victims who received a shock within 3 min had a 74% survival rate since a low response time of between 2 and 3 min was documented (62). Since time to defibrillation is so critical, automatic external defibrillators have been made much more accessible to the public. These devices can now be found in large gathering places such as stadiums, golf courses, airports and airplanes, shopping malls, large grocery stores, and other facilities where people in great numbers tend to congregate. So important is the early access to defibrillation that a great majority of states have enacted legislation to encourage use of these devices. The Cardiac Arrest Survival Act provides legal immunity for the layperson and the public business or corporate entity that uses or provides an automatic external defibrillator for resuscitation, which is essentially an expansion of the "Good Samaritan" type legislation. This immunity should encourage active participation by the public for involvement in victim resuscitation. Public access defibrillation has been described as the second most significant advance, compared to CPR, in the pre-hospital rescue scenario.

The final fourth link in the Chain of Survival is early ACLS by highly trained paramedical personnel. Emergency medical technicians expand (EMTs) incorporate basic CPR with interpreting cardiac dysrhythymias and, if required, defibrillation. Emergency medical technicians expand the immediate life-saving care by providing supplemental oxygen, intubation and control of the airway, gaining intravenous access and administering pharmacologic medications while in contact with a physican. This process occurs at the scene, and once the victim is stabilized, advanced cardiac life support continues through transport to the hospital emergency room. The most significant impact of early ACLS is to prevent the catastrophic progression of lack of oxygenation and cardiac arrest rather than to treat the terminal conditions inherent in this process.

The rescuer, whether a lay person of EMT, who begins CPR in the "field" must continue BLS (63) until one of the following events occurs:

1. The victim begins to show signs of spontaneous ventilation and perfusion.
2. Care is transferred to another qualified BLS responder, EMT, or ALS medical providers; or to a physician who makes the determination that resuscitation should be terminated.
3. The rescuer cannot continue resuscitation due to exhaustion or to hazards that may jeopardize the rescuer's life or the lives of others in the team.
4. An authentic no-CPR order is presented to the responders.

The determination to discontinue resuscitation depends on a stepwise evaluation of the efforts made during BLS and ACLS. A review of the process should ensure that each step in the resuscitation has been carried out in a flawless manner. Successful ventilation and intubation, intravenous access and the administration of appropriate medications as well as countershock should be achieved according to ACLS protocol. Electrocardiography evaluation should render a conclusion of no reversibility for the underlying agonal rhythm. Recently, the determination of end-tidal carbon dioxide has been advocated as a potential predictor of death (64). During resuscitation end-tidal carbon dioxide reflects the adequacy of cardiac output generated during chest compressions. This study suggested that after standard ACLS protocols had been followed for 20 min, a persistent end-tidal carbon dioxide level of 10 mmHg or less predicted nonsurvival in the victim with electrical activity, but without a pulse.

CARDIOVASCULAR DISEASE

Every year ~500,000 people are hospitalized for treatment of chest pain secondary to cardiac origin and 1.5 million victims will experienced a heart attack (65,66).

Some 500,000 people a year who have a myocardial infarction (heart attack) will die from this insult and ~225,000 of these deaths will occur within the first hour after symptoms and prior to reaching a hospital (67,68). In 17% of the victims, chest pain is the first and only symptom (67). It is again significant that time to intervention for the patient experiencing a myocardial infarction is crucial to survival; treatment must be undertaken within the first several hours after the symptoms occur (70,71). Early treatment underscores the necessity for rapid recognition of a cardiac event, followed by rapid CPR, defibrillation, ACLS and transport to the hospital.

The most common cause of a heart attack is ischemic atherosclerotic disease. The essential pathophysiology is the narrowing of the coronary artery lumens by deposits of fat-substrate such as cholesterol and lipids, which eventually retain calcium. The actual process of the accumulation of these plaques occurs very slowly, but has been demonstrated to begin at an early age. This same process affects the cerebral arteries as well and is the etiology for an ischemic stroke. As the coronary artery lumen narrows, a dynamic situation develops where blood flow and thus oxygen supply will not meet with increased demand for oxygen by the cardiac muscle fibers. Typically the coronary artery will have a circumference reduction of 70% for symptoms to occur. This condition of ischemia will produce a characteristic constellation of transient symptoms, referred to as angina pectoris. Chest pain is the most common sign of an acute cardiac ischemic event, occurring in 70–80% of the population (72). This pain appears to have several different components: transmission of dull, poorly localized pain occurs through the sympathetic visceral nerve fibers; a somatic pain generator produces the sharp and dermatomal aspects; and psychological input gives rise to the sense of impending doom (73,74). This cerebral input to the event may significantly exacerbate the ischemia since activation of sympathetic nervous system will increase heart rate and contractile force, further tipping the scale toward more energy consumption and thus oxygen demand.

Paradoxically, the majority of episodes of an acute coronary event (angina and or infarction) occur during periods of rest or mild to moderate exercise; profound physical exercise is associated with the minority of events (75). The victim will experience an intense, dull, crushing pressure sensation in the chest, most commonly behind the breastbone (retrosternally) and/or pain in the back, arms, shoulders, or mandible. Often nausea, vomiting, sweating, and shortness of breath (dyspnea) may accompany the pain. There appears to be a circadian rhythm regarding the occurrence of angina and the progression to infarction. Two daily peaks in incidence have been noted with the first pattern beginning from awakening to about noon, and the second peak occurring in the early evening (76,77). There are atypical presentations to unstable angina or myocardial infarction that will delay access for the victim. This subset of the population may have only vague, mild discomfort, which can be confused with a myriad of medical complaints. Diabetics, women, and the elderly all have a higher incidence of nonclassical presentations for cardiovascular ischemia (78,79). Diabetics are prone to neurological dysfunction and thus may have no sensation of the pain associated with angina. A retrospective review found that 30% of first heart attacks in men and 50% of first infarctions in women did not present with classical signs and symptoms and were clinically not recognized (80). When oxygen demand decreases, such as when the physical activity is discontinued, the decreased oxygen supply secondary to the narrowed lumen will be adequate and the symptoms will usually resolve. Progression of the disease, however, results in a much more severe mechanism for ischemia. The plaque is predisposed to rupture and when this occurs, activation of the coagulation system releases mediators that form a clot or thrombus over the plaque, which can further limit blood flow, or catastrophically, stop all blood flow completely. If the partial occlusion from the thrombus is severe enough, what is termed "unstable angina" develops. Though there have been many definitions of unstable angina, the main characteristic is that this type of angina occurs at rest and is progressive or prolonged in nature. Nocturnal angina, again with the victim at rest, would be classified as unstable angina. The heart is consuming the least amount of oxygen yet there is a lack of supply due to lumen reduction from the plaque. Clot enlargement provides the mechanism for dislodgement of particles or emboli, which then travel downstream, lodging in the microvasculature and these individuals are at a very high risk for progression to irreversible cardiac damage.

Complete occlusion of the coronary artery results in a myocardial infarction. Deprivation of oxygen results in the death of cardiac myofibrils and induces irritability in the cardiac conduction system, setting the stage for the initiation of lethal dysrhythmias such as ventricular fibrillation. Where and how severe the damage is to the heart depends on what coronary artery has the occlusion. If the left main coronary artery has an acute total obstruction, mortality is very high since no blood flow will occur through the two distal branches, the left anterior descending and circumflex arteries. Blood flow will be blocked to the entire left ventricle, the septum between the left and right ventricle, and the bundle branches. Even if the patient receives timely CPR, and clot lysis, a significant amount of heart may be destroyed resulting in scar tissue and a drastic reduction in blood flow, resulting in what is termed "congestive heart failure". If the thrombus were to lodge and occlude the right coronary artery, hypoxia would occur in the AV node, right ventricle, and in the majority of individuals, the posterior and inferior aspect of the left ventricle.

The continuum of acute cardiac injury, from unstable angina to myocardial infarction typically presents with characteristic electrocardiographic signs. Recall what the normal elements are to the ECG. During episodes of unstable angina where cardiac muscle demand for oxygen exceeds supply, ischemic changes to the ECG are seen as S–T segment depression, defined as $\geq$ to a 1 mm change from baseline on the standard graphpaper or changes in the T waves. When this S–T segment depression is downsloping, this is a sensitive sign of ischemia. The T waves may appear inverted or enlarged and symmetrical. When actual occlusion of the artery occurs, myocardial injury to tissues ensues and both muscle contraction and conduction are decreased from normal. The ECG change characteristic of injury is S–T segment elevation in contradistinction to changes of ischemia. When there is $\geq$1 mm above baseline for the S–T segment elevation, significant cardiac injury has occurred. This group of patients who exhibit S–T segment elevation on the ECG in two contiguous leads may be salvaged through reperfusion therapy. Restoration of blood flow and the course of injury is very dependent on early administration of thrombolytics or percutaneous transluminal coronary angioplasty (PTCA). The greatest improvement in mortality and morbidity occurs when reperfusion therapy is administered within the first 3 h after onset of symptoms (81,82). Conjoined with early CPR and defibrillaton, reperfusion therapy stands as one of the greatest advances in acute coronary syndromes. Current regimens include the fibrinolytics streptokinase and alteplase, as well as numerous other similar agents that act by inducing fibrinolysis through interactions with tissue plasminogen activator. The PTCA is a mechanical procedure whereby a catheter is guided through the coronary arteries into the area of stenosis, and then a balloon is inflated to expand the vessel. This procedure is restrictive in that only specialized centers have the capability to utilize this regimen, although it may be superior to thrombolytics.

Myocardial infarction defines the actual death of cardiac tissue. This is the end result of the process of ischemia with myocardial cell injury. The infarcted tissue area, again representative for the specific coronary artery occluded, will exhibit characteristics associated with loss of cellular life. Intracellular contents are released after loss of cell wall integrity. Some of these enzymes, such as creatine phosphokinase and the troponins, can be measured in the bloodstream to confirm infarction. The classic ECG changes for myocardial infarction are the presence of abnormal Q is waves. When a Q wave is or $\geq$1 mm in width and the height is $>$25% of the R wave height, the diagnosis can be made. An abnormal Q wave reveals the existence of dead cardiac tissue, but does not reveal anything about when the infarction happened. The assumption can be made for a recent infarction if the Q wave is associated with S–T segment changes and/or T wave changes. A non-Q wave infarction can also occur: There is myocardial cell wall dissolution with the release of cardiac enzymes, but only accompanied by S–T segment changes or T wave abnormalities. There is a lower mortality rate for non-Q wave heart attacks, but, unfortunately, an increased incidence of future reinfarction or death (83,84). Fibrinolytics are contraindicated in patients with non-Q wave infarction since the clot occlusion may be paradoxically aggravated by release of thrombin, which further activates platelets (85).

Prehospital intervention for the victim suffering an acute cardiac event is based upon the “Chain of Survival”. Once the signs and symptoms of a heart attack are recognized, early access to the emergency medical system is imperative. A common problem encountered is denial either from the victim or the rescuer, which impedes response time. Once the EMS personnel arrive at the scene a pertinent medical history is obtained and physical examination completed. A complete 12 lead ECG is obtained and then transmitted to the physician who is dictating care. Oxygen is the first line treatment for anyone complaining of chest pain. It should be recalled that supplemental oxygen substantially increases the oxygen tension in the blood and significantly improves tissue oxygenation. A critical blood flow restriction may be palliated by improving oxygen supply in this manner. The administration of the drug nitroglycerin is quickly administered for the victim symptomatic for angina in conjunction with oxygen. Nitroglycerin is delivered sublingually for rapid absorption into the bloodstream. Nitroglycerin is effective in relieving the symptoms of angina in several ways: relaxation of venous smooth muscle occurs due to binding of specific vascular receptors. As relaxation of the venous capacitance vessels occurs, venous return to the heart is decreased, thereby relieving ventricular wall tension, which ultimately decreases ventricular work and oxygen consumption. The nitrates also dilate the large coronary arteries as well as increasing blood flow through collateral vessels, which improves ischemic blood flow (86,87). Aspirin is the third drug that should be administered immediately by either the BLS provider or EMT when symptoms suggest a cardiac event (and the victim is not allergic to aspirin). A regular tablet of aspirin (325 mg), when ingested, will cause an immediate anticlotting mechanism by way of platelet inhibition. There is evidence that suggests aspirin decreases coronary artery reocclusion and future coronary symptoms, with reduction of death and furthermore, the effects of aspirin appear to be additive to fibrinolyis (88). The fourth drug that is administered during episodes of chest pain secondary to unstable angina or myocardial infarction is morphine. Although morphine is a narcotic analgesic, it produces beneficial hemodynamic effects in addition to profound pain relief. Morphine causes decreased vascular tone in the venous capacitance vessels, thus reducing myocardial wall tension, much like nitroglycerin. The mechanism, however, is different in that the action appears to be mediated through central nervous system reductions in sympathetic tone (89). A convenient mnemonic has been utilized, “MONA”, for recall of these four immediate effective therapies for pre-hospital treatment of the acute coronary syndrome.

CEREBROVASCULAR DISEASE

There has been a concerted effort in the Emergency Cardiovascular Care system to improve pre-hospital recognition of the warning signs of stroke and provide rapid access to the Emergency Medical System. Public awareness of the issues regarding a "brain attack" has lagged relative to the exposure and education afforded cardiovascular disease. Stroke ranks third behind heart disease and cancer for morbity in the United States; 500,000 Americans a year suffer from a cerebrovascular accident and 125,000 of these victims will die (90). Until recently, stroke victims were only offered supportive and rehabilitative therapy for the complications experienced if they survived the initial insult. However, advances in fibrinolytic therapy, as in treatment of cardiovascular disease, dramatically improves outcome for the patient who has experienced an ischemic stroke (91). Fibrinolytic treatment reduces stroke disability and significantly improves quality of life after hospital discharge (92,93). The caveat is that the cerebrovascular accident must be recognized and treatment initiated in a timely manner; fibrinolytics need to be provided within 3 h after the onset of an ischemic stroke (94). Thus there is a narrow window of opportunity to limit cerebral damage, which underscores how important the role is for the public in providing immediate access to the EMS system for the victim.

The underlying cause for an ischemic stroke is comparable to the etiology for myocardial infarction. There is a disruption to cerebral blood flow due to the presence of an occlusive clot. The oxygen supply to the particular area of the brain supplied by the blocked artery does not meet the tissue demand and the same process of ischemia, injury, and cell death will occur. The thrombus, which occludes the vessel, is the end result of atherosclerotic changes to the artery. However, due to the unique anatomical positions of the cerebral arterial system, a blood clot formed elsewhere in the body can embolize to disrupt blood flow to the brain. Approximately 75–85% of all strokes are of this type, and defined as ischemic, and furthermore can be classified as to the arterial system that is affected. The two major arterial conduits to the brain are the carotid arteries and vertebrobasilar arteries, which affect the cerebral hemispheres or brain stem–cerebellum, respectively. Typically, a person who is at risk will develop what is termed "a transient ischemic attack" (TIA) prior to a full-blown stroke. Essentially, a TIA is a reversible mini-stroke that may affect specific brain function or eyesight and will last anywhere from minutes to hours (95). The TIA is a harbinger of a future "brain attack" much like unstable angina will forecast a heart attack. About 5% of those persons presenting with a TIA will end up with a stroke in 1 month; the risk will increase to $\sim 12\%$ after 1 year and an extra 5%/year thereafter (96). Fortunately, the symptoms from a TIA will bring the patient into the medical system for evaluation whereby treatment regimens clearly reduce risk for ischemic stroke. The surgical procedure of carotid endarterectomy in which the carotid artery plaque is removed has been proven very beneficial for patients that have had a recent TIA and a $>70\%$ stenosis of the carotid artery (97). In those individuals who are not operable candidates, aspirin and the specific platelet inhibitor types of drugs have been shown to be successful in preventing subsequent stroke in patients presenting with TIA (98).

The minority of acute strokes are due to hemorrhage of cerebral artery. The bleeding may occur in the subarachnoid space, which is in the superficial exterior aspect of the brain, or in the brain tissue itself, defined as an intracerebral hemorrhage. The common etiology to a subarachnoid hemorrhage is an aneurysm where the arterial wall weakens, and eventually a disruption occurs (99). In the case of a hemorrhage into the brain tissue itself, high blood pressure appears to be the major causative factor (100). While there are similar signs and symptoms in both types of stroke, there are also distinct differences in findings, which aids in the diagnosis. In general, the presentation for a subarachnoid hemorrhagic stroke is more severe with a very common complaint of an extremely painful headache, which tends to be global, and may have radiation of pain into the face or neck. This headache is often accompanied by mental status changes, nausea, vomiting, photophobia, or cardiac dysrhythmias. In a minority of patients, a prodromal episode of these symptoms may be caused by leakage of the aneurysm offering a warning sign (101). While the victim suffering from an intracerebral hemorrhage may also present with a severe headache, these patients tend to have a greater neurological insult with significantly depressed mental status function. The signs and symptoms of an ischemic versus a hemorrhagic stroke overlap and diagnosis may be difficult based upon the medical history and physical findings. Since radiological imaging offers the greatest aid in differentiating these two types of cerebrovascular accidents, time is very critical to clinch the diagnosis to offer the appropriate treatment. Fibrinolytics would obviously be a catastrophic therapy in the mistaken treatment of what appears to be an ischemic stroke when the etiology is a ruptured blood vessel that requires surgery.

The American Heart Association "Chain of Survival" that has been implemented and associated with cerebrovascular disease has been applied to the pre-hospital care of the stroke victim. Early recognition of a stroke and activation of the EMS system are paramount in initial therapy, which is often problematic, since, unlike a heart attack, stroke may be difficult to detect. While early defibrillation is not ordinarily indicated for the stroke victim, the possibility always exists that coincidental lethal dysrhythmias may be present during the initial presentation (102). The last link in the chain is early hospital care. The common theme regarding out-of-hospital management for cardiac or stroke victims is rapid entry for the victim into advanced life saving. The '7-D' mnemonic has been recommended as an aid for care in the stroke patient: Detection; Dispatch; Delivery: Door; Data; Decision; Drug (103). Early detection, with an accurate recall of the initial signs of a stroke are critical to care and must be accomplished by the immediate family member or layperson, with immediate access to "Dispatch", the EMS personnel. An important point to emphasize is that the majority of strokes occur at home (104). Paramedics who arrive at the scene must confirm a rapid, tentative diagnosis through focused medical history and physical examination, and then "Deliver" the patient rapidly to the hospital. Once the patient is through the Emergency Department "Door" the medical history and physical examination are further refined along with radiography (computerized tomography). A "Decision" is made regarding whether fibrinolytic therapy is indicated for an ischemic stroke and the "Drug" treatment is initiated. The drug therapy must be initiated within 3 h after the onset of an ischemic stroke.

The changes in mental status and/or sensorimotor function in a cerebrovascular accident may range from minor, almost unrecognizable changes, to loss of consciousness and seizures. A person may exhibit grades of confusion, with a progression to stupor or coma where the airway is obtunded and basic life support is required. Comprehension of language often occurs with inappropriate responses to simple questions. Physical manifestations are often present unilaterally. Paralysis in either the face, upper, or lower extremity may range from slight weakness to frank inability to exercise any muscular control. Since the face is always exposed, muscle weakness is exhibited by loss of tone and sagging of the muscles in facial expression. Difficulty writing (aphasia) or speaking (dysarthria) occurs due to loss of appropriate motor input from the brain. Loss of sensation is another common sign of a stroke (or a TIA). Visual disturbances, including blindness are much more obvious and usually involve only one eye. If the location of the ischemia is in the vertebrobasilar arterial system, centers of the brain controlling coordination are involved and signs such as gait disturbances (gait ataxia) are common. The dilemma of pre-hospital rapid neurological assessment to evaluate the possible stroke victim when the presentation is varied has been improved by several instruments. The Cincinnati Pre-hospital Stroke Scale (104) is very effective in identifying the stroke victim. Three physical findings are assessed: facial droop; arm drift; and speech. Abnormal features in any one category is very predictive for cerebrovascular accident. The Los Angeles Pre-hospital Stroke Screen also is extremely useful for assessment. Six criteria are first evaluated in the medical history: (1) age $>$ 45 years, (2) absent history of seizures or epilepsy, (3) no history of motor loss, (5) serum glucose not $<$ 60 g/dL nor $>$ 400 g/dL, and (6) asymmetry in any one of the three categories of facial musculature, grip strength, and arm strength. If all criteria are positive, there is a 97% chance of an acute stroke (105). These tests have streamlined the response time and have allowed the hospital emergency room to prepare for rapid definitive diagnosis.

THE "ABCs" OF ADULT CPR

The evolution of the current basics of life-support has resulted in a streamlined set of actions that has standardized the initial care for the victim, whether accomplished by a public bystander or emergency room physician. Assessment of the victim always precedes a physical maneuver on the part of the rescuer; constant appraisal of the effectiveness of CPR and the response of the victim is a core principle in American Heart Association Basic Life Support tactics. The initial steps of resuscitation are never bypassed; for example, if the airway is not established, the single rescuer would never start chest compressions, or begin intravenous access. The stepwise process in the algorithm ensures that an orderly process occurs in a situation where chaos and a high degree of emotional turmoil exist for the rescuer. Since there are some basic differences in how resuscitation is administered to the adult versus a child, anyone 8 years or older is considered an adult.

When one encounters a potential victim, the first assessment is to determine unresponsiveness. "Shake and shout" has been a common first action to determine that the victim is really unconscious (there no doubt has been a number of resuscitations initiated upon someone who was sleeping, assuming unconsciousness)! Once there is no doubt that a true emergency exists, the rescuer sends another member of the group to activate the EMS system by phoning 911 and to obtain an AED. If the rescuer is alone, he or she must leave the victim momentarily to call 911 and get the AED; these automated defibrillators have a standardized placement near a telephone. After accessing the EMS and obtaining a defibrillator, the rescuer places the victim in the supine position, and kneels at the head (the left side is suggested when utilizing an AED). The "ABCs" of CPR now are initiated.

A = Airway

The unconscious person has a generalized relaxation of all muscles and in the throat this causes the tongue to move in a posterior direction, occluding the airway. Since the tongue is attached to the mandible, manipulating the jaw and head will retract anteriorly. Two methods are utilized to open the airway; the "head-tilt and chin-lift" or the "jaw-thrust" maneuvers. Tilting the head backward by placing one hand on the forehead and raising the chin with the two fingers of the other hand is the most commonly used technique. An important feature of this technique is to make sure that the fingers are placed on the inferior surface of the mandibular bone and not the soft tissue under the tongue, as the later placement will worsen airway compromise. In a situation where a neck injury is suspected with possible spinal cord compromise, extension of the head is contraindicated; the jaw-thrust is utilized to open the airway. The head is held in the neutral position while applying forward pressure with both hands at the angle of the jaw, just below the ears. In this way, there is no change in head position. At this point inspection of the mouth is important to remove any secretions, vomitus or foreign bodies that may be an impediment to air exchange. Once the airway is opened, the rescuer "looks, listens, and feels" for breathing by placing his or her cheek and ear close to the victim's mouth. The chest is examined for movement while feeling and listening for air passage. In the case of a partial obstruction of the airway, the victim will tend to make high-pitched "crowing" noises that may be accompanied by cyanosis of the skin (due to unoxygenated hemoglobin). Instead of the chest expanding with an inspiration, retraction of thorax or lung compartment will occur. It is imperative that the airway be opened and maintained in this situation since ineffective ventilations will invariably lead to hypoxia.

B = Breathing

Once it is ascertained that the victim is not breathing (this should occur within ~10 s), the rescuer places his mouth around the victim's mouth and pinches the nose shut with one hand while maintaining chin-lift with the other hand. Two long, extended breaths are given, each ~ 2 s, with the goal of providing ventilation to the lungs while minimizing the egress of air into the stomach. Since during unconsciousness there is a relaxation of all muscles, the lower esophageal sphincter will relax and thus any air that enters the stomach may force gastric contents into the esophagus and then into the trachea. Aspiration of these highly acidic stomach contents into the lungs may occur. The complex interplay between rescuer, positive pressure ventilation, peak airway pressure, tidal volume, and inspiratory flow rate has had a considerable degree of scientific evaluation (106–109). The consensus supports a tidal volume of between 800 and 1000 mL to maintain adequate oxygenation when only room air is provided in the rescue breathing. This volume is slightly less than the 1992 ECC Guidelines of a rescue tidal volume of 800–1200 mL. A slow prolonged breath over 2 s decreases peak positive pressure and thus entry of air into the stomach while providing the optimum tidal volume. When supplemental oxygen is available, evidence has confirmed that a tidal volume of 500 mL provides effective oxygenation and ventilation in the unintubated patient as long as the inspired oxygen fraction is $>40\%$ (110,111). Once rescue breathing is commenced, one should assess effectiveness by noting whether the chest rises with each breath. If there is no change or the rescuer observes that significant effort is required to minimally expand the chest, the airway step has not been optimized and the rescuer has to reopen the airway with additional head extension and chin-lift (or jaw-thrust if a head or neck injury is suspected). If readjustment of the airway does not provide the ability to ventilate, a foreign body lodged in the airway should be suspected and the rescuer should proceed through the algorithm specific for dealing with this issue. Victims with dentures may prove difficult to ventilate; generally dentures should be left in place since it is easier for the rescuer to form a seal around the mouth. However, loose dentures may be aspirated and should be removed if their retention is inadequate. In the case where the rescuer cannot maintain an adequate seal, or if the mouth is unavailable for airway exchange secondary to trauma, mouth-to-nose breathing should be attempted (112). A deep breath should be inhaled by the rescuer prior to respiratory exchange since this maneuver optimizes the maximum amount of oxygen made available for each tidal volume (113). Should the victim only require oxygenation and ventilation, rescue breathing provides one breath every 5 s or 12 breaths/min (114).

There is always the concern regarding exposure to an infectious organism when performing rescue breathing. At this point in time, there has not been any evidence documenting the transmission of human immunedeficiency virus (HIV), hepatitis, or tuberculosis when mouth-to-mouth resuscitation has been instituted in an emergency (115). However, reluctance upon the part of any lay rescue person to perform this action is understandable and there is no moral or legal duty to do so. Barrier devices have been developed that prevent intimate contact with the victim and there are two basic types: face shields and masks. This adjunctive equipment has been made available in the healthcare environments due to the requirements of the Occupational Health and Safety Administration. The face shield has a flexible plastic covering with a one way circular valve that, when placed over the victim, separates the rescuer from contact and from exhaled gases. Mouth-to-mask rescue ventilation provides a better seal and further distance from the victim's mouth than the face shield, which is advantageous should vomiting occur. Some of these masks have a port where supplemental oxygen can be provided and entrained with the rescue breathing. A flow rate of 10 L/min through one of these masks will increase the inspired concentration of oxygen to at least 40% (116). When supplemental oxygen is supplied in this manner, smaller tidal volumes, on the order of 400–600 mL, will maintain oxygenation while decreasing the risk of gastric insufflation (117).

C = Circulation

After delivery of two rescue breaths, the next step in basic CPR is to assess for signs of circulation. For many years the layperson was taught to feel for the presence or absence of a carotid pulse. Research in the 1990s found numerous pitfalls with the pulse check that appeared to have a negative impact on survival and, since 2000, this task is not taught to the lay responder anymore. Significant time delays in trying to determine if a pulse was present delayed time to defibrillation and thus survival (118). The accuracy of the pulse test revealed a sensitivity of only 55% and a specificity of 90% and overall the accuracy was 65% (119). At this time, the lay rescuer is instructed to look for signs of perfusion, such as movement, breathing, or coughing and if unsure, to begin chest compressions.

Correct positioning of the hands and compression skills are easily learned by the layperson. A simplified method for hand placement has been taught for several years and consists of placing the heel of one hand over the center of the breastbone (sternum) between the nipples and then interlocking the fingers of the remaining hand over the first, so that pressure will be transmitted through the heels of both hands. Effective compressions are generated by positioning the rescuer's shoulders over the hands and sternum and depressing the sternum from 1.5 to 2 in. Release after compression must be complete without taking the hands off the chest to prevent "bouncing". Chest compressions should be similar in action to that of a piston in a reciprocating engine with half of the cycle spent in compression and the other half spent in relaxation. The effectiveness of this ratio has been documented with regard to both cerebral and coronary perfusion pressures (120). The recommended rate for chest compressions is 100/min, which has been substantiated by numerous studies (121,122).

The single rescuer initiates chest compressions after providing the victim with two rescue breaths and assessing for signs of effective cardiac blood flow. A ratio of 15 compressions followed by 2 rescue breaths continues for four cycles and then the victim is reassessed for spontaneous circulation. Chest compressions should be resumed within 10 s after noting no signs of perfusion and the 15:2 cycle continued with an interruption for assessment of vital signs in several minutes, followed by the same ratio.

When additional responders are present during resuscitation of a cardiac arrest victim, immediate activation of the EMS system must be accomplished and a defibrillator brought to the scene, if these actions have not already been completed by the lone rescuer. The second rescuer should then assess the adequacy of ventilations and chest compressions and reassess for signs of a pulse and breathing within 10 s while CPR is halted. Though it is not expected that the layperson be able to engage in two-person resuscitation, the process is included here for completeness. Medical professionals as well as the paramedical caregivers should all be able to demonstrate this skill. The compressor is positioned in the normal manner, at the side of the victim. The second rescuer is stationed at the victim's head, maintaining the airway, monitoring for effective compression by carotid artery pulse check, and providing rescue breaths. Previous scientific guidelines utilized a compression:ventilation ratio of 5:2 (123), which has now been changed in light of recent scientific evidence. Currently, a ratio of 15 compressions to 2 ventilations is recommended for both one and two rescuer CPR (124–126) since it appears that improved survival occurs as a result of the higher rate in spite of a decreased number of ventilations. The effectiveness of chest compressions relative to coronary perfusion pressure (the difference between aortic diastolic pressure and the left ventricular end-diastolic pressure) suggests that, as the number of compressions increases, so does the perfusion pressure; therefore, 15 chest compressions improves and sustains blood pressure more effectively than the previous recommendation of 5 compressions to 2 ventilations. The pauses with the previously recommended 5:2 compression:ventilation scheme had more drops in cerebral and coronary perfusion and therefore decreased oxygen delivery compared to the new scheme. Therefore, whether a one- or a two-rescuer resuscitation occurs, the preferred compression/ventilation ratio is 15:2. When advanced life support is initiated and the patient is intubated (a breathing tube place through the mouth and into the trachea) there is no pausing for ventilations; chest compressions continue at 100/min and ventilations are provided at a rate of 12 times a minute (127).

Despite the fact that there has never been evidence to suggest that transmission of disease occurs through mouth-to-mouth exchange of air or secretions, studies have demonstrated a lack of enthusiasm upon the part of both the layperson and professional rescuers to perform this maneuver on strangers (128,129). Current guidelines, as of 2001, now indicate that if the rescuer is unable to perform mouth-to-mouth ventilations, chest compressions should be started for the victim (130). The Cerebral Resuscitation Group of Belgium concluded that there was no difference in outcome for the victim if chest compressions were or were not accompanied by mouth-to-mouth rescue breathing (124). Since any resuscitation attempt utilizing chest compressions without ventilation may provide a better outcome for the victim than no action at all, education regarding this tactic in resuscitation has been made available to the lay responder. While it appears contrary to basic physiological principles that resuscitation could be successful without providing oxygen to the blood, evidence suggests that agonal breathing mechanisms are able to maintain adequate $P\text{aO}_2$ and $P\text{aCO}_2$ during CPR without rescue breathing (131). The etiology for this paradox appears to be due to the decreased perfusion from chest compressions; since the cardiac output is only one-fourth that of normal, ventilation perfusion mismatch does not occur due to low rates of blood flow through the lungs. In essence there is a decreased requirement for oxygen; any excess ventilation is wasted due to this decreased perfusion and the lack of oxygen transport by the available red blood cells (132,133). This form of CPR is only recommended for the public rescuer since paramedical personnel should always have adjunctive airway devices available for resuscitation.

AIRWAY OBSTRUCTION

The tongue is the most common cause of airway obstruction and basic life support addresses this issue with various maneuvers to open the airway thus allowing either spontaneous respirations to resume or mouth-to-mouth ventilations to be initiated for the victim. Foreign body airway obstruction is the cause of ~3000 deaths a year (134).

In perspective, there are 198 deaths per 100,000 persons for coronary artery disease, 16.5 deaths per 100,000 individuals for motor vehicle accidents, and 1.2 deaths per 100,000 due to foreign body obstruction (135). The "cafe coronary" (where choking was mistaken for an acute coronary event) appears to be the most common cause of choking in adults since this emergency usually happens during eating and meat seems to be the culprit for most occurrences (136). A foreign body lodged in the airway can either completely occlude or partially occlude any segment of the respiratory passages. The key to distinguishing these two scenarios is that the victim is able to continue to breath, albeit with difficulty, during a partial obstruction, and therefore the rescuer should not attempt any rescue attempt that potentially could convert a partial to a complete obstruction. As in all basic life support, it is crucial to activate the emergency medical system to get assistance. When a victim begins to make high pitched "crowing" sounds, cannot speak, or becomes cyanotic, hypoxia quickly ensues and this person needs immediate aid. The public is taught the universal chocking sign where the neck is clutched with both hands. The first question to ask the choking victim if, in fact, he or she is unable to breathe and if they can speak. The next immediate step is the Heimlich maneuver (137), which should be attempted in anyone between the ages of one and adulthood. This action is not indicated in infants <1 year old (138). Forceful external elevation of the diaphragm utilizes the remaining volume of air in the lungs to expel a foreign body. Placement of the hands is very important to minimize injury to the internal organs; when the victim is standing or sitting the rescuer wraps both arms around the victim's body and clenches the hand to make a fist. This fist, with the thumb compressed against the abdominal skin is placed above the umbilicus and below the xiphoid process (the distal end of the breastbone). A rapid thrust is made in a superior–posterior direction and continued until either the foreign object is displaced or the person becomes unconscious.

Once unconscious the EMS system must be activated by calling 911 and CPR is initiated for the victim. In this circumstance, after the airway is opened, mouth-to-mouth ventilation may be possible due to the muscle relaxation that occurs with unconsciousness, converting a complete obstruction to a partial obstruction, thus allowing rescue breaths to provide oxygenation to the blood. When opening the airway and during subsequent ventilations, the only change in basic CPR is to open the mouth and look for the presence of the offending obstruction, and if visible, grasp the object with the fingers and remove it (139). Blind finger sweeps are prohibited since injury can easily occur to the soft tissues of the mouth and throat. The initiation of chest compressions may also create enough intrathoracic pressure to expel the foreign object (140,141). The recommended maneuver for the obese or pregnant patient is to utilize chest thrust since the increased abdominal girth in either type of victim makes the Heimlich procedure difficult in terms of finding landmarks and avoiding injury, especially to the fetus. The victim is grasped from behind and the arms encircle the chest, just under the armpits, with the fist placed upon the breastbone. Again the thumb of the first hand is placed next to the skin overlying the breastbone and the second hand is then placed over the first, and with the hands interlocked, rapid compressions are performed in a posterior manner.

Once the foreign body is expelled from the unconscious victim, the basic "ABCs" are initiated as in any life-support situation. "Look, listen, and feel" for signs of breathing and if no excursion of air is present, the two rescue breaths are immediately provided for the victim. The next action in the sequence is to observe signs of adequate circulation, and if none are present, chest compressions are initiated and an AED is attached to the patient (142).

THE AUTOMATIC EXTERNAL DEFIBRILLATOR

The key issue in cardiopulmonary resuscitation is rapid initiation of the "Chain of Survival" and the length of time between victim collapse and defibrillation. Public access defibrillation (PAD) has the capability of significantly improving survival rates from cardiac arrest, in some cases to almost 50% (143). Since ventricular fibrillation has the highest frequency of occurrence in cardiac arrest and can only be terminated by countershock, it is clear that early defibrillation is will dramatically improve survival rates. The ECC guidelines of 2000 have a goal defibrillation within five minutes of the EMS activation (911 call).

The first automated cardiac resuscitator was described by Diack et al. in 1979 (144). This 19 lb battery-powered and most importantly, portable device sensed respiratory rate and the ECG. Ventricular fibrillation and asystole could be diagnosed. An oropharyngeal airway utilized a transducer to detect respiratory pressure as well as an electrode, which was applied to the base of the tongue. An electrode was placed over the chest wall (xiphoid area), which completed the electrical circuit for defibrillation. After initial trials in animals, the device was used at St. Vincent Hospital, Portland, Oregon on a 49-year-old male who arrived to the ED in ventricular fibrillation. The patient had failed to respond to CPR, chest defibrillation and medications. The patient was actually seizing from massive doses of lidocaine injected to decrease the automaticity of cardiac condition. The automatic resuscitator converted this lethal rhythm with one 335 J shock via the tongue-epigastric pathway.

There are actually no fully automatic external defibrillators available to the public; this is a misnomer since some actions are required upon the rescuer for the device to work. Once the AED is attached to the patient by adhesive pads and turned on, electronic evaluation occurs of the victim's underlying rhythm, and if a lethal dysrhythmia is evident, the AED will advise the rescuer to activate the "shock" button. These devices first record and then interpret the ECG. Narrow range bandwidth amplifiers first filter out various artifacts such as powerline transmission, high or low frequency radio transmissions, and extraneous "noise" that occurs from poor connections. Successive segments of the filtered ECG are than analyzed through a mathematical algorithm with each segment further tested in a sequential matter. The specifics of these algorithms are not made public due to the competitive nature of the various companies manufacturing these devices, but, essentially the rate, amplitude, waveform, frequency, and baseline variability of the ECG are analyzed and mathematical integration results to identify the rhythm that would or would not be treatable by defibrillation. The accuracy of these devices is extremely high after extensive testing both *in vitro* and *in vivo* to an early skeptical audience of medical personnel. The rare errors encountered with AED function appears to be related to movement of the patient, such as when the patient is being ventilated or repositioned during the analysis mode. Agonal respirations by the victim also create movement artifact that will interfere with rhythm analysis. The errors have generally been of omission in that dysrhythmias that would benefit from defibrillation have not been recognized, such as very coarse or fine ventricular fibrillation (145).

Since the first biphasic waveform was used in an AED in 1996 there has been a progression toward utilizing this new technology in future defibrillators. The current monophasic waveform devices deliver current that is unipolar and either damped sinusoidal or truncated relative to the rate at which the pulsed current decreases to zero. The biphasic defibrillators utilize a biphasic wave form of which each are exactly opposite in polarities. Optimum defibrillation is a balance between producing enough current to terminate VF without extensive damage to the heart. When a monophasic defibrillator is used during CPR, 200 J of energy is recommended for the first shock, with two succeeding shocks of between 200 and 300 J suggested in the AHA VF algorithm. These increases in energy with each shock have been demonstrated to optimize defibrillation success while minimizing tissue damage (146,147). Numerous studies have confirmed that biphasic waveform energy utilizing shocks as low as 115–130 J were as effective in terminating VF as the monophasic 200 J shock (148,149). The current scientific evidence supports conclusions that low-energy biphasic waveforms have at least the equivalent effectiveness as the monophasic waveforms in defibrillating VF; it appears that biphasic waveform defibrillation will be the standard of care in the future.

Operation of the various AEDs is very straightforward and, although there are different models, the devices have very similar controls and functions. Once the AED is brought to the scene of a victim that is not breathing and has no effective pulse, it should be positioned at the victim's left side for easier electrode placement and to allow the "ABCs" of CPR to continue without interruption on the victim's right side. The machine is turned on, and then a series of prompts by an electronic voice guide the rescuer through the remaining steps. The electrodes are next placed on the skin, with the right pad positioned just under the right collar bone (clavicle) and the left pad placed lateral to the left nipple. The third step requires that everyone involved in the resuscitation desist from any contact with the victim while the AED analyzes the rhythm. This is extremely important in that any movement generated by the rescuers will induce an artifact error. Depending on the particular device, some AEDs will automatically analyze while some machines require manual selection by the operator. If VF or VT is present, an electronic voice will indicate that a shock should be delivered; everyone should clear the victim and there should be no one in contact with the body. Once the operator is sure that everyone is clear of the victim, the "shock" button is depressed and the victim's body will exhibit the generalized musculature contracture observed with a defibrillating current. Cardiopulmonary resuscitation is not resumed since the AED must again be ready to deliver another shock after analyzing the postshock rhythm. In this way, three shocks are successively delivered before resumption of "airway, breathing, and chest compressions". If the "no shock indicated" message is transmitted to the rescuers, either there is now a pulsatile, perfusing rhythm, or there is a lethal dysrhythmia that would not improve survival with a defibrillating shock (such as asystole). If signs of circulation become present, then rescue breathing should continue, unless of course the victim also has a recurrence of adequate ventilations (150).

There are some specific circumstances that must be considered with the use of an AED. Children that are < 8 years of age or victims weighing < 25 kg may not benefit from the current AED since the energy delivered in the monophasic devices are in excess of the recommended 2:4 J/kg. Though it appears that VF can be detected accurately in children, there is insufficient evidence that the algorithms devised for the adult cardiac arrest patient will always determine an arrest rhythm that will benefit from defibrillation, particularly with regard to pediatric tachy-arrhythmias (151,152). However, in the pediatric arrest patient the potential benefit greatly outweighs the risk of AED–individual injury, and therefore this device should be readily available for early application. Another special situation occurs when the victim has been in the water. Even when the victim has been removed from water, there is the risk of induced shock to the rescuer from the moisture present on the victim's body. The other concern, which has the most potential for occurrence, is that the shock would not be conducted along the appropriate pathway from the electrodes, instead bypassing the heart by the water present upon the skin. The third issue regarding AEDs is that many older victims may have a pulse generator present for cardiac rate control or for internal defibrillation. These devices are usually implanted in the superficial tissues of the chest and appear as an elevated, hard lump, which may or may not be easily observed, depending on the obesity of the patient. What can be observed is the scar from implantation; avoidance of pad placement over the implanted device would mitigate any interference for the AED to detect and provide a defibrillating shock. The last situation that may be encountered is the medication patches, which many patients utilize for a variety of conditions. Pad placement over these patches could significantly decrease the energy delivered to the heart; the recommended procedure is to remove the medication patch and wipe the medication away from the skin prior to pad placement (153).

The AED has the potential to be a strategic intervention to increase out-of-hospital survival in the cardiac arrest patient. Public access defibrillation will continue to be more available due to the efficacy already demonstrated in the previously mentioned studies as well as progressive legislation. The continued technology to produce smaller devices at less cost will undoubtedly increase access both in public places and into the homes of those individuals at risk for sudden cardiac death.

PEDIATRIC AND INFANT CARDIOPULMONARY RESUSCITATION

There are significant differences in the etiology for cardiac arrest in the adult compared to children. In adults, a terminal dysrhythmia is usually caused by progression of coronary artery disease where an acute hypoxic event produces hypoxia, injury, and then disruption of organized depolarization of myofibrils. Children are entirely different in that a hypoxic pulmonary event is the usual cause of the progression of a normal sinus rhythm to an extremely slow heart rate (bradycardia) and then to asystole. The majority of these arrests occur from foreign body obstruction, drowning, trauma, or Sudden Infant Death Syndrome (SIDS), poisoning, asthma, or pneumonia (154). This is where the American Heart Association CPR algorithm for the child is different than that of the adult. Since respiratory failure is such a significant etiology for cardiac arrest, the rescuer is instructed to provide CPR first then "phone fast" rather than the adult rescue scenario where activation of the EMS system (phone first) occurs prior to CPR. The remaining steps in the "ABCs" of life support are similar to the adult. Once unresponsiveness is determined for the victim and the rescuer shouts for help, the child should be placed supine, being careful to move the entire body as one if a head or neck injury is suspected. The airway is opened with the "head-tilt, chin-lift" as in the adult, or the "jaw-thrust maneuver" if there is suspicion for head or neck trauma. After opening the airway and inspecting the mouth for a foreign body, "look, listen, and feel" for the passage of air by the victim within the time frame of no more than ten seconds. If the assessment reveals lack of adequate ventilation, two slow rescue breaths with an adequate pause between them to allow for exhalation are delivered to the victim; the endpoint for tidal volume is a visible rise in the thoracic chest wall. As in the adult, if no air enters the lungs, the most common cause is an inadequate airway lumen secondary to either tongue obstruction or a foreign body. Repositioning of the head should be immediately attempted, and if the rescuer can still not ventilate, entry into the foreign body obstruction algorithm should be the next action undertaken. Should the rescuer provide effective ventilation for the two initial breaths and signs of circulation exist, a rate of 20 breaths/min is recommended for an infant (< 1 year of age) and for the child (1–8 years of age.) If no movement, spontaneous breathing, or other signs of circulation exist, chest compressions should be started within 10 s. The depth for compressions in an infant or child should be about one-third to one-half of the total distance from the child's anterior chest wall to the back, and at a rate of 100 times/min. In a child (1–8 years of age), the use of only one hand is recommended, with placement between the nipple line and the bottom of the breastbone (sternum.) As in the adult, the heel of the hand is used. A ratio of five compressions to one ventilation is recommended, with reassessment of the child after 20 cycles of compressions and ventilations have occurred. Chest compressions in an infant (< 1 year of age) are similar except that chest compressions are accomplished with two fingers to a depth of one-third to one-half the distance from the anterior chest to the back. The location for compression is one finger-width below an imagined line between the nipples. The rate is 100 times/min and the compression to ventilation ratio is 5:1, as in the child. Reassessment for signs of circulation and spontaneous ventilations should occur after ~ 1 min or 20 cycles of compressions and ventilations (155).

Foreign body obstruction is treated in a similar manner to the adult in a child between 1–8 years of age when assessment by the responder indicates a severe or complete airway occlusion. After immediate activation of the EMS system, the Heimlich maneuver is instituted with the same adult landmarks where the rescuer's fists are place above the umbilicus, being careful to stay away from the inferior aspect of the breastbone, where the xyphoid process is located. Should the child become unresponsive from respiratory arrest, CPR should be initiated, with the initial airway assessment focused upon looking for the foreign object, and, if visible, removing it. Two rescue breaths should be initiated and then chest compressions begun. As in the adult, chest compressions may cause the foreign object to be dislodged where it can be extricated. The infant (under the age of 1 year) is treated quite differently when foreign body aspiration is suspected, since concerns have been raised regarding intraabdominal injury and the Heimlich maneuver (156,157). The infant is cradled with one hand and arm, turned prone, and then five back blows are delivered between the shoulder blades (scapulae) using the heel of the hand. Immediately the victim is turned supine and cradled with the opposite hand and arm. Up to five chest-thrusts are delivered in the same location for chest compressions. This scheme is alternated until either the obstruction is dislodged or the infant becomes unconscious. Once unresponsive, the next action, as in the adult and child, is to look in the airway and determine if the obstruction can be removed. Cardiopulmonary resuscitation is then initiated and activation of the EMS system undertaken (158).

CONCLUSION

Cardiopulmonary resuscitation has made gigantic strides since the scientific community integrated the rudiments of airway maintenance, rescue breathing and external chest compressions in the 1960s. Once these procedures were developed, the foresight by healthcare professionals to implement CPR in the community and educate the public in the early 1970s has contributed greatly to the success of this program. Currently, the strategy is to simplify the training for Basic Life Support as well as to increase the number of lay responders. Since 1973 > 40 million people have learned the basic life-saving skills taught in CPR classes (156). The recognition that emergency cardiac care should not only provide an organized structure for resuscitation, but also to incorporate education in the prevention of risk factors for coronary artery disease, stroke, and pediatric mortality has the capability of dramatically reducing future morbidity and death. For example, ~ 30% of the deaths from atherosclerotic vascular disease are attributable to smoking, and in those individuals who quit smoking, the death rate declines to almost near normal (160,161). Risk factors, such as smoking, that can be changed by providing both education and interventional guidelines, are a continual focus for organizations like the American Heart Association to address at the present and in the future. As previously mentioned, public access for the automated defibrillator has the potential to greatly reduce deaths in the prehospital arrest scenario. As the time element for CPR and defibrillation has been proven to be so critical for reducing morbidity and mortality from cardiac arrest, those communities that have incorporated aggressive public and paramedical training for these two modalities have reported an almost 50% resuscitation rate for victims documented to have had ventricular fibrillation (1,2). The proliferation of AEDs both in public gathering places and into the home, certainly has the capability to improve these statistics. The continued focus upon rapid recognition of stroke victims in lay responder courses will make a dramatic improvement in rapid treatment and neurological salvage for these individuals. It has been stated that the community will be "the ultimate coronary care unit"(162) since the majority of cardiac arrests occur in the out-of-hospital setting and, therefore, public involvement is crucial to survival. The expectation for the future is that the public "coronary care unit" will be expanded to include a "neurological care unit" as well. The challenge for the future will be to continue to expand the public awareness and involvement in these programs as new scientific evidence continues to guide the evolution of cardiopulmonary resuscitation.

HISTORICAL EVENTS IN CPR

Antiquity	Prophet Elisha describes attempts to revive the dead.
Second century	Galen observed the inflation of a dead animal's lungs.
Middle Ages	Hot materials to the abdomen, whipping, rectal smoke.
Paracelsus, sixteenth century	Fireplace bellows ventilated a patient.
Tossach 1744	First recorded mouth-to-mouth resuscitation.
Squires, 1775	First successful defibrillation.
DeHaen, 1783	Chest compression, arm lift technique.
Leroy, 1830	First description of supine ventilation.
Schiff, 1847	Open chest cardiac compression.
Silvester; Howard, twenteeth century	Alternating arm position ventilation; back, abdominal and chest pressure, respectively.
Koenig; Maass, 1850s	Reports of eight successful closed-chest cardiac compressions in humans.
Holger-Nielson, twenty-first century	Prone back pressure, arm-lift.
Gurvich; Yuniev, 1939	First successful external defibrillation by a device.
Kouwenhoven, Knickerbocker, Isaacs, 1950s	Defibrillation experiments coupled with chest compressions.
Elam, 1960s	Physiology of rescue breathing.
Elam, Safar, Kouwenhoven, 1960s	Principles of modern CPR.
Zoll, 1956	First successful external defibrillation in humans.

BIBLIOGRAPHY

1. White RD, Asplin BR, Bugliosi TF, Hankins DG. High discharge survival rate after out of-hospital ventricular fibrillation by police and paramedics. Ann Emerg Med 1996;28: 480–485.
2. White RD, Hankins DG, Bugliosi TF. Seven years experience with early defibrillators by police and paramedics in an emergency medical services system. Resuscitation 1998;39: 145–151.
3. Holy Bible, Kings II 4:34–35 (King James Version).
4. Baker AB. Artificial respiration: the history of an idea. Med Hist 1971;15:336–346.
5. [Anonymaus]. Cardiopulmonary Resuscitation Conference Proceedings. The Ad Hoc Committee on Cardiopulmonary Resuscitation; Division of Medical Sciences of the National Research Council; 1967. p 7.
6. Julian DG. Cardiac resuscitation in the eighteenth century. Heart Lung 1975;4:46–48.
7. Gordon AS. The principles and practice of heart-lung resuscitation. Acta Anaesth Scand Suppl 1961;9:134–147.
8. Gordon AS, Affeldt JE, Sadove M, Raymon F, Whittenberger JL, Ivy AL. Air-flow patterns and pulmonary ventilation during manual artificial respiration on apneic normal adults. J Appl Physiol 1955;4:408–420.
9. Gordon AS, Fainer DC, Ivy AL. Artificial respiration: a new method and a comparative study of different methods in adults. JAMA 1950;144:1455–1464.
10. Elam JO. Rediscovery of expired air methods for emergency ventilation. In: Safar P, Elam JO, editors. Advances in Cardiopulmonary Resuscitation. Chapt. 39, New York: Springer-Verlag; 1977. p 263–265.
11. Elam JO, Brown ES, Elder JD Jr. Artificial respiration by mouth-to-mask method. A study of the respiratory gas exchange of paralyzed patients ventilated by operator's exhaled air. New Engl J Med 1954;250:749–754.
12. Safar P, Elam J. Manual versus mouth-to-mouth methods of artificial respiration. Anesthesiology 1958;19:111–112.
13. Safar P, Escarraga LA, Elam JO. A comparison of the mouth-to-mouth and mouth-to-airway methods of artificial respiration with the chest-pressure arm-lift methods. New Engl J Med 1958;258:671–677.
14. Safar P. Failure of manual respiration. J Appl Physiol 1959;14:84–88.
15. Safar P. Ventilatory efficacy of mouth-to-mouth artificial respiration. Airway obstruction during manual and mouth-to-mouth artificial respiration. JAMA 1958;167:335–341.
16. Safar P, Aguto-Escarraga L, Chang F. Upper airway obstruction in the unconscious patient. J Appl Physiol 1959;14: 760–764.
17. Morikawa S, Safar P, DeCarlo J. Influence of head-jaw position upon upper airway patency. Anesthesiology 1961; 22: 265–270.
18. Safar P, Redding J. The "tight jaw" in resuscitation. Anesthesiology 1959;20:701–702.
19. Elam JO, Greene Dg, Brown ES, Clements JA. Oxygen and carbon dioxide exchange and energy costs of expired air resuscitation. JAMA 1958;167:328–324.
20. Gordon AS, Frye CW, Gittelson L, Sadove MS, Beattie EJ. Mouth-to-mouth versus manual artificial respiration for children and adults. JAMA 1951;147:1444–1453.
21. Jude JR, Kouwenhoven WB, Knickerbocker GG. Cardiac arrest. JAMA 1961;128:1063.
22. Boehm RV. Arbeiten aus dem pharmakologischen Institue der Universitat Dorpat:13. Ueber Wiederbelebung nach Vergiftungen un Asphysie. Arch Exper Path U Pharmakol 1878;8:68–101.
23. Safar P. History of cardiopulmonary resuscitation. In: Kaye W, Bircher N, editors. Cardiopulmonary Resuscitation. New York: Churchill Livingstone; 1989.
24. Maass Die Methode der. Wiederbelebung bei Herztod nach chloroformeinathmung, Berlin Klin. Wochschr 1892;29: 265–268.
25. Crile WG. Surgical Anemia and Resuscitation. New York: D Appleton and Co; 1904. p 220–244.
26. Hooker DR, Kouwenhoven WB, Langworthy OR. The effect of alternating currents on the heart. Am J Physiol 1933;103: 444–454.
27. Gurvich HL, Yuniev GS. Restoration of heart rhythm during fibrillation by condenser discharge. Am Rev Soviet Med 1947;4:252–256.
28. Kouwenhoven WB, Jude JR, Knickebocker GG. Closed-chest cardiac massage. JAMA 1960;173:1064–1067.
29. Safar P. Initiation of closed-chest cardiopulmonary resuscitation basic life support. A personal history. Resuscitation 1989;18:7–20.
30. Kouwenhoven WB, Langworth OR. Cardiopulmonary resuscitation. An account of forty-five years of research. JAMA 1973;226:877–886.

31. Jude JR, Kouwenhoven WB, Knickerbocker GG. Cardiac arrest: report of application of external cardiac massage on 118 patients. JAMA 1961;178:1063–1070.
32. Safar P, Brown TC, Holtey WH. Ventilation and circulation with closed chest cardiac massage in man. JAMA 1961;176: 574–576.
33. Harris LC, Kirimli B, Safar P. Ventilation-cardiac compression rates and ratios in cardiopulmonary resuscitation. Anesthesiology 1967;28:806–813.
34. Zoll PM, et al. Termination of ventricular fibrillation in man by externally placed electric countershock. New Engl J Med 1956;254:727.
35. Weale FE, Rothwell-Jackson RL. The efficiency of cardiac massage. Lancet 1962;1:990–992.
36. Del Guercio LR, Coomraswamy RP, State D. Cardiac output and other hemodynamic variables during external cardiac massage in man. New Engl J Med 1963;269:1398–1404.
37. Thomsen JE, Stenlund RR, Row GG. Intracardiac pressures during closed chest cardiac massage. JAMA 1968; 205:116–118.
38. Criley JM, Blaufuss AH, Kissel GL. Cough induced cardiac compression. JAMA 1976;236:1246–1250.
39. Taylor GJ, Tucker WM, Greene HL, Rudikoff MT, Weisfeldt ML. Importance of prolonged compression during cardiopulmonary resuscitation in man. New Engl J Med 1977;296: 1515–1517.
40. Chandra N, Rudikoff MT, Weisfeldt ML. Simultaneous chest compression and ventilation at high airway pressure during cardiopulmonary resuscitation. Lancet 1980;1:175–178.
41. Werner JA, Greene HL, Janko CL, Cobb LA. Visualization of cardiac valve motion in man during external compression using two-dimensional echocardiography: implications regarding the mechanism of blood flow. Circulation 1981; 63:1417–1421.
42. Rich S, Wix HL, Shapiro EP. Clinical assessment of heart chamber size and valve motion in man during external compression using two-dimensional echocardiography: implications regarding the mechanism of blood flow. Am Heart J 1981;102:368–373.
43. Maier GW, et al. The physiology of external cardiac massage: high impulse cardiopulmonary resuscitation. Circulation 1984;70:86–101.
44. Feneley MP, et al. Sequence of mitral valve motion and transmitral flow during manual cardiopulmonary resuscitation in dogs. Circulation 1987;76:363–375.
45. Porter TR, et al. Transesophageal echocardiography to assess mitral valve function and flow during cardiopulmonary resuscitation. Am J Cardiol 1992;70:1056–1060.
46. West JB. Physiological Basis of Medical Practice. 12th ed. Baltimore: Williams & Wilkins; 1990. p 522.
47. Permut S, Bromberger-Barnea B, Bane HN. Alveolar pressure, pulmonary venous pressure and the vascular waterfall. Med Thorac 1962;19:239.
48. Cummins RO, editor. ACLS Provider Manual. American Heart Association; 2002. p 78.
49. Vukmir RB. Torsades de pointes: a review. Am J Emerg Med 1991;9:250–255.
50. Cummins RO, editor. Advanced Cardiac Life Support. American Heart Association; 1997-1999. p 39–40.
51. American Heart Association in collaboration with International Liaison Committee on Resuscitation and Emergency Cardiovascular Care: International Consesus on Science Part 3: Adult Basic Life Support. Circulation 2000; 102(Suppl I): I–226.
52. Brown DC, Lewis AJ, Criley JM. Asystole and its treatment: the possible role of the parasympathetic nervous system in cardiac arrest. J Am Coll Emerg Phys 1979;8: 448–542.
53. Thompson BM, Brooks RC, Pionkowski RS, Aprahamian C, Mateer JR. Immediate countershock treatment of asystole. Ann Emerg Med 1984;13:827–829.
54. Bocka JJ. External transcutaneous pacemakers. Ann Emerg Med 1989;18:1280–1286.
55. Paradis NA, Martin GB, Goetting MG, Rivers EP, Feingold M, Nowak RM. Aortic pressure during human cardiac arrest: identification of pseudo-electromechanical dissociation. Acta Anaesthesiol Scand 1991;35:253–256.
56. Bocka JJ, Overton DT, Hauser A. Electromechanical dissociation in human beings: an echocardiographic evaluation. Ann Emerg Med 1988;17:450–452.
57. Cummins RO editor. ACLS Provider Manual, American Heart Association. 2001. p 103–104.
58. Rosenberg D, Levin E, Myerburg RJ. A mnemonic for the recall of causes of electro-mechanical dissociation (EMD). Resuscitation 1999;40:57.
59. Cummins RO, Eisenberg MS. Prehospital cardiopulmonary resuscitation: is it effective?. JAMA 1985;253:2408–2412.
60. Cummins RO. From concept to standard-of-care? Review of the clinical experience with automated external defibrillators. Ann Emerg Med 1989;18:1269–1275.
61. Cummins RO, Eisenberg MS. Prehospital cardiopulmonary resuscitation: is it effective?. JAMA 1985;253:2408.
62. Valenzuela TD, Roe DJ, Nichol G, Clark LL, Spaite DW, Hardman RG. Outcomes of rapid defibrillation be security officers after cardiac arrest in casinos. N Engl J Med 2000; 343:1206–1209.
63. Cummin RO.. Advanced Cardiac Life Support, American Heart Association. 1997–1999. p 16–4.
64. Levine RL, Wayne MA, Miller CC. End-tidal carbon dioxide and outcome of out-of hospital cardiac arrest. New Eng J Med 1997;337:301–306.
65. Graves EJ. National hospital discharge survey: annual summary 1991. Vital Health Statistics 1993;13:1–62.
66. 2000 Heart and Stroke Statistical Supplement. Dallas: American Heart Association; 1999.
67. Eisenberg MD, Mengert TJ. Cardiac Resuscitation. New Engl J Med 2001;344:1304–1313.
68. Gillum RF. Trends in acute myocardial infarction and coronary heart disease death in the United States. J Am Coll Cardiol 1994;23:1273–1277.
69. Kannel WB, Schatzkin A. Sudden death: lessons from subsets in population studies. J Am Coll Cardiol 1985;5(Suppl 6); 141B–149B.
70. Mathey DG, Sheehan FH, Schofer J, Dodge HT. Time from onset of symptoms to thrombolytic therapy: a major determinant of myocardial salvage in patients with acute transmural infarction. J Am Coll Cardiol 1985;6: 518–525.
71. Anderson JL, Karagounis LA, Califf RM. Metaanalysis of five reported studies on the relation of early coronary patency grades with mortality and outcomes after acute myocardial infarction. Am J Cardiol 1996;78:1–8.
72. Kannel WB. Prevalence and clinical aspects of unrecognized myocardial infarction and sudden unexpected death. Circulation 1987;75(Suppl 2, pt 2): II–4–II–5.
73. Cummins RO. Advanced Cardiac Life Support, American Heart Association. 1997–1999. p 9–4.
74. Herrick J. Clinical features of sudden obstruction of the coronary arteries. JAMA 1912;59:2015–2020.
75. Smith M, Little WC. Potential precipitating factors of the onset of myocardial infarction. Am J Med Sci 1992;303:141–144.

76. Muller JE, Tofler GH, Stone PH. Circadian variation and triggers of onset of acute cardiovascular disease. Circulation 1989;79:733–744.
77. Peters RW, et al. Identification of a secondary peak in myocardial infarction onset 11 to 12 hours after awakening: the Cardiac Arrhythmia suppression Trial (CAST) experience. J Am Coll Cardiol 1993;22:998–1003.
78. Solomon CG, et al. Comparison of clinical presentation of acute myocardial infarction in patients older than 65 years of age to younger patients: the Multicenter Chest Pain Study experience. Am J Cardiol 1989;63:772–776.
79. Douglas PS, Ginsburg GS. The evaluation of chest pain in women. New Engl J Med 1996;334:1311–1315.
80. Brand FN, Larson M, Friedman LM, Kannel WB, Castelli WP. Epidemiologic assessment of angina before and after myocardial infarction: the Framingham Study. Am Heart J 1996;132(pt 1): 174–178.
81. Mathey DG, Sheehan FH, Schofer J, Dodge HT. Time from onset of symptoms to thrombolytic therapy: a major determinant of myocardial salvage in patients with acute transmural infarction. J Am Coll Cardiol 1985;6:518–525.
82. Newby LK, et al. Time from symptom onset to treatment and outcomes after thrombolytic therapy: GUSTO-1 Investigators. J Am Coll Cardiol 1996;27:1646–1655.
83. Berger CJ, et al. Prognosis after first myocardial infarction: comparison of Q-wave and non-Q-wave myocardial infarction in the Framingham Heart Study. JAMA 1992;268: 1545–1551.
84. Gibson RS. Non-Q-wave myocardial infarcton: pathophysiology, prognosis, and therapeutic strategy. Annu Rev Med 1989;40:395–410.
85. TIMI investigators. Effects of tissue plasminogen activator and a comparison of early invasive and conservative strategies in unstable angina and non-Q-wave myocardial infarction: results of the TIMI IIIB Trial. Thrombolysis in Myocardial Ischemia. Circulation 1994; 89:1545–1556.
86. Cohen MV, et al. The effects of nitroglycerin on coronary collaterals and myocardial contractility. J Clin Invest 1973;52:2836–2847.
87. Malindzak GS. Jr., Green HD, Stagg PL. Effects of nitroglycerin on flow after partial constriction of the coronary artery. J Appl Physiol 1970;29:17–22.
88. ISIS-2 (Second International Study of Infarct Survival) Collaborative Group. Randomized trial of intravenous streptokinase, oral aspirin, both or neither among 17,187 cases of suspected acute myocardial infarction: ISIS-2. Lancet 1988;2:349–360.
89. Lee G, et al. Comparative effects of morphine, meperidine and pentazocine on the cardiocirculatory dynamics in patients with acute myocardial infarction. Am J Med 1976; 60:949–955.
90. 2000 Heart and Stroke Statistical Update. Dallas, TX: American Heart Association; 1999.
91. The National Institute of Neurological Disorders and Stroke rt-PA Stroke Study Group. Tissue plasminogen activator for acute ischemic stroke. New Engl J Med 1995;333:1581–1587.
92. Bendzus M, Urbach H, Ries F, Solymosi L. Outcome after local intra-arterial fibrinolysis compared with the natural course of patients with a dense middle cerebral artery on early CT. Neuroradiology 1998;40:54–48.
93. Kwiatkowski TG, et al., for the NINDS r-tPA Stroke Study Group. Effects of tissue plasminogen activator for acute ischemic stroke at one ear. New Engl J Med 1993;340: 1781–1787.
94. Albers GW, et al. Intravenous tissue-type plasminogen activatior for treatment of acute stroke: the Standard Treatment with Alteplase to Reverse Stroke (STARS) Study. JAMA 2000;283:1145–1150.
95. Barnett HJ. The pathophysiology of transient cerebral ischemic attacks. Med Clin North Am 1979;63:649–679.
96. Viitanen M, Eriksson S, Asplund K. Risk of recurrent stroke, myocardial infarction and epilepsy during long- term follow-up after stroke. Eur Neurol 1988;28:227–231.
97. North American Symptomatic Carotid Endarterectomy Trial Collaborators. Beneficial effect of carotid endarterectomy in symptomatic patients with high-grade stenosis. New Engl J Med 1991;325:445–453.
98. Antiplatelet Trialists' Collaboration. Secondary prevention of vascular disease by prolonged antiplatelet treatment. BMJ 1988;296:320–331.
99. Weir B, editor. Aneurysms Affecting the Nervous System. Baltimore: Williams & Wilkins; 1987.
100. Brott T, Thalinger K, Hertzberg V. Hypertension as a risk factor for spontaneous intracerebral hemorrhage. Stroke 1986;17:1078–1083.
101. Waga S, Otsubo K, Handa H. Warning signs in intracranial aneurysms. Surg Neurol 1975;3:15–20.
102. Korpelainen JT, Sotaniemi KA, Makikallio A. Dynamic behavior of heart rate in ischemic stroke. Stroke 1999;30: 1008–1013.
103. Hazinski MF. Demystifying recognition and management of stroke. Curr Emerg Cardiac Care, Winter 1996;7:8.
104. Lyden PD, Rapp K, Babcock T, Rothcock J. Ultra-rapid identification, triage, and enrollment of stroke patients into clinical trials. J Stroke Cerebrovas Dis 1994;4:106–107.
105. Kidwell CS, et al. Design and retrospective analysis of the Los Angeles prehospital stroke screen (LAPSS). Prehosp Emerg Care 1998;2:267–273.
106. Wenzel V, Idris Ah, Lindner KH. Ventilation with an unprotected airway during cardiac arrest. In: Vincent JL, editor. Yearbook of Intensive Care and Emergency Medicine. Berlin: Springer-Verlag; 1997: 483–492.
107. Wenzel V, Idris AH. The current status of ventilation strategies during cardiopulmonary resuscitation. Curr Opin Crit Care 1997;3:206–213.
108. Stalinger A, et al. Effects of different mouth-to-mouth ventilation tidal volumes on gas exchange during simulated rescue breathing (abstract). Crit Care Med 2001. Forth-coming.
109. Dorges V, et al. Smaller tidal volumes with room air are not sufficient to ensure adequate oxygenation during bag-valve-mask ventilation. Resuscitation 2000;44:37–41.
110. Baskett P, Nolan J, Parr M. Tidal volumes which are perceived to be adequate for resuscitation. Resuscitation. 1996;31:231–234.
111. Wenzel V, et al. Effects of smaller tidal volumes during basic life support ventilation in patients with respiratory arrest: good ventilation, less risk?. Resuscitation 1999;43: 25–29.
112. Heartsaver CPR: A comprehensive course for the lay responder. Dallas: American Heart Association; 2000. p 23–29.
113. Htin KJ, et al. Rescuer breathing pattern significantly affects O_2 and CO_2 received by patient during mouth-to-mouth ventilation. Crit Care Med 1998;26: (Suppl 1) A56.
114. Stapleton ER, Auferheide TP, Hazinski MF. BLS for Healthcare Providers. Dallas: American Heart Association; 2001. p 68–70.
115. Cummins RO, editor. ACLS Provider Manual. Dallas: American Heart Association; 2001. p 208.
116. Johannigman JA, Branson RD. Oxygen enrichment of expired gas for mouth-to mask resuscitation. Respir Care 1991;36:99–103.

117. Idris AH, Wenzel V, Banner MJ, Melker RJ. Smaller tidal volumes minimize gastric inflation during CPR with an unprotected airway. Circulation 1995;92(Suppl I): I–759.
118. Cummins RO, Hazinski MF. Cardiopulmonary resuscitation techniques and instruction: when does evidence justify revision?. Ann Emerg Med 1999;34:780–784.
119. Eberle B, et al. Checking the carotid pulse check: diagnostic accuracy of first responders in patients with and without a pulse. Resuscitation 1996;33:107–116.
120. Handley AJ, Handley JA. The relationship between rate of chest compression and compression:relaxation ratio. Resuscitation 1995;30:237–241.
121. Swenson RD, et al. Hemodynamics in humans during conventional and experimental methods of cardiopulmonary resuscitation. Circulation 1998;78:630–639.
122. Kern KB, et al. A study of chest compression rates during cardiopulmonary resuscitation in humans. Arch Intern Med 1992;152:145–149.
123. Guidelines for cardiopulmonary resuscitation and emergency cardiac care. Emergency Cardiac Care Committee and Subcommittees, American Heart Association. JAMA 1992;268: 2171–2295.
124. Van Hoeyweghen RJ, et al., Quality and efficiency of bystander CPR: Belgian cerebral resuscitation. Resuscitation 1993;26: 47–52.
125. Kern KB, et al. Efficacy of chest compression—only BLS/CPR in the presence of an occluded airway. Resuscitation 1998;39: 179–188.
126. Wik L, Steen PA. The ventilation-compression ratio influences the effectiveness of two rescuer advanced cardiac life support on a manikin. Resuscitation 1996;31:113–119.
127. Cummins RO, editor. ACLS Provider Manual. Dallas: American Heart Association; 2001. p 30.
128. Hew P, Brenner B, Kaufman J. Reluctance of paramedics and emergency medical technicians to perform mouth-to-mouth resuscitation. J Emerg Med 1997;15:279–284.
129. Locke CJ, et al. Bystander cardiopulmonary resuscitation: concerns about mouth-to-mouth contact. Arch Intern Med 1995;155:938–943.
130. Stapleton ER, Aufderheide TP, Hazinski MF, editors. BLS for Healthcare Providers. Dallas: American Heart Association; 2001. p 80.
131. Tang W, et al. Cardiopulmonary resuscitation by precordial compression but without mechanical ventilation. Am J Resp Crit Care Med 1994;150:1709–1713.
132. Weil MH, et al. Differences in acid- base status between venous and arterial blood during cardiopulmonary resuscitation. New Engl J Med 1986;315:153–156.
133. Sanders AB, et al. Acid-base balance in a canine model of cardiac arrest. Ann Emerg Med 1988;17:667–671.
134. National Safety Council. Injury Fact. 1999. Itasca: National Safety Council; 1999.
135. National Safety Council. Accident Facts. 1997. Chicago: National Safety Council; 1997.
136. Ekberg O, Feinberg M. Clinical and demographic data in 75 patients with near-fatal choking episodes. Dysphagia 1992;7:205–208.
137. Heimlich HJ, Hoffmann KA, Canestri FR. Food-choking and drowning deaths prevented by external subdiaphragmatic compression: physiological basis. Ann Thoracic Surg 1975;20:188–195.
138. American Heart Association, International Liaison Committee on Resuscitation (ILCOR). Guidelines 2000 for Cardiopulmonary Resuscitation and Emergency Cardiovascular Care. International Consensus on Science. Circulation 2000;102 (Suppl I): I46–I–48.
139. Heartsaver CPR: A comprehensive course for the lay responder. Dallas: American Heart Association; 2000. p 31–33.
140. Langhell A, Sunde K, Wik L, Steen PA. Airway pressure with chest compression versus Heimlich manoeuvre in recently dead adults with complete airway obstruction. Resuscitation 2000;44:105–108.
141. Skullberg A. Chest compressions: an alternative to the Heimlich manoeuvre?. Resuscitation 1992;24:91.
142. Stapleton ER, Auferheide TP, Hazinski MF. BLS for Healthcare Providers. Dallas: American Heart Association; 2001. p 128.
143. White RD, Vukov LF, Bugliosi TF. Early defibrillation by police; initial experience with measurement of critical time intervals and patient outcome. Ann Emerg Med 1996;28:480–485.
144. Diack AW, Welborn WS, Rullman RG, Walter CW, Wayne MA. An automatic cardiac resuscitator for emergency treatment of cardiac arrest. Med Instrum 1979; Mar–Apr; 13(2): 78–83.
145. Cummins RO, Eisenber M, Bergner L, Murray JA. Sensitivity, accuracy, and safety of an automatic external defibrillator. Lancet 1984;2:318–320.
146. Kerber RE, et al. Energy, current, and success in defibrillation and cardioversion: clinical studies using an automated impedence-based method of energy adjustment. Circulation 1988;77:1038–1046.
147. Dahl C, et al. Myocardial necrosis from direct current countershock. Circulation 1974;50:956.
148. Bardy GH, et al. Truncated biphasic pulses for transthoracic defibrillation. Circulation 1995;91:1768–1774.
149. Bardy GH, et al. Transthoracic Investigators. Multicenter comparison of truncated biphasic shocks and standard damped sine wave monophasic shocks for transthoracic ventricular defibrillation. Circulation 1996;94:2507–2514.
150. Auferheide TP, Stapleton ER, Hazinski MF. Heartsaver AED for the Lay Rescuer and First Responder: Adult Cardiopulmonary Resuscitation and Automated External Defibrillation. Dallas: American Heart Association; 2002. p 4–11.
151. Cecchin F, et al. Accuracy of automatic external defibrillator analysis algorithm in young children. Circulation 1999; 100:I–663.
152. Hazinski MF, Walker C, Smith J, Deshpande J. Specificity of automatic external defibrillator (AED) rhythm analysis in pediatric tachyarrhythmias. Circulation 1997;96(Suppl I); I561.
153. Stapleton ER, Auferheide TP, Hazinski MF. BLS for Healthcare Providers. Dallas: American Heart Association; 2001. p 95–98.
154. Sirbaugh PE, et al. A prospective, population-based study of the demographics, epidemiology, management, and outcome of out-of-hospital pediatric cardiopulmonary arrest. Ann Emerg Med 1999;33:174–184.
155. Heartsaver CPR: A comprehensive course for the lay responder. Dallas: American Heart Association; 2000. p 101–107.
156. Hazinski MF, editor. PALS Provider Manual. Dallas: American Heart Association; 2002. p 64.
157. Fink JA, Klein RL. Complications of the Heimlich maneuver. J Pedatr Surg 1989;24:486–487.
158. Heartsaver CPR: A comprehensive course for the lay responder. Dallas: American Heart Association; 2000. p 101–107.
159. Heartsaver CPR: A comprehensive course for the lay responder. Dallas: American Heart Association; 2000. p 39.
160. Gordon T, Kannel WB, McGee D, Dawber TR. Death and coronary attacks in men after giving up cigarette smoking: a report from the Framingham Study. Lancet 1974;2:1345–1348.

161. US Dept of Health and Human Services. Reducing the Health Consequences of Smoking: 25 Years of Progress: A Report of the Surgeon General. US Dept of Health and Human Services, Public Health Service, Centers for Disease Control, Center for Chronic Disease Prevention and Health Promotion, Office on Smoking and Health. 1989. DHHS Publication (CDC); 89–8411.
162. McIntyre KM. Cardiopulmonary resuscitation and the ultimate coronary care unit. JAMA 1980;244:510–511.

See also CARDIAC OUTPUT, THERMODILUTION MEASUREMENT OF; RESPIRATORY MECHANICS AND GAS EXCHANGE; SHOCK, TREATMENT OF; VENTILATORS, ACUTE MEDICAL CARE; VENTILATORY MONITORING.

CARTILAGE AND MENISCUS, PROPERTIES OF

JEREMY J. MAO
ALEXANDER J. TROKEN
NICHOLAS W. MARION
University of Illinois
Chicago, Illinois
LEO Q. WAN
VAN C. MOW
Columbia University
New York, New York

INTRODUCTION

Synovial or diarthrodial joints are created to enable the movement between bones. Articular cartilage on the end of articulating bone, therefore, must accomplish two functions: (1) absorb, distribute, and transmit mechanical loading, and (2) create a low friction and wear surface for movement over decades of mammalian life. Three cartilage phenotypes exist: hyaline cartilage, fibrocartilage, and elastic cartilage. In the older literature, articular cartilage is often referred to as hyaline cartilage due to its glassy appearance; this appearance is derived from its high proteoglycan content. Indeed, articular cartilage has the highest proteoglycan content of all biological tissues, while, at the same time, it has the lowest cellular content. The chondrocytes not only secret and control collagen and proteoglycan contents in the extracellular matrix, but also are responsible for regulating the elaborate molecular architecture of these macromolecules and their ultrastructural organization (1–3). Throughout life, the healthy chondrocytes under normal conditions secrete and elaborate sufficient amounts of the extracellular matrix macromolecules and completely encase themselves in an environment that possesses truly remarkable biomechanical mechanisms that protect them against the mechanical insults associated with joint loading, and thus survive for long periods of time under normal health conditions (4–6).

Cartilage in a small number of joints in humans, such as the knee meniscus, temporo-mandibular joint, and intervertebral discs, is fibrocartilage. The intervertebral disc, besides its complex macromolecular architectural and ultrastructural organization, also has a complex macrostructural organization; the latter is manifested in the macro-layering of the outer rings of collagen-rich annulus fibrosis and an inner core of a proteoglycan-rich “kidney-shaped” nucleus pulposus. The cells of these fibrocartilaginous tissues are fibroblasts and chondrocytes, some of which are called fibrochondrocytes. Whereas the genotype and phenotype of cartilage cells determine the biochemical and molecular properties of cartilage, the mechanical properties of articular cartilage are largely dependent on the constituents of extracellular matrix (3). This divergence in the determination of biological and mechanical properties is attributed to the scarce cellularity in adult cartilage, with chondrocytes that account for only less than 10% of the adult cartilage volume (4,7). Comprehensive reviews of hyaline and fibrocartilage can be found elsewhere (1,3,8).

An average human takes approximately 2 million steps per year. The joints in the lower limbs, therefore, can undergo 1–4 million cyclic loads from physical activities (9,10). These loads can peak 4–5 times body weight (11,12), and can cause both macro- and micro-structural changes in articular cartilage that may ultimately lead to degenerative diseases such as osteoarthritis (4,7,13–15). Arthritis, which encompasses more than 100 diseases and conditions, is recognized as among the leading causes of physical disability worldwide (16). Thus, investigation of the properties of normal and arthritic cartilage is essential not only for the understanding of the etiology of arthritis (6), but also devising possible approaches toward the tissue engineering of cartilage and meniscus for clinical treatment modalities (17).

ARTICULAR CARTILAGE AND MENISCUS: COMPOSITION AND STRUCTURE

Chondrocytes and fibrochondrocytes are responsible for the morphogenesis, matrix synthesis, and maintenance of articular cartilage and meniscus as functional tissues. However, these cells only account for approximately 10% of the total cartilage volume in adults (3,7,18,19). Chondrocytes receive nutrients and shed metabolic waste products largely from convective transport and diffusion, either from/to the synovial fluid or from subchondral bone. In the adult, articular cartilage is generally aneural and avascular. Vasculature is present only in the periphery of mature meniscus (20).

Hyaline Cartilage and Articular Cartilage

Hyaline cartilage is present on the articulating surfaces of the bones in most, but not all, synovial joints. Articular cartilage serves to bear and distribute load and contribute to joint lubrication. It serves these different purposes through varying the amount of water relative to the amounts of Type I collagen and proteoglycans and the molecular and ultrastructural organizations of these structural molecules. Healthy articular cartilage appears smooth, bluish white, glistening, and intact. Osteoarthritic articular cartilage appears dull and coarse and may have tears and frays. Hyaline cartilage is also present in the growth plate at the metaphyseal region of long bones and in the cranial base and serves to enable longitudinal bone growth by endochondral ossification (21–23). A review of growth plate cartilage is beyond the scope of this chapter, but can be found elsewhere (24–26).

Articular cartilage has two immiscible phases—a solid phase and a fluid phase. Small electrolytes such as Na^+ and Cl^- are dissolved in the fluid phase and are freely mobile by diffusion and convection through the porous-permeable solid phase. The fluid and solid phases have been modeled in the now classic biphasic theory developed by Mow et al. (27). Normal fluid component ranges from 75 to 80% by wet weight, and the remaining 20 to 25% of the organic matrix forms solid material with complex material properties (3,18,19). Up to 65% of the solid ECM by dry weight is made of collagen, whereas proteoglycans constitute up to 25%; other glycoproteins, chondrocytes, and lipids can generally make up 10% (3,28,29). Collagen fibers are classified on the basis of their amino acid composition and molecular structure. Although an assortment of collagens exist in both hyaline cartilage and fibrocartilage, Type II collagen is most prevalent in articular cartilage, whereas Type I collagen is most common in the meniscus (3,30). The collagen fibers are assembled as tight triple-helical structures made from three polypeptide alpha-chains. The triple helices are then arranged as tropocollagen molecules, which are wound in a helical manner to form larger collagen fibers that are, in turn, are organized into a strong cohesive collagen network (3,31,32). This arrangement allows for considerable tensile stiffness and strength (33–38). The collagen also serves to restrain the swelling pressure created from the surrounding embedded proteoglycans (2,18,19,39). Proteoglycans (PGs) are hydrophilic macromolecules with numerous glycosaminoglycans (chondroitin and keratin sulfates) attached to a protein core; the protein core of this bottle-brush-shaped molecular is, in turn, attached to a hyaluronan (mw: molecular weight $\sim 0.5 \times 10^6$) resulting in a supra-macromolecule with an approximate molecular weight ranging from $(200 \text{ to } 300) \times 10^6$ (3,29,40–42). These enormous, negatively charged molecules are trapped in the fine porous meshwork of collagen by frictional and electrostatic forces and by steric exclusion; thus, in the ECM, PGs function largely to generate osmotic pressure (2,39) and to resist the compressive stresses of articulation acting on the cartilaginous surface. Although various PGs exist in cartilage, the one that constitutes up to 80–90% of the total PGs in cartilage is aggrecan (3). As the name implies, aggrecan facilitates the formation of large aggregates. Like collagen, aggrecan, as with all PGs, maintains a structure that is directly correlated with its function. The general structure of PGs occurs through noncovalent bonding of aggrecans to the hyaluronan via link proteins, thus securing firm linkages. Attached to the protein core are the glycosaminoglycan side chains (GAGs) that are vital for biological and biomechanical functions of the tissues; indeed, they are hallmarks of chondrogenic activity in tissue engineering. These GAGs bear the necessary physical properties that ultimately confer onto these tissues their hydrophyllic tendencies and compressive load-carriage abilities (3,18,19). The presence of large numbers of sulfate and carboxyl groups on the GAGs gives rise to a high negative-charge density in the ECM (2). This anionic nature attracts positively charged ions, creating an osmotic pressure, known as Donnan osmotic pressure, that favors tissue hydration (3,39,43). The fixed-negative charges also create intense repulsive forces of the GAGs against each other. This expansion force of the PG molecules causes tensile stresses to be developed within the surrounding collagen network surrounding the PGs. This swelling pressure thus resists the compressive forces against the cartilage without volume loss.

Articular cartilage is organized into three layers or zones (3,44) as shown in Fig. 1. The superficial zone forms the articular surface, whereas the deep zone is anchored to calcified cartilage and subchondral bone; both zones have well-defined collagen architectures. An intermediate zone exists in between with a random collagen fiber ultrastructural organization. These layered structural arrangements have long been hypothesized to be important in cartilage function (45–47). The overall thickness of articular cartilage, including the three zones, varies between joints, age, individuals, and species from less than a millimeter to a few millimeters, with the thickest being measured at the retro-surface of the human patella and femoral trochlea (3,13,48).

The superficial zone has the highest collagen, water content, and chondrocyte density, but the lowest proteoglycan content among all three zones (2,49–51). The abundant collagen fibrils are aligned parallel to the articular surface and provide the superficial zone with substantial tensile strength in an orthotropic manner (37,38,52,53). The chondrocytes in this zone are flattened and are apparently polarized to be parallel to the surface (Fig. 2a) (7,54). Recently, intricate 3D images have been taken to



Figure 1. Layered structure of cartilage collagen network showing three distinct regions (3).



Figure 2. (a) Articular cartilage from a mature rabbit femur showing typical zonal arrangement of chondrocytes (polished saw-cut of resin-embedded tissues, surface-stained with basic fuchsine and toluidine blue) (54). (b) Schema of chondrocyte organization in the superficial zone (SZ), middle zone (MZ), and deep zone (DZ) (7).

view the discoid-shaped cells as they are maintained in this layer. Methods have ranged from digital volumetric imaging (55) to atomic force microscopy (56).

The intermediate, or middle, zone is generally the thickest amongst the three uncalcified zones of articular cartilage. Collagen fibrils, although less dense, have a greater diameter than the superficial zone, but appear to be more randomly oriented (47,57). The intermediate zone also has the highest proteoglycan content (3). Chondrocytes are more rounded, although cell density is not as high as in the superficial zone (3,58) (Fig. 2b).

The deep zone is relatively thin and the collagen are intertwined to form larger fiber bundles, and, from this zone, they insert perpendicularly into the calcified zone, and thus anchor the uncalcified tissue to the bony ends as required by joint articulation. This organization allows the bundles to firmly anchor the articular cartilage to the underlying subchondral bone. In general, chondrocyte density decreases from the middle zone to the deep zone, where they are similarly aligned as the collagen bundles, arranging into columns perpendicular to the uncalcified-calcified cartilage intersurface (3,55).

Several recent studies have investigated the pericellular matrix (PCM) and the interterritorial matrix (ITM) of chondrocytes. Using algorithms to account for fluid flow and differences in the relative stiffness between the PCM, the ITM, and the chondrocyte, different elastic moduli between PCM and ITM have been found to have a significant effect on chondrocyte's mechanical environment (59). Gradient distributions of charges and material densities relative to chondrocyte surface are important in cartilage fluid flow dynamics and deformation behavior (60). Using micropipette isolation of chondrocytes and nuclei, chondrocyte nuclei have been found to be stiffer than intact chondrocytes (59,61,62). Cultured chondrocytes are able to elaborate a PCM rich in Type VI collagen; however, intact chondron pellets accumulate significantly more proteoglycans and Type II collagen than chondrocytes without a native PCM (63). Following a few weeks of accumulation of the ITM and PCM by isolated chondrocytes, a rapid increase in compressive stiffness occurs in both the chondron and the chondrocyte pellets (63). Using atomic force microscopy (AFM), the ITM is found to be stiffer to nanoindentation than the PCM (Figs. 3a and 3b) (64).



Figure 3. A representative height map of the PCM and ITM chondrocytes obtained through force mode of atomic force microscopy. Qualitatively, the ITM showed greater peak and valley contours than the topographic contour of the PCM (a). (b) presents the average Young's moduli of the PCM and ITM attained via nanoindentation. The average Young's modulus of the ITM (636.1 ± 124.91 kPa) was significantly greater than the PCM (265.1 ± 52.76 kPa) ($p < 0.01$) ($N = 19$) (64).

Meniscus and Fibrocartilage

The meniscus in the knee joint is a fibrocartilage. The two menisci (lateral and medial) in each knee joint are crescent or semi-lunar shaped and are attached to the joint capsule. The triangular cross section of the meniscus tapers radially inward from the periphery, and the center of the meniscus is thin and unattached. Thus, the cross section of the meniscus is wedge-shaped. The central region is a vascular and has more proteoglycans, hence more hyaline in appearance. The anterior and posterior horns of the meniscus form the tips of the crescents. The anterior horn of the lateral meniscus is attached to the tibia in front of the intercondylar eminence, partially blending with the anterior cruciate ligament. The posterior horn is attached to the tibia near the intercondylar eminence as well as to the femur via the meniscofemoral ligament. The anterior and posterior horns of the medial meniscus are attached to the tibia near their respective intercondylar fossae. The anterior horns of the lateral and medial menisci are connected by the transverse ligament. The thick peripheral borders and associated horns of the meniscus are vascularized by blood supply predominantly from the genicular arteries surrounding the joint. The thinner central portions of the meniscus are aneural and avascular, a region very much like hyaline cartilage (20). The meniscus is lubricated with synovial fluid (65), probably by the same lubrication mechanisms known to exist in articular cartilage (66). Fibrocartilage is found in a small number of other joints. The disk of the temporomandibular joint (TMJ) and the intervertebral disks are both composed of fibrocartilage, although they are drastically different structures with different distributions of cartilage and PGs and ultrastructual organization.

The fibrocartilagenous structure of the meniscus differs from that of hyaline cartilage in many ways. The cells of the meniscus are sometimes called fibrochondrocytes, although it is probable that some cells are more like fibroblasts, whereas others are more like chondrocytes (65,67). The peripheral two-thirds of the meniscus are primarily composed of a randomly oriented mesh-like, coarse, collagen fibrillar matrix (68–71). In deeper portions, large rope-like collagen fiber bundles are arranged circumferentially, retaining the overall semi-lunar shape of the meniscus and providing tensile strength. Smaller fibers are also found radially and connect to the larger circumferential collagen fiber bundles (72). As mentioned above, the inner portion of the meniscus resembles that of hyaline cartilage, containing a higher percentage of proteoglycans enmeshed within a randomly arranged collagen fibrillar matrix (71,73,74).

The function of the meniscus is to enhance higher congruity of the articulating surfaces of the distal femur and proximal tibia, to accommodate the range of motion, in addition to the same functions of load bearing and load distribution to that of articular cartilage (20). The previous assumption that the menisci are functionless, evolutionary remains of leg muscles is erroneous and that menisectomy (a common clinical procedure) is indeed a common procedure in animal models to study the etiology of osteoarthritis (75–78).

CARTILAGE AND MENISCUS: MECHANICAL PROPERTIES

Articular cartilage and meniscus are both important load-bearing tissues and vital to the maintenance of normal joint functions (3,18,19). Articular cartilage can absorb mechanical shock of joint motion and spread the applied load onto the subchondral bone. It also contributes to the lubrication mechanism and provides a surface with low friction, enabling repetitive gliding motion between articulating surfaces (7,66). The meniscus of the knee has important biomechanical functions such as load transmission at the otherwise highly incongruent tibiofemoral articulation, shock absorption, joint congruity, and stability (18,19). The salient biomechanical functions of articular cartilage and meniscus are dependent on their biological structure, composition, and the intrinsic material properties of the ECM. The knowledge of their material properties such as tensile, compressive, and shear moduli is essential to understand not only their biomechanical functions, but also in the tissue engineering of articular cartilage and meniscus to produce in a biomimetic manner artificial-biological replacements (17,79).

Tensile Properties

When cartilage is tensed, the tensile stress-strain behavior is nonlinear. A typical nonlinear stress-strain (σ-ϵ) curve for cartilage, meniscus, and other soft tissues is depicted in Fig. 4 (3). For small deformations, a ‘toe-region’ is seen in the stress-strain curve, in which the collagen fibrils will primarily realign in the direction of the externally applied force instead of being stretched (elongation per unit length). For larger deformations, the collagen fibrils are stretched, and a larger tensile stress is generated within the collagen fibers (e.g., 35–38,52,53,80–83). In this linear region, the stress is proportional to the applied strain, and their ratio is known as Young’s modulus in tension, or tensile modulus. This tensile modulus is a measure of the stiffness of the collagen-PG solid matrix and is primarily dependent on the density of collagen fibrils, fibril diameter, and type or amount of collagen cross-linking (3,18,19,52). Beyond the linear region, the cartilage strip will rupture abruptly, and the tensile failure stress is a measure of the strength of the collagen fibrillar network.

In general, the tensile modulus of articular cartilage will be in a range of 1–30 MPa, which is much larger than the compressive modulus of cartilage ($\sim$0.5 MPa), which is known as tension-compression nonlinear property of the



Figure 4. Typical stress-strain curve for articular cartilage and meniscus in a uniaxial and uniform strain rate experiment. The toe region is marked by an increasing slope, whereas the linear region appears to be a straight line (3).

cartilage (84–86). The tensile properties are also known to vary with location, depth, and orientation of test specimens of cartilage and meniscus. Hultkrantz (45) demonstrated the anisotropic organization of the collagen network by puncturing holes in the surface of articular cartilage with a round pin. He found that round puncture holes will form elongated splits, analogous to splits formed in lumber when a large round awl pierces it. The split-line patterns were, to him, evidence of collagen fiber orientation, which is still an enigma today because electron microscopy has not found such surface collagen anisotropy. (Nevertheless, the pattern of split lines is similar to Langer lines formed in the skin in a similar manner.) Much later, Woo et al. (38), Kempson et al. (52), and Roth and Mow (37) showed that the tensile strength and stiffness of the samples cut parallel to the split-line direction were higher than those cut perpendicular to it. The cartilage strips from high weight-bearing areas of human knee joints exhibit larger tensile modulus than those from low weight-bearing areas (53,82) because high weight-bearing areas generally have a relatively higher proteoglycan content. The adult human femoral articular cartilage exhibits a gradual decrease in tensile strength and stiffness as the distance from the articular surface increases (36,81), while this functional dependence was not observed for young bovine humeral joints (38). A dependency of cartilage tensile properties with skeletal maturation was found by Roth and Mow (37). These investigators found that, with the closing of the growth plate (indicative of skeletal maturity), the strength and stiffness of cartilage are much less that those properties of immature cartilage (open-physis). The effects of age on the tensile properties of adult cartilage were extensively studied by Kempson (81), and the results showed that the tensile modulus decreases with age, and that the modulus of the hip cartilage decreases more markedly than that of ankle cartilage. This finding may explain the relatively high occurrence of osteoarthritis in the hip compared with the ankle. Like articular cartilage, the tensile properties of meniscus vary with respect to the location (anterior, central, and posterior) and specimen orientation relative to the predominant collagen fiber direction (circumferential and radial) (18,19,74). Specimens from the posterior half of the medial meniscus have been shown to be significantly less stiff and less strong in tension than specimens from all other regions (87). This experimental result agrees with the ultrastructural findings using polarized light; In the posterior half of the medial meniscus, collagen fiber bundles have significantly reduced circumferential organization (87).

Numerous experiments have shown that the tensile modulus is correlated with the collagen content or the ratio of collagen content to proteoglycan content in articular cartilage (e.g., 82). The tensile modulus of articular cartilage decreases to only 1% after disruption of collagen cross-linking by elastase (88). In contrast, no significant correlations have been found between the tensile property of the cartilage and proteoglycan content (36,89). These findings indicate that collagen content, organization, and cross-linking play significant roles in generating high tensile modulus of articular cartilage. For meniscus, although the tensile properties show significant regional and directional variations, little difference appeared in the biochemical composition with site, and no significant correlation exists between tensile property and chemical contents (74). The variation of tensile properties seems to reflect local differences in collagen ultrastructure and fiber bundle direction as described above.

Compressive Properties

The compressive behavior of cartilage and meniscus has been extensively studied under various configurations, such as confined compression, unconfined compression, and indentation (see Fig. 5). Most of the earliest studies (e.g., 90–94) used the indentation technique to determine the mechanical property of articular cartilage and modeled the cartilage to be a single-phase, elastic body with the assumption of the Poisson's ratio ranging between 0.4 and 0.5 (e.g., 91–96). However, this single-phase elastic model cannot describe the time-dependent viscoelastic behavior of the tissue nor the role played by cartilage's major component (i.e., water). Cartilage and meniscus exhibit a viscoelastic creep in response to a constant load (i.e., its deformation will increase with time). Conversely, if a constant displacement is applied, the force response will decrease gradually with time to a constant value (i.e., a stress-relaxation will be observed).

These viscoelastic behaviors derive from the friction of water flowing through solid matrix (27,97), as well as the flow-independent intrinsic energy dissipation inside the macromolecular solid matrix during mechanical loading (98–101). As mentioned, articular cartilage and meniscus can be regarded as biphasic materials: a fluid phase composed of water and electrolytes, and a solid phase mainly composed of collagen and proteoglycans (27). The solid matrix is considered as being porous and permeable. Water resides in the microscopic pores and flows through the matrix during joint loading. Under a slow ramp loading, the observed viscoelastic behaviors are usually dominated by the large drag forces generated by the flow of interstitial fluid through the porous-permeable solid matrix, and therefore, the flow-independent intrinsic energy dissipation is negligible. However, osteoarthritic cartilage has higher permeability and lower ECM stiffness; in such tissues, the intrinsic viscoelastic behavior becomes the dominating component governing their mechanical behaviors.

The transient behavior of the tissue under compression is primarily determined by the mechanism of fluid pressurization because of high friction between solid and fluid phases, which is also known as flow-dependent viscoelastic behavior (27). Figure 6 (3) shows the stress-relaxation behavior of a tissue specimen under confined compression. In this experiment, before time t_0, the tissue is compressed with a constant rate, and the interstitial fluid inside the tissue will be pushed out through upper porous platen. As a result of the distributive fluid drag force, a larger deformation can be seen at the downstream side (Fig. 6a and 6b). During the relaxation phase (after t_0), no fluid exudation occurs, but the fluid needs to redistribute inside the tissue before the equilibrium is reached (Figs. 6c, 6d, and 6e). Although the velocity of fluid flow is very low, the friction force, or the drag force, could be very large because the pore


Applied load
Saline solution
Porous platen
Tissue sample
Container
(a)
Applied load
Saline solution
Impermeable platen
Tissue sample
Container
(b)
Applied load
Articular cartilage
Porous indenter
Subchondral bone
(c)

Figure 5. Schema of three configurations frequently used to study the compressive properties of articular cartilage. (a) In the confined compression configuration, a load is applied to the cartilage sample via a rigid porous permeable platen. The side walls are assumed to smooth, impermeable, and rigid, thereby preventing lateral expansion and fluid flow. (b) In the unconfined compression configuration, the cartilage sample is compressed between two rigid, smooth, and impermeable platens. The lateral side allows fluid flow. (c) In the indentation configuration, the cartilage is compressed via a rigid porous permeable indenter. The porous indenter allows the fluid exudation to occur freely into the indenter tip and, therefore, creep of the cartilage layer.


Unloaded
Fluid Efflux and Solid Matrix Compaction
Fluid Redistribution
Equilibrium
O
A
B
C
D
E
Displacement
ε_0
B C D E
A
O
t_0
TIME
Stress
σ_f
B
C
Flow-dependent Stress Relaxation
E
D
A
Equilibrium Stress
O
TIME

Figure 6. A schematic representation of fluid exudation and redistribution within cartilage during a rate-controlled confined compression stress-relaxation test (lower left). The horizontal bars in the upper figures. indicate the distribution of strain in the tissue. The lower graph (right) shows the stress response during the compression phase (O, A, B) and relaxation phase (B, C, D, E) (3).

size inside the tissue is very small ($\sim$ 50–65 nm for articular cartilage), and the permeability of the tissue is as low as 10^{-15} N·s/m^4. Therefore, the generated fluid pressure can be remarkably high inside the tissue during the transient state, which also means that chondrocytes encased within the ECM will normally be bathed in a highly pressurized fluid. It has been estimated that this fluid pressure could be 30 times more than the elastic stress generated in the solid matrix of articular cartilage (3). Considering that the equilibration process usually takes several hours, no real equilibrium state occurs in joints under physiological conditions because the joints are moving virtually at all times, even during sleep. Thus, the mechanism for fluid pressurization is likely to be the major physiological load-supporting mechanism in diarthroidal joints, and it plays an important role in shielding the solid matrix from large compressive stresses during the joint function (7).

At equilibrium, the fluid flow stops, no fluid pressure gradient exists inside the tissue, and the applied load is entirely supported by the solid matrix of the tissue. Thus, the compressive property can be obtained from the relations between stress and strain. It has been found that the equilibrium strain is proportional to the applied load. Typically, the equilibrium aggregate modulus (27) for normal articular cartilage ranges from 0.4 to 1.5 MPa, whereas the average equilibrium aggregate modulus for the meniscus is about 0.4 MPa. Table 1 shows the equilibrium aggregate moduli of lateral condyle and patellar groove cartilage and meniscus, showing considerable variation among the species and tissue location (3).

Tissue mechanical properties are highly dependent on their composition and structure. It has been shown that the equilibrium aggregate modulus for human articular cartilage correlates in an inverse manner with water content and in a direct manner with PG content (27,102,103). The highly loaded regions of articular cartilage generally have larger compressive modulus and greater PG content (53,104,105). In contrast, no correlation is found between the compressive stiffness and collagen content. Removal of PGs from articular cartilage samples dramatically decreases the compressive modulus, whereas trypsin

Table 1. Equilibrium Aggregate Modulus of Lateral Condyle, Patellar Groove Cartilage and Meniscus (MPa) (3)

	Human[a]	Bovine[b]	Canine[c]	Monkey[d]	Rabbit[e]
Lateral condyle	0.70	0.89	0.60	0.78	0.54
Patellar groove	0.53	0.47	0.55	0.52	0.51
Meniscus	NA	0.41	NA	NA	NA

[a] Young normal.
[b] 18 months to 2 years old.
[c] Mature beagles and greyhounds.
[d] Mature cynomologus monkeys.
[e] Mature New Zealand white rabbits.
[f] Not available.

digestion of collagen fibrils has little effect on compressive modulus (80,106).

The biphasic theory has been the most successful model for the compressive viscoelastic behaviors of cartilage and meniscus under various conditions (27). This theory assumes that (1) the solid matrix and interstitial fluid are immiscible and incompressible; (2) viscous dissipation is due to the fluid flow between water and the porous-permeable solid matrix; and (3) the frictional drag is proportional to the relative velocity and can be affected by ECM compression. This biphasic theory further assumes that the solid matrix experiences infinitesimal strain and that the stress-strain relations can be described by the generalized Hooke's law. Despite its simplification, as biological models typically are, the isotropic form of the linear biphasic theory has been shown to provide an accurate description of the compressive creep and stress relaxation behavior of these tissues. In particular, a numerical algorithm based on this biphasic theory was developed and accurately predicted the aggregate modulus, Poisson's ratio, and permeability of articular cartilage from the indentation creep experiment (13,100,107). The biphasic theory has also been extended by employing higher levels of tissue complexities, including material inhomogeneities (108–110), material symmetries (33,34,85,86,111), and matrix viscoelasticities (33,34,84,98–100).

Shear Properties

The intrinsic viscoelastic properties of the solid matrix of cartilage and meniscus can only be determined in a *pure* shear experiment and under small strain conditions. In pure shear, the kinematics of deformation does not permit volumetric change, and hence, no interstitial fluid flow is possible when no pressure gradients are applied. Under these three conditions, the tissue deforms without change in volume, and therefore, the interstitial fluid pressure and fluid flow are minimal. As a result, the flow-dependent viscoelastic properties are excluded, and the measured physical parameters will be independent on the friction or drag force between fluid phase and solid phase, which often occurs in compressive configurations, thus directly reflecting the intrinsic viscoelastic property of solid matrix. This flow-independent viscoelastic behavior of the collagen-PG matrix derives from the internal friction between collagen and PG molecules (3,101).

The first shear properties measurement was reported by Hayes and Mockros (112), and later, nonlinear viscoelastic and fatigue properties of bovine articular cartilage were investigated (113,114). However, all these tests were performed in a simple shear configuration, and dynamic shear properties of these studies were reported at frequencies (e.g., 20–1000 Hz) much higher than the physiological range (e.g., 1 Hz). Pure shear tests of articular cartilage and meniscus have been performed under transient, equilibrium, and dynamic conditions to characterize the intrinsic or flow-independent viscoelastic behavior (e.g., (101,115–117)). When a circular cartilage specimen is subject to a sudden change of angular displacement, the shear stress will increase instantaneously, followed by a rapid decay before equilibrium is reached. The quasilinear viscoelastic theory (118) has been shown to provide an excellent description of this intrinsic stress-relaxation behavior of normal human patellar cartilage (116). The equilibrium shear modulus for normal human, bovine, and canine articular cartilage has been found to vary in a range of 0.05–0.25 MPa. Values for the magnitude of the dynamic shear modulus $|G^*|$ of normal cartilage are in the range of 0.2–20 MPa and vary with both the frequency and magnitude of the normal stress. The phase shift angle (δ) for cartilage lies between 9° and 20° over a frequency range of 0.01 Hz to 20 Hz (101). Please note that δ is a measure of matrix dissipation, with a loss angle of 0° corresponding to a perfectly elastic material, and 90° to a perfectly dissipative material. The viscoelasticity of meniscus in response to shear is qualitatively similar to that exhibited by articular cartilage, although the magnitudes of the material coefficients of these tissues are significantly different. Meniscus shear properties exhibit an orthotropic symmetry (i.e., the three planes of symmetry defined by its fibrous architecture dominate the shear properties of the meniscus). The equilibrium shear moduli are 36.8 kPa, 29.8 kPa, and 21.4 kPa in the circumferential, axial, and radial directions, respectively (18,19,119). These shear modulus values are ten times less than those observed for articular cartilage. For dynamic tests, the magnitude of the complex shear modulus $|G^*|$ and phase shift angle δ for circumferential, axial, and radial specimens reflect orthotropic collagen fiber organizational symmetry as well (Fig. 7) (3).

The collagen network plays an active mechanical role in contributing to the shear stiffness and energy storage in cartilage (101). Conceptually, the role played by collagen when the specimen is in shear may be visualized as shown in Fig. 8 (101). The tension in the diagonally oriented collagen acts to increase the shear stiffness of the solid matrix. This effect is confirmed by the experimental result that $|G^*|$ is directly and significantly related to the collagen content of articular cartilage and also by the fact that



Figure 7. The magnitude of dynamic shear modulus $|G^*|$ and tan δ for meniscal specimens with normal vectors oriented circumferentially, axially, and radially at 1 rad/s (3).

cartilage has a relatively small loss angle and large shear modulus (101) compared with that of PG solutions at physiological concentrations (107,120,121). The depletion of the PG content has been shown to decrease the dynamic shear modulus up to 55% (101,122), which is considered as a result of the decrease of tensile stress inside the collagen fibrils due to the decrease of PG swelling pressure.

Swelling Properties

Swelling in articular cartilage derives from the presence of negatively charged groups (SO_3^- and COO^-) along the GAG chains of PG molecules. For normal and degenerative femoral head cartilage, the fixed-charge density (FCD) ranges from 0.04 to 0.18 mEq/g wet tissue at physiological pH (2,123). These fixed charges will require a high concentration of counter-ions (Na^+) to maintain electroneutrality, and the concentration, along with that of co-ions (Cl^-), is governed by the Donnan equilibrium ion distribution law (124). This excess of freely mobile ions will introduce an imbalance of ion concentration between the fluid compartment inside the tissue and the bathing fluid outside the tissue, giving rise to a higher pressure in the interstitial fluid than the ambient pressure in the external bath, known as the Donnan osmotic pressure. This osmotic pressure decreases with FCD and has a range of 0.1 to 0.25 MPa for normal articular cartilage. With the increase of the external saline concentration, the osmotic pressure will decrease. For the very large external saline concentration (e.g., 2 M), the osmotic pressure is considered to be extremely small, or zero.



Figure 8. A scheme representation of cartilage in pure shear. The tensile stress inside collagen fibrils provides shear stiffness (101).

This osmotic pressure causes the tissue to swell, as measured by both weight change (2,123) and dimensional change (125,126). These latter experimental results show that the swelling of articular cartilage is inhomogeneous and anisotropic. The swelling ability increases with depth, with the largest dimensional change for the deep zone and almost no change for the superficial layer. The magnitude of swelling is the largest in the thickness direction and the smallest in the split-line direction. In articular cartilage, the osmotic pressure is restrained by the surrounding collagen network. Therefore, residual stress or pre-stress exists inside the solid matrix even before external load is applied. Articular cartilage will warp or curl toward its articular surface upon its removal from the subchondral bone, and the curvature or the extent of curling will decrease with the increase of external saline concentration (126). It has been hypothesized that this curling is caused by the combination effects of swelling pressure and inhomogeneity inside the tissue (126–129). Recently, a three-layer orthotropic model based on triphasic theory (39) has been developed to describe the curling behavior of cartilage strip by considering its layered structure that includes depth-dependent collagen fibril orientation and chemical content distributions (128). The predicted curvature change with external saline concentration agrees well with previously published experimental results. This model has also suggested that the large stiffness of the superficial layer and high swelling pressures play key functional roles in the development of pre-stress in cartilage and in its curling behavior.

Quantification of morphological changes has been extensively used to study changes in cartilage swelling with osteoarthritis (OA) (44). With OA, compositional and microstructural changes will occur, which includes the fibrillation of the superficial zone of articular cartilage, the decrease of the PG concentration, and the imbibitions of water; these items are the earliest indicators of the OA degeneration of cartilage (18,19,29,102). The elevated water content or swelling has been shown to be very sensitive to collagen fibrillation. Experimental results also suggest that the water content of the tissue increases after digestion with collagenase (82,83,101). Physically, collagen fibrillation decreases the stiffness of the solid matrix, specifically the elastic bulk modulus, which allows the tissue to imbibe more water (52,104).

Triphasic Mixture Theory

To account for the swelling behavior, Donnan osmotic effects, ion transport, and electrical potentials inside the tissue, Lai et al. (39) developed the triphasic theory to incorporate the effects of negatively charged groups on the PGs of solid matrix. In this theory, the electrolytes (mainly Na^+ and Cl^-) within the interstitial fluid are considered as a separate phase, and the solid phase is charged. This triphasic theory was further extended to account for multiple species of ions in the tissue (130). Note that Huyghe and Janssen (131) developed an equivalent theory, named the quadriphasic theory, in which ion species Na^+ and Cl^- were treated as two separate phases.

Using the triphasic theory, the electrokinetic coefficients such as electrical conductivity has also been derived in terms of the physical parameters of charged tissues (39,130,132–134). Furthermore, a theoretical analysis (134,135) showed that the electrical potential inside the tissue comes from two competing sources: a diffusion potential deriving from the FCD inhomogeneity and a streaming potential resulting from the fluid flow within a charged material. These two sources of electrical potential have different polarity and compete against each other. Within the physiological range of material properties of articular cartilage, the polarity of electrical potential inside the tissue depends on the stiffness of the tissue. For softer tissues (such as OA tissue), the diffusion potential tends to dominate, whereas the streaming potential tends to dominate for stiffer tissues (such as normal tissue).

Numerical methods, such as finite difference and finite element formulations, have been developed to demonstrate the contributions of the FCD in mechano-electrochemical (MEC) behaviors of charged, hydrated soft tissues (43,134,136,137). These studies showed that that higher FCD decreases the characteristic time (gel time) and causes the tissue to reach equilibrium in a shorter amount of time, and showed that the osmotic effects can contribute up to 50% of the equilibrium confined compression stiffness (136) and about 30% in unconfined compression (43). With the finite element formation, Lu et al. (138) successfully correlated the predicted FCD with the biochemical measurements, while simultaneously measuring the apparent mechanical properties from the indentation creep experiment.

Recently, the triphasic formulations have been linearized, and the analytic solutions for the MEC response of the tissue under unconfined compression have been obtained both for transient state and at equilibrium (139). With a regular perturbation, simple relations have been derived to describe how the apparent properties, such as Young's modulus and Poisson's ratio, change with the fixed negative-charge density (FCD) at equilibrium (139,140). These relations actually are applicable to various testing configurations, even for steady permeation, and they indicate the correspondence of mechanical properties between an elastic body and a charged triphasic material such as articular cartilage and meniscus (139–142).

CARTILAGE WEAR AND DEGENERATION

Cartilage wear and degeneration have been extensively studied due to their significant roles in physically debilitating diseases such as osteoarthritis and rheumatoid arthritis (1). Two types of wear occur in synovial joints: fatigue wear and interfacial wear (66). Fatigue wear is independent of the lubrication within the joint and is caused by functional activities such as cyclic, repetitive loading. A balance is presumably maintained under the normal physiological condition whereby tissue turnover is maintained by cells in various components of the synovial joint. A number of factors may contribute to cartilage wear and degeneration. Collagen fibers can be severed by excessive functional activities, leading to a compromise in tensile strength. The normally tight collagen fiber bundles can be unwound and loosened (47,143). When inflammatory cytokines are released, proteoglycans are lost rapidly, leading to a breakdown of the ECM (144–146). Fibrillated cartilage from osteoarthritic patients shows an increase of apoptotic chondrocytes deeper than in the normal articular cartilage, which generally has apoptotic cells only near the surface (145,147). Collective loss of chondrocyte and ECM may lead to microcracks and fissures, which may further grow with functional loading. Thus, fatigue wear of cartilage is a mechanism dependent on biological synthesis and mechanical loading (5).

Interfacial wear can result from physical contact loading of articulating surfaces. Interfacial wear has been categorized into two classes: adhesive and abrasive wear (66). Adhesive wear is more common and occurs when a junction is created when the two solids are in contact. As the opposing surfaces continue to move past the junction, fragments from the weaker surface may be torn off and adhere to the stronger material. The concept is analogous to rubber skid marks left on a road from a braking car. The car is able to move past the formed junction only by having elements of the weaker material, the rubber tire, come off and adhere to the stronger material, which is, in this case, the road. Abrasive wear occurs when a harder material comes into contact with a softer material. No junction is formed. While in contact and rubbing against each other, the harder material cuts or plows into the softer material. The harder material can be either one of the opposing surfaces or loose particles caught between two softer opposing surfaces, cutting into both of them (66).

Pain, stiffness, swelling, and reduced range of motion are the common phenotypic characteristics of osteoarthrosis. Typically, clinical diagnosis is only made after significant cartilage deterioration. A number of methods have been formed to monitor the development of osteoarthrosis. Radiography has been the conventional method for both diagnosis and monitoring. The topographical variation in degenerative cartilage has been used in designing an arthroscopic indentation instrument in which osteoarthrosis could be diagnosed *in vivo* and possibly treated before the diminishing qualities of the disease (148). Other manners that have been proposed for detection are chondrocalcin measurement (149) and knee wear particle analysis, which is derived from the concept of abrasive wear (150).

CURRENT CARTILAGE REPAIR STRATEGIES

Cartilage's poor capacity for self-regeneration is well known. The poor regenerative capacity of cartilage has been contrasted to bone, because bone readily regenerates (unless it is a critical size bone defect) and has a relatively rich blood supply (151). A lack of angiogenesis has been cited as the primary cause for cartilage's poor capacity for regeneration. However, normal cartilage is avascular. Vascular supply to cartilage likely will turn it into bone. Thus, a lack of vascularization is not the direct cause for cartilage's poor regenerative capacity (152).

The regenerative ability of cartilage in response to injury also depends on factors such as joint loading, the degree of injury, the location of injury, and whether it is cartilage lesion alone or osteochondral lesion (153,154). Cartilage responds differently to slowly or rapidly applied loads. For example, loading causes fluid movement in the matrix and may serve to counteract the deformation and to distribute the loads throughout the tissue. However, rapid compressive loading may not allow the fluid to infuse matrix, thus transferring excessive loading to the cells and the ECM macromolecules. Should excessive force be sustained, the chondrocytes and ECM molecules may undergo rupture or degradation. Another factor in determining the cartilage's regenerative capability is the chondrocytes' intrinsic ability to replenish the supply of matrix molecules, as well as the approaches to remove degraded materials (17,153,155).

Articular cartilage injuries can be classified as follows: (1) cartilage matrix and cell injuries without substantial tissue defects; (2) defects, fissures, or ruptures in articular cartilage only; and (3) osteochondral lesions. The first category of cartilage injuries without substantial tissue defects, nonetheless, is associated with a decreased concentration of matrix macromolecules such as PGs and collagen. Albeit without tissue-level defects, loss of PGs and collagen results in a decrease in mechanical strength. Unless repaired, even the first category of cartilage injuries can lead to more substantial defects as described in the second and third categories (153,155).

The second category of articular cartilage injuries is localized within cartilage. They include focused mechanical disruption of the matrix including fissures, tears, incisions, or interruption of the integrity of articular surface. Chondrocytes not only attempt to replace the loss of matrix macromolecules but also proliferate to fill the voids created during injury (153,156). However, the rates of chondrocyte proliferation and matrix synthesis may not be sufficiently high to match the rate of cartilage degradation. As articular cartilage has no nerve supply, except at the very periphery, even substantial cartilage lesions may not elicit pain. A few types of synovial joint injuries likely exist that elicit pain, such as osteochondral injuries, synovial membrane injuries, and injuries to the periphery of articular cartilage. These injuries are usually not repaired by the articular chondrocytes (4).

The third category is osteochondral injuries that involve both articular cartilage and subchondral bone and elicit inflammatory responses such as an influx of blood-borne cells, platelets, and cytokines. Hemorrhaging or fibrin clot formation may occur and later develop into a fibrous mass. The influx of cytokines may induce migration of progenitor cells, although no guarantee exists that these progenitor cells, likely mesenchymal stem cells that are capable of differentiating into all connective tissue lineage cells, will differentiate into chondrocytes. In fact, osteochondral lesions are likely repaired, if reparable, by fibrocartilage or fibrous tissue instead of hyaline cartilage (154), and rarely possess the complex zonal structures of native articular cartilage (153,157). The mechanical strength of fibrocartilage is approximately one-third of the strength of native hyaline articular cartilage, and thus may not be able to fulfill the weight-bearing and load-bearing functions of normal articular cartilage. Over time, osteochondral lesions may undergo further degradation, leading to the exposure of subchondral bone, which results in osteoarthrosis and can lead to joint immobility.

Current clinical treatments for articular cartilage injuries have several deficiencies. Depending on the degree of injury and whether the defect is partial- or full-thickness, the treatments generally involve surgical irrigation, debridement, and tissue augmentation. Partial thickness injuries of the articular cartilage involving clefts and fissures, often in the early stages of osteoarthrosis, are most commonly treated with arthroscopic surgery such as lavage or debridement. Arthroscopic lavage involves the irrigation of the joint, whereas debridement is the arthroscopic removal of damaged tissue. By performing these treatments either alone or in combination, a decrease in joint pain usually results. However, lavage or debridement treatments rarely induce the repair process of cartilage (155,157).

Full-thickness injuries refer to lesions in both articular cartilage and subchondral bone. Although a large number of treatments are empirical, several procedures have taken the advantage to simulate the native repair process. Arthroscopic treatments such as abrasion arthroplasty, Pridie drilling, and microfracture are commonly used, and all include the further perforation of the subchondral bone to induce bleeding and further fibrous tissue formation. Abrasion arthroplasty and microfracture are used in conjunction with debridement to reduce the amount of damaged tissue within the joint. The outcome of these treatments is variable, largely because the healing and repair process within the articular surface are somewhat unpredictable. Furthermore, factors such as the patient's age, postoperative activity level, and overall heath also affect the outcome (158).

Recently, soft tissue grafts such as the transplantation of the periosteum or perichondrium have been used clinically to repair the articular surface for cylindrical, full-thickness defects. The rationale for using periosteum is its observed chondrogenic potential during development and fracture repair (159). The periosteum consists of a fibrous and cambial layer. The cambial layer contains precursor cells that are capable of differentiating into osteoblasts and perhaps chondrocytes. The process of periosteum transplantation involves the creation of a defect spanning the full thickness of articular cartilage and penetrating the subchondral bone, and then placement of the periosteum graft within the defect. However, much debate has occured as to which layer of the periosteum should lay adjacent to the bone and which layer should face the articular surface, as the cambial layer can form cartilage, whereas the fibrous layer forms fibrous tissue. Larger full-thickness defects are generally repaired using allogenic or autogenic osteochondral tissue plugs, called mosaicplasty, excised from nonload-bearing regions of the joint and inserted into the full-thickness defect. Reports exist of fibrous tissue formation and chondrocyte death at the interface between the plug and surrounding tissue, which may lead to further degeneration of the joint. Furthermore, donor site morbidity remains a drawback of the periosteum graft or mosaicplasty (160).

For substantial osteochondral lesions, total joint replacement using metallic condyle and plastic socket is most commonly in practice. Current modalities of total joint replacements suffer from drawbacks such as donor site morbidity, pathogen transmission, wear and tear, and a limited life span (161). Secondary surgeries are necessary in 10–15% of the cases and suffer from substantial difficulties such as scar tissue formation and loss of host tissue (162). More importantly, current total joint replacement therapies fail to yield biological regeneration.

CURRENT MENISCAL REPAIR STRATEGIES

Prior to the recognition of the importance of the meniscus in the biomechanics of the knee joint in the 1970s, the preferred treatment for meniscal injury such as tear was total excision of the meniscus or open meniscectomy. Despite some reports of temporary relief of symptoms, the long-term outcome of excision or meniscectomy was poor. In the 1980s, understanding of the material properties and biomechanical roles of the meniscus led to more conservative treatments for meniscal tears. Furthermore, the development of arthroscopy enabled more accurate diagnosis of meniscal tears and, subsequently, more precise surgical treatment that has substantially reduced the amount of damage to the surrounding tissue in comparison with open-joint surgery (163).

Partial-thickness split tears and small (< 5 mm) full-thickness split tears, vertically or obliquely, are usually left alone and without surgical intervention. The inner wall of the meniscus must be stable during probing, which is commonly performed arthroscopically during diagnosis. Follow-up arthroscopic examinations are often necessary to monitor tissue healing. These injuries are usually associated with ligament tears such as the anterior cruciate ligament (ACL). Ligament tears in conjunction with meniscal tears drastically reduce the stability of the knee and can lead to further meniscal damage.

Meniscal injuries that require surgical repair or excision are large defects with compromised vascular supply, large meniscal deformations, or damage to the peripheral or circumferential collagen fibers. In need of excision, it is preferable to leave a partial meniscus intact as opposed to full meniscectomy. The surgical approaches are either open-joint surgeries or arthroscopic surgery to suture tears within the meniscus (163).

TISSUE ENGINEERING OF ARTICULAR CARTILAGE AND MENISCUS

The rapidly evolving field of tissue engineering has promised to deliver biological replacements of damaged articular cartilage and meniscus. In comparison with current treatment modalities, tissue engineering represents a shift in the paradigm. Whereas current treatment modalities improve articular cartilage and meniscal injuries by increments, the end goal of tissue engineering is to generate or regenerate articular cartilage and meniscus.

Previous investigations of the structural, biochemical, and mechanical properties of articular cartilage and meniscus serve as the necessary foundation and have set the stage for the tissue engineering of these structures. For example, a commonly stated long-term goal of a biochemical study to investigate the PG distribution in various zones of articular cartilage was to improve the treatment of cartilage defects in arthritis, which was all too familiar for a published study or a grant proposal decades ago.

To tissue-engineer articular cartilage or meniscus, one has the conceptual liberty of selecting cell sources, scaffolds, or growth factors. Another essential choice is whether mechanical stress is to be applied to the tissue-engineered articular cartilage or meniscus prior to or after *in vivo* implantation. Thus, the initial stage of tissue engineering of articular cartilage and meniscus is an optimization process of cells, scaffolds, growth factors, or mechanical stimulus.

Cells Capable of Generating Articular Cartilage and Meniscus

Articular chondrocytes are the obvious choices for articular cartilage regeneration (164–166). From the standpoint of scientific discovery, articular cartilage or meniscal regeneration from articular chondrocytes or meniscal fibrochondrocytes has revealed a wealth of information (e.g., 167–169). From the standpoint of alignment with eventual therapeutic regeneration of synovial joint condyle in arthritis patients, the selection of articular chondrocytes is problematic. The essential problem at this time is that articular chondrocytes are not very expandable *ex vivo*. Thus, relatively large donor site defects are necessary to harvest a large amount of tissue(s) from the patient in order to obtain sufficient numbers of articular chondrocytes or meniscal fibrochondrocytes for healing substantial articular cartilage or meniscal defects. In contrast, mesenchymal stem cells, whose natural progeny includes both chondrocytes and fibrochondrocytes, can be obtained in small quantities (e.g., a few cc of bone marrow content) (170) or from other connective tissue sources such as adipose tissue (170,171), readily expanded *ex vivo* in cell culture and reliably differentiated into chondrocytes cells (170,172). Embryonic stem cells may turn out to be a viable cell source for synovial joint regeneration, especially in consideration of the recent demonstration of the differentiation of embryonic stem cells into osteogenic cells (173,174). Embryonic stem cells are likely to be of greater significance in synovial joint condyle regeneration if the isolation and expansion of adult MSCs encounter substantial difficulties. However, thus far, it does not appear to be the case for synovial joint condyle regeneration (172). Chondrogenic and osteogenic cells derived from MSCs appear to be the logical choices at this time for exploring clinically applicable approaches toward regenerating the synovial joint condyle (152,172,175–180).

Biomaterial Scaffolds Are often Necessary for the Engineering of Structural Tissues such as Articular Cartilage and Meniscus

The optimal scaffolds for articular cartilage and meniscal regeneration are yet to be determined. An increasing number of meritorious studies have reported a wide range of natural and synthetic polymers for articular cartilage regeneration. Many of the tested synthetic polymers are biocompatible and biodegradable, two desirable features for cartilage regeneration (181). A model scaffold should allow effective diffusion of essential nutrients and metabolic wastes, given that chondrocytes and fibrochondrocytes both rely on diffusion for survival.

For cartilage regeneration, natural and synthetic polymers may need to simulate the extracellular matrix environment of chondrocytes that are created by Type II collagen and PGs in a highly aqueous matrix. Several hydrogels simulate cartilage matrix to various degrees, such as alginate, hyaluronate, chitosan, and polyethylene glycol-based polymers (175,176,181–183). The organization of chondrocyte phenotypes in various zones of articular cartilage may also need to be simulated, as demonstrated in recent reports by encapsulating articular chondrocytes from various zones of bovine articular cartilage into different hydrogel layers (184–186). The water content and diffusion properties of hydrogels mimic an ECM to allow tissue-forming cells to obtain systemic nutrients (187). The initial viscous liquid form of several hydrogel materials provides a unique capability to form complicated shapes while maintaining uniform cell distributions. For examples, an aqueous-derived silk scaffold also encompasses hydrogel-type properties and has been shown to support chondrogenesis (188). Pellet culture is a practice devoid of scaffolds that takes advantage of the dense, avascular, and aneural condition of cartilage. This system is done simply by centrifuging chondrocytes or MSCs into a pellet and incubating them in desired conditions. Although pellets do not provide efficient shape retention, they do bestow valuable information *in vitro* as models for chondrogenic MSC differentiation. Despite various levels of reported success with *in vitro* models, cell-hydrogel interactions need to be better understood, along with optimization of hydrogel composition, cross-linking, and degradation behavior as a function of the *in vivo* regenerative outcome.

In engineering an osteochondral construct, it is essential to construct a mold that is specific to the joint. Computer-aided approaches have been developed to construct molds that will both accurately replicate the anatomy of the joint as well as preserve the intricate architectural integrity of the interior of the scaffold. These intricate details can range from pore size to channel orientation to surface texture and can effectively contribute to the synthesis, or lack thereof, of the tissue one is trying to engineer. Common methods for 3D mold fabrication are based on software programs that read and digitize computerized tomography or magnetic resonance imaging. Solid free-form fabrication (SFF) technology can be used to produce an actual 3D scaffold through combining the interior architecture image and the external scaffold image, which is done via a layering process from computer-aided design files. SFF shows excellent promise due to the possibility of controlling the aforementioned necessary parameters needed in scaffold fabrication.

Growth Factors Are Necessary for Modulating Cell Behavior

Growth factors are proteins and polypeptides capable of modulating all aspects of cell behavior such as proliferation, differentiation, and apoptosis. Cells can be regulated by self-released growth factors (autocrine effect), or by growth factors released by other cells (paracrine effect). For chondrogenic differentiation, TGF-β superfamily is frequently used (e.g., 176,189). The de-differentiation and re-differentiation of chondrocytes are regulated by combinations of TGF-β1, fibroblast growth factor-2, and sequential exposure to IGF-I (190). TGF-βs also stimulate GAG synthesis in isolated cultured meniscus cells (191). Platelet-derived growth factor (PDGF) promotes chondrogenesis in chick limbs both *in vitro* and *in vivo* (191). Resting zone chondrocytes treated with PDGF shows hypertrophic activity in forming new cartilage (192). Although many growth factors have provided positive results, the optimal scheme of their application is not yet fully understood. The reader is referred to several recent in-depth reviews of growth factor delivery in cartilage regeneration (154,183,193).

Functional Tissue Engineering of Articular Cartilage and Meniscus

The field of functional tissue engineering has been proposed in response to the need to engineer tissues that have not only the appropriate cellular and matrix structures, but also the necessary physical properties (194,196). The aforementioned mechanical properties of both articular cartilage and meniscus are quite complex and intricate to replicate. The rather severe loading environment of cartilage in a synovial joint attributes to poor repair capabilities as well as degeneration. It has been proposed that a potential solution to engineer tissues with the appropriate physical properties lies in the physical factors, among which mechanical stress is most well studied (194–196). Prior to the conception of functional tissue engineering, it is widely acknowledged that mechanical factors can effectively influence cell behavior such as proliferation, differentiation, and matrix synthesis. Significant evidence exists that physical stress can accelerate or improve tissue regeneration and repair *in vitro*. The preference of chondrocytes to synthesize proper ECM components at an accelerated pace can help engineer cartilage and meniscus in an efficient manner. This concept can be used to enhance engineered grafts to more accurately represent native tissue. In order to better provide these stresses, a movement has begun to construct mechanical bioreactors that increase matrix synthesis through different approaches. Examples in which mechanical stimulation has proven advantageous in synthesizing cartilage has been through fluid flow (197,198), simulated hypogravity (199), simulated microgravity (200), static and cyclic compression (201–203), and hydrostatic pressure (204). Recent studies have suggested that external mechanical loading of cells or cell-polymer constructs may enhance their mechanical strength (e.g., 186,205,206). Although practical in theory, the type, frequency, area, and amount of loading still need to be determined to furnish the optimal results of engineering each individual tissue.

The mechanical properties of engineered articular cartilage and meniscus can be readily tested, in many ways similar to the mechanical testing of native articular cartilage and meniscus. The results of compressive moduli of native and engineered articular cartilage or meniscus tissue using excised tissue plants and *in vitro* testing can be directly compared. However, loading measurements of native or engineered articular cartilage and meniscus have not been accomplished *in vivo*. Therefore, the ideal mechanical properties of tissue engineered articular cartilage can only be estimated, not accurately determined. Various biomaterials have been investigated for articular cartilage repair and have various mechanical properties that must be considered when designing a suitable scaffold. Engineering a scaffold that is too stiff may detrimentally affect cell viability and matrix synthesis. Stress shielding may occur and surrounding tissue may degrade as physiological loads are transferred to the more mechanically stiff implant. In contrast, a scaffold too soft will not exhibit the needed mechanical stiffness for the applied loads, causing physical breakdown and degradation of the material, leaving a void in the host tissue. Various zones of articular and fibrocartilage have different mechanical properties (56,207). Whether regional differences in the mechanical properties of articular cartilage and meniscus need to be simulated in tissue engineering remains to be explored (79).

SUMMARY AND CONCLUSIONS

Articular cartilage and meniscus are load-bearing and hydrated tissues that are key structures of diarthrodial joints. The similarities between the two structures include their remarkable capacity for resistance to and transmission of mechanical stress and their ability to enable joint lubrication. However, articular cartilage and meniscus have many important differences. Articular cartilage, in the overwhelming majority of human synovial joints, consists of hyaline cartilage, whereas the meniscus is composed of fibrocartilage. The mechanical properties of native articular cartilage and meniscus have been studied extensively and shown to vary with species, location, and even the orientation of test specimens. Motivated by the concept of functional tissue engineering, the mechanical properties of engineered articular cartilage from cells and biomaterials have also been investigated in recent years. As a result of drastically different structural and mechanical properties between articular cartilage and meniscus, the engineering challenges of the two tissues are different. Mesenchymal stem cells, or other stem cells, need to be differentiated into chondrocytes for the engineering of articular cartilage, whereas these stem cells may need to be differentiated into fibroblasts and chondrocytes, or perhaps fibrochondrocytes, for the engineering of meniscus. The optimal biomaterials for the engineering of articular cartilage and meniscus remain to be identified or fabricated. At least, the engineered articular cartilage and meniscus must adapt to possess similar mechanical properties of their native target tissues. The existing knowledge on the biological and mechanical properties of articular cartilage and meniscus provides the necessary foundation for the eventual goal to regenerate or replace diseased or lost articular cartilage and knee meniscus with engineered tissue analogs.

BIBLIOGRAPHY

1. Buckwalter JA, Mankin HJ. Instructional course lectures, the American Academy of Orthopaedic Surgeons—articular cartilage. Part II: Degeneration and osteoarthrosis, repair, regeneration, and transplantation. J Bone Joint Surg 1997;79:612–632.
2. Maroudas A. Physicochemical properties of articular cartilage. In: Freeman MAR, ed. Adult Articular Cartilage. Kent, UK: Pitman Medical Publishing; 1979. pp 215–290.
3. Mow VC, Gu WY, Chen FH. Structure and function of articular cartilage and meniscus. In: Mow VC, Huiskes R, eds. Basic Orthopaedic Biomechanics and Mechano-Biology; Third ed. New York: Lippincott Williams & Wilkins; 2005. pp 181–258.
4. Buckwalter JA, Mow VC. Cartilage repair in osteoarthritis. In: Moskowitz RW, Howell DS, Goldberg VM, Mankin HJ, eds. Osteoarthritis: Diagnosis and Management, 2nd ed. Philadelphia, PA: Saudners; 1992.
5. Howell DS, Treadwell BV, Trippel SB. Etiopathogenesis of osteoarthritis. In: Moskowitz RW, Goldberg VM, Howell DS, Altman RD, Buckwalter JA, eds. Osteoarthritis: Diagnosis and Medical/Surgical Management. 2th ed. Philadelphia, PA: WB Saunders; 1992. pp 233–252.
6. Poole AR, Howell DS. Etiopathogenesis of osteoarthritis. In: Moskowitz RW, Howell DS, Altman RD, Buckwalter JA, Goldberg VC, editors. Osteoarthritis, Diagnosis and Management. 3rd ed. Philadelphia, PA: WB Saunders Publishers; 2001. pp 29–47.
7. Mankin HJ, Mow VC, Buckwalter JA. Articular cartilage structure, composition and function. In: Buckwalter JA, Einhorn TA, Simon SR, eds. Orthopaedic Basic Science: Biology and Biomechanics of the Musculoskeletal System. Rosemont, IL: American Academy of Orthopaedic Surgeons; 2000. pp 443–470.
8. Benjamin M, Evans EJ. Fibrocartilage. J Anat 1990;171: 1–15.
9. Weightman B. Tensile fatigue of human articular cartilage. J Biomech 1976;9:193–200.
10. Seedhom BB, Wallbridge NC. Walking activities and wear of prosthesis. Ann Rheum Dis 1985;44:838–843.
11. Morrison JB. Bioengineering analysis of force actions transmitted by the knee joint. J Biomech Eng 1968;3:164–170.
12. Morrison JB. The mechanics of the knee joint in relation to normal walking. J Biomech 1970;3:51–61.
13. Athanasiou KA, Rosenwasser MP, Buckwalter JA, Malinene TI, Mow VC. Interspecies comparisons of in situ intrinsic mechanical properties of distal femoral cartilage. J Orthop Res 1991;9:330–340.
14. Ewers BJ, Dvoracek-Driksna D, Orth MW, Haut RC. The extent of matrix damage and chondrocyte death in mechanically traumatized articular cartilage explants depends on rate of loading. J Orthop Res 2001;19:779–784.
15. Torzilli PA, Grigiene R, Borrelli J Jr, Helfet DL. Effect of impact load on articular cartilage: Cell metabolism and viability, and matrix water content. J Biomech Eng 1999;121: 433–441.
16. Centers for Disease Control and Prevention (CDC). Prevalence of self-reported arthritis or chronic joint symptoms among adults- United States, 2001. MMWR 2002;51:948–950.
17. Vunjak-Novakovic G, Goldstein SA. Biomechanical principles of cartilage and tissue engineering. In: Mow VC, Huiskes R, eds. Basic Orthopaedic Biomechanics and Mechano-Biology,

3rd ed. New York: Lippincott Williams & Wilkins; 2005. pp 343–407.

18. Mow VC, Ratcliffe A, Chern KY, Kelly MA. Structure and function relationships of the meniscus of the knee. In: Mow VC, Arnoczky SP, Jackson DW, eds. Knee Meniscus: Basic and Clinical Foundations. New York: Raven Press; 1992. pp 37–57.
19. Mow VC, Ratcliffe A, Poole AR. Cartilage and diarthroidal joints as paradigms for hierarchical materials and structures. Biomaterials 1992;13:67–97.
20. Arnoczky SP. Gross and vascular anatomy of the meniscus and its role in meniscal healing, regeneration, and remodeling. In: Mow VC, Arnoczky SP, Jackson DW, eds. Knee Meniscus, Basic and Clinical Foundations. New York: Raven Press; 1992. pp 1–14.
21. Uhthoff HK, Wiley JJ. Behavior of the Growth Plate. New York: Raven Press; 1988.
22. Cohen B, Chorney GS, Phillips DP, Dick HM, Mow VC. Compressive stress-relaxation behavior of bovine growth plate may be described by the nonlinear biphasic theory. J Orthop Res 1994;12:804–813.
23. Williams PL. Gray's Anatomy. New York: Churchill Livingston; 1995.
24. Shimazu A, Nah HD, Kirsch T, Koyama E, Leatherman JL, Golden EB, Kosher RA, Pacifici M. Syndecan-3 and the control of chondrocyte proliferation during endochondral ossification. Exp Cell Res 1996;229:126–136.
25. Mao JJ, Nah HD. More research needed to understand how orthodontists communicate with cells. Am J Orthod Dentofacial Orthop 2004;125:676–689.
26. Tamamura Y, Otani T, Kanatani N, Koyama E, Kitagaki J, Komori T, Yamada Y, Costantini F, Wakisaka S, Pacifici M, Iwamoto M, Enomoto-Iwamoto M. Developmental regulation of Wnt/beta-catenin signals is required for growth plate assembly, cartilage integrity, and endochondral ossification. J Biol Chem 2005;280:19185–19195.
27. Mow VC, Kuei SC, Lai WM, Armstrong CG. Biphasic creep and stress relaxation of articular cartilage in compression: Theory and experiments. J Biomech Eng 1980;102:73–84.
28. Eyre DR. Structure and function of the cartilage collagen: Role of type IX in articular cartilage. In: Brandt KD, ed. Cartilage Changes in Osteoarthritis. Indianapolis, IN: Ciba-Geigy; 1990. pp 12–16.
29. Heinegard D, Bayliss M, Lorenzo P. Biochemistry and metabolism of normal and osteoarthritic cartilage. In: Brandt KD, Doherty M, Lohmander LS, eds. Osteoarthritis. New York: Oxford University Press; 2003. pp 73–82.
30. Eyre DR, Wu JJ. Collagen of fibrocartilage: A distinctive molecular phenotype in bovine meniscus. FEBS Lett 1983;158:265–270.
31. Eyre DR, Oguchi H. The hydroxypyridinium crosslinks of skeletal collagens: Their measurement, properties and a proposed pathway of formation. Biochem Biophys Res Commun 1980;92:402–410.
32. Eyre DR, Dickson IR, Van Ness K. Collagen cross-linking in human bone and articular cartilage. Age-related changes in the content of mature hydroxypyridinium residues. Biochemistry 1988;252:495–500.
33. Huang CY, Mow VC, Ateshian GA. The role of flow-independent viscoelasticity in the biphasic tensile and compressive responses of articular cartilage. J Biomech Eng 2001;123: 410–417.
34. Huang CY, Soltz MA, Kopacz M, Mow VC, Ateshian GA. Experimental verification of the roles of intrinsic matrix viscoelasticity and tension-compression nonlinearity in the biphasic response of cartilage. J Biomech Eng 2003;125: 84–93.
35. Kempson GE, Freeman MA, Swanson SA. Tensile properties of articular cartilage. Nature 1968;220:1127–1128.
36. Kempson GE, Muir H, Pollard C, Tuke M. The tensile properties of the cartilage of human femoral condyles related to the content of collagen and glycosaminoglycans. Biochim Biophys Acta 1973;297:456–472.
37. Roth V, Mow VC. The intrinsic tensile behavior of the matrix of bovine articular cartilage and its variation with age. J Bone Joint Surg 1980;62:1102–1117.
38. Woo SL-Y, Akeson WH, Jemmott GF. Measurements of nonhomogeneous directional mechanical properties of articular cartilage in tension. J Biomechan 1976;9:785–791.
39. Lai WM, Hou JS, Mow VC. A triphasic theory for the swelling and deformation behaviors of articular cartilage. J Biomech Eng 1991;113:245–258.
40. Buckwalter JA, Rosenberg LC. Electron microscopic studies of cartilage proteoglycans: Direct evidence for the variable length of the chondroitin sulfate-rich region of proteoglycan subunit core protein. J Biol Chem 1982;257:8930–8939.
41. Muir H. Proteoglycans as organizers of the intercellular matrix. Biochem Soc Trans 1983;9:613–622.
42. Muir H. The chondrocyte, architect of cartilage: Biomechanics, structure, function and molecular biology of cartilage matrix macromolecules. Bioessays 1995;17:1039–1048.
43. Sun DN, Guo XE, Likhitpanichkul M, Lai WM, Mow VC. The influence of the fixed negative charges on mechanical and electrical behaviors in articular cartilage under unconfined compression. J Biomech Eng 2004;126:1–11.
44. Hunziker EB, Michel M, Studer D. Ultrastructure of adult human articular cartilage matrix after cryotechnical processing. Microsc Res Tech 1997;37:271–284.
45. Hultkrantz W. Ueber die spaltrichtungen der gelenkknorpel. Anat Anzeig verhandl anat Gesellsch 1898;14:248–256.
46. Benninghoff A. Form und bau der gelenkknorpel in ihren beziehungen zu funktion. II. Der aufbau des gelenkknorpel in seinen beziehungen zu funktion. Z Zellforsch 1925;2: 783–862.
47. Broom ND. The collagen framework of articular cartilage: Its profound influence on normal and abnormal load-bearing function. In: Nimni ME, ed. Collagen: Chemistry, Biology and Biotechnology. Boca Raton, FL: CRC Press; 1988. pp 243–265.
48. Ceohn ZA, Henry JH, McCarthy DM, Mow VC, Ateshian GA. Computer simulations of patellofemoral joint surgery. Am J. Sports Med 2003;31:87–98.
49. Lipshitz H, Etheredge R 3rd, Glimcher MJ. Changes in the hexosamine content and swelling ratio of articular cartilage as functions of depth from the surface. J Bone Joint Surg 1976;58:1149–1153.
50. Mitrovic D, Quintero M, Stankovic A, Ryckewaert A. Cell density of adult human femoral condylar articular cartilage. Joints with normal and fibrillated surfaces. Lab Invest 1983;49:309–316.
51. Aydelotte MB, Schumacher BL, Kuettner KE. Heterogeneity of articular chondrocytes. In: Kuettner KE, ed. Articular Cartilage and Osteoarthritis. New York: Raven Press; 1992. pp 237–249.
52. Kempson GE. Mechanical properties of adult articular cartilage. In: Freeman MAR, ed. Adult Articular Cartilage. Kent, UK: Pitman Medical Publishing; 1979. pp 215–290.
53. Akizuki S, Mow VC, Muller F, Pita JC, Howell DS. Tensile properties of human knee joint cartilage. II. Correlations between weight bearing and tissue pathology and the kinetics of swelling. J Orthop Res 1987;5:173–186.
54. Hunziker EB, Tyler JA. Articular cartilage repair. In: Brandt KD, Doherty M, Lohmander LS, eds. Osteoarthritis. Oxford, UK: Oxford University Press; 2003. pp 93–101.

55. Jadin KD, Wong BL, Bae WC, Li KW, Williamson AK, Schumacher BL, Price JH, Sah RL. Depth-varying density and organization of chondrocytes in immature and mature bovine articular cartilage assessed by 3-D imaging and analysis. J Histochem Cytochem DOI: 10.1369/jhc.4A6511. 2005 (In Press).
56. Tomkoria S, Patel RV, Mao JJ. Heterogeneous nanomechanical properties of superficial and zonal regions of articular cartilage of the rabbit proximal radius condyle by atomic force microscopy. Med Eng Phys 2004;26:815–822.
57. Broom ND, Silyn-Roberts H. Collagen-collagen versus collagen-proteoglycan interactions in the determination of cartilage strength. Arthritis Rheum 1990;33:1512–1517.
58. Quinn TM, Hunziker EB, Hauselmann HJ. Variation of cell and matrix morphologies in articular cartilage among locations in the adult human knee. Osteoarthritis Cartilage 2005;13:672–678.
59. Guilak F, Mow VC. The mechanical environment of the chondrocyte: A biphasic finite element model of cell-matrix interactions in articular cartilage. J Biomech 2000;33:1663–1673.
60. Guilak F. The deformation behavior and viscoelastic properties of chondrocytes in articular cartilage. Biorheology 2000;37: 27–44.
61. Guilak F. Compression-induced changes in the shape and volume of the chondrocyte nucleus. J Biomech 1995;28:1529–1542.
62. Knight MM, Ross JM, Sherwin AF, Lee DA, Bader DL, Poole CA. Chondrocyte deformation within mechanically and enzymatically extracted chondrons compressed in agarose. Biochem Biophys Acta 2001;1526:141–146.
63. Graff RD, Kelley SS, Lee GM. Role of pericellular matrix in development of a mechanically functional neocartilage. Biotechnol Bioengin 2003;20:457–464.
64. Allen DM, Mao JJ. Heterogeneous nanostructural and nanoelastic properties of pericellular and interterritorial matrices of chondrocytes by atomic force microscopy. J Struct Biol 2004;145:196–204.
65. Stockwell RA. Biology of Cartilage Cells. Cambridge, UK: Cambridge University Press; 1979.
66. Ateshian GA, Mow VC. Friction, lubrication, and wear of articular cartilage and diarthroidal joints. In: Mow VC, Huiskes R, eds. Basic Orthopaedic Biomechanics and Mechano-Biology, Third ed. New York: Lippincott Williams & Wilkins; 2005. pp 447–494.
67. McDevitt CA, Miller A, Spindler KP. The cells and cell matrix interaction of the meniscus. In: Mow VC, Arnoczky SP, Jackson DW, eds. Knee Meniscus, Basic and Clinical Foundations. New York: Raven Press; 1992. pp 29–36.
68. Bullough PG, Munuera L, Murphy J, Weinstein AM. The strength of the menisci of the knee as it relates to their fine structure. J Bone Joint Surg Br 1970;52:564–567.
69. Aspden RM, Yarker YE, Hukins DW. Collagen orientations in the meniscus of the knee joint. J Anat 1985;140:371–380.
70. Kelly MA, Fithian DC, Chern KY, Mow VC. Structure and function of the meniscus: Basic and clinical implications. In: Mow VC, Ratcliffe A, Woo SLY, eds. Biomechanics of Diarthroidal Joints. New York: Springer-Verlag; 1990. pp 191–214.
71. Yasui K. Three-dimensional architecture of human normal menisci. J Jpn Orthop Assoc 1978;52:391–399.
72. Skaggs DL, Warden WH, Mow VC. Radial tie fibers influence the tensile properties of the bovine medial meniscus. J Orthop Res 1994;12:176–185.
73. Nakano T, Thompson JR, Aherne FX. Distribution of glycosaminoglycans and the nonreducible collagen crosslink, pyridinoline in porcine menisci. Can J Vet Res 1986;50: 532–536.
74. Fithian DC, Kelly MA, Mow VC. Material properties and structure-function relationships in the menisci. Clin Orthop Relat Res 1990;252:19–31.
75. Walker PS, Erkman MJ. The role of the menisci in force transmission across the knee. Clin Orthop Relat Res 1975;109:184–192.
76. Smith MM, Ghosh P. Experimental models of osteoarthritis. In: Moskowitz RW, Howell DS, Altman RD, Buckwalter JA, Goldberg VC, eds. Osteoarthritis, Diagnosis and Management. 3rd ed. Philadelphia, PA: WB Saunders Publishers; 2001. pp 171–199.
77. Moskowitz RW, Davis W, Sammarco J, et al., Experimentally induced degenerative joint lesions following partial meniscectomy in the rabbit. Arthritis Rheum 1973;16:397–404.
78. Dehaven KE. The role of the meniscus. In: Ewing JW, ed. Articular Cartilage and the Knee Joint Function: Basic Science and Arthroscopy. New York: Raven Press; 1990. pp 103–115.
79. Guilak F, Butler DL, Goldstein SA. Functional tissue engineering: The role of biomechanic in articular cartilage repair. Clin Orthop Relat Res 2001; (391 Suppl):S295–S305.
80. Kempson GE. Mechanical properties of articular cartilage and their relationship to matrix degeneration and age. Ann Rheum Dis 1975;34:111–113.
81. Kempson GE. Age-related changes in the tensile properties of human articular cartilage: A comparative study between the femoral head of the hip joint and the talus of the ankle joint. Biochim Biophys Acta 1991;1075:223–230.
82. Akizuki S, Mow VC, Muller F, Pita JC, Howell DS, Manicourt DH. Tensile properties of human knee joint cartilage: I. Influence of ionic conditions, weight bearing, and fibrillation on the tensile modulus. J Orthop Res 1986;4:379–392.
83. Setton LA, Mow VC, Muller FJ, Pita JC, Howell DS. Mechanical properties of canine articular cartilage are significantly altered following transection of the anterior cruciate ligament. J Orthop Res 1994;12:451–463.
84. Setton LA, Zhu W, Mow VC. The biphasic poroviscoelastic behavior of articular cartilage: role of the surface zone in governing the compressive behavior. J Biomech 1993;26: 581–592.
85. Soltz MA, Ateshian GA. A conewise linear elasticity mixture model for the analysis of tension-compression nonlinearity in articular cartilage. J Biomech Eng 2000;122:576–586.
86. Huang CY, Stankiewicz A, Ateshian GA, Mow VC. Anisotropy, inhomogeneity, and tension-compression nonlinearity of human glenohumeral cartilage in finite deformation. J Biomech 2005;38:799–809.
87. Fithian DC, Zhu WB, Ratcliffe A, Kelly MA, Mow VC. Exponential law representation of tensile properties of human meniscus. Proc Inst Mech Eng 1989;c384/058:85–90.
88. Bader DL, Kempson GE, Barrett AJ, Webb W. The effects of leucocyte elastase on the mechanical properties of adult human articular cartilage in tension. Biochemica et Biophysica Acta 1981;677:103–108.
89. Schmidt MB, Mow VC, Chun LE, Eyre DR. Effects of proteoglycan extraction on the tensile behavior of articular cartilage. J Orthop Res 1990;8:353–363.
90. Hirsh 1944.
91. Sokoloff L. Elasticity of aging cartilage. Fed Proc 1966;25: 1089–1095.
92. Kempson GE, Freeman MA, Swanson SA. The determination of a creep modulus for articular cartilage from indentation tests of the human femoral head. J Biomech 1971;4: 239–250.
93. Kempson GE, Spivey CJ, Swanson SA, Freeman MA. Patterns of cartilage stiffness on normal and degenerate human femoral heads. J Biomech 1971;4:597–609.

94. Hoch DH, Grodzinsky AJ, Koob TJ, Albert ML, Eyre DR. Early changes in material properties of rabbit articular cartilage after meniscectomy. J Orthop Res 1983;1:4–12.
95. Parsons JR, Black J. The viscoelastic shear behavior of normal rabbit articular cartilage. J Biomech 1977;10:21–29.
96. Altman RD, Tenenbaum J, Latta L, Riskin W, Blanco LN, Howell DS. Biomechanical and biochemical properties of dog cartilage in experimentally induced osteoarthritis. Ann Rheum Dis 1984;43:83–90.
97. Armstrong CG, Lai WM, Mow VC. An analysis of the unconfined compression of articular cartilage. J Biomech Eng 1984;106:165–173.
98. Mak AF. The apparent viscoelastic behavior of articular cartilage— The contributions from the intrinsic viscoelasticity and interstitial fluid flow. J Biomech Eng 1986;108:123–130.
99. Mak AF. Unconfined compression of hydrated viscoelastic tissues: A biphasic poroviscoelastic analysis. Biorheology 1986;23:371–383.
100. Mak AF, Lai WM, Mow VC. Biphasic indentation of articular cartilage—I. Theoretical analysis. J Biomech 1987;20:703–714.
101. Zhu W, Mow VC, Koob TJ, Eyre DR. Viscoelastic shear properties of articular cartilage and the effects of glycosidase treatments. J Orthop Res 1993;11:771–781.
102. Armstrong CG, Mow VC. Variations in the intrinsic mechanical properties of human articular cartilage with age, degeneration, and water content. J. Bone Joint Surg 1982;64: 88–94.
103. Roth V, Mow VC, Lai WM, Eyre DR. Correlation of intrinsic compressive properties of bovine articular cartilage with its uronic acid and water content. Trans Orthop Res Soc 1981;6:21.
104. Froimson MI, Ratcliffe A, Gardner TR, Mow VC. Differences in patellofemoral joint cartilage material properties and their significance to the etiology of cartilage surface fibrillation. Osteoarthritis Cartilage 1997;5:377–386.
105. Jurvelin J, Kiviranta I, Arokoski J, Tammi M, Helminen HJ. Indentation study of the biochemical properties of articular cartilage in the canine knee. Eng Med 1987;16:15–22.
106. Stahursky TM, Armstrong CG, Mow VC. Variation of the intrinsic aggregate modulus and permeability of articular cartilage with trypsin digestion. Proc Biomech Symp Trans ASME 1981;AMD43:137–140.
107. Mow VC, Zhu W, Lai WM, Hardingham TE, Hughes C, Muir H. The influence of link protein stabilization on the viscometric properties of proteoglycan aggregate solutions. Biochim Biophys Acta 1989;992:201–208.
108. Schinagl RM, Ting MK, Price JH, Sah RL. Video microscopy to quantitate the inhomogeneous equilibrium strain within articular cartilage during confined compression. Ann Biomed Eng 1996;24:500–512.
109. Chen AC, Bae WC, Schnagl RM, Sah RL. Depth- and strain-dependent mechanical and electromechanical properties of full-thickness articular cartilage in confined compression. J Biomechan 2001;34:1–12.
110. Wang CC, Hung CT, Mow VC. An analysis of the effects of depth-dependent aggregate modulus on articular cartilage stress-relaxation behavior in compression. J Biomech 2001;34:75–84.
111. Cohen B, Lai WM, Mow VC. A transversely isotropic biphasic model for unconfined compression of growth plate and chondroepiphysis. J Biomech Eng 1998;120:491–496.
112. Hayes WC, Mockros LF. Viscoelastic properties of human articular cartilage. J Appl Physiol 1971;31:562–568.
113. Spirt AA, Mak AF, Wassell RP. Nonlinear viscoelastic properties of articular cartilage in shear. J Orthop Res 1989;7: 43–49.
114. Simon WH, Mak A, Spirt A. The effect of shear fatigue on bovine articular cartilage. J Orthop Res 1990;8:86–93.
115. Roth V, Schoonbeck JM, Mow VC. Low frequency dynamic behavior of articular cartilage under torsional shear. Trans Orthop Res Soc 1982;7:150.
116. Zhu W, Lai WM, Mow VC. Intrinsic quasilinear viscoelastic behavior of the extracellular matrix of cartilage. Trans Orthop Res Soc 1986;11:407.
117. Setton LA, Mow VC, Howell DS. Mechanical behavior of articular cartilage in shear is altered by transection of the anterior cruciate ligament. J Orthop Res 1995;13:473–482.
118. Fung YC. Mechanical Properties of Living Tissues. New York: Springer-Verlag; 1981.
119. Zhu W, Chern KY, Mow VC. Anisotropic viscoelastic shear properties of bovine meniscus. Clin Orthop Relat Res 1994;306:34–45.
120. Mow VC, Mak AF, Lai WM, Rosenberg LC, Tang LH. Viscoelastic properties of proteoglycan subunits and aggregates in varying solution concentrations. J Biomech 1984;17:325–338.
121. Zhu W, Mow VC, Rosenberg LC, Tang LH. Determinations of kinetic changes of aggrecan-hyaluronan interactions in solution from its rheological properties. J Biomech 1994;27: 571–579.
122. Hayes WC, Bodine AJ. Flow-independent viscoelastic properties of articular cartilage matrix. J Biomechan 1978;11: 407–419.
123. Maroudas A, Muir H, Wingham J. The correlation of fixed negative charge with glycosaminoglycan content of human articular cartilage. Biochim Biophys Acta 1969;177:492–500.
124. Donnan FG. The theory of membrane equilibria. Chem Rev 1924;1:73–90.
125. Myers ER, Lai WM, Mow VC. A continuum theory and an experiment for the ion-induced swelling behavior of articular cartilage. J Biomech Eng 1984;106:151–158.
126. Setton LA, Tohyama H, Mow VC. Swelling and curling behaviors of articular cartilage. J Biomech Eng 1998;120: 355–361.
127. Setton LA, Lai WM, Mow VC. Swelling-induced residual stress and the mechanism of curling in articular cartilage in vitro. In: Tarbell JM, ed. Advances in Bioengineering. 1993. pp 59–62.
128. Wan LQ, Miller C, Guo XE, Mow VC. A three-layer orthotropic model for swelling and curling of articular cartilage. ASME-BED. Vail, Colorado, 2005.
129. Olsen S, Oloyede A. A finite element analysis methodology for representing the articular cartilage functional structure. Comput Meth Biomech Biomed En 2002;5(6):377–386.
130. Gu WY, Lai WM, Mow VC. A mixture theory for charged-hydrated soft tissues containing multi-electrolytes: Passive transport and swelling behaviors. J Biomech Eng 1998;120: 169–180.
131. Huyghe JM, Janssen JD. Quadriphasic mechanics of swelling incompressible prorous media. Int J Eng Sci 1997;35: 793–802.
132. Gu WY, Lai WM, Mow VC. Transport of fluid and ions through a porous-permeable charged-hydrated tissue, and streaming potential data on normal bovine articular cartilage. J Biomech 1993;26:709–723.
133. Gu WY, Yao H. Effects of hydration and fixed charge density on fluid transport in charged hydrated soft tissues. Ann Biomed Eng 2003;31:1162–1170.
134. Lai WM, Mow VC, Sun DD, Ateshian GA. On the electric potentials inside a charged soft hydrated biological tissue: streaming potential versus diffusion potential. J Biomech Eng, 2000;122:336–346.
135. Lai WM, Sun DD, Ateshian GA, Guo XE, Mow VC. Electrical signals for chondrocytes in cartilage. Biorheology 2002;39: 39–45.

136. Mow VC, Ateshian GA, Lai WM, Gu WY. Effects of fixed charges on the stress-relaxation behavior of hydrated soft tissues in a confined compression problem. Int J Solids Structures 1998;35:4945–4962.
137. Sun DN, Gu WY, Guo XE, Lai WM, Mow VC. A mixed finite element formulation of triphasic mechano-electrochemical theory for charged, hydrated biological soft tissues. Int J Num Methods Eng 1999;45:1375–1402.
138. Lu X, Sun DD, Guo XE, Chen FC, Lai WM, Mow VC. Indentation determined mechano-electrochemical properties and fixed charge density of articular cartilage. Ann Biomed Eng 2004;32:370–379.
139. Wan LQ, Miller C, Guo XE, Mow VC. Fixed electrical charges and mobile ions affect the measurable mechano-electrochemical properties of charged-hydrated biological tissues: The articular cartilage paradigm. Mechan Chem Biosyst 2004;1: 81–99.
140. Ateshian GA, Chahine NO, Basalo IM, Hung CT. The correspondence between equilibrium biphasic and triphasic material properties in mixture models of articular cartilage. J Biomechan 2004;37:391–400.
141. Likhitpanichkul M, Miller C, Guo XE, Mow VC. A triphasic model of cell under micropipette aspiration: The osmotic effect on cell mechanical properties. ASME-BED. Vail, Colorado, 2005.
142. Lu X, Miller C, Guo XE, Mow VC. A new correspondence principle for triphasic materials: Determination of fixed charge density and porosity of articular cartilage by indentation. ASME-BED. Vail, Colorado, 2005.
143. Broom ND. Structural consequences of traumatizing articular cartilage. Ann Rheum Dis 1986;45:225–234.
144. Cawston T. Matrix metalloproteinases and TIMPs: Properties and implications for the rheumatic diseases. Mol Med Today 1998;4:130–137.
145. Lotz M, Hashimoto S, Kuhn K. Mechanisms of chondrocyte apoptosis. Osteoarthritis Cartilage 1999;7:389–391.
146. Meredith Jr JE , Fazeli B, Schwartz MA. The extracellular matrix as a cell survival factor. Mol Biol Cell 1993;4:953–961.
147. Hashimoto S, Ochs RL, Komiya S, Lotz M. Linkage of chondrocyte apoptosis and cartilage degradation in human osteoarthritis. Arthritis Rheum 1998;41:1632–1638.
148. Lyyra T, Kiviranta I, Vaatainen U, Helminen HJ, Jervelin JS. *In vivo* characterization of indentation stiffness of articular cartilage in the normal human knee. J Biomed Mater Res 1999;48:482–487.
149. Kobayashi T, Yoshihara Y, Samura A, Tanaka O, Shimmei M. Chondrocalcin as a marker of articular cartilage degeneration in anterior cruciate ligament-deficient knees. Orthopedics 1998;21:773–776.
150. Kuster MS, Posdiadlo P, Stachowiak GW. Shape of wear particles found in human knee joints and their relationship to osteoarthritis. Br J Rheumatol 1998;37:978–984.
151. Hollinger JO, Winn S, Bonadio J. Options for tissue engineering to address challenges of the aging skeleton. Tissue Eng 2000;6:341–350.
152. Mao JJ. Stem-cell driven regeneration of synovial joints. Biol Cell 2005;97:289–301.
153. Buckwalter JA. Articular cartilage injuries. Review Clin Orthop Relat Res 2002;3:257–264.
154. Hunziker EB. Articular cartilage repair: basic science and clinical progress. A review of the current status and prospects. Osteoarthritis Cartilage 2002;10:432–463.
155. Martin JA, Buckwalter JA. The role of chondrocyte-matrix interactions in maintaining and repairing articular cartilage. Biorheology 2000;37:129–140.
156. Redman SN, Oldfield SF, Archer CW. Current strategies for articular cartilage repair. Eur Cell Mater 2005;9:23–32.
157. Johnson LL. Arthroscopic Abrasion Arthroscopy. In: McGinty JB, ed. Operative Arthroplasty. Philadelphia, PA: Lippincott-Raven; 1996.
158. Shapiro F, Koide S, Glimcher MJ. Cell origin and differentiation in the repair of full-thickness defects of articular cartilage. J Bone Joint Surg Am 1993;75:532–553.
159. O'Driscoll SW. Articular cartilage regeneration using periosteum. Clin Orthop 1999;367:S186–S203.
160. Ahmad CS, Guiney WB, Drinkwater CJ. Evaluation of donor site intrinsic healing response in autologous osteochondral grafting of the knee. Arthoscopy 2002;18:95–98.
161. NIH Consensus Panel. NIH Consensus Statement on total knee replacement December 8–10, 2003. J Bone Joint Surg Am 2004;86-A: 1328–1335.
162. Haydon CM, Mehin R, Burnett S, Rorabeck CH, Bourne RB, McCalden RW, MacDonald SJ. Revision total hip arthroplasty with use of a cemented femoral component. Results at a mean of ten years. J Bone Joint Surg Am 2004;86-A: 1179–1185.
163. DeHaven KE. Meniscectomy versus repair: Clinical experience. In: Mow VC, Arnoczky SP, Jackson DW, eds. Knee Meniscus: Basic and Clinical Foundations. New York: Raven Press; 1992. pp 131–139.
164. Jadlowiec JA, Celil AB, Hollinger JO. Bone tissue engineering: Recent advances and promising therapeutic agents. Expert Opin Biol Ther 2003;3:409–423.
165. Vacanti JP, Langer R. Tissue engineering: The design and fabrication of living replacement devices for surgical reconstruction and transplantation. Lancet 1999;354(Suppl)1: S132–S134.
166. Zhang JY, Doll BA, Beckman EJ, Hollinger JO. Three-dimensional biocompatible ascorbic-acid containing scaffold for bone tissue engineering. Tissue Eng 2003;9:1143–1157.
167. Weng Y, Cao Y, Silva CA, Vacant MP, Vacanti CA. Tissue-engineered composites of bone and cartilage for mandible condylar reconstruction. J Oral Maxillofac Surg 2001;59: 185–190.
168. Niederauer GG, Slivka MA, Leatherbury NC, Korvick DL, Harroff HH, Ehler WC, Dunn CJ, Kieswatter K. Evaluation of multiphase implants for repair of focal osteochondral defects in goats. Biomaterials 2000;21:2561–2574.
169. Freed LE, Grande DA, Lingbin Z, Emmanuel J, Marquis JC, Langer R. Joint resurfacing using allograft chondrocytes and synthetic biodegradable polymer scaffolds. J Biomed Mater Res 1994;28:891–899.
170. Caplan AI. Mesenchymal stem cells. J Orthop Res 1991;9: 641.
171. Gimble J, Guilak F. Adipose-derived adult stem cells: Isolation, characterization, and differentiation potential. Cytotherapy 2003;5:362–369.
172. Alhadlaq A, Mao JJ. Mesenchymal stem cell: Isolation and therapeutics. Stem Cells Develop 2004;13:436–448.
173. Buttery LD, Bourne S, Xynos JD, Wood H, Hughes FJ, Hughes SP, Episkopou V, Polak JM. Differentiation of osteoblasts and in vitro bone formation from murine embryonic stem cells. Tissue Eng 2001;7:89–99.
174. Sottile Thomson VA, McWhir J. In vitro osteogenic differentiation of human ES cells. Cloning Stem Cells 2003;5:149–155.
175. Alhadlaq A, Mao JJ. Tissue-engineered neogenesis of human-shaped mandibular condyle from rat mesenchymal stem cells. J Dent Res 2003;82:950–955.
176. Alhadlaq A, Elisseeff JH, Hong L, Williams CG, Caplan AI, Sharma B, Kopher RA, Tomkoria S, Lennon DP, Lopez A, Mao JJ. Adult stem cell driven genesis of human-shaped articular condyle. Ann Biomed Eng 2004;32:911–923.
177. Gao J, Dennis JE, Solchaga LA, Awadallah AS, Goldberg VM, Caplan AI. Tissue-engineered fabrication of an osteochondral composite graft using rat bone marrow-derived mesenchymal stem cells. Tissue Eng 2001;7:363–371.

178. Gao J, Dennis JE, Solchaga LA, Goldberg VM, Caplan AI. Repair of osteochondral defect with tissue-engineered two-phase composite material of injectable calcium phosphate and hyaluronan sponge. Tissue Eng 2002;8:827–837.
179. Gao J, Caplan AI. Mesenchymal stem cells and tissue engineering for orthopaedic surgery. Chir Organi Mov 2003;88:305–316.
180. Rahaman MN, Mao JJ. Stem cell based composite tissue constructs for regenerative medicine. Biotechnol Bioeng 2005;91:261–284.
181. Lee KY, Mooney DJ. Hydrogels for tissue engineering. Chem Rev 2001;101:1869–1879.
182. Anseth KS, Metters AT, Bryant SJ, Martens PJ, Elisseeff JH, Bowman CN. In situ forming degradable networks and their application in tissue engineering and drug delivery. J Control Release 2002;78:199–209.
183. Randolph MA, Anseth K, Yaremchuk MJ. Tissue engineering of cartilage. Clin Plast Surg 2003;30:519–537.
184. Klein TJ, Schumacher BL, Schmidt TA, Li KW, Voegtline MS, Masuda K, Thonar EJ, Sah RL. Tissue engineering of stratified articular cartilage from chondrocyte subpopulations. Osteoarthritis Cartilage 2003;11:595–602.
185. Kim TK, Sharma B, Williams CG, Ruffner MA, Malik A, McFarland EG, Elisseeff JH. Experimental model for cartilage tissue engineering to regenerate the zonal organization or articular cartilage. Osteoarthritis Cartilage 2003;11:653–664.
186. Williams CG, Kim TK, Taboas A, Malik A, Manson P, Elisseeff J. In vitro chondrogenesis of bone marrow-derived mesenchymal stem cells in a photopolymerizing hydrogel. Tissue Eng 2003;9:679–688.
187. Peppas NA, Huang Y, Torres-Lugo M, Ward JH, Zhang J. Physicochemical foundations and structural design of hydrogels in medicine and biology. Annu Rev Biomed Eng 2000;2: 9–29.
188. Wang Y, Kim U, Blasioli DJ, Kim H, Kaplan DL. In vitro cartilage tissue engineering with 3D porous aqueous-derived silk scaffolds and mesenchymal stem cells. Biomaterials 2005;26:7082–7094.
189. Pittenger MF, Mackay AM, Beck SC, Jaiswal RK, Douglas R, Mosca JD, Moorman MA, Simonetti DW, Craig S, Marshak DR. Multilineage potential of adult human mesenchymal stem cells. Science 1999;284:143–147.
190. Pei M, Seidel J, Vunjak-Novakovic G, Freed LE. Growth factors for sequential cellular de- and re-differentiation in tissue engineering. Biochem Biophys Res Commun 2002;294: 149–154.
191. Collier S, Ghosh P. Effects of transforming growth factor beta on proteoglycan synthesis by cell and explant cultures derived from the knee joint meniscus. Osteoarthritis Cartilage 1995;3:127–138.
192. Lohmann CH, Schwartz Z, Niederauer GG, Boyan BD. Degree of differentiation of chondrocytes and their pretreatment with platelet-derived growth factor. Regulating induction of cartilage formation in resorbable tissue carriers in vivo. Orthopade 2000;29(2):120–128.
193. Almarza AJ, Athanasiou KA. Design characteristics for the tissue engineering of cartilaginous tissues. Ann Biomed Eng 2004;32:2–17.
194. Butler DL, Shearn JT, Juncosa N, Dressler MR, Hunter SA. Functional tissue engineering parameters toward designing repair and replacement strategies. Clin Orthop Relat Res 2004; Suppl: S190–S199.
195. Guilak F, Fermor B, Keefe FJ, Kraus VB, Olson SA, Pisetsky DS, Setton LA, Weinberg JB. The role of biomechanics and inflammation in cartilage injury and repair. Clin Orthop Relat Res 2004;423:17–23.
196. Wang CC, Guo XE, Sun D, Mow VC, Ateshian GA, Hung CT. The functional environment of chondrocytes with cartilage subjected to compressive loading: A theoretical and experimental approach. Biorheology 2002;39:11–25.
197. Freed LE, Martin I, Vunjak-Novakovic G. Frontiers in tissue engineering. In vitro modulation of chondrogenesis. Clin Orthop Relat Res 1999; (367 Suppl):S46–S58.
198. Pazzano D, Mercier KA, Moran JM, Fong SS, DiBiasio DD, Rulfs JX, Kohles SS, Bonassar LJ. Comparison of chondrogenesis in static and perfused bioreactor culture. Biotechnol Prog 2000;16:893–896.
199. Freed LE, Langer R, Martin I, Pellis NR, Vunjak-Novakovic G. Tissue engineering of cartilage in space. PNAS USA 1997;94:13885–13890.
200. Freed LE, Vunjak-Novakovic G. Microgravity tissue engineering. In Vitro Cell Dev Biol Anim 1997;33:381–385.
201. Buschmann MD, Gluzband YA, Grodzinsky AJ, Hunziker EB. Mechanical compression modulates matrix biosynthesis in chondrocyte/agarose culture. J Cell Sci 1995;108(Part 4):1497–1508.
202. Mauck RL, Soltz MA, Wang CC, Wong DD, Chao PH, Valhmu WB, Hung CT, Ateshian GA. Functional tissue engineering of articular cartilage through dynamic loading of chondrocyte-seeded agarose gels. J Biomech Eng 2000;122:252–260.
203. Seidel JO, Pei M, Gray ML, Langer R, Freed LE, Vunjak-Novakovic G. Long-term culture of tissue engineered cartilage in a perfused chamber with mechanical stimulation. Biorheology 2004;41:445–458.
204. Saris DB, Sanyal A, An KN, Fitzsimmons JS, O'Driscoll SW. Periosteum responds to dynamic fluid pressure by proliferating in vitro. J Orthop Res 1999;17:668–677.
205. Simmons CA, Matlis S, Thornton AJ, Chen S, Wang CY, Mooney DJ. Cyclic strain enchances matrix mineralization by adult human mesenchymal stem cells via the extracellular signal-regulated kinase (ERK1/2) signaling pathway. J Biomech 2003;36:1087–1096.
206. Grodzinsky AJ, Levenston ME, Jin M, Frank EH. Cartilage tissue remodeling in response to mechanical forces. Annu Rev Biomed Eng 2000;2:691–713.
207. Hu K, Radhakrishnan P, Patel RV, Mao JJ. Regional structural and viscoelastic properties of fibrocartilage upon dynamic nanoindentation of the articular condyle. J Struct Biol 2001;136:46–52.

Further Reading

Archard JF. Wear theory and mechanisms. In: Peterson MB, Winder WO, eds. *Wear Control Handbook*. New York: ASME Publications; 1980. pp 35–80.

Dowson D. Basic tribology. In: Dowson D, Wright V, eds. *Introduction to the Biomechanics of Joints and Joint Replacement*. London: Mechanical Engineering Publications, Ltd.; 1981. pp 120–145.

Mow VC, Setton LA, Howell DS, Buckwalter JA. Structure-function relationships of articular cartilage and the effects of joint instability and trauma on cartilage function. In: Brandt KD, ed. *Cartilage Changes in Osteoarthritis*. Indianapolis, IN: Ciba-Geigy; 1990. pp 22–42.

Mow VC, Sun DD, Guo XE, Likhitpanichkul M, Lai WM. Fixed negative charges modulate mechanical behavior and electrical signals in articular cartilage under unconfined compression: The triphasic paradigm. In: *Porous Media, Proc Tribute to Professor Reint de Boer*. Berlin: Springer Verlag; 2002. pp 227–247.

See also BIOMECHANICS OF EXERCISE FITNESS; JOINTS, BIOMECHANICS OF; LIGAMENT AND TENDON, PROPERTIES OF.

CATARACT EXTRACTION. See LENSES, INTRAOCULAR.

CELL COUNTER, BLOOD

YI ZHANG
SRIRAM NEELAMEGHAM
University of Buffalo
Buffalo, New York

INTRODUCTION: NATURE OF BLOOD CELLS (1,2)

Cells compose $\sim 50\%$ of the volume of normal human blood, while plasma constitutes the remaining volume. Generally, cells in blood are divided into three categories: platelets, erythrocytes (or red blood cells, RBCs) and leukocytes (or white blood cells, WBCs) (Table 1) (3). Among these, the platelets or thrombocytes are small, irregular, disk-shaped cells that lack a nucleus. They are of size 2–3 μm in diameter. These cells primarily function to stop bleeding or hemorrhage, and they also participate in coronary artery disease. They do so by being part of the blood coagulation cascade and by aggregating with each other. Platelets are found in blood at a concentration of $0.15\text{–}0.5 \times 10^6$ cells·mm^{-3}. The second type of cells in blood, erythrocytes, contains a red respiratory protein called hemoglobin. These are disk-shaped, biconcave cells without nuclei. Their diameter ranges from 6 to 8 μm and their thickness is 1.5–2.5 μm. The primary function of erythrocytes is to transport oxygen and carbon dioxide between the lung and body tissues. Erythrocytes are the most numerous blood cells at concentrations of $4\text{–}6 \times 10^6$ cells·mm^{-3}. Mature erythrocytes emerge from precursors that are called reticulocytes. Erythrocyte counts are on average $\sim 10\%$ higher in the human adult male population than those in the female population. Lack of iron and hemoglobin in erythrocytes can lead to anemia, a pathological deficiency in the oxygen-carrying component of blood. The third type of blood cells is the leukocytes, whose primary function is to provide the body with immunity and to protect it from infection. Leukocytes are fewer in number than the erythrocytes with a concentration of $\sim 5\text{–}10 \times 10^3$ cells·mm^{-3}. These cells are roughly spherical in shape and they contain nuclei, and considerable internal and cell-surface structures.

Leukocytes are categorized in various ways depending on their function and differentiation pathway. One common method subdivides these cells into myeloid and lymphoid cells. Myeloid cells differentiate into phagocytes, while lymphoid cells primarily produce lymphocytes. The phagocytes include polymorphonuclear granulocytes and monocytes–macrophages. Of these, the former have lobed, irregular shaped (polymorphic) nucleus. They are further subdivided into neutrophils (55–70% of all leukocytes), eosinophils (2–4%), and basophils (0.5–1%), on the basis of how the cellular cytoplasmic granules are stained with acidic and basic dyes. Leukocytes are also commonly characterized based on particular cell-surface receptors that are expressed by them, since these are specific to a particular subpopulation. Many of these receptors are recognized by monoclonal antibodies. A systematic nomenclature has now evolved in which the term CD (Cluster Designation) refers to a group of antibodies that recognize a particular cell-surface antigen. The CD classification is thus often used to classify and identify particular leukocyte subpopulations. A method of blood cell counting called flow cytometry (described below), often uses the fluorescence of labeled antibodies to distinguish between various cell types.

Among the granulocytes, neutrophils are the most abundant cell type. These represent the body's first line of defense during immune response. They are characterized by a number of segmented nucleus lobes connected by fine nuclear strands or filaments. Immature–young neutrophils have a band- or horseshoe-shaped nucleus. Thus, while the younger neutrophils are known as band neutrophils, the mature cells are the segmented neutrophils. Segmented neutrophils are the predominant species in human blood, while band neutrophil levels are elevated following bacterial infection or acute inflammation. The term left shift is used to indicate an increase in the number of circulating immature neutrophils. Condition under which the number of circulating neutrophils is increased is called neutrophilia, while a decrease in this cell type results in neutropenia. Another important morphological characteristic of neutrophils is the virtual lack of endoplasmic reticulum and mitochondria. Mature neutrophils have short lifetimes in circulation and they migrate into tissues to defend against invading microbes during inflammation. Eosinophils, like other granulocytes, possess a polymorphous nucleus, generally with two lobes. They can response to allergy and parasitic infection. They attack large parasites such as helminthes via their C3b receptors. Eosinophils release various substances from

Table 1. Characteristic of Normal Blood Cells[a]

Cell Type	Concentration	Size, μm	Density, g·mL	Shape	Nucleus	Cytoplasm
Platelet(thrombocyte)	$0.15\text{–}0.5 \times 10^6 \cdot \mu L^{-1}$	2–3	1.03–1.06	Small disk shape	None	Granular
Erythrocyte (RBC)	$4\text{–}6 \times 10^6 \cdot \mu L^{-1}$	6–8	1.09–1.11	Biconcave disk	None	Hemoglobin
Leukocyte (WBC)	$5\text{–}10 \times 10^3 \cdot \mu L^{-1}$	8–20	1.05–1.10			
Neutrophil	55–70% of WBC	9–15	1.08–1.10	Various	Lobed	Granular
Eosinophil	2–4% of WBC	9–15	1.08–1.10	Various	Lobed	Granular
Basophil	0.5–1% of WBC	10–16	1.08–1.10	Various	Lobed	Granular
Monocyte	3–8% of WBC	14–20	1.05–1.08	Various	Round	Fine
Lymphocyte	20–40% of WBC	8–16	1.05–1.08	Round	Round	Clear

[a](Adapted from Ref. 3. pp 3–6.)

their eosinophilic granules. These include major basic proteins, plus cationic proteins, peroxidase, phospholipase D and histaminase. The number of eosinophils can augment in blood during allergy (eosinophilia), dermatological disorder and parasitic infection. Basophils have a two-lobe nucleus. They release inflammatory mediators, such as histamine and bradykinin, and prostaglandins and leukotrienes. Basophils play an important role in inflammatory and allergic response. Their number is increased in patients with hypoactive thyroid conditions and during certain malignancies like chronic myeloid leukemia.

Monocytes and macrophages (tissue monocytes) represent the second type of phagocytes and these are relatively large, long-lived cells compared to polymorphonuclear granulocytes. Their cytoplasm is transparent with typically a horseshoe-shape nucleus. Monocytes are involved in both acute and chronic inflammation. The transformation from monocytes to macrophages is controlled by different cytokines. When responding to chemical signals at the inflammation site, monocytes quickly migrate from the blood vessels and start to perform phagocytotic activity. These cells also have an intense secretory activity that results in the production and secretion of chemical mediators such as lysozymes and interferons. The number of monocytes in circulation is increased whenever there is increased amount of cell damage, such as during recovery from infection.

Lymphocytes are mononuclear cells that constitute $\sim$20–40% of all leukocytes. These cells have a round or oval shaped nucleus that is typically large in comparison to the overall cell size. Besides circulating in blood vessels, lymphocytes also populate the lymphoid organs, as well as the lymphatic circulation. The specificity of immune response is due to lymphocytes, since these cells can distinguish between different antigenic determinants. Lymphocytes are subdivided into three main categories: (*1*) T-cells, (*2*) B-cells, and (*3*) natural killer (NK) cells. T-Cells are responsible for cellular immune response and are involved in the regulation of antibody reactions by either helping or suppressing the activation of B lymphocytes. B cells are the primary source of cells responsible for humoral–antibody responses. These are responsible for the production of immune antibodies. The NK cells destroy target cells via nonphagocytic reaction mechanisms that are termed cytotoxic reaction. Lymphocyte number may increase in blood in patients with skin rashes from certain viral diseases such as measles and mumps, in patients with thyrotoxicosis, and in patients recuperating from certain acute infections.

RATIONALE FOR CELL COUNT

Blood cell count is achieved by determining the concentrations and other parameters of different cell types in a unit volume of circulating blood. It can be a complete blood count (CBC, defined later in this article), which examines every blood component, or it may measure only one element. Table 1 demonstrates the characteristic of normal blood cells from a healthy adult. These values vary with age, sex, race, living habit, and health status. Further, under pathological conditions, the distribution of blood cells may be perturbed and thus blood cell counting can aid diagnostics. For example, a typical symptom of common anemia is an inadequate amount of RBCs. The increase or decrease in the numbers of the different types of WBCs may indicate infection and inflammation as discussed above. In addition to the cell numbers, other information regarding blood cells, such as cell size, is also important. For example, in patients with anemia caused by vitamin B_{12} deficiency, the average size of the RBCs is larger than normal and this disease state is called macrocytic anemia. On the contrary, if red blood cells are smaller than normal, as in the case of microcytic anemia, the condition may be indicative of iron deficiency. Therefore, a routine blood test, which includes not only blood cell count but also measurement of other parameters, can aid disease diagnosis and treatment by health professionals.

HISTORY AND BASIC PRINCIPLES FOR BLOOD CELL COUNTING (4–10)

Cell counting has evolved over the centuries from a manual method that heavily relied on microscopic examination, to one where electrical and optical measurement strategies, along with computer automation, are playing an increasingly important role. Indeed, manual methods are still important in research laboratories that study a wide variety of animal systems and cell types, in addition to human blood. On the other hand, automated systems are typically used in clinical studies. In this context, modern technology has automated the process of blood cell counting and the assessment of various blood cell parameters. A CBC, thus, not only provides a panel of tests to quantify the composition of whole blood, it may also include more detailed information regarding the cell profile. Based on technical feasibility and cost, either a simple manually operated cell counter or a more advanced automated blood count platform can be applied to serve the specific medical diagnose need. A brief history and rationale that has lead to current strategies for blood cell counting is outlined below.

Microscopy Coupled with Manual Visualization

Notable, among the early attempts to count blood cells, was the work by Anton van Leeuwenhoek in the seventeenth century who counted the number of chicken erythrocytes in a glass capillary of known dimensions using his microscope. Later, in the nineteenth and early twentieth century, Burker employed a shallow rectangular chamber with a thin coverglass as a counting chamber. Advances in this basic design have now resulted in the laboratory hemocytometer, which is commonly employed for manual cell counting. Ehrlich's classical work on the staining of white blood granules laid the foundations of hematology and differential cell counting. In these studies, he demonstrated that it is possible to distinguish between the various blood cell subgroups using acidic and basic dyes that differentially stained the cellular granules and nucleus.

Hemocytometer

One device that utilizes the light microscope for cell counting is the hemocytometer. This is a commercially available counting chamber that is used for manual blood counting. It consists of two parts: a microscopic slide with improved Neubauer ruling, and a special thick flat cover slip (Fig. 1a). Both the hemocytometer slide and cover slip must meet specifications of the National Bureau of Standards. The slides have two raised surfaces for duplicate cell counting, each of them bearing square-shaped grids of dimensions 3 × 3 mm. The two raised surfaces are separated by an H-shaped moat. Each of the 3 × 3 mm squares has a central area of size 1 × 1 mm that is further subdivided by 25 groups of 16 smaller squares (Fig. 1b and c). During cell counting, the coverslip is placed on top of the counting surfaces such that the distance between the counting surface and the coverslip is 0.1 mm. Thus, the total volume in the space between the central 1 × 1 mm area and the coverslip is fixed at 0.1 mm^3. Samples to be studied can be loaded into the chamber using a standard laboratory pipette placed at the point labeled V-slash.

A phase contrast microscope is used to view blood on a hemocytometer slide. In such runs, a sample of diluted blood mixture is placed in a hemocytometer. For a proper count, cells should be evenly distributed. In a white cell count, blood is typically diluted 1:20 in a solution that lyses red cells and stains white cells. Because red cells are so much more numerous than white cells, blood is normally diluted 1:200 for red cell counts. The total number of cells in the central area with fixed volume of 0.1 mm^3 is counted and this measurement is used to estimate the concentration of cells per cubic millimeter (mm^3) according to, cell concentration = number of cells counted × dilution factor / volume under central grid. For simplicity, instead of counting all the cells in the central 1 × 1 mm area, counting cells present in a sufficient number of representative squares is also reasonable as long as the acceptable level of accuracy can be ensured. A suitable convention should be applied to avoid counting cells twice, for example, by counting only those cells that touch the top and right-hand margins of a square and omitting cells that touch the bottom and left margins. The World Health Organization (WHO) has recommended methods for the visual determination of WBC count and platelet count using hemocytometer (Recommended methods for the visual determination of WBC count and platelet count. Geneva: World Health Organization, 2000. WHO/DIL/00.3). It describes the detailed sample preparation procedure and counting techniques, and this could be used as a basic protocol for cell counting using the hemocytometer.

Electrooptic Measurements

Advances in electronics and electrooptics in the twentieth century have dramatically simplified blood cell counting and made automation of these processes possible. Some examples of early advances are illustrated in Fig. 2. Panel a describes a method developed in the 1940s where cells



Figure 1. (a) Diagram of hemocytometer with cover slip. (b and c) Expanded view of ruled area as seen under a microscope.


(a)
RBC/Hb-scale
Galvanometer
Absorption cell
Filter
Lamp
Ring-shape photocell
Diaphragm
(b)
Upper cannula
Valve
Photomultiplier
Lamp
Microscope
Slit
Darkfield condenser
Filter
Lower cannula
0000
Meter
H₂O dest
Micropump
Pump
Cell suspension
Lever
(c)
Slit
Photomultiplier
Microscope
0000
Counter
Counting chamber
Motor (stir the dish)
Dark-field condenser
Lamp

Figure 2. (a) Schematic of an early instrument using the ensemble method to obtain a blood cell count. The intensity of light that is scattered onto a ring-shaped photodetector is measured. The intensity is proportional to cell concentration. (b) Schematic of a photoelectric device that optically counts cells under flow. Here, a fluid stream containing cells is passed through a microscope viewing station. The photomultiplier detects the passage of cells. (c) Schematic diagram of a device using a photoelectric spot scanning method. Mechanical motion is provided to scan cells contained in the counting chamber (3).

were electrooptically measured based on turbidimetry. Here, light lost per millimeter of path length based on scattering or absorbance by blood cells was related to cell concentration. Using cell reference or artificial standards, thus, RBC concentrations could be determined. In this approach, instead of detecting cells individually, the cell concentrations were measured using principles analogous to Beer's law. Panel b illustrates a photoelectric device from 1953, where a thin fluid stream was created such that single cells passed via a microscope viewing station. Images of these cells were magnified and detected using a photomultiplier tube. Panel c illustrates another early instrument where erythrocytes could be counted automatically by means of photoelectric spot-scanning of a thin layer of diluted blood. Here the manual visual counting chamber technique discussed above was improved by introducing a photomultiplier and an electronic counting unit. A motor drives the counting chamber. An instrument based on this principle is the Casella Counter shown in Fig. 2c.

Electronic Cell Counter

In 1950s, Wallace Coulter (Founder of Coulter Company, now Beckman-Coulter Co.) developed a method for cell counting based on electric impedance. This method now forms the basis of most particle size analysis methods in the world. This method, also called low voltage direct



Figure 3. Schematic diagram of electronic cell counter using electric resistance method.

current (dc) method, is based on the measurement of changes in electrical resistance as cells pass through a small orifice that separates two electrodes. In this type of device (Fig. 3), cells are suspended in an electrically conductive diluent, such as saline. Low frequency electrical current is applied between two electrodes; one of them being placed in the cell medium and the second within the aperture tube. The aperture tube has a small orifice or sensing aperture that is typically of size 50–200 μm in diameter. During the measurement, cells are drawn through the aperture using a pressure gradient that is either generated by a mercury manometer or oil displacement pump. Cells are assumed to be non-conducting. Electrical resistance between the two electrodes or impedance in the current occurs as the cells pass through the sensing aperture, causing voltage pulses that are measurable. The number of pulses is proportional to the number of cells counted. The size of the voltage pulse is directly proportional to the size (volume) of the cell. This principle allows discrimination between cells of different sizes. Counting of specific-sized cells is also possible using threshold circuits that cut-off voltage pulses above and below predetermined values. The quantity of suspension drawn through the aperture is precisely controlled to allow the system to count and size particles precisely. Finally, several thousand particles are individually counted within seconds in this device. Measurements are independent of particle shape, color, and density.

Analogous to the above method is the radiofrequency (RF) resistance method where high voltage electromagnetic current is flown between the two electrodes instead of dc. This current circuits the cell membrane lipid layer and penetrates into the cell. While the dc method defines the volume of the cell, changes in conductivity measured using the RF method correlate with the cell's interior structure including the nucleus volume and density, and cytoplasm granule composition. Both dc and RF may be applied simultaneously and this can yield different information about cell size and cellular structure. Such a dual measurement strategy is employed by Sysmex cell counters to quantify the differential leukocyte counts (DLC) as discussed later.

Several factors affect the precision and accuracy of measurements made using the electric impedance methods. First, the aperture size is critical. The instrument is set to count only particles within the proper size range. The upper and lower levels of the size range are called size exclusion limits. Any cell or material larger or smaller than the size exclusion limits will not be counted. Sample must also not contain other material that might erroneously be counted as cells. In practice, erythrocyte and platelet aperture should be smaller than leukocyte aperture in order to increase platelet count sensitivity. Besides the size exclusion limits and aperture size, cell shape and physical properties are also important in determining the shape factor or the ratio of electrically measured volume to the geometric volume. Erythrocytes may result in different signals depending on their orientation with respect to the aperture in the sensing zone. Simultaneous passage of more than one cell at a time through aperture may also cause artificially large pulses, and thus circuits to correct for this coincidence error are required. The magnitude of the coincidence error increases with cell concentration. Correction should be completed by the countercomputer based on the relationship of cell count with cell concentration and aperture size. Finally, an internal cleaning system to prevent or slow down protein buildup in aperture is beneficial in minimizing aperture blockage.

Hydrodynamic focusing as discussed below helps to solve many of the problems above and it provides improved cell counting and characterization. This has been developed and assembled in many cell counters today and this feature dramatically improves the cell volume distribution resolution.

Laser Light Scattering and Fluorescence Detection

Optical scattering can be used alone or in combination with other electrical measurement strategies discussed above for cell counting and characterization. A key feature of such instruments is hydrodynamic focusing where an external sheath flow allows alignment of blood cells one-at-a-time in the path of a light beam, usually within a quartz flow cell (Fig. 4a). Incident light on cells within this flow stream are scattered or redirected in a manner that is dictated by the size of the cell and the intracellular distribution of refractive index. Lasers are generally preferred as the light source since it produces monochromatic light that has a small spot size. Photomultiplier tubes (PMTs) are used to collect the weak signal of scattered light. The light scattered at angles from 5–10° (forward scatter) in general correlates with cell size. Light scattered at 90° is called side-scatter and this is related to the cell shape, orientation, and cellular content. A cell with many complex intracellular organelles will also give a larger side-scatter signal than a cell with fewer intracellular organelles. The design of precise angles where scattered light signals are measured is specific to instrument manufacturers and the cell-enumeration strategy employed. In general, these scatter data together allow reliable identification of distinct populations, such as platelets, RBCs, monocytes, and neutrophils in a mixture. They can also allow enumeration of lymphocyte subsets and reticulocytes. While, optical scattering methods reveal information about cells that is


(a)
Cell suspension
Sheath fluid
Dichroic mirrors
Fluorescence lens
Photomultiplier tubes (PMT)
PMT 4
Fluorescence detector
PMT 3
Optical filters
PMT 2
Side scatter detector
PMT 1
Collection optics
Photodiode
Forward scatter detector
Laser source
Signal amplification
Computer data analysis
(b)
Excitation spectrum
Fluorescent emission spectrum
Absorption
Fluorescence emission
350
400
450
500
550
600
650
Wavelength (nm)

Figure 4. (a) Schematic of flow cytometry showing hydrodynamic focusing of cells by sheath fluid that brings the cells in the path of a laser beam. Light scattered by cell at various angles is collected. These are passed through an arrangement of optical filters to yield measures of forward scatter, side scatter and particle fluorescence. (b) Stokes shift is depicted for the fluorescent probe fluorescein where the wavelength of the absorbed and emitted quanta are shifted, with the emitted wavelength being longer than the absorbed light.

distinct from that obtained from the above electrical methods, their estimates of cell volume are not as accurate as the electrical methods.

A major advantage of optical methods using lasers is that such methods can be readily coupled with fluorescence detection (Fig. 4b). Fluorescent conjugated antibodies to specific cell-surface CD markers or specific ligands can be used not only to identify particular blood cells, but also to label cellular components that may be indicative of disease states. In such work, when the laser light reaches these cells, a fraction of the photons are absorbed by the fluorescent probe, which then reemit the photon at a longer wavelengths. The quantity of this emitted light (both scattered and fluorescent) is measured using photomultiplier tubes that are arranged in conjunction with a series of optical filters and dichroic mirrors as shown in Fig. 4a. The detection and conversion of scattered or fluorescent light into electrical signals is accomplished by photodetectors that capture photons on a light sensitive surface that elicits an electron cascade. The signal output from such detectors is amplified (either linearly or logarithmically) and then converted from analog to digital form for computer analysis. Multidimensional plots of various scattering properties with fluorescent signals can thus be generated to individually characterize each cell in a complex mixture.

COMPLETE BLOOD CELL COUNT (5,10)

Computer Blood Cell Count is a series of tests that result in the quantitation of the number of erythrocytes, leukocytes, and platelets in a volume of blood. The measurements also estimate the hemoglobin content and packed cell volume (or hematocrit) of erythrocytes. This can be done manually using a microscope along with cytochemical dyes, such as Wright–Giemsa stain. The combination of acidic and basic dyes here can differentially stain the granules, cytoplasm, and nuclei of various blood cell types. Alternatively, in clinical laboratories an automated cell counter can be used to count cells in a given volume. Low end instruments offer RBC and platelet analysis with three-part differential leukocyte count (DLC) while higher end instruments may include a five-part differential count along with reticulocyte analysis. The speed of the instrument and level of automation varies with the class of instrument. The analysis thus obtained is compared with the normal range and assessed for clinical or research purposes. A complete blood cell count mainly includes the following parameters:

Hemoglobin

Hemoglobin concentration (HGB) is reported in grams per deciliter ($g{\cdot}dL^{-1}$) of blood. This parameter typically varies in proportion to erythrocyte concentration in blood. The normal range for hemoglobin is age and sex dependent. Traditionally, hemoglobin is measured using the cyanmethemoglobin method, as recommended by the International Council for Standardization in Hematology (ICSH). Here, a lysing agent is added to disrupt RBCs and to release cellular hemoglobin. This hemoglobin is converted into a stable form called cyanmethemoglobin (see reaction below), the quantity of which can be measured using a spectrophotometer for absorbance measurement at ~540 nm.

$$\mathrm{Hb(Fe^{2+})} \xrightarrow{\mathrm{K_3Fe(CN)_6}} \mathrm{methemoglobin(Fe^{3+})} \xrightarrow{\mathrm{KCN}} \mathrm{cyanmethemoglobin}$$

Since cyanmethemoglobin measurements contain poisonous cyanide reagent, other more environmentally friendly methods for automated HGB measurement have been developed. Among them, sodium lauryl sulfate-hemoglobin (SLS-Hb) method is used by Sysmex automated cell counters. Here, the lauryl group of the ionic surfactant, which is hydrophobic, binds strongly with hemoglobin. This binding leads to rapid globin molecular conformation change and conversion of hemoglobin from the ferrous (Fe^{2+}) to the ferric (Fe^{3+}) state. The hydrophilic group of SLS now binds with Fe^{3+} to form a stable SLS-Hb. The absorption maximum of SLS-Hb occurs at 535 nm with a shoulder at 560 nm, and this feature is used to determine hemoglobin content. This reaction mechanism is useful since conversion to SLS-Hb occurs rapidly within 10 s.

Platelet Count

Platelet count (PLT) is normally expressed as thousands per microliter (μL) and can be measured manually using the hemocytometer. Care must be taken during such measurements to avoid platelet clumps that can occur in the absence of appropriate anticoagulant. Electronic counting of platelets can also be performed using electric impedance or light scattering methods. Such measurements are typically performed in channels that are designed to discriminate between erythrocytes and platelets. Size distributions resulting from platelet counts can be used to estimate the mean platelet volume (MPV), which is a measure of the platelet volume variation. In general, increased MPV may be expected in regenerative thrombocytopenia, which is accompanied by an increased production of platelets by bone marrow.

Red Blood Cell Count

The RBC or erythrocyte count is expressed in millions per microliter of whole blood. Such counts can be measured manually using the hemocytometer. In hematology analyzers, RBC content is typically measured using either the dc impendence method, light scattering analysis, or a combination of the two. Attention is placed during these measurements to discriminate between small RBCs and platelets. Results of such analysis typically result in a RBC size distribution plot from which other indices can be estimated. These indices include: (*1*) Hematocrit (HCT), which is also called packed cell volume (PCV). This is a measure of the volume fraction of RBCs in whole blood expressed in %vol/vol. Normal adult hematocrit ranges from 35 to 50%, and this is both sex and age dependent. Traditionally, hematocrit is determined by monitoring the height of packed RBCs after centrifugation in a standard microhematocrit tube, relative to the column length. Electronic cell analyzers can also estimate hematocrit by measuring the individual volumes of RBCs (also called MCV as described below) and determining the product of RBC count and MCV. (*2*) Mean corpuscular volume (MCV) is the mean volume of RBCs expressed in femtoliters (fl). The normal range is ~80–100 fL. The MCV can be experimentally determined from the RBC size distribution height. Alternatively, if HCT value is known, MCV is calculated based on the ratio of hematocrit and RBC count. This parameter is analogous to MPV, which can be derived from platelet data. When the MCV is low with normal HCT, the blood is said to be microcytic. (*3*) Mean corpuscular hemoglobin concentration (MCHC) is the mean concentration of hemoglobin in the RBCs in grams per deciliter ($g{\cdot}dL^{-1}$). This is calculated based on the ratio of HGB by HCT. Red cell populations with normal, high, or low values of MCHC are referred to as normochromic, hyperchromic, or hypochromic, respectively. The last case can occur during strongly regenerative anemia, where an increased population of reticulocytes with low HGB content pulls the average value down (an increased MCV would be expected under this scenario). (*4*) Mean corpuscular hemoglobin (MCH) is a measure of the mean mass of hemoglobin (HGB) in RBC, and is expressed in picograms (pg). (*5*) Red cell distribution width (RDW) is an index of the variation in cell volume within the RBC population. It is mathematically determined by (Standard deviation of RBC volume/ MCV) × 100. The normal range for RDW is 11–15%. While, red cell populations with normal RDW are called homogeneous, those with higher than normal are termed heterogenous. For example, increased number of reticulocytes, which is associated with erythropoiesis, will cause increased RDW values. The RDW index may be an early indicator of changes in red cell population sizes, for example, during anemia caused by iron deficiency. In this case, the presence of few microcytic RBCs may increase the standard deviation of the cell distribution even before marked changes in MCV are observed.

White Blood Cell Count

White blood cell or leukocyte count is measured in thousands per microliter. During manual WBC count, RBCs in blood are lysed and diluted sample is charged into the hemocytometer. Nucleated cells are counted and WBC concentration is determined. Alternatively, impedance-based electronic cell counters can be used to measure WBC count. Besides these basic methods, in automated cell counters, one of many technologies can be applied for WBC differential count. Beckman–Coulter instruments employ the VCS (volume, conductivity, and scattering) technology. In this method, the dc impedance principle is used to physically measure the volume of the cell that displaces the isotonic diluent. Alternating current in the RF range short circuits the bipolar lipid layer of the cell membrane allowing energy penetration into cell. This probe provides information on cell size and internal structure. This data is adjusted by the cell volume measurement to obtain an index called opacity. Finally, coherent light scattering from an incident laser beam is collected to obtain information on cellular granularity and cell surface structure. In Sysmex instruments both dc and RF methods are employed along with differential lysis of cells using lysis solution and temperature treatment. In CELL-DYN instruments from Abbott laboratories, the Multi-Angle Polarization Scattering Separation (M.A.P.S.S.) technology is used to obtain the differential count. Here light scattered by cells localized in a hydrodynamically focused flow stream is measured at three angles (0, 10, and 90°). Polarized light at 90° is also measured. Together these four parameters are used to perform the five-part differential count. Two methods are employed in the Bayer cell counters for differential leukocyte count. In the first method called the peroxidase method, RBCs are lysed and white cells are stained with peroxidase. These cells are counted based on size by forward scatter analysis, and absorbance using dark field optics. The second method, called the basophil method, involves stripping the cells using a non-ionic surfactant in acidic solution. Basophils are resistant to lysis while RBCs and platelets are lysed and other leukocytes are stripped of their cytoplasm. Light scattering analysis distinguishes basophils from other polymorphonuclear and mononuclear cells. The above peroxidase and basophil methods thus provide automated differential cell count by separating the cells into clusters.

Reticulocyte Count (RTC, RET, or RETIC)

Reticulocytes are formed in the last stages of erythropoiesis. These cells spend ~ 2 days in the bone marrow and 1–2 days in peripheral blood prior to maturing into RBCs. These are nonnucleated RBC, which by definition upon staining with supravital dyes contain two or more particles of blue-stained material that correspond to ribosomal RNA (ribonucleic acid). With new methylene blue, reticulocytes stain bluish-purple. Reticulocyte count as a percentage of RBCs is a measure of the erythropoietic activity in the bone marrow. This is a useful marker of bone marrow suppression following chemotherapy, recovery from anemia, and so on. Reticulocyte counts may be high when the body is replenishing the RBCs in circulation. Reiculocyte counts can be performed using microscopy and supravital stains, such as new methylene blue or brilliant cresyl blue. Reticulocyte counts can also be done using automated instruments. Here light scattering is typically applied to detect cell size and cell fluorescence–absorbance measurements in conjunction with dyes like Auramine O and new methylene blue for quantitation of reticulocytes. Such methods provide good discrimination between reticulocytes and mature RBCs, with greater accuracy than microscopy examination.

AUTOMATED CELL COUNTERS (4,5)

Manufacturers of automated cell counters typically present a vast product line with varying levels of sophistication to meet the market needs. Although the analysis principles may differ, all cell counters have some common basic components, specifically hydraulics, pneumatics and electrical systems (Fig. 5). Among these, the hydraulic



Figure 5. Flow diagram of an automated multichannel cell counter. (Adapted from Ref. 3).

system is designed to dispense, dilute and mix samples prior to analysis. The pneumatic system operates various valves and drives the sample through the hydraulic system. The electrical system controls the operation sequences including optical–electrical detection of signals and computer-assisted data analysis. Instrument electronic analyzers typically have at least two channels. In one channel a diluent is added and RBCs are counted and sized. In the second, lysing agent is added to remove red blood cells and leave WBC intact for counting. These also produce a solution in which hemoglobin can be measured. Platelet count may be performed in either of these two channels or in a different channel. Normally, a separate channel will be required for reticulocyte count measurement. Analysis of a single blood specimen can be performed rapidly within 1 min, and results are presented in the form of numerical tables, histograms, or cytograms. The degree of analysis is both software and user dependent. Upon comparison with standard values, the software may also place flags on the output data that indicate either potential problem with analysis or deviation from cell count characterization of normal controls.

Numerous companies manufacture automated cell counters. Table 2 presents the characteristics of four high end instruments manufactured by some of them.

The Beckman–Coulter LH750 (Beckman Coulter Inc., Fullerton, CA) is a new instrument that provides CBC and five-part DLC. Additionally, it provides automated detection of subpopulations of pathological cells, such as immature granulocytes and atypical lymphocytes. It uses the three-dimensional (3D) Volume, Conductivity, Scatter (VCS) technology to probe hydrodynamically focused cells. A helium–neon laser and multiangle light scattering analysis provide information about cellular internal structure, granularity and surface morphology.

Abbott Cell-DYN 4000 (Abbott Laboratories, Abbott Park, IL) is capable of providing 41 parameters, including fully automated reticulocyte and immature granulocyte count. It uses four-angle argon-laser light scattering (M.A.P.S.S. technology) and two-color fluorescence flow cytometry (two fluorescence emission laser optics) to perform automated leukocyte counts, reticulocyte count, and DLC analysis. Both hydrodynamically focused impedance count and optical method are used for optimal erythrocyte and platelet size distribution analysis. Hemoglobin concentration is measured in a separate sample aliquot based on spectrophotometry. Immature granulocyte and variant lymphocytes are detected by a multiparameter, multiweighted discriminant function: This function generates a flag and reports a confidence fraction (i.e., the probability that these cells are classified correctly).

Sysmex XE-2100 (Sysmex Corporation, Japan) provides analysis of 32 parameters including simultaneous WBC, five-part DLC, human progenitor cell and reticulocyte analysis. Using flow cytometry with a semiconductor laser, RF, and dc measurements, this instrument analyzes the size and the structural complexity of cells. Selective dyes and reagent assist in differentiating the WBC, nucleated RBCs and reticulocyte. The RBC and platelet counts are measured using sheath flow dc detection method. Hemoglobin concentration is measured using a non-cyanide hemoglobin method.

The Bayer ADVIA 120 hematology system (Bayer Diagnostics, Tarrytown, NY) is an automated analyzer with four independent measurement channels. The peroxidase [PEROX and basophil-lobularity (BASO)] channels determine WBC and DLC count. Hemoglobin channel is used to measure HGB. The last channel is the RBC/PLT channel that provides information on platelet activation in addition to measuring PLT and RBC indices. This instrument measures the intensity of light scattered by platelets at low angles (2–3°) to obtain cell volume/size data and high angles (5–15°) for information on internal complexity. From these paired intensities the instrument computes platelet volume (MPV) and platelet component concentration on a cell-by-cell basis. The mean platelet component concentration (MPC) is indicative of platelet activation state. Mean platelet mass can also be computed from the MPV and MPC.

CONCLUDING REMARKS

This article discussed the basic principles of hematology with emphasis on humans. Enumeration of cell population

Table 2. Characteristics of Hematology Analyzers[a]

Instrument	Beckman–Coulter LH 750	Abbott Cell-Dyn 4000	Sysmex XE-2100	Bayer ADVIA 120
Number of parameters	28	41	32	30
HGB	Modified cyanmethemoglobin method	Spectrophotometry	Non-cyanide hemoglobin method	Modified cyanmethemoglobin method
Platelet	VCS	Optical method and impedance count	Hydrodynamic focusing with dc detection	Light scattering
RBC	VCS	Impedance count and optical method	Hydrodynamic focusing with dc detection	Light scattering
WBC and DLC	Five-part DLC VCS technology	Five-part DLC Light scatter and fluorescence flow cytometry	Five-part DLC Flow cytometry, RF and dc detection	Five-part DLC Peroxidase staining optics system, light scattering
Reticulocyte Count	New Methylene blue staining and VCS	Fluorescent dye CD4K530 staining and flow cytometry	Auramine O staining, light scattering, flow cytometry	Oxazin 750 staining and optical scatter

[a] Adapted from Ref. 3.

distribution in peripheral blood is examined using optical, electrooptical and light scattering techniques. As seen, such experimental modalities can be automated and the resulting hematology analyzers can be used for clinical application. Even though the exact strategy of cell counting varies between various manufacturers of automated cell counters, performance standards for such instrumentation have been established by the National Committee for Clinical Laboratory Standard (NCCLS) and the International Council for Standardization in Hematology (ICSH). The parameters evaluated here include (*1*) accuracy in measurement within a single batch and between batches of blood samples; (*2*) carryover of parameters between consecutive samples; (*3*) linearity or the ability to get similar measurements when the sample is diluted to different levels before being read; and (*4*) clinical sensitivity or the specificity and efficiency with which flags are generated during analysis to detect abnormal readouts. In order to evaluate the above and to tune the instrument for higher accuracy and sensitivity, blood count calibrators are also available from instrument manufacturers. Suitable preparations of preserved blood can also be made by individual laboratories as described by WHO document LAB/97.2 (Calibration and control of basic blood cell counters. Geneva: World Health Organization, 1997. WHO/DIL/97.2). Besides automated counting, manual and semiautomated methods are also applied by research laboratories. Establishment of such methods requires optimization of blood anticoagulant [ethylenedramenatetraacetic acid (EDTA), heparin, or sodium citrate typically], definition of appropriate electrolyte for sample dilution and design and optimization of lysis reagents required for specific experimental systems.

While the last 50 years have seen the automation of blood counting using hematology analyzers, a plethora of cell-specific antibodies have also been developed more recently. While some of these reagents are already being applied in the modern blood analyzer, their application may increase in the future. Such development can not only increase the range of parameters measured by the analyzer, they can also improve the accuracy and sensitivity of today's instrumentation.

BIBLIOGRAPHY

1. Armitage JO, editor. Atlas of Clinical Hematology. 2004; Philadelphia: Lippincott Williams & Wilkins; p 266.
2. Stiene-Martin EA, Lotspeich-Steininger CA, Koepke JA, editors. Clinical Hematology: Principles, Procedures, Correlations. 2nd ed. 1998; Philadelphia: Lippincott Williams & Wilkins Publishers; p 817.
3. Webster JG, editor. Encyclopedia of Medical Devices and Instrumentation, 4 Volume Set. 1988; New York: John Wiley & Sons; p 3022.
4. Rodak BF. Hematology: Clinical Principles and Applications. 2nd ed. 2002; Philadelphia: WB Saunders.
5. Bain BJ. Blood Cells A Practical Guide. 3rd ed. 2002; Oxford: Blackwell Science Ltd.
6. Fujimoto K. Principles of Measurement in Hematology Analyzers Manufactured by Sysmex Corporation. Sysmex J Iner 1999;9(1):31–44.
7. Groner W, Kanter R. Optical Technology in Blood Cell Technology. Sysmex J Iner 1999;9(1):21–30.
8. Shapiro HM. Practical Flow Cytometry. 4th ed. 2003; New York: John Wiley & Sons, Inc.; p 736.
9. Tatsumi N et al. Principle of Blood Cell Counter-Development of Electric Impedance Method. Sysmex J Iner 1999;9(1):8–20.
10. Hamaguchi Y. Overview of the Principles of Sysmex's Hemoglobinometry. Sysmex J Iner 1999;9(1):45–51.

Further Reading

Lotspeich-Steininger CA, Stiene-Martin EA, Koepke JA. Clinical Hematology: Principles, Procedures, Correlations. 1992; Philadelphia: Lippincott. xix; p 757.

Carr JH, Rodak BF. Clinical Hematology Atlas. 2nd ed. 2004; St. Louis (MO): Elsevier Saunders.

Brown BA. Hematology: Principles and Procedure. 5th ed. 1988; Philadelphia: Lea & Febiger.

See also ANALYTICAL METHODS, AUTOMATED; BLOOD COLLECTION AND PROCESSING; CYTOLOGY, AUTOMATED; DIFFERENTIAL COUNTS, AUTOMATED.

CELLULAR IMAGING

AMMASI PERIASAMY
University of Virginia
Charlottesville, Virginia

INTRODUCTION

For decades, autoradiography has been used widely to follow the synthesis of macromolecules by using radioactive isotopes (1). Interpretation of autoradiograms depends on knowledge of biochemical pathways and precursors and are carefully chosen so that they are used by the cell to build only one kind of molecule. On the other hand, light microscopy techniques have become a powerful tool for cell biologists to study cells live or fixed noninvasively (2–4). Fixed cells can also be studied using electron microscopy, which provides higher resolution than the light microscopy system (5,6). However, the light microscopy system allows studying live cells in physiological conditions.

The microscope has been an essential tool found in virtually every biological laboratory after the observation and description of protozoa, bacteria, spermatozoa, and red blood cells by Antoni van Leeuwenhoek, in the 1670s (7,8). The ability to study the development, organization, and function of unicellular and higher organisms and to investigate structures and mechanisms at the microscopic level has allowed scientists to better grasp the often misunderstood relationship between microscopic and macroscopic behavior. Further, the microscope preserves temporal and spatial relationships that are frequently lost in traditional biochemical techniques and gives two- (2D) or three-dimensional (3D) resolution that other laboratory methods cannot. The benefits of fluorescence microscopy techniques are also numerous (3,9). The inherent specificity and sensitivity of fluorescence, the high temporal, spatial, and 3D resolution that is possible, and the enhancement of contrast resulting from detection of an absolute rather than relative signal (i.e., unlabeled features do not emit) are several advantages of fluorescence techniques. Additionally, the plethora of well-described spectroscopic techniques providing different types of information, and the commercial availability of fluorescent probes, many of which exhibit an environment- or analytic-sensitive response, broaden the range of possible applications. Recent advancements in light sources, detection systems, data acquisition methods, and image enhancement, analysis, and display methods have further broadened the applications in which fluorescence microscopy can successfully be applied (2,3). Particularly, the fluorescent probes can be used to target many cellular components to follow the cell signaling in space (nm to m) and time (ns to days).

There are a number of microscopic techniques that have been established for cellular imaging including transmitted light–differential interference contrast microscopy (DIC)–phase contrast, reflection contrast microscopy, polarization microscopy, luminescence microscopy, and fluorescence microscopy (2,3,10). Fluorescence microscopy has been categorized into wide-field fluorescence microscopy, laser scanning confocal microscopy, multiphoton excitation microscopy, Förster (or fluorescence) resonance energy-transfer (FRET) microscopy, fluorescence lifetime imaging (FLIM) microscopy, fluorescence correlation spectroscopy (FCS), total internal reflection fluorescence (TIRF) microscopy, and fluorescence recovery after photobleaching (FRAP) microscopy (2–4,10–15). Some of the other advanced microscopy techniques include near-field microscopy (16,17), atomic force microscopy (18), scanning force–probe microscopy (19), X-ray microscopy (20), and Raman microscopy (21,22). In this article, selected fluorescence microscopy techniques (see Fig. 1) used for cellular imaging such as wide-field, confocal, multiphoton, FRET, FLIM, and CARS microscopy with biological examples are described.



Figure 1. Illustration of various fluorescence microscopy techniques that could be coupled to any upright or inverted epifluorescent microscope. The respective instrumentations are described in the literature. Wide-field (23); confocal (2); multiphoton (3); wide-field FLIM (24); confocal FLIM (25); MP-FLIM (26); FCS and image correlation spectroscopy (27,28).

BASICS OF FLUORESCENCE

Fluorescence is one of the many different luminescence processes in which molecules emit light. Fluorescence is the emission of light from the excited singlet state. Since this type of transition is usually allowed within the molecular orbitals, the emission rates of fluorescence are in the order of 10^8 s^{-1}, and fluorescence lifetimes are in nanoseconds. In contrast, phosphorescence is the emission of light from the triplet excited state and this transition is typically forbidden. The emission rates are much in the order of 10^0–10^3 s^{-1}, and phosphorescence lifetimes are typically milliseconds to seconds.

The excitation of molecules by light occurs via the interaction of molecular dipole transition moments with the electric field of the light and, to a much lesser extent, interaction with the magnetic field. The fluorescence processes following light absorption and emission are usually illustrated by a Jabłoński diagram shown in Fig. 2. Examination of the Jabłoński diagram in Fig. 2 reveals that the energy of the emitted photon is typically less then that of the absorbed photon. Hence, the fluorescence occurs at lower energy (longer wavelength) and this process is called Stokes' shift. The reasons for the Stokes' shift are rapid transition to the lowest vibrational energy level of the excited state S_1, and decay of the fluorophore to a higher vibrational level of S_0. The excess of the excitation energy is typically converted to the thermal energy.

Very intense radiation fields, such as those produced by ultrafast femtosecond lasers, can cause simultaneous absorption of two or more photons (two-photon, three-photon absorption, etc.). This phenomenon was originally predicted by Maria Göppert-Mayer in 1931 (30). It is important to realize that fluorescence intensity resulting from one- and two-photon excitation has a different dependence on excitation light intensity (power). Consequently, the fluorescence intensity depends on the squared laser power for two-photon excitation, the cubed (3rd) power for three-photon excitation, and the fourth power for four-photons excitation. This very strong dependence of fluorescence signal on the excitation power is frequently used to control the mode of excitation.

FLUOROPHORES AND FLUORESCENCE MICROSCOPY

Fluorescence microscopy (FM) plays a vital role in the biological and biomedical sciences, where fluorescence



Figure 2. Jabłoński energy level diagram. S_0, S_1, and S_2 are singlet ground, first, and second electronic states, respectively; T1 = triplet state (4,29).

probe specificity and sensitivity can provide important information regarding the biochemical, biophysical, and structural status of cells. The continuing development of fluorescent probes, such as various mutant forms of green fluorescent proteins (GFPs) or fluorophores in conjunction with the strong emergence over the past two decades of confocal and multiphoton microscopy (and specialized applications, such as FRAP, FRET, and FLIM), has been a major contributor to our understanding of dynamic processes in cells and tissue (3,4,12,30–34).

Florescence microscopy can be applied noninvasively to the study of living cells in tissue down to detection levels corresponding to single molecules. Fluorescent probes bound to cellular components with monoclonal antibodies, specific ligand affinities, or covalent bonds allow us to measure chemical properties, such as ion concentrations, membrane potential, and enzymatic activity (35). They allow the experimenter to observe the distribution and function of macromolecules (proteins, lipids, nucleic acids) in living cells and tissues. Techniques have been developed that allow the investigator to place, in cells and tissues, chemically blocked (caged) molecules that can be released or activated (uncaged) by a pulse of light (photolysis) (36). Therefore, a variety of ions, metabolites, drugs, and peptides can be released at carefully controlled times and locations within the specimen. Fluorescent probes and reagents are available from Amersham Pharmacia Biotech, Calbiochem, Fluka, Jackson ImmunoResearch Laboratories, Molecular Probes, Polysciences, Serotec, Sigma-Aldrich, and others. Fluorescent proteins (GFP) and GFP vectors are available from Clontech Laboratories, Quantum Biotechnologies and Life Technologies. Details regarding the selection of fluorophores, labeling, and loading conditions for live cell imaging have been described in the literature (37).

Wide-Field Fluorescence Microscopy

Wide-field fluorescence microscopy is a conventional fluorescence microscope equipped with a movable xyz-axis stage that permits imaging of the specimen at different focus and lateral positions, a higher quantum efficiency CCD camera for quantification of the light emitted by the specimen at different spectra, excitation and emission filter wheels, and an appropriate software package that is capable of synchronizing hardware, acquiring images, and correcting them for distortions and information loss inherent in the imaging process (22). To allow simultaneous monitoring of spectral emissions at two or three wavelengths, a dichroic, double, or triple pass filter is used that reflects the respective excitation wavelength to excite the double- or triple-labeled cells and transmit the respective emission bands (www.chromatech.com; www.omegaoptical.com).

Wide-field microscopy is the simplest and most widely used technique. It is used for quantitative comparisons of cellular compartments and time-lapse studies for cell motility, intracellular mechanics, and molecular movement (www.api.com). For example, new fluorescent indicators have allowed the measurement of Ca^{2+} signals in the cytosol and organelles that are often localized (38,39) and nondestructive imaging of dynamic protein tyrosine kinase activities in single living cells (40). This microscope has also been used for localizing protein molecules in living cells (22,41–43). Moreover, it is essential to implement digital deconvolution approaches to remove the out-of-focus information from the images collected in wide-field microscopy (22) (www.api.com).

Laser Scanning Confocal Microscopy (LSCM)

Wide-field microscopy, however, suffers from a major drawback due to the generation of out-of-focus fluorescent signals. Laser scanning confocal microscopy (LSCM) provides the advantage of rejecting out-of-focus information, and also allows associations occurring inside the cell to be localized in three dimensions. A confocal image with improved lateral resolution yields a wealth of spectral information with several advantages over a wide-field image including controllable depth of field and the ability to collect serial optical sections from thick specimens. Owing to its nanometer depth resolution and nonintrusiveness, confocal provides a new approach to measure viscoelasticity and biochemical responses of living cells and real-time monitoring of cell membrane motion in natural environments (2). The LSCM has been widely used in many biological applications, such as calcium, pH, and membrane potential imaging (2,35).

Confocal microscopy was introduced in 1957. Since then, the technique has gained momentum, particularly after the invention of lasers in the 1960s. Commercially available LSCM generate a clear, thin image (512×512) within 1–3 s or less, free from out-of-focus information. A single diffraction-limited spot of laser or arc lamp light is projected on the specimen using a high numerical aperture objective lens. The light reflected or fluorescence emitted by the specimen is then collected by the objective and focused upon a pinhole aperture where the signal is detected by a photomultiplier tube (PMT). Light originating from above or below the image plane strikes the walls of the pinhole and is not transmitted to the detector (see Fig. 3). To generate a 2D image, the laser beam is scanned across the specimen pixel-by-pixel. To produce an image using LSCM, the laser beam must be moved in a regular 2D raster scan across the specimen. Also, the instantaneous response of the photomultiplier must be displayed with equivalent spatial resolution and relative brightness at all points on the synchronously scanned phosphor screen of a CRT monitor. For a 3D projection of a specimen, one needs to collect a series of images at different z-axis planes. The vertical spatial resolution is ~ 0.5 μm for a 40×1.3 NA objective; for lenses with higher magnification, the vertical spatial resolution is even smaller. Three-dimensional image reconstruction can be accomplished with many commercially available software systems. Another alternative is a commercially available spinning disk based confocal microscope that can be used for cellular imaging (44) (www.perkinelmer.com).

The LSCM has been widely used in many biological applications and as an example here we describe protein localization using Förster resonance energy transfer (FRET) (4,43,45–48). FRET is a distance-dependent physical process by which energy is transferred nonradiatively from an excited molecular fluorophore (the donor) to



Figure 3. Illumination and detector configuration for wide-field, confocal, and multiphoton microscopy systems. DM = dichroic mirror, WF = wide-field, LSCM = laser scanning confocal microscope, MEFIM = multiphoton excitation fluorescence imaging microscopy, N = nucleus, C = Cytoplasm (22).

another fluorophore (the acceptor) by means of intermolecular long-range dipole–dipole coupling. It can be an accurate measurement of molecular proximity at nanometer distances (1–10 nm) and highly efficient if the donor and acceptor are positioned within the Förster radius (the distance at which half the excitation energy of the donor is transferred to the acceptor, typically 3–6 nm). The efficiency of FRET is dependent on the inverse sixth power of intermolecular separation (29,49,50) making it a sensitive technique for investigating a variety of biological phenomena that produce changes in molecular proximity (51). As an example Fig. 4 shows acquisition and data analysis for localization of CFP- and YFP-C/EBPα proteins expressed in live mouse pituitary GHFT1-5 cell nucleus.

Multiphoton Excitation Microscopy

The instrumentation configuration of multiphoton excitation microscopy (MEM) is generally the same as the LSCM with the exceptions of the excitation light source and the optics. In the LSCM, a visible or ultraviolet (UV) light source is used and an infrared (IR) light source is used for MEM system [see Fig. 3; (52)]. In one-photon (wide-field or confocal) fluorescence microscopy, the absorption of laser energy excites the fluorescent molecules to a higher energy level and results in the emission of one-photon fluorescence. The fluorescence intensity increases at a linear rate with the excitation intensity. Typically, some of the absorbed light energy is dissipated as heat, so the emission wavelength is longer than the absorption wavelength. For example, a fluorophore might absorb one photon at 365 nm and fluoresce at a blue wavelength $\sim$420 nm.

The fluorophores exhibit two-photon absorption at approximately twice (730 nm) their one-photon absorption wavelengths, while two-photon (2p) emission is the same as that of one photon (420 nm), allowing the specimen to be imaged in the visible spectrum. When an IR laser beam is focused on a specimen, it illuminates at a single point and the fluorescence emission is localized to the vicinity of the focal point. The fluorescence intensity then falls off rapidly in the lateral and axial direction. In one-photon (1p) microscopy, illumination occurs throughout the excitation beam path, in an hourglass-shaped path (22). This results in absorption along the excitation beam path, giving rise to substantial fluorescence emission both below and above the focal plane. Excitation from other focal planes contributes to photobleaching and photodamage in the specimen planes that are not involved in imaging. The IR illumination in 2p excitation also penetrates deeper into the specimen than visible light excitation due to its higher energy, making it ideal for cellular imaging involving depth penetration through thick sections of tissue.

Two-photon absorption was theoretically predicted by Göeppert-Mayer in 1931 and was experimentally observed for the first time in 1961 using a ruby laser as the light source (30,53). Denk and others have experimentally demonstrated 2p imaging in a laser scanning confocal microscopy (54). Two-photon excitation occurs when two photons of $h\omega$ and $h\omega'$ are absorbed simultaneously and a molecule is excited to the state of energy $E = h\omega + h'\omega'$ (h = Planck's constant, ω = frequency). The probability that



Image Single Correction Window

Spectral Bleed-through (SBT)/Fluorophore Expression Level(FEL) Correction

Reminder: All the required images must be background subtracted before processing

Tips: move mouse over each label (a,b,c,d,e,f,g) to find which image it represents for

Control Images

○ a ment\051204\confocal\group1\processed\a.tif

○ b ment\051204\confocal\group1\processed\b.tif

○ c ment\051204\confocal\group1\processed\c.tif

● d ment\051204\confocal\group1\processed\d.tif

Double Label Images

○ e ent\051204\confocal\group1\processed\e.tif

○ f ent\051204\confocal\group1\processed\f.tif

● g ent\051204\confocal\group1\processed\g.tif

Please check below box if you want to use calibrated bleed-through ratio

☐

Correction Option

○ Remove Donor SBT/FEL ● Remove Acceptor SBT/FEL ○ Remove Both

Bleed-through Factor (range) 10 Threshold between 1 and 255

Figure 4. Localization of CFP- and YFP-C/EBPα proteins expressed in live mouse pituitary GHFT1-5 cells studied using confocal-FRET microscopy. Seven images (a–g) are required to remove the contamination in the FRET image (f). The PFRET (processed FRET) image was obtained after removing the donor (DSBT) and acceptor (ASBT) spectral bleedthrough using the PFRET software (shown on the left panel, www.circusoft.com). The spectral bleedthrough varies depending on the excitation power for the donor and acceptor molecules. The respective histogram for the processed (Hist_PFRET) and the contaminated FRET (Hist_f) demonstrates the importance of removing the spectral bleedthrough signals. The energy-transfer efficiency ($E = 20\%$) was estimated after implementing the detector spectral sensitivity correction for the donor and acceptor channel (43).

2p absorption will occur depends on the colocalization of two photons within the absorption cross-section of the fluorophore. The rate of excitation is proportional to the square of the instantaneous intensity. This extremely high local instantaneous intensity is produced by the combination of diffraction-limited focusing of a single laser beam in the specimen plane and the temporal concentration of a femtosecond (fs) mode-locked laser (typically of the order of 10^{-50}–10^{-49} $\mathrm{cm}^4 \cdot \mathrm{s}^{-1}/\mathrm{photon}^{-1}/\mathrm{molecule}$) (55). Three- or four photon (or multiphoton) is the extension of two-photon excitation (56).

Two-photon excitation microscopy has been widely used in the area of biomedical sciences including tissue engineering, protein–protein interactions, cell, neuron, molecular, and developmental biology (3,13,22,57–60). Here, we demonstrate as an example the importance of MEM in drug molecule cellular uptake, where MEM is the ideal system for monitoring cellular drug uptake. The separation between excitation and emission wavelengths is considerably more than the 1p (wide-field and confocal) excitation and emission. For example, the excitation for the YK-II-140 drug molecule is 416 nm and emission is at 528 nm and a Stokes shift is ~ 112 nm. In the case of MEM, the excitation for the same drug molecule is 770 nm and the Stokes shift separation is wider than 112 nm. Moreover, in MEM we were able to detect 100 μM drug cellular uptakes compared to 1.0 mM in the wide-field microscopy. The sensitivity of drug detection is improved largely due to the advantage of the MEM (see Fig. 5 for details).

Spectral Imaging Microscopy

Human color vision is a form of imaging spectroscopy, by which we determine the intensity and proportion of wavelengths present in our environment. Spectral imaging improves on the eye in that it can break up the light content of an image not just into red, green, and blue, but into an arbitrarily large number of wavelength classes. Furthermore, it can extend the range to include the invisible UV and IR regions of the spectrum denied to the unaided eye; this type of imaging is usually known as hyperspectral (61). The result of (hyper) spectral imaging is a data set, known as a data cube, in which spectral information is present at every picture-element (pixel) of a digitally acquired image. Integration of spectral and spatial data in scene analysis remains a challenge.

These multispectral imaging approaches have been used to analyze multiple dyes within a sample. Recently,



Figure 5. Comparison of one- and two-photon excitation of a living PC-3 cell loaded with YK-II-140 anticancer drug (1.0 mM concentration). Wide-field microscopy provides more autofluorescence from the cell and media (a) compared to the two-photon microscopy (b) The less autofluorescence improves the detection sensitivity of the drug cellular uptake. Wide-field (Ex 416 nm and Em 528 nm). MEFIM or two-photon (Ex 770 nm and Em 528 nm). Biorad Radiance 2100 confocal–multiphoton microscopy was used for the data acquisition.

Carl Zeiss (www.zeiss.de) introduced the Laser Scanning Microscope (LSM) 510 META system with the revolutionary emission fingerprinting technique permitting the clean separation of several even spectrally overlapping fluorescence signals of a specimen (62). The number of dyes that can be used and detected in the experiment is almost unlimited. The new system overcomes the limits of existing detection methods and permits both qualitative and quantitative analyses quickly and precisely *in vitro* and *in vivo*. Furthermore, it is beneficial in many cases for the elimination of unwanted signals, such as background noise or autofluorescence.

The Zeiss 510 Meta system scan head contains two conventional photomultiplier tube detectors (PMT), where the wavelength of the emission light is selected by means of either bandwidth or long passes filters. In the third detector, emission light is passed through a prism and the resulting spectrum is projected onto a detector consisting of a linear array of 32 PMTs, thus enabling the spectral detector to detect a full emission spectrum from a given fluorophore (www.zeiss.com). The advantage of detecting a broad spectrum of emissions is fully realized by the process of linear unmixing (63). This is an image analysis technique that is intrinsic to the LSCM controlling software that compares the experimentally derived emission data to a previously recorded reference spectrum for that fluorophore. In a situation involving samples with multiple overlapping spectra, linear unmixing allows the resolution of fluorophores with closely related emissions, the accurate distinction between GFP and FITC or GFP and YFP being the most often cited example of this feature.

There are other commercial spectral imaging units are available including Leica AOBS (www.leicamicrosystems.com) and Olympus FV1000 (www.olympus.com). The main differences between these three commercial systems are FV1000 based on Grating/slit/PMT two-channel bidirectional scanning mode; Leica system based on Prism/slit/PMT; and the Zeiss system based on Grating/multi-anode PMT.

Here, as an example we provided the data acquired using the Zeiss multiphoton Meta system to measure FRET signals resulting from protein–protein interactions involving C/EBPα. The GHFT1-5 mouse cells that expressed either the CFP- or YFP-C/EBPα fusion protein were used to collect the reference spectra. These reference spectra were used for the linear unmixing of spectra from cells expressing both proteins. Images were then acquired of cells expressing both the CFP- and YFP-C/EBPα bound as dimers to DNA elements in regions of heterochromatin that form clearly defined focal bodies in the nuclei of the mouse cells used here (Fig. 6). Images collected (ex 820 nm; em 545 nm) from cells expressing both the CFP- and YFP-C/EBPα lambda (λ) stacks were spectrally unmixed to reveal the donor bleed-through into the FRET channel (Fig. 6a), allowing the FRET signal to be corrected for the bleed-through signal (Fig. 6b). The emission spectrum for the signal in the FRET channel (Fig. 6c) was determined (b-FRET in panel d) and was then reacquired after selective photobleaching of YFP (a-FRET) using 514 nm, showing the unquenched donor signal. These results demonstrate the power of spectral FRET imaging using the Meta system to detect protein–protein interactions in a single living cell.

Fluorescence Lifetime Imaging Microscopy

Each of the fluorescence microscopy techniques described above uses intensity measurements to reveal fluorophore concentration and distribution in the cell. Recent advances in camera sensitivities and resolutions have improved the



Figure 6. Spectral FRET imaging microscopy. Reference spectra (CFP, YFP) were established using cells expressing either CFP- or YFP-C/EBPα; alone, and the emission spectra are shown in panel D. Images were then collected from cells expression both the CFP- and YFP-C/EBPα, and the signals were spectrally unmixed to reveal the donor bleed-through (a) into the FRET channel (c), the corrected FRET signal is shown in b. The emission spectrum for the signal in the FRET channel (b-FRET) is shown in panel *D*, and was reacquired after selective photobleaching of YFP (a-FRET). CFPex 820 nm; YFPex 920 nm. Zeiss510 META system was used for the data acquisition.

capability of these techniques to detect dynamic cellular events (3). Unfortunately, even with the improvements in technology, these fluorescence microscopic techniques do not have high speed time resolution to fully characterize the organization and dynamics of complex cellular structures. In contrast, the time-resolved fluorescence (lifetime) microscopic technique allows the measurement of dynamic events at very high temporal resolution (nanoseconds). Fluorescence lifetime imaging microscopy (FLIM) merges the information of the spatial distribution of the probe with probe lifetime information to enhance the reliability of the concentration measurements. This technique monitors the localized changes in probe fluorescence lifetime (14,24,25,29,43,64–67) and provides an enormous advantage for imaging dynamic events within the living cells.

The fluorescence lifetime (τ) is defined as the average time that a molecule remains in an excited state prior to returning to the ground state. In practice, the fluorescence lifetime is defined as the time in which the fluorescence intensity decays to $1/e$ of the initial intensity (I_0) immediately following excitation (i.e., 37% of I_0). If a laser pulse excites a large number of similar molecules with a similar local environment and as long as no interaction with another protein or cell organelles occurs, the lifetime is the “natural fluorescence lifetime”, τ_0. If energy is transferred, however, the actual fluorescence lifetime, τ, is less than the natural lifetime, τ_0, because an additional path for deexcitation is present (28).

Conventional fluorescence microscopy provides images that reveal primarily the distribution and amount of stain in the cell based on measurements of intensity. In contrast, the time-resolved fluorescence microscopic (or FLIM) technique allows the measurement of dynamic events at very high temporal resolution and can monitor interactions between cellular components with very high spatial resolution, as well. A fluorophore in a microscopic sample may exist, for example, in two environmentally distinct regions and have a similar fluorescence intensity distribution in both regions, but different fluorescence lifetimes. Measurements of fluorescence intensity alone would not reveal any difference between two or more regions, but imaging of the fluorescence lifetime would reveal such regional differences (52).

Instrumental methods for measuring fluorescence lifetimes are divided into two major categories: frequency-domain (29,65) and time-domain (52). With the time-domain method (or pulse method), the specimen is excited with a short pulse and the emitted fluorescence is integrated in two or more time windows (24). The relative intensity captured in the time windows is used to calculate the decay characteristics. The determination of prompt fluorescence with lifetime in the range of 0.1–100 ns requires elaborate fast excitation pulses and fast-gated detection circuits. As an alternative to the time-domain method, the frequency-domain method uses a homodyne detection scheme and requires a modulated light source and a modulated detector. The excitation light is modulated in a sinusoidal fashion. The fluorescence intensity shows a delay or phase shift with respect to the excitation and a smaller modulation depth (29).

The FLIM system can be coupled to any wide-field microscope (24,29,65) (www.tautec.com; www.lambert-instruments.nl). The lifetime method can also be applied to a laser-scanning confocal microscope (www.coord.nl; www.picoquant.com) and multiphoton microscopy (26) (www.becker-hickl.com). The FLIM techniques measure environmental changes within the living cells and can be used in multilabeling experiments. An important advantage of FLIM measurements is that they are independent of change in probe concentration, excitation intensity, and other factors that limit intensity based steady-state measurements. Additionally, FLIM enables the discrimination of fluorescence coming from different dyes, including autofluorescent materials that exhibit similar absorption and emission properties but show a difference in fluorescence lifetime. The FLIM system is not only used for protein–protein interactions, but also for various biological applications from single cell to single molecule as well as deep tissue cellular imaging (3,26,66,68,69).

The data provided here were collected using the two-photon FLIM system to demonstrate the feasibility of implementing the lifetime imaging technique for drug uptake in live cells. The intensity and the lifetime image are shown in Fig. 7 of a prostate cancer (PC-3) cell after adding the drug (1.0-mM concentration) for ~2 min. The data clearly demonstrate that there is a considerable difference in lifetime distribution in the cytoplasmic area versus the nucleus, thus allowing the quantitation of the dynamic process of drug molecule uptake in different cellular organelles. The lifetime distribution in the cytoplasm (2 ns) and nucleus (4 ns) clearly reflects differences in molecule uptake between them and both are considerably reduced compared to the natural lifetime (20 ns) of the drug molecule. The FLIM system would reduce background interference and thus enhance measurement precision to yield more accurate understanding of drug molecule associations involved in living cells. These technologies will significantly improve and expand existing capabilities for understanding the drug molecules interactions and for characterizing their binding properties as an ensemble and at the single molecule level.

Fluorescence Correlation Spectroscopy (FCS)

Fluorescence correlation spectroscopy (FCS) is a technique in which spontaneous fluorescence intensity fluctuations are measured in a microscopic detection volume of $\sim 10^{-15}$ L as defined by a tightly focused laser beam. This spectroscopy is a special case of fluctuation correlation techniques where the laser induced fluorescence from a very small probe volume is autocorrelated in time. Fluorescence intensity fluctuations measured by FCS represent changes in either the number or the fluorescence quantum yield of molecules resident in the detection volume (27). Small,



Cursor 1: 1525.95 x 0 y Diff.: 931.03 x
Cursor 2: 2456.98 x 0 y Mean: 2009.35 x

Cursor 1: 3023.89 x 0 y Diff.: 1950.14 x
Cursor 2: 4974.03 x 0 y Mean: 3987.75 x

Figure 7. The FLIM microscopy-drug moleculeYK-140 uptake in a single living cell. Multiphoton excitation time-resolved intensity (a) and lifetime (b) images of PC-3 cell after adding the YK-II-140 drug (1.0-mM concentration). There is a clear difference in distribution of lifetime in the nucleus ('N') (mean $\tau_N = 3.967$ ns) versus cytoplasm ('C') (mean $\tau_C = 2.009$ ns). Moreover, considerable amount of quenching of the drug molecule in the cellular environment demonstrates that the drug molecules were interacting with various cell organelles. Consequently, the lifetime was considerably reduced from its natural lifetime 20 ns. Ex–770 nm; Em–528/30 nm. Becker and Hickl board was used in the Biorad Radiance system to acquire the data.

rapidly diffusing molecules produce rapidly fluctuating intensity patterns, whereas larger molecules produce more sustained bursts of fluorescence. If no further effects on fluorescence characteristics are present, fluctuations in the emission light simply arise from occupation number changes in the illuminated region by random particle motion. Excellent article on FCS basics was written by Petra Schwille can be seen in the URL http://www user.gwdg.de/~pschwil/BTOL_FCS.pdf.

Image Correlation Spectroscopy (ICS) was developed as the imaging analog of FCS for measuring protein aggregation in biological membranes. The ICS method entails collecting fluorescence intensity fluctuations as a function of position by using a laser scanning microscope imaging system and analyzing the imaged intensity fluctuations by spatial autocorrelation analysis (28,70). The amplitude of the normalized spatial autocorrelation function is directly related to the absolute concentration of fluorophore in the focal volume and the state of aggregation of the fluorescent entities. Extension of ICS to temporal autocorrelation analysis of image time series also permits measurement of molecular transport occurring on slower time scales characteristic of macromolecules within the plasma membrane. The other related technique, Image Cross-Correlation Spectroscopy (ICCS) allows direct measurement of the interactions of two colocalized proteins labeled with fluorophores having different emission wavelengths. Both ICS and ICCS involve the use of laser scanning confocal microscopy to obtain fluorescence images of fluorescently labeled cell membranes.

RAMAN AND CARS MICROSCOPY

Confocal, multiphoton, and fluorescence lifetime imaging microscopy have become powerful techniques for revealing 3D imaging of molecular distribution and dynamics in living specimens. This followed the development of various natural and artificial fluorophores. For chemical species or cellular components that cannot be fluorescently labeled, Raman microscopy, which measures vibrational properties and does not require molecules to have a fluorescent label, can be used to identify specific signatures of cellular or chemical components (71,72). Raman spectroscopy is an extremely powerful tool for characterizing the physical and chemical properties of the biological molecules. Raman spectroscopy is based upon the Raman effect, which may be described as the scattering of light from a molecule with a shift in wavelength from that of the usually monochromatic excitation wavelength from ultraviolet to infrared light (21). The Raman shifts are thus measures of the amounts of energy involved in the transition between initial and final states of the scattering molecule. Resonance Raman can provide more specific molecular information by working on resonance with particular electronic transitions in the protein (73). Resonant Raman spectroscopy of neutrophilic and eosinophilic granulocytes provided very clear fingerprints of the presence of oxidizing enzymes that these cells require for their functionality (74). With the use of advanced detector technology, single-cell vibrational Raman spectroscopy proved to be sufficiently sensitive to show the typical spectra of the cell nucleus and cytoplasm in human white blood cells (75). The low scattering cross-section of naturally occurring compounds, such as DNA, RNA, and proteins can be overcome by high peak powers in the laser beams used to generate the Raman signal (76,77). Using the principle of Raman microscopy for cellular imaging, several systems have already been realized: Resonant Raman spectroscopy (75), surface-enhanced Raman spectroscopy (SERS) (78), coherent anti-Stokes Raman spectroscopy (CARS) (71,72), and Fourier transform infrared absorption (FTIR) (79).

CARS microscopy relies on the Raman Effect (80). In the spontaneous Raman process, molecules scatter photons, modifying the photon energy with energy quanta that corresponds to the molecule's vibrational modes. Vibrational contrast in CARS microscopy is inherent to the cellular species, thus requiring no endogenous or exogenous fluorophores that may also be prone to photobleaching. For CARS, two optical beams of frequencies ω_p (1064 nm) and ω_s (tunable 770–900 nm) interact in the sample to generate an anti-Stokes optical output at $\omega_{as} = 2\omega_p - \omega_s$ in the phase matched or a specific direction and is resonantly enhanced if $\omega_p - \omega_s$ coincides with the frequency of a Raman active molecular vibration across the entire focal volume. This nonlinear process uses pulsed laser sources. The signal intensity has quadratic and linear dependence on pump and stokes powers, respectively. As a result, it generates signal only within the focus, where the laser intensity is the highest, enabling 3D resolution. The molecular vibrational information obtained by CARS provides a detailed fingerprint of different bonds, functional groups, and conformations of molecules, biopolymers and even microorganisms (71,72). For example, the Raman shift at 2845 cm^{-1} was used to collect the lipid signal (bright red dots, as shown by arrow in Fig. 8a). When the frequency



Figure 8. Demonstration of CARS and non-CARS image. (a) CARS image of lipids in 3T3 fibroblast cells excited at the vibrational frequency of 2845 cm^{-1}. (b) The frequency was tuned away from the lipids vibrational modes, 2947 cm^{-1}. No lipid is observed as pointed by the arrows. This CARS image was collected at Prof. Sunney Xie's laboratory (Harvard University) and the CARS microscopy is based on Olympus Fluoview single beam scanning system using synchronizely pumped High Q laser system.

was tuned to 2947 cm^{-1}, the lipid signal disappeared as shown by arrow in Fig. 8b. As described in the Research Activity section above we propose to study the Raman C–H stretching modes and C–C stretching modes in lipid-phase transitions for which we need to tune to different vibrational frequency to calibrate the system. If a particular molecule vibrational frequency is not known, it can be determined by conventional Raman spectrometry. Therefore, vibrational spectroscopy has found wide application in structural characterization of biological materials and in probing interaction dynamics.

CONCLUSION

Multifaceted microscopy technology moved to the center stage in cellular imaging. There is no question that the described microscopy approaches in this paper will continue to increase in all directions, driven by advances in technological development and the growing number of cell biologist researchers who will routinely use this technology for cellular imaging. Even though some of the microscopy techniques are somewhat more complex, they provide an unprecedented level of information about the micromolecular interactions in cells under physiological conditions at a very high temporal and spatial resolution. New fluorophores such as green fluorescent proteins (GFPs) and in particular Quantum Dots will expand the usefulness of cellular imaging qualitatively and quantitatively and that will lead to more detailed insights in studying the cellular dynamics. Raman and CARS microscopy techniques would allow characterizing the physical and chemical properties of the biological without the fluorophore labeling.

ACKNOWLEDGMENTS

The author would like to thank Ms. Ye Chen, Jalan Washington, and Erica Caruso for their help provided in preparation of the manuscript. The author also would like to thank Dr. Milton Brown for providing the drug compounds and Ms. Elise Shumsky, Carl Zeiss for her help in spectral FRET imaging. This work is supported by funds from National Center for Research Resources (NCRR-NIH) and Funds for Excellence in Science and Technology (FEST) at the University of Virginia.

BIBLIOGRAPHY

1. Prescott D. Methods in Cell Physiology. New York: Academic Press; 1968.
2. Pawley JB, editor. Handbook of Biological Confocal Microscopy. 2nd ed. New York: Plenum Press; 1995.
3. Periasamy A, editor. Methods in Cellular Imaging. New York: Oxford University Press; 2001.
4. Periasamy A, Day RN, editors. Molecular Imaging: FRET Microscopy and Spectroscopy. New York: Oxford University Press; 2005.
5. Grimstone A. The Electron Microscope in Biology. New York: St. Martins; 1968.
6. Frank J. Three-dimensional imaging techniques in electron microscopy. Biotechniques 1989;7(2):164–173.
7. Hogg J. The Microscope: History, Construction, and Application. London: George Routledge and Sons; 1871.
8. Jones T. 1997. History of the Light Microscope. Available at http://www.utmem.edu/personal/thjones/hist/c1.htm.
9. Periasamy A, Herman B. Computerized fluorescence microscopic vision in the biomedical sciences. J Computer-Assisted Microsc 1994;6:1–26.
10. Inoue S, Spring KR. Video Microscopy: The Fundamentals. New York: Plenum Press; 1986.
11. Wang XF, Herman B, editors. Fluorescence Imaging Spectroscopy and Microscopy. New York: John Wiley & Sons, Inc.; 1996.
12. Lippincott-Schwartz J, Snapp E, Kenworthy A. Studying protein dynamics in living cells. Nat Rev Mol Cell Biol 2001;2(6): 444–456.
13. Diaspro A, editor. Confocal and Two-photon Microscopy: Foundations, Applications, and Advances. New York: John Wiley & Sons, Inc.; 2002.
14. Marriott G, Parker I. Biophotonics, Part A and B. Methods in Enzymology. San Diego: Academic Press; 2003.
15. Prasad PN. Introduction to Biophotonics. New York: Wiley-Interscience; 2003.
16. Betzig E, Trautman JK. Near-field optics: microscopy, spectroscopy, and surface modification beyond the diffraction limit. Science 1992;257:189–195.
17. Lewis A, Radko A, Ben Ami N, Palanker D, Lieberman K. Near-field scanning optical microscopy in cell biology. Trends Cell Biol 1999;9(2):70–73.
18. Lal R, John SA. Biological applications of atomic force microscopy. Am J Physiol 1994;266(1 Pt. 1):C1–C21.
19. Driscoll RJ, Youngquist MG, Baldeschwieler JD. Atomic-scale imaging of DNA using scanning tunnelling microscopy. Nature (London) 1990;346(6281):294–296.
20. Jacobsen C, Lindaas S, Williams S, Zhang X. Scanning luminescence X-ray microscopy:imaging fluorescence dyes at suboptical resolution. J Microsc 1993;172(2):121–129.
21. Hanlon EB, Manoharan R, Koo TW, Shafer KE, Motz JT, Fitzmaurice M, Kramer JR, Itzkan I, Dasari RR, Feld MS. Prospects for *In vivo* Raman spectroscopy. Phys Med Biol 2000;45(2):R1–59.
22. Periasamy A, Skoglund P, Noakes C, Keller R. An evaluation of two-photon excitation versus confocal and digital deconvolution fluorescence microscopy imaging in Xenopus morphogenesis. Microsc Res Tech 1999;47(3):172–181.
23. Periasamy A, Day RN. Visualizing protein interactions in living cells using digitized GFP imaging and FRET microscopy. Methods Cell Biol 1999;58:293–314.
24. Elangovan M, Day RN, Periasamy A. Nanosecond fluorescence resonance energy transfer-fluorescence lifetime imaging microscopy to localize the protein interactions in a single living cell. J Microsc 2002;205(Pt. 1):3–14.
25. Gerritsen HC, Asselbergs MA, Agronskaia AV, Van Sark WG. Fluorescence lifetime imaging in scanning microscopes: acquisition speed, photon economy and lifetime resolution. J Microsc 2002;206(Pt. 3):218–224.
26. Chen Y, Periasamy A. Characterization of two-photon excitation fluorescence lifetime imaging microscopy for protein localization. Microsc Res Tech 2004;63(1):72–80.
27. Berland KM, So PT, Gratton E. Two-photon fluorescence correlation spectroscopy: method and application to the intracellular environment. Biophys J 1995;68(2):694–701.
28. Petersen N. FCS and spatial correlations on biological surfaces. In: Rigler R, Elson EL, editors. Fluorescence Correlation Spectroscopy. Berlin: Springer Verlag; 2001. p 2–35.
29. Lakowicz JR. Principles of Fluorescence Spectroscopy. 2nd ed. New York: Plenum Press; 1999.
30. Göppert-Mayer M. Ueber Elementarakte mit Quantenspreungen. Ann Phys 1931;9:273–295.

31. Haugland RP. Molecular Probes: Handbook of Fluorescent Probes and Research. Eugene, Oregon: Molecular Probes Inc.; 1989.
32. Tsien RY, Waggoner A. Fluorophores for confocal microscopy: photphysics and photochemistry. In: Pawley JB, editor. Handbook of Biological Confocal Microscopy. New York: Plenum Press; 1995. p 267–279.
33. Tsien RY. Imagining imaging's future. Nat Rev Mol Cell Biol 2003;(Suppl):SS16–SS21.
34. Wallrabe H, Periasamy A. Imaging protein molecules using FRET and FLIM microscopy. Curr Opin Biotechnol 2005;16: 19–27.
35. Lemasters JJ, Qian T, Trollinger DR, Muller-Borer BJ, Elmore SP, Cascio WE. Laser scanning confocal microscopy applied to living cells and tissues. In: Periasamy A, editor. Methods in Cellular Imaging. New York: Oxford University Press; 2001. p 66–87.
36. Corrie JET, Katayama Y, Reid GP, Anson M. The development and application of photosensitive caged compounds to aid time-resolved structure determination of macromolecules. Philos Trans R Soc London A Ser 1992;340:233–236.
37. Harper IS. Flurophores and their Labeling Procedures for Monitoring Various Biological Signals. In: Periasamy A, editor. Methods in Cellular Imaging. New York: Oxford University Press; 2001. p 20–39.
38. Miyawaki A, Llopis J, Heim R, McCaffery JM, Adams JA, Ikura M, Tsien RY. Fluorescent indicators for Ca^{2+} based on green fluorescent proteins and calmodulin. Nature (London) 1997;388(6645):882–887.
39. Miyawaki A, Griesbeck O, Heim R, Tsien RY. Dynamic and quantitative Ca^{2+} measurements using improved cameleons. Proc Natl Acad Sci USA 1999;96(5):2135–2140.
40. Ting AY, Kain KH, Klemke RL, Tsien RY. Genetically encoded fluorescent reporters of protein tyrosine kinase activities in living cells. Proc Natl Acad Sci USA 2001;98 (26):15003–15008.
41. Day RN. Visualization of Pit-1 transcription factor interactions in the living cell nucleus by fluorescence resonance energy transfer microscopy. Mol Endocrinol 1998;12(9): 1410–1419.
42. Chen Y, Periasamy A. Time-correlated single photon counting (TCSPC) FLIM-FRET microscopy for protein localization. In: Periasamy A, Day RN, editors. Molecular Imaging: FRET Microscopy and Spectroscopy. New York: Oxford University Press; 2005. Chapt.13.
43. Chen Y, Elangovan M, Periasamy A. FRET data analysis: The algorithm. In: Periasamy A, Day RN, editors. Molecular Imaging: FRET Microscopy and Spectroscopy. New York: Oxford University Press; 2005. Chap. 7.
44. Maddox P, Desai A, Salmon ED, Mitchison TJ, Oogema K, Kapoor T, Matsumoto B, Inoue S. Dynamic confocal imaging of mitochondria in swimming Tetrahymena and of microtubule poleward flux in Xenopus extract spindles. Biol Bull 1999;197(2):263–265.
45. Elangovan M, Wallrabe H, Chen Y, Day RN, Barroso M, Periasamy A. Characterization of one- and two-photon excitation fluorescence resonance energy transfer microscopy. Methods 2003;29(1):58–73.
46. Mills JD, Stone JR, Rubin DG, Melon DE, Okonkwo DO, Periasamy A, Helm GA. Illuminating protein interactions in tissue using confocal and two-photon excitation fluorescent resonance energy transfer microscopy. J Biomed Opt 2003;8(3):347–356.
47. Sekar RB, Periasamy A. Fluorescence resonance energy transfer (FRET) microscopy imaging of live cell protein localizations. J Cell Biol 2003;160(5):629–633.
48. Wallrabe H, Elangovan M, Burchard A, Periasamy A, Barroso M. Confocal FRET microscopy to measure clustering of ligand-receptor complexes in endocytic membranes. Biophys J 2003; 85(1):559–571.
49. Forster T. Delocalized excitation and excitation transfer. In: Sinanoglu O, editor. Modern Quantum Chemistry Part III: Action of Light and Organic Crystals. New York: Academic Press; p 93–137.
50. Clegg RM. Fluorescence resonance energy transfer. In: Wang XF, Herman B, editors. Fluorescence Imaging Spectroscopy and Microscopy. Volume 137, New York: John Wiley & Sons, Inc.; 1996. p 179–251.
51. dos Remedios CG, Miki M, Barden JA. Fluorescence resonance energy transfer measurements of distances in actin and myosin: A critical evaluation. J Muscle Res Cell Motil 1987;8: 97–117.
52. Periasamy A, Wodnicki P, Wang XF, Kwon S, Gordon GW, Herman B. Time-resolved fluorescence lifetime imaging microscopy using a picosecond pulsed tunable dye laser system. Rev Sci Instrum 1996;67(10):3722–3731.
53. Kaiser W, Garrett CGB. Two-photon excitation in CaF2: Eu^{2+}. Phys Rev Lett 1961;7:229–231.
54. Denk W, Strickler JH, Webb WW. Two-photon laser scanning fluorescence microscopy. Science 1990;248(4951):73–76.
55. Denk W, Piston DW, Webb WW. Two-photon molecular excitation in laser-scanning microscopy. In: Pawley JB, editor. Handbook of Biological Confocal Microscopy. New York: Plenum Press; 1995. p 445–458.
56. Szmacinski H, Gryczynski I, Lakowicz JR. Three-photon induced fluorescence of the calcium probe Indo-1. Biophys J 1996;70(1):547–555.
57. Svoboda K, Helmchen F, Denk W, Tank DW. Spread of dendritic excitation in layer 2/3 pyramidal neurons in rat barrel cortex *In vivo*. Nat Neurosci 1999;2(1):65–73.
58. Bacskai BJ, Hickey GA, Skoch J, Kajdasz ST, Wang Y, Huang GF, Mathis CA, Klunk WE, Hyman BT. Four-dimensional multiphoton imaging of brain entry, amyloid binding, and clearance of an amyloid-beta ligand in transgenic mice. Proc Natl Acad Sci USA 2003;100(21):12462–12467.
59. Konig K, Riemann I. High-resolution multiphoton tomography of human skin with subcellular spatial resolution and picosecond time resolution. J Biomed Opt 2003;8(3): 432–439.
60. Soeller C, Jacobs MD, Jones KT, Ellis-Davies GC, Donaldson PJ, Cannell MB. Application of two-photon flash photolysis to reveal intercellular communication and intracellular Ca^{2+} movements. J Biomed Opt 2003;8(3):418–427.
61. Farkas D. Spectral microscopy for quantitative cell and tissue imaging. In: Periasamy A, editor. Methods in Cellular Imaging. New York: Oxford University Press; 2001. Chap. 20.
62. Dickinson ME, Simbuerger E, Zimmermann B, Waters CW, Fraser SE. Multiphoton excitation spectra in biological samples. J Biomed Opt 2003;8(3):329–338.
63. Nashmi R, Dickinson ME, McKinney S, Jareb M, Labarca C, Fraser SE, Lester HA. Assembly of alpha4beta2 nicotinic acetylcholine receptors assessed with functional fluorescently labeled subunits: effects of localization, trafficking, and nicotine-induced upregulation in clonal mammalian cells and in cultured midbrain neurons. J Neurosci 2003;23(37): 11554–11567.
64. Gadella TWJ, Jovin TM, Clegg RM. Fluorescence Lifetime Imaging Microscopy (Flim) - Spatial-Resolution of Microstructures on the Nanosecond Time-Scale. Biophys Chem 1993;48(2):221–239.
65. Gratton E, Breusegem S, Sutin J, Ruan Q, Barry N. Fluorescence lifetime imaging for the two-photon microscope: time-domain and frequency-domain methods. J Biomed Opt 2003;8(3):381–390.
66. Krishnan RV, Masuda A, Centonze VE, Herman B. Quantitative imaging of protein-protein interactions by multiphoton fluorescence lifetime imaging microscopy using a streak camera. J Biomed Opt 2003;8(3):362–367.

67. Redford G, Clegg RB. Real-Time Fluorescence Lifetime Imaging and FRET using Fast Gated Image Intensifiers. In: Periasamy A, Day RN, editors. Molecular Imaging: FRET Microscopy and Spectroscopy. New York: Oxford University Press; 2005. Chapt. 11, in press.
68. Bastiaens PI, Squire A. Fluorescence lifetime imaging microscopy: spatial resolution of biochemical processes in the cell. Trends Cell Biol 1999;9:48–52.
69. Hohng S, Joo C, Ha T. Single-Molecule Three-Color FRET. Biophys J 2004;87(2):1328–1337.
70. Petersen NO, Hoddelius PL, Wiseman PW, Seger O, Magnusson KE. Quantitation of membrane receptor distributions by image correlation spectroscopy: concept and application. Biophys J 1993;65(3):1135–1146.
71. Cheng JX, Volkmer A, Book LD, Xie XS. Multiplex coherent anti-Stokes Raman scattering microspectroscopy and study of lipid vesicles. J Phys Chem B 2002a 106:8493–8498.
72. Cheng JX, Jia YK, Zheng G, Xie XS. Laser-scanning coherent anti-Stokes Raman scattering microscopy and applications to cell biology. Biophys J 2002b;83(1):502–509.
73. Carey PR. Raman spectroscopy, the sleeping giant in structural biology, awakes. J Biol Chem 1999;274(38):26625–26628.
74. Salmaso BL, Puppels GJ, Caspers PJ, Floris R, Wever R, Greve J. Resonance Raman microspectroscopic characterization of eosinophil peroxidase in human eosinophilic granulocytes. Biophys J 1994;67(1):436–446.
75. Puppels GJ, de Mul FF, Otto C, Greve J, Robert-Nicoud M, Arndt-Jovin DJ, Jovin TM. Studying single living cells and chromosomes by confocal Raman microspectroscopy. Nature (London) 1990;347(6290):301–303.
76. Volkmer A, Cheng JX, Xie XS. Vibrational imaging with a high sensitivity via epidetected coherent anti-Stokes Raman scattering microscopy. Phys Rev Lett 2001;87:023901.
77. Uzunbajakava N, Lenferink A, Kraan Y, Volokhina E, Vrensen G, Greve J, Otto C. Nonresonant confocal Raman imaging of DNA and protein distribution in apoptotic cells. Biophys J 2003;84(6):3968–3981.
78. Hawi SR, Rochanakij S, Adar F, Campbell WB, Nithipatikom K. Detection of membrane-bound enzymes in cells using immunoassay and Raman microspectroscopy. Anal Biochem 1998;259(2):212–217.
79. Diem M, Chiriboga L, Lasch P, Pacifico A. IR spectra and IR spectral maps of individual normal and cancerous cells. Biopolymers 2002;67(4–5):349–353.
80. Nan X, Yang WY, Xie XS. CARS microscopy: lights up lipids in living cells. Biophoton Int 2004;11(8):44–47.

See also Cytology, automated; microscopy, confocal; microscopy, electron.

CEREBROSPINAL FLUID. See Hydrocephalus, tools for diagnosis and treatment of.

CHEMICAL ANALYZERS. See Analytical methods, automated.

CHEMICAL SHIFT IMAGING. See Nuclear magnetic resonance spectroscopy.

CHROMATOGRAPHY

Thayne L. Edwards
University of Washington
Seattle, Washington

INTRODUCTION

Chromatography is the process of separating a mobile phase mixture into its individual components using the relative interactions of the components with a stationary phase. Chromatography is often used as a method of purification, even when the components are closely related. When used in conjunction with a concentration or mass-based sensor, it can also be a power analytical method. This chapter explores the basic processes of the various types of chromatography and the closely related techniques of field-flow fractionation (FFF) and electrophoresis. Some of the basic theory of chromatography will be given in terms of retention mechanism and separation performance. In addition, a description of the basic types of chromatography, electrophoresis, and FFF will be given in relation to their theory and application.

Chromatography literally means "color writing" because of an observation in the early 1900s by Mikhail Tswett in separating pigments of plants into various color bands using $CaCO_3$ (1). Although Tswett is considered the father of chromatography, he was not the first to observe the chromatographic process in an experimental setting. Pliny the Elder (ca. 79 AD) recorded a crude paper chromatography experiment. Several others between this time and the realization of the usefulness of chromatography by Tswett also observed the process in the laboratory. It was not until the 1930s that it was recognized generally as an analytical technique (2). Since then, many advances, discoveries, and inventions have made chromatography an indispensable laboratory and industrial technique.

The purpose of chromatographic methods falls under either purification or analysis. Gas chromatography is almost invariably an analytical method whereas liquid chromatography is used for either. As a result of the extensive research into various methods of sample retention, even samples with relatively little difference in their physical or chemical structure can be separated. Chromatographic systems also range in size and complexity from a simple, gravity-fed packed column to a complex high pressure industrial-sized system with integrated components for sample introduction and fraction detection and collection. Often, chromatography is used in conjunction with another analytical method for determination of fraction purity and composition. For medical device instrumentation, chromatography is an invaluable technique that may find its application in a wide variety of ways such as protein purification and sample contamination detection.

Numerous journal articles and books have been written on the subject, as well as reviews (3) and a host of information published on the Internet (2,4–6). Several journals dedicated to chromatography and related fields also exist (Advances in Chromatography, Chromatographia, Biomedical Chromatography, Journal of Chromatography, Journal of Liquid Chromatography and Related Technologies, Journal of Planar Chromatography, Journal of Separation Science). This information is well accessible to anyone who has interest in pursuing the methods and techniques described in this chapter. No attempt has been made here to review all this material. For this reason, this chapter will not focus on the details and extensive literature, but on the


Sample bolus
Column (stationary phase)
Carrier
(mobile phase)
1
2
3
4
5
6
7
...
N
Effluent
Chromatogram (response vs. time)
Component A from t_0-t_1
Component B from t_1-t_2
Component N from t_{n-1}-t_n
Fraction collector
Detector

Figure 1. Depiction of a basic chromatographic system with the major components: carrier or mobile phase, sample bolus, column containing the stationary phase, concentration or mass-based detector, and the effluent. Also shown are the theoretical equilibrium plates, each width being one plate height.

basics and presenting what is generally possible with chromatography.

Chromatographic systems have a mobile phase and a stationary phase. The mobile phase is used to transport the samples through the stationary phase. The mobile phase is inert and does not interact with the sample or stationary phase. The stationary phase is unique for each separation because its purpose is to provide selective interaction with the samples. A simple chromatographic system is depicted in Fig. 1. Apart from the two fundamental required components just mentioned, a system must typically contain a sample injection port and detector in order to be useful as an analytical system. If it is to be used as a purification method, then it must also contain some method of recovering the fractions in the effluent.

The basic operating principle is that samples in the mixture, which interact to a higher degree with the stationary phase, travel slower and are retained longer in the system. This interaction, speed, and retention is relative to samples that interact to a lesser degree and so travel faster and are retained for a shorter duration. The spatial separation occurs in the mobile phase flow direction.

Chromatographic methods are grouped either into *liquid* or *gas* chromatography, based on the carrier phase and further identified by its particular method of sample retention. For example, in size-exclusion chromatography, the stationary phase is a bed of porous beads. The pores allow only samples smaller than a particular size to enter and then exit again. As a result of the pores tortuosity, the travel distance for these smaller samples is longer and thus increases the residence time relative to the larger samples. Some other methods include gas-adsorption, gas-liquid, capillary gas, liquid-adsorption, liquid-liquid, supercritical fluid, ion exchange, and affinity. In addition, the closely related fields of electrophoresis and FFF need to be mentioned as they typically complement chromatographic methods. In order to more fully understand the methods mentioned here, the basic theory will be mentioned first and then a more detailed description of the methods will follow.

GENERAL THEORY

The basic measurement in chromatography is the retention factor. This measurement is calculated from the measured retention times (t_0, t_A, t_B, ..., t_n) in the chromatogram output, as shown in Fig. 2. The void time t_0 is the elution time of an unretained sample. It is the time required to sweep one-column volume. All retention values are calculated relative to this time. The retention factor for sample A, R_A, is then

$$R_A = \frac{t_A - t_0}{t_0}$$

where t_A is the sample residence time. The ability of the separation column to distinguish between two components is quantified in the selectivity term S

$$S_{AB} = \frac{R_S}{R_A}$$

.

For mixtures, the degree of separation between two components is termed the resolution R_S. In most cases, the resolution is the most important factor because that is the purpose of performing chromatographic separations. It is calculated from the retention times t and the peak widths w for the two samples as

$$R_S = \frac{2(t_B - t_A)}{W_B + W_A}$$

The relative distance in the system at which a degree of equilibrium between the two phases occurs is referred to as a theoretical plate. Chromatographic systems usually have many theoretical plates. By dividing the length of the column L with the number of plates N gives the plate height, or height of an equivalent theoretical plate H. These numbers characterize the quality of the retention and can be determined from a chromatogram by assuming



Figure 2. Chromatogram of separation of a two-component mixture. The retention times are measured from the injection time.



Figure 3. Chromatogram of single peak from response of mass- or concentration-based detector showing measurements for determining the number of theoretical plates.

that the peaks are Gaussian shaped, as shown in Fig. 3. It is noted that this method is for an ideal situation and that other methods are available for peaks of other shapes. The sample peak width is measured either at baseline w or at half-height, $w_{1/2}$. In practice, it is more convenient and accurate to measure at half-height

$$N = 5.54\left(\frac{t_R}{W_{1/2}}\right)^2$$

and

$$H = \frac{L}{N}$$

Plate height is a summation of three effects, two of which are dependent on flow rate. This theory was proposed by van Deemter et al. (7). The first effect is due to equipment and users, such as column-packing and injection variabilities, and is not a function of the flow rate. This term can be minimized through careful design and manufacturing of the column. The use of automated sample handling also helps to reduce this effect. At low flow velocities u, molecular diffusion of the sample in the carrier dominates and peak broadening rises quickly. At higher flow velocities the sample plug broadens due to nonequilibrium effects such as eddy diffusion and multiple paths in the stationary phase. The van Deemter equation is

$$H = H_0 + H_1(u^{-1}) + H_2(u)$$

This equation is easily graphed (Fig. 4) for a visual indication of the optimal flow rate. In practice, it is best to have the flow rate slightly higher than at the optimum to avoid the region of rapid plate height increase. Each of the terms is dependent on the type of chromatography used.

Now, the resolution of the separation can be put in terms of plate height or the equivalent number of theoretical plates,

$$Rs_{AB} = \frac{\sqrt{N}}{4}\left[\frac{S_{AB}-1}{S_{AB}}\right]\left[\frac{1+R_B}{R_B}\right]$$



Figure 4. The van Deemter plot, based on the van Deemter equation for determining the optimal flow rate for a given chromatographic separation.

This form is useful for optimizing a separation based on the three groups in the equation. Resolution can be increased by increasing the number of theoretical plates, which can be accomplished by both increasing the column length and minimizing the plate height using the van Deemter plot. However, increasing the column length will also cause proportional band broadening, and so it is not always ideal. The second term involves adjusting the selectivity through column modifications such as changing either or both of the phases and the temperature. The temperature also plays an important role in the last term as well. By adjusting and tuning these parameters, nearly every difficult separation can be successfully resolved. Theoretically, choosing the proper stationary phase for the column and an appropriate mobile phase, any two materials can be separated. These phases are at the heart of chromatography.

TYPES OF CHROMATOGRAPHY AND RELATED TECHNOLOGIES

The mobile phase is either a gas, a liquid, or a supercritical fluid, whereas the stationary phases can be either a solid or a liquid. The types of chromatography are typically named by their phases or interaction process and are categorically divided by their stationary phase into either gas chromatography (GC) or liquid chromatography (LC). Another variation on LC is high performance liquid chromatography (HPLC), in which the carrier is driven by pressure. Some common subclasses of LC and GC are based on ion-exchange, phase change, adsorption, size exclusion, partitioning, and absorption. Specific types and hybrid systems also exist that fall under each of these categories. Each of these complements the others to build a broad spectrum of types of chromatographic separation technique available (8–11).

Gas Chromatography (GC)

Gas chromatography makes use of a pressurized gas cylinder and a carrier gas, such as helium, to carry the solute through the column. GC can be used for both purification and analysis, when a detector is used in tandem. Common detectors used in GC are thermal conductivity and flame ionization detectors. Many more types of detectors exist, each with its advantages and disadvantages. Three types of GC that are among the more common methods are gas adsorption, gas-liquid, and capillary gas chromatography.

Gas Adsorption. Gas adsorption chromatography has a solid stationary phase packed bed. The samples selectively adsorb and desorb to the stationary phase, effectively increasing each sample's retention time based on its isotherm. Some of the more common adsorbents used are silica, zeolite, and activated alumina. This method is the primary method for separating mixtures of gases.

Gas-Liquid. Separation in gas-liquid chromatography is based on the gaseous samples partitioning with a viscous liquid stationary phase. This liquid is supported in the column by coating a solid, most commonly diatomaceous earth. The solid support to the stationary phase liquid is inert to the samples. The sample retention time is governed by the rate at which it dissolves into and vaporizes out of the liquid. Thus, the relative partitioning of each of the samples in the liquid stationary phase is the basis of the separation.

Capillary Gas. In this method, the stationary phase is a capillary coated with a liquid (wall-coated open tubular) or a solid-coated capillary onto which the liquid is adsorbed (support-coated open tubular), as has been described in the previous two methods. Liquid or gum temperature stable polymers are used as the stationary phase. Most common polymers used are poly-ethylene glycol or poly-siloxanes. Also used are molecular sieves and alumina particles. Unlike the previous methods, the stationary phase has a small volume due to the capillary geometry and is thus limited to the amount of sample that can interact. However, because of the small column geometry, the partitioning or adsorption of the sample is relatively fast. The capillary is typically glass or fused silica coated with polyimide for support. The tubing (column) can be long and also be wound into tight areas for compactness and good temperature control. It is the most common gas chromatography analytical method.

Liquid Chromatography (LC) and High Performance Liquid Chromatography (HPLC)

As the carrier phase in LC is a liquid, it is naturally more amenable for biological separations and analysis, such as the purification of proteins. However, it is also amenable to any sample dissolved in a liquid. In LC, the carrier is driven by gravity through the column. These columns, made of glass or plastic and sometimes disposable, are typically used for lab-scale preparative work. For analysis of samples, the carrier is pressurized for increased speed and sample resolution. This variation is termed high performance liquid chromatography or HPLC. These systems are much more complex and costly. The columns are made of steel to withstand high pressures and are reused a number of times. Detectors are also placed inline with these columns for analysis, although HPLC is also used in preparative work as well (3,6,11–14).

Liquid Adsorption. Liquid adsorption, also termed liquid-solid chromatography, uses a solid stationary phase made of particles such as alumina or silica. In particular, this method is used in separating isomers. The retention is based on the adsorption/desorption kinetics of each sample onto the particles. Liquid adsorption is often found in large-scale applications because the adsorbent beds are relatively inexpensive.

Liquid-Liquid. In liquid-liquid chromatography (LLC), also called partition chromatography, the stationary phase is a liquid-coated solid surface. This liquid is immiscible with the liquid solvent mobile phase. Retention is based on partitioning of the sample between the two phases. LLC can be accomplished in either *normal* phase or *reverse* phase. Normal phase has a nonpolar mobile phase and polar stationary phase. Reverse phase is the opposite of having a polar mobile phase and nonpolar stationary phase. It is used primarily in separating nonvolatile components of mixtures and is similar to a chemical extraction process.

Size Exclusion. This method was described briefly in the introduction. It is somewhat unique because the stationary phase is inert to the sample. The increased path length due to tortuous pores that exclude large samples causes an increased retention time for samples smaller than the cut-off size. It is also referred to as filtration, gel permeation, or molecular-sieve chromatography. This method is useful for protein separation and purification such as in antibody production and buffer exchange applications.

Supercritical Fluid. Unlike the other methods, supercritical fluid chromatography is characterized by its unique carrier fluid. Supercritical fluids used to carry the sample have very high viscosities and molecular diffusivities compared with liquids but with densities on the same order. One type of supercritical fluid used is a mixture of carbon dioxide and modifiers. Implementation of this technique is difficult because of the high temperature and pressures to reach the supercritical fluid state.

Ion-Exchange. Ion-exchange chromatography is commonly used in the purification of biological materials, such as amino acids and proteins, and also ions in solution. This method is capable of quantifying samples in the ppb to ppm concentration range. The stationary phase is an ion-exchange resin that is either cationic or anionic. Charged atoms or molecules in the liquid phase sample bind to the stationary phase as they are passed through the column. The sample is released by adjusting the carrier pH or ionic strength. Separation by this method is highly selective and especially useful for anions in which separations are typically slow. The resins are typically high capacity and inexpensive.

Affinity. Affinity chromatography has a stationary phase that is highly selective to one particular sample.

Unlike other chromatographic methods, the sample is highly bound to the stationary phase until the carrier solution is changed and the sample released. To accomplish this selective release, the stationary phase is engineered using an inert affinity matrix, such as agarose or cellulose derivative, and infused with ligand molecules that are design to bind only the sample of choice. Immunologic interactions of specific antibody-antigen pairs are particularly useful because of the high specificity that can be obtained and the reversibility of the binding event. The addition of a high salt concentration or low pH to the stationary phase reverses the selectivity, similar to ion-exchange chromatography, and allows the release of the sample after the other components of the mixture have been washed away. Care must be taken to ensure that impurities do not foul the matrix. Some preprocessing is typically accomplished prior to the separation to remove the potential fouling components. This method is used often with biological samples.

Electrophoresis

Electrophoresis is a separation method using the transport of electrically charged compounds in a conductive liquid environment under the influence of an electric field (15,16). Positively charged molecules migrate toward a negative electrode, and negatively charged molecules migrate toward a positive electrode. It is regularly applied in analytical chemistry to determine the constituent molecules of a compound. It is also widely used in medical diagnostics and other biological areas to determine molecules within biological samples, such as protein and DNA. From the various modes of electrophoresis, capillary electrophoresis (CE) is the most widely used separation method used in a modern analytical laboratory (17). High separation speed, excellent resolution power, and low consumption of buffer and sample are some of the advantages. Typically, samples are injected into a capillary tube with diameters ranging between 25 and 100 μm, and an electrical field is applied along the capillary tube to separate compounds based on the differences in charge to mass ratio. Negatively ionized surface silanol group of the capillary creates an electrical double layer at the solid/liquid interface to preserve electroneutrality, and this mobile layer is pulled toward the negatively charged electrode when an electric field is applied. These ion layers drag the bulk buffer solution, causing an electro-osmotic flow. Compared with HPLC, which has a parabolic flow profile due to the laminar flow inside the channel, the flow profile is flat in the electro-osmotic flow, which helps the detection peak to be very sharp, increasing its sensitivity. Laser-induced fluorescence detection is the most widely used method for detecting the separated molecules (18). Over 100 review articles exist covering capillary electrophoresis, and Beale wrote an excellent review categorizing these articles (19).

Development in microfabrication technologies and the lab-on-a-chip concept in the early 1990s further expanded the role of this powerful analysis technique (20–22). Smaller sample injection into a microchannel and higher electric field result in short analysis time with excellent resolution. Applying higher electric field is possible due to the high surface-to-volume ratio of a microchannel that can dissipate the heat produced during electrophoresis faster. Automated sample injection and capability to perform the separation on arrays of microchannel in conjunction with the short analysis time enables high throughput analyses. Low manufacturing cost due to the batch fabrication capability of the microchips is another advantage over conventional separation technologies. Fig. 5 shows a typical channel configuration for a capillary electrophoresis microchip. High voltages are applied between reservoir 1 and 2 so that the sample in reservoir 1 fills the injection channel. Once the injection channel is filled, the high voltages are switched to reservoir 3 and 4, and the sample plug in the cross section gets injected into the separation channel. As the sample plug moves down the separation channel, separation occurs depending on the charge to mass ratio of the compounds being analyzed. In fluorescence detection, detection typically occurs at the end of the separation channel by illuminating the fluorescence-tagged sample with laser or UV light, followed by light detection using a photomultiplier tube (PMT).

Typical channels are several tens to hundreds of microns wide, a couple tens of microns deep, and the separation channel lengths are in the centimeter scale. Electric fields applied to these channels range in kV/cm scale. This high electric field and small sample size enables separation within several seconds compared with tens of minutes required in conventional chromatography, which can be of great benefit when monitoring time-dependent reactions, such as conducting an enzyme kinetic study (23). This system also enables automatic sample injection because voltages can be simply switched between reservoirs to inject samples into the separation channels without the need for manual sample loading, which further reduces the time associated with sample analyses. Several other sample injection schemes have been also studied. Instead of using a simple cross-channel injector, twin-T injectors can be used to further control the sample plug size (24). Electrical biasing of the different reservoirs such as



Figure 5. Typical channel configuration for a capillary electrophoresis microchip including loading or injection channel and separation channel.



Figure 6. CE microchip fabricated in borosilicate glass. Serpentine separation channel can be observed.

pinch injection can reduce band broadening of the sample plugs caused by leakage at the intersection of the injection channel (25). Fig. 6 shows a CE microchip made in borosilicate glass. Serpentine separation channel was created to have a longer separation channel within a compact geometry.

The most common material used for the microchip is glass. Some of the earliest capillary electrophoresis microchips were fabricated in glass due to the good optical properties, a surface that enables electro-osmotic flow, and well-developed microfabrication techniques. To further reduce the microchip fabrication cost, polymer materials have been used due to the low material cost and easy mass-fabrication processes. Injection molding or hot embossing of plastics and polymer casting of polydimethylsiloxane (PDMS) are some of the methods used (26–28).

The application of this technology has been expanded from simple chemical analysis to biological applications, such as DNA sequencing, immunoassay, and biological particle separation (viruses, bacteria, and eukaryotic cells) (22,29–31). DNA sequencing on microchips was first reported by Mathies in 1995 (32). Single base resolution reached 150–200 bases in 10–15 min. Some of the advantages on top of the excellent resolution and short analysis time are the capability for high throughput. The compact size of the separation channels enable a large number of channels to be placed close together, which also facilitates fast detection using optical imaging or scanning lenses. To pack even more channels into a small area, a 6 inch circular glass plate carrying 96 radical channels conversing at the center of the chip was also developed (33). Detection occurred using a spinning confocal system. Separation of antigen and antibody from the corresponding anti-body-antigen complex can be separated using microchip CE for immunoassays (34). Automatic sample injection capability can possibly eliminate the need of conventional robotic sample injection, which is commonly used in life science laboratories. More complex operations, by using electro-osmotic flow in conjunction with other operations such as lysing and concentration, have been demonstrated to show transport and analysis of biological particles (35–37). Dual injection has been also used where sample and reagents can be mixed on-column and analyzed to provide information about reaction kinetics, to perform on-column derivatization for improved separation and termination, and to develop methods for simultaneous analysis of anionic and cationic compounds (38). Electro-osmotic flow in microchannels has been used in numerous applications to transport and mix fluid and particles but is beyond the subject of this chapter (39,40).

Electrophoresis with Other Separation/Detection Methods

One of the advantages of capillary electrophoresis is that this technique is easy to combine with different separation and detection methods to provide even more versatile, powerful, and efficient analysis tools. Isoelectric focusing (IEF) is a separation technique to resolve amphoteric molecules based on their isoelectric points (pI) (41). Isoelectric point is the pH at which a molecule carries no net electric charge. In capillary isoelectric focusing (CIEF), the capillary is first filled with a mixture of ampholytes and samples (42). When an electric field is applied to the capillary, a pH gradient is formed inside the capillary and the sample molecules migrate and stop at a position where the pH equals the pI of the sample molecules due to the loss of their net charges. In a one-step process, the entire capillary is illuminated to obtain images of the separation. In a two-step process, the separated samples are mobilized to the detection point using chemical, hydrodynamic, or electro-osmotic flow mobilization to simplify the detection equipments. When analyzing mixture of peptides in a microchip-based CIEF, focusing time of less than 30 seconds and total analysis time as short as 5 minutes is possible. As a result of the high resolving power, this method is most commonly used for studying peptides, proteins, recombinant products, cell lysates, and other complex mixtures (43,44).

Although capillary electrophoresis can provide excellent resolution, it is challenging to identify unknown substances. Mass spectrometry is a technique used for separating ions by their mass to charge ratios that enables identification of compounds by the mass of one or more elements in the compounds and enables determination of isotopic composition of one or more elements in the compound. By coupling capillary electrophoresis with mass spectrometry, direct identification of analytes by molecular mass, selectivity enhancement, and insight into the molecular structures are possible (43,44). The most prominent application of this combination is in proteomics (45). Interfacing these two techniques is of great importance because mass spectrometry requires ionized gas as samples whereas the output from a CE system is fluid (46). Electrospray ionization (ESI) and matrix-assisted laser desorption/ionization (MALDI) are some of the most widely used ionization methods. ESI, first developed in the 1980s, is the softest ionization technique currently available. It transforms ions in solution into ions in gas phase based on the electrostatic effects in solutions. An electric potential applied to an electrospray tip breaks the solution containing mixture of samples and solvents into small charged droplets. The shrinkage of the charged droplets by solvent evaporation further disintegrates the drops and forms gas-phase ions. MALDI uses laser beams to ionize samples located inside a crystallized bimolecular matrix that is used to protect the sample from being destroyed by direct laser beam. For microchip-based capillary electrophoresis systems, efforts have been focused on developing on-chip electrospray ionization techniques so that coupling to MS systems are efficient (47). The ultimate goal of such a coupled system is to use the microchip for fast and convenient sample preparation followed by online sample introduction for MS analysis. Beyond proteomics, the CE-ESI-MS combination has been widely used for drug analysis, food analysis, achiral and chiral solutes analysis, glycoscreening, and metabolic disorder screening (48–52).

Other detection methods used include electrochemical detection (53), electrochemiluminescence, nuclear magnetic resonance (NMR), ultraviolet resonance Raman spectroscopy (54,55).

Field-Flow Fractionation

Another technique similar in many ways and complementary to chromatography is field-flow fractionation (FFF). It is relatively young compared with chromatography, proposed by Giddings in 1968. This technique is always performed in an open channel (no packing or coatings) that is usually, but not restricted to, a wide, flat geometry with the breadth to height ratio being greater than 100 (Fig. 7). The purpose of this geometry is to take advantage of the laminar velocity parabolic flow profile of the carrier while minimizing secondary dispersion effects from the sidewalls. Circular channels can also be used in this way but are difficult to implement a uniform field in. Just as in chromatography, the samples spatially separated along the length of the channel are eluted discretely at the outlet, if enough column length and separating power are provided. For this reason, chromatographic principles and basic theory also apply to FFF. For example, FFF system retentions are often characterized by the number of theoretical plates and the van Deemter theory and the separations are characterized by resolution. However, some distinct differences exist that demonstrate the unique and complementary characteristics of FFF.

The first difference between FFF and chromatography is that a force field is applied to affect the samples instead of a stationary phase. The second difference is that the field is applied normal to the flow and separation direction. In chromatography, this field always acts opposite to the direction of the separation. The third difference is that, in most simple FFF systems, a direct mathematical relationship exists between the field and sample elution time.

The mechanism of retention and separation in FFF systems is based on compartmentalizing the various samples in the mixture to velocity zones in the parabolic flow profile of the carrier. The samples are selectively perturbed using a field applied normal to the carrier flow that are then concentrated at the accumulation wall. Normal diffusion opposes this movement until an equilibrium condition is established. Each sample will form a layer thickness based on its degree of perturbation. The sample specific velocity is then obtained from the first moment of the concentration and velocity profiles. The exact mathematical relationship among the variables in each of these steps allows for the determination of specific sample properties based solely on the elution time. A simple concentration or mass-based detector is sufficient without the need for calibration as in chromatography. In practice, this type of analysis is complicated by other factors leading to the need for calibration or more complicated detectors.

Any type of field or combination of fields can, in theory, be used to drive the separation. Some of the common fields used are sedimentary, flow, thermal, and electric. Some less common fields include magnetic, acoustic, dielectric, and others.

Recent advancements in FFF have included miniaturization of FFF channels. Miniaturization not only reduces sample and carrier volume requirements but also enhances



Figure 7. *Top*: Representation of a typical FFF channel. *Bottom*: Cross-sectional slice of channel in the center along the length and showing the operational principles of a separation in FFF. The required components for retention are a parabolic velocity profile and sample selective field.

retention and separation in some cases. Some of the systems that benefit through field enhancement from reducing the scale are thermal, electric, magnetic, and dielectrophoretic. In addition, microscale and nanoscale fabrication technologies have also made possible the implementation of systems that were previously impossible, difficult, or unreasonable to try, such as acoustic, magnetic, and dielectrophoretic FFF, as well as combinations of these systems.

Several microscale systems have been successfully implemented: micro-electric FFF (56–60); micro-thermal FFF (61–66); and AcFFF by Edwards and Frazier (67). Gale also integrated an electrical impedance detector within the channel to minimize the plate height due to extracolumn volumes in the detector and between the column and detector (56). Both Gale and Edwards also developed sample injection methods to minimize plate height further (56,61).

Systems manufactured using microelectricalmechanical system (MEMS) technologies are not only suitable for creating an inexpensive, disposable analysis device, but also for integrating with other methods such as chromatography, sensors, fluid handling devices, and actuators to create a total analysis system, or lab-on-a-chip. FFF can be used as a sample preparation tool, analytical device, or both in these systems.

CONCLUSION

Chromatography and the closely related fields of FFF and electrophoresis have proven to be valuable methods over the last century for separation, purification, and analysis. As a result of the wide variety and combinations of phases used in chromatography and fields applied in FFF, the number of types of samples that have been or can be retained and separated in these systems appears to be endless. Further advances in column, carrier, and detector technology, such as miniaturization, will continue to push the limits outward and make available faster and higher quality separations. In turn, researchers and industries in fields such as chemical engineering, bioengineering, chemistry, and pharmaceutics that rely on these techniques will also advance.

BIBLIOGRAPHY

1. Tswett M. Physical chemical studies on chlorophyll adsoptions. Berichte der Deutschen botanischen Gesellschaft 1906;24: 316–323.
2. Lesney MS. A brief history of “color writing.” Today’s Chemist at Work 1998;7(8):67–72.
3. Dorsey JG, et al. Liquid chromatography: Theory and methodology. Analyt Chem 1998;70(12):591R–644R.
4. Carrier R, Yip K. Intro to Chromatography. Available http://www.rpi.edu/dept/chem-eng/Biotech-Environ/CHROMO/chromintro.html.
5. Hardy JK. Analyt Chem. Available http://ull.chemistry.vakron.edu/analytical/.
6. Kazakevich Y, McNair H. Basic liquid chromatography. Available http://hplc.chem.shu.edu/NEW/HPLC_Book/.
7. van Deemter J, et al. Longitudinal diffusion and resistance to mass transfer as causes of nonideality in chromatography. Chem Eng Sci 1956;5:271–289.
8. Brede C, Pedersen-Bjergaard S. State-of-the art of selective detection and identification of I^-, Br^-, Cl^-, and F-containing compounds in gas chromatography and liquid chromatography. J Chromatogr A 2004;1050(1):45.
9. Gonzalez FR. Application of capillary gas chromatography to studies on solvation thermodynamics. J Chromatog A 2004; 1037(1-2):233.
10. Roubani-Kalantzopoulou F. Determination of isotherms by gas-solid chromatography: Applications. J Chromatogr A 2004;1037(1-2):191.
11. He L, Beesley TE. Applications of enantiomeric gas chromatography: A review. J Liquid Chromatogr Related Technol 2005; 28(7-8):1075.
12. Abraham MH, et al. Hydrogen bonding. 42. Characterization of reversed-phase high-performance liquid chromatographic C-18 stationary phases. J Phys Organ Chem 1997;10(5):358–368.
13. Sherma J. High-performance liquid chromatography/mass spectrometry analysis of botanical medicines and dietary supplements: A review. J AOAC Int 2003;86(5):873.
14. Petrovic M, et al. Liquid chromatography-tandem mass spectrometry for the analysis of pharmaceutical residues in environmental samples: A review. J Chromatogr A 2005;1067(1-2):1.
15. Kuhn R. Hoffstetter-Kuhn S. Capillary Electrophoresis: Principles and Practice. Berlin, Germany: Springer-Verlag; 1993.
16. Baker DR. Capillary Electrophoresis. New York: Wiley-Interscience; 1995.
17. Horvath C, Nikelly JG. Capillary Electrophoresis and Chromatography. Washington, DC: American Chemical Society; 1990.
18. Nouadje G, et al. Capillary electrophoresis with laser-induced fluorescence detecion: Optical design and applications. Progress in HPLC-HPCE 1997;5:49–72.
19. Beale SC. Capillary electrophoresis. Analyt Chem 1998;70:279R–300R.
20. Effenhauser CS. Integrated chip-based microcolumn separation systems. Topics Curr Chem 1998;194:51–81.
21. Regnier FE, et al. Chromatography and electrophoresis on chips: critical elements of future integrated, microfluidic analytical systems for life science. Trends Biotechnol 1999;17(3): 101–106.
22. Dolnik V, et al. Capillary electrophoresis on microchip. Electrophoresis 2000;21:41–54.
23. Starkey DE, et al. A fluorogenic assay for b-glucuronidase using microchip-based capillary electrophoresis. J Chromatogr B 2001;762:33–41.
24. Effenhauser CS, et al. Glass chips for high-speed capillary electrophoresis separations with submicrometer plate heights. Analyt Chem 1993;65:2637–2642.
25. Jacobson SC, et al. Effects of injection schemes and column geometry on the performance of microchip electrophoresis devices. Analyt Chem 1994;66:1107–1113.
26. Effenhauser CS, et al. Integrated chip-based capillary electrophoresis. Electrophoresis 1997;18:2203–2213.
27. Martynova L, et al. Fabrication of plastic microfluidic channels by imprinting methods. Analyt Chem 1997;69:4783–4789.
28. McCormick RM, et al. Microchannel electrophoretic separations of DNA in injection-molded plastic substrates. Analyt Chem 1997;69:2626–2630.
29. Colyer CL, et al. Clinical potential of microchip capillary electrophoresis systems. Electrophoresis 1997;18:1733–1741.
30. Effenhauser CS, et al. Integrated capillary electrophoresis on flexible silicone microdevices: Analysis of DNA restriction fragments and detection of single DNA molecules on microchips. Analyt Chem 1997;69:3451–3457.
31. Carrilho E. DNA sequencing by capillary array electrophoresis and microfabricated array systems. Electrophoresis 2000;21: 55–65.
32. Woolley AT, Mathies RA. Ultra-high-speed DNA sequencing using capillary electrophoresis chips. Analyt Chem 1995;67: 3676–4086.

33. Simpson PC, et al. High-throughput genetic analysis using microfabricated 96-sample capillary array electrophoresis microplates. Proc Nat Acad Sci USA 1998;95:2256–2261.
34. Chiem N, arrison HDJ. Microchip-based capillary electrophoresis for immunoassays: analysis of monoclonal antibodies and theophylline. Analyt Chem 1997;69:373–378.
35. Li PCH, Harrison DJ. Transport, manipulation, and reaction of biological cells on-chip using electrokinetic effects. Analyt Chem 1997;69:1564–1568.
36. Cabrera CR, Yager P. Continuous concentration of bacteria in a microfluidic flow cell using electrokinetic techniques. Electrophoresis 2001;22:355–362.
37. Kremser L, et al. Capillary electrophoresis of biological particles: Viruses, bacteria, and eukaryotic cells. Electrophoresis 2004;25:2282–2291.
38. Priego-Capote F, Castro MDLd. Dual injection capillary electrophoresis: Foundations and applications. Electrophoresis 2004;25:4074–4085.
39. Debesset S, et al. An AC electro-osmotic micropump for circular chromatographic applications. Lab Chip 2004;4:396–400.
40. Glasgow I, et al. Electro-osmotic mixing in microchannels. Lab Chip 2004;4:558–562.
41. Hofmann O, Che D, Cruickshank KA, Muller UR. Adaptation of capillary isoelectric focusing to microchannels on a glass chip. Analyt Chem 1999;71:678–686.
42. Tan W, Fan ZH, Qiu CX, Ricco AJ, Gibbons I. Miniaturized capillary isoelectric focusing in plastic microfluidic devices. Electrophoresis 2002;23:3638–3645.
43. Shimura K. Recent advances in capillary isoelectric focusing: 1997–2001. Electrophoresis 2002;23:3847–3857.
44. Kilar F. Recent applications of capillary isoelectric focusing. Electrophoresis 2003;24:3908–3916.
45. Simpson DC, Smith RD. Combining capillary electrophoresis with mass spectrometry for applications in proteomics. Electrophoresis 2005;26:1291–1305.
46. Schmitt-Kopplin P, Frommberger M. Capillary electrophoresis-mass spectrometry: 15 years of development and applications. Electrophoresis 2003;24:3837–3867.
47. Sung W-C, Makamba H, Chen S-H. Chip-Based microfluidic devices coupled with electrospray ionization-mass spectrometry. Electrophoresis 2005;26:1783–1791.
48. Smyth WF. Recent applications of capillary electrophoreis-electrospray ionization-mass spectrometry in drug analysis. Electrophoresis 2005;26:1334–1357.
49. Simo C, Barbas C, Cifuentes A. Capillary electrophoresis-mass spectrometry in food analysis. Electrophoresis 2005;26:1306–1318.
50. Shamsi SA, Miller BE. Capillary electrophoresis-mass spectrometry: Recent advances to the analysis of small achiral and chiral solutes. Electrophoresis 2004;25:3927–3961.
51. Zamfir A, Peter-Katalinic J. Capillary electrophoresis-mass spectrometry for glycoscreening in biomedical. Electrophoresis 2004;25:1949–1963.
52. Senk P, Kozak L, Foret F. Capillary electrophoresis and mass spectrometry for screening of metabolic disorders in newborns. Electrophoresis 2004;25:1447–1456.
53. IV WRV, Pasas-Farmer SA, Fischer DJ, Frankenfeld CN, Lunte SM. Recent developments in electrochemical detection for microchip capillary electrophoresis. Electrophoresis 2004; 25:3528–3549.
54. Qiu H, Yan J, Sun X, Liu J, Cao W, Yang X, Wang E. Microchip capillary electrophoresis with an integrated indium tin oxide electrode-based electrochemiluminescence detector. Analyt Chem 2003;75:5435–5440.
55. Wolters AM, Jayawickrama DA, Webb AG, Sweedler JV. NMR detection with multiple solenoidal microcoils for continuous-flow capillary electrophoresis. Analyt Chem 2002;74:5550–5555.
56. Gale BK, et al. A micromachined electrical field-flow fractionation (mu-EFFF) system. IEEE Trans Biomed Eng 1998;45(12):1459–1469.
57. Gale BK, et al. Geometric scaling effects in electrical field flow fractionation. 1. Theoretical analysis. Analyt Chem 2001;73 (10):2345–2352.
58. Gale BK, et al. Geometric scaling effects in electrical field flow fractionation. 2. Experimental results. Analyt Chem 2002;74(5):1024–1030.
59. Gale BK. Novel techniques and instruments for field flow fractionation of biological materials. Abstr Papers Am Chem Soc 2003;225:U138–U138.
60. Gale BK. Miniaturized field flow fractionation systems. Abstr Papers Am Chem Soc 2004;227:U116–U116.
61. Edwards TL, et al. A microfabricated thermal field-flow fractionation system. Analyt Chem 2002;74(6):1211–1216.
62. Schimpf ME, Polymer analysis by thermal field-flow fractionation. J Liquid Chromatogr Related Technol 2002;25 (13-15):2101–2134.
63. Janca J. Micro-channel thermal field-flow fractionation: High-speed analysis of colloidal particles. J Liquid Chromatogr Related Technol 2003;26(6):849–869.
64. Janca J, Ananieva IA. Micro-thermal field-flow fractionation in the characterization of macromolecules and particles: Effect of the steric exclusion mechanism. E-Polymers 2003.
65. Janca J, et al. Effect of channel width on the retention of colloidal particles in polarization, steric, and focusing micro-thermal field-flow fractionation. J Chromatogr A 2004;1046 (1-2):167–173.
66. Bargiel S, et al. A micromachined system for the separation of molecules using thermal field-flow fractionation method. Sens Actuators A-Phys 2004;110(1-3):328–335.
67. Edwards TL. Microfrabricated acoustic and thermal field-flow fractionation systems. Electrical and computer engineering. Atlanta, GA: Georgia Institute of Technology; Ph.D. thesis, 2005. p 300.

See also ANALYTICAL METHODS, AUTOMATED; PHARMACOKINETICS AND PHARMACODYNAMICS; TRACER KINETICS.

CO_2 ELECTRODES

JOHN W. SEVERINGHAUS
University of California in San Francisco
San Francisco, California

METHODS OF MEASURING BLOOD pCO_2 BEFORE DISCOVERY OF THE pCO_2 ELECTRODE

Bubble Equilibration Methods

Carbon dioxide in blood is largely in the form of the bicarbonate ion, which could be converted to CO_2 gas by adding acid and extracting the gas in a vacuum. The concept of partial pressures gradually stimulated interest in measuring pCO_2 in the late nineteenth century. Gas analysis had been developed earlier, so the first method was to equilibrate a small gas bubble with a large volume of blood sample at body temperature, and then remove the bubble for gas analysis. Pflüger developed a tonometer for this purpose in the 1870s, and August Krogh used this method in fish in the early twentieth century. It was developed into a clinical and laboratory method by Richard Riley, using a specially adapted syringe with a capillary attached, which was invented by F. J. W. Roughton and P. Scholander during World War II. Riley's bubble method worked well for pCO_2, but poorly for pO_2 especially when blood was saturated with oxygen.

The Henderson–Hasselbalch Method

The most accurate early method was made possible by L. J. Henderson's discovery of buffering and his equation in 1908, its logarithmic modification by K. A. Hasselbalch in 1916, and P. T. Courage's design of a glass pH electrode (1925) in which blood could be measured with little loss of CO_2 to air. Blood pH was determined, usually at room temperature, there being no thermostated electrodes, and the Rosenthal temperature correction (-0.0147 pH units/°C) was used to compute pH at 37 °C. Plasma CO_2 content was determined in the Van Slyke manometric apparatus that used 1 mL of plasma (after carefully centrifuging blood under a gas tight seal, a floating cork). This method reached a precision of 0.3 mmHg pCO_2 in studies of the arterial to alveolar pCO_2 difference during surgical hypothermia at The National Institute of Health (NIH) (5).

Astrup and The Equilibration Method

Hundreds of patients with polio needed artificial ventilation in the communicable disease hospital in Copenhagen during epidemics in 1950–1952. Poul Astrup, M.D. (Professor of Clinical Chemistry, University of Copenhagen, Copenhagen, Denmark, and Director of the Clinical Laboratory, Rigshospitalet, Copenhagen, Denmark) and his associates, particularly Ole Siggaard Andersen, Ph.D., M.D. (Professor of Clinical Chemistry, University of Copenhagen, and Director, Clinical Chemistry Laboratory, Herlev Hospital, Copenhagen, Denmark), devised a way of determining blood pCO_2 using only a pH electrode to measure pH before and after equilibration of a blood sample with two known concentrations of pCO_2(6). Astrup made use of the little known fact that, as pCO_2 is changed, the relationship of pH to pCO_2 in a given blood sample is semilogarithmic (Fig. 1). By plotting the two measured values of pH at the known equilibrated pCO_2, he could graphically interpolate the pCO_2 from the original sample pH.

From 1954 until the mid-1960s, Astrup's method was made widely available by the Radiometer Co. of Copenhagen. The device had a thermostated capillary pH electrode, reference electrode, and tiny shaking equilibrator through which humidified gas flowed. Astrup's apparatus and method became obsolete with the introduction of the CO_2 electrode.

Ole Siggaard Andersen, Astrup, and others used the values obtained for pH and pCO_2 to calculate bicarbonate, total CO_2, and base excess, a term they introduced as a quantitative measure of the nonrespiratory or metabolic abnormality in a whole blood sample. Base excess proved to be the first accurate index of the nonrespiratory component of acid–base balance (7). Its first application was only for blood, but by 1966, it was shown to apply to the extracellular fluid of the entire body if one assumed an average extracellular fluid hemoglobin concentration of 5 g/dL.



Figure 1. Equilibration method for measuring arterial pCO_2 introduced by Astrup during the Copenhagen polio epidemic, 1952–1954. Log pCO_2 plotted versus pH results in straight lines with varying pCO_2, and shifts of pH and slope when blood is acidified or alkalinized. The shift gave rise to the concept of base excess.

THE CO_2 ELECTRODE

History

A carbon dioxide (CO_2) electrode was first described by physiologists Gesell and McGinty at the University of Michigan in 1926, for use in expired air, but not in blood (8). It used the effect of CO_2 on the pH of a film of peritoneal membrane wet with a salt solution. Their paper was rediscovered 40 years later by M. Laver at Massachusetts General Hospital who informed Trubohovich of this effect (9).

In August 1954, Richard W. Stow, Ph.D. (Associate Professor of Physical Medicine, Ohio State University, Columbus, Ohio) (Fig. 2), a physical chemist, reported the design of a CO_2 electrode at the fall meeting of the American Physiologic Society in Madison, Wisconsin (10).



Figure 2. Richard Stow, invented the CO_2 electrode in 1954 to assist in managing polio patients on ventilators (10).



Figure 3. Stow's sketch of his 1954 CO_2 electrode. (a) Cable connection enclosure. (b) Rubber membrane. (c) Retaining O ring. (h) Chamber for internal pH electrolyte. (j) Reference electrode of silver chloride, not in contact with internal electrolyte, but opening to exterior through port K.

The polio epidemic was raging at the time, and as part of the physical therapy faculty he had sought some way to measure pCO_2 in the victims. He read in the library about specific ion electrodes, and conceived the electrode idea. He had wrapped a thin rubber membrane wet with distilled water over a homemade combined pH and reference electrode (Fig. 3). When he changed gas pCO_2 outside the device, the pH inside changed as a log function of gas pCO_2. However, he was unable to get stable readings and said he doubted it could be made useful.

After his talk, Severinghaus asked him why he did not try adding sodium bicarbonate ($NaHCO_3$) to the water film in the electrode. He replied that he believed this would abolish the signal because bicarbonate would buffer the effect of pCO_2 on pH. Severinghaus replied that he was confident that bicarbonate would not block the sensitivity. Stow agreed that Severinghaus would further investigate this idea. In September, 1954, after returning from Madison to the National Institutes of Health, Severinghaus confirmed the advantage of adding bicarbonate ions. A schematic diagram of his modification of Stow's electrode is shown in Fig. 4. He used a Beckman bulb-type pH electrode, a chloride-coated silver wire reference, and a Beckman pH meter. He tied a film of cellophane over the pH electrode soaked in 25 m*M* $NaHCO_3$ and then covered the entire tip with a thin rubber dam, later from a surgical glove. The bicarbonate not only made the device stable, but doubled the pCO_2 sensitivity compared with an electrolyte of distilled water (or 1% NaCl). Salt was added to help stabilize the silver chloride reference electrode.



Figure 4. The concept of a pCO_2 electrode. The pH sensitive surface of a pH glass electrode is covered by a layer of electrolyte (here in cellophane), and then by a thin layer of a membrane permeable to CO_2, but not to hydrogen ions (here Teflon). The pH in that film is controlled by the partial pressure of CO_2 on the outside of the outer membrane as CO_2 dissolves and reacts with water to form carbonic acid. The carbonic acid dissociates into hydrogen and bicarbonate ions. Because the electrolyte has 5–20 m*M* HCO_3^- ions, changes of pCO_2 have no measurable effect on HCO_3^-. The mass law then requires H^+ to change in direct proportion to change in pCO_2. A doubling of pCO_2 doubles H^+ concentration, which is seen as a 0.3 pH unit fall.

In 1957, Stow. Baer and Randall (11) published their discovery of the CO_2 electrode without mentioning the need to add bicarbonate ion, and took no further interest in this idea. Stow had no interest in a patent, thinking it would distract him from his job, and also because his university only allowed inventors 10% of royalties. As a U.S. government employee, Severinghaus was not permitted to patent it, certainly not with a reluctant coinventor.

Severinghaus and co-worker A. Freeman Bradley proceeded to investigate and optimize the electrode design and to test its performance, linearity, drift, and response time. They constructed electrodes for laboratory use by several colleagues, but unfortunately made no attempt at commercial development for 4 years.

Between 1958 and 1960 several other investigators constructed and published similar CO_2 electrodes, in several instances without being aware of the Stow–Severinghaus electrode (12–14).

CO_2 ELECTRODE DESIGN DETAILS

A CO_2 electrode consists of a slightly spherical surfaced glass pH electrode and a silver chloride reference electrode. Both are mounted in a glass or plastic sleeve holding a Teflon or silicone rubber membrane, typically 12 μm thick, over the glass surface, in some cases with a spacer of very thin lens-cleaning paper between membrane and glass to



Figure 5. Cuvette with blood inlet and outlet connections in a thermostated water jacket made for the Stow–Severinghaus pCO_2 electrode (National Welding Co, San Francisco, 1959).

insure a uniform distribution of the electrolyte that is NaCl or KCl with ~ 5–20 mequiv/L of $NaHCO_3$. For use in blood, the electrode is mounted in a 37 °C cuvette into which a small sample of blood can be injected (typically 50 μL) (Fig. 5).

The electrode output voltage is a logarithmic function of pCO_2, ~ 60 mV for a 10-fold change of pCO_2, which induces a pH change of ~ 1 pH unit. Sensitivity is defined as Δ pH/ $\Delta \log pCO_2$, where S reaches nearly the ideal maximum value of 1.0 with HCO_3^- concentrations of 5–25 mM (Fig. 6). At higher bicarbonate levels, carbonate acts as a buffer, and reduces both sensitivity and speed of response. Response is faster at lower bicarbonate concentration, but carbonic acid pK' is 6.1, resulting in some change of bicarbonate as pCO_2 changes, reducing sensitivity. As bicarbonate concentration is lowered, sensitivity falls to 30 mV/decade pCO_2 change, or $S = 0.5$, at zero bicarbonate.

The log response is almost linear from 5 to 700 mmHg pCO_2. The response time to a step change of pCO_2 is exponential with a 95% response time of ~ 30 s, depending on the membrane thickness and material, bicarbonate ion concentration and the thickness of the electrolyte layer over the glass electrode surface. It can be made to respond in < 1 s by using thin silastic (silicone rubber) membrane, low bicarbonate concentration (i.e., 1 mequiv/L), and adding carbonic anhydrase to the electrolyte, but the downside is loss of stability and signal amplitude.



Figure 6. The first blood gas apparatus, with the Clark pO_2 electrode (below) in a stirred cuvette, and the Stow–Severinghaus pCO_2 electrode above, tilted to keep the internal air bubble of the pH electrode away from the tip (1957).

The CO_2 electrode is usually calibrated to read in millimeters of mercury. It reads the same value for gas and liquid equilibrated with that gas at the electrode temperature, usually 37 °C.

A useful test of a leaking membrane is to equilibrate a dilute solution (e.g., 1 mequiv/L) of HCl, or lactic acid with a known calibration gas, and test its reading. Any leak will permit acid entry and an erroneously high pCO_2.

Maintenance requires replacement of the membrane and electrolyte when errors are detected or when drift has driven the electrode beyond the ability of the apparatus to compensate its potential. The pH glass may become so impermeable to hydrogen ions that it shows low sensitivity or slow response after years of use.

The amplifier circuit must be electrically isolated from the ground because any ground path leakage will draw current through the silver chloride reference and changes its potential causing drift. The input impedance of all modern pH and pCO_2 meter amplifiers is $>10^{11}\,\Omega$.

The Combined Blood Gas Analysis Apparatus

In 1956, Leland Clark disclosed his invention of the oxygen electrode at a meeting in Atlantic City to which Severinghaus had invited physiologists interested in measuring pO_2. That invention made a huge difference in blood gas analysis.

While Severinghaus completed his anesthesia residency at the University of Iowa, with help from the physiology workshop, he constructed a thermostat into which he mounted both the Stow–Severinghaus CO_2 electrode and the Clark O_2 electrode in a stirred cuvette with a small blood tonometer. That apparatus was exhibited at the meeting of the American Society of Anesthesiologists in October 1957 and at the meeting of the Federation of American Societies of Experimental Biology in Atlantic City in the spring of 1958 and published in 1958 (15) (Fig. 7).



Figure 7. The first three-function blood gas analyzer, using a McInnes Belcher pH electrode (1930) with the pCO_2 and pO_2 electrodes in a 37 °C bath.

The Three-Function Blood Gas Analyzer

In 1958, after moving from the National Institutes of Health to the University of California, San Francisco, Severinghaus and Bradley added a pH electrode to the blood gas electrode waterbath, making the first three-function blood gas apparatus (Fig. 8). Forrest Bird, Ph.D., M.D. (President, Bird Corporation, Palm Springs, California) had designed popular positive-pressure ventilators, manufacturing them at the National Welding Co. in San Francisco. He proposed to manufacture the CO_2 electrode and to make it commercially available. From 1959–1961 the National Welding Co. sold the only available $p\mathrm{CO}_2$ electrode. The design concept was soon copied and marketed by Beckman, Radiometer, Instrumentation Labs and later by several other firms.

Impact of Blood Gas Analysis

During the 1960s, blood gas analysis became widely available in anesthesia, intensive and critical care facilities, and cardiorespiratory research laboratories. For several years, the Severinghaus paper (15) was among the most quoted articles in biologic literature, and blood gases were called the most important laboratory test for critically ill patients. Blood gas apparatus now uses automatic self-calibration and automatic transport of sample and washing of cuvettes, printing of results, and often sending the values to remote terminals. In the United States, regulations have been used by pathologists to require that these automated instruments can only be used by licensed technicians, usually meaning that the income flows to pathologists. Gone are the days when students, nurses, residents, and faculty all took part in doing blood gas analysis.

A more complete history of the CO_2 electrode and related blood gas technology is available in References (9,16).



Figure 8. Relationship of $p\mathrm{CO}_2$ electrode sensitivity to its internal electrolyte bicarbonate ion concentration. Maximum sensitivity occurs at $\sim 20\,\mathrm{m}M$ HCO_3^-, but for faster response, most electrodes operate at 5–10 mM.

HISTORY AND THEORY OF TRANSCUTANEOUS BLOOD OXYGEN MONITORING

From 1951 to 1952, the discovery of oxygen related blindness in premature infants created an urgent need for continuous noninvasive monitoring of blood oxygen. A new solution to the problem came from physiologists studying skin respiration. Human skin breathes, taking up oxygen and giving off CO_2 to the air. If skin is covered (as by a flat unheated $p\mathrm{CO}_2$ electrode) the surface $\mathrm{tc}p\mathrm{O}_2$ falls to zero in a few minutes. However, in 1951 Baumberger and Goodfriend showed that if skin blood flow is greatly increased by the highest tolerable heat (45 °C), the surface $p\mathrm{O}_2$ rises to about $p\mathrm{aO}_2$ (arterial blood) (17).

Within a year after Clark's invention of the membrane covered platinum polarographic electrode (18,19), Rooth used polarography to confirm the Baumberger report (20). Researchers tried unsuccessfully to use chemical vasodilators to make skin $p\mathrm{O}_2$ a monitor of $p\mathrm{aO}_2$. Kwan and Fatt (21) noted that $p\mathrm{O}_2$ of the palpebral conjunctiva measured with an unheated tiny Clark electrode mounted facing outward on a contact lens over the cornea simulated $p\mathrm{aO}_2$. This device was briefly marketed a decade later, but discontinued due to the danger of infection.

In Marburg, Germany, Professor of Physiology Dietrich Lübbers and students, especially Renate Huch, pursued the concept of heating the skin under an oxygen electrode by heating the electrode itself to as high as 45 °C. They were joined by Patrick Eberhard, and the group soon found ways of making electrically heated, thermostated oxygen surface electrodes. By 1972, they had shown a good relationship between heated skin and arterial blood $p\mathrm{O}_2$ in infants (22). Several firms began to design electrodes for this purpose.

DEVELOPMENT OF METHODS AND UNDERSTANDING OF THEORY

By 1977, the Marburg group had published at least 11 papers documenting the validity of transcutaneous oxygen measurement. At least three commercial $\mathrm{tc}p\mathrm{O}_2$ electrode systems were available (Helige, Roche, Radiometer). In November 1977, some 18 research teams joined for a workshop on transcutaneous blood gas methods in San Francisco, assessing the theory, problems, possibilities, and progress (23–30). The following summer (1978) many of these workers joined the Marburg team and others for the first international congress on transcutaneous blood gas monitoring, establishing the technology as an essential tool in neonatology and as useful in many other fields (31,32).

The agreement of $\mathrm{tc}p\mathrm{O}_2$ with $p\mathrm{aO}_2$ proved to be a cancellation of two opposing effects illustrated in Fig. 9 (27,33).

1. Heating of desaturated blood raises its $p\mathrm{O}_2$ by 7%/°C, or 50% at 43 °C, but in saturated blood, as in water, $p\mathrm{O}_2$ rises only 1.3%/°C (35);
2. Skin metabolism at the high temperature consumes O_2 as it diffuses outward from capillaries through living cells, reducing the value to about $p\mathrm{aO}_2$.


SUBCUTANEOUS
DERMIS
EPIDERMIS
LIVING
DEAD
O2 ELECTRODE
140
120
100
80
60
40
20
0
Po2
mmHg
Pao2
P̄co2
D
(33.6 mmHg)
97.7 % SO2
Pvo2
94.9 % SO2
4.5 (43°)
Vo2 ml/g/min
2.9 (37°)
ARTERY
FLOW = .746 ml/g/min
CAPILLARY
T°C
VEIN
HEATING ZONE
GAS EXCHANGE ZONE
200 μm
CONTACT GEL
POLYPROPYLENE MEMBRANE
CELLOPHANE SPACER + ELECTROLYTE
CATHODE
PIO2
Ø = 1.03
PO2 37°
12-25 μm
12-25 μm
44°
37°
PIO2 (IDEAL, Ø = 1)
TEMP.
T°C
44
42
40
38
36
2.0
1.0
0.5
MM.
0.2
0.1
0

Figure 9. A schema of the effect of both heating of skin surface by a transcutaneous electrode, and of local metabolism, on the tissue internal oxygen tension from the arteries out past the capillaries and the living and dead epidermis to the surface, and through the electrode membrane into the cathode that keeps its surface $pO_2 = 0$ by its electrical negative potential (39).

The outward oxygen diffusion is facilitated by heat that proved to "melt" some skin diffusion barriers (33,36). Skin O_2 conductivity C (adult volar forearm) was determined by two groups by comparison of flux with two membranes (teflon and mylar) of very high and low conductivity. With a large gold cathode Clark electrode, $C = 15\,\mathrm{nL \cdot cm^{-2} \cdot s^{-1} \cdot atm^{-1}}$(37) and with a mass spectrometer $C = 10\,\mathrm{nL \cdot cm^{-2} \cdot s^{-1} \cdot atm^{-1}}$(38).

Skin O_2 consumption (VO_2) was determined after thermal vasodilation by the rate of fall of tcpO_2 with circulatory occlusion (arm cuff) (Fig. 10) (27). Relative skin blood flow under the heated electrode was estimated by measuring the required heating power (39). Analysis of data collected at two levels of pO_2 and two temperatures permitted calculation of blood flow, capillary temperature under a heated electrode, and diffusion gradient from capillary to surface (40). Mean adult volar forearm skin VO_2 was $4.2 \pm 0.4\,\mathrm{\mu L \cdot g^{-1} \cdot min^{-1}}$ at 44 °C and $2.8 \pm 0.3\,\mathrm{\mu L \cdot g^{-1} \cdot min^{-1}}$ at 37 °C. At 44 °C, skin blood flow averaged $0.64 \pm 0.17\,\mathrm{mL \cdot g^{-1} \cdot min^{-1}}$, capillary temperature was 43 °C and the diffusion gradient was 32 ± 7 mmHg.

TRANSCUTANEOUS CO_2

In 1959, Severinghaus constructed a 37 °C thermostated open tipped CO_2 electrode to determine pCO_2 of various tissue surfaces in animals (Fig. 11) (41). Without heating the skin well above body temperature, skin pCO_2 at 37 °C climbed steadily over one-half of an hour to > 80 mmHg. Dog intestinal mucosa and liver surfaces were very high.

Fifteen years later, the success in transcutaneous measurement of oxygen led to design and testing of electrodes to measure tcpCO_2 by Beran et al. (42,43), Huch et al. (44) and Severinghaus et al. (45,46). Combined tcpO_2–tcpCO_2 electrodes were initially described by Parker et al. (47) and Severinghaus (48). Figure 12 schematically shows the internal design of an early Radiometer combined electrode. Figure 13 shows the electrode with a membrane mounted.



Figure 10. The time course of skin pO_2 and pCO_2 on an arm after sudden circulatory occlusion with a blood pressure cuff. The rate of fall of pO_2 from a high level is a measure of the skin metabolic rate. The pCO_2 rises at first from metabolic CO_2 production, but later at a steeper rate as skin generates lactic acid when skin pO_2 reaches zero. With release of occlusion, the electrode recovery time is delayed by both the skin washin and washout, and by electrode equilibration (34).

When a heated combined pO_2–pCO_2 electrode is first attached to skin, the time needed to equilibrate is ~5 min for both electrodes, although the pO_2 electrode may show later small changes as thermal vasodilation slowly develops (Fig. 14). The response to step changes in alveolar and arterial pCO_2 is slower as seen in Fig. 15. Here the response is delayed both by the washout or washin of CO_2 into the tissue by blood flow, and the electrode's own delay. The response is pseudoexponential, a combination of the two delays, resulting in a 95% response times of ~10 min.

Without correction, tcpCO_2 is not similar to paCO_2. Heating of blood (and water) raises pCO_2 ~4.6%/°C


METRIC 1 SYSTEM 2 3 4

Figure 11. The first tissue surface pCO_2 electrode (41) with a circulating temperature controlled water jacket.



Figure 12. Schema of the design of a combined tcpO_2–tcpCO_2 electrode. (a) pO_2 cathode, the end of a 12 μm platinum wire fused in glass. (b) A silver wire reference electrode. (c) pH glass electrode surface. (d) solid silver internal pH electrode (used to improve heat transfer to skin). (e) Internal pH electrolyte. (f) Heater Zener diode. (g) Thermistor. (h) Silver body, and reference electrode. J, K, L, M: O rings. N: Lexan jacket. Q: epoxy. P: Cable (48).



Figure 13. Photograph of combined pO_2–pCO_2 electrode with teflon membrane (48).



Figure 14. Initial responses of a combined pO_2–pCO_2 electrode when first mounted on skin. Both electrodes need ~5 min to equilibrate, the pO_2 showing a small late rise as skin hyperemia develops from the heating (49).

(41), metabolism adds ~3 mmHg pCO_2, and the cooling by skin and blood of the electrode surface further raises the electrode reading. The effect of heating on blood pCO_2 may be computed as $\Delta pCO_2 = \exp(0.046[T - 37])$ (51). The net effect at 43 °C was found to be tc$pCO_2 = 1.33p\mathrm{a}CO_2 +$ 4 mmHg (48,52) or tc$pCO_2 = 1.4p\mathrm{a}CO_2$ (53). This form of temperature-dependent correction factor was later incorporated in most commercial transcutaneous blood gas monitoring apparatus.

With this correction factor, the relationship of tcpCO_2 to paCO_2 is excellent, as shown in Fig. 16. The previous correction factors appear to have become incorrect for a second generation of the Radiometer tcpCO_2 electrodes, due to a design change in the internal temperature coefficient of the glass pH electrode. The additive factor of 4 mmHg changed to ~8 mmHg in the newer instruments (Kagawa S, personal communication).

Although tcpCO_2 appears to work at 42–43 °C, Tremper et al. showed that 44 °C was a better temperature when



Figure 15. Transcutaneous pCO_2 electrode response to a step increase of ventilation adjusted by the subject to reduce end tidal pCO_2 suddenly from 40 to 20 mmHg and hold it at a constant level for 18 min, followed by addition of enough CO_2 to inspired gas to raise end tidal pCO_2 as quickly as possible to ~50 mmHg. The response time constants (63%) are ~5 min (45).



Figure 16. Transcutaneous pCO$_2$ correlates well with arterial pCO$_2$ in patients during anesthesia or intensive care (48).

blood pressure was or had been low (54). The tc$p$CO$_2$ value was better than the P_{ET}CO$_2$ value (end-tidal or end-expired air) in predicting paCO$_2$ (bias and s.d. -1.6 ± 4.3 mmHg) in anesthetized adults ($n = 24$) (55).

A special advantage of tc$p$CO$_2$ is that it averages out breath-by-breath variations, and has almost no inherent "noise" or variability, such that it often is found to be the best trend monitor for detecting small changes in paCO$_2$ such as those induced by experimental variations (anesthesia, ventilatory settings, posture, F_IO$_2$, F_ICO$_2$, blood pressure, pharmacologic agents, etc).

APPLICATIONS

Transcutaneous technology is used in many ways, some of which are discussed in accompanying papers:

1. Neonatology: Guidance of O$_2$ therapy remains the most common use of transcutaneous monitoring (56–58). The suspected etiologic role of hyperoxia (tc$p$O$_2$ > 80 mmHg) in retinitis of premature infants has been confirmed in a cohort study (59). The tc$p$O$_2$ value can be measured above and below the ductus to demonstrate closure (60). In low birth weight infants, tc$p$CO$_2$ (at 40 °C!) is the best available monitor of ventilation (61).
2. Fetal Monitoring: Using specially designed electrodes attached to the fetal scalp, intrapartum monitoring revealed some important new pathophysiologic understanding (62–65). As hoped, changes in tc$p$O$_2$ rapidly reflected changing maternal and fetal conditions (66). The tc$p$O$_2$ value fell and tc$p$CO$_2$ rose with contractions during the second stages of labor (67). The tc$p$CO$_2$ value closely followed fetal paCO$_2$(68). When there were signs of fetal distress, fetal scalp tc$p$O$_2$ was < 15 mmHg (69). Surprisingly, O$_2$ administration to mothers with fetal distress did not alter fetal pCO$_2$ or raise pO$_2$(70). During maternal hypocapnia, fetal tc$p$O$_2$ fell due to the Bohr effect, whereas it rose during hypercapnia (71). Fetal tc$p$O$_2$ was considered influenced by local scalp blood flow (72). Repeated episodes of asphyxia were reported to express catecholamines, which reduced blood flow to the fetal skin, artifactually reducing tc$p$O$_2$(73,74). Fetal tc$p$CO$_2$ may have failed to disclose severe acidosis or circulatory impairment (75).
3. Sleep Studies: Combined pO$_2$–pCO$_2$ electrodes are used in sleep studies in combination with pulse oximetry, because nostril sampling of end-tidal pCO$_2$ is somewhat annoying and more apt to become plugged or dislodged (76–83). The combined tc$p$O$_2$–tc$p$CO$_2$ electrode made it possible to show that the ventilatory response to induced mild hypoxia in sleeping infants changes with age from acute depression at 1–5 days, to stimulation at 4–8 weeks, and mild or no stimulation at 10–14 weeks (84). A method was designed for estimating the ventilatory response to CO$_2$ during sleep using capnography and tc$p$CO$_2$(79).
4. Peripheral Circulation: The tc$p$O$_2$ electrodes are extensively used in evaluating arterial disease in the peripheral circulation (85–88). A test of adequacy of peripheral circulation, "initial slope index" (ISI) was suggested by Lemke and Lübbers (89). Blood flow is stopped by an arm cuff above the electrode and restarted when tc$p$O$_2 = 0$. The initial rate of rise should be a slope per min of at least 75% of the preocclusion tc$p$O$_2$.
5. Skin Circulation: Monitoring the viability of skin after injury or transplant or flap movement (90,91).
6. Ventilatory Control: In intensive care, transcutaneous electrodes greatly increased the safety and simplicity of PEEP optimization and respiratory management of adults with respiratory distress syndrome (92). They are widely used simply to reduce arterial blood sampling.
7. Hyperbaric Oxygen: Monitoring and guiding hyperbaric oxygen therapy, primarily for infections and wound healing (93,94). The tc$p$O$_2$ tracked paO$_2$ up to 4-atm hyperbaric pressure in normal subjects (95). Surprisingly, no one has reported using tc$p$O$_2$ in hyperbaric treatment of CO poisoning despite the demonstration by Barker and Tremper in experimental CO administration that transcutaneous pO$_2$ falls linearly as COHb increases, and reaches about one-fifth of its initial value at the highest COHb levels despite the maintenance of constant arterial pO$_2$(96). It is thus unknown whether HBO can normalize tissue pO$_2$ in the presence of high levels of COHb.
8. Clinical Physiology: Transcutaneous monitoring has found use in exercise tolerance studies (97,98). End-tidal CO$_2$ is not exactly equal to paCO$_2$ and the difference between them varies with posture and inspired oxygen concentration. When testing hypoxic ventilatory responses by monitoring P_{ET}CO$_2$, tc$p$CO$_2$ helps to correct these small errors (99).

9. Pharmacologic Research: Transcutaneous monitoring may be the simplest monitor of the depressant effects of opiates, sedatives, and anesthetics especially in awake children (100).
10. Animal Studies: Intestinal or other tissue animal experimental ischemia has been found to be better detected by the rise of the organ or tissue surface $p\mathrm{CO_2}$ using tc$p\mathrm{CO_2}$ electrodes at body temperature than by gastric tonometry (101). Both tc$p\mathrm{O_2}$ and tc$p\mathrm{CO_2}$ have been widely used in small and large animal studies (102) and to assess the effect of cardiopulmonary resusitation (CPR) (103).

ACCURACY

With the widespread use of tc$p\mathrm{O_2}$ and tc$p\mathrm{CO_2}$ came concern about its accuracy and the possible sources and effects of errors, especially with severe hypotension (28,104). Peabody et al.(25) identified two groups of infants in whom tc$p\mathrm{O_2}$ was lower than $p\mathrm{aO_2}$. These were infants receiving an intravascular infusion of tolazoline and infants with mean arterial blood pressures > 2.5 s.d. below the predicted average value. Vasoconstrictors also lower tc$p\mathrm{O_2}$(105). Both of these situations represent extreme alterations in peripheral blood flow. Mild hypotension, hypothermia, anemia, radiant warmers, and bilirubin lights did not adversely affect transcutaneous accuracy (106). In a large multiinstitutional study of 327 patients older than 1 month, when $p\mathrm{aO_2}$ was between 80 and 220 mmHg, Palmisano found the mean bias ± s.d. of tc$p\mathrm{O_2}$ was -43 ± 40 mmHg, and the slope of the regression was 0.65 (107). It was determined that tc$p\mathrm{CO_2}$ correlated far better with $p\mathrm{aCO_2}$: $R = 0.929$, slope 1.052, bias and s.d. $= 1.3 \pm 4.0$ mmHg ($n = 756$).

Defining a tc$p\mathrm{O_2}$ index as tc$p\mathrm{O_2}$/$p\mathrm{aO_2}$, Tremper and Shoemaker (108) studied the effect of shock. For 934 data sets taken on 92 patients not in shock, there was a correlation coefficient (r) of 0.89 and a tc$p\mathrm{O_2}$ index 0.79 ± 0.12 (SD). In five patients with moderate shock, the r was 0.78 and the tc$p\mathrm{O_2}$ index was 0.48 ± 0.07. In nine patients with severe shock, there was no correlation between tc$p\mathrm{O_2}$ and $p\mathrm{aO_2}$ and the tc$p\mathrm{O_2}$ index was 0.12 ± 0.12.

LIMITATIONS

Skin burns may occur after an electrode has been in one place over several hours at 44–45 °C, and sometimes even at 43 °C. Long-term monitoring requires site changes, or a dual electrode alternating system (109). There may be problems with drift of calibration, membrane failure, partial loss of skin contact giving errors in both O_2 and CO_2 readings. Maintenance of these electrodes requires training and some technical proficiency.

IMPACT OF PULSE OXIMETRY

Pulse oximetry came into widespread use in 1985–1987, and quickly replaced transcutaneous blood gas analysis in many situations. However, after an initial switch to oximetry, neonatologists found that oximetry failed to detect hyperoxia adequately (110) and now mostly use both technologies (111–115). In neonatology, a significant problem is that the inherent errors of pulse oximetry are $\sim 3\%$, which could fail to warn of $p\mathrm{aO_2} > 80$ unless a set point of $\sim 90\%$ $S_{\mathrm{p}}\mathrm{O_2}$ is chosen (116). Some have arbitrarily dismissed transcutaneous monitoring as "…plagued by technical problems, …Its use in efforts to prevent retinopathy of prematurity, an eye disease of preterm newborns often leading to blindness, proved disappointing" (117). To them, the transcutaneous field served as a model of problems in medical innovation, new technology, and personnel training. Not everyone agrees with this pessimism. Most technical problems have been solved, and the occurrence of blindness in very premature infants is now believed to be multifactorial, not just due to hyperoxia. Therefore when it occurs, it is not appropriate to attribute it to failed transcutaneous methodology.

CONCLUSIONS

The enthusiasm for transcutaneous blood gas analysis of the period 1976–1986 was followed by a decrease due to the advent of pulse oximetry. The number of papers per year listing medline keywords "transcutaneous blood gas" reached an early peak of 75 in 1979, when the first international symposium was devoted to this field, in Marburg and 200 in 1987. However, after 1986 many papers used the keywords "transcutaneous blood gas" when writers meant to refer to pulse oximetry.

Transcutaneous technology is inherently somewhat complicated. Users must change membranes and calibrate, change skin sites periodically to avoid burns, beware of drift or error due to poor circulation or poor skin attachment, and take account of the slower response than given by oximetry. Nonetheless, transcutaneous blood gas measurement continues to be used because of its unique ability to meet many special situations needing its characteristics of noninvasively and continuously determining partial pressures of O_2 and CO_2. Several professional organizations have published guidelines for use of these monitors (118,119).

BIBLIOGRAPHY

1. Severinghaus JW. The current status of transcutaneous blood gas analysis and monitoring. Blood Gas news (Radiometer house organ) 1998;7:4–9.
2. Severinghaus JW. The Invention and Development of Blood Gas Apparatus. Anesthesiology 2002;97:253–256.
3. Severinghaus JW. Severinghaus electrode. In: JR Maltby, editor. Notable Names in Anaesthesia. London: Royal Society of Medicine Press Ltd.; 2002.
4. Severinghaus JW, Astrup P, Murray J. Blood gas analysis and critical care medicine. Am J Respir Crit Care Med 1998;157:S114–S122.
5. Severinghaus JW, Stupfel MA, Bradley AFJ. Accuracy of blood pH and $p\mathrm{CO_2}$ determinations. J Appl Physiol 1956;19: 189–196.
6. Astrup P. A simple electrometric technique for the determination of carbon dioxide tension in blood and plasma, total

content of carbon dioxide in plasma and bicarbonate content in “separated” plasma at a fixed carbon dioxide tension. Scand J Clin Lab Invest 1956;8:33–43.

7. Siggaard-Andersen O, Engel K, Jorgensen K, Astrup P. A micro method for determination of pH, carbon dioxide tension, base excess and standard bicarbonate in capillary blood. Scand J Clin Lab Invest 1960;12:172–176.
8. Gesell R, McGinty DA. Regulation of respiration: VI. Continuous electrometric methods of recording changes in expired carbon dioxide and oxygen. Am J Physiol 1926;79:72–90.
9. Trubuhovich RV. History of $p\mathrm{CO_2}$ electrodes. Br J Anaesth 1970;42:360–362.
10. Stow RW, Randall BF. Electrical measurement of the $p\mathrm{CO_2}$ of blood (abstract). Am J Physiol 1954;179:678.
11. Stow RW, Baer RF, Randall B. Rapid measurement of the tension of carbon dioxide in blood. Arch Phys Med Rehabil 1957;38:646–650.
12. Gertz KH, Loeschcke HH. Elektrode zur bestimmung des CO_2 drucks. Naturwissenschaften 1958;45:160–161.
13. Hertz CH, Siesjo B. A rapid and sensitive electrode for continuous measurement of $p\mathrm{CO_2}$ in liquids and tissue. Acta Physiol Scand 1959;47:115–123.
14. Snell FM. Electrometric measurement of carbon dioxide and bicarbonate ion. J Appl Physiol 1960;15:729–732.
15. Severinghaus JW, Bradley AF. Electrodes for blood $p\mathrm{O_2}$ and $p\mathrm{CO_2}$ determination. J Appl Physiol 1958;13:515–520.
16. Severinghaus JW, Astrup P. History of blood gas analysis. Int Anesthesiol Clin 1987;25:69–95.
17. Baumberger JP, Goodfriend RB. Determination of arterial oxygen tension in man by equilibration through intact skin. Fed Proc 1951;10:10.
18. Clark LC. Monitor and control of tissue O_2 tensions. Trans Am Soc Artif Intern Organs 1956;2:41–48.
19. Clark LC, Clark EW. Personalized history of the Clark oxygen electrode. Inter Anesthesiol Clin 1987;25:1–30.
20. Rooth G, Sjostedt S, Caligara F. Bloodless determination of arterial oxygen tension by polarography. Sci Tools LKW Instr J 1957;4:37.
21. Kwan M, Fatt I. A noninvasive method of continuous arterial oxygen tension estimation from measured palperal conjunctival oxygen tension. Anesthesiology 1971;35:309–314.
22. Huch R, Lübbers DW, Huch A. Quantitative continuous measurement of partial oxygen pressure on the skin of adults and new-born babies. Pflügers Arch 1972;337:185–198.
23. Vesterager P. Transcutaneous $p\mathrm{CO_2}$ electrode. Scand J Clin Lab Invest 1977;37:27–30.
24. Friis Hansen B. Transcutaneous measurement of arterial blood oxygen tension with a new electrode. Scand J Clin Lab Invest 1977;37:31–36.
25. Peabody JL, Willis MM, Gregory GA, Tooley WH, Lucey JF. Clinical limitations and advantages of transcutaneous oxygen electrodes. Acta Anaesthesiol Scand Suppl 1978;68:76–82.
26. Tremper KK, Huxtable RF. Dermal heat transport analysis for transcutaneous O_2 measurement. Acta Anaeshesiol Scand Suppl 1978;68:4–8.
27. Severinghaus JW, Stafford MJ, Thunstrom AM. Estimation of skin metabolism and blood flow with $\mathrm{tcPo_2}$ and $\mathrm{tcPco_2}$ electrodes by cuff occlusion of the circulation. Acta Anaesth Scand Suppl 1978;68S:9–15.
28. Versmold HT, Linderkamp O, Holzmann M, Strohhacker I, Riegel KP. Limits of $\mathrm{tc}p\mathrm{O_2}$ monitoring in sick neonates: Relation to blood pressure, blood volume, peripheraal blood flow and acid base status. Acta Anaesthesiol Scand Suppl 1978;S68:88–90.
29. Kimmich HP, Kreutzer F. Model of oxygen transport through skin as basis for absolute transcutaneous measurement of $P\mathrm{aO_2}$. Acta Anaesthesiol Scand Suppl 1968;S68:16–19.
30. Fatt I. Transmucosal measurement of blood pH at the palpebral conjunctiva. Acta Anaesthesiol Scand Suppl 1978;S68: 142–144.
31. Huch A, Huch R. The development of the transcutaneous $p\mathrm{CO_2}$ technique into a clinical tool. In: Huch R, Huch A, Lucey JR, editors. Continuous Transcutaneous Blood Gas Monitoring, Birth Defects: Original Article Series. Volume XV-No. 4. New York: A.R.Liss; 1979.
32. Lübbers DW, Cutaneous and Transcutaneous $p\mathrm{O_2}$ and $p\mathrm{CO_2}$ and their measuring conditions. In: Huch R, Huch A, Lucey JF, editors. Continuous Transcutaneous Blood Gas Monitoring, Birth Defects: Original Article Series. Volume XV-No. 4. New York: A. R. Liss; 1979.
33. Lübbers DW. Theoretical basis of the transcutaneous blood gas measurements. Crit Care Med 1981;9:721–733.
34. Severinghaus JW. Transcutaneous Blood Gas Analysis. Respir Care 1982;27:152–159.
35. Severinghaus JW. Simple, accurate equations for human blood O_2 dissociation computations. J Appl Physiol 1979;46: 599–602.
36. Lübbers DW. Theory and development of transcutaneous oxygen pressure measurement. Int Anesthesiol Clin 1987; 25:31–65.
37. Eberhard P, Severinghaus JW. Measurement of heated skin O_2 diffusion conductance and $p\mathrm{CO_2}$ sensor induced O_2 gradient. Acta Anaesthesiol Scand Suppl 1978;68:1–3.
38. Hansen TN, Sonoda Y, McIlroy MB. Transfer of oxygen, nitrogen and carbon dioxide through normal adult human skin. J Appl Physiol 1980;49:438–443.
39. Parker D, Delpy D, Reynolds EOR, St. Andrew D. A transcutaneous $p\mathrm{O_2}$ electrode incorporating a thermal clearance local blood flow sensor. Acta Anaesthesiol Scand Suppl 1978; S68:33–39.
40. Thunstrom AM, Stafford MJ, Severinghaus JW. A two temperature, two $p\mathrm{O_2}$ method of estimating the determinants of $\mathrm{tc}p\mathrm{O_2}$. In: Huch R, Huch A, Lucey JR, editors. Continuous Transcutaneous Blood Gas Monitoring, Birth Defects: Original Article Series. Volume XV-No. 4, New York: A. R. Liss; 1979.
41. Severinghaus JW. CO_2 Spannung und Perfusion in Gewebe. Anaesthetist 1960;9:50–55.
42. Beran AV, Huxtable RF, Sperling DR. Electrochemical sensor for continuous transcutaneous $p\mathrm{CO_2}$ measurement. J Appl Physiol 1976;41:442–447.
43. Beran AV, Shigezawa GY, Yeung HN, Huxtable RF. An improved sensor and a method for transcutaneous CO_2 monitoring. Acta Anaesthesiol Scand Suppl 1978;S68:111–117.
44. Huch A, Seiler D, Meinzer K, Huch R, Galster H, Lübbers DW. Transcutaneous $p\mathrm{CO_2}$ measurement with a miniaturised electrode. Lancet 1977;1:982–983.
45. Severinghaus JW, Stafford M, Bradley AF. $\mathrm{tc}p\mathrm{CO_2}$ electode design, calibration and temperature gradient problems. Acta Anaesthesiol Scand Suppl 1978;68:118–122.
46. Severinghaus JW, Bradley AF, Stafford MJ. Transcutaneous $p\mathrm{CO_2}$ electrode design with internal silver heat path. In: Huch A, Huch R, Lucey JF, editors. Continuous Transcutaneous Blood Gas Monitoring, Birth Defects: Original Article Series. Volume XV-No. 4, New York: A.R. Liss, Inc.; 1979.
47. Parker D, Delpy D, Reynolds EOR. Single electrochemical sensor for transcutaneous measurement of $p\mathrm{O_2}$ and $p\mathrm{CO_2}$. In: Huch R, Huch A, Lucey JF, editors. Continuous Transcutaneous Bloo Gas Monitoring, in Birth Defects: Original Article Series. Volume XV-No. 4, New York: A. R. Liss; 1979.
48. Severinghaus JW. A combined transcutaneous $p\mathrm{O_2}$—$p\mathrm{CO_2}$ electrode with electrochemical HCO_3- stabilization. J Appl Physiol 1981;51:1027–1032.
49. Severinghaus JW. Transcutaneous monitoring of arterial $p\mathrm{CO_2}$. Resp Monit Int Care 1982; 85–91.

50. Gothgen I. Heat-indued changes in pO_2 and pCO_2 of blood. Acta Anaesthesiol Scand 1984;28:447–451.
51. Jacobsen E, Gothgen I. Relationship between arterial and heated skin surface carbon dioxide tension in adults. Acta Anaesthesiol Scand 1985;29:198–202.
52. Hazinski TA, Severinghaus JW. Transcutaneous analysis of arterial pCO_2. Med Instrum 1982;16:150–153.
53. Wimberley PD, Pedersen KG, Thode J Fogh-Andersen, Sorensen AM, Siggaard-Andersen O. Transcutaneou and capillary pCO_2 and and pO_2 measurements in healthy adults. Clin Chem 1983;29:1471–1473.
54. Tremper KK, Mentelos RA, Shoemaker WC. Effect of hypercarbia and shock on transcutaneous carbon dioxide at different electrode temperatures. Crit Care Med 1980;8:608–612.
55. Phan CQ, Tremper KK, Lee SE, Barker SJ. Noninvasive monitoring of carbon dioxide: A comparison of the partial pressure of transcutaneous and end-tidal carbon dioxide with the partial pressure of arterial carbon dioxide. J Clin Monit 1987;3:149–154.
56. Hoppenbrouwers T, Hodgman JE, Arakawa K, Durand M, Cabal LA. Transcutaneous oxygen and carbon dioxide during the first half year of life in premature and normal term infants. Pediatr Res 1992;31:73–79.
57. Huch R. Review: Perinatal monitoring. Acta Anaesthesiol Scand Suppl 1995;S107:91–94.
58. Huch A. Transcutaneous blood gas monitoring. Acta Anesthesiol Scand Suppl 1995;107:87–90.
59. Flynn JT, et al., A cohort study of transcutaneous oxygen tension and the incidence and severity of retinopathy of prematurity [see comments]. New Engl J Med 1992;326: 1050–1054.
60. Schmidt S, Kakatschikaschwili T, Langner K, Dudenhausen JW, Saling E. [Circulatory adaptation of the newborn infant immediately post partum by biolocal measurement of transcutaneous pCO_2]. Z Geburtshife Perinatol 1984;188: 21–23.
61. Binder N, Atherton H, Thorkelsson T, Hoath SB. Measurement of transcutaneous carbon dioxide in low brithweight infants during the first two weeks of life. Am J Perinatol 1994;11:237–241.
62. Huch A, Huch R, Schneider H. Fetal transcutaneous pO_2—current knowledge. In: Huch R, Huch A, Lucey JF, editors. Continuous Transcutaneous Blood Gas Monitoring, Birth Defects: Original Article Series. Volume XV-No. 4, New York: A.R.Liss; 1979.
63. Huch R, Huch A. Fetal and maternal $PtcO_2$ monitoring. Crit Care Med 1981;9:694–697.
64. Lofgren O. Continuous transcutaneous carbon dioxide monitoring in the fetus during labor. Crit Care Med 1981;9:750–751.
65. Okane M, Shigemitsu S, Inaba J, Koresawa M, Kubo T, Iwasaki H. Non-invasive continuous fetal transcutaneous pO_2 and pCO_2 monitoring during labor. J Perinat Med 1989;17:399–410.
66. Antoine C, Young BK, Silverman F. Simltaneous measurement of fetal tissue pH and transcutaneous pO_2 during labor. Eur J Obstet Gynecol Reprod Biol 1984;17:69–76.
67. Schmidt S, Langner K, Dudenhausen JW, Saling E. Reliability of transcutaneous measurement of oxygen and carbon dioxide partial pressure with a combined pO_2–pCO_2 electrochemical sensor in the fetus during labor. J Perinat Med 1985;13:127–133.
68. Bergmans MG, van Geijn HP, Weber T, Nickelsen C, Schmidt S, van den Berg PP. Fetal transcutaneous pCO_2 measurements during labour. Eur J Obstet Gynecol Reprod Biol 1993;51:1–7.
69. Kaneoka T, Kobayashi H, Uchida K, Shirakawa K. [Continuous fetal biochemical monitoring and cardiotocography]. Nippon Sanka Fujinka Gakkai Zasshi 1988;40:721–728.
70. Bartnicki J, Langner K, Harnack H, Meyenburg M. The influence of oxygen administration to the mother during labor on the fetal trasncutaneously measured carbon-dioxide partial pressure. J Perinat Med 1990;18:397–402.
71. Aarnoudse JG, Oeseburg B, Kwant G, Zwart A, Zijlstra WG, Huisjes HJ. Influence of variations in pH and pCO_2 on scalp tissue oxygen tension and carotid arterial oxygen tension in the fetal lamb. Biol Neonate 1981;40:252–263.
72. Smits TM, Aarnoudse JG, Zijlstra WG. Fetal scalp blood flow as recorded by laser Doppler flowmetry and transcutaneous pO_2 during labour. Early Hum Dev 1989;20:109–124.
73. Jensen A, Kunzel W, Kastendieck E. Fetal sympathetic activity, transcutaneous pO_2, and skin blood flow during repeated asphyxia in sheep. J Dev Physiol 1987;9:337–346.
74. Paulick R, Kastendieck E, Wernze H. Catecholamines in arterial and venous umbilical blood: placental extraction, correlation with fetal hypoxia, and transcutaneous partial oxygen tension. J Perinat Med 1985;13:31–42.
75. Braems G, Kunzel W, Lang U. Transcutaneous pCO_2 during labor—a comparison with fetal blood gas analysis and transcutaneous pO_2. Eur J Obstet Gynecol Reprod Biol 1993;52: 81–88.
76. Fukui M, Ohi M, Chin K, Kuno K. The effects of nasal CPAP on transcutaneous pCO_2 during non-REM sleep and REM sleep in patients with obstructive sleep apnea syndrome. Sleep 1993;16:S144–5.
77. Manning DJ, Stothers JK. Sleep state, hypoxia and periodic breathing in the neonate. Acta Paediatr Scand 1991;80:763–769.
78. Morielli A, Desjardins D, Brouillette RT. Transcutaneous and end-tidal carbon dioxide pressures should be measured during pediatric polysomnography. Am Rev Respir Dis 1993;148: 1599–1604.
79. Naifeh KH, Severinghaus JW. Validation of a maskless CO_2-response test for sleep and infant studies. J Appl Physiol 1988;64:391–396.
80. Naughton M, Benard D, Tam A, Rutherford R, Bradley TD. Role of hyperventilation in the pathogenesis of central sleep apneas in patients with congestive heart failure [see comments]. Am Rev Respir Dis 1993;148:330–338.
81. Naughton MT, Benard DC, Rutherford R, Bradley TD. Effect of continuous positive airway pressure on central sleep apnea and nocturnal pCO_2 in heart failure. Am J Respir Crit Care Med 1994;150:1598–1604.
82. Schafer T, Schafer D, Schläfke ME. Breathing, transcutaneous blood gases, and CO_2 response in SIDS siblings and control infants during sleep. J Appl Physiol 1993;74:88–102.
83. Schlaefke ME, Schaefer T, Kronberg H, Ullrich GJ, Hopmeier J. Transcutaneous monitoring as trigger for therapy of hypoxemia during sleep. Adv Exp Med Biol 1987;220:95–100.
84. Milerad J, Hertzberg T, Lagercrantz H. Ventilatory and metabolic responses to acute hypoxia in infants assessed by transcutaneous gas monitoring. J Dev Physiol 1987;9: 57–67.
85. White RA, Nolan L, Harley D, Long J, Klein S, Tremper K, Nelson R, Tabriski J, Shoemaker W. Noninvasive evaluation of peripheral vascular disease using transcutaneous oxygen tension. Am J Surg 1982;144:68–75.
86. Kram HB, Shoemaker WC. Diagnosis of major peripheral arterial trauma by transcutaneous oxygen monitoring. Am J Surg 1984;147:776–780.
87. Padberg FT, Back TL, Thompson PN, Hobson RW. Transcutaneous oxygen ($TcpO_2$) estimates probability of healing in the ischemic extremity. J Surg Res 1996;60:365–369.
88. Wutschert R, Bounameaux H. Determination of amputation level in ischemic limbs. Reappraisal of the measurement of $TcpO_2$. Diabetes Care 1997;20:1315–1318.

89. Lemke R, Klaus D, Lübbers DW, Oevermann G. Noninvasive $p\mathrm{tCO}_2$ initial slope index and invasive $p\mathrm{tCO}_2$ arterial index as diagnostic criterion of the state of peripheral circulation. Crit Care Med 1988;16:353–357.
90. Keller HP, Klaue P, Hockerts T, Lübbers DW. Transcutaneous $p\mathrm{O}_2$ measurement on skin transplants. In: Huch R, Huch A, Lucey JF, editors. Continuous Transcutaneous Blood Gas Monitoring, Birth Defects: Original Article Series. Volume XV-No. 4, New York: A.R.Liss; 1979.
91. Lübbers DW. Transcutaneous measurements of skin O_2 supply and blood gases. Adv Exp Med Biol 1992;316:49–60.
92. Tremper KK, Waxman K, Shoemaker WC. Use of transcutaneous oxygen sensors to titrate PEEP. Ann Surg 1981;193:206–209.
93. Dooley J, Schirmer J, Slade B, Folden B. Use of transcutaneous pressure of oxygen in the evaluation of edematous wounds. Undersea Hyperb Med 1996;23:167–174.
94. Wattel F, Pellerin P, Mathieu D, Patenotre P, Coget JM, Schoofs M, Leps P. [Hyperbaric oxygen therapy in the treatment of wounds, in plastic and reconstructive surgery]. Ann Chir Plast Esthet 1990;35:141–146.
95. Huch A, Huch R, Hollmann G, Hockerts T, Keller HP, Seiler D, Sadzek J, Lübbers DW. Transcutaneous $p\mathrm{O}_2$ of volunteers during hyperbaric oxygenation. Biotelemetry 1977;4: 88–100.
96. Barker SJ, Tremper KK. The effect of carbon monoxide inhalation on pulse oximetry and transcutaneous $p\mathrm{O}_2$ [see comments]. Anesthesiology 1987;66:677–679.
97. Sridhar MK, Carter R, Moran F, Banham SW. Use of a combined oxygen and carbon dioxide transcutaneous electrode in the estimation of gas exchange during exercise. Thorax 1993;48:643–647.
98. Breuer HW, Skyschally A, Alf DF, Schulz R, Heusch G. Transcutaneous $p\mathrm{CO}_2$-monitoring for the evaluation of the anaerobic threshold. Comparison to lactate and ventilatory threshold [see comments]. Int J Sports Med 1993;14:417–421.
99. Sato M, Severinghaus JW, Powell FL, Xu FD, Spellman MJJ. Augmented hypoxic ventilatory response in men at altitude. J Appl Physiol 1992;73:101–107.
100. Alswang M, Friesen RH, Bangert P. Effect of preanesthetic medication on carbon dioxide tension in children with congenital heart disease. J Cardiothorac Vasc Anesthesiol 1994;8: 415–419.
101. Rozenfeld RA, Dishart MK, Tønnessen TI, Schlichtig R. Methods for detecting intestinal ischemic anaerobic metabolic acidosis by local $p\mathrm{CO}_2$. J Appl Physiol 1996;81:1834–1842.
102. Keller HP, Klaue P, Lübbers DW. Transcutaneous $p\mathrm{O}_2$ measurements on rats and rabbits. In: Huch R, Huch A, Lucey JR, editors. Continuous Transcutaneous Blood Gas Monitoring, Birth Defects: Original Article Series. Volume XV-No. 4, New York: A.R.Liss; 1979.
103. Tremper KK, Shoemaker WC. Continuous CPR monitoring with transcutaneous oxygen and carbon dioxide sensors. Crit Care Med 1981;9:417–418.
104. Versmold HT, Linderkamp O, Holzmann M, Strohhacker I, Riegel K. Transcutaneous monitoring of $p\mathrm{O}_2$ in newborn infants: where are the limits? Influence of blood pressure, blood volume, blood flow, viscosity, and acid base state. In: Huch R, Huch A, Lucey JF, editors. Continuous Transcutaneous Blood Gas Monitoring, in Original Article Series. Volume XV-No. 4, New York: A.R. Liss; 1979.
105. Wendling P, Fussinger R, Schmidt HD, Stosseck K. [Validity of the transcutaneous $p\mathrm{O}_2$-measurement during pharmacologically induced changes of skin perfusion (author's transl)]. Anaesthesist 1982;31:135–138.
106. Ewald U, Huch A, Huch R, Rooth G. Skin reactive hyperemia recorded by a combined $\mathrm{Tc}p\mathrm{O}_2$ and laser Doppler sensor. Adv Exp Med Biol 1987;220:231–234.
107. Palmisano BW, Severinghaus JW. Transcutaneous $p\mathrm{CO}_2$ and $p\mathrm{O}_2$: a multicenter study of accuracy. J Clin Monit 1990;6: 189–195.
108. Tremper KK, Shoemaker WC. Transcutaneous oxygen monitoring of critically ill adults, with and without low flow shock. Crit Care Med 1981;9:706–709.
109. Fallenstein F, Ringer P, Huch R, Huch A. A new system for $\mathrm{tc}p\mathrm{O}_2$ long-term monitoring using a two-electrode sensor with alternating heating. Adv Exp Med Biol 1987;220: 285–289.
110. Paky F, Koeck CM. Pulse oximetry in ventilated preterm newborns: reliability of detection of hyperoxaemia and hypoxaemia, and feasibility of alarm settings. Acta Paediatr 1995;84:613–616.
111. Baeckert P, Bucher HU, Fallenstein F, Fanconi S, Huch R, Duc G. Is pulse oximetry reliable in detecting hyperoxemia in the neonate?, Adv Exp Med Biol 1987;220:165–169.
112. Bragiroli A, Sacco C, Carone M, Donner CF. Pulse oximeter and transcutaneous O_2 monitoring: criteria for a choice. Eur Respir J Suppl 1990;11:515s–517s.
113. Fallenstein F, Baeckert P, Huch R. Comparison of in-vivo response times between pulse oximetry and transcutaneous $p\mathrm{O}_2$ monitoring. Adv Exp Med Biol 1987;220:191–194.
114. Wimberley PD, Helledie NR, Friis-Hansen B, Fogh-Andersen N, Olesen H. Pulse oximetry versus transcutaneous $p\mathrm{O}_2$ in sick newborn infants. Scand J Clin Lab Invest Suppl 1987;188:19–25.
115. Wimberley PD. Oxygen monitoring in the newborn. Scand J Clin Lab Invest Suppl 1993;214:127–130.
116. Poets CF, Southall DP. Noninvasive monitoring of oxygenation in infants and children: practical considerations and areas of concern [see comments]. Pediatrics 1994;93:737–746.
117. Mike V, Krauss AN, Ross GS. Doctors and the health industry: a case study of transcutaneous oxygen monitoring in neonatal intensive care. Soc Sci Med 1996;42:1247–1258.
118. American Academy of Pediatrics Committee on Drugs: Guidelines for monitoring and management of pediatric patients during and after sedation for diagnostic and therapeutic procedures. Pediatrics 1992;89:1110–1115.
119. Wimberley PD, Burnett RW, Covington AK, Maas AHJ, Mueller-Plathe O, Siggaard-Andersen O, Weisberg HF, Zijlstra WG. Guidelines for transcutaneous $p\mathrm{O}_2$ and $p\mathrm{CO}_2$ measurement. IFCC document. Ann Biol Clin 1990;48:39–43.

See also BLOOD GAS MEASUREMENTS; CARDIOPULMONARY RESUSCITATION; RESPIRATORY MECHANICS AND GAS EXCHANGE.

COBALT-60 UNITS FOR RADIOTHERAPY

JOHN R. CUNNINGHAM
Camrose, Alberta, Canada

INTRODUCTION

Cobalt is a metal, between iron and nickel, in the periodic table. It resembles them and occurs fairly commonly in iron and nickel ores, such as those found near Sudbury, Ontario, Canada. Cobalt as a substance has been known since about the mid-1700s. It was discovered in 1735 by a Swedish chemist named Brandt and was named after Kobald, a goblin from Germanic legends, known for stealing silver. Its salts were used in ancient days for making pigments, which produced brilliant blue colors in pottery.

The ancient Egyptians used it in painting murals in tombs and temples. It is necessary, in trace amounts, for proper nutritional balance.

The nucleus of ^{59}Co, which is the only isotope of cobalt found in Nature, has 27 protons and 32 neutrons. It happens to have an unusually large neutron capture cross-section, which means that bombardment with neutrons turns many of its atoms into ^{60}Co, which is very highly radioactive. ^{60}Co has a relatively long half-life (5.26 years) and it decays to ^{60}Ni by the emission of a beta particle (an electron). ^{60}Ni is also radioactive and emits two energetic gamma rays with energies 1.17 and 1.33 MeV. Million electron volts = MeV. An electron volt is the amount of energy an electron has when it is accelerated through a voltage of 1 MV. It is very small: $1\ \text{MeV} = 1.602 \times 10^{-13}$ J. These gammma-rays are produced in almost equal number and the pair of them can be approximated by their average 1.25 MeV, to form radiation that has high penetration in matter.

Cobalt has an atomic weight of 58.933 atomic mass units (amu), a mass density of 8900 kg/m^3, and melts at ~ 1500 °C. All of these properties combine to make it unique as a practical source of radiation for cancer treatment, industrial radiography, sterilization of food, and other purposes requiring intense but physically small sources of radiation.

It was not isolated as a metal until early in the eighteenth century and was not used for its metallic properties until the twentieth century. Its most important modern use is in the production of alloys of steel that are very hard and very resistant to high temperatures. These alloys find their uses in cutting tools and such diverse products as jet engines and kitchen cutlery.

HISTORY

Sampson et al. (1) noted the interesting radioactive properties of ^{60}Co at least as early as 1936. Livingood and Seaborg (2) described its properties in 1941. W.V. Mayneord, of the Royal Cancer Hospital in London (later the Royal Marsden Hospital), and A. J. Cipriani, then Head of the Biology Division at Chalk River, Ontario, Canada, described its production by neutron bombardment of ^{59}Co in a nuclear reactor in 1947 (3).

In June of 1949, H.E. Johns, then professor of physics at the University of Saskatchewan, Canada, and physicist to the Saskatchewan Cancer Commission, visited the NRX nuclear reactor at Chalk River, Ontario, to discuss, with Cipriani and others, the possibilities of irradiating a sample of cobalt in order to produce a ^{60}Co source. The theoretical advantages of using the energetic gamma rays of ^{60}Co to destroy cancer cells had been known for some time, but practical problems of source production centered on the availability of a reactor with a sufficiently high neutron flux combined with a facility to handle and prepare the resulting highly radioactive source. Earlier, in 1945, J.S. Mitchell of Cambridge and J.V. Dunworth of Chalk River had discussed the possibilities of producing ^{60}Co using the high neutron flux expected to be available from NRX, a nuclear reactor being built at the Chalk River site. At that time NRX was not yet operating, but in 1949, when Johns visited it, it was. The NRX is a heavy water reactor and at that time had the highest available neutron flux in the world ($\sim 3 \times 10^{13}$ neutrons/cm^2/s). The reactor was heavily involved in a program of radioisotope production and the irradiation of cobalt was taken to be part of this program.

Arrangements were made to irradiate three samples of cobalt and they were placed in the reactor in the fall of 1949. They were removed ~ 1.5 years later. The first source was destined for a cobalt unit being designed and built by Dr. Johns and his students in Saskatoon (4). It was delivered there in July of 1951 and on the 18th of August it was installed in the cobalt unit that had been prepared for it. The second source was sent to the Victoria Hospital in London, Ontario, where it was installed on the 23rd of October 1951 in a unit that had been designed and built by Eldorado Mining and Refining Company (later Atomic Energy of Canada Ltd.). Dr. Ivan Smith treated the first patient in London on 27th of October 1951, just 4 days after the installation of the source. The first patient treated on the Saskatoon unit, by Dr. T.A. Watson, was on the 8th of November 1951. Some mystery surrounds the details of the third source. There is some evidence that it was originally intended to go to Mayneord in England, but that in 1951 it was considered that postwar reconstruction was not yet sufficiently advanced there so it was diverted to the M.D. Anderson Hospital in Houston, Texas. It was to be installed in a unit designed by L.G. Grimmett, who had recently been hired by Dr. Gilbert Fletcher largely for this task (5). Part of the mystery concerns the fact that it was delayed in its irradiation and was actually removed from the reactor for a time and later replaced. Some have suggested that this may have been related to the outbreak of the Korean War and the general sensitivity concerning nuclear matters. Whatever the reason, it was not actually shipped until July of 1952, almost a full year later than the other two sources. The M.D. Anderson unit was then at Oak Ridge Tennessee for experimental purposes and was transferred, with its source, to the M.D. Anderson Hospital in Houston in September of 1953. The first patient was treated, in Houston, on the 22nd of February 1954. Pictures of these three cobalt units are given in Fig. 1. Roger F. Robinson has told an informative and interesting history, which includes many details about the original sources, as well as stories about a number of the people involved(6).

Each of these three sources was used in cobalt units for the treatment of cancer for many years. The two Canadian units became prototypes for units that were subsequently sold commercially. The unit in London, built by Atomic Energy of Canada Ltd., was the first of a long series of machines manufactured by them. The first series was known as the “Eldorado” series. A later series of units went under the name “Theratron”. The descendant of that company: MDS Nordion, is still building and selling cobalt units. The Saskatoon unit, designed by H. E. Johns and several of his students at the University of Saskatchewan, was made by John MacKay of the Acme Machine and Electric Co. Ltd. in Saskatoon (7) and later commercially by Picker X-ray of Cleveland, Ohio. Each of these units is pictured in Fig. 1 near the times of their source installations.



Figure 1. The worlds first three cobalt units. Clockwise from above London, Ont., Canada, Saskatoon, Sask., Canada and Houston, Texas.

Before 1951, radiation therapy had been carried out almost exclusively by X-ray machines operating at tube voltages of 400,000 V or less. Such machines produce X-ray beams having a broad spectrum of X-ray energies with an average of one-third or less of the maximum. Thus, a 400 kV machine would correspond to a single energy of ~ 133 keV. Cobalt-60, with its average photon energy of 1.25 MeV, is the equivalent of an X-ray machine operating about six times the old value. As will be seen later, cobalt units are also mechanically and electrically simple devices and, following their introduction, rapidly became the standard machine for treating nearly all cancers other than that of the skin. Cobalt units have now been almost completely replaced by linear accelerators, which produce X rays having still greater penetration and higher outputs allowing shorter treatment times.

THE PHYSICS OF ACTIVATION: EXPOSURE AND DOSE

Only the physics directly related to the description of ^{60}Co sources and units will be discussed here. More detailed information can be found in standard textbooks such as those of Attix (8), Greening (9), and Johns and Cunningham (10).

Almost any material placed within the neutron radiation field of a nuclear reactor will become radioactive. The probability of this happening is determined by the cross-section of the material for capturing a neutron. The cross-section is the equivalent of a probability, although it is usually expressed as an area. Many atoms have neutron capture cross-sections, of the order of 10^{-24} cm^2 around 1935, Enrico Fermi, then in Rome, was measuring these cross-sections. When he found one of about this size he exclaimed, "That's as big as a barn!" 1 barn $= 10^{-24}$ cm^2 is the common measure of nuclear cross-section and its use is permitted by the International System (SI) of units, and if a neutron passes through this area it is "captured" by the nucleus to form a new nuclear species, which usually is radioactive.



Figure 2. The decay schemes of ^{60}Co and ^{60}Ni, showing the beta particle energies of ^{60}Co and the gamma-ray energies from ^{60}Ni.

The interaction of the neutron with a nucleus is quite complex, and a number of different products may be formed. The nucleus may capture the neutron to produce a new species that is stable, or the neutron may be re-emitted at the same or a different energy. In the latter case, we refer to the process as neutron scattering. The production of ^{60}Co is an example of neutron capture. A nucleus of ^{59}Co absorbs a neutron and forms ^{60}Co, which is radioactive and decays with a half-life of 5.26 years by the emission of an electron that turns it into an isotope of nickel, ^{60}Ni. The decay scheme of ^{60}Co and ^{60}Ni is shown in Fig. 2. The two gamma rays mentioned earlier are actually emitted by the Nickel nucleus ^{60}Ni. Some properties of cobalt and its radiation are given in Table 1.

The ^{60}Co activity produced is determined by the neutron flux density in the reactor, the neutron capture cross-section, the amount of ^{59}Co inserted into the reactor, and the length of time it is left there. The rate of production of radioactive atoms can be expressed as

$$\frac{N}{t} = N\sigma\phi \qquad (1)$$

where N is the number of ^{59}Co atoms placed in the reactor, σ is the neutron capture cross-section per atom, ϕ is the flux density of neutrons, and Δt is a time interval. The

Table 1. Properties of Cobalt and Its Radiation

Property	Value
Cobalt-59	
Atomic number	$Z = 27$
Atomic weight	$A = 58.933$ amu
Mass density	$\rho = 8900$ kg/m^3
Melting point	1500 K
Neutron capture cross-section	$\sigma = 37 \times 10^{-24}$ cm^2
Cobalt-60	
Half-life	$T_{1/2} = 5.26$ years
Bata energies	0.313 MeV (99.8%) 1.486 MeV (0.12%)
Nickel-60	
Photon energies	$\gamma_1 = 1.733$ MeV $\gamma_2 = 1.332$ MeV
Interaction coefficient in water	$(\mu/\rho) = 0.0698$ cm^2/g
Average Energy Absorbed in water	$E_{\mathrm{ab}} = 0.456$ MeV
Half-value layer in Pb	$X_{1/2} = 11$ mm

parameter ΔN will be the number of activations that take place in this time interval.

As an illustrative numerical example, consider a sample of 15 g of ^{59}Co to be located in a nuclear reactor at a point where the neutron flux density is 10^{14} cm^{-2}/s. This represents a source that is 1.5 cm in diameter and ~ 1 cm high and is fairly representative of sources and neutron fluxes that have been used. The original two Canadian sources were 2.54 cm in diameter and composed of ~ 26 disks each 0.5 mm thick. The American source was square in cross-section. From Eq. 1, and with the use of some of the information given in Table 1, we calculate the number of atoms of ^{59}Co that are converted to ^{60}Co during a period of time Δt. We also require a value for Avogadro's Number N_A, so that we can calculate the number of atoms (at) of ^{59}Co in 1 g of the substance.

$$N_A = 6.023 \times 10^{23}\,\mathrm{atoms/mol}$$

The number of ^{59}Co atoms in our 15 g sample is

$$N_{^{59}\mathrm{Co}} = 15\,\mathrm{g} \times \frac{6.023 \times 10^{23}\mathrm{at}}{\mathrm{mol}} \times \frac{1\,\mathrm{mol}}{58.933\,\mathrm{g}} = 1.533 \times 10^{23}\,\mathrm{at}$$

From Table 1, we see that the cross-section for neutron capture in ^{59}Co is 37×10^{-24} cm^2/atom. If the 15 g of cobalt were left in the reactor at this location for a period of 1 h, the number of atoms (at) converted to ^{60}Co, following Eq. 1, would be

$$N = 1.533 \times 10^{23} \times \frac{37 \times 10^{-24}\mathrm{cm}^2}{\mathrm{at}} \times \frac{10^{14}\,\mathrm{cm}^{-2}}{\mathrm{s}} \times \frac{3600\,\mathrm{s}}{\mathrm{h}}$$
$$= 2.042 \times 10^{18}\,\mathrm{at}$$

Although this appears to be a very large number of atoms it represents only ~ 0.2 mg of ^{60}Co. It does, however, represent a considerable amount of radioactivity and would be easy to measure.

The most fundamental parameter for the specification of the strength of a radioactive source is activity. Activity is defined as the number of decay processes that occur per second and its special unit is the bequerel (Bq), which is defined to be an average of one nuclear disintegration each second. Activity is easy to describe theoretically, but is very difficult to determine experimentally. It can be inferred from the number of atoms of the substance and the value of its half-life, which for ^{60}Co is given in Table 1 as 5.26 years.

Activity can be calculated from the simple relation

$$A = N\lambda \qquad (2)$$

where λ is a constant of proportionality known as the transformation constant. It is related to the half-life $T_{1/2}$, of the radioactivity by

$$\lambda = \frac{0.693}{T_{1/2}} \qquad (3)$$

where the number 0.693 is the natural logarithm of 2.

For example, the activity of ^{60}Co that would result from the above irradiation of 15 g of ^{59}Co would be

$$A = 2.04 \times 10^{18} \times \frac{0.693}{5.26\,\mathrm{year} \times 3.1557 \times 10^6\,\mathrm{s/year}}$$
$$= 0.0852 \times 10^{12}\,\mathrm{s}^{-1} = 85.2 \times 10^9/\mathrm{s} = 85.2\,\mathrm{GBq} \qquad (4)$$

where the half-life $T_{1/2}$ has been expressed in seconds. The activity that is actually produced in a reactor irradiation is considerably less than this theoretical amount. This is largely due to attenuation of the neutron flux by the considerable mass of the cobalt.

The more traditional unit of activity has been the curie (Ci), which corresponds to 3.7×10^{10} nuclear decays/s. The activity of the above source, stated in curies would be

$$A = \frac{85.2 \times 10^9}{\mathrm{s}} \times \frac{1\,\mathrm{Ci}}{3.7 \times 10^{10}/\mathrm{s}} = 2.30\,\mathrm{Ci}$$

The specification of a commercial source of radiation in terms of activity is not very practical because activity does not uniquely relate to the radiation output when an individual source is loaded into a treatment unit. The output will depend on the physical size and configuration of the source and the design of the collimator of the treatment unit.

This problem was solved by the use of a quantity called exposure. Exposure is defined in terms of the amount of ionization that is produced in air by the radiation. The special unit is the roentgen (R). One roentgen corresponds to the release of 2.58×10^{-4} C/kg of air.

For gamma-ray emitters, such as this one, a quantity known as the exposure rate constant (Γ), has been defined that relates the activity in curies to the exposure rate in roentgen/hour at a point in air 1 m from the source. It is calculated from the gamma-ray spectrum using the interaction coefficients of air (the required data are given in Table 1). For a ^{60}Co source, Γ, is

$$\Gamma = 1.29\,\mathrm{R \cdot m^2/h \cdot Ci^{-1}}$$

This allows calculation of the parameter that is frequently used to specify source strength: the "roentgens per hour at a meter" (Rmm). For our 2.30 Ci source it is

$$\mathrm{Rmm} = 2.30\,\mathrm{Ci} \times \frac{1.29\,\mathrm{R \cdot m^2}}{\mathrm{h \cdot Ci}}\,\frac{1}{1\,\mathrm{m}^2} = 2.97\,\mathrm{R \cdot h}$$

A much more practical quantity, from the point of view of radiotherapy, is the absorbed dose rate produced at some agreed distance. To explain this, it will be useful to first define absorbed dose and to go through some approximate calculations connecting activity and absorbed dose rate.

Absorbed dose is the physical quantity that most closely correlates with the biological effect of the radiation and it is defined (11) as the amount of energy absorbed per unit mass of an irradiated material. The special unit of absorbed dose is the gray (Gy), which is defined as 1 joule (J) of energy imparted to 1 kg of matter.

A ^{60}Co activity of 85.2×10^9 Bq, as derived above, would give rise to the following photon fluence rate at a distance of 1 m.

$$\psi = 2\,\frac{A}{4}\,\frac{1}{100^2} = \frac{85.2 \times 10^9\,\mathrm{Bq}}{2\ 10^4\,\mathrm{cm}^2} = 1.356 \times 10^6\,\mathrm{cm}^{-2}/\mathrm{s} \qquad (5)$$

The rate of photon interactions with a mass M of the water is given by

$$N' = \sum_i \psi_i \left(\frac{\mu}{\rho}\right)_i M \qquad (6)$$

where ψ_i is the fluence (number crossing an area equal to 1 cm^2) of each of the photon energies, $(\mu/\rho)_i$ is the mass interaction coefficient for each of them. The parameter(μ/ρ) expresses the cross-section, or probability of interaction of photons with 1 g of material and M is the mass of the material in grams. The summation in Eq. 6 is over the two components of the photon spectrum as depicted in Fig. 2.

Since the photon energies are so close together, we can use the average value of the interaction coefficients, which is given in Table 1 as 0.0698 cm^2/g. The rate of photon interactions, calculated from Eq. 6, would then be

$$N' = \frac{1.356 \times 10^6}{\mathrm{cm^2 s}} \times 0.0698 \, \frac{\mathrm{cm^2}}{\mathrm{g}} \times 1\,\mathrm{g} = 94.6 \times 10^3/\mathrm{s} \qquad (7)$$

Each photon that interacts imparts an average of 0.456 MeV (Table 1) of energy so the rate of energy absorbed E', from this irradiation would be

$$E' = \frac{94.6 \times 10^3}{\mathrm{s}} \times 0.456\,\mathrm{MeV} = 43.1 \times 10^3 \, \frac{\mathrm{MeV}}{\mathrm{s}} \qquad (8)$$

This is a very tiny amount of energy. It was deposited in 1 g of water. Its value can be converted to a more familiar energy unit by using the relation 1 MeV = 1.6022×10^{-13} J. The absorbed dose rate from these photons would then be

$$\begin{aligned} D' &= 43.1 \times 10^3 \, \frac{\mathrm{MeV}}{\mathrm{g\,s}} \times \frac{1.6022 \times 10^{-13}\mathrm{J}}{1\,\mathrm{MeV}} \times \frac{10^3\,\mathrm{g}}{\mathrm{kg}} \qquad (9) \\ &= 69.1 \times 10^{-7} \, \frac{\mathrm{J}}{\mathrm{kg\,s}} = 6.91 \times 10^{-6}\,\mathrm{Gy/s} \end{aligned}$$

$$D = 6.91 \times 10^{-6} \, \frac{\mathrm{Gy}}{\mathrm{s}} \times 3600 \, \frac{\mathrm{s}}{\mathrm{h}} = 0.025\,\mathrm{Gy} \qquad (10)$$

A simple radiation treatment for cancer typically involves an absorbed dose at the tumor of 2.0 Gy (in the old units; 200 rad), and because of attenuation in the tissues, and various other factors, this implies, for say a 2 min treatment, an activity almost 5000 times stronger than in our example source. The distance from the source to the tumor has typically been 80 cm. This would call for a source activity of $\sim 25 \times 10^{13}$ Bq or 250 TBq or $\sim$7500 Ci.

To attain this, the cobalt must be left in the reactor for a much longer time than in our example above. With a longer activation, one must note that while ^{60}Co is being formed it is also decaying. The resulting activity would be the sum of that which is being produced, as described by Eq. 1, and the amount that decays. This can be written as

$$\frac{dN}{dt} = N_0 \, \sigma \, \phi - \lambda N \qquad (11)$$

where N_0 is the initial number of ^{59}Co atoms present and λ is the transformation constant (see Eq. 2) for the ^{6O}Co decay. The other symbols have the same meaning as for Eq. 1. The solution to this equation, expressed in terms of activity, is

$$A(t) = A_{\max}(1 - e^{-\lambda t}) \qquad (12)$$

where $A_{\max} = N_0 \, \sigma \, \phi$ is the maximum activity attainable for an infinitely long irradiation. For the neutron irradiation conditions of our example, the maximum activity attainable is

$$\begin{aligned} A_{\max} &= 1.533 \times 10^{23}\,\mathrm{at} \times 37 \times 10^{-24} \, \frac{\mathrm{cm^2}}{\mathrm{at}} \times \frac{10^{14}}{\mathrm{cm^2 \cdot s}} \qquad (13) \\ &= 56.72 \times 10^{13}/\mathrm{s} = 567.2\,\mathrm{TBq} = 15,000\,\mathrm{Ci} \end{aligned}$$

It would require 5 years in the reactor to produce a source half this strong, that is, 7500 Ci.

This is not strong enough for modern treatment requirements and a higher neutron flux is required. As time has passed, reactor fluxes have increased considerably, and this has allowed both the irradiation times to be shortened and the sources to be made smaller.

There are a number of advantages to making cobalt sources as small as possible. One of these has to do with the sharpness of the edges of the radiation beam. This is known as penumbra and will be discussed later under that topic. It will be seen that a small diameter source is desirable. Another reason for a small source has to do with the amount of self-absorption and photon scattering that will take place within it. The source that we have been considering was a cylinder 1.0 cm in height, and for the gamma rays of cobalt this is almost a half value layer even in lead (Table 1), let alone in cobalt. It must be expected that the radiation emitted by such a source would be accompanied by considerable attenuation and would include an appreciable component of scattered photons. Because of the attenuation and scatter that takes place in the source, the dose rate is greatly overestimated in the calculations made above. The larger the source physically, the greater the activity required to give a desired dose rate.

SPECIFICATION OF SOURCE STRENGTH

In actual practice, the strength of the source is stated in terms of exposure rate at 1 m (Rmm). This is a measured quantity and is determined by the vendor of the source. Sources delivering up to 250 R/min at a meter are now available.

One way of judging the "efficiency" of the neutron irradiation is by stating the specific activity of the source produced. This is the activity, expressed in becquerel (or curie) per gram of cobalt. The specific activity of a 7500 Ci source that weighed 15 g would be 7500 Ci/15 g = 500 Ci/g. In modern reactors, the neutron flux density can be greater than the $10^{14}/\mathrm{cm}^{-2} \cdot \mathrm{s}^{-1}$ that we assumed, sources can be irradiated for longer times than in the example. Specific activities of up to 500 Ci/g have been produced. Cost goes up linearly with irradiation time, but, as can be seen, activity does not, and source strengths actually produced are decided by economic considerations. In actual practice, sources are not irradiated as solid cylinders, as has been assumed for this example, but rather they are made up into a capsule on demand from stocks or pellets that were preirradiated to a selection of specific activities. Pellets are shown in Fig. 3 along with a pair of stainless steel containers into which they will be placed. The pellets will be loaded into the cylinder shown in the center of the picture, then spacers, such as those shown on the right, are inserted to hold the pellets in position, and finally this cylinder, when capped, is inserted into the cylinder shown on the left and cold-welded shut. All



Figure 3. Cobalt pellets and source capsule with components.

of these operations are carried out remotely in a hot cell. Finally, the source is shipped in a well-protected and shielded container to be loaded into a cobalt unit.

COBALT UNIT DESIGN

The first cobalt units went into operation in 1951. Very soon after that they became available commercially, and the production of cobalt sources and cobalt units expanded to such an extent that, for 30 years, more radiotherapy was carried out with ^{60}Co than with all other types of radiation combined. Cobalt machines have the tremendous advantages of producing a completely predictable, steady, reliable beam of relatively high energy radiation, being mechanically simple, rarely needing repair, and being easy to repair when required.

HEAD DESIGN

In all cobalt units, the source is placed near the center of a large, lead-filled steel container. A device is provided for moving the source from a position where it is "Off", because it is shielded in all directions, to a position opposite an opening through which the useful beam may emerge. A number of mechanisms have been devised for moving the source, and two of them are shown in Fig. 4. In Fig. 4a, the source is mounted in a heavy metal (mostly tungsten) wheel that may be rotated through 180° to carry it from the Off position to the On position. In Fig. 4b, the source is mounted in a sliding plug or drawer that carries it from the Off to the On position. In one of the first cobalt units (the Eldorado A), the source did not move at all. The beam opening was filled with a tank of mercury that was pumped out of the way by air pressure to turn the machine On and then the mercury returned by gravity to turn the beam Off.



Figure 4. Two designs for cobalt unit heads. (a) A rotating wheel carries the source to the "on" position. A multiplane collimator controls the size of the rectangular beam. (b) A sliding drawer moves the source and a multileaf collimator moves on an arc to control the beam.

The sliding drawer mechanism shown in Fig. 4b has tended to be the more commonly used.

All machines must be arranged so that they fail "safe". That is, the source must be held in the On position by the continuous application of a force so that if the power fails, it must return quickly to the Off position. For both a and b in Fig. 4, this is provided by a strong spring. The lead-filled container, or "head" of the unit, must be of the order of 25 cm thick in all directions from the source. The design criteria will depend on the regulations in force where it is to be used, but basically it must be such that the leakage radiation emerging from the shield would not cause an overexposure to anyone staying at its surface for prolonged periods of time. This would imply, for example, a yearly equivalent dose of not >5 mSv (or - 500 mrem) at a distance of 1 m from the source. This exposure level is greater than the average in low natural background areas, but is less than the exposure in many other regions of the world where people live. The sievert (Sv) is the special unit of equivalent dose. One sievert will result in the same biological effect as 1 (Gy) gray of conventional X rays. If we assume a maximum source strength of 10,000 Ci, and again use the exposure rate constant of 1.29 R $m^2/h{\cdot}Ci^{-1}$, and assume that 1 R corresponds to an equivalent dose of 0.01 Sv, this would imply a thickness of 20–30 half-value layers. The half-value layer in lead for cobalt radiation is ~ 1.1 cm (Table 1), and this calculation would imply a thickness of ~ 30 cm. In actual practice a much more detailed calculation would be done, augmented by measurement.

This simple calculation can serve as a guide only. The half-value layer for a broad beam of radiation, such as in this case, would be >1.1 cm. On the other hand, it is unlikely that anyone would remain for a whole year just beside the head of the cobalt unit. In fact, 20–25 cm is about the thickness of the heads of most cobalt units.

Figure 4 also shows two types of collimators. Both consist of sets of bars that can be adjusted to produce a radiation beam with a rectangular cross-section. The diagrams at the bottom of Fig. 4 show an end-on view of the appearance of both collimator bars in the open and the closed positions.

MOUNTS

There are only two basic ways of mounting and "porting" radiation treatment units. One of the two oldest designs is illustrated in Fig. 5 and is an example of the so-called SSD mount. The head of the unit was held in a yoke, which was suspended by a column from a set of rails attached to the ceiling. It could be moved up and down or back and forth and the head could be rotated about the horizontal axis seen. The unit was also equipped with a treatment applicator, which in this case was mounted on the end of the collimator. The motions of the mount allowed the unit to "point" over a wide range of directions and enabled the operator to place the end of the treatment applicator against the skin of the patient at a prescribed location. The floor was left clear to allow easy and full movement of the treatment couch. The distance from the source to the skin of the patient (SSD) was thus a fixed quantity, usually 80 cm, and the focus of the "setup" was the surface of the patient. The size of the beam was defined there, and the reference point for dosimetry was just under the skin.



Figure 5. A Picker cobalt unit at the Ontario Cancer Institute, Toronto in the 1960s–1980s. The unit was mounted on a column suspended from rails on the ceiling leaving the floor clear. A protractor allows the angle to be set carefully using the "SSD" technique. The rack on the wall holds "wedge filters" that shape the beam intensity.



Figure 6. An isocentric mounted cobalt unit of the Theratron series produced by Atomic Energy of Canada Ltd., installed at the Ontario Cancer Institute in Toronto in the 1970s and 1980s.

The alternative mount is the so-called isocentric or fixed source-axis-distance (SAD) mount. An example, dating from the 1970s and 1980s is shown in Fig. 6. The head, encased in a streamlined plastic cover, is mounted on a gantry that can rotate about a horizontal axis. The patient lies on a couch as shown and is raised, lowered, moved sideways, or lengthways so that the tumor is positioned on the intersection of the gantry axis and the collimator axis. This means that for any angle of the gantry, the beam will pass through the tumor. This point is called the isocenter and was a fixed distance from the source, usually 80 cm, in later units 100 cm. The beam is specified by its size at the isocenter. The focus of attention is now at the tumor rather than the surface. In addition, the couch can usually be rotated about a vertical axis, also passing through the isocenter. Virtually all modern treatment units are mounted in the isocentric manner.

The procedures for treatment planning and dosimetry are somewhat different for each of these two types of mount. Treatment planning is discussed in several standard textbooks such as those by Bentel (12), Johns and Cunningham (10), and Kahn (13).

In 1956, an early and innovative symposium was held at Oak Ridge Institute of Nuclear Studies, just before the Eighth International Congress of Radiology, which was held in Mexico City. Problems of source production, machine design and installation, dosimetry, and source specification were discussed. The title of the publication that resulted from this symposium "Roentgens, rads and Riddles", largely reflected the uncertainties of the day in dosimetry. It also includes some history to that time and descriptions of a variety of cobalt units that had been made experimentally and by commercial suppliers.

Cobalt units are inherently simple machines and can be designed and constructed by relatively unsophisticated


(a) (b) (c)

Figure 7. Three experimental cobalt unit designs: (a) a unit with a number of special features, (b) a double-headed unit, and (c) a unit for half-body irradiation.

engineering facilities. This is illustrated by Fig. 7, which shows three quite different units that were designed and built at the Ontario Cancer Institute in Toronto. The unit in (a) was built in 1959 and had a number of special experimental features (14). These included a diagnostic X-ray tube installed in the head of the unit so that good quality placement films could be taken of patients undergoing treatment. This facility is now standard equipment in all modern radiation treatment machines. The films are called "port films". It was isocentrically mounted and was capable of full 360° rotation about the patient. This allowed continuous rotation during treatment or easy set up for the use of several fixed fields from different angles. The latter feature too, is standard on modern machines. The unit also had a large (95 cm) source-to-axis distance, which improved the depth dose characteristics (see the following section). This unit also had an ionization chamber in the counterweight so that the effective thickness of the patient could be determined. This did not prove to be as useful as expected and was not adopted by unit manufacturers.

The unit in Fig. 7b contained two sources and was called the Double-Header (15). The sources were arranged to be very nearly equal in strength and the beams were directed opposite to each other. This provided an automatic "parallel pair" of beams, which forms a component of many multiple field treatments. The real reason for the two sources, however, was to extend their useful life. The Ontario Cancer Institute had, at different times, as many as eight other cobalt units and two of the sources, after each had been used for ~5 years (approximately one half-life) in one or another of them were transferred to the Double-Header for another 5 years of use.

The third cobalt unit depicted in Fig. 7c, was especially designed for "half-body" treatments. It was equipped with a special collimator to provide radiation fields up to 150 cm long and 50 cm wide. It was fitted with a compensating filter so that a uniform dose distribution could be achieved (16).

CHARACTERISTICS OF THE RADIATION BEAM

The decay scheme for ^{60}Co is shown in Fig. 2. There are two γ rays of photon energies 1.17 and 1.33 MeV, respectively. These energies are very close to each other, so ^{60}Co is almost a monoenergetic emitter with energy 1.25 MeV. The actual beam from a cobalt source also contains lower energy photons, which come from the scattering processes that take place within the source. It is also inevitably contaminated with photons scattered from the mechanism that holds the source in position as well as from the various collimator components that are "in view" of the source. That the beam is not purely that from ^{60}Co is attested to by the fact that the linear attenuation coefficient for 1.25 MeV photons in water is 0.0698 cm^{-1} (Table 1), while the experimentally determined coefficient for a cobalt unit beam in water is closer to 0.063 cm^{-1}. A rather more "realistic" spectrum of the radiation for a cobalt unit has been determined by Rogers et al. (17) by Monte Carlo calculations. The low energy components contribute up to ~15% to the dose received by the patient.

In a patient, the intensity of a radiation beam falls off approximately exponentially. This can be seen from the data plotted in Fig. 8, where percentage depth doses for cobalt-60 radiation, and a few other radiations used in radiotherapy, are shown plotted against depth. Percentage depth dose is the single most important quantity in choosing a radiation for radiotherapy. The radiations shown vary from that produced by 100 kV X rays to 25 MV. The depth at which the percentage depth dose falls to



Figure 8. Percentage depth doses plotted against depth for a series of beam energies from superficial (low energy X rays) to megavoltage radiation. All curves are for a 10 × 10 cm field and the depth to 50% dose can be easily determined.

50% can be seen for each radiation by reference to the horizontal dashed line. It varies from < 2 cm for the superficial radiation through ~ 7 cm for "conventional" or 250 kV radiation, ~ 12 cm for ^{60}Co radiation, to > 22 cm for the 26-MV radiation. Cobalt-60 is right in the middle of this range. The graphs in Fig. 8 also show that for the higher energies, the dose at the surface is low and rises as penetration increases. For ^{60}Co radiation, it reaches its maximum at a depth of 0.5 cm and falls off relatively slowly from there. This low dose on the surface, the so-called skin sparing effect, was one of the important properties cobalt radiation had for radiotherapy.

When the cross-sectional area of a radiation beam is small, the dose received at a point below the surface is due almost entirely to primary radiation. As the area of the field is increased, the doses will increase due to an increase in scattered radiation. The greater the depth, the greater the increase, with the result that percentage depth dose increases with field size.

CALIBRATION

Calibration of the output of a cobalt unit is normally done with the use of an ionization chamber that has been calibrated against a standard exposure reference at a standardization laboratory. A calibration factor N_X, is determined by the laboratory and its meaning is that $N_X = X/M$, where X is a known exposure and M is the reading of the electrometer monitoring the ionization produced in the chamber by the radiation.

The traditional and simplest method for calibrating the output of a cobalt unit has been to measure exposure rate in air at a chosen distance and field size, and to derive from this the absorbed dose rate that would occur at the center of a small mass of tissue-like material located at this point. An alternative, but equivalent, method is to determine the dose at a chosen position at a specified depth in a water phantom, again for a specified beam size.

Procedures for calibration, and the mathematical formalism required, to determine absorbed dose from exposure measurements are given in textbooks (9,10), as well as in various dosimetry protocols, both national and international. Examples are those of the American Association of Physicists in Medicine (18) and the International Atomic Energy Agency (19). Since the calibration procedures will only be outlined here, these sources should be consulted for more detailed procedures.

Calibration in Air



Figure 9. Diagrams showing the meaning of a number of functions used for calibration and dose calculation for treatment planning.

A number of physical arrangements for making measurements in a radiation beam are illustrated in Fig. 9. The diagram on the left can be used to refer to calibration in air. An ionization chamber, which has been calibrated in terms of exposure, is placed at point P′, free in air, and a reading, M, is taken for a specified "source-on" time T. This exposure time must be the actual exposure time; that is, it must be exclusive of a time, if any, taken for the source mechanism to move the source from the off to the on position. The reading, M, must also include any adjustment required for atmospheric conditions if the temperature and pressure differ from those that pertain to the exposure calibration factor. This would normally be 22°C and 101.3 kPa (equivalent to 1 atm, or 760 mmHg). The parameter M must also be corrected for any small loss of charge that might occur due to charge recombination in the ion chamber during the exposure. Methods for making all of these corrections are discussed in Ref. 9,10,14, and 15. The ion chamber must also have been fitted with a buildup cap, if this is required to make its walls sufficiently thick to provide electronic equilibrium in them. The buildup cap must be made of water-like material. With these precautions, the exposure rate at the point designated in Fig. 9 as P′ would be

$$X = N_X \frac{M}{T} \tag{12}$$

If the cobalt unit is "isocentric" in mount, point Q′ would be on the axis of rotation of the gantry, a distance F_P from the source and the field size would be specified at this point. If the unit were operated in an SSD mode, the calibration point would be the one shown as Q′ in Fig. 9 and would be at a distance F_Q from the source. The absorbed dose rate, free in air, may be calculated from the exposure by the following relationship:

$$\dot{D}_{P'} = N_X \left(\frac{M}{T}\right) \left[0.00876 \, \frac{\mathrm{J}}{\mathrm{kg\,R}}\right] \left(\frac{\bar{\mu}_{\mathrm{en}}}{\rho}\right)_{\mathrm{air}}^{\mathrm{wat}} k(d_Q) \tag{13}$$

The term in square brackets is derived from the definition of the roentgen, which is the release of a certain electrical charge per kilogram of air, and the average energy required to release 1 C of this charge. (One roentgen is defined as the release of 2.58 × 10 C/kg of air, and each coulomb released requires an average 33.85 J. Thus, 1 R corresponds to 0.00876 J/kg of air.) The next term is the ratio of mass energy absorption coefficients averaged over the radiation spectrum for water to air, and the final term is a correction factor to account for the fact that in order to characterize a dose rate at a point in air, it must be surrounded by at least enough phantom (water-like) material to produce electronic equilibrium. This material will attenuate and scatter radiations, and $k(d_Q)$, the allowance for this, is estimated to be 0.985.

Although the size of the beam at point P′ is larger than it is at point Q′, the collimator opening is the same for both,



Figure 10. Graphs showing relative output data for a cobalt unit. The output is measured in air and is expressed relative to that of a 10×10-cm field.

and so the source self-absorption and scatter, and collimator scatter, would be expected to be essentially the same. Consequently, the dose rate at P′ should be related to that at Q′ by the inverse square law. For any given cobalt unit this must be tested experimentally, but would be expected to be valid except for distances F, of Fig. 9, that are < 50 cm or so

This is indicated by I in Fig. 9 and by the relation

$$\frac{\dot{D}_{Q'}}{\dot{D}_{P'}} = \frac{F_P^2}{F_Q^2} \tag{14}$$

On the other hand, if the collimator opening is changed, the dose rate at points such as P′ or Q′ will change, due principally to a change in the amount of collimator scatter reaching them. The way this output changes for an example cobalt unit is shown in Fig. 10, where relative dose rates measured on the axis (point P′ of Fig. 9) of an isocentric cobalt unit are plotted against the side length of a rectangular field. The data are normalized to 1.00 for a 10×10 cm field. From this diagram, it can be seen that the dose rates differ by $> 8\%$ from a small, 5×5 cm field to a large 25×25 cm field. The family of curves shown represents rectangular fields, and it can be seen that a rectangular field gives approximately the same relative dose rate, as does a square field of the same area. For example, a 5×20 cm field shows a relative dose rate of almost exactly 1.00, as does the square field, 10×10 cm, of the same area. Curves such as these are specific to a particular collimator design and must be determined as part of the procedure of commissioning a new treatment unit.

Calibration in a Phantom

The right-hand diagram in Fig. 9 shows the arrangement for calibration in a phantom. The procedure is essentially the same as that for calibration in air; Q in this diagram has the same location and field size as does P′. The same precautions must be taken with the ion chamber reading and the same calibration factor, N_X, is used. The dose rate at depth d_Q in a water phantom is given by an expression that is very similar to that in Eq. 13:

$$\dot{D}_{P'} = N_X \left(\frac{M}{T}\right)\left[0.00876\,\frac{\mathrm{J}}{\mathrm{kg}\cdot\mathrm{R}}\right]\left(\frac{\bar{\mu}_{en}}{\rho}\right)_{air}^{wat} k(c) \tag{15}$$

$(\bar{\mu}_{en}/\rho)_{wat}^{air}$ is, as before, the ratio of averaged mass-energy absorption coefficients, but in this case they should be averaged over the photon spectrum that is present in the phantom. Values for this ratio are given in Table 2. It is generally assumed to be the same in the phantom as in air, although this cannot be quite correct, as shown by Cunningham et al. (20), Eq. 12. The factor $k(c)$ is very similar to $k(d_Q)$ of Eq. 13, except that c is the radius of the ion chamber as it was configured when the calibration factor was obtained. This factor will be the same whether or not a buildup cap is actually in place in the phantom. The dose rate in a phantom, like that in air, varies with the field size, and a set of data like that shown in Fig. 10 can be compiled. The variation is greater, however, because the beam intensity incident on the phantom changes with collimator opening, as discussed previously, but in

Table 2. Dosimetry Factors for ^{60}Co Radiation[a]

	$(\bar{\mu}_{en}/\rho)_{med}^{wat}$				$(\bar{\mu}_{en}/\rho)_{air}^{med}$			
Spectrum	Graphite	Bakelite	Lucite	Polystyrene	Water	Muscle	Fat	Bone
Ratios of averaged mass energy absorption coefficient for a few materials								
Primary[b]	1.111	1.051	1.029	1.032	1.112	1.103	1.113	1.061
Primary plus scatter[c]	1.116	1.055	1.032	1.037	1.111	1.102	1.107	1.105
Ratios of averaged mass stopping powers								
Primary[b]	1.009	1.071	1.099	1.105	1.129			
Primary plus scatter[c]	1.011	1.073	1.101	1.109	1.131			

Average energy required to cause ionization in air, $W = 33.85$ (dry air)
$= 33.7$ (ambient air)

---

[a] From Ref. 10, page 230.

[b] Assuming monoenergetic 1.25-MeV photons.

[c] Spectrum derived by Monte Carlo calculation for depth 10 cm in a 20×20 cm beam.

addition, the scatter generated within the phantom changes with a change in irradiated volume.

General Calibrations

Radiation beams of energy lower than that of ^{60}Co are most frequently calibrated in air. Radiation beams higher in energy should always be calibrated in a phantom. Cobalt units, because of their energy and constancy of output, form a natural reference for all radiotherapy calibration procedures.

RELATIVE DOSE FUNCTIONS THAT ARE USED IN TREATMENT PLANNING

Over the years, a set of functions has been defined that make possible accurate point dose calculations as part of treatment planning. These are "tissue air ratio", "percentage depth dose", "backscatter factor", and "tissue phantom ratio". They are also used with radiations other than that from Co-60, but several of them were derived or refined for use with cobalt therapy. They will be discussed briefly. They can all be clarified by reference to Fig. 9.

Tissue Air Ratio (TAR)

Tissue air ratio, first called "tumor air ratio", was introduced by Johns to facilitate the calculation of tumor dose for rotation therapy. This type of treatment uses the isocentric mode of operation in that the tumor is placed on the axis of rotation of the treatment unit and the beam may be pointed toward the tumor from a selection of angles. The tissue air ratio, which may be defined by referring to Fig. 9, is the quotient formed by the dose, as determined for point P, on the central ray of the beam in a water phantom to the dose determined at the same point P′, with the water phantom removed. The dose at point P would be determined from Eq. 13 and the dose at P′ by Eq. 15, both exposures being made for the same time interval. In practice, it is assumed that all factors except the ion chamber readings will cancel, and tissue air ratios are actually taken to be

$$T_a(d, W_d) = M_P/M_{P'} \tag{16}$$

In this expression d, is the depth below the surface of the phantom and W_d is the field size at that depth. Tissue air ratio is an expression of the way the radiation beam is attenuated and scattered by the material of the phantom. It is the most fundamental of the relations discussed, and all of the others can be derived from it. Numerical data for this quantity for Co-60 are readily available.

Backscatter Factor

The ratio of doses determined from points Q and Q′ of Fig. 9 is a special value of the tissue air ratio. The depth, d_Q, is the special depth just needed to produce electronic equilibrium at the point of dose measurement. At this point primary attenuation is the same in the phantom at Q and in the small mass of phantom-like material placed at Q′ in order to make the measurement. Most of the scattered radiation reaching point Q is scattered backward from within the phantom. For the range of X rays that were in use before the advent of ^{60}CO, the depth d_Q, was very small and the point Q, was considered to be on the surface, hence the name backscatter factor. This quantity is also called "peak scatter factor" because the depth at which electronic equilibrium is attained also tends to be the depth of peak dose in the phantom. For ^{60}Co radiation, the depth of electronic equilibrium is taken to be 0.5 cm.

Percent Depth Dose

Whereas tissue air ratios relate doses in the phantom to doses free in air, percent depth doses interrelate doses at points within the phantom. Again referring to Fig. 9, the dose at point P is related to that at point Q by the percentage depth dose.

$$P(d, d_Q, W, F_0) = 100 M_P/M_Q \tag{17}$$

For this quantity, the field size is defined at the surface, and the distance F_0 from the source to the surface must be stated. The doses at points P and Q should be determined from ion chamber measurements by the factors indicated in Eq. 15, and, as for tissue air ratios, it is generally assumed that all factors, except for instrument readings, cancel between the numerator and denominator.

Since point P is farther from the source than is Q, part of the falloff in dose with depth is due to the inverse square attenuation. Because of this, percentage depth doses increase with SSD. For example, the most common source–surface distance in use for Co-60 has been 80 cm. This was chosen as a compromise between increasing percentage depth dose and decreasing output. If the surface distance is increased from 80 cm to 1 m, the percentage depth dose at 10 cm in a 10 × 10 cm beam will increase from 55.6 to 57.8. This change is just slightly less than would be entirely accounted for by the inverse square law.

Tissue Phantom Ratios

For radiation of energy higher than that of cobalt, the dosimeter must be equipped with thick walls, and its size makes it inconvenient for use in air—particularly for small field sizes. It becomes convenient, therefore, to make the reference measurement in a phantom rather than in air. This is indicated in the right side of Fig. 9 by the point indicated by Q, which is the same distance from the source as is P (and P′), but is in a phantom at some chosen reference depth. The tissue phantom ratio is then the ratio D_Q/D_P and is entirely analogous to tissue air ratio and has many of the same properties. This quantity is, for example, also independent of distance from the source.

Tissue phantom ratios were introduced by Karzmark et al. (21) for use with high energy radiation, but can be applied equally well to Co-60 radiation.

Relationships between the Dose Calculation Functions

From Fig. 9, one can easily see the relationships between the various doses. For example, D_P can be related to D_Q directly by a percentage depth dose. It could also be expressed by means of two tissue air ratios and the inverse square law:

$$D_{\mathrm{P}} = D_{\mathrm{Q}} \frac{T(d_{\mathrm{P}}, W_{\mathrm{d_P}})}{T(d_{\mathrm{Q}}, W_{\mathrm{d_Q}})} \left(\frac{F_{\mathrm{Q}}}{F_{\mathrm{P}}}\right)^2 = \frac{D_{\mathrm{Q}}}{100} P(d_{\mathrm{P}}, d_{\mathrm{Q}}, W_{\mathrm{d_Q}}, F_0) \quad (18)$$

The tissue phantom ratio is a combination of two tissue air ratios:

$$T\mathrm{p} = \frac{T(d_{\mathrm{Q}}, W_{\mathrm{Q}})}{T(d_{\mathrm{P}}, W_{\mathrm{P}})} \quad (19)$$

PENUMBRA

All of the previous considerations of dosimetry have been for points on the axis of the beam. Treatment planning is a 3D process, and regions not on the axis must also be considered. The behavior of the dose at points off the beam axis can be discussed by referring to Fig. 11.

In Fig. 11a, the radiation beam is incident on a point X′, in air. The conditions are the same as for the left side of Fig. 9. Consider a small dosimeter to be moved laterally across the beam from A to F. At A it is shielded by the collimator, while at X′ it is in the middle of the beam, in full "view" of the source. The dose will be at its greatest value at X′. At C it would still be in full view of the source, but it is slightly further away from the source than it is at X′ and the dose will be slightly lower. The expected doses at A, X′ and C, as well as other points on the line are shown by the dashed lines in Fig. 11b. At point D, the collimator blocks off half of the source and the dose would be expected to be one-half of its value at C. The point at E is just out of view of the source, and ideally the dose here should sink to zero. The portion of the line A–F between C and E is called the geometric penumbra. It is dependent on the diameter of the source, the distance f_c, from the source to the end of the collimator, and the distance $(f–f_c)$, from the end of the collimator to the line A–F. The geometrical penumbra is given by the very simple relation:

$$p = s\,\frac{(f - f_{\mathrm{c}})}{f_{\mathrm{c}}} \quad (20)$$



(a) (b)

Figure 11. Diagrams showing the geometrical considerations involved in describing the shape of a cross-beam profile for a cobalt unit. (a) Shows the source and the collimator and (b) side shows a dose profile line A–F.

The actual measured penumbra differs somewhat from this and is always a little larger. The source does not behave like a sharp, well-defined disk because of its volume, and the radiation therefore scattered within it and the radiation scattered from the structures that hold it in place, and from the beam collimating apparatus. There is also, inevitably, some transmission through the collimator and some scattering from its lower end. The result is that the dose outside of the beam at points A and F is not zero, and the real dose profile is rounded off as depicted by the solid curve in Fig. 11b.

The shape of the dose profile in a phantom for ^{60}Co radiation is only slightly different from that observed in air. The penumbral region is broadened somewhat by the transport of energy along the tracks of the electrons that are set into motion by the photons near the edge of the beam.

The meaning of field size can also be derived from Fig. 11. It is, by convention, taken to be the distance between points B and D. It is indicated as W_{d} in that diagram. This is the distance between the points that are at 50% of the dose on the axis at the same depth. It is also the full width at half maximum (fwhm) of the dose profile. Normally, the measurement of field size would be made in a phantom.

ISODOSE CHARTS

A more complete description of the dosage pattern of the beam is by means of an isodose chart. An isodose chart is a map of the distribution of the dose in a plane. Such charts are found in many books and papers in the literature and only one example will be given here. In Fig. 12, a small



Figure 12. Diagram showing an isodose chart for a beam from a cobalt unit treating a tumor in the neck of a patient. The target and some structures are shown.

beam from an isocentric cobalt unit is treating a tumor in the neck region of a patient. This is an application for which cobalt radiation is still ideal. The target area, which is shown by the cross-hatched region, has been chosen by a radiation oncologist. A safety region has been allowed for and the beam is planned to be directed as shown. The dose at the target will be calculated from the calibration information as described above and (in this case) a tissue air ratio. On the diagram, it has been given the value 100. The solid lines in Fig. 12 show the distribution of percentages of the dose planned for the center of the target. In this case, the dose distribution has not been corrected for air cavities that might be in the path of the beam but modern treatment planning methods, carried out by computers, would include such considerations.

The dose at the center of the tumor is $\sim 77\%$ of the maximum dose, and a single beam like this would not be deemed suitable. The planning process would be carried further by the addition of at least one more beam from another direction, so that the two would cross at the tumor and produce the maximum dose there. Such a treatment plan might even call for four or even more beams, all of which would be arranged to cross at the target.

Complete isodose distributions drawn for individually designed treatments for individual patients are part of the normal procedures of treatment planning. Dose calculation functions that have been discussed in this article have been incorporated into computer programs and enhanced into procedures that allow calculation of dose distributions for complicated treatment conditions. These calculation procedures have been refined to the extent that the 3D shape of the patient and tissue inhomogeneities can be accounted for. The development of these calculation methods has a lengthy history. Suffice it to say that current methods of calculation use Monte Carlo procedures and are quite precise.

NOTABLE FIRST CLINICAL APPLICATIONS

The use of large irregularly shaped radiation beams was introduced for use with cobalt units in the late 1950s. The task was irradiation of chains of lymph nodes for treatment of Hodgkin's disease. This was so successful that a diagnosis of this disease went from a virtual "death sentence" to one that was highly curable. These "mantle" fields, frequently shaped from low melting point lead alloys for individual patients, are still in use. One of the earliest developments of a computer program for the calculation of the dose distribution was introduced with these treatments in mind (22). This program too, is still in use.

A precursor to today's intensity modulation radiation therapy was instituted in the 1960s in Japan by Takahashi who described the use of multileaf collimators and dynamic treatment delivery with a cobalt unit in 1963 (23).

A group under A. Green at the Royal Northern Hospital in London, England pioneered conformal radiation therapy by developing cobalt machines in which the patient was automatically positioned during rotational therapy by moving the treatment couch and machine gantry by electromechanical systems. It was given the name "The Tracking Cobalt Project" because it attempted to make the dose distribution conform to the spread of the disease. With a similar intent Proimos in Patras, Greece and later Rawlinson and Cunningham in Toronto (24), described the use of synchronous shielding in a Co-60 beam to make the radiation beam conform to the target while avoiding critical normal tissues.

SUMMARY AND CONCLUSIONS

It is still likely, even now, that more cancer patients have been treated by radiation from cobalt units than by any other kind of radiation. The number is estimated to be > 30 million (25). The cobalt unit was the backbone of radiation therapy for over four decades. The cobalt unit is mechanically simple and its output is totally predictable and reliable. Sources with sufficient strength to enable practical, short treatment times can easily be produced. Because of the source decay, sources must be renewed at intervals of 5 years or so, but this procedure is quite straightforward and its expense is more than offset by the low maintenance cost of the machine.

The beam characteristics are well known and relatively easy to measure. It is also easy to make special filters and beam modifiers for individual treatment needs. The energy is high enough to provide skin sparing. The most important single parameter in choosing a radiation energy for therapy is depth dose and the depth dose of cobalt radiation is quite satisfactory for treating tumors that are within 10 cm or so of the surface. This includes head and neck tumors and all but deep-seated lesions in very large patients. With respect to this quantity ^{60}Co is in the middle ground. It remains the unit of choice as a first unit in a developing department and is a must as part of the equipment for any large radiotherapy department. Cobalt units are still being manufactured and sold at about half the rate that obtained at the peak of their use. Modern cobalt units include many of the technological innovations, such as computer control, that are part of the more modern treatment machines. An excellent chapter on Co-60 and its role in modern times has been written by Glenn Glasgow (26). This is recommended to the interested reader.

BIBLIOGRAPHY

1. Sampson M, Ridenouri LN, Bleakney W. A long lived radiocobalt produced by irradiating cobalt with neutrons. Phys Rev 1936;50:382.
2. Livingood JJ, Seaborg GT. Radio-active isotopes of Cobalt. Phys Rev 1941;60:913.
3. Mayneord WV, Cipriani AJ. The absorption of gamma-rays from ^{60}Co. Can J Res Sec A: Phys Sci 1947;25:303.
4. Johns HE, Bates LM, Watson TE. 1000 curie cobalt units for radiation therapy. The Saskatchewan cobalt-60 unit. Br J Radiol, 1952;25:296.
5. Grimmett LG, Kerman HD, Brucer M, Fletcher GH, Richardson JE. Design and construction of a multicurie cobalt teletherapy unit. A preliminary report. Radiology (Easton Pa) 1952;59:19.
6. Robinson RF. The race for Megavoltage. Acta Oncol 1995; 34:1055.

7. Johns HE, MacKay JA. A collimating device for ^{60}CO teletherapy units. J Fac Radiol, London 1953-1954;5:239.
8. Attix FH. Introduction to Radiological Physics and Radiation Dosimetry. New York: John Wiley and Sons Inc.; 1986.
9. Greening JR. Fundamentals of Radiation Dosimetry. Medical Physics Handbook 6. Bristol, England: Adam Hilger; 1981.
10. Johns HE, Cunningham JR. The Physics of Radiology. 4th ed. Springfield, (IL): Charles C. Thomas; 1983.
11. ICRU Report 33. Radiation Quantities and Units. Bethesda, (MD): International Commission on Radiation Units and Measurements; 1980.
12. Bentel GC. Radiation Therapy Planning. 2nd ed. New York: McGraw-Hill; 1996.
13. Khan FH. The Physics of Radiation Therapy. 3rd ed. Philadelphia: Lippincott Williams and Wilkins; 2003.
14. Johns HE, Cunningham JR. A precision cobalt 60 unit for fixed field and rotation therapy. Am J Roentgenol 1959;81:4.
15. Cunningham JR, Ash CL, Johns HE. A double headed cobalt 60 teletherapy unit. Am J Roentgenol 1964;92:202.
16. Leung PM, Rider WD, Webb HP, Aget H, Johns HE. Cobalt-60 therapy unit for large field irradiation. Int J Radiat Oncol Biol Phys 1981;7:705.
17. Rogers DWO, Bielajew AF, Ewart GM. Co beam contamination from the source capsule (Abstr.). Med Phys 1984;11:401.
18. American Association of Physicists in Medicine (AAPM), Task Group 51, A protocol for the determination of absorbed dose from high energy photon and electron beams. Med Phys 1983;120:741.
19. A Code of Practice for Absorbed Dose Determination in Photon and Electron Beams. Vienna: International Atomic Energy Agency (IAEA); 1987.
20. Cunningham JR, Woo M, Rogers DWO. The dependence of mass energy absorption coefficient ratios on beam size and depth in a phantom. Med Phys 1986;13:496.
21. Karzmark CJ, Deubert A, Loevinger R. Tissue-phantom ratios-an aid to treatment planning. Br J Radiol 1965;38:158.
22. Cunningham JR, Shrivastava PN, Wilkinson JM. Program IRREG–Calculation of dose from irregularly shaped radiation beams. Comp Prog Biomed 1972;2:192.
23. Takahashi S. Conformation radiotherapy-rotation techniques as applied to radiography and radiotherapy of cancer. Acta Radiol 1965;242 (Suppl): 1.
24. Rawlinson JA, Cunningham JR. An Examination of Synchronous Shielding in 60-Co Rotation Dose Distributions. Radiology. 1972;102:667.
25. Battista JJ. Cobalt-60 Radiation Therapy: Fifty Years Review and More. London: Ontario; October 27th 2001.
26. Glasgow GP. Cobalt-60 Teletherapy. Chapt. 10. In: Van Dyk J, editor. The Modern Technology of Radiation Oncology. Madison (WI): Medical Physics Publishing; 1999.

See also PHANTOM MATERIALS IN RADIOLOGY; RADIATION DOSIMETRY FOR ONCOLOGY; RADIOTHERAPY TREATMENT PLANNING, OPTIMIZATION OF; X-RAY THERAPY EQUIPMENT, LOW AND MEDIUM ENERGY.

COCHLEAR PROSTHESES

FRANCIS A. SPELMAN
University of Washington
Seattle, Washington

INTRODUCTION

Cochlear prostheses (also called *cochlear implants*) bypass acoustic processing of sound by the cochlea and convert acoustic signals into electrical currents. These currents are delivered via intracochlear electrodes, which directly stimulate the auditory nerve fibers that connect the cochlea to the central nervous system. Cochlear prostheses convert auditory signals into minute electrical currents that stimulate auditory nerve cells via electrodes placed near viable nerve cells. Cochlear implants differ profoundly from acoustic hearing aids. They stimulate the cells of the auditory nerve directly, bypassing the hair cells of the organ of Corti. Acoustic aids increase the mechanical signals that are delivered to the hair cells, aiding their depolarization and the delivery of signals to the auditory nerve. Since the introduction of commercial implants nearly 30 years ago, cochlear prostheses have become one of bioengineering's prominent success stories: $>60{,}000$ people use cochlear implants worldwide. The devices provide patients with a means to overcome deafness. Their success is such that, since the time that the article was written about cochlear implants in the first edition of this Encyclopedia, the cochlear implant has been recommended for people who are severely deaf, rather than reserving the implant for the profoundly deaf (1). Cochlear prostheses provide the standard treatment for people who are profoundly deaf.

In addition to cochlear prostheses, some prostheses are implanted surgically in the central nervous system as auditory brainstem implants, in the cochlear nucleus, or as mid-brain implants in the inferior colliculus.

This article is an update of the article *Cochlear Prosthesis* in the 1st ed. of this Encyclopedia (2).

CANDIDATES FOR IMPLANTS

Hearing loss can occur in either one or both ears. The common classifications of hearing impairment are mild (21–40 dB), moderate–severe (61–70 dB), severe (71–81 dB), and profound (90+ dB) (3). Here dB ($20\log_{10}[P_2/P_1]$) is the sound pressure, P_2, referenced to normal hearing thresholds, P_1, usually measured at 500, 1000, and 2000 Hz. It refers to the increase of sound pressure that must be used for a subject to reach hearing threshold. Blanchfield et al. number the severely to profoundly deaf between 464,000 and 738,000, all of whom are candidates for cochlear implants (4).

Some prostheses are implanted surgically in the cochlear nucleus. The numbers of patients receiving those devices are much smaller than those who receive implants in the cochlea, ~ 300 people (5). The candidates come primarily from subjects with neurofibromatosis (6–8). The morbidity and mortality with central implants is small, and the success is reasonable. The subjects do not do as well as those with the cochlear prostheses described below, but are able to decode speech (6). The emerging field of central auditory implants will not be covered further in this article because the numbers of users are relatively small at this time.

THE AUDITORY SYSTEM

A complete description of the functioning of the peripheral auditory system is beyond the scope of this article. However, to understand the operation of the prosthesis, one



Figure 1. A sketch of the peripheral auditory system, external ear, ear canal, eardrum, middle ear, and inner ear (2).

must know a little about the anatomy and physiology of the peripheral auditory system, which consists of the external ear, the middle ear, and the inner ear (9). Figure 1 shows the auditory system in a simplified form. Sound impinges on the external ear and is guided by way of the ear canal to the tympanic membrane (eardrum). The tympanic membrane vibrates with a relatively large displacement and low pressure. The ossicles (bones) of the middle ear act as an acoustic impedance transformer to change the vibration to relatively small displacement and high pressure at the oval window. The cochlea, the spiral-shaped organ of the inner ear, contains the cells that convert mechanical motion into the electrochemical signals that are recognized by the nervous system (9,10). Several sites on the World Wide Web provide animations of the operations of the components of the auditory system. One such site may be found at, http://www.neurophys.wisc.edu/animations. Other animations and data are maintained in a "virtual library" that has been assembled by the Association for Research in Otolaryngology at its web site http://www.aro.org. Geisler refers to both sites in his work, From Sound to Synapse (9).

THE AUDITORY PERIPHERY

The peripheral auditory system (Fig. 1) consists of the external ear, the middle ear and the inner ear (9). The external ear guides acoustic waves through the external auditory meatus to the tympanic membrane, which vibrates in response to air moving in the ear canal. The middle ear acts as a mechanical transformer, a system of levers and pistons, to match the air-driven tympanic membrane to the fluid-filled inner ear, the cochlea (9).

Figure 2 shows a cutaway view of the inner ear and its three chambers or scalae, that is, the scala vestibuli and the scala tympani, which communicate via the helicotrema, an opening at the apical end of the cochlea, and the scala media, which is isolated from the other two scalae by membranes (9,10). The stapes (stirrup) of the middle ear drives the fluids of the scala vestibuli and in doing so deflects the membranes of the scala media (10). One of these membranes, the basilar membrane, bears the hair cells, the motion-sensitive cells that excite the VIII cranial nerve (9,10).

The inner ear acts as a transduction and signal processing mechanism. Auditory information is decomposed into its fundamental frequencies by the frequency-sensitive basilar membrane. Amplitude, phase, and frequency information is carried by the cells of the auditory (VIII cranial) nerve. Simplistically, sounds are decomposed into their spectral peaks (11).



Figure 2. Cutaway view of the cochlea of the inner ear, showing the three chambers or scalae of the ear, and an artist's conception of a cochlear electrode array inserted into the scala tympani of the cochlea (2).

Each of the 30,000-odd fibers of the auditory nerve has an auditory threshold function that is sensitive to a small range of frequencies. All threshold minima lie within 10–15 dB; fibers have dynamic ranges that can be as much as 30–40 dB at their characteristic frequencies (9,12). The rate at which a single peripheral fiber fires is a monotonically increasing function of the acoustic stimulus at its characteristic frequency. The dynamic range of a fiber depends on a number of factors, including its threshold and its spontaneous firing rate, the latter of which can be as large as 100 spikes/s (9).

The responses of auditory nerve fibers are nonlinear. At low intensities, the responses of single nerve fibers mimic the frequency spectra of the complex sounds that stimulate the ears of experimental animals (13). At higher intensities, the spectra produced by the responding fibers are dominated by the low frequency component of the speech sound (its first formant) and the distortion products of that frequency (13). Recent evidence provides strong support for nonlinear system to preserve speech sounds at low and high intensity, in quiet and in noise (9).

In summary, the auditory system has a number of features that enable it to decode sound: (1) specific cells are excited at threshold by specific acoustic frequencies; (2) increasing intensity of an acoustic signal causes an increasing spread of influence from cells for which it is the best frequency, to cells that respond at threshold to other frequencies; (3) the intensity of a particular signal appears to be coded both by the rate at which cells fire and by the numbers of cells excited by a particular stimulus; (4) nonlinear properties of the auditory system cause the suppression of one cell's response to one frequency by stimulation with another frequency, by saturation of rate and by the production of distortion products in the system's response to high intensity excitation; and (5) frequency information contained in complex stimuli is preserved in the temporal responses of auditory neurons.

HISTORY OF COCHLEAR PROSTHESES

The first report of electrical stimulation of the ear is attributed to Volta, in a paper read to the British Royal Society in July of 1800 (14,15). He reported that his approach, using perhaps 50 V excitation, was uncomfortable, sounding like the boiling of fluid. He did not repeat the study. More recently, Djuorno and Eyries (16) reported the first attempt to excite the auditory nerve directly with electricity. Later, Doyle et al. reported results with electrical stimulation of the auditory nerve (17). Simmons performed an experiment a year later in which he went further, stimulating the VIII auditory nerve and the inferior colliculus of a human patient, showing that it was possible for the subject to distinguish frequencies well below 900 Hz, but not >1000 Hz (18). Simmons demonstrated that both peripheral and central stimulation of the auditory system was possible. In 1964, the House Ear Institute began an extensive series of surgeries to implant cochlear prostheses, reporting on their long-term effects in 1973 (19). The first experiments on multichannel cochlear prostheses were initiated by Simmons et al. in 1979 (20). Their results were promising, and now multichannel implants are the standard of the industry.

Since the first experiments, cochlear prostheses have been built and applied worldwide, receiving approval from governmental agencies and remarkable success in $>60{,}000$ patients. Indeed, cochlear prostheses are considered the standard treatment for profoundly and severely deaf adults. Three commercial firms, Cochlear Corp. (Sydney, Australia), Advanced Bionics Corporation (Valencia, CA; recently purchased by Boston Scientific Corporation), and Med-El Corporation (Innsbruck, Austria) produce cochlear implants successfully. The early cochlear implants were single-channel devices (21), but all of the cochlear prostheses that are implanted today are multichannel devices (22).

THEORY OF OPERATION

The cochlear implant operates on the premise that, if the hair cells of the auditory system are damaged, they can be bypassed and that neurons can be driven directly with very small electrical signals. Figure 3 shows a greatly simplified block diagram of a cochlear implant. Acoustic signals are transduced by a microphone, whose small electric signal is amplified. An external processor decomposes the electrical analogue of the acoustic signal. In the processors that are produced today, processing is digital, with the processor analyzing the instantaneous frequency content of the acoustic signal in the frequency domain. The signals are sent across the skin via a radio frequency link (in the VHF band) that transmits both information and power from the outside of the subject to the inside. These transcutaneous signals are shown with bidirectional paths. Data can be transferred in both directions, providing information to therapists about the condition of the electrodes and the state of the auditory system of the patient. The data flowing to and from the external signal processor are serial bit streams.

The transcutaneous bit streams can have rapid rates: consider that the sampling rate of the audio signal can


Transcutaneous Signals
Acoustic Signal
Microphone and Amplifier
External Digital Signal Processor
Internal Signal Processor/ Decoder
Controlled Current Sources
Currents to Electrodes

Figure 3. Simplified block diagram of a cochlear implant. Four blocks are shown, a microphone and amplifier, external digital signal processor; internal signal processor/decoder; and, controlled current sources (see text; after Ref. 23).

exceed 20,000 samples/s, and that updates of information delivered to the internal processor may present data at 5000 or more data points per second. The data must include the electrode(s) that are being driven, the amplitude and the pulse width of the current pulse that is applied. Rates can exceed 80,000 pulses/s (25). The internal signal processor–decoder decodes the incoming bit stream. It distributes drive signals to the current sources, selecting specific sources to drive, and setting the amplitude and duration of the control signals.

The current sources drive the electrodes of the cochlear implant's electrode array. Those electrodes are placed in the scala tympani of the cochlea, and direct the current drive signals to the neurons of the auditory nerve, the VIII cranial nerve. The electrodes of the array are placed in proximity to the neurons, in order to reduce the threshold currents necessary to excite the cells, and to reduce current spread within the inner ear (26).

Figure 4 shows one of the cochlear electrode arrays that is produced commercially by Cochlear Corporation (Sydney, Australia). There are 24 contacts in all, two of which are placed outside of the cochlea, leaving 22 contacts that may be driven to excite neurons of the auditory nerve. The contacts may be driven as monopoles (single internal current sources, referenced to an return contact external to the inner ear), as dipoles (pairs of internal current sources) or as combinations of three or more contacts. The contacts are placed along the inside of the spiraling, silicone carrier. The carrier is shaped to fit snugly against the modiolus of the scala tympani. The contacts can be driven singly or in combinations, for example, as dipoles or as multiple sources.

The three manufacturers of cochlear implants use scala tympani arrays that are similar to the array shown in Fig. 4. However, other approaches to stimulate the auditory nerve cells are possible. Normann and his colleagues have tested monolithic electrode arrays that are designed to penetrate the auditory nerve directly (27). Like others before him, Normann realized that bringing electrode contacts near the neurons will reduce thresholds and limit the spread of excitation (28–30). The concept has not been tested chronically in human subjects.



Figure 4. Picture of the Nucleus 24 Contour electrode array, showing 24 contacts and a shape that is designed to appose the modiolar wall of the scala tympani (24).

The concept of an *information channel* is critical to the understanding of the cochlear prosthesis. A channel may drive current to one electrode, but it often distributes drive to two or more electrodes. Field shaping and steering techniques suggest the use of multiple electrodes for each channel (31–33). Indeed, demonstrations by Bierer and Middlebrooks (33,34) showed that the quadrupolar configurations (called tripolar in the Bierer paper) produce more focused stimuli than either monopolar or bipolar excitations. Recent experiments in cats have upheld the finding, showing that multipolar stimulation allows two triads of electrodes to be driven simultaneously without significant crosstalk (35). It is clear that a channel may involve several electrodes driven simultaneously, and cannot be defined as the information conveyed by a single contact on an electrode array. While one contact may be driven at a time, bipolar stimulus configurations are common and multipolar configurations may emerge soon.

Signal processing techniques have changed dramatically since the time that the first version of this article was written. The number of available electrodes has more than doubled. In common to most processors is a bank of filters, analogue or, commonly, digital. The filtered signals are decomposed into time-varying envelope signals that are compressed and delivered as either amplitude modulated pulses or width modulated pulses. The pulses are delivered with a variety of strategies.

Continuous interleaved stimulation (CIS) is a technique by which a single electrode is stimulated at a time in order to eliminate field interactions between and among channels when electrodes are driven as monopoles (31). The electrodes receive signals from specific filters. The signals are converted to symmetrical, rectangular, biphasic current pulses whose amplitudes may be proportional to the envelope of the filter signal and whose width is invariant. Conversely, amplitude can be held constant and width can be varied. More recently, Advanced Bionics Corporation has used a processor whose repetition rate can be 5800 pulses/s per channel, to develop rapid updates of channels in the CIS paradigm. In a recent processor, HiRes, stimulation rates can be as much as 5800 pps when two widely spaced channels are driven simultaneously, and drops by one-half when the two channels are driven sequentially (36).

The *n*-of-*m* strategy employs a larger number of filters, *m*, than there are electrodes, *n* (37). Depending on which filters contain the maximum acoustic energy, pulses are delivered to appropriate electrodes. The cochlea is organized tonotopically along the basilar membrane. Hence, each electrode's field excites a specific group of characteristic frequencies in perceptual space. Those filters that exhibit the maximum energy determine the electrodes that will be driven by a given temporal sample of the acoustic signal. Biphasic, symmetrical, rectangular pulses are delivered to specific electrodes, *n*, at particular sample times. Because of the field interactions between electrodes no more than two channels are driven during a given sample.

Other techniques include simultaneous analog stimulation (SAS), in which widely separated electrodes are driven simultaneously to increase the rate at which information is transferred to the auditory nerve. The field interactions are reduced by driving electrodes that are separated by several millimeters in the inner ear (38). Simultaneous analog stimulation is a special case of the "filters with compression" technique described by Eddington > 20 years ago (39). Today, fewer electrodes are driven simultaneously, but they are updated more rapidly (40). Thus, SAS is a variation of both Eddington's filters and CIS. Eddington described a means by which electrodes were assigned the compressed analog outputs of filters. Those analogue signals were delivered continuously to the electrodes.

A potentially exciting new technique of stimulation takes advantage of the stochastic behavior of auditory neurons. If a stimulator provides high rate conditioning pulses to its electrode array, it is possible to simulate the stochastic firing frequencies of the cells of the auditory nerve (41). This approach has been tested in small numbers of European patients with what appears to be dramatic success, particularly with auditory signals in noise (Rubinstein, personal communication; see below).

Despite the richness of the processing techniques that have been employed, there are still hurdles to be overcome. The number of true, simultaneous channels is too small. It should be at least 16; there is often a mismatch between the frequency assigned to an electrode and its position in the cochlea; the signals that are delivered to the neurons do not contain fine temporal information; the phase information between channels is not preserved; and, there may be neurons missing, causing some electrodes and critical frequencies to be missing as well (42). Future implants may be able to address some of the concerns that are raised here.

EVALUATION OF COCHLEAR PROSTHESES

When human subjects first used cochlear implants, the numbers of subjects were small and tests were not standardized. As the devices improved, standard tests were developed and used across the centers at which implantation was being done (15). The tests include materials that are open and closed set. The test subjects do not review open set materials prior to the test, whereas closed set materials are reviewed before testing takes place. Subjects participate in word tests and sentence tests. In the former, single words are presented while in the latter sentences are presented and the subjects can deduce parts of the sentence logically.

In addition to providing word and sentence tests, consonant (C) and vowel (V) discrimination tests are included in the test batteries. In these tests, nonsense utterances, CVCs or VCVs, are presented and the subject must identify the appropriate vowel or consonant.

Open word tests are difficult while sentence tests are relatively easy. For example, implant users have steadily increased their comprehension of sentences from much $< 10\%$ with early single channel devices to 80% or above with today's multichannel devices (22). Many implant users are able to converse on the telephone, a significant result, since they cannot rely on the cues presented by lip reading in that situation. Still, word comprehension from open-word sets remains relatively low, between 40 and 50%, and most users dislike listening to music (43). Clearly, the context that comes from sentence structure and content is important to comprehension, and the complex spectral content of music makes it difficult.

Cochlear implants are a great bioengineering success. Wilson used an aviation metaphor recently, likening the cochlear implant to a DC-3, a reliable workhorse of an aircraft without the sophistication of a twenty-first century transport airplane (43). The implant has advanced from the single-channel stage of the Wright flyer, but has yet to reach its pinnacle.

THE BENEFITS AND RISKS OF IMPLANTATION

Cochlear implants provide clear benefits to their users. For example, hearing-impaired children learn language more rapidly with cochlear implants than they do with hearing aids (44). Adults do well and benefit from their implants, particularly when they are dealing with speech in quiet. However, for patients to achieve the greatest benefits from the device, their prostheses should be adjusted individually for the minimum and maximum stimulation levels for each electrodes in the array, the stimulation rate, and the speech processing strategy (45). Skinner suggests that for best results the parameters should be adjusted for the maximum dynamic range: from quiet sounds to maximum sounds that are "...not too loud..." (45).

A recent survey of patients from Toronto, Ontario, Canada, was taken of 42 early deafened adult users. Of the 30 who responded, $> 96\%$ said that they were satisfied with the implant, $> 93\%$ would undergo the procedure again, and 90% said that they would recommend the implant to another person in the same situation (46). The subjects were encouraged by family and peer support and bolstered by having a positive attitude before, during and after the process of implantation and therapy.

There are risks associated with the surgery, but they are quite small. Cunningham et al. (47) reviewed the cases of 462 adults and 271 children in a private tertiary care center for the years 1993–2002. They found that the overall incidence of infection postoperatively was 4.1%. Major infectious complications occurred in 3.0% of the cases; those complications required surgical intervention (47). Bacterial meningitis was found in 26 of 4264 children receiving cochlear implants in the United States (48). That was found to be associated with a particular electrode array that used a positioner to place it near the modiolar wall. The array was subsequently withdrawn from the market (http://www.fda.gov/cdrh/safety/cochlear.html), and there have been no other reports of the occurrence of meningitis. Cunningham et al. (47) recommended that children undergo vaccination before implantation to prevent bacterial infections.

THE COST OF IMPLANTATION

A recent article cited the cost of cochlear implant treatment as $> \$40,000.00$, of which \$20,000.00 is the approximate cost of the device itself (49). Despite the high cost of the device and the surgery, the cochlear prosthesis is beneficial when compared with the long-term costs of other medical device procedures (50,51). Garber et al. (49) asked why the cochlear implant has limited access despite its success and the likely market, and surveyed 25 of 231 practices and 96 of 213 hospitals to try to learn what caused the limits of availability. They concluded that both the practitioners and hospitals lose money when they provide cochlear implants, limiting access to the devices. The cochlear implant is approved in the United States for Medicare, Medicaid, and insurance reimbursement.

THE FUTURE OF COCHLEAR PROSTHESES

In a recent review, Wilson et al. (52) suggested that the future held combined acoustic and electrical stimulation, bilateral implants, new electrode designs and closer mimicking of processing in the normal cochlea. This article discusses electrode designs, combined acoustic, and bilateral stimulation and the closer mimicking of processing in the normal cochlea.

HIGH DENSITY ELECTRODE ARRAYS

Electrode arrays have remained much the same for more than a decade. They are built manually on substrates of silicone, using Pt–Ir (90–10%) alloyed electrodes. The group of Dr. Kensall Wise at the University of Michigan has proposed the use of high density arrays that are made on silicon substrates using IrO contacts (54,55). If such arrays can be built for human use, they will reduce the cost of building electrode arrays while increasing the specificity of excitation of cells. Another approach to the problem is to build electrode arrays on multilayered polymer substrates (Fig. 5). Sample arrays have been used to demonstrate the use of high density arrays in animal studies, with clear independence of channels driven in the first turn of the scala tympani (Snyder, Corbett, Bonham, Rebscher, and Johnson, personal communication).



Figure 5. Photograph of a 12-site sample array made by Advanced Cochlear Systems (Snoqualmie, WA) to insert into the scala tympani of a cat (53). The width of each gold electrode contact is 100 μm

The goal driving the development of these high density arrays is to increase the specificity of stimulation and to allow several independent groups of cells to be driven simultaneously (32,56). The work of Jolly (32) and Bierer and Middlebrooks (33,57) suggested that this might be the case. More recent work has confirmed the earlier results and extended them (35,34). The benefit of focused multipolar stimulation and of simultaneous excitation of several independent groups of neurons is not without cost. More driven electrodes require greater current consumption. Current consumption is increased with focusing, since focused stimuli require more applied current to reach the same potential fields in conducting media (58). It is likely that high density electrode arrays will be a part of cochlear implants, but there are engineering challenges to be met before it will happen.

COMBINED ACOUSTIC AND ELECTRICAL STIMULATION

Preliminary studies of combined electrical and acoustic stimulation have been done successfully in both Europe and the United States (52,59,60). The subjects come from the substantial population of people who preserve some hearing for frequencies <1 kHz, but who are severely impaired for frequencies >1 kHz. Two questions arise immediately. (1) Can low frequency hearing be preserved after an electrode array has been placed in the high frequency regions of the inner ear? (2) Can acoustic and electrical stimuli be applied simultaneously and successfully?

The likelihood of success is great, particularly if patients have short electrode arrays implanted, avoiding damage to the delicate structures of the inner ear. That concern is critical in the case of the hybrid stimulation scheme, since low frequency information will come via the normal, albeit amplified, acoustic pathway. Two manufacturers, Cochlear Corporation (Sydney, Australia) (60) and Med-El (Innsbruck, Austria) (59) have produced electrode arrays for the purpose and have tested them in clinical settings. The Med-El array has an implanted length of 31.5 mm (59), while the Cochlear Corporation array's length is 10 mm in its latest version (60). Both have had extensive laboratory tests and have been used clinically. Clinical tests confirm the initial hypothosis: when patients suffer primarily from high frequency hearing loss, the use of hybrid stimulation is likely to provide great benefit, and may well increase the numbers of people who can have near-normal hearing (52). Electrical and acoustic stimuli can be combined by implanting one ear with a cochlear prosthesis and using a hearing aid in the contralateral ear. This approach has had some reports of success and is currently under study in research laboratories.

NORMAL PROCESSING: CONDITIONING PULSES

In the 1990s, investigators began to consider the issue of the stochastic behavior of neurons (61) and that high rate conditioning stimuli might improve the behavior of cells in the auditory nerve, decreasing thresholds and increasing dynamic ranges (52). They proposed to use electric currents with 5 kHz pulse trains of brief pulses, biphasic rectangular pulses of 40 μs duration for each phase (62). Rubinstein and various colleagues pursued the idea further, suggesting that high rate stimuli might mimic stochastic resonance in neurons and improve signal processing in cochlear implants (60). Computer models validated the concept, as did initial tests in a human subject (63). An extensive neurophysiological study confirmed the idea in experimental animals (62).

Rubinstein and Frijns did preliminary tests for the use of high rate, low amplitude conditioning pulses in the processors of some human subjects, reporting success in the majority of their subjects (Rubinstein, personal communication). The concept is certainly a logical and promising idea; whether it will provide a dramatic improvement to cochlear implants is something that will be learned from further experiments in human subjects.

NORMAL PROCESSING: FINE STRUCTURE

Present cochlear implants impose low pass filter functions on the acoustic signals that they decode. Signals are filtered, and their envelopes detected, with a concomitant loss of fine structure. Fine structure is defined as information spanning frequencies from 500 to 10 kHz (22). Speech can be well understood in quiet environments. The users of present-day cochlear implants rarely enjoy music. Some of that may be improved by increasing the fine structure of the signals delivered to the ear via the cochlear implant. The Hilbert transform provides a potential approach to providing both amplitude information and fine structure (22,64,65). Smith et al. (63) determined that the envelope of the transform was important for speech perception, while the fine structure determines localization and pitch.

Processors that employ Hilbert transforms have yet to be produced in quantity. Although prototypes exist, they have not made their way into cochlear implants (64). The development of implants that can reproduce the fine structure of signals is likely to improve cochlear prostheses.

BILATERAL IMPLANTS

Binaural hearing is critical to sound localization and the extraction of auditory signals in noise. In addition, binaural implants may allow listeners to employ the “head shadow” benefit to hear a specific voice in the face of sounds produced by a competing crowd of people (52). Wilson notes promising results from several centers at which patients have received bilateral implants (52). He reports improvements in speech comprehension, as well as the results of several careful psychophysical studies that were focused on the balance between the prostheses that were implanted. Wilson and his colleagues concluded that bilateral implants are likely to provide clear benefits. While users are tolerant of some timing and amplitude mismatches, the careful matching of stimulus sites, that is, electrode locations, may be necessary for success (52). Another issue to consider is the cost of bilateral implantation. Bilateral implantation incurs the cost of two cochlear prostheses and two surgeries. Does the benefit accrued by the patient double? That remains to be seen at the time of this writing.

CONCLUSION

Cochlear prostheses are a clear bioengineering success story. More than 60,000 patients have benefited worldwide. Many users can talk on the telephone and communicate effectively without visual aids, like lipreading. The design of the cochlear prosthesis is likely to improve, even as the number of implantees grows rapidly, indeed, at double-digit rates. With that rich background and rapid growth, there are opportunities for bioengineers to produce even better cochlear prostheses.

ACKNOWLEDGMENTS

This work was sponsored by grants R43DC000531 and R43DC04614 of the National Institutes of Health.

BIBLIOGRAPHY

1. NIH NIH Consensus Statement: cochlear Implants in Adults and Children. Bethesda, MD, National Institutes of Health; 1995.
2. Webster JG. Encyclopedia of medical devices and instrumentation. New York: John Wiley & Sons; 1988.
3. Blanchfield BB, Feldman JJ, et al. The severely to profoundly hearing impaired population in the United States: Prevalence and demographics. Policy Anal Brief H Ser 1999; 1 (October): 1–4.
4. Blanchfield BB, Feldman JJ, et al. The severely to profoundly hearing-impaired population in the United States: prevalence estimates and demographics. J Am Acad Audiol 2001;12(4): 183–189.
5. Kuchta J. Neuroprosthetic hearing with auditory brainstem implants. Biomed Tech (Berlin) 2004;49(4):83–87.
6. Otto SR, Brackmann DE, et al. Multichannel auditory brainstem implant: update on performance in 61 patients. J Neurosurg 2002;96(6):1063–1071.
7. Schwartz MS, Otto SR, et al. Use of a multichannel auditory brainstem implant for neurofibromatosis type 2. Stereotact Funct Neurosurg 2003;81(1–4):110–114.
8. Kanowitz SJ, Shapiro WH, et al. Auditory brainstem implantation in patients with neurofibromatosis type 2. Laryngoscope 2004;114(12):2135–2146.
9. Geisler CD. From Sound to Synapse: Physiology of the Mammalian Ear. New York: Oxford University Press; 1998.
10. Dallos P, Popper AN, Fay RR, editors. The Cochlea. Springer Handbook of Auditory Research. New York: Springer; 1996.
11. Sachs MB, Young ED. Encoding of steady-state vowels in the auditory nerve: representation in terms of discharge rate. J Acoust Soc Am 1979;667(2):470–479.
12. Liberman MC. Auditory-nerve response from cats raised in a low-noise chamber. J Acoust Soc Am 1978;63(2):442–455.
13. Sachs MB, Young ED. Effects of nonlinearities on speech encoding in the auditory nerve. J Acoust Soc Am 1980; 68:858.
14. Volta A. On the electricity excited by mere contact of conducting substances of different kinds. R Soc Philos Trans 1800;90: 403–431.

15. Clark GM. Cochlear Implants: Fundamentals and Applications. New York: Springer-Verlag; 2003.
16. Djourno A, Eyries C. Prothese Autitive par excitation electrique a distance du nerf sensoriel a l'aide d'un bobinage inclus a demcure. Presse Med 1957;35:14–17.
17. Doyle JB, Doyle HD, et al. Electrical stimulation in eighth nerve deafness. Bull LosAngeles Neurol Soc 1963;18:148.
18. Simmons FB, Mongson CJ, et al. Electrical stimulation of the acoustic nerve and inferior colliculus in man. Arch Otolaryngol Head Neck Surg 1964;79:559.
19. House WF, Urban J. Long term results of electrode implantation and electronic stimulation of the cochlea in man. Ann Otolaryngol Rhinol Laryngol 1973;82:504.
20. Simmons FB, Mathews RG, et al. A functioning multichannel auditory nerve stimulator. A preliminary report on two human volunteers. Acta Otolaryngol 1979;87(3–4):170–175.
21. House WF, Berliner KI. Cochlear Implants: from idea to clinical practice. In: Cooper H, editors. Volume 1, Cochlear Implants: A Practical Guide. San Diego, CA: Singular Publishing Group, Inc.; 1991. p 9–33.
22. Zeng F-G. Trends in cochlear implants. Trends Amplif 2004;8(1):1–34.
23. Spelman F. Cochlear Prostheses. In: Ratner BD, Hoffman AS, Schoen FJ, Lemons JE, editors. Volume 1, Biomaterial Science: An Introduction to Materials in Medicine. Amsterdam: The Netherlands Elsevier Academic Press; 2004. p 658–669.
24. Anonymous. Nucleus 24 Contour, Cochlear Americas. 2004.
25. Kessler DK. The CLARION Multi-Strategy Cochlear Implant. Ann Otol Rhinol Laryngol Suppl 1999; 177(Apr.):8-16.
26. Jolly CN, Gstöttner W, et al. Principles and outcome in perimodiolar positioning. Ann Otolaryngol Rhinol Laryngol Suppl 2000;185(12):20–23.
27. Hillman T, Badi AN, et al. Cochlear nerve stimulation with a 3-dimensional penetrating electrode array. Otolaryngol Neurotol 2003;24(5):764–768.
28. Simmons FB. Electrical Stimulation of the Auditory Nerve in Man. Arch Otolaryngol 1966;84 (July, 1966):24–76.
29. White MW, Merzenich MM, et al. Multichannel cochlear implants: Channel interactions and Processor design. Arch Otolaryngol 1984;110:493–501.
30. Arts HA, Jones DA, et al. Prosthetic stimulation of the auditory system with intraneural electrodes. Ann Otolaryngol Rhinol Laryngol Suppl 2003;191:20–25.
31. Wilson BS, Finley CC, et al. Better speech recognition with cochlear implants. Nature (London) (July 18, 1991); 352:236–238.
32. Jolly CN, Spelman FA, et al. Quadrupolar stimulation for cochlear prostheses: Modeling and experimental data. IEEE Trans Biomed Eng 1996;43(8):857–865.
33. Bierer JA, Middlebrooks JC. Cortical responses to cochlear implant stimulation: Channel interactions. J Assoc Res Otolaryngol. 2004;5(1):32–48.
34. Snyder RL, Bierer JA, et al. Topographic spread of inferior colliculus activation in response to acoustic and intracochlear electric stimulation. J Assoc Res Otolaryngol 2004;5(3): 305–322.
35. Bonham B, Snyder RL, et al. The neurophysiological effects of simulated auditory prosthesis stimulation: channel interaction, current steering and channel morphing. San Francisco, CA: University of California at San Francisco; 2004.
36. Anonymous. New methodology for fitting cochlear implants. Valencia, CA: Advanced Bionics Corporation. 1–5; 2003.
37. McDermott HJ, McKay CM, et al. A new portable sound processor for the University of Melbourne/Nucleus Limited multielectrode cochlear implant. J Acoust Soc Am 1992;91: 3367–3371.
38. Anonymous. Clarion S-Series. Sylmar, CA, Advanced Bionics, Inc.; 1997.
39. Eddington DK. Speech discrimination in deaf subjects with cochlear implants. J Acoust Soc Am 1980;68:885–891.
40. Anonymous. PULSARci Cochlear Implant, Med-El; 2004.
41. Rubinstein JT, Hong R. Signal coding in cochlear implants: Exploiting stochastic effects of electrical stimulation. Ann Otol Rhinol Laryngol 2003;112(9, Part 2):14–19.
42. Moore BCJ. Coding of sounds in the auditory system and its relevance to signal processing and coding in cochlear implants. Otolaryngol Neurotol 2003;24(2):243–254.
43. Wilson BS. The History of Cochlear Implants. Neural Interfaces Workshop, Hyatt Regency Bethesda Hotel, Bethesda, MD: NIDCD, National Institutes of Health; 2004.
44. Skinner MW. Cochlear implants in children: What direction should future research take? 2001 Conference on Implantable Auditory Prostheses, Pacific Grove CA; 2001.
45. Skinner MW. Optimizing cochlear implant speech performance. Ann Otolaryngol Rhinol Laryngol Suppl 2003;191: 4–13.
46. Chee GH, Goldring JE, et al. Benefits of cochlear implantation in early-deafened adults: the Toronto experience. J Otol 2004;33(1):26–31.
47. Cunningham CD, 3rd, Slattery WH, 3rd, et al. Postoperative infection in cochlear implant patients. Otolaryngol Head Neck Surg 2004;131(1):109–114.
48. Reefhuis J, Honein MA, et al. Risk of bacterial meningitis in children with cochlear implants. N Engl J Med 2003;349(5): 435–445.
49. Garber S, Ridgely MS, et al. Payment under public and private insurance and access to cochlear implants. Arch Otolaryngol Head Neck Surg 2002;128(10):1145–1152.
50. Cheng AK, Niparko JK. Cost-utility of the cochlear implant in adults. Arch Otolaryngol Head Neck Surg 1999;125(11): 1214–1218.
51. Niparko JK, Kirk KI, et al. Cochlear Implants: Principles and Practices. Baltimore MA: Lippincott Williams & Wilkins; 2000.
52. Wilson BS, Lawson DT. Ann Rev Biomed Eng 2003;5:207–249.
53. Corbett SS, III, Johnson T, Rebscher S, Carson M, Ketterl J, Snyder R. unpublished results.
54. Weiland JD, Anderson DJ. Chronic neural stimulation with thin-film, iridium oxide electrodes. IEEE Trans Biomed Eng 2000;47(7):911–918.
55. Weiland JD, Anderson DJ, et al. *In vitro* electrical properties for iridium oxide versus titanium nitride stimulating electrodes. IEEE Trans Biomed Eng 2003;49(12): 1574-1579.
56. Clopton BM, Spelman FA. Technology and the future of cochlear implants. Ann Otolaryngol Rhinol Laryngol Suppl 2003;191:26–32.
57. Bierer JA, Litvak L, et al. Effects of electrode configuration on psychophysical measures of channel interaction in cochlear implant subjects. Soc Neurosci 2003.
58. Spelman FA, Pfingst BE, et al. The effects of electrode configuration on potential fields in the electrically-stimulated cochlea: models and measurements. Ann Otol Rhinol Laryngol 1995;104(Suppl. 166):131–136.
59. Adunka O, Kiefer J, et al. Development and evaluation of an improved cochlear implant electrode design for electric acoustic stimulation. Laryngoscope 2004;114(7):1237–1241.
60. Gantz BJ, Turner C. Combining acoustic and electrical speech processing: Iowa/Nucleus hybrid implant. Acta Otolaryngol 2004;124(4):344–347.
61. Rubinstein JT, Abbas PJ, et al. Stochastic Resonance: Can it be exploited by speech processors? Conference on Implantable Auditory Prostheses, Pacific Grove, CA; 1997.

62. Runge-Samuelson CL, Abbas PJ, et al. Response of the auditory nerve to sinusoidal electrical stimulation: effects of high-rate pulse trains. Hear Res 2004;194(1–2):1–13.
63. Rubinstein JT, Wilson BS, et al. Pseudospontaneous activity: stochastic independence of auditory nerve fibers with electrical stimulation. Hear Res 1999;127(1–2):108–118.
64. Clopton BM, Lineaweaver SKR, et al. Method of processing auditory data. United States Patent and Trademark Office. Advanced Cochlear Systems.
65. Smith ZM, Delgutte B, et al. Chimaeric sounds reveal dichotomies in auditory perception. Nature (London) 2002; 416: 87–90.

See also AUDIOMETRY; COMMUNICATIVE DISORDERS, COMPUTER APPLICATIONS FOR.

CODES AND REGULATIONS: MEDICAL DEVICES

MORRIS WAXLER
PATRICIA J. KAEDING
Godfrey & Kahn S.C.
Madison Wisconsin

INTRODUCTION

The U.S. Food and Drug Administration (FDA or agency) regulates medical devices according to specific definitions, classifications, requirements, codes, and standards. The FDAs authority and framework for medical device regulation are specified in the Federal Food, Drug, and Cosmetic Act of 1938, as amended (FDCA). The FDCA is codified at Title 21, Chapter 9, United States Code (21 USC) (1). For purposes of medical device regulation, several acts of Congress amending the FDCA are especially significant: the Medical Device Amendments of 1976, the Safe Medical Devices Act of 1990, the Food and Drug Administration Modernization Act of 1997, and the Medical Device and User Fee and Modernization Act of 2002. The FDA has promulgated regulations for the efficient enforcement of the FDCA. These regulations, which generally have the force of law, are codified in Title 21 of the Code of Federal Regulations (21 CFR or the regulations) (2). The agency also has issued guidances and guidelines to assist in the regulation of medical devices (3).

Pursuant to the FDCA, the FDA determines the entities subject to regulation (e.g., manufacturers, specifications developers), evaluates whether products and regulated entities are in compliance, and initiates appropriate regulatory and enforcement actions to impose penalties for violations. The FDA's requirements affect each stage of a medical device's lifecycle. Some FDA requirements apply to particular periods of a medical device's lifecycle. Others apply more broadly. Design, technical development, preclinical testing, clinical study, market authorization, market approval, postmarket assessment, modification, obsolescence, redesign, and labeling requirements are part of this regulatory framework for medical devices. The FDA's Center for Devices and Radiological Health (CDRH) is the FDA component with primary responsibility for medical device regulation.

WHAT IS A MEDICAL DEVICE?

The FDCA contains definitions for the various product areas the FDA regulates, including medical devices. Under the FDCA, a "device" must be

- "an instrument, apparatus, implement, machine, contrivance, implant, *in vitro* reagent, or other similar or related article, including any component, part, or accessory"
- which is either "intended for use in the diagnosis of disease or other conditions, or in the cure, mitigation, treatment, or prevention of disease, in man or other animals," or "intended to affect the structure or any function of the body of man or other animals," and
- "which does not achieve its primary intended purposes through chemical action within or on the body of man or other animals and which is not dependent upon being metabolized for the achievement of its primary intended purposes" [21 USC § 321(h)].

To be a medical device, a product must achieve its "primary intended purpose" without chemical or metabolic action within or on the body. This characteristic distinguishes "devices" from "drugs". For example, perfluorocarbon gas is injected into the human eye to hold a detached retina in place. The gas has no metabolic reaction with the body and thus is regulated as a medical device. But determining whether the FDA would consider a product, a "device", or a "drug" can be difficult. Products can be medical devices even if there is some chemical or metabolic reactions within or on the body. For example, the body often reacts metabolically to hip and other implants. Because these reactions are side effects rather than the primary intended purpose of these implants, the products are medical devices.

The FDCA's definition of medical device includes a concept that is a key part of the FDA's regulatory framework: A medical device is both the physical product and its intended use or uses. "Intended use" is sometimes described as the express and implied claims made for a product. This concept means, for example, that a manufacturer (and his representatives) cannot, without penalty, label, or promote a laser for refractive correction eye surgery if it is legally marketed only for cardiac surgery. The manufacturer must apply to the FDA for authorization or approval to use the laser for a new indication. Changes in indications or uses can create regulatory hurdles for a manufacturer.

MEDICAL DEVICE CLASSIFICATION

Prior to 1976, the FDCA did not contain any specific provisions for medical device regulation. The Medical Device Amendments (MDA) of 1976 greatly expanded the FDA's statutory authority over medical devices and established a comprehensive regulatory scheme for medical devices. The MDA established three classes of medical devices based on the potential risk of the device to patients or users. Devices with greater potential risks are subject to more regulatory controls.

Since 1976, the FDA has established classification regulations for > 1700 different generic types of devices, and grouped them into 16 medical specialties, such as cardiovascular, respiratory, general hospital, infection control, and restorative (4). Each of these generic types of devices is assigned to one of three regulatory classes depending on the level of controls needed to provide a reasonable assurance of the devices' safety and effectiveness. Unclassified devices and new devices are automatically Class III medical devices. But not all medical devices that a layperson likely would understand to be new remain "new" for purposes of the FDCA. If a manufacturer can show that its device is "substantially equivalent" to a device that was legally marketed in 1976, often referred to as a "predicate device", then the device becomes subject to the classification and requirements that apply to that predicate device.

Class I devices are those posing the least amount of risk. Examples include elastic bandages, examination gloves, and hand-held surgical instruments. Class I devices do not require FDA review prior to marketing. However, Class I devices are subject to the FDCA's general controls for all medical devices. These general controls are the regulatory common denominator for all medical devices, and include do not distribute adulterated or misbranded devices; register the commercial establishment with the FDA; list the marketed devices with the agency; label the devices in accordance with applicable labeling regulations; manufacture the devices in accordance with the quality system and good manufacturing practices regulations (many Class I devices, however, are exempt from this requirement); permit FDA inspection. The FDA has the authority to ban medical devices under appropriate circumstances; restrict the sale, distribution, or use of some devices; and require the submission of records and reports.

Class II medical devices have an intermediate level of risk. General controls alone are not sufficient to address the risks of Class II devices. Examples include powered wheelchairs, infusion pumps, and surgical drapes. Class II devices are subject to special controls that are developed to control risks specific to particular devices. Examples of the types of special controls used by FDA include performance standards, guidelines, postmarket surveillance, and patient registries. Most Class II devices require 510(k) premarket notification. The "510(k)" refers to FDCA section 510(k), codified at 21 USC § 360(k). A 510(k) submission contains information and data to show that the device is "substantially equivalent" to a legally marketed predicate device. Clinical data is usually not required for the FDA to clear a 510(k) submission for marketing. Some Class II devices are exempt from 510(k) clearance.

Class III medical devices are those presenting the greatest risks. Examples include replacement heart valves, silicone gel-filled breast implants, and implanted brain stimulators. In general, Class III devices are subject to premarket approval prior to marketing. General and special controls alone are insufficient to provide a reasonable assurance of the devices' safety and effectiveness. Class III devices are usually devices that are life sustaining, life supporting, or implantable, or have the potential for serious injury (e.g., sight threatening). New devices that are not substantially equivalent to a legally marketed device also are usually subject to premarket approval. A premarket approval application (PMA) contains extensive scientific and technical evidence that demonstrates that a reasonable assurance of safety and effectiveness exists for the device. Clinical studies are usually required to support FDA approval of a PMA.

Under the 1997 amendments to the FDCA, manufacturers of certain devices that have been found to be not substantially equivalent can request immediate reclassification into Class I or II based on the device's low risk level. This process is called *de novo* classification. If the FDA agrees, then the device becomes subject to the requirements of either Class I or II, and a PMA is not required.

FDA-REGULATED ENTITIES

The FDA regulates manufacturers, specification developers, distributors, contract manufacturers, sterilization facilities, importers, exporters, contract research organizations, and clinical researchers of medical devices. In addition, the FDA regulates, and otherwise influences, the use and nonuse of voluntary standards by these organizations and individuals to support their regulatory activities and submissions to the agency. The manner in which parties are regulated depends on their role in the distribution of the device and on the stage of the device's lifecycle. For example, the FDA requires preapproval of medical device clinical trials that present significant risks to patients. On the other hand, establishments must register with the FDA only after the FDA authorizes marketing of the device.

USE OF STANDARDS

The FDA recognizes that a device's conformance with recognized consensus standards can be used to support a PMA, 510(k), or other submissions to the agency (5). The FDA maintains a list of officially recognized standards (6). Some domestic and international standards focus on specific medical devices (e.g., respirators). Others characterize an important aspect of many medical devices, (e.g., electrical safety). The former is sometimes called a "vertical" standard. The latter is called a "horizontal" standard. The agency also issues guidance documents for specific devices that refer to the FDA-recognized standards or to other standards. Standards should be used consistent with FDAs guidances because there can be a considerable delay between the development of consensus standards and the agency's recognition of them.

ENFORCEMENT AND PENALTIES

The FDCA authorizes civil and criminal penalties for violations (21 U.S.C. §§ 331-337). The statute, for example, prohibits the adulteration or misbranding of medical devices as well as the introduction or delivery for introduction into interstate commerce, or the receipt in interstate commerce, of any adulterated or misbranded device. The

FDCA also prohibits the submission of false or misleading information to the agency, including the withholding of material or relevant information. For example, a failure to report to the FDA all device failures that occurred during the clinical trial of a Class III medical device is a violation. Such actions can lead to not only disapproval or withdrawal of the PMA for the device, but also civil and criminal penalties on manufacturer.

The FDCA authorizes the FDA to pursue some remedies administratively, including clinical investigator disqualifications, temporary detention of medical devices, and certain civil money penalties. Other remedies, including product seizures, injunctions, criminal charges, and some civil money penalties, require judicial proceedings in federal court. The FDA refers judicial enforcement actions to the U.S. Department of Justice, and works closely with the Justice Department to prosecute these actions. The FDCA is a strict liability statute, which means that a company's management may be prosecuted for a failure to detect, prevent, or correct violations. Knowing and following the rules is important.

REQUIREMENTS GENERALLY

Marketing safe and effective medical devices in the United States requires an understanding of FDA requirements that govern the entire life cycle of the device. These include requirements for conducting nonclinical laboratory studies and clinical trials, bringing a product to market, manufacturing practices, labeling, reporting device problems and patient injuries, carrying out recalls and corrective actions, and making modifications to the device.

NONCLINICAL LABORATORY STUDIES

Manufacturers and other entities must comply with the FDA's Good Laboratory Practices (GLP) regulations when conducting nonclinical laboratory studies that are going to be used to support any regulatory submission to the FDA (21 CFR Part 58). Good Laboratory Practices regulate the organization and personnel of the laboratory as well as the facilities, equipment, test operations and study protocols, and records and reporting. Failure to comply with these regulations may invalidate data submitted to the agency. Contract research organizations used to obtain data for regulatory submissions must comply with GLP regulations.

In addition, the study should conform to FDA-recognized standards that are relevant to particular aspects of the studies, for example, laser safety, toxicity, and biocompatibility. Also, the study's documentation should specifically identify and conform to those parts of FDA performance standards and guidance documents relevant to the device rather simply state overall compliance with the standard or guidance. Whenever particular laboratory study practices will not conform to relevant guidance, the manufacturer or study sponsor should, prior to conducting the studies, discuss the discrepancies with knowledgeable FDA staff, obtain a variance from the GLP regulations if necessary, and document the reasons for the discrepancies.

CLINICAL TRIALS

The FDA regulates clinical trials of medical devices under its investigational device provisions [21 USC § 360j(g), 21 CFR Part 812]. Also important are the regulations for institutional review boards [21 CFR Part 56] and the protection of human subjects [21 CFR Part 50], and the consolidated guidance for good clinical practice [ICH E6]. Different Part 812 procedures apply depending on whether the device study presents "significant risk" or "nonsignificant risk" (7). A significant risk device presents a potential for serious risk to the health, safety, or welfare of a subject. Significant risk devices can include implants, devices that support or sustain human life, and devices that are substantially important in diagnosing, curing, mitigating or treating disease, or in preventing impairment to human health. Examples include sutures, cardiac pacemakers, hydrocephalus shunts, and orthopedic implants. Nonsignificant risk devices are devices that do not pose a significant risk to human subjects. Examples include most daily-wear contact lenses and lens solutions, ultrasonic dental scalers, and urological catheters. Although these latter devices generally are nonsignificant risk devices, the FDA could consider a particular clinical trial using these devices to be a significant risk study and regulate the trial accordingly.

An institutional review board (IRB) may approve a nonsignificant risk device study, and the study may proceed without FDA approval. But clinical studies involving significant risks must receive FDA approval prior to IRB approval. Sponsors, usually investigators or manufacturers, apply for this FDA approval through submission of an Investigational Device Exemption (IDE) application. Although IRBs are to evaluate whether a study is a nonsignificant risk, the FDA has final authority and does determine, from time to time, that an FDA-approved IDE is needed even though an IRB approved a clinical trial protocol as being a nonsignificant risk study.

The FDA's IDE regulations set forth the requirements for submitting IDEs and conducting device clinical trials. These regulations are first and foremost designed to protect human subjects from unnecessary risk. In addition, the IDE regulations are designed to guide the development and documentation of evidence needed to evaluate a device's safety and effectiveness in a PMA application, or a device's substantial equivalence in a 510(k) submission. An IDE is a request for an exemption from the restriction that only legally marketed medical devices can be distributed.

The FDA has a pre-IDE meeting program that can be extremely valuable (8). These meetings usually include FDA review of some portions of a planned IDE submission. Pre-IDE meetings can be requested in a variety of circumstances, and are intended to provide the sponsor with preliminary FDA input related to the device. For example, the pre-IDE meeting should help clarify whether any additional preclinical or technical data are needed, what concerns FDA reviewers may have, whether the proposed protocols are adequate from the FDA's perspective, and the appropriate regulatory path to market for the device. Sponsors planning to conduct nonsignificant risk studies sometimes request a pre-IDE meeting to whether deficiencies exist in the protocols that might preclude marketing approval. Other sponsors find it useful to discuss issues related to ongoing preclinical testing.

An IDE sponsor must submit a detailed description of the device, including its intended use and indication for use, that is, what does the device do and in what kind of patients or user. The sponsor must submit an investigational plan and a detailed protocol for the proposed clinical trial, including proposed informed consent documents. An IDE application also requires other documentation, including results from all laboratory and animal studies conducted with the medical device proposed for the clinical study. These laboratory and animal studies must be conducted in conformity with GLPs. The sponsor must report all relevant published studies, both nonclinical and clinical, regarding the device. Information on all medical uses of the device, and on any clinical trials conducted outside the United States may also be required. If consensus standards exist for the device, the sponsor must identify them and explain whether the device conforms with them. If previous clinical trials were conducted under IRB-only approval, then that data must be submitted in the IDE.

The IDE regulations include an IDE application template (21 CFR 812.20). The FDA also has issued a number of guidance documents on IDE processes and specific types of medical devices (3). Prior to submitting an IDE application to FDA, agency guidance documents relevant to the medical device at issue should be reviewed, and relevant aspects of those guidances implemented. These guidances often recommend specific preclinical tests for categories of devices and can include template investigational plans. But these recommendations and templates are not always suitable for particular devices. Also, guidances are not binding on the FDA and may not fully reflect current agency thinking. Consultation with the FDA may be appropriate where a sponsor believes that modifications are needed for its device.

Once a sponsor submits a complete IDE, FDA must make a decision regarding the IDE submission no later than 30 calendar days from the stamped date of arrival of the IDE application at CDRH headquarters. The FDA's initial decision letter usually lists deficiencies in the IDE, even when FDA approves the IDE. A disapproval letter is rare, especially if the sponsor had a pre-IDE meeting with the FDA. Sponsors receiving a disapproval letter may find it useful to seek assistance from an experience regulatory affairs professional to help evaluate and resolve these deficiencies. If the FDA conditionally approves the IDE, but with deficiencies that have major impact on the clinical trial or the device's indications, these deficiencies should be resolved with the FDA before the clinical trial is started. The FDA usually "conditionally" approves an IDE application, meaning that the applicant may start the clinical trial immediately, but that the applicant must answer the deficiencies satisfactorily within a short time period (e.g., 30–45 days). When the FDA perceives a high risk to human subjects, it will initially approve the IDE for a limited number of subjects and study sites, and then approve expansion of the study after the preliminary data demonstrates reasonable safety. The FDA also typically provides a list of deficiencies that do not have to be answered to conduct the clinical trial, but must be responded to in the marketing application [e.g., 510(k) or PMA]. If any aspect of the FDA's response letter is unclear, clarification should be sought from the FDA or an experienced regulatory affairs professional, or both.

Responsibilities of a clinical trial sponsor, include, but are not limited to, obtaining IRB approval, providing adequate informed consent, and ensuring that the investigators are trained and follow the approved protocol. Adequate record keeping, especially of adverse events, and study site monitoring are critical to success. Annual reports of the clinical study must be submitted to the FDA on the anniversary of the FDA's initial approval of the IDE. Also, serious adverse events must be reported to the FDA within five working days of their occurrence. All adverse events must be reported to the FDA even if the sponsor does not believe the event is related to use of the medical device being studied. Sponsors should also consult medical practice specialty standards and international standards that may be relevant to the study.

Although IDE sponsors (and their agents) may conduct limited advertising for subjects, they must not claim or suggest that the device is safe and effective for the uses it is being studied for. When discussing the device with potential investors, issuing reports on the company, and conducting similar activities, sponsors must carefully avoid making any conclusory statements regarding the device's safety and effectiveness. These restrictions continue until the FDA authorizes or approves the device for marketing. Sponsors also may not charge subjects, investigators, hospitals, or other entities a price for the device that is larger than that necessary to recover costs for manufacture, research, development, and handling. These costs should be documented in the event of an FDA inspection or audit.

Although clinical investigations of medical devices generally must comply with IDE requirements, some limited exemptions exist. For example, a diagnostic device that is noninvasive, does not require an invasive sampling procedure that poses significant risk to the subject, does not introduce energy into a subject, is not used as a diagnostic procedure without confirmation by another medically established diagnostic device, and meets certain other requirements, is exempt from IDE requirements. But the study must still comply with IRB and informed consent requirements.

REGULATORY PATHWAYS TO MARKET

Some medical devices require clearance through premarket "510(k)" notification, some medical devices require premarket approval, and others are exempt from premarket notification and premarket review. The majority of devices—more than 75%—have entered the market through 510(k) premarket notification.

Premarket notification is a process under which the FDA decides whether the evidence demonstrates substantial equivalence between a new device and a legally marketed (predicate) device. If the FDA decides that the device is substantially equivalent to the predicate device, then the device is “cleared” for market. If the FDA decides that the device is not substantially equivalent, it is sometimes appropriate for a manufacturer to request *de novo* classification into Class I or II based on the device’s low potential risks. But if the FDA denies that request, the only pathway to market is the PMA approval process. Typically, the FDA will determine, in discussions with a manufacturer or sponsor, which of the three pathways to market is required: (1) 510(k) → substantial equivalence; (2) 510(k) → nonequivalence → *de novo*; (3) PMA. But, as noted, some medical devices are exempt from even 510(k) requirements.

The Medical Device User Fee and Modernization Act of 2002 (MDUFMA) authorizes user fees for premarket reviews of PMAs, PDPs, certain supplements, 510(k)s, and certain other submissions (21 USC §§ 379i-379j). The MDUFMA also set agency performance goals for many types of premarket reviews. These goals become more demanding on the FDA over time. User fees must be paid at the time a submission is sent to the agency or the agency will not file or review it. The MDUFMA includes some fee exemption, waiver, and reduction provisions, including a fee waiver for the first premarket application by a small business.

PREMARKET NOTIFICATION EXEMPTIONS

Class I medical devices are exempt from 510(k) notification unless the FDA has by regulation stated that a particular medical device type is not exempt, or has specified conditions under which it is exempt. But the exemption applies only where the device is intended and indicated for the use or uses specified in the applicable regulation. If the device is to be marketed for a different use or medical condition, then the device is not exempt from 510(k) notification. If the new use presents extremely high risks or involves particularly vulnerable patients, a PMA may be required instead of a 510(k).

The same basic exemption rules apply to Class II devices, except that few Class II devices are exempt from premarket review. For devices exempt from premarket review by regulation, some changes in uses or indications do not require premarket review of the device because certain uses or indications are sufficiently similar to legally marketed intended uses. But in other instances, the FDA decides that an otherwise exempt device must receive premarket notification even though the uses or indications seem very similar. Although the FDCA provides a means for manufacturers to obtain a formal opinion from the FDA where uncertainty exists about the regulatory status of a device, an informal opinion may be sufficient, and preferable, in some situations. Manufacturers should consult an experienced regulatory affairs professional to evaluate how best to proceed in these circumstances.

PREMARKET “510(K)” NOTIFICATION

A 510(k) submission → substantial equivalence decision requires a determination by the FDA that

1. The intended use of the sponsor’s device is the same as that of the predicate device(s). Predicate devices may be any Class I or II device with the same intended use. (A limited number of Class III devices marketed before 1976 also can be predicate devices if the FDA has not yet called for a PMA.)
2. The technological characteristics of the sponsor’s device must be either
   (a) The same as the predicate device.
   (b) Have performance characteristics that demonstrate that it is as safe and effective as the predicate device.

A substantially equivalent device is not “approved” for market. Instead, a 510(k) “clearance” decision is based on the FDA’s evaluation of whether the device is substantially equivalent to a legally marketed device for which a reasonable assurance of safety and effectiveness exists. “Substantial equivalence” is a term of art, and does not require that a sponsor’s device look or even operate the same as a predicate device. Two devices that visually appear dissimilar can be substantially equivalent under the FDCA. For example, the FDA cleared laser-light and water-jet microkeratomes as equivalent to vibrating steel blades to cut the cornea even though the former products use completely different cutting mechanisms than the latter.

The FDA has issued many guidance documents on various medical device types requiring premarket notification (3). The agency also has issued guidance documents for the 510(k) notification process. The FDA will provide prenotification consultation in telephone or in-person conferences to discuss a sponsor’s medical device and answer questions regarding written guidance documents and applicable standards. The FDCA requires the FDA to consider, in consultation with a sponsor, the “least burdensome”, appropriate means of evaluating a device (9). To maximize this requirement, a sponsor should understand, as much as possible, the requirements, guidances, and standards that apply to its medical device before meeting with FDA staff. As noted, guidances do not “bind” the FDA. But they can provide valuable information on the agency’s thinking on particular topics. Also, a sponsor should try to understand how similar devices have been regulated by the FDA.


510(k) Flow Chart
510(k) Notification
FDA Assesment
Substantially equivalent
Not substantially equivalent
Unable to determine SE
Marketing authorization
PMA or 510(k) *de nova* required
FDA requests additional information for reassement

The 510(k) submission → nonequivalence → *de novo* process use the same 510(k) processes to try to establish that substantial equivalence exists and obtain FDA clearance for marketing. But when the sponsor is unable to do so, despite thorough efforts to do so, then the objective becomes convincing the FDA that a PMA is not necessary for regulatory control of the device. This requires a showing that the risks from the device are minimal, that the device is effective for its intended use, and that general controls and, in some cases, special controls will be sufficient to mitigate the product's risks. A request for *de novo* classification must be made within 30 days of receiving a not substantially equivalent determination, describe the device in detail, and provide a detailed recommendation for classification. The FDA then has 60 days to respond to that request with a written order classifying the device and identifying any special controls that may be needed if the device is in Class II. The device is then considered cleared and may be marketed. If the FDA keeps the device in Class III, PMA approval will be required before marketing.

MARKETING APPROVAL

Class III medical devices generally are high risk devices that cannot be regulated adequately by general and special controls alone. In other words, the FDA must review the safety and effectiveness data for these devices to determine if they should be approved for the treatment or diagnosis of diseases or other conditions in humans, and under what conditions. Class III devices may be approved for marketing under the humanitarian use device exemption (HDE), product development protocol (PDP), or premarket approval application (PMA) requirements.

HUMANITARIAN USE DEVICES

The FDCA's humanitarian use device exemption provision is narrow in that the objective is to provide rapid access to new therapeutic or diagnostic devices for patients with rare diseases or conditions, that is, so-called "orphan" devices (21 USC § 360j(m), 21 CFR Part 814, Subpart H). The humanitarian use device (HUD) process is relatively rapid because the applicant does not have to conduct clinical trials to demonstrate reasonable assurance of safety and effective, and the statute allows the FDA significantly less time to act on an HUD application than the agency has for a PMA. Rather than provide data to determine the safety and effectiveness of the device, the applicant has only to satisfactorily explain to the FDA why the probable benefit of the device outweighs the risks to patients in the context of other treatments for the disease. However, this regulatory pathway has many requirements, including the disease or condition affects fewer than 4000 patients/year, the device would not otherwise be available for persons with this disease or condition, the device and will not expose patients to unreasonable or significant risks, and the benefits to health from the device's use must outweigh the risk. Because of the provision's narrow scope and limitations, the humanitarian use device exemption is not used frequently. But it can be very valuable in some instances.

PRODUCT DEVELOPMENT PROTOCOL

The product development protocol (PDP) is an alternative to the PMA process, but is rarely used [21 USC § 360e(f)]. The PDP's distinguishing feature is that it involves a close relationship between the FDA and the sponsor in designing appropriate preclinical and clinical investigations to establish the safety and effectiveness of a device. The PDP requires multiple levels of review and approval of study protocols. The requirements for proof of safety and effectiveness are the same as for a PMA. The PDP process thus offers few advantages for a manufacturer over premarket approval processes, particularly for a device that has undergone significant evaluation and investigation. The PDPs also have required much more FDA staff time than PMA processes.

PREMARKET APPROVAL (PMA)

The FDCA's requirements for PMA approval apply to most Class III medical devices, except for a few devices marketed before the 1976 MDA and those being used consistent with an investigational device exemption (IDE) in order to obtain clinical data to establish the device's safety and effectiveness (21 USC § 360e). The FDA has promulgated regulations on PMA requirements and processes (21 CFR Part 814). These regulations include the FDA's procedures for reviewing and acting on a PMA application. Other important sources for information on PMA issues include general guidances, guidances for specific devices, meetings with the agency and advisory panels, and correspondence from the agency.

The regulations specify and describe the general categories of required information in a PMA [21 CFR 814.20(b)]. These categories include an "indication for use" statement, a device description, and data from nonclinical and clinical studies of the device. The foreign and U.S. marketing history, if any, of the device by the applicant or others must be described in the PMA, including a list of countries in the device has been withdrawn from marketing.

INDICATION FOR USE

A PMA's "indication for use" statement must provide a general description of "the disease or condition the device will diagnose, treat, prevent, cure, or mitigate" and "the patient population for which the device is intended" [21 CFR 814.20(b)(3)]. The "indication for use" statement is key to the device's labeling and, if the device is approved, the uses for which it can be legally marketed. In addition to this statement, the application must include a separate description of existing alternative procedures and practices for the indicated use.

DEVICE DESCRIPTION

The device must be described in summary form and then in detail, including manufacturing and trade secret information where necessary, to allow FDA specialists to evaluate the risks associated with the device. The summary must explain "how the device functions, the basic scientific concepts that form the basis for the device, and the significant physical and performance characteristics of the device" [21 CFR 814.20(b)(3)]. The full device description must include detailed drawings, and details of each functional component or ingredient of the device, all properties of the device relevant to the indication for use, the scientific and technical principles of operation of the device, and the quality control methods (good manufacturing practices) used in the manufacture, processing, packing, storage, and installation of the device [21 CFR 814.20(b)(4)]. In addition, the applicant must reference any standard, mandatory or voluntary, that is relevant to the device for the indicated use. If applicable, the applicant must identify how the device deviates from the standard and demonstrate, to the FDA's satisfaction, how the applicant resolves these deviations.

NONCLINICAL STUDIES

A PMA must include summaries of nonclinical laboratory studies appropriate to the device, including, but not limited to, microbiological, toxicological, immunological, biocompatibility, stress, wear, shelf life studies. The PMA must also include a statement that each study was conducted in accordance with the FDA's good laboratory practices regulations, or explanations as to why not. The study summaries must include descriptions of the objectives, experimental design, data collection and analysis, and results of each study. The results should be described as positive, negative, or inconclusive with regard to the objectives of each study. After each of the studies is summarized, it must be described in sufficient detail to enable the FDA to determine the adequacy of the information for FDA review of the PMA.

CLINICAL STUDIES

Clinical studies involving human subjects with the device must be conducted in accordance with IDE regulations or, if they are conducted outside the United States without an FDA-approved IDE, they must be conducted in accordance with special requirements discussed with the FDA before the PMA is submitted. IRB and human subjects protection requirements and the ICH guidance for good clinical practice also apply. The results of these clinical studies must be summarized first and then discussed in sufficient detail to enable the FDA to determine the adequacy of the information for FDA approval of the PMA. Clinical trial summaries must include the following:

> "...a discussion of subject selection and exclusion criteria, study population, study period, safety and effectiveness data, adverse reactions and complications, patient discontinuation, patient complaints, device failures and replacements, results of statistical analyses of the clinical investigations, contraindications and precautions for use of the device, and other information from the clinical investigations as appropriate...." [21 CFR 814.20(b)(3)].

Discussion of the results of the clinical investigations must include details regarding:

> "...the clinical protocols, number of investigators and subjects per investigator, subject selection and exclusion criteria, study population, study period, safety and effectiveness data, adverse reactions and complications, patient discontinuation, patient complaints, device failures and replacements, tabulations of data from all individual subject report forms and copies of such forms for each subject who died during a clinical investigation or who did not complete the investigation, results of statistical analyses of the clinical investigations, device failures and replacements, contraindications and precautions for use of the device, and any other appropriate information from the clinical investigations...." [21 CFR 814.20(b)(6)].

The applicant must identify any investigation conducted under an FDA-approved IDE and provide a written statement with respect to compliance with IRB requirement, or explain the noncompliance. In addition to submitting the data for all the studies conducted by the applicant (or on the applicant's behalf), the applicant is responsible for submitting a bibliography of all studies (nonclinical as well as clinical) relevant to the device and copies of any studies requested by the FDA or the advisory panel. Also, the applicant must identify, discuss, and analyze:

> "...any other data, information, or report relevant to an evaluation of the safety and effectiveness of the device known to or that should reasonably be known to the applicant from any source, foreign or domestic, including information derived from investigations other than those proposed in the application and from commercial marketing experience." [21 CFR 814.20(b)(8)].

LABELING

The applicant must submit copies of all proposed labeling for the device, including contraindications, warnings, precautions, and adverse reactions. Labeling typically includes, but is not limited to, physician instructions, an operation manual, a patient brochure, and all applicable information, literature, or advertising materials that constitutes labeling [21 CFR 814.20(b)(10)]. The FDA reviews and revises the proposed labeling prior to PMA approval.

REVIEW STANDARD

The applicant must demonstrate that the nonclinical, clinical, and technical data submitted in the PMA embody valid scientific evidence of reasonable assurance that the device is safe and effective for its intended use. In addition, the applicant must discuss the benefits and risks (including any adverse effects) of the device, and describe any additional studies or surveillance the applicant intends to conduct following approval of the PMA. In evaluating safety and effectiveness, the FDA defines “valid scientific evidence” broadly and retains final authority on what is acceptable [21 CFR 860.7(c)]. The agency considers a variety of factors in deciding whether reasonable assurance of safety and effectiveness has been submitted for a medical device, including intended use (indication), use conditions, benefit–risk considerations, device reliability, and generally requires well-controlled clinical investigations (21 CFR 860.7).

PMA flow chart


Nonclinical studies
IDE compliance
Clinical trials
Premarket approval application
FDA review includes advisory committee input, as appropriate
Does the data provide reasonable assurance of the device’s safety & effectiveness for its intended use?
If yes, premarket approval
If no, cannot be marketed

UPDATE REPORT REQUIREMENTS

While the FDA is reviewing a PMA application, the applicant must update it. Such updates are required 3 months after the PMA filing date, following the applicant’s receipt of an FDA letter stating the PMA is “approvable”, and at any other time as requested by the FDA. An “approvable” letter is a decision by the FDA that the PMA will be approved after the applicant resolves minor deficiencies.

After a device is approved, periodic and other reports are required. The owner of an FDA-approved PMA device is responsible for periodically updating any safety and effectiveness information on the device that may reasonably affect the FDA’s evaluation of the device’s safety or effectiveness, or that may reasonably affect statements of contraindications, warnings, precautions, and adverse reactions. If a PMA owner becomes aware of off-label (unapproved) uses of its device that may be unsafe or ineffective, then it is responsible for reporting these unauthorized uses to the FDA, especially if adverse events are associated with them.

POSTMARKET RULES

Major postmarket requirements include adequate labeling, medical device reporting, corrections and removals, and device modifications integrated into a system for manufacturing quality medical devices.

LABELING OVERVIEW

Labeling of medical devices is one of a manufacturer’s key postmarket responsibilities. Each device must comply with general labeling requirements, and with the specific requirements and limits identified in the FDA’s authorization or approval to market the device.

LABELING: GENERAL REQUIREMENTS

Many general labeling requirements exist for medical devices (21 CFR Part 801, Subpart A). The regulations include details on issues such as how a manufacturer’s name is to be listed on a device package label. This article focuses on key concepts in the FDA’s regulation of device labeling. These concepts include the FDCA’s definition of “labeling”, the regulation’s definition of “intended use”, and “adequate directions for use” requirements.

Under the FDCA, “labeling means all labels and other written, printed, or graphic matter (1) upon any article or any of its containers or wrappers, or (2) accompanying such article” [21 USC § 321(m)]. This definition is very broad and includes promotional and advertising materials and oral statements about the device. The FDA’s regulation of advertising and promotion presents many challenges for medical device companies. Three basic principles are critical: materials must be truthful and not misleading, must contain a fair balance of benefits and risks, and must provide full disclosure for use.

The “intended use” of a medical device is the objective intent of the product as expressed by the manufacturer or distributor of the device (21 CFR 801.4). It includes all conditions, uses, or purposes stated by the manufacturer or distributor orally or in written form. As discussed earlier, “intended use” is an integral part of the FDCA’s “medical device” definition. If a manufacturer or distributor promotes an “intended use” different from the one authorized by the FDA, then the device is adulterated and misbranded until and unless the FDA authorizes the new use. This is often referred to as “off-label” use. The regulation further provides that “if a manufacturer knows, or has knowledge of facts that would give him notice that a device introduced into interstate commerce by him is to be used for conditions, purposes, or uses other than the ones for which he offers it, he is required to provide adequate labeling for such a device which accords with such other uses to the article is to be put.” “Intended use” is how the manufacturer intends the device to be used. “Indication for use” is a subset of “intended use” that usually represents a narrowing of the intended use to a specific patient population. In short, why a patient, or a practitioner on a patient’s behalf, would use a particular device. Indications for use include a general description of the disease or condition the device will diagnose, treat, prevent, cure, or mitigate, including a description of the patient population for which the device is intended. If differences related to gender, race, ethnicity, age, or other factors exist, they should be reflected as well in the product's labeling.

The FDCA requires device labeling to bear "adequate directions for use," unless the FDA has promulgated regulations exempting a particular device [21 USC § 352(f)]. Under the regulations, "[a]dequate directions for use means directions under which the layman can use a device safely and for the purposes for which it is intended..." (21 CFR 801.5). These directions include specification of all applicable use conditions, dose quantity, use frequency, use duration, time of use, method of use, and use preparation. Adequate directions for use on over-the-counter devices must include a statement of indication for use [21 CFR 801.61(b)].

Prescription devices are exempt from the adequate directions for use requirement because, by definition, such directions cannot be prepared for a prescription device (21 CFR 801.109). However, prescription devices must have adequate instructions for the device's use by practitioners, including, but not limited to information on its use and indications, and any adverse events, contraindications, and side effects that may accompany the use of the device. In addition, to qualify for the adequate directions for use exemption for prescription devices, the device must meet other conditions, such as being in the possession of the practitioner. The regulations authorize other exemptions from the adequate directions for use requirement, including ones for medical devices that have common uses known to ordinary individuals, for medical devices used in certain teaching not involving clinical research, and for medical devices used in manufacturing, processing, and repacking (21 CFR Part 801, Subpart D).

LABELING: SPECIFIC DEVICES

Sources for labeling requirements for particular devices include labeling regulations for a few specific kinds of devices, classification regulations that provide "indications for use" statements for most Class I and Class II devices, guidance documents on specific devices, the FDA marketing authorization and approval letters, and approved labeling for PMA-approved devices.

The FDA has issued specific labeling regulations for dentures, eyeglasses and sunglasses, hearing aids, menstrual tampons, latex condoms, and devices that contain natural rubber (21 CFR Part 801, Subpart H). It also has specific labeling regulations for *in vitro* diagnostic devices (21 CFR Part 809, Subpart B). Each approved PMA includes labeling requirements for the device specified in the approval letter, in the summary of safety and effectiveness, and in written instructions for physicians (and other appropriate professionals) and patients.

REPORTING, CORRECTIONS, AND REMOVALS

Entities that manufacture, prepare, process, package, and/or distribute medical devices are subject to certain requirements regarding device reporting, corrections, and removals. They must track, document, investigate, take action on, and report on events associated with their medical devices. Device user facilities (e.g., hospitals) and importers of medical devices also have responsibilities for reporting certain medical device events (21 CFR Part 803, Subparts A-B and C-D). This article focuses on FDA reporting requirements for device manufacturers (21 CFR Part 803, Subparts A-B and E).

Device manufacturers must report medical device reportable (MDR) events to the FDA with five workdays of becoming aware of a reportable incident if remedial action to prevent an unreasonable risk of substantial harm to the public health, or the event is of a type that the FDA has designated as requiring a report within five work days. Otherwise, MDR events must be reported to the FDA within 30 calendar days. An MDR event is any information that a manufacturer becomes aware of that reasonably suggests that the device marketed by the manufacturer may have "caused or contributed to a death or serious injury" or "malfunctioned...and would be likely to contribute to a death or serious injury, if the malfunction were to recur" [21 CFR 803.3(r), 803.50(a)]. By "any information", the regulations mean all information in the manufacturer's possession or that the manufacturer could obtain from user facilities, distributors, initial reporters of the information, or by analysis, testing, or evaluation of the device. The FDA's regulations specify that manufacturers "become aware" of a reportable event when any employee and any manager or supervisor of employees with responsibility for MDR events acquires information reasonably suggesting that a reportable adverse event has occurred. Moreover, MDR events include any information that necessitates "remedial action to prevent an unreasonable risk of substantial harm to the public health", including, but not limited to, trend analysis [21 CFR 803.3(c)].

Manufacturers should be very inclusive of potential MDR reportable events because the regulations define "caused or contributed" factors very broadly to include events due to user error and labeling misunderstandings in addition to manufacturing and design problems, and device failure and malfunction. In addition, the regulations define malfunction to mean the failure of the device to meet performance specifications of the device for the labeled intended use of the device. "Remedial action" means "any action other than routine maintenance or servicing, of a device where such action is necessary to prevent recurrence of a reportable event" [21 CFR 803.3(z)]. For MDR purposes, the regulations define "serious injury" more broadly than a life-threatening illness or injury. Serious injuries are also those that produce permanent functional impairment, or damage to, body structure or that requires treatment to preclude such impairment [21 CFR 803.3(bb)].

Manufacturers should have written procedures in place to identify, evaluate, and document potential MDR reportable events so that reports can be submitted to the agency accurately and within the required timeframes. A manufacturer must maintain files and records of all events associated with its medical devices whether the manufacturer decided that such events were MDR reportable, and the FDA must be given access to these records upon request. A manufacturer must maintain records of MDR reportable events for ready access by FDA inspectors, and also coordinate these files with the complaint files required by the FDA's Quality System Regulations.

In order to comply with MDR reporting and general record keeping requirements (21 CFR 803.17), a manufacturers must have a system of written procedures to identify, communicate, and evaluate events subject to MDR reporting requirements that is timely and effective; transmit medical device reports to the FDA that are complete and timely; document and record all information that was evaluated in determining if an event was MDR reportable, submitted to the FDA (including MDR reports), used in preparing semiannual reports or certifications to the FDA, and ensure that this documentation and record keeping is readily and promptly accessible to the FDA upon inspection.

Manufacturers also must submit reports to the FDA about medical devices that the manufacturer has corrected in, or removed from, the marketplace to reduce the risk to public health (21 CFR Part 806). A "corrected" medical device is one that the manufacturer has repaired, modified, destroyed, adjusted, relabeled, or inspected at the user location. This includes patient monitoring. A "removed" medical device is one that the manufacturer has physically moved from the user facility to repair, modify, destroy, adjust, relabel, or inspect. Corrections or removals do not have to be reported for devices that have not been distributed to users (stock recovery) or for routine maintenance. However, corrections or removals must be reported for "repairs of an unexpected nature, replacement of parts earlier than their normal life expectancy, or identical repairs or replacements of multiple units" of the device [21 CFR 806.2(k)]. The manufacturer must explain to the agency the reasons for, and estimate the risk to public health of, each correction and removal action within 10 days of initiating the action. The manufacturer must keep records of all corrections and removals, including those not reportable to the FDA, such as those for routine maintenance and stock recovery.

MODIFICATIONS TO MEDICAL DEVICES

Manufacturers must ensure that modifications to their marketed devices are made using design control requirements of the FDA's Quality System Regulations, including, but not limited to, verification and validation processes and updates of the design history file. Manufacturers should also have procedures in place to evaluate whether particular device modifications need to be reported to the FDA. All device modifications must be documented in the company's design and device history files. But some device modifications require prior approval by the agency, some require the opportunity for FDA disapproval prior to implementation, and still others may be reported after the company has implemented the changes. Because a medical device is defined as the physical apparatus and its intended use, significant changes to the product's intended use can require prior authorization from the FDA, even if no physical modification is made to the apparatus; the claim is only implied by the physical modification made to the apparatus; the manufacturer does not make the change but is aware that an entity to which the company sold the device is making additional substantial claims for the device. In other words, the FDA authorized manufacturer of a medical device can be responsible for the device it manufactures for the entire life cycle of the device.

The FDA's guidances for reporting device modifications for 510(k)-cleared devices and PMA-approved devices are summarized in Table 1 (10,11). Manufacturers should establish policies and principles for the company's medical devices based on these guidance documents and agency guidances specific to the company's devices.

QUALITY SYSTEM REGULATIONS

The two main objectives of the FDA's Quality System Regulations (QSR) (21 CFR Part 820) are to ensure (1) that quality in designed into medical devices, and (2) that management is responsible for the device throughout its life cycle and will be held accountable for shortcomings. The QSR sets forth the agency's current good manufacturing practices (cGMP) requirements for medical devices. Each manufacturer must integrate processes for controlling device modifications, labeling, and actions, reports, and record keeping regarding MDR events, corrections and removals into a quality system that is compliant with QSR. The QSR requires manufacturers to integrate all events associated with the manufacture and distribution of the medical devices into a corrective and preventive action (CAPA) subsystem linked to a record keeping subsystem that includes complaint files. The manufacturer must establish standard operating procedures that define, for example, the criteria for MDR reportable events for each kind of medical device that are manufactured, what actions are required, and the processes that must be followed. The manufacturer is responsible not only for maintaining complaint files and device history files, but for actively evaluating this information to maintain the medical device quality. This system involves using diverse information, including device maintenance, modifications, malfunctions, and failures with complaints from users, off-label (unapproved) use, and adverse reactions for continuous evaluation to ensure that the device is performing as designed. Corrective actions are to be taken as appropriate.

The corrective and preventive action subsystem is only one subsystem in a manufacturer's quality system. A quality system should be formed during the establishment of a company's management responsibilities and reviewed and revised during the initial design phase of device development. In addition to management and design control requirements, the QSR requires systems to control documents, purchasing, identification, traceability, production, processing, acceptance, nonconforming products, labeling, packaging, handling, storage, distribution, installation, servicing, and statistics. The regulations give a manufacturer the flexibility to develop a quality system for its medical devices that is tailored to the characteristics of these medical devices. However, the manufacturer's management team must justify and document the quality system, usually in

Table 1. Device Modification Reporting

Types of Modification	Premarket Notice [510(k)]	PMA Supplement
Changes due to recall or corrective action	Recall or corrective actions imply a safety or effectiveness problem with the device. Therefore, the FDA usually requires submission of a 510(k) notice if a device modification is necessary as part of the corrective action	Submit a “180-Day PMA Supplement” for design changes due to recall or corrective action even if the device still meets design specifications. Submit a “Special PMA Supplement-Changes Being Effected” for manufacturing changes that result from the corrective action
Changes that significantly affect safety or effectiveness	Use quality system, especially design controls, to determine if changes that significantly affect safety or effectiveness and if they do then submit a 510(k) notice	Submit a “180-Day PMA Supplement” for changes in, but not limited to, indications for use, labeling, new facilities, sterilization method, packaging, performance or design specifications, and the expiration date that affect safety or effectiveness. Use the quality system, especially design controls, to determine if changes affect safety or effectiveness. The FDA may issue a formal opinion that permits certain changes to be submitted in a “30-Day Supplement” rather than a “180-Day Supplement”
Labeling changes	Most, but not all, changes in intended use/ indication for use require submission of a 510(k) notice. For example, if the device will be indicated for use in a subset of patients for which the device is already cleared, then a 510(k) may not have to be submitted. Or no notice may be needed if a risk analysis demonstrates no additional risk by expanding the patient population being treated	Submit a “180-Day PMA Supplement”
Technology or performance specifications	Changes in a device’s control mechanism, principles of operation, or energy source usually requires submission of a 510(k) notice. Changes in sterilization method usually do not require 510(k) notification if design verification and validation is adequate	Submit a “180-Day PMA Supplement”
Materials changes	Evaluate the effects of materials changes on the performance characteristics of the device. If the performance characteristics are changed significantly or new labeling must be added then perhaps a 510(k) notice should be submitted to the FDA	Submit a “180-Day PMA Supplement”
Minor incremental changes or changes that do not affect safety or effectiveness	Use design controls to evaluate risks associated with “minor” evolutionary changes in the device. Proactively develop a decision rule about when these incremental changes should be reported to the FDA	Usually does not require FDA approval prior to implementation but describe the modifications in the Annual Report required for the PMA
Minor changes to the manufacturing process	Notice to the FDA not required	File a “30-Day Notice” to the FDA describing the changes in detail. Implement the changes at the end of the 30-day period unless the changes require submission of a “135-Day Supplement” because the 30 day notice to the FDA was inadequate
Changes that improve the safety of the device	Notice to the FDA not required	File a clearly marked “Special PMA Supplement—Changes Being Effected.” The changes that enhance safety include, but are not limited to, changes that strengthen a contraindication, an instruction, or quality controls. They must be described in detail

a quality system manual that specifies each of the subsystems as identified in the QSR and any deviations from it.

IMPLEMENTATION

Bioengineers and informed specialists developing innovative medical devices must understand the regulatory implications of their scientific and technical innovations in order to develop a realistic business plan for their product. Sometimes the innovations are considerable yet the agency regulatory pathways remain simple. For example, as discussed earlier, CDRH cleared laser-light and water-jet microkeratomes as equivalent to vibrating steel blades to cut the cornea even though the former products use completely different cutting mechanisms than the latter. Similarly, FDA decided that a manufacturer's microscopic dermal fragments should be regulated as human tissues under the same tissue bank rules used to regulate its macroscopic sheets of dermis. The FDA could have decided to regulate microscopic dermis as a medical device because of the additional processing (a decision that would have required requiring premarket authorization of the dermal fragments), but instead decided both were human tissues from a regulatory point of view. On the other hand, innovative products can be subject to profoundly different regulatory pathways. For example, external kidney dialysis products have almost always been regulated as medical devices by the CDRH using the 510(k) process, an efficient process. However, the FDA decided to use the drug–biologics review process (IND/NDA) to regulate an external kidney dialysis filter using human cells, a more complex and costly review process than for devices.

The following analysis of a hypothetical medical device illustrates some of the regulatory implications of innovative medical devices. The hypothetical device is an implanted artificial kidney that can continuously dialyze the human body. Currently, 90% of patients that require kidney dialysis are treated with an external device in which the patient's blood is dialyzed outside the body, an external kidney dialysis device. Some patients are treated with an external kidney dialysis device that infuses the dialysate (the dialysis solution) into the abdominal cavity (the peritoneum) and then drains the waste products out of the peritoneum ~45 min later or continuously overnight. As mentioned above, the FDA currently is regulating an external kidney dialysis product using more burdensome drug–biologic regulatory requirements rather than the simpler 510(k) process used for other dialysis machines. Therefore, if metabolic interaction and/or cells are used in an implanted artificial kidney devices, it is likely that either CDER or CBER will lead the review of the combination product through the FDA's drug–biologics approval process. However, if the implanted artificial kidney device achieved its intended use of dialysis without primarily biochemical or metabolic interaction with the human body, then the implanted artificial kidney likely would be regulated as a medical device by the CDRH. Filter material and microscopic control elements such as valves and motors are likely critical components. This example illustrates that issues imbedded in the scientific and technical characteristics of an innovative medical product could result in a regulatory pathway that is more complex, and costly, than already marketed alternative products.

Regardless of whether the innovative medical product, an implanted artificial kidney in this example, is reviewed by the FDA as a device, drug, or biologic, or a combination product, agency reviewers may or may not have expertise or knowledge directly relevant to the critical science. In fact, it is unlikely. Therefore, very early in product development the manufacturer should engage FDA reviewers in a dialogue about the cutting edge science or technology used in the device so that a common understanding evolves about key safety and effectiveness issues. This approach should help reduce misunderstandings about necessary nonclinical laboratory studies, animal study protocols, key safety and effectiveness endpoints, and fail-safe mechanisms so that agency reviewers will be comfortable with the risks associated with initial pilot study in humans. Also, the manufacturer should dialogue with agency reviewers about the scientific, clinical, and ethical issues associated with an initial clinical study in humans. In order to maximize control, manufacturers should take the initiative in making study proposals to the FDA rather than simply ask the agency for advice.

REGULATORY CHALLENGES

Medical device developers, academic researchers and engineers, start-up companies, research and development departments of large manufacturers, and other innovators are at the leading edge of scientific, technological, and medical product development, not the FDA. They therefore should be proactive with regard to the issues critical to the development and eventual marketing of the medical device. Developers of medical devices should take advantage of the opportunities to establish conditions for efficient FDA regulation of their devices before making regulatory submissions to the agency by developing a detailed quality system manual tailored to development and manufacture of the company's medical device; implementing good laboratory practices and specific standard operating procedures for nonclinical studies; identifying existing technical standards that are applicable to manufacturing quality devices, developing applicable standards where none exist; identifying the best clinical practices for clinical trials with the device; communicating the science and technology of the device to FDA reviewers; proposing a specific regulatory pathway to the agency based on a risk-benefit analysis of the device; incorporating feedback from discussions with the FDA. These proactive steps are particularly important for devices that are very innovative, and where scientific consensus may not exist on procedures and new standards needed to verify and validate the design of the device.

BIBLIOGRAPHY

1. Online access to the United States Code. Available at http://www.gpoaccess.gov/uscode/index.html. Accessed 2005 Feb 11.
2. Online access to U.S. Food and Drug Administration regulations. Available at http://www.accessdata.fda.gov/scripts/cdrh/cfdocs/cfcfr/CFRSearch.cfm. Accessed 2005 Feb 11.

3. U.S. Food and Drug Administration Guidance Documents. Available online at http://www.fda.gov/cdrh. A searchable database of FDA guidances involving medical devices is available at http://www.accessdata.fda.gov/scripts/cdrh/cfdocs/cfggp/search.cfm. Accessed 2005 Feb 11.
4. A searchable database of U.S. Food and Drug Administration Medical Device Classification Regulations. Available at http://www.accessdata.fda.gov/scripts/cdrh/cfdocs/cfPCD/PCDSimpleSearch.cfm. Accessed 2005 Feb 11.
5. U.S. Food and Drug Administration, Center for Devices and Radiological Health (2001, June 20). Recognition and Use of Consensus Standards; Final Guidance for Industry and FDA Staff. [Online version]. USFDA. http://www.fda.gov/cdrh/ost/guidance/321.html. Accessed 2005 Feb 11.
6. Standards recognized by the U.S. Food and Drug Administration. Available in a searchable online database at http://www.accessdata.fda.gov/scripts/cdrh/cfdocs/cfStandards/search.cfm. Accessed 2005 Feb 11.
7. U.S. Food and Drug Administration, Office of the Commissioner (2001, April 18). Information Sheets: Guidance for Guidance for Institutional Review Boards and Clinical Investigators: Medical Devices. [Online] USFDA. Available at http://www.fda.gov/oc/ohrt/irbs/devices.html. Accessed 2005 Feb 11.
8. U.S. Food and Drug Administration, Center for Devices and Radiological Health. (1999, March 25). IDE Guidance Memorandum-Pre-IDE Program: Issues and Answers. [Online version]. USFDA. Available at http://www.fda.gov/cdrh/ode/d99-1.html. Accessed 2005 Feb 11.
9. U.S. Food and Drug Administration. Center for Devices and Radiological Health. (2002, October 4). The Least Burdensome Provisions of the FDA Modernization Act of 1997: Concept and Principles; Final Guidance for FDA and Industry. [Online version]. USFDA. Available at http://www.fda.gov/cdrh/ode/guidance/1332.html. Accessed 2005 Feb 11.
10. U.S. Food and Drug Administration, Center for Devices and Radiological Health. (1997, Jan 10). Deciding When to Submit a 510(k) for a Change to an Existing Device. [Online version]. USFDA. Available at http://www.fda.gov/cdrh/ode/510kmod.html. Accessed 2005 Feb 11.
11. U.S. Food and Drug Administration, Center for Devices and Radiological Health. (1998, Feb 19). 30-Day Notices and 135-Day PMA Supplements for Manufacturing Method or Process Changes. [Online version]. USFDA. Available at http://www.fda.gov/cdrh/modact/daypmasp.html. Accessed 2005 Feb 11.

See also CODES AND REGULATIONS: RADIATION; HOME HEALTH CARE DEVICES; HUMAN FACTORS IN MEDICAL DEVICES; SAFETY PROGRAM, HOSPITAL.

CODES AND REGULATIONS: RADIATION

BRUCE THOMADSEN
GLENN GLASGOW
BENJAMIN EDWARDS
RALPH LIETO
University of Wisconsin-Madison
Madison, Wisconsin

INTRODUCTION

Every country develops its own regulations governing radiation. Because this text is coming from the United States, the regulations considered here mostly apply to that country. “Radiation” in this article always refers to electromagnetic radiation and to energies higher than that used for communications (radio and microwave): particularly to higher-energy, directly and indirectly ionizing radiation [referred to as ionizing radiation (IR) hereafter] and medium-energy, nonionizing radiation (NIR). The discovery of ionizing radiations (i.e., those forms of radiation with sufficient energy to directly or indirectly *ionize* atoms by stripping away one or more electrons, thereby producing an ion pair consisting of the freed electron and charged atom) at the end of the nineteenth century (c. 1895) was followed quickly by observations of radiation injury.The first *recommendations* on IR dose limitation and personnel protection appeared shortly thereafter. The first general *regulations* for ionizing radiation came with the advent of the program to develop nuclear weapons during World War II. Most of this article deals with IR only because those regulations are more complex and voluminous. In addition, because this Encyclopedia focuses on biomedical applications, this text will concentrate most on those regulations most pertinent to medical settings, particularly those that have changed since the original edition of the Encyclopedia (1).

Although the electrical and magnetic fields associated with NIR were well known long before the discovery of ionizing radiation, a lack of significant observable health effects and the scarcity of powerful NIR sources delayed the development of NIR exposure standards until much later. The development of NIR standards was further complicated by the very wide range of wavelengths and photon energies covered by the NIR designation, and by the consequently wide variety of NIR tissue interaction mechanisms associate with each spectral region. Despite these obstacles, a comprehensive framework of NIR safety guidance now exists, but generally with less regulatory rigor and compulsion than for IR. Efforts to harmonize the exposure limits offered by various standard setting organizations have improved consistency, although disparities remain in some spectral regions.

ORGANIZATIONS INVOLVED IN IONIZING RADIATION PROTECTION RECOMMENDATIONS AND REGULATIONS

Sources of Guidance

The U.S. government relies on guidance from scientific organizations in the development of regulations. None of these organizations have any regulatory authority in the United States, but supply information and recommendations for the regulation-making processes. The most important organizations include the following:

International Commission on Radiation Protection (ICRP): an international organization founded in 1928 under the International Congresses of Radiology (currently called the International Society of Radiology) that occasionally establishes panels to review the published literature on an issue concerning radiation protection and make recommendations.

International Commission on Radiation Units and Measurements (ICRU): An international organization organized in 1925 also under the International Congresses of Radiology that, like the ICRP, occasionally establishes panels to review the published literature on an issue concerning radiation units, measurement or dosimetry, and make recommendations.

National Council on Radiation Protection and Measurement (NCRP): A committee organized in 1929 as an informal gathering of radiation scientists to represent radiation-related organizations in the United States, and then formally chartered by Congress in 1964. As with the two international commissions, the NCRP establishes panels and writes reports on radiation related topic, and serves as the main source for guidance to the US government in the formulation of radiation regulations.

International Atomic Energy Agency (IAEA): An agency of the United Nations, the IAEA provides guidance documents and expert consultation on radiation safety issues, particularly for developing countries.

United Nations Committee on the Effects of Atomic Radiation (UNSCEAR): A committee under the United Nations established in 1955 to study the biological effects of radiation. Periodically this committee publishes report on their findings.

National Academy/Board on Radiation Effects Research (BRER): The BRER was established in 1981 to coordinate activities of the National Research Council involving the biological effects of radiation. Periodically, the BRER establishes panels to review the literature on the Biological Effects of Ionizing Radiation (BEIR) and issue reports bearing that acronym.

Joint Commission on Accreditation of Healthcare Organizations (JCAHO): A commission established by many medical organizations, such as the American Hospital Association and the American Medical Association. The Joint Commission establishes some standards for the use of radioactive materials and radiation in medical settings. Their standards, as of this writing, tend to be broad and vague statements on quality.

Professional Organizations: Organizations of professionals that may make recommendations, guidance documents or standards for various aspects of their profession. Often these documents form the basis for regulations. Some of the major organizations that influence radiation regulations include: The American Association of Physicists in Medicine; The American College of Interventional Cardiologist/The American College of Cardiology; The American College of Medical Physics; The American College of Nuclear Physicians; The American College of Radiology; The American Nuclear Society; The Health Physics Society/American Academy of Health Physics.

International Electrotechnical Commission (IEC)/American National Standards Institute (ANSI): organizations that establish standards mostly pertaining to industry and manufacturers, their recommendations sometimes find their way into U.S. regulations aimed toward manufacturers of radiation-producing equipment.

Divisions of the U.S. Government Regulating Ionizing Radiation

In the United States, no one governmental agency regulates radiation and radioactive materials. Rather, aspects of radiation regulation fall under several agencies. Some of the major agencies are listed below, although the list is not exhaustive.

Nuclear Regulatory Commission. The Nuclear Regulatory Commission(NRC) is headed by a five-member Commission appointed by the President. The authority for the NRC comes from the Atomic Energy Act of 1954 (as the Atomic Energy Commission), as amended. The NRC was established by the Energy Reorganization Act of 1974. Because of the historical development of radiation regulations, the NRC formerly only exercised control over reactors and reactor byproduct materials. Thus, naturally occurring radioactive material, radioactive materials produced in particle accelerators and machine produced radiation fell outside the purview of the NRC. By these acts, the NRC regulates:

Special nuclear material, which is uranium-233, or uranium-235, enriched uranium, or plutonium.

Source material, which is natural uranium or thorium or depleted uranium that is not suitable for use as reactor fuel.

Byproduct material, which is, generally, nuclear material (other than special nuclear material) that is produced or made radioactive in a nuclear reactor.

Most recently, the Energy Policy Act of 2005 extended NRC authority to include naturally occurring and accelerator-produced radioactive materials (NARM). Before this time, the individual States regulated NARM with a somewhat non-uniform array of regulations.

The relevant NRC rules governing the authorized use of radioactive materials for medical applications are found in Title 10 Code of Federal Regulations. The specific divisions of Title 10 with a significant impact on medical uses are the regulations in Part 19—Notices, instructions and reports to workers: inspection and investigations; Part 20—Standards for protection against radiation; Part 21—Reporting of defects and noncompliance; Part 30—Rules of general applicability to domestic licensing of byproduct material; Part 31— General domestic licenses for byproduct material; Part 32— Specific domestic licenses to manufacture or trade certain items containing byproduct material; Part 33— Specific domestic licenses of broad scope for byproduct material; Part 35— Medical use of byproduct material; Part 71— Packaging and transportation of radioactive material.

The rules in Part 19, Part 20, and, most of all, Part 35 dominate the daily activity of medical licensees (2–5).

Since the late 1990s, NRC regulation changes have been performance-based rather than risk-based only. This was largely in response to the wide criticism by the medical community of regulations and enforcement activity. This resulted in an Institute of Medicine–National Academy of Science report (6) that made several recommendations for improvement to the agency, and the subsequent NRC Strategic Assessment and Rebaselining Initiative. These initiated a major revision of the medical use rules of Part 35 (2). The NRC regulations attempt to protect workers and patients while minimizing its imposition on the practice of medicine. The last major change was completed in March 2005 that addressed training and experience of users, which demonstrates the lengthy federal rulemaking process (5).

Department of Transportation. The Department of Transportation (DOT) regulates (in Title 49 of the Code of Federal Regulations) shipping or carrying radioactive materials, be it by air or surface, including any radioactive materials on public streets or highways.

Environmental Protection Agency. The Environmental Protection Agency (EPA) regulates the allowed levels of radioactive materials in the air, water, and landfills, as well as radiation exposures to the public outside nuclear power reactors. In some cases their regulations also covers occupational exposures to radiation. The rules enforced by the EPA do not all come from a single section of the Code of Federal Regulations.

Department of Energy. The Department of Energy (DOE) is charged with leading the energy development in the United States. A large part of their work involves reactors, and for DOE funded projects and facilities, particular radiation regulations apply.

Department of Defense. The Department of Defense (DOD) establishes radiation regulations for DOD facilities.

Food and Drug Administration. Department of Health and Human Services (DHHS) enters into the radiation regulation field mostly through one of its 10 agencies, the Food and Drug Administration (FDA). The FDA is responsible for protecting the public health by assuring the safety, efficacy, and security of human and veterinary drugs, biological products, medical devices, our nation's food supply, cosmetics, and products that emit radiation, either ionizing or nonionizing. Accordingly, by Title 21 of the Code of Federal Regulations, Food and Drugs, Revised April 1, 2004, the FDA approves and regulates the testing, manufacture, and approved use of a radioactive drug, also called radiopharmaceutical, or a medical device containing a radioactive source. However, the radiation safety regulations of who is authorized to use such drugs or devices and the conditions for use are the responsibility of the NRC or its Agreement States. Regulations in Title 21 can be found on line at http://www.accessdata.fda.gov/scripts/cdrh/cfdocs/cfcfr/cfrsearch.cfm [5 October 2005]

Radiopharmaceuticals. Radiopharmaceuticals are used for diagnostic purposes such uptake, dilution, or imaging, or for therapy applications. The relevant FDA regulations applicable to approving a radioactive drug are found in 21CFR 200–680 (References to the Code of Federal Regulations are usually written with the number of the Title before "CFR" followed by the part number, so this reference is Title 21 of the Code of Federal Regulations, Parts 200 through 680.):

Subchapter C—Drugs: General
- Part 201: Labeling
- Part 211: Current Good Manufacturing Practice for Finished Pharmaceuticals

Subchapter D—Drugs for Human Use
- Part 310: New Drugs
- Part 312: Investigational New Drug Application
- Part 361: Prescription Drugs for Human Use Generally Recognized as Safe and Effective and Not Misbranded: Drugs Used in Research

Subchapter F—Biologics
- Part 600: Biological Products: General
- Part 601: Licensing
- Part 610: General Biological Products Standards
- Part 660: Additional Standards for Diagnostic Substances For Laboratory Tests

A rapidly increasing aspect of nuclear medicine is the use of radioactive drugs employing positron emitters for diagnostic imaging. Positron emitters have a physical characteristic of very short half-lives (less than a few hours). The dominant radiopharmaceutical is F-18 tagged to fluorodeoxyglucose (FDG). They are used to perform positron emission tomography (PET). A problem with the production of PET drugs is meeting the FDA current good manufacturing practices (CGMP) regulation, which ensures that PET drug products meet safety, identity, strength, quality and purity requirements. The cause is their short half-lives prevent completing the current good manufacturing practices (CGMP) in a manner to allow distribution and administration. Current good manufacturing practices (CGMP) covers items such as control of ingredients used to make drugs, production procedures and controls, recordkeeping, quality system and product testing. The FDA and professional societies, such as the Society of Nuclear Medicine, are working to achieve a resolution. (http://www.fda.gov/cder/regulatory/pet/default.htm).

Machines and Devices. It is the responsibility of the FDA to determine if a submission is a device or a drug. With the increasing complexity and miniaturization of technology this is becoming increasingly difficult. Nevertheless, the FDA must approve any device that will be used on–in humans. Examples of such radioactive medical devices are high dose rate (HDR) remote afterloaders, intravascular brachytherapy devices, and radioactive-liquid filled balloons for the treatment of brain tumors. In addition, either the NRC or an Agreement State must perform engineering and radiation safety evaluations of the ability of the device to safely contain radioactivity under the conditions of their possession and use. If deemed satisfactory, the regulatory authority issues a registration certificate. The evaluations are summarized in the registration that the NRC maintains in the National Sealed Source and Device Registry (NSSDR). The registration certificates contain detailed information on the sources and devices, such as how they are permitted to be distributed and possessed (specific license, general license, or exempt), design and function, radiation safety, and limitations on use. Either the NRC or Agreement States can issue a registration certificate for distributors and manufacturers within their jurisdiction, but only the NRC is responsible for devices distributed as exempt products (i.e., smoke detectors) and issues those registration certificates.

Analogous to drugs, the Radiation Control for Health and Safety Act of 1968 established the requirements and responsibility for the FDA to administer an electronic product radiation control program to protect the public health and safety. As part of that program, FDA has authority to issue regulations prescribing radiation safety performance standards for electronic products, most importantly including diagnostic X-ray systems. This gives the FDA the authority to promulgate regulations on the manufacture and assembly of such machines. Again, it is the individual state that regulates who can operate such machines and the radiation safety conditions of use. The exception to this is diagnostic mammography. For mammography, under the Mammography Quality Standards Act (MQSA) of 1992, the FDA approves the accrediting bodies that accredit the facilities to be eligible to perform screening or diagnostic mammography services. It also establishes minimum national quality standards for mammography facilities to ensure safe, reliable, and accurate mammography. These standards address the physician interpreters, the radiologic technologists performing the imaging, the medical physicists performing the testing, and machine performance and testing for mammography *only*. The Center for Devices and Radiological Health (CDRH) is the agency within the FDA that has responsibility for radiation machines and machines (http://www.fda.gov/cdrh/). The relevant FDA regulations applicable to the manufacture and performance of radiation machines are found in 21 CFR 900-1050:

- Subchapter I—Mammography Quality Standards Act (MQSA)
  - Part 900-Mammography
- Subchapter J-Radiological Health
  - Parts 1000–1050

For radioactive pharmaceuticals, implantable radioactive sources, radiation producing machines, or computer software that may be used with humans, approval must first be obtained by the vendor from the FDA. Before such approval, any use must be performed under an Investigational Drug Exemption (IDE) from a facility's Institutional Review Board (IRB), and if the drug or device poses significant risk, by the FDA also. After demonstration of the safety of the investigational drug or device, the FDA may approve general use following the manufacturer's instructions as given in the premarket approval (PMA) documentation. Use other than as described is considered "off-label," and, while allowed, imposes increased liability on the institution should something go wrong.

Occupational Safety and Health Administration. The Occupational Safety and Health Administration (OSHA) administers the Occupational Safety Health Act to assure safe and healthful working conditions. The health standard 29CFR 1910.1096 governs employee exposure to ionizing radiation from X-ray equipment, accelerators, accelerator-produced materials, electron microscopes, betatrons, and technology-enhanced naturally occurring radioactive materials not regulated by the NRC (7,8). The OSHA encourages states to develop and operate their own programs, which OSHA approves and monitors.

Their rules have not been revised since 1971 (9). and essentially reflect the NRC regulations at that time. At the time of writing, OSHA is considering revising its regulations.

States. Regulation of radioactive materials and radiation producing machines that are not covered by any federal rules fall to the individual states to regulate. However, the states often enter into agreements with federal agencies to assume the federal regulatory role. This is discussed in greater detail in the section on Regulatory Standards for Radioactive Byproduct Material.

Conference of Radiation Control Program Directors. There is one organization that needs to be noted especially with regard to the establishment of regulations by the individual states. This organization is the Conference of Radiation Control Program Directors (CRCPD). In the early 1960s many states were developing radiation control programs. Such programs included, but were not limited to, regulating the use of diagnostic and therapeutic X ray, environmental monitoring, and regulating the use of certain radioactive materials including NARM. Simultaneous to the development of these early state and local radiation control programs were similar activities at the federal level. Many of these and varied state, local, and federal programs and activities in radiation control were being developed independent of each other.

A need for uniformity was identified to avoid inconsistencies and conflicts of rules and regulations throughout the country regarding radiation users. As a result, the CRCPD was established in 1968 to (*1*) serve as a common forum for the many governmental radiation protection agencies to communicate with each other; and (*2*) promote uniform radiation protection regulations and activities. To achieve these purposes, the CRCPD developed the Suggested State Regulations (SSR) for radiation control, which it regularly updates as federal or industry changes occur at its websitw (10). The SSR address both radioactive materials and radiation machines in medicine and industry. Although the SSR are only recommendations, their importance is that many states have, and continue to, adopt them as their state regulations giving them the force of law. These suggested rules are discussed in detail below. The primary membership of CRCPD is radiation professionals in state and local government who regulate the use of radiation sources. But it works closely with all relevant federal agencies, (NRC, FDA, DOT, EPA, etc).

U.S. Divisions Regulating Nonionizing Radiation

The key U.S. government agencies involved in regulating NIR are listed in Table 1. U.S. regulatory guidance specifically addresses some kinds of NIR sources in some spectral regions while omitting direct mention of other sources and spectral regions. For example, Curtis (11) acknowledges that the exposure standards in the OSHA are dated, noting the following weaknesses: the construction industry standard does not include laser classification and controls; the radio frequency (RF) exposure limit is from the 1966 ANSI standard (it has no frequency dependence and does not address induced current limits); The RF Safety Program Elements are incomplete.

However, the obligation of employers under the General Duty Clause of OSHA [Occupational Safety and Health Act of 1970, 29 USC 654, section 5(a)(1)] to protect workers from recognized hazards compels the control of all potentially harmful NIR hazards, whether specifically regulated or not. Various government agencies also provide a wealth of guidance beyond the requirements specified in the regulations. As noted in Table 1, the FDA regulations apply primarily to manufacturers, so although much FDA guidance clearly pertains to the end users, the FDA typically does not inspect healthcare providers or enforce compliance with FDA guidance by healthcare facilities. However, other organizations that do routinely audit healthcare providers, including in particular the JCAHO, refer to and hold hospitals accountable for compliance with FDA guidance. Table 2 summarizes the requirements of those states having comprehensive laser safety regulations, adapted and updated from Ref. (12). Many of these states have also passed regulations for the control of other NIR hazards as well (see e.g. Article 14 in Chapter 1 of Title 12, Arizona Administrative Code). Several nonregulatory organizations have established exposure limits covering the entire NIR spectrum. The primary industry consensus

Table 1. U.S. Government Agency Nonionizing Radiation Regulations

Agency	Role	NIR Related Regulations/Guidance	Created by
FAA	Responsible for the safety of civil aviation; includes the safe and efficient use of navigable airspace	14cfr91.11: prohibits interference with aircrew FAA Order 7400.2 Part 6 Chapter 29 [Outdoor Laser Operations]; limits laser exposure levels near airports	Federal Aviation Act (1958)
FCC	Responsible for regulating interstate and international communications by radio, television, wire, satellite, and cable	To comply with the National Environmental Policy Act of 1969 (NEPA), established limits for Maximum Permissible Exposure (MPE) to RF radiation based on NCRP and ANSI/IEEE criteria, in 1996 Report and Order, and 1997 Second Memorandum Opinion and Order. In addition, per 47cfr18, industrial, scientific, and medical equipment manufacturers must comply with requirements designed to reduce electromagnetic interference	Communications Act (1934)
FDA and CDRH	Protecting the public health by assuring the safety, efficacy, and security of human and veterinary drugs, biological products, medical devices, our nation's food supply, cosmetics, and products that emit radiation	The following regulations apply primarily to manufacturers: 21cfr1040.10 and 11—laser products 21cfr1040.20—sunlamp products and ultraviolet lamps intended for use in sunlight products 21cfr1040.30—high intensity mercury vapor discharge lamps. 21cfr1030.10—microwave ovens	Food and Drugs Act (1906)
OSHA	Ensure the safety and health of America's workers by setting and enforcing standards; providing training, outreach, and education; establishing partnerships; and encouraging continual improvement in workplace safety and health	29cfr1910.97 nonionizing radiation 29cfr1910.268 telecommunications	Occupational Safety and Health Act (1970)

Table 2. Representative Sample of State Laser Regulations[a]

State	Regulation	Exemptions	Training Required	Warning Signs Required	Controls Required	Registration Required	ANSI or FDA Based	Outdoor or Light Show Requirements
AK	18AAC35, Art. 7, Sec. 670-730	Stored, Inoperable, Enclosed and below MPE (e.g., Class 1)	No	Yes	Yes	No	No	Yes
AZ	AAC Title 12, Chpt. 1, Article 14, Sec. R12-1-1421-1444	None, but focus on control of Class 3b and 4	Yes	Yes	Yes	Yes	ANSI/FDA	Yes
FL	FL Code: Chap. 64-E4	Stored, Class 1, 2, and 3a	Yes	Yes	Yes	Yes	ANSI/FDA	Yes
IL	Chapter 420 ILSC 56	Transported, negligible hazard	No	No	No	Yes	FDA	No
MA	105 CMR 121	Transit and storage	Yes	Yes	Yes	Yes	ANSI	Yes
NY	Title 12 NYCRR Part 50	Non-R&D Class 1, 2, and 3a	Yes	Yes	Yes	Yes	FDA	Yes
TX	Title 25 TAC Part 1 Rule 289.301	Transit, stored, inoperable	Yes	Yes	Yes	Yes	ANSI/FDA/IEC	Yes
WA	WAC 296-62-09005	None, but focus on control of Class 3b and 4	Yes	Yes	Yes	No	ANSI/FDA	No
HI	HAR 12-201-3	None	Yes	Yes	Yes	No	No	Yes

[a] Adapted and updated from Ref. 12.

standard organizations and international standard-setting agencies appear in Table 3. Some of these voluntary standards carry more weight than others, especially internationally. For example, all member countries of the European Union are required to adopt the laser safety standard, IEC/EN 60825-1, of the International Electrotechnical Commission (IEC), which has also been adopted by Japan, Australia, Canada, and nearly every other nation that publishes a laser standard (13). In addition, the FDA now accepts conformance with the IEC/EN 60825-1 in lieu of conformance with most (but not all) of the requirements of the U.S. Federal Laser Product Performance Standard (14). Similarly, the FDA, OSHA, and JCAHO all reference the ANSI Z136 series of standards.

REGULATORY STANDARDS FOR RADIOACTIVE BYPRODUCT MATERIAL

Use of IR in medical, dental, and veterinary facilities is governed by either federal (e.g., NRC, OSHA) or state regulations. The NRC, drawing its authority from the Atomic Energy Act of 1954, regulates byproduct material, source material, and special nuclear material, and their uses. Here OSHA controls IR sources (X-ray equipment, accelerators, accelerator-produced materials, electron microscopes, betatrons, and technology-enhanced naturally occurring radioactive materials) not covered by the Atomic Energy Act of 1954 and not regulated by the NRC. A 1989 "Memorandum of Understanding..." defined responsibilities and authorities of each agency (7). Each agency has arrangements with some states for regulatory enforcement. NRC has an Agreement State Program, by which a State can sign a formal agreement with the NRC to assume NRC regulatory authority and responsibility over certain byproduct, source, and small quantities of special nuclear material. There are 33 States, listed in Table 4, with two (Pennsylvania and Minnesota) in the process of becoming Agreement States. The Atomic Energy Act of 1954 provides a statutory basis under which NRC relinquishes to the states portions of its regulatory authority to license and regulate byproduct materials (radioisotopes); source materials (uranium and thorium); and certain quantities of special nuclear materials. The mechanism for the transfer of authority to a state is an agreement signed by the Governor of the State and the Chairman of the Commission. The NRC has established compatibility obligations with the Agreement State regarding its current rules and future regulations that it may promulgate. Because two-thirds of the states have assumed Agreement status, the NRC has provided them increasing voice in their activities. This is done through the NRC Office of Tribal and State Programs and the independent Organization of Agreement States (OAS). Both can be accessed via the URL, http://www.nrc.gov/what-we-do/state-tribal/agreement-states.html. The NRC regulations apply in federal facilities directly holding federal licenses and in the nonagreement states. Agreement states have certain periods (3 years or more) within which state regulations must become compliant, at certain levels of compliance, with NRC regulations. During this transition period state regulatory agencies enforce their current state regulations, based on NRC regulations in force prior to the regulatory changes, as they prepare new state regulations compliant with the recent revisions changes in federal codes. Twenty-six states, also in Table 4, have OSHA-approved state plans with their individual state standards and enforcement policies.

Table 3. Selected Organizations Publishing Voluntary NIR Safety Standards

Organization	Role	Significant NIR Standards
American Conference of Governmental Industrial Hygienists (ACGIH)	Professional society devoted to the administrative and technical aspects of occupational and environmental health	TLVs and BEIs (Threshold Limit Values for Chemical Substances and Physical Agents; Biological Exposure Indices)
American College of Radiology (ACR)	Maximize radiology value by advancing science, improving patient care quality, providing continuing education and conducting research	White Paper on MR Safety
American National Standards Institute (ANSI)	Promoting and facilitating voluntary consensus standards and conformity assessment systems	Z136.1—Safe Use of Lasers Z136.2—Safe Use of Optical Fiber Communication Systems Utilizing Laser Diode and LED Sources Z136.3 Safe Use of Lasers in Health Care Facilities Z136.5 Safe Use of Lasers in Educational Institutions Z136.6 Safe Use of Lasers Outdoors B11.21 Machine Tools Using Lasers—Safety Requirements for Design, Construction, Care and Use ANSI/IESNA RP-27.1 Recommended Practice for Photobiological Safety for Lamps and Lamp Systems—General Requirements; RP-27.3 Risk Group Classification and Labeling ANSI/IEEE 95.6 Safety Levels With Respect to Human Exposure to Electromagnetic Fields, 0–3 kHz ANSI/IEEE C95.1 Safety Levels with Respect to Human Exposure to Radio Frequency Electromagnetic Fields, 3 kHz–300 GHz
International Commission on Non-Ionizing Radiation Protection (ICNIRP)	Disseminate information and advice on the potential health hazards of exposure to nonionizing radiation to everyone with an interest in the subject	Guidelines on Limits of Exposure to Ultraviolet Radiation of Wavelengths Between 180 nm and 400 nm (Incoherent Optical Radiation) Guidelines on Limits of Exposure to Laser Radiation of Wavelengths between 180 nm and 1 mm Revision of the Guidelines on Limits of Exposure to Laser radiation of wavelengths between 400 nm and 1.4 μm Guidelines on Limits of Exposure to Broad-Band Incoherent Optical Radiation (0.38–3 μm) Guidelines for Limiting Exposure to Time-Varying Electric, Magnetic, and Electromagnetic Fields (up to 300 GHz) Guidelines on Limits of Exposure to Static Magnetic Fields
International Electrotechnical Commission (IEC); European Committee for Electrotechnical Standardization. (CENELEC)	Prepares and publishes international standards for all electrical, electronic and related technologies; these serve as a basis for national standardization and as references when drafting international tenders and contracts	60601-2-33: Particular Requirements for the Safety of Magnetic Resonance Equipment for Medical Diagnosis 60825-1: Equipment Classification, requirements, and user’s guide 60825-2: Safety of Optical Fibre Communication Systems 60825-3: Guidance for laser displays and shows 60825-4: Laser guards 60825-5: Manufacturer’s checklist for IEC 60825-1 60825-6: Safety of products with optical sources, exclusively used for visible information transmission to the human eye 60825-7: Safety of products emitting infrared optical radiation, exclusively used for wireless ’free air’ data transmission and surveillance 60825-8: Guidelines for the safe use of medical laser equipment 60825-9: Compilation of maximum permissible exposure to incoherent optical radiation 60825-10: Application guidelines and explanatory notes to IEC 60825-1 60825-12: Safety of Free Space Optical Communication Systems used for the Transmission of Information TR60825-14: A User’s Guide

In a few instances, the DOE operates research programs at national laboratories under DOE supervision and governs occupational exposure under 10CFR 835 (Occupational Radiation Protection). Because of its limited role, DOE regulations are not further discussed. Table 5 lists the web sites of these federal agencies and other organizations with interests in regulation of radiation in its many forms.

Table 4. NRC Agreement States[a] and States, Commonwealths, and Territories[b] with OSHA-Approved State Plans[c]

Alaska (O)	**Iowa** (A,O)		
Alabama (A)	Kansas (A)	***New Hampshire (A)***	Rhode Island (A)
Arizona(A,O)	**Kentucky**(A,O)	New Jersey (O)	**South Carolina** (A,O)
Arkansas (A)	Louisiana (A)	**New Mexico**(A,O)	**Tennessee**(A,O)
California(A,O)	Maine (A)	***New York***(A,O)[d]	Texas (A)
Colorado (A)	**Maryland**(A,O)	**North Carolina** (A,O)	**Utah**(A,O)
Connecticut (O)[d]	Massachusetts (A)	North Dakota (A)	Vermont (O)
Florida (A)	Michigan (O)	Ohio (A)	*Virgin Islands*(O)[d]
Georgia (A)	**Minnesota**(A[e],O)	Oklahoma (A)	Virginia (O)
Hawaii (O)	Mississippi (A)	**Oregon** (A,O)	**Washington** (A,O)
Illinois (A)	Nebraska (A)	Pennsylvania (A[e])	Wisconsin (A)
Indiana (O)	**Nevada** (A,O)	Puerto Rico (O)	Wyoming (O)

[a] Designated A.
[b] Designated O.
[c] Those that are both (A,O) are in bold print.
[d] These in italics have plans that cover public sector (State and local government) employment only.
[e] These are not yet agreement states, but have filed intent to become agreement states.

NRC Regulations—Summary of Changes to U.S. Regulations

The NRC has actively revised their governing regulations. The most recent revisions (4-24-02) were to four parts of the federal code: *10 CFR 19 (Notices, Instructions, and Reports to Workers; Inspections); 10 CFR20 (Standards for Protection Against Radiation); 10CFR32(Specific Domestic Licenses to Manufacture or Transfer Certain Items Containing Byproduct Material), and 10CFR35 (Medical Use of Byproduct Material)*(2–5). The Occupational Safety and Health Act enforces the terms of the OSHA promulgated in the federal code *29 CFR 1910.1096 (Ionizing Radiation)* which appear to date to 1970 (9). Indeed, current OSHA standards are based on original terms, definitions, and units historically used by the NRC in 1971, many of which were changed in the 2002 NRC revisions. While OSHA websites allude to potential code revisions under active internal review, none are posted for public comment. Hence, we focus on a synopsis of NRC revisions.

10 CFR 19 (Notices, Instructions, and Reports to Workers; Inspections). This long-standing regulation (2), with 14 sections, issued 12/18/1981, unrevised, remains in force. Table 6 lists seven important sections with brief comments about their content. Insuring that all current members of a constantly changing workforce receive initial and timely recurrent annual instruction is a significant regulatory compliance challenge for radiation safety officers (RSO) charged with their instruction.

10 CFR20 (Standards for Protection Against Radiation). These standards, consisting of 69 sections, are, with one exception, discussed later, mostly unchanged from the 5/21/1991 release (3). Tables 7a,7b lists 10 key headings with brief comments about their content.

Three sections, *10CFR20.1002/Scope; -0.1003/Definitions, and -.1301/Dose Limits for Individual Members of the Public* (4) were revised. 20.1002/Scope now states [conventional radiation units deleted] that "…limits in this part do not apply …to exposures from individuals administered radioactive materials (RAM) and released under §35.75…" 20.1003/Definitions adds "Occupational dose does not include…dose… dose… from individuals administered RAM and released under §35.75…" "Public dose does not include…dose… from individuals administered RAM and released under §35.75…"

20.1301/ Dose Limits for Individual Members of the Public now adds to the exclusion of dose from RAM in sanitary sewers, the following: "…does not exceed … 1 mSv in a year

Table 5. Useful Web Sites with Information About Radiation, Regulations, and Regulatory Issues

Agency	Internet Address, http://www.	Electronic Mail Address
Conference Radiation Control Program Directors	crcpd.org	Not given on web page
Department of Energy	energy.gov	Not given on web page
Department of Transportation	dot.gov	dot.commentsost.dot.gov
Environmental Protection Agency	epa.gov	Not given on web page
Food and Drug Administration	fda.gov	Not given on web page
Health Physics Society	hps.org	hpsBurkInc.com
Idaho State University	physics.isu.edu/radinf/rso toolbox	Not given on web page
International Atomic Energy Agency	iaea.org	official.mailiaea.org
International Commission on Radiological Protection	crp.org	scient.secretaryicrp.org
International Commission Radiation Units and Measurements	icru.org	icruicru.org
National Council on Radiation Protection and Measurements	ncrp.com	Not given on web page
Nuclear Regulatory Commission	nrc.gov	Not given on web page
Occupational Safety and Health Administration	osha.gov	Numerous information-specific links on web page

Table 6. Partial Contents of 10 CFR 19[a]

Section Major	Major contents of section
0.3/Definitions	Workers, licenses, restricted areas defined
0.11/Postings notices to workers	(a) Post regulations, (i) license and its conditions; (ii) operating procedures; (iii) violations; (b) Documents, forms must be conspicuous
0.12/Instructions to workers	Inform about: (a) storage, use RAM; (b) health protection problems; (c) procedures to reduce exposures; (d) regulations; (e) report conditions, violations; (f) response to warnings; (g) their exposures
0.13/Notification and reports to individuals	(a) Written exposure reports; (b) annual exposure reports per workers request; (c) other provisions not stated here
0.14/Presence of licensee's and workers representatives during inspections	(a) Licensee to allow inspections; (b) inspectors may meet workers; (c) reps may accompany inspectors during inspections; (d) other provisions not stated here
0.15/Consultations with workers during inspections	(a) Inspectors may consult privately with workers; (b) workers may consult privately with inspectors
0.16/Requests by workers for inspections	Workers may request inspections without retribution

[a]Notices, Instructions, & Reports to Workers; Inspections.

exclusive of the dose contributions from background radiation, from any medical administration to the individual, from individuals administered RAM and released under §35.75, from voluntary participation in medical research programs. . .”

Also, added: “. . .a licensee may permit visitors to an individual . . .to receive a radiation dose greater than . . . 1 mSv if 1. the radiation dose . . .does not exceed . . . 5 mSv and 2. the authorized users has determined *before the visit* that it is appropriate.”

Security of RAM is addressed in §20.1801. A new international and national concern is the security of byproduct sources in medical facilities. Most medical licensees have small (tenths of GBq) quantities of long-lived byproduct

Table 7a. Unchanged Components of CFR 20[a]

Section	Major contents of section
0.1101/Radiation Protection Program (RPP)	(a) RPP must be developed, documented, implemented, commensurate with extent and scope of licensed activities; (b) ALARA for occupational and public doses; (c) Annually review RPP content and implementation
0.120/Occupational Dose Limits Dose Equivalent (DE); Deep Dose Equivalent (DDE); Cumulative Dose Equivalent (CDE); Total Effective Dose Equivalent (TEDE)	(a) Annual TEDE 0.05 Sv; sum of DDE and CDE of organs 0.5 Sv; eye DE 0.15 Sv; shallow skin or extremity DE 0.5 Sv; (b) Excess DEs must be planned; (c) Other provisions not stated here
0.1208/Dose to an Embryo/Fetus	(a) 5 mSv dose to embryo/fetus, entire pregnancy, occupational exposure of mother; (b) Avoid variations in uniform monthly doses; (c) Dose is sum of DDE of mother and radionuclides in mother and embryo/fetus; (d) Other provisions not stated here
0.1502/Individual Monitoring of External/Internal Occupational Doses Cumulative Effective Dose Equivalent (CEDE)	(a) Those likely DE 10% of limits; (b) Those in high and very high radiation areas; (c) Those likely to receive CEDE of 10% from radionuclides; (d) Other provisions not stated here
0.1801/Security of radioactive materials	(a) Secure from unauthorized removal or access licensed material stored in controlled or unrestricted areas; (b) Licensed material not in storage shall have control and constant surveillance

[a]Standards for Protection Against Radiation.

Table 7b. Unchanged Components of CFR 20[a]

Section Major	Major contents of section
0.1901/Caution Signs	Radiation symbol (trefoil) color schema (magenta, purple, black) on yellow and design defined;
0.1904/Labeling Containers Radioactive Materials	(a) Containers of RAM must be marked either "CAUTION" or "DANGER", RADIOACTIVE MATERIAL; (b) Label must identify quantity, date, radiation levels, kind of material; (c) Remove/deface labels on empty containers
0.1906/Receiving/Opening Packages	(a) Package receipt and monitoring procedures; (b) Carrier notified if wipe test or radiation levels exceed limits; (c) Package opening procedures; (d) Other provisions not stated here
0.1501/Surveys and Monitoring	(a) Make necessary surveys; (b) Equipment used for surveys calibrated; (c) Excluding direct/indirect pocket dosimeters, NVLAP accreditation for badge processor
0.2001/Waste Disposal	(a) By transfer to authorized recipient; (b) By decay in storage; (c) By effluent release within limits; (d) Others provisions not stated here

[a] Standards . . .Protection . . .Radiation.

materials (^{137}Cs, ^{60}Co, etc.), ideal components for dispersal "dirty bomb". The IAEA has developed an action plan to combat nuclear terrorism (15,16). These international efforts likely will lead to new national and state regulations requiring greater security for radioactive sources.

Listed in Table 7b as unchanged is signage. Radiation areas and places or contains that hold radioactive materials must be posted as such. Fig. 1 shows a typical radiation area sign, and gives the criteria for each of the types of signs required.

The 10CFR32 (Specific Domestic Licenses to Manufacture or Transfer Certain Items Containing Byproduct Material) revisions (4-24-2002) are only notational bookkeeping, changing the paragraphs numbers and sections in Part 32 to correspond with the corresponding sections of the revised 10CFR35.



Figure 1. A typical "Caution: Radioactive Materials" sign. The wording on the sign follows the criteria: Rooms containing more than the quantity listed in Part 20 Appendix C–"CAUTION: RADIOACTIVE MATERIALS"; 2. Areas with exposure rates >0.05 mSv in 1 h, 30 cm from a source (or surface that radiation penetrates) – "CAUTION: RADIATION AREA" or "DANGER: RADIATION AREA" ; 3. Areas with exposure rates greater than 1 mSv in 1 h, 30 cm from a source (or surface that radiation penetrates) - "HIGH RADIATION AREA"; 4. Areas with exposure rates greater than 5 GY in 1 h, 1 METER from a source (or surface that radiation penetrates)– "GRAVE DANGER: RADIATION AREA"; 5. Areas where the derived air concentrations exceeds values in appendix B, to 20.1001–20.2401, or where an individual without respiratory protection could exceed, during the hours an individual is present in a week, an intake of 0.6% of the annual intake limit —"DANGER: AIRBORNE RADIOACTIVITY AREA".

Revisions in 10CFR 35 (Medical Use of Byproduct Material). With 126 sections, we focus only on those of direct interest or applicability to medical byproduct material. Tables 8a–e summarizes, using some shorthand notations, the major contents of the important sections. The bulk of regulatory changes relative to byproduct material occur in these sections.

Components of CFR 35 Applicable to All Forms of Brachytherapy (Tables 8a, b). A new term, Authorized Medical Physicist (AMP), and the training thereof, is defined, as well as types (low dose rate, LDR; pulsed dose rate, PDR; and high dose rate, HDR) of remote afterloading units (RAU), including medium dose rate (MDR). Mobile services and medical events are new additions. Roles of management, the RSO, and authorized users (AU) supervision of individuals are explained. Dose prescriptions, or written directives (WD) details and procedures are enumerated.

Table 8b notes source inventories are now at 6 month intervals. §35.75 explains new release criteria for patients (4). Some requirements for mobile medical services are in this section, as well as rules for decay-in-storage of RAM.

Some Components of CFR 35 (F) Applicable to Manual Brachytherapy (Table 8c). One major change is a requirement to decay output or source activities in 1% intervals. Another section adopts AAPM good practices, per various protocols, for quality assurance of therapy planning systems, as a regulation.

Some components of 10CFR 35 (H) for Photon-Emitting Remote Afterloaders (Tables 8d, e). In the nine sections, the most significant change is the requirements for MDR

Table 8a. Components of CFR 35 (A, B) Applicable to All Forms of Brachytherapy

Section	Major Contents of Section
0.2/Definitions	(a) Authorized medical physicist defined; (b) LDR, MDR, HDR, PDR defined; (c) Mobile medical service defined; (d) Medical event (no more misadministration's! explained; (e) Manual prescribed dose (total sources strength and time, or dose per WD) given; (f) Remote prescribed dose (total dose and dose per fraction per WD) given
0.24/Authority Radiation Protection Program	(a) Defines a stronger management role; (b) Defines and strengths RSO role
0.27/Supervision	Explains role of authorized user (AU) and supervised individuals with respect to process and procedures with RAM
0.40/Written Directives (WD)	(a) Written directives required or oral directives with 48 h for written; (b) HDR: radionuclide; site, fx dose, #fxs, total dose; (c) Others; before tmt: radionuclide; site, dose; before finish: # sources, total source strength and time (or total dose); revisions allowed during treatment.
0.41/Procedures...written directives	(a) ID patient; (b) administration per WD; (c) Check manual, computer dose calculations; (d) confirm console data
0.51/Training authorized medical physicist	(a) Board certifications; (b) degrees +1 year training + 1 y experience; (c) preceptor's written statement regarding training

Table 8b. Some Components of CFR 35 (C) Applicable to All Forms of Brachytherapy

Section	Major Components of Section
0.67/Requiremenst for possession	(a) Leak tests (5 nCi) before 1st use, 6 mos.; (b) exempt Ir-192 seeds in ribbons and unused sources; (c) 6 months. inventory
0.75/Release...patients containing...RAM	(a) OK if others TEDE $< 5\,\mathrm{mSv{\cdot}year^{-1}}$; (b) Instruction if others TEDE $> 1\,\mathrm{mSv/year}$;
0.80/Mobile medical services	(a) Facility agreement letters; (b) on-site, before use survey meter checks; (c) Post-treatment surveys; (d) possession licenses required for all sites
0.92/Decay in storage	(a) $T_{1/2} < 120$ day; decay to background level; (b) remove labels; keep records

Table 8c. Some Components of CFR 35 (F) Applicable to Manual Brachytherapy

Section	Major Contents of Section
0.404/Surveys after... implant and removal	(a) After implant; source accountability; (b) After source removal; keep records
0.406/Source accountability	(a) ...at all times...in storage and use; record
0.410/Safety instructions	(a) Initially, annually...to caregivers; (b) Size, type, handling, shielding, visitor
0.415/Safety precautions	(a) No room sharing with regular patients; (b) Post-room (RAM) and visitor limits; (c) Emergency equipment for source retrieval from or in patient
0.432/Source calibrations (post-10/24/04)	(a) Determine output or activity; (b) positioning in applicators per "protocols"; (c) decay outputs/activities at 1% intervals; keep records
0.433/Decay Sr-90 sources	Only AMP shall calculate decayed activity and keep records
0.457/Therapy-related computer systems	(a) Acceptance testing per "protocols"; (b) Source input parameters; (c) accuracy of dose/time at points; isodose and graphics plots; (d) localization image accuracy

Table 8d. Some Components of 10CFR 35 (H) for Photon. . .Remote Afterloaders

Section	Major Components of Section
0.604/Surveys of patients	Before releasing patient. . .survey patient and RAU to confirm . . .returned to safe
0.605/Installation, . . ., repair	(a) Certain source work, that is install, adjust, and so on, by licensed person; (b) For LDR RAU, licensed person or AMP can do certain source work; record
0.610/Safety procedures	(a) Secure unattended RAU; (b) only approved individuals present in room; (c) No dual operations; (d) written procedures for abnormal situations; posted copies; initial/annual instructions with drills; records
0.615/Safety precautions	(a) Control access with interlock; (b) area monitors; (c) CCTV/audio for all except LDR RAU; (d) for MPD/PDR an AMP and AU **or** operator-emergency response MD present at initiation and immediately available during treatments; (e) for HDR an AU and AMP physically present at initiation, but, during continuation, AMP and AU or operator-emergency response MD; (f) emergency equipment for unshielded source or source in patient.
0.657/Therapy-related computer system	(a) Acceptance testing per "protocols"; (b) Source input parameters; (c) accuracy of dose/time at points; isodose and graphics plots; (d) localization image accuracy; (e) electronic transfer to RAU accuracy

Table 8e. Some Components of 10CFR 35 (H) for Photon. . .Remote Afterloaders

Section	Major Contents of Section
0.630/Dosimerty system (DS) equipment	(a) Except for LDR RAUs, NIST/ ADCL calibrated DS; (b) 2 year and after service; or, (c) 4 year, if intercom pared with calibrated DS within 18–30 month.and $< 2\%$ change
0.633/Full calibrations (FC) of RAUs	(a) Before 1st use; at source exchanges and/or repairs to exposure assembly; (b) for $T_{1/2} > 75$ days, excluding LDR RAUs, quarterly; (c) LDR RAUs yearly; (d) FC: 5% output/1 mm positions, source retraction, timer accuracy/linearity; (e) tube lengths and functions; (f) quarterly autoradiographs of LDR RAU sources; (g) decay outputs/activities at 1% intervals; (h) FC and decay by AMP; keep records; for LDR RAU can use manufacturer's data for FC
0.643/Periodic spot-checks (SC) of RAUs	(a) For LDR RAUs, before 1st treatment; for other RAUs 1st use daily; (b) per WP by AMP; (c) AMP review by 15 day; (d) SC includes: interlocks, status lights, audio and CCTV, emergency equipment, source position monitors, timer, clocks, decayed source activity
0.647/Additional requirements. . .mobile RAUs	(a) Survey meter checks; (b) source inventory; (c) all 0.643 checks; (d) interlocks, status lights, radiation monitors, source positioning, before 1st use, simulated treatment at each address

and PDR units. Physicians other than AUs, trained in MDR and PDR operation, emergency procedures, and source removal, may work under the supervision of an AU. Note: We denote them as substitute authorized users (SAU). For the initial treatment, the AMP and AU *or* SAU must be present; during subsequent (continuation) treatments, the AMP, AU, *or* SAU must be *immediately available*. These requirements are less onerous than the prior requirements of the AU *always* being present during all treatments. Another section adopts AAPM good practices, per various protocols, for quality assurance of RAU therapy planning systems, as a regulation.

Requirements for dosimetry systems (DS), full calibrations (FC), and spot-checks (SC) are described, including those for mobile services.

Some Components of 10CFR35 (J)(Recognition of Specialty Boards). The 2002 revisions in 10CFR 35 did not address personnel training. On March 30, 2005, the NRC published the final rule (5) regarding specialty boards and personnel training. The rule identifies (on the NRC web site, *not* in the published rule) various approved specialty boards and describes pathways for approvals of RSOs, AMPs, authorized nuclear pharmacists, and physicians using many forms of byproduct materials. The rule offers multiple pathways by which individuals may achieve authorizations to perform various tasks or assume authorized titles, (e.g., RSO, AMP, authorized nuclear pharmacist, or physician authorized user). One pathway is the educational degree -> experience -> specialty examination -> certification path. Another pathway is the supervised experience -> preceptor statement path. For example, Table 9 shows five ways an individual, depending on their education, experience, and certification status, can qualify to be an RSO. This flexible approach offers individuals multiple pathways to achieve authorization, which maintaining the integrity of the approval process. For those not physicians, the education requirements are either (a) a bachelor or graduate degree in physical science, or, engineering or biologic science with 20 college credits in physical science, or, (b) a master's degree or PhD in physics, medical physics, or physical science, engineering, or applied mathematics. Experience requirements vary from 1 to 5 years depending on the authorization, and are shorter for those with higher degrees. Generally, experience must be gained under a certified medical physicist or authorized individual, and documented. Preceptors must document the successful completion of any structured training programs and attest to the individual's competency and ability to perform learned tasks independently. In some instances, structured didactic training programs including classroom and laboratory training are allowed. Table 10 show similar requirements for becoming an AMP or ANP.

Training requirements for physicians, Tables 11 and 12, generally offers physicians two options: Completing requirements for medical specialty board certification and passing a certification examination, or, completing a structured educational program with a specific number of classroom and laboratory hours and work experience. In some instances, a preceptor must provide a written statement attesting to the satisfactory completion of the requirements and to the individual's "...competency sufficient to function independently..." (5) In other instances, a certain number of cases must be performed. The classroom and laboratory training requirements are specific to each specialty. Tables 11 and 12 only broadly describe training requirements; details of each specialty training program as described in USNRC 2005.

Table 9. Training Requirements for Radiation Safety Officers

Person	Degree	Experience	Examination	Classroom Laboratory Training	Preceptor Statement	Special Training
(1) Radiation Safety Officer	*and* B or GD in PS; or, E or BS w 20 cc in PS;	*and* 5 or more years in HP including 3 years in AHP	*and* Passes Exam			
or, (2) Radiation Safety Officer	*and* M or PhD in P, MP, or PS, E, AM	*and* 2 years full-time training in MP under supervision by CMP, *or*, in CNM, by physician AU	*and* Passes Exam			
Or, (3) Radiation Safety Officer		1 year full-time RS under supervision by RSO		200 h in topical areas		
Or (4) Radiation Safety Officer	*and* is a CMP	*and* applicable experience			*and* has written attestation by preceptor	*and* training in RS, regulatory issues, and emergency procedures
or (5) Radiation Safety Officer	*and* is AU, AMP, or ANP on license	*and* applicable experience			*and* has written attestation by preceptor	*and* training in RS, regulatory issues, and emergency procedures

ANP = Authorized nuclear pharmacist; PS = Physical science; B = Bachelor's degree; CMP = Certified medical physicist; BS = Biological science; RS = Radiation safety; CC = College credits; AU = Authorized user; E—Engineering; CNM = Clinical nuclear medicine; GD = Graduate degree; MP = Medical Physicist; M = Master's degree; RSO = Radiation safety officer; Ph.D = Doctoral degree; AMP = Authorized medical physicist.

Table 10. Training Requirements for Authorized Medical Physicist and Nuclear Pharmacist

Person	Degree	Experience	Examination	Classroom Laboratory Training	Preceptor Statement	Special Training
(1) Authorized Medical Physicist	*and*; M or Ph.D . in P, MP, or PS, E, AM	*and* 2 years under supervision by CMP, *or*, . . .	*and* Passes			
or (2) Authorized Medical Physicist	*and*; M or Ph.D. in P, MP, or PS, E, AM	*and* 2 yrs in CRF under supervision by AU eligible physician	*and* Passes			
or (3) Authorized Medical Physicist	*and*; M or Ph.D. in P, MP, or PS, E, AM	*and* 1 year full-time training in MP and 1 year full-time experience by AMP eligible MP			*and* has written attestation of "competency and independency" by MP preceptor	*and* training in device operation, clinical use, and treatment planning systems
(1) Authorized Nuclear Pharmacist	Pharmacy; or, passed FPGEC exam	4000 h in nuclear pharmacy	*and* Passes			Current, active license
or (2) Authorized Nuclear Pharmacist				700 h in structured program with 200 h in topical areas	*and* has written attestation of "competency and independency" by preceptor ANP	

AM = Applied mathematics; ANP = Authorized nuclear pharmacist; PS = Physical science; CMP = Certified medical physicist; AMP = Authorized medical physicist; RS = Radiation safety; FPGEC = Frgn pharm.grad exam comm.; AU = Authorized user; CRF = Clinical radiation facility; E = Engineering; P = Physics; MP = Medical physicist; M = Master's degree.

Licensure. There are two categories of NRC licenses: General License and Specific License. General licenses have been issued for non-medical uses, such as fixed gauges containing sealed radioactive sources. Medical licenses are for specific uses of a licensed material in a medical program, for example, diagnostic nuclear medicine program. Specific licenses control manufacture, production, acquisition, receipt, possession, preparation, use, and transfer of byproduct material for medical uses. A Type A license of broad scope, often held by university medical facilities, exempts the licensee from certain requirements of a specific license, but requires the facility to assume responsibility by certain administrative processes for the radiation protection program. NRC license requirements, applications, renewals, amendments, notifications, exemptions, and issuances are described in *10CFR 35.11–19* (2). Licenses categories exists for the use of unsealed byproduct material for uptake, dilution, excretion studies without a written directive (§35.100), unsealed byproduct material for imaging and localization studies without a written directive (§35.200), unsealed byproduct material requiring a written directive (§35.300), manual brachytherapy sources (§35.400), sealed sources in teletherapy units, and stereo tactic radiosurgery units (§35.600), and for other uses of byproduct materials (§35.1000).

Some components of 10CFR 35 (L) (Record retentions) (Table 13). Table 13 summarize the duration (for license, for program, and for 5 and 3 years) requirements for the retention of records.

Some components of 10CFR35 (M) (Reports . . .Medical Events . . . Sources) (Table 14). The term *misadministration* is replaced with the term *medical event* (ME). The ME depends, in some cases, on the *difference* (presumably lower or higher) in delivered dose and prescribed dose (PD), and in other cases, in *exceeding* the PD. Moreover, the definitions are not in medical physics terms of absorbed dose in gray (Gy); rather, they are in health physics terms of effective dose equivalent (EDE), shallow dose equivalent (SDE), in sievert (Sv). Recall that in partial organ irradiation in health physics, organ or tissue weighting factors apply in calculating DE. As a brachytherapy ME will likely involve adjacent organs, some judgment may be required in deciding on the correct DE in an ME.

Table 14 summarizes the reporting of medical events; Reporting requirements are similar to pre-2002 regulations.

Transport

Every day thousands of packages containing radioactive material move via public transportation routes—roads, airplane, and railway. Of all the hazardous material shipments, it is estimated that ~1%, nearly 3 million packages annually, involve radioactive materials (17). These packages are needed for medicine, industry, and research.

Shipments can be made only to persons who are licensed by the Nuclear Regulatory Commission (NRC) or appropriate Agreement State to receive radioactive materials.

Table 11. Some Training Requirements for Physicians Using Sealed Sources and Medical Devices

Person	Certification Examination	Education	Experience	Laboratory Training	Preceptor Statement	Authorized User
(1) Physician (Manual brachytherapy and sources), *or,*	Passes examination by medical specialty board	3 year MR in Rad Onc				
(2) Physician (Manual brachytherapy and sources)		Structured educational program with 200 h topical classroom and laboratory and 500 h work experience	3 years clinical supervision by AU in Rad Onc		*and* has AU preceptor's written attestation of competency sufficient to function independently	
(1) Physician (Ophthalmic use Sr-90)		Active practice and 24 h classroom and laboratory training applicable to medical use of Sr-90,	*and* AU supervised clinical training		*and* has AU preceptor written certification of completed requirements *and* attestation of competency sufficient to function independently	
(1) Physician, dentist, or podiatrist (Sealed sources for diagnosis), *or,*	Passes examination by medical specialty board					
(2) Physician (Sealed sources for diagnosis)		8 h classroom and laboratory training applicable to medical use of Sr-90,		Has completed training in use of device for uses requested		
(1) Physician (RA, T, GSR units, TMD), *or*	Passes examination by medical specialty board	3-year MR in Rad Onc				
(2) Physician (RA, T, GSR units, TMD)		Structured educational program with 200 h topical classroom and laboratory and 500 h work experience	3 year clinical supervision by AU in Rad Onc		*and* has AU preceptor written certification of completed requirements *and* attestation of competency sufficient to function independently	

RA = Remote afterloader; MR = Medical residency; T = Teletherapy unit; AU = Authorized user; GSR = Gamma stereotactic radiosurgery Unit; TM = Therapeutic medical device

The shipment must be made in accordance with procedures established by the recipient. Prior to shipping radioactive materials, a copy of the recipient's radioactive materials license should be on file with the shipper's Radiation Safety Office to document what radionuclides, forms, and quantities the recipient is authorized to receive.

There are five categories of radioactive material packages. Development of the technical criteria for each packaging category is correlated to certain general and performance requirements. The categories include (1) excepted or limited quantity packaging; (2) type A packaging; (3) type B packaging; (4) industrial packaging; (5) fissile material packaging. All medical shipments occur in the first two categories. Figure 2 illustrates the "spectrum" of increasing package hazard with activity.

Both the Department of Transportation (DOT) and the Nuclear Regulatory Commission are responsible for the regulations governing a package containing hazardous materials that are intended for transport on public routes(18). The DOT regulations are found in 49 CFR 107, 172-178. The NRC regulations are found in Title 10 CFR Part 71. In 1979, the DOT and NRC agreed to a Memorandum of Understanding under which the DOT regulates Type A packages and below, carriers, and has authority for international shipments. The NRC regulates Type B and fissile packages, investigates incidents and accidents, and provides technical advise to DOT.

The transportation requirements were revised in October 2004 to bring U. S. standards into consistency with the latest international transportation safety regulations (19). The

Table 12. Some Training Requirements for Physicians Use of Radiopharmaceuticals

Person	Certification Examination	Education	Experience
(1) Physician (Uptake, Dilution, and Excretion Studies), *or*,	Passes examination by medical specialty board	Satisfies board education requirement	
(2) Physician (Uptake, Dilution, and Excretion Studies), *or*,		40 h topical classroom and laboratory	*and*, 20 h clinical supervised by AU
(3) Physician (Uptake, Dilution, and Excretion Studies)		Successfully completed 6 month NM training	
(1) Physician (Imaging and Localization Studies), *or*,	Passes examination by medical specialty board	Satisfies board education requirement	
(2) Physician (Imaging and Localization Studies), *or*		200 h classroom and laboratory training applicable to medical use and 500 h supervised work	*and* 500 h AU supervised clinical training
(3) Physician (Imaging and Localization Studies)		Successfully completed 6 month NM training	
(1) Physician (Therapy use Unsealed Byproduct Material), *or*,	Passes examination by medical specialty board	Satisfies board education requirement	
(2) Physician (Therapy use Unsealed Byproduct Material)		80 h topical classroom and laboratory	*and, c* linical supervision by AU for specific number of cases
Physician (Only I-131 for Hyperthyroidism, Thyroid Ca)		Special experience and 80 h classroom and laboratory training	*and*, c linical supervision by AU for specific number of cases
(1) Physician (Sealed Sources for Diagnosis), *or*,	Passes examination by medical specialty board	Satisfies board education requirement	
(2) Physician (Sealed Sources for Diagnosis)		8 h classroom and laboratory training	

international regulations follow the International Atomic Energy Agency (IAEA) report Safety Series ST-1-R, which most foreign countries have adopted (20). This is important because most radioactive materials for medical use are produced outside U.S. borders, for example sealed sources, ^{99}Mo/^{99m}Tc generators.

There are four essential elements that are the shipper's responsibility to properly providing packages for transport that contain radioactive, or any other hazardous, materials. These are proper containment, labeling/marking, documentation, and training. The major factors affecting these requirements for these elements are the radionuclide, physical form, and quantity (activity). The specific requirements for packaging containment, labeling, and documentation are in the relevant sections of 49CFR 172-177. This information can be found at the website http://hazmat.dot.gov.

Table 13. Some Components of 10CFR 35 (L) (Record Retentions)

Record Retention Requirement	Section
Duration of license	0.2024/RPP (b) RSO authority
Duration of program (device)	0.2610/Safety procedures for device
5 years	0.2041/Procedures for WP; 0.2026/RPP changes
3 years	0.2040/WDs;.2061/Meter calibrations; 0.2067/Leak tests and inventories; 0.2070/Surveys; 0.2075/Patient release; 0.2080/Mobile services; 0.2092/Decay in storage; 0.2310/Safety instructions; 0.2404/Implants and source removals;0.2406/Source accountability; 0.2432/Source calibrations; 0.2433/Sr-90 decays; 0.2605/RAU installation, repairs;0.2632/Full calibrations; 0.2643/Spot checks; 0.2647/Additional mobile records;

Table 14. Some Components of 10 CFR35 (M)[a]

Section	Major Contents of Section
0.3045/Report/notification medical event (excluding patient intervention) (1)	Dose differs from PD > 0.05 Sv EDE, 0.5 Sv organ/tissue and SDE skin, and, TD, *and*, TD delivered differs from PD by + 20% or falls outside PD range; or single fraction delivered dose differs from single fraction PD + 50%
0.3045/Report/notification medical event (excluding patient intervention) (2)	Dose *exceeds* 0.05 Sv EDE, 0.5 Sv organ/tissue and SDE skin, and, TD from wrong: (a) byproduct material; (b) administration route; (c) person; (d) treatment mode; (e) leaking source
0.3045/Report/notification medical event (excluding patient intervention) (3)	Excluding migrating permanent implant seeds, dose to skin/organ/tissue *other* than treatment site that exceeds 0.5 Sv organ/tissue and +50% dose expected from WD
0.3045/Report/notification medical event (excluding patient intervention) (3) (b)	Report any patient interventions producing permanent/physiological damage
0.3045/Report/notification medical event (excluding patient intervention) (3) (c, d)	Notify NRC next calendar day after ME with written report in 15 days; notify referring MD and patient unless referring MD chooses not to for medical reasons; details of reports omitted here
0.3067/Report leaking source	Report > 5 nCi removal contamination within 5 days

[a] Reports . . . Medical Events . . . Sources.


THE TRANSPORT PACKAGE ACTIVITY SPECTRUM
(With Packaging References)
THE TRANSPORT ACTIVITY
SPECTRUM
"Radioactive Material Definition
Not Regulated In Transport
Limited Quantities and Excepted Articles
Type A Quantities
Type B Quantities
Highway Route Controlled Quantity
Excepted packaging
Type A packaging
TYPE B PACKAGING

Figure 2. The "spectrum" of increasing radioactive package hazard with activity.

All shipments of radioactive material, with the exception of those containing very small, limited quantities must have labels bearing the word "Radioactive" and affixed to opposite sides of the outer package. There are three different labels: White-I, Yellow-II, or Yellow-III, as shown in Fig. 3. The criteria for the three labels are given in Table 15.

Training must be provided for those that prepare for transport, transport, or receive packages of hazardous materials. The training must be commensurate with the duties involved. For medical facilities, the training involves the proper receipt of radioactive packages and preparing packages for return to the vendor or manufacturer. For shippers, the training must be done at least every three years and be certified by the employer.

The receipt of labeled radioactive packages must be handled according to the procedures in NRC regulations (10 CFR 20.1906). This requires assessing radiation levels and removable contamination within 3 h of taking possession. Examples of returned packages are residual radiopharmaceuticals in syringes or vials from nuclear medicine studies or sealed sources after radiation therapy use. Any returned package must be prepared for transport in accordance with DOT requirements.

It is important to note that *anyone shipping radioactive materials must receive training from an approved program beforehand!*


RADIOACTIVE I
CONTENTS
ACTIVITY
7
RADIOACTIVE II
CONTENTS
ACTIVITY
7
RADIOACTIVE III
CONTENTS
ACTIVITY
7

Figure 3. Labels for radioactive packages based on the activity contents and radiation levels outside as given in Table 15.

Table 15. Shipping Label Criteria[a]

Label	Transportation Index, TI	Maximum Radiation Level on Surface, X
White–I	$\mathrm{TI} < 0.05$	$X < 5\ \mu\mathrm{Sv{\cdot}h^{-1}}$
Yellow–II	$0.05 \leq \mathrm{TI} < 1$	$5\ \mu\mathrm{Sv{\cdot}h^{-1}} \leq X < 500\ \mu\mathrm{Sv{\cdot}h^{-1}}$
Yellow–III	$1 \leq \mathrm{TI} < 10$	$500\ \mu\mathrm{Sv{\cdot}h^{-1}} \leq X < 2\ \mathrm{Sv{\cdot}h^{-1}}$
Yellow–III exclusive use of vehicle	$\mathrm{TI} \geq 10$	$2\ \mathrm{mSv{\cdot}h^{-1}} \leq X < 10\ \mathrm{mSv{\cdot}h^{-1}}$

[a] Transportation index $= 100$ the maximum reading in $\mathrm{mSv{\cdot}h^{-1}}$ at 1 m from the surface.

Disposal of Radioactive Material

Radioactive materials used in medicine can be solid, liquid, or gaseous. Some solids are specially encapsulated and called sealed sources. When the material is no longer useful or in a form or presence that is undesirable, the radioactive material is considered waste, and the licensee must dispose of it. All waste generated from medical use is categorized as low level radioactive waste. Depending on various factors, radioactive waste can be disposed by (1) decay-in-storage (DIS); (2). discharge into the environment (3) transfer for land burial; (4) return to the vendor/manufacturer.

Disposal by Decay-in-Storage. This is the dominant disposal method for radioactivity used in nuclear medicine. The container of radioactivity is stored and simply allowed to radioactively decay to background level. Currently, this disposal method is only available for radionuclides with a physical half-life <120 days. Depending on the size of the operations, the limiting factor with this method is adequate space for the waste volumes generated during the time that the waste is segregated to "decay". Shielding of the container(s) may be another consideration depending on the radiation levels involved from the waste during radioactive decay. Procedures must be developed to comply with 10 CFR 35.92 for the decay-in-storage (DIS) of waste. Release into the general medical waste stream requires that the radiation level be at background level when measured at the surface of the unshielded waste container. The survey meter or instrument used to measure the radiation level must be capable of detecting the radiation being emitted from the radionuclide(s) being stored.

Disposal into the Environment. In some circumstances, especially with medical research, the disposal of liquids into the sanitary sewer or by evaporative release to the atmosphere or the discharge of volatile gases may intentionally occur. This is permissible and safe providing that compliance is maintained with other regulations regarding toxic or hazardous properties of these materials.

Disposal in the sanitary sewer or into the atmosphere must comply with 10 CFR 20, Subpart K. The NRC release or discharge limits have a concentration and annual aggregate activity limit. Records of each release is kept, such that a periodic (at least annual) assessment can be performed to confirm compliance with release limits required in Part 20. These limits apply at the facility boundary of the radioactive material licensee. The release limits are radionuclide specific such that exposure or intake would not exceed the applicable occupational or general public dose limits. The current release limits are derived from the scientific basis presented in 1990 by the ICRP (21). Patient excreta containing readily dispersible forms of radioactivity are exempt from these release limits.

Waste from *in vitro* laboratory kits that use radioactive materials under a general licensed pursuant to 10 CFR 31.11 is exempt from waste disposal regulations. Radioactive labels must be defaced or removed, but there is no requirement to keep a record of release or make any measurement. A standard of good practice is to do a radiation survey of any general waste from an area where radioactive materials are used, such as a nuclear medicine radiopharmacy or an inpatient therapy room, to confirm that it is at background levels before release into the general waste.

Transfer for Burial. For some medical facilities, radioactive material may require disposal by transfer to a burial site because the volume of waste generated requires removal or the waste contains long-lived (>120 day half-life) items that cannot be decayed in storage. Medical facilities use a broker licensed by the NRC or Agreement State to receive the material. Packaging will follow instructions received from the broker and the burial site operator. Records of the transfer to the broker must be maintained to comply with 10 CFR 20. Because this is the most expensive means of disposal, most generators of waste also employ volume reduction, (e.g. compaction) to reduce costs.

At the time of writing, there are only three burial sites for low level radioactive waste in the United States Richland, Washington, Barnwell, South Carolina, and Tooele, Utah. All are commercially operated and regulated by the respective state. The facilities are designed, constructed, and operated to meet safety standards. The operator of the facility must also extensively characterize the site on which the facility is located and analyze how the facility will perform for thousands of years into the future. In 1985, the Low-level Radioactive Waste Policy Amendments Act gave the states responsibility for the disposal of their low-level radioactive waste by encouraging the states to enter into compacts that would allow them to dispose of waste at a common disposal facility. While most states have entered into compacts, but no new disposal facilities have been built since the Act was passed, or are any expected to be.

Since the 1985, the volume of medical low level radioactive waste shipped for burial has dropped dramatically because of the cost of disposal, employment of volume reduction methodologies, and the conversion to short half-life or nonradioactive agents.

Return Sources to the Vendor or Manufacturer. For solid or sealed sources especially, a viable means of disposal for a medial facility is return to the vendor or a manufacturer. This is common with items that have exceeded their useful activity or shelf-life, such as ^{99}Mo/^{99m}Tc generators or brachytherapy sealed sources (e.g., ^{192}Ir, ^{125}I) or quality control calibration sources (e.g., ^{57}Co, ^{153}Gd). For such package, the packaging, labeling, and surveys must comply with the instructions of the vendor/manufacturer and 10 CFR 71 (NRC) and 49 CFR 173 (DOT) regulations. Currently, there is no distinct time at which a sealed source might be considered waste. The licensee determines when a material is no longer usable and becomes considered part of the radioactive waste stream. For solid sources with >120 day half-life, because land burial is very expensive, many licensees choose to simply "store" sources under their control. Such sources require routine inventory and periodic leak-testing. The current standards for stored, *unused* sealed sources require inventory every 6 months and leak test within 10 years.

COMMUNICATIONS FROM THE NRC

The NRC issues to licensee's bulletins, directives, guidance's, information notices, newsletters, and regulatory summaries as new issues not covered in regulations arise and must be addressed. In some cases, these documents endure for many years, and may actually be incorporated by agreement states into their regulatory statutes.

Bulletins

Bulletins provide information to NRC licensees. Apparently there are no recent bulletins pertaining to medical Applications; the last one was in 1997 (22).

Directives

Directives appear in several forms. FC86-4, Revision 1—*Information Required for Licensing Remote Afterloading Devices*, a long-standing (1986) policy and guidance directive, explained the contents for NRC license applications for RAUs. While it is not current on the NRC web site, some states have adopted it, with some changes, into their licensing process for RAUs. FC83-20, Revision 2-*Facility Interlocks and Safety Devices for High, Medium, and Pulsed Dose-Rate Afterloading Units*, is not on the NRC web site. As the title implies, this release clarified the requirements for interlocks and safety devices. It appears that issues raised are addressed in the 2002 10CFR 35 revisions.

Guidances

Guidance's often discuss evolving technologies. For example, as intravascular brachytherapy developed, the NRC issued several guidance documents (23,24). These were necessary as the new 10CFR35 applies only to photon-emitting RAUs; beta-emitting RAUs fall into the emergent technology category evaluated on a case-by-case basis.

Information Notices

Information Notices advise licenses of recent concerns usually arising from medical events reported to the NRC. A recent notice discussed failures of HDR RAUs (25).

Newsletters

Newsletters, notable, Nuclear Materials Safety and Safeguards (NMSS), announce medical events and enforcement actions against those who violate regulations. A recent one reported on a hospital's failure "...to secure...licensed material..." (26).

Regulatory Summaries

Regulatory Summaries often clarify issues about the interpretation of regulations, such as the calibration measurements for brachytherapy sources (4).

Recent NRC Activities

Recent or current NRC activities are posted on the website www.nrc.gov. For those interested in commenting on proposed NRC regulations, a site, www.ruleform.llnl.gov, is available.

REGULATORY STANDARDS : OSHA

Tables 16–18 offer a limited synopsis of the major components of the OSHA regulations. As noted earlier, current enforceable OSHA regulations, *29 CFR 1910.1096 (Ionizing Radiation)*, dating from the 1970s, are now at variance with the recent NRC regulations.

A recent supporting statement (Fed Register [07/23/2004]) for information-collection requirement offers some insight into OSHA regulation terms, definitions, and their application.

As with the NRC, over the years OSHA has issued Directives, Standard Interpretations, and Compliance Letters regarding regulations. They are available on the website www.osha.gov.

While a few cover general radiation topics, most relate to non-medical (nuclear power plant) radiation issues. There appear to be no releases within the last 5 years that relate to medical uses of radiation under OSHA standards.

NONBYPRODUCT MATERIALS AND MACHINE-PRODUCED RADIATION

As noted above, the NRC was authorized only to oversee the use of fissile and byproduct material. Regulation of naturally occurring or accelerator produced radionuclides, or of radiation from machines fell to the individual states. Since every state develops their own regulations, the depth and coverage of those regulations very widely. Often, states with smaller populations and small nonfederal radionuclide programs tended to have less complete or in-depth regulations than states with larger populations and programs. Two developments have been working to change the wide variations in regulations between states.

Table 16. Partial Contents of 29 CFR 1910.1096(a), (b), and (c) of OSHA Regulations[a]

Section	Major Contents of Section
(a) Definitions—Radiation and areas	(1) Radiation; (2) Radioactive materials; (3) Restricted area; (4) unrestricted areas;
(a) Definitions—Quantities and equivalencies	(5) Dose; (6) Rad; (7) Rem; (1 R X or γ- ray; 1 rad X- or γ- ray or beta particle; 0.1 rad high energy proton; (8) Air dose
(a) Definitions—Neutron flux or equivalent	Neutron flux dose equivalency table
(b) (1) Exposure to employed individuals 18 years age or older in restricted areas (Rem/calendar quarter)	Whole body; Head and truck; active blood forming organs; eye lens, gonads: 1.25
	Hands and forearms; feet and ankles: 18.75 Skin of whole body: 7.5
(b)(2) Greater quarterly whole body doses allowed based on individual's age"N"	Whole body dose shall not exceed 3 rem per quarter *and* shall not exceed 5(N-18)
(b) (3) Exposure to employed individuals *under* 18 years age in restricted areas (Rem/calendar quarter)	Quarterly calendar dose limited to 10% of that allowed those 18 years of age
(c) Exposure of employed individuals 18 years age or older to airborne radioactive material in restricted areas shall not exceed	Limits in 10CFR Part 20 Table I, Ax.B (1971); for 40 h workweeks, 7 consecutive days; time proportionately applicable
(c) Exposure of employed individuals *under* 18 years age to airborne radioactive material in restricted areas shall not exceed	Limits in 10CFR Part 20 Table II, Ax.B (1971); for 40 h workweeks, 7 consecutive days; time proportionately applicable

[a] The use of conventional (old) units in this table reflects the fact that these regulations are outdated and lag behind the NRC regulations.

Agreement State Status

The first unifying factor is the growing trend toward agreement state status. An agreement state enters into an agreement with the NRC to take over for the NRC regulation and control of byproduct material. Before doing so, the state must demonstrate that the state regulations for byproduct material are compatible with those of the NRC. "Compatibility" varies based on guidelines from the NRC as to how important the NRC feels that the state regulations agree with the federal, according to the following scale (27):

A Basic radiation protection standard or related definitions, signs, labels or terms necessary for a common understanding of radiation protection principles. The State program element should be essentially identical to that of NRC;

B Program element with significant direct transboundary implications. The State program element should be essentially identical to that of NRC;

C Program element, the essential objectives of which should be adopted by the State to avoid conflicts, duplications or gaps. The manner in which the essential objectives are addressed need not be the same as NRC, provided the essential objectives are met;

D Not required for purposes of compatibility.

For example, occupational exposure limits fall under category A, requiring congruence between the state and federal regulations. On the other extreme, most application and recording regulations are left to the states' discretion. For the most part, the laxer categories are those with less impact. Thus, as states have adopted agreement status, the variation in regulations between states has decreased. Table 4 lists the agreement states as of 2005.

Conference of Radiation Control Program Directors

Established in 1968, the Conference of Radiation Control Program Directors (CRCPD) is an organization of representatives of state radiation control programs. The organization shares information useful to state radiation control agencies, and has educational meetings focused on topics of current interest to state regulators. The CRCPD also distributes to its members model state regulations, so when states revamp their respective radiation safety codes, they need not start from nothing(28). The contents of the model regulations are discussed below. Because many state agencies use these models as a guide for their radiation regulations, increasingly the various states' regulations have been converging. Still, many important aspects of regulations remain, for example, the allowed radiation limit to the general public. While most states follow the federal rules, some use more restrictive levels based (sometimes erroneously) on recommendations of the ICRP.

CRCPD Model Regulations

Since the CRCPD model program serves as the basis for many of the state rules, we will consider the provisions here for regulations dealing with ionizing radiation not from byproduct material. Because of the compatibility

Table 17. Partial Contents of 29 CFR 1910.1096(d) and (e) of OSHA Regulations

Section	Major Contents of Section
(d) (1) Definition of a survey	"An evaluation . . .radiation hazards. . .production, use, release, disposal, or presence . . .radioactive material or . . .radiation. . ."
(d) (2) Employer responsibility for monitors	". . .shall provide. . .personnel monitoring equipment. . ."
(d) (2) (i) 18 year age or older employee use of monitors in restricted areas;	". . .employeee . . .restricted areå likely to receive a quarterly dose $>$25% that in (b)(1); or, enters a high radiation area
(d) (2) (ii) *Under* 18 year age employee use of monitors in restricted areas	". . .employeee . . .restricted areå likely to receive a quarterly dose $>$5% that in (b)(1)
(d) (3) Personnel monitoring equipment	"e.g., film badges & rings, pocket chambers and dosimeters
(d) (3) Area definitions	Radiation area. . .could receive $>$5 mrem in any 1 h; or, $>$100 mrem in 5 consecutive days; High radiation area. . . could receive $>$100 mrem in any 1 h; Airborne radioactivity area. . .concentrations in excess 10CFR Part 20 Table I, column 1, Ax.B (1971)
(e) Caution signs, labels, signals	Radiation symbol(trefoil) described;
(e) (2) Radiation area posting	Radiation caution symbol with "Caution–Radiation Area"
(e) (3) (i) High radiation area posting	Radiation caution symbol with "Caution–High Radiation Area"
(e) (3) (ii) High radiation area control	". . .equipped with control device . . .cause radiation levels to be reduced $<$100 mrem in 1 h, or, . . .energize . . .alarm system. . . individual entering . . .supervisor. . .made aware of entry."
(e) (4) Airborne radioactivity area posting	Radiation caution symbol and "Caution–Airborne Radioactivity Area"
(e) (5) (i) Radioactive materials posting (excluding natural uranium or thorium)	Areas/rooms $>$10 times quantities in 10CFR Part 20 Apx.C (1971)
(e) (5) (ii) Radioactive materials posting for natural uranium or thorium	Areas/rooms $>$100 times quantities in 10CFR Part 20 (1971)
(e) (6) (i) Container labeling (excluding natural uranium or thorium)	Containers . . .transported, stored, used. . .$>$ quantities in 10CFR Part 20 Apx.C (1971). . .Radiation symbol and "Caution-Radioactive Materials"
(e) (6) (ii) Container labeling for natural uranium or thorium	Containers . . .transported, stored, used . . . $>$10 times quantities in 10CFR Part 20 Apx.C (1971). . .Radiation symbol and "Caution-Radioactive Materials"

The use of conventional (old) units in this table reflects the fact that these regulations are outdated and lag behind the NRC regulations.

requirement to become an agreement state, those parts of the CRCPD model regulations that deal with material under NRC oversight follow the federal rules as discussed above. Thus, these need not be considered here. The FDA does impose some requirements on the *manufacturers* of radioactive materials and radiation-producing machines intended for human use, but that leaves the *use* of machine-produced radiation and naturally occurring and accelerator-produced radionuclides only under the control of individual states.

The model regulations fall into many sections, with each section covering a particular part of radiation safety. General rules that apply to all applications and follow the NRC notably Parts 19 and 20 come in sections in the beginning. In addition to the general provisions, each of the parts that deal with particular applications all have sections addressing shielding and survey requirements for the modality (such that the radiation levels satisfy Part 20 limits), safety requirements for operation (such as door interlocks to prevent walking in during irradiation), ventilation if airborne radionuclide production is possible, record retention requirements and training and experience.

Machine-Produced Radiation

While much of machine-produced radiation is covered by state regulations, when used on humans applications manufacture of the units falls under the auspices of the FDA. The FDA rules can be found in 21 CFR 1020. For the most part, the state regulations follow the FDA guidances when applicable, but sometimes with a sizable delay.

Mammography forms a notable exception to the general lack of federal control over machine-produced radiation in medicine. Based on the MQSA, as noted above, the FDA sets requirements for practitioners on mammography, and failure to satisfy the requirements prevents providers from obtaining reimbursement from government sources. The requirements for mammography equipment are given below in the section on Diagnostic Units. In addition, there are considerable requirements placed on the training and experience of the persons involved: the radiologist, the radiographer, and the medical physicist [21 CFR 900.12 (a)].

Radiation producing machines fall into three main categories discussed in the following sections.

Table 18. Partial Contents of 29 CFR 1910.1096(f), (g), (h), (i), (j), and (k) of OSHA Regulations[a]

Section	Major Contents of Section
(f) Immediate evacuation warning signal	34 subsections regarding the signal characteristics, design, and testing requirements
(g) (i) Exceptions from posting requirements for sealed sources	Room/area with sealed source...not required...if radiation levels $< 5\,\mathrm{mrem{\cdot}h^{-1}}$ at 12 in from source container/housing
(g) (ii) Exceptions from posting requirements for rooms housing radioactivity patients	Rooms...not required to be posted...personnel in attendance who shall ...prevent individual exposure above limits
(g) (iii) Exceptions from posting requirements for rooms containing radioactive materials	Cautions signs not required for rooms containing radioactive materials for < 8 h and provided materials constantly attended...
(h) Exemptions for radioactive materials packaged for shipment	Radioactive materials packaged and labeled per DOT 49CFR Chp. I are exempt provided containers inside properly labeled
(i) (2) Instruction of personnel, postings	Individuals working in or frequenting any portion of a radiation area shall be informed of radioactive materials and radiation; instructed in safety...; instructed in applicable provisions of regulations...; advised of radiation exposure reports
(i) (3) Posing regulations and operating procedures	Employer...shall post...current copy of regulations and operating procedures
(j) Storage of radioactive materials	...shall be secured against unauthorized removal....
(k) Waste disposal	...by transfer to an authorized recipient...
(l) (i) Notification (immediate) of incidents	...any incident involving radiation which may have caused ...$>$ 25 rem whole body, 150 rem skin, or 375 rem to feet, ankles, hands, or forearms, or, release of radioactive materials $>$ 5000 applicable limits averaged over 24 h
(l) (ii) 2Notification (24 h) of incidents	...any individual ...5 rem or more total body; 30 rem skin, 75 rem to feet, ankles, hands, forearms,
(m) Reports of overexposure and excessive levels and concentrations	....written report in 30 days...to OSHA; notification of individual exposed
(n) Records	Advise employees of annual exposures; provide employees exposure records
(p) Definitions of agreement states	List of current agreement states

[a] The use of conventional (old) units in this table reflects the fact that these regulations are outdated and lag behind the NRC regulations.

Radiotherapy Units. Radiotherapy units consist of two major categories: orthovoltage X-ray units (i.e., conventional X-ray machines that treat with bremsstrahlung beams produced with tube potentials from 10 kVp to 300 kVcp) and those from accelerators (from electron beams with energies from 2 to 45 MeV). The regulations use as a diving line between the modalities a photon beam energy of 500 kV, which clearly delineates units since no machines currently in use run close to that specification. Table 19 lists the requirements for an orthovoltage unit, and Table 20 those for an accelerator.

Regardless of the machine type, the regulations require the output of the unit be determined using dosimeters calibrated at either the National Institute of Standards and Technology or at one of the Accredited Radiation Dosimetry Calibration Laboratories. The calibration procedure must follow a protocol established by a recognized national professional society. Also for either type of unit (except for contact therapy units), the facility design requires: the ability to monitor the patient aurally and visually; interlocks on the door to prevent entry during irradiation; beam-on indicators; and emergency power cutoffs by the control panel or door.

Radiography (Imaging) Units. Regulations for diagnostic radiographic units actually exceed those for the therapy units, even though the latter produce much greater quantities of radiation. Tables 21a,b and 22 give *highlights* of the regulations for radiographic and fluoroscopic units. The regulations also contain many points on how the specifications should be measured as well as cover other aspects not included in the tables. Table 21b gives values referred to in Table 21a. As an important factor in patient dose, the regulations also address exposure control for the various types of equipment.

In addition to the regulations for the radiographic and fluoroscopic units, there are also sections on radiotherapy simulators; computed tomography units; mammography units; mobile units; and veterinary units.

As noted above, mammography units have special requirements according to the MQSA. The requirements for these units are given in Table 23, and the special quality assurance requirements in Table 24. The quality assurance summary greatly simplifies the actual requirements, which have undergone some modifications to adapt better to various imaging systems and practice conditions. All persons involved in mammography, including the radiologist, radiographer and the medical physicist performing the quality measurements, must satisfy specific training and experience guidelines, as well as continuing education requirements.

Nonmedical Radiation-Producing Equipment. Nonmedical radiation producing equipment actually finds its way

Table 19. Requirements for Orthovoltage X-Ray Units

Leakage Radiation [air kerma rates]	< 1 mGy·h^{-1} 5 cm from housing
5–50 kV Systems	< 10 mGy·h^{-1} 1 m from target;
> 50 and < 500 kV Systems	< 300 mGy·h^{-1} 5 cm from housing
Permanent Beam Limiting Devices	Same attenuation as housing
Adjustable or Removable Beam Limiting Devices	Transmission $< 5\%$ of useful beam Opening indicated by light beam
Beam Filter System	Cannot be displaced Interlocked to prevent beam use with filter absent Slot provides same shielding as housing Filters clearly identified
Tube Immobilization	Cannot move when locked
Source Marking	Indicated to within 5 mm
Contact units beam blocking	Equivalent to 0.5 mm Pb at 100 kV
Timer	Unit has presetable timer and show elapsed or remaining time Retains reading with interruptions Terminates exposure after set time Precision of at least 1 s or 1% Prevents exposures with zero time Begins with shutter or is compensated for lags
Control Panel Functions	Displays indicate ac power, X-rays possible, X-rays on, shutter condition and tube potential and filter Termination button Locking device
Multiple Tubes	Only one used at a time Indication of which is in use
Target-to-Skin Distance	Accurate to within 1 cm, reproducible to within 2 mm
Shutters	Required if beam takes > 5 s to come on
Low Filtration X-ray Tubes	Permanent warning label

into medical application, for example, as cyclotrons making radioactive materials for imaging or analytic X-ray units to assess kidney stones. Much of the operation of such equipment would be covered by the general radiation safety provision of the regulations. Most of the additional rules deal with preventing the accidental irradiation of a person in a high radiation area.

Particle Accelerators (e.g., Cyclotrons). The main concern for a particle accelerator would be a staff member being in either the accelerator room or one of the rooms served by the beam lines. To prevent such occurrences, the rules require: interlocks on doors to prevent accidental entry with the beam on or inhibit the beam initiation with the door open; buttons to stop the beam from within the room; radiation-detector warning devices in the room; and hand-held Geiger counters carried when entering the room. The regulations also include the requirement for periodic testing of the safety devices to assure proper function.

Analytic X-Ray Units. The X-ray units covered under this heading usually are small devices (often fitting on a desktop), used for analysis of small samples, such as for crystallography or pathologic X rays of surgical samples. These devices are usually enclosed within a shielding box. While small, accidents that involve an operator's hand being in the box during beam production frequently lead to loss of fingers or hands. Thus, similarly to the particle accelerator, the rules try to keep hands out with the beam on, or prevent the beam if the doors are open. Rules include interlocks to prevent beam with doors open; warning lights indicating the status of the beam and shutters; and warning labels.

Nonbyproduct Radionuclides

State regulation of byproduct material must follow closely the NRC regulations. However, before the 2005 agreement, the states have been responsible originating their own regulations for NARM. Much of the suggested regulations (Part C) define quantities of NARM below regulatory concern. Table 31 gives a brief, and not nearly complete listing of some exemptions as examples. Appendix A of Part C of the suggested regulations gives air and water concentrations exemptions.

The regulations go on to exempt devices such as static eliminators containing less than specified amounts of radioactive materials (on the order of 20 MBq for heavy nuclides of 2 MBq for tritium). For clinical laboratories, small quantities of material (generally ~ 0.4 MBq except tritium at 1.85 MBq and ^{59}Fe at 0.7 MBq) used in assay kits and 1.85 MBq check sources are also exempt. The remainder of Part C addresses licensing and labeling. Medical use of radioactive materials is covered under Part G, which mostly mirrors the federal 10CFR35.

What is not clearly addressed in the model regulations is regulation on accelerator-produced radioactive materials. Some states have taken the tack that the same regulations

Table 20. Requirements for a Radiotherapy Accelerator

Leakage Radiation	Maximum < 0.2%, average < 0.1% useful beam −2 m radius of central ray at isocenter < 0.5% 1 m from electron path Neutron dose compliant with IEC standard
Collimator leakage	< 2% of useful beam for photon beams Maximum < 2%, average < 0.5% useful beam for electron beams, outside 7 cm of beam < 10% 2 cm outside of field
Filters/Wedges	Identification clearly marked Interlocked requiring selection Panel indicates wedge identification
Stray Radiation	Compliant with IEC standards
Beam Monitors	Redundant independent systems required Both systems show on control panel until reset Retrievable in case of power failures Count up
Beam Symmetry Monitor	Can detect asymmetry > 10% Terminates beam with asymmetries > 10%
Beam Control	Beam initiation requires monitor setting Preset displayed Reinitiation requires clearing of setting Monitor unit rate is displayed Provides termination for excess dose rate
Termination of beam	By monitor systems at respective preset Manually at panel By timer after preset time with reset necessary
Radiation selection	Type of radiation must be selected (if more than one available) Interlocks prevent simultaneous types Type displayed on panel Interlocks prevent inappropriate beam type and accessories Special mode allows X-rays for imaging with electron applicators
Energy Selection	Energy selection required Energy displayed on panel Interlock prevents beam without appropriate mechanical conditions
Stationary or moving beam	Selection required Mode indicated on panel Interlocks prevent beam in inappropriate condition
Moving beams	Beam controlled for dose per degree Interlocks stop beam if dose per degree off

Table 21a. Highlights of Requirements for All diagnostic X-Ray Units[a–c]

Warning label	Attached to the control panel containing main power switch
Battery charge indicator	Visual on control panel if relevant
Source leakage radiation	< 1 mGy/m^2 at maximum technique for 1 h
Radiation other than tube	< 20 μGy/h 5 cm
Half-value layer[d]	> values in Table 2dx including all material between tube and patient For variable filter units, control prevents incorrect selection
Multiple tubes	Selection of tube clearly indicated
Mechanical Support of the tube head	Hear remains stable during exposure (except dynamic studies)
Technique indication	Technique factors shown before exposure
Locks	Function properly

[a] Table by Tim Burns and Mark Geurts.

[b] For new units. Older units have some allowances made for regulations in effect at manufacture.

[c] Details for such units should be found in 21CFR1020 or in the particular state's regulations.

[d] Based in FDA regulations in 21CFR 1020.

Table 21b. Half–Value Layer Requirements

		Half-Value Layer in mm Aluminum	
Operating Range	Measured Potential, kVp	Diagnostic X-Ray Systems	Dental Intraoral
<51	30	0.3	N/A[a]
	40	0.4	N/A[a]
	50	0.5	1.5
51–70	51	1.2	1.5
	60	1.3	1.5
	70	1.5	1.5
>70	71	2.1	2.1
	80	2.3	2.3
	90	2.5	2.5
	100	2.7	2.7
	110	3.0	3.0
	120	3.2	3.2
	130	3.5	3.5
	140	3.8	3.8
	150	4.1	4.1

[a] Not available = NA.

apply to all radioactive materials regardless of their origin. Others recognize that most accelerator-produced radionuclides tend to have shorter half-lives, and therefore require less control. Thus, when dealing with accelerator-produced material, consultation with the particular state's regulations becomes imperative.

REGULATIONS FOR NONIONIZING RADIATION

Understanding and applying NIR regulatory standards and guidance requires careful attention to the spectral characteristics of the radiation source(s) involved. The situation is probably most clearly described by dividing

Table 22. Highlights of Requirements for Fluoroscopic Units[a–c]

Primary barrier	Primary barrier intercepts entire beam Transmission $\leq 0.2\%$
Beam limitation	Beam not exceed visible area by $>3\%$SID[d] Sum of excess $< 4\%$SID Beam < largest spot-film size Units with visible area $> 300\,\text{cm}^2$ shall have continuously adjustable collimators, down to $5 \times 5\,\text{cm}^2$, or, if fixed SID, to $125\,\text{cm}^2$
Spot-film beam limitation	Beam automatically limited to film size Beam adjustable to fields smaller than film size down to $5 \times 5\,\text{cm}^2$ Beam not exceed visible area by $>3\%$SID[d] Sum of excess $< 4\%$SID Misalignment of the centers of beam and film $< 2\%$ SID
Activation of fluoroscopy	Requires continuous press on switch Serial exposures may be terminated at any time
Entrance exposure rates	≤ 50 mGy/minute, except 1. if unit has no high mode for automatic exposure control (AEC) units, then $\leq 100\ \text{mGy}\cdot\text{min}^{-1}$; 2. during image recording
Indications	Panel shows kVp and mA during exposure
Source-to-skin distance	$\leq$38 cm for stationary units$\leq$30 cm for mobile units $\leq$20 for mobile, special surgical units
Fluoro timer	Maximum time without resetting $\leq$5 min Signals during fluoroscopy after time until reset
Control of scatter	Unit and table design prevent exposure of persons to scatter, except extremities, without ≥ 0.25 mm Pb equivalent attenuation or 1.2 m from beam

[a] Table by Tim Burns and Mark Geurts.

[b] For new units. Older units have some allowances made for regulations in effect at manufacture.

[c] Details for such units should be found in 21CFR1020 or in the particular state's regulations.

[d] SID is source to image intensifier distance.

Table 23. Characteristics of a Mammography System as Required by the Mammography Quality Standards Act

Item	Criterion
Type of equipment	Specially designed for mammography
Motion of tube-image receptor	Tube-image receptor may be fixed and remain so if power fails.
Image receptor size and grid	i. Screen-film units shall have a minimum of $18 \times 24\,\text{cm}^2$ and $24 \times 30\,\text{cm}^2$ and moving grids. ii. Magnification units can operate without the grid.
Light fields	Units with light fields shall have an average illumination of not less than 160 lux at 100 cm or the maximum source-image receptor distance, whichever is less.
Magnification	i. Units used for non-interventional problem solving shall have radiographic magnification capability ii. Units with magnification shall provide at least one magnification value between 1.4 and 2.0
Focal Spot selection	Unit indicates focal spot size and material selected prior to exposure, unless determined by algorithm during, where displayed after.
Compression	Unit shall have compression: i. power driven by hands-free controls on each side of the patient, including fine control;[a] ii. Compression paddle size shall match the full-field receptor size, and shall be level with the breast-support table to < 1 cm, except when designed otherwise; iii. The chest-wall edge shall be strain and parallel to the edge of the receptor, and may be curved for comfort if out of the field.
Technique factor selection and display	Has manual selection of mAs; ii. technique factors set display before exposure; iii. In automatic exposure control mode the technique used for the exposure displays afterwards.
Automatic exposure control (AEC)	i. Screen-film systems shall provide an AEC mode that is operable in all combinations of equipment; ii. positioning of detector shall permit flexibility in the placement under the target with the size and available positions of the detector marked on the input surface of the paddle, and the selected position of the detector indicated; iii. there shall be means to vary the selected optical density from the normal.
Film-Intensifying screens, if used	i. Film shall be designed for mammography; ii. screens shall be designed for mammography and the film used; iii. processing chemicals use as per manufacturer; iv. hot-lights and film masking devices shall be available;

[a] Applies to units built after 10/02.

NIR into three spectral regions: optical: ultraviolet (UV), visible, and infrared (IR); microwave RF; extremely low frequency (ELF) and static fields. The relationship between wavelength, frequency, and photon energy for these spectral regions is shown in Fig. 4.

Emission limits for specific optical sources combine with exposure limits to protect workers and the general public. These limits are further organized according to the type of source: lamps and other optical sources; and lasers. This separate consideration of non-laser sources and lasers necessarily reflects the different qualities of these sources. While lamps and other optical sources typically present a broad spectrum (i.e., the radiation is spread over many wavelengths) and widely divergent emission, lasers emit just one or at most a few discrete wavelengths in a very narrow, highly collimated beam.

The exposure limits for broad band non-laser optical sources are generally expressed in terms of some sort of spectral weighting scale to account for the fact that some wavelengths more efficiently cause injury than others. In the UV region, the International Commission on Non-ionizing Radiation Protection (ICNIRP) (29,30) and the National Institute for Occupational Safety and Health (NIOSH) (31) support the spectral weighting function and exposure limits set forth by the American Conference of Governmental Industrial Hygienists (ACGIH) (32) several decades ago. In this scheme, the weighting function is normalized to the peak of the spectral effectiveness curve at 270 nm, with an effective spectrally weighted limit of $30\,\text{J}\cdot\text{m}^{-2}$ over the region from 180 to 400 nm. Eye and skin exposure limits for monochromatic UV sources can be found in tables provided by ACGIH, ICNIRP, or NIOSH : The

Table 24. Quality Assurance Required for a Mammography System by the Mammography Quality Standards Act

	Daily Quality Control Tests for Film Systems
Film processor control	i. Base plus fog density within 0.03 of the established level; ii. mid-density on test strip within 0.15 of the established level; iii. density difference within 0.15 of the established level.
	Weekly Quality Control Tests for Film Systems
Phantom density and contrast	With approved phantoms, optical density$\geq$1.2 from typical exposure, varies < 0.2 from normal, passes imaging for phantom, and contrast changes < 0.05 with standard test.
	Quarterly Quality Control Test for Film Systems
Film fixer clearance	Residual fixer in film < 5 μgm·cm^{-2};
Reject analysis	Repeat or reject rate changes $< 2\%$ of the total films in analysis (otherwise determine the reason for change, corrective actions recorded and the results assessed).
	Semiannual Quality Control Tests for Film Systems
Darkroom fog	Darkroom fog shall not exceed 0.05 for 2 min exposure on the counter top
Screen-film contact	40 mesh screen on cassette shows no appreciable blurring.
Compression device performance	Device provides > 111 Nt force (between 111 and 200 Nt[a])
	Annual Quality Control Tests for Film Systems
Automatic exposure control performance	i. The AEC maintains optical density within 0.30 (or 0.15[a]) of mean (thickness varied from 2 to 6 cm and kVp varied appropriately for thicknesses); ii. optical density in center of phantom image > 1.2.
kVp accuracy and reproducibility	i. Indicated kVp accurate within 5% at: the lowest clinical kVp that can be measured by a kVp test device, the most commonly used clinical kVp, and the highest available clinical kVp; ii., the coefficient of variation of reproducibility of the kVp ≤ 0.02 at the most commonly used clinical settings
System resolution	High contrast pattern resolves 11 line pair/mm with bars perpendicular to anode–cathode axis, and 13 when parallel; pattern 4.5 cm above breast support, centered, 1 cm of chest edge; test performed for each focal spot and target material.
Half-value layer (HVL)	HVL in mm$\geq$kVp/100
Breast entrance air kerma and AEC reproducibility	Coefficient of variation for both air kerma and mAs$\leq$0.05
Dosimetry	Average glandular dose (cranio-caudal view standard breast) $\leq$3 mGy/exposure.
X-ray field/light field/image receptor/compression paddle alignment	i. System has beam-limiting devices that allow the entire edge field to extend to the chest wall edge of the receptor and assure that the x-ray field does not extend beyond any edge of the receptor $>$2% of the SID; i. misalignment of the light and x-ray field $\leq$2% of the SID; iii. chest wall edge of compression paddle $<$1% of the SID beyond the chest wall edge of the receptor.
Uniformity of screen speed	i. Difference between the maximum and minimum optical densities of all screens$\leq$ 0.30; ii. screen artifacts shall also be evaluated during this test.
System artifacts	System artifacts shall be evaluated for all available focal spot sizes and target filter combinations with a sheet of homogeneous material to cover the, for all cassette sizes used.
Radiation output	System[a] can produce $>$7 mGy·s^{-1} air kerma at 28 kVp in Mo target/Mo filter mode at any SID with a detector 4.5 cm above the breast support surface with the compression paddle in place, over 3 s.
Automatic decompression, if included	System provides override capability to allow maintenance of compression, a continuous display of the override status, and a manual emergency compression release that can be activated in the event of power or automatic release failure.

[a] For units after built 10/02.

Table 25. Some Exemptions from Regulation Control for Naturally Occurring Radionuclides

Incandescent gas mantles
Vacuum tubes
Welding rods
Electric lamps (< 50 mg thorium)
Glassware (< 10%t source material)
Outdoor or industrial germicidal lamps, sunlamps, lamps (< 2 gm thorium)
Glazed ceramic tableware (glaze <20% source material)
Piezoelectric ceramic(< 2% source material)
Photographic film, negatives, and prints
Finished optical lenses (< 30% thorium)
Aircraft engine parts (nickel-thoria alloy < 4% thorium)

Marine compasses
Timepieces, dials (various limits)
Lock illuminators
Precision balances
Automobile shift quadrant
Thermostat dials

Uranium as counterweights in aircraft, rockets, projectiles, missiles (labeled)
Electron tubes
Spark gap irradiators
Gas and aerosol detectors

limits are very similar for all three organizations. In addition to this general exposure limit, standard setting groups have established several hazard-specific limits spanning the entire optical region. The standard of ANSI and the Illumination Engineering Society of North America (IESNA) provides a typical treatment (33). This standard describes the application of exposure limits for the following hazards:

200–400 nm Skin and Eye Exposure Limit: very similar to the ACGIH, ICNIRP, and NIOSH ultraviolet limit.

320–400 nm Eye Exposure Limit: 1 mW·cm^{-2} for exposure durations >1 000 s, and 1 J·cm^{-2} for shorter exposure durations.

400–1400 nm Retinal Thermal Hazard Exposure Limit: an exposure duration dependent limit based on an associated burn hazard spectral weighting function table.

400–700 nm Retinal Blue Light Hazard Exposure Limit: a limit that is time dependent for exposure durations <10,000 s, and exposure rate dependent for longer durations, with an associated blue light hazard spectral weighting function table.

Retinal Blue Light Hazard Exposure Limit—Small Source: basically the Retinal Blue Light Hazard limit modified to accommodate sources subtending an angle <11 mrad

Aphakic Eye Hazard Exposure Duration: extends the Retinal Blue Light Hazard down to 305 nm and replaces the blue light hazard spectral weighting function with an aphakic hazard weighting function.



Figure 4. Nonionizing radiation: Wavelength, frequency, and photon energy for optical, microwave, radio frequency, and ELF spectral regions.

770–3,000 nm Infrared Hazard Exposure Limit: 0.1 W·cm^{-2} for exposure durations <1000 s and 1.8t$^{-0.75}$ W·cm^{-2} for shorter exposure durations.

770–1400 nm Infrared Radiation Hazard Exposure Limit – Weak Visual Stimulus: where the visual stimulus may not activate the aversion response.

400– 3,000 nm Skin – Thermal Hazard Exposure Limit: provides limits for thermal skin exposure.

The various references caution users that to recall that several compounds (e.g., tetracycline and its congeners, porphyrins, Retin-A.) can make individuals more susceptible to the photochemical damage associated with UV radiation and blue light. Some common drugs that promote photochemical reactions are listed in Table E1 of the ANSI Z136.1-2000 standard. (34)

Lasers present a unique set of optical radiation hazards and consequently detailed exposure limits have been developed. Laser exposure limits are based on wavelength and various beam characteristics (e.g., beam diameter and divergence, plus pulse characteristics for pulsed lasers). While the OSHA occupational safety and health standards (Part 1910 of Title 29 CFR) do not specifically address lasers, Safety and Health Regulations for Construction (29 CFR Part 1926.54) provides some very general requirements (e.g., documented training of laser operators, posting of laser use areas, laser protective eyewear for workers in areas where the laser radiation level could exceed 5 mW·cm^{-2}). The OSHAs construction standard also specifies non-wavelength specific (though presumably visible "light") laser radiation exposure limits of 0.001 mW·cm^{-2} for direct staring, 1 mW·cm^{-2} for incidental viewing, and 2.5 mW·cm^{-2} for diffuse reflections. Figure 5 illustrates the strong wavelength dependence of the ANSI Z136.1-2000^{k} eye maximum permissible exposure (MPE) irradiance for continuous wave lasers under default exposure durations. Pulsed laser MPEs are more complicated to calculate, especially for repetitively pulsed lasers. See Thomas et al. for guidance on performing these repetitively pulsed laser MPE calculations(35). The ANSI Z136.1-2000 standard provides a framework for calculating the MPE for lasers occupying the wavelength region between 0.18 µm and 1 mm. The time domain covered extends to pulse



Figure 5. Maximum permissible exposure (MPE) versus wavelength for continuous wave lasers, assuming extended viewing duration for UV wavelengths ($<0.4\,\mu$m), only accidental viewing (<0.25 s) for visible wavelengths (0.4–0.7 μm), and 10 s exposure for wavelengths ($>0.7\,\mu$m). For clarity this chart extends only to 2 μm, but the MPE remains 100 $\text{mW}\cdot\text{cm}^{-2}$ for wavelengths from 1.4 to 1 mm.

durations as short as 10^{-9} s for UV ($<0.4\,\mu$m) and far IR ($<1.4\,\mu$m), and down to 10^{-13} s for the visible and near-IR regions (i.e., 0.4–1.4 μm). However, laser technology has pushed beyond these boundaries, with pulse durations in the 10^{-15} s range and shorter wavelength laser-like sources operating near the threshold of ionizing radiation now attainable in the laboratory. Subsequent editions of the Z136.1 standard are expected to address these gaps.

The FDA Laser Product Performance Standard (21CFR1040.10&11) requires laser manufacturers to classify laser products sold in the United State into one of four hazard classes according to the laser's ability to cause injury. The ANSI Z136 series of standards then specifies the required control measures appropriate for each class of laser. The IEC/EN 60825 series of standards establishes a similar laser hazard classification scheme for both manufacturers and application of control measures. Table 26 summarizes, in very general terms, the classes and subclasses for each of these organizations. In an apparent nod to pending harmonization, the recent Z136.3-2005 Standard for the Safe Use of Lasers in Health Care Facilities utilizes the IEC classification designations instead of the ANSI/FDA scheme (36). The laser hazard classes established by each of these three standard setting organizations also have associated accessible emission limits (AEL), but the AEL for each hazard class may not be identical for each organization.

The microwave region of the frequency spectrum is generally considered to extend from 300 MHz to 300 GHz, while the RF portion covers from 3 kHz to 300 MHz. (32,37) An opportunity for nomenclature confusion arises from the fact that some organizations, including ICNIRP (38), consider this microwave region to be a subset of an RF range extending from 300 Hz to 300 GHz. See Figure 4 for a sense of relative position of these regions in the electromagnetic spectrum. The FDA/CDRH Microwave Oven standard (21CFR1030.10) defines a microwave oven as a device designed to heat, dry, or cook food using electromagnetic radiation from 890 to 6000 MHz (most commercial microwave ovens operate at either 915 or 2450 MHz), and requires microwave oven manufacturers to limit radiation levels to $<5\,\text{mW}\cdot\text{cm}^{-2}$ at any point 5 cm or more from any external surface. OSHAs Construction standard (29 CFR 1926.54) limits microwave exposure to $10\,\text{mW}\cdot\text{cm}^{-2}$ (no averaging), but offers no other guidance in this region. The NIR section of OSHA's General Industry standard (29 CFR 1910.97) specifies a $10\,\text{mW}\cdot\text{cm}^{-2}$, 6 min average for exposure limit for the 10 MHz–100 GHz range, with no spatial averaging, and prescribes RF warning sign appearance. This OSHA section applies to all radiations originating from radio stations, radar equipment, and other possible sources of electromagnetic radiation (e.g., as used for communication, radio navigation, and industrial and scientific purposes), but does not apply to the deliberate exposure of patients by health care providers. In addition, section 29 CFR 1910.268 [Telecommunications] provides guidance for "lock out tag out" type securing and grounding prior to working on 3–30 MHz radio station broadcast antennas, prohibits employers from allowing employees to look into energized microwave waveguides, requires compliance with the 29 CFR 1910.97 exposure limits, and requires posting warning signs with specific wording in accessible areas where those limits could be exceeded. Table 27 gives some sample exposure limits.

Several standards setting organizations have developed exposure limits for microwave and radiofrequency radiation. These standards show considerable consistency for the spectral region extending from 300 GHz (i.e., near the boundary between optical and microwave radiation) to ~ 15 GHz, where most standards recognize an exposure limit of $10\,\text{mW}\cdot\text{cm}^{-2}$. At lower frequencies, additional considerations come into play, as indicated in Table 28. At frequencies below ~ 10 MHz, the longer wavelengths necessitate separate limits for magnetic and electric field exposures. This distinction arises because at longer wavelengths the emitted energy from an antenna passes first through a *near field* region, in which the electric and magnetic fields are not directly coupled as they are under the *far field* conditions normally associated with electromagnetic radiation. In the far field, the electric field strength is always directly proportional to the magnetic field strength, and the radiation levels generally decrease with the inverse square of the distance. In the near field, the electric and magnetic fields are not coupled, more complicated relationships with distance exist, and many far field assumptions no longer hold. The distance that the near field extends from the emitter is often defined as the wavelength divided by 2π, although ICNIRP defines the near field simply as the distance within one wavelength from a radiating antenna (38). By using the ICNIRP expression and consulting Fig. 3, we see, for example, that while at 10 MHz the near field extends only 30 m, at 100 kHz it is 3 km. The ICNIRP exposure limits (reference levels) appear in Table 34 (38,39), expressed as separate electric and magnetic field strengths (the ICNIRP guidance actually expresses exposure limits in terms of

Table 26. Summary of Laser Classification Schemes

FDA/CDRH 21CFR1040.10	ANSI Z136	IEC/EN 80625
Class I—levels of laser radiation are not considered hazardous	Class 1—no hazard; exempt from all control measures	Class 1—no risk, even with viewing instruments Class 1M[a]—no risk except perhaps to eye when viewed through viewing instruments (eye loupes or binoculars)
Class IIa—levels of laser (applies to visible only) radiation are not considered hazardous if viewed $\leq 1000\,\mathrm{s}$ but are considered a chronic viewing hazard for any period of time $>1000\,\mathrm{s}$ Class II—levels of (visible only) laser radiation considered a chronic viewing hazard	Class 2—visible (0.4–$0.7\,\mu\mathrm{m}$) lasers not considered hazardous for momentary viewing ($<0.25\,\mathrm{s}$), but for which the Class 1 accessible emission limit may be exceeded for longer exposure durations; avoid prolonged staring	Class 2—no eye risk for short term exposures, even with viewing instruments; no risk to skin (applies to visible lasers only) Class 2M[a]–no eye risk for short term exposures, except perhaps with viewing instruments; no risk to skin (visible only)
Class IIIa—levels of laser radiation are considered, depending upon the irradiance, either an acute intrabeam viewing hazard or chronic viewing hazard, and an acute viewing hazard if viewed directly with optical instruments	Class 3a—with “Caution” label: does not exceed the appropriate irradiance MPE, except perhaps when viewed through collecting optics (e.g., microscopes, telescopes)—with “Danger” label: may exceed the appropriate irradiance MPE	Class 3R[b]—low risk to eyes, no risk to skin
Class IIIb—levels of laser radiation are considered to be an acute hazard to the skin and eyes from direct radiation	Class 3b—emit greater than Class 3a limits and pose an acute eye hazard; more rigorous controls are required to prevent exposure of the unprotected eye	Class 3B—medium to high risk to eyes, low risk to skin
Class 4—levels of laser radiation are considered an acute hazard to the skin and eyes from direct and scattered radiation	Class 4—acute eye and skin hazard, plus ignition source (fire) and laser-generated airborne contaminants hazards; strict control measures required	Class 4—high risk to eyes and skin

[a] The “M” designation in the IEC classification scheme is derived from "magnifying" optical viewing instruments.

[b] The “R”designation in the IEC classification scheme is derived from reduced or relaxed requirements for manufacturers (no key switch or interlock connector required) and users (usually no eye protection required).

quantities that are not easily measured directly, such as currents induced in the body; the references levels then extrapolate those limits via models to the directly measurable field strengths given).

The microwave and RF exposure limits are generally based on protection against known adverse health effects of NIR exposure, but these limits may not be sufficiently protective for individuals with implanted medical devices (e.g., pacemakers, insulin pumps, cochlear implants, etc.) (38). Also, in the ELF region (defined here as by the ICNIRP as $<300\,\mathrm{Hz}$ (40), although some organizations and regulations specify slightly different spectral boundaries), considerable ambiguity marks the basis underlying the generally accepted exposure limit values. As Petterson and Hitchcock note, exposure guideline derivation should ideally stem from accepted mechanisms of interaction, dose response studies in animals, and epidemiological evidence of similar effects in humans; none of this has occurred for ELF fields (41). This view was reiterated in a 2002 update of the American Industrial Hygiene Association (AIHA) White Paper on ELF Fields (42). Finally, accurately assessing non-ionizing radiation hazards is complicated by the difficulty in properly measuring RF and ELF field strength. The NIOSH *Manual for Measuring Occupational Electric and Magnetic Field Exposures* provides some insight into this subject (43).

Because of its shallow tissue penetration and ease of control, ELF electrical fields are generally not of much concern below $\sim 15\,\mathrm{kV{\cdot}m^{-1}}$. However, individuals with implanted medical devices (e.g., cardiac pacemakers

Table 27. Sample of Microwave and Radiofrequency Radiation Exposure Limits, 10 MHz–300 GHz[a]

Source	Reference	Frequency	Limit, mW·cm^{-2}		Additional Criteria
			Occupational	*Public*	
OSHA	29 CFR 1926.54(l) [Construction]	0.3–300 GHz	10		(no averaging)
OSHA	29 CFR 1910.97(a)(2)(i) [General Industry]	0.01–100 GHz	10		Power (duration ≥ 0.1 h): 10 mW·cm^{-2} Energy (duration < 0.1 h): 10 mW·hr·cm^{-2} in any 0.1 h (no spatial averaging)
ICNIRP	Guidelines up to 300 GHz (1998)[n]	2–300 GHz	50	10	Averaged over any 20 cm^2 exposed area and, above 10 GHz, any $68/f^{1.05}$ (f = frequency in GHz) minute period; Limit peak exposures averaged over 1 cm^2 < 20 times these limits
		400–2,000 MHz	$f/40$	$f/200$	f = frequency in MHz
		10–400 MHz	10	2	Between 100 kHz and 10 GHz, averaged over any 6 minute period

[a] We thank the International Commission on Non-Ionizing Radiation Protection, ICNIRP, for the permission to reprint part of its guidelines in the present article. We also thank Health Physics, where the guidelines were first published.

Table 28. ICNIRP Electrical and Magnetic Field Exposure Limits, Static—10 MHz[a]

Reference	Frequency	Reference Level (Exposure Limit)				Additional Criteria
		Occupational		*Public*		
		Electrical V·m^{-1}	Magnetic A·m^{-1}	Electrical V·m^{-1}	Magnetic A·m^{-1}	
ICNIRP Guidelines up to 300 GHz (1998)[b]	1–10 MHz	$610/f$	$1.6/f$	$87/f$	$0.73/f$	f = frequency in MHz
	0.065–1 MHz	610	$1.6/f$			f = frequency in MHz
	0.15–1 MHz			$87/f$	$0.73/f$	f = frequency in MHz
	0.82–65 kHz	610	24.4			
	3–150 kHz			87	5	
	0.025–0.82 kHz	$500/f$	$20/f$			f = frequency in kHz
	0.025–0.8 kHz			$250/f$	$4/f$	f = frequency in kHz
	8–25 Hz	20,000	$20{,}000/f$	10,000	$4{,}000/f$	f = frequency in Hz
	1–8 Hz	20,000	$163{,}000/f$	10,000	$32{,}000/f$	f = frequency in Hz
	0– Hz	Use electrical safety procedures to avoid electric shock	163,000	Avoid spark discharges	32,000	
ICNIRP Guidelines for Static Magnetic Fields (1994)[t]	Static		Average: 160,000 Maximum: 1,600,000 Limbs: 3,980,000		General: 33,000 Electronic medical implants: 400	

[a] We thank the International Commission on Non-Ionizing Radiation Protection, ICNIRP, for the permission to reprint part of its guidelines in the present article. We also thank Health Physics, where the guidelines were first published.
[b] 1 tesla (T) = 796,000 amperes per meter (A/m) in air, vacuum and biological materials.

and insulin pumps) should avoid ELF electric fields above 1 kV·m^{-1}. The static electric and magnetic field designation is generally applied to any radiator with a frequency below 1 Hz (37). Static electrical fields are relatively simple to shield with grounded conducting enclosures. Static magnetic fields are more difficult to shield. The NIR environment surrounding nuclear magnetic resonance imaging facilities (primarily a high strength static magnetic field, but also RF radiation) poses a particular concern. The American College of Radiology's White Paper on MR Safety (44) offers some useful guidance on control of the hazards associated with MRI systems. While the ACR White Paper has served to increase awareness and foster discussion, the user community has not achieved consensus on these recommendations (45,46).

The FDAs 21CFR892.1000 identifies MRI systems as Class II medical devices, meaning among other things that institutions must implement safety programs rather than merely following the manufacturer's recommendations. In addition, MRI manufacturers generally must provide the customers with information, for example, indicating the extent of the static magnetic field (i.e., the location of the 5 G line). Attachment B of the FDAs *Guidance for the Submission of Premarket Notifications for Magnetic Resonance Diagnostic Devices* lists the elements of a MRI safety program, including patient screening, appropriate levels of patient monitoring and supervision, emergency procedures and shutdowns, noise control measures, access restrictions, control of cryogenic hazards, adherence to the IEC operating mode guidelines, use of MRI compatible equipment, fire precautions, and so on (47). The 5 G line around MRI facilities is generally posted with warning signs to avoid harmful effects on medical device wearers. There is no generally accepted format for MRI warning signs, though Shellock offers some helpful suggestions (48). The FDA guidance indicates that a MRI procedure performed under any of the following conditions constitutes a significant risk as defined in 21CFR812.3(m)(4), triggering the requirement for a FDA investigational device exemption, as well as the institutional review board (IRB) approval specified in 21CFR56 and the informed consent rules of 21CFR50 (49,50): procedures utilizing >8 tesla (T) for adults, children and infants older than 1 month, or >4 T for neonates (infants <1 month old); specific absorption rate (SAR) $\geq 4\,\mathrm{W\cdot kg^{-1}}$ for 15 min or more for the whole body, $3\,\mathrm{W\cdot kg^{-1}}$ for 10 min or more for the head, $8\,\mathrm{W\cdot kg^{-1}}$ for 5 min or more per gram of tissue for the head or torso, or $12\,\mathrm{W\cdot kg^{-1}}$ for 5 min or more per gram of tissue for the extremities; or any time rate of change of gradient magnetic fields sufficient to produce severe discomfort or painful nerve stimulation.

The IEC 60601-2-33 standard specifies three modes of operation relating to RF energy-induced heating and gradient magnetic field (51):

Normal operating mode: suitable for all patients and requires only routine monitoring;

First level controlled (FLC): may cause undue physiological stress; requires medical supervision and operator confirmation to enter this mode.

Second level controlled (SLC): may produce significant risk; requires IRB approval, and manufacturers are required to restrict operator access to this mode (e.g., password, key lock).

Although the FDA does not currently require MRI manufacturers to incorporate provisions for these three IEC modes, in the current global market all MRI manufacturers already include such provisions, and the FDA has indicated their intention to adopt these IEC 60601-2-33 guidelines (47,50).

CONCLUSIONS

Understanding codes, regulations, and license conditions can be the least exciting but most challenging part of a medical physicist's job! The federal codes may be the basis for state codes, but state codes are not necessarily identical to federal codes, even in NRC agreement states or OSHA-approved states. Compliance with myriad regulations and license conditions is a challenge. However, by knowing the codes and regulations one can write a better license or structure a radiation safety program with which it is easier for one to comply. To be forewarned is to be forearmed! We encourage readers to thoroughly study those codes and regulations applicable to their own facilities and to stay current with continuingly changing codes and regulations.

ACRONYMS AND DEFINITIONS

Most acronyms are discussed in the text.

AAPM. The American Association of Physicists in Medicine.

ACGIH. American Conference of Governmental Industrial Hygienists.

ACMP. American College of Medical Physics.

ACR. American College of Radiology.

Agreement States. Those states that have entered into a formal agreement with the NRC to take over certain of its regulatory authority within that state.

AIHA. American Industrial Hygiene Association.

AMP. Authorized medical physicist.

ANSI. American National Standards Institute, the voluntary standards-setting organization in the United States and its representative to the International Organization for Standardization.

AU. Authorized user, a physician authorized to use radioactive materials in the health professions.

BEIR. Biological Effects of Ionizing Radiation, often referring to reports bearing that acronym from the BRER.

BRER. Board on Radiation Effects Research, a board of the National Academy to coordinate activities of the National Research Council involving the biological effects of radiation.

Byproduct material. Any radioactive material (except special nuclear material) yielded in or made radioactive by exposure to the radiation incident to the process of producing or utilizing special nuclear material.

CDRH. Center for Devices and Radiological Health, and agency of the Food and Drug Administration.

CGMP. Current good manufacturing practices.

CRCPD. Coference of Radiation Control Program Directors.

Department of Defense

DOE. Department of Energy.

DOT. Department of Transportation.

DS. Dosimetry system.

EDE. Effective dose equivalent.

ELF. Extremely low frequency.

EPA. Environmental Protection Agency.

FC. Full calibration.

FDA. Food and Drug Administration.

HDR. High dose-rate brachytherapy.

HPS. Health Physics Society.

IAEA. International Atomic Energy Agency, an arm of the United Nations.

ICNIRP. International Commission on Nonionizing Radiation Protection.

ICRP. International Commission on Radiation Protection.

ICRU. International Commission on Radiation Units and Measures.

IEC. International Electrotechnical Commission, an organization that establish standards mostly pertaining to industry and manufacturers.

IR. Ionizing radiation.

IRB. Institutional Review Board, an institutions committee that evaluates new drugs, procedures or devices for proposed human use.

JCAHO. Joint Commission on Accreditation of Healthcare Organizations.

LDR. Low dose-rate brachytherapy.

MDR. Medium dose-rate brachytherapy.

ME. Medical event (see Table 14).

MQSA. Mammography Quality Standards Act.

NARM. Naturally occurring and accelerator-produced radioactive materials.

NCRP. Nation Council on Radiation Protection and Measurement.

NIOSH. National Institute for Occupational Safety and Health.

NIR. Non-ionizing radiation.

NRC. Nuclear Regulatory Commission.

NSSDR. National Sealed Source and Device Registry, a registry maintained by the NRC of information on approved devices.

OAS. Organization of Agreement States.

OSHA. Occupational Health and Safety Administration.

PD. Prescribed dose.

PDR. Pulsed dose-rate brachytherapy.

PMA. Premarket approval.

RAM. Radioactive materials.

RAU. Remote afterloading unit for brachytherapy.

RF. Radiofrequency.

RSO. Radiation safety officer.

SAU. Substitute authorized user, a physician working under the supervision of an authorized user.

SC. Spot check.

SDE. Shallow dose equivalent.

Source Material. Uranium, thorium or any combination thereof, in any physical or chemical form, or ores that contain by weight one-twentieth of 1% of them, excluding special nuclear material.

Special nuclear material (SNM). Plutonium, uranium-233, uranium enriched in isotopes 233 or 235, or any material artificially enriched by any of these.

SSR. Suggested State Regulations, guidelines for state radiation rules assembled by the CRCPD.

UNSCEAR. United Nations Committee on the Effects of Atomic Radiation, a committee under the United Nations to study the biological effects of radiation.

UV. Ultraviolet.

BIBLIOGRAPHY

1. Deye JA. Codes and Regulations, Radiation. In: Webster JG, editor Encyclopedia of Medical Devices and Instruments. New York: John Wiley & Sons, Inc; 1988.
2. U.S. Nuclear Regulatory Commission. 10 CFR 19 (Notices, Instructions, and Reports to Workers; Inspections), 1981 [Online]. Nuclear Regulatory Commission. Available at http://www.nrc.gov/reading-rm/doc-collections/cfr/part 0.19. Accessed 2004, December 4.
3. U.S. Nuclear Regulatory Commission. 10 CFR 20 (Standards for Protection Against Radiation; Final Rule,) 1991. [Online]. Nuclear Regulatory Commission. Available at http://www.nrc.gov/reading-rm/doc-collections/cfr/part020. Accessed 2004, December 4.
4. U.S. Nuclear Regulatory Commission. 10 CFR 20, 32, and 35 (Medical use of byproduct material: final rule.) Washington DC, Federal Register; Vol.67, No.79 (April 24): 20250-20397, 2002; [Online]. Nuclear Regulatory Commission. Available at http://www.nrc.gov/reading-rm/doc-collections/cfr/part020/part032/035. Accessed 2004, December 4.
5. U.S. Nuclear Regulatory Commission. 10 CFR 35 (*Medical use of byproduct material-Recognition of Specialty Boards; Final Rule*) Washington DC, Federal Register; Vol.70, No.60 (March 30): 16366-16367, 2005; [Online]. Nuclear Regulatory Commission. Available at http://www.nrc.gov/reading-rm/doc-collections/cfr/part35. Accessed 2005, April 19.
6. Institute of Medicine. Radiation Medicine: A Need for Regulatory Reform. In: Gottfried K-LD, Penn G. editors. Committee for Review and Evaluation of the Medical Use Program of the Nuclear Regulatory Commission, Institute of Medicine: 1996 ISBN-0-309-58875-8.
7. Memorandum of Understanding Between the OSHA and U.S. Nuclear Regulatory Commission. CPL 02-00-086–CPL 2.86 (1989, December 22) [Online]. Occupational Safety & Health Administration. Available at http://www.osha.gov/pls/oshaweb/owadisp.show_document?p_table=DIRECTIVE&p_id=1658. Accessed 2005, April 29.
8. Federal Register [07/23/2004] 69: 44068-44069; Supporting Statement for the Information-Collection Requirement for the Ionizing-Radiation Standard (29CFR1910.1096) OMB Control No. 1218-0103(2004)(June2004).
9. Occupational Safety and Health Administration. 29 CFR 1910.1096 (Ionizing Radiations), [Online] Occupational Safety and Health Administration. Available at http://www.osha.gov/pls/oshaweb/owadisd.show. Accessed 2005, April 14.
10. Conference of Radiation Control Program Directors. Available at http://www.crcpd.org/free_docs.asp. Accessed 3 October 2005.
11. Curtis R. Non-ionizing radiation: standards and radiation (PowerPoint presentation). OSHA-Salt Lake Technical Center. [Online] Available at http://www.osha-slc.gov/SLTC/radiation_lectures/nir_stds_20021011.ppt. Accessed April 22, 2005.
12. Rockwell RJ, Parkinson J. State and local laser safety requirements. J Laser Appl 1999;11:225–231.
13. Henderson R, Schulmeister K. Laser Safety Philadelphia: Institute of Physics Publishing; 2004.

14. Center for Devices and Radiological Health. Laser Products – Conformance with IEC 60825-1, Am. 2 and IEC 60601-2-22; Final Guidance for Industry and FDA (Laser Notice 50), 2001.
15. News and Notices IAEA action plan to combat nuclear terrorism Health Phys 2002;82:908–909.
16. News and Notices “IAEA and UPU join forces to protect mail” Health Phys 2003;84:129–130.
17. Nuclear Energy Institute, Fact Sheet, August 2004.
18. U.S. Nuclear Regulatory Commission, U.S. Department of Transportation, U.S.-Specific Schedules of Requirements for Transport of Specified Types of Radioactive Material Consignments, RAMREG-002/U.S. Nuclear Regulatory Commission, NUREG-1600, January 1999.
19. Hazardous Materials Regulations; Compatibility With the Regulations of the International Atomic Energy Agency, RSPA-99-6283 (HM-230); Final rule; Published 01/26/2004; Effective Date: Oct 1, 2004; 69 FR 3631.
20. International Atomic Energy Agency, Regulations for the Safe Transport of Radioactive Material, 1996 Edition, Safety Standards Series/Requirements, ST-1, Vienna, Austria; International Atomic Energy Agency, 1996.
21. International Commission on Radiation Protection, 1990 Recommendations of the ICRP: ICRP Publication 60, Ann of the ICRP 21: 1-3 Oxford: Pergamon Press; 1991.
22. USNRC Potential for Erroneous Calibration, Bulletin 97-01. Dose Rate, or Radiation Exposure Measurements with Certain Victoreen Model 530 and 530SI Electrometer/Dosemeters (April 30, 1997).
23. Glasgow GP. Nuclear Regulatory Commission regulatory status of approved intravascular brachytherapy systems. Cardiovascular Rad Med 2002;3:1–11.
24. USNRC, 2004.
25. U.S. Nuclear Regulatory Commission . NRC Information Notice 2003-21: High-dose rate remote afterloader equipment failure. November 24, [Online] Available at http://www.nrc.gov/materials/miau/med-use-toolkit/info-notices.html. Accessed December 4, 2004.
26. U.S. Nuclear Regulatory Commission. Newsletter NUREG/BR-0117/04-2: Nuclear Material Safety and Safeguards [Online] Available at http://www.nrc.gov/reading-rm/doc-collections/nureg/brochures/br0117/04-2.pdf. Accessed December 4, 2004.
27. USNRC, Compatibility Categories and Health and Safety Identification for NRC Regulations and Other Program Elements—Procedure No. SA-200, 2004 [Online] Available at http://www.hsrd.ornl.gov/nrc/procintro.htm. Accessed 3 October 2005.
28. Conference of Directors of Radiation Control Programs, Suggested State Radiation Control Regulations. Avaliable at http://www.crcpd.org/SSRCRs. Accessed 3 October 2005.
29. International Commission on Non-Ionizing Radiation Protection. Guidelines on Limits of Exposure to Ultraviolet Radiation of Wavelengths Between 180 nm and 400 nm (incoherent optical radiation Health Phys 2004;87:171–186.
30. International Commission on Non-Ionizing Radiation Protection. Guidelines on UV Radiation Exposure Limits. Health Phys 1996;71:978.
31. National Institute for Occupational Safety and Health. Criteria for a Recommended Standard–Occupational Exposure to Ultraviolet Radiation; DHHS (NIOSH) Publication No. 73–11009, 1972.
32. American Conference of Governmental Industrial Hygienists. 2004 TLVs® and BEIs®. Cincinnati, OH: ACGIH, 2004.
33. American National Standards Institute/Illuminating Engineering Society of North America. RP-27.I-96: Recommended Practice for Photobiological Safety for Lamp & Lamp Systems - General Requirements. New York: IESNA; 1996.
34. American National Standards Institute, Inc., ANSI Z136.1-2000, American national standard for safe use of lasers. Orlando: (FL): Laser Institute of America; 2000.
35. Thomas RJ, et al. A procedure for multiple-pulse maximum permissible exposure determination under the Z136.1-2000 American National Standard for the Safe Use of Lasers. J Laser Appl 2001 13:134–139.
36. American National Standards Institute, Inc., ANSI Z136.3-2005, American national standard for safe use of lasers in health care facilities. Orlando, FL: Laser Institute of America; 2005.
37. Hitchcock RT. Radio-Frequency and Microwave Radiation. In: DiNardi SR. editor. The Occupational Environment—Its Evaluation and Control. Fairfax, VA: AIHA Press; 1998.
38. International Commission on Non-Ionizing Radiation Protection. Guidelines for Limiting Exposure to Time-Varying Electric, Magnetic, and Electromagnetic Fields (Up to 300 GHz). Health Phys 1994;74:494–522.
39. International Commission on Non-Ionizing Radiation Protection. Guidelines on Limits of Exposure to Static Magnetic Fields. Health Phys 1994;66:100–106.
40. International Non-Ionizing Committee of the International Radiation Protection Association. Review of Concepts, Quantities, Units and Terminology for Non-ionizing Radiation Protection. Health Phys 1985;49:1329–1362.
41. Patterson RM, Hitchcock RT. Extremely Low Frequency (ELF) Fields. In: DiNardi SR, editor. The Occupational Environment–Its Evaluation and Control. Fairfax, (VA): AIHA Press; 1998.
42. American Industrial Hygiene Association. AIHA White Paper on Extremely Low Frequency Fields, Fairfax, VA: AIHA; 2002.
43. Bowman JD, Kelsh MA, Kaune WT. Manual for Measuring Occupational Electrical and Magnetic Field Exposures [DHHS (NIOSH) Publication No. 98-154]. Cincinnati, (OH): National Institute for Occupational Safety and Health Publications Dissemination; 1998.
44. Kanal E, et al. American College of Radiology white paper on MR safety. Am J Radiol 2002;178:1335–1347.
45. Shellock FG, Crues JV. MR Safety and the American College of Radiology White Paper. Am J Radiology 2002;178:1349–1352.
46. Kanal E, et al American College of Radiology White Paper on MR Safety: 2004 Update and Revision. Am J Radiol 2004;182: 1111–1114.
47. Center for Devices and Radiological Health. Guidance for the Submission of Premarket Notifications for Magnetic Resonance Diagnostic Devices. CDRH, [Online]. Available at http://www.fda.gov/cdrh/ode/95.html. Accessed 5 October 2005.
48. Shellock FG. MR Safety Signs. RT Image 16(3): 2003. Available at http://www.rt-image.com/content=8702J84E489CAE9040A-240441. Accessed 30 Sept 2005.
49. Center for Devices & Radiological Health. Guidance for Industry and FDA Staff - Criteria for Significant Risk Investigations of Magnetic Resonance Diagnostic Devices. CDRH, 2003.
50. International Commission on Non-Ionizing Radiation Protection. Medical magnetic resonance (MR) procedures: protection of patients. Health Phys 2004;87:197–216.
51. Zaremba LA. FDA Guidance for magnetic resonance system safety and patient exposures: current status and future G considerations. In: Shellock FG, editor. Magnetic resonance procedures: health effects and safety, Boca Raton, (FL): CRC Press LLC; 2001.

See also CODES AND REGULATIONS: MEDICAL DEVICES; IONIZING RADIATION, BIOLOGICAL EFFECTS OF; NONINONIZING RADIATION, BIOLOGICAL EFFECTS OF; RADIATION PROTECTION INSTRUMENTATION.

COGNITIVE REHABILITATION. See REHABILITATION, COMPUTERS IN COGNITIVE.

COLORIMETRY

LI-JIUAN SHEN
National Taiwan University
Taipei, Taiwan

RICHARD MANDEL
Boston University
Boston, Massachusetts

WEI-CHIANG SHEN
University of Southern
California,
Los Angeles, California

INTRODUCTION

Light can be characterized as a wave with frequency and wavelength λ. This wave has energy E, which is proportional to its frequency

$$E = hc/\lambda = h\nu$$

where h is Planck's constant and c is the velocity of light. When such a wave of light encounters a molecule, it will either be absorbed (i.e., its energy will be transferred to the molecule) or scattered (i.e., its direction of propagation will be changed). The probability of occurrence of each process will depend on the nature of the molecule encountered. If the electromagnetic energy is absorbed, the molecule is said to be excited. A molecule or part of a molecule that can be excited by absorption is called a chromophore. The absorption of light generally excites the electrons of the molecule or chromophore from its ground electronic state to one of its excited electronic states. Absorption of light is likely to occur if the energy of the light is equal to the difference in the energy between the ground (E°) and excited (E^{*}) electronic state.

$$\lambda = hc/(E^{*} - E^{\circ})$$

These transitions have rather diffuse energies because excited states occur in both the vibrational and rotational as well as electronic states, giving rise to broadened energy ranges. A plot of the probability of absorption versus wavelength is called an absorption spectrum. The excitation energy is usually released as radiant energy in the form of kinetic energy and heat. Under certain conditions, some molecules rapidly reemit their energy as visible or ultraviolet (UV) light. This is known as fluorescence.

The wavelengths that give rise to electronic transitions in molecules are generally in the visible (700–400 nm) and UV (400–200 nm) region. These transitions are often characteristic of specific molecules and can be used to assay biological and biochemical samples. Transitions at longer wavelengths and lower energies in the infrared (IR) or near-infrared (NIR) generally correspond to excitation of vibrational states alone and are characteristic of specific functional groups such as carbonyl oxygen bonds or carbon–carbon bonds. Even though this region of the absorption spectrum does not find many biomedical applications, IR and NIR spectroscopy have been used for qualitative and quantitative analysis of different forms (crystal and amorphous) of pharmaceutical solids (1,2). It is further developed into an on-line process monitoring and control entitled process analytical technology (PAT) by the collaboration of U. S. Food and Drug Administration (FDA) and the pharmaceutical industry (3). On the other hand, transitions at shorter wavelengths and higher energies, in the vacuum UV and X-ray region, cannot be carried out on biological samples in aqueous solution and have limited usefulness in biomedical assays.

The probability of light absorption at a single wavelength is described by the Beer–Lambert law. It has been observed that the passage of light through any given thickness of any substance results in the absorption of a constant fraction of that incident light. In differential form, this equation can be written

$$dI/I = -KCdl$$

where dI/I is the fraction of light absorbed by a layer of thickness dl, K is a constant that depends on the properties of the substance, and C is the concentration of the absorbing substance. Thus, for a given beam of light passing through a sample of finite thickness, the amount absorbed at each point in that sample is proportional to the incident intensity at that point. If, for example, in the first millimeter of passage through a sample 50% of the light is absorbed, then in the second millimeter of passage 50% of the remaining light or 25% of the initial intensity will be absorbed, and in the third millimeter 50% of the remainder or 12.5% of the initial intensity will be absorbed. In total, 87.6% of the incident light beam will be absorbed by the 3 mm path length. Mathematically, this is calculated by integrating the above equation, which yields

$$ln(I_0/I) = K'Cl \quad \text{or} \quad I/I_0 = 10^{-K'Cl}$$

where $K' = K/2.303$, l is the path length, I_0 is the initial intensity, and I the final intensity of the light beam after having passed the sample. The left-hand side of the equation defines the optical density and is a useful quantity, because it is directly proportional to the concentration of the absorbing substance and the path length. Absorbance, also called optical density (OD), is designated by A. The transmittance of a solution, designated T, is the fraction (I/I_0) and is related to the absorbance by

$$A = -\log T$$

In the above example, the absorbance through a single millimeter path length is $-\log 0.5 = 0.301$, while the total absorbance through 3 mm is $3 \times 0.301 = 0.903 = -\log 0.125$.

A plot of absorbance as a function of concentration (called a Beer's law plot) is ideally a straight line, while a plot of transmittance is a hyperbolic curve (Fig. 1). Deviations from linearity will be discussed below. Absorbance is a unitless quantity. Therefore, the constant (K') in the above equation must be in units of reciprocal concentration and reciprocal length (typically $\text{cm}^{-1} \cdot M^{-1}$). The absorbance is proportional to both concentration and



Figure 1. Plots of concentrations versus (a) transmittance (A) and (b) absorbance (B).

length of light path, while the constant specifies a characteristic property of the absorbing chromophore. This constant, which is a function of wavelength, is called the absorption coefficient or extinction coefficient of the material. Absorption coefficients may be expressed on either a weight or a molar basis. The molar extinction coefficient, designated by *e* specifies the total absorption of a 1 *M* solution through a 1 cm path length. A molar extinction coefficient of 10,000 or greater is characteristic of a strongly absorbing substance.

Plots of absorbance as a function of concentration are linear if the absorbing chromophore remains the same over the concentration range studied, the chromophore is uniformly distributed, and the orientation of dichroic absorbers (i.e., substances having directional asymmetry) is random. Changes in the nature of the chromophore with concentration, such as ionization, hydration, aggregation, or disaggregation, will alter the absorption spectrum of the solution. There are no general rules as to whether the absorption will increase or decrease. An example of an absorption change resulting from molecular interactions is that of deoxyribonucleic acid (DNA). When the absorption of a solution of native DNA is compared with that of the same concentration of DNA bases, the DNA shows a 30–40% lower extinction coefficient at the 260 nm peak. Heating of the DNA to disrupt the orderly stacking of the bases in the double helix raises the extinction coefficient to that of its constituent bases. The DNA is said to be hypochromic with respect to its bases, while heating of the DNA is said to display a hyperchromic effect. This principle is also widely applied to determine the thermodynamic parameters of nucleic acids using colorimetric measurements. Often some parts of the spectrum will show increased absorbance and other parts will show decreased absorbance. In such a case and when there is an equilibrium between two different molecular forms, there will always exist a wavelength that shows invariant absorption. This point, known as an isobestic point, can be used to quantify concentration of compounds that can exist as different molecular forms. For example, phenol red changes from a protonated to an ionized form between pH 6 and 8, with a switch of the absorption wavelength from 432 (yellow) to 559 nm (red). The absorption at 479 nm, the isosbestic point, is constant regardless the molecular form of this compound and, therefore, this wavelength can be used to measure the concentration of phenol red without a concern to the pH of the solution (Fig. 2).



Figure 2. Absorption wavelength of phenol red under various pH conditions. A constant absorption wavelength is shown here at 479 nm, which is the isosbestic point.

Non-uniform distributions of chromophore in solution will lead to decreased absorption. This is most readily understood by considering a situation in which one-half of the cross-section of a light beam goes through a transparent solvent, while the other one-half traverses an absorbing solution. Even if the solution is totally absorbing, at least one-half of the light will be transmitted through the sample leading to a limiting absorbance of $\log(I/I_0) = \log 2 = 0.301$. Thus, a plot of absorbance versus concentration will lead to a curve asymptotically reaching 0.301 as the concentration increases. An example of nonuniform distributions leading to changed absorbance is illustrated by the absorption of Acridine Orange in the presence of cellular organelles. Acridine Orange is a weak base that accumulates in acidic cellular compartments, such as endosomes, lysosomes, and Golgi. When it is concentrated in such organelles, the apparent absorbance of the solution decreases. Since the acid gradient is generated by a membrane-bound enzyme that requires adenosine triphosphate (ATP) as its energy source, addition of ATP to a subcellular suspension containing Acridine Orange will cause a decrease in absorption. In this way, changes in the absorbance of Acridine Orange can be used to monitor the activity of the ATPase (4).

The most common biochemical or clinical use of the absorption properties of chromophores is to measure concentration. In brief, the absorption spectrum, that is, a graph of absorbance as a function of wavelength, is recorded from which a suitable wavelength is chosen. Generally, the wavelength chosen is at or near the peak in absorption of the chromophore. This maximizes the sensitivity of the absorption measurement and decreases possible error resulting from incorrect wavelength calibration of the instrument. Other wavelengths may be chosen if another chromophore present in the solution interferes with the measurement. The extinction coefficient is determined, or a calibration curve of the absorbance is run at a number of different concentrations of chromophore. Concentration is determined by weighing a standard or from the extinction coefficient, if it is accurately known. The plot is examined for linearity. Subsequent concentrations can be determined either directly from the extinction coefficient or from the calibration curve of absorbance versus concentration. For example, the concentration of DNA can be readily determined by measuring the absorbance of a solution at 260 nm. At this wavelength, an absorbance of 1.0 corresponds to a concentration of 50 and 33 $\mu g \cdot mL^{-1}$ for double- and single-stranded DNA, respectively, at a 1 cm path length.

Different substances can often be distinguished by the use of spectrophotometric measurements if they exhibit different absorption spectra. In an ideal solution, we can assume that the total absorption at any wavelength, is equal to the sum of the individual absorptions. This principle has been used to determine the protein and nucleic acid content of cell extracts and cell fractions or to assess the purity of nucleic acids. At 260 nm, ribonucleic acid (RNA) has a peak absorption of 50.8 $mL \cdot mg^{-1} \cdot cm^{-1}$, while at 280 nm, its absorption is 24.8. Proteins containing an average proportion of aromatic amino acids have a small peak of 2.06 $mL \cdot mg^{-1} \cdot cm^{-1}$ at 280 nm, which decreases to 1.18 $mL \cdot mg^{-1} \cdot cm^{-1}$ at 260 nm (5). By comparing the ratio of absorbance at these two wavelengths, the relative RNA and protein concentration can be determined. The method assumes that the total absorbance at 260 and 280 nm is due to the sum of the absorbances of the constituent protein and nucleic acid. Solving the simultaneous equations yields the concentrations as follows:

$$\text{Protein concentration (mg/mL)} = 0.674 \times A_{280} - 0.33 \times A_{260}$$

$$\text{Nucleic acid concentration (mg/mL)} = -0.016 \times A_{280} + 0.027 \times A_{260}$$

This relationship varies for different proteins and nucleic acids. For accurate work, a calibration must be carried out to determine the actual coefficients for the samples studied. For an accurate determination, specific reagents can selectively react with DNA, RNA, and protein, respectively, for its own quantification to avoid the interference from each other (6,7). For example, the bicinchoninic acid (BCA) assay, Coomassie Blue-G 250 dye binding assay (the Bradford), and the Lowry method are commonly used colorimetic methods for protein quantification (7).

Sometimes samples consist of light-absorbing particles in suspension rather than molecules in solution. For example, while many bacteria do not have chromophores that absorb visible light, suspensions consisting of intact bacteria display apparent absorption due to the scattering of light (Rayleigh scattering). Rayleigh equation demonstrates the reciprocal forth-power relationship between light scattering intensity and wavelength. This apparent absorption has been used to quickly measure bacterial or viral concentrations. A calibration curve is determined by comparing absorbance with viable cell count. For example, the concentration of *Salmonellatyphimurium* in suspension can be determined from the absorption at 440 nm, since the absorption is linear with concentration such that 1.07×10^8 bacteria mL^{-1} yields an apparent absorbance of 1.0, for a 1 cm path length. Methods that utilize the apparent absorption of scattering solutions are often referred to as turbidimetry. Turbidimetric methods can also be used to monitor the kinetics of enzymatic processes that cause changes in the level of light scattering. For example, the enzyme rennin will coagulate milk, leading to an increase in its scattering (monitored at 600 nm) (8). The initial rate of change of apparent absorbance can therefore be measured and used to determine the concentration of active enzyme added. In some cases, the material being measured consists of light-absorbing particles in suspension with chromophores. For example, the absorbance of bacteriophages is primarily due to DNA. Since scattering always begins at wavelengths removed from the absorption, its contribution can be subtracted by measuring the absorbance at longer wavelengths than that of the chromophore and by linearly extrapolating the scattering from the absorption peak. For kinetic measurements on scattering solutions, difference spectra are often used, where the wavelengths are chosen such that one is at the chromophore maximum, while the other is at wavelengths where the only absorption is due to scattering. Specialized instruments that allow for absorbance measurement at two different wavelengths simultaneously are required for such measurements.

Most of the approaches to detect specific DNA sequence are expensive and time-consuming, such as fluorescent microarrays. An inexpensive and rapid assay for the identification of DNA sequence and single nucleotide polymorphisms has been recently described by using a colorimetric method with nanotechnology (9). In this assay, the color of negatively charged gold nanoparticles (Au-nps) is very sensitive to the degree of aggregation. Single-stranded DNA can stabilize Au-nps and prevent the salt-induced aggregation. This method has been applied into clinical samples and successfully identified the relationship between a specific gene and a fatal arrythmia (9).

Due to the contribution of nanotechnology, Au-nps can be utilized as ideal color reporting groups as the colorimetric biosensors. For example, it can provide the qualification and quantification of Pb^{2+}(10), and the detection of polynucleotides (11).

INSTRUMENTATION

Presently, most colorimetry is done using spectrophotometers rather than colorimeters. In principle, spectrophotometers and colorimeters are similar, with the latter being very simple and inexpensive versions of spectrophotometers. Both instruments consist of a light source, a means of selecting wavelength, a sample compartment, and a detector of transmitted light, as shown in a single-beam spectrophotometer (Fig. 3). The source generally consists of an incandescent tungsten lamp for measurements in the visible range between 350 and 700 nm and a hydrogen deuterium, or xenon arc lamp for measurements in the UV range down to 190 nm. Thermal lens spectrophotometry, a new high sensitivity method utilizes a laser as its source (12). A stabilized current is generally provided, especially for measurements in the UV range to



Figure 3. A single-beam spectrophotometer.

prevent fluctuations in the intensity of the lamp. Light from the lamp is collimated or focused by a lens onto a wavelength selector. In the case of the simplest colorimeters, the wavelength selector is a broadband filter that yields a distribution of wavelengths with a width of ~ 40 nm. In spectrophotometers and more sophisticated colorimeters, the wavelength is chosen with a monochromoter by either reflecting the beam off a grating or by passing it through a prism. In a spectrophotometer, the bandwidth of light can be set by adjusting the exit slit. As the slit opening decreases, the light incident on the sample decreases, but the spectral resolution improves. Excessively wide bandwidth can lead to decreased peak absorption and interference from other substances absorbing at nearby wavelengths. In a colorimeter, the bandwidth is fixed, depending on the properties of the filters. While it is possible to obtain narrow bandpass filters if necessary, they may cost as much as the colorimeter.

The monochromatic light is then focused on the sample, contained in a transparent rectangular cuvette, a test tube, or a microplate with 6–384 wells. In some spectrophotometers, the sample compartment has been designed to accommodate with 96–1536-well microplate for high throughput screening (13). Colorimeters generally use test tubes made of any clear materials, such as glass or plastics, as long as they allow any required chemical reactions to be carried out in the same disposable container in which the measurement is carried out. Spectrophotometers and automated colorimeters designed to determine large numbers of samples usually hold rectangular cuvettes and microplates. These are generally made of glass or plastics for measurements within visible light wavelengths, and of quartz for measurements < 350 nm in the UV range. The transmitted light is incident on a phototube that records the intensity of the light reaching it. Some spectrophotometers are double-beam instruments, which electronically subtract an absorption blank. There are two types of the double-beam spectrophotometers. One is called the double -beam in-time spectrophotometer (Fig. 4). In this instrument, a single beam of light from the monochromator is alternately switched between the sample and the reference cuvettes. The two alternate beams then reach a single detector in separate time to provide an alternating signal with an amplitude that is proportional to the difference of the light intensities between the sample and the reference. The other type is called the double-beam in-space spectrophotometer (Fig. 5). In this instrument, two separate light pathways are created by a beam splitter and mirrors. One beam passes through the sample cuvette, and the other beam the reference cuvette. The light intensities of the sample and the reference cuvettes are measured by two separate detectors and the difference is recorded as the absolute photometric measurement.

Many spectrophotometers are still designed as single-beam instruments (Fig. 3); the solvent absorption is separately determined, stored, and subtracted by an interfaced microcomputer. In colorimeters and other single-beam instruments, the absorption is set to zero or the transmission is set to 100% when the reference blank is placed in the sample compartment. The detector is designed to give a direct reading of either transmission or absorbance. The newer spectrophotometer is a multifunctional instrument with a triple-mode cuvette port and microplate reading capability. The detection modalities include absorbance, fluorescence intensity, fluorescence polarization, time-resolved fluorescence, and luminiscence. With a dual-monochromator, the filters for specific wavelengths are not required in these spectrophotometers. (e.g., SpectraMax M5 by Molecular Devices Corp.). The function of spectrophotometer also has improvement in the rate of data acquisition. It can be as fast as 50 μs, which is beneficial in rapid kinetics.



Figure 4. A double beam in-time spectrophotometer.



Figure 5. A double-beam in-space spectrophotometer.

CLINICAL APPLICATIONS OF COLORIMETRIC METHODS

Colorimetry has seen wide applications in clinical and medicinal chemistry and in biochemistry. Colorimetric methods are used to measure concentration or enzyme activity. Lately, colorimetric methods are also applied in genomics and proteomics research, such as the single nucleotide polymorphism analysis (14), the detection of protein microarrays (15), and so on. The concentration of a substance can be determined directly and immediately if the unknown has a distinct absorption band that does not overlap other substances in the assay mixture. If not, the unknown may be analyzed indirectly on completion of one or more chemical reactions, yielding a colored compound with a definite stoichiometric relationship to the unknown compound. The reaction must be rapid and specific and must react completely with the unknown to be of use. In contrast to quantitative measurements, kinetic measurements determine initial reaction kinetics by the rate of appearance of an absorbing product or by the rate of disappearance of an absorbing reactant. Kinetic measurements are carried out either directly by monitoring changes in the absorption of substrates or cofactors or indirectly by coupling a second, third, or additional enzyme reactions to the primary one. Each of these cases will be discussed and illustrated later.

Due to the development of new automated diagnostic instruments, the manual colorimetric assays have become less useful in most clinical laboratories. However, most tests performed in automated instruments are based on simple colorimetry. Therefore, the principles in colorimetry are essential for the improvement and development of new automated assays. Furthermore, manual colorimetric methods are still used in handling small numbers of samples, such as in small clinical laboratories or for special diagnostic purposes.

There are several general precautions that should be taken in colorimetric measurements of clinical samples. These are as follows:

1. Sample preparation. Most clinical samples (e.g., blood and urine) contain a large amount of components other than the analyte. The results of the test are only meaningful if the background reading of the sample has been subtracted. The background must be obtained by using proper controls. Usually, when a measurement is made by the addition of a reagent, an identical sample without the reagent can be used as a control or blank. When an enzyme activity is measured, a control or blank can be obtained by excluding the specific substrate or by including a specific inhibitor for the enzymatic reaction. Because of instability, many specimens must be handled immediately after they reach the laboratory and cannot be stored. The turbidity of a sample will cause false readings in colorimetry. This problem generally can be eliminated either by centrifugation, filtration, or comparing with identical controls.
2. Buffer solutions. The absorbances, especially in the visible wavelength range, are usually pH dependent. Furthermore, the type and concentration of ions in the buffer may also influence the absorbance of a molecule or the rate of reaction. Therefore, careful attention must be paid to the solvent and buffer system. In addition, the rates of enzymatic reactions are highly pH dependent. It is therefore important to choose a buffer with an ionization potential (pK) appropriate to the optimal pH for the assay. For example, imidazole or triethanolamine buffer is commonly used in the pH range of 6.5–7.0.
3. Temperature. Kinetic measurements use enzymes to catalyze the reactions of intensely colored substances. Enzymatic reactions are highly temperature dependent. It is therefore necessary to use isothermal control when carrying out such assays. If not, it is necessary to know precisely the reaction temperature. If the reaction is carried out in the colorimeter, care must be taken to ensure that the temperature of the reaction mixture is not affected by the heat produced in the sample chamber.
4. Inhibitors. Enzymatic reactions are subject to competitive inhibition or to the action of specific inhibitors leading to apparent decreases in the measured activity or concentration of the unknown. It is therefore extremely important to eliminate these interfering substances or to include the proper controls during the assay. In cases of product inhibition, the initial rate should be used for the determination of the enzymatic activity.

In the following sections, several colorimetric measurements of clinical importance will be discussed. They are used primarily as examples to indicate the standard procedures of colorimetry in clinical laboratories. The number of applications of colorimetry is too vast to present an extensive survey in this article.

Quantitative Measurement

Direct Measurement. Direct colorimetric measurement for quantitative assays are limited to very few cases in which the compound of interest itself has an intense absorption and in which there is no interference from other components in the samples. One example is the determination of hemoglobin in blood. Since oxygenated and deoxygenated hemoglobins, carboxyhemoglobin, and hemoglobin derivatives have different absorption spectra, the concentration of a specific type of hemoglobin, as well as the oxygen-binding capacity, can be determined by measuring the ratio of absorption (A) at two different wavelengths (16) (e.g., A_{562}: A_{540} for carboxyhemoglobin and A_{560}: A_{506} or A_{650}: A_{825} for oxygen-binding capacity), similar to that described above for the protein–nucleic acid measurement.

Bilirubin measurement in blood samples can also be done by direct measurement at 460 nm (17). The absorbance is compared with that of a standard solution of potassium dichromate and is reported in term of units of icterus index. One unit of icterus is equivalent to a 1:10,000 solution of potassium dichromate. This determination is only approximate, because there are many other components in blood, mostly carotenoid pigments, which will interfere with the readings.

Indirect Measurements

Complex Formation. One of the most common applications of colorimetry is in the determination of protein concentration. Colorimetric determination of the total serum protein by the Biuret reaction is still used in many clinical laboratories. In this method, proteins react with copper sulfate in alkaline solution to form a Biuret complex that can be determined by the intensity of the violet color with an absorption at 555 nm (18). The Biuret reaction is a relatively straightforward, precise, and accurate method. Usually, 0.1 mL serum is added to 5 mL of Biuret Reagent solution, which contains sodium, potassium tartrate, potassium iodide, and copper sulfate in 0.2 M NaOH. After incubation at 30–32 °C for 10 min or at room temperature for 20 min, the reaction mixture is read at 555 nm. The sample absorbance is generally compared to human or bovine serum albumin (BSA) standards. The color of the Biuret complex is stable for several hours after it reaches the maximum intensity. The measurement of protein by Biuret measurement is subject to interference by other substances in serum. In serum separated from moderately hemolyzed blood or serum with high bilirubin content potassium cyanide is usually included in the reaction mixture to correct the difference. Dextrans may also interfere by causing turbidity. For these determinations, appropriate blanks should be used instead of just saline or water, as described in most general procedures.

Many other methods use nearly colorless chemical reagents that complex with the protein to form highly colored compounds. One of them, the Lowry method (19), is the single most utilized assay in biochemistry research and is the most cited reference in the biochemical literature. However, it is not widely used in clinical applications. A variety of dyes, which form strong binding complexes with protein, is also used to quantitate protein concentration. For example, Coomassie Brilliant Blue R-250 is commonly used to visualize and quantify proteins in gels separated by electrophoresis and to quantify proteins eluted from gels (20). To visualize proteins, gels are stained with dye in 50% methanol–10% acetic acid solvent, after which excess dye is removed by the solvent. To accurately quantitate protein concentration, dye bound to protein is removed by electroelution or chemical elution, and absorbance of the solutions at 595 nm is measured. Coomassie Brilliant Blue stained electrophoresis gels are quantitated by direct scanning colorimetry at the same wavelength. This dye is most useful to quantify proteins present in the amount range of 0.5–50 μg. The binding of silver to protein has been used to visualize and to quantitate proteins separated in gels (21). While this method is ~ 100 times more sensitive than Coomassie Brilliant Blue staining, it is also much more expensive due to the cost of the silver reagent. Recently, several visible dyes have been developed for the staining of protein in electrophoresis (22). Many of them can reach the sensitivity at the ng level, and some of them, such as 3, 3′-diethyl-9-methyl-4,5,4′,5′-dibenzothiacarbocyanine (Stain-All), can simultaneously stain DNA and RNA with the appearance of different colors.

A complex between the dye, Methylene Blue, and protein has been used to quantitate the growth of cells in culture and their inhibition by cytotoxic drugs. Cultures are stained, destained, then solubilized overnight in a 1% aqueous Sarkosyl solution, and quantified at 620 nm. This assay can be automated by using 96-well microtiter plates and commercially available spectrophotometers designed for enzyme-linked immunosorbent assays (ELISA) (23). The dye complex can also show specificity and can be used to assay a single protein in a specimen. For example, serum albumin can be determined by its high affinity binding to Bromocresol Green (24).

Another important colorimetric method by complex formation in clinical laboratories is the measurement of metal ions by chelators. For example, serum iron levels are measured by the complex formation between ferrous and ferrozine. Serum iron can be determined either with or without the removal of proteins by trichloroacetic acid precipitation. Ferric is usually reduced to ferrous by ascorbic acid. The complex of Fe^{2+}-ferrozine has a dark violet color with an absorbance at 562 nm. Advantages of this method are its simplicity, sensitivity (molar absorbance = 27,900), and the constant absorbance in a wide range of pH (from pH 4–10) (25).

Colorimetry is commonly used for water testing, including specific impurities, such as ammonia, calcium, chlorine, copper, iron, nitrite, phenol, phosphate, sulfate, and sulfide, or total hardness. These tests are available in kit form and can be used with portable colorimeters for field testing. The methods generally utilize either complex formation or derivatization of the inorganic impurity to yield a highly colored compound.

Derivatization. Besides complex formation, substances can be detected colorimetrically after chemical modification to give colored products. One example is the diazotization of bilirubin. As mentioned previously, the direct measurement of bilirubin by its yellow color is inaccurate, because there are many pigments in serum that can interfere with the detection. For a more reliable assay, bilirubin is reacted with diazotized sulfanilic acid to give azobilirubin, which is red-violet in moderately acid solution and blue in strongly acid or alkaline solution. Most of the methods currently used in clinical laboratories (e.g., the Jendrassik–Grof method and the Malloy–Evelyn method) are based on this diazotization reaction.

Bilirubin exists in serum in two forms, the glucuronide-conjugated and the free form. The conjugated form (clinically known as "direct bilirubin") is more soluble in water and can be detected by a direct reaction with the diazo reagent. The free form (clinically known as "indirect bilirubin") is less soluble in water and can be detected by diazo reagent only if other reagents are also included. In the Malloy–Evelyn method, ethanol is added to increase the solubility of free bilirubin. In the Jendrassik–Grof method, caffeine–benzoate is added to displace serum protein-bound bilirubin. Therefore, both free and conjugated bilirubin can be detected by the diazo reagent. The Jendrassik–Grof method is generally considered the method of choice for the measurement of bilirubin in most clinical laboratories (26). The diazo reagent in this method is a mixture of sulfanilic acid and sodium nitrite in hydrogen chloride. This reagent should be prepared within 30 min of use. Serum is reacted with the diazo reagent for exactly 10 min, and the reaction is stopped by the addition of ascorbic acid solution. A strongly alkaline solution (tartrate in 1 N NaOH) is then added, and the color developed is compared with a standard curve of absorbance at 600 nm. Bilirubin is extremely sensitive to light. Sunlight can markedly decrease the bilirubin content in samples (as much as 50%/h). However, serum specimens can be stored for many weeks or months without appreciable change of bilirubin content if they are kept in the dark in a freezer. Other examples of derivatization include the determination of cholesterol by Liebermann–Burchard reaction. In this reaction, cholesterol is reacted with a mixture of acetic anhydride, acetic acid, and sulfuric acid to give a bluish green product that can be measured colorimetrically.

Enzymatic Conversion. Enzymatic conversion can be used to determine concentrations by the measurement of either the loss of substrate, the creation of product, or the change of the cofactor (coenzyme). Nicotinamide adenine dinucleotide (NAD) and nicotinamide adenine dinucleotide phosphate (NADP) and their respective reduced forms, NADH and NADPH are cofactors that have been extensively utilized for analytical purposes in colorimetric assays. These cofactors serve as the natural oxidizing and reducing agents in a wide variety of enzyme systems. With the appropriate enzyme, they can selectively oxidize or reduce a single substrate in the presence of innumerable other compounds, making possible the analysis of a single compound in a complex mixture. Both NADH and NADPH have identical absorption bands with peak absorption at 340 nm. The compounds NAD and NADP do not absorb at this wavelength. Therefore, changes in oxidation or reduction can be measured colorimetrically. In addition, the reduced forms can be completely destroyed at acidic pH without affecting the oxidized forms and the oxidized forms can be completely destroyed at basic pH without affect the reduced forms (27).

The measurement of glucose-6-phosphate in the range of 20–200 μM can be done in one step by monitoring the reduction of NADP to NADPH. This reaction is carried out by the oxidation of glucose-6-phosphate to 6-phosphate gluconolactone by the enzyme glucose-6-phosphate dehydrogenase, for which NADP is the coenzyme and is reduced to NADPH. The reaction is quantitated by measuring the 340 nm absorption of NADPH after completion of the reaction. Biological substances that do not react directly with nicotinamide nucleotides can be analyzed in this system by one or more additional enzymes. For example, glucose can be determined by the following two-step reaction that convert NADP to NADPH.

$$\text{Glucose} + \text{ATP} \xrightarrow{\text{hexokinase}} \text{Glucose-6-phosphate} + \text{ADP}$$

$$\text{Glucose-6-phosphate} + \text{NADP} \xrightarrow[\text{dehydrogenase}]{\text{glucose-6-phosphate}} \text{6-Phosphate gluconolactone} + \text{NADPH} + \text{H}^+$$

An example of a three-step assay is the enzymatic analysis of inorganic phosphate (P_i), carried out with three simultaneous reactions, ends in the conversion of NADP to NADPH (28).

$$\text{Glycogen} + P_i \xrightarrow{\text{phosphorylase}\,\alpha} \text{Glucose-1-phosphate}$$

$$\text{Glucose-1-phosphate} \xrightarrow{\text{phosphate glucomutase}} \text{Glucose-6-phosphate}$$

$$\text{Glucose-6-phosphate} + \text{NADP} \xrightarrow{\text{glucose-6-phosphate dehydrogenase}} \text{6-Phosphate gluconolactone} + \text{NADPH}$$

Hydrogen peroxide can be readily quantitated colorimetrically by its peroxidase-catalyzed reaction with a colorless chromogenic oxygen acceptor to form an intensely colored product. This reaction can therefore be used to measure the concentration of any organic compound that, on reaction, will produce hydrogen peroxide. For example, glucose levels in serum can be determined by indirect detection using the enzyme glucose oxidase. This enzyme catalyzes the oxidation of glucose to gluconic acid and hydrogen peroxide. The amount of hydrogen peroxide produced can be detected by reaction with peroxidase, and most commonly *o*-dianisidine. The oxidized product of *o*-dianisidine has a strong absorbance ~540 nm. The overall reactions are as follows:

$$\text{Glucose} + O_2 + H_2O \xrightarrow[\text{oxidase}]{\text{glucose}} \text{Gluconic acid} + H_2O_2$$

$$H_2O_2 + o\text{-Dianisidine} \xrightarrow{\text{peroxidase}} H_2O + \text{Oxidized } o\text{-dianisidine}$$

Since this measurement is dependent on the color formation of the oxidized chromogen, other substances in the sample can interfere with this reaction by competing with chromogens for hydrogen peroxide and by reducing the final color intensity. Some of the interfering substances in serum are creatine, uric acid, ascorbic acid, bilirubin, and glutathione. Therefore, results obtained directly from serum tend to be lower than the true values. Serum samples, especially with red cells, or extensive hemolysis require precipitation of the protein to remove interfering enzymes, with measurements carried out on the protein-free filtrates. Direct measurements of glucose from urine specimens cannot be done by the glucose oxidase method because of the presence of enzyme inhibitors.

Glucose oxidase is highly specific to β-d-glucose. In aqueous solutions, glucose exists 36% in the α form and 64% in the β form. The same ratio of the two forms is also found in serum. Crystalline glucose, however, can be either the α or β form, depending on the conditions of crystallization. In order to correct the difference in standard solutions, some commercial preparations of glucose oxidase contain another enzyme, mutarotase, which accelerates the conversion of α form to β form during the assay. Alternatively, standard solutions from crystalline glucose can be prepared 2 h before the determination to allow the mutarotation to reach equilibrium. The final assay solution contains the following components: glucose oxidase ($5\,\mathrm{U{\cdot}mL^{-1}}$), peroxidase ($16\,\mathrm{U{\cdot}mL^{-1}}$), and *o*-dianisidine ($0.6\,\mu\mathrm{mol{\cdot}mL^{-1}}$) in a pH 7.0 phosphate buffer. Under these assay conditions, glucose can be measured at a range of up to $250\ \mathrm{mg{\cdot}dL^{-1}}$. Samples with higher glucose concentrations should be diluted before the determination. Note that most chromogens used in the peroxidase reaction (e.g., *o*-dianisidine and *o*-tolidine) are potential carcinogens, and precautions should be taken when handling these compounds.

Colorimetric assays have found substantial applications in determination of concentration by ELISA. For example, the previously described assay to measure glucose concentration has been adapted as follows (29). The production of hydrogen peroxide from glucose is catalyzed by glucose oxidase, an enzyme consisting of apoglucose oxidase and flavin adenine dinucleotide (FAD) cofactor. If a ligand is bound to FAD and antibodies to that ligand are added to the solution, the enzyme will be inactive. Competition by free ligand will make conjugated FAD available for apoglucose oxidase. Since this reaction is enzymatic, excess glucose can be added, which leads to amplification of the signal. Therefore, very low concentrations of ligand can be assayed colorimetrically by the oxidation of glucose.

Besides glucose, the production of hydrogen peroxide as an intermediate has been employed to measure a number of clinically important substances including lecithin, high density lipoprotein cholesterol, phospholipids, digoxin, and triglycerides in human serum (30). In the last example, triglycerides are hydrolyzed to glycerol and fatty acid with lipase. The resulting glycerol is phosphorylated by l-α-glycerophosphate oxidase to produce hydrogen peroxide, which reacts in the peroxidase-catalyzed coupling of 4-aminoantipyrine and sodium 2-hydroxy-3,5-dichlorobenzene sulfonate to form an intense red product.

Kinetic Measurement

Kinetic measurements are generally used to determine the activity of enzymes. The expression of enzyme activity units (U) has been extremely arbitrary and inconsistent over the years. Historically, activity has been measured colorimetrically, and often activity for many common enzymes is expressed as an initial rate of absorbance change of a particular chromogen at the appropriate wavelength per unit time. More recently, enzyme activities have been expressed on a molar basis (i.e., the molar rate of destruction, or creation of substrates or products per unit time). Kinetic measurement of enzyme activity requires more control than quantitative measurements, since activity is usually a function of pH, ionic strength, temperature, substrate concentration, and the presence of activators and inhibitors.

Direct Measurement. An enzymatic reaction can be monitored by the measurement of either the rate of loss of the substrate, the formation of the product, or the rate of change of the cofactor (coenzyme) concentration. All of these methods are commonly used to determine enzyme activity.

Substrate. In an enzymatic reaction, which converts a substrate to a colored product or a colored substrate to a colorless product, enzymatic activity can be detected colorimetrically. An example of this type of measurement is prostatic acid phosphatase determination (31). Acid phosphatase is present in many tissues, including bone, liver, kidney, erythrocytes, and platelets. Its level in serum is measured as a diagnostic for the detection of metastatic, prostatic carcinoma. Therefore, substrates specific to prostatic acid phosphatase isoenzyme are most desirable for this assay. One of the most commonly used substrates is thymolphthalein monophosphate, which, upon hydrolysis by the enzyme, produces thymolphthalein, a compound with intensive absorbance at 590 nm in alkaline solution.

$$\text{Thymolphthalein monophosphate} \xrightarrow[\text{phosphatase}]{\text{acid}} \text{Thymolphthalein} + \mathrm{HPO_4^{2-}}$$

The course of this reaction can be monitored by a direct colorimetric measurement of product formation. Note that thymolphthalein monophosphate is not completely specific for prostatic acid phosphatase. However, unlike acid phosphatase from other sources, prostatic acid phosphatase can be inhibited by tartrate. Thus, from the assays of the enzyme activity in the presence or absence of tartrate, one can determine the phosphatase activity specific to the prostatic secretion. Acid phosphatase is extremely labile at the neutral pH of normal serum. Therefore, specimens for the enzyme measurement should be handled on ice and delivered to the laboratory as rapidly as possible. Serum separated in the laboratory should be acidified by acetate buffer to a pH range (pH 5–6) to stabilize the enzyme. Samples should be stored in the freezer if they are not to be assayed on the same day.

Acid phosphatase activity is highly dependent on pH and the specific ion in the buffer. Small changes in these parameters may cause a large difference in the enzyme activity measurements. To avoid a discrepancy between assays, a standardized procedure has to be followed carefully. Additional factors, such as the ratio of serum sample to the volume of final mixture, surfactant (Brij-35) for activation of enzyme, and the source and concentration of the substrate, must be consistent. For example, thymolphthalein monophosphate obtained from different commercial sources has been found to give as much as a 40% deviation in the enzyme activity by the colorimetric measurement. A typical assay procedure uses a substrate solution consisting of 0.6 mL of 0.15 M acetate buffer (pH 5.4), 1 mM thymolphthalein monophosphate and 1.5 $\text{g}\cdot\text{L}^{-1}$ Brij-35, a sample volume of 50 μL serum, a 30 min incubation at 37 °C, and final color development in 1 mL of 0.1 M NaOH and 0.1 M Na_2CO_3. The absorbance at 590 nm is then measured. In controls, the substrate solution is incubated without serum sample. Acid phosphatase activity is determined by subtracting the reading of the control from that of the sample.

The activity of a large number of proteolytic enzymes can be measured directly using specific synthetic substrates designed for that purpose. For example, the activity of leucine aminopeptidase can be directly measured by the hydrolysis of l-leucyl-β-naphthylamide to β-naphthylamine, which can be read at 560 nm. The clinically important γ-glutamyl transpeptidase can be measured by its reaction with glutamyl nitroanilide to form nitroaniline, which can be read at 405 nm.

Cofactors. The cofactors NAD and NADP find wide use in the kinetic measurement of enzyme activity, as well as in the previously discussed quantitative measurement of substrate concentration. One of the most important enzymes to be measured in clinical laboratories is lactate dehydrogenase. Marked increase of the enzyme level has been found following myocardial infarction. Elevations have also been reported in leukemia, in anemias, and in some liver diseases. This enzyme catalyzes the interconversion of lactate and pyruvate in the presence of NAD or NADH.

$$\text{Lactate} + \text{NAD} \xrightleftharpoons[\text{dehydrogenase}]{\text{lactate}} \text{Pyruvate} + \text{NADH}$$

In clinical laboratories, the reaction can be detected in either direction (i.e., using either lactate or pyruvate as substrate). A simple colorimetric method to detect the change of absorbance at 340 nm is sufficient to measure the enzyme activity (32). Generally, a small aliquot of serum sample is added to a cuvette and is mixed with a substrate solution containing either lactate and NAD or pyruvate and NADH. The reaction mixture in the absence of enzyme is set up, and the absorbance at 340 nm is measured. A dilution of enzyme is added and the OD_{340} is either monitored continuously or measured every minute or two for an appropriate time interval. The initial rate of increase in absorbance will be linear in time and proportional to the quantity of enzyme. The enzyme activity will therefore be proportional to the rate of change of the absorbance. A standard assay procedure is performed at 30°C. When the absorption change is measured in a spectrophotometer without constant temperature equipment, the effect of temperature on the enzyme activity must be considered. For example, the enzyme activity measured at 30 °C is 1.44-fold higher than that at 25 °C. Any enzymes that require the NADs as cofactors can be assayed in this manner. In clinical laboratories, lactate dehydrogenase is usually determined with samples of serum. Normally, serum contains no inhibitors or interfering substances for this enzyme assay. However, blood samples with marked hemolysis should be avoided, because they may give false elevations of this enzyme in the serum. It has been reported that commercial NADH contains inhibitors for the dehydrogenase reactions. Therefore, when pyruvate is used as the substrate for lactate dehydrogenase determination, inhibitors in the NADH solution should be considered. Many other enzymes can be determined by direct colorimetric measurement of NAD–NADH or NADP–NADPH conversion. Some of these enzymes with clinical importance are isocitrate dehydrogenase, glutamate dehydrogenase, and glucose-6-phosphate dehydrogenase.

Indirect Measurements. The activity of an enzyme that is not NAD or NADP dependent can nonetheless be measured with this system if its products are substrates for other enzymatic reactions requiring pyridine nucleotides. For example, phosphate glucomutase can be determined as follows

$$\text{Glucose-1-phosphate} \xrightarrow{\text{phosphate glucomutase}} \text{Glucose-6-phosphate}$$

$$\text{Glucose-6-phosphate} + \text{NADP} \xrightarrow[\text{dehydrogenase}]{\text{glucose-6-phosphate}}$$

$$\text{6-Phosphate gluconolactone} + \text{NADPH}$$

To prevent interfering side reactions, this assay is often carried out in two steps. The phosphate glucomutase is allowed to react for a measured time period, without added NADP or glucose-6-phosphate dehydrogenase after which the reaction is stopped with heat. The quantity of glucose-6-phosphate produced during that time period is then determined by carrying out the second reaction. Even though NADPH can be directly monitored at 340 nm, it can also be measured indirectly by the interaction with a tetrazolium salt, 3-(4,5-dimethylthiazol-2-yl)-2,5-diphenyltetrazolium bromide (MTT), to reduce the latter to a more intensely colored form that absorbs in the visible rather than the UV range. The reducing reaction occurs only in the presence of an intermediate electron carrier, such as phenazine methosulfate. The final color of the reduced tetrazolium salt has an absorption ~520 nm. This same reagent is now used in place of [^{3}H]thymidine to measure cell proliferation or complement mediated cytotoxicity in lymphocytes. 3-(4,5-Dimethylthiazol-2-yl)-2,5-diphenyltetrazolium bromide is cleaved to a dark blue formazan product only if the cell has active mitochondria while even newly dead cells show no color change.

The enzyme creatine kinase is measured in clinical laboratories for the detection of diseases related to skeletal or heart muscles. In the presence of magnesium ions, this enzyme catalyzes the reaction of creatine phosphate with adenosine diphosphate (ADP):

$$\text{Creatine phosphate} + \text{ADP} \xrightleftharpoons{\text{creatine kinase}} \text{Creatine} + \text{ATP}$$

This reaction can be detected by coupling with two other enzymes (33). The first enzyme, hexokinase, can use ATP, one of the products of the previous reaction, to convert d-glucose to d-glucose-6-phosphate, which is subsequently detected with the second enzyme, d-glucose-6-phosphate dehydrogenase, by measuring the conversion of NADP to NADPH as the increase of absorbance at 340 nm. The reactions catalyzed by the auxiliary enzymes are as follows:

$$\text{ATP} + \text{D-glucose} \xrightarrow{\text{hexokinase}} \text{ADP} + \text{glucose-6-phosphate}$$

$$\text{Glucose-6-phosphate} + \text{NADP} \xrightarrow{\text{glucose-6-phosphate}} \text{D-Glucose-6-phosphate lactone} + \text{NADPH}$$

Since creatine kinase in serum is rapidly inactivated by oxidation, reducing agents are required to reactivate the enzyme in each assay. The most commonly used reactivating compound is *N*-acetylcysteine. Other sulfhydryl compounds can also be used if they do not interfere with the measurement (i.e., absorbance at 340 nm, solubility, and odor). Serum with extensive hemolysis should be avoided, because it may give falsely elevated values. One of the factors from hemolyzed red cells is the enzyme, adenylate kinase, which can generate additional amounts of ATP from ADP without creatine phosphate. To eliminate this artifact, 3 m*M* of adenosine monophosphate (AMP) should be included in the assay solution to inhibit adenylate kinase activity. Higher concentrations of AMP are required in markedly hemolyzed serum samples. However, at high concentrations, AMP can also inhibit creatine kinase activity. The false activity contributed from enzymes other than creatine kinase can be detected by running an appropriate control, without creatine phosphate in the final assay solution. The coupling of three reactions in this manner leads to a complicated assay that requires 10 different reagents added to the sample. These include imidazole buffer at pH 6.7 (100 m*M*), creatine phosphate (30 m*M*), ADP (2 m*M*), Mg^{2+} (10 m*M*), d-glucose (20 m*M*), NADP (2 m*M*), AMP (5 m*M*), *N*-acetylcysteine (20 m*M*), glucose-6-phosphate dehydrogenase ($1.5\,U\cdot mL^{-1}$), and hexokinase ($2.5\ U\cdot mL^{-1}$).

FUTURE DEVELOPMENTS

Colorimetric methods will continue to be important analytical tools in research and clinical laboratories. Applications that replace the need for radioactive compounds will continue to be developed because of the increasing costs and difficulties associated with the processing and disposal of radioactive materials. In the same way that the ELISA has replaced radioimmunoassay (RIA), colorimetric methods will continue to replace applications requiring radioisotopes. For example, in recent developments of microarray technology, colorimetry is still one of the major detection methods for the measurement of the signals (14,34). However, the sensitivity of colorimetric methods is limited by the absorption of the chromophores, new reagents with very high extinction coefficients will need to be developed for direct colorimetric measurements (35). This limitation is also overcome by the coupling of a second reaction to the primary measurement. Such amplifying systems will be increasingly used as a means to increase the colorimetric sensitivity. Modified colorimetric methods, such as the kinetic spectrophotometric method, can also markedly improve the sensitivity of the determination. For example, trace concentrations of iron can be determined by the oxidation of *o*-tolidine (36). The rate of oxidation, which can be measured colorimetrically at 440 nm for the oxidized *o*-tolidine derivative, is proportional to the concentration of ferric ion. This method can detect as low as $4 \times 10^{-7} M$ iron in acidic solutions. The use of lasers as light sources in colorimetry has opened a new frontier of analytical chemistry. The method, called “thermal lens spectrophotometry” is based on the direct measurement of the absorbed radiant energy by the “thermal lens effect” and can detect a very small absorption by increasing the power of the heating laser (12). This method can determine accurately an absorbance that is lower than 0.001.

Since the sensitivity of fluorimetry is often greater than that of colorimetry, it will probably find more new applications than colorimetry especially in biomedical measurements. However, the instrumentation and the stability of fluorimetric measurements are generally more expensive and more complex than colorimetry. In addition, new colorimetric instruments have been developed that are capable of measuring several wavelengths simultaneously, of processing large numbers of samples automatically, and of reading the results of samples contained in multiwell or multicuvette containers. Furthermore, colorimeters with computer interfaces will automatically calculate results, will average multiple determinations, and will print and store the final data. This kind of instrumentation, already widely used in ELISA and microarrays, will be increasingly borrowed for use in other colorimetric assays. Therefore, colorimetry will continue to be used because of its speed, simplicity, versatility, and low cost. It can be anticipated that more sophisticated methods of colorimetric measurement, in combination with other advanced technologies such as nanotechnology (11), will continue to be developed into new analytical methods with various biomedical and clinical applications.

BIBLIOGRAPHY

1. Bugay DE. Characterization of the solid-state: spectroscopic techniques. Adv Drug Deliver Rev 2001;48:43–65.
2. Stephenson GA, Forbes RA, Reutzel-Edens SM. Characterization of the solid state: quantitative issues. Adv Drug Deliver Rev 2001;48:67–90.
3. Yu LX, Lionberger RA, Raw AS, D’Costa R, Wu H, Hussain AS. Applications of process analytical technology to crystallization processes. Adv Drug Deliver Rev 2004;56:349–369.
4. Stone DK, Xie X-S, Racker E. An ATP driven proton pump in clathrin-coated vesicles. J Biol Chem 1983;258:4059.
5. Warburg O, Christian W. Isolation and crystallization of enolase. Biochem Z 1941;310:384.
6. Morozkin ES, Laktionov PP, Rykova EY, Vlassov VV. Fluorometric quantification of RNA and DNA in solutions containing both nucleic acids. Anal Biochem 2003;322:48–50.
7. Sapan CV, Lundblad RL, Price NC. Colorimetric protein assay techniques. Biotechnol Appl Biochem 1999;29:99–108.
8. McMahon DJ, Brown RJ. Milk coagulation time—linear relationship with inverse of rennet activity. J Dairy Sci 1983;66: 341.
9. Li H, Rothberg LJ. Label-free colorimetric detection of specific sequences in genomic DNA amplified by the polymerase chain reaction. J Am Chem Soc 2004;126:10958–10961.

10. Liu J, Lu Y. Accelerated color change of gold nanoparticles assembled by DNAzymes for simple and fast colorimetric Pb^{2+} detection. J Am Chem Soc 2004;126:12298–12305.
11. Elghanian R, Storhoff JJ, Mucic RC, Letsinger RL, Mirkin CA. Selective colorimetric detection of polynucleotides based on the distance-dependent optical properties of gold nanoparticles. Science 1997;277:1078–1081.
12. Long ME, Swofford RL, Abrecht AC. Thermal lens technique: A new method of absorption spectroscopy. Science 1976;191: 183.
13. Sittampalam GS, Kahl SD, Janzen WP. High-throughput screening: advances in assay technologies. Cur Opin Chem Biol 1997;1:384.
14. Ihara T, Tanaka S, Chikaura Y, Jyo A. Preparation of DNA-modified nanoparticles and preliminary study for colorimetric SNP analysis using their selective aggregations. Nucleic Acids Res 2004;32:e105.
15. Liang RQ, Tan CY, Ruan KC. Colorimetric detection of protein microarrays based on nanogold probe coupled with silver enhancement. J Immunol Methods 2004;285:157–163.
16. Van Kampen EJ, Zijlstra WG. Spectrophotometry of hemoglobin and hemoglobin derivatives. Adv Clin Chem 1983;23:199.
17. Henry RJ, Golub OJ, Berkman S, Segalove M. Critique on the Icterus index determination. Am J Clin Pathol 1953;23:841.
18. Kingsley GR. Procedure for serum protein determinations. Stand Methods Clin Chem 1972;7:199.
19. Lowry OH, Rosebrough NS, Farr AL, Randall RI. Protein measurement with the Folin phenol reagent. J Biol Chem 1951;193:265.
20. Rylatt DB, Parish CR. Protein determination on an automatic spectrophotometer. Anal Biochem 1982;121:213.
21. Peats S. Quantitation of protein and DNA in silver stained gels. Anal Biochem 1984;140:178.
22. Jin L-T, Choi J-K. Usefulness of visible dyes for the staining of protein or DNA in electrophoresis. Electrophoresis 2004;25: 2429.
23. Finlay GJ, Baguley BC, Wilson WR. A semiautomated microculture method for investigating growth inhibiting effects of cytotoxic compounds on exponentially growing carcinoma cells. Anal Biochem 1984;139:272.
24. Webster D. The immediate reaction between bromcresol green and serum as a measure of albumin content. Clin Chem (Winston-Salem, NC) 1977;23:663.
25. Stookey LL. Ferrozine—a new spectrophotometric reagent for iron. Anal Chem 1970;42:779.
26. Jendrassik L, Grof P. Simplified photometric methods for the determination of the blood bilirubin. Biochem Z 1938; 297:81.
27. Lowry O, Passonneau J. A Flexible System of Enzymatic Analysis. New York: Academic Press; 1972. Chapt. 5.
28. Fawaz EN, Roth L, Fawaz G. The enzymatic estimation of inorganic phosphate. Biochem Z 1966;344:212.
29. Morris DL, Ellis PB, Carrico HJ, Yeager RM, Schroeder HR, Schroeder JP, Albarella JP, Boguslaski RC. Flavin adenine dinucleotide as a label in homogeneous colorimetric iminunoassays. Anal Chem 1981;53:658.
30. Fossati P, Prencipe L. Serum triglycerides determined colorimotrically with an enzyme that produces hydrogen peroxide. Clin Chem (Winston-Salem, NC) 1982;28:2077.
31. Ewen LM, Spitzer RW. Improved determination of prostatic acid phosphatase (sodium thymolphthalein monophosphate substrate). Clin Chem (Winston-Salem, NC) 1976;22:627.
32. Babson AL, Philips GE. A rapid colorimetric assay for serum lactic dehydrogenase. Clin Chim Acta 1965;12:210.
33. Szasz G, Gruber W, Bernt E. Creatine kinase in serum. 1. Determination of optimum reaction conditions. Clin Chem (Winston-Salem, NC) 1976;22:650.
34. Hoever M, Zbinden P. The evolution of microarrayed compound screening. Drug Discover Today 2004;9:358.
35. Hargis LG, Howell JA, Sutton RE. Ultraviolet and light absorption spectrometry. Anal Chem 1996;68:169R–183R.
36. Rooze H. Kinetic-spectrophotometric determination of trace levels of iron. Anal Chem 1984;56:601.

Further Reading

Evenson MA. Chapt. 3: Spectrophotomtric Techniques. In: Burtis CA, Ashwood ER, editors. Tietz Textbook of Clinical Chemistry. 3rd ed. Philadelphia (PA): W.B. Saunders; 1999. p 75–93. A widely used reference and textbook for clinical chemists. Chapter 3 covers both the concepts and the instrumentation of spectrophotometry.

Hargis LG, Howell JA, Sutton RE. Ultraviolet and light absorption spectrometry. *Anal Chem* 1996;68:169R–183R. A review includes a comprehensive list of reagents used for the spectrophotometric analysis of organic and inorganic compounds. It also includes a brief description of data processing and instrumentation. A total of 440 literatures are cited in this article.

Mikkelsen SR, Corton E. Bioanalytical Chemistry. Hoboken (NJ): John Wiley & Sons Inc., 2004. Chapt. 1. Spectroscopic Methods for Matrix Characterization. Chapt. 2. Enzyme. These two chapters focus on the biochemical and biomedical applications, especially to the spectroscopic measurement of protein concentrations and enzyme kinetics.

Pesce AJ, Frings CS, Gauldie J. Chapt. 4. Spectral Techniques. In: Kaplan LA, Pesce AJ, Kazmierczak SC, editors. Clinical Chemistry: Theory, Analysis, Correlation. 4th ed. St. Louis (MO): Mosby; 2003. p 83–106. This chapter includes a good description on the design of various types of spectrophotometers.

Skoog DA, West DM, Holler FJ, Crouch SR. Fundamentals of Analytical Chemistry. Brooks/Cole: 2004. A textbook in analytical chemistry with extensive coverage of both the principles and applications. Part V, Spectrochemical Analysis, includes: Chapt. 24. Introduction to Spectrochemical Analysis; Chapt. 25. Instruments for Optical Spectroscopy; and Chapt. 26: Molecular Absorption Spectroscopy.

See also ANALYTICAL METHODS, AUTOMATED; FLUORESCENCE MEASUREMENTS.

COMPUTERS IN CARDIOGRAPHY.

See ELECTROCARDIOGRAPHY, COMPUTERS IN.

COLPOSCOPY

MOSTAFA A. SELIM
ABDELWAHAB D. SHALODI
Cleveland Metropolitan
General Hospital
Palm Coast, Florida

Today, fewer women die annually from carcinoma of the cervix then in any period in modern history. Increased utilization of cervical cytology (Pap smears) and better assessment and evaluation of patients with abnormal Pap smears are important reasons for the progress in this field.

The Papanicolaou stained cytology smear is an invaluable tool for detecting cervical carcinoma. Such a test depends on collection of exfoliating cells from the cervix, spreading the material on a glass slide, and staining with special stains in order to identify the microscopic structures in nuclei and the cytoplasm of the cell. An abnormal smear is called positive and a normal smear is called negative for malignancy. However, in recent years the incidence of false-negative smears has been recognized to be significant, varying between 15 and 22% (1–4). This high incidence of false-negative smears emphasizes the need for histological study of the abnormal cervix before any therapy is started, regardless of the findings from the cytology smear.

In order to fill the serious gap in the screening of cervical cancer and its precursors created by the high incidence of false-negative smears, colposcopy is utilized (3–6).

THE COLPOSCOPE

The word colposcopy simply means viewing the vagina. The colposcope is a binocular, long-focal-length, wide-field microscope with which it is possible to examine the epithelium and subepithelial vascular pattern of the cervix at magnifications varying from 6 to 40×. Figure 1 shows a typical instrument. A beam of light is projected between the objectives so that the cervix is well illuminated. To help the visualization of blood vessels, a green filter may be fitted to the light source. This adds contrast in viewing microvessels against the tissue. Photographic apparatus consisting of a prefocused lens system, a 35 mm camera, and a flash tube are attached to the colposcope in order to document the findings. The photographs obtained using 35 mm film are two dimensional (2D). To obtain three-dimensional (3D) images, the instrument may be fitted with a stereocamera that produces image pairs. These pairs give a stereoscopic effect when viewed in a special viewer. The colposcope, the camera, and the flash tube are mounted on a fixed, sturdy base with rack-and-pinion drives for fine positioning and focusing. Modern colopo-scope is equipped with digital video camera interfaced microcomputer.



Figure 1. Colposcope with camera and flash attached.

FINDINGS

A colposcopic examination is considered satisfactory whenever it is possible to view all of the critical portions of cervical anatomy, and if an abnormal lesion is seen, the upper margin of this lesion must be adequately visualized. Specifically, it is necessary to view the entire transformation zone. The transformation zone is the lower segment of the endocervical canal. This area is normally covered by columnar epithelium, although through the process of metaplasia some areas or the entire zone can be transformed into squamous epithelium. The normal transformation zone is recognized by the presence of small glandular openings, nabothian cysts, and a normal pattern.

The procedure can be performed quickly and easily on out-patients without anesthesia. However, the gynecologist needs intensive training in order to master the interpretation of what they sees.

The colposcope was first devised by Hinselmann in 1925 at Hamburg, Germany. The instrument became popular in the German speaking and Latin nations. It was accepted in the English speaking nations in the 1960s. One of the reasons for the delay in accepting colposcopy was that all of the original studies and the terminology were written in German (7,8).

INDICATIONS FOR COLPOSCOPY (3–6)

Ideally all patients, during their gynecological examination, at one time or another ought to be examined colposcopically. However, since colposcopy is time consuming and requires specialized training, this is usually not possible, and thus the following indications are recommended:

1. All patients with abnormal cervical cytology.
2. All patients with an abnormal lesion on the cervix, vulva, or vagina.
3. Cases of persistent cervicitis, vulvitis, or vaginitis.
4. Pregnant patients with unexplained vaginal bleeding.
5. All offspring of diethylstilbestrol-exposed pregnancies.

Colposcopy plays an essential role in evaluating these patients. The colposcope helps to pinpoint the abnormal area. However, the final diagnosis has to await histopathological diagnosis. This tissue diagnosis is obtained through endocervical curettings, punch biopsy, and/or cone biopsy according to the individual case, as illustrated in Fig. 2.

Recent studies confirmed that colposcopy could be utilized in follow-up in conservative management of low grade



Figure 2. Protocol for management of patients.

precancerous lesions, as most of them regress on its own. In addition, the colposcope can help in detecting and guiding treatment of genital infections.

A movable, counterweighted arm is used for rough positioning of the colposcope. The arm is fixed to the examining table or to a heavy wheeled base (5,6).

There are several commercially available colposcopes. Manipulation, magnification, length, intensity, and type of green filter vary from one instrument to another. For detailed inspection of the vascular pattern, the magnification ought to be not <14× and preferably 16× (7,8).

TECHNIQUE OF COLPOSCOPY

1. The cervix and the upper vagina are examined, at a magnification of not < 14×, after excess mucus is removed by cotton swab moistened by physiological saline, which allows the subepithelial architecture to be seen in greater detail. To enhance visibility the green filter should be used.
2. Acetic acid (3%) is gently applied by a cotton swab. Abnormal epithelium will become whitish and sharply demarcated. The normal squamous epithelium appears pink, and columnar epithelium will have a grape-like appearance. The effect of the acetic acid will last ∼ 30–40 s.
3. Endocervical curetting and punch biopsies should be done for all unusual-appearing areas. Specimens should be put in separate formalin-containing bottles.
4. Bleeding is usually minimal and does not need any packing. However, during pregnancy, when vascularity is increased, Oxycel, Surgicel packing, or the use of Munsell's solution may be necessary.

Normal pattern of blood vessels. An example of a satisfactory colposcopic finding is shown in Fig. 3. The sketch identifies the various features of this view of the cervix. An example of an unsatisfactory view of the cervix is shown in Fig. 4. In this case the transformation zone as indicated in the sketch is not fully visualized; the columnar epithelium is not seen and/or the upper margin of the lesion extends into the endocervical canal and thus cannot be fully visualized.

In evaluating satisfactory colposcopic findings, many factors must be considered. It is beyond the scope of this article to provide a detailed description of the different patterns seen in colposcopy, but a general idea of what is looked for can be presented. In order to reach an adequate diagnosis, the colposcopist must consider the following criteria in observing the uterine cervix: (*1*) vascular pattern, (*2*) intercapillary space, (*3*) color and texture, (*4*) surface pattern, and (*5*) sharpness of the line of demarcation between the lesion and the rest of the cervix.

The lower segment of the endocervical canal that extends to the visible part of the cervix is the transformation zone. This area is originally and normally covered by columnar epithelium. Through a process of metaplasia, some areas or the whole zone can be transferred into squamous epithelium. The normal transformation zone is recognized by the presence of small glandular openings, nabothian cysts, and a normal pattern of blood vessels (Fig. 3).

Vascular Pattern

Normal epithelium vessels appear as fine dots or a network of capillaries. However, in abnormal pathology, the individual vessel becomes prominent, leading to punctuation (Fig. 5). A mosaic pattern is due to increased communication between the individual vessels, arranged parallel to the surface epithelium (Fig. 6). Atypical vessels are capillaries that are irregular in shape, size, course, and arrangement (Fig. 7).

Intercapillary Space. Due to rapid proliferation of the abnormal epithelium, the intercapillary distance between the vessels is increased. The intercapillary distance of normal capillaries varies between 50 and 250 µm with an average of 100 µm. The intercapillary distance in early



Figure 3. (a) Areas of glandular epithelium extending to ectocervix became whitish upon addition of acetic acid. Note the grape-like appearance of the glandular epithelium; no abnormal vessels or lesions are seen, and the lower end of the cervical canal is adequately visualized. (b) Sketch of the transformation zone, consisting of columnar and squamous epithelium. The squamous–columnar junction is part of the transformation zone. In the lower left corner of the diagram there is an island of glandular epithelium in the middle of the squamous epithelium. Note that the color of the squamous epithelium in the transformation zone is identical to that of the original squamous epithelium.

intraepithelial neoplasia (CIN 1) is 200 μm, while in severe intraepithelial neoplasia (CIN 3) it is 450–550 μm (6) (Figs. 5 and 6).

Color Tone. Abnormal epithelium is darker than normal epithelium, and upon addition of acetic acid it temporarily becomes whitish (Figs. 5 and 6).

Surface Epithelium. Abnormal lesions are uneven, granular, papillomatous, or nodular (Figs. 5–7). Normal squamous epithelium is smooth, whereas columnar epithelium has a grape-like appearance (Fig. 3).

Line of Demarcation. The abnormal epithelium is usually raised and well demarcated from the normal epithelium, especially after addition of acetic acid (Figs. 3–7).



Figure 4. (a) Unsatisfactory view of the cervix and (b) accompanying sketch. This cervix is covered completely by squamous epithelium; no glandular epithelium is seen, including the lower endocervical canal. The left side of the cervix has a large red region. This region is covered by newer squamous epithelium, which is more transparent so that the normally arranged vessels are seen though it. The entire field of the figure is covered by squamous epithelium. Neither glandular epithelium nor the squamocolumnar junction can be seen. This represents an unsatisfactory colposcopic examination.

ACCESSORY INSTRUMENTS TO COLPOSCOPY

The best examination table is one that can be adjusted for height and tilt, is in the lithotomy position, and is preferably electrically operated. Punch biopsy forceps ought to be sharp with square jaws (Fig. 8) in order to obtain well-oriented, adequate tissue for pathological examination. In addition, in order to prevent loss of fragments of tissue obtained by endocervical curettings, the curette must be a closed-sided instrument to create negative suction (Fig. 9).

To aid in visualization of the endocervical canal, which cannot be seen by a colposcope, a Hamou microcolpohysteroscope can be utilized (Fig. 10). The technique utilizes



Figure 5. Punctation. Large, well-defined areas of the transformation zone became white after addition of acetic acid. The areas are covered by punctate of blood vessels with wide intercapillary distances. These abnormal lesions do not extend into the canal, and the lower canal columnar epithelium is seen and is normal. Some glandular openings are seen in the lower right part of the figure.



Figure 6. Large transformation zone covered by a mosaic pattern, inside well-defined borders. The areas became whitish after addition of acetic acid. The upper margin of the abnormal lesion can be adequately seen. The columnar epithelium is seen and appears to be normal. These findings are typical for carcinoma *in situ*, a precancerous lesion.



Figure 7. Highly abnormal cervix covered by atypical vessels with increased intercapillary distance. It is nodular and shows an exophytic growth pattern with a whitish and glossy appearance. These findings are indicative of invasive carcinoma.



Figure 8. Punch biopsy forceps. Note the square jaw necessary to obtain an adequate and well-oriented biopsy for pathological examination.



Figure 9. Curette. Note that it is serrated and open only from one side in order to prevent loss of tissue. The stem is hollow to create a suction effect.



Figure 10. Hamou microcolpohysteroscope. Note that it has the same caliber as the curette and has an outlet for a fiberoptic light source.

the contact technique, thereby achieving ~ 60× magnification, and does not need any transmission media other than the normal mucus secretion of the endocervix. This method can aid in assessing the extent of the disease and may aid in defining the extent of cone biopsy, whenever it is needed to investigate or to treat the disease (9).

Digital Colposcopy (10–12)

Digital colposcopy is an improvement on regular colposcopy. Integrating video camera interfaced microcomputer and using real time image achieve this. Such arrangement allows computerized manipulation of the image signal. In order to manipulate the image by the computer it needs to be converted into matrix number. Each number is representing one point in image matrixes, called pixel. Each pixel has a value that corresponds to discrete gray level. The computer then converts the number back to analogue for display on the video.

Regular colposcope uses green filter to enhance visualization of blood vessels and discoloration. However, this has its limitation. Digital colposcopy has different ways to improve on this (e.g., spatial filtering the image). These are pixel-by-pixel process that creates a new image, where the pixels values are determined, taking into account the value of neighboring pixels.

A very significant advantage to digital colposcopy is that it allows storage of colposcopic images in digital format on different media. This gives an unlimited ways of storage and filing.

Digital colposcopy is useful in metric measurement of the lesions and accuracy of measurement improved by the new techniques and software. This measurements and the improvement in digital filing helps the clinician in accurate follow-up of the lesions for regression or progression. Recent clinical studies confirmed that it is possible to transmit the images for consultation: which proved of help to areas lacking specialists in the field of oncology. In addition digital colposcopy helps in quality control, follow-up and in teaching.

SUMMARY

The manuscript describes the history, the instrument of colposcope and the advances into the digital age. The significant clinical application of this instrument in diagnosis and treatment of precancerous,cancerous lesions of the cervix is described. The terminology used to explain the vascular changes in the cervix is defined.

BIBLIOGRAPHY

1. Selim MA, So-Bosita JL, Blair OM, Little BA. Cervical biopsy versus conization. Obstet Gynecol (NY) 1973;41:177–182.
2. Selim MA, So-Bosita JL, Neuman MR. Carcinoma *in situ* of the cervix uteri. Surg Obstet Gynecol 1974;139:697–700.
3. Selim MA, Vasquez HH, Masri R. Indications and experience in colposcopy in management of cervical neoplasia Surg Obstet Gynecol 1977;149:529–532.
4. Selim MA, Razi A. Cryosurgery for intraepithelial neoplasia of the cervix. Cancer (Philadelphia) 1980;46:2315–2318.
5. Sootra-Gartaux, Carter I, Jourdau-DeSilva N, Decremax P. Regression of low grade epithelial neoplasia. Obst Gynecol 2004;104:751–755.
6. Norman JE, et al. An evaluation of economic and suitability of screening for chlamydia trachomatis infection in women attending antenatal, abortion, colposcopy and family planning clinic in Scotland UK BJOG 2004;111:1261–1268.
7. Kolshad P, Stafl A, editors. Atlas of Colposcopy. Baltimore: University Park Press; 1972.
8. Jordan JA. Colposcopy in the diagnosis of cervical cancer and precursor. Clin Obstet Gynecol 1985;12:67–76.
9. Soutter WP, Fenton DW, Gudgeon P, Shoup P. Quantitative microcolpohysteroscope assessment of the extent of endocervical involvement by cervical intraepithelial neoplasia. Br J Obstet Gynecol 1984;91:712–715.
10. Craine BL, Craine ER. Digital imaging colposcopy. Basic concepts and application. Obs Gynecol 1993;82:869–873.
11. Craine BL, Craine ER, O'Toole CJ, Ji Q. Digital imaging colposcopy: corrected are measurements using shape- from -shading. IEEE Trans Med Imaging 1998;17:1003–1010.
12. Schadell D, et al. Suitability of digital colposcopy for telematic applications. Biomed Tech 2004;49:157–162.

See also CRYOSURGERY; CYTOLOGY, AUTOMATED; SEXUAL INSTRUMENTATION.

COMMUNICATION AIDS FOR THE BLIND. See BLIND AND VISUALLY IMPAIRED, ASSISTIVE TECHNOLOGY FOR.

COMMUNICATION DEVICES

ALBERT COOK
University of Alberta

INTRODUCTION

Augmentative and alternative communication (AAC) systems supplement, but do not replace other modes of communication such as speech, gestures, vocalizations, or facial expressions. The need for AAC, may be *congenital in utero* or *perinatal* (e.g., cerebral palsy or developmental disability) or a*cquired* (neurological conditions). The severity of need varies from mild to moderate to severe based on physical, cognitive and linguistic involvement. The overall prevalence from mild to severe for AAC needs is 0.2–0.6% of the total population (1). The age range encompasses three distinct ranges: infant to preschool, school age to teenage, and teenage to adult. The selection of systems to meet the needs of individuals in these age ranges is influenced by the experience that the individual brings to the use of AAC and the degree to which language and speech have been developed prior to the need for AAC. If the person has developed speech and language, and then subsequently lost those abilities, it is very different from the child born without speech and language who has never had the opportunity to develop those skills. Alternative communication needs may also change over time. For example, the needs of children change as they develop cognitive and language skills. In contrast, some disorders are degenerative and result in loss of function and decrease in skills (e.g., amyotrophic lateral sclerosis, multiple sclerosis). Using current technologies, we are able to meet the AAC needs for children who have cerebral palsy or developmental disabilities, individuals with good cognitive skills, and adults with degenerative diseases. Our current approaches are less effective for individuals who have mental retardation, are ambulatory, have dual sensory impairment, traumatic brain injury or are elderly.

NEEDS SERVED BY AAC

There are two basic communication needs that lead to the use of augmentative and alternative communication systems: conversation and graphics (2). These two needs differ in many important aspects. Conversational needs are those that would typically be accomplished using speech if it were available. Examples are an informal conversation with a friend, a formal oral presentation to a group of people, a telephone conversation, or a small group discussion. Much of conversational use focuses on interaction between two or more people. Light (3) describes four types of communicative interaction: (1) expression of needs and wants, (2) information transfer, (3) social closeness, and (4) social etiquette. Expression of needs and wants is the most basic of AAC needs and allows requests for objects or people to be made. Information transfer allows expression of ideas, discussion and meaningful dialogue. Social closeness refers to the ways in which communication serves to connect individuals to each other, regardless of the content of the conversation. Social etiquette is used to describe those formalities that we adapt to our listener. For example, students will speak differently to their peers than to their teacher. Graphic communication describes all the things that we normally do using a pencil and paper, computer, calculator, and other similar tools, and it includes writing, drawing, mathematics, and Internet access.

Rates of communication using speech vary between 150 and 250 words/min (4). In contrast, many AAC devices use a keyboard to generate messages. This can result in significantly lower rates of communication than for speech. For example, a trained, nondisabled typist can generate typed text during transcription at a rate of nearly 100 words/min. However, this is still only about two-thirds of the rate of speech. If this same typist is asked to compose rather than transcribe, then their rate will drop by 50% to a maximum of 50 words/min (5). Many people who have disabilities must rely on single-finger typing, and they may only be able to type at a maximum rate of 10–12 words/min. Scanning (see below) reduces the maximum rates to as low as 3–5 words/min. The great disparity in rates of communication between a speaking person and an AAC system user often results in the speaking person's dominating a conversation with a nonspeaking person. This renders the individual using an AAC device to a passive role in the conversation.

There are three types of graphic communication: writing, mathematics, and drawing/plotting. Since each of these types of graphic communication serves a different need, AAC devices designed to meet each type also have different characteristics. Writing results in an electronic (soft copy) or paper (hard copy) output. However, writing does not need to be via letters combined into words on a page. Other symbols (e.g., line drawings, pictures) can also be printed on paper and used, in place of written output. Since some devices allow the selection of whole words, which are then output to a printer, spelling is not a prerequisite for the generation of written output. Alternatively, a nonspeaking person can point to letters on a board and have an attendant write down the letters to accomplish writing tasks.

There are three types of writing: note taking, messaging, and formal writing, the requirements of which all differ (6). Portability is important for note taking since the needs may be in many different locations (e.g., home, library, school, job, or meetings). Note taking may require writing at a high rate in order to keep up with the speaker. Just as nondisabled persons typically use abbreviations and other shorthand notations, so do users of AAC writing devices. Words and phrases stored in an AAC device may further increase the rate of text entry. The difference between note taking and messaging is the recipient of the written output. Messaging typically results in a note made for another person to read. This affects the types of abbreviations and shorthand notations that are used. The writing rate may also be slower than note taking since the person receiving the message is not present and waiting for it. Individuals who have intellectual disabilities and use symbols for communication can also use messaging. For example, individuals living in group homes who wish to send messages to their families, but are unable to use voice communication over the telephone can use rubber stamps with the appropriate AAC symbols (7). These stamped messages are then FAXed to their significant others as a message. The family can respond by using a second set of rubberstamps with the symbols on them.

The most demanding type of writing is formal writing, including reports, school homework, writing for publication, and similar applications. Here, accuracy is of prime importance, with rate becoming secondary. Word processing allows accurate entry of written material, but some users may take up to several hours to create one page of written material. However, with an entry rate of 1.5 to 5 words/min, it can take 2.5 h or more, and the use of abbreviations and other input acceleration techniques is necessary to allow an individual to keep up with the demands of work or school.

The AAC systems for mathematics focus on the written manipulation of numbers required for arithmetic and higher mathematics, as opposed to calculator functions. The goal is to for the user to learn mathematics in a manner that is as close as possible to that used by nondisabled peers. Cursor movement is a key difference between written English (the cursor always moves left to right and moves down one line at the right margin) and mathematics, where the cursor moves left to right as we enter numbers to be added, but once we have a column of numbers, the cursor moves right to left as we enter the sum. Carry or borrow are concepts when learning to add or subtract, and children are taught to cross out the number at the top of the adjacent column and substitute the borrowed or carried value. These types of cursor movement are also required in a math worksheet for children who cannot use pencil and paper. Algebra requires special symbols (e.g., Greek letters) and the use of superscripts and subscripts. Statistics or calculus adds the need for special symbols such as summation signs and integral signs and the formatting of problems. Some commercial AAC devices include some or all of these mathematical functions.

The final type of graphic output is drawing used to convey information, to help us clarify our thinking, and for creative expression. Typically, we use pencils, paint and brush, or computer programs to draw. Many people who are unable to use these conventional means of drawing because of motor limitations utilize computer programs designed for drawing or plotting

CHARACTERISTICS OF AUGMENTATIVE COMMUNICATION SYSTEMS

The characteristics of AAC devices can be grouped into three major components shown in Fig. 1: (1) control interface, (2) processor, and (3) activity output (6). The control interface links to a selection method, selection set, and an optional user display. The processor is further broken down into components of (1) selection technique, (2) rate enhancement and vocabulary expansion, (3) vocabulary storage, (4) text



Figure 1. Characteristics of AAC systems.

editing, and (5) output control. The activity outputs to the communication partner include visual display, speech, and printer. A control port for external devices (e.g., computers or electronic aids to daily living) is sometimes included. Not every device includes all the individual functions shown in Fig. 1. In some cases, the functions shown in Fig. 1 are implemented in software using portable computers. Others are based on special purpose computers designed specifically for use as AAC devices.

Control Interface

The control interface is the way in which the user is able to make entries into the AAC device to generate a communication utterance or output. There are various types of interfaces based on the number of independent choices that can be made by an anatomical site or a combination of anatomical sites (e.g., hand, arm, head, chin, leg, foot).



Figure 2. Typical interfaces for augmentative communication systems, (a) paddle (tread) switch; (b) array of paddle switches (slot switch); (c) wobble switches; (d) joystick; (e) brow wrinkle switch; (f) sip and puff switch (pneumatic). (From Electronic Devices for Rehabilitation, New York: John Wiley & Sons, 1984, with permission.)

Keyboards, single or dual switches, and joysticks or multiple switch arrays are the most commonly used control interfaces for augmentative communication devices. A variety of switches used with AAC systems are shown in Fig. 2 (8).

Various types of keyboards are typically used for AAC devices. When a standard keyboard is not accessible due to limited fine motor control, enlarged keyboards are used with gross muscle movements (e.g, hand, foot, elbow activation). When range of motion prevents reaching all the keys, a contracted keyboard is used with finger or mouth stick activation. Keyboards may also be modified by the use of key guards that prevent accidental activation of keys. When keyboards of any type cannot be used, single or multiple switches are used. Some examples of these are shown in Fig. 3.

Selection Set

The selection set of the augmentative communication device presents the symbol system and possible vocabulary selections to the user. One type of selection set is the label on the keys of a keyboard. The selection set may include individual letters, words, phrases, or other symbols. The mode of presentation to the user may be display-based, chart-based, or memory-based (9). Display- and chart-based approaches present a list of vocabulary choices (e.g., words, letters, symbols), and the user chooses the item of interest from that list. Display-based methods are electronically generated and built into the device. Chart-based approaches are typically on a separate sheet that is used for prompting and often not needed after training. Both of these types require only recognition memory, that is, the ability to recognize the correct item when a list is provided. Memory-based presentation of the selection set does not include a prompting list and relies on recall memory. This is a more difficult task than recognition


1 2 3 4 5 6 7 8 9 0
A B C D F G H I J
K L M N O P Q R S
T U V W X Y Z
SPACE YES NO
(a)
(b)
(c)
(d)

Figure 3. Direct selection communication devices. (a) Pointing boards with letters or other symbols, (b) hand-held keyboard, notebook-sized keyboard, and (d) palm-sized keyboards for high portability when good fine motor control exists.

for individuals with cognitive limitations due to developmental disabilities, stroke, brain injury, or similar conditions. Even in the absence of such disabilities, only $\sim$ 200–300 vocabulary items and corresponding recall codes can be easily remembered and used. Thus, the use of display-based selection sets is desirable. However, display-based selection sets are often static, that is, there is one set of elements from which the user can choose. While this set of elements can be combined to access a larger set of vocabulary through codes or abbreviations, this converts a display-based selection set to a memory-based one.

One way of avoiding the problem of limited vocabulary choices associated with memory-based systems is the use of dynamic communication displays. An AAC device that has a dynamic display is shown in Fig. 2d. Dynamic displays change the displayed selection set when a new level is selected. Since the user's selection set is always updated on the display panel, it can be altered easily depending on previous choices. For example, a general selection set may consist of categories such as work, home, food, clothing, greetings, or similar classifications. If one of these is chosen, either by touching the display surface directly, using a mouse-driven cursor or by switch access, then a new selection set is displayed. This retains the display-based selection set while dramatically increasing the functional size of the selection set. For example, a variety of food-related items and activities (eat, drink, ice cream, pasta, etc.) would follow the choice of "foods" from the general selection set. The symbols on the display can be varied, and this changes the targets for the user. Since each new selection set is displayed, the user can depend on recall, not recognition memory.

A significantly different approach to the presentation of vocabulary choices to the Individual who uses AAC is implemented in Visual Scene Displays (VSDs) (10). Visual scene displays capture events in person's life on a screen. Hotspots are then liked to text messages that describe events, invite discussion or serve as prompts for conversational use. These VSDs offer a greater degree of contextual information to the Individual who uses AAC and communication partner information in order to support interaction. They enable communication partners to participate more actively in an interactive conversation and may represent either a generic context (e.g., a person's home) or a very specific personalized event (e.g., a birthday party). The screen contains pictures of the activity, place or event. A caregiver typically enters the vocabulary associated with the screen elements, although it could be the user who enters the text. A comparison of characteristics of a traditional grid AAC display containing vocabulary elements and a VSD is shown in Table 1. The biggest advantages of the VSD are the type of material that can be included in the display, the degree of personalization, the management of the display, and the methods available for concept retrieval. The functional uses of a traditional display focus on communication of needs, wants, and information exchange. The VSDs provide greater conversational support by allowing an interaction to be a shared activity and a potential learning environment for the user. While also including communication needs, wants, and information exchange, VSDs add a real element of social closeness. The VSDs can be applied to stimulate conversation between interactants, support play, shared experiences, and telling of stories. They also facilitate active participation of interactants during shared activities and can provide instruction to both the user and the communication partner through specific information or prompts. Specific populations that can be served by VSDs include those with cognitive limitations (e.g., Down's syndrome) and those with language limitations (e.g., aphasia, autism).

Another approach that allows dependence on recognition memory though a display-based approach is word prediction or word completion. These approaches can be used with any selection technique (11). In this case, there is a window on the screen that displays the most likely words based on the letters entered. To complete the word, the user selects the code (e.g., a number listed next to the word). If the desired word is not listed, the user continues to enter letters and the displayed words change as more letters are entered. For example, if the word "what" is entered, a word completion device may list "time", "is" "are" "can", etc., as choices to follow "What". The display is a display-based selection set that is dynamic based on user input. There are two approaches to the storage of items to be presented in a predictive system. Fixed dictionaries use a preselected stored word vocabulary that never changes. We can have different vocabularies for different contexts such as school, work or recreation. Other systems offer a menu of words using an adaptive vocabulary that is altered based on the user's own selections and is constantly updated. Character prediction phrase prediction are similar approaches using non-orthographic symbols or phrases instead of letters or words.

Selection Method

Two basic selection methods, direct selection or indirect selection are used in AAC systems (6). Direct selection is the fastest and easiest selection method to understand and use because each possible choice in the selection set is

Table 1. Comparison of Standard Grid AAC Display and Visual Scene Displays

Variable	Typical AAC Grid	VSD
Type of representation	Symbols, TO, line drawings	Digital photos, line drawings
Personalization	Limited	High
Amount of context	Low	High
Layout	Grid	Full or partial screen, grid
Display management	Menu, pages	Menu pages, navigation Bars
Concept retrieval	Select gird space, pop ups	Hotspots, speech key, select grid space

available at all times and the user merely chooses the one that he or she wants. Several examples of direct selection AAC devices are shown in Figure 2. Indirect selection is used to provide access for individuals who lack the motor skills necessary to use select directly and involves one or more intermediate steps between the user's action and the entry of the choice into the device. A variety of indirect selection AAC devices are shown in Figure 4. There are three types of indirect selection are scanning, directed scanning and coded access. All scanning-approaches rely on the basic principle of presenting the selection set choices to the user sequentially and having the user indicate when his or her choice is presented. Typically, the indication is by the activation of a switch by a single movement of any body part. A hybrid method called directed scanning allows the user to first activate the control interface (typically a joystick or other array of switches) to select a direction for cursor movement (vertically or horizontally) and then to stop the cursor movement with a switch at the desired element. Several types of scanning are used. In step scanning, the scan advances one step each time the switch is pressed. With autoscanning, the scan steps automatically until the switch is hit. An inverse scan reverses the process and advances continuously as long as the switch is depressed and stops when the switch is released. Each of these has advantages for different types of users.

Scanning is inherently slow, and there have been a number of approaches that increase the rate of selection (6). Just by placing the most frequently used characters near the beginning of the scan, the rate can be increased by as much as 30%. Many of the rate enhancement methods involve selecting groups of characters first to narrow the choices, then selecting the desired item from the selected group. Several types of adaptations are employed with scanning to increase the rate of selection. With group item scanning, items are clustered in groups. The first scan is through the groups and a switch press selects one. Then the items in the group are scanned sequentially. A row column scan is a group-item scan with the elements arranged in a matrix of rows and columns. The rows are scanned top to bottom, and then the columns are scanned left to right. A halving scan presents each half of the display until a switch is hit, then scans within that half.



Figure 4. Scanning communication systems. (a) Simple pointing boards in which the listener points to each element and waits for a response, (b) circular scanning with up to 32 elements, (c) electronic row-column matrix scanning with picture display and voice output, (d) alternative electronic row-column matrix scanning with voice output. Parts (c) and (d) can have a variety of symbols (letters, words, pictures, line drawings) in the scanned elements.

In coded access, the individual uses a single switch or an array of switches to generate a unique sequence of movements to select a code that corresponds to each item in the selection set. The most common form of coded access used in AAC devices is the Morse code. Here the selection set is the alphabet, and an intermediate step [e.g., holding longer (dash) or shorter (dot)] is necessary in order to make a selection. Two-switch Morse code is also used in which one switch sends dots and the other sends dashes. Morse code was developed to be efficient and fast, and these features are exploited in its AAC applications. However, Morse code is a memory-based technique in general (although some display-based approaches have been used) and this can result in additional constraints on the user. The memory-based nature also makes it useful for individuals who have visual limitations that prevent them from using a display-based approach.

Output Formats

Most AAC devices and some assistive technology applications rely on voice output. There are two types of speech output, differing in the manner by which the speech is electronically produced. These are (1) digital recording, and (2) speech synthesis. Digitized Speech is similar to a tape recorder. The speech is electronically compressed with up to a few minutes of speech (2–3 s/utterance) stored at any one time. A care provider can record any voice (male, female, child) or sound (e.g., laughter) and the user can play it back using either direct or indirect selection. One drawback is that all vocabulary to be spoken must be recorded and the user cannot produce a new or novel utterence.

Voice synthesis is electronic generation of speech using a mathematical model of the vocal tract realized in software or hardware. The two types of sounds in speech are voiced and unvoiced (a hissing sound similar to unvoiced sounds such as s or f). Both of these types of speech signal are used as sound sources for the vocal tract model. The parameters of the model are varied to produce speech in a manner similar to the variation of the tongue, teeth, lips, and throat during human speech. The parameters are either derived from actual speech samples (e.g., linear predictive coding-base synthesis) or from a set of parameters representing each phoneme (~64 phonemes are required for intelligible speech synthesis) or morpheme (combinations of phonemes-over 1500 are required for intelligible synthesis). Text can also be converted directly to speech by using a set of rules. The conversion of text characters into the parameters required by the vocal tract model in the speech synthesizer is accomplished by text-to-speech software. The synthesizer combines the phonemes or morphemes into words. There are $\sim$400 rules necessary for letter-to-phoneme conversion. Some systems also use morphonemic rules. About 8000 morphemes can generate 95% of all words. The major advantage of speech synthesis is that there is unlimited vocabulary as long as it can be represented in text strings.

Internet Access

Another common output for AAC devices is Internet access using the AAC device. While some AAC devices include basic computer functions (word processing, spreadsheet, presentation software, web browser), many do not. In the latter case, the AAC device is connected to a computer wither via hard wire or infrared link. In either case, any stored vocabulary or special access methods used with the AAC device are then available for on-line use. Further, many commercial AAC systems utilize portable computers with AAC software, and they can also function as Internet workstations. One of the most important communication functions accomplished via the internet is e-mail. Aside from the benefits that we all receive from e-mail (global access, low cost) people who have disabilities also have the benefit of composition independently and at a slower speed than face-to-face communication since the recipient reads it at a later time. The major advantage is that the person's disability is not immediately visible, and individuals who use AACs report that they enjoy establishing relationships with people who experience them first as a person and then learn of their disability (12). Information retrieval, socialization (e.g., chat rooms), development of literacy through large amounts of reading and writing, booking of airline or theater reservations, and general conduct of business from home without traveling to a place of business are other advantages of Internet access for individuals who use AACs.

AAC ASSESSMENT

Effective use of an augmentative communication device requires skills in several domains. These include gross and fine motor control required to make selections; visual, auditory, and tactile sensory capabilities; and cognitive and language abilities (e.g., the use of some symbolic representation).

Needs Assessment

The first step in an assessment aimed at the selection of an AAC system is the documentation of the individual's communication needs. The second step is to determine how many of these can be met through the individual's current communication methods. Finally, an AAC system is selected that will reduce as many of the unmet communication needs as possible through a systematic intervention.

The Participation Model (4) is a framework that focuses on identification of opportunity and access barriers to AAC use. Opportunity barriers are classified as policy, practice, attitude, knowledge, or skill (of support personnel). Access barriers include natural supports, environmental considerations, and user competencies. These are evaluated in terms of their potential to increase natural abilities (speech, gestures, vocalizations), improvement of communication through environmental adaptations or strategies, and profiles of the individual's abilities and skills. These are all measured and related to AAC use. Interventions are developed to address barriers resulting from opportunity, natural abilities, environment, or lack of an AAC system. Once identified, an intervention plan is derived for each identified barrier. For example, a policy may need to be changed, a teacher's attitude toward AAC altered, or the staff of a facility needs to be trained to develop their skills and knowledge of AAC. Natural ability interventions may involve speech-language pathology services to increase loudness or intelligibility of speech. Environmental adaptation interventions may result in a change in the layout of a classroom to place the individuals who use AAC in the center of the class rather than the periphery. The AAC system interventions determine the skills the user has and identify a system or systems that will be of use to that individual.

Physical–Motor Assessment

Physical assessment consists of identifying an anatomic site that can be used to indicate choices from the selection set. The primary sites are the upper limb (L/R), head and/or neck, eyes, leg, foot, or arm. These may be used directly or with a hand pointer to increase precision, or a mouth or head stick. Adaptations such as a keyguard or a hand splint may also be used. A variety of methods for using head control are shown in Fig. 5.

Sensory Assessment

Visual, auditory, and tactile abilities must also be assessed. Visual skills include acuity, tracking, and visual scanning. Auditory thresholds and speech perception should also be evaluated. Tactile response may be limiting if it is too sensitive or not sensitive enough. In the former case, the



Figure 5. The head may be used as a control site by attaching a light beam (a): a reflective dot used with an infrared transmitter/receiver on the device (b), of a mechanical head pinter (c). part a (From Electronic Devices for Rehabilitation, New York: John Wiley & Sons, 1984, with permission, part c from Zygo Industries, Inc.)

person may be tactually defensive and not be able to use a switch or other interface that has a rough surface. If the person is insensitive, then they may not be able to sense when a switch or key is activated.

Cognitive and Language Assessment

A variety of symbols are used in AAC selection sets. These include real objects (including miniatures of object such as doll house furniture), colored drawings, line drawings, words, or letters. The symbol type for any given individual is selected through a formal assessment process (4). Language assessment related to AAC use is very difficult due to lack of expressive ability (i.e., the very reason for the need for AAC). Two approaches are employed. The first is single word vocabulary testing that measures vocabulary comprehension in relation to the individual's level of functioning. This assessment includes relationship concepts that have no real-world referent as well as traditional language sampling. The second type of language evaluation is a literacy assessment. This can include a reading evaluation in which both word recognition and reading comprehension are used (4). Several types of spelling tests are employed. Recognition spelling requires the user to pick the correct choice from a list of options. This requires only recognition memory and is easily accommodated into AAC devices. The second approach relies on first letter of word spelling and is related to AAC word completion techniques. Spontaneous spelling is the typical letter-by-letter text generation we all learn in school. This is the most flexible and powerful spelling skill since it results in the generation of vocabulary limited only by the persons knowledge, not by the features of the device.

A cognitive assessment may also be conducted to determine how the individual understands the world and how communication can be best facilitated within this understanding. No formal tests predict the ability of an individual to meet the cognitive requirements of various AAC techniques (4). Many cognitive tests require expressive language via AAC itself in order to accurately assess cognitive ability. For this reason, the individual's cognitive ability must be estimated to assess the probability of an AAC device being successful. There are several basic cognitive skills relevant to the use of an AAC system. These include: alertness, attention span, cause and effect, vigilance (the ability to visually and auditorially attend to a task and process information), expression of preferences, making choices, symbolic representation, and understanding of object and/or pictorial permanence.

Educational Assessment

The SETT model was developed to aid in the effective selection and use of assistive technologies, including AAC, in education (13). It consists of four elements: student, environment, task, tools. Each element Includes a set of questions that focus on the interrelationship between the elements to enhance classroom use of AAC. Student-related questions include What does the student need to do?, What are the student's special needs?, What are the student's current abilities? Environment questions comprise: What materials and devices are available?, What is the physical layout? Are there special issues?, What is the instructional arrangement?, Are changes planned?, What supports are available to the student?, What resources are available to those supporting the student? Task questions focus on: What activities take place?, What activities support the student's curriculum?, What are critical elements of activities?, How can activities be modified to meet student needs?, How can technology support the student's participation in the activities? Finally, tools questions include: What strategies might be used to increase student performance?, What no-tech, low tech, and high tech options should be considered? How might tools be tried with student in environments where they will be used? The SETT framework promotes team building. Consensus is built by using clearly understood language, requiring broad-based participation, and valuing input from all perspectives. Exploring environments and tasks strengthens the links between assessment and intervention. It is also necessary to develop a system of tools to enhance the student's abilities to address the tasks and build competency. The SETT framework can address and overcome many of the obstacles that lead to marginal student inclusion, general dissatisfaction, and device abandonment. It can also increase opportunities for success that come with assistive technology systems that are well matched to the student's needs and abilities.

TRAINING INDIVIDUALS WHO USE AAC FOR COMMUNICATIVE COMPETENCE

There are some disturbing statistics regarding AAC use. For example, Magilei and Sandoval (14) reported that 87% of parents reported that their child had access to assistive technology, but they had no training or technology assistance. Also, 33% of all assistive devices are abandoned, largely due to failure to meet the user's needs in community settings. Thus, it is essential that individuals who use AAC devices receive adequate training.

There are four basic types of AAC competence that must be developed in order for the user to be an effective communicator (15). Operational competence refers to understanding of the mechanics of making a selection, turning the device on or off, battery charging, and so on. This involves both the user and the caregiver. Linguistic competence is the understanding of the language elements (symbols, rules of language) that are included in the system. Social competence is the effective use of the AAC system in a functional manner to convey a message to a listener in a given context. Strategic competence deals with the strategies necessary to determine when to use one AAC mode rather than another and how to use it most effectively with a given partner. Communication partners must also be also trained. For children, the training of parents to recognize communication attempts and to understand the operational, linguistic, strategic, and social competencies is also important.

Both physical and communication skills are required for the use of an augmentative communication device. Communicative competence can be developed once sufficient skills are available in both of these domains to allow basic communication. Physical skills are required to make choices from the selection, and these skills may need to be developed in order for the individual to use the device effectively.

For operational competence development, training may be through tutorials built into a device, supplied separately by a manufacturer on a CD/DVD or made available through a company website. A provider (speech-language pathologist, teacher, rehabilitation engineer) may also provide this training face-to-face. In order for the user to develop linguistic competence the AAC device user must understand the symbol system and rules of organization. The individual who uses AAC often must be competent in two languages: the spoken language of the community and the language of their AAC device (15). Development of linguistic competence may require many hours of practice, often built around a functional task.

Many users of AAC devices have little or no experience in social discourse, and training in social competence is required. Rules of conversation are altered for AAC use, and the perception of the individual by their communication partners is also different than conversations between two speakers. In order to be socially competent, the user must have knowledge, judgment, and skills in both sociolinguistic (e.g., turn taking, initiating a conversation, conversational repair) and sociorelational areas (e.g., understanding of interaction between individuals) (15). These skills are best taught in the contexts in which they are to be used, that is, training should occur in the community at school, work, shopping mall, rather than in a clinic setting. Training should be motivational, educational, and functional through the use of age and environmentally appropriate activities, such as playing a board game, which allows participation and multiple communication turns around a topic. The incorporation of creativity and fun activities into therapy sessions can lead to carryover of desired skills–goals and limit the amount of drill-like exercises.

Every user of an AAC device develops strategies that make use more effective. Strategic competence describes the degree to which the user of the device is able to develop adaptive methods to make the most of the device. For example, a child's speech may be better understood at home than at school. He will rely on the electronic AAC device more in school, but they will also develop strategies to make maximum use of both systems. One approach to strategic competence training is to simulate a situation, model the types of interaction likely to occur, and have the user "practice" the strategies and skills necessary to make it a success, followed by an actual situation in which the user goes into the community. If the provider accompanies the user they can then prompt, encourage, and help to clarify when necessary. This combination of clinic-based practice and community-based skill development is often very effective.

A seven-step process for developing communication competence in individuals who use AACs has been developed (16). These seven steps are (1) specify the goal, do baseline observations, (2) select vocabulary, (3) teach the facilitators how to support the individual who uses AAC in developing the target skill, (4) teach the skill to the individual who uses AAC, (5) check for generalization, (6) evaluate outcomes, and (7) complete maintenance checks.

VOCABULARY SELECTION

There are a variety of types of vocabulary that serve various needs. For conversational messages, greetings, small talk, information sharing, wrap-ups, farewells, and conversational repair are important types of vocabulary to have available. Small talk is used for initiating and maintaining conversations and is transition between the greeting and information sharing. It builds social closeness where content is less important than connection to another person. Sometimes scripts (complete dialogues or stories that are stored and replayed bit by bit) are stored in the device so they can be used over and over. For an adult, a story might be about a film that the user saw and enjoyed and wants to talk about. For a child, the story could be about a trip to the circus. Generic small talk is more general and can be used in different conversations with different people. The needs of the AAC vocabulary vary by context, communication mode, and user characteristics.

For preliterate users, a coverage vocabulary is needed to communicate essential messages including greetings, requests for objects and information, comments (e.g., "that's cool", "wow", "that is terrible"), emotional states (e.g., happy, sad, angry), and needs (e.g., "I feel sick", help me"). In order to increase linguistic competence, developmental vocabulary is also required (4). This vocabulary includes words and concepts that are not yet understood. The vocabulary is not selected for functional purposes, but rather to encourage language and vocabulary growth. In some cases, the individual may learn or memorize the location of utterances and become more functionally communicative than their cognitive or linguistic skills would suggest.

For literate users, there are a variety of vocabulary resources (4). Core vocabulary is used by a variety of individuals and occurs frequently. There are word lists based on successful patterns as well as those based on a specific user. In one study, Individuals who use AACs who were operationally and socially competent used a list of 500 words that covered 80% of total utterances for all users (4). Fringe vocabulary refers to words and messages that are unique to the individual. These include names of people, places, activities, and preferred expressions. Fringe vocabulary personalizes the AAC system and compliments the core vocabulary list. Items for this list are identified by informants, usually the user, family, and friends. Fringe vocabulary is selected based on initial items of high interest to the user that have the potential for frequent use. This vocabulary provides ease of production by the user and interpretation by the partner. One method of selecting vocabulary is to use environmental inventories. These inventories attempt to document the individual's experiences by noting precipitating events and subsequent consequences in communicative interactions. A pool of vocabulary items is reduced to a list of the most critical words that the user can manage. Another approach is communication diaries and checklists in which informants record the words and phrases needed by an Individual who uses AAC.

Privacy Issues in AAC

When collecting data on vocabulary used by an individual there is a real risk of invading their privacy, since stored information may include intimate utterances or vocabulary, personal data, or confidential information (16). The use of automatic monitoring devices that capture all of what the user generates by collecting AAC device output in an electronic form during use to assess compliance with a training plan is also a potential violation of privacy. On the other hand, the collection of data reflecting the experience of the individual user of AAC can provide important information related to the individual and more broadly to AAC needs. The user should be able to make the choice as to whether their data is collected or not, and should be able to turn off a data logger when a private conversation is desired.

BIBLIOGRAPHY

1. Blackstone S. Populations and practices in AAC. Augment Commun News 1990;3(4): 1–3.
2. Cook AM. Communication devices. In: Webster JG, editor. Encyclopedia of Medical Devices and Instrumentation. New York: John Wiley & Sons; 1988.
3. Light J. Interaction involving individuals using augmentative and alternative communication systems: State of the art and future directions. Augment Altern. Commun 1988; 4(2): 66–82.
4. Beukelman DR, Mirenda P. Augmentative and alternative communication, management of severe communication disorders in children and adults. 2nd ed. Baltimore MD: Paul H. Brooks; 1998.
5. Foulds RA. Communication rates for non-speech expression as a function of manual tasks and linguistic constraints. Proc Int Conf Rehab Eng 1980;83–87.
6. Cook AM, Husswy SM. Assistive Tecnologies: Principles and Practice. St. Louis: Mosby; 2002.
7. Brodin J. Facsimile transmission for graphic symbol users. Euro Rehab 1992;2:87–92.
8. Electronic Devices for Rehabilitation. New York: John Wiley & Sons; 1984.
9. Vanderheiden GC, Lloyd LL. Communication systems and their components. In: Blackstone S, Bruskin D, editors. Augmentative communication: an introduction. Rockville, MD: American Speech-Language and Hearing Association; 1986.
10. Blackstone S. Visual Scene Displays. Augment Commun News 2004;16(2):1–5.
11. Swiffin AL, Arnott JL, Pickering AA, Newell AF. Adaptive and predictive techniques in a communication prosthesis. Augment Altern Commun 1987;3(4):181–191.
12. Blackstone S. The Internet: what's the big deal? Augment Commun News 1996; 9(4):1–5.
13. Zabala J. The SETT Framework: Critical Areas to Consider When Making Informed Assistive Technology Decisions. Proc Closing Gap Conf 1995.
14. Magilei A, Sandoval L. Creative Therapy Activities Using AAC for Adolescents and Adults. Proc CSUN Conf 2003.
15. Light J. Toward a definition of communicative competence for individuals using augmentative and alternative communication systems. Augment Altern Commun 1989;5(2):137–144.
16. Light JC, Binger C. Building communicative competence with individuals who use augmentative and alternative communication. Baltimore, MD: Paul H. Brookes Publishing; 1998.
17. Wiliams M. Privacy and AAC. Alt Speaking 2000;5(2):1–2.

See also COMMUNICATIVE DISORDERS, COMPUTER APPLICATIONS FOR; LARYNGEAL PROSTHETIC DEVICES.

COMMUNICATION DISORDERS, COMPUTER APPLICATIONS FOR

CYNTHIA J. CRESS
JORDAN R. GREEN
University of Nebraska-Lincoln
Lincoln, Nebraska

INTRODUCTION

A variety of relative inexpensive, portable, and easy-to-use computer devices are now available to educators, researchers, clinicians, clients, and other independent users. This article includes discussion of software and hardware applications for reprogrammable computer devices as well as discussion of devices with fixed programs that evolved from programmable computer technology. A communication disorder is defined as an impairment in the ability to (1) receive and/or process a message or symbol system; (2) represent concepts, messages or symbol systems; and/or (3) transmit and use messages or symbol systems (1,2). This impairment is observed in disorders of speech (use of the oromotor system to produce the movements and sounds of speech), language (comprehension and/or use of spoken, written, or other symbol systems), and hearing (detection, perception and processing of auditory system information, and associated language, speech, or interpersonal factors).

Types of communication disorders may affect specific areas of speech, language, or hearing, as well as broader aspects of communication and social interaction. Persons may have multiple disorders within these areas, as well as closely related disabilities such as swallowing impairments, physical impairments, cognitive impairments, and/or sensory impairments. Disorders may be congenital (present from birth) or acquired (through illness, injury, or late-onset disorders). Some disorders that are presumed to be associated with factors present at birth may not be demonstrated until later childhood. Children may experience speech and/or language delays in early childhood that are resolved with experience and not diagnosed as a disability. Some communication disorders are considered organic (associated with a physical or neurological cause), while other disorders may be functional (attributed to experiential or unknown causes). Communication disorders that are associated with systemic and/or neurological symptoms may continue to affect communication skills throughout the lifespan, although many persons develop compensatory skills to effectively produce, process, and comprehend spoken and written information.

Speech impairments tend to be grouped into one of three categories, depending on the aspects of speech most affected: disorders of articulation (difficulty producing speech sounds), fluency (unusual interruption in speaking rhythm, rate and/or repetition), or voice (difficulty producing appropriate loudness, pitch, quality or nasality) (3). Specific speech disorders that can affect multiple aspects of speech in children and/or adults include the following:

Apraxia: Neuromuscular deficits in planning and programming speech movements; if seen in children, usually called Childhood Apraxia of Speech.

Cleft Palate–Lip: Incomplete fusion of oral structures prenatally that may result in articulation and/or nasality problems.

Dysarthria: Speech problems that are caused by abnormal function of the muscles or nerves that control articulation, phonation, resonance, and/or respiration. Dysarthria is often associated with weakness or imprecision of movements; with severe dysarthria, as in some persons with cerebral palsy, the person may be considered "nonspeaking" and rely primarily on alternative forms of communication to speech *(Augmentative and Alternative Communication, or AAC).*

Laryngeal Pathology: Changes in voice quality due to injury, nodules, or tumors; a removal of the larynx (or laryngectomy) requires alternative forms of voicing and/or communication.

Language disorders are commonly distinguished as either developmental (congenital), or acquired. Three general categories of acquired language disorders in adults and older children include the following (3):

Aphasia: Impairment in understanding and/or producing language after language is developed, resulting from brain damage such as due to a stroke.

Dementia: General loss in mental functions, including language, due to pathological deterioration of the brain; this includes Alzheimer's disease.

Brain Injury: Acquired injury to the brain from trauma (Traumatic Brain Injury) or illness (e.g., encephalitis, meningitis) that results in a variety of communication, language, and/or cognitive processing disorders (e.g., memory, attention).

Developmental language disorders are presumed to result from conditions present at birth, and are usually manifested in early childhood. Common developmental disorders that affect language and may affect other cognitive or social processes include the following (3):

Specific Language Impairment: Significant deficits in language comprehension and use that are not attributable to hearing, cognitive, or motor disabilities.

Learning Disability: Difficulties in acquisition and use of listening, speaking, reading, writing, reasoning, and/or mathematical skills.

Dyslexia: Specific reading disorder with difficulties representing and analyzing sounds and print representations of words.

Central Auditory Processing Disorder: Difficulty identifying interpreting or organizing auditory information with normal hearing acuity skills.

Mental Retardation: Impaired cognitive function that affects a variety of skills including communication, self-help skills, and independence.

Autism Spectrum Disorders: Impairments in social interaction, communication, and restricted interests/routines that affect skills at relating appropriately to people, events and objects.

Categories of hearing impairment relate to the types and severity of hearing functions affected (4). Dysfunction of the outer or middle portions of the ear is considered conductive hearing loss, and dysfunction of the cochlea or auditory nerve is called sensorineural hearing loss. Hearing loss from either cause can be slight, mild, moderate, severe, or profound, depending on the sensitivity of the person's hearing in decibels. Persons with mild-to-severe hearing impairments in their better ear are considered hard of hearing, and often benefit from hearing aids to help amplify spoken language. Persons with profound hearing loss in both ears are usually called deaf, and may have speech or language delays secondary to the hearing impairment. Some deaf persons may communicate primarily through signed languages (such as American Sign Language) and learn English as a second language through visual and/or residual auditory input. Some persons with severe to profound hearing loss may elect to have a cochlear implant, a surgically implanted electromagnetic device to stimulate sensory input to the cochlea.

This article is organized according to the general type of computer application, then by specific applications to disorders of speech, language, and hearing. Types of computer applications in communication disorders include clinic administration and management, analysis of normal function, assessment, intervention, and assistive devices. Tables in each section present potential benefits and limitations of computer applications for each type of application discussed. These benefit and limitation tables are intended to briefly highlight some of the issues involved in computer applications and are not organized thematically or listed in any hierarchical order of significance. For consistency across different sections, the general term *client* has been used to refer to the user of the computer applications, since many programs developed for one population (such as children) can also be used with other populations in limited circumstances.

Computer applications listed are intended to overlap somewhat between different sections. For example, many of the techniques developed for analysis of normal function are also used to assess atypical function across all areas of communication disorders. Also, similar techniques have been developed in computer-aided assessment of some speech and hearing functions. As far as possible, programs and devices are described as types of applications rather than specific programs, which are updated and revised too frequently be considered in a reference chapter. Specific examples of software and hardware applications can be derived from the references and websites listed.

ADMINISTRATION–INFORMATION PROCESSING

Overview

Computer software designed for administration may apply to other functions within communication disorders; for example, word processing programs are potential tools for language intervention, and statistical programs may be linked to other analysis functions in research. This section will concentrate on devices and programs that facilitate, but do not directly accompany clinical, teaching, or research processes.

Clinical Management Applications

Programs are available to collect, organize, store, and report clinical information. Examples of functions addressed by available management software include the following (5–7): (1) maintaining mailing and billing logs, (2) collecting client case history, (3) maintaining correspondence and form letters, (4) graphing and organizing client performance data, (5) retrieving or compiling cumulative information, (6) analyzing cost effectiveness or distribution of clinic activities, (7) coordinating inventory control or budget management, (8) maintaining attendance or scheduling for activities, (9) creating electronic spreadsheets, (10) managing a calendar or clinical team interaction, (11) generating individualized evaluation plans (IEPs), and (12) writing and editing reports.

Computer-based applications are also used to create or adapt clinical materials for speech-language pathology (5). Many of these applications use standard multimedia tools such as digital resource libraries, authoring programs, and integrated drawing, video and/or web resources (8). For example, clinicians might create customized articulation or vocabulary exercises for their clients to practice. Clients might interact with commercially available story programs and interface to individualized prompts for additional narrative retelling or speech tasks. Adults and children might create self-prompting materials or applications to remind them of sequences or strategies for difficult tasks (9). Persons with literacy difficulties might create visual and/or auditory supplements for reading and writing materials to provide multisensory information.

Teaching Application

Programs assisting educators in the field of communication disorders supplement textbook materials, provide shared electronic information files, or simulate aspects of communication disorders for demonstration and practice. In a classroom, computers can be used to visually demonstrate lecture points by producing speech waveforms, demonstrating language analysis, or manipulating audio signals during a lecture. Many programs that simulate or demonstrate testing procedures or communication problems can be utilized in the classroom or for individual student practice. Students may individually respond to group tasks during lectures, allowing for personalized feedback on concept acquisition (10). University networking systems allow for web-based student input and discussion, creation and posting of assignments, feedback and dialog with instructors, and regular updating of course materials and progress (11–13). These networking systems have created opportunities for interactive learning through distance education courses and programs in communication disorders (14,15)

Research Applications

Research-based software can collect or manage information through electronic databases, statistical analysis, data manipulation or integration, and grant or report writing assistance. Large bibliographic databases such as Medline or ERIC search for references for a requested topic, title, or description. The Child Language Data Exchange System (CHILDES) collects and maintains electronic transcripts of typical and disordered language samples available for open access and analysis by language researchers (16). Community or professional listservs and websites can share software, information, messages, or reports, usually for access to all interested persons.

Also, computer networks can link researchers as well as clinicians or clients to other computer users, information centers, or databases. Improved computer conferencing technologies allow real-time shared work environments at a distance, including joint editing of documents, spreadsheets, or data analysis. Web-based video conferencing technologies allow real-time interactions among researchers at multiple locations.

Summary for Administration–Information Management Functions

Potential Benefits for Computer Applications

Allows easy storage, recall, and modification of information.

Provides standard format for reports.

Facilitates documentation of results for report or grant writing.

Sorts information across categories or levels.

Can coordinate or code information for multiple variables of interest.

Provides clean copy of output.

Links computer users in real time or through listservs.

Allows shared workspaces and interactions among persons at multiple locations.

Enables quick access to large bases of information.

Allows shared research databases and remote control of computer functions.

Allows students to practice analysis procedures independently.

Computer-based coding requires researchers to convert subjective decisions into rules.

Potential Limitations of Computer Applications

May require more total time on clerical tasks instead of passing routine functions to clerical staff.

Large data systems have more to lose if the system “crashes”.

Potential for data corruption or transmission problems, particularly during periods of high web traffic or network overload.

Information may be entered into computer by users with little clinical knowledge.

Limited monitoring and/or maintenance of many web-based listservs or websites.

Large databases may be difficult to manage and access.

Standard format may discourage originality in report writing.

Computer organization may promote biased or poorly designed research.

Clinicians may design activities to utilize new technologies rather than primarily to meet a client's communication goals.

Students may need more direct interaction or coaching for some types of activities.

Potential for completion of distance education class assignments that do not reflect independent student work.

ANALYSIS OF NORMAL FUNCTION

Overview

Many advances in the assessment and intervention of communication disorders have resulted from extensions of the study of normal speech, hearing, and language functions. Computer technology has expanded the scope of acoustic, aerodynamic, and physiological studies of typical speech. Computer technology has also expanded the scope, accuracy, and speed of analysis of some aspects of language and hearing performance. Many of the applications discussed for analysis of normal function are also used to detect atypical functions, and may overlap with information in the Assessment section.

Speech Analysis Applications

Generate Stimuli. In psychoacoustic studies, digitized speech signals can be created to experimentally manipulate the acoustic features of a stimulus (17). Programs can also randomize the presentation order of acoustic stimuli manipulations, or synchronize stimuli with other experimental. Digitized signals are also converted to analog signals for synthesizing non-naturally occurring signals, or controlling peripheral devices such as pure tone or waveform generators. Adaptive techniques have been devised to randomly present ordered stimuli, organize intervals between events, and modify stimulus levels according to previous values and subject responses. Such programs can respond differentially to indications of subject fatigue or performance variation.

Record Data. Multichannel digital recorders are used to simultaneously capture multiple analog signals from a speaker including acoustic, airflow, air pressure, lung volume, muscle activity, and oral force and movement. The number of channels that can be recorded is only limited by the recorder and available storage memory. Specialized analog transducers and amplifiers convert each signal type into a voltage that can be digitized. These signals provide an objective means to study the physiologic processes that underlie speech production and to establish normative reference data, which can be used to gauge the degree of impairment in individuals with disordered speech. Most modern speech laboratories rely heavily on analog-to-digital conversion. Digitized signals can be easily accessed for editing, analysis, modification, and integration with other data.

Digital audio recordings of speech sounds are the most widely studied aspects of speech. Commercial sound cards provide a sufficient sampling rate and signal/noise ratio for most analysis applications. Typically, a preamplifier is used to increase signal gain prior to digitization.

Computer applications have also been essential for recording speech and swallowing movements. Most knowledge of speech movements has been derived from strain gauge devices, that were mounted directly to the upper lip, lower lip, and jaw [e.g., (18,19)]. Optically based motion capture (OBMC) systems register facial motion in three dimensions (3D) during speech and are rapidly replacing strain gauge techniques. These systems use computer-based visual pattern recognition to extract the motions of passively illuminated markers that are attached to the face. The OBMC systems offer a number of significant advantages over other methods for registering speech motion. Specifically, subjects are not required to maintain a specific posture while speaking nor are they encumbered by wires or metal beams extending from the mouth. At present, OBMC systems provide the only suitable method for studying orofacial movements in young children (20). One significant limitation of OBMC is, however, that they can only record the motions of superficial facial structures.

Most of the information regarding the performance of the articulators inside the mouth during speech and swallowing (i.e., tongue, velum, and the pharynx) has been obtained using four technologies: cineradiography, videofluroscopy, X-ray microbeam, and Electromagnetic Midsagittal Articulography (EMA). Cineradiography is a filmed X-ray and is typically no longer performed because of concerns regarding radiation exposure. Videofluroscopy is an X-ray technique that reduces radiation exposure and is usually only performed on individuals undergoing a clinical assessment of swallowing (21,22). X-ray microbeam minimizes X-ray exposure by using predictive algorithms to maintain a focused X-ray beam on pellets attached to moving structures such as the tongue (23). Electromagnetic Midsagittal Articulography tracks the motion of electromagnetic sensors through a calibrated magnetic field surrounding the midsagittal plane of the head (24).

Manipulate Data. Once digitized, the data representing the various aspects of speech performance are displayed and analyzed using custom or commercially available software. Computer programs can extract spatial, temporal, and spectral information from digitized signal input. Signal conditioning techniques are used to filter, rectify, and differentiate digital signals. These manipulations can be performed by dedicated hardware or computer software.

Several manufactures have developed commercial software for capturing speech recordings and for synthesizing speech (25–27). For example, Barlow and colleagues (28,29) have developed commercial software and hardware for recording and analyzing speech airflow, orofacial force, and orofacial reflexes. In contrast, commercial products for analyzing speech movements and muscle activity have not been developed. Presently, programming environments such as MATLAB (30) and Lab View (31) provide researchers who only have a moderate degree of programming experience a means to develop custom analyses to meet their specific needs.

Hearing Analysis Applications

Research in hearing science utilizes many of the same techniques of stimulus generation, recording, manipulation, storage, and control as speech science. For example, computer-generated tones or speech can be used in audiometry to maximize control over stimulus characteristics such as frequency or timing (32,33). Computer models of auditory processes can simulate relative effects or differences in intelligibility in response to systematic changes in the auditory system (34,35). Computer systems can produce randomly ordered sounds that are necessary for some types of auditory physiology and psychoacoustic research, as well as store and index massive databases of data.

Signal-averaging is essential for computer analysis techniques, such as acoustic emittance or auditory evoked response (AER), that require separation of a signal from background responses (36). The AER systems analyze brainstem responses to sound by averaging EEG measurements for repeated sound presentations. Modifications can include nonlinear gating of signal initiation that is not possible with analog signals.

Language Analysis Applications

Analysis of normal linguistic function with computers utilizes descriptive techniques to track developmental progress and maintain databases for language clients, or databasing systems to compare language development patterns observed to those of other populations (37). Descriptive analyses currently available summarize lexical and syntactic functions in normal or disordered language development, such as the Systematic Analysis of Language Transcripts (SALT) (38). Over the past 20 years, SALT analysis has provided standards for language transcript coding and analysis in comparison to normative expectations, including school-based language assessments (39).

The relative speed and standardization of these transcript and analysis systems enables the collection of large and accessible databases of language behavior and variation. One of the largest databases in the study of language development is the Child Language Data Exchange System (CHILDES) (16,40). Continuing development of databases provides accessible digitized audio and/or video transcripts for comparison of performance of children and adults, not only with typical and multicultural development, but Down syndrome, specific language impairment, aphasia, or focal brain injury (37).

Summary for Analysis Applications

Potential Benefits of Computer Analysis

Makes possible complex transformation of a speech signal.

Enables precise timing manipulations for stimulus intervals and randomization.

Allows precise editing, analysis, modification, and recombination of signal or subarrays of signals, without splicing of tapes.

Easier to incorporate probability theory and statistics in analysis process.

Enables selective analysis of separate muscle groups.

Can be used to record speech movements.

Can compare multiple sequences, continuous data points, or multiple plots of data directly with point-by-point analysis.

Can compute online analysis as study is conducted.

Digitally generated speech and/or auditory signals are less distorted and more easily controlled.

Digitally stored data does not degrade as fast as analog.

Signal averaging is necessary for evoked potential study because potentials of interest are small and contaminated by noise.

Possibility for richer and more flexible stimuli.

Analysis techniques can more easily borrow models from other disciplines.

Standardization of transcript collection and coding makes analysis across individuals easier, more reliable.

Computer databases can be collected and shared across research facilities.

Quicker analysis of routine elements of language sample frees more time for other types of analysis.

Language transcripts can be searched for items of interest quickly.

Potential Limitations of Computer Analysis

Limited and nonintelligent algorithms may reduce research questions to analyses of narrow aspects of behavior.

Assumptions for analyzing, storing, or manipulating signals or behaviors are implicit in programs and difficult to retrieve.

Time savings in analysis may be offset by increased transcription or data-entry 